

Project Review: RI/FS

Former Grumman Settling Ponds (a.k.a. Bethpage Community Park) Site No. 1-30-003A- OU3, Town of Oyster Bay, Nassau County.

Background: The site is a 11-acre park that was formerly a wastewater and processed chromium sludge drying area for Grumman Aerospace. The land was donated to the Town of Oyster Bay in 1962 and the waste water lagoons, rag pits and disposal areas were filled in and made into a ballfield and parking area.

Project Phase and Project Review Objective:

Objective is to review findings of the RI and discuss IRMs and overall remedial alternatives.

A. Finalizing the remedial investigation Report onsite and offsite RI.

Soils: Volatile organic (VOC) contamination mainly with TCE and DCE, vinyl chloride, BTEX, Freon, PCBs and inorganic compounds, mainly chromium sludges, cadmium, lead and to a lessextent arsenic.

Groundwater: Perched groundwater is some areas with solvents and some LNAPL in limited areas.

Offsite Groundwater: Extent and co-mingling with the OU2 Plume, Navy responsibility. A large solvent plume more than a mile long is migrating off -site containing

Soil Vapor: Soil vapor investigation is now complete.

B. The IRMs completed to date:


- * The **Huge** soil excavation by the Town of Oyster Bay
- * SVE by Northrop Grumman
- * Groundwater pump and treat by Northrop Grumman.

C. Human Health Risk Assessment: The PRP has elected to submit an HHRA. They want this to guide remedial action objectives.


D. The Preliminary Screening of Alternatives.

**Project Review NGC Operable Unit 3
RI-FS and IRM's
Former Grumman Settling Ponds
a.k.a Bethpage Community Park
May 21, 2009**

**NEW YORK STATE
DEPARTMENT OF**



**ENVIRONMENTAL
CONSERVATION**



- EXPLANATION**
- PROPERTY BOUNDARY OF THE FORMER RUCC POLYMER SITE
 - PROPERTY BOUNDARY OF THE FORMER GRUAMAN AIRCRAFT TIE
 - PROPERTY BOUNDARY OF U.S. NAVY SEC
 - ▨ QUANTIC NORTHROP GRUAMAN SPICED PROPERTY
 - ▨ QUANTIC U.S. NAVY OWNED PROPERTY
 - WELLS
 - A INDUSTRIAL WELL
 - B PUBLIC SUPPLY WELL
 - C OBSERVATION, MONITORING WELL
 - D INVESTIGATION WELL
 - E UNKNOWN USE OF WELL
 - F NORTHROP GRUAMAN OR NAVY PRODUCTION/INDUSTRIAL WELL OR OLD GENERAL WELL
 - G EXISTING VERTICAL PROFILE BORING
 - ABANDONED OR DESTROYED WELL
 - H REVERSE FLOW MONITORING WELL (APPROXIMATE)
 - I INJECTION WELL
-
- SHALLOW WELLS
 - INTERMEDIATE WELLS
 - DEEP WELLS
 - DEEP 2 AND DEEP 3 WELLS
-
- SP10 SOUTH PARANADALE WATER DISTRICT
 - LWD LOSTOWN WATER DISTRICT
 - NYWS NEW YORK WATER SERVICE
 - WMS WESTWAKE WATER DISTRICT
 - TDW TOWN OF DESTROYED WATER DISTRICT
 - MSD MISCELLANEOUS WATER DISTRICT
 - WVF VILLAGE OF FRESHWATER WATER DISTRICT
 - VP VERTICAL PROFILE BORING

- NOTES:**
1. THIS FIGURE DOES NOT INCLUDE ALL ACTIVE MONITORING AND OBSERVATION WELLS INSTALLED SINCE 1992.
 2. THIS FIGURE INCLUDES ALL SHALLOW WELLS IDENTIFIED IN TABLE 1-11 OF THE OUTREACH - 2000 SV REPORT PLUS SELECT ADDITIONAL MONITORING AND OBSERVATION WELLS.
 3. THIS FIGURE INCLUDES LOCATIONS OF PUBLIC SUPPLY WELLS BASED ON INFORMATION REQUESTED BY ARCADIS IN SEPTEMBER 2001 LETTER.
 4. THIS FIGURE INCLUDES LOCATIONS OF VERTICAL PROFILE BORINGS INSTALLED BY THE US NAVY.
 5. DRAIN LOCATIONS OBTAINED FROM USGS TOPOGRAPHIC MAPS (BARSBILLS, NATIVILLE, WESTINGTON, AND FRESHPORT QUADRANGLES), AND INFORMATION PROVIDED BY NORTHROP GRUAMAN.
 6. NORTHROP GRUAMAN PROPERTY BUILDINGS BASED ON DATA PROVIDED IN SEPTEMBER 2000.
 7. LOCATION OF MONITORING WELLS INSTALLED BY OVRMA & ANTILLAS AT PLANT 1 (A, B, C, D TO J, K-L) ARE ESTIMATED FROM O&S SITE PLAN, PROVIDED ON DECEMBER 18, 2002.
 8. THIS FIGURE INCLUDES LOCATIONS OF WELLS ASSOCIATED WITH THE QUANTIC AREA INDUSTRIAL ACTON, PERFORMED BY THE NAVY.



ALL COORDINATES REFERENCED TO NAD83/ARCADIS DATUM 88

DRAFT

NO. INDEX	REVISION	DATE
-----------	----------	------

PROJECT FILE

NORTHROP GRUAMAN CORPORATION
BETHPAGE, NEW YORK

PROJECT TITLE
LOCATION OF NORTHROP GRUAMAN,
U.S. NAVY & RUCC POLYMER SITES
AND LOCATIONS OF WELLS

ARCADIS

To: Bethpage (unbldg)
 Title: 2008
 Number: 017427
 Tel: 631-946-7600 Fax: 631-946-7610
 www.arcadis-us.com

IDL	IDL
-----	-----

PROJECT MANAGER C. SAN GRUAMAN	DEFINITION MANAGER
LWD USER PREFIX	CHECKED BY D. STEIN
DRW/PLN/REV NUMBER 00001	DRAWN BY A. SANJEEV
PROJECT NUMBER NY001348.	DRAWING NUMBER 1



Project Area – December 2004

Key Points

- Northrop Grumman signed an Order on Consent (AOC) to investigate environmental conditions related to the Bethpage Community Park.
- The RI/ FS is currently being implemented, as follows:
 - RI field work has essentially been completed in the Park.
 - Offsite RI work is almost complete south of the Park
 - The Onsite RI Report was submitted and comments sent back.
- The NYS-funded offsite vapor intrusion study was completed.
- Northrop Grumman implemented two IRMs for soil gas and groundwater.
- Grumman has submitted HHRA and list of alternatives



- EXPLANATION**
- NORTHROP GRUMMAN PROPERTY LINE
 - - - FENCE
 - - - LIMITS OF BETHPAGE HIGH SCHOOL MAIN BUILDING
 - ▭ BASK
 - bit BITUMINOUS PAVEMENT
 - VP-1 MONITORING WELL
 - VP-1 VERTICAL PROFILE BORING
 - SP-1 SOIL GAS POINT
 - PEZ-1 PIEZOMETER
 - ABANDONED PEZOMETER
 - ABANDONED MONITORING WELL
 - 7-34 CPT BORING
 - 7-3 CPT/WP BORING
 - I-3-68/SOIL BORING/GEOTECHNICAL BORING
 - NYSDEC NYSD&E SOIL GAS POINT
 - NWSPD NAVAL WEAPONS INDUSTRIAL RESERVE PLANT
 - CPT CONE PENETROMETER
 - MIPE MEMBRANE INTERFACE PROBE
 - OU3 OPERABLE UNIT 3
 - R REMEDIAL INVESTIGATION
 - IRM INTERIM REMEDIAL MEASURE
 - NYSDEC NEW YORK STATE DEPARTMENT OF ENVIRONMENTAL CONSERVATION
 - D&B D'AMICO AND BARTOLUCCI CONSULTING ENGINEERS

- NOTES:**
- MONITORING WELLS AND VP's VP-1 TO VP-20 SURVEYED TO NORTH AMERICAN DATUM (NA83). ALL OTHER LOCATIONS ARE APPROXIMATE BASED ON FIELD MEASUREMENTS.
 - PARK FEATURES SHOWN WERE PRESENT PRIOR TO TOWN OF OYSTER BAY REDEVELOPMENT IN 2005.
 - GRID DOES NOT CORRELATE TO TOWN OF OYSTER BAY 2005 RM PREDESIGN SAMPLING GRID OR TO D&B SAMPLING GRID SHOWN IN APPENDIX B.
 - APPENDIX B PROVIDES LOCATIONS OF SAMPLES COLLECTED BY D&B FOR THE PCB INVESTIGATION/DELINATION PROGRAM AS WELL AS THE OU3 RI.
- 0 100' 200'
SCALE IN FEET

SEAL			
1	12/2008	SUPPLEMENT TO RI REPORT	MR
0	01/2008	REMEDIATION INVESTIGATION REPORT	MR
NO.	ISSUED DATE	REVISION DESCRIPTION	BY/CHK

ARCADIS
OF NEW YORK, INC.

Two Huntington Quadrangle
Suite 1918
Melville, NY 11747
Tel: 631-548-7900 Fax: 631-548-7918
www.arcadis-usa.com

PROJECT TITLE
**NORTHROP GRUMMAN SYSTEMS CORPORATION
OPERABLE UNIT 3
(FORMER GRUMMAN SETTLING PONDS)
BETHPAGE, NEW YORK**

PROJECT MANAGER
C. SAN GIOVANNI

DEPARTMENT MANAGER
M. WOLFERT

SHEET TITLE
**SITE AREA CONE PENETROMETER BORING,
MEMBRANE INTERFACE PROBE BORING, SOIL
BORING, SOIL GAS POINT, VERTICAL PROFILE
BORING, PIEZOMETER, AND WELL LOCATIONS**


LEAD DESIGN PROF.
M. REINDL

CHECKED BY
A. SANCHEZ

TASK/PHASE NUMBER
00007

PROJECT NUMBER
NY001464.0807

DRAWING NUMBER
3-1



LEGEND:

- HISTORICAL FEATURES
- HISTORICAL FENCE LINE
- PROPERTY LINE
- FENCE
- TEMPORARY FENCE
- + PREVIOUSLY-INSTALLED SOIL PRUNE
- PREVIOUSLY-INSTALLED SOIL BORING
- EXISTING MONITORING WELL
- IN SOIL BORING LOCATION
- TEST PIT LOCATED BASED ON IN-HOUSE CONDUCTIVITY RESULTS (INDICATIVE OF BURIED METAL OBJECTS)
- TEST PIT LOCATED BASED ON APPARENT CONDUCTIVITY AND GRINDING (CORRELATING HIGHER RESISTIVITY INDICATIVE OF FORMATION INTERFACES) (SHALLOWER THAN APPROXIMATELY 20 FEET BELOW GRADE)
- TEST PIT LOCATED BASED ON RESISTIVITY DATA (REGARDLESS OF FORMATION INTERFACES) UP TO APPROXIMATELY 40 FEET BELOW GRADE)
- TEST PIT LOCATED AT PREVIOUS SOIL BORING VIB-3 WHERE "SLUDGE-LIKE MATERIAL" WAS ENCOUNTERED
- TEST PIT TO INVESTIGATE FURNACE AND PIT BOTTOM


NOTES:

1. PARK FEATURES AND STRUCTURES DERIVED FROM A MARCH 14, 1974 AERIAL PHOTOGRAPH.
2. THE APPROXIMATE LOCATIONS AND DIMENSIONS OF THE PARK FEATURES AND STRUCTURES HAVE BEEN FIELD VERIFIED.



Typical Test Pit in the Ballfield Area





EXPLANATION	
	NORTHROP GRUMMAN PROPERTY LINE
	FENCE
	LIMITS OF BETHPAGE HIGH SCHOOL MAIN BUILDING
	LINE OF EQUAL GROUNDWATER ELEVATION, IN FT MSL
	DIRECTION OF HORIZONTAL COMPONENT OF GROUNDWATER FLOW
	BASIN
	BITUMINOUS PAVEMENT
	MONITORING WELL LOCATION AND DESIGNATION
	PROPOSED MONITORING WELL LOCATION AND DESIGNATION
	NAVAL WEAPONS INDUSTRIAL RESERVE PLANT
	GROUNDWATER ELEVATION (FT MSL)
	FEET
	MEAN SEA LEVEL

- NOTES:**
1. MONITORING WELLS SURVEYED TO NORTH AMERICAN DATUM (NAD) 83.
 2. PARK FEATURES SHOWN WERE PRESENT PRIOR TO TOWN OF OYSTER BAY REDEVELOPMENT IN 2005.
 3. GROUNDWATER ELEVATIONS BASED ON DEPTHS TO WATER MEASURED ON SEPTEMBER 27, 2006.
 4. MONITORING WELLS BCPMW-4-3, BCPMW-5-1, BCPMW-6-1, BCPMW-6-2, AND BCPMW-7-1 NOT INSTALLED AT TIME OF SEPTEMBER 2006 GROUNDWATER MEASUREMENT ROUND.

© 2008 ARCADIS OF NEW YORK, INC.	SEAL
	NO. ISSUED DATE REVISION DESCRIPTION BY/CHK
	01/2008 REMEDIAL INVESTIGATION REPORT MR
	01/2008 REMEDIAL INVESTIGATION REPORT MR

ARCADIS
OF NEW YORK, INC.

Two Huntington Quadrangle
Suite 1010
Melville, NY 11747
Tel: 801-348-7888 Fax: 801-348-7818
www.arcadis-usa.com

PROJECT TITLE
 NORTHROP GRUMMAN SYSTEMS CORPORATION
 OPERABLE UNIT 3
 (FORMER GRUMMAN SETTLING PONDS)
 BETHPAGE, NEW YORK

PROJECT MANAGER
 C. SAN GIOVANNI

DEPARTMENT MANAGER
 M. WOLPERT

SHEET TITLE
 CONFIGURATION OF THE
 WATER TABLE AND
 GROUNDWATER FLOW DIRECTION
 SEPTEMBER 2006

LEAD DESIGN PROF.


CHECKED BY
 N. RENDL

TASK/PHASE NUMBER
 00007

DRAWN BY
 A. SANCHEZ

PROJECT NUMBER
 NY001464.0807

DRAWING NUMBER
4-6



F-4-PZ				
VOLATILE ORGANIC COMPOUND	CONCENTRATION (µg/L)			
	01/08/08	07/08/07	07/08/07	07/08/07
BENZENE	ND	ND	ND	ND
CS-1,2-DICHLOROBENZENE	0.87	9.8	ND	ND
ETHYLBENZENE	ND	ND	ND	ND
TRICHLOROETHENE	2.1	1.5	ND	ND
TOLUENE	ND	ND	ND	ND
VINYL CHLORIDE	ND	ND	ND	ND
XYLENES	2.4	2.5	ND	ND
TOTAL VOCs	5.4	25	ND	ND
METALS	01/08/08	07/08/07	07/08/07	07/08/07
CHROMIUM	240	ND	ND	ND
CHROMIUM (HEXAVALENT)	ND	ND	ND	ND
IRON	18,000	211	ND	ND

H-7-PZ				
VOLATILE ORGANIC COMPOUND	CONCENTRATION (µg/L)			
	01/08/08	07/08/07	07/08/07	07/08/07
BENZENE	0.3	ND	ND	ND
CS-1,2-DICHLOROBENZENE	52	65	27	180
ETHYLBENZENE	0.82	ND	ND	ND
TRICHLOROETHENE	1,300	1,200	190	140
TOLUENE	20	5.9	ND	0.62
VINYL CHLORIDE	130	51	330	77
XYLENES	4.3	1.7	2	0.32
TOTAL VOCs	1,516	1,358	571	409
METALS	01/08/08	07/08/07	07/08/07	07/08/07
CHROMIUM	3,800	ND	740	ND
CHROMIUM (HEXAVALENT)	ND	5.2	ND	ND
IRON	665,000	34,000	216,000	6,030

H-3-PZ				
VOLATILE ORGANIC COMPOUND	CONCENTRATION (µg/L)			
	01/08/08	07/08/07	07/08/07	07/08/07
BENZENE	1.2	ND	ND	ND
CS-1,2-DICHLOROBENZENE	8.3	ND	35	ND
ETHYLBENZENE	ND	1,200	790	440
TRICHLOROETHENE	1.3	79	24	ND
TOLUENE	190	28,000	23,000	6,900
VINYL CHLORIDE	76	120	140	22
XYLENES	7,300	7,500	4,300	2,380
TOTAL VOCs	7,693	38,195	28,398	9,824
METALS	01/08/08	07/08/07	07/08/07	07/08/07
CHROMIUM	150	ND	79	ND
CHROMIUM (HEXAVALENT)	NA	ND	ND	ND
IRON	118,000	14,000	18,600	ND

I-4-PZ			
VOLATILE ORGANIC COMPOUND	CONCENTRATION (µg/L)		
	01/08/08	07/08/07	07/08/07
BENZENE	ND	ND	ND
CS-1,2-DICHLOROETHENE	82,000	69,000	4,700
ETHYLBENZENE	490	430	420
TRICHLOROETHENE	22,000	22,200	48,000
TOLUENE	20,000	16,000	15,000
VINYL CHLORIDE	8,100	8,400	8,200
XYLENES	1,700	1,500	1,400
TOTAL VOCs	120,418	119,409	118,828
METALS	01/08/08	07/08/07	07/08/07
CHROMIUM	190	ND	ND
CHROMIUM (HEXAVALENT)	89	ND	ND
IRON	37	ND	ND

- EXPLANATION**
- NORTHROP GRUMMAN PROPERTY LINE
 - - - FENCE
 - LIMITS OF BETHPAGE HIGH SCHOOL MAIN BUILDING
 - BASIN
 - APPROXIMATE AREAL EXTENT OF DEEP LOW PERMEABILITY ZONE, BASED ON CPT SBT LOGS
 - BITUMINOUS PAVEMENT
 - F-4-PZ (●) PIEZOMETER
 - Q-5 (●) MIP/CPT BORING
 - N-99 (■) CPT BORING
 - Q-49-PZ (■) ABANDONED PIEZOMETER
 - LINE OF EQUAL PERCHED-WATER ELEVATION, IN FEET ABOVE MSL
 - (77.23) PERCHED WATER ELEVATION (FT MSL)
 - (PH0) PERCHED-WATER NOT DETECTED
 - NA NOT ANALYZED
 - ND CONSTITUENT NOT DETECTED
 - NWIRP NAVAL WEAPONS INDUSTRIAL RESERVE PLANT
 - MIP MEMBRANE INTERFACE PROBE
 - CPT CONE PENETROMETER
 - SBT SOIL BEHAVIOR TYPE
 - PDT PORE DISSIPATION TEST
 - FT FEET
 - MSL MEAN SEA LEVEL
 - VOC VOLATILE ORGANIC COMPOUND
 - µg/L MICROGRAMS PER LITER

- NOTES:**
- PIEZOMETERS SURVEYED TO NORTH AMERICAN DATUM (NAD) 83. CPT LOCATIONS ARE APPROXIMATE BASED ON FIELD MEASUREMENTS.
 - PARK FEATURES SHOWN WERE PRESENT PRIOR TO TOWN OF DYSTER BAY REDEVELOPMENT IN 2005.
 - WATER-LEVEL ELEVATIONS IN PIEZOMETERS BASED ON WATER LEVELS RECORDED ON JULY 13, 2007.
 - PORE DISSIPATION TESTS PERFORMED ON CPT BORINGS FROM APRIL 24, TO MAY 12, 2006, JULY 17 TO 20, 2006, AND JANUARY 17 TO 31, 2007.
 - PERCHED WATER ELEVATIONS OBTAINED FROM CPT BORING PORE DISSIPATION TESTS (PDTs) WERE CALCULATED USING ELEVATION OF WATER IN CLOSEST PIEZOMETER.
 - GROUNDWATER ELEVATION IN SOUTHWEST PARK REGION RANGES FROM APPROXIMATELY 73 TO 75 FT MSL. THEREFORE WATER-LEVELS (BASED ON PDTs) LESS THAN 77 FT MSL WERE INTERPRETED TO BE REPRESENTATIVE OF GROUNDWATER, RATHER THAN PERCHED WATER CONDITIONS.
 - BASED ON LOCAL-SCALE LITHOLOGIC HETEROGENEITY, PERCHED WATER MAY NOT BE CONTINUOUSLY PRESENT IN AREA SHOWN.
 - 78-FOOT CONTOUR DEFINES AREAL EXTENT OF PERCHED WATER.
 - ELEVATION OF THE DEEP LOW PERMEABILITY ZONE RANGES FROM A MINIMUM OF 53 FT MSL (BOTTOM) TO A MAXIMUM OF 87 FT MSL (TOP).

NO	ISSUED DATE	REVISION DESCRIPTION	BY/OD
D	01/2008	REMEDIAL INVESTIGATION REPORT	MR

ARCADIS
OF NEW YORK, INC.

Two Huntington Quadrangle
Suite 1210
Hempstead, NY 11747
Tel: 631-248-7800 Fax: 631-248-7818
www.arcadis-us.com

PROJECT TITLE
NORTHROP GRUMMAN SYSTEMS CORPORATION
OPERABLE UNIT 3
(FORMER GRUMMAN SETTLING PONDS)
BETHPAGE, NEW YORK

PROJECT MANAGER
C. SAN GIOVANNI

DEPARTMENT MANAGER
M. WOLFERT

SHEET TITLE
AREAL EXTENT OF DEEP LOW PERMEABILITY
ZONE AND CONCENTRATIONS OF
VOLATILE ORGANIC COMPOUNDS AND
SELECT METALS IN PERCHED WATER

LEAD DESIGN PROJ.
TASK/PHASE NUMBER
00007

PROJECT NUMBER
NY001464.0807

CHECKED BY
M. REINDL




DRAWN BY
A. SANCHEZ

DRAWING NUMBER
5-6

Date/Time: Thu, 28 Jun 2006 - 11:20am
 Drawn/Checked: R1726 (LMS) (lms)
 Plot/Name: C:\PROJECTS\Remediation\Draw\0007_R_Report\015-4-01_perched_wat_015-4-01.dwg
 User Name: C:\PROJECTS\Remediation\Draw\0007_R_Report\015-4-01_perched_wat_015-4-01.dwg
 Copyright © 2008 ARCADIS OF NEW YORK, INC.

Current Version: 5/20/08
Drawing No. 5-12

Scale: 1" = 100' (Horizontal)
Scale: 1" = 10' (Vertical)
Date: 5/20/08
Drawing No. 5-12




DEFINITION OF ISOCONCENTRATION CONTOURS (DIGITAL WATER RESPONSE)

- 1 - 50 µg/L
- 2 - 100 µg/L
- 3 - 500 µg/L
- 4 - 1,000 µg/L

DEFINITION OF ISOCONCENTRATION CONTOURS (ANALYTICAL DATA)

- 1 - 50 µg/L
- 2 - 100 µg/L
- 3 - 500 µg/L
- 4 - 1,000 µg/L



- NOTES:**
1. ZONES OF SLITS CONSIST OF SILTS, CLAYEY SILTS, AND SILTY SANDS.
 2. ZONES OF CLAYS CONSIST OF CLAY, SILTY CLAY, AND SILTY CLAY.
 3. UP LITHOLOGY BASED ON THE INTERPRETATION OF SHOWN LOGS, WHICH WOULD BE NEARLY-SAME RESPONSE OF THE FORMER WATER, OFF LITHOLOGY BASED ON THE RESPONSE, WHICH DETERMINES SOIL RESPONSE PROVIDED BY MONITORING OF RESPONSE LOG AND SLURRY PUMPING (SA) TO DETERMINE THE OFF-LOGS SOIL BEHAVIOR TYPE, OFF DATA WERE CORRELATED WITH GREAT SPOON SAMPLES TO VERIFY SOIL LITHOLOGY AND GRAN SIZE.
 4. WATER-LEVEL LOCATIONS IN WELLS MEASURED ON SEPTEMBER 21, 2006 AND JULY 13, 2007.
 5. SOILS OTHER THAN LOW-PERMEABILITY ZONES (i.e. SILTS AND CLAYS) CONSIST OF SANDS FROM MEDICAL CORPUS, SCHOOL GROUNDS, AND GRASSES WERE IDENTIFIED COLLECTED AS "SAND" ABOVE.
 6. MONITORING WELL WATER QUALITY DATA FROM JULY 2007.
 7. TOP SOIL BORING LOCATIONS ARE APPROXIMATE.



KEY PLAN SHOWING CROSS SECTION B-B'

SHEET TITLE: HYDROGEOCHEMICAL CROSS SECTION B-B' WITH TRICHLOROETHENE CONCENTRATIONS IN GROUNDWATER PROJECT NUMBER: 00002 SHEET NUMBER: 5-12	PROJECT TITLE: NORTHROP GRUAMAN SYSTEMS CORPORATION OPERABLE UNIT 3 (FORMER GRUAMAN SETTLING PONDS) BETHPAGE, NEW YORK PROJECT NUMBER: NY001464.0807	PROJECT MANAGER: C. SMO GONZALEZ SUPERVISOR: M. WILFERT	LEAD DESIGN PROJ.: M. WILFERT CHECKED BY: M. WILFERT
		DATE: 5/20/08 REVISION DESCRIPTION: REVISION DESCRIPTION ISSUED DATE: 5/20/08	DRAWN BY: A. SANCHEZ DRAWING NUMBER: 5-12

SOUTHWESTERN PORTION OF BETHPAGE COMMUNITY PARK



EXPLANATION


- NORTHROP GRUMMAN CORPORATION PROPERTY LINE
- FENCE
- BASIN
- 0-1" BITUMINOUS PAVEMENT
- VOCs NEAR LAND SURFACE (APPROX. 0-25 FT. BLS.)
- VOCs NEAR WATER TABLE IN CLAYEY ZONES (APPROX. 30-55 FT. BLS.)
- SVOCs, METALS AND PCBs DETECTED NEAR LAND SURFACE (APPROX. 0-25 FT. BLS.)

NOTES:

- THIS FIGURE IS QUALITATIVE IN NATURE AND IS NOT INTENDED TO CONVEY QUANTITATIVE INTERPRETATION OF SAMPLE RESULTS.
- ALL AREAS OF CONCERN IN PARK NOT SHOWN

LEGEND:

- VOC VOLATILE ORGANIC COMPOUNDS
- PCB POLYCHLORINATED BIPHENYLS
- SVOC SEMI-VOLATILE ORGANIC COMPOUNDS
- FT. BLS. FEET BELOW LAND SURFACE



DRAWING NOT TO SCALE

ISSUED DATE	REVISION DESCRIPTION	BY/DO
6-27-07	NYSDEC PUBLIC MEETING	DES

ARCADIS
OF NEW YORK, INC.

Two Huntington Quadrangle
Suite 1010
Melville, NY 11747
Tel: 631-440-7000 Fax: 631-440-7010
www.arcadis-us.com

PROJECT TITLE

OPERABLE UNIT 3
FORMER GRUMMAN
SETTLING PONDS
BETHPAGE, NEW YORK

PROJECT MANAGER
C. SAN GIOVANNI

DEPARTMENT MANAGER
M. WOLFERT

SHEET TITLE

CONCEPTUAL SITE MODEL

LEAD DESIGN PROF.


TASK/PHASE NUMBER
00002

PROJECT NUMBER
NY001464.1007

CHECKED BY
M. REINOL


DRAWN BY
A. SANCHEZ

FIGURE
6



Layer Title: 01-4
 01/2008

Path Name: C:\WORK\CTY\Northrop Grumman\01010307 01 Report\01-4.dwg
 User Name: j...



- EXPLANATION**
- NORTHROP GRUMMAN PROPERTY LINE
 - - - FENCE
 - - - LIMITS OF BETHPAGE HIGH SCHOOL MAN BUILDING
 - GROUNDWATER TCE ISOCONCENTRATION CONTOUR (DASHED WHERE INFERRED)
 - ▨ BASK
 - 6" BITUMINOUS PAVEMENT
 - ⊕ MONITORING WELL
 - ⊕ VERTICAL PROFILE BORING
 - ⊕ ABANDONED MONITORING WELL
 - NWRP NAVAL WEAPONS INDUSTRIAL RESERVE PLANT
 - TCE TRICHLOROETHENE
 - (10) TCE CONCENTRATION IN ug/L
 - (ND) NOT DETECTED
 - (?) SAMPLE NOT COLLECTED AT WATER TABLE
 - ug/L MICROGRAMS PER LITER

- NOTES:**
- MONITORING WELLS AND VPIs VP-1 TO VP-20 SURVEYED TO NORTH AMERICAN DATUM (NAD) 83. ALL OTHER VP LOCATIONS ARE APPROXIMATE BASED ON FIELD MEASUREMENTS.
 - PARK FEATURES SHOWN WERE PRESENT PRIOR TO TOWN OF OYSTER BAY REDEVELOPMENT IN 2005.
 - MAXIMUM TCE CONCENTRATION IS SHOWN FOR EACH VP (INCLUDES CO-LOCATED VPIs). SAMPLE WAS COLLECTED AT THE WATER TABLE UNLESS OTHERWISE NOTED.
 - MOST RECENT TCE CONCENTRATION IS SHOWN FOR EACH MONITORING WELL AT CLUSTERED LOCATIONS. THE HIGHEST TCE CONCENTRATION IS SHOWN.

- DEFINITION OF ISOCONCENTRATION CONTOURS**
- 5 ug/L
 - 50 ug/L
 - 100 ug/L
 - 500 ug/L
- LINE OF EQUAL TCE CONCENTRATION DENOTING CONCENTRATIONS LOWER THAN SURROUNDING CONTOURS.

SEAL	
01/2008	REMEDIAL INVESTIGATION REPORT
ISSUED DATE	REVISION DESCRIPTION
	BY/CHK

ARCADIS
OF NEW YORK, INC.

Two Huntington Quadrangle
Suite 1818
Melville, NY 11747
Tel: 631-348-7800 Fax: 631-348-7818
www.arcadis-us.com

PROJECT TITLE
**NORTHROP GRUMMAN SYSTEMS CORPORATION
 OPERABLE UNIT 3
 (FORMER GRUMMAN SETTLING PONDS)
 BETHPAGE, NEW YORK**

PROJECT MANAGER
C. SAN GIOVANNI

DEPARTMENT MANAGER
M. WOLPERT

SHEET TITLE
**TRICHLOROETHENE
 IN SHALLOW GROUNDWATER**

LEAD DESIGN PROF.
N. REMOLD


CHECKED BY
N. REMOLD

TASK/PHASE NUMBER
00007

DRAWN BY
A. SANCHEZ

PROJECT NUMBER
NY001464.0807

DRAWING NUMBER
5-8



SEAL



PROJECT TITLE
 NORTHROP GRUMMAN SYSTEMS CORPORATION

PROJECT MANAGER
 C. SAN GIOVANNI

DEPARTMENT MANAGER
 M. WOLFERT

LEAD DESIGN PROF.

SHEET TITLE


TASK/PHASE NUMBER

Vapor Intrusion Evaluation



Soil Gas Interim Remedial Measure

- Objective:
 - Prevent off-site migration of VOCs in soil gas
- System components:
 - Depressurization/Monitoring Wells
 - Below-Grade Piping
 - Equipment Building (Blower/Electrical Systems)
 - Emissions Control (Vapor Treatment)



- EXPLANATION:**
- NORTHROP GRUMMAN PROPERTY LINE
 - FENCE
 - - - LIMITS OF BETHPAGE HIGH SCHOOL MAIN BUILDING
 - 6"t. BITUMINOUS PAVEMENT
 - [Green Hatched Box] PROPOSED LOCATION OF GROUNDWATER & SOIL GAS INTERIM REMEDIAL MEASURE SYSTEMS
 - [Orange Hatched Box] SOIL GAS PILOT STUDY LOCATION
 - [Blue Hatched Box] GROUNDWATER BENCH SCALE/TREATABILITY STUDY SAMPLE COLLECTION LOCATION


DRAFT

© 2007 ARCADIS OF NEW YORK, INC.		NO PLAN	SCALE	<p>Two Huntington Quadrangle 9-11-15 P.O. Box, NY 11767 Tel: 878-434-1000 Fax: 878-434-1011 www.arcadis-us.com</p>	PROJECT TITLE	PROJECT MANAGER	DEVELOPMENT MANAGER	LEAD DESIGN PRINCIPAL	DRAWN BY
					<p>NORTHROP GRUMMAN OPERABLE UNIT 3 INTERIM REMEDIAL MEASURES BETHPAGE, NEW YORK</p>	C. SAN GIOVANNI	M. WILFERT		D. STEIN
					<p>PROJECT TITLE</p> <p>PROPOSED LOCATION OF INTERIM REMEDIAL MEASURE SYSTEMS</p>			<p>NO. / DATE</p> <p>1 / 6-07</p> <p>NO. / ISSUED DATE</p>	<p>DRAWN BY</p> <p>A. SANCHEZ</p> <p>DATE</p> <p>8</p>
		<p>WIS/AC: PUBLIC MEETING</p> <p>REVISION DESCRIPTION</p>	BY/CHKD					<p>NO. / DATE</p> <p>1 / 6-07</p> <p>NO. / ISSUED DATE</p>	<p>PROJECT NUMBER</p> <p>NY001464.1007</p>

Groundwater Interim Remedial Measure

- Objectives:
 - Minimize off-site migration of VOCs in groundwater
 - Create/enhance VOC-free water-table lens south of Park
- Options Under Consideration:
 - Groundwater Pump & Treat
 - Enhanced Biodegradation
 - Reactive Barrier
 - Chemical Oxidation

CITY OF OYSTER BAY: ENGINE: LOUIS B. INC. INC. 100 WEST 100th STREET, OYSTER BAY, NY 11574
 PROJECT: NORTHROP GRUMMAN OPERABLE UNIT 3 - FORMER GRUMMAN SETTLEMENT PONDS
 DRAWING: 111-10000-001 - SITE PLAN
 DATE: 08/14/2009
 SCALE: AS SHOWN
 PROJECT: NORTHROP GRUMMAN OPERABLE UNIT 3 - FORMER GRUMMAN SETTLEMENT PONDS
 DRAWING: 111-10000-001 - SITE PLAN
 DATE: 08/14/2009
 SCALE: AS SHOWN



- NOTES:**
1. LOCATION OF WORK: ALL WORK DESCRIBED IN THESE DRAWINGS/SPECIFICATIONS SHALL BE PERFORMED ON BEHALF OF NORTHROP GRUMMAN SYSTEMS CORPORATION AND THE CONTRACTOR SHALL NOTIFY THE TOWN OF OYSTER BAY HEREBY DEPARTMENT AND ENGINEER OF THE PROPOSED START OF WORK WITHIN THESE PLATTED AREAS A MINIMUM OF 48 HOURS PRIOR TO THE START OF THE WORK.
 2. CONTRACTORS SHOULD VISIT THE SITE AND EXAMINE ALL OF THE PHYSICAL CONDITIONS THAT AFFECT THE PWD, BLD PROJ.
 3. CONTRACTORS SHALL OBTAIN ALL NECESSARY MEASUREMENTS TO VERIFY THE ABILITY TO COMPLETE THE WORK IN ACCORDANCE WITH THE SCOPE OF WORK AND AGREEMENT. NO ADJUSTMENTS TO THE BID OR CONTRACT PRICE WILL BE PERMITTED BASED ON CHANGING CONDITIONS.
 4. CONTRACTORS SHALL PROVIDE ALL LABOR, MATERIAL, AND EQUIPMENT, UNLESS OTHERWISE STATED, NECESSARY TO PERFORM THIS WORK. THE SITE WILL BE A ZONED SITE.
 5. CONTRACTORS SHALL BE RESPONSIBLE FOR OBTAINING ALL TRAFFIC PERMITS AND APPROVALS NECESSARY TO PERFORM THIS WORK, INCLUDING AGREEMENTS WITH APPLICABLE LOCAL AND TRAFFIC AGENCIES.
 6. ALL SITE WORKERS SHALL HAVE THE APPROPRIATE HEALTH AND SAFETY TRAINING. REVIEW AND SIGN THE PROJECT HEALTH AND SAFETY PLAN. UNLESS OTHERWISE GRANTED BY THE PROJECT HEALTH AND SAFETY OFFICER AND REVIEW AND ACKNOWLEDGE NORTHROP GRUMMAN SYSTEMS CORPORATION ANTICIPATED SYSTEMS EASTERN REGION'S (SOP) "ON-SITE CONTRACTOR'S ENVIRONMENTAL, SAFETY AND HEALTH COMPLIANCE MANUAL, REVISED, NEW YORK, DATED JUNE 15, 2004" COPIES OF EACH PERSON'S APPLICABLE STRAIGHT CERTIFICATES SHALL BE PROVIDED TO THE PROJECT HEALTH AND SAFETY OFFICER PRIOR TO THE EMPLOYEE'S ON-SITE WORK AT THE SITE. COPIES OF TRAINING CERTIFICATES SHALL BE KEPT ON FILE WITH THE PROJECT FILE.
 7. WHILE CONSTRUCTION ACTIVITIES ARE UNDER WAY AT LEAST ONE CONTRACTOR PERSONNEL OR OTHER SUPERVISOR SHALL BE PRESENT AT THE JOB SITE AT ALL TIMES AND SHALL DIRECTLY REPORT TO THE ARCADIS SITE SUPERVISOR.
 8. ALL EXCAVATED/CONDUIT MATERIALS INTO THE CATEGORIZED CONSTRUCTION AREAS, INCLUDING SOIL MATERIAL, CONCRETE/JOURNAL/METAL MATERIAL SHALL BE DISPOSED OF BY CONTRACTOR. SOIL MATERIAL WILL BE CHARACTERIZED AND DISPOSED OF IN ACCORDANCE WITH THE SPECIFICATIONS ON DRAWING TO ADD ALL FEDERAL, STATE AND LOCAL REGULATIONS.
 9. CONTRACTORS ARE RESPONSIBLE FOR LOCATING AND VERIFYING LOCATION OF ALL UTILITIES WITHIN AREA AFFECTED BY CONSTRUCTION. OWNER OR OWNER'S AGENTS OR LOCATIONS PROVIDED TO CONTRACTOR WITH RESPECT TO UTILITIES SHALL BE SUPPLIED TO THE CONTRACTOR WITH A RECORD OF UTILITIES AT COMPLETION OF CONSTRUCTION. IF A CONFLICT EXISTS BETWEEN THE UTILITY LOCATION AND THE CONSTRUCTION OPERATIONS, IT IS THE CONTRACTOR'S RESPONSIBILITY TO NOTIFY THE ENGINEER IMMEDIATELY SO THAT THE CONFLICT MAY BE RESOLVED.
 10. CONTRACTOR IS RESPONSIBLE FOR PROVIDING THE ENGINEER WITH ALL INFORMATION REQUESTED TO COMPLETE A SET OF "AS-BUILT" DRAWINGS BY ISSUING A RECORD SET OF DAILY PROGRESS OF WORK.
 11. UNLESS OTHERWISE NOTED, ALL AREAS DISTURBED BY THIS WORK SHALL BE RESTORED TO ORIGINAL CONDITION.
 12. CONTRACTOR TO PROTECT AND PRESERVE ALL EXISTING FEATURES (E.G. MONITORING WELLS, EQUIPMENT, ETC.) WHICH ARE AFFECTED BY CONSTRUCTION. DAMAGE SUSTAINED TO ANY EXISTING FEATURE SHALL BE REPAIRED/REPLACED AT CONTRACTOR'S EXPENSE TO SATISFACTION OF ENGINEER.
 13. CONTRACTOR SHALL PERFORM ALL WORK IN ACCORDANCE WITH ALL COUNTY, LOCAL, STATE, AND FEDERAL REGULATIONS, INCLUDING BUT NOT LIMITED TO, ALL APPLICABLE LOCAL, STATE, AND FEDERAL (DEQA, USFSA, AND DOT, ETC.) RULES AND REGULATIONS.
 14. UNLESS OTHERWISE INDICATED HEREIN, ALL MATERIALS AND EQUIPMENT FURNISHED UNDER THIS CONTRACT SHALL BE NEW, FREE FROM DEFECTS, AND SHALL BE QUANTITIES FOR A PERIOD OF AT LEAST ONE YEAR FROM THE DATE OF ACCEPTANCE OF THE WORK. THE CONTRACTOR SHALL FURNISH, AT NO COST TO THE ENGINEER, ALL LABOR AND MATERIALS NECESSARY TO CORRECT DEFECTS DUE TO FAULTY WORKMANSHIP OR MATERIALS.
 15. OTHER CONSTRUCTION ACTIVITIES MAY BE TAKING PLACE CONCURRENTLY WITH THIS PROJECT. THE CONTRACTOR SHALL COORDINATE WITH THE VARIOUS PARTIES AND SHALL COORDINATE SCHEDULES.
 16. THE INFORMATION SHOWN ON THE DRAWINGS CONCERNING TYPE AND LOCATION OF UNDERGROUND UTILITIES IS NOT GUARANTEED TO BE ACCURATE. ALL INCLUDE. CONTRACTOR IS RESPONSIBLE FOR MAKING HIS OWN INVESTIGATIONS AS TO THE TYPE AND LOCATION OF UNDERGROUND UTILITIES AS MAY BE NECESSARY TO AVOID DAMAGE THERE TO.
 17. TRENCHING WILL BE PERFORMED IN AREAS WHERE VEHICULAR TRAFFIC MAY BE PRESENT. THE CONTRACTOR SHALL NOTIFY THE TOWN OF OYSTER BAY HEREBY DEPARTMENT AND ENGINEER OF THE PROPOSED START OF WORK WITHIN THESE PLATTED AREAS A MINIMUM OF 48 HOURS PRIOR TO THE START OF THE WORK. FURTHERMORE, CONTRACTOR SHALL NOTIFY THE TOWN OF OYSTER BAY HEREBY DEPARTMENT AND ENGINEER OF THE PROPOSED START OF WORK WITHIN THESE PLATTED AREAS A MINIMUM OF 48 HOURS PRIOR TO THE START OF THE WORK. FURTHERMORE, CONTRACTOR SHALL NOTIFY THE TOWN OF OYSTER BAY HEREBY DEPARTMENT AND ENGINEER OF THE PROPOSED START OF WORK WITHIN THESE PLATTED AREAS A MINIMUM OF 48 HOURS PRIOR TO THE START OF THE WORK.
 18. PIPE ROUTING SHOWN FOR CONSTRUCTION LAYOUT PURPOSES ONLY. ACTUAL ROUTING TO BE FIELD DETERMINED AND IS SUBJECT TO ENGINEER'S APPROVAL.
 19. CONTRACTOR SHALL EXTEND ALL PROPOSED PERMS AND MAKE ALL NECESSARY CONNECTIONS TO WELL VALVES.
 20. ALL PIPING PRESSURE TESTS SHALL BE MADE BY THE CONTRACTOR IN THE PRESENCE OF THE ENGINEER.
 21. CONTRACTOR SHALL PROVIDE ALL PRODUCTS AND PROPERLY CALIBRATED TESTING EQUIPMENT REQUIRED TO PERFORM THE PIPING PRESSURE TESTING WORK.
 22. TESTS MAY BE PERFORMED ON SEPARATE SECTIONS OF PIPING TO EXPEDITE CONSTRUCTION. THE CONTRACTOR SHALL NOT PERFORM PRESSURE TESTING AGAINST SYSTEM VALVES.
 23. AFTER THE INITIAL PRESSURE TEST ON PIPING IS COMPLETE SUCCESSFULLY, THE CONTRACTOR SHALL BACKFILL THE TRENCHES AS SPECIFIED.
 24. EXCAVATIONS SHALL BE KEPT FREE FROM STANDING WATER.
 25. CONTRACTOR SHALL NOTIFY THE ENGINEER AT THE COMPLETION OF EXCAVATIONS AND TRENCHING TO ALLOW FOR INSPECTIONS.
 26. CONTRACTOR SHALL PROVIDE APPROPRIATE SAFETY BARRIERS AROUND TRENCHING AND EXCAVATION TO PREVENT ACCIDENTS OF UNAUTHORIZED ENTRY.
 27. BACKFILL OF TRENCHES IN UNPAVED AREAS WILL BE APPLIED IN 6-INCH THICK COMPACTED TIES. BACKFILL OF TRENCHES IN GRAVELLED ROAD CROSSING AREAS SHALL BE APPLIED IN 4-INCH COMPACTED LIPS THAT A 600 WOODEN PROCTOR DENSITY SHALL BE ACHIEVED.
 28. CONTRACTORS FILL SOURCE MUST BE TESTED BY CONTRACTOR AND APPROVED BY THE ENGINEER PRIOR TO COMMENCING THE WORK. AND/OR PLACING THE MATERIAL.
 29. EXCAVATIONS WILL BE BACKFILLED AS PROMPTLY AS WORK PERMITS. ONLY INSURED OPERATIONS HAVE BEEN COMPLETED.
 30. DO NOT PLACE MATERIALS ON SURFACES THAT ARE MUDRY, FROZEN, OR CONTAIN ICE OR FOG.
 31. INSULATION SHALL BE PLACED A MINIMUM OF 18 INCHES FROM THE CENTER OF ALL TRENCHES IN ALL AREAS. THIS TAP SHALL CONTAIN A 1/2\"/>

GENERAL NOTES:

SECTION 48 BLOCK 8, LOT 80 USE WITHIN THE TOWN OF OYSTER BAY AND ARE ZONED "M" GENERAL BUSINESS.

THE FOLLOWING IS A SUMMARY LISTING OF ZONING REGULATIONS PRINTED IN THE EDGE OF THE TOWN OF OYSTER BAY:

WILSONVILLE (LOT WITHIN PROPOSED)	40 FEET
MARKHAM BUSINESS DEVELOPMENT	80 FEET
MINIMUM FRONT YARD SETBACK	10 FEET
MINIMUM REAR YARD SETBACK	20 FEET
CRACKLE BUILDING HEIGHT	30 FEET

No.	Date	Revisions	By	Check	Drawn by	Checked by

Professional Engineer's Name: **WILLIAM S. WITTEK**
 Professional Engineer's No.: 0000027
 State: NY
 Date: 08/14/2009
 Scale: AS SHOWN
 Project No.: 111-10000-001
 Drawing No.: 111-10000-001-001
 Title: SITE PLAN

NORTHROP GRUMMAN CORPORATION • 100 WEST 100th STREET, OYSTER BAY, NEW YORK
 OPERABLE UNIT 3 - FORMER GRUMMAN SETTLEMENT PONDS


ARCADIS
 ARCADIS OF NEW YORK, INC.


SITE PLAN

ARCADIS Project No.: 111-10000-001-00003	Scale: AS SHOWN
DATE: 08/14/2009	ARCADIS
6723 Tompsett Road	60 FEET
Box 46	80 FEET
Syracuse, NY 13214	10 FEET
TEL: 315.448.0100	20 FEET

1

Soil Gas Sampling





Human Health Risk Assessment, Screening of Alternatives and FS

TECHNOLOGY	CONTAMINANT			COMMENTS
	VOCs	PCBs	Metals	
SOILS, LPZ, AND PERCHED WATER				
Excavation w/off-site disposal	Y	Y	Y	Retained for all alternatives
Excavation w/on-site treatment	Y	Y	Y	Off-site disposal is more effective and less costly than on-site treatment options considered (soil washing, chemical oxidation, and incineration). Incineration was also eliminated due to the likelihood that the technology would not be acceptable to the NYSDEC, NYSDOH, and/or public.
Stabilization	N	Y	Y	Stabilization is not effective at treating VOCs.
Stabilization enhanced w/Zero-Valent Iron for VOCs only	Y	Y	Y	Retained for Alternatives 2 and 3
Stabilization enhanced w/Zero-Valent Iron for VOCs & PCBs	Y	Y	Y	Retained for Alternative 3 (2'-6'/10') only
In-situ Thermal Remediation	Y	N	N	Retained for Alternatives 2 and 3
In-situ Thermal Remediation (enhanced for PCBs)	Y	Y	N	Overall costs were prohibitive compared to excavating w/off-site disposal for alternatives considered.
Soil Vapor Extraction	Y	N	N	Retained for Alternatives 2 and 3
Multi-phase Extraction	Y	N	Y	Retained for Alternatives 2 and 3
Gravel Cap	Y	Y	Y	Retained for Alternatives 2 and 3
GROUNDWATER				
Pump & Treat	Y	NA	Y	Retained for all alternatives
Stabilization enhanced w/Zero-Valent Iron for VOCs only	Y	NA	Y	Retained for Alternatives 2 and 3
In-situ Thermal Remediation	Y	NA	N	Retained for Alternatives 2 and 3
In-situ Chemical Oxidation w/Permanganate	Y	NA	N	Retained for Alternative 4 only
In-situ Chemical Oxidation w/Persulfate	Y	NA	N	Site-specific bench-scale tests found permanganate to be a more effective oxidant.
Multi-phase Extraction	Y	NA	Y	The OM&M costs will be prohibitive due to the large quantity of water that would have to be extracted, treated, and discharged.
Enhanced Anaerobic Bioremediation	Y	NA	N	Is not compatible with the existing GW IRM due to the generation and release of significant quantities of dissolved iron within the anaerobic zone which would, ultimately, render the groundwater recovery system inoperable.
SOIL VAPOR				
Soil Vapor Extraction	Y	NA	NA	Retained for all alternatives

Estimated Project Schedule

- On-Site
 - RI Field Work: Completed
 - Soil Gas IRM Startup: October 2007
 - RI Report: Late Summer 2007
 - Feasibility Study: December 2007
 - Groundwater IRM Startup: October 2008
- Off-Site
 - RI Field Work: First Quarter 2008
 - RI Report: June 2008
 - Feasibility Study: September 2008
- Additional Public Meetings: To Be Determined

