

Mr. Henry Wilkie  
Project Manager  
New York State Department of Environmental Conservation  
Remedial Bureau A  
625 Broadway  
Albany, New York 12233-7015

Mr. Steven Scharf, P.E.  
Project Manager  
New York State Department of Environmental Conservation  
Remedial Bureau A  
625 Broadway  
Albany, New York 12233-7015

Subject:

2016 Second Quarter Operation Maintenance and Monitoring Report,  
Operable Unit 2, Northrop Grumman Systems Corporation and Naval Weapons  
Industrial Reserve Plant (NWIRP) Sites, Bethpage, New York.  
(NYSDEC Site #s 1-30-003A and B)

Dear Henry and Steve:

On behalf of Northrop Grumman Systems Corporation (Northrop Grumman), Arcadis is providing the NYSDEC with the 2016 Second Quarter Operation Maintenance and Monitoring Report (Report). This Report was prepared to document the operation, maintenance, and monitoring (OM&M) activities conducted for the on-site portion of the Operable Unit 2 (OU2) groundwater remedy and the results of ongoing volatile organic compound (VOC) and inorganic monitoring in groundwater to meet the remedial objectives set forth in the March 2001 OU2 Record of Decision (ROD).

Table 1 summarizes OU2 remedial system performance operational data and water balance. Tables 2 and 3 provide the analytical results for remedial system water and vapor samples for this period. Tables 4 and 5 provide the air modeling

Arcadis of New York, Inc.  
Two Huntington Quadrangle  
Suite 1S10  
Melville  
New York 11747  
Tel 631 249 7600  
Fax 631 249 7610  
[www.arcadis.com](http://www.arcadis.com)

ENVIRONMENT

Date:  
August 31, 2016

Contact:  
David E. Stern

Phone:  
631.391.5284

Email:  
[david.stern@arcadis.com](mailto:david.stern@arcadis.com)

Our ref:  
NY001496.315I.GWMI4

Mr. Henry Wilkie  
Mr. Steven Scharf, P.E.  
August 31, 2016

inputs and outputs and resulting analyses, based on vapor samples collected from the Tower 96 and Tower 102 systems, respectively, for this period.

Tables 6, 7 and 8 provide the validated analytical results of groundwater monitoring for this period. Figures 1 through 4 show the Locations of Wells and Onsite Groundwater Remedy, Locations of Treatment Systems and Discharges, ONCT Groundwater Extraction and Treatment System Site Plan and the ONCT Groundwater Extraction and Treatment System Schematic, respectively.

Please contact us if you have any questions or comments.

Sincerely,

Arcadis of New York, Inc.



David E. Stern  
Senior Hydrogeologist



Carlo San Giovanni  
Project Manager

Copies:

Ed Hannon – Northrop Grumman  
Fred Weber – Northrop Grumman  
Walter Parish – NYSDEC Region 1  
Steven Karpinski – New York State Department of Health  
Joseph DeFranco – Nassau County Department of Health  
Lora Fly – NAVFAC Midlant Environmental  
David Brayack – TetraTech NUS, Inc.  
Roger Smith – Glenn Springs Holdings, Inc.  
Manfred Bohms – Steel Equities  
Thomas Taccone – USEPA  
Robert Alvey – USEPA  
Carol Stein-USEPA  
Matthew Russo – Town of Oyster Bay  
Stan Carey – Massapequa Water District  
Matthew Snyder – New York American Water  
Frank Koch – South Farmingdale Water District  
John Reinhardt – Town of Hempstead Water District  
Michael Boufis – Bethpage Water District  
Lois Lovisolo – Bethpage Public Library (Public Repository)  
File

**Table 1**  
**Operational Summary for the On-Site Portion of the OU2 Groundwater Remedy, Second Quarter 2016 <sup>(1)</sup>**  
**Operable Unit 2, Northrop Grumman Systems Corporation,**  
**Bethpage, New York**

	Quarterly Flow Rates (gpm)		Quarterly Flow Volumes (MG)			Quarterly VOC Concentrations (µg/L)		VOC Mass Removed (lbs) <sup>(7)</sup>	
	Design <sup>(2)</sup>	Average <sup>(3,4)</sup>	Design <sup>(2)</sup>	Actual <sup>(3,4)</sup>	% of Design	TCE <sup>(5)</sup>	TVOC <sup>(5,6)</sup>	Quarterly	Cumulative
<b>Influent Groundwater</b>									
Well 1 <sup>(11), (12)</sup>	800	845	107.1	103.0	96%	615	650	559	42,155
Well 3R <sup>(11), (12)</sup>	700	998	93.7	123.0	131%	487	540	543	87,926
Well 17 <sup>(12)</sup>	1,000	1,047	133.9	127.6	95%	129	160	167	52,096
Well 18 <sup>(12)</sup>	600	984	80.4	114.7	143%	47	68	64	6,012
Well 19 <sup>(12)</sup>	700	795	93.7	99.0	106%	129	160	130	7,701
<b>Total <sup>(14)</sup></b>	<b>3,800</b>	<b>4,669</b>	<b>509</b>	<b>567</b>	<b>111%</b>	<b>--</b>	<b>--</b>	<b>1,463</b>	<b>195,890</b>
<b>Effluent Groundwater <sup>(8)</sup></b>									
Calpine	100 - 400	228	--	29.9	--	--	--	--	--
OXY Biosparge <sup>(10)</sup>	2 - 42	0	--	0	--	--	--	--	--
West Recharge Basins	1,112 - 1,455	1,568	--	210.0	--	--	2.9	--	--
South Recharge Basins	2,231	2,445	298.8	327.4	110%	--	1.8	--	--
<b>Total <sup>(13)</sup></b>	<b>--</b>	<b>4,241</b>	<b>--</b>	<b>567</b>	<b>--</b>	<b>--</b>	<b>--</b>	<b>--</b>	<b>--</b>
<b>Additional Flow to South Recharge Basins</b>									
Storm Water Runoff Contributing to South Recharge Basins Flow Volume <sup>(14)</sup>	--	--	--	18.2	--	--	--	--	--
<b>Total Flow Volume to South Recharge Basins <sup>(13,15)</sup></b>	<b>--</b>	<b>--</b>	<b>299</b>	<b>346</b>	<b>116%</b>	<b>--</b>	<b>--</b>	<b>--</b>	<b>--</b>
<b>Treatment Efficiencies <sup>(9)</sup></b>									
Tower 96 System:	99.5%								
Tower 102 System:	>99.9%								

Notes and abbreviations on last page.

**Table 1**  
**Operational Summary for the On-Site Portion of the OU2 Groundwater Remedy, Second Quarter 2016 <sup>(1)</sup>**  
**Operable Unit 2, Northrop Grumman Systems Corporation,**  
**Bethpage, New York**

**Notes and Abbreviations:**

- (1) Quarterly reporting period: April 04, 2016 through July 06, 2016.
  - (2) "Design" flow rates were determined for the five remedial wells and for the South Recharge Basins based on computer modeling (ARCADIS G&M, Inc. 2003c, modified in April 2005). Flow rates for Calpine, OXY Biosparge and West Recharge Basins are typical flow rates and are provided for reader information. "Design" flow volumes represent the volume of water that should be pumped/discharged during the reporting period and is calculated by multiplying the design rate by the reporting period duration
  - (3) "Average" flow rates for the remedial wells represent the average actual pumping rates when the pumps are operational and do not take into account the time that a well is not operational. During this quarterly reporting period, the remedial wells operated for the following percentage of the time: Well 1 (91%), Well 3R (92%), Well 17 (91%), Well 18 (87%), and Well 19 (93%). "Actual" volumes are determined via totalizing flow meters.
  - (4) "Average" flow rates for the system discharges represent the average flow rate during the entire reporting period and are determined by dividing the total flow during the reporting period by the reporting period duration. The Calpine and South Recharge Basins flow volumes are determined via totalizing flow meters. The West Recharge Basin flow is calculated by subtracting the cumulative flow to the other discharges from the total influent flow. Actual flow to the recharge basins is greater, as shown, because storm water combines with the plant effluent prior to discharge to the recharge basins.
  - (5) The TCE and TVOC concentrations for the remedial wells are from the quarterly sampling event performed during this reporting period on May 12, 2016 (Table 2).
  - (6) The TVOC concentration for the two sets of recharge basins are their respective average monthly SPDES concentration for the current quarter.
  - (7) TVOC mass removed for the reporting period is calculated by multiplying the TVOC concentration from the quarterly sampling event and the quantity of water pumped during the reporting period.
  - (8) There are four discharges for the effluent groundwater: South Recharge Basins, West Recharge Basins, Calpine and OXY Biosparge system. Treated water is continuously discharged to the south and west recharge basins, and is available "on-demand" to both the Calpine Power Plant (Calpine) for use as make-up water, and the biosparge remediation system operated by Occidental Chemical (OXY Biosparge).
  - (9) Treatment System Efficiencies are calculated by dividing the difference between the remedial well flow weighted influent and effluent TVOC concentrations by the remedial well flow weighted influent concentration.
  - (10) Occidental Chemical reported in May 2016 that the OXY Biosparge system required no water usage in the 1st Quarter of 2016, and no planned usage for the remainder of 2016.
  - (11) Wells 1 and 3R were shut down on April 14 and 15, 2016 for Occidental blower repair at Tower 96.
  - (12) The majority of downtime during Second Quarter 2016 was due to communication failures at both systems and some downtime at Tower 102 was due to a low compressed air condition. The low compressed air condition was remedied and a radiofrequency survey is planned for ONCT to investigate the cause of communication failures.
  - (13) Total pumpage/recharge rates are accurate to ±15% due to limitations in metering. Flow meter calibration is scheduled.
  - (14) Storm Water Runoff Volume is calculated by multiplying the adjusted tributary area and NOAA precipitation data for the reporting periods. The adjusted tributary area is tributary area that is adjusted by the runoff coefficient to exclude the infiltration volume from the total rainfall volume. The tributary area, runoff coefficient, and adjusted tributary area are from Dvirka and Bartilucci Consulting Engineers' Storm Water Permit Evaluation Report (January, 28, 2010). The NOAA precipitation data are calculated as a sum of NOAA daily precipitation data for the reporting period. NOAA precipitation data are retrieved from Station GHCND:USW00054787 - FARMINGDALE REPUBLIC AIRPORT, NY US.
  - (15) Total Flow Volume to South Recharge Basins is estimated as a sum of flow volumes contributed from the Effluent Groundwater to South Recharge Basins and from Storm Water Runoff to South Recharge Basins.
- |      |                      |       |   |
|------|----------------------|-------|---|
| --   | not applicable       | NOAA  | National Oceanic and Atmospheric Administration |
| µg/L | micrograms per liter | SPDES | State Pollution Discharge Elimination System    |
| gpm  | gallons per minute   | TCE   | trichloroethene                                 |
| lbs  | pounds               | TVOC  | total volatile organic compounds                |
| MG   | million gallons      | VOC   | volatile organic compounds                      |

**Table 2**  
**Concentrations of Constituents in Remedial Wells and**  
**Treatment System Effluents, Second Quarter 2016, Operable Unit 2,**  
**Northrop Grumman Systems Corporation,**  
**Bethpage, New York**

Constituents (units in µg/L)	Location ID: Sample ID: Sample Date:	WELL 1 WELL 1 5/12/2016	WELL 3R WELL 3R 5/12/2016	96 EFFLUENT T96 EFFLUENT (GW) 5/12/2016	WELL 17 WELL 17 5/12/2016
<b><u>Volatile Organic Compounds (VOCs)<sup>(1,2)</sup></u></b>					
1,1,1-Trichloroethane		< 4.0	<b>0.77 J</b>	< 1.0	<b>0.39 J</b>
1,1,2,2-Tetrachloroethane		< 4.0	< 1.0	< 1.0	< 1.0
1,1,2-Trichloroethane		< 4.0	< 1.0	< 1.0	< 1.0
1,1-Dichloroethane		<b>0.85 J</b>	<b>1.5</b>	< 1.0	<b>0.89 J</b>
1,1-Dichloroethene		<b>1.0 J</b>	<b>4.1</b>	< 1.0	<b>1.6</b>
1,2-Dichloroethane		< 4.0	< 1.0	< 1.0	< 1.0
1,2-Dichloropropane		<b>4.1</b>	< 1.0	< 1.0	< 1.0
2-Butanone (MEK)		< 40	< 10	< 10	< 10
2-Hexanone (MBK)		< 20	< 5.0	< 5.0	< 5.0
4-methyl-2-pentanone (MIK)		< 20	< 5.0	< 5.0	< 5.0
Acetone		< 40	< 10	< 10	< 10
Benzene		< 2.0	< 0.50	< 0.50	< 0.50
Bromodichloromethane		< 4.0	< 1.0	< 1.0	< 1.0
Bromoform		< 4.0	< 1.0	< 1.0	< 1.0
Bromomethane		< 8.0	< 2.0	< 2.0	< 2.0
Carbon Disulfide		< 8.0	< 2.0	< 2.0	< 2.0
Carbon tetrachloride		< 4.0	< 1.0	< 1.0	< 1.0
Chlorobenzene		< 4.0	< 1.0	< 1.0	< 1.0
Chloroethane		< 4.0	< 1.0	< 1.0	< 1.0
Chloroform		< 4.0	<b>0.24 J</b>	< 1.0	<b>0.39 J</b>
Chloromethane		< 4.0	< 1.0	< 1.0	< 1.0
cis-1,2-dichloroethene		<b>4.4</b>	<b>5.3</b>	< 1.0	<b>3.1</b>
cis-1,3-dichloropropene		< 4.0	< 1.0	< 1.0	< 1.0
Dibromochloromethane		< 4.0	< 1.0	< 1.0	< 1.0
Ethylbenzene		< 4.0	< 1.0	< 1.0	< 1.0
Methylene Chloride		< 8.0	< 2.0	< 2.0	< 2.0
Styrene		< 4.0	< 1.0	< 1.0	< 1.0
Tetrachloroethene		<b>24</b>	<b>29</b>	< 1.0	<b>23</b>
Toluene		< 4.0	< 1.0	< 1.0	< 1.0
trans-1,2-dichloroethene		< 4.0	< 1.0	< 1.0	< 1.0
trans-1,3-dichloropropene		< 4.0	< 1.0	< 1.0	< 1.0
Trichloroethylene		<b>615</b>	<b>487</b>	<b>3.0</b>	<b>129</b>
Trichlorotrifluoroethane (Freon 113)		< 20	<b>2.1 J</b>	< 5.0	<b>4.2 J</b>
Vinyl Chloride		< 4.0	<b>7.6</b>	< 1.0	< 1.0
Xylene-o		< 4.0	< 1.0	< 1.0	< 1.0
Xylenes - m,p		< 4.0	< 1.0	< 1.0	< 1.0
<b>Total VOCs<sup>(3)</sup></b>		<b>650</b>	<b>540</b>	<b>3.0</b>	<b>160</b>
<b>1,4-Dioxane<sup>(1,2)</sup></b>		<b>6.30</b>	<b>13.5</b>	<b>2.64</b>	<b>4.18</b>

Notes and abbreviations on last page.

**Table 2**  
**Concentrations of Constituents in Remedial Wells and**  
**Treatment System Effluents, Second Quarter 2016, Operable Unit 2,**  
**Northrop Grumman Systems Corporation,**  
**Bethpage, New York**

Constituents (units in µg/L)	Well 18 Well 18 5/12/2016	WELL 18 REP-051216-KV-1 5/12/2016	WELL 19 WELL 19 5/12/2016	102 EFFLUENT T102 EFFLUENT (GW) 5/12/2016
<b><u>Volatile Organic Compounds (VOCs)<sup>(1,2)</sup></u></b>				
1,1,1-Trichloroethane	0.64 J	0.54 J	0.35 J	< 1.0
1,1,2,2-Tetrachloroethane	< 1.0	< 1.0	< 1.0	< 1.0
1,1,2-Trichloroethane	< 1.0	< 1.0	< 1.0	< 1.0
1,1-Dichloroethane	1.3	1.2	0.75 J	< 1.0
1,1-Dichloroethene	3.3	1.5	1.3	< 1.0
1,2-Dichloroethane	< 1.0	< 1.0	< 1.0	< 1.0
1,2-Dichloropropane	< 1.0	< 1.0	< 1.0	< 1.0
2-Butanone (MEK)	< 10	< 10	< 10	< 10
2-Hexanone (MBK)	< 5.0	< 5.0	< 5.0	< 5.0
4-methyl-2-pentanone (MIK)	< 5.0	< 5.0	< 5.0	< 5.0
Acetone	< 10	< 10	< 10	< 10
Benzene	< 0.50	< 0.50	< 0.50	< 0.50
Bromodichloromethane	< 1.0	< 1.0	< 1.0	< 1.0
Bromoform	< 1.0	< 1.0	< 1.0	< 1.0
Bromomethane	< 2.0	< 2.0	< 2.0	< 2.0
Carbon Disulfide	< 2.0	< 2.0	< 2.0	< 2.0
Carbon tetrachloride	< 1.0	< 1.0	< 1.0	< 1.0
Chlorobenzene	< 1.0	< 1.0	< 1.0	< 1.0
Chloroethane	< 1.0	< 1.0	< 1.0	< 1.0
Chloroform	< 1.0	< 1.0	0.42 J	< 1.0
Chloromethane	< 1.0	< 1.0	< 1.0	< 1.0
cis-1,2-dichloroethene	2.1	2.1	18	< 1.0
cis-1,3-dichloropropene	< 1.0	< 1.0	< 1.0	< 1.0
Dibromochloromethane	< 1.0	< 1.0	< 1.0	< 1.0
Ethylbenzene	< 1.0	< 1.0	< 1.0	< 1.0
Methylene Chloride	< 2.0	< 2.0	< 2.0	< 2.0
Styrene	< 1.0	< 1.0	< 1.0	< 1.0
Tetrachloroethene	12	12	6.2	< 1.0
Toluene	< 1.0	< 1.0	< 1.0	< 1.0
trans-1,2-dichloroethene	< 1.0	< 1.0	< 1.0	< 1.0
trans-1,3-dichloropropene	< 1.0	< 1.0	< 1.0	< 1.0
Trichloroethylene	47	46	129	< 1.0
Trichlorotrifluoroethane (Freon 113)	1.8 J	1.7 J	< 5.0	< 5.0
Vinyl Chloride	< 1.0	< 1.0	< 1.0	< 1.0
Xylene-o	< 1.0	< 1.0	< 1.0	< 1.0
Xylenes - m,p	< 1.0	< 1.0	< 1.0	< 1.0
<b>Total VOCs<sup>(3)</sup></b>	<b>68</b>	<b>65</b>	<b>160</b>	<b>0</b>
<b>1,4-Dioxane<sup>(1,2)</sup></b>	<b>4.57</b>	<b>2.53</b>	<b>4.36</b>	<b>3.58</b>

Notes and abbreviations on last page.

**Table 2**  
**Concentrations of Constituents in Remedial Wells and Treatment System Effluents, Second Quarter 2016, Operable Unit 2, Northrop Grumman Systems Corporation, Bethpage, New York**

**Notes and Abbreviations:**

- (1) VOC samples analyzed using USEPA Method 8260C. 1,4-Dioxane samples analyzed using USEPA Method 8270 SIM.
- (2) Results for the program are validated at 20% frequency, per protocols specified in OU2 Groundwater Monitoring Plan (Arcadis 2016).
- (3) Total VOC results rounded to two significant figures.
  
- 2.4** Bold value indicates a detection.
- < 5.0 Compound is not detected above its laboratory quantification limit.
- µg/L micrograms per liter
- J Constituent value is estimated.
- NYSDEC New York State Department of Conservation
- REP blind replicate sample
- SIM selective ion monitoring
- VOC volatile organic compounds

**Table 3**  
**Vapor Sample Analytical Results for Treatment Systems,**  
**Second Quarter 2016, Northrop Grumman Systems Corporation,**  
**Operable Unit 2, Bethpage, New York**

Constituents (Units in µg/m <sup>3</sup> )	Location ID:	96 INFLUENT	96 MID-EFFLUENT	96 EFFLUENT	102 INFLUENT	102 EFFLUENT
	Sample ID:	T96 INFLUENT	T96 MIDTRAIN	T96 EFFLUENT	T102 INFLUENT	T102 EFFLUENT
	Date:	(AA)	(AA)	(AA)	(AA)	(AA)
		5/12/2016	5/12/2016	5/12/2016	5/12/2016	5/12/2016
<b><u>Volatile Organic Compounds (VOCs)<sup>(1)</sup></u></b>						
1,1,1-Trichloroethane		31	13	< 0.55	9.8	< 0.55
1,1,2,2-Tetrachloroethane		< 0.69	< 0.69	< 0.69	< 0.69	< 0.69
1,1,2-Trichloroethane		2.9	0.60	< 0.55	1.0	< 0.55
1,1-Dichloroethane		58	49	< 0.81	32	7.7
1,1-Dichloroethylene		139	161	0.56	73	33
1,2-Dichloroethane		2.8	1.4	< 0.81	2.5	< 0.81
1,2-Dichloropropane		101	26	< 0.92	2.2	< 0.92
Benzene		2.6	0.70	0.24	0.73	< 0.64
Bromodichloromethane		< 0.67	< 0.67	< 0.67	< 0.67	< 0.67
Bromoform		< 0.41	< 0.41	< 0.41	< 0.41	< 0.41
Bromomethane		< 0.78	< 0.78	< 0.78	< 0.78	< 0.78
Carbon disulfide		< 0.62	< 0.62	< 0.62	< 0.62	< 0.62
Carbon tetrachloride		6.0	2.5	< 0.25	3.0	< 0.25
Chlorobenzene		3.4	0.46	< 0.92	< 0.92	< 0.92
Chloroethane		7.7	8.4	6.9	< 0.53	< 0.53
Chloroform		13	9.3	< 0.98	11	1.6
Chloromethane		1.1	0.99	3.9	1.3	1.0
cis-1,3-Dichloropropene		< 0.91	< 0.91	< 0.91	< 0.91	< 0.91
Dibromochloromethane		< 0.85	< 0.85	< 0.85	< 0.85	< 0.85
Ethylbenzene		< 0.87	< 0.87	< 0.87	< 0.87	< 0.87
Methylene chloride		1.7	1.4	19	2.4	11
Styrene		< 0.85	< 0.85	< 0.85	< 0.85	< 0.85
Tetrachloroethylene		1,230	224	1.4	327	5.2
Toluene		1.0	< 0.75	0.36	1.7	< 0.75
trans-1,3-Dichloropropene		< 0.91	< 0.91	< 0.91	< 0.91	< 0.91
Trichloroethylene		23,600	6,660	15	2,340	83
Trichlorotrifluoroethane (Freon 113)		205	132	< 0.77	61	6.7
Vinyl chloride		132	164	0.79	0.23	< 0.10
Xylene-o		0.61	< 0.87	< 0.87	< 0.87	< 0.87
Xylenes - m,p		< 0.87	< 0.87	0.48	0.78	< 0.87
<b>Total VOCs <sup>(2)</sup></b>		<b>25,539</b>	<b>7,455</b>	<b>49</b>	<b>2,870</b>	<b>150</b>

Notes and abbreviations on last page.



**Table 3**  
**Vapor Sample Analytical Results for Treatment Systems,**  
**Second Quarter 2016, Northrop Grumman Systems Corporation,**  
**Operable Unit 2, Bethpage, New York**

**Notes and Abbreviations:**

- (1) Vapor samples collected by ARCADIS on the dates shown and submitted to a NYSDOH ELAP certified laboratory for VOC analyses per Modified USEPA Method TO-15.
- (2) "Total VOCs" represents the sum of individual concentrations of compounds detected rounded to the nearest whole number.

<b>24</b>	Bold data indicates that the analyte was detected at or above its reporting limit.
D	Concentration is based on a diluted sample analysis.
ELAP	Environmental Laboratory Approval Program
J	Compound detected below its reporting limit; value is estimated.
NYSDOH	New York State Department of Health
USEPA	United States Environmental Protection Agency
VOC	volatile organic compound
µg/m <sup>3</sup>	micrograms per cubic meter

**Table 4A**  
**Summary of SCREEN3 Model Input and Outputs**  
**Tower 96 Treatment System, Operable Unit 2,**  
**Northrop Grumman Systems Corporation,**  
**Bethpage, New York**

Parameters	Date Sampled:	9/9/2015	12/15/2015	3/14/2016	5/12/2016
<b>SCREEN3 Model Input</b>					
Source Type		Point	Point	Point	Point
Emission Rate (g/s)		1	1	1	1
Stack Height (ft)		55	55	55	55
Stack Height (m)		16.8	16.8	16.8	16.8
Stack Inside Diameter (m)		0.508	0.508	0.508	0.508
Air Flow Rate (scfm@stack temp) <sup>(1)</sup>		4,581	4,610	4,631	4,584
Air Flow Rate (acfm) <sup>(2), (3)</sup>		4,840	4,810	4,800	4,826
Stack Gas Exit Temperature (K) <sup>(2)</sup>		311	307	305	310
Ambient Air Temperature (K) <sup>(4)</sup>		293	275	277	287
Receptor Height (m) <sup>(5)</sup>		1.5	1.5	1.5	1.5
Urban/Rural		Urban	Urban	Urban	Urban
Building Height (m)		6.7	6.7	6.7	6.7
Min Horizontal Bldg Dim (m)		9.8	9.8	9.8	9.8
Max Horizontal Bldg Dim (m)		12.8	12.8	12.8	12.8
Consider Bldg Downwash?		Yes	Yes	Yes	Yes
Simple/Complex Terrain Above Stack		Simple	Simple	Simple	Simple
Simple/Complex Terrain Above Stack Base		Simple	Simple	Simple	Simple
Meteorology		Full	Full	Full	Full
Automated Distances Array		Yes	Yes	Yes	Yes
Terrain Height Above Stack Base		0	0	0	0
<b>SCREEN3 Model Output</b>					
1-HR Max Concentration at Receptor Height ( $\mu\text{g}/\text{m}^3$ ) <sup>(6)</sup>		199	196	198	190
Annualization Factor <sup>(7)</sup>		0.08	0.08	0.08	0.08
Average Annual Concentration at Receptor Height ( $\mu\text{g}/\text{m}^3$ ) <sup>(8)</sup>		15.9	15.7	15.8	15.2
Distance To Max Concentration (m) <sup>(9)</sup>		109	110	110	112

Notes and abbreviations on last page.

**Table 4A**  
**Summary of SCREEN3 Model Input and Outputs**  
**Tower 96 Treatment System, Operable Unit 2,**  
**Northrop Grumman Systems Corporation,**  
**Bethpage, New York**

**Notes and Abbreviations:**

- (1) The stack air flow rate at the stack temperature (in scfm) was calculated by multiplying the stack air flow rate in acfm by the ratio of the standard temperature to the actual stack gas exit temperature in degrees Kelvin.
- (2) The stack air flow rate (in acfm) and temperature were measured using inline instrumentation. Values were measured at the blower effluent location.
- (3) The stack air flow rate is taken from the actual stack air flow rate on the day of sampling.
- (4) The ambient temperature was recorded from wunderground.com website for Islip, New York. The mean average temperature from the website was used in the model calculation.
- (5) The receptor height corresponds to the average inhalation level.
- (6) SCREEN3 calculated constituent concentration at listed conditions at the specified inhalation level.
- (7) A USEPA time averaging conversion factor of 1/0.08 was used to convert the 1-hour maximum concentration output to an annual average.
- (8) Average annual constituent concentration at the receptor height was calculated by multiplying the one hour maximum concentration by the annualization
- (9) SCREEN3 calculated distance to the 1-hour maximum concentration.

µg/m <sup>3</sup>	micrograms per cubic meter
acfm	actual cubic feet per minute
ft	feet
g/s	grams per second
K	Kelvin
m	meters
scfm	standard cubic feet per minute
USEPA	United States Environmental Protection Agency

**Table 4B**  
**Summary of Air Emissions Model Output**  
**Tower 96 Treatment System, Operable Unit 2,**  
**Northrop Grumman Systems Corporation,**  
**Bethpage, New York**

Compound	SCG <sup>(1)</sup> (µg/m <sup>3</sup> )	Actual Effluent Concentrations <sup>(2)</sup> (µg/m <sup>3</sup> )			
		9/9/2015	12/15/2015	3/14/2016	5/12/2016
1,1-Dichloroethane	95,000 <sup>(3)</sup>	<b>34</b>	<b>5.3</b>	<b>4.5</b>	0
1,1-Dichloroethene	19,800 <sup>(3)</sup>	<b>60.7</b>	<b>56.7</b>	<b>21</b>	<b>0.56</b>
Benzene	1,300	0	0	0	<b>0.24</b>
Chloroethane	619,000 <sup>(3)</sup>	<b>13</b>	<b>8.2</b>	<b>7.4</b>	<b>6.9</b>
Chloroform	150	<b>2.5</b>	0	0	0
Chloromethane	22,000	<b>1.6</b>	<b>2.7</b>	<b>2.7</b>	<b>3.9</b>
Methylene Chloride	14,000	<b>1.7</b>	<b>0.87</b>	<b>2.3</b>	<b>19</b>
Tetrachloroethene	300	<b>0.37</b>	<b>0.61</b>	<b>1.2</b>	<b>1.4</b>
Toluene	37,000	0	0	0	<b>0.36</b>
Trichloroethene	14,000	<b>3.8</b>	<b>9.7</b>	<b>9.1</b>	<b>15</b>
Trichlorotrifluoroethane (Freon 113)	960,000	<b>2.6</b>	0	0	0
Vinyl chloride	180,000	<b>28.4</b>	<b>44.5</b>	<b>1.4</b>	<b>0.79</b>
Xylenes-m&p		0	0	0	<b>0.48</b>

Notes and abbreviations on last page.

**Table 4B**  
**Summary of Air Emissions Model Output**  
**Tower 96 Treatment System, Operable Unit 2,**  
**Northrop Grumman Systems Corporation,**  
**Bethpage, New York**

Compound	AGC <sup>(4)</sup> ( $\mu\text{g}/\text{m}^3$ )	Annual MASC <sup>(5)</sup> ( $\mu\text{g}/\text{m}^3$ )			
		9/9/2015	12/15/2015	3/14/2016	5/12/2016
1,1-Dichloroethane	0.63	1.73E+04	1.77E+04	1.76E+04	1.82E+04
1,1-Dichloroethene	200	5.51E+06	5.61E+06	5.59E+06	5.78E+06
Benzene	0.13	3.58E+03	3.65E+03	3.63E+03	3.76E+03
Chloroethane	10,000	2.75E+08	2.81E+08	2.79E+08	2.89E+08
Chloroform	14.7	4.05E+05	4.12E+05	4.11E+05	4.25E+05
Chloromethane	90	2.48E+06	2.53E+06	2.51E+06	2.60E+06
Methylene Chloride	60	1.65E+06	1.68E+06	1.68E+06	1.73E+06
Tetrachloroethene	4	1.10E+05	1.12E+05	1.12E+05	1.16E+05
Toluene	5,000	1.38E+08	1.40E+08	1.40E+08	1.44E+08
Trichloroethene	0.2	5.51E+03	5.61E+03	5.59E+03	5.78E+03
Trichlorotrifluoroethane (Freon 113)	180,000	4.96E+09	5.05E+09	5.03E+09	5.20E+09
Vinyl chloride	0.068	1.87E+03	1.91E+03	1.90E+03	1.96E+03
Xylenes-m&p	100	2.75E+06	2.81E+06	2.79E+06	2.89E+06

Notes and abbreviations on last page.

**Table 4B**  
**Summary of Air Emissions Model Output**  
**Tower 96 Treatment System, Operable Unit 2,**  
**Northrop Grumman Systems Corporation,**  
**Bethpage, New York**

Compound	AGC <sup>(4)</sup> (µg/m <sup>3</sup> )	Percent of Annual MASC <sup>(6)</sup>				Cumulative % MASC <sup>(7)</sup>
		9/9/2015	12/15/2015	3/14/2016	5/12/2016	
1,1-Dichloroethane	0.63	0.20%	0.03%	0.03%	0.00%	0.08%
1,1-Dichloroethene	200	0.0%	0.0%	0.0%	0.0%	0.00%
Benzene	0.13	0.0%	0.0%	0.0%	0.0%	0.00%
Chloroethane	10,000	0.0%	0.0%	0.0%	0.0%	0.00%
Chloroform	14.7	0.0%	0.0%	0.0%	0.0%	0.00%
Chloromethane	90	0.0%	0.0%	0.0%	0.0%	0.00%
Methylene Chloride	60	0.0%	0.0%	0.0%	0.0%	0.00%
Tetrachloroethene	4	0.0%	0.0%	0.0%	0.0%	0.00%
Toluene	5,000	0.0%	0.0%	0.0%	0.0%	0.00%
Trichloroethene	0.2	0.07%	0.17%	0.16%	0.26%	0.15%
Trichlorotrifluoroethane (Freon 113)	180,000	0.0%	0.0%	0.0%	0.0%	0.00%
Vinyl chloride	0.068	1.52%	2.33%	0.07%	0.04%	1.14%
Xylenes-m&p	100	0.00%	0.00%	0.00%	0.00%	0.00%

Notes and abbreviations on last page.

**Table 4B**  
**Summary of Air Emissions Model Output**  
**Tower 96 Treatment System, Operable Unit 2,**  
**Northrop Grumman Systems Corporation,**  
**Bethpage, New York**

**Notes and Abbreviations:**

- (1) Refers to the compound-specific SGC per the NYSDEC DAR-1 AGC/SGC tables revised February 28, 2014.
- (2) Only VOCs that were detected in the effluent vapor sample (T96 EFF) over the past year of system operation are included in this table.
- (3) An SGC was not provided in the DAR-1 AGC/SGC Tables, dated February 28, 2014. An interim SGC was developed based on guidelines provided in Section IV.A.2.b.1 of the NYSDEC DAR-1 Guidelines for the Control of Toxic Ambient Air Contaminants, 1991 edition.
- (4) AGC refers to the compound-specific annual guideline concentration per the NYSDEC DAR-1 AGC/SGC tables, revised February 28, 2014. NYSDEC DAR-1 AGCs were scaled using the results of a site-specific annual USEPA SCREEN 3 model to calculate the annual MASC per monitoring event.
- (5) Annual MASC was calculated by dividing the product of the AGC of a compound and the ratio of the SCREEN3 gas emission rate and the SCREEN 3 average annual concentration at receptor height by the air flow rate at the stack temperature and multiplying by the appropriate conversion factors.
- (6) Percent of MASC was calculated by dividing the actual effluent concentration by the MASC for the past four quarters of operation. Percentages have been rounded to two digits.
- (7) Cumulative percent of the MASC was calculated using a time-weighted average of the percent MASC per event. Percentages have been rounded to two digits.

$\mu\text{g}/\text{m}^3$	micrograms per cubic meter
0.57	bold value indicates a detection
AGC	annual guideline concentration
DAR-1	Division of Air Resources-1
MASC	maximum allowable stack concentration
NYSDEC	New York State Department of Environmental Conservation
SGC	short-term guideline concentration

**Table 5A**  
**Summary of SCREEN3 Model Input and Outputs**  
**Tower 102 Treatment System, Operable Unit 2,**  
**Northrop Grumman Systems Corporation,**  
**Bethpage, New York**

Parameters	Date Sampled:	9/9/2015	12/14/2015	3/14/2016	5/12/2016
<b>SCREEN3 Model Input</b>					
Source Type		Point	Point	Point	Point
Emission Rate (g/s)		1	1	1	1
Stack Height (ft)		69.52	69.52	69.52	69.52
Stack Height (m)		21.19	21.19	21.19	21.19
Stack Inside Diameter (m)		0.61	0.61	0.61	0.61
Air Flow Rate (scfm@stack temp) <sup>(1)</sup>		7,930	7,655	7,873	7,750
Air Flow Rate (acfm) <sup>(2), (3)</sup>		8,080	7,800	8,000	7,928
Stack Gas Exit Temperature (K) <sup>(2)</sup>		300	300	299	301
Ambient Air Temperature (K) <sup>(4)</sup>		293	275	277	288
Receptor Height (m) <sup>(5)</sup>		1.5	1.5	1.5	1.5
Urban/Rural		Urban	Urban	Urban	Urban
Building Height (m)		7.62	7.62	7.62	7.62
Min Horizontal Bldg Dim (m)		12.5	12.5	12.5	12.5
Max Horizontal Bldg Dim (m)		15.54	15.54	15.54	15.54
Consider Bldg Downwash?		Yes	Yes	Yes	Yes
Simple/Complex Terrain Above Stack		Simple	Simple	Simple	Simple
Simple/Complex Terrain Above Stack Base		Simple	Simple	Simple	Simple
Meteorology		Full	Full	Full	Full
Automated Distances Array		Yes	Yes	Yes	Yes
Terrain Height Above Stack Base		0	0	0	0
<b>SCREEN3 Model Output</b>					
1-HR Max Concentration at Receptor Height ( $\mu\text{g}/\text{m}^3$ ) <sup>(6)</sup>		111	114	111	111
Annualization Factor <sup>(7)</sup>		0.08	0.08	0.08	0.08
Average Annual Concentration at Receptor Height ( $\mu\text{g}/\text{m}^3$ ) <sup>(8)</sup>		8.8	9.1	8.9	8.8
Distance To Max Concentration (m) <sup>(9)</sup>		144	142	143	144

Notes and abbreviations on last page.



**Table 5A**  
**Summary of SCREEN3 Model Input and Outputs**  
**Tower 102 Treatment System, Operable Unit 2,**  
**Northrop Grumman Systems Corporation,**  
**Bethpage, New York**

**Notes and Abbreviations:**

- (1) The stack air flow rate at the stack temperature (in scfm) was calculated by multiplying the stack air flow rate in acfm by the ratio of the standard temperature to the actual stack gas exit temperature in degrees Kelvin.
- (2) The stack air flow rate (in acfm) and temperature were measured using inline instrumentation. Values were measured at the blower effluent location.
- (3) The stack air flow rate is taken from the actual stack air flow rate on the day of sampling.
- (4) The ambient temperature was recorded from wunderground.com website for Islip, New York. The mean actual temperature from the website was used in the model calculation.
- (5) The receptor height corresponds to the average inhalation level.
- (6) SCREEN3 calculated constituent concentration at listed conditions at the specified inhalation level.
- (7) A USEPA time averaging conversion factor of 1/0.08 was used to convert the 1-hour maximum concentration output to an annual average.
- (8) Average annual constituent concentration at the receptor height was calculated by multiplying the one hour maximum concentration by the annualization
- (9) SCREEN3 calculated distance to the 1-hour maximum concentration.

µg/m <sup>3</sup>	micrograms per cubic meter
acfm	actual cubic feet per minute
ft	feet
g/s	grams per second
K	Kelvin
m	meters
scfm	standard cubic feet per minute
USEPA	United States Environmental Protection Agency

**Table 5B**  
**Summary of Air Emissions Model Output,**  
**Tower 102 Treatment System, Opearable Unit 2**  
**Northrop Grumman Systems Corporation,**  
**Bethpage, New York**

Compound	SCG <sup>(1)</sup> (µg/m <sup>3</sup> )	Actual Effluent Concentrations <sup>(2)</sup> (µg/m <sup>3</sup> )			
		9/9/2015	12/14/2015	3/14/2016	5/12/2016
1,1-Dichloroethane	95,000 <sup>(3)</sup>	<b>8.1</b>	<b>1.1</b>	<b>6.1</b>	<b>7.7</b>
1,1-Dichloroethene	19,800 <sup>(3)</sup>	<b>35</b>	<b>4.4</b>	<b>28</b>	<b>33</b>
Benzene	1,300	<b>0.51</b>	0	0	0
Carbon Disulfide	6,200	0	0	<b>0.50</b>	0
Chloroform	150	<b>1.6</b>	0	<b>1.0</b>	<b>1.6</b>
Chloromethane	22,000	<b>1.3</b>	<b>0.74</b>	<b>1.3</b>	<b>1.0</b>
Ethylbenzene	20,700 <sup>(3)</sup>	<b>0.69</b>	0	0	0
Methylene Chloride	14,000	<b>1.5</b>	<b>3.1</b>	0	<b>11</b>
Tetrachloroethene	300	<b>3.7</b>	0	<b>1.8</b>	<b>5.2</b>
Toluene	37,000	<b>21</b>	0	0	0
Trichloroethene	14,000	<b>12</b>	<b>4.9</b>	<b>31</b>	<b>83</b>
Trichlorotrifluoroethane (Freon 113)	960,000	<b>7.7</b>	0	<b>7.4</b>	<b>6.7</b>
Vinyl Chloride	180,000	0	0	<b>0.54</b>	0
Xylene-m,p	22,000	<b>1.9</b>	0	0	0
Xylene-o	22,000	<b>0.56</b>	0	0	0

Notes and abbreviations on last page.

**Table 5B**  
**Summary of Air Emissions Model Output,**  
**Tower 102 Treatment System, Opearable Unit 2**  
**Northrop Grumman Systems Corporation,**  
**Bethpage, New York**

Compound	AGC <sup>(4)</sup> (µg/m <sup>3</sup> )	Annual MASC <sup>(5)</sup> (µg/m <sup>3</sup> )			
		9/9/2015	12/14/2015	3/14/2016	5/12/2016
1,1-Dichloroethane	0.63	1.88E+04	1.88E+04	1.87E+04	1.91E+04
1,1-Dichloroethene	200	5.96E+06	5.97E+06	5.95E+06	6.07E+06
Benzene	0.13	3.87E+03	3.88E+03	3.87E+03	3.95E+03
Carbon Disulfide	700	2.09E+07	2.09E+07	2.08E+07	2.13E+07
Chloroform	14.7	4.38E+05	4.39E+05	4.37E+05	4.46E+05
Chloromethane	90	2.68E+06	2.69E+06	2.68E+06	2.73E+06
Ethylbenzene	1,000	2.98E+07	2.99E+07	2.98E+07	3.04E+07
Methylene Chloride	60	1.79E+06	1.79E+06	1.79E+06	1.82E+06
Tetrachloroethene	4	1.19E+05	1.19E+05	1.19E+05	1.21E+05
Toluene	5,000	1.49E+08	1.49E+08	1.49E+08	1.52E+08
Trichloroethene	0.2	5.96E+03	5.97E+03	5.95E+03	6.07E+03
Trichlorotrifluoroethane (Freon 113)	180,000	5.36E+09	5.37E+09	5.36E+09	5.47E+09
Vinyl Chloride	0.068	2.03E+03	2.03E+03	2.02E+03	2.07E+03
Xylene-m,p	100	2.98E+06	2.99E+06	2.98E+06	3.04E+06
Xylene-o	100	2.98E+06	2.99E+06	2.98E+06	3.04E+06

Notes and abbreviations on last page.

**Table 5B**  
**Summary of Air Emissions Model Output,**  
**Tower 102 Treatment System, Opearable Unit 2**  
**Northrop Grumman Systems Corporation,**  
**Bethpage, New York**

Compound	AGC <sup>(4)</sup> (µg/m <sup>3</sup> )	Percent of Annual MASC <sup>(6)</sup>				Cumulative % MASC <sup>(7)</sup>
		9/9/2015	12/14/2015	3/14/2016	5/12/2016	
1,1-Dichloroethane	0.63	0.04%	0.01%	0.03%	0.04%	0.03%
1,1-Dichloroethene	200	0.0%	0.0%	0.0%	0.0%	0.0%
Benzene	0.13	0.01%	0.0%	0.0%	0.0%	0.0%
Carbon Disulfide	700	0.0%	0.0%	0.0%	0.0%	0.0%
Chloroform	14.7	0.0%	0.0%	0.0%	0.0%	0.0%
Chloromethane	90	0.0%	0.0%	0.0%	0.0%	0.0%
Ethylbenzene	1,000	0.0%	0.0%	0.0%	0.0%	0.0%
Methylene Chloride	60	0.0%	0.0%	0.0%	0.0%	0.0%
Tetrachloroethene	4	0.0%	0.0%	0.0%	0.0%	0.0%
Toluene	5,000	0.0%	0.0%	0.0%	0.0%	0.0%
Trichloroethene	0.2	0.20%	0.1%	0.52%	1.37%	0.4%
Trichlorotrifluoroethane (Freon 113)	180,000	0.0%	0.0%	0.0%	0.0%	0.0%
Vinyl Chloride	0.068	0.0%	0.0%	0.03%	0.00%	0.0%
Xylene-m,p	100	0.0%	0.0%	0.0%	0.0%	0.0%
Xylene-o	100	0.0%	0.0%	0.0%	0.0%	0.0%

Notes and abbreviations on last page.

**Table 5B**  
**Summary of Air Emissions Model Output,**  
**Tower 102 Treatment System, Opearable Unit 2**  
**Northrop Grumman Systems Corporation,**  
**Bethpage, New York**

**Notes and Abbreviations:**

- (1) Refers to the compound-specific SGC per the NYSDEC DAR-1 AGC/SGC tables revised February 28, 2014.
- (2) Only VOCs that were detected in the effluent vapor sample (T102 EFF) over the past year of system operation are included in this table.
- (3) An SGC was not provided in the DAR-1 AGC/SGC Tables, dated February 28, 2014. An interim SGC was developed based on guidelines provided in Section IV.A.2.b.1 of the NYSDEC DAR-1 Guidelines for the Control of Toxic Ambient Air Contaminants, 1991 edition.
- (4) AGC refers to the compound-specific annual guideline concentration per the NYSDEC DAR-1 AGC/SGC tables, revised February 28, 2014. NYSDEC DAR-1 AGCs were scaled using the results of a site-specific annual USEPA SCREEN 3 model to calculate the annual MASC per monitoring event.
- (5) Annual MASC was calculated by dividing the product of the AGC of a compound and the ratio of the SCREEN3 gas emission rate and the SCREEN 3 average annual concentration at receptor height by the air flow rate at the stack temperature and multiplying by the appropriate conversion factors.
- (6) Percent of MASC was calculated by dividing the actual effluent concentration by the MASC for the past four quarters of operation. Percentages have been rounded to two digits.
- (7) Cumulative percent of the MASC was calculated using a time-weighted average of the percent MASC per event. Percentages have been rounded to two digits.

$\mu\text{g}/\text{m}^3$	micrograms per cubic meter
<b>0.55</b>	Bold value indicates a detection
--	Compound not reported, unable to compute MASC
AGC	annual guideline concentration
DAR-1	Division of Air Resources-1
MASC	maximum allowable stack concentration
NYSDEC	New York State Department of Environmental Conservation
SCG	short-term guideline concentration

**Table 6**  
**Concentrations of Volatile Organic Compounds**  
**and 1,4 Dioxane in Monitoring Wells,**  
**Second Quarter 2016, Operable Unit 2,**  
**Northrop Grumman Systems Corporation,**  
**Bethpage, New York**

Constituent (units in µg/L)	Well: Sample ID: Date:	FW-03 FW-03 4/27/2016	GM-13D GM-13D 5/11/2016	GM-15SR GM-15S 4/13/2016	GM-15I GM15I 6/30/2016	GM-15D GM15D 6/30/2016	GM-15D2 GM15D2 4/13/2016
<b>Volatile Organic Compounds (VOCs)<sup>(1,2)</sup></b>							
1,1,1-Trichloroethane		<1.0	<b>1.1</b>	<1.0	<1.0	<1.0	<1.0
1,1,2,2-Tetrachloroethane		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
1,1,2-Trichloroethane		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
1,1-Dichloroethane		<1.0	<b>3.7</b>	<1.0	<1.0	<1.0	<b>0.23 J</b>
1,1-Dichloroethene		<1.0	<b>5.0</b>	<1.0	<1.0	<1.0	<b>0.56 J</b>
1,2-Dichloroethane		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
1,2-Dichloropropane		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
2-Butanone		<10	<10	<10	<10	<10	<10
4-methyl-2-pentanone		<5.0	<5.0	<5.0	<5.0	<5.0	<5.0
Acetone		<10	<10	<10	<10	<10	<10
Benzene		<0.50	<0.50	<0.50	<0.50	<0.50	<0.50
Bromodichloromethane		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
Bromoform		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
Bromomethane		<2.0	<2.0	<2.0	<2.0	<2.0	<2.0
Carbon Disulfide		<2.0	<2.0	<2.0	<2.0	<2.0	<2.0
Carbon tetrachloride		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
Chlorobenzene		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
Chloroethane		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
Chloroform		<1.0	<1.0	<1.0	<1.0	<1.0	<b>0.22 J</b>
Chloromethane		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
cis-1,2-dichloroethene		<1.0	<b>9.1</b>	<1.0	<1.0	<1.0	<1.0
cis-1,3-dichloropropene		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
Dibromochloromethane		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
Ethylbenzene		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
Methylene Chloride		<2.0	<2.0	<2.0	<2.0	<2.0	<2.0
Styrene		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
Tetrachloroethene		<b>4.4</b>	<b>100</b>	<1.0	<1.0	<b>0.28 J</b>	<b>5.6</b>
Toluene		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
trans-1,2-dichloroethene		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
trans-1,3-dichloropropene		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
Trichloroethylene		<b>2.2</b>	<b>39.6</b>	<b>2.7</b>	<b>3.1</b>	<1.0	<b>8.8</b>
Trichlorotrifluoroethane (Freon 113)		<5.0	<b>2.6 J</b>	<5.0	<5.0	<5.0	<b>0.83 J</b>
Vinyl Chloride		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
Xylene-o		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
Xylenes - m,p		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
<b>Total VOCs<sup>(3)</sup></b>		<b>6.6</b>	<b>160</b>	<b>2.7</b>	<b>3.1</b>	<b>0.28</b>	<b>16</b>
<b>1,4 Dioxane<sup>(1,2)</sup></b>		<b>0.156</b>	<b>2.98</b>	<b>1.21</b>	< 0.10	< 0.10	<b>3.50</b>

See notes on last page

**Table 6**  
**Concentrations of Volatile Organic Compounds**  
**and 1,4 Dioxane in Monitoring Wells,**  
**Second Quarter 2016, Operable Unit 2,**  
**Northrop Grumman Systems Corporation,**  
**Bethpage, New York**

Constituent (units in µg/L)	Well:	GM-17I	GM-17D	GM-18I	GM-18D	GM-20I	GM-20D
	Sample ID:	GM-17I	GM-17D	GM-18I	GM-18D	GM-20I	GM-20D
	Date:	5/2/2016	5/2/2016	6/14/2016	6/14/2016	6/14/2016	6/14/2016
<b>Volatile Organic Compounds (VOCs)<sup>(1,2)</sup></b>							
1,1,1-Trichloroethane		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
1,1,2,2-Tetrachloroethane		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
1,1,2-Trichloroethane		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
1,1-Dichloroethane		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
1,1-Dichloroethene		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
1,2-Dichloroethane		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
1,2-Dichloropropane		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
2-Butanone		<10	<10	<10	<10	<10	<10
4-methyl-2-pentanone		<5.0	<5.0	<5.0	<5.0	<5.0	<5.0
Acetone		<10	<10	<10	<10	<10	<10
Benzene		<0.50	<0.50	<0.50	<0.50	<0.50	<0.50
Bromodichloromethane		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
Bromoform		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
Bromomethane		<2.0	<2.0	<2.0	<2.0	<2.0	<2.0
Carbon Disulfide		<2.0	<2.0	<2.0	<2.0	<2.0	<2.0
Carbon tetrachloride		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
Chlorobenzene		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
Chloroethane		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
Chloroform		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
Chloromethane		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
cis-1,2-dichloroethene		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
cis-1,3-dichloropropene		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
Dibromochloromethane		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
Ethylbenzene		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
Methylene Chloride		<2.0	<2.0	<2.0	<2.0	<2.0	<2.0
Styrene		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
Tetrachloroethene		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
Toluene		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
trans-1,2-dichloroethene		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
trans-1,3-dichloropropene		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
Trichloroethylene		<b>0.65 J</b>	<b>0.61 J</b>	<b>0.56 J</b>	<b>0.39 J</b>	<b>0.85 J</b>	<b>0.94 J</b>
Trichlorotrifluoroethane (Freon 113)		<5.0	<5.0	<5.0	<5.0	<5.0	<5.0
Vinyl Chloride		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
Xylene-o		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
Xylenes - m,p		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
<b>Total VOCs<sup>(3)</sup></b>		<b>0.65</b>	<b>0.61</b>	<b>0.56</b>	<b>0.39</b>	<b>0.85</b>	<b>0.94</b>
<b>1,4 Dioxane<sup>(1,2)</sup></b>		<b>7.34</b>	<b>8.63</b>	<b>4.39</b>	<b>4.81</b>	<b>2.28</b>	<b>3.47</b>

See notes on last page

**Table 6**  
**Concentrations of Volatile Organic Compounds**  
**and 1,4 Dioxane in Monitoring Wells,**  
**Second Quarter 2016, Operable Unit 2,**  
**Northrop Grumman Systems Corporation,**  
**Bethpage, New York**

Constituent (units in µg/L)	Well:	GM-21S	GM-21I	GM-21D	GM-21D2	GM-33D2	GM-34D
	Sample ID:	GM-21S	GM-21I	GM-21D	GM-21D2	GM-33D2	GM-34D
	Date:	4/29/2016	6/17/2016	5/5/2016	5/5/2016	5/10/2016	4/27/2016
<b>Volatile Organic Compounds (VOCs)<sup>(1,2)</sup></b>							
1,1,1-Trichloroethane		<1.0	<1.0	<1.0	<b>0.92 J</b>	<1.0	<1.0
1,1,2,2-Tetrachloroethane		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
1,1,2-Trichloroethane		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
1,1-Dichloroethane		<1.0	<1.0	<1.0	<b>1.9</b>	<1.0	<b>0.69 J</b>
1,1-Dichloroethene		<1.0	<1.0	<1.0	<b>5.2</b>	<1.0	<b>3.4</b>
1,2-Dichloroethane		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
1,2-Dichloropropane		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
2-Butanone		<10	<10	<10	<10	<10	<10
4-methyl-2-pentanone		<5.0	<5.0	<5.0	<5.0	<5.0	<5.0
Acetone		<10	<10	<10	<10	<10	<10
Benzene		<0.50	<0.50	<0.50	<0.50	<0.50	<0.50
Bromodichloromethane		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
Bromoform		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
Bromomethane		<2.0	<2.0	<2.0	<2.0	<2.0	<2.0
Carbon Disulfide		<2.0	<2.0	<2.0	<2.0	<2.0	<2.0
Carbon tetrachloride		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
Chlorobenzene		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
Chloroethane		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
Chloroform		<1.0	<1.0	<1.0	<b>0.24 J</b>	<1.0	<b>0.59 J</b>
Chloromethane		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
cis-1,2-dichloroethene		<1.0	<1.0	<1.0	<b>5.4</b>	<1.0	<b>10</b>
cis-1,3-dichloropropene		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
Dibromochloromethane		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
Ethylbenzene		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
Methylene Chloride		<2.0	<2.0	<2.0	<2.0	<2.0	<2.0
Styrene		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
Tetrachloroethene		<1.0	<1.0	<1.0	<b>6.0</b>	<b>3.2</b>	<b>9.1</b>
Toluene		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
trans-1,2-dichloroethene		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
trans-1,3-dichloropropene		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
Trichloroethylene		<b>0.58 J</b>	<b>0.71 J</b>	<b>1.7</b>	<b>71.9</b>	<b>13.8</b>	<b>428</b>
Trichlorotrifluoroethane (Freon 113)		<5.0	<5.0	<5.0	<b>2.5 J</b>	<b>5.3</b>	<b>9.4</b>
Vinyl Chloride		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
Xylene-o		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
Xylenes - m,p		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
<b>Total VOCs<sup>(3)</sup></b>		<b>0.58</b>	<b>0.71</b>	<b>1.7</b>	<b>94</b>	<b>22</b>	<b>460</b>
<b>1,4 Dioxane<sup>(1,2)</sup></b>		<b>2.59</b>	<b>2.60</b>	<b>3.48</b>	<b>4.14</b>	<b>4.14</b>	<b>8.52</b>

See notes on last page



**Table 6**  
**Concentrations of Volatile Organic Compounds**  
**and 1,4 Dioxane in Monitoring Wells,**  
**Second Quarter 2016, Operable Unit 2,**  
**Northrop Grumman Systems Corporation,**  
**Bethpage, New York**

Constituent (units in µg/L)	Well:	GM-34D2	GM-35D2	GM-36D	GM-36D2	GM-37D	GM-37D2
	Sample ID:	GM-34D2	GM35D2	GM-36D	GM-36D2	GM-37D	GM-37D2
	Date:	4/27/2016	4/20/2016	5/9/2016	5/9/2016	4/14/2016	4/14/2016
<b>Volatile Organic Compounds (VOCs)<sup>(1,2)</sup></b>							
1,1,1-Trichloroethane		<1.0	<1.0	<1.0	<b>0.42 J</b>	<1.0	<b>0.67 J</b>
1,1,2,2-Tetrachloroethane		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
1,1,2-Trichloroethane		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
1,1-Dichloroethane		<1.0	<1.0	<1.0	<b>0.98 J</b>	<b>0.52 J</b>	<b>2.1</b>
1,1-Dichloroethene		<b>0.62 J</b>	<1.0	<1.0	<b>0.80 J</b>	<1.0	<b>0.95 J</b>
1,2-Dichloroethane		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
1,2-Dichloropropane		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
2-Butanone		<10	<10	<10	<10	<10	<10
4-methyl-2-pentanone		<5.0	<5.0	<5.0	<5.0	<5.0	<5.0
Acetone		<10	<10	<10	<10	<10	<10
Benzene		<0.50	<0.50	<0.50	<0.50	<0.50	<0.50
Bromodichloromethane		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
Bromoform		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
Bromomethane		<2.0	<2.0	<2.0	<2.0	<2.0	<2.0
Carbon Disulfide		<2.0	<2.0	<2.0	<2.0	<2.0	<2.0
Carbon tetrachloride		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
Chlorobenzene		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
Chloroethane		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
Chloroform		<1.0	<1.0	<b>0.56 J</b>	<b>0.27 J</b>	<1.0	<b>0.31 J</b>
Chloromethane		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
cis-1,2-dichloroethene		<b>2.5</b>	<b>0.34 J</b>	<1.0	<1.0	<1.0	<b>0.29 J</b>
cis-1,3-dichloropropene		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
Dibromochloromethane		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
Ethylbenzene		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
Methylene Chloride		<2.0	<2.0	<2.0	<2.0	<2.0	<2.0
Styrene		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
Tetrachloroethene		<b>6.9</b>	<b>5.7</b>	<1.0	<1.0	<1.0	<b>0.79 J</b>
Toluene		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
trans-1,2-dichloroethene		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
trans-1,3-dichloropropene		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
Trichloroethylene		<b>142</b>	<b>60</b>	<1.0	<b>2.7</b>	<b>1.1</b>	<b>2.8</b>
Trichlorotrifluoroethane (Freon 113)		<b>1.1 J</b>	<b>1.1 J</b>	<5.0	<5.0	<5.0	<5.0
Vinyl Chloride		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
Xylene-o		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
Xylenes - m,p		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
<b>Total VOCs<sup>(3)</sup></b>		<b>150</b>	<b>67</b>	<b>0.56</b>	<b>5.2</b>	<b>1.6</b>	<b>7.9</b>
<b>1,4 Dioxane<sup>(1,2)</sup></b>		<b>8.96</b>	<b>7.52</b>	<b>2.00 B</b>	<b>10.9 B</b>	<b>0.360</b>	<b>0.745</b>

See notes on last page

**Table 6**  
**Concentrations of Volatile Organic Compounds**  
**and 1,4 Dioxane in Monitoring Wells,**  
**Second Quarter 2016, Operable Unit 2,**  
**Northrop Grumman Systems Corporation,**  
**Bethpage, New York**

Constituent (units in µg/L)	Well:	REP041416MO1	GM-38D	GM-38D2	GM-39DA	GM-39DB	GM-70D2
	Sample ID:	GM-37D2	GM38D	GM38D2	GM-39DA	GM-39DB	GM-70D2
	Date:	4/14/2016	4/20/2016	4/20/2016	5/3/2016	5/3/2016	4/26/2016
<b>Volatile Organic Compounds (VOCs)<sup>(1,2)</sup></b>							
1,1,1-Trichloroethane		0.71 J	0.62 J	1.2	<1.0	<1.0	<1.0
1,1,2,2-Tetrachloroethane		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
1,1,2-Trichloroethane		<1.0	<1.0	0.48 J	<1.0	<1.0	<1.0
1,1-Dichloroethane		2.3	1.1	2.3	<1.0	<1.0	<1.0
1,1-Dichloroethene		0.98 J	1.0	2.1	<1.0	<1.0	<1.0
1,2-Dichloroethane		<1.0	0.40 J	<1.0	<1.0	<1.0	<1.0
1,2-Dichloropropane		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
2-Butanone		<10	<10	<10	<10	<10	<10
4-methyl-2-pentanone		<5.0	<5.0	<5.0	<5.0	<5.0	<5.0
Acetone		<10	<10	<10	<10	<10	<10
Benzene		<0.50	<0.50	<0.50	<0.50	<0.50	<0.50
Bromodichloromethane		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
Bromoform		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
Bromomethane		<2.0	<2.0	<2.0	<2.0	<2.0	<2.0
Carbon Disulfide		<2.0	<2.0	<2.0	<2.0	<2.0	<2.0
Carbon tetrachloride		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
Chlorobenzene		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
Chloroethane		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
Chloroform		0.33 J	0.26 J	0.43 J	<1.0	<1.0	<1.0
Chloromethane		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
cis-1,2-dichloroethene		0.28 J	0.68 J	2.3	<1.0	<1.0	<1.0
cis-1,3-dichloropropene		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
Dibromochloromethane		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
Ethylbenzene		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
Methylene Chloride		<2.0	<2.0	<2.0	<2.0	<2.0	<2.0
Styrene		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
Tetrachloroethene		0.80 J	4.2	<1.0	<1.0	<1.0	2.7
Toluene		<1.0	<1.0	<1.0	<1.0	<1.0	0.51 J
trans-1,2-dichloroethene		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
trans-1,3-dichloropropene		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
Trichloroethylene		3	111	202 D	6.1	21	8.9
Trichlorotrifluoroethane (Freon 113)		<5.0	<5.0	<5.0	<5.0	<5.0	<5.0
Vinyl Chloride		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
Xylene-o		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
Xylenes - m,p		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
<b>Total VOCs<sup>(3)</sup></b>		<b>8.4</b>	<b>120</b>	<b>210</b>	<b>6.1</b>	<b>21</b>	<b>12</b>
<b>1,4 Dioxane<sup>(1,2)</sup></b>		<b>0.720</b>	<b>1.70</b>	<b>2.22</b>	<b>3.01</b>	<b>2.99</b>	<b>4.62</b>

See notes on last page

**Table 6**  
**Concentrations of Volatile Organic Compounds**  
**and 1,4 Dioxane in Monitoring Wells,**  
**Second Quarter 2016, Operable Unit 2,**  
**Northrop Grumman Systems Corporation,**  
**Bethpage, New York**

Constituent (units in µg/L)	Well: Sample ID: Date:	GM-71D2 GM71D2 4/12/2016	GM-73D GM-73D 6/29/2016	GM-73D2 GM-73D2 5/6/2016	GM-73D3 GM-73D3 5/6/2016	GM-74I GM74I 4/13/2016	GM-74D GM-74D 4/13/2016
<b>Volatile Organic Compounds (VOCs)<sup>(1,2)</sup></b>							
1,1,1-Trichloroethane		2.2	<1.0	<1.0	<1.0	<1.0	<1.0
1,1,2,2-Tetrachloroethane		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
1,1,2-Trichloroethane		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
1,1-Dichloroethane		6.6	<1.0	0.43 J	<1.0	<1.0	<1.0
1,1-Dichloroethene		3.6	<1.0	0.65 J	<1.0	<1.0	<1.0
1,2-Dichloroethane		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
1,2-Dichloropropane		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
2-Butanone		<10	<10	<10	<10	<10	<10
4-methyl-2-pentanone		<5.0	<5.0	<5.0	<5.0	<5.0	<5.0
Acetone		<10	<10	<10	<10	<10	<10
Benzene		<0.50	<0.50	<0.50	<0.50	<0.50	<0.50
Bromodichloromethane		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
Bromoform		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
Bromomethane		<2.0	<2.0	<2.0	<2.0	<2.0	<2.0
Carbon Disulfide		<2.0	<2.0	<2.0	<2.0	<2.0	<2.0
Carbon tetrachloride		0.24 J	<1.0	<1.0	<1.0	<1.0	<1.0
Chlorobenzene		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
Chloroethane		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
Chloroform		0.60 J	<1.0	0.39 J	<1.0	<1.0	<1.0
Chloromethane		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
cis-1,2-dichloroethene		0.76 J	<1.0	0.51 J	<1.0	<1.0	<1.0
cis-1,3-dichloropropene		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
Dibromochloromethane		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
Ethylbenzene		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
Methylene Chloride		<2.0	<2.0	<2.0	<2.0	<2.0	<2.0
Styrene		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
Tetrachloroethene		<1.0	<1.0	1.8	0.70 J	<1.0	<1.0
Toluene		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
trans-1,2-dichloroethene		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
trans-1,3-dichloropropene		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
Trichloroethylene		12.5	7.9	33.2	1.6	0.62 J	1.2
Trichlorotrifluoroethane (Freon 113)		<5.0	<5.0	<5.0	<5.0	<5.0	<5.0
Vinyl Chloride		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
Xylene-o		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
Xylenes - m,p		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
<b>Total VOCs<sup>(3)</sup></b>		<b>27</b>	<b>7.9</b>	<b>37</b>	<b>2.3</b>	<b>0.62</b>	<b>1.2</b>
<b>1,4 Dioxane<sup>(1,2)</sup></b>		<b>1.32</b>	<b>3.42</b>	<b>3.08</b>	<b>0.667</b>	<b>5.33</b>	<b>4.37</b>

See notes on last page

**Table 6**  
**Concentrations of Volatile Organic Compounds**  
**and 1,4 Dioxane in Monitoring Wells,**  
**Second Quarter 2016, Operable Unit 2,**  
**Northrop Grumman Systems Corporation,**  
**Bethpage, New York**

Constituent (units in µg/L)	Well:	GM-74D2	GM-74D3	GM-75D2	GM-78S	GM-78I	GM-78D <sup>(2)</sup>
	Sample ID:	GM-74D2	GM-74D3	GM-75D2	GM-78S	GM-78I	GM-78D
	Date:	5/5/2016	5/5/2016	5/10/2016	4/28/2016	4/28/2016	5/3/2016
<b>Volatile Organic Compounds (VOCs)<sup>(1,2)</sup></b>							
1,1,1-Trichloroethane		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
1,1,2,2-Tetrachloroethane		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
1,1,2-Trichloroethane		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
1,1-Dichloroethane		<b>0.47 J</b>	<1.0	<1.0	<1.0	<1.0	<1.0
1,1-Dichloroethene		<b>0.75 J</b>	<b>0.41 J</b>	<1.0	<1.0	<1.0	<1.0
1,2-Dichloroethane		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
1,2-Dichloropropane		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
2-Butanone		<10	<10	<10	<10	<10	<10
4-methyl-2-pentanone		<5.0	<5.0	<5.0	<5.0	<5.0	<5.0
Acetone		<10	<10	<10	<10	<10	<10
Benzene		<0.50	<0.50	<0.50	<0.50	<0.50	<0.50
Bromodichloromethane		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
Bromoform		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
Bromomethane		<2.0	<2.0	<2.0	<2.0	<2.0	<2.0
Carbon Disulfide		<2.0	<2.0	<2.0	<2.0	<2.0	<2.0
Carbon tetrachloride		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
Chlorobenzene		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
Chloroethane		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
Chloroform		<b>0.30 J</b>	<1.0	<1.0	<1.0	<1.0	<1.0
Chloromethane		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
cis-1,2-dichloroethene		<b>0.32 J</b>	<b>0.35 J</b>	<1.0	<1.0	<1.0	<1.0
cis-1,3-dichloropropene		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
Dibromochloromethane		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
Ethylbenzene		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
Methylene Chloride		<2.0	<2.0	<2.0	<2.0	<2.0	<2.0
Styrene		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
Tetrachloroethene		<b>3.7</b>	<b>3.4</b>	<b>0.90 J</b>	<b>0.82</b>	<1.0	<1.0
Toluene		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
trans-1,2-dichloroethene		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
trans-1,3-dichloropropene		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
Trichloroethylene		<b>7.2</b>	<b>5.8</b>	<b>18.8</b>	<b>0.45 J</b>	<b>0.38 J</b>	<b>3.8</b>
Trichlorotrifluoroethane (Freon 113)		<b>0.67 J</b>	<b>0.65 J</b>	<5.0	<5.0	<5.0	<5.0
Vinyl Chloride		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
Xylene-o		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
Xylenes - m,p		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
<b>Total VOCs<sup>(3)</sup></b>		<b>13</b>	<b>11</b>	<b>20</b>	<b>1.3</b>	<b>0.38</b>	<b>3.8</b>
<b>1,4 Dioxane<sup>(1,2)</sup></b>		<b>2.34</b>	<b>1.89</b>	<b>2.85</b>	<b>3.08</b>	<b>2.42</b>	<b>4.75</b>

See notes on last page

**Table 6**  
**Concentrations of Volatile Organic Compounds**  
**and 1,4 Dioxane in Monitoring Wells,**  
**Second Quarter 2016, Operable Unit 2,**  
**Northrop Grumman Systems Corporation,**  
**Bethpage, New York**

Constituent (units in µg/L)	Well:	GM-78D2	GM-79I	GM-79D	HN-24I	HN-40S
	Sample ID:	GM-78D2	GM-79I	GM-79D	HN-24I	HN-40S
	Date:	5/3/2016	4/13/2016	4/13/2016	4/28/2016	4/13/2016
<b>Volatile Organic Compounds (VOCs)<sup>(1,2)</sup></b>						
1,1,1-Trichloroethane		<1.0	<1.0	<1.0	<b>0.87 J</b>	<1.0
1,1,2,2-Tetrachloroethane		<1.0	<1.0	<1.0	<1.0	<1.0
1,1,2-Trichloroethane		<1.0	<1.0	<1.0	<1.0	<1.0
1,1-Dichloroethane		<1.0	<1.0	<1.0	<b>1.5</b>	<1.0
1,1-Dichloroethene		<1.0	<1.0	<1.0	<b>5.2</b>	<1.0
1,2-Dichloroethane		<1.0	<1.0	<1.0	<1.0	<1.0
1,2-Dichloropropane		<1.0	<1.0	<1.0	<1.0	<1.0
2-Butanone		<10	<10	<10	<10	<10
4-methyl-2-pentanone		<5.0	<5.0	<5.0	<5.0	<5.0
Acetone		<10	<10	<10	<10	<10
Benzene		<0.50	<0.50	<0.50	<0.50	<0.50
Bromodichloromethane		<1.0	<1.0	<1.0	<1.0	<1.0
Bromoform		<1.0	<1.0	<1.0	<1.0	<1.0
Bromomethane		<2.0	<2.0	<2.0	<2.0	<2.0
Carbon Disulfide		<2.0	<2.0	<2.0	<2.0	<2.0
Carbon tetrachloride		<1.0	<1.0	<1.0	<b>0.30 J</b>	<1.0
Chlorobenzene		<1.0	<1.0	<1.0	<1.0	<1.0
Chloroethane		<1.0	<1.0	<1.0	<1.0	<1.0
Chloroform		<1.0	<1.0	<1.0	<b>1.1</b>	<b>2.7</b>
Chloromethane		<1.0	<1.0	<1.0	<1.0	<1.0
cis-1,2-dichloroethene		<1.0	<1.0	<b>0.44 J</b>	<b>0.77 J</b>	<1.0
cis-1,3-dichloropropene		<1.0	<1.0	<1.0	<1.0	<1.0
Dibromochloromethane		<1.0	<1.0	<1.0	<1.0	<1.0
Ethylbenzene		<1.0	<1.0	<1.0	<1.0	<1.0
Methylene Chloride		<2.0	<2.0	<2.0	<2.0	<2.0
Styrene		<1.0	<1.0	<1.0	<1.0	<1.0
Tetrachloroethene		<1.0	<1.0	<b>0.42 J</b>	<b>24.6</b>	<1.0
Toluene		<1.0	<1.0	<1.0	<1.0	<1.0
trans-1,2-dichloroethene		<1.0	<1.0	<1.0	<1.0	<1.0
trans-1,3-dichloropropene		<1.0	<1.0	<1.0	<1.0	<1.0
Trichloroethylene		<b>1.3</b>	<1.0	<b>25.9</b>	<b>15</b>	<1.0
Trichlorotrifluoroethane (Freon 113)		<5.0	<5.0	<5.0	<5.0	<5.0
Vinyl Chloride		<1.0	<1.0	<1.0	<1.0	<1.0
Xylene-o		<1.0	<1.0	<1.0	<1.0	<1.0
Xylenes - m,p		<1.0	<1.0	<1.0	<1.0	<1.0
<b>Total VOCs<sup>(3)</sup></b>		<b>1.3</b>	<b>0</b>	<b>27</b>	<b>49</b>	<b>2.7</b>
<b>1,4 Dioxane<sup>(1,2)</sup></b>		<b>6.75</b>	<b>4.08</b>	<b>6.03</b>	<b>4.20</b>	<b>1.21</b>

See notes on last page

**Table 6**  
**Concentrations of Volatile Organic Compounds**  
**and 1,4 Dioxane in Monitoring Wells,**  
**Second Quarter 2016, Operable Unit 2,**  
**Northrop Grumman Systems Corporation,**  
**Bethpage, New York**

Constituent (units in µg/L)	Well:	HN-40I	HN-42S	HN-42I	MW-3-1	N-10624	N-10627
	Sample ID:	HN-40I	HN-42S	HN-42I	MW-3-1	N-10624	N-10627
	Date:	4/13/2016	4/26/2016	4/26/2016	5/11/2016	7/1/2016	5/10/2016
<b>Volatile Organic Compounds (VOCs)<sup>(1,2)</sup></b>							
1,1,1-Trichloroethane		<1.0	<1.0	<1.0	<b>0.75 J</b>	<1.0	<1.0
1,1,2,2-Tetrachloroethane		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
1,1,2-Trichloroethane		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
1,1-Dichloroethane		<1.0	<1.0	<1.0	<b>2.9</b>	<1.0	<1.0
1,1-Dichloroethene		<1.0	<1.0	<1.0	<b>2.0</b>	<1.0	<1.0
1,2-Dichloroethane		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
1,2-Dichloropropane		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
2-Butanone		<10	<10	<10	<10	<10	<10
4-methyl-2-pentanone		<5.0	<5.0	<5.0	<5.0	<5.0	<5.0
Acetone		<10	<10	<10	<10	<10	<10
Benzene		<0.50	<0.50	<0.50	<0.50	<0.50	<0.50
Bromodichloromethane		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
Bromoform		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
Bromomethane		<2.0	<2.0	<2.0	<2.0	<2.0	<2.0
Carbon Disulfide		<2.0	<2.0	<2.0	<2.0	<2.0	<2.0
Carbon tetrachloride		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
Chlorobenzene		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
Chloroethane		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
Chloroform		<1.0	<1.0	<1.0	<b>0.28 J</b>	<1.0	<1.0
Chloromethane		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
cis-1,2-dichloroethene		<1.0	<1.0	<1.0	<b>8.9</b>	<1.0	<1.0
cis-1,3-dichloropropene		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
Dibromochloromethane		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
Ethylbenzene		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
Methylene Chloride		<2.0	<2.0	<2.0	<2.0	<2.0	<2.0
Styrene		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
Tetrachloroethene		<1.0	<1.0	<1.0	<b>16.1</b>	<1.0	<1.0
Toluene		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
trans-1,2-dichloroethene		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
trans-1,3-dichloropropene		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
Trichloroethylene		<1.0	<1.0	<b>0.71 J</b>	<b>86.7</b>	<1.0	<b>0.41 J</b>
Trichlorotrifluoroethane (Freon 113)		<5.0	<5.0	<5.0	<5.0	<5.0	<5.0
Vinyl Chloride		<1.0	<1.0	<1.0	<b>16.3</b>	<1.0	<1.0
Xylene-o		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
Xylenes - m,p		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
<b>Total VOCs<sup>(3)</sup></b>		<b>0</b>	<b>0</b>	<b>0.71</b>	<b>130</b>	<b>0</b>	<b>0.41</b>
<b>1,4 Dioxane<sup>(1,2)</sup></b>		<b>&lt;0.11</b>	<b>&lt;0.11</b>	<b>0.289</b>	<b>4.28</b>	<b>2.25</b>	<b>2.52</b>

See notes on last page

**Table 6**  
**Concentrations of Volatile Organic Compounds**  
**and 1,4 Dioxane in Monitoring Wells,**  
**Second Quarter 2016, Operable Unit 2,**  
**Northrop Grumman Systems Corporation,**  
**Bethpage, New York**

Constituent (units in µg/L)	Well: Sample ID: Date:	N-10631 N-10631 4/29/2016
<b><u>Volatile Organic Compounds (VOCs)<sup>(1, 2)</sup></u></b>		
1,1,1-Trichloroethane		<1.0
1,1,2,2-Tetrachloroethane		<1.0
1,1,2-Trichloroethane		<1.0
1,1-Dichloroethane		<1.0
1,1-Dichloroethene		<1.0
1,2-Dichloroethane		<1.0
1,2-Dichloropropane		<1.0
2-Butanone		<10
4-methyl-2-pentanone		<5.0
Acetone		<10 B
Benzene		<0.50
Bromodichloromethane		<1.0
Bromoform		<1.0
Bromomethane		<2.0
Carbon Disulfide		<2.0
Carbon tetrachloride		<1.0
Chlorobenzene		<1.0
Chloroethane		<1.0
Chloroform		<1.0
Chloromethane		<1.0
cis-1,2-dichloroethene		<1.0
cis-1,3-dichloropropene		<1.0
Dibromochloromethane		<1.0
Ethylbenzene		<1.0
Methylene Chloride		<2.0
Styrene		<1.0
Tetrachloroethene		<1.0
Toluene		<1.0
trans-1,2-dichloroethene		<1.0
trans-1,3-dichloropropene		<1.0
Trichloroethylene		<b>1.4</b>
Trichlorotrifluoroethane (Freon 113)		<5.0
Vinyl Chloride		<1.0
Xylene-o		<1.0
Xylenes - m,p		<1.0
<b>Total VOCs<sup>(3)</sup></b>		<b>1.4</b>
<b>1,4 Dioxane<sup>(1,2)</sup></b>		<b>3.76</b>

See notes on last page

**Table 6**  
**Concentrations of Volatile Organic Compounds**  
**and 1,4 Dioxane in Monitoring Wells,**  
**Second Quarter 2016, Operable Unit 2,**  
**Northrop Grumman Systems Corporation,**  
**Bethpage, New York**

**Notes and Abbreviations:**

- (1) Samples were analyzed for VOCs using USEPA Method 8260 C; samples were analyzed for 1,4-Dioxane using USEPA Method 8270D SIM.
- (2) Results for the program are validated at 20% frequency, per protocols specified in OU2 Groundwater Monitoring Plan (Arcadis 2016).
- (3) Total VOCs rounded to two significant figures.
- Bold** Constituent detected
- J** Constituent value is estimated
- D** Concentration is based on a diluted sample analysis
- B** Blank Contamination
- REP** Replicate Sample
- µg/L** Micrograms per liter
- VOCs** Volatile Organic Compounds
- <5.0** Compound not detected above its laboratory quantification limit.



**Table 7**  
**Concentrations of Metals and 1,4-Dioxane in Monitoring Wells**  
**Second Quarter 2016, Operable Unit 2**  
**Northrop Grumman Systems Corporation**  
**Bethpage, New York.**

Constituent (units in mg/L)	Well: Sample ID: Date:	GM-15SR GM-15S 4/13/2016	GM-78I GM-78I 4/28/2016	GM-78S GM-78S 4/28/2016	MW-01GF MW-1GF 4/19/2016	MW-02GF MW-2GF 4/19/2016	N-10631 N-10631 4/29/2016	PLT1 MW-04 PLT1 MW04 5/2/2016	PLT1 MW-05 PLT1 MW05 4/19/2016	PLT1 MW-06 PLT1 MW-06 5/2/2016	PLT1 MW-06 REP050216MO1 5/2/2016
<b>Metals <sup>(1)</sup></b>											
Cadmium		--	<3.0	<3.0	<3.0	<3.0	<b>13.2</b>	--	--	--	--
Cadmium (Dissolved)		--	<3.0	<3.0	<3.0	<3.0	<b>16.7</b>	--	--	--	--
Chromium		<b>640</b>	<10	<10	<10	<b>29.2</b>	<b>36.1</b>	<10	<b>552</b>	<b>191</b>	<b>197</b>
Chromium (Dissolved)		<b>641</b>	<10	<10	<10	<b>30.1</b>	<b>45.6</b>	<10	<b>555</b>	<b>196</b>	<b>195</b>
1,4-dioxane <sup>(1,2)</sup>		<b>1.21</b>	<b>2.42</b>	<b>3.08</b>	<b>4.06</b>	<b>3.75</b>	<b>3.76</b>	<b>0.248</b>	<b>0.433</b>	ND	<b>0.132</b>

**Notes and Abbreviations:**

<sup>(1)</sup> Results for the program are validated at 20% frequency, per protocols specified in OU2 Groundwater Monitoring Plan (Arcadis 2016).

<sup>(2)</sup> Samples were analyzed for 1,4-Dioxane using USEPA Method 8270D SIM.

- Bold** Constituent detected  
**ND** Not Detected  
**REP** Blind duplicate sample  
**mg/L** Milligrams per liter  
**--** Not analyzed

**Table 8**  
**Concentrations of Volatile Organic Compounds and 1,4 Dioxane in Outpost Wells <sup>(1)</sup>**  
**Second Quarter 2016, Operable Unit 2,**  
**Northrop Grumman Systems Corporation**  
**Bethpage, New York**

Constituents units in (ug/L)	Well ID:	BPOW 1-1	BPOW 1-2	BPOW 1-3	BPOW 1-4	BPOW 1-5	BPOW 1-6	BPOW 2-1	BPOW 2-2	BPOW 2-3
	Sample ID:	BPOW 1-1	BPOW 1-2	BPOW 1-3	BPOW 1-4	BPOW 1-5	BPOW 1-6	BPOW 2-1	BPOW 2-2	BPOW 2-3
	Sample Date:	6/8/2016	6/7/2016	6/10/2016	6/21/2016	6/17/2016	6/17/2016	6/10/2016	6/2/2016	6/16/2016
<b>Volatile Organic Constituents <sup>(2, 4)</sup></b>										
1,1,1-Trichloroethane		<b>0.25 J</b>	<b>0.34 J</b>	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50
1,1,2,2-Tetrachloroethane		<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50
1,1,2-Trichloroethane		<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50
1,1-Dichloroethane		<0.50	<b>0.13 J</b>	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50
1,1-Dichloroethene		<b>0.18 J</b>	<b>0.26 J</b>	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50
1,2-Dichloroethane		<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50
1,2-Dichloropropane		<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50
2-Butanone (MEK)		<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0
Methyl N-Butyl Ketone (2-Hexanone)		<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0
4-Methyl-2-Pentanone		<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0
Acetone		<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0
Benzene		<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<b>0.080 J</b>	<0.50	<0.50
Bromodichloromethane		<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50
Bromoform		<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50
Bromomethane		<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50
Carbon Disulfide		<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50
Carbon Tetrachloride		<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50
Chlorobenzene		<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50
Chloroethane		<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50
Chloroform		<b>0.11 J</b>	<b>0.066 J</b>	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50
Chloromethane		<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50
cis-1,2-Dichloroethene		<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50
cis-1,3-Dichloropropene		<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50
Dibromochloromethane		<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50
Ethylbenzene		<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50
Methylene Chloride		<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50
Styrene (Monomer)		<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50
Tetrachloroethene		<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50
Toluene		<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50
trans-1,2-Dichloroethene		<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50
trans-1,3-Dichloropropene		<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50
Trichloroethene		<b>1.1</b>	<b>0.85</b>	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50
Trichlorotrifluoroethane (Freon)		<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
Vinyl chloride		<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50
o-Xylene		<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50
m,p-Xylene		<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50
<b>TVOCs <sup>(5)</sup></b>		<b>1.6</b>	<b>1.7</b>	<b>0</b>	<b>0</b>	<b>0</b>	<b>0</b>	<b>0.08</b>	<b>0</b>	<b>0</b>
<b>1,4 Dioxane <sup>(2,4)</sup></b>		<b>0.165 J</b>	<b>0.160 J</b>	<b>0.167 J</b>	<b>0.093 J</b>	<b>0.043 J</b>	<b>0.0406 J</b>	<b>0.474 J</b>	<b>0.338 J</b>	<b>3.94</b>

**Table 8**  
**Concentrations of Volatile Organic Compounds and 1,4 Dioxane in Outpost Wells <sup>(1)</sup>**  
**Second Quarter 2016, Operable Unit 2,**  
**Northrop Grumman Systems Corporation**  
**Bethpage, New York**

Constituents units in (ug/L)	BPOW 3-1	BPOW 3-2	BPOW 3-3	BPOW 3-4	REP062216MO1	BPOW 4-1R <sup>(3)</sup>	BPOW 4-2R <sup>(3)</sup>
	BPOW 3-1 6/16/2016	BPOW 3-2 6/16/2016	BPOW 3-3 6/21/2016	BPOW 3-4 6/22/2016	BPOW 3-4 6/22/2016	BPOW 4-1R 5/31/2016	BPOW 4-2R 6/1/2016
<b>Volatile Organic Constituents <sup>(2,4)</sup></b>							
1,1,1-Trichloroethane	<0.50	<0.50	<0.50	<b>0.074 J</b>	<0.50	<0.50	<1.0
1,1,2,2-Tetrachloroethane	<0.50	<0.50	<0.50	<0.50	<0.50	<1.0	<1.0
1,1,2-Trichloroethane	<0.50	<0.50	<0.50	<b>0.62 J</b>	<b>0.63 J</b>	<1.0	<1.0
1,1-Dichloroethane	<0.50	<0.50	<0.50	<b>0.69</b>	<b>0.67</b>	<1.0	<1.0
1,1-Dichloroethene	<0.50	<0.50	<0.50	<b>0.13 J</b>	<b>0.12 J</b>	<1.0	<1.0
1,2-Dichloroethane	<0.50	<0.50	<0.50	<b>0.79</b>	<b>0.7</b>	<1.0	<1.0
1,2-Dichloropropane	<0.50	<0.50	<0.50	<0.50	<0.50	<1.0	<1.0
2-Butanone (MEK)	<5.0	<5.0	<5.0	<5.0	<5.0	<10	<10
Methyl N-Butyl Ketone (2-Hexanone)	<2.0	<2.0	<2.0	<2.0	<2.0	<5.0	<5.0
4-Methyl-2-Pentanone	<2.0	<2.0	<2.0	<2.0	<2.0	<5.0	<5.0
Acetone	<5.0	<5.0	<5.0	<5.0	<5.0	<10	<10
Benzene	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50
Bromodichloromethane	<0.50	<0.50	<0.50	<0.50	<0.50	<1.0	<1.0
Bromoform	<0.50	<0.50	<0.50	<0.50	<0.50	<1.0	<1.0
Bromomethane	<0.50	<0.50	<0.50	<0.50	<0.50	<2.0	<2.0
Carbon Disulfide	<0.50	<0.50	<0.50	<0.50	<0.50	<2.0	<2.0
Carbon Tetrachloride	<0.50	<0.50	<0.50	<b>0.46 J</b>	<b>0.39 J</b>	<b>0.22 J</b>	<b>0.20 J</b>
Chlorobenzene	<0.50	<0.50	<0.50	<0.50	<0.50	<1.0	<1.0
Chloroethane	<0.50	<0.50	<0.50	<0.50	<0.50	<1.0	<1.0
Chloroform	<0.50	<0.50	<0.50	<b>1.2</b>	<b>1.1</b>	<b>0.13 J</b>	<b>0.10 J</b>
Chloromethane	<0.50	<0.50	<0.50	<0.50	<0.50	<1.0	<1.0
cis-1,2-Dichloroethene	<0.50	<0.50	<0.50	<b>0.98</b>	<b>0.94</b>	<1.0	<b>0.26 J</b>
cis-1,3-Dichloropropene	<0.50	<0.50	<0.50	<0.50	<0.50	<1.0	<1.0
Dibromochloromethane	<0.50	<0.50	<0.50	<0.50	<0.50	<1.0	<1.0
Ethylbenzene	<0.50	<0.50	<0.50	<0.50	<0.50	<1.0	<1.0
Methylene Chloride	<0.50	<0.50	<0.50	<0.50	<0.50	<2.0	<2.0
Styrene (Monomer)	<0.50	<0.50	<0.50	<0.50	<0.50	<1.0	<1.0
Tetrachloroethene	<0.50	<0.50	<0.50	<0.50	<0.50	<1.0	<b>0.10 J</b>
Toluene	<0.50	<0.50	<0.50	<0.50	<0.50	<1.0	<1.0
trans-1,2-Dichloroethene	<0.50	<0.50	<0.50	<0.50	<0.50	<1.0	<1.0
trans-1,3-Dichloropropene	<0.50	<0.50	<0.50	<0.50	<0.50	<1.0	<1.0
Trichloroethene	<0.50	<0.50	<0.50	<b>63</b>	<b>60</b>	<b>1.1</b>	<b>1.9</b>
Trichlorotrifluoroethane (Freon)	<1.0	<1.0	<1.0	<b>0.62 J</b>	<b>0.62 J</b>	<b>17</b>	<b>13</b>
Vinyl chloride	<0.50	<0.50	<0.50	<0.50	<0.50	<1.0	<1.0
o-Xylene	<0.50	<0.50	<0.50	<0.50	<0.50	<1.0	<1.0
m,p-Xylene	<0.50	<0.50	<0.50	<0.50	<0.50	<1.0	<1.0
<b>TVOCs <sup>(5)</sup></b>	<b>0</b>	<b>0</b>	<b>0</b>	<b>68</b>	<b>65</b>	<b>18</b>	<b>15</b>
<b>1,4 Dioxane <sup>(2,4)</sup></b>	<b>0.882</b>	<b>4.54</b>	<b>6.16</b>	<b>3.91</b>	<b>4.54</b>	<b>2.32</b>	<b>1.80</b>


**Table 8**  
**Concentrations of Volatile Organic Compounds and 1,4 Dioxane in Outpost Wells <sup>(1)</sup>**  
**Second Quarter 2016, Operable Unit 2,**  
**Northrop Grumman Systems Corporation**  
**Bethpage, New York**

**Notes and Abbreviations:**

- (1) These outpost wells have been recently repurposed for use as plume monitoring wells per the June 2015 Groundwater Monitoring Plan Addendum (ARCADIS of New York, Inc., 2015) as conditionally approved by the NYSDEC (August 25, 2015). Therefore, TVOC trigger levels that may have been previously established are no longer shown
- (2) Samples were analyzed for VOCs using USEPA Method 524.2; samples were analyzed for 1,4-Dioxane using USEPA Method 522
- (3) The NAVY abandoned original Wells BPOW4-1 and BPOW4-2 and installed replacement Wells BPOW4-1R and BPOW4-2R between August, 2014 and October, 2014
- (4) Results for the program are validated at 20% frequency, per protocols specified in OU2 Groundwater Monitoring Plan (Arcadis 2016)
- (5) TVOCs are rounded to two significant figures

**Bold value indicates constituent detected.**


REP	Blind Duplicate Sample
TVOCs	Total Volatile Organic Compounds
USEPA	United States Environmental Protection Agency
VOC	Volatile Organic Compounds
µg/L	micrograms per liter
<0.5	Compound not detected above its laboratory quantification limit.
J	Value is estimated concentration



**EXPLANATION**


- PROPERTY BOUNDARY OF THE FORMER GRUMMAN AEROSPACE SITE
- PROPERTY BOUNDARY OF THE FORMER NAVY SITE
- PROPERTY BOUNDARY OF THE FORMER OXY/RUCO SITE
- +++++ LONG ISLAND RAILROAD
- DENOTES NORTHROP GRUMMAN OWNED PROPERTY (AS OF 2009)
- DENOTES NAVY OWNED PROPERTY (AS OF 2014)
- ▨ DENOTES FORMER NAVY OWNED PROPERTY
- RECHARGE BASIN
- 10592 ● OBSERVATION/MONITORING/OUTPOST WELL (1)
- 9591 ● PUBLIC SUPPLY WELL (2)
- WELL-17 ● NORTHROP GRUMMAN REMEDIAL WELL
- ▭ PART OF ON-SITE REMEDY
- NWIRP NAVAL WEAPONS INDUSTRIAL RESERVE PLANT
- TOH (LWD) TOWN OF HEMPSTEAD LEVITOWN WATER DISTRICT
- HWD HICKSVILLE WATER DISTRICT
- SFWD SOUTH FARMINGDALE WATER DISTRICT
- BWD BETHPAGE WATER DISTRICT
- NYAW NEW YORK AMERICAN WATER

**NOTE:**  
 (1) THIS FIGURE DEPICTS OBSERVATION/MONITORING/OUTPOST WELLS INCLUDED IN THE OU-2 GROUNDWATER MONITORING PROGRAM.  
 (2) PUBLIC SUPPLY WELLS ARE NOT SAMPLED AS A PART OF THE OU2 GROUNDWATER MONITORING PROGRAM AND ARE ONLY FOR REFERENCE.



NORTHROP GRUMMAN SYSTEMS CORPORATION  
 BETHPAGE, NEW YORK  
**OPERABLE UNIT 2**

**LOCATIONS OF WELLS AND ON-SITE GROUNDWATER REMEDY**



**EXPLANATION**

- PROPERTY BOUNDARY OF THE FORMER GRUMMAN AEROSPACE SITE
- PROPERTY BOUNDARY OF THE FORMER NAVY SITE
- PROPERTY BOUNDARY OF THE FORMER OXY/RUCO SITE
- +++++ LONG ISLAND RAILROAD
- DENOTES NORTHROP GRUMMAN OWNED PROPERTY (AS OF 2009)
- DENOTES NAVY OWNED PROPERTY (AS OF 2014)
- ▨ DENOTES FORMER NAVY OWNED PROPERTY
- RECHARGE BASIN
- 10592 ◆ OBSERVATION/MONITORING/OUTPOST WELL (1)
- 9591 ● PUBLIC SUPPLY WELL (2)
- WELL-17 ◆ NORTHROP GRUMMAN REMEDIAL WELL
- PART OF ON-SITE REMEDY
- NWIRP NAVAL WEAPONS INDUSTRIAL RESERVE PLANT
- TOH (LWD) TOWN OF HEMPSTEAD LEVITOWN WATER DISTRICT
- HWD HICKSVILLE WATER DISTRICT
- SFWD SOUTH FARMINGDALE WATER DISTRICT
- BWD BETHPAGE WATER DISTRICT
- NYAW NEW YORK AMERICAN WATER

**NOTE:**

(1) THIS FIGURE DEPICTS OBSERVATION/MONITORING/OUTPOST WELLS INCLUDED IN THE OU-2 GROUNDWATER MONITORING PROGRAM.  
 (2) PUBLIC SUPPLY WELLS ARE NOT SAMPLED AS A PART OF THE OU2 GROUNDWATER MONITORING PROGRAM AND ARE ONLY FOR REFERENCE.

0 1000' 2000'  
 APPROXIMATE SCALE IN FEET


NORTHROP GRUMMAN SYSTEMS CORPORATION  
 BETHPAGE, NEW YORK  
**OPERABLE UNITS 2 AND 3**

**LOCATIONS OF TREATMENT SYSTEMS  
 AND DISCHARGES**

**ARCADIS** Design & Construction  
for natural and built assets

FIGURE  
**2**

CITY:SYRACUSE,NY DIV:GROUPENV DB:A,SANCHEZ LD:ALS PIC:(Opt) PM:(Recd) TM:(Opt) LVR:(Opt)ON="OFF-REF"  
 \arcadis-us.com\office\data\Syracuse-NY\ENVCAD\Syracuse\ACTN\001496315\GWMMA1496315\F03.dwg LAYOUT: 3 SAVED: 3/18/2016 2:32 PM ACADVER: 19.1S (LMS TECH) PAGES: 3 PLOTSTYLETABLE: ..... PLOTTED: 8/11/2016 3:16 PM BY: IAMICELI, KIMBERLY  
 XREFS: IMAGES: PROJECTNAME: .....  
 NO. GW PIPE  
 XBD: BL



- LEGEND:**
- FORMER NORTHROP GRUMMAN PROPERTY LINE
  - INFLUENT LINE
  - - - - BYPASS
  - - - - STORM DRAIN (EFFLUENT)
  - - - - NON POTABLE WATER DISTRIBUTION LINE (EFFLUENT)
  - +++++ RAILROAD TRACKS
  - - - - FENCE
  - WELL 18 REMEDIAL WELL
  - BASIN
  - ONCT ON-SITE CONTAMINANT

**NOTES:**  
 DRAWING IS NOT TO BE USED FOR DESIGN PURPOSES. LAYOUT OF PIPING IS FOR REPRESENTATION ONLY (LOCATIONS ARE APPROXIMATE).


NORTHROP GRUMMAN SYSTEMS CORPORATION  
 BETHPAGE, NEW YORK  
**OPERABLE UNIT 2**

**ONCT GROUNDWATER  
 EXTRACTION AND TREATMENT  
 SYSTEM SITE PLAN**


**ARCADIS** Design & Consultancy  
for natural and built assets

FIGURE  
**3**

# TOWER 96 TREATMENT SYSTEM:



# TOWER 102 TREATMENT SYSTEM:



- LEGEND:
- PROCESS WATER
  - - - PROCESS AIR
  - - - - STEAM
  - W SAMPLE LOCATION
  - W WATER SAMPLE
  - V VAPOR SAMPLE
  - ONCT ON-SITE CONTAMINANT

NORTHROP GRUMMAN SYSTEMS CORPORATION  
BETHPAGE, NEW YORK  
**OPERABLE UNIT 2**

**ONCT GROUNDWATER  
EXTRACTION AND TREATMENT  
SYSTEM SCHEMATIC**

**ARCADIS** Design & Consultancy  
for natural and  
built assets

FIGURE  
**4**

CITY: SYRACUSE, NY DIV: GROUP ENV DB: A. SANCHEZ LD: ALS PIC: (Opt) PM: (Recd) TM: (Opt) LVR: (Opt) ON: -OFF-REF-  
 \arcadis-us.com\office\data\Syracuse-NY\ENV\CA\AD\SYRACUSE\ACTN\001496315\GWM41496315\1514F04.dwg LAYOUT: 4 - SAVED: 3/15/2016 10:09 AM ACADVER: 19.1S (LMS TECH) PAGESETUP: - - - PLOTSTYLETABLE: - - - PLOT: 8/11/2016 3:19 PM BY: IAMICELI, KIMBERLY  
 XREFS: IMAGES: PROJECTNAME: - - -