


# CONTRACT DRAWINGS

# OPERABLE UNIT 3 GROUNDWATER INTERIM REMEDIAL MEASURE

## FORMER GRUMMAN SETTLING PONDS


AUGUST 2008

## NORTHROP GRUMMAN SYSTEMS CORPORATION BETHPAGE, NEW YORK



REFERENCE: BASE MAP USGS 7.5 MINUTE QUADRANGLE, AMITYVILLE, FREEPORT, N.Y. 1969, PHOTOREVISED 1979. HUNTINGTON, HICKSVILLE, N.Y., 1967, PHOTOREVISED 1979.

LOCATION MAP  
0 2000' 4000'  
GRAPHIC SCALE





### INDEX TO DRAWINGS

1	SITE PLAN
2	TREATMENT BUILDING AREA PLAN
3	PIPING AND INSTRUMENTATION DIAGRAM #1
4	PIPING AND INSTRUMENTATION DIAGRAM #2
5	PIPING AND INSTRUMENTATION DIAGRAM #3
6	LEGEND, ABBREVIATIONS AND INTERLOCKS
7	EQUIPMENT LAYOUT
8	WELL DETAIL
9	MISCELLANEOUS SECTIONS AND DETAILS
10	MISCELLANEOUS SECTIONS AND DETAILS
11	SPECIFICATIONS
12	SOIL MANAGEMENT PLAN
13	ELECTRICAL SITE PLAN
14	ONE-LINE DIAGRAM
15	EQUIPMENT LAYOUT-ELECTRICAL
16	EQUIPMENT LAYOUT-INSTRUMENTATION
17	EQUIPMENT DETAILS AND SCHEMATICS
18	FOUNDATION PLAN VIEW AND DETAILS
19	SLAB-ON-GRADE PLAN VIEW AND DETAILS
20	BUILDING ELEVATIONS
21	STRUCTURAL NOTES AND SYMBOLS #1
22	STRUCTURAL NOTES AND SYMBOLS #2



ARCADIS U.S., INC.

CITY:SYRACUSE DIV:GROUPE-85 DR:GHS LD:GHS P:C: PM: TM: LYRON+OFF-REF- G:\PROJECT\Northrop Grumman\Superfund\2008\01464.1807\GWRM\Design Documents\Design Report\Final Design Report\Contract DWGs\lead\0146401-02.dwg LAYOUT: 1 SAVED: 9/2/2008 3:10 PM ACADVER: 17.1S (LIMS TECH) PAGESSETUP: ---- PLOTSTYLETABLE: ARCADIS\_MELVILLE.CTB PLOTTED: 9/2/2008 3:27 PM BY: SANCHEZ, ADRIAN PROJECTNAME: XREFS: IMAGES: 01464X02 Witek.VI.jpg 01464X01 BCP\_Aerial.jpg 01464X00 Witek.VI.jpg ACCESS\_RD\_NAD83



- NOTES:**
- LOCATION OF WORK: ALL WORK DESCRIBED IN THESE DRAWINGS/SPECIFICATIONS SHALL BE PERFORMED ON BEHALF OF NORTHROP GRUMMAN SYSTEMS CORPORATION, INC.
  - CONTRACTORS SHOULD VISIT THE SITE AND EXAMINE ALL OF THE PHYSICAL CONDITIONS THAT AFFECT THE FINAL BID PRICE.
  - CONTRACTORS SHALL OBTAIN ALL NECESSARY FIELD MEASUREMENTS TO VERIFY THE ABILITY TO EXECUTE THE WORK IN ACCORDANCE WITH THIS SCOPE OF WORK AND DRAWINGS. NO ADDITIONS OR REVISIONS TO THE BID OR CONTRACT PRICE WILL BE PERMITTED BASED ON EXISTING CONDITIONS.
  - CONTRACTORS SHALL PROVIDE ALL LABOR, MATERIAL, AND EQUIPMENT, UNLESS OTHERWISE STATED, NECESSARY TO PERFORM THIS WORK. THE SITE WILL BE A UNION SITE.
  - CONTRACTORS SHALL BE RESPONSIBLE FOR OBTAINING ALL TRADE PERMITS, AND APPROVALS NECESSARY TO PERFORM THIS WORK; INCLUDING AGREEMENTS WITH APPLICABLE, LOCAL AND TRADE UNIONS.
  - ALL SITE WORKERS SHALL HAVE THE APPROPRIATE HEALTH AND SAFETY TRAINING; REVIEW AND SIGN THE PROJECT HEALTH AND SAFETY PLAN UNLESS WAIVER IS GRANTED BY THE PROJECT HEALTH AND SAFETY OFFICE; AND REVIEW AND ACKNOWLEDGE NORTHROP GRUMMAN SYSTEMS CORPORATION INTEGRATED SYSTEMS EASTERN REGION'S (ISER) "ON-SITE CONTRACTOR'S ENVIRONMENTAL, SAFETY AND HEALTH COMPLIANCE MANUAL. BETHPAGE, NEW YORK, DATED JUNE 12, 2008." COPIES OF EACH PERSON'S APPLICABLE STRANDING CERTIFICATES SHALL BE PROVIDED TO THE PROJECT HEALTH AND SAFETY OFFICER PRIOR BEFORE THE EMPLOYEE CAN START WORK AT THE SITE. COPIES OF TRAINING CERTIFICATES SHALL BE KEPT ON FILE WITH THE PROJECT FILE.
  - WHILE CONSTRUCTION ACTIVITIES ARE UNDER WAY AT LEAST ONE CONTRACTOR, FOREMAN, OR CREW SUPERVISOR SHALL BE PRESENT AT THE JOB SITE AT ALL TIMES AND WILL DIRECTLY REPORT TO THE ARCADIS SITE SUPERVISOR.
  - ALL EXCAVATED/DEMOLITION MATERIALS INTO TWO CATEGORIES: CONCRETE/ASPHALT/METAL MATERIAL AND SOIL MATERIAL. CONCRETE/ASPHALT/METAL MATERIAL SHALL BE DISPOSED OF BY CONTRACTOR. SOIL MATERIAL WILL BE CHARACTERIZED AND DISPOSED OF IN ACCORDANCE WITH THE SPECIFICATIONS ON DRAWING 12 AND ALL FEDERAL, STATE AND LOCAL REGULATIONS.
  - CONTRACTORS ARE RESPONSIBLE FOR LOCATING AND VERIFYING LOCATION OF ALL UTILITIES WITHIN AREA AFFECTED BY CONSTRUCTION. COPIES OF PRINTS OBTAINED OR LOCATIONS PROVIDED TO CONTRACTOR WITH RESPECT TO UTILITIES SHALL BE SUPPLIED TO THE ENGINEER WITH A RECORD SET OF DRAWINGS AT COMPLETION OF CONSTRUCTION. IF A CONFLICT EXISTS BETWEEN THE UTILITY LOCATION AND THE CONSTRUCTION DRAWINGS, CONTRACTOR IS TO NOTIFY THE ENGINEER IMMEDIATELY SO THAT THE CONFLICT MAY BE RESOLVED.
  - CONTRACTOR IS RESPONSIBLE FOR PROVIDING THE ENGINEER WITH ALL INFORMATION REQUIRED TO COMPLETE A SET OF "RECORD" DRAWINGS BY KEEPING A RECORD SET OF DAILY PROGRESSION OF WORK.
  - UNLESS OTHERWISE NOTED, ALL AREAS DISTURBED BY THIS WORK SHALL BE RESTORED TO ORIGINAL CONDITION.
  - CONTRACTOR TO PROTECT AND PRESERVE ALL EXISTING FEATURES (I.E. MONITORING WELLS, EQUIPMENT, ETC.) WITHIN AREAS AFFECTED BY CONSTRUCTION. DAMAGE SUSTAINED TO AN EXISTING FEATURE WILL BE REPAIRED/REPLACED AT CONTRACTOR'S EXPENSE TO SATISFACTION OF ENGINEER.
  - CONTRACTOR SHALL PERFORM ALL WORK IN ACCORDANCE WITH ALL COUNTY, LOCAL, STATE, AND FEDERAL REGULATIONS, INCLUDING, BUT NOT LIMITED TO, ALL APPLICABLE LOCAL, STATE, AND/OR FEDERAL (OSHA, USEPA, AND DOT, ETC.) RULES AND REGULATIONS.
  - UNLESS OTHERWISE INDICATED HEREIN, ALL MATERIALS AND EQUIPMENT FURNISHED UNDER THIS CONTRACT SHALL BE NEW, FREE FROM DEFECTS, AND SHALL BE GUARANTEED FOR A PERIOD OF AT LEAST ONE YEAR FROM THE DATE OF ACCEPTANCE OF THE WORK. THE CONTRACTOR SHALL FURNISH, AT NO COST TO THE ENGINEER, ALL LABOR AND MATERIALS NECESSARY TO CORRECT PROBLEMS DUE TO FAULTY WORKMANSHIP OR MATERIALS.
  - OTHER CONSTRUCTION ACTIVITIES MAY BE TAKING PLACE CONCURRENTLY WITH THIS PROJECT. THE CONTRACTOR SHALL CONSULT WITH THE VARIOUS PARTIES AND SHALL COORDINATE SCHEDULES.
  - THE INFORMATION SHOWN ON THE DRAWINGS CONCERNING TYPE AND LOCATION OF UNDERGROUND UTILITIES IS NOT GUARANTEED TO BE ACCURATE OR ALL INCLUSIVE. CONTRACTOR IS RESPONSIBLE FOR MAKING HIS OWN DETERMINATIONS AS TO THE TYPE AND LOCATION OF UNDERGROUND UTILITIES AS MAY BE NECESSARY TO AVOID DAMAGE THERETO.
  - TRENCHING WILL BE PERFORMED IN AREAS WHERE VEHICULAR TRAFFIC MAY BE PRESENT. THE CONTRACTOR(S) SHALL NOTIFY THE TOWN OF OYSTER BAY HIGHWAY DEPARTMENT AND ENGINEER OF THE PROPOSED START OF WORK WITHIN THESE TRAFFIC AREAS A MINIMUM OF 48 HOURS PRIOR TO THE START OF THE WORK. FURTHERMORE, THE CONTRACTOR WILL PERFORM THIS WORK IN A MANNER TO ALLOW FOR MINIMAL DISRUPTION TO TRAFFIC. THIS WILL INCLUDE PERFORMING WORK IN ACCORDANCE WITH TOWN OF OYSTER BAY HIGHWAY DEPARTMENT REQUIREMENTS IN SECTIONS AND/OR PROVIDING TRAFFIC PLATES TO ALLOW TRENCH SECTIONS TO BE DRIVEN OVER. TRAFFIC CONTROLS SHALL BE PROVIDED AS REQUIRED BY TOWN OF OYSTER BAY HIGHWAY DEPARTMENT REQUIREMENTS.
  - PIPE ROUTING SHOWN FOR CONSTRUCTION LAYOUT PURPOSES ONLY. ACTUAL ROUTING TO BE FIELD DETERMINED AND IS SUBJECT TO ENGINEER'S APPROVAL.
  - CONTRACTOR SHALL EXTEND ALL PROCESS PIPING AND MAKE ALL NECESSARY CONNECTIONS TO WELL VAULTS.
  - ALL PIPING PRESSURE TESTS SHALL BE MADE BY THE CONTRACTOR IN THE PRESENCE OF THE ENGINEER.
  - CONTRACTOR SHALL PROVIDE ALL PRODUCTS AND PROPERLY CALIBRATED TESTING EQUIPMENT REQUIRED TO PERFORM THE PIPING PRESSURE TESTING WORK.
  - TESTS MAY BE PERFORMED ON SEPARATE SECTIONS OF PIPING TO EXPEDITE CONSTRUCTION. THE CONTRACTOR SHALL NOT PERFORM PRESSURE TESTING AGAINST SYSTEM VALVES.
  - AFTER THE INITIAL PRESSURE TEST ON PIPING IS COMPLETED SUCCESSFULLY, THE CONTRACTOR SHALL BACKFILL THE TRENCHES AS SPECIFIED.
  - EXCAVATIONS SHALL BE KEPT FREE FROM STANDING WATER.
  - CONTRACTOR SHALL NOTIFY THE ENGINEER AT THE COMPLETION OF EXCAVATIONS AND TRENCHING TO ALLOW FOR INSPECTIONS.
  - CONTRACTOR SHALL PROVIDE APPROPRIATE SAFETY BARRICADES AROUND TRENCHING AND EXCAVATION TO PREVENT ACCIDENTS OR UNAUTHORIZED ENTRY.
  - BACKFILL OF TRENCHES IN UNPAVED AREAS WILL BE APPLIED IN 6-INCH THICK COMPACTED LIFTS. BACKFILL OF TRENCHES IN DESIGNATED ROAD CROSSING AREAS SHALL BE APPLIED IN 6-INCH COMPACTED LIFTS SUCH THAT A 95% MODIFIED PROCTOR DENSITY SHALL BE ACHIEVED.
  - CONTRACTOR'S FILL SOURCE MUST BE TESTED BY CONTRACTOR AND APPROVED BY THE ENGINEER PRIOR TO COMMENCING THE WORK AND/OR PLACING THE MATERIAL.
  - EXCAVATIONS WILL BE BACKFILLED AS PROMPTLY AS WORK PERMITS ONCE REQUIRED INSPECTIONS HAVE BEEN COMPLETED.
  - DO NOT PLACE MATERIALS ON SURFACES THAT ARE MUDDY, FROZEN, OR CONTAIN ICE OR FROST.
  - CONTRACTOR SHALL PLACE A STRIP(S) OF UTILITY WARNING TAPE SPACED AT 18 INCHES ON CENTER IN ALL TRENCHED AREAS. THIS TAPE SHALL CONTAIN A WIRE FOR METAL DETECTION OR HAVE AN ALUMINUM CORE. TAPE SHALL BE PLACED AT A DEPTH OF 6 INCHES IN NON-PAVED AREAS AND BELOW THE SUBBASE IN PAVED AREAS.
  - ALL CONCRETE AND PAVEMENT CUTS ARE TO BE SMOOTH EDGE SAW CUTS BY CIRCULAR SAW BLADES.
  - SURVEY NOTE: MAP FEATURES BASED ON SURVEY PREPARED BY NELSON & POPE ENGINEERS AND SURVEYORS, "EXISTING TOPOGRAPHY", DATED 4-19-07.
  - EXISTING FEATURES ON PARK AND OFF-SITE ARE BASED ON AERIAL PHOTOGRAPHY AND ARE APPROXIMATE.
  - ALL PAVED AREAS SHALL BE RESTORED.
  - ALL EXISTING GROUNDWATER EXTRACTION PIPING SHALL BE FLUSHED OUT PRIOR TO CONNECTING TO FINAL CONNECTION.
  - ALL INFLUENT LINES SHALL BE FLUSHED PRIOR TO MAKING FINAL CONNECTIONS AT WELL VAULT AND BUILDING.
  - PIPE CLEAN-OUTS SHALL BE INSTALLED AT WELL VAULTS AND AT PIPE PENETRATIONS INSIDE TREATMENT BUILDING FOR ALL INFLUENT LINES.
  - GROUNDWATER IRM LINES SHALL BE FLUSHED OUT WITH CLEAN WATER PRIOR TO PRESSURE TESTING.
  - ALL INFORMATION PRESENTED ON THESE DRAWINGS IS CONFIDENTIAL.

**ZONING NOTES:**

SECTION 46 BLOCK G, LOT 92 LIE WITHIN THE TOWN OF OYSTER BAY AND ARE ZONED "GB" GENERAL BUSINESS.

THE FOLLOWING IS A PARTIAL LISTING OF ZONING REQUIREMENTS PRINTED IN THE CODE OF THE TOWN OF OYSTER BAY:

MAXIMUM LOT WIDTH/FRONTAGE:	40 FEET
MAXIMUM BUILDING COVERAGE:	80%
MINIMUM FRONT YARD SETBACK:	10 FEET
MINIMUM REAR YARD SETBACK:	20 FEET
MAXIMUM BUILDING HEIGHT:	35 FEET



THIS BAR REPRESENTS ONE INCH ON THE ORIGINAL DRAWING.

USE TO VERIFY FIGURE REPRODUCTION SCALE

No.	Date	Revisions	By	Ckd

THIS DRAWING IS THE PROPERTY OF THE ARCADIS ENTITY IDENTIFIED IN THE TITLE BLOCK AND MAY NOT BE REPRODUCED OR ALTERED IN WHOLE OR IN PART WITHOUT THE EXPRESS WRITTEN PERMISSION OF SAME.

Professional Engineer's Name  
**WILLIAM S. WITTEK**

Professional Engineer's No.  
080827

State  
NY


Date Signed

Project Mgr.  
CSG

Designed by  
CDL

Drawn by  
BKD

Checked by  
TEM



NORTHROP GRUMMAN CORPORATION • BETHPAGE, NEW YORK  
OPERABLE UNIT 3 - FORMER GRUMMAN SETTLING PONDS

**SITE PLAN**

ARCADIS Project No.  
NY001464.1807.00003

Date  
JUNE 2008

ARCADIS  
6723 Towpath Road  
Box 66  
Syracuse, NY 13214  
Tel: 315-446-9120

CITY:SYR;RAY\_DWG:GROU1P:85 DB:GHS LD:GHS PIC: PM: TM: LY:RON;OFF:REF: G:\PROJECT\Northrop Grumman\Superfund\2008\OU3\NY001464.1807\GWRM\Design Documents\Design Report\Final Design Report\Contract DWGs\add01464G01-02.dwg LAYOUT: 2 SAVED: 9/3/2008 3:36 PM ACADVER: 17.1S (LIMS TECH) PAGES: 17 PLOTSTYLETABLE: ARCADIS\_MELVILLE.CTB PLOTTED: 9/3/2008 4:08 PM BY: SANCHEZ, ADRIAN

PROJECTNAME: ...  
 IMAGES: 01464X02 BCP\_Aerial.jpg  
 01464X01 Wittek\_W.jpg  
 01464X00  
 XREFS: ACCESS\_RD\_NAD83

0 20' 40'  
 SCALE IN FEET


THIS BAR REPRESENTS ONE INCH ON THE ORIGINAL DRAWING.

USE TO VERIFY FIGURE REPRODUCTION SCALE

No.	Date	Revisions	By	Ckd

THIS DRAWING IS THE PROPERTY OF THE ARCADIS ENTITY IDENTIFIED IN THE TITLE BLOCK AND MAY NOT BE REPRODUCED OR ALTERED IN WHOLE OR IN PART WITHOUT THE EXPRESS WRITTEN PERMISSION OF SAME.


Professional Engineer's Name  
**WILLIAM S. WITTEK**  
 Professional Engineer's No.  
 080827  
 State NY Date Signed Project Mgr. CSG  
 Designed by CDL Drawn by BKD Checked by TEM



NORTHROP GRUMMAN CORPORATION • BETHPAGE, NEW YORK  
 OPERABLE UNIT 3 - FORMER GRUMMAN SETTLING PONDS


## TREATMENT BUILDING AREA PLAN

ARCADIS Project No.  
 NY001464.1807.00003  
 Date  
 JUNE 2008  
 ARCADIS  
 6723 Towpath Road  
 Box 66  
 Syracuse, NY 13214  
 Tel: 315-446-9120




LEGEND:

- X EXISTING FENCE
- [Stippled Box] EXISTING GRAVEL ROADWAY
- [Solid Grey Box] EXISTING SOIL AND GROUNDWATER PIPELINE TRENCH
- [Dotted Box] PROPOSED GRAVEL ROADWAY
- [Hatched Box] PROPOSED GROUNDWATER IRM PIPELINE TRENCH
- IRM INTERIM REMEDIAL MEASURE
- NWIRP NAVAL WEAPONS INDUSTRIAL RESERVE PLANT
- ECU EMISSION CONTROL UNIT



CITY: SYRACUSE, DIV: GROUP: 141, DB: GHS, KLS, KFS, LD: GHS, PIC: PM, TM: LYRONE, OFF: REF, G:\CAD\ACT\NY001464180700003\DWG\G101464M01.dwg, LAYOUT: 3, SAVER: 7/24/2008 10:50 AM, ACADVER: 17.0S (LMS TECH), PAGES: 17, PLOTTED: 8/28/2008 5:43 PM, BY: STEINBERGER, GEORGE, PROJECTNAME: ---, XREFS: 01464X00, IMAGES: W:\tek\w\jip




NOTE:  
 LEGEND, ABBREVIATIONS AND INTERLOCKS  
 SHOWN ON CONTRACT DRAWING 6.

NOT TO SCALE  
 THIS BAR REPRESENTS ONE INCH ON THE ORIGINAL DRAWING.  
 USE TO VERIFY FIGURE REPRODUCTION SCALE

No.	Date	Revisions	By	Ckd

THIS DRAWING IS THE PROPERTY OF THE ARCADIS ENTITY IDENTIFIED IN THE TITLE BLOCK AND MAY NOT BE REPRODUCED OR ALTERED IN WHOLE OR IN PART WITHOUT THE EXPRESS WRITTEN PERMISSION OF SAME.


Professional Engineer's Name  
**WILLIAM S. WITTEK**  
 Professional Engineer's No.  
 080827  
 State  
 NY  
 Date Signed  
 8/28/08  
 Project Mgr.  
 CSG  
 Designed by  
 CDL  
 Drawn by  
 KLS  
 Checked by  
 TEM



NORTHROP GRUMMAN CORPORATION • BETHPAGE, NEW YORK  
 OPERABLE UNIT 3 - FORMER GRUMMAN SETTLING PONDS  
**PIPING AND INSTRUMENTATION DIAGRAM #1**  
 MECHANICAL

ARCADIS Project No.  
 NY001464.1807.00003  
 Date  
 AUGUST 2008  
 ARCADIS  
 6723 Towpath Road  
 (P.O. Box 66)  
 Syracuse, NY 13214  
 Tel: 315.446.9120

CITY:SYRNY DIV:GROUP:141:ENV DB:GHS:KLS LD:GHS:PIC: PM: TM: LYRON:OFF:REF: PLOT: 8/28/2008 5:42 PM BY: STEINBERGER, GEORGE  
 G:\CAD\ACT\NY0014641180700003\DWG\01464M02.dwg LAYOUT: 4 SAVED: 7/25/2008 11:34 AM ACADVER: 17.0S (LMS TECH) PAGES: 17.0S (LMS TECH) PAGES: 17.0S (LMS TECH) PAGES: 17.0S (LMS TECH) PAGES: 17.0S (LMS TECH)  
 PROJECT NAME: ---  
 XREFS: 01464X00  
 IMAGES: W:\net\w\j\p



NOT TO SCALE

THIS BAR REPRESENTS ONE INCH ON THE ORIGINAL DRAWING.

USE TO VERIFY FIGURE REPRODUCTION SCALE

No.	Date	Revisions	By	Ckd

Professional Engineer's Name  
**WILLIAM S. WITTEK**

Professional Engineer's No.  
080827

State  
NY


Date Signed  
8/28/08

Project Mgr.  
CSG

Designed by  
CDL

Drawn by  
KLS

Checked by  
TEM



NORTHROP GRUMMAN CORPORATION • BETHPAGE, NEW YORK  
OPERABLE UNIT 3 - FORMER GRUMMAN SETTLING PONDS

## PIPING AND INSTRUMENTATION DIAGRAM #2


MECHANICAL

ARCADIS Project No.  
NY001464.1807.00003

Date  
AUGUST 2008

ARCADIS  
6723 Towpath Road  
(P.O. Box 66)  
Syracuse, NY 13214  
Tel: 315.446.9120

CITY: SYRACUSE DIV/GROUP: 85 DB: GHS LD: GHS PIC: PM: TM: LYRONE: OFF: REF: G:\CAD\ACT\NY014641807\00003\DWG\01464M03.dwg LAYOUT: 5 \_SAVED: 7/24/2008 10:50 AM ACADVER: 17.0S (LMS TECH) PAGES: 17 PAGES SETUP: --- PLOTSTYLETABLE: PLTCONT1.CTB PLOTTED: 8/28/2008 5:42 PM BY: STEINBERGER, GEORGE  
 XREFS: 01464X00 PROJECTNAME: ---  
 IMAGES: Witek V1.jpg




NOTE:  
 LEGEND, ABBREVIATIONS AND INTERLOCKS  
 SHOWN ON CONTRACT DRAWING 6.

NOT TO SCALE  
 THIS BAR REPRESENTS ONE INCH ON THE ORIGINAL DRAWING.  
 USE TO VERIFY FIGURE REPRODUCTION SCALE

No.	Date	Revisions	By	Ckd

Professional Engineer's Name  
**WILLIAM S. WITTEK**  
 Professional Engineer's No.  
 080827  
 State: NY Date Signed: 8/28/08 Project Mgr.: CSG  
 Designed by: CDL Drawn by: KLS Checked by: TEM




NORTHROP GRUMMAN CORPORATION • BETHPAGE, NEW YORK  
 OPERABLE UNIT 3 - FORMER GRUMMAN SETTLING PONDS  
**PIPING AND INSTRUMENTATION DIAGRAM #3**  
 MECHANICAL

ARCADIS Project No.  
 NY001464.1807.00003  
 Date  
 AUGUST 2008  
 ARCADIS  
 6723 Towpath Road  
 (P.O. Box 66)  
 Syracuse, NY 13214  
 Tel: 315.446.9120

CITY:SYRNY DIV:GROUPE-141 DBKLS LD:GHS PIC: PM: LYRON=OFF=REF\* G:CADACTNY001464180700003DDWG01464G05.dwg LAYOUT: 6\_SAVED: 7/24/2008 10:47 AM ACADVER: 7.05 (LMS TECH) PAGES: 6 PLOTTED: 8/28/2008 5:39 PM BY: STEINBERGER, GEORGE  
 XREFS: 01464X00 PROJECTNAME: Wtnek V1.jpg

**EQUIPMENT LEGEND:**



**ABBREVIATIONS:**

A	AIR	LI	LEVEL INDICATOR
ABV	ACTIVATED BLOCK VALVE	LIC	LEVEL INDICATING CONTROLLER
AL	ALUMINUM	LSH	LEVEL SWITCH HIGH
AS	AIR STRIPPER	LSL	LEVEL SWITCH LOW
BF	BAG FILTER	LT	LEVEL TRANSMITTER
Ø	DIAMETER	MV	MANUAL VALVE
FAH	FLOW ALARM HIGH	NC	NORMALLY CLOSED
FAL	FLOW ALARM LOW	NO	NORMALLY OPEN
FE	FLOW ELEMENT	PAH	PRESSURE ALARM HIGH
FI	FLOW INDICATOR	PAL	PRESSURE ALARM LOW
FIT	FLOW INDICATING TRANSMITTER	PT	PRESSURE TRANSMITTER
FM	FLOW METER	PI	PRESSURE INDICATOR
FO	FAIL OPEN	PLC	PROGRAMMABLE LOGIC CONTROLLER
FP	FLOOR PENETRATION	PPZ	POTASSIUM PERMANANATE ZEOLITE
FQI	TOTALIZED FLOW INDICATOR	PSL	PRESSURE SWITCH LOW
GAC	VAPOR-PHASE GRANULAR ACTIVATED CARBON	PSH	PRESSURE SWITCH HIGH
GA	GAUGE HIGH DENSITY	PVC	POLYVINYL CHLORIDE
HDPE	POLYETHYLENE	SCH	SCHEDULE
HOA	HAND-OFF-AUTO	SDR	STANDARD DIMENSION RATIO
HP	HORSEPOWER	TAL	TEMPERATURE ALARM LOW
HS	HAND SWITCH	TI	TEMPERATURE INDICATOR
INS	INSULATED	TI	TEMPERATURE INDICATING TRANSMITTER
KI	PUMP RUN TIME INDICATOR	TYP	TYPICAL
KW	KILOWATT	RW	RECOVERY WELL
LAH	LEVEL ALARM HIGH	UG	UNDERGROUND
LAHH	LEVEL ALARM HIGH-HIGH	VFD	VARIABLE FREQUENCY DRIVE
LAL	LEVEL ALARM LOW	W	WATER
LALL	LEVEL ALARM LOW-LOW	YI	RUN INDICATION
LE	LEVEL ELEMENT	ZI	POSITION INDICATOR

**PLC INPUT/OUTPUT SCHEDULE:**

**ANALOG INPUTS:**

- PT-110
- PT-120
- PT-130
- PT-140
- FIT-110
- FIT-120
- FIT-130
- FIT-140
- LI-400
- FIT-500
- PT-500
- TT-500
- PT-700
- FIT-700
- TT-900

**DISCRETE INPUTS:**

- YI-110
- YI-120
- YI-130
- YI-140
- KI-110
- KI-120
- KI-130
- KI-140
- PSL-111
- PSL-121
- PSL-131
- PSL-141
- PAH-400
- PAL-400
- LAH-400
- YI-410
- LSH-900

**DISCRETE OUTPUTS:**

- P-110 SHUTDOWN
- P-120 SHUTDOWN
- P-130 SHUTDOWN
- P-140 SHUTDOWN
- AIR STRIPPER SHUTDOWN
- P-900 ON/OFF
- AUTODIALER
- AUTODIALER
- AUTODIALER
- AUTODIALER
- HIGH PRESSURE AT AIR STRIPPER (PAH-400), SIGNAL ALARM AT PLC AND ACTIVATE AUTODIALER. AIR STRIPPER WILL BE SHUT DOWN LOCALLY BY AIR STRIPPER CONTROL PANEL ON A 5 MINUTE DELAY.
- LOW PRESSURE AT AIR STRIPPER (PAL-400), SIGNAL ALARM AT PLC AND ACTIVATE AUTODIALER. AIR STRIPPER WILL BE SHUT DOWN LOCALLY BY AIR STRIPPER CONTROL PANEL ON A 5 MINUTE DELAY.
- HIGH SUMP LEVEL AT AIR STRIPPER (LAH-400), SHUT DOWN EXTRACTION WELL PUMPS, SIGNAL ALARM AT PLC AND ACTIVATE AUTODIALER. AIR STRIPPER WILL BE SHUT DOWN LOCALLY BY AIR STRIPPER CONTROL PANEL ON A 5 MINUTE DELAY.

**PIPE IDENTIFICATION TAGS:**

DIAMETER - SERVICE - SCHEDULE - MATERIAL - OTHER

DIAMETER: NOMINAL DIAMETER (INCHES)

SERVICE:  
A = AIR  
W = WATER

SCHEDULE = US STANDARD UNITS

MATERIAL:  
AL = ALUMINUM  
HDPE = HIGH DENSITY POLYETHYLENE  
PVC = POLYVINYL CHLORIDE

OTHER:  
B = BARE  
INS = INSULATED  
UG = UNDERGROUND

**MAIN PLC INTERLOCK SCHEDULE:**

- LOW PRESSURE IN P-110 INFLUENT LINE (PAL-110), SHUT DOWN P-110, SIGNAL ALARM AT PLC AND ACTIVATE AUTODIALER
- HIGH PRESSURE IN P-110 INFLUENT LINE (PAH-110), SHUT DOWN P-110, SIGNAL ALARM AT PLC AND ACTIVATE AUTODIALER
- LOW FLOW IN P-110 INFLUENT LINE (FAL-110), SHUT DOWN P-110, SIGNAL ALARM AT PLC AND ACTIVATE AUTODIALER
- LOW PRESSURE IN P-120 INFLUENT LINE (PAL-120), SHUT DOWN P-120, SIGNAL ALARM AT PLC AND ACTIVATE AUTODIALER
- HIGH PRESSURE IN P-120 INFLUENT LINE (PAH-120), SHUT DOWN P-120, SIGNAL ALARM AT PLC AND ACTIVATE AUTODIALER
- LOW FLOW IN P-120 INFLUENT LINE (FAL-120), SHUT DOWN P-120, SIGNAL ALARM AT PLC AND ACTIVATE AUTODIALER
- LOW PRESSURE IN P-130 INFLUENT LINE (PAL-130), SHUT DOWN P-130, SIGNAL ALARM AT PLC AND ACTIVATE AUTODIALER
- HIGH PRESSURE IN P-130 INFLUENT LINE (PAH-130), SHUT DOWN P-130, SIGNAL ALARM AT PLC AND ACTIVATE AUTODIALER
- LOW FLOW IN P-130 INFLUENT LINE (FAL-130), SHUT DOWN P-130, SIGNAL ALARM AT PLC AND ACTIVATE AUTODIALER
- LOW PRESSURE IN P-140 INFLUENT LINE (PAL-140), SHUT DOWN P-140, SIGNAL ALARM AT PLC AND ACTIVATE AUTODIALER
- HIGH PRESSURE IN P-140 INFLUENT LINE (PAH-140), SHUT DOWN P-140, SIGNAL ALARM AT PLC AND ACTIVATE AUTODIALER
- LOW FLOW IN P-140 INFLUENT LINE (FAL-140), SHUT DOWN P-140, SIGNAL ALARM AT PLC AND ACTIVATE AUTODIALER
- LOW FLOW AT COMBINED AIR STRIPPER INFLUENT LINE (FAL-200), SHUT DOWN EXTRACTION WELL PUMPS, SHUT DOWN AIR STRIPPER SYSTEM (5 MINUTE DELAY) SIGNAL ALARM AT PLC AND ACTIVATE AUTODIALER
- HIGH FLOW AT COMBINED AIR STRIPPER INFLUENT LINE (FAH-200), SHUT DOWN EXTRACTION WELL PUMPS, SHUT DOWN AIR STRIPPER SYSTEM (5 MINUTE DELAY) SIGNAL ALARM AT PLC AND ACTIVATE AUTODIALER. AIR STRIPPER SHUT DOWN DELAY WILL BE CONTROLLED BY AIR STRIPPER LOCAL CONTROL PANEL.
- HIGH PRESSURE AT AIR STRIPPER (PAH-400), SIGNAL ALARM AT PLC AND ACTIVATE AUTODIALER. AIR STRIPPER WILL BE SHUT DOWN LOCALLY BY AIR STRIPPER CONTROL PANEL ON A 5 MINUTE DELAY.
- LOW PRESSURE AT AIR STRIPPER (PAL-400), SIGNAL ALARM AT PLC AND ACTIVATE AUTODIALER. AIR STRIPPER WILL BE SHUT DOWN LOCALLY BY AIR STRIPPER CONTROL PANEL ON A 5 MINUTE DELAY.
- HIGH SUMP LEVEL AT AIR STRIPPER (LAH-400), SHUT DOWN EXTRACTION WELL PUMPS, SIGNAL ALARM AT PLC AND ACTIVATE AUTODIALER. AIR STRIPPER WILL BE SHUT DOWN LOCALLY BY AIR STRIPPER CONTROL PANEL ON A 5 MINUTE DELAY.
- LOW PRESSURE SWITCH (PSL-111) IN P-110 ACTIVATED (DE-ENERGIZED), SHUT DOWN WELL PUMPS.
- LOW PRESSURE SWITCH (PSL-121) IN P-120 ACTIVATED (DE-ENERGIZED), SHUT DOWN WELL PUMPS.
- LOW PRESSURE SWITCH (PSL-131) IN P-130 ACTIVATED (DE-ENERGIZED), SHUT DOWN WELL PUMPS.
- LOW PRESSURE SWITCH (PSL-141) IN P-140 ACTIVATED (DE-ENERGIZED), SHUT DOWN WELL PUMPS.
- HIGH PRESSURE SWITCH (PSH-AS) AT AIR STRIPPER ACTIVATED, SHUT DOWN WELL PUMPS.
- LOW PRESSURE SWITCH (PSL-AS) AT AIR STRIPPER ACTIVATED, SHUT DOWN WELL PUMPS.
- HIGH LEVEL SWITCH (LSH-AS) AT AIR STRIPPER ACTIVATED, SHUT DOWN WELL PUMPS.

- LOW AIR FLOW AT AIR STRIPPER BLOWER DISCHARGE LINE (FAL-500), SHUT DOWN EXTRACTION WELL PUMPS. SHUT DOWN AIR STRIPPER SYSTEM (5 MINUTE DELAY), SIGNAL ALARM AT PLC AND ACTIVATE AUTODIALER. AIR STRIPPER SHUT DOWN DELAY WILL BE CONTROLLED BY AIR STRIPPER LOCAL CONTROL PANEL.
- HIGH AIR FLOW AT AIR STRIPPER BLOWER DISCHARGE LINE (FAH-500), SHUT DOWN EXTRACTION WELL PUMPS. SHUT DOWN AIR STRIPPER SYSTEM (5 MINUTE DELAY), SIGNAL ALARM AT PLC AND ACTIVATE AUTODIALER. AIR STRIPPER SHUT DOWN DELAY WILL BE CONTROLLED BY AIR STRIPPER LOCAL CONTROL PANEL.
- LOW AIR TEMPERATURE AT AIR STRIPPER BLOWER DISCHARGE (TAL-500), SHUT DOWN EXTRACTION WELL PUMPS. SHUT DOWN AIR STRIPPER SYSTEM (5 MINUTE DELAY), SIGNAL ALARM AT PLC AND ACTIVATE AUTODIALER. AIR STRIPPER SHUT DOWN DELAY WILL BE CONTROLLED BY AIR STRIPPER LOCAL CONTROL PANEL.
- LOW AIR PRESSURE AT AIR STRIPPER BLOWER DISCHARGE LINE (PAL-500), SHUT DOWN EXTRACTION WELL PUMPS, SHUT DOWN AIR STRIPPER SYSTEM (5 MINUTE DELAY), SIGNAL ALARM AT PLC AND ACTIVATE AUTODIALER. AIR STRIPPER SHUT DOWN DELAY WILL BE CONTROLLED BY AIR STRIPPER LOCAL CONTROL PANEL.
- HIGH-HIGH PRESSURE AT AIR STRIPPER PUMP DISCHARGE LINE (PAHH-700), SHUT DOWN EXTRACTION WELL PUMPS, SHUT DOWN AIR STRIPPER SYSTEM (5 MINUTE DELAY), SIGNAL ALARM AT PLC AND ACTIVATE AUTODIALER. AIR STRIPPER SHUT DOWN DELAY WILL BE CONTROLLED BY AIR STRIPPER LOCAL CONTROL PANEL.
- HIGH LEVEL AT BUILDING SUMP (LAH-900), SHUT DOWN EXTRACTION WELL PUMPS, SHUT DOWN AIR STRIPPER SYSTEM (5 MINUTE DELAY), SIGNAL ALARM AT PLC AND ACTIVATE AUTODIALER. AIR STRIPPER SHUT DOWN DELAY WILL BE CONTROLLED BY AIR STRIPPER LOCAL CONTROL PANEL.
- LOW AIR TEMPERATURE AT BUILDING (TAH-900), SIGNAL ALARM AT PLC AND ACTIVATE AUTODIALER.
- LOW PRESSURE IN P-110 INFLUENT LINE (PAL-111), SIGNAL ALARM AT PLC AND ACTIVATE AUTODIALER.
- LOW PRESSURE IN P-120 INFLUENT LINE (PAL-121), SIGNAL ALARM AT PLC AND ACTIVATE AUTODIALER.
- LOW PRESSURE IN P-130 INFLUENT LINE (PAL-131), SIGNAL ALARM AT PLC AND ACTIVATE AUTODIALER.
- LOW PRESSURE IN P-140 INFLUENT LINE (PAL-141), SIGNAL ALARM AT PLC AND ACTIVATE AUTODIALER.
- HIGH PRESSURE AT AIR STRIPPER PUMP DISCHARGE LINE (PAH-700), OPEN SECONDARY VALVE (MBV-402 OR MBV-401) AND CLOSE PRIMARY VALVE (MBV-401 OR MBV-402). PRIMARY AND SECONDARY VALVE DESIGNATION SHALL ALTERNATE AFTER OPERATOR ACKNOWLEDGES THAT PRIMARY BAG FILTERS HAVE BEEN CHANGED.
- IN THE EVENT THAT ALL WELL PUMPS ARE SHUT DOWN BY PLC, AIR STRIPPER SYSTEM SHALL BE SHUT DOWN.


**AIR STRIPPER LOCAL CONTROL PANEL INTERLOCK SCHEDULE:**

- HIGH PRESSURE AT AIR STRIPPER (PSH-AS), SIGNAL DRY CONTACT FOR EXTERNAL SHUT DOWN/INDICATION, SIGNAL LOCAL PANEL ALARM LIGHT, AND SHUT DOWN AIR STRIPPER BLOWER (5 MINUTE DELAY).
- LOW PRESSURE AT AIR STRIPPER (PSL-AS), SIGNAL DRY CONTACT FOR EXTERNAL SHUT DOWN/INDICATION, SIGNAL LOCAL PANEL ALARM LIGHT, AND SHUT DOWN AIR STRIPPER BLOWER (5 MINUTE DELAY).
- HIGH SUMP LEVEL AT AIR STRIPPER (LSH-AS), SIGNAL DRY CONTACT FOR EXTERNAL SHUT DOWN/INDICATION, SIGNAL LOCAL PANEL ALARM LIGHT, AND SHUT DOWN AIR STRIPPER BLOWER (5 MINUTE DELAY).
- AIR STRIPPER DISCHARGE PUMP SPEED WILL BE CONTROLLED BY VFD BASED ON AIR STRIPPER SUMP LEVEL SET POINT.


NOT TO SCALE  THIS BAR REPRESENTS ONE INCH ON THE ORIGINAL DRAWING.	USE TO VERIFY FIGURE REPRODUCTION SCALE	Professional Engineer's Name <b>WILLIAM S. WITTEK</b>				NORTHROP GRUMMAN CORPORATION • BETHPAGE, NEW YORK OPERABLE UNIT 3 - FORMER GRUMMAN SETTLING PONDS	ARCADIS Project No. NY001464.1807.00003	Date AUGUST 2008	<b>6</b>
		State NY	Date Signed 8/28/08						
No. Date Revisions By Ckd		Professional Engineer's No. 080827		State NY		Date Signed 8/28/08		Project Mgr. CSG	
THIS DRAWING IS THE PROPERTY OF THE ARCADIS ENTITY IDENTIFIED IN THE TITLE BLOCK AND MAY NOT BE REPRODUCED OR ALTERED IN WHOLE OR IN PART WITHOUT THE EXPRESS WRITTEN PERMISSION OF SAME.		Designed by CDL		Drawn by KLS		Checked by TEM		MECHANICAL	

CITY: SYRACUSE, NY DIV: GROUP 141 DB: GHS KLS KEW LD: GHS PIC: PM: TM: LYRONE OFF: REF: G:\CAD\ACT\NY001464180700003\DWG\01464G01.dwg LAYOUT: 7 SAVED: 8/28/2008 4:23 PM ACADVER: 17.05 (LMS TECH) PAGES: 17.05 (LMS TECH) PLOT: 8/28/2008 5:41 PM BY: STEINBERGER, GEORGE  
 PROJECT NAME: WITTEK W I J P G  
 XREFS: 01464X00  
 IMAGES: WITTEK W I J P G

1  
10



- NOTES:
- REFER TO CONTRACT DRAWINGS 9 AND 10 FOR MISCELLANEOUS SECTIONS AND DETAILS.
  - REFER TO CONTRACT DRAWING 15 FOR EQUIPMENT POWER, LIGHTING, HVAC AND GROUNDING PLAN.
  - REFER TO CONTRACT DRAWING 16 FOR INSTRUMENTATION PLAN.
  - REFER TO CONTRACT DRAWINGS 18 THROUGH 21 FOR FOUNDATION AND BUILDING DETAILS AND SPECIFICATIONS.
  - REFER TO CONTRACT DRAWINGS 3, 4, AND 5 FOR VALVE, SAMPLE TAP, PRESSURE GAUGE, AND TEMPERATURE GAUGE LOCATIONS.
  - REFER TO CONTRACT DRAWING 6 FOR LEGEND AND ABBREVIATIONS.
  - REFER TO CONTRACT DRAWING 11 FOR EQUIPMENT, INSTRUMENT, AND MECHANICAL SPECIFICATIONS.
  - ACTUAL LOCATION OF BAG FILTER SYSTEM UNITS AND ASSOCIATED PIPING SUBJECT TO CHANGE AS DETERMINED IN FIELD.



No.	Date	Revisions	By	Ckd

THIS DRAWING IS THE PROPERTY OF THE ARCADIS ENTITY IDENTIFIED IN THE TITLE BLOCK AND MAY NOT BE REPRODUCED OR ALTERED IN WHOLE OR IN PART WITHOUT THE EXPRESS WRITTEN PERMISSION OF SAME.

Professional Engineer's Name  
**WILLIAM S. WITTEK**  
Professional Engineer's No.  
080827  
State  
NY  
Date Signed  
8/28/08  
Project Mgr.  
CSG  
Designed by  
CDL  
Drawn by  
TEM  
Checked by  
TEM




NORTHROP GRUMMAN CORPORATION • BETHPAGE, NEW YORK  
OPERABLE UNIT 3 - FORMER GRUMMAN SETTLING PONDS  
**EQUIPMENT LAYOUT**  
MECHANICAL


ARCADIS Project No.  
NY001464.1807.00003  
Date  
AUGUST 2008  
ARCADIS  
6723 Towpath Road  
(P.O. Box 66)  
Syracuse, NY 13214  
Tel: 315.446.9120




CITY:SYRACUS DIV:GROUP:85 DB:GHS LD:GHS PIC: PM: TM: LYNONE:OFF:REF: G:\CAD\ACT\NY0014641807\000303\DWG\01464G04.dwg LAYOUT: 8 \_SAVED: 7/24/2008 10:47 AM ACADVER: 17.05 (LMS TECH) PAGES: 10 PAGES SETUP: PLOT: PLOT STYLE TABLE: PLTCONT1.ctb PLOTTED: 8/28/2008 5:40 PM BY: STEINBERGER, GEORGE  
 XREFS: 0:1464X00  
 IMAGES: Witek VJ.jpg  
 PROJECT NAME:



**PLAN**  
NOT TO SCALE



**TYPICAL RECOVERY WELL DETAIL**  
NOT TO SCALE



**PITLESS ADAPTER**  
NOT TO SCALE

**WELL INSTALLATION PROCEDURE:**

- EXCAVATE TO 4' AROUND WELL CASING TO PRODUCE A 6' x 6' x 4' DEEP AREA FOR SETTING CONCRETE MANHOLE WELL ENCLOSURE.
- WELD PITLESS ADAPTER TO 6" WELL CASING PIPE.
- WELD 7'0" x 18" LONG UPPER CASING ON PITLESS ADAPTER.
- CONNECT EXISTING 3" (OR 4"0) HDPE PIPE TO PITLESS ADAPTER USING 3"0 HDPE PIPE WITH 3"0 MALE NPT END.
- BACKFILL EXCAVATION TO DEPTH OF 2' $\frac{1}{2}$ ' BELOW GRADE (BED HDPE PIPE IN SAND OR PEA GRAVEL PRIOR TO BACKFILL).
- SET 4'0 CONCRETE MANHOLE WELL ENCLOSURE.
- INSTALL CONDUIT TO INSIDE OF MANHOLE ENCLOSURE AND ATTACH JUNCTION BOX TO MANHOLE INTERIOR.
- PULL PUMP POWER WIRING TO MANHOLE VIA NEW CONDUIT.
- PREPARE PUMP BY ATTACHING THE APPROPRIATE LENGTH OF 2"0 HDPE PIPE (OUT FITTED WITH THE INTERNAL COMPONENT OF THE PITLESS ADAPTER) THE APPROPRIATE LENGTH OF 3/32"  $\phi$  SUPPORT CABLE AND THE APPROPRIATE LENGTH OF ELECTRICAL POWER CABLES.
- TEMPORARILY CONNECT POWER TO PUMP AND BUMP PUMP TO CHECK FOR PROPER ROTATION. MARK WIRES TO NOTE PROPER CONNECTIONS, AND THEN DISCONNECT TEMPORARY ELECTRICAL CONNECTION TO THE PUMP.
- INSTALL THE WELL PUMP TO THE APPROPRIATE DEPTH
- SECURE 3/32" SUPPORT CABLE TO EYE HOOK INSTALLED IN THE UPPER WELL CASING ABOVE THE PITLESS ADAPTER.
- THREAD PUMP POWER CABLES THROUGH WELL SEAL AND INSTALL WELL SEAL.
- MAKE ELECTRICAL CONNECTIONS TO PROVIDE POWER TO PUMP.
- PLACE COVER ON MANHOLE WELL ENCLOSURE.
- BACKFILL AND COMPACT AREA AROUND MANHOLE WELL ENCLOSURE.
- RESTORE ANY DISTURBED SURFACES TO ORIGINAL CONDITION.

THIS BAR REPRESENTS ONE INCH ON THE ORIGINAL DRAWING. USE TO VERIFY FIGURE REPRODUCTION SCALE	No.	Date	Revisions	By	Ckd	
	THIS DRAWING IS THE PROPERTY OF THE ARCADIS ENTITY IDENTIFIED IN THE TITLE BLOCK AND MAY NOT BE REPRODUCED OR ALTERED IN WHOLE OR IN PART WITHOUT THE EXPRESS WRITTEN PERMISSION OF SAME.					

Professional Engineer's Name  
**WILLIAM S. WITTEK**  
Professional Engineer's No.  
080827  
State  
NY  
Date Signed  
8/28/08  
Project Mgr.  
CSG  
Designed by  
CDL  
Drawn by  
TEM




NORTHROP GRUMMAN CORPORATION • BETHPAGE, NEW YORK  
OPERABLE UNIT 3 - FORMER GRUMMAN SETTLING PONDS

**WELL DETAIL**

MECHANICAL


ARCADIS Project No.  
NY001464.1807.00003  
Date  
AUGUST 2008  
ARCADIS  
6723 Towpath Road  
(P.O. Box 66)  
Syracuse, NY 13214  
Tel: 315.446.9120

CITY:SYRACUS DIV:GROUP:141/ENV DB:GHS:KLS LD:GHS PIC: PM: TM: LYRON:OFF=REF\*  
 G:\CAD\ACT\NY0014641807\00003\DWG\G01464G07.dwg LAYOUT: 9\_SAVED: 7/24/2008 10:49 AM ACADVER: 17.0S (LMS TECH) PAGES: 17.0S (LMS TECH) PAGES: 17.0S (LMS TECH) PAGES: 17.0S (LMS TECH) PAGES: 17.0S (LMS TECH) PAGES: 17.0S (LMS TECH)  
 PROJECTNAME: ---  
 XREFS: 01464X00  
 IMAGES: W:\tek\w\j\p




NOTE:  
 DEPTH OF TRENCH VARIES FROM 2'-6" TO 5'-0".

**EXISTING TRENCH DETAIL 1**  
 NOT TO SCALE




NOTE:  
 EXTEND REINFORCEMENT A MINIMUM OF 48 BAR DIAMETERS BEYOND THE FACE OF THE OPENING

**TYPICAL FLOOR SLAB PENETRATION 3**  
 NOT TO SCALE



NOTE:  
 1. GRAVEL ROADWAY TO BE RESTORED TO ORIGINAL CONDITIONS.

**TRENCH DETAIL AT GRAVEL ROADWAY CROSSING 2**  
 NOT TO SCALE



**TYPICAL GRAVEL ACCESS ROAD DETAIL 4**  
 NOT TO SCALE

THIS BAR REPRESENTS ONE INCH ON THE ORIGINAL DRAWING.	USE TO VERIFY FIGURE REPRODUCTION SCALE	No.	Date	Revisions	By	Ckd
		THIS DRAWING IS THE PROPERTY OF THE ARCADIS ENTITY IDENTIFIED IN THE TITLE BLOCK AND MAY NOT BE REPRODUCED OR ALTERED IN WHOLE OR IN PART WITHOUT THE EXPRESS WRITTEN PERMISSION OF SAME.				

Professional Engineer's Name <b>WILLIAM S. WITTEK</b>		
Professional Engineer's No. 080827		
State NY	Date Signed 8/28/08	Project Mgr. CSG
Designed by CDL	Drawn by	Checked by TEM




**ARCADIS**  
 ARCADIS OF NEW YORK, INC.

NORTHROP GRUMMAN CORPORATION • BETHPAGE, NEW YORK  
 OPERABLE UNIT 3 - FORMER GRUMMAN SETTLING PONDS

**MISCELLANEOUS SECTIONS AND DETAILS**

ARCADIS Project No. NY001464.1807.00003
Date AUGUST 2008
ARCADIS 6723 Towpath Road (P.O. Box 66) Syracuse, NY 13214 Tel: 315.446.9120



CITY: SYRACUSE DIV/GROUP: 85 DB: GHS LD: GHS PIC: PM: TM: LYRONE: OFF: REF: G:\CAD\ACT\NY001464180700003\DWG\01464G06.dwg LAYOUT: 10 SAVED: 7/24/2008 10:49 AM ACADVER: 17.05 (LMS TECH) PAGES: 17.05 (LMS TECH) PLOTTED: 8/28/2008 5:39 PM BY: STEINBERGER, GEORGE





**NOTE:**

1. ALL DUCTING WILL BE INSULATED WITH TRYMER 2000 FOAM INSULATION NOT SHOWN ON THIS DETAIL FOR CLARITY. SEE CONTRACT DRAWING 11 FOR SPECIFICATIONS.
2. ECU'S SHALL BE INSULATED.

**DUCT PROFILE 1**



**INFLUENT PIPE PROFILE 2**



**NOTE:**


1. OTHER OPTIONS TO SUPPORT STACK WILL BE DETERMINED IN THE FIELD.

**STACK DETAIL 5**

NOT TO SCALE

SCALE(S) AS INDICATED				
THIS BAR REPRESENTS ONE INCH ON THE ORIGINAL DRAWING:	USE TO VERIFY FIGURE REPRODUCTION SCALE			
No.	Date	Revisions	By	Ckd
THIS DRAWING IS THE PROPERTY OF THE ARCADIS ENTITY IDENTIFIED IN THE TITLE BLOCK AND MAY NOT BE REPRODUCED OR ALTERED IN WHOLE OR IN PART WITHOUT THE EXPRESS WRITTEN PERMISSION OF SAME.				

Professional Engineer's Name  
**WILLIAM S. WITTEK**  
Professional Engineer's No.  
080827  
State  
NY  
Date Signed  
8/28/08  
Project Mgr.  
CSG  
Designed by  
CDL  
Drawn by  
BKD  
Checked by  
TEM



NORTHROP GRUMMAN CORPORATION • BETHPAGE, NEW YORK  
OPERABLE UNIT 3 - FORMER GRUMMAN SETTLING PONDS  
**MISCELLANEOUS SECTIONS AND DETAILS**  
MECHANICAL

ARCADIS Project No.  
NY001464.1807.00003  
Date  
AUGUST 2008  
ARCADIS  
6723 Towpath Road  
(P.O. Box 66)  
Syracuse, NY 13214  
Tel: 315.446.9120

CITY: SYRACUSE DIV/GROUP: 141 DB/KLS LD/GHS PIC: PM: TYRONE OFF=REF\* G/CAD/ACT/NY00146418070000303DWDWG01464G08.dwg LAYOUT: 11 SAVED: 7/24/2008 10:49 AM ACADVER: 17.05 (LMS TECH) PAGES: 17.05 (LMS TECH) PAGES SETUP: --- PLOT STYLE TABLE: PLTCONT1.CTB PLOTTED: 8/28/2008 5:38 PM BY: STEINBERGER, GEORGE  
 XREFS: 01464X00 PROJECT NAME: ---  
 IMAGES: W:\tek\w\j\p

**INSTRUMENT SPECIFICATIONS:**

1. FLOWMETERS SHALL BE 2-INCH (FIT-110, -140), 3-INCH (FIT-120, -130) or 4-INCH (FIT-700) MAGNETOFLW BADGER MAGNETIC WAFER-STYLE FLOWMETERS OR EQUAL WITH LINER SUITABLE FOR WATER SERVICE, 316 SS ELECTRODES, GROUNDING RINGS, AND INTEGRAL MOUNT ELECTRONICS WITH LOCAL RATE AND TOTAL DISPLAY.
2. LIQUID PRESSURE TRANSMITTERS (PT-110, -120, -130, -140, -700) SHALL BE FOXBORO MODEL IGP10-T22D1F-M1L1 GAUGE PRESSURE TRANSMITTER OR EQUAL WITH LOCAL DISPLAY, 10-300 PSI RANGE, STAINLESS STEEL WETTED MATERIAL, 4-20 MA OUTPUT, LOOP POWERED.
3. AIR PRESSURE TRANSMITTER (PT-500) SHALL BE FOXBORO MODEL IGP20-T22B21F-M1L1 GAUGE PRESSURE TRANSMITTER OR EQUAL WITH LOCAL DISPLAY, 3.5-200 INCHES H2O RANGE, STAINLESS STEEL WETTED MATERIAL, 4-20 MA OUTPUT, LOOP POWERED.
4. TEMPERATURE TRANSMITTERS (TT-500 - TT-900) SHALL BE FOXBORO MODEL RTT15-T1WCQNAF-L1 INSERTION-STYLE TEMPERATURE TRANSMITTER OR EQUAL WITH LOCAL DISPLAY, NEMA RATED ENCLOSURE, 3-INCH RTD WITH NO WELL, 4-20 MA OUTPUT, LOOP POWERED.
5. AIR FLOW METER (FIT-500) SHALL BE SIERRA MODEL 620S-L06M1EN2V4DD0 INSERTION-STYLE THERMA MASS METER OR EQUAL FOR AIR FLOW, 18-30 VDC, 3/8-INCH DIAMETER PROBE, 4-20 MA OUTPUT WITH DISPLAY.
6. TEMPERATURE INDICATORS (TI-501, -601) SHALL BE WIKA MODEL 232 OR EQUAL 3-INCH INSERTION-STYLE BIMETAL THERMOMETER WITH 4-INCH STEM, LOWER MOUNT, 316 SS WELL WITH U OF 2.5 INCHES, 0-140°F RANGE.
7. LIQUID PRESSURE GAUGES (PI-110, -120, -130, -140, -800) SHALL BE WIKA MODEL 232 OR EQUAL 4.5-INCH PROCESS GAUGE WITH LOWER MOUNT, 316 SS CONNECTION, 0-30 PSI RANGE.
8. AIR PRESSURE GAUGES (PI-501, -502, -601, -602, -603) SHALL BE WIKA MODEL 232 OR EQUAL 4.5-INCH LOW PRESSURE PROCESS GAUGE WITH LOWER MOUNT, 316 SS CONNECTION, 0-20 INCHES H2O RANGE.
9. LEVEL SWITCH (LSL-300) SHALL BE GEMS MODEL MBLU40T OR EQUAL FLOAT SWITCH, NORMALLY OPEN OUTPUT WITH 40' CABLE.
10. PRESSURE SWITCH (PSL-111, -121, -131, -141) SHALL BE ASHCROFT TYPE 400 B SERIES WITH WATER TIGHT ENCLOSURE AND DUAL SPDT SWITCHES. 15 PSI MAXIMUM RANGE.

**CONTROL SYSTEM SPECIFICATIONS**

1. CONTROL SYSTEM SHALL BE AN ALLEN-BRADLEY PLC CONTROL SYSTEM WITH THE FOLLOWING FEATURES:  
 SLOT RACK  
 SLC 5/04 CONTROLLER  
 ETHERNET MODULE  
 POWER SUPPLY  
 ANALOG INPUT MODULES  
 ANALOG OUTPUT MODULES  
 DC INPUT MODULES  
 DC OUTPUT MODULES  
 UPS AND POWER-LOSS SENSOR
2. CONTROL SYSTEM USER INTERFACE SHALL BE AN ARISTA ARP-1715BP-RB103H-T PC WITH THE FOLLOWING FEATURES:  
 STANDARD POWER COATED ALUMINUM  
 15" ELO RESISTIVE TOUCH DISPLAY  
 P4 2.8GHZ CPU  
 RAM 1 GB  
 HARD DRIVE 40 GB  
 CD ROM  
 OPERATING SYSTEM XP PROFESSIONAL  
 AC POWER SUPPLY  
 INCREASED CONTROL PANEL DEPTH  
 ADDITIONAL PROGRAM AND TEST TIME ADDED
3. SYSTEM AUTODIALER SHALL BE A SENSAPHONE WITH TELULAR CELLULAR MODEM CELL MODEM SHALL INCLUDE AN EXTERNAL ANTENNA WITH 15' OF WHIP

**MAJOR EQUIPMENT SPECIFICATIONS**

1. WELL PUMPS (P-110, -140) SHALL BE GRUNDFOS MODEL 40S30-9 OR EQUAL SUBMERSIBLE WELL PUMPS WITH 3 HP, 460 V, 3 PHASE MOTORS CAPABLE OF 40 GPM AT 200 FEET TDH.
2. WELL PUMPS (P-120, -130) SHALL BE GRUNDFOS MODEL 75S75-9 OR EQUAL SUBMERSIBLE WELL PUMPS WITH 7.5 HP, 460 V, 3 PHASE MOTORS CAPABLE OF 85 GPM AT 200 FEET TDH.
3. AIR STRIPPER (AS-400) SHALL BE BISCO ENVIRONMENTAL/NEEP SYSTEMS MODEL 31261 SHALLOW TRAY SYSTEM OR EQUAL WITH 6 TRAYS, 316 SS CONSTRUCTION, WITH A MAXIMUM FLOW RATE OF 425 GPM, AND THE FOLLOWING COMPONENTS MOUNTED ON THE EQUIPMENT SKID:  
 INDUCED-DRAFT BLOWER (B-400) WITH A 40 HP, 460V, 3 PHASE MOTOR CAPABLE OF 1800 CFM AT A PRESSURE OF 45" W.C.  
 DISCHARGE PUMP (P-400) WITH A 7.5 HP, 460 V, 3 PHASE MOTOR CAPABLE OF 250 GPM AT 75 FEET TDH CONTROLLED BY A VARIABLE FREQUENCY DRIVE BASED ON LIQUID LEVEL IN THE STRIPPER SUMP.  
 INSTRUMENTATION AS SHOWN ON CONTRACT DRAWING 4.  
 LOCAL CONTROL PANEL WITH FAIL SAFE CIRCUITRY DRY CONTACTS OUTPUTS TO MAIN TREATMENT SYSTEM PLC; SEE CONTRACT DRAWING 6 FOR INTERLOCK REQUIREMENTS.
4. BAG FILTER VESSELS (BF-401, -402, -403, -404) SHALL BE FILTRATION SYSTEMS MODEL NC-223-V OR EQUAL BAG FILTER HOUSING OF CARBON STEEL CONSTRUCTION RATED AT 150 PSIG.
5. GRANULAR ACTIVATED CARBON VESSELS (C-501, -502) SHALL BE TIGG MODEL NB-8 VAPOR-PHASE ADSORBER OR EQUAL OF CARBON STEEL CONSTRUCTION CONTAINING 6,000 LBS. OF GAC PER VESSEL.
6. POTASSIUM PERMANGANATE VESSELS (PM-601, -602) SHALL BE TIGG MODEL NB-8 VAPOR-PHASE ADSORBER OR EQUAL OF CARBON STEEL CONSTRUCTION CONTAINING 12,000 LBS. OF POTASSIUM PERMANGANATE PER VESSEL.
7. BOOSTER PUMP (P-800) SHALL BE DAVEY MODEL HS12-40HT1 OR EQUAL WITH 304 SS CASING AND SHAFT, EPOXY-COATED STEEL PRESSURE TANK, AND 120 V, SINGLE PHASE, 0.9 KW MOTOR CAPABLE OF 12 GPM AT 40 PSI TDH.
8. EFFLUENT HOLDING TANK (T-800) SHALL BE CHEMTAINER MODEL TA35771A OR EQUAL WITH 300-GALLON CAPACITY AND LINEAR HIGH DENSITY POLYETHYLENE CONSTRUCTION.
9. SUMP PUMP (P-900) SHALL BE HYDROMATIC MODEL OSP50M1 OR EQUAL MANUALLY CONTROLLED SUMP PUMP WITH A ½ HP, 115 V, SINGLE PHASE MOTOR CAPABLE OF 30 GPM AT 20 FEET TDH.
10. PITLESS ADAPTER SHALL BE BAKER MANUFACTURING MODEL 3PS67WBWE22T3S 6-INCH STANDARD INDUSTRIAL PITLESS UNIT OR EQUAL WITH 3-INCH OUTLET, 2-INCH DROP PIPE AND 6-INCH LOWER AND 7-INCH UPPER WELDED CASING CONNECTIONS.


**MECHANICAL SPECIFICATIONS**

1. ALL ABOVE-GROUND PIPING SHALL BE PVC SCHEDULE 80.
2. ALL PVC PIPE JOINTS SHALL BE SOLVENT WELDED.
3. ALL UNDERGROUND HDPE PIPE SHALL BE HDPE SDR 17, UNLESS OTHERWISE SPECIFIED.
4. ALL HDPE PIPES SHALL BE BUTT-FUSED.
5. ALL PIPE SHALL BE INSTALLED AND PRESSURE TESTED IN ACCORDANCE WITH MANUFACTURER'S SPECIFICATIONS. ZERO LEAKAGE IS ALLOWED FOR ALL JOINTS.
6. ALL PIPE SHALL BE SUPPORTED AT 7'-0" O.C. (MAX.) AND LOCATED 2'-0" FROM ALL JOINT LOCATIONS. PIPING SHALL BE SUPPORTED PRIMARILY BY THE BUILDING FLOOR SLAB.
7. BALL VALVES SHALL BE PVC TRUE UNION BALL VALVES WITH VITON O-RING SEAL, TEFLON SELF-LUBRICATING SEATS, TIGHT SHUTOFF IN EITHER DIRECTION, FULL PORT DESIGN, SOLVENT WELDED SOCKET ENDS AND OPERATING HANDLE. MANUFACTURER: HAYWARD, NIBCO, PLASTO-MATIC, OR EQUAL.
8. GLOBE VALVES SHALL BE ASAHI MANUAL CONTROL VALVES OF PVC CONSTRUCTION WITH EPDM SEALS, AND SOCKET CONNECTIONS.
9. MOTORIZED BLOCK VALVES (MBV-501, -502) SHALL CONSIST OF A BALL VALVE WITH HAYWARD SERIES EJM ELECTRIC ACTUATOR, 115VAC EQUIPPED WITH POSITION INDICATOR.
10. CHECK VALVES SHALL BE SWING CHECK TYPE WITH VITON SEATS. MANUFACTURER: HAYWARD, NIBCO, PLASTO-MATIC, OR EQUAL.
11. SAMPLE TAPS AND DRAIN VALVES SHALL CONSIST OF A ½" DIAMETER PVC PIPE EXTENSION, BALL VALVE AND NIPPLE. SAMPLE TAPS AND DRAIN VALVES SHALL BE LOCATED AT LOCATIONS SHOWN ON THE DRAWINGS AND AT ALL LOW ELEVATIONS IN THE PROCESS PIPING.
12. ALL FLOW METERS SHALL HAVE STRAIGHT PIPE AT A MINIMUM OF 10 PIPE DIAMETERS PRECEDING AND 5 PIPE DIAMETERS FOLLOWING, OR AS SPECIFIED BY THE MANUFACTURER.
13. SPOOL PIECES SHALL BE 16"Ø STAINLESS STEEL HEAVY DUTY AIR ISOLATION/CONTROL DAMPER WITH MANUAL ACTUATOR, AMERICAN HEATING & VENTILATION MODEL VC-56, MODIFIED FOR LOWER LEAK RATES AT HIGHER PRESSURE.
14. WELL VAULT ACCESS COVER SHALL BE BILCO MODEL J-2ALH20 OR EQUAL WITH ¼" ALUMINUM DIAMOND PATTERN PLATE COVER, ½" ALUMINUM CHANNEL FRAME WITH RECESSED ANCHORS, CONTINUOUS EPDM DEBRIS GASKET, RATED FOR H2O LOADING.
15. DUCT SHALL BE 16"Ø SCH. 10 ALUMINUM DUCT WITH TRYMER 2000 FOAM INSULATION WITH WHITE PVC/POLYESTER COVER. COMBINED WEIGHT 9.25 POUNDS/ LINEAR FOOT WITH ¼" THICK FLANGES, STAINLESS STEEL BOLTING, AND ½" NEOPRENE GASKETS.
16. ALL DUCT SHALL BE SUPPORTED AT 10'-0" C.C. (MAX.) AND LOCATED 2'-0" FROM ALL JOINT LOCATIONS. SUPPORTS SHALL BE ANCHORED TO THE EQUIPMENT SLAB AND PROTECTIVE SLEEVES SHALL BE USED FOR ALL INSULATED DUCT.
17. ECU'S SHALL BE INSULATED WITH 2-INCH RIGID STYROFOAM BOARDS FINISHED WITH STUCCO-EMBOSSED ALUMINUM JACKETING.

THIS BAR REPRESENTS ONE INCH ON THE ORIGINAL DRAWING. USE TO VERIFY FIGURE REPRODUCTION SCALE

THIS DRAWING IS THE PROPERTY OF THE ARCADIS ENTITY IDENTIFIED IN THE TITLE BLOCK AND MAY NOT BE REPRODUCED OR ALTERED IN WHOLE OR IN PART WITHOUT THE EXPRESS WRITTEN PERMISSION OF SAME.

Professional Engineer's Name <b>WILLIAM S. WITTEK</b>				
Professional Engineer's No. 080827				
State	Date Signed	Project Mgr.		
NY	8/28/08	CSG		
Designed by	Drawn by	Checked by		
CDL	KLS	TEM		





NORTHROP GRUMMAN CORPORATION • BETHPAGE, NEW YORK  
 OPERABLE UNIT 3 - FORMER GRUMMAN SETTLING PONDS

**SPECIFICATIONS**

MECHANICAL

ARCADIS Project No. NY001464.1807.00003
Date AUGUST 2008
ARCADIS 6723 Towpath Road (P.O. Box 66) Syracuse, NY 13214 Tel: 315.446.9120

CITY: SYRACUSE DIV: GROUP: 85 DB: GHS: KFS LD: GHS: PIC: PM: TM: LYRONE: OFF: REF: G:\CAD\ACT\NY0014641807\00003\DWG\01464G09.dwg LAYOUT: 12 SAVED: 7/25/2008 4:14 PM ACADVER: 17.05 (LWS TECH) PAGES: 17 OF 17 PLOTTED: 8/28/2008 5:37 PM BY: STEINBERGER, GEORGE



EMISSIONS SHALL BE CONTROLLED BY MISTING DURING SOIL INTRUSIVE SITE ACTIVITIES.

COMMUNITY AIR MONITORING PLAN SHALL BE IMPLEMENTED DURING SOIL INTRUSIVE SITE ACTIVITIES.

THIS BAR REPRESENTS ONE INCH ON THE ORIGINAL DRAWING.

USE TO VERIFY FIGURE REPRODUCTION SCALE

No.	Date	Revisions	By	Ckd

Professional Engineer's Name  
**WILLIAM S. WITTEK**

Professional Engineer's No.  
080827

State  
NY


Date Signed  
8/28/08

Project Mgr.  
CSG

Designed by  
CDL

Drawn by  
BKD

Checked by  
TEM



**ARCADIS**

ARCADIS OF NEW YORK, INC.

NORTHROP GRUMMAN CORPORATION • BETHPAGE, NEW YORK

OPERABLE UNIT 3 - FORMER GRUMMAN SETTLING PONDS

**SOIL MANAGEMENT PLAN**

ARCADIS Project No.  
NY001464.1807.00003

Date  
AUGUST 2008

ARCADIS  
6723 Towpath Road  
(P.O. Box 66)  
Syracuse, NY 13214  
Tel: 315.446.9120

CITY/SYRANI DIV/GRUPP/DE/CHS LD/CHS FC: PM: TM: LYRON+OFF+REF: 10/16/10 Drawing Project NY1001464.1407 Drawing Current Drawing General Notes.dwg LAYOUT: 22 SAVE: 7/24/2008 9:58 PM ACADVER: 17.05 (LMS TECH) PAGES: 34X22 PLOTSTYLETABLE: PLTCONT1.CTB PLOTTED: 8/29/2008 9:39 AM BY: HUNT, AARON

**PRE-ENGINEERED BUILDING**

- 1.1 DESIGN REQUIREMENTS**
- A. APPLICABLE BUILDING CODE: NEW YORK STATE BUILDING CODE 2007.
  - B. DESIGN WALL AND ROOF PANEL SYSTEM TO WITHSTAND SPECIFIED LOADS WITH DEFLECTION OF 1/240TH OF SPAN, MAXIMUM.
  - C. ANCHOR RODS: FURNISH DESIGN CRITERIA FOR ANCHOR BOLTS FURNISHED BY OTHERS, TO RESIST THE LOADS INDUCED BY THE DESIGN LOADS ON THE STRUCTURE.
- 1.2 SUBMITTALS**
- A. DESIGN DATA: PROVIDE DETAILED DESIGN CRITERIA AND CALCULATIONS.
  - B. CERTIFICATION: MANUFACTURER CERTIFICATION THAT THE BUILDING CONFORMS TO THE CONTRACT DOCUMENTS AND MANUFACTURER'S STANDARD DESIGN PROCEDURES.
  - C. SHOP DRAWINGS: SHOW BUILDING LAYOUT, PRIMARY AND SECONDARY FRAMING MEMBER SIZES AND LOCATIONS, CROSS-SECTIONS, AND PRODUCT AND CONNECTION DETAILS.
  - D. PRODUCT DATA: INFORMATION ON MANUFACTURED PRODUCTS TO BE INCORPORATED INTO THE PROJECT.
  - E. COLOR CHARTS: FOR SELECTION OF COLORS.
  - F. ANCHOR ROD INSTALLATION DRAWINGS: LAYOUTS WITH BOLT DIAMETERS.
  - G. REACTIONS: SUBMIT REACTIONS FOR DESIGN OF FOUNDATION.
  - H. SPECIMEN WARRANTY.
- 1.3 QUALITY ASSURANCE**
- A. DESIGN STRUCTURAL COMPONENTS, DEVELOP SHOP DRAWINGS, AND PERFORM SHOP AND SITE WORK UNDER DIRECT SUPERVISION OF A PROFESSIONAL ENGINEER EXPERIENCED IN DESIGN OF THIS WORK AND LICENSED IN THE STATE OF NEW YORK.
  - B. DESIGN DATA AND SHOP DRAWINGS SUBMITTED FOR REVIEW SHALL BEAR THE SEAL OF A PROFESSIONAL ENGINEER LICENSED IN THE STATE OF NEW YORK.
  - C. QUALIFICATIONS:
    - 1. MANUFACTURER: COMPANY SPECIALIZING IN MANUFACTURING PRODUCTS SPECIFIED IN THIS SECTION WITH MINIMUM 5 YEARS DOCUMENTED EXPERIENCE.
    - 2. ERECTOR: COMPANY SPECIALIZING IN PERFORMING WORK OF THIS SECTION WITH MINIMUM 5 YEARS DOCUMENTED EXPERIENCE AND APPROVED BY MANUFACTURER.
- 1.4 WARRANTY**
- A. PROVIDE MANUFACTURER'S STANDARD WARRANTY FOR:
    - 1. PANEL FINISH: 20 YEARS.
    - 2. WEATHER-TIGHTNESS: 20 YEARS
- PART 2 PRODUCTS**
- 2.1 MANUFACTURERS**
- A. NUCOR BUILDING SYSTEMS.
  - B. OR AS APPROVED.
- 2.2 METAL MATERIALS**
- A. STRUCTURAL STEEL PLATE, BAR, SHEET, AND STRIP FOR USE IN BOLTED AND WELDED CONSTRUCTIONS: ASTM A572, A570, A529, OR A36, WITH MINIMUM YIELD STRENGTH OF 50,000 PSI.
  - B. STRUCTURAL STEEL MATERIAL FOR USE IN ROLL FORMED OR PRESS BROKEN SECONDARY STRUCTURAL MEMBERS: ASTM A570, OR A607 WITH MINIMUM YIELD STRENGTH OF 55,000 PSI.
  - C. GALVANIZED STEEL SHEET FOR ROLL-FORMED OR PRESS BROKEN ROOF AND WALL COVERINGS, TRIM AND FLASHING: ASTM A653, WITH MINIMUM YIELD STRENGTH OF 50,000 PSI.
  - D. HOT-ROLLED STEEL SHAPES: W, M AND S SHAPES, ANGLES, RODS, CHANNELS AND OTHER SHAPES; ASTM A992 OR ASTM A36 AS APPLICABLE; WITH MINIMUM YIELD STRENGTHS REQUIRED FOR THE DESIGN.
  - E. STRUCTURAL BOLTS AND NUTS USED WITH PRIMARY FRAMING: HIGH STRENGTH, ASTM A325.
  - F. BOLTS AND NUTS USED WITH SECONDARY FRAMING MEMBERS: ASTM A307.
- 2.3 FRAMING COMPONENTS**
- A. PRIMARY FRAMING: RIGID FRAME SOLID WEB FRAMING CONSISTING OF TAPERED OR UNIFORM DEPTH RAFTERS RIGIDLY CONNECTED TO TAPERED OR UNIFORM DEPTH COLUMNS. PROVIDE A CLEAR SPAN THAT SUPPORTS THE LOADS AT BAY SPACINGS INDICATED.
  - B. ENDWALL FRAMING: PORTAL FRAME FRAMING.
  - C. PURLINS: Z-SHAPED; DEPTH AS REQUIRED; WITH MINIMUM YIELD STRENGTH OF 55,000 PSI; SIMPLE SPAN OR CONTINUOUS SPAN AS REQUIRED FOR DESIGN.
  - D. GIRTS: Z- OR C-SHAPED; DEPTH AS REQUIRED; WITH MINIMUM YIELD STRENGTH OF 55,000 PSI; SIMPLE SPAN OR CONTINUOUS SPAN AS REQUIRED FOR DESIGN.
  - E. WIND BRACING: PORTAL, TORSIONAL, DIAGONAL BRACING OR DIAPHRAGM IN ACCORDANCE WITH MANUFACTURER'S STANDARD DESIGN PRACTICES; UTILIZING RODS, ANGLES, AND OTHER MEMBERS, WITH MINIMUM YIELD STRENGTHS AS REQUIRED FOR DESIGN.
  - F. PRIMARY FRAME FLANGE BRACING: ATTACHED FROM PURLINS OR GIRTS TO THE PRIMARY FRAMING, MINIMUM YIELD STRENGTH AS REQUIRED FOR DESIGN.
  - G. BASE ANGLES: 2 INCH BY 3 INCH BY 0.059 INCH STEEL ANGLES, WITH MINIMUM YIELD STRENGTH OF 55,000 PSI.
  - H. DOOR HEADERS AND JAMBS: Z- OR C-SHAPED; DEPTH AS REQUIRED; WITH MINIMUM YIELD STRENGTH OF 55,000 PSI.
  - I. SAG ANGLES AND BRIDGING: STEEL ANGLES WITH MINIMUM YIELD STRENGTH OF 36,000 PSI.
  - J. FABRICATION: FABRICATE ACCORDING TO MANUFACTURER'S STANDARD PRACTICE
    - 1. FABRICATE STRUCTURAL MEMBERS MADE OF WELDED PLATE SECTIONS BY JOINING THE FLANGES AND WEBS BY CONTINUOUS AUTOMATIC SUBMERGED ARC WELDING PROCESS.
    - 2. ALL WELDING OPERATORS AND PROCESSES SHALL BE QUALIFIED IN ACCORDANCE WITH THE AMERICAN WELDING SOCIETY "STRUCTURAL WELDING CODE", AWS D1.1.
    - 3. FIELD CONNECTIONS: PREPARE MEMBERS FOR BOLTED FIELD CONNECTIONS BY MAKING PUNCHED, DRILLED, OR REAMED HOLES IN THE SHOP.
  - K. SHOP COATING: FINISH ALL STRUCTURAL STEEL MEMBERS USING ONE COAT OF MANUFACTURER'S STANDARD SHOP COAT, AFTER CLEANING OF OIL, DIRT, LOOSE SCALE AND FOREIGN MATTER.
- 2.4 ROOF AND WALL PANEL COMPONENTS**
- A. ROOF PANELS:** 36 INCH WIDE NET COVERAGE WITH 1-1/4 INCH MAJOR RIBS AT 12 INCHES ON CENTER WITH MINOR RIBS SPACED BETWEEN THE MAJOR RIBS.
1. MATERIAL: GALVANIZED STEEL WITH G90 COATING.
  2. THICKNESS: 26 GAUGE.
  3. SIDE LAPS: AT LEAST ONE FULL MAJOR RIB, WITH A SUPPORTING MEMBER BEARING EDGE ON THE LOWER PANEL AND AN ANTI-CAPILLARY GROOVE ON THE UPPER PANEL.
  4. LENGTH: CONTINUOUS FROM EAVE TO RIDGE.
  5. ENDLAPS WHERE REQUIRED: 6 INCHES WIDE, LOCATED AT A SUPPORT MEMBER.
  6. FINISH: KYNAR 500 PRE-PAINTED FINISH ON EXTERIOR SURFACE, WASH COAT ON INTERIOR SURFACE. COLOR SELECTED BY OWNER FROM MANUFACTURER'S FULL LINE.
  7. THE ROOF SHALL BE TESTED AND CERTIFIED TO MEET UNDERWRITERS LABORATORIES, INC., UPLIFT RATING: UL 90.
- B. WALL PANELS:** 36 INCH WIDE NET COVERAGE WITH 1-1/4 INCH MAJOR RIBS AT 12 INCHES ON CENTER WITH MINOR RIBS SPACED BETWEEN THE MAJOR RIBS.
1. MATERIAL: GALVANIZED STEEL WITH G90 COATING.
  2. THICKNESS: 26 GAUGE.
  3. SIDE LAPS: TWO FULLY OVERLAPPING MAJOR RIBS SECURED TOGETHER WITH 1/4 INCH DIAMETER COLOR-MATCHED CARBON STEEL FASTENERS.
  4. LENGTH: CONTINUOUS FROM SILL TO EAVE.
  5. ENDLAPS WHERE REQUIRED: 4 INCHES WIDE, LOCATED AT A SUPPORT MEMBER.
  6. CRIMP PANELS AT THE BASE AND NOTCH TO MAKE ROOF PANEL CONFIGURATION AT THE EAVE.
  7. CUT PANELS SQUARE AT EACH END; PROVIDE BASE TRIM AT SILL.
  8. FINISH: KYNAR 500 PRE-PAINTED FINISH ON EXTERIOR SURFACE, WASH COAT ON INTERIOR SURFACE. COLOR SELECTED BY OWNER FROM MANUFACTURER'S FULL LINE.
- C. PANEL FASTENERS:**
1. FOR ROOF PANELS: STAINLESS STEEL-CAPPED CARBON STEEL FASTENERS WITH INTEGRAL SEALING WASHER.
  2. FOR WALL PANELS: COATED CARBON STEEL.
  3. COLOR OF EXPOSED FASTENER HEADS TO MATCH THE WALL PANEL FINISH.

**PRE-ENGINEERED BUILDING (CONT.)**

- 4. CONCEALED FASTENERS: SELF-DRILLING TYPE, OF SIZE AS REQUIRED.
- 5. PROVIDE FASTENERS IN QUANTITIES AND LOCATION AS REQUIRED BY THE MANUFACTURER.
- D. FLASHING AND TRIM: MATCH MATERIAL AND COLOR OF ADJACENT COMPONENTS. PROVIDE TRIM AT RAKES, INCLUDING PEAK AND CORNER ASSEMBLIES, HIGH AND LOW EAVES, CORNERS, BASES, FRAMED OPENINGS AND AS REQUIRED OR SPECIFIED TO PROVIDE WEATHER-TIGHTNESS AND A FINISHED APPEARANCE.
- E. PLASTIC PARTS: GLASS FIBER-REINFORCED RESIN OR THERMO-FORMED ABS.
  - 1. ABS: MINIMUM 1/8 INCH THICK.
  - 2. COLOR: MANUFACTURER'S STANDARD COLOR.
- F. SEALANTS, MASTICS AND CLOSURES: MANUFACTURER'S STANDARD TYPE.
  - 1. PROVIDE AT ROOF PANEL ENDLAPS, SIDELAPS, RAKE, EAVE, TRANSITIONS AND ACCESSORIES AS REQUIRED TO PROVIDE A WEATHER-RESISTANT ROOF SYSTEM; USE TAPE MASTIC OR GUNNABLE SEALANT AT SIDELAPS AND ENDLAPS.
  - 2. PROVIDE AT WALL PANEL RAKES, EAVES, TRANSITIONS AND ACCESSORIES.
  - 3. CLOSURES: FORMED TO MATCH PANEL PROFILES; CLOSED CELL ELASTIC MATERIAL, MANUFACTURER'S STANDARD COLOR.
  - 4. TAPE MASTIC: PRE-FORMED BUTYL RUBBER-BASED, NON-HARDENING, NON-CORROSIVE TO METAL; WHITE OR LIGHT GRAY.
  - 5. GUNNABLE SEALANT: NON-SKINNING SYNTHETIC ELASTOMER BASED MATERIAL; GRAY OR BRONZE.
  - 6. BLANKET INSULATION: GLASS FIBER WITH FACTORY-LAMINATED FACING MATERIAL:
    - 1. GLASS FIBER: ODORLESS; NEUTRAL-COLORED, LONG FILAMENT, FLEXIBLE RESILIENT, PRODUCED IN COMPLIANCE WITH THE NAIMA 202 SPECIFICATIONS.
    - 2. THERMAL RESISTANCE: TO MEET R=19 AT 75 DEGREES F MEAN TEMPERATURE.
    - 3. FLAME SPREAD INDEX: 25 OR LESS, WHEN TESTED IN ACCORDANCE WITH UL 723.
    - 4. SMOKE DEVELOPED INDEX: 50 OR LESS, WHEN TESTED IN ACCORDANCE WITH UL 723.
    - 5. UL CLASSIFIED.
    - 6. FACING: WHITE VINYL SCRIM POLYESTER, 0.0025 INCH THICK PVC FILM, GLASS FIBER SCRIM REINFORCING, 0.0005 INCH THICK POLYESTER FILM, PERMEANCE 0.02 PERMS, COMPOSITE FIBERGLASS AND FACING TO MEET FLAME SPREAD OF 25 OR LESS, SMOKE DEVELOPED OF 50 OR LESS, WHEN TESTED IN ACCORDANCE WITH UL 723.
    - 7. PROVIDE FACING 3 INCHES WIDER ON BOTH EDGES THAN BLANKET.
    - 8. WIDTH: AS REQUIRED FOR INSTALLATION.
  - 9. USE BLANKET INSULATION AT ROOF AND WALLS.
- 2.5 WALL ACCESSORIES
  - A. SERVICE DOORS.
  - B. SECTIONAL OVERHEAD DOORS.
  - C. PROVIDE FRAMED OPENINGS FOR LOUVERS.
- 2.6 ROOF ACCESSORIES
  - A. EAVE GUTTERS: ROLL-FORMED 26 GAUGE STEEL SHEET, WITH GUTTER STRAPS, FASTENERS AND JOINT SEALANT; SAME COLOR AS WALL PANELS.
    - 1. DOWNSPOUTS: 4 BY 5 INCHES IN 10 FOOT LENGTHS WITH DOWNSPOUT ELBOWS AND DOWNSPOUT STRAPS; SAME COLOR AS WALL PANELS.
  - B. SNOWGUARDS:
    - 1. MANUFACTURERS: SNOWAX, INC., OR AS APPROVED.
    - 2. FABRICATED FROM CLEAR POLYCARBONATE.
    - 3. PROVIDE ADHESIVE FOR SECURING SNOWGUARDS TO ROOF PANELS.
    - 4. CONSULT MANUFACTURER FOR SPACING RECOMMENDATIONS.
  - C. PROVIDE FRAMED OPENINGS FOR FANS.
- 2.7 DOORS
  - A. OVERHEAD DOORS TO BE COILING TYPE, STEEL CONSTRUCTION, INSULATED. CURTAIN SLATS MIN 20 GA EXTERIOR AND 24 GA BACK COVER. LOCKING MECHANISM REQUIRED. PROVIDE COUNTERBALANCING MECHANISM WITH HELICAL TORSIONAL SPRINGS. PLACE HOOD EXTERIOR OF BUILDING.
  - B. INTERIOR MANDOOR - 20 GA., HONEY COMB CORE, WITH 16 GA. FRAME AND LOCKS.
  - C. EXTERIOR MANDOOR - 18 GA., INSULATED CORE, STANDARD KEYING, BALL BEARING HINGES, AND 16 GA. FRAME.

**COLD FORMED METAL FRAMING**



- 1.1 MATERIALS**
- A. STEEL SHEET: ASTM A653/A 653M, STRUCTURAL STEEL, ZINC COATED, OF GRADE AND COATING AS FOLLOWS:
    - 1. GRADE: 33 OR 50, CLASS 1 OR 2 AS REQUIRED BY STRUCTURAL CALCULATIONS.
    - 2. COATING: G60 (Z180).
- 1.2 FRAMING ACCESSORIES**
- A. FABRICATE STEEL-FRAMING ACCESSORIES OF THE SAME MATERIAL AND FINISH USED FOR FRAMING MEMBERS, WITH MINIMUM YIELD STRENGTH OF 33,000 PSI (230 MPa).
  - B. PROVIDE ACCESSORIES OF MANUFACTURER'S STANDARD THICKNESS AND CONFIGURATION.
- 1.3 MISCELLANEOUS MATERIALS**
- A. GALVANIZING REPAIR PAINT: SSPC-PAINT 20 OR DOD-P21035, ASTM A780.
- 1.4 FASTENERS**
- A. SCREWS: CORROSION-RESISTANT COATED, SELF-DRILLING, PAN OR HEX WASHER HEAD. PROVIDE SCREW TYPE AND SIZE AS REQUIRED BY STRUCTURAL DESIGN CALCULATIONS FOR THE CONDITION AND THICKNESS OF MATERIALS BEING JOINED.
- 1.5 FABRICATION**
- A. FABRICATE ASSEMBLIES TO SIZE AND CONFIGURATION REQUIRED.
  - B. CUT ALL FRAMING COMPONENTS SQUARE FOR ATTACHMENT TO PERPENDICULAR MEMBERS, OR AS REQUIRED FOR AN ANGULAR FIT AGAINST ABUTTING MEMBERS.
  - C. FASTEN COMPONENTS WITH SELF-DRILLING SCREWS OR WELDING. FURNISH SCREWS OF SIZES TO BE SUFFICIENT TO INSURE STRENGTH OF CONNECTION. TOUCH UP ALL WELDS WITH ZINC-RICH PRIMER. MECHANICAL FASTENERS, EITHER POWDER ACTUATED OR PNEUMATICALLY DRIVEN, ARE PROHIBITED.
  - D. REINFORCE AND BRACE ASSEMBLIES TO WITHSTAND HANDLING STRESSES.
  - E. COLD-FORMED METAL FRAMING MAY BE SHOP OR FIELD FABRICATED FOR INSTALLATION, OR IT MAY BE FIELD ASSEMBLED.
  - F. INSTALL COLD-FORMED METAL FRAMING ACCORDING TO ASTM C1007, UNLESS MORE STRINGENT REQUIREMENTS ARE INDICATED.
  - G. INSTALL COLD-FORMED METAL FRAMING AND ACCESSORIES PLUMB, SQUARE, AND TRUE TO LINE, AND WITH CONNECTIONS SECURELY FASTENED, ACCORDING TO MANUFACTURER'S WRITTEN RECOMMENDATIONS AND REQUIREMENTS IN THIS SECTION.
    - 1. CUT FRAMING MEMBERS BY SAWING OR SHEARING; DO NOT TORCH CUT.
    - 2. FASTEN COLD-FORMED METAL FRAMING MEMBERS BY WELDING OR SCREW FASTENING, AS STANDARD WITH FABRICATOR. WIRE TYING OF FRAMING MEMBERS IS NOT PERMITTED.
  - H. INSTALL STUDS AT SPACING AS SHOWN ON DRAWINGS AND AS REQUIRED BY STRUCTURAL DESIGN CALCULATIONS, AT EACH SIDE OF OPENINGS AND NOT MORE THAN 2 INCHES FROM ABUTTING WALLS.
    - a. FRAME CORNERS WITH THREE STUDS.
    - b. FRAME WALL OPENINGS WIDER THAN STUD SPACING WITH DOUBLE STUD AT EACH JAMB.
  - I. INSTALL SUPPLEMENTARY FRAMING OR BLOCKING TO SUPPORT WORK ATTACHED TO FRAMING.
- 1.6 TOLERANCES**
- A. STUDS: VERTICAL ALIGNMENT (PLUMBNESS), 1/960 (1/8 INCH IN 10 FEET).
  - B. WALLS: HORIZONTAL ALIGNMENT (LEVELNESS), 1/960 (1/8 INCH IN 10 FEET).
  - C. STUD SPACING: 1/8 INCH FROM DESIGNATED SPACING PROVIDING THAT THE CUMULATIVE ERROR DOES NOT EXCEED REQUIREMENTS OF FINISHING MATERIALS.

THIS BAR REPRESENTS ONE INCH ON THE ORIGINAL DRAWING.

USE TO VERIFY FIGURE REPRODUCTION SCALE

No.	Date	Revisions	By	Ckd

Professional Engineer's Name  
**AARON A HUNT**  
 Professional Engineer's No.  
 083766  
 State  
 NY  
 Project Mgr.  
 CSG  
 Designed by  
 AAH  
 Drawn by  
 AAH  
 Checked by  
 TEM/WSW



NORTHROP GRUMMAN CORPORATION • BETHPAGE, NEW YORK  
 OPERABLE UNIT 3 - FORMER GRUMMAN SETTLING PONDS

**STRUCTURAL NOTES AND SYMBOLS #2**


STRUCTURAL

ARCADIS Project No.  
 NY001464.1807.00003  
 Date  
 AUGUST 2008  
 ARCADIS  
 6723 Towpath Road  
 Box 66  
 Syracuse, NY 13214  
 Tel: 315-446-9120




CITY: SYRACUSE DIV: GROUP: 85 DB: GHS LD: GHS PIC: PM: TM: LYRON: OFF: REF: LAYOUT: 20  
 PROJECTNAME: 01464X00-AAH PE  
 XREFS: 01464X00-AAH PE  
 IMAGES: 01464X00-AAH PE  
 PAGES: 17 OF 17  
 PLOT: 8/29/2008 9:39 AM BY: HUNT, AARON


NOTE: THE PRE-ENGINEERED METAL BUILDING SHALL BE INCLUSIVE OF TWO 16" ROUND DUCT PENETRATION POINTS. PLEASE SEE APPROXIMATE LOCATION OF DUCT PENETRATION POINTS ON CONTRACT DRAWING 7. WALL PENETRATION KITS WILL BE PROVIDED BY THE BUILDING MANUFACTURER AND SHALL BE INSTALLED AS DIRECTED BY THE INSTALLATION INSTRUCTIONS ALSO PROVIDED BY THE BUILDING MANUFACTURER




**EAST ELEVATION**  
1/4" = 1'-0"



**NORTH ELEVATION**  
1/4" = 1'-0"




**WEST ELEVATION**  
1/4" = 1'-0"




**SOUTH ELEVATION**  
1/4" = 1'-0"

DESIGN INFORMATION (NYSBC 2007)	
DESIGN ROOF LIVE LOAD	20 psf
DESIGN ROOF COLLATERAL LOAD (APPLY PURLINS AND FRAMES)	10 psf
NET ALLOWABLE DESIGN SOIL BEARING PRESSURE (PRESUMED BEARING PRESSURE)	1000 psf MIN (VERIFY DURING CONSTRUCTION)
DESIGN SNOW LOAD	
NYSBC 2007 SECTION 1608	
GROUND SNOW LOAD	20 PSF
SNOW EXPOSURE FACTOR, Ce	0.9
SNOW LOAD IMPORTANCE FACTOR, Is	1.1
THERMAL FACTOR, Ct	1.0
FLAT ROOF SNOW LOAD, Pf	13.9 psf
SLOPED ROOF SNOW LOAD, Ps	13.9 psf
DESIGN WIND LOAD	
NYSBC 2007 SECTION 1609	
BASIC WIND SPEED	110 MPH
WIND LOAD IMPORTANCE FACTOR =	1.15
BUILDING CATEGORY III	
WIND EXPOSURE B	
INTERNAL PRESSURE COEFFICIENT	0.18
COMPONENTS AND CLADDING LOADS	
ROOF:	
ZONE 4 +10.2 PSF, -42 PSF	
WALLS:	
ZONE 4 +25 PSF, -27.1 PSF	
DESIGN SEISMIC LOADS	
NYSBC 2007 SECTION 1613	
SEISMIC LOAD IMPORTANCE FACTOR =	1.25
MAPPED SPECTRAL RESPONSE ACCELERATIONS	
SS 0.30	
S1 0.07	
SITE CLASS D	
SPECTRAL RESPONSE COEFFICIENTS	
Sds 0.312	
Sd1 0.112	
SEISMIC DESIGN CATEGORY B	
BASIC SEISMIC FORCE RESISTING SYSTEM	
ORDINARY STEEL MOMENT FRAMES	
DESIGN BASE SHEAR	
STEEL "BUILDING" BASE SHEAR 5 KIPS	
SEISMIC RESPONSE COEFFICIENT Cs	
Cs STEEL 0.111 (MOMENT FRAMES)	
RESPONSE MODIFICATION FACTOR	
R STEEL MOMENT FRAME 3.5	
ANALYSIS PROCEDURE USED: EQUIVALENT LATERAL FORCE PROCEDURE	



No.	Date	Revisions	By	Ckd

Professional Engineer's Name  
**AARON A HUNT**  
 Professional Engineer's No.  
 083766  
 State  
 NY  
 Project Mgr.  
 CSG  
 Designed by  
 AAH  
 Drawn by  
 AAH  
 Checked by  
 TEM/WSW







NORTHROP GRUMMAN CORPORATION • BETHPAGE, NEW YORK  
 OPERABLE UNIT 3 - FORMER GRUMMAN SETTLING PONDS  
**BUILDING ELEVATIONS**  
 STRUCTURAL

ARCADIS Project No.  
 NY001464.1807.00003  
 Date  
 AUGUST 2008  
 ARCADIS  
 6723 Towpath Road  
 Box 66  
 Syracuse, NY 13214  
 Tel: 315-446-9120





CITY: SYRACUSE DIV: GROUP: 85 DR: GHS LD: CHS PIC: PM: TM: LY: RC: N: OFF: TREF: 10133P: ID: 0014641407: Drawing: Slab-On-Grade.dwg LAYOUT: 19 SAVED: 7/24/2008 3:56 PM ACADIVER: 17.05 (LMS TECH) PAGESETUP: BETHPAGE OCE 24X22 PLOTTING: 8/28/2008 9:39 AM BY: HUNT, AARON



No.	Date	Revisions	By	Ckd







Professional Engineer's Name  
**AARON A HUNT**  
 Professional Engineer's No.  
 083766  
 State NY  
 Date Signed 8/21/08  
 Project Mgr. CSG  
 Drawn by AAH  
 Checked by TEM/WSW



NORTHROP GRUMMAN CORPORATION • BETHPAGE, NEW YORK  
 OPERABLE UNIT 3 - FORMER GRUMMAN SETTLING PONDS  
**SLAB ON GRADE PLAN VIEW AND DETAILS**  
 STRUCTURAL

ARCADIS Project No.  
 NY001464.1807.00003  
 Date  
 AUGUST 2008  
 ARCADIS  
 6723 Towpath Road  
 Box 66  
 Syracuse, NY 13214  
 Tel: 315-446-9120


CITY:SYRNY DIV:GROUP:85 DB:GHS LD:GHS PIC: PM: TM: LYRCN-REF=REF" LOR3FF10data\Project\NY1001464.1407\Drawing\Current\Drawings\Foundation.dwg LAYOUT:1: 18 SAVED: 8/4/2008 10:08 AM ACADVER: 17.05 (LMS TECH) PAGESSETUP: BETHPAGE 0CE 34X22 PLOTSTYLETABLE: PLTCONT1.CTB PLOTTED: 8/29/2008 9:39 AM BY: HUNT, AARON



No.	Date	Revisions	By	Ckd

Professional Engineer's Name  
**AARON A HUNT**  
Professional Engineer's No.  
083766

State NY Date Signed 8/29/08 Project Mgr. CSG  
Designed by AAH Drawn by AAH Checked by TEM/WSW



NORTHROP GRUMMAN CORPORATION • BETHPAGE, NEW YORK  
OPERABLE UNIT 3 - FORMER GRUMMAN SETTLING PONDS

## FOUNDATION PLAN VIEW AND DETAILS



STRUCTURAL

ARCADIS Project No.  
NY001464.1807.0003

Date  
AUGUST 2008



ARCADIS  
6723 Towpath Road  
Box 66  
Syracuse, NY 13214  
Tel: 315-446-9120

CITY:SYR-AY DIV/GRP:85 DB/GHS LD/GHS PIC: PM: T.M. LYRONI=OFF=REF\*  
 G:\Project\NY01464\1407\ElectricalDrawings - Recovery Well\AutoCAD Drawings\2-25-08\17 Electrical Details.dwg LAYOUT: 17 SAVED: 7/25/2008 1:54 PM ACADVER: 17.15 (LMS TECH) PAGES: 17 PLOTTED: 8/29/2008 6:28 PM BY: ARMSSTRONG, TOM  
 XREFS: 01464X00 PROJECTNAME:




\*SFSI = SECONDARY FAIL-SAFE INTERLOCK

**SCHEMATIC RECOVERY WELL PUMP**  
(P-120 AND P-130 ARE SIMILAR)




\*SFSI = SECONDARY FAIL-SAFE INTERLOCK


**SCHEMATIC RECOVERY WELL PUMP**  
(P-110 AND P-140 ARE SIMILAR)




**ELECTRIC UNIT HEATER (EUH-3) RISER**  
DIAGRAM




**RISER EF-1**  
(EF-2 IS SIMILAR)




**SECONDARY FAIL-SAFE INTERLOCK**  
CONTROL PANEL (SFSI-CP)



**ELECTRIC - TRENCH DETAIL**  
NO SCALE



**SECTION**  
**ELECTRICAL HANDHOLE DETAIL**  
NO SCALE



**EXHAUST FAN SCHEMATIC**  
(EF-1 AND EF-2 ARE SIMILAR)


**NO SCALE**

THIS BAR REPRESENTS ONE INCH ON THE ORIGINAL DRAWING.

USE TO VERIFY FIGURE REPRODUCTION SCALE

No.	Date	Revisions	By	Ckd

Professional Engineer's Name  
**THOMAS P. ARMSTRONG JR.**  
Professional Engineer's No.  
085236  
State  
NY  
Date Signed  
8-29-08  
Project Mgr.  
CSG  
Designed by  
TPA  
Drawn by  
EK  
Checked by  
TEM/WSW



NORTHROP GRUMMAN CORPORATION • BETHPAGE, NEW YORK  
OPERABLE UNIT 3 - FORMER GRUMMAN SETTLING PONDS  
**EQUIPMENT DETAILS AND SCHEMATICS**

MECHANICAL

ARCADIS Project No.  
NY001464.1607.0003  
Date  
JULY 2008  
ARCADIS  
6723 Township Road  
Box 66  
Syracuse, NY 13214  
Tel: 315-446-9120

CITY:SYR-AY DIV:GROUP:65 DB:GHS LD:GHS PIC: PM: TM: LYRON-OF-REF-  
 C:\projects\001464\1401\elec\drawings - Recovery Well\AutoCAD Drawings\7-25-08\16 Electrical Plan Instrumentation\7-22-08.dwg LAYOUT: 16 SAVED: 7/25/2008 1:55 PM ACADVER: 17.15 (LMS TECH) PAGES: 16 BETHPAGE OCE 54X22 PLOTSTYLE: CTB PLOTTED: 8/29/2008  
 PROJECTNAME: ---  
 IMAGES: 01464X00 Equipment Layout  
 XREFS: ---



CONDUCTOR WIRE			
SYMBOL	CONTROL WIRE	GROUND	CONDUIT
D2	2#14	1#14	3/4"
D4	4#14	1#14	3/4"
D8	8#14	1#14	3/4"
D14	14#14	1#14	3/4"
D40	40#14	1#14	1 1/4"
A1	(1) PR #18	1#14	3/4"
A2	(2) PR #18	1#14	3/4"
A4	(4) PR #18	1#14	3/4"
P2	2 #12	1#12	3/4"

**NOTES**

- ALL CONTROL WIRE HOMERUNS SHALL TERMINATE IN MAIN CONTROL PANEL (MCP), UNLESS OTHERWISE NOTED.
- REFER TO SHEET 14 FOR POWER CIRCUITING AND CONDUCTOR REQUIREMENTS.
- SFSI-CP SHALL BE LOCATED ADJACENT TO MCP.
- DISCRETE HOMERUNS MAY BE COMBINED IN ONE CONDUIT PROVIDED CONDUIT IS NO MORE THAN 40% FULL.
- ANALOG HOMERUNS MAY BE COMBINED IN ONE CONDUIT PROVIDED CONDUIT IS NO MORE THAN 40% FULL.


**DESIGN ASSUMPTIONS**

- AUTODIALER IS INCLUDED IN MAIN CONTROL PANEL (MCP). THEREFORE, HARDWIRING TO AUTODIALER IS NOT SHOWN ON THESE DRAWINGS.
- PLC ALARM INDICATION LIGHTS ARE INCLUDED WITHIN THE MCP. THEREFORE, HARDWIRING TO INDICATION LIGHTS ARE NOT SHOWN ON THESE DRAWINGS.
- AIR STRIPPER INSTRUMENTATION WIRING BETWEEN DEVICES AND AIR STRIPPER CONTROL PANEL ARE PROVIDED BY AIR STRIPPER EQUIPMENT MANUFACTURER. THEREFORE, HARDWIRING FOR THESE DEVICES TO AIR STRIPPER CONTROL PANEL IS NOT SHOWN.



No.	Date	Revisions	By	Ckd


Professional Engineer's Name  
**THOMAS P. ARMSTRONG JR.**  
 Professional Engineer's No.  
 085236  
 State NY Date Signed 8-29-08 Project Mgr. CSG  
 Designed by TPA Drawn by EK Checked by TEM/WSW





NORTHROP GRUMMAN CORPORATION • BETHPAGE, NEW YORK  
 OPERABLE UNIT 3 - FORMER GRUMMAN SETTLING PONDS  
**EQUIPMENT LAYOUT - INSTRUMENTATION**  
 MECHANICAL

ARCADIS Project No.  
 NY001464.1807.00003  
 Date  
 JULY 2008  
 ARCADIS  
 6723 Towpath Road  
 Box 66  
 Syracuse, NY 13214  
 Tel: 315-446-9120

CITY:SYR-AY DIV:GROUP:85 DB:GHS LD:GHS PIC: PM: TM: LYRON+OFF-REF-  
 G:\Projects\NY01464\_1407\ElectricalDrawings - Recovery Well\AutoCAD Drawings\15-0815 Electrical Plan-7-25-08.dwg LAYOUT: 15 SAVER: 7/25/2008 1:55 PM ACADVER: 17.1S (LMS TECH) PAGES: 001-002 PLOTSTYLETABLE: PLOTCONT.LCTB PLOTTED: 8/29/2008 6:28 PM BY: ARMSTRONG, TOM




HVAC AND LIGHTING SCHEDULE						
SYMBOL	DESCRIPTION	MOUNTING	MANUFACTURER & PART NUMBER	QUANTITY	REMARKS	MISC.
FA3	LIGHTING FIXTURE 3-LAMP FLOURESCENT, OPEN-TYPE	PENDANT	DAY-BRITE CAT #: 1F332PP120	8	120 VAC, 59-INCH T8 LAMPS, PENDANT MOUNT FROM CEILING AT 9'-0" AFF.	
WP1	LIGHTING FIXTURE, WALL PACK, HPS	WALL	DAY-BRITE CAT #: NWP070S12	3	120 VAC, 70 WATT HPS LAMPS, MOUNT 9'-6" ABOVE GRADE.	
XA-1	EXIT SIGN, ILLUMINATED	WALL	DAY-BRITE CAT #: VERW	2	SINGLE-FACE, RED LED LETTERS MOUNT 7'-2" AFF	
EF-X	EXHAUST FAN WALL-MOUNTED	WALL	EF-1: GREENHECK SBE-1H20-4 EF-2: GREENHECK SE1-8-440-D-1	1 1	120 VAC, WITH THERMOSTAT	
E-1	EMERGENCY LIGHTS	WALL	DAY-BRITE CAT #: VU6	3	MOUNT 8'-0" AFF.	
EUH-X	UNIT HEATER, FORCED AIR, RESISTIVE	CEILING	EUH-1: CHROMALOX LUH-05-43-32 EUH-2: CHROMALOX LUH-07-43-32 EUH-3: CHROMALOX LUH-02-32-34	1 1 1	w/REMOTE THERMOSTAT	ALL w/EDS-1
L-X	LOUVER	WALL	L-1: ECD-601, 2.09 sq.ft of FREE AREA L-2: ECD-601, 0.46 sq.ft of FREE AREA	1 1	120 VAC ACTUATOR, EXTERIOR BIRDSCREEN, INTERIOR INSECT SCREEN	



No.	Date	Revisions	By	Ckd

THIS DRAWING IS THE PROPERTY OF THE ARCADIS ENTITY IDENTIFIED IN THE TITLE BLOCK AND MAY NOT BE REPRODUCED OR ALTERED IN WHOLE OR IN PART WITHOUT THE EXPRESS WRITTEN PERMISSION OF SAME.

Professional Engineer's Name  
**THOMAS P. ARMSTRONG JR.**  
 Professional Engineer's No.  
 085236  
 State NY Date Signed 8-29-08 Project Mgr. CSG  
 Designed by TPA Drawn by EK Checked by TEM/WSW




NORTHROP GRUMMAN CORPORATION • BETHPAGE, NEW YORK  
 OPERABLE UNIT 3 - FORMER GRUMMAN SETTLING PONDS

## EQUIPMENT LAYOUT - ELECTRICAL

MECHANICAL

ARCADIS Project No. NY001464.1807.00003  
 Date JULY 2008  
 ARCADIS  
 6723 Towpath Road  
 Box 66  
 Syracuse, NY 13214  
 Tel: 315-446-9120

CITY:SYR-NY DIV/GROUP:85 DB:GHS LD:GHS PIC: PM: TH: LYR:ONE-OFF-REF- G:\Project\NY001484\_1407\ElectricalDrawings - Recovery Well\AutoCAD Drawings\7-25-08\14 One-Line.dwg  
 LAYOUT: 14 SAVED: 7/25/2008 1:55 PM ACADVER: 17.14 (LMS TECH) PAGES: 17.14 (LMS TECH) PLOT: 8/29/2008 6:28 PM BY: ARMSTRONG, TOM  
 PROJECT NAME: 01464X00



- NOTES:**
- PROVIDE 2 #12, 1 #12 GROUND -3/4" C. FOR EACH LIGHTING AND RECEPTACLE CIRCUIT, UNLESS OTHERWISE NOTED.
  - MAIN DISCONNECT SHALL BE LOCATED AT BUILDING IN ACCORDANCE WITH NEC.

**ABBREVIATIONS**

1FVNR	FULL VOLTAGE, NON-REVERSING (SIZE 1) STARTER
A.F.F.	ABOVE FINISHED FLOOR
A	AMPERES
DTT	DRY TYPE TRANSFORMER
EF	EXHAUST FAN
EUH	ELECTRIC UNIT HEATER
HP	HORSEPOWER
kVA	KILOVOLT-AMPS
kW	KILOWATT
MCC	MOTOR CONTROL CENTER
MCP	MOTOR CIRCUIT PROTECTOR CIRCUIT BREAKER
O.L.	OVERLOAD
PB	PANELBOARD
T-M	THERMAL MAGNETIC CIRCUIT BREAKER
V	VOLTS
VAC	VOLTS AC

**LEGEND**

	ENCLOSURE LIMITS
	MOTOR STARTER, FVNR-TYPE EQUIPPED WITH THERMAL OVERLOADS (FULL VOLTAGE, NON-REVERSING)
	MOTOR, # DENOTES H.P.
	EARTH GROUND
	TRANSFORMER, POWER
	MOLDED CASE CIRCUIT BREAKER
	ELECTRIC UTILITY METER CABINET
	ENCLOSED SWITCH NF = NON-FUSIBLE XX = NEMA RATING ZZ = AMPACITY RATING
	CONDUCTOR SYMBOL

**CONDUCTOR SCHEDULE**

SYMBOL	QUANTITY	WIRE SIZE	GROUND	CONDUIT	COMMENTS
20	3	#12	1 #12	3/4"	
30	3	#10	1 #10	1"	
50	3	#6	1 #6	1"	
70	3	#4	1 #4	1 1/2"	
100	3	#2	1 #2	1 1/4"	
200	4	#3/0	1 #4	2 1/2"	PROVIDE TYPE "USE-2" OR "XHHW-2"
400	(2 SETS) 4	#3/0	1 #1/0	(2) 2 1/2"	PROVIDE TYPE "USE-2" OR "XHHW-2"

**PANEL PB-1 ENCLOSURE: NEMA TYPE 1, CABINET MOUNTING: SURFACE**  
**VOLTS: 120 / 240, PHASE: 1, WIRE: 3W, 10,000 AIC, 60A. C/B, FEED: TOP**

LOAD SERVED	LOAD (KVA)		BREAKER		CKT	PH	CKT	BREAKER		LOAD (KVA)		LOAD SERVED	
	A	B	AMP	POLE				POLE	AMP	A	B		
LIGHTS - CONTROL ROOM	0.1		20	1	1	A	2	1	20	0.6		RECEPTACLES - A	
LIGHTS - PUMP ROOM	0.6		20	1	3	B	4	1	20	0.4		RECEPTACLES - B	
LIGHTS - OUTDOOR	0.4		20	1	5	A	6	1	20	0.4		RECEPTACLES - OUTDOOR	
MAIN CONTROL PANEL		1.0	20	1	7	B	8	1	20	0.1		EXIT LIGHTS	
SUMP PUMP (P-900)	0.7		20	1	9	A	10	1	20	0.6		6 FLOW METERS (FIT)	
EUH-3 (CONTROL ROOM)	1.3		20	2	11	B	12	1	20	1.1		BOOSTER PUMP (P-800)	
			20	1	13	A	14	1	20	0.4		EF-1 / L1	
SFSLCP		0.2	20	1	15	B	16	1	20	0.4		EF-2 / L2	
SPARE			20	1	17	A	18	1	20			SPARE	
BLANK			20	1	19	B	20	1	20			BLANK	
BLANK			20	1	21	A	22	1	20			BLANK	
BLANK			20	1	23	B	24	1	20			BLANK	
BLANK			20	1	25	A	26	1	20			BLANK	
BLANK			20	1	27	B	28	1	20			BLANK	
BLANK			20	1	29	A	30	1	20			BLANK	
<b>TOTAL</b>		2.5	3.1							2.0	2.0		
TOTAL CONNECTED KVA:													
										A: 4.4			
										B: 5.1			
										TOTAL: 9.5			

**ELEVATION MCC-1**

MAIN LUGS (200A)	TRANS. PRIMARY	EUH-1
6" BLANK SPACE		6" BLANK SPACE
TVSS	EUH-2	
RW-1		RW-3
RW-2		RW-4
12" BLANK SPACE	FUTURE DUCT HEATER	6" BLANK SPACE
AIR STRIPPER		12" BLANK SPACE


**NO SCALE**

THIS BAR REPRESENTS ONE INCH ON THE ORIGINAL DRAWING.

USE TO VERIFY FIGURE REPRODUCTION SCALE

No.	Date	Revisions	By	Ckd

Professional Engineer's Name  
**THOMAS P. ARMSTRONG JR.**  
 Professional Engineer's No.  
 085236  
 State: NY Date Signed: 8-29-08 Project Mgr.: CSG  
 Drawn by: EK Checked by: TEM/MWSW



**ARCADIS**  
 ARCADIS OF NEW YORK, INC.



NORTHROP GRUMMAN CORPORATION • BETHPAGE, NEW YORK  
 OPERABLE UNIT 3 - FORMER GRUMMAN SETTLING PONDS

**ONE-LINE DIAGRAM**

ELECTRICAL

ARCADIS Project No.  
 NY001464.1807.00003  
 Date  
 JULY 2008  
 ARCADIS  
 6723 Towpath Road  
 Box 66  
 Syracuse, NY 13214  
 Tel: 315-446-9120

CITY:STR-AY; DIV:GROUP:85; DB:GHS; LD:GHS; PIC: TM; LYNONE="OFF=REF"; G:\p\electrical\1407\electrical\CAD Drawings\17-25-08\13 Electrical Site.dwg LAYOUT: 13; SAVER: 7/25/2008 1:55 PM; ACADVER: 17.1S (LMS TECH); PAGES: 1; BETHPAGE DCE 34X22 PLOTSTYLETABLE: PLOTCONT1.CTB; PLOTTED: 8/29/2008 6:28 PM; BY: ARMSTRONG, TOM



SYMBOL	WIRE		GROUND	CONDUIT	COMMENTS
	QUANTITY	SIZE			
20	3	#12	1 #12	3/4"	
30	3	#10	1 #10	1"	
50	3	#6	1 #6	1"	
70	3	#4	1 #6	1 1/2"	
400	(2 SETS) 4	#3/0	1 #1/0	(2) 2 1/2"	PROVIDE TYPE "USE-2" OR "X-HW-2"

- NOTES:**
- SEE CONTRACT DRAWING 14 FOR ONE-LINE DIAGRAM.
  - SEE CONTRACT DRAWING 17 FOR ELECTRIC HANDHOLE AND TRENCHING DETAILS.
  - CONDUIT TRENCH TO BE INSTALLED WITHIN LIMITS OF EXISTING OU3 SG PIPE TRENCH WHERE POSSIBLE.

**LEGEND**

# CONDUCTOR SYMBOL - REFER TO SCHEDULE  
 □ HH-# ELECTRIC HANDHOLE  
 ● RW-# RECOVERY WELL  
 --- ELECTRIC CONDUCTOR

**ELECTRICAL SPECIFICATIONS:**

**GENERAL**

- ALL ELECTRICAL EQUIPMENT SHALL BE U.L. LISTED AND LABELED.
- ALL ELECTRICAL WORK SHALL BE IN ACCORDANCE WITH THE LATEST REVISION OF NFPA-70 NEC.

**RIGID METAL CONDUIT (RGS)**

- GALVANIZED STEEL, HOT-DIPPED ZINC, ANSI STANDARD C80.1 AND C80.4.
- MANUFACTURER SHALL BE ALLIED TUBE & CONDUIT CORPORATION, TRIANGLE WIRE AND CABLE INC., OR EQUAL.

**NONMETALLIC (PVC) CONDUIT**

- NONMETALLIC RIGID CONDUIT AND FITTINGS SHALL BE SCHEDULE 40, POLYVINYL CHLORIDE AND SHALL BE RESISTANT TO CORROSION.
- CONDUIT AND FITTINGS SHALL BE IN ACCORDANCE WITH NEMA STANDARD TC-2 AND TC-3, LATEST REVISION.
- MANUFACTURER SHALL BE CARLON ELECTRIC CONDUIT CO., TRIANGLE PVC CO., OR EQUAL.

**JUNCTION BOXES**

JUNCTION BOXES AND FITTINGS SHALL BE OF GALVANIZED STEEL OR COPPER FREE ALUMINUM.

**WIRES AND CABLES**

- GENERAL
  - ALL CONDUCTORS, UNLESS OTHERWISE NOTED, SHALL BE STRANDED COPPER, CONSTRUCTED OF SOFT DRAWN OR ANNEALED COPPER.
  - CONDUCTORS INSULATION SHALL BE COLOR CODED, WITH COLOR OF INSULATION ONE COLOR THROUGHOUT THE ENTIRE RUN.
  - 120/240 VAC, SINGLE PHASE, 3 WIRE  
 CONDUCTOR 1 - BLACK  
 CONDUCTOR 2 - RED  
 NEUTRAL - WHITE  
 GROUND - GREEN
- LOW VOLTAGE CONDUCTORS
  - ALL CONDUCTORS FOR POWER, LIGHTING AND 120 VAC CONTROL SHALL BE RATED A MINIMUM 600 VAC.
  - CONDUCTORS SHALL BE CONSTRUCTED OF UNCOATED CLASS C COPPER CONCENTRIC-LAY-STRANDED WIRES.
  - POWER AND LIGHTING CONDUCTORS SHALL BE TYPE THHN-90C/THWN-2-90C WITH PVC INSULATION AND NYLON JACKET.
- INSTRUMENTATION CABLES
  - TWISTED PAIR OF NO. 18 AWG TINNED COATED CLASS C COPPER CONCENTRIC LAY STRANDED WIRES WITH AN ALUMINUM POLYESTER SHIELD AND COPPER DRAIN. RATED FOR 600V AND COLOR COATED PVC OUTER JACKET.
- CONNECTORS
  - PIGTAIL SPlicing #10 AND SMALLER, USE TAPERED SPRING WIRE NUTS. MANUFACTURER SHALL BE IDEAL WING NUT, BUCHANAN B-CAP, T&B PIGGIES, OR EQUAL.
  - FOR TERMINATION OF #14 CONTROL WIRES TO TERMINALS, USE INSULATED COMPRESSION SPADE TYPE CONNECTORS. MANUFACTURER SHALL BE BURNDY HYDENT, T&B STA-KON, OR EQUAL.
  - SPLICERS AND TERMINALS FOR #8 AND LARGER SHALL BE COPPER COMPRESSION TYPE. MANUFACTURER SHALL BE BURNDY HYDENT OR HYLUG, T&B, STA-CON, OR EQUAL.
  - FIXTURE CONNECTIONS MANUFACTURER SHALL BE T&B STA-KON SERIES PT-66M, IDEAL CRIMP SLEEVE NO. 410 WITH LONG BARREL, OR EQUAL.

**GROUNDING**


- GROUNDING OF ELECTRICAL SYSTEMS AND EQUIPMENT SHALL, AT A MINIMUM, MEET THE REQUIREMENTS OF THE NEC ARTICLE 250 OR SHALL EXCEED ARTICLE 250 AS HEREIN SPECIFIED.
- ALL CONDUITS SHALL HAVE AN INTERNAL GROUND CONDUCTOR. THIS GROUND CONDUCTOR SHALL BE PROVIDED ALTHOUGH IT MAY NOT BE SHOWN OR SCHEDULED ON THE PLANS.
- GROUNDING ELECTRODE CONDUCTORS SHALL BE A MINIMUM OF NO. 6 AWG STRANDED COPPER.
- GROUND RODS SHALL BE 3/4" DIAMETER, 10 FEET LONG, STEEL CORE WITH COPPER MOLTEN WELDED OR ELECTROLYTICALLY BONDED TO EXTERIOR.
- ALL CONNECTIONS SHALL BE MADE WITH COMPRESSION OR CADWELD CONNECTORS.

**ENCLOSURE**

- ENCLOSURES SHALL BE NEMA RATED FOR LOCATION UNLESS OTHERWISE NOTED.
- WET LOCATIONS OR OUTDOORS, ENCLOSURES SHALL BE NEMA TYPE 4, STAINLESS STEEL.
- ENCLOSURES SHALL HAVE NAMEPLATE ON THE EXTERIOR IDENTIFYING THE APPLICATION FUNCTION OF THE EQUIPMENT ENCLOSED.

**WIRING DEVICES**

- RECEPTACLES MARKED AS GFCI SHALL BE OF THE GROUND FAULT CIRCUIT INTERRUPTER TYPE. MANUFACTURER SHALL BE GE TYPE TGR 20, OR EQUAL.
- SWITCHES
  - LIGHTING SWITCHES SHALL BE RATED 20 AMPERES AT 277 VAC, TOGGLE OPERATED, PLASTIC ENCLOSED, SINGLE POLE, THREE-WAY OR FOUR-WAY AS SHOWN OR REQUIRED. MANUFACTURER SHALL BE P&S SERIES 20AC1 SPECIFICATION GRADE, OR EQUAL.
  - SWITCHES SHALL HAVE SILVER ALLOY CONTACTS AND PROVISIONS FOR SIDE AND BACK WIRING.
  - EACH SWITCH SHALL BE SUITED FOR FULL-RATED CAPACITY ON TUNGSTEN FILAMENT AND FLUORESCENT LAMP LOADS.
- FACEPLATE AND COVERS
  - FINISHED AREAS SHALL HAVE STAINLESS STEEL TYPE 302 ALLOY COVERS.
  - WET AND CORROSIVE AREAS SHALL BE WEATHERPROOF COVERS WITH GASKETS.



No.	Date	Revisions	By	Ckd



USE TO VERIFY FIGURE REPRODUCTION SCALE

Professional Engineer's Name  
**THOMAS P. ARMSTRONG JR.**

Professional Engineer's No.  
085236

State: NY Date Signed: 8-29-08 Project Mgr.: CSG

Designed by: TPA Drawn by: EK Checked by: TEM/MSW



NORTHROP GRUMMAN CORPORATION • BETHPAGE, NEW YORK  
OPERABLE UNIT 3 - FORMER GRUMMAN SETTLING PONDS

**ELECTRICAL SITE PLAN**

ELECTRICAL

ARCADIS Project No.  
NY001464.1807.00003

Date  
JULY 2008

ARCADIS  
6723 Towpath Road  
Box 66  
Syracuse, NY 13214  
Tel: 315-446-9120