

Outpost Monitoring Well Installation Summary Report

1-30-003B

Naval Weapons Industrial Reserve Plant (NWIRP)

Bethpage, New York



Engineering Field Activity Northeast Naval Facilities Engineering Command

Contract Number N62467-94-D-0888

Contract Task Order 0812

March ²⁰⁰⁴ 2004

**OUTPOST MONITORING WELL INSTALLATION
SUMMARY REPORT**

**NAVAL WEAPONS INDUSTRIAL RESERVE PLANT (NWIRP)
BETHPAGE, NEW YORK**

**COMPREHENSIVE LONG-TERM
ENVIRONMENTAL ACTION NAVY (CLEAN) CONTRACT**

**Submitted to:
Engineering Field Activity Northeast
Environmental Branch Code EV2
Naval Facilities Engineering Command
10 Industrial Highway, Mail Stop #82
Lester, Pennsylvania 19113-2090**



**Submitted by:
TetraTech NUS, Inc.
600 Clark Avenue, Suite 3
King of Prussia, Pennsylvania 19406-1433**

**CONTRACT NUMBER N62467-94-D-0888
CONTRACT TASK ORDER 0812**

MARCH 2004

PREPARED UNDER THE DIRECTION OF:

A handwritten signature in black ink, appearing to read "David D. Brayack", written over a horizontal line.

**DAVID D. BRAYACK
PROJECT MANAGER
PITTSBURGH, PENNSYLVANIA**

APPROVED FOR SUBMISSION BY:

A handwritten signature in black ink, appearing to read "John J. Trepanowski", written over a horizontal line.

**JOHN J. TREPANOWSKI
PROGRAM MANAGER
KING OF PRUSSIA, PENNSYLVANIA**

TABLE OF CONTENTS

<u>SECTION</u>		<u>PAGE NO.</u>
1.0	INTRODUCTION	1-1
1.1	SCOPE OF WORK	1-1
1.2	REPORT FORMAT	1-1
2.0	WELL DRILLING AND INSTALLATION	2-1
2.1	DRILLING METHODOLOGY	2-1
2.2	SOIL SAMPLING	2-1
2.3	BOREHOLE GEOPHYSICAL LOGGING	2-1
2.4	MONITORING WELL INSTALLATION	2-2
2.5	MONITORING WELL DEVELOPMENT AND SAMPLING	2-3
2.6	WELL REHABILITATION AND RECONSTRUCTION	2-4

TABLE

2-1	OUTPOST MONITORING WELL CONSTRUCTION SUMMARY	2-6
-----	--	-----

FIGURE

1-1	OUTPOST MONITORING WELL LOCATIONS	1-2
-----	---	-----

APPENDICES

A	BPOW1-1 WELL DATA
B	BPOW1-2 WELL DATA
C	BPOW1-3 WELL DATA
D	BPOW2-1 WELL DATA
E	BPOW2-2 WELL DATA
F	BPOW3-1 WELL DATA
G	BPOW3-2 WELL DATA
H	BPOW4-1 WELL DATA
I	BPOW4-2 WELL DATA
J	CHAIN-OF-CUSTODY FORMS
K	SAMPLE LOG SHEETS
L	ANALYTICAL RESULTS
M	SURVEY DATA

1.0 INTRODUCTION

This report summarizes the installation and development of nine Outpost Monitoring Wells located south and hydraulically downgradient of the Naval Weapons Industrial Reserve Plant (NWIRP) New York. The wells were installed in support of Navy's Record of Decision for Operable Unit No. 2 (April 2003) to provide advance warning of potential contaminant impact to local public water suppliers. Tetra Tech NUS, Inc., (TtNUS) performed the work for the U.S. Navy Engineering Field Activity Northeast under Contract Task Order 0812 of Comprehensive Long-Term Environmental Action Navy (CLEAN) Contract Number N62467-94-D-0888.


1.1 SCOPE OF WORK

Nine Outpost Monitoring Wells (BPOW1-1, 1-2 and 1-3, BPOW2-1 and 2-2, BPOW3-1 and 3-2, and BPOW 4-1 and 4-2) were drilled and installed between June 2003 and December 2003. These wells were installed in accordance with the "Work Plan Addendum for Outpost Monitoring Wells Installation Program" attached as Appendix B to the "Public Water Supply Contingency Plan" dated July 2003. Figure 1-1 illustrates the approximate locations of these wells.

Target screen intervals were initially selected with the aid of an advanced regional groundwater model that accounted for the location of groundwater contamination, groundwater flow paths, and screen intervals and extraction rates for local public water supply wells. Final screen intervals were selected in the field based on actual lithology. These intervals are summarized in Table 2-1. Final well locations and well head elevations were surveyed.

1.2 REPORT FORMAT

This report presents the methodology and field logs for the installation of the Outpost Monitoring Wells. Section 1.0 provides a brief introduction and summary of the scope of work. Field methodologies for well installation are provided in Section 2.0. Monitoring well construction diagrams, boring logs, borehole geophysical logs, and well development sheets for each well are provided in the appendices. The information is organized by well, with Appendices A through I providing the data for Wells BPOW1-1 through BPOW4-2, respectively. Groundwater samples were collected at the end of well development. Chain-of-custody forms, sample log sheets, and analytical results are presented in Appendices J, K, and L, respectively. Survey drawings are provided in Appendix M.



DRAWN BY J. LAMEY	DATE 4/28/00
CHECKED BY D. BRAYACK	DATE 12/23/02
COST/CHECKED AREA	
SCALE AS NOTED	

Tetra Tech NUS, Inc.
LOCATION OF OUTPOST MONITORING WELLS
NAVAL WEAPONS INDUSTRIAL RESERVE PLANT
BETHPAGE, NEW YORK

CONTRACT NUMBER N4037	OWNER NUMBER
APPROVED BY	DATE
APPROVED BY	DATE
DRAWING NO. FIGURE 1-1	REV 0

2.0 WELL DRILLING AND INSTALLATION

This section describes the field methodologies for installation and development of nine Outpost Monitoring Wells. The work was performed in accordance with the "Work Plan Addendum for Monitoring Well Installation Program, Naval Weapons Industrial Reserve Plant, Bethpage, New York" (TtNUS, July 2003). Field work was performed from June through December 2003. Uni-Tech Drilling Company, Inc. (UTD), of Malaga, New Jersey, drilled and installed the wells under subcontract to TtNUS. Aqua Terra Geophysics, Inc., of Bellport, New York, under subcontract to UTD, performed the borehole geophysical logging.

2.1 DRILLING METHODOLOGY

Well boreholes were advanced using mud rotary techniques. Well boreholes were approximately 8 inches in diameter. In addition, boreholes for wells BPOW2-2, BPOW3-2, BPOW4-1 and BPOW4-2 were initially reamed to 10 to 12 inches in diameter to a depth of approximately 87 to 105 feet to allow for installation of permanent, polyvinyl chloride (PVC) surface casing. This casing was used to control sloughing of the upper borehole. Drilling mud consisted of potable water and polymer-free sodium bentonite. All drilling mud was contained and recirculated in a baffled, high capacity mud pan.

2.2 SOIL SAMPLING

Soil samples were collected from well borings for lithology description. The samples were collected from the deepest well at each cluster and were taken at periodic depths at the discretion of the field geologist. The samples were described and entered on the boring logs as shown in the attachments. The soil samples were used to provide a comparison to the geophysical logs that were also run on the deepest well at each cluster. The well screen placement was determined by evaluating the geophysical log for each cluster.

Soil samples were collected using 2-inch diameter split-spoon samplers according to American Standard of Test Methods (ASTM) D-1586. Depths not sampled were logged for lithology based on the drilling cuttings brought to the surface entrained in the drilling mud.

2.3 BOREHOLE GEOPHYSICAL LOGGING

Borehole geophysical logs were recorded in the deepest wells (BPOW1-3, BPOW2-2, BPOW3-2 and BPOW4-2) installed. Following advancement to the total well depth of each well boring to be logged, the drilling tools were withdrawn from the borehole. A geophysical probe was then run down the borehole and back up. The geophysical data was recorded using a Mount Sopris MGX II digital logger. The probe was

multi-function and recorded a natural gamma ray log, as well as single point resistivity, and standard potential logs. Geophysical borehole log printouts are provided for the logged wells in the appendices.

2.4 MONITORING WELL INSTALLATION

After advancement of the well borings to the appropriate depths, monitoring wells were installed to the depths indicated in Table 2-1. The mud in the screened interval was thinned to the fullest extent possible prior to well installation. Well material was then installed in the open borehole to the appropriate depth.

All of the wells were constructed of 4-inch diameter, Schedule 80, National Sanitation Foundation-approved polyvinyl chloride (PVC) well screen and riser pipe. All well screens had slot sizes of 0.010 inches. Threaded bottom caps were fitted to the bottom of each well. All pipe sections and bottom caps were flush-jointed and flush-threaded.

Primary filter packs were installed in the annuli around the well screens to the depths indicated in Table 3-1. The filter packs consisted of FilterPro #1 quartz sand installed using a tremie pipe or by allowing the filter pack to gravity fall into the annulus from the surface. Filter packs were installed to the approximate depths as follows:

- Deep (D) Wells: minimum of 10 feet above the top of the screen
- Deep 2 (D2) Wells: minimum of 20 feet above the top of the screen
- Deep 3 (D3) Wells: minimum of 25 feet above the top of the screen

Secondary filter packs of finer sand (FilterPro #0 quartz sand) than the primary filter pack were installed in the annulus around the well riser above the primary filter pack to the depths indicated in Table 3-1. The secondary filter packs were installed to the approximate depths as follows:

- Deep (D) Wells: minimum of 5 foot above the top of the primary filter pack
- Deep 2 (D2) Wells: minimum of 10 foot above the top of the primary filter pack
- Deep 3 (D3) Wells : minimum of 15 feet above the top of the primary filter pack

A 2- to 4-foot thick bentonite seal was installed above the secondary filter pack. The annulus above the bentonite seal was grouted with Volclay© high-solids bentonite slurry. Both the bentonite seal and bentonite slurry were installed using a tremie pipe.

Seven of the nine wells were completed at the surface with a 12-inch diameter steel curb box, set in a 3-foot by 3-foot by 0.5-foot thick concrete pad (BPOW1-1 to BPOW3-2). Because of limited space between

an underground utility and the curb, two of the wells were installed with a 9-inch diameter steel curb box (BPOW4-1 and BPOW4-2). The concrete pad on these two wells was the same as the other seven wells. A layer of fine sand was installed above the grout slurry and inside the curb box to allow for drainage of water from the curb box. The tops of all well risers were set approximately 8 inches below grade. Lockable gripper caps were installed on all well riser tops.

2.5 MONITORING WELL DEVELOPMENT AND SAMPLING

The monitoring wells were developed to remove drilling mud and fine formation particles from the well filter packs. Monitoring wells were developed no sooner than 24 hours after installation. Development was accomplished using two methods: airlifting, mechanical surging, and pumping with a submersible pump for all of the wells.

Monitoring wells were developed using a combination of air lifting, mechanical surging, and pumping with a submersible pump. A threaded, 2-inch diameter steel eductor pipe with a surge block assembly was installed in the wells with the surge block set at the base of the well screen. A 3/4-inch diameter polyethylene airline was inserted in the eductor pipe to a depth above the top of the well screen. The deep wells were developed at 5-foot intervals in the screened interval using a combination of mechanical surging (vertical movement of the surge block by a truck-mounted mechanical device) and air lifting. Once the screened interval was completely developed using this technique, the pipe was removed from the well and development continued using a submersible pump. The submersible pump was placed approximately 50 to 75 feet below the static water level in order to remove the stagnant water from above the well screen. When the water became clear, the inside of the well casing was rinsed with water from the pump discharge, and the pump was slowly raised through the water column (with the pump running) until it was at or near the static water level. Pumping ceased and development was complete when the water level stabilized, all traces of drilling mud were removed, and the well produced clear, sediment-free water. The well cap was cleaned and rinsed with deionized water and placed back onto the well riser.

Field water quality parameters of pH, specific conductance, temperature, dissolved oxygen, and turbidity were monitored and recorded periodically throughout well development. In compliance with NYSDEC policy, all wells, (except for BPOW3-2 and BPOW4-2), were developed until turbidity was less than 50 nephelometric turbidity units (NTUs). Every effort was made to develop well BPOW3-2 and BPOW4-2 to a measured turbidity of less than 50 NTUs; however, the 50 NTU criterion was unattainable in these wells due to the lithology of the formation screened (clay and clayey/silty sand). In this case, turbidity was stabilized and development was deemed complete.

Following development of the pumping stage, the pump rate was decreased and a groundwater sample was collected from each well and was analyzed for VOC compounds. All development fluids were containerized and stored at the decontamination area for proper disposal to the POTW.

2.6 WELL REHABILITATION AND RECONSTRUCTION

Monitoring well BPOW4-1 was installed on July 17, 2003. The well screen was set from 652 to 692 feet below ground surface (bgs). During development it was determined that the 4-inch diameter well screen had been damaged and that sand had infiltrated through the screen to a depth of approximately 660 feet bgs. It is unknown how the damage occurred. Well development was terminated and the repair of this well would be conducted at a later date by Unitech Drilling Company, Inc.

On December 8, 2003 repair of this well began. A 2-inch diameter threaded steel pipe was lowered into the 4-inch schedule 80 well screen and riser using the Failing 1500 drill rig. At approximately 660 feet bgs resistance was hit, indicating the level of the sand. Once the pipe was set, a ½-inch polyethylene tubing was placed inside the 2-inch pipe to a depth of approximately 200 feet. An Atlas Copco 185 CFM air compressor was used to supply air through the tubing. As the air was introduced through the tubing, both water and sand began to exit up through the 2-inch pipe and into the mud tub that was placed over the well. This method is similar to the reverse circulation method of drilling and also similar to the air lift method of development. A constant head of water had to be introduced to the well in an effort to keep the sand from entering the well. Water was supplied by using a 2,000 gallon tank and a 2,000 gallon capacity water truck. Approximately 8,000 gallons was used during the repair operation. Approximately one full 55-gallon drum was filled with sand and debris from the damaged area of the well.

As the water, sand and pieces of well screen was evacuated from the hole, UTD began to lower the 2-inch pipe further into the well screen. The 2-inch pipe was finally lowered to a depth of approximately 692 feet bgs, indicating that all of the sand had been evacuated from the well. Material that was forced out of the well included a fine to coarse sand, fine sub-rounded gravel, traces of lignite and pieces of well screen. The sand pack used to place around the well screen was also observed in the cuttings that were evacuated.

After several minutes of making sure all debris was evacuated from the well, UTD began to pull the 2-inch pipe, which took approximately 2 hours. Once the pipe was removed, UTD assembled 4 ten foot sections of 2-inch diameter 10 slot stainless steel screen. A stainless steel pointed end cap was placed on the bottom of the screen. A ten foot section of stainless steel riser pipe was attached to the 40 feet of well screen. A "K" packer was then placed on top of the riser pipe. This packer will serve as a barrier to prevent any sand from infiltrating above the screened interval. This 50 foot section, with the riser and

packer at the top was dropped into the well and allowed to free fall, with the water acting as a floating medium, to the bottom of the cleaned out well.

In order to check the depth of the 2-inch well, UTD immediately began to re-insert the 2-inch pipe and was able to determine that the 2-inch well had successfully been installed. The 2-inch pipe hit resistance at approximately 642 feet bgs. UTD left this pipe in overnight and air lift development operations began the following day using the method described in Section 2.5.

**TABLE 2-1
MONITORING WELL SUMMARY
OUTPOST WELLS
NWIRP, BETHPAGE
BETHPAGE, NEW YORK**

Well Number	Casing Set (ft bgs)	Date Start	Date Complete	Total Depth (ft bgs)	Total Well Depth (ft bgs)	Gamma Log Depth (ft bgs)	Screened Interval (ft bgs)	Top of Gravel Pack (ft bgs)	Top of Fine Sand (ft bgs)	Comments
BPOW1-1	NA	11/10/03	11/11/03	250	241		196-231 and 236-241	186	181	Blank Sect. 231-236
BPOW1-2	NA	11/03/03	11/05/03	350	335		310-335	300	295	
BPOW1-3	NA	10/22/03	10/29/03	430	419	419	374-399 and 409-419	364	359	Blank Sect. 399-409
BPOW2-1	NA	8/25/03	8/28/03	410	400		360-365 and 375-400	350	345	Blank Sect. 365-375
BPOW2-2	105	8/6/03	8/21/03	510	495	487	455-495	435	425	
BPOW3-1	NA	9/29/03	10/8/03	530	516		446-451 and 481-516	426	416	Blank Sect. 451-481
BPOW3-2	95	9/15/03	9/26/03	660	647	659	612-632 and 637-647	587	572	Blank Sect. 632-637
BPOW4-1	87	7/8/03	7/18/03	700	692		652-692	620	602	
BPOW4-2	100	6/5/03	7/7/03	780	765	775	725-735 and 745-765	705	690	Blank Sect. 735-745

NOTES:

All well screen and riser was schedule 80 PVC and all screen slot sizes are 0.010 inches (10 slot). Development consisted of air lift, surging and submersible pump and all wells were drilled using the mud rotary method.

ft bgs= feet below ground surface

Blank Sect.= schedule 80 PVC riser placed between screened sections of the well

NA= not applicable. No casing was set in these wells.


Gamma log run only on deepest well in each cluster.

APPENDIX A
BPOW1-1 WELL DATA



MONITORING WELL SHEET

PROJECT: NWIRP DRILLING Co.: UNITECH BORING No.: BPOW1-1
 PROJECT No.: N 4037 DRILLER: BLEMINGS DATE COMPLETED: 11/11/03
 SITE: BETHPAGE DRILLING METHOD: MUD ROT NORTHING: _____
 GEOLOGIST: CONTI DEV. METHOD: AIR LIFT/PUMP EASTING: _____





BORING LOG

PROJECT NAME: NWIRP Bethpage
 PROJECT NUMBER: N4037
 DRILLING COMPANY: Uni-Tech
 DRILLING RIG: FAILING 1500

BORING No.: BPOW 1-1
 DATE: 11/10/03
 GEOLOGIST: Conti
 DRILLER: BLEMINGS

Sample No. and Type or RQD	Depth (FL) or Run No.	Blows / 6" or RQD (%)	Sample Recovery / Sample Length	Lithology Change (Depth/Ft.) or Screened Interval	MATERIAL DESCRIPTION			U S C S *	Remarks	PID/FID Reading (ppm)			
					Soil Density/ Consistency or Rock Hardness	Color	Material Classification			Sample	Sampler BZ	Borehole**	Driller BZ**
	0	/					SAND AND GRAVEL	SW	SEE BORING				0
		/						GW	LOG BPOW 1-3 OR GAMMA LOG FOR DETAILS				
	10	/											0
	20	/											0
	30	/					SAND AND GRAVEL	SW GW					0
	40	/											0
	50	/											0

* When rock coring, enter rock brokenness.

** Include monitor reading in 6 foot intervals @ borehole. Increase reading frequency if elevated response read.

Remarks: _____

Drilling Area
 Background (ppm): 0

Converted to Well: Yes No

Well I.D. #: BPOW 1-1



BORING LOG

PROJECT NAME: NWIRP Bethpage
 PROJECT NUMBER: N4037
 DRILLING COMPANY: Uni-Tech
 DRILLING RIG: FAILING 1500

BORING No.: BPOW 1-1
 DATE: 11/10/03
 GEOLOGIST: Conti
 DRILLER: BLEMINGS

Sample No. and Type or RQD	Depth (Ft.) or Run No.	Blows / 6" or RQD (%)	Sample Recovery / Sample Length	Lithology Change (Depth/Ft.) or Screened Interval	MATERIAL DESCRIPTION			U S C S *	Remarks	PID/FID Reading (ppm)			
					Soil Density/ Consistency or Rock Hardness	Color	Material Classification			Sample	Sampler BZ	Borehole**	Driller BZ**
	50	/					SAND AND GRAVEL	GWS SWJ					0
	60	/											0
	70	/											0
	80	/											0
	90	/					SILTY SAND - SOME GRAVEL - TR CLAY						0
	100	/											0

* When rock coring, enter rock brokenness.

** Include monitor reading in 6 foot intervals @ borehole. Increase reading frequency if elevated response read.

Remarks: _____

Drilling Area Background (ppm):

Converted to Well: Yes No Well I.D. #: BPOW 1-1



BORING LOG

PROJECT NAME: NWIRP Bethpage
PROJECT NUMBER: N4037
DRILLING COMPANY: Uni-Tech
DRILLING RIG: FALLING 1500

BORING No.: BPOW 1-1
DATE: 11/11/03
GEOLOGIST: Conti
DRILLER: BLEMINGS

Sample No. and Type or RQD	Depth (FL) or Run No.	Blows / 6" or RQD (%)	Sample Recovery / Sample Length	Lithology Change (Depth/Fl.) or Screened Interval	MATERIAL DESCRIPTION			U S C S *	Remarks	PID/FID Reading (ppm)									
					Soil Density/ Consistency or Rock Hardness	Color	Material Classification			Sample	Sampler BZ	Borehole**	Driller BZ**						
	150																		
	160						SILTY SAND												
	170																		
	180						TR CLAY												
	190																		
	200																		

* When rock coring, enter rock brokenness.

** Include monitor reading in 6 foot intervals @ borehole. Increase reading frequency if elevated response read.

Remarks: _____

Drilling Area Background (ppm):

Converted to Well: Yes No _____ Well I.D. #: BPOW 1-1



BORING LOG

PROJECT NAME: NWIRP Bethpage
PROJECT NUMBER: N4037
DRILLING COMPANY: Uni-Tech
DRILLING RIG: FALING 1500

BORING No.: BPOW1-1
DATE: 11/11/03
GEOLOGIST: Conti
DRILLER: BLEMINGS

Sample No. and Type or RQD	Depth (Ft.) or Run No.	Blows / 6" or RQD (%)	Sample Recovery / Sample Length	Lithology Change (Depth/Ft.) or Screened Interval	MATERIAL DESCRIPTION			U S C S *	Remarks	PID/FID Reading (ppm)								
					Soil Density/ Consistency or Rock Hardness	Color	Material Classification			Sample	Sampler BZ	Borehole**	Driller BZ**					
	200	/					SILTY SAND										0	
	210	/																0
	220	/																0
	230	/		231			SOME CLAY											0
	240	/		236			SILTY SAND		SET WELL 11/11/03									0
	250	/							196 → 231 SCR 231 → 236 BL 236 → 241 SCR									0
									C SAND TO 186 F " TO 181									0

* When rock coring, enter rock brokenness.

** Include monitor reading in 6 foot intervals @ borehole. Increase reading frequency if elevated reponse read.

Remarks: _____

Drilling Area Background (ppm):

Converted to Well: Yes No _____ Well I.D. #: BPOW1-1



Tetra Tech NUS, Inc.

MONITORING WELL DEVELOPMENT RECORD

Well: BPOW1-1 Depth to Bottom (ft.): 241 BGS Responsible Personnel: Conti
 Site: NWIRP Static Water Level Before (ft.): _____ Drilling Co.: Uni-Tech
 Date Installed: 11/11/03 Static Water Level After (ft.): _____ Project Name: NWIRP Bethpage-Outpost Wells
 Date Developed: 11/24/03 Screen Length (ft.): SEE Project Number: N4037
 Dev. Method: AIR LIFT PUMP Specific Capacity: _____
 Pump Type: 3" SUBMERSIBLE Casing ID (in.): 3.316

196-231-SCR
 231-236-BL
 231-241-SCR

Time	Estimated Flow Rate (GPM)	Cumulative Water Volume (Gal.)	Water Level Readings (Ft. below TOC)	Temperature (Degrees C)	pH	Specific Conductance (Units $\mu S/cm$)	Turbidity (NTU)	Remarks (odor, color, etc.)
0955	30	Start	31.6	13.12	4.40	0.362	651/355	Gray-turbid
1015		900	35.17	12.08	4.35	0.329	222/100	Sl. Gray
1035		1400	34.11	11.86	4.32	0.325	168/876	Sl. Gray 10-24y
1040	Load	1600	Start into 2000 gal tank	12.00	4.39	0.310	253/122	1850 / foggy
1055		2500	34.12	11.94	4.42	0.307	185.4/105	2450 / foggy
1015		850	34.48	12.26	4.43	0.303		2700
1125	Load	1100	Start into 2000 gal tank	12.05	4.41	0.308	169/274	3220
1135		300	34.45	12.31	4.43	0.307	200/34	3700
1155		1000	34.00	12.47	4.43	0.303	24/52	400
1215	Load	1600	34.42	12.47	4.43	0.303		
		1800	Start into 2000 gal tank	12.45				
1245		strict 1200 gal tank	32.16	12.08	4.36	0.359	511/339	Known turbid
1305		650	33.48	12.54	4.36	0.359	326/222	4" / 14. Brown
1320		1100	33.52	12.76	4.38	0.360	298/196	5.4" / 14. Brown
	Load	1100	Start into 2000 gal tank	12.34	4.32			
1345		700	33.35	12.34	4.32	0.364	373/218	14. Brown
1405			33.38	12.01	4.32	0.361	248/194	6100 Gray



Tetra Tech NUS, Inc.

MONITORING WELL DEVELOPMENT RECORD

Well: BPOW1-1 Depth to Bottom (ft.): 241.665 Responsible Personnel: Conti
 Site: NWIRP Static Water Level Before (ft.): 31.5 Drilling Co.: Uni-Tech
 Date Installed: 11/11/03 Static Water Level After (ft.): _____ Project Name: NWIRP Bethpage-Outpost Wells
 Date Developed: 11/24/03 & 11/25/03 Screen Length (ft.): _____ Project Number: N4037
 Dev. Method: AIR LIFT/PUMP Specific Capacity: _____
 Pump Type: 3" SUB Casing ID (in.): 3 13/16


Time	Estimated Flow Rate (GPM)	Cumulative Water Volume (Gal.)	Water Level Readings (Ft. below TOC)	Temperature (Degrees C)	pH	Specific Conductance (Units $\mu\text{m S/cm}$)	Turbidity (NTU)	Remarks (odor, color, etc.)
1430	Load	1600	33.41	12.14	7.5	0.358	156/92	7000 / SL. GRAY
11/24/03								
0830	Load	500	31.6	11.83	4.57	0.461	468/260	Total 7000 Gall 11/24/03
0850	Load	1000	32.86	10.82	4.53	0.390	110/28	SL. brown-gray
0910	Load	1000	32.88	10.12	4.50	0.323	57/15	2500 / CLEAR
0915	Load	1000						8000 / CLEAR
1030	START	INTO 1400 GALLON TANK						8100 / CLEAR
1130	13	800	32.6	12.12	4.75	.385	33/12	CLEAR
1140	13	900	32.6	12.00	4.76	.390	38/12	"
1200	12	1100	32.6	11.99	4.78	.389	31/11	"
	LOAD	LUS w/	1100 GALLONS					
	DONE	w/ PUMP	- TOOK SAMPLES	1200 HRS				

11/24/03

11/25/03

8

APPENDIX B
BPOW1-2 WELL DATA






MONITORING WELL SHEET

PERMIT No:

PROJECT: NWIRP DRILLING Co.: UNITECH BORING No.: BPOW1-2
 PROJECT No.: N4037 DRILLER: BLEMINGS DATE COMPLETED: 11/5/03
 SITE: BETHPAGE DRILLING METHOD: MUD ROT NORTHING: _____
 GEOLOGIST: CONTI DEV. METHOD: AIR LIFT/PUMP EASTING: _____



REV 2112104



BORING LOG

PROJECT NAME: NWIRP Bethpage
 PROJECT NUMBER: N4037
 DRILLING COMPANY: Uni-Tech
 DRILLING RIG: FALLING 1500

BORING No.: BPOW 1-2
 DATE: 11/3/03
 GEOLOGIST: Conti
 DRILLER: BLEMINGS

Sample No. and Type or RQD	Depth (Ft.) or Run No.	Blows / 6" or RQD (%)	Sample Recovery / Sample Length	Lithology Change (Depth/Ft.) or Screened Interval	MATERIAL DESCRIPTION			U S C S *	Remarks	PID/FID Reading (ppm)			
					Soil Density/ Consistency or Rock Hardness	Color	Material Classification			Sample	Sampler BZ	Borehole**	Driller BZ**
0930	0	/					SAND AND GRAVEL		SEE BPOW1-3 LOG AND GAMMA LOG FOR MORE DETAIL				0
	10	/											0
	20	/											0
	30	/											0
	40	/											0
1030	50	/											0

* When rock coring, enter rock brokenness.

** Include monitor reading in 6 foot intervals @ borehole. Increase reading frequency if elevated response read.

Remarks: _____

Drilling Area Background (ppm):

Converted to Well: Yes No Well I.D. #: BPOW1-2



BORING LOG

PROJECT NAME: NWIRP Bethpage
 PROJECT NUMBER: N4037
 DRILLING COMPANY: Uni-Tech
 DRILLING RIG: FAILING 1500

BORING No.: BPOW1-2
 DATE: 11/3/03
 GEOLOGIST: Conti
 DRILLER: BLEMINGS

Sample No. and Type or RQD	Depth (FL) or Run No.	Blows / 6" or RQD (%)	Sample Recovery / Sample Length	Lithology Change (Depth/Ft.) or Screened Interval	MATERIAL DESCRIPTION			U S C S *	Remarks	PID/FID Reading (ppm)				
					Soil Density/Consistency or Rock Hardness	Color	Material Classification			Sample	Sampler BZ	Borehole**	Driller BZ**	
	50						SAND & GRAVEL							0
	60													0
	70													0
	80						SILTY SAND - SOME GRAVEL							0
	90													0
	1130													0

* When rock coring, enter rock brokenness.

** Include monitor reading in 6 foot intervals @ borehole. Increase reading frequency if elevated response read.

Remarks: N4037

Drilling Area Background (ppm):

Converted to Well: Yes No Well I.D. #: BPOW1-2



BORING LOG

PROJECT NAME: NWIRP Bethpage
 PROJECT NUMBER: N4037
 DRILLING COMPANY: Uni-Tech
 DRILLING RIG: FALING 1500

BORING No.: BPOW1-2
 DATE: 11/3/03
 GEOLOGIST: Conti
 DRILLER: BLEMINGS

Sample No. and Type or RQD	Depth (Ft.) or Run No.	Blows / 6" or RQD (%)	Sample Recovery / Sample Length	Lithology Change (Depth/FL) or Screened Interval	MATERIAL DESCRIPTION			U S C S *	Remarks	PID/FID Reading (ppm)			
					Soil Density/ Consistency or Rock Hardness	Color	Material Classification			Sample	Sampler BZ	Borehole**	Driller BZ**
	100	/					SILTY SAND	SM SP					0
	1200	110	/										0
	120	/											0
	1300	130	/				SILTY SAND	SM SP					0
	1400	140	/										0
	1500	150	/										0

11/3

* When rock coring, enter rock brokenness.

** Include monitor reading in 6 foot intervals @ borehole. Increase reading frequency if elevated response read.

Remarks: _____

Drilling Area
 Background (ppm):

Converted to Well: Yes No

Well I.D. #: BPOW1-2



BORING LOG

PROJECT NAME: NWIRP Bethpage
 PROJECT NUMBER: N4037
 DRILLING COMPANY: Uni-Tech
 DRILLING RIG: FALING 1500

BORING No.: BPOW 1-2
 DATE: 11-4-03
 GEOLOGIST: Conti
 DRILLER: REMINGS

Sample No. and Type or RQD	Depth (FL) or Run No.	Blows / 6" or RQD (%)	Sample Recovery / Sample Length	Lithology Change (Depth/FL) or Screened Interval	MATERIAL DESCRIPTION			U S C S *	Remarks	PID/FID Reading (ppm)										
					Soil Density/ Consistency or Rock Hardness	Color	Material Classification			Sample	Sampler BZ	Borehole**	Driller BZ**							
	150	/																		0
	160	/																		
	170	/																		
	180	/																		
	190	/																		
	200	/																		

11/4
↓

* When rock coring, enter rock brokenness.

** Include monitor reading in 6 foot intervals @ borehole. Increase reading frequency if elevated response read.

Remarks: _____

Drilling Area Background (ppm): 0

Converted to Well: Yes No Well I.D. #: BPOW1-2



BORING LOG

PROJECT NAME: NWIRP Bethpage
 PROJECT NUMBER: N4037
 DRILLING COMPANY: Uni-Tech
 DRILLING RIG: FALINGS 1500

BORING No.: BPOW 1-2
 DATE: 11/4/03
 GEOLOGIST: Conti
 DRILLER: BLENINGS

Sample No. and Type or RQD	Depth (Ft.) or Run No.	Blows / 6" or RQD (%)	Sample Recovery / Sample Length	Lithology Change (Depth/FL) or Screened Interval	MATERIAL DESCRIPTION		U S C S *	Remarks	PID/FID Reading (ppm)				
					Soil Density/ Consistency or Rock Hardness	Color			Material Classification	Sample	Sampler BZ	Borehole**	Driller BZ**
	250	/											0
		/											
		/											
	260	/											0
		/											
		/											
	270	/											0
		/											
		/											
	280	/											0
		/											
		/											
	290	/											0
		/											
		/											
	300	/											0

* When rock coring, enter rock brokeness.

** Include monitor reading in 6 foot intervals @ borehole. Increase reading frequency if elevated reponse read.

Remarks: _____

Drilling Area Background (ppm): 0

Converted to Well: Yes No

Well I.D. #: BPOW 1-2



Tetra Tech NUS, Inc.

MONITORING WELL DEVELOPMENT RECORD

Well: BPOW1-2 Depth to Bottom (ft.): 335 BGS Responsible Personnel: Conti
 Site: NWIRP Static Water Level Before (ft.): 34.6 BGS Drilling Co.: Uni-Tech
 Date Installed: 11/5/03 Static Water Level After (ft.): _____ Project Name: NWIRP Bethpage-Outpost Wells
 Date Developed: 11/18/03 Screen Length (ft.): 25' Project Number: N4037
 Dev. Method: AIR LIFT/PUMP Specific Capacity: _____
 Pump Type: 3" SUB Casing ID (in.): 3 3/16

HORIGN/LAMORTE

Time	Estimated Flow Rate (GPM)	Cumulative Water Volume (Gal.)	Water Level Readings (Ft. below TOC)	Temperature (Degrees C)	pH	Specific Conductance (Units _____) mS/cm	Turbidity (NTU)	Remarks (odor, color, etc.)
1600	30	1100						INITIAL LOAD (1)
1700	LOAD	(1) LVS INTO	w/ 1100 GALLONS					PIPE AT 235 MINUTE
0915	30	600	83.3	12.46	4.56	.227	630/519	GRAY-TURBID
0935	30	1200	49	12.30	4.63	.090	388/289	" "
1015	27	1600	49.5	12.05	4.61	.085	316/182	" "
1025	LOAD	(2) LVS INTO	w 1600 GAL - START INTO					(270)
1045	30	600	48.5	12.50	4.68	.083	350/190	" "
1105	27.5	1100	47.5	11.79	4.73	.079	232/133	" "
1120	LOAD	(3) LVS INTO	w/ 1100 GAL - START INTO					(380)
1140	30	600	46	12.08	4.75	.080	321/134	GRAY/SL TURBID
1200	30	1200	46.5	12.25	4.74	.080	216/98	" "
1220	27	1600	46.5	12.05	4.75	.078	232/90	" "
1300	LOAD	(4) LVS INTO	w/ 1600 GAL - START INTO					LOW FR PIPE TO 5' FROM BOTTOM 330' + SURGE
1320	30	600	44.0	12.52	4.71	.083	310/157	GRAY-SL TURBID
1340	27.5	1100	44.6	12.60	4.73	.080	306/90	
1400	LOAD	(5) LVS INTO	w/ 1100 GAL - START INTO					(650)
1420	30	600	42.7	12.56	4.71	.080	308/116	GRAY-SL TURBID

11/18

11/19



Tetra Tech NUS, Inc.

MONITORING WELL DEVELOPMENT RECORD

Well: BPOW1-2 Depth to Bottom (ft.): 335 B/F Responsible Personnel: Conti
 Site: NWIRP Static Water Level Before (ft.): 34.6 Drilling Co.: Uni-Tech
 Date Installed: 11/5/03 Static Water Level After (ft.): 25' Project Name: NWIRP Bethpage-Outpost Wells
 Date Developed: 11/18 Screen Length (ft.): 25' Project Number: N4037
 Dev. Method: AIR LIFT/PUMP Specific Capacity: _____
 Pump Type: 3" SUB. Casing ID (in.): 3 3/16"

HOPKINSON/LANDJIE

Time	Estimated Flow Rate (GPM)	Cumulative Water Volume (Gal.)	Water Level Readings (Ft. below TOC) BGS	Temperature (Degrees C)	pH	Specific Conductance (Units) mS/cm	Turbidity (NTU)	Remarks (odor, color, etc.)
1440	30	1200	42.7	12.42	4.72	.079	202/80	GRAY - SL TURBID
1500	27	1600	42.7	12.15	4.74	.078	184/68	" " "
1530	LOAD	(6) LVS	W/ 1600 GALLONS					(8100) THIS WELL SO FAR.
0810	START	INTO 1400 GALLON TANK						
0830	30	600	42.7	11.62	4.31	.123	215/104	GRAY - SL TURBID
0850	27	1100	42.7	11.34	4.40	.086	156/67	" " "
0850	LOAD	(7) LVS	w/ 1100 GALLONS - START	INTO				(9200)
0910	30	600	42.7	11.56	4.38	.081	160/64	CLEMP SL "
0930	30	1200	42.7	11.73	4.41	.077	146/37	" " "
0950	27.0	1600	42.5	11.53	4.42	.077	134/37	" " "
0950	LOAD	(8) LVS	w/ 1600 GALLONS / START	INTO 1400 GALL TANK				(10,800)
1010	30	600	42.5	11.53	4.42	.079	153/52	" " "
1030	27.5	1100	42.5	11.60	4.42	.078	113/39	" " "
1040	LOAD	(9) LVS	w/ 1100 GALLONS / START	INTO 2000 GALLON				(11,900)
1100	30	600	41.0	11.73	4.45	.079	173/53	" " "
1120	30	1200	41.0	11.54	4.47	.080	121/37	" " "
1140	27.5	1600	41.0	11.54	4.47	.081	85/31	" " "
1225	LOAD	(10) LVS	w/ 1600 GALLONS - START	INTO 1400 GAL				(13,500)

11/19 (Cont)

11/20

8

START PUMPING ON 12/11/03



Tetra Tech NUS, Inc.

MONITORING WELL DEVELOPMENT RECORD

Well: BPOW1-2 Depth to Bottom (ft.): 335' BGS Responsible Personnel: Conti
 Site: NWIRP Static Water Level Before (ft.): 34.6 Drilling Co.: Uni-Tech
 Date Installed: 11/5/03 Static Water Level After (ft.): _____ Project Name: NWIRP Bethpage-Outpost Wells
 Date Developed: 11/18 → 11/20 Screen Length (ft.): 2.5' Project Number: 310-335
 Dev. Method: AIR LIFT/PUMP Specific Capacity: _____
 Pump Type: 3" SUB. Casing ID (in.): 3 13/16"

110828A/LAMOTIE

Time	Estimated Flow Rate (GPM)	Cumulative Water Volume (Gal.)	Water Level Readings (Ft. below TOC)	Temperature (Degrees C)	pH	Specific Conductance (Units mS/cm)	Turbidity (NTU)	Remarks (odor, color, etc.)
1245	30	600	41.0	11.88	4.46	.080	140/43	CLEAR - VSL TURBID 330-335
1305	27.5	1100	41.0	11.82	4.45	.076	131/35	" " " " 325-330
1320	LOAD (11)	475 WY	1100	GALLONS/START INTO 2000				(14,600)
1340	30	600	41.0	11.62	4.41	.076	155/39	" " " " 320-325
1400	30	1200	41.0	11.56	4.43	.075	76/29	" " " " 315-320
1420	27	1600	41.0	11.54	4.43	.074	74/25	" " " " 310-315
	LOAD (12)	175/1600						
		DONE W/		AIR LIFT				(16,200)
1320	START	INTO 1400 GAL						
1340	20	400	37.5	12.16	5.01	.172	99/1057	GRAY - TURBID
1400	20	800	37.5	11.93	5.18	.097	465/373	" " " "
1410	20	1000	37.5	11.59	5.23	.097	362/234	" " " "
1420	18	1100	37.5	11.56	5.24	.090	265/205	" " " "
1430	LOAD	175 W/	1100	GALLONS				
0820	START	INTO	2000	GALLONS				
0840	20	400	37.5	10.50	4.42	.151	456/316	GRAY/TURBID
0900	17.5	700	37.5	11.16	4.63	.083	43/81	CLEAR VSL TURBID
0920	17.0	1000	37.5	11.14	4.60	.082	41/43	CLEAR VSL TURBID

11/20

12

12/1

12/2

DONE W/ PUMP - SAMPLE @ 0930.



APPENDIX C
BPOW1-3 WELL DATA






MONITORING WELL SHEET

PERMIT No:

PROJECT: NWIRP DRILLING Co.: UTD BORING No.: BPOW1-3
 PROJECT No.: N4037 DRILLER: BUEMINGS DATE COMPLETED: 10/29/03
 SITE: BETHPAGE DRILLING METHOD: MUD ROT NORTHING: _____
 GEOLOGIST: CONTI DEV. METHOD: AIR LIFT/PUMP EASTING: _____



Elevation / Depth of Top of Riser: 1

Elevation / Height of Top of Surface Casing: 1

I.D. of Surface Casing: 12" Φ

Type of Surface Casing: STEEL

Type of Surface Seal: CONCRETE PAD 3' x 3' x 6"

I.D. of Riser: 3 13/16"

Type of Riser: SCH 80 PVC

Borehole Diameter: 8"

Type of Backfill: VOLCLAY GROUT

Elevation / Depth of Seal: F. SAND 1359

Type of Seal: NA

Elevation / Depth of Top of Filter Pack: 1364

Elevation / Depth of Top of Screen: 1374

Type of Screen: PVC SCH 80

Slot Size x Length: 10 SL

I.D. of Screen: 3 13/16"

Type of Filter Pack: #1 SILICA SAND

Elevation / Depth of Bottom of Screen: 1419

Elevation / Depth of Bottom of Filter Pack: 1420

Type of Backfill Below Well: SAND

Elevation / Total Depth of Borehole: 1430

374
399
409
419

7 10' BLANK

Not to Scale



BORING LOG

PROJECT NAME: NWIRP Bethpage
 PROJECT NUMBER: N4037
 DRILLING COMPANY: Uni-Tech
 DRILLING RIG: FAILING 1500

BORING No.: BPOW 1-3
 DATE: 10/22/03
 GEOLOGIST: Conti
 DRILLER: BLEMINGS

Sample No. and Type or RQD	Depth (FL) or Run No.	Blows / 6" or RQD (%)	Sample Recovery / Sample Length	Lithology Change (Depth/Ft.) or Screened Interval	MATERIAL DESCRIPTION			U S C S *	Remarks	PID/FID Reading (ppm)			
					Soil Density/ Consistency or Rock Hardness	Color	Material Classification			Sample	Sampler BZ	Borehole**	Driller BZ**
	0	/			LOOSE		SAND AND GRAVEL	SW	NOTE: MOST OF MATL DESC BASED ON CUTTINGS AND FROM GAMMA LOG - A FEW SPOONS WERE TAKEN - FOR CONFIRMATION.				0
		/			TO			GW					
	10	/			DENSE								0
	20	/											0
	30	/					SAND AND GRAVEL	SW					0
		/						GW					
	40	/											0
	50	/											0

* When rock coring, enter rock brokenness.

** Include monitor reading in 6 foot intervals @ borehole. Increase reading frequency if elevated reponse read.

Remarks: 8" Φ MUD ROTARY - NO CASING SET IN THIS HOLE.

Drilling Area Background (ppm): 0

Converted to Well: Yes No Well I.D. #: BPOW 1-3



BORING LOG

PROJECT NAME: NWIRP Bethpage
 PROJECT NUMBER: N4037
 DRILLING COMPANY: Uni-Tech
 DRILLING RIG: FAILING 1500

BORING No.: BPOW1-3
 DATE: 10/22/03
 GEOLOGIST: Conti
 DRILLER: BLEMINGS

Sample No. and Type or RQD	Depth (Fl. or Run No.	Blows / 6" or RQD (%)	Sample Recovery / Sample Length	Lithology Change (Depth/Ft.) or Screened Interval	MATERIAL DESCRIPTION			U S C S *	Remarks	PID/FID Reading (ppm)				
					Soil Density/ Consistency or Rock Hardness	Color	Material Classification			Sample	Sampler BZ	Borehole**	Driller BZ**	
	55						SAND AND GRAVEL							0
	60													0
	1500 70													0
	80						SAND - SOME GRAVEL							0
	1600 90													0
	100													0

* When rock coring, enter rock brokenness.

** Include monitor reading in 6 foot intervals @ borehole. Increase reading frequency if elevated response read.

Remarks: _____

Drilling Area Background (ppm):

Converted to Well: Yes No Well I.D. #: BPOW1-3



BORING LOG

PROJECT NAME: NWIRP Bethpage
 PROJECT NUMBER: N4037
 DRILLING COMPANY: Uni-Tech
 DRILLING RIG: FAILING 1500

BORING No.: BPOW1-3
 DATE: 10/22/03 - 10/23/03
 GEOLOGIST: Conti
 DRILLER: BLEMINGS

Sample No. and Type or RQD	Depth (Ft.) or Run No.	Blows / 6" or RQD (%)	Sample Recovery / Sample Length	Lithology Change (Depth/Ft.) or Screened Interval	MATERIAL DESCRIPTION			U S C S *	Remarks	PID/FID Reading (ppm)			
					Soil Density/ Consistency or Rock Hardness	Color	Material Classification			Sample	Sampler BZ	Borehole**	Driller BZ**
	100	/					SAND - SOME GRAVEL TRACE CLAY	SC SP					0
	110	/											0
	120	/							MORE CLAY				0
	130	51/50	-8/1		V DENSE	BRN	F/C SAND - SOME GRAVEL	SW	WET. 3/4" GRAVEL SUB ROUND				0
	140	/					SOME CLAY		To = 150				0
	150	/											0

10/22
10/23

* When rock coring, enter rock brokenness.

** Include monitor reading in 6 foot intervals @ borehole. Increase reading frequency if elevated response read.

Remarks: _____

Drilling Area Background (ppm):

Converted to Well: Yes No Well I.D. #: BPOW1-3



BORING LOG

PROJECT NAME: NWIRP Bethpage
 PROJECT NUMBER: N4037
 DRILLING COMPANY: Uni-Tech
 DRILLING RIG: FAILING 1500

BORING No.: BPOW1-3
 DATE: 10/23/03
 GEOLOGIST: Conti
 DRILLER: BLEMINGS

Sample No. and Type or RQD	Depth (FT) or Run No.	Blows / 6" or RQD (%)	Sample Recovery / Sample Length	Lithology Change (Depth/FT) or Screened Interval	MATERIAL DESCRIPTION			U S C S *	Remarks	PID/FID Reading (ppm)					
					Soil Density/ Consistency or Rock Hardness	Color	Material Classification			Sample	Sampler BZ	Borehole**	Driller BZ**		
	150	/					SAND - SOME GRAVEL								0
	160	/													0
0940	170	/													0
	180	/					SILTY SAND - SOME GR.								0
	190	/													0
1000	200	/													0

* When rock coring, enter rock brokenness.

** Include monitor reading in 6 foot intervals @ borehole. Increase reading frequency if elevated response read.

Remarks: _____

Drilling Area Background (ppm):

Converted to Well: Yes No Well I.D. #: BPOW1-3



BORING LOG

PROJECT NAME: NWIRP Bethpage
 PROJECT NUMBER: N4037
 DRILLING COMPANY: Uni-Tech
 DRILLING RIG: FAILING 1500

BORING No.: BPOW1-3
 DATE: 10/23/03
 GEOLOGIST: Conti
 DRILLER: BLEMINGS

Sample No. and Type or RQD	Depth (Ft.) or Run No.	Blows / 6" or RQD (%)	Sample Recovery / Sample Length	Lithology Change (Depth/Ft.) or Screened Interval	MATERIAL DESCRIPTION			U S C S *	Remarks	PID/FID Reading (ppm)			
					Soil Density/ Consistency or Rock Hardness	Color	Material Classification			Sample	Sampler BZ	Borehole**	Driller BZ**
	250						SILTY SAND	SM SP					0
	260												0
	270												0
	280						SILTY SAND - TR CLAY	SM SP					0
	290						TO SOME CLAY	SC (CLAYEY SAND)					0
	300												0

* When rock coring, enter rock brokenness.

** Include monitor reading in 6 foot intervals @ borehole. Increase reading frequency if elevated response read.

Remarks: _____

Drilling Area
 Background (ppm):

Converted to Well: Yes No Well I.D. #: BPOW1-3



BORING LOG

PROJECT NAME: NWIRP Bethpage
 PROJECT NUMBER: N4037
 DRILLING COMPANY: Uni-Tech
 DRILLING RIG: FALLING 1500

BORING No.: BPOW1-3
 DATE: 10/23/03
 GEOLOGIST: Conti
 DRILLER: BLEMINGS

Sample No. and Type or RQD	Depth (FL) or Run No.	Blows / 6" or RQD (%)	Sample Recovery / Sample Length	Lithology Change (Depth/FL) or Screened Interval	MATERIAL DESCRIPTION			U S C S *	Remarks	PID/FID Reading (ppm)			
					Soil Density/ Consistency or Rock Hardness	Color	Material Classification			Sample	Sampler BZ	Borehole**	Driller BZ**
	350	/					SILTY F/M SAND TR CLAY	SM SP					0
	360	/											0
	370	/											0
	380	/					SAME AS ABOVE						0
	390	/											0
	400	/											0

* When rock coring, enter rock brokenness.

** Include monitor reading in 6 foot intervals @ borehole. Increase reading frequency if elevated response read.

Remarks: _____

Drilling Area
 Background (ppm):

Converted to Well: Yes No Well I.D. #: BPOW 1-3



BORING LOG

PROJECT NAME: NWIRP Bethpage
 PROJECT NUMBER: N4037
 DRILLING COMPANY: Uni-Tech
 DRILLING RIG: FALLING 1500

BORING No.: BPOW1-3
 DATE: 10/23/03
 GEOLOGIST: Conti
 DRILLER: BLEMINGS

Sample No. and Type or RQD	Depth (Ft.) or Run No.	Blows / 6" or RQD (%)	Sample Recovery / Sample Length	Lithology Change (Depth/Ft.) or Screened Interval	MATERIAL DESCRIPTION			U S C S	Remarks	PID/FID Reading (ppm)			
					Soil Density/ Consistency or Rock Hardness	Color	Material Classification			Sample	Sampler BZ	Borehole**	Driller BZ**
	400						SANDY CLAY	SC	(FROM CUTTINGS AND GAMMA LOG)				0
S-4 e 1545	410 411	51 53	.6/1		V DENSE		SILTY SAND-TR CLAY	SM WET					0
	420						BOTM @ 420 w/ 8" φ						0
							GAMMA LOG TO 419'						
							SET WELL SCR. 374-399 "						
							399-409 BLANK						
							409-419 SCR						

* When rock coring, enter rock brokenness.

** Include monitor reading in 6 foot intervals @ borehole. Increase reading frequency if elevated response read.

Remarks: _____

Drilling Area Background (ppm): 0

Converted to Well: Yes No

Well I.D. #: BPOW1-3



Tetra Tech NUS, Inc.

MONITORING WELL DEVELOPMENT RECORD

Well: BPOW1-3 Depth to Bottom (ft.): 419' BGS Responsible Personnel: Conti
 Site: NWIRP Static Water Level Before (ft.): 33.5 BGS Drilling Co.: Uni-Tech
 Date Installed: 10/29/03 Static Water Level After (ft.): _____ Project Name: NWIRP Bethpage-Outpost Wells
 Date Developed: 11/13 Screen Length (ft.): 40' Project Number: N4037
 Dev. Method: AIR LIFT/PUMP Specific Capacity: _____
 Pump Type: 3" SUBMERSIBLE Casing ID (in.): 3 3/4

374 - 399 - SCR
 399 - 409 - BL
 409 - 419 - SCR

Time	Estimated Flow Rate (GPM)	Cumulative Water Volume (Gal.)	Water Level Readings (Ft. below TEE) BGS	Temperature (Degrees C)	pH	Specific Conductance (Units) mS/cm	Turbidity (NTU) HORSE / LAMORTE	Remarks (odor, color, etc.)
0940	—	—	33.5	—	—	—	—	INITIAL / DEV PIPE @ 280 ±
1010	30	900	42'	11.86	4.43	- 308	999	GRAY TURBID
1035	29'	1600	41.5	11.65	4.34	- 137	999	" "
1040	LOAD	① LVS	w/ 1600 GALLONS	START	START	INTO 1400 GAL		
1100	30	600	38.5	11.83	4.23	- 118	701	" "
1120	27.5	1100	38.5	11.78	4.23	- 107	644	" "
1130	LOAD	② LVS	w/ 1100 GALLONS					
1140	START	INTO	2000 TANK					
1200	40	800	37.5	11.73	4.34	- 105	556/240	" SL TURBID
1220	40	1600	38.0	11.53	4.24	- 102	469/241	" "
1230	LOAD	③ LVS	w/ 1600 GALLONS	START	START	INTO 1400	GALLONS	TANK = 1300 TOTAL
1245	40	600	38.0	11.40	4.18	- 095	496/235	pH paper 4 → 5 Gray SL Turbid
1300	37	1100	38.0	11.34	4.18	- 095	409/183	" " "
1320	LOAD	④ LVS	w/ 1100 GALLONS	START	START	INTO 2000	TANK	check calib
1340	35	700	38	11.29	4.05	- 095	375/196	pH paper 4-5 solution was 3.86
1400	35	1400	38	11.27	4.14	- 145	305/198	GRAY SL TURBID
1415	LOAD	⑤ LVS	w/ 1600 GALLONS	START	START	INTO 1200		
1435	35	700	38	11.00	4.25	- 102	258/168	" "
1450	31	1100	38	10.83	4.16	- 098	292/141	" " "

Recalibrate

(3100)



Tetra Tech NUS, Inc.

MONITORING WELL DEVELOPMENT RECORD

Well: BPOW1-3 Depth to Bottom (ft.): 419' BGS Responsible Personnel: Conti
 Site: NWIRP Static Water Level Before (ft.): 33.5 Drilling Co.: Uni-Tech
 Date Installed: 10/29/03 Static Water Level After (ft.): SEE PG 1 Project Name: NWIRP Bethpage-Outpost Wells
 Date Developed: 11/13 Screen Length (ft.): SEE PG 1 Project Number: N4037
 Dev. Method: AIR LIFT PUMP Specific Capacity: _____
 Pump Type: 3" SUB. Casing ID (in.): 3.716

HORIBA/LAMORTE

Time	Estimated Flow Rate (GPM)	Cumulative Water Volume (Gal.)	Water Level Readings (Ft. below TGG) ± 28' BGS	Temperature (Degrees C)	pH	Specific Conductance (Units) mS/cm	Turbidity (NTU)	Remarks (odor, color, etc.)
1120		START INTO 2000 GALLON						LOWERED
1140	35	700	33.5	11.52	4.15	.141	778	GRAY/TURBID
1200	35	1400	33.5	11.49	4.19	.100	444/245	" SL "
1215	LOAD (7)	LVS w/ 1600 GALLONS	1600 GALLONS (1700)	START INTO 1400 GALLON				
1235	30	600	33.5	11.58	4.26	.100	297/125	GRAY/SL TURBID
1255	27.5	1100	33.5	11.57	4.28	.098	214/87	" "
1305	LOAD (8)	LVS w/ 1100 GALLONS	(START INTO 2000 TANK)					
1325	30	600	33.5	11.43	4.30	.099	207/80	" "
1345	30	1200	33.5	11.42	4.29	.101	148/52	" "
1405	27	1600	33.5	11.33	4.27	.101	138/46	" "
1405	LOAD (9)	LVS w/ 1600 GALLONS	(START INTO 1400 GAL)					
1425	30	600	33.5	11.21	4.11	.108	115/42	" V SL TURBID
1445	27.5	1100	33.5	11.20	4.13	.099	72/34	" "
1500	LOAD (10)	LVS w/ 1100 GALLONS	(START INTO 2000 GALLON)					SURGE WELL.
1520	30	600	33.5	11.15	4.37	.150	149/44	GRAY V SL TURBID
1540	30	1200	33.5	11.20	4.41	.107	53/34	CLEAR " " 419-419
1600	27	1600	33.5	11.18	4.42	.106	51/31	" " " 409-419
1610	LOAD (11)	LVS w/ 1600 GALLONS						

11/17

01

11/17



Tetra Tech NUS, Inc.

MONITORING WELL DEVELOPMENT RECORD

Well: BPOW1-2 Depth to Bottom (ft.): 419' BGS Responsible Personnel: Conti
 Site: NWIRP Static Water Level Before (ft.): 33.5± Drilling Co.: Uni-Tech
 Date Installed: 10/29/03 Static Water Level After (ft.): _____ Project Name: NWIRP Bethpage-Outpost Wells
 Date Developed: 11/13 → 11/18/03 Screen Length (ft.): SEE P-1 Project Number: N4037
 Dev. Method: AIR LIFT / PUMP Specific Capacity: _____
 Pump Type: 3" SUB. Casing ID (in.): 3.375"

HOPKIN/ LAMSTER

Time	Estimated Flow Rate (GPM)	Cumulative Water Volume (Gal.)	Water Level Readings (Ft. below TGG) BGS	Temperature (Degrees C)	pH	Specific Conductance (Units mS/cm)	Turbidity (NTU)	Remarks (odor, color, etc.)
0925	START	INTO	1400 GALLON TANK					
0945	30	600	33.5	11.42	4.44	.106	58/27	CLEAR V.S.L. TURBID 374-379
1005	27.5	1100	33.5	11.39	4.44	.106	33/19	" " " 389-394
1015	LOAD	1200	W/ 1100 GALLONS	START IN TO 2000				
1035	30	600	33.5	11.36	4.40	.104	46/26	" " " 384-389
1055	30	1200	33.5	11.32	4.41	.109	25/22	" " " 379-394
1115	27	1600	33.5	11.35	4.42	.106	25/21	" " " 374-379
	LOAD	1300	W/ 1600 GALLONS	(DUNE AIR LIFT)				
0940	START	INTO	2000 GALLON / PUMP W	1000	1000	AIR LIFT		
1000	20	400	35.0	11-01	4.64	.100	999/1053	WL 33.5± INTANK
1020	17.5	700	35.0	11.19	4.64	.096	222/285	GRAY / TURBID (1400)
	LOAD	LVS	W/ 1700 GALLONS					(1700)
1120	START	INTO	2000 GALLON					
1140	20	400	35.0	11.27	4.75	.096	287/302	GRAY TURBID
1200	17.5	700	35.0	11.38	4.67	.097	36/64	CLEAR / SL TURBID
1220	15	900	35.0	11.37	4.65	.094	4/45	"
	LOAD	W/ PUMP	TOOK SAMPLE @ 1230					

11/18

W
N

12/2

AQUA TERRA GEOPHYSICS INC

AS PER DB ON
10/24/03:

- 1-1 196-231 SC
- 231-236 BL
- 236-241 SC


- 1-2 310-335

- 1-3 374-399 SC
- 399-409 BL
- 409-419 SC


CO		COMPANY		UNI TECH DRILLING	
WELL		WELL ID		BROW L-3	
FLD		FIELD		NWIRP BETHPAGE	
CTY		COUNTRY		STATE	
STE		LOCATION		OTHER SERVICES	
FILING No		SEC		TWP	
PERMANENT DATUM		ELEVATION		R.F.E	
LOG MEAS. FROM		GROUND SURFACE		ABOVE PERM. DATUM	
DRILLING MEAS. FROM		DATE		OCTOBER 25, 2003	
DATE		TYPE LOG		TYPE LOG IN HOLE	
RDN No		DEPTH-DRILLER		SALINITY	
TYPE LOG		DEPTH-LOGGER		DENSITY	
DEPTH-DRILLER		BTM LOGGED INTERVAL		LEVEL	
DEPTH-LOGGER		TOP LOGGED INTERVAL		MAX. REC. TEMP.	
BTM LOGGED INTERVAL		OPERATING HOURS TIME		RECORDED BY	
TOP LOGGED INTERVAL		RECORDED BY		BENJAMIN RICE	
OPERATING HOURS TIME		WITNESSED BY		STEAN CONTI	
WITNESSED BY		BOREHOLE RECORD		CASING RECORD	
RDN No		RINCH		SIZE	
BOREHOLE RECORD		FROM		WEIGHT	
RINCH		TO		FROM	
GROUND SURFACE		TOTAL DEPTH		TO	


Natural Gamma Log: Down Run

Natural Gamma Log: Up Run





50
60
70
80
90
100
110
120





270
280
290
300
310
320
330
340
350
360





APPENDIX D
BPOW2-1 WELL DATA






MONITORING WELL SHEET

PERMIT No:

PROJECT: NWIRP DRILLING Co.: UNITECH BORING No.: BPOW2-1
 PROJECT No.: N4037 DRILLER: EVANS DATE COMPLETED: 8/28/03
 SITE: BPOW2 DRILLING METHOD: MUD ROT NORTHING: _____
 GEOLOGIST: CONTI DEV. METHOD: AIR LIFT/PUMP EASTING: _____





BORING LOG

PROJECT NAME: NWIRP Bethpage
 PROJECT NUMBER: N4037
 DRILLING COMPANY: Uni-Tech
 DRILLING RIG: FAILING 1500

BORING No.: BPOW 2-1
 DATE: 8/25/03
 GEOLOGIST: Conti
 DRILLER: EVANS

Sample No. and Type or RQD	Depth (Ft.) or Run No.	Blows / 6" or RQD (%)	Sample Recovery / Sample Length	Lithology Change (Depth/Ft.) or Screened Interval	MATERIAL DESCRIPTION			U S C S *	Remarks	PID/FID Reading (ppm)									
					Soil Density/ Consistency or Rock Hardness	Color	Material Classification			Sample	Sampler BZ	Borehole**	Driller BZ**						
1630	0	/																	
		/								SEE LOG 2-2 AND GAMMA LOG FOR MORE DETAIL									
	10	/								SAND & GRAVEL	GW								0
	20	/																	0
	30	/								SAME		1/2" Ø GRAVEL							0
	40	/																	0
1730	50	/																	0

* When rock coring, enter rock brokenness.

** Include monitor reading in 6 foot intervals @ borehole. Increase reading frequency if elevated response read.

Remarks: 8" Ø MUD ROTARY - INITIALLY

Drilling Area
 Background (ppm): 0

Converted to Well: Yes No Well I.D. #: BPOW 2-1



BORING LOG

PROJECT NAME: NWIRP Bethpage
 PROJECT NUMBER: N4037
 DRILLING COMPANY: Uni-Tech
 DRILLING RIG: FAILING 1500

BORING No.: BPOW2-1
 DATE: 8/26/03
 GEOLOGIST: Conti
 DRILLER: EVANS

Sample No. and Type or RQD	Depth (Ft.) or Run No.	Blows / 6" or RQD (%)	Sample Recovery / Sample Length	Lithology Change (Depth/Ft.) or Screened Interval	MATERIAL DESCRIPTION			U S C S *	Remarks	PID/FID Reading (ppm)			
					Soil Density/ Consistency or Rock Hardness	Color	Material Classification			Sample	Sampler BZ	Borehole**	Driller BZ**
	50	/					SAND AND GRAVEL	GW					0
	60	/											0
	70	/					SAND - SOME GRAVEL	(FROM CUTTINGS)					0
		/					SOME CLAY	GW SC?					
	80	/											0
	90	/											0
	100	/											

* When rock coring, enter rock brokenness.

** Include monitor reading in 6 foot intervals @ borehole. Increase reading frequency if elevated response read.

Remarks: _____

Drilling Area
 Background (ppm): 0

Converted to Well: Yes No

Well I.D. #: BPOW2-1



BORING LOG

PROJECT NAME: NWIRP Bethpage
 PROJECT NUMBER: N4037
 DRILLING COMPANY: Uni-Tech
 DRILLING RIG: FBIUNG 1500

BORING No.: BPOW
 DATE: 8/26/03
 GEOLOGIST: Conti
 DRILLER: EVANS

Sample No. and Type or RQD	Depth (Ft.) or Run No.	Blows / 6" or RQD (%)	Sample Recovery / Sample Length	Lithology Change (Depth/Ft.) or Screened Interval	MATERIAL DESCRIPTION			U S C S *	Remarks	PID/FID Reading (ppm)									
					Soil Density/ Consistency or Rock Hardness	Color	Material Classification			Sample	Sampler BZ	Borehole**	Driller BZ**						
	100	/																	
		/					SILTY SAND-TRF GRAVEL												
		/																	
1035 ±	110	/																	
		/																	
	120	/																	
		/																	
	130	/					SILTY SAND-SOME CLAY	SC / SM											
		/																	
	140	/																	
		/																	
1100	150	/					SAME	SC / SM											

* When rock coring, enter rock brokenness.

** Include monitor reading in 6 foot intervals @ borehole. Increase reading frequency if elevated response read.

Remarks: _____

Drilling Area Background (ppm):

Converted to Well: Yes No

Well I.D. #: BPOW2-1



BORING LOG

PROJECT NAME: NWIRP Bethpage
 PROJECT NUMBER: N4037
 DRILLING COMPANY: Uni-Tech
 DRILLING RIG: FAILING 1500

BORING No.: BPOW2-1
 DATE: 8/26/03
 GEOLOGIST: Conti
 DRILLER: EVANS

Sample No. and Type or RQD	Depth (FL) or Run No.	Blows / 6" or RQD (%)	Sample Recovery / Sample Length	Lithology Change (Depth/FL) or Screened Interval	MATERIAL DESCRIPTION			U S C S *	Remarks	PID/FID Reading (ppm)			
					Soil Density/ Consistency or Rock Hardness	Color	Material Classification			Sample	Sampler BZ	Borehole**	Driller BZ**
	150	/				TAN BRN	SILTY SAND-TR CLAY	SM					0
	160	/											0
	170	/											0
	180	/					SILTY SAND	SM					0
	190	/											0
	200	/											0

* When rock coring, enter rock brokenness.

** Include monitor reading in 6 foot intervals @ borehole. Increase reading frequency if elevated response read.

Remarks: _____

Drilling Area Background (ppm):

Converted to Well: Yes No Well I.D. #: BPOW 2-1



BORING LOG

PROJECT NAME: NWIRP Bethpage
 PROJECT NUMBER: N4037
 DRILLING COMPANY: Uni-Tech
 DRILLING RIG: FALLING 1500

BORING No.: BPOW2-1
 DATE: 8/26/03
 GEOLOGIST: Conti
 DRILLER: EVANS

Sample No. and Type or RQD	Depth (Ft.) or Run No.	Blows / 6" or RQD (%)	Sample Recovery / Sample Length	Lithology Change (Depth/Ft.) or Screened Interval	MATERIAL DESCRIPTION			U S C S *	Remarks	PID/FID Reading (ppm)									
					Soil Density/ Consistency or Rock Hardness	Color	Material Classification			Sample	Sampler BZ	Borehole**	Driller BZ**						
	200																		
						GRAY	SANDY CLAY	SC	(FROM CUTTINGS)										0
	210					GRAY	SILTY SAND	SM											0
	1215 220						SAME												0
	230																		0
	240																		0
	1230 250						SAME												0

* When rock coring, enter rock brokenness.

** Include monitor reading in 6 foot intervals @ borehole. Increase reading frequency if elevated response read.

Remarks: _____

Drilling Area
 Background (ppm):

Converted to Well: Yes No Well I.D. #: BPOW2-1



BORING LOG

PROJECT NAME: NWIRP Bethpage
 PROJECT NUMBER: N4037
 DRILLING COMPANY: Uni-Tech
 DRILLING RIG: FALING 1500

BORING No.: BPOW 2-1
 DATE: 8/26/03
 GEOLOGIST: Conti
 DRILLER: EVANS

Sample No. and Type or RQD	Depth (Ft.) or Run No.	Blows / 6" or RQD (%)	Sample Recovery / Sample Length	Lithology Change (Depth/FL) or Screened Interval	MATERIAL DESCRIPTION			U S C S .	Remarks	PID/FID Reading (ppm)									
					Soil Density/ Consistency or Rock Hardness	Color	Material Classification			Sample	Sampler BZ	Borehole**	Driller BZ**						
	250																		
							GRAY SILTY SAND	SM SP											
	260																		
	1245 270						SAME.												
	280																		
	290						MORE CLAY NOTICED SANDY CLAY	SC											
	1310 300																		

* When rock coring, enter rock brokenness.

** Include monitor reading in 6 foot intervals @ borehole. Increase reading frequency if elevated response read.

Remarks: _____

Drilling Area Background (ppm):

Converted to Well: Yes No Well I.D. #: BPOW 2-1



BORING LOG

PROJECT NAME: NWIRP Bethpage
 PROJECT NUMBER: N4037
 DRILLING COMPANY: Uni-Tech
 DRILLING RIG: FALING 1500

BORING No.: BPOW 2-1
 DATE: 8/26/03
 GEOLOGIST: Conti
 DRILLER: EVANS

Sample No. and Type or RQD	Depth (FT) or Run No.	Blows / 6" or RQD (%)	Sample Recovery / Sample Length	Lithology Change (Depth/FT) or Screened Interval	MATERIAL DESCRIPTION			U S C S *	Remarks	PID/FID Reading (ppm)												
					Soil Density/ Consistency or Rock Hardness	Color	Material Classification			Sample	Sampler BZ	Borehole**	Driller BZ**									
	300																					
							SANDY CLAY															
	1400 310																					
	320						SILTY SAND	SP SM														
	330																					
	340						SAME															
	1530 350																					

* When rock coring, enter rock brokenness.

** Include monitor reading in 6 foot intervals @ borehole. Increase reading frequency if elevated response read.

Remarks: _____

Drilling Area Background (ppm):

Converted to Well: Yes No

Well I.D. #: BPOW 2-1



BORING LOG

PROJECT NAME: NWIRP Bethpage
 PROJECT NUMBER: N4037
 DRILLING COMPANY: Uni-Tech
 DRILLING RIG: FALLING 1500

BORING No.: BPOW
 DATE: 8/27/03
 GEOLOGIST: Conti
 DRILLER: EVANS

Sample No. and Type or RQD	Depth (Ft.) or Run No.	Blows / 6" or RQD (%)	Sample Recovery / Sample Length	Lithology Change (Depth/Ft.) or Screened Interval	MATERIAL DESCRIPTION			U S C S .	Remarks	PID/FID Reading (ppm)									
					Soil Density/ Consistency or Rock Hardness	Color	Material Classification			Sample	Sampler BZ	Borehole**	Driller BZ**						
	350																		
							SILTY SAND	SM SP											0
	360			360															0
				365															
	370						MORE CLAY												0
				375															
	380										SET WELL								0
											360 → 400								0
											W/ BLANK SECTION FROM 365 → 375								
											C SAND TO 350								
											F SAND TO 345								
	390																		0
											DRILLED 8" TO								
											410								
	400																		0

* When rock coring, enter rock brokenness.

** Include monitor reading in 6 foot intervals @ borehole. Increase reading frequency if elevated response read.

Remarks: _____

Drilling Area
 Background (ppm):

Converted to Well: Yes No Well I.D. #: BPOW 2-1



Tetra Tech NUS, Inc.

MONITORING WELL DEVELOPMENT RECORD

Well: BROW 2-1 Depth to Bottom (ft.): 400 BGS Responsible Personnel: Conti
 Site: NWIRP Static Water Level Before (ft.): 11.0' ± Drilling Co.: Uni-Tech
 Date Installed: 8/28/03 Static Water Level After (ft.): _____ Project Name: NWIRP Bethpage-Outpost Wells
 Date Developed: 9/15/03 Screen Length (ft.): 40' - 10' BLANK Project Number: N4037
 Dev. Method: AIR LIFT / PUMP Specific Capacity: _____
 Pump Type: _____ Casing ID (in.): 3 3/16 U-22 2020 360-400
 HORIBA/LAMORTE 365-375 (BLANK)

Time	Estimated Flow Rate (GPM)	Cumulative Water Volume (Gal.)	Water Level Readings (Ft. below FEET)	Temperature (Degrees C)	pH	Specific Conductance (Units mS/cm)	Turbidity (NTU)	Remarks (odor, color, etc.)
0955	START	AIR LIFT	INTO 1800 GALLON TANK					
1015	20	400	28.00	13.66	4.81	.173	999	GRAY - TURBID RODS @ 250' ± GRAY AND TURBID
1035	20	800	27.50	14.20	4.94	.125	999	" " "
1055	20	1200	27.00	13.89	4.95	.115	999	" " "
1115	20	1600	27.00	14.15	4.95	.117	999	" " "
9/5*	LOAD	(1) WLS	(1600)					→ CLEAR / NON TURBID.
1030	INITIAL WLS		24.00	LOAD (2)	WLS	(1600)		LOWER RODS TO ~ 340' THEN SURGE
1235	START	AIR LIFT	INTO 1400 GALLON TANK					
1255	25	500	26.00	13.62	5.60	.141	349/21	CLEAR
1315	25	1000	26.00	13.52	5.67	.121	395/12	" SURGE
1320	LOAD	(3) DOME	(1100) = 4300					
1320	START	INTO 1800 GALLON TANK						
1340	30	600	26.00	13.59	5.62	.119	384/9	CLEAR
1400	30	1200	25.50	13.55	5.63	.119	390/8	" 5900
1420	27	1600	25.50	13.56	5.62	.120	388/9	" LOAD (4) WLS (1600)
1420	START	INTO 1800 GALLON						SURGE
1440	25	500	25.50	13.45	5.52	.114	308/7	"
1500	27.5	1100	25.50	13.69	5.50	.112	274/5	" LOAD (5) WLS (1100) = 7000

47



Tetra Tech NUS, Inc.

MONITORING WELL DEVELOPMENT RECORD

Well: BPOVJ2 - 1 Depth to Bottom (ft.): 400 BGS Responsible Personnel: Conti
 Site: NWIRP Static Water Level Before (ft.): _____ Drilling Co.: Uni-Tech
 Date Installed: 8/28/03 Static Water Level After (ft.): _____ Project Name: NWIRP Bethpage-Outpost Wells
 Date Developed: 9/15/03 Screen Length (ft.): 40 - 10' BLANK Project Number: N4037
 Dev. Method: AIR LIFT / PUMP Specific Capacity: _____
 Pump Type: _____ Casing ID (in.): 3 13/16

U-22
HORIBA/LAMOTTE

Time	Estimated Flow Rate (GPM)	Cumulative Water Volume (Gal.)	Water Level Readings (Ft. below FE GS)	Temperature (Degrees C)	pH	Specific Conductance (Units mS/cm)	Turbidity (NTU)	Remarks (odor, color, etc.)
1510	START	INTO 1800 GALLON TANK						
1530	30	600	25.50	13.33	5.47	.114	270/5	CLEAR.
1550	30	1200	25.50	13.40	5.45	.112	265/6	"
1610	27	1600	25.50	13.38	5.42	.116	275/5	"
		LOAD (6)	LVS w/1600 GALLONS		(8.00)			THIS WELL SO FAR.
0850	START	INTO 1400 GALLON TANK						LOWER RODS TO BOTM/SURGE
0910	30	600	27.00	13.08	4.51	.198	372/54	CLEAR - SL TURBID 25.70 SWL
0930	27.5	1100	27.00	13.00	4.74	.092	298/26	" NON TURBID
0950	27	1600	27.00	12.94	4.73	.089	134/15	" "
		LOAD (7)	LVS w/1600 GALLONS		10.200	1050		SURGE WELL.
1000	START	INTO 1400 GALLON TANK						
1020	25	500	27.00	13.05	4.75	.092	285/43	CLEAR - SL TURBID
1040	25	1000	27.00	13.14	4.70	.091	146/21	" NON "
1050		LOAD (8)	LVS w/1100 GALLONS		11.300			
1050	START	INTO 1800 GALLON						
1110	30	600	27.00	12.96	4.73	.095	198/14	" "
1130	27.5	1100	27.00	12.95	4.74	.093	137/12	" "
1150	27	1600	26.50	13.08	4.76	.092	169/10	" " 395.400

LOAD (9) LVS w/1600 GAL 12,900

9/8

9/9

9/8



Tetra Tech NUS, Inc.

MONITORING WELL DEVELOPMENT RECORD

Well: BPOW 2-1 Depth to Bottom (ft.): 400' BGS Responsible Personnel: Conti
 Site: NW 12P Static Water Level Before (ft.): _____ Drilling Co.: Uni-Tech
 Date Installed: 5/28/03 Static Water Level After (ft.): _____ Project Name: NWIRP Bethpage-Outpost Wells
 Date Developed: 9/15/03 Screen Length (ft.): 40' - 10' BLANK Project Number: N4037
 Dev. Method: AIR LIFT / PUMP Specific Capacity: _____
 Pump Type: GRUNDFOSS SUB. Casing ID (in.): 3 13/16

U22 2020
HORIBA/LAMOTIE

Time	Estimated Flow Rate (GPM)	Cumulative Water Volume (Gal.)	Water Level Readings (Ft. below FEEL GS)	Temperature (Degrees C)	pH	Specific Conductance (Units mS/cm)	Turbidity (NTU)	Remarks (odor, color, etc.)	
1155	START	INTO 1400 GALLON TANK						CLEAR NON TURBID	
1215	30	600	25.00	13.15	4.87	.096	290/12	" " 390-395	
1235	27.5	1100	25.00	12.89	4.83	.093	165/11	" " 385-390	
1240	LOAD	(10) LUS	W/ 1100 GALLONS		14.00	(THIS WELL)			
1240	START	INTO 1800 GALLON TANK							
1300	30	600	25.00	12.96	4.88	.092	160/14	CLEAR NON TURBID 380-385	
1320	27.5	1100	25.00	12.75	4.87	.092	218/12	" " 375-380	
1340	27	1600	25.00	12.72	4.86	.091	160/12	" " 360-365	
	LOAD	(11) LUS	W/ 1600 GALLONS		15.600			(AIR) ↑	
			START @ 800 GALLONS PREVIOUS WELLS					(PUMP) ↓	
1035	START	PUMPING 25.5							
1055	15	300 (1100)	26.0	13.34	5.79	.160	99/993	GRAY/TURBID	
1115	10	200 (1300)	26.0	13.32	5.70	.128	398/36	CLEAR SL TURBID	
1135	15	300 (1600)	26.0	13.35	5.65	.120	216/24	" NON "	
1155	10	200 (1800)	26.0	13.38	5.64	.118	135/14	" "	
			15,600					DONE	
			1000						
			16,600						
			TOTAL THIS WELL.						

APPENDIX E
BPOW2-2 WELL DATA






MONITORING WELL SHEET

PERMIT No:

PROJECT: NWIRP DRILLING Co.: UNITECH BORING No.: BPOW 2-2
 PROJECT No.: N4037 DRILLER: EVANS DATE COMPLETED: 8/20/03
 SITE: BPOW 2 DRILLING METHOD: MUD ROT NORTHING: _____
 GEOLOGIST: CONT1 DEV. METHOD: _____ EASTING: _____



Elevation / Depth of Top of Riser: 1
 Elevation / Height of Top of Surface Casing: 1
 I.D. of Surface Casing: _____
 Type of Surface Casing: STEEL
 Type of Surface Seal: CONCRETE PAD
 I.D. of Riser: 3 13/16"
 Type of Riser: PVC SCH 80
 Borehole Diameter: 8"
 Type of Backfill: VOLCLAY GROUT
 Elevation / Depth of Seal: F SAND #0 1425
 Type of Seal: NA
 Elevation / Depth of Top of Filter Pack:(c) 1435
 Elevation / Depth of Top of Screen: 1455
 Type of Screen: PVC SCH 80
 Slot Size x Length: 10 SL x 40'
 I.D. of Screen: 3 13/16"
 Type of Filter Pack: #1 SILICA SAND
 Elevation / Depth of Bottom of Screen: 1495
 Elevation / Depth of Bottom of Filter Pack: 1496
 Type of Backfill Below Well: SAND
 Elevation / Total Depth of Borehole: 1510



BORING LOG

PROJECT NAME: NWIRP Bethpage
 PROJECT NUMBER: N4037
 DRILLING COMPANY: Uni-Tech
 DRILLING RIG: FALING 1500

BORING No.: BPOW2-2
 DATE: 8/6/03
 GEOLOGIST: Conti
 DRILLER: EVANS

Sample No. and Type or RQD	Depth (FL) or Run No.	Blows / 6" or RQD (%)	Sample Recovery / Sample Length	Lithology Change (Depth/FL) or Screened Interval	MATERIAL DESCRIPTION			U S C S *	Remarks	PID/FID Reading (ppm)			
					Soil Density/Consistency or Rock Hardness	Color	Material Classification			Sample	Sampler BZ	Borehole**	Driller BZ**
8/6 1445	0				DENSE	TAN BRN	GRAVEL AND SAND	GW	SOME 1" SUB ANG/SUB ROUND GRAVEL LOGGED FROM CUTTINGS.				0
	10												0
	1500	20					SAME						0
8/6 8/7 105	40						GRAVEL AND SAND	GW					0
									SET CASING @ 45' - WOULD NOT GO DEEPER - HOLE DEPTH @ 100'				
	50												

* When rock coring, enter rock brokenness.

** Include monitor reading in 6 foot intervals @ borehole. Increase reading frequency if elevated response read.

Remarks: START w/ 8" Ø MUD ROTARY.
CETCO PURE GOLD GEL (DRILLING MUD)
HOPE WAS REAMED TO 12" TO 100' BUT COULD ONLY INSTALL 10" CAS TO 45'

Drilling Area

Background (ppm):

Converted to Well: Yes No

Well I.D. #: BPOW2-2



BORING LOG

PROJECT NAME: NWIRP Bethpage
 PROJECT NUMBER: N4037
 DRILLING COMPANY: Uni-Tech
 DRILLING RIG: FAILING 1500

BORING No.: BPOW 2-2
 DATE: 8/7/03
 GEOLOGIST: Conti
 DRILLER: EVANS

Sample No. and Type or RQD	Depth (FL) or Run No.	Blows / 6" or RQD (%)	Sample Recovery / Sample Length	Lithology Change (Depth/FL) or Screened Interval	MATERIAL DESCRIPTION			U S C S *	Remarks	PID/FID Reading (ppm)				
					Soil Density/ Consistency or Rock Hardness	Color	Material Classification			Sample	Sampler BZ	Borehole**	Driller BZ**	
	50						GRAVEL AND SAND	GW						0
	1030	60												0
	1045	70			DENSE		SAND - SOME GRAVEL		OUT OF F. GRAVEL = 70 TO 80'					0
							TO INTERBEDDED SAND AND CLAYEY SILT							
	1100	80												0
	1115	90					SAND - TR CLAY TO 100'							0
	1130	100												0

* When rock coring, enter rock brokenness.

** Include monitor reading in 6 foot intervals @ borehole. Increase reading frequency if elevated response read.

Remarks: WILL ATTEMPT TO SET CASING (10") @ 100'
BUT ONLY WENT DOWN TO 45 - TRIED TO PULL BUT COULD NOT
RESUME 8" @ THRU CASING ON 8/11/03

Drilling Area

Background (ppm): 0

Converted to Well: Yes No Well I.D. #: BPOW 2-2



BORING LOG

PROJECT NAME: NWIRP Bethpage
 PROJECT NUMBER: N4037
 DRILLING COMPANY: Uni-Tech
 DRILLING RIG: FAILING 1500

BORING No.: BPOW2-2
 DATE: 8/12/03 / 8/13/03 / 8/18/03
 GEOLOGIST: Conti
 DRILLER: EVANS

8/12
8/13
8/18

Sample No. and Type or RQD	Depth (FL) or Run No.	Blows / 6" or RQD (%)	Sample Recovery / Sample Length	Lithology Change (Depth/FL) or Screened Interval	MATERIAL DESCRIPTION			U S C S *	Remarks	PID/FID Reading (ppm)									
					Soil Density/ Consistency or Rock Hardness	Color	Material Classification			Sample	Sampler BZ	Borehole**	Driller BZ**						
	100																		
								SM	LOGGED FROM CUTTINGS.										0
								SP	SET 8"φ TO 105 - THRU 10" - WHICH WAS ONLY SET TO 45 + SEE NB 1360 FOR DETAILS										0
	110																		0
	120								SAND										0
	130																		0
	140								SAND - TR CLAY										0
										NOTED SOME CLAY IN CUTTINGS									
	150								SAND - SOME CLAY										0

* When rock coring, enter rock brokenness.

** Include monitor reading in 6 foot intervals @ borehole. Increase reading frequency if elevated response read.

Remarks: SET/GROUTED 8"φ CAS TO 105' ON 8/12/03

Drilling Area Background (ppm):

Converted to Well: Yes No Well I.D. #: BPOW2-2



BORING LOG

PROJECT NAME: NWIRP Bethpage
 PROJECT NUMBER: N4037
 DRILLING COMPANY: Uni-Tech
 DRILLING RIG: FAILING 1500

BORING No.: BPOW2-2
 DATE: 8/18/03
 GEOLOGIST: Conti
 DRILLER: EVANS

Sample No. and Type or RQD	Depth (Ft.) or Run No.	Blows / 6" or RQD (%)	Sample Recovery / Sample Length	Lithology Change (Depth/Ft.) or Screened Interval	MATERIAL DESCRIPTION			U S C S *	Remarks	PID/FID Reading (ppm)								
					Soil Density/ Consistency or Rock Hardness	Color	Material Classification			Sample	Sampler BZ	Borehole**	Driller BZ**					
	150																	
S-1 e 1140	151	38 50/6	1/1		V DENSE	ORANG BRN	F/M SAND -TR GRAY CLAY IN "WASH" PORTION	SP	WET GOOD RECOVERY	0			0					
	1230	160																0
	1300	170																0
	1400	180					SAND F/M	SP										0
	1430	190																0
	1500	200					SAND - TR CLAY											0

* When rock coring, enter rock brokenness.

** Include monitor reading in 6 foot intervals @ borehole. Increase reading frequency if elevated response read.

Remarks: _____

Drilling Area Background (ppm):

Converted to Well: Yes No Well I.D. #: BPOW2-2



BORING LOG

PROJECT NAME: NWIRP Bethpage
 PROJECT NUMBER: N4037
 DRILLING COMPANY: Uni-Tech
 DRILLING RIG: FALLING 1500

BORING No.: BPOW 2-2
 DATE: 8/18/03
 GEOLOGIST: Conti
 DRILLER: EVANS

Sample No. and Type or RQD	Depth (FL) or Run No.	Blows / 6" or RQD (%)	Sample Recovery / Sample Length	Lithology Change (Depth/FL) or Screened Interval	MATERIAL DESCRIPTION			U S C S *	Remarks	PID/FID Reading (ppm)				
					Soil Density/ Consistency or Rock Hardness	Color	Material Classification			Sample	Sampler BZ	Borehole**	Driller BZ**	
	200				DENSE		SAND F/M							0
	1530	210					SILTY SAND-TR CLAY							0
	220													0
	1545	230					SAND (SILTY)	SM SP	(FROM CUTTINGS)					0
	240													0
	1600	250												0

* When rock coring, enter rock brokenness.

** Include monitor reading in 6 foot intervals @ borehole. Increase reading frequency if elevated response read.

Remarks: _____

Drilling Area
 Background (ppm):

Converted to Well: Yes No Well I.D. #: BPOW 2-2



BORING LOG

PROJECT NAME: NWIRP Bethpage
 PROJECT NUMBER: N4037
 DRILLING COMPANY: Uni-Tech
 DRILLING RIG: FALLING 1500

BORING No.: BPOW 2-2
 DATE: 8/19/03
 GEOLOGIST: Conti
 DRILLER: EVANS

Sample No. and Type or RQD	Depth (FT.) or Run No.	Blows / 6" or RQD (%)	Sample Recovery / Sample Length	Lithology Change (Depth/FT.) or Screened Interval	MATERIAL DESCRIPTION			U S C S *	Remarks	PID/FID Reading (ppm)			
					Soil Density/ Consistency or Rock Hardness	Color	Material Classification			Sample	Sampler BZ	Borehole**	Driller BZ**
S-2 C 1050	250	30 50/1	0.6/1		✓ DENSE	YELLOW BRN	SILTY F/M SAND	SM /SP	WET MICAEOUS				0
	260												0
	270						SILTY F/M SAND						0
1115	280												0
	290						SAME, - MORE CLAY NOTICED						0
1145	300												0

* When rock coring, enter rock brokenness.

** Include monitor reading in 6 foot intervals @ borehole. Increase reading frequency if elevated response read.

Remarks: _____

Drilling Area
 Background (ppm):

Converted to Well: Yes No Well I.D. #: BPOW 2-2



BORING LOG

PROJECT NAME: NWIRP Bethpage
 PROJECT NUMBER: N4037
 DRILLING COMPANY: Uni-Tech
 DRILLING RIG: FAILING 1500

BORING No.: BPOW 2-2
 DATE: 8/19/03
 GEOLOGIST: Conti
 DRILLER: EVANS

Sample No. and Type or RQD	Depth (Ft.) or Run No.	Blows / 6" or RQD (%)	Sample Recovery / Sample Length	Lithology Change (Depth/Ft.) or Screened Interval	MATERIAL DESCRIPTION			U S C S *	Remarks	PID/FID Reading (ppm)										
					Soil Density/ Consistency/ or Rock Hardness	Color	Material Classification			Sample	Sampler BZ	Borehole**	Driller BZ**							
	300	/																		
		/					SILTY SAND													0
	310	/																		0
	1215 320	/					SAME		LESS CLAY											0
	330	/																		0
	340	/					SAME		TR OF CLAY											0
	1230 350	/																		0

* When rock coring, enter rock brokenness.

** Include monitor reading in 6 foot intervals @ borehole. Increase reading frequency if elevated response read.

Remarks: _____

Drilling Area
 Background (ppm):

Converted to Well: Yes No Well I.D. #: BPOW 2-2



BORING LOG

PROJECT NAME: NWIRP Bethpage
 PROJECT NUMBER: N4037
 DRILLING COMPANY: Uni-Tech
 DRILLING RIG: FAILING 1500

BORING No.: BPOW 2-2
 DATE: 8/19/03
 GEOLOGIST: Conti
 DRILLER: EVANS

Sample No. and Type or RQD	Depth (Ft.) or Run No.	Blows / 6" or RQD (%)	Sample Recovery / Sample Length	Lithology Change (Depth/Fl.) or Screened Interval	MATERIAL DESCRIPTION			U S C S *	Remarks	PID/FID Reading (ppm)									
					Soil Density/ Consistency or Rock Hardness	Color	Material Classification			Sample	Sampler BZ	Borehole**	Driller BZ**						
	350																		
S3 e 1230		36 50	1/1		DENSE	GRAY BON	SILTY SAND - TR CLAY	SM SP	WET										
	360																		
	1330	370					SAND - TR CLAY												
	380																		
	1430	390					SAND	SM SP											
	400																		

* When rock coring, enter rock brokenness.

** Include monitor reading in 6 foot intervals @ borehole. Increase reading frequency if elevated response read.

Remarks: _____

Drilling Area
 Background (ppm):

Converted to Well: Yes No Well I.D. #: BPOW 2-2



BORING LOG

PROJECT NAME: NWIRP Bethpage
 PROJECT NUMBER: N4037
 DRILLING COMPANY: Uni-Tech
 DRILLING RIG: FALING

BORING No.: BPOW2-2
 DATE: 8/19/03
 GEOLOGIST: Conti
 DRILLER: EVANS

Sample No. and Type or RQD	Depth (Fl.) or Run No.	Blows / 6" or RQD (%)	Sample Recovery / Sample Length	Lithology Change (Depth/Ft.) or Screened Interval	MATERIAL DESCRIPTION			U S C S *	Remarks	PID/FID Reading (ppm)						
					Soil Density/ Consistency or Rock Hardness	Color	Material Classification			Sample	Sampler BZ	Borehole**	Driller BZ**			
	400	/					SILTY F/M SAND								0	
	150 410	/														0
	420	/					SAME									0
	1530 430	/														0
	440	/					SAME. W/ TR CLAY.									0
	1600 450	/														0

* When rock coring, enter rock brokenness.

** Include monitor reading in 6 foot intervals @ borehole. Increase reading frequency if elevated response read.

Remarks: _____

Drilling Area
 Background (ppm):

Converted to Well: Yes No Well I.D. #: BPOW2-2



BORING LOG

PROJECT NAME: NWIRP Bethpage
 PROJECT NUMBER: N4037
 DRILLING COMPANY: Uni-Tech
 DRILLING RIG: FAILING 1500

BORING No.: BPOW 2-2
 DATE: 8-19-03
 GEOLOGIST: Conti
 DRILLER: EVANS

Sample No. and Type or RQD	Depth (FL) or Run No.	Blows / 6" or RQD (%)	Sample Recovery / Sample Length	Lithology Change (Depth/FL) or Screened Interval	MATERIAL DESCRIPTION			U S C S *	Remarks	PID/FID Reading (ppm)				
					Soil Density/ Consistency or Rock Hardness	Color	Material Classification			Sample	Sampler BZ	Borehole**	Driller BZ**	
SA 1600	450	36/50	1/1		V. DENSE	BLK GRAY	CLAYEY SAND (LAMINATED)	SC	WET					0
	460						SILTY SAND		LESS CLAY AT 455±					0
	470								476 (PROPOSED)					0
	480						SAND							0
	490								SET WELL ON 8/29/03 SCREEN 455-495 SAND(C) 435-446 SAND(F) 425-435					
	500						SAND - TR CLAY		≈ 495 - STOP, HERE = 40 BELOW 455					

* When rock coring, enter rock brokenness.

** Include monitor reading in 6 foot intervals @ borehole. Increase reading frequency if elevated response read.

Remarks: _____

Drilling Area
 Background (ppm):

Converted to Well: Yes No Well I.D. #: BPOW 2-2



Tetra Tech NUS, Inc.

MONITORING WELL DEVELOPMENT RECORD

Well: BPOW 2 - 2 Depth to Bottom (ft.): 495 (GS) Responsible Personnel: Conti
 Site: NWIRP - BPOW 2 Static Water Level Before (ft.): 22'(GS) Drilling Co.: Uni-Tech
 Date Installed: 8/20/03 Static Water Level After (ft.): _____ Project Name: NWIRP Bethpage-Outpost Wells
 Date Developed: 9-3-03 → Screen Length (ft.): 40' Project Number: N4037
 Dev. Method: AIR LIFT/PUMP Specific Capacity: _____
 Pump Type: _____ Casing ID (in.): 3 1/2

HORIZA/LAMOTE

Time	Estimated Flow Rate (GPM)	Cumulative Water Volume (Gal.)	Water Level Readings (Ft. below TOE) GS.	Temperature (Degrees C)	pH	Specific Conductance (Units mS/cm)	Turbidity (NTU)	Remarks (odor, color, etc.)
0915	--	--	22.00	--	--	--	--	INITIAL
0945	23	700	31.00	13.69	4.68	.255	999	PACKER @ 300' ± GRAY-TURBID
1015	20	1200	29.50	13.15	4.89	.132	651/268	
1035	16	(1600)	LOAD (1) LVS					
1040	START	DEV INTO 400	1400 GAL.					
1100	20	800	29.00	13.60	5.00	.118	490/143	GRAY-SL TURBID PACKER @ 320'
1120	20	(1200)	29.00	13.97	5.01	.106	333/75	" " " "
1140	20	2800	29.00	13.80	5.09	.104	266/53	" " " "
1143			LOAD (2) LVS					
1145	START	INTO 1800	GAL					
1205	25	500	29.00	13.77	5.10	.102	360/81	CLEAR SL " " 320' (24)
1225	28.5	900	29.00	--	5.10	.100	290/43	" " " "
1245	20	1200	29.00	13.22	5.14	.099	236/36	" " " "
1303		(1600)	LOAD (3) LVS					
1305	START	INTO 1400	GALLON					
1325	28.5	450	29.00	13.35	5.11	.098	289/54	" " " "
1345	20	800	29.00	13.26	5.11	.098	211/32	" " " "
1405	18	(1100)	29.00	14.00	5.03	.092	154/21	" " " "

LOAD (4) LVS



Tetra Tech NUS, Inc.

MONITORING WELL DEVELOPMENT RECORD

SCREEN 455 → 445

Well: BPOW2-2 Depth to Bottom (ft.): 495' (45) Responsible Personnel: Conti
 Site: NWIRP Static Water Level Before (ft.): 22' Drilling Co.: Uni-Tech
 Date Installed: 8/20/03 Static Water Level After (ft.): _____ Project Name: NWIRP Bethpage-Outpost Wells
 Date Developed: 9/13/03 Screen Length (ft.): 40' Project Number: N4037
 Dev. Method: AIR LIFT / PUMP Specific Capacity: _____
 Pump Type: _____ Casing ID (in.): 3.716

U/22 2020
HOBABA/LAMOTTE

Time	Estimated Flow Rate (GPM)	Cumulative Water Volume (Gal.)	Water Level Readings (Ft. below TOC)	Temperature (Degrees C)	pH	Specific Conductance (Units mS/cm)	Turbidity (NTU)	Remarks (odor, color, etc.)
1430	START	INTO 1800	GALLON	—	—	—	—	LOWER PIPE TO ≈ 470', BGS GRAY/TURBID
1450	25	500	29.00	13.95	5.06	.094	300/53	CLEAR - SL TURBID
1510	28.5	900	29.00	13.78	5.14	.092	218/26	" " "
1530	20	1200	28.00	13.76	5.16	.091	202/21	" "
1550	16	1600	28.00	13.75	5.17	.090	150/16	" "
1551		LOAD (5)	LVS					
1550	START	INTO 1400	GALLON					
1610	20	400	28.00	13.73	5.17	.091	241/27	CLEAR
1630	20	800	28.00	13.20	5.16	.092	258/18	" "
1650	20	1100	28.00	13.70	5.17	.091	264/20	" " (2) LUSE 1700 HRS
0915	START	INTO 1800	23.00	—	—	—	—	
0935	25	500	27.50	15.64	5.13	.135	278/26	" "
0955	22.5	900	27.50	14.95	5.38	.106	281/16	" "
1015	20	1200	27.50	15.44	5.57	.104	262/12	" "
1035	20	1600	27.50	14.25	5.60	.102	270/12	" " LOAD (7) LVS 1035 HRS
1035	START	INTO 1400	GALLON					
1055	25	500	27.50	13.93	5.86	.124	300/17	CLEAR - LOWER PIPE TO BOTTOM
1115	22.5	900	27.50	14.79	5.84	.116	605/99	" " SL TURBID
1130	LOAD (8)	LVS. (10900)		—	—	—	—	

2

9/3 ↑
9/4 ↓



Tetra Tech NUS, Inc.

MONITORING WELL DEVELOPMENT RECORD

Well: BPOW2-2 Depth to Bottom (ft.): 495 345 Responsible Personnel: Conti
 Site: NWIRP Static Water Level Before (ft.): 22' Drilling Co.: Uni-Tech
 Date Installed: 8/20/03 Static Water Level After (ft.): _____ Project Name: NWIRP Bethpage-Outpost Wells
 Date Developed: 9/13/03 → Screen Length (ft.): 40 Project Number: N4037
 Dev. Method: AIR LIFT PUMP Specific Capacity: _____
 Pump Type: _____ Casing ID (in.): 3 13/16

HORIBA/LAMORTE

Time	Estimated Flow Rate (GPM)	Cumulative Water Volume (Gal.)	Water Level Readings (Ft. below TOC)	Temperature (Degrees C)	pH	Specific Conductance (Units mS/cm.)	Turbidity (NTU)	Remarks (odor, color, etc.)
1130	START INTO 1500 GALLON							
1150	20	400	27.50	13.93	5.83	.117	457/61	CLEAR - SL TURBID
1210	22.5	900	27.50	13.51	5.87	.117	316/16	" NOT "
1230	20	1200	27.50	13.67	5.88	.112	356/11	" " "
1250	20	1600	27.50	13.66	5.87	.121	335/10	LOAD (3) LVS (SURGE)
1300	START INTO 1400 GALLON							
1320	20	400	27.50	13.60	5.82	.110	328/47	CLEAR V SL TURBID
1340	20	800	27.50	13.63	5.83	.108	219/13	" NON TURBID
1400	18.3	1100	27.50	13.65	5.84	.107	216/11	" " " (10) LVS
1400	START INTO 1800 GALLON							
1420	20	400	27.0	14.29	5.84	.102	199/15	CLEAR
1440	20	800	27.0	13.97	5.77	.106	353/8	"
1500	20	1200	27.0	13.93	5.78	.105	287/6	"
1510	20	1400	27.0	13.94	5.77	.104	276/6	"
1520	20	1600	27.0	13.97	5.79	.105	290/7	"
			LOAD (1) LAST LOAD.					COMPLETE
			15,200	TOTAL				

SCREEN INT
 495-490
 490-485
 480-485
 475-486
 470-475
 465-470
 460-465
 455-460



Tetra Tech NUS, Inc.

MONITORING WELL DEVELOPMENT RECORD

Well: BROW2-2 Depth to Bottom (ft.): 495.6s Responsible Personnel: Conti
 Site: NWIRP Static Water Level Before (ft.): 23.8 Gs Drilling Co.: Uni-Tech
 Date Installed: 8/20/03 Static Water Level After (ft.): _____ Project Name: NWIRP Bethpage-Outpost Wells
 Date Developed: 1/10/03 Screen Length (ft.): 40' Project Number: N4037
 Dev. Method: PUMP Specific Capacity: _____
 Pump Type: GRUNDFOS SUB Casing ID (in.): 3 3/4


HORIBA/LAMORTE

Time	Estimated Flow Rate (GPM)	Cumulative Water Volume (Gal.)	Water Level Readings (Ft. below TOC)	Temperature (Degrees C)	pH	Specific Conductance (Units _____) mS/cm	Turbidity (NTU)	Remarks (odor, color, etc.)
0930	START PUMPING.		IN 1800 GALLON TANK					
0950	15	300	25.3	13.21	5.59	.165	456/153	GRAY/TURBID
1010	15	600	25.3	13.25	5.63	.126	264/38	CLEAR/ V.SL TURBID
1030	13.3	800	25.3	13.20	5.70	.118	250/18	" NON TURBID
				15,200				DONE PUMPING.
				800				
				14,000	BROW2-2			

AQUA TERRA GEOPHYSICS INC

CO		WELL		FLD		CTY		STE		FILING No	
PERMANENT DATUM		COMPANY		UNI TECH DRILLING		WELL ID		BPOW 2 - 2		ELEVATION	
LOG MEAS FROM		FIELD		NWIRP BETHPAGE		STATE		ABOVE PERM DATUM		OTHER SERVICES	
DRILLING MEAS FROM		COUNTRY		STATE		LOCATION		SEC		TWP	
DATE		AUGUST 19, 2003		TYPE FLUID IN HOLE		BENTONITE		K.B.		D.F.	
RUN No		SALINITY		DENSITY		LEVEL		MAX REC. TEMP.		G.L.	
TYPE LOG		DEPTH-DRILLER		DEPTH-LOGGER		BTM LOGGED INTERVAL		TOP LOGGED INTERVAL		OPERATING RIG TIME	
RECORDED BY		BENJAMIN RICE		WITNESSED BY		STAN CONTI		BOREHOLE RECORD		CASING RECORD	
NO.		BIT		FROM		TO		SIZE		WGT.	
8 INCH		103 FEET		TOTAL DEPTH		8 INCH		PVC		GROUND SURFACE	
				103 FEET							

-880 SP (mV) -450 1 100 Single Point Resistance (Ohms) 300
 0 Current (ma) 1 120 0 Natural Gamma (cps) 120



50

60

70

80

90

100


110

120


130


140

150



66





160

170

180

190

200

210


220

230



240


250

260




67





380
390
400
410
420
430
440
450
460
470
480



69





APPENDIX F
BPOW3-1 WELL DATA





Tetra Tech NUS, Inc.

WELL No.: BPOW3-1

MONITORING WELL SHEET

PERMIT No:

PROJECT: NWIRP DRILLING Co.: UNITECH BORING No.: BPOW3-1
 PROJECT No.: N4037 DRILLER: BLEMINGS DATE COMPLETED: 10/8/03
 SITE: BETHPAGE DRILLING METHOD: MUD ROT NORTHING: _____
 GEOLOGIST: CONTI DEV. METHOD: AIR/PUMP EASTING: _____

Elevation / Depth of Top of Riser: /
 Elevation / Height of Top of Surface Casing: /
 I.D. of Surface Casing: 12"
 Type of Surface Casing: STEEL
 Type of Surface Seal: CONCRETE PAD

Ground Elevation Datum:

NO CASING AT THIS WELL

I.D. of Riser: 3 13/16"
 Type of Riser: SCH. 80 PVC
 Borehole Diameter: 8" Ø

Type of Backfill: VOLCLAY GROUT

Elevation / Depth of F. SAND #0 Seal: / 416

Type of Seal: CO SAND
C. SAND

Elevation / Depth of Top of Filter Pack: / 426

Elevation / Depth of Top of Screen: / 446

Type of Screen: PVC SCH 80

Slot Size x Length: 10 SLOT

I.D. of Screen: 3 13/16"


Type of Filter Pack: #1 SILICA SAND

Elevation / Depth of Bottom of Screen: / 516

Elevation / Depth of Bottom of Filter Pack: / 517

Type of Backfill Below Well: SILICA SAND

Elevation / Total Depth of Borehole: / 530



REV 2/12/04



BORING LOG

PROJECT NAME: NWIRP Bethpage
 PROJECT NUMBER: N4037
 DRILLING COMPANY: Uni-Tech
 DRILLING RIG: FAILING 1500

BORING No.: BPOW3-1
 DATE: 9-29-03 & 10/1/03
 GEOLOGIST: Conti
 DRILLER: BLEMINGS

Sample No. and Type or RQD	Depth (FL) or Run No.	Blows / 6" or RQD (%)	Sample Recovery / Sample Length	Lithology Change (Depth/FL) or Screened Interval	MATERIAL DESCRIPTION			U S C S *	Remarks	PID/FID Reading (ppm)				
					Soil Density/ Consistency or Rock Hardness	Color	Material Classification			Sample	Sampler BZ	Borehole**	Driller BZ**	
1000	0						SAND & GRAVEL		FOR MORE DETAILS OF LOG - SEE BPOW3-2 OR GEOPHYSICAL LOG.					0
1030	10								ALSO - DUE TO DRILLING MUD INTER CONNECTION W/ BPOW3-2 HAD TO GROUT THIS INITIAL HOLE 0-200' THEN MOVED 49' SE FROM ORIG LOC. START NEW ON 10/1/03. SEE NB 1360 FOR DETAILS.					0
	20								10/1/03					
1100	30						SAME.		0-90' NEW LOC					0
	40													0
1130	50													0

* When rock coring, enter rock brokenness.

** Include monitor reading in 6 foot intervals @ borehole. Increase reading frequency if elevated response read.

Remarks: 8" Φ MUD ROTARY TO START HOLE. 9/29/03

Drilling Area
 Background (ppm): 0

Converted to Well: Yes No Well I.D. #: BPOW3-1



BORING LOG

PROJECT NAME: NWIRP Bethpage
 PROJECT NUMBER: N4037
 DRILLING COMPANY: Uni-Tech
 DRILLING RIG: FAILING 1500

BORING No.: BPOW 3-1
 DATE: 9-29-03 / 10/2/03
 GEOLOGIST: Conti
 DRILLER: BLEMINGS

Sample No. and Type or RQD	Depth (Ft.) or Run No.	Blows / 6" or RQD (%)	Sample Recovery / Sample Length	Lithology Change (Depth/Ft.) or Screened Interval	MATERIAL DESCRIPTION			U S C S	Remarks	PID/FID Reading (ppm)				
					Soil Density/Consistency or Rock Hardness	Color	Material Classification			Sample	Sampler BZ	Borehole**	Driller BZ**	
	50						SAND AND GRAVEL							0
	60													0
	120	70					SOME CLAY							0
	80													0
	90						SAND AND GRAVEL		90 → 290					0
									10/2/03					
	1400	100					SILTY SAND							0

* When rock coring, enter rock brokenness.

** Include monitor reading in 6 foot intervals @ borehole. Increase reading frequency if elevated response read.

Remarks: _____

Drilling Area Background (ppm):

Converted to Well: Yes No Well I.D. #: BPOW3-1



BORING LOG

PROJECT NAME: NWIRP Bethpage
 PROJECT NUMBER: N4037
 DRILLING COMPANY: Uni-Tech
 DRILLING RIG: FAILING 1500

BORING No.: BPOW3-1
 DATE: 9/30/03
 GEOLOGIST: Conti
 DRILLER: BLEMINGS

Sample No. and Type or RQD	Depth (FL) or Run No.	Blows / 6" or RQD (%)	Sample Recovery / Sample Length	Lithology Change (Depth/FL) or Screened Interval	MATERIAL DESCRIPTION			U S C S *	Remarks	PID/FID Reading (ppm)			
					Soil Density/ Consistency or Rock Hardness	Color	Material Classification			Sample	Sampler BZ	Borehole**	Driller BZ**
	100						SILTY F/M SAND		TR CLAY				0
	110												0
	120						SAME - MORE CLAY						0
	130												0
	140						SILTY SAND (F/M)						0
	150												0

9/30
0830

* When rock coring, enter rock brokeness.

** Include monitor reading in 6 foot intervals @ borehole. Increase reading frequency if elevated reponse read.

Remarks: _____

Drilling Area Background (ppm):

Converted to Well: Yes No Well I.D. #: BPOW3-1



BORING LOG

PROJECT NAME: NWIRP Bethpage
 PROJECT NUMBER: N4037
 DRILLING COMPANY: Uni-Tech
 DRILLING RIG: FAILING 1500

BORING No.: BPOW3-1
 DATE: 9/30/03
 GEOLOGIST: Conti
 DRILLER: BLEMINGS

Sample No. and Type or RQD	Depth (FT) or Run No.	Blows / 6" or RQD (%)	Sample Recovery / Sample Length	Lithology Change (Depth/FT) or Screened Interval	MATERIAL DESCRIPTION			U S C S *	Remarks	PID/FID Reading (ppm)				
					Soil Density/ Consistency or Rock Hardness	Color	Material Classification			Sample	Sampler BZ	Borehole**	Driller BZ**	
	150						SILTY F/M SAND							0
	160													0
	170													0
	180						SAME							0
	190													0
	200													0

* When rock coring, enter rock brokenness.

** Include monitor reading in 6 foot intervals @ borehole. Increase reading frequency if elevated reponse read.

Remarks: HAD INTERCONNECTION W/ BPOW3-2 WHILE DRILLING THIS HOLE - HAD TO GROUT HOLE 0-200 MOVED 2' 49' SE FROM 3-1 - SEE PG 98 NB 1360 FOR SKETCH.

Drilling Area

Background (ppm): 0

Converted to Well: Yes No Well I.D. #: BPOW3-1



BORING LOG

PROJECT NAME: NWIRP Bethpage
 PROJECT NUMBER: N4037
 DRILLING COMPANY: Uni-Tech
 DRILLING RIG: FAILING 1500

BORING No.: BPOW3-1
 DATE: 10-2-03
 GEOLOGIST: Conti
 DRILLER: BLEMINGS

Sample No. and Type or RQD	Depth (FL) or Run No.	Blows / 6" or RQD (%)	Sample Recovery / Sample Length	Lithology Change (Depth/FL) or Screened Interval	MATERIAL DESCRIPTION			U S C S *	Remarks	PID/FID Reading (ppm)			
					Soil Density/ Consistency or Rock Hardness	Color	Material Classification			Sample	Sampler BZ	Borehole**	Driller BZ**
	200	/					SILTY SAND TR CLAY	SM SP					0
	210	/											0
	220	/											0
	230	/											0
	240	/					SAME - MORE CLAY.						0
	250	/											0

* When rock coring, enter rock brokenness.

** Include monitor reading in 6 foot intervals @ borehole. Increase reading frequency if elevated reponse read.

Remarks: _____

Drilling Area
 Background (ppm):

Converted to Well: Yes No Well I.D. #: BPOW3-1



BORING LOG

PROJECT NAME: NWIRP Bethpage
 PROJECT NUMBER: N4037
 DRILLING COMPANY: Uni-Tech
 DRILLING RIG: FAILING 1500

BORING No.: BPOW3-1
 DATE: 10/2/03
 GEOLOGIST: Conti
 DRILLER: BLEMINGS

Sample No. and Type or RQD	Depth (Ft.) or Run No.	Blows / 6" or RQD (%)	Sample Recovery / Sample Length	Lithology Change (Depth/Ft.) or Screened Interval	MATERIAL DESCRIPTION			U S C S *	Remarks	PID/FID Reading (ppm)									
					Soil Density/ Consistency or Rock Hardness	Color	Material Classification			Sample	Sampler BZ	Borehole**	Driller BZ**						
	250	/					SILTY F/M SAND											0	
	260	/																	0
	270	/																	0
	280	/																	0
	290	/																	0
	300	/																	0

10/2
10/6

* When rock coring, enter rock brokeness.

** Include monitor reading in 6 foot intervals @ borehole. Increase reading frequency if elevated reponse read.

Remarks: 8" ϕ MUD ROTARY.

Drilling Area Background (ppm): 0

Converted to Well: Yes No Well I.D. #: BPOW3-1



BORING LOG

PROJECT NAME: NWIRP Bethpage
 PROJECT NUMBER: N4037
 DRILLING COMPANY: Uni-Tech
 DRILLING RIG: FAILING 1500

BORING No.: BPOW 3-1
 DATE: 10/6/03
 GEOLOGIST: Conti
 DRILLER: BLEWINGS

Sample No. and Type or RQD	Depth (FL) or Run No.	Blows / 6" or RQD (%)	Sample Recovery / Sample Length	Lithology Change (Depth/Ft.) or Screened Interval	MATERIAL DESCRIPTION			U S C S *	Remarks	PID/FID Reading (ppm)						
					Soil Density/ Consistency or Rock Hardness	Color	Material Classification			Sample	Sampler BZ	Borehole**	Driller BZ**			
	300	/					SAND - TR CLAY								0	
	310	/														0
	320	/					SAME									0
	330	/														0
	340	/					SAME. - TO MORE CLAY									0
	350	/														0

* When rock coring, enter rock brokenness.

** Include monitor reading in 6 foot intervals @ borehole. Increase reading frequency if elevated response read.

Remarks: _____

Drilling Area
 Background (ppm):

Converted to Well: Yes No Well I.D. #: BPOW 3-1



BORING LOG

PROJECT NAME: NWIRP Bethpage
 PROJECT NUMBER: N4037
 DRILLING COMPANY: Uni-Tech
 DRILLING RIG: FAILING 1500

BORING No.: BPOW3-1
 DATE: 10/6/03
 GEOLOGIST: Conti
 DRILLER: BLEMINGS

Sample No. and Type or RQD	Depth (Ft.) or Run No.	Blows / 6" or RQD (%)	Sample Recovery / Sample Length	Lithology Change (Depth/Ft.) or Screened Interval	MATERIAL DESCRIPTION			U S C S *	Remarks	PID/FID Reading (ppm)				
					Soil Density/ Consistency or Rock Hardness	Color	Material Classification			Sample	Sampler BZ	Borehole**	Driller BZ**	
	350	/			DENSE		SILTY F/M SAND TR CLAY							0
	360	/												0
	370	/												0
	380	/					SAME - LESS CLAY.							0
	390	/												0
	400	/							MORE CLAY					0

* When rock coring, enter rock brokenness.

** Include monitor reading in 6 foot intervals @ borehole. Increase reading frequency if elevated response read.

Remarks: _____

Drilling Area
 Background (ppm): 0

Converted to Well: Yes No Well I.D. #: BPOW3-1



BORING LOG

PROJECT NAME: NWIRP Bethpage
 PROJECT NUMBER: N4037
 DRILLING COMPANY: Uni-Tech
 DRILLING RIG: FAILING 1500

BORING No.: BPOW 3-1
 DATE: 10/6/03
 GEOLOGIST: Conti
 DRILLER: BUEMINGS

Sample No. and Type or RQD	Depth (Ft.) or Run No.	Blows / 6" or RQD (%)	Sample Recovery / Sample Length	Lithology Change (Depth/Ft.) or Screened Interval	MATERIAL DESCRIPTION			U S C S *	Remarks	PID/FID Reading (ppm)						
					Soil Density/ Consistency or Rock Hardness	Color	Material Classification			Sample	Sampler BZ	Borehole**	Driller BZ**			
	400	/					SILTY SAND (F/M)								0	
	410	/					MORE CLAY									0
	420	/														0
	430	/														0
	440	/					SILTY SAND-TR CLAY									0
	450	/														0

* When rock coring, enter rock brokenness.

** Include monitor reading in 6 foot intervals @ borehole. Increase reading frequency if elevated response read.

Remarks: _____

Drilling Area
 Background (ppm):

Converted to Well: Yes No

Well I.D. #: BPOW 3-1



BORING LOG

PROJECT NAME: NWIRP Bethpage
 PROJECT NUMBER: N4037
 DRILLING COMPANY: Uni-Tech
 DRILLING RIG: FAILING 1500

BORING No.: BPOW
 DATE: 10/6/03
 GEOLOGIST: Conti
 DRILLER: BLEMINGS

Sample No. and Type or RQD	Depth (FL) or Run No.	Blows / 6" or RQD (%)	Sample Recovery / Sample Length	Lithology Change (Depth/FT) or Screened Interval	MATERIAL DESCRIPTION			U S C S *	Remarks	PID/FID Reading (ppm)								
					Soil Density/ Consistency or Rock Hardness	Color	Material Classification			Sample	Sampler BZ	Borehole**	Driller BZ**					
	450	/					SILTY SAND (F/M)											
	460	/																
	470	/					SAME											
	480	/																
	490	/					SAME											
	500	/																

* When rock coring, enter rock brokenness.

** Include monitor reading in 6 foot intervals @ borehole. Increase reading frequency if elevated response read.

Remarks: _____

Drilling Area Background (ppm):

Converted to Well: Yes No Well I.D. #: BPOW 3-1



BORING LOG

PROJECT NAME: NWIRP Bethpage
 PROJECT NUMBER: N4037
 DRILLING COMPANY: Uni-Tech
 DRILLING RIG: FALLING 1500

BORING No.: BPOW 3-1
 DATE: 10/6/03
 GEOLOGIST: Conti
 DRILLER: BLEMINGS

Sample No. and Type or RQD	Depth (Ft.) or Run No.	Blows / 6" or RQD (%)	Sample Recovery / Sample Length	Lithology Change (Depth/Ft.) or Screened Interval	MATERIAL DESCRIPTION			U S C S	Remarks	PID/FID Reading (ppm)							
					Soil Density/Consistency or Rock Hardness	Color	Material Classification			Sample	Sampler BZ	Borehole**	Driller BZ**				
	500	/					SILTY SAND (F/M)									0	
	510	/															0
	520	/					SAME										0
	530	/															0
		/		BTM					SET WELL								
		/							446 TO 516								
		/							BLANK FROM								
		/							451 TO 481								

* When rock coring, enter rock brokenness.

** Include monitor reading in 6 foot intervals @ borehole. Increase reading frequency if elevated response read.

Remarks: 8" Ø TO 530' (NO CASING AT SURFACE)

Drilling Area
 Background (ppm): 0

Converted to Well: Yes No Well I.D. #: BPOW 3-1



Tetra Tech NUS, Inc.

MONITORING WELL DEVELOPMENT RECORD

Well: BPOW3-1 Depth to Bottom (ft.): 516' BGS Responsible Personnel: Conti
 Site: NWIRP Static Water Level Before (ft.): 32' GS Drilling Co.: Uni-Tech
 Date Installed: 10/8/03 Static Water Level After (ft.): _____ Project Name: NWIRP Bethpage-Outpost Wells
 Date Developed: 10/16/03 Screen Length (ft.): 40' Project Number: N4037
 Dev. Method: AIR LIFT/PUMP Specific Capacity: _____
 Pump Type: _____ Casing ID (in.): 3 1/16

{ 446 - 451 SCR 5'
 451 - 461 BL
 481 - 516 SCR 35'

Time	Estimated Flow Rate (GPM)	Cumulative Water Volume (Gal.)	Water Level Readings (Ft. below FOG) GS.	Temperature (Degrees C)	pH	Specific Conductance (Units) ms/cm	Turbidity (NTU)	Remarks (odor, color, etc.)
0740	START	INTO 2000 GALLON						
0800	30	600	39' GS	11.83	4.16	.189	524/314	
0820	30	1200	39'	11.94	4.45	.100	495/286	
0830	LOAD	2 LVS w/ 1600 GALS.		[3200]				
0915	START	INTO 2000 GALLON						
0935	30	600	39'	13.00	4.43	.096	960/276	GRAY / SL TURBID
0955	30	1200	39'	13.20	4.57	.094	788/217	"
1015	27	1600	LVS w/ 1600	[4800]				
1050	START	INTO 2000 GAL.						
1110	30	600	39'	14.23	4.53	.095	803/184	"
1130	30	1200	39'	13.57	4.48	.090	892/138	"
1150	27	1600	39'	13.64	4.48	.092	884/122	"
	LOAD	4 LVS w/ 1600 GALS	[6400]					
1250	START	INTO 2000 GAL.						
1310	30	600	39'	14.25	4.53	.098	-/172	"
1330	30	1200	39'	13.35	4.65	.085	-/140	"
1350	27	1600	39'	13.40	4.61	.084	-/113	"
	LOAD	5 LVS w/ 1600	[8000]					

10/15
10/16

80



Tetra Tech NUS, Inc.

MONITORING WELL DEVELOPMENT RECORD

Well: BPOW 3-1 Depth to Bottom (ft.): 516 BGS Responsible Personnel: Conti
 Site: NWIRP Static Water Level Before (ft.): 32' BGS Drilling Co.: Uni-Tech
 Date Installed: 10/8/03 Static Water Level After (ft.): _____ Project Name: NWIRP Bethpage-Outpost Wells
 Date Developed: 10/16/03 Screen Length (ft.): 40 SEE PG 1 Project Number: N4037
 Dev. Method: AIR LIFT/PUMP Specific Capacity: _____
 Pump Type: _____ Casing ID (in.): 3 13/16

HORIBA/LAMOTIE

Time	Estimated Flow Rate (GPM)	Cumulative Water Volume (Gal.)	Water Level Readings (Ft. below FOO)	Temperature (Degrees C)	pH	Specific Conductance (Units <u>_____</u>) <u>ms/cm</u>	Turbidity (NTU)	Remarks (odor, color, etc.)
1420	START	INTO	2000 GAL	---	---	---	---	GRAY - SL TURBID
1440	30	600	36'	12.93	4.24	.090	796/148	" " "
1500	30	1200	36'	12.84	4.25	.084	815/111	" " "
1520	27	1600	36'	12.83	4.25	.079	684/93	" " "
1520	LOAD (6)	LVS w/ 1600 GAL		9.00				LOWERED PIPE INTO SCREENS
1000	LOAD (7)	LVS w/ 1600 GAL						AVENUE
1100	START INTO	1600 GAL						≈ 511' 5' FROM BOTTOM ±
1120	30	600	34.6'	13.18	4.65	.159	203/34	Y. SL TURBID
1140	30	1200	34.6'	13.13	5.01	.092	167/35	" " 511-516
1200	27	1600	34.6'	12.94	5.04	.085	156/32	" " 506-511
	LOAD (8)	LVS w/ 1600 GAL		[12.00]				
1245	START INTO	1600 GAL						
1305	30	600	34.5	13.80	5.01	.088	587/45	V. SL TURBID 501-506
1325	30	1200	34.5	13.59	5.22	.085	585/30	" " 496-501
1345	27	1600	34.5	13.25	5.16	.083	531/31	" " 491-496
1430	LOAD (9)	LVS w/ 1600 GAL		[14.00]				
1450	30	600	34.5	12.31	5.05	.085	317/45	V. SL TURBID 486-491
1510	30	1200	34.5	12.23	5.05	.082	225/34	" " 481-486
1530	27	1600	34.5	12.20	5.07	.082	241/31	" " 446-451

10/16
10/20

of
f

LOAD (10) LVS w/ 1600 = 16,000 (END OF AIR LIFT)



Tetra Tech NUS, Inc.

MONITORING WELL DEVELOPMENT RECORD

Well: BPOW 3-1 Depth to Bottom (ft.): 516 BGS Responsible Personnel: Conti
 Site: NWIRP Static Water Level Before (ft.): 31.5GS Drilling Co.: Uni-Tech
 Date Installed: 10/18/03 Static Water Level After (ft.): Project Name: NWIRP Bethpage-Outpost Wells
 Date Developed: 10/16/03 → Screen Length (ft.): SEE PG 1 Project Number: N4037
 Dev. Method: AIR LIFT PUMP Specific Capacity:
 Pump Type: GRABFOS 3" SUB Casing ID (in.): 3 1/4"
ST. STEEL.

LAMOTIE

Time	Estimated Flow Rate (GPM)	Cumulative Water Volume (Gal.)	Water Level Readings (Ft. below TOC)	Temperature (Degrees C)	pH	Specific Conductance (Units mS/cm)	Turbidity (NTU)	Remarks (odor, color, etc.)
1030	BEGIN SETTING PUMP		31.5					31.5 GS - WL - PRIOR TO PUMP INSERTION
1040	START PUMP		31.5					
1100	15'	300	32.0	13.37	5.76	.087		GRAY & TURBID
1110	15	450	32.0	13.15	5.85	.081	429	" "
1120	15	600	32.0	13.13	5.85	.087	176	" SL TURBID
1130	15	750	32.0	13.02	5.85	.088	109	" V SL TURBID
1140	15	900	32.0	13.12	5.81	.084	49	" " "
		DONE w/ PUMP						
1145		TAKE BPOW 3-1-DEV FOR			VOC			




APPENDIX G
BPOW3-2 WELL DATA



MONITORING WELL SHEET

PERMIT No:

PROJECT: NWIRP DRILLING Co.: UNITECH BORING No.: BPOW3-2
 PROJECT No.: N4037 DRILLER: BLEMINGS DATE COMPLETED: 9/25/03
 SITE: BETHPAGE DRILLING METHOD: MUD ROT NORTHING: _____
 GEOLOGIST: CONT1 DEV. METHOD: AIR/ PUMP EASTING: _____



Elevation / Depth of Top of Riser: 1

Elevation / Height of Top of Surface Casing: 1

I.D. of Surface Casing: 12"

Type of Surface Casing: STEEL

Type of Surface Seal: CONCRETE PAD

I.D. of Riser: 3 13/16"

Type of Riser: SCH 80 PVC

Borehole Diameter: 7 7/8"

Type of Backfill: VOLCLAY GROUT

Elevation / Depth of Seal: 1 572

Type of Seal: #0 SAND C. SAND

Elevation / Depth of Top of Filter Pack: 1 587

Elevation / Depth of Top of Screen: 1 612

Type of Screen: PVC SCH 80

Slot Size x Length: 10 SLOT

I.D. of Screen: 3 13/16"

Type of Filter Pack: #1 SILICA SAND

Elevation / Depth of Bottom of Screen: 1 647

Elevation / Depth of Bottom of Filter Pack: 1 648

Type of Backfill Below Well: SILICA SAND

Elevation / Total Depth of Borehole: 1 650

Not to Scale



BORING LOG

PROJECT NAME: NWIRP Bethpage
 PROJECT NUMBER: N4037
 DRILLING COMPANY: Uni-Tech
 DRILLING RIG: FALLING 1500

BORING No.: BPOW3-2
 DATE: 9/16/03
 GEOLOGIST: Conti
 DRILLER: BLEKINGS

Sample No. and Type or RQD	Depth (Fl.) or Run No.	Blows / 6" or RQD (%)	Sample Recovery / Sample Length	Lithology Change (Depth/Ft.) or Screened Interval	MATERIAL DESCRIPTION			U S C S .	Remarks	PID/FID Reading (ppm)									
					Soil Density/ Consistency or Rock Hardness	Color	Material Classification			Sample	Sampler BZ	Borehole**	Driller BZ**						
	50																		
							SAND AND GRAVEL		SUB ANG TO SUB ROUND GRAVEL.										0
																			0
	60																		0
																			0
																			0
	70																		0
																			0
																			0
	80						SAND - SOME GRAVEL												0
																			0
																			0
	90						SILTY SAND		LESS GRAVEL										0
																			0
																			0
																			0
	100																		0

↑
9/15
9/16
↓

* When rock coring, enter rock brokenness.

** Include monitor reading in 6 foot intervals @ borehole. Increase reading frequency if elevated response read.

Remarks: _____

Drilling Area Background (ppm):

Converted to Well: Yes No Well I.D. #: BPOW3-2



BORING LOG

PROJECT NAME: NWIRP Bethpage
 PROJECT NUMBER: N4037
 DRILLING COMPANY: Uni-Tech
 DRILLING RIG: FALLING 1500

BORING No.: BPOW 3-2
 DATE: 9-18-03
 GEOLOGIST: Conti
 DRILLER: BLEMINGS

Sample No. and Type or RQD	Depth (FL) or Run No.	Blows / 6" or RQD (%)	Sample Recovery / Sample Length	Lithology Change (Depth/FL) or Screened Interval	MATERIAL DESCRIPTION			U S C S .	Remarks	PID/FID Reading (ppm)									
					Soil Density/ Consistency or Rock Hardness	Color	Material Classification			Sample	Sampler BZ	Borehole**	Driller BZ**						
	150																		
1080					DENSE		SILTY SAND - TR CLAY - TR GRAVEL												0
	160																		0
	170																		0
	180																		0
S-1	190																		0
1150	191	50/50	-1/1		V DENSE	TAN BRN	SILTY SAND (F/M)	SM 1/SP	POOR REC										0
	200																		0

* When rock coring, enter rock brokenness.

** Include monitor reading in 6 foot intervals @ borehole. Increase reading frequency if elevated response read.

Remarks: _____

Drilling Area
 Background (ppm):

Converted to Well: Yes No Well I.D. #: BPOW 3-2



BORING LOG

PROJECT NAME: NWIRP Bethpage
 PROJECT NUMBER: N4037
 DRILLING COMPANY: Uni-Tech
 DRILLING RIG: FAILING 1500

BORING No.: BPOW3-2
 DATE: 9/18/03
 GEOLOGIST: Conti
 DRILLER: BLEMINGS

Sample No. and Type or RQD	Depth (Ft.) or Run No.	Blows / 6" or RQD (%)	Sample Recovery / Sample Length	Lithology Change (Depth/Ft.) or Screened Interval	MATERIAL DESCRIPTION			U S C S .	Remarks	PIDVFID Reading (ppm)			
					Soil Density/ Consistency or Rock Hardness	Color	Material Classification			Sample	Sampler BZ	Borehole**	Driller BZ**
	250	/			DENSE		SAND (FM) TR CLAY	SM SP					0
	260	/											0
1430	270	/							MORE CLAY				0
	280	/			DENSE	GRAY	SILTY SANDY CLAY	SM SP					0
9/18	290	/					SILTY SAND	SP SM					0
9/22	1000	/											0
1080	300	/											0

* When rock coring, enter rock brokenness.

** Include monitor reading in 6 foot intervals @ borehole. Increase reading frequency if elevated response read.

Remarks: _____

Drilling Area Background (ppm):

Converted to Well: Yes No Well I.D. #: BPOW3-2



BORING LOG

PROJECT NAME: NWIRP Bethpage
 PROJECT NUMBER: N4037
 DRILLING COMPANY: Uni-Tech
 DRILLING RIG: FAILING 500

BORING No.: BPOW 3-2
 DATE: 9/22/03
 GEOLOGIST: Conti
 DRILLER: BLEMINGS

Sample No. and Type or RQD	Depth (FL) or Run No.	Blows / 6" or RQD (%)	Sample Recovery / Sample Length	Lithology Change (Depth/Fl.) or Screened Interval	MATERIAL DESCRIPTION			U S C S *	Remarks	PID/FID Reading (ppm)			
					Soil Density/ Consistency or Rock Hardness	Color	Material Classification			Sample	Sampler BZ	Borehole**	Driller BZ**
	350				DENSE GRAY		SANDY CLAY	SC					0
	360						SILTY SAND-TR CLAY						0
	1130 370						SAME - SOME GRAVEL		GRAVEL BASED ON CUTTINGS AND DRILL TOOLS				0
	1145 380												0
	390												0
	1200 400												0

* When rock coring, enter rock brokenness.

** Include monitor reading in 6 foot intervals @ borehole. Increase reading frequency if elevated response read.

Remarks: _____

Drilling Area Background (ppm):

Converted to Well: Yes No Well I.D. #: BPOW 3-2



BORING LOG

PROJECT NAME: NWIRP Bethpage
 PROJECT NUMBER: N4037
 DRILLING COMPANY: Uni-Tech
 DRILLING RIG: FALLING 1500

BORING No.: BPOW3-2
 DATE: 9/22/03
 GEOLOGIST: Conti
 DRILLER: BLEMINGS

Sample No. and Type or RGD	Depth (Ft.) or Run No.	Blows / 6" or RGD (%)	Sample Recovery / Sample Length	Lithology Change (Depth/Ft.) or Screened Interval	MATERIAL DESCRIPTION			U S C S *	Remarks	PID/FID Reading (ppm)									
					Soil Density/ Consistency or Rock Hardness	Color	Material Classification			Sample	Sampler BZ	Borehole**	Driller BZ**						
	450																		
	1345 460																		
	1400 470							SC	SANDY CLAY	DRILLER NOTES MORE CLAY 2 470' BGS.									
	480								TO SILTY SAND	SM SP									
	1415 490																		
	500																		

* When rock coring, enter rock brokenness.

** Include monitor reading in 6 foot intervals @ borehole. Increase reading frequency if elevated response read.

Remarks: _____

Drilling Area Background (ppm): 0

Converted to Well: Yes No Well I.D. #: BPOW3-2



BORING LOG

PROJECT NAME: NWIRP Bethpage
 PROJECT NUMBER: N4037
 DRILLING COMPANY: Uni-Tech
 DRILLING RIG: FAILING 1500

BORING No.: BPOW3-2
 DATE: 9-23-03
 GEOLOGIST: Conti
 DRILLER: BLEMINGS

Sample No. and Type or RQD	Depth (FL) or Run No.	Blows / 6" or RQD (%)	Sample Recovery / Sample Length	Lithology Change (Depth/Ft.) or Screened Interval	MATERIAL DESCRIPTION			U S C S *	Remarks	PID/FID Reading (ppm)			
					Soil Density/ Consistency or Rock Hardness	Color	Material Classification			Sample	Sampler BZ	Borehole**	Driller BZ**
	550				DENSE GRAY		SILTY SAND	SM Sp					0
	560												0
	570												0
	580						SAME AS ABOVE						0
	590												0
	600												0

* When rock coring, enter rock brokenness.

** Include monitor reading in 6 foot intervals @ borehole. Increase reading frequency if elevated response read.

Remarks: _____

Drilling Area
 Background (ppm): 0

Converted to Well: Yes No

Well I.D. #: BPOW3-2



Tetra Tech NUS, Inc.

MONITORING WELL DEVELOPMENT RECORD

Well: SPW3-2 Depth to Bottom (ft.): 647' Responsible Personnel: Conti
 Site: NWIRP Static Water Level Before (ft.): 33 ± 6s Drilling Co.: Uni-Tech
 Date Installed: 9/15/03 Project Name: NWIRP Bethpage-Outlet Wells
 Date Developed: 10/13/03 Screen Length (ft.): 40' / 30' Project Number: N4037
 Dev. Method: AIR LIFT / PUMP Specific Capacity: 612-632 SCR
 Pump Type: 3 1/4" Casing ID (in.): 632-637 BLANK
637-647 SCR

Time	Estimated Flow Rate (GPM)	Cumulative Water Volume (Gal.)	Water Level Readings (Ft. below TOC)	Temperature (Degrees C)	pH	Specific Conductance (Units μ S/cm)	Turbidity (NTU)	Remarks (odor, color, etc.)
1030	LOAD (1)	LEAVES	w/ (1600) GAL					GRAY TURBID - NO RDGS
1030	START	INTO 1400	DO GAL TANKS					DEV PIPE @ 360' INITIALLY
1050	35	700	39' ±	13.91	4.13	.138	999	BRN GRAY TURBID
1110	27.5	1100	39'	13.26	4.37	.078	999	" "
1115	LOAD (2)	LEAVES w/ (1100)		[2700]				
1135	30	600	39'	13.73	4.57	.077	999	" "
1155	32.5	1300	39'	13.79	4.58	.073	999	" "
1210	LOAD (3)	LEAVES w/ (1700)		[4400]				
1215	START	INTO 1400	GAL					GRAY - TURBID
1235	25	500	39'	14.14	4.70	.070	999	
1255	27.5	1100	39	14.14	4.52	.081	999/731	" "
1300	LOAD (4)	LEAVES w/ (1100)		[5500]				
1300	START	INTO 2000	GAL					
1320	30	600	39'	14.40	4.51	.079	999/1036	GRAY TURBID
1340	30	1200	39'	13.90	4.67	.071	999/527	" "
1400	LOAD (5)	LEAVES w/ (1600)	GALS	[7100]	START INTO 1400			GAL ON TANK
1420	30	600	37'	13.80	4.90	.075	999/747	GRAY TURBID
1440	27.5	1100	37'	13.90	4.81	.075	999/552	" "
	LOAD (6)	LEAVES w/ (1400)	GALS	[8200]	10/13/03			

* NOTE: GW SAMPLES CONTAIN NO SEDIMENT, GW HAD THE APPEARANCE OF "LUMINADE" - WOULD NOT CLEAR UP (<50NTUS) DURING AIR LIFT.



Tetra Tech NUS, Inc.

MONITORING WELL DEVELOPMENT RECORD

Well: BROW 3-2 Depth to Bottom (ft.): 647' S.G.S. Responsible Personnel: Conti
 Site: NWIRP Static Water Level Before (ft.): 34' 10/15 Drilling Co.: Uni-Tech
 Date Installed: 9-15-03 Static Water Level After (ft.): _____ Project Name: NWIRP Bethpage-Outpost Wells
 Date Developed: 10/13 Screen Length (ft.): SEE PG 1 Project Number: N4037
 Dev. Method: AIR LIFT / PUMP Specific Capacity: _____
 Pump Type: _____ Casing ID (in.): 2 13/16

HORISA / LAMARIE

Time	Estimated Flow Rate (GPM)	Cumulative Water Volume (Gal.)	Water Level Readings (Ft. below TOG) GS	Temperature (Degrees C)	pH	Specific Conductance (Units mS/cm)	Turbidity (NTU)	Remarks (odor, color, etc.)
14 20	30	600	36'	12.26	4.88	.057	706/262	GRAY-SL TURBID
14 40	27	1100	36'	12.76	4.84	.057	595/211	" "
14 45	LOAD	(12) LVS	w/ 1100 GALS	[16,300]	START INTO	2000 GAL		
15 05	30	600	36'	13.15	5.01	.058	817/278	" "
15 25	30	1200	36'	13.00	5.03	.058	682/207	" "
15 45	27	1600	36'	13.03	5.13	.057	727/178	" "
16 00	LOAD	(13) LVS	w/ 1600 GAL	[17,900]				
08 00	START INTO	2000	34' INI					
08 20	30	600	35' (GS)	12.67	4.51	.115	585/310	GRAY / SL TURBID
08 40	30	1200	35'	12.66	4.68	.068	472/237	" "
09 00	27	1600	35'	12.77	4.73	.064	423/210	" "
09 00	LOAD	(14) LVS	w/ 1600 GALS	[19,500]	START INTO	1400		642-647
09 20	30	600	35'	12.74	4.83	.063	641/318	" "
09 40	27	1100	35'	12.95	4.86	.062	401/233	" "
10 00	LOAD	(15) LVS	w/ 1100 GALS	[20,600]	START INTO	2000 GAL		
10 20	30	600	35'	13.15	4.89	.067	648/289	" "
10 40	30	1200	35'	13.10	5.03	.071	528/211	" "
11 00	27	1600	35'	13.05	5.05	.073	621/228	" "
	LOAD	(16) LVS	w/ 1600 GAL	22,200 THRU	28 INCH (AIR LIFT)			* DONE AIR LIFT

10/14 ↓

10/15

10/20

AQUA TERRA GEOPHYSICS INC

COMPANY UNI TECH DRILLING
 WELL ID BPOW3-2
 FIELD NWTRP BETHPAGE
 COUNTRY STATE
 LOCATION

CO WELL FLD CITY STE FILING No
 PERMANENT DATUM
 LOG MEAS. FROM GROUND SURFACE ABOVE PERM. DATUM
 DRILLING MEAS. FROM


DATE SEPTEMBER 21, 2003
 RUN No
 TYPE LOG
 DEPTH-DRILLER 660 FEET
 DEPTH-LOGGER 659 FEET
 BITM LOGGED INTERVAL
 TOP LOGGED INTERVAL
 OPERATING RIG TIME 1.5 HRS.
 RECORDED BY BENJAMIN RICE
 WITNESSED BY STAN CONTI

BOREHOLE RECORD		CASING RECORD					
NO.	BIT	FROM	TO	SIZE	WGT.	FROM	TO
	8 INCH	95 FEET	TOTAL DEPTH	8 INCH	PVC	GROUND SURFACE	95 FEET


OTHER SERVICES

ELEVATION
 RGE
 K.B.
 D.F.
 Q.L.

2150 GP (mV) -1850 240 Single Point Resistance (ohms) 340
 Current (ma) 1 120 Natural Gamma (cps) 110



160
170
180
190
200
210
220
230
240
250
160



106

380

390

400

410

420

430

440


450


460

470


480

108





APPENDIX H
BPOW4-1 WELL DATA






Tetra Tech NUS, Inc.

WELL No.: BPOW4-1

MONITORING WELL SHEET

PERMIT No:

PROJECT: NWIRP DRILLING Co.: UNITECH BORING No.: BPOW4-1
 PROJECT No.: N4037 DRILLER: BLEMMINGS DATE COMPLETED: 7/17/03
 SITE: BEHPAGE DRILLING METHOD: MUD ROT RECONSTRUCTED 2 → 12/9/03
 GEOLOGIST: CONTI DEV. METHOD: AIR/PUMP EASTING: _____



Elevation / Depth of Top of Riser: 1
 Elevation / Height of Top of Surface Casing: 1
 I.D. of Surface Casing: 9"
 Type of Surface Casing: STEEL
 Type of Surface Seal: CONCRETE PAD 2'x2'x6"
 I.D. of Riser: 3 13/16"
 Type of Riser: PVC SCH 80
 Borehole Diameter: 8 3/4" ≈ 9"
 Type of Backfill: VOLCLAY GROUT
 Elevation / Depth of Seal: F SAND #0 1602
 Type of Seal: NA
 Elevation / Depth of Top of Filter Pack: 1620
 Elevation / Depth of Top of Screen: 1652
 Type of Screen: PVC SCH 80 (PLACED 7/17/03)
 Slot Size x Length: 10 SL x 40'
 INITIAL I.D. of Screen: 3 13/16"
 Type of Filter Pack: #1 SILICA SAND
 Elevation / Depth of Bottom of Screen: 1692
 Elevation / Depth of Bottom of Filter Pack: 1693
 Type of Backfill Below Well: SILICA SAND
 Elevation / Total Depth of Borehole: 1700

Ground Elevation Datum:

10" CAS TO 85'

85'

K-PACKER AT 642'

10 SLOT 2" Φ STAINLESS STEEL SCREEN

INSTALLED 12/9/03 AS PART OF RECONSTRUCTION OF WELL.

NOTE: 10' S.S RISER PLACED ABOVE SCREEN - 652 → 642

Not to Scale



BORING LOG

PROJECT NAME: NWIRP Bethpage
 PROJECT NUMBER: N4037
 DRILLING COMPANY: Uni-Tech
 DRILLING RIG: FAILING 1500

BORING No.: BPOW4-1
 DATE: 7-8-03
 GEOLOGIST: Conti / Shickora
 DRILLER: J BLEMINGS

Sample No. and Type or RQD	Depth (Ft.) or Run No.	Blows / 6" or RQD (%)	Sample Recovery / Sample Length	Lithology Change (Depth/Ft.) or Screened Interval	MATERIAL DESCRIPTION			U S C S .	Remarks	PID/FID Reading (ppm)				
					Soil Density/ Consistency or Rock Hardness	Color	Material Classification			Sample	Sampler BZ	Borehole**	Driller BZ**	
	0	/					TOP 6" TOPSOIL							
	10	/					SAND AND GRAVEL		(FROM CUTTINGS)					0
	20	/												0
	30	/												0
	40	/					SAND AND GRAVEL		1" ϕ SUB ROUND FROM CUTTINGS					0
	50	/												0

* When rock coring, enter rock brokenness.

** Include monitor reading in 6 foot intervals @ borehole. Increase reading frequency if elevated reponse read.

Remarks: START W 8" ϕ MUD ROTARY - REAM TO 12"
TO SET 10" CASING.

Drilling Area Background (ppm): 0

Converted to Well: Yes No Well I.D. #: BPOW4-1



BORING LOG

PROJECT NAME: NWIRP Bethpage
 PROJECT NUMBER: N4037
 DRILLING COMPANY: Uni-Tech
 DRILLING RIG: FAILING 1500

BORING No.: BPOW4-1
 DATE: 7-8-03 / 7-9-03
 GEOLOGIST: Conti
 DRILLER: J BLEMINGS

Sample No. and Type or RQD	Depth (FL) or Run No.	Blows / 6" or RQD (%)	Sample Recovery / Sample Length	Lithology Change (Depth/Ft.) or Screened Interval	MATERIAL DESCRIPTION			U S C S *	Remarks	PID/FID Reading (ppm)									
					Soil Density/ Consistency or Rock Hardness	Color	Material Classification			Sample	Sampler BZ	Borehole**	Driller BZ**						
	50	/			DENSE		SAND AND GRAVEL												0
	60	/																	
	70	/																	0
	80	/					SAND												
	90	/					CLAYEY SAND		± 90'										0
	100	/					Sand and Gravel		1/4" φ sub round										0

7/8
7/9

7/11
↓

* When rock coring, enter rock brokeness.

** Include monitor reading in 6 foot intervals @ borehole. Increase reading frequency if elevated reponse read.

Remarks: Beam to 12" φ ON 7-10-03
set 10" CASING TO 85' ON 7-10-03
8 3/4" φ drilling from 85' to T.D.

Drilling Area
Background (ppm):

Converted to Well: Yes No Well I.D. #: BPOW4-1



BORING LOG

PROJECT NAME: NWIRP Bethpage
 PROJECT NUMBER: N4037
 DRILLING COMPANY: Uni-Tech
 DRILLING RIG: FAILING 1500

BORING No.: BPOW4-1
 DATE: 7-11-03 / 7-14-03
 GEOLOGIST: Conti / Shickora
 DRILLER: J BLEMINGS

↑
7/11
7/14
↓

Sample No. and Type or RQD	Depth (Ft.) or Run No.	Blows / 6" or RQD (%)	Sample Recovery / Sample Length	Lithology Change (Depth/Ft.) or Screened Interval	MATERIAL DESCRIPTION			U S C S *	Remarks	PID/FID Reading (ppm)								
					Soil Density/ Consistency or Rock Hardness	Color	Material Classification			Sample	Sampler BZ	Borehole**	Driller BZ**					
	100																	
	1055	110					Sand (Trace gravel)		(from cuttings)									0
	0925																	
	120						Sand + Gravel		1/2" ϕ sub round									
	1050	130					Sand and Gravel		1" ϕ sub round from cuttings									0
	1445	140																
	1515	150					clayey Sand + Gravel		1" ϕ sub round									0

* When rock coring, enter rock brokenness.

** Include monitor reading in 6 foot intervals @ borehole. Increase reading frequency if elevated response read.

Remarks: _____

Drilling Area Background (ppm):

Converted to Well: Yes No Well I.D. #: BPOW 4-1



BORING LOG

PROJECT NAME: NWIRP Bethpage
 PROJECT NUMBER: N4037
 DRILLING COMPANY: Uni-Tech
 DRILLING RIG: Failing 1500

BORING No.: BPOW 4-1
 DATE: 7-14-03
 GEOLOGIST: Conti / Shickora
 DRILLER: J. Blening

Sample No. and Type or RQD	Depth (Ft.) or Run No.	Blows / 6" or RQD (%)	Sample Recovery / Sample Length	Lithology Change (Depth/Ft.) or Screened Interval	MATERIAL DESCRIPTION			U S C S *	Remarks	PID/FID Reading (ppm)								
					Soil Density/ Consistency or Rock Hardness	Color	Material Classification			Sample	Sampler BZ	Borehole**	Driller BZ**					
	150	/	/															
1540	160	/	/				Sand + Gravel		1" ϕ subground								0	
1617	170	/	/				Same as above											0
1647	180	/	/															
1719	190	/	/				Same as above											0
	200	/	/															

↑
7/4
7/15
↓

* When rock coring, enter rock brokenness.

** Include monitor reading in 6 foot intervals @ borehole. Increase reading frequency if elevated reponse read.

Remarks: _____

Drilling Area Background (ppm): 0

Converted to Well: Yes No Well I.D. #: BPOW 4-1



BORING LOG

PROJECT NAME: NWIRP Bethpage
 PROJECT NUMBER: N4037
 DRILLING COMPANY: Uni-Tech
 DRILLING RIG: Falling 1500

BORING No.: BPOW 4-1
 DATE: 7-15-03
 GEOLOGIST: Conti Shickora
 DRILLER: J. Blenkins

Sample No. and Type or RQD	Depth (FL) or Run No.	Blows / 6" or RQD (%)	Sample Recovery / Sample Length	Lithology Change (Depth/Fl.) or Screened Interval	MATERIAL DESCRIPTION			U S C S *	Remarks	PID/FID Reading (ppm)								
					Soil Density/ Consistency or Rock Hardness	Color	Material Classification			Sample	Sampler BZ	Borehole**	Driller BZ**					
	200	/																
0930	210	/					Clayey Sand (Trace gravel)		From cuttings									0
	220	/																
1005	230	/					Sandy Silt + Clay		From cuttings									0
	240	/					Same as above											0
1033	250	/					Sand (Trace clay)											0

* When rock coring, enter rock brokenness.

** Include monitor reading in 6 foot intervals @ borehole. Increase reading frequency if elevated response read.

Remarks: _____

Drilling Area
 Background (ppm):

Converted to Well: Yes No Well I.D. #: BPOW 4-1



BORING LOG

PROJECT NAME: NWIRP Bethpage
 PROJECT NUMBER: N4037
 DRILLING COMPANY: Uni-Tech
 DRILLING RIG: Falling 1500

BORING No.: BPOW 4-1
 DATE: 7-15-03
 GEOLOGIST: Conti Shickora
 DRILLER: J. Blenkins

Sample No. and Type or RQD	Depth (Ft.) or Run No.	Blows / 6" or RQD (%)	Sample Recovery / Sample Length	Lithology Change (Depth/Ft.) or Screened Interval	MATERIAL DESCRIPTION			U S C S *	Remarks	PID/FID Reading (ppm)								
					Soil Density/ Consistency or Rock Hardness	Color	Material Classification			Sample	Sampler BZ	Borehole**	Driller BZ**					
	250	/																
	260	/																
1059	270	/					Black Sand (Trace Silt/clay) Some lignite		From cuttings									0
	280	/																
1123	290	/					Sand (some clay)		From cuttings									0
	300	/																

* When rock coring, enter rock brokeness.

** Include monitor reading in 6 foot intervals @ borehole. Increase reading frequency if elevated reponse read.

Remarks: _____

Drilling Area
 Background (ppm):

Converted to Well: Yes No Well I.D. #: BPOW 4-1



BORING LOG

PROJECT NAME: NWIRP Bethpage
 PROJECT NUMBER: N4037
 DRILLING COMPANY: Uni-Tech
 DRILLING RIG: Failing 1500

BORING No.: BPOW 4-1
 DATE: 7-15-03
 GEOLOGIST: Conti Shickora
 DRILLER: J-Blenings

Sample No. and Type or RQD	Depth (FT) or Run No.	Blows / 6" or RQD (%)	Sample Recovery / Sample Length	Lithology Change (Depth/FT) or Screened Interval	MATERIAL DESCRIPTION			U S C S *	Remarks	PID/FID Reading (ppm)							
					Soil Density/ Consistency or Rock Hardness	Color	Material Classification			Sample	Sampler BZ	Borehole**	Driller BZ**				
	300	/															
1151	310	/					Sand (some clay)		From cuttings								0
	320	/															
1320	330	/					Same as above		From cuttings								0
	340	/															
1957	350	/					Same as above		From cuttings								0

* When rock coring, enter rock brokenness.

** Include monitor reading in 6 foot intervals @ borehole. Increase reading frequency if elevated response read.

Remarks: _____

Drilling Area

Background (ppm):

Converted to Well: Yes No

Well I.D. #: BPOW 4-1



BORING LOG

PROJECT NAME: NWIRP Bethpage
 PROJECT NUMBER: N4037
 DRILLING COMPANY: Uni-Tech
 DRILLING RIG: Falling 1500

BORING No.: BPOW 4-1
 DATE: 7-15-03
 GEOLOGIST: Conti Shickora
 DRILLER: J. Blenings

Sample No. and Type or RQD	Depth (Ft.) or Run No.	Blows / 6" or RQD (%)	Sample Recovery / Sample Length	Lithology Change (Depth/Ft.) or Screened Interval	MATERIAL DESCRIPTION			U S C S *	Remarks	PID/FID Reading (ppm)								
					Soil Density/ Consistency or Rock Hardness	Color	Material Classification			Sample	Sampler BZ	Borehole**	Driller BZ**					
	350	/																
	360	/																
1423	370	/					Sand (Trace silt/clay)		From cuttings									0
	380	/																
1455	390	/					Same as above		From cuttings									0
	400	/																

* When rock coring, enter rock brokeness.

** Include monitor reading in 6 foot intervals @ borehole. Increase reading frequency if elevated reponse read.

Remarks: _____

Drilling Area
 Background (ppm): 0

Converted to Well: Yes No Well I.D. #: BPOW 4-1



BORING LOG

PROJECT NAME: NWIRP Bethpage
 PROJECT NUMBER: N4037
 DRILLING COMPANY: Uni-Tech
 DRILLING RIG: Falling 1500

BORING No.: BPOW 4-1
 DATE: 7-15-03
 GEOLOGIST: Conti Shickora
 DRILLER: J Blenings

Sample No. and Type or RQD	Depth (Ft.) or Run No.	Blows / 6" or RQD (%)	Sample Recovery / Sample Length	Lithology Change (Depth/Ft.) or Screened Interval	MATERIAL DESCRIPTION			U S C S *	Remarks	PID/FID Reading (ppm)								
					Soil Density/ Consistency or Rock Hardness	Color	Material Classification			Sample	Sampler BZ	Borehole**	Driller BZ**					
	400	/																
1521	410	/					Same as above		From cuttings									0
	420	/																
1605	430	/					Sandy clay (Trace silt)		From cuttings									0
	440	/																
	450	/					Same as above											0

↑
7/15

* When rock coring, enter rock brokenness.

** Include monitor reading in 6 foot intervals @ borehole. Increase reading frequency if elevated response read.

Remarks: _____

Drilling Area Background (ppm): 0

Converted to Well: Yes No Well I.D. #: BPOW 4-1



BORING LOG

PROJECT NAME: NWIRP Bethpage
 PROJECT NUMBER: N4037
 DRILLING COMPANY: Uni-Tech
 DRILLING RIG: Failing 1500

BORING No.: BPOW 4-1
 DATE: 7-15-03
 GEOLOGIST: Centr Shickora
 DRILLER: J. Blenkins

Sample No. and Type or RQD	Depth (Fl. or Run No.)	Blows / 6" or RQD (%)	Sample Recovery / Sample Length	Lithology Change (Depth/Fl.) or Screened Interval	MATERIAL DESCRIPTION			U S C S *	Remarks	PID/FID Reading (ppm)		
					Soil Density/ Consistency or Rock Hardness	Color	Material Classification			Sample	Sampler BZ	Borehole**
	450	/	/									
	460	/	/									
0940	470	/	/				Sand (Trace Silt and clay and Lignite)		From cuttings			0
	480	/	/									
1009	490	/	/				Same as above		From cuttings			0
	500	/	/									

7/16
↓

* When rock coring, enter rock brokenness.

** Include monitor reading in 6 foot intervals @ borehole. Increase reading frequency if elevated reponse read.

Remarks: _____

Drilling Area Background (ppm):

Converted to Well: Yes No Well I.D. #: BPOW4-1



BORING LOG

PROJECT NAME: NWIRP Bethpage
 PROJECT NUMBER: N4037
 DRILLING COMPANY: Uni-Tech
 DRILLING RIG: Falling 1500

BORING No.: BPOW 4-1
 DATE: 7-16-03
 GEOLOGIST: Genti Shickora
 DRILLER: J. Blenkins

Sample No. and Type or ROD	Depth (FL) or Run No.	Blows / 6" or RQD (%)	Sample Recovery / Sample Length	Lithology Change (Depth/FL) or Screened Interval	MATERIAL DESCRIPTION			U S C S *	Remarks	PID/FID Reading (ppm)			
					Soil Density/Consistency or Rock Hardness	Color	Material Classification			Sample	Sampler BZ	Borehole**	Driller BZ**
	500	/							From cuttings				0
1038	510	/							Sand (Trace silt & clay)				
	520	/											
1103	530	/							Same as above	From Cuttings			0
	540	/											
1132	550	/							Same as above	From Cuttings			0

* When rock coring, enter rock brokenness.

** Include monitor reading in 6 foot intervals @ borehole. Increase reading frequency if elevated reponse read.

Remarks: _____

Drilling Area
 Background (ppm):

Converted to Well: Yes No

Well I.D. #: BPOW 4-1



BORING LOG

PROJECT NAME: NWIRP Bethpage
 PROJECT NUMBER: N4037
 DRILLING COMPANY: Uni-Tech
 DRILLING RIG: Failing 1500

BORING No.: BPOW 4-1
 DATE: 7-16-03
 GEOLOGIST: Conti Shickora
 DRILLER: J. Blewings

Sample No. and Type or RQD	Depth (FL) or Run No.	Blows / 6" or RQD (%)	Sample Recovery / Sample Length	Lithology Change (Depth/FL) or Screened Interval	MATERIAL DESCRIPTION			U S C S *	Remarks	PID/FID Reading (ppm)								
					Soil Density/ Consistency or Rock Hardness	Color	Material Classification			Sample	Sampler BZ	Borehole**	Driller BZ**					
	550																	
	560																	
1334	570						Sand (Trace fine gravel + lignite)		From cuttings									0
	580																	
1402	590						Sand (Trace clay and gravel)		From cuttings									0
	600																	

* When rock coring, enter rock brokenness.

** Include monitor reading in 6 foot intervals @ borehole. Increase reading frequency if elevated response read.

Remarks: _____

Drilling Area Background (ppm):

Converted to Well: Yes No Well I.D. #: BPOW 4-1



BORING LOG

PROJECT NAME: NWIRP Bethpage
 PROJECT NUMBER: N4037
 DRILLING COMPANY: Uni-Tech
 DRILLING RIG: Failing 1500

BORING No.: BPOW 4-1
 DATE: 7-16-03
 GEOLOGIST: Conti Shickora
 DRILLER: J. Blenings

Sample No. and Type or RQD	Depth (Ft.) or Run No.	Blows / 6" or RQD (%)	Sample Recovery / Sample Length	Lithology Change (Depth/Ft.) or Screened Interval	MATERIAL DESCRIPTION			U S C S *	Remarks	PID/FID Reading (ppm)								
					Soil Density/ Consistency or Rock Hardness	Color	Material Classification			Sample	Sampler BZ	Borehole**	Driller BZ**					
	600	/																
1433	610	/					Sand (Trace clay and lignite)		From cuttings									0
	620	/																
1508	630	/					Sand (Trace Clay)		From cuttings									0
		/							Losing mud to formation at ~ 635' BGS									
	640	/					medium to coarse grain Sand & Fine Gravel											
		/							Losing mud to formation									
↑ 7/16	1710	650	/				Sand + Fine Gravel											0

* When rock coring, enter rock brokenness.

** Include monitor reading in 6 foot intervals @ borehole. Increase reading frequency if elevated response read.

Remarks: _____

Drilling Area Background (ppm): 0

Converted to Well: Yes No

Well I.D. #: BPOW4-1



BORING LOG

PROJECT NAME: NWIRP Bethpage
 PROJECT NUMBER: N4037
 DRILLING COMPANY: Uni-Tech
 DRILLING RIG: Failing 1500

BORING No.: BPOW 4-1
 DATE: 7-17-03
 GEOLOGIST: Conti Shickora
 DRILLER: J. Blenings

Sample No. and Type or RQD	Depth (Fl.) or Run No.	Blows / 6" or RQD (%)	Sample Recovery / Sample Length	Lithology Change (Depth/Fl.) or Screened Interval	MATERIAL DESCRIPTION			U S C S *	Remarks	PID/FID Reading (ppm)							
					Soil Density/ Consistency or Rock Hardness	Color	Material Classification			Sample	Sampler BZ	Borehole**	Driller BZ**				
	650	/		652													
0852	660	/		/			Medium to coarse grain Sand (Trace silt and clay) (fine gravel)		From cuttings								0
0923	670	/		/			Same as above		From cuttings								0
	680	/		/													
1005	690	/		/			Same as above		From cuttings								0
		/		692													
1031	700	/		EoB			Same as above										0

* When rock coring, enter rock brokenness.

** Include monitor reading in 6 foot intervals @ borehole. Increase reading frequency if elevated response read.

Remarks: _____

Drilling Area Background (ppm): 0

Converted to Well: Yes No Well I.D. #: BPOW 4-1



Tetra Tech NUS, Inc.

MONITORING WELL DEVELOPMENT RECORD

Page 1 of 1

Well: BPOW 4-1 Depth to Bottom (ft.): 612 ± BGS Responsible Personnel: Conti
 Site: NWIRP BETHPAGE Static Water Level Before (ft.): ~45' Drilling Co.: Uni-Tech
 Date Installed: 7-17-03 Static Water Level After (ft.): _____ Project Name: NWIRP Bethpage-Outpost Wells
 Date Developed: 7/23/03 → Screen Length (ft.): _____ Project Number: N4037
 Dev. Method: AIR LIFT / PUMP Specific Capacity: _____
 Pump Type: _____ Casing ID (in.): _____

Time	Estimated Flow Rate (GPM)	Cumulative Water Volume (Gal.)	Water Level Readings (Ft. below TOC)	Temperature (Degrees C)	pH	Specific Conductance (Units / cm)	Turbidity (NTU)	Remarks (odor, color, etc.)
7/23 0930	—	—	—	—	—	—	—	INITIAL START
1020	30 ±	1400	—	15.80	9.05	.447	990	GRAY - V. TURBID
1025	LOAD (1)	LEAVES	—	—	—	—	—	1400 NET
1155	START	AIR LIFT	—	—	—	—	—	—
1225	30 ±	900/2300	—	14.50	7.03	.104	990	BRN - V. TURBID w/F SAND
1305	LOAD (2)	2800	—	—	—	—	—	—
1305	START LOAD (3) 2100K	—	—	—	—	—	—	—
1335	27 ±	800/3800	—	18.60	6.25	.126	560	BRN - SL TURBID w/F SAND
1400	—	900 3700	—	—	—	—	—	—
								— HAVING PROBLEMS w/ SAND IN WELL - ALSO DEV ROPE "HUNG UP" IN HOLE. SEE NB 1360 FOR DETAILS = 7/23/03
								7/24/03
								[WILL ATTEMPT TO REPAIR WELL AND REDEVELOP]

JPH COND
1.61 176

TURB
0

TEMP
16.57

DEV. AFTER REPAIR TO WELL



Tetra Tech NUS, Inc.

MONITORING WELL DEVELOPMENT RECORD

Well: EP0W4-1 Depth to Bottom (ft.): 692' Responsible Personnel: Conti
 Site: NWIRP Static Water Level Before (ft.): 28' Bgs Drilling Co.: Uni-Tech
 Date Installed: 7/17/03 Static Water Level After (ft.): _____ Project Name: NWIRP Bethpage-Outpost Wells
 Date Developed: 12/10/03 Screen Length (ft.): 40' Project Number: N4037
 Dev. Method: AIR LIFT/PUMP Specific Capacity: _____
 Pump Type: 3" SUB Casing ID (in.): 2" φ

Due to 2" φ SCREEN - CANNOT isolate the zones within the screen, during dev.

HORIBA/LAMORTE

Time	Estimated Flow Rate (GPM)	Cumulative Water Volume (Gal.)	Water Level Readings (Ft. below TOG)	Temperature (Degrees C)	pH	Specific Conductance (Units _____) mS/cm	Turbidity (NTU)	Remarks (odor, color, etc.)
1030	LOAD	① LVS w/ 1600	GALLONS					LOAD ① NO PARAMETERS WELL DEV PIPE AT 600' INITIALLY
1130	START	INTO 2000	GALLON TRUNK					
1150	25	500	33.0	11.29	4.21	149	76/42	Gray - Sl Turbid.
1210	27.5	1100	33.0	11.17	4.58	105	43/37	" "
1230	27	1600	33.0	11.05	4.60	97	45/35	" "
1240	LOAD	② LVS w/ 1600 =		32007	START INTO 1400			GALLON
1300	30	600	33.5	11.40	4.57	93	85/40	" "
1320	27.5	1100	33.5	11.22	4.58	89	69/41	" "
1330	LOAD	③ LVS w/ 1100	GALLONS					START INTO 2000 (4300)
1350	25	500	33.5	11.33	4.62	89	70/50	Gray Sl Turbid
1410	27.5	1100	33.5	10.94	4.58	87	82/40	" "
1430	27	1600	33.5	11.19	4.64	83	85/41	" "
1440	LOAD	④ LVS w/ 1600 =		5900	START INTO 1400			GAL
1500	30	600	33.5	11.12	4.63	86	72/48	Gray SL Turbid
1520	27.5	1100	33.5	11.18	4.64	85	75/49	" "
1530	LOAD	⑤ LVS w/ 1100	GALLONS					START INTO 1600 7000
1550	25	500	33.5	11.15	4.65	86	88/55	" "
1610	27.5	1100	33.5	11.20	4.61	83	76/45	" "
1630	27	1600	33.5	11.12	4.63	87	78/45	" "
1630	LOAD	⑥ LVS w/ 1600	GALLONS					[8600]

27



Tetra Tech NUS, Inc.

MONITORING WELL DEVELOPMENT RECORD

Well: BPOW 4-1 Depth to Bottom (ft.): 692 Responsible Personnel: Conti
 Site: NWIRP Static Water Level Before (ft.): 28' Drilling Co.: Uni-Tech
 Date Installed: 7/17/03 Static Water Level After (ft.): _____ Project Name: NWIRP Bethpage-Outpost Wells
 Date Developed: 12/16/03 Screen Length (ft.): 40 Project Number: N4037
 Dev. Method: AIR LIFT Specific Capacity: _____
 Pump Type: 3" SUB. Casing ID (in.): 3" φ SS

HORREN/LANDITE


Time	Estimated Flow Rate (GPM)	Cumulative Water Volume (Gal.)	Water Level Readings (Ft. below TOE)	Temperature (Degrees C)	pH	Specific Conductance (Units)	Turbidity (NTU)	Remarks (odor, color, etc.)
0820	START INTO	2000	GALLON TANK					CLEAR V. SL TURBID
0840	30	600	35.5	12.08	4.68	.089	117/49	" "
0900	27.5	1100	35.5	11.87	4.75	.083	68/32	" "
0920	27	1600	35.5	12.03	4.80	.082	80/32	" "
0925	LOAD (7)	LVS w/ 1600	GALLONS					(START INTO 1400)
0945	25	500	35.5	12.07	4.82	.081	103/39	CLEAR V SL TURBID
1005	27.5	1100	35.5	12.05	4.81	.082	78/29	" "
1010	LOAD (8)	LVS w/ 1100	GALLONS					(START INTO 2000)
1030	25	500	35.5	12.25	4.88	.082	105/32	" "
1050	27.5	1100	35.5	12.25	4.89	.079	114/31	" "
1110	27	1600	35.5	12.36	4.90	.078	117/27	" "
1130	LOAD (9)	LVS w/ 1600	GALLONS					(START INTO 1400 GALLON)
1150	25	500	35.5	12.24	4.87	.077	111/31	" "
1210	27.5	1400	35.5	12.11	4.87	.074	70/25	" "
		END OF AIR LIFT DEV.	(14000)	TOTAL				

12/11

28



APPENDIX I
BPOW4-2 WELL DATA






MONITORING WELL SHEET

PERMIT No:

PROJECT: NWIRP DRILLING Co.: UNITECH BORING No.: BPOW4-2
 PROJECT No.: N4037 DRILLER: BLEMINGS DATE COMPLETED: 7/7/03
 SITE: BETH PAGE DRILLING METHOD: MUD ROT NORTHING: _____
 GEOLOGIST: CONTI DEV. METHOD: AIR/PUMP EASTING: _____



Elevation / Depth of Top of Riser: 1
 Elevation / Height of Top of Surface Casing: 1
 I.D. of Surface Casing: 9"
 Type of Surface Casing: STEEL
 Type of Surface Seal: CONCRETE
PAD 2' x 2' x 6"
 I.D. of Riser: 3 13/16"
 Type of Riser: PVC SCH 80
 Borehole Diameter: 9 1/2"
 Type of Backfill: VOLCLAY
GROUT
 Elevation / Depth of Seal: F SAND #0 1690
 Type of Seal: NA
 Elevation / Depth of Top of Filter Pack: C SAND 1705
 Elevation / Depth of Top of Screen: 1725
 Type of Screen: PVC SCH 80
 Slot Size x Length: 10 x 30 W 10' BLANK
 I.D. of Screen: 3 13/16" 735 → 745
 Type of Filter Pack: #1 SILICA SAND
 Elevation / Depth of Bottom of Screen: 1765
 Elevation / Depth of Bottom of Filter Pack: 1766
 Type of Backfill Below Well: SILICA SAND
 Elevation / Total Depth of Borehole: 1780



BORING LOG

PROJECT NAME: NWIRP Bethpage
 PROJECT NUMBER: N4037
 DRILLING COMPANY: Uni-Tech
 DRILLING RIG: FAILING 1500

BORING No.: BPOW4-2
 DATE: 6/4/03 →
 GEOLOGIST: Conti
 DRILLER: J. BLEMINGS

Sample No. and Type or RQD	Depth (Fl.) or Run No.	Blows / 6" or RQD (%)	Sample Recovery / Sample Length	Lithology Change (Depth/Fl.) or Screened Interval	MATERIAL DESCRIPTION			U S C S	Remarks	PID/FID Reading (ppm)			
					Soil Density/ Consistency or Rock Hardness	Color	Material Classification			Sample	Sampler BZ	Borehole**	Driller BZ**
6/4	1130	0			DENSE	BRN	SAND AND GRAVEL		LOGGED FROM CUTTINGS IN BETWEEN SAMPLES.				0
	0900								RODS "CHATTERING" FROM 0' TO 20'.				0
6/5		10							RESTART @ NEW LOCATION - ≈ 1' WEST - 0-20 ≈ 15 MIN. NO OBSTRUCTIONS GOOD RETURN OF DRILL CUTTINGS.				0
	0915	20			M DENSE	BRN	SAND - SOME GRAVEL SW		MIX MORE MUD				0
	1030	30											0
	1100	40					SAND AND GRAVEL		(FROM CUTTINGS)				0
	1120	50											0

* When rock coring, enter rock brokenness.

** Include monitor reading in 6 foot intervals @ borehole. Increase reading frequency if elevated response read.

Remarks: START W/ 8" Φ MUD ROT. GOT TO 6' - LOST RETURN Drilling Area Background (ppm): 0
TOO CLOSE TO STORM SEWER - MOVE ≈ 1' WEST (CLOSER TO CURB)
DRILL TO 150 ± W/ 8" Φ - BEAM W/ 12" Φ TO 150 - SET 10" Φ CASING.

Converted to Well: Yes No Well I.D. #: BPOW4-2



BORING LOG

PROJECT NAME: NWIRP Bethpage
 PROJECT NUMBER: N4037
 DRILLING COMPANY: Uni-Tech
 DRILLING RIG: FALLING 1500

BORING No.: BPOW4-2
 DATE: 6-5-03 / 6-17-03
 GEOLOGIST: Conti
 DRILLER: J BLEMINGS

Sample No. and Type or RQD	Depth (Ft.) or Run No.	Blows / 6" or RQD (%)	Sample Recovery / Sample Length	Lithology Change (Depth/Ft.) or Screened Interval	MATERIAL DESCRIPTION			U S C S *	Remarks	PID/FID Reading (ppm)			
					Soil Density/ Consistency or Rock Hardness	Color	Material Classification			Sample	Sampler BZ	Borehole**	Driller BZ**
S-1 e 1120	52	100/6"	5/5		V DENSE	YELLOW BRN	SAND AND GRAVEL	GW	WET SUBROUND 1" GRAVEL. W/ 1 1/2" PCS IN WASH PORTION OF SAMPLE.	0			0
	1200	60											0
	1230	70					SAND AND GRAVEL		LESS GRAVEL ≈ 70' TO 80'				0
	1300	80					DENSE BRN SILTY F/M SAND	SP					0
	1330	90											0
	1400	100											0

* When rock coring, enter rock brokenness.

** Include monitor reading in 6 foot intervals @ borehole. Increase reading frequency if elevated reponse read.

Remarks: SET 10" @ 110' (GROUTED IN) SEE NB1351 FOR Drilling Area Background (ppm): 0
DETAILS - SET 10" @ 100' ON 6/17/03 - AT 2ND LOCATION.

Converted to Well: Yes No Well I.D. #: BPOW4-2



BORING LOG

PROJECT NAME: NWIRP Bethpage
 PROJECT NUMBER: N4037
 DRILLING COMPANY: Uni-Tech
 DRILLING RIG: FALING 1500

BORING No.: BPOW4-2
 DATE: 6/5/03 / 6/17/03 / 6/19/03
 GEOLOGIST: Conti
 DRILLER: J BLEWINGS

Sample No. and Type or RQD	Depth (FL) or Run No.	Blows / 6" or RQD (%)	Sample Recovery / Sample Length	Lithology Change (Depth/FL) or Screened Interval	MATERIAL DESCRIPTION			U S C S *	Remarks	PID/FID Reading (ppm)									
					Soil Density/ Consistency or Rock Hardness	Color	Material Classification			Sample	Sampler BZ	Borehole**	Driller BZ**						
	100																		
					DENSE	BRN	SILTY F/M SAND	SM SP											0
	1130	110								10"Ø SET @ 110 AND GROUTED IN PERM. HAD TO MOVE 10' N. DUE TO LEAKAGE AROUND CAS. SET 2ND CAS TO 100' ON 6/17/03.								0	
	1230	120																	0
		130																	0
		140																	0
	1415	150																	0

* When rock coring, enter rock brokenness.

** Include monitor reading in 6 foot intervals @ borehole. Increase reading frequency if elevated response read.

Remarks: _____

Drilling Area Background (ppm):

Converted to Well: Yes No

Well I.D. #: BPOW4-2



BORING LOG

PROJECT NAME: NWIRP Bethpage
 PROJECT NUMBER: N4037
 DRILLING COMPANY: Uni-Tech
 DRILLING RIG: FAILING 1500

BORING No.: BPOW4-2
 DATE: 6/19/03
 GEOLOGIST: Conti
 DRILLER: J BLEMINGS

Sample No. and Type or RQD	Depth (FL) or Run No.	Blows / 6" or RQD (%)	Sample Recovery / Sample Length	Lithology Change (Depth/Ft.) or Screened Interval	MATERIAL DESCRIPTION			U S C S *	Remarks	PID/FID Reading (ppm)								
					Soil Density/ Consistency or Rock Hardness	Color	Material Classification			Sample	Sampler BZ	Borehole**	Driller BZ**					
	150																	
S ₂	152	100/6	.5/5		V DENSE	BRN	SAND-SOME GRAVEL TR WHITE CLAY	SP	WET			0						0
	1440																	
	1500	160																0
	1520	170																0
	1540	180																0
	1600	190																0
	1620	200																0

* When rock coring, enter rock brokenness.

** Include monitor reading in 6 foot intervals @ borehole. Increase reading frequency if elevated response read.

Remarks: _____

Drilling Area
 Background (ppm):

Converted to Well: Yes No Well I.D. #: BPOW4-2



BORING LOG

PROJECT NAME: NWIRP Bethpage
 PROJECT NUMBER: N4037
 DRILLING COMPANY: Uni-Tech
 DRILLING RIG: FAILING 1500

BORING No.: BPOW4-2
 DATE: 6/19/03 → 6/20/03
 GEOLOGIST: Conti
 DRILLER: J. BLEMINGS

Sample No. and Type or ROD	Depth (FL) or Run No.	Blows / 6" or ROD (%)	Sample Recovery / Sample Length	Lithology Change (Depth/FL) or Screened Interval	MATERIAL DESCRIPTION			U S C S *	Remarks	PID/FID Reading (ppm)									
					Soil Density/ Consistency or Rock Hardness	Color	Material Classification			Sample	Sampler BZ	Borehole**	Driller BZ**						
	200																		0
S-3	210	50	2/2																
K640	212	28	32		V DENSE GRAY	BRN TO GRAY	F/M SAND - TR CLAY SP SEAM ≈ 211' ≈ 2" THICK	SP	WET		0								0
	220									HT SOME CLAY									0
	230									REACHED 230' ON 6/19/03 MORE CLAY NOTICED ≈ 230' IN CUTTINGS.									0
	240																		0
	250																		0

6/19
6/20

* When rock coring, enter rock brokenness.
 ** Include monitor reading in 6 foot intervals @ borehole. Increase reading frequency if elevated response read.

Remarks: _____

Drilling Area Background (ppm): 0

Converted to Well: Yes No Well I.D. #: BPOW4-2



BORING LOG

PROJECT NAME: NWIRP Bethpage
 PROJECT NUMBER: N4037
 DRILLING COMPANY: Uni-Tech
 DRILLING RIG: FAILING 1500

BORING No.: BPOW4-2
 DATE: 6/20/03
 GEOLOGIST: Conti
 DRILLER: J BLEMINGS

Sample No. and Type or RQD	Depth (Ft.) or Run No.	Blows / 6" or RQD (%)	Sample Recovery / Sample Length	Lithology Change (Depth/Ft.) or Screened Interval	MATERIAL DESCRIPTION			U S C S *	Remarks	PID/FID Reading (ppm)			
					Soil Density/ Consistency or Rock Hardness	Color	Material Classification			Sample	Sampler BZ	Borehole**	Driller BZ**
5-4 0	250	28 38	1.5/2.0		V DENSE	MOTTLED ORANGE BRN GRAY	SILTY F/M SAND	SM	WET/MICACEOUS	0			0
0945		109/6					SOME CLAY IN "WASH" PORTION OF SAMPLE.						
	260												0
	270												0
	280												0
	290												0
	300												0

* When rock coring, enter rock brokenness.

** Include monitor reading in 6 foot intervals @ borehole. Increase reading frequency if elevated response read.

Remarks: _____

Drilling Area
 Background (ppm):

Converted to Well: Yes No

Well I.D. #: BPOW4-2



BORING LOG

PROJECT NAME: NWIRP Bethpage
 PROJECT NUMBER: N4037
 DRILLING COMPANY: Uni-Tech
 DRILLING RIG: FALLING 1500

BORING No.: BPOW4-2
 DATE: 6/20/03
 GEOLOGIST: Conti
 DRILLER: J BLEMINGS

Sample No. and Type or RQD	Depth (Ft.) or Run No.	Blows / 6" or RQD (%)	Sample Recovery / Sample Length	Lithology Change (Depth/Ft.) or Screened Interval	MATERIAL DESCRIPTION			U S C S *	Remarks	PID/FID Reading (ppm)										
					Soil Density/ Consistency or Rock Hardness	Color	Material Classification			Sample	Sampler BZ	Borehole**	Driller BZ**							
	300																			
	310																			
	1145	311	100%	4/5	V DENSE	GRAY	SILTY F/M SAND	SP	WET			0								0
							TR GRAVEL													
	1200	320																		
	1230	330																		
	1300	340																		
	350																			

6/20
6/23

* When rock coring, enter rock brokeness.

** Include monitor reading in 6 foot intervals @ borehole. Increase reading frequency if elevated reponse read.

Remarks: _____

Drilling Area Background (ppm):

Converted to Well: Yes No

Well I.D. #: BPOW4-2



BORING LOG

PROJECT NAME: NWIRP Bethpage
 PROJECT NUMBER: N4037
 DRILLING COMPANY: Uni-Tech
 DRILLING RIG: FAILING 1500

BORING No.: BPOW4-2
 DATE: 6/23/03
 GEOLOGIST: Conti
 DRILLER: J BLENNINGS

Sample No. and Type or RQD	Depth (Ft.) or Run No.	Blows / 6" or RQD (%)	Sample Recovery / Sample Length	Lithology Change (Depth/Ft.) or Screened Interval	MATERIAL DESCRIPTION			U S C S *	Remarks	PID/FID Reading (ppm)								
					Soil Density/ Consistency or Rock Hardness	Color	Material Classification			Sample	Sampler BZ	Borehole**	Driller BZ**					
	350																	
S _e ⁶ 1345	351	50 50	1/1		V STIFF / HARD	BRN GRAY	SILTY CLAY	CL	MOIST VERY HARD - WAS DIFFICULT TO PRY LOOSE FROM SPOON					0				0
	360																	
	1400	370																
	1430	380																
	1500	390																
	1515	400																

* When rock coring, enter rock brokenness.

** Include monitor reading in 6 foot intervals @ borehole. Increase reading frequency if elevated response read.

Remarks: _____

Drilling Area
 Background (ppm):

Converted to Well: Yes No Well I.D. #: BPOW4-2



BORING LOG

PROJECT NAME: NWIRP Bethpage
 PROJECT NUMBER: N4037
 DRILLING COMPANY: Uni-Tech
 DRILLING RIG: FAILING 1500

BORING No.: BPOW4-2
 DATE: 6/23/03
 GEOLOGIST: Conti
 DRILLER: J BLEMINGS

Sample No. and Type or RQD	Depth (FL) or Run No.	Blows / 6" or RQD (%)	Sample Recovery / Sample Length	Lithology Change (Depth/FL) or Screened Interval	MATERIAL DESCRIPTION			U S C S *	Remarks	PID/FID Reading (ppm)								
					Soil Density/ Consistency or Rock Hardness	Color	Material Classification			Sample	Sampler BZ	Borehole**	Driller BZ**					
	400																	
	6-7 410																	
6/23/03	1550 411	100%	0.9/1		VDENSE /STIFF	GRAY	SANDY CLAY - STREAKS OF LIGNITE MATL	SC	MOIST MICACEOUS									
	1600 420						STILL IN SOME CLAY		(CUTTINGS)									
	1630 430																	
MON 6/23																		
6/24 TUE.																		
	0900 440																	
	0930 450																	

* When rock coring, enter rock brokenness.

** Include monitor reading in 6 foot intervals @ borehole. Increase reading frequency if elevated reponse read.

Remarks: _____

Drilling Area
 Background (ppm):

Converted to Well: Yes No

Well I.D. #: BPOW4-2



BORING LOG

PROJECT NAME: NWIRP Bethpage
 PROJECT NUMBER: N4037
 DRILLING COMPANY: Uni-Tech
 DRILLING RIG: FAILING 1500

BORING No.: BPOW 4-2
 DATE: 6/24/03
 GEOLOGIST: Conti
 DRILLER: J BLEMINGS

Sample No. and Type or RQD	Depth (Ft.) or Run No.	Blows / 6" or RQD (%)	Sample Recovery / Sample Length	Lithology Change (Depth/Ft.) or Screened Interval	MATERIAL DESCRIPTION			U S C S *	Remarks	PID/FID Reading (ppm)			
					Soil Density/ Consistency or Rock Hardness	Color	Material Classification			Sample	Sampler BZ	Borehole**	Driller BZ**
5-B 0930	450	100/6'	2/5		V DENSE	GRAY	SILTY F/M SAND	SM SP	WET MICACEOUS	0			0
0945	460												0
1000	470												0
1030	480												0
1100	490												0
500													

* When rock coring, enter rock brokenness.

** Include monitor reading in 6 foot intervals @ borehole. Increase reading frequency if elevated response read.

Remarks: _____

Drilling Area
 Background (ppm):

Converted to Well: Yes No Well I.D. #: BPOW 4-2



BORING LOG

PROJECT NAME: NWIRP Bethpage
 PROJECT NUMBER: N4037
 DRILLING COMPANY: Uni-Tech
 DRILLING RIG: FALLING 1500

BORING No.: BPOW 4-2
 DATE: 0124103
 GEOLOGIST: Conti
 DRILLER: J BLEMINGS

Sample No. and Type or RQD	Depth (Ft.) or Run No.	Blows / 6" or RQD (%)	Sample Recovery / Sample Length	Lithology Change (Depth/Ft.) or Screened Interval	MATERIAL DESCRIPTION			USCS*	Remarks	PID/FID Reading (ppm)								
					Soil Density/ Consistency or Rock Hardness	Color	Material Classification			Sample	Sampler BZ	Borehole**	Driller BZ**					
	500																	
																		0
5-9 e	510	100%			V DENSE	GRAY	F/M SAND - TR F SP WET			0								0
1130	511						GRAVEL TR BLACK STREAKS (LIGNITE)?		MICACEOUS									
	1200	520																0
	1230	530																0
	1245	540																0
	1300	550																0

* When rock coring, enter rock brokenness.

** Include monitor reading in 6 foot intervals @ borehole. Increase reading frequency if elevated reponse read.

Remarks: _____

Drilling Area Background (ppm): 0

Converted to Well: Yes No _____ Well I.D. #: BPOW 4-2



BORING LOG

PROJECT NAME: NWIRP Bethpage
 PROJECT NUMBER: N4037
 DRILLING COMPANY: Uni-Tech
 DRILLING RIG: FAILING 1500

BORING No.: BPOW4-2
 DATE: 6/24/03
 GEOLOGIST: Conti
 DRILLER: J BLEMINGS

Sample No. and Type or RQD	Depth (FT) or Run No.	Blows / 6" or RQD (%)	Sample Recovery / Sample Length	Lithology Change (Depth/FT) or Screened Interval	MATERIAL DESCRIPTION			U S C S *	Remarks	PID/FID Reading (ppm)									
					Soil Density/ Consistency or Rock Hardness	Color	Material Classification			Sample	Sampler BZ	Borehole**	Driller BZ**						
	550																		
S-10 e 1330	551	100% 16"	4/5		DENSE	GRAY	F/M SAND	SP	WET MICACEOUS	0									0
	560																		0
	570																		0
1430	580																		0
	590																		0
1500																			0
	600																		0

* When rock coring, enter rock brokenness.

** Include monitor reading in 6 foot intervals @ borehole. Increase reading frequency if elevated response read.

Remarks: _____

Drilling Area
 Background (ppm):

Converted to Well: Yes No Well I.D. #: BPOW4-2



BORING LOG

PROJECT NAME: NWIRP Bethpage
 PROJECT NUMBER: N4037
 DRILLING COMPANY: Uni-Tech
 DRILLING RIG: FALING 1500

BORING No.: BPOW4-2
 DATE: 6/24/03
 GEOLOGIST: Conti
 DRILLER: J BLEMINGS

Sample No. and Type or RQD	Depth (Ft.) or Run No.	Blows / 6" or RQD (%)	Sample Recovery / Sample Length	Lithology Change (Depth/Ft.) or Screened Interval	MATERIAL DESCRIPTION			U S C S *	Remarks	PID/FID Reading (ppm)										
					Soil Density/ Consistency or Rock Hardness	Color	Material Classification			Sample	Sampler BZ	Borehole**	Driller BZ**							
	600																			
	1530																			
	610	100																		
	1550	611	6"	5/5		DENSE	TAN GRAY	F/M SAND - SOME TAN SANDY CLAY - TOP 2" OF SPOON	SP/SM	WET ⇒ MOIST										
	620																			
	630																			
	640																			
6/24	650																			

* When rock coring, enter rock brokenness.

** Include monitor reading in 6 foot intervals @ borehole. Increase reading frequency if elevated response read.

Remarks: _____

Drilling Area Background (ppm):

Converted to Well: Yes No

Well I.D. #: BPOW4-2



BORING LOG

PROJECT NAME: NWIRP Bethpage
 PROJECT NUMBER: N4037
 DRILLING COMPANY: Uni-Tech
 DRILLING RIG: FAILING 1500

BORING No.: BPOW4-2
 DATE: 6/25/03
 GEOLOGIST: Conti
 DRILLER: J BLEMINGS

Sample No. and Type or RQD	Depth (Ft.) or Run No.	Blows / 6" or RQD (%)	Sample Recovery / Sample Length	Lithology Change (Depth/Ft.) or Screened Interval	MATERIAL DESCRIPTION			U S C S *	Remarks	PID/FID Reading (ppm)			
					Soil Density/ Consistency or Rock Hardness	Color	Material Classification			Sample	Sampler BZ	Borehole**	Driller BZ**
6/25 S-12 Q 0935	650 651	100% 6"	5.5		DENSE	GRAY	SAND AND GRAVEL TR CLAY	SW	WET ~ 3/4" Ø SUB ROUND GRAVEL	0			0
	1000	600											0
	670												0
	1015	680											0
	1030	680											0
	700												0

* When rock coring, enter rock brokenness.

** Include monitor reading in 6 foot intervals @ borehole. Increase reading frequency if elevated response read.

Remarks: _____

Drilling Area
 Background (ppm):

Converted to Well: Yes No Well I.D. #: BPOW 4-2



BORING LOG

PROJECT NAME: NWIRP Bethpage
 PROJECT NUMBER: N4037
 DRILLING COMPANY: Uni-Tech
 DRILLING RIG: FALING 1500

BORING No.: BPOW4-2
 DATE: 6/25/03
 GEOLOGIST: Conti
 DRILLER: J BLEMINGS

Sample No. and Type or RQD	Depth (Ft.) or Run No.	Blows / 6" or RQD (%)	Sample Recovery / Sample Length	Lithology Change (Depth/Ft.) or Screened Interval	MATERIAL DESCRIPTION			U S C S *	Remarks	PID/FID Reading (ppm)						
					Soil Density/Consistency or Rock Hardness	Color	Material Classification			Sample	Sampler BZ	Borehole**	Driller BZ**			
1100	700														0	
1115	710				DENSE GRAY		COARSE SAND-SOME SP F/M SAND		WET - FROM CUTTINGS NO SPOON HERE							0
	720															0
	730															0
	740				B L A N K											0
	742						SANDY SOME V CLAY @ 742' NOTED THEN		DRILLER NOTED SOME CLAY AT 742 W STREAKS TO 747.							0
1500	750						F TO C SAND									0

* When rock coring, enter rock brokenness.
 ** Include monitor reading in 6 foot intervals @ borehole. Increase reading frequency if elevated response read.

Remarks: _____ Drilling Area Background (ppm):

Converted to Well: Yes No Well I.D. #: BPOW4-2



BORING LOG

PROJECT NAME: NWIRP Bethpage
 PROJECT NUMBER: N4037
 DRILLING COMPANY: Uni-Tech
 DRILLING RIG: FAILING 1500

BORING No.: BPOW4-2
 DATE: 6/25/03
 GEOLOGIST: Conti
 DRILLER: J BLEMINGS

Sample No. and Type or RQD	Depth (Ft.) or Run No.	Blows / 6" or RQD (%)	Sample Recovery / Sample Length	Lithology Change (Depth/Ft.) or Screened Interval	MATERIAL DESCRIPTION			U S C S *	Remarks	PID/FID Reading (ppm)					
					Soil Density/ Consistency or Rock Hardness	Color	Material Classification			Sample	Sampler BZ	Borehole**	Driller BZ**		
	750			765	DENSE	GRAY	FIC SAND							0	
	1540	760													0
	770									NOTICED SOME CLAY IN CUTTINGS DRILLER ALSO NOTED CLAY @ 770'±					0
	780								GAMMA LOG TO 775.					0	


* When rock coring, enter rock brokenness.

** Include monitor reading in 6 foot intervals @ borehole. Increase reading frequency if elevated response read.

Remarks: _____

Drilling Area Background (ppm):

Converted to Well: Yes No Well I.D. #: BPOW4-2



1. Pipe initially @ 755' ± 20' INTO SCREEN
Start at top - raise & lower pipe @ every
1000 gallons



Tetra Tech NUS, Inc.

MONITORING WELL DEVELOPMENT RECORD

Page 1 of 4

Well: BPOW4-2 Depth to Bottom (ft.): 765' ± BGS Responsible Personnel: Conti
 Site: NWIRP Static Water Level Before (ft.): 241.65 Drilling Co.: Uni-Tech
 Date Installed: 7-7-03 Project Name: NWIRP Bethpage-Outpost Wells
 Date Developed: 7/28/03 Screen Length (ft.): 30' w/ 10' BLANK Project Number: N4037
 Dev. Method: AIR LIFT/PUMP Specific Capacity: _____
 Pump Type: _____ Casing ID (in.): _____

* COULD NOT GET PROBE PAST THE DEV PIPE JOINTS.

LAMOTTE

Time	Estimated Flow Rate (GPM)	Cumulative Water Volume (Gal.)	Water Level Readings (Ft. below TOC)	Temperature (Degrees C)	pH	Specific Conductance (Units mS/cm)	Turbidity (NTU)	Remarks (odor, color, etc.)
1600	—	—	41 ±	—	—	—	—	BRN GRAY - TURBID
1700	30	(1400)	NA*	13.46	4.47	.172	999	
0810	START	AIR LIFT	7/29/03					
0840	~ 40	~ 1200/200	NA	14.15	4.62	.074	999	BRN GRAY - TURBID
0845	~ 40	(1400)	LOAD 2	TAKEN TO FRAC TANK.				
0920	START	AIR LIFT	INTO 2000 GAL TANK					
0950	~ 33	1000/300	NA	14.66	4.73	.060	999	BRN GRAY - TURBID
1015	~ 33	(1800)/400	NA	15.24	4.63	.053	999	" " "
1020	START	AIR LIFT	INTO 1500 GAL TANK					
1050	~ 37	1100/5700	NA	14.65	4.79	.049	999	" " " 1100
1100	~ 35	(1400)/6000	LOAD 4	TAKEN TO FRAC TANK				
1115	START	AIR LIFT	INTO 2000 GALLON TANK					
1145	~ 33	1000/7000	NA	14.41	4.81	.048	999	" " " 1000
1210	~ 33	(1800) 7000	NA	14.49	4.74	.049	999	650
1255	START	AIR LIFT	INTO 1500 GALLON TANK					
1335	~ 35	(1400) 9200	NA	14.31	4.91	.059	999	" " " 550
1350	START	AIR LIFT	INTO 3000 GALLON TANK					
1420	~ 33	1000	NA	14.68	4.88	.042	760	450

7/28

7/28

7/29

F 7



Tetra Tech NUS, Inc.

MONITORING WELL DEVELOPMENT RECORD

Well: BF04-2 Depth to Bottom (ft.): 96.5 ± 8.65 Responsible Personnel: Conti
 Site: NWIRP Static Water Level Before (ft.): 36.5 GGS Drilling Co.: Uni-Tech
 Date Installed: 7-7-03 Static Water Level After (ft.): _____ Project Name: NWIRP Bethpage-Outpost Wells
 Date Developed: 7/29/03 Screen Length (ft.): 30' w/ 10' BLANK Project Number: N4037
 Dev. Method: AIR LIFT / PUMP Specific Capacity: _____
 Pump Type: _____ Casing ID (in.): 3 13/16"

HORIBA[®] TURBIDITY RDS SUSPECT / USE LAMOTTE →

Time	Estimated Flow Rate (GPM)	Cumulative Water Volume (Gal.)	Water Level Readings (Ft. below TOC)	Temperature (Degrees C)	pH	Specific Conductance (Units mS/cm)	Turbidity (NTU) *	Remarks (odor, color, etc.)
1445	~ 33	(1800) 11000	NA	14.91	5.08	.042	999	LT GRAY SL TURBID 400
1450	START AIR LIFT INTO 1500 GAL TANK.							
1520	~ 37	1100	NA	14.68	5.30	.045	982	" " " " 400
1530	~ 35	(1400) 12400						
1535	START AIR LIFT INTO 2000 GAL							
1605	~ 33	1000	NA	15.33	5.46	.044	859	" " " " 370
1630	~ 33	(1800) 14200	NA	16.40	5.52	.045	818	" " " " 340
1635	START AIR LIFT INTO 1500 GAL TANK							
1715	~ 35	(1400) 15600	NA	16.23	5.47	.049	819	" " " " 300
0825	START AIR LIFT INTO 2000 GAL							ADDED 15' MORE OF FOODS AND SURGE EVERY 1000 GALLONS
0905	~ 30	900	NA	13.89	5.17	.083	999	GRAY & TURBID OFF SCALE
0935	~ 30	(1800) 17400	NA	14.91	5.16	.060	975	" & SL TURBID 500
1010	START AIR LIFT INTO 1500 GAL							
1055	~ 31	(1400) 18800		14.42	5.35	.057	999	" " " " 700
1100	START AIR LIFT INTO 2000 GAL							
1130	~ 33	1000	NA	15.07	5.45	.051	683	" & SL TURBID 270
1200	30	(1900) 20600	NA	15.55	5.53	.048	660	" & SL " 240

7/29

F 00

7/30



Tetra Tech NUS, Inc.

MONITORING WELL DEVELOPMENT RECORD

Well: 3604-2 Depth to Bottom (ft.): 765 ± BGS Responsible Personnel: Conti
 Site: NWIRP Static Water Level Before (ft.): 36.5 BGS Drilling Co.: Uni-Tech
 Date Installed: 7/7/03 Static Water Level After (ft.): _____ Project Name: NWIRP Bethpage-Outpost Wells
 Date Developed: 7/28/03 Screen Length (ft.): 30' + 10' BLANK Project Number: N4037
 Dev. Method: AIR LIFT/PUMP Specific Capacity: 765 → 745 SCREEN
 Pump Type: _____ Casing ID (in.): 3 13/16" ID 735 → 725 SCREEN

Time	Estimated Flow Rate (GPM)	Cumulative Water Volume (Gal.)	Water Level Readings (Ft. below FOG)	Temperature (Degrees C)	pH	Specific Conductance (Units/cm)	Turbidity (NTU)	Remarks (odor, color, etc.)
1240	START	AIR LIFT INTO	1500 GALLON					LAMOTHE
1320	35	(1400) 22 ⁰⁰⁰	39.5	15.76	5.59	0.055	627	GRAY/SL TURBID
1335	START	AIR LIFT INTO	2000 GAL					
1405	30	900	40.2	14.86	5.53	0.045	651	230
1435	30	(1800) 23 ⁸⁰⁰	40.2	14.95	5.56	0.042	649	" " " NO SED 220
1440	START	AIR LIFT	INTO 1500 GAL					
1520	35	(1400) 25 ²⁰⁰	40.5	14.84	5.67	0.043	571	" " " NO SED 200
1520	START	AIR LIFT	INTO 2000 GALLON					
1550	33	1000	40.5	14.89	5.71	0.044	542	" " " NO SED 200
1620	30	(1800) 27 ⁰⁰⁰	40.5	14.77	5.69	0.041	571	" " " NO SED 160
0810	START	AIR LIFT	INTO 2000 GALLON					WL @ 36.5 BGS 5' OFF BOTM 760-765
0840	30	1000	38	14.20	4.49	0.081	834	390
0915	28	(1800) 28 ⁸⁰⁰	37.5	14.66	4.64	0.051	610	GRAY SL TURBID 230
0920	START	AIR LIFT	INTO 1500 GALLON					
0955	40	(1400) 30 ²⁰⁰	38	14.79	4.76	0.052	506	" " " 160
1000	START	AIR LIFT	INTO 2000 GALLON					
1030	36	1100	37.5	15.12	4.84	0.042	464	" " " 130
1100	30	(1800) 32 ⁰⁰⁰	37.5	19.93*	4.85	0.041	350	" " " 140

*NO SURE, WHY IT INCREASED
 W/ DOUBLE CHECKED

7/30
 7/31



Tetra Tech NUS, Inc.

MONITORING WELL DEVELOPMENT RECORD


Well: BPOW4-2 Depth to Bottom (ft.): 76.5 ± 8.5 Responsible Personnel: Conti
 Site: NWIRP Static Water Level Before (ft.): 36.5 Drilling Co.: Uni-Tech
 Date Installed: 7-7-03 Static Water Level After (ft.): 39.5 Project Name: NWIRP Bethpage-Outpost Wells
 Date Developed: 7/28/03 → 7/31/03 Screen Length (ft.): 30' + 10' BLANK Project Number: N4037
 Dev. Method: AIR LIFT/PUMP Specific Capacity: 30 GPM @ 3' DD
 Pump Type: GRUNDFOS SUB Casing ID (in.): 3 3/16



Time	Estimated Flow Rate (GPM)	Cumulative Water Volume (Gal.)	Water Level Readings (Ft. below TOC)	Temperature (Degrees C)	pH	Specific Conductance (Units mS/cm)	Turbidity (NTU)	Remarks (odor, color, etc.)
1110	START AIR LIFT INTO	1500 GALLON TANK						
1145	40	(1400) 33,400	38.5	15.28	4.94	0.040	416	GRAY V. SL TURBID 130
1235	START AIR LIFT INTO	2000 GAL TANK						
1325	33	(1000)	39.5	15.65	4.93	0.046	469	" " " 130
1355	30	(1800) 35,200	39.5	15.45	4.95	0.042	445	" " " 130
				AIR LIFT DEV.		COMPLETE		
1200	START	DEV BY PUMP INTO	2000 GAL					INITIAL WL. 27.5 ± G/S
1230	17	500	29.0	14.95	4.78	0.109	999	GRAY - TURBID OFF SCALE
1300	15	900	29.0	15.73	4.82	0.072	"	" " " 450
1330	14	1200	29.0	15.24	4.87	0.059	908	" SL " 300
1400	12.5	1500	29.0	15.62	4.98	0.058	706	" " " 190
1430	12	(1800) 37,000	29.0	15.59	4.80	0.061	784	" " " 160
1530	START	PUMP INTO	2000 GAL.					
1600	13 ±	400	29.0	15.15	4.93	0.056	685	" " " 150
1630	13	800	29.0	14.85	4.96	0.054	669	" " " 140
1700	13	(1200) 38,200	29.0	14.95	4.95	0.056	675	" " " 145


745-750
730-735
725-730

AQUA TERRA GEOPHYSICS INC


CO		WELL		FLD		CTY		STE		FILING No	
PERMANENT DATUM		COMPANY		UNITECH DRILLING		WELL ID		BPOW 4-2		FIELD	
LOG MEAS. FROM		GROUND SURFACE		ABOVE PERM. DATUM		COUNTRY		NASSAU		STATE	
DRILLING MEAS. FROM		DATE		JUNE 26, 2003		TYPE FLUID IN HOLE		BENTONITE		OTHER SERVICES	
RUN No		TYPE LOG		780 FEET		DENSITY					
DEPTH-DRILLER		DEPTH-LOGGER		775 FEET		MAX. REC. TEMP.					
BTM LOGGED INTERVAL		TOP LOGGED INTERVAL									
OPERATING RIG TIME		RECORDED BY		BENJAMIN RICE							
WITNESSED BY		STAN CONTI									
RUN NO.		BOREHOLE RECORD		CASING RECORD		WGT.		FROM		TO	
12 INCH		GROUND SURFACE		94 FEET		10 INCH		PVC		GROUND SURFACE	
8 INCH		94 FEET		TOTAL DEPTH						94 FEET	











160
170
180
190
200
210
220
230
240
250
260






154







490
500
510
520
530
540
550
560
570
580
590



156





7P
 JUL 1965
 1965
 111



APPENDIX J
CHAIN-OF-CUSTODY FORMS





TETRA TECH NUS, INC.

CHAIN OF CUSTODY

NUMBER BPOW-080503

PAGE 1 OF 1

PROJECT NO: N14057		SITE NAME: NWIRP BETHPAGE		PROJECT MANAGER AND PHONE NUMBER: D. BRAYACK 412 921 8375		LABORATORY NAME AND CONTACT: STL LAB / V. BOCTOT (412) 820 8380	
SAMPLERS (SIGNATURE): <i>Splonda</i>		FIELD OPERATIONS LEADER AND PHONE NUMBER: S CONTI 412 931 8422		ADDRESS: 450 WILLIAM PITT WAY		CITY, STATE: PITTSBURGH, PA. 15238	
STANDARD TAT <input type="checkbox"/>		CARRIERWAYBILL NUMBER: FED EX AB# 8412 3491 3948		CONTAINER TYPE: PLASTIC (P) or GLASS (G)		PRESERVATIVE USED: 40% HCL 40% HNO3 40% H2O2	
RUSH TAT <input type="checkbox"/>		DATE: <input type="checkbox"/> 24 hr. <input type="checkbox"/> 48 hr. <input type="checkbox"/> 72 hr. <input type="checkbox"/> 7 day <input type="checkbox"/> 14 day		MATRIX		TYPE OF ANALYSIS	
DATE	TIME	SAMPLE ID	MATRIX	GRAB (G) COMP (C)	No. OF CONTAINERS	TOTAL CASMIUM (500ml) 40 ml Vial	COMMENTS
8/5	0730	BP-IB-080503	AQ	G	2	TSS (500ml)	
8/5	0750	BP-IDW-BT1-080503	AQ	G	5		FROM BAKER TANK A201 (1)
8/5	0810	BP-IDW-BT2-080503	AQ	G	5		FROM BAKER TANK A224 (2)
8/4	1700	BP-BPOW4-2-DEV	AQ/GW	G	3		TAKEN AT BPOW4-2 - FROM PUMP, DURING FINAL STAGE OF DEVELOPMENT.
1. RELINQUISHED BY		DATE		TIME		DATE	
SPLONDA		8/5/03		1200		1. RECEIVED BY	
2. RELINQUISHED BY		DATE		TIME		DATE	
						2. RECEIVED BY	
3. RELINQUISHED BY		DATE		TIME		DATE	
						3. RECEIVED BY	
COMMENTS: CAU D BRAYACK FOR QUESTIONS - SEND RESULTS TO TENUS/BRAYACK							
DISTRIBUTION: WHITE (ACCOMPANIES SAMPLE) YELLOW (FIELD COPY) PINK (FILE COPY)							



TETRA TECH NUS, INC.

CHAIN OF CUSTODY

NUMBER **BP0W-091003**

PAGE **1** OF **1**

PROJECT NO: N14037 SAMPLERS (SIGNATURE): <i>SJ Contri</i>		SITE NAME: NWIRP BETHPAGE		PROJECT MANAGER AND PHONE NUMBER DAVE BRAYACK 412 921 8375		LABORATORY NAME AND CONTACT: 412 830 8380 STL LAB / N BOSTON	
STANDARD TAT <input type="checkbox"/> RUSH TAT <input type="checkbox"/>		24 hr. <input type="checkbox"/> 48 hr. <input type="checkbox"/> 72 hr. <input type="checkbox"/> 7 day <input type="checkbox"/> 14 day <input type="checkbox"/>		FIELD OPERATIONS LEADER AND PHONE NUMBER SJ CONTI 412 921 8422		ADDRESS 450 WILLIAM PITT WAY	
CARRIERWAYBILL NUMBER FED EX # 8412 2491 1625		CARRIERWAYBILL NUMBER 8412 2491 1625		CITY, STATE PGH. PA 15238			
MATRIX		GRAB (G) COMP (C)		NO. OF CONTAINERS		TYPE OF ANALYSIS VOLS (40ml VIALS) TOTAL CADMIUM (ECON) TOTAL CHROME (ECON) TSS (50 ml)	
DATE YEAR TIME		SAMPLE ID		PRESERVATIVE USED		COMMENTS	
9/10	0700	BP-TB-091003	AG G	2	AOC HCL		
9/11	0730	BP-IDW-A201-091103	AG G	5	AOC HCL		
9/11	0800	BP-IDW-A204-091103	AG 2G	5	AOC HCL		
9/10	1030	BP-BP0W2-2-DEV	GW G	3	AOC HCL		DEV WATER ETC BAKER TANK A201 DEV WATER, SUMP ETC A204 FROM USEL BP0W2-2 DURING END OF DEV.
9/10	1300	BP-BP0W2-1-DEV	GW G	3	AOC HCL		FROM BP0W2-1 END OF DEV.
1. RELINQUISHED BY <i>SJ Contri</i>		DATE 9/11/03		TIME 1200		1. RECEIVED BY FED EX	
2. RELINQUISHED BY		DATE		TIME		2. RECEIVED BY	
3. RELINQUISHED BY		DATE		TIME		3. RECEIVED BY	

160



TETRA TECH NUS, INC.

CHAIN OF CUSTODY

NUMBER BROW-100803

PAGE 1 OF 1

PROJECT NO: N4037
SAMPLERS (SIGNATURE) NWIRP BETHPSE

SITE NAME: NWIRP BETHPSE
PROJECT MANAGER AND PHONE NUMBER: D. BRAYACK 412 921 8375
FIELD OPERATIONS LEADER AND PHONE NUMBER: S CONTI 412 921 8432

LABORATORY NAME AND CONTACT: STL LAB / V. BORTOT
ADDRESS: 450 WILLIAM PITT WAY
CITY, STATE: PITTSBURGH PA 15238

STANDARD TAT
RUSH TAT 24 hr. 48 hr. 72 hr. 7 day 14 day

CARRIERWAYBILL NUMBER: FEDEX # 8412 2491 1485

CONTAINER TYPE: 40L (40M/VOR)
PRESERVATIVE USED: HCL

DATE	TIME	SAMPLE ID	MATRIX	GRAB (G)	COMP (G)	No. OF CONTAINERS	TYPE OF ANALYSIS	VOCS (40M/VOR)	TCLP METALS 80X	GRO (40M/VOR)	TOTAL METALS	TOTAL SOLIDS / PH (95% BTD)	COMMENTS
10/8	0830	BP-TB-100803	AP	G	G	2	VOCS (40M/VOR)	HCL					RE-THRU PUMP & TUBING
10/9	1200	BP-RB-100903	AP	G	G	2	VOCS (40M/VOR)	HCL					RE-SAMPLE FROM BROW-100803 2-1
10/9	1130	BROW-1-100903	GW	G	G	3	VOCS (40M/VOR)	HCL					RE-SAMPLE FROM BROW-100803
			GW	G	G	3	VOCS (40M/VOR)	HCL					RE-SAMPLE FROM BROW-100803
10/8	0915	BP-IDW-SB-9544	SOIL	G	G	3	VOCS (40M/VOR)	HCL					SURGE BOX 9544 (CUTTINGS)
10/8	0945	BP-IDW-SB-0312	SOIL	G	G	3	VOCS (40M/VOR)	HCL					0312 (CUTTINGS)
10/8	1000	BP-IDW-SB-9523	SOIL	G	G	3	VOCS (40M/VOR)	HCL					9523 (CUTTINGS)
10/8	1030	BP-IDW-SB-0042	AP	G	G	9	VOCS (40M/VOR)	HCL					THIN MUD SB 3-2, 3-1 (0042)
							THIN MUD						
							"THINNED OUT MUD"						

1. RELINQUISHED BY: S Conto
DATE: 10/9/03 TIME: 1400
2. RECEIVED BY: FED EX
DATE: DATE TIME: TIME
3. RECEIVED BY: DATE TIME: TIME

COMMENTS: 9544 = MOIST SAND - TAN BEN
DISTRIBUTION: WHITE (ACCOMPANIES SAMPLE)

FIELD PH (0042): 798
PINK (FILE COPY)
YELLOW (FIELD COPY)
FORM NO. TINUS-001 3/99



TETRA TECH NUS, INC.

CHAIN OF CUSTODY

NUMBER BROW-102103

PAGE 1 OF 1

PROJECT NO: N4037
SITE NAME: NWIRP BETHPAGE
SAMPLERS (SIGNATURE)

PROJECT MANAGER AND PHONE NUMBER
DAVE BRAYACK - 412 921 8375
FIELD OPERATIONS LEADER AND PHONE NUMBER

LABORATORY NAME AND CONTACT:
STL LAB / V. FORST
ADDRESS
412 820 8380

SI CONTI - 412 921 8422
CARRIERWAYBILL NUMBER
FED EX # 8316 7332 9630

450 WILLIAM PITT WAY
CITY, STATE
PITTSBURGH PA 15238

STANDARD TAT
RUSH TAT 24 hr. 48 hr. 72 hr. 7 day 14 day

CONTAINER TYPE
PLASTIC (P) or GLASS (G)
PRESERVATIVE USED

DATE YEAR	TIME	SAMPLE ID	MATRIX	GRAB (G) COMP (C)	No. OF CONTAINERS	TYPE OF ANALYSIS	COMMENTS
10/21	0800	BP-TB-102103	AO	G	2	AOCL 400 TOTAL CADMIUM 500 TOTAL CHROME 500 TSS (250ml)	
10/21	1000	BP-BROW 3-2-DEV	GW	G	3	VOCs (40ml Vials) AOCL 400	FROM BROW 3-2 END OF DEV
10/21	1145	BP-BROW 3-1-DEV	GW	G	3	VOCs (40ml Vials) AOCL 400	FROM BROW 3-1 END OF DEV
10/22	0820	BP-IDW-A224-102203	AW GW	G	5		DEV WATER 2-1, 3-2
10/22	0840	BP-IDW-A201-102203	AW GW	G	5		DEV WATER 2-1, 3-2

1. RELINQUISHED BY	DATE	TIME	1. RECEIVED BY	DATE	TIME
SI Contt	10/22/03	1600	FED EX		
2. RELINQUISHED BY			2. RECEIVED BY		
3. RELINQUISHED BY			3. RECEIVED BY		



TETRA TECH NUS, INC.

CHAIN OF CUSTODY

NUMBER BPOW-120103

PAGE 1 OF 1

PROJECT NO: N4037
SITE NAME: NWIRP BETHAGE
SAMPLERS (SIGNATURE)

SJ Conda

STANDARD TAT
RUSH TAT
 24 hr. 48 hr. 72 hr. 7 day 14 day

PROJECT MANAGER AND PHONE NUMBER
D. BRAYACK 412 921 8375
FIELD OPERATIONS LEADER AND PHONE NUMBER
S CONTI 412 921 8422
CARRIER/WAYBILL NUMBER
FED EX AC # 8412 2491 1514

LABORATORY NAME AND CONTACT: STL LAB/V. BORTOT
ADDRESS
450 WILLIAM PIT WAY
CITY, STATE
PITTSBURGH, PA 15238

CONTAINER TYPE
PLASTIC (P) or GLASS (G)
PRESERVATIVE USED
HCL

NO. OF CONTAINERS
MATRIX
TYPE OF ANALYSIS
VOCs (40 ml)

DATE	TIME	SAMPLE ID	MATRIX	GRAB (G)	COMP (G)	NO. OF CONTAINERS	COMMENTS
12/1	1100	BP-TB-120103	AQ	G	G	2	TRIP BLANK
12/2	1220	BP-BPOW1-3-DEV	GW	G	G	3	END OF DEV STAGE / PUMPING
12/2	0930	BP-BPOW1-2-DEV	GW	G	G	3	"
12/1	1200	BP-BPOW1-1-DEV	GW	G	G	3	"
12/2	1400	BPOW2-1-120203	GW	G	G	3	RE-SAMPLE OF BPOW 2-1 RE-TURBIDITY AND TUBING
12/2	1245	BP-RB-120203	AQ	G	G	2	

1. RELINQUISHED BY	DATE	TIME	1. RECEIVED BY	DATE	TIME
<i>SJ Conda</i>	12/2/03	1700	FED EX		
2. RELINQUISHED BY	DATE	TIME	2. RECEIVED BY	DATE	TIME
3. RELINQUISHED BY	DATE	TIME	3. RECEIVED BY	DATE	TIME

COMMENTS



TETRA TECH NUS, INC.

CHAIN OF CUSTODY

NUMBER BPOW-121503

PAGE 1 OF 1

PROJECT NO: N14037		SITE NAME: NWIRE BETHPAUSE		PROJECT MANAGER AND PHONE NUMBER: DAVE BRAYACK 412 921 8375		LABORATORY NAME AND CONTACT: SIL LAB / V. BORTOT	
SAMPLERS (SIGNATURE) <i>SJ Conata</i>				FIELD OPERATIONS LEADER AND PHONE NUMBER: SJ CONTI 412 921 8422		ADDRESS: 450 WILLIAM PITT WAY	
STANDARD TAT <input type="checkbox"/> RUSH TAT <input type="checkbox"/>		72 hr. <input type="checkbox"/> 7 day <input type="checkbox"/> 14 day <input type="checkbox"/>		CARRIER/WAYBILL NUMBER: FED EX # 8412 2491 4039		CITY, STATE: PITTSBURGH PA 15238	
DATE YEAR MONTH		SAMPLE ID		MATRIX		TYPE OF ANALYSIS	
12/13 1400		BP-TB-121503		AQ G 2		VOCs 40 ml VOA	
12/13 1535		BP-BPOW-4-1-DEV		GW G 3		PRESERVATIVE USED AGC HCL	
						NO. OF CONTAINERS	
						COM (G)	
						GRAB (G)	
						ALSO: INCLUDED SOME UNUSED SOIL SAMPLE JARS.	
						TRIP BLANK DURING FINAL STAGE OF DEV	
						COMMENTS	

1. RELINQUISHED BY	DATE	TIME	1. RECEIVED BY	DATE	TIME
<i>SJ Conata</i>	12/16/03	1200	FED EX		
2. RELINQUISHED BY	DATE	TIME	2. RECEIVED BY	DATE	TIME
3. RELINQUISHED BY	DATE	TIME	3. RECEIVED BY	DATE	TIME

COMMENT: GW FROM FINAL STAGE OF DEV.

DISTRIBUTION: WHITE (ACCOMPANIES SAMPLE) YELLOW (FILE COPY) PINK (FILE COPY)

FORM NO. TINIUS-001 3/99

APPENDIX K
SAMPLE LOG SHEETS





GROUNDWATER SAMPLE LOG SHEET

Project Site Name: NWIRP Bethpage
Project No.: N4037

Sample ID No.: BP-BP0W4-2-DEV
Sample Location: BP0W4-2
Sampled By: SJC
C.O.C. No.: BP0W-080503

- Domestic Well Data
- Monitoring Well Data
- Other Well Type: _____
- QA Sample Type: _____

- Type of Sample:
 Low Concentration
 High Concentration

SAMPLING DATA:

LAMORE

Date:	Color	pH	S.C.	Temp.	Turbidity	DO	ORP	Salinity
Time:	Visual	Standard	mS/cm	°C	NTU	mg/l	mV	
<u>8/4/03</u>	<u>CLEAR</u>	<u>4.95</u>	<u>-056</u>	<u>14.95</u>	<u>145</u>	<u>—</u>	<u>—</u>	<u>—</u>

PURGE DATA:

Date:	Volume	pH	S.C.	Temp. (C)	Turbidity	DO	ORP	Salinity
Method:								
Monitor Reading (ppm):								
Well Casing Diameter & Material Type:								
Total Well Depth (TD):								
Static Water Level (WL):								
One Casing Volume(gal/L):								
Start Purge (hrs):								
End Purge (hrs):								
Total Purge Time (min):								
Total Vol. Purged (gal/L):								

SAMPLE COLLECTION INFORMATION:

Analysis	Preservative	Container Requirements	Collected
Volatile Organic Compounds	<u>4°C/HCL</u>	<u>3 40 mL Glass Vials</u>	<input checked="" type="checkbox"/>

OBSERVATIONS / NOTES:

Hydropunch advanced to sample depth and screen exposed at: NA hrs. TDS = NA

Sample depth (screened interval) = from NA to NA ft.

Screen exposed to formation for NA minutes.

Depth of borehole prior to advancing hydropunch = NA ft.

SAMPLED FROM PUMP - DURING LAST STAGE OF DEVELOPMENT

Circle if Applicable:

<input type="checkbox"/> MS/MSD	Duplicate ID No.:
---------------------------------	-------------------

Signature(s):
SJC



GROUNDWATER SAMPLE LOG SHEET

Project Site Name: NWIRP Bethpage
Project No.: N4037

Sample ID No.: BP-8P0W2-1-DEV
Sample Location: BPOW2-1
Sampled By: SJC
C.O.C. No.: BPOW-091003

- Domestic Well Data
- Monitoring Well Data
- Other Well Type: _____
- QA Sample Type: _____

- Type of Sample:
- Low Concentration
 - High Concentration

SAMPLING DATA:

HORIBA/LANDRE

Date:	Color	pH	S.C.	Temp.	Turbidity	DO	ORP	Salinity
Time:	Visual	Standard	mS/cm	°C	NTU	mg/l	mV	
<u>9/10/03</u>	<u>CLEAR</u>	<u>5.64</u>	<u>118</u>	<u>13.38</u>	<u>135/14</u>	<u>-</u>	<u>-</u>	<u>-</u>

PURGE DATA:

Date:	Volume	pH	S.C.	Temp. (C)	Turbidity	DO	ORP	Salinity
Method:								
Monitor Reading (ppm):								
Well Casing Diameter & Material Type:								
Total Well Depth (TD):								
Static Water Level (WL):								
One Casing Volume(gal/L):								
Start Purge (hrs):								
End Purge (hrs):								
Total Purge Time (min):								
Total Vol. Purged (gal/L):								

SAMPLE COLLECTION INFORMATION:

Analysis	Preservative	Container Requirements	Collected
Volatile Organic Compounds	<u>4°C/HCL</u>	<u>3</u> 40 mL Glass Vials	<input checked="" type="checkbox"/>

OBSERVATIONS / NOTES:

Hydropunch advanced to sample depth and screen exposed at: _____ hrs. TDS = _____

Sample depth (screened interval) = from _____ to _____ ft.

Screen exposed to formation for _____ minutes.

Depth of borehole prior to advancing hydropunch = _____ ft.

Circle if Applicable:		Signature(s): <u>SJC</u>
<input type="checkbox"/> MS/MSD	Duplicate ID No.:	



GROUNDWATER SAMPLE LOG SHEET

Project Site Name: NWIRP Bethpage
 Project No.: N4037

Domestic Well Data
 Monitoring Well Data
 Other Well Type:
 QA Sample Type:

Sample ID No.: BP-BPOW12-2-DEV
 Sample Location: BPOW2-2
 Sampled By: SJC
 C.O.C. No.: BPOW-091003
 Type of Sample:
 Low Concentration
 High Concentration

SAMPLING DATA:

HORIBA/LAMORE

Date:	Color	pH	S.C.	Temp.	Turbidity	DO	ORP	Salinity
Time:	Visual	Standard	mS/cm	°C	NTU	mg/l	mV	
9/10/03	CLEAR	5.70	.118	13.20	250/18	-	-	-

PURGE DATA:

Date:	Volume	pH	S.C.	Temp. (C)	Turbidity	DO	ORP	Salinity
Method:								
Monitor Reading (ppm):								
Well Casing Diameter & Material Type:								
Total Well Depth (TD):								
Static Water Level (WL):								
One Casing Volume(gal/L):								
Start Purge (hrs):								
End Purge (hrs):								
Total Purge Time (min):								
Total Vol. Purged (gal/L):								

SAMPLE COLLECTION INFORMATION:

Analysis	Preservative	Container Requirements	Collected
Volatile Organic Compounds	4°C/HCL	3 x 40 mL Glass Vials	✓

OBSERVATIONS / NOTES:

Hydropunch advanced to sample depth and screen exposed at: hrs. TDS =

Sample depth (screened interval) = from to ft.

Screen exposed to formation for minutes.

Depth of borehole prior to advancing hydropunch = ft.

Circle if Applicable:

MS/MSD	Duplicate ID No.:
--------	-------------------

Signature(s):

S. J. Conti



GROUNDWATER SAMPLE LOG SHEET

Project Site Name: NWIRP Bethpage Sample ID No.: BPOW2-1-100903
 Project No.: N4037 Sample Location: BPOW2-1
 Sampled By: SJC
 C.O.C. No.: BPOW-100803
 Type of Sample:
 Domestic Well Data
 Monitoring Well Data
 Other Well Type:
 QA Sample Type:
 Low Concentration
 High Concentration

SAMPLING DATA: HORIBA LAMOTTE

Date:	Color	pH	S.C.	Temp.	Turbidity	DO	ORP	Salinity
Time:	Visual	Standard	mS/cm	°C	NTU	mg/l	mV	
10/9/03	CLEAR	4.42	-131	13.24	219/6	—	—	—

PURGE DATA: GALS TIME RATE

Date:	Volume	pH	S.C.	Temp. (C)	Turbidity	DO	ORP	Salinity
10/9/03	0	—	—	—	—	1005	—	—
Method: PUMP	0	—	—	—	—	1005	—	—
Monitor Reading (ppm): 0	300	4.39	.208	13.46	999/672	1025	15 GPM	—
Well Casing Diameter & Material "	500	4.43	.148	13.60	796/407	1045	12.5 "	—
Type: 4" SCH 80 PVC 3.31 ID	750	4.43	.134	13.26	199/8	1105	12.5 "	—
Total Well Depth (TD): 400'	1000	4.42	-131	13.24	219/6	1125	12.5 "	—
Static Water Level (WL): 23.2								
One Casing Volume (gal): ~200								
Start Purge (hrs): 1005								
End Purge (hrs): 1130								
Total Purge Time (min): 90								
Total Vol. Purged (gal): 1000								

SAMPLE COLLECTION INFORMATION:

Analysis	Preservative	Container Requirements	Collected
Volatile Organic Compounds	4°C	3 x 40 mL Glass Vials	✓
		24.3 WL @ 1025	

OBSERVATIONS / NOTES:

Hydropunch advanced to sample depth and screen exposed at: NA hrs. TDS = NA
 Sample depth (screened interval) = from NA to NA ft.
 Screen exposed to formation for NA minutes.
 Depth of borehole prior to advancing hydropunch = NA ft.

Resample of this well.
 Was sampled previously at
 the end of Development.
 See Dev Sheets for Details

Circle if Applicable: MS/MSD Duplicate ID No.:

Signature(s): SJC



GROUNDWATER SAMPLE LOG SHEET

Project Site Name: NWIRP Bethpage
 Project No.: N4037

Domestic Well Data
 Monitoring Well Data
 Other Well Type:
 QA Sample Type:

Sample ID No.: BP-BPOW3-2-DEV
 Sample Location: BPOW3-2
 Sampled By: STC
 C.O.C. No.: BPOW-102103
 Type of Sample:
 Low Concentration
 High Concentration

SAMPLING DATA:

LAMORE

Date:	Color	pH	S.C.	Temp.	Turbidity	DO	ORP	Salinity
Time:	Visual	Standard	mS/cm	°C	NTU	mg/l	mV	
10/21/03	CLEAR	5.80	077	13.05	49	-	-	-

PURGE DATA:

Date:	Volume	pH	S.C.	Temp. (C)	Turbidity	DO	ORP	Salinity
Method:								
Monitor Reading (ppm):								
Well Casing Diameter & Material Type:								
Total Well Depth (TD):								
Static Water Level (WL):								
One Casing Volume(gal/L):								
Start Purge (hrs):								
End Purge (hrs):								
Total Purge Time (min):								
Total Vol. Purged (gal/L):								

SAMPLE COLLECTION INFORMATION:

Analysis	Preservative	Container Requirements	Collected
Volatile Organic Compounds	4°C	3-40 mL Glass Vials	✓

OBSERVATIONS / NOTES:

Hydropunch advanced to sample depth and screen exposed at: _____ hrs. TDS = _____

Sample depth (screened interval) = from _____ to _____ ft.

Screen exposed to formation for _____ minutes.

Depth of borehole prior to advancing hydropunch = _____ ft.

Circle if Applicable:

MS/MSD	Duplicate ID No.:
--------	-------------------

Signature(s):

Stontu



GROUNDWATER SAMPLE LOG SHEET

Project Site Name: NWIRP Bethpage Sample ID No.: BP-BROW 3-1-DEV
 Project No.: N4037 Sample Location: BROW 3-1
 Sampled By: SJC
 C.O.C. No.: BROW-102103
 Type of Sample:
 Domestic Well Data
 Monitoring Well Data
 Other Well Type:
 QA Sample Type:
 Low Concentration
 High Concentration

SAMPLING DATA:		LAMOORE							
Date:	<u>10/21/03</u>	Color	pH	S.C.	Temp.	Turbidity	DO	ORP	Salinity
Time:	<u>1145</u>	Visual	Standard	mS/cm	°C	NTU	mg/l	mV	
Method:	<u>PUMP</u>	<u>CLEAR</u>	<u>5.81</u>	<u>.084</u>	<u>13.12</u>	<u>51</u>	<u>-</u>	<u>-</u>	<u>-</u>

PURGE DATA:								
Date:	Volume	pH	S.C.	Temp. (C)	Turbidity	DO	ORP	Salinity
Method:								
Monitor Reading (ppm):								
Well Casing Diameter & Material Type:								
Total Well Depth (TD):								
Static Water Level (WL):								
One Casing Volume(gal/L):								
Start Purge (hrs):								
End Purge (hrs):								
Total Purge Time (min):								
Total Vol. Purged (gal/L):								

SAMPLE COLLECTION INFORMATION:			
Analysis	Preservative	Container Requirements	Collected
Volatile Organic Compounds	4°C	3 40 mL Glass Vials	✓

OBSERVATIONS / NOTES:

Hydropunch advanced to sample depth and screen exposed at: hrs. TDS =

Sample depth (screened interval) = from to ft.

Screen exposed to formation for minutes.

Depth of borehole prior to advancing hydropunch = ft.

Circle if Applicable:		Signature(s): <i>SJ Conte</i>
MS/MSD	Duplicate ID No.:	



GROUNDWATER SAMPLE LOG SHEET

Project Site Name: NWIRP Bethpage
 Project No.: N4037

Domestic Well Data
 Monitoring Well Data
 Other Well Type: _____
 QA Sample Type: _____

Sample ID No.: BP-BPOW1-1-DEV
 Sample Location: BPOW1-1
 Sampled By: SJC
 C.O.C. No.: BPOW-120103
 Type of Sample:
 Low Concentration
 High Concentration

SAMPLING DATA:

HORIBA / LAMORE

Date: <u>12/1/03</u>	Color	pH	S.C.	Temp.	Turbidity	DO	ORP	Salinity
Time: <u>1200</u>	Visual	Standard	mS/cm	°C	NTU	mg/l	mV	
Method: <u>PUMP</u>	<u>CLEAR</u>	<u>4.78</u>	<u>389</u>	<u>11.99</u>	<u>31/11</u>	<u>-</u>	<u>-</u>	<u>-</u>

PURGE DATA:

Date:	Volume	pH	S.C.	Temp. (C)	Turbidity	DO	ORP	Salinity
Method:								
Monitor Reading (ppm):								
Well Casing Diameter & Material Type:								
Total Well Depth (TD):								
Static Water Level (WL):								
One Casing Volume(gal/L):								
Start Purge (hrs):								
End Purge (hrs):								
Total Purge Time (min):								
Total Vol. Purged (gal/L):								

SAMPLE COLLECTION INFORMATION:

Analysis	Preservative	Container Requirements	Collected
Volatile Organic Compounds	4°C	3 x 40 mL Glass Vials	✓

OBSERVATIONS / NOTES:

Hydropunch advanced to sample depth and screen exposed at: _____ hrs. TDS = _____

Sample depth (screened interval) = from _____ to _____ ft.

Screen exposed to formation for _____ minutes.

Depth of borehole prior to advancing hydropunch = _____ ft.

Circle if Applicable:

<input type="checkbox"/> MS/MSD	Duplicate ID No.:
---------------------------------	-------------------

Signature(s):

SJC



GROUNDWATER SAMPLE LOG SHEET

Project Site Name: NWIRP Bethpage
 Project No.: N4037

Domestic Well Data
 Monitoring Well Data
 Other Well Type: _____
 QA Sample Type: _____

Sample ID No.: BP-BPDW1-2-DEV
 Sample Location: BPDW1-2
 Sampled By: SJC
 C.O.C. No.: BPDW-120103
 Type of Sample:
 Low Concentration
 High Concentration

SAMPLING DATA:

HORIBA / LAMOTTE

Date: <u>12/2/03</u>	Color	pH	S.C.	Temp.	Turbidity	DO	ORP	Salinity
Time: <u>0930</u>	Visual	Standard	mS/cm	°C	NTU	mg/l	mV	
Method: <u>PUMP</u>	<u>CLEAR</u>	<u>4.60</u>	<u>082</u>	<u>11.14</u>	<u>41/43</u>	<u>-</u>	<u>-</u>	<u>-</u>

PURGE DATA:

Date:	Volume	pH	S.C.	Temp. (C)	Turbidity	DO	ORP	Salinity
Method:								
Monitor Reading (ppm):								
Well Casing Diameter & Material Type:								
Total Well Depth (TD):								
Static Water Level (WL):								
One Casing Volume(gal/L):								
Start Purge (hrs):								
End Purge (hrs):								
Total Purge Time (min):								
Total Vol. Purged (gal/L):								

SAMPLE COLLECTION INFORMATION:

Analysis	Preservative	Container Requirements	Collected
Volatile Organic Compounds	4°C	<u>3</u> 40 mL Glass Vials	<input checked="" type="checkbox"/>

OBSERVATIONS / NOTES:

Hydropunch advanced to sample depth and screen exposed at: _____ hrs. TDS = _____

Sample depth (screened interval) = from _____ to _____ ft.

Screen exposed to formation for _____ minutes.

Depth of borehole prior to advancing hydropunch = _____ ft.

Circle if Applicable:

MS/MSD

Duplicate ID No.: _____

Signature(s):



GROUNDWATER SAMPLE LOG SHEET

Project Site Name: NWIRP Bethpage
Project No.: N4037

Sample ID No.: BP- BPOW1-3-DEV
Sample Location: BPOW1-3
Sampled By: SJC
C.O.C. No.: BPOW-120103
Type of Sample:
 Low Concentration
 High Concentration

- Domestic Well Data
- Monitoring Well Data
- Other Well Type: _____
- QA Sample Type: _____

SAMPLING DATA:

HORIBA / LAMOTTE

Date:	Color	pH	S.C.	Temp.	Turbidity	DO	ORP	Salinity
Time:	Visual	Standard	mS/cm	°C	NTU	mg/l	mV	
12-2-03	CLEAR	4.65	.094	11.37	4 / 45	-	-	-

PURGE DATA:

Date:	Volume	pH	S.C.	Temp. (C)	Turbidity	DO	ORP	Salinity
Method:								
Monitor Reading (ppm):								
Well Casing Diameter & Material Type:								
Total Well Depth (TD):								
Static Water Level (WL):								
One Casing Volume(gal/L):								
Start Purge (hrs):								
End Purge (hrs):								
Total Purge Time (min):								
Total Vol. Purged (gal/L):								

SAMPLE COLLECTION INFORMATION:

Analysis	Preservative	Container Requirements	Collected
Volatile Organic Compounds	4°C	3 40 mL Glass Vials	✓

OBSERVATIONS / NOTES:

Hydropunch advanced to sample depth and screen exposed at: _____ hrs. TDS = _____

Sample depth (screened interval) = from _____ to _____ ft.

Screen exposed to formation for _____ minutes.

Depth of borehole prior to advancing hydropunch = _____ ft.

Circle if Applicable: MS/MSD Duplicate ID No.: _____

Signature(s): *SJC*



GROUNDWATER SAMPLE LOG SHEET

Project Site Name: NWIRP Bethpage
 Project No.: N4037

Domestic Well Data
 Monitoring Well Data
 Other Well Type:
 QA Sample Type:

Sample ID No.: BPOW2-1-120203
 Sample Location: BPOW2-1
 Sampled By: SJC
 C.O.C. No.: BPOW-120103
 Type of Sample:
 Low Concentration
 High Concentration

SAMPLING DATA:		HORIBA/LA MOTTE							
Date:	<u>12/02/03</u>	Color	pH	S.C.	Temp.	Turbidity	DO	ORP	Salinity
Time:	<u>1400</u>	Visual	Standard	mS/cm	°C	NTU	mg/l	mV	
Method:	<u>pump</u>	<u>CLEAR</u>	<u>4.64</u>	<u>.119</u>	<u>11.98</u>	<u>1/0</u>	<u>—</u>	<u>—</u>	<u>—</u>

PURGE DATA:		TIME							
Date:	<u>12/2/03</u>	Volume	pH	S.C.	Temp. (C)	Turbidity	DO	ORP	Salinity
Method:	<u>pump</u>	<u>START w/ pump</u>					<u>1300</u>	<u>—</u>	<u>—</u>
Monitor Reading (ppm):	<u>0</u>	<u>300 CLEAR</u>	<u>4.69</u>	<u>.138</u>	<u>12.31</u>	<u>1/2</u>	<u>1320</u>	<u>—</u>	<u>—</u>
Well Casing Diameter & Material		<u>600</u>	<u>4.63</u>	<u>.123</u>	<u>12.01</u>	<u>1/1</u>	<u>1340</u>	<u>—</u>	<u>—</u>
Type:	<u>3 3/16" ID PVC</u>	<u>800</u>	<u>4.64</u>	<u>.119</u>	<u>11.98</u>	<u>1/0</u>	<u>1400</u>	<u>—</u>	<u>—</u>
Total Well Depth (TD):	<u>400'</u>								
Static Water Level (WL):	<u>~23'</u>								
One Casing Volume (gal/L):	<u>~250</u>								
Start Purge (hrs):	<u>1300</u>								
End Purge (hrs):	<u>1400</u>								
Total Purge Time (min):	<u>60</u>								
Total Vol. Purged (gal/L):	<u>800</u>								

15 GPM
15 GPM
13 GPM

SAMPLE COLLECTION INFORMATION:			
Analysis	Preservative	Container Requirements	Collected
Volatile Organic Compounds	4°C	3 x 40 mL Glass Vials	✓

OBSERVATIONS / NOTES:

Hydropunch advanced to sample depth and screen exposed at: _____ hrs. TDS = _____

Sample depth (screened interval) = from _____ to _____ ft. 2ND RESAMPLE

Screen exposed to formation for _____ minutes.

Depth of borehole prior to advancing hydropunch = _____ ft.

Circle if Applicable: MS/MSD Duplicate ID No.: _____ Signature(s): SJC



GROUNDWATER SAMPLE LOG SHEET

Project Site Name: NWIRP Bethpage
Project No.: N4037

Sample ID No.: BP-BROW 4-1-DEV

Sample Location: BROW 4-1

Sampled By: SJC

C.O.C. No.: BROW-121503

- Domestic Well Data
- Monitoring Well Data
- Other Well Type: _____
- QA Sample Type: _____

- Type of Sample:
- Low Concentration
 - High Concentration

SAMPLING DATA:

HORIBA / LAMORTE

Date:	<u>12/15/03</u>	Color	pH	S.C.	Temp.	Turbidity	DO	ORP	Salinity
Time:	<u>1535</u>	Visual	Standard	mS/cm	°C	NTU	mg/l	mV	
Method:	<u>PUMP</u>	<u>CLEAR</u>	<u>4.48</u>	<u>0.68</u>	<u>11.84</u>	<u>85/29</u>	<u>-</u>	<u>-</u>	<u>-</u>

PURGE DATA:

Date:	Volume	pH	S.C.	Temp. (C)	Turbidity	DO	ORP	Salinity
Method:								
Monitor Reading (ppm):								
Well Casing Diameter & Material Type:								
Total Well Depth (TD):								
Static Water Level (WL):								
One Casing Volume(gal/L):								
Start Purge (hrs):								
End Purge (hrs):								
Total Purge Time (min):								
Total Vol. Purged (gal/L):								

SAMPLE COLLECTION INFORMATION:

Analysis	Preservative	Container Requirements	Collected
Volatile Organic Compounds	4°C	<u>3</u> 40 mL Glass Vials	<input checked="" type="checkbox"/>

OBSERVATIONS / NOTES:

Hydropunch advanced to sample depth and screen exposed at: _____ hrs. TDS = _____

Sample depth (screened interval) = from _____ to _____ ft.

Screen exposed to formation for _____ minutes.

Depth of borehole prior to advancing hydropunch = _____ ft.

Circle if Applicable:


Signature(s):

MS/MSD Duplicate ID No.:

SJC



APPENDIX L
ANALYTICAL RESULTS



TETRA TECH NUS INC

Client Sample ID: BP-BPOW1-1-DEV

GC/MS Volatiles

Lot-Sample #....: C3L030292-004	Work Order #....: F5X4P1AA	Matrix.....: WATER
Date Sampled...: 12/01/03	Date Received...: 12/03/03	MS Run #.....: 3338043
Prep Date.....: 12/04/03	Analysis Date...: 12/04/03	
Prep Batch #....: 3338159	Analysis Time...: 12:13	
Dilution Factor: 1	Initial Wgt/Vol: 5 mL	Final Wgt/Vol...: 5 mL
Analyst ID.....: 010099	Instrument ID...: HP5	
	Method.....: SW846 8260B	

PARAMETER	RESULT	LIMIT	UNITS	MDL
Acetone	ND	10	ug/L	2.5
Benzene	ND	1.0	ug/L	0.11
Bromodichloromethane	ND	1.0	ug/L	0.12
Bromoform	ND	1.0	ug/L	0.18
Bromomethane	ND	2.0	ug/L	0.37
2-Butanone	ND	5.0	ug/L	1.2
Carbon disulfide	ND	1.0	ug/L	0.16
Carbon tetrachloride	ND	1.0	ug/L	0.20
Chlorobenzene	ND	1.0	ug/L	0.11
Dibromochloromethane	ND	1.0	ug/L	0.093
Chloroethane	ND	2.0	ug/L	0.18
Chloroform	0.32 J	1.0	ug/L	0.14
Chloromethane	ND	2.0	ug/L	0.075
1,1-Dichloroethane	1.6	1.0	ug/L	0.16
1,2-Dichloroethane	ND	1.0	ug/L	0.092
1,1-Dichloroethene	2.9	1.0	ug/L	0.21
1,2-Dichloroethene	ND	1.0	ug/L	0.32
(total)				
1,2-Dichloropropane	ND	1.0	ug/L	0.11
cis-1,3-Dichloropropene	ND	1.0	ug/L	0.18
trans-1,3-Dichloropropene	ND	1.0	ug/L	0.087
Ethylbenzene	ND	1.0	ug/L	0.11
2-Hexanone	ND	5.0	ug/L	1.2
Methylene chloride	ND	2.0	ug/L	0.16
4-Methyl-2-pentanone	ND	5.0	ug/L	1.0
Styrene	ND	1.0	ug/L	0.11
1,1,2,2-Tetrachloroethane	ND	1.0	ug/L	0.16
Tetrachloroethene	1.2	1.0	ug/L	0.24
Toluene	0.22 J	1.0	ug/L	0.14
1,1,1-Trichloroethane	6.4	1.0	ug/L	0.16
1,1,2-Trichloroethane	ND	1.0	ug/L	0.12
Trichloroethene	1.9	1.0	ug/L	0.095
Vinyl chloride	ND	3.0	ug/L	0.17
Xylenes (total)	ND	3.0	ug/L	0.45

(Continued on next page)

TETRA TECH NUS INC

Client Sample ID: BP-BPOWL-2-DEV

GC/MS Volatiles

Lot-Sample #....: C3L030292-003	Work Order #....: F5X4M1AA	Matrix.....: WATER
Date Sampled....: 12/02/03	Date Received...: 12/03/03	MS Run #.....: 3338043
Prep Date.....: 12/04/03	Analysis Date...: 12/04/03	
Prep Batch #....: 3338159	Analysis Time...: 11:50	
Dilution Factor: 1	Initial Wgt/Vol: 5 mL	Final Wgt/Vol...: 5 mL
Analyst ID.....: 010099	Instrument ID...: HP5	
	Method.....: SW846 8260B	

PARAMETER	RESULT	REPORTING		
		LIMIT	UNITS	MDL
Acetone	2.5 J	10	ug/L	2.5
Benzene	ND	1.0	ug/L	0.11
Bromodichloromethane	ND	1.0	ug/L	0.12
Bromoform	ND	1.0	ug/L	0.18
Bromomethane	ND	2.0	ug/L	0.37
2-Butanone	ND	5.0	ug/L	1.2
Carbon disulfide	ND	1.0	ug/L	0.16
Carbon tetrachloride	ND	1.0	ug/L	0.20
Chlorobenzene	ND	1.0	ug/L	0.11
Dibromochloromethane	ND	1.0	ug/L	0.093
Chloroethane	ND	2.0	ug/L	0.18
Chloroform	ND	1.0	ug/L	0.14
Chloromethane	ND	2.0	ug/L	0.075
1,1-Dichloroethane	ND	1.0	ug/L	0.16
1,2-Dichloroethane	ND	1.0	ug/L	0.092
1,1-Dichloroethene	ND	1.0	ug/L	0.21
1,2-Dichloroethene	ND	1.0	ug/L	0.32
(total)				
1,2-Dichloropropane	ND	1.0	ug/L	0.11
cis-1,3-Dichloropropene	ND	1.0	ug/L	0.18
trans-1,3-Dichloropropene	ND	1.0	ug/L	0.087
Ethylbenzene	ND	1.0	ug/L	0.11
2-Hexanone	ND	5.0	ug/L	1.2
Methylene chloride	ND	2.0	ug/L	0.16
4-Methyl-2-pentanone	ND	5.0	ug/L	1.0
Styrene	ND	1.0	ug/L	0.11
1,1,2,2-Tetrachloroethane	ND	1.0	ug/L	0.16
Tetrachloroethene	0.58 J	1.0	ug/L	0.24
Toluene	ND	1.0	ug/L	0.14
1,1,1-Trichloroethane	ND	1.0	ug/L	0.16
1,1,2-Trichloroethane	ND	1.0	ug/L	0.12
Trichloroethene	ND	1.0	ug/L	0.095
Vinyl chloride	ND	3.0	ug/L	0.17
Xylenes (total)	ND	3.0	ug/L	0.45

(Continued on next page)

TETRA TECH NUS INC

Client Sample ID: BP-BPOW1-3-DEV

GC/MS Volatiles

Lot-Sample #....: C3L030292-002	Work Order #....: FSX4J1AA	Matrix.....: WATER
Date Sampled....: 12/02/03	Date Received...: 12/03/03	MS Run #.....: 3338043
Prep Date.....: 12/04/03	Analysis Date...: 12/04/03	
Prep Batch #....: 3338159	Analysis Time...: 11:26	
Dilution Factor: 1	Initial Wgt/Vol: 5 mL	Final Wgt/Vol...: 5 mL
Analyst ID.....: 010099	Instrument ID...: HP5	
	Method.....: SW846 8260B	

PARAMETER	RESULT	REPORTING LIMIT	UNITS	MDL
Acetone	ND	10	ug/L	2.5
Benzene	ND	1.0	ug/L	0.11
Bromodichloromethane	ND	1.0	ug/L	0.12
Bromoform	ND	1.0	ug/L	0.18
Bromomethane	ND	2.0	ug/L	0.37
2-Butanone	ND	5.0	ug/L	1.2
Carbon disulfide	ND	1.0	ug/L	0.16
Carbon tetrachloride	ND	1.0	ug/L	0.20
Chlorobenzene	ND	1.0	ug/L	0.11
Dibromochloromethane	ND	1.0	ug/L	0.093
Chloroethane	ND	2.0	ug/L	0.18
Chloroform	ND	1.0	ug/L	0.14
Chloromethane	ND	2.0	ug/L	0.075
1,1-Dichloroethane	ND	1.0	ug/L	0.16
1,2-Dichloroethane	ND	1.0	ug/L	0.092
1,1-Dichloroethene	ND	1.0	ug/L	0.21
1,2-Dichloroethene	ND	1.0	ug/L	0.32
(total)				
1,2-Dichloropropane	ND	1.0	ug/L	0.11
cis-1,3-Dichloropropene	ND	1.0	ug/L	0.18
trans-1,3-Dichloropropene	ND	1.0	ug/L	0.087
Ethylbenzene	ND	1.0	ug/L	0.11
2-Hexanone	ND	5.0	ug/L	1.2
Methylene chloride	ND	2.0	ug/L	0.16
4-Methyl-2-pentanone	ND	5.0	ug/L	1.0
Styrene	ND	1.0	ug/L	0.11
1,1,2,2-Tetrachloroethane	ND	1.0	ug/L	0.16
Tetrachloroethene	ND	1.0	ug/L	0.24
Toluene	ND	1.0	ug/L	0.14
1,1,1-Trichloroethane	ND	1.0	ug/L	0.16
1,1,2-Trichloroethane	ND	1.0	ug/L	0.12
Trichloroethene	ND	1.0	ug/L	0.095
Vinyl chloride	ND	3.0	ug/L	0.17
Xylenes (total)	ND	3.0	ug/L	0.45

(Continued on next page)

TETRA TECH NUS INC

Client Sample ID: BP-BPOW2-1-DEV

GC/MS Volatiles

Lot-Sample #....: C3I120361-005 Work Order #....: FX9AW1AA Matrix.....: WATER
 Date Sampled...: 09/10/03 12:00 Date Received...: 09/12/03 MS Run #.....:
 Prep Date.....: 09/17/03 Analysis Date...: 09/18/03
 Prep Batch #....: 3260714 Analysis Time...: 00:47
 Dilution Factor: 1
 Analyst ID.....: 034635 Instrument ID...: HP5
 Method.....: SW846 8260B

PARAMETER	RESULT	REPORTING LIMIT	UNITS	MDL
Acetone	ND	10	ug/L	2.5
Benzene	2.9	1.0	ug/L	0.11
Bromodichloromethane	ND	1.0	ug/L	0.12
Bromoform	ND	1.0	ug/L	0.18
Bromomethane	ND	2.0	ug/L	0.37
2-Butanone	ND	5.0	ug/L	1.2
Carbon disulfide	ND	1.0	ug/L	0.16
Carbon tetrachloride	ND	1.0	ug/L	0.20
Chlorobenzene	ND	1.0	ug/L	0.11
Dibromochloromethane	ND	1.0	ug/L	0.093
Chloroethane	ND	2.0	ug/L	0.18
Chloroform	ND	1.0	ug/L	0.14
Chloromethane	ND	2.0	ug/L	0.075
1,1-Dichloroethane	ND	1.0	ug/L	0.16
1,2-Dichloroethane	ND	1.0	ug/L	0.092
1,1-Dichloroethene	ND	1.0	ug/L	0.21
1,2-Dichloroethene	ND	1.0	ug/L	0.32
(total)				
1,2-Dichloropropane	ND	1.0	ug/L	0.11
cis-1,3-Dichloropropene	ND	1.0	ug/L	0.18
trans-1,3-Dichloropropene	ND	1.0	ug/L	0.087
Ethylbenzene	ND	1.0	ug/L	0.11
2-Hexanone	ND	5.0	ug/L	1.2
Methylene chloride	ND	2.0	ug/L	0.16
4-Methyl-2-pentanone	ND	5.0	ug/L	1.0
Styrene	ND	1.0	ug/L	0.11
1,1,2,2-Tetrachloroethane	ND	1.0	ug/L	0.16
Tetrachloroethene	ND	1.0	ug/L	0.24
Toluene	ND	1.0	ug/L	0.14
1,1,1-Trichloroethane	ND	1.0	ug/L	0.16
1,1,2-Trichloroethane	ND	1.0	ug/L	0.12
Trichloroethene	ND	1.0	ug/L	0.095
Vinyl chloride	ND	3.0	ug/L	0.17
Xylenes (total)	ND	3.0	ug/L	0.45

(Continued on next page)

TETRA TECH NUS INC

Client Sample ID: BPOW2-1-100903

GC/MS Volatiles

Lot-Sample #....: C3J100416-001 Work Order #....: F2CR81AA Matrix.....: WATER
 Date Sampled....: 10/08/03 Date Received...: 10/10/03 MS Run #.....: 3287107
 Prep Date.....: 10/14/03 Analysis Date...: 10/14/03
 Prep Batch #....: 3287263 Analysis Time...: 15:26
 Dilution Factor: 1 Initial Wgt/Vol: 5 mL Final Wgt/Vol...: 5 mL
 Analyst ID.....: 016328 Instrument ID...: HP6
 Method.....: SW846 8260B

PARAMETER	RESULT	REPORTING		
		LIMIT	UNITS	MDL
Acetone	3.1 J	10	ug/L	2.5
Benzene	ND	1.0	ug/L	0.11
Bromodichloromethane	ND	1.0	ug/L	0.12
Bromoform	ND	1.0	ug/L	0.18
Bromomethane	ND	2.0	ug/L	0.37
2-Butanone	ND	5.0	ug/L	1.2
Carbon disulfide	ND	1.0	ug/L	0.16
Carbon tetrachloride	ND	1.0	ug/L	0.20
Chlorobenzene	ND	1.0	ug/L	0.11
Dibromochloromethane	ND	1.0	ug/L	0.093
Chloroethane	ND	2.0	ug/L	0.18
Chloroform	ND	1.0	ug/L	0.14
Chloromethane	ND	2.0	ug/L	0.075
1,1-Dichloroethane	ND	1.0	ug/L	0.16
1,2-Dichloroethane	ND	1.0	ug/L	0.092
1,1-Dichloroethene	ND	1.0	ug/L	0.21
1,2-Dichloroethene	ND	1.0	ug/L	0.32
(total)				
1,2-Dichloropropane	ND	1.0	ug/L	0.11
cis-1,3-Dichloropropene	ND	1.0	ug/L	0.18
trans-1,3-Dichloropropene	ND	1.0	ug/L	0.087
Ethylbenzene	ND	1.0	ug/L	0.11
2-Hexanone	ND	5.0	ug/L	1.2
Methylene chloride	ND	2.0	ug/L	0.16
4-Methyl-2-pentanone	ND	5.0	ug/L	1.0
Styrene	ND	1.0	ug/L	0.11
1,1,2,2-Tetrachloroethane	ND	1.0	ug/L	0.16
Tetrachloroethene	ND	1.0	ug/L	0.24
Toluene	ND	1.0	ug/L	0.14
1,1,1-Trichloroethane	ND	1.0	ug/L	0.16
1,1,2-Trichloroethane	ND	1.0	ug/L	0.12
Trichloroethene	ND	1.0	ug/L	0.095
Vinyl chloride	ND	3.0	ug/L	0.17
Xylenes (total)	ND	3.0	ug/L	0.45

(Continued on next page)

TETRA TECH NUS INC

Client Sample ID: BPOW2-1-120203

GC/MS Volatiles

Lot-Sample #....: C3L030292-005 Work Order #....: F5X4R1AA Matrix.....: WATER
 Date Sampled....: 12/02/03 Date Received...: 12/03/03 MS Run #.....: 3338043
 Prep Date.....: 12/04/03 Analysis Date...: 12/04/03
 Prep Batch #....: 3338159 Analysis Time...: 12:37
 Dilution Factor: 1 Initial Wgt/Vol: 5 mL Final Wgt/Vol...: 5 mL
 Analyst ID.....: 010099 Instrument ID...: HP5
 Method.....: SW846 8260B

PARAMETER	RESULT	REPORTING		
		LIMIT	UNITS	MDL
Acetone	ND	10	ug/L	2.5
Benzene	ND	1.0	ug/L	0.11
Bromodichloromethane	ND	1.0	ug/L	0.12
Bromoform	ND	1.0	ug/L	0.18
Bromomethane	ND	2.0	ug/L	0.37
2-Butanone	ND	5.0	ug/L	1.2
Carbon disulfide	ND	1.0	ug/L	0.16
Carbon tetrachloride	ND	1.0	ug/L	0.20
Chlorobenzene	ND	1.0	ug/L	0.11
Dibromochloromethane	ND	1.0	ug/L	0.093
Chloroethane	ND	2.0	ug/L	0.18
Chloroform	ND	1.0	ug/L	0.14
Chloromethane	ND	2.0	ug/L	0.075
1,1-Dichloroethane	ND	1.0	ug/L	0.16
1,2-Dichloroethane	ND	1.0	ug/L	0.092
1,1-Dichloroethene	ND	1.0	ug/L	0.21
1,2-Dichloroethene (total)	ND	1.0	ug/L	0.32
1,2-Dichloropropane	ND	1.0	ug/L	0.11
cis-1,3-Dichloropropene	ND	1.0	ug/L	0.18
trans-1,3-Dichloropropene	ND	1.0	ug/L	0.087
Ethylbenzene	ND	1.0	ug/L	0.11
2-Hexanone	ND	5.0	ug/L	1.2
Methylene chloride	ND	2.0	ug/L	0.16
4-Methyl-2-pentanone	ND	5.0	ug/L	1.0
Styrene	ND	1.0	ug/L	0.11
1,1,2,2-Tetrachloroethane	ND	1.0	ug/L	0.16
Tetrachloroethene	ND	1.0	ug/L	0.24
Toluene	ND	1.0	ug/L	0.14
1,1,1-Trichloroethane	ND	1.0	ug/L	0.16
1,1,2-Trichloroethane	ND	1.0	ug/L	0.12
Trichloroethene	ND	1.0	ug/L	0.095
Vinyl chloride	ND	3.0	ug/L	0.17
Xylenes (total)	ND	3.0	ug/L	0.45

(Continued on next page)

TETRA TECH NUS INC

Client Sample ID: BP-BPOW2-2-DEV

GC/MS Volatiles

Lot-Sample #....: C3I120361-004 Work Order #....: FX9AR1AA Matrix.....: WATER
 Date Sampled....: 09/10/03 10:30 Date Received...: 09/12/03 MS Run #.....:
 Prep Date.....: 09/17/03 Analysis Date...: 09/18/03
 Prep Batch #....: 3260714 Analysis Time...: 00:24
 Dilution Factor: 1
 Analyst ID.....: 034635 Instrument ID...: HP5
 Method.....: SW846 8260B

PARAMETER	RESULT	REPORTING		
		LIMIT	UNITS	MDL
Acetone	ND	10	ug/L	2.5
Benzene	ND	1.0	ug/L	0.11
Bromodichloromethane	ND	1.0	ug/L	0.12
Bromoform	ND	1.0	ug/L	0.18
Bromomethane	ND	2.0	ug/L	0.37
2-Butanone	ND	5.0	ug/L	1.2
Carbon disulfide	ND	1.0	ug/L	0.16
Carbon tetrachloride	ND	1.0	ug/L	0.20
Chlorobenzene	ND	1.0	ug/L	0.11
Dibromochloromethane	ND	1.0	ug/L	0.093
Chloroethane	ND	2.0	ug/L	0.18
Chloroform	ND	1.0	ug/L	0.14
Chloromethane	ND	2.0	ug/L	0.075
1,1-Dichloroethane	ND	1.0	ug/L	0.16
1,2-Dichloroethane	ND	1.0	ug/L	0.092
1,1-Dichloroethene	ND	1.0	ug/L	0.21
1,2-Dichloroethene	ND	1.0	ug/L	0.32
(total)				
1,2-Dichloropropane	ND	1.0	ug/L	0.11
cis-1,3-Dichloropropene	ND	1.0	ug/L	0.18
trans-1,3-Dichloropropene	ND	1.0	ug/L	0.087
Ethylbenzene	ND	1.0	ug/L	0.11
2-Hexanone	ND	5.0	ug/L	1.2
Methylene chloride	ND	2.0	ug/L	0.16
4-Methyl-2-pentanone	ND	5.0	ug/L	1.0
Styrene	ND	1.0	ug/L	0.11
1,1,2,2-Tetrachloroethane	ND	1.0	ug/L	0.16
Tetrachloroethene	ND	1.0	ug/L	0.24
Toluene	ND	1.0	ug/L	0.14
1,1,1-Trichloroethane	ND	1.0	ug/L	0.16
1,1,2-Trichloroethane	ND	1.0	ug/L	0.12
Trichloroethene	ND	1.0	ug/L	0.095
Vinyl chloride	ND	3.0	ug/L	0.17
Xylenes (total)	ND	3.0	ug/L	0.45

(Continued on next page)

SEVERN TRENT LABORATORIES, INC.

PRELIMINARY DATA SUMMARY

 The results shown below may still require additional laboratory review and are subject to change. Actions taken based on these results are the responsibility of the data user.

Tetra Tech NUS Inc PAGE 3
 Lot #: C3J230178 NWIRP Beth Page Date Reported: 11/07/03
Project Number: CTO812

PARAMETER	RESULT	REPORTING LIMIT	UNITS	ANALYTICAL METHOD
-----------	--------	--------------------	-------	----------------------

Client Sample ID: BP-BPOW3-1-DEV

Sample #: 003 Date Sampled: 10/21/03 11:45 Date Received: 10/23/03 Matrix: WATER

Volatile Organics by GC/MS

Reviewed

Acetone	ND	10	ug/L	SW846 8260B
Benzene	ND	1.0	ug/L	SW846 8260B
Bromodichloromethane	ND	1.0	ug/L	SW846 8260B
Bromoform	ND	1.0	ug/L	SW846 8260B
Bromomethane	ND	2.0	ug/L	SW846 8260B
2-Butanone	ND	5.0	ug/L	SW846 8260B
Carbon disulfide	ND	1.0	ug/L	SW846 8260B
Carbon tetrachloride	ND	1.0	ug/L	SW846 8260B
Chlorobenzene	ND	1.0	ug/L	SW846 8260B
Dibromochloromethane	ND	1.0	ug/L	SW846 8260B
Chloroethane	ND	2.0	ug/L	SW846 8260B
Chloroform	ND	1.0	ug/L	SW846 8260B
Chloromethane	ND	2.0	ug/L	SW846 8260B
1,1-Dichloroethane	ND	1.0	ug/L	SW846 8260B
1,2-Dichloroethane	ND	1.0	ug/L	SW846 8260B
1,1-Dichloroethene	ND	1.0	ug/L	SW846 8260B
1,2-Dichloroethene	ND	1.0	ug/L	SW846 8260B
(total)				
1,2-Dichloropropane	ND	1.0	ug/L	SW846 8260B
cis-1,3-Dichloropropene	ND	1.0	ug/L	SW846 8260B
trans-1,3-Dichloropropene	ND	1.0	ug/L	SW846 8260B
Ethylbenzene	ND	1.0	ug/L	SW846 8260B
2-Hexanone	ND	5.0	ug/L	SW846 8260B
Methylene chloride	ND	2.0	ug/L	SW846 8260B
4-Methyl-2-pentanone	ND	5.0	ug/L	SW846 8260B
Styrene	ND	1.0	ug/L	SW846 8260B
1,1,2,2-Tetrachloroethane	ND	1.0	ug/L	SW846 8260B
Tetrachloroethene	ND	1.0	ug/L	SW846 8260B
Toluene	ND	1.0	ug/L	SW846 8260B
1,1,1-Trichloroethane	ND	1.0	ug/L	SW846 8260B
1,1,2-Trichloroethane	ND	1.0	ug/L	SW846 8260B
Trichloroethene	ND	1.0	ug/L	SW846 8260B
Vinyl chloride	ND	3.0	ug/L	SW846 8260B
Xylenes (total)	ND	3.0	ug/L	SW846 8260B

(Continued on next page)

183

SEVERN TRENT LABORATORIES, INC.

PRELIMINARY DATA SUMMARY

 The results shown below may still require additional laboratory review and are subject to change. Actions taken based on these results are the responsibility of the data user.

Tetra Tech NUS Inc PAGE 2
 NWIRP Beth Page Date Reported: 11/07/03
 Project Number: CT0812

Lot #: C3J230178

PARAMETER	RESULT	REPORTING LIMIT	UNITS	ANALYTICAL METHOD
-----------	--------	--------------------	-------	----------------------

Client Sample ID: BP-BPOW3-2-DEV

Sample #: 002 Date Sampled: 10/21/03 10:00 Date Received: 10/23/03 Matrix: WATER

Volatile Organics by GC/MS

Reviewed

Acetone	ND	10	ug/L	SW846 8260B
Benzene	ND	1.0	ug/L	SW846 8260B
Bromodichloromethane	ND	1.0	ug/L	SW846 8260B
Bromoform	ND	1.0	ug/L	SW846 8260B
Bromomethane	ND	2.0	ug/L	SW846 8260B
2-Butanone	ND	5.0	ug/L	SW846 8260B
Carbon disulfide	ND	1.0	ug/L	SW846 8260B
Carbon tetrachloride	ND	1.0	ug/L	SW846 8260B
Chlorobenzene	ND	1.0	ug/L	SW846 8260B
Dibromochloromethane	ND	1.0	ug/L	SW846 8260B
Chloroethane	ND	2.0	ug/L	SW846 8260B
Chloroform	ND	1.0	ug/L	SW846 8260B
Chloromethane	ND	2.0	ug/L	SW846 8260B
1,1-Dichloroethane	ND	1.0	ug/L	SW846 8260B
1,2-Dichloroethane	ND	1.0	ug/L	SW846 8260B
1,1-Dichloroethene	ND	1.0	ug/L	SW846 8260B
1,2-Dichloroethene	ND	1.0	ug/L	SW846 8260B
(total)				
1,2-Dichloropropane	ND	1.0	ug/L	SW846 8260B
cis-1,3-Dichloropropene	ND	1.0	ug/L	SW846 8260B
trans-1,3-Dichloropropene	ND	1.0	ug/L	SW846 8260B
Ethylbenzene	ND	1.0	ug/L	SW846 8260B
2-Hexanone	ND	5.0	ug/L	SW846 8260B
Methylene chloride	ND	2.0	ug/L	SW846 8260B
4-Methyl-2-pentanone	ND	5.0	ug/L	SW846 8260B
Styrene	ND	1.0	ug/L	SW846 8260B
1,1,2,2-Tetrachloroethane	ND	1.0	ug/L	SW846 8260B
Tetrachloroethene	ND	1.0	ug/L	SW846 8260B
Toluene	0.29 J	1.0	ug/L	SW846 8260B
1,1,1-Trichloroethane	ND	1.0	ug/L	SW846 8260B
1,1,2-Trichloroethane	ND	1.0	ug/L	SW846 8260B
Trichloroethene	ND	1.0	ug/L	SW846 8260B
Vinyl chloride	ND	3.0	ug/L	SW846 8260B
Xylenes (total)	ND	3.0	ug/L	SW846 8260B

J Estimated result. Result is less than RL.

(Continued on next page)

SEVERN TRENT LABORATORIES, INC.

PRELIMINARY DATA SUMMARY

The results shown below may still require additional laboratory review and are subject to change. Actions taken based on these results are the responsibility of the data user.

Lot #: C3L170286
 Tetra Tech NUS Inc
 REPORTING
 ANALYTICAL
 PAGE 1
 NWIRP Beth Page
 Date Reported: 1/08/04
 Project Number: CTO812

PARAMETER	RESULT	LIMIT	UNITS	METHOD
-----------	--------	-------	-------	--------

Client Sample ID: BP-BPOW4-1-DEV

Sample #: 001
Date Sampled: 12/15/03 15:35
Date Received: 12/17/03
Matrix: WATER

Volatile Organics by GC/MS

Reviewed

Acetone	ND	10	ug/L	SW846 8260B
Benzene	ND	1.0	ug/L	SW846 8260B
Bromodichloromethane	ND	1.0	ug/L	SW846 8260B
Bromoform	ND	1.0	ug/L	SW846 8260B
Bromomethane	ND	2.0	ug/L	SW846 8260B
2-Butanone	ND	5.0	ug/L	SW846 8260B
Carbon disulfide	ND	1.0	ug/L	SW846 8260B
Carbon tetrachloride	ND	1.0	ug/L	SW846 8260B
Chlorobenzene	ND	1.0	ug/L	SW846 8260B
Dibromochloromethane	ND	1.0	ug/L	SW846 8260B
Chloroethane	ND	2.0	ug/L	SW846 8260B
Chloroform	ND	1.0	ug/L	SW846 8260B
Chloromethane	ND	2.0	ug/L	SW846 8260B
1,1-Dichloroethane	ND	1.0	ug/L	SW846 8260B
1,2-Dichloroethane	ND	1.0	ug/L	SW846 8260B
1,1-Dichloroethene	ND	1.0	ug/L	SW846 8260B
1,2-Dichloroethene	ND	1.0	ug/L	SW846 8260B
(total)				
1,2-Dichloropropane	ND	1.0	ug/L	SW846 8260B
cis-1,3-Dichloropropene	ND	1.0	ug/L	SW846 8260B
trans-1,3-Dichloropropene	ND	1.0	ug/L	SW846 8260B
Ethylbenzene	ND	1.0	ug/L	SW846 8260B
2-Hexanone	ND	5.0	ug/L	SW846 8260B
Methylene chloride	ND	2.0	ug/L	SW846 8260B
4-Methyl-2-pentanone	ND	5.0	ug/L	SW846 8260B
Styrene	ND	1.0	ug/L	SW846 8260B
1,1,2,2-Tetrachloroethane	ND	1.0	ug/L	SW846 8260B
Tetrachloroethene	ND	1.0	ug/L	SW846 8260B
Toluene	0.28 J	1.0	ug/L	SW846 8260B
1,1,1-Trichloroethane	ND	1.0	ug/L	SW846 8260B
1,1,2-Trichloroethane	ND	1.0	ug/L	SW846 8260B
Trichloroethene	ND	1.0	ug/L	SW846 8260B
Vinyl chloride	ND	3.0	ug/L	SW846 8260B
Xylenes (total)	ND	3.0	ug/L	SW846 8260B

J Estimated result. Result is less than RL.

(Continued on next page)

TETRA TECH NUS INC

Client Sample ID: BP-BPOW4-2-DEV

GC/MS Volatiles

Lot-Sample #....: C3H060299-003 Work Order #....: FVQ101AA Matrix.....: WATER
 Date Sampled....: 08/04/03 Date Received...: 08/06/03 MS Run #.....: 3219024
 Prep Date.....: 08/07/03 Analysis Date...: 08/07/03
 Prep Batch #....: 3219133 Analysis Time...: 11:05
 Dilution Factor: 1 Initial Wgt/Vol: 5 mL Final Wgt/Vol...: 5 mL
 Analyst ID.....: 016328 Instrument ID...: HP6
 Method.....: SW846 8260B

PARAMETER	RESULT	LIMIT	UNITS	MDL
Acetone	ND	10	ug/L	2.5
Benzene	ND	1.0	ug/L	0.11
Bromodichloromethane	ND	1.0	ug/L	0.12
Bromoform	ND	1.0	ug/L	0.18
Bromomethane	ND	2.0	ug/L	0.37
2-Butanone	ND	5.0	ug/L	1.2
Carbon disulfide	ND	1.0	ug/L	0.16
Carbon tetrachloride	ND	1.0	ug/L	0.20
Chlorobenzene	ND	1.0	ug/L	0.11
Dibromochloromethane	ND	1.0	ug/L	0.093
Chloroethane	ND	2.0	ug/L	0.18
Chloroform	ND	1.0	ug/L	0.14
Chloromethane	ND	2.0	ug/L	0.075
1,1-Dichloroethane	ND	1.0	ug/L	0.16
1,2-Dichloroethane	ND	1.0	ug/L	0.092
1,1-Dichloroethene	ND	1.0	ug/L	0.21
1,2-Dichloroethene	ND	1.0	ug/L	0.32
(total)				
1,2-Dichloropropane	ND	1.0	ug/L	0.11
cis-1,3-Dichloropropene	ND	1.0	ug/L	0.18
trans-1,3-Dichloropropene	ND	1.0	ug/L	0.087
Ethylbenzene	ND	1.0	ug/L	0.11
2-Hexanone	ND	5.0	ug/L	1.2
Methylene chloride	ND	2.0	ug/L	0.16
4-Methyl-2-pentanone	ND	5.0	ug/L	1.0
Styrene	ND	1.0	ug/L	0.11
1,1,2,2-Tetrachloroethane	ND	1.0	ug/L	0.16
Tetrachloroethene	ND	1.0	ug/L	0.24
Toluene	ND	1.0	ug/L	0.14
1,1,1-Trichloroethane	ND	1.0	ug/L	0.16
1,1,2-Trichloroethane	ND	1.0	ug/L	0.12
Trichloroethene	ND	1.0	ug/L	0.095
Vinyl chloride	ND	3.0	ug/L	0.17
Xylenes (total)	ND	3.0	ug/L	0.45

(Continued on next page)



APPENDIX M
SURVEY DATA