

**Quarterly Operations Report  
Third Quarter 2012**

**Soil Vapor Extraction Containment System  
Site 1, Former Drum Marshalling Yard  
Naval Weapons Industrial Reserve Plant  
Bethpage, New York**

**Contract No. N40085-10-D-9409  
Contract Task Order No. 0005**

March 2013

Prepared for:



Naval Facilities Engineering Command Mid-Atlantic  
9742 Maryland Avenue  
Norfolk, VA 23511

Prepared by:



**H&S Environmental, Inc.  
160 East Main Street, Suite 2F  
Westborough, Massachusetts 01581  
(508) 366-7442**

**Quarterly Operations Report  
Third Quarter 2012**

**Soil Vapor Extraction Containment System  
Site 1, Former Drum Marshalling Yard  
Naval Weapons Industrial Reserve Plant  
Bethpage, New York**

**Contract No. N40085-10-D-9409  
Contract Task Order No. 0005**

March 2013

Prepared for:

Naval Facilities Engineering Command Mid-Atlantic  
9742 Maryland Avenue  
Norfolk, VA 23511



A handwritten signature in blue ink, appearing to read 'Patrick Schauble'.

---

Patrick Schauble, P.E.  
Program Manager

3/26/13

Date

A handwritten signature in blue ink, appearing to read 'Jennifer Good'.

---

Jennifer Good, P.G.  
Project Manager

3/26/13

Date

## TABLE OF CONTENTS

<b>1.0</b>	<b>INTRODUCTION.....</b>	<b>1-1</b>
1.1	Site Location.....	1-1
1.2	Background.....	1-1
1.3	Project Overview and Objective.....	1-2
1.4	SVECS Overview.....	1-2
<b>2.0</b>	<b>SVECS OPERATION AND MAINTENANCE .....</b>	<b>2-1</b>
2.1	Routine Maintenance Activities .....	2-1
2.2	Non-routine Maintenance / Site Activities .....	2-1
<b>3.0</b>	<b>SVECS MONITORING .....</b>	<b>3-1</b>
3.1	Monthly Air Quality Monitoring.....	3-1
3.2	Quarterly Air Quality Monitoring .....	3-1
3.3	Quarterly Off-site Vapor Monitoring .....	3-2
3.4	Air Quality Concentration Trends .....	3-2
<b>4.0</b>	<b>CONCLUSIONS AND RECOMMENDATIONS.....</b>	<b>4-1</b>
<b>5.0</b>	<b>REFERENCES.....</b>	<b>5-1</b>

### **TABLES**

TABLE 1	Monthly Vapor Analytical Results – July 2012
TABLE 2	Monthly Vapor Analytical Results – August 2012
TABLE 3	Monthly Vapor Analytical Results – September 2012
TABLE 4	Quarterly Vapor Analytical Results – Third Quarter 2012
TABLE 5	Quarterly Offsite Soil Vapor Monitoring Results – Third Quarter 2012
TABLE 6	Quarterly Vapor Analytical Results through Third Quarter 2012

### **FIGURES**

FIGURE 1	Site Location Map
FIGURE 2	Site Area and Vicinity
FIGURE 3	Site Plan – Existing SVECS Layout
FIGURE 4	System Layout Plan
FIGURE 5	Third Quarter 2012 Vapor Analytical Map – Select VOC Concentrations

### **APPENDICES**

APPENDIX A	NYSDEC Air Permit Equivalent Approval
APPENDIX B	Vapor Concentration Trend Graphs of Select VOCs

## Acronyms and Abbreviations

bgs	below ground surface
CTO	Contract Task Order
DAR	Division of Air Resources
DoD	Department of Defense
ELAP	Environmental Laboratory Accreditation Program
FMS	Flow Monitoring Station
GOCO	Government Owned Contractor Operated
H&S	H&S Environmental, Inc.
i.w.	inches of water column
NAVFAC	Naval Facilities Engineering Command Mid-Atlantic
NELAC	National Environmental Accreditation Conference
NGC	Northrop Grumman Corporation
NWIRP	Naval Weapons Industrial Reserve Plant
NYSDEC	New York State Department of Environmental Conservation
NYDOH	New York Department of Health
O&M	Operation and Maintenance
PCB	polychlorinated biphenyls
PCE	tetrachloroethene
PID	photoionization detector
scfm	standard cubic feet per minute
SVECS	soil vapor extraction containment system
SVEW	soil vapor extraction well
SVOC	semi-volatile organic compound
SVPM	soil vapor pressure monitor
TCA	trichloroethane
TCE	trichloroethene
TCL	target compound list
TtEC	Tetra Tech EC, Inc.
TtNUS	Tetra Tech NUS, Inc.
VGAC	vapor-phase granular activated carbon
VOC	volatile organic compound

## 1.0 INTRODUCTION

H&S Environmental, Inc. (H&S) has prepared this Quarterly Operations Report for the Third Quarter 2012 for the Soil Vapor Extraction Containment System (SVECS) at Site 1, Former Drum Marshalling Area, at the Naval Weapons Industrial Reserve Plant (NWIRP) in Bethpage, New York. This report has been prepared for the U.S. Department of the Navy (Navy), Naval Facilities Engineering Command (NAVFAC), Mid-Atlantic, under Contract No. N40085-10-D-9409, Contract Task Order (CTO) No. 0005. This Third Quarter 2012 Operations Report details activities that occurred from June 2012 to September 2012. Data was collected and operational activities were performed by H&S in accordance with the following documents:

- *Final Operation & Maintenance Plan for Soil Vapor Extraction Containment System Site 1, Former Drum Marshalling Yard at Naval Weapons Industrial Reserve Plant Bethpage, New York* prepared by Tetra Tech EC, Inc. (TtEC) in 2010, hereafter referred to as the “O&M Manual.”
- *Final Supplemental Offsite Soil Vapor Intrusion Monitoring Plan for the Soil Vapor Extraction Containment System, Site 1, Former Drum Marshalling Yard at Naval Weapons Industrial Reserve Plant, Bethpage, New York* prepared by Tetra Tech NUS, Inc. (TtNUS) in 2012.

### 1.1 Site Location

NWIRP Bethpage is located in east central Nassau County, Long Island, New York, approximately 30 miles east of New York City. The Navy's property totaled approximately 109.5 acres and was formerly a Government Owned Contractor-Operated (GOCO) facility that was operated by the Northrop Grumman Corporation (NGC) until September 1998. NWIRP Bethpage is bordered on the north, west, and south by property owned, or formerly owned, by NGC that covered approximately 605 acres, and on the east by a residential neighborhood. Site 1 lies within the fenced area of NWIRP Bethpage and is located east of Plant No. 3, west of 11<sup>th</sup> Street, and north of Plant 17 South (**Figures 1 and 2**).

### 1.2 Background

NWIRP Bethpage was established in 1941. Since inception, the primary mission of the facility has been the research, prototyping, testing, design engineering, fabrication, and primary assembly of military aircraft. Historical operations that resulted in hazardous material generation at the facility included metal finishing processes, maintenance operations, painting of aircraft and components, and other activities that involve aircraft manufacturing. Wastes generated by plant operations were disposed of directly into drainage sumps, dry wells, and/or on the ground surface, resulting in the disposal of a number of hazardous wastes, including volatile organic compounds (VOCs), semivolatile organic compounds (SVOCs), polychlorinated biphenyls (PCBs), and inorganic analytes (chromium and cadmium) at the site. Some of these contaminants have migrated from the source area to surrounding areas, including the soils at these sites and the groundwater beneath and downgradient of the NWIRP Bethpage property. NWIRP Bethpage is currently listed by the New York State Department of Environmental Conservation (NYSDEC) as an “inactive hazardous waste site” (#1-30-003B).

Soils at Site 1 consist mainly of unconsolidated sediments that overlie crystalline bedrock. A clay unit is present near the groundwater table (50 feet below ground surface [bgs]) at the southeast corner of the site. This clay unit is suspected to be a source of chlorinated solvents that are migrating into the overlying soil gas and the source of offsite VOCs in soil vapor (TtEC 2010).

Chlorinated solvents including trichloroethene (TCE), tetrachloroethene (PCE), and 1,1,1-trichloroethane (TCA) have been identified as the VOCs of interest in soil gas at the site. Concentrations greater than 1,000  $\mu\text{g}/\text{m}^3$  (micrograms per cubic meter) of soil vapor have been directly associated with Site 1 activities and historical environmental data, and based on preliminary screening, exceed guidelines established by the New York Department of Health (NYDOH) for slab soil vapor concentrations. Of these compounds, TCE is the primary VOC of concern. Mitigation of TCE contamination in accordance with NYDOH guidance is expected to mitigate other VOCs associated with the site. PCBs, cadmium, and chromium have also been identified in site soils at concentrations requiring remediation. The majority of these chemicals has been detected in the central portion of Site 1 and will be addressed via a separate remediation (TtEC 2010).

Prior to implementation of the SVECS, the mean concentrations of VOCs in soil gas samples collected along the eastern fence-line were 41,128  $\mu\text{g}/\text{m}^3$  of TCE, 381  $\mu\text{g}/\text{m}^3$  of PCE, and 20,634  $\mu\text{g}/\text{m}^3$  of 1,1,1-TCA. The maximum concentrations of VOCs in the soil gas samples were 180,000  $\mu\text{g}/\text{m}^3$  of TCE, 1,200  $\mu\text{g}/\text{m}^3$  of PCE, and 90,000  $\mu\text{g}/\text{m}^3$  of 1,1,1-TCA (TtEC 2010).

### 1.3 Project Overview and Objective

The remedial objective for this project is to use an on-site soil vapor extraction system to prevent further off-site migration of VOC contaminated soil vapor and to the extent practical, capture contaminated soil vapor with a TCE concentration greater than 250  $\mu\text{g}/\text{m}^3$ . A secondary objective of this project is to address soil vapor with a TCE concentration greater than 5  $\mu\text{g}/\text{m}^3$ . The SVECS is an interim action intended to address migration of VOCs in contaminated soil vapors and has been designed for a four-year operational life; it is expected to operate continuously 24 hours/day, seven days/week, with the exception of maintenance and adjustment periods (TtEC 2010).

### 1.4 SVECS Overview

The SVECS consists of soil vapor extraction, soil vapor monitoring, and soil vapor treatment. Twelve SVE wells (SVEWs) are located along the eastern boundary of Site 1 in six clusters, each consisting of one intermediate well and one deep well. Intermediate wells SVE-101I, SVE-102I, SVE-103I, SVE-104I, SVE-105I, and SVE-106I have a screened interval between 25 and 35 ft bgs. Deep wells SVE-101D, SVE-102D, SVE-103D, SVE-104D, SVE-105D, and SVE-106D have a screened interval between 40 and 60 ft bgs. The groundwater table fluctuates between approximately 50 and 55 feet bgs. Each SVEW is operated at a flow rate such that the combined total flow rate is approximately 400 standard cubic feet per minute (scfm) of soil vapor. Each intermediate depth SVEW requires a minimum vacuum of 4 inches of water column (i.w.) and each deep SVEW requires a minimum vacuum of 20 i.w. in order to extract the targeted flow rates. These twelve SVEWs have been piped below the ground to the Flow Monitoring Station (FMS), where flow, vacuum, and vapor quality are monitored. Within the FMS, the discharges

from the individual SVEWs have been equipped with a 2-inch flow control butterfly valve, a vacuum gauge, and a sampling port. The sampling port is utilized to measure the flow rate from an individual well using a portable velocity meter and to collect vapor samples. All the SVE lines collect into a single manifold within the FMS and from this location a single underground pipeline has been routed approximately 1,400 linear feet to the Treatment Building (Building 03-35). Five additional SVEWs (SV-107D, SV-108D, SV-109D, SV-110D, and SV-111D) were installed in October 2011 to address potential VOCs under Plant No. 3 and the South Warehouse. A site plan depicting well locations is included as **Figure 3**.

The SVECS is housed within the Treatment Building, an existing and unoccupied building also known as Building 03-35. The treatment system consists of a moisture separator, two SVE blowers, and a 5,000-lb vapor-phase granular activated carbon (VGAC) unit for removal of chlorinated VOCs from the off-gas. Soil vapor that enters the Treatment Building first passes through the moisture separator tank where any condensate is separated and removed by a portable pump into 55-gallon drums and then disposed of onsite to the County's sanitary sewer system when necessary. The vapor is then passed through an air filter and SVE blower and then treated in the VGAC unit. The treated vapor is discharged from the VGAC via an exhaust stack. The SVECS has a control panel comprised of mechanical interlocks and relays for local operation. A System Layout Plan is presented in **Figure 4**, which also illustrates the design flow rates through the soil vapor extraction and treatment process.

The off-gas from the SVECS is monitored for chlorinated VOCs as identified in the NYSDEC Division of Air Resources (DAR) permit equivalent effluent limitations (**Appendix A**) and monitoring requirements (TtEC 2010). Samples are submitted to a National Environmental Laboratory Accreditation Conference (NELAC)-accredited, Department of Defense (DoD) Environmental Laboratory Accreditation Program (ELAP)-certified laboratory, Air Toxics, Inc. located in Folsom, CA, for analysis of target compound list (TCL) VOCs, including PCE, 1,1,1-TCA, and TCE, by modified method TO-15.

A total of 18 soil vapor pressure monitor (SVPM) / soil gas monitoring points have been installed in the neighborhood east of Site 1 at NWIRP Bethpage. These off-site monitoring points consist of eight previously existing SVPMs as well as 10 recently installed SVPMs, as described below. Pressure readings from the SVPMs are used to evaluate the SVECS vacuum field, and along with analytical results of vapor samples collected from these locations, to further evaluate the SVECS operation.

## **2.0 SVECS OPERATION AND MAINTENANCE**

While designed to run autonomously, the SVECS requires regular visits by an operator to record and adjust operational parameters and to perform scheduled maintenance. The SVECS is equipped with telemetry that will alert an on-call operator in the event of a plant shutdown.

### **2.1 Routine Maintenance Activities**

Routine maintenance activities at the SVECS were performed during the operator's weekly visits during this reporting period. These activities include general site inspections (of the grounds, buildings, doors and locks), collection of operational data (vapor flowrates, pressures, vacuums, temperature and photoionization detector [PID] readings), adjustment of system valves, collection of vapor samples (on a monthly and quarterly basis), collection/disposal of condensate if needed, cleaning of filters, switching of lead/lag blower assignments, and preventive maintenance of system equipment.

### **2.2 Non-routine Maintenance / Site Activities**

The following non-routine activities were performed during this reporting period:

- On 5 September and 6 September, ten additional SVPMs were installed along 10<sup>th</sup> Avenue, 11<sup>th</sup> Avenue, and Sycamore Street and one SVPM was decommissioned in place, bringing the total number of off-site SVPMs to 18. Details of these installation activities have been provided under separate cover. Quarterly monitoring of all 18 locations was performed in the Third Quarter, after installation of the 10 additional SVPMs was complete.
- On 5 September, blower motor B-1A failed and the system continued to operate using the second blower motor, B-1B. Blower motor B-1B subsequently failed on 24 September, and the system was down while procurement of two replacement blower motors occurred. Two new blower motors were installed on 3 October, and the system resumed operation. Adjustments were made to the system to limit the system flow rate to 400 scfm in order to avoid overloading the motor.



### 3.0 SVECS MONITORING

Several process vapor samples are collected on a monthly basis to monitor SVECS effectiveness. These samples consist of an influent sample (as well as a duplicate sample), located immediately prior to the VGAC unit, and an effluent sample, located after the VGAC unit and before the exhaust stack. Vapor samples are also collected from the 12 original SVEWs on a quarterly basis to determine the effectiveness of the remediation activities and monitor the capture of the contaminated soil vapor by the SVEWs. In addition, quarterly pressure measurements are collected from the SVEWs and SVPs to monitor the SVECS vacuum field, and soil gas sampling for SVPs is conducted annually (generally in the winter time-frame).

#### 3.1 Monthly Air Quality Monitoring

Analysis of influent and effluent vapor sample locations is performed to evaluate VOC mass removal and the effectiveness of the VGAC adsorption unit. Composite vapor samples are collected using 6-L summa canisters with 30-minute flow regulators.

Treated off-gas discharged at the exhaust stack is subject to emissions limitations and associated calculations approved by the NYSDEC DAR in February 2010. A copy of the NYSDEC approved calculations is presented in the Air Permit Equivalent included as **Appendix A**.

A summary of monthly vapor sampling results collected in July, August, and September (Third Quarter) is presented in **Tables 1, 2, and 3**, respectively. Emission rate calculations for both the influent stream (prior to VGAC treatment) and effluent stream (following VGAC treatment) and estimated monthly mass recoveries are also presented. Emission rates of the influent stream are calculated to monitor progress and determine when influent concentrations have reached levels at which vapor treatment via carbon adsorption is no longer required. The data presented in **Tables 1, 2, and 3** demonstrate that all constituents were within the effluent emission rates (**Appendix A**). Raw analytical data is provided under a separate cover.

#### 3.2 Quarterly Air Quality Monitoring

Composite vapor samples are collected quarterly using 6-L summa canisters with 30-minute flow regulators at six intermediate and six deep SVE wells. The samples are collected for the purpose of tracking and documenting the performance of the SVECS at maintaining hydraulic containment and capturing the contaminated soil vapors (TtEC 2010).

Quarterly vapor samples were collected on 11 September from the 12 SVEWs. A summary of detected compounds is included as **Table 4**. Analytical results of select VOCs (1,1,1-TCA, PCE, and TCE) detected at the 12 SVEWs during the Third Quarter monitoring event are presented graphically as **Figure 5**. Raw analytical data is provided under a separate cover.

### 3.3 Quarterly Off-site Vapor Monitoring

Vacuum readings are collected quarterly from the 12 SVEWs and 18 SVPs in order to monitor the SVECS vacuum field. Valve positions of the SVEWs are also recorded at this time. Results of the Third Quarter vapor monitoring are presented in **Table 5**.

### 3.4 Air Quality Concentration Trends

Historical vapor analytical results through the Third Quarter are presented in **Table 6**. In addition, concentration trends of select VOCs over time for the SVECS combined influent (1,1,1-TCA, PCE, TCE, and total VOCs) and each of the 12 SVEWs (1,1,1-TCA, PCE, and TCE) are presented in **Appendix B**. Concentration trends observed through the Third Quarter are discussed below. In general, unless otherwise indicated, concentrations of 1,1,1-TCA, PCE, and TCE exhibited similar trends at each given location.

- **Combined Influent:** Overall VOC concentrations in the combined influent remained relatively consistent throughout the beginning of the Third Quarter, and then increased slightly at the end of the quarter with total VOC concentrations of 2,223 µg/L, 2,330 µg/L, and 2,892 µg/L in July, August, and September, respectively. Combined influent VOC concentrations had increased in August 2011 (2,820 µg/L) and then gradually leveled off prior to the observed increase in September 2012. Overall concentrations remain well below baseline concentrations observed in December 2009 when a total VOC concentration of 63,650 µg/L was observed.
- **SV-101I:** Concentrations observed at this location decreased overall throughout 2010 and 2011 with minor fluctuations. Concentrations increased throughout 2012 reaching concentrations of 7,200 µg/L TCE, 93 µg/L PCE, and 3,200 µg/L 1,1,1-TCA in the Third Quarter 2012, with PCE exhibiting the greatest increase. All concentrations remain well below baseline concentrations observed in December 2009 (180,000 µg/L TCE, 1,700 µg/L PCE, and 51,000 µg/L 1,1,1-TCA).
- **SV-101D:** No overall trend is discernible. Concentrations decreased through 2010, increased in the Third Quarter 2011, and then decreased in the Fourth Quarter 2011 reaching non-detectable levels in the First Quarter 2012. Concentrations again increased through the Third Quarter 2012 (400 µg/L TCE, 150 µg/L PCE, and 9.9 µg/L 1,1,1-TCA). All concentrations remain well below baseline concentrations observed in December 2009 (100,000 µg/L TCE, 3,200 µg/L PCE, and 26,000 µg/L 1,1,1-TCA).
- **SV-102I:** No overall trend is discernible. Peak concentrations were observed in June 2010 (300 µg/L TCE, 17 µg/L PCE, and 13 µg/L 1,1,1-TCE) with concentrations decreasing throughout the remainder of 2010. Concentrations increased slightly and then decreased again during 2011. Concentrations again increased through 2012, reaching concentrations of 99 µg/L TCE, 6.4 µg/L PCE, and 3.3 µg/L 1,1,1-TCA in the Third Quarter 2012. Though these concentrations are above baseline concentrations observed in December 2009 (5.6 µg/L TCE, 2.4 µg/L PCE, and non-detectable 1,1,1-TCA), they are below peak concentrations observed in June 2010.

- SV-102D: Concentrations observed at this location decreased overall throughout 2010. Concentrations generally increased throughout 2011 but remained below baseline concentrations observed in December 2009 (440 µg/L TCE, 10 µg/L PCE, and 130 µg/L 1,1,1-TCA). Overall concentrations decreased in the First Quarter 2012, then increased through the Third Quarter 2012 (170 µg/L TCE, 24 µg/L PCE, and 3.9 µg/L 1,1,1-TCA). Concentration of TCE and PCE remain well below baseline concentrations observed in December 2009, and concentrations of 1,1,1-TCA, though above baseline concentrations, remain below the peak concentration observed in October 2011 (39 µg/L).
- SV-103I: Concentrations observed at this location have decreased from baseline concentrations observed in December 2009 (900 µg/L TCE, 580 µg/L PCE, and 900 µg/L 1,1,1-TCA), remaining at low or non-detectable levels through the first half of 2011. Concentration increased in the latter half of 2011, decreased in the beginning of 2012, then increased again, reaching concentrations of 130 µg/L TCE, 430 µg/L PCE, and 9.2 µg/L 1,1,1-TCA in the Third Quarter 2012. All concentrations remain below baseline concentrations observed in December 2009.
- SV-103D: Concentrations observed at this location have decreased from peak concentrations observed in December 2009 (3,100 µg/L TCE and 3,000 µg/L 1,1,1-TCA) and March 2010 (28,000 µg/L PCE), decreasing to low or non-detectable levels through the first half of 2011. Concentrations increased in the latter half of 2011, decreased in the beginning of 2012, then increased again, reaching concentrations of 480 µg/L TCE, 4,700 µg/L PCE, and 22 µg/L 1,1,1-TCA in the Third Quarter 2012. All concentrations remain below baseline concentrations observed in December 2009.
- SV-104I: Concentrations observed at this location have decreased from baseline concentrations observed in December 2009 (710 µg/L TCE, 3,100 µg/L PCE, and 730 µg/L 1,1,1-TCA), decreasing through the first half of 2011. Concentrations increased in the Third Quarter 2011, and then decreased through the Second Quarter 2012. Concentrations again increased in the Third Quarter 2012 (73 µg/L TCE, 86 µg/L PCE, and 8.3 µg/L 1,1,1-TCA). All concentrations remain well below baseline concentrations observed in December 2009.
- SV-104D: Concentrations observed at this location have decreased from peak concentrations observed in December 2009 (3,600 µg/L 1,1,1-TCA) and March 2010 (6,000 µg/L TCE and 39,000 µg/L PCE), and continue to decrease through the Third Quarter 2010. Concentrations have varied since then, with concentrations of 1,700 µg/L TCE, 4,600 µg/L PCE, and 620 µg/L 1,1,1-TCA observed in the Third Quarter 2012. All concentrations remain below baseline concentrations observed in December 2009.
- SV-105I: No overall trend is discernible. Peak concentrations were observed in June 2010 for TCE (370 µg/L) and PCE (240 µg/L) and October 2011 for 1,1,1-TCA (29 µg/L) with concentrations of TCE and PCE decreasing throughout the remainder of 2010 and into 2011. Concentrations increased during the latter half of 2011, decreased in early 2012, and then increased somewhat reaching concentrations of 260 µg/L TCE, 100 µg/L PCE, and 26 µg/L 1,1,1-TCA in the Third Quarter 2012. Though these concentrations are above baseline

concentrations observed in December 2009 (76 µg/L TCE, 70 µg/L PCE, and 9.9 µg/L 1,1,1-TCA), they are below peak concentrations observed in June 2010 and October 2011.

- SV-105D: No overall trend is discernible. Peak concentrations were observed for TCE in December 2011 (7,000 µg/L), PCE in December 2009 (2,100 µg/L), and 1,1,1-TCA in September 2010 (1,000 µg/L). Concentrations observed in Third Quarter 2012 (2,200 µg/L TCE, 270 µg/L PCE, and 270 µg/L 1,1,1-TCA) were below baseline concentrations observed in October 2009 for PCE (2,100 µg/L) and 1,1,1-TCA (550 µg/L) and above baseline concentrations for TCE (1,700 µg/L). Concentrations observed in Third Quarter 2012 remain below peak concentrations observed for all three analytes.
- SV-106I: Concentrations observed at this location have decreased from baseline concentrations observed in December 2009 (1,900 µg/L TCE, 390 µg/L PCE, and 220 µg/L 1,1,1-TCA), which were also the peak concentrations observed to date. Concentrations have varied over time, but those observed in the Third Quarter 2012 (260 µg/L TCE, 27 µg/L PCE, and 11 µg/L 1,1,1-TCA) remain well below baseline / peak concentrations.
- SV-106D: Concentrations observed at this location have decreased from baseline concentrations observed in December 2009 (3,900 µg/L TCE, 390 µg/L PCE, and 220 µg/L 1,1,1-TCA), which were also the peak concentrations observed to date. Concentrations have varied over time, but those observed in the Third Quarter 2012 (380 µg/L TCE, 62 µg/L PCE, and 26 µg/L 1,1,1-TCA) remain well below baseline / peak concentrations.

#### **4.0 CONCLUSIONS AND RECOMMENDATIONS**

As stated previously, the intent of the Site 1 SVECS is to prevent further off-site migration of VOC contaminated soil vapor and to the extent practical, capture soil vapor with elevated TCE concentrations. The removal of VOCs by the SVECS indicates that progress is being made toward these goals. Influent vapor analytical data with concentrations of TCE consistently greater than 250 µg/L indicate that the SVECS should continue to be operated on a full-time basis to achieve continued capture of contaminated soil vapor. Monthly monitoring of the combined influent and effluent as well as quarterly monitoring of individual SVEWs should continue, as well as quarterly and annual monitoring of the SVPMs. Ongoing optimization activities should be performed in order to improve system performance.

## **5.0 REFERENCES**

Tetra Tech EC, Inc. (TtEC). 2010. *Final Operation & Maintenance Plan for Soil Vapor Extraction Containment System, Site 1, Former Drum Marshalling Yard at Naval Weapons Industrial Reserve Plant, Bethpage, New York.* June.

Tetra Tech NUS, Inc. (TtNUS). 2012. *Final Supplemental Offsite Soil Vapor Intrusion Monitoring Plan for the Soil Vapor Extraction Containment System, Site 1, Former Drum Marshalling Yard at Naval Weapons Industrial Reserve Plant, Bethpage, New York.* February.

## **TABLES**

**Table 1**  
**Soil Vapor Extraction Containment System**  
**Site 1, Former Drum Marshalling Yard**  
**Naval Weapons Industrial Reserve Plant - Bethpage, NY**  
**Vapor Monitoring Results**  
**July 2012**

Compound	Concentration (mg/m <sup>3</sup> )				Emission Rate <sup>(1),(2)</sup>				Monthly Mass Recovery <sup>(3)</sup> (lbs)
	Influent #1	Influent #2	Average	Effluent	Prior to Treatment		Following Treatment		
					(lbs/hr)	(lbs/yr)	(lbs/hr)	(lbs/yr)	
Acetone	28	NS	28	8.2 J	0.0000	0.4349	0.0000	0.1274	0.0369
Benzene	0.45 J	NS	0.45 J	0	0.0000	0.0070	0.0000	0.0000	0.0006
2-Butanone	8.2 J	NS	8.2 J	0	0.0000	0.1274	0.0000	0.0000	0.0108
Carbon Disulfide	2.6 J	NS	2.6 J	2.4 J	0.0000	0.0404	0.0000	0.0373	0.0034
Carbon Tetrachloride	0.95 J	NS	0.95 J	0	0.0000	0.0148	0.0000	0.0000	0.0013
Chlorobenzene	2.6 J, B	NS	2.6 J, B	2.5 J, B	0.0000	0.0404	0.0000	0.0388	0.0034
Chloroform	7.2	NS	7.2	0	0.0000	0.1118	0.0000	0.0000	0.0095
Cumene	10	NS	10	7.1	0.0000	0.1553	0.0000	0.1103	0.0132
1,4-Dichlorobenzene	0.96 J	NS	0.96 J	0	0.0000	0.0149	0.0000	0.0000	0.0013
1,1-Dichloroethane	17	NS	17	4.1	0.0000	0.2641	0.0000	0.0637	0.0224
1,2-Dichloroethane	1.2 J	NS	1.2 J	0	0.0000	0.0186	0.0000	0.0000	0.0016
cis-1,2-Dichloroethene	190	NS	190	27	0.0003	2.9514	0.0000	0.4194	0.2507
trans-1,2-Dichloroethene	2.3 J	NS	2.3 J	0	0.0000	0.0357	0.0000	0.0000	0.0030
trans-1,3-Dichloropropene	0.91 J	NS	0.91 J	0	0.0000	0.0141	0.0000	0.0000	0.0012
Ethanol	3.8 J	NS	3.8 J	0	0.0000	0.0590	0.0000	0.0000	0.0050
Freon 11	7.1	NS	7.1	7.1	0.0000	0.1103	0.0000	0.1103	0.0094
Freon 12	3.0 J	NS	3.0 J	3.0 J	0.0000	0.0466	0.0000	0.0466	0.0040
Freon 113	56	NS	56	0	0.0001	0.8699	0.0000	0.0000	0.0739
Methylene Chloride	1.2 J	NS	1.2 J	0	0.0000	0.0186	0.0000	0.0000	0.0016
Propylbenzene	0	NS	0	0.91 J	0.0000	0.0000	0.0000	0.0141	0.0000
Tetrachloroethene	620	NS	620	0	0.0011	9.6307	0.0000	0.0000	0.8180
Tetrahydrofuran	6.1	NS	6.1	0	0.0000	0.0948	0.0000	0.0000	0.0080
Toluene	1.4 J	NS	1.4 J	0	0.0000	0.0217	0.0000	0.0000	0.0018
1,2,4-Trichlorobenzene	0.94 J	NS	0.94 J	0	0.0000	0.0146	0.0000	0.0000	0.0012
1,1,1-Trichloroethane	250	NS	250	0	0.0004	3.8834	0.0000	0.0000	0.3298
Trichloroethene	1000	NS	1000	2.5 J	0.0018	15.5334	0.0000	0.0388	1.3193
2,2,4-Trimethylpentane	0.64 J	NS	0.64 J	0	0.0000	0.0099	0.0000	0.0000	0.0008
m,p-Xylene	0.60 J	NS	0.60 J	0	0.0000	0.0093	0.0000	0.0000	0.0008
Total VOCs	2223	NS	2223	65	0.0039	34.5332	0.0001	1.0067	2.9330

**Notes:**

All samples were analyzed for full list VOCs by modified method TO-15. Only detected analytes are presented above. The duplicate influent sample (Influent #2) could not be analyzed due to an issue with the summa canister.

Average Monthly Vapor Temp (°F) = 118  
Average Monthly Flowrate (cfm) = 519  
Average Monthly Flowrate (scfm) = 474  
Operational Hours for the month = 744

(1) Emissions (lbs/hr) = Concentration (mg/m<sup>3</sup>)\*(lb/454000000mg)\*(0.3048^3m<sup>3</sup>/ft<sup>3</sup>)\*exhaust flow (scfm)\*(60min/hour)

(2) Emissions (lbs/yr) = Emissions (lbs/hour)\*(8760hours/yr)

(3) Monthly Mass Removal = AVERAGE FLOWRATE (scfm) \* 0.3048^3m<sup>3</sup>/ft<sup>3</sup> \* INF AVG CONC (ug/m<sup>3</sup>) \* (lb/454000000ug) \* 60 min/hr \* OPERATIONAL TIME (hr)



**Table 2**  
**Soil Vapor Extraction Containment System**  
**Site 1, Former Drum Marshalling Yard**  
**Naval Weapons Industrial Reserve Plant - Bethpage, NY**  
**Vapor Monitoring Results**  
**August 2012**

Compound	Concentration (mg/m <sup>3</sup> )				Emission Rate <sup>(1),(2)</sup>				Monthly Mass Recovery <sup>(3)</sup> (lbs)
	Influent #1	Influent #2	Average	Effluent	Prior to Treatment		Following Treatment		
					(lbs/hr)	(lbs/yr)	(lbs/hr)	(lbs/yr)	
Acetone	13 J	6.8 J	9.9 J	11 J	0.0000	0.1553	0.0000	0.1726	0.0132
Benzene	0	0.69 J	0.35 J	0	0.0000	0.0054	0.0000	0.0000	0.0005
2-Butanone	3.2 J	0	1.6 J	0	0.0000	0.0251	0.0000	0.0000	0.0021
Carbon Tetrachloride	1.2 J	1.3 J	1.3 J	0	0.0000	0.0196	0.0000	0.0000	0.0017
Chloroform	7.1	7.1	7.1	0	0.0000	0.1114	0.0000	0.0000	0.0095
Cumene	70	16	43	16	0.0001	0.6747	0.0000	0.2511	0.0573
1,1-Dichloroethane	16	17	17	6.1	0.0000	0.2589	0.0000	0.0957	0.0220
1,2-Dichloroethane	1.0 J	1.1 J	1.1 J	0	0.0000	0.0165	0.0000	0.0000	0.0014
1,1-Dichloroethene	0	1.1 J	0.6 J	0	0.0000	0.0086	0.0000	0.0000	0.0007
cis-1,2-Dichloroethene	180	180	180	50	0.0003	2.8243	0.0001	0.7845	0.2399
trans-1,2-Dichloroethene	0	2.4 J	1.2 J	0	0.0000	0.0188	0.0000	0.0000	0.0016
Ethanol	5.4 J	3.2 J	4.3 J	2.6 J	0.0000	0.0675	0.0000	0.0408	0.0057
Freon 11	7.9	8.1	8.0	9.4	0.0000	0.1255	0.0000	0.1475	0.0107
Freon 12	3.0 J	3.6 J	3.3 J	3.2 J	0.0000	0.0518	0.0000	0.0502	0.0044
Freon 113	75	76	76	2.3 J	0.0001	1.1846	0.0000	0.0361	0.1006
Hexane	0	0.91 J	0.46 J	0	0.0000	0.0071	0.0000	0.0000	0.0006
2-Hexanone	0.97 J	0	0.49 J	0	0.0000	0.0076	0.0000	0.0000	0.0006
Methylene Chloride	2.6 J	0.90 J	1.8 J	1.1 J	0.0000	0.0275	0.0000	0.0173	0.0023
Propylbenzene	0	0.31 J	0.16 J	0	0.0000	0.0024	0.0000	0.0000	0.0002
Tetrachloroethene	700	710	705	0	0.0013	11.0620	0.0000	0.0000	0.9395
Tetrahydrofuran	5.0	4.7	4.9	0.61 J	0.0000	0.0761	0.0000	0.0096	0.0065
Toluene	0	3.0 J	1.5 J	0	0.0000	0.0235	0.0000	0.0000	0.0020
1,1,1-Trichloroethane	280	280	280	1.1 J	0.0005	4.3934	0.0000	0.0173	0.3731
Trichloroethene	980	980	980	1.8 J	0.0018	15.3769	0.0000	0.0282	1.3060
1,2,4-Trimethylbenzene	0.53 J	0.74 J	0.64 J	0	0.0000	0.0100	0.0000	0.0000	0.0008
2,2,4-Trimethylpentane	1.0 J	1.0 J	1.0 J	0	0.0000	0.0157	0.0000	0.0000	0.0013
m,p-Xylene	0	0.76 J	0.38 J	0	0.0000	0.0060	0.0000	0.0000	0.0005
Total VOCs	2353	2307	2330	105	0.0042	36.5563	0.0002	1.6508	3.1048

**Notes:**

All samples were analyzed for full list VOCs by modified method TO-15. Only detected analytes are presented above.

Average Monthly Vapor Temp (°F) = 118  
Average Monthly Flowrate (cfm) = 524  
Average Monthly Flowrate (scfm) = 479  
Operational Hours for the month = 744

(1) Emissions (lbs/hr) = Concentration (mg/m<sup>3</sup>)\*(lb/454000000mg)\*(0.3048^3m<sup>3</sup>/ft<sup>3</sup>)\*exhaust flow (scfm)\*(60min/hour)

(2) Emissions (lbs/yr) = Emissions (lbs/hour)\*(8760hours/yr)

(3) Monthly Mass Removal = AVERAGE FLOWRATE (scfm) \* 0.3048^3m<sup>3</sup>/ft<sup>3</sup> \* INF AVG CONC (ug/m<sup>3</sup>) \* (lb/454000000ug) \* 60 min/hr \* OPERATIONAL TIME (hr)

**Table 3**  
**Soil Vapor Extraction Containment System**  
**Site 1, Former Drum Marshalling Yard**  
**Naval Weapons Industrial Reserve Plant - Bethpage, NY**  
**Vapor Monitoring Results**  
**September 2012**

Compound	Concentration (mg/m <sup>3</sup> )				Emission Rate <sup>(1),(2)</sup>				Monthly Mass Recovery <sup>(3)</sup> (lbs)
	Influent #1	Influent #2	Average	Effluent	Prior to Treatment		Following Treatment		
					(lbs/hr)	(lbs/yr)	(lbs/hr)	(lbs/yr)	
Acetone	12 J	5.4 J	8.7 J	7.8 J	0.0000	0.1383	0.0000	0.1240	0.0090
Benzene	0.40 J	0	0.20 J	0	0.0000	0.0032	0.0000	0.0000	0.0002
2-Butanone	4.6 J	0	2.3 J	0	0.0000	0.0366	0.0000	0.0000	0.0024
Carbon Disulfide	1.9 J	2.0 J	2.0 J	1.6 J	0.0000	0.0310	0.0000	0.0254	0.0020
Carbon Tetrachloride	1.7 J	0	0.9 J	0	0.0000	0.0135	0.0000	0.0000	0.0009
Chloroform	7.6	7.4	7.5	1.4 J	0.0000	0.1192	0.0000	0.0223	0.0077
Chloromethane	1.7 J	0	0.9 J	1.5 J	0.0000	0.0135	0.0000	0.0238	0.0009
Cumene	19	0	9.5 J	3.8 J	0.0000	0.1510	0.0000	0.0604	0.0098
1,1-Dichloroethane	18	18	18	9.4	0.0000	0.2861	0.0000	0.1494	0.0186
1,2-Dichloroethane	1.1 J	1.2 J	1.2 J	0	0.0000	0.0183	0.0000	0.0000	0.0012
cis-1,2-Dichloroethene	180	170	175	83	0.0003	2.7815	0.0002	1.3192	0.1804
trans-1,2-Dichloroethene	2.3 J	0	1.2 J	0	0.0000	0.0183	0.0000	0.0000	0.0012
Freon 11	7.7	9.3	8.5	4.4 J	0.0000	0.1351	0.0000	0.0699	0.0088
Freon 12	3.3 J	3.2 J	3.3 J	2.3 J	0.0000	0.0517	0.0000	0.0366	0.0033
Freon 113	99	94	97	8.7	0.0002	1.5338	0.0000	0.1383	0.0995
Methylene Chloride	4.1 J	0	2.1 J	0	0.0000	0.0326	0.0000	0.0000	0.0021
2-Propanol	0	0	0	2.6 J	0.0000	0.0000	0.0000	0.0413	0.0000
Tetrachloroethene	800	870	835	2.8 J	0.0015	13.2718	0.0000	0.0445	0.8605
Tetrahydrofuran	49	14	32	0.99 J	0.0001	0.5007	0.0000	0.0157	0.0325
Toluene	0.64 J	0	0.32 J	1.8 J	0.0000	0.0051	0.0000	0.0286	0.0003
1,1,1-Trichloroethane	320	350	335	7.9	0.0006	5.3246	0.0000	0.1256	0.3452
Trichloroethene	1300	1400	1350	7.8	0.0024	21.4575	0.0000	0.1240	1.3913
2,2,4-Trimethylpentane	1.3 J	2.5 J	1.9 J	0	0.0000	0.0302	0.0000	0.0000	0.0020
m,p-Xylene	0.84 J	0	0.42 J	0	0.0000	0.0067	0.0000	0.0000	0.0004
Total VOCs	2836	2947	2892	148	0.0052	45.9601	0.0003	2.3490	2.9801

**Notes:**

All samples were analyzed for full list VOCs by modified method TO-15. Only detected analytes are presented above.

Average Monthly Vapor Temp (°F) = 115  
Average Monthly Flowrate (cfm) = 528  
Average Monthly Flowrate (scfm) = 485  
Operational Hours for the month = 568

(1) Emissions (lbs/hr) = Concentration (mg/m<sup>3</sup>)\*(lb/454000000mg)\*(0.3048^3m<sup>3</sup>/ft<sup>3</sup>)\*exhaust flow (scfm)\*(60min/hour)

(2) Emissions (lbs/yr) = Emissions (lbs/hour)\*(8760hours/yr)

(3) Monthly Mass Removal = AVERAGE FLOWRATE (scfm) \* 0.3048^3m<sup>3</sup>/ft<sup>3</sup> \* INF AVG CONC (ug/m<sup>3</sup>) \* (lb/454000000ug) \* 60 min/hr \* OPERATIONAL TIME (hr)

**Table 4**  
**Soil Vapor Extraction Containment System**  
**Site 1, Former Drum Marshalling Yard**  
**Naval Weapons Industrial Reserve Plant - Bethpage, NY**  
**Third Quarter 2012 Vapor Analytical Results Summary**

Sample ID	SVE 101I	SVE101D	SVE102I	SVE102D	SVE103I	SVE103D	SVE104I	SVE104D	SVE105I	SVE105D	SVE 106I	SVE 106D
Sample Date	09/11/12	09/11/12	09/11/12	09/11/12	09/11/12	09/11/12	09/11/12	09/11/12	09/11/12	09/11/12	09/11/12	09/11/12
<b>Analysis by TO-15 (<math>\mu\text{g}/\text{m}^3</math>)</b>												
1,1,1-Trichloroethane	3200	9.9	3.3 J	3.9 J	9.2	22	8.3	620	26	270	11	26
1,1-Dichloroethane	61	1.0 J	ND	0.51 J	1.5 J	1.9 J	ND	100	5.6	72	1.6 J	4.3
1,2,4-Trimethylbenzene	5.1 J	2.9 J	2.3 J	2.8 J	3.3 J	3.2 J	2.2 J	2.5 J	2.8 J	2.8 J	3.2 J	3.6 J
1,2-Dichlorobenzene	ND	ND	1.0 J	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,2-Dichloroethane	11 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,3,5-Trimethylbenzene	ND	0.68 J	0.89 J	ND	0.92 J	ND	0.75 J	ND	0.92 J	ND	0.84 J	0.97 J
1,3-Dichlorobenzene	ND	ND	ND	1.2 J	1.1 J	ND	ND	ND	ND	ND	ND	ND
1,4-Dichlorobenzene	ND	ND	1.2 J	1.3 J	0.95 J	2.6 J	ND	ND	0.81 J	ND	0.74 J	0.87 J
2,2,4-Trimethylpentane	6.7 J	0.99 J	ND	0.53 J	0.83 J	2.1 J	ND	ND	ND	ND	ND	1.2 J
2-Butanone	ND	2.2 J	ND	3.7 J	ND	ND	ND	ND	ND	ND	ND	4.0 J
2-Propanol	ND	ND	ND	ND	ND	5.5 J	ND	ND	ND	ND	ND	ND
4-ethyltoluene	ND	1.9 J	3.2 J	2.1 J	2.2 J	ND	1.9 J	ND	1.3 J	ND	2.5 J	2.9 J
Acetone	ND	3.6 J	7.2 J	7.1 J	8.4 J	10 J	6.5 J	ND	7.8 J	10 J	3.7 J	11 J
alpha-Chlorotoluene	ND	ND	ND	0.78 J	ND	ND	ND	ND	ND	ND	ND	ND
Benzene	6.7 J	0.59 J	ND	ND	0.97 J	ND	ND	1.5 J	0.63 J	ND	ND	1.1 J
Carbon Disulfide	11 J	1.9 J	1.8 J	2.0 J	1.9 J	5.4 J	5.2 J	6.3 J	1.8 J	3.9 J	2.2 J	ND
Carbon Tetrachloride	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	5.6
Chlorobenzene	20 J, B	2.5 J, B	2.7 J, B	3.3 J, B	2.8 J, B	11 J, B	2.3 J, B	10 J, B	2.9 J, B	5.9 J, B	2.5 J, B	3.1 J, B
Chloroform	ND	5.4	6.6	23	2.3 J	9.3 J	2.8 J	5.8 J	3.2 J	3.8 J	1.5 J	6.9
cis-1,2-Dichloroethene	20 J	2.1 J	ND	1.1 J	19	300	5.0	2200	13	150	7.5	7.1
cis-1,3-Dichloropropene	ND	ND	ND	0.69 J	ND	ND	ND	ND	ND	ND	ND	ND
Cyclohexane	ND	ND	ND	ND	0.47 J	ND	ND	ND	ND	ND	ND	ND
Ethanol	19 J	2.9 J	ND	ND	3.6 J	ND	ND	ND	2.8 J	ND	ND	8.8
Ethylbenzene	4.7 J	1.5 J	1.4 J	0.65 J	2.2 J	2.3 J	0.89 J	2.3 J	ND	ND	1.4 J	1.2 J
Freon 11	ND	1.5 J	2.5 J	11	2.4 J	3.1 J	1.6 J	ND	1.5 J	ND	1.5 J	2.7 J
Freon 113	ND	3.4 J	ND	ND	1.1 J	ND	3.0 J	880	3.2 J	37	3.0 J	13
Freon 12	ND	2.6 J	2.6 J	2.1 J	2.3 J	2.9 J	2.6 J	2.7 J	2.0 J	2.9 J	2.9 J	3.3 J
Heptane	ND	ND	0.83 J	ND	ND	ND	ND	ND	ND	ND	ND	1.0 J
Hexane	3.1 J	ND	0.36 J	ND	0.84 J	ND	ND	ND	ND	ND	ND	1.8 J
m,p-Xylene	12 J	1.7 J	2.8 J	2.2 J	3.9	5.8 J	2.4 J	3.8 J	2.0 J	3.1 J	2.6 J	4.2
Methylene Chloride	ND	2.0 J	ND	0.36 J	0.99 J	ND	ND	ND	ND	ND	ND	1.7 J
o-Xylene	6.3 J	1.8 J	1.6 J	1.4 J	2.1 J	ND	1.2 J	ND	ND	ND	0.93 J	1.9 J
n-Propylbenzene	ND	0.61 J	0.90 J	0.97 J	0.80 J	ND	0.60 J	ND	0.68 J	ND	0.54 J	1.0 J
Tetrachloroethene	93	150	6.4	24	430	4700	86	4600	100	270	27	62
Tetrahydrofuran	ND	3.2	ND	4.0	3.6	ND	1.4 J	8.2 J	ND	1.3 J	ND	4.0
Toluene	26	0.98 J	1.3 J	0.86 J	7.1	4.7 J	0.68 J	2.5 J	0.79 J	ND	0.93 J	15
trans-1,2-Dichloroethene	ND	ND	ND	ND	ND	ND	ND	27	1.5 J	ND	ND	ND
Trichloroethene	7200	400	99	170	130	480	73	1700	260	2200	260	380

**Notes:**

$\mu\text{g}/\text{m}^3$  = micrograms per cubic meter

All samples were analyzed for full list VOCs by modified method TO-15. Only detected analytes are presented above.

**Table 5**  
**Soil Vapor Extraction Containment System**  
**Site 1, Former Drum Marshalling Yard**  
**Naval Weapons Industrial Reserve Plant - Bethpage, NY**  
**Third Quarter 2012 Offsite Soil Vapor Monitoring**

SVPM/ SVEW Location	Vacuum (i.w.)	Valve Position (% open)
<b>Monitoring Date: 10/12/12</b>		
BPS1-SVPM2001S	0.01	--
BPS1-SVPM2001I	0.01	--
BPS1-SVPM2001D	0.01	--
BPS1-SVPM2002S	0.02	--
BPS1-SVPM2002I	0.11	--
BPS1-SVPM2002D	0.12	--
BPS1-SVPM2003S	0.01	--
BPS1-SVPM2003I	0.04	--
BPS1-SVPM2003D	0.04	--
BPS1-SVPM2004S	0.04	--
BPS1-SVPM2004I	0.04	--
BPS1-SVPM2004D	0.06	--
BPS1-SVPM2006S	0.01	--
BPS1-SVPM2006I	0.01	--
BPS1-SVPM2006D	0.02	--
BPS1-SVPM2007S	0.01	--
BPS1-SVPM2007D	0.01	--
BPS1-SVPM2007I	0.01	--
SV-101I	5	60
SV-101D	10	60
SV-102I	5	40
SV-102D	10	40
SV-103I	5	40
SV-103D	8	40
SV-104I	8	40
SV-104D	11	40
SV-105I	5	40
SV-105D	8	40
SV-106I	5	40
SV-106D	8	40

**Notes:**

i.w. = inches of water column

SVEW = soil vapor extraction well

SVPM = soil vapor pressure monitor

Vacuum readings for the SVPMs were measured using a portable Magnehelic® Differential Pressure Gauge 2000-0, with a range of 0-0.50 i.w. Vacuum readings for SVEWs were recorded from dedicated in-line pressure gauges.

Third Quarter 2012 Monitoring was performed in Oct 2012 as the gauge was not reading accurately when performed in Sept 2012.

Table 6  
Soil Vapor Extraction Containment System  
Site 1, Former Drum Marshalling Yard  
Naval Weapons Industrial Reserve Plant - Bethpage, NY  
Quarterly Vapor Monitoring Results of Individual Wells  
Through Third Quarter 2012

Sample ID	SVE 101I											
	12/21/09	03/31/10	06/09/10	09/16/10	12/08/10	03/30/11	06/28/11	09/06/11	10/14/11	02/10/12	05/11/12	09/11/12
<b>Analysis by TO-15 (µg/m<sup>3</sup>)</b>												
1,1,1-Trichloroethane	51000	3900	2600	450	850	300	1	0.7 J	0.7 J	1500	1500	3200
1,1,2,2-Tetrachloroethane	NR	NR	NR	ND	ND	ND	1 J	0.7 J	0.8 J	ND	ND	ND
1,1,2-Trichloroethane	NR	NR	NR	3	5	ND	1 J	0.6 J	0.6 J	4.0 J	ND	ND
1,1-Dichloroethane	1200	65	34	14	31	5	0.8 J	0.4 J	0.4 J	28	28	61
1,1-Dichloroethene	250	ND	ND	4	8	ND	0.7 J	0.4 J	0.5 J	7.6 J	10	ND
1,2,3-Trichloropropane	NR	NR	NR	ND	ND	ND	1 J	0.6 J	0.8 J	NR	NR	NR
1,2,3-Trimethylbenzene	NR	NR	NR	6	2	ND	0.6 J	ND	0.5 J	NR	NR	NR
1,2,4-Trichlorobenzene	NR	NR	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,2,4-Trimethylbenzene	NR	NR	NR	15	5	2	1	ND	0.7 J	ND	3.2 J	5.1 J
1,2-Dibromoethane	NR	NR	NR	ND	ND	ND	ND	ND	0.8 J	ND	ND	ND
1,2-Dichlorobenzene	NR	NR	NR	ND	ND	ND	0.6	ND	0.6 J	ND	ND	ND
1,2-Dichloroethane	NR	30	ND	4	8	ND	0.9	0.5 J	0.5 J	6.9 J	6.4 J	11 J
1,2-Dichloropropane	NR	NR	NR	ND	ND	ND	ND	0.6 J	0.6 J	ND	ND	ND
1,3,5-Trimethylbenzene	NR	NR	NR	4	ND	ND	0.6 J	ND	0.5 J	ND	ND	ND
1,3-Butadiene	NR	NR	NR	ND	ND	ND	0.7	0.4 J	0.4 J	ND	ND	ND
1,3-Dichlorobenzene	NR	NR	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,4-Dichlorobenzene	NR	NR	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,4-Dioxane	NR	NR	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND
2,2,4-Trimethylpentane	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND	ND	6.7 J
2-Butanone	NR	NR	NR	3	1	ND	3	1	1	ND	ND	ND
2-Hexanone	NR	NR	NR	ND	ND	ND	ND	0.5 J	0.5 J	ND	ND	ND
2-Propanol	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND	ND	ND
3-Chloro-1-propene	NR	NR	NR	ND	ND	ND	ND	0.4 J	ND	ND	ND	ND
4-Ethyltoluene	NR	NR	NR	3	ND	ND	0.7 J	ND	ND	ND	1.7 J	ND
4-Methyl-2-pentanone	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND	ND	ND
Acetone	NR	NR	NR	9	5	9	22	16	8	22 J	10 J	ND
alpha-Chlorotoluene	NR	NR	NR	ND	ND	ND	ND	ND	0.5 J	ND	ND	ND
Acrylonitrile	NR	NR	NR	ND	ND	ND	ND	0.4 J	ND	NR	NR	NR
Benzene	NR	NR	NR	1	ND	ND	1	0.4 J	0.6 J	ND	ND	6.7 J
Benzyl Chloride	NR	NR	NR	ND	ND	ND	ND	ND	ND	NR	NR	NR
Bromodichloromethane	NR	NR	NR	23	ND	ND	1	0.8 J	0.8 J	ND	ND	ND
Bromoform	NR	NR	NR	ND	ND	ND	ND	ND	1 J	ND	ND	ND
Bromomethane	NR	NR	NR	ND	ND	ND	0.8	0.6 J	0.5 J	ND	ND	ND
Carbon Disulfide	NR	NR	NR	ND	ND	ND	0.9	0.5 J	0.4 J	ND	ND	11 J
Carbon Tetrachloride	NR	NR	NR	2	ND	ND	2	1 J	1 J	ND	ND	ND
Chlorobenzene	NR	NR	NR	ND	ND	ND	ND	ND	0.5 J	ND	ND	20 J, B
Chlorodibromomethane	NR	NR	NR	ND	ND	ND	ND	ND	0.9 J	NR	NR	NR
Chloroethane	NR	NR	NR	ND	ND	ND	0.6	0.4 J	0.4 J	ND	ND	ND
Chloroform	NR	NR	NR	2	1	ND	1	0.8 J	0.6 J	ND	ND	ND
Chloromethane	NR	NR	NR	1	0.5	ND	1	1	1	7.1 J	ND	ND
cis-1,2-Dichloroethene	480	59	ND	9	15	3	0.7 J	ND	0.4 J	7.1 J	7.4 J	20 J
cis-1,3-Dichloropropene	NR	NR	NR	ND	ND	ND	0.7 J	ND	ND	ND	ND	ND
Cumene	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND	ND	ND
Cyclohexane	NR	NR	NR	ND	ND	ND	0.9	0.7	0.3 J	ND	ND	ND
Dichlorodifluoromethane	NR	NR	NR	3	2	ND	3	2	3	ND	ND	ND
Diisopropyl ether	NR	NR	NR	ND	ND	ND	ND	ND	ND	NR	NR	NR
Ethanol	NR	NR	NR	5	4	2	10	7	3	6.9 J	5.3 J	19 J
Ethyl Acetate	NR	NR	NR	ND	ND	ND	ND	ND	ND	NR	NR	NR
Ethyl tert-butyl ether	NR	NR	NR	ND	ND	ND	0.7 J	ND	ND	NR	NR	NR
Ethylbenzene	NR	NR	NR	3	ND	ND	1	ND	0.5 J	ND	ND	4.7 J
Freon 11	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND	ND	ND
Freon 113	NR	NR	NR	ND	ND	ND	2	2 J	1 J	ND	ND	ND
Freon 114	NR	NR	NR	ND	ND	ND	2	1 J	0.9 J	ND	ND	ND
Freon 12	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND	ND	ND
Heptane	NR	NR	NR	ND	ND	ND	2	ND	0.5 J	ND	ND	ND
Hexachlorobutadiene	NR	NR	NR	ND	ND	ND	2 J	ND	1 J	ND	ND	ND
Hexane	NR	NR	NR	1	ND	ND	3	3	0.7	ND	ND	3.1 J
iso-Octane	NR	NR	NR	2	ND	ND	4	ND	0.6 J	NR	NR	NR
Isopropylbenzene	NR	NR	NR	ND	ND	ND	0.8 J	ND	0.6 J	NR	NR	NR
Isopropyl alcohol	NR	NR	NR	ND	0.8	0.8	2	3	0.7	NR	NR	NR
m,p-Xylene	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND	1.8 J	12 J
Methyl Methacrylate	NR	NR	NR	ND	ND	ND	0.6 J	ND	0.4 J	NR	NR	NR
Methyl-tert-Butyl-Ether	NR	NR	NR	ND	ND	ND	1	1	0.4 J	ND	ND	ND
Methylene Chloride	NR	NR	NR	ND	1	4	8	17	2	2.3 J	ND	ND
MIBK	NR	NR	NR	ND	ND	ND	1	ND	0.4 J	NR	NR	NR
Naphthalene	NR	NR	NR	4	5	5	ND	ND	ND	NR	NR	NR
n-Butane	NR	NR	NR	0.8	0.7	ND	2	0.7	0.8	NR	NR	NR
o-Xylene	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND	ND	6.3 J
p-Isopropyltoluene	NR	NR	NR	ND	ND	ND	0.6 J	ND	ND	NR	NR	NR
n-Propylbenzene	NR	NR	NR	2	ND	ND	0.7 J	ND	ND	ND	ND	ND
Propylene	NR	NR	NR	ND	2	2	ND	ND	0.5	NR	NR	NR
Styrene	NR	NR	NR	ND	ND	ND	0.7 J	ND	ND	ND	ND	ND
tert-Amyl methyl ether	NR	NR	NR	ND	ND	ND	ND	ND	0.5 J	NR	NR	NR
tert-Butyl Alcohol	NR	NR	NR	ND	ND	ND	0.7	0.4 J	0.4 J	NR	NR	NR
Tetrachloroethene	1700	410	260	36	63	10	1	ND	2	48	46	93
Tetrahydrofuran	NR	NR	NR	4	2	2	1	1	0.5 J	ND	ND	ND
Toluene	NR	NR	NR	3	ND	ND	3	0.4 J	0.8	ND	ND	26
Total Xylenes	NR	NR	NR	13	ND	ND	4	ND	2 J	NR	NR	NR
trans-1,2-Dichloroethene	ND	ND	ND	ND	ND	ND	0.7 J	0.4 J	0.4 J	ND	ND	ND
trans-1,3-Dichloropropene	NR	NR	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND
Trichloroethene	180000	18000	14000	1200	2400	560	1	0.6 J	0.6 J	4200	4300	7200
Trichlorofluoromethane	NR	NR	NR	2	1	ND	2	2	2	NR	NR	NR
Vinyl Acetate	NR	NR	NR	1	ND	ND	ND	0.7 J	ND	NR	NR	NR
Vinyl Bromide	NR	NR	NR	ND	ND	ND	1	0.6 J	0.6 J	NR	NR	NR
Vinyl Chloride	ND	ND	ND	ND	ND	ND	0.5 J	0.3 J	0.3 J	ND	ND	ND

**Notes:**

µg/m<sup>3</sup> = micrograms per cubic meter

NR = Not Recorded

NA = Data not available. Vapor samples could not be collected due to water in the extraction wells.

Table 6  
Soil Vapor Extraction Containment System  
Site 1, Former Drum Marshalling Yard  
Naval Weapons Industrial Reserve Plant - Bethpage, NY  
Quarterly Vapor Monitoring Results of Individual Wells  
Through Third Quarter 2012

Sample ID	SVE 101D											
	12/21/09	03/31/10	06/09/10	09/16/10	12/22/10	03/30/11	06/28/11	09/06/11	10/14/11	02/10/12	05/11/12	09/11/12
<b>Analysis by TO-15 (µg/m<sup>3</sup>)</b>												
1,1,1-Trichloroethane	26000	130	53	ND	ND	ND	3	8	0.8 J	ND	3.1 J	9.9
1,1,2,2-Tetrachloroethane	NR	NR	NR	ND	ND	ND	3	0.9 J	1 J	ND	ND	ND
1,1,2-Trichloroethane	NR	NR	NR	ND	ND	ND	2	0.6 J	0.7 J	ND	ND	ND
1,1-Dichloroethane	660	3.9	ND	ND	ND	ND	2	0.9 J	0.5 J	ND	ND	1.0 J
1,1-Dichloroethene	180	2	ND	ND	ND	ND	ND	0.7 J	0.4 J	ND	ND	ND
1,2,3-Trichloropropane	NR	NR	NR	ND	ND	ND	2	0.8 J	0.8 J	NR	NR	NR
1,2,3-Trimethylbenzene	NR	NR	NR	ND	ND	ND	4	1	1	NR	NR	NR
1,2,4-Trichlorobenzene	NR	NR	NR	ND	ND	ND	2 J	ND	ND	ND	3.2 J	ND
1,2,4-Trimethylbenzene	NR	NR	NR	ND	ND	ND	10	3	3	ND	2.7 J	2.9 J
1,2-Dibromoethane	NR	NR	NR	ND	ND	ND	3	ND	0.9 J	ND	0.72 J	ND
1,2-Dichlorobenzene	NR	NR	NR	ND	ND	ND	2 J	ND	0.7 J	ND	ND	ND
1,2-Dichloroethane	NR	0.5	ND	ND	ND	ND	2	0.5 J	0.5 J	ND	ND	ND
1,2-Dichloropropane	NR	NR	NR	ND	ND	ND	2	0.6 J	0.5 J	ND	ND	ND
1,3,5-Trimethylbenzene	NR	NR	NR	ND	ND	ND	3	0.9 J	1	ND	ND	0.68 J
1,3-Butadiene	NR	NR	NR	ND	ND	ND	ND	0.4 J	0.5 J	ND	ND	ND
1,3-Dichlorobenzene	NR	NR	NR	ND	ND	ND	1 J	ND	ND	ND	ND	ND
1,4-Dichlorobenzene	NR	NR	NR	ND	ND	ND	1 J	ND	ND	ND	ND	ND
1,4-Dioxane	NR	NR	NR	ND	ND	ND	1	ND	ND	ND	ND	ND
2,2,4-Trimethylpentane	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND	ND	0.99 J
2-Butanone	NR	NR	NR	ND	1	2	8	1	1	ND	ND	2.2 J
2-Hexanone	NR	NR	NR	ND	ND	ND	2	0.7 J	0.5 J	ND	ND	ND
2-Propanol	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND	ND	ND
3-Chloro-1-propene	NR	NR	NR	ND	ND	ND	ND	0.4 J	0.4 J	ND	ND	ND
4-Ethyltoluene	NR	NR	NR	ND	ND	ND	3	0.8 J	1	ND	1.3 J	1.9 J
4-Methyl-2-pentanone	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND	ND	ND
Acetone	NR	NR	NR	19	10	10	36	4	9	4.4 J	14 J	3.6 J
alpha-Chlorotoluene	NR	NR	NR	ND	ND	ND	2 J	ND	0.5 J	ND	ND	ND
Acrylonitrile	NR	NR	NR	ND	ND	ND	ND	0.4 J	ND	NR	NR	NR
Benzene	NR	NR	NR	ND	1	ND	4	0.5 J	0.5 J	0.59 J	ND	0.59 J
Benzyl Chloride	NR	NR	NR	ND	ND	ND	ND	ND	ND	NR	NR	NR
Bromodichloromethane	NR	NR	NR	ND	ND	ND	3	0.9 J	0.8 J	ND	ND	ND
Bromoform	NR	NR	NR	ND	ND	ND	3 J	ND	1 J	ND	ND	ND
Bromomethane	NR	NR	NR	ND	ND	ND	2	0.6 J	0.5 J	ND	ND	ND
Carbon Disulfide	NR	NR	NR	ND	ND	ND	2	0.8	0.5 J	ND	ND	1.9 J
Carbon Tetrachloride	NR	NR	NR	ND	ND	ND	4	1 J	1	ND	ND	ND
Chlorobenzene	NR	NR	NR	ND	ND	ND	2	0.5 J	0.6 J	ND	ND	2.5 J, B
Chlorodibromomethane	NR	NR	NR	ND	ND	ND	3	0.9 J	1 J	NR	NR	NR
Chloroethane	NR	NR	NR	ND	ND	ND	ND	0.4 J	0.4 J	ND	ND	ND
Chloroform	NR	NR	NR	ND	ND	ND	2	7	0.7 J	ND	0.91 J	5.4
Chloromethane	NR	NR	NR	1	2	ND	3	0.4	1	ND	ND	ND
cis-1,2-Dichloroethene	220	8.5	7.5	ND	3	ND	2	2	0.5 J	ND	ND	2.1 J
cis-1,3-Dichloropropene	NR	NR	NR	ND	ND	ND	2	0.5 J	ND	ND	ND	ND
Cumene	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND	ND	ND
Cyclohexane	NR	NR	NR	ND	ND	ND	2	0.4 J	0.4 J	ND	ND	ND
Dichlorodifluoromethane	NR	NR	NR	2	3	ND	5	3	3	ND	ND	ND
Diisopropyl ether	NR	NR	NR	14	ND	ND	ND	ND	ND	NR	NR	NR
Ethanol	NR	NR	NR	7	5	11	29	1	3	2.4 J	3.2 J	2.9 J
Ethyl Acetate	NR	NR	NR	12	ND	ND	ND	ND	0.5 J	NR	NR	NR
Ethyl tert-butyl ether	NR	NR	NR	ND	ND	ND	1	0.5 J	ND	NR	NR	NR
Ethylbenzene	NR	NR	NR	ND	ND	ND	4	0.8 J	0.9	ND	ND	1.5 J
Freon 11	NR	NR	NR	NR	NR	NR	NR	NR	NR	1.2 J	1.7 J	1.5 J
Freon 113	NR	NR	NR	4	2	ND	4	7	1 J	ND	ND	3.4 J
Freon 114	NR	NR	NR	ND	ND	ND	3	1 J	1 J	ND	ND	ND
Freon 12	NR	NR	NR	NR	NR	NR	NR	NR	NR	1.4 J	2.6 J	2.6 J
Heptane	NR	NR	NR	ND	ND	ND	3	0.4 J	0.5 J	ND	ND	ND
Hexachlorobutadiene	NR	NR	NR	ND	ND	ND	ND	1 J	1 J	ND	ND	ND
Hexane	NR	NR	NR	30	2	2	18	2	0.8	ND	ND	ND
iso-Octane	NR	NR	NR	ND	ND	ND	4	0.7 J	0.6 J	NR	NR	NR
Isopropylbenzene	NR	NR	NR	ND	ND	ND	2	0.5 J	0.6 J	NR	NR	NR
Isopropyl alcohol	NR	NR	NR	9	1	4	9	1	0.9	NR	NR	NR
m,p-Xylene	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND	1.4 J	1.7 J
Methyl Methacrylate	NR	NR	NR	ND	ND	ND	2	0.4 J	3	NR	NR	NR
Methyl-tert-Butyl-Ether	NR	NR	NR	4	ND	ND	5	0.7	0.4 J	ND	ND	ND
Methylene Chloride	NR	NR	NR	150	7	4	84	8	2	0.54 J	1.4 J	2.0 J
MIBK	NR	NR	NR	ND	ND	ND	4	0.5 J	0.5 J	NR	NR	NR
Naphthalene	NR	NR	NR	ND	ND	ND	3	0.8 J	0.9 J	NR	NR	NR
n-Butane	NR	NR	NR	ND	20	7	8	0.6	ND	NR	NR	NR
o-Xylene	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND	0.77 J	1.8 J
p-Isopropyltoluene	NR	NR	NR	ND	ND	ND	2 J	0.6 J	ND	NR	NR	NR
n-Propylbenzene	NR	NR	NR	ND	ND	ND	2	0.7 J	0.8 J	ND	0.32 J	0.61 J
Propylene	NR	NR	NR	ND	ND	ND	ND	ND	0.4	NR	NR	NR
Styrene	NR	NR	NR	ND	ND	ND	1	ND	ND	ND	ND	ND
tert-Amyl methyl ether	NR	NR	NR	ND	ND	ND	2	0.5 J	0.5 J	NR	NR	NR
tert-Butyl Alcohol	NR	NR	NR	ND	ND	ND	2	0.5 J	0.5 J	NR	NR	NR
Tetrachloroethene	3200	1200	1200	ND	4	ND	26	210	2	ND	79	150
Tetrahydrofuran	NR	NR	NR	ND	ND	ND	7	1	1	ND	0.93 J	3.2
Toluene	NR	NR	NR	ND	2	3	12	0.9	1	0.82 J	ND	0.98 J
Total Xylenes	NR	NR	NR	ND	ND	ND	18	3	4	NR	NR	NR
trans-1,2-Dichloroethene	ND	ND	ND	ND	ND	ND	2	0.6 J	0.4 J	ND	ND	ND
trans-1,3-Dichloropropene	NR	NR	NR	ND	ND	ND	2	ND	ND	ND	ND	ND
Trichloroethene	100000	1600	310	3	1	ND	3	120	1 J	ND	200	400
Trichlorofluoromethane	NR	NR	NR	ND	2	ND	4	3	2	NR	NR	NR
Vinyl Acetate	NR	NR	NR	ND	1	ND	ND	0.6 J	ND	NR	NR	NR
Vinyl Bromide	NR	NR	NR	ND	ND	ND	2	0.6 J	0.6 J	NR	NR	NR
Vinyl Chloride	ND	ND	ND	ND	ND	ND	1	0.4 J	0.3 J	ND	ND	ND

**Notes:**  
µg/m<sup>3</sup> = micrograms per cubic mete  
NR = Not Recorded  
NA = Data not available. Vapor samp

Table 6  
Soil Vapor Extraction Containment System  
Site 1, Former Drum Marshalling Yard  
Naval Weapons Industrial Reserve Plant - Bethpage, NY  
Quarterly Vapor Monitoring Results of Individual Wells  
Through Third Quarter 2012

Sample ID	SVE 102I											
	12/21/09	03/31/10	06/09/10	09/16/10	12/22/10	03/30/11	06/28/11	09/06/11	10/14/11	02/10/12	05/11/12	09/11/12
<b>Analysis by TO-15 (µg/m<sup>3</sup>)</b>												
1,1,1-Trichloroethane	ND	ND	13	3	ND	NA	2	3	2	ND	0.60 J	3.3 J
1,1,2,2-Tetrachloroethane	NR	NR	NR	ND	ND	NA	1 J	0.8 J	0.8 J	ND	ND	ND
1,1,2-Trichloroethane	NR	NR	NR	ND	ND	NA	1 J	0.6 J	0.6 J	ND	ND	ND
1,1-Dichloroethane	ND	ND	ND	ND	ND	NA	0.8 J	0.5 J	0.5 J	ND	ND	ND
1,1-Dichloroethene	ND	ND	ND	ND	ND	NA	0.7 J	0.4 J	0.4 J	ND	ND	ND
1,2,3-Trichloropropane	NR	NR	NR	ND	ND	NA	1 J	0.6 J	0.8 J	NR	NR	NR
1,2,3-Trimethylbenzene	NR	NR	NR	10	ND	NA	5	1	2	NR	NR	NR
1,2,4-Trichlorobenzene	NR	NR	NR	ND	ND	NA	1 J	ND	ND	ND	ND	ND
1,2,4-Trimethylbenzene	NR	NR	NR	35	1	NA	18	3	5	0.77 J	1.5 J	2.3 J
1,2-Dibromoethane	NR	NR	NR	ND	ND	NA	1 J	ND	0.8 J	ND	ND	ND
1,2-Dichlorobenzene	NR	NR	NR	ND	ND	NA	0.8 J	ND	ND	ND	ND	1.0 J
1,2-Dichloroethane	NR	ND	ND	ND	ND	NA	0.8	0.4 J	0.4 J	ND	ND	ND
1,2-Dichloropropane	NR	NR	NR	ND	ND	NA	0.9 J	0.6 J	0.6 J	ND	ND	ND
1,3,5-Trimethylbenzene	NR	NR	NR	7	ND	NA	4	0.8 J	1	ND	ND	0.89 J
1,3-Butadiene	NR	NR	NR	ND	ND	NA	NA	0.3 J	ND	ND	ND	ND
1,3-Dichlorobenzene	NR	NR	NR	ND	ND	NA	0.7 J	ND	ND	ND	ND	ND
1,4-Dichlorobenzene	NR	NR	NR	ND	ND	NA	0.6 J	ND	ND	ND	ND	1.2 J
1,4-Dioxane	NR	NR	NR	ND	ND	NA	0.8	ND	0.4 J	ND	ND	ND
2,2,4-Trimethylpentane	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND	ND	ND
2-Butanone	NR	NR	NR	ND	1	NA	4	1	2	ND	ND	ND
2-Hexanone	NR	NR	NR	ND	ND	NA	0.9	0.6 J	0.5 J	ND	ND	ND
2-Propanol	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND	ND	ND
3-Chloro-1-propene	NR	NR	NR	ND	ND	NA	0.6 J	ND	ND	ND	ND	ND
4-Ethyltoluene	NR	NR	NR	5	ND	NA	4	0.8 J	1	0.64 J	0.72 J	3.2 J
4-Methyl-2-pentanone	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND	ND	ND
Acetone	NR	NR	NR	6	5	NA	14	4	7	7.8	9.9 J	7.2 J
alpha-Chlorotoluene	NR	NR	NR	ND	ND	NA	0.7 J	ND	ND	ND	ND	ND
Acrylonitrile	NR	NR	NR	ND	ND	NA	0.5	0.4 J	ND	NR	NR	NR
Benzene	NR	NR	NR	ND	ND	NA	1	0.4 J	0.5 J	ND	ND	ND
Benzyl Chloride	NR	NR	NR	ND	ND	NA	ND	ND	ND	NR	NR	NR
Bromodichloromethane	NR	NR	NR	ND	ND	NA	2	0.8 J	0.7 J	ND	ND	ND
Bromoform	NR	NR	NR	ND	ND	NA	1 J	ND	1 J	ND	ND	ND
Bromomethane	NR	NR	NR	ND	ND	NA	0.8	0.5 J	0.5 J	ND	ND	ND
Carbon Disulfide	NR	NR	NR	ND	ND	NA	0.7	0.5 J	0.4 J	ND	ND	1.8 J
Carbon Tetrachloride	NR	NR	NR	ND	ND	NA	2	1 J	1 J	ND	ND	ND
Chlorobenzene	NR	NR	NR	ND	ND	NA	0.9	ND	0.5 J	ND	ND	2.7 J, B
Chlorodibromomethane	NR	NR	NR	ND	ND	NA	1 J	ND	0.9 J	NR	NR	NR
Chloroethane	NR	NR	NR	ND	ND	NA	0.6	0.4 J	0.3 J	ND	ND	ND
Chloroform	NR	NR	NR	4	ND	NA	3	5	4	0.75 J	1.4 J	6.6
Chloromethane	NR	NR	NR	ND	0.9	NA	1	0.4	0.4	ND	ND	ND
cis-1,2-Dichloroethene	ND	ND	ND	ND	ND	NA	0.7 J	0.5 J	0.5 J	ND	ND	ND
cis-1,3-Dichloropropene	NR	NR	NR	ND	ND	NA	0.7 J	ND	ND	ND	ND	ND
Cumene	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND	ND	ND
Cyclohexane	NR	NR	NR	ND	ND	NA	0.6 J	ND	0.4 J	ND	ND	ND
Dichlorodifluoromethane	NR	NR	NR	ND	2	NA	3	2	2	ND	ND	ND
Diisopropyl ether	NR	NR	NR	ND	ND	NA	NA	ND	ND	NR	NR	NR
Ethanol	NR	NR	NR	2	3	NA	8	2	4	3.0 J	ND	ND
Ethyl Acetate	NR	NR	NR	ND	ND	NA	NA	ND	ND	NR	NR	NR
Ethyl tert-butyl ether	NR	NR	NR	ND	ND	NA	0.7 J	ND	ND	NR	NR	NR
Ethylbenzene	NR	NR	NR	3	ND	NA	4	0.8 J	1	ND	ND	1.4 J
Freon 11	NR	NR	NR	NR	NR	NR	NR	NR	NR	1.1 J	2.0 J	2.5 J
Freon 113	NR	NR	NR	ND	ND	NA	2	1 J	1 J	ND	ND	ND
Freon 114	NR	NR	NR	ND	ND	NA	2	1 J	1 J	ND	ND	ND
Freon 12	NR	NR	NR	NR	NR	NR	NR	NR	NR	1.9 J	2.4 J	2.6 J
Heptane	NR	NR	NR	ND	ND	NA	1	ND	0.5 J	ND	ND	0.83 J
Hexachlorobutadiene	NR	NR	NR	ND	ND	NA	3	1 J	1 J	ND	ND	ND
Hexane	NR	NR	NR	ND	1	NA	1	0.8	0.8	ND	ND	0.36 J
iso-Octane	NR	NR	NR	ND	ND	NA	1	0.6 J	0.6 J	NR	NR	NR
Isopropylbenzene	NR	NR	NR	ND	ND	NA	1	ND	0.6 J	NR	NR	NR
Isopropyl alcohol	NR	NR	NR	ND	0.6	NA	2	1	0.8	NR	NR	NR
m,p-Xylene	NR	NR	NR	NR	NR	NA	NR	NR	NR	0.63 J	0.97 J	2.8 J
Methyl Methacrylate	NR	NR	NR	ND	ND	NA	0.6 J	ND	ND	NR	NR	NR
Methyl-tert-Butyl-Ether	NR	NR	NR	ND	ND	NA	0.7	0.5 J	0.4 J	ND	ND	ND
Methylene Chloride	NR	NR	NR	ND	6	NA	4	3	3	1.3 J	1.0 J	ND
MIBK	NR	NR	NR	ND	ND	NA	0.8 J	ND	ND	NR	NR	NR
Naphthalene	NR	NR	NR	3	ND	NA	5	0.8 J	1	NR	NR	NR
n-Butane	NR	NR	NR	4	2	NA	1	0.4 J	ND	NR	NR	NR
o-Xylene	NR	NR	NR	NR	NR	NA	NR	NR	NR	ND	ND	1.6 J
p-Isopropyltoluene	NR	NR	NR	ND	ND	NA	1 J	ND	ND	NR	NR	NR
n-Propylbenzene	NR	NR	NR	3	ND	NA	2	0.6 J	0.9 J	ND	ND	0.90 J
Propylene	NR	NR	NR	ND	ND	NA	ND	ND	ND	NR	NR	NR
Styrene	NR	NR	NR	ND	ND	NA	0.7 J	ND	ND	ND	ND	ND
tert-Amyl methyl ether	NR	NR	NR	ND	ND	NA	0.7 J	ND	0.4 J	NR	NR	NR
tert-Butyl Alcohol	NR	NR	NR	ND	ND	NA	1	0.5 J	0.5 J	NR	NR	NR
Tetrachloroethene	2.4	1.4	17	6	NR	NA	3	6	6	ND	1.6 J	6.4
Tetrahydrofuran	NR	NR	NR	6	0.6	NA	5	1	1	ND	ND	ND
Toluene	NR	NR	NR	3	1	NA	4	0.8	1	0.66 J	ND	1.3 J
Total Xylenes	NR	NR	NR	22	ND	NA	20	3	6	NR	NR	NR
trans-1,2-Dichloroethene	ND	ND	ND	ND	ND	NA	0.7 J	0.4 J	0.4 J	ND	ND	ND
trans-1,3-Dichloropropene	NR	NR	NR	ND	ND	NA	0.7 J	ND	ND	ND	ND	ND
Trichloroethene	5.6	3.8	300	88	3	NA	34	76	52	10	26	99
Trichlorofluoromethane	NR	NR	NR	ND	1	NA	2	2	2	NR	NR	NR
Vinyl Acetate	NR	NR	NR	ND	ND	NA	ND	0.6 J	ND	NR	NR	NR
Vinyl Bromide	NR	NR	NR	ND	ND	NA	1	0.6 J	0.6 J	NR	NR	NR
Vinyl Chloride	ND	ND	ND	ND	ND	NA	0.5 J	0.4 J	0.3 J	ND	ND	ND

**Notes:**  
µg/m<sup>3</sup> = micrograms per cubic mete  
NR = Not Recorded  
NA = Data not available. Vapor samp



Table 6  
Soil Vapor Extraction Containment System  
Site 1, Former Drum Marshalling Yard  
Naval Weapons Industrial Reserve Plant - Bethpage, NY  
Quarterly Vapor Monitoring Results of Individual Wells  
Through Third Quarter 2012

Sample ID	SVE 102D											
	12/21/09	03/31/10	06/09/10	09/16/10	12/08/10	03/30/11	06/28/11	09/06/11	10/14/11	02/10/12	05/11/12	09/11/12
<b>Analysis by TO-15 (µg/m<sup>3</sup>)</b>												
1,1,1-Trichloroethane	130	53	14	7	2	2	6	4	5	1.4 J	1.2 J	3.9 J
1,1,2,2-Tetrachloroethane	NR	NR	NR	ND	ND	ND	1 J	0.9 J	1 J	ND	ND	ND
1,1,2-Trichloroethane	NR	NR	NR	ND	ND	ND	1 J	0.6 J	0.8 J	ND	ND	ND
1,1-Dichloroethane	ND	2.7	ND	ND	ND	ND	1	0.6 J	0.7 J	ND	ND	0.51 J
1,1-Dichloroethene	ND	ND	ND	ND	ND	ND	1	0.6 J	0.6 J	ND	ND	ND
1,2,3-Trichloropropane	NR	NR	NR	ND	ND	ND	ND	0.7 J	0.9 J	NR	NR	NR
1,2,3-Trimethylbenzene	NR	NR	NR	5	ND	ND	7	1	2	NR	NR	NR
1,2,4-Trichlorobenzene	NR	NR	NR	ND	ND	ND	2 J	ND	0.8 J	ND	ND	ND
1,2,4-Trimethylbenzene	NR	NR	NR	18	2	2	22	4	6	ND	2.3 J	2.8 J
1,2-Dibromoethane	NR	NR	NR	ND	ND	ND	1 J	ND	1 J	ND	ND	ND
1,2-Dichlorobenzene	NR	NR	NR	ND	ND	ND	1 J	ND	0.8 J	ND	ND	ND
1,2-Dichloroethane	NR	ND	ND	ND	ND	ND	0.9	0.5 J	0.5 J	ND	ND	ND
1,2-Dichloropropane	NR	NR	NR	ND	ND	ND	1	0.6 J	0.6 J	ND	ND	ND
1,3,5-Trimethylbenzene	NR	NR	NR	4	ND	ND	4	ND	1	ND	ND	ND
1,3-Butadiene	NR	NR	NR	1	ND	ND	ND	0.3 J	0.4 J	ND	ND	ND
1,3-Dichlorobenzene	NR	NR	NR	ND	ND	ND	0.8 J	ND	0.7 J	ND	ND	1.2 J
1,4-Dichlorobenzene	NR	NR	NR	ND	ND	ND	0.8 J	ND	0.6 J	ND	ND	1.3 J
1,4-Dioxane	NR	NR	NR	ND	ND	ND	1	ND	0.6 J	ND	ND	ND
2,2,4-Trimethylpentane	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND	ND	0.53 J
2-Butanone	NR	NR	NR	4	0.9	0.7	5	1	1	ND	ND	3.7 J
2-Hexanone	NR	NR	NR	ND	ND	ND	0.9 J	0.6 J	0.6 J	ND	ND	ND
2-Propanol	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND	ND	ND
3-Chloro-1-propene	NR	NR	NR	ND	ND	ND	0.7 J	0.4 J	ND	ND	ND	ND
4-Ethyltoluene	NR	NR	NR	3	ND	ND	4	1	1	0.36 J	1.0 J	2.1 J
4-Methyl-2-pentanone	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND	ND	ND
Acetone	NR	NR	NR	10	8	6	12	4	4	8.4	6.0 J	7.1 J
alpha-Chlorotoluene	NR	NR	NR	ND	ND	ND	0.9 J	ND	0.6 J	ND	ND	0.78 J
Acrylonitrile	NR	NR	NR	ND	ND	ND	0.5	0.4 J	ND	NR	NR	NR
Benzene	NR	NR	NR	ND	ND	ND	1	0.5 J	0.9	ND	ND	ND
Benzyl Chloride	NR	NR	NR	ND	ND	ND	ND	ND	ND	NR	NR	NR
Bromodichloromethane	NR	NR	NR	ND	ND	ND	2	0.9 J	1 J	ND	ND	ND
Bromoform	NR	NR	NR	ND	ND	ND	2 J	ND	1 J	ND	ND	ND
Bromomethane	NR	NR	NR	ND	ND	ND	1	0.6 J	0.5 J	ND	ND	ND
Carbon Disulfide	NR	NR	NR	ND	ND	ND	0.9	0.5 J	0.5 J	ND	ND	2.0 J
Carbon Tetrachloride	NR	NR	NR	ND	ND	ND	2	2	2	ND	ND	ND
Chlorobenzene	NR	NR	NR	ND	ND	ND	1 J	ND	0.7 J	ND	ND	3.3 J, B
Chlorodibromomethane	NR	NR	NR	ND	ND	ND	2 J	0.9 J	1 J	NR	NR	NR
Chloroethane	NR	NR	NR	ND	ND	ND	0.7	0.4 J	0.4 J	ND	ND	ND
Chloroform	NR	NR	NR	11	2	3	9	14	17	19	19	23
Chloromethane	NR	NR	NR	ND	1	0.6	1	0.4	0.4	ND	ND	ND
cis-1,2-Dichloroethene	ND	1.4	ND	ND	0.9	ND	1	0.5 J	0.9	ND	ND	1.1 J
cis-1,3-Dichloropropene	NR	NR	NR	ND	ND	ND	0.9 J	ND	0.6 J	ND	ND	0.69 J
Cumene	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND	ND	ND
Cyclohexane	NR	NR	NR	ND	ND	ND	0.7 J	0.5 J	0.4 J	ND	ND	ND
Dichlorodifluoromethane	NR	NR	NR	2	3	2	4	3	3	ND	ND	ND
Diisopropyl ether	NR	NR	NR	ND	ND	ND	ND	ND	ND	NR	NR	NR
Ethanol	NR	NR	NR	5	3	4	3	1	1	ND	ND	ND
Ethyl Acetate	NR	NR	NR	ND	ND	ND	ND	ND	ND	NR	NR	NR
Ethyl tert-butyl ether	NR	NR	NR	ND	ND	ND	0.8 J	0.4 J	0.5 J	NR	NR	NR
Ethylbenzene	NR	NR	NR	3	ND	ND	4	ND	1	ND	ND	0.65 J
Freon 11	NR	NR	NR	NR	NR	NR	NR	NR	NR	4.8	5.8	11
Freon 113	NR	NR	NR	ND	ND	ND	3	2	2	ND	ND	ND
Freon 114	NR	NR	NR	ND	ND	ND	2	1 J	1 J	ND	ND	ND
Freon 12	NR	NR	NR	NR	NR	NR	NR	NR	NR	2.6 J	2.1 J	2.1 J
Heptane	NR	NR	NR	ND	ND	ND	1	0.4 J	0.6 J	ND	ND	ND
Hexachlorobutadiene	NR	NR	NR	ND	ND	ND	3	1 J	2 J	ND	ND	ND
Hexane	NR	NR	NR	1	ND	ND	1	0.8	0.5 J	ND	ND	ND
iso-Octane	NR	NR	NR	ND	ND	ND	1	1	0.7 J	NR	NR	NR
Isopropylbenzene	NR	NR	NR	ND	ND	ND	1	0.5 J	0.8 J	NR	NR	NR
Isopropyl alcohol	NR	NR	NR	1	ND	ND	2	1	1	NR	NR	NR
m,p-Xylene	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND	1.4 J	2.2 J
Methyl Methacrylate	NR	NR	NR	ND	ND	ND	0.8 J	0.4 J	0.4 J	NR	NR	NR
Methyl-tert-Butyl-Ether	NR	NR	NR	ND	ND	ND	0.9	0.5 J	0.4 J	ND	ND	ND
Methylene Chloride	NR	NR	NR	7	2	ND	4	2	0.9	1.0 J	ND	0.36 J
MIBK	NR	NR	NR	ND	ND	ND	1	0.4 J	0.4 J	NR	NR	NR
Naphthalene	NR	NR	NR	3	ND	ND	6	3	2	NR	NR	NR
n-Butane	NR	NR	NR	ND	2	ND	2	2	ND	NR	NR	NR
o-Xylene	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND	ND	1.4 J
p-Isopropyltoluene	NR	NR	NR	ND	ND	ND	1	ND	0.7 J	NR	NR	NR
n-Propylbenzene	NR	NR	NR	ND	ND	ND	3	0.7 J	1	ND	ND	0.97 J
Propylene	NR	NR	NR	ND	ND	ND	ND	ND	ND	NR	NR	NR
Styrene	NR	NR	NR	ND	ND	ND	0.8 J	ND	0.5 J	ND	ND	ND
tert-Amyl methyl ether	NR	NR	NR	ND	ND	ND	0.9 J	0.5 J	0.5 J	NR	NR	NR
tert-Butyl Alcohol	NR	NR	NR	ND	ND	ND	1	0.4 J	0.6	NR	NR	NR
Tetrachloroethene	10	31	31	19	3	9	25	23	39	5.9	6.5	24
Tetrahydrofuran	NR	NR	NR	36	7	3	6	1	1	0.54 J	0.74 J	4.0
Toluene	NR	NR	NR	3	ND	ND	4	0.8	2	0.49 J	0.99 J	0.86 J
Total Xylenes	NR	NR	NR	15	ND	ND	22	2 J	7	NR	NR	NR
trans-1,2-Dichloroethene	ND	ND	ND	ND	ND	ND	1	0.5 J	0.5 J	ND	ND	ND
trans-1,3-Dichloropropene	NR	NR	NR	ND	ND	ND	0.8 J	ND	0.5 J	ND	ND	ND
Trichloroethene	440	390	190	110	17	21	89	81	87	34	58	170
Trichlorofluoromethane	NR	NR	NR	5	2	6	9	12	13	NR	NR	NR
Vinyl Acetate	NR	NR	NR	ND	ND	ND	2	ND	ND	NR	NR	NR
Vinyl Bromide	NR	NR	NR	ND	ND	ND	1	0.6 J	0.6 J	NR	NR	NR
Vinyl Chloride	ND	ND	ND	ND	ND	ND	0.6	0.4 J	0.3 J	ND	ND	ND

**Notes:**  
µg/m<sup>3</sup> = micrograms per cubic mete  
NR = Not Recorded  
NA = Data not available. Vapor samp



Table 6  
Soil Vapor Extraction Containment System  
Site 1, Former Drum Marshalling Yard  
Naval Weapons Industrial Reserve Plant - Bethpage, NY  
Quarterly Vapor Monitoring Results of Individual Wells  
Through Third Quarter 2012

Sample ID	SVE 103I											
	12/21/09	03/31/10	06/09/10	09/16/10	12/08/10	03/30/11	06/28/11	09/06/11	10/14/11	02/10/12	05/11/12	09/11/12
<b>Analysis by TO-15 (µg/m<sup>3</sup>)</b>												
1,1,1-Trichloroethane	900	ND	ND	ND	ND	ND	0.9 J	6	6	ND	1.6 J	9.2
1,1,2,2-Tetrachloroethane	NR	NR	NR	ND	ND	ND	1 J	0.9 J	ND	ND	ND	ND
1,1,2-Trichloroethane	NR	NR	NR	ND	ND	ND	0.7 J	0.7 J	ND	ND	ND	ND
1,1-Dichloroethane	26	ND	ND	ND	ND	ND	0.6 J	2	2	ND	0.75 J	1.5 J
1,1-Dichloroethene	ND	ND	ND	ND	ND	ND	0.6 J	0.6 J	ND	ND	ND	ND
1,2,3-Trichloropropane	NR	NR	NR	ND	ND	ND	0.9 J	0.8 J	0.6 J	NR	NR	NR
1,2,3-Trimethylbenzene	NR	NR	NR	ND	ND	ND	4	1	2	NR	NR	NR
1,2,4-Trichlorobenzene	NR	NR	NR	ND	ND	ND	1 J	ND	ND	ND	ND	ND
1,2,4-Trimethylbenzene	NR	NR	NR	2	ND	1	14	3	5	2.2 J	3.3 J	3.3 J
1,2-Dibromoethane	NR	NR	NR	ND	ND	ND	0.9 J	0.8 J	ND	ND	ND	ND
1,2-Dichlorobenzene	NR	NR	NR	ND	ND	ND	0.7 J	ND	ND	ND	ND	ND
1,2-Dichloroethane	NR	ND	ND	ND	ND	ND	0.7 J	0.5 J	ND	ND	ND	ND
1,2-Dichloropropane	NR	NR	NR	ND	ND	ND	0.7 J	0.6 J	ND	ND	ND	ND
1,3,5-Trimethylbenzene	NR	NR	NR	ND	ND	ND	2	0.9 J	1	ND	ND	0.92 J
1,3-Butadiene	NR	NR	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,3-Dichlorobenzene	NR	NR	NR	ND	ND	ND	ND	ND	ND	1.1 J	ND	1.1 J
1,4-Dichlorobenzene	NR	NR	NR	ND	ND	ND	ND	ND	ND	ND	ND	0.95 J
1,4-Dioxane	NR	NR	NR	ND	ND	ND	0.5 J	0.6 J	0.4 J	ND	ND	ND
2,2,4-Trimethylpentane	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND	ND	0.83 J
2-Butanone	NR	NR	NR	2	ND	ND	4	1	1	4.7 J	5.2 J	ND
2-Hexanone	NR	NR	NR	ND	ND	ND	0.6 J	0.5 J	ND	ND	0.24 J	ND
2-Propanol	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND	ND	ND
3-Chloro-1-propene	NR	NR	NR	ND	ND	ND	0.4 J	0.4 J	ND	ND	ND	ND
4-Ethyltoluene	NR	NR	NR	ND	ND	ND	3	0.8 J	1	1.5 J	1.4 J	2.2 J
4-Methyl-2-pentanone	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND	ND	ND
Acetone	NR	NR	NR	13	6	6	17	4	3	65	27	8.4 J
alpha-Chlorotoluene	NR	NR	NR	ND	ND	ND	0.6 J	ND	ND	ND	ND	ND
Acrylonitrile	NR	NR	NR	ND	ND	ND	0.4 J	0.4 J	ND	NR	NR	NR
Benzene	NR	NR	NR	2	ND	ND	1	0.6 J	0.5 J	ND	ND	0.97 J
Benzyl Chloride	NR	NR	NR	ND	ND	ND	ND	ND	ND	NR	NR	NR
Bromodichloromethane	NR	NR	NR	ND	ND	ND	1 J	0.8 J	ND	ND	ND	ND
Bromoform	NR	NR	NR	ND	ND	ND	1 J	1 J	ND	ND	ND	ND
Bromomethane	NR	NR	NR	ND	ND	ND	0.6 J	0.6 J	0.4 J	ND	ND	ND
Carbon Disulfide	NR	NR	NR	ND	ND	ND	0.6 J	0.6 J	0.5 J	ND	ND	1.9 J
Carbon Tetrachloride	NR	NR	NR	ND	ND	ND	1	1 J	0.9 J	ND	ND	ND
Chlorobenzene	NR	NR	NR	ND	ND	ND	0.6 J	0.5 J	0.5 J	ND	ND	2.8 J, B
Chlorodibromomethane	NR	NR	NR	ND	ND	ND	1 J	0.9 J	ND	NR	NR	NR
Chloroethane	NR	NR	NR	ND	ND	ND	0.5 J	0.5 J	0.3 J	ND	ND	ND
Chloroform	NR	NR	NR	ND	ND	ND	0.8 J	3	2	19	1.1 J	2.3 J
Chloromethane	NR	NR	NR	1	1	1	1	0.4	0.4 J	ND	ND	ND
cis-1,2-Dichloroethene	58	ND	ND	1	ND	1	0.5 J	16	12	18	16	19
cis-1,3-Dichloropropene	NR	NR	NR	ND	ND	ND	0.5 J	ND	ND	ND	ND	ND
Cumene	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND	ND	ND
Cyclohexane	NR	NR	NR	1	ND	ND	0.8	0.5 J	ND	ND	ND	0.47 J
Dichlorodifluoromethane	NR	NR	NR	3	2	2	3	2	2	ND	ND	ND
Diisopropyl ether	NR	NR	NR	3	ND	ND	ND	ND	ND	NR	NR	NR
Ethanol	NR	NR	NR	17	3	6	14	2	1	ND	5.9 J	3.6 J
Ethyl Acetate	NR	NR	NR	3	ND	ND	ND	ND	ND	NR	NR	NR
Ethyl tert-butyl ether	NR	NR	NR	ND	ND	ND	0.6 J	0.5 J	ND	NR	NR	NR
Ethylbenzene	NR	NR	NR	1	ND	ND	3	0.8 J	1	ND	ND	2.2 J
Freon 11	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND	1.2 J	2.4 J
Freon 113	NR	NR	NR	ND	ND	ND	2	2	1 J	ND	ND	1.1 J
Freon 114	NR	NR	NR	ND	ND	ND	1 J	1 J	0.8 J	ND	ND	ND
Freon 12	NR	NR	NR	NR	NR	NR	NR	NR	NR	2.0 J	2.5 J	2.3 J
Heptane	NR	NR	NR	2	ND	ND	1	0.5 J	ND	ND	ND	ND
Hexachlorobutadiene	NR	NR	NR	ND	ND	ND	2 J	1 J	1 J	ND	ND	ND
Hexane	NR	NR	NR	6	ND	ND	3	1	0.6 J	ND	ND	0.84 J
iso-Octane	NR	NR	NR	2	ND	ND	1	0.7 J	0.5 J	NR	NR	NR
Isopropylbenzene	NR	NR	NR	ND	ND	ND	0.8 J	0.6 J	ND	NR	NR	NR
Isopropyl alcohol	NR	NR	NR	4	ND	3	2	1	0.5 J	NR	NR	NR
m,p-Xylene	NR	NR	NR	NR	NR	NR	NR	NR	NR	1.8 J	1.6 J	3.9
Methyl Methacrylate	NR	NR	NR	ND	ND	ND	0.5 J	0.4 J	ND	NR	NR	NR
Methyl-tert-Butyl-Ether	NR	NR	NR	1	ND	ND	0.7 J	0.7 J	0.6 J	ND	ND	ND
Methylene Chloride	NR	NR	NR	29	ND	2	8	4	1	9.0	1.0 J	0.99 J
MIBK	NR	NR	NR	ND	ND	ND	ND	0.5 J	ND	NR	NR	NR
Naphthalene	NR	NR	NR	ND	ND	ND	7	0.9 J	2	NR	NR	NR
n-Butane	NR	NR	NR	3	1	1	3	0.6	ND	NR	NR	NR
o-Xylene	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND	1.2 J	2.1 J
p-Isopropyltoluene	NR	NR	NR	ND	ND	ND	0.9 J	0.6 J	ND	NR	NR	NR
n-Propylbenzene	NR	NR	NR	ND	ND	ND	2	0.7 J	0.9 J	ND	0.45 J	0.80 J
Propylene	NR	NR	NR	ND	ND	ND	2	ND	ND	NR	NR	NR
Styrene	NR	NR	NR	ND	ND	ND	0.6 J	ND	ND	ND	ND	ND
tert-Amyl methyl ether	NR	NR	NR	ND	ND	ND	0.6 J	0.5 J	ND	NR	NR	NR
tert-Butyl Alcohol	NR	NR	NR	ND	ND	ND	0.8	0.7	0.9	NR	NR	NR
Tetrachloroethene	580	ND	ND	ND	ND	2	1 J	420	590	140	200	430
Tetrahydrofuran	NR	NR	NR	1	ND	ND	4	1	1	3.4 J	2.9	3.6
Toluene	NR	NR	NR	6	ND	1	6	0.9	1	ND	0.65 J	7.1
Total Xylenes	NR	NR	NR	6	ND	ND	15	3	5	NR	NR	NR
trans-1,2-Dichloroethene	580	ND	ND	ND	ND	ND	0.6 J	1	1	ND	ND	ND
trans-1,3-Dichloropropene	NR	NR	NR	ND	ND	ND	0.5 J	ND	ND	ND	ND	ND
Trichloroethene	900	0.9	ND	ND	ND	ND	0.9 J	100	97	29	47	130
Trichlorofluoromethane	NR	NR	NR	2	ND	1	2	2	2	NR	NR	NR
Vinyl Acetate	NR	NR	NR	3	ND	ND	ND	ND	ND	NR	NR	NR
Vinyl Bromide	NR	NR	NR	ND	ND	ND	0.7 J	0.7 J	ND	NR	NR	NR
Vinyl Chloride	ND	ND	ND	ND	ND	ND	0.4 J	0.4 J	0.3 J	ND	ND	ND

**Notes:**  
µg/m<sup>3</sup> = micrograms per cubic mete  
NR = Not Recorded  
NA = Data not available. Vapor samp

Table 6  
Soil Vapor Extraction Containment System  
Site 1, Former Drum Marshalling Yard  
Naval Weapons Industrial Reserve Plant - Bethpage, NY  
Quarterly Vapor Monitoring Results of Individual Wells  
Through Third Quarter 2012

Sample ID	SVE 103D											
	12/21/09	03/31/10	06/09/10	09/16/10	12/08/10	03/30/11	06/28/11	09/06/11	10/14/11	02/10/12	05/11/12	09/11/12
<b>Analysis by TO-15 (µg/m<sup>3</sup>)</b>												
1,1,1-Trichloroethane	3000	1100	230	ND	13	ND	2 J	20	31	7.4 J	6.9 J	22
1,1,2,2-Tetrachloroethane	NR	NR	NR	ND	ND	ND	2 J	2 J	12 J	ND	ND	ND
1,1,2-Trichloroethane	NR	NR	NR	ND	ND	ND	1 J	2 J	10 J	ND	ND	ND
1,1-Dichloroethane	82	69	ND	ND	2	2	1 J	4	9	1.6 J	1.5 J	1.9 J
1,1-Dichloroethene	ND	ND	ND	ND	ND	ND	1 J	2	6 J	ND	ND	ND
1,2,3-Trichloropropane	NR	NR	NR	ND	ND	ND	2 J	2 J	11 J	NR	NR	NR
1,2,3-Trimethylbenzene	NR	NR	NR	5	ND	2	4	ND	7 J	NR	NR	NR
1,2,4-Trichlorobenzene	NR	NR	NR	ND	ND	ND	ND	ND	9 J	ND	ND	ND
1,2,4-Trimethylbenzene	NR	NR	NR	8	2	7	12	ND	9 J	ND	2.4 J	3.2 J
1,2-Dibromoethane	NR	NR	NR	ND	ND	ND	2 J	2 J	11 J	ND	ND	ND
1,2-Dichlorobenzene	NR	NR	NR	ND	ND	ND	ND	ND	9 J	ND	ND	ND
1,2-Dichloroethane	NR	ND	ND	ND	ND	ND	1 J	1 J	6 J	ND	ND	ND
1,2-Dichloropropane	NR	NR	NR	ND	ND	ND	1 J	1 J	8 J	ND	ND	ND
1,3,5-Trimethylbenzene	NR	NR	NR	ND	ND	2	3	ND	8 J	ND	ND	ND
1,3-Butadiene	NR	NR	NR	ND	ND	ND	1	0.8 J	ND	ND	ND	ND
1,3-Dichlorobenzene	NR	NR	NR	ND	ND	ND	ND	ND	8 J	ND	ND	ND
1,4-Dichlorobenzene	NR	NR	NR	ND	ND	ND	ND	ND	8 J	ND	ND	2.6 J
1,4-Dioxane	NR	NR	NR	ND	ND	ND	0.9 J	1	6 J	ND	ND	ND
2,2,4-Trimethylpentane	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND	ND	2.1 J
2-Butanone	NR	NR	NR	4	1	4	5	2	6 J	ND	ND	ND
2-Hexanone	NR	NR	NR	ND	ND	ND	1 J	1 J	5 J	ND	ND	ND
2-Propanol	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND	ND	5.5 J
3-Chloro-1-propene	NR	NR	NR	ND	ND	ND	0.8 J	1 J	4 J	ND	ND	ND
4-Ethyltoluene	NR	NR	NR	ND	ND	ND	3	ND	8 J	ND	1.2 J	ND
4-Methyl-2-pentanone	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND	ND	ND
Acetone	NR	NR	NR	10	6	21	19	9	10	13 J	11 J	10 J
alpha-Chlorotoluene	NR	NR	NR	ND	ND	ND	ND	ND	8 J	ND	ND	ND
Acrylonitrile	NR	NR	NR	ND	ND	ND	0.5 J	0.8 J	ND	NR	NR	NR
Benzene	NR	NR	NR	ND	ND	12	1	1 J	6 J	ND	ND	ND
Benzyl Chloride	NR	NR	NR	ND	ND	ND	ND	ND	ND	NR	NR	NR
Bromodichloromethane	NR	NR	NR	ND	ND	ND	2 J	2 J	ND	ND	ND	ND
Bromoform	NR	NR	NR	ND	ND	ND	ND	2 J	14 J	ND	ND	ND
Bromomethane	NR	NR	NR	ND	ND	ND	1 J	1 J	6 J	ND	ND	ND
Carbon Disulfide	NR	NR	NR	ND	ND	ND	1 J	1 J	6 J	ND	ND	5.4 J
Carbon Tetrachloride	NR	NR	NR	ND	ND	ND	2 J	2 J	12 J	ND	ND	ND
Chlorobenzene	NR	NR	NR	ND	ND	ND	1 J	1 J	8 J	ND	ND	11 J, B
Chlorodibromomethane	NR	NR	NR	ND	ND	ND	2 J	2 J	14 J	NR	NR	NR
Chloroethane	NR	NR	NR	ND	ND	ND	0.9 J	1 J	5 J	ND	ND	ND
Chloroform	NR	NR	NR	ND	1	ND	1 J	6	29	3.6 J	1.6	9.3 J
Chloromethane	NR	NR	NR	3	0.7	1	2	0.9	4 J	ND	ND	ND
cis-1,2-Dichloroethene	420	1500	370	ND	92	ND	1 J	360	160	290	230	300
cis-1,3-Dichloropropene	NR	NR	NR	ND	ND	ND	ND	1 J	6 J	ND	ND	ND
Cumene	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND	ND	ND
Cyclohexane	NR	NR	NR	ND	ND	5	1 J	0.9 J	5 J	ND	ND	ND
Dichlorodifluoromethane	NR	NR	NR	6	2	2	4	3	10	ND	ND	ND
Diisopropyl ether	NR	NR	NR	5	ND	ND	ND	1 J	6 J	NR	NR	NR
Ethanol	NR	NR	NR	6	5	56	10	2	9	5.5 J	ND	ND
Ethyl Acetate	NR	NR	NR	5	ND	ND	ND	ND	ND	NR	NR	NR
Ethyl tert-butyl ether	NR	NR	NR	ND	ND	ND	1 J	1 J	5 J	NR	NR	NR
Ethylbenzene	NR	NR	NR	ND	ND	8	3	0.9 J	7 J	ND	ND	2.3 J
Freon 11	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND	ND	3.1 J
Freon 113	NR	NR	NR	ND	10	10	3 J	12	20	ND	ND	ND
Freon 114	NR	NR	NR	ND	ND	ND	2 J	2 J	12 J	ND	ND	ND
Freon 12	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND	ND	2.9 J
Heptane	NR	NR	NR	ND	ND	8	1 J	1 J	5 J	ND	ND	ND
Hexachlorobutadiene	NR	NR	NR	ND	ND	ND	4 J	3 J	18 J	ND	ND	ND
Hexane	NR	NR	NR	3	1	20	2	3	6 J	ND	ND	ND
iso-Octane	NR	NR	NR	ND	ND	ND	1 J	1 J	8 J	NR	NR	NR
Isopropylbenzene	NR	NR	NR	ND	ND	ND	1 J	1 J	8 J	NR	NR	NR
Isopropyl alcohol	NR	NR	NR	5	ND	5	2	2	5 J	NR	NR	NR
m,p-Xylene	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND	1.3 J	5.8 J
Methyl Methacrylate	NR	NR	NR	ND	ND	ND	1 J	1 J	5 J	NR	NR	NR
Methyl-tert-Butyl-Ether	NR	NR	NR	ND	ND	ND	1 J	2	6 J	ND	ND	ND
Methylene Chloride	NR	NR	NR	7	3	4	4	19	11	ND	ND	ND
MIBK	NR	NR	NR	ND	ND	ND	1 J	1 J	6 J	NR	NR	NR
Naphthalene	NR	NR	NR	ND	ND	ND	3	ND	5 J	NR	NR	NR
n-Butane	NR	NR	NR	2	2	67	2	2	ND	NR	NR	NR
o-Xylene	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND	ND	ND
p-Isopropyltoluene	NR	NR	NR	ND	ND	ND	1 J	ND	7 J	NR	NR	NR
n-Propylbenzene	NR	NR	NR	ND	ND	1	2	ND	6 J	ND	ND	ND
Propylene	NR	NR	NR	ND	ND	9	2	ND	ND	NR	NR	NR
Styrene	NR	NR	NR	ND	ND	ND	ND	ND	5 J	ND	ND	ND
tert-Amyl methyl ether	NR	NR	NR	ND	ND	ND	1 J	1 J	6 J	NR	NR	NR
tert-Butyl Alcohol	NR	NR	NR	3	ND	ND	1 J	0.9 J	5 J	NR	NR	NR
Tetrachloroethene	20000	28000	16000	9	1500	ND	3	1600	6700	3800	3200	4700
Tetrahydrofuran	NR	NR	NR	4	1	ND	6	2	6	2.0 J	ND	ND
Toluene	NR	NR	NR	4	2	40	4	0.9 J	6 J	ND	ND	4.7 J
Total Xylenes	NR	NR	NR	ND	ND	34	16	3 J	21 J	NR	NR	NR
trans-1,2-Dichloroethene	ND	24	ND	ND	1	ND	1 J	3	7 J	ND	ND	ND
trans-1,3-Dichloropropene	NR	NR	NR	ND	ND	ND	ND	ND	5 J	ND	ND	ND
Trichloroethene	3100	1600	640	7	92	ND	2 J	290	240	180	200	480
Trichlorofluoromethane	NR	NR	NR	6	1	3	3	3	11	NR	NR	NR
Vinyl Acetate	NR	NR	NR	4	ND	ND	ND	ND	ND	NR	NR	NR
Vinyl Bromide	NR	NR	NR	ND	ND	ND	2 J	1 J	8 J	NR	NR	NR
Vinyl Chloride	ND	5.9	ND	ND	2	ND	0.8 J	4	5 J	ND	ND	ND

**Notes:**  
µg/m<sup>3</sup> = micrograms per cubic mete  
NR = Not Recorded  
NA = Data not available. Vapor samp

Table 6  
Soil Vapor Extraction Containment System  
Site 1, Former Drum Marshalling Yard  
Naval Weapons Industrial Reserve Plant - Bethpage, NY  
Quarterly Vapor Monitoring Results of Individual Wells  
Through Third Quarter 2012

Sample ID	SVE 104I											
	12/21/09	03/31/10	06/09/10	09/16/10	12/08/10	03/30/11	06/28/11	09/06/11	10/14/11	02/10/12	05/11/12	09/11/12
<b>Analysis by TO-15 (µg/m<sup>3</sup>)</b>												
1,1,1-Trichloroethane	730	4.2	ND	4	NR	NA	1 J	4	2	ND	ND	8.3
1,1,2,2-Tetrachloroethane	NR	NR	NR	ND	ND	NA	1 J	0.7 J	ND	ND	ND	ND
1,1,2-Trichloroethane	NR	NR	NR	ND	ND	NA	1 J	ND	ND	ND	ND	ND
1,1-Dichloroethane	24	0.54	ND	ND	ND	NA	1 J	0.6 J	0.5 J	ND	ND	ND
1,1-Dichloroethene	ND	ND	ND	ND	ND	NA	1 J	ND	ND	ND	ND	ND
1,2,3-Trichloropropane	NR	NR	NR	ND	ND	NA	1 J	ND	ND	NR	NR	NR
1,2,3-Trimethylbenzene	NR	NR	NR	4	ND	NA	ND	ND	0.7 J	NR	NR	NR
1,2,4-Trichlorobenzene	NR	NR	NR	ND	ND	NA	ND	ND	ND	ND	ND	ND
1,2,4-Trimethylbenzene	NR	NR	NR	12	1	NA	ND	ND	2	ND	ND	2.2 J
1,2-Dibromoethane	NR	NR	NR	ND	ND	NA	2 J	ND	ND	ND	ND	ND
1,2-Dichlorobenzene	NR	NR	NR	ND	ND	NA	ND	ND	ND	ND	ND	ND
1,2-Dichloroethane	NR	ND	ND	ND	ND	NA	1 J	ND	ND	ND	ND	ND
1,2-Dichloropropane	NR	NR	NR	ND	ND	NA	1 J	ND	ND	ND	ND	ND
1,3,5-Trimethylbenzene	NR	NR	NR	3	ND	NA	ND	ND	0.5 J	ND	ND	0.75 J
1,3-Butadiene	NR	NR	NR	ND	ND	NA	1	0.4 J	ND	ND	ND	ND
1,3-Dichlorobenzene	NR	NR	NR	ND	ND	NA	ND	ND	ND	ND	ND	ND
1,4-Dichlorobenzene	NR	NR	NR	ND	ND	NA	ND	ND	ND	ND	ND	ND
1,4-Dioxane	NR	NR	NR	ND	ND	NA	0.8 J	0.4 J	ND	ND	ND	ND
2,2,4-Trimethylpentane	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND	ND	ND
2-Butanone	NR	NR	NR	3	0.6	NA	3	1	0.8	ND	ND	ND
2-Hexanone	NR	NR	NR	ND	ND	NA	0.9 J	ND	ND	ND	ND	ND
2-Propanol	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND	ND	ND
3-Chloro-1-propene	NR	NR	NR	ND	ND	NA	0.9	0.3 J	ND	ND	ND	ND
4-Ethyltoluene	NR	NR	NR	2	ND	NA	ND	ND	ND	ND	ND	1.9 J
4-Methyl-2-pentanone	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND	ND	ND
Acetone	NR	NR	NR	11	3	NA	21	5	5	4.8 J	6.5 J	6.5 J
alpha-Chlorotoluene	NR	NR	NR	ND	ND	NA	ND	ND	ND	ND	ND	ND
Acrylonitrile	NR	NR	NR	ND	ND	NA	0.6 J	0.3 J	ND	NR	NR	NR
Benzene	NR	NR	NR	1	ND	NA	1 J	0.4 J	0.4 J	ND	ND	ND
Benzyl Chloride	NR	NR	NR	ND	ND	NA	ND	ND	ND	NR	NR	NR
Bromodichloromethane	NR	NR	NR	ND	ND	NA	2 J	0.8 J	ND	ND	ND	ND
Bromoform	NR	NR	NR	ND	ND	NA	ND	ND	ND	ND	ND	ND
Bromomethane	NR	NR	NR	ND	ND	NA	1 J	0.4 J	ND	ND	ND	ND
Carbon Disulfide	NR	NR	NR	ND	ND	NA	1 J	0.5 J	0.5 J	ND	ND	5.2 J
Carbon Tetrachloride	NR	NR	NR	ND	ND	NA	2 J	1 J	1 J	ND	ND	ND
Chlorobenzene	NR	NR	NR	ND	ND	NA	1 J	0.5 J	ND	ND	ND	2.3 J, B
Chlorodibromomethane	NR	NR	NR	ND	ND	NA	2 J	ND	ND	NR	NR	NR
Chloroethane	NR	NR	NR	ND	ND	NA	0.9 J	0.3 J	ND	ND	ND	ND
Chloroform	NR	NR	NR	2	ND	NA	1 J	3	1	ND	ND	2.8 J
Chloromethane	NR	NR	NR	ND	0.5	NA	2	0.5	0.8	ND	ND	ND
cis-1,2-Dichloroethene	110	14	ND	2	0.8	NA	0.9 J	2	3	0.90 J	ND	5.0
cis-1,3-Dichloropropene	NR	NR	NR	ND	ND	NA	1 J	ND	ND	ND	ND	ND
Cumene	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND	ND	ND
Cyclohexane	NR	NR	NR	0.8	ND	NA	1 J	ND	ND	ND	ND	ND
Dichlorodifluoromethane	NR	NR	NR	2	2	NA	3	2	2	ND	ND	ND
Diisopropyl ether	NR	NR	NR	5	ND	NA	ND	ND	ND	NR	NR	NR
Ethanol	NR	NR	NR	19	1	NA	12	2	3	ND	1.2 J	ND
Ethyl Acetate	NR	NR	NR	5	ND	NA	ND	ND	ND	NR	NR	NR
Ethyl tert-butyl ether	NR	NR	NR	ND	ND	NA	1 J	ND	ND	NR	NR	NR
Ethylbenzene	NR	NR	NR	2	ND	NA	1 J	0.6 J	0.6 J	ND	ND	0.89 J
Freon 11	NR	NR	NR	NR	NR	NR	NR	NR	NR	1.2 J	1.0 J	1.6 J
Freon 113	NR	NR	NR	ND	ND	NA	3 J	2	2	ND	ND	3.0 J
Freon 114	NR	NR	NR	ND	ND	NA	2 J	0.9 J	0.7 J	ND	ND	ND
Freon 12	NR	NR	NR	NR	NR	NR	NR	NR	NR	2.4 J	2.1 J	2.6 J
Heptane	NR	NR	NR	1	ND	NA	1 J	ND	ND	ND	ND	ND
Hexachlorobutadiene	NR	NR	NR	ND	ND	NA	2 J	ND	ND	ND	ND	ND
Hexane	NR	NR	NR	10	ND	NA	12	0.5 J	0.4 J	0.82 J	ND	ND
iso-Octane	NR	NR	NR	ND	ND	NA	1 J	0.5 J	0.5 J	NR	NR	NR
Isopropylbenzene	NR	NR	NR	ND	ND	NA	1 J	ND	ND	NR	NR	NR
Isopropyl alcohol	NR	NR	NR	6	ND	NA	7	0.7	0.5	NR	NR	NR
m,p-Xylene	NR	NR	NR	NR	NR	NA	NR	NR	NR	ND	ND	2.4 J
Methyl Methacrylate	NR	NR	NR	ND	ND	NA	0.9 J	ND	ND	NR	NR	NR
Methyl-tert-Butyl-Ether	NR	NR	NR	1	ND	NA	4	ND	ND	ND	ND	ND
Methylene Chloride	NR	NR	NR	51	ND	NA	65	1	0.9	2.6	ND	ND
MIBK	NR	NR	NR	ND	ND	NA	1 J	ND	ND	NR	NR	NR
Naphthalene	NR	NR	NR	ND	ND	NA	ND	ND	0.7 J	NR	NR	NR
n-Butane	NR	NR	NR	2	0.6	NA	2	0.5 J	ND	NR	NR	NR
o-Xylene	NR	NR	NR	NR	NR	NA	NR	NR	NR	ND	ND	1.2 J
p-Isopropyltoluene	NR	NR	NR	ND	ND	NA	ND	ND	ND	NR	NR	NR
n-Propylbenzene	NR	NR	NR	1	ND	NA	ND	ND	ND	ND	ND	0.60 J
Propylene	NR	NR	NR	ND	ND	NA	ND	ND	0.4	NR	NR	NR
Styrene	NR	NR	NR	ND	ND	NA	ND	ND	ND	ND	ND	ND
tert-Amyl methyl ether	NR	NR	NR	ND	ND	NA	1 J	ND	ND	NR	NR	NR
tert-Butyl Alcohol	NR	NR	NR	ND	ND	NA	0.9 J	0.3 J	0.3 J	NR	NR	NR
Tetrachloroethene	3100	210	68	96	16	NA	2 J	54	33	12	ND	86
Tetrahydrofuran	NR	NR	NR	4	1	NA	1	1	0.8	0.58 J	ND	1.4 J
Toluene	NR	NR	NR	7	ND	NA	2	1	0.6 J	0.59 J	ND	0.68 J
Total Xylenes	NR	NR	NR	12	ND	NA	3 J	3	2 J	NR	NR	NR
trans-1,2-Dichloroethene	15	ND	ND	ND	ND	NA	1 J	0.5 J	0.4 J	ND	ND	ND
trans-1,3-Dichloropropene	NR	NR	NR	ND	ND	NA	ND	ND	ND	ND	ND	ND
Trichloroethene	710	44	60	72	12	NA	2 J	44	25	9.6	ND	73
Trichlorofluoromethane	NR	NR	NR	2	ND	NA	3	2	2	NR	NR	NR
Vinyl Acetate	NR	NR	NR	2	ND	NA	ND	ND	0.5 J	NR	NR	NR
Vinyl Bromide	NR	NR	NR	ND	ND	NA	1 J	0.5 J	ND	NR	NR	NR
Vinyl Chloride	ND	0.47	ND	ND	ND	NA	0.7 J	0.3 J	0.3 J	ND	ND	ND

**Notes:**  
µg/m<sup>3</sup> = micrograms per cubic mete  
NR = Not Recorded  
NA = Data not available. Vapor samp

Table 6  
Soil Vapor Extraction Containment System  
Site 1, Former Drum Marshalling Yard  
Naval Weapons Industrial Reserve Plant - Bethpage, NY  
Quarterly Vapor Monitoring Results of Individual Wells  
Through Third Quarter 2012

Sample ID	SVE 104D											
	12/21/09	03/31/10	06/09/10	09/16/10	12/22/10	03/30/11	06/28/11	09/06/11	10/14/11	02/10/12	05/11/12	09/11/12
<b>Analysis by TO-15 (µg/m<sup>3</sup>)</b>												
1,1,1-Trichloroethane	3600	3000	860	ND	270	ND	370	620	440	520	580	620
1,1,2,2-Tetrachloroethane	NR	NR	NR	ND	ND	ND	1 J	ND	9 J	ND	ND	ND
1,1,2-Trichloroethane	NR	NR	NR	ND	ND	ND	2 J	7 J	7 J	ND	ND	ND
1,1-Dichloroethane	290	350	140	ND	66	ND	56	110	77	87	95	100
1,1-Dichloroethene	ND	ND	ND	ND	ND	ND	3	7 J	7 J	3.0 J	5.0 J	ND
1,2,3-Trichloropropane	NR	NR	NR	ND	ND	ND	2 J	7 J	7 J	NR	NR	NR
1,2,3-Trimethylbenzene	NR	NR	NR	ND	ND	ND	7	ND	6 J	NR	NR	NR
1,2,4-Trichlorobenzene	NR	NR	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,2,4-Trimethylbenzene	NR	NR	NR	3	ND	ND	21	ND	7 J	ND	4.0 J	2.5 J
1,2-Dibromoethane	NR	NR	NR	ND	ND	ND	2 J	ND	9 J	ND	ND	ND
1,2-Dichlorobenzene	NR	NR	NR	ND	ND	ND	1 J	ND	7 J	ND	ND	ND
1,2-Dichloroethane	NR	ND	ND	ND	ND	ND	1 J	5 J	5 J	ND	ND	ND
1,2-Dichloropropane	NR	NR	NR	ND	ND	ND	2 J	6 J	5 J	ND	ND	ND
1,3,5-Trimethylbenzene	NR	NR	NR	ND	ND	ND	4	ND	5 J	ND	ND	ND
1,3-Butadiene	NR	NR	NR	ND	ND	ND	ND	3 J	ND	ND	ND	ND
1,3-Dichlorobenzene	NR	NR	NR	ND	ND	ND	1 J	ND	ND	ND	ND	ND
1,4-Dichlorobenzene	NR	NR	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,4-Dioxane	NR	NR	NR	ND	ND	ND	2	9	4 J	ND	ND	ND
2,2,4-Trimethylpentane	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND	ND	ND
2-Butanone	NR	NR	NR	ND	ND	ND	7	5 J	3 J	ND	ND	ND
2-Hexanone	NR	NR	NR	ND	ND	ND	1 J	8	ND	ND	ND	ND
2-Propanol	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND	ND	ND
3-Chloro-1-propene	NR	NR	NR	ND	ND	ND	1 J	4 J	ND	ND	ND	ND
4-Ethyltoluene	NR	NR	NR	ND	ND	ND	4	ND	5 J	ND	1.7 J	ND
4-Methyl-2-pentanone	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND	ND	ND
Acetone	NR	NR	NR	10	ND	6	26	10	8	46	12 J	ND
alpha-Chlorotoluene	NR	NR	NR	ND	ND	ND	1 J	ND	5 J	ND	ND	ND
Acrylonitrile	NR	NR	NR	ND	ND	ND	0.8 J	4	ND	NR	NR	NR
Benzene	NR	NR	NR	ND	ND	ND	2	4 J	4 J	ND	ND	1.5 J
Benzyl Chloride	NR	NR	NR	ND	ND	ND	1 J	ND	ND	NR	NR	NR
Bromodichloromethane	NR	NR	NR	ND	ND	ND	2 J	8 J	7 J	ND	ND	ND
Bromoform	NR	NR	NR	ND	ND	ND	3 J	ND	11 J	ND	ND	ND
Bromomethane	NR	NR	NR	ND	ND	ND	1 J	6 J	5 J	ND	ND	ND
Carbon Disulfide	NR	NR	NR	ND	ND	ND	1	5 J	4 J	ND	ND	6.3 J
Carbon Tetrachloride	NR	NR	NR	ND	ND	ND	3	9 J	8 J	ND	ND	ND
Chlorobenzene	NR	NR	NR	ND	ND	ND	1 J	ND	5 J	ND	ND	10 J, B
Chlorodibromomethane	NR	NR	NR	ND	ND	ND	2 J	9 J	10 J	NR	NR	NR
Chloroethane	NR	NR	NR	ND	ND	ND	1 J	4 J	4 J	ND	ND	ND
Chloroform	NR	NR	NR	ND	ND	ND	3	10	9 J	ND	2.2 J	5.8 J
Chloromethane	NR	NR	NR	0.9	ND	ND	2	3 J	3 J	ND	ND	ND
cis-1,2-Dichloroethene	2400	6600	3500	ND	1200	ND	1000	3600	2100	2200	2800 J	2200
cis-1,3-Dichloropropene	NR	NR	NR	ND	ND	ND	1 J	ND	ND	ND	ND	ND
Cumene	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND	ND	ND
Cyclohexane	NR	NR	NR	ND	ND	ND	2	4 J	ND	ND	ND	ND
Dichlorodifluoromethane	NR	NR	NR	2	ND	ND	4	9 J	8 J	ND	ND	ND
Diisopropyl ether	NR	NR	NR	ND	ND	ND	ND	ND	ND	NR	NR	NR
Ethanol	NR	NR	NR	4	4	6	20	10	ND	11 J	2.2 J	ND
Ethyl Acetate	NR	NR	NR	ND	ND	ND	ND	6 J	ND	NR	NR	NR
Ethyl tert-butyl ether	NR	NR	NR	ND	ND	ND	1 J	4 J	ND	NR	NR	NR
Ethylbenzene	NR	NR	NR	ND	ND	ND	4	ND	5 J	ND	ND	2.3 J
Freon 11	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND	ND	ND
Freon 113	NR	NR	NR	ND	560	560	280	260	550	720	980	880
Freon 114	NR	NR	NR	ND	ND	ND	2 J	10 J	9 J	ND	ND	ND
Freon 12	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND	ND	2.7 J
Heptane	NR	NR	NR	ND	ND	ND	2	5 J	5 J	ND	ND	ND
Hexachlorobutadiene	NR	NR	NR	ND	ND	ND	5	ND	14 J	ND	ND	ND
Hexane	NR	NR	NR	2	ND	2	7	5 J	4 J	ND	ND	ND
iso-Octane	NR	NR	NR	ND	ND	ND	3	7 J	6 J	NR	NR	NR
Isopropylbenzene	NR	NR	NR	ND	ND	ND	2 J	ND	6 J	NR	NR	NR
Isopropyl alcohol	NR	NR	NR	1	ND	ND	7	6	4 J	NR	NR	NR
m,p-Xylene	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND	1.1 J	3.8 J
Methyl Methacrylate	NR	NR	NR	ND	ND	ND	1 J	4 J	ND	NR	NR	NR
Methyl-tert-Butyl-Ether	NR	NR	NR	ND	ND	ND	3	4 J	4 J	ND	ND	ND
Methylene Chloride	NR	NR	NR	6	ND	14	28	9	6 J	ND	ND	ND
MIBK	NR	NR	NR	ND	ND	ND	1 J	5 J	ND	NR	NR	NR
Naphthalene	NR	NR	NR	ND	ND	ND	7	ND	5 J	NR	NR	NR
n-Butane	NR	NR	NR	ND	ND	3	5	4 J	ND	NR	NR	NR
o-Xylene	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND	ND	ND
p-Isopropyltoluene	NR	NR	NR	ND	ND	ND	2 J	ND	ND	NR	NR	NR
n-Propylbenzene	NR	NR	NR	ND	ND	ND	3	ND	ND	ND	ND	ND
Propylene	NR	NR	NR	ND	ND	ND	ND	ND	3 J	NR	NR	NR
Styrene	NR	NR	NR	ND	ND	ND	1 J	ND	ND	ND	ND	ND
tert-Amyl methyl ether	NR	NR	NR	ND	ND	ND	1 J	5 J	4 J	NR	NR	NR
tert-Butyl Alcohol	NR	NR	NR	ND	ND	ND	2	4 J	3 J	NR	NR	NR
Tetrachloroethene	20000	39000	21000	ND	2400	ND	1400	5800	6300	3800	4300	4600
Tetrahydrofuran	NR	NR	NR	ND	ND	ND	7	4 J	3 J	2.8 J	ND	8.2 J
Toluene	NR	NR	NR	ND	ND	ND	8	4 J	4 J	ND	ND	2.5 J
Total Xylenes	NR	NR	NR	ND	ND	ND	20	ND	14 J	NR	NR	NR
trans-1,2-Dichloroethene	130	70	30	ND	13	ND	14	25	22	26	31	27
trans-1,3-Dichloropropene	NR	NR	NR	ND	ND	ND	1 J	ND	ND	ND	ND	ND
Trichloroethene	4600	6000	2400	ND	470	ND	420	1600	1300	1400	1400	1700
Trichlorofluoromethane	NR	NR	NR	ND	ND	ND	3	9 J	7 J	NR	NR	NR
Vinyl Acetate	NR	NR	NR	ND	ND	ND	ND	5 J	4 J	NR	NR	NR
Vinyl Bromide	NR	NR	NR	ND	ND	ND	2 J	6 J	ND	NR	NR	NR
Vinyl Chloride	ND	12	ND	ND	ND	ND	2	5	5 J	ND	ND	ND

**Notes:**  
µg/m<sup>3</sup> = micrograms per cubic mete  
NR = Not Recorded  
NA = Data not available. Vapor samp

Table 6  
Soil Vapor Extraction Containment System  
Site 1, Former Drum Marshalling Yard  
Naval Weapons Industrial Reserve Plant - Bethpage, NY  
Quarterly Vapor Monitoring Results of Individual Wells  
Through Third Quarter 2012

Sample ID	SVE 105I											
	12/21/09	03/31/10	06/09/10	09/16/10	12/08/10	03/30/11	06/28/11	09/06/11	10/14/11	02/10/12	05/11/12	09/11/12
<b>Analysis by TO-15 (<math>\mu\text{g}/\text{m}^3</math>)</b>												
1,1,1-Trichloroethane	9.9	11	29	ND	24	1	1J	21	31	11	13	26
1,1,2,2-Tetrachloroethane	NR	NR	NR	ND	ND	ND	0.8J	1J	0.9J	ND	ND	ND
1,1,2-Trichloroethane	NR	NR	NR	ND	ND	ND	0.7J	0.8J	0.9J	ND	ND	ND
1,1-Dichloroethane	ND	5.7	13	ND	6	ND	0.6J	5	7	4.2	5.6	5.6
1,1-Dichloroethene	ND	ND	ND	ND	ND	ND	0.6J	0.6J	0.5J	ND	ND	ND
1,2,3-Trichloropropane	NR	NR	NR	ND	ND	ND	0.7J	0.8J	0.9J	NR	NR	NR
1,2,3-Trimethylbenzene	NR	NR	NR	14	ND	1	0.7J	1	2	NR	NR	NR
1,2,4-Trichlorobenzene	NR	NR	NR	ND	ND	ND	ND	ND	1J	ND	ND	ND
1,2,4-Trimethylbenzene	NR	NR	NR	44	3	4	1	3	7	1.4J	1.7J	2.8J
1,2-Dibromoethane	NR	NR	NR	ND	ND	ND	0.9J	ND	0.8J	ND	ND	ND
1,2-Dichlorobenzene	NR	NR	NR	ND	ND	ND	0.9J	ND	0.8J	ND	ND	ND
1,2-Dichloroethane	NR	ND	ND	ND	ND	ND	0.7J	0.6J	0.5J	ND	ND	ND
1,2-Dichloropropane	NR	NR	NR	ND	ND	ND	0.7J	0.5J	0.6J	ND	ND	ND
1,3,5-Trimethylbenzene	NR	NR	NR	10	ND	1	2	0.9J	1	0.48J	ND	0.92J
1,3-Butadiene	NR	NR	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,3-Dichlorobenzene	NR	NR	NR	ND	ND	ND	ND	ND	0.7J	ND	ND	ND
1,4-Dichlorobenzene	NR	NR	NR	ND	ND	ND	ND	ND	0.7J	ND	ND	0.81J
1,4-Dioxane	NR	NR	NR	ND	ND	ND	0.7J	0.7J	0.6J	ND	ND	ND
2,2,4-Trimethylpentane	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND	ND	ND
2-Butanone	NR	NR	NR	4	1	6	6	2	1	3.6J	ND	ND
2-Hexanone	NR	NR	NR	ND	ND	ND	0.7J	0.6J	0.4J	ND	ND	ND
2-Propanol	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND	ND	ND
3-Chloro-1-propene	NR	NR	NR	ND	ND	ND	0.4J	ND	ND	ND	ND	ND
4-Ethyltoluene	NR	NR	NR	7	ND	ND	3	0.8J	1	0.94J	0.53J	1.3J
4-Methyl-2-pentanone	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND	ND	ND
Acetone	NR	NR	NR	11	3	15	27	9	4	25	4.7J	7.8J
alpha-Chlorotoluene	NR	NR	NR	ND	ND	ND	0.5J	ND	0.7J	ND	ND	ND
Acrylonitrile	NR	NR	NR	ND	ND	ND	0.3J	0.4J	ND	NR	NR	NR
Benzene	NR	NR	NR	ND	ND	4	1	0.6J	0.6J	ND	ND	0.63J
Benzyl Chloride	NR	NR	NR	ND	ND	ND	ND	ND	ND	NR	NR	NR
Bromodichloromethane	NR	NR	NR	ND	ND	ND	1J	1J	0.9J	ND	ND	ND
Bromoform	NR	NR	NR	ND	ND	ND	1J	1J	1J	ND	ND	ND
Bromomethane	NR	NR	NR	ND	ND	ND	0.8	0.6J	0.5J	ND	ND	ND
Carbon Disulfide	NR	NR	NR	ND	ND	ND	0.9	0.6J	0.6J	ND	ND	1.8J
Carbon Tetrachloride	NR	NR	NR	ND	ND	ND	1	1J	1	ND	ND	ND
Chlorobenzene	NR	NR	NR	ND	ND	ND	0.6J	0.5J	0.6J	ND	ND	2.9J, B
Chlorodibromomethane	NR	NR	NR	ND	ND	ND	1J	0.9J	1J	NR	NR	NR
Chloroethane	NR	NR	NR	ND	ND	ND	0.7	0.4J	0.4J	ND	ND	ND
Chloroform	NR	NR	NR	ND	2	ND	0.9J	4	3	0.78J	1.0J	3.2J
Chloromethane	NR	NR	NR	0.9	ND	ND	3	0.5	0.4	ND	ND	ND
cis-1,2-Dichloroethene	ND	6.6	20	ND	ND	ND	1	10	16	8.1	9.7	13
cis-1,3-Dichloropropene	NR	NR	NR	ND	13	ND	0.5J	ND	0.5J	ND	ND	ND
Cumene	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND	ND	ND
Cyclohexane	NR	NR	NR	ND	ND	3	0.7J	0.6J	0.5J	ND	ND	ND
Dichlorodifluoromethane	NR	NR	NR	2	2	2	3	2	3	ND	ND	ND
Diisopropyl ether	NR	NR	NR	ND	ND	ND	ND	0.6J	ND	NR	NR	NR
Ethanol	NR	NR	NR	5	1	37	19	3	2	15	1.1J	2.8J
Ethyl Acetate	NR	NR	NR	ND	ND	2	ND	ND	ND	NR	NR	NR
Ethyl tert-butyl ether	NR	NR	NR	ND	ND	ND	0.5J	0.5J	0.4J	NR	NR	NR
Ethylbenzene	NR	NR	NR	4	ND	3	3	0.9	1	ND	ND	ND
Freon 11	NR	NR	NR	NR	NR	NR	NR	NR	NR	1.1J	0.87J	1.5J
Freon 113	NR	NR	NR	ND	2	ND	2	3	3	1.8J	5.5J	3.2J
Freon 114	NR	NR	NR	ND	ND	ND	1J	1J	1J	ND	ND	ND
Freon 12	NR	NR	NR	NR	NR	NR	NR	NR	NR	2.3J	1.8J	2.0J
Heptane	NR	NR	NR	ND	ND	3	3	0.5J	0.5J	ND	ND	ND
Hexachlorobutadiene	NR	NR	NR	ND	ND	ND	2J	1J	2J	ND	ND	ND
Hexane	NR	NR	NR	2	ND	11	2	1	0.5J	ND	ND	ND
iso-Octane	NR	NR	NR	ND	ND	4	1	0.7J	0.7J	NR	NR	NR
Isopropylbenzene	NR	NR	NR	ND	ND	ND	0.8J	0.6J	0.8J	NR	NR	NR
Isopropyl alcohol	NR	NR	NR	ND	ND	6	9	2	7	NR	NR	NR
m,p-Xylene	NR	NR	NR	NR	NR	NR	NR	NR	NR	0.91J	1.0J	2.0J
Methyl Methacrylate	NR	NR	NR	ND	ND	ND	0.6J	0.5J	0.4J	NR	NR	NR
Methyl-tert-Butyl-Ether	NR	NR	NR	ND	ND	1	0.7J	0.7J	0.4J	ND	ND	ND
Methylene Chloride	NR	NR	NR	6	0.8	48	7	5	1	0.94J	ND	ND
MIBK	NR	NR	NR	ND	ND	ND	0.8J	0.6J	0.5J	NR	NR	NR
Naphthalene	NR	NR	NR	3	ND	1	6	0.8J	8	NR	NR	NR
n-Butane	NR	NR	NR	0.5	ND	23	2	0.6	ND	NR	NR	NR
o-Xylene	NR	NR	NR	NR	NR	NR	NR	NR	NR	0.49J	ND	ND
p-Isopropyltoluene	NR	NR	NR	ND	ND	ND	0.9J	0.6J	0.7J	NR	NR	NR
n-Propylbenzene	NR	NR	NR	4	ND	ND	2	0.7J	1	ND	ND	0.68J
Propylene	NR	NR	NR	ND	ND	ND	ND	ND	ND	NR	NR	NR
Styrene	NR	NR	NR	ND	ND	ND	0.5J	ND	0.5J	ND	ND	ND
tert-Amyl methyl ether	NR	NR	NR	ND	ND	ND	0.5J	0.5J	0.5J	NR	NR	NR
tert-Butyl Alcohol	NR	NR	NR	1	ND	ND	4	0.6J	0.4J	NR	NR	NR
Tetrachloroethene	70	9.1	240	ND	55	5	2	95	100	31	43	100
Tetrahydrofuran	NR	NR	NR	5	2	ND	4	2	2	1.0J	0.99J	ND
Toluene	NR	NR	NR	4	ND	14	5	2	1	0.60J	ND	0.79J
Total Xylenes	NR	NR	NR	28	ND	11	17	4	6	NR	NR	NR
trans-1,2-Dichloroethene	ND	ND	1.6	ND	ND	ND	0.5J	1	1	ND	ND	1.5J
trans-1,3-Dichloropropene	NR	NR	NR	ND	ND	ND	0.5J	ND	0.5J	ND	ND	ND
Trichloroethene	76	6.3	370	ND	120	7	1	170	200	110	140	260
Trichlorofluoromethane	NR	NR	NR	1	1	2	2	2	2	NR	NR	NR
Vinyl Acetate	NR	NR	NR	ND	ND	ND	3	ND	ND	NR	NR	NR
Vinyl Bromide	NR	NR	NR	ND	ND	ND	0.7J	ND	0.6J	NR	NR	NR
Vinyl Chloride	ND	ND	ND	ND	ND	ND	0.4J	0.4J	0.3J	ND	ND	ND

**Notes:**  
 $\mu\text{g}/\text{m}^3$  = micrograms per cubic meter  
 NR = Not Recorded  
 NA = Data not available. Vapor samp



Table 6  
Soil Vapor Extraction Containment System  
Site 1, Former Drum Marshalling Yard  
Naval Weapons Industrial Reserve Plant - Bethpage, NY  
Quarterly Vapor Monitoring Results of Individual Wells  
Through Third Quarter 2012

Sample ID	SVE 105D											
	12/21/09	03/31/10	06/09/10	09/16/10	12/08/10	03/30/11	06/28/11	09/06/11	12/02/11	02/10/12	05/11/12	09/11/12
<b>Analysis by TO-15 (µg/m<sup>3</sup>)</b>												
1,1,1-Trichloroethane	550	47	320	1000	590	ND	1 J	490	930	350	320	270
1,1,2,2-Tetrachloroethane	NR	NR	NR	ND	ND	ND	0.9 J	8 J	ND	ND	ND	ND
1,1,2-Trichloroethane	NR	NR	NR	ND	ND	ND	0.8 J	6 J	ND	ND	ND	ND
1,1-Dichloroethane	300	28	270	250	ND	ND	0.6 J	74	150	69	78	72
1,1-Dichloroethene	3.9	ND	ND	2	4	4	0.6 J	6 J	ND	ND	ND	ND
1,2,3-Trichloropropane	NR	NR	NR	ND	ND	ND	0.9 J	7 J	ND	NR	NR	NR
1,2,3-Trimethylbenzene	NR	NR	NR	8	ND	ND	3	ND	ND	NR	NR	NR
1,2,4-Trichlorobenzene	NR	NR	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,2,4-Trimethylbenzene	NR	NR	NR	30	4	2	8	ND	ND	ND	3.4 J	2.8 J
1,2-Dibromoethane	NR	NR	NR	ND	ND	ND	1 J	ND	ND	ND	ND	ND
1,2-Dichlorobenzene	NR	NR	NR	ND	ND	ND	4	ND	ND	ND	ND	ND
1,2-Dichloroethane	NR	ND	ND	ND	ND	ND	4	5 J	ND	ND	ND	ND
1,2-Dichloropropane	NR	NR	NR	ND	ND	ND	0.7 J	5 J	ND	ND	ND	ND
1,3,5-Trimethylbenzene	NR	NR	NR	6	ND	ND	2	ND	ND	ND	ND	ND
1,3-Butadiene	NR	NR	NR	ND	ND	ND	0.4	3 J	ND	ND	ND	ND
1,3-Dichlorobenzene	NR	NR	NR	ND	ND	ND	0.6 J	ND	ND	ND	ND	ND
1,4-Dichlorobenzene	NR	NR	NR	ND	ND	ND	0.7 J	ND	ND	ND	ND	ND
1,4-Dioxane	NR	NR	NR	ND	ND	ND	0.8	ND	ND	ND	ND	ND
2,2,4-Trimethylpentane	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND	ND	ND
2-Butanone	NR	NR	NR	7	2	2	4	6 J	ND	ND	ND	ND
2-Hexanone	NR	NR	NR	ND	ND	ND	0.7 J	7 J	ND	ND	ND	ND
2-Propanol	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND	ND	ND
3-Chloro-1-propene	NR	NR	NR	ND	ND	ND	0.5 J	3 J	ND	ND	ND	ND
4-Ethyltoluene	NR	NR	NR	5	ND	ND	2	ND	ND	ND	ND	ND
4-Methyl-2-pentanone	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND	ND	ND
Acetone	NR	NR	NR	35	5	11	22	10	5	ND	15 J	10 J
alpha-Chlorotoluene	NR	NR	NR	ND	ND	ND	0.7 J	ND	ND	ND	ND	ND
Acrylonitrile	NR	NR	NR	ND	ND	ND	0.4 J	4 J	ND	NR	NR	NR
Benzene	NR	NR	NR	ND	1	3	1	4 J	ND	ND	ND	ND
Benzyl Chloride	NR	NR	NR	ND	ND	ND	ND	ND	ND	NR	NR	NR
Bromodichloromethane	NR	NR	NR	6	ND	ND	1 J	8 J	ND	ND	ND	ND
Bromoform	NR	NR	NR	ND	ND	ND	1 J	ND	ND	ND	ND	ND
Bromomethane	NR	NR	NR	ND	ND	ND	0.6 J	6 J	ND	ND	ND	ND
Carbon Disulfide	NR	NR	NR	ND	ND	ND	0.8	4 J	ND	ND	ND	3.9 J
Carbon Tetrachloride	NR	NR	NR	3	6	ND	1	10 J	ND	4.0 J	8.1 J	ND
Chlorobenzene	NR	NR	NR	ND	ND	ND	1	ND	ND	ND	ND	5.9 J, B
Chlorodibromomethane	NR	NR	NR	ND	ND	ND	1 J	9 J	ND	NR	NR	NR
Chloroethane	NR	NR	NR	1	1	ND	0.5 J	4 J	ND	ND	ND	ND
Chloroform	NR	NR	NR	ND	4	ND	0.8 J	10 J	3 J	ND	2.7 J	3.8 J
Chloromethane	NR	NR	NR	1	ND	ND	2	3 J	ND	ND	ND	ND
cis-1,2-Dichloroethene	61	36	85	300	ND	ND	0.7 J	150	380	190	220	150
cis-1,3-Dichloropropene	NR	NR	NR	ND	ND	ND	0.6 J	ND	ND	ND	ND	ND
Cumene	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND	ND	ND
Cyclohexane	NR	NR	NR	ND	ND	1	0.8	ND	ND	ND	ND	ND
Dichlorodifluoromethane	NR	NR	NR	2	5	2	3	9 J	3 J	ND	ND	ND
Diisopropyl ether	NR	NR	NR	2	ND	ND	ND	ND	ND	NR	NR	NR
Ethanol	NR	NR	NR	8	2	26	12	10	10	5.2 J	ND	ND
Ethyl Acetate	NR	NR	NR	2	ND	ND	ND	ND	ND	NR	NR	NR
Ethyl tert-butyl ether	NR	NR	NR	ND	ND	ND	0.6 J	4 J	ND	NR	NR	NR
Ethylbenzene	NR	NR	NR	4	ND	2	3	ND	ND	ND	ND	ND
Freon 11	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND	ND	ND
Freon 113	NR	NR	NR	81	89	ND	2	62	40	18 J	43	37
Freon 114	NR	NR	NR	ND	ND	ND	1 J	10 J	ND	ND	ND	ND
Freon 12	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND	ND	2.9 J
Heptane	NR	NR	NR	ND	ND	1	0.9	5 J	ND	ND	ND	ND
Hexachlorobutadiene	NR	NR	NR	ND	ND	ND	2 J	ND	ND	ND	ND	ND
Hexane	NR	NR	NR	5	2	5	2	4 J	ND	ND	ND	ND
iso-Octane	NR	NR	NR	ND	ND	2	1	7 J	ND	NR	NR	NR
Isopropylbenzene	NR	NR	NR	ND	ND	ND	0.8 J	ND	ND	NR	NR	NR
Isopropyl alcohol	NR	NR	NR	2	ND	2	2	6	ND	NR	NR	NR
m,p-Xylene	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND	1.9 J	3.1 J
Methyl Methacrylate	NR	NR	NR	ND	ND	ND	0.7 J	4 J	ND	NR	NR	NR
Methyl-tert-Butyl-Ether	NR	NR	NR	ND	ND	ND	0.7 J	4 J	ND	ND	ND	ND
Methylene Chloride	NR	NR	NR	16	5	2	6	8	3 J	8.4 J	ND	ND
MIBK	NR	NR	NR	ND	ND	ND	0.8 J	5 J	ND	NR	NR	NR
Naphthalene	NR	NR	NR	9	ND	ND	4	ND	ND	NR	NR	NR
n-Butane	NR	NR	NR	ND	2	13	2	4 J	ND	NR	NR	NR
o-Xylene	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND	ND	ND
p-Isopropyltoluene	NR	NR	NR	ND	ND	ND	0.8 J	ND	ND	NR	NR	NR
n-Propylbenzene	NR	NR	NR	3	ND	ND	1	ND	ND	ND	ND	ND
Propylene	NR	NR	NR	2	ND	1	ND	ND	ND	NR	NR	NR
Styrene	NR	NR	NR	ND	ND	ND	0.7 J	ND	ND	ND	ND	ND
tert-Amyl methyl ether	NR	NR	NR	ND	ND	ND	0.6 J	5 J	ND	NR	NR	NR
tert-Butyl Alcohol	NR	NR	NR	3	ND	ND	0.9	4 J	ND	NR	NR	NR
Tetrachloroethene	2100	1.1	650	270	420	ND	2	240	330	140	220	270
Tetrahydrofuran	NR	NR	NR	6	3	2	3	5 J	2 J	ND	1.6 J	1.3 J
Toluene	NR	NR	NR	3	2	8	14	4 J	ND	ND	ND	ND
Total Xylenes	NR	NR	NR	22	ND	10	20	ND	ND	NR	NR	NR
trans-1,2-Dichloroethene	19	1.1	3.1	3	ND	ND	0.6 J	7 J	3 J	ND	ND	ND
trans-1,3-Dichloropropene	NR	NR	NR	ND	ND	ND	0.5 J	ND	ND	ND	ND	ND
Trichloroethene	1700	68	200	1100	1400	1	2	3000	7000	3600	4500	2200
Trichlorofluoromethane	NR	NR	NR	ND	3	1	2	9 J	ND	NR	NR	NR
Vinyl Acetate	NR	NR	NR	2	ND	ND	ND	4 J	ND	NR	NR	NR
Vinyl Bromide	NR	NR	NR	ND	ND	ND	0.8 J	6 J	ND	NR	NR	NR
Vinyl Chloride	ND	ND	ND	ND	ND	ND	0.4 J	4 J	ND	ND	ND	ND

**Notes:**  
µg/m<sup>3</sup> = micrograms per cubic mete  
NR = Not Recorded  
NA = Data not available. Vapor samp

Table 6  
Soil Vapor Extraction Containment System  
Site 1, Former Drum Marshalling Yard  
Naval Weapons Industrial Reserve Plant - Bethpage, NY  
Quarterly Vapor Monitoring Results of Individual Wells  
Through Third Quarter 2012

Sample ID	SVE 106I											
	12/21/09	03/31/10	06/09/10	09/16/10	12/08/10	03/30/11	06/28/11	09/06/11	10/14/11	02/10/12	05/11/12	09/11/12
<b>Analysis by TO-15 (µg/m<sup>3</sup>)</b>												
1,1,1-Trichloroethane	220	8.6	ND	4	ND	NA	6	3	7	1.0 J	2.2 J	11
1,1,2,2-Tetrachloroethane	NR	NR	NR	ND	ND	NA	1 J	0.8 J	1 J	ND	ND	ND
1,1,2-Trichloroethane	NR	NR	NR	ND	ND	NA	0.7 J	0.6 J	0.8 J	ND	ND	ND
1,1-Dichloroethane	120	ND	ND	1	ND	NA	1	0.5 J	1	0.62 J	0.70 J	1.6 J
1,1-Dichloroethene	ND	ND	ND	ND	ND	NA	0.6 J	2	0.6 J	ND	ND	ND
1,2,3-Trichloropropane	NR	NR	NR	ND	ND	NA	0.9 J	0.6 J	0.9 J	NR	NR	NR
1,2,3-Trimethylbenzene	NR	NR	NR	9	ND	NA	9	1	2	NR	NR	NR
1,2,4-Trichlorobenzene	NR	NR	NR	2	ND	NA	2	ND	0.8 J	ND	ND	ND
1,2,4-Trimethylbenzene	NR	NR	NR	29	ND	NA	29	3	6	1.1 J	2.2 J	3.2 J
1,2-Dibromoethane	NR	NR	NR	ND	ND	NA	1 J	ND	1 J	ND	ND	ND
1,2-Dichlorobenzene	NR	NR	NR	1	ND	NA	0.7 J	ND	0.9 J	ND	ND	ND
1,2-Dichloroethane	NR	ND	ND	0.8	ND	NA	0.6 J	0.5 J	0.6 J	ND	ND	ND
1,2-Dichloropropane	NR	NR	NR	ND	ND	NA	0.7 J	ND	0.7 J	ND	ND	ND
1,3,5-Trimethylbenzene	NR	NR	NR	6	ND	NA	5	0.9 J	1	ND	ND	0.84 J
1,3-Butadiene	NR	NR	NR	1	ND	NA	ND	2	0.6	ND	0.87 J	ND
1,3-Dichlorobenzene	NR	NR	NR	ND	ND	NA	ND	ND	0.7 J	ND	ND	ND
1,4-Dichlorobenzene	NR	NR	NR	ND	ND	NA	0.7 J	2	0.7 J	ND	ND	0.74 J
1,4-Dioxane	NR	NR	NR	ND	ND	NA	0.7	0.5 J	0.6 J	ND	ND	ND
2,2,4-Trimethylpentane	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND	120	ND
2-Butanone	NR	NR	NR	4	ND	NA	7	0.5 J	2	0.70 J	ND	ND
2-Hexanone	NR	NR	NR	ND	ND	NA	1	0.6 J	0.5 J	ND	ND	ND
2-Propanol	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND	ND	ND
3-Chloro-1-propene	NR	NR	NR	ND	ND	NA	0.4 J	0.5 J	0.4 J	ND	ND	ND
4-Ethyltoluene	NR	NR	NR	5	ND	NA	5	1	1	0.37 J	2.0 J	2.5 J
4-Methyl-2-pentanone	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND	ND	ND
Acetone	NR	NR	NR	5	5	NA	22	11	9	5.6 J	9.5 J	3.7 J
alpha-Chlorotoluene	NR	NR	NR	ND	ND	NA	0.6 J	ND	0.7 J	ND	ND	ND
Acrylonitrile	NR	NR	NR	0.4	ND	NA	0.4 J	0.4 J	ND	NR	NR	NR
Benzene	NR	NR	NR	0.8	ND	NA	0.9	0.9	0.6 J	ND	ND	ND
Benzyl Chloride	NR	NR	NR	1	ND	NA	0.7 J	ND	ND	NR	NR	NR
Bromodichloromethane	NR	NR	NR	ND	ND	NA	0.8 J	0.5 J	1 J	ND	ND	ND
Bromoform	NR	NR	NR	ND	ND	NA	1 J	0.3 J	2 J	ND	ND	ND
Bromomethane	NR	NR	NR	0.9	ND	NA	0.6 J	2	0.6 J	ND	ND	ND
Carbon Disulfide	NR	NR	NR	0.8	ND	NA	0.8	0.5 J	0.6	ND	ND	2.2 J
Carbon Tetrachloride	NR	NR	NR	2	ND	NA	1	ND	3	0.91 J	0.55 J	ND
Chlorobenzene	NR	NR	NR	ND	ND	NA	0.7 J	0.3 J	0.7 J	ND	ND	2.5 J, B
Chlorodibromomethane	NR	NR	NR	ND	ND	NA	1 J	1	1 J	NR	NR	NR
Chloroethane	NR	NR	NR	0.6	ND	NA	0.7	0.8	0.5 J	ND	ND	ND
Chloroform	NR	NR	NR	1	ND	NA	2	0.4 J	2	ND	1.4 J	1.5 J
Chloromethane	NR	NR	NR	0.8	0.8	NA	2	ND	0.4	ND	ND	ND
cis-1,2-Dichloroethene	46	ND	ND	4	ND	NA	6	0.5 J	4	1.6 J	2.3 J	7.5
cis-1,3-Dichloropropene	NR	NR	NR	ND	ND	NA	0.6 J	ND	0.5 J	ND	ND	ND
Cumene	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND	ND	ND
Cyclohexane	NR	NR	NR	ND	ND	NA	0.6 J	ND	0.4 J	ND	2.9	ND
Dichlorodifluoromethane	NR	NR	NR	3	2	NA	3	0.8 J	3	ND	ND	ND
Diisopropyl ether	NR	NR	NR	ND	ND	NA	ND	ND	ND	NR	NR	NR
Ethanol	NR	NR	NR	3	2	NA	15	9	1	1.6 J	ND	ND
Ethyl Acetate	NR	NR	NR	ND	ND	NA	ND	ND	ND	NR	NR	NR
Ethyl tert-butyl ether	NR	NR	NR	ND	ND	NA	0.6 J	0.4 J	0.5 J	NR	NR	NR
Ethylbenzene	NR	NR	NR	3	ND	NA	4	2	1	ND	3.6	1.4 J
Freon 11	NR	NR	NR	NR	NR	NR	NR	NR	NR	1.2 J	0.96 J	1.5 J
Freon 113	NR	NR	NR	4	ND	NA	5	4	12	12	6.5	3.0 J
Freon 114	NR	NR	NR	2	ND	NA	1 J	0.9 J	1 J	ND	ND	ND
Freon 12	NR	NR	NR	NR	NR	NR	NR	NR	NR	2.1 J	2.2 J	2.9 J
Heptane	NR	NR	NR	ND	ND	NA	0.8 J	0.7 J	0.5 J	ND	7.6	ND
Hexachlorobutadiene	NR	NR	NR	2	ND	NA	2 J	1 J	2 J	ND	ND	ND
Hexane	NR	NR	NR	0.8	ND	NA	1	1	1	ND	ND	ND
iso-Octane	NR	NR	NR	1	ND	NA	19	0.9 J	0.8 J	NR	NR	NR
Isopropylbenzene	NR	NR	NR	1	ND	NA	1	0.5 J	0.7 J	NR	NR	NR
Isopropyl alcohol	NR	NR	NR	1	ND	NA	13	1	1	NR	NR	NR
m,p-Xylene	NR	NR	NR	NR	NR	NA	NR	NR	NR	0.80 J	15	2.6 J
Methyl Methacrylate	NR	NR	NR	ND	ND	NA	0.5 J	ND	0.5 J	NR	NR	NR
Methyl-tert-Butyl-Ether	NR	NR	NR	ND	ND	NA	0.7 J	0.5 J	0.7	ND	ND	ND
Methylene Chloride	NR	NR	NR	2	0.8	NA	6	2	5	0.71 J	2.0 J	ND
MIBK	NR	NR	NR	ND	ND	NA	0.8 J	0.4 J	0.5 J	NR	NR	NR
Naphthalene	NR	NR	NR	6	ND	NA	26	1	2	NR	NR	NR
n-Butane	NR	NR	NR	0.8	0.5	NA	1	0.5 J	ND	NR	NR	NR
o-Xylene	NR	NR	NR	NR	NR	NA	NR	NR	NR	ND	5.9	0.93 J
p-Isopropyltoluene	NR	NR	NR	2	ND	NA	1	ND	0.8 J	NR	NR	NR
n-Propylbenzene	NR	NR	NR	3	ND	NA	3	0.7 J	0.9 J	ND	0.48 J	0.54 J
Propylene	NR	NR	NR	ND	ND	NA	ND	ND	ND	NR	NR	NR
Styrene	NR	NR	NR	ND	ND	NA	0.7 J	ND	0.5 J	ND	ND	ND
tert-Amyl methyl ether	NR	NR	NR	ND	ND	NA	0.6 J	0.4 J	0.6 J	NR	NR	NR
tert-Butyl Alcohol	NR	NR	NR	0.9	ND	NA	2	1 J	0.8	NR	NR	NR
Tetrachloroethene	390	35	ND	15	ND	NA	15	7	19	4.3 J	7.2	27
Tetrahydrofuran	NR	NR	NR	6	ND	NA	8	2	2	0.87 J	1.2 J	ND
Toluene	NR	NR	NR	2	ND	NA	5	3	1	0.44 J	3.4	0.93 J
Total Xylenes	NR	NR	NR	17	ND	NA	22	8	6	NR	NR	NR
trans-1,2-Dichloroethene	7.9	ND	3.1	0.9	ND	NA	0.8	0.5 J	0.7 J	ND	ND	ND
trans-1,3-Dichloropropene	NR	NR	NR	ND	ND	NA	0.6 J	ND	ND	ND	ND	ND
Trichloroethene	1900	41	ND	140	10	NA	210	92	190	69	110	260
Trichlorofluoromethane	NR	NR	NR	2	1	NA	2	2	2	NR	NR	NR
Vinyl Acetate	NR	NR	NR	1	ND	NA	3	ND	ND	NR	NR	NR
Vinyl Bromide	NR	NR	NR	0.9	ND	NA	0.7 J	0.5 J	0.7 J	NR	NR	NR
Vinyl Chloride	ND	ND	ND	0.5	ND	NA	0.4 J	0.3 J	0.4 J	ND	ND	ND

**Notes:**  
µg/m<sup>3</sup> = micrograms per cubic mete  
NR = Not Recorded  
NA = Data not available. Vapor samp

Table 6  
Soil Vapor Extraction Containment System  
Site 1, Former Drum Marshalling Yard  
Naval Weapons Industrial Reserve Plant - Bethpage, NY  
Quarterly Vapor Monitoring Results of Individual Wells  
Through Third Quarter 2012



Sample ID	SVE 106D											
	12/21/09	03/31/10	06/09/10	09/16/10	12/08/10	03/30/11	06/28/11	09/06/11	10/14/11	02/10/12	05/11/12	09/11/12
<b>Analysis by TO-15 (µg/m<sup>3</sup>)</b>												
1,1,1-Trichloroethane	340	32	30	20	12	9	20	23	29	ND	11	26
1,1,2,2-Tetrachloroethane	NR	NR	NR	ND	ND	ND	ND	0.9 J	1 J	ND	ND	ND
1,1,2-Trichloroethane	NR	NR	NR	ND	ND	ND	ND	0.7 J	0.9 J	ND	ND	ND
1,1-Dichloroethane	250	6.3	ND	5	2	5	4	3	3	ND	3.0	4.3
1,1-Dichloroethene	ND	ND	ND	ND	ND	ND	0.5 J	0.7 J	0.8	ND	ND	ND
1,2,3-Trichloropropane	NR	NR	NR	ND	ND	ND	ND	0.7 J	1 J	NR	NR	NR
1,2,3-Trimethylbenzene	NR	NR	NR	8	ND	ND	6	ND	2	NR	NR	NR
1,2,4-Trichlorobenzene	NR	NR	NR	NR	ND	ND	1 J	ND	0.9 J	ND	1.9 J	ND
1,2,4-Trimethylbenzene	NR	NR	NR	17	2	2	23	ND	4	ND	ND	3.6 J
1,2-Dibromoethane	NR	NR	NR	ND	ND	ND	ND	ND	1 J	ND	ND	ND
1,2-Dichlorobenzene	NR	NR	NR	ND	ND	ND	ND	ND	1 J	ND	ND	ND
1,2-Dichloroethane	NR	ND	ND	ND	ND	ND	ND	0.6 J	0.7 J	ND	ND	ND
1,2-Dichloropropane	NR	NR	NR	ND	ND	ND	ND	0.6 J	0.8 J	ND	ND	ND
1,3,5-Trimethylbenzene	NR	NR	NR	6	ND	ND	4	ND	1	ND	2.3 J	0.97 J
1,3-Butadiene	NR	NR	NR	ND	ND	ND	ND	0.3 J	ND	ND	ND	ND
1,3-Dichlorobenzene	NR	NR	NR	ND	ND	ND	ND	ND	0.8 J	ND	ND	ND
1,4-Dichlorobenzene	NR	NR	NR	ND	ND	ND	ND	ND	0.8 J	ND	ND	0.87 J
1,4-Dioxane	NR	NR	NR	ND	ND	ND	0.5 J	0.7 J	0.7 J	ND	ND	ND
2,2,4-Trimethylpentane	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND	390	1.2 J
2-Butanone	NR	NR	NR	8	2	0.8	5	1	2	ND	ND	4.0 J
2-Hexanone	NR	NR	NR	ND	ND	ND	ND	0.5 J	0.8 J	ND	ND	ND
2-Propanol	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND	ND	ND
3-Chloro-1-propene	NR	NR	NR	ND	ND	ND	ND	0.4 J	0.4 J	ND	ND	ND
4-Ethyltoluene	NR	NR	NR	6	ND	ND	4	ND	1	ND	2.8 J	2.9 J
4-Methyl-2-pentanone	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND	ND	ND
Acetone	NR	NR	NR	25	9	5	11	6	6	4.8 J	13 J	11 J
alpha-Chlorotoluene	NR	NR	NR	ND	ND	ND	ND	ND	0.9 J	ND	ND	ND
Acrylonitrile	NR	NR	NR	ND	ND	ND	0.4 J	0.4 J	ND	NR	NR	NR
Benzene	NR	NR	NR	ND	ND	ND	2	0.5 J	0.6 J	0.58 J	1.5 J	1.1 J
Benzyl Chloride	NR	NR	NR	ND	ND	ND	ND	ND	0.6 J	NR	NR	NR
Bromodichloromethane	NR	NR	NR	ND	ND	ND	ND	0.9 J	1 J	ND	ND	ND
Bromoform	NR	NR	NR	ND	ND	ND	ND	ND	2 J	ND	ND	ND
Bromomethane	NR	NR	NR	ND	ND	ND	ND	0.6 J	0.7 J	ND	ND	ND
Carbon Disulfide	NR	NR	NR	ND	ND	ND	0.6 J	0.6 J	0.6	ND	ND	ND
Carbon Tetrachloride	NR	NR	NR	8	26	17	9	6	18	ND	18	5.6
Chlorobenzene	NR	NR	NR	ND	ND	ND	ND	0.5 J	0.8 J	ND	ND	3.1 J, B
Chlorodibromomethane	NR	NR	NR	ND	ND	ND	ND	1 J	1 J	NR	NR	NR
Chloroethane	NR	NR	NR	ND	ND	ND	0.4 J	0.4 J	0.4 J	ND	ND	ND
Chloroform	NR	NR	NR	ND	2	2	5	5	5	ND	6.4	6.9
Chloromethane	NR	NR	NR	3	1	0.5	0.7	0.5	0.6	1.2 J	ND	ND
cis-1,2-Dichloroethene	79	13	11	13	2	11	11	5	4	ND	4.1	7.1
cis-1,3-Dichloropropene	NR	NR	NR	ND	ND	ND	ND	ND	0.7 J	ND	ND	ND
Cumene	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND	1.4 J	ND
Cyclohexane	NR	NR	NR	ND	ND	ND	1	0.4 J	0.4 J	ND	7.0	ND
Dichlorodifluoromethane	NR	NR	NR	6	3	3	4	2	3	ND	ND	ND
Diisopropyl ether	NR	NR	NR	ND	ND	ND	ND	ND	1 J	NR	NR	NR
Ethanol	NR	NR	NR	8	3	2	17	4	ND	2.3 J	ND	8.8
Ethyl Acetate	NR	NR	NR	ND	ND	ND	ND	ND	ND	NR	NR	NR
Ethyl tert-butyl ether	NR	NR	NR	ND	ND	ND	ND	0.6 J	0.6 J	NR	NR	NR
Ethylbenzene	NR	NR	NR	5	ND	ND	5	ND	1	ND	6.3	1.2 J
Freon 11	NR	NR	NR	NR	NR	NR	NR	NR	NR	1.2 J	1.3 J	2.7 J
Freon 113	NR	NR	NR	ND	18	30	16	25	25	ND	15	13
Freon 114	NR	NR	NR	ND	ND	ND	ND	1 J	1 J	ND	ND	ND
Freon 12	NR	NR	NR	NR	NR	NR	NR	NR	NR	1.1 J	2.3 J	3.3 J
Heptane	NR	NR	NR	ND	ND	ND	1	0.4 J	0.6 J	0.82 J	18	1.0 J
Hexachlorobutadiene	NR	NR	NR	ND	ND	ND	ND	1 J	2 J	ND	ND	ND
Hexane	NR	NR	NR	3	ND	ND	3	2	0.6 J	ND	ND	1.8 J
iso-Octane	NR	NR	NR	ND	ND	ND	130	0.7 J	0.8 J	NR	NR	NR
Isopropylbenzene	NR	NR	NR	ND	ND	ND	0.8 J	0.5 J	0.8 J	NR	NR	NR
Isopropyl alcohol	NR	NR	NR	5	ND	2	3	2	ND	NR	NR	NR
m,p-Xylene	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND	21	4.2
Methyl Methacrylate	NR	NR	NR	ND	ND	ND	ND	0.4 J	0.4 J	NR	NR	NR
Methyl-tert-Butyl-Ether	NR	NR	NR	ND	ND	ND	ND	1	0.5 J	ND	ND	ND
Methylene Chloride	NR	NR	NR	4	2	4	5	17	1	3.9	ND	1.7 J
MIBK	NR	NR	NR	ND	ND	ND	0.5 J	0.4 J	0.6 J	NR	NR	NR
Naphthalene	NR	NR	NR	8	ND	ND	25	ND	3	NR	NR	NR
n-Butane	NR	NR	NR	ND	1	0.9	6	0.9	ND	NR	NR	NR
o-Xylene	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND	24	1.9 J
p-Isopropyltoluene	NR	NR	NR	ND	ND	ND	0.7 J	ND	0.9 J	NR	NR	NR
n-Propylbenzene	NR	NR	NR	ND	ND	ND	2	ND	0.9 J	ND	0.45 J	1.0 J
Propylene	NR	NR	NR	ND	ND	ND	ND	ND	MD	NR	NR	NR
Styrene	NR	NR	NR	ND	ND	ND	ND	ND	0.6 J	ND	ND	ND
tert-Amyl methyl ether	NR	NR	NR	ND	ND	ND	ND	0.5 J	0.6 J	NR	NR	NR
tert-Butyl Alcohol	NR	NR	NR	4	ND	ND	0.6 J	0.5 J	ND	NR	NR	NR
Tetrachloroethene	720	65	70	ND	13	19	41	8	66	ND	28	62
Tetrahydrofuran	NR	NR	NR	8	2	1	7	2	2	ND	1.1 J	4.0
Toluene	NR	NR	NR	5	2	2	11	0.5 J	3	0.81 J	11	15
Total Xylenes	NR	NR	NR	21	ND	ND	25	ND	6	NR	NR	NR
trans-1,2-Dichloroethene	15	ND	ND	ND	ND	ND	0.6 J	0.8	0.9	ND	ND	ND
trans-1,3-Dichloropropene	NR	NR	NR	ND	ND	ND	ND	ND	0.6 J	ND	ND	ND
Trichloroethene	3400	600	900	230	130	170	210	260	320	ND	180	380
Trichlorofluoromethane	NR	NR	NR	6	2	2	3	2	3	NR	NR	NR
Vinyl Acetate	NR	NR	NR	4	ND	ND	ND	ND	ND	NR	NR	NR
Vinyl Bromide	NR	NR	NR	ND	ND	ND	ND	0.6 J	0.9	NR	NR	NR
Vinyl Chloride	ND	1.6	ND	ND	ND	ND	ND	0.4 J	0.5 J	ND	ND	ND

**Notes:**  
µg/m<sup>3</sup> = micrograms per cubic mete  
NR = Not Recorded  
NA = Data not available. Vapor samp



## **FIGURES**






Department of the Navy  
Naval Facilities Engineering Command, Mid-Atlantic  
Site 1, Former Drum Marshalling Area  
Naval Weapons Industrial Reserve Plant  
Bethpage, NY

Figure 1: Site Location Map

H&S Environmental, Inc.








Department of the Navy  
 Naval Facilities Engineering Command, Mid-Atlantic  
 Site 1, Former Drum Marshalling Area  
 Naval Weapons Industrial Reserve Plant  
 Bethpage, NY

Figure 2  
 Site 1 Area and Vicinity

H&S Environmental, Inc.



<b>SITE PLAN</b>			
EXISTING LAYOUT SVE CONTAINMENT SYSTEM SITE 1 - NWIRP BETHPAGE BETHPAGE, NEW YORK			
H&S Environmental, Inc. 160 East Main Street, Suite 2F, Westborough, MA 01581			
SCALE IN FEET 0 160	DATE 5/22/2012	FIGURE 3	



NOTES:

1. ALL MAN DOORS AND OVERHEAD DOORS ARE EXISTING. MAN DOORS ARE APPROXIMATELY 7'X3'. OVERHEAD DOOR IS APPROXIMATELY 10'X10'.

PROCESS EQUIPMENT LIST		
ITEM NUMBER	NUMBER REQUIRED	NAME/DESCRIPTION
M-1	1	<b>MOISTURE SEPARATOR</b> -CONFIGURATION: VERTICAL, CYLINDRICAL -MATERIAL OF CONSTRUCTION: CARBON STEEL, EPOXY INTERIOR COATING, PAINT EXTERIOR COATING -CAPACITY: 400 GALLON CONDENSATE COLLECTION -DIMENSIONS: 5 FT DIA X 6 FEET HT, 718 GALLON
F-1	1	<b>MAKE-UP AIR FILTER</b> -CONFIGURATION: INTAKE FILTER/SILENCER COMBINATION HOUSING -MATERIAL OF CONSTRUCTION: CARBON STEEL, CORROSION RESISTANCE COATING -CAPACITY: 500 CFM AT 20 IW, 4 INCH FLANGED CONNECTION
F-2	1	<b>BLOWER AIR FILTER</b> -CONFIGURATION: INLINE VACUUM SERVICE FILTER -MATERIAL OF CONSTRUCTION: CARBON STEEL, CORROSION RESISTANCE COATING -CAPACITY: 1,200 CFM AT 35 IW, 10 INCH FLANGED CONNECTION
B-1A, B-1B	2	<b>SOIL VAPOR EXTRACTION BLOWER</b> -CONFIGURATION: HORIZONTAL CENTRIFUGAL -RATING: 600 CFM AT 40 IW -MOTOR: 7.5 HP, 460V, 3PH, 60HZ, ODP
VGAC-1	1	<b>VAPOR-PHASE GRANULAR ACTIVATED CARBON</b> -CONFIGURATION: RECTANGULAR TANK -MATERIAL OF CONSTRUCTION: CARBON STEEL, EPOXY INTERIOR COATING, EPOXY EXTERIOR COATING -RATING: 1,600 CFM AT 3 IW, 2,000 CFM AT 6 IW -CAPACITY: 5,000 LBS CARBON -DIMENSIONS: 6' X 8' FOOTPRINT, 6' 8" HT


<b>TETRA TECH ENGINEERING CORPORATION PC</b> <small>EST. 1987</small>		<small>DATE</small> <small>DATE</small> <small>DATE</small> <small>DATE</small>
<b>DEPARTMENT OF THE NAVY</b>	<b>NAVAL FACILITIES ENGINEERING COMMAND, MID-ATLANTIC</b>	<b>NAVAL WEAPONS INDUSTRIAL RESERVE PLANT</b>
<b>NAVAL FACILITIES ENGINEERING COMMAND</b>	<b>BETHPAGE, NEW YORK</b>	<b>SITE 1, FORMER DRUM MARSHALLING AREA</b>
<b>REVISION</b>	<b>DESCRIPTION</b>	<b>LAYOUT PLAN</b>
0	ISSUED FOR CONSTRUCTION	OFFICER IN CHARGE
	PREP BY	DATE
	DLB	10-14-09
	APPROV	SGP
	SUBMITTED BY	(NAME)
	SOUTHINGTON, CT	(DATE)
	OFFICER IN CHARGE	DATE
	APPROV	DATE

THIS DRAWING PRODUCED ON AUTOCAD  
DO NOT REVISE MANUALLY

THIS DOCUMENT IS THE PROPERTY OF  
NAVAL FACILITIES ENGINEERING COMMAND,  
PREPARED BY TETRA TECH ENGINEERING  
CORPORATION PC, AND IS PROVIDED UPON THE  
CONDITION THAT IT WILL NOT BE REPRODUCED,  
COPIED, OR ISSUED TO A THIRD PARTY, AND WILL  
BE USED SOLELY FOR THE ORIGINAL INTENDED  
PURPOSE AND SOLELY FOR THE EXECUTION  
OR REVIEW OF THE ENGINEERING CONSTRUCTION  
OF THE PROJECT.

IT IS A VIOLATION OF THE NEW YORK STATE  
EDUCATION LAW, ARTICLE 145, FOR ANY PERSON  
UNLESS UNDER THE DIRECTION OF A NEW YORK  
STATE LICENSED PROFESSIONAL ENGINEER, TO  
ALTER AN ITEM ON THIS DOCUMENT IN ANY WAY.

SAT TO	DATE
CODE I.D. NO.	
SCALE : AS SHOWN	
SPEC. NO.	
CONSTR. CONTR. NO.	N62473-10-D-3211
NAVFAC DRAWING NO.	Figure 4
SHEET	OF
D	1-3



SV-106I	9/11/2012
1,1,1-TCA	11
PCE	27
TCE	260

SV-106D	9/11/2012
1,1,1-TCA	26
PCE	62
TCE	380

SV-105D	9/11/2012
1,1,1-TCA	270
PCE	270
TCE	2200

SV-105I	9/11/2012
1,1,1-TCA	26
PCE	100
TCE	260

SV-103D	9/11/2012
1,1,1-TCA	22
PCE	4700
TCE	480

SV-103I	9/11/2012
1,1,1-TCA	9.2
PCE	430
TCE	130

SV-104D	9/11/2012
1,1,1-TCA	620
PCE	4600
TCE	1700

SV-104I	9/11/2012
1,1,1-TCA	8.3
PCE	86
TCE	73

SV-101D	9/11/2012
1,1,1-TCA	9.9
PCE	150
TCE	400

SV-101I	9/11/2012
1,1,1-TCA	3200
PCE	93
TCE	7200

SV-102D	9/11/2012
1,1,1-TCA	3.9 J
PCE	24
TCE	170

SV-102I	9/11/2012
1,1,1-TCA	3.3 J
PCE	6.4
TCE	99

**LEGEND**

- FORMER NWIRP BOUNDARY
- CURRENT NWIRP BOUNDARY
- ⊕ SVE CONTAINMENT WELL LOCATION
- J ESTIMATED VALUE
- ND NOT DETECTED ABOVE LABORATORY METHOD DETECTION LIMIT
- PCE TETRACHLOROETHENE
- 1,1,1-TCA 1,1,1-TRICHLOROETHANE
- TCE TRICHLOROETHENE

ALL CONCENTRATIONS REPORTED IN ug/m3.

3rd QUARTER 2012 VAPOR ANALYTICAL MAP  
SELECT VOC CONCENTRATIONS

SVE CONTAINMENT SYSTEM  
SITE 1 - NWIRP BETHPAGE  
BETHPAGE, NEW YORK

H&S Environmental, Inc.  
160 East Main Street, Suite 2F, Westborough, MA 01581



DATE  
2/5/2013

FIGURE  
5



**APPENDIX A**

**NYSDEC AIR PERMIT  
EQUIVALENT APPROVAL**



**New York State Department of Environmental Conservation**  
**Division of Environmental Remediation**  
**Bureau of Remedial Action A**  
**625 Broadway, 11<sup>th</sup> Floor**  
**Albany, New York 12233-7015**  
**Phone: (518) 402-9625 • Fax: (518) 402-9022**



**Website:** [www.dec.state.ny.us](http://www.dec.state.ny.us)

February 5, 2010

Lora Fly, Project Manager  
Naval Facilities Engineering Command-Midlant  
9742 Maryland Avenue  
Norfolk, VA 23511-3095

RE: Naval Weapons Industrial Research Plant( NWIRP)  
Site-Bethpage, NYSDEC No. 1-30-003B.

Dear Ms. Fly:

Tetra Tech FW, on behalf of the Department of the Navy (Navy), has submitted the enclosed New York State Department of Environmental Conservation (NYSDEC) Division of Air Resources (DAR) Air Permit Application as a permit equivalent. This DAR Air permit equivalent is for the soil vapor extraction system at Site 1 of Plant 3 of the former Naval Weapons Industrial Reserve Plant (NWIRP) site in Bethpage, NY. The NYSDEC Division of Environmental Remediation (DER) has reviewed the permit equivalent and, by means of this letter approves the Site 1 remedy air discharge for immediate operation.

The NWIRP Site 1 SVE system utilizes the reasonably available control technology (RACT) with activated carbon. The air discharge will be periodically monitored at start up and will be added for routine monitoring in the operation, maintenance and monitoring (OMM) plan, to be submitted shortly for Departmental review.

If you have any questions, please contact me at your earliest convenience at (518)402-9620.

Sincerely,

A handwritten signature in cursive script, appearing to read "Steve Scharf".

Steven M. Scharf, P.E.  
Project Engineer  
Division of Environmental Remediation  
Bureau of Remedial Action A

Enclosure

cc/w/enc: J. Swartwout/S. Scharf/File  
W. Parish, Region 1 NYSDEC  
A. J. Shah, Region 1 NYSDEC  
S. Patselos, Tetra Tech FW  
J. Cofman, Northrop Grumman

E docs: Region 1, Nassau, Oyster Bay (T): NWIRP Bethpage 130003B-OUI-OMM



# New York State Department of Environmental Conservation Air Permit Application



DEC ID									
-	-	-	-	-	-	-	-	-	-

APPLICATION ID														
-	-	-	-	-	-	-	-	-	-	-	-	-	-	-

OFFICE USE ONLY									
/	/	/	/	/	/	/	/	/	/

## Section I - Certification

Title V Certification	
I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons directly responsible for gathering the information [required pursuant to 6 NYCRR 201-6.3(d)] I believe the information is, true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fines and imprisonment for knowing violations.	
Responsible Official	Title
Signature	Date <u>    /    /    </u>

State Facility Certification	
I certify that this facility will be operated in conformance with all provisions of existing regulations.	
Responsible Official	Title
Signature	Date <u>    /    /    </u>

## Section II - Identification Information

Title V Facility Permit <u>N/A</u> <input type="checkbox"/> New <input type="checkbox"/> Significant Modification <input type="checkbox"/> Renewal <input type="checkbox"/> Minor Modification	<input type="checkbox"/> Administrative Amendment General Permit Title: _____	State Facility Permit <u>N/A</u> <input type="checkbox"/> New <input type="checkbox"/> Modification General Permit Title: _____
<input checked="" type="checkbox"/> Application involves construction of new facility		<input type="checkbox"/> Application involves construction of new emission unit(s)

Owner/Firm				
Name <u>US Navy / NAVFAC Midlant</u>				
Street Address <u>9742 Maryland Ave, Bldg Z-144</u>				
City <u>Norfolk</u>	State <u>VA</u>	Country <u>US</u>	Zip <u>23511-3095</u>	
Owner Classification <input checked="" type="checkbox"/> Federal <input type="checkbox"/> Corporation/Partnership		<input type="checkbox"/> State <input type="checkbox"/> Individual	<input type="checkbox"/> Municipal	Taxpayer ID
Facility				
Name <u>Naval Weapons Industrial Reserve Plant (NWIRP) Site 1</u>				
Location Address <u>Bethpage</u>				
<input type="checkbox"/> City / <input checked="" type="checkbox"/> Town / <input type="checkbox"/> Village <u>Oyster Bay, New York</u>			Zip <u>11714</u>	
Project Description				
<input type="checkbox"/> Continuation Sheet(s) <u>Vapor phase granular activated carbon to remove VOCs from soil gas</u>				

Owner/Firm Contact Mailing Address				
Name (Last, First, Middle Initial) <u>Fly, Lora</u>			Phone No. <u>(757) 444-0781</u>	
Affiliation <u>Department of the Navy</u>		Title <u>Remedial PM</u>	Fax No. ( )	
Street Address <u>9742 Maryland Ave, Bldg Z-144</u>				
City <u>Norfolk</u>	State <u>VA</u>	Country <u>US</u>	Zip <u>23511-3095</u>	
Facility Contact Mailing Address				
Name (Last, First, Middle Initial)			Phone No. ( )	
Affiliation		Title	Fax No. ( )	
Street Address				
City	State	Country	Zip	

**New York State Department of Environmental Conservation  
Air Permit Application**



DEC ID									
-	-	-	-	-	-	-	-	-	-

**Section III - Facility Information**

Classification						
<input type="checkbox"/> Hospital	<input type="checkbox"/> Residential	<input type="checkbox"/> Educational/Institutional	<input type="checkbox"/> Commercial	<input checked="" type="checkbox"/> Industrial	<input type="checkbox"/> Utility	

Affected States (Title V Only) <i>N/A</i>						
<input type="checkbox"/> Vermont	<input type="checkbox"/> Massachusetts	<input type="checkbox"/> Rhode Island	<input type="checkbox"/> Pennsylvania	Tribal Land: _____		
<input type="checkbox"/> New Hampshire	<input type="checkbox"/> Connecticut	<input type="checkbox"/> New Jersey	<input type="checkbox"/> Ohio	Tribal Land: _____		

SIC Codes									
9999									

Facility Description							<input type="checkbox"/> Continuation Sheet(s)
<i>Soil vapor remediation by SVE followed by vapor phase GAC.</i>							

Compliance Statements (Title V Only) <i>N/A</i>						
<p>I certify that as of the date of this application the facility is in compliance with all applicable requirements: <input type="checkbox"/> YES <input type="checkbox"/> NO</p> <p>If one or more emission units at the facility are not in compliance with all applicable requirements at the time of signing this application (the 'NO' box must be checked), the noncomplying units must be identified in the "Compliance Plan" block on page 8 of this form along with the compliance plan information required. For all emission units at this facility that are operating <u>in compliance</u> with all applicable requirements complete the following:</p> <ul style="list-style-type: none"> <li><input type="checkbox"/> This facility will continue to be operated and maintained in such a manner as to assure compliance for the duration of the permit, except those units referenced in the compliance plan portion of Section IV of this application.</li> <li><input type="checkbox"/> For all emission units, subject to any applicable requirements that will become effective during the term of the permit, this facility will meet all such requirements on a timely basis.</li> <li><input type="checkbox"/> Compliance certification reports will be submitted at least once a year. Each report will certify compliance status with respect to each requirement, and the method used to determine the status.</li> </ul>						

Facility Applicable Federal Requirements <i>N/A</i>								<input type="checkbox"/> Continuation Sheet(s)	
Title	Type	Part	Sub Part	Section	Sub Division	Paragraph	Sub Paragraph	Clause	Sub Clause

Facility State Only Requirements								<input type="checkbox"/> Continuation Sheet(s)	
Title	Type	Part	Sub Part	Section	Sub Division	Paragraph	Sub Paragraph	Clause	Sub Clause

New York State Department of Environmental Conservation  
Air Permit Application



DEC ID									
-									

Section III - Facility Information (continued)

Facility Compliance Certification <u>N/A</u> <span style="float:right"><input type="checkbox"/> Continuation Sheet(s)</span>									
Rule Citation									
Title	Type	Part	Sub Part	Section	Sub Division	Paragraph	Sub Paragraph	Clause	Sub Clause
<input type="checkbox"/> Applicable Federal Requirement		<input type="checkbox"/> Capping			CAS No.		Contaminant Name		
<input type="checkbox"/> State Only Requirement		-							
Monitoring Information									
<input type="checkbox"/> Ambient Air Monitoring		<input type="checkbox"/> Work Practice Involving Specific Operations				<input type="checkbox"/> Record Keeping/Maintenance Procedures			
Description									
Work Practice									
Type	Code	Process Material Description					Reference Test Method		
Parameter									
Code		Description					Manufacturer Name/Model No.		
Limit									
Upper		Lower		Code		Limit Units Description			
Averaging Method									
Code		Description			Code		Description		

Facility Emissions Summary <span style="float:right"><input checked="" type="checkbox"/> Continuation Sheet(s)</span>					
CAS No.	Contaminant Name	PTE		Actual (lbs/yr)	
		(lbs/yr)	Range Code		
NY075 - 00 - 5	PM-10				
NY075 - 00 - 0	PARTICULATES				
7446 - 09 - 5	SULFUR DIOXIDE				
NY210 - 00 - 0	OXIDES OF NITROGEN				
630 - 08 - 0	CARBON MONOXIDE				
7439 - 92 - 1	LEAD				
NY998 - 00 - 0	VOC	1,222			
NY100 - 00 - 0	HAP	1,813			
00071 - 55 - 6	1,1,1-Trichloroethane (Methyl Chloroform)	591			
00127 - 18 - 4	Tetrachloroethylene	8			
00079 - 01 - 6	Trichloroethylene	1,181			
00075 - 34 - 3	1,1-Dichloroethane	11			
00075 - 35 - 4	1,1-Dichloroethylene (Vinylidene Chloride)	16			



New York State Department of Environmental Conservation  
Air Permit Application



DEC ID									
-	-	-	-	-	-	-	-	-	-

Section III - Facility Information

CAS No.	Contaminant Name	PTE		Actual (lbs/yr)
		(lbs/yr)	Range Code	
00540-59-0	cis-1,2-Dichloroethene	5		
00107-06-2	1,2-Dichloroethane	0		
00156-60-5	trans-1,2-Dichloroethene	0		
00075-01-4	Vinyl Chloride	0		
-	-			
-	-			
-	-			
-	-			
-	-			
-	-			
-	-			
-	-			
-	-			
-	-			
-	-			
-	-			
-	-			
-	-			
-	-			
-	-			
-	-			
-	-			
-	-			
-	-			
-	-			
-	-			
-	-			
-	-			
-	-			
-	-			
-	-			
-	-			
-	-			

New York State Department of Environmental Conservation  
Air Permit Application



DEC ID									
-	-	-	-	-	-	-	-	-	-

Section IV - Emission Unit Information

Emission Unit Description <span style="float: right;"><input type="checkbox"/> Continuation Sheet(s)</span>										
EMISSION UNIT	1	-	0	0	E	U	1	Effluent from first soil vapor extraction blower (BL-1)		
Vapor Phase Granular Activated Carbon Unit. The emission point is stack 00ST-2										

Building <span style="float: right;"><input type="checkbox"/> Continuation Sheet(s)</span>					
Building	Building Name		Length (ft)	Width (ft)	Orientation
03-35	Treatment Building		60	40	0

Emission Point <span style="float: right;"><input type="checkbox"/> Continuation Sheet(s)</span>						
EMISSION PT.	00ST2					
Ground Elev. (ft)	Height (ft)	Height Above Structure (ft)	Inside Diameter (in)	Exit Temp. (°F)	Cross Section	
	36	6	8	70	Length (in)	Width (in)
Exit Velocity (FPS)	Exit Flow (ACFM)	NYTM (E) (KM)	NYTM (N) (KM)	Building	Distance to Property Line (ft)	Date of Removal
	1,000			03-35	100'	

Emission Point <span style="float: right;"><input type="checkbox"/> Continuation Sheet(s)</span>						
EMISSION PT.						
Ground Elev. (ft)	Height (ft)	Height Above Structure (ft)	Inside Diameter (in)	Exit Temp. (°F)	Cross Section	
					Length (in)	Width (in)
Exit Velocity (FPS)	Exit Flow (ACFM)	NYTM (E) (KM)	NYTM (N) (KM)	Building	Distance to Property Line (ft)	Date of Removal

Emission Source/Control <span style="float: right;"><input type="checkbox"/> Continuation Sheet(s)</span>							
Emission Source		Date of Construction	Date of Operation	Date of Removal	Control Type		Manufacturer's Name/Model No.
ID	Type				Code	Description	
BL1/2	1				048	Granular Act. Carbon	Tetrasolv Filtration
Design Capacity	Design Capacity Units			Waste Feed		Waste Type	
	Code	Description		Code	Description	Code	Description

Emission Source/Control <span style="float: right;"><input type="checkbox"/> Continuation Sheet(s)</span>							
Emission Source		Date of Construction	Date of Operation	Date of Removal	Control Type		Manufacturer's Name/Model No.
ID	Type				Code	Description	
Design Capacity	Design Capacity Units			Waste Feed		Waste Type	
	Code	Description		Code	Description	Code	Description



New York State Department of Environmental Conservation  
Air Permit Application



DEC ID									
-									

Section IV - Emission Unit Information (continued)

Process Information					<input type="checkbox"/> Continuation Sheet(s)	
EMISSION UNIT <b>4-00EU1</b>				PROCESS <b>SVE</b>		
Description						
The Soil Vapor Extraction System will consist of 12 SVE wells (6 intermediate and 6 deep), a moisture separator, and 2 soil vapor extraction blowers (BL-1 and BL-2) which both vent to a vapor phase granular activated carbon unit for treatment prior to discharge from stack 00ST2. The VGAC unit will be a 5,000 pound unit filled with Tetrasolv Virgin Carbon. The VGAC unit has been designed to operate nominally at 600 cfm, with a maximum of 1,000 cfm.						
Source Classification Code (SCC)	Total Thruput		Thruput Quantity Units			
	Quantity/Hr	Quantity/Yr	Code	Description		
<input type="checkbox"/> Confidential <input checked="" type="checkbox"/> Operating at Maximum Capacity <input type="checkbox"/> Activity with Insignificant Emissions	Operating Schedule		Building	Floor/Location		
	Hrs/Day	Days/Yr				
	24	365	03-35	Main		
Emission Source/Control Identifier(s)						
BL-1	BL-2					
EMISSION UNIT				PROCESS		
Description						
Source Classification Code (SCC)	Total Thruput		Thruput Quantity Units			
	Quantity/Hr	Quantity/Yr	Code	Description		
<input type="checkbox"/> Confidential <input type="checkbox"/> Operating at Maximum Capacity <input type="checkbox"/> Activity with Insignificant Emissions	Operating Schedule		Building	Floor/Location		
	Hrs/Day	Days/Yr				
Emission Source/Control Identifier(s)						

New York State Department of Environmental Conservation  
Air Permit Application



DEC ID									
-	-	-	-	-	-	-	-	-	-

Section IV - Emission Unit Information (continued)

Emission Unit	Emission Point	Process	Emission Source	Emission Unit Applicable Federal Requirements										<input type="checkbox"/> Continuation Sheet(s)	
				Title	Type	Part	Sub Part	Section	Sub Division	Parag.	Sub Parag.	Clause	Sub Clause		
-															
-															
-															
-															

Emission Unit	Emission Point	Process	Emission Source	Emission Unit State Only Requirements										<input type="checkbox"/> Continuation Sheet(s)	
				Title	Type	Part	Sub Part	Section	Sub Division	Parag.	Sub Parag.	Clause	Sub Clause		
-															
-															
-															
-															

Emission Unit Compliance Certification										<input type="checkbox"/> Continuation Sheet(s)
Rule Citation										
Title	Type	Part	Sub Part	Section	Sub Division	Paragraph	Sub Paragraph	Clause	Sub Clause	
G	NYCRR	212	-							
<input type="checkbox"/> Applicable Federal Requirement			<input type="checkbox"/> State Only Requirement			<input type="checkbox"/> Capping				
Emission Unit	Emission Point	Process	Emission Source	CAS No.			Contaminant Name			
1-00EU1	00ST3	SVE		00079-01-6			Trichloroethylene			
Monitoring Information										
<input type="checkbox"/> Continuous Emission Monitoring <input checked="" type="checkbox"/> Intermittent Emission Testing <input type="checkbox"/> Ambient Air Monitoring					<input type="checkbox"/> Monitoring of Process or Control Device Parameters as Surrogate <input type="checkbox"/> Work Practice Involving Specific Operations <input type="checkbox"/> Record Keeping/Maintenance Procedures					
Description										
Monthly grab samples analyzed for VOCs from the VGAC unit influent and effluent										
Work Practice		Process Material				Reference Test Method				
Type	Code	Description								
						Manufacturer Name/Model No.				
Code		Description								
23		Concentration								
Limit			Limit Units							
Upper		Lower		Code	Description					
36,000				255	micrograms per cubic meter					
Averaging Method			Monitoring Frequency			Reporting Requirements				
Code	Description		Code	Description		Code	Description			
01	Instantaneous		05	Monthly		10	Upon Request			



New York State Department of Environmental Conservation  
Air Permit Application



DEC ID									
-	-	-	-	-	-	-	-	-	-

Section IV - Emission Unit Information (continued)

Determination of Non-Applicability (Title V Only) <i>N/A</i>										<input type="checkbox"/> Continuation Sheet(s)	
Rule Citation											
Title	Type	Part	Sub Part	Section	Sub Division	Paragraph	Sub Paragraph	Clause	Sub Clause		
Emission Unit		Emission Point		Process	Emission Source		<input type="checkbox"/> Applicable Federal Requirement				
							<input type="checkbox"/> State Only Requirement				
Description											
Rule Citation											
Title	Type	Part	Sub Part	Section	Sub Division	Paragraph	Sub Paragraph	Clause	Sub Clause		
Emission Unit		Emission Point		Process	Emission Source		<input type="checkbox"/> Applicable Federal Requirement				
							<input type="checkbox"/> State Only Requirement				
Description											
Process Emissions Summary										<input checked="" type="checkbox"/> Continuation Sheet(s)	
EMISSION UNIT		1-00EU1					PROCESS		SVE		
CAS No.	Contaminant Name			% Thruput	% Capture	% Control	ERP (lbs/hr)	ERP How Determined			
00071-55-6	1,1,1-Trichloroethane					80	0.34	02			
PTE			Standard Units	PTE How Determined		Actual					
(lbs/hr)	(lbs/yr)	(standard units)				(lbs/hr)	(lbs/yr)				
0.07	591			02							
EMISSION UNIT		1-00EU1					PROCESS		SVE		
CAS No.	Contaminant Name			% Thruput	% Capture	% Control	ERP (lbs/hr)	ERP How Determined			
00127-18-4	Tetrachloroethylene					80	0.00	02			
PTE			Standard Units	PTE How Determined		Actual					
(lbs/hr)	(lbs/yr)	(standard units)				(lbs/hr)	(lbs/yr)				
0.00 BRT	8			02							
EMISSION UNIT		1-00EU1					PROCESS		SVE		
CAS No.	Contaminant Name			% Thruput	% Capture	% Control	ERP (lbs/hr)	ERP How Determined			
00079-01-6	Trichloroethylene					80	0.67	02			
PTE			Standard Units	PTE How Determined		Actual					
(lbs/hr)	(lbs/yr)	(standard units)				(lbs/hr)	(lbs/yr)				
0.13	1,181			02							



New York State Department of Environmental Conservation  
Air Permit Application



DEC ID									
-									

Section IV - Emission Unit Information (continued)

EMISSION UNIT		Emission Unit Emissions Summary				<input checked="" type="checkbox"/> Continuation Sheet(s)
i-00EU1						
CAS No.		Contaminant Name				
00075-34-3		1,1-Dichloroethane				
ERP (lbs/yr)	PTE Emissions			Actual		
	(lbs/hr)	(lbs/yr)	(lbs/hr)	(lbs/yr)		
	BRT	11				
CAS No.		Contaminant Name				
00075-35-4		1,1-Dichloroethylene (Vinylidene Chloride)				
ERP (lbs/yr)	PTE Emissions			Actual		
	(lbs/hr)	(lbs/yr)	(lbs/hr)	(lbs/yr)		
	BRT	16				
CAS No.		Contaminant Name				
00540-59-0		cis-1,2-Dichloroethane				
ERP (lbs/yr)	PTE Emissions			Actual		
	(lbs/hr)	(lbs/yr)	(lbs/hr)	(lbs/yr)		
	BRT	5				
CAS No.		Contaminant Name				
00107-06-2		1,2-Dichloroethane				
ERP (lbs/yr)	PTE Emissions			Actual		
	(lbs/hr)	(lbs/yr)	(lbs/hr)	(lbs/yr)		
	BRT	BRT				

Compliance Plan N/A												<input type="checkbox"/> Continuation Sheet(s)
For any emission units which are <u>not in compliance</u> at the time of permit application, the applicant shall complete the following												
Consent Order		Certified progress reports are to be submitted every 6 months beginning ___ / ___ / ___										
Emission Unit	Process	Emission Source	Applicable Federal Requirement									
			Title	Type	Part	Sub Part	Section	Sub Division	Parag.	Sub Parag.	Clause	Sub Clause
Remedial Measure / Intermediate Milestones										R/I	Date Scheduled	

New York State Department of Environmental Conservation  
Air Permit Application



DEC ID									
-	-	-	-	-	-	-	-	-	-

Section IV - Emission Unit Information

EMISSION UNIT		Emission Unit Emissions Summary (continuation)			
1-00E41					
CAS No.		Contaminant Name			
00156-60-5		trans-1,2-Dichloroethene			
ERP (lbs/yr)	PTE Emissions		Actual		
	(lbs/hr)	(lbs/yr)	(lbs/hr)	(lbs/yr)	
		BRT	BRT		
CAS No.		Contaminant Name			
00075-01-4		Vinyl Chloride			
ERP (lbs/yr)	PTE Emissions		Actual		
	(lbs/hr)	(lbs/yr)	(lbs/hr)	(lbs/yr)	
		BRT	BRT		
CAS No.		Contaminant Name			
-					
ERP (lbs/yr)	PTE Emissions		Actual		
	(lbs/hr)	(lbs/yr)	(lbs/hr)	(lbs/yr)	
CAS No.		Contaminant Name			
-					
ERP (lbs/yr)	PTE Emissions		Actual		
	(lbs/hr)	(lbs/yr)	(lbs/hr)	(lbs/yr)	
CAS No.		Contaminant Name			
-					
ERP (lbs/yr)	PTE Emissions		Actual		
	(lbs/hr)	(lbs/yr)	(lbs/hr)	(lbs/yr)	
CAS No.		Contaminant Name			
-					
ERP (lbs/yr)	PTE Emissions		Actual		
	(lbs/hr)	(lbs/yr)	(lbs/hr)	(lbs/yr)	
CAS No.		Contaminant Name			
-					
ERP (lbs/yr)	PTE Emissions		Actual		
	(lbs/hr)	(lbs/yr)	(lbs/hr)	(lbs/yr)	
CAS No.		Contaminant Name			
-					
ERP (lbs/yr)	PTE Emissions		Actual		
	(lbs/hr)	(lbs/yr)	(lbs/hr)	(lbs/yr)	



**New York State Department of Environmental Conservation  
Air Permit Application**



DEC ID									
-									

**Section IV - Emission Unit Information (continued)**

Request for Emission Reduction Credits						<input type="checkbox"/> Continuation Sheet(s)			
EMISSION UNIT -									
Emission Reduction Description									
Contaminant Emission Reduction Data									
Baseline Period ____ / ____ / ____ to ____ / ____ / ____						Reduction			
						Date		Method	
						/ /			
CAS No.		Contaminant Name				ERC (lbs/yr)			
						Netting		Offset	
-									
-									
-									
Facility to Use Future Reduction									
Name						APPLICATION ID			
						- / -			
Location Address									
<input type="checkbox"/> City / <input type="checkbox"/> Town / <input type="checkbox"/> Village						State		Zip	

Use of Emission Reduction Credits						<input type="checkbox"/> Continuation Sheet(s)			
EMISSION UNIT -									
Proposed Project Description									
Contaminant Emissions Increase Data									
CAS No.		Contaminant Name				PEP (lbs/yr)			
-									
Statement of Compliance									
<input type="checkbox"/> All facilities under the ownership of this "ownership/firm" are operating in compliance with all applicable requirements and state regulations including any compliance certification requirements under Section 114(a)(3) of the Clean Air Act Amendments of 1990, or are meeting the schedule of a consent order.									
Source of Emission Reduction Credit - Facility									
Name						PERMIT ID			
						- / -			
Location Address									
<input type="checkbox"/> City / <input type="checkbox"/> Town / <input type="checkbox"/> Village						State		Zip	
Emission Unit	CAS No.	Contaminant Name			ERC (lbs/yr)				
					Netting		Offset		
-	-								
-	-								
-	-								

New York State Department of Environmental Conservation  
Air Permit Application



DEC ID										
-										


Supporting Documentation

- P.E. Certification (form attached)
- List of Exempt Activities (form attached)
- Plot Plan
- Methods Used to Determine Compliance (form attached)
- Calculations
- Air Quality Model ( \_\_\_\_ / \_\_\_\_ / \_\_\_\_ )
- Confidentiality Justification
- Ambient Air Monitoring Plan ( \_\_\_\_ / \_\_\_\_ / \_\_\_\_ )
- Stack Test Protocols/Reports ( \_\_\_\_ / \_\_\_\_ / \_\_\_\_ )
- Continuous Emissions Monitoring Plans/QA/QC ( \_\_\_\_ / \_\_\_\_ / \_\_\_\_ )
- MACT Demonstration ( \_\_\_\_ / \_\_\_\_ / \_\_\_\_ )
- Operational Flexibility: Description of Alternative Operating Scenarios and Protocols
- Title IV: Application/Registration
- ERC Quantification (form attached)
- Use of ERC(s) (form attached)
- Baseline Period Demonstration
- Analysis of Contemporaneous Emission Increase/Decrease
- LAER Demonstration ( \_\_\_\_ / \_\_\_\_ / \_\_\_\_ )
- BACT Demonstration ( \_\_\_\_ / \_\_\_\_ / \_\_\_\_ )
- Other Document(s): \_\_\_\_\_ ( \_\_\_\_ / \_\_\_\_ / \_\_\_\_ )  
 \_\_\_\_\_ ( \_\_\_\_ / \_\_\_\_ / \_\_\_\_ )  
 \_\_\_\_\_ ( \_\_\_\_ / \_\_\_\_ / \_\_\_\_ )  
 \_\_\_\_\_ ( \_\_\_\_ / \_\_\_\_ / \_\_\_\_ )  
 \_\_\_\_\_ ( \_\_\_\_ / \_\_\_\_ / \_\_\_\_ )  
 \_\_\_\_\_ ( \_\_\_\_ / \_\_\_\_ / \_\_\_\_ )  
 \_\_\_\_\_ ( \_\_\_\_ / \_\_\_\_ / \_\_\_\_ )  
 \_\_\_\_\_ ( \_\_\_\_ / \_\_\_\_ / \_\_\_\_ )  
 \_\_\_\_\_ ( \_\_\_\_ / \_\_\_\_ / \_\_\_\_ )  
 \_\_\_\_\_ ( \_\_\_\_ / \_\_\_\_ / \_\_\_\_ )  
 \_\_\_\_\_ ( \_\_\_\_ / \_\_\_\_ / \_\_\_\_ )  
 \_\_\_\_\_ ( \_\_\_\_ / \_\_\_\_ / \_\_\_\_ )  
 \_\_\_\_\_ ( \_\_\_\_ / \_\_\_\_ / \_\_\_\_ )  
 \_\_\_\_\_ ( \_\_\_\_ / \_\_\_\_ / \_\_\_\_ )  
 \_\_\_\_\_ ( \_\_\_\_ / \_\_\_\_ / \_\_\_\_ )


## **APPENDIX B**

### **VAPOR CONCENTRATION TREND GRAPHS**

**Soil Vapor Extraction Containment System  
 Site 1, Former Drum Marshalling Yard  
 Naval Weapons Industrial Reserve Plant - Bethpage, NY  
 Vapor Concentration Trends of Select and Total VOCs  
 COMBINED INFLUENT**




Soil Vapor Extraction Containment System  
Site 1, Former Drum Marshalling Yard  
Naval Weapons Industrial Reserve Plant - Bethpage, NY  
Groundwater Concentration Trends of Select VOCs  
**SV-101I**



Soil Vapor Extraction Containment System  
Site 1, Former Drum Marshalling Yard  
Naval Weapons Industrial Reserve Plant - Bethpage, NY  
Groundwater Concentration Trends of Select VOCs


SV-101D






Soil Vapor Extraction Containment System  
Site 1, Former Drum Marshalling Yard  
Naval Weapons Industrial Reserve Plant - Bethpage, NY  
Groundwater Concentration Trends of Select VOCs

SV102I




Soil Vapor Extraction Containment System  
Site 1, Former Drum Marshalling Yard  
Naval Weapons Industrial Reserve Plant - Bethpage, NY  
Groundwater Concentration Trends of Select VOCs

SV-102D




Soil Vapor Extraction Containment System  
Site 1, Former Drum Marshalling Yard  
Naval Weapons Industrial Reserve Plant - Bethpage, NY  
Groundwater Concentration Trends of Select VOCs

SV-103I




Soil Vapor Extraction Containment System  
Site 1, Former Drum Marshalling Yard  
Naval Weapons Industrial Reserve Plant - Bethpage, NY  
Groundwater Concentration Trends of Select VOCs

SV103D




Soil Vapor Extraction Containment System  
Site 1, Former Drum Marshalling Yard  
Naval Weapons Industrial Reserve Plant - Bethpage, NY  
Groundwater Concentration Trends of Select VOCs

SV104I




Soil Vapor Extraction Containment System  
Site 1, Former Drum Marshalling Yard  
Naval Weapons Industrial Reserve Plant - Bethpage, NY  
Groundwater Concentration Trends of Select VOCs

**SV-104D**



Soil Vapor Extraction Containment System  
Site 1, Former Drum Marshalling Yard  
Naval Weapons Industrial Reserve Plant - Bethpage, NY  
Groundwater Concentration Trends of Select VOCs


SV-105I






Soil Vapor Extraction Containment System  
Site 1, Former Drum Marshalling Yard  
Naval Weapons Industrial Reserve Plant - Bethpage, NY  
Groundwater Concentration Trends of Select VOCs

SV-105D



Soil Vapor Extraction Containment System  
Site 1, Former Drum Marshalling Yard  
Naval Weapons Industrial Reserve Plant - Bethpage, NY  
Groundwater Concentration Trends of Select VOCs

SV-106I



Soil Vapor Extraction Containment System  
Site 1, Former Drum Marshalling Yard  
Naval Weapons Industrial Reserve Plant - Bethpage, NY  
Groundwater Concentration Trends of Select VOCs

SV-106D

