

**2015 OU2 GROUNDWATER INVESTIGATION  
RE114D1, RE114D2, RE114D3 (VPB148)  
INSTALLATION REPORT**

**NAVAL WEAPONS INDUSTRIAL RESERVE PLANT (NWIRP)  
SITE 1 OU2  
BETHPAGE, NY**

**Prepared for:**



**Department of the Navy  
Naval Facilities Engineering Command, Atlantic  
9324 Virginia Avenue  
Building Z-144  
Norfolk, Virginia 23511**

**March 2016**

**2015 OU2 GROUNDWATER INVESTIGATION  
RE114D1, RE114D2, RE114D3 (VPB148)  
INSTALLATION REPORT**

**NWIRP BETHPAGE  
SITE 1 OU2  
BETHPAGE, NY**

Prepared for:



**Department of the Navy  
Naval Facilities Engineering Command, Atlantic  
9324 Virginia Avenue  
Building Z-144  
Norfolk, Virginia 23511**

Prepared by:



**Resolution Consultants  
*A Joint Venture of AECOM & EnSafe*  
1500 Wells Fargo Building  
440 Monticello Avenue  
Norfolk, Virginia 23510**

**Contract Number: N62470-11-D-8013  
CTO WE15**

**March 2016**

A handwritten signature in black ink that reads "Brian Caldwell".

---

**Brian Caldwell  
Contract Task Order Manager**

## Table of Contents

LIST OF ACRONYMS AND ABBREVIATIONS.....	iii
1.0 PROJECT BACKGROUND .....	1
1.1 Scope and Objectives .....	1
1.2 Site History .....	1
1.3 Geology and Hydrogeology .....	2
2.0 FIELD PROGRAM.....	4
2.1 Drilling and Well Construction .....	4
2.2 Well Development .....	4
2.3 Sampling .....	5
2.4 Decontamination and Investigation Derived Waste (IDW) .....	5
2.5 Surveying .....	6
3.0 REFERENCES .....	8

### Tables

Table 1	Monitoring Well Construction Summary
Table 2	Monitoring Well Development Summary
Table 3	Analytical Data Summary
Table 4	Stabilized Field Parameters

### Figures

Figure 1	General Location Map
Figure 2	RE114D1, RE114D2, and RE114D3 Location Map

## **Appendices**

### Appendix A – RE114D1, RE114D2, RE114D3

Section 1 Boring Logs

Section 2 Monitoring Well Construction Logs

Section 3 Groundwater Sample Log Sheets

Section 4 Analytical Data Validation

Section 5 Survey

---

## List of Acronyms and Abbreviations

AOC	Area of Concern
bgs	below ground surface
COR	Continuously Operating Reference
EPA	Environmental Protection Agency, United States
ESS	Environmental Sequence Stratigraphy
ft	feet
GOCO	Government-Owned Contractor-Operated
GPS	Global Positioning System
IDW	Investigation Derived Waste
IR	Installation Restoration
Katahdin	Katahdin Analytical Services
NAD	North American Datum
NAVD	North American Vertical Datum
NAVFAC	Naval Facilities Engineering Command
NG	Northrop Grumman
NTU	nephelometric turbidity units
NWIRP	Naval Weapons Industrial Reserve Plant
NYS	New York State
NYSDEC	New York State Department of Environmental Conservation
OU	Operable Unit
PCBs	Polychlorinated Biphenyls
POTW	Publicly Owned Treatment Works
PPE	Personal Protective Equipment
PVC	Polyvinylchloride
SAP	Sampling and Analysis Plan
SVOC	Semivolatile Organic Compounds
TCE	Trichloroethene
TCL	Target Compound List
TCLP	Toxicity Characteristic Leaching Procedure
TOC	Total Organic Carbon
UFP	United Federal Programs
US	United States
VOC	Volatile Organic Compounds
VPB	Vertical Profile Boring

---

## **1.0 PROJECT BACKGROUND**

Resolution Consultants has prepared this Data Summary Report for the Naval Facilities Engineering Command (NAVFAC), Mid-Atlantic under task order WE15 Contract N62470-11-D-8013. This report describes the installation of three monitoring wells and one initial quarterly groundwater monitoring event (specifically at the Vertical Profile Boring [VPB] 148 location) in 2015 for the Naval Weapons Industrial Reserve Plant (NWIRP) Bethpage Operable Unit (OU) 2 Site 1 offsite plume. NWIRP Bethpage is located in east-central Nassau County, Long Island, New York, approximately 30 miles east of New York City (Figure 1).

### **1.1 Scope and Objectives**

This report provides information on the installation of three wells (RE114D1, RE114D2 and RE114D3) associated with the VPB148 location. The purpose of this investigation was to ascertain contaminant levels and depths, and the western extent of the offsite plume area south of Hempstead Turnpike and west of Hicksville Road. The locations of RE114D1, RE114D2 and RE114D3, VPBs and monitoring well locations are shown in Figure 2.

The field investigation included completing three monitoring wells, well development, soil/groundwater analysis, groundwater grab samples, and surveying. Field tasks were conducted in 2015 in accordance with the *United Federal Programs Sampling and Analysis Plan (UFP SAP)*, Bethpage, New York (Resolution, 2013a). In addition, the work adhered to the following UFP SAP Addendums: *Groundwater Sampling Using Low Stress (Low Flow) Purging and Sampling Protocol* (Resolution Consultants, 2013b) and *Installation of Vertical Profile Borings and Monitoring Wells* (Resolution Consultants, 2013c).

Documentation of these activities is included in Appendix A of this report.

### **1.2 Site History**

NWIRP Bethpage is in the Hamlet of Bethpage, Town of Oyster Bay, New York. Since its inception in 1941, the plant's primary mission was the research, prototyping, testing, design, engineering, fabrication, and primary assembly of military aircraft. The facilities at NWIRP included four plants used for assembly and prototype testing, a group of quality control laboratories, two warehouse complexes (north and south), a salvage storage area, water recharge basins, the Industrial Wastewater Treatment Plant, and several smaller support buildings.

The Navy's property originally totaled 109.5 acres and was formerly a Government-Owned Contractor-Operated (GOCO) facility that was operated by Northrop Grumman (NG) until September 1998. Prior to 2002, the NWIRP property was bordered on the north, west, and south by current or former NG facilities, and on the east by a residential neighborhood. By March 2008, approximately 100 acres of NWIRP property were transferred to Nassau County in three separate actions. The remaining 9 acres and access easements were retained by the Navy to continue remedial efforts at Installation Restoration (IR) Site 1 – Former Drum Marshalling Area and Site 4 – Former Underground Storage Tanks (Area of Concern [AOC] 22). A parcel of land connecting the two sites was also retained. Currently, the 9-acre parcel of NWIRP is bordered on the east by the residential neighborhood and on the north, south, and west by Steel Equities; however, a small portion is still owned by Nassau County. Access to the NWIRP is from South Oyster Bay Road.

### **1.3 Geology and Hydrogeology**

Overburden at the site consists of well over 1,000 feet (ft) of unconsolidated deposits overlying crystalline bedrock of the Hartland Formation. Overburden is divided into four geologic units: the upper Pleistocene deposits, the Magothy Formation, the clay member of the Raritan Formation ("Raritan Clay") and the Lloyd Sand member of the Raritan Formation ("Lloyd Sand") (Geraghty and Miller, 1994).

The upper Pleistocene ranges in thickness from approximately 50 to 100 ft and consists of till and outwash deposits of medium to coarse sand and gravel with lenses of fine sand, silt and clay (Smolensky and Feldman, 1990); these deposits form the Upper Glacial Aquifer. Directly underlying this unit is the Magothy Formation with a thickness of 650 to 900 ft and lower extent of 700 to 1000 ft below ground surface (bgs), as observed at the former NWIRP and extending southeast to areas south of Southern State Parkway. Locally at the RE114 locations, the bottom of the Magothy (top of the Raritan Clay) is encountered at approximately 913 feet bgs. The Magothy is characterized by fine to medium sands and silts interbedded with zones of clays, silty sands and sandy clays. Sand and gravel lenses are found in some areas between depths of 600 and 880 ft bgs; these deposits form the main producing zones of the Magothy Aquifer.

Investigations performed by the Navy since 2012 indicate that the bottom of the Magothy (top of the Raritan Clay) can extend to depths of 700 to greater than 1,000 ft bgs. The top of the Raritan Clay deepens to the south-southeast, as evidenced by clay depths of 1,000 ft bgs (or more) in borings installed offsite. The Raritan Clay Unit is of continental origin and consists of clay, silty clay, clayey silt, and fine silty sand. This member acts as a confining layer over the Lloyd Sand Unit. The Lloyd Sand Unit is also of continental origin, having been deposited in a large fresh water lacustrine

---

environment. The material consists of fine to coarse-grained sands, gravel, inter-bedded clay, and silty sand. These deposits form the Lloyd Aquifer.

The Upper Glacial Aquifer and the Magothy Aquifer comprise the aquifers of interest at the NWIRP. Regionally, these formations are generally considered to form a common, interconnected aquifer as the coarse nature of each unit near their contact allows for the unrestricted flow of groundwater between the formations.

The Magothy Aquifer is the major source of public water in Nassau County. The most productive water bearing zones are the discontinuous lenses of sand and gravel that occur within the siltier matrix. The major water-bearing zones are coarse sand and gravel lenses located in the lower portion of the Magothy. The Magothy Aquifer is commonly regarded to function overall as an unconfined aquifer at shallow depths and a confined aquifer at deeper depths. The drilling program at the NWIRP has revealed that clay zones beneath the facility are common, and above depths of approximately 500 feet bgs are laterally discontinuous. Preliminary cross section results from Environmental Sequence Stratigraphy (ESS) analysis suggests that below depths of approximately 500 feet bgs some clay layers may be persistent in a north-south direction; additional ESS cross section analyses are planned for the east-west direction.

Groundwater is encountered at a depth of approximately 50 ft bgs at the facility. Historically, because of pumping and recharge at the facility, groundwater depths have been measured to range from 40 to 60 ft bgs. The groundwater flow in the area is to the south-southeast.



---

## **2.0 FIELD PROGRAM**

Three monitoring wells (RE114 series wells) were installed in the vicinity of VPB148 between September and November 2015. Field investigation activities consisted of drilling, well installation, well development, sampling, soil/groundwater analysis, and surveying. Drilling during this investigation was performed by Delta Well and Pump Company of Ronkonkoma, New York. A description of these tasks is provided below.

### **2.1 Drilling and Well Construction**

Monitoring wells RE114D1, RE114D2 and RE114D3 were installed using mud rotary drilling techniques (Figure 2). Depths of monitoring wells RE114D1, RE114D2 and RE114D3 were 560 ft, 635 ft and 725 ft respectively. Well construction details are summarized in Table 1. Boring logs with lithologic descriptions of the well screen interval are included in the Appendix A. *2014 OU2 Groundwater Investigation VPB148* (Resolution Consultants, 2014) documents the installation of this VPB including detailed lithologic descriptions, continuous gamma plot and multiple VOC sample results over the entire boring length.

Prior to installing each monitoring well, the results of the groundwater samples, the geophysical logs, lithology and field data from the vertical profile borings were analyzed. Screen intervals were determined based on this analysis: intervals with the highest VOC concentrations as measured in the hydropunch samples, and coincident intervals with the highest apparent permeability based on the gamma logs. During the monitoring well installation, split spoon samples were collected every 5 ft in the screen interval. One soil sample per monitoring well was analyzed for Total Organic Carbon (TOC) via United States (US) Environmental Protection Agency (EPA) series SW-846 method 9060A by Katahdin Analytical Services (Katahdin). Data validation of TOC data was performed by Resolution Consultants. Data validation packages and analytical data tables are included in Appendix A.

Wells were constructed of 4-inch diameter, Schedule 80, National Sanitation Foundation-approved polyvinylchloride (PVC) riser pipe and .010-slot well screen. Wells were completed at the surface with a 12-inch diameter steel curb box. Well risers were set below grade and fit with lockable J plugs. Detailed monitoring well construction diagrams are included in Appendix A.

### **2.2 Well Development**

Following installation, all monitoring wells were developed to evacuate silts and other fine-grained materials and to establish the filter pack to promote a hydraulic connection between the well and

the surrounding aquifer. Well development was not initiated until at least 24 hours after well installation.

Monitoring well screens were developed using a combination of air lifting, manual surging, and pumping with a submersible pump. Turbidity was monitored during development to determine stabilization. In compliance with New York State Department of Environmental Conservation (NYSDEC) policy, wells were developed until turbidity was less than 50 nephelometric turbidity units (NTUs) if possible. Table 2 summarizes total pumped volume from air and pump development and final turbidity. Well development logs are included in Appendix A.

### **2.3 Sampling**

Following development, wells were allowed to stabilize for at least 2 weeks prior to groundwater sampling in accordance with low flow sampling procedures. Wells were purged using a bladder pump with a drop tube intake placed at the approximate midpoint of the screened interval. The following water quality parameters were continuously measured: water temperature, pH, conductivity, oxidation-reduction potential, dissolved oxygen and turbidity. Groundwater analytical samples were collected when water quality parameters stabilized. Samples were analyzed for VOCs via method 8260B and 1,4-dioxane via Method 8270C by Katahdin. All development and purge water was managed as investigation derived waste (IDW). Groundwater sample logs and data validation packages are included in Appendix A.

Monitoring wells RE114D1, RE114D2 and RE114D3 are sampled quarterly as part of the Navy's ongoing Environmental Restoration Program. Resolution Consultants sampled these three wells during the December 2015 quarterly monitoring event. Analytical results and stabilized field parameters for these data are summarized in Table 3 and 4, respectively. Data validation is documented in Appendix A.

### **2.4 Decontamination and Investigation Derived Waste (IDW)**

Resolution Consultants utilized dedicated and disposable sampling equipment when possible to avoid the potential for cross-contamination of samples. The sampling equipment included dedicated plastic scoops, disposable Teflon or polyethylene tubing, disposable gloves, and laboratory supplied sample bottles. Hand held equipment and split spoons were decontaminated using Liquinox and water wash, a potable water rinse, followed by a distilled water rinse. Water was collected in 5-gallon pails or 55-gallon drums. Non dedicated sampling equipment was decontaminated as outlined in the UFP SAP Addendum - *Groundwater Sampling Using Low Stress (Low Flow) Purging and Sampling Protocol* (Resolution Consultants, 2013b).

As part of the IDW management practices and in accordance with the SAP, the investigation waste (consisting of soil cuttings, drilling muds, IDW fluids, and personal protective equipment [PPE]) generated during the groundwater monitoring well installation and sampling was containerized and staged at NWIRP Bethpage.

IDW solids were containerized in roll offs. Representative samples from each roll off were submitted to Katahdin for analysis of:

- Target Compound List (TCL) VOCs
- TCL Semi-volatile Organic Compounds (SVOCs)
- Toxicity Characteristic Leaching Procedure (TCLP) Metals
- Polychlorinated Biphenyls (PCBs)
- Total petroleum hydrocarbons
- Corrosivity
- Ignitability
- Reactive Cyanide
- Reactive Sulfide
- Paint Filter

IDW fluid generated during well development and purging was containerized in frac tanks and stored at NWIRP Bethpage for characterization and ultimate disposal to the Publicly Owned Treatment Works (POTW), in accordance with the facilities existing discharge permit. A representative water sample was collected from each frac tank and submitted to Katahdin for analysis of VOCs via Method SW 624, pH via Method SW 9040B, PCBs via Method 8082 and Total Metals via Method SW 846. All analytical criteria were met for disposal of water.

## **2.5 Surveying**

A survey of the monitoring well locations was conducted at the end of fieldwork by C. T. Male, Inc., of Latham, NY, under the direct supervision of Resolution Consultants. The locations were tied into the existing base map developed for this investigation. The survey elevation is referenced to the North American Vertical Datum (NAVD) 1988 and has a vertical accuracy of 0.01 foot. Vertical control is based on observations of the Continuously Operating Reference (COR) Stations Queens and Central Islip. The horizontal location is referenced to the North American Datum (NAD) 1983 (2011) N.Y. Long Island Zone 3104 and has an accuracy of 0.1 foot. Local horizontal and vertical

control is based on Global Positioning System (GPS) observations using the NYSNet Real Time Network.

A table of survey data (latitude/longitude, northing/easting, elevations of ground, rim and PVC) and a survey map is included in Appendix A.

### **3.0 REFERENCES**

Geraghty and Miller, Inc., 1994. *Remedial Investigation Report, Grumman Aerospace Corporation, Bethpage, New York*. Revised September 1994.

Naval Facilities Engineering Command (NAVFAC), 2003. *Record of Decision Naval Weapons Industrial Reserve Plant Bethpage, New York, Operable Unit 2 – Groundwater*, NYS Registry: 1-30-003B. April 2003.

Resolution Consultants, 2013a. *United Federal Programs Sampling and Analysis Plan, Site OU-2 Offsite Trichloroethene (TCE) Groundwater Plume Investigation, Bethpage, New York*. April 2013.

Resolution Consultants, 2013b. UFP SAP Addendum, *Groundwater Sampling Using Low Stress (Low Flow) Purging and Sampling Protocol*. November 2013.

Resolution Consultants, 2013c. UFP SAP Addendum, *Installation of Vertical Profile Borings and Monitoring Wells*. December 2013.

Resolution Consultants, 2014. *2015 OU2 Groundwater Investigation VPB148, Bethpage, NY*. November 2014.

Smolensky, D., and Feldman, S., 1990. *Geohydrology of the Bethpage-Hicksville-Levittown Area, Long Island, New York, U.S. Geological Survey Water-Resourced Investigations Report 88-4135*, 25 pp.

## Tables

**TABLE 1**  
**MONITORING WELL CONSTRUCTION SUMMARY**  
**2015 OU2 GROUNDWATER INVESTIGATION**  
**NWIRP BETHPAGE, NY**

<b>MONITORING WELL</b>	<b>WELL COMPLETION DATE</b>	<b>GROUND ELEVATION (MSL)</b>	<b>PVC ELEVATION (INNER CASING) (MSL)</b>	<b>WELL DEPTH (ft bgs)</b>	<b>CASING DEPTH (ft bgs)</b>	<b>SCREEN INTERVAL (ft bgs)</b>	<b>SUMP DEPTH INTERVAL (ft bgs)</b>	<b>BORING DEPTH (ft bgs)</b>
RE114D1	10/22/2015	74.59	74.04	560	53	535 - 555	555 - 560	578
RE114D2	11/13/2015	74.48	73.96	635	53	610 - 630	630 - 635	648
RE114D3	10/5/2015	74.59	74.17	725	53	700 - 720	720 - 725	740

MSL - mean sea level

ft bgs - feet below ground surface

**TABLE 2**  
**MONITORING WELL DEVELOPMENT SUMMARY**  
**2015 OU2 GROUNDWATER INVESTIGATION**  
**NWIRP BETHPAGE, NY**

MONITORING WELL	AIR DEVELOPMENT		PUMP DEVELOPMENT			APPROX. TOTAL DEVELOPMENT VOLUME (GAL)	FINAL TURBIDITY (NTUs)
	DATE	APPROX. VOLUME (GAL)	DATE	FINAL PUMP DEPTH (FT BGS)	APPROX. VOLUME (GAL)		
RE114D1	11/19/2015	4,000	11/24/2015-11/25/2015	535-555	12,000	16,000	23.1
RE114D2	11/22/2015	4,000	12/1/2015	610-630	4,000	8,000	6.16
RE114D3	11/23/2015	3,000	11/30/2015	700-720	4,000	7,000	0.02

GAL - gallon

FT BGS - feet below ground surface

NTUs - Nephelometric Turbidity Units



**TABLE 3. ANALYTICAL DATA SUMMARY**  
**2015 OU2 GROUNDWATER INVESTIGATION**  
**NWIRP BETHPAGE, NY**

Location	NYSDEC Groundwater Guidance or Standard Value (Note 1)	RE114D1	RE114D2	RE114D3
Sample Date		12/21/2015	12/16/2015	12/16/2015
Sample ID		RE114D1-GW-122115	RE114D2-GW-121615	RE114D3-GW-121615
Sample type code		N	N	N
<b>VOC 8260C (ug/L)</b>				
1,1,1-TRICHLOROETHANE	5	<b>0.64 J</b>	< 0.50 U	< 0.50 U
1,1,2,2-TETRACHLOROETHANE	5	< 0.50 U	< 0.50 U	< 0.50 U
1,1,2-TRICHLORO-1,2,2-TRIFLUOROETHANE	5	<b>20 J</b>	<b>14</b>	<b>13</b>
1,1,2-TRICHLOROETHANE	1	<b>1.6 J</b>	< 0.50 U	< 0.50 U
1,1-DICHLOROETHANE	5	<b>1.5 J</b>	< 0.50 U	< 0.50 U
1,1-DICHLOROETHENE	5	<b>4.0 J</b>	< 0.50 U	<b>1.1</b>
1,2,4-TRICHLOROBENZENE	5	< 0.50 U	< 0.50 U	< 0.50 U
1,2-DIBROMO-3-CHLOROPROPANE	0.04	< <b>0.75 U</b>	< <b>0.75 U</b>	< <b>0.75 U</b>
1,2-DIBROMOETHANE	NL	< 0.50 U	< 0.50 U	< 0.50 U
1,2-DICHLOROBENZENE	3	< 0.50 U	< 0.50 U	< 0.50 U
1,2-DICHLOROETHANE	5	< 0.50 U	< 0.50 U	< 0.50 U
1,2-DICHLOROETHENE, TOTAL	5	<b>5.1 J</b>	<b>0.82 J</b>	<b>0.67 J</b>
1,2-DICHLOROPROPANE	1	< 0.50 U	< 0.50 U	< 0.50 U
1,3-DICHLOROBENZENE	3	< 0.50 U	< 0.50 U	< 0.50 U
1,4-DICHLOROBENZENE	3	< 0.50 U	< 0.50 U	< 0.50 U
1,4-DIOXANE (Method 8270D_SIM)	NL	<b>5.5</b>	<b>2.5</b>	<b>2.1</b>
2-BUTANONE	50	< 2.5 UJ	< 2.5 U	< 2.5 U
2-HEXANONE	50	< 2.5 UJ	< 2.5 U	< 2.5 U
4-METHYL-2-PENTANONE	NL	< 2.5 U	< 2.5 UJ	< 2.5 UJ
ACETONE	50	< 2.5 UJ	< 2.5 U	< 2.5 U
BENZENE	1	< 0.50 U	< 0.50 U	< 0.50 U
BROMODICHLOROMETHANE	50	< 0.50 U	< 0.50 U	< 0.50 U
BROMOFORM	50	< 0.50 U	< 0.50 U	< 0.50 U
BROMOMETHANE	5	< 1.0 U	< 1.0 UJ	< 1.0 UJ
CARBON DISULFIDE	60	< 0.50 U	< 0.50 U	< 0.50 U
CARBON TETRACHLORIDE	5	<b>2.5 J</b>	< 0.50 U	< 0.50 U
CHLOROBENZENE	5	< 0.50 U	< 0.50 U	< 0.50 U
CHLOROETHANE	5	< 1.0 UJ	< 1.0 U	< 1.0 U
CHLOROFORM	7	<b>2.9 J</b>	<b>0.40 J</b>	< 0.50 U
CHLOROMETHANE	5	< 1.0 U	< 1.0 U	< 1.0 U
CIS-1,2-DICHLOROETHENE	5	<b>5.1 J</b>	<b>0.82 J</b>	<b>0.67 J</b>
CIS-1,3-DICHLOROPROPENE	0.4	< <b>0.50 U</b>	< <b>0.50 U</b>	< <b>0.50 U</b>
CYCLOHEXANE	NL	< 0.50 U	< 0.50 U	< 0.50 U
DIBROMOCHLOROMETHANE	5	< 0.50 U	< 0.50 U	< 0.50 U
DICHLORODIFLUOROMETHANE	5	<b>1.0 J</b>	< 1.0 U	< 1.0 U
ETHYLBENZENE	5	< 0.50 U	< 0.50 U	< 0.50 U
ISOPROPYLBENZENE	5	< 0.50 U	< 0.50 U	< 0.50 U
M- AND P-XYLENE	NL	< 1.0 U	< 1.0 U	< 1.0 U
METHYL ACETATE	NL	< 0.75 U	< 0.75 U	< 0.75 U
METHYL CYCLOHEXANE	NL	< 0.50 U	< 0.50 U	< 0.50 U
METHYL TERT-BUTYL ETHER	10	< 0.50 U	< 0.50 U	< 0.50 U
METHYLENE CHLORIDE	5	< 2.5 U	< 2.5 U	< 2.5 U
O-XYLENE	NL	< 0.50 U	< 0.50 U	< 0.50 U
STYRENE	5	< 0.50 U	< 0.50 U	< 0.50 U
TETRACHLOROETHENE	5	< 0.50 U	< 0.50 UJ	< 0.50 UJ
TOLUENE	5	<b>0.30 J</b>	< 0.50 U	< 0.50 U
TRANS-1,2-DICHLOROETHENE	5	< 0.50 U	< 0.50 U	< 0.50 U
TRANS-1,3-DICHLOROPROPENE	0.4	< <b>0.50 UJ</b>	< <b>0.50 U</b>	< <b>0.50 U</b>
TRICHLOROETHENE	5	<b>370</b>	<b>70</b>	<b>43</b>
TRICHLOROFLUOROMETHANE	5	< 1.0 U	< 1.0 U	< 1.0 U
VINYL CHLORIDE	2	< 1.0 U	< 1.0 U	< 1.0 U
XYLENES, TOTAL	5	< 1.5 U	< 1.5 U	< 1.5 U

**Notes:**

1 New York State Department of Environmental Conservation Division of Water Technical and Operation Guidance series (6 NYCRR 700-706, Part 703.5 summarized in TOGS 1.1.1)

Ambient water quality standards and groundwater effluent limitations, class GA; NL = Not Listed

**Bold** = Detected; **Bold and Italics** = Not detected exceeds NYS Groundwater Standards or guidance value

Yellow highlighted values exceed Groundwater Standards or guidance value

Sample type codes: N - normal environmental sample, FD - field duplicate

U = Nondetected result. The analyte was analyzed for, but was not detected above the reported sample quantitation limit.

UJ = The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte.

J = The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.

M = the matrix spike or matrix spike duplicate did not meet recovery or precision requirements.

**TABLE 4**  
**STABILIZED FIELD PARAMETERS**  
**2015 OU2 GROUNDWATER INVESTIGATION**  
**NWIRP BETHPAGE, NY**

Well	Date	Temperature (°C)	pH	Specific Conductance (µS/cm)	DO (mg/L)	ORP (mV)	Turbidity (NTU)	Depth to water (ft bgs)	Flow rate (ml/min)
RE114D1	12/21/2015	13.85	5.82	0.073	2.62	148.7	21.00	31.64	500
RE114D2	12/16/2015	14.28	5.99	0.070	0.66	100.9	34.1	31.84	500
RE114D3	12/16/2015	14.35	5.45	0.033	5.78	245.2	1.42	32.26	500

°C - degrees Celsius

µS/cm - Microsiemens per Centimeter

mg/L - milligrams per liter



mV - Millivolts

NTU - Nephelometric Turbidity Unit

ft bgs - feet below ground surface


ml/min - milliliters per minute

## Figures



GENERAL LOCATION MAP  
 NWIRP BETHPAGE  
 BETHPAGE, NEW YORK

CONTRACT NUMBER N62470-11-D-8013		CTO NUMBER WE15	
APPROVED BY ---		DATE ---	
APPROVED BY ---		DATE ---	
FIGURE NO. 1			REV 0



RE114D1, RE114D2, AND RE114D3 LOCATION MAP  
 NAVAL WEAPONS INDUSTRIAL RESERVE PLANT  
 BETHPAGE, NEW YORK

CONTRACT NUMBER N62470-11-D8013	CTO NUMBER WE 15
APPROVED BY PS	DATE 2/15/2016
APPROVED BY	DATE
FIGURE NO. 2	REV 0

## **Appendix A**

### **RE114D1, RE114D2, RE114D3**

**Section 1**









**Boring Logs**



<b>Client:</b> Department of the Navy, Naval Facilities Engineering Command, Mid-Atlantic		<b>Logged By:</b> G. Hicks
<b>Location:</b> Elm Dr. North and Elbow Lane, Bethpage, NY		<b>Drilling Company:</b> Delta Well & Pump
<b>Project #:</b> 60266526	<b>Ground Elevation (msl):</b> 74.59	<b>Well Screen Interval (ft):</b> 535-555
<b>Start Date:</b> 10/7/2015	<b>Drilling Method:</b> Auger (0-50' bgs) Mud Rotary (>50' bgs)	<b>Water Level (ft):</b>
<b>Finish Date:</b> 10/22/2015	<b>Northing:</b> 201728.64 <b>Easting:</b> 1124289.94	<b>Total Depth (ft):</b> 578.0

DEPTH (ft)	PID (ppm)	Formation	USCS	GRAPHIC LOG	MATERIAL DESCRIPTION	Well Completion	Well Construction
0					0-538 ft bgs: See VPB148 for Descriptions		
50							10" Diameter Steel Casing
100							
150							
200							
250							Bentonite Grout
300							
350							
400							
450							4" Diameter Schedule 80 PVC Riser

<b>Client:</b> Department of the Navy, Naval Facilities Engineering Command, Mid-Atlantic		<b>Logged By:</b> G. Hicks
<b>Location:</b> Elm Dr. North and Elbow Lane, Bethpage, NY		<b>Drilling Company:</b> Delta Well & Pump
<b>Project #:</b> 60266526	<b>Ground Elevation (msl):</b> 74.59	<b>Well Screen Interval (ft):</b> 535-555
<b>Start Date:</b> 10/7/2015	<b>Drilling Method:</b> Auger (0-50' bgs) Mud Rotary (>50' bgs)	<b>Water Level (ft):</b>
<b>Finish Date:</b> 10/22/2015	<b>Northing:</b> 201728.64 <b>Easting:</b> 1124289.94	<b>Total Depth (ft):</b> 578.0

DEPTH (ft)	PID (ppm)	Formation	USCS	GRAPHIC LOG	MATERIAL DESCRIPTION	Well Completion	Well Construction
490					0-538 ft bgs: See VPB148 for Descriptions ( <i>continued</i> )		4" Diameter Schedule 80 PVC Riser ( <i>continued</i> )
492							
494							
496							
498							
500							
502							
504							
506							
508							
510							
512							
514							
516							
518							
520							
522							
524							
526							
528							
530							
532							
534							
536							
538	0.2		SM		Light yellowish brown (10YR 6/4) fine to medium subrounded Silty SAND, trace soft fat clay		4" Diameter Schedule 80 PVC, 10 Slot Well Screen (535-555 ft bgs)
540							
542							
544	0		SP		Pale brown (10YR 6/1) poorly graded medium subangular SAND, trace Silt		
546							Sump
548	0		SC		Grayish brown (10YR 5/2) fine to medium subangular medium stiff Clayey SAND, trace Silt		
550							
552							#1 Sand to Bottom
554	0		SP		Grayish brown (10YR 5/2) fine to medium subangular Silty SAND		
556							
558							
560							
562							
564							
566							
568							
570							
572							
574							
576							
578					End of boring at 578.0 ft. bgs.		

<b>Client:</b> Department of the Navy, Naval Facilities Engineering Command, Mid-Atlantic		<b>Logged By:</b> G. Hicks
<b>Location:</b> Elm Dr. North and Elbow Lane, Bethpage, NY		<b>Drilling Company:</b> Delta Well & Pump
<b>Project #:</b> 60266526	<b>Ground Elevation (msl):</b> 74.48	<b>Well Screen Interval (ft):</b> 610-630
<b>Start Date:</b> 11/27/2015	<b>Drilling Method:</b> Auger (0-50' bgs) Mud Rotary (>50' bgs)	<b>Water Level (ft):</b>
<b>Finish Date:</b> 11/13/2015	<b>Northing:</b> 201710.25 <b>Easting:</b> 1124365.4	<b>Total Depth (ft):</b> 648.0

DEPTH (ft)	PID (ppm)	Formation	USCS	GRAPHIC LOG	MATERIAL DESCRIPTION	Well Completion	Well Construction
0					0-613 ft bgs: See VPB148 for Descriptions		
50							10" Diameter Steel Casing
100							
150							
200							
250							Bentonite Grout
300							
350							
400							
450							
500							4" Diameter Schedule 80 PVC Riser
550							






<b>Client:</b> Department of the Navy, Naval Facilities Engineering Command, Mid-Atlantic		<b>Logged By:</b> G. Hicks
<b>Location:</b> Elm Dr. North and Elbow Lane, Bethpage, NY		<b>Drilling Company:</b> Delta Well & Pump
<b>Project #:</b> 60266526	<b>Ground Elevation (msl):</b> 74.48	<b>Well Screen Interval (ft):</b> 610-630
<b>Start Date:</b> 11/27/2015	<b>Drilling Method:</b> Auger (0-50' bgs) Mud Rotary (>50' bgs)	<b>Water Level (ft):</b>
<b>Finish Date:</b> 11/13/2015	<b>Northing:</b> 201710.25 <b>Easting:</b> 1124365.4	<b>Total Depth (ft):</b> 648.0

DEPTH (ft)	PID (ppm)	Formation	USCS	GRAPHIC LOG	MATERIAL DESCRIPTION	Well Completion	Well Construction
550					0-613 ft bgs: See VPB148 for Descriptions ( <i>continued</i> )		4" Diameter Schedule 80 PVC Riser ( <i>continued</i> )
552							
554							
556							
558							
560							
562							
564							
566							
568							
570							
572							
574							
576							
578							
580							
582							
584							
586							
588							
590							
592							
594							
596							
598							
600							
602							
604							
606							
608							
610							
612							
614	0		SP		Grayish brown (2.5Y 5/2) poorly graded medium subangular SAND, trace Iron, trace lignite		4" Diameter Schedule 80 PVC, 10 Slot Well Screen (610-630 ft bgs)
616							
618	0		SP		Brown (7.5YR 5/2) poorly graded medium subangular SAND		
620							
622							
624	0		SM		Olive gray (5Y 5/2) poorly graded medium subangular SAND, few Silt		
626							
628	0		SP		Olive gray (5Y 5/2) poorly graded medium subangular SAND, trace Iron		
630							
632							Sump
634							#1 Sand to Bottom
636							
638							
640							
642							
644							
646							
648					End of boring at 648.0 ft. bgs.		

<b>Client:</b> Department of the Navy, Naval Facilities Engineering Command, Mid-Atlantic			<b>Logged By:</b> M. Zobel		
<b>Location:</b> Elm Dr. North and Elbow Lane, Bethpage, NY			<b>Drilling Company:</b> Delta Well & Pump		
<b>Project #:</b> 60266526		<b>Ground Elevation (msl):</b> 74.59		<b>Well Screen Interval (ft):</b> 700-720	
<b>Start Date:</b> 9/22/2015		<b>Drilling Method:</b> Auger (0-50' bgs) Mud Rotary (>50' bgs)		<b>Water Level (ft):</b>	
<b>Finish Date:</b> 10/5/2015		<b>Northing:</b> 201719.48 <b>Easting:</b> 1124277.84		<b>Total Depth (ft):</b> 740.0	

DEPTH (ft)	PID (ppm)	Formation	USCS	GRAPHIC LOG	MATERIAL DESCRIPTION	Well Completion	Well Construction
0					0-703 ft bgs: See VPB148 for Descriptions		
50							10" Diameter Steel Casing
100							
150							
200							
250							Bentonite Grout
300							
350							
400							
450							
500							
550							4" Diameter Schedule 80 PVC Riser
600							
650							

<b>Client:</b> Department of the Navy, Naval Facilities Engineering Command, Mid-Atlantic		<b>Logged By:</b> M. Zobel
<b>Location:</b> Elm Dr. North and Elbow Lane, Bethpage, NY		<b>Drilling Company:</b> Delta Well & Pump
<b>Project #:</b> 60266526	<b>Ground Elevation (msl):</b> 74.59	<b>Well Screen Interval (ft):</b> 700-720
<b>Start Date:</b> 9/22/2015	<b>Drilling Method:</b> Auger (0-50' bgs) Mud Rotary (>50' bgs)	<b>Water Level (ft):</b>
<b>Finish Date:</b> 10/5/2015	<b>Northing:</b> 201719.48 <b>Easting:</b> 1124277.84	<b>Total Depth (ft):</b> 740.0

DEPTH (ft)	PID (ppm)	Formation	USCS	GRAPHIC LOG	MATERIAL DESCRIPTION	Well Completion	Well Construction
660					0-703 ft bgs: See VPB148 for Descriptions (continued)		4" Diameter Schedule 80 PVC Riser (continued)  #00 Filter Sand          #1 Filter Sand          4" Diameter Schedule 80 PVC, 10 Slot Well Screen (700-720 ft bgs)  Sump    #1 Sand to Bottom
662							
664							
666							
668							
670							
672							
674							
676							
678							
680							
682							
684							
686							
688							
690							
692							
694							
696							
698							
700							
702							
704	0		SP		White (Gley 1 8/N) poorly graded fine SAND, trace soft fat Clay		
706							
708	0		GP		White (Gley 1 8/N) fine Sandy poorly graded fine subangular GRAVEL, trace soft fat Clay		
710							
712	0		SW-SC		White (Gley 1 8/N) fine subangular Gravelly well graded fine to coarse subangular SAND with soft fat Clay		
714							
716	0		GW		White (Gley 1 8/N) fine to coarse subrounded Sandy fine subangular GRAVEL, trace soft fat Clay		
718							
720							
722							
724							
726							
728							
730							
732							
734							
736							
738							
740					End of boring at 740.0 ft. bgs.		


## **Section 2**

### **Monitoring Well Construction Logs**



Client: NAVFAC	Project Number: 60266526	<b>WELL ID: RE114D1</b>
Site Location: NWIRP BETHPAGE, NY		
Well Location: Elm Dr. North & Elbow Ln., Levittown, NY		Date Installed: 10/7/2015 - 10/22/2015
Method: MUD ROTARY		Inspector: G. HICKS
Coords: Northing: 201728.64 Easting: 1124289.94		Contractor: DELTA WELL & PUMP

### MONITORING WELL CONSTRUCTION DETAIL




Describe Measuring Point: \_\_\_\_\_  
 Ground Surface \_\_\_\_\_  
 Signature \_\_\_\_\_ Date \_\_\_\_\_





Client: NAVFAC	Project Number: 60266526	<b>WELL ID: RE114D2</b>
Site Location: NWIRP BETHPAGE, NY		
Well Location: Elm Dr. North & Elbow Ln., Levittown, NY		Date Installed: 10/27/2015 - 11/13/2015
Method: MUD ROTARY		Inspector: G. HICKS
Coords: Northing: 201710.25 Easting: 1124365.4		Contractor: DELTA WELL & PUMP

### MONITORING WELL CONSTRUCTION DETAIL



Approved: \_\_\_\_\_

Signature \_\_\_\_\_

Date \_\_\_\_\_


Describe Measuring Point:

Ground Surface



Client: NAVFAC	Project Number: 60266526	<b>WELL ID: RE114D3</b>
Site Location: NWIRP BETHPAGE, NY		
Well Location: Elm Dr. North & Elbow Ln., Levittown, NY		Date Installed: 9/22/2015 - 10/5/2015
Method: MUD ROTARY		Inspector: G. HICKS & M. ZOBEL
Coords: Northing: 201719.48 Easting: 1124277.84		Contractor: DELTA WELL & PUMP

### MONITORING WELL CONSTRUCTION DETAIL



Approved: \_\_\_\_\_

Describe Measuring Point:

Signature \_\_\_\_\_

Date \_\_\_\_\_

Ground Surface \_\_\_\_\_

### **Section 3**

## **Groundwater Sample Log Sheets**



Well ID: RE11401

# Low Flow Ground Water Sample Collection Record

Client: Navy NWIRP Bethpage Date: 12/21/15 Time: Start 1100 am/pm  
 Project No: 60266526 Finish 1330 am/pm  
 Site Location: Elm Dr. N  
 Weather Conds: partly sunny 50° Collector(s): \_\_\_\_\_

1. WATER LEVEL DATA: (measured from Top of Casing)
- a. Total Well Length 560 c. Length of Water Column \_\_\_\_\_ (a-b) Casing Diameter/Material 4-inch PVC  
 b. Water Table Depth 31.68 d. Calculated System Volume (see back) 13.1

2. WELL PURGE DATA
- a. Purge Method: Geotech bladder pump with drop tube assembly
- b. Acceptance Criteria defined (see workplan)
- Temperature ± 3%
  - pH ± 0.1 unit
  - Sp. Cond. ± 3%
  - Turbidity ± 10%
  - ORP ± 10mV
  - Drawdown < 0.3'
  - D.O. ± 10% (values >0.5 mg/L)
- Remove a minimum 1 screen volume
- c. Field Testing Equipment used:
- |            |            |                         |
|------------|------------|-------------------------|
| Make       | Model      | Serial Number           |
| <u>VSI</u> | <u>556</u> | <u>05H 1965/450231X</u> |

Time (24hr)	Volume Removed (Liters)	Temp. (°C)	pH	Spec. Cond. (mS/cm)	DO (mg/L)	ORP (mV)	Turbidity (NTU)	Flow Rate (ml/min)	Depth to water (ft)	Color/Odor
<u>11:30</u>		<u>1</u>								<u>ON</u>
<u>11:40</u>		<u>13.95</u>	<u>6.73</u>	<u>0.066</u>	<u>13.36</u>	<u>142.7</u>		<u>350</u>	<u>31.60</u>	<u>cloudy</u>
<u>11:45</u>		<u>13.44</u>	<u>6.13</u>	<u>0.068</u>	<u>9.00</u>	<u>142.7</u>			<u>31.60</u>	
<u>11:50</u>		<u>13.53</u>	<u>5.94</u>	<u>0.070</u>	<u>6.37</u>	<u>145.5</u>		<del><u>350</u></del>		
<u>11:55</u>		<u>13.56</u>	<u>5.92</u>	<u>0.070</u>	<u>6.36</u>	<u>143.4</u>				
<u>12:00</u>		<u>13.57</u>	<u>5.90</u>	<u>0.071</u>	<u>4.33</u>	<u>140.7</u>		<u>500</u>	<u>31.62</u>	

- d. Acceptance criteria pass/fail
- |                                     |                                     |                          |                          |
|-------------------------------------|-------------------------------------|--------------------------|--------------------------|
|                                     | Yes                                 | No                       | N/A                      |
| Has required volume been removed    | <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
| Has required turbidity been reached | <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
| Have parameters stabilized          | <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
- If no or N/A - Explain below.
- (continued on back)


3. SAMPLE COLLECTION: Method: Geotech bladder pump with drop tube assembly

Sample ID	Container Type	No. of Containers	Preservation	Analysis Req.	Time
<u>RE10401-GW-122115</u>	<u>40-mL vials</u>	<u>3</u>	<u>HCl</u>	<u>VOCs</u>	<u>1320</u>
	<u>1-L amber</u>	<u>2</u>	<u>none</u>	<u>1,4-Dioxane</u>	

Comments: Bottom depth is way off, at least 40ft of bonded is out of the well. thing point is 10ft at the bottom  
\* Tubing is marked "TOP" \* Need to check tubing length and trim to the correct length.

Signature: Paul K... Date: 12/21/15

Purge Volume Calculation



Volume / Linear Ft. of Pipe		
ID (in)	Gallon	Liter
0.25	0.0025	0.0097
0.375	0.0057	0.0217
0.5	0.0102	0.0386
0.75	0.0229	0.0869
1	0.0408	0.1544
1.25	0.0637	0.2413
1.5	0.0918	0.3475
2	0.1632	0.6178
2.5	0.2550	0.9653
3	0.3672	1.3900
4	0.6528	2.4711
6	1.4688	5.5600

One screen volume  
(4-inch well)

15 ft = 37.1 L / 9.8 G  
20 ft = 49.4 L / 13.1 G  
25 ft = 61.8 L / 16.3 G

Well ID: RE 114D-1 21130

(continued from front)

Time (24 hr)	Volume Removed (Liters)	Temp (°C)	pH	Specific Cond. (mS/cm)	DO (mg/L)	ORP (mV)	Turbidity (NTU)	Flow Rate (ml/min)	Depth to water (ft)	Color/Odor
12:05		13.64	5.74	0.072	3.00	143.2		500	31.6	
12:10		13.64	5.72	0.072	2.92	143.8	160.4			
12:15	5 gal	13.88	5.75	0.073	2.75	138.8				
12:20		13.77	5.80	0.073	3.34	138.7	37.04		31.62	
12:25		13.84	5.83	0.073	4.00	137.0				
12:30		13.79	5.81	0.073	3.02	140.3	27.33		31.62	
12:35		13.76	5.73	0.073	2.99	138.3	28.42			
12:40		13.87	5.73	0.073	2.80	143.5				
12:45		13.90	5.73	0.073	2.61	146.3			31.64	
12:50	10 gal	13.81	5.80	0.073	2.46	147.5	21.60			
12:55		13.87	5.78	0.073	2.25	149.3				
13:00		13.93	5.79	0.073	3.98	149.1	21.07		31.64	
13:05		13.95	5.83	0.073	2.98	148.8	21.47	500		
13:10		13.86	5.83	0.073	2.77	147.9	22.08			
13:15	13 gal	13.85	5.82	0.073	2.62	148.7	21.00			
13:20										sample



RESOLUTION  
CONSULTANTS

Well ID: RE11402

# Low Flow Ground Water Sample Collection Record

Client: Navy NWIRP Bethpage Date: 12/16/15 Time: Start 1300 am/pm  
 Project No: 60266526 Finish 1630 am/pm  
 Site Location: Elm Place  
 Weather Conds: Sunny 60° Collector(s): \_\_\_\_\_

### 1. WATER LEVEL DATA: (measured from Top of Casing)

a. Total Well Length 635 c. Length of Water Column \_\_\_\_\_ (a-b) Casing Diameter/Material  
4-inch PVC  
 b. Water Table Depth \_\_\_\_\_ d. Calculated System Volume (see back) \_\_\_\_\_

### 2. WELL PURGE DATA

a. Purge Method: Geotech bladder pump with drop tube assembly

#### b. Acceptance Criteria defined (see workplan)

- Temperature  $\pm 3\%$
  - pH  $\pm 0.1$  unit
  - Sp. Cond.  $\pm 3\%$
  - Turbidity  $\pm 10\%$
  - ORP  $\pm 10mV$
  - Drawdown  $< 0.3'$
  - D.O.  $\pm 10\%$  (values  $> 0.5$  mg/L)
- Remove a minimum 1 screen volume

c. Field Testing Equipment used: \_\_\_\_\_ Make \_\_\_\_\_ Model \_\_\_\_\_ Serial Number \_\_\_\_\_

Time (24hr)	Volume		Temp. (°C)	pH	Spec.			Turbidity (NTU)	Flow Rate (ml/min)	Depth to water (ft)	Color/Odor
	Removed (Liters)				Cond. (mS/cm)	DO (mg/L)	ORP (mV)				
1345											OK
1355											blow out
1435								400			reset bladder
1445	3 gal		14.30	5.85	0.069	3.29	114.6	44	500	32.03	
1450											
1455			14.13	6.08	0.072	1.94	107.3		475	42.6	

d. Acceptance criteria pass/fail

	Yes	No	N/A	(continued on back)
Has required volume been removed	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
Has required turbidity been reached	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
Have parameters stabilized	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	

If no or N/A - Explain below.

### 3. SAMPLE COLLECTION:


Method: Geotech bladder pump with drop tube assembly

Sample ID	Container Type	No. of Containers	Preservation	Analysis Req.	Time
<u>RE11402-GW-121615</u>	<u>40-mL vials</u>	<u>3</u>	<u>HCl</u>	<u>VOCs</u>	<u>1615</u>
	<u>1-L amber</u>	<u>2</u>	<u>none</u>	<u>1,4-Dioxane</u>	

Comments: 1355 p. 11 pump reset bladder

Signature \_\_\_\_\_ Date \_\_\_\_\_

Purge Volume Calculation



Volume / Linear Ft. of Pipe		
ID (in)	Gallon	Liter
0.25	0.0025	0.0097
0.375	0.0057	0.0217
0.5	0.0102	0.0386
0.75	0.0229	0.0869
1	0.0408	0.1544
1.25	0.0637	0.2413
1.5	0.0918	0.3475
2	0.1632	0.6178
2.5	0.2550	0.9653
3	0.3672	1.3900
4	0.6528	2.4711
6	1.4688	5.5600

One screen volume  
(4-inch well)  
  
15 ft = 37.1 L / 9.8 G  
20 ft = 49.4 L / 13.1 G  
25 ft = 61.8 L / 16.3 G

Well ID:

(continued from front)

Time (24 hr)	Volume Removed (Liters)	Temp (°C)	pH	Specific Cond. (mS/cm)	DO (mg/L)	ORP (mV)	Turbidity (NTU)	Flow Rate (ml/min)	Depth to water (ft)	Color/Odor
15:00	-	14.34	5.99	0.072	1.59	111.4		475	32.00	
15:05		14.36	5.98	0.071	1.58	110.4	36.8	475	31.97	
15:10		14.36	5.89	0.073	1.11	115.0	35.5	475	31.96	
15:15		14.34	5.89	0.072	0.93	113.8	32.5	500		
15:20		14.33	6.04	0.072	1.00	101.9	35.6	500	31.98	
15:25		14.35	5.97	0.071	0.95	107.0	34.7	500	31.97	
15:30		14.33	6.00	0.072	0.82	105.1		475	31.98	
15:35		14.34	6.01	0.071	0.86	104.9	33.4			
15:40		14.32	6.00	0.071	0.75	104.6	31.0	500	31.97	
15:45	10 Gal	14.30	5.97	0.070	0.66	103.8	30.5	500	31.91	
15:50		14.30	5.98	0.070	0.70	102.7				
15:55		14.32	5.99	0.071	0.63	101.7	31.3			
16:00	12 gal	14.32	5.99	0.071	0.63	101.4	33.4		31.84	
16:05	13 gal	14.28	5.99	0.070	0.63	100.9	35.7			
16:10		14.28	5.99	0.070	0.66	100.9	34.1			
16:15										sample



Well ID: RE11403

# Low Flow Ground Water Sample Collection Record

Client: Navy NWIRP Bethpage Date: 12/16/15 Time: Start 1300 am/pm  
 Project No: 60266526 Finish 1830 am/pm  
 Site Location: \_\_\_\_\_  
 Weather Conds: Sunny 60° Collector(s): \_\_\_\_\_

**1. WATER LEVEL DATA: (measured from Top of Casing)**

a. Total Well Length 725 c. Length of Water Column \_\_\_\_\_ (a-b) Casing Diameter/Material 4-inch PVC  
 b. Water Table Depth 32.35 d. Calculated System Volume (see back) \_\_\_\_\_

**2. WELL PURGE DATA**

a. Purge Method: Geotech bladder pump with drop tube assembly

b. Acceptance Criteria defined (see workplan)

- Temperature ± 3%
- pH ± 0.1 unit
- Sp. Cond. ± 3%
- Turbidity ± 10%
- ORP ± 10mV
- Drawdown < 0.3'
- D.O. ± 10% (values >0.5 mg/L)
- Remove a minimum 1 screen volume

c. Field Testing Equipment used:

Make	Model	Serial Number
<u>YSI</u>	<u>556 MPS</u>	<u>05G1942 AC</u>

Time (24hr)	Volume Removed (Liters)	Temp. (°C)	pH	Spec. Cond. (mS/cm)	DO (mg/L)	ORP (mV)	Turbidity (NTU)	Flow Rate (ml/min)	Depth to water (ft)	Color/Odor
<u>14:20</u>	<u>-</u>	<u>14.41</u>	<u>10.00</u>	<u>0.073</u>	<u>9.65</u>	<u>176.9</u>	<u>-</u>	<u>500</u>	<u>32.27</u>	
<u>14:40</u>	<u>-</u>	<u>14.39</u>	<u>5.93</u>	<u>0.042</u>	<u>5.08</u>	<u>218.0</u>	<u>29.3</u>	<u>500</u>	<u>-</u>	<u>Clear/odor</u>
<u>14:45</u>	<u>-</u>	<u>14.40</u>	<u>5.63</u>	<u>0.035</u>	<u>5.61</u>	<u>224.3</u>	<u>-</u>	<u>500</u>	<u>32.25</u>	
<u>14:50</u>	<u>-</u>	<u>14.37</u>	<u>5.63</u>	<u>0.035</u>	<u>5.62</u>	<u>224.9</u>	<u>-</u>	<u>500</u>	<u>32.26</u>	
<u>14:55</u>	<u>48 Gal</u>	<u>14.37</u>	<u>5.60</u>	<u>0.035</u>	<u>5.68</u>	<u>228.5</u>	<u>2.75</u>	<u>500</u>	<u>32.24</u>	
<u>15:05</u>	<u>-</u>	<u>14.39</u>	<u>5.52</u>	<u>0.034</u>	<u>5.72</u>	<u>233.4</u>	<u>1.82</u>	<u>500</u>	<u>32.27</u>	

d. Acceptance criteria pass/fail (continued on back)

	Yes	No	N/A
Has required volume been removed	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Has required turbidity been reached	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Have parameters stabilized	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

If no or N/A - Explain below.

**3. SAMPLE COLLECTION:**

Method: Geotech bladder pump with drop tube assembly

Sample ID	Container Type	No. of Containers	Preservation	Analysis Req.	Time
<u>RE11403-GW-121615</u>	<u>40-mL vials</u>	<u>3</u>	<u>HCl</u>	<u>VOCs</u>	<u>1800</u>
<u>RE11403-GW-121615</u>	<u>1-L amber</u>	<u>2</u>	<u>none</u>	<u>1,4-Dioxane</u>	


Comments \_\_\_\_\_

Signature \_\_\_\_\_

Date \_\_\_\_\_



Purge Volume Calculation



Volume / Linear Ft. of Pipe		
ID (in)	Gallon	Liter
0.25	0.0025	0.0097
0.375	0.0057	0.0217
0.5	0.0102	0.0386
0.75	0.0229	0.0869
1	0.0408	0.1544
1.25	0.0637	0.2413
1.5	0.0918	0.3475
2	0.1632	0.6178
2.5	0.2550	0.9653
3	0.3672	1.3900
4	0.6528	2.4711
6	1.4688	5.5600

One screen volume  
(4-inch well)

15 ft = 37.1 L / 9.8 G  
20 ft = 49.4 L / 13.1 G  
25 ft = 61.8 L / 16.3 G

Well ID:

(continued from front)

Time (24 hr)	Volume Removed (Liters)	Temp (°C)	pH	Specific Cond. (mS/cm)	DO (mg/L)	ORP (mV)	Turbidity (NTU)	Flow Rate (ml/min)	Depth to water (ft)	Color/Odor	
15:10	-	14.41	5.53	0.034	5.71	232.9		500	32.27		
15:15		14.40	5.57	0.033	5.74	236.3	1.56	500	32.25		
15:20		14.41	5.50	0.034	5.74	236.1	1.32	500	32.26		
15:25		14.40	5.49	0.034	5.76	238.4	1.47	500			
15:30	10 Gal	14.37	5.48	0.033	5.78	237.2		500	32.27		
15:35		14.38	5.47	0.053	5.78	240.2	1.53	500	32.26		
15:40		14.37	5.46	0.033	5.78	241.6	1.48				
15:45		14.36	5.45	0.033	5.78	241.0		500	32.25		
15:50	13.5 Gal	14.35	5.45	0.033	5.78	245.2	1.42	500	32.26		
15:55											
16:00		Test Sample									
16:05											
16:10											
16:15											
16:20											
16:30											

## **Section 4**

### **Analytical Data Validation**

[Attachment D of the Data Validation report for the December 2015 Quarterly Sampling included here contains only results tables for RE114D1, RE114D2 and RE114D3; for the December 2015 Quarterly Sampling Data Validation report with complete Attachment D with all well results tables see *December 2015 Groundwater Sampling Data Summary Report, Bethpage, NY*, Resolution Consultants, 2016.]



**DATA VALIDATION REPORT**

Project:	Regional Groundwater Investigation — NWIRP Bethpage	
Laboratory:	Katahdin Analytical	
Sample Delivery Group:	BETHPAGE-3	
Analyses/Method:	Volatile Organic Compounds by U.S. EPA SW-846 Method 8260C 1,4-Dioxane by U.S. EPA SW-846 Method 8270D via Selective Ion Monitoring (SIM)	
Validation Level:	3	
Project Number:	0888812477.SA.DV	
Prepared by:	Dana Miller/Resolution Consultants	Completed on: 02/5/2016
Reviewed by:	Tina Clemmey/Resolution Consultants	File Name: BETHPAGE 3_8260C_8270D

**SUMMARY**

This report summarizes data review findings for samples listed below, collected by Resolution Consultants from the Regional Groundwater Investigation — NWIRP Bethpage Site on 14 to 29 December 2015 in accordance with the following Sampling and Analysis Plans:

- *Sampling and Analysis Plan, Bethpage, New York.* (Resolution Consultants, April 2013).
- *UFP SAP Addendum, Installation of Vertical Profile Borings and Monitoring Wells, Operable Unit 2, NWIRP Bethpage, New York.* (Resolution Consultants, November 2013).
- *UFP SAP Addendum, Inclusion of Additional Target Analytes for Volatile Organics Analyses, NWIRP Bethpage OU2, Bethpage, New York.* (Resolution Consultants, August 2014).

Sample ID	Matrix/Sample Type	Analysis
FIELD1-FB-121615	Field Blank	8260C/8270D_SIM
RE103D1-GW-121415	Groundwater	8260C/8270D_SIM
RE103D2-GW-121415	Groundwater	8260C/8270D_SIM
RE103D3-GW-121415	Groundwater	8260C/8270D_SIM
RE104D1-GW-121515	Groundwater	8260C/8270D_SIM
RE104D2-GW-121515	Groundwater	8260C/8270D_SIM
DUPLICATE1-GW-121515	Field Duplicate of RE104D2-GW-121515	8260C/8270D_SIM
RE104D3-GW-121515	Groundwater	8260C/8270D_SIM
RE105D1-GW-121715	Groundwater	8260C/8270D_SIM
RE105D2-GW-121715	Groundwater	8260C/8270D_SIM
RE107D1-GW-121815	Groundwater	8260C/8270D_SIM

Sample ID	Matrix/Sample Type	Analysis
RE107D2-GW-121815	Groundwater	8260C/8270D_SIM
RE107D3-GW-122915	Groundwater	8260C/8270D_SIM
RE108D1-GW-122215	Groundwater	8260C/8270D_SIM
RE108D2-GW-122215	Groundwater	8260C/8270D_SIM
RE114D1-GW-122115	Groundwater	8260C/8270D_SIM
RE114D2-GW-121615	Groundwater	8260C/8270D_SIM
RE114D3-GW-121615	Groundwater	8260C/8270D_SIM
RE120D1-GW-121815	Groundwater	8260C/8270D_SIM
RE120D2-GW-122915	Groundwater	8260C/8270D_SIM
RE120D3-GW-122915	Groundwater	8260C/8270D_SIM
RE121D1-GW-122115	Groundwater	8260C/8270D_SIM
RE121D2-GW-122115	Groundwater	8260C/8270D_SIM
RE122D1-GW-121515	Groundwater	8260C/8270D_SIM
RE122D2-GW-121515	Groundwater	8260C/8270D_SIM
RE122D3-GW-121515	Groundwater	8260C/8270D_SIM
RE123D1-GW-122115	Groundwater	8260C/8270D_SIM
RE123D2-GW-122115	Groundwater	8260C/8270D_SIM
RE123D3-GW-122115	Groundwater	8260C/8270D_SIM
TRIP BLANK 121415	Trip Blank	8260C
TRIP BLANK 121615	Trip Blank	8260C
TRIP BLANK-121815	Trip Blank	8260C
TRIP BLANK-122915	Trip Blank	8260C
TT101D1-GW-121715	Groundwater	8260C/8270D_SIM
TT101D2-GW-122115	Groundwater	8260C/8270D_SIM
DUPLICATE-GW-122115	Field Duplicate of TT101D2-GW-122115	8260C/8270D_SIM
TT101D-GW-121715	Groundwater	8260C/8270D_SIM

Data validation activities were conducted using the following guidance documents: *Test Methods for Evaluating Solid Waste, Physical/Chemical Methods SW-846, specifically Method 8260C, Volatile Organic Compounds by Gas Chromatography/Mass Spectrometry* (United States Environmental Protection Agency [U.S. EPA] 2006), *SW-846 Method 8270D, Semivolatile Organic Compounds by Gas Chromatograph/Mass Spectrometry* (U.S. EPA 2007), *U.S. Environmental Protection Agency Contract Laboratory Program National Functional Guidelines for Superfund Organic Methods Data Review* (U.S. EPA, June 2008), and *Department of Defense Quality Systems Manual for Environmental Laboratories, Version 4.2* (October 2010). In the absence of method-specific information, laboratory quality control (QC) limits, project-specific requirements, and/or professional judgment were used as appropriate.

## **REVIEW ELEMENTS**

The data were evaluated based on the following parameters (where applicable to the method):

- ✓ Data completeness (chain-of-custody)/sample integrity
- ✓ Holding times and sample preservation
- ✓ Gas chromatography/Mass spectrometer performance checks
- ✗ Initial calibration verification (ICV)/continuing calibration verification (CCV)
- ✓ Laboratory blanks/trip blanks/field blanks
- ✗ Surrogate spike recoveries
- ✗ Matrix spike and/or matrix spike duplicate results
- ✓ Laboratory control sample/laboratory control sample duplicate results
- ✗ Field duplicates
- ✓ Internal standards
- ✓ Sample results/reporting issues

The symbol (✓) indicates that no validation qualifiers were applied based on this parameter. Acceptable data parameters for which all criteria were met and no qualification was performed and non-conformance or other issues that were noted during validation, but did not result in qualification of data are not discussed further. The symbol (✗) indicates that a QC non-conformance resulted in the qualification of data. Any QC non-conformance that resulted in the qualification of data is discussed below.

## **RESULTS**

### **Initial Calibration/Continuing Calibration Verification**

Calibration data were reviewed for conformance with the QC acceptance criteria to ensure that:

- The initial calibration percent relative standard deviation, correlation coefficient/coefficient of determination, and/or response factor method acceptance criteria were met
- The ICV standard percent recovery acceptance criteria were met
- The CCV method percent difference or percent drift and response factor acceptance criteria were met
- The retention time method acceptance criteria were met

Data qualification to the analytes associated with the specific initial calibration (ICAL) was as follows:

**ICAL Linearity Non-conformance:**

Criteria	Actions	
	Detected Results	Non-detected Results
%RSD >15% and quantitation based on mean response factor	J	UJ

**Notes:**

%RSD = Relative standard deviation  
 J = Estimated  
 UJ = Undetected and estimated

Data qualification to the analytes associated with the specific ICV was as follows:

**ICV Recovery Non-conformance:**

Criteria	Actions	
	Detected Results	Non-detected Results
Recovery >120%	J	UJ
Recovery < 80%	J	UJ

**Notes:**

J = Estimated  
 UJ = Undetected and estimated

Data qualification to the analytes associated with the specific CCV was as follows:

**CCV Linearity Non-conformance:**

Criteria	Actions	
	Detected Results	Non-detected Results
%Difference or %Drift > 20%	J	UJ

**Notes:**

J = Estimated  
 UJ = Undetected and estimated

ICAL, ICV and CCV non-conformances are summarized in Attachment A in Tables A-1, A-2, and A-3.

**Surrogate Spike Recoveries**

Surrogates provide information needed to assess the accuracy of analyses. Known amounts of surrogate compounds, or compounds which are not likely to be found in the actual samples, are added to each organic sample to check for accuracy. If surrogate percent recoveries (%Rs) are close

to the known concentrations, the reported target compound concentrations are assumed to be accurate. Data qualification on the basis of surrogate recovery was as follows:

**Surrogate Recovery Non-conformance Chart:**

Criteria	Action	
	Detected	Non-detected
% R > Upper Limit	J	No qualification
20% ≤ %R < Lower Limit	J	UJ
% R < 20%	J	Rejected

**Notes:**

- %R = Percent recovery
- J = Estimated
- UJ = Undetected and estimated

Surrogate recovery non-conformance is summarized in Attachment A in Table A-4.

**Matrix Spike/Matrix Spike Duplicate (MS/MSD) Results**

MS/MSDs are generated to provide information about the effect of each sample matrix on the sample preparation and the measurement methodology. MS/MSD percent recoveries (%Rs) assess the effect of the sample matrix on the accuracy of the analytical results and %Rs above the laboratory control limit could indicate a potential high result bias while %Rs below QC limits could indicate a potential low result bias. The relative percent differences (RPDs) between the MS and MSD results are evaluated to assess sample precision. The MS/MSD %Rs and RPDs were reviewed for conformance with the QC acceptance criteria. Data qualification to the analytes associated with the specific MS/MSD non-conformances were as follows:

**MS/MSD Non-conformances Chart:**

Criteria	Action	
	Detected Compounds	Non-detected Compounds
%R>Upper Limit	J	No qualification
20% ≤ %R < Lower Limit	J	UJ
%R <20%	J	Rejected

**Notes:**

- %R = Percent recovery
- RPD = Relative percent difference
- J = Estimated
- UJ = Undetected and estimated

MS/MSD non-conformances are summarized in Attachment A in Table A-5.

### Field Duplicate

Two field duplicate pairs were collected to assess precision: RE104D2-GW-121515/ DUPLICATE1-GW-121515 and TT101D2-GW-122115/DUPLICATE-GW-122115. Field duplicate RPDs were reviewed for conformance with the Resolution Consultants QC criteria of  $\leq 30\%$  for aqueous matrices and  $\leq 50\%$  for solid matrices. These criteria apply if both results were greater than two times the limit of quantitation (LOQ). Data qualification to the analytes associated with the specific field duplicate RPDs was as follows:

### Field Duplicate Non-conformances Chart:

Criteria	RPD	Action	
		Detected	Non-detected
Sample and duplicate are nondetect	Not calculable (NC)	No qualification	No qualification
Sample and duplicate results $\geq 2x$ LOQ	>30 (aqueous)	J	Not Applicable
	>50 (solids)		
If sample or duplicate result is $>2x$ LOQ and the other is not detected	NC	J	UJ
If sample or duplicate result is $<2x$ LOQ and the other is not detected	NC	No qualification	No qualification

**Notes:**

- LOQ = Limit of quantitation
- J = Estimated
- UJ = Undetected and estimated

Field duplicate non-conformances are summarized in Attachment A in Table A-6.

### Qualifications Actions

The data were reviewed independently from the laboratory to assess data quality. All compounds detected at concentrations less than the limit of quantitation but greater than the method detection limit were qualified by the laboratory as estimated (J). This "J" qualifier was retained during data validation. Any sample that was analyzed at a dilution because of high concentrations of target or non-target analytes was checked to confirm that the results and/or sample-specific limit of quantitation and limit of detections were adjusted accordingly by the laboratory. Trichloroethene in sample RE108D2-GW-121215 result value reported above the calibration range and was qualified estimated "J" because the value was off-scale.

No results were rejected; therefore, analytical completeness was calculated to be 100 percent. Data not qualified during data review are considered usable by the project. The remaining results qualified as estimated may be high or low, but the data are usable for their intended purpose,



according to U.S. EPA and Department of Defense guidelines. Final data review qualifiers used to describe results and how they should be interpreted by the end data user are provided in Attachment B and Attachment C. Attachment D provides final results after data review.

## **ATTACHMENTS**

Attachment A: Non-Conformance Summary Tables

Attachment B: Qualifier Codes and Explanations

Attachment C: Reason Codes and Explanations

Attachment D: Final Results after Data Review

**Attachment A**  
**Non-Conformance Summary Table**

Table A-1 Initial Calibration Non-Conformance					
Method	Analyte	%RSD	Limit	Associated Samples	Qualifier
8260C	CHLOROETHANE	17.80841	<15%	TI0330-1, -2, -5, -6, -11, -4, -7, -3DL, -10RA, -12, -13, -14, -17, -4DL, -6DL, and 7DL	Detects: J Non-detects: UJ
8260C	TETRACHLOROETHENE	15.13611	<15%	TI0428-4, -1, -3RA, -1DL, -2RA, and TI0330-17DL	Detects: J Non-detects: UJ

**Notes:**

%RSD = Relative standard deviation  
 UJ = Non-detect estimated value  
 J = Estimated value

**Table A-2  
Initial Calibration Verification Non-Conformance**

Method	Analyte	ICV ID	%R	Limit	Associated Samples	Qualifier
8260C	TETRACHLOROETHENE	P3840.D	150.8	80-120	TI0116-1, -2, -3, -4, -5, -6, -7, -8, -9, -11, -10RA, -2DL, -4DL, -9DL, -3DL, -11DL, TI0214-1, -4, -5, -6, -7, -9, -8, -10, 12, -8DL, and -7DL	Detects: J Non-detects: UJ
8260C	TRANS-1,3-DICHLOROPROPENE	C6396A.D	123.47	80-120	TI0330-1, -2, -5, -6, -11, -4, -7, -3DL, -10RA, -12, -13, -14, -17, -4DL, -6DL, and 7DL	Detects: J Non-detects: UJ
8260C	ACETONE	P4114A.D	72.62	80-120	TI0428-3RA, -1DL, -2RA, -4, -1, and TI0330-17DL	Detects: J Non-detects: UJ

**Notes:**

ICV ID = Initial calibration verification identification  
 ID = Identification  
 %R = Percent recovery  
 UJ = Non-detect estimated value  
 J = Estimated value

**Table A-3**  
**Continuing Calibration Verification Non-Conformance**

Lab ID /Calibration ID	Analyte	%D	%D Limit	Associated Samples	Qualifier
WG176285-4 / P3940.D	BROMOMETHANE	23.79988	+/- 20	TI0116-1, -2, -3, -4, -5, -6, -7, -8, -9, and -11	Detects: J Non-detects: UJ
WG176319-4 / P3964.D	BROMOMETHANE	24.57249	+/- 20	TI0116-10RA, TI0214-1, -4, -5, -6, -7, and -9	Detects: J Non-detects: UJ
WG176319-4 / P3964.D	4-METHYL-2-PENTANONE	20.68251	+/- 20	TI0116-10RA, TI0214-1, -4, -5, -6, -7, and -9	Detects: J Non-detects: UJ
WG176436-4 / P3989.D	BROMOMETHANE	28.03265	+/- 20	TI0214-8, -10, and -12	Detects: J Non-detects: UJ
WG176436-4 / P3989.D	CHLOROETHANE	27.72207	+/- 20	TI0214-8, -10, and -12	Detects: J Non-detects: UJ
WG176436-4 / P3989.D	4-METHYL-2-PENTANONE	21.50811	+/- 20	TI0214-8, -10, and -12	Detects: J Non-detects: UJ
WG176832-4 / P4138.D	ACETONE	-34.27373	+/- 20	TI0428-4, and -1	Detects: J Non-detects: UJ
WG176788-4 / C6418.D	CHLOROMETHANE	-20.54679	+/- 20	TI0330-10RA, -12, -13, -14, -17, -4DL, -6DL, -and -7DL	Detects: J Non-detects: UJ
WG176788-4 / C6418.D	ACETONE	-27.76004	+/- 20	TI0330-10RA, -12, -13, -14, -17, -4DL, -6DL, -and -7DL	Detects: J Non-detects: UJ
WG176788-4 / C6418.D	TETRACHLOROETHENE	-21.38037	+/- 20	TI0330-10RA, -12, -13, -14, -17, -4DL, -6DL, -and -7DL	Detects: J Non-detects: UJ
WG176788-4 / C6418.D	METHYL ACETATE	-25.56044	+/- 20	TI0330-10RA, -12, -13, -14, -17, -4DL, -6DL, -and -7DL	Detects: J Non-detects: UJ
WG176732-4 / C6394.D	ACETONE	57.49765	+/- 20	TI0330-1, -2, -5, -6, -11, -4, -7, and -3DL	Detects: J Non-detects: UJ
WG176732-4 / C6394.D	2-BUTANONE	25.58556	+/- 20	TI0330-1, -2, -5, -6, -11, -4, -7, and -3DL	Detects: J Non-detects: UJ
WG176732-4 / C6394.D	2-HEXANONE	22.15201	+/- 20	TI0330-1, -2, -5, -6, -11, -4, -7, and -3DL	Detects: J Non-detects: UJ

**Notes:**

ID = Identification  
 %D = Percent difference  
 UJ = Non-detect estimated value  
 J = Detected estimated value

**Table A-4  
Surrogate Non-Conformance**

<b>Method</b>	<b>Surrogate</b>	<b>%R</b>	<b>Limits</b>	<b>Associated Sample</b>	<b>Qualifier</b>
8260C	1,2-DICHLOROETHANE-D4	121	70-120	RE114D1-GW-122115	Detects: J
8260C	DIBROMOFLUOROMETHANE	117	85-115	RE114D1-GW-122115	Detects: J
8260C	DIBROMOFLUOROMETHANE	116	85-115	RE121D2-GW-122115	Detects: J

**Notes:**

- %R = Percent recovery
- UJ = Non-detect estimated value
- J = Detected estimated value

**Table A-5  
Matrix Spike/Matrix Spike Duplicate Non-Conformance  
(Micrograms per liter)**

Spiked Sample	Analyte	Sample Result	Spike Added	MS %R	MSD %R	%R Limits	Qualifier
TT101D2-GW-122115	METHYLENE CHLORIDE	<2.5	50.0	<b>53.4</b>	60.2	55-140	UJ
TT101D2-GW-122115	CIS-1,2-DICHLOROETHENE	1.7	50.0	<b>54.6</b>	<b>59.8</b>	70-125	J
TT101D2-GW-122115	1,2,4-TRICHLOROBENZENE	<0.50	50.0	<b>50.8</b>	<b>56.2</b>	65-135	UJ
TT101D2-GW-122115	CHLOROENZENE	<0.50	50.0	<b>55.8</b>	<b>60.2</b>	80-120	UJ
TT101D2-GW-122115	1,1-DICHLOROETHANE	<0.50	50.0	<b>64.4</b>	70.8	70-135	UJ
TT101D2-GW-122115	CIS-1,3-DICHLOROPROPENE	<0.50	50.0	<b>60.8</b>	<b>64.4</b>	70-130	UJ
TT101D2-GW-122115	1,2-DIBROMO-3-CHLOROPROPANE	<0.75	50.0	<b>46.4</b>	57	50-130	UJ
TT101D2-GW-122115	ISOPROPYL BENZENE	<0.50	50.0	<b>56.2</b>	<b>61</b>	75-125	UJ
TT101D2-GW-122115	TRANS-1,2-DICHLOROETHENE	<0.50	50.0	<b>58.4</b>	65.2	60-140	UJ
TT101D2-GW-122115	BENZENE	<0.50	50.0	<b>62.4</b>	<b>67.6</b>	80-120	UJ
TT101D2-GW-122115	1,2-DICHLOROPROPANE	<0.50	50.0	<b>63.8</b>	<b>68.8</b>	75-125	UJ
TT101D2-GW-122115	O-XYLENE	<0.50	50.0	<b>58.8</b>	<b>62.2</b>	80-120	UJ
TT101D2-GW-122115	1,3-DICHLOROENZENE	<0.50	50.0	<b>51.4</b>	<b>56.8</b>	75-125	UJ
TT101D2-GW-122115	1,1-DICHLOROETHENE	3.6	50.0	<b>56.8</b>	<b>63.4</b>	70-130	J
TT101D2-GW-122115	1,1,2-TRICHLOROETHANE	0.50	50.0	<b>63.4</b>	<b>65.4</b>	75-125	J
TT101D2-GW-122115	CYCLOHEXANE	<0.50	50.0	<b>63.8</b>	<b>69</b>	71-133	UJ
TT101D2-GW-122115	TOLUENE	<0.50	50.0	<b>65</b>	<b>69.6</b>	75-120	UJ
TT101D2-GW-122115	CARBON TETRACHLORIDE	1.3	50.0	<b>63.6</b>	66.6	65-140	J
TT101D2-GW-122115	1,2-DICHLOROETHANE	<0.50	50.0	<b>61.6</b>	<b>66</b>	70-130	UJ
TT101D2-GW-122115	1,2-DICHLOROETHENE, TOTAL	1.7	100	<b>56.5</b>	<b>62.5</b>	84-121	J
TT101D2-GW-122115	XYLENES, TOTAL	<1.5	150	<b>59.8</b>	<b>63.2</b>	89-116	UJ
TT101D2-GW-122115	STYRENE	<0.50	50.0	<b>60.4</b>	<b>63.4</b>	65-135	UJ
TT101D2-GW-122115	DIBROMOCHLOROMETHANE	<0.50	50.0	<b>59.4</b>	63.6	60-135	UJ
TT101D2-GW-122115	1,4-DICHLOROENZENE	<0.50	50.0	<b>50.8</b>	<b>54.6</b>	75-125	UJ
TT101D2-GW-122115	ETHYLBENZENE	<0.50	50.0	<b>56.2</b>	<b>60.8</b>	75-125	UJ
TT101D2-GW-122115	M- AND P-XYLENE	<1.0	100	<b>60.2</b>	<b>63.8</b>	75-130	UJ
TT101D2-GW-122115	BROMOFORM	<0.50	50.0	<b>55.6</b>	<b>57</b>	70-130	UJ
TT101D2-GW-122115	BROMODICHLOROMETHANE	<0.50	50.0	<b>67.6</b>	<b>70</b>	75-120	UJ
TT101D2-GW-122115	CHLOROFORM	0.90	50.0	<b>57</b>	<b>62.4</b>	65-135	J
TT101D2-GW-122115	1,1,1-TRICHLOROETHANE	0.34	50.0	<b>58.9</b>	<b>64.3</b>	65-130	J
TT101D2-GW-122115	1,2-DIBROMOETHANE	<0.50	50.0	<b>61.2</b>	<b>66.6</b>	80-120	UJ
TT101D2-GW-122115	1,1,2,2-TETRACHLOROETHANE	<0.50	50.0	<b>51.6</b>	<b>59.2</b>	65-130	UJ
TT101D2-GW-122115	1,2-DICHLOROENZENE	<0.50	50.0	<b>52</b>	<b>57.6</b>	70-120	UJ

**Notes:**

- MS = Matrix spike
- MSD = Matrix spike duplicate
- %R = Percent recovery
- Bold** = Percent recovery not within control limit
- UJ = Nondetect analyte in associated sample qualified estimated "UJ" because the %R is lower than the control limit.
- J = Detected analyte in associated sample qualified estimated "J" because %R is lower than the control limit.

Table A-6  
Field Duplicate  
(Micrograms per liter)

Sample ID	Duplicate ID	Analyte	Sample Result	Duplicate Result	RPD	Qualifiers
TT101D2-GW-122115	DUPLICATE-GW-122115	1,1-DICHLOROETHENE	3.6	5	32.6	J - both results

**Notes:**

RPD = Relative percent difference

J = Estimated value



**Attachment B**  
**Qualifier Codes and Explanations**

Qualifier	Explanation
J	The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
UJ	The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual quantitation limit necessary to accurately and precisely measure the analyte in the sample.
U	The analyte was analyzed for, but was not detected above the reported sample quantitation limit.

**Attachment C**  
**Reason Codes and Explanations**

Reason Code	Explanation
be	Equipment blank contamination
bf	Field blank contamination
bl	Laboratory blank contamination
bm	Missing blank information
bt	Trip blank contamination
c	Calibration issue
cr	Chromatographic resolution
d	Reporting limit raised due to chromatographic interference
dt	Dissolved result > total over limit
e	Ether interference
ej	Above calibration range; result estimated.
f	Presumed contamination from FB or ER.
fd	Field duplicate RPDs
h	Holding times
hs	Headspace greater than 6mm in all sample vials
i	Internal standard areas
ii	Injection internal standard area or retention time exceedance
it	Instrument tune
k	Estimated maximum possible concentrations (EMPC)
l	LCS recoveries
lc	Labeled compound recovery
ld	Laboratory duplicate RPDs
lp	Laboratory control sample/laboratory control sample duplicate RPDs
m	Matrix spike recovery
mc	Deviation from the method
md	MS/MSD RPDs
nb	Negative laboratory blank contamination
p	Chemical preservation issue
p-h	Uncertainty near detection limit (< Reporting Limit), historical reason code applied.
pe	Post Extraction Spike
q	Quantitation issue
r	Dual column RPD
rt	SIM ions not within + 2 seconds
s	Surrogate recovery
sp	Sample preparation issue
su	Evidence of ion suppression
t	Temperature Preservation Issue
x	Low % solids
y	Serial dilution results
z	ICS results

**Attachment D**  
**Final Results after Data Review**

				Sample Delivery Group		BETHPAGE-3	
				Lab ID		TI0330-4	
				Sample ID		RE114D1-GW-122115	
				Sample Date		12/21/2015	
				Sample Type		Groundwater	
Method	Analyte	CAS No	Units	Result	Qual	RC	
8260C	1,1,1-TRICHLOROETHANE	71-55-6	UG L	0.64	J	s	
8260C	1,1,2,2-TETRACHLOROETHANE	79-34-5	UG L	0.5	U		
8260C	1,1,2-TRICHLORO-1,2,2-TRIFLUOROETHANE	76-13-1	UG L	20	J	s	
8260C	1,1,2-TRICHLOROETHANE	79-00-5	UG L	1.6	J	s	
8260C	1,1-DICHLOROETHANE	75-34-3	UG L	1.5	J	s	
8260C	1,1-DICHLOROETHENE	75-35-4	UG L	4	J	s	
8260C	1,2,4-TRICHLOROBENZENE	120-82-1	UG L	0.5	U		
8260C	1,2-DIBROMO-3-CHLOROPROPANE	96-12-8	UG L	0.75	U		
8260C	1,2-DIBROMOETHANE	106-93-4	UG L	0.5	U		
8260C	1,2-DICHLOROBENZENE	95-50-1	UG L	0.5	U		
8260C	1,2-DICHLOROETHANE	107-06-2	UG L	0.5	U		
8260C	1,2-DICHLOROETHENE, TOTAL	540-59-0	UG L	5.1	J	s	
8260C	1,2-DICHLOROPROPANE	78-87-5	UG L	0.5	U		
8260C	1,3-DICHLOROBENZENE	541-73-1	UG L	0.5	U		
8260C	1,4-DICHLOROBENZENE	106-46-7	UG L	0.5	U		
8260C	2-BUTANONE	78-93-3	UG L	2.5	UJ	c	
8260C	2-HEXANONE	591-78-6	UG L	2.5	UJ	c	
8260C	4-METHYL-2-PENTANONE	108-10-1	UG L	2.5	U		
8260C	ACETONE	67-64-1	UG L	2.5	UJ	c	
8260C	BENZENE	71-43-2	UG L	0.5	U		
8260C	BROMODICHLOROMETHANE	75-27-4	UG L	0.5	U		
8260C	BROMOFORM	75-25-2	UG L	0.5	U		
8260C	BROMOMETHANE	74-83-9	UG L	1	U		
8260C	CARBON DISULFIDE	75-15-0	UG L	0.5	U		
8260C	CARBON TETRACHLORIDE	56-23-5	UG L	2.5	J	s	
8260C	CHLOROBENZENE	108-90-7	UG L	0.5	U		
8260C	CHLOROETHANE	75-00-3	UG L	1	UJ	c	
8260C	CHLOROFORM	67-66-3	UG L	2.9	J	s	
8260C	CHLOROMETHANE	74-87-3	UG L	1	U		
8260C	CIS-1,2-DICHLOROETHENE	156-59-2	UG L	5.1	J	s	
8260C	CIS-1,3-DICHLOROPROPENE	10061-01-5	UG L	0.5	U		
8260C	CYCLOHEXANE	110-82-7	UG L	0.5	U		
8260C	DIBROMOCHLOROMETHANE	124-48-1	UG L	0.5	U		
8260C	DICHLORODIFLUOROMETHANE	75-71-8	UG L	1	J	s	
8260C	ETHYLBENZENE	100-41-4	UG L	0.5	U		
8260C	ISOPROPYLBENZENE	98-82-8	UG L	0.5	U		
8260C	M- AND P-XYLENE	108-38-3/106-42	UG L	1	U		
8260C	METHYL ACETATE	79-20-9	UG L	0.75	U		
8260C	METHYL CYCLOHEXANE	108-87-2	UG L	0.5	U		
8260C	METHYL TERT-BUTYL ETHER	1634-04-4	UG L	0.5	U		
8260C	METHYLENE CHLORIDE	75-09-2	UG L	2.5	U		
8260C	O-XYLENE	95-47-6	UG L	0.5	U		
8260C	STYRENE	100-42-5	UG L	0.5	U		
8260C	TETRACHLOROETHENE	127-18-4	UG L	0.5	U		
8260C	TOLUENE	108-88-3	UG L	0.3	J	s	
8260C	TRANS-1,2-DICHLOROETHENE	156-60-5	UG L	0.5	U		
8260C	TRANS-1,3-DICHLOROPROPENE	10061-02-6	UG L	0.5	UJ	c	
8260C	TRICHLOROETHENE	79-01-6	UG L	370			
8260C	TRICHLOROFUOROMETHANE	75-69-4	UG L	1	U		
8260C	VINYL CHLORIDE	75-01-4	UG L	1	U		
8260C	XYLENES, TOTAL	1330-20-7	UG L	1.5	U		
8270D SIM	1,4-DIOXANE	123-91-1	UG L	5.5			

				Sample Delivery Group		BETHPAGE-3	
				Lab ID	TI0214-5		
				Sample ID	RE114D2-GW-121615		
				Sample Date	12/16/2015		
				Sample Type	Groundwater		
Method	Analyte	CAS No	Units	Result	Qual	RC	
8260C	1,1,1-TRICHLOROETHANE	71-55-6	UG L	0.5	U		
8260C	1,1,2,2-TETRACHLOROETHANE	79-34-5	UG L	0.5	U		
8260C	1,1,2-TRICHLORO-1,2,2-TRIFLUOROETHANE	76-13-1	UG L	14			
8260C	1,1,2-TRICHLOROETHANE	79-00-5	UG L	0.5	U		
8260C	1,1-DICHLOROETHANE	75-34-3	UG L	0.5	U		
8260C	1,1-DICHLOROETHENE	75-35-4	UG L	0.5	U		
8260C	1,2,4-TRICHLOROBENZENE	120-82-1	UG L	0.5	U		
8260C	1,2-DIBROMO-3-CHLOROPROPANE	96-12-8	UG L	0.75	U		
8260C	1,2-DIBROMOETHANE	106-93-4	UG L	0.5	U		
8260C	1,2-DICHLOROBENZENE	95-50-1	UG L	0.5	U		
8260C	1,2-DICHLOROETHANE	107-06-2	UG L	0.5	U		
8260C	1,2-DICHLOROETHENE, TOTAL	540-59-0	UG L	0.82	J		
8260C	1,2-DICHLOROPROPANE	78-87-5	UG L	0.5	U		
8260C	1,3-DICHLOROBENZENE	541-73-1	UG L	0.5	U		
8260C	1,4-DICHLOROBENZENE	106-46-7	UG L	0.5	U		
8260C	2-BUTANONE	78-93-3	UG L	2.5	U		
8260C	2-HEXANONE	591-78-6	UG L	2.5	U		
8260C	4-METHYL-2-PENTANONE	108-10-1	UG L	2.5	UJ	c	
8260C	ACETONE	67-64-1	UG L	2.5	U		
8260C	BENZENE	71-43-2	UG L	0.5	U		
8260C	BROMODICHLOROMETHANE	75-27-4	UG L	0.5	U		
8260C	BROMOFORM	75-25-2	UG L	0.5	U		
8260C	BROMOMETHANE	74-83-9	UG L	1	UJ	c	
8260C	CARBON DISULFIDE	75-15-0	UG L	0.5	U		
8260C	CARBON TETRACHLORIDE	56-23-5	UG L	0.5	U		
8260C	CHLOROBENZENE	108-90-7	UG L	0.5	U		
8260C	CHLOROETHANE	75-00-3	UG L	1	U		
8260C	CHLOROFORM	67-66-3	UG L	0.4	J		
8260C	CHLOROMETHANE	74-87-3	UG L	1	U		
8260C	CIS-1,2-DICHLOROETHENE	156-59-2	UG L	0.82	J		
8260C	CIS-1,3-DICHLOROPROPENE	10061-01-5	UG L	0.5	U		
8260C	CYCLOHEXANE	110-82-7	UG L	0.5	U		
8260C	DIBROMOCHLOROMETHANE	124-48-1	UG L	0.5	U		
8260C	DICHLORODIFLUOROMETHANE	75-71-8	UG L	1	U		
8260C	ETHYLBENZENE	100-41-4	UG L	0.5	U		
8260C	ISOPROPYLBENZENE	98-82-8	UG L	0.5	U		
8260C	M- AND P-XYLENE	108-38-3/106-42	UG L	1	U		
8260C	METHYL ACETATE	79-20-9	UG L	0.75	U		
8260C	METHYL CYCLOHEXANE	108-87-2	UG L	0.5	U		
8260C	METHYL TERT-BUTYL ETHER	1634-04-4	UG L	0.5	U		
8260C	METHYLENE CHLORIDE	75-09-2	UG L	2.5	U		
8260C	O-XYLENE	95-47-6	UG L	0.5	U		
8260C	STYRENE	100-42-5	UG L	0.5	U		
8260C	TETRACHLOROETHENE	127-18-4	UG L	0.5	UJ	c	
8260C	TOLUENE	108-88-3	UG L	0.5	U		
8260C	TRANS-1,2-DICHLOROETHENE	156-60-5	UG L	0.5	U		
8260C	TRANS-1,3-DICHLOROPROPENE	10061-02-6	UG L	0.5	U		
8260C	TRICHLOROETHENE	79-01-6	UG L	70			
8260C	TRICHLOROFUOROMETHANE	75-69-4	UG L	1	U		
8260C	VINYL CHLORIDE	75-01-4	UG L	1	U		
8260C	XYLENES, TOTAL	1330-20-7	UG L	1.5	U		
8270D SIM	1,4-DIOXANE	123-91-1	UG L	2.5			

				Sample Delivery Group	BETHPAGE-3		
				Lab ID	TI0214-4		
				Sample ID	RE114D3-GW-121615		
				Sample Date	12/16/2015		
				Sample Type	Groundwater		
Method	Analyte	CAS No	Units	Result	Qual	RC	
8260C	1,1,1-TRICHLOROETHANE	71-55-6	UG L	0.5	U		
8260C	1,1,2,2-TETRACHLOROETHANE	79-34-5	UG L	0.5	U		
8260C	1,1,2-TRICHLORO-1,2,2-TRIFLUOROETHANE	76-13-1	UG L	13			
8260C	1,1,2-TRICHLOROETHANE	79-00-5	UG L	0.5	U		
8260C	1,1-DICHLOROETHANE	75-34-3	UG L	0.5	U		
8260C	1,1-DICHLOROETHENE	75-35-4	UG L	1.1			
8260C	1,2,4-TRICHLOROBENZENE	120-82-1	UG L	0.5	U		
8260C	1,2-DIBROMO-3-CHLOROPROPANE	96-12-8	UG L	0.75	U		
8260C	1,2-DIBROMOETHANE	106-93-4	UG L	0.5	U		
8260C	1,2-DICHLOROBENZENE	95-50-1	UG L	0.5	U		
8260C	1,2-DICHLOROETHANE	107-06-2	UG L	0.5	U		
8260C	1,2-DICHLOROETHENE, TOTAL	540-59-0	UG L	0.67	J		
8260C	1,2-DICHLOROPROPANE	78-87-5	UG L	0.5	U		
8260C	1,3-DICHLOROBENZENE	541-73-1	UG L	0.5	U		
8260C	1,4-DICHLOROBENZENE	106-46-7	UG L	0.5	U		
8260C	2-BUTANONE	78-93-3	UG L	2.5	U		
8260C	2-HEXANONE	591-78-6	UG L	2.5	U		
8260C	4-METHYL-2-PENTANONE	108-10-1	UG L	2.5	UJ		c
8260C	ACETONE	67-64-1	UG L	2.5	U		
8260C	BENZENE	71-43-2	UG L	0.5	U		
8260C	BROMODICHLOROMETHANE	75-27-4	UG L	0.5	U		
8260C	BROMOFORM	75-25-2	UG L	0.5	U		
8260C	BROMOMETHANE	74-83-9	UG L	1	UJ		c
8260C	CARBON DISULFIDE	75-15-0	UG L	0.5	U		
8260C	CARBON TETRACHLORIDE	56-23-5	UG L	0.5	U		
8260C	CHLOROBENZENE	108-90-7	UG L	0.5	U		
8260C	CHLOROETHANE	75-00-3	UG L	1	U		
8260C	CHLOROFORM	67-66-3	UG L	0.5	U		
8260C	CHLOROMETHANE	74-87-3	UG L	1	U		
8260C	CIS-1,2-DICHLOROETHENE	156-59-2	UG L	0.67	J		
8260C	CIS-1,3-DICHLOROPROPENE	10061-01-5	UG L	0.5	U		
8260C	CYCLOHEXANE	110-82-7	UG L	0.5	U		
8260C	DIBROMOCHLOROMETHANE	124-48-1	UG L	0.5	U		
8260C	DICHLORODIFLUOROMETHANE	75-71-8	UG L	1	U		
8260C	ETHYLBENZENE	100-41-4	UG L	0.5	U		
8260C	ISOPROPYLBENZENE	98-82-8	UG L	0.5	U		
8260C	M- AND P-XYLENE	108-38-3/106-42	UG L	1	U		
8260C	METHYL ACETATE	79-20-9	UG L	0.75	U		
8260C	METHYL CYCLOHEXANE	108-87-2	UG L	0.5	U		
8260C	METHYL TERT-BUTYL ETHER	1634-04-4	UG L	0.5	U		
8260C	METHYLENE CHLORIDE	75-09-2	UG L	2.5	U		
8260C	O-XYLENE	95-47-6	UG L	0.5	U		
8260C	STYRENE	100-42-5	UG L	0.5	U		
8260C	TETRACHLOROETHENE	127-18-4	UG L	0.5	UJ		c
8260C	TOLUENE	108-88-3	UG L	0.5	U		
8260C	TRANS-1,2-DICHLOROETHENE	156-60-5	UG L	0.5	U		
8260C	TRANS-1,3-DICHLOROPROPENE	10061-02-6	UG L	0.5	U		
8260C	TRICHLOROETHENE	79-01-6	UG L	43			
8260C	TRICHLOROFUOROMETHANE	75-69-4	UG L	1	U		
8260C	VINYL CHLORIDE	75-01-4	UG L	1	U		
8260C	XYLENES, TOTAL	1330-20-7	UG L	1.5	U		
8270D SIM	1,4-DIOXANE	123-91-1	UG L	2.1			





**DATA VALIDATION REPORT**

Project:	Regional Groundwater Investigation — NWIRP Bethpage		
Laboratory:	Katahdin Analytical		
Sample Delivery Groups:	SI7928		
Analyses/Method:	Total Organic Carbon (TOC) by U.S. EPA SW-846 Method 9060A and Standard Method 5310B for Total Organic Carbon by High-Temperature Combustion		
Validation Level:	3		
Project Number:	0888812477.SA.DV		
Prepared by:	Dana Miller/Resolution Consultants	Completed on:	10/28/2015
Reviewed by:	Tina Clemmey/Resolution Consultants	File Name:	SI7928_9060A_5310B

**SUMMARY**

This report summarizes data review findings for samples listed below, collected by Resolution Consultants from the Regional Groundwater Investigation — NWIRP Bethpage site on 30 September 2015 in accordance with the following Sampling and Analysis Plans:

- *Sampling and Analysis Plan, Bethpage, New York.* (Resolution Consultants April 2013).
- *UFP SAP Addendum, Installation of Vertical Profile Borings and Monitoring Wells, Operable Unit 2, NWIRP Bethpage, New York.* (Resolution Consultants November 2013).
- *UFP SAP Addendum, Inclusion of Additional Target Analytes for Volatile Organics Analyses, NWIRP Bethpage OU2, Bethpage, New York.* (Resolution Consultants August 2014).

Sample ID	Lab ID	Matrix/Sample Type	Analysis
RE114D3-SOIL-093015-713-715	SI7928-1	Soil	9060A
RE114D3-EB-093015	SI7928-2	Equipment Blank	5310B

Data validation activities were conducted using the following guidance documents: *Test Methods for Evaluating Solid Waste, Physical/Chemical Methods SW-846, specifically Method 9060A, Total Organic Carbon* (U.S. EPA, 1996), *Method SM5310B, Total Organic Carbon by High-Temperature Combustion*, *U.S. Environmental Protection Agency (U.S. EPA) Contract Laboratory Program National Functional Guidelines for Inorganic Superfund Data Review* (NFG, January 2010, and Department of Defense (DoD) Quality Systems Manual (QSM) for Environmental Laboratories, Version 4.2 (October 2010). In

the absence of method-specific information, laboratory quality control (QC) limits, project-specific requirements and/or professional judgment were used as appropriate.

## **REVIEW ELEMENTS**

The data were evaluated based on the following parameters (where applicable to the method):

- ✓ Data completeness (chain-of-custody)/sample integrity
- ✓ Holding times and sample preservation
- ✓ Gas chromatography/Mass spectrometer performance checks
- ✓ Initial calibration/continuing calibration verification
- ✓ Laboratory blanks/equipment blanks/field blanks/trip blanks
- NA Surrogate spike recoveries
- ✓ Matrix spike and/or matrix spike duplicate results
- ✓ Laboratory control sample laboratory control sample duplicate results
- NA Field duplicates
- NA Internal standards
- ✓ Sample results/reporting issues

The symbol (✓) indicates that no validation qualifiers were applied based on this parameter. NA indicates that the parameter was not included as part of this data set or was not applicable to this validation and therefore not reviewed. Acceptable data parameters for which all criteria were met and no qualification was performed, and non-conformance or other issues that were noted during validation, but did not result in qualification of data are not discussed further.

## **Qualifications Actions**

The data were reviewed independently from the laboratory to assess data quality. All compounds detected at concentrations less than the limit of quantitation but greater than the method detection limit were qualified by the laboratory as estimated (J). This "J" qualifier was retained during data validation. Any sample that was analyzed at a dilution because of high concentrations of target or non-target analytes was checked to confirm that the results and/or sample-specific limit of quantitation and limit of detections were adjusted accordingly by the laboratory.

No results were qualified during this review. Analytical completeness was calculated to be 100% and the data are usable for their intended purpose, according to U.S. Environmental Protection Agency and Department of Defense guidelines. Attachment A, Table A-1 provides final results after data review.

**ATTACHMENTS**

Attachment A: Table A-1 Final Results after Data Review

**Attachment A**  
**Final Results after Data Review**

**Table A-1  
Final Results after Data Review  
Regional Groundwater Investigation NWIRP Bethpage**

<b>Sample Delivery Group</b>				SI7928		SI7928	
<b>Lab ID</b>				SI7928-1		SI7928-2	
<b>Sample ID</b>				RE11403-SOIL-093015-713-715		RE114D3-EB-093015	
<b>Sample Date</b>				9/30/2015		9/30/2015	
<b>Sample Type</b>				Soil		Equipment Blank	
<b>Method</b>	<b>Analyte</b>	<b>CAS No</b>	<b>Units</b>	Result	Qual	Result	Qual
2540G	TOTAL SOLIDS	-29	PCT	89		NA	
5310B	TOTAL ORGANIC CARBON	-28	MG_L	NA		0.23	
9060A	TOTAL ORGANIC CARBON	-28	UG_G	240	J	NA	

**Notes:**

ID = Identification  
PCT = Percent  
MG\_L = Milligrams per liter  
UG\_G = Micrograms per gram  
Qual = Final interpreted qualifier  
NA = Not analyzed  
J = Estimated value – Value was below the limit of quantitation.



**DATA VALIDATION REPORT**

Project:	Regional Groundwater Investigation — NWIRP Bethpage		
Laboratory:	Katahdin Analytical		
Sample Delivery Groups:	SI8281		
Analyses/Method:	Total Organic Carbon (TOC) by U.S. EPA SW-846 Method 9060A and Standard Method 5310B for Total Organic Carbon by High-Temperature Combustion		
Validation Level:	3		
Project Number:	0888812477.SA.DV		
Prepared by:	Dana Miller/Resolution Consultants	Completed on:	11/20/2015
Reviewed by:	Tina Clemmey/Resolution Consultants	File Name:	SI8281_ 9060A_5310B

**SUMMARY**

This report summarizes data review findings for samples listed below, collected by Resolution Consultants from the Regional Groundwater Investigation — NWIRP Bethpage site on 19 October 2015 in accordance with the following Sampling and Analysis Plans:

- *Sampling and Analysis Plan, Bethpage, New York.* (Resolution Consultants April 2013).
- *UFP SAP Addendum, Installation of Vertical Profile Borings and Monitoring Wells, Operable Unit 2, NWIRP Bethpage, New York.* (Resolution Consultants November 2013).
- *UFP SAP Addendum, Inclusion of Additional Target Analytes for Volatile Organics Analyses, NWIRP Bethpage OU2, Bethpage, New York.* (Resolution Consultants August 2014).

Sample ID	Lab ID	Matrix/Sample Type	Analysis
RE114D1-SOIL-101915-553-555	SI8281-1	Soil	9060A
RE114D1-EB-101915	SI8281-1	Equipment Blank	5310B

Data validation activities were conducted using the following guidance documents: *Test Methods for Evaluating Solid Waste, Physical/Chemical Methods SW-846, specifically Method 9060A, Total Organic Carbon* (U.S. EPA, 1996), *Method SM5310B, Total Organic Carbon by High-Temperature Combustion*, *U.S. Environmental Protection Agency (U.S. EPA) Contract Laboratory Program National Functional Guidelines for Inorganic Superfund Data Review* (NFG, January 2010, and Department of Defense (DoD) Quality Systems Manual (QSM) for Environmental Laboratories, Version 4.2 (October 2010). In

the absence of method-specific information, laboratory quality control (QC) limits, project-specific requirements and/or professional judgment were used as appropriate.

## **REVIEW ELEMENTS**

The data were evaluated based on the following parameters (where applicable to the method):

- ✓ Data completeness (chain-of-custody)/sample integrity
- ✓ Holding times and sample preservation
- ✓ Gas chromatography/Mass spectrometer performance checks
- ✓ Initial calibration/continuing calibration verification
- ✓ Laboratory blanks/equipment blanks/field blanks/trip blanks
- NA Surrogate spike recoveries
- ✓ Matrix spike and/or matrix spike duplicate results
- ✓ Laboratory control sample laboratory control sample duplicate results
- NA Field duplicates
- NA Internal standards
- ✓ Sample results/reporting issues

The symbol (✓) indicates that no validation qualifiers were applied based on this parameter. NA indicates that the parameter was not included as part of this data set or was not applicable to this validation and therefore not reviewed. Acceptable data parameters for which all criteria were met and no qualification was performed, and non-conformance or other issues that were noted during validation, but did not result in qualification of data are not discussed further.

## **Qualifications Actions**

The data was reviewed independently from the laboratory to assess data quality. Any sample that was analyzed at a dilution because of high concentrations of target or non-target analytes was checked to confirm that the results and/or sample-specific limit of quantitation and limit of detections were adjusted accordingly by the laboratory.

No results were qualified during this review. Analytical completeness was calculated to be 100% and the data are usable for their intended purpose, according to U.S. Environmental Protection Agency and Department of Defense guidelines. Attachment A, Table A-1 provides final results after data review.

## **ATTACHMENTS**

Attachment A: Table A-1 Final Results after Data Review

**Attachment A**  
**Final Results after Data Review**



**Table A-1  
Final Results after Data Review  
Regional Groundwater Investigation NWIRP Bethpage**

<b>Sample Delivery Group</b>				SI8281	SI8281
<b>Lab ID</b>				SI8281-1	SI8281-2
<b>Sample ID</b>				RE114DI-SOIL-101915-553-555	RE114DI-EB-101915
<b>Sample Date</b>				10/19/2015	10/19/2015
<b>Sample Type</b>				Soil	Equipment Blank
<b>Method</b>	<b>Analyte</b>	<b>CAS No</b>	<b>Units</b>	Result	Result
2540G	TOTAL SOLIDS	-29	PCT	83	NA
5310B	TOTAL ORGANIC CARBON	-28	MG_L	NA	0.12
9060A	TOTAL ORGANIC CARBON	-28	UG_G	660	NA

**Notes:**

ID = Identification  
PCT = Percent  
MG\_L = Milligrams per liter  
UG\_G = Micrograms per gram  
NA = Not analyzed



**DATA VALIDATION REPORT**

Project:	Regional Groundwater Investigation — NWIRP Bethpage		
Laboratory:	Katahdin Analytical		
Sample Delivery Groups:	SI9042		
Analyses/Method:	Total Organic Carbon (TOC) by U.S. EPA SW-846 Method 9060A and Standard Method 5310B for Total Organic Carbon by High-Temperature Combustion		
Validation Level:	3		
Project Number:	0888812477.SA.DV		
Prepared by:	Dana Miller/Resolution Consultants	Completed on:	12/15/2015
Reviewed by:	Tina Clemmey/Resolution Consultants	File Name:	SI9042_ 9060A_5310B

**SUMMARY**

This report summarizes data review findings for samples listed below, collected by Resolution Consultants from the Regional Groundwater Investigation — NWIRP Bethpage site on 9 November 2015 in accordance with the following Sampling and Analysis Plans:

- *Sampling and Analysis Plan, Bethpage, New York.* (Resolution Consultants April 2013).
- *UFP SAP Addendum, Installation of Vertical Profile Borings and Monitoring Wells, Operable Unit 2, NWIRP Bethpage, New York.* (Resolution Consultants November 2013).
- *UFP SAP Addendum, Inclusion of Additional Target Analytes for Volatile Organics Analyses, NWIRP Bethpage OU2, Bethpage, New York.* (Resolution Consultants August 2014).

Sample ID	Lab ID	Matrix/Sample Type	Analysis
RE114D2-SOIL-110915-618-620	SI9042-1	Soil	9060A
RE114D2-EB-110915	SI9042-2	Equipment Blank	5310B

Data validation activities were conducted using the following guidance documents: *Test Methods for Evaluating Solid Waste, Physical/Chemical Methods SW-846, specifically Method 9060A, Total Organic Carbon* (U.S. EPA, 1996), *Method SM5310B, Total Organic Carbon by High-Temperature Combustion*, *U.S. Environmental Protection Agency (U.S. EPA) Contract Laboratory Program National Functional Guidelines for Inorganic Superfund Data Review* (NFG, January 2010, and Department of Defense (DoD) Quality Systems Manual (QSM) for Environmental Laboratories, Version 4.2 (October 2010). In

the absence of method-specific information, laboratory quality control (QC) limits, project-specific requirements and/or professional judgment were used as appropriate.

## **REVIEW ELEMENTS**

The data were evaluated based on the following parameters (where applicable to the method):

- ✓ Data completeness (chain-of-custody)/sample integrity
- ✓ Holding times and sample preservation
- ✓ Gas chromatography/Mass spectrometer performance checks
- ✓ Initial calibration/continuing calibration verification
- ✓ Laboratory blanks/equipment blanks/field blanks/trip blanks
- NA Surrogate spike recoveries
- NA Matrix spike and/or matrix spike duplicate results
- ✓ Laboratory control sample laboratory control sample duplicate results
- NA Field duplicates
- NA Internal standards
- ✓ Sample results/reporting issues

The symbol (✓) indicates that no validation qualifiers were applied based on this parameter. NA indicates that the parameter was not included as part of this data set or was not applicable to this validation and therefore not reviewed. Acceptable data parameters for which all criteria were met and no qualification was performed, and non-conformance or other issues that were noted during validation, but did not result in qualification of data are not discussed further.

## **Qualifications Actions**

The data were reviewed independently from the laboratory to assess data quality. Any sample that was analyzed at a dilution because of high concentrations of target or non-target analytes was checked to confirm that the results and/or sample-specific limit of quantitation and limit of detections were adjusted accordingly by the laboratory.

No results were qualified during this review. Analytical completeness was calculated to be 100% and the data are usable for their intended purpose, according to U.S. Environmental Protection Agency and Department of Defense guidelines. Attachment A, Table A-1 provides final results after data review.

## **ATTACHMENTS**

Attachment A: Table A-1 Final Results after Data Review

**Attachment A**  
**Final Results after Data Review**

**Table A-1**  
**Final Results after Data Review**  
**Regional Groundwater Investigation NWIRP Bethpage**

<b>Sample Delivery Group</b>				SI9042	SI9042
<b>Lab ID</b>				SI9042-1	SI9042-2
<b>Sample ID</b>				RE114D2-SOIL-110915-618-620	RE114D2-EB-110915
<b>Sample Date</b>				11/9/2015	11/9/2015
<b>Sample Type</b>				Soil	Equipment Blank
<b>Method</b>	<b>Analyte</b>	<b>CAS No</b>	<b>Units</b>	Result	Result
2540G	TOTAL SOLIDS	-29	PCT	82	NA
5310B	TOTAL ORGANIC CARBON	-28	MG_L	NA	0.17
9060A	TOTAL ORGANIC CARBON	-28	UG_G	1900	NA

**Notes:**


ID = Identification  
PCT = Percent  
MG\_L = Milligrams per liter  
UG\_G = Micrograms per gram  
NA = Not analyzed

## **Section 5**

### **Survey**

UNAUTHORIZED ALTERATION OR ADDITION TO THIS DOCUMENT IS A VIOLATION OF SECTION 7209 SUBDIVISION 2 OF THE NEW YORK STATE EDUCATION LAW.

Description	Northing	Easting	Latitude	Longitude	Ground	Rim	PVC
RE114D1	201728.64	1124289.94	N40-43-09.36	W73-29-41.29	74.59	74.59	74.04
RE114D2	201710.25	1124365.40	N40-43-09.18	W73-29-41.61	74.48	74.48	73.96
RE114D3	201719.48	1124277.84	N40-43-09.27	W73-29-41.45	74.59	74.59	74.17




BENCHMARK SET  
NHOA ON HYDRANT  
ELEVATION=74.49'

LEGEND

- LP Light Pole
- MW Monitoring Well
- SMH Sanitary Manhole
- VPB 141 Vertical Profile Boring
- ⊕ HYD Water Hydrant
- WV Water Valve

Map Notes

1. Information shown hereon was compiled from an actual field survey conducted on December 7, 2015.
2. North orientation is Grid North based on the New York State Plane Coordinate System, Long Island Zone, NAD 83(2011) epoch 2010.00 as obtained from GPS observations.
3. Vertical datum shown hereon is NAVD 88(Geoid12A) as obtained from RTK GPS observations using the Queens CORS as a base station.



DWG NO. 15-702

Date	RECORD OF WORK	Appr.	VERTICAL PROFILE BORING 148 SURVEY LOCATION RE114D1-RE114D2-RE114D3 ELM DRIVE NORTH AND ELBOW LANE	
			TOWN OF LEVITTOWN	NASSAU COUNTY, NEW YORK
<b>C.T. MALE ASSOCIATES</b> Engineering, Surveying, Architecture & Landscape Architecture, D.P.C.				
Drafter: LMK                      Checker: JFC			50 CENTURY HILL DRIVE, LATHAM, NY 12110 518.786.7400 * FAX 518.786.7299	
Appr. by: JFC                      Proj. No. 14.4121			SCALE: 1"=30'	DATE: DECEMBER 7, 2015