

**Quarterly Operations Report  
First Quarter 2016**

**Soil Vapor Extraction Containment System  
Site 1, Former Drum Marshalling Yard  
Naval Weapons Industrial Reserve Plant  
Bethpage, New York**

**Contract No. N40085-10-D-9409  
Contract Task Order No. 0005**

July 2016

Prepared for:



Naval Facilities Engineering Command Mid-Atlantic  
9324 Virginia Avenue  
Norfolk, VA 23511

Prepared by:



**KOMAN Government Solutions, LLC  
160 East Main Street, Suite 2F  
Westborough, Massachusetts 01581  
(508) 366-7442**

**Quarterly Operations Report  
First Quarter 2016**

**Soil Vapor Extraction Containment System  
Site 1, Former Drum Marshalling Yard  
Naval Weapons Industrial Reserve Plant  
Bethpage, New York**

**Contract No. N40085-10-D-9409  
Contract Task Order No. 0005**

July 2016

Prepared for:

Naval Facilities Engineering Command Mid-Atlantic  
9324 Virginia Avenue  
Norfolk, VA 23511



---

Patrick Schauble  
Program Manager

7/26/16

Date

---

Jennifer Good  
Project Manager

7/26/16

Date

## TABLE OF CONTENTS

<b>1.0</b>	<b>INTRODUCTION.....</b>	<b>1-1</b>
1.1	Site Location.....	1-1
1.2	Background.....	1-1
1.3	Project Overview and Objective.....	1-2
1.4	SVECS Overview.....	1-2
<b>2.0</b>	<b>SVECS OPERATION AND MAINTENANCE.....</b>	<b>2-1</b>
2.1	Routine Maintenance Activities.....	2-1
2.2	Non-routine Maintenance / Site Activities.....	2-1
<b>3.0</b>	<b>SVECS MONITORING.....</b>	<b>3-1</b>
3.1	Monthly Air Quality Monitoring.....	3-1
3.2	Quarterly Air Quality Monitoring of SVEWs.....	3-1
3.3	Quarterly Soil Vapor Pressure Monitoring of SVEWs and Off-site SVPMs.....	3-2
3.4	Annual Vapor Quality Monitoring of Off-site SVPMs.....	3-2
3.5	Soil Vapor Quality Concentration Trends.....	3-3
<b>4.0</b>	<b>CONCLUSIONS AND RECOMMENDATIONS.....</b>	<b>4-1</b>
<b>5.0</b>	<b>REFERENCES.....</b>	<b>5-1</b>

### **TABLES**

TABLE 1	Monthly Vapor Analytical Results – January 2016
TABLE 2	Monthly Vapor Analytical Results – February 2016
TABLE 3	Monthly Vapor Analytical Results – March 2016
TABLE 4	Quarterly Vapor Analytical Results of SVE Wells – First Quarter 2016
TABLE 5	Quarterly Vapor Analytical Results of SVE Wells through First Quarter 2016
TABLE 6	Quarterly Off-site Soil Vapor Monitoring Results of SVPMs – First Quarter 2016
TABLE 7	Quarterly Off-site Soil Vapor Monitoring Results of SVPMs through First Quarter 2016
TABLE 8	Annual Off-site Soil Vapor Analytical Results of SVPMs – January 2016
TABLE 9	Historical Off-site Soil Vapor Analytical Results of SVPMs through January 2016

### **FIGURES**

FIGURE 1	Site Location Map
FIGURE 2	Site Area and Vicinity
FIGURE 3	Site Plan – Existing SVECS Layout
FIGURE 4	System Layout Plan

FIGURE 5 First Quarter 2016 Vapor Analytical Map – Select VOC Concentrations - SVEWs

FIGURE 6 First Quarter 2016 Vacuum Readings – SVPMs

## **APPENDICES**

APPENDIX A NYSDEC Air Discharge Limit Documentation

APPENDIX B Data Validation Reports and Validated Data Summary – SVPMs

APPENDIX C Vapor Concentration Trend Graphs of Select VOCs – SVEWs

APPENDIX D Vapor Concentration Trend Graphs of Select VOCs – SVPMs



## Acronyms and Abbreviations

bgs	below ground surface
CTO	Contract Task Order
DAR	Division of Air Resources
DCA	dichloroethane
DCE	dichloroethene
DoD	Department of Defense
ELAP	Environmental Laboratory Accreditation Program
FMS	Flow Monitoring Station
GOCO	Government Owned Contractor Operated
i.w.	inches of water column
KGS	KOMAN Government Solutions, LLC
NAVFAC	Naval Facilities Engineering Command Mid-Atlantic
Navy	U.S. Department of the Navy
NELAC	National Environmental Accreditation Conference
NG	Northrop Grumman
NWIRP	Naval Weapons Industrial Reserve Plant
NYSDEC	New York State Department of Environmental Conservation
NYSDOH	New York State Department of Health
O&M	Operation and Maintenance
PCB	polychlorinated biphenyls
PCE	tetrachloroethene
PID	photoionization detector
QA/QC	quality assurance / quality control
RPD	relative percent difference
scfm	standard cubic feet per minute
SVECS	soil vapor extraction containment system
SVEW	soil vapor extraction well
SVOC	semi-volatile organic compound
SVPM	soil vapor pressure monitor
TCA	trichloroethane
TCE	trichloroethene
TCL	target compound list

TtEC	Tetra Tech EC, Inc.
TtNUS	Tetra Tech NUS, Inc.
VGAC	vapor-phase granular activated carbon
VOC	volatile organic compound

## 1.0 INTRODUCTION

KOMAN Government Solutions, LLC (KGS) has prepared this Quarterly Operations Report for the First Quarter 2016 for the Soil Vapor Extraction Containment System (SVECS) at Site 1, Former Drum Marshalling Area, at the Naval Weapons Industrial Reserve Plant (NWIRP) in Bethpage, New York. This report has been prepared for the U.S. Department of the Navy (Navy), Naval Facilities Engineering Command (NAVFAC), Mid-Atlantic, under Contract No. N40085-10-D-9409, Contract Task Order (CTO) No. 0005. This First Quarter 2016 Operations Report details activities that occurred from January 2016 to March 2016. Data was collected and operational activities were performed by KGS in accordance with the following documents:

- *Final Operation & Maintenance Plan for Soil Vapor Extraction Containment System Site 1, Former Drum Marshalling Yard at Naval Weapons Industrial Reserve Plant Bethpage, New York* prepared by Tetra Tech EC, Inc. (TtEC) in 2010, hereafter referred to as the “O&M Manual.”
- *Final Supplemental Offsite Soil Vapor Intrusion Monitoring Plan for the Soil Vapor Extraction Containment System, Site 1, Former Drum Marshalling Yard at Naval Weapons Industrial Reserve Plant, Bethpage, New York* prepared by Tetra Tech NUS, Inc. (TtNUS) in 2012.

### 1.1 Site Location

NWIRP Bethpage is located in east central Nassau County, Long Island, New York, approximately 30 miles east of New York City. In the late 1990s, the Navy's property totaled approximately 109.5 acres and was formerly a Government Owned Contractor-Operated (GOCO) facility that was operated by Northrop Grumman (NG) until September 1998. NWIRP Bethpage was bordered on the north, west, and south by property owned, or formerly owned, by NG that covered approximately 550 acres, and on the east by a residential neighborhood. The Navy currently retains approximately nine acres of the former NWIRP, including Site 1, which lies within the fenced area of NWIRP Bethpage and is located east of Plant No. 3, west of 11<sup>th</sup> Street, and north of Plant 17 South (**Figures 1 and 2**).

### 1.2 Background

NWIRP Bethpage was established in 1943. Since inception, the primary mission of the facility has been the research, prototyping, testing, design engineering, fabrication, and primary assembly of military aircraft. Historical operations that resulted in hazardous material generation at the facility included metal finishing processes, maintenance operations, painting of aircraft and components, and other activities that involve aircraft manufacturing. Wastes generated by plant operations were disposed of directly into drainage sumps, dry wells, and/or on the ground surface, resulting in the disposal of a number of hazardous wastes, including volatile organic compounds (VOCs), semi-volatile organic compounds (SVOCs), polychlorinated biphenyls (PCBs), and inorganic analytes (chromium and cadmium) at the site. Some of these contaminants have migrated from the source area to surrounding areas, including the soils at these sites and the groundwater beneath and downgradient of the NWIRP Bethpage property. NWIRP Bethpage is currently listed by the New York State Department of Environmental Conservation (NYSDEC) as an “inactive hazardous waste site” (#1-30-003B).

Soils at Site 1 consist mainly of unconsolidated sediments that overlie crystalline bedrock. A clay unit is present near the groundwater table (50 feet below ground surface [bgs]) at the southeast corner of the site. This clay unit is suspected to be a source of chlorinated solvents that are migrating into the overlying soil gas and the source of off-site VOCs in soil vapor (TtEC 2010).

Chlorinated solvents including trichloroethene (TCE), tetrachloroethene (PCE), and 1,1,1-trichloroethane (TCA) have been identified as the VOCs of interest in soil gas at the site. Concentrations greater than 1,000 micrograms per cubic meter ( $\mu\text{g}/\text{m}^3$ ) of soil vapor have been directly associated with Site 1 activities and historical environmental data, and based on preliminary screening, exceed guidelines established by the New York State Department of Health (NYSDOH) for sub-slab soil vapor concentrations. Of these compounds, TCE is the primary VOC of concern. Mitigation of TCE contamination in accordance with NYSDOH guidance is expected to remediate other VOCs associated with the site. PCBs, cadmium, and chromium have also been identified in site soils at concentrations requiring remediation. The majority of these chemicals has been detected in the central portion of Site 1 and will be addressed via a separate remediation (TtEC 2010).

Prior to implementation of the SVECS, the mean concentrations of VOCs in soil gas samples collected along the eastern fence-line were 41,128  $\mu\text{g}/\text{m}^3$  of TCE, 381  $\mu\text{g}/\text{m}^3$  of PCE, and 20,634  $\mu\text{g}/\text{m}^3$  of 1,1,1-TCA. The maximum concentrations of VOCs in the soil gas samples were 180,000  $\mu\text{g}/\text{m}^3$  of TCE, 1,200  $\mu\text{g}/\text{m}^3$  of PCE, and 90,000  $\mu\text{g}/\text{m}^3$  of 1,1,1-TCA (TtEC 2010).

### 1.3 Project Overview and Objective

The remedial objective for this project is to use an on-site soil vapor extraction system to prevent further off-site migration of VOC-contaminated soil vapor and to the extent practical, capture contaminated soil vapor with a TCE concentration greater than 250  $\mu\text{g}/\text{m}^3$ . A secondary objective of this project is to address soil vapor with a TCE concentration greater than 5  $\mu\text{g}/\text{m}^3$ . The SVECS is an interim action intended to address migration of VOCs in contaminated soil vapors. It is expected to operate continuously 24 hours/day, seven days/week, with the exception of maintenance and adjustment periods, until the remedial objectives are met (TtEC 2010).

### 1.4 SVECS Overview

The SVECS consists of soil vapor extraction, soil vapor monitoring, and soil vapor treatment. Twelve SVE wells (SVEWs) are located along the eastern boundary of Site 1 in six clusters, each consisting of one intermediate well and one deep well. Intermediate wells SVE-101I, SVE-102I, SVE-103I, SVE-104I, SVE-105I, and SVE-106I have a screened interval between 25 and 35 ft bgs. Deep wells SVE-101D, SVE-102D, SVE-103D, SVE-104D, SVE-105D, and SVE-106D have a screened interval between 40 and 60 ft bgs. The groundwater table fluctuates between approximately 50 and 55 feet bgs. Each SVEW is operated at a flow rate such that the combined total flow rate is approximately 300-400 standard cubic feet per minute (scfm) of soil vapor. Each intermediate depth SVEW requires an approximate vacuum of 4 inches of water column (i.w.) and each deep SVEW requires an approximate vacuum of 10 to 20 i.w. in order to extract the targeted flow rates. These twelve SVEWs have been piped below the ground to the Flow Monitoring Station (FMS), where flow, vacuum, and vapor quality are monitored. Within the FMS,

the discharges from the individual SVEWs have been equipped with a 2-inch flow control butterfly valve, a vacuum gauge, and a sampling port. The sampling port is utilized to measure the flow rate from an individual well using a portable velocity meter and to collect vapor samples. All the SVE lines collect into a single manifold within the FMS and from this location a single underground pipeline has been routed approximately 1,400 linear feet to the Treatment Building (Building 03-35). Five additional SVEWs (SV-107D, SV-108D, SV-109D, SV-110D, and SV-111D) were installed in October 2011 to address potential VOCs under Plant No. 3 and the South Warehouse. A site plan depicting well locations is included as **Figure 3**.

The SVECS is housed within the Treatment Building, an existing and unoccupied building also known as Building 03-35. The treatment system consists of a moisture separator, two SVE blowers, and a 5,000-lb vapor-phase granular activated carbon (VGAC) unit for removal of chlorinated VOCs from the off-gas. Soil vapor that enters the Treatment Building first passes through the moisture separator tank where any condensate is separated. To date, no condensate has formed in this tank. The vapor is then passed through an air filter and SVE blower and then treated in the VGAC unit. The treated vapor is discharged from the VGAC via an exhaust stack. The SVECS has a control panel comprised of mechanical interlocks and relays for local operation. A System Layout Plan is presented in **Figure 4**, which also illustrates the design flow rates through the soil vapor extraction and treatment process.

The off-gas from the SVECS is monitored for chlorinated VOCs as identified in the NYSDEC Division of Air Resources (DAR) permit equivalent effluent limitations and updated approval documentation (**Appendix A**) and monitoring requirements (TtEC 2010). Samples are submitted to a National Environmental Laboratory Accreditation Conference (NELAC)-accredited, Department of Defense (DoD) Environmental Laboratory Accreditation Program (ELAP)-certified laboratory, Air Toxics, Inc. located in Folsom, CA, for analysis of VOCs by modified method TO-15. Prior to January 2014, samples were analyzed for target compound list (TCL) VOCs. As of January 2014, upon approval by NYSDEC and NYSDOH, samples are analyzed for site-specific VOCs. The site-specific VOCs are: 1,1,1-TCA, 1,1-dichloroethane (DCA), 1,1-dichloroethene (DCE), 1,2-DCA, cis-1,2-DCE, PCE, trans-1,2-DCE, TCE, and vinyl chloride.

A total of 18 soil vapor pressure monitor (SVPM) / soil gas monitoring points have been installed in the neighborhood east of Site 1 at NWIRP Bethpage (**Figure 3**). These off-site monitoring points consist of eight previously existing SVPMs as well as 10 SVPMs installed in September 2012. Pressure readings from the SVPMs are collected quarterly and used to evaluate the SVECS vacuum field. In addition, analytical results of vapor samples collected annually from these locations and the pressure readings are used to further evaluate the SVECS operation and the potential for vapor intrusion.

## **2.0 SVECS OPERATION AND MAINTENANCE**

While designed to run autonomously, the SVECS requires regular visits by an operator to record and adjust operational parameters and to perform scheduled maintenance. The SVECS is equipped with telemetry that will alert an on-call operator in the event of a plant shutdown.

### **2.1 Routine Maintenance Activities**

Routine maintenance activities at the SVECS were performed during the operator's weekly visits during this reporting period. These activities include general site inspections (of the grounds, buildings, doors and locks), collection of operational data (vapor flowrates, pressures, vacuums, temperature and photoionization detector [PID] readings), adjustment of system valves, collection of vapor samples (on a monthly and quarterly basis), collection/disposal of condensate if needed, cleaning of filters, switching of lead/lag blower assignments, and preventive maintenance of system equipment.

In addition, the following routine maintenance task was also performed at the SVECS during this quarterly reporting period:

- On 21 January, a carbon changeout was performed on the VGAC unit.

### **2.2 Non-routine Maintenance / Site Activities**

The following non-routine activities / repair activities occurred at the SVECS during this quarterly reporting period:

- On 3 March, the roll-up door to the blower building was repaired.

### 3.0 SVECS MONITORING

Several process vapor samples are collected on a monthly basis to monitor the SVECS operation. These samples consist of an influent sample (as well as a duplicate sample), located immediately prior to the VGAC unit, and an effluent sample, located after the VGAC unit and before the exhaust stack. Vapor samples are also collected from the 12 original SVEWs on a quarterly basis to monitor the capture of the contaminated soil vapor by the SVEWs. In addition, quarterly pressure measurements are collected from the SVEWs and SVPs to monitor the SVECS vacuum field, and soil gas sampling for SVPs is conducted annually (generally in the winter time-frame) to evaluate the effectiveness of the SVECS. The first annual soil gas sampling event was conducted in the winter 2012-2013. The fourth annual sampling event was conducted in the winter 2015-2016; samples were collected from the 18 SVPs in January 2016, as discussed in Section 3.4 below.

#### 3.1 Monthly Air Quality Monitoring

Analysis of influent and effluent vapor sample locations is performed to evaluate VOC mass removal and the effectiveness of the VGAC adsorption unit. Time-integrated vapor samples are collected using 6-L summa canisters with 30-minute flow regulators.

Treated off-gas discharged at the exhaust stack is subject to emissions limitations. Initially, discharge goals were derived from calculations submitted by the Navy and approved by the NYSDEC DAR in February 2010. In September 2011, the Navy submitted an evaluation proposing revised discharge goals (TtNUS 2011), which NYSDEC approved in October 2011. A copy of this documentation is included as **Appendix A**.

A summary of monthly vapor sampling results collected in January, February, and March (First Quarter) is presented in **Tables 1, 2, and 3**, respectively. Emission rate calculations for both the influent stream (prior to VGAC treatment) and effluent stream (following VGAC treatment) and estimated monthly mass recoveries are also presented. Emission rates of the influent stream as well as mass recovery are calculated to monitor progress and determine when influent concentrations have reached levels at which vapor treatment via carbon adsorption is no longer required. The data presented in **Tables 1, 2, and 3** demonstrate that all constituents were within the effluent emission rate guidelines (**Appendix A**). Raw analytical data is provided under a separate cover.

#### 3.2 Quarterly Air Quality Monitoring of SVEWs

Time-integrated vapor samples are collected quarterly using 6-L summa canisters with 30-minute flow regulators at six intermediate and six deep SVE wells. The samples are collected for the purpose of tracking and documenting the performance of the SVECS (TtEC 2010).

Quarterly vapor samples were collected on 13 January from the 12 SVEWs. A summary of detected compounds is included as **Table 4**. Analytical results of select VOCs (1,1,1-TCA, PCE, and TCE) detected at the 12 SVEWs during the First Quarter monitoring event are presented graphically as

**Figure 5.** Raw analytical data is provided under a separate cover. Historical analytical results of quarterly vapor samples collected from December 2009 through the First Quarter 2016 are presented in **Table 5.**

### 3.3 Quarterly Soil Vapor Pressure Monitoring of SVEWs and Off-site SVPMS

Vacuum readings are collected quarterly from the 12 SVEWs and 18 SVPMS in order to monitor the SVECS vacuum field. Vacuum readings from the 18 SVPMS were collected both before and after the collection of soil gas samples from these locations, on 13 January and 14 January, respectively. Results of the First Quarter vapor monitoring are presented in **Table 6.**

Vacuum readings for the individual SVEWs provide an indication that a vacuum is being established along the fence line. During the First Quarter, the recorded vacuum measurements from the SVEWs ranged from 1.5 i.w. to 26.5 i.w.

As indicated in **Table 6,** vacuum measurements of the SVPMS ranged from 0.01 to 0.18 i.w. during the First Quarter monitoring event. These measurements indicate that a vacuum field continues to be maintained in the residential neighborhood adjacent to Site 1. Vacuum readings from the 18 SVPMS are presented graphically as **Figure 6.**

Historical results of quarterly vapor monitoring from Third Quarter 2012 through First Quarter 2016 are presented in **Table 7.**

### 3.4 Annual Vapor Quality Monitoring of Off-site SVPMS

Time-integrated vapor samples are collected annually using 6-L summa canisters with 30-minute flow regulators at 18 SVPMS locations.

#### 3.4.1 Vapor Quality Results

Annual vapor samples were collected on 14 January from the 18 SVPMS locations. Validated analytical results of samples collected in January 2016 are summarized in **Table 8.** As indicated, 1,1,1-TCA was detected at only one of the 18 locations, at a concentration of  $0.87 \text{ J } \mu\text{g}/\text{m}^3$  at SVPMS-2007D. PCE was detected at ten of the 18 locations, with concentrations ranging from  $0.83 \text{ J } \mu\text{g}/\text{m}^3$  at SVPMS-2004I to  $10 \mu\text{g}/\text{m}^3$  at SVPMS-2001D. TCE was detected at six of the 18 locations, with concentrations ranging from  $1.6 \text{ J } \mu\text{g}/\text{m}^3$  at SVPMS-2006S to  $48 \mu\text{g}/\text{m}^3$  (and a duplicate concentration of  $48 \mu\text{g}/\text{m}^3$ ) at SVPMS-2006I. All detected concentrations were well below the NYSDOH sub-slab screening values of  $1,000 \mu\text{g}/\text{m}^3$  for 1,1,1-TCA,  $1,000 \mu\text{g}/\text{m}^3$  for PCE, and  $250 \mu\text{g}/\text{m}^3$  for TCE.

Data validation reports and a validated analytical data summary are presented in **Appendix B.** Raw analytical data is provided under separate cover. Historical vapor quality analytical results collected from the 18 SVPMS locations, beginning in October 2008 and including the most recent results obtained in January 2016, are presented in **Table 9.**



### 3.4.2 Quality Assurance/Quality Control Sampling

Quality assurance/quality control (QA/QC) samples were collected during the annual off-site vapor monitoring event in accordance with the *Final Supplemental Offsite Soil Vapor Intrusion Monitoring Plan* (TtNUS 2012). These samples consisted of blind field duplicates (collected from SVPM-2002S and SVPM-2006I) and field blanks as ambient air samples.

For field blanks, ambient air samples were collected simultaneously during the soil gas sampling to evaluate potential chemicals in the local ambient air. The 6-L summa canister was positioned at an upwind location at a height of four feet above grade. The ambient air sample was obtained over an eight-hour period for each day that routine samples were collected.

For field duplicate samples, the precision between the original sample and its duplicate is evaluated by calculating the relative percent difference (RPD). RPDs for the First Quarter sampling event are presented in the data validation report in **Appendix B**. As indicated, RPDs for all analytes were below the guideline of 50% when calculated. The overall consistency between the samples and its duplicate verifies that proper sample collection methods were followed.

### 3.5 Soil Vapor Quality Concentration Trends

#### 3.5.1 Historical SVEW Vapor Quality Results and Concentration Trends

Historical vapor analytical results for the 12 SVEWs through the First Quarter are presented in **Table 5**. In addition, concentration trends of select VOCs over time for the SVECS combined influent (1,1,1-TCA, PCE, TCE, and total VOCs) and each of the 12 SVEWs (1,1,1-TCA, PCE, and TCE) are presented in **Appendix C**. Concentration trends observed in the 12 SVEWs through the First Quarter are discussed below.

- Combined Influent: Overall VOC concentrations in the combined influent decreased throughout the First Quarter, with total VOC concentrations of 3,696  $\mu\text{g}/\text{m}^3$ , 2,658  $\mu\text{g}/\text{m}^3$ , and 2,277  $\mu\text{g}/\text{m}^3$  in January, February, and March, respectively. Overall concentrations remain below baseline concentrations observed in December 2009 when a total VOC concentration of 63,650  $\mu\text{g}/\text{m}^3$  was observed.
- SV-101I: Concentrations observed at this location increased in the First Quarter from concentrations observed in the Fourth Quarter, with concentrations of 8,200  $\mu\text{g}/\text{m}^3$  TCE, 83  $\mu\text{g}/\text{m}^3$  PCE, and 2,700  $\mu\text{g}/\text{m}^3$  1,1,1-TCA. All concentrations remain below baseline concentrations observed in December 2009 (180,000  $\mu\text{g}/\text{m}^3$  TCE, 1,700  $\mu\text{g}/\text{m}^3$  PCE, and 51,000  $\mu\text{g}/\text{m}^3$  1,1,1-TCA).
- SV-101D: Concentrations observed at this location increased in the First Quarter from concentrations observed in the Fourth Quarter, with concentrations of 2,200  $\mu\text{g}/\text{m}^3$  TCE, 310  $\mu\text{g}/\text{m}^3$  PCE, and 27  $\mu\text{g}/\text{m}^3$  1,1,1-TCA. All concentrations remain below baseline concentrations observed in December 2009 (100,000  $\mu\text{g}/\text{m}^3$  TCE, 3,200  $\mu\text{g}/\text{m}^3$  PCE, and 26,000  $\mu\text{g}/\text{m}^3$  1,1,1-TCA).

- SV-102I: Concentrations observed at this location decreased in the First Quarter from concentrations observed in the Fourth Quarter, with concentrations of 12  $\mu\text{g}/\text{m}^3$  TCE, 2.4 J  $\mu\text{g}/\text{m}^3$  PCE, and 0.87 J  $\mu\text{g}/\text{m}^3$  1,1,1-TCA. The First Quarter concentrations are above baseline concentrations observed in December 2009 for TCE and 1,1,1-TCA and were similar for PCE (5.6  $\mu\text{g}/\text{m}^3$  TCE, 2.4  $\mu\text{g}/\text{m}^3$  PCE, and non-detectable 1,1,1-TCA). The concentrations, however, are below the peak concentrations observed in June 2010 (300  $\mu\text{g}/\text{m}^3$  TCE, 17  $\mu\text{g}/\text{m}^3$  PCE, and 13  $\mu\text{g}/\text{m}^3$  1,1,1-TCA).
- SV-102D: Concentrations observed at this location decreased slightly or remained similar in the First Quarter from concentrations observed in the Fourth Quarter, with concentrations of 120  $\mu\text{g}/\text{m}^3$  TCE, 42  $\mu\text{g}/\text{m}^3$  PCE, and 3.5 J  $\mu\text{g}/\text{m}^3$  of 1,1,1-TCA. Concentrations remain below baseline concentrations observed in December 2009 for TCE and 1,1,1-TCA (440  $\mu\text{g}/\text{m}^3$  TCE and 130  $\mu\text{g}/\text{m}^3$  1,1,1-TCA). The concentration of PCE is above the baseline concentration observed in December 2009 (10  $\mu\text{g}/\text{m}^3$  PCE) and is the maximum observed to date.
- SV-103I: Concentrations observed at this location increased or remained similar in the First Quarter from concentrations observed in the Fourth Quarter, with concentrations of 70  $\mu\text{g}/\text{m}^3$  TCE, 450  $\mu\text{g}/\text{m}^3$  PCE, and 1.2 J  $\mu\text{g}/\text{m}^3$  1,1,1-TCA. Concentrations remain below baseline concentrations observed in December 2009 (900  $\mu\text{g}/\text{m}^3$  TCE, 580  $\mu\text{g}/\text{m}^3$  PCE, and 900  $\mu\text{g}/\text{m}^3$  1,1,1-TCA).
- SV-103D: Concentrations observed at this location decreased in the First Quarter from concentrations observed in the Fourth Quarter, with non-detectable levels of TCE, PCE and 1,1,1-TCA, suggesting First Quarter results may not be indicative of actual conditions. All concentrations remain below baseline concentrations observed in December 2009 (3,100  $\mu\text{g}/\text{m}^3$  TCE, 20,000  $\mu\text{g}/\text{m}^3$  PCE, and 3,000  $\mu\text{g}/\text{m}^3$  1,1,1-TCA).
- SV-104I: Concentrations observed at this location decreased for TCE, increased for PCE, and remained similar for 1,1,1-TCA in the First Quarter compared to concentrations observed in the Fourth Quarter. Concentrations observed in the First Quarter were as follows: 35  $\mu\text{g}/\text{m}^3$  TCE, 79  $\mu\text{g}/\text{m}^3$  PCE, and 4.6  $\mu\text{g}/\text{m}^3$  1,1,1-TCA. Concentrations remain below baseline concentrations observed in December 2009 (710  $\mu\text{g}/\text{m}^3$  TCE, 3,100  $\mu\text{g}/\text{m}^3$  PCE, and 730  $\mu\text{g}/\text{m}^3$  1,1,1-TCA).
- SV-104D: Concentrations observed at this location decreased in the First Quarter from concentrations observed in the Fourth Quarter, with concentrations of 1,600  $\mu\text{g}/\text{m}^3$  TCE, 7,700  $\mu\text{g}/\text{m}^3$  PCE, and 760  $\mu\text{g}/\text{m}^3$  1,1,1-TCA. Concentrations remain below baseline concentrations observed in December 2009 (4,600  $\mu\text{g}/\text{m}^3$  TCE, 20,000  $\mu\text{g}/\text{m}^3$  PCE, and 3,600  $\mu\text{g}/\text{m}^3$  1,1,1-TCA).
- SV-105I: Concentrations observed at this location decreased in the First Quarter from concentrations observed in the Fourth Quarter, with concentrations of 84  $\mu\text{g}/\text{m}^3$  TCE, 44  $\mu\text{g}/\text{m}^3$  PCE, and 12  $\mu\text{g}/\text{m}^3$  1,1,1-TCA. Though these concentrations are above baseline concentrations observed in December 2009 for TCE and 1,1,1-TCA (76  $\mu\text{g}/\text{m}^3$  TCE and 9.9  $\mu\text{g}/\text{m}^3$  1,1,1-TCA), they are below peak concentrations observed in June 2010 for TCE, PCE, and 1,1,1-TCA (370  $\mu\text{g}/\text{m}^3$  TCE, 240  $\mu\text{g}/\text{m}^3$  PCE, and 29  $\mu\text{g}/\text{m}^3$  1,1,1-TCA).

- SV-105D: Concentrations observed at this location increased or were similar in the First Quarter from concentrations observed in the Fourth Quarter, with concentrations of 410  $\mu\text{g}/\text{m}^3$  TCE, 140  $\mu\text{g}/\text{m}^3$  PCE, and 62  $\mu\text{g}/\text{m}^3$  1,1,1-TCA. These concentrations are below baseline concentrations observed in December 2009 (1,700  $\mu\text{g}/\text{m}^3$  TCE, 2,100  $\mu\text{g}/\text{m}^3$  PCE, and 550  $\mu\text{g}/\text{m}^3$  1,1,1-TCA).
- SV-106I: Concentrations observed at this location decreased in the First Quarter from concentrations observed in the Fourth Quarter, with concentrations of 200  $\mu\text{g}/\text{m}^3$  TCE, 11  $\mu\text{g}/\text{m}^3$  PCE, and 2.8 J  $\mu\text{g}/\text{m}^3$  1,1,1-TCA. These concentrations are below baseline concentrations observed in December 2009 (1,900  $\mu\text{g}/\text{m}^3$  TCE, 390  $\mu\text{g}/\text{m}^3$  PCE, and 220  $\mu\text{g}/\text{m}^3$  1,1,1-TCA).
- SV-106D: Concentrations observed at this location increased in the First Quarter from concentrations observed in the Fourth Quarter, with concentrations of 280  $\mu\text{g}/\text{m}^3$  TCE, 33  $\mu\text{g}/\text{m}^3$  PCE, and 11  $\mu\text{g}/\text{m}^3$  1,1,1-TCA. These concentrations are below baseline concentrations observed in December 2009 (3,400  $\mu\text{g}/\text{m}^3$  TCE, 720  $\mu\text{g}/\text{m}^3$  PCE, and 340  $\mu\text{g}/\text{m}^3$  1,1,1-TCA).

### 3.5.2 Historical SVPM Vapor Quality Results and Concentration Trends

**Table 9** presents historical vapor quality analytical results collected from the 18 SVPM locations, beginning in October 2008 and including the most recent results obtained in January 2016. As indicated, concentrations observed in January 2016 have decreased substantially from initial concentrations observed in October 2008, and were generally similar to those observed in January 2015, with a few exceptions, as discussed in the *Concentration Trends Summary* below.

#### TCE Detection Summary

- In 2008, TCE was detected at all 18 locations, with concentrations ranging from 1.0  $\mu\text{g}/\text{m}^3$  (SVPM-2004S) to 89,000  $\mu\text{g}/\text{m}^3$  (SVPM-2002I); concentrations exceeded the NYSDOH sub-slab screening value of 250  $\mu\text{g}/\text{m}^3$  at nine locations (SVPM-2001S, SVPM-2001I, SVPM-2001D, SVPM-2002S, SVPM-2002I, SVPM-2002D, SVPM-2003D, SVPM-2004I, and SVPM-2004D).
- In 2013, TCE concentrations ranged from non-detectable levels at 12 locations to 47  $\mu\text{g}/\text{m}^3$  (SVPM-2006I), and no locations exceeded the NYSDOH sub-slab screening value of 250  $\mu\text{g}/\text{m}^3$ .
- In 2014, TCE was detected at nine of the 18 locations, with concentrations ranging from 0.73 J  $\mu\text{g}/\text{m}^3$  at SVPM-2003I to 3.7 J  $\mu\text{g}/\text{m}^3$  at SVPM-2004I and no locations exceeded the NYSDOH sub-slab screening value of 250  $\mu\text{g}/\text{m}^3$ .
- In 2015, TCE was detected at two of the 18 locations, with concentrations ranging from 1.5 J  $\mu\text{g}/\text{m}^3$  at SVPM-2004D to 30  $\mu\text{g}/\text{m}^3$  at SVPM-2006D, and no locations exceeded the NYSDOH sub-slab screening value of 250  $\mu\text{g}/\text{m}^3$ .
- In 2016, TCE was detected at six of the 18 locations, with concentrations ranging from 1.6 J  $\mu\text{g}/\text{m}^3$  at SVPM-2006S to 48  $\mu\text{g}/\text{m}^3$  (and a duplicate concentration of 48  $\mu\text{g}/\text{m}^3$ ) at SVPM-2006I, and no locations exceeded the NYSDOH sub-slab screening value of 250  $\mu\text{g}/\text{m}^3$ .

### PCE Detection Summary

- In 2008, PCE was detected at all 18 locations, with concentrations ranging from 1.8  $\mu\text{g}/\text{m}^3$  (SVPM-2004S) to 5,000  $\mu\text{g}/\text{m}^3$  (SVPM-2001I); concentrations exceeded the NYSDOH sub-slab screening value of 1,000  $\mu\text{g}/\text{m}^3$  at two locations (SVPM-2001S and SVPM-2001I).
- In 2013, PCE concentrations ranged from non-detectable levels at seven locations to 2.3 J  $\mu\text{g}/\text{m}^3$  (SVPM-2004D), and no locations exceeded the NYSDOH sub-slab screening value of 1,000  $\mu\text{g}/\text{m}^3$ .
- In 2014, PCE was detected at 15 of the 18 locations, with concentrations ranging from 0.53 J  $\mu\text{g}/\text{m}^3$  at SVPM-2001D to 2.9 J  $\mu\text{g}/\text{m}^3$  at SVPM-2004I, and no locations exceeded the NYSDOH sub-slab screening value of 1,000  $\mu\text{g}/\text{m}^3$ .
- In 2015, PCE was detected at three of the 18 locations, with concentrations ranging from 1.7 J  $\mu\text{g}/\text{m}^3$  at SVPM-2006D to 7.1  $\mu\text{g}/\text{m}^3$  at SVPM-2004D, and no locations exceeded the NYSDOH sub-slab screening value of 1,000  $\mu\text{g}/\text{m}^3$ .
- In 2016, PCE was detected at ten of the 18 locations, with concentrations ranging from 0.83 J  $\mu\text{g}/\text{m}^3$  at SVPM-2004I to 10  $\mu\text{g}/\text{m}^3$  at SVPM-2001D, and no locations exceeded the NYSDOH sub-slab screening value of 1,000  $\mu\text{g}/\text{m}^3$ .

### 1,1,1-TCA Detection Summary

- In 2008, 1,1,1-TCA was detected at all 18 locations, with concentrations ranging from 1.4  $\mu\text{g}/\text{m}^3$  (SVPM-2004S) to 52,000  $\mu\text{g}/\text{m}^3$  (SVPM-2002I); concentrations exceeded the NYSDOH sub-slab screening value of 1,000  $\mu\text{g}/\text{m}^3$  at six locations (SVPM-2001S, SVPM-2001I, SVPM-2001D, SVPM-2002S, SVPM-2002I, SVPM-2002D).
- In 2013, 1,1,1-TCA was detected at only one location, SVPM-2007D, at a concentration of 1.3 J  $\mu\text{g}/\text{m}^3$ , well below the NYSDOH sub-slab screening value of 1,000  $\mu\text{g}/\text{m}^3$ .
- In 2014, 1,1,1-TCA was not detected at any location.
- In 2015, 1,1,1-TCA was not detected at any location.
- In 2016, 1,1,1-TCA was detected at only one of the 18 locations, at a concentration of 0.87 J  $\mu\text{g}/\text{m}^3$  at SVPM-2007D, well below the NYSDOH sub-slab screening value of 1,000  $\mu\text{g}/\text{m}^3$ .

### Concentration Trends Summary

Concentration trends of select VOCs (1,1,1-TCA, PCE, and TCE) over time for each of the 18 SVPMs are presented in **Appendix D**. As indicated by the trend graphs and as discussed above, an overall decreasing trend was observed at a majority of the locations between October 2008 and January 2016, with a few exceptions. These exceptions include SVPM-2006I, SVPM-2006D, and to a lesser extent, SVPM-2001D.

- SVPM-2001D: Concentrations of TCE, PCE, and cis-1,2-DCE increased slightly in January 2016 (3.9 J  $\mu\text{g}/\text{m}^3$  TCE, 10  $\mu\text{g}/\text{m}^3$  PCE, and 6.3  $\mu\text{g}/\text{m}^3$  cis-1,2-DCE) from concentrations observed in January 2015 (non-detectable levels of TCE, PCE, and cis-1,2-DCE), but remain well below initial concentrations observed in October 2008 (1,500  $\mu\text{g}/\text{m}^3$  TCE, 720  $\mu\text{g}/\text{m}^3$  PCE, and 73  $\mu\text{g}/\text{m}^3$  cis-1,2-DCE).
- SVPM-2006I: Concentrations of TCE, PCE, and cis-1,2-DCE increased in January 2016 (48  $\mu\text{g}/\text{m}^3$  TCE, 2.2 J  $\mu\text{g}/\text{m}^3$  PCE, and 260  $\mu\text{g}/\text{m}^3$  cis-1,2-DCE) from concentrations observed in January 2015 (non-detectable levels of TCE, PCE, and cis-1,2-DCE). Concentrations of these three compounds in 2016 are above concentrations observed in January 2014 and are nearing or above concentrations observed in January 2013. Concentrations of 1,1,1-TCA were at non-detectable levels in 2013, 2014, 2015, and 2016. Though concentrations of TCE and PCE have recently increased, concentrations in January 2016 still remain below initial concentrations observed in October 2008 for TCE and PCE, as well as 1,1,1-TCA (71  $\mu\text{g}/\text{m}^3$  TCE, 29  $\mu\text{g}/\text{m}^3$  PCE, and 22  $\mu\text{g}/\text{m}^3$  1,1,1-TCA). However, the concentration of cis-1,2-DCE observed in January 2016 is above the initial concentration observed in October 2008 (45  $\mu\text{g}/\text{m}^3$  cis-1,2-DCE), though below the maximum concentration observed in January 2013 (340  $\mu\text{g}/\text{m}^3$  cis-1,2-DCE).
- SVPM-2006D: Concentrations of TCE, PCE, and cis-1,2-DCE increased in January 2016 (47  $\mu\text{g}/\text{m}^3$  TCE, 1.9 J  $\mu\text{g}/\text{m}^3$  PCE, and 320  $\mu\text{g}/\text{m}^3$  cis-1,2-DCE) from concentrations observed in January 2015 (30  $\mu\text{g}/\text{m}^3$  TCE, 1.7  $\mu\text{g}/\text{m}^3$  PCE, and 180  $\mu\text{g}/\text{m}^3$  cis-1,2-DCE). Concentrations of these three compounds in 2016 are also above concentrations observed in January 2013 and January 2014. Concentrations of 1,1,1-TCA were at non-detectable levels in 2013, 2014, 2015, and 2016. Though concentrations of TCE and PCE have recently increased, concentrations in January 2016 still remain below initial concentrations observed in October 2008 for TCE and PCE, as well as 1,1,1-TCA (61  $\mu\text{g}/\text{m}^3$  TCE, 11  $\mu\text{g}/\text{m}^3$  PCE, and 35  $\mu\text{g}/\text{m}^3$  1,1,1-TCA). However, the concentration of cis-1,2-DCE observed in January 2016 is above the initial concentration observed in October 2008 (89  $\mu\text{g}/\text{m}^3$  cis-1,2-DCE) and is the highest concentration observed at this location to date.

As shown on **Figure 3**, SVPM-2006I and SVPM-2006D are intermediate and deep wells, respectively, located along 10<sup>th</sup> Street, between Sycamore Avenue and Maple Avenue, to the east of the site. As mentioned above, recent data indicates increasing contaminant concentration trends at these locations, especially for cis-1,2-DCE, though all concentrations remain below the respective NYSDOH sub-slab screening values. The ratio of cis-1,2-DCE to other contaminants (e.g. TCE) at these SVPMs is considerably greater than at other locations to the north, south, or west of these SVPMs, suggesting a possible off-site source to the east of 10<sup>th</sup> Street. Concentrations at these locations will continue to be evaluated to determine if these recent trends continue.

## 4.0 CONCLUSIONS AND RECOMMENDATIONS

As stated previously, the intent of the Site 1 SVECS is to prevent further off-site migration of VOC contaminated soil vapor and to the extent practical, capture soil vapor with elevated TCE concentrations. Based on the presence of a vacuum field and the reduction of VOC concentrations to less than the screening values in the off-property area, the SVECS is functioning as designed. Influent vapor analytical data with concentrations of TCE greater than 250 µg/L indicate that the SVECS should continue to be operated on a full-time basis to achieve continued capture of contaminated soil vapor. Monthly monitoring of the combined influent and effluent as well as quarterly monitoring of individual SVEWs should continue. Quarterly and annual monitoring of the SVPMs should also continue in order to ensure that a measurable vacuum field is being established and that the area is being effectively treated. In order to effectively evaluate recent increasing concentration trends in SVPM-2006I and SVPM-2006D, an additional round of SVPM sampling in the summer / fall 2016 timeframe should be considered, prior to the next scheduled annual sampling event in January 2017.

## 5.0 REFERENCES

New York State Department of Health (NYSDOH). 2006. *Guidance for Evaluating Soil Vapor Intrusion in the State of New York*. October.

Tetra Tech EC, Inc. (TtEC). 2010. *Final Operation & Maintenance Plan for Soil Vapor Extraction Containment System, Site 1, Former Drum Marshalling Yard at Naval Weapons Industrial Reserve Plant, Bethpage, New York*. June.

Tetra Tech NUS, Inc. (TtNUS). 2011. *Modification to Existing Soil Vapor Extraction Containment System at Site 1 – Former Drum Marshalling Area, Installation of Soil Vapor Extraction Wells SVE-107D to -111D, NWIRP Bethpage, Bethpage, New York*. September.

TtNUS. 2012. *Final Supplemental Offsite Soil Vapor Intrusion Monitoring Plan for the Soil Vapor Extraction Containment System, Site 1, Former Drum Marshalling Yard at Naval Weapons Industrial Reserve Plant, Bethpage, New York*. February.

## **TABLES**



**Table 1**  
**Soil Vapor Extraction Containment System**  
**Site 1, Former Drum Marshalling Yard**  
**Naval Weapons Industrial Reserve Plant - Bethpage, NY**  
**Vapor Monitoring Results**  
**January 2016**

Compound	Concentration (ug/m <sup>3</sup> )				Emission Rate <sup>(1),(2)</sup>				Monthly Mass Recovery <sup>(3)</sup> (lbs)
	Influent #1	Influent #2	Average	Effluent	Prior to Treatment		Following Treatment		
					(lbs/hr)	(lbs/yr)	(lbs/hr)	(lbs/yr)	
1,1,1-Trichloroethane	350	340	345	140	0.0004	3.5511	0.0002	1.4410	0.2986
1,1-Dichloroethane	14	12	13	7.4	0.0000	0.1338	0.0000	0.0762	0.0113
1,1-Dichloroethene	0	0	0	0	0.0000	0.0000	0.0000	0.0000	0.0000
1,2-Dichloroethane	0	0	0	0	0.0000	0.0000	0.0000	0.0000	0.0000
cis-1,2-Dichloroethene	240	230	235	160	0.0003	2.4189	0.0002	1.6469	0.2034
Tetrachloroethene	1700	1700	1700	0	0.0020	17.4982	0.0000	0.0000	1.4712
trans-1,2-Dichloroethene	3.3 J	3.2 J	3.3 J	2.0 J	0.0000	0.0335	0.0000	0.0206	0.0028
Trichloroethene	1400	1400	1400	130	0.0016	14.4103	0.0002	1.3381	1.2116
Vinyl Chloride	0	0	0	0	0.0000	0.0000	0.0000	0.0000	0.0000
Total VOCs	3707	3685	3696	439	0.0043	38.0458	0.0005	4.5228	3.1987

**Notes:**

All samples were analyzed for site-specific VOCs by modified method TO-15.

Average Monthly Vapor Temp (°F) = 93  
Average Monthly Flowrate (cfm) = 329  
Average Monthly Flowrate (scfm) = 314  
Operational Hours for the month = 736.5

(1) Emissions (lbs/hr) = Concentration (ug/m<sup>3</sup>)\*(lb/454000000ug)\*(0.3048^3m<sup>3</sup>/ft<sup>3</sup>)\*exhaust flow (scfm)\*(60min/hour)

(2) Emissions (lbs/yr) = Emissions (lbs/hour)\*(8760hours/yr)

(3) Monthly Mass Removal = AVERAGE FLOWRATE (scfm) \* 0.3048^3m<sup>3</sup>/ft<sup>3</sup> \* INF AVG CONC (ug/m<sup>3</sup>) \* (lb/454000000ug) \* 60 min/hr \* OPERATIONAL TIME (hr)

**Table 2**  
**Soil Vapor Extraction Containment System**  
**Site 1, Former Drum Marshalling Yard**  
**Naval Weapons Industrial Reserve Plant - Bethpage, NY**  
**Vapor Monitoring Results**  
**February 2016**

Compound	Concentration (ug/m <sup>3</sup> )				Emission Rate <sup>(1),(2)</sup>				Monthly Mass Recovery <sup>(3)</sup> (lbs)
	Influent #1	Influent #2	Average	Effluent	Prior to Treatment		Following Treatment		
					(lbs/hr)	(lbs/yr)	(lbs/hr)	(lbs/yr)	
1,1,1-Trichloroethane	240	250	245	0	0.0003	2.4677	0.0000	0.0000	0.1955
1,1-Dichloroethane	14	14	14	0	0.0000	0.1410	0.0000	0.0000	0.0112
1,1-Dichloroethene	1.1 J	1.3 J	1.2 J	0	0.0000	0.0121	0.0000	0.0000	0.0010
1,2-Dichloroethane	0.71 J	0.95 J	0.83 J	0	0.0000	0.0084	0.0000	0.0000	0.0007
cis-1,2-Dichloroethene	190	200	195	0	0.0002	1.9641	0.0000	0.0000	0.1556
Tetrachloroethene	1200	1200	1200	0	0.0014	12.0868	0.0000	0.0000	0.9576
trans-1,2-Dichloroethene	2.3 J	2.5 J	2.4 J	0	0.0000	0.0242	0.0000	0.0000	0.0019
Trichloroethene	1000	1000	1000	1.4 J	0.0011	10.0723	0.0000	0.0141	0.7980
Vinyl Chloride	0	0	0	0	0.0000	0.0000	0.0000	0.0000	0.0000
Total VOCs	2648	2669	2658	1.4	0.0031	26.7766	0.0000	0.0141	2.1213

**Notes:**

All samples were analyzed for site-specific VOCs by modified method TO-15.

Average Monthly Vapor Temp (°F) = 94  
Average Monthly Flowrate (cfm) = 323  
Average Monthly Flowrate (scfm) = 307  
Operational Hours for the month = 694

(1) Emissions (lbs/hr) = Concentration (ug/m<sup>3</sup>) \* (lb/454000000ug) \* (0.3048^3m<sup>3</sup>/ft<sup>3</sup>) \* exhaust flow (scfm) \* (60min/hour)

(2) Emissions (lbs/yr) = Emissions (lbs/hour) \* (8760hours/yr)

(3) Monthly Mass Removal = AVERAGE FLOWRATE (scfm) \* 0.3048^3m<sup>3</sup>/ft<sup>3</sup> \* INF AVG CONC (ug/m<sup>3</sup>) \* (lb/454000000ug) \* 60 min/hr \* OPERATIONAL TIME (hr)

**Table 3**  
**Soil Vapor Extraction Containment System**  
**Site 1, Former Drum Marshalling Yard**  
**Naval Weapons Industrial Reserve Plant - Bethpage, NY**  
**Vapor Monitoring Results**  
**March 2016**

Compound	Concentration (ug/m <sup>3</sup> )				Emission Rate <sup>(1),(2)</sup>				Monthly Mass Recovery <sup>(3)</sup> (lbs)
	Influent #1	Influent #2	Average	Effluent	Prior to Treatment		Following Treatment		
					(lbs/hr)	(lbs/yr)	(lbs/hr)	(lbs/yr)	
1,1,1-Trichloroethane	220	200	210	0	0.0002	2.1147	0.0000	0.0000	0.1791
1,1-Dichloroethane	10	9.8	10	0	0.0000	0.0997	0.0000	0.0000	0.0084
1,1-Dichloroethene	0	0	0	0	0.0000	0.0000	0.0000	0.0000	0.0000
1,2-Dichloroethane	0	0.43 J	0.22 J	0	0.0000	0.0022	0.0000	0.0000	0.0002
cis-1,2-Dichloroethene	180	160	170	0	0.0002	1.7119	0.0000	0.0000	0.1450
Tetrachloroethene	1200	1100	1150	0	0.0013	11.5803	0.0000	0.0000	0.9809
trans-1,2-Dichloroethene	2.2 J	1.8 J	2.0 J	0	0.0000	0.0201	0.0000	0.0000	0.0017
Trichloroethene	770	700	735	0	0.0008	7.4014	0.0000	0.0000	0.6269
Vinyl Chloride	0	0	0	0	0.0000	0.0000	0.0000	0.0000	0.0000
Total VOCs	2382	2172	2277	0	0.0026	22.9302	0.0000	0.0000	1.9423

**Notes:**

All samples were analyzed for site-specific VOCs by modified method TO-15.

Average Monthly Vapor Temp (°F) = 100  
Average Monthly Flowrate (cfm) = 326  
Average Monthly Flowrate (scfm) = 307  
Operational Hours for the month = 742

(1) Emissions (lbs/hr) = Concentration (ug/m<sup>3</sup>) \* (lb/454000000ug) \* (0.3048^3m<sup>3</sup>/ft<sup>3</sup>) \* exhaust flow (scfm) \* (60min/hour)

(2) Emissions (lbs/yr) = Emissions (lbs/hour) \* (8760hours/yr)

(3) Monthly Mass Removal = AVERAGE FLOWRATE (scfm) \* 0.3048^3m<sup>3</sup>/ft<sup>3</sup> \* INF AVG CONC (ug/m<sup>3</sup>) \* (lb/454000000ug) \* 60 min/hr \* OPERATIONAL TIME (hr)

**Table 4**  
**Soil Vapor Extraction Containment System**  
**Site 1, Former Drum Marshalling Yard**  
**Naval Weapons Industrial Reserve Plant - Bethpage, NY**  
**First Quarter 2016 Vapor Analytical Results Summary of SVE Wells**

Sample ID	SVE 101I	SVE 101D	SVE 102I	SVE 102D	SVE 103I	SVE 103D	SVE 104I	SVE 104D	SVE 105I	SVE 105D	SVE 106I	SVE 106D
Sample Date	01/13/16	01/13/16	01/13/16	01/13/16	01/13/16	01/13/16	01/13/16	01/13/16	01/13/16	01/13/16	01/13/16	01/13/16
Analysis by TO-15 (µg/m <sup>3</sup> )												
1,1,1-Trichloroethane	2700	27	0.87 J	3.5 J	1.2 J	ND	4.6	760	12	62	2.8 J	11
1,1-Dichloroethane	45	2.3 J	ND	0.81 J	ND	ND	2.9 J	91	17	21	1.2 J	2.7 J
1,1-Dichloroethene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,2-Dichloroethane	9.0 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
cis-1,2-Dichloroethene	6.0 J	5.8	ND	8.9	13	ND	54	3200	17	18	3.2	3.2
Tetrachloroethene	83	310	2.4 J	42	450	ND	79	7700	44	140	11	33
trans-1,2-Dichloroethene	ND	ND	ND	ND	ND	ND	ND	38	ND	ND	ND	ND
Trichloroethene	8200	2200	12	120	70	ND	35	1600	84	410	200	280
Vinyl Chloride	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND

**Notes:**

All samples were analyzed for site-specific VOCs by modified method TO-15.

µg/m<sup>3</sup> = micrograms per cubic meter

ND = Not detected above method detection limit

Table 5  
 Soil Vapor Extraction Containment System  
 Site 1, Former Drum Marshalling Yard  
 Naval Weapons Industrial Reserve Plant - Bethpage, NY  
 Quarterly Vapor Monitoring Results of SVE Wells  
 Through First Quarter 2016

Sample ID	SVE 101I																									
Sample Date	12/21/09	03/31/10	06/09/10	09/16/10	12/08/10	03/30/11	06/28/11	09/06/11	10/14/11	02/10/12	05/11/12	09/11/12	12/05/12	01/15/13	05/16/13	08/27/13	11/08/13	01/30/14	04/10/14	07/29/14	10/02/14	01/12/15	05/07/15	08/12/15	10/29/15	01/13/16
Analysis by TO-15 (µg/m <sup>3</sup> )																										
1,1,1-Trichloroethane	51000	3900	2600	450	850	300	1	0.7 J	0.7 J	1500	1500	3200	4400	3400	1900	2200	2900	2600	1200	1600	2500	2000	720	520	2200	2700
1,1-Dichloroethane	1200	65	34	14	31	5	0.8 J	0.4 J	0.4 J	28	28	61	76	62	35	36	57	50	22	29	51	39	15	10	42	45
1,1-Dichloroethene	250	ND	ND	4	8	ND	0.7 J	0.4 J	0.5 J	7.6 J	10	ND	15 J	ND	12 J	8.9 J	16 J	11 J	7.9 J	6.2 J	21	11 J	ND	ND	ND	ND
1,2-Dichloroethane	NR	30	ND	4	8	ND	0.9	0.5 J	0.5 J	6.9 J	6.4 J	11 J	14 J	12 J	10 J	8.6 J	9.2 J	7.5 J	4.4 J	9.2 J	12 J	9.8 J	5.2 J	3.8	15	9.0 J
cis-1,2-Dichloroethene	480	59	ND	9	15	3	0.7 J	ND	0.4 J	7.1 J	7.4 J	20 J	22 J	14 J	6.2 J	11 J	22 J	12 J	4.2 J	8.8 J	24	9.4 J	4.6 J	3.8	9.2 J	6.0 J
Tetrachloroethene	1700	410	260	36	63	10	1	ND	2	48	46	93	120	80	49	79	100	80	34	67	83	54	31	31	74	83
trans-1,2-Dichloroethene	ND	ND	ND	ND	ND	ND	0.7 J	0.4 J	0.4 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Trichloroethene	180000	18000	14000	1200	2400	560	1	0.6 J	0.6 J	4200	4300	7200	12000	8100	5200	5400	8900	7100	3300	4400	6900	5300	2500	1600	7600	8200
Vinyl Chloride	ND	ND	ND	ND	ND	ND	0.5 J	0.3 J	0.3 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND

**Notes:**

µg/m<sup>3</sup> = micrograms per cubic meter

NR = Not Recorded

NA = Data not available

ND = Not detected above method

detection limit

Table 5  
 Soil Vapor Extraction Containment System  
 Site 1, Former Drum Marshalling Yard  
 Naval Weapons Industrial Reserve Plant - Bethpage, NY  
 Quarterly Vapor Monitoring Results of SVE Wells  
 Through First Quarter 2016

Sample ID	SVE 101D																									
	12/21/09	03/31/10	06/09/10	09/16/10	12/22/10	03/30/11	06/28/11	09/06/11	10/14/11	02/10/12	05/11/12	09/11/12	12/05/12	01/15/13	05/16/13	08/27/13	11/08/13	01/30/14	04/10/14	07/29/14	10/02/14	01/12/15	05/07/15	08/12/15	10/29/15	01/13/16
Analysis by TO-15 (µg/m <sup>3</sup> )																										
1,1,1-Trichloroethane	26000	130	53	ND	ND	ND	3	8	0.8 J	ND	3.1 J	9.9	11	ND	ND	5.6	16	14	12	20	19	12	ND	22	22	27
1,1-Dichloroethane	660	3.9	ND	ND	ND	ND	2	0.9 J	0.5 J	ND	ND	1.0 J	1.1 J	1.1 J	ND	ND	1.5 J	1.4 J	1.2 J	0.89 J	1.4 J	ND	ND	2.5 J	2.8 J	2.3 J
1,1-Dichloroethene	180	2	ND	ND	ND	ND	ND	0.7 J	0.4 J	ND	ND	ND	ND	ND	ND	ND	1.0 J	0.75 J	ND	ND	ND	ND	ND	ND	ND	ND
1,2-Dichloroethane	NR	0.5	ND	ND	ND	ND	2	0.5 J	0.5 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
cis-1,2-Dichloroethene	220	8.5	7.5	ND	3	ND	2	2	0.5 J	ND	ND	2.1 J	3.2	ND	ND	ND	3.0 J	4.5	3.5	1.5 J	4.1	2.3 J	ND	3.3	5.9	5.8
Tetrachloroethene	3200	1200	1200	ND	4	ND	26	210	2	ND	79	150	170	130	0.92 J	73	330	340	270	240	260	200	1.0 J	230	250	310
trans-1,2-Dichloroethene	ND	ND	ND	ND	ND	ND	2	0.6 J	0.4 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Trichloroethene	100000	1600	310	3	1	ND	3	120	1 J	ND	200	400	350	120	ND	56	540	680	330	180	410	190	1.7 J	450	1000	2200
Vinyl Chloride	ND	ND	ND	ND	ND	ND	1	0.4 J	0.3 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND

**Notes:**

µg/m<sup>3</sup> = micrograms per cubic meter

NR = Not Recorded

NA = Data not available

ND = Not detected above method

detection limit

Table 5  
 Soil Vapor Extraction Containment System  
 Site 1, Former Drum Marshalling Yard  
 Naval Weapons Industrial Reserve Plant - Bethpage, NY  
 Quarterly Vapor Monitoring Results of SVE Wells  
 Through First Quarter 2016

Sample ID	SVE 102I																									
	12/21/09	03/31/10	06/09/10	09/16/10	12/22/10	03/30/11	06/28/11	09/06/11	10/14/11	02/10/12	05/11/12	09/11/12	12/05/12	01/15/13	05/16/13	08/27/13	11/08/13	02/05/14	04/10/14	07/29/14	10/02/14	01/12/15	05/07/15	08/12/15	10/29/15	01/13/16
Analysis by TO-15 (µg/m <sup>3</sup> )																										
1,1,1-Trichloroethane	ND	ND	13	3	ND	NA	2	3	2	ND	0.60 J	3.3 J	ND	ND	ND	1.6 J	ND	ND	0.95 J	10	4.0 J	0.82 J	1.6 J	12	2.8 J	0.87 J
1,1-Dichloroethane	ND	ND	ND	ND	ND	NA	0.8 J	0.5 J	0.5 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,1-Dichloroethene	ND	ND	ND	ND	ND	NA	0.7 J	0.4 J	0.4 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,2-Dichloroethane	NR	ND	ND	ND	ND	NA	0.8	0.4 J	0.4 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
cis-1,2-Dichloroethene	ND	ND	ND	ND	ND	NA	0.7 J	0.5 J	0.5 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Tetrachloroethene	2.4	1.4	17	6	NR	NA	3	6	6	ND	1.6 J	6.4	1.5 J	2.4 J	1.4 J	3.3 J	2.6 J	ND	ND	10	4.8 J	1.5 J	2.5 J	13	6.6	2.4 J
trans-1,2-Dichloroethene	ND	ND	ND	ND	ND	NA	0.7 J	0.4 J	0.4 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Trichloroethene	5.6	3.8	300	88	3	NA	34	76	52	10	26	99	10	10	15	49	21	7.6	8.0	84	39	8.0	22	120	40	12
Vinyl Chloride	ND	ND	ND	ND	ND	NA	0.5 J	0.4 J	0.3 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND

**Notes:**

µg/m<sup>3</sup> = micrograms per cubic meter

NR = Not Recorded

NA = Data not available

ND = Not detected above method

detection limit

Table 5  
 Soil Vapor Extraction Containment System  
 Site 1, Former Drum Marshalling Yard  
 Naval Weapons Industrial Reserve Plant - Bethpage, NY  
 Quarterly Vapor Monitoring Results of SVE Wells  
 Through First Quarter 2016

Sample ID	SVE 102D																									
	12/21/09	03/31/10	06/09/10	09/16/10	12/08/10	03/30/11	06/28/11	09/06/11	10/14/11	02/10/12	05/11/12	09/11/12	12/05/12	01/15/13	05/16/13	08/27/13	11/08/13	01/30/14	04/24/14	07/29/14	10/02/14	01/12/15	05/07/15	08/12/15	10/29/15	01/13/16
Analysis by TO-15 (µg/m <sup>3</sup> )																										
1,1,1-Trichloroethane	130	53	14	7	2	2	6	4	5	1.4 J	1.2 J	3.9 J	ND	ND	ND	2.3 J	3.1 J	ND	1.6 J	4.5	5.1	2.6 J	ND	5.2	4.9	3.5 J
1,1-Dichloroethane	ND	2.7	ND	ND	ND	ND	1	0.6 J	0.7 J	ND	ND	0.51 J	0.95 J	ND	ND	ND	0.69 J	ND	0.44 J	ND	ND	ND	ND	ND	1.0 J	0.81 J
1,1-Dichloroethene	ND	ND	ND	ND	ND	ND	1	0.6 J	0.6 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,2-Dichloroethane	NR	ND	ND	ND	ND	ND	0.9	0.5 J	0.5 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	0.38 J	ND	ND	ND	ND	ND
cis-1,2-Dichloroethene	ND	1.4	ND	ND	0.9	ND	1	0.5 J	0.9	ND	ND	1.1 J	4.1	ND	ND	ND	3.4	ND	2.8 J	0.89 J	3.6	1.6 J	ND	4.2	9.3	8.9
Tetrachloroethene	10	31	31	19	3	9	25	23	39	5.9	6.5	24	25	0.96 J	1.4 J	14	28	2.6 J	9.6	16	20	11	3.8 J	22	41	42
trans-1,2-Dichloroethene	ND	ND	ND	ND	ND	ND	1	0.5 J	0.5 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Trichloroethene	440	390	190	110	17	21	89	81	87	34	58	170	140	6.5	ND	88	160	3.9 J	39	79	92	36	20	160	180	120
Vinyl Chloride	ND	ND	ND	ND	ND	ND	0.6	0.4 J	0.3 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND

**Notes:**

µg/m<sup>3</sup> = micrograms per cubic meter

NR = Not Recorded

NA = Data not available

ND = Not detected above method

detection limit



Table 5  
 Soil Vapor Extraction Containment System  
 Site 1, Former Drum Marshalling Yard  
 Naval Weapons Industrial Reserve Plant - Bethpage, NY  
 Quarterly Vapor Monitoring Results of SVE Wells  
 Through First Quarter 2016

Sample ID	SVE 103I																									
	12/21/09	03/31/10	06/09/10	09/16/10	12/08/10	03/30/11	06/28/11	09/06/11	10/14/11	02/10/12	05/11/12	09/11/12	12/05/12	01/15/13	05/16/13	08/27/13	11/08/13	01/30/14	04/10/14	07/29/14	10/02/14	01/12/15	05/07/15	08/12/15	10/29/15	01/13/16
Analysis by TO-15 (µg/m <sup>3</sup> )																										
1,1,1-Trichloroethane	900	ND	ND	ND	ND	ND	0.9 J	6	6	ND	1.6 J	9.2	ND	ND	1.4 J	4.7 J	2.8 J	0.92 J	ND	4.6	4.9	ND	1.3 J	6.6	3.6 J	1.2 J
1,1-Dichloroethane	26	ND	ND	ND	ND	ND	0.6 J	2	2	ND	0.75 J	1.5 J	0.77 J	ND	ND	1.5 J	1.3 J	ND	ND	0.89 J	2.0 J	ND	0.68 J	ND	1.4 J	ND
1,1-Dichloroethene	ND	ND	ND	ND	ND	ND	0.6 J	0.6 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,2-Dichloroethane	NR	ND	ND	ND	ND	ND	0.7 J	0.5 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
cis-1,2-Dichloroethene	58	ND	ND	1	ND	1	0.5 J	16	12	18	16	19	6.0	2.4 J	5.0	11	15	6.9	3.4	4.2	6.1	ND	11	9.3	7.3	13
Tetrachloroethene	580	ND	ND	ND	ND	2	1 J	420	590	140	200	430	120	40	78	220	200	97	40	150	130	8.6	130	290	210	450
trans-1,2-Dichloroethene	580	ND	ND	ND	ND	ND	0.6 J	1	1	ND	ND	ND	ND	ND	ND	ND	0.85 J	ND	ND	ND	ND	ND	ND	ND	ND	ND
Trichloroethene	900	0.9	ND	ND	ND	ND	0.9 J	100	97	29	47	130	48	16	35	95	78	46	20	47	50	4.9 J	37	92	74	70
Vinyl Chloride	ND	ND	ND	ND	ND	ND	0.4 J	0.4 J	0.3 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND

**Notes:**

µg/m<sup>3</sup> = micrograms per cubic meter

NR = Not Recorded

NA = Data not available

ND = Not detected above method

detection limit

Table 5  
 Soil Vapor Extraction Containment System  
 Site 1, Former Drum Marshalling Yard  
 Naval Weapons Industrial Reserve Plant - Bethpage, NY  
 Quarterly Vapor Monitoring Results of SVE Wells  
 Through First Quarter 2016

Sample ID	SVE 103D																									
	12/21/09	03/31/10	06/09/10	09/16/10	12/08/10	03/30/11	06/28/11	09/06/11	10/14/11	02/10/12	05/11/12	09/11/12	12/05/12	01/15/13	05/16/13	08/27/13	11/08/13	01/30/14	04/10/14	07/29/14	10/02/14	01/12/15	05/07/15	08/12/15	10/29/15	01/13/16
Analysis by TO-15 (µg/m <sup>3</sup> )																										
1,1,1-Trichloroethane	3000	1100	230	ND	13	ND	2 J	20	31	7.4 J	6.9 J	22	190	ND	150	170	200	550	400	25	38	ND	310	26	30 J	ND
1,1-Dichloroethane	82	69	ND	ND	2	2	1 J	4	9	1.6 J	1.5 J	1.9 J	10 J	ND	10	10 J	20 J	50	48	ND	7.8 J	ND	24	ND	ND	ND
1,1-Dichloroethene	ND	ND	ND	ND	ND	ND	1 J	2	6 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,2-Dichloroethane	NR	ND	ND	ND	ND	ND	1 J	1 J	6 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
cis-1,2-Dichloroethene	420	1500	370	ND	92	ND	1 J	360	160	290	230	300	750	ND	550	700	2600	2100	1800	280	490	ND	930	310	530	ND
Tetrachloroethene	20000	28000	16000	9	1500	ND	3	1600	6700	3800	3200	4700	4600	1.6 J	3300	4900	17000	15000	8600	6600	8900	ND	5800	8900	17000	ND
trans-1,2-Dichloroethene	ND	24	ND	ND	1	ND	1 J	3	7 J	ND	ND	ND	8.8 J	ND	5.7 J	8.8 J	18 J	32	18	ND	ND	ND	17	ND	ND	ND
Trichloroethene	3100	1600	640	7	92	ND	2 J	290	240	180	200	480	440	6.0	360	660	2100	1400	900	530	680	ND	580	640	1200	ND
Vinyl Chloride	ND	5.9	ND	ND	2	ND	0.8 J	4	5 J	ND	ND	ND	ND	ND	1.9 J	ND	14 J	ND	2.6 J	ND	ND	ND	ND	ND	ND	ND

**Notes:**

µg/m<sup>3</sup> = micrograms per cubic meter

NR = Not Recorded

NA = Data not available

ND = Not detected above method

detection limit

Table 5  
 Soil Vapor Extraction Containment System  
 Site 1, Former Drum Marshalling Yard  
 Naval Weapons Industrial Reserve Plant - Bethpage, NY  
 Quarterly Vapor Monitoring Results of SVE Wells  
 Through First Quarter 2016

Sample ID	SVE 104I																									
Sample Date	12/21/09	03/31/10	06/09/10	09/16/10	12/08/10	03/30/11	06/28/11	09/06/11	10/14/11	02/10/12	05/11/12	09/11/12	12/05/12	01/15/13	05/16/13	08/27/13	11/08/13	01/30/14	04/24/14	07/29/14	10/02/14	01/12/15	05/07/15	08/12/15	10/29/15	01/13/16
Analysis by TO-15 (µg/m <sup>3</sup> )																										
1,1,1-Trichloroethane	730	4.2	ND	4	NR	NA	1 J	4	2	ND	ND	8.3	ND	ND	ND	3.1 J	2.6 J	ND	9.6	17	15	7.0	1.5 J	8.3	4.0 J	4.6
1,1-Dichloroethane	24	0.54	ND	ND	ND	NA	1 J	0.6 J	0.5 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	7.4	8.7	7.7	6.6	ND	ND	ND	2.9 J
1,1-Dichloroethene	ND	ND	ND	ND	ND	NA	1 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,2-Dichloroethane	NR	ND	ND	ND	ND	NA	1 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
cis-1,2-Dichloroethene	110	14	ND	2	0.8	NA	0.9 J	2	3	0.90 J	ND	5.0	ND	2.7 J	ND	3.3	5.3	ND	94	160	160	130	7.3	4.2	6.6	54
Tetrachloroethene	3100	210	68	96	16	NA	2 J	54	33	12	ND	86	1.6 J	4.8 J	2.3 J	30	36	ND	69	210	190	91	13	82	66	79
trans-1,2-Dichloroethene	15	ND	ND	ND	ND	NA	1 J	0.5 J	0.4 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	1.8 J	2.1 J	1.4 J	ND	ND	ND	ND
Trichloroethene	710	44	60	72	12	NA	2 J	44	25	9.6	ND	73	ND	3.1 J	ND	30	31	ND	39	110	120	43	17	85	54	35
Vinyl Chloride	ND	0.47	ND	ND	ND	NA	0.7 J	0.3 J	0.3 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND

**Notes:**

µg/m<sup>3</sup> = micrograms per cubic meter

NR = Not Recorded

NA = Data not available

ND = Not detected above method

detection limit

Table 5  
 Soil Vapor Extraction Containment System  
 Site 1, Former Drum Marshalling Yard  
 Naval Weapons Industrial Reserve Plant - Bethpage, NY  
 Quarterly Vapor Monitoring Results of SVE Wells  
 Through First Quarter 2016

Sample ID	SVE 104D																									
	12/21/09	03/31/10	06/09/10	09/16/10	12/22/10	03/30/11	06/28/11	09/06/11	10/14/11	02/10/12	05/11/12	09/11/12	12/05/12	01/15/13	05/16/13	08/27/13	11/08/13	01/30/14	04/10/14	07/29/14	10/02/14	01/12/15	05/07/15	08/12/15	10/29/15	01/13/16
Analysis by TO-15 (µg/m <sup>3</sup> )																										
1,1,1-Trichloroethane	3600	3000	860	ND	270	ND	370	620	440	520	580	620	920	820	0.89 J	500	600	340	84	930	880	1.7 J	350	480	790	760
1,1-Dichloroethane	290	350	140	ND	66	ND	56	110	77	87	95	100	190	160	ND	95	130	56	22	120	130	ND	72	77	120	91
1,1-Dichloroethene	ND	ND	ND	ND	ND	ND	3	7 J	7 J	3.0 J	5.0 J	ND	11 J	ND	ND	ND	ND	4.3 J	1.0 J	ND	ND	ND	ND	ND	ND	
1,2-Dichloroethane	NR	ND	ND	ND	ND	ND	1 J	5 J	5 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	
cis-1,2-Dichloroethene	2400	6600	3500	ND	1200	ND	1000	3600	2100	2200	2800 J	2200	4200	3700	8.6	2000	3200	1600	460	3300	4400	21	1500	2500	3600	3200
Tetrachloroethene	20000	39000	21000	ND	2400	ND	1400	5800	6300	3800	4300	4600	4500	4200	69	2600	3900	2500	780	8200	8000	120	2200	5100	10000	7700
trans-1,2-Dichloroethene	130	70	30	ND	13	ND	14	25	22	26	31	27	55	40	ND	24	40	15	3.5	34	53	ND	18	39	49	38
Trichloroethene	4600	6000	2400	ND	470	ND	420	1600	1300	1400	1400	1700	2300	2100	14	1200	1600	1100	430	2000	2100	19	1100	1200	2200	1600
Vinyl Chloride	ND	12	ND	ND	ND	ND	2	5	5 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	

**Notes:**

µg/m<sup>3</sup> = micrograms per cubic meter

NR = Not Recorded

NA = Data not available

ND = Not detected above method

detection limit

Table 5  
 Soil Vapor Extraction Containment System  
 Site 1, Former Drum Marshalling Yard  
 Naval Weapons Industrial Reserve Plant - Bethpage, NY  
 Quarterly Vapor Monitoring Results of SVE Wells  
 Through First Quarter 2016

Sample ID	SVE 105I																									
	12/21/09	03/31/10	06/09/10	09/16/10	12/08/10	03/30/11	06/28/11	09/06/11	10/14/11	02/10/12	05/11/12	09/11/12	12/05/12	01/15/13	05/16/13	08/27/13	11/08/13	01/30/14	04/10/14	07/29/14	10/02/14	01/12/15	05/07/15	08/12/15	10/29/15	01/13/16
Analysis by TO-15 (µg/m <sup>3</sup> )																										
1,1,1-Trichloroethane	9.9	11	29	ND	24	1	1 J	21	31	11	13	26	22	22	11	24	18	32	26	17	20	20	25	29	30	12
1,1-Dichloroethane	ND	5.7	13	ND	6	ND	0.6 J	5	7	4.2	5.6	5.6	10	12	8.8	8.0	7.4	24	6.8	7.0	8.2	8.6	22	15	28	17
1,1-Dichloroethene	ND	ND	ND	ND	ND	ND	0.6 J	0.6 J	0.5 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,2-Dichloroethane	NR	ND	ND	ND	ND	ND	0.7 J	0.6 J	0.5 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
cis-1,2-Dichloroethene	ND	6.6	20	ND	ND	ND	1	10	16	8.1	9.7	13	16	13	14	14	7.4	17	6.2	9.5	12	7.5	31	28	23	17
Tetrachloroethene	70	9.1	240	ND	55	5	2	95	100	31	43	100	77	66	38	91	57	77	48	73	85	51	43	87	66	44
trans-1,2-Dichloroethene	ND	ND	1.6	ND	ND	ND	0.5 J	1	1	ND	ND	1.5 J	ND	ND	ND	ND	1.0 J	1.6 J	ND	ND	2.8 J	ND	ND	ND	2.3 J	ND
Trichloroethene	76	6.3	370	ND	120	7	1	170	200	110	140	260	180	160	94	220	140	180	190	140	200	130	160	290	240	84
Vinyl Chloride	ND	ND	ND	ND	ND	ND	0.4 J	0.4 J	0.3 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND

**Notes:**

µg/m<sup>3</sup> = micrograms per cubic meter

NR = Not Recorded

NA = Data not available

ND = Not detected above method

detection limit

Table 5  
 Soil Vapor Extraction Containment System  
 Site 1, Former Drum Marshalling Yard  
 Naval Weapons Industrial Reserve Plant - Bethpage, NY  
 Quarterly Vapor Monitoring Results of SVE Wells  
 Through First Quarter 2016

Sample ID	SVE 105D																									
	12/21/09	03/31/10	06/09/10	09/16/10	12/08/10	03/30/11	06/28/11	09/06/11	12/02/11	02/10/12	05/11/12	09/11/12	12/05/12	01/15/13	05/16/13	08/27/13	11/08/13	01/30/14	04/10/14	07/29/14	10/02/14	01/12/15	05/07/15	08/12/15	10/29/15	01/13/16
Analysis by TO-15 (µg/m <sup>3</sup> )																										
1,1,1-Trichloroethane	550	47	320	1000	590	ND	1 J	490	930	350	320	270	380	430	160	110	120	190	ND	92	79	4.3 J	16	35	52	62
1,1-Dichloroethane	300	28	270	250	ND	ND	0.6 J	74	150	69	78	72	110	110	46	45	70	46	ND	36	28	ND	4.7	12	30	21
1,1-Dichloroethene	3.9	ND	ND	2	4	4	0.6 J	6 J	ND	ND	ND	ND	ND	ND	ND	ND	1.5 J	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,2-Dichloroethane	NR	ND	ND	ND	ND	ND	4	5 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
cis-1,2-Dichloroethene	61	36	85	300	ND	ND	0.7 J	150	380	190	220	150	210	200	73	76	85	46	ND	50	36	ND	3.6	16	22	18
Tetrachloroethene	2100	1.1	650	270	420	ND	2	240	330	140	220	270	350	330	100	140	260	300	ND	140	120	2.1 J	18	76	130	140
trans-1,2-Dichloroethene	19	1.1	3.1	3	ND	ND	0.6 J	7 J	3 J	ND	ND	ND	ND	ND	1.4 J	2.4 J	3.6	1.3 J	ND	1.3 J	1.9 J	ND	ND	ND	ND	ND
Trichloroethene	1700	68	200	1100	1400	1	2	3000	7000	3600	4500	2200	3800	3800	1400	900	1200	1900	8.5	650	520	15	75	250	400	410
Vinyl Chloride	ND	ND	ND	ND	ND	ND	0.4 J	4 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND

**Notes:**

µg/m<sup>3</sup> = micrograms per cubic meter

NR = Not Recorded

NA = Data not available

ND = Not detected above method

detection limit

Table 5  
 Soil Vapor Extraction Containment System  
 Site 1, Former Drum Marshalling Yard  
 Naval Weapons Industrial Reserve Plant - Bethpage, NY  
 Quarterly Vapor Monitoring Results of SVE Wells  
 Through First Quarter 2016

Sample ID	SVE 106I																									
	12/21/09	03/31/10	06/09/10	09/16/10	12/08/10	03/30/11	06/28/11	09/06/11	10/14/11	02/10/12	05/11/12	09/11/12	12/05/12	01/15/13	05/16/13	08/27/13	11/08/13	01/30/14	04/10/14	07/29/14	10/02/14	01/12/15	05/07/15	08/12/15	10/29/15	01/13/16
Analysis by TO-15 (µg/m <sup>3</sup> )																										
1,1,1-Trichloroethane	220	8.6	ND	4	ND	NA	6	3	7	1.0 J	2.2 J	11	ND	ND	ND	ND	18	1.4 J	3.8 J	8.9	2.2 J	ND	8.0	29	30	2.8 J
1,1-Dichloroethane	120	ND	ND	1	ND	NA	1	0.5 J	1	0.62 J	0.70 J	1.6 J	2.5 J	1.9 J	ND	ND	3.8	ND	17	3.9	1.1 J	ND	18	2.6 J	3.4	1.2 J
1,1-Dichloroethene	ND	ND	ND	ND	ND	NA	0.6 J	2	0.6 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,2-Dichloroethane	NR	ND	ND	0.8	ND	NA	0.6 J	0.5 J	0.6 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	1.3 J	ND	ND	ND
cis-1,2-Dichloroethene	46	ND	ND	4	ND	NA	6	0.5 J	4	1.6 J	2.3 J	7.5	5.4	3.7	ND	ND	8.3	ND	23	11	3.1 J	ND	23	6.6	4.9	3.2
Tetrachloroethene	390	35	ND	15	ND	NA	15	7	19	4.3 J	7.2	27	14	7.0	0.73 J	ND	19	4.2 J	6.2	11	2.9 J	ND	14	39	49	11
trans-1,2-Dichloroethene	7.9	ND	3.1	0.9	ND	NA	0.8	0.5 J	0.7 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Trichloroethene	1900	41	ND	140	10	NA	210	92	190	69	110	260	180	110	5.5	ND	210	28	70	110	16	0.87 J	130	560	660	200
Vinyl Chloride	ND	ND	ND	0.5	ND	NA	0.4 J	0.3 J	0.4 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND

**Notes:**

µg/m<sup>3</sup> = micrograms per cubic meter

NR = Not Recorded

NA = Data not available

ND = Not detected above method

detection limit

Table 5  
 Soil Vapor Extraction Containment System  
 Site 1, Former Drum Marshalling Yard  
 Naval Weapons Industrial Reserve Plant - Bethpage, NY  
 Quarterly Vapor Monitoring Results of SVE Wells  
 Through First Quarter 2016

Sample ID	SVE 106D																									
	12/21/09	03/31/10	06/09/10	09/16/10	12/08/10	03/30/11	06/28/11	09/06/11	10/14/11	02/10/12	05/11/12	09/11/12	12/05/12	01/15/13	05/16/13	08/27/13	11/08/13	01/30/14	04/10/14	07/29/14	10/02/14	01/12/15	05/07/15	08/12/15	10/29/15	01/13/16
Analysis by TO-15 (µg/m <sup>3</sup> )																										
1,1,1-Trichloroethane	340	32	30	20	12	9	20	23	29	ND	11	26	18	ND	ND	27	25	5.8	6.3	14	28	ND	26	ND	ND	11
1,1-Dichloroethane	250	6.3	ND	5	2	5	4	3	3	ND	3.0	4.3	5.8	ND	ND	4.9	11	3.7	3.3	5.1	8.9	ND	2.6 J	ND	ND	2.7 J
1,1-Dichloroethene	ND	ND	ND	ND	ND	ND	0.5 J	0.7 J	0.8	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,2-Dichloroethane	NR	ND	ND	ND	ND	ND	ND	0.6 J	0.7 J	ND	ND	ND	ND	ND	ND	ND	2.5 J	ND	ND	ND	1.1 J	ND	ND	ND	ND	ND
cis-1,2-Dichloroethene	79	13	11	13	2	11	11	5	4	ND	4.1	7.1	8.2	ND	ND	10	15	2.8 J	3.9	8.4	15	ND	36	ND	ND	3.2
Tetrachloroethene	720	65	70	ND	13	19	41	8	66	ND	28	62	48	ND	1.3 J	50	58	16	17	22	60	ND	110	ND	1.4 J	33
trans-1,2-Dichloroethene	15	ND	ND	ND	ND	ND	0.6 J	0.8	0.9	ND	ND	ND	ND	ND	ND	ND	1.1 J	ND	ND	ND	ND	ND	ND	ND	ND	ND
Trichloroethene	3400	600	900	230	130	170	210	260	320	ND	180	380	300	ND	ND	460	440	160	84	170	370	0.56 J	71	1.6 J	ND	280
Vinyl Chloride	ND	1.6	ND	ND	ND	ND	ND	0.4 J	0.5 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND

**Notes:**

µg/m<sup>3</sup> = micrograms per cubic meter

NR = Not Recorded

NA = Data not available

ND = Not detected above method

detection limit



**Table 6**  
**Soil Vapor Extraction Containment System**  
**Site 1, Former Drum Marshalling Yard**  
**Naval Weapons Industrial Reserve Plant - Bethpage, NY**  
**First Quarter 2016 Off-site Soil Vapor Monitoring of SVPMs**

SVPM/ SVEW Location	Vacuum Reading (i.w.) Pre- Vapor Sample Collection	Vacuum Reading (i.w.) Post- Vapor Sample Collection	Valve Position (% open)
<b>Monitoring Date:</b>	<b>1/13/16</b>	<b>1/14/16</b>	<b>1/13/16</b>
BPS1-SVPM2001S	0.03	0.08	--
BPS1-SVPM2001I	0.04	0.12	--
BPS1-SVPM2001D	0.04	0.02	--
BPS1-SVPM2002S	0.05	0.09	--
BPS1-SVPM2002I	0.04	0.04	--
BPS1-SVPM2002D	0.13	0.18	--
BPS1-SVPM2003S	0.04	0.04	--
BPS1-SVPM2003I	0.03	0.04	--
BPS1-SVPM2003D	0.04	0.05	--
BPS1-SVPM2004S	0.04	0.05	--
BPS1-SVPM2004I	0.05	0.09	--
BPS1-SVPM2004D	0.04	0.12	--
BPS1-SVPM2006S	0.01	0.04	--
BPS1-SVPM2006I	0.03	0.05	--
BPS1-SVPM2006D	0.02	0.04	--
BPS1-SVPM2007S	0.04	0.04	--
BPS1-SVPM2007I	0.06	0.05	--
BPS1-SVPM2007D	0.05	0.05	--
SV-101I	7.5	7.0	40
SV-101D	17.0	16.0	50
SV-102I	4.5	5.0	40
SV-102D	8.0	6.0	40
SV-103I	6.5	6.5	40
SV-103D	11.0	11.0	40
SV-104I	9.0	9.5	40
SV-104D	10.0	10.3	40
SV-105I	3.0	2.5	40
SV-105D	5.5	5.5	50
SV-106I	1.5	5.5	40
SV-106D	26.0	26.5	40

**Notes:**

i.w. = inches of water column

SVEW = soil vapor extraction well

SVPM = soil vapor pressure monitor

\* Indicates a positive pressure reading was measured as opposed to a negative vacuum reading.

Vacuum readings for the SVPMs were measured using a portable Magnehelic® Differential Pressure Gauge 2000-0, with a range of 0-0.50 i.w. Vacuum readings for SVEWs were recorded from dedicated in-line pressure gauges.

Table 7  
Soil Vapor Extraction Containment System  
Site 1, Former Drum Marshalling Yard  
Naval Weapons Industrial Reserve Plant - Bethpage, NY  
Quarterly Off-site Soil Vapor Monitoring of SVPMS  
Through First Quarter 2016

SVPMS/ SVEW Location	Third Quarter 2012	Fourth Quarter 2012	First Quarter 2013		Second Quarter 2013	Third Quarter 2013	Fourth Quarter 2013	First Quarter 2014		Second Quarter 2014	Third Quarter 2014		Fourth Quarter 2014	First Quarter 2015		Second Quarter 2015	Third Quarter 2015	Fourth Quarter 2015	First Quarter 2016	
	Vacuum Reading (i.w.)	Vacuum Reading (i.w.)	Vacuum Reading (i.w.) Pre-Vapor Sample Collection	Vacuum Reading (i.w.) Post-Vapor Sample Collection	Vacuum Reading (i.w.)	Vacuum Reading (i.w.)	Vacuum Reading (i.w.)	Vacuum Reading (i.w.) Pre-Vapor Sample Collection	Vacuum Reading (i.w.) Post-Vapor Sample Collection	Vacuum Reading (i.w.)	Vacuum Reading (i.w.)	Vacuum Reading (i.w.)	Vacuum Reading (i.w.)	Vacuum Reading (i.w.)	Vacuum Reading (i.w.) Pre-Vapor Sample Collection	Vacuum Reading (i.w.) Post-Vapor Sample Collection	Vacuum Reading (i.w.)	Vacuum Reading (i.w.)	Vacuum Reading (i.w.)	Vacuum Reading (i.w.) Pre-Vapor Sample Collection
<b>Monitoring Date:</b>	<b>10/10/2012</b>	<b>12/6/2012</b>	<b>1/15/13</b>	<b>1/16/13</b>	<b>5/29/13</b>	<b>8/27/13</b>	<b>11/8/13</b>	<b>1/29/14</b>	<b>1/30/14</b>	<b>4/10/14</b>	<b>7/29/14</b>	<b>8/1/14</b>	<b>10/2/14</b>	<b>1/13/15</b>	<b>1/14/15</b>	<b>5/6/15</b>	<b>8/12/15</b>	<b>10/29/15</b>	<b>1/13/16</b>	<b>1/14/16</b>
BPS1-SVPM2001S	0.01	0.02	0.01	0.01	0.02	0.08	0.06	0.01	0.02	*0.02	*0.02	*0.02	0.09	0.01	0.08	0.02	0.08	0.07	0.03	0.08
BPS1-SVPM2001I	0.01	0.02	0.02	0.01	0.10	0.12	0.10	0.04	0.04	0.12	*0.01	*0.01	0.14	0.05	0.11	0.04	0.11	0.08	0.04	0.12
BPS1-SVPM2001D	0.01	0.01	0.01	0.01	0.01	0.00	0.00	0.01	*0.01	*0.01	*0.01	*0.01	0.10	*0.01	*0.01	0.03	0.01*	0.01*	0.04	0.02
BPS1-SVPM2002S	0.02	0.01	0.02	0.02	0.06	0.12	0.10	0.08	0.03	0.10	*0.01	0.01	0.09	*0.01	0.11	0.15	0.06	0.06	0.05	0.09
BPS1-SVPM2002I	0.11	0.10	0.01	0.02	0.10	0.18	0.16	0.06	0.08	0.18	0.14	0.14	0.18	*0.21	0.13	0.13	0.10	0.12	0.04	0.04
BPS1-SVPM2002D	0.12	0.10	0.01	0.01	0.10	0.18	0.16	0.01	*0.01	*0.02	0.00	0.00	0.06	*0.01	0.14	0.13	0.14	0.13	0.13	0.18
BPS1-SVPM2003S	0.01	0.01	0.03	0.02	0.04	*0.02	0.02	0.06	*0.01	*0.01	0.02	0.04	*0.01	*0.01	0.02	0.03	*0.01	0.04	0.04	0.04
BPS1-SVPM2003I	0.04	0.02	0.03	0.04	0.10	0.04	0.04	0.02	0.02	0.04	0.02	0.04	*0.02	0.06	0.02	0.05	0.04	0.04	0.03	0.04
BPS1-SVPM2003D	0.04	0.02	0.01	0.04	0.05	0.04	0.04	0.02	*0.01	0.04	0.04	*0.01	0.03	*0.01	0.02	0.04	0.05	0.04	0.04	0.05
BPS1-SVPM2004S	0.04	0.04	0.03	0.02	0.03	0.04	0.02	0.04	0.00	0.04	*0.02	*0.01	*0.01	0.04	0.05	0.03	0.03	0.04	0.04	0.05
BPS1-SVPM2004I	0.04	0.04	0.02	0.01	0.04	0.04	0.02	0.02	*0.01	0.04	*0.01	0.02	*0.01	0.10	0.05	0.05	*0.01	0.06	0.05	0.09
BPS1-SVPM2004D	0.06	0.04	0.03	0.01	0.04	0.04	0.04	0.02	0.04	0.02	*0.01	0.02	0.08	0.04	0.06	0.02	0.05	0.05	0.04	0.12
BPS1-SVPM2006S	0.01	0.01	0.01	0.01	0.02	0.00	0.00	0.00	*0.01	0.02	0.02	0.01	*0.03	0.01	0.01	0.02	0.01	0.02	0.01	0.04
BPS1-SVPM2006I	0.01	0.01	0.01	0.01	0.01	*0.01	*0.01	0.00	*0.01	0.01	0.01	0.01	0.00	0.02	0.01	0.02	0.01	0.02	0.03	0.05
BPS1-SVPM2006D	0.02	0.02	0.01	0.01	0.02	*0.01	0.00	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.01	0.03	0.01	0.02	0.02	0.04
BPS1-SVPM2007S	0.01	0.01	0.01	0.01	0.04	0.00	*0.01	0.01	0.02	0.00	0.02	0.02	0.00	*0.01	0.02	0.01	0.02	0.02	0.04	0.04
BPS1-SVPM2007I	0.01	0.01	0.01	0.01	0.04	*0.01	*0.02	0.02	0.01	*0.01	0.02	0.02	0.00	0.01	0.02	0.00	0.02	0.01	0.06	0.05
BPS1-SVPM2007D	0.01	0.01	0.01	0.01	0.02	*0.01	0.04	0.02	0.02	*0.01	0.01	0.01	0.00	0.01	0.01	0.02	0.02	0.00	0.05	0.05
SV-101I	5	7	10	--	6.0	5.1	4.8	5.0	--	7.1	8.0	--	4.5	6.0	--	7.0	4.8	3.6	7.5	7.0
SV-101D	10	16	16	--	16.0	23.5	24.5	17.0	--	22.5	16.0	--	16.0	14.0	--	13.0	11.0	13.0	17.0	16.0
SV-102I	5	3	16	--	3.0	6.9	6.5	4.4	--	8.7	5.0	--	6.0	6.5	--	2.0	2.4	3.4	4.5	5.0
SV-102D	10	18	10	--	22.0	26.6	22.3	15.0	--	26.0	15.0	--	17.0	17.5	--	13.5	10.5	10.5	8.0	6.0
SV-103I	5	2	20	--	4.0	3.5	3.1	6.6	--	5.6	2.0	--	3.0	4.5	--	6.1	4.0	3.7	6.5	6.5
SV-103D	8	24	10	--	24.2	27.7	20.8	15.0	--	24.5	16.0	--	16.0	19.0	--	24.0	14.5	12.8	11.0	11.0
SV-104I	8	6	20	--	4.0	3.5	3.1	10.0+	--	10.0+	10.0	--	10.0	10.0+	--	4.0	3.0	4.6	9.0	9.5
SV-104D	11	10	10	--	10.0	9.0	8.0	10.0	--	11.5	6.0	--	6.0	10.5	--	16.0	14.0	8.9	10.0	10.3
SV-105I	5	9	16	--	7.5	4.3	3.6	5.0	--	8.2	3.0	--	2.5	7.0	--	7.5	4.5	3.8	3.0	2.5
SV-105D	8	7	8	--	8.0	5.0	4.0	15.5	--	30	6.0	--	3.0	23.5	--	28.5	11.5	12.0	5.5	5.5
SV-106I	5	8	16	--	8.0	4.0	3.6	10.0+	--	10.0+	6.0	--	7.5	10.0+	--	6.2	2.4	3.7	1.5	5.5
SV-106D	8	12	10	--	11.0	7.0	6.0	6.5	--	16.0	6.0	--	5.0	10.0	--	17.0	25.5	18.5	26.0	26.5

**Notes:**  
i.w. = inches of water column  
SVEW = soil vapor extraction well  
SVPMS = soil vapor pressure monitor  
\* Indicates a positive pressure reading was measured as opposed to a negative vacuum reading.  
  
Vacuum readings for the SVPMS were measured using a portable Magnehelic® Differential Pressure Gauge 2000-0, with a range of 0-0.50 i.w. Vacuum readings for SVEWs were recorded from dedicated in-line vacuum gauges.

**Table 8**  
**Soil Vapor Extraction Containment System**  
**Site 1, Former Drum Marshalling Yard**  
**Naval Weapons Industrial Reserve Plant - Bethpage, NY**  
**Annual Off-site Vapor Analytical Results Summary of SVPMs**  
**January 2016**

Sample ID	Screening Value <sup>(1)</sup>	SVPM 2001S	SVPM 2001I	SVPM 2001D	SVPM 2002S		SVPM 2002I	SVPM 2002D	SVPM 2003S	SVPM 2003I	SVPM 2003D	SVPM 2004S	SVPM 2004I	SVPM 2004D	SVPM 2006S	SVPM 2006I		SVPM 2006D	SVPM 2007S	SVPM 2007IR	SVPM 2007D
Sample Date		01/14/16	01/14/16	01/14/16	01/14/16	01/14/16 - Duplicate	01/14/16	01/14/16	01/14/16	01/14/16	01/14/16	01/14/16	01/14/16	01/14/16	01/14/16	01/14/16	01/14/16 - Duplicate	01/14/16	01/14/16	01/14/16	01/14/16
<b>Analysis by TO-15 (µg/m<sup>3</sup>)</b>																					
1,1,1-Trichloroethane	<b>1,000</b>	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	<b>0.87 J</b>
1,1-Dichloroethane	--	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,1-Dichloroethene	--	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,2-Dichloroethane	--	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
cis-1,2-Dichloroethene	--	ND	ND	<b>6.3</b>	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	<b>3.4</b>	<b>260</b>	<b>280</b>	<b>320</b>	ND	<b>4.4 J</b>	<b>3.1</b>
Tetrachloroethene	<b>1,000</b>	ND	<b>1.2 J</b>	<b>10</b>	ND	ND	ND	ND	ND	<b>0.89 J</b>	ND	ND	<b>0.83 J</b>	<b>3.6 J</b>	ND	<b>2.2 J</b>	<b>2.1 J</b>	<b>1.9 J</b>	<b>0.89 J</b>	<b>2.3 J</b>	<b>2.0 J</b>
trans-1,2-Dichloroethene	--	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	<b>3.4</b>	<b>3.6</b>	<b>3.3</b>	ND	ND	ND
Trichloroethene	<b>250</b>	ND	ND	<b>3.9 J</b>	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	<b>1.6 J</b>	<b>48</b>	<b>61</b>	<b>47</b>	ND	<b>1.9 J</b>	<b>2.7 J</b>
Vinyl Chloride	--	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND

**Notes:**

µg/m<sup>3</sup> = micrograms per cubic meter

J = Estimated value

ND = Not detected above laboratory method detection limit (MDL)

SVPM = soil vapor pressure monitor

Bolded value indicates detected analyte.

All samples were analyzed for site-specific VOCs by modified method TO-15. Site specific compound specified in the *Final Supplemental Offsite Soil Vapor Intrusion Monitoring Plan for the Soil Vapor Extraction Containment System Site 1 – Former Drum Marshalling Area, NWIRP Bethpage, New York* (Tetra Tech 2012).

(1) Screening Value is the New York State Department of Health (NYSDOH) air guideline value for subslab.

**Table 9**  
**Soil Vapor Extraction Containment System**  
**Site 1, Former Drum Marshalling Yard**  
**Naval Weapons Industrial Reserve Plant - Bethpage, NY**  
**Historical Off-site Vapor Analytical Results Summary of SVPMs**  
**Through January 2016**

Sample ID	Screening Value <sup>(2)</sup>	SVPM 2001S					SVPM 2001I					SVPM 2001D						SVPM 2002S						SVPM 2002I					SVPM 2002D					
		Oct 2008	01/15/13	01/29/14	01/13/15	01/14/16	Oct 2008	01/15/13	01/29/14	01/13/15	01/14/16	Oct 2008	01/15/13	1/15/13 - Duplicate	01/29/14	01/13/15	1/13/15 - Duplicate	01/14/16	Oct 2008	01/15/13	01/29/14	01/13/15	01/14/16	1/14/16 - Duplicate	Oct 2008	01/15/13	01/29/14	1/29/14 - Duplicate	01/13/15	01/14/16	Oct 2008	01/15/13	01/29/14	01/13/15
Analysis by TO-15 (µg/m <sup>3</sup> )																																		
1,1,1-Trichloroethane <sup>(1)</sup>	1,000	1,300	ND	ND	ND	ND	1,700	ND	ND	ND	ND	1,400	ND	ND	ND	ND	ND	21,000	ND	ND	ND	ND	ND	52,000	ND	ND	ND	ND	ND	27,000	ND	ND	ND	ND
1,1-Dichloroethane <sup>(1)</sup>	--	11	ND	ND	ND	ND	29	ND	ND	ND	ND	26	ND	ND	ND	ND	ND	170	ND	ND	ND	ND	ND	680	ND	ND	ND	ND	ND	490	ND	ND	ND	ND
1,1-Dichloroethene <sup>(1)</sup>	--	9.2 J	ND	ND	ND	ND	16	ND	ND	ND	ND	17	ND	ND	ND	ND	ND	220	ND	ND	ND	ND	ND	890	ND	ND	ND	ND	ND	480	ND	ND	ND	ND
1,2-Dichloroethane <sup>(1)</sup>	--	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
cis-1,2-Dichloroethene <sup>(1)</sup>	--	20	ND	ND	ND	ND	94	ND	ND	ND	ND	73	ND	ND	ND	ND	6.3	49 J	ND	ND	ND	ND	ND	170	ND	ND	ND	ND	ND	130	ND	ND	ND	ND
Tetrachloroethene <sup>(1)</sup>	1,000	4,000	ND	1.3 J	ND	ND	5,000	ND	1.9 J	ND	1.2 J	720	ND	ND	0.53 J	ND	ND	10	420	ND	2.2 J	ND	ND	740	ND	1.8 J	ND	ND	ND	48 J	ND	1.8 J	ND	ND
trans-1,2-Dichloroethene <sup>(1)</sup>	--	7.9 J	ND	ND	ND	ND	16	ND	ND	ND	ND	11	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Trichloroethene <sup>(1)</sup>	250	1,700	ND	ND	ND	ND	2,700	ND	ND	ND	ND	1,500	ND	ND	ND	ND	ND	3.9 J	34,000	ND	1.1 J	ND	ND	89,000	12	1.8 J	1.4 J	ND	ND	26,000	ND	ND	ND	ND
Vinyl Chloride <sup>(1)</sup>	--	NS	ND	ND	ND	ND	NS	ND	ND	ND	ND	NS	ND	ND	ND	ND	ND	NS	ND	ND	ND	ND	NS	ND	ND	ND	ND	ND	NS	ND	ND	ND	ND	

**Table 9**  
**Soil Vapor Extraction Containment System**  
**Site 1, Former Drum Marshalling Yard**  
**Naval Weapons Industrial Reserve Plant - Bethpage, NY**  
**Historical Off-site Vapor Analytical Results Summary of SVPMs**  
**Through January 2016**

Sample ID	Screening Value <sup>(2)</sup>	SVPM 2003S					SVPM 2003I					SVPM 2003D					SVPM 2004S					SVPM 2004I					SVPM 2004D				
		Oct 2008	01/16/13	01/29/14	01/13/15	01/14/16	Oct 2008	01/16/13	01/29/14	01/13/15	01/14/16	Oct 2008	01/16/13	01/29/14	01/13/15	01/14/16	Oct 2008	01/16/13	01/29/14	01/13/15	01/14/16	Oct 2008	01/16/13	01/29/14	01/13/15	01/14/16	Oct 2008	01/16/13	01/29/14	01/13/15	01/14/16
Analysis by TO-15 (µg/m <sup>3</sup> )																															
1,1,1-Trichloroethane <sup>(1)</sup>	1,000	66	ND	ND	ND	ND	170 J	ND	ND	ND	ND	720 J	ND	ND	ND	ND	1.4	ND	ND	ND	ND	460	ND	ND	ND	ND	480	ND	ND	ND	ND
1,1-Dichloroethane <sup>(1)</sup>	--	ND	ND	ND	ND	ND	0.49 J	ND	ND	ND	ND	8.6	ND	ND	ND	ND	ND	ND	ND	ND	ND	44	ND	ND	ND	ND	74	ND	ND	ND	ND
1,1-Dichloroethene <sup>(1)</sup>	--	ND	ND	ND	ND	ND	2	ND	ND	ND	ND	23	ND	ND	ND	ND	ND	ND	ND	ND	ND	7.1	ND	ND	ND	ND	ND	ND	ND	ND	
1,2-Dichloroethane <sup>(1)</sup>	--	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	0.25 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	
cis-1,2-Dichloroethene <sup>(1)</sup>	--	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	1.6	ND	ND	ND	ND	ND	ND	ND	ND	ND	4.6	ND	ND	ND	ND	ND	ND	ND	ND	
Tetrachloroethene <sup>(1)</sup>	1,000	19	1.6 J	ND	ND	ND	14	0.97 J	1.5 J	ND	0.89 J	8.9	ND	2.4 J	ND	ND	1.8	1.0 J	1.3 J	ND	ND	1,000	0.68 J	2.9 J	ND	0.83 J	580	2.3 J	1.5 J	7.1	3.6 J
trans-1,2-Dichloroethene <sup>(1)</sup>	--	ND	2.3 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	3.9	ND	ND	ND	ND	ND	ND	ND	ND	
Trichloroethene <sup>(1)</sup>	250	20	4.9	ND	ND	ND	82	ND	0.73 J	ND	ND	710	ND	ND	ND	ND	1.0	ND	ND	ND	ND	550	ND	3.7 J	ND	ND	600	ND	0.80 J	1.5 J	ND
Vinyl Chloride <sup>(1)</sup>	--	NS	ND	ND	ND	ND	NS	ND	ND	ND	ND	NS	ND	ND	ND	ND	NS	ND	ND	ND	ND	NS	ND	ND	ND	ND	NS	ND	ND	ND	

**Table 9**  
**Soil Vapor Extraction Containment System**  
**Site 1, Former Drum Marshalling Yard**  
**Naval Weapons Industrial Reserve Plant - Bethpage, NY**  
**Historical Off-site Vapor Analytical Results Summary of SVPMs**  
**Through January 2016**

Sample ID	Screening Value <sup>(2)</sup>	SVPM 2006S					SVPM 2006I						SVPM 2006D					SVPM 2007S					SVPM 2007I/IR					SVPM 2007D							
		Oct 2008	01/16/13	01/30/14	01/13/15	01/14/16	Oct 2008	01/16/13	01/30/14	01/13/15	01/14/16	1/14/16 - Duplicate	Oct 2008	01/16/13	01/30/14	01/13/15	01/14/16	Oct 2008	01/16/13	01/30/14	01/14/15	1/14/15 - Duplicate	01/14/16	Oct 2008	01/16/13	01/30/14	01/14/15	01/14/16	Oct 2008	01/16/13	1/16/13 - Duplicate	01/30/14	1/30/14 - Duplicate	01/14/15	01/14/16
Analysis by TO-15 (µg/m <sup>3</sup> )																																			
1,1,1-Trichloroethane <sup>(1)</sup>	1,000	12	ND	ND	ND	ND	22	ND	ND	ND	ND	ND	35	ND	ND	ND	ND	150	ND	ND	ND	ND	ND	260	ND	ND	ND	ND	870	1.3 J	1.1 J	ND	ND	ND	0.87 J
1,1-Dichloroethane <sup>(1)</sup>	--	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,1-Dichloroethene <sup>(1)</sup>	--	ND	ND	ND	ND	ND	0.62	ND	ND	ND	ND	ND	1.2	ND	ND	ND	ND	0.26 J	ND	ND	ND	ND	ND	0.69 J	ND	ND	ND	ND	13	ND	ND	ND	ND	ND	ND
1,2-Dichloroethane <sup>(1)</sup>	--	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
cis-1,2-Dichloroethene <sup>(1)</sup>	--	4.1	5.4	ND	ND	3.4	45	340	10	ND	260	280	89	190	22	180	320	ND	13	2.0 J	ND	ND	ND	ND	ND	ND	ND	4.4 J	ND	9.8	11	2.0 J	ND	ND	3.1
Tetrachloroethene <sup>(1)</sup>	1,000	14	1.0 J	1.4 J	ND	ND	29	1.9 J	1.5 J	ND	2.2 J	2.1 J	11	1.4 J	ND	1.7 J	1.9 J	13	1.1 J	1.4 J	ND	ND	0.89 J	25	1.8 J	ND	2.3 J	2.3 J	5.3 J	2.2 J	1.8 J	1.2 J	ND	ND	2.0 J
trans-1,2-Dichloroethene <sup>(1)</sup>	--	ND	ND	ND	ND	ND	1.4 J	4.6	ND	ND	3.4	3.6	2.7	2.2 J	ND	2.0 J	3.3	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	1.3 J	ND	ND	ND	ND	ND	
Trichloroethene <sup>(1)</sup>	250	32	ND	0.80 J	ND	1.6 J	71	47	2.9 J	ND	48	61	61	17	2.1 J	30	47	29	5.0	2.5 J	ND	ND	ND	87	ND	ND	ND	1.9 J	400	5.5 J	2.9 J	ND	ND	ND	2.7 J
Vinyl Chloride <sup>(1)</sup>	--	NS	ND	ND	ND	ND	NS	ND	ND	ND	ND	ND	NS	ND	ND	ND	ND	NS	ND	ND	ND	ND	NS	ND	ND	ND	ND	NS	ND	ND	ND	ND	ND	ND	

**Notes:**

µg/m<sup>3</sup> = micrograms per cubic meter

J = Estimated value

ND = Not detected above laboratory method detection limit (MDL)

NS = Not sampled

SVPM = soil vapor pressure monitor

Bolded value indicates detected analyte.



(1) Site specific compound specified in the *Final Supplemental Offsite Soil Vapor Intrusion Monitoring Plan for the Soil Vapor Extraction Containment System Site 1 – Former Drum Marshalling Area, NWIRP Bethpage, New York* (Tetra Tech 2012).

(2) Screening Value is the New York State Department of Health (NYSDOH) air guideline value for subslab.

(3) October 2008 data taken from *Site 1 Phase II Soil Vapor Report* (Tetra Tech 2009).

## **FIGURES**






Department of the Navy  
Naval Facilities Engineering Command, Mid-Atlantic  
Site 1, Former Drum Marshalling Area  
Naval Weapons Industrial Reserve Plant  
Bethpage, NY

Figure 1: Site Location Map

KOMAN Government Solutions, LLC








Department of the Navy  
 Naval Facilities Engineering Command, Mid-Atlantic  
 Site 1, Former Drum Marshalling Area  
 Naval Weapons Industrial Reserve Plant  
 Bethpage, NY

Figure 2  
 Site 1 Area and Vicinity

**KOMAN Government Solutions, LLC**





NOTES:  
 1. ALL MAN DOORS AND OVERHEAD DOORS ARE EXISTING. MAN DOORS ARE APPROXIMATELY 7'X3'. OVERHEAD DOOR IS APPROXIMATELY 10'X10'.

PROCESS EQUIPMENT LIST		
ITEM NUMBER	NUMBER REQUIRED	NAME/DESCRIPTION
M-1	1	MOISTURE SEPARATOR -CONFIGURATION: VERTICAL, CYLINDRICAL -MATERIAL OF CONSTRUCTION: CARBON STEEL EPOXY INTERIOR COATING, PAINT EXTERIOR COATING -CAPACITY: 400 GALLON CONDENSATE COLLECTION -DIMENSIONS: 5 FT DIA X 6 FEET HT, 718 GALLON
F-1	1	MAKE-UP AIR FILTER -CONFIGURATION: INTAKE FILTER/SILENCER COMBINATION HOUSING -MATERIAL OF CONSTRUCTION: CARBON STEEL, CORROSION RESISTANCE COATING -CAPACITY: 500 CFM AT 20 IW, 4 INCH FLANGED CONNECTION
F-2	1	BLOWER AIR FILTER -CONFIGURATION: INLINE VACUUM SERVICE FILTER -MATERIAL OF CONSTRUCTION: CARBON STEEL, CORROSION RESISTANCE COATING -CAPACITY: 1,200 CFM AT 35 IW, 10 INCH FLANGED CONNECTION
B-1A, B-1B	2	SOIL VAPOR EXTRACTION BLOWER -CONFIGURATION: HORIZONTAL CENTRIFUGAL -RATING: 600 CFM AT 40 IW -MOTOR: 7.5 HP, 480V, 3PH, 60HZ ODP
VGAC-1	1	VAPOR-PHASE GRANULAR ACTIVATED CARBON -CONFIGURATION: RECTANGULAR TANK -MATERIAL OF CONSTRUCTION: CARBON STEEL EPOXY INTERIOR COATING, EPOXY EXTERIOR COATING -RATING: 1,600 CFM AT 3 IW, 2,000 CFM AT 6 IW -CAPACITY: 5,000 LBS CARBON -DIMENSIONS: 6' X 8' FOOTPRINT, 6' 8" HT

<b>TETRA TECH ENGINEERING CORPORATION PC</b> <small>DATE: _____ BY: _____ CH. ENG. DATE: _____</small>	
SUBMITTED BY: _____ <small>(FIRM NUMBER)</small>	DATE: _____
DRAWING NO.: _____ <small>(PROJECT)</small>	SHEET NO.: _____
OFFICE IN CHARGE: _____	DATE: _____
APPROVED: _____ <small>(SIGNATURE)</small>	
DATE: _____	


REV	DESCRIPTION	DATE
0	ISSUED FOR CONSTRUCTION	10-14-09

DEPARTMENT OF THE NAVY NAVAL FACILITIES ENGINEERING COMMAND, MID-ATLANTIC NAVAL WEAPONS INDUSTRIAL RESERVE PLANT BETHPAGE, NEW YORK	SITE 1, FORMER DRUM MARSHALLING AREA SOIL VAPOR EXTRACTION CONTAINMENT SYSTEM LAYOUT PLAN
SEAL AREA	EPM FOR COMMANDER, NAVFAC

THIS DRAWING PRODUCED ON AUTOCAD DO NOT REVISE MANUALLY	SAT TO: _____ DATE: _____
THIS DOCUMENT IS THE PROPERTY OF NAVAL FACILITIES ENGINEERING COMMAND, PREPARED BY TETRA TECH ENGINEERING CORPORATION PC, AND IS PROVIDED UPON THE CONDITION THAT IT WILL NOT BE REPRODUCED, COPIED, OR ISSUED TO A THIRD PARTY, AND WILL BE USED SOLELY FOR THE ORIGINAL INTENDED PURPOSE AND SOLELY FOR THE EXECUTION OR REVIEW OF THE ENGINEERING CONSTRUCTION OF THE PROJECT.	CODE I.D. NO. _____ SCALE: AS SHOWN SPEC. NO. _____ CONSTR. CONTR. NO. _____ N62473-10-D-3211 NAVFAC DRAWING NO. _____ Figure 4
IT IS A VIOLATION OF THE NEW YORK STATE EDUCATION LAW, ARTICLE 145, FOR ANY PERSON, UNLESS UNDER THE DIRECTION OF A NEW YORK STATE LICENSED PROFESSIONAL ENGINEER, TO ALTER AN ITEM ON THIS DOCUMENT IN ANY WAY.	SHEET OF _____ DIS. SH. NO. _____ SIZE: 1-3



SV-106D	01/13/16
1,1,1-TCA	11
PCE	33
TCE	280

SV-106I	01/13/16
1,1,1-TCA	2.8 J
PCE	11
TCE	200

SV-105I	01/13/16
1,1,1-TCA	12
PCE	44
TCE	84

SV-105D	01/13/16
1,1,1-TCA	62
PCE	140
TCE	410

SV-103D	01/13/16
1,1,1-TCA	ND
PCE	ND
TCE	ND

SV-103I	01/13/16
1,1,1-TCA	1.2 J
PCE	450
TCE	70

SV-104D	01/13/16
1,1,1-TCA	760
PCE	7,700
TCE	1,600

SV-104I	01/13/16
1,1,1-TCA	4.6
PCE	79
TCE	35


SV-101D	01/13/16
1,1,1-TCA	27
PCE	310
TCE	2,200

SV-101I	01/13/16
1,1,1-TCA	2700
PCE	83
TCE	8,200

SV-102D	01/13/16
1,1,1-TCA	3.5 J
PCE	42
TCE	120

SV-102I	01/13/16
1,1,1-TCA	0.87 J
PCE	2.4 J
TCE	12





PLANT 3

SITE 1

SITE 4

WAREHOUSE I

WAREHOUSE J

WAREHOUSE K

BUILDING 10

WAREHOUSE E

WAREHOUSE F

WAREHOUSE G

WAREHOUSE A

WAREHOUSE B

WAREHOUSE C

WAREHOUSE D

TRAP & CLEANOUT #5

TRAP & CLEANOUT #4

TRAP & CLEANOUT #3

TRAP & CLEANOUT #2

TREATMENT BUILDING

FLOW MONITORING STATION

Sycamore Ave  
SVPM-2004D  
SVPM-2004I  
SVPM-2004S

SVPM-2001S  
SVPM-2001I  
SVPM-2001D

SVPM-2006S  
SVPM-2006I  
SVPM-2006D

SVPM-2002D  
SVPM-2002I  
SVPM-2002S

SVPM-2007I  
SVPM-2007D  
SVPM-2007S

Maple Ave  
SVPM-2003D  
SVPM-2003S  
SVPM-2003I

SVPM-2004S	01/13/16	01/13/16
Vacuum (i.w.)	0.04	0.05

SVPM-2004I	01/13/16	01/13/16
Vacuum (i.w.)	0.05	0.09

SVPM-2004D	01/13/16	01/13/16
Vacuum (i.w.)	0.04	0.12

SVPM-2001S	01/13/16	01/14/16
Vacuum (i.w.)	0.03	0.08

SVPM-2001I	01/13/16	01/13/16
Vacuum (i.w.)	0.04	0.12

SVPM-2001D	01/13/16	01/13/16
Vacuum (i.w.)	0.04	0.02

SVPM-2002S	01/13/16	01/13/16
Vacuum (i.w.)	0.05	0.09

SVPM-2002I	01/13/16	01/13/16
Vacuum (i.w.)	0.04	0.04

SVPM-2002D	01/13/16	01/13/16
Vacuum (i.w.)	0.13	0.18

SVPM-2003S	01/13/16	01/13/16
Vacuum (i.w.)	0.04	0.04

SVPM-2003I	01/13/16	01/13/16
Vacuum (i.w.)	0.03	0.04

SVPM-2003D	01/13/16	01/13/16
Vacuum (i.w.)	0.04	0.05

SVPM-2007S	01/13/16	01/13/16
Vacuum (i.w.)	0.04	0.04

SVPM-2007I	01/13/16	01/13/16
Vacuum (i.w.)	0.06	0.05

SVPM-2007D	01/13/16	01/13/16
Vacuum (i.w.)	0.05	0.05

SVPM-2006S	01/13/16	01/13/16
Vacuum (i.w.)	0.01	0.04

SVPM-2006I	01/13/16	01/13/16
Vacuum (i.w.)	0.03	0.05

SVPM-2006D	01/13/16	01/13/16
Vacuum (i.w.)	0.02	0.04

**LEGEND**

- FORMER NWIRP BOUNDARY
  - - - CURRENT NWIRP BOUNDARY
  - SOIL VAPOR PRESSURE MONITOR (SVPM)
  - \* INDICATES A POSITIVE PRESSURE READING
- ALL VACUUM READINGS IN INCHES OF WATER COLUMN (i.w.)

**1ST QUARTER 2016  
OFFSITE SOIL VAPOR MONITORING  
QUARTERLY VACUUM PRESSURE READINGS - SVPMs**

**SVE CONTAINMENT SYSTEM  
SITE 1 - NWIRP BETHPAGE  
BETHPAGE, NEW YORK**

**KOMAN Government Solutions, LLC**  
160 East Main Street, Suite 2F, Westborough, MA 01581

SCALE IN FEET 	DATE 04/19/2016	FIGURE 6	
-------------------	--------------------	-------------	--

**APPENDIX A**

**NYSDEC AIR DISCHARGE LIMIT  
DOCUMENTATION**

From: Steven Scharf [<mailto:sxscharf@gw.dec.state.ny.us>]  
Sent: Thursday, October 06, 2011 11:57 AM  
To: Fly, Lora B CIV NAVFAC MIDLANT, IPTNE  
Cc: John Swartwout; Walter Parish; Steven Karpinski; John cofman; [klumpe@steelequities.com](mailto:klumpe@steelequities.com);  
[David.Brayack@tnus.com](mailto:David.Brayack@tnus.com)  
Subject: NWIRP Plant 3 Site 1 SVE Modification Plan

Lora,

The New York State Department of Environmental Conservation (NYSDEC), in conjunction with the New York State Department of Health (NYSDOH), have reviewed the Navy Submittal entitled:

" Modification to existing Soil vapor Extraction (SVE) Containment System At Site 1-Former Drum Marshaling Area, Installation of Soil Vapor Extraction Wells SVE-107D to 111D, NWIRP Bethpage, September 2011."

Based on this Departmental review, and the follow up October 6, 2011 tele-conference, this modification work plan is acceptable and can be used for immediate implementation. The NWIRP Site 1 SVE system has redundant blowers and overcapacity, even with the additional SVE wells being added. should the Navy and the new property owner, Steel Equities Inc., for the former Plant 3 complex come to agreement to add SVE piping from the former Plant 3, this would be acceptable. Appropriate plans, consistent with the covenants and restrictions to the deed, should be submitted accordingly.

A letter will not follow this e-mail. If you have any questions, please contact me directly.

Electronic Documentation Information  
NWIRP Bethpage  
130003B-OU1-OMM  
FOIable  
Region 1, Nassau (C), Oyster Bay (T)

Thanks,

Steven M. Scharf, P.E.  
Project Engineer  
New York State Department of  
Environmental Conservation  
Division of Environmental Remediation  
Remedial Action, Bureau A  
625 Broadway  
Albany, NY 12233-7015  
(518)402-9620  
Fax: (518)402-9022

#### 4.0 PROPOSED REVISIONS TO VAPOR DISCHARGE GOALS

To determine the continued need for off gas treatment, the quality of the influent vapor stream was initially estimated based on soil gas results and compared to discharge goals. Vapor phase treatment was initially installed for the system based on projected relatively high concentrations of several chemicals including 1,1,1-trichloroethane (TCA), trichloroethene (TCE), and tetrachloroethene (PCE). Since the December 2009 startup, VOC concentrations in the extracted vapors have decreased by approximately 98.3 percent and it is uncertain as to whether vapor phase treatment is still required. Presented below are the December 2009 and March 2011 influent (untreated) VOC concentrations and loadings and current discharge goals.

Parameter	December 2009 Influent VOCs		March 2011 Influent VOCs ( $\mu\text{g}/\text{m}^3$ )		Current Discharge Goal (pound/hour) <sup>(3)</sup>
	Concentration ( $\mu\text{g}/\text{m}^3$ ) <sup>1</sup>	Loading (pound/hour) <sup>1</sup>	Concentration ( $\mu\text{g}/\text{m}^3$ )	Loading (pound/hour) <sup>(2)</sup>	
TCA	13,000	0.074	150	0.00023	0.13
TCE	42,000	0.26	460	0.00069	0.07
PCE	7,900	0.029	440	0.00066	0.0009

<sup>(1)</sup> Initial VOC Loading Rates are from baseline data taken in December 2009. The flow meter was not yet installed when this data was taken, so a value of 385 CFM (flow rate in January 2010) was used to estimate system loading.

<sup>(2)</sup> Calculated using a flow rate of 400 CFM.

<sup>(3)</sup> Current discharge goals were based on calculated VOC concentrations using soil gas data from the fence line investigation, a flow rate of 600 CFM, and an assumed treatment efficiency for each VOC of 80 to 90 percent. Based on this evaluation, the existing treatment is no longer required to meet discharge goals.

A DAR-1 Model Analysis was then conducted using the August 2010 influent vapor concentrations of TCA, TCE, and PCE at a flow rate of 500 CFM. The calculated results were then used to back calculate proposed discharge goals based on an allowance of 100% of the annual guideline concentrations (see Appendix E). The following table provides a summary of the proposed discharge goals.


Parameter	August 2010 Influent VOCs (370 CFM – Actual)		Percent AGC Using August 2010 Data	Proposed Discharge Goals	
	Concentration ( $\mu\text{g}/\text{m}^3$ )	Loading (pounds/ hour)		Concentration at 500 CFM ( $\mu\text{g}/\text{m}^3$ )	Loading (pounds/ hour)
TCA	868	0.0009	0.0004	None <sup>1</sup>	225
TCE	4,170	0.0039	19.4	11,000	0.02
PCE	5,780	0.0057	14.2	22,000	0.04

<sup>(1)</sup> Greater than 100,000  $\mu\text{g}/\text{m}^3$ .

AGC - Annual Guideline Concentration



**New York State Department of Environmental Conservation**  
**Division of Environmental Remediation**  
**Bureau of Remedial Action A**  
**625 Broadway, 11<sup>th</sup> Floor**  
**Albany, New York 12233-7015**  
**Phone: (518) 402-9625 • Fax: (518) 402-9022**



**Website:** [www.dec.state.ny.us](http://www.dec.state.ny.us)

February 5, 2010

Lora Fly, Project Manager  
Naval Facilities Engineering Command-Midlant  
9742 Maryland Avenue  
Norfolk, VA 23511-3095

RE: Naval Weapons Industrial Research Plant( NWIRP)  
Site-Bethpage, NYSDEC No. 1-30-003B.

Dear Ms. Fly:

Tetra Tech FW, on behalf of the Department of the Navy (Navy), has submitted the enclosed New York State Department of Environmental Conservation (NYSDEC) Division of Air Resources (DAR) Air Permit Application as a permit equivalent. This DAR Air permit equivalent is for the soil vapor extraction system at Site 1 of Plant 3 of the former Naval Weapons Industrial Reserve Plant (NWIRP) site in Bethpage, NY. The NYSDEC Division of Environmental Remediation (DER) has reviewed the permit equivalent and, by means of this letter approves the Site 1 remedy air discharge for immediate operation.

The NWIRP Site 1 SVE system utilizes the reasonably available control technology (RACT) with activated carbon. The air discharge will be periodically monitored at start up and will be added for routine monitoring in the operation, maintenance and monitoring (OMM) plan, to be submitted shortly for Departmental review.

If you have any questions, please contact me at your earliest convenience at (518)402-9620.

Sincerely,

A handwritten signature in black ink, appearing to read "Steve Scharf".

Steven M. Scharf, P.E.  
Project Engineer  
Division of Environmental Remediation  
Bureau of Remedial Action A

Enclosure

cc/w/enc: J. Swartwout/S. Scharf/File  
W. Parish, Region 1 NYSDEC  
A. J. Shah, Region 1 NYSDEC  
S. Patselos, Tetra Tech FW  
J. Cofman, Northrop Grumman

E docs: Region 1, Nassau, Oyster Bay (T): NWIRP Bethpage 130003B-OUI-OMM

# New York State Department of Environmental Conservation Air Permit Application



DEC ID									
-	-	-	-	-	-	-	-	-	-

APPLICATION ID									
-	-	-	-	-	-	-	-	-	-

OFFICE USE ONLY									
-	-	-	-	-	-	-	-	-	-

## Section I - Certification

Title V Certification	
I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons directly responsible for gathering the information [required pursuant to 6 NYCRR 201-6.3(d)] I believe the information is, true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fines and imprisonment for knowing violations.	
Responsible Official	Title
Signature	Date <u>    </u> / <u>    </u> / <u>    </u>

State Facility Certification	
I certify that this facility will be operated in conformance with all provisions of existing regulations.	
Responsible Official	Title
Signature	Date <u>    </u> / <u>    </u> / <u>    </u>

## Section II - Identification Information

Title V Facility Permit <u>N/A</u>	<input type="checkbox"/> New	<input type="checkbox"/> Significant Modification	<input type="checkbox"/> Administrative Amendment	State Facility Permit <u>N/A</u>
<input type="checkbox"/> Renewal	<input type="checkbox"/> Minor Modification	General Permit Title: _____		<input type="checkbox"/> New
<input checked="" type="checkbox"/> Application involves construction of new facility			<input type="checkbox"/> Application involves construction of new emission unit(s)	

Owner/Firm				
Name <u>US Navy / NAVFAC Midlant</u>				
Street Address <u>9740 Maryland Ave, Bldg Z-144</u>				
City <u>Norfolk</u>	State <u>VA</u>	Country <u>US</u>	Zip <u>23511-3095</u>	
Owner Classification <input checked="" type="checkbox"/> Federal	<input type="checkbox"/> State	<input type="checkbox"/> Municipal	Taxpayer ID	
<input type="checkbox"/> Corporation/Partnership	<input type="checkbox"/> Individual			
Facility				
Name <u>Naval Weapons Industrial Reserve Plant (NWIRP) Site 1</u>				
Location Address <u>Bethpage</u>				
<input type="checkbox"/> City / <input checked="" type="checkbox"/> Town / <input type="checkbox"/> Village	<u>Oyster Bay, New York</u>			Zip <u>11714</u>
Project Description				
<u>Vapor phase granular activated carbon to remove VOCs from soil gas</u>				

Owner/Firm Contact Mailing Address				
Name (Last, First, Middle Initial) <u>Fly, Lora</u>			Phone No. <u>(757) 444-0781</u>	
Affiliation <u>Department of the Navy</u>		Title <u>Remedial PM</u>	Fax No. ( )	
Street Address <u>9742 Maryland Ave, Bldg Z-144</u>				
City <u>Norfolk</u>	State <u>VA</u>	Country <u>US</u>	Zip <u>23511-3095</u>	
Facility Contact Mailing Address				
Name (Last, First, Middle Initial)			Phone No. ( )	
Affiliation		Title	Fax No. ( )	
Street Address				
City	State	Country	Zip	

**New York State Department of Environmental Conservation  
Air Permit Application**



DEC ID									
-	-	-	-	-	-	-	-	-	-

**Section III - Facility Information**

Classification					
<input type="checkbox"/> Hospital	<input type="checkbox"/> Residential	<input type="checkbox"/> Educational/Institutional	<input type="checkbox"/> Commercial	<input checked="" type="checkbox"/> Industrial	<input type="checkbox"/> Utility

Affected States (Title V Only) <i>N/A</i>					
<input type="checkbox"/> Vermont	<input type="checkbox"/> Massachusetts	<input type="checkbox"/> Rhode Island	<input type="checkbox"/> Pennsylvania	Tribal Land: _____	
<input type="checkbox"/> New Hampshire	<input type="checkbox"/> Connecticut	<input type="checkbox"/> New Jersey	<input type="checkbox"/> Ohio	Tribal Land: _____	

SIC Codes									
9999									

Facility Description		<input type="checkbox"/> Continuation Sheet(s)
<i>Soil vapor remediation by SVE followed by vapor phase GAC.</i>		

Compliance Statements (Title V Only) <i>N/A</i>	
<p>I certify that as of the date of this application the facility is in compliance with all applicable requirements: <input type="checkbox"/> YES <input type="checkbox"/> NO</p> <p>If one or more emission units at the facility are not in compliance with all applicable requirements at the time of signing this application (the 'NO' box must be checked), the noncomplying units must be identified in the "Compliance Plan" block on page 8 of this form along with the compliance plan information required. For all emission units at this facility that are operating <u>in compliance</u> with all applicable requirements complete the following:</p> <ul style="list-style-type: none"> <li><input type="checkbox"/> This facility will continue to be operated and maintained in such a manner as to assure compliance for the duration of the permit, except those units referenced in the compliance plan portion of Section IV of this application.</li> <li><input type="checkbox"/> For all emission units, subject to any applicable requirements that will become effective during the term of the permit, this facility will meet all such requirements on a timely basis.</li> <li><input type="checkbox"/> Compliance certification reports will be submitted at least once a year. Each report will certify compliance status with respect to each requirement, and the method used to determine the status.</li> </ul>	

Facility Applicable Federal Requirements <i>N/A</i>									<input type="checkbox"/> Continuation Sheet(s)
Title	Type	Part	Sub Part	Section	Sub Division	Paragraph	Sub Paragraph	Clause	Sub Clause

Facility State Only Requirements									<input type="checkbox"/> Continuation Sheet(s)
Title	Type	Part	Sub Part	Section	Sub Division	Paragraph	Sub Paragraph	Clause	Sub Clause





New York State Department of Environmental Conservation  
 Air Permit Application



DEC ID	
-	-

Section III - Facility Information

Facility Emissions Summary (continuation)				
CAS No.	Contaminant Name	PTE		Actual (lbs/yr)
		(lbs/yr)	Range Code	
00540-59-0	cis-1,2-Dichloroethene	5		
00107-06-2	1,2-Dichloroethane	0		
00156-60-5	trans-1,2-Dichloroethene	0		
00075-01-4	Vinyl Chloride	0		
-	-			
-	-			
-	-			
-	-			
-	-			
-	-			
-	-			
-	-			
-	-			
-	-			
-	-			
-	-			
-	-			
-	-			
-	-			
-	-			
-	-			
-	-			
-	-			
-	-			
-	-			
-	-			
-	-			
-	-			
-	-			
-	-			
-	-			
-	-			
-	-			
-	-			
-	-			
-	-			
-	-			

New York State Department of Environmental Conservation  
Air Permit Application



DEC ID									
-									

Section IV - Emission Unit Information

Emission Unit Description <span style="float: right;"><input type="checkbox"/> Continuation Sheet(s)</span>										
EMISSION UNIT	1	-	0	0	E	U	1	Effluent from first soil vapor extraction blower (BL-1)		
Vapor Phase Granular Activated Carbon Unit. The emission point is stack 00ST-2										

Building <span style="float: right;"><input type="checkbox"/> Continuation Sheet(s)</span>					
Building	Building Name		Length (ft)	Width (ft)	Orientation
03-35	Treatment Building		60	40	0

Emission Point <span style="float: right;"><input type="checkbox"/> Continuation Sheet(s)</span>						
EMISSION PT.	00ST2					
Ground Elev. (ft)	Height (ft)	Height Above Structure (ft)	Inside Diameter (in)	Exit Temp. (°F)	Cross Section	
	36	6	8	70	Length (in)	Width (in)
Exit Velocity (FPS)	Exit Flow (ACFM)	NYTM (E) (KM)	NYTM (N) (KM)	Building	Distance to Property Line (ft)	Date of Removal
	1,000			03-35	100'	

Emission Point <span style="float: right;"><input type="checkbox"/> Continuation Sheet(s)</span>						
EMISSION PT.						
Ground Elev. (ft)	Height (ft)	Height Above Structure (ft)	Inside Diameter (in)	Exit Temp. (°F)	Cross Section	
					Length (in)	Width (in)
Exit Velocity (FPS)	Exit Flow (ACFM)	NYTM (E) (KM)	NYTM (N) (KM)	Building	Distance to Property Line (ft)	Date of Removal

Emission Source/Control <span style="float: right;"><input type="checkbox"/> Continuation Sheet(s)</span>							
Emission Source ID	Type	Date of Construction	Date of Operation	Date of Removal	Control Type		Manufacturer's Name/Model No.
BL1/2	1				048	Granular Act. Carbon	Tetrasolv Filtration
Design Capacity	Design Capacity Units			Waste Feed		Waste Type	
	Code	Description		Code	Description	Code	Description
Emission Source ID	Type	Date of Construction	Date of Operation	Date of Removal	Control Type		Manufacturer's Name/Model No.
Design Capacity	Design Capacity Units			Waste Feed		Waste Type	
	Code	Description		Code	Description	Code	Description



DEC ID									
-									

Section IV - Emission Unit Information (continued)

Process Information										<input type="checkbox"/> Continuation Sheet(s)	
EMISSION UNIT 1-00EU1							PROCESS SVE				
Description											
The Soil Vapor Extraction System will consist of 12 SVE wells (6 intermediate and 6 deep), a moisture separator, and 2 soil vapor extraction blowers (BL-1 and BL-2) which both vent to a vapor phase granular activated carbon unit for treatment prior to discharge from stack 00ST2. The VGAC unit will be a 5,000 pound unit filled with Tetrasolv Virgin Carbon. The VGAC unit has been designed to operate nominally at 600 cfm, with a maximum of 1,000 cfm.											
Source Classification Code (SCC)		Total Thruput		Thruput Quantity Units							
		Quantity/Hr	Quantity/Yr	Code	Description						
<input type="checkbox"/> Confidential <input checked="" type="checkbox"/> Operating at Maximum Capacity <input type="checkbox"/> Activity with Insignificant Emissions		Operating Schedule		Building	Floor/Location						
		Hrs/Day	Days/Yr								
		24	365	03-35	Main						
Emission Source/Control Identifier(s)											
BL-1		BL-2									
EMISSION UNIT -										PROCESS	
Description											
Source Classification Code (SCC)		Total Thruput		Thruput Quantity Units							
		Quantity/Hr	Quantity/Yr	Code	Description						
<input type="checkbox"/> Confidential <input type="checkbox"/> Operating at Maximum Capacity <input type="checkbox"/> Activity with Insignificant Emissions		Operating Schedule		Building	Floor/Location						
		Hrs/Day	Days/Yr								
Emission Source/Control Identifier(s)											



New York State Department of Environmental Conservation  
Air Permit Application



DEC ID									
-	-	-	-	-	-	-	-	-	-

Section IV - Emission Unit Information (continued)

Emission Unit	Emission Point	Process	Emission Source	Emission Unit Applicable Federal Requirements										<input type="checkbox"/> Continuation Sheet(s)	
				Title	Type	Part	Sub Part	Section	Sub Division	Parag.	Sub Parag.	Clause	Sub Clause		
-															
-															
-															
-															

Emission Unit	Emission Point	Process	Emission Source	Emission Unit State Only Requirements										<input type="checkbox"/> Continuation Sheet(s)	
				Title	Type	Part	Sub Part	Section	Sub Division	Parag.	Sub Parag.	Clause	Sub Clause		
-															
-															
-															
-															

Emission Unit Compliance Certification										<input type="checkbox"/> Continuation Sheet(s)
Rule Citation										
Title	Type	Part	Sub Part	Section	Sub Division	Paragraph	Sub Paragraph	Clause	Sub Clause	
G	NYCRR	212	-							
<input type="checkbox"/> Applicable Federal Requirement			<input type="checkbox"/> State Only Requirement			<input type="checkbox"/> Capping				
Emission Unit	Emission Point	Process	Emission Source	CAS No.			Contaminant Name			
1-00EU1	00ST3	SVE		00079-01-6			Trichloroethylene			
Monitoring Information										
<input type="checkbox"/> Continuous Emission Monitoring <input checked="" type="checkbox"/> Intermittent Emission Testing <input type="checkbox"/> Ambient Air Monitoring				<input type="checkbox"/> Monitoring of Process or Control Device Parameters as Surrogate <input type="checkbox"/> Work Practice Involving Specific Operations <input type="checkbox"/> Record Keeping/Maintenance Procedures						
Description										
Monthly grab samples analyzed for VOCs from the VGAC unit influent and effluent										
Work Practice		Process Material				Reference Test Method				
Type	Code	Description								
		Parameter				Manufacturer Name/Model No.				
Code		Description								
23		Concentration								
Limit		Limit Units								
Upper		Lower		Code	Description					
36,000				255	micrograms per cubic meter					
Averaging Method			Monitoring Frequency			Reporting Requirements				
Code	Description		Code	Description		Code	Description			
01	Instantaneous		05	Monthly		10	Upon Request			



New York State Department of Environmental Conservation  
Air Permit Application



DEC ID									
-									

Section IV - Emission Unit Information (continued)

Determination of Non-Applicability (Title V Only) <i>N/A</i>										<input type="checkbox"/> Continuation Sheet(s)	
Rule Citation											
Title	Type	Part	Sub Part	Section	Sub Division	Paragraph	Sub Paragraph	Clause	Sub Clause		
Emission Unit		Emission Point		Process	Emission Source		<input type="checkbox"/> Applicable Federal Requirement <input type="checkbox"/> State Only Requirement				
Description											
Rule Citation											
Title	Type	Part	Sub Part	Section	Sub Division	Paragraph	Sub Paragraph	Clause	Sub Clause		
Emission Unit		Emission Point		Process	Emission Source		<input type="checkbox"/> Applicable Federal Requirement <input type="checkbox"/> State Only Requirement				
Description											
Process Emissions Summary										<input checked="" type="checkbox"/> Continuation Sheet(s)	
EMISSION UNIT		1-00EU1						PROCESS		SVE	
CAS No.	Contaminant Name			% Thruput	% Capture	% Control	ERP (lbs/hr)	ERP How Determined			
00071-55-6	1,1,1-Trichloroethane					80	0.34	02			
PTE			Standard Units	PTE How Determined		Actual					
(lbs/hr)	(lbs/yr)	(standard units)				(lbs/hr)	(lbs/yr)				
0.07	591			02							
EMISSION UNIT		1-00EU1						PROCESS		SVE	
CAS No.	Contaminant Name			% Thruput	% Capture	% Control	ERP (lbs/hr)	ERP How Determined			
00127-18-4	Tetrachloroethylene					80	0.00	02			
PTE			Standard Units	PTE How Determined		Actual					
(lbs/hr)	(lbs/yr)	(standard units)				(lbs/hr)	(lbs/yr)				
<del>0.00</del> BRT	8			02							
EMISSION UNIT		1-00EU1						PROCESS		SVE	
CAS No.	Contaminant Name			% Thruput	% Capture	% Control	ERP (lbs/hr)	ERP How Determined			
00079-01-6	Trichloroethylene					80	0.67	02			
PTE			Standard Units	PTE How Determined		Actual					
(lbs/hr)	(lbs/yr)	(standard units)				(lbs/hr)	(lbs/yr)				
0.13	1,181			02							

New York State Department of Environmental Conservation  
Air Permit Application



DEC ID									
-	-	-	-	-	-	-	-	-	-

Section IV - Emission Unit Information (continued)

EMISSION UNIT		Emission Unit Emissions Summary				<input checked="" type="checkbox"/> Continuation Sheet(s)
1-00EU1						
CAS No.		Contaminant Name				
00075-34-3		1,1-Dichloroethane				
ERP (lbs/yr)	PTE Emissions			Actual		
	(lbs/hr)	(lbs/yr)	(lbs/hr)	(lbs/yr)		
	BRT	11				
CAS No.		Contaminant Name				
00075-35-4		1,1-Dichloroethylene (Vinylidene Chloride)				
ERP (lbs/yr)	PTE Emissions			Actual		
	(lbs/hr)	(lbs/yr)	(lbs/hr)	(lbs/yr)		
	BRT	16				
CAS No.		Contaminant Name				
00540-59-0		cis-1,2-Dichloroethene				
ERP (lbs/yr)	PTE Emissions			Actual		
	(lbs/hr)	(lbs/yr)	(lbs/hr)	(lbs/yr)		
	BRT	5				
CAS No.		Contaminant Name				
00107-06-2		1,2-Dichloroethane				
ERP (lbs/yr)	PTE Emissions			Actual		
	(lbs/hr)	(lbs/yr)	(lbs/hr)	(lbs/yr)		
	BRT	BRT				

Compliance Plan N/A													<input type="checkbox"/> Continuation Sheet(s)
For any emission units which are <u>not in compliance</u> at the time of permit application, the applicant shall complete the following													
Consent Order			Certified progress reports are to be submitted every 6 months beginning / /										
Emission Unit	Process	Emission Source	Applicable Federal Requirement										
			Title	Type	Part	Sub Part	Section	Sub Division	Parag.	Sub Parag.	Clause	Sub Clause	
Remedial Measure / Intermediate Milestones											R/I	Date Scheduled	

New York State Department of Environmental Conservation  
Air Permit Application



DEC ID									
-									

Section IV - Emission Unit Information

EMISSION UNIT		Emission Unit Emissions Summary (continuation)			
1-00EU1					
CAS No.		Contaminant Name			
00156-60-5		trans-1,2-Dichloroethene			
ERP (lbs/yr)	PTE Emissions		Actual		
	(lbs/hr)	(lbs/yr)	(lbs/hr)	(lbs/yr)	
		BRT	BRT		
CAS No.		Contaminant Name			
00075-01-4		Vinyl Chloride			
ERP (lbs/yr)	PTE Emissions		Actual		
	(lbs/hr)	(lbs/yr)	(lbs/hr)	(lbs/yr)	
		BRT	BRT		
CAS No.		Contaminant Name			
-					
ERP (lbs/yr)	PTE Emissions		Actual		
	(lbs/hr)	(lbs/yr)	(lbs/hr)	(lbs/yr)	
CAS No.		Contaminant Name			
-					
ERP (lbs/yr)	PTE Emissions		Actual		
	(lbs/hr)	(lbs/yr)	(lbs/hr)	(lbs/yr)	
CAS No.		Contaminant Name			
-					
ERP (lbs/yr)	PTE Emissions		Actual		
	(lbs/hr)	(lbs/yr)	(lbs/hr)	(lbs/yr)	
CAS No.		Contaminant Name			
-					
ERP (lbs/yr)	PTE Emissions		Actual		
	(lbs/hr)	(lbs/yr)	(lbs/hr)	(lbs/yr)	
CAS No.		Contaminant Name			
-					
ERP (lbs/yr)	PTE Emissions		Actual		
	(lbs/hr)	(lbs/yr)	(lbs/hr)	(lbs/yr)	
CAS No.		Contaminant Name			
-					
ERP (lbs/yr)	PTE Emissions		Actual		
	(lbs/hr)	(lbs/yr)	(lbs/hr)	(lbs/yr)	



**New York State Department of Environmental Conservation  
Air Permit Application**



DEC ID									
-									

**Section IV - Emission Unit Information (continued)**

Request for Emission Reduction Credits						<input type="checkbox"/> Continuation Sheet(s)			
EMISSION UNIT -									
Emission Reduction Description									
Contaminant Emission Reduction Data									
Baseline Period ____ / ____ / ____ to ____ / ____ / ____						Reduction			
						Date		Method	
						/ /			
CAS No.			Contaminant Name			ERC (lbs/yr)			
						Netting		Offset	
-			-						
-			-						
-			-						
Facility to Use Future Reduction									
Name					APPLICATION ID				
					- / - / - / - / - / - / - / - / - / -				
Location Address									
<input type="checkbox"/> City / <input type="checkbox"/> Town / <input type="checkbox"/> Village					State		Zip		

Use of Emission Reduction Credits						<input type="checkbox"/> Continuation Sheet(s)			
EMISSION UNIT -									
Proposed Project Description									
Contaminant Emissions Increase Data									
CAS No.			Contaminant Name			PEP (lbs/yr)			
-			-						
Statement of Compliance									
<input type="checkbox"/> All facilities under the ownership of this "ownership/firm" are operating in compliance with all applicable requirements and state regulations including any compliance certification requirements under Section 114(a)(3) of the Clean Air Act Amendments of 1990, or are meeting the schedule of a consent order.									
Source of Emission Reduction Credit - Facility									
Name					PERMIT ID				
					- / - / - / - / - / - / - / - / - / -				
Location Address									
<input type="checkbox"/> City / <input type="checkbox"/> Town / <input type="checkbox"/> Village					State		Zip		
Emission Unit		CAS No.		Contaminant Name		ERC (lbs/yr)			
						Netting		Offset	
-		-		-					
-		-		-					
-		-		-					



DEC ID									
-									

Supporting Documentation

- P.E. Certification (form attached)
- List of Exempt Activities (form attached)
- Plot Plan
- Methods Used to Determine Compliance (form attached)
- Calculations
  - Air Quality Model ( \_\_\_\_ / \_\_\_\_ / \_\_\_\_ )
  - Confidentiality Justification
  - Ambient Air Monitoring Plan ( \_\_\_\_ / \_\_\_\_ / \_\_\_\_ )
  - Stack Test Protocols/Reports ( \_\_\_\_ / \_\_\_\_ / \_\_\_\_ )
  - Continuous Emissions Monitoring Plans/QA/QC ( \_\_\_\_ / \_\_\_\_ / \_\_\_\_ )
  - MACT Demonstration ( \_\_\_\_ / \_\_\_\_ / \_\_\_\_ )
  - Operational Flexibility: Description of Alternative Operating Scenarios and Protocols
  - Title IV: Application/Registration
  - ERC Quantification (form attached)
  - Use of ERC(s) (form attached)
  - Baseline Period Demonstration
  - Analysis of Contemporaneous Emission Increase/Decrease
  - LAER Demonstration ( \_\_\_\_ / \_\_\_\_ / \_\_\_\_ )
  - BACT Demonstration ( \_\_\_\_ / \_\_\_\_ / \_\_\_\_ )
  - Other Document(s): \_\_\_\_\_ ( \_\_\_\_ / \_\_\_\_ / \_\_\_\_ )
  - \_\_\_\_\_ ( \_\_\_\_ / \_\_\_\_ / \_\_\_\_ )
  - \_\_\_\_\_ ( \_\_\_\_ / \_\_\_\_ / \_\_\_\_ )
  - \_\_\_\_\_ ( \_\_\_\_ / \_\_\_\_ / \_\_\_\_ )
  - \_\_\_\_\_ ( \_\_\_\_ / \_\_\_\_ / \_\_\_\_ )
  - \_\_\_\_\_ ( \_\_\_\_ / \_\_\_\_ / \_\_\_\_ )
  - \_\_\_\_\_ ( \_\_\_\_ / \_\_\_\_ / \_\_\_\_ )
  - \_\_\_\_\_ ( \_\_\_\_ / \_\_\_\_ / \_\_\_\_ )
  - \_\_\_\_\_ ( \_\_\_\_ / \_\_\_\_ / \_\_\_\_ )
  - \_\_\_\_\_ ( \_\_\_\_ / \_\_\_\_ / \_\_\_\_ )
  - \_\_\_\_\_ ( \_\_\_\_ / \_\_\_\_ / \_\_\_\_ )
  - \_\_\_\_\_ ( \_\_\_\_ / \_\_\_\_ / \_\_\_\_ )
  - \_\_\_\_\_ ( \_\_\_\_ / \_\_\_\_ / \_\_\_\_ )

## **APPENDIX B**

### **DATA VALIDATION REPORT AND VALIDATED DATA SUMMARY - SVPMs**

**DATA USABILITY SUMMARY REPORT (DUSR)**  
**VOLATILE ORGANIC COMPOUNDS**  
USEPA Region II –Data Validation

**Project Name:** Naval Weapons Industrial Reserve Plant, Site 1  
**Location:** 999 Oyster Bay Rd, Bethpage, NY  
**Project Number:** 2034-505  
**SDG #:** 1501203  
**Client:** H&S Environmental, Inc.  
**Date:** 02/18/2016  
**Laboratory:** Air Toxics Ltd.  
**Reviewer:** Sherri Pullar

**Summary:**

1. Data validation was performed on the data for twenty (20) air samples and 2 (two) field blank samples were analyzed for Volatiles by TO-15 in accordance to NYSDEC, Analytical Services Protocol (ASP) Format.
2. The samples were collected on 01/13-14/2016. The samples were submitted to Air Toxics Ltd., Folsom, CA on 01/18/2016 for analysis.
3. The USEPA Region-II SOP # HW-31, Revision 4, October 2006, Validating Air Samples Volatile Organic Analysis of Ambient Air in Canister by Method TO-15 was used in evaluating the Volatiles data in this summary report.
4. In general, the data are valid as reported and may be used for decision making purposes. Selected data points were qualified due to nonconformance of certain Quality Control criteria (see discussion below).

## Samples:

The samples included in this review are listed below:

Client Sample ID	Laboratory Sample ID	Collection Date	Analysis	Matrix	Sample Status
BPS1-SVPM2001S-011416	1601227-01A	1/14/2016	VOA	Air	
BPS1-SVPM2001I-011416	1601227-02A	1/14/2016	VOA	Air	
BPS1-SVPM2001D-011416	1601227-03A	1/14/2016	VOA	Air	
BPS1-SVPM2002S-011416	1601227-04A	1/14/2016	VOA	Air	
BPS1-SVPM2002I-011416	1601227-05A	1/14/2016	VOA	Air	
BPS1-SVPM2002D-011416	1601227-06A	1/14/2016	VOA	Air	
BPS1-SVPM2003S-011416	1601227-07A	1/14/2016	VOA	Air	
BPS1-SVPM2003I-011416	1601227-08A	1/14/2016	VOA	Air	
BPS1-SVPM2003D-011416	1601227-09A	1/14/2016	VOA	Air	
BPS1-SVPM2004S-011416	1601227-10A	1/14/2016	VOA	Air	
BPS1-SVPM2004I-011416	1601227-11A	1/14/2016	VOA	Air	
BPS1-SVPM2004D-011416	1601227-12A	1/14/2016	VOA	Air	
BPS1-SVPM2006S-011416	1601227-13A	1/14/2016	VOA	Air	
BPS1-SVPM2006I-011416	1601227-14A	1/14/2016	VOA	Air	
BPS1-SVPM2006D-011416	1601227-15A	1/14/2016	VOA	Air	
BPS1-SVPM2007S-011416	1601227-16A	1/14/2016	VOA	Air	
BPS1-SVPM2007IR-011416	1601227-17A	1/14/2016	VOA	Air	
BPS1-SVPM2007D-011416	1601227-18A	1/14/2016	VOA	Air	
BPS1-DUP01-011416	1601227-19A	1/14/2016	VOA	Air	Field Duplicate of sample BPS1-SVPM2002S-011416
BPS1-DUP02-011416	1601227-20A	1/14/2016	VOA	Air	Field Duplicate of sample BPS1-SVPM2006I-011416
BPS1-FB2001-011316	1601227-21A	1/13/2016	VOA	Air	Field Blank
BPS1-FB2002-011416	1601227-22A	1/14/2016	VOA	Air	Field Blank

## Sample Conditions/Problems:

1. The Traffic Reports/Chain-of-Custody Records, Sampling Report and/or Laboratory Case Narrative did indicate that there were the following problems with sample receipt, condition of samples, analytical problems or special circumstances affecting the quality of the data:
  - a. “The Chain of Custody (COC) information for samples BPS1-SVPM2007IR-011416, BPS1-DUP01-011416 and BPS1-DUP02-011416 did not match the entries on the sample tags with regard to sample identification. Therefore the information on the COC was used to process and report the samples.”
  - b. “The Chain of Custody (COC) information for sample BPS1-SVPM2001I-011416 and BPS1-SVPM2001D-011416 did not match the information on the canister with



- regard to canister identification. The client was notified of the discrepancy and the information on the canister was used to process and report the samples.”
- c. “Despite the use of flow controllers for sample collection, the final canister vacuums for sample BPS1-SVPM2007IR-011416 was measured at ambient pressure. This ambient pressure reading was confirmed by the laboratory upon sample receipt.”

**Actions:** Results for sample BPS1-SVPM2007IR-011416 were qualified as estimated (UJ/J).

**Holding Times:**

1. All air samples were analyzed within the method holding time for summa canisters (30 days). No qualifications were required.

**GC/MS Tuning:**

1. All of the BFB tunes in the initial and continuing calibrations met the percent relative abundance criteria. No qualifications were required.

**Initial Calibration:**

1. Initial calibration curve analyzed on 01/12/2016 (msd17.i) exhibited acceptable %RSDs ( $\leq 30.0\%$ ) for all compounds and average RRF values ( $\geq 0.050$ ) for all compounds. No qualifications were required.

**Continuing Calibration Verification (CCV):**

1. CCV analyzed on 01/21/2016 @ 10:09AM (msd17.i) exhibited acceptable %Ds ( $\leq 30.0\%$ ) for all compounds. No qualifications were required.
2. CCV analyzed on 01/22/2016 @ 10:19AM (msd17.i) exhibited acceptable %Ds ( $\leq 30.0\%$ ) for all compounds. No qualifications were required.

**Surrogates:**

1. All surrogates %REC values for all water samples and associated QC were within the laboratory control limits. No qualifications were required.

**Internal Standard (IS) Area Performance:**

1. All samples exhibited acceptable area count for all three internal standards within the QC limits. No qualifications were required.

**Method Blank (MB), Storage Blank (SB), Trip Blank (TB), Field Blank (FB), Rinsate Blank (RB, Equipment Blank (EB) and Canister Certification:**

1. Method Blank (1601227-23A) analyzed on 01/21/16 was free of contamination. No qualifications were required.
2. Method Blank (1601227-23B) analyzed on 01/22/16 was free of contamination. No qualifications were required.
3. Field Blank (BPS1-FB2001-011316) (1601227-21A) analyzed on 01/22/2016 was free of contamination. No qualifications were required.
4. Field Blank (BPS1-FB2002-011416) (1601227-22A) analyzed on 01/22/2016 was free of contamination. No qualifications were required.

**Laboratory Control Sample (LCS)/ Laboratory Control Sample Duplicate (LCSD):**

1. Laboratory Control Samples (1601227-25A/AA) were analyzed on 01/21/2016. All %RECs and RPDs were within the laboratory control limits. No qualifications were required.
2. Laboratory Control Samples (1601227-25B/BB) were analyzed on 01/22/2016. All %RECs and RPDs were within the laboratory control limits. No qualifications were required.

**Field Duplicate:**

1. Sample BPS1-DUP01-011416 (1601227-19A) was collected as field duplicate for sample BPS1-SVPM2002S-011416 (1601227-07A). Both samples were reported as non-detect, no qualifications were required.
2. Sample BPS1-DUP02-011416 (1601227-20A) was collected as field duplicate for sample BPS1-SVPM2006I-011416 (1601227-14A). RPDs were within the control limits (<30%). No qualifications were required.

Field Sample	Compound	Analytical Method	Result	Units	Field Duplicate	Result	Units	RPD	Qualifier
BPS1-SVPM2006I-011416	Cis-1,2-Dichloroethene	TO-15	260	µg/m <sup>3</sup>	BPS1-DUP02-011416	280	µg/m <sup>3</sup>	7.4	None

Field Sample	Compound	Analytical Method	Result	Units	Field Duplicate	Result	Units	RPD	Qualifier
BPS1-SVPM2006I-011416	Tetrachloroethene	TO-15	2.2	µg/m <sup>3</sup>	BPS1-DUP02-011416	2.1	µg/m <sup>3</sup>	4.7	None
BPS1-SVPM2006I-011416	Trans-1,2-Dichloroethene	TO-15	3.4	µg/m <sup>3</sup>	BPS1-DUP02-011416	3.6	µg/m <sup>3</sup>	5.7	None
BPS1-SVPM2006I-011416	Trichloroethene	TO-15	48	µg/m <sup>3</sup>	BPS1-DUP02-011416	61	µg/m <sup>3</sup>	23.9	None

### **Sample Duplicate:**

1. Sample duplicate was performed on sample BPS1-SVPM2001I-011416 (151203-02A/AA). All RPDs were ≤ 30%. No qualifications were required.
2. Sample duplicate was performed on sample BPS1-FB2002-011415 (1501203-22A/AA). All RPDs were ≤ 30%. No qualifications were required.

### **Target Compound Identification:**

1. All Relative Retention Times (RRTs) of the reported compounds were within ± 0.06 RRT units of the standard (opening CCV).
2. Sample compound spectra were compared against the laboratory standard spectra.
3. No QC deviations were observed.

### **Compound Quantitation and Reported Detection Limits:**

1. All sample results were reported within the linear calibration range. No qualifications were required.
2. Manual Calculation:

$$\text{Concentration } (\mu\text{g}/\text{m}^3) = \frac{\text{Result (ppbv)} \times \text{Molecular weight} \times \text{DF}}{24.46}$$

BPS1-SVPM2004D-011416 (1601227-12A)

Tetrachloroethene

Result (ppbv) = 0.35010

Molecular Weight @ 25°C = 165.83

DF = 1.51

$$\text{Concentration } (\mu\text{g}/\text{m}^3) = \frac{0.35010 \times 165.83 \times 1.51}{24.45} = 3.5855 \mu\text{g}/\text{m}^3$$

Compound	Laboratory ( $\mu\text{g}/\text{m}^3$ )	Validation ( $\mu\text{g}/\text{m}^3$ )	%D
Tetrachloroethene	3.6	3.6	0.0

**Comments:**

1. Volatile data package meet requirement for New York State Department of Environmental Conservation (NYSDEC) Analytical Services Protocol (ASP) Category B Deliverables.
2. Validation qualifiers (if required) were entered into the EDD for SDG: 1601227.
3. Summary of the qualified data is listed in the Data Summary Table for SDG: 1601227.

**NWIRP BETHPAGE, BETHPAGE, NY****SITE 1****DATA SUMMARY TABLE****AIR****SDG: 1601227**

Sample Name	Lab ID	Analytical Name	Analytical Method	Sample Date	Result	Unit	Qualifier	LOD	LOQ
BPS1-SVPM2001S-011416	1601227-01A	1,1,1-Trichloroethane	TO-15	20160121	3.8	UG_M3	U	3	3.8
BPS1-SVPM2001S-011416	1601227-01A	1,1-Dichloroethane	TO-15	20160121	2.8	UG_M3	U	2.3	2.8
BPS1-SVPM2001S-011416	1601227-01A	1,1-Dichloroethene	TO-15	20160121	2.8	UG_M3	U	2.2	2.8
BPS1-SVPM2001S-011416	1601227-01A	1,2-Dichloroethane	TO-15	20160121	2.8	UG_M3	U	2.3	2.8
BPS1-SVPM2001S-011416	1601227-01A	cis-1,2-Dichloroethene	TO-15	20160121	2.8	UG_M3	U	2.2	2.8
BPS1-SVPM2001S-011416	1601227-01A	tetrachloroethene	TO-15	20160121	4.7	UG_M3	U	3.8	4.7
BPS1-SVPM2001S-011416	1601227-01A	trans-1,2-Dichloroethene	TO-15	20160121	2.8	UG_M3	U	2.2	2.8
BPS1-SVPM2001S-011416	1601227-01A	Trichloroethene	TO-15	20160121	3.8	UG_M3	U	3	3.8
BPS1-SVPM2001S-011416	1601227-01A	Vinyl Chloride	TO-15	20160121	1.8	UG_M3	U	1.4	1.8
BPS1-SVPM2001I-011416	1601227-02A	1,1,1-Trichloroethane	TO-15	20160121	4	UG_M3	U	3.2	4
BPS1-SVPM2001I-011416	1601227-02A	1,1-Dichloroethane	TO-15	20160121	3	UG_M3	U	2.4	3
BPS1-SVPM2001I-011416	1601227-02A	1,1-Dichloroethene	TO-15	20160121	2.9	UG_M3	U	2.3	2.9
BPS1-SVPM2001I-011416	1601227-02A	1,2-Dichloroethane	TO-15	20160121	3	UG_M3	U	2.4	3
BPS1-SVPM2001I-011416	1601227-02A	cis-1,2-Dichloroethene	TO-15	20160121	2.9	UG_M3	U	2.3	2.9
BPS1-SVPM2001I-011416	1601227-02A	tetrachloroethene	TO-15	20160121	1.2	UG_M3	J	4	5
BPS1-SVPM2001I-011416	1601227-02A	trans-1,2-Dichloroethene	TO-15	20160121	2.9	UG_M3	U	2.3	2.9
BPS1-SVPM2001I-011416	1601227-02A	Trichloroethene	TO-15	20160121	4	UG_M3	U	3.2	4
BPS1-SVPM2001I-011416	1601227-02A	Vinyl Chloride	TO-15	20160121	1.9	UG_M3	U	1.5	1.9
BPS1-SVPM2001D-011416	1601227-03A	1,1,1-Trichloroethane	TO-15	20160121	5.3	UG_M3	U	4.2	5.3
BPS1-SVPM2001D-011416	1601227-03A	1,1-Dichloroethane	TO-15	20160121	3.9	UG_M3	U	3.1	3.9
BPS1-SVPM2001D-011416	1601227-03A	1,1-Dichloroethene	TO-15	20160121	3.8	UG_M3	U	3.1	3.8
BPS1-SVPM2001D-011416	1601227-03A	1,2-Dichloroethane	TO-15	20160121	3.9	UG_M3	U	3.1	3.9
BPS1-SVPM2001D-011416	1601227-03A	cis-1,2-Dichloroethene	TO-15	20160121	6.3	UG_M3		3.1	3.8
BPS1-SVPM2001D-011416	1601227-03A	tetrachloroethene	TO-15	20160121	10	UG_M3		5.3	6.6
BPS1-SVPM2001D-011416	1601227-03A	trans-1,2-Dichloroethene	TO-15	20160121	3.8	UG_M3	U	3.1	3.8
BPS1-SVPM2001D-011416	1601227-03A	Trichloroethene	TO-15	20160121	3.9	UG_M3	J	4.2	5.2
BPS1-SVPM2001D-011416	1601227-03A	Vinyl Chloride	TO-15	20160121	2.5	UG_M3	U	2	2.5
BPS1-SVPM2002S-011416	1601227-04A	1,1,1-Trichloroethane	TO-15	20160121	4.2	UG_M3	U	3.4	4.2
BPS1-SVPM2002S-011416	1601227-04A	1,1-Dichloroethane	TO-15	20160121	3.1	UG_M3	U	2.5	3.1
BPS1-SVPM2002S-011416	1601227-04A	1,1-Dichloroethene	TO-15	20160121	3.1	UG_M3	U	2.4	3.1
BPS1-SVPM2002S-011416	1601227-04A	1,2-Dichloroethane	TO-15	20160121	3.1	UG_M3	U	2.5	3.1
BPS1-SVPM2002S-011416	1601227-04A	cis-1,2-Dichloroethene	TO-15	20160121	3.1	UG_M3	U	2.4	3.1
BPS1-SVPM2002S-011416	1601227-04A	tetrachloroethene	TO-15	20160121	5.2	UG_M3	U	4.2	5.2
BPS1-SVPM2002S-011416	1601227-04A	trans-1,2-Dichloroethene	TO-15	20160121	3.1	UG_M3	U	2.4	3.1
BPS1-SVPM2002S-011416	1601227-04A	Trichloroethene	TO-15	20160121	4.2	UG_M3	U	3.3	4.2



NWIRP BETHPAGE, BETHPAGE, NY

SITE 1

DATA SUMMARY TABLE

AIR

SDG: 1601227

Sample Name	Lab ID	Analytical Name	Analytical Method	Sample Date	Result	Unit	Qualifier	LOD	LOQ
BPS1-SVPM2002S-011416	1601227-04A	Vinyl Chloride	TO-15	20160121	2	UG_M3	U	1.6	2
BPS1-SVPM2002I-011416	1601227-05A	1,1,1-Trichloroethane	TO-15	20160121	4	UG_M3	U	3.2	4
BPS1-SVPM2002I-011416	1601227-05A	1,1-Dichloroethane	TO-15	20160121	2.9	UG_M3	U	2.3	2.9
BPS1-SVPM2002I-011416	1601227-05A	1,1-Dichloroethene	TO-15	20160121	2.9	UG_M3	U	2.3	2.9
BPS1-SVPM2002I-011416	1601227-05A	1,2-Dichloroethane	TO-15	20160121	2.9	UG_M3	U	2.3	2.9
BPS1-SVPM2002I-011416	1601227-05A	cis-1,2-Dichloroethene	TO-15	20160121	2.9	UG_M3	U	2.3	2.9
BPS1-SVPM2002I-011416	1601227-05A	tetrachloroethene	TO-15	20160121	4.9	UG_M3	U	3.9	4.9
BPS1-SVPM2002I-011416	1601227-05A	trans-1,2-Dichloroethene	TO-15	20160121	2.9	UG_M3	U	2.3	2.9
BPS1-SVPM2002I-011416	1601227-05A	Trichloroethene	TO-15	20160121	3.9	UG_M3	U	3.1	3.9
BPS1-SVPM2002I-011416	1601227-05A	Vinyl Chloride	TO-15	20160121	1.8	UG_M3	U	1.5	1.8
BPS1-SVPM2002D-011416	1601227-06A	1,1,1-Trichloroethane	TO-15	20160121	3.9	UG_M3	U	3.1	3.9
BPS1-SVPM2002D-011416	1601227-06A	1,1-Dichloroethane	TO-15	20160121	2.9	UG_M3	U	2.3	2.9
BPS1-SVPM2002D-011416	1601227-06A	1,1-Dichloroethene	TO-15	20160121	2.8	UG_M3	U	2.2	2.8
BPS1-SVPM2002D-011416	1601227-06A	1,2-Dichloroethane	TO-15	20160121	2.9	UG_M3	U	2.3	2.9
BPS1-SVPM2002D-011416	1601227-06A	cis-1,2-Dichloroethene	TO-15	20160121	2.8	UG_M3	U	2.2	2.8
BPS1-SVPM2002D-011416	1601227-06A	tetrachloroethene	TO-15	20160121	4.8	UG_M3	U	3.8	4.8
BPS1-SVPM2002D-011416	1601227-06A	trans-1,2-Dichloroethene	TO-15	20160121	2.8	UG_M3	U	2.2	2.8
BPS1-SVPM2002D-011416	1601227-06A	Trichloroethene	TO-15	20160121	3.8	UG_M3	U	3	3.8
BPS1-SVPM2002D-011416	1601227-06A	Vinyl Chloride	TO-15	20160121	1.8	UG_M3	U	1.4	1.8
BPS1-SVPM2003S-011416	1601227-07A	1,1,1-Trichloroethane	TO-15	20160121	3.8	UG_M3	U	3	3.8
BPS1-SVPM2003S-011416	1601227-07A	1,1-Dichloroethane	TO-15	20160121	2.8	UG_M3	U	2.2	2.8
BPS1-SVPM2003S-011416	1601227-07A	1,1-Dichloroethene	TO-15	20160121	2.7	UG_M3	U	2.2	2.7
BPS1-SVPM2003S-011416	1601227-07A	1,2-Dichloroethane	TO-15	20160121	2.8	UG_M3	U	2.2	2.8
BPS1-SVPM2003S-011416	1601227-07A	cis-1,2-Dichloroethene	TO-15	20160121	2.7	UG_M3	U	2.2	2.7
BPS1-SVPM2003S-011416	1601227-07A	tetrachloroethene	TO-15	20160121	4.7	UG_M3	U	3.7	4.7
BPS1-SVPM2003S-011416	1601227-07A	trans-1,2-Dichloroethene	TO-15	20160121	2.7	UG_M3	U	2.2	2.7
BPS1-SVPM2003S-011416	1601227-07A	Trichloroethene	TO-15	20160121	3.7	UG_M3	U	3	3.7
BPS1-SVPM2003S-011416	1601227-07A	Vinyl Chloride	TO-15	20160121	1.8	UG_M3	U	1.4	1.8
BPS1-SVPM2003I-011416	1601227-08A	1,1,1-Trichloroethane	TO-15	20160121	3.8	UG_M3	U	3	3.8
BPS1-SVPM2003I-011416	1601227-08A	1,1-Dichloroethane	TO-15	20160121	2.8	UG_M3	U	2.2	2.8
BPS1-SVPM2003I-011416	1601227-08A	1,1-Dichloroethene	TO-15	20160121	2.8	UG_M3	U	2.2	2.8
BPS1-SVPM2003I-011416	1601227-08A	1,2-Dichloroethane	TO-15	20160121	2.8	UG_M3	U	2.2	2.8
BPS1-SVPM2003I-011416	1601227-08A	cis-1,2-Dichloroethene	TO-15	20160121	2.8	UG_M3	U	2.2	2.8
BPS1-SVPM2003I-011416	1601227-08A	tetrachloroethene	TO-15	20160121	0.89	UG_M3	J	3.8	4.7
BPS1-SVPM2003I-011416	1601227-08A	trans-1,2-Dichloroethene	TO-15	20160121	2.8	UG_M3	U	2.2	2.8

**NWIRP BETHPAGE, BETHPAGE, NY****SITE 1****DATA SUMMARY TABLE****AIR****SDG: 1601227**

Sample Name	Lab ID	Analytical Name	Analytical Method	Sample Date	Result	Unit	Qualifier	LOD	LOQ
BPS1-SVPM2003I-011416	1601227-08A	Trichloroethene	TO-15	20160121	3.7	UG_M3	U	3	3.7
BPS1-SVPM2003I-011416	1601227-08A	Vinyl Chloride	TO-15	20160121	1.8	UG_M3	U	1.4	1.8
BPS1-SVPM2003D-011416	1601227-09A	1,1,1-Trichloroethane	TO-15	20160121	4	UG_M3	U	3.2	4
BPS1-SVPM2003D-011416	1601227-09A	1,1-Dichloroethane	TO-15	20160121	3	UG_M3	U	2.4	3
BPS1-SVPM2003D-011416	1601227-09A	1,1-Dichloroethene	TO-15	20160121	2.9	UG_M3	U	2.3	2.9
BPS1-SVPM2003D-011416	1601227-09A	1,2-Dichloroethane	TO-15	20160121	3	UG_M3	U	2.4	3
BPS1-SVPM2003D-011416	1601227-09A	cis-1,2-Dichloroethene	TO-15	20160121	2.9	UG_M3	U	2.3	2.9
BPS1-SVPM2003D-011416	1601227-09A	tetrachloroethene	TO-15	20160121	5	UG_M3	U	4	5
BPS1-SVPM2003D-011416	1601227-09A	trans-1,2-Dichloroethene	TO-15	20160121	2.9	UG_M3	U	2.3	2.9
BPS1-SVPM2003D-011416	1601227-09A	Trichloroethene	TO-15	20160121	4	UG_M3	U	3.2	4
BPS1-SVPM2003D-011416	1601227-09A	Vinyl Chloride	TO-15	20160121	1.9	UG_M3	U	1.5	1.9
BPS1-SVPM2004S-011416	1601227-10A	1,1,1-Trichloroethane	TO-15	20160121	4.1	UG_M3	U	3.3	4.1
BPS1-SVPM2004S-011416	1601227-10A	1,1-Dichloroethane	TO-15	20160121	3	UG_M3	U	2.4	3
BPS1-SVPM2004S-011416	1601227-10A	1,1-Dichloroethene	TO-15	20160121	3	UG_M3	U	2.4	3
BPS1-SVPM2004S-011416	1601227-10A	1,2-Dichloroethane	TO-15	20160121	3	UG_M3	U	2.4	3
BPS1-SVPM2004S-011416	1601227-10A	cis-1,2-Dichloroethene	TO-15	20160121	3	UG_M3	U	2.4	3
BPS1-SVPM2004S-011416	1601227-10A	tetrachloroethene	TO-15	20160121	5.1	UG_M3	U	4.1	5.1
BPS1-SVPM2004S-011416	1601227-10A	trans-1,2-Dichloroethene	TO-15	20160121	3	UG_M3	U	2.4	3
BPS1-SVPM2004S-011416	1601227-10A	Trichloroethene	TO-15	20160121	4	UG_M3	U	3.2	4
BPS1-SVPM2004S-011416	1601227-10A	Vinyl Chloride	TO-15	20160121	1.9	UG_M3	U	1.5	1.9
BPS1-SVPM2004I-011416	1601227-11A	1,1,1-Trichloroethane	TO-15	20160121	4	UG_M3	U	3.2	4
BPS1-SVPM2004I-011416	1601227-11A	1,1-Dichloroethane	TO-15	20160121	2.9	UG_M3	U	2.3	2.9
BPS1-SVPM2004I-011416	1601227-11A	1,1-Dichloroethene	TO-15	20160121	2.9	UG_M3	U	2.3	2.9
BPS1-SVPM2004I-011416	1601227-11A	1,2-Dichloroethane	TO-15	20160121	2.9	UG_M3	U	2.3	2.9
BPS1-SVPM2004I-011416	1601227-11A	cis-1,2-Dichloroethene	TO-15	20160121	2.9	UG_M3	U	2.3	2.9
BPS1-SVPM2004I-011416	1601227-11A	tetrachloroethene	TO-15	20160121	0.83	UG_M3	J	3.9	4.9
BPS1-SVPM2004I-011416	1601227-11A	trans-1,2-Dichloroethene	TO-15	20160121	2.9	UG_M3	U	2.3	2.9
BPS1-SVPM2004I-011416	1601227-11A	Trichloroethene	TO-15	20160121	3.9	UG_M3	U	3.1	3.9
BPS1-SVPM2004I-011416	1601227-11A	Vinyl Chloride	TO-15	20160121	1.8	UG_M3	U	1.5	1.8
BPS1-SVPM2004D-011416	1601227-12A	1,1,1-Trichloroethane	TO-15	20160121	4.1	UG_M3	U	3.3	4.1
BPS1-SVPM2004D-011416	1601227-12A	1,1-Dichloroethane	TO-15	20160121	3	UG_M3	U	2.4	3
BPS1-SVPM2004D-011416	1601227-12A	1,1-Dichloroethene	TO-15	20160121	3	UG_M3	U	2.4	3
BPS1-SVPM2004D-011416	1601227-12A	1,2-Dichloroethane	TO-15	20160121	3	UG_M3	U	2.4	3
BPS1-SVPM2004D-011416	1601227-12A	cis-1,2-Dichloroethene	TO-15	20160121	3	UG_M3	U	2.4	3
BPS1-SVPM2004D-011416	1601227-12A	tetrachloroethene	TO-15	20160121	3.6	UG_M3	J	4.1	5.1



**NWIRP BETHPAGE, BETHPAGE, NY****SITE 1****DATA SUMMARY TABLE****AIR****SDG: 1601227**

Sample Name	Lab ID	Analytical Name	Analytical Method	Sample Date	Result	Unit	Qualifier	LOD	LOQ
BPS1-SVPM2004D-011416	1601227-12A	trans-1,2-Dichloroethene	TO-15	20160121	3	UG_M3	U	2.4	3
BPS1-SVPM2004D-011416	1601227-12A	Trichloroethene	TO-15	20160121	4	UG_M3	U	3.2	4
BPS1-SVPM2004D-011416	1601227-12A	Vinyl Chloride	TO-15	20160121	1.9	UG_M3	U	1.5	1.9
BPS1-SVPM2006S-011416	1601227-13A	1,1,1-Trichloroethane	TO-15	20160121	3.9	UG_M3	U	3.1	3.9
BPS1-SVPM2006S-011416	1601227-13A	1,1-Dichloroethane	TO-15	20160121	2.9	UG_M3	U	2.3	2.9
BPS1-SVPM2006S-011416	1601227-13A	1,1-Dichloroethene	TO-15	20160121	2.8	UG_M3	U	2.2	2.8
BPS1-SVPM2006S-011416	1601227-13A	1,2-Dichloroethane	TO-15	20160121	2.9	UG_M3	U	2.3	2.9
BPS1-SVPM2006S-011416	1601227-13A	cis-1,2-Dichloroethene	TO-15	20160121	3.4	UG_M3		2.2	2.8
BPS1-SVPM2006S-011416	1601227-13A	tetrachloroethene	TO-15	20160121	4.8	UG_M3	U	3.8	4.8
BPS1-SVPM2006S-011416	1601227-13A	trans-1,2-Dichloroethene	TO-15	20160121	2.8	UG_M3	U	2.2	2.8
BPS1-SVPM2006S-011416	1601227-13A	Trichloroethene	TO-15	20160121	1.6	UG_M3	J	3	3.8
BPS1-SVPM2006S-011416	1601227-13A	Vinyl Chloride	TO-15	20160121	1.8	UG_M3	U	1.4	1.8
BPS1-SVPM2006I-011416	1601227-14A	1,1,1-Trichloroethane	TO-15	20160121	3.9	UG_M3	U	3.1	3.9
BPS1-SVPM2006I-011416	1601227-14A	1,1-Dichloroethane	TO-15	20160121	2.9	UG_M3	U	2.3	2.9
BPS1-SVPM2006I-011416	1601227-14A	1,1-Dichloroethene	TO-15	20160121	2.8	UG_M3	U	2.3	2.8
BPS1-SVPM2006I-011416	1601227-14A	1,2-Dichloroethane	TO-15	20160121	2.9	UG_M3	U	2.3	2.9
BPS1-SVPM2006I-011416	1601227-14A	cis-1,2-Dichloroethene	TO-15	20160121	260	UG_M3		2.3	2.8
BPS1-SVPM2006I-011416	1601227-14A	tetrachloroethene	TO-15	20160121	2.2	UG_M3	J	3.9	4.8
BPS1-SVPM2006I-011416	1601227-14A	trans-1,2-Dichloroethene	TO-15	20160121	3.4	UG_M3		2.3	2.8
BPS1-SVPM2006I-011416	1601227-14A	Trichloroethene	TO-15	20160121	48	UG_M3		3.1	3.8
BPS1-SVPM2006I-011416	1601227-14A	Vinyl Chloride	TO-15	20160121	1.8	UG_M3	U	1.5	1.8
BPS1-SVPM2006D-011416	1601227-15A	1,1,1-Trichloroethane	TO-15	20160121	4.2	UG_M3	U	3.3	4.2
BPS1-SVPM2006D-011416	1601227-15A	1,1-Dichloroethane	TO-15	20160121	3.1	UG_M3	U	2.5	3.1
BPS1-SVPM2006D-011416	1601227-15A	1,1-Dichloroethene	TO-15	20160121	3	UG_M3	U	2.4	3
BPS1-SVPM2006D-011416	1601227-15A	1,2-Dichloroethane	TO-15	20160121	3.1	UG_M3	U	2.5	3.1
BPS1-SVPM2006D-011416	1601227-15A	cis-1,2-Dichloroethene	TO-15	20160121	320	UG_M3		2.4	3
BPS1-SVPM2006D-011416	1601227-15A	tetrachloroethene	TO-15	20160121	1.9	UG_M3	J	4.2	5.2
BPS1-SVPM2006D-011416	1601227-15A	trans-1,2-Dichloroethene	TO-15	20160121	3.3	UG_M3		2.4	3
BPS1-SVPM2006D-011416	1601227-15A	Trichloroethene	TO-15	20160121	47	UG_M3		3.3	4.1
BPS1-SVPM2006D-011416	1601227-15A	Vinyl Chloride	TO-15	20160121	2	UG_M3	U	1.6	2
BPS1-SVPM2007S-011416	1601227-16A	1,1,1-Trichloroethane	TO-15	20160121	4.1	UG_M3	U	3.3	4.1
BPS1-SVPM2007S-011416	1601227-16A	1,1-Dichloroethane	TO-15	20160121	3.1	UG_M3	U	2.5	3.1
BPS1-SVPM2007S-011416	1601227-16A	1,1-Dichloroethene	TO-15	20160121	3	UG_M3	U	2.4	3
BPS1-SVPM2007S-011416	1601227-16A	1,2-Dichloroethane	TO-15	20160121	3.1	UG_M3	U	2.5	3.1
BPS1-SVPM2007S-011416	1601227-16A	cis-1,2-Dichloroethene	TO-15	20160121	3	UG_M3	U	2.4	3





NWIRP BETHPAGE, BETHPAGE, NY

SITE 1

DATA SUMMARY TABLE

AIR

SDG: 1601227

Sample Name	Lab ID	Analytical Name	Analytical Method	Sample Date	Result	Unit	Qualifier	LOD	LOQ
BPS1-SVPM2007S-011416	1601227-16A	tetrachloroethene	TO-15	20160121	0.89	UG_M3	J	4.1	5.2
BPS1-SVPM2007S-011416	1601227-16A	trans-1,2-Dichloroethene	TO-15	20160121	3	UG_M3	U	2.4	3
BPS1-SVPM2007S-011416	1601227-16A	Trichloroethene	TO-15	20160121	4.1	UG_M3	U	3.3	4.1
BPS1-SVPM2007S-011416	1601227-16A	Vinyl Chloride	TO-15	20160121	1.9	UG_M3	U	1.6	1.9
BPS1-SVPM2007IR-011416	1601227-17A	1,1,1-Trichloroethane	TO-15	20160121	3.6	UG_M3	UJ	2.9	3.6
BPS1-SVPM2007IR-011416	1601227-17A	1,1-Dichloroethane	TO-15	20160121	2.7	UG_M3	UJ	2.1	2.7
BPS1-SVPM2007IR-011416	1601227-17A	1,1-Dichloroethene	TO-15	20160121	2.6	UG_M3	UJ	2.1	2.6
BPS1-SVPM2007IR-011416	1601227-17A	1,2-Dichloroethane	TO-15	20160121	2.7	UG_M3	UJ	2.1	2.7
BPS1-SVPM2007IR-011416	1601227-17A	cis-1,2-Dichloroethene	TO-15	20160121	4.4	UG_M3	J	2.1	2.6
BPS1-SVPM2007IR-011416	1601227-17A	tetrachloroethene	TO-15	20160121	2.3	UG_M3	J	3.6	4.5
BPS1-SVPM2007IR-011416	1601227-17A	trans-1,2-Dichloroethene	TO-15	20160121	2.6	UG_M3	UJ	2.1	2.6
BPS1-SVPM2007IR-011416	1601227-17A	Trichloroethene	TO-15	20160121	1.9	UG_M3	J	2.8	3.5
BPS1-SVPM2007IR-011416	1601227-17A	Vinyl Chloride	TO-15	20160121	1.7	UG_M3	UJ	1.3	1.7
BPS1-SVPM2007D-011416	1601227-18A	1,1,1-Trichloroethane	TO-15	20160121	0.87	UG_M3	J	3.3	4.2
BPS1-SVPM2007D-011416	1601227-18A	1,1-Dichloroethane	TO-15	20160121	3.1	UG_M3	U	2.5	3.1
BPS1-SVPM2007D-011416	1601227-18A	1,1-Dichloroethene	TO-15	20160121	3	UG_M3	U	2.4	3
BPS1-SVPM2007D-011416	1601227-18A	1,2-Dichloroethane	TO-15	20160121	3.1	UG_M3	U	2.5	3.1
BPS1-SVPM2007D-011416	1601227-18A	cis-1,2-Dichloroethene	TO-15	20160121	3.1	UG_M3		2.4	3
BPS1-SVPM2007D-011416	1601227-18A	tetrachloroethene	TO-15	20160121	2	UG_M3	J	4.2	5.2
BPS1-SVPM2007D-011416	1601227-18A	trans-1,2-Dichloroethene	TO-15	20160121	3	UG_M3	U	2.4	3
BPS1-SVPM2007D-011416	1601227-18A	Trichloroethene	TO-15	20160121	2.7	UG_M3	J	3.3	4.1
BPS1-SVPM2007D-011416	1601227-18A	Vinyl Chloride	TO-15	20160121	2	UG_M3	U	1.6	2
BPS1-DUP01-011416	1601227-19A	1,1,1-Trichloroethane	TO-15	20160121	3.9	UG_M3	U	3.1	3.9
BPS1-DUP01-011416	1601227-19A	1,1-Dichloroethane	TO-15	20160121	2.9	UG_M3	U	2.3	2.9
BPS1-DUP01-011416	1601227-19A	1,1-Dichloroethene	TO-15	20160121	2.8	UG_M3	U	2.2	2.8
BPS1-DUP01-011416	1601227-19A	1,2-Dichloroethane	TO-15	20160121	2.9	UG_M3	U	2.3	2.9
BPS1-DUP01-011416	1601227-19A	cis-1,2-Dichloroethene	TO-15	20160121	2.8	UG_M3	U	2.2	2.8
BPS1-DUP01-011416	1601227-19A	tetrachloroethene	TO-15	20160121	4.8	UG_M3	U	3.8	4.8
BPS1-DUP01-011416	1601227-19A	trans-1,2-Dichloroethene	TO-15	20160121	2.8	UG_M3	U	2.2	2.8
BPS1-DUP01-011416	1601227-19A	Trichloroethene	TO-15	20160121	3.8	UG_M3	U	3	3.8
BPS1-DUP01-011416	1601227-19A	Vinyl Chloride	TO-15	20160121	1.8	UG_M3	U	1.4	1.8
BPS1-DUP02-011416	1601227-20A	1,1,1-Trichloroethane	TO-15	20160121	4.1	UG_M3	U	3.3	4.1
BPS1-DUP02-011416	1601227-20A	1,1-Dichloroethane	TO-15	20160121	3.1	UG_M3	U	2.5	3.1
BPS1-DUP02-011416	1601227-20A	1,1-Dichloroethene	TO-15	20160121	3	UG_M3	U	2.4	3
BPS1-DUP02-011416	1601227-20A	1,2-Dichloroethane	TO-15	20160121	3.1	UG_M3	U	2.5	3.1



NWIRP BETHPAGE, BETHPAGE, NY

SITE 1

DATA SUMMARY TABLE

AIR

SDG: 1601227


Sample Name	Lab ID	Analytical Name	Analytical Method	Sample Date	Result	Unit	Qualifier	LOD	LOQ
BPS1-DUP02-011416	1601227-20A	cis-1,2-Dichloroethene	TO-15	20160121	280	UG_M3		2.4	3
BPS1-DUP02-011416	1601227-20A	tetrachloroethene	TO-15	20160121	2.1	UG_M3	J	4.1	5.2
BPS1-DUP02-011416	1601227-20A	trans-1,2-Dichloroethene	TO-15	20160121	3.6	UG_M3		2.4	3
BPS1-DUP02-011416	1601227-20A	Trichloroethene	TO-15	20160121	61	UG_M3		3.3	4.1
BPS1-DUP02-011416	1601227-20A	Vinyl Chloride	TO-15	20160121	1.9	UG_M3	U	1.6	1.9
BPS1-FB2001-011316	1601227-21A	1,1,1-Trichloroethane	TO-15	20160122	4.4	UG_M3	U	3.6	4.4
BPS1-FB2001-011316	1601227-21A	1,1-Dichloroethane	TO-15	20160122	3.3	UG_M3	U	2.6	3.3
BPS1-FB2001-011316	1601227-21A	1,1-Dichloroethene	TO-15	20160122	3.2	UG_M3	U	2.6	3.2
BPS1-FB2001-011316	1601227-21A	1,2-Dichloroethane	TO-15	20160122	3.3	UG_M3	U	2.6	3.3
BPS1-FB2001-011316	1601227-21A	cis-1,2-Dichloroethene	TO-15	20160122	3.2	UG_M3	U	2.6	3.2
BPS1-FB2001-011316	1601227-21A	tetrachloroethene	TO-15	20160122	5.5	UG_M3	U	4.4	5.5
BPS1-FB2001-011316	1601227-21A	trans-1,2-Dichloroethene	TO-15	20160122	3.2	UG_M3	U	2.6	3.2
BPS1-FB2001-011316	1601227-21A	Trichloroethene	TO-15	20160122	4.4	UG_M3	U	3.5	4.4
BPS1-FB2001-011316	1601227-21A	Vinyl Chloride	TO-15	20160122	2.1	UG_M3	U	1.7	2.1
BPS1-FB2002-011416	1601227-22A	1,1,1-Trichloroethane	TO-15	20160122	3.8	UG_M3	U	3	3.8
BPS1-FB2002-011416	1601227-22A	1,1-Dichloroethane	TO-15	20160122	2.8	UG_M3	U	2.3	2.8
BPS1-FB2002-011416	1601227-22A	1,1-Dichloroethene	TO-15	20160122	2.8	UG_M3	U	2.2	2.8
BPS1-FB2002-011416	1601227-22A	1,2-Dichloroethane	TO-15	20160122	2.8	UG_M3	U	2.3	2.8
BPS1-FB2002-011416	1601227-22A	cis-1,2-Dichloroethene	TO-15	20160122	2.8	UG_M3	U	2.2	2.8
BPS1-FB2002-011416	1601227-22A	tetrachloroethene	TO-15	20160122	4.7	UG_M3	U	3.8	4.7
BPS1-FB2002-011416	1601227-22A	trans-1,2-Dichloroethene	TO-15	20160122	2.8	UG_M3	U	2.2	2.8
BPS1-FB2002-011416	1601227-22A	Trichloroethene	TO-15	20160122	3.8	UG_M3	U	3	3.8
BPS1-FB2002-011416	1601227-22A	Vinyl Chloride	TO-15	20160122	1.8	UG_M3	U	1.4	1.8

## **APPENDIX C**


### **VAPOR CONCENTRATION TREND GRAPHS – SVEWs**

**Soil Vapor Extraction Containment System  
 Site 1, Former Drum Marshalling Yard  
 Naval Weapons Industrial Reserve Plant - Bethpage, NY  
 Vapor Concentration Trends of Select and Total VOCs  
 SVEWs**


**COMBINED INFLUENT**




**Soil Vapor Extraction Containment System**  
**Site 1, Former Drum Marshalling Yard**  
**Naval Weapons Industrial Reserve Plant - Bethpage, NY**  
**Concentration Trends of Select VOCs**  
**SVEWs**  
**SV-101I**



Soil Vapor Extraction Containment System  
Site 1, Former Drum Marshalling Yard  
Naval Weapons Industrial Reserve Plant - Bethpage, NY  
Concentration Trends of Select VOCs  
SVEs  
SV-101D




**Soil Vapor Extraction Containment System**  
**Site 1, Former Drum Marshalling Yard**  
**Naval Weapons Industrial Reserve Plant - Bethpage, NY**  
**Concentration Trends of Select VOCs**  
**SVEWs**  
**SV-101D (smaller scale)**







**Soil Vapor Extraction Containment System**  
**Site 1, Former Drum Marshalling Yard**  
**Naval Weapons Industrial Reserve Plant - Bethpage, NY**  
**Concentration Trends of Select VOCs**  
**SVEs**  
**SV102I**




**Soil Vapor Extraction Containment System**  
**Site 1, Former Drum Marshalling Yard**  
**Naval Weapons Industrial Reserve Plant - Bethpage, NY**  
**Concentration Trends of Select VOCs**  
**SVEs**  
**SV-102D**




**Soil Vapor Extraction Containment System**  
**Site 1, Former Drum Marshalling Yard**  
**Naval Weapons Industrial Reserve Plant - Bethpage, NY**  
**Concentration Trends of Select VOCs**  
**SVEs**  
**SV-103I**




**Soil Vapor Extraction Containment System**  
**Site 1, Former Drum Marshalling Yard**  
**Naval Weapons Industrial Reserve Plant - Bethpage, NY**  
**Concentration Trends of Select VOCs**  
**SVEs**  
**SV103D**




**Soil Vapor Extraction Containment System**  
**Site 1, Former Drum Marshalling Yard**  
**Naval Weapons Industrial Reserve Plant - Bethpage, NY**  
**Concentration Trends of Select VOCs**  
**SVEs**  
**SV104I**



**Soil Vapor Extraction Containment System**  
**Site 1, Former Drum Marshalling Yard**  
**Naval Weapons Industrial Reserve Plant - Bethpage, NY**  
**Concentration Trends of Select VOCs**  
**SVEs**  
**SV-104D**




**Soil Vapor Extraction Containment System**  
**Site 1, Former Drum Marshalling Yard**  
**Naval Weapons Industrial Reserve Plant - Bethpage, NY**  
**Concentration Trends of Select VOCs**  
**SVEWs**  
**SV-105I**







**Soil Vapor Extraction Containment System**  
**Site 1, Former Drum Marshalling Yard**  
**Naval Weapons Industrial Reserve Plant - Bethpage, NY**  
**Concentration Trends of Select VOCs**  
**SVEs**  
**SV-105D**




Soil Vapor Extraction Containment System  
Site 1, Former Drum Marshalling Yard  
Naval Weapons Industrial Reserve Plant - Bethpage, NY  
Concentration Trends of Select VOCs  
SVEWs  
SV-106I



**Soil Vapor Extraction Containment System**  
**Site 1, Former Drum Marshalling Yard**  
**Naval Weapons Industrial Reserve Plant - Bethpage, NY**  
**Concentration Trends of Select VOCs**  
**SVEs**  
**SV-106D**




**Soil Vapor Extraction Containment System**  
**Site 1, Former Drum Marshalling Yard**  
**Naval Weapons Industrial Reserve Plant - Bethpage, NY**  
**Concentration Trends of Select VOCs**  
**SVEWs**  
**SV-106D (smaller scale)**




## **APPENDIX D**

### **VAPOR CONCENTRATION TREND GRAPHS – SVPMs**

Soil Vapor Extraction Containment System  
Site 1, Former Drum Marshalling Yard  
Naval Weapons Industrial Reserve Plant - Bethpage, NY  
Concentration Trends of Select VOCs  
SVPMs




Soil Vapor Extraction Containment System  
Site 1, Former Drum Marshalling Yard  
Naval Weapons Industrial Reserve Plant - Bethpage, NY  
Concentration Trends of Select VOCs  
SVPMs







Soil Vapor Extraction Containment System  
Site 1, Former Drum Marshalling Yard  
Naval Weapons Industrial Reserve Plant - Bethpage, NY  
Concentration Trends of Select VOCs  
SVPMs




Soil Vapor Extraction Containment System  
Site 1, Former Drum Marshalling Yard  
Naval Weapons Industrial Reserve Plant - Bethpage, NY  
Concentration Trends of Select VOCs  
SVPMs




Soil Vapor Extraction Containment System  
Site 1, Former Drum Marshalling Yard  
Naval Weapons Industrial Reserve Plant - Bethpage, NY  
Concentration Trends of Select VOCs  
SVPMs




Soil Vapor Extraction Containment System  
Site 1, Former Drum Marshalling Yard  
Naval Weapons Industrial Reserve Plant - Bethpage, NY  
Concentration Trends of Select VOCs  
SVPMs




Soil Vapor Extraction Containment System  
Site 1, Former Drum Marshalling Yard  
Naval Weapons Industrial Reserve Plant - Bethpage, NY  
Concentration Trends of Select VOCs  
SVPMs



Soil Vapor Extraction Containment System  
Site 1, Former Drum Marshalling Yard  
Naval Weapons Industrial Reserve Plant - Bethpage, NY  
Concentration Trends of Select VOCs  
SVPMs




Soil Vapor Extraction Containment System  
Site 1, Former Drum Marshalling Yard  
Naval Weapons Industrial Reserve Plant - Bethpage, NY  
Concentration Trends of Select VOCs  
SVPMs







Soil Vapor Extraction Containment System  
Site 1, Former Drum Marshalling Yard  
Naval Weapons Industrial Reserve Plant - Bethpage, NY  
Concentration Trends of Select VOCs  
SVPMs




Soil Vapor Extraction Containment System  
Site 1, Former Drum Marshalling Yard  
Naval Weapons Industrial Reserve Plant - Bethpage, NY  
Concentration Trends of Select VOCs  
SVPMs




Soil Vapor Extraction Containment System  
Site 1, Former Drum Marshalling Yard  
Naval Weapons Industrial Reserve Plant - Bethpage, NY  
Concentration Trends of Select VOCs  
SVPMs




Soil Vapor Extraction Containment System  
Site 1, Former Drum Marshalling Yard  
Naval Weapons Industrial Reserve Plant - Bethpage, NY  
Concentration Trends of Select VOCs  
SVPMs




Soil Vapor Extraction Containment System  
Site 1, Former Drum Marshalling Yard  
Naval Weapons Industrial Reserve Plant - Bethpage, NY  
Concentration Trends of Select VOCs  
SVPMs




Soil Vapor Extraction Containment System  
Site 1, Former Drum Marshalling Yard  
Naval Weapons Industrial Reserve Plant - Bethpage, NY  
Concentration Trends of Select VOCs  
SVPMs



Soil Vapor Extraction Containment System  
Site 1, Former Drum Marshalling Yard  
Naval Weapons Industrial Reserve Plant - Bethpage, NY  
Concentration Trends of Select VOCs  
SVPMs




Soil Vapor Extraction Containment System  
Site 1, Former Drum Marshalling Yard  
Naval Weapons Industrial Reserve Plant - Bethpage, NY  
Concentration Trends of Select VOCs  
SVPMs







Soil Vapor Extraction Containment System  
Site 1, Former Drum Marshalling Yard  
Naval Weapons Industrial Reserve Plant - Bethpage, NY  
Concentration Trends of Select VOCs  
SVPMs




Soil Vapor Extraction Containment System  
Site 1, Former Drum Marshalling Yard  
Naval Weapons Industrial Reserve Plant - Bethpage, NY  
Concentration Trends of Select VOCs  
SVPMs




Soil Vapor Extraction Containment System  
Site 1, Former Drum Marshalling Yard  
Naval Weapons Industrial Reserve Plant - Bethpage, NY  
Concentration Trends of Select VOCs  
SVPMs




Soil Vapor Extraction Containment System  
Site 1, Former Drum Marshalling Yard  
Naval Weapons Industrial Reserve Plant - Bethpage, NY  
Concentration Trends of Select VOCs  
SVPMs




Soil Vapor Extraction Containment System  
Site 1, Former Drum Marshalling Yard  
Naval Weapons Industrial Reserve Plant - Bethpage, NY  
Concentration Trends of Select VOCs  
SVPMs




Soil Vapor Extraction Containment System  
Site 1, Former Drum Marshalling Yard  
Naval Weapons Industrial Reserve Plant - Bethpage, NY  
Concentration Trends of Select VOCs  
SVPMs



Soil Vapor Extraction Containment System  
Site 1, Former Drum Marshalling Yard  
Naval Weapons Industrial Reserve Plant - Bethpage, NY  
Concentration Trends of Select VOCs  
SVPMs




Soil Vapor Extraction Containment System  
Site 1, Former Drum Marshalling Yard  
Naval Weapons Industrial Reserve Plant - Bethpage, NY  
Concentration Trends of Select VOCs  
SVPMs







Soil Vapor Extraction Containment System  
Site 1, Former Drum Marshalling Yard  
Naval Weapons Industrial Reserve Plant - Bethpage, NY  
Concentration Trends of Select VOCs  
SVPMs




Soil Vapor Extraction Containment System  
Site 1, Former Drum Marshalling Yard  
Naval Weapons Industrial Reserve Plant - Bethpage, NY  
Concentration Trends of Select VOCs  
SVPMs




Soil Vapor Extraction Containment System  
Site 1, Former Drum Marshalling Yard  
Naval Weapons Industrial Reserve Plant - Bethpage, NY  
Concentration Trends of Select VOCs  
SVPMs




Soil Vapor Extraction Containment System  
Site 1, Former Drum Marshalling Yard  
Naval Weapons Industrial Reserve Plant - Bethpage, NY  
Concentration Trends of Select VOCs  
SVPMs



Soil Vapor Extraction Containment System  
Site 1, Former Drum Marshalling Yard  
Naval Weapons Industrial Reserve Plant - Bethpage, NY  
Concentration Trends of Select VOCs  
SVPMs



Soil Vapor Extraction Containment System  
Site 1, Former Drum Marshalling Yard  
Naval Weapons Industrial Reserve Plant - Bethpage, NY  
Concentration Trends of Select VOCs  
SVPMs



Soil Vapor Extraction Containment System  
Site 1, Former Drum Marshalling Yard  
Naval Weapons Industrial Reserve Plant - Bethpage, NY  
Concentration Trends of Select VOCs  
SVPMs

