



25 November 2020

Mr. Scott Sokolowski  
Remedial Project Manager  
Naval Facilities Engineering Command, Mid Atlantic  
9324 Virginia Avenue, Building Z-144  
Norfolk, VA 23511-3095

**Subject: US NAVY CONTRACT NO. N40085-16-D-2288  
CONTRACT TASK ORDER NO. 4042  
2020 THIRD QUARTER SVECS OPERATIONS SUMMARY - SITE 1  
NAVAL WEAPONS INDUSTRIAL RESERVE PLANT, BETHPAGE, NY**

Dear Mr. Sokolowski:

An electronic copy of the *2020 Third Quarter Operations Report, Soil Vapor Extraction Containment System, Site 1, Former Drum Marshalling Yard, Naval Weapons Industrial Reserve Plant, Bethpage, New York*, has been submitted to your attention.

Please contact me at [rgregory@komangs.com](mailto:rgregory@komangs.com) or 610.400.0636 if you have any questions or comments regarding this submittal.

Sincerely,  
KOMAN Government Solutions, LLC (KGS)

Robert G. Gregory  
Project Manager

Cc: Mr. Brian Murray (NAVFAC) – 1 CD  
Mr. Vin Varricchio (NWIRP Bethpage Facility Management) – 2 hard copies, 2 CDs  
Mr. Jason Pelton (NYSDEC) – 1 CD  
Mr. William Cords (NAVAIR) – 1 Electronic Copy  
Mr. James Sullivan (NYSDOH) – 1 Electronic Copy  
Ms. Monica Marrow (Jacobs - NIRIS) – 1 hard copy, DDS Form, 1 CD  
Mr. David Brayack (Tetra Tech) – 1 CD

**Quarterly Operations Report  
Third Quarter 2020**

**Soil Vapor Extraction Containment System  
Site 1, Former Drum Marshalling Yard  
Naval Weapons Industrial Reserve Plant  
Bethpage, New York**

**Contract No. N40085-16-D-2288  
Contract Task Order No. N4008517F4042**

November 2020

Prepared for:



Naval Facilities Engineering Command Mid-Atlantic  
9324 Virginia Avenue  
Norfolk, VA 23511

Prepared by:



**KOMAN Government Solutions, LLC  
180 Gordon Drive, Suite 110  
Exton PA, 19341  
(610) 363-3000**

**Quarterly Operations Report  
Third Quarter 2020**

**Soil Vapor Extraction Containment System  
Site 1, Former Drum Marshalling Yard  
Naval Weapons Industrial Reserve Plant  
Bethpage, New York**

**Contract No. N40085-16-D-2288  
Contract Task Order No. N4008517F4042**

November 2020

Prepared for:

Naval Facilities Engineering Command Mid-Atlantic  
9324 Virginia Avenue  
Norfolk, VA 23511



Patrick Schauble  
Program Manager

11/25/2020

Date

Robert Gregory  
Project Manager

11/25/2020

Date



## TABLE OF CONTENTS

<b>1.0 INTRODUCTION.....</b>	<b>1-1</b>
1.1 Site Location.....	1-1
1.2 Background.....	1-1
1.3 Project Overview and Objective.....	1-2
1.4 SVECS Overview .....	1-2
<b>2.0 SVECS OPERATION AND MAINTENANCE .....</b>	<b>2-1</b>
2.1 Routine Maintenance Activities .....	2-1
2.2 Non-routine Maintenance / Site Activities .....	2-1
<b>3.0 SVECS MONITORING.....</b>	<b>3-1</b>
3.1 Monthly Air Quality Monitoring.....	3-1
3.2 Quarterly Air Quality Monitoring of SVEWs .....	3-1
3.3 Quarterly Soil Vapor Pressure Monitoring of SVEWs and Off-site SVPMs.....	3-2
3.4 Annual Vapor Quality Monitoring of Off-site SVPMs .....	3-2
3.5 Soil Vapor Quality Concentration Trends .....	3-2
<b>4.0 CONCLUSIONS AND RECOMMENDATIONS.....</b>	<b>4-1</b>
<b>5.0 REFERENCES.....</b>	<b>5-1</b>

### FIGURES

FIGURE 1	Site Location Map
FIGURE 2	Site Area and Vicinity
FIGURE 3	Site Plan – Existing SVECS Layout
FIGURE 4	System Layout Plan
FIGURE 5	Third Quarter 2020 Vapor Analytical Map – Select VOC Concentrations - SVEWs
FIGURE 6	Third Quarter 2020 Soil Vapor Pressure Readings – SVPMs

### TABLES

TABLE 1	Monthly Vapor Analytical Results – July 2020
TABLE 2	Monthly Vapor Analytical Results – August 2020
TABLE 3	Monthly Vapor Analytical Results – September 2020
TABLE 4	Quarterly Vapor Analytical Results of SVE Wells – Third Quarter 2020
TABLE 5	Quarterly Vapor Analytical Results of SVE Wells through Third Quarter 2020
TABLE 6	Quarterly Off-site Soil Vapor Monitoring Results of SVPMs – Third Quarter 2020



**APPENDICES**

APPENDIX A NYSDEC Air Discharge Limit Documentation

APPENDIX B Vapor Concentration Trend Graphs of Select VOCs – SVEWs

## Acronyms and Abbreviations

bgs	below ground surface
CTO	Contract Task Order
DAR	Division of Air Resources
DCA	dichloroethane
DCE	dichloroethene
DoD	Department of Defense
ELAP	Environmental Laboratory Accreditation Program
FMS	Flow Monitoring Station
GOCO	Government Owned Contractor Operated
i.w.	inches of water column
KGS	KOMAN Government Solutions, LLC
NAVFAC	Naval Facilities Engineering Command Mid-Atlantic
Navy	U.S. Department of the Navy
NELAC	National Environmental Laboratory Accreditation Conference
NG	Northrop Grumman
NWIRP	Naval Weapons Industrial Reserve Plant
NYSDEC	New York State Department of Environmental Conservation
NYSDOH	New York State Department of Health
O&M	Operation and Maintenance
PCB	polychlorinated biphenyls
PCE	tetrachloroethene
PID	photoionization detector
scfm	standard cubic feet per minute
SVE	soil vapor extraction
SVECS	soil vapor extraction containment system
SVEW	soil vapor extraction well
SVOC	semi-volatile organic compound
SVPM	soil vapor pressure monitor
TCA	trichloroethane
TCE	trichloroethene
TCL	target compound list
TtEC	Tetra Tech EC, Inc.
TtNUS	Tetra Tech NUS, Inc.
µg/m <sup>3</sup>	micrograms per cubic meter
VC	vinyl chloride
VGAC	vapor-phase granular activated carbon
VOC	volatile organic compound

## 1.0 INTRODUCTION

KOMAN Government Solutions, LLC (KGS) has prepared this Quarterly Operations Report for the Third Quarter 2020 for the Soil Vapor Extraction Containment System (SVECS) at Site 1, Former Drum Marshalling Area, at the Naval Weapons Industrial Reserve Plant (NWIRP) in Bethpage, New York. This report has been prepared for the U.S. Department of the Navy (Navy), Naval Facilities Engineering Command (NAVFAC), Mid-Atlantic, under Contract No. N40085-16-D-2288, Contract Task Order (CTO) No. N4008517F4042. This Third Quarter 2020 Operations Report details activities that occurred from July 2020 to September 2020. Data was collected, and operational activities were performed by KGS in accordance with the following documents:

- *Final Operation & Maintenance Plan for Soil Vapor Extraction Containment System Site 1, Former Drum Marshalling Yard at Naval Weapons Industrial Reserve Plant Bethpage, New York* prepared by Tetra Tech EC, Inc. (TtEC) in 2010, hereafter referred to as the “O&M Manual.”
- *Final Supplemental Offsite Soil Vapor Intrusion Monitoring Plan for the Soil Vapor Extraction Containment System, Site 1, Former Drum Marshalling Yard at Naval Weapons Industrial Reserve Plant, Bethpage, New York* prepared by Tetra Tech NUS, Inc. (TtNUS) in 2012.

### 1.1 Site Location

NWIRP Bethpage is located in east central Nassau County, Long Island, New York, approximately 30 miles east of New York City. In the late 1990s, the Navy's property totaled approximately 109.5 acres and was formerly a Government Owned Contractor-Operated (GOCO) facility that was operated by Northrop Grumman (NG) until September 1998. NWIRP Bethpage was bordered on the north, west, and south by property owned, or formerly owned, by NG that covered approximately 550 acres, and on the east by a residential neighborhood. The Navy currently retains approximately nine acres of the former NWIRP, including Site 1, which lies within the fenced area of NWIRP Bethpage and is located east of Plant No. 3, west of 11<sup>th</sup> Street, and north of Plant 17 South (**Figures 1 and 2**).

### 1.2 Background

NWIRP Bethpage was established in 1943. Since inception, the primary mission of the facility was the research, prototyping, testing, design engineering, fabrication, and primary assembly of military aircraft. Historical operations that resulted in hazardous material generation at the facility included metal finishing processes, maintenance operations, painting of aircraft and components, and other activities that involve aircraft manufacturing. Wastes generated by plant operations were disposed of directly into drainage sumps, dry wells, and/or on the ground surface, resulting in the disposal of a number of hazardous wastes, including volatile organic compounds (VOCs), semi-volatile organic compounds (SVOCs), polychlorinated biphenyls (PCBs), and inorganic analytes (chromium and cadmium) at the site. Some of these contaminants have migrated from the source area to surrounding areas, including the soils at these sites and the groundwater beneath and downgradient of the NWIRP Bethpage property. NWIRP Bethpage is currently listed by the New York State Department of Environmental Conservation (NYSDEC) as an “inactive hazardous waste site” (#1-30-003B).

Soils at Site 1 consist mainly of unconsolidated sediments that overlie crystalline bedrock. A clay unit is present near the groundwater table (50 feet below ground surface [bgs]) at the southeast corner of the site. This clay unit is suspected to be a source of chlorinated solvents that are migrating into the overlying soil gas and the source of off-site VOCs in soil vapor (TtEC, 2010).

Chlorinated solvents including trichloroethene (TCE), tetrachloroethene (PCE), and 1,1,1-trichloroethane (TCA) have been identified as the VOCs of interest in soil gas at the site. Concentrations greater than 1,000 micrograms per cubic meter ( $\mu\text{g}/\text{m}^3$ ) of soil vapor have been directly associated with Site 1 activities and historical environmental data, and based on preliminary screening, exceed guidelines established by the New York State Department of Health (NYSDOH) for sub-slab soil vapor concentrations at the time. Of these compounds, TCE is the primary VOC of concern. Mitigation of TCE contamination in accordance with NYSDOH guidance is expected to remediate other VOCs associated with the site. PCBs, cadmium, and chromium have also been identified in site soils at concentrations requiring remediation. The majority of these chemicals have been detected in the central portion of Site 1 and will be addressed via a separate remediation (TtEC, 2010).

Prior to implementation of the SVECS, the mean concentrations of VOCs in soil gas samples collected along the eastern fence-line were 41,128  $\mu\text{g}/\text{m}^3$  of TCE, 381  $\mu\text{g}/\text{m}^3$  of PCE, and 20,634  $\mu\text{g}/\text{m}^3$  of 1,1,1-TCA. The maximum concentrations of VOCs in the soil gas samples were 180,000  $\mu\text{g}/\text{m}^3$  of TCE, 1,200  $\mu\text{g}/\text{m}^3$  of PCE, and 90,000  $\mu\text{g}/\text{m}^3$  of 1,1,1-TCA (TtEC, 2010).

### 1.3 Project Overview and Objective

The remedial objective for this project is to use an on-site soil vapor extraction system to prevent further off-site migration of VOC-contaminated soil vapor and to the extent practical, capture contaminated soil vapor with a TCE concentration greater than 250  $\mu\text{g}/\text{m}^3$ . A secondary objective of this project is to address soil vapor with a TCE concentration greater than 5  $\mu\text{g}/\text{m}^3$ . The SVECS is an interim action intended to address migration of VOCs in contaminated soil vapors. It is expected to operate continuously 24 hours/day, seven days/week, with the exception of maintenance and adjustment periods, until the remedial objectives are met (TtEC, 2010).

### 1.4 SVECS Overview

The SVECS consists of soil vapor extraction, soil vapor monitoring, and soil vapor treatment. Twelve soil vapor extraction wells (SVEWs) are located along the eastern boundary of Site 1 in six clusters, each consisting of one intermediate well and one deep well. Intermediate wells SVE-101I, SVE-102I, SVE-103I, SVE-104I, SVE-105I, and SVE-106I have a screened interval between 25 and 35 feet bgs. Deep wells SVE-101D, SVE-102D, SVE-103D, SVE-104D, SVE-105D, and SVE-106D have a screened interval between 40 and 60 feet bgs. The groundwater table fluctuates between approximately 50 and 55 feet bgs. Each SVEW is operated at a flow rate such that the combined total flow rate is approximately 300-400 standard cubic feet per minute (scfm) of soil vapor. Each intermediate depth SVEW requires an approximate vacuum of 4 inches of water column (i.w.) and each deep SVEW requires a vacuum of up to 20 i.w. in order to extract the targeted flow rates. These 12 SVEWs have been piped below the ground to the Flow Monitoring Station (FMS), where flow, vacuum, and vapor quality are monitored. Within the

FMS, the discharges from the individual SVEWs have been equipped with a 2-inch flow control butterfly valve, a vacuum gauge, and a sampling port. The sampling port is utilized to measure the flow rate from an individual well using a portable velocity meter and to collect vapor samples. All the soil vapor extraction (SVE) lines collect into a single manifold within the FMS and from this location a single underground pipeline has been routed approximately 1,400 linear feet to the Treatment Building (Building 03-35). Five additional SVEWs (SV-107D, SV-108D, SV-109D, SV-110D, and SV-111D) were installed in October 2011 to address potential VOCs under Plant No. 3 and the South Warehouse. A site plan depicting well locations is included as **Figure 3**.

The SVECS is housed within the Treatment Building, an existing and unoccupied building also known as Building 03-35. The treatment system consists of a moisture separator, two SVE blowers, and a 5,000-pound vapor-phase granular activated carbon (VGAC) unit for removal of chlorinated VOCs from the off-gas. Soil vapor that enters the Treatment Building first passes through the moisture separator tank where any condensate is separated. To date, no condensate has formed in this tank. The vapor is then passed through an air filter and SVE blower and then treated in the VGAC unit. The treated vapor is discharged from the VGAC via an exhaust stack. The SVECS has a control panel comprised of mechanical interlocks and relays for local operation. A System Layout Plan is presented in **Figure 4**, which also illustrates the design flow rates through the soil vapor extraction and treatment process.

The off-gas from the SVECS is monitored for chlorinated VOCs as identified in the NYSDEC Division of Air Resources (DAR) permit equivalent effluent limitations and updated approval documentation (**Appendix A**) and monitoring requirements (TtEC, 2010). Samples are submitted to a National Environmental Laboratory Accreditation Conference (NELAC)-accredited, Department of Defense (DoD) Environmental Laboratory Accreditation Program (ELAP)-accredited laboratory, Eurofins Air Toxics, LLC, located in Folsom, California, for analysis of VOCs by modified method TO-15. Prior to January 2014, samples were analyzed for target compound list (TCL) VOCs. As of January 2014, upon approval by NYSDEC and NYSDOH, samples are analyzed for site-specific VOCs. The site-specific VOCs are: 1,1,1-TCA, 1,1-dichloroethane (DCA), 1,1-dichloroethene (DCE), 1,2-DCA, cis-1,2-DCE, PCE, trans-1,2-DCE, TCE, and vinyl chloride (VC).

A total of 18 soil vapor pressure monitor (SVPM) / soil gas monitoring points have been installed in the residential neighborhood east of Site 1 at NWIRP Bethpage (**Figure 3**). These off-site monitoring points consist of eight previously existing SVPMs as well as 10 SVPMs installed in September 2012. Soil vapor pressure readings from the SVPMs are collected quarterly and used to evaluate the SVECS vacuum field. In addition, analytical results of vapor samples collected annually from these locations and the soil vapor pressure readings are used to further evaluate the SVECS operation and the potential for vapor intrusion.

## **2.0 SVECS OPERATION AND MAINTENANCE**

While designed to run autonomously, the SVECS requires regular visits by an operator to record and adjust operational parameters and to perform scheduled maintenance. The SVECS is equipped with telemetry that will alert an on-call operator in the event of a plant shutdown.

### **2.1 Routine Maintenance Activities**

Routine maintenance activities at the SVECS were performed during the operator's weekly visits during this reporting period. These activities include general site inspections (of the grounds, buildings, doors and locks), collection of operational data (vapor flowrates, pressures, vacuums, temperature and photoionization detector [PID] readings), adjustment of system valves, collection of vapor samples (on a monthly and quarterly basis), collection/disposal of condensate if needed, cleaning of filters, switching of lead/lag blower assignments, and preventive maintenance of system equipment.

### **2.2 Non-routine Maintenance / Site Activities**

The following non-routine activities / repair activities occurred at the SVECS during the Third Quarter 2020 reporting period:

- No non-routine activities were required during the current reporting period.
- System documentation notes that the boiler located within the Treatment Building (associated with the steam-enhanced product recovery system being conducted under separate contract) is active intermittently.

### 3.0 SVECS MONITORING

Several process vapor samples are collected on a monthly basis to monitor the SVECS operation. These samples consist of an influent sample (as well as a duplicate sample), located immediately prior to the VGAC unit, and an effluent sample, located after the VGAC unit and before the exhaust stack. Vapor samples are also collected from the 12 original SVEWs on a quarterly basis to monitor the capture of the contaminated soil vapor by the SVEWs. In addition, quarterly pressure measurements are collected from the 12 SVEWs and the 18 SVPs to monitor the SVECS vacuum field, and soil gas sampling from the 18 SVPs is conducted annually (generally in the winter time-frame) to evaluate the effectiveness of the SVECS. The first annual soil gas sampling event was conducted in the winter 2012-2013. The eighth annual sampling event was conducted in February 2020 and the results will be presented in the 2020 Annual Operations Report.

#### 3.1 Monthly Air Quality Monitoring

Analysis of influent and effluent vapor sample locations is performed to evaluate VOC mass removal and the effectiveness of the VGAC adsorption unit. Time-integrated vapor samples are collected using 6-liter summa canisters with 30-minute flow regulators.

Treated off-gas discharged at the exhaust stack is subject to emissions limitations. Initially, discharge goals were derived from calculations submitted by the Navy and accepted by the NYSDEC in the February 2010 DAR permit equivalent application. In September 2011, the Navy submitted an evaluation proposing revised discharge goals (TtNUS, 2011), which NYSDEC agreed to in October 2011. A copy of this documentation is included as **Appendix A**.

A summary of monthly vapor sampling results collected in July, August, and September (Third Quarter) is presented in **Tables 1, 2, and 3**, respectively. Emission rate calculations for both the influent stream (prior to VGAC treatment) and effluent stream (following VGAC treatment) and the computed monthly mass recoveries are also presented. Emission rates of the influent stream as well as mass recovery are calculated to monitor progress and determine when influent concentrations have reached levels at which vapor treatment via carbon adsorption is no longer required. The data presented in **Tables 1, 2, and 3** demonstrate that all constituents were within the effluent emission rate guidelines (**Appendix A**). Raw analytical data are provided under a separate cover.

#### 3.2 Quarterly Air Quality Monitoring of SVEWs

Time-integrated vapor samples are collected quarterly using 6-liter summa canisters with 30-minute flow regulators at six intermediate and six deep SVEWs. The samples are collected for the purpose of tracking and documenting the performance of the SVECS (TtEC, 2010).

Quarterly vapor samples were collected on 12 August from the 12 SVEWs. A summary of detected compounds is included as **Table 4**. Raw analytical data are provided under a separate cover. Analytical results of select VOCs (1,1,1-TCA, PCE, and TCE) detected at the 12 SVEWs during the Third Quarter monitoring event are presented graphically on **Figure 5**. Historical analytical results of



quarterly vapor samples collected from December 2009 through the Third Quarter 2020 are presented in **Table 5**.

### 3.3 Quarterly Soil Vapor Pressure Monitoring of SVEWs and Off-site SVPMs

Soil vapor pressure readings are collected quarterly from the 12 SVEWs and 18 SVPMs to monitor the SVECS vacuum field. Soil vapor pressure readings from the 12 SVEWs and 18 SVPMs were collected on 12 August. Results of the Third Quarter vapor monitoring are presented in **Table 6**.

The vapor pressure readings collected from the SVEWs ranged between -3.0 to -10.0 i.w. indicating that a vacuum has been established along the fence line. The vapor pressure readings collected from the SVPMs ranged between -0.03 to -0.23 i.w. indicating that a vacuum has been established in the residential neighborhood. Pressure readings from the 18 SVPMs are presented graphically in **Figure 6**.

### 3.4 Annual Vapor Quality Monitoring of Off-site SVPMs

Time-integrated vapor samples are collected annually using 6-liter summa canisters with 30-minute flow regulators at 18 SVPM locations. The Annual 2020 SVPM samples were collected in February 2020. Analytical results of the SVPM will be included in the 2020 Annual Operations Report prepared during the Fourth Quarter.

### 3.5 Soil Vapor Quality Concentration Trends

The Third Quarter vapor analytical results for the 12 SVEWs are presented in **Table 4**. Historical vapor analytical results for the 12 SVEWs through the Third Quarter are presented in **Table 5**. In addition, concentration trends of select VOCs for the SVECS combined influent (1,1,1-TCA, PCE, TCE, and total VOCs) and each of the 12 SVEWs (1,1,1-TCA, PCE, and TCE) are presented in **Appendix B**. Concentration trends observed in the 12 SVEWs through the Third Quarter are discussed below.

- Combined Influent: Overall VOC concentrations in the combined influent decreased throughout the Third Quarter 2020, with total VOC concentrations of 1,268  $\mu\text{g}/\text{m}^3$ , 1,064  $\mu\text{g}/\text{m}^3$  in July (**Table 1**) and August (**Table 2**), respectively, and a minor increase (1,098  $\mu\text{g}/\text{m}^3$ ) in September (**Table 3**). Overall, TCE, PCE and 1,1,1-TCA concentrations remain approximately one to three orders of magnitude below baseline concentrations measured in December 2009 (42,000  $\mu\text{g}/\text{m}^3$  TCE, 7,900  $\mu\text{g}/\text{m}^3$  PCE, and 13,000  $\mu\text{g}/\text{m}^3$  1,1,1-TCA).
- SV-101I: Concentrations measured at this location (6,100  $\mu\text{g}/\text{m}^3$  TCE, 78  $\mu\text{g}/\text{m}^3$  PCE, and 2,000  $\mu\text{g}/\text{m}^3$  1,1,1-TCA) increased in the Third Quarter 2020 relative to concentrations measured in the Second Quarter 2020. However, the measured concentrations are consistent with respect to the range in concentration variability noted over the past several years. All concentrations remain below baseline concentrations measured in December 2009 (180,000  $\mu\text{g}/\text{m}^3$  TCE, 1,700  $\mu\text{g}/\text{m}^3$  PCE, and 51,000  $\mu\text{g}/\text{m}^3$  1,1,1-TCA).
- SV-101D: Concentration measured at this location (180  $\mu\text{g}/\text{m}^3$  TCE, 16  $\mu\text{g}/\text{m}^3$  PCE, and 3.0 J  $\mu\text{g}/\text{m}^3$  1,1,1-TCA) decreased in the Third Quarter 2020 relative to concentrations measured in the



Second Quarter 2020. All concentrations remain below baseline concentrations measured in December 2009 (100,000  $\mu\text{g}/\text{m}^3$  TCE, 3,200  $\mu\text{g}/\text{m}^3$  PCE, and 26,000  $\mu\text{g}/\text{m}^3$  1,1,1-TCA).

- SV-102I: Concentrations measured at this location (71  $\mu\text{g}/\text{m}^3$  TCE, 9.6  $\mu\text{g}/\text{m}^3$  PCE, and 7.7  $\mu\text{g}/\text{m}^3$  1,1,1-TCA) increased in the Third Quarter 2020 relative to concentrations measured in the Second Quarter 2020. The concentrations in the Third Quarter 2020 are above the baseline concentrations measured in December 2009 (5.6  $\mu\text{g}/\text{m}^3$  TCE, 2.4  $\mu\text{g}/\text{m}^3$  PCE, and non-detect 1,1,1-TCA) but are below the maximum concentrations measured in June 2010 (300  $\mu\text{g}/\text{m}^3$  TCE, 17  $\mu\text{g}/\text{m}^3$  PCE, and 13  $\mu\text{g}/\text{m}^3$  1,1,1-TCA).
- SV-102D: Concentrations measured at this location (150  $\mu\text{g}/\text{m}^3$  TCE, 18  $\mu\text{g}/\text{m}^3$  PCE, 3.6  $\mu\text{g}/\text{m}^3$  1,1,1-TCA) have increased in the Third Quarter 2020 relative to concentrations measured in the Second Quarter 2020. Concentrations of TCE and 1,1,1-TCA remain below baseline concentrations measured in December 2009 (440  $\mu\text{g}/\text{m}^3$  TCE and 130  $\mu\text{g}/\text{m}^3$  1,1,1-TCA) and PCE remains below the maximum concentration measured in September 2016 (51  $\mu\text{g}/\text{m}^3$ ).
- SV-103I: Concentrations of two VOCs measured at this location (33  $\mu\text{g}/\text{m}^3$  TCE and 6.7  $\mu\text{g}/\text{m}^3$  1,1,1-TCA) increased slightly in the Third Quarter 2020 relative to concentrations measured in the Second Quarter 2020. The concentration of PCE (190  $\mu\text{g}/\text{m}^3$ ) decreased substantially in the Third Quarter 2020 relative to concentrations measured in the Second Quarter 2020 and is consistent with the Fourth Quarter 2019 and First Quarter 2020 concentrations. All concentrations remain below baseline concentrations measured in December 2009 (900  $\mu\text{g}/\text{m}^3$  TCE, 580  $\mu\text{g}/\text{m}^3$  PCE, and 900  $\mu\text{g}/\text{m}^3$  1,1,1-TCA).
- SV-103D: Concentrations measured at this location (57  $\mu\text{g}/\text{m}^3$  TCE, 680  $\mu\text{g}/\text{m}^3$  PCE, and 29  $\mu\text{g}/\text{m}^3$  1,1,1-TCA) decreased substantially in the Third Quarter 2020 relative to the Second Quarter 2020. All concentrations remain below baseline concentrations measured in December 2009 (3,100  $\mu\text{g}/\text{m}^3$  TCE, 20,000  $\mu\text{g}/\text{m}^3$  PCE, and 3,000  $\mu\text{g}/\text{m}^3$  1,1,1-TCA).
- SV-104I: Concentrations measured at this location (170  $\mu\text{g}/\text{m}^3$  TCE, 3,900  $\mu\text{g}/\text{m}^3$  PCE, and 68  $\mu\text{g}/\text{m}^3$  1,1,1-TCA) increased substantially in the Third Quarter 2020 relative to concentrations measured in the Second Quarter 2020. Concentrations of TCE and 1,1,1-TCA remain below baseline concentrations measured in December 2009 (710  $\mu\text{g}/\text{m}^3$  TCE and 730  $\mu\text{g}/\text{m}^3$  1,1,1-TCA) while the concentration of PCE represents the maximum concentration measured to date.
- SV-104D: Concentrations measured at this location (1,000  $\mu\text{g}/\text{m}^3$  TCE, 8,800  $\mu\text{g}/\text{m}^3$  PCE, and 630  $\mu\text{g}/\text{m}^3$  1,1,1-TCA) increased substantially in the Third Quarter 2020 relative to concentrations measured in the Second Quarter 2020. All concentrations remain below baseline concentrations measured in December 2009 (4,600  $\mu\text{g}/\text{m}^3$  TCE, 20,000  $\mu\text{g}/\text{m}^3$  PCE, and 3,600  $\mu\text{g}/\text{m}^3$  1,1,1-TCA).
- SV-105I: Concentrations of two VOCs measured at this location (67  $\mu\text{g}/\text{m}^3$  TCE and 41  $\mu\text{g}/\text{m}^3$  PCE) increased in the Third Quarter 2020 relative to concentrations measured in the Second Quarter 2020. The concentration of 1,1,1-TCA (40  $\mu\text{g}/\text{m}^3$ ) decreased in the Third Quarter. Concentrations of TCE and PCE remain below baseline concentrations measured in December

2009 (76  $\mu\text{g}/\text{m}^3$  TCE and 70  $\mu\text{g}/\text{m}^3$  PCE). The measured concentration of 1,1,1-TCA in the Third Quarter 2020 is above the baseline concentration measured in December 2009 (9.9  $\mu\text{g}/\text{m}^3$ ) but below the maximum concentration measured in May 2020 (88  $\mu\text{g}/\text{m}^3$ ).

- SV-105D: Concentrations of two VOCs measured at this location (470  $\mu\text{g}/\text{m}^3$  TCE and 200  $\mu\text{g}/\text{m}^3$  1,1,1-TCA) increased substantially in the Third Quarter 2020 relative to concentrations measured in the Second Quarter 2020 while the measured concentration of PCE (31  $\mu\text{g}/\text{m}^3$ ) decreased slightly in the Third Quarter. All concentrations remain below baseline concentrations measured in December 2009 (1,700  $\mu\text{g}/\text{m}^3$  TCE, 2,100  $\mu\text{g}/\text{m}^3$  PCE, and 550  $\mu\text{g}/\text{m}^3$  1,1,1-TCA).
- SV-106I: Concentrations of two VOCs measured at this location (310  $\mu\text{g}/\text{m}^3$  TCE and 27  $\mu\text{g}/\text{m}^3$  1,1,1-TCA) increased in the Third Quarter 2020 relative to concentrations measured in the Second Quarter 2020 while the concentration of PCE (1,400  $\mu\text{g}/\text{m}^3$ ) substantially decreased in the Third Quarter. The concentrations of TCE and 1,1,1-TCA are below the baseline concentrations measured in December 2009 (1,900  $\mu\text{g}/\text{m}^3$  TCE and 220  $\mu\text{g}/\text{m}^3$  1,1,1-TCA). The concentration of PCE (1,400  $\mu\text{g}/\text{m}^3$ ) remained above the baseline concentration (390  $\mu\text{g}/\text{m}^3$ ) but was below the maximum concentration (96,000  $\mu\text{g}/\text{m}^3$ ) measured in February 2020. All Third Quarter 2020 concentrations are notably less than the elevated concentrations measured in the First Quarter 2020 that had been attributed to ongoing soil removal operations being conducted at that time.
- SV-106D: Concentrations measured at this location (37  $\mu\text{g}/\text{m}^3$  TCE, 27  $\mu\text{g}/\text{m}^3$  PCE, and 7.5  $\mu\text{g}/\text{m}^3$  1,1,1-TCA) decreased substantially in the Third Quarter 2020 relative to concentrations measured in the Second Quarter 2020. All concentrations remain below baseline concentrations measured in December 2009 (3,400  $\mu\text{g}/\text{m}^3$  TCE, 720  $\mu\text{g}/\text{m}^3$  PCE, and 340  $\mu\text{g}/\text{m}^3$  1,1,1-TCA). All Third Quarter 2020 concentrations are notably less than the elevated concentrations measured in the First Quarter 2020 that had been attributed to ongoing soil removal operations being conducted at that time.

## 4.0 CONCLUSIONS AND RECOMMENDATIONS

As stated previously, the intent of the Site 1 SVECS is to prevent further off-site migration of VOC contaminated soil vapor and to the extent practical, capture soil vapor with elevated TCE concentrations. Based on the presence of a vacuum field and the reduction of VOC concentrations to less than the screening values in the off-property area, the SVECS is functioning as designed.

Concentrations of TCE, PCE, and 1,1,1-TCA increased sharply at two SVEWs during the First Quarter 2020: SV-106I and SV-106D. Concentrations for all three constituents at both SVEWs represent the maximum concentrations measured to date. The PCE concentration at SV-103D measured during the First Quarter 2020 was above the baseline concentration measured in December 2009 but below the maximum concentration measured in March 2010. A significant excavation effort for the removal of contaminated soil was performed during the First Quarter 2020 sampling event in the vicinity of these wells and the disturbance of subsurface soils may have facilitated volatilization of site-related VOCs. An excavation to 20 feet bgs north of the SV-106 wells was ongoing during the February 2020 quarterly sampling event. The excavation contractor monitored for VOCs and dust downwind of the Site 1 work site and no elevated measurements were recorded, indicating no discernible release of VOCs to the atmosphere. The Second Quarter 2020 results for PCE at SV-103I and 1,1,1-TCE at SV-105I both increased relative to the First Quarter results, and represent maximum values identified to date. SV-105I is located within 100 feet of SV-106I and SV-106D, at which high levels of VOCs were recorded and attributed to the soil excavation effort. SV-103I is several hundred feet further to the south of SV-105I; the source of the increase in PCE concentration at this SVEW is not clear given the current dataset.

With progress toward completion of the contaminated soil removal operations during the Second Quarter 2020, the concentrations of these VOCs captured by nearby SVEWs has substantially diminished. For the SV-106I and SV-106D well pair measured with the highest concentrations to date of TCE, PCE, and 1,1,1-TCA in the First Quarter 2020, concentrations of TCE and 1,1,1-TCA returned to levels below the December 2009 baseline values. PCE concentrations remained elevated during the Second Quarter 2020 relative to the baseline values but were significantly lower than the levels measured in the First Quarter 2020.

Site 1 restoration during the Third Quarter 2020 included backfilling of excavated areas with clean soil covered by topsoil. A further decline of soil vapor VOC concentrations to levels equal to or lower than those measured in prior sampling events was observed during the Third Quarter 2020. The one exception to this overall downward trend in soil vapor VOC concentration was observed in the area of SV-104I and SV-104D at which measured concentrations of VOCs increased relative to those measured in the Second Quarter 2020, with the measured level of PCE at SV-104I in August 2020 representing the highest concentration measured to date. It is expected that this location-specific measured PCE concentration will dissipate over time as the soil vapor concentrations stabilize following the completion of the Site 1 restoration efforts in the Fourth Quarter 2020.

Review of the monthly vapor monitoring results for the Third Quarter 2020 indicates that the VOC removal efficiencies by the VGAC unit are trending downward and plans for the exchange of the VGAC

media are in place for the Fourth Quarter 2020. VOC emission rates remain well below the approved Site 1 guidelines.

## 5.0 REFERENCES

New York State Department of Health (NYSDOH). 2006. *Guidance for Evaluating Soil Vapor Intrusion in the State of New York*. October.



Tetra Tech EC, Inc. (TtEC). 2010. *Final Operation & Maintenance Plan for Soil Vapor Extraction Containment System, Site 1, Former Drum Marshalling Yard at Naval Weapons Industrial Reserve Plant, Bethpage, New York*. June.

Tetra Tech NUS, Inc. (TtNUS). 2011. *Modification to Existing Soil Vapor Extraction Containment System at Site 1 – Former Drum Marshalling Area, Installation of Soil Vapor Extraction Wells SVE-107D to -111D, NWIRP Bethpage, Bethpage, New York*. September.

TtNUS. 2012. *Final Supplemental Offsite Soil Vapor Intrusion Monitoring Plan for the Soil Vapor Extraction Containment System, Site 1, Former Drum Marshalling Yard at Naval Weapons Industrial Reserve Plant, Bethpage, New York*. February.

## **FIGURES**






Department of the Navy  
Naval Facilities Engineering Command, Mid-Atlantic  
Site 1, Former Drum Marshalling Area  
Naval Weapons Industrial Reserve Plant  
Bethpage, NY

Figure 1: Site Location Map

KOMAN Government Solutions, LLC






Department of the Navy  
 Naval Facilities Engineering Command, Mid-Atlantic  
 Site 1, Former Drum Marshalling Area  
 Naval Weapons Industrial Reserve Plant  
 Bethpage, NY



Figure 2  
 Site 1 Area and Vicinity

**KOMAN Government Solutions, LLC**






<b>SITE PLAN EXISTING LAYOUT</b>			
<b>SVE CONTAINMENT SYSTEM SITE 1 - NWIRP BETHPAGE BETHPAGE, NEW YORK</b>			
<b>KOMAN Government Solutions, LLC</b> 180 Gordon Road, Suite 110, Exton, PA 19341			
SCALE IN FEET 0 160	DATE 10/24/2017	FIGURE 3	



NOTES:  
 1. ALL MAN DOORS AND OVERHEAD DOORS ARE EXISTING. MAN DOORS ARE APPROXIMATELY 7'X3'. OVERHEAD DOOR IS APPROXIMATELY 10'X10'.

PROCESS EQUIPMENT LIST		
ITEM NUMBER	NUMBER REQUIRED	NAME/DESCRIPTION
M-1	1	MOISTURE SEPARATOR -CONFIGURATION: VERTICAL, CYLINDRICAL -MATERIAL OF CONSTRUCTION: CARBON STEEL, EPOXY INTERIOR COATING, PAINT EXTERIOR COATING -CAPACITY: 400 GALLON CONDENSATE COLLECTION -DIMENSIONS: 5 FT DIA X 6 FEET HT, 718 GALLON
F-1	1	MAKE-UP AIR FILTER -CONFIGURATION: INTAKE FILTER/SILENCER COMBINATION HOUSING -MATERIAL OF CONSTRUCTION: CARBON STEEL, CORROSION RESISTANCE COATING -CAPACITY: 500 CFM AT 20 IW, 4 INCH FLANGED CONNECTION
F-2	1	BLOWER AIR FILTER -CONFIGURATION: INLINE VACUUM SERVICE FILTER -MATERIAL OF CONSTRUCTION: CARBON STEEL, CORROSION RESISTANCE COATING -CAPACITY: 1,200 CFM AT 35 IW, 10 INCH FLANGED CONNECTION
B-1A, B-1B	2	SOIL VAPOR EXTRACTION BLOWER -CONFIGURATION: HORIZONTAL CENTRIFUGAL -RATING: 600 CFM AT 40 IW -MOTOR: 7.5 HP, 480V, 3PH, 60HZ ODP
VGAC-1	1	VAPOR-PHASE GRANULAR ACTIVATED CARBON -CONFIGURATION: RECTANGULAR TANK -MATERIAL OF CONSTRUCTION: CARBON STEEL, EPOXY INTERIOR COATING, EPOXY EXTERIOR COATING -RATING: 1,600 CFM AT 3 IW, 2,000 CFM AT 6 IW -CAPACITY: 5,000 LBS CARBON -DIMENSIONS: 6' X 8' FOOTPRINT, 6' 8" HT

DEPARTMENT OF THE NAVY NAVAL FACILITIES ENGINEERING COMMAND, MID-ATLANTIC NAVAL WEAPONS INDUSTRIAL RESERVE PLANT SITE 1, FORMER DRUM MARSHALLING AREA SOIL VAPOR EXTRACTION CONTAINMENT SYSTEM LAYOUT PLAN	NAVFACIES ENGINEERING COMMAND BETHPAGE, NEW YORK	TETRA TECH ENGINEERING CORPORATION PC SUBMITTED BY: [NAME] CHECKED BY: [NAME] DATE: [DATE]	APPROVED DATE	OFFICER IN CHARGE APPROVED DATE
SEAL AREA	SAT TO	DATE	DATE	DATE
THIS DRAWING PRODUCED ON AUTOCAD DO NOT REVISE MANUALLY	THIS DOCUMENT IS THE PROPERTY OF NAVAL FACILITIES ENGINEERING COMMAND, PREPARED BY TETRA TECH ENGINEERING CORPORATION PC, AND IS PROVIDED UPON THE CONDITION THAT IT WILL NOT BE REPRODUCED, COPIED, OR ISSUED TO A THIRD PARTY, AND WILL BE USED SOLELY FOR THE ORIGINAL INTENDED PURPOSE AND SOLELY FOR THE EXECUTION OR REVIEW OF THE ENGINEERING CONSTRUCTION OF THE PROJECT.	CODE I.D. NO. SCALE: AS SHOWN SPEC. NO. CONSTR. CONTR. NO. N62473-10-D-3211 NAVFAC DRAWING NO. Figure 4	SHEET DIS. SH. NO. 1-3	OF DIS. SH. NO. 1-3



SV-106D	8/12/20
1,1,1-TCA	7.5
PCE	27
TCE	37

SV-106I	8/12/20
1,1,1-TCA	27
PCE	1,400
TCE	310

SV-105I	8/12/20
1,1,1-TCA	40
PCE	41
TCE	67

SV-105D	8/12/20
1,1,1-TCA	200
PCE	31
TCE	470

SV-103D	8/12/20
1,1,1-TCA	29
PCE	680
TCE	57

SV-103I	8/12/20
1,1,1-TCA	6.7
PCE	190
TCE	33

SV-104D	8/12/20
1,1,1-TCA	630
PCE	8,800
TCE	1,000

SV-104I	8/12/20
1,1,1-TCA	68
PCE	3,900
TCE	170

SV-101D	8/12/20
1,1,1-TCA	3.0 J
PCE	16
TCE	180

SV-101I	8/12/20
1,1,1-TCA	2,000
PCE	78
TCE	6,100

SV-102D	8/12/20
1,1,1-TCA	3.6 J
PCE	18
TCE	150

SV-102I	8/12/20
1,1,1-TCA	7.7
PCE	9.6
TCE	71

**LEGEND**

- FORMER NWIRP BOUNDARY
- - - CURRENT NWIRP BOUNDARY
- ⊕ SVE CONTAINMENT WELL LOCATION
- J ESTIMATED VALUE
- ND NOT DETECTED ABOVE LABORATORY METHOD DETECTION LIMIT
- 1,1,1-TCA 1,1,1-TRICHLOROETHANE
- PCE TETRACHLOROETHENE
- TCE TRICHLOROETHENE

ALL CONCENTRATIONS REPORTED IN ug/m3.


**3RD QUARTER 2020 VAPOR ANALYTICAL MAP  
SELECT VOC CONCENTRATIONS - SVEWS**

**SVE CONTAINMENT SYSTEM  
SITE 1 - NWIRP BETHPAGE  
BETHPAGE, NEW YORK**

**KOMAN Government Solutions, LLC**  
180 Gordon Road, Suite 110, Exton, PA 19341

SCALE IN FEET 0 160	DATE 8/15/2020	FIGURE 5	
------------------------	-------------------	-------------	--





PLANT 3

SITE 1

SITE 4

WAREHOUSE I

WAREHOUSE J

WAREHOUSE K

BUILDING 10

WAREHOUSE E

WAREHOUSE F

WAREHOUSE G

WAREHOUSE A

WAREHOUSE B

WAREHOUSE C

WAREHOUSE D

TREATMENT BUILDING

TRAP & CLEANOUT #5

TRAP & CLEANOUT #4

TRAP & CLEANOUT #3

TRAP & CLEANOUT #2

TRAP & CLEANOUT

FLOW MONITORING STATION

Sycamore Ave

Maple Ave

11th ST

10th ST

9th ST

SVPM-2004S	8/12/20
Pressure (i.w.)	- 0.04

SVPM-2004I	8/12/20
Pressure (i.w.)	- 0.06

SVPM-2004D	8/12/20
Pressure (i.w.)	- 0.09

SVPM-2001S	8/12/20
Pressure (i.w.)	- 0.23

SVPM-2001I	8/12/20
Pressure (i.w.)	- 0.17

SVPM-2001D	8/12/20
Pressure (i.w.)	- 0.11

SVPM-2002S	8/12/20
Pressure (i.w.)	- 0.09

SVPM-2002I	8/12/20
Pressure (i.w.)	- 0.15

SVPM-2002D	8/12/20
Pressure (i.w.)	- 0.20

SVPM-2003S	8/12/20
Pressure (i.w.)	- 0.03

SVPM-2003I	8/12/20
Pressure (i.w.)	- 0.06

SVPM-2003D	8/12/20
Pressure (i.w.)	- 0.08

SVPM-2007S	8/12/20
Pressure (i.w.)	- 0.06

SVPM-2007I	8/12/20
Pressure (i.w.)	- 0.04

SVPM-2007D	8/12/20
Pressure (i.w.)	- 0.04

SVPM-2006S	8/12/20
Pressure (i.w.)	- 0.06

SVPM-2006I	8/12/20
Pressure (i.w.)	- 0.05

SVPM-2006D	8/12/20
Pressure (i.w.)	- 0.03

SVPM-2006S	8/12/20
SVPM-2006I	8/12/20
SVPM-2006D	8/12/20

SVPM-2007I	8/12/20
SVPM-2007D	8/12/20
SVPM-2007S	8/12/20

**LEGEND**

- FORMER NWIRP BOUNDARY
- CURRENT NWIRP BOUNDARY
- SOIL VAPOR PRESSURE MONITOR (SVPM)
- INDICATES A POSITIVE PRESSURE READING

ALL PRESSURE READINGS IN INCHES OF WATER COLUMN (i.w.)

3RD QUARTER 2020  
OFFSITE SOIL VAPOR MONITORING  
QUARTERLY SOIL VAPOR PRESSURE READINGS - SVPMs

SVE CONTAINMENT SYSTEM  
SITE 1 - NWIRP BETHPAGE  
BETHPAGE, NEW YORK

KOMAN Government Solutions, LLC  
180 Gordon Road, Suite 110, Exton, PA 19341

SCALE IN FEET

DATE  
9/16/2020

FIGURE  
6



## **TABLES**

**Table 1**  
**Soil Vapor Extraction Containment System**  
**Site 1, Former Drum Marshalling Yard**  
**Naval Weapons Industrial Reserve Plant - Bethpage, NY**  
**Vapor Monitoring Results**  
**July 2020**

Compound	Concentration (ug/m <sup>3</sup> )				Emission Rate <sup>(1),(2)</sup>				Monthly Mass Recovery <sup>(3)</sup> (lbs)
	Influent #1	Influent #2	Average	Effluent	Prior to Treatment		Following Treatment		
					(lbs/hr)	(lbs/yr)	(lbs/hr)	(lbs/yr)	
1,1,1-Trichloroethane	29	250	139.5	190	0.0001	1.2907	0.0002	1.7580	0.1096
1,1-Dichloroethane	1.6 J	18.0	9.8	25	0.0000	0.0907	0.0000	0.2313	0.0077
1,1-Dichloroethene	0.0	2.8 J	1.4	6.6	0.0000	0.0130	0.0000	0.0611	0.0011
1,2-Dichloroethane	0.0	0.0	0	0.0	0.0000	0.0000	0.0000	0.0000	0.0000
cis-1,2-Dichloroethene	26	240	133	430	0.0001	1.2306	0.0005	3.9786	0.1045
Tetrachloroethene	130	1100	615	0.0	0.0006	5.6903	0.0000	0.0000	0.4833
trans-1,2-Dichloroethene	0.0	3.2	1.6	5.0	0.0000	0.0148	0.0000	0.0463	0.0013
Trichloroethene	75	660	367.5	200	0.0004	3.4003	0.0002	1.8505	0.2888
Vinyl Chloride	0.0	0.0	0	0.0	0.0000	0.0000	0.0000	0.0000	0.0000
Total VOCs	262	2274	1268	857	0.0013	11.7304	0.0009	7.9257	0.9963

**Notes:**

All samples were analyzed for site-specific VOCs by modified method TO-15.

Average Monthly Vapor Temp (°F) = 123  
Average Monthly Flowrate (cfm) = 312  
Average Monthly Flowrate (scfm) = 282  
Operational Hours for the month = 744

(1) Emissions (lbs/hr) = Concentration (ug/m<sup>3</sup>)\*(lb/454000000ug)\*(0.3048^3m<sup>3</sup>/ft<sup>3</sup>)\*exhaust flow (scfm)\*(60min/hour)

(2) Emissions (lbs/yr) = Emissions (lbs/hour)\*(8760hours/yr)

(3) Monthly Mass Removal = AVERAGE FLOWRATE (scfm) \* 0.3048^3m<sup>3</sup>/ft<sup>3</sup> \* INF AVG CONC (ug/m<sup>3</sup>) \* (lb/454000000ug) \* 60 min/hr \* OPERATIONAL TIME (hr)

**Table 2**  
**Soil Vapor Extraction Containment System**  
**Site 1, Former Drum Marshalling Yard**  
**Naval Weapons Industrial Reserve Plant - Bethpage, NY**  
**Vapor Monitoring Results**  
**August 2020**

Compound	Concentration (ug/m <sup>3</sup> )				Emission Rate <sup>(1),(2)</sup>				Monthly Mass Recovery <sup>(3)</sup> (lbs)
	Influent #1	Influent #2	Average	Effluent	Prior to Treatment		Following Treatment		
					(lbs/hr)	(lbs/yr)	(lbs/hr)	(lbs/yr)	
1,1,1-Trichloroethane	27	160	93.5	250	0.0001	0.7228	0.0002	1.9326	0.0614
1,1-Dichloroethane	2.7 J	14.0	8.35	36	0.0000	0.0645	0.0000	0.2783	0.0055
1,1-Dichloroethene	0.0	0.0	0	9.1	0.0000	0.0000	0.0000	0.0703	0.0000
1,2-Dichloroethane	0.0	0.0	0	0.0	0.0000	0.0000	0.0000	0.0000	0.0000
cis-1,2-Dichloroethene	35	220	127.5	460	0.0001	0.9856	0.0004	3.5559	0.0837
Tetrachloroethene	140	900	520	0.0	0.0005	4.0197	0.0000	0.0000	0.3414
trans-1,2-Dichloroethene	0.0	3.8	1.9	6.8	0.0000	0.0147	0.0000	0.0526	0.0012
Trichloroethene	85	540	312.5	270	0.0003	2.4157	0.0002	2.0872	0.2052
Vinyl Chloride	0.0	0.0	0	0.0	0.0000	0.0000	0.0000	0.0000	0.0000
Total VOCs	290	1838	1064	1032	0.0009	8.2230	0.0009	7.9768	0.6984

**Notes:**

All samples were analyzed for site-specific VOCs by modified method TO-15.

Average Monthly Vapor Temp (°F) = 122  
Average Monthly Flowrate (cfm) = 260  
Average Monthly Flowrate (scfm) = 236  
Operational Hours for the month = 744

(1) Emissions (lbs/hr) = Concentration (ug/m<sup>3</sup>)\*(lb/454000000ug)\*(0.3048^3m<sup>3</sup>/ft<sup>3</sup>)\*exhaust flow (scfm)\*(60min/hour)

(2) Emissions (lbs/yr) = Emissions (lbs/hour)\*(8760hours/yr)

(3) Monthly Mass Removal = AVERAGE FLOWRATE (scfm) \* 0.3048^3m<sup>3</sup>/ft<sup>3</sup> \* INF AVG CONC (ug/m<sup>3</sup>) \* (lb/454000000ug) \* 60 min/hr \* OPERATIONAL TIME (hr)

**Table 3**  
**Soil Vapor Extraction Containment System**  
**Site 1, Former Drum Marshalling Yard**  
**Naval Weapons Industrial Reserve Plant - Bethpage, NY**  
**Vapor Monitoring Results**  
**September 2020**

Compound	Concentration (ug/m <sup>3</sup> )				Emission Rate <sup>(1),(2)</sup>				Monthly Mass Recovery <sup>(3)</sup> (lbs)
	Influent #1	Influent #2	Average	Effluent	Prior to Treatment		Following Treatment		
					(lbs/hr)	(lbs/yr)	(lbs/hr)	(lbs/yr)	
1,1,1-Trichloroethane	17	170	93.5	210	0.0001	0.8545	0.0002	1.9192	0.0702
1,1-Dichloroethane	1.2 J	13	7.1	30	0.0000	0.0649	0.0000	0.2742	0.0053
1,1-Dichloroethene	0.0	0.0	0	5.6	0.0000	0.0000	0.0000	0.0512	0.0000
1,2-Dichloroethane	0.0	0.0	0	0.0	0.0000	0.0000	0.0000	0.0000	0.0000
cis-1,2-Dichloroethene	18	200	109	400	0.0001	0.9962	0.0004	3.6557	0.0819
Tetrachloroethene	97	1000	548.5	0.0	0.0006	5.0129	0.0000	0.0000	0.4120
trans-1,2-Dichloroethene	0.0	2.3 J	1.15	5.2	0.0000	0.0105	0.0000	0.0475	0.0009
Trichloroethene	57	620	338.5	220	0.0004	3.0936	0.0002	2.0106	0.2543
Vinyl Chloride	0.0	0.0	0	0.0	0.0000	0.0000	0.0000	0.0000	0.0000
Total VOCs	190	2005	1098	871	0.0011	10.0326	0.0009	7.9584	0.8246

**Notes:**

All samples were analyzed for site-specific VOCs by modified method TO-15.

Average Monthly Vapor Temp (°F) = 120  
Average Monthly Flowrate (cfm) = 306  
Average Monthly Flowrate (scfm) = 279  
Operational Hours for the month = 720

(1) Emissions (lbs/hr) = Concentration (ug/m<sup>3</sup>)\*(lb/454000000ug)\*(0.3048<sup>3</sup>m<sup>3</sup>/ft<sup>3</sup>)\*exhaust flow (scfm)\*(60min/hour)

(2) Emissions (lbs/yr) = Emissions (lbs/hour)\*(8760hours/yr)

(3) Monthly Mass Removal = AVERAGE FLOWRATE (scfm) \* 0.3048<sup>3</sup>m<sup>3</sup>/ft<sup>3</sup> \* INF AVG CONC (ug/m<sup>3</sup>) \* (lb/454000000ug) \* 60 min/hr \* OPERATIONAL TIME (hr)



**Table 4**  
**Soil Vapor Extraction Containment System**  
**Site 1, Former Drum Marshalling Yard**  
**Naval Weapons Industrial Reserve Plant - Bethpage, NY**  
**Third Quarter 2020 Vapor Analytical Results Summary of SVE Wells**

Sample ID	SVE 101I	SVE 101D	SVE 102I	SVE 102D	SVE 103I	SVE 103D	SVE 104I	SVE 104D	SVE 105I	SVE 105D	SVE 106I	SVE 106D
Sample Date	08/12/20	08/12/20	08/12/20	08/12/20	08/12/20	08/12/20	08/12/20	08/12/20	08/12/20	08/12/20	08/12/20	08/12/20
Analysis by TO-15 ( $\mu\text{g}/\text{m}^3$ )												
1,1,1-Trichloroethane	2,000	3.0 J	7.7	3.6 J	6.7	29	68	630	40	200	27	7.5
1,1-Dichloroethane	29	ND	ND	ND	ND	5.0	6.4 J	76	9.9	79	3.2 J	ND
1,1-Dichloroethene	3.8 J	ND	ND	ND	ND	ND	ND	5.8 J	ND	3.1 J	ND	ND
1,2-Dichloroethane	8.0 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
cis-1,2-Dichloroethene	ND	3.1 J	ND	3.0 J	1.7 J	120	18	3,400	0.98 J	9.3	86	1.3 J
Tetrachloroethene	78	16	9.6	18	190	680	3,900	8,800	41	31	1,400	27
trans-1,2-Dichloroethene	ND	ND	ND	ND	ND	ND	ND	36	ND	ND	ND	ND
Trichloroethene	6,100	180	71	150	33	57	170	1,000	67	470	310	37
Vinyl Chloride	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND

**Notes:**

All samples were analyzed for site-specific VOCs by modified method TO-15.

$\mu\text{g}/\text{m}^3$  = micrograms per cubic meter

ND = Not detected above method detection limit

Table 5  
Soil Vapor Extraction Containment System  
Site 1, Former Drum Marshalling Yard  
Naval Weapons Industrial Reserve Plant - Bethpage, NY  
Quarterly Vapor Monitoring Results of SVE Wells  
Through Third Quarter 2020

Sample ID	SVE 1011																					
	12/21/09	03/31/10	06/09/10	09/16/10	12/08/10	03/30/11	06/28/11	09/06/11	10/14/11	02/10/12	05/11/12	09/11/12	12/05/12	01/15/13	05/16/13	08/27/13	11/08/13	01/30/14	04/10/14	07/29/14	10/02/14	01/12/15
Analysis by TO-15 (µg/m <sup>3</sup> )																						
1,1,1-Trichloroethane	51000	3900	2600	450	850	300	1	0.7 J	0.7 J	1500	1500	3200	4400	3400	1900	2200	2900	2600	1200	1600	2500	2000
1,1-Dichloroethane	1200	65	34	14	31	5	0.8 J	0.4 J	0.4 J	28	28	61	76	62	35	36	57	50	22	29	51	39
1,1-Dichloroethene	250	ND	ND	4	8	ND	0.7 J	0.4 J	0.5 J	7.6 J	10	ND	15 J	ND	12 J	8.9 J	16 J	11 J	7.9 J	6.2 J	21	11 J
1,2-Dichloroethane	NR	30	ND	4	8	ND	0.9	0.5 J	0.5 J	6.9 J	6.4 J	11 J	14 J	12 J	10 J	8.6 J	9.2 J	7.5 J	4.4 J	9.2 J	12 J	9.8 J
cis-1,2-Dichloroethene	480	59	ND	9	15	3	0.7 J	ND	0.4 J	7.1 J	7.4 J	20 J	22 J	14 J	6.2 J	11 J	22 J	12 J	4.2 J	8.8 J	24	9.4 J
Tetrachloroethene	1700	410	260	36	63	10	1	ND	2	48	46	93	120	80	49	79	100	80	34	67	83	54
trans-1,2-Dichloroethene	ND	ND	ND	ND	ND	ND	0.7 J	0.4 J	0.4 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Trichloroethene	180000	18000	14000	1200	2400	560	1	0.6 J	0.6 J	4200	4300	7200	12000	8100	5200	5400	8900	7100	3300	4400	6900	5300
Vinyl Chloride	ND	ND	ND	ND	ND	ND	0.5 J	0.3 J	0.3 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND

Sample Date	SVE 1011																					
	05/07/15	08/12/15	10/29/15	01/13/16	04/21/16	09/13/16	11/16/16	01/17/17	04/26/17	08/15/17	12/11/17	02/06/18	05/03/18	08/02/18	11/05/18	02/05/19	05/02/19	08/12/19	12/20/19	02/27/20	05/07/20	08/12/20
Analysis by TO-15 (µg/m <sup>3</sup> )																						
1,1,1-Trichloroethane	720	520	2200	2700	3000	ND	ND	1100	1400	2700	4300	3600	950	1900	2500	1500	920	1400	2000	2000	1100	2000
1,1-Dichloroethane	15	10	42	45	38	ND	ND	17	22	47	59	43	16	25	35	22	15	21	34	32	16	29
1,1-Dichloroethene	ND	ND	ND	ND	6.9 J	ND	ND	4.5 J	6.0 J	8.0 J	ND	8.2 J	ND	ND	ND	ND	ND	ND	10 J	8.0 J	4.7 J	3.8 J
1,2-Dichloroethane	5.2 J	3.8	15	9.0 J	ND	ND	ND	3.1 J	4.2 J	7.0 J	11 J	8.6 J	4.5 J	10.0 J	ND	6.9	7.0 J	5.6 J	7.3 J	8.0 J	4.3 J	8.0 J
cis-1,2-Dichloroethene	4.6 J	3.8	9.2 J	6.0 J	ND	ND	ND	ND	4.0 J	7.0 J	7.0 J	6.6 J	3.2 J	7.0 J	ND	ND	5.0 J	5.1 J	4.4 J	ND	ND	ND
Tetrachloroethene	31	31	74	83	82	ND	ND	29	41	87	130	100	42	74	91	56	40	60	73	60	31	78
trans-1,2-Dichloroethene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Trichloroethene	2500	1600	7600	8200	7100	ND	ND	3400	4100	7600	13000	11000	3600	5300	7500	5100	3600	4000	6100	6600	3300	6100
Vinyl Chloride	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND

**Notes:**  
µg/m<sup>3</sup> = micrograms per cubic meter  
NR = Not Recorded  
NA = Data not available  
ND = Not detected above method  
detection limit

Table 5  
Soil Vapor Extraction Containment System  
Site 1, Former Drum Marshalling Yard  
Naval Weapons Industrial Reserve Plant - Bethpage, NY  
Quarterly Vapor Monitoring Results of SVE Wells  
Through Third Quarter 2020

Sample ID	SVE 101D																						
	Sample Date	12/21/09	03/31/10	06/09/10	09/16/10	12/22/10	03/30/11	06/28/11	09/06/11	10/14/11	02/10/12	05/11/12	09/11/12	12/05/12	01/15/13	05/16/13	08/27/13	11/08/13	01/30/14	04/10/14	07/29/14	10/02/14	01/12/15
Analysis by TO-15 (µg/m <sup>3</sup> )																							
1,1,1-Trichloroethane	26000	130	53	ND	ND	ND	3	8	0.8 J	ND	3.1 J	9.9	11	ND	ND	5.6	16	14	12	20	19	12	
1,1-Dichloroethane	660	3.9	ND	ND	ND	ND	2	0.9 J	0.5 J	ND	ND	1.0 J	1.1 J	1.1 J	ND	ND	1.5 J	1.4 J	1.2 J	0.89 J	1.4 J	ND	
1,1-Dichloroethene	180	2	ND	ND	ND	ND	ND	0.7 J	0.4 J	ND	ND	ND	ND	ND	ND	ND	1.0 J	0.75 J	ND	ND	ND	ND	
1,2-Dichloroethane	NR	0.5	ND	ND	ND	ND	2	0.5 J	0.5 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	
cis-1,2-Dichloroethene	220	8.5	7.5	ND	3	ND	2	2	0.5 J	ND	ND	2.1 J	3.2	ND	ND	ND	3.0 J	4.5	3.5	1.5 J	4.1	2.3 J	
Tetrachloroethene	3200	1200	1200	ND	4	ND	26	210	2	ND	79	150	170	130	0.92 J	73	330	340	270	240	260	200	
trans-1,2-Dichloroethene	ND	ND	ND	ND	ND	ND	2	0.6 J	0.4 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	
Trichloroethene	100000	1600	310	3	1	ND	3	120	1 J	ND	200	400	350	120	ND	56	540	680	330	180	410	190	
Vinyl Chloride	ND	ND	ND	ND	ND	ND	1	0.4 J	0.3 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	

Sample Date	SVE 101D																					
	05/07/15	08/12/15	10/29/15	01/13/16	04/21/16	09/13/16	11/16/16	01/17/17	04/26/17	08/15/17	12/11/17	02/06/18	05/03/18	08/02/18	11/05/18	02/05/19	05/02/19	08/12/19	12/20/19	02/27/20	05/07/20	08/12/20
Analysis by TO-15 (µg/m <sup>3</sup> )																						
1,1,1-Trichloroethane	ND	22	22	27	22	ND	20	15	5.0	22	20	12	9.3	ND	9.8	5.9	2.1 J	14	22	6.8	7.8	3.0 J
1,1-Dichloroethane	ND	2.5 J	2.8 J	2.3 J	1.7 J	ND	3.1	2.2 J	0.85 J	3.0 J	2.3 J	2.4 J	1.8 J	ND	0.88 J	0.72 J	ND	ND	4.9	0.83 J	0.72 J	ND
1,1-Dichloroethene	ND	ND	ND	ND	ND	ND	0.76 J	0.80 J	ND	ND	ND	0.60 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,2-Dichloroethane	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
cis-1,2-Dichloroethene	ND	3.3	5.9	5.8	6.4	ND	31	21	3.9	14	12	19	4.4	ND	2.5 J	1.6 J	ND	ND	13	2.0 J	0.99 J	3.1 J
Tetrachloroethene	1.0 J	230	250	310	220	ND	300	240	66	250	190	220	190	ND	210	240	51	190	210	220	160	16
trans-1,2-Dichloroethene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Trichloroethene	1.7 J	450	1000	2200	990	ND	970	760	260	1100	880	900	780	ND	700	270	50	190	240	190	210	180
Vinyl Chloride	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND

**Notes:**  
µg/m<sup>3</sup> = micrograms per cubic meter  
NR = Not Recorded  
NA = Data not available  
ND = Not detected above method  
detection limit

Table 5  
Soil Vapor Extraction Containment System  
Site 1, Former Drum Marshalling Yard  
Naval Weapons Industrial Reserve Plant - Bethpage, NY  
Quarterly Vapor Monitoring Results of SVE Wells  
Through Third Quarter 2020

Sample ID	SVE 1021																					
	12/21/09	03/31/10	06/09/10	09/16/10	12/22/10	03/30/11	06/28/11	09/06/11	10/14/11	02/10/12	05/11/12	09/11/12	12/05/12	01/15/13	05/16/13	08/27/13	11/08/13	02/05/14	04/10/14	07/29/14	10/02/14	01/12/15
Analysis by TO-15 (µg/m <sup>3</sup> )																						
1,1,1-Trichloroethane	ND	ND	13	3	ND	NA	2	3	2	ND	0.60 J	3.3 J	ND	ND	ND	1.6 J	ND	ND	0.95 J	10	4.0 J	0.82 J
1,1-Dichloroethane	ND	ND	ND	ND	ND	NA	0.8 J	0.5 J	0.5 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,1-Dichloroethene	ND	ND	ND	ND	ND	NA	0.7 J	0.4 J	0.4 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,2-Dichloroethane	NR	ND	ND	ND	ND	NA	0.8	0.4 J	0.4 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
cis-1,2-Dichloroethene	ND	ND	ND	ND	ND	NA	0.7 J	0.5 J	0.5 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Tetrachloroethene	2.4	1.4	17	6	NR	NA	3	6	6	ND	1.6 J	6.4	1.5 J	2.4 J	1.4 J	3.3 J	2.6 J	ND	ND	10	4.8 J	1.5 J
trans-1,2-Dichloroethene	ND	ND	ND	ND	ND	NA	0.7 J	0.4 J	0.4 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Trichloroethene	5.6	3.8	300	88	3	NA	34	76	52	10	26	99	10	10	15	49	21	7.6	8.0	84	39	8.0
Vinyl Chloride	ND	ND	ND	ND	ND	NA	0.5 J	0.4 J	0.3 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND

Sample Date	SVE 1021																					
	05/07/15	08/12/15	10/29/15	01/13/16	04/21/16	09/13/16	11/16/16	01/17/17	04/26/17	08/15/17	12/11/17	02/06/18	05/03/18	08/02/18	11/05/18	02/05/19	05/02/19	08/12/19	12/20/19	02/27/20	05/07/20	08/12/20
Analysis by TO-15 (µg/m <sup>3</sup> )																						
1,1,1-Trichloroethane	1.6 J	12	2.8 J	0.87 J	ND	1.3 J	1.2 J	0.54 J	ND	6.4	0.95 J	ND	ND	7.4	1.8 J	ND	ND	8.8	ND	ND	ND	7.7
1,1-Dichloroethane	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,1-Dichloroethene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,2-Dichloroethane	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
cis-1,2-Dichloroethene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Tetrachloroethene	2.5 J	13	6.6	2.4 J	ND	2.9 J	3.2 J	1.6 J	1.4 J	7.8	2.7 J	1.4 J	1.8 J	8.1	3.4 J	1.5 J	3.8 J	11	ND	1.5 J	ND	9.6
trans-1,2-Dichloroethene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Trichloroethene	22	120	40	12	ND	21	24	8.4	12	74	15	7.9	14	72	24	7.8	15	100	0.75 J	10	11	71
Vinyl Chloride	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND

**Notes:**

µg/m<sup>3</sup> = micrograms per cubic meter  
 NR = Not Recorded  
 NA = Data not available  
 ND = Not detected above method  
 detection limit

Table 5  
Soil Vapor Extraction Containment System  
Site 1, Former Drum Marshalling Yard  
Naval Weapons Industrial Reserve Plant - Bethpage, NY  
Quarterly Vapor Monitoring Results of SVE Wells  
Through Third Quarter 2020

Sample ID	SVE 102D																					
	12/21/09	03/31/10	06/09/10	09/16/10	12/08/10	03/30/11	06/28/11	09/06/11	10/14/11	02/10/12	05/11/12	09/11/12	12/05/12	01/15/13	05/16/13	08/27/13	11/08/13	01/30/14	04/24/14	07/29/14	10/02/14	01/12/15
Analysis by TO-15 (µg/m <sup>3</sup> )																						
1,1,1-Trichloroethane	130	53	14	7	2	2	6	4	5	1.4 J	1.2 J	3.9 J	ND	ND	ND	2.3 J	3.1 J	ND	1.6 J	4.5	5.1	2.6 J
1,1-Dichloroethane	ND	2.7	ND	ND	ND	ND	1	0.6 J	0.7 J	ND	ND	0.51 J	0.95 J	ND	ND	ND	0.69 J	ND	0.44 J	ND	ND	ND
1,1-Dichloroethene	ND	ND	ND	ND	ND	ND	1	0.6 J	0.6 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,2-Dichloroethane	NR	ND	ND	ND	ND	ND	0.9	0.5 J	0.5 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	0.38 J	ND
cis-1,2-Dichloroethene	ND	1.4	ND	ND	0.9	ND	1	0.5 J	0.9	ND	ND	1.1 J	4.1	ND	ND	ND	3.4	ND	2.8 J	0.89 J	3.6	1.6 J
Tetrachloroethene	10	31	31	19	3	9	25	23	39	5.9	6.5	24	25	0.96 J	1.4 J	14	28	2.6 J	9.6	16	20	11
trans-1,2-Dichloroethene	ND	ND	ND	ND	ND	ND	1	0.5 J	0.5 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Trichloroethene	440	390	190	110	17	21	89	81	87	34	58	170	140	6.5	ND	88	160	3.9 J	39	79	92	36
Vinyl Chloride	ND	ND	ND	ND	ND	ND	0.6	0.4 J	0.3 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND

Sample Date	SVE 102D																					
	05/07/15	08/12/15	10/29/15	01/13/16	04/21/16	09/13/16	11/16/16	01/17/17	04/26/17	08/15/17	12/11/17	02/06/18	05/03/18	08/02/18	11/05/18	02/05/19	05/02/19	08/12/19	12/20/19	02/27/20	05/07/20	08/12/20
Analysis by TO-15 (µg/m <sup>3</sup> )																						
1,1,1-Trichloroethane	ND	5.2	4.9	3.5 J	1.1 J	6.6	3.8 J	2.7 J	1.8 J	3.6 J	1.8 J	1.8 J	ND	2.4 J	2.2 J	1.2 J	ND	3.0 J	1.1 J	1.0 J	ND	3.6 J
1,1-Dichloroethane	ND	ND	1.0 J	0.81 J	ND	0.93 J	0.95 J	0.8 J	0.50 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,1-Dichloroethene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,2-Dichloroethane	ND	ND	ND	ND	ND	ND	ND	0.75 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
cis-1,2-Dichloroethene	ND	4.2	9.3	8.9	4.4	13	10	5.2	2.6 J	2.2 J	1.3 J	1.8 J	ND	0.86 J	ND	2.3 J	ND	ND	0.92 J	ND	ND	3.0 J
Tetrachloroethene	3.8 J	22	41	42	18	51	37	26	15	17	15	18	6.2	12	13	9.4	2.3 J	13	8.7	7	3.9 J	18
trans-1,2-Dichloroethene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Trichloroethene	20	160	180	120	38	150	74	44	48	80	43	61	15	50	54	22	19	79	36	28	17	150
Vinyl Chloride	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND

**Notes:**

µg/m<sup>3</sup> = micrograms per cubic meter  
 NR = Not Recorded  
 NA = Data not available  
 ND = Not detected above method  
 detection limit

Table 5  
Soil Vapor Extraction Containment System  
Site 1, Former Drum Marshalling Yard  
Naval Weapons Industrial Reserve Plant - Bethpage, NY  
Quarterly Vapor Monitoring Results of SVE Wells  
Through Third Quarter 2020

Sample ID	SVE 1031																						
	Sample Date	12/21/09	03/31/10	06/09/10	09/16/10	12/08/10	03/30/11	06/28/11	09/06/11	10/14/11	02/10/12	05/11/12	09/11/12	12/05/12	01/15/13	05/16/13	08/27/13	11/08/13	01/30/14	04/10/14	07/29/14	10/02/14	01/12/15
Analysis by TO-15 (µg/m <sup>3</sup> )																							
1,1,1-Trichloroethane	900	ND	ND	ND	ND	ND	0.9 J	6	6	ND	1.6 J	9.2	ND	ND	1.4 J	4.7 J	2.8 J	0.92 J	ND	4.6	4.9	ND	
1,1-Dichloroethane	26	ND	ND	ND	ND	ND	0.6 J	2	2	ND	0.75 J	1.5 J	0.77 J	ND	ND	1.5 J	1.3 J	ND	ND	0.89 J	2.0 J	ND	
1,1-Dichloroethene	ND	ND	ND	ND	ND	ND	0.6 J	0.6 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	
1,2-Dichloroethane	NR	ND	ND	ND	ND	ND	0.7 J	0.5 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	
cis-1,2-Dichloroethene	58	ND	ND	1	ND	1	0.5 J	16	12	18	16	19	6.0	2.4 J	5.0	11	15	6.9	3.4	4.2	6.1	ND	
Tetrachloroethene	580	ND	ND	ND	ND	2	1 J	420	590	140	200	430	120	40	78	220	200	97	40	150	130	8.6	
trans-1,2-Dichloroethene	580	ND	ND	ND	ND	ND	0.6 J	1	1	ND	ND	ND	ND	ND	ND	ND	0.85 J	ND	ND	ND	ND	ND	
Trichloroethene	900	0.9	ND	ND	ND	ND	0.9 J	100	97	29	47	130	48	16	35	95	78	46	20	47	50	4.9 J	
Vinyl Chloride	ND	ND	ND	ND	ND	ND	0.4 J	0.4 J	0.3 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	

Sample Date	05/07/15	08/12/15	10/29/15	01/13/16	04/21/16	09/13/16	11/16/16	01/17/17	04/26/17	08/15/17	12/11/17	02/06/18	05/03/18	08/02/18	11/05/18	02/05/19	05/02/19	08/12/19	12/20/19	02/27/20	05/07/20	08/12/20
Analysis by TO-15 (µg/m <sup>3</sup> )																						
1,1,1-Trichloroethane	1.3 J	6.6	3.6 J	1.2 J	0.76 J	6.0	2.2 J	0.73 J	ND	6.0	0.94 J	0.77 J	ND	5.8	2.4 J	1.0 J	ND	11	5.1	ND	4.8	6.7
1,1-Dichloroethane	0.68 J	ND	1.4 J	ND	ND	1.9 J	1.1 J	ND	ND	1.8 J	ND	ND	ND	1.5 J	ND	ND	1.0 J	1.8 J	2.7 J	ND	0.67 J	ND
1,1-Dichloroethene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,2-Dichloroethane	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
cis-1,2-Dichloroethene	11	9.3	7.3	13	2.7 J	5.2	2.2 J	1.8 J	1.3 J	5.8	0.75 J	1.4 J	1.6 J	3.4	2.9	3.4	2.3 J	5.6	8.6	1.8 J	3.2	1.7 J
Tetrachloroethene	130	290	210	450	71	200	99	70	36	180	56	56	70	200	120	150	69	510	190	100	1200	190
trans-1,2-Dichloroethene	ND	ND	ND	ND	ND	1.3 J	ND	ND	ND	ND	ND	ND	ND	1.2 J	ND	ND	ND	ND	ND	ND	ND	ND
Trichloroethene	37	92	74	70	17	67	34	20	9.9	63	21	19	17	54	36	24	18	90	89	23	29	33
Vinyl Chloride	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND

**Notes:**

µg/m<sup>3</sup> = micrograms per cubic meter  
 NR = Not Recorded  
 NA = Data not available  
 ND = Not detected above method  
 detection limit

Table 5  
Soil Vapor Extraction Containment System  
Site 1, Former Drum Marshalling Yard  
Naval Weapons Industrial Reserve Plant - Bethpage, NY  
Quarterly Vapor Monitoring Results of SVE Wells  
Through Third Quarter 2020

Sample ID	SVE 103D																						
	Sample Date	12/21/09	03/31/10	06/09/10	09/16/10	12/08/10	03/30/11	06/28/11	09/06/11	10/14/11	02/10/12	05/11/12	09/11/12	12/05/12	01/15/13	05/16/13	08/27/13	11/08/13	01/30/14	04/10/14	07/29/14	10/02/14	01/12/15
Analysis by TO-15 (µg/m <sup>3</sup> )																							
1,1,1-Trichloroethane	3000	1100	230	ND	13	ND	2 J	20	31	7.4 J	6.9 J	22	190	ND	150	170	200	550	400	25	38	ND	
1,1-Dichloroethane	82	69	ND	ND	2	2	1 J	4	9	1.6 J	1.5 J	1.9 J	10 J	ND	10	10 J	20 J	50	48	ND	7.8 J	ND	
1,1-Dichloroethene	ND	ND	ND	ND	ND	ND	1 J	2	6 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	
1,2-Dichloroethane	NR	ND	ND	ND	ND	ND	1 J	1 J	6 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	
cis-1,2-Dichloroethene	420	1500	370	ND	92	ND	1 J	360	160	290	230	300	750	ND	550	700	2600	2100	1800	280	490	ND	
Tetrachloroethene	20000	28000	16000	9	1500	ND	3	1600	6700	3800	3200	4700	4600	1.6 J	3300	4900	17000	15000	8600	6600	8900	ND	
trans-1,2-Dichloroethene	ND	24	ND	ND	1	ND	1 J	3	7 J	ND	ND	ND	8.8 J	ND	5.7 J	8.8 J	18 J	32	18	ND	ND	ND	
Trichloroethene	3100	1600	640	7	92	ND	2 J	290	240	180	200	480	440	6.0	360	660	2100	1400	900	530	680	ND	
Vinyl Chloride	ND	5.9	ND	ND	2	ND	0.8 J	4	5 J	ND	ND	ND	ND	ND	1.9 J	ND	14 J	ND	2.6 J	ND	ND	ND	

Sample Date	SVE 103D																						
	05/07/15	08/12/15	10/29/15	01/13/16	04/21/16	09/13/16	11/16/16	01/17/17	04/26/17	08/15/17	12/11/17	02/06/18	05/03/18	08/02/18	11/05/18	02/05/19	05/02/19	08/12/19	12/20/19	02/27/20	05/07/20	08/12/20	
Analysis by TO-15 (µg/m <sup>3</sup> )																							
1,1,1-Trichloroethane	310	26	30 J	ND	38	ND	16 J	11 J	23 J	22	8.2 J	63	47	35	33 J	18 J	19	48	48	150	170	29	
1,1-Dichloroethane	24	ND	ND	ND	ND	ND	6.2 J	ND	4.3 J	ND	ND	4.5 J	ND	ND	ND	ND	2.7 J	ND	12 J	14 J	15 J	5	
1,1-Dichloroethene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	
1,2-Dichloroethane	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	
cis-1,2-Dichloroethene	930	310	530	ND	310	ND	340	210	250	180	130	320	210	190	340	200	160	140	330	310	400	120	
Tetrachloroethene	5800	8900	17000	ND	7500	ND	12000	13000	7500	6800	9200	8000	7700	6900	12000	8000	4400	8400	9000	22000	15000	680	
trans-1,2-Dichloroethene	17	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	
Trichloroethene	580	640	1200	ND	300	ND	730	620	320	440	420	380	340	340	460	260	180	380	560	420	410	57	
Vinyl Chloride	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	

**Notes:**

µg/m<sup>3</sup>= micrograms per cubic meter  
 NR = Not Recorded  
 NA = Data not available  
 ND = Not detected above method  
 detection limit

Table 5  
Soil Vapor Extraction Containment System  
Site 1, Former Drum Marshalling Yard  
Naval Weapons Industrial Reserve Plant - Bethpage, NY  
Quarterly Vapor Monitoring Results of SVE Wells  
Through Third Quarter 2020

Sample ID	SVE 1041																						
	Sample Date	12/21/09	03/31/10	06/09/10	09/16/10	12/08/10	03/30/11	06/28/11	09/06/11	10/14/11	02/10/12	05/11/12	09/11/12	12/05/12	01/15/13	05/16/13	08/27/13	11/08/13	01/30/14	04/24/14	07/29/14	10/02/14	01/12/15
Analysis by TO-15 (µg/m <sup>3</sup> )																							
1,1,1-Trichloroethane	730	4.2	ND	4	NR	NA	1 J	4	2	ND	ND	8.3	ND	ND	ND	3.1 J	2.6 J	ND	9.6	17	15	7.0	
1,1-Dichloroethane	24	0.54	ND	ND	ND	NA	1 J	0.6 J	0.5 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	7.4	8.7	7.7	6.6	
1,1-Dichloroethene	ND	ND	ND	ND	ND	NA	1 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	
1,2-Dichloroethane	NR	ND	ND	ND	ND	NA	1 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	
cis-1,2-Dichloroethene	110	14	ND	2	0.8	NA	0.9 J	2	3	0.90 J	ND	5.0	ND	2.7 J	ND	3.3	5.3	ND	94	160	160	130	
Tetrachloroethene	3100	210	68	96	16	NA	2 J	54	33	12	ND	86	1.6 J	4.8 J	2.3 J	30	36	ND	69	210	190	91	
trans-1,2-Dichloroethene	15	ND	ND	ND	ND	NA	1 J	0.5 J	0.4 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	1.8 J	2.1 J	1.4 J		
Trichloroethene	710	44	60	72	12	NA	2 J	44	25	9.6	ND	73	ND	3.1 J	ND	30	31	ND	39	110	120	43	
Vinyl Chloride	ND	0.47	ND	ND	ND	NA	0.7 J	0.3 J	0.3 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	

Sample Date	SVE 1041																					
	05/07/15	08/12/15	10/29/15	01/13/16	04/21/16	09/13/16	11/16/16	01/17/17	04/26/17	08/15/17	12/11/17	02/06/18	05/03/18	08/02/18	11/05/18	02/05/19	05/02/19	08/12/19	12/20/19	02/27/20	05/07/20	08/12/20
Analysis by TO-15 (µg/m <sup>3</sup> )																						
1,1,1-Trichloroethane	1.5 J	8.3	4.0 J	4.6	0.48 J	6.9	6.5	ND	1.2 J	7.8	1.7 J	1.3 J	1.4 J	9.1	3.1 J	1.7 J	1.9 J	14	1.2 J	1.3 J	1.8 J	68
1,1-Dichloroethane	ND	ND	ND	2.9 J	ND	ND	3.6	ND	ND	1.3 J	ND	ND	ND	1.4 J	ND	ND	ND	ND	ND	ND	ND	6.4 J
1,1-Dichloroethene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,2-Dichloroethane	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
cis-1,2-Dichloroethene	7.3	4.2	6.6	54	0.92 J	2.1 J	110	ND	4.1	31	6.7	4.6	12	27	20	18	17	28	13	7.4	1.8 J	18
Tetrachloroethene	13	82	66	79	10	80	530	0.68 J	21	190	90	20	34	96	76	46	34	130	20	21	11	3900
trans-1,2-Dichloroethene	ND	ND	ND	ND	ND	ND	1.2 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Trichloroethene	17	85	54	35	7.6	83	110	ND	15	87	22	11	15	63	33	14	24	73	13	10	9.3	170
Vinyl Chloride	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND

**Notes:**

µg/m<sup>3</sup>= micrograms per cubic meter  
 NR = Not Recorded  
 NA = Data not available  
 ND = Not detected above method  
 detection limit



Table 5  
Soil Vapor Extraction Containment System  
Site 1, Former Drum Marshalling Yard  
Naval Weapons Industrial Reserve Plant - Bethpage, NY  
Quarterly Vapor Monitoring Results of SVE Wells  
Through Third Quarter 2020

Sample ID	SVE 104D																						
	Sample Date	12/21/09	03/31/10	06/09/10	09/16/10	12/22/10	03/30/11	06/28/11	09/06/11	10/14/11	02/10/12	05/11/12	09/11/12	12/05/12	01/15/13	05/16/13	08/27/13	11/08/13	01/30/14	04/10/14	07/29/14	10/02/14	01/12/15
Analysis by TO-15 (µg/m <sup>3</sup> )																							
1,1,1-Trichloroethane	3600	3000	860	ND	270	ND	370	620	440	520	580	620	920	820	0.89 J	500	600	340	84	930	880	1.7 J	
1,1-Dichloroethane	290	350	140	ND	66	ND	56	110	77	87	95	100	190	160	ND	95	130	56	22	120	130	ND	
1,1-Dichloroethene	ND	ND	ND	ND	ND	ND	3	7 J	7 J	3.0 J	5.0 J	ND	11 J	ND	ND	ND	ND	4.3 J	1.0 J	ND	ND	ND	
1,2-Dichloroethane	NR	ND	ND	ND	ND	ND	1 J	5 J	5 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	
cis-1,2-Dichloroethene	2400	6600	3500	ND	1200	ND	1000	3600	2100	2200	2800 J	2200	4200	3700	8.6	2000	3200	1600	460	3300	4400	21	
Tetrachloroethene	20000	39000	21000	ND	2400	ND	1400	5800	6300	3800	4300	4600	4500	4200	69	2600	3900	2500	780	8200	8000	120	
trans-1,2-Dichloroethene	130	70	30	ND	13	ND	14	25	22	26	31	27	55	40	ND	24	40	15	3.5	34	53	ND	
Trichloroethene	4600	6000	2400	ND	470	ND	420	1600	1300	1400	1400	1700	2300	2100	14	1200	1600	1100	430	2000	2100	19	
Vinyl Chloride	ND	12	ND	ND	ND	ND	2	5	5 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	

Sample Date	SVE 104D																					
	05/07/15	08/12/15	10/29/15	01/13/16	04/21/16	09/13/16	11/16/16	01/17/17	04/26/17	08/15/17	12/11/17	02/06/18	05/03/18	08/02/18	11/05/18	02/05/19	05/02/19	08/12/19	12/20/19	02/27/20	05/07/20	08/12/20
Analysis by TO-15 (µg/m <sup>3</sup> )																						
1,1,1-Trichloroethane	350	480	790	760	460	460	710	88	260	390	290	440	520	510	100	480	410	460	360	320	270	630
1,1-Dichloroethane	72	77	120	91	54	73	110	11	31	60	44	67	57	59	15	54	50	47	73	37	18	76
1,1-Dichloroethene	ND	ND	ND	ND	ND	ND	7.6 J	1.2 J	2.9 J	3.0 J	ND	ND	ND	ND	ND	ND	ND	ND	4.2 J	ND	5.8 J	
1,2-Dichloroethane	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
cis-1,2-Dichloroethene	1500	2500	3600	3200	1900	2400	3800	400	1000	2200	1600	2500	2200	2300	700	2500	1900	1800	3000	1600	830	3400
Tetrachloroethene	2200	5100	10000	7700	4500	9400	15000	1400	3000	5900	7600	6000	6500	6800	1500	6500	4400	4800	3200	3600	2000	8800
trans-1,2-Dichloroethene	18	39	49	38	30	38	67	6.5	16	30	22	37	39	37	9.3	43	36	30	45	27	20	36
Trichloroethene	1100	1200	2200	1600	750	1400	2200	290	600	980	860	1100	870	870	210	790	740	780	690	600	370	1000
Vinyl Chloride	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND

**Notes:**

µg/m<sup>3</sup>= micrograms per cubic meter  
 NR = Not Recorded  
 NA = Data not available  
 ND = Not detected above method  
 detection limit

Table 5  
Soil Vapor Extraction Containment System  
Site 1, Former Drum Marshalling Yard  
Naval Weapons Industrial Reserve Plant - Bethpage, NY  
Quarterly Vapor Monitoring Results of SVE Wells  
Through Third Quarter 2020

Sample ID	SVE 1051																					
	12/21/09	03/31/10	06/09/10	09/16/10	12/08/10	03/30/11	06/28/11	09/06/11	10/14/11	02/10/12	05/11/12	09/11/12	12/05/12	01/15/13	05/16/13	08/27/13	11/08/13	01/30/14	04/10/14	07/29/14	10/02/14	01/12/15
Analysis by TO-15 (µg/m <sup>3</sup> )																						
1,1,1-Trichloroethane	9.9	11	29	ND	24	1	1 J	21	31	11	13	26	22	22	11	24	18	32	26	17	20	20
1,1-Dichloroethane	ND	5.7	13	ND	6	ND	0.6 J	5	7	4.2	5.6	5.6	10	12	8.8	8.0	7.4	24	6.8	7.0	8.2	8.6
1,1-Dichloroethene	ND	ND	ND	ND	ND	ND	0.6 J	0.6 J	0.5 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,2-Dichloroethane	NR	ND	ND	ND	ND	ND	0.7 J	0.6 J	0.5 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
cis-1,2-Dichloroethene	ND	6.6	20	ND	ND	ND	1	10	16	8.1	9.7	13	16	13	14	14	7.4	17	6.2	9.5	12	7.5
Tetrachloroethene	70	9.1	240	ND	55	5	2	95	100	31	43	100	77	66	38	91	57	77	48	73	85	51
trans-1,2-Dichloroethene	ND	ND	1.6	ND	ND	ND	0.5 J	1	1	ND	ND	1.5 J	ND	ND	ND	ND	1.0 J	1.6 J	ND	ND	2.8 J	ND
Trichloroethene	76	6.3	370	ND	120	7	1	170	200	110	140	260	180	160	94	220	140	180	190	140	200	130
Vinyl Chloride	ND	ND	ND	ND	ND	ND	0.4 J	0.4 J	0.3 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND

Sample Date	SVE 1051																					
	05/07/15	08/12/15	10/29/15	01/13/16	04/21/16	09/13/16	11/16/16	01/17/17	04/26/17	08/15/17	12/11/17	02/06/18	05/03/18	08/02/18	11/05/18	02/05/19	05/02/19	08/12/19	12/20/19	02/27/20	05/07/20	08/12/20
Analysis by TO-15 (µg/m <sup>3</sup> )																						
1,1,1-Trichloroethane	25	29	30	12	5.0	16	11	5.6	4.8	13	5.6	4.9	3.5 J	8.7	10	4.6	3.3 J	21	4.8	2.3 J	88	40
1,1-Dichloroethane	22	15	28	17	1.5 J	2.8	3.4	2.2 J	2.7 J	2.1 J	0.98 J	3.5	0.99 J	1.2 J	1.6 J	1.3 J	4.8	3.4	1.8 J	0.86 J	ND	9.9
1,1-Dichloroethene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,2-Dichloroethane	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	1.6 J	ND	ND	ND	ND	ND	ND	ND	ND
cis-1,2-Dichloroethene	31	28	23	17	1.8 J	7.9	5.0	2.6 J	4.2	5.1	1.9 J	5.0	2.5 J	1.9 J	3.7	2.1 J	7.5	6.2	3.2	ND	ND	0.98 J
Tetrachloroethene	43	87	66	44	27	64	46	26	17	50	27	21	17	23	46	20	13	38	15	11	9.3	41
trans-1,2-Dichloroethene	ND	ND	2.3 J	ND	ND	0.83 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Trichloroethene	160	290	240	84	39	250	160	50	38	140	58	40	30	60	110	36	32	130	41	17	18	67
Vinyl Chloride	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND

**Notes:**

µg/m<sup>3</sup>= micrograms per cubic meter  
 NR = Not Recorded  
 NA = Data not available  
 ND = Not detected above method  
 detection limit

Table 5  
Soil Vapor Extraction Containment System  
Site 1, Former Drum Marshalling Yard  
Naval Weapons Industrial Reserve Plant - Bethpage, NY  
Quarterly Vapor Monitoring Results of SVE Wells  
Through Third Quarter 2020

Sample ID	SVE 105D																						
	Sample Date	12/21/09	03/31/10	06/09/10	09/16/10	12/08/10	03/30/11	06/28/11	09/06/11	12/02/11	02/10/12	05/11/12	09/11/12	12/05/12	01/15/13	05/16/13	08/27/13	11/08/13	01/30/14	04/10/14	07/29/14	10/02/14	01/12/15
Analysis by TO-15 (µg/m <sup>3</sup> )																							
1,1,1-Trichloroethane	550	47	320	1000	590	ND	1 J	490	930	350	320	270	380	430	160	110	120	190	ND	92	79	4.3 J	
1,1-Dichloroethane	300	28	270	250	ND	ND	0.6 J	74	150	69	78	72	110	110	46	45	70	46	ND	36	28	ND	
1,1-Dichloroethene	3.9	ND	ND	2	4	4	0.6 J	6 J	ND	ND	ND	ND	ND	ND	ND	ND	1.5 J	ND	ND	ND	ND	ND	
1,2-Dichloroethane	NR	ND	ND	ND	ND	ND	4	5 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	
cis-1,2-Dichloroethene	61	36	85	300	ND	ND	0.7 J	150	380	190	220	150	210	200	73	76	85	46	ND	50	36	ND	
Tetrachloroethene	2100	1.1	650	270	420	ND	2	240	330	140	220	270	350	330	100	140	260	300	ND	140	120	2.1 J	
trans-1,2-Dichloroethene	19	1.1	3.1	3	ND	ND	0.6 J	7 J	3 J	ND	ND	ND	ND	ND	1.4 J	2.4 J	3.6	1.3 J	ND	1.3 J	1.9 J	ND	
Trichloroethene	1700	68	200	1100	1400	1	2	3000	7000	3600	4500	2200	3800	3800	1400	900	1200	1900	8.5	650	520	15	
Vinyl Chloride	ND	ND	ND	ND	ND	ND	0.4 J	4 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	

Sample Date	SVE 105D																					
	05/07/15	08/12/15	10/29/15	01/13/16	04/21/16	09/13/16	11/16/16	01/17/17	04/26/17	08/15/17	12/11/17	02/06/18	05/03/18	08/02/18	11/05/18	02/05/19	05/02/19	08/12/19	12/20/19	02/27/20	05/07/20	08/12/20
Analysis by TO-15 (µg/m <sup>3</sup> )																						
1,1,1-Trichloroethane	16	35	52	62	68	47	29	23	38	33	24	28	13	ND	27	61	75	54	66	26	15	200
1,1-Dichloroethane	4.7	12	30	21	15	22	23	19	21	12	14	12	12	ND	14	16	22	20	25	13	3.7	79
1,1-Dichloroethene	ND	ND	ND	ND	ND	ND	ND	ND	ND	2.7 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	3.1 J
1,2-Dichloroethane	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
cis-1,2-Dichloroethene	3.6	16	22	18	26	31	19	19	32	20	13	17	22	ND	18	24	32	36	27	26	4.1	9.3
Tetrachloroethene	18	76	130	140	130	150	110	69	70	120	130	97	48	ND	140	140	85	78	100	94	39	31
trans-1,2-Dichloroethene	ND	ND	ND	ND	ND	1.8 J	2.0 J	1.2 J	1.6 J	ND	ND	ND	ND	ND	0.88 J	0.92 J	ND	ND	1.7 J	ND	ND	ND
Trichloroethene	75	250	400	410	350	360	210	140	200	310	170	160	57	ND	140	170	220	190	180	110	83	470
Vinyl Chloride	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND

**Notes:**

µg/m<sup>3</sup> = micrograms per cubic meter  
 NR = Not Recorded  
 NA = Data not available  
 ND = Not detected above method  
 detection limit

Table 5  
Soil Vapor Extraction Containment System  
Site 1, Former Drum Marshalling Yard  
Naval Weapons Industrial Reserve Plant - Bethpage, NY  
Quarterly Vapor Monitoring Results of SVE Wells  
Through Third Quarter 2020

Sample ID	SVE 1061																					
	12/21/09	03/31/10	06/09/10	09/16/10	12/08/10	03/30/11	06/28/11	09/06/11	10/14/11	02/10/12	05/11/12	09/11/12	12/05/12	01/15/13	05/16/13	08/27/13	11/08/13	01/30/14	04/10/14	07/29/14	10/02/14	01/12/15
Analysis by TO-15 (µg/m <sup>3</sup> )																						
1,1,1-Trichloroethane	220	8.6	ND	4	ND	NA	6	3	7	1.0 J	2.2 J	11	ND	ND	ND	ND	18	1.4 J	3.8 J	8.9	2.2 J	ND
1,1-Dichloroethane	120	ND	ND	1	ND	NA	1	0.5 J	1	0.62 J	0.70 J	1.6 J	2.5 J	1.9 J	ND	ND	3.8	ND	17	3.9	1.1 J	ND
1,1-Dichloroethene	ND	ND	ND	ND	ND	NA	0.6 J	2	0.6 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,2-Dichloroethane	NR	ND	ND	0.8	ND	NA	0.6 J	0.5 J	0.6 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
cis-1,2-Dichloroethene	46	ND	ND	4	ND	NA	6	0.5 J	4	1.6 J	2.3 J	7.5	5.4	3.7	ND	ND	8.3	ND	23	11	3.1 J	ND
Tetrachloroethene	390	35	ND	15	ND	NA	15	7	19	4.3 J	7.2	27	14	7.0	0.73 J	ND	19	4.2 J	6.2	11	2.9 J	ND
trans-1,2-Dichloroethene	7.9	ND	3.1	0.9	ND	NA	0.8	0.5 J	0.7 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Trichloroethene	1900	41	ND	140	10	NA	210	92	190	69	110	260	180	110	5.5	ND	210	28	70	110	16	0.87 J
Vinyl Chloride	ND	ND	ND	0.5	ND	NA	0.4 J	0.3 J	0.4 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND

Sample Date																						
	05/07/15	08/12/15	10/29/15	01/13/16	04/21/16	09/13/16	11/16/16	01/17/17	04/26/17	08/15/17	12/11/17	02/06/18	05/03/18	08/02/18	11/05/18	02/05/19	05/02/19	08/12/19	12/20/19	02/27/20	05/07/20	08/12/20
Analysis by TO-15 (µg/m <sup>3</sup> )																						
1,1,1-Trichloroethane	8.0	29	30	2.8 J	1.5 J	12	7.5	5.5	2.0 J	11	4.8	0.91 J	2.0 J	8.8	4.2	0.78 J	1.9 J	14	34	880	7.0 J	27
1,1-Dichloroethane	18	2.6 J	3.4	1.2 J	ND	ND	1.3 J	2.4 J	0.56 J	5.4	1.9 J	ND	1.6 J	0.69 J	ND	1.2 J	ND	ND	5.6	260	ND	3.2 J
1,1-Dichloroethene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	55	ND	ND
1,2-Dichloroethane	1.3 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
cis-1,2-Dichloroethene	23	6.6	4.9	3.2	0.84 J	3.8	3.1 J	3.2	1.5 J	14	3.9	0.57 J	2.2 J	1.7 J	1.5 J	3.4	1.8 J	1.4 J	5.8	6600	41	86
Tetrachloroethene	14	39	49	11	5.1 J	20	6.7	4.9	3.9 J	16	8.3	2.5 J	4.5 J	12	9.9	3.1 J	3.1 J	20	20	96000	5500	1400
trans-1,2-Dichloroethene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	33 J	ND	ND
Trichloroethene	130	560	660	200	40	190	71	53	59	170	83	39	45	88	79	43	44	150	100	9300	180	310
Vinyl Chloride	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND

**Notes:**  
µg/m<sup>3</sup> = micrograms per cubic meter  
NR = Not Recorded  
NA = Data not available  
ND = Not detected above method  
detection limit

Table 5  
Soil Vapor Extraction Containment System  
Site 1, Former Drum Marshalling Yard  
Naval Weapons Industrial Reserve Plant - Bethpage, NY  
Quarterly Vapor Monitoring Results of SVE Wells  
Through Third Quarter 2020

Sample ID	SVE 106D																					
	12/21/09	03/31/10	06/09/10	09/16/10	12/08/10	03/30/11	06/28/11	09/06/11	10/14/11	02/10/12	05/11/12	09/11/12	12/05/12	01/15/13	05/16/13	08/27/13	11/08/13	01/30/14	04/10/14	07/29/14	10/02/14	01/12/15
Analysis by TO-15 (µg/m <sup>3</sup> )																						
1,1,1-Trichloroethane	340	32	30	20	12	9	20	23	29	ND	11	26	18	ND	ND	27	25	5.8	6.3	14	28	ND
1,1-Dichloroethane	250	6.3	ND	5	2	5	4	3	3	ND	3.0	4.3	5.8	ND	ND	4.9	11	3.7	3.3	5.1	8.9	ND
1,1-Dichloroethene	ND	ND	ND	ND	ND	ND	0.5 J	0.7 J	0.8	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,2-Dichloroethane	NR	ND	ND	ND	ND	ND	ND	0.6 J	0.7 J	ND	ND	ND	ND	ND	ND	2.5 J	ND	ND	ND	ND	1.1 J	ND
cis-1,2-Dichloroethene	79	13	11	13	2	11	11	5	4	ND	4.1	7.1	8.2	ND	ND	10	15	2.8 J	3.9	8.4	15	ND
Tetrachloroethene	720	65	70	ND	13	19	41	8	66	ND	28	62	48	ND	1.3 J	50	58	16	17	22	60	ND
trans-1,2-Dichloroethene	15	ND	ND	ND	ND	ND	0.6 J	0.8	0.9	ND	ND	ND	ND	ND	ND	1.1 J	ND	ND	ND	ND	ND	ND
Trichloroethene	3400	600	900	230	130	170	210	260	320	ND	180	380	300	ND	ND	460	440	160	84	170	370	0.56 J
Vinyl Chloride	ND	1.6	ND	ND	ND	ND	ND	0.4 J	0.5 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND

Sample Date	05/07/15	08/12/15	10/29/15	01/13/16	04/21/16	09/13/16	11/16/16	01/17/17	04/26/17	08/15/17	12/11/17	02/06/18	05/03/18	08/02/18	11/05/18	02/05/19	05/02/19	08/12/19	12/20/19	02/27/20	05/07/20	08/12/20
	Analysis by TO-15 (µg/m <sup>3</sup> )																					
1,1,1-Trichloroethane	26	ND	ND	11	7.2	30	14	10	7.6	18	8.3	4.6	2.2 J	14	12	10	8.0	30	250	500	46	7.5
1,1-Dichloroethane	2.6 J	ND	ND	2.7 J	13	6.8	21	17	2.6 J	11	7.1	1.6 J	2.8 J	6.1	7.9	7.3	2.2 J	2.5 J	36	260	12 J	ND
1,1-Dichloroethene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	25 J	ND	ND
1,2-Dichloroethane	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
cis-1,2-Dichloroethene	36	ND	ND	3.2	24	14	22	20	5.6	24	13	5.0	4.6	16	21	22	7.5	16	15	3700	240	1.3 J
Tetrachloroethene	110	ND	1.4 J	33	27	57	33	24	17	44	39	15	9.5	26	37	26	15	37	35	25000	4800	27
trans-1,2-Dichloroethene	ND	ND	ND	ND	ND	0.63 J	1.3 J	2.1 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	20 J	ND	ND
Trichloroethene	71	1.6 J	ND	280	170	450	210	170	190	300	220	140	89	210	220	170	170	420	290	4400	730	37
Vinyl Chloride	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	0.52 J	ND	ND	ND

**Notes:**  
µg/m<sup>3</sup> = micrograms per cubic meter  
NR = Not Recorded  
NA = Data not available  
ND = Not detected above method  
detection limit

**Table 6**  
**Soil Vapor Extraction Containment System**  
**Site 1, Former Drum Marshalling Yard**  
**Naval Weapons Industrial Reserve Plant - Bethpage, NY**  
**Third Quarter 2020 Off-site Soil Vapor Monitoring of SVPMs**

SVPM/ SVEW Location	Pressure Reading (i.w.)	Valve Position (% open)
<b>Monitoring Date:</b>	<b>8/12/20</b>	<b>8/12/20</b>
BPS1-SVPM2001S	-0.23	--
BPS1-SVPM2001I	-0.17	--
BPS1-SVPM2001D	-0.11	--
BPS1-SVPM2002S	-0.09	--
BPS1-SVPM2002I	-0.15	--
BPS1-SVPM2002D	-0.20	--
BPS1-SVPM2003S	-0.03	--
BPS1-SVPM2003I	-0.06	--
BPS1-SVPM2003D	-0.08	--
BPS1-SVPM2004S	-0.04	--
BPS1-SVPM2004I	-0.06	--
BPS1-SVPM2004D	-0.09	--
BPS1-SVPM2006S	-0.06	--
BPS1-SVPM2006I	-0.05	--
BPS1-SVPM2006D	-0.03	--
BPS1-SVPM2007S	-0.06	--
BPS1-SVPM2007I	-0.04	--
BPS1-SVPM2007D	-0.04	--
SV-101I	-3.0	40
SV-101D	-8.0	50
SV-102I	-4.0	40
SV-102D	-6.0	40
SV-103I	-5.0	40
SV-103D	-7.0	40
SV-104I	-7.0	40
SV-104D	-5.0	40
SV-105I	-4.0	40
SV-105D	-6.0	40
SV-106I	-7.0	40
SV-106D	-10.0	50

**Notes:**

i.w. = inches of water column  
SVEW = soil vapor extraction well  
SVPM = soil vapor pressure monitor

Pressure readings for the SVPMs were measured using a portable Magnehelic® Differential Pressure Gauge 2000-0, with a range of 0-0.50 i.w. Vacuum readings for SVEWs were recorded from dedicated in-line pressure gauges.

**APPENDIX A**

**NYSDEC AIR DISCHARGE LIMIT  
DOCUMENTATION**



From: Steven Scharf [<mailto:sxscharf@gw.dec.state.ny.us>]  
Sent: Thursday, October 06, 2011 11:57 AM  
To: Fly, Lora B CIV NAVFAC MIDLANT, IPTNE  
Cc: John Swartwout; Walter Parish; Steven Karpinski; John cofman; [klumpe@steelequities.com](mailto:klumpe@steelequities.com);  
[David.Brayack@tnus.com](mailto:David.Brayack@tnus.com)  
Subject: NWIRP Plant 3 Site 1 SVE Modification Plan

Lora,

The New York State Department of Environmental Conservation (NYSDEC), in conjunction with the New York State Department of Health (NYSDOH), have reviewed the Navy Submittal entitled:

" Modification to existing Soil vapor Extraction (SVE) Containment System At Site 1-Former Drum Marshaling Area, Installation of Soil Vapor Extraction Wells SVE-107D to 111D, NWIRP Bethpage, September 2011."

Based on this Departmental review, and the follow up October 6, 2011 tele-conference, this modification work plan is acceptable and can be used for immediate implementation. The NWIRP Site 1 SVE system has redundant blowers and overcapacity, even with the additional SVE wells being added. should the Navy and the new property owner, Steel Equities Inc., for the former Plant 3 complex come to agreement to add SVE piping from the former Plant 3, this would be acceptable. Appropriate plans, consistent with the covenants and restrictions to the deed, should be submitted accordingly.

A letter will not follow this e-mail. If you have any questions, please contact me directly.

Electronic Documentation Information  
NWIRP Bethpage  
130003B-OU1-OMM  
FOIable  
Region 1, Nassau (C), Oyster Bay (T)

Thanks,

Steven M. Scharf, P.E.  
Project Engineer  
New York State Department of  
Environmental Conservation  
Division of Environmental Remediation  
Remedial Action, Bureau A  
625 Broadway  
Albany, NY 12233-7015  
(518)402-9620  
Fax: (518)402-9022

#### 4.0 PROPOSED REVISIONS TO VAPOR DISCHARGE GOALS

To determine the continued need for off gas treatment, the quality of the influent vapor stream was initially estimated based on soil gas results and compared to discharge goals. Vapor phase treatment was initially installed for the system based on projected relatively high concentrations of several chemicals including 1,1,1-trichloroethane (TCA), trichloroethene (TCE), and tetrachloroethene (PCE). Since the December 2009 startup, VOC concentrations in the extracted vapors have decreased by approximately 98.3 percent and it is uncertain as to whether vapor phase treatment is still required. Presented below are the December 2009 and March 2011 influent (untreated) VOC concentrations and loadings and current discharge goals.

Parameter	December 2009 Influent VOCs		March 2011 Influent VOCs ( $\mu\text{g}/\text{m}^3$ )		Current Discharge Goal (pound/hour) <sup>(3)</sup>
	Concentration ( $\mu\text{g}/\text{m}^3$ ) <sup>1</sup>	Loading (pound/hour) <sup>1</sup>	Concentration ( $\mu\text{g}/\text{m}^3$ )	Loading (pound/hour) <sup>(2)</sup>	
TCA	13,000	0.074	150	0.00023	0.13
TCE	42,000	0.26	460	0.00069	0.07
PCE	7,900	0.029	440	0.00066	0.0009

<sup>(1)</sup> Initial VOC Loading Rates are from baseline data taken in December 2009. The flow meter was not yet installed when this data was taken, so a value of 385 CFM (flow rate in January 2010) was used to estimate system loading.

<sup>(2)</sup> Calculated using a flow rate of 400 CFM.

<sup>(3)</sup> Current discharge goals were based on calculated VOC concentrations using soil gas data from the fence line investigation, a flow rate of 600 CFM, and an assumed treatment efficiency for each VOC of 80 to 90 percent. Based on this evaluation, the existing treatment is no longer required to meet discharge goals.

A DAR-1 Model Analysis was then conducted using the August 2010 influent vapor concentrations of TCA, TCE, and PCE at a flow rate of 500 CFM. The calculated results were then used to back calculate proposed discharge goals based on an allowance of 100% of the annual guideline concentrations (see Appendix E). The following table provides a summary of the proposed discharge goals.

Parameter	August 2010 Influent VOCs (370 CFM – Actual)		Percent AGC Using August 2010 Data	Proposed Discharge Goals	
	Concentration ( $\mu\text{g}/\text{m}^3$ )	Loading (pounds/ hour)		Concentration at 500 CFM ( $\mu\text{g}/\text{m}^3$ )	Loading (pounds/ hour)
TCA	868	0.0009	0.0004	None <sup>1</sup>	225
TCE	4,170	0.0039	19.4	11,000	0.02
PCE	5,780	0.0057	14.2	22,000	0.04

<sup>(1)</sup> Greater than 100,000  $\mu\text{g}/\text{m}^3$ .

AGC - Annual Guideline Concentration

**New York State Department of Environmental Conservation**  
**Division of Environmental Remediation**  
**Bureau of Remedial Action A**  
**625 Broadway, 11<sup>th</sup> Floor**  
**Albany, New York 12233-7015**  
**Phone: (518) 402-9625 • Fax: (518) 402-9022**



**Website:** [www.dec.state.ny.us](http://www.dec.state.ny.us)

February 5, 2010

Lora Fly, Project Manager  
Naval Facilities Engineering Command-Midlant  
9742 Maryland Avenue  
Norfolk, VA 23511-3095

RE: Naval Weapons Industrial Research Plant( NWIRP)  
Site-Bethpage, NYSDEC No. 1-30-003B.

Dear Ms. Fly:

Tetra Tech FW, on behalf of the Department of the Navy (Navy), has submitted the enclosed New York State Department of Environmental Conservation (NYSDEC) Division of Air Resources (DAR) Air Permit Application as a permit equivalent. This DAR Air permit equivalent is for the soil vapor extraction system at Site 1 of Plant 3 of the former Naval Weapons Industrial Reserve Plant (NWIRP) site in Bethpage, NY. The NYSDEC Division of Environmental Remediation (DER) has reviewed the permit equivalent and, by means of this letter approves the Site 1 remedy air discharge for immediate operation.

The NWIRP Site 1 SVE system utilizes the reasonably available control technology (RACT) with activated carbon. The air discharge will be periodically monitored at start up and will be added for routine monitoring in the operation, maintenance and monitoring (OMM) plan, to be submitted shortly for Departmental review.

If you have any questions, please contact me at your earliest convenience at (518)402-9620.

Sincerely,

Steven M. Scharf, P.E.  
Project Engineer  
Division of Environmental Remediation  
Bureau of Remedial Action A

Enclosure

cc/w/enc: J. Swartwout/S. Scharf/File  
W. Parish, Region 1 NYSDEC  
A. J. Shah, Region 1 NYSDEC  
S. Patselos, Tetra Tech FW  
J. Cofman, Northrop Grumman

E docs: Region 1, Nassau, Oyster Bay (T): NWIRP Bethpage 130003B-OUI-OMM

# New York State Department of Environmental Conservation Air Permit Application



DEC ID									
-	-	-	-	-	-	-	-	-	-

APPLICATION ID														
-	-	-	-	-	-	-	-	-	-	-	-	-	-	-

OFFICE USE ONLY									
/	/	/	/	/	/	/	/	/	/

## Section I - Certification

Title V Certification	
I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons directly responsible for gathering the information [required pursuant to 6 NYCRR 201-6.3(d)] I believe the information is, true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fines and imprisonment for knowing violations.	
Responsible Official	Title
Signature	Date <u>    </u> / <u>    </u> / <u>    </u>

State Facility Certification	
I certify that this facility will be operated in conformance with all provisions of existing regulations.	
Responsible Official	Title
Signature	Date <u>    </u> / <u>    </u> / <u>    </u>

## Section II - Identification Information

Title V Facility Permit <u>N/A</u> <input type="checkbox"/> New <input type="checkbox"/> Significant Modification <input type="checkbox"/> Administrative Amendment <input type="checkbox"/> Renewal <input type="checkbox"/> Minor Modification    General Permit Title: _____	State Facility Permit <u>N/A</u> <input type="checkbox"/> New <input type="checkbox"/> Modification General Permit Title: _____
<input checked="" type="checkbox"/> Application involves construction of new facility <input type="checkbox"/> Application involves construction of new emission unit(s)	

Owner/Firm			
Name <u>US Navy / NAVFAC Midlant</u>			
Street Address <u>9742 Maryland Ave, Bldg Z-144</u>			
City <u>Norfolk</u>	State <u>VA</u>	Country <u>US</u>	Zip <u>23511-3095</u>
Owner Classification <input checked="" type="checkbox"/> Federal <input type="checkbox"/> Corporation/Partnership	<input type="checkbox"/> State <input type="checkbox"/> Individual	<input type="checkbox"/> Municipal	Taxpayer ID
Facility			<input type="checkbox"/> Confidential
Name <u>Naval Weapons Industrial Reserve Plant (NWIRP) Site 1</u>			
Location Address <u>Bethpage</u>			
<input type="checkbox"/> City / <input checked="" type="checkbox"/> Town / <input type="checkbox"/> Village <u>Oyster Bay, New York</u>			Zip <u>11714</u>
Project Description			<input type="checkbox"/> Continuation Sheet(s)
<u>Vapor phase granular activated carbon to remove VOCs from soil gas</u>			

Owner/Firm Contact Mailing Address			
Name (Last, First, Middle Initial) <u>Fly, Lora</u>		Phone No. <u>(757) 444-0781</u>	
Affiliation <u>Department of the Navy</u>	Title <u>Remedial PM</u>	Fax No. ( )	
Street Address <u>9742 Maryland Ave, Bldg Z-144</u>			
City <u>Norfolk</u>	State <u>VA</u>	Country <u>US</u>	Zip <u>23511-3095</u>
Facility Contact Mailing Address			
Name (Last, First, Middle Initial)		Phone No. ( )	
Affiliation	Title	Fax No. ( )	
Street Address			
City	State	Country	Zip

**New York State Department of Environmental Conservation  
Air Permit Application**



DEC ID									
-	-	-	-	-	-	-	-	-	-

**Section III - Facility Information**

Classification						
<input type="checkbox"/> Hospital	<input type="checkbox"/> Residential	<input type="checkbox"/> Educational/Institutional	<input type="checkbox"/> Commercial	<input checked="" type="checkbox"/> Industrial	<input type="checkbox"/> Utility	

Affected States (Title V Only) <i>N/A</i>						Tribal Land: _____
<input type="checkbox"/> Vermont	<input type="checkbox"/> Massachusetts	<input type="checkbox"/> Rhode Island	<input type="checkbox"/> Pennsylvania			Tribal Land: _____
<input type="checkbox"/> New Hampshire	<input type="checkbox"/> Connecticut	<input type="checkbox"/> New Jersey	<input type="checkbox"/> Ohio			

SIC Codes									
9999									

Facility Description		<input type="checkbox"/> Continuation Sheet(s)
<i>Soil vapor remediation by SVE followed by vapor phase GAC.</i>		

Compliance Statements (Title V Only) <i>N/A</i>	
<p>I certify that as of the date of this application the facility is in compliance with all applicable requirements: <input type="checkbox"/> YES <input type="checkbox"/> NO</p> <p>If one or more emission units at the facility are not in compliance with all applicable requirements at the time of signing this application (the 'NO' box must be checked), the noncomplying units must be identified in the "Compliance Plan" block on page 8 of this form along with the compliance plan information required. For all emission units at this facility that are operating <u>in compliance</u> with all applicable requirements complete the following:</p> <ul style="list-style-type: none"> <li><input type="checkbox"/> This facility will continue to be operated and maintained in such a manner as to assure compliance for the duration of the permit, except those units referenced in the compliance plan portion of Section IV of this application.</li> <li><input type="checkbox"/> For all emission units, subject to any applicable requirements that will become effective during the term of the permit, this facility will meet all such requirements on a timely basis.</li> <li><input type="checkbox"/> Compliance certification reports will be submitted at least once a year. Each report will certify compliance status with respect to each requirement, and the method used to determine the status.</li> </ul>	

Facility Applicable Federal Requirements <i>N/A</i>								<input type="checkbox"/> Continuation Sheet(s)	
Title	Type	Part	Sub Part	Section	Sub Division	Paragraph	Sub Paragraph	Clause	Sub Clause

Facility State Only Requirements								<input type="checkbox"/> Continuation Sheet(s)	
Title	Type	Part	Sub Part	Section	Sub Division	Paragraph	Sub Paragraph	Clause	Sub Clause









New York State Department of Environmental Conservation  
Air Permit Application



DEC ID									
-	-	-	-	-	-	-	-	-	-

Section IV - Emission Unit Information

Emission Unit Description										<input type="checkbox"/> Continuation Sheet(s)	
EMISSION UNIT	1	-	0	0	E	U	1	Effluent from first soil vapor extraction blower (BL-1) Vapor Phase Granular Activated Carbon Unit. The emission point is stack COST-2			

Building					<input type="checkbox"/> Continuation Sheet(s)	
Building	Building Name			Length (ft)	Width (ft)	Orientation
03-35	Treatment Building			60	40	0

Emission Point							<input type="checkbox"/> Continuation Sheet(s)
EMISSION PT.	COST-2						
Ground Elev. (ft)	Height (ft)	Height Above Structure (ft)	Inside Diameter (in)	Exit Temp. (°F)	Cross Section		
	36	6	8	70	Length (in)	Width (in)	
Exit Velocity (FPS)	Exit Flow (ACFM)	NYTM (E) (KM)	NYTM (N) (KM)	Building	Distance to Property Line (ft)	Date of Removal	
	1,000			03-35	100'		
EMISSION PT.							
Ground Elev. (ft)	Height (ft)	Height Above Structure (ft)	Inside Diameter (in)	Exit Temp. (°F)	Cross Section		
					Length (in)	Width (in)	
Exit Velocity (FPS)	Exit Flow (ACFM)	NYTM (E) (KM)	NYTM (N) (KM)	Building	Distance to Property Line (ft)	Date of Removal	

Emission Source/Control								<input type="checkbox"/> Continuation Sheet(s)
Emission Source		Date of Construction	Date of Operation	Date of Removal	Control Type		Manufacturer's Name/Model No.	
ID	Type				Code	Description		
BL1/2	1				048	Granular Act. Carbon	Tetrasolv Filtration	
Design Capacity	Design Capacity Units			Waste Feed		Waste Type		
	Code	Description		Code	Description	Code	Description	
Emission Source		Date of Construction	Date of Operation	Date of Removal	Control Type		Manufacturer's Name/Model No.	
ID	Type				Code	Description		
Design Capacity	Design Capacity Units			Waste Feed		Waste Type		
	Code	Description		Code	Description	Code	Description	

New York State Department of Environmental Conservation  
Air Permit Application



DEC ID									
-									

Section IV - Emission Unit Information (continued)

Process Information						<input type="checkbox"/> Continuation Sheet(s)	
EMISSION UNIT 4-00EU1					PROCESS SVE		
Description							
The Soil Vapor Extraction System will consist of 12 SVE wells (6 intermediate and 6 deep), a moisture separator, and 2 soil vapor extraction blowers (BL-1 and BL-2) which both vent to a vapor phase granular activated carbon unit for treatment prior to discharge from stack 00ST2. The VGAC unit will be a 5,000 pound unit filled with Tetrasolv Virgin Carbon. The VGAC unit has been designed to operate nominally at 600 cfm, with a maximum of 1,000 cfm.							
Source Classification Code (SCC)	Total Thruput		Thruput Quantity Units				
	Quantity/Hr	Quantity/Yr	Code	Description			
<input type="checkbox"/> Confidential <input checked="" type="checkbox"/> Operating at Maximum Capacity <input type="checkbox"/> Activity with Insignificant Emissions	Operating Schedule		Building	Floor/Location			
	Hrs/Day	Days/Yr					
	24	365	03-35	Main			
Emission Source/Control Identifier(s)							
BL-1	BL-2						
EMISSION UNIT -					PROCESS		
Description							
Source Classification Code (SCC)	Total Thruput		Thruput Quantity Units				
	Quantity/Hr	Quantity/Yr	Code	Description			
<input type="checkbox"/> Confidential <input type="checkbox"/> Operating at Maximum Capacity <input type="checkbox"/> Activity with Insignificant Emissions	Operating Schedule		Building	Floor/Location			
	Hrs/Day	Days/Yr					
Emission Source/Control Identifier(s)							



New York State Department of Environmental Conservation  
Air Permit Application



DEC ID									
-	-	-	-	-	-	-	-	-	-

Section IV - Emission Unit Information (continued)

Emission Unit	Emission Point	Process	Emission Source	Emission Unit Applicable Federal Requirements										<input type="checkbox"/> Continuation Sheet(s)	
				Title	Type	Part	Sub Part	Section	Sub Division	Parag.	Sub Parag.	Clause	Sub Clause		
-															
-															
-															
-															

Emission Unit	Emission Point	Process	Emission Source	Emission Unit State Only Requirements										<input type="checkbox"/> Continuation Sheet(s)	
				Title	Type	Part	Sub Part	Section	Sub Division	Parag.	Sub Parag.	Clause	Sub Clause		
-															
-															
-															
-															

Emission Unit Compliance Certification										<input type="checkbox"/> Continuation Sheet(s)
Rule Citation										
Title	Type	Part	Sub Part	Section	Sub Division	Paragraph	Sub Paragraph	Clause	Sub Clause	
G	NYCRR	212	-							
<input type="checkbox"/> Applicable Federal Requirement			<input type="checkbox"/> State Only Requirement			<input type="checkbox"/> Capping				
Emission Unit	Emission Point	Process	Emission Source	CAS No.			Contaminant Name			
1-00EU1	00ST3	SVE		00079-01-6			Trichloroethylene			
Monitoring Information										
<input type="checkbox"/> Continuous Emission Monitoring <input checked="" type="checkbox"/> Intermittent Emission Testing <input type="checkbox"/> Ambient Air Monitoring					<input type="checkbox"/> Monitoring of Process or Control Device Parameters as Surrogate <input type="checkbox"/> Work Practice Involving Specific Operations <input type="checkbox"/> Record Keeping/Maintenance Procedures					
Description										
Monthly grab samples analyzed for VOCs from the VGAC unit influent and effluent										
Work Practice		Process Material				Reference Test Method				
Type	Code	Description								
		Parameter				Manufacturer Name/Model No.				
Code		Description								
23		Concentration								
Limit			Limit Units							
Upper		Lower		Code	Description					
36,000				255	micrograms per cubic meter					
Averaging Method			Monitoring Frequency			Reporting Requirements				
Code	Description		Code	Description		Code	Description			
01	Instantaneous		05	Monthly		10	Upon Request			

New York State Department of Environmental Conservation  
Air Permit Application



DEC ID									
-	-	-	-	-	-	-	-	-	-

Section IV - Emission Unit Information (continued)

Determination of Non-Applicability (Title V Only) <i>N/A</i>										<input type="checkbox"/> Continuation Sheet(s)	
Rule Citation											
Title	Type	Part	Sub Part	Section	Sub Division	Paragraph	Sub Paragraph	Clause	Sub Clause		
Emission Unit		Emission Point		Process	Emission Source		<input type="checkbox"/> Applicable Federal Requirement <input type="checkbox"/> State Only Requirement				
Description											
Rule Citation											
Title	Type	Part	Sub Part	Section	Sub Division	Paragraph	Sub Paragraph	Clause	Sub Clause		
Emission Unit		Emission Point		Process	Emission Source		<input type="checkbox"/> Applicable Federal Requirement <input type="checkbox"/> State Only Requirement				
Description											
Process Emissions Summary										<input checked="" type="checkbox"/> Continuation Sheet(s)	
EMISSION UNIT		1-00EU1					PROCESS		SVE		
CAS No.	Contaminant Name			% Thruput	% Capture	% Control	ERP (lbs/hr)	ERP How Determined			
00071-55-6	1,1,1-Trichloroethane					80	0.34	02			
PTE			Standard Units	PTE How Determined		Actual					
(lbs/hr)	(lbs/yr)	(standard units)				(lbs/hr)	(lbs/yr)				
0.07	591			02							
EMISSION UNIT		1-00EU1					PROCESS		SVE		
CAS No.	Contaminant Name			% Thruput	% Capture	% Control	ERP (lbs/hr)	ERP How Determined			
00127-18-4	Tetrachloroethylene					80	0.00	02			
PTE			Standard Units	PTE How Determined		Actual					
(lbs/hr)	(lbs/yr)	(standard units)				(lbs/hr)	(lbs/yr)				
<del>0.00</del> 8RT	8			02							
EMISSION UNIT		1-00EU1					PROCESS		SVE		
CAS No.	Contaminant Name			% Thruput	% Capture	% Control	ERP (lbs/hr)	ERP How Determined			
00079-01-6	Trichloroethylene					80	0.67	02			
PTE			Standard Units	PTE How Determined		Actual					
(lbs/hr)	(lbs/yr)	(standard units)				(lbs/hr)	(lbs/yr)				
0.13	1,181			02							



New York State Department of Environmental Conservation  
Air Permit Application



DEC ID									
-									

Section IV - Emission Unit Information (continued)

EMISSION UNIT		Emission Unit Emissions Summary				<input checked="" type="checkbox"/> Continuation Sheet(s)
i-00EU1						
CAS No.		Contaminant Name				
00075-34-3		1,1-Dichloroethane				
ERP (lbs/yr)	PTE Emissions			Actual		
	(lbs/hr)	(lbs/yr)	(lbs/hr)	(lbs/yr)		
	BRT	11				
CAS No.		Contaminant Name				
00075-35-4		1,1-Dichloroethylene (Vinylidene Chloride)				
ERP (lbs/yr)	PTE Emissions			Actual		
	(lbs/hr)	(lbs/yr)	(lbs/hr)	(lbs/yr)		
	BRT	16				
CAS No.		Contaminant Name				
00540-59-0		cis-1,2-Dichloroethane				
ERP (lbs/yr)	PTE Emissions			Actual		
	(lbs/hr)	(lbs/yr)	(lbs/hr)	(lbs/yr)		
	BRT	5				
CAS No.		Contaminant Name				
00107-06-2		1,2-Dichloroethane				
ERP (lbs/yr)	PTE Emissions			Actual		
	(lbs/hr)	(lbs/yr)	(lbs/hr)	(lbs/yr)		
	BRT	BRT				

Compliance Plan N/A												<input type="checkbox"/> Continuation Sheet(s)
For any emission units which are <u>not in compliance</u> at the time of permit application, the applicant shall complete the following												
Consent Order		Certified progress reports are to be submitted every 6 months beginning ___ / ___ / ___										
Emission Unit	Process	Emission Source	Applicable Federal Requirement									
			Title	Type	Part	Sub Part	Section	Sub Division	Parag.	Sub Parag.	Clause	Sub Clause
Remedial Measure / Intermediate Milestones										R/I	Date Scheduled	

New York State Department of Environmental Conservation  
Air Permit Application



DEC ID									
-	-	-	-	-	-	-	-	-	-

Section IV - Emission Unit Information

EMISSION UNIT		Emission Unit Emissions Summary (continuation)			
1-00E41					
CAS No.		Contaminant Name			
00156-60-5		trans-1,2-Dichloroethene			
ERP (lbs/yr)	PTE Emissions		Actual		
	(lbs/hr)	(lbs/yr)	(lbs/hr)	(lbs/yr)	
BRT		BRT			
CAS No.		Contaminant Name			
00075-01-4		Vinyl Chloride			
ERP (lbs/yr)	PTE Emissions		Actual		
	(lbs/hr)	(lbs/yr)	(lbs/hr)	(lbs/yr)	
BRT		BRT			
CAS No.		Contaminant Name			
-					
ERP (lbs/yr)	PTE Emissions		Actual		
	(lbs/hr)	(lbs/yr)	(lbs/hr)	(lbs/yr)	
CAS No.		Contaminant Name			
-					
ERP (lbs/yr)	PTE Emissions		Actual		
	(lbs/hr)	(lbs/yr)	(lbs/hr)	(lbs/yr)	
CAS No.		Contaminant Name			
-					
ERP (lbs/yr)	PTE Emissions		Actual		
	(lbs/hr)	(lbs/yr)	(lbs/hr)	(lbs/yr)	
CAS No.		Contaminant Name			
-					
ERP (lbs/yr)	PTE Emissions		Actual		
	(lbs/hr)	(lbs/yr)	(lbs/hr)	(lbs/yr)	
CAS No.		Contaminant Name			
-					
ERP (lbs/yr)	PTE Emissions		Actual		
	(lbs/hr)	(lbs/yr)	(lbs/hr)	(lbs/yr)	
CAS No.		Contaminant Name			
-					
ERP (lbs/yr)	PTE Emissions		Actual		
	(lbs/hr)	(lbs/yr)	(lbs/hr)	(lbs/yr)	
CAS No.		Contaminant Name			
-					
ERP (lbs/yr)	PTE Emissions		Actual		
	(lbs/hr)	(lbs/yr)	(lbs/hr)	(lbs/yr)	



**New York State Department of Environmental Conservation  
Air Permit Application**



DEC ID									
-									

**Section IV - Emission Unit Information (continued)**

Request for Emission Reduction Credits						<input type="checkbox"/> Continuation Sheet(s)			
EMISSION UNIT -									
Emission Reduction Description									
Contaminant Emission Reduction Data									
Baseline Period ____ / ____ / ____ to ____ / ____ / ____						Reduction			
						Date		Method	
						/ /			
CAS No.		Contaminant Name				ERC (lbs/yr)			
						Netting		Offset	
-									
-									
-									
Facility to Use Future Reduction									
Name						APPLICATION ID			
						- / -			
Location Address									
<input type="checkbox"/> City / <input type="checkbox"/> Town / <input type="checkbox"/> Village						State		Zip	

Use of Emission Reduction Credits						<input type="checkbox"/> Continuation Sheet(s)			
EMISSION UNIT -									
Proposed Project Description									
Contaminant Emissions Increase Data									
CAS No.		Contaminant Name				PEP (lbs/yr)			
-									
Statement of Compliance									
<input type="checkbox"/> All facilities under the ownership of this "ownership/firm" are operating in compliance with all applicable requirements and state regulations including any compliance certification requirements under Section 114(a)(3) of the Clean Air Act Amendments of 1990, or are meeting the schedule of a consent order.									
Source of Emission Reduction Credit - Facility									
Name						PERMIT ID			
						- / -			
Location Address									
<input type="checkbox"/> City / <input type="checkbox"/> Town / <input type="checkbox"/> Village						State		Zip	
Emission Unit	CAS No.	Contaminant Name			ERC (lbs/yr)				
					Netting		Offset		
-	-								
-	-								
-	-								





DEC ID									
-									

Supporting Documentation


- P.E. Certification (form attached)
- List of Exempt Activities (form attached)
- Plot Plan
- Methods Used to Determine Compliance (form attached)
- Calculations
- Air Quality Model ( \_\_\_\_ / \_\_\_\_ / \_\_\_\_ )
- Confidentiality Justification
- Ambient Air Monitoring Plan ( \_\_\_\_ / \_\_\_\_ / \_\_\_\_ )
- Stack Test Protocols/Reports ( \_\_\_\_ / \_\_\_\_ / \_\_\_\_ )
- Continuous Emissions Monitoring Plans/QA/QC ( \_\_\_\_ / \_\_\_\_ / \_\_\_\_ )
- MACT Demonstration ( \_\_\_\_ / \_\_\_\_ / \_\_\_\_ )
- Operational Flexibility: Description of Alternative Operating Scenarios and Protocols
- Title IV: Application/Registration
- ERC Quantification (form attached)
- Use of ERC(s) (form attached)
- Baseline Period Demonstration
- Analysis of Contemporaneous Emission Increase/Decrease
- LAER Demonstration ( \_\_\_\_ / \_\_\_\_ / \_\_\_\_ )
- BACT Demonstration ( \_\_\_\_ / \_\_\_\_ / \_\_\_\_ )
- Other Document(s): \_\_\_\_\_ ( \_\_\_\_ / \_\_\_\_ / \_\_\_\_ )
- \_\_\_\_\_ ( \_\_\_\_ / \_\_\_\_ / \_\_\_\_ )
- \_\_\_\_\_ ( \_\_\_\_ / \_\_\_\_ / \_\_\_\_ )
- \_\_\_\_\_ ( \_\_\_\_ / \_\_\_\_ / \_\_\_\_ )
- \_\_\_\_\_ ( \_\_\_\_ / \_\_\_\_ / \_\_\_\_ )
- \_\_\_\_\_ ( \_\_\_\_ / \_\_\_\_ / \_\_\_\_ )
- \_\_\_\_\_ ( \_\_\_\_ / \_\_\_\_ / \_\_\_\_ )
- \_\_\_\_\_ ( \_\_\_\_ / \_\_\_\_ / \_\_\_\_ )
- \_\_\_\_\_ ( \_\_\_\_ / \_\_\_\_ / \_\_\_\_ )
- \_\_\_\_\_ ( \_\_\_\_ / \_\_\_\_ / \_\_\_\_ )
- \_\_\_\_\_ ( \_\_\_\_ / \_\_\_\_ / \_\_\_\_ )
- \_\_\_\_\_ ( \_\_\_\_ / \_\_\_\_ / \_\_\_\_ )
- \_\_\_\_\_ ( \_\_\_\_ / \_\_\_\_ / \_\_\_\_ )
- \_\_\_\_\_ ( \_\_\_\_ / \_\_\_\_ / \_\_\_\_ )

## **APPENDIX B**


### **VAPOR CONCENTRATION TREND GRAPHS – SVEWs**

Soil Vapor Extraction Containment System  
Site 1, Former Drum Marshalling Yard  
Naval Weapons Industrial Reserve Plant - Bethpage, NY  
Vapor Concentration Trends of Select and Total VOCs  
SVEWs


**COMBINED INFLUENT**




Soil Vapor Extraction Containment System  
Site 1, Former Drum Marshalling Yard  
Naval Weapons Industrial Reserve Plant - Bethpage, NY  
Concentration Trends of Select VOCs  
SVEWs  
**SV-101I**




Soil Vapor Extraction Containment System  
Site 1, Former Drum Marshalling Yard  
Naval Weapons Industrial Reserve Plant - Bethpage, NY  
Concentration Trends of Select VOCs  
SVEWs  
SV-101D




**Soil Vapor Extraction Containment System**  
**Site 1, Former Drum Marshalling Yard**  
**Naval Weapons Industrial Reserve Plant - Bethpage, NY**  
**Concentration Trends of Select VOCs**  
**SVEWs**  
**SV-101D (smaller scale)**



Soil Vapor Extraction Containment System  
Site 1, Former Drum Marshalling Yard  
Naval Weapons Industrial Reserve Plant - Bethpage, NY  
Concentration Trends of Select VOCs  
SVEWs  
SV102I




**Soil Vapor Extraction Containment System**  
**Site 1, Former Drum Marshalling Yard**  
**Naval Weapons Industrial Reserve Plant - Bethpage, NY**  
**Concentration Trends of Select VOCs**  
**SVEs**  
**SV-102D**







Soil Vapor Extraction Containment System  
Site 1, Former Drum Marshalling Yard  
Naval Weapons Industrial Reserve Plant - Bethpage, NY  
Concentration Trends of Select VOCs  
SVEWs  
SV-103I




**Soil Vapor Extraction Containment System**  
**Site 1, Former Drum Marshalling Yard**  
**Naval Weapons Industrial Reserve Plant - Bethpage, NY**  
**Concentration Trends of Select VOCs**  
**SVEWs**  
**SV103D**




**Soil Vapor Extraction Containment System**  
**Site 1, Former Drum Marshalling Yard**  
**Naval Weapons Industrial Reserve Plant - Bethpage, NY**  
**Concentration Trends of Select VOCs**  
**SVEWs**  
**SV104I**




Soil Vapor Extraction Containment System  
Site 1, Former Drum Marshalling Yard  
Naval Weapons Industrial Reserve Plant - Bethpage, NY  
Concentration Trends of Select VOCs  
SVEWs  
SV-104D




**Soil Vapor Extraction Containment System**  
**Site 1, Former Drum Marshalling Yard**  
**Naval Weapons Industrial Reserve Plant - Bethpage, NY**  
**Concentration Trends of Select VOCs**  
**SVEWs**  
**SV-105I**




Soil Vapor Extraction Containment System  
Site 1, Former Drum Marshalling Yard  
Naval Weapons Industrial Reserve Plant - Bethpage, NY  
Concentration Trends of Select VOCs  
SVEWs  
SV-105D



**Soil Vapor Extraction Containment System**  
**Site 1, Former Drum Marshalling Yard**  
**Naval Weapons Industrial Reserve Plant - Bethpage, NY**  
**Concentration Trends of Select VOCs**  
**SVEWs**  
**SV-106I**



**Soil Vapor Extraction Containment System**  
**Site 1, Former Drum Marshalling Yard**  
**Naval Weapons Industrial Reserve Plant - Bethpage, NY**  
**Concentration Trends of Select VOCs**  
**SVEWs**  
**SV-106D**





**Soil Vapor Extraction Containment System**  
**Site 1, Former Drum Marshalling Yard**  
**Naval Weapons Industrial Reserve Plant - Bethpage, NY**  
**Concentration Trends of Select VOCs**  
**SVEWs**  
**SV-106D (smaller scale)**

