

Prepared for:

Photocircuits Corporation
31 Sea Cliff Avenue
Glen Cove, New York 11542

Prepared by:

McLaren/Hart, Inc.
28 Madison Avenue Extension
Albany, New York 12203

September 28, 1998

**REMEDIAL INVESTIGATION REPORT
31 AND 45A SEA CLIFF AVENUE SITES
PHOTOCIRCUITS CORPORATION
GLEN COVE, NEW YORK**

Pall Letter Bullets - proposed general answers

Bullet One - lack of downgradient potentiometric and water quality data: Based on the results of the pilot study and the data contained in the 2nd quarter 2003 report, we believe that hydraulic control is being achieved in the area of the hydraulic control wells. Collection of potentiometric and water quality downgradient would also be desirable, and perhaps it could be arranged with Pall's cooperation. Note that it may be some time before groundwater quality downgradient of the Hydraulic Control system improves.

Bullet Two - lack of cross gradient data: Collection of cross - gradient data to the east is inhibited by the arterial highway, and to the west by the photocircuits main building in the main contaminant area. Data further west could be collected, however, it is unlikely that the effect of the hydraulic control system could be discerned at great distance. I am not sure about what Pall means by the phrase "the flow pathways that have been confirmed under the Arterial Highway and west of the hydraulic control network". What flow pathways have been confirmed and by whom?

Bullet Three - Lack of tracer studies - we informally explored this possibility with Photocircuits before approving the system. In a sense, there are already tracers available (VOCs). This would require the cooperation of Pall. Also, it would be good to know if Pall is getting Soybean oil on their property..... Usually, the Department has not required tracer studies in similar situations.

Bullet Four - Only four wells instead of the originally designed five: The number of wells was decreased to four due to difficulties in placement encountered in the field - see 2nd quarter 2003 report. The pilot test and design documents indicate that 4 wells should be sufficient, as is confirmed by the results indicated in the above report.

Bullet 5 - less than the 3 gpm pumping rate: 2nd quarter 2003 report shows hydraulic control achieved by 1gpm per well. Actually, design document projects 2 gpm, not 3. A low pumping rate may be used because, despite the high hydraulic conductivity, the gradient that must be overcome is fairly low.

Bullet 6 - System only intended to capture from MW-7 source area: This is the only known major source area on the site. See potentiometric maps: there may be longer groundwater routes to the west that bring contamination to the Pall site - probably deep, because of the longer route. As far as I can tell, Pall and Photocircuits monitoring data confirms that the contamination entering to the west is deep.

Bullet 7 - Photocircuits maps in 3rd quarter 2003 report indicate that contamination is not being captured to the East near the arterial highway: Pall's contour maps indicate that the flow direction in this area is more NNW than N, so the contamination is probably not getting around the hydraulic control system. Also, consider the local topography (sloping up to east).

Bullet 8 - Lowered pumping rate - rate lowered due to mechanical difficulties and due to soybean oil presence. As noted above, 2nd quarter report indicates sufficiency of current rate

Bullet 9 - DOH concerns: Have discussed with R. Mitchell. We agree with the DOH that eventually downgradient samples should be acquired

Bullet 10 - Draft Pall sampling results - we await our copy with interest

Bullet 11 - We await our copy of your results with interest

Bullet 12 - Static water heights - resistivity images - etc: Perhaps Pall should outline their suggestion about resistivity imaging, additional injections (tracers) etc. This seems to repeat previous items.

TABLE OF CONTENTS

<u>Section</u>	<u>Page</u>
1.0 INTRODUCTION.....	1
2.0 SITE BACKGROUND.....	2
2.1 Site Location.....	2
2.2 Site Geology	2
2.3 Site Hydrogeology	3
2.4 Preliminary Site Investigation of August 1996	3
3.0 FIELD SAMPLING METHODOLOGIES	6
3.1 Soil Sampling.....	6
3.2 Groundwater Grab Sampling.....	7
3.3 Monitoring Well Installation.....	8
3.4 Monitoring Well Sampling.....	8
3.5 Slug Testing.....	9
4.0 RESULTS AND CONCLUSIONS	12
4.1 Soil Sampling and Analysis.....	12
4.1.1 Photocircuits Site	12
4.1.2 45A Site	12
4.2 Groundwater Quality.....	13
4.2.1 Nature of contamination	13
4.2.2 Photocircuits Site	13
4.2.3 45A Site	15
4.3 Geotechnical Testing.....	17
4.4 Conclusions.....	17
5.0 INTERIM REMEDIAL MEASURE.....	18
6.0 REFERENCES.....	20

FIGURES

- 2-1 Site Plan and Monitoring Well Locations
- 2-2 Groundwater Contour Map – Shallow Wells, May 13, 1998
- 2-3 Groundwater Contour Map – Deep Wells, May 13, 1998
- 2-4 Soil and Groundwater Grab Sampling Results – 45A Site
- 2-5 Soil and Groundwater Grab Sampling Results – Photocircuits Site
- 2-6 Monitoring Well Sampling Results, May, 1998

TABLES

- 2-1 Analytical Summary of Volatile Organic Compounds in Soils
- 2-2 Summary of Soil and Groundwater Grab Analytical Results Exceeding NYSDEC Criteria
- 2-3 Analytical Summary of Volatile Organic Compounds in Groundwater (Grab Samples)
- 2-4 Water Level Measurements/Monitoring Well Construction Details
- 2-5 Groundwater Sampling Field-Measured Parameters
- 2-6 Analytical Summary of Volatile Organic Compounds – Monitoring Well Sampling Event of May 13-15, 1998
- 3-1 Summary of Falling/Rising Head Slug Testing Data and Results

APPENDICES

- A Soil Boring Logs/Well Log
- B Laboratory Analytical Data Package (provided under separate cover)
- C Geotechnical Testing Results
- D Slug Test Raw Data and Calculations

1.0 INTRODUCTION

This Remedial Investigation (RI) Report presents the results of the RI activities conducted on behalf of Photocircuits Corporation (Photocircuits) at the properties located at 45A Sea Cliff Avenue ("45A Site") and 31 Sea Cliff Avenue ("Photocircuits Site"), Glen Cove, New York. The RI activities described in this Report have been conducted in satisfaction of the requirements set forth in the New York Department of Environmental Conservation (NYSDEC) Orders on Consent (Nos. W1-0771-96-07 and W1-0713-94-12, and in accordance with the scope of work and procedures presented in the NYSDEC-approved Remedial Investigation / Interim Remedial Measure (RI/IRM) Work Plan dated March 25, 1997, as well as NYSDEC Technical and Administrative Guidance Memoranda (TAGMs) and other applicable guidance.

The investigation results presented in this RI Report supplement those presented in the Preliminary Site Investigation (PSI) Report of November 15, 1996 and are intended to serve as a basis for selection and design of an Interim Remedial Measure (IRM). A preliminary conceptual description of the proposed IRM is provided in this Report.

The scope of work of the activities described in this Report consisted of the following tasks:

- Soil and groundwater sampling using a Geoprobe to further delineate impacts detected during the Preliminary Site Investigation (PSI) in the vicinity of the former solvent AST located in the Building 7 area of the 45A Site
- Soil and groundwater sampling using a Geoprobe to further delineate impacts detected during the PSI in the Acid/Base/Solvent Tank Farm area of the Photocircuits Site
- Installation of one additional shallow monitoring well on the 45A Site
- Sampling of monitoring wells on both sites
- Slug testing of monitoring wells on both sites

2.0 SITE BACKGROUND

2.1 SITE LOCATION

The Photocircuits Site and the 45A Site are located on the south side of Sea Cliff Avenue in Glen Cove, New York. The 45A Site was owned by Pass & Seymour Inc. and was purchased by Alpha Forty-Five L.L.C in April 1996. Photocircuits currently leases the 45A Site in connection with its manufacturing operations. The Photocircuits Site is bordered by Pall Corporation to the north, Cedar Swamp Road to the east, the Glen Head Country Club to the south, and the former Pass & Seymour site to the west. The 45A Site is bordered by the Associated Drapery site to the north, Pall Corp. to the northeast, and Photocircuits to the east, south, and west. A Site Plan showing details of both the 31 and 45A Sea Cliff Avenue Sites is provided in Figure 2-1.

2.2 SITE GEOLOGY

The Photocircuits and 45A sites are underlain by the following sequences, in descending order: the Upper Glacial Aquifer, the Port Washington confining unit, the Port Washington aquifer, the Lloyd Aquifer, and bedrock. The Upper Glacial aquifer is composed of stratified beds of fine to coarse sand and gravel with some interbedded lenses of silt and clay and extends to a depth of approximately 200 feet below the sites. The Port Washington confining unit, which extends approximately 100 feet below the Upper Glacial aquifer, consists of silt and clay with some interbedded sand and gravel lenses. The Port Washington aquifer is composed of sand and gravel with variable amounts of interbedded clay and silt. The Port Washington aquifer is approximately 50 feet thick. The Lloyd aquifer, which is approximately 200 feet thick, consists of discontinuous layers of gravel, sand, sandy clay, silt, and clay. It roughly parallels the crystalline bedrock, which is present at a depth of approximately 550 feet below the site (Geraghty and Miller, 1989).

2.3 SITE HYDROGEOLOGY

As discussed above, the uppermost hydrogeologic unit beneath the Photocircuits and 45A Sea Cliff Sites is the Upper Glacial aquifer. Depth to water measurements collected during groundwater sampling by McLaren/Hart indicate that groundwater is present at 4 to 10 feet below ground surface beneath the Photocircuits site and at 8 to 25 feet beneath the 45A Site (McLaren/Hart Preliminary Site Investigation Report, November 11, 1996). Groundwater was encountered in soil borings drilled on the eastern portion of the 45A Site at 23 to 25 feet below grade. Groundwater level measurements collected from the deep monitoring wells at the Photocircuits site during previous investigations indicate that groundwater flow is to the northwest. Shallow groundwater flow has also been shown to be toward the northwest.

Water level measurements were collected from all wells on both sites (except MW-2) during the May, 1998 groundwater sampling event. Groundwater contour maps for the shallow and deep wells are provided in Figures 2-2 and 2-3, respectively. As indicated by the contour map, the predominant direction of groundwater flow is consistent with previous observations, that is, primarily to the northwest.

2.4 PRELIMINARY SITE INVESTIGATION OF AUGUST 1996

A preliminary site investigation was conducted in August 1996 with the following objectives:

- Confirm the results of the earlier soil sampling on the 31 Site in the Acid/Base/Solvent tank farm area
- Delineate detections of VOCs in and around the Acid/Base/Solvent tank farm
- Determine the nature and extent of soil VOC impacts on the 45A Site
- Determine groundwater flow direction
- Reevaluate groundwater quality and confirm previous groundwater sampling results

August 1996 Soil Sampling Results

Analytical results from the seventeen soil samples collected on the Photocircuits Site indicated the presence of volatile organic compounds (VOCs) in soils at five areas of review (AORs), with two of which, the drum storage area and the acid/base/solvent tank farm, contain VOCs at concentrations in excess of the NYSDEC Soil Cleanup Objectives contained in Technical and Administrative Guidance Memorandum (TAGM) HWR-94-4046.

On the 45A Site, soil samples from three of the four investigated AORs indicated the presence of VOCs. One soil sample, GP-30, near the former location of the aboveground PCE storage tank pad (since removed), contained VOC concentrations in excess of the NYSDEC Soil Cleanup Objective for tetrachloroethene (PCE).

August 1996 Ground Water Sampling Results

During the August 1996 PSI, VOCs were detected in four of the eleven monitoring wells on the Photocircuits Site. The groundwater sample from MW-7 in the vicinity of the acid/base/solvent tank farm and the drum storage area, indicated the presence of the following compounds at concentrations in excess of 6NYCRR Part 703.5 standards for Class GA waters: vinyl chloride, chloroethane, 1,1-dichloroethene, methylene chloride, 1,1-dichloroethane, 1,2-dichloroethane, 2-butanone, 1,1,1-trichloroethane, trichloroethene (TCE), toluene, and PCE.

The sample from MW-10, a deep well on the northeast corner of the Photocircuits property, contained the following compounds at concentrations exceeding the Part 703.5 standards: 1,1-dichloroethene, 1,1-dichloroethane, 1,1,1-trichloroethane, TCE, and PCE.

The groundwater sample from NC-Well, a shallow well located adjacent to the north edge of the Photocircuits property along Sea Cliff Avenue, contained 1,1-dichloroethane and 1,1,1-trichloroethane in concentrations in excess of Part 703.5 standards.

Groundwater grab sample GW-GP-10 was collected from a temporary well point on the east side of the Butler No. 2 Building and indicated concentrations of toluene, m, p and o-xylene in excess of the NYSDEC standards.

On the 45A Site, groundwater samples from two of the three shallow monitoring wells indicated VOCs above the laboratory detection limits. The sample from well MW-1S, which is located southeast of the main building, indicated PCE at a concentration exceeding the part 703.5 standard. The sample from well MW-3S, located north of the main building, indicated TCE and PCE at concentrations in excess of the part 703.5 standards.

3.0 FIELD SAMPLING METHODOLOGIES

3.1 SOIL SAMPLING

Soil sampling was conducted at the 45A Site in the vicinity of the former above ground solvent storage tank. On the Photocircuits site, soil sampling was conducted in the vicinity of the Acid/Base/Solvent Tank Farm. Soil sampling was conducted using a Geoprobe direct-push sampler. Soil samples were collected continuously from ground surface to the depth at which ground water was encountered. Soil samples were screened with a PID (OVM 580B), and samples were selected for laboratory analysis based on the screening results. Soil samples were obtained by driving a decontaminated four foot long, acetate-lined, stainless steel sampling tube to the desired sampling depth. The sampling tube was then retrieved at the surface and the acetate liner split to allow PID screening. Soil was removed from the acetate liner at selected six-inch sampling intervals and transferred to laboratory containers. Soil borings were logged for lithology and moisture content. Lithologic information as well as PID readings are provided on boring logs included in Appendix A.

Soil samples were analyzed using SW-846 Method 8260, including a 15-compound library search. Soil samples were preserved on ice until delivered to the laboratory. Analytical work was performed by Envirotech Research of Edison, New Jersey, a NY-certified laboratory. Appropriate sample chain-of-custody procedures were followed for sample handling. Analytical results for soils are summarized in Tables 2-1 and 2-2. Laboratory analytical data packages are provided in Appendix B.

Geotechnical Testing

Six soil samples were collected for geotechnical testing. Four samples from the 45A Site and two samples from the Photocircuits Site were collected. The objective of the geotechnical sampling was to provide detailed data on the physical characteristics of subsurface soils for use

in the selection and design of the IRM. Testing was performed by Paulus, Sokolowski and Sartor, Inc., of Warren, New Jersey, and consisted of the following tests:

- Grain size distribution
- Moisture content
- Density
- Hydraulic Conductivity
- Total Organic Carbon (TOC) by loss on ignition method

Results of geotechnical testing are provided in Appendix C.

3.2 GROUNDWATER GRAB SAMPLING

Groundwater grab sampling was conducted with the objective of delineating the lateral extent of VOCs detected in the water table aquifer during the PSI. Delineation on the 45A Site was focused primarily on the PCE previously detected in the vicinity of the above-ground solvent storage tank. On the Photocircuits site groundwater grab sampling activities were focused on completing delineation of VOC contamination in the vicinity of the Acid/Base/Solvent tank farm, monitoring well MW-7, and a portion of the adjacent parking lot. Groundwater grab sampling locations for the 45A Site are shown in Figure 2-4. Groundwater grab sampling locations for the Photocircuits Site are shown in Figure 2-5. Analytical results for groundwater grab sampling are summarized in Tables 2-2 and 2-3.

A Geoprobe with a temporary well point sampler was used to obtain groundwater grab samples on both sites. The samples were obtained by hydraulically driving a decontaminated, vertically slotted, two-foot long temporary well point into the first water bearing zone. Once the temporary well point was positioned in the water bearing zone, a minimum of three well point volumes were removed before sampling by either bailing with a ½-inch diameter bailer, or by pumping

using a dedicated length of polyethylene tubing and a peristaltic pump. The bailer was used where the water yield in the borehole was insufficient to allow use of the peristaltic pump.

3.3 MONITORING WELL INSTALLATION

One additional shallow monitoring well (MW-4S) was installed on the 45A Site on April 22, 1998. The new well was installed to provide confirmation of the delineation of the groundwater plume in the vicinity of Building 7 and the former above ground PCE storage tank. The well was installed by Summit Drilling Co. of Bridgewater, New Jersey, using the air rotary method. Split spoon samples were collected every two feet from 5 to 11 feet, and water was encountered at approximately 9-10 feet below grade. A drilling log of the well is provided in Appendix A. The location of the well is shown in Figure 2-1.

The well was completed to a depth of 15 feet below grade with 10 feet of four inch diameter, 0.020 inch slot PVC screen set from 5 to 15 feet. The well was developed by pumping at a rate of 1.5-2 gallons per minute (gpm). Development was concluded after approximately 55 gallons of water had been removed from the well. Visible turbidity of the discharge water was not present after approximately 40 gallons had been removed.

3.4 MONITORING WELL SAMPLING

Groundwater sampling was conducted May 13-15, 1998. Depth to water measurements were made in monitoring wells using an electronic water level indicator prior to purging. Water level measurements and monitoring well construction details are provided in Table 2-4. Each of the wells was purged prior to sampling using either a centrifugal pump or submersible pump. Purging was complete when three to five well volumes were removed from each well, or when the well became dry. Measurements of temperature, specific conductance, pH, turbidity, and dissolved oxygen were taken prior to purging, after purging, and immediately after sampling. In

several cases where wells were purged dry or recovered poorly, post-purging and post-sampling measurements were not obtained due to the lack of sufficient water in the well for measurement. Field-measured parameters are presented in Table 2-5.

Samples were collected from eleven wells on the Photocircuits Site and four wells on the 45A Site. Several wells were purged to dryness and were allowed to recharge sufficiently prior to sampling. Groundwater samples were collected using disposable Teflon bailers and new bailer cord for each well. Samples were obtained by lowering the bailer into the well until it was submerged in the water column. The bailer was then retrieved and the sample transferred to laboratory-prepared containers.

Groundwater samples were analyzed for volatile organic compounds (VOCs) by SW-846 Method 8260 plus a 15-compound library search by Envirotech Research. Chain-of-custody procedures were followed throughout sample handling. In addition to the field samples, trip blanks, field blanks, and field duplicate samples were collected for internal QA/QC purposes. Analytical results of all monitoring well samples are presented in Table 2-6 and are shown in Figure 2-6.

Analytical data was subjected to an internal QA/QC review to ensure quality and completeness. Results of the internal review did not indicate any significant deficiencies in the quality or reporting of the data by the laboratory.

3.5 SLUG TESTING

Falling and rising head slug tests were conducted on monitoring wells on site to determine a range of representative hydraulic conductivity (k) values for the sand aquifer. The slug testing procedure consists of instantaneously lowering or raising the water level in a well and measuring the change in water level over time until equilibrium is re-established. The instantaneous change

in water level was achieved by rapidly inserting a sand-filled PVC tube (slug) to displace the water level in each well. After the water level had returned to its original static level (falling head test), the slug was rapidly removed, and the rising water levels were then measured (rising head test).

Prior to each slug test, the static water level in the well was measured with an electronic water level indicator, and the bottom of the well casing was sounded to confirm the exact well depth. A pressure transducer connected to an In-Situ HERMIT data logger was then lowered into the well approximately one foot off the bottom. Initial settings were programmed on the data logger prior to beginning the test. The HERMIT was programmed for high speed early time data collection at a logarithmic schedule to measure the water level changes over time.

As the slug was rapidly submerged below the water level in the well, the data logger was simultaneously started to continuously measure the initial water level rise and subsequent decline at specified time increments. After the water level in the well had recovered to static equilibrium, the slug was rapidly withdrawn and the data logger restarted to record the rising water level. The test was terminated when the water level had risen to its initial static level. The computer program AQTESOLV (Rumbaugh and Duffield, 1989) was used to compute hydraulic conductivity values.

Slug tests were conducted on 14 monitoring wells to obtain a range of hydraulic conductivity (k) values for the water-table aquifer. The analytical results for the slug tests are summarized in Table 3-1. The raw slug test data and graphs are presented in Appendix D.

The Bouwer and Rice method was used to analyze slug test data. Rising head tests were performed on 14 wells, while falling head tests were performed on 12 of those 14 wells. Static water levels must be above the screened zone in order to obtain meaningful data from a falling head test. The water levels in MW-4S and MW-6, however, were within the screened zone. Therefore, no falling head test was performed on these two wells. The combination of both rising and falling head slug

tests conducted for these 14 wells yielded variable k values ranging from 1.862E-05 cm/s at MW-5 to 5.300E-02 cm/s at MW-1S.

Of the eight wells for which analytical results were available for both rising and falling head slug tests, seven of the eight wells had good to excellent agreement between rising head and falling head test results when comparing k values in units of cm/s. Rising and falling head results within the same order of magnitude are considered to be in good agreement. The results for the slug tests conducted in MW-2S differed by about one order of magnitude.

4.0 RESULTS AND CONCLUSIONS

4.1 SOIL SAMPLING AND ANALYSIS

4.1.1 Photocircuits Site

Soil samples were collected at six locations on the Photocircuits site (31-SB-33, 34,35,36, and 37); soil sampling locations are shown on Figure 2-5, and analytical results are presented in Tables 2-1 and 2-2. TVOC concentrations ranged from non-detectable to 48 ug/kg, with all but two of the borings having TVOC concentrations of less than 10 ug/kg. PCE and TCE were the VOCs most frequently detected. NYSDEC soil cleanup objectives (TAGM 4046) were not exceeded in the soil samples collected from the Photocircuits site.

4.1.2 45A Site

Soil borings were advanced at three locations within Building 7 on the 45A Sea Cliff Avenue site, as shown on Figure 2-4. Two soil samples were collected from each borings SB-31 and -32, and three soil samples were collected from boring SB-33; analytical results are provided in Tables 2-1 and 2-2. Only the soil sample from the 12-16 ft depth in boring SB-33 contained a contaminant in excess of NYSDEC soil cleanup objectives (2,500 ug/kg of PCE, as compared to the NYSDEC cleanup objective of 1,400 ug/kg).

Photoionization (PID) readings from the screening of soil samples collected from the sampled depths in borings SB-31, -32, and -33 ranged from 100-200 ppm to 2,166 ppm. While the PID screening is only semi-quantitative, it suggests that there is substantially greater PCE present in the unsaturated zone beneath Building 7 than is detected in the soil samples, and that the PCE is largely present as soil vapor rather than being adsorbed to soil solids.

4.2 GROUNDWATER QUALITY

4.2.1 Nature of Contamination

The list of parameters for analysis of soil and groundwater samples was selected based on the results of previous studies at the site. The contaminants of concern at both the Photocircuits site and the 45A Site are volatile organic compounds (VOCs). More specifically, the majority of the VOCs detected are chlorinated hydrocarbons. Of these compounds, three are common solvents: trichloroethene, tetrachloroethene, and 1,1,1-trichloroethane. The other chlorinated hydrocarbons which were detected are likely the result of biologic degradation of the three solvent compounds, as they do not have appreciable industrial usage and several studies have shown that chlorinated hydrocarbons can undergo microbially-mediated dehalogenation reactions in groundwater under anaerobic (absence of oxygen) conditions, as follows:

tetrachloroethene $\Rightarrow$ trichloroethene $\Rightarrow$ dichloroethene isomers $\Rightarrow$ vinyl chloride $\Rightarrow$

1,1,1-trichloroethane $\Rightarrow$ 1,1-dichloroethane $\Rightarrow$ chloroethane

Both vinyl chloride and chloroethane are subject to degradation (mineralization) by aerobic (presence of oxygen) pathways (Norris, et al, 1994; Weidemeier, et al, 1996). Natural attenuation of VOC constituents is further discussed below in Section 4.2.2.

4.2.2 Photocircuits Site

Analytical results for groundwater grab samples collected on the Photocircuits site (GW-1, 4, 7, 9, 10, 11, 12 and 13) are presented in Tables 2-2 and 2-3, and the analytical results for samples collected from monitoring wells on the Photocircuits property are presented in Table 2-6.

Historic analytical results for samples collected from monitoring wells on the Photocircuits property were previously presented in the PSI Report of November 15, 1996.

Groundwater quality at the northern boundary of the property (along Sea Cliff Avenue) is defined by two clusters of monitoring wells: MW-3, -8 and the Nassau County Well (NC-Well); and MW-9, -10 and -11. Well depths and construction details for each of these wells are provided in Table 2-4. Total volatile organic compound (TVOC) concentration for MW-3, -8 and NC-Well ranged from 1.4 to 16 ug/L, with the greatest individual VOC detection being 5.7 ug/L of trichloroethene in MW-8 (this was also the only exceedance of state or federal drinking water standards in this monitoring well cluster). TVOC concentrations for MW-9, -10 and -11 ranged from 4.8 ug/L in MW-9 to 145 ug/L in MW-10. Exceedances of state or federal drinking water standards resulting from detection of individual VOCs were as follows: MW-9 - no exceedances, MW-10 (deep) - three exceedances, and MW-11 (deep) - one exceedance. By comparing the current groundwater results with results of previous studies, it is evident that groundwater quality at the downgradient boundary of the Photocircuits site is materially the same, or better, than previously reported both in terms of the VOCs detected and their respective concentrations.

The results of previous studies have indicated the presence of a localized area of relatively high concentrations of VOCs in the vicinity of MW-7. The analytical results for the groundwater sample collected from MW-7 are comparable to historic results for this well, both in terms of the VOCs detected and their respective concentrations. To assess the distribution of impacted groundwater in this area, groundwater grab samples were collected from selected locations, as shown on Figure 2-5; the first round of samples (GW-1, -4 and -7) were followed by a second set of samples (GW-9, -10, -11, -12, and -13). The first round of samples indicated that a relatively sharp concentration gradient exists when moving northward from MW-7 (3,400ug/L TVOC) to GW-4 (148 ug/L TVOC) to GW-7 (9.2 ug/L), and that the extent of shallow groundwater contamination decreases sharply in the vicinity of grab sample GW-7.

The results from GW-1 (8,000 ug/L TVOC) indicate that the extent of groundwater contamination to the south had not been defined, therefore requiring the collection of groundwater grab samples GW-9, -10, -11, -12, and -13. The results from the analysis of samples from GW-10, -11, -12, and -13 (TVOC concentrations of 200, 5, 2 and 4 ug/L, respectively) define the southern extent of the localized area of elevated shallow groundwater concentrations. The results from GW-9 (TVOC concentration of 1,800 ug/L) indicate that shallow groundwater contamination is present to the west of the chemical tank farm and south of the Photocircuits Main Building. Results from monitoring wells MW-4 and -5 (located southwest of the Main Building define the southwestern extent of the localized area of elevated shallow groundwater concentrations. Results from monitoring well MW-9 (located northwest of the Main Building) indicate that shallow groundwater contamination does not extend to MW-9, thus completing the northwest delineation activity

Basically the same suite of chlorinated VOCs were detected in MW-7 and the surrounding groundwater grab samples. With the exception of 6,000 ug/L of 1,1,1-trichloroethane in GW-1, the VOCs detected in the highest concentrations were degradation products (1,1-dichloroethane; dichloroethene isomers; vinyl chloride; and chloroethane). This finding suggests that natural attenuation through microbial degradation is occurring within the impacted area.

Comparison of MW-10 results from 1996 to the current 1998 sampling round indicates that the VOC concentrations remain essentially similar in 1998 to those detected in 1996.

4.2.3 45A Site

Groundwater samples were collected from the three existing monitoring wells and the new monitoring well, and groundwater grab samples were collected from seven locations. The locations of the grab sampling points are shown in Figure 2-4. Monitoring well locations are

shown in Figure 2-1. Analytical results for monitoring well samples are presented in Table 2-6, and analytical results for groundwater grab samples are presented in Table 2-3.

For the three wells located in the southern portion of the site (MW-1S, -2S and -4S), TVOC concentrations varied from 1.8 ug/L to 340 ug/L, with the predominant VOC being tetrachloroethene (also known as perchloroethylene, "perc" and PCE). Well 3S, located at the northern property boundary, had a TVOC concentration of 110 ug/L, with trichloroethene (TCE) being the dominant VOC.

Groundwater grab samples were proposed at locations in around Building 7, based on the results of the PSI. These locations were modified in the field based on findings. The highest TVOC concentrations were detected in samples collected from within the building; GW-2 and GW-3 had TVOC concentrations of 32,000 and 17,000 ug/L, respectively, with PCE being the dominant VOC. TVOC concentrations in groundwater grab samples collected around and downgradient of Building 7 ranged from less than 10 ug/l in GW-4, -5 and -6 to 130 ug/L in GW-7. Coupled with the groundwater results from the PSI, these results indicate that there is a localized area of elevated concentrations of VOCs (predominantly PCE) in the groundwater underlying Building 7. The concentration gradient from under Building 7 (GW-2 and -3) to the area immediately downgradient (GW-4, -5, -6 and -7) indicates that the contaminant mass is largely confined to the footprint of Building 7. Comparison of groundwater sampling results of wells MW-1S, 2S, and 3S from 1996 to the current results indicates an increase in the PCE concentration in well MW-1S from 47 ug/L in 1996 to 71 ug/L in 1998. Both wells MW-2S and MW-4S had sampling results within the ranges of historical data since December 1991. The Federal Maximum Contaminant Level for PCE is 5 ug/L (for drinking water).

4.3 GEOTECHNICAL TESTING

Six soil samples were submitted for geotechnical testing, including particle size distribution, moisture content, total organic carbon and permeability; the testing was conducted to aid in determining the suitability of the site for the application of soil vapor extraction technology. The results of the geotechnical testing are provided in Appendix C. The results indicate that the unsaturated zones at the Photocircuits and 45A sites are comprised of relatively coarse grained materials with low organic carbon content (0.19-0.65 %) and indicate a permeability range of 3.8×10^{-4} to 1.5×10^{-2} cm/sec. These results are consistent with field observations as well as available literature.

4.4 CONCLUSIONS

The sampling and analysis described in this report accomplish the objectives of the investigation component of the approved work plan which was to determine the nature and distribution of contamination attributable to the sites and gather sufficient information to conduct the Feasibility Study. The investigation has also provided data sufficient to confirm the suitability of the proposed IRM for the Sites.

The shaded areas shown in Figure 2-6 represent the two areas which will be the focus area for implementation of the IRM at the site. Information gathered during the implementation of the IRM will be evaluated in preparing the Feasibility Study.

5.0 INTERIM REMEDIAL MEASURE

The RI work plan discussed the observed contamination and provided an evaluation of possible remedial technologies for the application of an interim remedial measure (IRM). The findings of the RI confirmed the results of the PSI in that there are two areas of relatively concentrated contamination, one on the Photocircuits site and one on the 45A site. The RI also determined that the extent of soil and groundwater contamination associated with these impacted areas is limited to the areas shown in Figure 2-6.

The RI work plan proposed the application of soil vapor extraction coupled with air sparging as the best technology for the IRM. Results of the RI confirm the applicability of these technologies, for the following reasons:


- The unsaturated soils are suitable for the application of soil vapor extraction technology because the permeability of the soils is conducive to the necessary air flow rates for the efficient extraction of soil vapors.
- The low organic carbon measurements for the soil samples indicate that contaminants will not be highly adsorbed to soils, and can therefore be readily sparged and extracted under vacuum (the PID readings collected from the borings at Building 7 further support this point).
- The concentration gradients indicate that the contaminant mass at each site are confined to a relatively localized area; remedial efficiency tends to increase if the contamination is more localized/concentrated.



- Both areas of contamination are covered (by pavement and/or a building) which limits infiltration of precipitation (thus limiting migration) and also helps to raise the efficiency of vacuum extraction (less loss of vacuum).


6.0 REFERENCES

Norris, R.D., R.E. Hinchey, R.A. Brown, P.L. McCarty, L. Semprini, J.T. Wilson, D.H. Kampbell, M. Reinhard, E.J. Bouwer, R.C. Borden, T.M. Vogel, J.M. Thomas, and C.H. Ward. 1994. *Handbook of Bioremediation*. Boca Raton, Florida: Lewis Publishers.

Wiedemeier, T.H., J.T. Wilson, D.H. Kampbell, J.E. Hansen, and P. Haas. 1996. Technical protocol for evaluating the natural attenuation of chlorinated ethenes in groundwater. *Proceedings of the Petroleum Hydrocarbons and Organic Chemicals in Groundwater: Prevention, Detection, and Remediation Conference*, Houston, Texas, November 13-15.









Mcclaren/Hart
INC.

REV	DATE	DESCRIPTION	APP'D

PHOTOCIRCUITS CORPORATION
GLEN COVE, NEW YORK

McLAREN/HART ENVIRONMENTAL ENGINEERING CORP.
WARREN, NEW JERSEY

DRWN: J.R.F.	CHK'D: D.B.	APP'D: G.B.S.
SCALE AS SHOWN		DATE: 07/21/98

GROUNDWATER CONTOUR MAP
SHALLOW WELLS 5/13/98


FIGURE 2-2



ABBREVIATIONS

TCE = TRICHLOROETHENE
PCE = TETRACHLOROETHENE
1,1,1-TCA = 1,1,1-TRICHLOROETHANE

FORMER
PASS AND SEYMOUR
FACILITY



LEGEND

- PROPERTY LINE
- RIGHT-OF-WAY
- SAMPLING LOCATION (1996)
- ▲ GROUNDWATER GRAB SAMPLE LOCATION (1998)
- ◆ MONITORING WELL LOCATION
- SOIL SAMPLE LOCATION (1998)
- ND* NO ANALYTES DETECTED IN EXCESS OF NYSDEC CRITERIA
- NOTE: ALL RESULTS REPORTED IN PARTS PER BILLION (ppb)

FIGURE 2-4

SOIL AND GROUNDWATER
GRAB SAMPLING RESULTS (SITE 45A)

PHOTOCIRCUITS CORPORATION
GLEN COVE, NEW YORK




DRWN: J.R.F.

CHK'D: C.B.S.

SCALE: AS SHOWN

DATE: 07/28/98



LEGEND

- PROPERTY LINE
- RIGHT-OF-WAY
- SOIL SAMPLE LOCATION (1996)
- ▲ GROUNDWATER GRAB SAMPLE
- ◆ MONITORING WELL LOCATION
- SOIL SAMPLE LOCATION (1998)

ND* NO ANALYTES DETECTED IN EXCESS OF NYSDEC CRITERIA

NOTE: ALL RESULTS REPORTED IN PARTS PER BILLION (ppb)

FIGURE 2-5

SOIL AND GROUNDWATER
SAMPLING RESULTS (PHOTOCIRCUITS SITE)

PHOTOCIRCUITS CORPORATION
GLEN COVE, NEW YORK



DRWN: J.R.F.

CHK'D: C.B.S.

SCALE: AS SHOWN

DATE: 07/22/98




Table 2-1
Analytical Summary for Volatile Organic Compounds in Soil
Photocircuits Corporation
Glen Cove, New York

Sample Location	NYSDEC/USEPA	45A-SB-31	45A-SB-31	45A-SB-32	45A-SB-32	45A-SB-33	45A-SB-33
Sample Depth (ft)	Soil Cleanup	12-16	20-22	12-16	20-24	16	16-20
Sample ID	Objectives*	54859	54863	54862	54873	54866	54870
Sample Date	(ppb)	04/09/98	04/09/98	04/09/98	04/09/98	04/08/98	04/08/98
Dilution Factor		1.0	1.0	1.0	1.0	50.0	1.0

VOLATILE COMPOUNDS (ppb)

Chloromethane	NS	1.0 U	1.2 U	1.2 U	1.2 U	140 U	1.1 U
Bromomethane	NS	1.0 U	1.2 U	1.2 U	1.2 U	140 U	1.1 U
VinylChloride	200	1.0 U	1.2 U	1.2 U	1.2 U	140 U	1.1 U
Chloroethane	1900	1.0 U	1.2 U	1.2 U	1.2 U	140 U	1.1 U
MethyleneChloride	100	1.5 B	1.2 B	1.5 B	3.6 B	140 U	1.8 B
Trichlorofluoromethane	NS	1.0 U	1.2 U	1.2 U	1.2 U	140 U	1.1 U
1,1-Dichloroethene	400	1.0 U	1.2 U	1.2 U	1.2 U	140 U	1.1 U
1,1-Dichloroethane	200	1.0 U	1.2 U	1.2 U	1.2 U	140 U	1.1 U
trans-1,2-Dichloroethene	300	1.0 U	1.2 U	1.2 U	1.2 U	140 U	1.1 U
cis-1,2-Dichloroethene	NS	1.0 U	1.2 U	1.2 U	1.2 U	140 U	1.1 U
Chloroform	300	1.0 U	1.2 U	1.2 U	1.2 U	140 U	1.1 U
1,2-Dichloroethane	100	1.0 U	1.2 U	1.2 U	1.2 U	140 U	1.1 U
1,1,1-Trichloroethane	800	1.0 U	1.2 U	1.2 U	0.9 J	140 U	1.1 U
Carbon Tetrachloride	600	1.0 U	1.2 U	1.2 U	1.2 U	140 U	1.1 U
Bromodichloromethane	NS	1.0 U	1.2 U	1.2 U	1.2 U	140 U	1.1 U
1,2-Dichloropropane	NS	1.0 U	1.2 U	1.2 U	1.2 U	140 U	1.1 U
cis-1,3-Dichloropropene	NS	1.0 U	1.2 U	1.2 U	1.2 U	140 U	1.1 U
Trichloroethene	700	1.0 U	1.2 U	1.2 U	1.0 J	140 U	1.1 U
Dibromochloromethane	NS	1.0 U	1.2 U	1.2 U	1.2 U	140 U	1.1 U
1,1,2-Trichloroethane	NS	1.0 U	1.2 U	1.2 U	1.2 U	140 U	1.1 U
Benzene	60	1.0 U	1.2 U	1.2 U	1.2 U	140 U	1.1 U
trans-1,3-Dichloropropene	NS	1.0 U	1.2 U	1.2 U	1.2 U	140 U	1.1 U
2-ChloroethylVinylEther	NS	1.0 U	1.2 U	1.2 U	1.2 U	140 U	1.1 U
Bromoform	NS	1.0 U	1.2 U	1.2 U	1.2 U	140 U	1.1 U
Tetrachloroethene	1400	31	33	52	48	2500	10
1,1,2,2-Tetrachloroethane	600	1.0 U	1.2 U	1.2 U	1.2 U	140 U	1.1 U
Toluene	1500	1.7	1.1 J	22	3.9	140 U	2.2
Chlorobenzene	1700	1.0 U	1.2 U	1.2 U	1.2 U	140 U	1.1 U
Ethylbenzene	5500	1.0 U	1.2 U	1.2 U	1.2 U	140 U	1.1 U
Xylene(Total)	1200	1.0 U	1.2 U	0.6 J	1.2 U	140 U	0.6 J

Total Confident Conc. VOAs (s)	33	33	74	52	2500	12
Total Estimated Conc. VOA TICs (s)	0	8.6	0	8.3	0	7.9

NS: Not Specified

U: Analyte was not detected above the referenced reporting limit

B: Analyte was also detected in blank

J: Estimated Concentration at or below the reporting limit

JB: Sample result below the CRQL and analyte detected in associated field blank

*: Taken from NYSDEC Soil Cleanup Objectives to protect groundwater quality and USEPA recommended soil cleanup objectives. The higher of the two values is listed.

Table 2-1
Analytical Summary for Volatile Organic Compounds in Soil
Photocircuits Corporation
Glen Cove, New York

Sample Location	NYSDEC/USEPA	45A-SB-33	31-SB-34	31-SB-35	31-SB-36	31-SB-37
Sample Depth (ft)	Soil Cleanup	22-24	4	4	4	3
Sample ID	Objectives*	54871	56157	56159	56161	56162
Sample Date	(ppb)	04/08/98	04/20/98	04/20/98	04/20/98	04/20/98
Dilution Factor		1.0	1.0	1.0	1.0	1.0

VOLATILE COMPOUNDS (ppb)

Chloromethane	NS	1.2 U	1.2 U	1.1 U	1.2 U	1.1 U
Bromomethane	NS	1.2 U	1.2 U	1.1 U	1.2 U	1.1 U
VinylChloride	200	1.2 U	1.2 U	1.1 U	1.2 U	1.1 U
Chloroethane	1900	1.2 U	1.2 U	1.1 U	1.2 U	1.1 U
MethyleneChloride	100	3.1 B	1.5 B	1.2 B	1.1 JB	1.1 JB
Trichlorofluoromethane	NS	1.2 U	1.2 U	1.1 U	1.2 U	1.1 U
1,1-Dichloroethene	400	1.2 U	1.2 U	1.1 U	1.2 U	1.1 U
1,1-Dichloroethane	200	1.2 U	6.8	1.1 U	1.2 U	1.1 U
trans-1,2-Dichloroethene	300	1.2 U	1.2 U	1.1 U	1.2 U	1.1 U
cis-1,2-Dichloroethene	NS	1.2 U	2.1	1.1 U	2.2	1.1 U
Chloroform	300	1.2 U	1.2 U	1.1 U	1.2 U	1.1 U
1,2-Dichloroethane	100	1.2 U	1.2 U	1.1 U	1.2 U	1.1 U
1,1,1-Trichloroethane	800	0.8 J	3.2	1.1 U	5.8	1.1 U
CarbonTetrachloride	600	1.2 U	1.2 U	1.1 U	1.2 U	1.1 U
Bromodichloromethane	NS	1.2 U	1.2 U	1.1 U	1.2 U	1.1 U
1,2-Dichloropropane	NS	1.2 U	1.2 U	1.1 U	1.2 U	1.1 U
cis-1,3-Dichloropropene	NS	1.2 U	1.2 U	1.1 U	1.2 U	1.1 U
Trichloroethene	700	0.7 J	1.6	1.1 U	21	1.5
Dibromochloromethane	NS	1.2 U	1.2 U	1.1 U	1.2 U	1.1 U
1,1,2-Trichloroethane	NS	1.2 U	1.2 U	1.1 U	1.2 U	1.1 U
Benzene	60	1.2 U	1.2 U	1.1 U	1.2 U	1.1 U
trans-1,3-Dichloropropene	NS	1.2 U	1.2 U	1.1 U	1.2 U	1.1 U
2-ChloroethylVinylEther	NS	1.2 U	1.2 U	1.1 U	1.2 U	1.1 U
Bromoform	NS	1.2 U	1.2 U	1.1 U	1.2 U	1.1 U
Tetrachloroethene	1400	60	20	1.1 U	19	4.1
1,1,2,2-Tetrachloroethane	600	1.2 U	1.2 U	1.1 U	1.2 U	1.1 U
Toluene	1500	6.9	2.9	4.5	1.2 U	0.6 J
Chlorobenzene	1700	1.2 U	1.2 U	1.1 U	1.2 U	1.1 U
Ethylbenzene	5500	1.2 U	1.0 J	0.6 J	1.2 U	1.1 U
Xylene(Total)	1200	0.9 J	5.6	3.6	1.2 U	1.1 U

Total Confident Conc. VOAs (s)	67	42	81	48	56
Total Estimated Conc. VOA TICs (s)	10.0	7.0	81	0	0

NS: Not Specified

U: Analyte was not detected above the referenced reporting limit

B: Analyte was also detected in blank

J: Estimated Concentration at or below the reporting limit

JB: Sample result below the CRQL and analyte detected in associated field blank

*: Taken from NYSDEC Soil Cleanup Objectives to protect groundwater quality and USEPA recommended soil cleanup objectives. The higher of the two values is listed.

Table 2-1
Analytical Summary for Volatile Organic Compounds in Soil
Photocircuits Corporation
Glen Cove, New York

Sample Location	YSDEC/USEP	31-SB-5	31-SB-6
Sample Depth (ft)	Soil Cleanup	4	3
Sample ID	Objectives*	56165	56168
Sample Date	(ppb)	04/20/98	04/20/98
Dilution Factor		1.0	1.0

Chloromethane	NA	1.2 U	1.1 U
Bromomethane	NA	1.2 U	1.1 U
VinylChloride	200	1.2 U	1.1 U
Chloroethane	1900	1.2 U	1.1 U
MethyleneChloride	100	1.0 JB	1.0 JB
Trichlorofluoromethane	NA	1.2 U	1.1 U
1,1-Dichloroethene	400	1.2 U	1.1 U
1,1-Dichloroethane	200	1.2 U	1.1 U
trans-1,2-Dichloroethene	300	1.2 U	1.1 U
cis-1,2-Dichloroethene	NA	1.2 U	1.6
Chloroform	300	1.2 U	1.1 U
1,2-Dichloroethane	100	1.2 U	1.1 U
1,1,1-Trichloroethane	800	1.2 U	1.1 U
CarbonTetrachloride	600	1.2 U	1.1 U
Bromodichloromethane	NA	1.2 U	1.1 U
1,2-Dichloropropane	NA	1.2 U	1.1 U
cis-1,3-Dichloropropene	NA	1.2 U	1.1 U
Trichloroethene	700	1.2 U	2.1
Dibromochloromethane	NA	1.2 U	1.1 U
1,1,2-Trichloroethane	NA	1.2 U	1.1 U
Benzene	60	1.2 U	1.1 U
trans-1,3-Dichloropropene	NA	1.2 U	1.1 U
2-ChloroethylVinylEther	NA	1.2 U	1.1 U
Bromoform	NA	1.2 U	1.1 U
Tetrachloroethene	1400	1.2 U	2.0
1,1,2,2-Tetrachloroethane	600	1.2 U	1.1 U
Toluene	1500	0.8 J	1.0 J
Chlorobenzene	1700	1.2 U	1.1 U
Ethylbenzene	5500	1.2 U	1.1 U
Xylene(Total)	1200	1.2 U	1.1 U

Total Confident Conc. VOAs (s)	0	5.7
Total Estimated Conc. VOA TICs (s)	0	0

Table 2-2
Summary of Analytical Results Exceeding NYSDEC Criteria (Soils and Groundwater Grab Samples)
Photocircuits Corporation
Glen Cove, New York

SOIL (PPB)							
Sample ID	NYSDEC/ USEPA Soil Cleanup (ppb) Criteria	45A-SB-33					
Depth (ft)		16					
Volatile Compounds (ppb)							
Tetrachloroethene	1400	2500					
GROUNDWATER (PPB)							
Sample ID	NYSDEC GW Criteria (ppb)	45A-GW-1 28	45A-GW-2 28	45A-GW-3 28	45A-GW-7 12		
Depth (ft)							
1,1,1-Trichloroethene	5	-	150	140	-		
Trichloroethene	5	-	130	130	13		
Tetrachloroethene	5	20	32000	17000	120		
GROUNDWATER (PPB)							
Sample ID	NYSDEC GW Criteria (ppb)	31-GW-1 8	31-GW-4 12	31-GW-9 -	31-GW-10 -	31-GW-11 -	31-GW-13 -
Depth (ft)							
Vinyl Chloride	2	-	3.4	640	-	3.7	9.1
Chloroethane	50	-	-	57	180	-	-
1,1-Dichloroethene	5	570	12	11	-	-	-
1,1-Dichloroethane	5	1300	89	440	36	-	8.9
1,1,1-Trichloroethane	5	6000	18	7.2	-	-	-
Trichloroethene	5	-	-	38	-	-	-
Tetrachloroethene	5	150	7.1	-	-	-	-

"-" : Analyte was not detected above the applicable NYSDEC criteria

Table 2-3
Analytical Summary for Volatile Organic Compounds in Groundwater (Grab Samples)
Photocircuits Corporation
Glen Cove, New York

Sampling Location Sample ID Sample Date Dilution Factor	NYSDEC GW Criteria (ppb)	45A-GW-1 54865 04/08/98 1.0	45A-GW-2 54874 04/09/98 200.0	45A-GW-3 54822 04/10/98 100.0	45A-GW-4 54827 04/10/98 1.0	45A-GW-5 54823 04/10/98 1.0
VOIATILE COMPOUNDS (ppb)						
Chloromethane	NS	0.9 U	190 U	93 U	0.9 U	0.9 U
Bromomethane	NS	0.3 U	54 U	27 U	0.3 U	0.3 U
VinylChloride	2	0.4 U	78 U	39 U	0.4 U	0.4 U
Chloroethane	50	1.0 U	210 U	100 U	1.0 U	1.0 U
MethyleneChloride	5	1.0 U	210 U	100 U	1.0 U	1.0 U
Trichlorofluoromethane	NS	0.2 U	46 U	23 U	0.2 U	0.2 U
1,1-Dichloroethene	5	0.6 U	110 U	55 U	0.6 U	0.6 U
1,1,1-Dichloroethane	5	0.3 U	62 U	31 U	0.3 U	0.3 U
trans-1,2-Dichloroethene	NS	0.3 U	60 U	30 U	0.3 U	0.3 U
cis-1,2-Dichloroethene	NS	1.0 U	200 U	100 U	1.0 U	1.0 U
Chloroform	7	0.2 U	40 U	20 U	0.2 U	0.2 U
1,2-Dichloroethane	5	0.2 U	44 U	22 U	0.2 U	0.2 U
1,1,1-Trichloroethane	5	0.3	150	140	0.2 U	0.2 U
Carbon Tetrachloride	5	0.2 U	32 U	16 U	0.2 U	0.2 U
Bromodichloromethane	NS	0.2 U	38 U	19 U	0.2 U	0.2 U
1,2-Dichloropropane	NS	0.5 U	92 U	46 U	0.5 U	0.5 U
cis-1,3-Dichloropropene	NS	0.3 U	66 U	33 U	0.3 U	0.3 U
Trichloroethene	5	0.4 U	130	130	0.4 U	0.4 U
Dibromochloromethane	50	0.2 U	46 U	23 U	0.2 U	0.2 U
1,1,2-Trichloroethane	NS	0.4 U	86 U	43 U	0.4 U	0.4 U
Benzene	0.7	0.2 U	48 U	24 U	0.2 U	0.2 U
trans-1,3-Dichloropropene	NS	0.3 U	62 U	31 U	0.3 U	0.3 U
2-ChloroethylVinylEther	NS	0.5 U	92 U	46 U	0.5 U	0.5 U
Bromoform	NS	0.3 U	60 U	30 U	0.3 U	0.3 U
Tetrachloroethene	5	20	32000	17000	2.3	0.5
1,1,2,2-Tetrachloroethane	5	0.3 U	66 U	33 U	0.3 U	0.3 U
Toluene	5	2.9	36 U	18 U	0.9	2.6
Chlorobenzene	4	0.1 U	28 U	14 U	0.1 U	0.1 U
Ethylbenzene	5	0.4	48 U	24 U	0.2 U	0.3
Xylene(Total)	5	1.0 U	200 U	100 U	1.0 U	1.0 U
Total Confident Conc. VOAs (s)		24	32280	17270	3.2	3.4
Total Estimated Conc. VOA TICs (s)		0	0	0	0	0

NS: Not Specified

U: Analyte was not detected above the referenced reporting limit

Table 2-3
Analytical Summary for Volatile Organic Compounds in Groundwater (Grab Samples)
Photocircuits Corporation
Glen Cove, New York

Sampling Location Sample ID Sample Date Dilution Factor	NYSDEC GW Criteria (ppb)	45A-GW-6 54825 04/10/98 1.0	45A-GW-7 54826 04/10/98 1.0	31-GW-1 56169 04/20/98 100.0	31-GW-4 56164 04/20/98 1.0	31-GW-7 56170 04/20/98 1.0	TB041098 54824 04/09/98 1.0
VOLATILE COMPOUNDS (ppb)							
Chloromethane	NS	0.9 U	0.9 U	93 U	0.9 U	0.9 U	0.9 U
Bromomethane	NS	0.3 U	0.3 U	27 U	0.3 U	0.3 U	0.3 U
VinylChloride	2	0.4 U	0.4 U	39 U	3.4	0.4 U	0.4 U
Chloroethane	50	1.0 U	1.0 U	100 U	4.5	1.0 U	1.0 U
MethyleneChloride	5	1.0 U	1.0 U	100 U	2.7	1.0 U	1.0 U
Trichlorofluoromethane	NS	0.2 U	0.2 U	23 U	0.2 U	0.2 U	0.2 U
1,1-Dichloroethene	5	0.6 U	0.6 U	570	12	0.6 U	0.6 U
1,1-Dichloroethane	5	0.3 U	0.3 U	1300	89	0.3 U	0.3 U
trans-1,2-Dichloroethene	NS	0.3 U	0.3 U	30 U	0.3 U	0.3 U	0.3 U
cis-1,2-Dichloroethene	NS	1.0 U	1.0 U	100 U	3.7	1.0 U	1.0 U
Chloroform	7	0.2 U	0.2 U	20 U	0.2 U	0.8	0.2 U
1,2-Dichloroethane	5	0.2 U	0.2 U	22 U	0.8	0.2 U	0.2 U
1,1,1-Trichloroethane	5	0.2 U	0.2 U	6000	18	1.4	0.2 U
CarbonTetrachloride	5	0.2 U	0.2 U	16 U	0.2 U	0.2 U	0.2 U
Bromodichloromethane	NS	0.2 U	0.2 U	19 U	0.2 U	0.2 U	0.2 U
1,2-Dichloropropane	NS	0.5 U	0.5 U	46 U	0.5 U	0.5 U	0.5 U
cis-1,3-Dichloropropene	NS	0.3 U	0.3 U	33 U	0.3 U	0.3 U	0.3 U
Trichloroethene	5	0.4 U	1.3	41 U	4.7	1.3	0.4 U
Dibromochloromethane	50	0.2 U	0.2 U	23 U	0.2 U	0.2 U	0.2 U
1,1,2-Trichloroethane	NS	0.4 U	0.4 U	43 U	0.4 U	0.4 U	0.4 U
Benzene	0.7	0.2 U	0.3	24 U	0.2 U	0.2 U	0.2 U
trans-1,3-Dichloropropene	NS	0.3 U	0.3 U	31 U	0.3 U	0.3 U	0.3 U
2-ChloroethylVinylEther	NS	0.5 U	0.5 U	46 U	0.5 U	0.5 U	0.5 U
Bromoform	NS	0.3 U	0.3 U	30 U	0.3 U	0.3 U	0.3 U
Tetrachloroethene	5	0.7	120	150	7.1	2.2	0.1 U
1,1,2,2-Tetrachloroethane	5	0.3 U	0.3 U	33 U	0.3 U	0.3 U	0.3 U
Toluene	5	2.1	2.4	18 U	0.2 U	0.7	0.2 U
Chlorobenzene	4	0.1 U	0.1 U	14 U	0.1 U	0.1 U	0.1 U
Ethylbenzene	5	0.2	0.3	24 U	0.6	0.8	0.2 U
Xylene(Total)	5	1.0 U	1.0 U	100 U	2.0	2.0	1.0 U
Total Confident Conc. VOAs (s)		3.0	136	8020	148	9.2	0
Total Estimated Conc. VOA TICs (s)		0	0	0	0	0	0

NS: No standard specified

U: Analyte was not detected above the referenced reporting limit

Table 2-3
Analytical Summary for Volatile Organic Compounds in Groundwater (Grab Samples)
Photocircuits Corporation
Glen Cove, New York

Sampling Location Sample ID Sample Date Dilution Factor	NYSDEC GW Criteria (ppb)	31-GW-9 66934 6/17/98 6.0	31-GW-10 66935 6/17/98 1.0	31-GW-11 66936 6/17/98 1.0	31-GW-12 66937 6/17/98 1.0	31-GW-13 66938 6/17/98 1.0	F3061798 66939 6/17/98 1.0	YB061798 66940 6/17/98 1.0
VOLATILE ORGANIC COMPOUNDS								
Chloromethane	NS	4.6 U	0.9 U	0.9 U	0.9 U	0.9 U	0.9 U	0.9 U
Bromomethane	NS	1.4 U	0.3 U	0.3 U	0.3 U	0.3 U	0.3 U	0.3 U
Vinyl Chloride	2	640	0.4 U	3.7	0.7	9.1	0.4 U	0.4 U
Chloroethane	50	57	180	1.0 U	1.0 U	2.9	1.0 U	1.0 U
Methylene Chloride	5	5.2 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U
Trichlorofluoromethane	NS	1.2 U	0.2 U	0.2 U	0.2 U	0.2 U	0.2 U	0.2 U
1,1-Dichloroethene	5	11	0.6 U	0.6 U	0.6 U	0.6 U	0.6 U	0.6 U
1,1-Dichloroethane	5	440	36	1	0.3 U	8.9	0.3 U	0.3 U
trans-1,2-Dichloroethene	NS	3.7	1.1	0.3 U	0.3 U	1.5	0.3 U	0.3 U
cis-1,2-Dichloroethene	NS	520	1.0 U	1.0 U	1.2	15	1.0 U	1.0 U
Chloroform	7	1.0 U	0.2 U	0.2 U	0.2 U	0.2 U	0.2 U	0.2 U
1,2-Dichloroethane	5	1.5	1	0.2 U	0.2 U	0.2 U	0.2 U	0.2 U
1,1,1-Trichloroethane	5	7.2	0.2 U	0.2 U	0.2 U	0.2 U	0.2 U	0.2 U
Carbon Tetrachloride	5	0.8 U	0.2 U	0.2 U	0.2 U	0.2 U	0.2 U	0.2 U
Bromodichloromethane	NS	0.9 U	0.2 U	0.2 U	0.2 U	0.2 U	0.2 U	0.2 U
1,2-Dichloropropane	NS	2.3 U	0.5 U	0.5 U	0.5 U	0.5 U	0.5 U	0.5 U
cis-1,3-Dichloropropene	NS	1.6 U	0.3 U	0.3 U	0.3 U	0.3 U	0.3 U	0.3 U
Trichloroethene	5	38	0.4 U	0.4 U	0.4 U	1.9	0.4 U	0.4 U
Dibromochloromethane	50	1.2 U	0.2 U	0.2 U	0.2 U	0.2 U	0.2 U	0.2 U
1,1,2-Trichloroethane	NS	2.2 U	0.4 U	0.4 U	0.4 U	0.4 U	0.4 U	0.4 U
Benzene	0.7	1.2 U	0.8	0.3	0.2 U	1.1	0.2 U	0.2 U
trans-1,3-Dichloropropene	NS	1.6 U	0.3 U	0.3 U	0.3 U	0.3 U	0.3 U	0.3 U
2-Chloroethyl Vinyl Ether	NS	2.3 U	0.5 U	0.5 U	0.5 U	0.5 U	0.5 U	0.5 U
Bromoform	NS	1.5 U	0.3 U	0.3 U	0.3 U	0.3 U	0.3 U	0.3 U
Tetrachloroethene	5	0.5 U	0.1	0.1 U	0.1 U	0.2	0.1 U	0.1 U
1,1,2,2-Tetrachloroethane	5	1.6 U	0.3 U	0.3 U	0.3 U	0.3 U	0.3 U	0.3 U
Toluene	5	0.9 U	0.2 U	0.2 U	0.2 U	0.2 U	0.6	0.2 U
Chlorobenzene	4	0.7 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U
Ethylbenzene	5	1.2 U	0.5	0.2 U	0.2 U	0.2 U	0.2 U	0.2 U
Xylenes (Total)	5	5.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U
Total Confident Conc. VOAs (s)		1718.4	219.5	5	1.9	40.6	0.6	0
Total Estimated Conc. VOA TICs (s)		0	0	0	15	0	14	0

NS: No standard specified

U: Analyte was not detected above the referenced reporting limit

Table 2-4
Water Level Measurements/Monitoring Well Construction Details
Photocircuits Corporation
Glen Cove, New York

Site	Well Number	Casing Diameter (in)	Depth to Bottom (ft)	Top of Casing Elevation (ft above MSL)	August 7, 1996		September 10, 1996		May 13, 1998	
					Depth to Water (ft)	Ground Water Elevation (ft above MSL)	Depth to Water (ft)	Ground Water Elevation (ft above MSL)	Depth to Water (ft)	Ground Water Elevation (ft above MSL)
45A Sea Cliff Ave. Site	MW-1s	4	20.62	101.94	10.68	91.26	11.41	90.53	8.75	82.51
	MW-2s	4	20.71	100.87	8.37	92.5	8.86	92.01	6.66	85.84
	MW-3s	4	18.73	99.83	8.8	91.03	9.56	90.27	7.02	84.01
	MW-4s	4	15.00	NA	NA	NA	NA	NA	5.20	NA
31 Sea Cliff Ave. Site	MW-2	2	24.62	102.76	9.2	93.56	10.02	92.74	NA	NA
	MW-3	2	18.98	98.8	6.2	92.6	7.15	91.65	3.75	88.85
	MW-4	2	23.66	97.56	4.24	93.32	5.28	92.28	2.17	91.15
	MW-5	2	99.32	97.39	4.26	93.13	5.56	91.83	2.41	90.72
	MW-6	2	13.45	99	4.2	94.8	5.25	93.75	2.60	92.2
	MW-7	4	23.37	95.9	5.38	90.52	6.3	89.6	3.55	86.97
	MW-8	4	169.3	99.01	8.04	90.97	8.88	90.13	5.88	85.09
	MW-9	4	27.57	98.5	7.34	91.16	8.47	90.03	5.80	85.36
	MW-10	4	130.27	98.43	7.74	90.69	8.61	89.82	5.64	85.05
	MW-11	4	170	98.46	7.9	90.56	8.79	89.67	5.90	84.66
	NC-Well	2	10.39	97.57	4.88	92.69	5.9	91.67	3.01	89.68

Note: MSL = Mean Sea Level

NA = Data Not Available

MW-2 location is assumed to be paved over

TABLE 2-5

Well ID	MW-1S	MW-2S	MW-3S	MW-4S	MW-2	MW-3	MW-4	MW-5	MW-6	MW-7
Site Location	45a	45a	45a	45a	31	31	31	31	31	31
Depth to Water (ft)	8.75	6.66	7.02	5.20	?	3.75	2.17	2.41	2.60	3.55
Total Depth (ft)	20.62	20.71	18.73	15.00	24.62	18.98	23.66	99.32	13.45	23.37
Well Diameter (in)	4	4	4	4	2	2	2	2	2	4
One Volume (gal)	7.80	9.10	6.30	4.70	9.10	2.47	3.45	15.50	1.72	12.80
3 Volumes (gal)	22.00	27.30	18.00	14.00	27.30	7.40	10.40	45.00	5.20	38.00

Pre-Purge							
pH	6.65	6.33	5.48	6.72	6.41	6.53	6.73
Temperature (°C)	13.0	13.4	15.5	15.6	4.6	12.3	14.2
Sp. Cond. (µS/cm)	0.499	0.718	0.674	0.271	0.582	0.261	0.855
Turbidity (NTU)	238	118	25	475	24	248.00	771
DO (mg/l)	4.97	7.62	2.89	7.34		1.95	2.62
							4.18
							2.97
							1.75

Post-Turne										
pH	6.49	6.28	5.38	7.15	6.76	6.48	6.77	7.95	DIRY	9.74
Temperature (°C)	12.8	13.1	16.0	15.6	5.6	13.1	14.1	15.3	DIRY	17.8
Sp. Cond. (µS/cm)	0.455	0.698	0.743	0.341	0.481	0.266	0.875	0.160	DIRY	3.640
Turbidity (NTU)	284	147	999	75	44	-10	380	166	DIRY	491
DO (mg/l)	4.83	7.87	3.35	8.60	1.65	1.73	6.79		DIRY	3.84

Post-Sample										
pH	6.88	6.23	5.17	7.06	6.24	6.95	6.62	7.99	6.74	9.59
Temperature (°C)	12.9	13.0	16.1	15.1	5.6	14.4	15.2	15.7	16.1	18.1
Sp. Cond. (µS/cm)	0.445	0.705	0.754	0.190	0.450	0.194	0.839	0.161	0.456	3.330
Turbidity (NTU)	9	-10	999	280	16	305	58	82	113	342
DO (mg/l)	5.80	7.90	3.05	8.60		3.81	2.65	6.59	2.42	1.73

Purge Start Time	9:25	12:37	9:58	13:15	11:30	11:10	13:55	11:35	14:31	13:42
Purge End Time	9:32	12:57	10:03	13:25	11:50	11:20	14:02	12:35	14:33	13:52
Purge Method	2" Grundfos	2" Grundfos	2" Grundfos	2" Grundfos	CP	2" Grundfos	2" Grundfos	2" Grundfos	2" Grundfos	2" Grundfos
Volume Purged (gal)	23.0	28.0	20.0	24.0	27.5	13.0	12.0	25.0	4.0	30.0
Purge Rate (gpm)	3	2	3	2	2	2	2	2	2	2
Sample Date	5/13/98	5/13/98	5/14/98	5/13/98	3/18/97	5/13/98	5/13/98	5/14/98	5/13/98	5/14/98
Sample Time	9:40	15:50	10:07	15:35	8:20	15:17	16:05	14:45	16:16	14:29

CP: Central Pump.

TABLE 2-5
Ground Water Sampling Field Parameters, May 1998
Photoircuits Corporation
Glen Cove, New York

Well ID	Site Location					
MW-8	31	5.88	5.80	5.64	5.90	3.01
MW-9	31	27.57	130.27	98.46	97.57	2
MW-10	31	4	4	4	4	1.20
MW-11	31	106.00	14.10	81.00	106.00	3.60
NC-Well	31	318.00	42.30	243.00	318.00	

Pre-Purge						
pH	7.90	7.30	7.40	7.64	7.17	
Temperature (°C)	18.0	14.1	18.0	17.3	16.5	
Sp. Cond. (uS/cm)	0.220	0.425	0.340	0.235	0.515	
Turbidity (NTU)	68	302	136	-8	999	
DOC (mg/l)	7.30	1.53	5.50	6.01	4.24	

Post-Purge						
pH	7.50	6.83	7.10	6.81	7.45	
Temperature (°C)	15.0	13.9	17.0	15.7	16.9	
Sp. Cond. (uS/cm)	0.200	0.308	0.840	0.196	0.603	
Turbidity (NTU)	96	999	136	-10	264	
DOC (mg/l)	8.80	1.97	3.00	7.32	4.83	

Post-Sample						
pH	7.50	6.76	8.00	7.60	7.45	
Temperature (°C)	15.0	13.3	16.0	15.0	16.6	
Sp. Cond. (uS/cm)	0.220	0.347	0.340	0.220	0.560	
Turbidity (NTU)	216	999	196	178	54	
DOC (mg/l)	9.40	3.17	6.20	7.00	2.80	

Purge Start Time	11:53	12:51	10:35	9:05	10:52	
Purge End Time	12:15	13:07	11:10	9:45	10:56	
Purge Method	2" Grundfos	2" Grundfos	2" Grundfos	2" Grundfos	CP	
Volume Purged (gal)	150.0	45.0	190.0	220.0	4.0	
Purge Rate (gpm)	6	3	5	5	1	
Sample Date	5/16/98	5/14/98	5/16/98	5/16/98	5/14/98	
Sample Time	12:30	13:21	11:25	10:44	11:06	

CP: Centrifugal pump.

Table 2-6
Analytical Summary for Volatile Organic Compounds
Monitoring Well Sampling Event May 13-15, 1998
Photocircuits Corporation
Glen Cove, New York

Sampling Location	NYSDEC	MW-1S	MW-2S	MW-3S	MW-3SD*	MW-4S
Sample ID	GW	61008	61001	61007	61011	61002
Sample Date	Criteria	5/14/98	5/13/98	5/14/98	5/14/98	5/13/98
Dilution Factor	(ppb)	1.0	1.0	1.0	1.0	2.0

VOLATILE COMPOUNDS (ppb)

Chloromethane	NS	0.9 U	0.9 U	0.9 U	0.9 U	1.9 U
Bromomethane	NS	0.3 U	0.3 U	0.3 U	0.3 U	0.5 U
VinylChloride	2	0.4 U	0.4 U	0.4 U	0.4 U	0.8 U
Chloroethane	50	1.0 U	1.0 U	1.0 U	1.0 U	2.1 U
MethyleneChloride	5	1.0 U	1.0 U	1.0 U	1.0 U	2.1 U
Trichlorofluoromethane	NS	0.2 U	0.2 U	0.2 U	0.2 U	0.5 U
1,1-Dichloroethene	5	0.6 U	0.6 U	0.6 U	0.6 U	1.1 U
1,1-Dichloroethane	5	0.3 U	0.3 U	0.3 U	0.3 U	0.6 U
trans-1,2-Dichloroethene	NS	0.3 U	0.3 U	0.3 U	0.3 U	0.6 U
cis-1,2-Dichloroethene	NS	1.1	1.0 U	3.0	2.9	2.0 U
Chloroform	7	0.2 U	0.5	0.2 U	0.2 U	0.4 U
1,2-Dichloroethane	5	0.2 U	0.2 U	0.2 U	0.2 U	0.4 U
1,1,1-Trichloroethane	5	0.3	0.2 U	0.2 U	0.2 U	0.4 U
CarbonTetrachloride	5	0.2 U	0.2 U	0.2 U	0.2 U	0.3 U
Bromodichloromethane	NS	0.2 U	0.2 U	0.2 U	0.2 U	0.4 U
1,2-Dichloropropane	NS	0.5 U	0.5 U	0.5 U	0.5 U	0.9 U
cis-1,3-Dichloropropene	NS	0.3 U	0.3 U	0.3 U	0.3 U	0.7 U
Trichloroethene	5	3.0	0.4 U	100	100	13
Dibromochloromethane	50	0.2 U	0.2 U	0.2 U	0.2 U	0.5 U
1,1,2-Trichloroethane	NS	0.4 U	0.4 U	0.4 U	0.4 U	0.9 U
Benzene	0.7	0.2 U	0.2 U	0.2 U	0.2 U	0.5 U
trans-1,3-Dichloropropene	NS	0.3 U	0.3 U	0.3 U	0.3 U	0.6 U
2-ChloroethylVinylEther	NS	0.5 U	0.5 U	0.5 U	0.5 U	0.9 U
Bromoform	NS	0.3 U	0.3 U	0.3 U	0.3 U	0.6 U
Tetrachloroethene	5	71	1.3	9.1	9.7	330
1,1,2,2-Tetrachloroethane	5	0.3 U	0.3 U	0.3 U	0.3 U	0.7 U
Toluene	5	0.2 U	0.2 U	0.2 U	0.2 U	0.4 U
Chlorobenzene	4	0.1 U	0.1 U	0.1 U	0.1 U	0.3 U
Ethylbenzene	5	0.2 U	0.2 U	0.2 U	0.2 U	0.5 U
Xylene(Total)	5	1.0 U	1.0 U	1.0 U	1.0 U	2.0 U

Total Confident Conc. VOAs (s)	75	1.8	112	113	343
Total Estimated Conc. VOA TICs (s)	0	0	0	0	0

NS: Not Specified

U: Analyte was not detected above the referenced reporting limit

*: Duplicate samples of MW-3S and MW-7

Table 2-6
 Analytical Summary for Volatile Organic Compounds
 Monitoring Well Sampling Event May 13-15, 1998
 Photocircuits Corporation
 Glen Cove, New York

Sampling Location	NYSDEC	MW-NC	MW-3	MW-4	MW-5	MW-6
Sample ID	GW	61005	61000	61003	61012	61004
Sample Date	Criteria	5/14/98	5/13/98	5/13/98	5/14/98	5/13/98
Dilution Factor	(ppb)	1.0	1.0	1.0	1.0	1.0

VOLATILE COMPOUNDS (ppb)

Chloromethane	NS	0.9 U	0.9 U	0.9 U	0.9 U	0.9 U
Bromomethane	NS	0.3 U	0.3 U	0.3 U	0.3 U	0.3 U
VinylChloride	2	0.4 U	0.4 U	0.4 U	0.4 U	0.4 U
Chloroethane	50	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U
MethyleneChloride	5	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U
Trichlorofluoromethane	NS	0.2 U	0.2 U	0.2 U	0.2 U	0.2 U
1,1-Dichloroethene	5	0.6 U	0.6 U	0.6 U	0.6 U	0.6 U
1,1-Dichloroethane	5	0.4	0.3 U	0.3 U	0.3 U	0.5
trans-1,2-Dichloroethene	NS	0.3 U	0.3 U	0.3 U	0.3 U	0.3 U
cis-1,2-Dichloroethene	NS	5.1	1.0 U	1.0 U	1.0 U	1.5
Chloroform	7	0.2 U	0.2 U	0.2 U	0.2 U	0.2 U
1,2-Dichloroethane	5	0.2 U	0.2 U	0.2 U	0.2 U	0.2 U
1,1,1-Trichloroethane	5	0.2 U	0.2 U	0.2 U	0.2 U	0.2 U
CarbonTetrachloride	5	0.2 U	0.2 U	0.2 U	0.2 U	0.2 U
Bromodichloromethane	NS	0.2 U	0.2 U	0.2 U	0.2 U	0.2 U
1,2-Dichloropropane	NS	0.2	0.5 U	0.5 U	0.5 U	0.5 U
cis-1,3-Dichloropropene	NS	0.3 U	0.3 U	0.3 U	0.3 U	0.3 U
Trichloroethene	5	2.4	0.4 U	0.4 U	0.9	0.4
Dibromochloromethane	50	0.2 U	0.2 U	0.2 U	0.2 U	0.2 U
1,1,2-Trichloroethane	NS	0.4 U	0.4 U	0.4 U	0.4 U	0.4 U
Benzene	0.7	0.2 U	0.2 U	0.2 U	0.2 U	0.2 U
trans-1,3-Dichloropropene	NS	0.3 U	0.3 U	0.3 U	0.3 U	0.3 U
2-ChloroethylVinylEther	NS	0.5 U	0.5 U	0.5 U	0.5 U	0.5 U
Bromoform	NS	0.3 U	0.3 U	0.3 U	0.3 U	0.3 U
Tetrachloroethene	5	0.9	0.1 U	0.4	0.7	0.7
1,1,2,2-Tetrachloroethane	5	0.3 U	0.3 U	0.3 U	0.3 U	0.3 U
Toluene	5	0.2 U	1.1	0.2 U	0.2 U	0.2 U
Chlorobenzene	4	0.1 U	0.1 U	0.1 U	0.1 U	0.1 U
Ethylbenzene	5	0.2 U	0.3	0.2 U	0.2 U	0.2 U
Xylene(Total)	5	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U

Total Confident Conc. VOAs (s)	9.0	1.4	0.4	1.6	2.4
Total Estimated Conc. VOA TICs (s)	0	0	0	0	8.8

NS: Not Specified

U: Analyte was not detected above the referenced reporting limit

Table 2-6
Analytical Summary for Volatile Organic Compounds
Monitoring Well Sampling Event May 13-15, 1998
Photocircuits Corporation
Glen Cove, New York

Sampling Location	NYSDEC	MW-7	MW-7D*	MW-8	MW-9	MW-10
Sample ID	GW	61014	61010	61016	61009	61014
Sample Date	Criteria	5/14/98	5/14/98	5/15/98	5/14/98	5/15/98
Dilution Factor	(ppb)	25.0	25.0	1.0	1.0	1.0

VOLATILE COMPOUNDS (ppb)

Chloromethane	NS	23 U	23 U	0.9 U	0.9 U	0.9 U
Bromomethane	NS	6.8 U	6.8 U	0.3 U	0.3 U	0.3 U
VinylChloride	2	18	16	0.4 U	1.1	1.9
Chloroethane	50	71	74	1.0 U	1.0 U	1.0 U
MethyleneChloride	5	26 U	26 U	1.0 U	1.0 U	1.0 U
Trichlorofluoromethane	NS	5.8 U	5.8 U	0.2 U	0.2 U	0.2 U
1,1-Dichloroethene	5	14 U	14 U	0.6 U	0.6 U	13
1,1-Dichloroethane	5	3200	3200	2.0	1.6	62
trans-1,2-Dichloroethene	NS	7.5 U	7.5 U	0.3 U	0.3 U	0.3 U
cis-1,2-Dichloroethene	NS	25 U	25 U	6.3	2.0	46.0
Chloroform	7	5.0 U	5.0 U	0.2 U	0.2 U	0.2 U
1,2-Dichloroethane	5	5.5 U	5.5 U	0.2 U	0.2 U	1.4
1,1,1-Trichloroethane	5	12	12	0.2 U	0.2 U	3.1
CarbonTetrachloride	5	4.0 U	4.0 U	0.2 U	0.2 U	0.2 U
Bromodichloromethane	NS	4.8 U	4.8 U	0.2 U	0.2 U	0.2 U
1,2-Dichloropropane	NS	12 U	12 U	0.5 U	0.5 U	0.5 U
cis-1,3-Dichloropropene	NS	8.2 U	8.2 U	0.3 U	0.3 U	0.3 U
Trichloroethene	5	50	55	5.7	0.4 U	14
Dibromochloromethane	50	5.8 U	5.8 U	0.2 U	0.2 U	0.2 U
1,1,2-Trichloroethane	NS	11 U	11 U	0.4 U	0.4 U	0.4 U
Benzene	0.7	6.0 U	6.0 U	0.2 U	0.2 U	0.2 U
trans-1,3-Dichloropropene	NS	7.8 U	7.8 U	0.3 U	0.3 U	0.3 U
2-ChloroethylVinylEther	NS	12 U	12 U	0.5 U	0.5 U	0.5 U
Bromoform	NS	7.5 U	7.5 U	0.3 U	0.3 U	0.3 U
Tetrachloroethene	5	15	18	2.0	0.1	3.3
1,1,2,2-Tetrachloroethane	5	8.2 U	8.2 U	0.3 U	0.3 U	0.3 U
Toluene	5	26	27	0.2 U	0.2 U	0.2 U
Chlorobenzene	4	3.5 U	3.5 U	0.1 U	0.1 U	0.1 U
Ethylbenzene	5	6.0 U	6.0 U	0.2 U	0.2 U	0.2 U
Xylene(Total)	5	25 U	25 U	1.0 U	1.0 U	1.0 U

Total Confident Conc. VOAs (s)	3392	3402	16	4.8	145
Total Estimated Conc. VOA TICs (s)	0	0	0	0	0

NS: Not Specified

U: Analyte was not detected above the referenced reporting limit

*: Duplicate samples of MW-3S and MW-7

Table 2-6
 Analytical Summary for Volatile Organic Compounds
 Monitoring Well Sampling Event May 13-15, 1998
 Photocircuits Corporation
 Glen Cove, New York

Sampling Location	NYSDEC	MW-11	FB051498	TB51298
Sample ID	GW	61015	61006	61017
Sample Date	Criteria	5/15/98	5/14/98	5/12/98
Dilution Factor	(ppb)	1.0	1.0	1.0

VOLATILE COMPOUNDS (ppb)

Chloromethane	NS	0.9 U	0.9 U	0.9 U
Bromomethane	NS	0.3 U	0.3 U	0.3 U
VinylChloride	2	0.4 U	0.4 U	0.4 U
Chloroethane	50	1.0 U	1.0 U	1.0 U
MethyleneChloride	5	1.0 U	1.4	1.0 U
Trichlorofluoromethane	NS	0.2 U	0.2 U	0.2 U
1,1-Dichloroethene	5	0.9	0.6 U	0.6 U
1,1-Dichloroethane	5	2.6	0.3 U	0.3 U
trans-1,2-Dichloroethene	NS	0.3 U	0.3 U	0.3 U
cis-1,2-Dichloroethene	NS	21.0	1.0 U	1.0 U
Chloroform	7	0.2 U	0.2 U	0.2 U
1,2-Dichloroethane	5	0.2 U	0.2 U	0.2 U
1,1,1-Trichloroethane	5	0.2	0.2 U	0.2 U
CarbonTetrachloride	5	0.2 U	0.2 U	0.2 U
Bromodichloromethane	NS	0.2 U	0.2 U	0.2 U
1,2-Dichloropropane	NS	0.5 U	0.5 U	0.5 U
cis-1,3-Dichloropropene	NS	0.3 U	0.3 U	0.3 U
Trichloroethene	5	16	0.4 U	0.4 U
Dibromochloromethane	50	0.2 U	0.2 U	0.2 U
1,1,2-Trichloroethane	NS	0.4 U	0.4 U	0.4 U
Benzene	0.7	0.2 U	0.2 U	0.2 U
trans-1,3-Dichloropropene	NS	0.3 U	0.3 U	0.3 U
2-ChloroethylVinylEther	NS	0.5 U	0.5 U	0.5 U
Bromoform	NS	0.3 U	0.3 U	0.3 U
Tetrachloroethene	5	1.5	0.1 U	0.1 U
1,1,2,2-Tetrachloroethane	5	0.3 U	0.3 U	0.3 U
Toluene	5	0.2 U	0.7	0.2 U
Chlorobenzene	4	0.1 U	0.1 U	0.1 U
Ethylbenzene	5	0.2 U	0.2 U	0.2 U
Xylene(Total)	5	1.0 U	1.0 U	1.0 U

Total Confident Conc. VOAs (s)	42	2.1	0
Total Estimated Conc. VOA TICs (s)	0	4.7	0

NS: Not Specified

U: Analyte was not detected above the referenced reporting limit

Table J-1
Summary of Falling/Rising Head Slug Testing Data and Results
Photocircuits Corp.
Glen Cove, New York

MONITORING WELL	MW-1S		MW-2S		MW-3S		MW-4S		MW-3		MW-4		MW-5	
	FALLING	RISING	FALLING	RISING	FALLING	RISING	FALLING	RISING	FALLING	RISING	FALLING	RISING	FALLING	RISING
INPUT PARAMETERS *														
H ₀ (ft)	NQ		1.227	2.198	NQ		0.594	NA	1.736	1.416	1.934	2.42	2.561	3.116
R _c (ft)			0.1667	0.1667			0.1667		0.1667	0.08333	0.08333	0.08333	0.08333	0.08333
R _w (ft)			0.3333	0.3333			0.3333		0.3333	0.25	0.25	0.25	0.25	0.25
D (ft)			190.9	193.1			191.7		191.5	194.9	194.9	196.8	196.8	196.9
l (ft)			10	10			10		10	10	10	10	10	10
H (ft)			11.45	13.75			10.38		6.5	13.83	13.83	20.46	20.46	96.22
COMPUTED PARAMETERS (Bouwer-Rice method)														
K (ft/min)	NQ		1.060E-01	1.259E-02	NQ		6.266E-03	NA	2.080E-02	1.767E-03	1.262E-03	8.069E-04	6.859E-04	3.723E-05
K (ft/day)			1.526E+02	1.813E+01			9.023E+00		2.995E+01	2.544E+00	1.817E+00	1.162E+00	9.877E-01	5.361E-02
K (cm/s)			5.300E-02	6.295E-03			3.133E-03		1.040E-02	8.835E-04	6.310E-04	4.035E-04	3.430E-04	1.862E-05

NA: Falling head slug test was not appropriate because water level was within screened zone
NQ: Data measured during test were not of suitable quality to provide a useable analytical result
Ho: Initial drawdown in test well (Note: Yo is recalculated by program based on linearity of graph)
Rc: Internal radius of test well casing
Rw: Effective radius of test well
D: Saturated aquifer thickness under static conditions
l: Length of test well screen
H: Height of water column in test well under static conditions
K: Hydraulic conductivity
* Analytical Program: AQTESOLV, Duffield and Rumbaugh (1989)

Table 3-1
Summary of Falling/Rising Head Slug Testing Data and Results
Photocredits Corp.
Glen Cove, New York

MONITORING WELL	MW-6		MW-7		MW-8		MW-9		MW-10		MW-11		NC Well	
	FALLING	RISING	FALLING	RISING	FALLING	RISING	FALLING	RISING	FALLING	RISING	FALLING	RISING	FALLING	RISING

INPUT
PARAMETERS *

Ho (ft)	NA	2.023	2.639	NQ	1.496	0.044	3.728	2.697	3.853	4.23	NQ	1.442	3.136	4.393
Re (ft)		0.08333	0.1667		0.1667	0.1667	0.1667	0.1667	0.1667	0.1667		0.1667	0.08333	0.08333
Rw (ft)		0.25	0.3333		0.3333	0.3333	0.3333	0.3333	0.3333	0.3333		0.3333	0.25	0.25
D (ft)		196.4	194.8		194.1	194.1	193.4	193.4	194.3	194.3		194.1	196	196
l (ft)		10	15.33		15.33	15.33	15.33	15.33	15.33	15.33		15	5	5
h (ft)		9.85	18.12		163.4	163.4	20.92	20.92	124.57	124.57		164.13	6.39	6.39

COMPUTED
PARAMETERS (Bouwer-Rice method)

K (ft/min)	NA	8.329E-04	6.572E-03	NQ	1.677E-02	1.566E-02	3.891E-04	1.745E-03	6.849E-03	5.866E-03	NQ	6.587E-02	5.522E-04	5.402E-04
K (ft/day)		1.199E+00	9.464E+00		2.415E+01	2.255E+01	5.603E-01	2.513E+00	9.863E+00	8.447E+00		9.485E+01	7.952E-01	7.779E-01
K (cm/s)		4.165E-04	3.286E-03		8.385E-03	7.830E-03	1.946E-04	8.725E-04	3.425E-03	2.933E-03		3.294E-02	2.761E-04	2.701E-04

NA: Falling head slug test was not appropriate because water level was within screened zone

NQ Data measured during test were not of suitable quality to provide a useable analytical result

Ho: Initial drawdown in test well (Note: Yo is recalculated by program based on linearity of graph)

Re: Internal radius of test well casing

Rw: Effective radius of test well

D: Saturated aquifer thickness under static conditions

l: Length of test well screen

h: Height of water column in test well under static conditions

K: Hydraulic conductivity

* Analytical Program: AQTESOLV, Duffield and Rumbaugh (1989)

Appendix A

Soil Borings Logs/Well Log

SOIL BORING LOG

Page 1 of 1

		PROJECT NAME: Photocircuits	PROJECT NO.: 12080	Boring No: 45A-GW-1
		PROJECT LOCATION: 45A Seaclyff Avenue, Glen Cove Long Island		LOCATION SKETCH 
COMPLETION DATE: 4/8/98	TOTAL DEPTH OF BOREHOLE: 28 Feet	MONITORING DEVICE: OVM (PID)	GEOLOGIST / OFFICE: J. Gagnon/Warren	
DRILLING CONTRACTOR / DRILLER: Zebra/ Matt		DRILLING EQUIPMENT: Geoprobe	DRILLING METHOD / BIT: Hollow Stem Push Rod	
SAMPLING METHOD: Acetate-Lined Macrocore	DEPTH TO GROUNDWATER 22	GROUND SURFACE ELEVATION: NA	WELL INSTALLED? No	
MEMO: Boring located to the south of building 7.				

DEPTH (Feet)	RECOVERY (Feet)	OVM (PPM)	BURMEISTER SYSTEM SOIL DESCRIPTION Color, Texture, Moisture, Etc.	SAMPLES
0			Ground Surface	0
1	3.0	0	Asphalt fall in and fill, coarse gravel and pebbles	1
2				2
3				3
4				4
5	3.0	0	Asphalt fall in	5
6				6
7				7
8			Natural materials	8
9	3.8	0	Back fill material	9
10			Fine to coarse tan to med brwn SAND, w/ little to fine gravel and med gravel	10
11				11
12				12
13	3.8	0	Fine to coarse tan to med brwn SAND, w/ little to fine gravel and med gravel, trace pebbles and cobble	13
14				14
15				15
16				16
17	4.0	1.9	Fine to coarse tan to med brwn SAND, w/ little to fine gravel and med gravel, trace pebbles and cobble	17
18				18
19			Fine to med SAND with silt and trace clay	19
20			Silty CLAY with a 2" lens of fine to medium sand with silt	20
21	2.0	1.2	Damp Silty CLAY	21
22			WET SAND with trace gravel	22
23			End of boring at 28' b.g.	23
24				24

SOIL BORING LOG

Page 1 of 1

		PROJECT NAME: Photocircuits		PROJECT NO.: 12080		Boring No: 45A-GW-2			
		PROJECT LOCATION: 45A Seaciff Avenue, Glen Cove Long Island				LOCATION SKETCH 			
COMPLETION DATE: 4/10/98		TOTAL DEPTH OF BOREHOLE: 22 Feet		MONITORING DEVICE: OVM (PID)				GEOLOGIST / OFFICE: J. Gagnon/Warren	
DRILLING CONTRACTOR / DRILLER: Zebra/ Matt		DRILLING EQUIPMENT: Geoprobe		DRILLING METHOD / BIT: Hollow Stem Push Rod					
SAMPLING METHOD: Acetate-Lined Macrocore		DEPTH TO GROUNDWATER: 22 Feet		GROUND SURFACE ELEVATION: NA				WELL INSTALLED? No	
MEMO: Boring located inside building 7.									

DEPTH (Feet)	RECOVERY (Feet)	OVM (PPM)	BURMEISTER SYSTEM SOIL DESCRIPTION Color, Texture, Moisture, Etc.	SAMPLES
0			Ground Surface	0
1	2.5	332	Dark brwn Silty SAND with fine to medium gravel and trace cobble	1
2			Firm Sandy CLAY	2
3				3
4				4
5	3.0	227	Very fine light brwn/ tan SAND w/ gravel and pebbles	5
6				6
7				7
8				8
9	3.0	370	Dark brwn Silty SAND	9
10			Fine to coarse beach like SAND	10
11				11
12				12
13	1.0	236	Light brwn/ tan Silty SAND with coarse materials	13
14	1.4	168	Light brwn/ tan Silty SAND with coarse materials 2" lens of sand and clay, moist	14
15				15
16				16
17	2.0	189	Light brwn/ tan Silty SAND with coarse materials	17
18	1.7	492	Light brwn/ tan fine SAND with trace clay	18
19				19
20				20
21	1.5	329	Damp, Light brwn/ tan fine SAND with trace clay	21
22				22
23			End of boring at 22' b.g.	23
24				24

SOIL BORING LOG

Page 1 of 1

		PROJECT NAME: Photocircuits		PROJECT NO.: 12080		Boring No: 45A-GW-3			
		PROJECT LOCATION: 45A Seacliff Avenue, Glen Cove Long Island				LOCATION SKETCH 			
COMPLETION DATE: 4/10/98		TOTAL DEPTH OF BOREHOLE: 22 Feet		MONITORING DEVICE: OVM (PID)				GEOLOGIST / OFFICE: J. Gagnon/Warren	
DRILLING CONTRACTOR / DRILLER: Zebra/ Matt		DRILLING EQUIPMENT: Geoprobe		DRILLING METHOD / BIT: Hollow Stem Push Rod					
SAMPLING METHOD: Acetate-Lined Macrocore		DEPTH TO GROUNDWATER: 22 Feet		GROUND SURFACE ELEVATION: NA				WELL INSTALLED? No	
MEMO: Boring located inside building 7.									

DEPTH (Feet)	RECOVERY (Feet)	OVM (PPM)	BURMEISTER SYSTEM SOIL DESCRIPTION Color, Texture, Moisture, Etc.	SAMPLES
0			Ground Surface	
1	3.0	176		
2				
3				
4				
5	3.5	229	Very dark brwn fine silty SAND w/ coarse materials and pebbles	
6			Light brwn/ tan finr SAND w/ coarse materials, some gravel	
7				
8				
9	4.0		USED AS GEOTECHNICAL SAMPLE	
10				
11				
12				
13	1.0	180	Fine light brwn SAND coarse	
14	1.0	60	Fine light brwn SAND coarse	
15				
16				
17	2.0	412	Fine light brwn SAND coarse	
18	2	1036	Dark brwn brittle, Silty SAND with clay little pebbles	
19				
20				
21	1.0	177	Light brwn/ tan fine to coarse SAND, moist	
22				
23			End of boring at 22' b.g.	
24				

SOIL BORING LOG

Page 1 of 1

		PROJECT NAME: Photocircuits		PROJECT NO.: 12080		Boring No: 45A-GW-4			
		PROJECT LOCATION: 45A Seacliff Avenue, Glen Cove Long Island				LOCATION SKETCH 			
COMPLETION DATE: 4/10/98		TOTAL DEPTH OF BOREHOLE: 8 Feet		MONITORING DEVICE: OVM (PID)				GEOLOGIST / OFFICE: J. Gagnon/Warren	
DRILLING CONTRACTOR / DRILLER: Zebra/ Matt		DRILLING EQUIPMENT: Geoprobe		DRILLING METHOD / BIT: Hollow Stem Push Rod					
SAMPLING METHOD: Acetate-Lined Macrocore		DEPTH TO GROUNDWATER: 8 Feet		GROUND SURFACE ELEVATION: NA				WELL INSTALLED? No	
MEMO: Boring located inside building 7.									

DEPTH (Feet)	RECOVERY (Feet)	OVM (PPM)	BURMEISTER SYSTEM SOIL DESCRIPTION Color, texture, Moisture, Etc.	SAMPLES
0			Ground Surface: Asphalt	0
1	2.5	0	Asphalt fall in Very coarse medium brown SAND with medium and large gravel	1
2				2
3				3
4				4
5	4.0	0	Very coarse medium brown SAND with medium and large gravel	5
6				6
7				7
8				8
9			End of boring at 8' b.g.	9
10				10
11				11
12				12
13				13
14				14
15				15
16				16
17				17
18				18
19				19
20				20
21				21
22				22
23				23
24				24

SOIL BORING LOG

Page 1 of 1

		PROJECT NAME: Photocircuits	PROJECT NO.: 12080	Boring No: 45A-GW-5
		PROJECT LOCATION: 45A Seacliff Avenue, Glen Cove Long Island		LOCATION SKETCH 
COMPLETION DATE: 4/10/98	TOTAL DEPTH OF BOREHOLE: 12 Feet	MONITORING DEVICE: OVM (PID)	GEOLOGIST / OFFICE: J. Gagnon/Warren	
DRILLING CONTRACTOR / DRILLER: Zebra/ Matt		DRILLING EQUIPMENT: Geoprobe	DRILLING METHOD / BIT: Hollow Stem Push Rod	
SAMPLING METHOD: Acetate-Lined Macrocore	DEPTH TO GROUNDWATER: 12 Feet	GROUND SURFACE ELEVATION: NA	WELL INSTALLED? No	
MEMO: Boring located inside building 7.				

DEPTH (Feet)	RECOVERY (Feet)	OVM (PPM)	BURMEISTER SYSTEM SOIL DESCRIPTION Color, Texture, Moisture, Etc.	SAMPLES
0			Ground Surface	0
1	3.0	0.4	Asphalt fall in, fine silty SAND with coarse materials	1
2				2
3				3
4				4
5	4.0	0.2	Fine silty SAND with coarse materials, pieces of large rock	5
6				6
7				7
8				8
9	3.5	0	Fine silty SAND with coarse materials, pieces of large rock	9
10			Very coarse SAND with pebbles, rock, wet.	10
11				11
12				12
13			End of boring at 12' b.g.	13
14				14
15				15
16				16
17				17
18				18
19				19
20				20
21				21
22				22
23				23
24				24

SOIL BORING LOG

Page 1 of 1

		PROJECT NAME: Photocircuits	PROJECT NO.: 12080	Boring No: 45A-GW-6
		PROJECT LOCATION: 45A Seacliff Avenue, Glen Cove Long Island		LOCATION SKETCH 
COMPLETION DATE: 4/10/98	TOTAL DEPTH OF BOREHOLE: 12 Feet	MONITORING DEVICE: OVM (PID)	GEOLOGIST / OFFICE: J. Gagnon/Warren	
DRILLING CONTRACTOR / DRILLER: Zebra/ Matt	DRILLING EQUIPMENT: Geoprobe	DRILLING METHOD / BIT: Hollow Stem Push Rod		
SAMPLING METHOD: Acetate-Lined Macrocore	DEPTH TO GROUNDWATER: 12 Feet	GROUND SURFACE ELEVATION: NA	WELL INSTALLED? No	
MEMO: Boring located inside building 7.				

DEPTH (Feet)	RECOVERY (Feet)	OVM (PPM)	BURMEISTER SYSTEM SOIL DESCRIPTION Color, Texture, Moisture, Etc.	SAMPLES
0			Ground Surface	0
1	2.0	0	Asphalt fall in, medium brown silty SAND with coarse material and pebbles	1
2				2
3				3
4				4
5	3.0	0	Light brown/ tan fine to coarse SAND with gravel	5
6				6
7				7
8				8
9	4.0	0	Light brown/ tan fine to coarse SAND with gravel	9
10				10
11			Coarse SAND, wet	11
12				12
13			End of boring at 12' b.g.	13
14				14
15				15
16				16
17				17
18				18
19				19
20				20
21				21
22				22
23				23
24				24

SOIL BORING LOG

Page 1 of 1

		PROJECT NAME: Photocircuits		PROJECT NO.: 12080		Boring No: 45A-GW-7			
		PROJECT LOCATION: 45A Seacliff Avenue, Glen Cove Long Island				LOCATION SKETCH 			
COMPLETION DATE: 4/10/98		TOTAL DEPTH OF BOREHOLE: 12 Feet		MONITORING DEVICE: OVM (PID)				GEOLOGIST / OFFICE: J. Gagnon/Warren	
DRILLING CONTRACTOR / DRILLER: Zebra/ Matt		DRILLING EQUIPMENT: Geoprobe		DRILLING METHOD / BIT: Hollow Stem Push Rod					
SAMPLING METHOD: Acetate-Lined Macrocore		DEPTH TO GROUNDWATER: 12 Feet		GROUND SURFACE ELEVATION: NA				WELL INSTALLED? No	
MEMO: Boring located inside building 7.									

DEPTH (Feet)	RECOVERY (Feet)	OVM (PPM)	BURMEISTER SYSTEM SOIL DESCRIPTION Color, Texture, Moisture, Etc.	SAMPLES
0			Ground Surface	0
1	1.5	0	Asphalt fall in Medium brown coarse Sand with medium to fine gravel	1
2				2
3				3
4				4
5	1.5	0	Medium brown coarse Sand with medium to fine gravel	5
6				6
7				7
8				8
9	3.0	0	Coarse SAND with gravel and cobble	9
10				10
11				11
12				12
13			End of boring at 12' b.g.	13
14				14
15				15
16				16
17				17
18				18
19				19
20				20
21				21
22				22
23				23
24				24

SOIL BORING LOG

Page 1 of 1

		PROJECT NAME: Photocircuits		PROJECT NO.: 12080		Boring No: 45A-SB-31			
		PROJECT LOCATION: 45A Seaciff Avenue, Glen Cove Long Island				LOCATION SKETCH 			
COMPLETION DATE: 4/9/98		TOTAL DEPTH OF BOREHOLE: 24 Feet		MONITORING DEVICE: OVM (PID)				GEOLOGIST / OFFICE: J. Gagnon/Warren	
DRILLING CONTRACTOR / DRILLER: Zebra/ Matt		DRILLING EQUIPMENT: Geoprobe		DRILLING METHOD / BIT: Hollow Stem Push Rod					
SAMPLING METHOD: Acetate-Lined Macrocore		DEPTH TO GROUNDWATER: 24 Feet		GROUND SURFACE ELEVATION: NA				WELL INSTALLED? No	
MEMO: Boring located inside building 7.									

DEPTH (Feet)	RECOVERY (Feet)	OVM (PPM)	BURMEISTER SYSTEM SOIL DESCRIPTION Color, Texture, Moisture, Etc.	SAMPLES
0			Ground Surface	
1	2.0	1904	Concrete fall in, Very dark brwn Silty SAND	45A-SB-32-(0-4):
2				
3				
4				
5	3.0	708	Concrete fall in, Very dark brwn Silty SAND Light brwn tan soft SAND	45A-SB-33-(4-8):
6				
7				
8				
9	4.0	212	Light brwn/ tan soft SAND with pebbles and cobble	
10				
11				
12				
13	3.0	270	Soft light brwn/ tan SAND	
14			Silty medium brwn CLAY, moist	
15			Medium brwn SAND w/ trace clay	
16				
17	1.5	115	Fine light brwn SAND w/ trace clay	
18				
19	1.5	249	Fine light brwn SAND w/ trace clay	
20				
21	1.0	110	Fine light brwn SAND w/ trace clay, damp	
22				
23	1.0	105	Fine light brwn SAND w/ trace clay, damp	
24				

End of boring at 24' b.g.

SOIL BORING LOG

Page 1 of 1

		PROJECT NAME: Photocircuits	PROJECT NO.: 12080	Boring No: 45A-SB-32
		PROJECT LOCATION: 45A Seaciff Avenue, Glen Cove Long Island		LOCATION SKETCH 
COMPLETION DATE: 4/9/98	TOTAL DEPTH OF BOREHOLE: 24 Feet	MONITORING DEVICE: OVM (PID)	GEOLOGIST / OFFICE: J. Gagnon/Warren	
DRILLING CONTRACTOR / DRILLER: Zebra/ Matt		DRILLING EQUIPMENT: Geoprobe	DRILLING METHOD / BIT: Hollow Stem Push Rod	
SAMPLING METHOD: Acetate-Lined Macrocore	DEPTH TO GROUNDWATER: 22 Feet	GROUND SURFACE ELEVATION: NA	WELL INSTALLED? No	
MEMO: Boring located inside building 7.				

DEPTH (Feet)	RECOVERY (Feet)	OVM (PPM)	BURMEISTER SYSTEM SOIL DESCRIPTION Color, Texture, Moisture, Etc.	SAMPLES
0			Ground Surface	
1	2.5	1153	Dark brwn Silty SAND with little gravel and pebbles	45A-SB-32-(0-4):
2			Soft light brwn/ tan SAND with gravel and pebbles	
3				
4				
5	3.0	577	Concrete fall in Dark brwn Silty SAND with little gravel and pebbles	45A-SB-33-(4-8):
6			Soft light brwn/ tan SAND and PEBBLES	
7				
8				
9	4.0	N/A	Dark brwn Silty SAND with little gravel and pebbles	
10			Soft light brwn/ tan SAND and PEBBLES	
11				
12				
13	3.0	263	Soft light brwn/ tan SAND	
14			Silty SAND with trace clay, 4" lens stiff sand/ clay	
15			Soft tan SAND	
16				
17	1.0	728	Medium brwn SILTY CLAY, sandy silt w/ trace clay at bottom	
18				
19	2.0	514	Soft light brwn fine SAND	
20				
21	1.0	270	Damp fine light brown SAND	
22				
23	1.0	317	Wet fine light brown SAND	
24				

End of boring at 24' b.g.

SOIL BORING LOG

Page 1 of 1

		PROJECT NAME: Photocircuits		PROJECT NO.: 12080		Boring No: 45A-SB-33			
		PROJECT LOCATION: 45A Seacliff Avenue, Glen Cove Long Island				LOCATION SKETCH 			
COMPLETION DATE: 4/8/98		TOTAL DEPTH OF BOREHOLE: 28 Feet		MONITORING DEVICE: OVM (PID)				GEOLOGIST / OFFICE: J. Gagnon/Warren	
DRILLING CONTRACTOR / DRILLER: Zebra/ Matt		DRILLING EQUIPMENT: Geoprobe		DRILLING METHOD / BIT: Hollow Stem Push Rod					
SAMPLING METHOD: Acetate-Lined Macrocore		DEPTH TO GROUNDWATER: 22 Feet		GROUND SURFACE ELEVATION: NA				WELL INSTALLED? No	
MEMO: Boring located inside building 7.									

DEPTH (Feet)	RECOVERY (Feet)	OVM (PPM)	BURMEISTER SYSTEM SOIL DESCRIPTION Color, Texture, Moisture, Etc.	SAMPLES	
0			Ground Surface		0
1	3.0	519	Concrete fall in, fine SAND with fine to med gravel, med brwn/ tan 4" lens near bottom with pieces of black sand with trace clay	45A-SB-33-(0-4):	1
2					2
3					3
4					4
5	3.0	217	Back fill material Med brwn to tan fine to coarse SAND, with med gravel and some pebbles and cobble	45A-SB-33-(4-8):	5
6					6
7					7
8					8
9	4.0	405	Back fill material and concrete fall in Med brwn to tan fine SAND		9
10					10
11					11
12					12
13	3.0	1579	Fine to coarse tan to med brwn SAND	45A-SB-33-(12-16):	13
14					14
15			Silty SAND with trace clay		15
16					16
17	3.0	197	Fine tan SAND soft, trace clay	45A-SB-33-(16-20):	17
18					18
19					19
20					20
21	2.0	229	Damp fine tan SAND		21
22					22
23	2.0	297	WET fine tan SAND		23
24					24

End of boring at 28' b.g.

SOIL BORING LOG

Page 1 of 1

		PROJECT NAME: Photocircuits		PROJECT NO.: 12080		Boring No: 31-SB-1			
		PROJECT LOCATION: 31 Seacliff Avenue, Glen Cove Long Island				LOCATION SKETCH 			
COMPLETION DATE: 4/20/98		TOTAL DEPTH OF BOREHOLE: 8 Feet		MONITORING DEVICE: OVM (PID)				GEOLOGIST / OFFICE: J. Gagnon/Warren	
DRILLING CONTRACTOR / DRILLER: McLaren/ Hart/ J. Lute		DRILLING EQUIPMENT: Geoprobe		DRILLING METHOD / BIT: Hollow Stem Push Rod					
SAMPLING METHOD: Acetate-Lined Macrocore		DEPTH TO GROUNDWATER: 8 Feet		GROUND SURFACE ELEVATION: NA				WELL INSTALLED? No	
MEMO: Boring located									

DEPTH (Feet)	RECOVERY (Feet)	OVM (PPM)	BURMEISTER SYSTEM SOIL DESCRIPTION Color, Texture, Moisture, Etc.	SAMPLES
0			Ground Surface: Asphalt	0
1	3.0	0.7	Asphalt fall in, Black/ dark brown fine SAND with coarse material	1
2			Medium brown fine SAND with coarse material, pebbles trace cobble	2
3			Coarse damp fine SAND	3
4			Silty SAND with little black clay and cobble	4
5	3.0	3.7	Wet, very coarse black SAND with pebbles and cobble	5
6				6
7				7
8				8
9			End of boring at 8' b.g.	9
10				10
11				11
12				12
13				13
14				14
15				15
16				16
17				17
18				18
19				19
20				20
21				21
22				22
23				23
24				24

SOIL BORING LOG

Page 1 of 1

		PROJECT NAME: Photocircuits		PROJECT NO.: 12080		Boring No: 31-SB-2			
		PROJECT LOCATION: 31 Seacliff Avenue, Glen Cove Long Island				LOCATION SKETCH 			
COMPLETION DATE: 4/20/98		TOTAL DEPTH OF BOREHOLE: 8 Feet		MONITORING DEVICE: OVM (PID)				GEOLOGIST / OFFICE: J. Gagnon/Warren	
DRILLING CONTRACTOR / DRILLER: McLaren/ Hart/ J. Lute		DRILLING EQUIPMENT: Geoprobe		DRILLING METHOD / BIT: Hollow Stem Push Rod					
SAMPLING METHOD: Acetate-Lined Macrocore		DEPTH TO GROUNDWATER: 8 Feet		GROUND SURFACE ELEVATION: NA				WELL INSTALLED? No	
MEMO: Boring located									

DEPTH (Feet)	RECOVERY (Feet)	OVM (PPM)	BURMEISTER SYSTEM SOIL DESCRIPTION Color, Texture, Moisture, Etc.	SAMPLES
0			Ground Surface: Asphalt	0
1	2.0	24.7	Light brown fine SAND with some coarse material and pebbles 2" lens of white quartz rock	1
2			Black very coarse SAND with pebbles	2
3				3
4				4
5	3.0	18.9	Wet, coarse material small pebbles very little sand	5
6			Black very coarse sand with pebbles and cobble mixed throughout	6
7				7
8				8
9			End of boring at 8' b.g.	9
10				10
11				11
12				12
13				13
14				14
15				15
16				16
17				17
18				18
19				19
20				20
21				21
22				22
23				23
24				24

SOIL BORING LOG

Page 1 of 1

		PROJECT NAME: Photocircuits		PROJECT NO.: 12080		Boring No: 31-SB-3			
		PROJECT LOCATION: 31 Seacliff Avenue, Glen Cove Long Island				LOCATION SKETCH 			
COMPLETION DATE: 4/20/98		TOTAL DEPTH OF BOREHOLE: 12 Feet		MONITORING DEVICE: OVM (PID)				GEOLOGIST / OFFICE: J. Gagnon/Warren	
DRILLING CONTRACTOR / DRILLER: McLaren/ Hart/ J. Lute		DRILLING EQUIPMENT: Geoprobe		DRILLING METHOD / BIT: Hollow Stem Push Rod					
SAMPLING METHOD: Acetate-Lined Macrocore		DEPTH TO GROUNDWATER: 8 Feet		GROUND SURFACE ELEVATION: NA				WELL INSTALLED? No	
MEMO: Boring located									

DEPTH (Feet)	RECOVERY (Feet)	OVM (PPM)	BURMEISTER SYSTEM SOIL DESCRIPTION Color, Texture, Moisture, Etc.	SAMPLES
0			Ground Surface: Asphalt	0
1	3.0	11.7	Asphalt and white coarse SAND mixed with cobble	1
2			Black Silty SAND and CLAY, pebbles	2
3			Damp fine light brown tan SAND with trace clay	3
4				4
5	3.5	13	Fine to coarse light brown SAND, trace gravel damp	5
6				6
7				7
8				8
9	4.0	0	Wet, very coarse to fine light brown tan SAND with pebbles, gravel	9
10				10
11				11
12				12
13			End of boring at 12' b.g.	13
14				14
15				15
16				16
17				17
18				18
19				19
20				20
21				21
22				22
23				23
24				24

SOIL BORING LOG

Page 1 of 1

		PROJECT NAME: Photocircuits		PROJECT NO.: 12080		Boring No: 31-SB-4	
		PROJECT LOCATION: 31 Seacliff Avenue, Glen Cove Long Island					
COMPLETION DATE: 4/20/98	TOTAL DEPTH OF BOREHOLE: 12 Feet	MONITORING DEVICE: OVM (PID)		GEOLOGIST / OFFICE: J. Gagnon/Warren			
DRILLING CONTRACTOR / DRILLER: McLaren/ Hart/ J. Lute		DRILLING EQUIPMENT: Geoprobe		DRILLING METHOD / BIT: Hollow Stem Push Rod			
SAMPLING METHOD: Acetate-Lined Macrocore	DEPTH TO GROUNDWATER: 8 Feet	GROUND SURFACE ELEVATION: NA		WELL INSTALLED? No			
MEMO: Boring located							

DEPTH (Feet)	RECOVERY (Feet)	OVM (PPM)	BURMEISTER SYSTEM SOIL DESCRIPTION Color, Texture, Moisture, Etc.	SAMPLES
0			Ground Surface: Asphalt	
1	2.0	14.3	Very dark brown silty SAND, moist	
2			Very dark brown silty SAND with pebbles and cobble, moist	
3			Fine to coarse light brown/ tan SAND with pebbles and other coarse material	
4				
5	4.0	11.1	Very firm gray/ tan SANDY CLAY little coarse material	
6				
7			Red/ medium brown silty SAND, little clay	
8				
9	2.0	11.1	Wet, COBBLE	
10			Red to medium brown fine silty SAND some pebbles and cobble	
11				
12			Medium brown coarse to fine SAND with cobble and pebbles	
13			End of boring at 12' b.g.	
14				
15				
16				
17				
18				
19				
20				
21				
22				
23				
24				

SOIL BORING LOG

Page 1 of 1

		PROJECT NAME: Photocircuits	PROJECT NO.: 12080	Boring No: 31-SB-5
		PROJECT LOCATION: 31 Seacliff Avenue, Glen Cove Long Island		LOCATION SKETCH 
COMPLETION DATE: 4/20/98	TOTAL DEPTH OF BOREHOLE: 12 Feet	MONITORING DEVICE: QVM (PID)	GEOLOGIST / OFFICE: J. Gagnon/Warren	
DRILLING CONTRACTOR / DRILLER: McLaren/ Hart/ J. Lute	DRILLING EQUIPMENT: Geoprobe	DRILLING METHOD / BIT: Hollow Stem Push Rod		
SAMPLING METHOD: Acetate-Lined Macrocore	DEPTH TO GROUNDWATER: 8 Feet	GROUND SURFACE ELEVATION: NA	WELL INSTALLED? No	
MEMO: Boring located				

DEPTH (Feet)	RECOVERY (Feet)	QVM (PPM)	BURMEISTER SYSTEM SOIL DESCRIPTION Color, Texture, Moisture, Etc.	SAMPLES
0			Ground Surface: Asphalt	0
1	3.0	12.4	Red to light brown SAND with cobble	1
2				2
3			Tan to light brown silty SAND with cobble and pebbles	3
4				4
5	3.0	18.3	Very coarse SAND with coarse materials	5
6				6
7			Red to brown on outside- inside light grey firm CLAY and SAND	7
8				8
9			End of boring at 8' b.g.	9
10				10
11				11
12				12
13				13
14				14
15				15
16				16
17				17
18				18
19				19
20				20
21				21
22				22
23				23
24				24

SOIL BORING LOG

Page 1 of 1

		PROJECT NAME: Photocircuits		PROJECT NO.: 12080		Boring No: 31-SB-6		
		PROJECT LOCATION: 31 Seacliff Avenue, Glen Cove Long Island						LOCATION SKETCH 
COMPLETION DATE: 4/20/98		TOTAL DEPTH OF BOREHOLE: 12 Feet		MONITORING DEVICE: OVM (PID)		GEOLOGIST / OFFICE: J. Gagnon/Warren		
DRILLING CONTRACTOR / DRILLER: McLaren/ Hart/ J. Lute		DRILLING EQUIPMENT: Geoprobe		DRILLING METHOD / BIT: Hollow Stem Push Rod				
SAMPLING METHOD: Acetate-Lined Macrocore		DEPTH TO GROUNDWATER: 8 Feet		GROUND SURFACE ELEVATION: NA		WELL INSTALLED? No		
MEMO: Boring located								

DEPTH (Feet)	RECOVERY (Feet)	OVM (PPM)	BURMEISTER SYSTEM SOIL DESCRIPTION Color, Texture, Moisture, Etc.	SAMPLES
0			Ground Surface: Asphalt	0
1	2.5	0	Dark Brown SILT with cobbles and pebbles.	1
2				2
3				3
4				4
5	3.0	0	Dark Brown SILT with cobbles and pebbles. Coarse SAND (like beach sand) with coarse materials.	5
6				6
7				7
8				8
9			Coarse SAND (like beach sand) with coarse materials, wet	9
10				10
11				11
12				12
13			End of boring at 12' b.g.	13
14				14
15				15
16				16
17				17
18				18
19				19
20				20
21				21
22				22
23				23
24				24

SOIL BORING LOG

Page 1 of 1

		PROJECT NAME: Photocircuits	PROJECT NO.: 12080	Boring No: 31-SB-7
		PROJECT LOCATION: 31 Seacliff Avenue, Glen Cove Long Island		LOCATION SKETCH 
COMPLETION DATE: 4/20/98	TOTAL DEPTH OF BOREHOLE: 8 Feet	MONITORING DEVICE: OVM (PID)	GEOLOGIST / OFFICE: J. Gagnon/Warren	
DRILLING CONTRACTOR / DRILLER: McLaren/ Hart/ J. Lute		DRILLING EQUIPMENT: Geoprobe	DRILLING METHOD / BIT: Hollow Stem Push Rod	
SAMPLING METHOD: Acetate-Lined Macrocore	DEPTH TO GROUNDWATER: 6 Feet	GROUND SURFACE ELEVATION: NA	WELL INSTALLED? No	
MEMO: Boring located				

DEPTH (Feet)	RECOVERY (Feet)	OVM (PPM)	BURMEISTER SYSTEM SOIL DESCRIPTION Color, Texture, Moisture, Etc.	SAMPLES
0			Ground Surface: Asphalt	0
1	3.0	2.1	Black silty SAND and CLAY with pebbles	1
2				2
3			Damp, coarse SAND with coarse materials	3
4				4
5	4.0	0	USE AS A GEOTECHNICAL SAMPLE	5
6				6
7				7
8				8
9			End of boring at 8' b.g.	9
10				10
11				11
12				12
13				13
14				14
15				15
16				16
17				17
18				18
19				19
20				20
21				21
22				22
23				23
24				24



Central Jersey Industrial Park
Chimney Rock Road, Bldg. 9W
Bound Brook, NJ 08805
Telephone: (908) 722-4266
Toll Free: (800) 242-6648
FAX: (732) 356-1009

WELL LOG

WELL: MW# DATE DRILLED: 04/22/1998 CCORD #1:
 COCRD #2:

SITE: Photocircuits Corp, 11 Sea Cliff Avenue, , Glen Cove, NY
OWNER: Photocircuits Corp, 11 Sea Cliff Avenue, , Glen Cove, NY

PERMIT #1 :
PERMIT #2 :

COUNTY:
XSTREET:
USE: MONICOX

INNER CASING: PVC
DIAMETER: 4"
LENGTH: 4'

OUTER CASING:
DIAMETER:
LENGTH:

```
SCREEN TYPE 1: PVC
SCREEN TYPE 2:
DIAMETER: 4"
LENGTH 1: 10'
LENGTH 2:
SLOT SIZE: .02
```

DRILLING METHOD: Air Rotary
SAMPLING METHOD:
HOLE DIA: 3", 3"
TOTAL DEPTH: 14'

SET WELL: 14'
GRAVEL PK SZ: Morie #2
DRILLER: Carmine DeCorso
SURFACE COMPLETION: M

GAL PER MIN: 3-5
STAT H2O LVL: 9'

DEVELOPMENT METHOD: Pump CASING SEAL: Portland
DEVELOPMENT TIME: 1/4 Hour OPEN HOLE:

DEPTH BELOW SURFACE FROM - TO	BLOWS PER 6" ON SAMPLER
0 - 1	10
1 - 2	12
2 - 3	15
3 - 4	18
4 - 5	20
5 - 6	22
6 - 7	25
7 - 8	28
8 - 9	30
9 - 10	32
10 - 11	35
11 - 12	38
12 - 13	40
13 - 14	42
14 - 15	45
15 - 16	48
16 - 17	50
17 - 18	52
18 - 19	55
19 - 20	58
20 - 21	60
21 - 22	62
22 - 23	65
23 - 24	68
24 - 25	70
25 - 26	72
26 - 27	75
27 - 28	78
28 - 29	80
29 - 30	82
30 - 31	85
31 - 32	88
32 - 33	90
33 - 34	92
34 - 35	95
35 - 36	98
36 - 37	100
37 - 38	102
38 - 39	105
39 - 40	108
40 - 41	110
41 - 42	112
42 - 43	115
43 - 44	118
44 - 45	120
45 - 46	122
46 - 47	125
47 - 48	128
48 - 49	130
49 - 50	132
50 - 51	135
51 - 52	138
52 - 53	140
53 - 54	142
54 - 55	145
55 - 56	148
56 - 57	150
57 - 58	152
58 - 59	155
59 - 60	158
60 - 61	160
61 - 62	162
62 - 63	165
63 - 64	168
64 - 65	170
65 - 66	172
66 - 67	175
67 - 68	178
68 - 69	180
69 - 70	182
70 - 71	185
71 - 72	188
72 - 73	190
73 - 74	192
74 - 75	195
75 - 76	198
76 - 77	200
77 - 78	202
78 - 79	205
79 - 80	208
80 - 81	210
81 - 82	212
82 - 83	215
83 - 84	218
84 - 85	220
85 - 86	222
86 - 87	225
87 - 88	228
88 - 89	230
89 - 90	232
90 - 91	235
91 - 92	238
92 - 93	240
93 - 94	242
94 - 95	245
95 - 96	248
96 - 97	250
97 - 98	252
98 - 99	255
99 - 100	258

REMARKS / SOILS IDENTIFICATION

0' - 1' Asphalt & road stone.
1' - 14' Brown & tan m/f sand trace m/f
grave trace silt.

Ground Surface

At-Grade Protective Weatheright Manhole

Locking Compression Cap

2' x 2' Concrete Pad
Travel Mix Concrete

PVC Casing
1" Diameter

Year Cement Grout
ASTM Type II, 5# Bentonite Added
2' - 3'

PVC Screen
1" Diameter

Travel Pack
2 - 14'

Bore Hole
3", 8" Diameter

Section C-20

TOTAL P.02

Appendix B

To be submitted separately

Appendix C

Geotechnical Testing Results

UNDISTURBED SAMPLE LOG

Boring No.:

Job No.: 1434-0014-03

Sample No. & Depth: 45A-GW-1 12'-16'

Project: MCLAREN HART
(GLEN COVE, NY)

Recovery: 44"

Date Tested: 4/23/98

Sample Method: GEOPROBE

Tested By: LL

Date of Sample: 4/8/98

Checked By: DA

Testing Notes: SEE BELOW

~ BURMISTER ~
Soil Classification

Depth Length (inches)

Tube	Sample	
48		
46		
44		
42		
40	7"	Tan c-f SAND, tr. Silt, tr. to little m-f Gravel
38		
36	3"	dk gray, br c-f SAND, tr. Silt, some c-f Gravel
34		
32		
30		
28		
26		
24		
22	24"	Tan c-m-f SAND, tr. Silt, some m-f Gravel
20		K, GSD, Gs, TOC, & etc. (10"-33")
18		
16		
14		
12		
10		
8		
6		
4	10"	Tan m-f SAND, tr. Silt, tr. f Gravel
2		

Remarks: SAVED BOT. 9"

UNDISTURBED SAMPLE LOG

Boring No.:

Job No.: 1434-0014-03

Sample No. & Depth: 45A-GW-4 Depth?

Project: McLAREN HART
(GLEN COVE, NY)

Recovery: 45"

Date Tested: 4/24/98

Sample Method: GEOPROBE

Tested By: LL

Date of Sample: 4/10/98

Checked By: DA

Testing Notes: SEE BELOW

~ BURMISTER ~
Soil Classification

Depth Length (inches)

Tube

Sample

48		
46		
44		
42		
40		
38	13"	lt. tan c-f SAND, tr. silt, little to some m-f Gravel
36		
34		
32		
30	5"	dk orange tan c-m-f SAND, tr. silt, tr. f Gravel
28		
26		
24		
22		
20		
18		
16	22"	lt. tan bec. tan br c-f SAND, tr. silt, some m-f Gravel
14		K, GSD, Gs, TOC, etc. (6" - 26")
12		
10		color change
8		1/8" thick dk gray m-f SAND layer
6		
4		
2	5"	gray tan c-f SAND, tr. silt, some c-f Gravel

Remarks: SAVED 11 1/2" OF TOP 13"

UNDISTURBED SAMPLE LOG

Boring No.:

Job No.: 1434-0014-03

Sample No. & Depth: 454-32 8'-12'

Project: McLAREN HART
(GLEN COVE, NY)

Recovery: 42"

Date Tested: 4/24/98

Sample Method: GEOPROBE

Tested By: LL

Date of Sample: 4/9/98

Checked By: DA

Testing Notes: SEE BELOW

~ BURMISTER ~

Depth Length (inches)

Soil Classification

Tube	Sample	
48		
46		
44		
42		
40	6"	Tan orange m-f SAND, tr. silt, tr. m-f Gravel
38		
36		
34		
32		
30		
28		
26	22"	Tan br. c-f SAND, tr. silt, some m-f Gravel
24		K, GSD, Gs, TOC, & etc (15"-35")
22		
20		
18		
16		
14		
12	5"	Tan gray m-f SAND, tr. silt, tr. f Gravel
10		
8		
6	9"	lt. gray br. c-f SAND, little silt, little m-f Gravel w/ concrete frags.
4		
2		

Remarks: a. JAR SAMPLE SAVED OF PORTION FROM 0"-9"
b. CONTENTS OF TUBE LOOSE 0"-42"

UNDISTURBED SAMPLE LOG

Boring No.:

Job No.: 1434-0014-03

Sample No. & Depth: 45A-GW-3 8'-12'

Project: MCLAREN HART
(GLEN COVE, N.Y.)

Recovery: 44"

Date Tested: 4/24/98

Sample Method: GEOPROBE

Tested By: LL

Date of Sample: 4/10/98

Checked By: DA

Testing Notes: SEE BELOW

~ BURMISTER ~
Soil Classification

Depth Length (inches)

Tube	Sample	
48		
46		
44		
42		
40		
38		
36		
34		
32		
30		
28		
26	35"	Tan br. c+-f SAND, tr. silt, little m-f Gravel
24		K, GSD, Gs, TOC, 8d etc (14"-32")
22		
20		
18		
16		
14		
12		
10		
8		
6	9"	Lt. gray br. c-m-f SAND, tr+silt, little f Gravel, occasional
4		concrete frags.
2		

Remarks: @ BOTTOM 9" LOOSE

⑤ SAVED TOP 9" (33"-42")

UNDISTURBED SAMPLE LOG

Boring No.:

Job No.: 1434-0014-03

Sample No. & Depth: 31-3B-0 4'-8'

Project: MCLAREN HART
(GLEN COVE, NY)

Recovery: 38"

Date Tested: 4/27/98

Sample Method: GEOPROBE

Tested By: LL

Date of Sample: 4/20/98

Checked By: DA

Testing Notes: SEE BELOW

~ BURMISTER ~

Depth

Length (inches)

Soil Classification

Tube	Sample	
48		
46		
44		
42		
40		
38	3"	olive gray m-f SAND, little silt
36		
34	8"	DR tan br, olive micaceous c-f SAND, little clayey silt, some
32		c-f Gravel (Gravel = Mica Schist)
30		
28		
26		
24		
22		
20		
18	27"	Tan, gray br. c-m-f SAND, little silt, some c-f Gravel
16		K, GSD, Gs, TOC, 8d (2"-25")
14		
12		
10		
8		
6		
4		
2		

Remarks: JAR SAMPLE SAVED OF PORTION FROM 27"-35"

UNDISTURBED SAMPLE LOG

Boring No.:

Job No.: 1434-0014-03

Sample No. & Depth: 31-SB-1 0'-4'

Project: MCLAREN HART
(GLEN COVE, NY)

Recovery: 28"

Date Tested: 4/27/98

Sample Method: GEOPROBE

Tested By: LL

Date of Sample: 4/20/98

Checked By: DA

Testing Notes: SEE BELOW

~ BURMISTER ~

Depth Length (inches)

Soil Classification


Tube	Sample	
48		
46		
44		
42		
40		
38		
36		
34		
32		
30		
28		
26		
24	8 1/2"	> Blk c-f SAND, little silt, some c-f Gravel, occasional asphalt; cinder frags
22		
20		
18		
16		
14		
12	16 1/2"	> Tan br. bec. gray br. c-m-f SAND, tr. silt, some m-f Gravel K, GSD, GS, TOC, 8d (4" - 19 1/2")
10		
8		
6		> color change
4		
2	3"	> Blk. m-f sand, some organic clayey silt, some c-f Gravel, occasional roots; organic matter.

Remarks:


ⓐ TOP 8 1/2" LOOSE

ⓑ JAR SAMPLE SAVED OF BOT. 3"

GRAIN-SIZE DISTRIBUTION




BORING	SAMPLE	DEPTH	SYMBOL	CLASSIFICATION	MC	LL	PL
45A	GW-1	12'-16'		TANC ⁺ -f SAND, tr. silt, some m-f+Gravel	4.8	~	~




BORING	SAMPLE	DEPTH	SYMBOL	CLASSIFICATION	MC	LL	PL
45A	GW-4	?		Lt. tanc ⁺ -f SAND, tr. silt, some ⁺ m-f+Gravel	5.6	~	~

PROJ. NO. ~ 1434-0014-03 ~

GRAIN - SIZE DISTRIBUTION



BORING	SAMPLE	DEPTH	SYMBOL	CLASSIFICATION	MC	LL	PL
45A-	32	B'-12'		Tan br. c+f SAND, tr. SILT, some m-f+GRAVEL	1.2	~	~






BORING	SAMPLE	DEPTH	SYMBOL	CLASSIFICATION	MC	LL	PL
45A-GW-	3	B'-12'		Tan br. c+f SAND, tr. SILT, little m-f+GRAVEL	2.6	~	~

~ 1434-0014-03 ~

5/15/98

GRAIN - SIZE DISTRIBUTION



 PR 10
 ~ 1434-0014-03 ~



TOTAL ORGANIC CARBON
(ASTM D 2974) LOSS ON IGNITION METHOD

TEST RESULTS

SAMPLE NO.	% ORGANIC MATTER
45A-6W-1	0.30
45A-6W-3	0.19
45A-6W-4	0.22
45A-32	0.19
31-SB-1	0.65
31-SB-6	0.45



**PAULUS
SOKOLOWSKI
and SARTOR, INC.
CONSULTING ENGINEERS**


MC LAREN HART
JOB. NO. 1434-0014-03PROJ
GLEN COVE, N.Y.

DATE 5/15/98


SAMPLE #	TAKE #	WGT. TAKE (WET SOIL)	WGT. TAKE (DRY SOIL)	WGT. WATER	WGT. TAKE	WGT. DRY SOIL	MOIST. %	~ DENSITY ~										~ MOIST. CONT. ~																												
								DENSITY SAMPLE	RECONSTD K SAMPLE	DENSITY SAMPLE	RECONSTD K SAMPLE	TAKE	WGT. TAKE (WET SOIL)	WGT. TAKE (DRY SOIL)	WGT. WATER	WGT. TAKE	WGT. DRY SOIL	MOIST. %	WGT. TAKE (WET SOIL)	WGT. TAKE (DRY SOIL)	WGT. WATER	WGT. TAKE	WGT. DRY SOIL	MOIST. %																						
31-SB-6	28	919.2	1040.6	777.8	1073.3	1016.5	60.8	431.2	110.0	607.0	585.3	9.7	10.0	10.0	110.0	425.2	745.3	565.1	8.6	8.9	10.0	9.7	1073.3	777.8	110.0	431.2	607.8	642.1	2.93	1.69	2.875	0.0114	0.0110	128.7	9.7	117.3	2.69	0.431	62.6%	0.301	0.301	0.244	0.245	3.8x10 ⁻⁴	-	8.4x10 ⁻⁴
31-SB-1	29	777.8	1073.3	1016.5	56.8	431.2	110.0	607.0	585.3	9.7	10.0	10.0	110.0	425.2	745.3	565.1	8.6	8.9	10.0	9.7	1073.3	777.8	110.0	431.2	607.8	642.1	2.93	1.69	2.875	0.0114	0.0110	128.7	9.7	117.3	2.69	0.431	62.6%	0.301	0.301	0.244	0.245	3.8x10 ⁻⁴	-	8.4x10 ⁻⁴		

Appendix D

Slug Test Raw Data And Calculations




0.1083	1.227	1
0.1166	0.811	1
0.1333	0.726	1
0.15	0.556	1
0.175	0.509	1
0.2083	0.453	1
0.2166	0.405	1
0.2416	0.358	1
0.25	0.311	1
0.2583	0.302	1
0.2833	0.217	1
0.2916	0.33	1
0.3	0.33	1
0.3083	0.245	1
0.3166	0.377	1
0.325	0.396	1
0.3333	0.386	1
0.3666	0.273	1
0.3833	0.349	1




0.0083	1.416	1
0.0166	1.283	1
0.025	1.227	1
0.0333	1.198	1
0.0416	1.189	1
0.05	1.151	1
0.0583	1.151	1
0.0666	1.095	1
0.075	1.01	1
0.0833	1.066	1
0.0916	1.028	1
0.1	1	1
0.1083	0.991	1
0.1166	0.925	1
0.125	0.934	1
0.1333	0.925	1
0.1416	0.925	1
0.15	0.859	1
0.1583	0.877	1
0.1666	0.717	1
0.175	0.802	1
0.1833	0.877	1
0.2	0.67	1
0.2083	0.943	1
0.2166	0.981	1
0.225	0.651	1
0.2333	0.632	1
0.2416	0.755	1
0.25	0.707	1
0.2583	0.67	1
0.2666	0.66	1
0.275	0.651	1
0.2833	0.641	1
0.2916	0.632	1
0.3	0.622	1
0.3083	0.604	1
0.3166	0.594	1
0.325	0.585	1
0.3333	0.594	1
0.35	0.556	1
0.3666	0.528	1
0.3833	0.519	1
0.4	0.5	1
0.4166	0.471	1
0.4333	0.462	1
0.45	0.33	1
0.4666	0.434	1
0.4833	0.302	1
0.5	0.358	1
0.5166	0.405	1
0.5333	0.462	1

0.55	0.32	1
0.5666	0.292	1
0.5833	0.405	1
0.6	0.358	1
0.6166	0.424	1
0.6333	0.311	1
0.65	0.358	1
0.6666	0.254	1
0.7	0.273	1
0.7166	0.273	1
0.7333	0.264	1
0.75	0.245	1
0.7666	0.245	1
0.7833	0.245	1
0.8	0.226	1
0.8166	0.613	1
0.8333	0.245	1
0.85	0.226	1
0.8666	0.018	1
0.8833	0.311	1
0.9	0.198	1
0.9166	0.198	1
0.9333	0.179	1
0.95	0.179	1
0.9666	0.169	1
0.9833	0.169	1
1	0.169	1
1.2	0.113	1
1.4	0.075	1
1.6	0.056	1
1.8	0.047	1
2	0.037	1
2.2	0.028	1
2.4	0.018	1
2.6	0.009	1
2.8	0.009	1
3	0	1
3.2	0.009	1
3.4	0.009	1
3.6	0	1



0.1083	2.42	1
0.1166	2.278	1
0.125	1.796	1
0.1333	1.768	1
0.1416	1.815	1
0.15	1.494	1
0.1583	1.853	1
0.1666	1.579	1
0.175	1.702	1
0.1833	0.425	1
0.1916	1.664	1
0.2	1.267	1
0.2083	1.437	1
0.2166	1.361	1
0.225	1.361	1
0.2333	1.371	1
0.2416	1.191	1
0.25	1.361	1
0.2583	1.286	1
0.2666	1.295	1
0.275	1.276	1
0.2833	1.267	1
0.2916	1.257	1
0.3	1.238	1
0.3083	1.229	1
0.3166	1.219	1
0.325	1.2	1
0.3333	1.191	1
0.35	1.172	1
0.3666	1.153	1
0.3833	1.134	1
0.4	1.096	1
0.4166	1.077	1
0.4333	1.059	1
0.45	1.04	1
0.4666	1.021	1
0.4833	1.011	1
0.5	0.983	1
0.5166	0.973	1
0.5333	0.955	1
0.55	0.936	1
0.5666	0.917	1
0.5833	0.898	1
0.6	0.879	1
0.6166	0.869	1
0.6333	0.851	1
0.65	0.841	1
0.6666	0.822	1
0.6833	0.813	1
0.7	0.813	1
0.7166	0.803	1


0.7333	0.784	1
0.75	0.775	1
0.7666	0.765	1
0.7833	0.747	1
0.8	0.737	1
0.8166	0.718	1
0.8333	0.718	1
0.85	0.709	1
0.8666	0.69	1
0.8833	0.69	1
0.9	0.68	1
0.9166	0.671	1
0.9333	0.661	1
0.95	0.652	1
0.9666	0.652	1
0.9833	0.633	1
1	0.614	1
1.2	0.529	1
1.4	0.444	1
1.6	0.378	1
1.8	0.321	1
2	0.274	1
2.2	0.227	1
2.4	0.198	1
2.6	0.179	1
2.8	0.151	1
3	0.132	1
3.2	0.113	1
3.4	0.104	1
3.6	0.085	1
3.8	0.085	1
4	0.066	1
4.2	0.056	1
4.4	0.047	1
4.6	0.047	1
4.8	0.028	1
5	0.028	1
5.2	0.028	1
5.4	0.019	1
5.6	0.019	1
5.8	0.019	1
6	0.019	1
6.2	0.009	1
6.4	0.009	1
6.6	0.009	1
6.8	0.009	1
7	0	1
7.2	0	1




0.0833	3.116	1
0.0916	2.918	1
0.1	2.36	1
0.1083	2.275	1
0.1166	2.228	1
0.125	2.105	1
0.1333	2.002	1
0.1416	1.888	1
0.15	2.332	1
0.1583	2.105	1
0.1666	2.115	1
0.175	2.049	1
0.1833	2.039	1
0.1916	2.039	1
0.2	2.058	1
0.2083	2.011	1
0.2166	2.039	1
0.225	2.058	1
0.2333	2.077	1
0.2416	2.03	1
0.25	2.077	1
0.2583	2.058	1
0.2666	1.964	1
0.275	2.049	1
0.2833	1.983	1
0.2916	2.039	1
0.3	2.058	1
0.3083	2.002	1
0.3166	2.039	1
0.325	2.03	1
0.3333	2.068	1
0.35	2.02	1
0.3666	2.011	1
0.3833	2.03	1
0.4	1.935	1
0.4166	2.02	1
0.4333	2.011	1
0.45	2.002	1
0.4666	1.964	1
0.4833	1.983	1
0.5	2.049	1
0.5166	1.992	1
0.5333	1.992	1
0.55	1.983	1
0.5666	2.068	1
0.5833	1.794	1
0.6	1.964	1
0.6166	2.19	1
0.6333	1.983	1
0.65	1.964	1
0.6666	1.935	1

0.6833	1.945	1
0.7	2.115	1
0.7166	2.002	1
0.7333	1.888	1
0.75	1.954	1
0.7666	1.954	1
0.7833	1.964	1
0.8	1.879	1
0.8166	1.954	1
0.8333	1.917	1
0.85	1.917	1
0.8666	1.983	1
0.8833	1.926	1
0.9	1.983	1
0.9166	2.002	1
0.9333	1.983	1
0.95	2.049	1
0.9666	1.935	1
0.9833	1.954	1
1	1.926	1
1.2	1.926	1
1.4	1.898	1
1.6	1.879	1
1.8	1.86	1
2	1.841	1
2.2	1.841	1
2.4	1.822	1
2.6	1.803	1
2.8	1.794	1
3	1.775	1
3.2	1.765	1
3.4	1.756	1
3.6	1.747	1
3.8	1.737	1
4	1.728	1
4.2	1.709	1
4.4	1.699	1
4.6	1.69	1
4.8	1.671	1
5	1.662	1
5.2	1.652	1
5.4	1.652	1
5.6	1.643	1
5.8	1.624	1
6	1.614	1
6.2	1.605	1
6.4	1.595	1
6.6	1.586	1
6.8	1.577	1
7	1.558	1
7.2	1.548	1

7.4	1.539	1
7.6	1.529	1
7.8	1.52	1
8	1.51	1
8.2	1.501	1
8.4	1.492	1
8.6	1.482	1
8.8	1.473	1
9	1.463	1
9.2	1.454	1
9.4	1.444	1
9.6	1.435	1
9.8	1.425	1
10	1.416	1
11	1.369	1
12	1.322	1
13	1.274	1
14	1.237	1
15	1.199	1




0.075	2.639	1
0.0833	2.501	1
0.1	1.967	1
0.1166	1.344	1
0.1333	1.049	1
0.1666	1.03	1
0.175	0.911	1
0.2083	0.873	1
0.2166	0.741	1
0.2833	0.672	1
0.2916	0.653	1
0.3083	0.584	1
0.325	0.571	1
0.3333	0.553	1
0.35	0.521	1
0.3666	0.496	1
0.3833	0.414	1
0.4333	0.408	1
0.45	0.383	1
0.4666	0.358	1
0.5166	0.289	1
0.55	0.276	1
0.5666	0.263	1
0.6	0.232	1
0.6166	0.213	1
0.7	0.207	1
0.7166	0.182	1
0.7333	0.169	1
0.75	0.163	1
0.7666	0.157	1
0.7833	0.144	1
0.8	0.144	1
0.8166	0.138	1
0.8333	0.131	1
0.85	0.125	1
0.8666	0.119	1
0.8833	0.113	1
0.9	0.106	1
0.9166	0.1	1
0.9333	0.094	1
0.95	0.094	1
0.9666	0.087	1
0.9833	0.087	1
1	0.081	1
1.2	0.05	1
1.4	0.025	1
1.6	0.012	1
1.8	0	1



0.1166	2.394	1
0.125	2.3	1
0.1333	2.218	1
0.1416	2.143	1
0.15	2.067	1
0.1583	1.954	1
0.1666	1.898	1
0.175	1.835	1
0.1833	1.766	1
0.1916	1.703	1
0.2	1.64	1
0.2083	1.577	1
0.2166	1.533	1
0.225	1.47	1
0.2333	1.42	1
0.2416	1.357	1
0.25	1.319	1
0.2583	1.275	1
0.2666	1.219	1
0.275	1.162	1
0.2833	1.087	1
0.2916	1.011	1
0.3	0.942	1
0.3083	0.879	1
0.3166	0.823	1
0.325	0.773	1
0.3333	0.741	1
0.35	0.647	1
0.3666	0.578	1
0.3833	0.509	1
0.4	0.433	1
0.4166	0.326	1
0.4333	0.307	1
0.45	0.276	1
0.4666	0.201	1
0.4833	0.458	1
0.5	0.835	1
0.5166	0.659	1
0.5333	0.578	1
0.55	0.509	1
0.5666	0.402	1
0.5833	0.452	1
0.6	0.408	1
0.6166	0.169	1
0.6333	0.289	1
0.65	0.408	1
0.6666	0.307	1
0.6833	0.326	1
0.7	0.389	1
0.7166	0.219	1
0.7333	0.201	1


0.75	0.226	1
0.7666	0.232	1
0.7833	0.175	1
0.8	0.138	1
0.8166	0.163	1
0.8333	0.138	1
0.85	0.144	1
0.8666	0.119	1
0.8833	0.113	1
0.9	0.113	1
0.9166	0.182	1
0.9333	0.119	1
0.95	0.087	1
0.9666	0.069	1
0.9833	0.056	1
1	0.062	1
1.2	0.031	1



0.1	2.728	1
0.1083	2.627	1
0.1166	2.59	1
0.125	2.565	1
0.1333	2.546	1
0.1416	2.514	1
0.15	2.502	1
0.1583	2.489	1
0.1666	2.47	1
0.175	2.439	1
0.1833	2.439	1
0.1916	2.414	1
0.2	2.401	1
0.2083	2.395	1
0.2166	2.389	1
0.225	2.357	1
0.2333	2.344	1
0.2416	2.319	1
0.25	2.307	1
0.2583	2.307	1
0.2666	2.294	1
0.275	2.282	1
0.2833	2.269	1
0.2916	2.42	1
0.3	2.238	1
0.3083	2.407	1
0.3166	2.363	1
0.325	2.181	1
0.3333	2.187	1
0.35	2.175	1
0.3666	2.206	1
0.3833	2.187	1
0.4	2.156	1
0.4166	2.068	1
0.4333	2.225	1
0.45	2.187	1
0.4666	2.2	1
0.4833	2.15	1
0.5	2.124	1
0.5166	2.106	1
0.5333	2.08	1
0.55	2.062	1
0.5666	2.036	1
0.5833	2.011	1
0.6	1.999	1
0.6166	1.974	1
0.6333	1.955	1
0.65	1.936	1
0.6666	1.917	1
0.6833	1.892	1
0.7	1.873	1


0.7166	1.854	1
0.7333	1.842	1
0.75	1.823	1
0.7666	1.798	1
0.7833	1.772	1
0.8	1.741	1
0.8166	1.716	1
0.8333	1.835	1
0.85	1.684	1
0.8666	1.659	1
0.8833	1.634	1
0.9	1.609	1
0.9166	1.584	1
0.9333	1.559	1
0.95	1.534	1
0.9666	1.508	1
0.9833	1.49	1
1	1.477	1
1.2	1.339	1
1.4	1.219	1
1.6	1.1	1
1.8	0.999	1
2	0.911	1
2.2	0.842	1
2.4	0.786	1
2.6	0.723	1
2.8	0.666	1
3	0.622	1
3.2	0.578	1
3.4	0.534	1
3.6	0.496	1
3.8	0.465	1
4	0.434	1
4.2	0.415	1
4.4	0.396	1
4.6	0.383	1
4.8	0.364	1
5	0.358	1
5.2	0.346	1
5.4	0.333	1
5.6	0.32	1
5.8	0.314	1
6	0.302	1
6.2	0.295	1
6.4	0.289	1
6.6	0.289	1
6.8	0.283	1
7	0.27	1
7.2	0.264	1
7.4	0.264	1
7.6	0.264	1

7.8	0.27	1
8	0.283	1
8.2	0.27	1
8.4	0.258	1
8.6	0.251	1
8.8	0.251	1
9	0.245	1
9.2	0.245	1
9.4	0.239	1
9.6	0.239	1
9.8	0.27	1
10	0.276	1
11	0.239	1
12	0.232	1
13	0.232	1
14	0.245	1
15	0.232	1
16	0.226	1
17	0.232	1
18	0.226	1
19	0.232	1
20	0.232	1
21	0.226	1
22	0.226	1




0.1416	3.853	1
0.15	3.74	1
0.1583	3.445	1
0.1666	1.735	1
0.175	3.005	1
0.1833	3.049	1
0.1916	2.923	1
0.2	2.885	1
0.2083	2.81	1
0.2166	2.69	1
0.225	2.69	1
0.2333	2.634	1
0.2416	2.583	1
0.25	2.521	1
0.2583	2.477	1
0.2666	2.42	1
0.275	2.376	1
0.2833	2.338	1
0.2916	2.288	1
0.3	2.244	1
0.3083	2.206	1
0.3166	2.156	1
0.325	2.124	1
0.3333	2.08	1
0.35	2.005	1
0.3666	1.936	1
0.3833	1.854	1
0.4	1.779	1
0.4166	1.722	1
0.4333	1.659	1
0.45	1.596	1
0.4666	1.54	1
0.4833	1.483	1
0.5	1.427	1
0.5166	1.376	1
0.5333	1.301	1
0.55	1.269	1
0.5666	1.225	1
0.5833	1.188	1
0.6	1.163	1
0.6166	1.125	1
0.6333	1.219	1
0.65	1.043	1
0.6666	1.2	1
0.6833	0.949	1
0.7	0.924	1
0.7166	0.873	1
0.7333	0.848	1
0.75	0.817	1
0.7666	0.792	1
0.7833	0.76	1

0.8	0.729	1
0.8166	0.704	1
0.8333	0.685	1
0.85	0.666	1
0.8666	0.634	1
0.8833	0.616	1
0.9	0.59	1
0.9166	0.59	1
0.9333	0.584	1
0.95	0.559	1
0.9666	0.54	1
0.9833	0.528	1
1	0.502	1
1.2	0.339	1
1.4	0.22	1
1.6	0.144	1
1.8	0.094	1
2	0.069	1
2.2	0.044	1
2.4	0.044	1
2.6	0.025	1
2.8	0.012	1
3	0.012	1




0.2833	3.136	1
0.2916	3.13	1
0.3	3.13	1
0.3083	3.092	1
0.3166	3.073	1
0.325	3.061	1
0.3333	3.042	1
0.35	3.017	1
0.3666	2.979	1
0.3833	2.891	1
0.4	2.897	1
0.4166	2.86	1
0.4333	2.809	1
0.45	2.79	1
0.4666	2.765	1
0.4833	2.734	1
0.5	2.721	1
0.5166	2.684	1
0.5333	2.658	1
0.55	2.633	1
0.5666	2.633	1
0.5833	2.539	1
0.6	2.533	1
0.6166	2.526	1
0.6333	2.508	1
0.65	2.451	1
0.6666	2.42	1
0.6833	2.426	1
0.7	2.363	1
0.7166	2.363	1
0.7333	2.281	1
0.75	2.313	1
0.7666	2.25	1
0.7833	2.244	1
0.8	2.231	1
0.8166	2.2	1
0.8333	2.206	1
0.85	2.149	1
0.8666	2.086	1
0.8833	2.099	1
0.9	2.112	1
0.9166	2.08	1
0.9333	2.011	1
0.95	2.017	1
0.9666	2.017	1
0.9833	1.961	1
1	2.011	1
1.2	1.772	1
1.4	1.583	1
1.6	1.395	1
1.8	1.275	1

2	1.125	1
2.2	1.03	1
2.4	0.93	1
2.6	0.848	1
2.8	0.76	1
3	0.703	1
3.2	0.641	1
3.4	0.578	1
3.6	0.54	1
3.8	0.496	1
4	0.452	1
4.2	0.414	1
4.4	0.383	1
4.6	0.339	1
4.8	0.333	1
5	0.295	1
5.2	0.276	1
5.4	0.251	1
5.6	0.232	1
5.8	0.213	1
6	0.194	1
6.2	0.175	1
6.4	0.163	1
6.6	0.15	1
6.8	0.138	1
7	0.125	1
7.2	0.113	1
7.4	0.1	1
7.6	0.087	1
7.8	0.081	1
8	0.075	1
8.2	0.069	1
8.4	0.062	1
8.6	0.05	1
8.8	0.043	1
9	0.031	1
9.2	0.037	1
9.4	0.025	1
9.6	0.031	1
9.8	0.043	1
10	0.037	1
11	0.012	1




0.0833	0.647	1
0.0916	0.508	1
0.1	0.341	1
0.1083	0.23	1
0.1166	0.161	1
0.125	0.116	1
0.1333	0.085	1
0.1416	0.066	1
0.15	0.05	1
0.1583	0.041	1
0.1666	0.031	1
0.175	0.025	1
0.1833	0.018	1
0.1916	0.012	1
0.2	0.009	1
0.2083	0.009	1
0.2166	0.003	1
0.225	0	1
0.2333	0.003	1
0.2416	0	1




0.0583	2.198	1
0.0666	1.811	1
0.075	1.745	1
0.0833	1.67	1
0.0916	1.604	1
0.1	1.538	1
0.1083	1.453	1
0.1166	1.415	1
0.125	1.358	1
0.1333	1.311	1
0.1416	1.255	1
0.15	1.198	1
0.1583	1.151	1
0.1666	1.113	1
0.175	1.066	1
0.1833	1.028	1
0.1916	0.99	1
0.2	0.953	1
0.2083	0.915	1
0.2166	0.887	1
0.225	0.849	1
0.2333	0.82	1
0.2416	0.792	1
0.25	0.764	1
0.2583	0.736	1
0.2666	0.707	1
0.275	0.679	1
0.2833	0.66	1
0.2916	0.632	1
0.3	0.613	1
0.3083	0.585	1
0.3166	0.566	1
0.325	0.547	1
0.3333	0.528	1
0.35	0.49	1
0.3666	0.462	1
0.3833	0.443	1
0.4	0.415	1
0.4166	0.396	1
0.4333	0.377	1
0.45	0.368	1
0.4666	0.349	1
0.4833	0.339	1
0.5	0.33	1
0.5166	0.32	1
0.5333	0.32	1
0.55	0.301	1
0.5666	0.301	1
0.5833	0.292	1
0.6	0.292	1
0.6166	0.283	1

0.6333	0.273	1
0.65	0.273	1
0.6666	0.264	1
0.6833	0.264	1
0.7	0.254	1
0.7166	0.245	1
0.7333	0.245	1
0.75	0.245	1
0.7666	0.245	1
0.7833	0.235	1
0.8	0.235	1
0.8166	0.235	1
0.8333	0.226	1
0.85	0.226	1
0.8666	0.217	1
0.8833	0.217	1
0.9	0.217	1
0.9166	0.207	1
0.9333	0.207	1
0.95	0.207	1
0.9666	0.207	1
0.9833	0.198	1
1	0.198	1
1.2	0.169	1
1.4	0.15	1
1.6	0.141	1
1.8	0.122	1
2	0.113	1
2.2	0.103	1
2.4	0.094	1
2.6	0.094	1
2.8	0.084	1
3	0.084	1
3.2	0.084	1
3.4	0.084	1
3.6	0.075	1
3.8	0.075	1
4	0.075	1
4.2	0.075	1
4.4	0.075	1
4.6	0.066	1
4.8	0.066	1
5	0.075	1
5.2	0.066	1




0.0666	0.594	1
0.075	0.575	1
0.0833	0.565	1
0.0916	0.547	1
0.1	0.537	1
0.1083	0.528	1
0.1166	0.509	1
0.125	0.499	1
0.1333	0.49	1
0.1416	0.481	1
0.15	0.471	1
0.1583	0.462	1
0.1666	0.452	1
0.175	0.443	1
0.1833	0.443	1
0.1916	0.433	1
0.2	0.415	1
0.2083	0.415	1
0.2166	0.405	1
0.225	0.396	1
0.2333	0.396	1
0.2416	0.386	1
0.25	0.377	1
0.2583	0.367	1
0.2666	0.358	1
0.275	0.358	1
0.2833	0.349	1
0.2916	0.339	1
0.3	0.339	1
0.3083	0.33	1
0.3166	0.32	1
0.325	0.311	1
0.3333	0.311	1
0.35	0.292	1
0.3666	0.282	1
0.3833	0.273	1
0.4	0.264	1
0.4166	0.254	1
0.4333	0.245	1
0.45	0.235	1
0.4666	0.226	1
0.4833	0.216	1
0.5	0.207	1
0.5166	0.198	1
0.5333	0.188	1
0.55	0.179	1
0.5666	0.179	1
0.5833	0.169	1
0.6	0.16	1
0.6166	0.16	1
0.6333	0.15	1

0.65	0.141	1
0.6666	0.132	1
0.6833	0.132	1
0.7	0.122	1
0.7166	0.122	1
0.7333	0.113	1
0.75	0.113	1
0.7666	0.103	1
0.7833	0.103	1
0.8	0.094	1
0.8166	0.094	1
0.8333	0.084	1
0.85	0.084	1
0.8666	0.084	1
0.8833	0.075	1
0.9	0.075	1
0.9166	0.075	1
0.9333	0.066	1
0.95	0.066	1
0.9666	0.066	1
0.9833	0.056	1
1	0.056	1
1.2	0.037	1
1.4	0.028	1
1.6	0.018	1
1.8	0.009	1
2	0.009	1
2.2	0.018	1
2.4	0.009	1
2.6	0.009	1




0.025	1.736	1
0.0333	1.083	1
0.0416	0.407	1
0.05	0.29	1
0.0583	0.268	1
0.0666	0.249	1
0.075	0.233	1
0.0833	0.217	1
0.0916	0.202	1
0.1	0.186	1
0.1083	0.173	1
0.1166	0.161	1
0.125	0.151	1
0.1333	0.145	1
0.1416	0.132	1
0.15	0.126	1
0.1583	0.12	1
0.1666	0.11	1
0.175	0.107	1
0.1833	0.101	1
0.1916	0.094	1
0.2	0.088	1
0.2083	0.085	1
0.2166	0.078	1
0.225	0.075	1
0.2333	0.072	1
0.2416	0.069	1
0.25	0.066	1
0.2583	0.06	1
0.2666	0.06	1
0.275	0.056	1
0.2833	0.053	1
0.2916	0.05	1
0.3	0.047	1
0.3083	0.047	1
0.3166	0.044	1
0.325	0.041	1
0.3333	0.041	1
0.35	0.037	1
0.3666	0.034	1
0.3833	0.031	1
0.4	0.028	1
0.4166	0.025	1
0.4333	0.025	1
0.45	0.025	1
0.4666	0.022	1
0.4833	0.022	1



0	1.934	1
0.0083	1.859	1
0.0166	1.802	1
0.025	1.745	1
0.0333	1.66	1
0.0416	1.642	1
0.05	1.585	1
0.0583	1.538	1
0.0666	1.5	1
0.075	1.453	1
0.0833	1.415	1
0.0916	1.377	1
0.1	1.33	1
0.1083	1.292	1
0.1166	1.264	1
0.125	1.226	1
0.1333	1.179	1
0.1416	1.16	1
0.15	1.132	1
0.1583	1.104	1
0.1666	1.075	1
0.175	1.047	1
0.1833	1.019	1
0.1916	0.99	1
0.2	0.962	1
0.2083	0.943	1
0.2166	0.915	1
0.225	0.906	1
0.2333	0.877	1
0.2416	0.858	1
0.25	0.83	1
0.2583	0.792	1
0.2666	0.792	1
0.275	0.764	1
0.2833	0.755	1
0.2916	0.736	1
0.3	0.717	1
0.3083	0.698	1
0.3166	0.679	1
0.325	0.67	1
0.3333	0.651	1
0.35	0.622	1
0.3666	0.594	1
0.3833	0.566	1
0.4	0.537	1
0.4166	0.519	1
0.4333	0.49	1
0.45	0.471	1
0.4666	0.453	1
0.4833	0.434	1
0.5	0.415	1


0.5166	0.396	1
0.5333	0.377	1
0.55	0.358	1
0.5666	0.349	1
0.5833	0.32	1
0.6	0.32	1
0.6166	0.302	1
0.6333	0.292	1
0.65	0.283	1
0.6666	0.273	1
0.6833	0.264	1
0.7	0.254	1
0.7166	0.235	1
0.7333	0.235	1
0.75	0.217	1
0.7666	0.207	1
0.7833	0.207	1
0.8	0.198	1
0.8166	0.188	1
0.8333	0.179	1
0.85	0.179	1
0.8666	0.179	1
0.8833	0.169	1
0.9	0.16	1
0.9166	0.151	1
0.9333	0.169	1
0.95	0.141	1
0.9666	0.132	1
0.9833	0.132	1
1	0.132	1
1.2	0.084	1
1.4	0.056	1
1.6	0.047	1
1.8	0.037	1
2	0.028	1
2.2	0.018	1
2.4	0.028	1
2.6	0.018	1
2.8	0.018	1
3	0.018	1
3.2	0.018	1
3.4	0.018	1
3.6	0.009	1
3.8	0.009	1
4	0.009	1



0.0416	2.561	1
0.05	2.173	1
0.0583	1.975	1
0.0666	1.918	1
0.075	1.871	1
0.0833	1.871	1
0.0916	1.824	1
0.1	1.795	1
0.1083	1.786	1
0.1166	1.748	1
0.125	1.758	1
0.1333	1.72	1
0.1416	1.72	1
0.15	1.654	1
0.1583	1.692	1
0.1666	1.606	1
0.175	1.692	1
0.1833	1.588	1
0.1916	1.625	1
0.2	1.588	1
0.2083	1.578	1
0.2166	1.569	1
0.225	1.55	1
0.2333	1.54	1
0.2416	1.521	1
0.25	1.503	1
0.2583	1.493	1
0.2666	1.484	1
0.275	1.465	1
0.2833	1.455	1
0.2916	1.446	1
0.3	1.436	1
0.3083	1.417	1
0.3166	1.408	1
0.325	1.389	1
0.3333	1.389	1
0.35	1.361	1
0.3666	1.332	1
0.3833	1.314	1
0.4	1.295	1
0.4166	1.276	1
0.4333	1.257	1
0.45	1.238	1
0.4666	1.21	1
0.4833	1.191	1
0.5	1.181	1
0.5166	1.162	1
0.5333	1.143	1
0.55	1.125	1
0.5666	1.106	1
0.5833	1.087	1

0.6	1.068	1
0.6166	1.058	1
0.6333	1.039	1
0.65	1.021	1
0.6666	1.002	1
0.6833	0.983	1
0.7	0.973	1
0.7166	0.964	1
0.7333	0.945	1
0.75	0.935	1
0.7666	0.917	1
0.7833	0.907	1
0.8	0.888	1
0.8166	0.869	1
0.8333	0.86	1
0.85	0.85	1
0.8666	0.832	1
0.8833	0.822	1
0.9	0.813	1
0.9166	0.794	1
0.9333	0.784	1
0.95	0.775	1
0.9666	0.765	1
0.9833	0.756	1
1	0.746	1
1.2	0.624	1
1.4	0.52	1
1.6	0.425	1
1.8	0.368	1
2	0.312	1
2.2	0.274	1
2.4	0.236	1
2.6	0.198	1
2.8	0.179	1
3	0.151	1
3.2	0.132	1
3.4	0.113	1
3.6	0.094	1
3.8	0.085	1
4	0.075	1
4.2	0.075	1
4.4	0.056	1
4.6	0.056	1
4.8	0.056	1
5	0.047	1
5.2	0.047	1
5.4	0.038	1
5.6	0.038	1
5.8	0.038	1
6	0.038	1
6.2	0.028	1


6.4	0.019	1
6.6	0.019	1



0.0166	3.86	1
0.025	2.406	1
0.0333	1.283	1
0.0416	1.057	1
0.05	1.104	1
0.0583	1.085	1
0.0666	1.085	1
0.075	1.076	1
0.0833	1.076	1
0.0916	1.076	1
0.1	1.066	1
0.1083	1.066	1
0.1166	1.066	1
0.125	1.057	1
0.1333	1.085	1
0.1416	1.057	1
0.15	1.047	1
0.1583	1.057	1
0.1666	1.047	1
0.175	1.038	1
0.1833	1.047	1
0.1916	1.038	1
0.2	1.047	1
0.2083	1.038	1
0.2166	1.038	1
0.225	1.038	1
0.2333	1.038	1
0.2416	1.038	1
0.25	1.038	1
0.2583	1.029	1
0.2666	1.029	1
0.275	1.029	1
0.2833	1.029	1
0.2916	1.029	1
0.3	1.029	1
0.3083	1.029	1
0.3166	1.029	1
0.325	1.029	1
0.3333	1.029	1
0.35	1.029	1
0.3666	1.029	1
0.3833	1.029	1
0.4	1.019	1
0.4166	1.019	1
0.4333	1.019	1
0.45	1.019	1
0.4666	1.019	1
0.4833	1.029	1
0.5	1.019	1
0.5166	1.019	1
0.5333	1.019	1

0.55	1.019	1
0.5666	1.019	1
0.5833	1.019	1
0.6	1.01	1
0.6166	1.019	1
0.6333	1.01	1
0.65	1.019	1
0.6666	1.019	1
0.6833	1.01	1
0.7	1.01	1
0.7166	1.01	1
0.7333	1.01	1
0.75	1.01	1
0.7666	1.01	1
0.7833	1.01	1
0.8	1.01	1
0.8166	1.01	1
0.8333	1.01	1
0.85	1.01	1
0.8666	1.01	1
0.8833	1.01	1
0.9	1	1
0.9166	1	1
0.9333	1	1
0.95	1	1
0.9666	1	1
0.9833	1	1
1	1	1
1.2	1	1
1.4	0.991	1
1.6	0.991	1
1.8	0.981	1
2	0.981	1
2.2	0.972	1
2.4	0.972	1
2.6	0.972	1
2.8	0.962	1
3	0.953	1
3.2	0.953	1
3.4	0.953	1
3.6	0.953	1
3.8	0.944	1
4	0.944	1
4.2	0.944	1
4.4	0.934	1
4.6	0.934	1
4.8	0.925	1
5	0.925	1
5.2	0.925	1
5.4	0.925	1
5.6	0.915	1


5.8	0.915	1
6	0.906	1
6.2	0.906	1
6.4	0.896	1
6.6	0.906	1
6.8	0.906	1
7	0.896	1
7.2	0.896	1
7.4	0.887	1
7.6	0.887	1
7.8	0.887	1
8	0.887	1



0.0666	2.023	1
0.075	1.879	1
0.0833	1.759	1
0.0916	1.684	1
0.1	1.608	1
0.1083	1.533	1
0.1166	1.47	1
0.125	1.407	1
0.1333	1.357	1
0.1416	1.307	1
0.15	1.263	1
0.1583	1.219	1
0.1666	1.168	1
0.175	1.131	1
0.1833	1.093	1
0.1916	1.062	1
0.2	1.024	1
0.2083	0.992	1
0.2166	0.961	1
0.225	0.936	1
0.2333	0.905	1
0.2416	0.879	1
0.25	0.848	1
0.2583	0.823	1
0.2666	0.798	1
0.275	0.779	1
0.2833	0.754	1
0.2916	0.735	1
0.3	0.71	1
0.3083	0.691	1
0.3166	0.672	1
0.325	0.653	1
0.3333	0.641	1
0.35	0.603	1
0.3666	0.578	1
0.3833	0.546	1
0.4	0.515	1
0.4166	0.496	1
0.4333	0.471	1
0.45	0.446	1
0.4666	0.427	1
0.4833	0.402	1
0.5	0.389	1
0.5166	0.37	1
0.5333	0.351	1
0.55	0.339	1
0.5666	0.326	1
0.5833	0.307	1
0.6	0.295	1
0.6166	0.282	1
0.6333	0.27	1


0.65	0.263	1
0.6666	0.251	1
0.6833	0.245	1
0.7	0.232	1
0.7166	0.226	1
0.7333	0.219	1
0.75	0.207	1
0.7666	0.201	1
0.7833	0.194	1
0.8	0.188	1
0.8166	0.182	1
0.8333	0.175	1
0.85	0.169	1
0.8666	0.163	1
0.8833	0.163	1
0.9	0.157	1
0.9166	0.15	1
0.9333	0.144	1
0.95	0.144	1
0.9666	0.138	1
0.9833	0.138	1
1	0.131	1
1.2	0.1	1
1.4	0.081	1
1.6	0.062	1
1.8	0.056	1
2	0.05	1
2.2	0.05	1
2.4	0.05	1
2.6	0.043	1
2.8	0.037	1
3	0.037	1
3.2	0.031	1
3.4	0.031	1
3.6	0.031	1
3.8	0.037	1
4	0.031	1
4.2	0.037	1
4.4	0.037	1
4.6	0.037	1
4.8	0.031	1
5	0.031	1
5.2	0.031	1
5.4	0.031	1
5.6	0.031	1
5.8	0.031	1
6	0.031	1
6.2	0.025	1
6.4	0.031	1
6.6	0.031	1
6.8	0.031	1

7	0.031	1
7.2	0.025	1
7.4	0.018	1
7.6	0.018	1
7.8	0.012	1



0.0416	3.846	1
0.05	3.676	1
0.0583	3.563	1
0.0666	3.406	1
0.075	3.274	1
0.0833	3.148	1
0.0916	3.035	1
0.1	2.928	1
0.1083	2.803	1
0.1166	2.715	1
0.125	2.608	1
0.1333	2.514	1
0.1416	2.413	1
0.15	2.338	1
0.1583	2.237	1
0.1666	2.155	1
0.175	2.08	1
0.1833	1.998	1
0.1916	1.923	1
0.2	1.854	1
0.2083	1.784	1
0.2166	1.709	1
0.225	1.646	1
0.2333	1.59	1
0.2416	1.527	1
0.25	1.464	1
0.2583	1.414	1
0.2666	1.357	1
0.275	1.307	1
0.2833	1.257	1
0.2916	1.206	1
0.3	1.162	1
0.3083	1.118	1
0.3166	1.068	1
0.325	1.037	1
0.3333	0.993	1
0.35	0.911	1
0.3666	0.842	1
0.3833	0.779	1
0.4	0.716	1
0.4166	0.666	1
0.4333	0.615	1
0.45	0.559	1
0.4666	0.515	1
0.4833	0.471	1
0.5	0.433	1
0.5166	0.395	1
0.5333	0.364	1
0.55	0.339	1
0.5666	0.307	1
0.5833	0.282	1


0.6	0.257	1
0.6166	0.232	1
0.6333	0.213	1
0.65	0.201	1
0.6666	0.175	1
0.6833	0.157	1
0.7	0.144	1
0.7166	0.125	1
0.7333	0.119	1
0.75	0.106	1
0.7666	0.094	1
0.7833	0.081	1
0.8	0.075	1
0.8166	0.062	1
0.8333	0.062	1
0.85	0.056	1
0.8666	0.043	1
0.8833	0.037	1
0.9	0.031	1
0.9166	0.031	1
0.9333	0.025	1
0.95	0.025	1
0.9666	0.018	1
0.9833	0.006	1
1	0.006	1



0.0583	2.697	1
0.0666	2.653	1
0.075	2.628	1
0.0833	2.602	1
0.0916	2.59	1
0.1	2.571	1
0.1083	2.552	1
0.1166	2.533	1
0.125	2.521	1
0.1333	2.502	1
0.1416	2.489	1
0.15	2.471	1
0.1583	2.458	1
0.1666	2.445	1
0.175	2.427	1
0.1833	2.414	1
0.1916	2.401	1
0.2	2.389	1
0.2083	2.376	1
0.2166	2.364	1
0.225	2.345	1
0.2333	2.339	1
0.2416	2.32	1
0.25	2.307	1
0.2583	2.295	1
0.2666	2.282	1
0.275	2.269	1
0.2833	2.263	1
0.2916	2.244	1
0.3	2.232	1
0.3083	2.225	1
0.3166	2.207	1
0.325	2.2	1
0.3333	2.188	1
0.35	2.163	1
0.3666	2.137	1
0.3833	2.119	1
0.4	2.093	1
0.4166	2.075	1
0.4333	2.056	1
0.45	2.031	1
0.4666	2.005	1
0.4833	1.993	1
0.5	1.974	1
0.5166	1.949	1
0.5333	1.93	1
0.55	1.911	1
0.5666	1.892	1
0.5833	1.873	1
0.6	1.855	1
0.6166	1.836	1


0.6333	1.817	1
0.65	1.798	1
0.6666	1.779	1
0.6833	1.767	1
0.7	1.748	1
0.7166	1.729	1
0.7333	1.71	1
0.75	1.697	1
0.7666	1.679	1
0.7833	1.66	1
0.8	1.641	1
0.8166	1.635	1
0.8333	1.616	1
0.85	1.597	1
0.8666	1.584	1
0.8833	1.565	1
0.9	1.553	1
0.9166	1.54	1
0.9333	1.521	1
0.95	1.509	1
0.9666	1.496	1
0.9833	1.484	1
1	1.465	1
1.2	1.295	1
1.4	1.151	1
1.6	1.025	1
1.8	0.918	1
2	0.817	1
2.2	0.736	1
2.4	0.667	1
2.6	0.597	1
2.8	0.541	1
3	0.484	1
3.2	0.434	1
3.4	0.396	1
3.6	0.352	1
3.8	0.302	1
4	0.258	1
4.2	0.227	1
4.4	0.201	1
4.6	0.189	1
4.8	0.176	1
5	0.157	1
5.2	0.126	1
5.4	0.113	1
5.6	0.107	1
5.8	0.101	1
6	0.088	1
6.2	0.082	1
6.4	0.082	1
6.6	0.069	1

6.8	0.069	1
7	0.063	1
7.2	0.057	1
7.4	0.063	1
7.6	0.063	1
7.8	0.057	1
8	0.051	1
8.2	0.051	1
8.4	0.044	1
8.6	0.044	1
8.8	0.038	1
9	0.038	1
9.2	0.038	1
9.4	0.038	1
9.6	0.038	1
9.8	0.038	1
10	0.032	1
11	0.025	1
12	0.025	1
13	0.019	1
14	-0.006	1




0.0583	4.23	1
0.0666	3.922	1
0.075	3.847	1
0.0833	3.715	1
0.0916	3.658	1
0.1	3.589	1
0.1083	3.539	1
0.1166	3.463	1
0.125	3.388	1
0.1333	3.325	1
0.1416	3.275	1
0.15	3.262	1
0.1583	3.168	1
0.1666	3.105	1
0.175	3.048	1
0.1833	2.986	1
0.1916	2.942	1
0.2	2.891	1
0.2083	2.841	1
0.2166	2.791	1
0.225	2.747	1
0.2333	2.703	1
0.2416	2.659	1
0.25	2.621	1
0.2583	2.571	1
0.2666	2.527	1
0.275	2.489	1
0.2833	2.445	1
0.2916	2.407	1
0.3	2.37	1
0.3083	2.326	1
0.3166	2.288	1
0.325	2.25	1
0.3333	2.225	1
0.35	2.15	1
0.3666	2.074	1
0.3833	1.999	1
0.4	1.936	1
0.4166	1.873	1
0.4333	1.816	1
0.45	1.76	1
0.4666	1.703	1
0.4833	1.647	1
0.5	1.596	1
0.5166	1.546	1
0.5333	1.496	1
0.55	1.439	1
0.5666	1.395	1
0.5833	1.357	1
0.6	1.313	1
0.6166	1.263	1

0.6333	1.225	1
0.65	1.188	1
0.6666	1.15	1
0.6833	1.106	1
0.7	1.068	1
0.7166	1.037	1
0.7333	1.005	1
0.75	0.968	1
0.7666	0.936	1
0.7833	0.924	1
0.8	0.886	1
0.8166	0.861	1
0.8333	0.817	1
0.85	0.81	1
0.8666	0.779	1
0.8833	0.754	1
0.9	0.722	1
0.9166	0.71	1
0.9333	0.678	1
0.95	0.653	1
0.9666	0.634	1
0.9833	0.622	1
1	0.603	1
1.2	0.396	1
1.4	0.257	1
1.6	0.176	1
1.8	0.119	1
2	0.081	1
2.2	0.062	1
2.4	0.025	1
2.6	0.012	1
2.8	0	1
3	0	1



0.05	1.442	1
0.0583	1.433	1
0.0666	1.433	1
0.075	1.386	1
0.0833	1.225	1
0.0916	1.018	1
0.1	0.876	1
0.1083	0.744	1
0.1166	0.641	1
0.125	0.546	1
0.1333	0.462	1
0.1416	0.386	1
0.15	0.33	1
0.1583	0.282	1
0.1666	0.235	1
0.175	0.198	1
0.1833	0.16	1
0.1916	0.132	1
0.2	0.113	1
0.2083	0.094	1
0.2166	0.084	1
0.225	0.066	1
0.2333	0.056	1
0.2416	0.047	1
0.25	0.037	1
0.2583	0.037	1
0.2666	0.028	1
0.275	0.018	1
0.2833	0.018	1
0.2916	0.018	1
0.3	0.009	1
0.3083	0.009	1
0.3166	0.009	1
0.325	0	1



0.0333	4.393	1
0.0416	4.33	1
0.05	4.211	1
0.0583	4.148	1
0.0666	4.11	1
0.075	4.079	1
0.0833	4.047	1
0.0916	4.016	1
0.1	3.985	1
0.1083	3.959	1
0.1166	3.934	1
0.125	3.909	1
0.1333	3.89	1
0.1416	3.871	1
0.15	3.846	1
0.1583	3.827	1
0.1666	3.809	1
0.175	3.79	1
0.1833	3.771	1
0.1916	3.752	1
0.2	3.733	1
0.2083	3.714	1
0.2166	3.702	1
0.225	3.683	1
0.2333	3.664	1
0.2416	3.645	1
0.25	3.633	1
0.2583	3.614	1
0.2666	3.601	1
0.275	3.582	1
0.2833	3.57	1
0.2916	3.551	1
0.3	3.551	1
0.3083	3.526	1
0.3166	3.507	1
0.325	3.494	1
0.3333	3.482	1
0.35	3.45	1
0.3666	3.419	1
0.3833	3.394	1
0.4	3.369	1
0.4166	3.343	1
0.4333	3.318	1
0.45	3.287	1
0.4666	3.262	1
0.4833	3.237	1
0.5	3.211	1
0.5166	3.186	1
0.5333	3.167	1
0.55	3.142	1
0.5666	3.117	1

0.5833	3.098	1
0.6	3.073	1
0.6166	3.048	1
0.6333	3.029	1
0.65	3.004	1
0.6666	2.985	1
0.6833	2.966	1
0.7	2.941	1
0.7166	2.922	1
0.7333	2.897	1
0.75	2.878	1
0.7666	2.853	1
0.7833	2.841	1
0.8	2.815	1
0.8166	2.797	1
0.8333	2.778	1
0.85	2.753	1
0.8666	2.734	1
0.8833	2.715	1
0.9	2.696	1
0.9166	2.683	1
0.9333	2.658	1
0.95	2.646	1
0.9666	2.621	1
0.9833	2.608	1
1	2.589	1
1.2	2.376	1
1.4	2.156	1
1.6	1.961	1
1.8	1.785	1
2	1.634	1
2.2	1.502	1
2.4	1.376	1
2.6	1.263	1
2.8	1.156	1
3	1.062	1
3.2	0.968	1
3.4	0.88	1
3.6	0.798	1
3.8	0.722	1
4	0.672	1
4.2	0.622	1
4.4	0.565	1
4.6	0.521	1
4.8	0.49	1
5	0.452	1
5.2	0.421	1
5.4	0.383	1
5.6	0.358	1
5.8	0.314	1
6	0.289	1

6.2	0.264	1
6.4	0.257	1
6.6	0.232	1
6.8	0.232	1
7	0.232	1
7.2	0.232	1
7.4	0.232	1
7.6	0.207	1
7.8	0.194	1
8	0.188	1
8.2	0.169	1
8.4	0.157	1
8.6	0.144	1
8.8	0.138	1
9	0.132	1
9.2	0.119	1
9.4	0.106	1
9.6	0.094	1
9.8	0.081	1
10	0.081	1