

SUPPLEMENTAL REMEDIAL INVESTIGATION REPORT

**Former Columbia Cement Company, Inc. Facility
159 Hanse Avenue
Freeport, New York**

SITE # 1-30-052

Prepared for:

**Atlantic Richfield Company
1 West Pennsylvania Avenue
Suite 440
Towson, Maryland 21204-0527**



Prepared by:

**URS Corporation
12 Commerce Drive
Cranford, New Jersey 07016**



December 2006

TABLE OF CONTENTS

	<u>Page</u>
1.0 INTRODUCTION	1
1.1 Background Information	1
1.2 Site Description.....	2
1.3 Site Geology/Hydrogeology.....	3
2.0 SUPPLEMENTAL INVESTIGATION ACTIVITIES	5
2.1 Soil Investigation Activities.....	6
2.1.1 Pre-Closure Soil Sampling.....	6
2.1.2 UST Closure Soil Sampling.....	6
2.1.3 Post-Closure Soil Sampling	8
2.2 Groundwater Investigation Activities	9
2.2.1 2004 Groundwater Sampling	9
2.2.2 Groundwater Biofeasibility Sampling.....	9
2.2.3 Offsite Monitoring Well Installation and Sampling.....	10
2.2.4 Slug Testing	11
2.2.5 2006 Groundwater Sampling	11
2.3 Soil Vapor Investigation Activities	12
2.3.1 2005 Vapor Intrusion Sampling	12
2.3.2 2006 Vapor Intrusion Sampling	14
2.4 Treatability Study Investigation Activities.....	15
2.4.1 Bench-Scale Testing.....	15
3.0 RESULTS	17
3.1 Soil Investigation Activities.....	17
3.1.1 Pre-Closure Soil Sampling.....	17
3.1.2 Sampling During Building Owner's UST Closure	17
3.1.3 Post UST Closure Soil Sampling	18
3.1.3.1 Closure Verification.....	18
3.1.3.2 Delineation Sampling.....	19
3.1.4 Soil Investigation Summary	20
3.2 Groundwater Investigation Activities	21
3.2.1 2004 Groundwater Activities	21
3.2.1.1 Groundwater Levels and Flow	21
3.2.1.2 Groundwater Volatile Organic Compound Results	21
3.2.1.3 Groundwater Geotechnical Data	22
3.2.2 2005 Off-Site Monitoring Well Installation and Sampling.....	23
3.2.3 2006 Groundwater Activities	24
3.2.3.1 Groundwater Levels and Flow	24
3.2.3.2 Groundwater Volatile Organic Compound Results	24
3.2.3.3 Groundwater Geotechnical Data	26

TABLE OF CONTENTS (continued)

	<u>Page</u>
3.2.4 Slug Testing	27
3.3 Soil Vapor Investigation Results.....	28
3.3.1 2005 Vapor Intrusion Sampling Results	28
3.3.2 2006 Vapor Intrusion Sampling Results	28
3.3.2.1 Soil Gas	29
3.3.2.2 Sub-Slab Vapor	30
3.3.2.3 Indoor Air Samples	31
3.3.2.4 Ambient Air Samples.....	31
3.4 Bench-Scale Treatability Study Results	32
3.4.1 In-Situ Chemical Oxidation Test	32
3.4.2 Enhanced Natural Attenuation Test	32
4.0 SUMMARY	34
5.0 REFERENCES	36

TABLES

- Table 1 Summary of Soil Sampling /Analysis Program
- Table 2 Summary of Groundwater Sampling / Analysis Program
- Table 3 Summary of Soil Analytical Results – Pre-UST Closure Soil Borings
- Table 4 Summary of Soil Analytical Results – Post-UST Excavation Soil Sampling
- Table 5 Summary of Soil Analytical Results – Post-Closure Soil Borings
- Table 6 Summary of Field Measurements – June, 2004 Groundwater Sampling
- Table 7 Summary of Groundwater Analytical Results – June, 2004 Groundwater Sampling
- Table 8 Summary of Field Measurements – April 2005 Groundwater Sampling
- Table 9 Summary of Groundwater Analytical Results – April, 2005 Groundwater Sampling
- Table 10 Summary of Field Measurements – June, 2006 Groundwater Sampling
- Table 11 Summary of Groundwater Analytical Results – June, 2006 Groundwater Sampling
- Table 12 Summary of Groundwater Geochemical Data – June, 2006 Groundwater Sampling
- Table 13 Summary of Slug Testing Results
- Table 14 Summary of 2005 Vapor Intrusion Testing Results
- Table 15 Summary of 2006 Vapor Intrusion Testing Results

FIGURES

- Figure 1 Site Location Map
- Figure 2 Site Plan and Sampling Locations Map
- Figure 3 UST Area Soil Sampling Locations and Results
- Figure 4 Residual Source Areas
- Figure 5 Soil 1,1,1-TCA Concentrations - Cross-Section A-A'
- Figure 6 Soil 1,1,1-TCA Concentrations - Cross-Section B-B'

TABLE OF CONTENTS (continued)

- Figure 7 Soil 1,1,1-TCA Concentrations - Cross-Section C-C'
- Figure 8 Soil 1,1,1-TCA Concentrations - Cross-Section D-D'
- Figure 9 Soil 1,1-DCA Concentrations - Cross-Section A-A'
- Figure 10 Soil 1,1-DCA Concentrations - Cross-Section B-B'
- Figure 11 Soil 1,1-DCA Concentrations - Cross-Section C-C
- Figure 12 Soil 1,1-DCA Concentrations - Cross-Section D-D'
- Figure 13 Soil Chloroethane Concentrations - Cross-Section A-A'
- Figure 14 Soil Chloroethane Concentrations - Cross-Section B-B'
- Figure 15 Soil Chloroethane Concentrations - Cross-Section C-C'
- Figure 16 Soil Chloroethane Concentrations - Cross-Section D-D'
- Figure 17 Water Table Elevation Contour Map – June 6, 2006
- Figure 18 Water Table Elevation Contour Map – April 26, 2005
- Figure 19 Water Table Elevation Contour Map – June 6, 2006
- Figure 20 Groundwater Volatile Organic Data
- Figure 21 Groundwater Geochemical Data
- Figure 22 2005 Vapor Intrusion Sampling Locations and Results
- Figure 23 2006 Vapor Intrusions Sampling Locations and Results

APPENDICES

- Appendix A Delaware Engineering December 2003 RIR Data Tables
- Appendix B Soil Boring Logs
- Appendix C Groundwater Sampling Logs
- Appendix D Monitoring Well Boring Logs and Well Construction Diagrams
- Appendix E Slug Test Drawdown Curves
- Appendix F Soil Gas Sampling Logs
- Appendix G Bench-Scale Treatability Testing Reports
- Appendix H Laboratory Data QA/QC Review

1.0 INTRODUCTION

This Supplemental Remedial Investigation Report (SRIR) was prepared to present data obtained from subsurface investigation activities at the former Columbia Cement Company (CCC) site located at 159 Hanse Avenue in Freeport, New York ("Site"). URS Corporation (URS) prepared the SRIR on behalf of the Atlantic Richfield Company, a BP affiliate (BP) and in response to requests from the New York State Department of Environmental Conservation (NYSDEC) as partial fulfillment of requirements of the New York State Inactive Hazardous Waste Disposal Remedial (Superfund) Program. The SRIR presents a summary of the December 2003 Remedial Investigation Report (RIR) (Delaware Engineering, 2003) that previously was submitted to NYSDEC, and presents data obtained by URS subsequent to the RIR.

1.1 BACKGROUND INFORMATION

CCC, which was owned by Burmah Castrol, produced adhesives for a variety of applications. In 1988, while CCC operated the facility, approximately 1,760 gallons of 1,1,1-trichloroethane (1,1,1-TCA) was released to a storm drain during filling of an underground storage tank (UST) due to a failure of a contractor's tanker truck. The spill was reported and response measures were performed under regulatory oversight. In 1996, the property was sold to Illinois Tool Works (ITW). In 1998, Burmah Castrol entered into a Consent Agreement (Index WI#W2-02-0813-98-05) with the NYSDEC regarding the 1,1,1-TCA spill. In 2001, British Petroleum (BP) purchased all Burmah Castrol holdings and assumed liability for the 1,1,1-TCA spill. A Remedial Investigation (RI) was conducted by Delaware Engineering on behalf of BP and the RIR was submitted to NYSDEC in July 2003. In response to NYSDEC comments, a revised RIR was submitted in December 2003. Tables of data from the RIR are presented in Appendix A. Site characterization descriptions presented herein reflect information provided in the RI.

In September 2003, URS Corporation was retained by BP to prepare a Feasibility Study (FS) to evaluate remedial options for the Site. The FS was prepared based on data and information in the December 2003 RI Report and NYSDEC's comments to a draft RI, dated October 27, 2003. The FS was also prepared based on site conditions at the time of preparation. The Draft FS was submitted to NYSDEC on April 30, 2004.

In January 2004, ITW ceased operations at the Site and vacated the building. In May 2004, ITW informed BP they intended to close and remove the 10 existing USTs at the Site, in anticipation of sale of the property. The USTs were removed in September 2004. Since the 1,1,1-TCA spill occurred in the center of the UST area, the removal of the USTs dramatically changed conditions and access in the spill area and presented opportunities for remedial alternatives that previously

were unavailable or impractical. Based on discussions with and approvals from NYSDEC, URS conducted supplemental investigation activities that would allow for refinement of site characterization to be used in preparation of a revised FS that takes the changed conditions (e.g. absence of USTs in the spill area) into consideration. These supplemental investigation activities and results are described in the following sections of this report. These supplemental investigation activities included:

- Multiple rounds of low-flow groundwater sampling of all site monitoring wells, including collection of biofeasibility parameters.
- Collection of post-excavation soil samples during UST closure.
- Collection of direct push soil samples in the UST/spill area after UST removal.
- Installation of 2 additional offsite monitoring wells and subsequent groundwater sampling.
- Performance of bench-scale testing of potential remedial alternatives.
- Performance of soil vapor, sub-slab vapor and indoor air sampling to evaluate the vapor intrusion pathway.
- Slug testing of selected monitoring wells.

1.2 SITE DESCRIPTION

The former CCC facility consists of approximately 2 acres in an area of Freeport, New York that is highly developed with commercial and industrial facilities. Freeport is located in Nassau County on the south shore of Long Island. The site location is shown on Figure 1. The Site building covers approximately 65,000 square feet, and consists of former offices, material storage, production rooms, and warehousing. Ten 8,000-gallon underground storage tanks (USTs) were located near the southeast corner of the property. The Site is bordered by a former Columbia Cement warehouse and parking spaces to the north. Rohm & Haas Electronic Components borders the property to the east. The Knickerbocker building, with multiple tenants, is located to the south of the property. The property is bordered by Hanse Avenue to the West. Farber Plastics and Love & Quiches bakery is located on the opposite (west) side of Hanse Avenue. A Site Plan is presented as Figure 2.

The Site is located on a peninsula on the south side of Long Island. Freeport Creek is located 500 feet west of the Site and Stadium Park Canal is 1,000 feet east of the site. Stadium Park Canal merges with Freeport Creek approximately 1,500 feet southeast of the site. From this point, surface water flows south through tidal marshes to the Atlantic Ocean, approximately 5 miles south of the Site.

The Site is very flat, ranging from 5 to 10 feet above Mean Sea Level (MSL). A surveyor established a benchmark on Hanse Avenue with an artificial reference elevation of 100 feet, and from this reference, site elevations ranged from 97.63 to 99.07. Surface water at the site drains to the west toward Freeport Creek. Storm drains located on site, also drain to Freeport Creek.

Ten 8,000-gallon USTs were installed in 1988. Five of these USTs (the southern tank farm) were installed in the Spring of 1988 (prior to the 1,1,1-TCA spill) and the remaining five (the northern tank farm) were installed after the spill. Due to excessive cracking, the concrete pad around the USTs was replaced in 1989. As stated previously, these USTs were closed and removed by ITW in September 2004. The UST removal is discussed in greater detail in Section 2.1.

1.3 SITE GEOLOGY/HYDROGEOLOGY

Soil borings advanced during investigation activities at the Site encountered five stratigraphic units beneath the site. In order of increasing depth, these units are: fill material; tidal marsh deposits; gravelly sand; gray clay and silt; and gray sand. Each of these units is discussed below.

- The fill material is encountered across the entire site and consists of reworked native soil and various debris related to previous Site use as a municipal landfill. The fill material ranges in thickness from 3.1 feet (ft) to 22.9 ft, with an average thickness of about 11 ft.
- The tidal marsh deposits are encountered beneath the fill material over most of the site, but are absent in some areas, including the UST/spill area. The tidal marsh deposits consist of brown, dark gray and black organic clayey silt with some fine to medium sand and varying amounts of roots, wood and peat. Where present, the tidal marsh material is encountered at an average depth of 9.5 ft and has an average thickness of 4 ft.
- The gravelly sand is a relatively thick and flat-lying unit encountered beneath the tidal marsh deposits, and beneath the fill material where the tidal marsh deposits are absent. The unit consists of medium dense, brown to light gray, coarse to fine sand, with little

medium to fine surrounded gravel. Minor amounts of silt and clay were found in isolated samples. The gravelly sand thickness ranges from 15 to 30 ft and is thickest in the western portion of the site. The base of the gravelly sand is relatively flat and is encountered at about 35 ft below grade.

- The gray clay and silt underlies the gravelly sand. It consists of a medium gray clayey silt to silt and clay with little to trace sand and becomes clayier with depth. In the two borings on Site that penetrated the entire clay unit, the thickness ranged from 14 ft to 15.3 ft. The gray clay and silt unit likely acts as a lower confining unit beneath the site.
- An undifferentiated light gray fine sand underlies the gray clay and silt. It is described as a gray to light gray medium to fine sand with little silt. Based on literature review, this unit ranges in thickness from 20 to 30 ft beneath the Site.

The shallow water-bearing units beneath the Site are not utilized as a drinking water source. Deeper confined units include the Jameco, Magothy and Lloyd aquifers, which are used for drinking water in some areas of Long Island. Due to saltwater encroachment near the southern shore of Long Island, these units are not a source of drinking water near the Site. Groundwater beneath the site is classified as Class GSA (saline ground water).

Shallow groundwater at the Site is encountered in the fill material at depths ranging from 5.5 to 8.0 feet below grade (ft bgs). In various areas of the site, the water table is encountered in the fill material, the tidal marsh deposits, or the gravelly sand. Due to this fact and extensive connectivity between these units, particularly where the tidal marsh unit is thin or absent, these units have been treated collectively as a single unconfined aquifer. Some shallow monitoring wells are screened across all three units. Deep monitoring wells screened at the base of the gravelly sand have nearly identical groundwater elevations as adjacent shallow wells. The shallow unconfined groundwater discharges to Freeport Creek. The gray clay and silt unit acts as a lower confining layer or aquitard, separating the water table aquifer from the underlying gray sand. The gray sand is a separate confined water-bearing unit.

Groundwater flows primarily to the west, however, due to the Site's location, groundwater levels exhibit tidal influences, as described below. As is typical in coastal areas, shallow groundwater at the site is influenced by two tidal cycles per day. During tidal monitoring, groundwater level changes of 1 ft or less were recorded on Site. The tidal range is greatest to the west, suggesting a greater hydraulic connection to Freeport Creek than to Stadium Park Canal. The timing and

degree of tidal response between the shallow and deep wells suggests that in some areas of the Site, the tidal marsh unit may restrict flow between the fill material and the gravelly sand.

As part of the RI, Delaware Engineering performed tidal monitoring of Site monitoring wells. During high tide, flow was generally to the west with a very shallow hydraulic gradient of 0.00095 ft/ft. During low tide, a groundwater divide forms in the north-central portion of the site. Groundwater east of this divide flows to the east and groundwater west of the divide flows to the west. Based on this observation, the gradient in the spill area alternates from east to west with a very minimal gradient in both directions. This alternating flow direction should serve to minimize contaminant transport from the site. The mean tide flow direction is east to west, with a hydraulic gradient of 0.0002 ft/ft net flow to the west.

2.0 SUPPLEMENTAL INVESTIGATION ACTIVITIES

From May 2004 to October 2006, URS performed supplemental remedial investigation activities at the Site. The activities were performed in coordination with NYSDEC. The purpose of these activities was to:

- Address data gaps in the RI identified by NYSDEC and NYDOH.
- Obtain soil data from areas previously inaccessible due to the former presence of the USTs.
- Obtain supplemental soil and groundwater data to evaluate additional remedial alternatives in the FS.
- Collect soil vapor, sub-slab vapor and indoor air samples to assess the vapor intrusion pathway.

The scope of work for the various phases of the Supplemental Remedial Investigation are described in the following sections of this report.

2.1 SOIL INVESTIGATION ACTIVITIES

2.1.1 Pre-Closure Soil Sampling

ITW contracted MACTEC Consultants (MACTEC) to coordinate and oversee closure and removal of the 10 onsite USTs. On May 20 and 21, 2004, MACTEC advanced 10 soil borings around the south and east sides of the UST area to collect soil samples. The soil samples were originally intended to be used in lieu of post-excavation samples. Soil samples were collected using hollow stem auger methods and were collected in 2-inch diameter split spoons. MACTEC collected soil samples from each boring at the UST invert depth of 12 feet below grade (fbg). Since only limited soil sampling had been done in the immediate vicinity of the spill area, URS participated in this soil boring program and collected additional soil samples at depths below the UST invert in the area of the 1988 1,1,1-TCA spill. The purpose of these samples was to delineate the extent of contamination detected in RI boring SB-98-2. URS collected soil samples from the MACTEC borings at depths ranging from 16 to 20 fbg. Samples were submitted under chain of custody documentation for analysis of Target Compound List (TCL) volatile organic compounds (VOCs).

2.1.2 UST Closure Soil Sampling

As stated previously, ITW, the property owner, removed the 10 onsite USTs. Each UST had an 8,000-gallon capacity, and had been out of use since January 2004. The UST closure was done in coordination with NYSDEC's Chemical Bulk Storage Division.

Closure activities commenced on August 23, 2004. A summary of MACTEC's activities is presented below. Labels painted on the ground and on piping inside the site building identified each UST by a number. According to the labels, the UST contents (when in service) were as follows:

<u>UST ID</u>	<u>Contents</u>
▪ UST # 1	Acetone
▪ UST # 2	Hexane
▪ UST # 3	Hexane
▪ UST # 4	Laktane
▪ UST # 5	Toluene
▪ UST # 6	Toluene
▪ UST # 7	Heptane

- UST # 8 MEK
- UST # 9 Toluene
- UST # 10 Acetone

The concrete pad around the USTs was broken using a jackhammer and removed. The UST piping was flushed out, disconnected and removed. A vac truck was used to pump residual liquids out of the USTs prior to removal. The interiors of the USTs were cleaned by a worker inside the tank. Due to concerns about damaging the structural integrity of the building, sheeting was driven into the ground around each UST prior to removal. A backhoe was used to remove backfill above and around each UST. Chains were then used to lift the UST out of the excavation. All USTs appeared to be in good condition. Each UST was 21.33 ft long with an 8 ft diameter, and was constructed of double-wall steel with a fiberglass lining. No visible holes or leaks were noted. The USTs had been installed in 1988. Following removal of each UST, both URS and MACTEC collected a post-excavation soil sample from the base of the excavation out of the backhoe bucket. The depth of the post-excavation soil samples was approximately 12 feet below grade.

During UST closure excavations, additional objects were encountered in the excavations. A series of pipes unrelated to the existing USTs was uncovered. A total of eight 2-inch steel pipes were found in the excavation about 2 feet below grade. Five of the pipes were oriented northwest and were located east of the USTs. The north end of the pipes bent downward to a depth of about 8 feet. Portions of the remaining three pipes were located adjacent to the other five, but they also turned and ran east-west between the two tank farms. The pipes were not connected to anything, but may have been associated with former Site USTs. The pipes were removed, cleaned, and disposed of with the USTs. URS collected two soil samples beneath the pipes and one sample from the soil stockpile removed from the deep end of the pipes. Also, in the area between the two tank farms where landfill debris is present, a small steel drum was located. The drum was rusted, partially crushed and in very poor condition. A black viscous tar-like liquid was observed in the drum. MACTEC removed the drum and surrounding soil and overpacked it for disposal. URS collected a soil sample from below the location where the drum was found. The soil was not stained. UST closure activities were documented in detail in MACTEC's *Site Assessment and UST Closure Report for TACC/ITW Facility, 159 Hanse Avenue, Freeport, New York*, dated December 21, 2005, submitted to NYSDEC's Chemical Bulk Storage Division.

2.1.3 Post-Closure Soil Sampling

Prior to removal of the USTs, soil sampling in the vicinity of the 1,1,1-TCA spill was limited because of the presence of the USTs. Also, since no as-built drawings were available, the exact location and orientation of the UST piping and the storm sewer piping were unknown, further limiting areas accessible for soil sampling. After the USTs were removed, the only known underground structure present in the spill area was the storm drain and associated piping. The piping was uncovered and replaced during closure activities so its location and orientation was known. This allowed for extensive soil sampling not possible when the USTs were in place. URS completed soil sampling beneath the former USTs and around the storm drain to delineate the nature and extent of soil impacts from the 1,1,1-TCA spill.

From October 6 to October 8, 2004, URS conducted soil sampling in the spill/UST area. The soil sampling was performed after the UST excavation had been backfilled with clean fill material, but before the area was paved. Soil samples were collected using direct-push methods and were collected in 4-foot long by 2-inch diameter macro-core samples with dedicated acetate liners. Drilling services were provided by Zebra Environmental Corporation of Lynbrook, New York.

Two sets of soil borings were incorporated into the program:

- 1) Closure verification borings. At the center of each former UST location a soil boring was advanced to 30 feet below grade. These borings were designated T-01 through T-10, corresponding with the UST Identification numbers listed in Section 2.1.2. In borings T-01 through T-10 soil samples were collected from the following depths: 16 to 18 ft bgs, 20 to 22 ft bgs, 24 to 26 ft bgs and 28 to 30 ft bgs. From each soil boring, the soil samples from 16 to 18 ft bgs and 20 to 22 ft bgs were analyzed for TCL VOCs with a one-week turnaround time. The results from these analyses were compared to the NYSDEC Recommended Soil Cleanup Objectives (RSCO), presented in NYSDEC Technical Administrative Guidance Document 4046 (TAGM). If exceedences of the NYSDEC RSCOs were detected in the 20 to 22 ft bgs sample, the two deeper samples from that boring were activated for VOC analysis.
- 2) Delineation borings. During the various stages of the RI, limited soil sampling was performed around the 1,1,1-TCA spill area. To delineate soil impacts detected in the RI soil samples, URS advanced 9 soil borings around the spill area (D-01 through D-09). Soil samples were collected from 10 to 12 ft bgs, 16 to 18 ft bgs, 20 to 22 ft bgs, 24 to 26 ft bgs and 28 to 30 ft bgs. From each soil boring, the soil samples from 10 to 12 ft bgs, 16

to 18 ft bgs and 20 to 22 ft bgs were analyzed for TCL VOCs with a one-week turnaround time. The results from these analyses were compared to the NYSDEC RSCOs. If exceedences of the NYSDEC RSCOs were detected in the 20 to 22 ft bgs sample, the two deeper samples from that boring were activated for VOC analysis.

A summary of the Post Closure Soil Sampling Program is provided in Table 1. Soil boring locations are shown on Figure 2. Boring logs are presented in Appendix B.

2.2 GROUNDWATER INVESTIGATION ACTIVITIES

2.2.1 2004 Groundwater VOC Sampling

Between June 7 and June 10, 2004, URS collected groundwater samples from all 15 existing site monitoring wells (9 shallow wells, 4 deep wells and 2 lower aquifer wells). Prior to sampling, a synchronous round of water level measurements was made in the wells. Each well was opened and the headspace was screened with a calibrated photoionization detector (PID). The well was then sounded with an interface probe capable of detecting free-phase NAPL. The depth to water and total depth of each well was measured from the surveyed top of the inner casing. After this round of measurements was made, the wells were sampled.

Wells were sampled using low-flow purging and sampling methods (Puls and Barcelona, 1996). The well was pumped with a peristaltic pump at a flow rate of 0.2 to 0.5 liters per minute (l/min). Water was pumped through a flow cell that contained a YSI Model 6820 water quality meter. The YSI contains probes that measure pH, specific conductance, temperature, turbidity, dissolved oxygen (DO) and oxidation-reduction potential (ORP). Measurements of these in-situ parameters were recorded every 3 to 5 minutes until they stabilized. A well was considered stabilized when the in-situ parameters changed less than 10% over 3 consecutive readings. Samples were collected from the pump discharge. Samples were submitted under chain of custody documentation for analysis of TCL VOCs. Samples were analyzed by Accutest Laboratories, a NYSDEC-certified laboratory (certification #10983) using NYSDEC ASP methods with Category B deliverables. A summary of the groundwater sampling program is presented in Table 2. Groundwater sampling logs are presented in Appendix C.

2.2.2 Groundwater Biofeasibility Sampling

Groundwater sampling during the Delaware Engineering RI did not include any sampling for biofeasibility parameters (parameters indicative of conditions conducive to biodegradation or

providing evidence of biodegradation). These parameters include field parameters such as pH, dissolved oxygen and oxidation-reduction potential (ORP). Laboratory parameters include dissolved gasses (ethane, ethane and methane), chloride, nitrate, nitrite, iron II and iron III, manganese II and manganese III, sulfate, alkalinity, and total organic carbon (TOC). URS completed sampling and analysis for these biofeasibility parameters as part of sampling from selected wells during the June 2004, April 2005 and June 2006 groundwater sampling events. Sampling was conducted using the sampling procedures described above and samples submitted for analysis to Accutest Laboratories under chain of custody documentation. A summary of the groundwater sampling program is presented in Table 2.

2.2.3 Off-Site Monitoring Well Installation and Sampling

Results of groundwater sampling conducted during the RI and performed by URS in June 2004 indicated that groundwater contamination is present at the western site boundary at concentrations exceeding the NYS Groundwater Standards (GWS). In June 2004, chloroethane was detected in well MS-97-1S at 430 µg/l and in well MW-98-9D at 510 µg/l, which exceed the NYS GWS of 5 µg/l. Chlorobenzene also was detected in well MW-98-9D at 7 µg/l, which exceeds the NYS GWS of 5 µg/l. Due to these exceedences at the downgradient site boundary, NYSDEC requested that BP install additional wells west of the site to delineate the downgradient extent of the chloroethane plume. After consulting with NYSDEC, downgradient well locations were selected on the west side of Hanse Avenue.

URS secured the required street opening permits from the Village of Freeport to install monitoring wells on the west side of Hanse Avenue. Downgradient wells MW-05-14S and MW-05-15D were installed on April 19 and 20, 2005. The wells were installed using standard hollow stem auger methods. Drilling services were provided by Aquifer Drilling & Testing (ADT) of New Hyde Park, New York. To avoid contact with subsurface utilities during drilling, each boring was advanced to 5 feet bgs using an "air knife". Boring MW-05-15D was continuously sampled with a split spoon sampler from 5 feet bgs to 38 ft bgs. Boring MW-05-14S was installed adjacent to MW-05-15D so split spoon samples were not collected. Wells MW-05-14S and MW-05-15D were constructed of 2-inch PVC with screen depths and intervals equivalent to those of wells MW-97-1S and MW-98-9D, respectively. Drill cuttings were drummed and temporarily stored in the former CCC building for subsequent offsite disposal. Boring logs and well construction diagrams are provided in Appendix D. After installation, the wells were developed by pumping with a submersible pump until clear of sediment. Well locations are shown on Figure 2.

On April 26, 2005, URS sampled new wells MW-05-14S and MW-05-15D, and existing wells MW-97-1S, MW-98-9D and MW-03-13S. Wells were purged using low-flow methods. Wells were pumped at 0.2 to 0.5 L/Min through a flow cell with a calibrated Horiba U-22 water quality meter, where measurements for pH, conductivity, temperature, DO, turbidity and ORP were made. Measurements were recorded every 3 to 5 minutes. When the readings had stabilized, the sample was collected through the pump tubing. The purge water and development water was drummed and temporarily stored in the former CCC building for subsequent offsite disposal. Samples were stored on ice and transported under chain-of custody documentation to Accutest Laboratories for analysis under the NYSDEC ASP protocols. Samples were analyzed for TCL VOCs.

2.2.4 Slug Testing

On October 6, 2005, URS conducted slug testing on four site wells. Falling head and rising head slug tests were conducted in wells MW-05-14S, MW-97-1S, MW-98-9D and MW-97-6S. Prior to each test, a pressure transducer was installed in the well and allowed to equilibrate. The transducer was connected to a Hermit 3000 datalogger. The slug was a five-foot long 1.5-inch diameter section of PVC pipe filled with cement. The slug was introduced into the water column of the well as the datalogger was simultaneously started for the falling head slug test. The datalogger was programmed to record at a logarithmic rate, in which more frequent readings are recorded at the start of the test when head changes are greatest, and less frequently as the test progresses. The greatest interval between readings was one minute. When the water level recovered to its pre-test depth, the rising slug test was initiated by simultaneously pulling the slug out of the water column and restarting the datalogger to record the rate at which the water level recovered to its pre-test depth. The slug and water level indicator were decontaminated between wells by scrubbing with an Alconox® solution and rinsing with deionized water. Slug test data was downloaded to a computer and analyzed using the Bouwer and Rice method (Bouwer and Rice, 1976) on a spreadsheet. Slug test data is presented in Appendix E.

2.2.5 2006 Groundwater VOC Sampling

In addition to the 2004 and 2005 groundwater sampling of selected and newly installed wells described above, between June 6 and June 9, 2006, URS collected groundwater samples from all 17 existing site monitoring wells (10 shallow wells, 5 deep wells and 2 lower aquifer wells). Groundwater samples were collected using methods described in Section 2.2.1. As with the June 2004 groundwater sampling event, samples were collected for additional parameters to assess

aquifer geochemical conditions and potential for natural attenuation of VOCs. Groundwater sampling logs are presented in Appendix C.

2.3 SOIL VAPOR INVESTIGATION ACTIVITIES

2.3.1 2005 Vapor Intrusion Sampling

At the request of NYDOH, a soil-gas survey was conducted to evaluate the presence of organic vapors in the subsurface at the Site. Prior to implementing the soil gas survey, URS prepared a work plan describing the details of the program. NYSDEC and NYSDOH reviewed and approved the work plan. The samples were collected in general accordance with the protocols described in the NYSDOH document “*FINAL Guidance for Evaluating Soil Vapor Intrusion in the State of New York*” dated October 2006. The sample locations, depicted on Figure 2, were as follows:

- Four sample locations, SG-05-01 and SG-05-04, located north, east, south and west, respectively of the former UST area. As requested by NYSDEC in its June 17, 2005 comments, sample location SG-05-02 was relocated adjacent to former soil-gas sampling location SG-16.
- Three sample locations, SG-05-05, SG-05-06, and SG-05-07 along the southern side of the Site building.
- Three sample locations, SG-05-08, SG-05-09, and SG-05-10 along the northern side of the Site building.
- Two ambient air/background air samples were obtained on the east and west sides of the site.
- As requested by NYSDEC in its June 17, 2005 comments, an additional sample location, SG-05-11, was added adjacent to the 1,1,1-TCA spill area.

At each sampling location (other than the background sample locations), a permanent soil vapor sampling point was installed. Permanent sampling points were installed so that if soil vapor contamination is detected, the concentrations can be monitored to evaluate the progress of future remedial measures at abating soil vapor contamination. Soil gas sampling points were installed by ADT, of New Hyde Park, New York on September 14 and 15, 2005. Prior to installation of

the sampling points, URS gauged nearby monitoring wells to assess the water table depths so that the soil gas point would be screened at least one foot above the water table. ADT advanced a 2-inch diameter hole through the concrete or asphalt surface to approximately 5 feet below grade. A $\frac{1}{4}$ -inch diameter polyethylene air sampling tube tipped with a 6-inch long stainless steel screen was advanced to the bottom of the borehole and the bottom 12 inches of the boring was filled with coarse sand to form the sampling zone. Each vapor sampling point was finished at grade with a flush-mount steel manhole and cover so that the points can be used for future monitoring.

The soil gas samples were collected on September 20 and 21, 2005. Samples were obtained using laboratory supplied pre-cleaned 6-liter SUMMA ® canisters. To evaluate the potential for “short circuit” of ambient air into soil vapor samples, a small polyethylene bucket, equipped with purge and vent ports as well as a grommet equipped with a $\frac{1}{4}$ -inch diameter hole for the sampling tube, was placed upside down over the sample point, with the sampling tube passing through the bottom of the bucket. A foam rubber gasket was placed around the edge of the bucket and which was held in place by weights to form a tight seal between the bucket and the ground surface around the sample point. The purge and vent ports on the bucket were opened and helium was introduced into the bucket space until an 80 to 100 percent concentration was measured at the vent port. Both ports were then closed.

The sampling line was purged at 200 cc/min and checked for helium intrusion and, if, 10 percent helium or less is measured, sampling for sub-slab vapors was initiated. The soil vapor sampling line was attached to the SUMMA Canister after the pre-sampling vacuum had been recorded. Each SUMMA Canister was equipped with a dedicated flow controller pre-set to collect the 6 liter sample over 30 minutes, or a maximum of 200 cc/min. During the sampling period, the sampling line was monitored periodically for the presence of helium by means of a helium detector and a tee port on the sampling line. No helium intrusion was detected. During the sampling period, the vacuum reading was also monitored. Soil gas sampling logs are presented in Appendix F.

After the sampling was completed, the SUMMA canister vacuum readings were recorded, chain-of-custody documentation was completed, and the samples were forwarded to the Accutest Laboratories, an ELAP certified laboratory for analysis. Sample analysis was performed following the U.S. EPA Compendium Method TO-15: Determination of Volatile Organic Compounds (VOCs) In Air Collected In Specially-Prepared Canisters And Analyzed By Gas Chromatography/Mass Spectrometry (GC/MS) (1999).

2.3.2 2006 Vapor Intrusion Sampling

Based on the results of the 2005 soil vapor sampling, NYDOH requested that BP collect additional samples, including:

- Three sub-slab vapor samples and two indoor air samples in the former Columbia Cement building;
- One outdoor ambient air sample;
- One sub-slab and one indoor air sample in the neighboring Knickerbocker Building;
- One sub-slab vapor sample at the neighboring Rohm & Haas building (along with an additional ambient air sample);.
- Resample selected exterior soil vapor sampling points.

On August 1, 2006, BP submitted a Revised Supplemental Soil Vapor Sampling Workplan that was accepted by NYSDEC and NYSDOH. On August 15, 2006, URS collected soil gas samples from sample points SG-05-1, SG-05-04, SG-05-05, SG-05-08 and SG-05-11. Sample locations are shown on Figure 2. Sampling procedures are described in Section 2.3.1. On August 16, 2006, samples were collected from the former Columbia Cement building and the Knickerbocker Building. Three sub-slab vapor samples were collected from former the Columbia Cement building (SS-06-01, SS-06-02 and SS-06-03). One sub-slab vapor sample (SS-06-03) was collected from the Knickerbocker building from a location near soil gas point SG-05-06. Sample locations were selected in the field following consultation with NYSDOH, NYSDEC and the Nassau County Board of Health, who observed the sampling.

Samples were collected by advancing a 4-inch diameter core barrel through the floor slab. A 6-inch long by ¼-inch diameter dedicated stainless steel screen was connected to polyethylene sample tubing. The sample screen was either driven into the aggregate below the slab or secured in the void space below the slab. The annular space between the sample tubing and slab was sealed with bentonite. As with the soil gas samples, a helium tracer gas was used to assess atmospheric intrusion into the sample.

Sub-slab vapor samples were collected using 6-liter SUMMA canisters. Samples were collected at a flow rate of 200 ml/minute for 30 minutes. When sampling was completed, the SUMMA canister valve was closed, the vacuum was recorded, and the canister was disconnected from the sample tubing. Sample tubing and screens were removed and the holes were grouted with bentonite and topped with concrete to match pre-existing surface conditions.

Two indoor air samples were collected from the former Columbia Cement building (IA-06-01 and IA-06-02). One indoor air sample was collected from the Knickerbocker building (IA-06-03), adjacent to sub-slab sample SS-06-04). In addition, one ambient air sample was collected outside the former Columbia Cement building, near the former UST area. Sample locations are shown on Figure 2. Indoor air samples and the ambient air samples were collected by placing a 6 L SUMMA canister approximately 4 feet above the ground and opening the valve to collect the sample at a flow rate of 200 ml/minute for 30 minutes. When sampling was completed, the SUMMA canister valve was closed and the vacuum was recorded. SVI samples were analyzed by Accutest Laboratories in Dayton, New Jersey.

Due to access restrictions, no sub-slab vapor was collected from the Rohm & Haas facility. On August 16, 2006, NYSDOH indicated that a shallow soil gas sample collected on the former Columbia Cement property, as close as reasonably possible to the Rohm & Haas building / property line would be an acceptable alternative. On October 5, 2006, an exterior sub-slab sample (SS-06-05) was collected approximately 10 feet from the Rohm & Haas building (about 3 feet from the property line). A track-mounted direct-push rig was used to advance a 2-inch diameter hole through the concrete pavement and 6 inches into the underlying aggregate and soil. Materials encountered beneath the concrete pavement included aggregate and landfill debris (silty sand with glass, metal and wood fragments). Sample SS-06-05 was collected using the same methods used to collect the interior sub-slab samples. In addition, one ambient air sample was collected, as described above. Due to a shortage of 6-liter SUMMA canisters, Accutest Laboratories could only provide 1-liter SUMMA canisters for this sampling event. Six-liter SUMMA canisters were provided by STL Laboratories of Burlington, Vermont. As a QA/QC check sub-slab sample SS-06-05 and ambient air sample AA-06-02 were collected using both 1-liter and 6-liter SUMMA canisters. Sample locations are shown on Figure 2. Soil gas, sub-slab vapor and indoor air sampling logs are presented in Appendix F.

2.4 TREATABILITY INVESTIGATION ACTIVITIES

2.4.1 Bench-Scale Treatability Testing

Upon review of data from soil and groundwater sampling described above, URS performed an initial analysis of potential alternatives for remediation of contaminated soil and groundwater at the site. The analysis allowed for screening of remedial technologies based on likelihood of success, ease of implementation and cost. Certain remedial technologies that were identified required laboratory bench-scale treatability testing to evaluate their effectiveness under site

conditions and to determine required dosages. These technologies include in-situ chemical oxidation (ISCO) to treat residual soil contamination in the source area and enhanced bioremediation to treat the downgradient groundwater VOC plume. The bench scale test results and other recent site data will be utilized in completing the updated FS and allow for evaluation of updated remedial options including enhanced and natural degradation to address residual contamination associated with the 1,1,1-TCA spill. The bench-scale treatability testing was performed by Adventus Americas, Inc. (Adventus), under subcontract to URS.

For the ISCO bench-scale treatability study, URS collected soil from the spill area by advancing a soil boring SB042005 through the base of the storm drain where the spill occurred (SD-1). Soil for the bench-scale testing was collected from split spoon samples and drill cuttings between 12 ft bgs and 22 ft bgs. into a 5-gallon pail. Groundwater from well MW-1D-97 was collected in a 5-gallon pail for use in the ISCO bench-scale tests. The soil and groundwater were shipped to Adventus' Mississauga, Ontario facility. Based on the compounds present in the soil, activated persulfate was chosen as the oxidant for testing. Two activation methods (hydrogen peroxide and chelated iron) were tested. The testing was conducted on combined soil and groundwater from the site. Testing was done using a series of laboratory vessels containing site soil/groundwater mixtures and injected doses of permanganate and activation agents. The mixes were then sampled over time to evaluate the effectiveness of the permanganate / activation agent combinations. Details of the bench-scale testing procedures are presented in Appendix G.

For the enhanced bioremediation bench-scale treatability study, soil was collected from soil borings MW-05-14S and MW-05-15D during installation of the offsite wells. Groundwater was collected from well MW-98-9D. Soil and groundwater were shipped in 5-gallon pails to Adventus' Mississauga, Ontario for the testing. Based on previous groundwater sampling data, the primary limiting factor for natural attenuation at the site was identified as available organic carbon in the subsurface. For this reason, two slow-release carbon sources were chosen for the bench-scale testing: HRC® and EHC®. These amendments were injected into columns packed with soil from the site. The tests were conducted in replicates along with appropriate sterile and non-sterile controls. Groundwater from the site was pumped through these columns at a rate to mimic the natural pore volume flush rate. Influent and effluent groundwater samples were collected periodically over a twelve-week period to assess the removal of COCs. Details of the bench-scale testing procedures are presented in Appendix G.

3.0 RESULTS

3.1 SOIL INVESTIGATION ACTIVITIES

3.1.1 Pre-Closure Soil Sampling

URS collected 11 soil samples from 10 soil borings around the perimeter of the UST area. Samples were collected at depths ranging from 16 to 20 feet below grade, where the highest spill-related impacts were detected during the RI and analyzed for TCL VOCs. No compounds were detected at concentrations exceeding the NYSDEC RSCOs. Acetone was detected in 10 of 11 samples at concentrations ranging from 0.027 mg/kg to 0.12 mg/kg, all of which are below the RSCO of 0.2 mg/kg. Methylene chloride was detected in 9 of 11 samples at concentrations ranging from 0.0006 mg/kg to 0.0014 mg/kg, all of which are below the RSCO of 0.1 mg/kg. Methylene chloride was also detected in laboratory blanks, suggesting its presence may be related to laboratory contamination. No impacts from the 1988 1,1,1-TCA spill were detected in the Pre-Closure Soil Boring samples. Sample results are presented in Table 3. Results are plotted in Figure 3.

3.1.2 Sampling During Building Owner's UST Closure

URS collected one soil sample from beneath each of the ten USTs removed in August and September 2004. In addition, URS collected two additional samples from the northeast and southeast corners of the UST # 6 excavation, and one sample from the northern sidewall of the UST #8. URS also collected a sample of the UST fill above UST #8 prior to removal of the UST. Soil samples were analyzed for TCL VOCs. Sample results are presented in Table 4. Results are plotted in Figure 3.

No compounds were detected above RSCOs in the post-excavation samples. In samples TANK6, TANK 6-3, TANK 7, TANK 9, no compounds were detected above laboratory detection limits. Toluene was detected in samples TANK 1 through TANK 5, TANK 6-2, TANK 8, TANK 8-2 and TANK 10 at concentrations ranging from 0.001 mg/kg to 0.006 mg/kg, well below the RSCO of 1.5 mg/kg. In sample TANK 10, 1,1,1-TCA was detected at 0.016 mg/kg, 1,1-DCA was detected at 0.006 mg/kg, well below their respective RSCO of 0.08 mg/kg and 0.2 mg/kg. Also in TANK 10, PCE was detected at 0.01 mg/kg and TCE was detected at 0.001 mg/kg, below their RSCOs of 1.4 mg/kg and 0.7 mg/kg, respectively.

In the other samples collected during UST closure activities, 1,1,1-TCA, 1,1-DCA and PCE were detected in sample DRAIN-1, below the storm drain line. 1,1-DCA and chloroform were detected in sample DRUM-1, below a damaged steel drum. Chloroform was detected in samples PIPE 1 and PIPE 2 (below piping discovered in the UST excavation) and toluene was detected in sample PIPE 1. No target VOCs were detected in sample PILE 1, from the soil stockpile removed from around the piping. All compounds noted above were detected at concentrations well below their respective RSCOs.

The only exceedences of RSCOs were detected in sample PIPE 3, which was soil taken from the inside of one of the pipes removed. In PIPE 3, ethylbenzene 14 mg/kg), toluene (32 mg/kg) and xylenes (150 mg/kg) were detected at concentrations exceeding their respective RSCOs of 5.5 mg/kg, 1.5 mg/kg and 1.2 mg/kg. No chlorinated solvents were identified in the sample. This suggests the piping was formerly used for a petroleum-based product, not a solvent. Similar concentrations were not found in subsurface soils at the Site, and ethylbenzene and xylenes were not detected in any other post-excavation soil sample above laboratory detection limits.

3.1.3 Post-Closure Soil Sampling

3.1.3.1 Closure Verification

URS collected 40 soil samples from 10 UST Closure Confirmation soil borings (T-1 through T-10) in the former UST area. Each boring was advanced at the center of a former UST location through the backfill material, approximately at the same location where the post-excavation soil sample was collected. Twenty seven of these samples were analyzed for TCL VOCs. Analytical results are presented in Table 5 and are plotted on Figure 3.

1,1,1-TCA was detected at concentrations exceeding the RSCO of 0.8 mg/kg in samples T-03-16-18, T-03-20-22 and T-08-16-18 at concentrations ranging from 2.2 mg/kg to 4,800 mg/kg. 1,1-DCA was detected at concentrations exceeding the RSCO of 0.2 mg/kg in T-01-16-18, T-02-16-18, T-03-16-18, T-03-20-22, T-07-20-22 and T-08-16-18 at concentrations ranging from 0.49 mg/kg to 390 mg/kg. 1,2-DCA and 1,1-DCE were detected in T-03-20-22 at 1.2 mg/kg and 18 mg/kg, respectively which exceed their respective RSCOs of 0.1 mg/kg and 0.4 mg/kg. Chloroethane was detected in samples T-03-16-18, T-03-20-22 and T-08-16-18 at concentrations exceeding the RSCO of 1.9 mg/kg at concentrations ranging from 9 mg/kg to 16 mg/kg.

The only compound detected in the UST Closure Confirmation borings at a concentration exceeding the RSCO that is not related to the 1988 1,1,1-TCA spill was acetone. Acetone was

detected in samples T-01-16-18, T-02-16-18, T-03-16-18 and T-04-16-18 at concentrations ranging from 0.23 mg/kg to 0.32 mg/kg, which exceeds the RSCO of 0.2 mg/kg. Other compounds at concentrations above method detection limits (MDLs) but below the RSCOs include 2-butanone, benzene, carbon disulfide, chlorobenzene, toluene, xylenes, methylene chloride, tetrachloroethene and trichloroethene.

3.1.3.2 Delineation Study

During the RI, exceedences of the NYSDEC RSCOs were detected in soil samples from borings SB-98-2, SB-98-3, SB-98-4 and MW-0-11A. From October 6 through October 8, 2004, URS advanced nine borings (D-01 through D-09) to confirm and delineate these exceedences. Sample depths were selected based on depths of exceedences in RI borings. Sample results are presented in Table 5 and are shown on Figure 3. Soil boring logs are presented in Appendix B.

Boring D-1 was advanced adjacent to RI borings SB-98-3 and MW-00-11A to confirm exceedences detected in these borings and assess whether soil contaminant concentrations have attenuated over time. In sample D-01-16-18 (16 to 18 ft bgs), 1,1,1-TCA (690 mg/kg), 1,1-DCA (11 mg/kg), 1,1-DCE (0.92 mg/kg) and chloroethane (8.4 mg/kg) were detected at concentrations exceeding RSCOs. No exceedences were detected in samples D-01-10-12 (10 to 12 ft bgs) and D-01-20-22 (20 to 22 ft bgs), so the impacted interval is vertically delineated at this location. The concentration of 1,1,1-DCA in D-01-16-18 (690 mg/kg) was significantly less than that in MW-00-11A at the same depth (2,600 mg/kg). 1,1-DCA and chloroethane were not detected in MW-00-11A, but exceeded the RSCOs in D-01-16-18. This suggests that 1,1,1-TCA in spill area soils has degraded to a degree, producing daughter products 1,1-DCA and chloroethane. Acetone (0.42 mg/kg) and 2-butanone (0.37 mg/kg) were also detected in D-01-16-18 at levels exceeding the RSCOs, but these compounds are not attributed to the 1988 1,1,1-TCA spill.

To the east of the spill area, borings D-2 and D-3 were advanced to delineate soil impacts detected in SB-98-2 at 10 to 13.7 ft bgs and 15.1 to 15.67 ft bgs. No exceedences of RSCOs were detected in 3 samples collected from boring D-2 at 10 to 12 ft bgs, 16 to 18 ft bgs and 20 to 22 ft bgs. In Boring D-3, 1,1-DCA was detected at 10 to 12 ft bgs at 0.26 mg/kg, which slightly exceeds the RSCO of 0.20 mg/kg. Based on these results, soil spill area impacts are effectively delineated to the east.

To the north of the spill area, no exceedences of RSCOs were detected in 3 samples from boring D-4, approximately 10 feet north of RI boring MW-00-11A. However, exceedences were detected further north in boring T-3 (see above).

Boring D-5 was advanced west of the spill area, approximately midway between storm drain SD-1 and boring SB-98-04. No exceedences of RSCOs were detected in boring D-5. Borings D-6 and D-7 were advanced about 10 feet and north and south, respectively, of RI boring SB-98-4, where 1,1-DCA(0.36 mg/kg), chloroethane (1.60 mg/kg) and acetone (0.57 mg/kg) were detected at concentrations exceeding the RSCOs. In sample D-07-10-12, 1,1,1-TCA (10 mg/kg), 1,1-DCA (75 mg/kg) and chloroethane (3.7 mg/kg) were detected at concentrations exceeding the RSCOs and greater than those in SB-98-4.

Boring D-8 was advanced about 10 feet south of storm drain SD-1. In sample D-08-10-12, 1,1,1-TCA (840 mg/kg), 1,1-DCA (100 mg/kg), 1,1-DCE (1.3 mg/kg) and 1,2-DCA (0.15 mg/kg) were detected at concentrations exceeding their respective RSCOs. No exceedences of RSCOs were detected in deeper samples from boring D-8. No exceedences of RSCOs were detected in samples from boring D-9, approximately 20 feet south of D-8.

3.1.4 Soil Investigation Summary

Based on the results described above, the extent of soil contamination in the spill area has been effectively delineated. Impacted soil at levels significantly exceeding the RSCOs is present in definable pockets. These areas are shown on Figure 4. Figure 4 also shows the orientation of cross-sections A-A', B-B', C-C' and D-D'. Soil sampling data from the RI and URS's Supplemental Investigation along these cross-sections are plotted on Figures 5 through 16. Concentrations of 1,1,1-TCA along the cross-section lines are shown on Figures 5 through 8. Concentrations of 1,1-DCA are shown in Figures 9 through 12 and chloroethane concentrations along the cross-sections are shown on Figures 13 through 16. These cross-sections show the vertical delineation of the primary spill-related soil contaminants in the spill area. The table on Figure 4 summarizes the vertical extent of each of the laterally delineated impacted areas. The table also shows the volume of each of the impacted areas and the volume of overlying non-impacted soil. The total volume of soil within the 4 pockets of contaminated soil is estimated at 1,100 cubic yards including clean soil and fill overlying the contaminated soil. The table shows that 610 cubic yards of soil and clean fill would need to be removed to excavate 490 cubic yards of impacted soil as a remedial measure.

3.2 GROUNDWATER INVESTIGATION ACTIVITIES

3.2.1 2004 Groundwater Sampling

3.2.1.1 Groundwater Levels and Flow

URS sampled existing site monitoring wells in June 2004. Groundwater level measurements and PID readings are presented on Table 6. Table 6 also presents the in-situ measurements recorded when the well had stabilized following purging. A water table elevation contour map for June 2004 is presented as Figure 17.

3.2.1.2 Groundwater Volatile Organic Compound Results

Sampling results from the June 2004 groundwater sampling event are presented in Table 7. Groundwater VOC results for all sampling events since 1997 are shown on Figure 19. As in groundwater sampling during the RI, the highest contaminant concentrations were detected in well MW-1S, adjacent to the spill location. 1,1,1-TCA, 1,1-DCA and chloroethane were detected in MW-1S at 150 µg/l, 660 µg/l and 10,000 µg/l, respectively, which exceeds their New York State Ambient Groundwater Quality Standard (GWS) of 5 µg/l. 1,1-DCE was detected at 4 µg/l, below the GWS of 5 µg/l. Several compounds unrelated to the 1988 1,1,1-TCA spill were also detected in MW-1S. Benzene and methylene chloride were detected at 15 µg/l and 230 µg/l, respectively, exceeding their respective GWS of 1 µg/l and 5 µg/l. Vinyl chloride was detected at 15 µg/l, exceeding the GWS of 2 µg/l. 1,2-DCA, ethylbenzene, toluene and xylenes were detected in MW-1S at concentrations below their GWS. It should be noted that the 2004 concentrations of 1,1,1-TCA (150 µg/l), 1,1-DCA (660 µg/l) and chloroethane (10,000 µg/l) in MW-1S were significantly below their 1997 concentrations of 2,600 µg/l, 47,000 µg/l and 49,000 µg/l, respectively, indicating that these compounds are attenuating over time in the spill area. Meanwhile, in nearby deep well MW-97-1D, no VOCs were detected at or above MDLs. Similarly, no VOCs were detected at or above MDLs in well MW-00-11A, screened below the lower gray clay layer.

To the west of the spill area, no VOCs were detected in shallow well MW-98-8S. Chloroethane was detected in well MW-98-8D at 14 µg/l, suggesting limited contaminant transport to the west of the spill area.

To the south of the spill area, chloroethane was detected in well MW-97-4S at 190 µg/l and chlorobenzene was detected at 1 µg/l, below its GWS of 5 µg/l. Chlorobenzene (79 µg/l) and 1,1-DCA (7 µg/l) were detected in well MW-97-5S at concentrations exceeding their GWS of 5 µg/l. In well MW-00-12D, no compounds were detected at laboratory detection limits.

In the northeast corner of the site in well MW-97-3S, chlorobenzene was detected at 8 µg/l. Chlorobenzene was also detected along the north central portion of the site in well MW-97-7S at 4 µg/l. Similarly, in the northeast corner of the site in wells MW-97-2S and MW-98-10D, chlorobenzene at 16 µg/l and 7 µg/l.

Along the southern Site boundary, about 100 feet southeast of the spill area, chloroethane (410 µg/l) and chlorobenzene (11 µg/l) were detected at concentrations exceeding the GWS. At the southeast (downgradient) corner of the Site in wells MW-97-1S and MW-98-9D, chloroethane was detected at 430 µg/l and 510 µg/l, respectively. Chlorobenzene was detected in wells MW-97-1S and MW-98-9D at 4 µg/l and 7 µg/l. Similarly, total xylenes were detected in wells MW-97-1S and MW-98-9D at 2 µg/l in both wells, below the GWS of 5 µg/l.

3.2.1.3 Groundwater Geochemical Data

In-situ physical parameter measurements made during purging are presented on Table 6. Geochemical sample data is presented in Table 7. Relevant physical and geochemical parameter data are plotted on Figure 20.

Natural attenuation of chlorinated VOCs typically occurs by reductive dechlorination, which generally occurs under anaerobic, reducing conditions. Dissolved oxygen was measured at less than 0.5 mg/l in all wells sampled, indicating anaerobic conditions. All wells also exhibited negative redox potential, ranging from -14.3 mV in well MW-97-7S to -207.3 mV in well MW-98-10D. This indicates a reducing environment, and it is noted that redox potentials of less than -150 mV would be most conducive to reductive dechlorination. Groundwater pH ranged from 6.19 to 6.67. The pH measured in MW-00-11A was 5.13, but this well is screened in a separate aquifer.

Ethane and ethene are indicators of reductive dechlorination, as these are the innocuous end products of the breakdown of chlorinated ethanes and ethenes. In Site wells in the gravelly sand aquifer, ethane concentrations ranged from 0.67 µg/l in MW-98-10D to 1,320 µg/l in MW-1S. The high ethane concentration in the spill area suggests degradation of 1,1,1-TCA to ethane.

Ethene was only detected in MW-1S, at 1.3 g/l. Methane is a product of anaerobic methanogenesis, another process which can contribute to the degradation of chlorinated VOCs. Methane concentrations ranged from 97 µg/l in MW-1D-97 to 10,000 µg/l in MW097-2S. The elevated methane concentrations are an indicator of methanogenesis.

The total alkalinity of groundwater system can be indicative of the extent to which degradation processes are occurring. The presence of carbon dioxide, produced during the respiration of organic compounds, can elevate alkalinity levels by forming carbonic acid, which subsequently dissolves carbonate minerals present in the affected groundwater system. On this basis, elevated concentrations of alkalinity in areas impacted by organic compounds contained in chlorinated solvents generally can be an indicator of natural attenuation. Alkalinity values ranged from 424 mg/l in MW-98-9D to 1,070 mg/l in MW-98-8S. Chloride is often a useful indicator of natural attenuation since it is produced during reductive dechlorination. Chloride values ranged from 38.4 mg/l in MW-97-2S to 388 mg/l in MW-97-3S. Total organic carbon (TOC) is the typical source of electrons needed to reduce chlorinated compounds. Higher concentrations (e.g. > 20 mg/l) indicate favorable conditions for natural attenuation (NA). TOC concentrations ranged from 6.3 mg/l in MW-97-5S to 22.9 mg/l in MW-97-3S.

3.2.2 Off-Site Monitoring Well Installation and Sampling

On April 19, 2005, monitoring wells MW-05-14S and MW-05-15D were installed in Hanse Avenue, approximately 70 feet west of MW-98-9D. The wells were installed as flushmount wells in Hanse Avenue. The lithology encountered was similar was similar to that encountered on Site. Fill material was present to a depth of about 25 feet below grade. The gray gravelly sand was encountered from 25 to 37 ft bgs. The gray silt/clay was encountered at 37 ft bgs.

On April 26, 2005, URS sampled these new wells for VOCs, as well as wells MW-97-1S, MW-98-9D and MW-00-13S. Water level and other field measurements are presented in Table 8. A groundwater elevation contour map for April 2005 is presented as Figure 17. The map shows that, as observed in the RI, the hydraulic gradient at the site is very low, about 0.0002 ft/ft. The map shows that, as observed in the RI, the hydraulic gradient at the site is very low, about 0.0002 ft/ft. Groundwater flow at the time of measurement was to the west. It should be noted that collecting a complete round of groundwater level measurements can take 2 to 3 hours. With tidal fluctuations, such measurements may not represent an actual "snapshot" of groundwater elevations. The contours should be considered accordingly. In the 2003 RI, measurements were made over an entire tidal cycle, and contour maps of high, low and mean tides were presented.

The mean tide contour map, which represents the overall groundwater flow pattern has no divide and flow is basically due west.

Groundwater VOC data is presented in Table 9 and is plotted on Figure 18. As in the June 2004 sampling event, no target VOCs were detected in well MW-03-13S. Chloroethane was detected in wells MW-97-1S and MW-98-9D at 170 µg/l and 910 µg/l, above the GWS of 50 µg/l. Chlorobenzene was detected in wells MW-97-1S and MW-98-9D at 3 µg/l and 9 µg/l. Chlorobenzene was detected in MW-05-14S at 24 µg/l, exceeding the GWS of 5 µg/l. Chlorobenzene was detected in MW-05-15D at 3 µg/l. Chloroethane was detected in MW-05-14S and MW-05-15D at 13 µg/l and 120 g/l, respectively. The presence of chloroethane in MW-05-15D indicates that contamination resulting from the 1988 1,1,1-TCA spill has migrated beyond the Site boundary. The source of the chlorobenzene contamination is not known, although it is not known to have been stored or used on Site. The 24 µg/l of chlorobenzene detected in MW-05-14S is higher than concentrations detected on Site.

3.2.3 2006 Groundwater Sampling

3.2.3.1 2006 Groundwater Levels and Flow

URS sampled existing site monitoring wells again in June 2006. Groundwater level measurements and PID readings are presented on Table 10. Table 10 also presents the in-situ measurements recorded when the well had stabilized following purging. A groundwater elevation contour map for June 2006 is presented as Figure 18. As stated previously, due to tidal fluctuations, the measurements may not represent an actual “snapshot” of groundwater elevations.

3.2.3.2 2006 Groundwater Volatile Organic Compound Results

Sampling results from the June 2006 groundwater sampling event are presented in Table 11. Groundwater VOC results for all sampling events since 1997 are shown on Figure 19. This was the first complete sampling round since the USTs were removed. In general, VOC concentrations in and around the spill area were significantly lower than those observed during previous sampling events. In well MW-1S, the concentration of chloroethane decreased from 10,000 µg/l in 2004 to 1,900 µg/l in June 2006. No other VOCs were detected in MW-1S at levels exceeding the MDLs, including 1,1,1-TCA, 1,1-DCA and vinyl chloride, which exceeded the GWS in prior sampling rounds but were below GWS in the 2006 sampling.

In nearby deep well MW-97-1D, chloroethane was detected at the GWS of 5 µg/l and 1,1-DCA was detected at 5.1 µg/l, marginally exceeding the GWS of 5 µg/l. No VOCs were detected at MDLs. As recently as 2003, chloroethane and 1,1-DCA were detected at 1,200 µg/l and 120 µg/l, respectively in MW-1D-97. Similarly, no VOCs were detected at laboratory MDLs in well MW-00-11A, screened below the lower gray clay layer.

To the west of the spill area, no VOCs were detected in shallow well MW-98-8S. Chloroethane was detected in well MW-98-8D at 38 µg/l, suggesting continued limited contaminant transport to the west of the spill area.

To the south of the spill area, chloroethane was detected in well MW-97-4S at only 3.0 µg/l, down from 190 µg/l in 2004. No other VOCs were not detected at or above their MDLs. In well MW-00-12D, Chloroethane was detected at 1,300 µg/l, and increase from 120 µg/l in 2004. 1,1-DCA and 1,1-DCE were detected at 11 µg/l and 5.8 g/l, respectively.

In the northeast corner of the site in well MW-97-3S, no VOCs were detected at or above the MDLs. In 2004, chlorobenzene was detected at 8 µg/l, marginally exceeding the GWS of 5 µg/l. Chlorobenzene was also detected along the north central portion of the site in well MW-97-7S at 1.3 µg/l. In the northeast corner of the Site in wells MW-97-2S and MW-98-10D, chlorobenzene was detected at 16 µg/l and 7.3 µg/l, respectively, similar to their 2004 concentrations.

Along the southern Site boundary, in well MW-97-6S, about 100 feet southeast of the spill area, chloroethane (200 µg/l) was detected at concentrations exceeding its GWS. Chlorobenzene (3.8 µg/l) was detected at a concentration below the GWS. At the southeast (downgradient) corner of the Site in wells MW-97-1S and MW-98-9D, chloroethane was detected at 730 µg/l and 120 µg/l, respectively, a decrease from 2004. Chlorobenzene was detected in wells MW-97-1S and MW-98-9D at 2.5 µg/l and 12 µg/l. No other VOCs were detected at concentrations exceeding their GWS.

In off Site shallow well MW-05-14S, chloroethane was detected at 1.0 µg/l and chlorobenzene was detected at 7.7 µg/l. In deep well MW-05-15D, chloroethane was detected at 200 µg/l, a slight increase from the 120 µg/l detected in 2005. Chlorobenzene was detected at 2.4 µg/l in MW-05-15D, below its GWS.

Although the groundwater chlorinated VOC plume has extended beyond the downgradient Site boundary, the data suggest significant natural attenuation is occurring in Site groundwater. In

spill area wells MW-1S and MW-1D-97, contaminant concentrations have decreased significantly over recent years. In shallow well MW-1S, 1,1,1-TCA concentrations decreased from 2,600 µg/l to less than 6.8 µg/l from 1997 to 2006, while 1,1-DCA decreased from 47,000 µg/l to less than 6.4 µg/l and chloroethane decreased from 49,000 µg/l to 1,900 µg/l over the same time period. The presence of chloroethane itself indicates reductive dechlorination of parent 1,1,1-TCA has and is occurring. Similarly, over the same time period, concentration of 1,1,1-TCA, 1,1-DCA and chloroethane in well MW-1D-97 decreased from 1,500 µg/l, 5,500 and 6,800 µg/l, respectively to less than 10 µg/l. Within 50 feet of the spill area, no 1,1,1-TCA is currently detected and the only spill-related compound currently above the GWS is chloroethane. Again, this illustrates limited extent of the plume and suggests significant natural attenuation of the chlorinated VOCs in Site groundwater. At the downgradient property boundary, chloroethane was detected in shallow and deep wells most recently at 120 µg/l and 720 µg/l, respectively. However, only 70 feet downgradient from these locations, chloroethane concentrations decreased to 1.0 µg/l and 200 µg/l, respectively, indicating that natural processes are limiting plume migration to some extent.

3.2.3.3 2006 Groundwater Geochemical Data

June 2006 in-situ physical parameter measurements made during purging are presented on Table 10. Geochemical sample data is presented in Table 12. Relevant physical and geochemical parameter data are plotted on Figure 20.

The June 2006 results for natural attenuation parameters are generally similar to those from 2004. Ethane and ethene were not detected in any wells, possibly due to elevated detection limits. Ethane was previously detected in several Site wells. Methane was detected at concentrations similar to those from 2004. Results for total and dissolved iron, alkalinity, chloride, sulfate and TOC were also close to the 2004 results.

Similarly, the in-situ parameters measured in 2006 during purging (pH, specific conductance, D.O. and ORP) were also similar to those from 2004. The pH values remain close to neutral, which will support biotic activity. The D.O. and ORP indicate that the aquifer remains anaerobic, which supports reductive dechlorination of 1,1,1-TCA, and 1,1-DCA.

Overall, Site groundwater geochemical conditions appear to be conducive to natural attenuation. The dissolved oxygen concentrations and redox potential indicate a reducing environment. Methane concentrations are indicative of methanogenesis. These conditions are supportive of

reductive dechlorination of 1,1,1-TCA to 1,1-DCA, and 1,1-DCA to chloroethane. However, these same conditions may not be as conducive to complete mineralization of chloroethane.

3.2.4 Slug Testing

Slug test data was analyzed using the Bouwer-Rice method (Bouwer and Rice, 1976). Data was downloaded from the datalogger and put into a spreadsheet. Known well parameters were entered into the spreadsheet. These parameters included the screen length (d), casing radius (r_c) and well radius (r_w). For all wells, the screen length is 10 feet. As in the RI slug tests, the casing radius and well radius values of 1-inch and 2-inches were used. Based on the RI slug test results and aquifer lithology, the effective radius (R_e), or radius impacted by the slug test, was estimated at 1 foot. The Bouwer-Rice solution was estimated by adjusting the x-axis intercept (h_0) and hydraulic conductivity (K) were adjusted to graphically fit a line to the appropriate portion of the drawdown curve plotted semi-logarithmically.

Wells MW-97-1S, MW-98-9D and MW-97-6S all exhibited very little displacement (0.34 feet to 0.65 feet) and recovered most of the initial displacement within a few seconds for both the falling head and rising head slug tests. The estimated average hydraulic conductivity values for these wells ranged from 34.63 ft/day ($1.22 \times 10^{-2} \text{ cm/sec}$) in MW-97-6S to 44.75 ft/day ($1.58 \times 10^{-2} \text{ cm/sec}$) in MW-97-1S. These results agree fairly well with results from the same wells during the RI slug tests. A comparison is presented in the following table:

WELL	URS SLUG TEST		DEL. ENG. SLUG TEST	
	K (cm/sec)	K (ft/day)	K (cm/sec)	K (ft/day)
MW-97-1S	1.58×10^{-2}	44.75	2.32×10^{-2}	65.77
MW-97-6S	1.22×10^{-2}	34.63	2.64×10^{-2}	74.84
MW-98-9D	1.51×10^{-2}	42.75	3.62×10^{-2}	102.63
MW-05-14S	7.77×10^{-4}	2.20	NA	NA

The slug test results from newly installed well MW-05-14S were notably different from results from the other Site wells. The initial displacement in MW-05-14S was up to 1.28 feet. The well also took about 3 minutes to recover from the initial displacement. The estimated average hydraulic conductivity of 2.2 ft/day (7.77 cm/sec) was an order of magnitude lower than the other wells tested. A complete summary of slug testing results is presented in table 13.

3.3 SOIL VAPOR INVESTIGATION RESULTS

3.3.1 2005 Soil Gas Sampling Results

Soil gas samples were collected from 11 sampling points (SG-05-01 through SG-05-11) on September 20 and 21, 2005. Two background ambient air samples (SG-05-AMB-E and SG-05-AMB-W). Sample results are presented in Table 14 and are plotted on Figure 21. Sample results are presented in units of both micrograms per cubic meter ($\mu\text{g}/\text{m}^3$) and parts per million by volume (ppbv).

The sampling results identified several VOCs. The VOCs most prevalently identified in soil gas included 1,1,1-TCA, 1,1-DCA, chloroethane, acetone, methylene chloride, heptane, hexane, toluene, benzene, ethylbenzene, xylene, tetrachloroethene, trichloroethene, vinyl chloride, carbon disulfide, carbon tetrachloride, chlorobenzene, cyclohexane, ethanol and freon. Some of these compounds correspond to Site related activities and/or the 1988 1,1,1-TCA spill. 1,1,1-TCA concentrations in the spill area ranged from $33 \mu\text{g}/\text{m}^3$ (6 ppbv) in SG-05-03 to $21,100 \mu\text{g}/\text{m}^3$ (3,870 ppbv). 1,1,1-TCA was not detected in samples SG-05-01, SG-05-07 and SG-05-08. In the spill area, 1,1-DCA was detected at concentrations ranging from $2,770 \mu\text{g}/\text{m}^3$ (733 ppbv) in SG-05-11 to $14,000 \mu\text{g}/\text{m}^3$ (3470 ppbv) in SG-05-04. 1,1-DCA was not detected in SG-05-01. Chloroethane was detected in spill area soil gas samples at concentrations ranging from $12 \mu\text{g}/\text{m}^3$ (4.7 ppbv) to $5,040 \mu\text{g}/\text{m}^3$ (1,910 ppbv). Chloroethane was not detected in SG-05-09. Several of the VOCs detected in soil gas were also detected in the two ambient air samples, including acetone, benzene, heptane, methylene chloride, tetrachloroethene, trichloroethene, toluene and xylenes.

The results indicate that soil gas impacts consisting of chlorinated VOCs are present in and around the UST / spill area, but concentrations of these compounds decrease with distance from this area. However, several VOCs were detected throughout the site and may be attributable to the Site's industrial setting and historic use of the Site area as a municipal landfill.

3.3.2 2006 Soil Vapor Intrusion Sampling Results

Vapor intrusion sampling data from the August and October 2006 sampling events is presented in Table 14. Sample results are presented in units of both micrograms per cubic meter ($\mu\text{g}/\text{m}^3$) and parts per million by volume (ppbv). The data are plotted on Figure 22.

3.3.2.1 Soil Gas

Soil gas samples were obtained from the spill area and from perimeter locations of exterior areas of the Site. Highest soil gas sample results were observed in the spill area. Concentrations were shown to rapidly attenuate with distance from the spill area. Compounds that were spill-related and non-spill-related were observed in the soil gas samples suggesting that ambient conditions associated with the landfill and industrial setting of the area likely influence soil gas sample results. Data are described below.

Three soil gas samples were collected from the spill/UST area (SG-05-01, SG-05-04 and SG-05-11). As observed in the 2005 sampling, compounds related to the 1988 1,1,1-TCA spill (1,1,1-TCA, 1,1-DCA, 1,1-DCE and chloroethane), as well as compounds stored in the former USTs (hexane and methyl cyclohexane, a component of Laktane) were detected at elevated concentrations in this area. 1,1,1-TCA concentrations ranged from non-detect to 50,600 µg/m³; 1,1-DCA concentrations ranged from non-detect to 56,700 µg/m³; and chloroethane concentrations ranged from 356 µg/m³ to 17,500 µg/m³. Hexane concentrations ranged from 1,240 µg/m³ to 20,700 µg/m³. Tetrachloroethene (PCE) was detected at concentration ranging from non-detect to 3,280 µg/m³ and trichloroethene was detected at non-detect to 1,590 µg/m³. Use and storage of PCE and TCE were not reported at the site, but given Site usage for adhesive manufacturing, past usage of these compounds is possible.

Three additional soil gas samples were collected from points around the Site perimeter. Sample SG-05-05 is located along the southern Site boundary; sample SG-05-08 is located in the northwest corner of the Site; and sample SG-05-10 is located in the northeast corner of the Site. In sample SG-05-05, 1,1,1-TCA, 1,1-DCA and chloroethane were detected at 1,300 µg/m³, 1,990 µg/m³, and 74.4 µg/m³, respectively. Other compounds detected at elevated concentrations include PCE (963 µg/m³), TCE (554 µg/m³), cis-1,2-DCE (140 µg/m³) and Freon 114 (368 µg/m³). In sample SG-05-08, 1,1-DCA and chloroethane were detected at 22 µg/m³ and 8.7 µg/m³, respectively. Other compounds detected at elevated concentrations include pentane (158 µg/m³), heptane (85.7 µg/m³) and hexane (83.2 µg/m³). In sample SG-05-10, 1,1,1-TCA, 1,1-DCA and chloroethane were detected at 25 µg/m³, 1,980 µg/m³, and 1,450 µg/m³, respectively. Other compounds detected at elevated concentrations include hexane (846 µg/m³), pentane (724 µg/m³), and heptane (141 µg/m³). Overall, the 2006 soil gas sampling results are similar to those from 2005.

3.3.2.2 Sub-Slab Vapor

Three sub-slab vapor samples were collected in the former Columbia Cement building. Sample SS-06-01 was collected in the room directly north of the spill area; sample SS-06-02 was collected in the room directly west of the spill area; and sample SS-06-03 was collected northwest of the spill area. As was the case for the soil vapor samples, highest concentrations were detected in closest proximity to the spill area, and concentrations of compounds attenuated rapidly with distance. In sample SS-06-01, 1,1,1-TCA and 1,1-DCA and were detected at 189 µg/m³ and 47.4 µg/m³, respectively. Chloroethane was not detected. Other compounds detected in SS-06-01 at elevated concentrations include PCE (195 µg/m³), TCE (57.5 µg/m³), acetone (129 µg/m³), xylenes (40 µg/m³) and MEK (63.4 µg/m³). In sample SS-06-02, 1,1,1-TCA, 1,1-DCA and chloroethane were detected at 86,200 µg/m³, 30,600 µg/m³, and 10,500 µg/m³, respectively. Other compounds detected at elevated concentrations include PCE (2,140 µg/m³), TCE (534 µg/m³), 1,1-DCE (308 µg/m³), and methylene chloride (251 µg/m³). In sample SS-06-03, 1,1,1-TCA and 1,1-DCA were detected at 14 µg/m³ and 8.9 µg/m³, respectively. Chloroethane was not detected. Other compounds detected at elevated concentrations include acetone (87.9 µg/m³), PCE (43 µg/m³), toluene (23 µg/m³), and xylenes (36 µg/m³).

In the Knickerbocker building, one sub-slab vapor sample was collected approximately 35 feet south of soil gas sample SG-05-05. In sample SS-06-04, 1,1,1-TCA and 1,1-DCA were detected at 27 µg/m³ and 10 µg/m³, respectively. Chloroethane was not detected. Other compounds detected at elevated concentrations include PCE (121 µg/m³), TCE (7.0 µg/m³), toluene (82.5 µg/m³), and xylenes (140 µg/m³).

Exterior sub-slab vapor sample SS-06-05 was collected about 10 feet west of the Rohm & Haas building. In sample SS-06-05, 1,1,1-TCA and 1,1-DCA were detected at 38 µg/m³ and 216 µg/m³, respectively. Chloroethane was not detected. Other compounds detected at elevated concentrations include PCE (564 µg/m³), TCE (58 µg/m³), acetone (208 µg/m³), and hexane (12 µg/m³).

The results indicate that sub-slab vapor has been impacted in the southwest portion of the site building, but the concentrations in other areas of the building are significantly lower. Also, sub-slab vapor at neighboring buildings is not significantly impacted.

3.3.2.3 Indoor Air Samples

Indoor air samples were obtained from the Columbia Cement building and the adjacent Knickerbocker building. At both locations, far fewer compounds were detected indoor air samples, and for those detected, the concentrations were significantly lower than in the sub-slab and soil vapor samples. This indicates only limited infiltration, if any, across the floor slabs of the buildings.

Two indoor air samples were collected within the former Columbia Cement building. Sample IA-06-01 was collected near sub-slab sample SS-06-02. Sample IA-06-02 was collected in the room immediately west of where sub-slab sample SS-06-03 was collected. 1,1,1-TCA, 1,1-DCA and chloroethane were not detected in sample IA-06-1. Compounds detected include toluene (18 µg/m³), xylenes (17 µg/m³), acetone (12 µg/m³) and hexane (6.7 µg/m³). In sample IA 06-02, 1,1,1-TCA was detected at a trace level of 0.93 µg/m³. 1,1-DCA and chloroethane were not detected. Compounds detected include acetone (18 µg/m³), toluene (8.7 µg/m³), xylenes (7.4 µg/m³), and hexane (3.9µg/m³).

In the Knickerbocker building, one indoor air sample (IA-06-03) was collected adjacent to sub-slab vapor sample SS-06-04. In sample IA-06-03, 1,1,1-TCA, 1,1-DCA and chloroethane were not detected. Compounds detected were similar to those detected in the former Columbia Cement building, and included acetone (20 µg/m³), MEK (5.9 µg/m³), and pentane (2.3 µg/m³).

The indoor air sampling results indicate the presence of low levels of VOCs. These VOCs consist primarily of BTEX compounds, hexane and acetone, not the chlorinated VOCs detected in the sub-slab vapor. This suggests that the slab is currently acting as an effective barrier against vapor intrusion.

3.3.2.4 Ambient Air Samples

One outdoor ambient air sample was collected on August 16, 2006 between the former UST area and the eastern property line. The compounds detected were TCE (31 µg/m³), cis-1,2-DCE µg/m³), acetone (1.3 µg/m³) and the methylene chloride (0.94 µg/m³). The source of the high ambient TCE concentration is not known, but is likely related to the industrial setting of the Site. On October 5, 2006, one ambient air sample was collected adjacent to sample SS-06-05. Compounds detected in sample AA-06-10-05 were MEK (36.3 µg/m³), toluene (15 µg/m³), pentane (2.7 µg/m³) and methylene chloride (2.3 µg/m³).

3.4 BENCH-SCALE TREATABILITY STUDY RESULTS

Bench-scale treatability testing was performed to evaluate the effectiveness of two potential remedial alternatives:

- 1) In-Situ Chemical Oxidation (ISCO) to treat spill area soil contamination; and
- 2) Enhanced Bioremediation to treat the downgradient chloroethane plume via a permeable reactive barrier (PRB).

3.4.1 In-Situ Chemical Oxidation Test

For the ISCO bench-scale test, soil was collected from boring SB-042005, which was advanced through the bottom of storm drain SD-1. Groundwater for the ISCO bench-scale test was collected from well MW-1D-97. Upon receipt at Adventus' lab, the soil and groundwater were sampled for VOCs and were spiked to match previously detected values in source area soil and groundwater. Mixtures of Site soil and groundwater were placed in jars for testing. Sodium persulfate ($\text{Na}_2\text{S}_2\text{O}_8$) was used as the oxidizing agent in the testing, as it has been demonstrated to be effective at treating chlorinated solvents. Hydrogen peroxide (H_2O_2) and ethylenediaminetetraacetic acid iron (III) sodium salt ($\text{NaFe(III)}\text{EDTA}$) were tested as activators to increase the oxidizing effectiveness of the persulfate. Details of the ISCO bench-scale treatability study are presented in the *Final Report – Bench Scale Test for Chemical Oxidation treatment of Chlorinated Solvent Impacted Soils* presented in Appendix G.

The results of the testing indicated that the highest removal efficiency was seen with hydrogen peroxide activated persulfate. This combination provided removal of 98.7% and 80% of 1,1,1-TCA in soil and groundwater, respectively and 99.5% and 99.4% removal of chloroethane in soil and groundwater, respectively 6 days following treatment. The iron activated sodium persulfate was much less successful at treating 1,1,1-TCA and chloroethane. Based on the testing results, the estimated treatment dosage is 42 g of sodium persulfate per Kg of soil and 60 g of hydrogen peroxide per Kg of soil.

3.4.2 Enhanced Natural Attenuation Test

For the enhanced bioremediation bench-scale test, soil was collected from boring MW-05-15D, which was advanced on the west side of Hanse Avenue and converted to monitoring well MW-

05-15D. Groundwater for the enhanced bioremediation bench-scale test was collected from well MW-98-9D. Upon receipt at Adventus' lab, the soil and groundwater were sampled for VOCs and were spiked to match previously detected values in downgradient soil and groundwater.

The objective of the enhanced natural attenuation bench scale test was to evaluate the effectiveness of HRC® and EHC® for use in a permeable reactive barrier (PRB) or other application to treat chloroethane in downgradient Site groundwater. HRC is a polylactic acid ester, which slowly releases lactic acid and other volatile organic acids (VFAs) including acetic, propionic, btyric and lactic acids in groundwater. The VFAs serve as electron donors and promote reductive chlorination of chlorinated VOCs.

EHC® is a combination of controlled-release solid carbon and zero-valent iron (ZVI) to stimulate reductive dechlorination. In contrast to HRC, the organic component of EHC is solid fibrous organic material that is nutrient rich and hydrophylic with a high surface area for growth of bacteria. Bacterial growth causes fermentation of the carbon and release of VFAs utilized by other bacteria in reductive dechlorination. The ZVI particles stimulate direct chemical dechlorination and further reduce the redox potential, providing a more reducing environment for these processes.

The HRC and EHC were combined with site soil in column systems. A total of six column systems were prepared, including sterile and non-sterile control columns. A detailed description of the test setup is provided in the *EHC and HRC Bench Scale Testing Final Report*, presented in Appendix F. Effluent samples were analyzed on six occasions over 107 days. The fifth sampling event at 94 days indicated that HRC and EHC were capable of treating chloroethane, with 62% and 52% removals, respectively, compared with 5% and 20% respective removals in the sterile and non-sterile controls. Overall, however, at the conclusion of the testing, the HRC and EHC amended columns did not show increased chloroethane removal compared to the sterile and non-sterile control columns because after 107 days, the chloroethane removal in the sterile and non-sterile controls was 51% and 88%, respectively. The EHC amended columns showed essentially the same removal (88%) as the non-sterile control. The HRC-amended columns had chloroethane removals of 96% and 99.5%, which was only 8% to 12% greater than the non-sterile control column. Therefore, the organic substrate amendments did not provide significant enhancements over the control columns. The non-sterile control column had a chloroethane rate of 88%, indicating significant naturally occurring biological and/or chemical degradation. The lack of enhanced biotic removal of chloroethane may be due to the lack of a microbial community capable of anaerobic biodegradation of chloroethane in downgradient soil. Details of the first enhanced bioremediation bench-scale testing are provided in Appendix G. A second treatability

test has evaluated aerobic biodegradation of chloroethane and the results of this test will be provided under separate cover.

4.0 SUMMARY

The results of this supplemental investigation, along with data gathered during the RI, can be summarized as follows:

- Soil contamination exceeding the NYSDEC RSCOs is present in the spill area. The contaminants present at concentration exceeding the RSCOs include spill-related compounds (1,1,1-TCA, 1,1-DCA and chloroethane), BTEX, acetone, methylene chloride and other compounds. The impacted soil has been delineated both laterally and vertically. The impacted soil is estimated to be in 4 pockets in the spill area. The estimated volume of impacted soil is 315 cubic yards, with 345 cubic yards of clean soil and fill overlying it. Contaminant concentration in adjacent borings at similar depth intervals have shown concentration decreases and signs of degradation over time. Also, the presence of 1,1,1-TCA daughter products indicates that the chlorinated VOCs are undergoing natural attenuation in the soil matrix.
- Groundwater contamination resulting from the spill has created a plume that has migrated beyond the western Site boundary. The groundwater contaminant plume also shows evidence of natural attenuation. Since 1997, 1,1,1-TCA concentrations within the source area wells have decreased approximately an order of magnitude, and with 50 feet of the spill area, 1,1,1,1-TCA is not detected in any wells. At the downgradient property boundary, chloroethane is the only spill-related compound detected, although it was also detected in offsite wells on the west side of Hanse Avenue.
- Geochemical conditions also appear to support natural attenuation of chlorinated ethanes. Dissolved oxygen and redox potential indicate a reducing environment. The dissolved oxygen concentrations and redox potential indicate a reducing environment. Ethane and methane concentrations are indicative of reductive dechlorination and methanogenesis, respectively. These conditions are supportive of reductive dechlorination of 1,1,1-TCA to 1,1-DCA, and 1,1-DCA to chloroethane. However, these conditions are not as conducive to the complete mineralization of chloroethane.
- Soil gas sampling indicated that VOCs are present in shallow soil throughout the Site. Concentrations of spill-related compounds were greatest in samples in and around the

spill area, but are detected around the site. Several other VOCs were detected in multiple soil gas samples, including BTEX, PCE, TCE, methylene chloride and several other compounds. Several of these compounds were also detected in ambient air samples collected outdoors at the Site.

- In the former Columbia Cement building, the indoor air concentrations of PCE, TCE and 1,1,1-TCA are three to five orders of magnitude lower than those found in the sub-slab vapor samples. The indoor air results are not at levels that would trigger any response measures based on information provided in the guidance manual. Furthermore, the indoor air concentrations do not exceed OSHA 8 hour PELs for the noted compounds. However, the sub-slab vapor concentrations of PCE ($2,140 \mu\text{g}/\text{m}^3$), TCE ($534 \mu\text{g}/\text{m}^3$) and 1,1,1-TCA ($86,200 \mu\text{g}/\text{m}^3$) are at levels where the matrices suggest mitigation as a potential response measure regardless of indoor air concentrations. The presence of these elevated sub-slab concentrations present a potential risk should the slab be compromised due to cracking or activities that might require cutting or coring the slab. It should be noted that the Site building remains unoccupied, thereby eliminating current exposure concerns in the building at this time.
- Bench scale treatability testing was performed to evaluate potential remedial options to treat soil and groundwater contamination at the Site. One test was conducted to test the effectiveness of in-site chemical oxidation to treat residual soil contamination in the spill area. The results of the test indicate that hydrogen peroxide activated persulfate successfully removed 98.7% and 80% of 1,1,1-TCA in soil and groundwater, respectively and 99.5% and 99.4% removal of chloroethane in soil and groundwater, respectively 6 days following treatment. Testing of EHC and HRC to for enhanced bioremediation of downgradient groundwater chloroethane contamination showed that the addition of amendments did not increase removal of chloroethane significantly over un-amended control columns.

The results of this Supplemental Remedial Investigation provide information to close several data gaps and satisfy data requests made by NYSDEC and NYDOH. The data gathered in this investigation, along with data from previous investigations provides a comprehensive understanding of Site conditions, contaminant distribution and feasible remedial options. The data from this Supplemental Remedial Investigation, along with data from the RI, will be used as a basis to prepare a FS for the Site. The FS will address soil, groundwater and soil gas contamination detected at the Site and will be submitted to NYSDEC shortly.

5.0 REFERENCES

- Bouwer, H., and Rice, R.C., 1976, A slug test for determining hydraulic conductivity of unconfined aquifers with completely or partially penetrating wells: Water Resources Research, 12(3): 423-428.
- Delaware Engineering, P.C., 2003. Final Remedial Investigation Report; Poultney Street; prepared for the Remediation Management (a BP Affiliated Company), Chesterton, Indiana; July.
- New York State Department of Environmental Conservation (NYSDEC), 1998. Ambient Water Quality Standards and Guidance Values and Groundwater Effluent Limitations, Water a Technical and Operational Guidance Series (TOGS) 1.1.1; Reissued June.
- New York State Department of Environmental Conservation (NYSDEC), 1990. Technical and Administrative Guidance Memorandum (TAGM) #4030: Selection of Remedial Actions at Inactive Hazardous Waste Sites; January.
- New York State Department of Environmental Conservation (NYSDEC), 1994. Technical and Administrative Guidance Memorandum (TAGM) #4046: Determination of Soil Cleanup Objectives and Cleanup Levels; January.
- New York State Department of Health (NYSDOH), 2006. Final Guidance for Evaluating Soil Vapor Intrusion in the State of New York; October.
- Puls, R.W., and Barcelona, M.J., 1996, *Low-flow (minimal drawdown) Ground-water Sampling Procedures*: EPA/540/S-95/504.
- United States Environmental Protection Agency, 1988. Guidance for Conducting Remedial Investigations and Feasibility Studies Under CERCLA, EPA/540/G-89/004, OSWER Directive 9355.3-01; October.

TABLE 1
SUMMARY OF SOIL ANALYTICAL PROGRAM
SUPPLEMENTAL REMEDIAL INVESTIGATION ACTIVITIES
FORMER COLUMBIA CEMENT FACILITY
FREREPORT, NEW YORK

Sampling Event	Location / Boring ID	Sample ID	Sample Depth (ft bgs)	Sample Date	Sampling Method	Analytical Parameters
PRE-CLOSURE SOIL BORINGS						
Boring B1	B1-18-20	18 - 20	5/20/2004	Split Spoon	VOCs	
Boring B2	B2-16-18	16 - 18	5/20/2004	Split Spoon	VOCs	
Boring B3	B3-16-18	16 - 18	5/20/2004	Split Spoon	VOCs	
Boring B4	B4-19.5-20	19.5 - 20	5/20/2004	Split Spoon	VOCs	
Boring B5	B5-19-20	19 - 20	5/20/2004	Split Spoon	VOCs	
Boring B6	B6-17.5-18	17 - 18	5/21/2004	Split Spoon	VOCs	
Boring B7	B7-17-18	17 - 18	5/21/2004	Split Spoon	VOCs	
Boring B7	B7-19-20	19 - 20	5/21/2004	Split Spoon	VOCs	
Boring B8	B8-18-19	18 - 19	5/21/2004	Split Spoon	VOCs	
Boring B9	B9-18-19	18 - 19	5/21/2004	Split Spoon	VOCs	
Boring B10	B10-19-20	19 - 20	5/21/2004	Split Spoon	VOCs	
UST CLOSURE POST-EXCAVATION SOIL SAMPLING						
TANK #1	TANK 1	12 - 12.5	8/27/2004	Backhoe Bucket	VOCs	
TANK #2	TANK 2	12 - 12.5	8/30/2004	Backhoe Bucket	VOCs	
TANK #3	TANK 3	12 - 12.5	8/31/2004	Backhoe Bucket	VOCs	
TANK #4	TANK 4	12 - 12.5	8/31/2004	Backhoe Bucket	VOCs	
TANK #5	TANK 5	12 - 12.5	9/1/2004	Backhoe Bucket	VOCs	
TANK #6	TANK 6	12 - 12.5	9/3/2004	Backhoe Bucket	VOCs	
TANK #6	TANK 6-2	~ 8	9/3/2004	Backhoe Bucket	VOCs	
TANK #6	TANK 6-3 SIDEWALL	~ 0.8	9/3/2004	Backhoe Bucket	VOCs	
TANK #7	TANK 7	12 - 12.5	9/3/2004	Backhoe Bucket	VOCs	
TANK #8	TANK 8	12 - 12.5	9/2/2004	Backhoe Bucket	VOCs	
TANK #8	TANK 8-2 ON TOP OF 8	1 - 1.5	9/2/2004	Backhoe Bucket	VOCs	
TANK #9	TANK 9	12 - 12.5	9/2/2004	Backhoe Bucket	VOCs	
TANK #10	TANK 10	12 - 12.5	9/2/2004	Backhoe Bucket	VOCs	

TABLE 1
SUMMARY OF SOIL ANALYTICAL PROGRAM
SUPPLEMENTAL REMEDIAL INVESTIGATION ACTIVITIES
FORMER COLUMBIA CEMENT FACILITY
FREEPORT, NEW YORK

Sampling Event	Location / Boring ID	Sample ID	Sample Depth (ft bgs)	Sample Date	Sampling Method	Analytical Parameters
UST CLOSURE POST-EXCAVATION SOIL SAMPLING (continued)						
UST BACKFILL	BACKFILL 1	12 - 12.5	5/21/2004	Stockpile	VOCS	
UST BACKFILL	BACKFILL 1	12 - 12.5	5/21/2004	Stockpile	VOCS	
BENEATH SEWER PIPE	DRAIN 1	3 - 3.5	9/15/2004	Scoop	VOCs, SVOCs	
BENEATH LEAKING DRUM	DRUM 1	3 - 3.5	9/15/2004	Scoop	VOCS	
PIPE EXC. SOIL PILE	PILE 1	3 - 3.5	9/15/2004	Stockpile	VOCS	
BENEATH PIPING	PIPE 2	3 - 3.5	9/15/2004	Backhoe Bucket	VOCS	
BENEATH PIPING	PIPE 2	8 - 8.5	9/15/2004	Scoop	VOCS	
SOIL INSIDE PIPING	PIPE 3	N/A	9/1/2004	Scoop	VOCS	
POST-CLOSURE SOIL BORINGS						
Boring T-01	T-01-16-18	16 - 18	10/6/2004	Macro-Core Sampler	VOCS	
Boring T-01	T-01-20-22	20 - 22	10/6/2004	Macro-Core Sampler	VOCS	
Boring T-02	T-02-16-18	16 - 18	10/6/2004	Macro-Core Sampler	VOCS	
Boring T-02	T-02-20-22	20 - 22	10/6/2004	Macro-Core Sampler	VOCS	
Boring T-02	T-02-24-26	24 - 26	10/6/2004	Macro-Core Sampler	VOCS	
Boring T-02	T-02-28-30	28 - 30	10/6/2004	Macro-Core Sampler	VOCS	
Boring T-03	T-03-16-18	16 - 18	10/6/2004	Macro-Core Sampler	VOCS	
Boring T-03	T-03-20-22	20 - 22	10/6/2004	Macro-Core Sampler	VOCS	
Boring T-03	T-03-24-26	24 - 26	10/6/2004	Macro-Core Sampler	VOCS	
Boring T-03	T-03-28-30	28 - 30	10/6/2004	Macro-Core Sampler	VOCS	
Boring T-04	T-04-16-18	16 - 18	10/6/2004	Macro-Core Sampler	VOCS	
Boring T-04	T-04-20-22	20 - 22	10/6/2004	Macro-Core Sampler	VOCS	
Boring T-05	T-05-16-18	16 - 18	10/6/2004	Macro-Core Sampler	VOCS	
Boring T-05	T-05-20-22	20 - 22	10/6/2004	Macro-Core Sampler	VOCS	
Boring T-06	T-06-16-18	16 - 18	10/6/2004	Macro-Core Sampler	VOCS	
Boring T-06	T-06-20-22	20 - 22	10/6/2004	Macro-Core Sampler	VOCS	

TABLE 1

**SUMMARY OF SOIL ANALYTICAL PROGRAM
SUPPLEMENTAL REMEDIAL INVESTIGATION ACTIVITIES
FORMER COLUMBIA CEMENT COMPANY FACILITY
FREEPORT, NEW YORK**

Sampling Event	Location / Boring ID	Sample ID	Sample Depth (ft bgs)	Sample Date	Sampling Method	Analytical Parameters
POST-CLOSURE SOIL BORINGS (continued)						
Boring T-07	T-07-16-18	16 - 18	10/7/2004	Macro-Core Sampler	VOCS	
Boring T-07	T-07-20-22	20 - 22	10/7/2004	Macro-Core Sampler	VOCS	
Boring T-07	T-07-24-26	24 - 26	10/7/2004	Macro-Core Sampler	VOCS	
Boring T-07	T-07-28-30	28 - 30	10/7/2004	Macro-Core Sampler	VOCS	
Boring T-08	T-08-16-18	16 - 18	10/7/2004	Macro-Core Sampler	VOCS	
Boring T-08	T-08-20-22	20 - 22	10/7/2004	Macro-Core Sampler	VOCS	
Boring T-08	T-08-24-26	24 - 26	10/7/2004	Macro-Core Sampler	VOCS	
Boring T-09	T-09-16-18	16 - 18	10/7/2004	Macro-Core Sampler	VOCS	
Boring T-09	T-09-20-22	20 - 22	10/7/2004	Macro-Core Sampler	VOCS	
Boring T-10	T-10-16-18	16 - 18	10/7/2004	Macro-Core Sampler	VOCS	
Boring T-10	T-10-20-22	20 - 22	10/7/2004	Macro-Core Sampler	VOCS	
Boring D-01	D-01-10-12	10 - 12	10/7/2004	Macro-Core Sampler	VOCS	
Boring D-01	D-01-16-18	16 - 18	10/7/2004	Macro-Core Sampler	VOCS	
Boring D-01	D-01-20-22	20 - 22	10/7/2004	Macro-Core Sampler	VOCS	
Boring D-02	D-02-10-12	10 - 12	10/7/2004	Macro-Core Sampler	VOCS	
Boring D-02	D-02-16-18	16 - 18	10/7/2004	Macro-Core Sampler	VOCS	
Boring D-02	D-02-20-22	20 - 22	10/7/2004	Macro-Core Sampler	VOCS	
Boring D-03	D-03-10-12	10 - 12	10/8/2004	Macro-Core Sampler	VOCS	
Boring D-03	D-03-16-18	16 - 18	10/8/2004	Macro-Core Sampler	VOCS	
Boring D-03	D-03-20-22	20 - 22	10/8/2004	Macro-Core Sampler	VOCS	
Boring D-04	D-04-10-12	10 - 12	10/8/2004	Macro-Core Sampler	VOCS	
Boring D-04	D-04-16-18	16 - 18	10/8/2004	Macro-Core Sampler	VOCS	
Boring D-04	D-04-20-22	20 - 22	10/8/2004	Macro-Core Sampler	VOCS	
Boring D-05	D-05-10-12	10 - 12	10/8/2004	Macro-Core Sampler	VOCS	
Boring D-05	D-05-16-18	16 - 18	10/8/2004	Macro-Core Sampler	VOCS	

TABLE 1
SUMMARY OF SOIL ANALYTICAL PROGRAM
SUPPLEMENTAL REMEDIAL INVESTIGATION ACTIVITIES
FORMER COLUMBIA CEMENT FACILITY
FREREPORT, NEW YORK

Sampling Event	Location / Boring ID	Sample ID	Sample Depth (ft bgs)	Sample Date	Sampling Method	Analytical Parameters
POST-CLOSURE SOIL BORINGS (continued)						
	Boring D-05	D-05-20-22	20 - 22	10/8/2004	Macro-Core Sampler	VOCS
	Boring D-06	D-06-10-12	10 - 12	10/8/2004	Macro-Core Sampler	VOCS
	Boring D-06	D-06-16-18	16 - 18	10/8/2004	Macro-Core Sampler	VOCS
	Boring D-06	D-06-20-22	20 - 22	10/8/2004	Macro-Core Sampler	VOCS
	Boring D-07	D-07-10-12	10 - 12	10/6/2004	Macro-Core Sampler	VOCS
	Boring D-07	D-07-16-18	16 - 18	10/6/2004	Macro-Core Sampler	VOCS
	Boring D-07	D-07-20-22	20 - 22	10/6/2004	Macro-Core Sampler	VOCS
	Boring D-08	D-08-10-12	10 - 12	10/8/2004	Macro-Core Sampler	VOCS
	Boring D-08	D-08-16-18	16 - 18	10/8/2004	Macro-Core Sampler	VOCS
	Boring D-08	D-08-20-22	20 - 22	10/8/2004	Macro-Core Sampler	VOCS
	Boring D-08	D-08-24-26	24 - 26	10/8/2004	Macro-Core Sampler	VOCS
	Boring D-09	D-09-12-14	12 - 14	10/8/2004	Macro-Core Sampler	VOCS
	Boring D-09	D-09-14-16	14 - 16	10/8/2004	Macro-Core Sampler	VOCS

NOTES:

ft bgs : Feet below ground surface

VOCS : Volatile Organic Compounds

SVOCs : Semi-Volatile organic compounds

TABLE 2
 SUMMARY OF GROUNDWATER ANALYTICAL PROGRAM
 SUPPLEMENTAL REMEDIAL INVESTIGATION ACTIVITIES
 FORMER COLUMBIA CEMENT FACILITY
 FREEPORT, NEW YORK

Sampling Event	Well ID	Sample ID	Sample Date	Sampling Method	Analytical Parameters
JUNE 2004 SAMPLING EVENT					
	MW-1S	MW-1S	6/7/2004	Low-Flow	VOCs, Dissolved Gasses, Fe II, Total Fe, Mn II, Chloride, Nitrate, Nitrite, Sulfate, Total Organic Carbon, Alkalinity
	MW-97-1S	MW-97-1S	6/8/2004	Low-Flow	VOCs, Dissolved Gasses, Fe II, Total Fe, Mn II, Total Mn, Chloride, Nitrate, Nitrite, Sulfate, Total Organic Carbon, Alkalinity
	MW-1D-97	MW-1D-97	6/7/2004	Low-Flow	VOCs, Dissolved Gasses, Fe II, Total Fe, Mn II, Total Mn, Chloride, Nitrate, Nitrite, Sulfate, Total Organic Carbon, Alkalinity
	MW-97-2S	MW-97-2S	6/8/2004	Low-Flow	VOCs, Dissolved Gasses, Fe II, Total Fe, Mn II, Total Mn, Chloride, Nitrate, Nitrite, Sulfate, Total Organic Carbon, Alkalinity
	MW-97-3S	MW-97-3S	6/9/2004	Low-Flow	VOCs, Dissolved Gasses, Fe II, Total Fe, Mn II, Total Mn, Chloride, Nitrate, Nitrite, Sulfate, Total Organic Carbon, Alkalinity
	MW-97-4S	MW-97-4S	6/10/2004	Low-Flow	VOCs, Dissolved Gasses, Fe II, Total Fe, Chloride, Nitrate, Nitrite, Sulfate, Total Organic Carbon, Alkalinity
	MW-97-5S	MW-97-5S	6/10/2004	Low-Flow	VOCs, Dissolved Gasses, Fe II, Total Fe, Mn II, Total Mn, Chloride, Nitrate, Nitrite, Sulfate, Total Organic Carbon, Alkalinity
	MW-97-6S	MW-97-6S	6/10/2004	Low-Flow	VOCs, Dissolved Gasses, Fe II, Total Fe, Mn II, Total Mn, Chloride, Nitrate, Nitrite, Sulfate, Total Organic Carbon, Alkalinity
	MW-97-7S	MW-97-7S	6/9/2004	Low-Flow	VOCs
	MW-98-8S	MW-98-8S	6/9/2004	Low-Flow	VOCs, Dissolved Gasses, Fe II, Total Fe, Mn II, Total Mn, Chloride, Nitrate, Nitrite, Sulfate, Total Organic Carbon, Alkalinity
	MW-98-8D	MW-98-8D	6/9/2004	Low-Flow	VOCs, Dissolved Gasses, Fe II, Total Fe, Mn II, Total Mn, Chloride, Nitrate, Nitrite, Sulfate, Total Organic Carbon, Alkalinity
	MW-98-9D	MW-98-9D	6/8/2004	Low-Flow	VOCs, Dissolved Gasses, Fe II, Total Fe, Mn II, Total Mn, Chloride, Nitrate, Nitrite, Sulfate, Total Organic Carbon, Alkalinity
	MW-98-10D	MW-98-10D	6/8/2004	Low-Flow	VOCs, Dissolved Gasses, Fe II, Total Fe, Mn II, Total Mn, Chloride, Nitrate, Nitrite, Sulfate, Total Organic Carbon, Alkalinity
	MW-00-11A	MW-00-11A	6/9/2004	Low-Flow	VOCs
	MW-00-12D	MW-00-12D	6/10/2004	Low-Flow	VOCs, Dissolved Gasses, Fe II, Total Fe, Mn II, Total Mn, Chloride, Nitrate, Nitrite, Sulfate, Total Organic Carbon, Alkalinity
	MW-03-13S	MW-03-13S	6/10/2004	Low-Flow	VOCs, Dissolved Gasses, Fe II, Total Fe, Mn II, Total Mn, Chloride, Nitrate, Nitrite, Sulfate, Total Organic Carbon, Alkalinity

TABLE 2
 SUMMARY OF GROUNDWATER ANALYTICAL PROGRAM
 SUPPLEMENTAL REMEDIAL INVESTIGATION ACTIVITIES
 FORMER COLUMBIA CEMENT FACILITY
 FREEPORT, NEW YORK

Sampling Event	Well ID	Sample ID	Sample Date	Sampling Method	Analytical Parameters
MAY 2005 SAMPLING EVENT					
	MW-97-1S	MW-97-1S	4/26/2005	Low-Flow	VOCs
	MW-98-9D	MW-98-9D	4/26/2005	Low-Flow	VOCs
	MW-00-13S	MW-00-13S	4/26/2005	Low-Flow	VOCs
	MW-05-14S	MW-05-14S	4/26/2005	Low-Flow	VOCs
	MW-05-15D	MW-05-15D	4/26/2005	Low-Flow	VOCs

TABLE 2
SUMMARY OF GROUNDWATER ANALYTICAL PROGRAM
SUPPLEMENTAL REMEDIAL INVESTIGATION ACTIVITIES
FORMER COLUMBIA CEMENT FACILITY
FREEPORT, NEW YORK

Sampling Event	Well ID	Sample ID	Sample Date	Sampling Method	Analytical Parameters
JUNE 2006 SAMPLING EVENT					
	MW-1S	MW-1S	6/7/2006	Low-Flow	VOCs, Dissolved Gasses, Fe II, Total Fe, Chloride, Sulfate, Total Organic Carbon, Alkalinity
	MW-97-1S	MW-97-1S	6/7/2006	Low-Flow	VOCs, Dissolved Gasses, Fe II, Total Fe, Chloride, Sulfate, Total Organic Carbon, Alkalinity
	MW-1D-97	MW-1D-97	6/7/2006	Low-Flow	VOCs, Dissolved Gasses, Fe II, Total Fe, Chloride, Sulfate, Total Organic Carbon, Alkalinity
	MW-97-2S	MW-97-2S	6/9/2006	Low-Flow	VOCs, Dissolved Gasses, Fe II, Total Fe, Chloride, Sulfate, Total Organic Carbon, Alkalinity
	MW-97-3S	MW-97-3S	6/9/2006	Low-Flow	VOCs, Dissolved Gasses, Fe II, Total Fe, Chloride, Sulfate, Total Organic Carbon, Alkalinity
	MW-97-4S	MW-97-4S	6/8/2006	Low-Flow	VOCs, Dissolved Gasses, Fe II, Total Fe, Chloride, Sulfate, Total Organic Carbon, Alkalinity
	MW-97-5S	MW-97-5S	6/9/2006	Low-Flow	VOCs, Dissolved Gasses, Fe II, Total Fe, Chloride, Sulfate, Total Organic Carbon, Alkalinity
	MW-97-6S	MW-97-6S	6/8/2006	Low-Flow	VOCs, Dissolved Gasses, Fe II, Total Fe, Chloride, Sulfate, Total Organic Carbon, Alkalinity
	MW-97-7S	MW-97-7S	6/6/2006	Low-Flow	VOCs, Dissolved Gasses, Fe II, Total Fe, Chloride, Sulfate, Total Organic Carbon, Alkalinity
	MW-98-8S	MW-98-8S	6/7/2006	Low-Flow	VOCs, Dissolved Gasses, Fe II, Total Fe, Chloride, Sulfate, Total Organic Carbon, Alkalinity
	MW-98-8D	MW-98-8D	6/7/2006	Low-Flow	VOCs, Dissolved Gasses, Fe II, Total Fe, Chloride, Sulfate, Total Organic Carbon, Alkalinity
	MW-98-9D	MW-98-9D	6/8/2006	Low-Flow	VOCs, Dissolved Gasses, Fe II, Total Fe, Chloride, Sulfate, Total Organic Carbon, Alkalinity
	MW-98-10D	MW-98-10D	6/9/2006	Low-Flow	VOCs, Dissolved Gasses, Fe II, Total Fe, Chloride, Sulfate, Total Organic Carbon, Alkalinity
	MW-00-11A	MW-00-11A	6/7/2006	Low-Flow	VOCs, Dissolved Gasses, Fe II, Total Fe, Chloride, Sulfate, Total Organic Carbon, Alkalinity
	MW-00-12D	MW-00-12D	6/8/2006	Low-Flow	VOCs, Dissolved Gasses, Fe II, Total Fe, Chloride, Sulfate, Total Organic Carbon, Alkalinity
	MW-03-13S	MW-03-13S	6/6/2006	Low-Flow	VOCs, Dissolved Gasses, Fe II, Total Fe, Chloride, Sulfate, Total Organic Carbon, Alkalinity
	MW-05-14S	MW-05-14S	6/8/2006	Low-Flow	VOCs, Dissolved Gasses, Fe II, Total Fe, Chloride, Sulfate, Total Organic Carbon, Alkalinity
	MW-05-15D	MW-05-15D	6/6/2006	Low-Flow	VOCs, Dissolved Gasses, Fe II, Total Fe, Chloride, Sulfate, Total Organic Carbon, Alkalinity

NOTES:

VOCs : Volatile Organic Compounds
 Diss. Gases : Ethane, ethene and methane
 Fe II : Dissolved (Ferrous) Iron
 Total Fe : Total Iron
 Mn II : Dissolved Manganese
 Total Mn : Total Manganese

TABLE 3
SUMMARY OF SOIL ANALYTICAL RESULTS
PRE-JUST CLOSURE SOIL BORINGS
FORMER COLUMBIA CEMENT COMPANY FACILITY
FREREPORT, NEW YORK

URS SAMPLE ID	NYSDOC LAB SAMPLE ID	NYSDOC TEST DATE	B1-8-20	B2-5-18	B3-6-18	B4-19-5-20	B5-19-20	B6-17-5-18	B7-17-18
SAMPLE DATE			05/09/01	05/09/01	05/20/04	05/20/04	05/20/04	05/21/04	05/21/04
SAMPLE DEPTH (ft)			06' 20"	06' 20"	18'	19' 5"	19' 20"	17' 5" - 18'	17' 18"
DILUTION FACTOR			1	1	1	1	1	1	1
MASS (g)			(mg/g)	(mg/g)	(mg/g)	(mg/g)	(mg/g)	(mg/g)	(mg/g)
VOCs									
1,1,1-Trichloroethane	~661	0.8	0.0047	J	0.0056	U	0.0061	U	0.006
1,1,2,2-Tetrachloroethane	0.6		0.0012	U	0.0011	U	0.0012	U	0.0012
1,1,2-Trichloroethane	NA		0.0035	U	0.0033	U	0.0035	U	0.0036
1,1-Dichloroethane	0.2		0.0024	J	0.0056	U	0.0058	U	0.0061
1,1-Dichloroethene	0.4		0.0024	U	0.0022	U	0.0023	U	0.0024
1,2-Dichloroethane	0.1		0.0024	U	0.0022	U	0.0023	U	0.0024
1,2-Dichloropropane	NA		0.0012	U	0.0011	U	0.0012	U	0.0012
2-Butanone	0.3		0.0059	U	0.0056	U	0.0058	U	0.0061
2-Hexanone	NA		0.0059	U	0.0056	U	0.0058	U	0.0061
Acetone	0.2		0.1		0.082		0.027		0.12
Benzene	0.06		0.0012	U	0.0011	U	0.0012	U	0.0012
Bromodichloromethane	NA		0.0012	U	0.0011	U	0.0012	U	0.0012
Bromoform	NA		0.0047	U	0.0044	U	0.0047	U	0.0049
Bromomethane	NA		0.0059	U	0.0056	U	0.0058	U	0.0061
Carbon Disulfide	2.7		0.0024	J	0.0012	J	0.0007	J	0.0012
Carbon Tetrachloride	0.6		0.0024	U	0.0022	U	0.0023	U	0.0024
Chlorobenzene	1.7		0.0059	U	0.0056	U	0.0058	U	0.0061
Chloroethane	1.9		0.0059	U	0.0056	U	0.0058	U	0.0061
Chloroform	0.3		0.0059	U	0.0056	U	0.0058	U	0.0061
Chloromethane	NA		0.0059	U	0.0056	U	0.0058	U	0.0061
cis-1,2-Dichloroethene	NA		0.0059	U	0.0056	U	0.0058	U	0.0061
cis-1,3-Dichloropropene	NA		0.0059	U	0.0056	U	0.0058	U	0.0061
Dibromochloromethane	NA		0.0059	U	0.0056	U	0.0058	U	0.0061
Ethylbenzene	5.5		0.0047	J	0.0044	J	0.0047	J	0.0049
4-Methyl-2-Pentanone	1		0.0059	U	0.0056	U	0.0058	U	0.0061
Methylene Chloride	0.1		0.0014	JB	0.0007	JB	0.0035	JB	0.0011
Styrene	NA		0.0059	U	0.0056	U	0.0058	U	0.0061
Tetrachloroethene	1.4		0.0012	U	0.0011	U	0.0012	U	0.0012
Toiline	1.5		0.0059	U	0.0056	U	0.0058	U	0.0061
trans-1,2-Dichloroethene	NA		0.0059	U	0.0056	U	0.0058	U	0.0061
trans-1,3-Dichloropropene	NA		0.0059	U	0.0056	U	0.0058	U	0.0061
Trichloroethene	0.7		0.0012	U	0.0011	U	0.0012	U	0.0012
Vinyl Chloride	0.2		0.0059	U	0.0056	U	0.0058	U	0.0061
Xylene (Total)	1.2		0.0059	U	0.0056	U	0.0058	U	0.0061
Total Confident Conc.	NA		0.1		0.082		0.027		0.12
Total Estimated Conc. (TICs)	NA		0.129		0		0		0

TABLE 3
SUMMARY OF SOIL ANALYTICAL RESULTS
PRE-JUST CLOSURE SOIL BORINGS
FORMER COLUMBIACEMENT COMPANY FACILITY
FREERPORT, NEW YORK

UFS SAMPLE ID	LAB SAMPLE ID	NYSDDEC TAG#	BT-19-20	B8-18-19	B9-18-19	BT-19-20
SAMPLE DATE		531006 05/21/04	531009 05/21/04	531010 05/21/04	531011 05/21/04	
SAMPLE DEPTH (ft)	Recommended	19 - 20	18 - 19	18 - 19	18 - 20	
DILUTION FACTOR	Objectives	1	1	1	1	
UNITS	(mg/kg)	(mg/kg)	(mg/kg)	(mg/kg)	(mg/kg)	(mg/kg)
VOCS						
1,1,1-Trichloroethane	0.8	0.0055	U	0.0056	U	0.0057
1,1,2,2-Tetrachloroethane	0.6	0.0011	U	0.0011	U	0.0011
1,1,2-Trichloroethane	NA	0.0033	U	0.0034	U	0.0034
1,1-Dichloroethane	0.2	0.0055	U	0.0056	U	0.0056
1,1-Dichloroethene	0.4	0.0022	U	0.0022	U	0.0023
1,2-Dichloroethane	0.1	0.0022	U	0.0022	U	0.0023
1,2-Dichloropropane	NA	0.0011	U	0.0011	U	0.0011
2-Butanone	0.3	0.0055	U	0.0056	U	0.0057
2-Hexanone	NA	0.0055	U	0.0056	U	0.0056
Acetone	0.2	0.092	0.098	0.08	0.11	
Benzene	0.06	0.0011	U	0.0011	U	0.0011
Bromodichloromethane	NA	0.0011	U	0.0011	U	0.0011
Bromoform	NA	0.0044	U	0.0045	U	0.0046
Bromomethane	NA	0.0055	U	0.0056	U	0.0057
Carbon Disulfide	2.7	0.0044	J	0.0014	J	0.002
Carbon Tetrachloride	0.6	0.0022	U	0.0022	U	0.0023
Chlorobenzene	1.7	0.0055	U	0.0056	U	0.0057
Chloroethane	1.9	0.0055	U	0.0056	U	0.0057
Chloroform	0.3	0.0055	U	0.0056	U	0.0056
Chloromethane	NA	0.0055	U	0.0056	U	0.0057
cis-1,2-Dichloroethene	NA	0.0055	U	0.0056	U	0.0057
cis-1,3-Dichloropropene	NA	0.0055	U	0.0056	U	0.0057
Dibromochloromethane	NA	0.0055	U	0.0056	U	0.0057
Ethylbenzene	5.5	0.0044	U	0.0045	U	0.0046
4-Methyl-2-Pantanone	1	0.0055	U	0.0056	U	0.0057
Methylene Chloride	0.1	0.0006	JB	0.0034	JB	0.0014
Styrene	NA	0.0055	U	0.0056	U	0.0057
Tetrachloroethene	1.4	0.0011	U	0.0011	U	0.0011
Toluene	1.5	0.0055	U	0.0056	U	0.0057
trans-1,2-Dichloroethene	NA	0.0055	U	0.0056	U	0.0057
trans-1,3-Dichloropropene	NA	0.0055	U	0.0056	U	0.0057
Trichloroethene	0.7	0.0011	U	0.0011	U	0.0011
Vinyl Chloride	0.2	0.0055	U	0.0056	U	0.0057
Xylene (Total)	1.2	0.0055	U	0.0056	U	0.0057
Total Confident Conc.	NA	0.092	0.098	0.087	0.1199	
Total Estimated Conc. (TICs)	NA	0	0	0	0	

TABLE 3
SUMMARY OF SOIL ANALYTICAL RESULTS
PRE-UST CLOSURE SOIL BORINGS
FORMER COLUMBIA CEMENT COMPANY FACILITY
FREEPORT, NEW YORK

NOTES:

NA: No Standard
NR: Not analyzed.

U: The compound was not detected at the indicated concentration.

J: Data indicates the presence of a compound that meets the identification criteria. The result is less than the quantitation limit but greater than zero.

The concentration given is an approximate value.

B: The analyte was found in the laboratory blank as well as the sample. This indicates possible laboratory contamination of the sample.

BOLD: Result exceeds NYDEC TAGM Recommended Soil Cleanup Criteria

TABLE 4

**SUMMARY OF SOIL ANALYTICAL RESULTS
POST-UST EXCAVATION SOIL SAMPLING
FORMER COLUMBIA CEMENT COMPANY FACILITY
EPE REPORT NEW YORK**

TABLE 4
SUMMARY OF SOIL ANALYTICAL RESULTS
POST-UST EXCAVATION SOIL SAMPLING
FORMER COLUMBIA CEMENT COMPANY FACILITY
FREEPORT, NEW YORK

URS SAMPLE ID	NYSDOE LAB SAMPLE ID	LAB DATE	SAMPLE DEPTH UNITS	TESTS	TANK 7		TANK 8		TANK 9		TANK 10		
					RECOMMENDED TEST CLEANUP	TESTING TESTING	mg/kg	mg/kg	mg/kg	mg/kg	12 FT BGS	12 FT BGS	
1,1,1-Trichloroethane	ACM 404	9/2/2004	Tank 7	N77-521	N76856-A	N76856-4	0.011 U	0.012 U	0.011 U	0.012 U	0.016	N76856-1	
1,1,2,2-Tetrachloroethane				NE	9/2/2004	9/2/2004	0.6	0.011 U	0.012 U	0.011 U	0.012 U	0.012 U	9/2/2004
1,1,2-Trichloroethane				NE	9/2/2004	9/2/2004	0.011 U	0.012 U	0.011 U	0.012 U	0.012 U	0.012 U	9/2/2004
1,1-Dichloroethane				0.2	0.011 U	0.012 U	0.011 U	0.012 U	0.011 U	0.012 U	0.012 U	0.006	J
1,1-Dichloroethene				0.4	0.011 U	0.012 U	0.011 U	0.012 U	0.011 U	0.012 U	0.012 U	0.012 U	
1,2-Dichloroethane				0.1	0.011 U	0.012 U	0.011 U	0.012 U	0.011 U	0.012 U	0.012 U	0.012 U	
1,2-Dichloroethene				NE	0.011 U	0.012 U	0.011 U	0.012 U	0.011 U	0.012 U	0.012 U	0.012 U	
1,2-Dichloropropane				NE	0.011 U	0.012 U	0.011 U	0.012 U	0.011 U	0.012 U	0.012 U	0.012 U	
2-Butanone				0.3	0.011 U	0.012 U	0.011 U	0.012 U	0.011 U	0.012 U	0.012 U	0.012 U	
2-Hexanone				NE	0.011 U	0.012 U	0.011 U	0.012 U	0.011 U	0.012 U	0.012 U	0.012 U	
Acetone				0.2	0.011 U	0.012 U	0.011 U	0.012 U	0.011 U	0.012 U	0.012 U	0.012 U	
Benzene				0.06	0.011 U	0.012 U	0.011 U	0.012 U	0.011 U	0.012 U	0.012 U	0.012 U	
Bromodichloromethane				NE	0.011 U	0.012 U	0.011 U	0.012 U	0.011 U	0.012 U	0.012 U	0.012 U	
Bromoform				NE	0.011 U	0.012 U	0.011 U	0.012 U	0.011 U	0.012 U	0.012 U	0.012 U	
Carbon Disulfide				2.7	0.011 U	0.012 U	0.011 U	0.012 U	0.011 U	0.012 U	0.012 U	0.012 U	
Carbon Tetrachloride				0.6	0.011 U	0.012 U	0.011 U	0.012 U	0.011 U	0.012 U	0.012 U	0.012 U	
Chlorobenzene				1.7	0.011 U	0.012 U	0.011 U	0.012 U	0.011 U	0.012 U	0.012 U	0.012 U	
Chlorodibromomethane				NE	0.011 U	0.012 U	0.011 U	0.012 U	0.011 U	0.012 U	0.012 U	0.012 U	
Chloroform				0.3	0.011 U	0.012 U	0.011 U	0.012 U	0.011 U	0.012 U	0.012 U	0.012 U	
Cis-1,3-Dichloropropene				NE	0.011 U	0.012 U	0.011 U	0.012 U	0.011 U	0.012 U	0.012 U	0.012 U	
Ethyl Chloride				1.9	0.011 U	0.012 U	0.011 U	0.012 U	0.011 U	0.012 U	0.012 U	0.012 U	
Ethylbenzene				5.5	0.011 U	0.012 U	0.011 U	0.012 U	0.011 U	0.012 U	0.012 U	0.012 U	
Methyl Bromide				NE	0.011 U	0.012 U	0.011 U	0.012 U	0.011 U	0.012 U	0.012 U	0.012 U	
Methyl Chloride				NE	0.011 U	0.012 U	0.011 U	0.012 U	0.011 U	0.012 U	0.012 U	0.012 U	
Methyl Isobutyl Ketone				1	0.011 U	0.012 U	0.011 U	0.012 U	0.011 U	0.012 U	0.012 U	0.012 U	
Methylene Chloride				0.1	0.011 U	0.012 U	0.011 U	0.012 U	0.011 U	0.012 U	0.012 U	0.012 U	
Styrene				NE	0.011 U	0.012 U	0.011 U	0.012 U	0.011 U	0.012 U	0.012 U	0.012 U	
Tetrachloroethene				1.4	0.011 U	0.012 U	0.011 U	0.012 U	0.011 U	0.012 U	0.012 U	0.012 U	
Toluene				1.5	0.011 U	0.012 U	0.001 J	0.001 J	0.006 J	0.012 U	0.002 J	0.002 J	
Trans-1,3-Dichloropropene				NE	0.011 U	0.012 U	0.011 U	0.012 U	0.011 U	0.012 U	0.012 U	0.012 U	
Trichloroethene				0.7	0.011 U	0.012 U	0.011 U	0.012 U	0.011 U	0.012 U	0.001 J	0.001 J	
Vinyl Chloride				0.2	0.011 U	0.012 U	0.012 U	0.012 U	0.011 U	0.012 U	0.012 U	0.012 U	
Xylenes (Total)				1.2	0.011 U	0.012 U	0.011 U	0.012 U	0.011 U	0.012 U	0.012 U	0.012 U	
Total VOC TIC					0	0	0	0	0	0	0	0	

GLE 4

**SUMMARY OF SOIL ANALYTICAL RESULTS
POST-UST EXCAVATION SOIL SAMPLING
FORMER COLUMBIA CEMENT COMPANY FACILITY
FREEPORT, NEW YORK**

WRS SAMPLE ID	NYSDCC LAB SAMPLE ID	STATION	BACKFILL 1 N78486-3	BACKFILL 2 N77152-6	DRAIN 1 N78141-6	DRUM 1 N78141-1	PIPE-1 N7841-2	PIPE-2 N7841-3	PIPE-3 N7841-4
SAMPLE DATE	TEST DATE		1/2/2004	1/2/2004	9/15/2004	9/15/2004	9/15/2004	9/15/2004	9/15/2004
SAMPLE DEPTH	SOIL CUBE DEPTH	OBJECTIVE DEPTH	N/A	N/A	3 FT BGS	3 FT BGS	3 FT BGS	3 FT BGS	NA
UNITS	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
VOLATILE ORGANIC COMPOUNDS									
1,1,1-Trichloroethane	0.8		0.011 U	0.011 U	0.008 J	0.011 U	0.011 U	0.011 U	0.49 U
1,1,2,2-Tetrachloroethane	0.6		0.011 U	0.011 U	0.01 U	0.011 U	0.011 U	0.01 U	0.49 U
1,1,2-Trichloroethane	NE		0.011 U	0.011 U	0.01 U	0.011 U	0.011 U	0.01 U	0.49 U
1,1-Dichloroethane	0.2		0.011 U	0.011 U	0.002 J	0.002 J	0.002 J	0.002 J	0.49 U
1,1-Dichloroethylene	0.4		0.011 U	0.011 U	0.01 U	0.011 U	0.011 U	0.01 U	0.49 U
1,2-Dichloroethane	0.1		0.011 U	0.011 U	0.01 U	0.011 U	0.011 U	0.01 U	0.49 U
1,2-Dichloroethene	NE		0.011 U	0.011 U	0.01 U	0.011 U	0.011 U	0.01 U	0.49 U
1,2-Dichloropropane	NE		0.011 U	0.011 U	0.01 U	0.011 U	0.011 U	0.01 U	0.49 U
2-Butanone	0.3		0.011 U	0.011 U	0.01 U	0.011 U	0.011 U	0.01 U	0.49 U
2-Hexanone	NE		0.011 U	0.011 U	0.01 U	0.011 U	0.011 U	0.01 U	0.49 U
Acetone	0.2		0.011 U	0.011 U	0.01 U	0.011 U	0.011 U	0.01 U	0.49 U
Benzene	0.06		0.011 U	0.011 U	0.01 U	0.011 U	0.011 U	0.01 U	0.49 U
Bromodichloromethane	NE		0.011 U	0.011 U	0.01 U	0.011 U	0.011 U	0.01 U	0.49 U
Bromoform	NE		0.011 U	0.011 U	0.01 U	0.011 U	0.011 U	0.01 U	0.49 U
Carbon Disulfide	2.7		0.011 U	0.011 U	0.01 U	0.011 U	0.011 U	0.01 U	0.49 U
Carbon Tetrachloride	0.6		0.011 U	0.011 U	0.01 U	0.011 U	0.011 U	0.01 U	0.49 U
Chlorobenzene	1.7		0.011 U	0.011 U	0.01 U	0.011 U	0.011 U	0.01 U	0.49 U
Chlorodibromomethane	NE		0.011 U	0.011 U	0.01 U	0.011 U	0.011 U	0.01 U	0.49 U
Chloroform	0.3		0.011 U	0.011 U	0.01 U	0.011 U	0.011 U	0.01 U	0.49 U
Cis-1,3-Dichloropropene	NE		0.011 U	0.011 U	0.01 U	0.011 U	0.011 U	0.01 U	0.49 U
Ethyl Chloride	1.9		0.011 U	0.011 U	0.01 U	0.011 U	0.011 U	0.01 U	0.49 U
Ethylbenzene	5.5		0.011 U	0.011 U	0.01 U	0.011 U	0.011 U	0.01 U	0.49 U
Methyl Bromide	NE		0.011 U	0.011 U	0.01 U	0.011 U	0.011 U	0.01 U	0.49 U
Methyl Chloride	NE		0.011 U	0.011 U	0.01 U	0.011 U	0.011 U	0.01 U	0.49 U
Methyl Isobutyl Ketone	1		0.011 U	0.011 U	0.01 U	0.011 U	0.011 U	0.01 U	0.49 U
Methylene Chloride	0.1		0.011 U	0.011 U	0.01 U	0.011 U	0.011 U	0.01 U	0.49 U
Styrene	NE		0.011 U	0.011 U	0.01 U	0.011 U	0.011 U	0.01 U	0.49 U
Tetrachloroethylene	1.4		0.011 U	0.011 U	0.01 U	0.016 U	0.016 U	0.01 U	0.49 U
Toluene	1.5		0.002 J	0.011 U	0.01 U	0.011 U	0.001 J	0.001 J	0.49 U
Trans-1,3-Dichloropropene	NE		0.011 U	0.011 U	0.01 U	0.011 U	0.011 U	0.01 U	0.49 U
Trichloroethylene	0.7		0.011 U	0.011 U	0.01 U	0.011 U	0.011 U	0.01 U	0.49 U
Vinyl Chloride	0.2		0.011 U	0.011 U	0.01 U	0.011 U	0.011 U	0.01 U	0.49 U
Xylenes (Total)	1.2		0.011 U	0.011 U	0.01 U	0.011 U	0.011 U	0.01 U	0.49 U
Total VOC TIC	0		0	0	0.007 J	0	0	0	0.5281 J

TABLE 4
SUMMARY OF SOIL ANALYTICAL RESULTS
POST-UST EXCAVATION SOIL SAMPLING
FORMER COLUMBIA CEMENT COMPANY FACILITY
FREEPORT, NEW YORK

URS SAMPLE ID LAB SAMPLE ID SAMPLE DATE SAMPLE DEPTH UNITS	NYSDEC TAGM RECOMMENDED SOIL CLEANUP OBJECTIVE	DRAIN-1 N78141-6 9/15/2004 3 FT BGS. mg/kg
SEMI-VOLATILE ORGANIC COMPOUNDS		
1,2,4-Trichlorobenzene	3.4	0.019 U
1,2-Dichlorobenzene	7.9	0.021 U
1,3-Dichlorobenzene	1.6	0.02 U
1,4-Dichlorobenzene	8.5	0.019 U
2,4,5-Trichlorophenol	0.1	0.021 U
2,4,6-Trichlorophenol	NA	0.02 U
2,4-Dichlorophenol	0.4	0.023 U
2,4-Dimethylphenol	NA	0.028 U
2,4-Dinitrophenol	0.2	0.04 U
2,4-Dinitrotoluene	NA	0.021 U
2,6-Dinitrotoluene	1	0.018 U
2-Chloronaphthalene	NA	0.02 U
2-Chlorophenol	0.8	0.021 U
2-Methylnaphthalene	36.4	0.02 U
2-Nitroaniline	0.43	0.024 U
2-Nitrophenol	0.33	0.026 U
3&4-Methylphenol	NA	0.039 U
3,3'-Dichlorobenzidine	NA	0.026 U
3-Nitroaniline	0.5	0.024 U
4,6-Dinitro-2-Methylphenol	NA	0.021 U
4-Bromophenyl Phenyl Ether	NA	0.02 U
4-Chloro-3-Methylphenol	0.24	0.029 U
4-Chloroaniline	0.22	0.024 U
4-Chlorophenyl Phenyl Ether	NA	0.019 U
4-Nitroaniline	NA	0.022 U
4-Nitrophenol	0.1	0.076 U
Acenaphthene	50	0.022 U
Acenaphthylene	41	0.016 U
Anthracene	50	0.02 U
Benzo(A)Anthracene	0.224	0.021 U
Benzo(A)Pyrene	0.061	0.018 U
Benzo(B)Fluoranthene	1.1	0.018 U
Benzo(G,H,I)Perylene	50	0.03 U
Benzo(K)Fluoranthene	1.1	0.03 U
Bis(2-Chloro-1-Methylethyl) Ether	NA	0.025 U
Bis(2-Chloroethoxy)Methane	NA	0.02 U
Bis(2-Chloroethyl)Ether	NA	0.024 U
Bis(2-Ethylhexyl)Phthalate	50	0.045 U
Butyl Benzyl Phthalate	50	0.028 U
Carbazole	NA	0.022 U
Chrysene	0.4	0.021 U
Dibenzo(A,H)Anthracene	0.014	0.028 U
Dibenzofuran	6.2	0.019 U
Diethyl Phthalate	7.1	0.024 U
Dimethyl Phthalate	2	0.018 U
Di-N-Butyl Phthalate	8.1	0.019 U
Fluoranthene	50	0.018 U
Fluorene	50	0.02 U
Hexachlorobenzene	0.41	0.02 U
Hexachlorobutadiene	NA	0.025 U
Hexachlorocyclopentadiene	NA	0.02 U
Hexachloroethane	NA	0.021 U
Indeno(1,2,3-cd)Pyrene	3.2	0.043 U
Isophorone	4.4	0.022 U
Naphthalene	13	0.019 U
N-Dioctyl Phthalate	50	0.024 U
Nitrobenzene	0.2	0.02 U
N-Nitrosodi-N-Propylamine	NA	0.022 U
N-Nitrosodiphenylamine	NA	0.02 U
c-Cresol	0.1	0.028 U
Pentachlorophenol	1	0.022 U
Phenanthrene	50	0.021 U
Phenol	0.03	0.029 U
Pyrene	50	0.04 U

TABLE 5
SUMMARY OF SOIL ANALYTICAL RESULTS
POST-JUST EXCAVATION SOIL SAMPLING
FORMER COLUMBIA CEMENT COMPANY FACILITY
FREEPORT, NEW YORK

NOTES:

mg/kg : Milligrams Per Kilogram (ppm)

U : Compound was not detected.

J : The result is a quantitatively estimated value.

D : Result is obtained from a diluted sample.

NE : Not Established

Boxed : Exceeds NYSDEC TAGM Recommended Soil Cleanup Objective

SUMMARY OF SOIL ANALYTICAL RESULTS
POST-CLOSURE SOIL BORINGS
FORMER COLUMBIA CEMENT FACILITY
FREERPORT, NEW YORK

TABLE 5

BORING ID	NYSDEC TAGM 4046	T-01 -01-16-18	T-01 -01-20-22	T-02 -02-16-18	T-02 -02-20-22	T-02 -02-24-26	T-02 -02-28-30	T-03 -03-16-18	T-03 -03-20-22
URS SAMPLE ID	Recommended Soil Cleanup Objective (mg/kg)	NE0188-6 10/6/2004 16 - 18 (mg/kg)	NE0188-7 10/6/2004 20 - 22 (mg/kg)	NE0188-0 10/6/2004 16 - 18 (mg/kg)	NE0188-11 10/6/2004 20 - 22 (mg/kg)	NE0188-2 10/6/2004 24 - 26 (mg/kg)	NE0188-13 10/6/2004 28 - 30 (mg/kg)	NE0188-14 10/6/2004 16 - 18 (mg/kg)	NE0188-15 10/6/2004 20 - 22 (mg/kg)
VOC									
1,1,1-Trichloroethane	0.8	0.003 J	0.01 J	0.011 J	0.042	0.011 U	0.001 J	2.2	4800 D
1,1,2,2-Tetrachloroethane	0.6	0.021 U	0.011 U	0.019 U	0.013 U	0.011 U	0.014 U	0.16 U	4.9 U
1,1,2-Trichloroethane	NE	0.021 U	0.011 U	0.019 U	0.013 U	0.011 U	0.014 U	0.16 U	4.9 U
1,1-Dichloroethane	0.2	0.004 J	0.001 J	0.008 J	0.039	0.011 U	0.014 U	2.3	390 D
1,1-Dichloroethylene	0.4	0.021 U	0.011 U	0.019 U	0.013 U	0.011 U	0.014 U	0.16 U	18
1,2-Dichloroethane	0.1	0.021 U	0.011 U	0.019 U	0.013 U	0.011 U	0.014 U	0.16 U	1.2 J
1,2-Dichloroethene	NE	0.021 U	0.011 U	0.019 U	0.013 U	0.011 U	0.014 U	0.16 U	4.9 U
1,2-Dichloropropane	NE	0.021 U	0.011 U	0.019 U	0.013 U	0.011 U	0.014 U	0.16 U	4.9 U
2-Butanone	0.3	0.074	0.011 U	0.180	0.056 U	0.011 U	0.014 U	0.16 U	4.9 U
2-Hexanone	NE	0.021 U	0.011 U	0.019 U	0.013 U	0.011 U	0.014 U	0.16 U	4.9 U
Acetone	0.2	0.27	0.011 U	0.32 D	0.043	0.011 U	0.014 U	0.16 U	4.9 U
Benzene	0.06	0.034	0.011 U	0.008 J	0.013 U	0.011 U	0.014 U	0.016 J	4.9 U
Bromodichloromethane	NE	0.021 U	0.011 U	0.019 U	0.013 U	0.011 U	0.014 U	0.16 U	4.9 U
Bromoform	NE	0.021 U	0.011 U	0.019 U	0.013 U	0.011 U	0.014 U	0.16 U	4.9 U
Carbon Disulfide	2.7	0.019 J	0.011 U	0.045	0.008 D	0.011 U	0.014 U	0.270	4.9 U
Carbon Tetrachloride	0.6	0.021 U	0.011 U	0.019 U	0.013 U	0.011 U	0.014 U	0.016 J	4.9 U
Chlorobenzene	1.7	0.041	0.011 U	0.038	0.004 J	0.011 U	0.014 U	0.16 U	4.9 U
Chlorodibromomethane	NE	0.021 U	0.011 U	0.019 U	0.013 U	0.011 U	0.014 U	0.16 U	4.9 U
Chloroform	0.3	0.021 U	0.011 U	0.019 U	0.013 U	0.011 U	0.014 U	0.16 U	4.9 U
Cis-1,3-Dichloropropene	NE	0.021 U	0.011 U	0.019 U	0.013 U	0.011 U	0.014 U	0.16 U	4.9 U
Chloroethane	1.9	0.42	0.004 J	0.43 D	1.1 D	0.011 U	0.014 U	16 D	15
Ethylbenzene	5.5	0.021 U	0.011 U	0.019 U	0.013 U	0.011 U	0.014 U	0.16 U	4.9 U
Methyl Bromide	NE	0.021 U	0.011 U	0.019 U	0.013 U	0.011 U	0.014 U	0.16 U	4.9 U
Methyl Chloride	NE	0.021 U	0.011 U	0.019 U	0.013 U	0.011 U	0.014 U	0.16 U	4.9 U
Methyl Isobutyl Ketone	1	0.021 U	0.011 U	0.019 U	0.013 U	0.011 U	0.014 U	0.16 U	1.1 J
Methylene Chloride	0.1	0.021 U	0.011 U	0.019 U	0.013 U	0.011 U	0.014 U	0.16 U	4.9 U
Styrene	NE	0.021 U	0.011 U	0.019 U	0.013 U	0.011 U	0.014 U	0.025 J	240 U
Tetrachloroethene	1.4	0.021 U	0.011 U	0.019 U	0.013 U	0.011 U	0.014 U	0.16 U	4.9 U
Toluene	1.5	0.003 J	0.011 U	0.008 J	0.001 J	0.011 U	0.014 U	0.16 U	4.9 U
Trans-1,3-Dichloropropene	NE	0.021 U	0.011 U	0.019 U	0.013 U	0.011 U	0.014 U	0.079 J	4.2 J
Trichloroethene	0.7	0.021 U	0.011 U	0.019 U	0.013 U	0.011 U	0.014 U	0.16 U	4.9 U
Vinyl Chloride	0.2	0.021 U	0.011 U	0.019 U	0.013 U	0.011 U	0.014 U	0.039 J	4.9 U
Xylenes (Total)	1.2	0.01 J	0.011 U	0.009 J	0.002 J	0.011 U	0.014 U	0.16 U	4.9 U
Total VOC TIC	NE	1.19 J	0.007 J	3.738 J	1.585 J	0	0	3.199 J	32.8 J

TABLE 5
SUMMARY OF SOIL ANALYTICAL RESULTS
POST-CLOSURE SOIL BORINGS
FORMER COLUMBIA CEMENT FACILITY
FREEPORT, NEW YORK

BORING ID	NYSDEC URS SAMPLE ID	NYSDEC LAB SAMPLE ID	TAGM 446 Recommended Soil Cleanup Objective (mg/kg)	T-03 13-21-26 N80188-16	T-03 28-30 N80188-17	T-04 16-18 N80188-18	T-04 20-22 N80188-19	T-05 16-18 N80188-22	T-05 20-22 N80188-23	T-06 16-18 N80188-26	T-06 20-22 N80188-27
SAMPLE DATE	SAMPLE DEPTH (ft)	UNITS	VOC	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
				(mg/kg)	(mg/kg)	(mg/kg)	(mg/kg)	(mg/kg)	(mg/kg)	(mg/kg)	(mg/kg)
1,1,1-Trichloroethane	0.8		0.010 J	0.019 J	0.022 J	0.011 U	0.011 U	0.011 U	0.012 U	0.012 U	0.023
1,1,2,2-Tetrachloroethane	0.6		0.012 U	0.012 U	0.026 U	0.011 U	0.011 U	0.011 U	0.012 U	0.012 U	0.011 U
1,1,2-Trichloroethane	NE		0.012 U	0.012 U	0.026 U	0.011 U	0.003 J	0.005 J	0.011 U	0.012 U	0.011 U
1,1-Dichloroethane	0.2		0.003 J	0.003 J	0.026 U	0.012 U	0.012 U	0.011 U	0.011 U	0.012 U	0.08
1,1-Dichloroethene	0.4		0.012 U	0.012 U	0.026 U	0.012 U	0.012 U	0.011 U	0.011 U	0.012 U	0.011 U
1,2-Dichloroethane	0.1		0.012 U	0.012 U	0.026 U	0.011 U	0.011 U	0.011 U	0.011 U	0.012 U	0.011 U
1,2-Dichloroethene	NE		0.012 U	0.012 U	0.026 U	0.011 U	0.012 U	0.011 U	0.011 U	0.012 U	0.011 U
1,2-Dichloropropane	NE		0.012 U	0.012 U	0.026 U	0.011 U	0.012 U	0.011 U	0.011 U	0.012 U	0.011 U
2-Butanone	0.3		0.012 U	0.012 U	0.043	0.011 U	0.012 U	0.011 U	0.011 U	0.012 U	0.011 U
2-Hexanone	NE		0.012 U	0.012 U	0.026 U	0.011 U	0.011 U	0.011 U	0.011 U	0.012 U	0.011 U
Acetone	0.2		0.012 U	0.012 U	0.023	0.011 U	0.011 U	0.011 U	0.011 U	0.012 U	0.011 U
Benzene	0.06		0.012 U	0.012 U	0.002 J	0.011 U	0.002 J	0.011 U	0.011 U	0.012 U	0.011 U
Bromodichloromethane	NE		0.012 U	0.012 U	0.026 U	0.011 U	0.012 U	0.011 U	0.011 U	0.012 U	0.011 U
Bromoform	NE		0.012 U	0.012 U	0.026 U	0.011 U	0.011 U	0.011 U	0.011 U	0.012 U	0.011 U
Carbon Disulfide	2.7		0.012 U	0.002 J	0.008 J	0.011 U	0.011 U	0.001 J	0.011 U	0.012 U	0.011 U
Carbon Tetrachloride	0.6		0.012 U	0.012 U	0.026 U	0.011 U	0.011 U	0.011 U	0.011 U	0.012 U	0.011 U
Chlorobenzene	1.7		0.012 U	0.012 U	0.003 J	0.011 U	0.011 U	0.011 U	0.011 U	0.012 U	0.011 U
Chlorodibromomethane	NE		0.012 U	0.012 U	0.026 U	0.011 U	0.011 U	0.011 U	0.011 U	0.012 U	0.011 U
Chloroform	0.3		0.012 U	0.012 U	0.026 U	0.011 U	0.011 U	0.011 U	0.011 U	0.012 U	0.011 U
Cis-1,3-Dichloropropene	NE		0.012 U	0.012 U	0.026 U	0.011 U	0.011 U	0.011 U	0.011 U	0.012 U	0.002 J
Chloroethane	1.9		0.012 U	0.012 U	0.015 J	0.011 U	0.011 U	0.011 U	0.011 U	0.012 U	0.011 U
Ethylbenzene	5.5		0.012 U	0.012 U	0.026 U	0.011 U	0.011 U	0.011 U	0.011 U	0.012 U	0.011 U
Methyl Bromide	NE		0.012 U	0.012 U	0.026 U	0.011 U	0.011 U	0.011 U	0.011 U	0.012 U	0.011 U
Methyl Chloride	NE		0.012 U	0.012 U	0.026 U	0.011 U	0.011 U	0.011 U	0.011 U	0.012 U	0.011 U
Methyl Isobutyl Ketone	1		0.012 U	0.012 U	0.026 U	0.011 U	0.011 U	0.011 U	0.011 U	0.012 U	0.011 U
Methylene Chloride	0.1		0.012 U	0.012 U	0.026 U	0.011 U	0.011 U	0.011 U	0.011 U	0.012 U	0.031
Styrene	NE		0.012 U	0.012 U	0.026 U	0.011 U	0.011 U	0.011 U	0.011 U	0.012 U	0.011 U
Tetrachloroethene	1.4		0.012 U	0.012 U	0.026 U	0.011 U	0.011 U	0.011 U	0.011 U	0.012 U	0.011 U
Toluene	1.5		0.012 U	0.012 U	0.003 J	0.011 U	0.012 U	0.011 U	0.011 U	0.012 U	0.011 U
Trans-1,3-Dichloropropene	NE		0.012 U	0.012 U	0.026 U	0.011 U	0.012 U	0.011 U	0.011 U	0.012 U	0.011 U
Trichloroethene	0.7		0.012 U	0.012 U	0.026 U	0.011 U	0.011 U	0.011 U	0.011 U	0.012 U	0.011 U
Vinyl Chloride	0.2		0.012 U	0.012 U	0.026 U	0.011 U	0.012 U	0.011 U	0.011 U	0.012 U	0.011 U
Xylenes (Total)	1.2		0.012 U	0.012 U	0.006 J	0.011 U	0.012 U	0.011 U	0.011 U	0.012 U	0.011 U
Total VOC TIC	NE		0	0	3.783 J	0	0	0	0.007 J	0.006 J	0

TABLE 5
SUMMARY OF SOIL ANALYTICAL RESULTS
POST-CLOSURE SOIL BORINGS
FORMER COLUMBIA CEMENT FACILITY
FREERPORT, NEW YORK

BORING ID	NYSDEC TAGM 4046	T-07 1-07/16-18	T-07 1-07/20-22	T-07 1-07/24-26	T-07 1-07/28-30	T-08 1-08/18-32	T-08 1-08/18-34	T-08 1-08/18-42	T-08 1-08/18-45	T-08 1-08/18-18	T-08 1-08/20-22	T-08 1-08/18-35	T-09 1-09/18-38
URS SAMPLE ID	LAB SAMPLE ID	Recommended Soil Cleanup Objective (mg/kg)	Sample Date	Sample Depth (ft)	Sample Depth (m)								
UNITS	UNITS	UNITS	UNITS	UNITS	UNITS	UNITS	UNITS	UNITS	UNITS	UNITS	UNITS	UNITS	UNITS
VOC													
1,1,1-Trichloroethane	0.8		0.011 U		0.002 J		0.011 U		0.012 U		94 D		0.01 U
1,1,2,2-Tetrachloroethane	0.6		0.011 U		0.013 U		0.011 U		0.012 U		0.054 U		0.016 U
1,1,2-Trichloroethane	NE		0.011 U		0.013 U		0.011 U		0.012 U		0.054 U		0.018 U
1,1-Dichloroethane	0.2		0.005 J		0.49 D		0.011 U		0.012 U		0.012 U		0.018 U
1,1-Dichloroethene	0.4		0.011 U		0.006 J		0.011 U		0.012 U		0.012 U		0.004 J
1,2-Dichloroethane	0.1		0.011 U		0.013 U		0.011 U		0.012 U		0.012 U		0.018 U
1,2-Dichloroethene	NE		0.011 U		0.013 U		0.011 U		0.012 U		0.012 U		0.018 U
1,2-Dichlortopropane	NE		0.011 U		0.013 U		0.011 U		0.012 U		0.054 U		0.018 U
2-Butanone	0.3		0.011 U		0.013 U		0.011 U		0.012 U		0.054 U		0.018 U
2-Hexanone	NE		0.011 U		0.013 U		0.011 U		0.012 U		0.054 U		0.018 U
Acetone	0.2		0.011 U		0.013 U		0.011 U		0.012 U		0.012 U		0.018 U
Benzene	0.06		0.011 U		0.013 U		0.011 U		0.012 U		0.054 U		0.018 U
Bromodichloromethane	NE		0.011 U		0.013 U		0.011 U		0.012 U		0.006 J		0.008 J
Bromoform	NE		0.011 U		0.013 U		0.011 U		0.012 U		0.054 U		0.018 U
Carbon Disulfide	2.7		0.002 J		0.001 J		0.011 U		0.012 U		0.054 U		0.01 U
Carbon Tetrachloride	0.6		0.011 U		0.013 U		0.011 U		0.012 U		0.018 U		0.007 J
Chlorobenzene	1.7		0.011 U		0.013 U		0.011 U		0.012 U		0.054 U		0.018 U
Chlorodibromomethane	NE		0.011 U		0.013 U		0.011 U		0.012 U		0.054 U		0.018 U
Chloroform	0.3		0.011 U		0.013 U		0.011 U		0.012 U		0.054 U		0.018 U
Cis-1,3-Dichloropropene	NE		0.011 U		0.013 U		0.011 U		0.012 U		0.054 U		0.018 U
Chloroethane	1.9		0.011 U		0.41 D		0.011 U		0.012 U		0.012 U		0.018 U
Ethylibenzene	5.5		0.011 U		0.013 U		0.011 U		0.012 U		0.054 U		0.018 U
Methyl Bromide	NE		0.011 U		0.013 U		0.011 U		0.012 U		0.054 U		0.018 U
Methyl Chloride	NE		0.011 U		0.013 U		0.011 U		0.012 U		0.054 U		0.018 U
Methyl Isobutyl Ketone	1		0.011 U		0.013 U		0.011 U		0.012 U		0.054 U		0.018 U
Methylene Chloride	0.1		0.011 U		0.013 U		0.011 U		0.012 U		0.054 U		0.018 U
Styrene	NE		0.011 U		0.013 U		0.011 U		0.012 U		0.012 U		0.018 U
Tetrachloroethene	1.4		0.011 U		0.013 U		0.011 U		0.012 U		0.054 U		0.018 U
Toluene	1.5		0.011 U		0.013 U		0.011 U		0.012 U		0.35 J		0.018 U
Trans-1,3-Dichloropropene	NE		0.011 U		0.013 U		0.011 U		0.012 U		0.38		0.018 U
Trichloroethene	0.7		0.011 U		0.013 U		0.011 U		0.012 U		0.054 U		0.018 U
Vinyl Chloride	0.2		0.011 U		0.001 J		0.011 U		0.012 U		0.054 U		0.018 U
Xylenes (Total)	1.2		0.011 U		0.013 U		0.011 U		0.012 U		0.054 U		0.018 U
Total VOC TIC	NE		0.006 J		0.007 J		0		2.841 J		0.451 J		0.009 J

.8LE 5
SUMMARY OF SOIL ANALYTICAL RESULTS
POST-CLOSURE SOIL BORINGS
FORMER COLUMBIA CEMENT FACILITY
FREEPORT, NEW YORK

BORING ID	NYSDEC URS SAMPLE ID	TAGM 4046 LAB SAMPLE ID	Recommended Soil Cleanups	T-09 06/20/22 N80188-15 10/07/2004	T-10 06/20/22 N80188-43 10/07/2004	T-10 06/20/22 N80188-44 10/07/2004	D-01 D-01-10-12 N80188-47 10/07/2004	D-01 D-01-16-18 N80188-48 10/07/2004	D-01 D-01-20-22 N80188-49 10/07/2004	D-02 D-02-10-12 N80188-52 10/07/2004	D-02 D-02-16-18 N80188-53 10/07/2004
SAMPLE DATE	SAMPLE DEPTH (ft)	Objectives	UNITS	(m)	(m)	(m)	(m/kg)	(m/kg)	(m/kg)	(m/kg)	(m/kg)
TOX	mg/m ³	mg/m ³	mg/m ³	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg
1,1,1-Trichloroethane	0.8		0.011 U	0.003 J	0.011 U	0.017	690 D	0.013 U	0.01 J	0.013	0.021 U
1,1,2,2-Tetrachloroethane	0.6		0.011 U	0.019 J	0.011 U	0.012 U	0.310 U	0.013 U	0.028 U	0.028 U	0.021 U
1,1,2-Trichloroethane	NE		0.011 U	0.019 U	0.011 U	0.012 U	0.310 U	0.013 U	0.028 U	0.028 U	0.021 U
1,1-Dichloroethene	0.2		0.011 U	0.061	0.011 U	0.17	11.0 DJ	0.013 U	0.008 J	0.013 U	0.021 U
1,1-Dichloroethene	0.4		0.011 U	0.019 U	0.011 U	0.012 U	0.92	0.013 U	0.028 U	0.028 U	0.021 U
1,2-Dichloroethane	0.1		0.011 U	0.019 U	0.011 U	0.012 U	0.310 U	0.013 U	0.028 U	0.028 U	0.021 U
1,2-Dichloroethene	NE		0.011 U	0.019 U	0.011 U	0.012 U	0.310 U	0.013 U	0.028 U	0.028 U	0.021 U
1,2-Dichloropropane	NE		0.011 U	0.019 U	0.011 U	0.012 U	0.310 U	0.013 U	0.028 U	0.028 U	0.021 U
2-Butanone	0.3		0.011 U	0.019 U	0.011 U	0.018	0.37	0.015	0.03	0.015	0.021 U
2-Hexanone	NE		0.011 U	0.019 U	0.011 U	0.012 U	0.310 U	0.013 U	0.028 U	0.028 U	0.021 U
Acetone	0.2		0.011 U	0.018 J	0.005 J	0.022	0.42	0.011 J	0.086	0.011 J	0.015 J
Benzene	0.06		0.011 U	0.019 U	0.011 U	0.012 U	0.096	0.013 U	0.028 U	0.028 U	0.021 U
Bromodichloromethane	NE		0.011 U	0.019 U	0.011 U	0.012 U	0.310 U	0.013 U	0.028 U	0.028 U	0.021 U
Bromoform	NE		0.011 U	0.019 U	0.011 U	0.012 U	0.310 U	0.013 U	0.028 U	0.028 U	0.021 U
Carbon Disulfide	2.7		0.011 U	0.016 J	0.011 U	0.002 J	0.130 J	0.007 J	0.026 J	0.007 J	0.021 U
Carbon Tetrachloride	0.6		0.011 U	0.019 U	0.011 U	0.012 U	0.310 U	0.013 U	0.028 U	0.028 U	0.021 U
Chlorobenzene	1.7		0.011 U	0.019 U	0.011 U	0.012 U	0.0864	0.013 U	0.007 J	0.007 J	0.021 U
Chlorodibromomethane	NE		0.011 U	0.019 U	0.011 U	0.012 U	0.310 U	0.013 U	0.028 U	0.028 U	0.021 U
Chloroform	0.3		0.011 U	0.019 U	0.011 U	0.012 U	0.310 U	0.013 U	0.028 U	0.028 U	0.021 U
Cis-1,3-Dichloropropene	NE		0.011 U	0.019 U	0.011 U	0.012 U	0.310 U	0.013 U	0.028 U	0.028 U	0.021 U
Chloroethane	1.9		0.011 U	0.006 J	0.011 U	0.006 J	8.4 DJ	0.013 U	0.028 U	0.028 U	0.021 U
Ethylbenzene	5.5		0.011 U	0.019 U	0.011 U	0.007 J	0.31	0.013 U	0.028 U	0.028 U	0.021 U
Methyl Bromide	NE		0.011 U	0.019 U	0.011 U	0.012 U	0.310 U	0.013 U	0.028 U	0.028 U	0.021 U
Methyl Chloride	NE		0.011 U	0.019 U	0.011 U	0.012 U	0.75 J	0.013 U	0.028 U	0.028 U	0.021 U
Methyl Isobutyl Ketone	1		0.011 U	0.019 U	0.011 U	0.012 U	0.310 U	0.013 U	0.028 U	0.028 U	0.021 U
Methylene Chloride	0.1		0.011 U	0.019 U	0.011 U	0.012 U	0.075 J	0.013 U	0.028 U	0.028 U	0.021 U
Styrene	NE		0.011 U	0.019 U	0.011 U	0.012 U	0.310 U	0.013 U	0.028 U	0.028 U	0.021 U
Tetrachloroethene	1.4		0.011 U	0.019 U	0.011 U	0.003 J	0.310 U	0.013 U	0.028 U	0.028 U	0.021 U
Toluene	1.5		0.011 U	0.019 U	0.011 U	0.035	1.1	0.013 U	0.016 J	0.016 J	0.021 U
Trans-1,3-Dichloropropene	NE		0.011 U	0.019 U	0.011 U	0.012 U	0.310 U	0.013 U	0.028 U	0.028 U	0.021 U
Trichloroethene	0.7		0.011 U	0.019 U	0.011 U	0.002 J	0.120	0.013 U	0.028 U	0.028 U	0.021 U
Vinyl Chloride	0.2		0.011 U	0.019 U	0.011 U	0.012 U	0.310 U	0.013 U	0.028 U	0.028 U	0.021 U
Xylenes (Total)	1.2		0.011 U	0.019 U	0.011 U	0.03	0.90	0.013 U	0.028 U	0.028 U	0.021 U
Total VOC TIC	NE		0	0	0	1.91 J	69.08 J	0	0.731 J	0	0

TABLE 5
SUMMARY OF SOIL ANALYTICAL RESULTS
POST-CLOSURE SOIL BORINGS
FORMER COLUMBIA CEMENT FACILITY
FREEPORT, NEW YORK

BORING ID	NYSDEC TAGM#46	D-12 D-12-20-22	D-03 D-03-10-12	D-03 N80188-58	D-03 N80188-59	D-03 N80188-60	D-04 N80188-63	D-04 N80188-64	D-04 N80188-65	D-04 N80188-66
URS SAMPLE ID	Recommended Soil Cleanup Objective (mg/kg)	10/7/2004 20 - 22 (mg/kg)	10/7/2004 10 - 12 (mg/kg)	10/8/2004 10 - 12 (mg/kg)	10/8/2004 16 - 18 (mg/kg)	10/8/2004 20 - 22 (mg/kg)	10/8/2004 10 - 12 (mg/kg)	10/8/2004 16 - 18 (mg/kg)	10/8/2004 20 - 22 (mg/kg)	10/8/2004 16 - 18 (mg/kg)
VOC										
1,1,1-Trichloroethane	0.8	0.013 U	0.002 J	0.021 U	0.011 U	0.011 U	0.078 U	0.016	0.011 U	0.011 U
1,1,2,2-Tetrachloroethane	0.6	0.013 U	0.019 U	0.021 U	0.011 U	0.011 U	0.078 U	0.012 U	0.011 U	0.011 U
1,1,2-Trichloroethane	NE	0.013 U	0.019 U	0.021 U	0.011 U	0.011 U	0.078 U	0.012 U	0.011 U	0.011 U
1,1-Dichloroethane	0.2	0.013 U	0.23	0.021 U	0.011 U	0.011 U	0.078 U	0.14	0.011 U	0.011 U
1,1-Dichloroethene	0.4	0.013 U	0.019 U	0.021 U	0.011 U	0.011 U	0.078 U	0.012 U	0.011 U	0.011 U
1,2-Dichloroethane	0.1	0.013 U	0.019 U	0.021 U	0.011 U	0.011 U	0.078 U	0.012 U	0.011 U	0.011 U
1,2-Dichloroethene	NE	0.013 U	0.019 U	0.021 U	0.011 U	0.011 U	0.078 U	0.012 U	0.011 U	0.011 U
1,2-Dichloropropane	NE	0.013 U	0.019 U	0.021 U	0.011 U	0.011 U	0.078 U	0.012 U	0.011 U	0.011 U
2-Butanone	0.3	0.013 U	0.019 U	0.032	0.011 U	0.011 U	0.078 U	0.02	0.011 U	0.011 U
2-Hexanone	NE	0.013 U	0.019 U	0.021 U	0.011 U	0.011 U	0.078 U	0.02	0.011 U	0.011 U
Acetone	0.2	0.013 U	0.014 J	0.14	0.011 U	0.011 U	0.078 U	0.012 U	0.011 U	0.011 U
Benzene	0.06	0.013 U	0.019 U	0.021 U	0.011 U	0.011 U	0.078 U	0.012 U	0.011 U	0.011 U
Bromodichloromethane	NE	0.013 U	0.019 U	0.021 U	0.011 U	0.011 U	0.078 U	0.012 U	0.011 U	0.011 U
Bromoform	NE	0.013 U	0.019 U	0.021 U	0.011 U	0.011 U	0.078 U	0.012 U	0.011 U	0.011 U
Carbon Disulfide	2.7	0.013 U	0.007 J	0.003 J	0.011 U	0.011 U	0.078 U	0.012 U	0.011 U	0.011 U
Carbon Tetrachloride	0.6	0.013 U	0.019 U	0.021 U	0.011 U	0.011 U	0.078 U	0.021 J	0.006 J	0.011 U
Chlorobenzene	1.7	0.013 U	0.019 U	0.021 U	0.011 U	0.011 U	0.078 U	0.012 U	0.011 U	0.011 U
Chlorodibromomethane	NE	0.013 U	0.019 U	0.021 U	0.011 U	0.011 U	0.078 U	0.009 J	0.012 U	0.011 U
Chloroform	0.3	0.013 U	0.019 U	0.021 U	0.011 U	0.011 U	0.078 U	0.012 U	0.011 U	0.011 U
Cis-1,3-Dichloropropene	NE	0.013 U	0.019 U	0.021 U	0.011 U	0.011 U	0.078 U	0.012 U	0.011 U	0.011 U
Chloroethane	1.9	0.013 U	0.019 U	0.021 U	0.011 U	0.011 U	0.078 U	0.012 U	0.011 U	0.011 U
Ethylbenzene	5.5	0.013 U	0.019 U	0.021 U	0.011 U	0.011 U	0.078 U	0.28	0.012 U	0.003 J
Methyl Bromide	NE	0.013 U	0.019 U	0.021 U	0.011 U	0.011 U	0.078 U	0.019 J	0.015	0.011 U
Methyl Chloride	NE	0.013 U	0.019 U	0.021 U	0.011 U	0.011 U	0.078 U	0.012 U	0.011 U	0.011 U
Methyl Isobutyl Ketone	1	0.013 U	0.019 U	0.021 U	0.011 U	0.011 U	0.078 U	0.012 U	0.011 U	0.011 U
Methylene Chloride	0.1	0.013 U	0.019 U	0.021 U	0.011 U	0.011 U	0.078 U	0.28	0.012 U	0.011 U
Styrene	NE	0.013 U	0.019 U	0.021 U	0.011 U	0.011 U	0.078 U	0.012 U	0.011 U	0.011 U
Tetrachloroethene	1.4	0.013 U	0.019 U	0.021 U	0.011 U	0.011 U	0.078 U	0.012 U	0.011 U	0.011 U
Toluene	1.5	0.013 U	0.019 U	0.021 U	0.011 U	0.011 U	0.078 U	0.012 U	0.011 U	0.011 U
Trans-1,3-Dichloropropene	NE	0.013 U	0.019 U	0.021 U	0.011 U	0.011 U	0.078 U	0.009 J	0.002 J	0.011 U
Trichloroethene	0.7	0.013 U	0.019 U	0.021 U	0.011 U	0.011 U	0.078 U	0.012 U	0.011 U	0.011 U
Vinyl Chloride	0.2	0.013 U	0.019 U	0.021 U	0.011 U	0.011 U	0.078 U	0.012 U	0.011 U	0.011 U
Xylenes (Total)	1.2	0.013 U	0.019 U	0.021 U	0.011 U	0.011 U	0.078 U	0.023 J	0.027	0.011 U
Total VOC TIC	NE	0	0	0.024 J	0	0	0	70.7 J	0.103 J	0.006 J

TABLE 5
SUMMARY OF SOIL ANALYTICAL RESULTS
POST-CLOSURE SOIL BORINGS
FORMER COLUMBIA CEMENT FACILITY
FREEPORT, NEW YORK

BORING ID	NYSDEC TAGN 4046	D-05 N91-9B-68	D-05 D-45-6-18 N80-9B-49	D-05 D-05-20-22 N80-9B-70	D-05 D-06-10-12 N80-9B-73	D-06 D-06-16-18 N80-9B-74	D-06 D-06-20-22 N80-9B-75	D-07 D-07-10-12 N80-9B-81	D-07 D-07-16-18 N80-9B-82
URS SAMPLE ID	Recommended Soil Cleanup Objective (mg/kg)	10/8/2004 10 - 12 (mg/kg)	10/8/2004 16 - 18 (mg/kg)	10/8/2004 20 - 22 (mg/kg)	10/8/2004 10 - 12 (mg/kg)	10/8/2004 16 - 18 (mg/kg)	10/6/2004 20 - 22 (mg/kg)	10/6/2004 10 - 12 (mg/kg)	10/6/2004 16 - 18 (mg/kg)
1,1,1-Trichloroethane	0.8	0.003 J	0.012 U	0.011 U	0.012 U	0.018 U	0.011 U	0.011 U	0.011 U
1,1,2,2-Tetrachloroethane	0.6	0.011 U	0.012 U	0.011 U	0.012 U	0.018 U	0.011 U	0.011 U	0.018 U
1,1,2-Trichloroethane	NE	0.011 U	0.012 U	0.011 U	0.012 U	0.018 U	0.011 U	0.011 U	0.018 U
1,1-Dichloroethane	0.2	0.002 J	0.012 U	0.011 U	0.004 J	0.011 U	0.011 U	0.011 U	0.018 U
1,1-Dichloroethene	0.4	0.011 U	0.012 U	0.011 U	0.018 U	0.011 U	0.011 U	0.011 U	0.001 J
1,2-Dichloroethane	0.1	0.011 U	0.012 U	0.011 U	0.018 U	0.011 U	0.011 U	0.011 U	0.018 U
1,2-Dichloroethene	NE	0.011 U	0.012 U	0.011 U	0.018 U	0.011 U	0.011 U	0.011 U	0.018 U
1,2-Dichloropropane	NE	0.011 U	0.012 U	0.011 U	0.018 U	0.011 U	0.011 U	0.011 U	0.018 U
2-Butanone	0.3	0.024	0.012 U	0.011 U	0.018 U	0.011 U	0.011 U	0.011 U	0.018 U
2-Hexanone	NE	0.011 U	0.012 U	0.011 U	0.018 U	0.011 U	0.011 U	0.011 U	0.018 U
Acetone	0.2	0.049	0.014	0.011 U	0.004	0.018 U	0.011 U	0.011 U	0.018 U
Benzene	0.06	0.002 J	0.012 U	0.011 U	0.067	0.011 U	0.011 U	0.011 U	0.018 U
Bromodichloromethane	NE	0.011 U	0.012 U	0.011 U	0.018 U	0.011 U	0.011 U	0.011 U	0.018 U
Bromoform	NE	0.011 U	0.012 U	0.011 U	0.018 U	0.011 U	0.011 U	0.011 U	0.018 U
Carbon Disulfide	2.7	0.006 J	0.002 J	0.003 J	0.014 J	0.002 J	0.002 J	0.002 J	0.018 U
Carbon Tetrachloride	0.6	0.011 U	0.012 U	0.011 U	0.018 U	0.011 U	0.011 U	0.011 U	0.018 U
Chlorobenzene	1.7	0.011 U	0.012 U	0.011 U	0.011 J	0.011 U	0.011 U	0.011 U	0.018 U
Chlorodibromomethane	NE	0.011 U	0.012 U	0.011 U	0.018 U	0.011 U	0.011 U	0.011 U	0.018 U
Chloroform	0.3	0.011 U	0.012 U	0.011 U	0.018 U	0.011 U	0.011 U	0.011 U	0.018 U
Cis-1,3-Dichloropropene	NE	0.011 U	0.012 U	0.011 U	0.018 U	0.011 U	0.011 U	0.011 U	0.018 U
Chloroethylene	1.9	0.039	0.012 U	0.011 U	0.042	0.011 U	0.011 U	0.011 U	0.018 U
Ethylbenzene	5.5	0.011 U	0.012 U	0.011 U	0.018 U	0.011 U	0.011 U	0.011 U	0.018 U
Methyl Bromide	NE	0.011 U	0.012 U	0.011 U	0.018 U	0.011 U	0.011 U	0.011 U	0.018 U
Methyl Chloride	NE	0.011 U	0.012 U	0.011 U	0.018 U	0.011 U	0.011 U	0.011 U	0.018 U
Methyl Isobutyl Ketone	1	0.011 U	0.012 U	0.011 U	0.018 U	0.011 U	0.011 U	0.011 U	0.018 U
Methylene Chloride	0.1	0.011 U	0.012 U	0.011 U	0.018 U	0.011 U	0.011 U	0.011 U	0.018 U
Styrene	NE	0.011 U	0.012 U	0.011 U	0.018 U	0.011 U	0.011 U	0.011 U	0.018 U
Tetrachloroethene	1.4	0.011 U	0.012 U	0.011 U	0.018 U	0.011 U	0.011 U	0.011 U	0.018 U
Toluene	1.5	0.011 U	0.012 U	0.011 U	0.018 U	0.011 U	0.011 U	0.011 U	0.018 U
Trans-1,3-Dichloropropene	NE	0.011 U	0.012 U	0.011 U	0.014 J	0.011 U	0.011 U	0.011 U	0.0008 J
Trichloroethene	0.7	0.011 U	0.012 U	0.011 U	0.018 U	0.011 U	0.011 U	0.011 U	0.018 U
Vinyl Chloride	0.2	0.011 U	0.012 U	0.011 U	0.018 U	0.011 U	0.011 U	0.011 U	0.018 U
Xylenes (Total)	1.2	0.008 J	0.012 U	0.011 U	0.006 J	0.011 U	0.011 U	0.011 U	0.018 U
Total VOC TIC	NE	1.391 J	0	0	0.617 J	0	0	1.51 J	0

TABLE 5
SUMMARY OF SOIL ANALYTICAL RESULTS
POST-CLOSURE SOIL BORINGS
FORMER COLUMBIA CEMENT FACILITY
FREEPORT, NEW YORK

BORING ID	NYSDEC TAGM 4046	D-07 N80 88-3	D-08 N80 88-78	D-08 N80 88-79	D-08 N80 88-80	D-08 N80 88-81	D-09 N80 188-81	D-09-12-14 N80 188-86	D-09 N80 188-87
URS SAMPLE ID	LAB SAMPLE ID	Recommended Soil cleanup Objective (mg/kg)	10/6/2004 20 - 22	10/8/2004 10 - 12	10/8/2004 16 - 18	10/8/2004 20 - 22	10/8/2004 24 - 26	10/8/2004 12 - 14	10/8/2004 14 - 16
SAMPLE DATE	SAMPLE DEPTH (ft)	UNITS	(mg/kg)	(mg/kg)	(mg/kg)	(mg/kg)	(mg/kg)	(mg/kg)	(mg/kg)
VOC									
1,1,1-Trichloroethane	0.8		0.012 U	8.0 E	0.003 J	0.002 J	0.011 U	0.011 U	0.011 U
1,1,2,2-Tetrachloroethane	0.6		0.012 U	0.18 U	0.011 U	0.012 U	0.011 U	0.011 U	0.011 U
1,1,2-Trichloroethane	NE		0.012 U	0.18 U	0.011 U	0.012 U	0.011 U	0.011 U	0.011 U
1,1-Dichloroethane	0.2		0.012 U	100 D	0.001 J	0.004 J	0.011 U	0.011 U	0.011 U
1,1,1-Dichloroethene	0.4		0.012 U	1.3 D	0.011 U	0.012 U	0.011 U	0.011 U	0.011 U
1,1,2-Dichloroethane	0.1		0.012 U	0.15 J	0.011 U	0.012 U	0.011 U	0.011 U	0.011 U
1,2-Dichloroethene	NE		0.012 U	0.18 U	0.011 U	0.012 U	0.011 U	0.011 U	0.011 U
1,2-Dichloropropane	NE		0.012 U	0.18 U	0.011 U	0.012 U	0.011 U	0.011 U	0.011 U
2-Butanone	0.3		0.012 U	0.18 U	0.011 U	0.012 U	0.011 U	0.011 U	0.011 U
2-Hexanone	NE		0.012 U	0.18 U	0.011 U	0.012 U	0.011 U	0.011 U	0.011 U
Acetone	0.2		0.012 U	0.14 J	0.007 J	0.012 U	0.011 U	0.009 J	0.011 U
Benzene	0.06		0.012 U	0.054 J	0.011 U	0.012 U	0.011 U	0.011 U	0.011 U
Bromodichloromethane	NE		0.012 U	0.18 U	0.011 U	0.012 U	0.011 U	0.011 U	0.011 U
Bromoform	NE		0.012 U	0.18 U	0.011 U	0.012 U	0.011 U	0.011 U	0.011 U
Carbon Disulfide	2.7		0.012 U	0.18 U	0.002 J	0.003 J	0.011 U	0.011 U	0.011 U
Carbon Tetrachloride	0.6		0.012 U	0.18 U	0.011 U	0.012 U	0.011 U	0.002 J	0.011 U
Chlorobenzene	1.7		0.012 U	0.18 U	0.011 U	0.012 U	0.011 U	0.011 U	0.011 U
Chlorodibromomethane	NE		0.012 U	0.18 U	0.011 U	0.012 U	0.011 U	0.011 U	0.011 U
Chloroform	0.3		0.012 U	0.18 U	0.011 U	0.012 U	0.011 U	0.011 U	0.011 U
Cis-1,3-Dichloropropene	NE		0.012 U	0.18 U	0.011 U	0.012 U	0.011 U	0.011 U	0.011 U
Chloroethane	1.9		0.012 U	7.7 D	0.011 U	0.21	0.011 U	0.011 U	0.011 U
Ethylbenzene	5.5		0.012 U	0.18 U	0.011 U	0.012 U	0.011 U	0.011 U	0.011 U
Methyl Bromide	NE		0.012 U	0.18 U	0.011 U	0.012 U	0.011 U	0.011 U	0.011 U
Methyl Chloride	NE		0.012 U	1.0	0.011 U	0.012 U	0.011 U	0.011 U	0.011 U
Methyl Isobutyl Ketone	1		0.012 U	0.18 U	0.011 U	0.012 U	0.011 U	0.011 U	0.011 U
Methylene Chloride	0.1		0.012 U	1.0	0.011 U	0.012 U	0.011 U	0.011 U	0.011 U
Silrene	NE		0.012 U	0.18 U	0.011 U	0.012 U	0.011 U	0.011 U	0.011 U
Tetrachloroethene	1.4		0.012 U	0.11 J	0.011 U	0.012 U	0.011 U	0.011 U	0.011 U
Toluene	1.5		0.012 U	1.1	0.011 U	0.012 U	0.011 U	0.011 U	0.011 U
Trans-1,3-Dichloropropene	NE		0.012 U	1.0	0.011 U	0.012 U	0.011 U	0.011 U	0.011 U
Trichloroethene	0.7		0.012 U	0.061 J	0.011 U	0.012 U	0.011 U	0.011 U	0.011 U
Vinyl Chloride	0.2		0.012 U	0.18 U	0.011 U	0.012 U	0.011 U	0.011 U	0.011 U
Xylenes (Total)	1.2		0.012 U	0.18 U	0.011 U	0.012 U	0.011 U	0.011 U	0.011 U
Total VOC TIC	NE		0	9.3 J	0	0.03 J	0	0	0

TABLE 5
SUMMARY OF SOIL ANALYTICAL RESULTS
POST-CLOSURE SOIL BORINGS
FORMER COLUMBIA CEMENT COMPANY FACILITY
FREEPORT, NEW YORK

NOTES:

mg/kg : Milligrams Per Kilogram (ppm)

U : Compound was not detected.

J : The result is a quantitatively estimated value.

D : Result is obtained from a diluted sample.

NE : Not Established

Boxed : Exceeds NYSDEC TAGM Recommended Soil Cleanup Objective

TABLE 6
SUMMARY OF FIELD PARAMETERS
JUNE 2004 GROUNDWATER SAMPLING
FORMER COLUMBIA CEMENT COMPANY FACILITY
FREEPORT, NY

Well	MW-1S	MW-1D-97	MW-97-1S	MW-98-9D	MW-97-2S	MW-98-10D	MW-97-6S	MW-97-7S
Date	6/7/2004	6/7/2004	6/8/2004	6/8/2004	6/8/2004	6/9/2004	6/9/2004	6/9/2004
DTW (ft)	6.64	5.8	5.95	5.9	6.89	7	6.72	6.9
TD (ft)	20.96	33.62	21.14	36.56	23.93	34.94	25.73	31.75
pH (Std. Units)	6.55	6.64	6.28	6.29	6.15	6.19	6.13	6.27
ORP (mV)	-86	-51.4	-31.2	-26.6	-14.5	-207.3	-15.3	-14.3
Temp. (Deg. C)	15.74	17.68	16.57	17.71	17.56	18.83	17.05	17.55
Spec. Cond. (mS/cm)	1.48	1.84	0.794	0.85	0.982	0.899	1.401	0.905
D.O. (mg/l)	0.23	0.33	0.29	0.35	0.48	0.69	0.41	0.34
Turbidity (NTU)	1084.8	5.9	250.1	1096.1	164.7	24.8	245	371.9

NOTES:

(ft) : Feet
 DTW : Depth to water from top of casing
 TD : Total depth from top of casing

ph (Std. Units) : pH measured in Standard Units
 ORP (mV) : Oxidation-Reduction Potential measured in millivolts
 Temp. (Deg. C) : Temperature measured in degrees centigrade
 Spec. Cond. (mS/cm) : Specific Conductance measured in micro-Siemens per centimeter
 D.O. (mg/l) : Dissolved Oxygen measured in milligrams per liter.
 Turbidity (NTU) : Turbidity measured in nephelometric turbidity units

TABLE 6
SUMMARY OF FIELD PARAMETERS
JUNE 2004 GROUNDWATER SAMPLING
FORMER COLUMBIA CEMENT COMPANY FACILITY
FREEPORT, NY

Well	MW-97-3S	MW-98-8D	MW-98-8S	MW-00-11A	MW-03-13S	MW-00-12D	MW-97-4S	MW-97-5S
Date	6/9/2004	6/9/2004	6/9/2004	6/9/2004	6/10/2004	6/10/2004	6/10/2004	6/10/2004
DTW (ft)	6.99	7.17	7.25	2.46	6.18	6.77	7.14	7.01
TD (ft)	24.81	34.88	19.76	60.14	24.28	34.7	24.95	25.41
pH (Std. Units)	6.37	6.51	6.67	5.13	6.53	6.59	6.54	6.66
ORP (mV)	-165.3	-81.2	-72.8	-206.4	-42.8	-33.5	-173	-159
Temp. (Deg. C)	17.38	17.28	14.75	18.44	19.59	15.89	15.8	15.31
Spec. Cond. (mS/cm)	1.75	1.083	1.967	0.026	1.044	1.437	1.18	0.891
D.O. (mg/l)	0.33	0.36	0.35	0.25	0.43	0.35	0.25	0.28
Turbidity (NTU)	236.9	5.1	2.4	240.6	957.2	576.2	83.4	41

NOTES:

(ft) : Feet
DTW : Depth to water from top of casing
TD : Total depth from top of casing

ph (Std. Units) : pH measured in Standard Units

ORP (mV) : Oxidation-Reduction Potential measured in millivolts

Temp. (Deg. C) : Temperature measured in degrees centigrade

Spec. Cond. (mS/cm) : Specific Conductance measured in micro-Siemens per centimeter

D.O. (mg/l) : Dissolved Oxygen measured in milligrams per liter.

Turbidity (NTU) : Turbidity measured in nephelometric turbidity units

TABLE 7
SUMMARY OF GROUNDWATER ANALYTICAL RESULTS
JUNE 2004 GROUNDWATER SAMPLING
FORMER COLUMBIA CEMENT COMPANY FACILITY
FREEPORT, NEW YORK

WELL ID	NYSDC TAG#	MW-16 MW-15	MW-97-1S	MW-10-97	MW-97-2S	MW-97-3S	MW-97-4S	MW-97-5S	MW-97-5S
FIELD SAMPLE ID									
DAB SAMPLE ID									
SAMPLE ID									
Volatile Organic Compounds (ug/l)									
1,1,1-Trichloroethane	5		150 JD	10 U					
1,1,2,2-Tetrachloroethane	5		10 U						
1,1,2-Trichloroethane	1		10 U						
1,1-Dichloroethane	5		660 JD	10 U					
1,1-Dichloroethene	5		10 U						
1,2-Dichloroethane	0.6		10 U						
1,2-Dichloroethene (Total)	5		4 J	10 U					
1,2-Dichloropropane	1		10 U						
2-Butanone	50		10 U						
2-Hexanone	50		10 U						
Acetone	50		10 U						
Benzene	1		15	10 U					
Bromodichloromethane	5		10 U						
Bromotform	5		10 U						
Carbon Disulfide									
Carbon Tetrachloride	NA		10 U						
Chlorobenzene	5		10 U						
Chlorodibromomethane	5		10 U						
Chloroform	7		10 U						
Cis-1,3-Dichloropropene	0.4		10 U						
Ethyl Chloride	5		10,000 D	430 D	10 U	10 U	10 U	190 D	79
Ethylbenzene	5		2 J	10 U	10 U	10 U	10 U		410 D
Methyl Bromide	5		10 U						
Methyl Chloride	5		10 U						
Methyl Isobutyl Ketone	NS		10 U						
Methylene Chloride	5		230 JD	10 U					
Styrene	5		10 U						
Tetrachloroethene	5		10 U						
Toluene	5		4 J	10 U					
Trans-1,3-Dichloropropene	0.4		10 U						
Trichloroethane	5		10 U						
Vinyl Chloride	2		15	10 U					
Xylenes (Total)	5		10	2 J	10 U				
Total VOC TIC	NE		1154 J	60 J	0	55 J	42 J	12 J	0
Dissolved Gases (ug/l)									
Ethane	NE		1320	47.5	8.19	1.4	1.2	75	22.2
Ethane	NE		1.3	0.075 J	15				
Methane	NE		6320	9430	907	10000	9520	2090	0.075 J
								4210	9030

TABLE 7
SUMMARY OF GROUNDWATER ANALYTICAL RESULTS
JUNE 2004 GROUNDWATER SAMPLING
FORMER COLUMBIA CEMENT COMPANY FACILITY
FREEPORT, NEW YORK

WELL ID	FIELD SAMPLE ID	INSIDE	W-97-SS	W-97-S7	MW-97-2S	MW-97-3S	MW-97-4S	MW-97-5S	MW-97-6S
	FIELD SAMPLE ID	ANALYST	ANALYST	ANALYST	ANALYST	ANALYST	ANALYST	ANALYST	ANALYST
Total Iron		NE	26.9	23.8	9.14	29.5	0.177	2.63	8.07
Iron II		NE	11.7	13.1	1.3	19.9	10.0 U	1.4	30.6
Total Manganese		NE	NT	0.13	0.416	0.192	0.0471	NT	1.4
Manganese II		NE	0.43 J	1.0 U	0.39 J	0.18 J	1.0 U	NT	0.224
Total Dissolved Solids		NE	693	400	1040	606	549	701	814
Alkalinity, Total As CaCO ₃		NE	138	54	132	38.4	398	119	79.7
Chloride		NE	0.110 U	0.110 U	0.110 U	0.110 U	0.110 U	0.110 U	0.110 U
Nitrate		NE	0.100 U	0.100 U	0.100 U	0.100 U	0.100 U	0.100 U	0.100 U
Nitrate/Nitrite Nitrogen		NE	0.010 U	0.010 U	0.010 U	0.010 U	0.010 U	0.010 U	0.010 U
Nitrite		NE	20.0 U	20.0 U	27.1	20.0 U	20.0 U	63.6	20.0 U
Sulfate		NE	10.1	6.7	10.9	8.5	22.9	6.5	10.1
Total Organic Carbon		NE							

TABLE 7
SUMMARY OF GROUNDWATER ANALYTICAL RESULTS
JUNE 2004 GROUNDWATER SAMPLING
FORMER COLUMBIA CEMENT COMPANY FACILITY
FREEPORT, NEW YORK

WELL ID	NYSDEC TAG#	TAG# Groundwater	MW 98-35 MW 98-35 NS9286-5 NS9286	MW 98-35 MW 98-35 NS9286-5 NS9286	MW 98-9D MW 98-9D N69-50-2A	MW 98-10D MW 98-10D N69-50-5A	MW-00-1A MW-00-1A N69285-7	MW-00-12D MW-00-12D N69400-2	MW-03-13S MW-03-13S N69400-1
FIELD SAMPLE ID	LAB SAMPLE ID	SAMPLE ID	Standard Conc. (ppm)	Sample Conc. (ppm)	Sample Conc. (ppm)	Sample Conc. (ppm)	Sample Conc. (ppm)	Sample Conc. (ppm)	Sample Conc. (ppm)
Volatile Organic Compounds (ppm)									
1,1,1-Trichloroethane	5		10 U	10 U	10 U	10 U	10 U	10 U	10 U
1,1,2,2-Tetrachloroethane	5		10 U	10 U	10 U	10 U	10 U	10 U	10 U
1,1,2-Trichloroethane	1		10 U	10 U	10 U	10 U	10 U	10 U	10 U
1,1-Dichloroethene	5		10 U	10 U	10 U	10 U	10 U	10 U	10 U
1,2-Dichloroethane	0.6		10 U	10 U	10 U	10 U	0 U	10 U	10 U
1,2-Dichloroethene (Total)	5		10 U	10 U	10 U	10 U	10 U	10 U	10 U
1,2-Dichloropropane	1		10 U	10 U	10 U	10 U	10 U	10 U	10 U
2-Butanone	50		10 U	10 U	10 U	10 U	10 U	10 U	10 U
2-Hexanone	50		10 U	10 U	10 U	10 U	10 U	10 U	10 U
Acetone	50		10 U	10 U	10 U	10 U	10 U	10 U	10 U
Benzene	1		10 U	10 U	10 U	10 U	10 U	10 U	10 U
Bromodichloromethane	5		10 U	10 U	10 U	10 U	10 U	10 U	10 U
Bromoform	5		10 U	10 U	10 U	10 U	10 U	10 U	10 U
Carbon Disulfide	NA		10 U	10 U	10 U	10 U	10 U	10 U	10 U
Carbon Tetrachloride	5		10 U	10 U	10 U	10 U	10 U	10 U	10 U
Chlorobenzene	5		4 J	10 U	10 U	7 J	7 J	10 U	10 U
Chlorodibromomethane	5		10 U	10 U	10 U	10 U	10 U	10 U	10 U
Chloroform	7		10 U	10 U	10 U	10 U	10 U	10 U	10 U
Cis-1,3-Dichloropropene	0.4		10 U	10 U	10 U	10 U	10 U	10 U	10 U
Ethyl Chloride	5		10 U	10 U	14	510 D	10 U	10 U	10 U
Ethylbenzene	5		10 U	10 U	10 U	10 U	10 U	10 U	10 U
Methyl Bromide	5		10 U	10 U	10 U	10 U	10 U	10 U	10 U
Methyl Chloride	5		10 U	10 U	10 U	10 U	10 U	10 U	10 U
Methyl Isobutyl Ketone	NS		10 U	10 U	10 U	10 U	10 U	10 U	10 U
Methylene Chloride	5		10 U	10 U	10 U	10 U	10 U	10 U	10 U
Styrene	5		10 U	10 U	10 U	10 U	10 U	10 U	10 U
Tetrachloroethene	5		10 U	10 U	10 U	10 U	10 U	10 U	10 U
Toluene	5		10 U	10 U	10 U	10 U	10 U	10 U	10 U
Trans-1,3-Dichloropropene	0.4		10 U	10 U	10 U	10 U	10 U	10 U	10 U
Trichloroethene	5		10 U	10 U	10 U	10 U	10 U	10 U	10 U
Vinyl Chloride	2		10 U	10 U	10 U	10 U	10 U	10 U	10 U
Xylenes (Total)	5		10 U	10 U	10 U	10 U	10 U	10 U	10 U
Total VOC TIC	NE		10 J	0	10 U	2 J	10 U	10 U	10 U
Dissolved Gasses (ug/l)									
Ethane	NE		NT	1.5	10.1	64.8	0.67	NT	145
Ethene	NE		NT	0.075 U	0.075 U	0.075 U	0.075 U	NT	0.31
Methane	NE		NT	3820	3790	9600	9360	NT	0.075 U
						61 J	0	32 J	73 J

TABLE 7
SUMMARY OF GROUNDWATER ANALYTICAL RESULTS
JUNE 2004 GROUNDWATER SAMPLING
FORMER COLUMBIA CEMENT COMPANY FACILITY
FREERPORT, NEW YORK

WELL ID	NYSDEC TAGM 404	MW-97-7S	MW-98-8S	MW-98-8D	MW-98-9D	MW-98-10D	MW-0-11A	MW-0-12D	MW-03-13S
FIELD SAMPLE ID		MW-97-7S	MW-98-8S	MW-98-8D	MW-98-9D	MW-98-10D	MW-0-11A	MW-0-12D	MW-03-13S
LAB SAMPLE ID		N6926-5	N6926-5	N6926-5	N6926-5	N69150-2A	N69286-7	N69400-2	N69400-1
SAMPLE ID									
Metals (mg/l)									
Total Iron	NE	NT	14	5.1	17.7	17.9	NT	10.9	22.8
Iron II	NE	NT	100 U	100 U	9.9	11	NT	2.2	3.7
Total Manganese	NE	NT	0.534	0.418	0.241	NT	NT	NT	0.152
Manganese II	NE	NT	0.49 J	0.38 J	0.20 J	NT	NT	NT	0.12 J
Miscellaneous (mg/l)									
Alkalinity, Total As CaCO ₃	NE	NT	1070	697	424	453	NT	988	525
Chloride	NE	NT	179	68.7	58.5	74.3	NT	121	123
Nitrate	NE	NT	0.110 U	0.110 U	0.110 U	0.110 U	NT	0.110 U	0.110 U
Nitrate/Nitrite Nitrogen	NE	NT	0.100 U	0.100 U	0.100 U	0.100 U	NT	0.100 U	0.100 U
Nitrite	NE	NT	0.010 U	0.010 U	0.010 U	0.010 U	NT	0.010 U	0.010 U
Sulfate	NE	NT	23.1	20.0 U	20.0 U	20.0 U	NT	26.9	20.0 U
Total Organic Carbon	NE	NT	11.3	7.9	7.7	6.6	NT	9.4	8.8

TABLE 7
SUMMARY OF GROUNDWATER ANALYTICAL RESULTS
JUNE 2004 GROUNDWATER SAMPLING
FORMER COLUMBIA CEMENT COMPANY FACILITY
FREEPORT, NEW YORK

NOTES:

Box/Bold : Exceeds NYSDDEC GW Standard

D : Result is obtained from a diluted sample.

J : The result is a quantitatively estimated value.

U : Compound was not detected.

NE : Not Established

NT : Not Tested

$\mu\text{g/l}$: Micrograms Per Liter

mg/l : Milligrams Per Liter

TABLE 8
SUMMARY OF FIELD MEASUREMENTS
APRIL 2005 GROUNDWATER SAMPLING
FORMER COLUMBIA CEMENT COMPANY FACILITY
FREEPORT, NY

Well	MW-97-1S	MW-98-9D	MW-05-14S	MW-05-15D	MW-03-13S
Date	4/26/2005	4/26/2005	4/26/2005	4/26/2005	4/26/2005
DTW (ft)	5.82	5.85	5.04	4.95	6.05
TD (ft)	24.11	36.34	25.00	38.30	24.30
pH (Std. Units)	6.48	6.39	6.34	6.62	6.8
ORP (mV)	-108	-117	-86	-71	-135
Temp. (Deg. C)	17.14	17.94	16.63	17.79	15.66
Spec. Cond. (mS/cm)	0.89	0.90	14.30	0.30	0.90
D.O. (mg/l)	0.0	0.0	0.0	0.0	0.0
Turbidity (NTU)	89.1	225	61	39.2	32.8

NOTES:

(ft) : Feet

DTW : Depth to water from top of casing

TD : Total depth from top of casing

pH (Std. Units) : pH measured in Standard Units

ORP (mV) : Oxidation-Reduction Potential measured in millivolts

Temp. (Deg. C) : Temperature measured in degrees centigrade

Spec. Cond. (mS/cm) : Specific Conductance measured in micro-Siemens per centimeter

D.O. (mg/l) : Dissolved Oxygen measured in milligrams per liter.

Turbidity (NTU) : Turbidity measured in nephelometric turbidity units

TABLE 9
SUMMARY OF GROUNDWATER ANALYTICAL RESULTS
APRIL 2005 GROUNDWATER SAMPLING
FORMER COLUMBIA CEMENT COMPANY FACILITY
FREEPORT, NEW YORK

URS Sample ID Laboratory Sample ID Sampling Date Dilution Factor Units	NYSDEC TAGM 4046 Groundwater Standard (ppm)	MW-87 TS N97288-3 04/26/05	MW-98-9D N97288-2 04/26/05	MW-05-14S N97288-5 04/26/05	MW-05-15D N97288-6 04/26/05	MW-05-15D DUP N97288-7 04/26/05	MW-03-13S N97288-4 04/26/05	TB042605 N97288-1 04/26/05
Volatile Organic Compounds	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l
1,1,1-Trichloroethane	5	10 U	100 U	10 U	10 U	10 U	10 U	10 U
1,1,2,2-Tetrachloroethane	5	10 U	100 U	10 U	10 U	10 U	10 U	10 U
1,1,2-Trichloroethane	NA	10 U	100 U	10 U	10 U	10 U	10 U	10 U
1,1-Dichloroethane	5	10 U	100 U	10 U	10 U	10 U	10 U	10 U
1,1-Dichloroethene	5	10 U	100 U	10 U	10 U	10 U	10 U	10 U
1,2-Dichloroethane	5	10 U	100 U	10 U	10 U	10 U	10 U	10 U
1,2-Dichloroethylene (total)	NA	10 U	100 U	10 U	10 U	10 U	10 U	10 U
1,2-Dichloropropane	NA	10 U	100 U	10 U	10 U	10 U	10 U	10 U
2-Butanone	50	10 U	100 U	10 U	10 U	10 U	10 U	10 U
2-Hexanone	NA	10 U	100 U	10 U	10 U	10 U	10 U	10 U
4-Methyl-2-pentanone	NA	10 U	100 U	10 U	10 U	10 U	10 U	10 U
Acetone	50	10 U	100 U	10 U	10 U	10 U	10 U	10 U
Benzene	0.7	10 U	100 U	10 U	10 U	10 U	10 U	10 U
Bromodichloromethane	NA	10 U	100 U	10 U	10 U	10 U	10 U	10 U
Bromoform	NA	10 U	100 U	10 U	10 U	10 U	10 U	10 U
Bromomethane	NA	10 U	100 U	10 U	10 U	10 U	10 U	10 U
Carbon disulfide	50	10 U	100 U	10 U	10 U	10 U	10 U	10 U
Carbon tetrachloride	5	10 U	100 U	10 U	10 U	10 U	10 U	10 U
Chlorobenzene	5	3 J	100 U	24	3 J	3 J	2 J	10 U
Chloroethane	50	170	910 D	13	120	110	10 U	10 U
Chloroform	7	10 U	100 U	10 U	10 U	10 U	10 U	10 U
Chloromethane	NA	10 U	100 U	10 U	10 U	10 U	10 U	10 U
cis-1,3-Dichloropropene	NA	10 U	100 U	10 U	10 U	10 U	10 U	10 U
Dibromchloromethane	50	10 U	100 U	10 U	10 U	10 U	10 U	10 U
Ethylbenzene	5	10 U	100 U	10 U	10 U	10 U	10 U	10 U
Methylene chloride	5	10 U	100 U	10 U	10 U	10 U	10 U	10 U
Styrene	NA	10 U	100 U	10 U	10 U	10 U	10 U	10 U
Tetrachloroethene	5	10 U	100 U	10 U	10 U	10 U	10 U	10 U
Toluene	5	10 U	100 U	10 U	10 U	10 U	10 U	10 U
trans-1,3-Dichloropropene	NA	10 U	100 U	10 U	10 U	10 U	10 U	10 U
Trichloroethene	5	10 U	100 U	10 U	10 U	10 U	10 U	10 U
Vinyl chloride	2	10 U	100 U	10 U	10 U	10 U	10 U	10 U
Xylene (total)	5	1 J	100 U	10 U	10 U	10 U	10 U	10 U
Total Target VOCs	NA	174	910	37	123	112	0	0
Total TIC, Volatile	NA	79 J	120 J	6 J	31 J	26 J	134 J	0

BLE 9
SUMMARY OF GROUNDWATER ANALYTICAL RESULTS
APRIL, 2005 SAMPLING EVENT
FORMER COLUMBIA CEMENT COMPANY FACILITY
FREEPORT, NEW YORK

NOTES:

Box/Bold : Exceeds NYSDDEC GW Standard

D : Result is obtained from a diluted sample.

J : The result is a quantitatively estimated value.

U : Compound was not detected.

NE : Not Established

NT : Not Tested

µg/l : Micrograms Per Liter

mg/l : Milligrams Per Liter

TABLE 10
SUMMARY OF FIELD MEASUREMENTS
JUNE 2006 GROUNDWATER SAMPLING
FORMER COLUMBIA CEMENT COMPANY FACILITY
FREEPORT, NY

Well	MW-1S	MW-97-1S	MW-1D-97	MW-97-2S	MW-97-3S	MW-97-4S	MW-97-5S	MW-97-6S	MW-97-7S
Data	6/7/2006	6/7/2006	6/7/2006	6/9/2006	6/9/2006	6/8/2006	6/9/2006	6/8/2006	6/6/2006
Ref. Elevation (ft MSL)	6.84	6.46	6.89	7.52	7.47	7.69	6.73	7.57	7.61
DTW (ft)	5.62	5.33	5.85	6.52	6.10	6.64	5.47	6.42	6.73
GW Elev. (ft MSL)	1.22	1.13	1.04	1.00	1.37	1.05	1.26	1.15	0.88
TD (ft)	20.02	24.08	33.65	23.93	24.76	24.95	15.50	25.66	31.35
pH (Std. Units)	7.37	6.52	6.93	6.43	6.68	6.97	7.03	6.47	6.66
ORP (mV)	-195	-90	57	-80	-69	-102	-147	-80	-108
Temp. (Deg. C)	15.59	15.98	15.37	17.43	16.66	15.99	16.83	16.58	17.13
Spec. Cond. (mS/cm)	1.28	1.34	1.40	1.22	1.94	1.58	0.942	1.69	1.09
D.O. (mg/l)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Turbidity (NTU)	83.6	7.4	0.9	77.6	29.8	7.6	266	5.8	0.7

NOTES:

Ref. Elevation (ft MSL) : Elevation of top of well casing measured in feet above Mean Sea Level

(ft) : Feet

DTW : Depth to water from top of casing

GW Elev. (ft MSL) : Groundwater elevation measured in feet above Mean Sea Level

TD : Total depth from top of casing

ph (Std. Units) : pH measured in Standard Units

ORP (mV) : Oxidation-Reduction Potential measured in millivolts

Temp. (Deg. C) : Temperature measured in degrees centigrade

Spec. Cond. (mS/cm) : Specific Conductance measured in micro-Siemens per centimeter

D.O. (mg/l) : Dissolved Oxygen measured in milligrams per liter.

Turbidity (NTU) : Turbidity measured in nephelometric turbidity units

TABLE 10
SUMMARY OF FIELD MEASUREMENTS
JUNE 2006 GROUNDWATER SAMPLING
FORMER COLUMBIA CEMENT COMPANY FACILITY
FREEPORT, NY

Well	MW-98-8S	MW-98-8D	MW-98-9D	MW-98-10D	MW-00-11A	MW-00-12D	MW-03-13S	MW-05-14S	MW-05-15D
Data	6/7/2006	6/7/2006	6/8/2006	6/9/2006	6/7/2006	6/8/2006	6/6/2006	6/8/2006	6/8/2006
Ref. Elevation (ft MSL)	7.88	7.69	6.43	7.72	6.45	7.41	6.83	5.76	5.74
DTW (ft)	6.90	6.57	5.42	6.69	3.10	6.36	6.43	4.69	4.59
GW Elev. (ft MSL)	0.98	1.12	1.01	1.03	3.35	1.05	0.40	1.07	1.15
TD (ft)	20.82	34.79	36.52	34.85	60.55	34.57	24.30	24.93	38.23
pH (Std. Units)	6.84	6.87	6.46	6.51	5.36	6.92	6.83	6.56	6.29
ORP (mV)	-137	-125	-85	-84	206	-101	-163	-99	-52
Temp. (Deg. C)	15.74	16.14	16.47	17.79	15.73	16.16	19.51	16.17	16.77
Spec. Cond. (mS/cm)	2.57	2.25	1.35	1.20	0.040	1.88	1.30	9.65	0.311
D.O. (mg/l)	0.0	0.0	0.0	0.0	2.51	0.0	0.0	0.0	0.0
Turbidity (NTU)	13.9	3.1	35.1	247	1.7	8.9	216	3.9	8.2

NOTES:

Ref. Elevation (ft MSL) : Elevation of top of well casing measured in feet above Mean Sea Level

(ft) : Feet

DTW : Depth to water from top of casing

GW Elev. (ft MSL) : Groundwater elevation measured in feet above Mean Sea Level

TD : Total depth from top of casing

ph (Std. Units) : pH measured in Standard Units

ORP (mV) : Oxidation-Reduction Potential measured in millivolts

Temp. (Deg. C) : Temperature measured in degrees centigrade

Spec. Cond. (mS/cm) : Specific Conductance measured in micro-Siemens per centimeter

D.O. (mg/l) : Dissolved Oxygen measured in milligrams per liter.

Turbidity (NTU) : Turbidity measured in nephelometric turbidity units

**SUMMARY OF GROUNDWATER ANALYTICAL RESULTS
JUNE 2006 GROUNDWATER SAMPLING
FORMER COLUMBIA CEMENT COMPANY FACILITY
REPORT, NEW YORK**

TABLE 11
SUMMARY OF GROUNDWATER ANALYTICAL RESULTS
JUNE 2006 GROUNDWATER SAMPLING
FORMER COLUMBIA CEMENT COMPANY FACILITY
FREEPORT, NEW YORK

URS Sample ID	NYSDDEC ID/GW 404	MW-1S	MW-97-1S	DW-060706	MW-1D-97	MW-97-2S	MW-97-3S	MW-97-4S
Laboratory Sample ID		7416	743172	74314	743163	743951	743949	743967
Sampling Date		06/07/06	06/07/06	06/07/06	06/07/06	06/07/06	06/08/06	06/08/06
Dilution Factor		1.0	1.0	1.0	1.0	1.0	1.0	1.0
Units	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l	ug/l
Metals (mg/l)								
Total Iron	NE	27700	29300	29900	3110	34200	240	994
Dissolved iron	NE	39.7	150	150	39.7	6790	134	39.7
Miscellaneous (mg/l)								
Alkalinity - mg/l	NE	498			876	521	499	644
Chloride - mg/l	NE	86.7	560	531	77.4	42.3	294	86.1
Sulfate - mg/l	NE	1.0	77.5	180	1.0	5.0	5.0	36.7
Total Organic Carbon - mg/l	NE	6.5	11.6	11.7	33.1	9.3	20.6	98.1
								6.7
								5.2

TABLE 11
SUMMARY OF GROUNDWATER ANALYTICAL RESULTS
JUNE 2006 GROUNDWATER SAMPLING
FORMER COLUMBIA CEMENT COMPANY FACILITY
FREEPORT, NEW YORK

URS Sample ID	NYSDEC Tag#	MW-97-6S	MW-97-7S	MW-98-8S	MW-98-9D	MW-98-10D	MW-00-11A
Laboratory Sample ID	Tag#	743968	743112	743170	743966	743169	743968
Sampling Date	Sample Date	06/06/06	06/07/06	06/07/06	06/08/06	06/07/06	06/08/06
Division Factor Units		1.0	1.0	1.0	1.0	1.0	1.0
Volatile Organic Compounds		ug/L	ug/L	ug/L	ug/L	ug/L	ug/L
1,1,1-Trichloroethane	5	0.7	0.3	0.3	0.3	3.4	0.3
1,1,2,2-Tetrachloroethane	5	0.7	0.3	0.3	0.3	3.4	0.3
1,1,2-Trichloroethane	1	0.7	0.3	0.3	0.3	3.3	0.3
1,1-Dichloroethane	5	0.6	0.3	0.3	0.3	3.2	0.3
1,1-Dichloroethene	5	0.7	0.4	0.4	0.4	3.5	0.4
1,2-Dichloroethane	0.6	0.6	0.3	0.3	0.3	2.9	0.3
cis-1,2-Dichloroethene	NA	0.9	0.4	0.4	0.4	4.3	0.4
trans-1,2-Dichloroethene	NA	0.9	0.4	0.4	0.4	4.3	0.4
1,2-Dichloroethene (Total)	5	0.9	0.4	0.4	0.4	4.3	0.4
1,2-Dichloropropane	1	0.6	0.3	0.3	0.3	2.9	0.3
2-Butanone	50	1.9	0.9	0.9	0.9	9.4	0.9
2-Hexanone	50	1.0	0.5	0.5	0.5	5.2	0.5
Acetone	50	2.5	1.3	1.3	1.3	13	1.3
Benzene	1	0.7	0.3	0.3	0.3	3.3	0.3
Bromodichloromethane	5	0.6	0.3	0.3	0.3	3.2	0.3
Bromform	5	0.4	0.2	0.2	0.2	2.2	0.2
Bromomethane	5	0.6	0.3	0.3	0.3	3.2	0.3
Carbon Disulfide	NA	0.7	0.3	0.3	0.3	3.4	0.3
Carbon Tetrachloride	5	0.6	0.3	0.3	0.3	3.1	0.3
Chlorobenzene	5	3.8	1.3	0.4	0.4	12	7.3
Chlorodibromomethane	5	0.5	0.3	0.3	0.3	2.7	0.3
Chloroethane	5	200	0.2	0.2	0.2	730	0.2
Chloroform	7	1.0	0.5	0.5	0.5	5.2	0.5
Chloromethane	5	0.6	0.3	0.3	0.3	2.9	0.3
cis-1,3-Dichloropropene	0.4	0.5	0.2	0.2	0.2	2.4	0.2
Ethybenzene	5	0.9	0.5	0.5	0.5	4.6	0.5
Methyl Isobutyl Ketone	NS	1.0	0.5	0.5	0.5	5.2	0.5
Methylene Chloride	5	1.0	0.5	0.5	0.5	5.1	0.5
Styrene	5	0.8	0.4	0.4	0.4	3.9	0.4
Tetrachloroethene	5	0.9	0.4	0.4	0.4	4.5	0.4
Toluene	5	0.8	0.4	0.4	0.4	4.0	0.4
trans-1,3-Dichloropropene	0.4	0.5	0.2	0.2	0.2	2.4	0.2
Trichloroethene	5	0.7	0.4	0.4	0.4	3.7	0.4
Vinyl Chloride	2	0.6	0.3	0.3	0.3	2.8	0.3
Xylene(Total)	5	0.8	0.4	0.4	0.4	3.8	0.4
Total Confident Conc. VOAs (s)	NE	204	1.3	0	38	742	11
Total Estimated Conc. VOATICs (s)	NE	0	3.9	0	0	51	92
Dissolved Gases (ug/L)						0	0
Methane	NE	12000	10000	8000	7200	11000	5.0
Ethene	NE	500	500	500	500	1000	5.0
Ethane	NE	500	500	500	500	1000	5.0

Table 11
SUMMARY OF GROUNDWATER ANALYTICAL RESULTS
JUNE 2006 GROUNDWATER SAMPLING
FORMER COLUMBIA CEMENT COMPANY FACILITY
FREEPORT, NEW YORK

URS Sample ID	NYDEC ID	MW-97-69	MW-97-75	MW-98-45	MW-98-80	MW-98-9D	MW-98-10B	MW-98-11A	MW-98-12D
Laboratory Sample ID	TACh 408	73868	74112	74317	74317	74316	74316	74316	743968
Sampling Date	06/06/06	06/06/06	06/06/06	06/07/06	06/07/06	06/08/06	06/08/06	06/07/06	06/08/06
Dilution Factor	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0
Units	ug/L	ug/L	ug/L						
Metals (mg/l)									
Total Iron	NE	33900	23400	15400	15900	27800	21100	936	7110
Dissolved Iron	NE	2550	39.7 U	150 U	150 U	4170	1830	268	39.7 U
Miscellaneous (mg/l)									
Alkalinity - mg/l	NE	751	468	862	916	545	488	8.07	774
Chloride - mg/l	NE	75.4	59.9	277	170	92.5	79.2	5.0 U	128
Sulfate - mg/l	NE	5.0 U	5.0 U	1.0 U	1.0 U	5.0 U	5.0 U	1.0 U	54.7
Total Organic Carbon - mg/l	NE	14.0	6.7	13.7	13.4	11.4	2.2	1.0 U	10.1

TABLE 11
SUMMARY OF GROUNDWATER ANALYTICAL RESULTS
JUNE 2006 GROUNDWATER SAMPLING
FORMER COLUMBIA CEMENT COMPANY FACILITY
FREERPORT, NEW YORK

URS Sample ID	NYSDEC Lab ID	Tank 104 Groundwater Conc. (ug/L)	TWW-06-14S 743964 06/08/06	TWW-05-15D 743953 06/09/06	TB-060606 743111 06/06/06	FB-060606 743115 06/06/06	TB-060606-Diss 743113 06/06/06	FB-060606-Diss 743115 06/06/06	TB-060606 743113 06/06/06	1.0 ug/L
Volatile Organic Compounds	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	
1,1,1-Trichloroethane	5	0.3	0.3	0.3	0.3	0.3	0.3	0.3	0.3	NR
1,1,2,2-Tetrachloroethane	5	0.3	0.3	0.3	0.3	0.3	0.3	0.3	0.3	NR
1,1-Dichloroethane	1	0.3	0.3	0.3	0.3	0.3	0.3	0.3	0.3	NR
1,1-Dichloroethene	5	0.4	0.4	0.4	0.4	0.4	0.4	0.4	0.4	NR
1,2-Dichloroethane	0.6	0.3	0.3	0.3	0.3	0.3	0.3	0.3	0.3	NR
dis-1,2-Dichloroethene	NA	0.4	0.4	0.4	0.4	0.4	0.4	0.4	0.4	NR
trans-1,2-Dichloroethene	NA	0.4	0.4	0.4	0.4	0.4	0.4	0.4	0.4	NR
1,2-Dichloroethene (Total)	5	0.4	0.4	0.4	0.4	0.4	0.4	0.4	0.4	NR
1,2-Dichloropropane	1	0.3	0.3	0.3	0.3	0.3	0.3	0.3	0.3	NR
2-Butanone	50	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	NR
2-Hexanone	50	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	NR
Acetone	50	1.3	1.3	1.3	1.3	1.3	1.3	1.3	1.3	NR
Benzene	1	0.3	0.4	0.3	0.3	0.3	0.3	0.3	0.3	NR
Bromodichloromethane	5	0.3	0.3	0.3	0.3	0.3	0.3	0.3	0.3	NR
Bromoform	5	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	NR
Bromomethane	5	0.3	0.3	0.3	0.3	0.3	0.3	0.3	0.3	NR
Carbon Disulfide	NA	0.3	0.4	0.3	0.3	0.3	0.3	0.3	0.3	NR
Carbon Tetrachloride	5	0.3	0.3	0.3	0.3	0.3	0.3	0.3	0.3	NR
Chlorobenzene	5	0.4	7.7	2.4	2.4	0.4	0.4	0.4	0.4	NR
Chlorodibromomethane	5	0.3	0.3	0.3	0.3	0.3	0.3	0.3	0.3	NR
Chloroethane	5	0.2	1.0	200	0.2	0.2	0.2	0.2	0.2	NR
Chloroform	7	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	NR
Chloromethane	5	0.3	0.3	0.3	0.3	0.3	0.3	0.3	0.3	NR
(1) cis-1,3-Dichloropropene	0.4	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	NR
Ethylbenzene	5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	NR
Methyl Isobutyl Ketone	NS	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	NR
Methylene Chloride	5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	NR
Styrene	5	0.4	0.4	0.4	0.4	0.4	0.4	0.4	0.4	NR
Tetrachloroethene	5	0.4	0.4	0.4	0.4	0.4	0.4	0.4	0.4	NR
Toluene	5	0.4	0.4	0.4	0.4	0.4	0.4	0.4	0.4	NR
trans-1,3-Dichloropropene	0.4	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	NR
Trichloroethene	5	0.4	0.4	0.4	0.4	0.4	0.4	0.4	0.4	NR
Vinyl Chloride	2	0.3	0.3	0.3	0.3	0.3	0.3	0.3	0.3	NR
Xylene (Total)	5	0.4	0.4	0.4	0.5	0.5	0.4	0.4	0.4	NR
Total Confident Conc. VOAs (s)	NE	0	9.5	203	0	0	0	0	0	NR
Total Estimated Conc. VOA TCs (s)	NE	56	0	7.9	0	0	0	0	0	NR
Dissolved Gases (ug/L)										0
Methane	NE	7800	11000	2600	NR	5.0	NR	NR	NR	5.0
Ethene	NE	500	500	250	NR	5.0	NR	NR	NR	5.0
Ethane	NE	500	500	250	NR	5.0	NR	NR	NR	5.0

TABLE 11
SUMMARY OF GROUNDWATER ANALYTICAL RESULTS
JUNE 2006 GROUNDWATER SAMPLING
FORMER COLUMBIA CEMENT COMPANY FACILITY
FREEPORT, NEW YORK

URS Sample ID	NYSDEC Sample ID	NYT 71-73	NYT 06-140	TB 06-0906	FB 060606	TB 060606	FB 060606 Diss	TB 060706
Laboratory Sample ID	1A61-406	1A61-406	74394	74394	74311	74313	74315	743173
Sampling Date	06/06/06	06/06/06	06/09/06	06/09/06	06/09/06	06/09/06	06/09/06	06/07/06
Dilution Factor	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0
Units	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L
Total Iron	NE	25900	21000	4480	NR	39.7	NR	39.7
Dissolved iron	NE	39.7	1490	2900	NR	39.7	NR	39.7
Miscellaneous (mg/l)								
Alkalinity - mg/l	NE	409	681	125	NR	5.0	NR	NR
Chloride - mg/l	NE	130	2780	18.6	NR	5.0	NR	NR
Sulfate - mg/l	NE	5.0	41.3	5.0	NR	5.0	NR	NR
Total Organic Carbon - mg/l	NE	8.8	8.7	2.6	NR	1.0	NR	NR

...GLE 11
SUMMARY OF GROUNDWATER ANALYTICAL RESULTS
JUNE, 2006 SAMPLING EVENT
FORMER COLUMBIA CEMENT COMPANY FACILITY
FREEPORT, NEW YORK

NOTES:

Box/Bold :Exceeds NYSDDEC GW Standard

D :Result is obtained from a diluted sample.

J :The result is a quantitatively estimated value.

U :Compound was not detected.

NE :Not Established

NT :Not Tested

ug/l :Micrograms Per Liter

mg/l :Milligrams Per Liter

(1) : Values listed reflect the combined standards for the cis and trans isomers of 1,3-Dichloropropene.

TABLE 12
SUMMARY OF SLUG TESTING RESULTS
FORMER COLUMBIA CEMENT COMPANY FACILITY
FREEPORT, NEW YORK

WELL	TEST	d (ft)	r_c (ft)	r_w (ft)	h_0 (ft)	HYDRAULIC CONDUCTIVITY		
						ft/d	cm/sec	Avg. (ft/d)
MW-97-1S	Falling Head	10	0.083	0.17	1.2	43.0	1.52E-02	
	Rising Head	10	0.083	0.17	1.1	46.5	1.64E-02	44.75
MW-98-9D	Falling Head	10	0.083	0.17	1.3	42.5	1.50E-02	
	Rising Head	10	0.083	0.17	1.2	43.0	1.52E-02	42.75
MW-05-14S	Falling Head	10	0.083	0.17	0.6	1.9	6.71E-04	
	Rising Head	10	0.083	0.17	0.75	2.5	8.83E-04	2.20
MW-97-6S	Falling Head #1	10	0.083	0.17	1.2	36.5	1.29E-02	
	Rising Head #1	10	0.083	0.17	0.8	32.0	1.13E-02	
	Falling Head #2	10	0.083	0.17	1.0	31.5	1.11E-02	
	Rising Head #2	10	0.083	0.17	1.0	38.5	1.36E-02	34.63

Notes

d : screen length

r_c : casing radius

r_w : borehole radius

h_0 : x-axis intercept

1.22E-02

SUMMARY OF 2005 SOIL VAPOR INTRUSION ANALYTICAL RESULTS
FORMER COLUMBIA CEMENT COMPANY FACILITY
FREEPORT, NEW YORK

TABLE 13

SAMPLING LOCATION: SAMPLING DATE: ACCUTEST SAMPLE ID	SG-05-01 09/21/05 J10451-6			SG-05-02 09/20/05 J10451-7			SG-05-03 09/21/05 J10451-3			SG-05-04 09/21/05 J10451-5			SG-05-05 09/21/05 J10451-2							
	CAS No.	GC/MS Volatiles	ug/m ³	ppbv	ug/m ³	ppbv	ug/m ³	ppbv	ug/m ³	ppbv	ug/m ³	ppbv	ug/m ³	ppbv	ug/m ³	ppbv				
67-64-1 Acetone	19	U	8	U	16	6.9	3.8	U	1.6	U	3.8	U	1.6	U	3.8	U	1.6	U		
106-99-0 1,3-Butadiene	18	U	8	U	3.5	U	1.6	U	3.5	U	1.6	U	3.5	U	1.6	U	1.6	U		
71-43-2 Benzene	61.3	19.2	14	4.3	99.4	31.1	237	74.2	57.8	57.8	11	U	11	U	11	U	1.6	U		
75-27-4 Bromodichloromethane	54	U	8	U	11	1.6	U	11	U	1.6	U	1.6	U	1.6	U	1.6	U	1.6	U	
75-25-2 Bromoform	83	U	8	U	17	1.6	U	17	U	1.6	U	17	U	1.6	U	17	U	1.6	U	
74-83-9 Bromomethane	31	U	8	U	6.2	1.6	U	6.2	U	1.6	U	6.2	U	1.6	U	6.2	U	1.6	U	
593-60-2 Bromoethene	35	U	8	U	7	1.6	U	7	U	1.6	U	7	U	1.6	U	7	U	1.6	U	
100-44-7 Benzyl Chloride	41	U	8	U	8.2	1.6	U	8.2	U	1.6	U	8.2	U	1.6	U	8.2	U	1.6	U	
75-15-0 Carbon disulfide	448	144	4	J	1.3	J	22	7.2	15	4.9	4.9	4.9	4.9	4.9	33	10.6	10.6	U		
108-90-7 Chlorobenzene	37	U	8	U	7.4	U	1.6	U	7.4	U	1.6	U	7.4	U	1.6	U	7.4	U	1.6	U
75-00-3 Chloroethane	747	283	164	62.3	12	4.7	1370	521	269	269	269	521	521	521	102	102	102	U	U	
67-66-3 Chloroform	39	U	8	U	7.8	U	1.6	U	7.8	U	1.6	U	7.8	U	1.6	U	7.8	U	1.6	U
74-87-3 Chloromethane	17	U	8	U	3.3	U	1.6	U	3.3	U	1.6	U	3.3	U	1.6	U	3.3	U	1.6	U
107-05-1 3-Chloropropene	25	U	8	U	5	U	1.6	U	5	U	1.6	U	5	U	1.6	U	5	U	1.6	U
95-49-8 2-Chlorotoluene	41	U	8	U	8.3	U	1.6	U	8.3	U	1.6	U	8.3	U	1.6	U	8.3	U	1.6	U
56-23-5 Carbon tetrachloride	50	U	8	U	10	U	1.6	U	10	U	1.6	U	10	U	1.6	U	10	U	1.6	U
110-82-7 Cyclohexane	9980	2900	5.5	U	9470	2340	308	89.5	413	413	120	120	120	120	66.8	66.8	66.8	19.4	19.4	
75-34-3 1,1-Dichloroethane	32	U	8	U	89.2	22.5	86.4	21.8	259	259	14000	14000	14000	14000	3470	3470	3470	420	420	
75-35-4 1,1-Dichloroethylene	32	U	8	U	12	U	1.6	U	12	U	1.6	U	12	U	1.6	U	12	U	1.6	U
106-93-4 1,2-Dibromoethane	61	U	8	U	6.5	U	1.6	U	6.5	U	1.6	U	6.5	U	1.6	U	6.5	U	1.6	U
107-06-2 1,2-Dichloroethane	32	U	8	U	7.4	U	1.6	U	5.1	J	1.1	J	7.4	U	1.6	U	7.4	U	1.6	U
78-87-5 1,2-Dichloropropane	37	U	8	U	5.8	U	1.6	U	5.8	U	1.6	U	5.8	U	1.6	U	5.8	U	1.6	U
123-91-1 1,4-Dioxane	29	U	8	U	18	3.7	U	11	2.3	2.3	9.4	9.4	9.4	9.4	1.9	1.9	1.9	4.8	4.8	
75-71-8 Dichlorodifluoromethane	40	U	8	U	14	U	1.6	U	14	U	1.6	U	14	U	1.6	U	14	U	1.6	U
124-48-1 Dibromochloromethane	68	U	8	U	6.3	U	1.6	U	46.8	11.8	29	7.3	7.3	7.3	11	11	11	2.7	2.7	
156-60-5 trans-1,2-Dichloroethylene	32	U	8	U	4.2	J	4.8	J	1.2	J	257	64.8	64.8	64.8	1320	1320	1320	226	226	
156-59-2 cis-1,2-Dichloroethylene	17	J	4.2	J	8	U	7.3	U	1.6	U	7.3	U	1.6	U	7.3	U	7.3	U	1.6	U
10061-01-1 cis-1,3-Dichloropropene	36	U	8	U	9.6	U	1.6	U	9.6	U	1.6	U	9.6	U	1.6	U	9.6	U	1.6	U
541-73-1 m-Dichlorobenzene	48	U	8	U	9.6	U	1.6	U	9.6	U	1.6	U	9.6	U	1.6	U	9.6	U	1.6	U
95-50-1 o-Dichlorobenzene	48	U	8	U	9.6	U	1.6	U	9.6	U	1.6	U	9.6	U	1.6	U	9.6	U	1.6	U
106-46-7 p-Dichlorobenzene	48	U	8	U	9.6	U	1.6	U	9.6	U	1.6	U	9.6	U	1.6	U	9.6	U	1.6	U
10061-02-1 trans-1,3-Dichloropropene	36	U	8	U	7.3	U	1.6	U	7.3	U	1.6	U	7.3	U	1.6	U	7.3	U	1.6	U
64-17-5 Ethanol	38	U	20	U	7.5	U	4	U	7.5	U	4	U	7.5	U	4	U	7.5	U	3.2	J

TABLE 13
SUMMARY OF 2005 SOIL VAPOR INTRUSION ANALYTICAL RESULTS
FORMER COLUMBIA CEMENT COMPANY FACILITY
FREEPORT, NEW YORK

SAMPLING LOCATION: SAMPLING DATE: ACCUTEST SAMPLE ID	SG-05-01 09/21/05 J10451-6			SG-05-02 09/20/05 J10451-7			SG-05-03 09/21/05 J10451-3			SG-05-04 09/21/05 J10451-5			SG-05-05 09/21/05 J10451-2		
	ug/m ³	ppbv	ug/m ³	ppbv	ug/m ³	ppbv	ug/m ³	ppbv	ug/m ³	ppbv	ug/m ³	ppbv	ug/m ³	ppbv	
100-41-4 Ethylbenzene	35 U	8 U	4.8 J	1.1 J	4.3 J	1 J	3.5 J	J	6.5 J	J	1.5 J	J	1.6 U	1.6 U	
141-78-6 Ethyl Acetate	29 U	8 U	5.8 U	1.6 U	5.8 U	1.6 U	5.8 U	1.6 U	5.8 U	1.6 U	5.8 U	1.6 U	5.8 U	1.6 U	
622-96-8 4-Ethyltoluene	39 U	8 U	7.9 U	1.6 U	7.9 U	1.6 U	7.9 U	1.6 U	7.9 U	1.6 U	7.9 U	1.6 U	7.9 U	1.6 U	
76-13-1 Freon 113	61 U	8 U	12 U	1.6 U	12 U	1.6 U	12 U	1.6 U	12 U	1.6 U	12 U	1.6 U	12 U	1.6 U	
76-14-2 Freon 114	56 U	8 U	6.2 J	0.88 J	16 J	2.3 J	11 U	1.6 U	16 U	1.6 U	16 U	1.6 U	16 U	2.3 U	
142-82-5 Heptane	349 U	85.2 U	4.5 J	1.1 J	88.9 U	21.7 J	77 U	18.8 U	9.8 U	9.8 U	2.4 U	2.4 U	2.4 U	2.4 U	
87-68-3 Hexachlorobutadiene	85 U	8 U	17 U	1.6 U	17 U	1.6 U	17 U	1.6 U	17 U	1.6 U	17 U	1.6 U	17 U	1.6 U	
110-54-3 Hexane	12200 U	3460 U	102 U	28.9 U	708 U	201 U	1740 U	494 U	59.6 U	59.6 U	16.9 U	16.9 U	16.9 U	16.9 U	
591-78-6 2-Hexanone	33 U	8 U	6.5 U	1.6 U	6.5 U	1.6 U	6.5 U	1.6 U	6.5 U	1.6 U	6.5 U	1.6 U	6.5 U	1.6 U	
67-63-0 Isopropyl Alcohol	20 U	8 U	3.9 U	1.6 U	3.9 U	1.6 U	3.9 U	1.6 U	3.9 U	1.6 U	3.9 U	1.6 U	3.9 U	1.6 U	
75-09-2 Methylene Chloride	28 U	8 U	2.7 U	0.78 U	2.8 U	0.82 U	59.1 U	17 U	15 U	15 U	15 U	15 U	15 U	15 U	
78-93-3 Methyl ethyl ketone	24 U	8 U	4.7 U	1.6 U	4.7 U	1.6 U	4.7 U	1.6 U	4.7 U	1.6 U	4.7 U	1.6 U	4.7 U	1.6 U	
108-10-1 Methyl Isobutyl Ketone	33 U	8 U	6.6 U	1.6 U	6.6 U	1.6 U	6.6 U	1.6 U	6.6 U	1.6 U	6.6 U	1.6 U	6.6 U	1.6 U	
1634-04-4 Methyl Tert Butyl Ether	29 U	8 U	5.8 U	1.6 U	5.8 U	1.6 U	5.8 U	1.6 U	5.8 U	1.6 U	5.8 U	1.6 U	5.8 U	1.6 U	
115-07-1 Propylene	34 U	20 U	6.9 U	4 U	6.9 U	4 U	6.9 U	4 U	534 U	311 U	199 U	199 U	199 U	199 U	
100-42-5 Styrene	34 U	8 U	6.8 U	1.6 U	6.8 U	1.6 U	6.8 U	1.6 U	6.8 U	1.6 U	6.8 U	1.6 U	6.8 U	1.6 U	
71-55-6 1,1,1-Trichloroethane	44 U	8 U	1840 U	337 U	33 U	6 U	5190 U	952 U	952 U	952 U	253 U	253 U	253 U	253 U	
79-34-5 1,1,2,2-Tetrachloroethane	55 U	8 U	11 U	1.6 U	11 U	1.6 U	11 U	1.6 U	11 U	1.6 U	11 U	1.6 U	11 U	1.6 U	
79-00-5 1,1,2-Trichloroethane	44 U	8 U	8.7 U	1.6 U	8.7 U	1.6 U	8.7 U	1.6 U	8.7 U	1.6 U	8.7 U	1.6 U	8.7 U	1.6 U	
120-82-1 1,2,4-Trichlorobenzene	59 U	8 U	12 U	1.6 U	12 U	1.6 U	12 U	1.6 U	12 U	1.6 U	12 U	1.6 U	12 U	1.6 U	
95-63-6 1,2,4-Trimethylbenzene	39 U	8 U	9.8 U	2 U	7.9 U	1.6 U	7.9 U	1.6 U	7.9 U	1.6 U	7.9 U	1.6 U	7.9 U	1.6 U	
108-67-8 1,3,5-Trimethylbenzene	39 U	8 U	7.9 U	1.6 U	7.9 U	1.6 U	7.9 U	1.6 U	7.9 U	1.6 U	7.9 U	1.6 U	7.9 U	1.6 U	
540-84-1 2,2,4-Trimethylpentane	413 U	542 U	116 U	305 U	65.3 U	169 U	36.2 U	481 U	481 U	481 U	103 U	103 U	103 U	103 U	
75-65-0 Tertiary Butyl Alcohol	24 U	8 U	4.9 U	1.6 U	4.9 U	1.6 U	4.9 U	1.6 U	4.9 U	1.6 U	4.9 U	1.6 U	4.9 U	1.6 U	
127-18-4 Tetrachloroethylene	54 U	8 U	400 U	59 U	96.3 U	14.2 U	1030 U	152 U	152 U	152 U	209 U	209 U	209 U	209 U	
109-99-9 Tetrahydrofuran	24 U	8 U	4.7 U	1.6 U	4.7 U	1.6 U	4.7 U	1.6 U	4.7 U	1.6 U	4.7 U	1.6 U	4.7 U	1.6 U	
108-88-3 Toluene	26 U	7 U	4.5 J	1.2 J	11 U	3 U	14 U	3.6 U	3.6 U	3.6 U	17 U	17 U	17 U	17 U	
79-01-6 Trichloroethylene	43 U	8 U	76.3 U	14.2 U	116 U	21.5 U	335 U	62.3 U	62.3 U	62.3 U	188 U	188 U	188 U	188 U	
75-69-4 Trichlorofluoromethane	45 U	8 U	9 U	1.6 U	9 U	1.6 U	529 U	207 U	598 U	234 U	234 U	234 U	234 U	234 U	
75-01-4 Vinyl chloride	53.2 U	20.8 U	4.1 U	1.6 U	5.6 U	1.6 U	5.6 U	1.6 U	5.6 U	1.6 U	5.6 U	1.6 U	5.6 U	1.6 U	
108-05-4 Vinyl Acetate	28 U	8 U	5.6 U	1.6 U	5.6 U	1.6 U	5.6 U	1.6 U	5.6 U	1.6 U	5.6 U	1.6 U	5.6 U	1.6 U	
m,p-Xylene	45.6 U	10.5 U	14 U	3.3 U	7.8 U	1.8 U	8.3 U	1.9 U	1.9 U	1.9 U	1.9 U	1.9 U	1.9 U	1.9 U	
95-47-6 o-Xylene	35 U	8 U	5.6 U	1.3 U	6.9 U	1.6 U	6.9 U	1.6 U	6.9 U	1.6 U	6.9 U	1.6 U	6.9 U	1.6 U	
1330-20-7 Xylenes (total)	45.6 U	10.5 U	20 U	4.6 U	7.8 U	1.8 U	11 U	2.6 U	2.6 U	2.6 U	13 U	13 U	13 U	13 U	

TABLE 13
SUMMARY OF 2005 SOIL VAPOR INTRUSION ANALYTICAL RESULTS
FORMER COLUMBIA CEMENT COMPANY FACILITY
FREREPORT, NEW YORK

SAMPLING LOCATION: SAMPLING DATE: ACCUTEST SAMPLE ID	SG-05-06 09/21/05 J10451-13			SG-05-07 09/21/05 J10451-1			SG-05-08 09/20/05 J10451-9			SG-05-09 09/20/05 J10451-10			SG-05-10 09/20/05 J10451-12						
	ug/m ³	ppbv	ug/m ³	ppbv	ug/m ³	ppbv	ug/m ³	ppbv	ug/m ³	ppbv	ug/m ³	ppbv	ug/m ³	ppbv					
CAS No. GC/MS Volatiles																			
67-64-1 Acetone	69.6	29.3	3.8	U	1.6	U	128	54	3.8	U	1.6	U	3.8	U					
106-99-0 1,3-Butadiene	3.5	U	1.6	U	3.5	U	3.5	U	3.5	U	1.6	U	3.5	U					
71-43-2 Benzene	46	14.4	27	8.3	70	21.9	5.1	U	1.6	U	1.6	U	15	4.6					
75-27-4 Bromodichloromethane	11	U	1.6	U	11	U	1.6	U	11	U	1.6	U	11	U					
75-25-2 Bromofrom	17	U	1.6	U	17	U	1.6	U	17	U	1.6	U	17	U					
74-83-9 Bromomethane	6.2	U	1.6	U	6.2	U	1.6	U	6.2	U	1.6	U	6.2	U					
593-60-2 Bromoethene	7	U	1.6	U	7	U	1.6	U	7	U	1.6	U	7	U					
100-44-7 Benzyl Chloride	8.2	U	1.6	U	8.2	U	1.6	U	8.2	U	1.6	U	8.2	U					
75-15-0 Carbon disulfide	28	9	154	49.6	333	107	11	3.5	U	74.4	U	23.9	U	23.9	U				
108-90-7 Chlorobenzene	7.4	U	1.6	U	89.3	19.4	41	8.8	7.4	U	1.6	U	7.4	U	1.6	U			
75-00-3 Chloroethane	1100	416	83.4	31.6	22	8.4	4.2	U	1.6	U	1.6	U	792	U	300	U			
67-66-3 Chloroform	7.8	U	1.6	U	7.8	U	1.6	U	7.8	U	1.6	U	7.8	U	1.6	U			
74-87-3 Chloromethane	3.3	U	1.6	U	3.3	U	1.6	U	3.3	U	1.6	U	3.3	U	1.6	U			
107-05-1 3-Chloropropene	5	U	1.6	U	5	U	1.6	U	5	U	1.6	U	5	U	1.6	U			
95-49-8 2-Chrototoluene	8.3	U	1.6	U	8.3	U	1.6	U	8.3	U	1.6	U	8.3	U	1.6	U			
56-23-5 Carbon tetrachloride	10	U	1.6	U	10	U	1.6	U	10	U	1.6	U	10	U	1.6	U			
110-82-7 Cyclohexane	189	54.8	403	117	28	8.2	5.5	U	1.6	U	1.6	U	5.5	U	1.6	U			
75-34-3 1,1-Dichloroethane	210	52	16	4	36	9	210	51.9	U	935	U	231	U	56.3	U	14.2	U		
75-35-4 1,1-Dichloroethylene	19	4.8	6.3	U	1.6	U	6.3	U	1.6	U	1.6	U	1.6	U	1.6	U	1.6	U	
106-93-4 1,2-Dibromoethane	12	U	1.6	U	12	U	1.6	U	12	U	1.6	U	12	U	1.6	U	1.6	U	
107-06-2 1,2-Dichloroethane	6.5	U	1.6	U	6.5	U	1.6	U	6.5	U	1.6	U	6.5	U	1.6	U	1.6	U	
78-87-5 1,2-Dichloropropane	7.4	U	1.6	U	7.4	U	1.6	U	7.4	U	1.6	U	7.4	U	1.6	U	1.6	U	
123-91-1 1,4-Dioxane	5.8	U	1.6	U	5.8	U	1.6	U	5.8	U	1.6	U	5.8	U	1.6	U	1.6	U	
75-71-8 Dichlorodifluoromethane	4.4	J	0.88	J	5.9	J	1.2	J	5.4	J	1.1	J	7.9	J	1.6	J	108	J	
124-48-1 Dibromochloromethane	14	U	1.6	U	14	U	1.6	U	14	U	1.6	U	14	U	1.6	U	14	U	
156-80-5 trans-1,2-Dichloroethylbenzene	14	3.6	6.3	U	1.6	U	6.3	U	1.6	U	6.3	U	6.3	U	6.3	U	6.3	U	
156-59-2 cis-1,2-Dichloroethylene	93.6	23.6	15	3.9	30	7.5	6.3	U	1.6	U	1.6	U	1.6	U	1.6	U	1.6	U	
10061-01-cis-1,3-Dichloropropene	7.3	U	1.6	U	7.3	U	1.6	U	7.3	U	1.6	U	9.6	U	1.6	U	9.6	U	
541-73-1 m-Dichlorobenzene	9.6	U	1.6	U	9.6	U	1.6	U	9.6	U	1.6	U	9.6	U	1.6	U	9.6	U	
95-50-1 o-Dichlorobenzene	9.6	U	1.6	U	9.6	U	1.6	U	9.6	U	1.6	U	9.6	U	1.6	U	9.6	U	
106-46-7 p-Dichlorobenzene	9.6	U	1.6	U	9.6	U	1.6	U	9.6	U	1.6	U	9.6	U	1.6	U	9.6	U	
10061-02-trans-1,3-Dichloropropene	7.3	U	1.6	U	7.3	U	1.6	U	7.3	U	1.6	U	7.3	U	1.6	U	7.3	U	
64-17-5 Ethanol	6	U	7.5	U	4	U	31	16.5	U	11	U	6	U	7.5	U	4	U	7.5	U

TABLE 13
SUMMARY OF 2005 SOIL VAPOR INTRUSION ANALYTICAL RESULTS
FORMER COLUMBIA CEMENT COMPANY FACILITY
FREEPORT, NEW YORK

SAMPLING LOCATION: SAMPLING DATE: ACCUTEST SAMPLE ID	SG-05-06 09/21/05 J10451-13			SG-05-07 09/21/05 J10451-1			SG-05-08 09/20/05 J10451-9			SG-05-09 09/20/05 J10451-10			SG-05-10 09/20/05 J10451-12			
	ug/m ³	ppbv	ug/m ³	ppbv	ug/m ³	ppbv	ug/m ³	ppbv	ug/m ³	ppbv	ug/m ³	ppbv	ug/m ³	ppbv		
100-41-4 Ethylbenzene	17	3.9	3.8	J	0.88	J	6.1	J	1.4	J	6.9	U	1.6	U	1.6	U
141-78-6 Ethyl Acetate	5.8	U	1.6	U	5.8	U	1.6	U	5.8	U	1.6	U	5.8	U	1.6	U
622-96-8 4-Ethyltoluene	7.9	U	1.6	U	7.9	U	1.6	U	7.9	U	1.6	U	7.9	U	1.6	U
76-13-1 Freon 113	12	U	1.6	U	12	U	1.6	U	12	U	1.6	U	12	U	1.6	U
76-14-2 Freon 114	10	J	1.5	J	11	U	1.6	U	9.1	J	1.3	J	11	U	1.6	U
142-82-5 Heptane	37	9	349		85.1		205		50.1		6.6	U	1.6	U	60.2	14.7
87-68-3 Hexachlorobutadiene	17	U	1.6	U	17	U	1.6	U	17	U	1.6	U	17	U	1.6	U
110-54-3 Hexane	258	73.3	990		281		145		41.2		11		3.1		807	229
591-78-6 2-Hexanone	6.5	U	1.6	U	6.5	U	1.6	U	6.5	U	1.6	U	6.5	U	1.6	U
67-63-0 Isopropyl Alcohol	3.9	U	1.6	U	3.9	U	1.6	U	3.9	U	1.6	U	3.9	U	1.6	U
75-09-2 Methylene chloride	20	5.7	2.9	J	0.83	J	5.6	U	1.6	U	5.6	U	1.6	U	5.6	U
78-93-3 Methyl ethyl ketone	4.7	U	1.6	U	4.7	U	1.6	U	4.7	U	1.6	U	4.7	U	1.6	U
108-10-1 Methyl Isobutyl Ketone	6.6	U	1.6	U	6.6	U	1.6	U	6.6	U	1.6	U	6.6	U	1.6	U
1634-04-4 Methyl Tert Butyl Ether	5.8	U	1.6	U	5.8	U	1.6	U	5.8	U	1.6	U	5.8	U	1.6	U
115-07-1 Propylene	6.9	U	4	U	6.9	U	4	U	6.9	U	4	U	47.6		27.7	6.9
100-42-5 Styrene	6.8	U	1.6	U	6.8	U	1.6	U	6.8	U	1.6	U	6.8	U	1.6	U
71-55-6 1,1,1-Trichloroethane	66.6	12.2	8.7	U	1.6	U	8.7	U	1.6	U	182		33.4		32	5.8
79-34-5 1,1,2,2-Tetrachloroethane	11	U	1.6	U	11	U	1.6	U	11	U	1.6	U	11	U	1.6	U
79-00-5 1,1,2,2-Trichloroethane	8.7	U	1.6	U	8.7	U	1.6	U	8.7	U	1.6	U	8.7	U	1.6	U
120-82-1 1,2,4-Trichlorobenzene	12	U	1.6	U	12	U	1.6	U	12	U	1.6	U	12	U	1.6	U
95-63-6 1,2,4-Trimethylbenzene	7.9	U	1.6	U	7.9	U	1.6	U	7.9	U	1.6	U	7.9	U	1.6	U
108-67-8 1,3,5-Trimethylbenzene	7.9	U	1.6	U	7.9	U	1.6	U	7.9	U	1.6	U	7.9	U	1.6	U
540-84-1 2,2,4-Trimethylpentane	476	102	115		24.7		338		72.4		159		34.1		1560	335
75-65-0 Tertiary Butyl Alcohol	4.9	U	1.6	U	4.9	U	1.6	U	4.9	U	1.6	U	4.9	U	1.6	U
127-18-4 Tetrachloroethylene	140	20.7	11	U	1.6	U	4.7	U	1.6	U	4.7	U	1.6	U	4.7	U
109-99-9 Tetrahydrofuran	4.7	U	1.6	U	4.7	U	1.6	U	4.7	U	1.6	U	4.7	U	1.6	U
108-88-3 Toluene	9.8	2.6	21		5.6		12		3.3		3.4	J	0.9		9.8	2.6
79-01-6 Trichloroethylene	67.7	12.6	8.6	U	1.6	U	8.6	U	1.6	U	4.9	J	0.91	J	8.6	1.6
75-69-4 Trichlorofluoromethane	9	U	1.6	U	9	U	1.6	U	9	U	1.6	U	9	U	1.6	U
75-01-4 Vinyl chloride	119	46.6	45.5		17.8		15		5.8		4.1	U	1.6	U	21	8.4
108-05-4 Vinyl Acetate	5.6	U	1.6	U	5.6	U	1.6	U	5.6	U	1.6	U	5.6	U	1.6	U
m,p-Xylene	43.9	10.1	11		2.6		13		2.9		6.5	J	1.5	J	8.3	1.9
95-47-6 o-Xylene	41	9.4	6.9	U	1.6	U	12		2.8		6.9	U	1.6	U	6.9	U
1330-20-7 Xylenes (total)	84.7	19.5	11		2.6		25		5.7		6.5	J	1.5	J	8.3	1.9

JLE 13
SUMMARY OF 2005 SOIL VAPOR INTRUSION ANALYTICAL RESULTS
FORMER COLUMBIA CEMENT COMPANY FACILITY
FREREPORT, NEW YORK

CAS No.	GC/MS Volatiles	SAMPLING LOCATION: 09/21/05 J10451-4		SG-05-AMB-E 09/20/05 J10451-11		SG-05-AMB-W 09/20/05 J10451-8	
		ug/m ³	ppbv	ug/m ³	ppbv	ug/m ³	ppbv
67-64-1	Acetone	27.6	11.6	12	5	5	2.1
106-99-0	1,3-Butadiene	3.5	U	1.6	U	0.44	U
71-43-2	Benzene	33.2	10.4	15	4.8	0.35	J
75-27-4	Bromodichloromethane	11	U	1.6	U	0.2	U
75-25-2	Bromoform	17	U	1.6	U	2.1	U
74-83-9	Bromomethane	6.2	U	1.6	U	0.78	U
593-60-2	Bromoethene	7	U	1.6	U	0.87	U
100-44-7	Benzyl Chloride	8.2	U	1.6	U	0.2	U
75-15-0	Carbon disulfide	26	8.3	0.62	U	0.62	U
103-90-7	Chlorobenzene	7.4	U	1.6	U	0.92	U
75-00-3	Chloroethane	5040	1910	0.53	U	0.2	U
67-66-3	Chloroform	7.8	U	1.6	U	0.98	U
74-87-3	Chloromethane	3.3	U	1.6	U	0.34	U
107-05-1	3-Chloropropene	5	U	1.6	U	0.63	U
95-49-8	2-Chlorotoluene	8.3	U	1.6	U	1	U
56-23-5	Carbon tetrachloride	10	U	1.6	U	0.2	U
110-82-7	Cyclohexane	132	38.4	0.69	U	0.69	U
75-34-3	1,1-Dichloroethane	2970	733	0.81	U	0.2	U
75-35-4	1,1-Dichloroethylene	76.5	19.3	0.79	U	0.2	U
106-93-4	1,2-Dibromoethane	12	U	1.6	U	1.5	U
107-06-2	1,2-Dichloroethane	6.5	U	1.6	U	0.81	U
78-87-5	1,2-Dichloropropane	7.4	U	1.6	U	0.92	U
123-91-1	1,4-Dioxane	5.8	U	1.6	U	0.72	U
75-71-8	Dichlorodifluoromethane	7.9	U	1.6	U	2.1	U
124-48-1	Dibromochloromethane	14	U	1.6	U	0.2	U
156-60-5	trans-1,2-Dichloroethylene	3.6	J	0.9	J	0.43	2
156-59-2	cis-1,2-Dichloroethylene	13	U	3.2	U	0.79	U
10061-01-cis-1,3-Dichloropropene	7.3	U	1.6	U	0.91	U	0.2
541-73-1	m-Dichlorobenzene	9.6	U	1.6	U	1.2	U
95-50-1	o-Dichlorobenzene	9.6	U	1.6	U	0.2	U
106-46-7	p-Dichlorobenzene	10	U	1.7	U	0.2	U
10061-02-trans-1,3-Dichloropropene	7.3	U	1.6	U	0.91	U	0.2
64-17-5	Ethanol	24.6	13.1	12	6.4	1.7	0.9

**SUMMARY OF 2005 SOIL VAPOR INTRUSION ANALYTICAL RESULTS
FORMER COLUMBIA CEMENT COMPANY FACILITY
FREEPORT, NEW YORK**

SAMPLING LOCATION: SAMPLING DATE: ACCUTEST SAMPLE ID	SG-05-11 09/21/05 J10451-4			SG-05-AMB-E 09/20/05 J10451-11			SG-05-AMB-W 09/20/05 J10451-8		
	ug/m ³	ppbv	ug/m ³	ppbv	ug/m ³	ppbv	ug/m ³	ppbv	ug/m ³
100-41-4 Ethylbenzene	6.9 U	1.6 U	0.87 U	0.2 U	0.87 U	0.2 U	0.87 U	0.2 U	0.2 U
141-78-6 Ethyl Acetate	5.8 U	1.6 U	27 U	7.4 U	4 U	1.1 U	1.1 U	1.1 U	1.1 U
622-96-8 4-Ethyltoluene	7.9 U	1.6 U	0.98 U	0.2 U	0.98 U	0.2 U	0.98 U	0.2 U	0.2 U
76-13-1 Freon 113	202	26.3	1.3 J	0.17 J	1.3 J	0.17 J	1.3 J	0.17 J	0.17 J
76-14-2 Freon 114	11 U	1.6 U	1.4 U	0.2 U	1.4 U	0.2 U	1.4 U	0.2 U	0.2 U
142-82-5 Heptane	4.1 J	1 J	0.45 J	0.11 J	0.82 U	0.2 U	0.82 U	0.2 U	0.2 U
87-68-3 Hexachlorobutadiene	17 U	1.6 U	2.1 U	0.2 U	2.1 U	0.2 U	2.1 U	0.2 U	0.2 U
110-54-3 Hexane	276	78.2	0.7 U	0.2 U	0.39 J	0.11 J	0.39 J	0.11 J	0.11 J
591-78-6 2-Hexanone	6.5 U	1.6 U	0.82 U	0.2 U	0.82 U	0.2 U	0.82 U	0.2 U	0.2 U
67-63-0 Isopropyl Alcohol	3.9 U	1.6 U	0.49 U	0.2 U	0.49 U	0.2 U	0.49 U	0.2 U	0.2 U
75-09-2 Methylene chloride	128	36.8	0.63 J	0.18 J	1 U	0.29 U	1 U	0.29 U	0.29 U
78-93-3 Methyl ethyl ketone	4.7 U	1.6 U	0.59 U	0.2 U	0.59 U	0.2 U	0.59 U	0.2 U	0.2 U
108-10-1 Methyl Isobutyl Ketone	24	5.9	0.82 U	0.2 U	0.82 U	0.2 U	0.82 U	0.2 U	0.2 U
1634-04-4 Methyl Tert Butyl Ether	5.8 U	1.6 U	0.72 U	0.2 U	0.72 U	0.2 U	0.72 U	0.2 U	0.2 U
115-07-1 Propylene	6.9 U	4 U	0.86 U	0.5 U	0.86 U	0.5 U	0.86 U	0.5 U	0.5 U
100-42-5 Styrene	6.8 U	1.6 U	0.4 J	0.094 J	0.85 U	0.2 U	0.85 U	0.2 U	0.2 U
71-55-6 1,1,1-Trichloroethane	21100	3870	1.1 U	0.2 U	1.1 U	0.2 U	1.1 U	0.2 U	0.2 U
79-34-5 1,1,2,2-Tetrachloroethane	11 U	1.6 U	1.4 U	0.2 U	1.4 U	0.2 U	1.4 U	0.2 U	0.2 U
79-00-5 1,1,2-Trichloroethane	8.7	1.6 U	1.1 U	0.2 U	1.1 U	0.2 U	1.1 U	0.2 U	0.2 U
120-82-1 1,2,4-Trichlorobenzene	12 U	1.6 U	1.5 U	0.2 U	1.5 U	0.2 U	1.5 U	0.2 U	0.2 U
95-63-6 1,2,4-Trimethylbenzene	7.9 U	1.6 U	0.98 U	0.2 U	0.98 U	0.2 U	0.98 U	0.2 U	0.2 U
108-67-8 1,3,5-Trimethylbenzene	7.9 U	1.6 U	0.98 U	0.2 U	0.98 U	0.2 U	0.98 U	0.2 U	0.2 U
540-84-1 2,2,4-Trimethylpentane	193	41.4	0.93 U	0.2 U	0.93 U	0.2 U	0.93 U	0.2 U	0.2 U
75-65-0 Tertiary Butyl Alcohol	4.9 U	1.6 U	0.61 U	0.2 U	0.61 U	0.2 U	0.61 U	0.2 U	0.2 U
127-18-4 Tetrachloroethylene	1480	218	1.4 U	0.2 U	1.4 U	0.2 U	1.4 U	0.2 U	0.2 U
109-99-9 Tetrahydrofuran	4.7 U	1.6 U	0.59 U	0.2 U	0.59 U	0.2 U	0.59 U	0.2 U	0.2 U
108-88-3 Toluene	9	2.4	1.9	0.5 U	0.79	0.21	0.79	0.21	0.21
79-01-6 Trichloroethylene	152	28.2	1.1 U	0.2 U	1.1 U	0.2 U	1.1 U	0.2 U	0.2 U
75-69-4 Trichlorofluoromethane	9 U	1.6 U	1.1 J	0.19 J	1.1 J	0.19 J	1.1 J	0.19 J	0.19 J
75-01-4 Vinyl chloride	59.6	23.3	0.51 U	0.2 U	0.51 U	0.2 U	0.51 U	0.2 U	0.2 U
108-05-4 Vinyl Acetate	5.6 U	1.6 U	0.7 U	0.2 U	0.7 U	0.2 U	0.7 U	0.2 U	0.2 U
m,p-Xylene	7.4	1.7	0.87 U	0.2 U	0.87 U	0.2 U	0.87 U	0.2 U	0.2 U
95-47-6 o-Xylene	6.9 U	1.6 U	0.87 U	0.2 U	0.87 U	0.2 U	0.87 U	0.2 U	0.2 U
1330-20-7 Xylenes (total)	7.4	1.7	0.43 J	0.1 J	0.4 J	0.1 J	0.4 J	0.093 J	0.093 J

...BLE 13
SUMMARY OF 2005 SOIL VAPOR INTRUSION ANALYTICAL RESULTS
FORMER COLUMBIA CEMENT COMPANY FACILITY
FREEPORT, NEW YORK

NOTES:

U : Compound not detected at stated detection limit

J : The result is a quantitatively estimated value.

$\mu\text{g}/\text{m}^3$: Micrograms per cubic meter

ppbv : Parts per million by volume

TABLE 14

SUMMARY OF 206 SOIL VAPOR INTRUSION ANALYTICAL RESULTS
FORMER COLUMBIA CEMENT COMPANY FACILITY
FREEPORT, NEW YORK

SAMPLE TYPE SAMPLE LOCATION	AMBIENT AIR AA-06-01 08/16/06	COLUMBIA CEMENT BLDG.				INDOOR AIR				
		IA-06-01 08/16/06	J38685-8	IA-06-02 08/16/06	J38685-11	IA-06-03 08/16/06	J38685-14	KNICKERBOCKER		
ACCUTEST SAMPLE ID	J38685-10	µg/m ³	ppbv	µg/m ³	ppbv	µg/m ³	ppbv	µg/m ³	ppbv	
GC/MS Volatiles										
Acetone	1.3	0.53	12	5	1.6	1.2	0.38	7.7	20	
Benzene	0.64	U	0.20	5.1	U	0.92	U	0.38	J	
Chlorobenzene	0.92	U	0.20	7.4	U	0.53	U	0.92	U	
Chloroethane	0.53	U	0.20	4.2	U	0.81	U	0.2	U	
1,1-Dichloroethane	0.81	U	0.20	6.5	U	1.6	U	0.53	U	
1,1-Dichloroethene	0.79	U	0.20	6.3	U	1.6	U	0.81	U	
1,2-Dichloroethane	0.81	U	0.20	6.5	U	1.6	U	0.79	U	
trans-1,2-Dichloroethene	0.79	U	0.20	6.3	U	1.6	U	0.2	U	
cis-1,2-Dichloroethene	1.4	0.35	6.3	U	1.6	U	0.79	U	0.2	U
Ethylbenzene	0.87	U	0.20	6.9	U	1.6	U	0.36	U	
Freon 113	1.5	U	0.20	12	U	1.6	U	0.2	U	
Freon 114	1.4	U	0.20	11	U	1.6	U	0.2	U	
Heptane	0.82	U	0.20	3	J	0.73	J	0.54	U	
Hexane	0.70	U	0.20	6.7	U	1.9	U	1.1	U	
Methylene chloride	0.94	0.27	5.6	U	1.6	U	1	0.3	0.9	
Methyl cyclohexane	ND	ND	ND	ND	ND	ND	ND	ND	ND	
Methyl ethyl ketone	0.59	U	0.20	4.7	U	1.6	U	0.78	5.9	
Pentane	0.59	U	0.20	4.4	J	1.5	J	1.2	2.3	
1,1,1-Trichloroethane	1.1	U	0.20	8.7	U	1.6	U	0.17	J	
Tetrachloroethene	1.4	U	0.20	11	U	1.6	U	1.1	J	
Toluene	0.75	U	0.20	18	U	4.9	U	2.3	U	
Trichloroethene	31	5.8	8.6	U	1.6	U	1.1	U	1.1	
Vinyl chloride	0.51	U	0.20	4.1	U	1.6	U	0.2	U	
m,p-Xylene	0.87	U	0.20	12	U	2.8	U	1.3	U	
o-Xylene	0.87	U	0.20	4.2	J	0.97	J	0.47	U	
Xylenes (total)	0.87	U	0.20	17	U	3.8	U	1.7	U	
Total TIC, Volatile	0	0	0	0	0	0	0	3.1	J	

TABLE 14
SUMMARY OF 2006 SOIL VAPOR INTRUSION ANALYTICAL RESULTS
FORMER COLUMBIA CEMENT COMPANY FACILITY
FREEPORT, NEW YORK

SAMPLE TYPE SAMPLE LOCATION	COLUMBIA CEMENT BLDG.				SUB-SLAB SAMPLES				KNICKERBOCKER SS-06-04 08/16/06 J38685-12	
	SAMPLE ID ACCUTEST SAMPLE ID	SS-06-01 08/16/06	SS-06-02 08/16/06	SS-06-03 08/16/06	J38685-9	J38685-7	ppbv	µg/m³	ppbv	µg/m³
GC/MS Volatiles	µg/m³	ppbv	µg/m³	ppbv	µg/m³	ppbv	µg/m³	ppbv	µg/m³	ppbv
Acetone	129	54.4	278	117	87.9	37.0	42.0	17.7		
Benzene	3.1 J	0.97 J	27 J	8.5 J	2.6 J	0.82 J	6.7	2.1		
Chlorobenzene	7.4 U	1.6 U	46 U	10 U	7.4 U	1.6 U	7.4	1.6	U	
Chloroethane	4.2 U	1.6 U	10500	3990	4.2 U	1.6 U	4.2	1.6	U	
1,1-Dichloroethane	47.4	11.7	30600	7550	8.9	2.2	10	2.5		
1,1-Dichloroethene	6.3 U	1.6 U	308	77.7	6.3 U	1.6 U	6.3	1.6	U	
1,2-Dichloroethane	6.5 U	1.6 U	40 U	10 U	6.5 U	1.6 U	6.5	1.6	U	
trans-1,2-Dichloroethene	6.3 U	1.6 U	40 U	10 U	6.3 U	1.6 U	6.3	1.6	U	
cis-1,2-Dichloroethene	6.7	1.7	21 J	5.2 J	6.3 U	1.6 U	6.3	1.6	U	
Ethylbenzene	6.5 J	1.5 J	55.6	12.8	6.1 J	1.4 J	26	5.9		
Freon 113	12 U	1.6 U	77 U	10 U	12 U	1.6 U	15	1.9		
Freon 114	11 U	1.6 U	101	14.5	11 U	1.6 U	17	2.4		
Heptane	6.6 U	1.6 U	41 U	10 U	6.6 U	1.6 U	6.6	1.6	U	
Hexane	5.6 U	1.6 U	86.7	24.6	3.1 J	0.89 J	6.7	1.9		
Methylene chloride	5.6 U	1.6 U	251	72.3	5.6 U	1.6 U	32	9.1		
Methyl cyclohexane	ND	ND	ND	ND	ND	ND	ND	ND		
Methyl ethyl ketone	63.4	21.5	109	36.9	40.4	13.7	3.8	1.3	J	
Pentane	4.7 U	1.6 U	72.7	24.7	4.7 U	1.6 U	3.8	1.3	J	
1,1,1-Trichloroethane	189	34.6	86200	15800	14	2.6	27	4.9		
Tetrachloroethene	195	28.7	2140	316	43	6.3	121	17.9		
Toluene	18	4.7	55.4	14.7	23	6.1	82.5	21.9		
Trichloroethene	57.5	10.7	534	99.3	5.9 J	1.1 J	7.0	1.3	J	
Vinyl chloride	4.1 U	1.6 U	16 J	6.2 J	4.1 U	1.6 U	4.1	1.6	U	
m,p-Xylene	29	6.6	136	31.4	25	5.8	97.7	22.5		
o-Xylene	12	2.7	67.3	15.5	10	2.4	43	9.8		
Xylenes (total)	40	9.3	204	47.0	36	8.2	140	32.2		
Total TIC, Volatile		73.9 J		203 J	0	0	0	165.3 J		

**SUMMARY OF 2016 SOIL VAPOR INTRUSION ANALYTICAL RESULTS
FORMER COLUMBIA CEMENT COMPANY FACILITY
FREEPORT, NEW YORK**

SAMPLE TYPE SAMPLE LOCATION	SAMPLE ID SAMPLING DATE ACCUTEST SAMPLE ID	SOIL GAS SAMPLES						
		SPILL / UST AREA			08/15/06 J38685-4			
		SG-05-01 08/15/06 J38685-3	ppbv	µg/m³	ppbv	µg/m³	ppbv	
GC/MS Volatiles	µg/m³							
Acetone	140	U	57	U	240	U	100	U
Benzene	151	J	47.2	J	390	U	122	U
Chlorobenzene	260	U	57	U	460	U	100	U
Chloroethane	1820		689		356	U	135	U
1,1-Dichloroethane	230	U	57	U	56700	U	14000	U
1,1-Dichloroethene	230	U	57	U	678	U	171	U
1,2-Dichloroethane	230	U	57	U	400	U	100	U
trans-1,2-Dichloroethene	230	U	57	U	400	U	100	U
cis-1,2-Dichloroethene	230	U	57	U	2790	U	704	U
Ethylbenzene	250	U	57	U	430	U	100	U
Freon 113	440	U	57	U	770	U	100	U
Freon 114	400	U	57	U	700	U	100	U
Heptane	865		211		410	U	100	U
Hexane	20700		5870		2010	U	569	U
Methylene chloride	200	U	57	U	350	U	100	U
Methyl cyclohexane	ND		6300		ND	ND	ND	ND
Methyl ethyl ketone	170	U	57	U	290	U	100	U
Pentane	1780		606		456	U	155	U
1,1,1-Trichloroethane	310	U	57	U	30800	U	5640	U
Tetrachloroethene	390	U	57	U	3280	U	484	U
Toluene	210	U	57	U	380	U	100	U
Trichloroethene	310	U	57	U	1590	U	295	U
Vinyl chloride	111	J	43.4	J	322	U	126	U
m,p-Xylene	208	J	47.9	J	430	U	100	U
o-Xylene	250	U	57	U	430	U	100	U
Xylenes (total)	208	J	47.9	J	430	U	100	U
Total TIC, Volatile			70300	J			3820	J
								4110 J

**SUMMARY OF 206 SOIL VAPOR INTRUSION ANALYTICAL RESULTS
FORMER COLUMBIA CEMENT COMPANY FACILITY
FREEPORT, NEW YORK**

SAMPLE TYPE	SAMPLE LOCATION	SOIL GAS SAMPLES							
		SPILL / UST AREA		SG-05-08 08/15/06		SG-05-10 08/15/06			
SAMPLE ID	SG-05-05 08/15/06	J38685-6	J38685-1	08/15/06	J38685-5	ppbv	ppbv	ppm3	ppbv
SAMPLING DATE									
ACCUTEST SAMPLE ID									
GC/MS Volatiles	µg/m3	ppbv	µg/m3	ppbv	µg/m3	ppbv	µg/m3	ppm3	ppbv
Acetone	146	61.5	57.0	24.0	9.5	U	4.0	U	4.0
Benzene	68.7	21.5	38.3	12.0	16	5.0	5.0	U	5.0
Chlorobenzene	15	U	3.2	U	3.2	U	18	U	4.0
Chloroethane	74.4	28.2	8.7	3.3	1450	551	488	U	488
1,1-Dichloroethane	1990	492	22	5.4	1980	488	17.6	U	17.6
1,1-Dichloroethene	56.7	14.3	13	U	3.2	U	69.8	U	4.0
1,2-Dichloroethane	13	U	3.2	U	13	U	3.2	U	4.0
trans-1,2-Dichloroethene	13	U	3.2	U	13	U	3.2	U	4.0
cis-1,2-Dichloroethene	140	35.2	13	U	3.3	U	17	U	4.2
Ethylbenzene	14	U	3.2	U	14	U	3.2	U	4.0
Freon 113	38	4.9	18	J	2.4	J	31	U	4.0
Freon 114	368	52.7	18	J	2.6	J	28	U	4.0
Heptane	9.8	J	2.4	J	85.7	20.9	141	U	34.4
Hexane	79.3	22.5	83.2	23.6	846	240	U	4.0	U
Methylene chloride	18	5.3	34.7	10.0	14	U	4.0	U	4.0
Methyl cyclohexane	ND	ND	ND	ND	ND	ND	ND	ND	ND
Methyl ethyl ketone	9.4	U	3.2	U	22	7.6	12	U	4.0
Pentane	159	54.1	158	53.5	724	246	U	4.0	U
1,1,1-Trichloroethane	1300	239	17	U	3.2	U	25	U	4.5
Tetrachloroethene	963	142	22	U	2.9	J	46.4	U	12.3
Toluene	10	J	2.7	J	11	J	3.2	U	4.0
Trichloroethene	554	103	17	U	2.9	J	21	U	4.0
Vinyl chloride	22	8.7	8.2	U	3.2	U	67.2	U	26.3
m,p-Xylene	13	J	2.9	J	9.6	J	2.2	J	4.0
o-Xylene	14	U	3.2	U	7.4	J	1.7	J	4.0
Xylenes (total)	13	J	2.9	J	17	J	3.9	J	4.0
Total TIC, Volatile			1190	J	1672	J	3120	J	3120

SUMMARY OF 206 SOIL VAPOR INTRUSION ANALYTICAL RESULTS
FORMER COLUMBIA CEMENT COMPANY FACILITY
FREEPORT, NEW YORK

FILE 14

SAMPLE TYPE	SAMPLE LOCATION	SUB-SLAB SAMPLE						AMBIENT AIR SAMPLE		
		SAMPLE ID	SS-06-05 (1 L can) 10/05/06		SS-06-05 (6 L can) 10/05/06		AA-06-10-05 (1 L can) 10/05/06	AA-06-10-05 (6 L can) 10/05/06		
			J43168-1	687244	J43168-2	687243		687243		
GC/MS Volatiles	ug/m3	ppbv	ug/m3	ppbv	ug/m3	ppbv	ug/m3	ppbv	ug/m3	ppbv
Acetone	208	87.6	330	140	2.6	U	1.1	U	12	U
Benzene	10	3.2	13	4.0	0.61	U	0.19	U	0.64	U
Chlorobenzene	2.7	U	0.59	U	4.6	U	2.7	U	0.59	U
Chloroethane	1.3	U	0.49	U	6.6	U	2.5	U	1.3	U
1,1-Dichloroethane	216	53.3	340	85	2.3	U	0.58	U	0.81	U
1,1-Dichloroethene	2.8	U	0.71	U	4.0	U	1.0	U	0.71	U
1,2-Dichloroethane	2.2	U	0.54	U	16	U	2.3	U	0.54	U
trans-1,2-Dichloroethene	2.2	U	0.56	U	4.0	U	1.0	U	2.2	U
cis-1,2-Dichloroethene	9.9	2.5	U	U	6.5	U	1.5	U	1.7	U
Ethylbenzene	5.2	J	1.2	J	6.5	U	1.7	U	0.43	U
Freon 113	4.7	U	0.61	U	7.7	U	1.0	U	4.7	U
Freon 114	2.4	U	0.35	U	7.7	U	1.0	U	2.4	U
Heptane	7.4	U	1.8	U	9.4	U	2.3	U	2.5	U
Hexane	12	U	3.4	U	17	U	4.9	U	2	J
Methylene chloride	4.5	J	1.3	J	8.7	U	2.5	U	2.3	U
Methyl cyclohexane	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Methyl ethyl ketone	1.2	U	0.42	U	32	U	11	U	36.3	J
Pentane	35.6	12.1	ND	ND	ND	ND	2.7	U	0.9	J
1,1,1-Trichloroethane	38	7	51	9.4	2.6	U	3	U	0.47	U
Tetrachloroethene	564	83.1	290	43	3	U	0.44	U	1.1	U
Toluene	18	4.8	28	7.4	15	U	3.9	U	4.9	U
Trichloroethene	58	10.8	86	16	3.1	U	0.58	U	1.1	U
Vinyl chloride	1.3	U	0.51	U	2.6	U	1.0	U	0.51	U
m,p-Xylene	12	U	2.7	U	18	U	4.1	U	0.86	U
o-Xylene	4.8	J	1.1	J	6.5	U	1.5	U	0.83	U
Xylenes (total)	17	3.8	U	25	5.7	U	297	J	0.19	U
Total TIC, Volatile		254.3	J						ND	ND

SUMMARY OF 2006 SOIL VAPOR INTRUSION ANALYTICAL RESULTS
FORMER COLUMBIA CEMENT COMPANY FACILITY
FREEPORT, NEW YORK

TABLE 14

NOTES:

$\mu\text{g}/\text{m}^3$: Micrograms per cubic meter

ppbv : Parts per billion by volume

U : Not detected at stated detection limit.


J : Estimated value

ND : Not Detected

TABLE 15
EVALUATION OF VAPOR INTRUSION DATA
AUGUST - OCTOBER 2006
FORMER COLUMBIA CEMENT COMPANY FACILITY
FREEPORT, NEW YORK

LOCATION	COMPOUND	Maximum Sub-Slab Concentration (ug/m ³)	Indoor Air Concentration (ug/m ³)	Ambient Air Concentration (ug/m ³)	Attenuation Factor	Applicable NYSDOH Matrix	Matrix Decision	Comments
Columbia Cement	Tetrachloroethylene (PCE)	2,140	1.3	1.4	6.1E-04	2	Mitigate	2nd Indoor sample was <11
	Trichloroethylene (TCE)	534	1.1	31	2.1E-03	1	Mitigate	2nd Indoor sample was <8.6
	1,1,1-Trichloroethane (TCA)	86,200	0.93	1.1	1.1E-05	2	Mitigate	2nd Indoor sample was <8.7
Knickerbocker	Tetrachloroethylene (PCE)	121	1.1	1.4	9.1E-03	2	Monitor	
	Trichloroethylene (TCE)	7.0	1.1	31	1.6E-01	1	Monitor	
	1,1,1-Trichloroethane (TCA)	27	1.1	1.1	4.1E-02	2	No further action	
Rohm & Haas	Tetrachloroethylene (PCE)	564	--	3	NC	2	Monitor or Mitigate	
	Trichloroethylene (TCE)	58	--	3.1	NC	1	Monitor or Mitigate	
	1,1,1-Trichloroethane (TCA)	38	--	2.6	NC	2	No further action	

Note: For non-detect results, the compound's method detection limit was used to evaluate the decision matrix.

LEGEND:

SOIL BORING
SAMPLE INTERVALS
ARE SHARED

FORMER UST
LOCATION

ND
NOT DETECTED

J
ESTIMATED VALUE

10
VALUE EXCEEDS NYSPEC TAGM RECOMMENDED SOIL
CLEANUP OBJECTIVE

10
VALUE EXCEEDS NYSDDEC TAGM IN RECOMMENDED SOIL
CLEANUP OBJECTIVE BY AN ORDER OF MAGNITUDE

ALL CONCENTRATION EXPRESSED AS mg/kg.

SCALE HORIZONTAL 1"=10'
VERTICAL 1"=5'

**FORMER COLUMBIA
CEMENT COMPANY, INC.
159 HANSEN AVENUE
FREEPORT, NEW YORK**

**SOIL 1,1,1-TCA CONCENTRATIONS
CROSS SECTION A - A'**


URS

12 COMMERCE DRIVE
CRANFORD, NJ 07016
PHONE: (908) 272-8300
FAX: (908) 272-3940

DATE: 11/07/05

PROJECT: 38546433

FIGURE 5



**FORMER COLUMBIA
CEMENT COMPANY, INC.
159 HANSEN AVENUE
FREEPORT, NEW YORK**

**SOIL 1,1,1-TCA CONCENTRATIONS
CROSS SECTION B - B'**


SCALE HORIZONTAL 1"=10'
VERTICAL 1"=5'


URS

12 COMMERCE DRIVE
CRANFORD, NJ, 07016
PHONE: (908) 272-8300
FAX: (908) 272-3940

FIGURE 6

DATE: 11/07/05
PROJECT: 38546433





SCALE HORIZONTAL 1"=10'
VERTICAL 1"=5'

**FORMER COLUMBIA
CEMENT COMPANY, INC.
159 HANSEN AVENUE
FREEPORT, NEW YORK**

SOIL 1,1,1-TCA CONCENTRATIONS

CROSS SECTION D - D'


URS

12 COMMERCE DRIVE
CRANFORD, NJ 07016
PHONE: (908) 272-8300
FAX: (908) 272-3940

DATE: 11/07/05

PROJECT: 38546433

FIGURE 8




SCALE HORIZONTAL 1"=10'
VERTICAL 1"=5'

**FORMER COLUMBIA
CEMENT COMPANY, INC.
159 HANSEN AVENUE
FREEPORT, NEW YORK**
**SOIL CONCENTRATIONS OF 1,1-DCA
CROSS SECTION A - A'**

URS

12 COMMERCE DRIVE
CRAWFORD, NJ 07016
PHONE: (908) 272-3300
FAX: (908) 272-3940

DATE: 11/07/05
PROJECT: 38546433



**FORMER COLUMBIA
CEMENT COMPANY, INC.**
159 HANSEN AVENUE
FREEPORT, NEW YORK


**SOIL CONCENTRATIONS OF 1,1-DCA
CROSS SECTION B - B'**

URS

12 COMMERCE DRIVE
CRANFORD, NJ 07016
PHONE: (908) 272-8300
FAX: (908) 272-3940

FIGURE 10

SCALE HORIZONTAL 1"=10'
VERTICAL 1"=5'



SCALE HORIZONTAL 1"=10'

VERTICAL 1"=5'

URS12 COMMERCE DRIVE
CRANFORD, NJ 07016
PHONE: (908) 272-8300
FAX: (908) 272-3940

**FORMER COLUMBIA
CEMENT COMPANY, INC.
159 HANSEN AVENUE
FREEPORT, NEW YORK**


SOIL 1,1-DCA CONCENTRATIONS

CROSS SECTION D - D'

DATE: 11/07/05

PROJECT: 38546433

FIGURE 12



SCALE
VERTICAL 1"=5'
HORIZONTAL 1"=10'

35 —

30 —

25 —

20 —

15 —

10 —

5 —

0 —

TANK 1 T-1
TANK 2 T-2
TANK 3 T-3
TANK 4 T-4
TANK 5 T-5

A —
A'

LEGEND:

() FORMER UST LOCATION.
[] SOIL BORING SAMPLE INTERVALS ARE SHARED

ND NOT DETECTED
J ESTIMATED VALUE
D RESULT IS FROM DILUTED SAMPLE

[] 10 VALUE EXCEEDS NYSDDEC TAGM IN RECOMMENDED SOIL CLEANUP OBJECTIVE BY AN ORDER OF MAGNITUDE
ALL CONCENTRATION EXPRESSED AS mg/kg.


**FORMER COLUMBIA
CEMENT COMPANY, INC.
159 HANSEN AVENUE
FREEPORT, NEW YORK**
**SOIL CONCENTRATIONS OF CHLOROETHANE
CROSS SECTION A - A'**

URS

12 COMMERCE DRIVE
CRANFORD, NJ 07016
PHONE: (908) 272-8300
FAX: (908) 272-3940

DATE: 11/07/05
PROJECT: 38546433

FIGURE 13



LEGEND:

() SOIL BORING
SAMPLE INTERVALS
ARE SHARED

() FORMER UST
LOCATION

J ESTIMATED VALUE
D RESULT IS FROM DILUTED SAMPLE
ND NOT DETECTED

10 VALUE EXCEEDS NYSDEC TAGM RECOMMENDED SOIL
CLEANUP OBJECTIVE
 10 VALUE EXCEEDS NYSDEC TAGM IN RECOMMENDED SOIL
CLEANUP OBJECTIVE BY AN ORDER OF MAGNITUDE

ALL CONCENTRATION EXPRESSED AS mg/kg.


**FORMER COLUMBIA
CEMENT COMPANY, INC.
159 HANSEN AVENUE
FREEPORT, NEW YORK**
**SOIL CONCENTRATIONS OF CHLOROETHANE
CROSS SECTION B - B'**


SCALE HORIZONTAL 1"=10'
SCALE VERTICAL 1"=5'

URS

12 COMMERCE DRIVE
CRANFORD, NJ 07016
PHONE: (908) 272-8300
FAX: (908) 272-3940

DATE: 11/07/05
PROJECT: 38546433
FIGURE 14





**FORMER COLUMBIA
CEMENT COMPANY, INC.
159 HANSEN AVENUE
FREEPORT, NEW YORK**

SOIL CONCENTRATIONS OF CHLOROETHANE CROSS SECTION D - D'

SCALE HORIZONTAL 1"=10'
VERTICAL 1"=5'

URS

12 COMMERCE DRIVE
CRAWFORD, NJ 07016
PHONE: (908) 272-8300
FAX: (908) 272-3940

DATE: 11/07/05

PROJECT: 38546433

FIGURE 16

APPENDIX A

**DELAWARE ENGINEERING
DECEMBER 2003 RIR DATA TABLES**

Table 1
Summary of Site Stratigraphy
Former Columbia Cement Company, Inc. Facility
Freeport, Nassau County, New York

Boring I.D.	Fill ¹ (Interval-Feet BGS/[Elevation])	Tidal Marsh ² (Interval-Feet BGS/[Elevation])	Gravelly Sand ³ (Interval-Feet BGS/[Elevation])	Gray Clay and Silt Lower Confining Unit ⁴ (Interval-Feet BGS/[Elevation])	Gray Sand ⁵ (Interval-Feet BGS/[Elevation])
B-8	0-7.0	7.0-12.0	12.0->35.0	NE	NE
MW-1S	0-11.50 [97.96-86.46]	11.50-15.30 [86.46-82.66]	15.30-34.9 [82.66-63.06]	34.9->38 [63.06-<59.96]	NE
MW-1D-97	0-6.10 [97.63-91.53]	6.10-7.25 [91.53-90.38]	7.25->26.0 [90.38-<71.63]	NE	NE
MW-97-1S	0-9.75 [98.83-88.08]	9.75-11.25 [89.08-87.58]	11.25->25.0 [87.58-<73.41]	NE	NE
MW-97-2S	0-7.90 [98.66-90.76]	7.90-13.35 [80.76-85.31]	13.35->25.0 [85.31-<73.66]	NE	NE
MW-97-3S	0-9.10 [98.86-89.76]	9.10-13.15 [89.76-85.71]	13.15->25.5 [85.71-<73.36]	NE	NE
MW-97-4S	0-9.80 [98.59-88.79]	9.80-11.55 [88.79-87.04]	11.55->26.0 [87.04-<72.59]	NE	NE
MW-97-5S	0-10.10 [98.69-88.59]	10.10-12.95 [88.59-85.74]	12.95->26.0 [85.74-<72.69]	NE	NE
MW-97-6S	0-17.60 [98.79-81.19]	NE	17.60->32.0 [81.19-<66.79]	NE	NE
MW-97-7S	0-7.70 [98.68-90.98]	7.70-13.55 [90.98-85.13]	13.55-35.3 [85.13-63.38]	35.30->38.0 [63.38-<60.88]	NE
MW-98-8D	0-5.65 [97.54-91.89]	5.65-11.71 [91.69-85.84]	11.70-37.0 [85.84-60.54]	37.0->40.0 [60.54-<57.54]	NE
MW-98-9D	0-9.85 [98.75-88.90]	9.85-10.75 [88.90-88.00]	10.75-37.1 [88.00-61.65]	37.1->38.0 [61.65-<60.75]	NE
MW-98-10D	0-18.5 [97.89-79.39]	NE	18.5-34.6 [79.39-63.29]	34.6-48.55 [63.29-49.34]	48.55->61.5 [49.34-<36.39]
MW-00-11A	0-8.45 [98.6-90.15]	8.45-12.95 [90.15-85.65]	12.95-34.7 [85.65-63.90]	34.7-50.0 [63.90-48.60]	50.0->52.5 [48.60-<46.10]
MW-00-12D	0-10.85 [98.05-87.20]	10.85-14.65 [87.20-83.40]	14.65->25.5 [83.4->72.55]	NE	NE
MW-03-13S	0-10.9 [98.43-87.53]	10.9-13.3 [87.53-85.13]	13.3->26.0 [85.13-<72.43]	NE	NE
TB-97-1	0-8.77 [98.11-88.34]	9.77-22.4 [88.34-75.71]	22.4->26.0 [75.71-<72.11]	NE	NE
TB-97-2	0-22.9 [98.24-75.34]	NE	22.9->26.0 [75.34-<72.24]	NE	NE
TB-97-3	0-7.75 [98.28-90.53]	7.75-12.1 [90.58-86.18]	12.1->25.0 [86.18-<73.28]	NE	NE
TB-97-4	0-3.10 [98.43-95.33]	3.10-13.35 [95.33-85.08]	13.35->25.0 [85.08-73.43]	NE	NE
TB-97-5	0-7.80 [98.07-91.27]	7.80-13.70 [91.27-85.37]	13.7->25.0 [85.37-<74.07]	NE	NE
TB-97-6	0-15.10 [97.64-82.54]	NE	15.10-34.0 [82.54-63.64]	34.0->38.0 [63.64-<59.64]	NE
SB-98-2	0-19.35 [97.83-78.46]	19.35-19.58 [78.46-78.25]	19.58-35.67 [78.25-62.16]	35.67->38.0 [62.16-<59.33]	NE
SB-98-3	0-14.55 [98.44-83.69]	NE	14.55-35.16 [83.89-63.28]	35.16->38.0 [63.28-<60.44]	NE
SB-98-4	0-12.65 [99.01-86.36]	12.65-13.49 [86.36-85.52]	13.49->14.0 [85.52-<85.01]	NE	NE
BSB-98-5	0-11.35 [98.34-87.59]	11.35-13.63 [87.59-85.31]	13.63-34.55 [85.31-64.39]	34.55->38.0 [64.39-<60.94]	NE

Notes:

BGS = Below Ground Surface; NE = Not Encountered

Elevations based on a benchmark established by Rust E&I at utility pole F34, assumed site datum = 100.00

¹ = Fill consists of soil (20-75%) and landfill debris (80-25%); cinders, brick, stone, concrete, glass, wood, textile debris & metal.

² = Tidal Marsh unit generally consists of a dark brown to dark gray-black organic clayey silt to occasional clay and silt with frequent roots and wood; occasionally peat-like.

³ = Gravelly Sand unit generally consists of a brown to light gray coarse, medium(+) to fine sand, little medium to fine(+) surrounded gravel.

⁴ = Gray Clay and Silt unit or "Lower Confining" unit consists of a gray silt and clay, trace fine sand grading downward to a non-plastic clay and silt, trace fine sand.

⁵ = Gray Sand unit generally consists of a brownish gray to light medium to fine (+) fine sand, little silt.

TABLE 2A
Groundwater Elevation Data
Former Columbia Cement Company, Inc. Facility
Freeport, New York
December 30, 1998 Data

Monitoring Well	Round 1 feet	Round 2 feet	Round 3 feet	Round 4 feet	Round 5 feet	Round 6 feet	Round 7 feet	Round 8 feet	Round 9 feet
MW-1S	91.81	91.84	91.85	91.82	91.82	91.79	91.73	91.66	91.59
MW-1D-97	91.83	91.85	91.86	91.86	91.84	91.79	91.74	91.67	91.62
MW-97-1S	91.65	91.63	91.60	91.65	91.60	91.53	91.49	91.43	91.37
MW-97-2S	91.48	91.52	91.51	91.51	91.51	91.48	91.45	91.42	91.37
MW-97-3S	91.95	91.98	91.98	91.99	91.94	91.91	91.85	91.75	91.66
MW-97-4S	91.85	91.85	91.86	91.85	91.83	91.75	91.73	91.66	91.59
MW-97-5S	91.85	91.87	91.86	91.85	91.84	91.78	91.72	91.65	91.57
MW-97-6S	91.74	91.73	91.71	91.73	91.71	91.65	91.64	91.59	91.54
MW-97-7S	91.64	91.67	91.67	91.66	91.66	91.64	91.59	91.56	91.50
MW-98-8S	91.93	92.24	91.98	91.93	91.92	91.86	91.80	91.73	91.65
MW-98-8D	91.92	91.96	91.97	91.97	91.94	91.89	91.82	91.76	91.66
MW-98-9D	91.66	91.66	91.62	91.66	91.60	91.56	91.51	91.46	91.39
MW-98-10D	91.53	91.57	91.56	91.55	91.52	91.52	91.50	91.44	91.42
	Round 10 feet	Round 11 feet	Round 12 feet	Round 13 feet	Round 14 feet	Round 15 feet	Round 16 feet	Round 17 feet	Round 18 feet
MW-1S	91.52	91.41	91.34	91.22	91.16	91.06	90.97	90.96	90.93
MW-1D-97	91.54	91.44	91.34	91.23	91.17	91.08	91	91.01	90.95
MW-97-1S	91.29	91.23	91.16	91.07	91.02	90.95	90.93	90.92	90.93
MW-97-2S	91.33	91.28	91.22	91.16	91.13	91.08	91.03	91.01	90.99
MW-97-3S	91.56	91.44	91.31	91.18	91.11	91.01	90.93	90.89	90.89
MW-97-4S	91.51	91.42	91.33	91.21	91.14	91.05	91.00	90.97	90.93
MW-97-5S	91.49	91.39	91.29	91.17	91.11	91.01	90.92	90.90	90.89
MW-97-6S	91.48	91.40	91.32	91.26	91.19	91.13	91.06	91.03	91.01
MW-97-7S	91.46	91.40	91.32	91.26	91.22	91.16	91.09	91.07	91.06
MW-98-8S	91.55	91.47	91.34	91.21	91.20	91.05	90.96	90.93	90.90
MW-98-8D	91.56	91.46	91.35	91.22	91.16	91.04	90.95	90.93	90.91
MW-98-9D	91.31	91.25	91.18	91.10	91.05	90.98	90.95	90.94	90.95
MW-98-10D	91.38	91.31	91.25	91.18	91.17	91.12	91.08	91.05	91.04
	Round 19 feet	Round 20 feet	Round 21 feet	Round 22 feet	Round 23 feet	Round 24 feet	Round 25 feet	Round 26 feet	
MW-1S	90.93	90.95	90.97	91.03	91.07	91.10	91.15	91.20	
MW-1D-97	90.96	90.97	90.99	91.06	91.08	91.11	91.17	91.23	
MW-97-1S	90.93	90.98	90.99	91.02	91.05	91.06	91.10	91.14	
MW-97-2S	91.01	91.01	91.21	91.03	91.05	91.06	91.07	91.10	
MW-97-3S	90.9	90.93	90.88	91.04	91.09	91.1	91.19	91.23	
MW-97-4S	90.94	90.95	90.99	91.03	91.06	91.06	91.1	91.15	
MW-97-5S	90.89	90.92	90.95	91	91.05	91.06	91.09	91.14	
MW-97-6S	91.01	91.01	91.06	91.04	91.07	91.07	91.1	91.15	
MW-97-7S	91.05	91.05	91.06	91.08	91.09	91.11	91.15	91.17	
MW-98-8S	90.91	90.91	90.97	91.05	91.08	91.10	91.20	91.22	
MW-98-8D	90.91	90.92	90.98	91.04	91.08	91.08	91.19	91.23	
MW-98-9D	90.95	91.00	91.01	91.04	91.07	91.08	91.12	91.17	
MW-98-10D	91.04	91.05	91.05	91.10	91.11	91.11	91.14	91.16	
	Minimum	Maximum	Max-Min						
MW-1S	90.93	91.85	0.92						
MW-1D-97	90.95	91.86	0.91						
MW-97-1S	90.92	91.65	0.73						
MW-97-2S	90.99	91.52	0.53						
MW-97-3S	90.88	91.99	1.11						
MW-97-4S	90.93	91.86	0.93						
MW-97-5S	90.89	91.87	0.98						
MW-97-6S	91.01	91.74	0.73						
MW-97-7S	91.05	91.67	0.62						
MW-98-8S	90.9	92.24	1.34						
MW-98-8D	90.91	91.97	1.06						
MW-98-9D	90.94	91.66	0.72						
MW-98-10D	91.04	91.57	0.53						

TABLE 2B
Groundwater Elevation Data
Former Columbia Cement Company, Inc. Facility
Freeport New York
February 16, 1999 Data

	Round 1 feet	Round 2 feet	Round 3 feet	Round 4 feet	Round 5 feet	Round 6 feet	Round 7 feet	Round 8 feet	Round 9 feet
MW-1S	91.62	91.64	91.64	91.66	91.66	91.61	91.58	91.55	91.49
MW-1D-97	91.65	91.65	91.68	91.69	91.69	91.68	91.64	91.58	91.52
MW-97-1S	91.43	91.43	91.42	91.41	91.40	91.39	91.36	91.32	91.25
MW-97-2S	91.34	91.35	91.36	91.35	91.34	91.35	91.34	91.33	91.29
MW-97-3S	91.73	91.75	91.77	91.78	91.77	91.74	91.68	91.61	91.53
MW-97-4S	91.63	91.65	91.65	91.67	91.67	91.65	91.62	91.58	91.51
MW-97-5S	91.63	91.66	91.66	91.66	91.67	91.65	91.60	91.54	91.47
MW-97-6S	91.53	91.54	91.55	91.57	91.57	91.56	91.53	91.51	91.47
MW-97-7S	91.50	91.52	91.53	91.54	91.54	91.53	91.52	91.49	91.46
MW-98-8S	91.74	91.75	91.77	91.78	91.78	91.75	91.68	91.64	91.57
MW-98-8D	91.72	91.72	91.75	91.75	91.75	91.72	91.64	91.61	91.61
MW-98-9D	91.44	91.44	91.42	91.43	91.41	91.41	91.37	91.33	91.26
MW-98-10D	91.36	91.38	91.38	91.39	91.38	91.37	91.36	91.33	91.29
	Round 10 feet	Round 11 feet	Round 12 feet	Round 13 feet	Round 14 feet	Round 15 feet	Round 16 feet	Round 17 feet	Round 18 feet
MW-1S	91.43	91.36	91.26	91.22	91.15	91.08	91.06	91.05	91.06
MW-1D-97	91.47	91.40	91.31	91.24	91.17	91.14	91.08	91.07	91.07
MW-97-1S	91.19	91.14	91.09	91.03	90.99	90.96	90.96	90.97	90.97
MW-97-2S	91.25	91.20	91.16	91.12	91.09	91.05	91.05	91.04	91.05
MW-97-3S	91.45	91.36	91.25	91.17	91.09	91.01	90.99	91.00	91.00
MW-97-4S	91.44	91.38	91.29	91.22	91.15	91.09	91.04	91.04	91.04
MW-97-5S	91.41	91.34	91.25	91.18	91.11	91.05	91.01	91.01	91.01
MW-97-6S	91.43	91.35	91.32	91.26	91.21	91.16	91.13	91.13	91.13
MW-97-7S	91.43	91.37	91.33	91.28	91.24	91.19	91.17	91.17	91.17
MW-98-8S	91.50	91.42	91.33	91.25	91.18	91.10	91.08	91.08	91.08
MW-98-8D	91.47	91.38	91.29	91.20	91.11	91.04	91.01	91.02	91.01
MW-98-9D	91.20	91.15	91.10	91.04	91.00	90.97	90.98	90.98	90.98
MW-98-10D	91.25	91.22	91.17	91.13	91.11	91.07	91.06	91.05	91.06
	Round 19 feet	Round 20 feet	Round 21 feet	Round 22 feet	Round 23 feet	Round 24 feet	Round 25 feet	Round 26 feet	Round 27 feet
MW-1S	91.11	91.15	91.21	91.29	91.36	91.42	91.48	91.55	91.57
MW-1D-97	91.15	91.19	91.25	91.30	91.39	91.44	91.50	91.58	91.60
MW-97-1S	91.07	91.10	91.12	91.21	91.24	91.28	91.36	91.38	91.39
MW-97-2S	91.08	91.10	91.15	91.17	91.21	91.22	91.25	91.32	91.33
MW-97-3S	91.10	91.16	91.23	91.31	91.42	91.49	91.57	91.63	91.68
MW-97-4S	91.12	91.16	91.23	91.31	91.38	91.43	91.50	91.56	91.59
MW-97-5S	91.09	91.15	91.30	91.28	91.34	91.43	91.47	91.55	91.59
MW-97-6S	91.19	91.21	91.22	91.27	91.33	91.41	91.45	91.46	91.51
MW-97-7S	91.20	91.22	91.26	91.30	91.33	91.39	91.43	91.46	91.49
MW-98-8S	91.17	91.21	91.30	91.36	91.55	91.51	91.58	91.65	91.69
MW-98-8D	91.12	91.17	91.25	91.31	91.41	91.45	91.55	91.62	91.65
MW-98-9D	91.08	91.11	91.14	91.22	91.24	91.30	91.35	91.38	91.40
MW-98-10D	91.10	91.13	91.14	91.20	91.23	91.26	91.31	91.35	91.36
	Round 28 feet	Round 29 feet	Round 30 feet	Round 31 feet	Round 32 feet	Minimum feet	Maximum feet	Max-Min feet	
MW-1S	91.61	91.60	91.55	91.57	91.53	91.05	91.66	0.61	
MW-1D-97	91.64	91.64	91.58	91.60	91.55	91.07	91.69	0.62	
MW-97-1S	91.40	91.39	91.38	91.40	91.40	90.96	91.43	0.47	
MW-97-2S	91.35	91.34	91.32	91.35	91.35	91.04	91.36	0.32	
MW-97-3S	91.70	91.71	91.63	91.67	91.63	90.99	91.78	0.79	
MW-97-4S	91.62	91.61	91.56	91.58	91.55	91.04	91.67	0.63	
MW-97-5S	91.62	91.62	91.55	91.61	91.58	91.01	91.67	0.66	
MW-97-6S	91.52	91.51	91.46	91.49	91.45	91.13	91.57	0.44	
MW-97-7S	91.51	91.51	91.46	91.49	91.49	91.17	91.54	0.37	
MW-98-8S	91.72	91.68	91.65	91.64	91.61	91.08	91.78	0.70	
MW-98-8D	91.68	91.68	91.62	91.66	91.62	91.01	91.75	0.74	
MW-98-9D	91.41	91.39	91.38	91.40	91.41	90.97	91.44	0.47	
MW-98-10D	91.36	91.37	91.35	91.35	91.35	91.05	91.39	0.34	

Table 2C
Summary of Water Table Elevation Data (May 3, 2000)
Former Columbia Cement Company, Inc. Facility
Freeport, Nassau County, New York

Well I.D.	Measuring Point Elevation ¹	Depth to Water During Low Tide ²	Elevation of Water Table During Low Tide ²	Depth to Water During High Tide ³	Elevation of Water Table During High Tide ³
MW-1S	97.60	6.57	91.03	5.93	91.67
MW-1D-97	97.72	6.66	91.06	6.02	91.70
MW-97-1S	97.22	6.20	91.02	5.70	91.52
MW-97-2S	98.26	7.19	91.07	6.78	91.48
MW-97-3S	98.21	7.16	91.05	6.32	91.89
MW-97-4S	98.46	7.41	91.05	6.76	91.70
MW-97-5S	98.33	7.33	91.00	6.62	91.71
MW-97-6S	98.35	7.22	91.13	6.74	91.61
MW-97-7S	98.37	7.19	91.18	6.78	91.59
MW-98-8S	98.71	7.56	91.15	6.83	91.88
MW-98-8D	98.49	7.50	90.99	6.71	91.78
MW-98-9D	97.22	6.25	90.97	5.73	91.49
MW-98-10D	98.46	7.39	91.07	7.02	91.44
MW-00-11A	97.22	---	NM	---	NM
MW-00-12D	98.20	7.14	91.06	6.46	91.74

Notes:

Elevations based on a benchmark established by Rust E&I at utility pole F34, assumed site datum = 100.00

¹ = Measuring point elevation is at marked Top of 2" I.D. PVC.

² = Low Tide (May 3, 2000 at 3:57 P.M.).

³ = High Tide (May 3, 2000 at 10:22 P.M.).

Table 3

Summary of Hydraulic Conductivity Test Results
Former Columbia Cement Company, Inc. Facility
Freeport, New York

Monitoring Well I.D.	Test Method			
	Hvorslev		Bouwer & Rice	
	(cm/sec)	(ft/day)	(cm/sec)	(ft/day)
MW-1S	6.15E-04	1.74	4.45E-04	1.26
MW-97-1S	3.16E-02	89.59	2.32E-02	65.77
MW-97-2S	3.03E-02	85.90	2.33E-02	66.06
MW-97-3S	1.36E-02	38.56	1.44E-02	40.82
MW-97-4S	3.96E-02	112.27	2.41E-02	68.32
MW-97-5S	2.49E-02	70.59	1.58E-02	44.79
MW-97-6S	3.64E-02	103.19	2.64E-02	74.84
MW-97-7S	2.24E-02	63.50	2.08E-02	58.97
MW-98-8S	7.23E-03	20.50	4.24E-03	12.02
MW-03-13S	1.90E-02	53.86	1.12E-02	31.75
MW-1D-97	1.23E-02	34.87	1.02E-02	28.92
MW-98-8D	1.21E-02	34.30	7.47E-03	21.18
MW-98-9D	4.15E-02	117.65	3.62E-02	102.63
MW-98-10D	1.63E-02	46.21	1.08E-02	30.62
MW-00-12D	1.30E-02	36.85	1.37E-02	38.83
MW-00-11A	2.12E-02	60.09	1.28E-02	36.28
Min.	6.15E-04	1.74	4.45E-04	1.26
Max.	4.15E-02	117.65	3.62E-02	102.63
Average	2.15E-02	60.60	1.59E-02	45.19
Geometric Mean	1.61E-02	45.64	1.20E-02	34.02

NOTE:

The application of the Hvorslev method assumes unconfined conditions for all "S" wells and "D" wells at the site. Confined conditions are assumed for monitoring well MW-00-11A; therefore, the application of the Hvorslev method is considered most appropriate.

Table 4

Summary of Well Construction Details
Former Columbia Cement Company, Inc. Facility
Freeport, Nassau County, New York

Well I.D.	Ground Surface Elevation ¹	Concrete Seal depth in feet BGS/[Elevation]	Cement-Bentonite Grout depth in feet BGS/[Elevation]	Bentonite Seal depth in feet BGS/[Elevation]	Sand Pack depth in feet BGS/[Elevation]	Screen depth in feet BGS/[Elevation]
MW-1S	98.04	-0-3.0	-3.0-8.0	-8.0-10.0	~10.0-21.0	~11.0-21.0
MW-1D-97	97.96	0-3.0	3.0-22.0 [94.96-75.96]	22.0-27.5 [75.96-70.46]	27.5-34.5 [70.46-63.46]	28.65-33.65 [69.31-64.31]
MW-97-1S	97.63	0-3.0	3.0-9.2 [94.63-88.43]	9.15-12.25 [88.43-85.38]	12.25-25.0 [85.38-72.63]	14.25-24.25 [83.38-73.38]
MW-97-2S	98.83	0-3.0	3.0-9.3 [95.83-89.53]	9.3-12.5 [89.53-86.33]	12.5-25.0 [86.33-73.83]	14.5-24.5 [84.33-74.33]
MW-97-3S	98.66	0-3.0	3.0-11.0 [95.66-87.66]	11.0-14.0 [87.66-84.66]	14.0-25.25 [84.66-73.41]	15.0-25.0 [83.66-73.66]
MW-97-4S	98.86	0-3.0	3.0-11.0 [95.86-87.86]	11.0-14.0 [87.86-84.86]	14.0-25.5 [84.86-73.36]	15.25-25.25 [83.61-73.61]
MW-97-5S	98.59	0-3.0	3.0-9.7 [95.59-88.89]	9.7-13.0 [88.89-85.59]	13.0-26.0 [85.59-72.59]	15.80-25.80 [82.79-72.79]
MW-97-6S	98.69	0-3.0	3.0-10.6 [95.69-88.09]	10.55-14.0 [88.09-84.69]	14.0-25.5 [84.69-73.19]	15.5-25.5 [83.19-73.19]
MW-97-7S	98.79	0-3.0	3.0-16.1 [95.79-82.69]	16.1-20.0 [82.69-78.79]	20.0-31.5 [78.79-67.29]	21.35-31.35 [77.44-67.44]
MW-98-8S	98.89	0-3.0	3.0-5.0 [95.89-93.89]	5.0-8.0 [93.89-90.89]	8.0-21.0 [90.89-77.89]	10.0-20.0 [88.89-78.89]
MW-98-8D	98.68	0-3.0	3.0-20.0 [95.68-78.68]	20.0-23.0 [78.68-75.68]	23.0-35.3 [75.68-63.38]	25.0-35.0 [73.68-63.68]
MW-98-9D	97.54	0-3.0	3.0-23.0 [94.54-74.54]	23.0-26.0 [74.54-71.54]	26.0-37.1 [71.54-60.44]	27.0-37.0 [70.54-60.54]
MW-98-10D	98.75	0-3.0	3.0-23.0 [95.75-75.75]	23.0-26.0 [75.75-72.75]	26.0-37.1 [72.75-61.65]	27.0-37.0 [71.75-61.75]
MW-00-11A	97.89	0-3.0	3.0-45.0 [94.89-52.89]	45.0-48.5 [52.89-49.39]	48.5-61.5 [49.39-36.39]	51.0-61.0 [46.89-36.89]
MW-00-12D	98.60	0-3.0	3.0-19.0 [95.60-79.60]	19.0-22.5 [79.60-76.10]	22.50-38.0 [79.60-60.60]	25.0-35.0 [73.60-63.60]
MW-03-13S	98.05	0-3.0	3.0-5.0 [95.05-93.05]	5.0-8.0 [93.05-90.05]	8.0-25.5 [90.05-72.55]	10.0-25.0 [88.05-73.05]

Note:

Elevations based on a benchmark established by Rust E&I at utility pole F34, assumed site datum = 100.00
 Survey of monitoring well MW-03-13S was performed by Donald Stedje, L.S. of Central Valley, New York on June 26, 2003

Table 5

Volatile Organic Analytical Data Summary - Soil Borings
 Former Columbia Cement Company, Inc. Facility
 Freeport, New York

Sampling Dates: December 1998 (MW-00-11 and MW-00-12 April 2000)

Sample ID	SB-98-2 (10-13.7') Fill	SB-98-2 (15.1-15.67') Fill/Tp Gr/Snd	SB-98-2 (34.0-34.5') Gr Clay/Silt	SB-98-3 (18-19.35') Fill	X-1 SB-98-3 (18-19.35') Tidal Marsh	SB-98-3 (19.35-19.58') Gr Clay/Silt	SB-98-3 (35.67-36') Gr Clay/Silt	SB-98-4 (10-12') Fill	SB-98-4 (10-12') Fill	SITE SPECIFIC RSOC
Compound	7,000,000 D	38,000	20	1,200,000 D	1,800,000 D	810,000 D	9 J	430 D	1,049	
1,1,1-Trichloroethane	240,000 U	2,400 U	10 U	48,000 U	96,000 U	2,400 U	10 U	10 U	10 U	NA
1,1,2,2-Tetrachloroethane	240,000 U	320 J	10 U	48,000 U	96,000 U	2,400 U	10 U	10 U	10 U	386
1,1,2-Trichloroethane	71,000 J	400 J	3 J	17,000 J	96,000 U	120,000 D	1 J	360 D	207	
1,1-Dichloroethane	240,000 U	2,400 U	10 U	48,000 U	96,000 U	1,100 J	10 U	6 J	449	
1,1-Dichloroethylene	240,000 U	2,400 U	10 U	48,000 U	96,000 U	2,400 U	10 U	10 U	10 U	NA
1,2-Dichloroethane	240,000 U	2,400 U	10 U	48,000 U	96,000 U	2,400 U	10 U	10 U	10 U	NA
1,2-Dichloroethylene (total)	240,000 U	2,400 U	10 U	48,000 U	96,000 U	2,400 U	10 U	10 U	10 U	NA
1,2-Dichloropropane	240,000 U	2,400 U	10 U	48,000 U	96,000 U	2,400 U	10 U	10 U	10 U	NA
2-Butanone	240,000 U	2,400 U	4 J	48,000 U	96,000 U	2,400 U	6 J	84	311	
2-Hexanone	240,000 U	2,400 U	10 U	48,000 U	96,000 U	2,400 U	10 U	10 U	10 U	1,587
4-Methyl-2-Pentanone	240,000 U	2,400 U	10 U	48,000 U	96,000 U	2,400 U	10 U	10 U	10 U	1,311
Acetone	240,000 U	2,400 U	27	48,000 U	96,000 U	2,400 U	31	570 D	152	
Benzene	240,000 U	2,400 U	10 U	48,000 U	96,000 U	2,400 U	10 U	52	115	
Bromodichloromethane	240,000 U	2,400 U	10 U	48,000 U	96,000 U	2,400 U	10 U	10 U	10 U	NA
Bromoform	240,000 U	460 J	10 U	48,000 U	96,000 U	2,400 U	10 U	10 U	10 U	366
Bromomethane	240,000 U	2,400 U	10 U	48,000 U	96,000 U	2,400 U	10 U	10 U	10 U	NA
Carbon Disulfide	240,000 U	2,400 U	10 U	48,000 U	96,000 U	2,400 U	10 U	10 U	10 U	3,726
Carbon Tetrachloride	240,000 U	2,400 U	10 U	48,000 U	96,000 U	2,400 U	10 U	10 U	10 U	NA
Chlorobenzene	240,000 U	2,400 U	10 U	48,000 U	96,000 U	2,400 U	10 U	10 U	10 U	NA
Chloroethane	240,000 U	2,400 U	4 J	48,000 U	96,000 U	2,400 U	10 U	10 U	10 U	NA
Chloroform	240,000 U	2,400 U	10 U	48,000 U	96,000 U	2,400 U	10 U	10 U	10 U	1,600 D
Chloromethane	240,000 U	2,400 U	10 U	48,000 U	96,000 U	2,400 U	10 U	10 U	10 U	299
cis-1,3-Dichloropropene	240,000 U	2,400 U	10 U	48,000 U	96,000 U	2,400 U	10 U	10 U	10 U	NA
Dibromochloromethane	240,000 U	2,400 U	10 U	48,000 U	96,000 U	2,400 U	10 U	10 U	10 U	NA
Ethylbenzene	250,000	2,400 U	10 U	48,000 U	96,000 U	2,400 U	10 U	13	7,590	
Methylene Chloride	240,000 U	2,400 U	10 U	48,000 U	96,000 U	2,400 U	10 U	23	145	
Styrene	240,000 U	2,400 U	10 U	48,000 U	96,000 U	2,400 U	10 U	10 U	10 U	6,348
Tetrachloroethene	240,000 U	2,400 U	10 U	48,000 U	96,000 U	450 J	10 U	50	1,911	
Toluene	660,000	820 J	10 U	48,000 U	96,000 U	8,200	10 U	10 U	2,070	
trans-1,3-Dichloropropene	240,000 U	2,400 U	10 U	48,000 U	96,000 U	2,400 U	10 U	10 U	10 U	NA
Trichloroethene	240,000 U	2,400 U	10 U	48,000 U	96,000 U	350 J	10 U	10 U	10 U	869
Vinyl Chloride	240,000 U	2,400 U	10 U	48,000 U	96,000 U	2,400 U	10 U	10 U	10 U	157
Xylene (total)	1,500,000	420 J	10 U	48,000 U	96,000 U	400 J	10 U	34	1,656	

Figure 5

Volatile Organic Analytical Data Summary - Soil Borings
 Former Columbia Cement Company, Inc. Facility
 Freeport, New York

Sampling Dates: December 1998 (MW-00-11 and MW-00-12 April 2000)

Sample ID	SB-98-4 (14.55-16') Fill/Gr. Snd	SB-98-4 (28-30') Gr. Snd	SB-98-4 (35.16-36') Gr. Clay/Silt	SB-98-5 (8-10') Fill	SB-98-7 (8-10') Fill	BSB-98-7 (11.35-13.63') Tidal Marsh	BSB-98-7 (28-30') Gr. Snd	BSB-98-7 (34.55-36') Gr. Clay/Silt	SITE SPECIFIC RSCo
1,1,1-Trichloroethane	67	3 J	28	75	10 U	10 U	10 U	10 U	1,049
1,1,2,2-Tetrachloroethane	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	NA
1,1,2-Trichloroethane	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	386
1,1-Dichloroethane	2 J	10 U	3 J	5 J	10 U	10 U	10 U	10 U	207
1,1-Dichloroethene	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	449
1,2-Dichloroethane	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	NA
1,2-Dichloroethene (total)	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	NA
1,2-Dichloropropane	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	NA
2-Butanone	10	5 J	10 U	34	4 J	2 J	8 J	311	
2-Hexanone	10 U	6 J	10 U	10 U	10 U	10 U	10 U	10 U	1,587
4-Methyl-2-Pentanone	10 U	10	10 U	10 U	10 U	10 U	10 U	10 U	1,311
Acetone	42	42	65	55	210	62	24	36	152
Benzene	2 J	10 U	10 U	5 J	10 U	10 U	10 U	10 U	115
Bromodichloromethane	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	NA
Bromoform	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	366
Bromomethane	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	NA
Carbon Disulfide	10 U	10 U	10 U	10 U	10 U	2 J	10 U	10 U	3,726
Carbon Tetrachloride	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	NA
Chlorobenzene	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	NA
Chloroethane	4 J	10 U	2 J	10 U	10 U	10 U	10 U	10 U	255
Chloroform	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	299
Chloromethane	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	NA
cis-1,3-Dichloropropene	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	NA
Dibromochloromethane	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	NA
Ethylbenzene	10 U	10 U	10 U	3 J	10 U	10 U	10 U	10 U	7,590
Methylene Chloride	10 U	2 J	2 J	17	10	2 J	9 J	145	
Styrene	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	6,348
Tetrachloroethene	10 U	10 U	10 U	5 J	10 U	10 U	10 U	10 U	1,911
Toluene	10	10 U	10 U	32	10 U	10 U	10 U	10 U	2,070
trans-1,3-Dichloropropene	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	NA
Trichloroethene	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	869
Vinyl Chloride	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	157
Xylene (total)	4 J	10 U	10 U	22	10 U	10 U	10 U	10 U	1,656

Table 5

Volatile Organic Analytical Data Summary - Soil Borings
Former Columbia Cement Company, Inc. Facility
Freeport, New York

Sampling Dates: December 1998 (MW-00-11 and MW-00-12 April 2000)

Sample ID	MW-98-8D (4-6') Rill	MW-98-8D (7.7-8') Tidal Marsh	MW-98-8D (34.75-36') Gr Clay/Silt	MW-98-9D (6.1-6.5') Tidal Marsh	MW-98-9D (12-14') TM/Gr Snd	MW-98-9D (9.85-10.2') Gr Clay/Silt	MW-98-10D (12-14') Gr Snd	MW-98-10D (37.1-38') Gr Clay/Silt	SITE SPECIFIC RSCO
1,1,1-Trichloroethane	22	10 U	10 U	10 U	10 U	10 U	10 U	10 U	1,049
1,1,2,2-Tetrachloroethane	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	NA
1,1,2-Trichloroethane	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	386
1,1-Dichloroethane	2 J	10 U	10 U	10 U	10 U	10 U	10 U	10 U	207
1,1-Dichloroethene	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	449
1,2-Dichloroethane	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	NA
1,2-Dichloroethylene (total)	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	NA
1,2-Dichloropropane	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	NA
2-Butanone	19	10 U	15	10 U	10 U	10 U	10 U	7 J	10 U
2-Hexanone	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	311
4-Methyl-2-Pentanone	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	1,587
Acetone	13	78	14	80	26	36	33	11	1,311
Benzene	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	152
Bromodichloromethane	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	115
Bromoform	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	NA
Bromomethane	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	366
Carbon Disulfide	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	NA
Carbon Tetrachloride	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	3,726
Chlorobenzene	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	NA
Chloroethane	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	NA
Chloroform	10 U	17	10 U	10 U	10 U	10 U	10 U	10 U	255
Chloromethane	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	299
cis-1,3-Dichloropropene	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	NA
Dibromochloromethane	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	6,348
Ethylbenzene	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	1,911
Methylene Chloride	3 J	10 U	10 U	10 U	10 U	10 U	10 U	10 U	7,590
Styrene	10 U	9 J	10 U	10 U	10 U	10 U	10 U	10 U	145
Tetrachloroethene	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	NA
Toluene	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	2,070
trans-1,3-Dichloropropene	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	NA
Trichloroethene	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	869
Vinyl Chloride	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	157
Xylene (total)	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	1,656

Volatile Organic Analytical Data Summary - Soil Borings
 Former Columbia Cement Company, Inc. Facility
 Freeport, New York

Sampling Dates: December 1998 (MW-00-11 and MW-00-12 April 2000)

Sample ID	MW-00-12D (8.0-8.5') Fill	MW-00-12D (8.5-10') Fill	MW-00-12D (34.7-36') Fill	MW-00-11A (1-2') Fill	MW-00-11A (2-4') Fill	MW-00-11A (4-6') Fill	MW-00-11A (6-8') Fill	MW-00-11A (8-10') Fill	MW-00-11A (10-12') Fill	SITE SPECIFIC RSCO
1,1,1-Trichloroethane	10 J	10 U	6 U	100 U	6 U	6 U	210 U	135 U	40000 U	66000 U
1,1,2,2-Tetrachloroethane	12 U	10 U	6 U	6 U	6 U	6 U	120 U	64 U	1500 U	3000 U
1,1,2-Trichloroethane	12 U	10 U	6 U	6 U	6 U	6 U	60 U	64 U	1500 U	3000 U
1,1-Dichloroethane	10 J	10 U	6 U	13 U	8 U	6 U	63 U	58 JD	3400 U	3400 U
1,1-Dichloroethene	12 U	10 U	6 U	6 U	6 U	6 U	60 U	64 U	1500 U	3000 U
1,2-Dichloroethane	12 U	10 U	6 U	6 U	6 U	6 U	60 U	64 U	1500 U	3000 U
1,2-Dichloropropane	12 U	10 U	6 U	12 U	12 U	12 U	60 U	64 U	1500 U	3000 U
2-Butanone-(MEK)	49 J	19 U	13 U	13 U	12 U	12 U	120 U	200 U	3000 U	6000 U
2-Hexanone	23 U	19 U	13 U	13 U	12 U	12 U	120 U	130 U	3000 U	6000 U
4-Methyl-2-Pentanone (MIBK)	23 U	19 U	13 U	13 U	12 U	12 U	120 U	130 U	3000 U	6000 U
Acetone	210 UB	19 U	22 U	84 U	140 U	420 U	810 U	2300 JD	3300 JD	1,587
Benzene	4 J	2 J	1 J	6 U	6 U	4 J	17 JD	64 U	1500 U	3000 U
Bromodichloromethane	12 U	10 U	6 U	6 U	6 U	6 U	60 U	64 U	1500 U	3000 U
Bromoform	12 U	10 U	6 U	6 U	6 U	6 U	60 U	64 U	1500 U	3000 U
Bromomethane	23 U	19 U	13 U	12 U	12 U	12 U	120 U	130 U	3000 U	6000 U
Carbon Disulfide	12 U	10 U	6 U	6 U	3 J	2 J	27 JD	64 U	1500 U	3000 U
Carbon Tetrachloride	12 U	10 U	6 U	6 U	6 U	6 U	60 U	64 U	1500 U	3000 U
Chlorobenzene	12 U	10 U	6 U	6 U	6 U	6 U	60 U	64 U	1500 U	3000 U
Chloroethane	14 J	19 U	2 U	5 J	12 U	5 J	48 JD	130 U	3000 U	6000 U
Chloroform	5 J	10 U	6 U	6 U	9 J	7 J	60 U	64 U	1500 U	3000 U
Chloromethane	23 U	19 U	13 U	12 U	12 U	12 U	120 U	130 U	3000 U	6000 U
cis-1,2-Dichloroethene	12 U	10 U	6 U	6 U	6 U	6 U	60 U	64 U	1500 U	3000 U
cis-1,3-Dichloropropene	12 U	10 U	6 U	6 U	6 U	6 U	60 U	64 U	1500 U	3000 U
Dibromochloromethane	12 U	10 U	6 U	6 U	6 U	6 U	60 U	64 U	1500 U	3000 U
Ethylbenzene	12 U	10 U	6 U	6 U	6 U	6 U	60 U	64 U	1500 U	3000 U
Methylene Chloride	25 U	10 U	7 U	20 U	17 U	170 U	150 U	5500 U	4900 U	2,070
Styrene	12 U	10 U	6 U	6 U	6 U	6 U	60 U	64 U	1500 U	3000 U
Tetrachloroethene	12 U	10 U	13 U	2 J	1 J	1 J	60 U	64 U	350 JD	3000 U
Toluene	3 J	10 U	6 U	7 U	10 U	33 JD	48 JD	1500 JD	1400 JD	1,911
trans-1,2-Dichloroethene	12 U	10 U	6 U	6 U	6 U	6 U	60 U	64 U	1500 U	3000 U
trans-1,3-Dichloropropene	12 U	10 U	6 U	6 U	6 U	6 U	60 U	64 U	1500 U	3000 U
Trichloroethene	12 U	10 U	6 U	6 U	6 U	6 U	60 U	64 U	1500 U	3000 U
Vinyl Chloride	23 U	19 U	13 U	12 U	12 U	12 U	120 U	130 U	3000 U	6000 U
Xylene (total)	12 U	10 U	6 U	6 U	6 U	6 U	60 U	64 U	400 JD	3000 U

Table 5

Volatile Organic Analytical Data Summary - Soil Borings
 Former Columbia Cement Company, Inc. Facility
 Freeport, New York

Sampling Dates: December 1998 (MW-00-11 and MW-00-12 April 2000)

Sample ID	MW-00-11A (12-14') Fill	MW-00-11A (14-16') Fill	MW-00-11A (16-18') Fill	MW-00-11A (18-20') Fill/Gr Snd	MW-00-11A (22-24') Gr Snd	MW-00-11A (24-26') Gr Snd	MW-00-11A (26-28') Gr Snd	MW-00-11A (28-30') Gr Snd	MW-00-11A (30-32') Gr Snd	SITE SPECIFIC RSCO
1,1,1-Trichloroethane	1100000	U	8300000	2600000	910000	8	6	U	6	J
1,1,2,2-Tetrachloroethane	3200	U	42000	U	31000	U	6	U	6	NA
1,1,2-Trichloroethane	3200	U	42000	U	31000	U	6	U	6	386
1,1-Dichloroethane	1600	JD	42000	U	31000	U	6	U	6	207
1,1-Dichloroethene	3200	U	42000	U	31000	U	6	U	6	449
1,2-Dichloroethane	3200	U	42000	U	31000	U	6	U	6	NA
1,2-Dichloropropane	3200	U	42000	U	31000	U	6	U	6	NA
2-Butanone-(MEK)	6400	U	84000	U	150000	U	62000	U	12	NA
2-Hexanone	6400	U	84000	U	150000	U	62000	U	13	NA
4-Methyl-2-Pentanone (MIBK)	6400	U	84000	U	150000	U	62000	U	12	12
Acetone	3500	JD	31000	JD	17000	U	12	U	12	1,587
Benzene	3200	U	42000	U	77000	U	31000	U	6	1,311
Bromodichloromethane	3200	U	42000	U	77000	U	31000	U	6	152
Bromoform	3200	U	42000	U	77000	U	31000	U	6	311
Bromomethane	6400	U	84000	U	150000	U	62000	U	12	1,587
Carbon Disulfide	3200	U	42000	U	77000	U	31000	U	6	NA
Carbon Tetrachloride	3200	U	42000	U	77000	U	31000	U	6	NA
Chlorobenzene	3200	U	42000	U	77000	U	31000	U	6	115
Chloroethane	1100	JD	84000	U	150000	U	62000	U	12	NA
Chloroform	3200	U	42000	U	77000	U	31000	U	6	366
Chloromethane	6400	U	84000	U	150000	U	62000	U	12	NA
cis-1,2-Dichloroethylene	3200	U	42000	U	77000	U	31000	U	6	299
cis-1,3-Dichloropropene	3200	U	42000	U	77000	U	31000	U	6	NA
Dibromochloromethane	3200	U	42000	U	77000	U	31000	U	6	NA
Ethylbenzene	3200	U	42000	U	77000	U	31000	U	6	NA
Methylene Chloride	3100	JD	25000	JD	19000	U	6	U	6	7,590
Styrene	3200	U	42000	U	77000	U	31000	U	6	145
Tetrachloroethene	3200	U	42000	U	77000	U	31000	U	6	6,348
Toluene	2500	JD	42000	U	77000	U	31000	U	6	1,911
trans-1,2-Dichloroethene	3200	U	42000	U	77000	U	31000	U	6	2,070
trans-1,3-Dichloropropene	3200	U	42000	U	77000	U	31000	U	6	NA
Trichloroethene	3200	U	42000	U	77000	U	31000	U	6	869
Vinyl Chloride	6400	U	84000	U	150000	U	62000	U	12	157
Xylene (total)	3200	U	42000	U	77000	U	31000	U	12	1,656
						6	U	6	U	1,660

Figure 5

Volatile Organic Analytical Data Summary - Soil Borings
 Former Columbia Cement Company, Inc. Facility
 Freeport, New York

Sampling Dates: December 1998 (MW-00-11 and MW-00-12 April 2000)

Sample ID	MW-00-11A (32-34') Gr Snd	MW-00-11A (34-36') Gr Snd / Gr Clay/Silt	MW-00-11A (38-40') Gr Clay/Silt	MW-00-11A (40-42') Gr Clay/Silt	MW-00-11A (42-44') Gr Clay/Silt	MW-00-11A (44-46') Gr Clay/Silt	MW-00-11A (48-50') Gr Clay/Silt	MW-00-11A (50-52') Gray Sand	SITE SPECIFIC	RSCO
1,1,1-Trichloroethane	3 J	6 U	6 U	5 J	3 J	2 J	6 U	7 U	7 U	1,049
1,1,2,2-Tetrachloroethane	6 U	6 U	6 U	6 U	6 U	6 U	6 U	7 U	7 U	NA
1,1,2-Trichloroethane	6 U	6 U	6 U	6 U	6 U	6 U	6 U	7 U	7 U	386
1,1-Dichloroethane	6 U	6 U	6 U	6 U	6 U	6 U	6 U	7 U	7 U	207
1,1-Dichloroethene	6 U	6 U	6 U	6 U	6 U	6 U	6 U	7 U	7 U	449
1,2-Dichloroethane	6 U	6 U	6 U	6 U	6 U	6 U	6 U	7 U	7 U	NA
1,2-Dichloropropane	6 U	6 U	6 U	6 U	6 U	6 U	6 U	7 U	7 U	NA
2-Butanone-(MEK)	13 U	12 U	13 U	10 J	13 U	33 J	6 J	13 U	13 U	NA
2-Hexanone	13 U	12 U	13 U	13 U	13 U	13 U	13 U	13 U	13 U	311
4-Methyl-2-Pentanone (MIBK)	13 U	12 U	13 U	13 U	13 U	13 U	13 U	13 U	13 U	1,587
Acetone	13 U	25 UB	42 UB	52 UB	61 UB	140 UB	36 UB	10 J	13 U	1,311
Benzene	6 U	6 U	6 U	6 U	6 U	6 U	6 U	6 U	7 U	152
Bromodichloromethane	6 U	6 U	6 U	6 U	6 U	6 U	6 U	7 U	7 U	115
Bromoform	6 U	6 U	6 U	6 U	6 U	6 U	6 U	7 U	7 U	NA
Bromomethane	13 U	12 U	13 U	13 U	13 U	13 U	13 U	13 U	13 U	366
Carbon Disulfide	4 J	6 U	6 U	6 U	6 U	6 U	6 U	7 U	7 U	NA
Carbon Tetrachloride	6 U	6 U	6 U	6 U	6 U	6 U	6 U	7 U	7 U	255
Chlorobenzene	6 U	6 U	6 U	6 U	6 U	6 U	6 U	7 U	7 U	299
Chloroethane	13 U	12 U	13 U	13 U	13 U	13 U	13 U	13 U	13 U	NA
Chloroform	6 U	6 U	6 U	6 U	2 J	3 J	5 J	2 J	7 U	NA
Chloromethane	13 U	12 U	13 U	13 U	13 U	13 U	13 U	13 U	13 U	7,590
cis-1,2-Dichloroethylene	6 U	6 U	6 U	6 U	6 U	6 U	6 U	7 U	7 U	NA
cis-1,3-Dichloropropene	6 U	6 U	6 U	6 U	6 U	6 U	6 U	7 U	7 U	145
Dibromochloromethane	6 U	6 U	6 U	6 U	6 U	6 U	6 U	7 U	7 U	6,348
Ethylbenzene	6 U	6 U	6 U	6 U	6 U	6 U	6 U	7 U	7 U	1,911
Methylene Chloride	6 U	6 U	6 U	6 U	6 U	6 U	6 U	7 U	7 U	2,070
Styrene	6 U	6 U	6 U	6 U	6 U	9 U	15 UB	8 U	7 U	NA
Tetrachloroethene	6 U	6 U	6 U	6 U	6 U	6 U	6 U	7 U	7 U	869
Toluene	6 U	6 U	6 U	6 U	6 U	6 U	6 U	7 U	7 U	157
trans-1,2-Dichloroethene	6 U	6 U	6 U	6 U	6 U	2 J	6 U	7 U	7 U	NA
trans-1,3-Dichloropropene	6 U	6 U	6 U	6 U	6 U	6 U	6 U	7 U	7 U	1,656
Vinyl Chloride	13 U	12 U	13 U	13 U	13 U	13 U	13 U	13 U	13 U	1,660
Xylene (total)	6 U	6 U	6 U	6 U	6 U	6 U	6 U	7 U	7 U	

Table 5

Volatile Organic Analytical Data Summary - Soil Borings
 Former Columbia Cement Company, Inc. Facility
 Freeport, New York

Sampling Dates: December 1998 (MW-00-11 and MW-00-12 April 2000)

Sample ID	MW-00-11A (54-56') Gray Sand	MW-00-11A (56-58') Gray Sand	MW-00-11A (58-60') Gray Sand	SITE SPECIFIC RSCO
Compound				
1,1,1-Trichloroethane	5	U	6	U
1,1,2,2-Tetrachloroethane	5	U	6	U
1,1,2-Trichloroethane	5	U	6	U
1,1-Dichloroethane	5	U	6	U
1,1-Dichloroethene	5	U	6	U
1,2-Dichloroethane	5	U	6	U
1,2-Dichloropropane	5	U	6	U
2-Butanone-(MEK)	10	U	13	U
2-Hexanone	10	U	13	U
4-Methyl-2-Pentanone (MIBK)	10	U	13	U
Acetone	15	U	13	U
Benzene	5	U	6	U
Bromodichloromethane	5	U	6	U
Bromoform	5	U	6	U
Bromomethane	10	U	13	U
Carbon Disulfide	5	U	6	U
Carbon Tetrachloride	5	U	6	U
Chlorobenzene	5	U	6	U
Chloroethane	10	U	13	U
Chloroform	5	U	6	U
Chloromethane	10	U	13	U
cis-1,2-Dichloroethylene	5	U	6	U
cis-1,3-Dichloropropene	5	U	6	U
Dibromochloromethane	5	U	6	U
Ethylbenzene	5	U	6	U
Methylene Chloride	5	U	4	U
Styrene	5	U	6	U
Tetrachloroethene	5	U	6	U
Toluene	5	U	6	U
trans-1,2-Dichloroethene	5	U	6	U
trans-1,3-Dichloropropene	5	U	6	U
Trichloroethene	5	U	6	U
Vinyl Chloride	10	U	13	U
Xylene (total)	5	U	6	U

All results expressed in ug/Kg.

Concentration in bold exceeds the RSCO (Based on Site Specific Organic Carbon Content of 1.38 percent).

U-indicates not detected at or above the listed concentration.

J- indicates estimated concentration below the contract required reporting limit but above the instrument detection limit.

D- indicates sample was diluted prior to analysis.

Gr Sand - indicates Gravely Sand Unit and Gr Clay/Silt indicated Gray Clay and Silt Unit

Table 6

Semivolatile Organic Analytical Data Summary - Soil Borings
 Former Columbia Cement Company, Inc. Facility
 Freeport, New York

Sampling Dates: December 15, 16, 22 and 23, 1998

Compound	Sample ID	SB-98-2 (10-13.7') Fill	SB-98-4 (28-30') Gr Sand	SB-98-3 (18-19.35') Fill	X-1 SB-98-3 (18-19.35')	BSB-98-7 (8-10') Fill	BSB-98-7 (11-13.63') Tidal Marsh	BSB-98-7 (34.55-36') Gr Clay/Silt	MW-98-8D (4-6') Fill	SITE SPECIFIC RSCO
Phenol	380 U	380 U	380 U	340 J	410 U	510 U	640 U	420 U	440 U	37.26
bis(2-Chloroethyl)Ether	380 U	380 U	380 U	450 U	410 U	510 U	640 U	420 U	440 U	
2-Chlorophenol	380 U	380 U	380 U	450 U	410 U	510 U	640 U	420 U	440 U	
1,3-Dichlorobenzene	380 U	380 U	380 U	450 U	410 U	510 U	640 U	420 U	440 U	
1,4-Dichlorobenzene	380 U	230 J	450 U	410 U	510 U	640 U	420 U	420 U	440 U	11,730
1,2-Dichlorobenzene	380 U	380 U	450 U	410 U	510 U	640 U	420 U	420 U	440 U	
2-Methylphenol	380 U	380 U	450 U	410 U	510 U	640 U	420 U	420 U	440 U	
2,2'-oxybis(1-Chloropropane)	380 U	380 U	450 U	410 U	510 U	640 U	420 U	420 U	440 U	
4-Methylphenol	380 U	380 U	450 U	410 U	89 J	510 U	640 U	420 U	440 U	
N-Nitroso-di-n-propylamine	380 U	380 U	450 U	410 U	510 U	640 U	420 U	420 U	440 U	
Hexachloroethane	380 U	380 U	450 U	410 U	510 U	640 U	420 U	420 U	440 U	
Nitrobenzene	380 U	380 U	450 U	410 U	510 U	640 U	420 U	420 U	440 U	
Isophorone	380 U	380 U	450 U	410 U	510 U	640 U	420 U	420 U	440 U	
2-Nitrophenol	380 U	380 U	450 U	410 U	510 U	640 U	420 U	420 U	440 U	
2,4-Dimethylphenol	380 U	380 U	450 U	410 U	510 U	640 U	420 U	420 U	440 U	
2,4-Dichlorophenol	380 U	380 U	450 U	410 U	510 U	640 U	420 U	420 U	440 U	
1,2,4-Trichlorobenzene	380 U	380 U	450 U	410 U	510 U	640 U	420 U	420 U	440 U	
Naphthalene	660	380 U	1300	720	510 U	640 U	420 U	420 U	440 U	17,940
4-Chloraniline	380 U	380 U	450 U	410 U	510 U	640 U	420 U	420 U	440 U	
Hexachlorobutadiene	380 U	380 U	450 U	410 U	510 U	640 U	420 U	420 U	440 U	
bis(2-Chloroethoxy)methane	380 U	380 U	450 U	410 U	510 U	640 U	420 U	420 U	440 U	
4-Chloro-3-Methylphenol	380 U	380 U	980	410 U	510 U	640 U	420 U	420 U	440 U	324
2-MethylNaphthalene	360 J	380 U	450 U	320 J	510 U	640 U	420 U	420 U	440 U	50,000
Hexachlorocyclopentadiene	380 U	380 U	450 U	410 U	510 U	640 U	420 U	420 U	440 U	
2,4,6-Trichlorophenol	380 U	380 U	450 U	410 U	510 U	640 U	420 U	420 U	440 U	
2,4,5-Trichlorophenol	930 U	920 U	1100 U	990 U	1200 U	1500 U	1000 U	1100 U	1100 U	
2-Chloronaphthalene	380 U	380 U	450 U	410 U	510 U	640 U	420 U	420 U	440 U	
2-Nitroaniline	930 U	920 U	1100 U	990 U	1200 U	1500 U	1000 U	1100 U	1100 U	
Dimethylphthalate	380 U	380 U	450 U	410 U	510 U	640 U	420 U	420 U	440 U	
Acenaphthylene	380 U	380 U	450 U	410 U	510 U	640 U	420 U	420 U	440 U	
2,6-Dinitrotoluene	380 U	380 U	450 U	410 U	510 U	640 U	420 U	420 U	440 U	
3-Nitroaniline	930 U	920 U	1100 U	990 U	1200 U	1500 U	1000 U	1100 U	1100 U	
Acenaphthene	240 J	380 U	740	410 U	510 U	640 U	420 U	420 U	440 U	50,000
2,4-Dinitrophenol	930 U	920 U	1100 U	990 U	1200 U	1500 U	1000 U	1100 U	1100 U	
4-Nitrophenol	930 U	380 U	1100 U	990 U	1200 U	1500 U	1000 U	1100 U	1100 U	
Dibenzofuran	380 U	380 U	450 U	410 U	510 U	640 U	420 U	420 U	440 U	8,478
2,4-Dinitrotoluene	380 U	380 U	450 U	410 U	510 U	640 U	420 U	420 U	440 U	

File 6

Semivolatile Organic Analytical Data Summary - Soil Borings
Former Columbia Cement Company, Inc. Facility
Freeport, New York

Sampling Dates: December 15, 16, 22 and 23, 1998

Compound	Sample ID	SB-98-2 (10-13.7) Fill	SB-98-4 (28-30') Gr Snd	SB-98-3 (18-19.35') Fill	X-1 SB-98-3 (18-19.35') SB-98-3 (18-19.35')	BSB-98-7 (8-10') Fill	BSB-98-7 (11-13.63') Tidal Marsh	BSB-98-7 (34.55-36') Gr Clay/Silt	MW-98-8D (4-6') Fill	SITE SPECIFIC RSCO
Diethylphthalate	380 U	380 U	450 U	410 U	510 U	640 U	420 U	420 U	440 U	
4-Chlorophenyl-phenylether	380 U	380 U	450 U	410 U	510 U	640 U	420 U	420 U	440 U	
Fluorene	380 J	380 U	450 U	130 J	510 U	640 U	420 U	420 U	200 J	
4-Nitroaniline	930 U	920 U	1100 U	990 U	1200 U	1500 U	1000 U	1000 U	1100 U	50,000
4,6-Dinitro-2-methylphenol	930 U	920 U	1100 U	990 U	1200 U	1500 U	1000 U	1000 U	1100 U	
N-Nitrosodiphenylamine	380 U	380 U	450 U	410 U	510 U	640 U	420 U	420 U	440 U	
4-Bromophenyl-phenylether	380 U	380 U	450 U	410 U	510 U	640 U	420 U	420 U	440 U	
Hexachlorobenzene	380 U	380 U	450 U	410 U	510 U	640 U	420 U	420 U	440 U	
Penta-chlorophenol	930 U	380 U	1100 U	990 U	1200 U	1500 U	1000 U	1000 U	1100 U	
Phenanthrene	5300	380 U	4200	700	330 J	170 J	420 U	420 U	830	50,000
Anthracene	210 J	380 U	450 U	410 U	510 U	640 U	420 U	420 U	260 J	50,000
Carbazole	380 U	380 U	450 U	410 U	510 U	640 U	420 U	420 U	440 U	
Di-n-butylphthalate	2900	1800	520	660	80 J	640 U	420 U	420 U	440 U	
Fluoranthene	3600	380 U	2500	420	700	480 J	130 J	130 J	890	50,000
Pyrene	560	380 U	920	160 J	720	450 J	420 U	420 U	570	50,000
Butylbenzylphthalate	380 U	380 U	450 U	520	510 U	640 U	420 U	420 U	100 J	50,000
3,3'-Dichlorobenzidine	380 U	380 U	450 U	410 U	510 U	640 U	420 U	420 U	440 U	
Benz(a)anthracene	380 U	380 U	450 U	410 U	510 U	640 U	420 U	420 U	440 U	
Chrysene	2200	380 U	450 U	410 U	480 J	640 U	420 U	420 U	440 U	
bis(2-Ethylhexyl)phthalate	56,000 D	340 J	20,000 E	74,000 D	96,000 D	1,800	180 J	180 J	1,400	50,000
Di-n-octylphthalate	6200	380 U	1300	2,800	410 J	640 U	420 U	420 U	440 U	
Benz(b)fluoranthene	380 U	380 U	450 U	410 U	510 U	640 U	420 U	420 U	440 U	
Benz(k)fluoranthene	380 U	380 U	450 U	410 U	510 U	640 U	420 U	420 U	440 U	
Benz(a)pyrene	380 U	380 U	450 U	410 U	510 U	640 U	420 U	420 U	440 U	
Indeno(1,2,3-cd)pyrene	380 U	380 U	450 U	410 U	510 U	640 U	420 U	420 U	440 U	
Dibenz(a,h)anthracene	380 U	380 U	450 U	410 U	510 U	640 U	420 U	420 U	440 U	
Benzo(g,h,i)perylene	380 U	380 U	450 U	410 U	510 U	640 U	420 U	420 U	440 U	

All results expressed in ug/Kg.

Concentration in bold exceeds the RSCO (Based on Site Specific Organic Carbon Content of 1.38 percent).

U-indicates not detected at or above the listed concentration.

J- indicates estimated concentration below the contract required reporting limit but above the instrument detection limit.

D- indicates sample was diluted prior to analysis.

E- indicates estimated value, concentration exceeded the instrument calibration range.

Table 7
Pesticide/PCB Analytical Data Summary - Soil Borings
Former Columbia Cement Company, Inc. Facility
Freeport, New York

Sampling Dates: December 15, 16, 22 and 23, 1998

Compound	Sample ID	SB-98-2 (10-13.7')	SB-98-4 (28-30')	SB-98-3 (18-19.35')	X-1 SB-98-3 (18-19.35')	BSB-98-7 (8-10')	BSB-98-7 (11.35-13.63')	BSB-98-7 (34.55-36')	MW-98-8D (4-6')	SITE SPECIFIC RSCO
alpha-BHC	2.0 U	0.05 U	2.3 U	2.1 U	2.6 U	3.3 U	2.2 U	2.2 U	2.3 U	
beta-BHC	2.0 U	0.05 U	2.3 U	2.1 U	2.6 U	3.3 U	2.2 U	2.2 U	2.3 U	
delta-BHC	2.0 U	0.05 U	2.3 U	2.1 U	2.6 U	3.3 U	2.2 U	2.2 U	2.3 U	
gamma-BHC (Lindane)	2.0 U	0.05 U	2.3 U	2.1 U	2.6 U	3.3 U	2.2 U	2.2 U	2.3 U	
Heptachlor	2.0 U	0.05 U	2.3 U	2.1 U	2.6 U	3.3 U	2.2 U	2.2 U	2.3 U	
Aldrin	2.0 U	0.05 U	2.3 U	2.1 U	2.6 U	3.3 U	2.2 U	2.2 U	2.3 U	
Heptachlor epoxide	2.0 U	0.05 U	2.3 U	2.1 U	2.6 U	3.3 U	2.2 U	2.2 U	2.3 U	
Endosulfan I	2.0 U	0.05 U	2.3 U	2.1 U	2.6 U	3.3 U	2.2 U	2.2 U	2.3 U	
Dieldrin	3.8 U	0.1 U	4.5 U	4.1 U	6.0	6.4 U	4.2 U	4.2 U	4.4 U	44
4,4'-DDDE	3.8 U	0.1 U	4.5 U	4.1 U	5.1 U	6.4 U	4.2 U	4.2 U	4.4 U	
Endrin	3.8 U	0.1 U	4.5 U	4.1 U	5.1 U	6.4 U	4.2 U	4.2 U	4.4 U	
Endosulfan II	3.8 U	0.1 U	4.5 U	4.1 U	5.1 U	6.4 U	4.2 U	4.2 U	4.4 U	
4,4'-DDD	3.8 U	0.1 U	4.5 U	4.1 U	5.1 U	6.4 U	4.2 U	4.2 U	4.4 U	
Endosulfan sulfate	3.8 U	0.1 U	4.5 U	4.1 U	5.1 U	6.4 U	4.2 U	4.2 U	4.4 U	
4,4'-DDT	210	0.1 U	4.5 U	4.1 U	5.1 U	6.4 U	4.2 U	4.2 U	4.4 U	
Methoxychlor	20 U	10 U	23 U	21 U	26 U	33 U	22 U	22 U	8.6 J	2,100
Endrin ketone	3.8 U	0.1 U	4.5 U	4.1 U	5.1 U	6.4 U	4.2 U	4.2 U	4.4 U	10,000
Endrin aldehyde	3.8 U	0.1 U	4.5 U	4.1 U	5.1 U	6.4 U	4.2 U	4.2 U	4.4 U	2,900
alpha-Chlordane	2.0 U	0.05 U	2.3 U	2.1 U	2.6 U	3.3 U	2.2 U	2.2 U	2.3 U	
gamma-Chlordane	2.0 U	0.05 U	20 P	2.1 U	2.6 U	3.3 U	2.2 U	2.2 U	2.3 U	
Toxaphene	200 U	100 U	230 U	210 U	260 U	330 U	220 U	220 U	230 U	
Aroclor-1016	38 U	1 U	45 U	41 U	51 U	64 U	42 U	42 U	44 U	
Aroclor-1221	78 U	2 U	91 U	83 U	100 U	130 U	85 U	90 U		
Aroclor-1232	38 U	1 U	45 U	41 U	51 U	64 U	42 U	42 U	44 U	
Aroclor-1242	38 U	1 U	45 U	41 U	51 U	64 U	42 U	42 U	44 U	
Aroclor-1248	38 U	1 U	45 U	41 U	51 U	64 U	42 U	42 U	44 U	
Aroclor-1254	38 U	1 U	45 U	41 U	51 U	64 U	42 U	42 U	44 U	
Aroclor-1260	38 U	1 U	45 U	41 U	51 U	64 U	42 U	42 U	44 U	

All results expressed in ug/Kg.

U-indicates not detected at or above the listed concentration.

J- indicates estimated concentration below the contract required reporting limit but above the instrument detection limit.
Concentration in bold exceeds the RSCO (Based on Site Specific Organic Carbon Content of 1.38 percent).

Table 8

Inorganic Analytical Data Summary - Soil Borings
Former Columbia Cement Company, Inc. Facility
Freeport, New York

Sampling Dates: December 15, 16, 22 and 23, 1998

Sample ID	SB-98-2 Fill (10-13.7')	SB-98-3 Fill (18-19.35')	X-1 Fill SB-98-3 (18-19.35')	SB-98-4 Gr Sand (28-30')	BSB-98-7 Fill (8-10')	BSB-98-7 Tidal Marsh (11.35-13.63')	BSB-98-7 Gr Clay/Silt (34.55-36')	MW-98-8D Fill (4-6')	NYS RSCO
Aluminum	715	1100	585	2280	6070	11600	8270	8350	SB
Antimony	0.85 U	34.7	97.6	0.87 U	22.7	3.9	0.09 U	33.2	SB
Arsenic	0.8	3.2	0.46 U	0.07 U	28.9	15.3	12.2	6.6	7.5 or SB
Barium	21.2	52.7	45.3	9.3	954	119	21.3	707	300 or SB
Beryllium	0.11 U	0.12 U	0.11 U	0.11 U	0.21 B	0.64	0.35	0.39	0.16 or SB
Cadmium	0.09 U	0.1 U	0.1 U	0.09 U	7.5	1.8	0.21	6	1 or SB
Calcium	28800	2070	3340	288	21000	2520	10000	21200	SB
Chromium	10	217	17.6	5	64	36.3	18.8	49.9	10 or SB
Cobalt	4	3.5	0.1 U	1.3 B	19.7	6.5	8.9	13.8	30 or SB
Copper	71.2	41.9	119	2.3	633	76.2	10	447	25 or SB
Iron	26100	32700	92900	3340	5200	79300	39800	63900	2,000 or SB
Lead	44.8	42.5	872	0.8	3160	230	4.6	1590	SB
Magnesium	15500	391	655	715	1910	4140	4060	2750	SB
Manganese	139	223	350	26	919	175	137	449	SB
Mercury	0.09	0.1	0.31	0.04 U	0.96	0.70	0.08	0.70	0.1
Nickel	14.4	26.5	0.21 U	2.8	82.7	19.4	15.2	65.1	13 or SB
Potassium	65.2 B	180 B	1.9 U	242 B	3310	8020	3830	941	SB
Selenium	0.09 U	0.09 U	1.5 U	0.09 U	0.1 U	0.1 U	0.1 U	0.19 U	2 or SB
Silver	0.27 U	0.29 U	0.29 U	0.28 U	0.02 U	0.02 U	0.02 U	3.1	SB
Sodium	81.5 B	140 B	234 B	64.2 B	6070	4530	411 B	725	SB
Thallium	0.15 U	0.16 U	1.1 U	0.15 U	2.6	0.17 U	0.17 U	0.5 B	SB
Vanadium	4.7	47.2	0.1 U	5.8	20.6	38.9	26	32.5	150 or SB
Zinc	240	282	478	478	10.9	2380	456	49.8	2230

All results expressed in mg/Kg.
Concentration in bold exceeds the RSCO

Note: Boring sample BSB-98-7 represents site background (SB)

U - indicates not detected at or above the listed concentration

B- indicates estimated concentration below the contract required reporting limit but above the instrument detection limit

Table 9
Total Organic Carbon Analytical Data Summary
Former Columbia Cement Company, Inc. Facility
Freeport, New York

Sampling Dates: December 15, 16, 17, 18, 21, 22 and 23, 1998

	Sample ID	TOC Result (mg/Kg)	TOC (%)
Fill			
	BSB-98-7 (8-10')	16,300	1.63
	MW-98-8D (4-6')	15,700	1.57
	SB-98-2 (10-13.7')	2,150	0.215
	SB-98-3 (18-19.35')	6,110	0.611
	X-1 [SB-98-3 (18-19.35')]	8,200	0.82
	SB-98-4 (10-12')	17,600	1.76
Tidal Marsh			
	SB-98-3 (19.35-19.58')	29,800	2.98
	BSB-98-7 (11.35-13.63')	17,700	1.77
	MW-98-8D (7.7-8')	13,300	1.33
	MW-98-9D (6.1-6.5')	15,300	1.53
	MW-98-10D (9.85-10.2')	4,240	0.424
Gravelly Sand			
	SB-98-4 (14.55-16')	2,640	0.264
	SB-98-4 (28-30')	551	0.0551
	BSB-98-7 (28-30')	2,700	0.27
	MW-98-10D (12-14')	891	0.0891
Gray Clay & Silt			
	SB-98-2 (34.0-34.5')	2,300	0.23
	SB-98-3 (35.67-36')	1,310	0.131
	BSB-98-7 (34.55-36')	3,460	0.346
	SB-98-4 (35.16-36')	2,200	0.22
	MW-98-9D (37-38')	1,150	0.115
	MW-98-10D (37.1-38')	3,100	0.31
Transition Samples			
	*SB-98-2 (15.1-15.67')	3,780	0.378
	**MW-98-8D (34.75-36')	2,110	0.211
	***MW-98-9D (12-14')	10,300	1.03
Dry Well Sediments			
	DWSS-08 (0-6")	10,500	1.05
	DWSS-08 (24-30")	25,900	2.59
	X-2 [DWSS-08 (24-30")]	18,500	1.85

* Transition from Fill to Gravelly Sand

** Transition from Gravelly Sand to Gray Clay & Silt

*** Transition from Tidal Marsh to Gravelly Sand

Volatile Organic Analytical Data Summary-Ground Water
 Former Columbia Cement Company, Inc. Facility
 Freeport, New York
 Sampling Dates: January 1999; April 2000; May 2003

Sample ID	Screened Interval (depth ft. below ground surface)	MW-1S		MW-97-1D		MW-97-1S		MW-97-2S		NYS Groundwater Standard
		4/2000	-11.0 - 21.0	5/2003	1/4/1999	4/2000	69.31-64.31	14.25-24.25	83.38-73.36	
Date Sampled	1/4/1999	4/2000		5/2003	1/4/1999	4/2000	69.31-64.31	14.25-24.25	83.38-73.36	14.5-24.5
Compound										84.33-74.33
Chloro methane	1,000 U	10 U	1,000 U	100 U	100 U	100 U	10 U	10 U	20 U	10 U
Bromo methane	1,000 U	10 U	1,000 U	100 U	100 U	100 U	10 U	10 U	20 U	10 U
Vinyl Chloride	1,000 U	26	1,000 U	100 U	9 J	100 U	10 U	10 U	20 U	10 U
Chloroethane	11,000	12,000 D	13,000	500	480 D	1200	120	320 D	220	10 U
Methylene Chloride	170 J	580 BD	500 U	500	840 BD	50 U	10 U	20	10 U	15
Acetone	300 J	10 U	1,000 U	230 J	10 U	100 U	7 J	20 U	10 U	8 J
Carbon Disulfide	1,000 U	5 U	500 U	500 U	5 U	50 U	5 U	10 U	5 U	5 U
1,1-Dichloroethene	1,000 U	23	500 U	500 U	5	50 U	10 U	5 U	10 U	5 U
1,1-Dichloroethane	4,300	2,600 D	690	4,100	350 D	140	10 U	5 U	10 U	5 U
1,2-Dichloroethene (total)	1,000 U	5 U	500 U	500 U	5 U	50 U	10 U	5 U	10 U	5 U
Chloroform	1,000 U	5 U	500 U	500 U	5 U	50 U	10 U	5 U	10 U	5 U
1,2-Dichloroethane	1,000 U	5 U	500 U	500 U	5 U	50 U	10 U	5 U	10 U	5 U
2-Butanone	1,000 U	10 U	1,000 U	500 U	5 U	50 U	10 U	5 U	10 U	5 U
1,1,1-Trichloroethane	350 J	140 BD	500 U	5,100	2 J	50 U	10 U	20 U	10 U	10 U
Carbon Tetrachloride	1,000 U	5 U	500 U	500 U	5 U	50 U	10 U	5 U	10 U	5 U
Bromodichloromethane	1,000 U	5 U	500 U	500 U	5 U	50 U	10 U	5 U	10 U	5 U
1,2-Dichloropropane	1,000 U	5 U	500 U	500 U	5 U	50 U	10 U	5 U	10 U	5 U
cis-1,3-Dichloropropene	1,000 U	5 U	500 U	500 U	5 U	50 U	10 U	5 U	10 U	5 U
Trichloroethene	1,000 U	4 J	500 U	500 U	9	50 U	10 U	5 U	10 U	5 U
Dibromochloromethane	1,000 U	5 U	500 U	500 U	5 U	50 U	10 U	5 U	10 U	5 U
1,1,2-Trichloroethane	1,000 U	5 U	500 U	500 U	5 U	50 U	10 U	5 U	10 U	5 U
Benzene	1,000 U	23	500 U	500 U	5 U	50 U	10 U	5 U	10 U	5 U
trans-1,3-Dichloropropene	1,000 U	5 U	500 U	500 U	5 U	50 U	10 U	5 U	10 U	5 U
Bromoform	1,000 U	5 U	500 U	500 U	5 U	50 U	10 U	5 U	10 U	5 U
4-Methyl-2-Pentanone	1,000 U	10 U	1,000 U	500 U	5 U	50 U	10 U	5 U	10 U	5 U
2-Hexanone	1,000 U	10 U	1,000 U	500 U	10 U	100 U	10 U	20 U	10 U	10 U
Tetrachloroethene	1,000 U	1 J	500 U	500 U	1 J	50 U	10 U	20 U	10 U	10 U
1,1,2,2-Tetrachloroethane	1,000 U	5 U	500 U	500 U	5 U	50 U	10 U	5 U	10 U	5 U
Toluene	1,000 U	76	500 U	500 U	11	50 U	10 U	5 U	10 U	5 U
Chlorobenzene	1,000 U	2 J	500 U	500 U	5 U	50 U	10 U	5 U	10 U	5 U
Ethylbenzene	1,000 U	5 J	500 U	500 U	5 U	50 U	10 U	5 U	10 U	5 U
Styrene	1,000 U	5 U	500 U	500 U	5 U	50 U	10 U	5 U	10 U	5 U
Xylenes (total)	1,000 U	19	500 U	500 U	1 J	2 J	1 J	2 J	10 U	5 U

10
Volatile Organic Analytical Data Summary-Ground Water
Former Columbia Cement Company, Inc. Facility
Freeport, New York
Sampling Dates: January 1999; April 2000; May 2003

Sample ID	Screened Interval (depth ft. below ground surface)	Screened Interval (Elevation)	MW-97-3S			MW-97-4S			MW-97-5S			MW-97-6S			NYS Groundwater Standard	
			1/4/1999	5/2003	4/2000	1/4/1999	5/2003	4/2000	1/4/1999	5/2003	4/2000	1/4/1999	5/2003	4/2000		
Chloromethane	10 U	10 U	10 U	100 U	100 U	10 U	50 U	10 U	500 U	50 U	10 U	500 U	50 U	10 U	500 U	
Bromomethane	10 U	10 U	10 U	100 U	100 U	10 U	50 U	10 U	500 U	50 U	10 U	500 U	50 U	10 U	500 U	
Vinyl Chloride	10 U	10 U	10 U	100 U	100 U	10 U	50 U	10 U	500 U	50 U	10 U	500 U	50 U	10 U	500 U	
Chloroethane	1 J	8 J	10 U	500	8 J	140	260	810 D	3,600	400	910 D	2,600	910 D	2,600	910 D	2,600
Methylene Chloride	10 U	5 U	5 U	100 U	5 U	5 U	50 U	5 U	250 U	50 U	5 U	250 U	50 U	5 U	250 U	50 U
Acetone	10 U	10 U	10 U	100 U	100 U	10 U	50 U	10 U	500 U	50 U	10 U	500 U	50 U	10 U	500 U	50 U
Carbon Disulfide	10 U	5 U	1 J	100 U	5 U	5 U	50 U	5 U	250 U	50 U	5 U	250 U	50 U	5 U	250 U	50 U
1,1-Dichloroethene	10 U	5 U	5 U	100 U	5 U	5 U	50 U	5 U	250 U	50 U	5 U	250 U	50 U	5 U	250 U	50 U
1,1,1-Trichloroethane	10 U	5 U	5 U	100 U	5 U	5 U	50 U	5 U	250 U	50 U	5 U	250 U	50 U	5 U	250 U	50 U
1,2-Dichloroethene (total)	10 U	5 U	5 U	100 U	5 U	5 U	50 U	5 U	250 U	50 U	5 U	250 U	50 U	5 U	250 U	50 U
Chloroform	19 U	5 U	5 U	100 U	5 U	5 U	50 U	5 U	250 U	50 U	5 U	250 U	50 U	5 U	250 U	50 U
1,2-Dichloroethane	10 U	5 U	5 U	100 U	5 U	5 U	50 U	5 U	250 U	50 U	5 U	250 U	50 U	5 U	250 U	50 U
2-Butanone	10 U	10 U	10 U	100 U	10 U	10 U	50 U	5 U	250 U	50 U	5 U	250 U	50 U	5 U	250 U	50 U
1,1,1-Trichloroethane	10 U	5 U	5 U	100 U	5 U	5 U	50 U	5 U	250 U	50 U	5 U	250 U	50 U	5 U	250 U	50 U
Carbon Tetrachloride	10 U	5 U	5 U	100 U	5 U	5 U	50 U	5 U	250 U	50 U	5 U	250 U	50 U	5 U	250 U	50 U
Bromodichloromethane	10 U	5 U	5 U	100 U	5 U	5 U	50 U	5 U	250 U	50 U	5 U	250 U	50 U	5 U	250 U	50 U
1,2-Dichloropropane	10 U	5 U	5 U	100 U	5 U	5 U	50 U	5 U	250 U	50 U	5 U	250 U	50 U	5 U	250 U	50 U
cis-1,3-Dichloropropene	10 U	5 U	5 U	100 U	5 U	5 U	50 U	5 U	250 U	50 U	5 U	250 U	50 U	5 U	250 U	50 U
Trichloroethene	10 U	5 U	5 U	100 U	5 U	5 U	50 U	5 U	250 U	50 U	5 U	250 U	50 U	5 U	250 U	50 U
Dibromochloromethane	10 U	5 U	5 U	100 U	5 U	5 U	50 U	5 U	250 U	50 U	5 U	250 U	50 U	5 U	250 U	50 U
1,1,2-Trichloroethane	10 U	5 U	5 U	100 U	5 U	5 U	50 U	5 U	250 U	50 U	5 U	250 U	50 U	5 U	250 U	50 U
Benzene	10 U	5 U	5 U	100 U	5 U	5 U	50 U	5 U	250 U	50 U	5 U	250 U	50 U	5 U	250 U	50 U
trans-1,3-Dichloropropene	10 U	5 U	5 U	100 U	5 U	5 U	50 U	5 U	250 U	50 U	5 U	250 U	50 U	5 U	250 U	50 U
Bromoform	10 U	5 U	5 U	100 U	5 U	5 U	50 U	5 U	250 U	50 U	5 U	250 U	50 U	5 U	250 U	50 U
4-Methyl-2-Pentanone	10 U	10 U	10 U	100 U	10 U	10 U	50 U	10 U	500 U	50 U	10 U	500 U	50 U	10 U	500 U	50 U
2-Hexanone	10 U	10 U	10 U	100 U	10 U	10 U	50 U	10 U	500 U	50 U	10 U	500 U	50 U	10 U	500 U	50 U
Tetrachloroethene	10 U	5 U	5 U	100 U	5 U	5 U	50 U	5 U	250 U	50 U	5 U	250 U	50 U	5 U	250 U	50 U
1,1,2,2-Tetrachloroethane	10 U	5 U	5 U	100 U	5 U	5 U	50 U	5 U	250 U	50 U	5 U	250 U	50 U	5 U	250 U	50 U
Toluene	10 U	5 U	5 U	100 U	5 U	5 U	50 U	5 U	250 U	50 U	5 U	250 U	50 U	5 U	250 U	50 U
Chlorobenzene	10 U	8	7	100 U	5 U	3 J	50 U	5 U	250 U	50 U	5 U	250 U	50 U	5 U	250 U	50 U
Ethylbenzene	10 U	5 U	5 U	100 U	5 U	5 U	50 U	5 U	250 U	50 U	5 U	250 U	50 U	5 U	250 U	50 U
Styrene	10 U	5 U	5 U	100 U	5 U	5 U	50 U	5 U	250 U	50 U	5 U	250 U	50 U	5 U	250 U	50 U
Xylene (total)	10 U	5 U	5 U	100 U	5 U	5 U	50 U	5 U	250 U	50 U	5 U	250 U	50 U	5 U	250 U	50 U

5**

.10
Volatile Organic Analytical Data Summary-Ground Water
 Former Columbia Cement Company, Inc. Facility
 Freeport, New York
Sampling Dates: January 1999; April 2000; May 2003

Sample ID	Screened Interval (depth ft. below g) Screened Interval (Elevation)	MW-97-7S 21.35-31.35 77.44-67.44				MW-98-8S 10.0-20.0 78.89-68.89				MW-98-8D 25.0-35.0 73.68-63.68				MW-98-9D 27.0-37.0 70.54-60.54				NYS Groundwater Standard			
		Date Sampled	Compound	1/4/1999	4/2000	5/2003	1/4/1999	4/2000	5/2003	4/1/1999	4/2000	5/2003	4/1/1999	4/2000	5/2003	4/1/1999	4/2000	5/2003	4/1/1999	4/2000	5/2003
	Chloromethane	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	100 U	100 U	5
	Bromomethane	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	100 U	100 U	5
	Vinyl Chloride	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	100 U	100 U	5
	Chloroethane	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	100 U	100 U	2
	Methylene Chloride	10 U	19	5 U	5 U	10 U	13	5 U	3 J	93	46	10 U	38	290 D	810	5	5	5	5	5	5
	Acetone	10 U	9 J	10 U	10 U	10 U	18	10 U	13	10 U	13	5 U	5 U	10 U	5 U	5 U	5 U	5 U	50 U	50 U	5
	Carbon Disulfide	10 U	5 U	5 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	100 U	100 U	50
	1,1-Dichloroethene	10 U	5 U	5 U	10 U	10 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	50 U	50 U	50 GV
	1,1-Dichloroethane	10 U	5 U	5 U	10 U	10 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	50 U	50 U	5
	1,2-Dichloroethene (total)	10 U	5 U	5 U	10 U	10 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	50 U	50 U	5
	Chloroform	10 U	5 U	5 U	10 U	10 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	50 U	50 U	5
	1,1,2-Dichloroethane	10 U	5 U	5 U	10 U	10 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	50 U	50 U	7
	2-Butanone	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	100 U	100 U	5
	1,1,1-Trichloroethane	10 U	5 U	5 U	10 U	10 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	50 U	50 U	5
	Carbon Tetrachloride	10 U	5 U	5 U	10 U	10 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	50 U	50 U	5
	Bromodichloromethane	10 U	5 U	5 U	10 U	10 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	50 U	50 U	5
	1,2-Dichloropropane	10 U	5 U	5 U	10 U	10 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	50 U	50 U	5
	cis-1,3-Dichloropropene	10 U	5 U	5 U	10 U	10 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	50 U	50 U	1
	Trichloroethene	10 U	5 U	5 U	10 U	10 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	50 U	50 U	0.4*
	Dibromochloromethane	10 U	5 U	5 U	10 U	10 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	50 U	50 U	5
	1,1,2,2-Tetrachloroethane	10 U	5 U	5 U	10 U	10 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	50 U	50 U	5
	Benzene	10 U	5 U	5 U	10 U	10 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	50 U	50 U	1
	trans-1,3-Dichloropropene	10 U	5 U	5 U	10 U	10 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	50 U	50 U	1
	Bromoform	10 U	5 U	5 U	10 U	10 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	50 U	50 U	0.4*
	4-Methyl-2-Pentanone	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	100 U	100 U	NS
	2-Hexanone	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	100 U	100 U	NS
	Tetrachloroethene	10 U	5 U	5 U	10 U	10 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	50 U	50 U	5
	1,1,2,2-Tetrachloroethane	10 U	5 U	5 U	10 U	10 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	50 U	50 U	5
	Toluene	10 U	5 U	5 U	10 U	10 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	50 U	50 U	5
	Chlorobenzene	10 U	3 J	6	10 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	50 U	50 U	5
	Ethylbenzene	10 U	5 U	5 U	10 U	10 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	50 U	50 U	5
	Styrene	10 U	5 U	5 U	10 U	10 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	50 U	50 U	5
	Xylene (total)	10 U	5 U	5 U	10 U	10 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	50 U	50 U	5**

Table 10
Volatile Organic Analytical Data Summary-Ground Water
Former Columbia Cement Company, Inc. Facility
Freeport, New York
Sampling Dates: January 1990; April 2000; May 2003

Sample ID	Screened Interval (depth ft. below ground surface)	MW-98-10D 27.0-37.0 71.75-61.75	MW-00-11A 51.0-61.0 46.89-36.89	MW-00-12D 25.0-35.0 73.6-63.6	MW-03-13S	NYS Groundwater Standard
Screened Interval (Elevation)	Date Sampled	5/2003	4/2000	5/2003	4/2000	5/2003
Chloromethane	1/4/1999	10 U	10 U	10 U	10 U	10 U
Bromomethane		10 U	10 U	10 U	10 U	10 U
Vinyl Chloride		10 U	10 U	10 U	10 U	10 U
Chloroethane		10 U	10 U	11	10 U	10 U
Methylene Chloride		10 U	23	5 U	5 U	17
Acetone		10 U	10 J	10 U	34	10 U
Carbon Disulfide		10 U	5 U	5 U	5 U	69
1,1-Dichloroethene		10 U	5 U	5 U	5 U	50
1,1-Dichloroethane		10 U	5 U	5 U	5 U	60 GV
1,2-Dichloroethene (total)		10 U	5 U	5 U	5 U	5 U
Chloroform		1 J	5 U	5 U	5 U	5 U
1,2-Dichloroethane		10 U	5 U	5 U	5 U	5 U
2-Butanone		10 U	10 U	10 U	10 U	10 U
1,1,1-Trichloroethane		10 U	5 U	4 J	5 U	50 GV
Carbon Tetrachloride		10 U	5 U	5 U	5 U	5 U
Bromodichloromethane		10 U	5 U	5 U	5 U	5 U
1,2-Dichloropropane		10 U	5 U	5 U	5 U	5 U
cis-1,3-Dichloropropene		10 U	5 U	5 U	5 U	5 U
Trichloroethene		10 U	5 U	5 U	5 U	0.4*
Dibromochloromethane		10 U	5 U	5 U	5 U	5 U
1,1,2-Trichloroethane		10 U	5 U	5 U	5 U	5 U
Benzene		10 U	5 U	5 U	5 U	5 U
trans-1,3-Dichloropropene		10 U	5 U	5 U	5 U	1
Bromoform		10 U	5 U	5 U	5 U	0.4*
4-Methyl-2-Pentanone		10 U	10 U	10 U	500 U	5 U
2-Hexanone		10 U	10 U	10 U	10 U	NS
Tetrachloroethene		10 U	5 U	5 U	500 U	50 GV
1,1,2,2-Tetrachloroethane		10 U	5 U	5 U	500 U	5 U
Toluene		10 U	5 U	5 U	500 U	5 U
Chlorobenzene		10 U	6	5 U	500 U	5 U
Ethylbenzene		10 U	5 U	5 U	500 U	5 U
Styrene		10 U	5 U	5 U	500 U	5 U
Xylene (total)		10 U	5 U	5 U	500 U	5 U

All results expressed in $\mu\text{g/L}$.

NS indicates no groundwater standard.

GV indicates guidance value.

* Standard applies to the sum of the cis and trans isomers.

** Standard applies to the sum of the isomers.

Value in bold exceeds the groundwater standard.

U-indicates not detected at or above the listed concentration.

J-indicates estimated concentration below the contract required reporting limit but above the instrument detection limit.

Table 11

Semivolatile Organic Analytical Data Summary - Groundwater
 Former Columbia Cement Company, Inc. Facility
 Freeport, New York

Sampling Date: January 4, 1999

Compound	Sample ID	MW-1S	X-3 (MW-1S)	MW-97-1D	MW-98-8S	MW-98-8D	NYS Groundwater Standard
Phenol		10 U	10 U	10 U	10 U	10 U	1 **
bis(2-Chloroethyl)Ether		10 U	10 U	10 U	10 U	10 U	1
2-Chlorophenol		10 U	10 U	10 U	10 U	10 U	1 **
1,3-Dichlorobenzene		10 U	10 U	10 U	10 U	10 U	3*
1,4-Dichlorobenzene		10 U	10 U	10 U	10 U	10 U	3*
1,2-Dichlorobenzene		10 U	10 U	10 U	10 U	10 U	3*
2-Methylphenol		10 U	10 U	10 U	10 U	10 U	1 **
2,2'-oxybis(1-Chloropropane)		10 U	10 U	10 U	10 U	10 U	5
4-Methylphenol		10 U	10 U	10 U	10 U	10 U	1 **
N-Nitroso-di-n-propylamine		10 U	10 U	10 U	10 U	10 U	NS
Hexachloroethane		10 U	10 U	10 U	10 U	10 U	5
Nitrobenzene		10 U	10 U	10 U	10 U	10 U	0.4
Isophorone		10 U	10 U	10 U	10 U	10 U	50 GV
2-Nitrophenol		10 U	10 U	10 U	10 U	10 U	1 **
2,4-Dimethylphenol		10 U	10 U	10 U	10 U	10 U	1 **
2,4-Dichlorophenol		10 U	10 U	10 U	10 U	10 U	1 **
1,2,4-Trichlorobenzene		10 U	10 U	10 U	10 U	10 U	1 **
Naphthalene		8 J	8 J	10 U	10 U	10 U	5*
4-Chloroaniline		10 U	10 U	10 U	10 U	10 U	10 GV
Hexachlorobutadiene		10 U	10 U	10 U	10 U	10 U	5
bis(2-Chloroethyl)methane		10 U	10 U	10 U	10 U	10 U	0.5
4-Chloro-3-Methylphenol		10 U	10 U	10 U	10 U	10 U	5
2-Methylnaphthalene		1 J	1 J	10 U	10 U	10 U	1 **
Hexachlorocyclopentadiene		10 U	10 U	10 U	10 U	10 U	NS
2,4,6-Trichlorophenol		10 U	10 U	10 U	10 U	10 U	5
2,4,5-Trichlorophenol		25 U	25 U	25 U	25 U	25 U	1 **
2-Chloronaphthalene		10 U	10 U	10 U	10 U	10 U	10 GV
2-Nitroaniline		25 U	25 U	25 U	25 U	25 U	5
Dimethyliphtalate		10 U	10 U	10 U	10 U	10 U	50 GV
Aceanaphthylene		10 U	10 U	10 U	10 U	10 U	NS
2,6-Dinitrotoluene		10 U	10 U	10 U	10 U	10 U	5
3-Nitroaniline		25 U	25 U	25 U	25 U	25 U	NS
Acenaphthene		10 U	10 U	6 J	10 U	1 J	20 GV
2,4-Dinitrophenol		25 U	25 U	25 U	25 U	25 U	1 **
4-Nitrophenol		25 U	25 U	25 U	25 U	25 U	1 **
Dibenzofuran		10 U	10 U	2 J	10 U	10 U	NS
2,4-Dinitrotoluene		10 U	10 U	10 U	10 U	10 U	1
Diethylphthalate		10 U	10 U	10 U	10 U	10 U	50 GV
4-Chlorophenyl-phenylether		10 U	10 U	10 U	10 U	10 U	NS

Table 11

Semivolatile Organic Analytical Data Summary - Groundwater
 Former Columbia Cement Company, Inc. Facility
 Freeport, New York

Sampling Date: January 4, 1999

Compound	Sample ID	MW-1S	X-3 (MW-1S)	MW-97-1D	MW-98-8S	MW-98-8D	NYS Groundwater Standard
Fluorene		10 U	10 U	4 J	10 U	10 U	50 GV
4-Nitroaniline		25 U	25 U	25 U	25 U	25 U	5
4,6-Dinitro-2-methylphenol		25 U	25 U	25 U	25 U	25 U	1 **
N-Nitrosodiphenylamine		10 U	10 U	10 U	10 U	10 U	50 GV
4-Bromophenyl-phenylether		10 U	10 U	10 U	10 U	10 U	5
Hexachlorobenzene		10 U	10 U	10 U	10 U	10 U	0.04
Pentachlorophenol		25 U	25 U	25 U	25 U	25 U	1 **
Phenanthrene		10 U	10 U	10 U	10 U	10 U	50 GV
Anthracene		10 U	10 U	10 U	10 U	10 U	50 GV
Carbazole		10 U	10 U	10 U	10 U	10 U	NS
Di-n-butylphthalate		1 J	2 J	1 J	10 U	10 U	NS
Fluoranthene		10 U	10 U	10 U	10 U	10 U	50 GV
Pyrene		10 U	10 U	10 U	10 U	10 U	50 GV
Butylbenzylphthalate		J J	10 U	10 U	10 U	10 U	50 GV
3,3'-Dichlorobenzidine		10 U	10 U	10 U	10 U	10 U	5
Benzo(a)anthracene		10 U	10 U	10 U	10 U	10 U	0.002
Chrysene		10 U	10 U	10 U	10 U	10 U	0.002
bis(2-Ethylhexyl)phthalate		10 U	10 U	10 U	10 U	10 U	5
Di-n-octylphthalate		2 J	1 J	10 U	10 U	10 U	50 GV
Benz(e)fluoranthene		10 U	10 U	10 U	10 U	10 U	0.002
Benz(f)fluoranthene		10 U	10 U	10 U	10 U	10 U	0.002
Benz(a)pyrene		10 U	10 U	10 U	10 U	10 U	Non Detect
Indeno(1,2,3-cd)pyrene		10 U	10 U	10 U	10 U	10 U	0.002
Dibenz(a,h)anthracene		10 U	10 U	10 U	10 U	10 U	NS
Benz(g,h,i)perylene		10 U	10 U	10 U	10 U	10 U	NS

All results expressed in ug/L.

* Standard applies to each isomer individually.

** Standard applies to sum of total phenolic compounds

Table 12
Pesticide/PCB Analytical Data Summary - Groundwater
Former Columbia Cement Company, Inc. Facility
Freeport, New York

Sampling Date: January 4, 1999

Sample ID Compound	MW-1S	X-3 (MW-1S)	MW-97-1D	MW-98-8S	MW-98-8D	NYS Groundwater Standard
alpha-BHC	0.026 U	0.026 U	0.026 U	0.026 U	0.028 U	0.05
beta-BHC	0.026 U	0.026 U	0.026 U	0.026 U	0.028 U	0.01
delta-BHC	0.026 U	0.026 U	0.026 U	0.026 U	0.028 U	0.04
gamma-BHC (Lindane)	0.026 U	0.026 U	0.026 U	0.026 U	0.028 U	0.05
Heptachlor	0.026 U	0.026 U	0.026 U	0.026 U	0.028 U	0.04
Aldrin	0.026 U	0.026 U	0.026 U	0.026 U	0.028 U	Non-Detect
Heptachlor epoxide	0.026 U	0.026 U	0.026 U	0.026 U	0.028 U	0.03
Endosulfan I	0.026 U	0.026 U	0.026 U	0.026 U	0.028 U	NS
Dieldrin	0.053 U	0.051 U	0.053 U	0.052 U	0.057 U	0.004
4,4'-DDE	0.053 U	0.051 U	0.053 U	0.052 U	0.057 U	0.2
Endrin	0.053 U	0.051 U	0.053 U	0.052 U	0.057 U	Non-Detect
Endosulfan II	0.053 U	0.051 U	0.053 U	0.052 U	0.057 U	NS
4,4'-DDD	0.053 U	0.051 U	0.053 U	0.052 U	0.057 U	0.3
Endosulfan sulfate	0.053 U	0.051 U	0.053 U	0.052 U	0.057 U	NS
4,4'-DDT	0.053 U	0.051 U	0.053 U	0.052 U	0.057 U	0.2
Methoxychlor	0.26 U	0.26 U	0.26 U	0.26 U	0.28 U	35
Endrin ketone	0.053 U	0.051 U	0.053 U	0.052 U	0.057 U	5
Endrin aldehyde	0.053 U	0.051 U	0.053 U	0.052 U	0.057 U	5
alpha-Chlordane	0.026 U	0.026 U	0.026 U	0.026 U	0.028 U	0.05
gamma-Chlordane	0.026 U	0.026 U	0.026 U	0.026 U	0.028 U	0.05
Toxaphene	2.6 U	2.6 U	2.6 U	2.6 U	2.8 U	NS
Aroclor-1016	0.53 U	0.51 U	0.53 U	0.52 U	0.57 U	0.09
Aroclor-1221	1 U	1 U	1 U	1 U	1.1 U	0.09
Aroclor-1232	0.53 U	0.51 U	0.53 U	0.52 U	0.57 U	0.09
Aroclor-1242	0.53 U	0.51 U	0.53 U	0.52 U	0.57 U	0.09
Aroclor-1248	0.53 U	0.51 U	0.53 U	0.52 U	0.57 U	0.09
Aroclor-1254	0.53 U	0.51 U	0.53 U	0.52 U	0.57 U	0.09
Aroclor-1260	0.53 U	0.51 U	0.53 U	0.52 U	0.57 U	0.09

All results expressed in ug/L.

U-indicates not detected at or above the listed concentration.

J- indicates estimated concentration below the contract required reporting limit but above the instrument detection limit.

Table 13
Inorganic Analytical Data Summary - Groundwater
Former Columbia Cement Company, Inc. Facility
Freeport, New York

Sampling Date: January 4, 1999

Sample ID	MW-1S	X-3 (MW-1S)	MW-97-1D	MW-98-8S	MW-98-8D	NYS Groundwater Standard
Analyte						
Aluminum	176 B	198 B	1430	282	3380	
Antimony	15.9 U	15.9 U	15.9 U	15.9 U	15.9 U	3
Arsenic	2.3 B	1.3 B	1.3 U	1.3 U	1.3 U	25
Barium	468	467	703	1540	65.3	1,000
Beryllium	2 U	2 U	2 U	2 U	2 U	3 GV
Cadmium	1.9 B	1.7 U	1.7 U	1.7 U	1.7 U	5
Calcium	63,400	63,200	196,000	243,000	37,000	
Chromium	2.7 U	4.1 B	4.8 B	2.7 U	13.5	50
Cobalt	3.2 B	4.4 B	5.6 B	10.3 B	3.1 B	
Copper	1.1 U	1.1 U	1.1 U	1.1 U	12.3 B	200
Iron	25,900	28,600	12,900	13,400	5,640	300
Lead	1 B	1.8 B	0.9 U	0.9 U	7	25
Magnesium	13,500	13,500	31,400	34,900	5,380	35,000 GV
Manganese	357	361	306	321	125	300
Mercury	0.38	0.2 U	0.2 U	0.35	0.44	2
Nickel	15 B	19.6 B	47.4	52.6	13.3 B	
Potassium	19,300	19,400	49,500	70,400	6,780	
Selenium	1.6 U	1.6 U	1.6 U	1.6 U	1.6 U	10
Silver	5.1 U	5.1 U	5.1 U	5.1 U	5.1 U	50
Sodium	48,400	48,400	155,000	232,000	35,400	20,000
Thallium	2.8 U	2.8 U	2.8 U	7.2 B	2.8 U	0.5 GV
Vanadium	1.7 U	1.8 B	6.2 B	1.7 U	19.4 B	
Zinc	247	199	71	48.7	116	2,000
Cyanide	10 U	10 U	10 U	10 U	10 U	200

All results expressed in ug/L.

GV indicates guidance value

Concentration in bold exceeds the groundwater standard

U - indicates not detected at or above the listed concentration

B- indicates estimated concentration below the contract required reporting limit but above the instrument detection limit

Table 14
Volatile Organic Analytical Data Summary - Soil Gas
Former Columbia Cement Company, Inc. Facility
Freeport, New York

Sampling Dates: December 16 and 17, 1998

Compound	Sample ID	SG-04	SG-06	SG-07	SG-X2	SG-11	SG-13	SG-15
Chloromethane		10 U						
Bromomethane		10 U						
Vinyl Chloride		10 U						
Chloroethane		10 U						
Methylene Chloride		10 U						
Acetone		10 U						
Carbon Disulfide		10 U						
1,1-Dichloroethene		10 U						
1,1-Dichloroethane		10 U						
1,2-Dichloroethene (total)		10 U						
Chloroform		10 U						
1,2-Dichloroethane		10 U						
2-Butanone		10 U						
1,1,1-Trichloroethane		10 U						
Carbon Tetrachloride		10 U						
Bromodichloromethane		10 U						
1,2-Dichloropropane		10 U						
cis-1,3-Dichloropropene		10 U						
Trichloroethene		10 U	1 J	10 U				
Dibromo-chloromethane		10 U						
1,1,2-Trichloroethane		10 U	10 U	10 U	10 U	2 J	10 U	10 U
Benzene		10 U						
trans-1,3-Dichloropropene		10 U						
Bromoform		10 U						
4-Methyl-2-Pentanone		10 U						
2-Hexanone		10 U						
Tetrachloroethene		10 U						
1,1,2,2-Tetrachloroethane		10 U						
Toluene		10 U						
Chlorobenzene		10 U						
Ethylbenzene		10 U						
Styrene		10 U						
Xylene (total)		10 U						

All results expressed in mg/m³.

U- indicates not detected at or above the listed concentration

J - indicates estimated concentration below the laboratory reporting limit but above the instrument detection limit

Table 14
Volatile Organic Analytical Data Summary - Soil Gas
Former Columbia Cement Company, Inc. Facility
Freeport, New York

Sampling Dates: December 16 and 17, 1998

Compound	Sample ID	SG-16	SG-17	SG-X1	SG-20	BACK-01	BACK-02
Chloromethane		10 U	10 U				
Bromomethane		10 U	10 U				
Vinyl Chloride		10 U	10 U				
Chloroethane		10 U	10 U				
Methylene Chloride		10 U	10 U				
Acetone		10 U	10 U				
Carbon Disulfide		10 U	10 U				
1,1-Dichloroethene		10 U	10 U				
1,1-Dichloroethane		17	10 U	10 U	10 U	10 U	10 U
1,2-Dichloroethene (total)		10 U	10 U				
Chloroform		10 U	10 U				
1,2-Dichloroethane		10 U	10 U				
2-Butanone		10 U	10 U				
1,1,1-Trichloroethane		6 J	10 U	10 U	10 U	10 U	10 U
Carbon Tetrachloride		10 U	10 U				
Bromodichloromethane		10 U	10 U				
1,2-Dichloropropane		10 U	10 U				
cis-1,3-Dichloropropene		10 U	10 U				
Trichloroethene		10 U	10 U				
Dibromochloromethane		10 U	10 U				
1,1,2-Trichloroethane		10 U	10 U				
Benzene		10 U	10 U				
trans-1,3-Dichloropropene		10 U	10 U				
Bromoform		10 U	10 U				
4-Methyl-2-Pentanone		10 U	10 U				
2-Hexanone		10 U	10 U				
Tetrachloroethene		10 U	10 U	10 U	10 U	1 J	10 U
1,1,2,2-Tetrachloroethane		10 U	10 U				
Toluene		10 U	10 U				
Chlorobenzene		10 U	10 U				
Ethylbenzene		10 U	10 U	10 U	10 U	1 J	10 U
Styrene		10 U	10 U	10 U	10 U	1 J	10 U
Xylene (total)		10 U	10 U	10 U	2 J	4 J	10 U

All results expressed in mg/m³.

U- indicates not detected at or above the listed concentration

J - indicates estimated concentration below the laboratory reporting limit but above the instrument detection limit

Table 15
Soil Gas Analytical Results
Former Columbia Cement Company, Inc. Facility
Freeport, New York
April 2000

Parameter	SG-1A	SG-2A	SG-3A	
1,1,1-Trichloroethane	30.00	240.00	710.00	D
1,1,2,2-Tetrachloroethane	6.90	U	6.90	U
1,1,2-Trichloroethane	5.50	U	5.50	U
1,1-Dichloroethane	13.00		51.00	50.00
1,1-Dichloroethene	4.00	U	4.00	U
1,2,4-Trichlorobenzene	7.40	U	7.40	U
1,2,4-Trimethylbenzene	4.90	U	7.60	5.10
1,2-Dibromoethane	7.70	U	7.70	U
1,2-Dichlorobenzene	6.00	U	6.00	U
1,2-Dichloroethane	4.00	U	4.00	U
1,2-Dichloropropane	4.60	U	4.60	U
1,3,5-Trimethylbenzene	4.90	U	4.90	U
1,3-Butadiene	2.50	U	2.50	U
1,3-Dichlorobenzene	6.00	U	6.00	U
1,4-Dichlorobenzene	6.00	U	6.00	U
1,4-Dioxane	3.60	U	3.60	U
2,2,4-Trimethylpentane	5.40	U	5.40	U
2-Chlorotoluene	5.20	U	5.20	U
3-Chloropropene	3.10	U	3.10	U
4-Ethyltoluene	4.90	U	4.90	U
Acetone	510.00	D	340.00	D
Benzene	3.20	U	6.50	5.10
Bromodichloromethane	6.70	U	6.70	U
Bromoethene	4.40	U	4.40	U
Bromoform	10.00	U	10.00	U
Bromomethane	3.90	U	3.90	U
Carbon Disulfide	3.10	U	6.20	9.90
Carbon Tetrachloride	6.30	U	6.30	U
Chlorobenzene	4.60	U	4.60	U
Chloroethane	2.60	U	2.60	U
Chloroform	13.00		4.90	U
Chloromethane	2.10	U	2.10	U
cis-1,2-Dichloroethene	4.00	U	4.00	U
cis-1,3-Dichloropropene	4.50	U	4.50	U
Cyclohexane	35.00		18.00	16.00
Dibromochloromethane	9.90	U	9.90	U
Dichlorodifluoromethane	4.90	U	4.90	U
Dichlorotetrafluoroethane	7.00	U	7.00	U
Ethylbenzene	4.30	U	4.30	U
FreonTF	7.70	U	7.70	U
Hexachlorobutadiene	11.00	U	11.00	U
Isopropyl Alcohol	2.50	U	2.50	U

Table 15
Soil Gas Analytical Results
Former Columbia Cement Company, Inc. Facility
Freeport, New York
April 2000

Parameter	SG-1A	SG-2A		SG-3A
Methyl Butyl Ketone	4.10	U	4.10	U
Methyl Ethyl Ketone	33.00		33.00	52.00
Methyl Isobutyl Ketone	4.10	U	4.10	U
Methylene Chloride	30.00		140.00	93.00
Methyltert-ButylEther	3.60	U	3.60	U
n-Heptane	4.10	U	4.10	U
n-Hexane	94.00		54.00	22.00
Styrene	4.30	U	4.30	U
Tetrachloroethene	53.00		29.00	16.00
Tetrahydrofuran	2.90	U	2.90	U
Toluene	44.00		31.00	37.00
trans-1,2-Dichloroethene	4.00	U	4.00	U
trans-1,3-Dichloropropene	4.50	U	4.50	U
Trichloroethene	5.40	U	5.40	U
Trichlorofluoromethane	5.60	U	5.60	U
VinylChloride	2.60	U	2.60	U

All values expressed in ug/M³

U indicates not detected at or above the listed concentration

D indicates analysis based on diluted sample

855.00000 956.30 1446.00

Soil Gas Analytical Data Summary

Sampling Dates: December 1998 and April 2000

Compound	Sample ID	SG-11	SG-13	SG-16	SG-20	SG-1A	SG-2A	ACGIH TLV TWA ppm	NIOSH TWA ppm	OSHA TWA ppm	Conversion Factor mg/m^3	TYPICAL INDOOR AIR BACKGROUND CONC. mg/m^3	ATSDR MRLA mg/m^3		
1,1,1-Trichloroethane	10 U	10 U	6	10 U	0.030	0.24	0.71	10 U	55	10	5.46	1.267	1.182 mi		
1,1,2-Trichloroethane	21	10 U	10 U	10 U	0.0055 U	0.0035 U	0.005 U	10 U	100	55	5.46	5.46	NAV		
1,1-Dichloroethane	10 U	10 U	17	10 U	0.013	0.051	0.030	10 U	400	100	5.46	5.46	NAV		
1,1-Dichloroethylene	10 U	10 U	10 U	10 U	0.004	U	0.004	10 U	200	810	1.00	4.05	4.05	NAV	
1,2,4-Trichlorobenzene	NA	NA	NA	NA	0.009	U	0.009	U	NA	25	121	4.00	4.05	4.05	0.08 mi
Acetone	10 U	10 U	10 U	10 U	0.0049 U	0.0076	0.0051	10 U	NA	25	120	2.5	1.20	1.20	0.0328
Benzene	10 U	10 U	10 U	10 U	0.5100	0.3200	0.3200	10 U	750	750	250	1.00	1.00	NAV	
Chloroform	10 U	10 U	10 U	10 U	0.0032 U	0.0065	0.0051	10 U	10	32	0.1 (LST)	0.1	1 (LST)	34.94 chr	
Clohexane	10 U	10 U	10 U	10 U	0.0031 U	0.0062	0.0059	10 U	10	31	1 (LST)	3	1 (LST)	0.016	
Cyclohexane	10 U	10 U	10 U	10 U	0.0026 U	0.0026	0.0026	10 U	1000	2640	NE	62	62	0.013 mi	
Ethylbenzene	NA	NA	NA	NA	0.0130	0.0049	0.0049	U	10 U	20	49	2.64	2.64	NAV	
Methyl Ethyl Ketone	10 U	10 U	10 U	10 U	0.0350	0.0180	0.0160	NA	300	1037	9.76	4.88	4.88	39.6 mi	
Methylene Chloride	10 U	10 U	10 U	10 U	0.0043 U	0.0043	0	0.0043 U	1030	300	1050	3.44	3.44	0.014 mi	
n-Heptane	10 U	10 U	10 U	10 U	0.0330	0.0330	0.0230	10 U	430	100	430	4.34	4.34	NAV	
Syrene	NA	NA	NA	NA	0.0300	0.140	0.0330	10 U	200	590	200	2.95	2.95	0.0273	
Tetrachloroethylene	10 U	10 U	10 U	10 U	0.0940	0.0540	0.0220	NA	50	174	NE	25	25	NAV	
Toluene	10 U	10 U	10 U	10 U	0.0043 U	0.0043	0	0.0043 U	100	176	50	180	180	1.05 chr	
Trichloroethylene	10 U	10 U	10 U	10 U	0.0230	0.0230	0.0160	10 U	20	85	50	100	100	0.012	
Xylenic (total)	10 U	10 U	10 U	10 U	0.0440	0.0310	0.0370	10 U	50	171	NE	100	100	2.11 chr	
	10 U	10 U	10 U	10 U	0.0054 U	0.0054	U	10 U	50	270	NE	375	375	0.25 mi	
	10 U	10 U	10 U	10 U	2.1	NA	4.1	100	430	1000	NA	5.33	5.33	0.27 mi	
									100	100	NA	4.20	4.20	1.51 mi	
									100	100	NA	3.77	3.77	0.0326	
									100	100	NA	0.0326	0.0326	0.54 mi	
									100	430	100	4.34	4.34	0.43 chr	

Notes:

1) All sample results expressed in milligrams per cubic meter (mg/m^3).2) The following standards have been provided for comparison values and are presented in both parts per million (ppm) and mg/m^3 :

- American Conference of Governmental Industrial Hygienists (ACGIH) Threshold Limit Value (TLV) Time-Weighted Average (TWA) and Short-Term Exposure Limit (STEL) values;
- National Institute for Occupational Safety and Health (NIOSH) exposure limits (ST indicates a short-term exposure limit; PEL indicates a permissible exposure limit; C indicates a ceiling value);
- Occupational Safety and Health Administration (OSHA) Permissible Exposure Limit (PEL) values (C indicates a ceiling value).

Please note that the conversion factor (ppm to mg/m^3) for each compound has been provided in the far right column.

3) "U" indicates that the compound was not detected at or above the reporting limit indicated.

4) "—" indicates that the result reported is below the reporting limit but greater than the method detection limit (MDL) and the reported concentration is considered estimated. Although the laboratory reporting limit is 10 mg/m^3 , the MDL for each compound is significantly lower and estimated results greater than the MDL but less than the reporting limit have been reported.

5) Non-target compounds were detected in the following samples: SG-04, SG-06, SG-07, SG-15, SG-17, SG-X1 (a blind duplicate of SG-17) and HAC-K-02.

6) Samples BACK-01 and HAC-K-02 are background samples of ambient air collected as part of the site gas survey using the same sampling train.

7) NA indicates not analyzed

8) NE indicated none established

9) SG-1A, SG-2A and SC-3A collected in April 2000

10) NAV indicates data not available

11) Typical Indoor Air data from USEPA "National Ambient Volatile Organic Compounds (VOCs) Data Base Update", EPA/600/R-98/010a, March 1998

12) ATSDR MRLs from Agency For Toxic Substances and Disease Registry, Minimal Risk Levels for Hazardous Substances

13) NC = acute; CH = chronic; int = intermediate exposures

Table 17A

Remedial Investigation
SD-8 Volatile Organic Analytical Data Summary
Former Columbia Cement Company, Inc. Facility
Freeport, New York

Sample ID Date Depth Sample Taken Compound	SD-8 12/23/98 (0-6")	SD-8 12/23/98 (24-30")	SD-8 4/7/99 (0-6")	SD-8 4/7/99 (6-12")	SD-8 4/7/99 (12-18")	SD-8 4/7/99 (18-24")	SD-8 4/7/99 (24-30")	NYSDEC RSCO
Chloromethane	13 U	11 U	10 U	10 U	10 U	10 U	10 U	10 U
Bromomethane	13 U	11 U	10 U	10 U	10 U	10 U	10 U	10 U
Vinyl Chloride	13 U	11 U	6 J	10 U	10 U	10 U	10 U	200
Chloroethane	13 U	11 U	10 U	10 U	10 U	10 U	10 U	1,900
Methylene Chloride	3 J	11 U	16	4 J	2 J	3 J	88	100
Acetone	13	11 U	130 B	44 U	5 U	30 U	55 B	200
Carbon Disulfide	13 U	11 U	10 U	10 U	10 U	10 U	10 U	
1,1-Dichloroethene	13 U	11 U	10 U	10 U	10 U	10 U	10 U	
1,1-Dichloroethane	24	4 J	10 U	10 U	10 U	10 U	6 J	2 J
1,2-Dichloroethene (total)	13 U	11 U	10 U	10 U	10 U	10 U	10 U	39
Chloroform	13 U	11 U	10 U	10 U	10 U	10 U	10 U	2 J
1,2-Dichloroethane	13 U	11 U	10 U	10 U	10 U	10 U	10 U	100
2-Butanone	13 U	11 U	45	28 U	10 U	87	10 J	400
1,1,1-Trichloroethane	380 D	850 D	33	45 U	59	10 U	96	800
Carbon Tetrachloride	13 U	11 U	10 U	10 U	10 U	10 U	10 U	
Bromodichloromethane	13 U	11 U	10 U	10 U	10 U	10 U	10 U	
1,2-Dichloropropane	13 U	11 U	10 U	10 U	10 U	10 U	10 U	
cis-1,3-Dichloropropene	13 U	11 U	10 U	10 U	10 U	10 U	10 U	
Trichloroethene	13 U	11 U	2 J	10 U	10 U	0.6 J	10 U	2 J
Dibromochloromethane	13 U	11 U	10 U	10 U	10 U	10 U	10 U	700
1,1,2-Trichloroethane	13 U	11 U	10 U	10 U	10 U	10 U	10 U	
Benzene	13 U	11 U	10 U	10 U	10 U	10 U	10 U	
trans-1,3-Dichloropropene	13 U	11 U	10 U	10 U	10 U	10 U	10 U	
Bromoform	13 U	11 U	10 U	10 U	10 U	10 U	10 U	
4-Methyl-2-Pentanone	13 U	11 U	10 U	10 U	10 U	10 U	10 U	
2-Hexanone	13 U	11 U	6 J	10 U	10 U	10 U	10 U	2 J
Tetrachloroethene	13 U	11 U	10 U	10 U	10 U	10 U	10 U	
1,1,2,2-Tetrachloroethane	13 U	11 U	10 U	10 U	10 U	0.3 J	10 U	1 J
Toluene	3 J	2 J	24	6 J	10 U	10 U	10 U	10 U
Chlorobenzene	13 U	11 U	12 J	4 J	10 U	10 U	4 J	6 J
Ethylbenzene	13 U	11 U	2 J	1 J	10 U	10 U	10 U	1,500
Styrene		2 J	45	20	19	19	45	1,200
Xylene (total)								

Table 17A

Remedial Investigation
SD-8 Volatile Organic Analytical Data Summary
Former Columbia Cement Company, Inc. Facility
Freeport, New York

Sample ID Date Depth Sample Taken Compound	SD-8 4/7/1999 (30-36")	SD-8 4/7/1999 (36-42")	SD-8 4/7/1999 (42-48")	SD-8 4/7/1999 (48-53")	SD-8 4/2000 (0-12")	NYSDEC RSCO
Chloromethane	10 U	10 U	10 U	10 U	10 U	7 U
Bromomethane	10 U	10 U	10 U	10 U	14 U	
Vinyl Chloride	10 U	10 U	10 U	10 U	14 U	200
Chloroethane	13	780	140	200	14 U	1,900
Methylene Chloride	9 J	23 J	17 J	5 J	12 U	100
Acetone	25 U	300 B	150 B	44 B	18 U	200
Carbon Disulfide	10 U	16 J	3 J	10 U	7 U	
1,1-Dichloroethene	10 U	10 U	10 U	10 U	7 U	
1,1-Dichloroethane	21	74	33	12 J	17	400
1,2-Dichloroethene (total)	10 U	10 U	10 U	10 U	7 U	100
Chloroform	10 U	10 U	10 U	10 U	7 U	
1,2-Dichloroethane	10 U	10 U	10 U	10 U	7 U	
2-Butanone	7 J	93	51	22 J	14 U	
1,1,1-Trichloroethane	49	52	34	11 J	4800 D	800
Carbon Tetrachloride	10 U	10 U	10 U	10 U	10 U	
Bromodichloromethane	10 U	10 U	10 U	10 U	10 U	
1,2-Dichloropropane	10 U	10 U	10 U	10 U	7 U	
cis-1,3-Dichloropropene	10 U	10 U	10 U	10 U	7 U	
Trichloroethene	0.8 J	10 U	10 U	10 U	7 U	
Dibromochloromethane	10 U	10 U	10 U	10 U	7 U	
1,1,2-Trichloroethane	10 U	10 U	10 U	10 U	7 U	
Benzene	10 U	10 U	10 U	10 U	7 U	
trans-1,3-Dichloropropene	10 U	10 U	10 U	10 U	7 U	
Bromoform	10 U	10 U	10 U	10 U	7 U	
4-Methyl-2-Pentanone	10 U	10 U	4 J	10 U	14 U	
2-Hexanone	10 U	10 U	1 J	10 U	14 U	
Tetrachloroethene	10 U	10 U	10 U	10 U	7 U	
1,1,2,2-Tetrachloroethane	10 U	10 U	10 U	10 U	7 U	
Toluene	1 J	15 J	8 J	4 J	2 J	1,500
Chlorobenzene	10 U	10 U	10 U	10 U	7 U	
Ethylbenzene	2 J	10 U	4 J	10 U	7 U	
Styrene	10 U	10 U	10 U	10 U	7 U	
Xylene (total)	6 J	23 J	15 J	3 J	4 J	1,200

Table 17B

**Remedial Investigation
SD-8 Volatile Organic Analytical Data Summary
Former Columbia Cement Company, Inc. Facility**

Parameter	Volatile Organic Compounds (ug/Kg)	Freightport, New York										RSCO
		SD-1 0-12*	SD-2 0-12*	SD-3 0-12*	X-1 0-12*	SD-4 0-12*	SD-5 0-12*	SD-6 0-12*	SD-7 0-12*	SD-8 0-12*	SD-9 0-12*	
Chloromethane	<1000	<6	<7	<7	<8	<60	<6	<6	<7	N/A	N/A	
Vinyl Chloride	<2000	<12	<14	<14	<16	<120	<11	<12	<14	200	N/A	
Bromomethane	<2000	<12	<14	<14	<16	<120	<11	<12	<14	N/A	N/A	
Chloroethane	<2000	<12	<14	<14	<16	<120	<11	<12	<14	1900	N/A	
Trichlorofluoromethane	<2000	<12	<14	<14	<16	<120	<11	<12	<14	N/A	N/A	
Acetone	<1700	<58	<14	<16	<26	<210	<86	<18	<22	200	N/A	
1,1-Dichloroethene	<1000	<6	<7	<7	<8	<60	<6	<6	<7	N/A	N/A	
Acrylonitrile	<2000	<12	<14	<14	<16	<120	<11	<12	<14	N/A	N/A	
Iodomethane	<1000	<6	<7	<7	<8	<60	<6	<6	<7	N/A	N/A	
Methylene Chloride	<2000	<11	<14	<14	<21	<67	<6	<13	<12	100	N/A	
Carbon Disulfide	<1000	2	<7	<7	<8	6	<6	<6	<7	2700	N/A	
trans-1,2-Dichloroethene	<1000	<6	<7	<7	<8	<60	<6	<6	<7	N/A	N/A	
1,1-Dichloroethane	<1000	<6	<7	<7	<8	<60	<6	<6	<7	17	200	
Vinyl Acetate	<2000	<12	<12	<14	<14	<16	<120	<11	<12	<14	N/A	
2-Butene-(MEK)	<2000	<12	<14	<14	<16	<120	<11	<12	<14	300	N/A	
cis-1,2-Dichloroethylene	<1000	<6	<7	<7	<8	<60	<6	<6	<7	4800	N/A	
Bromoform	<1000	<6	<7	<7	<8	<60	<6	<6	<7	600	N/A	
1,2-Dichloroethane	<1000	<6	<7	<7	<8	<60	<6	<6	<7	300	N/A	
1,1,1-Trichloroethane	<1000	2	<7	<7	4	<60	<6	<6	<7	100	N/A	
Carbon Tetrachloride	<1000	<6	<7	<7	<8	<60	<6	<6	<7	800	N/A	
Benzene	<1000	<6	<7	<7	<8	<60	<6	<6	<7	60	N/A	
Dibromoethane	<1000	<6	<7	<7	<8	<60	<6	<6	<7	N/A	N/A	
1,2-Dichloropropane	<1000	<6	<7	<7	<8	<60	<6	<6	<7	700	N/A	
Trichlorethane	<1000	<6	<7	<7	<8	<60	<6	<6	<7	N/A	N/A	
Bromodichloromethane	<1000	<6	<7	<7	<8	<60	<6	<6	<7	1500	N/A	
cis-1,3-Dichloropropene	<1000	<6	<7	<7	<8	<60	<6	<6	<7	N/A	N/A	
4-Methyl-2-Pentanone (MBK)	<2000	<12	<14	<14	<16	<60	<6	<6	<14	1700	N/A	
trans-1,3-Dichloropropene	<1000	<6	<7	<7	<8	<60	<6	<6	<7	N/A	N/A	
1,1,2-Trichloroethane	<1000	<6	<7	<7	<8	<60	<6	<6	<7	1200	N/A	
Toluene	560	<6	<7	2	<8	26	<6	<6	<7	N/A	N/A	
2-Hexanone	<2000	<12	<14	<14	<16	<60	<6	<6	<7	11	N/A	
Dihomochloromethane	<1000	<6	<7	<7	<8	<60	<6	<6	<7	600	N/A	
1,2-Dimethoxane	<1000	<6	2	2	<8	<60	<6	<6	<7	4	1600	
Tetrachlormethane	<1000	<6	3	5	<6	1750	95	270	2	1200	N/A	
1,1,1,2-Tetrachloroethane	<1000	<6	<7	<7	<8	<60	<6	<6	<7	N/A	N/A	
Chlorobenzene	<1000	<6	<7	<7	<8	<60	<6	<6	<7	1700	N/A	
Ethylbenzene	970	<6	<7	<7	<8	<60	<6	<6	<7	600	N/A	
Trial Xylenes	230	<6	2	2	<8	<60	<6	<6	<7	4	1600	
Bromoform	<1000	<6	3	5	<6	1750	95	270	2	1200	N/A	
Styrene	<1000	<6	<7	<7	<8	<60	<6	<6	<7	N/A	N/A	
1,1,2,2-Tetrachloroethane	970	<6	<7	<7	<8	<60	<6	<6	<7	8500	N/A	
1,3-Dichlorobenzene	<1000	<6	<7	<7	<8	<60	<6	<6	<7	7900	N/A	
1,4-Dichlorobenzene	<1000	<6	<7	<7	<8	<60	<6	<6	<7	8500	N/A	
1,2-Dichlorobenzene	<1000	<6	<7	<7	<8	<60	<6	<6	<7	7900	N/A	
1,2-Dibromo-3-Chloropropane	<2000	<12	<14	<14	<16	<120	<11	<12	<14	N/A	N/A	

Table 17B

Remedial Investigation
SD-8 Volatile Organic Analytical Data Summary
Former Columbia Cement Company, Inc. Facility

Semi-volatile Organic Compounds (ug/m ³)	SD-2	SD-3	X-1	SD-4	SD-5	SD-6	SD-7	SD-8	RSCO
bis(2-Chloroethyl)ether	<210	<2350	<240	<2600	<2000	<1950	<210	<235	N/A
1,3-Dichlorobenzene	<210	<2350	<240	<2600	<2000	<1950	<210	<235	N/A
1,4-Dichlorobenzene	<210	<2350	<240	<2600	<2000	<1950	<210	<235	N/A
Benzyl Alcohol	<400	<4600	<470	<5100	<4000	<3800	<400	<450	N/A
1,2-Dichlorobenzene	<210	<2350	<240	<2600	<2000	<1950	<210	<235	N/A
bis(2-Chloroisopropyl)ether	<210	<2350	<240	<2600	<2000	<1950	<210	<235	N/A
N-Nitrosodi-n-propylamine	<210	<2350	<240	<2600	<2000	<1950	<210	<235	N/A
Hexachlorobutane	<210	<2350	<240	<2600	<2000	<1950	<210	<235	N/A
Nitrobenzene	<210	<2350	<240	<2600	<2000	<1950	<210	<235	N/A
Isophorone	<210	<2350	<240	<2600	<2000	<1950	<210	<235	200
Benzoic Acid	<400	<4600	<470	<5100	<4000	<3800	<400	<450	4400
Bis(2-Chlorohydroxy)-methane	<210	<2350	<240	<2600	<2000	<1950	<210	<235	N/A
1,2,4-Trichlorobenzene	<210	<2350	<240	<2600	<2000	<1950	<210	<235	N/A
Naphthalene	<210	<2350	<240	<2600	<2000	<1950	<210	<235	N/A
4-Chloronaniline	<210	<2350	<240	<2600	<2000	<1950	<210	<235	13000
Heptachlorobutadiene	<210	<2350	<240	<2600	<2000	<1950	<210	<235	220
2-Methylphthalide	<210	<2350	<240	<2600	<2000	<1950	<210	<235	N/A
Hexachlorocyclopentadiene	<210	<2350	<240	<2600	<2000	<1950	<210	<235	36400
2-Chloronaphthalene	<210	<2350	<240	<2600	<2000	<1950	<210	<235	N/A
2-Nitroaniline	<1010	<11500	<1200	<12900	<10000	<9500	<1000	<1150	430
Dimethyl Phthalate	<400	<4600	<470	<5100	<4000	<3800	<400	<450	2000
Acenaphthylene	<210	<2350	<240	<2600	<2000	<1950	<210	<235	N/A
Acenaphthene	<210	<2350	<240	<2600	<2000	<1950	<210	<235	50000
2,6-Dinitrotoluene	<210	<2350	<240	<2600	<2000	<1950	<210	<235	1000
3-Nitrotoluene	<1010	<11500	<1200	<12900	<10000	<9500	<1000	<1150	510
Dibenzofuran	<210	<2350	<240	<2600	<2000	<1950	<210	<235	6200
2,4-Dinitrotoluene	<210	<2350	<240	<2600	<2000	<1950	<210	<235	N/A
Diethyl Phthalate	<400	<4600	<470	<5100	<4000	<3800	<400	<450	7100
4-Chlorophenyl Phenyl Ether	<210	<2350	<240	<2600	<2000	<1950	<210	<235	N/A
Fluorene	<210	<2350	<240	<2600	<2000	<1950	<210	<235	50000
4-Nitroaniline	<1010	<11500	<1200	<12900	<10000	<9500	<1000	<1150	N/A
N-Nitrosodiphenylamine	<210	<2350	<240	<2600	<2000	<1950	<210	<235	N/A
4-Bromophenyl Phenyl Ether	<210	<2350	<240	<2600	<2000	<1950	<210	<235	N/A
Hexachlorobutane	<210	<2350	<240	<2600	<2000	<1950	<210	<235	N/A
Phenanthrene	<210	<2350	<240	<2600	<2000	<1950	<210	<235	410
Anthracene	<210	<2350	<240	<2600	<2000	<1950	<210	<235	N/A
Di-n-butylphthalate	<400	<4600	<470	<5100	<4000	<3800	<400	<450	50000
Fluoranthene	<210	<2350	<240	<2600	<2000	<1950	<210	<235	224
3,3'-Dichlorobenzidine	<400	<4600	<470	<5100	<4000	<3800	<400	<450	8100
Chrysene	<210	<2350	<240	<2600	<2000	<1950	<210	<235	50000
Benzidine	<210	<2350	<240	<2600	<2000	<1950	<210	<235	400
Butyl Benzyl Phthalate	<400	<4600	<470	<5100	<4000	<3800	<400	<450	50000
Benzofuran	<210	<2350	<240	<2600	<2000	<1950	<210	<235	1100
Benzofuran	<210	<2350	<240	<2600	<2000	<1950	<210	<235	1100
Benzofuran	<210	<2350	<240	<2600	<2000	<1950	<210	<235	61
Indeno[1,2,3-cd]Pyrene	<210	<2350	<240	<2600	<2000	<1950	<210	<235	3200

Table 17B

**Remedial Investigation
SD-8 Volatile Organic Analytical Data Summary
Former Columbia Cement Company, Inc. Facility**

	SD-4	SD-3	X-1	SD-4	SD-5	SD-6	SD-7	SD-8	RSCO
Dibenz(a,h)Anthracene	<210	<2350	<240	<2600	<2000	<1950	<210	<235	14
Benz (b,h)Perylene	<210	<2350	<240	<2600	<2000	<1950	<210	<235	5000
Phenol	<210	<2350	<240	<2600	<2000	<1950	<210	<235	30
2-Chlorophenol	<210	<2350	<240	<2600	<2000	<1950	<210	<235	800
2-Nitrophenol	<210	<2350	<240	<2600	<2000	<1950	<210	<235	330
2,4-Dimethylphenol	<210	<2350	<240	<2600	<2000	<1950	<210	<235	N/A
2,4-Dichlorophenol	<210	<1500	<1200	<12900	<10000	<9500	<10000	<1150	400
4-Chloro-3-methylphenol (p-)	<210	<2350	<240	<2600	<2000	<1950	<210	<235	240
2,4,6-Trichlorophenol	<210	<2350	<240	<2600	<2000	<1950	<210	<235	N/A
2,4-Dinitrophenol	<1010	<11500	<1200	<12900	<10000	<9500	<10000	<1150	200
4-Nitrophenol	<1010	<11500	<1200	<12900	<10000	<9500	<10000	<1150	100
2-Methyl-4,6-dinitrophenol	<1010	<11500	<1200	<12900	<10000	<9500	<10000	<1150	N/A
2,4,5-Trichlorophenol	<1010	<11500	<1200	<12900	<10000	<9500	<10000	<1150	100
Pentachlorophenol	<1010	<11500	<1200	<12900	<10000	<9500	<10000	<1150	100
2-Methylphenol (o-Cresol)	<210	<2350	<240	<2600	<2000	<1950	<210	<235	100
4-Methylphenol (p-Cresol)	<210	<2350	<240	<2600	<2000	<1950	<210	<235	900
METALS (mg/Kg)									
SD-2	SD-3	X-1	SD-4	SD-5	SD-6	SD-7	SD-8	RSCO	
Arsenic	16	6.6	11	13	11	5.5	4.2	8	7.5 or SB
Berium	79	49	49	63	31	18	32	53	28.9
Cadmium	1.6	4.1	5.4	7.4	2	1.3	1.7	2.8	954
Chromium	16	18	21	27	14	7.5	11	22	1 or SB
Lead	210	88	89	130	140	31	180	140	7.5
Mercury	1.0	0.06	0.07	0.1	0.04	0.32	0.1	0.1	3160
Selenium	<7.3	<7.9	<7.7	<8.4	<6.4	<4.5	<5.3	0.1	0.96
Silver	<1.2	5.8	2.1	4.2	2.1	2.8	5	1.3	<0.1
Diesel Range Organics (mg/Kg)	<61	<69	<72	<77	<60	<57	700	<69	
Percent Solids	81.8	72.3	69.5	64.3	83.2	87.1	82.1	71.9	

Notes:

- 1) SB indicates site background
- 2) N/A indicates not applicable
- 3) < indicates estimated concentration below the contract required reporting limit but above the instrument detection limit.
- 4) Value in bold exceeds the Recommended Soil Cleanup Objective (RSCO).
- 5) < indicates not detected at or above the listed concentration.

Table 18

Volatile Organic Analytical Data Summary - Surface Water Freeport Creek
 Former Columbia Cement Company, Inc. Facility
 Freeport, New York

Sampling Date: April 2000

Sample ID	OutFall	OutFall	100' Up Stream Center Deep	100' Up Stream Center Shallow	100' Down Stream Center Deep	100' Down Stream Center Shallow	100' Upstream 25' From Shore Deep	100' Upstream 25' From Shore Shallow	100' Down Stream 25' From Shore Deep	100' Down Stream 25' From Shore Shallow	NYSDDEC Water Standard
Chloromethane	X-1	5 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	5
Vinyl Chloride			10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	5
Bromomethane			10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	5
Chloroethane			10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	5
Acetone			13 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	5
1,1-Dichloroethene			6 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	50 (GV)
Methylene Chloride			5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	NS
Carbon Disulfide			5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5
trans-1,2-Dichloroethene			5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	NS
1,1-Dichloroethane			5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5
2-Butanone-(MEK)			10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	5
cis-1,2-Dichloroethylene			5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	50 (GV)
Chloroform			5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	NS
1,2-Dichloroethane			5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	7
1,1,1-Trichloroethane			5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	0.6
Carbon Tetrachloride			5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5
Benzene			10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	5
1,2-Dichloropropane			5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5
Trichloroethane			5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	1
Bromodichloromethane			5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	1
cis-1,3-Dichloropropene			5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5
trans-1,3-Dichloropropene			5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	50 (GV)
1,1,2-Trichloroethene			5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	0.4*
Dibromochloromethane			5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	1
Bromoform			5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	50 (GV)
4-Methyl-2-Pentanone (MIBK)			10 U	10 U	4 U	10 U	10 U	10 U	10 U	10 U	NS
Toluene			5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5
2-Hexanone			10 U	10 U	5 U	5 U	5 U	5 U	5 U	5 U	5
Tetrachloroethene			5 U	5 U	5 U	5 U	5 U	5 U	10 U	10 U	50 (GV)
Chlorobenzene			5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5
Ethyl benzene			5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5
Syrene			5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5
Total Xylenes			6 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5
1,1,2,2-Tetrachloroethane			5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5

Note:

- * Standard applies to the sum of the cis and trans isomers.
- GV Indicates guidance value.

Table 19
Volatile Organic Analytical Data Summary - Sediment Freeport Creek
 Former Columbia Cement Company, Inc. Facility
 Freeport, New York
 Sampling Date: April 2000

Sample ID	100' Up Stream 25' From Shore	100' UP Stream 100' From Shore	100' UP Stream 200' From Shore	100' Down Stream 25' From Shore	100' Down Stream 100' From Shore	100' Down Stream 25' From Shore	200' Down Stream 50' From Shore	200' Down Stream 50' From Shore	200' Down Stream 100' From Shore	200' Down Stream From Shore	Out Fall	X-1 Out Fall
Chloromethane	12 U	17 U	22 U	8 U	17 U	18 U	25 U	20 U	19 U	8 U	8 U	8 U
Vinyl Chloride	25 U	34 U	43 U	15 U	34 U	35 U	49 U	40 U	38 U	15 U	15 U	15 U
Bromomethane	25 U	34 U	43 U	15 U	34 U	35 U	49 U	40 U	38 U	15 U	15 U	15 U
Chloroethene	25 U	34 U	43 U	15 U	34 U	35 U	49 U	40 U	38 U	15 U	15 U	15 U
Acetone	250	380	290	16	88	400	75	440	580	33	35	35
1,1-Dichloroethylene	12 U	17 U	22 U	8 U	17 U	18 U	25 U	20 U	19 U	8 U	8 U	8 U
Methylene Chloride	12 U	17 U	22 U	15 U	17 U	18 U	25 U	20 U	19 U	8 U	8 U	8 U
Carbon Disulfide	54	49	66	8 U	11 U	65	12 J	120	200	8 U	8 U	17 U
trans-1,2-Dichloroethylene	12 U	17 U	22 U	8 U	17 U	18 U	25 U	20 U	19 U	8 U	8 U	8 U
1,1-Dichloroethane	12 U	17 U	22 U	8 U	17 U	18 U	25 U	20 U	19 U	8 U	8 U	8 U
2-Butanone-(MEK)	66	110	83	15 U	34 U	130	49 U	140	170	15 U	15 U	15 U
cis-1,2-Dichloroethane	12 U	17 U	22 U	8 U	17 U	18 U	25 U	20 U	19 U	8 U	8 U	8 U
Chloroform	12 U	17 U	22 U	13	17 U	18 U	25 U	20 U	19 U	8 U	8 U	8 U
1,2-Dichloroethane	12 U	17 U	22 U	8 U	17 U	18 U	25 U	20 U	19 U	2 J	9	9
1,1,1-Trichloroethane	12 U	17 U	22 U	8 U	17 U	18 U	25 U	20 U	19 U	8 U	8 U	8 U
Carbon Tetrachloride	25 U	34 U	43 U	15 U	34 U	35 U	49 U	40 U	38 U	15 U	15 U	15 U
Benzene	12 U	17 U	22 U	8 U	17 U	18 U	25 U	20 U	19 U	8 U	8 U	8 U
1,2-Dichloropropane	12 U	17 U	22 U	8 U	17 U	18 U	25 U	20 U	19 U	8 U	8 U	8 U
Trichloroethene	12 U	17 U	22 U	8 U	17 U	18 U	25 U	20 U	19 U	8 U	8 U	8 U
Bromo dichloromethane	12 U	17 U	22 U	8 U	17 U	18 U	25 U	20 U	19 U	8 U	8 U	8 U
cis-1,3-Dichloropropene	12 U	17 U	22 U	8 U	17 U	18 U	25 U	20 U	19 U	8 U	8 U	8 U
trans-1,3-Dichloropropene	12 U	17 U	22 U	8 U	17 U	18 U	25 U	20 U	19 U	8 U	8 U	8 U
1,1,2-Trichloropropane	12 U	17 U	22 U	8 U	17 U	18 U	25 U	20 U	19 U	8 U	8 U	8 U
Dibromo dichloromethane	12 U	17 U	22 U	8 U	17 U	18 U	25 U	20 U	19 U	8 U	8 U	8 U
Bromodform	12 U	17 U	22 U	8 U	17 U	18 U	25 U	20 U	19 U	8 U	8 U	8 U
4-Methyl-2-Pentanone (MIBK)	25 U	34 U	43 U	15 U	34 U	35 U	49 U	40 U	38 U	15 U	15 U	15 U
Toluene	7 J	17 U	22 U	8 U	17 U	18 U	25 U	20 U	19 U	8 U	8 U	8 U
2-Hexanone	25 U	34 U	43 U	15 U	34 U	35 U	49 U	40 U	38 U	15 U	15 U	15 U
Tetrachloroethene	12 U	17 U	22 U	8 U	17 U	18 U	25 U	20 U	19 U	8 U	8 U	8 U
Chlorobenzene	12 U	17 U	22 U	8 U	17 U	18 U	25 U	20 U	19 U	8 U	8 U	8 U
Ethybenzene	12 U	17 U	22 U	8 U	17 U	18 U	25 U	20 U	19 U	8 U	8 U	8 U
Styrene	12 U	17 U	22 U	8 U	17 U	18 U	25 U	20 U	19 U	8 U	8 U	8 U
Total Xylenes	12 U	17 U	22 U	8 U	17 U	18 U	25 U	20 U	19 U	8 U	8 U	8 U
1,1,2-Tetrachloroethane	12 U	17 U	22 U	8 U	17 U	18 U	25 U	20 U	19 U	8 U	8 U	8 U
Total Organic Carbon (mg/Kg)	495	720	1010	397	880	3160	1180	1130	1100	575	450	450
Percent Solids	40.7	29	27	77	29.6	28.4	20.4	20.2	20.4	65.8	65	65

Table 20

**Physical/Chemical Properties
Chemicals of Concern**
Former Columbia Cement Company, Inc. Facility
Freeport, New York

COMPOUND	Solubility mg/L	Density g/mL	Partition Coefficient mL/g OC	Henry's Law Constant atm m3/mol	Octanol/Water Partition Coefficient Log Kow	Bioconcentration Factor (Fish)
1,1,1-Trichloroethane	1,334	1.3376	152	2.76E-02	2.5	5.6
1,1-Dichloroethane	5,500	1.174	30	4.31E-03	1.79	Low
1,1-Dichloroethene	2,225	1.218	65	3.40E-02	1.84	5.6
Acetone					-2.40E-01	Low
Benzene	1,750	0.8786	2.2	2.06E-05	2.12	5.2
Chloroethane	5,740	0.92	83	5.59E-03	1.49	Low
Ethylbenzene	152	0.867	37	6.15E-04	3.15	37.5
Methylene Chloride	20,000	1.3266	1100	6.43E-03	1.3	5
Toluene	535	0.867	8.8	2.03E-03	2.73	10.7
Vinyl Chloride	2,670	0.9121	300	6.37E-03	1.38	1.17
Xylene	198	0.868	57	8.19E-02	7.04E-03	3.26

References

NYSDEC Technical and Administrative Guidance Memorandum, Determination of Soil Cleanup Objectives and Cleanup Levels, JWR-94-4046, January 24, 1991

United States Environmental Protection Agency, Chemical Summary For Methylchloroform, EPA 749-f-94-014a, August 1994

USEPA, Superfund Public Health Evaluation Manual, EPA 540/1-86/060, 1986

United States Army Corps of Engineers, Riverine Emergency Management Model, Chemical Properties Table, August 1997

Verschueren, K., Handbook of Environmental Data on Organic Chemicals, Van Nostrand Reinhold Company, 1983

Table 21
Former Columbia Cement Company, Inc., Facility
Vegetation Identified in Natural Areas
Within One-Half Mile of the Site

Successional Shrub Field (SSF)

White Birch	<i>Betula papyrifera</i>
Pitch Pine	<i>Pinus rigida</i>
White Cedar	<i>Chamaccyparis thyoides</i>
Ailanthus	<i>Ailanthus altissima</i>
Staghorn Sumac	<i>Rhus typhina</i>
Tartarian Honeysuckle	<i>Lonicera tatarica</i>
Arrowwood	<i>Viburnum dentatum</i>
Pin Oak	<i>Quercus palustris</i>
White Poplar	<i>Populus alba</i>
Weeping Willow	<i>Salix babylonica</i>
Bay Berry	<i>Myrica heterophylla</i>
Groundsel tree	<i>Baccharis halimifolia</i>
Japanese Honeysuckle	<i>Lonicera Japonica</i>
Common Reed	<i>Phragmites australis</i>
Glass Wort	<i>Salicornia europaca</i>
Seaside Golden Rod	<i>Solidago sempervirens</i>
Red Raspberry	<i>Rubus strigosus</i>
Poke Weed	<i>Phytolacca rigida</i>

SMG: Salt Marsh Grass

Spartina species

Table 22
Former Columbia Cement Co., Inc., Facility
Mammal/Amphibian/Reptile/Fish /Bird Species That Could Potentially
Utilize Habitats Within One-Half Mile Of The Site

COMMON NAME	GENUS AND SPECIES
<u>Mammals</u>	
Eastern Cottontail	<i>Sylvilagus floridanus</i>
Star-nosed Mole	<i>Condylura cristata</i>
Deer Mouse	<i>Peromyscus maniculatus</i>
House Mouse	<i>Mus musculus</i>
Meadow Jumping Mouse	<i>Zapus hudsonius</i>
House Mouse	<i>Mus musculus</i>
Raccoon	<i>Procyon lotor</i>
Norway Rat	<i>Rattus norvegicus</i>
Striped Skunk	<i>Mephitis mephitis</i>
Gray Squirrel	<i>Sciurus carolinensis</i>
Eastern Chipmunk	<i>Tamias striatus</i>
Eastern Mole	<i>Scalopus aquaticus</i>
Opossum	<i>Didelphis virginiana</i>
Meadow Vole	<i>Microtus pennsylvanicus</i>
Muskrat	<i>Ondatra zibethicus</i>
<u>Amphibians/Reptiles</u>	
Diamondback Terrapin	<i>Malaclemys terrapin</i>
Bull Frog	<i>Rana catesbeiana</i>
Green Frog	<i>Rana clamitans</i>
Pickerel Frog	<i>Rana palustris</i>
Spring Peeper	<i>Hyla crucifer</i>
Brown Snake	<i>Storeria dekayi</i>
Eastern Ribbon Snake	<i>Thamnophis sauritus</i>
Northern Water Snake	<i>Nerodia sipedon</i>
<u>Fish</u>	
Blue Fish	<i>Pomatomus saltatrix</i>
Winter Flounder	<i>Pleuronectes americanus</i>
Fluke	<i>Paralichthys dentatus</i>
Atlantic Mackerel	<i>Scomber scombrus</i>
Scup	<i>Stenotomus chrysops</i>
Cunner	<i>Tautogolabrus adspersus</i>
Striped Bass	<i>Morone saxatilis</i>
Skates	<i>Rajidae</i>
Atlantic Silversides	<i>Menidia menidia</i>

COMMON NAME	GENUS AND SPECIES
Birds	
American Crow	<i>Corvus brachyrhynchos</i>
American Goldfinch	<i>Carduelis tristis</i>
American Kestrel	<i>Falco sparverius</i>
American Robin	<i>Turdus migratorius</i>
Barn Swallow	<i>Hirundo rustica</i>
Black-capped Chickadee	<i>Parus atricapillus</i>
Blue Jay	<i>Cyanocitta cristata</i>
Brown-headed Cowbird	<i>Molothrus ater</i>
Bufflehead	<i>Bucephala albeola</i>
Canada Goose	<i>Branta canadensis</i>
Chimney Swift	<i>Chaetura pelagica</i>
Common Erget	<i>Casmerodius albus</i>
Common Goldeneye	<i>Bucephala clangula americana</i>
Common Grackle	<i>Quiscalus quiscula</i>
Common Merganser	<i>Mergus merganser americanus</i>
Common Tern	<i>Sterna hirundo</i>
Cormorant	<i>Phalacrocorax auritus</i>
Eastern Phoebe	<i>Sayornis phoebe</i>
European Starling	<i>Sturnus vulgaris</i>
Glossy Ibis	<i>Plegadis falcinellus</i>
Great Blue Heron	<i>Ardea herodias</i>
Great Egret	<i>Ardea alba</i>
Greater Scaup	<i>Aythya marila mariloides</i>
Herring Gulls	<i>Larus argentatus</i>
Hooded Merganser	<i>Mergus cucullatus</i>
House Sparrow	<i>Passer domesticus</i>
Killdeer	<i>Charadrius vociferus</i>
Least Tern	<i>Sterna antillarum</i>
Lesser Scaup	<i>Aythya affinis</i>
Little Blue Heron	<i>Egretta caerulea</i>
Mallard	<i>Anas platyrhynchos</i>
Mourning Dove	<i>Zenaida macroura</i>
Northern Cardinal	<i>Cardinalis cardinalis</i>
Old Squaw	<i>Clangula hyemalis</i>
Red-winged Blackbird	<i>Agelaius phoeniceus</i>
Rough-winged Swallow	<i>Stelgidopteryx ruficollis</i>
Snowy Egret	<i>Egretta thula</i>
Song Sparrow	<i>Melospiza melodia</i>
Spotted Sandpiper	<i>Actitis macularia</i>
Yellow- Crowned Night-Heron	<i>Nyctanassa violacea</i>

Invertebrates	
Atlantic Horseshoe Crab	<i>Limulus polyphemus</i>
Long finned Squid	<i>Loligo pealei</i>
Short finned Squid	<i>Illex illecebrosus</i>
New England Neptune	<i>Neptuna decemcostata</i>
Knobbed Whelk	<i>Busycon carica</i>
Northern Lobster	<i>Homarus americanus</i>

COMMON NAME	GENUS AND SPECIES
Northern Seastar	<i>Asterias vulgaris</i>
Spider Crab	<i>Halicarcinus maenas</i>
Northern Quahog	<i>Mercenaria mercenaria</i>
Blue Mussels	<i>Mytilus edulis</i>
Moon Jelly	<i>Aurelia aurita</i>
Acorn Barnacles	<i>Balanus eburneus</i>
Common Periwinkles	<i>Littorina littorea</i>
Common Northern Moon Snail	<i>Lunatia heros</i>

APPENDIX B
SOIL BORING LOGS


URS CORPORATION

Soil Boring Log

Location of Boring


See Figure 2 for boring location

Job No.: 38546433	Client: BP ATLANTIC RICHFIELD	Location: COLUMBIA CEMENT FREEPORT, NY
Logged By: Driller:	ANDREW KOHLBECKER ZEBRA ENVIRONMENTAL, INC	Boring No.: T-01
Drilling Method: Sampling Method:	2" GEOPROBE GEOPROBE DIRECT PUSH	Sheet: 2 of 2 Drilling
Water Level: Depth of Screen: Depth of Gravel: Depth of Bentonite:	~7 FEET BELOW GRADE N/A N/A N/A	Start Time Finish Time 9:57 10:43 Date Date 10/6/2004 10/6/2004



URS CORPORATION

Soil Boring Log




URS CORPORATION

Soil Boring Log

Location of Boring See Figure 2 for boring location							Job No.: 38546433	Client: BP ATLANTIC RICHFIELD	Location: COLUMBIA CEMENT FREEPORT, NY
							Logged By: ANDREW KOHBECKER	Boring No.: T-02	
							Driller: ZEBRA ENVIRONMENTAL, INC		Sheet: 2 of 2
							Drilling Method: 2" GEOPROBE		Drilling
							Sampling Method: GEOPROBE DIRECT PUSH	Start Time 10:49	Finish Time 11:36
							Water Level: ~7 FEET BELOW GRADE		
							Depth of Screen: N/A		
							Depth of Gravel: N/A	Date 10/6/2004	Date 10/6/2004
							Depth of Bentonite: N/A		
Sampler Type	Sample No.	Inches Driv.	Blow Count /	PID (ppm)	Analytical Sa	Depth (ft.)	Soil Graph	Surface Conditions	
		48		0.0		21	SP	Black medium to coarse SAND with fine gravel, medium dense, wet	
		24		0.0		22		Grading with slight odor	
				3.9		23			
				0.0		24		Light grey medium to coarse SAND with fine gravel, loose, wet	
				0.0		25			
		48		0.0		26	SP	Grey medium to fine SAND, medium dense, wet	
		36		0.0		27			
				0.0		28		Grey medium to fine micaeous SAND, dense, wet	
				0.0		29			
				0.0		30			
		48		0.0		31	EOB	Grey medium to coarse SAND, some medium rounded gravel, dense, wet	
				0.0		32			
				0.0		33			
				0.0		34		NOTES:	
				0.0		35		1. SAMPLE DEPTH TIME ANALYSIS	
						36		T-02-16-18 16-18 11:05 VOC	
						37		T-02-20-22 20-22 11:15 VOC	
						38		T-02-24-26 24-26 11:25 VOC	
						39		T-02-28-30 28-30 11:35 VOC	
						40	2. EVIDENCE OF CONTAMINATION		
								ODOR: 22 - 23 fbg	
								STAINING: None	
							3. DEPTH OF BORING - 32 FEET BELOW GROUND SURFACE		

URS CORPORATION
Soil Boring Log

Location of Boring See Figure 2 for boring location	Job No.:	Client:	Location:
	38546433	BP ATLANTIC RICHFIELD	COLUMBIA CEMENT FREEPORT, NY
	Logged By:	ANDREW KOHLBECKER	Boring No.:
	Driller:	ZEBRA ENVIRONMENTAL, INC	T-03
	Drilling Method:	2" GEOPROBE	Sheet:
	Sampling Method:	GEOPROBE DIRECT PUSH	1 of 2
	Water Level:	~7 FEET BELOW GRADE	Drilling
	Depth of Screen:	N/A	Start Time
	Depth of Gravel:	N/A	Finish Time
	Depth of Bentonite:	N/A	Date



URS CORPORATION

Soil Boring Log


Location of Boring See Figure 2 for boring location	Job No.:	Client:	Location:
	38546433	BP ATLANTIC RICHFIELD	COLUMBIA CEMENT FREEPORT, NY
	Logged By:	ANDREW KOHLBECKER	Boring No.:
	Driller:	ZEBRA ENVIRONMENTAL, INC	T-03
	Drilling Method:	2" GEOPROBE	Sheet:
	Sampling Method:	GEOPROBE DIRECT PUSH	2 of 2
	Water Level:	~7 FEET BELOW GRADE	Drilling
	Depth of Screen:	N/A	Start Time
	Depth of Gravel:	N/A	Finish Time
	Depth of Bentonite:	N/A	Date

11:47 12:27
Date Date
10/6/2004 10/6/2007

Sampler Type	Sample No./ Inches Driv./ ft.	Blow Count / PfD (ppm)	Analytical Sa	Depth (ft.)	Soil Graph	Surface Conditions
						Black organic CLAY, soft, moist
	48	0.0	OH	21	SP	Gading with organic odor, oily residue on Macrocore
				22		Dark brown medium SAND with peat, trace fine gravel, wet
				23		
				24		Light grey medium to coarse SAND with fine gravel, medium dense, wet
				25		
				26		
				27		Grey fine to medium SAND, medium dense, wet
				28		
				29		
				30		
	44	0.2	SP	31	EOB	
				32		
				33		
				34		NOTES:
				35		1. SAMPLE DEPTH TIME ANALYSIS
				36		T-03-16-18 16-18 11:55 VOC
				37		T-03-20-22 20-22 12:05 VOC
				38		T-03-24-26 24-26 12:15 VOC
				39		T-03-28-30 28-30 12:25 VOC
				40		
	48	0.0	EOB	35		2. EVIDENCE OF CONTAMINATION
				36		ODOR: 21-22 fbg
				37		STAINING: 21-22 fbg
				38		
				39		
				40		3. DEPTH OF BORING - 32 FEET BELOW GROUND SURFACE
				35		
				36		
				37		
				38		

URS CORPORATION

Soil Boring Log

<p>Location of Boring See Figure 2 for boring location</p>						Job No.:	Client:	Location:	
						38546433	BP ATLANTIC RICHFIELD	COLUMBIA CEMENT FREEPORT, NY	
						Logged By:	ANDREW KOHLBECKER	Boring No.:	
						Driller:	ZEBRA ENVIRONMENTAL, INC	T-04	
						Drilling Method:	2" GEOPROBE	Sheet:	
						Sampling Method:	GEOPROBE DIRECT PUSH	1 of 2	
						Water Level:	~7 FEET BELOW GRADE	Drilling	
						Depth of Screen:	N/A	Start Time	
						Depth of Gravel:	N/A	Finish Time	
						Depth of Bentonite:	N/A	Date	
		10/6/2004	10/6/2004						
Sampler Type 	Sample No. / Depth Inches Driv. / Recov	Blow Count / 6"	PID (ppm)	Analytical Sample	Depth (ft.)	Soil Graph	Surface Conditions CRUSHED GRAVEL FILL		
							Advanced boring through backfill to 12'.		
							1		
							2		
							Crushed stone backfill		
							3		
							4		
							FILL		
							5		
							6		
							7		
							▼		
							8		
							9		
							10		
							11		
							12		
						SC	Dark greyish brown medium to coarse SAND with fine gravel, medium dense, wet		
						SM	Dark brown silty fine to medium SAND with debris (wood, glass, plastic), odor noted, loose, wet		
						OH/PT	Dark brown silty fine to medium SAND with debris, loose, wet		
						OH/PT	Dark brown silty fine to medium SAND with landfill debris, loose, wet		
						OH/PT	Dark brown organic CLAY with plant matter, soft, moist		
						OH/PT	20		


URS CORPORATION

Soil Boring Log

Location of Boring See Figure 2 for boring location						Job No.: 38546433	Client: BP ATLANTIC RICHFIELD	Location: COLUMBIA CEMENT FREEPORT, NY
						Logged By: ANDREW KOHLBECKER	Boring No.: T-04	
						Driller: ZEBRA ENVIRONMENTAL, INC	Sheet: 2 of 2	
						Drilling Method: 2" GEOPROBE	Drilling	
						Sampling Method: GEOPROBE DIRECT PUSH	Start Time	Finish Time
						Water Level: ~7 FEET BELOW GRADE	12:45	13:28
						Depth of Screen: N/A		
						Depth of Gravel: N/A	Date	Date
						Depth of Bentonite: N/A	10/6/2004	10/6/2004
Sampler Type	Sample No.	Inches Driv.	Blow Count /	PID (ppm)	Analytical S	Depth (ft.)	Soil Graph	Surface Conditions
		48		0.0		21	OH/PT	Dark brown organic CLAY, 6" of peat, soft, moist
		44		0.0		22	SP	Light grey medium to coarse SAND with fine gravel, medium dense, wet
				0.0		23		
				0.0		24		
		48		0.0		25		
		48		0.0		26		Grey medium to fine SAND, dense, wet
				0.0		27		
				0.0		28	SP	
		48		0.0		29		
		48		0.0		30		
				0.0		31		
				0.0		32	EOB	
						33		
						34		NOTES:
						35		1. SAMPLE DEPTH TIME ANALYSIS
						36		T-04-16-18 16-18 13:00 VOC
						37		T-04-20-22 20-22 13:10 VOC
						38		T-04-24-26 24-26 13:20 VOC
						39		T-04-28-30 28-30 13:30 VOC
						40		2. EVIDENCE OF CONTAMINATION
								ODOR: 13-16 fbg
								STAINING: None
								3. DEPTH OF BORING - 32 FEET BELOW GROUND SURFACE

URS CORPORATION

Soil Boring Log



URS CORPORATION

Soil Boring Log

Location of Boring


See Figure 2 for boring location

Job No.: 38546433	Client: BP ATLANTIC RICHFIELD	Location: COLUMBIA CEMENT FREEPORT, NY
Logged By:	ANDREW KOHLBECKER	Boring No.:
Driller:	ZEBRA ENVIRONMENTAL, INC	T-05
Drilling Method:	2" GEOPROBE	Sheet:
Sampling Method:	GEOPROBE DIRECT PUSH	2 of 2 Drilling
Water Level:	~7 FEET BELOW GRADE	Start Time Finish Time 13:38 14:20
Depth of Screen:	N/A	
Depth of Gravel:	N/A	Date Date
Depth of Bentonite:	N/A	10/6/2004 10/6/2004

URS CORPORATION

Soil Boring Log

Location of Boring See Figure 2 for boring location		Job No.: 38546433	Client: BP REMEDIATION MANAGEMENT	Location: COLUMBIA CEMENT CO. FREEPORT, NY
Logged By: ANDREW KOHLBECKER		Boring No.: T-06		
Driller: ZEBRA ENVIRONMENTAL, INC		Sheet: 1 of 2		
Drilling Method: 2" GEOPROBE		Sampling Method: GEOPROBE DIRECT PUSH		Drilling
Water Level: ~7 FEET BELOW GRADE		Start Time	Finish Time	
Depth of Screen: N/A				
Depth of Gravel: N/A		Date	Date	
Depth of Bentonite: N/A		10/6/2004	10/6/2004	




URS CORPORATION

Soil Boring Log

Location of Boring See Figure 2 for boring location						Job No.:	Client:	Location:		
						38546433	BP REMEDIATION MANAGEMENT	COLUMBIA CEMENT CO. FREEPORT, NY		
						Logged By:	ANDREW KOHLBECKER	Boring No.:		
						Driller:	ZEBRA ENVIRONMENTAL, INC	T-06		
						Drilling Method:	2" GEOPROBE	Sheet:		
						Sampling Method:	GEOPROBE DIRECT PUSH	2 of 2		
						Water Level:	-7 FEET BELOW GRADE	Start Time	Finish Time	
						Depth of Screen:	N/A	14:35	15:30	
						Depth of Gravel:	N/A	Date	Date	
						Depth of Bentonite:	N/A	10/6/2004	10/6/2004	
Surface Conditions										
Sampler Type	Sample No.	Inches Driv.	Blow Count /	PID (ppm)	Analytical S	Depth (ft.)	Soil Graph			
		48		0.0		21	SP	Light gray gravelly SAND, medium dense, wet		
		34		0.0		22				
				0.0		23				
				0.0		24				
		48		0.0		25		Light gray to medium coarse SAND with some gravel, medium dense, wet		
		30		0.0		26				
				0.0		27				
				0.0		28		Gray medium to fine SAND, dense, wet		
		48		0.0		29				
				0.0		30				
				0.0		31				
				0.0		32	EOB			
						33				
						34	NOTES:			
						35	1 SAMPLE DEPTH TIME ANALYSIS			
						36	T-06-16-18	16-18	14:50	VOC
						37	T-06-20-22	20-22	15:05	VOC
						38	T-06-24-26	24-26	15:15	VOC
						39	T-06-28-30	28-30	15:30	VOC
						40	2 EVIDENCE OF CONTAMINATION			
							ODOR: None			
							STAINING: None			
							3 DEPTH OF BORING - 32 FEET BELOW GROUND SURFACE			

URS CORPORATION
Soil Boring Log

Location of Boring See Figure 2 for boring location	Job No.:	Client:	Location:
	38546433	BP ATLANTIC RICHFIELD	COLUMBIA CEMENT FREEPORT, NY
	Logged By:	ANDREW KOHLBECKER	Boring No.:
	Driller:	ZEBRA ENVIRONMENTAL, INC	T-07
	Drilling Method:	2" GEOPROBE	Sheet:
	Sampling Method:	GEOPROBE DIRECT PUSH	1 of 2
	Water Level:	-7 FEET BELOW GRADE	Drilling
	Depth of Screen:	N/A	Start Time
	Depth of Gravel:	N/A	Finish Time
	Depth of Bentonite:	N/A	Date
			10/7/2004
			10/7/2004



URS CORPORATION

Soil Boring Log

Location of Boring See Figure 2 for boring location		Job No.: 38546433	Client: BP ATLANTIC RICHFIELD	Location: COLUMBIA CEMENT FREEPORT, NY
		Logged By: Driller:	ANDREW KOHLBECKER ZEBRA ENVIRONMENTAL, INC	Boring No.: T-07
		Drilling Method:	2" GEOPROBE	Sheet: 2 of 2
		Sampling Method:	GEOPROBE DIRECT PUSH	Drilling
		Water Level:	~7 FEET BELOW GRADE	Start Time Finish Time 8:25 9:25
		Depth of Screen:	N/A	
		Depth of Gravel:	N/A	Date Date 10/7/2004 10/7/2004
		Depth of Bentonite:	N/A	

Sampler Type	Sample No./ Inches Driv.	Blow Count /	PID (ppm)	Analytical Se	Depth (ft.)	Soil Graph	Surface Conditions			
		48	0.0		21	SC	Brown to gray gravelly SAND, medium dense, wet			
		6	0.0		22					
			0.0		23					
			0.0		24		Light gray SAND, some rounded gravel, medium dense, wet			
		48	0.0		25	SC				
		24	0.0		26					
			0.0		27					
			0.0		28		Gray fine to medium SAND, well sorted, dense, wet			
		48	0.1		29	SC				
		24	0.1		30					
			0.1		31					
			0.1		32	EOB				
					33					
					34		NOTES:			
					35		1 SAMPLE DEPTH TIME ANALYSIS			
					36		T-07-16-18 16-18 8:45 VOC			
					37		T-07-20-22 20-22 9:00 VOC			
					38		T-07-24-26 24-26 9:10 VOC			
					39		T-07-28-30 28-30 9:25 VOC			
					40		2 EVIDENCE OF CONTAMINATION			
							ODOR: None			
							STAINING: None			
							3 DEPTH OF BORING - 32 FEET BELOW GROUND SURFACE			

URS CORPORATION

Soil Boring Log

Location of Boring See Figure 2 for boring location						Job No.: 38546433	Client: BP ATLANTIC RICHFIELD	Location: COLUMBIA CEMENT FREEPORT, NY
						Logged By: ANDREW KOHLBECKER	Boring No.:	
						Driller: ZEBRA ENVIRONMENTAL, INC	T-08	
						Drilling Method: 2" GEOPROBE	Sheet: 1 of 2	
						Sampling Method: GEOPROBE DIRECT PUSH	Drilling	
						Water Level: ~7 FEET BELOW GRADE	Start Time 9:30	Finish Time 10:10
						Depth of Screen: N/A	Date 10/7/2004	Date 10/7/2004
						Depth of Gravel: N/A		
						Depth of Bentonite: N/A		
Sampler Type	Sample No. / Depth	Inches Driv. / Recov.	Blow Count / 6"	PID (ppm)	Analytical Sample	Depth (ft.)	Soil Graph	Surface Conditions
						1		
						2		
						3		
						4		
						5	FILL	
						6		
						7		
						8		
						9		
						10		
						11		
						12		Orange coarse to fine SAND, some silt, loose, wet (Fill)
	48	24		0.0		13	FILL	
				0.0		14		
				56.6		15		Gray organic CLAY, medium stiff, moist
				12.2		16	OH	
	48			0.0		17		
				14.8		18		
				0.5		19	SW	Brown - reddish brown gravelly SAND, medium dense, wet
				0.5		20		


URS CORPORATION

Soil Boring Log

Location of Boring See Figure 2 for boring location						Job No.: 38546433	Client: BP ATLANTIC RICHFIELD	Location: COLUMBIA CEMENT FREEPORT, NY
						Logged By: ANDREW KOHLBECKER	Boring No.: T-08	
						Driller: ZEBRA ENVIRONMENTAL, INC		
						Drilling Method: 2" GEOPROBE	Sheet:	2 of 2
						Sampling Method: GEOPROBE DIRECT PUSH	Drilling	
						Water Level: ~7 FEET BELOW GRADE	Start Time	Finish Time
						Depth of Screen: N/A	9:30	10:10
						Depth of Gravel: N/A	Date	Date
						Depth of Bentonite: N/A	10/7/2004	10/7/2004
Sampler Type	Sample No. /	Inches Driv. /	Blow Count /	PID (ppm)	Analytical Se	Depth (ft.)	Soil Graph	Surface Conditions
		48		0.6		21		Brown/reddish brown gravelly SAND, medium dense, wet
		30		0.6		22		
				0.6		23		
				0.6		24		Grades into a light gray medium to coarse SAND
		48		0.6		25		
		24		0.6		26		
				0.6		27		
				0.9		28	GP	Light gray sandy GRAVEL, wet
		48		0.0		29		Gray coarse to medium SAND with fine gravel, wet
		24		0.0		30		
				0.7		31		
				0.9		32	SW	
						33		
						34		EOB
						35		NOTES:
						36		1 SAMPLE DEPTH TIME ANALYSIS
						37		T-08-14-15 14-15 9:35 VOC
						38		T-08-16-18 16-18 9:45 VOC
						39		T-08-20-22 20-22 9:50 VOC
						40		T-08-24-26 24-26 10:00 VOC
								T-08-28-30 28-30 10:10 VOC
								2 EVIDENCE OF CONTAMINATION
								ODOR: None
								STAINING: None
								3 DEPTH OF BORING - 32 FEET BELOW GROUND SURFACE

URS CORPORATION


Soil Boring Log



URS CORPORATION

Soil Boring Log

Location of Boring See Figure 2 for boring location	Job No.:	Client:	Location:
	38546433	BP ATLANTIC RICHFIELD	COLUMBIA CEMENT FREEPORT, NY
	Logged By:	ANDREW KOHLBECKER	Boring No.:
	Driller:	ZEBRA ENVIRONMENTAL, INC	T-09
	Drilling Method:	2" GEOPROBE	Sheet:
	Sampling Method:	GEOPROBE DIRECT PUSH	2 of 2
	Water Level:	~7 FEET BELOW GRADE	Drilling
	Depth of Screen:	N/A	Start Time
	Depth of Gravel:	N/A	Finish Time
	Depth of Bentonite:	N/A	Date
			10/7/2004
			10/7/2004




URS CORPORATION

Soil Boring Log

Location of Boring

See Figure 2 for boring location

Job No.: 38546433	Client: BP ATLANTIC RICHFIELD	Location: COLUMBIA CEMENT FREEPORT, NY	
Logged By:	ANDREW KOHLBECKER	Boring No.:	
Driller:	ZEBRA ENVIRONMENTAL, INC	T-10	
Drilling Method:	2" GEOPROBE	Sheet: 1 of 2	
Sampling Method:	GEOPROBE DIRECT PUSH	Drilling	
Water Level:	-7 FEET BELOW GRADE	Start Time	Finish Time
Depth of Screen:	N/A	11:25	11:55
Depth of Gravel:	N/A	Date	Date
Depth of Bentonite:	N/A	10/7/2004	10/7/2004



URS CORPORATION

Soil Boring Log

Location of Boring See Figure 2 for boring location						Job No.: 38546433	Client: BP ATLANTIC RICHFIELD	Location: COLUMBIA CEMENT FREEPORT, NY
						Logged By: ANDREW KOHLBECKER	Boring No.: T-10	
						Driller: ZEBRA ENVIRONMENTAL, INC		
						Drilling Method: 2" GEOPROBE	Sheet: 2 of 2	
						Sampling Method: GEOPROBE DIRECT PUSH	Drilling	
						Water Level: -7 FEET BELOW GRADE	Start Time 11:25	Finish Time 11:55
						Depth of Screen: N/A		
						Depth of Gravel: N/A	Date 10/7/2004	Date 10/7/2004
						Depth of Bentonite: N/A		
Sampler Type	Sample No.	Inches Driv./	Blow Count /	PID (ppm)	Analytical Se	Depth (ft.)	Soil Graph	Surface Conditions
		48		0.2		21	SP/ OL	Gravelly SAND with dark brown organic silty clay, wet
		30		0.2		22		
				0.3		23		Brown medium to coarse SAND with dark brown organic silty clay, wet
				0.3		24		Brown SAND and rounded fine GRAVEL (1/4-1/2" dia)
		48		0.3		25	SP	
		24		0.3		26		
				0.3		27		
				0.3		28		Light gray medium to coarse SAND, some rounded fine gravel, wet
		48		0.0		29		
		30		0.0		30		
				0.4		31		
				0.6		32	EOB	
						33		
						34		NOTES:
						35		1 SAMPLE DEPTH TIME ANALYSIS
						36		T-10-16-18 16-18 11:30 VOC
						37		T-10-20-22 20-22 11:40 VOC
						38		T-10-24-26 24-26 11:45 VOC
						39		T-10-28-30 31-32 11:55 VOC
						40		2 EVIDENCE OF CONTAMINATION ODOR: None STAINING: None
							3 DEPTH OF BORING - 32 FEET BELOW GROUND SURFACE	


URS CORPORATION

Soil Boring Log

Location of Boring

See Figure 2 for boring location

Job No.: 38546433	Client: BP ATLANTIC RICHFIELD	Location: COLUMBIA CEMENT FREEPORT, NY
Logged By:	ANDREW KOHLBECKER	Boring No.:
Driller:	ZEBRA ENVIRONMENTAL, INC	D-01
Drilling Method:	2" GEOPROBE	Sheet:
Sampling Method:	GEOPROBE DIRECT PUSH	1 of 2
Water Level:	-7 FEET BELOW GRADE	Drilling
Depth of Screen:	N/A	Start Time
Depth of Gravel:	N/A	12:30
Depth of Bentonite:	N/A	Finish Time
		13:20
	Date	Date
	10/7/2004	10/7/2004




URS CORPORATION

Soil Boring Log

Location of Boring See Figure 2 for boring location						Job No.: 38546433	Client: BP ATLANTIC RICHFIELD	Location: COLUMBIA CEMENT FREEPORT, NY
						Logged By: ANDREW KOHLBECKER	Boring No.: D-01	
						Driller: ZEBRA ENVIRONMENTAL, INC	Sheet:	
						Drilling Method: 2" GEOPROBE	2 of 2	
						Sampling Method: GEOPROBE DIRECT PUSH	Drilling	
						Water Level: ~7 FEET BELOW GRADE	Start Time 12:30	Finish Time 13:20
						Depth of Screen: N/A		
						Depth of Gravel: N/A	Date 10/7/2004	Date 10/7/2004
						Depth of Bentonite: N/A		
Sampler Type	Sample No.	Inches Driv.	Blow Count /	PID (ppm)	Analytical Sa	Depth (ft.)	Soil Graph	Surface Conditions
		48	30	1.2		21		Gray medium SAND and rounded fine GRAVEL, loose, wet
				1.2		22		
				1.2		23		
				1.2		24		Gray medium to coarse SAND and rounded fine GRAVEL, loose, wet
		48	24	1.2		25		
				1.2		26		
				1.2		27		
				1.2		28		Grey medium SAND, dense, wet
		48	24	7.1		29		
				7.1		30		Grading with fine gravel
				7.1		31		
				7.1		32		
						33		NOTES:
						34		1 SAMPLE DEPTH TIME ANALYSIS
						35		D-01-10-12 6-8 12:40 VOC
						36		D-01-16-18 15-16 12:50 VOC
						37		D-01-20-22 16-18 12:55 VOC
						38		D-01-24-26 20-22 13:05 VOC
						39		D-01-28-30 24-26 13:15 VOC
						40		D-01-32-34 28-30 13:20 VOC
								2 EVIDENCE OF CONTAMINATION
								ODOR: None
								STAINING: None
								3 DEPTH OF BORING - 32 FEET BELOW GROUND SURFACE

URS CORPORATION
Soil Boring Log


Location of Boring See Figure 2 for boring location	Job No.:	Client:	Location:
	38546433	BP ATLANTIC RICHFIELD	COLUMBIA CEMENT FREEPORT, NY
	Logged By:	ANDREW KOHLBECKER	Boring No.:
	Driller:	ZEBRA ENVIRONMENTAL, INC	D-02
	Drilling Method:	2" GEOPROBE	Sheet:
			1 of 2
	Sampling Method:	GEOprobe DIRECT PUSH	Drilling
	Water Level:	~7 FEET BELOW GRADE	Start Time
	Depth of Screen:	N/A	Finish Time



URS CORPORATION

Soil Boring Log

Location of Boring See Figure 2 for boring location		Job No.: 38546433	Client: BP ATLANTIC RICHFIELD	Location: COLUMBIA CEMENT FREEPORT, NY
		Logged By: Driller:	ANDREW KOHLBECKER ZEBRA ENVIRONMENTAL, INC	Boring No.: D-02
		Drilling Method:	2" GEOPROBE	Sheet: 2 of 2
		Sampling Method:	GEOPROBE DIRECT PUSH	Drilling
		Water Level:	~7 FEET BELOW GRADE	Start Time Finish Time 1335 1415
		Depth of Screen:	N/A	
		Depth of Gravel:	N/A	Date Date 10/7/2004 10/7/2004
		Depth of Bentonite:	N/A	




URS CORPORATION

Soil Boring Log

Location of Boring

See Figure 2 for boring location

Job No.:	Client: BP ATLANTIC RICHFIELD	Location: COLUMBIA CEMENT FREEPORT, NY	
38546433			
Logged By:	ANDREW KOHLBECKER	Boring No.:	
Driller:	ZEBRA ENVIRONMENTAL, INC	D-03	
Drilling Method:	2" GEOPROBE	Sheet:	
Sampling Method:	GEOPROBE DIRECT PUSH	1 of 2	
Water Level:	-7 FEET BELOW GRADE	Drilling	
Depth of Screen:	N/A	Start Time	Finish Time
Depth of Gravel:	N/A	8:35	9:50
Depth of Bentonite:	N/A	Date	Date
		10/8/2004	10/8/2004




URS CORPORATION
Soil Boring Log

Location of Boring

See Figure 2 for boring location

Job No.:	Client:	Location:
38546433	BP ATLANTIC RICHFIELD	COLUMBIA CEMENT FREEPORT, NY
Logged By:	ANDREW KOHLBECKER	Boring No.:
Driller:	ZEBRA ENVIRONMENTAL, INC	D-03
Drilling Method:	2" GEOPROBE	Sheet:
Sampling Method:	GEOPROBE DIRECT PUSH	1 of 2 Drilling Start Time Finish Time
Water Level:	-7 FEET BELOW GRADE	8:35 9:50
Depth of Screen:	N/A	
Depth of Gravel:	N/A	Date
Depth of Bentonite:	N/A	10/8/2004




URS CORPORATION

Soil Boring Log

Location of Boring

See Figure 2 for boring location

Job No.: 38546433	Client: BP ATLANTIC RICHFIELD	Location: COLUMBIA CEMENT FREEPORT, NY
Logged By:	ANDREW KOHLBECKER	Boring No.:
Driller:	ZEBRA ENVIRONMENTAL, INC	D-04
Drilling Method:	2" GEOPROBE	Sheet:
Sampling Method:	GEOPROBE DIRECT PUSH	1 of 2 Drilling Start Time Finish Time
Water Level:	~7 FEET BELOW GRADE	9:55 10:45
Depth of Screen:	N/A	
Depth of Gravel:	N/A	Date
Depth of Bentonite:	N/A	10/8/2004 10/8/2004



URS CORPORATION

Soil Boring Log


Location of Boring See Figure 2 for boring location							Job No.: 38546433	Client: BP ATLANTIC RICHFIELD	Location: COLUMBIA CEMENT FREEPORT, NY	
							Logged By: ANDREW KOHLBECKER	Boring No.: D-04		
							Driller: ZEBRA ENVIRONMENTAL, INC	Sheet: 1 of 2		
							Drilling Method: 2" GEOPROBE	Drilling		
							Sampling Method: GEOPROBE DIRECT PUSH	Start Time Finish Time		
							Water Level: ~7 FEET BELOW GRADE	9:55 10:45		
							Depth of Screen: N/A	Date		
							Depth of Gravel: N/A	Date		
							Depth of Bentonite: N/A	10/8/2004 10/8/2004		
Sampler Type	Sample No.	Inches Driv.	Blow Count /	PID (ppm)	Analytical Se	Depth (ft.)	Soil Graph	Surface Conditions		
		48		0.1		21	SP	Brown medium to coarse SAND, medium dense, wet		
		24		0.1		22				
				0.1		23				
				0.1		24				
		48		0.1		25		Light gray medium to coarse SAND and fine GRAVEL, dense, wet		
		38		0.1		26				
				0.1		27				
				0.1		28		Light gray coarse SAND, some fine gravel, wet		
		48		0.1		29				
		44		0.1		30				
				0.1		31				
				0.1		32	Gray fine micaceous SAND. Dense, wet			
						EOB				
							NOTES:			
							1 SAMPLE DEPTH TIME ANALYSIS D-04-10-12 10-12 10:00 VOC D-04-16-18 15-16 10:15 VOC D-04-20-22 20-22 10:25 VOC D-04-24-26 24-26 10:35 VOC D-04-28-30 28-30 10:45 VOC			
							2 EVIDENCE OF CONTAMINATION			
							ODOR: None			
							STAINING: None			
							3 DEPTH OF BORING - 32 FEET BELOW GROUND SURFACE			

URS CORPORATION
Soil Boring Log

Location of Boring

See Figure 2 for boring location

Job No.: 38546433	Client: BP ATLANTIC RICHFIELD	Location: COLUMBIA CEMENT FREEPORT, NY	
Logged By:	ANDREW KOHLBECKER	Boring No.:	
Driller:	ZEBRA ENVIRONMENTAL, INC	D-05	
Drilling Method:	2" GEOPROBE	Sheet: 1 of 2	
Sampling Method:	GEOPROBE DIRECT PUSH	Drilling	
Water Level:	-7 FEET BELOW GRADE	Start Time	Finish Time
Depth of Screen:	N/A	11:00	11:55
Depth of Gravel:	N/A	Date	Date
Depth of Bentonite:	N/A	10/8/2004	10/8/2004



URS CORPORATION


Soil Boring Log

Location of Boring See Figure 2 for boring location		Job No.: 38546433	Client: BP ATLANTIC RICHFIELD	Location: COLUMBIA CEMENT FREEPORT, NY
		Logged By: Driller:	ANDREW KOHLBECKER ZEBRA ENVIRONMENTAL, INC	Boring No.: D-05
		Drilling Method: Sampling Method:	2" GEOPROBE GEOPROBE DIRECT PUSH	Sheet: 1 of 2
		Water Level: Depth of Screen:	~7 FEET BELOW GRADE N/A	Drilling Start Time Finish Time 11:00 11:55
		Depth of Gravel: Depth of Bentonite:	N/A N/A	Date Date 10/8/2004 10/8/2004

Sampler Type	Sample No.	Inches Driv.	Blow Count /	PID (ppm)	Analytical S	Depth (ft.)	Soil Graph	Surface Conditions			
								SP	SM	EOB	NOTES:
		48		0.2		21		Light gray to tan medium to coarse SAND and fine rounded GGRAVEL, medium dense, wet			
		30		0.2		22					
				0.2		23					
				0.2		24		Light gray medium to fine SAND, some fine rounded gravel			
		48		0.1		25					
		24		0.1		26					
				0.1		27		Gray fine micaceous SAND and SILT, dense, wet			
		48		0.1		28					
		48		0.1		29					
				0.1		30					
				0.1		31					
				0.1		32		EOB			
						33					
						34					
						35		1 SAMPLE	DEPTH	TIME	ANALYSIS
						36		D-05-10-12	10-12	11:05	VOC
						37		D-05-16-18	16-18	11:15	VOC
						38		D-05-20-22	20-22	11:30	VOC
						39		D-05-24-26	24-26	11:40	VOC
						40		D-05-28-30	28-30	11:50	VOC
								2 EVIDENCE OF CONTAMINATION			
								ODOR: None			
								STAINING: None			
								3 DEPTH OF BORING - 32 FEET BELOW GROUND SURFACE			

URS CORPORATION

Soil Boring Log



URS CORPORATION

Soil Boring Log

Location of Boring See Figure 2 for boring location		Job No.: 38546433	Client: BP ATLANTIC RICHFIELD	Location: COLUMBIA CEMENT FREEPORT, NY
		Logged By: Driller:	ANDREW KOHLBECKER ZEBRA ENVIRONMENTAL, INC	Boring No.: D-06
		Drilling Method:	2" GEOPROBE	Sheet: 1 of 2
		Sampling Method:	GEOPROBE DIRECT PUSH	Drilling
		Water Level:	~7 FEET BELOW GRADE	Start Time Finish Time 12:10 13:03
		Depth of Screen:	N/A	
		Depth of Gravel:	N/A	Date Date 10/8/2004 10/8/2004
		Depth of Bentonite:	N/A	

Sampler Type	Sample No./ Inches Drv.	Blow Count / PfD (ppm)	Analytical Sae	Depth (ft.)	Soil Graph	Surface Conditions
48	18	0.1	SP	21	Light gray coarse SAND with rounded fine gravel, medium dense, wet	
		0.1		22		
		0.1		23		
		0.1		24		
	24	0.1		25		
		0.1		26		
		0.1		27		
		0.1		28		
	32	0.2	SM	29	Light gray micaceous silty fine SAND, dense, wet	
		0.2		30		
		0.2		31		
		0.2		32		
				33		
				34		
48	32		EOB	35	NOTES: 1 SAMPLE DEPTH TIME ANALYSIS D-06-10-12 12-13 12:20 VOC D-06-16-18 16-18 12:30 VOC D-06-20-22 20-22 12:40 VOC D-06-24-26 24-26 12:50 VOC D-06-28-30 28-30 13:05 VOC 2 EVIDENCE OF CONTAMINATION ODOR: None STAINING: None 3 DEPTH OF BORING - 32 FEET BELOW GROUND SURFACE	
				36		
				37		
				38		
				39		
				40		

URS CORPORATION

Soil Boring Log

Location of Boring See Figure 2 for boring location		Job No.: 38546433	Client: BP ATLANTIC RICHFIELD	Location: COLUMBIA CEMENT FREEPORT, NY
		Logged By: ANDREW KOHLBECKER	Boring No.: D-07	
		Driller: ZEBRA ENVIRONMENTAL, INC		
		Drilling Method: 2" GEOPROBE	Sheet: 1 of 2	
		Sampling Method: GEOPROBE DIRECT PUSH	Drilling	
		Water Level: ~7 FEET BELOW GRADE	Start Time	Finish Time
		Depth of Screen: N/A	8:55	9:46
		Depth of Gravel: N/A	Date	Date
		Depth of Bentonite: N/A	10/6/2004	10/6/2004
Sampler Type	Sample No. / Depth	Inches Driv. / Recov.	Blow Count / 6"	PID (ppm)
				Analytical Sample
				Depth (ft.)
				Soil Graph
				Surface Conditions
				CRUSHED GRAVEL FILL
				Advanced boring through backfill to 8'.
				Crushed stone backfill
				FILL
				1
				2
				3
				4
				5
				6
				7
				8
				OL/PT
				9
				10
				11
				12
				13
				14
				15
				16
				SP
				17
				18
				19
				20

URS CORPORATION


Soil Boring Log

Location of Boring See Figure 2 for boring location							Job No.: 38546433	Client: BP ATLANTIC RICHFIELD	Location: COLUMBIA CEMENT FREEPORT, NY	
							Logged By: ANDREW KOHLBECKER	Boring No.: D-07		
							Driller: ZEBRA ENVIRONMENTAL, INC	Sheet: 1 of 2		
							Drilling Method: 2" GEOPROBE	Sampling Method: GEOPROBE DIRECT PUSH		
							Water Level: ~7 FEET BELOW GRADE	Drilling Start Time 8:55	Finish Time 9:46	
							Depth of Screen: N/A			
							Depth of Gravel: N/A	Date 10/6/2004	Date 10/6/2004	
							Depth of Bentonite: N/A			
Sampler Type	Sample No. /	Inches Driv.	Blow Count /	PID (ppm)	Analytical Sa	Depth (ft.)	Surface Conditions			
							Soil Graph			
		48		0.0		21	Light gray medium SAND, trace fine rounded gravel, medium dense, wet			
		36		0.0		22				
				0.0		23				
				0.0		24	Light gray coarse SAND with fine gravel, loose, wet			
		48		0.0		25				
		12		0.0		26				
				0.0		27				
				0.0		28	Light gray medium SAND, well sorted, dense, wet			
		48		0.0		29				
		18		0.0		30				
				0.0		31				
				0.0		32	EOB			
						33				
						34				
						35	NOTES:			
						36	1 SAMPLE	DEPTH	TIME	ANALYSIS
						37	D-07-10-12	10-12	9:00	VOC
						38	D-07-16-18	16-18	9:10	VOC
						39	D-07-20-22	20-22	9:20	VOC
						40	D-07-24-26	24-26	9:30	VOC
							D-07-28-30	28-30	9:45	VOC
							2 EVIDENCE OF CONTAMINATION			
							ODOR: None			
							STAINING: None			
							3 DEPTH OF BORING - 32 FEET BELOW GROUND SURFACE			

URS CORPORATION
Soil Boring Log

Location of Boring

Job No.: 38546433	Client: BP ATLANTIC RICHFIELD	Location: COLUMBIA CEMENT FREEPORT, NY	
Logged By:	ANDREW KOHLBECKER	Boring No.:	
Driller:	ZEBRA ENVIRONMENTAL, INC	D-08	
Drilling Method:	2" GEOPROBE	Sheet:	
Sampling Method:	GEOPROBE DIRECT PUSH	1 of 2	
Water Level:	-7 FEET BELOW GRADE	Drilling	
Depth of Screen:	N/A	Start Time	Finish Time
Depth of Gravel:	N/A	13:10	14:10
Depth of Bentonite:	N/A	Date	Date
		10/8/2004	10/8/2004



URS CORPORATION

Soil Boring Log


Location of Boring See Figure 2 for boring location							Job No.: 38546433	Client: BP ATLANTIC RICHFIELD	Location: COLUMBIA CEMENT FREEPORT, NY
							Logged By: ANDREW KOHLBECKER	Boring No.: D-08	
							Driller: ZEBRA ENVIRONMENTAL, INC	Sheet:	
							Drilling Method: 2" GEOPROBE	1 of 2	
							Sampling Method: GEOPROBE DIRECT PUSH	Drilling	
							Water Level: ~7 FEET BELOW GRADE	Start Time 13:10	Finish Time 14:10
							Depth of Screen: N/A		
							Depth of Gravel: N/A	Date 10/8/2004	Date 10/8/2004
							Depth of Bentonite: N/A		
Sampler Type	Sample No./ Inches Driv.	Blow Count / PfD (ppm)	Analytical Sa	Depth (ft.)	Soil Graph	Surface Conditions			
	48	0.5		21	SP	Light gray medium to coarse SAND, with fine, rounded gravel, medium dense, moist			
	30	0.5		22					
		4.5		23		Light gray medium to coarse SAND, little gravel, wet			
		4.5		24					
	48	0.2		25					
	24	0.2		26					
		0.2		27					
	48	0.5		28	SP/ SM	Gray fine micaceous SAND and SILT, dense, wet			
	36	0.5		29					
		0.5		30		Gray fine to medium SAND, dense, wet			
		0.5		31					
		0.5		32	EOB				
				33					
				34		NOTES:			
				35		1 SAMPLE	DEPTH	TIME	ANALYSIS
				36		D-08-10-12	10-12	13:15	VOC
				37		D-08-16-18	16-18	13:30	VOC
				38		D-08-20-22	22-23	13:45	VOC
				39		D-08-24-26	24-26	13:55	VOC
				40		D-08-28-30	28-30	14:10	VOC
						2 EVIDENCE OF CONTAMINATION			
						ODOR: None			
						STAINING: None			
						3 DEPTH OF BORING - 32 FEET BELOW GROUND SURFACE			

URS CORPORATION
Soil Boring Log

Location of Boring

See Figure 2 for boring location

Job No.:	Client:	Location:	
38546433	BP/BELCI	FREEPORT, NY	
Logged By:	ANDREW KOHLBECKER	Boring No.:	
Driller:	ZEBRA ENVIRONMENTAL, INC	D-09	
Drilling Method:	2" GEOPROBE	Sheet:	
Sampling Method:	GEOPROBE DIRECT PUSH	1 of 1	
Water Level:	-7 FEET BELOW GRADE	Drilling	
Depth of Screen:	N/A	Start Time	Finish Time
Depth of Gravel:	N/A	14:15	14:20
Depth of Bentonite:	N/A	Date	Date
		10/8/2004	10/8/2004



APPENDIX C
GROUNDWATER SAMPLING LOGS

JUNE 2004 SAMPLING LOGS

Well MW-1S

Groundwater Sampling Log; Former Columbia Cement Company Site
Atlantic Richfield Company (BP) - Freeport, NY

Well ID		MW-1S	Start	10:28	Team	AK.JRR			
Date		6/7/2004	Finish	11:40	Diameter	4 inches			
						Yes/No	Yes/No		
Depth to Water		6.64 ft TOC				2-inch pump ? N	Duplicate?	N	
Total Depth		20.96 ft TOC				Whale Pump ? N	MS/MSD?	N	
Depth to Pump		15 ft TOC				Peristaltic Pump? Y	Split-Sample?	N	
Pump Rate		0.45 L/min				Comments:	PERISTALTIC		
adjusted to:		L/min	at		minutes				
adjusted to:		L/min	at		minutes				
Time (minutes)	Time	Depth to Water (ft TOC)	pH (std units)	ORP (mV)	Temperature (deg C)	Spec. Cond. (mS/cm)	Diss. Oxygen (mg/L)	Turbidity (NTU)	
0	10:28	6.64							
5	10:33	6.77	6.63	-72	16.01	1.57	0.62	28.5	
10	10:38	6.75	6.67	-75.5	15.80	1.55	0.47	158.7	
15	10:43	6.72	6.65	-76.9	15.78	1.53	0.38	74.8	
20	10:48	6.72	6.64	-75.9	15.81	1.53	0.33	451.3	
25	10:53	6.74	6.61	-78.7	15.77	1.50	0.29	1084.8	
30	10:58	6.73	6.59	-81.7	15.95	1.49	0.27	463.3	
35	11:03	6.72	6.58	-88.8	15.77	1.47	0.25	1084.8	
40	11:08	6.69	6.54	-84.4	15.83	1.49	0.24	1085.0	
45	11:13	6.67	6.55	-86	15.74	1.48	0.23	1084.8	
0									
0									
0									
Analyses						clear	cloudy	turbid	
VOC, TOC			<input type="checkbox"/>				<input checked="" type="checkbox"/>	<input type="checkbox"/>	
ALK, CHL			<input type="checkbox"/>						
TOT FE			<input type="checkbox"/>						
DIS GASSES			<input type="checkbox"/>						
SO ₄ , NO ₃			<input type="checkbox"/>						
MN II, TOT MN			<input type="checkbox"/>						
Water Quality						Comments			
						80 SUNNY			
Duplicate ID						Shipped	SDG		

Well MW-97-1D

Groundwater Sampling Log; Former Columbia Cement Company Site
Atlantic Richfield Company (BP) - Freeport, NY

Well ID		MW-97-1D	Start	12:25	Team	AK, JRR		
Date		6/7/2004	Finish	13:30	Diameter	2 inches		
						Yes/No	Yes/No	
Depth to Water		5.80 ft TOC			2-inch pump ? N	Duplicate?	N	
Total Depth		33.62 ft TOC			Whale Pump ? N	MS/MSD?	N	
Depth to Pump		31 ft TOC			Peristaltic Pump? Y	Split-Sample?	N	
Pump Rate		0.48 L/min			Comments:	PERISTALTIC		
adjusted to:		L/min	at	minutes				
adjusted to:		L/min	at	minutes				
Time (minutes)	Time	Depth to Water (ft TOC)	pH (std units)	ORP (mV)	Temperature (deg C)	Spec. Cond. (mS/cm)	Diss. Oxygen (mg/L)	Turbidity (NTU)
0	12:25	5.80						
5	12:30	5.92	6.43	-68.0	17.45	1.099	0.81	37.5
10	12:35	5.92	6.60	-55.7	17.89	1.640	0.53	8.7
15	12:40	5.91	6.62	-53.8	17.93	1.862	0.46	14.7
20	12:45	5.91	6.63	-52.0	17.66	1.853	0.40	12.4
25	12:50	5.90	6.64	-51.7	17.71	1.855	0.37	3.4
30	12:55	5.89	6.64	-51.2	17.68	1.852	0.35	5.4
35	13:00	5.88	6.64	-53.1	17.49	1.840	0.34	5.7
40	13:05	5.89	6.64	-53.1	17.71	1.848	0.34	3.1
45	13:10	5.88	6.64	-52.2	17.70	1.844	0.33	4.9
50	13:15	5.88	6.64	-51.4	17.68	1.840	0.33	5.9
0								
0								
Analyses								
VOC, TOC				<input type="checkbox"/>		clear		
ALK, CHL				<input type="checkbox"/>		cloudy		
TOT FE				<input type="checkbox"/>		turbid		
DIS GASSES				<input type="checkbox"/>				
SO ₄ , NO ₃				<input type="checkbox"/>				
MN II, TOT MN				<input type="checkbox"/>				
Duplicate ID					Water Quality	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
					Comments			
					85 SUNNY			
					Shipped		SDG	

Well MW-97-1S

Groundwater Sampling Log; Former Columbia Cement Company Site
Atlantic Richfield Company (BP) - Freeport, NY

Well ID		MW-97-1S	Start	8:00	Team	AK, JRR		
Date		6/8/2004	Finish	9:00	Diameter	2 inches		
				Yes/No	Yes/No			
Depth to Water		5.95 ft TOC		2-inch pump ? N	Duplicate?	N		
Total Depth		21.14 ft TOC		Whale Pump ? N	MS/MSD?	N		
Depth to Pump		19 ft TOC		Peristaltic Pump? Y	Split-Sample?	N		
Pump Rate		0.49 L/min		Comments:	PERISTALTIC			
adjusted to:		L/min	at	minutes				
adjusted to:		L/min	at	minutes				
Time (minutes)	Time	Depth to Water (ft TOC)	pH (std units)	ORP (mV)	Temperature (deg C)	Spec. Cond. (mS/cm)	Diss. Oxygen (mg/L)	Turbidity (NTU)
0	8:00	5.95						
14	8:14	5.99	6.33	-6.6	16.48	0.798	0.77	53.2
19	8:19	5.98	6.23	-9.8	16.44	0.794	0.40	31.5
24	8:24	5.99	6.25	-16.2	16.51	0.793	0.34	25.3
29	8:29	5.99	6.27	-22.3	16.49	0.791	0.32	23.3
34	8:34	5.99	6.28	-26.2	16.48	0.790	0.30	35.7
39	8:39	5.99	6.27	-28.6	16.53	0.801	0.28	59.6
44	8:44	5.98	6.28	-31.2	16.57	0.794	0.29	250.1
0								
0								
0								
0								
Analyses				clear	cloudy	turbid		
VOC, TOC		<input type="checkbox"/>	Water Quality	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		
ALK, CHL		<input type="checkbox"/>	Comments					
TOT FE		<input type="checkbox"/>	75 SUNNY					
DIS GASES		<input type="checkbox"/>	PID: 0.6 ppm					
SO ₄ , NO ₃		<input type="checkbox"/>						
MN II, TOT MN		<input type="checkbox"/>		Shipped		SDG		
Duplicate ID								

Well MW-97-2S

Groundwater Sampling Log; Former Columbia Cement Company Site
Atlantic Richfield Company (BP) - Freeport, NY

Well ID		MW-97-2S	Start	11:05	Team	AK, JRR		
Date		6/8/2004	Finish	11:55	Diameter	2 inches		
				Yes/No		Yes/No		
Depth to Water		6.89 ft TOC		2-inch pump ? N		Duplicate?	N	
Total Depth		23.93 ft TOC		Whale Pump ? N		MS/MSD?	N	
Depth to Pump		19 ft TOC		Peristaltic Pump? Y		Split-Sample?	N	
Pump Rate		0.48 L/min		Comments:		PERISTALTIC		
adjusted to:		L/min	at	minutes				
adjusted to:		L/min	at	minutes				
Time (minutes)	Time	Depth to Water (ft TOC)	pH (std units)	ORP (mV)	Temperature (deg C)	Spec. Cond. (mS/cm)	Diss. Oxygen (mg/L)	Turbidity (NTU)
0	11:05	6.89						
5	11:10	6.88	6.17	8.2	17.61	0.981	0.87	1052.3
10	11:15	6.89	6.15	4.1	17.59	0.958	0.61	191.4
15	11:20	6.88	6.15	-1.6	17.58	0.970	0.48	138.5
20	11:25	6.88	6.16	-6.8	17.57	0.972	0.43	179.2
25	11:30	6.88	6.16	-8.8	17.63	0.964	0.55	200.7
30	11:35	6.88	6.16	-11.4	17.58	0.980	0.51	252.7
35	11:40	6.88	6.15	-14.5	17.56	0.982	0.48	164.7
0								
0								
0								
0								
0								
Analyses								
VOC, TOC				<input type="checkbox"/>				
ALK, CHL				<input type="checkbox"/>				
TOT FE				<input type="checkbox"/>				
DIS GASSES				<input type="checkbox"/>				
SO ₄ , NO ₃				<input type="checkbox"/>				
MN II, TOT MN				<input type="checkbox"/>				
Duplicate ID				Water Quality		clear	cloudy	turbid
				<input checked="" type="checkbox"/>		<input type="checkbox"/>	<input type="checkbox"/>	
Comments								
85 SUNNY								
PID:0.3ppm								
Shipped				SDG				

Well MW-97-3S

Groundwater Sampling Log; Former Columbia Cement Company Site
Atlantic Richfield Company (BP) - Freeport, NY

Well ID		MW-97-3S	Start	9:57	Team	AK, JRR																																																																																																																																
Date		6/9/2004	Finish	10:45	Diameter	2 inches																																																																																																																																
				Yes/No		Yes/No																																																																																																																																
Depth to Water		6.99 ft TOC		2-inch pump ? N		Duplicate?	N																																																																																																																															
Total Depth		24.81 ft TOC		Whale Pump ? N		MS/MSD?	N																																																																																																																															
Depth to Pump		20 ft TOC		Peristaltic Pump? Y		Split-Sample?	N																																																																																																																															
Pump Rate		0.47 L/min		Comments:		PERISTALTIC																																																																																																																																
adjusted to:		L/min	at	minutes																																																																																																																																		
adjusted to:		L/min	at	minutes																																																																																																																																		
<table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th>Time (minutes)</th> <th>Time</th> <th>Depth to Water (ft TOC)</th> <th>pH (std units)</th> <th>ORP (mV)</th> <th>Temperature (deg C)</th> <th>Spec. Cond. (mS/cm)</th> <th>Diss. Oxygen (mg/L)</th> <th>Turbidity (NTU)</th> </tr> </thead> <tbody> <tr><td>0</td><td>9:57</td><td>6.99</td><td></td><td></td><td></td><td></td><td></td><td></td></tr> <tr><td>5</td><td>10:02</td><td>7.00</td><td>6.48</td><td>-101</td><td>17.48</td><td>1.802</td><td>1.25</td><td>1119.9</td></tr> <tr><td>10</td><td>10:07</td><td>7.00</td><td>6.43</td><td>-119.7</td><td>17.32</td><td>1.780</td><td>0.60</td><td>991.8</td></tr> <tr><td>15</td><td>10:12</td><td>7.00</td><td>6.40</td><td>-135.9</td><td>17.23</td><td>1.757</td><td>0.33</td><td>1139.0</td></tr> <tr><td>20</td><td>10:17</td><td>7.01</td><td>6.39</td><td>-146.8</td><td>17.41</td><td>1.765</td><td>0.31</td><td>616.8</td></tr> <tr><td>25</td><td>10:22</td><td>7.00</td><td>6.37</td><td>-156.6</td><td>17.47</td><td>1.763</td><td>0.30</td><td>348.0</td></tr> <tr><td>30</td><td>10:27</td><td>7.00</td><td>6.38</td><td>-158.9</td><td>17.28</td><td>1.762</td><td>0.32</td><td>540.2</td></tr> <tr><td>35</td><td>10:32</td><td>7.00</td><td>6.37</td><td>-165.3</td><td>17.38</td><td>1.750</td><td>0.33</td><td>236.9</td></tr> <tr><td>0</td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr> <tr><td>0</td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr> <tr><td>0</td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr> <tr><td>0</td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr> <tr><td>0</td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr> </tbody> </table>									Time (minutes)	Time	Depth to Water (ft TOC)	pH (std units)	ORP (mV)	Temperature (deg C)	Spec. Cond. (mS/cm)	Diss. Oxygen (mg/L)	Turbidity (NTU)	0	9:57	6.99							5	10:02	7.00	6.48	-101	17.48	1.802	1.25	1119.9	10	10:07	7.00	6.43	-119.7	17.32	1.780	0.60	991.8	15	10:12	7.00	6.40	-135.9	17.23	1.757	0.33	1139.0	20	10:17	7.01	6.39	-146.8	17.41	1.765	0.31	616.8	25	10:22	7.00	6.37	-156.6	17.47	1.763	0.30	348.0	30	10:27	7.00	6.38	-158.9	17.28	1.762	0.32	540.2	35	10:32	7.00	6.37	-165.3	17.38	1.750	0.33	236.9	0									0									0									0									0								
Time (minutes)	Time	Depth to Water (ft TOC)	pH (std units)	ORP (mV)	Temperature (deg C)	Spec. Cond. (mS/cm)	Diss. Oxygen (mg/L)	Turbidity (NTU)																																																																																																																														
0	9:57	6.99																																																																																																																																				
5	10:02	7.00	6.48	-101	17.48	1.802	1.25	1119.9																																																																																																																														
10	10:07	7.00	6.43	-119.7	17.32	1.780	0.60	991.8																																																																																																																														
15	10:12	7.00	6.40	-135.9	17.23	1.757	0.33	1139.0																																																																																																																														
20	10:17	7.01	6.39	-146.8	17.41	1.765	0.31	616.8																																																																																																																														
25	10:22	7.00	6.37	-156.6	17.47	1.763	0.30	348.0																																																																																																																														
30	10:27	7.00	6.38	-158.9	17.28	1.762	0.32	540.2																																																																																																																														
35	10:32	7.00	6.37	-165.3	17.38	1.750	0.33	236.9																																																																																																																														
0																																																																																																																																						
0																																																																																																																																						
0																																																																																																																																						
0																																																																																																																																						
0																																																																																																																																						
Analyses																																																																																																																																						
VOC, TOC				<input type="checkbox"/>																																																																																																																																		
ALK, CHL				<input type="checkbox"/>																																																																																																																																		
TOT FE				<input type="checkbox"/>																																																																																																																																		
DIS GASES				<input type="checkbox"/>																																																																																																																																		
SO ₄ , NO ₃				<input type="checkbox"/>																																																																																																																																		
MN II, TOT MN				<input type="checkbox"/>																																																																																																																																		
Duplicate ID				Water Quality		clear	cloudy																																																																																																																															
						<input checked="" type="checkbox"/>	<input type="checkbox"/>																																																																																																																															
				Comments																																																																																																																																		
				85 SUNNY																																																																																																																																		
				PID: 0.00ppm																																																																																																																																		
				Shipped			SDG																																																																																																																															

Well MW-97-4S

Groundwater Sampling Log; Former Columbia Cement Company Site Atlantic Richfield Company (BP) - Freeport, NY

Well ID		MW-97-4S	Start	10:00	Team	AK, JRR		
Date		6/10/2004	Finish	11:25	Diameter	2 inches		
Comments:								
Depth to Water		7.14	ft TOC		2-inch pump ? N	Duplicate?	N	
Total Depth		24.95	ft TOC		Whale Pump ? N	MS/MSD?	N	
Depth to Pump		20	ft TOC		Peristaltic Pump? Y	Split-Sample?	N	
Pump Rate		0.48	L/min		Comments:	PERISTALTIC		
adjusted to:			L/min	at				
adjusted to:			L/min	at				
Time (minutes)	Time	Depth to Water (ft TOC)	pH (std units)	ORP (mV)	Temperature (deg C)	Spec. Cond. (mS/cm)	Diss. Oxygen (mg/L)	Turbidity (NTU)
0	10:00	7.14						
15	10:15	7.15	6.62	-45.2	16.38	1.134	0.64	18.8
20	10:20	7.17	6.56	-52.3	16.20	1.146	0.40	30.1
25	10:25	7.17	6.56	-63.8	15.96	1.149	0.36	61.3
30	10:30	7.17	6.56	-76.3	15.95	1.148	0.32	63.1
35	10:35	7.18	6.56	-85.0	15.97	1.161	0.30	216.7
40	10:40	7.18	6.56	-104.0	15.92	1.170	0.28	198.0
45	10:45	7.18	6.55	-128.6	15.88	1.176	0.27	493.4
50	10:50	7.18	6.56	-149.8	15.81	1.174	0.27	27.8
55	10:55	7.19	6.55	-176.2	15.85	1.173	0.26	217.1
60	11:00	7.19	6.54	-182.5	15.91	1.178	0.26	112.6
65	11:05	7.19	6.54	-179.0	15.81	1.193	0.26	227.9
70	11:10	7.19	6.54	-173.0	15.80	1.180	0.25	83.4
Analyses								
VOC, TOC				<input type="checkbox"/>	clear	cloudy	turbid	
ALK, CHL				<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
TOT FE				<input type="checkbox"/>				
DIS GASES				<input type="checkbox"/>				
SO4, NO3				<input type="checkbox"/>				
MN II, TOT MN				<input type="checkbox"/>				
Comments:								
80-85 CLOUDY								
PID: 0.6 ppm								
Duplicate ID					Shipped		SDG	

Well MW-97-5S

Groundwater Sampling Log; Former Columbia Cement Company Site
Atlantic Richfield Company (BP) - Freeport, NY

Well ID	MW-97-5S	Start	11:30	Team	AK, JRR			
Date	6/10/2004	Finish	12:30	Diameter	2 inches			
				Yes/No	Yes/No			
Depth to Water	7.01 ft TOC	2-inch pump ? N			Duplicate?	N		
Total Depth	25.41 ft TOC	Whale Pump ? N			MS/MSD?	N		
Depth to Pump	20 ft TOC	Peristaltic Pump? Y			Split-Sample?	N		
Pump Rate	0.48 L/min	Comments: PERISTALTIC						
adjusted to:	L/min	at	minutes					
adjusted to:	L/min	at	minutes					
Time (minutes)	Time	Depth to Water (ft TOC)	pH (std units)	ORP (mV)	Temperature (deg C)	Spec. Cond. (mS/cm)	Diss. Oxygen (mg/L)	Turbidity (NTU)
0	11:30	7.01						
5	11:35	7.07	6.65	-90.8	15.60	0.419	0.77	167.9
10	11:40	7.08	6.59	-104.2	15.49	0.515	0.52	874.3
15	11:45	7.08	6.60	-137.1	15.39	0.674	0.40	49.2
20	11:50	7.07	6.62	-154.4	15.41	0.765	0.35	29.4
25	11:55	7.06	6.63	-159.6	15.41	0.815	0.32	18.2
30	12:00	7.06	6.63	-163.9	15.42	0.859	0.30	15.9
35	12:05	7.06	6.65	-164.7	15.37	0.881	0.29	81.9
40	12:10	7.06	6.66	-159.0	15.31	0.891	0.28	41.0
0								
0								
0								
0								
Analyses								
VOC, TOC			<input type="checkbox"/>					
ALK, CHL			<input type="checkbox"/>					
TOT FE			<input type="checkbox"/>					
DIS GASES			<input type="checkbox"/>					
SO ₄ , NO ₃			<input type="checkbox"/>					
MN II, TOT MN			<input type="checkbox"/>					
Duplicate ID				Water Quality	<input checked="" type="checkbox"/> clear	<input type="checkbox"/> cloudy	<input type="checkbox"/> turbid	
				Comments				
				85 CLOUDY				
				PID: 0.4 ppm				
Shipped				SDG				

Well MW-97-6S

Groundwater Sampling Log; Former Columbia Cement Company Site
Atlantic Richfield Company (BP) - Freeport, NY

Well ID		MW-97-6S	Start	7:50	Team	AK, JRR			
Date		6/9/2004	Finish	8:35	Diameter	2 inches			
						Yes/No	Yes/No		
Depth to Water		6.72 ft TOC				2-inch pump ? N	Duplicate?	N	
Total Depth		25.73 ft TOC				Whale Pump ? N	MS/MSD?	N	
Depth to Pump		20 ft TOC				Peristaltic Pump? Y	Split-Sample?	N	
Pump Rate		0.49 L/min				Comments:	PERISTALTIC		
adjusted to:		L/min	at		minutes				
adjusted to:		L/min	at		minutes				
Time (minutes)	Time	Depth to Water (ft TOC)	pH (std units)	ORP (mV)	Temperature (deg C)	Spec. Cond. (mS/cm)	Diss. Oxygen (mg/L)	Turbidity (NTU)	
0	7:50	6.72							
5	7:55	6.85	6.03	-3.9	16.96	1.391	0.58	295.1	
10	8:00	6.86	6.07	-9.4	16.95	1.393	0.50	268.7	
15	8:05	6.86	6.11	-11.3	16.97	1.394	0.45	232.5	
20	8:10	6.87	6.12	-12	17.02	1.392	0.44	261.5	
25	8:15	6.87	6.12	-10.7	17.03	1.400	0.40	399.0	
30	8:20	6.88	6.13	-15.3	17.05	1.401	0.41	245.0	
0									
0									
0									
0									
0									
Analyses									
VOC, TOC			<input type="checkbox"/>						
ALK, CHL			<input type="checkbox"/>						
TOT FE			<input type="checkbox"/>						
DIS GASES			<input type="checkbox"/>						
SO ₄ , NO ₃			<input type="checkbox"/>						
MN II, TOT MN			<input type="checkbox"/>						
Duplicate ID									
						clear	cloudy	turbid	
						<input checked="" type="checkbox"/> Water Quality	<input type="checkbox"/>	<input type="checkbox"/>	
						Comments			
						75 SUNNY			
						PID:25.3			
						Shipped		SDG	

Well MW-97-7S

Groundwater Sampling Log; Former Columbia Cement Company Site
Atlantic Richfield Company (BP) - Freeport, NY

Well ID		MW-97-7S	Start	9:00	Team	AK,JRR			
Date		6/9/2004	Finish	9:35	Diameter	2 inches			
						Yes/No	Yes/No		
Depth to Water		6.90 ft TOC			2-inch pump ? N		Duplicate?	N	
Total Depth		31.75 ft TOC			Whale Pump ? N		MS/MSD?	N	
Depth to Pump		26 ft TOC			Peristaltic Pump? Y		Split-Sample?	N	
Pump Rate		0.48 L/min			Comments:	PERISTALTIC			
adjusted to:		L/min	at	minutes					
adjusted to:		L/min	at	minutes					
Time (minutes)	Time	Depth to Water (ft TOC)	pH (std units)	ORP (mV)	Temperature (deg C)	Spec. Cond. (mS/cm)	Diss. Oxygen (mg/L)	Turbidity (NTU)	
0	9:00	6.90							
5	9:05	6.91	6.21	7.4	17.62	0.922	0.90	390.2	
10	9:10	6.93	6.20	3.7	17.55	0.916	0.57	665.0	
15	9:15	6.93	6.22	-5.5	17.51	0.907	0.43	1139.8	
20	9:20	6.93	6.26	-9.1	17.53	0.905	0.39	829.2	
25	9:25	6.93	6.26	-12.2	17.51	0.904	0.36	551.7	
30	9:30	6.94	6.27	-14.3	17.55	0.905	0.34	371.9	
0									
0									
0									
0									
0									
Analyses									
VOC, TOC				<input type="checkbox"/>		clear	cloudy	turbid	
ALK, CHL				<input type="checkbox"/>					
TOT FE				<input type="checkbox"/>					
DIS GASSES				<input type="checkbox"/>					
SO4, NO3				<input type="checkbox"/>					
MN II, TOT MN				<input type="checkbox"/>					
Duplicate ID							Shipped	SDG	

Well MW-98-8S

Groundwater Sampling Log; Former Columbia Cement Company Site Atlantic Richfield Company (BP) - Freeport, NY

Well ID		MW-98-8S	Start	12:00	Team	AK, JRR		
Date		6/9/2004	Finish	12:50	Diameter	2 inches		
					Yes/No	Yes/No		
Depth to Water		7.25	ft TOC		2-inch pump ? N	Duplicate?	N	
Total Depth		19.76	ft TOC		Whale Pump ? N	MS/MSD?	N	
Depth to Pump		15	ft TOC		Peristaltic Pump? Y	Split-Sample?	N	
Pump Rate		0.46	L/min		Comments:	PERISTALTIC		
adjusted to:			L/min	at				
adjusted to:			L/min	at				
Time (minutes)	Time	Depth to Water (ft TOC)	pH (std units)	ORP (mV)	Temperature (deg C)	Spec. Cond. (mS/cm)	Diss. Oxygen (mg/L)	Turbidity (NTU)
0	12:00	7.25						
13	12:13	7.32	6.71	-66.1	17.14	1.986	1.17	6.9
18	12:18	7.32	6.66	-57.1	17.07	1.983	0.71	4.3
23	12:23	7.31	6.67	-60.8	17.00	1.980	0.52	3.4
28	12:28	7.30	6.66	-65.4	16.85	1.972	0.44	1.6
33	12:33	7.30	6.68	-69.7	16.86	1.972	0.39	4.0
38	12:38	7.29	6.68	-72.2	16.74	1.965	0.37	0.9
43	12:43	7.28	6.67	-72.8	14.75	1.967	0.35	2.4
0								
0								
0								
0								
0								
Analyses								
VOC, TOC				<input type="checkbox"/>		clear	cloudy	turbid
ALK, CHL				<input type="checkbox"/>				
TOT FE				<input type="checkbox"/>				
DIS GASSES				<input type="checkbox"/>				
SO4, NO3				<input type="checkbox"/>				
MN II, TOT MN				<input type="checkbox"/>				
					Water Quality	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
					Comments			
					90 SUNNY & WINDY			
					PID: 0.3 ppm			
Duplicate ID				Shipped		SDG		

Well MW-98-8D

Groundwater Sampling Log; Former Columbia Cement Company Site
Atlantic Richfield Company (BP) - Freeport, NY

Well ID		MW-98-8D	Start	11:00	Team	AK, JRR			
Date		6/9/2004	Finish	11:55	Diameter	2 inches			
						Yes/No	Yes/No		
Depth to Water		7.17 ft TOC				2-inch pump ? N	Duplicate?	N	
Total Depth		34.88 ft TOC				Whale Pump ? N	MS/MSD?	N	
Depth to Pump		30 ft TOC				Peristaltic Pump? Y	Split-Sample?	N	
Pump Rate		0.46 L/min				Comments:	PERISTALTIC		
adjusted to:		L/min	at		minutes				
adjusted to:		L/min	at		minutes				
Time (minutes)	Time	Depth to Water (ft TOC)	pH (std units)	ORP (mV)	Temperature (deg C)	Spec. Cond. (mS/cm)	Diss. Oxygen (mg/L)	Turbidity (NTU)	
0	11:00	7.17							
7	11:07	7.19	6.56	-48.8	17.95	1.079	1.42	217.0	
12	11:12	7.19	6.46	-54.4	17.56	1.080	0.75	109.1	
17	11:17	7.19	6.47	-54	17.50	1.078	0.56	78.0	
22	11:22	7.19	6.49	-62.3	17.31	1.058	0.48	22.3	
27	11:27	7.18	6.50	-69.8	17.22	1.059	0.42	75.0	
32	11:32	7.17	6.51	-71.2	17.19	1.073	0.39	327.0	
37	11:37	7.14	6.52	-77.1	17.26	1.079	0.37	1138.8	
42	11:42	7.13	6.51	-81.2	17.28	1.083	0.36	5.1	
0									
0									
0									
0									
Analyses									
VOC, TOC			<input type="checkbox"/>						
ALK, CHL			<input type="checkbox"/>						
TOT FE			<input type="checkbox"/>						
DIS GASES			<input type="checkbox"/>						
SO ₄ , NO ₃			<input type="checkbox"/>						
MN II, TOT MN			<input type="checkbox"/>						
Duplicate ID									
			Water Quality			clear	cloudy	turbid	
			<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>				
			Comments						
			85 SUNNY & WINDY						
			PID: 1.3ppm						
			Shipped				SDG		

Well MW-98-9D

Groundwater Sampling Log; Former Columbia Cement Company Site
Atlantic Richfield Company (BP) - Freeport, NY

Well ID		MW-98-9D	Start	9:29	Team	AK, JRR										
Date		6/8/2004	Finish	10:35	Diameter	2 inches										
						Yes/No	Yes/No									
Depth to Water		5.90 ft TOC				2-inch pump ? N	Duplicate?	N								
Total Depth		36.56 ft TOC				Whale Pump ? N	MS/MSD?	N								
Depth to Pump		33 ft TOC				Peristaltic Pump? Y	Split-Sample?	N								
Pump Rate		0.43 L/min				Comments:	PERISTALTIC									
adjusted to:		L/min	at		minutes											
adjusted to:		L/min	at		minutes											
Time (minutes)	Time	Depth to Water (ft TOC)	pH (std units)	ORP (mV)	Temperature (deg C)	Spec. Cond. (mS/cm)	Diss. Oxygen (mg/L)	Turbidity (NTU)								
0	9:29	5.90														
5	9:34	5.93	6.29	6.2	17.41	0.857	2.28	73.5								
10	9:39	5.91	6.25	-5.6	17.69	0.850	1.20	427.3								
15	9:44	5.91	6.28	-12.2	17.62	0.849	0.86	133.1								
20	9:49	5.91	6.28	-10.5	17.71	0.849	0.65	299.1								
25	9:54	5.91	6.29	-9.3	17.73	0.850	0.53	75.5								
30	9:59	5.91	6.29	-9.4	17.71	0.855	0.46	1096.3								
35	10:04	5.91	6.29	-16.2	17.77	0.851	0.40	321.8								
40	10:09	5.91	6.29	-21.3	17.75	0.852	0.37	307.8								
45	10:14	5.90	6.29	-26.6	17.71	0.850	0.35	1096.1								
0																
0																
0																
Analyses			<table border="1" style="margin-left: auto; margin-right: auto;"> <tr> <td></td> <td>clear</td> <td>cloudy</td> <td>turbid</td> </tr> <tr> <td>Water Quality</td> <td><input checked="" type="checkbox"/></td> <td><input type="checkbox"/></td> <td><input type="checkbox"/></td> </tr> </table>							clear	cloudy	turbid	Water Quality	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
	clear	cloudy	turbid													
Water Quality	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>													
VOC, TOC		<input type="checkbox"/>														
ALK, CHL		<input type="checkbox"/>														
TOT FE		<input type="checkbox"/>														
DIS GASES		<input type="checkbox"/>														
SO ₄ , NO ₃		<input type="checkbox"/>														
MN II, TOT MN		<input type="checkbox"/>														
Duplicate ID	MW-9D-98D		Comments													
			SUNNY 75													
			PID: 1.2ppm													
			Shipped			SDG										

Well MW-98-10D

Groundwater Sampling Log; Former Columbia Cement Company Site
Atlantic Richfield Company (BP) - Freeport, NY

Well ID		MW-98-10D	Start	12:25	Team	AK, JRR																																																																																																																																
Date		6/8/2004	Finish	13:30	Diameter	2 inches																																																																																																																																
						Yes/No	Yes/No																																																																																																																															
Depth to Water		7.00 ft TOC			2-inch pump ? N	Duplicate?	N																																																																																																																															
Total Depth		34.94 ft TOC			Whale Pump ? N	MS/MSD?	N																																																																																																																															
Depth to Pump		31 ft TOC			Peristaltic Pump? Y	Split-Sample?	N																																																																																																																															
Pump Rate		0.48 L/min			Comments:	PERISTALTIC																																																																																																																																
adjusted to:		L/min	at	minutes																																																																																																																																		
adjusted to:		L/min	at	minutes																																																																																																																																		
<table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th>Time (minutes)</th> <th>Time</th> <th>Depth to Water (ft TOC)</th> <th>pH (std units)</th> <th>ORP (mV)</th> <th>Temperature (deg C)</th> <th>Spec. Cond. (mS/cm)</th> <th>Diss. Oxygen (mg/L)</th> <th>Turbidity (NTU)</th> </tr> </thead> <tbody> <tr><td>0</td><td>12:25</td><td>7.00</td><td></td><td></td><td></td><td></td><td></td><td></td></tr> <tr><td>5</td><td>12:30</td><td>7.02</td><td>6.07</td><td>-0.8</td><td>18.94</td><td>0.932</td><td>1.94</td><td>7.7</td></tr> <tr><td>10</td><td>12:35</td><td>7.01</td><td>6.08</td><td>-33.7</td><td>18.87</td><td>0.925</td><td>1.21</td><td>18.7</td></tr> <tr><td>15</td><td>12:40</td><td>7.01</td><td>6.10</td><td>-57.4</td><td>18.83</td><td>0.917</td><td>1.05</td><td>6.8</td></tr> <tr><td>20</td><td>12:45</td><td>7.00</td><td>6.15</td><td>-73.4</td><td>18.77</td><td>0.910</td><td>0.92</td><td>3.8</td></tr> <tr><td>25</td><td>12:50</td><td>7.00</td><td>6.15</td><td>-87.2</td><td>18.96</td><td>0.910</td><td>0.86</td><td>7.2</td></tr> <tr><td>30</td><td>12:55</td><td>7.00</td><td>6.16</td><td>-113.7</td><td>17.90</td><td>0.898</td><td>0.80</td><td>7.5</td></tr> <tr><td>35</td><td>13:00</td><td>6.99</td><td>6.18</td><td>-178.5</td><td>19.01</td><td>0.909</td><td>0.75</td><td>678.0</td></tr> <tr><td>40</td><td>13:05</td><td>7.00</td><td>6.18</td><td>-196.1</td><td>18.95</td><td>0.898</td><td>0.72</td><td>399.5</td></tr> <tr><td>45</td><td>13:10</td><td>7.00</td><td>6.19</td><td>-201.4</td><td>18.86</td><td>0.896</td><td>0.71</td><td>393.3</td></tr> <tr><td>50</td><td>13:15</td><td>6.98</td><td>6.19</td><td>-207.3</td><td>18.83</td><td>0.899</td><td>0.69</td><td>24.8</td></tr> <tr><td>0</td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr> <tr><td>0</td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr> </tbody> </table>									Time (minutes)	Time	Depth to Water (ft TOC)	pH (std units)	ORP (mV)	Temperature (deg C)	Spec. Cond. (mS/cm)	Diss. Oxygen (mg/L)	Turbidity (NTU)	0	12:25	7.00							5	12:30	7.02	6.07	-0.8	18.94	0.932	1.94	7.7	10	12:35	7.01	6.08	-33.7	18.87	0.925	1.21	18.7	15	12:40	7.01	6.10	-57.4	18.83	0.917	1.05	6.8	20	12:45	7.00	6.15	-73.4	18.77	0.910	0.92	3.8	25	12:50	7.00	6.15	-87.2	18.96	0.910	0.86	7.2	30	12:55	7.00	6.16	-113.7	17.90	0.898	0.80	7.5	35	13:00	6.99	6.18	-178.5	19.01	0.909	0.75	678.0	40	13:05	7.00	6.18	-196.1	18.95	0.898	0.72	399.5	45	13:10	7.00	6.19	-201.4	18.86	0.896	0.71	393.3	50	13:15	6.98	6.19	-207.3	18.83	0.899	0.69	24.8	0									0								
Time (minutes)	Time	Depth to Water (ft TOC)	pH (std units)	ORP (mV)	Temperature (deg C)	Spec. Cond. (mS/cm)	Diss. Oxygen (mg/L)	Turbidity (NTU)																																																																																																																														
0	12:25	7.00																																																																																																																																				
5	12:30	7.02	6.07	-0.8	18.94	0.932	1.94	7.7																																																																																																																														
10	12:35	7.01	6.08	-33.7	18.87	0.925	1.21	18.7																																																																																																																														
15	12:40	7.01	6.10	-57.4	18.83	0.917	1.05	6.8																																																																																																																														
20	12:45	7.00	6.15	-73.4	18.77	0.910	0.92	3.8																																																																																																																														
25	12:50	7.00	6.15	-87.2	18.96	0.910	0.86	7.2																																																																																																																														
30	12:55	7.00	6.16	-113.7	17.90	0.898	0.80	7.5																																																																																																																														
35	13:00	6.99	6.18	-178.5	19.01	0.909	0.75	678.0																																																																																																																														
40	13:05	7.00	6.18	-196.1	18.95	0.898	0.72	399.5																																																																																																																														
45	13:10	7.00	6.19	-201.4	18.86	0.896	0.71	393.3																																																																																																																														
50	13:15	6.98	6.19	-207.3	18.83	0.899	0.69	24.8																																																																																																																														
0																																																																																																																																						
0																																																																																																																																						
Analyses						clear	cloudy	turbid																																																																																																																														
VOC, TOC				<input type="checkbox"/>	Water Quality	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>																																																																																																																														
ALK, CHL				<input type="checkbox"/>	Comments																																																																																																																																	
TOT FE				<input type="checkbox"/>	85 SUNNY & WINDY																																																																																																																																	
DIS GASES				<input type="checkbox"/>	PID:0.5ppm																																																																																																																																	
SO ₄ , NO ₃				<input type="checkbox"/>																																																																																																																																		
MN II, TOT MN				<input type="checkbox"/>																																																																																																																																		
Duplicate ID				Shipped		SDG																																																																																																																																

Well MW-00-11A

Groundwater Sampling Log; Former Columbia Cement Company Site Atlantic Richfield Company (BP) - Freeport, NY

Well ID		MW-00-11A	Start	13:00	Team	AK, JRR		
Date		6/9/2004	Finish	14:15	Diameter	2 inches		
				Yes/No		Yes/No		
Depth to Water		2.46	ft TOC	2-inch pump ? N		Duplicate?	N	
Total Depth		60.14	ft TOC	Whale Pump ? N		MS/MSD?	N	
Depth to Pump		55	ft TOC	Peristaltic Pump? Y		Split-Sample?	N	
Pump Rate		0.49	L/min	Comments:		PERISTALTIC		
adjusted to:			L/min	at	minutes			
adjusted to:			L/min	at	minutes			
Time (minutes)	Time	Depth to Water (ft TOC)	pH (std units)	ORP (mV)	Temperature (deg C)	Spec. Cond. (mS/cm)	Diss. Oxygen (mg/L)	Turbidity (NTU)
0	13:00	2.46						
20	13:20	2.46	5.14	89.9	18.76	0.028	0.98	271.6
25	13:25	2.46	5.04	103.2	18.72	0.027	0.63	607.2
30	13:30	2.46	5.00	80.4	18.68	0.027	0.41	1143.8
35	13:35	2.45	5.00	52.2	18.59	0.027	0.37	1143.5
40	13:40	2.44	4.99	34.2	18.62	0.027	0.33	761.2
45	13:45	2.43	5.02	-25.7	18.51	0.027	0.30	1108.0
50	13:50	2.42	5.04	-110.4	18.58	0.027	0.29	1080.5
55	13:55	2.40	5.12	-153.4	18.50	0.027	0.28	1142.9
60	14:00	2.41	5.09	-171.4	18.42	0.026	0.28	318.8
65	14:05	2.40	5.10	-203.5	18.48	0.026	0.27	228.3
70	14:10	2.40	5.10	-200.8	18.54	0.026	0.26	189.5
75	14:15	2.40	5.13	-206.4	18.44	0.026	0.25	240.6
Analyses								
VOC, TOC			<input type="checkbox"/>			clear	cloudy	turbid
ALK, CHL			<input type="checkbox"/>			<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
TOT FE			<input type="checkbox"/>					
DIS GASSES			<input type="checkbox"/>					
SO4, NO3			<input type="checkbox"/>					
MN II, TOT MN			<input type="checkbox"/>					
Duplicate ID					Comments			
					90 SUNNY & WINDY			
					PID: 0.5 ppm			
					Shipped		SDG	

Well MW-00-12D

Groundwater Sampling Log; Former Columbia Cement Company Site
Atlantic Richfield Company (BP) - Freeport, NY

Well ID		MW-00-12D	Start	9:00	Team	AK, JRR			
Date		6/10/2004	Finish	9:55	Diameter	2 inches			
						Yes/No	Yes/No		
Depth to Water		6.77 ft TOC			2-inch pump ? N		Duplicate?	N	
Total Depth		34.70 ft TOC			Whale Pump ? N		MS/MSD?	N	
Depth to Pump		30 ft TOC			Peristaltic Pump? Y		Split-Sample?	N	
Pump Rate		0.48 L/min			Comments:	PERISTALTIC			
adjusted to:		L/min	at	minutes					
adjusted to:		L/min	at	minutes					
Time (minutes)	Time	Depth to Water (ft TOC)	pH (std units)	ORP (mV)	Temperature (deg C)	Spec. Cond. (mS/cm)	Diss. Oxygen (mg/L)	Turbidity (NTU)	
0	9:00	6.77							
15	9:15	6.81	6.56	-12	16.05	1.430	0.26	1187.1	
20	9:20	6.81	6.54	-11.6	15.92	1.427	0.53	1186.7	
25	9:25	6.81	6.55	-21.1	15.85	1.435	0.45	178.0	
30	9:30	6.83	6.57	-26.4	16.85	1.436	0.42	231.5	
35	9:35	6.85	6.59	-30.4	15.91	1.439	0.38	182.4	
40	9:40	6.86	6.59	-28.2	15.89	1.437	0.36	25.1	
45	9:45	6.86	6.59	-33.5	15.89	1.437	0.35	576.2	
0									
0									
0									
0									
0									
Analyses									
VOC, TOC				<input type="checkbox"/>			clear	cloudy	
ALK, CHL				<input type="checkbox"/>			<input type="checkbox"/>	<input type="checkbox"/>	
TOT FE				<input type="checkbox"/>					
DIS GASSES				<input type="checkbox"/>					
SO ₄ , NO ₃				<input type="checkbox"/>					
MN II, TOT MN				<input type="checkbox"/>					
Duplicate ID				Water Quality	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		
				Comments					
				75-80 PARTLY CLOUDY					
				PID: 6.6 ppm					
				Shipped		SDG			

Well MW-13-3S

Groundwater Sampling Log; Former Columbia Cement Company Site Atlantic Richfield Company (BP) - Freeport, NY

Well ID	MW-03-3S	Start	7:45	Team	AK, JRR			
Date	6/10/2004	Finish	8:45	Diameter	2 inches			
Depth to Water	6.18 ft TOC			Yes/No	Yes/No			
Total Depth	24.28 ft TOC			2-inch pump ? N	Duplicate?	N		
Depth to Pump	20 ft TOC			Whale Pump ? N	MS/MSD?	N		
Pump Rate	0.46 L/min			Peristaltic Pump? Y	Split-Sample?	N		
adjusted to	L/min	at	minutes	Comments:	PERISTALTIC			
adjusted to	L/min	at	minutes					
Time (minutes)	Time	Depth to Water (ft TOC)	pH (std units)	ORP (mV)	Temperature (deg C)	Spec. Cond. (mS/cm)	Diss. Oxygen (mg/L)	Turbidity (NTU)
0	7:45	6.18						
10	7:55	6.35	6.37	10.3	19.92	1.053	1.86	39.4
15	8:00	6.50	6.39	-18.9	19.58	1.047	0.85	68.5
20	8:05	6.37	6.45	-29	19.50	1.042	0.68	602.6
25	8:10	6.40	6.48	-30.3	19.46	1.044	0.59	566.1
30	8:15	6.41	6.50	-33.3	19.49	1.044	0.53	250.1
35	8:20	6.42	6.51	-36	19.57	4.045	0.48	617.2
40	8:25	6.44	6.52	-40.4	19.54	1.043	0.45	890.2
45	8:30	6.45	6.53	-42.8	19.59	1.044	0.43	957.2
0								
0								
0								
0								
Analyses								
VOC, TOC				X				
ALK, CHL				X				
TOT FE				X				
DIS GASSES				X				
SO ₄ , NO ₃				X				
MN II, TOT MN				X				
Water Quality					clear	cloudy	turbid	
Comments								
75 PARTLY CLOUDY								
PID: 0.0 ppm								
Duplicate ID								SDG
Shipped								

APRIL 2005 SAMPLING LOGS

Well MW-97-1S

Page 1 of 1

Groundwater Sampling Log: Remediation Management Company (BP) - Freeport, NY

Well MW-98-9D

Page 1 of 1

Groundwater Sampling Log; Remediation Management Company (BP) - Freeport, NY

Well MW-03-13S

Page 1 of 1

Groundwater Sampling Log; Remediation Management Company (BP) - Freeport, NY

Well MW-05-14S

Page 1 of 1

Groundwater Sampling Log; Remediation Management Company (BP) - Freeport, NY

Well MW-05-15D

Page 1 of 1

Groundwater Sampling Log; Remediation Management Company (BP) - Freeport, NY

JUNE 2006 SAMPLING LOGS

Well MW-1S

**Groundwater Sampling Log; Former Columbia Cement Company Site
Atlantic Richfield Company (BP) - Freeport, NY**

Well MW-97-1D

Groundwater Sampling Log; Former Columbia Cement Company Site Atlantic Richfield Company (BP) - Freeport, NY

Well ID		MW-97-1D	Start	10:58	Team	LG, TT		
Date		6/7/2006	Finish	11:46	Diameter	2 inches		
						Yes/No	Yes/No	
Depth to Water		5.85 ft TOC			2-inch pump ? N	Duplicate?	N	
Total Depth		33.65 ft TOC			Whale Pump ? N	MS/MSD?	N	
Depth to Pump		30 ft TOC			Peristaltic Pump? Y	Split-Sample?	N	
Pump Rate		0.50 L/min			Comments:	PERISTALTIC		
adjusted to:		0.4 L/min	at 6	minutes				
adjusted to:		0.3 L/min	at 9	minutes				
Time (minutes)	Time	Depth to Water (ft TOC)	pH (std units)	ORP (mV)	Temperature (deg C)	Spec. Cond. (mS/cm)	Diss. Oxygen (mg/L)	Turbidity (NTU)
0	10:58	5.85						
3	11:01	5.85	6.88	31.0	14.94	1.06	0.0	0.0
6	11:04		6.68	39.0	155.03	1.06	0.0	0.0
9	11:07		6.71	40.0	15.21	1.06	0.0	0.0
12	11:10	5.82	6.77	42.0	15.17	1.06	0.0	0.0
15	11:13		6.81	42.0	15.17	1.06	0.0	2.7
18	11:16	5.83	6.81	43.0	15.13	1.06	0.0	1.9
21	11:19		6.83	49.0	15.28	1.34	0.0	0.0
24	11:22	5.84	6.90	52.0	15.31	1.37	0.0	0.9
27	11:25		6.91	56.0	15.35	1.39	0.0	0.6
30	11:28	5.84	6.93	57.0	15.37	1.40	0.0	0.9
37	11:35	5.84	Collect Sample					
48	11:46	5.91	6.99	-17.0	15.37	1.910	0.03	0.0
Analyses						clear	cloudy	turbid
VOC, TOC			X		Water Quality	X	<input type="checkbox"/>	<input type="checkbox"/>
ALK, CHL			X					
TOT FE			X		Comments			
DIS GASSES			X		Rainy, 70			
SO4, NO3			X		PID: 0 ppm			
Duplicate ID				Shipped		SDG		

Well MW-97-1S

Groundwater Sampling Log; Former Columbia Cement Company Site
Atlantic Richfield Company (BP) - Freeport, NY

Well ID		MW-97-1S	Start	16:39	Team	LG, TT		
Date		6/7/2006	Finish	17:47	Diameter	2 inches		
						Yes/No	Yes/No	
Depth to Water		5.33 ft TOC	2-inch pump ? N			Duplicate?	N	
Total Depth		24.08 ft TOC	Whale Pump ? N			MS/MSD?	N	
Depth to Pump		19 ft TOC	Peristaltic Pump? Y			Split-Sample?	N	
Pump Rate		0.30 L/min	Comments:			PERISTALTIC		
adjusted to:		L/min	at		minutes			
adjusted to:		L/min	at		minutes			
Time (minutes)	Time	Depth to Water (ft TOC)	pH (std units)	ORP (mV)	Temperature (deg C)	Spec. Cond. (mS/cm)	Diss. Oxygen (mg/L)	Turbidity (NTU)
0	16:39	5.33						
3	16:42	5.33	6.54	-62	15.97	1.38	0.51	15.4
6	16:45		6.49	-73	16.03	1.37	0.33	11.3
9	16:48		6.51	-78	16.01	1.36	0.14	6.3
12	16:51		6.50	-81	15.95	1.36	0.07	3.6
15	16:54	5.32	6.51	-84	15.96	1.36	0.00	1.4
18	16:57		6.51	-86	16.00	1.36	0.00	8.2
21	17:00		6.51	-87	15.98	1.35	0.00	6.7
24	17:03		6.52	-89	16.01	1.35	0.00	7.2
27	17:06	5.32	6.52	-90	15.98	1.34	0.00	7.4
36	17:15	5.32	Collect sample					
68	17:47	5.24	6.55	-73	15.96	1.37	0.12	2.1
Analyses								
VOC, TOC			<input checked="" type="checkbox"/>			clear	cloudy	turbid
ALK, CHL			<input checked="" type="checkbox"/>			<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
TOT FE			<input checked="" type="checkbox"/>					
DIS GASES			<input checked="" type="checkbox"/>					
SO ₄ , NO ₃			<input checked="" type="checkbox"/>					
Duplicate ID			DUP-060706			Comments		
						Rainy, 70		
						PID: 0 ppm		
						Shipped	SDG	

Well MW-97-2S

Groundwater Sampling Log; Former Columbia Cement Company Site Atlantic Richfield Company (BP) - Freeport, NY

Well ID		MW-97-2S	Start	13:48	Team	TT, KH		
Date		6/9/2006	Finish	14:35	Diameter	2 inches		
				Yes/No		Yes/No		
Depth to Water		6.52	ft TOC	2-inch pump ? N		Duplicate?	N	
Total Depth		23.89	ft TOC	Whale Pump ? N		MS/MSD?	N	
Depth to Pump		19	ft TOC	Peristaltic Pump? Y		Split-Sample?	N	
Pump Rate		0.30	L/min	Comments:		PERISTALTIC		
adjusted to:			L/min	at	minutes			
adjusted to:			L/min	at	minutes			
Time (minutes)	Time	Depth to Water (ft TOC)	pH (std units)	ORP (mV)	Temperature (deg C)	Spec. Cond. (mS/cm)	Diss. Oxygen (mg/L)	Turbidity (NTU)
0	13:48	6.52						
3	13:51	6.52	6.43	-62	17.71	1.24	0.62	1.4
6	13:54		6.26	-59	17.55	1.22	0.0	6.5
9	13:57		6.24	-62	17.44	1.22	0.0	8.0
12	14:00	6.54	6.22	-63	17.42	1.23	0.0	3.0
15	14:03		6.24	-65	17.44	1.23	0.0	4.0
18	14:06		6.29	-69	17.56	1.23	0.0	3.8
21	14:09	6.54	6.39	-74	17.56	1.23	0.0	3.9
24	14:12		6.40	-79	17.52	1.22	0.0	77.5
27	14:15		6.41	-79	17.51	1.22	0.0	78.5
30	14:18		6.43	-80	17.43	1.22	0.0	77.6
32	14:20	Collect Sample						
47	14:35	6.50	6.46	-53	17.48	1.31	0.77	18.4
Analyses								
VOC, TOC				<input checked="" type="checkbox"/>		clear	cloudy	turbid
ALK, CHL				<input checked="" type="checkbox"/>		<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
TOT FE				<input checked="" type="checkbox"/>				
DIS GASES				<input checked="" type="checkbox"/>				
SO4, NO3				<input checked="" type="checkbox"/>				
				Comments				
				Partly Cloudy 75				
				PID: 0 ppm				
Duplicate ID				Shipped			SDG	

Well MW-97-3S

Groundwater Sampling Log; Former Columbia Cement Company Site Atlantic Richfield Company (BP) - Freeport, NY

Well MW-97-4S

Groundwater Sampling Log; Former Columbia Cement Company Site Atlantic Richfield Company (BP) - Freeport, NY

Well ID	MW-97-4S	Start	13:14	Team	LG, TT			
Date	6/8/2006	Finish	14:03	Diameter	2 inches			
Depth to Water	6.64 ft TOC			Yes/No	Yes/No			
Total Depth	24.95 ft TOC			2-inch pump ? N	Duplicate?	N		
Depth to Pump	20 ft TOC			Whale Pump ? N	MS/MSD?	N		
Pump Rate	0.35 L/min			Peristaltic Pump? Y	Split-Sample?	N		
adjusted to:	0.25 L/min	at 6	minutes	Comments:	PERISTALTIC			
adjusted to:	0.3 L/min	at 9	minutes					
Time (minutes)	Time	Depth to Water (ft TOC)	pH (std units)	ORP (mV)	Temperature (deg C)	Spec. Cond. (mS/cm)	Diss. Oxygen (mg/L)	Turbidity (NTU)
0	13:14	6.64						
3	13:17	6.64	6.99	-43.0	16.15	1.51	0.95	139.0
6	13:20		6.82	-58.0	16.17	1.53	0.28	93.0
9	13:23		6.85	-66.0	16.10	1.55	0.02	62.0
12	13:26		6.93	-77.0	16.07	1.57	0.00	14.2
15	13:29	6.66	6.96	-82.0	16.05	1.57	0.00	8.3
18	13:32		6.97	-86.0	16.08	1.58	0.00	16.1
21	13:35		6.97	-91.0	16.07	1.58	0.00	12.2
24	13:38		6.97	-94.0	16.06	1.58	0.00	10.5
27	13:41	6.66	6.97	-97.0	16.06	1.58	0.00	7.9
30	13:44		6.97	-99.0	16.02	1.58	0.00	8.5
33	13:47	6.66	6.97	-102.0	15.99	1.58	0.00	7.6
41	13:55	Collect Sample						
49	14:03	6.67	6.96	-89.0	16.05	1.60	0.32	6.9
Analyses					clear	cloudy	turbid	
VOC, TOC			X	Water Quality	X			
ALK, CHL			X					
TOT FE			X	Comments				
DIS GASES			X	Sunny, 70				
SO4, NO3			X	PID: 0.0 ppm				
Duplicate ID				Shipped		SDG		

Well MW-97-5S

Groundwater Sampling Log; Former Columbia Cement Company Site
Atlantic Richfield Company (BP) - Freeport, NY

Well ID		MW-97-5S	Start	11:23	Team	TT, KH			
Date		6/9/2006	Finish	12:15	Diameter	2 inches			
						Yes/No	Yes/No		
Depth to Water		5.47 ft TOC			2-inch pump ? N	Duplicate?	N		
Total Depth		25.80 ft TOC			Whale Pump ? N	MS/MSD?	N		
Depth to Pump		20 ft TOC			Peristaltic Pump? Y	Split-Sample?	N		
Pump Rate		0.30 L/min			Comments:	PERISTALTIC			
adjusted to:		L/min	at	minutes					
adjusted to:		L/min	at	minutes					
Time (minutes)	Time	Depth to Water (ft TOC)	pH (std units)	ORP (mV)	Temperature (deg C)	Spec. Cond. (mS/cm)	Diss. Oxygen (mg/L)	Turbidity (NTU)	
0	11:23	5.47							
3	11:26		6.97	-115.0	18.72	0.871	5.57	69.3	
6	11:29		6.99	-135.0	17.22	0.858	0.00	89.7	
9	11:32		6.96	-137.0	16.95	0.895	0.00	526.0	
12	11:35	5.82	6.92	-136.0	16.91	0.906	0.00	603.0	
15	11:38		6.88	-136.0	16.74	0.914	0.00	304.0	
18	11:41		6.86	-136.0	16.63	0.921	0.00	226.0	
21	11:44	5.87	6.87	-137.0	16.69	0.922	0.00	233.0	
24	11:47		6.90	-139.0	16.64	0.932	0.00	357.0	
27	11:50		6.98	-144.0	16.71	0.939	0.00	284.0	
30	11:53		7.00	-146.0	16.83	0.936	0.00	273.0	
33	11:56		7.03	-147.0	16.83	0.942	0.00	266.0	
37	12:00	5.88	Collect Sample						
49	12:12	5.57	7.05	-114.0	17.64	0.973	0.00	143.0	
Analyses									
VOC, TOC			<input checked="" type="checkbox"/>			clear	cloudy	turbid	
ALK, CHL			<input checked="" type="checkbox"/>			<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
TOT FE			<input checked="" type="checkbox"/>						
DIS GASES			<input checked="" type="checkbox"/>						
SO ₄ , NO ₃			<input checked="" type="checkbox"/>						
Duplicate ID	N/A					Shipped		SDG	

Well MW-97-6S

Groundwater Sampling Log; Former Columbia Cement Company Site
Atlantic Richfield Company (BP) - Freeport, NY

Well ID		MW-97-6S	Start	15:32	Team	LG, TT		
Date		6/8/2006	Finish	16:20	Diameter	2 inches		
						Yes/No	Yes/No	
Depth to Water		6.42 ft TOC				2-inch pump ? N	Duplicate?	N
Total Depth		25.66 ft TOC				Whale Pump ? N	MS/MSD?	N
Depth to Pump		20 ft TOC				Peristaltic Pump? Y	Split-Sample?	N
Pump Rate		0.25 L/min				Comments: PERISTALTIC		
adjusted to		0.3 L/min	at 6	minutes				
adjusted to		L/min	at	minutes				
Time (minutes)	Time	Depth to Water (ft TOC)	pH (std units)	ORP (mV)	Temperature (deg C)	Spec. Cond. (mS/cm)	Diss. Oxygen (mg/L)	Turbidity (NTU)
0	15:32	6.42						
3	15:35	6.42	6.57	-62	16.88	1.68	1.92	59.3
6	15:38		6.40	-63	16.56	1.69	1.01	75.2
9	15:41		6.38	-66	16.53	1.68	0.80	29.3
12	15:44	6.43	6.41	-70	16.57	1.69	0.15	9.7
15	15:47		6.43	-72	16.58	1.69	0.00	4.9
18	15:50		6.44	-74	16.52	1.70	0.00	8.6
21	15:53		6.44	-76	16.53	1.70	0.00	6.9
24	15:56		6.45	-78	16.56	1.70	0.00	5.5
27	15:59	6.44	6.46	-79	16.57	1.69	0.00	4.7
30	16:02		6.47	-80	16.58	1.69	0.00	5.8
38	16:10							
48	16:20	6.45	6.47	-58	16.68	1.70	0.28	13.7
Analyses								
VOC, TOC			X			clear	cloudy	turbid
ALK, CHL			X					
TOT FE			X					
DIS GASSES			X					
SO ₄ , NO ₃			X					
Duplicate ID						Shipped		SDG

Well MW-97-7S
 Groundwater Sampling Log; Former Columbia Cement Company Site
 Atlantic Richfield Company (BP) - Freeport, NY

Well ID		MW-97-7S	Start	14:50	Team	LG, TT		
Date		6/6/2006	Finish	15:50	Diameter	2 inches		
						Yes/No		Yes/No
Depth to Water		6.73 ft TOC				2-inch pump ? N	Duplicate?	N
Total Depth		31.35 ft TOC				Whale Pump ? N	MS/MSD?	N
Depth to Pump		26 ft TOC				Peristaltic Pump? Y	Split-Sample?	N
Pump Rate		0.40 L/min				Comments:	PERISTALTIC	
adjusted to:		3 L/min	at 8		minutes			
adjusted to:		L/min	at		minutes			

Time (minutes)	Time	Depth to Water (ft TOC)	pH (std units)	ORP (mV)	Temperature (deg C)	Spec. Cond. (mS/cm)	Diss. Oxygen (mg/L)	Turbidity (NTU)
0	14:50	6.73						
5	14:55		6.33	-50	17.33	0.632	1.26	19.8
8	14:58	6.74	6.26	-47	17.02	0.630	0.73	12.5
11	15:01		6.23	-52	16.55	0.621	0.13	10.1
14	15:04		6.40	-68	16.89	0.725	0.00	9.1
17	15:07	6.72	6.50	-81	16.98	0.815	0.00	2.2
20	15:10		6.61	-101	16.96	0.988	0.00	1.8
23	15:13		6.67	-106	17.01	0.97	0.00	1.3
26	15:16		6.69	-107	16.99	1.01	0.00	1.6
29	15:19		6.67	-108	17.01	1.04	0.00	0.3
32	15:22		6.67	-109	17.20	1.06	0.00	0.6
35	15:25	6.71	6.66	-108	17.18	1.08	0.00	0.5
38	15:28		6.66	-108	17.13	1.09	0.00	0.7
50	15:40	6.71	Collect Sample					
60	15:50		6.61	-90	16.70	1.090	0.00	17.7

Analyses						clear	cloudy	turbid	
VOC, TOC			X			Water Quality	X	<input type="checkbox"/>	<input type="checkbox"/>
ALK, CHL			X						
TOT FE			X			Comments			
DIS GASES			X			75-80 PARTLY CLOUDY			
SO4, NO3			X			PID: 6.6 ppm			
Duplicate ID						Shipped		SDG	

Well MW-98-8S

Groundwater Sampling Log; Former Columbia Cement Company Site
Atlantic Richfield Company (BP) - Freeport, NY

Well ID		MW-98-8S	Start	13:49	Team	LG, TT		
Date		6/7/2006	Finish	14:30	Diameter	2 inches		
						Yes/No	Yes/No	
Depth to Water		6.90 ft TOC				2-inch pump ? N	Duplicate?	N
Total Depth		20.82 ft TOC				Whale Pump ? N	MS/MSD?	N
Depth to Pump		15 ft TOC				Peristaltic Pump? Y	Split-Sample?	N
Pump Rate		0.30 L/min				Comments:	PERISTALTIC	
adjusted to:		L/min	at		minutes			
adjusted to:		L/min	at		minutes			
Time (minutes)	Time	Depth to Water (ft TOC)	pH (std units)	ORP (mV)	Temperature (deg C)	Spec. Cond. (mS/cm)	Diss. Oxygen (mg/L)	Turbidity (NTU)
0	13:49	6.90						
3	13:52	6.90	6.63	-114	15.84	2.71	0.31	717.0
6	13:55		6.66	-117	15.73	2.51	0.22	126.0
9	13:58		6.65	-119	15.76	2.49	0.00	49.5
12	14:01	6.97	6.70	-128	15.34	2.52	0.00	24.0
15	14:04		6.81	-131	15.72	2.55	0.08	15.8
18	14:07	6.97	6.81	-133	15.75	2.56	0.02	14.2
21	14:10		6.83	-135	15.75	2.56	0.00	14.7
24	14:13		6.84	-137	15.74	2.57	0.00	13.9
31	14:20	6.97	Collect Sample					
41	14:30	6.98	6.85	-115	15.74	2.52	0.13	14.2
0								
0								
Analyses								
VOC, TOC			X			clear	cloudy	turbid
ALK, CHL			X					
TOT FE			X					
DIS GASSES			X					
SO ₄ , NO ₃			X					
Duplicate ID						Shipped		SDG

Well MW-98-8D

Groundwater Sampling Log; Former Columbia Cement Company Site
Atlantic Richfield Company (BP) - Freeport, NY

Well ID		MW-98-8D	Start	15:00	Team	LG, TT		
Date		6/7/2006	Finish	15:42	Diameter	2 inches		
						Yes/No	Yes/No	
Depth to Water		6.57 ft TOC				2-inch pump ? N	Duplicate?	N
Total Depth		34.76 ft TOC				Whale Pump ? N	MS/MSD?	N
Depth to Pump		30 ft TOC				Peristaltic Pump? Y	Split-Sample?	N
Pump Rate		0.30 L/min				Comments:	PERISTALTIC	
adjusted to:		L/min	at		minutes			
adjusted to:		L/min	at		minutes			
Time (minutes)	Time	Depth to Water (ft TOC)	pH (std units)	ORP (mV)	Temperature (deg C)	Spec. Cond. (mS/cm)	Diss. Oxygen (mg/L)	Turbidity (NTU)
0	15:00	6.57						
3	15:03	6.57	7.25	12	16.12	0.349	4.41	111.4
6	15:06		7.01	-94	16.08	1.51	2.01	17.3
9	15:09		6.76	-114	16.13	2.16	0.29	11.1
12	15:12		6.85	-120	16.14	2.18	0.10	2.2
15	15:15	6.59	6.87	-121	16.14	2.21	0.00	4.3
18	15:18		6.87	-124	16.15	2.24	0.00	3.9
21	15:21	6.58	6.87	-125	16.14	2.25	0.00	3.1
24	15:24	6.59	6.87	-125	16.14	2.25	0.00	2.7
30	15:30	6.59	Collect Sample					
42	15:42	6.58	6.85	-103	16.13	2.27	0.31	1.1
0								
0								
Analyses						clear	cloudy	turbid
VOC, TOC			X			<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
ALK, CHL			X					
TOT FE			X					
DIS GASES			X					
SO ₄ , NO ₃			X					
Duplicate ID				Shipped		SDG		

Well MW-98-9D

Groundwater Sampling Log; Former Columbia Cement Company Site Atlantic Richfield Company (BP) - Freeport, NY

Well ID	MW-98-9D	Start	11:18	Team	LG, TT			
Date	6/8/2006	Finish	12:05	Diameter	2 inches			
					Yes/No		Yes/No	
Depth to Water	5.42 ft TOC				2-inch pump ? N		Duplicate?	N
Total Depth	36.52 ft TOC				Whale Pump ? N		MS/MSD?	N
Depth to Pump	32 ft TOC				Peristaltic Pump? Y		Split-Sample?	N
Pump Rate	0.35 L/min				Comments:		PERISTALTIC	
adjusted to:	0.3 L/min	at 6		minutes				
adjusted to:	L/min	at		minutes				
Time (minutes)	Time	Depth to Water (ft TOC)	pH (std units)	ORP (mV)	Temperature (deg C)	Spec. Cond. (mS/cm)	Diss. Oxygen (mg/L)	Turbidity (NTU)
0	11:18	5.42						
3	11:21	5.42	6.37	-60	16.44	1.48	2.36	71.1
6	11:24		6.40	-68	15.45	1.42	1.13	60.1
9	11:27		6.45	-75	16.48	1.39	0.73	11.3
12	11:30		6.46	-77	16.48	1.38	0.00	8.3
15	11:33	5.43	6.46	-79	16.46	1.38	0.00	16.3
18	11:36		6.46	-80	16.47	1.38	0.00	31.4
21	11:39		6.46	-82	16.45	1.37	0.00	33.7
24	11:42		6.46	-83	16.43	1.37	0.00	36.9
27	11:45		6.46	-84	16.44	1.36	0.00	38.2
30	11:48	5.45	6.46	-85	16.47	1.35	0.00	35.1
37	11:55							
47	12:05	5.46	6.56	-55	16.48	1.38	0.31	11.2
Analyses					clear	cloudy	turbid	
VOC, TOC		X						
ALK, CHL		X						
TOT FE		X						
DIS GASSES		X						
SO ₄ , NO ₃		X						
Comments								
Sunny, 70								
PID: 0 ppm								
Duplicate ID				Shipped			SDG	

Well MW-98-10D

Groundwater Sampling Log; Former Columbia Cement Company Site
Atlantic Richfield Company (BP) - Freeport, NY

Well ID		MW-98-10D	Start	12:46	Team	TT, KH		
Date		6/9/2006	Finish	13:33	Diameter	2 inches		
						Yes/No	Yes/No	
Depth to Water		6.69 ft TOC	2-inch pump ? N			Duplicate?	N	
Total Depth		34.85 ft TOC	Whale Pump ? N			MS/MSD?	N	
Depth to Pump		30 ft TOC	Peristaltic Pump? Y			Split-Sample?	N	
Pump Rate		0.50 L/min	Comments:			PERISTALTIC		
adjusted to:		0.35 L/min at 9 minutes						
adjusted to:		L/min at minutes						
Time (minutes)	Time	Depth to Water (ft TOC)	pH (std units)	ORP (mV)	Temperature (deg C)	Spec. Cond. (mS/cm)	Diss. Oxygen (mg/L)	Turbidity (NTU)
0	12:46	6.69						
3	12:49	6.69	6.56	-64	18.26	1.21	0.64	16.6
6	12:52		6.35	-64	17.75	1.21	0.0	24.7
9	12:55		6.27	-63	17.70	1.20	0.0	46.3
12	12:58	6.71	6.26	-65	17.95	1.20	0.0	86.5
15	13:01		6.40	-74	17.91	1.19	0.0	199.0
18	13:04		6.47	-79	17.89	1.19	0.0	235.0
21	13:07	6.71	6.49	-81	7.83	1.19	0.0	253.0
24	13:10		6.51	-83	17.84	1.19	0.0	258.0
27	13:13		6.51	-84.0	17.79	1.20	0.0	247.0
34	13:20							
47	13:33	6.72	6.52	-64	17.83	1.24	0.0	10.8
Analyses								
VOC, TOC			<input checked="" type="checkbox"/>			clear	cloudy	turbid
ALK, CHL			<input checked="" type="checkbox"/>					
TOT FE			<input checked="" type="checkbox"/>					
DIS GASES			<input checked="" type="checkbox"/>					
SO ₄ , NO ₃			<input checked="" type="checkbox"/>					
Duplicate ID							Shipped	SDG

Well MW-00-11A

Groundwater Sampling Log; Former Columbia Cement Company Site Atlantic Richfield Company (BP) - Freeport, NY

Well ID		MW-00-11A	Start	12:10	Team	LG, TT		
Date		6/7/2006	Finish	12:55	Diameter	2 inches		
				Yes/No	Yes/No			
Depth to Water		3.10	ft TOC	2-inch pump ? N		Duplicate?	N	
Total Depth		60.26	ft TOC	Whale Pump ? N		MS/MSD?	N	
Depth to Pump		55	ft TOC	Peristaltic Pump? Y		Split-Sample?	N	
Pump Rate		0.30	L/min	Comments:		PERISTALTIC		
adjusted to:			L/min	at	minutes			
adjusted to:			L/min	at	minutes			
Time (minutes)	Time	Depth to Water (ft TOC)	pH (std units)	ORP (mV)	Temperature (deg C)	Spec. Cond. (mS/cm)	Diss. Oxygen (mg/L)	Turbidity (NTU)
0	12:10	3.10						
5	12:15		7.19	92	15.73	0.054	2.84	82.1
8	12:18		7.03	109	15.78	0.049	2.67	77.9
11	12:21	3.11	6.63	149	15.74	0.043	2.63	50.3
14	12:24		5.90	197	15.73	0.042	2.60	20.2
17	12:27		5.36	202	15.74	0.041	2.53	1.1
20	12:30		5.35	204	15.75	0.041	2.51	1.3
23	12:33	3.11	5.36	206	15.73	0.040	2.51	1.7
30	12:40	3.11	Collect Sample					
45	12:55	3.06	5.59	122	15.72	0.039	1.24	8.1
Analyses								
VOC, TOC			X			clear	cloudy	turbid
ALK, CHL			X					
TOT FE			X					
DIS GASSES			X					
SO4, NO3			X					
				Comments				
				Rainy, 60				
				PID: 0.0 ppm				
Duplicate ID				Shipped		SDG		

Well MW-00-12D

Groundwater Sampling Log; Former Columbia Cement Company Site
Atlantic Richfield Company (BP) - Freeport, NY

Well ID		MW-00-12D	Start	14:20	Team	LG, TT		
Date		6/8/2006	Finish	15:04	Diameter	2 inches		
						Yes/No	Yes/No	
Depth to Water		6.36 ft TOC				2-inch pump ? N	Duplicate?	N
Total Depth		34.57 ft TOC				Whale Pump ? N	MS/MSD?	N
Depth to Pump		30 ft TOC				Peristaltic Pump? Y	Split-Sample?	N
Pump Rate		0.35 L/min				Comments:	PERISTALTIC	
adjusted to:		0.3 L/min	at 9		minutes			
adjusted to:		L/min			minutes			
Time (minutes)	Time	Depth to Water (ft TOC)	pH (std units)	ORP (mV)	Temperature (deg C)	Spec. Cond. (mS/cm)	Diss. Oxygen (mg/L)	Turbidity (NTU)
0	14:20	6.36						
3	14:23	6.36	7.29	49	15.91	0.097	3.61	22.3
6	14:26		6.25	110	16.00	0.113	2.87	15.2
9	14:29		6.06	57	16.02	0.163	2.16	14.0
12	14:32		6.73	-24	16.17	0.921	1.12	9.7
15	14:35	6.36	6.83	-77	16.17	1.71	0.21	11.5
18	14:38		6.87	-95	16.15	1.85	0.00	9.1
21	14:41		6.89	-97	16.14	1.86	0.00	7.8
24	14:44	6.36	6.91	-99	16.12	0.87	0.00	8.2
27	14:47		6.92	-101	16.16	1.88	0.00	8.9
35	14:55							
44	15:04	6.34	6.97	-93	16.11	1.94	0.20	6.9
0								
Analyses								
VOC, TOC			<input checked="" type="checkbox"/>			clear	cloudy	turbid
ALK, CHL			<input checked="" type="checkbox"/>			<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
TOT FE			<input checked="" type="checkbox"/>					
DIS GASES			<input checked="" type="checkbox"/>					
SO ₄ , NO ₃			<input checked="" type="checkbox"/>					
Duplicate ID				Comments				
				Sunny, 70				
				PID: 0 ppm				
				Shipped		SDG		

Well MW-03-13S

Groundwater Sampling Log; Former Columbia Cement Company Site
Atlantic Richfield Company (BP) - Freeport, NY

Well ID		MW-03-13S	Start	12:30	Team	LG, TT																																																																																																																																										
Date		6/6/2006	Finish	13:45	Diameter	2 inches																																																																																																																																										
							Yes/No	Yes/No																																																																																																																																								
Depth to Water		6.43 ft TOC	2-inch pump ? N			Duplicate?	N																																																																																																																																									
Total Depth		24.30 ft TOC	Whale Pump ? N			MS/MSD?	N																																																																																																																																									
Depth to Pump		20 ft TOC	Peristaltic Pump? Y			Split-Sample?	N																																																																																																																																									
Pump Rate		0.45 L/min	Comments:			PERISTALTIC																																																																																																																																										
adjusted to:		0.3 L/min	at 8	minutes																																																																																																																																												
adjusted to:		L/min	at	minutes																																																																																																																																												
<table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th>Time (minutes)</th> <th>Time</th> <th>Depth to Water (ft TOC)</th> <th>pH (std units)</th> <th>ORP (mV)</th> <th>Temperature (deg C)</th> <th>Spec. Cond. (mS/cm)</th> <th>Diss. Oxygen (mg/L)</th> <th>Turbidity (NTU)</th> </tr> </thead> <tbody> <tr><td>0</td><td>12:30</td><td>6.43</td><td></td><td></td><td></td><td></td><td></td><td></td></tr> <tr><td>5</td><td>12:35</td><td>6.43</td><td>6.75</td><td>-155</td><td>20.05</td><td>1.36</td><td>0.36</td><td>0.0</td></tr> <tr><td>8</td><td>12:38</td><td></td><td>6.70</td><td>-152</td><td>20.09</td><td>1.33</td><td>0.15</td><td>0.0</td></tr> <tr><td>11</td><td>12:41</td><td>6.41</td><td>6.62</td><td>-151</td><td>19.81</td><td>1.33</td><td>0.11</td><td>0.0</td></tr> <tr><td>14</td><td>12:44</td><td></td><td>6.64</td><td>-1556</td><td>19.75</td><td>1.32</td><td>0.02</td><td>0.0</td></tr> <tr><td>17</td><td>12:47</td><td></td><td>6.71</td><td>-161</td><td>19.66</td><td>1.32</td><td>0.01</td><td>0.0</td></tr> <tr><td>20</td><td>12:50</td><td>6.40</td><td>6.80</td><td>-164</td><td>19.59</td><td>1.31</td><td>0.01</td><td>139.0</td></tr> <tr><td>23</td><td>12:53</td><td></td><td>6.84</td><td>-165</td><td>19.56</td><td>1.31</td><td>0.00</td><td>196.0</td></tr> <tr><td>26</td><td>12:56</td><td></td><td>6.85</td><td>-166</td><td>19.65</td><td>1.31</td><td>0.00</td><td>212.0</td></tr> <tr><td>29</td><td>12:59</td><td>6.38</td><td>6.85</td><td>-164</td><td>19.68</td><td>1.30</td><td>0.00</td><td>218.0</td></tr> <tr><td>32</td><td>13:02</td><td></td><td>6.83</td><td>-162</td><td>19.55</td><td>1.30</td><td>0.00</td><td>215.0</td></tr> <tr><td>35</td><td>13:05</td><td>6.35</td><td>6.83</td><td>-163</td><td>19.51</td><td>1.30</td><td>0.00</td><td>216.0</td></tr> <tr><td>45</td><td>13:15</td><td></td><td>Collect sample</td><td></td><td></td><td></td><td></td><td></td></tr> <tr><td>60</td><td>13:30</td><td>6.30</td><td>6.83</td><td>-137</td><td>19.99</td><td>1.33</td><td>0.23</td><td>111.0</td></tr> </tbody> </table>										Time (minutes)	Time	Depth to Water (ft TOC)	pH (std units)	ORP (mV)	Temperature (deg C)	Spec. Cond. (mS/cm)	Diss. Oxygen (mg/L)	Turbidity (NTU)	0	12:30	6.43							5	12:35	6.43	6.75	-155	20.05	1.36	0.36	0.0	8	12:38		6.70	-152	20.09	1.33	0.15	0.0	11	12:41	6.41	6.62	-151	19.81	1.33	0.11	0.0	14	12:44		6.64	-1556	19.75	1.32	0.02	0.0	17	12:47		6.71	-161	19.66	1.32	0.01	0.0	20	12:50	6.40	6.80	-164	19.59	1.31	0.01	139.0	23	12:53		6.84	-165	19.56	1.31	0.00	196.0	26	12:56		6.85	-166	19.65	1.31	0.00	212.0	29	12:59	6.38	6.85	-164	19.68	1.30	0.00	218.0	32	13:02		6.83	-162	19.55	1.30	0.00	215.0	35	13:05	6.35	6.83	-163	19.51	1.30	0.00	216.0	45	13:15		Collect sample						60	13:30	6.30	6.83	-137	19.99	1.33	0.23	111.0
Time (minutes)	Time	Depth to Water (ft TOC)	pH (std units)	ORP (mV)	Temperature (deg C)	Spec. Cond. (mS/cm)	Diss. Oxygen (mg/L)	Turbidity (NTU)																																																																																																																																								
0	12:30	6.43																																																																																																																																														
5	12:35	6.43	6.75	-155	20.05	1.36	0.36	0.0																																																																																																																																								
8	12:38		6.70	-152	20.09	1.33	0.15	0.0																																																																																																																																								
11	12:41	6.41	6.62	-151	19.81	1.33	0.11	0.0																																																																																																																																								
14	12:44		6.64	-1556	19.75	1.32	0.02	0.0																																																																																																																																								
17	12:47		6.71	-161	19.66	1.32	0.01	0.0																																																																																																																																								
20	12:50	6.40	6.80	-164	19.59	1.31	0.01	139.0																																																																																																																																								
23	12:53		6.84	-165	19.56	1.31	0.00	196.0																																																																																																																																								
26	12:56		6.85	-166	19.65	1.31	0.00	212.0																																																																																																																																								
29	12:59	6.38	6.85	-164	19.68	1.30	0.00	218.0																																																																																																																																								
32	13:02		6.83	-162	19.55	1.30	0.00	215.0																																																																																																																																								
35	13:05	6.35	6.83	-163	19.51	1.30	0.00	216.0																																																																																																																																								
45	13:15		Collect sample																																																																																																																																													
60	13:30	6.30	6.83	-137	19.99	1.33	0.23	111.0																																																																																																																																								
Analyses					clear	cloudy	turbid																																																																																																																																									
VOC, TOC			<input checked="" type="checkbox"/>	Water Quality	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>																																																																																																																																									
ALK, CHL			<input checked="" type="checkbox"/>	Comments																																																																																																																																												
TOT FE			<input checked="" type="checkbox"/>	75-80 PARTLY CLOUDY																																																																																																																																												
DIS GASSES			<input checked="" type="checkbox"/>	PID: 6.6 ppm																																																																																																																																												
SO4, NO3			<input checked="" type="checkbox"/>																																																																																																																																													
Duplicate ID				Shipped		SDG																																																																																																																																										

Well MW-05-14S

Groundwater Sampling Log; Former Columbia Cement Company Site Atlantic Richfield Company (BP) - Freeport, NY

Well MW-05-15D

Groundwater Sampling Log; Former Columbia Cement Company Site
Atlantic Richfield Company (BP) - Freeport, NY


Well ID	MW-05-15D	Start	8:56	Team	LG, TT			
Date	6/8/2006	Finish	9:50	Diameter	2 inches			
				Yes/No		Yes/No		
Depth to Water	4.59	ft TOC	2-inch pump ? N		Duplicate?	N		
Total Depth	38.23	ft TOC	Whale Pump ? N		MS/MSD?	N		
Depth to Pump	33	ft TOC	Peristaltic Pump? Y		Split-Sample?	N		
Pump Rate	0.20	L/min	Comments: PERISTALTIC					
adjusted to:	0.35	L/min	at 6	minutes				
adjusted to:		L/min	at	minutes				
Time (minutes)	Time	Depth to Water (ft TOC)	pH (std units)	ORP (mV)	Temperature (deg C)	Spec. Cond. (mS/cm)	Diss. Oxygen (mg/L)	Turbidity (NTU)
0	8:56	4.59						
3	8:59	4.59	6.14	1	16.73	0.382	0.93	19.3
6	9:02		6.15	-12	16.84	0.343	0.71	15.9
9	9:05		6.09	-23	16.71	0.323	0.21	7.9
12	9:08		6.15	-33	16.74	0.285	2.06	14.2
15	9:11	4.70	6.16	-37	16.74	0.290	0.00	8.7
18	9:14		6.18	-40	16.72	0.291	0.00	9.6
21	9:17							
24	9:20	4.71	6.21	-43	16.74	0.299	0.00	8.3
27	9:23		6.23	-45	16.72	0.301	0.00	10.2
30	9:26		6.25	-48	16.74	0.302	0.00	7.9
33	9:29		6.28	-50	16.75	0.310	0.00	7.7
36	9:32	4.73	6.29	-52	16.77	0.311	0.00	8.2
44	9:40	4.73	Collect Sample					
54	9:50	4.75	6.61	-47	16.69	0.358	0.31	3.2
Analyses								
VOC, TOC			<input checked="" type="checkbox"/>	Water Quality		clear	cloudy	turbid
ALK, CHL			<input checked="" type="checkbox"/>			<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
TOT FE			<input checked="" type="checkbox"/>	Comments				
DIS GASES			<input checked="" type="checkbox"/>	Sunny. 70				
SO ₄ , NO ₃			<input checked="" type="checkbox"/>	PID: 0 ppm				
Duplicate ID	MW0616			Shipped		SDG		

APPENDIX D

**MONITORING WELL BORING LOGS AND
WELL CONSTRUCTION DIAGAMS**

URS CORPORATION
Soil Boring Log

Location of Boring	Job No.:	Client:	Location:
	38546433	BP/BELCI ATLANTIC RICHFIELD	COLUMBIA CEMENT FREEPORT, NY
Logged By:	ANDREW KOHLBECKER		Boring No.:
	MW-05-15D		
Driller:	AQUIFER DRILLING & TESTING		Sheet:
	4.5" HOLLOW STEM AUGER		1 of 2
Sampling Method:	Drilling		
	SPLIT SPOONS		
Water Level:	-6 FEET BELOW GRADE		Start Time
Depth of Screen:			Finish Time
Depth of Gravel:			Date
Depth of Bentonite:			4/19/2005
			4/19/2005



URS CORPORATION


Soil Boring Log

Location of Boring	Job No.:	Client:	Location:
	38546433	BP/BELCI ATLANTIC RICHFIELD	COLUMBIA CEMENT FREEPORT, NY
	Logged By:	ANDREW KOHLBECKER	Boring No.:
	Driller:	AQUIFER DRILLING & TESTING	MW-05-15D
	Drilling Method:	4.5" HOLLOW STEM AUGER	Sheet:
	Sampling Method:	SPLIT SPOONS	2 of 2
	Water Level:	-6 FEET BELOW GRADE	Drilling Start Time
	Depth of Screen:		Finish Time
	Depth of Gravel:		Date
	Depth of Bentonite:		4/19/2005

URS CORPORATION

MONITORING WELL CONSTRUCTION DIAGRAM


MW-05-14S



URS CORPORATION


MONITORING WELL CONSTRUCTION DIAGRAM

MW-05-15D




APPENDIX E
SLUG TEST DRAWDOWN CURVES


MW-00-14S
Falling Head Slug Test
Bouwer & Rice Analysis




MW-00-14S
Falling Head Slug Test
Bouwer & Rice Analysis




MW-00-14S
Rising Head Slug Test
Bouwer & Rice Analysis




MW-00-14S
Rising Head Slug Test
Bouwer & Rice Analysis




MW-97-1S
Falling Head Slug Test
Bouwer & Rice Analysis




MW-97-1S
Falling Head Slug Test
Bouwer & Rice Analysis




MW-97-1S
Rising Head Slug Test
Bouwer & Rice Analysis




MW-97-1S
Rising Head Slug Test
Bouwer & Rice Analysis




MW-97-6S
Rising Head Slug Test #1
Bouwer & Rice Analysis




MW-97-6S
Falling Head Slug Test #1
Bouwer & Rice Analysis




MW-97-6S
Falling Head Slug Test #2
Bouwer & Rice Analysis




MW-97-6S
Falling Head Slug Test #2
Bouwer & Rice Analysis




MW-97-6S
Rising Head Slug Test #1
Bouwer & Rice Analysis




MW-97-6S
Rising Head Slug Test #1
Bouwer & Rice Analysis




MW-97-6S
Rising Head Slug Test #2
Bouwer & Rice Analysis




MW-97-6S
Rising Head Slug Test #2
Bouwer & Rice Analysis




MW-98-9D
Falling Head Slug Test
Bouwer & Rice Analysis




MW-98-9D
Falling Head Slug Test
Bouwer & Rice Analysis



MW-98-9D
Rising Head Slug Test
Bouwer & Rice Analysis



MW-98-9D
Rising Head Slug Test
Bouwer & Rice Analysis



APPENDIX F
SOIL GAS SAMPLING LOGS

2005 SOIL GAS SAMPLING LOGS

URS Corporation

EPA Method TO-15

SAMPLING DATA SHEET

GENERAL INFORMATION

SITE LOCATION: SG-05-01
SITE ADDRESS: Former Columbia
Cement Facility, Freeport, NY
SAMPLING DATE: 09/21/05

SHIPPING DATE: 09/22/05
CANISTER S/N: A-306
SAMPLER ID: Peter Reynolds
OPERATOR: Peter Reynolds
CANISTER LEAK
CHECK DATE: N/A

SAMPLING INFORMATION

	INTERIOR °C	AMBIENT °C	MINIMUM °C	MAXIMUM °C	VACUUM in/Hg	VACUUM in/Hg
START	N/A	20.0	20.0	20.0	-30.0	N/A
STOP	N/A	20.0	N/A	N/A	-4.0	N/A

SAMPLING TIMES

START	STOP
0830	0902

INSTRUMENT READINGS

PID(ppm)	FID (ppm)	% He Enclosure	% He Sample	Time
0.0	N/A	92.0	0.03	0820
0.0	N/A	88.0	0.01	0830
0.0	N/A	75.0	0.0	0902

COMMENTS

Sampled 5 feet below grade (soil gas point, grouted at grade).

Flow Controller FC-58

URS Corporation

EPA Method TO-15

SAMPLING DATA SHEET

GENERAL INFORMATION

SITE LOCATION: SG-05-02
SITE ADDRESS: Former Columbia
Cement Facility, Freeport, NY
SAMPLING DATE: 09/20/05

SHIPPING DATE: 09/22/05
CANISTER S/N: A-374
SAMPLER ID: Peter Reynolds
OPERATOR: Peter Reynolds
CANISTER LEAK
CHECK DATE: N/A

SAMPLING INFORMATION

	INTERIOR °C	AMBIENT °C	MINIMUM °C	MAXIMUM °C	VACUUM in/Hg	VACUUM in/Hg
START	N/A	27.8	27.8	27.8	-30.0	N/A
STOP	N/A	27.8	N/A	N/A	-4.8	N/A

SAMPLING TIMES

START	STOP
1400	1435

INSTRUMENT READINGS

PID(ppm)	FID (ppm)	% He Enclosure	% He Sample	Time
0.0	N/A	94.0	0.04	1400
0.0	N/A	90.0	0.0	1414
0.0	N/A	82.0	0.0	1425
0.0	N/A	89.0	0.04	1440

COMMENTS

Sampled 5 feet below grade (soil gas point, grouted at grade).

Flow Controller FC-139

Helium recharged at 1440 as a final check.

URS Corporation

EPA Method TO-15

SAMPLING DATA SHEET

GENERAL INFORMATION

SITE LOCATION: SG-05-03
SITE ADDRESS: Former Columbia
Cement Facility, Freeport, NY
SAMPLING DATE: 09/21/05

SHIPPING DATE: 09/22/05
CANISTER S/N: A-138
SAMPLER ID: Peter Reynolds
CANISTER LEAK
CHECK DATE: N/A

SAMPLING INFORMATION

	INTERIOR °C	AMBIENT °C	MINIMUM °C	MAXIMUM °C	VACUUM in/Hg	VACUUM in/Hg
START	N/A	25.6	25.6	25.6	-30.0	N/A
STOP	N/A	25.6	N/A	N/A	-4.9	N/A

SAMPLING TIMES

START	STOP
1000	1037

INSTRUMENT READINGS

PID(ppm)	FID (ppm)	% He Enclosure	% He Sample	Time
0.0	N/A	95.0	3.0	1000
0.0	N/A	87.0	0.20	1013
0.0	N/A	91.0	0.06	1024
0.0	N/A	76.0	0.17	1047

COMMENTS

Sampled 5 feet below grade (soil gas point, grouted at grade).
Flow Controller FC-99

URS Corporation

EPA Method TO-15

SAMPLING DATA SHEET

GENERAL INFORMATION

SITE LOCATION: SG-05-04
SITE ADDRESS: Former Columbia
Cement Facility, Freeport, NY
SAMPLING DATE: 09/21/05

SHIPPING DATE: 09/22/05
CANISTER S/N: A-293
SAMPLER ID: Peter Reynolds
OPERATOR: Peter Reynolds
CANISTER LEAK
CHECK DATE: N/A

SAMPLING INFORMATION

	INTERIOR °C	AMBIENT °C	MINIMUM °C	MAXIMUM °C	VACUUM in/Hg	VACUUM in/Hg
START	N/A	25.6	25.6	25.6	-28.8	N/A
STOP	N/A	25.6	N/A	N/A	-4.0	N/A

SAMPLING TIMES

START	STOP
0855	0929

INSTRUMENT READINGS

PID(ppm)	FID (ppm)	% He Enclosure	% He Sample	Time
0.0	N/A	94.0	0.09	0845
0.0	N/A	81.0	0.0	0916
0.0	N/A	79.0	0.0	0929

COMMENTS

Sampled 5 feet below grade (soil gas point, grouted at grade).

Flow Controller FC-70

URS Corporation

EPA Method TO-15

SAMPLING DATA SHEET

GENERAL INFORMATION

SITE LOCATION: SG-05-05
SITE ADDRESS: Former Columbia
Cement Facility, Freeport, NY
SAMPLING DATE: 09/21/05

SHIPPING DATE: 09/22/05
CANISTER S/N: A-164
SAMPLER ID: Peter Reynolds
OPERATOR: Peter Reynolds
CANISTER LEAK
CHECK DATE: N/A

SAMPLING INFORMATION

	INTERIOR °C	AMBIENT °C	MINIMUM °C	MAXIMUM °C	VACUUM in/Hg	VACUUM in/Hg
START	N/A	26.7	26.7	26.7	-24.0	N/A
STOP	N/A	26.7	N/A	N/A	-4.0	N/A

SAMPLING TIMES

START	STOP
1117	1152

INSTRUMENT READINGS

PID(ppm)	FID (ppm)	% He Enclosure	% He Sample	Time
0.0	N/A	91.0	0.10	1116
0.0	N/A	82.0	0.10	1142
0.0	N/A	79.0	0.0	1152

COMMENTS

Sampled 5 feet below grade (soil gas point, grouted at grade).

Flow Controller FC-112

URS Corporation

EPA Method TO-15

SAMPLING DATA SHEET

GENERAL INFORMATION

SITE LOCATION: SG-05-06
SITE ADDRESS: Former Columbia
Cement Facility, Freeport, NY
SAMPLING DATE: 09/21/05

SHIPPING DATE: 09/22/05
CANISTER S/N: A-316
SAMPLER ID: Peter Reynolds
OPERATOR: Peter Reynolds
CANISTER LEAK
CHECK DATE: N/A

SAMPLING INFORMATION

	INTERIOR °C	AMBIENT °C	MINIMUM °C	MAXIMUM °C	VACUUM in/Hg	VACUUM in/Hg
START	N/A	29.4	29.4	29.4	-30.0	N/A
STOP	N/A	29.4	N/A	N/A	-3.5	N/A

SAMPLING TIMES

START	STOP
1227	1305

INSTRUMENT READINGS

PID(ppm)	FID (ppm)	% He Enclosure	% He Sample	Time
0.0	N/A	90.0	0.12	1226
0.0	N/A	83.0	0.05	1253
0.0	N/A	77.0	0.04	1312

COMMENTS

Sampled 5 feet below grade (soil gas point, grouted at grade).

Flow Controller FC-61

URS Corporation

EPA Method TO-15

SAMPLING DATA SHEET

GENERAL INFORMATION

SITE LOCATION: SG-05-07
SITE ADDRESS: Former Columbia
Cement Facility, Freeport, NY
SAMPLING DATE: 09/20/05

SHIPPING DATE: 09/22/05
CANISTER S/N: A-362
SAMPLER ID: Peter Reynolds
OPERATOR: Peter Reynolds
CANISTER LEAK
CHECK DATE: N/A

SAMPLING INFORMATION

	INTERIOR °C	AMBIENT °C	MINIMUM °C	MAXIMUM °C	VACUUM in/Hg	VACUUM in/Hg
START	N/A	22.2	22.2	22.2	-27.8	N/A
STOP	N/A	22.2	N/A	N/A	-3.8	N/A

SAMPLING TIMES

START	STOP
0849	0917

INSTRUMENT READINGS

PID(ppm)	FID (ppm)	% He Enclosure	% He Sample	Time
2.0	N/A	94.0	0.22	0842
1.5	N/A	92.0	0.20	0849
0.8	N/A	87.0	0.29	0859
0.9	N/A	82.0	0.24	0921

COMMENTS

Sampled 5feet below grade (soil gas point, grouted at grade).

Flow Controller FC-93

URS Corporation

EPA Method TO-15

SAMPLING DATA SHEET

GENERAL INFORMATION

SITE LOCATION: SG-05-08
SITE ADDRESS: Former Columbia
Cement Facility, Freeport, NY
SAMPLING DATE: 09/20/05

SHIPPING DATE: 09/22/05
CANISTER S/N: A-471
SAMPLER ID: Peter Reynolds
OPERATOR: Peter Reynolds
CANISTER LEAK:
CHECK DATE: N/A

SAMPLING INFORMATION

	INTERIOR °C	AMBIENT °C	MINIMUM °C	MAXIMUM °C	VACUUM in/Hg	VACUUM in/Hg
START	N/A	22.2	22.2	22.2	-26.0	N/A
STOP	N/A	22.2	N/A	N/A	-5.0	N/A

SAMPLING TIMES

START	STOP
0958	1033

INSTRUMENT READINGS

PID(ppm)	FID (ppm)	% He Enclosure	% He Sample	Time
0.0	N/A	85.0	0.36	0957
0.0	N/A	83.0	0.42	1019
0.0	N/A	63.0	0.26	1039

COMMENTS

Sampled 5feet below grade (soil gas point, grouted at grade).

Flow Controller FC-073

URS Corporation

EPA Method TO-15

SAMPLING DATA SHEET

GENERAL INFORMATION

SITE LOCATION: SG-05-09
SITE ADDRESS: Former Columbia
Cement Facility, Freeport, NY
SAMPLING DATE: 09/20/05

SHIPPING DATE: 09/22/05
CANISTER S/N: A-171
SAMPLER ID: Peter Reynolds
OPERATOR: Peter Reynolds
CANISTER LEAK
CHECK DATE: N/A

SAMPLING INFORMATION

	INTERIOR °C	AMBIENT °C	MINIMUM °C	MAXIMUM °C	VACUUM in/Hg	VACUUM in/Hg
START	N/A	22.2	22.2	22.2	-26.8	N/A
STOP	N/A	22.2	N/A	N/A	-5.0	N/A

SAMPLING TIMES

START	STOP
1106	1140

INSTRUMENT READINGS

PID(ppm)	FID (ppm)	% He Enclosure	% He Sample	Time
0.0	N/A	93.0	0.10	1105
0.0	N/A	57.0	0.0	1115
0.0	N/A	83.0	0.16	1124
0.0	N/A	78.0	0.0	1141

COMMENTS

Sampled 5 feet below grade (soil gas point, grouted at grade).

Flow Controller FC-89

Helium recharged at 1124.

URS Corporation

EPA Method TO-15

SAMPLING DATA SHEET

GENERAL INFORMATION

SITE LOCATION: SG-05-10
SITE ADDRESS: Former Columbia
Cement Facility, Freeport, NY
SAMPLING DATE: 09/20/05

SHIPPING DATE: 09/22/05
CANISTER S/N: A-335
SAMPLER ID: Peter Reynolds
OPERATOR: Peter Reynolds
CANISTER LEAK
CHECK DATE: N/A

SAMPLING INFORMATION

	INTERIOR °C	AMBIENT °C	MINIMUM °C	MAXIMUM °C	VACUUM in/Hg	VACUUM in/Hg
START	N/A	26.7	26.7	26.7	-30.0	N/A
STOP	N/A	26.7	N/A	N/A	-4.8	N/A

SAMPLING TIMES

START	STOP
1303	1341

INSTRUMENT READINGS

PID(ppm)	FID (ppm)	% He Enclosure	% He Sample	Time
0.4	N/A	90.0	0.76	1257
0.4	N/A	87.0	0.0	1305
0.0	N/A	79.0	0.10	1322
0.0	N/A	65.0	0.0	1344

COMMENTS

Sampled 5 feet below grade (soil gas point, grouted at grade).

Flow Controller FC-107

URS Corporation

EPA Method TO-15

SAMPLING DATA SHEET

GENERAL INFORMATION

SITE LOCATION: SG-05-11
SITE ADDRESS: Former Columbia
Cement Facility, Freeport, NY
SAMPLING DATE: 09/21/05

SHIPPING DATE: 09/22/05
CANISTER S/N: A-369
SAMPLER ID: Peter Reynolds
OPERATOR: Peter Reynolds
CANISTER LEAK
CHECK DATE: N/A

SAMPLING INFORMATION

	INTERIOR °C	AMBIENT °C	MINIMUM °C	MAXIMUM °C	VACUUM in/Hg	VACUUM in/Hg
START	N/A	25.6	25.6	25.6	N/A	N/A
STOP	N/A	25.6	N/A	N/A	N/A	N/A

SAMPLING TIMES

START	STOP
0936	1009

INSTRUMENT READINGS

PID(ppm)	FID (ppm)	% He Enclosure	% He Sample	Time
0.0	N/A	94.0	0.15	0929
0.0	N/A	88.0	0.03	0935
0.0	N/A	82.0	0.0	0945
0.0	N/A	79.0	0.0	1007

COMMENTS

Sampled 5 feet below grade (soil gas point, grouted at grade).

URS Corporation

EPA Method TO-15

SAMPLING DATA SHEET

GENERAL INFORMATION

SITE LOCATION: SG-05-AMB-E

SITE ADDRESS: Former Columbia
Cement Facility, Freeport, NY

SAMPLING DATE: 09/20/05

SHIPPING DATE: 09/22/05

CANISTER S/N: A441

SAMPLER ID: Peter Reynolds

OPERATOR: Peter Reynolds

CANISTER LEAK

CHECK DATE: N/A

SAMPLING INFORMATION

	INTERIOR °C	AMBIENT °C	MINIMUM °C	MAXIMUM °C	VACUUM in/Hg	VACUUM in/Hg
START	N/A	27.8	27.8	27.8	-30.0	N/A
STOP	N/A	27.8	N/A	N/A	-4.8	N/A

SAMPLING TIMES

START	STOP
1318	1356

INSTRUMENT READINGS

PID(ppm)	FID (ppm)	% He Enclosure	% He Sample	Time
0.0	N/A	N/A	N/A	1318
0.0	N/A	N/A	N/A	1333
0.0	N/A	N/A	N/A	1356

COMMENTS

Sampled along the eastern side of the site building.

Flow Controller FC-178

URS Corporation

EPA Method TO-15

SAMPLING DATA SHEET

GENERAL INFORMATION

SITE LOCATION: SG-05-AMB-W
SITE ADDRESS: Former Columbia
Cement Facility, Freeport, NY
SAMPLING DATE: 09/20/05

SHIPPING DATE: 09/22/05
CANISTER S/N: A-217
SAMPLER ID: Peter Reynolds
OPERATOR: Peter Reynolds
CANISTER LEAK
CHECK DATE: N/A

SAMPLING INFORMATION

	INTERIOR °C	AMBIENT °C	MINIMUM °C	MAXIMUM °C	VACUUM in/Hg	VACUUM in/Hg
START	N/A	23.9	23.9	23.9	-28.5	N/A
STOP	N/A	23.9	N/A	N/A	-5.0	N/A

SAMPLING TIMES

START	STOP
0939	1012

INSTRUMENT READINGS

PID(ppm)	FID (ppm)	% He Enclosure	% He Sample	Time
0.0	N/A	N/A	N/A	0941
0.0	N/A	N/A	N/A	0959
0.0	N/A	N/A	N/A	1005
0.0	N/A	N/A	N/A	1012

COMMENTS

Sampled west of the site building.

Flow Controller FC-90

2006 SOIL GAS SAMPLING LOGS

URS Corporation

EPA Method TO-15

SAMPLING DATA SHEET

GENERAL INFORMATION

SITE LOCATION: SG-05-01
SITE ADDRESS: Former Columbia
Cement Facility, Freeport, NY
SAMPLING DATE: 8/15/06

SHIPPING DATE: 8/17/06
CANISTER S/N: A670/6521
SAMPLE ID: SG-05-01
OPERATOR: Peter Reynolds
CANISTER LEAK
CHECK DATE: 8/15/06
-28 in Hg

SAMPLING INFORMATION

	INTERIOR °C	AMBIENT °C	MINIMUM °C	MAXIMUM °C	VACUUM in/Hg	VACUUM in/Hg
START	N/A	24	N/A	N/A	-28	N/A
STOP	N/A	24	N/A	N/A	-5	N/A

SAMPLING TIMES

START	STOP
1254	1324

INSTRUMENT READINGS

PID(ppm)	FID (ppm)	% He Enclosure	% He Sample	Time
0.0	N/A	81.2	< 1%	1252
0.0	N/A	65.4	< 1%	1312
0.0	N/A	94.5	10.2%	1328

COMMENTS

Sampled 5 feet below grade (soil gas point, grouted at grade).

Flow Controller FC-247

URS Corporation

EPA Method TO-15

SAMPLING DATA SHEET

GENERAL INFORMATION

SITE LOCATION: SG-05-04
SITE ADDRESS: Former Columbia
Cement Facility, Freeport, NY
SAMPLING DATE: 08/15/06

SHIPPING DATE: 08/17/06
CANISTER S/N: A-21/4240
SAMPLE ID: SG-05-04
OPERATOR: Peter Reynolds
CANISTER LEAK
CHECK DATE: 08/15/06
-30 in Hg

SAMPLING INFORMATION

	INTERIOR °C	AMBIENT °C	MINIMUM °C	MAXIMUM °C	VACUUM in/Hg	VACUUM in/Hg
START	N/A	26.7	N/A	N/A	-30	N/A
STOP	N/A	26.7	N/A	N/A	-5	N/A

SAMPLING TIMES

START	STOP
1358	1436

INSTRUMENT READINGS

PID(ppm)	FID (ppm)	% He Enclosure	% He Sample	Time
0.0	N/A	89.8	3.8%	1344
0.0	N/A	73.9	< 1%	1414
0.0	N/A	60.1	< 1%	1438

COMMENTS

Sampled 5 feet below grade (soil gas point, grouted at grade).
Flow Controller FC-246

URS Corporation

EPA Method TO-15

SAMPLING DATA SHEET

GENERAL INFORMATION

SITE LOCATION: SG-05-05
SITE ADDRESS: Former Columbia
Cement Facility, Freeport, NY
SAMPLING DATE: 89/15/06

SHIPPING DATE: 08/17/06
CANISTER S/N: A-457/24152/1428
SAMPLE ID: SG-05-05
OPERATOR: Peter Reynolds
CANISTER LEAK
CHECK DATE: 8/15/06
-27 in Hg

SAMPLING INFORMATION

	INTERIOR °C	AMBIENT °C	MINIMUM °C	MAXIMUM °C	VACUUM in/Hg	VACUUM in/Hg
START	N/A	29.4	N/A	N/A	-27	N/A
STOP	N/A	29.4	N/A	N/A	-5	N/A

SAMPLING TIMES

START	STOP
1519	1546

INSTRUMENT READINGS

PID(ppm)	FID (ppm)	% He Enclosure	% He Sample	Time
0.0	N/A	88.7	< 1%	1502
0.0	N/A	55.8	< 1%	1549

COMMENTS

Sampled 5 feet below grade (soil gas point, grouted at grade).
Flow Controller FC-255

URS Corporation

EPA Method TO-15

SAMPLING DATA SHEET

GENERAL INFORMATION

SITE LOCATION: SG-05-08
SITE ADDRESS: Former Columbia
Cement Facility, Freeport, NY
SAMPLING DATE: 08/15/06

SHIPPING DATE: 08/17/06
CANISTER S/N: A-166/6905
SAMPLE ID: SG-05-08
OPERATOR: Peter Reynolds
CANISTER LEAK
CHECK DATE: 08/15/06
-29 in Hg

SAMPLING INFORMATION

	INTERIOR °C	AMBIENT °C	MINIMUM °C	MAXIMUM °C	VACUUM in/Hg	VACUUM in/Hg
START	N/A	24	N/A	N/A	-28	N/A
STOP	N/A	24	N/A	N/A	-4	N/A

SAMPLING TIMES

START	STOP
1033	1104

INSTRUMENT READINGS

PID(ppm)	FID (ppm)	% He Enclosure	% He Sample	Time
0.0	N/A	77.3	4	1025
0.0	N/A	66.8	3.8	1030
0.0	N/A	84.1	4.9	1110

COMMENTS

Sampled 5feet below grade (soil gas point, grouted at grade).

Flow Controller FC-070

Heavy traffic in area: diesel trucks in the area.

County Carting next door.

URS Corporation

EPA Method TO-15

SAMPLING DATA SHEET

GENERAL INFORMATION

SITE LOCATION: SG-05-10
SITE ADDRESS: Former Columbia
Cement Facility, Freeport, NY
SAMPLING DATE: 08/15/06

SHIPPING DATE: 08/17/06
CANISTER S/N: A-364/5685
SAMPLE ID: SG-05-10
OPERATOR: Peter Reynolds
CANISTER LEAK
CHECK DATE: 08/15/06
-29 in Hg

SAMPLING INFORMATION

	INTERIOR °C	AMBIENT °C	MINIMUM °C	MAXIMUM °C	VACUUM in/Hg	VACUUM in/Hg
START	N/A	29.4	N/A	N/A	-29.5	N/A
STOP	N/A	29.4	N/A	N/A	-4.0	N/A

SAMPLING TIMES

START	STOP
1453	1528

INSTRUMENT READINGS

PID(ppm)	FID (ppm)	% He Enclosure	% He Sample	Time
0.0	N/A	82.04	< 1%	1450
0.0	N/A	73.2	< 1%	1520
0.0	N/A	49.5	< 1%	1528

COMMENTS

Sampled 5 feet below grade (soil gas point, grouted at grade).

Flow Controller FC-285

URS Corporation

EPA Method TO-15

SAMPLING DATA SHEET

GENERAL INFORMATION

SITE LOCATION: SG-05-11
SITE ADDRESS: Former Columbia
Cement Facility, Freeport, NY
SAMPLING DATE: 08/15/06

SHIPPING DATE: 08/17/06/05
CANISTER S/N: A-441/24182/1418
SAMPLE ID: SG-05-11
OPERATOR: Peter Reynolds
CANISTER LEAK
CHECK DATE: 08/15/06
-29 in Hg

SAMPLING INFORMATION

	INTERIOR °C	AMBIENT °C	MINIMUM °C	MAXIMUM °C	VACUUM in/Hg	VACUUM in/Hg
START	N/A	23.9	N/A	N/A	-28	N/A
STOP	N/A	23.9	N/A	N/A	-5	N/A

SAMPLING TIMES

START	STOP
1151	1224

INSTRUMENT READINGS

PID(ppm)	FID (ppm)	% He Enclosure	% He Sample	Time
0.0	N/A	78.7	< 1%	1146
0.0	N/A	62.5	< 1%	1205
0.0	N/A	80.9	< 1%	1226

COMMENTS

Sampled 5 feet below grade (soil gas point, grouted at grade).

Flow Controller # FC-070

URS Corporation

EPA Method TO-15

SAMPLING DATA SHEET

GENERAL INFORMATION

SITE LOCATION: SS-06-01
SITE ADDRESS: Former Columbia
Cement Facility, Freeport, NY
SAMPLING DATE: 08/16/06

SHIPPING DATE: 08/17/06
CANISTER S/N: A479/1403
SAMPLE ID: SS-06-01
OPERATOR: Peter Reynolds
CANISTER LEAK
CHECK DATE: 08/16/06
-30 in Hg

SAMPLING INFORMATION

	INTERIOR °C	AMBIENT °C	MINIMUM °C	MAXIMUM °C	VACUUM in/Hg	VACUUM in/Hg
START	26.7	29.4	N/A	N/A	-28.0	N/A
STOP	26.7	29.4	N/A	N/A	-5.0	N/A

SAMPLING TIMES

START	STOP
1634	1706

INSTRUMENT READINGS

PID(ppm)	FID (ppm)	% He Enclosure	% He Sample	Time
		94.7%	6.1%	1630
		64.5%	1.5%	1708

COMMENTS

Sampled ~ 1 foot below grade inside Site building. Expendable point.

Point removed and grouted after sampling.

Flow Controller FC-281.

URS Corporation

EPA Method TO-15

SAMPLING DATA SHEET

GENERAL INFORMATION

SITE LOCATION: SS-06-02
SITE ADDRESS: Former Columbia
Cement Facility, Freeport, NY
SAMPLING DATE: 08/16/06

SHIPPING DATE: 08/17/06
CANISTER S/N: A341/5222
SAMPLE ID: SS-06-02
OPERATOR: Peter Reynolds
CANISTER LEAK
CHECK DATE: 08/16/06
-30 in Hg

SAMPLING INFORMATION

	INTERIOR °C	AMBIENT °C	MINIMUM °C	MAXIMUM °C	VACUUM in/Hg	VACUUM in/Hg
START	26.7	29.4	N/A	N/A	-30.0	N/A
STOP	26.7	29.4	N/A	N/A	-4.0	N/A

SAMPLING TIMES

START	STOP
1443	1518

INSTRUMENT READINGS

PID(ppm)	FID (ppm)	% He Enclosure	% He Sample	Time
		92.6%	11.0%	1440
		90.7%	7.1%	1520

COMMENTS

Sampled ~ 1 foot below grade inside Site building. Expendable point.

Point removed and grouted after sampling.

Flow Controller FC-253.

URS Corporation

EPA Method TO-15

SAMPLING DATA SHEET

GENERAL INFORMATION

SITE LOCATION: SS-06-03
SITE ADDRESS: Former Columbia
Cement Facility, Freeport, NY
SAMPLING DATE: 08/16/06

SHIPPING DATE: 08/17/06
CANISTER S/N: A376/5699
SAMPLE ID: SS-06-03
OPERATOR: Peter Reynolds
CANISTER LEAK
CHECK DATE: 08/16/06
-30 in Hg

SAMPLING INFORMATION

	INTERIOR °C	AMBIENT °C	MINIMUM °C	MAXIMUM °C	VACUUM in/Hg	VACUUM in/Hg
START	26.7	29.4	N/A	N/A	-30.0	N/A
STOP	26.7	29.4	N/A	N/A	-4.0	N/A

SAMPLING TIMES

START	STOP
1305	1337

INSTRUMENT READINGS

PID(ppm)	FID (ppm)	% He Enclosure	% He Sample	Time
		92.6%	9.1%	1250
		92.1%	4.1%	1339

COMMENTS

Sampled ~ 1 foot below grade inside Site building. Expendable point.

Point removed and grouted after sampling.

Flow Controller FC-263.

URS Corporation

EPA Method TO-15

SAMPLING DATA SHEET

GENERAL INFORMATION

SITE LOCATION: SS-06-04

SITE ADDRESS: Former Columbia
Cement Facility, Freeport, NY

SAMPLING DATE: 08/16/06

SHIPPING DATE: 08/17/06

CANISTER S/N: A133/4234

SAMPLE ID: SS-06-04

OPERATOR: Peter Reynolds

CANISTER LEAK

CHECK DATE: 08/16/06

-30 in Hg

SAMPLING INFORMATION

	INTERIOR °C	AMBIENT °C	MINIMUM °C	MAXIMUM °C	VACUUM in/Hg	VACUUM in/Hg
START	26.7	29.4	N/A	N/A	-30.0	N/A
STOP	26.7	29.4	N/A	N/A	-4.0	N/A

SAMPLING TIMES

START	STOP
1543	1616

INSTRUMENT READINGS

PID(ppm)	FID (ppm)	% He Enclosure	% He Sample	Time
		89.3%	< 1%	1540
		72.7%	< 1%	1618

COMMENTS

Sampled ~ 1 foot below grade inside Knickerbock Site building. Expendable point.

Point removed and grouted after sampling.

Flow Controller FC-266.

URS Corporation

EPA Method TO-15

SAMPLING DATA SHEET

GENERAL INFORMATION

SITE LOCATION: IA-06-01
SITE ADDRESS: Former Columbia
Cement Facility, Freeport, NY
SAMPLING DATE: 08/16/06

SHIPPING DATE: 08/17/06
CANISTER S/N: A370/5706
SAMPLE ID: IA-06-01
OPERATOR: Peter Reynolds
CANISTER LEAK
CHECK DATE: 08/16/06
-30 in Hg

SAMPLING INFORMATION

	INTERIOR °C	AMBIENT °C	MINIMUM °C	MAXIMUM °C	VACUUM in/Hg	VACUUM in/Hg
START	26.7	29.4	N/A	N/A	-30.0	N/A
STOP	26.7	29.4	N/A	N/A	-4.0	N/A

SAMPLING TIMES

START	STOP
1305	1339

INSTRUMENT READINGS

PID(ppm)	FID (ppm)	% He Enclosure	% He Sample	Time

COMMENTS

Sampled ~ 4 feet above grade in the Site building.

Flow Controller FC-087

URS Corporation

EPA Method TO-15

SAMPLING DATA SHEET

GENERAL INFORMATION

SITE LOCATION: IA-06-02
SITE ADDRESS: Former Columbia
Cement Facility, Freeport, NY
SAMPLING DATE: 08/16/06

SHIPPING DATE: 08/17/06
CANISTER S/N: A370/5706
SAMPLE ID: IA-06-02
OPERATOR: Peter Reynolds
CANISTER LEAK
CHECK DATE: 08/16/06
-27 in Hg

SAMPLING INFORMATION

	INTERIOR °C	AMBIENT °C	MINIMUM °C	MAXIMUM °C	VACUUM in/Hg	VACUUM in/Hg
START	26.7	29.4	N/A	N/A	-27	N/A
STOP	26.7	29.4	N/A	N/A	-4.0	N/A

SAMPLING TIMES

START	STOP
1450	1521

INSTRUMENT READINGS

PID(ppm)	FID (ppm)	% He Enclosure	% He Sample	Time

COMMENTS

Sampled ~ 4 feet above grade in the Site building.

Flow Controller FC-050.

URS Corporation

EPA Method TO-15

SAMPLING DATA SHEET

GENERAL INFORMATION

SITE LOCATION: IA-06-03

SHIPPING DATE: 08/17/06

SITE ADDRESS: Former Columbia
Cement Facility, Freeport, NY

CANISTER S/N: A313/5201

SAMPLING DATE: 08/16/06

SAMPLE ID: IA-06-03

OPERATOR: Peter Reynolds

CANISTER LEAK

CHECK DATE: 08/16/06

-29 in Hg

SAMPLING INFORMATION

	INTERIOR °C	AMBIENT °C	MINIMUM °C	MAXIMUM °C	VACUUM in/Hg	VACUUM in/Hg
START	26.7	29.4	N/A	N/A	-30.0	N/A
STOP	26.7	29.4	N/A	N/A	-4.0	N/A

SAMPLING TIMES

START	STOP
1621	1650

INSTRUMENT READINGS

PID(ppm)	FID (ppm)	% He Enclosure	% He Sample	Time

COMMENTS

Sampled ~ 4 feet above grade in the Knickerbocker Building.

Flow Controller FC-181.

URS Corporation

EPA Method TO-15

SAMPLING DATA SHEET

GENERAL INFORMATION

SITE LOCATION: AA-06-01
SITE ADDRESS: Former Columbia
Cement Facility, Freeport, NY
SAMPLING DATE: 08/16/06

SHIPPING DATE: 08/17/06
CANISTER S/N: A313/5201
SAMPLE ID: AA-06-01
OPERATOR: Peter Reynolds
CANISTER LEAK
CHECK DATE: 08/16/06
-29 in Hg

SAMPLING INFORMATION

	INTERIOR °C	AMBIENT °C	MINIMUM °C	MAXIMUM °C	VACUUM in/Hg	VACUUM in/Hg
START	26.7	29.4	N/A	N/A	-29.0	N/A
STOP	26.7	29.4	N/A	N/A	-4.0	N/A

SAMPLING TIMES

START	STOP
1337	1411

INSTRUMENT READINGS

PID(ppm)	FID (ppm)	% He Enclosure	% He Sample	Time

COMMENTS

Sampled ~ 4 feet above grade outside Site building near former tank farm..
Flow Controller FC-310.

URS Corporation

EPA Method TO-15

SAMPLING DATA SHEET

GENERAL INFORMATION

SITE LOCATION: SS-06-05 (1)
SITE ADDRESS: Former Columbia
Cement Facility, Freeport, NY
SAMPLING DATE: 10/05/06

SHIPPING DATE: 10/06/06
CANISTER S/N: A564/24180/1269
SAMPLE ID: SS-06-05 (1)
OPERATOR: Nicole Reese
CANISTER LEAK
CHECK DATE: 10/05/05
-29 in Hg

SAMPLING INFORMATION

	INTERIOR °C	AMBIENT °C	MINIMUM °C	MAXIMUM °C	VACUUM in/Hg	VACUUM in/Hg
START	26.7	29.4	N/A	N/A	-29.0	N/A
STOP	26.7	29.4	N/A	N/A	-4.0	N/A

SAMPLING TIMES

START	STOP
1021	1026

INSTRUMENT READINGS

PID(ppm)	FID (ppm)	% He Enclosure	% He Sample	Time
N/A	N/A	N/A	N/A	N/A

COMMENTS

Sampled ~ 1 foot below grade outside Site building near R&H property line.

Expendable point. Point removed and grouted after sampling.

Flow Controller FC-233.

URS Corporation

EPA Method TO-15

SAMPLING DATA SHEET

GENERAL INFORMATION

SITE LOCATION: SS-06-05 (6)
SITE ADDRESS: Former Columbia
Cement Facility, Freeport, NY
SAMPLING DATE: 10/05/06

SHIPPING DATE: 10/06/06
CANISTER S/N: A3254/555656/5323

SAMPLE ID: SS-06-05 (6)
OPERATOR: Peter Reynolds

CANISTER LEAK

CHECK DATE: 10/06/05 (6)
-30 in Hg

SAMPLING INFORMATION

	INTERIOR °C	AMBIENT °C	MINIMUM °C	MAXIMUM °C	VACUUM in/Hg	VACUUM in/Hg
START	26.7	29.4	N/A	N/A	-30.0	N/A
STOP	26.7	29.4	N/A	N/A	-4.0	N/A

SAMPLING TIMES

START	STOP
1214	1254

INSTRUMENT READINGS

PID(ppm)	FID (ppm)	% He Enclosure	% He Sample	Time
		90.0%	< 1%	1212
		85.2%	< 1%	1226
		88.9	< 1%	1257

COMMENTS

Sampled ~ 1 foot below grade outside Site building near R&H property line.

Expendable point. Point removed and grouted after sampling.

Flow Controller FC-105.

URS Corporation

EPA Method TO-15

SAMPLING DATA SHEET

GENERAL INFORMATION

SITE LOCATION: AA-06-05 (1)
SITE ADDRESS: Former Columbia
Cement Facility, Freeport, NY
SAMPLING DATE: 10/05/06

SHIPPING DATE: 10/06/06
CANISTER S/N: A564/24180/1269
SAMPLE ID: SS-06-05 (1)
OPERATOR: Peter Reynolds
CANISTER LEAK
CHECK DATE: 10/05/05
-30 in Hg

SAMPLING INFORMATION

	INTERIOR °C	AMBIENT °C	MINIMUM °C	MAXIMUM °C	VACUUM in/Hg	VACUUM in/Hg
START	26.7	29.4	N/A	N/A	-29.0	N/A
STOP	26.7	29.4	N/A	N/A	-4.0	N/A

SAMPLING TIMES

START	STOP
1021	1026

INSTRUMENT READINGS

PID(ppm)	FID (ppm)	% He Enclosure	% He Sample	Time
N/A	N/A	N/A	N/A	N/A

COMMENTS

Sampled ~ 4 feet above grade outside Site building near R&H property line.

Flow Controller FC-233.

URS Corporation

EPA Method TO-15

SAMPLING DATA SHEET

GENERAL INFORMATION

SITE LOCATION: AA-06-05 (6)
SITE ADDRESS: Former Columbia
Cement Facility, Freeport, NY
SAMPLING DATE: 10/05/06

SHIPPING DATE: 10/06/06
CANISTER S/N: A2900/555656/5534

SAMPLE ID: AA-06-05 (6)
OPERATOR: Nicole Reese

CANISTER LEAK

CHECK DATE: 10/05/05
-30 in Hg

SAMPLING INFORMATION

	INTERIOR °C	AMBIENT °C	MINIMUM °C	MAXIMUM °C	VACUUM in/Hg	VACUUM in/Hg
START	26.7	29.4	N/A	N/A	-30.0	N/A
STOP	26.7	29.4	N/A	N/A	-4.0	N/A

SAMPLING TIMES

START	STOP
1206	1241

INSTRUMENT READINGS

PID(ppm)	FID (ppm)	% He Enclosure	% He Sample	Time
N/A	N/A	N/A	N/A	N/A

COMMENTS

Ambient air sample ~ 4 feet above grade outside Site building near R&H property line.

Flow Controller T28.

APPENDIX G

**BENCH SCALE TREATABILITY STUDY
TESTING REPORTS**



ADVENTUS
AMERICAS

**EHC AND HRC FEASIBILITY STUDY FOR THE TREATMENT OF CHLORINATED
SOLVENTS IN GROUNDWATER FROM THE FORMER COLUMBIA CEMENT INC.
FACILITY, FREEPORT, NY (THE SITE): BENCH SCALE TREATABILITY
INVESTIGATION**

FINAL REPORT

Prepared for:

**URS Corp.
12 Commerce Drive
Cranford, NJ 07016**

Submitted by:
**ADVENTUS AMERICAS
ADVENTUS Project No.: AAI5-032**

October 21, 2005

EXECUTIVE SUMMARY

A bench-scale treatability was completed at Adventus Remediation Technologies' facility in Mississauga, Ontario, for the treatment of groundwater impacted with chlorinated volatile organic compounds from the former Columbia Cement, Inc. facility in Freeport, NY (the Site). The purpose of the project was to determine the capability of EHC and HRC to treat chloroethane (1,500 ug/L), the primary contaminant in groundwater.

A review of the scientific literature indicated that degradation of chloroethane could occur both via biotic as well as abiotic pathways under reducing conditions. HRC supports biological degradation while EHC supports both biological and chemical reduction.

A set of six flow-through column systems was set up, which included two control columns, two EHC columns and two HRC columns. Two application rates (0.1% and 0.5%) of EHC and HRC were tested. The effectiveness of these treatment systems was assessed using data collected in six sampling events over a period of 107 days.

Overall the treatment systems have demonstrated some reduction in chloroethane over time. However, during the initial three sampling events, it was difficult to assess the effectiveness of the treatments due to the decrease in chloroethane concentrations in the feed and control systems. Both systems showed a significant lag time of between 42 and 71 days, before degradation of chloroethane was truly observed.

Only one of the six sampling events indicated that there was an added benefit of using enhancements such as EHC and HRC to degrade chloroethane. Significant removal was observed in the non-sterile and sterile control columns indicating that the added enhancements did not significantly improve the biotic removal of chloroethane. Removal of chloroethane was primarily from combined abiotic methods and biotic methods without the enhancements. This indicates that chloroethane has a potential to attenuate naturally.

The experiments were conducted at a pore volume flush rate three times the rate observed in the field. Within the limited enhancement that was observed, the data shows that in the short term, HRC performed better than EHC. However, it is likely that the slow release feature of EHC coupled with zero valent iron would perform better in the long run. The study concludes that it is not feasible to enhance the reductive dechlorination of chloroethane in groundwater at the Site.

TABLE OF CONTENTS

1.0 INTRODUCTION	1
1.1. Project Background	1
1.2. EHC and HRC Technology Background	1
2.0 PROJECT OBJECTIVES AND METHODS	2
1.3. Project Objectives.....	2
1.4. Initial Groundwater and Soil Characterization.....	2
2.3 Column Test Set Up	3
3.0 COLUMN RESULTS	6
3.1 pH and ORP Data.....	6
3.2 First Sampling Event (Day 14).....	6
3.3 Second Sampling Event (Day 29).....	7
3.4 Third Sampling Event (Day 42).....	8
3.5 Fourth Sampling Event (Day 71)	10
3.6 Additional Sampling Event #1 (Day 94).....	11
3.7 Additional Sampling Event #2 (Day 107)	12
4.0 CONCLUSIONS	13

APPENDICIES

Appendix A – Methodology for Headspace SPME GC/ECD determination of VOCs in water samples

Appendix B – Summary of pH and Oxidation Reduction Potentials Readings

Appendix C – Analytical Data

1.0 INTRODUCTION

1.1. Project Background

This report was prepared for URS Corp. to determine the ability of EHC and HRC to treat the COI present in groundwater at the former Columbia Cement Inc. facility in Freeport, New York (Site). This report presents the results and interpretation of data collected from a bench-scale feasibility study completed between April 2005 and September 2005 at Adventus Remediation Technologies' facility in Mississauga, Ontario.

1.2. EHC and HRC Technology Background

EHC is a patented combination of controlled-release solid carbon and zero-valent iron (ZVI) to stimulate reductive dechlorination of persistent organic solvents in groundwater and source zones. The organic component of EHC (fibrous organic material) is nutrient rich, hydrophilic, and has high surface area; thus, it is an ideal support for growth of bacteria in the groundwater environment. As they grow on EHC particle surfaces, indigenous heterotrophic bacteria consume dissolved oxygen and thereby reduce the redox potential in groundwater. In addition, as the bacteria grow on the organic particles they ferment the carbon and release volatile fatty acids (VFAs) such as acetic, propionic, butyric, and lactic acids, which diffuse from the site of fermentation into the groundwater plume and serve as electron donors for other bacteria including dehalogenators and halorespiring species. Finally, the small ZVI particles provide substantial reactive surface area that stimulates direct chemical dechlorination and an additional drop in the redox potential of the groundwater. These physical, chemical, and biological processes combine to create an environment that stimulates chemical and microbiological dechlorination of solvents.

On the other hand, HRC is an ester of polylactic acid, which slowly releases lactic acid and other VFAs in groundwater. The VFAs serve as electron donor and promote the reductive dechlorination of chlorinated solvents.

Groundwater at the Site is predominantly contaminated with CA (CA), which is a degradation product of 1,1,1-TCA, a compound that was released at the Site. A review of the scientific literature indicated that degradation of CA could occur both via biotic as well as abiotic pathways. HRC supports biological degradation while EHC supports both biological and chemical reduction.

2.0 PROJECT OBJECTIVES AND METHODS

1.3. Project Objectives

The aim of this bench-scale feasibility study was to determine the ability of EHC and HRC to treat chlorinated volatile organic compounds in impacted groundwater collected at the Site. Specific objectives included:

- chemical characterization of the groundwater and soil samples;
- evaluation of the performance of EHC and HRC applied at two application rates;
- identification of the most effective product and determination of its optimal application rate for full-scale treatment;
- providing a comprehensive final report, including recommendations for potential full-scale implementation.

1.4. Initial Groundwater and Soil Characterization

On April 27, 2005 Adventus received one five-gallon pail of groundwater (MW-05-15D) and one five-gallon pail of soil (MW-98-9D) from the Site. Both pails were placed into cold room storage upon receipt.

On April 28, 2005 a sample of the groundwater was submitted for volatile organic compounds (VOC), total organic carbon (TOC), chloride, alkalinity, pH, nitrate, sulfate, total iron, and dissolved iron analyses. The soil was homogenized by hand and samples were collected for VOC, TOC, chloride, alkalinity, pH, nitrate, sulfate, and total iron analyses. All samples were shipped via overnight courier to Severn Trent Laboratories (STL) – Chicago for analysis.

The initial groundwater and soil characterization results are presented in **Tables 1 and 2**. The main VOC present in the groundwater was CA (730 ug/L) and a trace amount of chlorobenzene (CB) was also detected at 4 ug/L. Analysis of the Site soil revealed a low concentration of m&p-Xylene (12 ug/kg). All other VOCs were below the analytical detection limit (i.e., non-detect). This indicates that the soil itself is not from a highly contaminated area or that losses have occurred during the collection and/or shipment of the samples.

The TOC concentration was much greater in the soil (9,300 mg/kg) than in the groundwater sample (8 mg/L).

Table 1: Initial VOC and TOC results in the Site soil and groundwater samples

Parameter	Soil	Units	Water	Units
Chloroethane	ND (6.1)	ug/kg	730	ug/L
Chlorobenzene	ND (6.1)	ug/kg	4	ug/L
m&p-Xylene	12	ug/kg	ND (2)	ug/L
Total VOCs	12	ug/kg	734	ug/L
TOC	9,300	mg/kg	8	mg/L

ND = non detect (detection limit)

The inorganic constituents are summarized in Table 2. The Site soil and groundwater were both neutral and had pH values of 6.9 and 6.3, respectively. The inorganic chemistry of the groundwater was dominated by chloride (75 mg/L) and trace amounts of sulfate (0.29 mg/L), total iron (8 mg/L) and dissolved iron (0.065 mg/L) were detected. The carbonate alkalinity was 380 mg/L in the groundwater and was below the detection limit in the soil. The inorganic chemistry of the soil was dominated by total iron (9,700 mg/kg) and lower concentrations of chloride (3.3 mg/kg) and sulfate (3 mg/kg) were also detected.

Table 2: Inorganic constituents in the Site soil and groundwater samples

Parameter	Soil	Units	Water	Units
Chloride	3.3	mg/kg	75	mg/L
Total Alkalinity (as CaCO ₃)	ND (500)	mg/kg	380	mg/L
pH	6.9	pH units	6.3	pH units
Nitrate-N	ND (1.2)	mg/kg	ND (0.1)	mg/L
Sulfate	3	mg/kg	0.29	mg/L
Total Iron	9,700	mg/kg	8	mg/L
Total Dissolved Iron	NA	---	0.065	mg/L

ND = non detect (detection limit)


NA = not applicable

2.3 Column Test Set Up

On June 21, 2005, six column systems were set up with Plexiglas columns (Table 3, Photographs 1A and 1B). Two of the columns were amended with EHC, two columns received HRC and the remaining two were control columns. The EHC columns were filled with a 0.1% and 0.5% (by mass) mixtures of EHC with Site soil. The same application rates were tested for the HRC columns. The first control column was filled with Site soil "as received" and the second control column was filled with Site soil that was autoclaved at 250°F for 20 minutes. One gram of mercuric chloride, a microbial inhibitor, was also added to the autoclaved soil.

Table 3: Summary of the Column Testing

System #	Description	Application Rate (%)
1	EHC2007Fe50	0.1
2	EHC2007Fe50	0.5
3	HRC	0.1
4	HRC	0.5
5	Control	0
6	Sterile Control	0



Photograph 1A and 1B. Laboratory set up of the EHC columns. Each system consists of a column (A) followed by Tedlar bag to collect the effluent (B). Columns 1 – 6 (Left to Right).

The concentrations of CA and CB in the Site groundwater sample were below the typical Site concentrations and thus the feed water was spiked with these two constituents of interest. A separate feed was prepared for the sterile control column as described above except mercuric chloride was also added to the feed bag. Spiked groundwater was continuously being pumped into the bottom of each column. The effluent line from each column was connected to a separate Tedlar bag, which collected the effluent from the column over time. Initially, the feed flow rate was set at 150 mL/day to fill the columns and then was reduced to 70 mL/day. This corresponded to a pore volume flush rate that was three times that calculated from field observations/measurements. This was the

slowest flow rate that could be tested to collect sufficient water for analysis at each sampling event.

Oxidation-reduction potential (ORP) and pH were initially monitored daily and then weekly. On July 11th (Day 14), July 26th (Day 29), August 8th (Day 42) September 6th (Day 71), 2005 influent and effluent samples were collected from each system. The influents were sampled for VOC and the column effluents were sampled for VOC, ethane, alkalinity, chloride, and TOC analyses. All samples from the first four sampling events were submitted to Severn Trent Laboratories.

Two additional sampling events were completed on September 29th (Day 94) and October 12th (Day 107). During the final two sampling events, effluent samples were collected directly from the column and were analyzed by Adventus using the solid phase microextraction (SPME) method (Appendix A).

3.0 COLUMN RESULTS

3.1 pH and ORP Data

The pH and ORP data is presented in Appendix B. The Site groundwater pH ranged between 6.5 and 7.3. The pH values of the control column effluents were similar to the feed and ranged between 6.5 and 7.0. The effluents from both the EHC and HRC treatment columns initially showed a decrease in the pH and then the pH increased into the neutral range with time. The pH of the EHC columns ranged between 5.8 and 7.1, while the pH of the HRC columns ranged between 5.0 and 6.9.

During the initial 30 days of the study the EHC columns produced the best reductive conditions. After day 30, the EHC, HRC, and control columns all showed slightly positive ORP values. The last reading showed that the treatment columns, control columns, and feeds all had negative ORP values. Neither, EHC or HRC were not able to sustain low ORP levels (-150 mV or less) considered optimum to support reductive dechlorination until Day 107.

3.2 First Sampling Event (Day 14)

Appendix C shows all the analytical data collected during this study. Table 4 shows the data for Day 14 sampling event. On Day 14, the CA concentrations in the two feeds were found to be below the targeted concentrations of 1,500 ug/L and 20 ug/L for CA and CB, respectively.

Table 4: Influence of EHC and HRC on VOC concentrations after 14 days

Parameter	Concentration (ug/L)							
	0.1% EHC	0.5% EHC	0.1% HRC	0.5% HRC	Control	Sterile Control	Feed	Sterile Feed
CA	490	500	510	430	540	480	800	720
CB	2.3	3.7	2.3	9.5	7.4	16	7	10

ND = non detect (detection limit)

Both controls showed reductions in the CA concentration when compared to their respective feeds. The sterile control system showed 33% reduction in CA while the non-sterile control showed 32.5% reduction in CA. This indicates that some abiotic removal as well as removal by indigenous microorganisms was occurring in both columns.

Removal of CA was 39% in the 0.1% EHC column, and was 38% in the 0.5% EHC column. Consequently, the enhanced biotic removal of CA in the EHC columns was only 5.5 to 6.5% more than that in the non-sterile control.

Removal of CA in the 0.1% HRC column was 36%, indicating that the biotic removal in this column was 3.5% more than that in the non-sterile column. Removal of CA in the 0.5% HRC column was 46%, indicating that the biotic removal in this column was 13.5% more than that in the non-sterile column.

The results indicate that significant enhancement in biotic removal from addition of EHC or HRC was not achieved on Day 14. This is probably due to a lag time associated with establishing the microbial colonies. The native anaerobic bacteria were most likely exposed to oxygen during sample collection and mixing of the soils in the laboratory for baseline testing. Consequently, the microorganisms responsible for reductive dechlorination were most likely inhibited during the early periods of the test.

The TOC results were higher in the columns amended with EHC and HRC than the controls (Table 5). As expected, the TOC concentration was greater in the EHC column with the higher application rate. The 0.5% HRC column was not sampled for TOC since there was not enough volume on Day 14.

Table 5: Influence of EHC and HRC on TOC and Ethane concentrations after 14 days

Parameter	Concentration					
	0.1% EHC	0.5% EHC	0.1% HRC	0.5% HRC	Control	Sterile Control
TOC (mg/L)	70	630	220	NA	13	53
Ethane (ug/L)	ND (4)	ND (4)	ND (4)	ND (4)	ND (4)	ND (4)

ND = non detect (detection limit)

NA = Not analyzed; due to insufficient volume of effluent

Please note that alkalinity and chloride results are not available for the Day 14 sampling event since the wrong preservative was added to these sample jars.

3.3 Second Sampling Event (Day 29)

Table 6 shows data from Day 29 sampling event. The VOC concentrations in the sterile feed were similar to the Day 14 results while the non-sterile feed showed an additional reduction in the CA concentration. Both feeds were below the targeted CA concentration of 1,500 ug/L. Losses in the headspace of the feed bag were most likely the reason for the drop in feed concentration.

Table 6: Influence of EHC and HRC on VOC concentrations after 29 days

Parameter	Concentration (ug/L)							
	0.1% EHC	0.5% EHC	0.1% HRC	0.5% HRC	Control	Sterile Control	Feed	Sterile Feed
CA	700	430	530	590	640	600	210	750
CB	ND (1)	5.1	ND (1)	ND (1)	ND (1)	ND (1)	ND (1)	ND (1)

ND = non detect (detection limit)

The sterile control system showed 20% reduction in CA which indicates that significant abiotic removal was occurring in the columns.

Since the non-sterile feed concentration dropped significantly (210 ppb), the results are compared to the sterile feed. Removal of CA was 7% in the 0.1% EHC column, and was 43% in the 0.5% EHC column. At best, the biotic removal of CA in the EHC columns was only 23% more than that in the sterile control.

Removal of CA in the 0.1% HRC column was 29%, indicating that the biotic removal in this column was 9% more than that in the sterile column. Removal of CA in the 0.5% HRC column was 21%, indicating that the biotic removal in this column was 1% more than that in the sterile column.

The results indicate that significant enhancement in biotic removal from addition of EHC or HRC was not achieved after 29 days.

The alkalinity of site groundwater did not change as a result of either treatment. The chloride concentrations of the effluents were between 5 and 25 mg/L greater than the background chloride concentration (75 mg/L). The sterile control had the highest chloride concentration since mercuric chloride was used as the microbial inhibitor. TOC concentrations in the EHC and HRC treatment columns decreased since Day 14 (Table 7). Ethane was not detected in any column effluent on Day 29.

Table 7: Influence of EHC and HRC on Alkalinity, Chloride, TOC and Ethane concentrations after 29 days

Parameter	Concentration					
	0.1% EHC	0.05% EHC	0.1% HRC	0.05% HRC	Control	Sterile Control
Alkalinity (mg/L)	370	380	420	330	420	370
Chloride (mg/L)	80	80	80	84	86	100
TOC (mg/L)	14	100	16	120	13	16
Ethane (ug/L)	ND (8)	ND (40)	ND (4)	ND (4)	ND (4)	ND (4)

ND = non detect (detection limit)

3.4 Third Sampling Event (Day 42)

Table 8 shows data for Day 42 sampling event. The total VOC concentration in both feeds continued to decrease from the previous sampling events and the CA concentrations were significantly lower than the targeted concentration of 1,500 ug/L. Possible explanation for the decrease in the feed concentration is that CA stock standard (50 mg CA per mL methanol) that was used to spike the Site groundwater showed a decreased in the CA concentration over time and thus the feed was being spiked to a concentration lower than the targeted (1,500 ug/L) value.

Table 8: Influence of EHC and HRC on VOC concentrations after 42 days

Parameter	Concentration (ug/L)							
	0.1% EHC	0.5% EHC	0.1% HRC	0.5% HRC	Control	Sterile Control	Feed	Sterile Feed
CA	230	200	350	290	400	510	310	280
CB	ND (1)	2.7	ND (1)	ND (1)	ND (1)	ND (1)	1.4	1.5

ND = non detect (detection limit)

Effluent CA concentrations from both controls were higher than the feed indicating 100% removal in both control columns.

Removal of CA was 26% in the 0.1% EHC column, and was 35% in the 0.5% EHC column. There was no removal of CA in the 0.1% HRC column and only 6.5% removal in the 0.5% HRC column. Due to a low CA feed concentration, it was difficult to determine to what extent EHC or HRC were able to enhance the biotic removal. At best the enhancement may have been 35% for EHC and 6.5% for HRC. The results indicate that significant enhancement in biotic removal from addition of EHC or HRC was not achieved.

Table 9 shows supporting analytical data for Day 42. The alkalinity of Site groundwater did not change as a result of either treatment. The chloride concentrations of the effluents were between 9 and 17 mg/L greater than the background chloride concentration (75 mg/L). Once again the sterile control column had the highest chloride concentration since mercuric chloride was used as a microbial inhibitor. TOC concentrations in the treatment (EHC and HRC) and control columns were very similar and, the TOC concentrations in the treatment columns decreased greatly from the values on Day 29. After 42 days of column operation, ethane was not detected in any column effluent.

Table 9: Influence of EHC and HRC on Alkalinity, Chloride, TOC and Ethane concentrations after 42 days

Parameter	Concentration					
	0.1% EHC	0.05% EHC	0.1% HRC	0.05% HRC	Control	Sterile Control
Alkalinity (mg/L)	330	300	370	330	380	350
Chloride (mg/L)	90	84	84	91	84	92
TOC (mg/L)	9.6	12	9.9	11	9.5	11
Ethane (ug/L)	ND (4)	ND (4)	ND (4)	ND (4)	ND (4)	ND (4)

ND = non detect (detection limit)

3.5 Fourth Sampling Event (Day 71)

Table 10 shows the data for Day 71 sampling event. On Day 71, the CA concentrations in the two feeds were greater than those reported during the first three sampling events since a new CA stock standard was used for spiking the feeds.

Both controls showed reductions in the CA concentration when compared to their respective feeds. The sterile control system showed 82% reduction in CA while the non-sterile control showed 89% reduction in CA. This indicates that significant abiotic removal was occurring in both columns.

Removal of CA was 92% in the 0.1% EHC column, and was 91% in the 0.5% EHC column. Consequently, the biotic removal of CA in the EHC columns was only 2 to 4% more than that in the non-sterile control.

Removal of CA in the 0.1% HRC column was 98.5%, indicating that the biotic removal in this column was 10% more than that in the non-sterile column. Removal of CA in the 0.5% HRC column was 100%, indicating that the biotic removal in this column was 11% more than that in the non-sterile column.

The results indicate that the addition of EHC or HRC did not achieve significant enhancement in the biotic removal of VOCs.

Table 10: Influence of EHC and HRC on VOC concentrations after 71 days

Parameter	Concentration (ug/L)							
	0.1% EHC	0.5% EHC	0.1% HRC	0.5% HRC	Control	Sterile Control	Feed	Sterile Feed
CA	180	190	33	4.8	230	390	2,200	2,200
CB	ND (1)	0.9	ND (1)	0.56	ND (1)	ND (1)	ND (5)	ND (5)

ND = non detect (detection limit)

The alkalinity of the Site groundwater increased in both the treatment and control columns (Table 11). The initial Site groundwater characterization revealed an alkalinity concentration of 380 mg/L and the column effluents had alkalinity values between 410 and 490 mg/L on Day 71.

The chloride concentrations of the column effluents also showed an increase between 15 and 24 mg/L greater than the background chloride concentration (75 mg/L). The sterile control continued to have the highest chloride concentration and as previously noted this was due to the addition of mercuric chloride.

The TOC concentrations in the treatment and control columns were similar to those from the third sampling event. The values were less than optimal to support reductive dechlorination. The steep drop in TOC from Day 29 was surprising as sufficient quantities of HRC and EHC were injected in the systems.

Ethane was not detected in any column effluent on Day 71.

Table 11: Influence of EHC and HRC on Alkalinity, Chloride, TOC and Ethane concentrations after 71 days

Parameter	Concentration					
	0.1% EHC	0.05% EHC	0.1% HRC	0.05% HRC	Control	Sterile Control
Alkalinity (mg/L)	440	410	420	450	470	490
Chloride (mg/L)	90	90	97	92	95	99
TOC (mg/L)	10	11	11	11	10	16
Ethane (ug/L)	ND (4)	ND (4)	ND (4)	ND (4)	ND (4)	ND (4)

ND = non detect (detection limit)

3.6 Additional Sampling Event #1 (Day 94)

Table 12 shows data from Day 94 sampling. The CA concentrations in the two feeds were slightly below the targeted concentration on Day 94. The slightly lower CA concentration in the non-sterile feed is likely due to the activity of indigenous microbes in the Site groundwater. Both controls showed reductions in the CA concentration when compared to their respective feeds. The sterile control system showed 5% reduction in CA while the non-sterile control showed 20% reduction in CA.

Removal of CA was 52% in the 0.1% EHC column, and was 50% in the 0.5% EHC column. Consequently, the biotic removal of CA in the EHC columns was about 30 to 30% more than that in the non-sterile control.

Removal of CA in the 0.1% HRC column was 62%, indicating that the biotic removal in this column was 42% more than that in the non-sterile column. Removal of CA in the 0.5% HRC column was 99%, indicating that the biotic removal in this column was 79% more than that in the non-sterile column. This was the only case where appreciable enhancements in biotic removal of CA were seen from among all the data sets.

Table 12: Influence of EHC and HRC on VOC concentrations after 94 days

Parameter	Concentration (ug/L)							
	0.1% EHC	0.5% EHC	0.1% HRC	0.5% HRC	Control	Sterile Control	Feed	Sterile Feed
CA	485	500	380	ND (10)	810	1,280	1,005	1,345
DCM	230	260	185	ND (10)	415	345	ND (10)	ND (10)
TCE	20	20	20	15	20	ND (10)	25	18
PCE	ND (10)	ND (10)	ND (10)	ND (10)	ND (10)	20	135	68

ND = non detect (detection limit)

The original feed water from the site was exhausted so the experiments were continued with a second batch of groundwater collected from the site. Lower concentrations of other VOCs (methylene chloride (DCM), tetrachloroethylene (PCE), trichloroethylene (TCE)) were also detected in the feed bags and/or column effluents (Table 12). This may be related to the use of a second batch of groundwater from the Site. DCM was not detected in the feed bags but was detected in the effluent of both controls. Trace concentrations of trichloroethylene (TCE) and tetrachloroethylene (PCE) were detected in the feeds and in some of the column effluents.

3.7 Additional Sampling Event #2 (Day 107)

The results from Day 107 sampling are shown in Table 13. Both controls showed reductions in the CA concentration when compared to their respective feeds. The sterile control system showed 51% reduction in CA while the non-sterile control showed 88% reduction in CA.

There was no enhancement in the biotic removal of CA in both EHC columns as the non-sterile effluent concentration of CA was essentially the same as the effluent from the treatment columns.

There was 96% removal of CA in the 0.1% HRC column and 99.5% removal of CA in the 0.5% HRC column. Consequently, the biotic removal of CA in HRC columns was only 8% to 12% more than that in the non-sterile column.

As observed in the previous sampling, DCM was produced in all the column effluents. Trace concentrations of TCE and PCE were also detected in the effluent columns.

Table 13: Influence of EHC and HRC on VOC concentrations after 107 days

Parameter	Concentration (ug/L)							
	0.1% EHC	0.5% EHC	0.1% HRC	0.5% HRC	Control	Sterile Control	Feed	Sterile Feed
CA	305	250	80	ND (10)	270	960	2,245	1,448
DCM	145	120	100	185	220	185	ND (10)	ND (10)
TCE	10	10	15	ND (10)	10	ND (10)	40	20
PCE	ND (10)	45	ND (10)	ND (10)	15	65	45	18

ND = non detect (detection limit)

4.0 CONCLUSIONS

The purpose of this bench-scale feasibility study was to determine the ability of EHC and HRC to treat chlorinated volatile organic compounds in impacted groundwater collected from the Site. The following conclusions are provided based on the results of the testing:

- The initial characterization of the Site groundwater revealed that it had lower than expected concentrations of the COI (CA and CB), thus the Site groundwater was spiked with these COI to better represent the Site conditions.
- Due to VOC reductions in the feed during the first three sampling event, it was difficult to assess the effectiveness of the treatments. Both the EHC and HRC treatments showed reductions in the total VOC concentrations, but the control systems also showed reductions in total VOCs.
- A lag time of approximately 70 days was observed in both systems for the microorganisms to get established. The ORP in both systems stayed in the positive range until after Day 94.
- The fifth sampling (Day 94) showed that both EHC and HRC treatments were capable of treating CA. This was the only time the data indicated that biotic removal of CA was significantly enhanced by HRC and EHC.
- A consistently high biotic removal of CA was not seen with either EHC or HRC.
- The data shows that significant amounts of CA were being removed by abiotic means as well as biotic means without enhancements in the control columns. Consequently, there was no added value from using enhancements like HRC and EHC.
- The lack of enhanced biotic removal may have been from the lack of appropriate microorganisms capable of degrading CA in the soil from the downgradient area.

APPENDICIES

**FINAL REPORT: EHC AND HRC FEASIBILITY
STUDY FOR THE TREATMENT OF CHLORINATED
SOLVENTS IN GROUNDWATER FROM THE
FORMER COLUMBIA CEMENT INC., FREEPORT,
NY (THE SITE)**

Appendix A: Methodology for Headspace SPME GC/ECD determination of VOCs in water samples

In-house method of VOC analysis for Adventus Remediation Technologies
Method developed by Michael Gibson, PhD.

Introduction:

Solid phase microextraction (SPME) followed by GC desorption and analysis has been demonstrated to be an effective and reliable method of monitoring volatile contaminants in water samples. SPME fibers can be desorbed in the manual injection ports of most gas chromatographs (GC), not requiring the specialized hardware necessary for purge and trap or headspace systems typically used for VOC analysis (Santos F.J. et al., 1996).

The SPME fiber is a fused-silica fiber coated with a stationary phase, housed in a specialized syringe-type holder for protection and for inserting through septa. The fiber can either be immersed in an aqueous sample or be exposed to the headspace above an aqueous sample. The absorption of analytes is based on equilibrium partitioning between the coating and the sample. Where samples are contaminated with oils or other components, which may damage or reduce the life of the fibers headspace analysis may be preferable. James and Stack (1997) compared headspace and immersion SPME for VOC analysis of wastewaters and found headspace SPME to be preferable.

The in-house method of analysis of VOCs in water samples was developed on the basis of headspace SPME followed by direct GC analysis.

Method:


The fibers used were Carboxen™/Polydimethylsiloxane with a 75 μ m thick stationary phase (Supelco No. 57318). Two (2) ml aqueous samples were placed in 4ml amber glass headspace vials with Teflon lined septa (Supelco No. 27006) with a 4 mm Teflon coated magnetic stir bar. Samples were stirred for 10 minutes prior to insertion of the fiber, the fiber was inserted (ensuring that it did not come in contact with the aqueous phase) for an additional 10 minutes. Fibers were removed from the samples and immediately (within 30 seconds) placed into the injection port of the GC for desorption and analysis.

Chromatographic analysis was performed using a SRI 8610C Gas Chromatograph coupled with a flame ionization detector (FID) and dry electrolytic conductivity detector (DELCD). The injection port was lined with a small bore, 0.75 mm ID, glass liner (Supelco No. 26375-05). Both the injector and detector were maintained at 200 °C. The analytical column was a VOCOL capillary column (30 m x 0.25 mm, 1.5 μ m film thickness, Supelco No. 24205-U). Helium was used as the carrier gas; column flow rate was 10 ml/min. The column oven temperature program started at 40 °C for 2 min, increased at 10 °C/min to 150 °C for 2 min, then increased at 30 °C to 200 °C for a final 1 min.

References.

James K J, Stack M A (1997) Fresenius J Anal Chem 358: 833-837.

Santos F J, Galceran M T, Fraisse D (1996) J. Chromatogr. A, 742: 181-189.

Appendix B – Summary of pH and Oxidation Reduction Potential Readings**Figure A: pH readings of feeds and column effluents over time**

Appendix B – Summary of pH and Oxidation Reduction Potential Readings




Figure B: ORP readings of feeds and column effluents over time

Appendix C – Analytical Data

AA15-032 Initial Results

Baseline Sampling	28-Apr				
		Soil Initial 39285	UNITS	Water Initial 39286	UNITS
Dichlorodifluoromethane	ND (6.1)	ug/kg		ND (1)	ug/L
Chloromethane	ND (6.1)	ug/kg		ND (1)	ug/L
Vinyl chloride	ND (6.1)	ug/kg		ND (1)	ug/L
Bromomethane	ND (6.1)	ug/kg		ND (1)	ug/L
Chloroethane	ND (6.1)	ug/kg		730	ug/L
Trichlorofluoromethane	ND (6.1)	ug/kg		ND (1)	ug/L
1,1-Dichloroethene	ND (6.1)	ug/kg		ND (1)	ug/L
Carbon disulfide	ND (6.1)	ug/kg		ND (5)	ug/L
Acetone	ND (6.1)	ug/kg		ND (5)	ug/L
Methylene chloride	ND (6.1)	ug/kg		ND (1)	ug/L
trans-1,2-Dichloroethene	ND (6.1)	ug/kg		ND (1)	ug/L
Methyl-tert-butyl-ether (MTBE)	ND (6.1)	ug/kg		ND (1)	ug/L
1,1-Dichloroethane	ND (6.1)	ug/kg		ND (1)	ug/L
2,2-Dichloropropane	ND (6.1)	ug/kg		ND (1)	ug/L
cis-1,2-Dichloroethene	ND (6.1)	ug/kg		ND (1)	ug/L
2-Butanone (MEK)	ND (6.1)	ug/kg		ND (5)	ug/L
Bromochloromethane	ND (6.1)	ug/kg		ND (1)	ug/L
Chloroform	ND (6.1)	ug/kg		ND (1)	ug/L
1,1,1-Trichloroethane	ND (6.1)	ug/kg		ND (1)	ug/L
1,1-Dichloropropene	ND (6.1)	ug/kg		ND (1)	ug/L
Carbon tetrachloride	ND (6.1)	ug/kg		ND (1)	ug/L
Benzene	ND (6.1)	ug/kg		ND (1)	ug/L
1,2-Dichloroethane	ND (6.1)	ug/kg		ND (1)	ug/L
Trichloroethene	ND (6.1)	ug/kg		ND (1)	ug/L
1,2-Dichloropropane	ND (6.1)	ug/kg		ND (1)	ug/L
Dibromomethane	ND (6.1)	ug/kg		ND (1)	ug/L
Bromodichloromethane	ND (6.1)	ug/kg		ND (1)	ug/L
cis-1,3-Dichloropropene	ND (6.1)	ug/kg		ND (1)	ug/L
4-Methyl-2-pentanone (MIBK)	ND (6.1)	ug/kg		ND (5)	ug/L
Toluene	ND (6.1)	ug/kg		ND (1)	ug/L
trans-1,3-Dichloropropene	ND (6.1)	ug/kg		ND (1)	ug/L
1,1,2-Trichloroethane	ND (6.1)	ug/kg		ND (1)	ug/L
Tetrachloroethene	ND (6.1)	ug/kg		ND (1)	ug/L
1,3-Dichloropropane	ND (6.1)	ug/kg		ND (1)	ug/L
2-Hexanone	ND (6.1)	ug/kg		ND (5)	ug/L
Dibromochloromethane	ND (6.1)	ug/kg		ND (1)	ug/L
1,2-Dibromoethane (EDB)	ND (6.1)	ug/kg		ND (1)	ug/L
Chlorobenzene	ND (6.1)	ug/kg		4	ug/L
1,1,1-Tetrachloroethane	ND (6.1)	ug/kg		ND (1)	ug/L
Ethylbenzene	ND (6.1)	ug/kg		ND (1)	ug/L
m,p-Xylenes	12	ug/kg		ND (2)	ug/L
o-Xylene	ND (6.1)	ug/kg		ND (1)	ug/L
Styrene	ND (6.1)	ug/kg		ND (1)	ug/L
Bromoform	ND (6.1)	ug/kg		ND (1)	ug/L
Isopropylbenzene	ND (6.1)	ug/kg		ND (1)	ug/L
Bromobenzene	ND (6.1)	ug/kg		ND (1)	ug/L
1,1,2,2-Tetrachloroethane	ND (6.1)	ug/kg		ND (1)	ug/L
1,2,3-Trichloropropane	ND (6.1)	ug/kg		ND (1)	ug/L
n-Propylbenzene	ND (6.1)	ug/kg		ND (1)	ug/L
2-Chlorotoluene	ND (6.1)	ug/kg		ND (1)	ug/L
1,3,5-Trimethylbenzene	ND (6.1)	ug/kg		ND (1)	ug/L
4-Chlorotoluene	ND (6.1)	ug/kg		ND (1)	ug/L
tert-Butylbenzene	ND (6.1)	ug/kg		ND (1)	ug/L
1,2,4-Trimethylbenzene	ND (6.1)	ug/kg		ND (1)	ug/L
sec-Butylbenzene	ND (6.1)	ug/kg		ND (1)	ug/L
1,3-Dichlorobenzene	ND (6.1)	ug/kg		ND (1)	ug/L
p-Isopropyltoluene	ND (6.1)	ug/kg		ND (1)	ug/L
1,4-Dichlorobenzene	ND (6.1)	ug/kg		ND (1)	ug/L
n-Butylbenzene	ND (6.1)	ug/kg		ND (1)	ug/L
1,2-Dichlorobenzene	ND (6.1)	ug/kg		ND (1)	ug/L
1,2-Dibromo-3-chloropropane	ND (6.1)	ug/kg		ND (1)	ug/L
1,2,4-Trichlorobenzene	ND (6.1)	ug/kg		ND (1)	ug/L
Hexachlorobutadiene	ND (6.1)	ug/kg		ND (1)	ug/L
Naphthalene	ND (6.1)	ug/kg		ND (1)	ug/L
1,2,3-Trichlorobenzene	ND (6.1)	ug/kg		ND (1)	ug/L
1,3,5-Trichlorobenzene	ND (6.1)	ug/kg		ND (1)	ug/L
% Solids, solid	82.6	%		n/a	
% Moisture, Solids	17.4	%		n/a	
Alkalinity, Total as CaCO ₃	ND (500)	mg/kg		380	mg/L
Chloride	3.3	mg/kg		75	mg/L
Nitrate as N	ND (1.2)	mg/kg		ND (0.1)	mg/L
Sulfate	3	mg/kg		0.29	mg/L
TOC	9,300	mg/kg		8	mg/L
pH	6.9	pH units		6.3	pH units
Total Iron	9,700	mg/kg		8	mg/L
Dissolved Iron	n/a	mg/kg		0.065	mg/L

The dissolved Fe result was below the RL but above the MCL.

AAI5-032 Sampling #1 t=14 days

Analyte	Column 1 Effluent		Column 2 Effluent		Units	
	38927	Qualifier	DL	38928	Qualifier	
TOC Average Duplicates	70		10	630		40 mg/L
Dichlorodifluoromethane	1 U		1	1 U		1 ug/L
Chloromethane	1 U		1	1 U		1 ug/L
Vinyl chloride	1 U		1	1 U		1 ug/L
Bromomethane	1 U*		1	1 U*		1 ug/L
Chloroethane	490		10	500		10 ug/L
Trichlorofluoromethane	1 U		1	1 U		1 ug/L
1,1-Dichloroethene	1 U		1	1 U		1 ug/L
Carbon disulfide	5 U		5	2.4 J		5 ug/L
Acetone	52		5	96		5 ug/L
Methylene chloride	58		1	69		1 ug/L
trans-1,2-Dichloroethene	1 U		1	1 U		1 ug/L
Methyl-tert-butyl-ether (MTBE)	1 U		1	1 U		1 ug/L
1,1-Dichloroethane	1 U		1	1 U		1 ug/L
2,2-Dichloropropane	1 U		1	1 U		1 ug/L
cis-1,2-Dichloroethene	1 U		1	1 U		1 ug/L
2-Butanone (MEK)	5 U		5	47		5 ug/L
Bromochloromethane	1 U		1	1 U		1 ug/L
Chloroform	1 U		1	1 U		1 ug/L
1,1,1-Trichloroethane	1 U		1	1 U		1 ug/L
1,1-Dichloropropene	1 U		1	1 U		1 ug/L
Carbon tetrachloride	1 U		1	1 U		1 ug/L
Benzene	1 U		1	1 U		1 ug/L
1,2-Dichloroethane	1 U		1	1.3		1 ug/L
Trichloroethene	1 U		1	6		1 ug/L
1,2-Dichloropropane	1 U		1	1 U		1 ug/L
Dibromomethane	1 U		1	1 U		1 ug/L
Bromodichloromethane	1 U*		1	1 U*		1 ug/L
cis-1,3-Dichloropropene	1 U		1	1 U		1 ug/L
4-Methyl-2-pentanone (MIBK)	5 U		5	5 U		5 ug/L
Toluene	1 U		1	1 U		1 ug/L
trans-1,3-Dichloropropene	1 U		1	1 U		1 ug/L
1,1,2-Trichloroethane	1 U		1	1 U		1 ug/L
Tetrachloroethene	1 U		1	1 U		1 ug/L
1,3-Dichloropropane	1 U		1	1 U		1 ug/L
2-Hexanone	5 U		5	5 U		5 ug/L
Dibromochloromethane	1 U*		1	1 U*		1 ug/L
1,2-Dibromoethane (EDB)	1 U		1	1 U		1 ug/L
Chlorobenzene	2.3		1	3.7		1 ug/L
1,1,1,2-Tetrachloroethane	1 U		1	1 U		1 ug/L
Ethylbenzene	1 U		1	2.6		1 ug/L
m&p-Xylenes	2 U		2	2 U		2 ug/L
o-Xylene	1 U		1	1 U		1 ug/L
Styrene	1 U		1	1 U		1 ug/L
Bromoform	1 U*		1	1 U*		1 ug/L

AA15-032 Sampling #1 t=14 days

Analyte	Column 1 Effluent		Column 2 Effluent		DL	Units
	38927	Qualifier	38928	Qualifier		
Isopropylbenzene	1 U	1	1 U	1	1 ug/L	
Bromobenzene	1 U	1	1 U	1	1 ug/L	
1,1,2,2-Tetrachloroethane	1 U	1	1 U	1	1 ug/L	
1,2,3-Trichloropropane	1 U	1	1 U	1	1 ug/L	
n-Propylbenzene	1 U	1	1 U	1	1 ug/L	
2-Chlorotoluene	1 U	1	1 U	1	1 ug/L	
1,3,5-Trimethylbenzene	1 U	1	1 U	1	1 ug/L	
4-Chlorotoluene	1 U	1	1 U	1	1 ug/L	
tert-Butylbenzene	1 U	1	1 U	1	1 ug/L	
1,2,4-Trimethylbenzene	1 U	1	1 U	1	1 ug/L	
sec-Butylbenzene	1 U	1	1 U	1	1 ug/L	
1,3-Dichlorobenzene	1 U	1	1 U	1	1 ug/L	
p-Isopropyltoluene	1 U	1	1 U	1	1 ug/L	
1,4-Dichlorobenzene	1 U	1	1 U	1	1 ug/L	
n-Butylbenzene	1 U	1	1 U	1	1 ug/L	
1,2-Dichlorobenzene	1 U	1	1 U	1	1 ug/L	
1,2-Dibromo-3-chloropropane	1 U	1	1 U	1	1 ug/L	
1,3,5-Trichlorobenzene	1 U	1	1 U	1	1 ug/L	
1,2,4-Trichlorobenzene	1 U	1	1 U	1	1 ug/L	
Hexachlorobutadiene	1 U	1	1 U	1	1 ug/L	
Naphthalene	1 U	1	1 U	1	1 ug/L	
1,2,3-Trichlorobenzene	1 U	1	1 U	1	1 ug/L	
Ethane	4 U		4	4 U		4 ug/L

U = compound analyzed but not detected at a concentration above the reporting limit.

AAI5-032 Sampling #1 t=14 days

Analyte	Column 3 Effluent		Column 4 Effluent		DL	Units
	38929	Qualifier	38930	Qualifier		
TOC Average Duplicates	220		40	—	—	1 ug/L
Dichlorodifluoromethane	1 U		1	1 U	—	1 ug/L
Chloromethane	1 U		1	1 U	—	1 ug/L
Vinyl chloride	1 U		1	1 U	—	1 ug/L
Bromomethane	1 U*		1	1 U*	—	1 ug/L
Chloroethane	510		10	430	—	10 ug/L
Trichlorofluoromethane	1 U		1	1 U	—	1 ug/L
1,1-Dichloroethene	1 U		1	1 U	—	1 ug/L
Carbon disulfide	1.3 J		5	1.9 J	—	5 ug/L
Acetone	49		5	220	—	50 ug/L
Methylene chloride	56		1	62	—	1 ug/L
trans-1,2-Dichloroethene	1 U		1	1 U	—	1 ug/L
Methyl-tert-butyl-ether (MTBE)	1 U		1	1 U	—	1 ug/L
1,1-Dichloroethane	1 U		1	1 U	—	1 ug/L
2,2-Dichloropropane	1 U		1	1 U	—	1 ug/L
cis-1,2-Dichloroethene	1 U		1	1 U	—	1 ug/L
2-Butanone (MEK)	84		5	160	—	50 ug/L
Bromochloromethane	1 U		1	1 U	—	1 ug/L
Chloroform	1 U		1	1 U	—	1 ug/L
1,1,1-Trichloroethane	1 U		1	1 U	—	1 ug/L
1,1-Dichloropropene	1 U		1	1 U	—	1 ug/L
Carbon tetrachloride	1 U		1	1 U	—	1 ug/L
Benzene	1 U		1	1 U	—	1 ug/L
1,2-Dichloroethane	1 U		1	2.3	—	1 ug/L
Trichloroethene	1 U		1	1 U	—	1 ug/L
1,2-Dichloropropane	1 U		1	1 U	—	1 ug/L
Dibromomethane	1 U		1	1 U	—	1 ug/L
Bromodichloromethane	1 U*		1	1 U*	—	1 ug/L
cis-1,3-Dichloropropene	1 U		1	1 U	—	1 ug/L
4-Methyl-2-pentanone (MIBK)	5 U		5	5 U	—	5 ug/L
Toluene	1 U		1	1 U	—	1 ug/L
trans-1,3-Dichloropropene	1 U		1	1 U	—	1 ug/L
1,1,2-Trichloroethane	1 U		1	1 U	—	1 ug/L
Tetrachloroethene	1 U		1	1 U	—	1 ug/L
1,3-Dichloropropane	1 U		1	1 U	—	1 ug/L
2-Hexanone	5 U		5	5 U	—	5 ug/L
Dibromochloromethane	1 U*		1	1 U*	—	1 ug/L
1,2-Dibromoethane (EDB)	1 U		1	1 U	—	1 ug/L
Chlorobenzene	2.3		1	9.5	—	1 ug/L
1,1,1,2-Tetrachloroethane	1 U		1	1 U	—	1 ug/L
Ethylbenzene	1 U		1	1 U	—	1 ug/L
m&p-Xylenes	2 U		2	2 U	—	2 ug/L
o-Xylene	1 U		1	1 U	—	1 ug/L
Styrene	1 U		1	1 U	—	1 ug/L
Bromoform	1 U*		1	1 U*	—	1 ug/L

AAI5-032 Sampling #1 t=14 days

Analyte	Column 3 Effluent		Column 4 Effluent		DL	Units
	38929	Qualifier	38930	Qualifier		
Isopropylbenzene	1 U	1	1 U	1	1 ug/L	
Bromobenzene	1 U	1	1 U	1	1 ug/L	
1,1,2,2-Tetrachloroethane	1 U	1	1 U	1	1 ug/L	
1,2,3-Trichloropropane	1 U	1	1 U	1	1 ug/L	
n-Propylbenzene	1 U	1	1 U	1	1 ug/L	
2-Chlorotoluene	1 U	1	1 U	1	1 ug/L	
1,3,5-Trimethylbenzene	1 U	1	1 U	1	1 ug/L	
4-Chlorotoluene	1 U	1	1 U	1	1 ug/L	
tert-Butylbenzene	1 U	1	1 U	1	1 ug/L	
1,2,4-Trimethylbenzene	1 U	1	1 U	1	1 ug/L	
sec-Butylbenzene	1 U	1	1 U	1	1 ug/L	
1,3-Dichlorobenzene	1 U	1	1 U	1	1 ug/L	
p-Isopropyltoluene	1 U	1	1 U	1	1 ug/L	
1,4-Dichlorobenzene	1 U	1	1 U	1	1 ug/L	
n-Butylbenzene	1 U	1	1 U	1	1 ug/L	
1,2-Dichlorobenzene	1 U	1	1 U	1	1 ug/L	
1,2-Dibromo-3-chloropropane	1 U	1	1 U	1	1 ug/L	
1,3,5-Trichlorobenzene	1 U	1	1 U	1	1 ug/L	
1,2,4-Trichlorobenzene	1 U	1	1 U	1	1 ug/L	
Hexachlorobutadiene	1 U	1	1 U	1	1 ug/L	
Naphthalene	1 U	1	1 U	1	1 ug/L	
1,2,3-Trichlorobenzene	1 U	1	1 U	1	1 ug/L	

Analyte	38929	Qualifier	DL	38930	Qualifier	DL	Units
Ethane	4 U	4	4 U	4 U	4	4	4 ug/L

U = compound analyzed but not detected at a concentration above the reporting limit.

AAI5-032 Sampling #1 t=14 days

Analyte	Column 5 Effluent			Column 6 Effluent			
	38931	Qualifier	DL	38932	Qualifier	DL	Units
TOC Average Duplicates	13		2	53			10 mg/L
Dichlorodifluoromethane	1 U		1	1 U			1 ug/L
Chloromethane	1 U		1	1 U			1 ug/L
Vinyl chloride	1 U		1	1 U			1 ug/L
Bromomethane	1 U*		1	1 U*			1 ug/L
Chloroethane	540		10	480			10 ug/L
Trichlorofluoromethane	1 U		1	1 U			1 ug/L
1,1-Dichloroethene	1 U		1	1 U			1 ug/L
Carbon disulfide	5 U		5	5 U			5 ug/L
Acetone	5 U		5	58			5 ug/L
Methylene chloride	90		1	51			1 ug/L
trans-1,2-Dichloroethene	1 U		1	1 U			1 ug/L
Methyl-tert-butyl-ether (MTBE)	1 U		1	1 U			1 ug/L
1,1-Dichloroethane	1 U		1	1 U			1 ug/L
2,2-Dichloropropane	1 U		1	1 U			1 ug/L
cis-1,2-Dichloroethene	1 U		1	1 U			1 ug/L
2-Butanone (MEK)	5 U		5	12			5 ug/L
Bromochloromethane	1 U		1	1 U			1 ug/L
Chloroform	1 U		1	1 U			1 ug/L
1,1,1-Trichloroethane	1 U		1	1 U			1 ug/L
1,1-Dichloropropene	1 U		1	1 U			1 ug/L
Carbon tetrachloride	1 U		1	1 U			1 ug/L
Benzene	1 U		1	1 U			1 ug/L
1,2-Dichloroethane	1 U		1	1 U			1 ug/L
Trichloroethene	1 U		1	1 U			1 ug/L
1,2-Dichloropropane	1 U		1	1 U			1 ug/L
Dibromomethane	1 U		1	1 U			1 ug/L
Bromodichloromethane	1 U*		1	1 U*			1 ug/L
cis-1,3-Dichloropropene	1 U		1	1 U			1 ug/L
4-Methyl-2-pentanone (MIBK)	5 U		5	5 U			5 ug/L
Toluene	1 U		1	1 U			1 ug/L
trans-1,3-Dichloropropene	1 U		1	1 U			1 ug/L
1,1,2-Trichloroethane	1 U		1	1 U			1 ug/L
Tetrachloroethene	1 U		1	1 U			1 ug/L
1,3-Dichloropropane	1 U		1	1 U			1 ug/L
2-Hexanone	5 U		5	5 U			5 ug/L
Dibromochloromethane	1 U*		1	1 U*			1 ug/L
1,2-Dibromoethane (EDB)	1 U		1	1 U			1 ug/L
Chlorobenzene	7.4		1	16			1 ug/L
1,1,1,2-Tetrachloroethane	1 U		1	1 U			1 ug/L
Ethylbenzene	1 U		1	1 U			1 ug/L
m&p-Xylenes	2 U		2	2 U			2 ug/L
o-Xylene	1 U		1	1 U			1 ug/L
Styrene	1 U		1	1 U			1 ug/L
Bromoform	1 U*		1	1 U*			1 ug/L

AA15-032 Sampling #1 t=14 days

Analyte	Column 5 Effluent			Column 6 Effluent			Units
	38931	Qualifier	DL	38932	Qualifier	DL	
Isopropylbenzene	1 U	1	1 U	1	1 U	1 ug/L	
Bromobenzene	1 U	1	1 U	1	1 U	1 ug/L	
1,1,2,2-Tetrachloroethane	1 U	1	1 U	1	1 U	1 ug/L	
1,2,3-Trichloropropane	1 U	1	1 U	1	1 U	1 ug/L	
n-Propylbenzene	1 U	1	1 U	1	1 U	1 ug/L	
2-Chlorotoluene	1 U	1	1 U	1	1 U	1 ug/L	
1,3,5-Trimethylbenzene	1 U	1	1 U	1	1 U	1 ug/L	
4-Chlorotoluene	1 U	1	1 U	1	1 U	1 ug/L	
tert-Butylbenzene	1 U	1	1 U	1	1 U	1 ug/L	
1,2,4-Trimethylbenzene	1 U	1	1 U	1	1 U	1 ug/L	
sec-Butylbenzene	1 U	1	1 U	1	1 U	1 ug/L	
1,3-Dichlorobenzene	1 U	1	1 U	1	1 U	1 ug/L	
p-Isopropyltoluene	1 U	1	1 U	1	1 U	1 ug/L	
1,4-Dichlorobenzene	5	1	1 U	1	1 U	1 ug/L	
n-Butylbenzene	1 U	1	1 U	1	1 U	1 ug/L	
1,2-Dichlorobenzene	1 U	1	1 U	1	1 U	1 ug/L	
1,2-Dibromo-3-chloropropane	1 U	1	1 U	1	1 U	1 ug/L	
1,3,5-Trichlorobenzene	1 U	1	1 U	1	1 U	1 ug/L	
1,2,4-Trichlorobenzene	1 U	1	1 U	1	1 U	1 ug/L	
Hexachlorobutadiene	1 U	1	1 U	1	1 U	1 ug/L	
Naphthalene	1 U	1	1 U	1	1 U	1 ug/L	
1,2,3-Trichlorobenzene	1 U	1	1 U	1	1 U	1 ug/L	

Analyte	38931	Qualifier	DL	38932	Qualifier	DL	Units
Ethane	4 U	4	4 U	4	4 U	4	4 ug/L

U = compound analyzed but not detected at a concentration above the reporting limit.

AA15-032 Sampling #1 t=14 days

Analyte	Feed #1		Feed #2		DL	Units
	38933	Qualifier	38934	Qualifier		
TOC Average Duplicates	---	---	---	---	---	---
Dichlorodifluoromethane	1 U		1	1 U	1 ug/L	
Chloromethane	1 U		1	1 U	1 ug/L	
Vinyl chloride	1 U		1	1 U	1 ug/L	
Bromomethane	1 U*		1	1 U*	1 ug/L	
Chloroethane	800		10	720	10 ug/L	
Trichlorofluoromethane	1 U		1	1 U	1 ug/L	
1,1-Dichloroethene	1 U		1	1 U	1 ug/L	
Carbon disulfide	5 U		5	5 U	5 ug/L	
Acetone	5 U		5	5 U	5 ug/L	
Methylene chloride	1 U		1	1 U	1 ug/L	
trans-1,2-Dichloroethene	1 U		1	1 U	1 ug/L	
Methyl-tert-butyl-ether (MTBE)	1 U		1	1 U	1 ug/L	
1,1-Dichloroethane	1 U		1	1 U	1 ug/L	
2,2-Dichloropropane	1 U		1	1 U	1 ug/L	
cis-1,2-Dichloroethene	1 U		1	1 U	1 ug/L	
2-Butanone (MEK)	5 U		5	5 U	5 ug/L	
Bromoform	1 U		1	1 U	1 ug/L	
Chloroform	1 U		1	1 U	1 ug/L	
1,1,1-Trichloroethane	1 U		1	1 U	1 ug/L	
1,1-Dichloropropene	1 U		1	1 U	1 ug/L	
Carbon tetrachloride	1 U		1	1 U	1 ug/L	
Benzene	1 U		1	1 U	1 ug/L	
1,2-Dichloroethane	1 U		1	1 U	1 ug/L	
Trichloroethene	1 U		1	1 U	1 ug/L	
1,2-Dichloropropane	1 U		1	1 U	1 ug/L	
Dibromomethane	1 U		1	1 U	1 ug/L	
Bromodichloromethane	1 U*		1	1 U*	1 ug/L	
cis-1,3-Dichloropropene	1 U		1	1 U	1 ug/L	
4-Methyl-2-pentanone (MIBK)	5 U		5	5 U	5 ug/L	
Toluene	1 U		1	1 U	1 ug/L	
trans-1,3-Dichloropropene	1 U		1	1 U	1 ug/L	
1,1,2-Trichloroethane	1 U		1	1 U	1 ug/L	
Tetrachloroethene	1 U		1	1 U	1 ug/L	
1,3-Dichloropropane	1 U		1	1 U	1 ug/L	
2-Hexanone	5 U		5	5 U	5 ug/L	
Dibromochloromethane	1 U*		1	1 U*	1 ug/L	
1,2-Dibromoethane (EDB)	1 U		1	1 U	1 ug/L	
Chlorobenzene	7		1	10	1 ug/L	
1,1,1,2-Tetrachloroethane	1 U		1	1 U	1 ug/L	
Ethylbenzene	1 U		1	1 U	1 ug/L	
m&p-Xylenes	2 U		2	2 U	2 ug/L	
o-Xylene	1 U		1	1 U	1 ug/L	
Styrene	1 U		1	1 U	1 ug/L	
Bromoform	1 U*		1	1 U*	1 ug/L	

AA15-032 Sampling #1 t=14 days

Analyte	Feed #1		Feed #2		DL	Units
	38933	Qualifier	38934	Qualifier		
Isopropylbenzene	1 U	1	1 U	1	1 ug/L	
Bromobenzene	1 U	1	1 U	1	1 ug/L	
1,1,2,2-Tetrachloroethane	1 U	1	1 U	1	1 ug/L	
1,2,3-Trichloropropane	1 U	1	1 U	1	1 ug/L	
n-Propylbenzene	1 U	1	1 U	1	1 ug/L	
2-Chlorotoluene	1 U	1	1 U	1	1 ug/L	
1,3,5-Trimethylbenzene	1 U	1	1 U	1	1 ug/L	
4-Chlorotoluene	1 U	1	1 U	1	1 ug/L	
tert-Butylbenzene	1 U	1	1 U	1	1 ug/L	
1,2,4-Trimethylbenzene	1 U	1	1 U	1	1 ug/L	
sec-Butylbenzene	1 U	1	1 U	1	1 ug/L	
1,3-Dichlorobenzene	1 U	1	1 U	1	1 ug/L	
p-Isopropyltoluene	1 U	1	1 U	1	1 ug/L	
1,4-Dichlorobenzene	1 U	1	1 U	1	1 ug/L	
n-Butylbenzene	1 U	1	1 U	1	1 ug/L	
1,2-Dichlorobenzene	1 U	1	1 U	1	1 ug/L	
1,2-Dibromo-3-chloropropane	1 U	1	1 U	1	1 ug/L	
1,3,5-Trichlorobenzene	1 U	1	1 U	1	1 ug/L	
1,2,4-Trichlorobenzene	1 U	1	1 U	1	1 ug/L	
Hexachlorobutadiene	1 U	1	1 U	1	1 ug/L	
Naphthalene	1 U	1	1 U	1	1 ug/L	
1,2,3-Trichlorobenzene	1 U	1	1 U	1	1 ug/L	

Analyte

Ethane

U = compound analyzed but not detected at a concentration above the reporting limit.

AAI5-032 Sampling #2 t=29 days

Analyte	Column 1 Effluent	Column 2 Effluent	Column 3 Effluent	Qualifed	Units
	40030	40031	40032	Qualifed	
Alkalinity, Total as CaCO ₃	370	380	420		mg/L
Chloride	80	80	80		mg/L
TOC Average Duplicates	14	100	16		mg/L
Dichlorodifluoromethane	1.0	U	1.0	U	ug/L
Chloromethane	1.0	U	1.0	U	ug/L
Vinyl chloride	1.0	U	1.0	U	ug/L
Bromomethane	1.0	U	1.0	U	ug/L
Chloroethane	700	430	530		ug/L
Trichlorofluoromethane	1.0	U	1.0	U	ug/L
1,1-Dichloroethene	1.0	U	1.0	U	ug/L
Carbon disulfide	5.0	U	5.0	U	ug/L
Acetone	5.0	U	20		ug/L
Methylene chloride	45	39	53		ug/L
trans-1,2-Dichloroethene	1.0	U	1.0	U	ug/L
Methyl-tert-butyl-ether (MTBE)	1.0	U	1.0	U	ug/L
1,1-Dichloroethane	1.0	U	1.0	U	ug/L
2,2-Dichloropropane	1.0	U	1.0	U	ug/L
cis-1,2-Dichloroethene	1.0	U	1.1		ug/L
2-Butanone (MEK)	5.0	U	6.1		ug/L
Bromoform	1.0	U	1.0	U	ug/L
1,1,1-Trichloroethane	1.0	U	1.0	U	ug/L
1,1-Dichloropropene	1.0	U*	1.0	U*	ug/L
Carbon tetrachloride	1.0	U	1.0	U	ug/L
Benzene	1.0	U	1.0	U	ug/L
1,2-Dichloroethane	1.0	U	1.2		ug/L
Trichloroethene	1.0	U	5.1		ug/L
1,2-Dichloropropane	1.0	U	1.0	U	ug/L
Dibromomethane	1.0	U	1.0	U	ug/L
Bromodichloromethane	1.0	U	1.0	U	ug/L
cis-1,3-Dichloropropene	1.0	U	1.0	U	ug/L
4-Methyl-2-pentanone (MIBK)	5.0	U	5.0	U	ug/L
Toluene	1.0	U	1.0	U	ug/L
trans-1,3-Dichloropropene	1.0	U	1.0	U	ug/L
1,1,2-Trichloroethane	1.0	U	1.0	U	ug/L
Tetrachloroethene	1.0	U	1.0	U	ug/L
1,3-Dichloropropane	1.0	U	1.0	U	ug/L
2-Hexanone	5.0	U	5.0	U	ug/L
Dibromochloromethane	1.0	U	1.0	U	ug/L
1,2-Dibromoethane (EDB)	1.0	U	1.0	U	ug/L
Chlorobenzene	1.0	U	4.1		ug/L
1,1,1,2-Tetrachloroethane	1.0	U	1.0	U	ug/L
Ethylbenzene	1.0	U	1.0	U	ug/L
m&p-Xylenes	2.0	U	2.0	U	ug/L

AAI5-032 Sampling #2 t=29 days

Analyte	Column 1		Column 2		Column 3		
	Effluent	Qualifier	Effluent	Qualifier	Effluent	Qualifier	
	40030		40031		40032		Units
o-Xylene	1.0	U	1.0	U	1.0	U	ug/L
Styrene	1.0	U	1.0	U	1.0	U	ug/L
Bromoform	1.0	U	1.0	U	1.0	U	ug/L
Isopropylbenzene	1.0	U	1.0	U	1.0	U	ug/L
Bromobenzene	1.0	U	1.0	U	1.0	U	ug/L
1,1,2,2-Tetrachloroethane	1.0	U	1.0	U	1.0	U	ug/L
1,2,3-Trichloropropane	1.0	U	1.0	U	1.0	U	ug/L
n-Propylbenzene	1.0	U	1.0	U	1.0	U	ug/L
2-Chlorotoluene	1.0	U	1.0	U	1.0	U	ug/L
1,3,5-Trimethylbenzene	1.0	U	1.0	U	1.0	U	ug/L
4-Chlorotoluene	1.0	U	1.0	U	1.0	U	ug/L
tert-Butylbenzene	1.0	U	1.0	U	1.0	U	ug/L
1,2,4-Trimethylbenzene	1.0	U	1.0	U	1.0	U	ug/L
sec-Butylbenzene	1.0	U	1.0	U	1.0	U	ug/L
1,3-Dichlorobenzene	1.0	U	1.0	U	1.0	U	ug/L
p-Isopropyltoluene	1.0	U	1.0	U	1.0	U	ug/L
1,4-Dichlorobenzene	1.0	U	1.0	U	1.0	U	ug/L
n-Butylbenzene	1.0	U	1.0	U	1.0	U	ug/L
1,2-Dichlorobenzene	1.0	U	1.0	U	1.0	U	ug/L
1,2-Dibromo-3-chloropropane	1.0	U	1.0	U	1.0	U	ug/L
1,3,5-Trichlorobenzene	1.0	U	1.0	U	1.0	U	ug/L
1,2,4-Trichlorobenzene	1.0	U	1.0	U	1.0	U	ug/L
Hexachlorobutadiene	1.0	U	1.0	U	1.0	U	ug/L
Naphthalene	1.0	U	1.0	U	1.0	U	ug/L
1,2,3-Trichlorobenzene	1.0	U	1.0	U	1.0	U	ug/L

AAI5-032 Sampling #2 t=29 days

Analyte	Column 4 Effluent 40033	Column 5 Effluent 40034	Column 6 Effluent 40035	Qualifie	Qualifie	Qualifie	Units
Alkalinity, Total as CaCO ₃	330	420	370				mg/L
Chloride	84	86	100				mg/L
TOC Average Duplicates	120	13	16				mg/L
Dichlorodifluoromethane	1.0	U	1.0	U	1.0	U	ug/L
Chloromethane	1.0	U	1.0	U	1.0	U	ug/L
Vinyl chloride	1.0	U	1.0	U	1.0	U	ug/L
Bromomethane	1.0	U	1.0	U	1.0	U	ug/L
Chloroethane	590	640	600				ug/L
Trichlorofluoromethane	1.0	U	1.0	U	1.0	U	ug/L
1,1-Dichloroethene	1.0	U	1.0	U	1.0	U	ug/L
Carbon disulfide	5.0	U	5.0	U	5.0	U	ug/L
Acetone	17		5.0	U	11		ug/L
Methylene chloride	140		88		47		ug/L
trans-1,2-Dichloroethene	1.0	U	1.0	U	1.0	U	ug/L
Methyl-tert-butyl-ether (MTBE)	1.0	U	1.0	U	1.0	U	ug/L
1,1-Dichloroethane	1.0	U	1.0	U	1.0	U	ug/L
2,2-Dichloropropane	1.0	U	1.0	U	1.0	U	ug/L
cis-1,2-Dichloroethene	1.0	U	1.0	U	1.0	U	ug/L
2-Butanone (MEK)	23		5.0	U	5.0	U	ug/L
Bromochloromethane	1.0	U	1.0	U	1.0	U	ug/L
Chloroform	1.0	U	1.0	U	1.0	U	ug/L
1,1,1-Trichloroethane	1.0	U	1.0	U	1.0	U	ug/L
1,1-Dichloropropene	1.0	U*	1.0	U*	1.0	U*	ug/L
Carbon tetrachloride	1.0	U	1.0	U	1.0	U	ug/L
Benzene	1.0	U	1.0	U	1.0	U	ug/L
1,2-Dichloroethane	3.1		1.0	U	1.0	U	ug/L
Trichloroethene	1.0	U	1.0	U	1.0	U	ug/L
1,2-Dichloropropane	1.0	U	1.0	U	1.0	U	ug/L
Dibromomethane	1.0	U	1.0	U	1.0	U	ug/L
Bromodichloromethane	1.0	U	1.0	U	1.0	U	ug/L
cis-1,3-Dichloropropene	1.0	U	1.0	U	1.0	U	ug/L
4-Methyl-2-pentanone (MIBK)	5.0	U	5.0	U	5.0	U	ug/L
Toluene	1.0	U	1.0	U	1.0	U	ug/L
trans-1,3-Dichloropropene	1.0	U	1.0	U	1.0	U	ug/L
1,1,2-Trichloroethane	1.0	U	1.0	U	1.0	U	ug/L
Tetrachloroethene	1.0	U	1.0	U	1.0	U	ug/L
1,3-Dichloropropane	1.0	U	1.0	U	1.0	U	ug/L
2-Hexanone	5.0	U	5.0	U	5.0	U	ug/L
Dibromochloromethane	1.0	U	1.0	U	1.0	U	ug/L
1,2-Dibromoethane (EDB)	1.0	U	1.0	U	1.0	U	ug/L
Chlorobenzene	10		2.1		21		ug/L
1,1,1,2-Tetrachloroethane	1.0	U	1.0	U	1.0	U	ug/L
Ethylbenzene	1.0	U	1.0	U	1.0	U	ug/L
m&p-Xylenes	2.0	U	2.0	U	2.0	U	ug/L

AAI5-032 Sampling #2 t=29 days

Analyte	Column 4	Column 5	Column 6	Qualifier	Units
	Effluent 40033	Effluent 40034	Effluent 40035		
o-Xylene	1.0	U	1.0	U	ug/L
Styrene	1.0	U	1.0	U	ug/L
Bromoform	1.0	U	1.0	U	ug/L
Isopropylbenzene	1.0	U	1.0	U	ug/L
Bromobenzene	1.0	U	1.0	U	ug/L
1,1,2,2-Tetrachloroethane	1.0	U	1.0	U	ug/L
1,2,3-Trichloropropane	1.0	U	1.0	U	ug/L
n-Propylbenzene	1.0	U	1.0	U	ug/L
2-Chlorotoluene	1.0	U	1.0	U	ug/L
1,3,5-Trimethylbenzene	1.0	U	1.0	U	ug/L
4-Chlorotoluene	1.0	U	1.0	U	ug/L
tert-Butylbenzene	1.0	U	1.0	U	ug/L
1,2,4-Trimethylbenzene	1.0	U	1.0	U	ug/L
sec-Butylbenzene	1.0	U	1.0	U	* ug/L
1,3-Dichlorobenzene	1.0	U	1.0	U	ug/L
p-Isopropyltoluene	1.0	U	1.0	U	ug/L
1,4-Dichlorobenzene	1.3	3.1	1.0	U	ug/L
n-Butylbenzene	1.0	U	1.0	U	ug/L
1,2-Dichlorobenzene	1.0	U	1.0	U	ug/L
1,2-Dibromo-3-chloropropane	1.0	U	1.0	U	ug/L
1,3,5-Trichlorobenzene	1.0	U	1.0	U	ug/L
1,2,4-Trichlorobenzene	1.0	U	1.0	U	ug/L
Hexachlorobutadiene	1.0	U	1.0	U	ug/L
Naphthalene	1.0	U	1.0	U	ug/L
1,2,3-Trichlorobenzene	1.0	U	1.0	U	ug/L

AA15-032 Sampling #2 t=29 days

Analyte	Feed #1	Feed #2		
	40036	Qualifed	40037	Qualifed Units
Alkalinity, Total as CaCO ₃				
Chloride				
TOC Average Duplicates				
Dichlorodifluoromethane	1.0	U	1.0	ug/L
Chloromethane	1.0	U	1.0	ug/L
Vinyl chloride	1.0	U	1.0	ug/L
Bromomethane	1.0	U	1.0	ug/L
Chloroethane	210		750	ug/L
Trichlorofluoromethane	1.0	U	1.0	ug/L
1,1-Dichloroethene	1.0	U	1.0	ug/L
Carbon disulfide	5.0	U	5.0	ug/L
Acetone	5.0	U	5.0	ug/L
Methylene chloride	6.1		1.0	ug/L
trans-1,2-Dichloroethene	1.0	U	1.0	ug/L
Methyl-tert-butyl-ether (MTBE)	1.0	U	1.0	ug/L
1,1-Dichloroethane	1.0	U	1.0	ug/L
2,2-Dichloropropane	1.0	U	1.0	ug/L
cis-1,2-Dichloroethene	1.0	U	1.0	ug/L
2-Butanone (MEK)	5.0	U	5.0	ug/L
Bromochloromethane	1.0	U	1.0	ug/L
Chloroform	1.0	U	1.0	ug/L
1,1,1-Trichloroethane	1.0	U	1.0	ug/L
1,1-Dichloropropene	1.0	U*	1.0	ug/L
Carbon tetrachloride	1.0	U	1.0	ug/L
Benzene	1.0	U	1.0	ug/L
1,2-Dichloroethane	1.0	U	1.0	ug/L
Trichloroethene	1.0	U	1.0	ug/L
1,2-Dichloropropane	1.0	U	1.0	ug/L
Dibromomethane	1.0	U	1.0	ug/L
Bromodichloromethane	1.0	U	1.0	ug/L
cis-1,3-Dichloropropene	1.0	U	1.0	ug/L
4-Methyl-2-pentanone (MIBK)	5.0	U	5.0	ug/L
Toluene	1.0	U	1.0	ug/L
trans-1,3-Dichloropropene	1.0	U	1.0	ug/L
1,1,2-Trichloroethane	1.0	U	1.0	ug/L
Tetrachloroethene	1.0	U	1.0	ug/L
1,3-Dichloropropane	1.0	U	1.0	ug/L
2-Hexanone	5.0	U	5.0	ug/L
Dibromochloromethane	1.0	U	1.0	ug/L
1,2-Dibromoethane (EDB)	1.0	U	1.0	ug/L
Chlorobenzene	160		4.8	ug/L
1,1,1,2-Tetrachloroethane	1.0	U	1.0	ug/L
Ethylbenzene	1.0	U	1.0	ug/L
m&p-Xylenes	2.0	U	2.0	ug/L

AAI5-032 Sampling #2 t=29 days

Analyte	Feed #1		Feed #2		Units
	40036	Qualifier	40037	Qualifier	
o-Xylene	1.0	U	1.0	U	ug/L
Styrene	1.0	U	1.0	U	ug/L
Bromoform	1.0	U	1.0	U	ug/L
Isopropylbenzene	1.0	U	1.0	U	ug/L
Bromobenzene	1.0	U	1.0	U	ug/L
1,1,2,2-Tetrachloroethane	1.0	U	1.0	U	ug/L
1,2,3-Trichloropropane	1.0	U	1.0	U	ug/L
n-Propylbenzene	1.0	U	1.0	U	ug/L
2-Chlorotoluene	1.0	U	1.0	U	ug/L
1,3,5-Trimethylbenzene	1.0	U	1.0	U	ug/L
4-Chlorotoluene	1.0	U	1.0	U	ug/L
tert-Butylbenzene	1.0	U	1.0	U	ug/L
1,2,4-Trimethylbenzene	1.0	U	1.0	U	ug/L
sec-Butylbenzene	1.0	U	1.0	U	ug/L
1,3-Dichlorobenzene	1.0	U	1.0	U	ug/L
p-Isopropyltoluene	1.0	U	1.0	U	ug/L
1,4-Dichlorobenzene	1.0	U	1.0	U	ug/L
n-Butylbenzene	1.0	U	1.0	U	ug/L
1,2-Dichlorobenzene	1.0	U	1.0	U	ug/L
1,2-Dibromo-3-chloropropane	1.0	U	1.0	U	ug/L
1,3,5-Trichlorobenzene	1.0	U	1.0	U	ug/L
1,2,4-Trichlorobenzene	1.0	U	1.0	U	ug/L
Hexachlorobutadiene	1.0	U	1.0	U	ug/L
Naphthalene	1.0	U	1.0	U	ug/L
1,2,3-Trichlorobenzene	1.0	U	1.0	U	ug/L

AAI5-032 Sampling #2 t=29 days

Analyte	Column 1	Column 2	Column 3	Qualif 	Units
	Effluent	Effluent	Effluent		
Alkalinity, Total as CaCO ₃	370	380	420		mg/L
Chloride	80	80	80		mg/L
TOC Average Duplicates	14	100	16		mg/L
Dichlorodifluoromethane	1.0	U	1.0	U	ug/L
Chloromethane	1.0	U	1.0	U	ug/L
Vinyl chloride	1.0	U	1.0	U	ug/L
Bromomethane	1.0	U	1.0	U	ug/L
Chloroethane	700	430	530		ug/L
Trichlorofluoromethane	1.0	U	1.0	U	ug/L
1,1-Dichloroethene	1.0	U	1.0	U	ug/L
Carbon disulfide	5.0	U	5.0	U	ug/L
Acetone	5.0	U	20		ug/L
Methylene chloride	45	39	53		ug/L
trans-1,2-Dichloroethene	1.0	U	1.0	U	ug/L
Methyl-tert-butyl-ether (MTBE)	1.0	U	1.0	U	ug/L
1,1-Dichloroethane	1.0	U	1.0	U	ug/L
2,2-Dichloropropane	1.0	U	1.0	U	ug/L
cis-1,2-Dichloroethene	1.0	U	1.1		ug/L
2-Butanone (MEK)	5.0	U	6.1		ug/L
Bromochloromethane	1.0	U	1.0	U	ug/L
Chloroform	1.0	U	1.0	U	ug/L
1,1,1-Trichloroethane	1.0	U	1.0	U	ug/L
1,1-Dichloropropene	1.0	U*	1.0	U*	ug/L
Carbon tetrachloride	1.0	U	1.0	U	ug/L
Benzene	1.0	U	1.0	U	ug/L
1,2-Dichloroethane	1.0	U	1.2		ug/L
Trichloroethene	1.0	U	5.1		ug/L
1,2-Dichloropropane	1.0	U	1.0	U	ug/L
Dibromomethane	1.0	U	1.0	U	ug/L
Bromodichloromethane	1.0	U	1.0	U	ug/L
cis-1,3-Dichloropropene	1.0	U	1.0	U	ug/L
4-Methyl-2-pentanone (MIBK)	5.0	U	5.0	U	ug/L
Toluene	1.0	U	1.0	U	ug/L
trans-1,3-Dichloropropene	1.0	U	1.0	U	ug/L
1,1,2-Trichloroethane	1.0	U	1.0	U	ug/L
Tetrachloroethene	1.0	U	1.0	U	ug/L
1,3-Dichloropropane	1.0	U	1.0	U	ug/L
2-Hexanone	5.0	U	5.0	U	ug/L
Dibromochloromethane	1.0	U	1.0	U	ug/L
1,2-Dibromoethane (EDB)	1.0	U	1.0	U	ug/L
Chlorobenzene	1.0	U	4.1		ug/L
1,1,1,2-Tetrachloroethane	1.0	U	1.0	U	ug/L
Ethylbenzene	1.0	U	1.0	U	ug/L
m&p-Xylenes	2.0	U	2.0	U	ug/L

AAI5-032 Sampling #2 t=29 days

Analyte	Column 1		Column 2		Column 3		
	Effluent	Qualifier	Effluent	Qualifier	Effluent	Qualifier	Units
o-Xylene	1.0	U	1.0	U	1.0	U	ug/L
Styrene	1.0	U	1.0	U	1.0	U	ug/L
Bromoform	1.0	U	1.0	U	1.0	U	ug/L
Isopropylbenzene	1.0	U	1.0	U	1.0	U	ug/L
Bromobenzene	1.0	U	1.0	U	1.0	U	ug/L
1,1,2,2-Tetrachloroethane	1.0	U	1.0	U	1.0	U	ug/L
1,2,3-Trichloropropane	1.0	U	1.0	U	1.0	U	ug/L
n-Propylbenzene	1.0	U	1.0	U	1.0	U	ug/L
2-Chlorotoluene	1.0	U	1.0	U	1.0	U	ug/L
1,3,5-Trimethylbenzene	1.0	U	1.0	U	1.0	U	ug/L
4-Chlorotoluene	1.0	U	1.0	U	1.0	U	ug/L
tert-Butylbenzene	1.0	U	1.0	U	1.0	U	ug/L
1,2,4-Trimethylbenzene	1.0	U	1.0	U	1.0	U	ug/L
sec-Butylbenzene	1.0	U	1.0	U	1.0	U	ug/L
1,3-Dichlorobenzene	1.0	U	1.0	U	1.0	U	ug/L
p-Isopropyltoluene	1.0	U	1.0	U	1.0	U	ug/L
1,4-Dichlorobenzene	1.0	U	1.0	U	1.0	U	ug/L
n-Butylbenzene	1.0	U	1.0	U	1.0	U	ug/L
1,2-Dichlorobenzene	1.0	U	1.0	U	1.0	U	ug/L
1,2-Dibromo-3-chloropropane	1.0	U	1.0	U	1.0	U	ug/L
1,3,5-Trichlorobenzene	1.0	U	1.0	U	1.0	U	ug/L
1,2,4-Trichlorobenzene	1.0	U	1.0	U	1.0	U	ug/L
Hexachlorobutadiene	1.0	U	1.0	U	1.0	U	ug/L
Naphthalene	1.0	U	1.0	U	1.0	U	ug/L
1,2,3-Trichlorobenzene	1.0	U	1.0	U	1.0	U	ug/L

AA15-032 Sampling #2 t=29 days

Analyte	Column 4 Effluent 40033	Column 5 Effluent 40034	Column 6 Effluent 40035	Qualifie	Qualifie	Qualifie	Units
Alkalinity, Total as CaCO ₃	330	420	370				mg/L
Chloride	84	86	100				mg/L
TOC Average Duplicates	120	13	16				mg/L
Dichlorodifluoromethane	1.0	U	1.0	U	1.0	U	ug/L
Chloromethane	1.0	U	1.0	U	1.0	U	ug/L
Vinyl chloride	1.0	U	1.0	U	1.0	U	ug/L
Bromomethane	1.0	U	1.0	U	1.0	U	ug/L
Chloroethane	590	640	600				ug/L
Trichlorofluoromethane	1.0	U	1.0	U	1.0	U	ug/L
1,1-Dichloroethene	1.0	U	1.0	U	1.0	U	ug/L
Carbon disulfide	5.0	U	5.0	U	5.0	U	ug/L
Acetone	17		11				ug/L
Methylene chloride	140	88	47				ug/L
trans-1,2-Dichloroethene	1.0	U	1.0	U	1.0	U	ug/L
Methyl-tert-butyl-ether (MTBE)	1.0	U	1.0	U	1.0	U	ug/L
1,1-Dichloroethane	1.0	U	1.0	U	1.0	U	ug/L
2,2-Dichloropropane	1.0	U	1.0	U	1.0	U	ug/L
cis-1,2-Dichloroethene	1.0	U	1.0	U	1.0	U	ug/L
2-Butanone (MEK)	23		5.0	U	5.0	U	ug/L
Bromochloromethane	1.0	U	1.0	U	1.0	U	ug/L
Chloroform	1.0	U	1.0	U	1.0	U	ug/L
1,1,1-Trichloroethane	1.0	U	1.0	U	1.0	U	ug/L
1,1-Dichloropropene	1.0	U*	1.0	U*	1.0	U*	ug/L
Carbon tetrachloride	1.0	U	1.0	U	1.0	U	ug/L
Benzene	1.0	U	1.0	U	1.0	U	ug/L
1,2-Dichloroethane	3.1		1.0	U	1.0	U	ug/L
Trichloroethene	1.0	U	1.0	U	1.0	U	ug/L
1,2-Dichloropropane	1.0	U	1.0	U	1.0	U	ug/L
Dibromomethane	1.0	U	1.0	U	1.0	U	ug/L
Bromodichloromethane	1.0	U	1.0	U	1.0	U	ug/L
cis-1,3-Dichloropropene	1.0	U	1.0	U	1.0	U	ug/L
4-Methyl-2-pentanone (MIBK)	5.0	U	5.0	U	5.0	U	ug/L
Toluene	1.0	U	1.0	U	1.0	U	ug/L
trans-1,3-Dichloropropene	1.0	U	1.0	U	1.0	U	ug/L
1,1,2-Trichloroethane	1.0	U	1.0	U	1.0	U	ug/L
Tetrachloroethene	1.0	U	1.0	U	1.0	U	ug/L
1,3-Dichloropropane	1.0	U	1.0	U	1.0	U	ug/L
2-Hexanone	5.0	U	5.0	U	5.0	U	ug/L
Dibromochloromethane	1.0	U	1.0	U	1.0	U	ug/L
1,2-Dibromoethane (EDB)	1.0	U	1.0	U	1.0	U	ug/L
Chlorobenzene	10		2.1		21		ug/L
1,1,1,2-Tetrachloroethane	1.0	U	1.0	U	1.0	U	ug/L
Ethylbenzene	1.0	U	1.0	U	1.0	U	ug/L
m&p-Xylenes	2.0	U	2.0	U	2.0	U	ug/L

AA15-032 Sampling #2 t=29 days

Analyte	Column 4 Effluent		Column 5 Effluent		Column 6 Effluent		Units
	40033	Qualified	40034	Qualified	40035	Qualified	
o-Xylene	1.0	U	1.0	U	1.0	U	ug/L
Styrene	1.0	U	1.0	U	1.0	U	ug/L
Bromoform	1.0	U	1.0	U	1.0	U	ug/L
Isopropylbenzene	1.0	U	1.0	U	1.0	U	ug/L
Bromobenzene	1.0	U	1.0	U	1.0	U	ug/L
1,1,2,2-Tetrachloroethane	1.0	U	1.0	U	1.0	U	ug/L
1,2,3-Trichloropropane	1.0	U	1.0	U	1.0	U	ug/L
n-Propylbenzene	1.0	U	1.0	U	1.0	U	ug/L
2-Chlorotoluene	1.0	U	1.0	U	1.0	U	ug/L
1,3,5-Trimethylbenzene	1.0	U	1.0	U	1.0	U	ug/L
4-Chlorotoluene	1.0	U	1.0	U	1.0	U	ug/L
tert-Butylbenzene	1.0	U	1.0	U	1.0	U	ug/L
1,2,4-Trimethylbenzene	1.0	U	1.0	U	1.0	U	ug/L
sec-Butylbenzene	1.0	U	1.0	U	1.0	U	ug/L
1,3-Dichlorobenzene	1.0	U	1.0	U	1.0	U	ug/L
p-Isopropyltoluene	1.0	U	1.0	U	1.0	U	ug/L
1,4-Dichlorobenzene	1.3		3.1		1.0	U	ug/L
n-Butylbenzene	1.0	U	1.0	U	1.0	U	ug/L
1,2-Dichlorobenzene	1.0	U	1.0	U	1.0	U	ug/L
1,2-Dibromo-3-chloropropane	1.0	U	1.0	U	1.0	U	ug/L
1,3,5-Trichlorobenzene	1.0	U	1.0	U	1.0	U	ug/L
1,2,4-Trichlorobenzene	1.0	U	1.0	U	1.0	U	ug/L
Hexachlorobutadiene	1.0	U	1.0	U	1.0	U	ug/L
Naphthalene	1.0	U	1.0	U	1.0	U	ug/L
1,2,3-Trichlorobenzene	1.0	U	1.0	U	1.0	U	ug/L

AA15-032 Sampling #2 t=29 days

Analyte	Feed #1		Feed #2	
	40036	Qualifc	40037	Qualifc Units
Alkalinity, Total as CaCO ₃				
Chloride				
TOC Average Duplicates				
Dichlorodifluoromethane	1.0	U	1.0	ug/L
Chloromethane	1.0	U	1.0	ug/L
Vinyl chloride	1.0	U	1.0	ug/L
Bromomethane	1.0	U	1.0	ug/L
Chloroethane	210		750	ug/L
Trichlorofluoromethane	1.0	U	1.0	ug/L
1,1-Dichloroethene	1.0	U	1.0	ug/L
Carbon disulfide	5.0	U	5.0	ug/L
Acetone	5.0	U	5.0	ug/L
Methylene chloride	6.1		1.0	ug/L
trans-1,2-Dichloroethene	1.0	U	1.0	ug/L
Methyl-tert-butyl-ether (MTBE)	1.0	U	1.0	ug/L
1,1-Dichloroethane	1.0	U	1.0	ug/L
2,2-Dichloropropane	1.0	U	1.0	ug/L
cis-1,2-Dichloroethene	1.0	U	1.0	ug/L
2-Butanone (MEK)	5.0	U	5.0	ug/L
Bromochloromethane	1.0	U	1.0	ug/L
Chloroform	1.0	U	1.0	ug/L
1,1,1-Trichloroethane	1.0	U	1.0	ug/L
1,1-Dichloropropene	1.0	U*	1.0	ug/L
Carbon tetrachloride	1.0	U	1.0	ug/L
Benzene	1.0	U	1.0	ug/L
1,2-Dichloroethane	1.0	U	1.0	ug/L
Trichloroethene	1.0	U	1.0	ug/L
1,2-Dichloropropane	1.0	U	1.0	ug/L
Dibromomethane	1.0	U	1.0	ug/L
Bromodichloromethane	1.0	U	1.0	ug/L
cis-1,3-Dichloropropene	1.0	U	1.0	ug/L
4-Methyl-2-pentanone (MIBK)	5.0	U	5.0	ug/L
Toluene	1.0	U	1.0	ug/L
trans-1,3-Dichloropropene	1.0	U	1.0	ug/L
1,1,2-Trichloroethane	1.0	U	1.0	ug/L
Tetrachloroethene	1.0	U	1.0	ug/L
1,3-Dichloropropane	1.0	U	1.0	ug/L
2-Hexanone	5.0	U	5.0	ug/L
Dibromochloromethane	1.0	U	1.0	ug/L
1,2-Dibromoethane (EDB)	1.0	U	1.0	ug/L
Chlorobenzene	160		4.8	ug/L
1,1,1,2-Tetrachloroethane	1.0	U	1.0	ug/L
Ethylbenzene	1.0	U	1.0	ug/L
m&p-Xylenes	2.0	U	2.0	ug/L

AAI5-032 Sampling #2 t=29 days

Analyte	Feed #1	Feed #2	Qualifier	Qualifier	Units
	40036	40037			
o-Xylene	1.0	U	1.0	U	ug/L
Styrene	1.0	U	1.0	U	ug/L
Bromoform	1.0	U	1.0	U	ug/L
Isopropylbenzene	1.0	U	1.0	U	ug/L
Bromobenzene	1.0	U	1.0	U	ug/L
1,1,2,2-Tetrachloroethane	1.0	U	1.0	U	ug/L
1,2,3-Trichloropropane	1.0	U	1.0	U	ug/L
n-Propylbenzene	1.0	U	1.0	U	ug/L
2-Chlorotoluene	1.0	U	1.0	U	ug/L
1,3,5-Trimethylbenzene	1.0	U	1.0	U	ug/L
4-Chlorotoluene	1.0	U	1.0	U	ug/L
tert-Butylbenzene	1.0	U	1.0	U	ug/L
1,2,4-Trimethylbenzene	1.0	U	1.0	U	ug/L
sec-Butylbenzene	1.0	U	1.0	U	ug/L
1,3-Dichlorobenzene	1.0	U	1.0	U	ug/L
p-Isopropyltoluene	1.0	U	1.0	U	ug/L
1,4-Dichlorobenzene	1.0	U	1.0	U	ug/L
n-Butylbenzene	1.0	U	1.0	U	ug/L
1,2-Dichlorobenzene	1.0	U	1.0	U	ug/L
1,2-Dibromo-3-chloropropane	1.0	U	1.0	U	ug/L
1,3,5-Trichlorobenzene	1.0	U	1.0	U	ug/L
1,2,4-Trichlorobenzene	1.0	U	1.0	U	ug/L
Hexachlorobutadiene	1.0	U	1.0	U	ug/L
Naphthalene	1.0	U	1.0	U	ug/L
1,2,3-Trichlorobenzene	1.0	U	1.0	U	ug/L

AA15-032 Sampling #3 t= 42 days

Analyte	Column 1 Effluent 40168	Column 2 Effluent 40169	Column 3 Effluent 40170	Qualifie	Qualifie	Qualifie Units
Alkalinity, Total as CaCO ₃	330	300	370			mg/L
Chloride	90	84	84			mg/L
TOC Average Duplicates	9.6	12	9.9			mg/L
Dichlorodifluoromethane	1.0	U*	1.0	U*	1.0	U* ug/L
Chloromethane	1.0	U*	1.0	U*	1.0	U* ug/L
Vinyl chloride	1.0	U*	1.0	U*	1.0	U* ug/L
Bromomethane	1.0	U*	1.0	U*	1.0	U* ug/L
Chloroethane	230	200	350	H		ug/L
Trichlorofluoromethane	1.0	U*	1.0	U*	1.0	U* ug/L
1,1-Dichloroethene	1.0	U	1.0	U	1.0	U ug/L
Carbon disulfide	5.0	U	5.0	U	5.0	U ug/L
Acetone	5.0	U*	5.0	U*	5.0	U* ug/L
Methylene chloride	16	25	44			ug/L
trans-1,2-Dichloroethene	1.0	U	1.0	U	1.0	U ug/L
Methyl-tert-butyl-ether (MTBE)	1.0	U	1.0	U	1.0	U ug/L
1,1-Dichloroethane	1.0	U	1.0	U	1.0	U ug/L
2,2-Dichloropropane	1.0	U	1.0	U	1.0	U ug/L
cis-1,2-Dichloroethene	1.0	U	1.3		1.0	U ug/L
2-Butanone (MEK)	5.0	U	5.0	U	5.0	U ug/L
Bromoform	1.0	U	1.0	U	1.0	U ug/L
1,1,1-Trichloroethane	1.0	U	1.0	U	1.0	U ug/L
1,1-Dichloropropene	1.0	U	1.0	U	1.0	U ug/L
Carbon tetrachloride	1.0	U	1.0	U	1.0	U ug/L
Benzene	1.0	U	1.0	U	1.0	U ug/L
1,2-Dichloroethane	1.0	U	1.0	U	1.0	U ug/L
Trichloroethene	1.0	U	2.7		1.0	U ug/L
1,2-Dichloropropane	1.0	U	1.0	U	1.0	U ug/L
Dibromomethane	1.0	U	1.0	U	1.0	U ug/L
Bromodichloromethane	1.0	U	1.0	U	1.0	U ug/L
cis-1,3-Dichloropropene	1.0	U	1.0	U	1.0	U ug/L
4-Methyl-2-pentanone (MIBK)	5.0	U	5.0	U	5.0	U ug/L
Toluene	1.0	U	1.0	U	1.0	U ug/L
trans-1,3-Dichloropropene	1.0	U	1.0	U	1.0	U ug/L
1,1,2-Trichloroethane	1.0	U	1.0	U	1.0	U ug/L
Tetrachloroethene	1.0	U	1.0	U	1.0	U ug/L
1,3-Dichloropropane	1.0	U	1.0	U	1.0	U ug/L
2-Hexanone	5.0	U	5.0	U	5.0	U ug/L
Dibromochloromethane	1.0	U	1.0	U	1.0	U ug/L
1,2-Dibromoethane (EDB)	1.0	U	1.0	U	1.0	U ug/L
Chlorobenzene	1.0	U	1.0	U	1.0	U ug/L
1,1,1,2-Tetrachloroethane	1.0	U	1.0	U	1.0	U ug/L
Ethylbenzene	1.0	U	1.0	U	1.0	U ug/L
m&p-Xylenes	2.0	U	2.0	U	2.0	U ug/L

AA15-032 Sampling #3 t= 42 days

Analyte	Column 1		Column 2		Column 3		Qualifc	Units
	Effluent	40168	Effluent	40169	Effluent	40170		
o-Xylene	1.0	U	1.0	U	1.0	U	ug/L	
Styrene	1.0	U	1.0	U	1.0	U	ug/L	
Bromoform	1.0	U	1.0	U	1.0	U	ug/L	
Isopropylbenzene	1.0	U	1.0	U	1.0	U	ug/L	
Bromobenzene	1.0	U	1.0	U	1.0	U	ug/L	
1,1,2,2-Tetrachloroethane	1.0	U	1.0	U	1.0	U	ug/L	
1,2,3-Trichloropropane	1.0	U	1.0	U	1.0	U	ug/L	
n-Propylbenzene	1.0	U	1.0	U	1.0	U	ug/L	
2-Chlorotoluene	1.0	U	1.0	U	1.0	U	ug/L	
1,3,5-Trimethylbenzene	1.0	U	1.0	U	1.0	U	ug/L	
4-Chlorotoluene	1.0	U	1.0	U	1.0	U	ug/L	
tert-Butylbenzene	1.0	U	1.0	U	1.0	U	ug/L	
1,2,4-Trimethylbenzene	1.0	U	1.0	U	1.0	U	ug/L	
sec-Butylbenzene	1.0	U	1.0	U	1.0	U	ug/L	
1,3-Dichlorobenzene	1.0	U	1.0	U	1.0	U	ug/L	
p-Isopropyltoluene	1.0	U	1.0	U	1.0	U	ug/L	
1,4-Dichlorobenzene	1.0	U	1.1		1.0	U	ug/L	
n-Butylbenzene	1.0	U	1.0	U	1.0	U	ug/L	
1,2-Dichlorobenzene	1.0	U	1.0	U	1.0	U	ug/L	
1,2-Dibromo-3-chloropropane	1.0	U	1.0	U	1.0	U	ug/L	
1,3,5-Trichlorobenzene	1.0	U	1.0	U	1.0	U	ug/L	
1,2,4-Trichlorobenzene	1.0	U	1.0	U	1.0	U	ug/L	
Hexachlorobutadiene	1.0	U	1.0	U	1.0	U	ug/L	
Naphthalene	1.0	U	1.0	U	1.0	U	ug/L	
1,2,3-Trichlorobenzene	1.0	U	1.0	U	1.0	U	ug/L	

AAI5-032 Sampling #3 t= 42 days

Analyte	Column 4 Effluent 40171	Qualifed	Column 5 Effluent 40172	Qualifed	Column 6 Effluent 40173	Qualifed	Units
Alkalinity, Total as CaCO ₃	330		380		350		mg/L
Chloride	91		84		92		mg/L
TOC Average Duplicates	11		9.5		11		mg/L
Dichlorodifluoromethane	1.0	U*	1.0	U*	1.0	U*	ug/L
Chloromethane	1.0	U*	1.0	U*	1.0	U*	ug/L
Vinyl chloride	1.0	U*	1.0	U*	1.0	U*	ug/L
Bromomethane	1.0	U*	1.0	U*	1.0	U*	ug/L
Chloroethane	290		400		510		ug/L
Trichlorofluoromethane	1.0	U*	1.0	U*	1.0	U*	ug/L
1,1-Dichloroethene	1.0	U	1.0	U	1.0	U	ug/L
Carbon disulfide	5.0	U	5.0	U	5.0	U	ug/L
Acetone	5.0	U*	5.0	U*	5.0	U*	ug/L
Methylene chloride	60		73		41		ug/L
trans-1,2-Dichloroethene	1.0	U	1.0	U	1.0	U	ug/L
Methyl-tert-butyl-ether (MTBE)	1.0	U	1.0	U	1.0	U	ug/L
1,1-Dichloroethane	1.0	U	1.0	U	1.0	U	ug/L
2,2-Dichloropropane	1.0	U	1.0	U	1.0	U	ug/L
cis-1,2-Dichloroethene	1.0	U	1.0	U	1.0	U	ug/L
2-Butanone (MEK)	5.0	U	5.0	U	5.0	U	ug/L
Bromoform	1.0	U	1.0	U	1.0	U	ug/L
1,1,1-Trichloroethane	1.0	U	1.0	U	1.0	U	ug/L
1,1-Dichloropropene	1.0	U	1.0	U	1.0	U	ug/L
Carbon tetrachloride	1.0	U	1.0	U	1.0	U	ug/L
Benzene	1.0	U	1.0	U	1.0	U	ug/L
1,2-Dichloroethane	1.5	H	1.0	U	1.0	U	ug/L
Trichloroethene	1.0	U	1.0	U	1.0	U	ug/L
1,2-Dichloropropane	1.0	U	1.0	U	1.0	U	ug/L
Dibromomethane	1.0	U	1.0	U	1.0	U	ug/L
Bromodichloromethane	1.0	U	1.0	U	1.0	U	ug/L
cis-1,3-Dichloropropene	1.0	U	1.0	U	1.0	U	ug/L
4-Methyl-2-pentanone (MIBK)	5.0	U	5.0	U	5.0	U	ug/L
Toluene	1.0	U	1.0	U	1.0	U	ug/L
trans-1,3-Dichloropropene	1.0	U	1.0	U	1.0	U	ug/L
1,1,2-Trichloroethane	1.0	U	1.0	U	1.0	U	ug/L
Tetrachloroethene	1.0	U	1.0	U	1.0	U	ug/L
1,3-Dichloropropane	1.0	U	1.0	U	1.0	U	ug/L
2-Hexanone	5.0	U	5.0	U	5.0	U	ug/L
Dibromochloromethane	1.0	U	1.0	U	1.0	U	ug/L
1,2-Dibromoethane (EDB)	1.0	U	1.0	U	1.0	U	ug/L
Chlorobenzene	1.0	U	1.0	U	26	H	ug/L
1,1,1,2-Tetrachloroethane	1.0	U	1.0	U	1.0	U	ug/L
Ethylbenzene	1.0	U	1.0	U	1.0	U	ug/L
m&p-Xylenes	2.0	U	2.0	U	2.0	U	ug/L

AAI5-032 Sampling #3 t= 42 days

Analyte	Column 4		Column 5		Column 6		Qualifie Units
	Effluent	40171	Effluent	40172	Effluent	40173	
o-Xylene		1.0	U	1.0	U	1.0	U ug/L
Styrene		1.0	U	1.0	U	1.0	U ug/L
Bromoform		1.0	U	1.0	U	1.0	U ug/L
Isopropylbenzene		1.0	U	1.0	U	1.0	U ug/L
Bromobenzene		1.0	U	1.0	U	1.0	U ug/L
1,1,2,2-Tetrachloroethane		1.0	U	1.0	U	1.0	U ug/L
1,2,3-Trichloropropane		1.0	U	1.0	U	1.0	U ug/L
n-Propylbenzene		1.0	U	1.0	U	1.0	U ug/L
2-Chlorotoluene		1.0	U	1.0	U	1.0	U ug/L
1,3,5-Trimethylbenzene		1.0	U	1.0	U	1.0	U ug/L
4-Chlorotoluene		1.0	U	1.0	U	1.0	U ug/L
tert-Butylbenzene		1.0	U	1.0	U	1.0	U ug/L
1,2,4-Trimethylbenzene		1.0	U	1.0	U	1.0	U ug/L
sec-Butylbenzene		1.0	U	1.0	U	1.0	U ug/L
1,3-Dichlorobenzene		1.0	U	1.0	U	1.0	U ug/L
p-Isopropyltoluene		1.0	U	1.0	U	1.0	U ug/L
1,4-Dichlorobenzene		1.8		1.0	U	1.0	U ug/L
n-Butylbenzene		1.0	U	1.0	U	1.0	U ug/L
1,2-Dichlorobenzene		1.0	U	1.0	U	1.0	U ug/L
1,2-Dibromo-3-chloropropane		1.0	U	1.0	U	1.0	U ug/L
1,3,5-Trichlorobenzene		1.0	U	1.0	U	1.0	U ug/L
1,2,4-Trichlorobenzene		1.0	U	1.0	U	1.0	U ug/L
Hexachlorobutadiene		1.0	U	1.0	U	1.0	U ug/L
Naphthalene		1.0	U	1.0	U	1.0	U ug/L
1,2,3-Trichlorobenzene		1.0	U	1.0	U	1.0	U ug/L

AA15-032 Sampling #3 t= 42 days

Analyte	Feed #1 40174	Qualifie 40175	Feed #2 40175	Qualifie Units
Alkalinity, Total as CaCO₃				
Chloride				
TOC Average Duplicates				
Dichlorodifluoromethane	1.0	U*	1.0	ug/L
Chloromethane	1.0	U*	1.0	ug/L
Vinyl chloride	1.0	U*	1.0	ug/L
Bromomethane	1.0	U*	1.0	ug/L
Chloroethane	310		280	ug/L
Trichlorofluoromethane	1.0	U*	1.0	ug/L
1,1-Dichloroethene	1.0	U	1.0	ug/L
Carbon disulfide	5.0	U	5.0	ug/L
Acetone	5.0	U*	5.0	ug/L
Methylene chloride	1.0	U	1.0	ug/L
trans-1,2-Dichloroethene	1.0	U	1.0	ug/L
Methyl-tert-butyl-ether (MTBE)	1.0	U	1.0	ug/L
1,1-Dichloroethane	1.0	U	1.0	ug/L
2,2-Dichloropropane	1.0	U	1.0	ug/L
cis-1,2-Dichloroethene	1.0	U	1.0	ug/L
2-Butanone (MEK)	5.0	U	5.0	ug/L
Bromochloromethane	1.0	U	1.0	ug/L
Chloroform	1.0	U	1.0	ug/L
1,1,1-Trichloroethane	1.0	U	1.0	ug/L
1,1-Dichloropropene	1.0	U	1.0	ug/L
Carbon tetrachloride	1.0	U	1.0	ug/L
Benzene	1.0	U	1.0	ug/L
1,2-Dichloroethane	1.0	U	1.0	ug/L
Trichloroethene	1.4		1.5	ug/L
1,2-Dichloropropane	1.0	U	1.0	ug/L
Dibromomethane	1.0	U	1.0	ug/L
Bromodichloromethane	1.0	U	1.0	ug/L
cis-1,3-Dichloropropene	1.0	U	1.0	ug/L
4-Methyl-2-pentanone (MIBK)	5.0	U	5.0	ug/L
Toluene	1.0	U	1.0	ug/L
trans-1,3-Dichloropropene	1.0	U	1.0	ug/L
1,1,2-Trichloroethane	1.0	U	1.0	ug/L
Tetrachloroethene	1.0	U	1.0	ug/L
1,3-Dichloropropane	1.0	U	1.0	ug/L
2-Hexanone	5.0	U	5.0	ug/L
Dibromochloromethane	1.0	U	1.0	ug/L
1,2-Dibromoethane (EDB)	1.0	U	1.0	ug/L
Chlorobenzene	11	H	8.7	ug/L
1,1,1,2-Tetrachloroethane	1.0	U	1.0	ug/L
Ethylbenzene	1.0	U	1.0	ug/L
m&p-Xylenes	2.0	U	2.0	ug/L

AAI5-032 Sampling #3 t= 42 days

Analyte	Feed #1		Feed #2		Qualifie Units
	40174	Qualifie	40175	Qualifie	
o-Xylene	1.0	U	1.0	U	ug/L
Styrene	1.0	U	1.0	U	ug/L
Bromoform	1.0	U	1.0	U	ug/L
Isopropylbenzene	1.0	U	1.0	U	ug/L
Bromobenzene	1.0	U	1.0	U	ug/L
1,1,2,2-Tetrachloroethane	1.0	U	1.0	U	ug/L
1,2,3-Trichloropropane	1.0	U	1.0	U	ug/L
n-Propylbenzene	1.0	U	1.0	U	ug/L
2-Chlorotoluene	1.0	U	1.0	U	ug/L
1,3,5-Trimethylbenzene	1.0	U	1.0	U	ug/L
4-Chlorotoluene	1.0	U	1.0	U	ug/L
tert-Butylbenzene	1.0	U	1.0	U	ug/L
1,2,4-Trimethylbenzene	1.0	U	1.0	U	ug/L
sec-Butylbenzene	1.0	U	1.0	U	ug/L
1,3-Dichlorobenzene	1.0	U	1.0	U	ug/L
p-Isopropyltoluene	1.0	U	1.0	U	ug/L
1,4-Dichlorobenzene	1.0	U	1.0	U	ug/L
n-Butylbenzene	1.0	U	1.0	U	ug/L
1,2-Dichlorobenzene	1.0	U	1.0	U	ug/L
1,2-Dibromo-3-chloropropane	1.0	U	1.0	U	ug/L
1,3,5-Trichlorobenzene	1.0	U	1.0	U	ug/L
1,2,4-Trichlorobenzene	1.0	U	1.0	U	ug/L
Hexachlorobutadiene	1.0	U	1.0	U	ug/L
Naphthalene	1.0	U	1.0	U	ug/L
1,2,3-Trichlorobenzene	1.0	U	1.0	U	ug/L

AA15-032 Sampling #5 t = 94 days

Analyte	DL	0.1% EHC2007Fe50		0.5% EHC2007Fe50		0.1% HRC 40840	0.5% HRC 40841	Control 40842	Sterile Control 40843	Feed #1 40844	Feed #2 - Sterile 40845	Feed #2 - Sterile 40845 D	Feed #2 - Sterile 40845 Avg
		40838	40839	40840	40841								
Vinyl Chloride	VC	10.0	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Dichloromethane	DCM	10.0	230	260	185	ND	415	345	ND	ND	ND	ND	ND
Cis-1,2-Dichloroethene	cis-DCE	10.0	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Chloroform	CF	10.0	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Carbon Tetrachloride	CT	14.0	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,2-Dichloroethane	1,2DCA	10.0	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Trichloroethene	TCE	10.0	20	20	15	20	ND	25	15	20	17.5		
Tetrachloroethene	PCE	20.0	ND	ND	ND	ND	ND	20	135	135	0	67.5	
Chloroethane	CA	10.0	485	500	380	0	810	1280	1005	1330	1360	1345	
Total VOCs		735	780	585	15		1,245	1,845	1,165	1,480	1,380	1,430	

AA15-032 Sampling #6 t = 107 days

Analyte	DL	0.1%	0.5%	0.1% HRC	0.5% HRC	Control	Sterile	Feed #1	Feed #2 -	Feed #2 -	Feed #2 -
		EHC2007Fe50	EHC2007Fe50				Control	Feed #1	Sterile	Feed #2 - Sterile	Feed #2 - Sterile
Vinyl Chloride	VC	10.0	ND	ND	ND	ND	ND	ND	ND	ND	ND
Dichloromethane	DCM	10.0	145	120	100	165	220	185	0	0	0
Cis-1,2-Dichloroethene	cis-DCE	10.0	ND	ND	ND	ND	ND	ND	ND	ND	ND
Chloroform	CF	10.0	ND	ND	ND	ND	ND	ND	ND	ND	ND
Carbon Tetrachloride	CT	14.0	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,2-Dichloroethane	1,2DCA	10.0	ND	ND	ND	ND	ND	ND	ND	ND	ND
Trichloroethene	TCE	10.0	10	10	15	ND	10	ND	40	20	20
Tetrachloroethene	PCE	20.0	0	45	0	0	15	65	45	15	20
Chloroethane	CA	10.0	305	250	80	5	270	960	2245	1540	1355
Total VOCs		460	425	195	100	515	1,210	2,330	1,575	1,385	1,485



ADVENTUS
AMERICAS

VIA E-MAIL: mark_becker@urscorp.com

August 03, 2005

Mr. Mark Becker
Project Manager
URS Corp.
12 Commerce Drive
Cranford, NJ 07016

**SUBJECT: Final Report – Bench Scale Test For Chemical Oxidation Treatment of
Chlorinated Solvent Impacted Soils
Adventus Project No. AAI5-031**

Dear Mr. Becker,

This document constitutes the final report for the chemical oxidation treatment of chlorinated solvent impacted soils from the Former Columbia Cement, Inc., Freeport, NY (the Site). This report presents the results of the initial characterization of the Site soil and water, and the results of the activated persulfate testing.

Sample Reception

On April 27, 2005 Adventus received one (five gallon) pail of soil (SB-042005) and one (five-gallon) pail of water (MW-ID-97) from the Site. Both pails were placed into cold room storage upon receipt.

On April 28, 2005 the soil was homogenized by hand and duplicate samples were collected for volatile organic compounds (VOC), total organic carbon (TOC), and chemical oxygen demand (COD) analyses. A composite sample of water was also collected and submitted for VOC, TOC, and COD analyses. All samples were shipped via overnight courier to Severn Trent Laboratories (STL) – Chicago for analysis.

A natural oxidant demand (NOD) test was also conducted on a sample of the Site soil using a standard NOD protocol (**Appendix A**).

Initial Soil and Groundwater Characterization Results

The initial VOC, TOC, and COD concentrations in the Site soil and water samples are presented in **Table 1**. The main VOC present in the Site soil was 1,1,1-trichloroethane (TCA) (135,500 µg/kg). Nine other VOCs were detected in the soil at much lower concentrations (**Table 1**). The TOC and COD concentrations were 5,250 mg/kg and 18,000 mg/kg, respectively.

The Site water contained trace concentrations of chloroethane (4.8 µg/L) and 1,1-dichloroethane (1 µg/L). TOC and COD concentrations were 11µg/L and 33µg/L, respectively.

The calculated soil Natural Oxidant Demand (NOD) was 42 mg KMnO₄ per gram of soil.

Table 1: Initial VOC and COD concentrations in the Site soil and water samples

Parameter	Soil¹	Units	Water	Units
Chloroethane	ND (120)	µg/kg	4.8	µg/L
1,1-Dichloroethane	525	µg/kg	1.0	µg/L
1,1,1-Trichloroethane	135,500	µg/kg	ND (1)	µg/L
Trichloroethene	60	µg/kg	ND (1)	µg/L
Toluene	825	µg/kg	ND (1)	µg/L
Tetrachloroethene	80	µg/kg	ND (1)	µg/L
Ethylbenzene	60	µg/kg	ND (1)	µg/L
m&p-Xylene	265	µg/kg	ND (2)	µg/L
o-Xylene	114	µg/kg	ND (1)	µg/L
p-Isopropyltoluene	80	µg/kg	ND (1)	µg/L
Naphthalene	60	µg/kg	ND (1)	µg/L
Total VOCs	137,569	µg/g	5.8	µg/L
TOC	5,250	mg/kg	11	mg/L
COD	18,000	mg/kg	33	mg/L

¹Average of duplicate samples

ND = non detect (detection limit)

Experimental Procedure

Based on the mix of target compounds, activated persulfate was selected as the oxidant of choice. Two activation methods (hydrogen peroxide and chelated iron) were tested. Treatment was conducted on combined soil and groundwater samples from the site.

Approximately 300 g of the homogenized site soil was weighed out into 12 – 1L glass jars with Teflon lined lids. The initial characterization revealed that the VOCs concentrations in

the Site water were much lower than the concentrations present at the site, thus the Site water was spiked with seven constituents of interest (COI) as outlined in **Table 2**.

Table 2: Initial and Target COI concentrations in the Site water

Parameter	Site Water Received April 27 th	Target Concentration	Units
Vinyl Chloride	ND (1)	15	µg/L
Chloroethane	4.8	10,000	µg/L
Methylene Chloride	ND (1)	10	µg/L
1,1-Dichloroethane	1.0	660	µg/L
1,1,1-Trichloroethane	ND (1)	150	µg/L
Benzene	ND (1)	15	µg/L
Toluene	ND (1)	4	µg/L

Table 3 summarizes the persulfate treatments and sampling schedule for each jar. Jars 1, 4, 7, and 10 were controls and thus were filled with spiked Site water. Jars 2, 3, 5, and 6 were filled with a solution of spiked Site water containing 6.3 g/L persulfate ($\text{Na}_2\text{S}_2\text{O}_8$) and 30 g/L 30% hydrogen peroxide (H_2O_2). Jars 8, 9, 11 and 12 were filled with a solution of spiked Site water containing 6.3 g/L sodium persulfate ($\text{Na}_2\text{S}_2\text{O}_8$) and 0.5 g/L ethylenediaminetetraacetic acid iron (III) sodium salt (NaFe(III)EDTA). The jars were inverted several times to mix the soil and water and were placed into an insulated box.

On day 2 (48 hrs after the first application of sodium persulfate), the water and soil in jars 1, 2, 3, 7, 8 and 9 were sampled for VOC, and COD at STL-Chicago. The water was also sampled for persulfate and analyzed by Adventus.

Jars 5, 6, 11, and 12 were re-amended with persulfate and the appropriate activator on day 2. For jars 5 and 6 the 6.3 g of persulfate was dissolved in 30 g of 30% H_2O_2 and then added to the treatment jar. For jars 11 and 12 approximately 40 mL of water was removed from the treatment jar and the 6.3 g of persulfate and 0.5 g of NaFe(III)EDTA were dissolved in this solution and then returned to the treatment jar.

On day 6 (96 hours after the second application of sodium persulfate) the water and soil for the remaining jars were sampled as outlined above for day 2.

Table 3: Summary of Treatments

Jars	Persulfate Addition	Persulfate Activator	Sampling
1,4,7,10	None	None	Jars 1 and 7 sampled on Day 2 Jars 4 and 10 sampled on Day 4
2,3	6.3 g on Day 0	H_2O_2	Sampled on Day 2
5,6	6.3 g on Days 0 & 6	H_2O_2	Sampled on Day 6
8,9	6.3 g on Day 0	NaFe(III)EDTA	Sampled on Day 2
11,12	6.3 g on Days 0 & 6	NaFe(III)EDTA	Sampled on Day 6

Results

This section presents the total VOC, COD, and persulfate results of the sodium persulfate batch tests. With the exception of the controls, all other results reported in this section are the average of duplicate treatment jars. The complete analytical data set is included in Appendices B, C, D, and E.

The soil VOC concentrations in all four-control jars were much lower than the initial characterization result. The lower concentrations in the controls may be attributed to partitioning of COIs into the aqueous phase or a hot spot may have been sampled during the initial characterization.

Hydrogen Peroxide Activated Persulfate Treatment

The soil and water results from the persulfate treatment jars activated with hydrogen peroxide are presented in **Tables 4** and **5**. On day 2 the soil VOC concentrations decreased from 2,779 µg/kg in the control to 1,439 µg/kg in response to 6.3 g/L persulfate and 30 g/L of H₂O₂. After an additional 6.3 g/L of persulfate, 30 g/L of 30% H₂O₂ (equivalent to 9 g of H₂O₂) and a four day incubation period, the soil VOC concentrations decreased from 2,275 µg/kg in the control to 502 µg/kg. This corresponded to 48% and 78% removals of total VOC after 2 and 6 days of hydrogen peroxide activated persulfate treatment, respectively.

The COD concentrations were reduced by 57% and 47%, on days 2 and 6 respectively, in response to the persulfate treatment.

Table 4: VOC and COD concentrations in soil following H₂O₂ activated persulfate treatment

Parameter	Day 2			Day 6		
	Control	6.3 g Na ₂ S ₂ O ₈	% Removal After 2 Days	Control	12.6 g Na ₂ S ₂ O ₈	% Removal After 6 Days
Total VOC (µg/kg)	2,779	1,439	48%	2,275	502	78%
COD (mg/kg)	20,000	8,550	57%	9,100	4,850	47%

The water persulfate concentrations revealed that persulfate was fully consumed on day 2 and day 6.

On day 2 the water VOC concentrations decreased from 14,806 µg/L in the control to 1,430 µg/L in response to 6.3 g/L persulfate and 30 g/L of 30% H₂O₂. After the second application of persulfate and H₂O₂ and four additional days of incubation, the water VOC concentrations decreased from 13,952 µg/L in the control to 782 µg/L. This corresponded

to 90% and 94% removals of total VOC after 2 and 6 days of hydrogen peroxide activated persulfate treatment, respectively.

Despite the substantial removal of VOCs, only a small decrease in the COD concentration was observed on day 2 and no reduction in the COD concentration was observed on day 6. This is consistent with other studies (Brown et.al), which have shown that sodium persulfate works well on organics and is not consumed in satisfying the general oxidant demand of a soil (i.e. reduced metals etc.).

Table 5: VOC, COD, and persulfate concentrations in water following H₂O₂ activated persulfate treatment

Parameter	Day 2			Day 6		
	Control	6.3 g Na ₂ S ₂ O ₈	% Removal After 2 Days	Control	12.6 g Na ₂ S ₂ O ₈	% Removal After 6 Days
Total VOC (µg/L)	14,806	1,430	90%	13,952	782	94%
COD (mg/L)	310	305	2%	300	360	0%
Persulfate (g/L)	0	0	---	0	0	---

NaFe(III)EDTA Activated Persulfate Treatment

The soil and water analytical results from the persulfate treatment jars activated with NaFe(III)EDTA are presented in Tables 6 and 7.

On day 2 the soil VOC concentrations decreased from 2,590 µg/kg in the control to 2,516 µg/kg in response to 6.3 g/L persulfate and 0.5 g/L of NaFe(III)EDTA. After an additional 6.3 g/L of persulfate, 0.5 g/L of NaFe(III)EDTA and a four day incubation period, the soil VOC concentrations decreased from 2,530 µg/kg in the control to 2,321 µg/kg. This corresponded to 3% and 8% removals of total VOC after 2 and 6 days of NaFe(III)EDTA activated persulfate treatment, respectively.

On day 2 the soil COD concentration was reduced by 57%. The COD concentration on day 6 was greater than the control. The COD concentrations in the persulfate treated jars on days 2 and 6 were similar, but the concentration in the control was much lower than the initial COD concentration and the value on day 2, thus it appears that control value may have been incorrect.

Table 6: VOC and COD concentrations in soil following NaFe(III)EDTA activated persulfate treatment

Parameter	Day 2			Day 6		
	Control	6.3 g Na ₂ S ₂ O ₈	% Removal After 2 Days	Control	12.6 g Na ₂ S ₂ O ₈	% Removal After 6 Days
Total VOC (µg/kg)	2,590	2,516	3%	2,530	2,321	8%
COD (mg/kg)	26,000	11,100	57%	6,500	11,000	0

The persulfate concentrations in the water were 5.1 g/L and 10.4 g/L on days 2 and 6, respectively. This corresponded to a consumption of 1.2 g and 2.2 g of persulfate on days 2 and 6, respectively. This shows that persulfate radicals were not generated using chelated iron as an activator.

The water VOC concentrations on days 2 and 6 were 11,758 µg/L and 7,843 µg/L, respectively. The COD concentrations were greater in the jars amended with sodium persulfate and NaFe(III)EDTA than in the controls.

Table 7: VOC, COD, and persulfate concentrations in water following NaFe(III)EDTA activated persulfate treatment

Parameter	Day 2			Day 6		
	Control	6.3 g Na ₂ S ₂ O ₈	% Removal After 2 Days	Control	12.6 g Na ₂ S ₂ O ₈	% Removal After 6 Days
Total VOC (µg/L)	14,890	11,758	21%	9,879	7,843	21%
COD (mg/L)	270	715	0	290	1,050	0
Persulfate (g/L)	0	5.1	---	0	10.4	---

When accounting for the total mass of VOCs in the soil (300 g) and water (approximately 835 mL), the oxidation results (Table 8) show that persulfate activated with hydrogen peroxide was more effective in oxidizing the VOCs than persulfate activated with NaFe(III)EDTA.

Table 8: Mass balance of VOCs in water and soil following H₂O₂ and NaFe(III)EDTA activated persulfate treatments

Parameter	Treatment	Media	Control	After Day 2	% Removal after Day 2	Control	After Day 6	% Removal after Day 6
Total VOCs (μg)	H ₂ O ₂	Soil	834	432	48%	683	151	78%
	H ₂ O ₂	Water	13,234	1,577	88%	12,348	803	94%
	NaFe(III) EDTA	Soil	777	755	3%	759	696	8%
	NaFe(III) EDTA	Water	13,199	10,565	20%	9,021	7,262	19%

Removal of TCA and CA

Table 9 below summarizes the concentrations of key COI in groundwater and soil after Day 2 and Day 6, for each control and treatment jar. The TCA and CA concentrations indicate that there is some variability in the results for the duplicate control and treatment jars.

Table 9: Concentrations of target COI in water and soil following H₂O₂ and NaFe(III)EDTA activated persulfate treatments

Parameter	Media	Treatment	Day 2		Day 6		Units
			1 st Jar	Duplicate Jar	1 st Jar	Duplicate Jar	
TCA	Soil	Control	1,300	1,600	1,000	1,300	$\mu\text{g}/\text{kg}$
	Water	Control	440	510	700	680	$\mu\text{g}/\text{L}$
	Soil	H ₂ O ₂	120	1,500	13	680	$\mu\text{g}/\text{kg}$
	Water	H ₂ O ₂	300	770	430	140	$\mu\text{g}/\text{L}$
	Soil	NaFe(III)EDTA	1,700	1,900	390	3,300	$\mu\text{g}/\text{kg}$
	Water	NaFe(III)EDTA	400	410	850	1,100	$\mu\text{g}/\text{L}$
CA	Soil	Control	1,400	880	1,200	1,000	$\mu\text{g}/\text{kg}$
	Water	Control	14,000	14,000	13,000	8,800	$\mu\text{g}/\text{L}$
	Soil	H ₂ O ₂	55	170	ND (5.9)	ND (6.1)	$\mu\text{g}/\text{kg}$
	Water	H ₂ O ₂	89	87	7.8	7.2	$\mu\text{g}/\text{L}$
	Soil	NaFe(III)EDTA	980	150	210	500	$\mu\text{g}/\text{kg}$
	Water	NaFe(III)EDTA	11,000	11,000	5,700	7,500	$\mu\text{g}/\text{L}$

ND = non detect (detection limit)

Table 10 below summarizes the percent removal of key COI for both tests in groundwater and soil after Day 2 and Day 6. High and low percent removals for TCA and CA are shown for each case.

Table 10: Percent removal of target COI in water and soil following H₂O₂ and NaFe(III)EDTA activated persulfate treatments

Parameter	Media	Treatment	% Removal after Day 2		% Removal after Day 6	
			High	Low	High	Low
TCA	Soil	H ₂ O ₂	90.77	-15.38	98.70	32.00
	Water	H ₂ O ₂	31.82	-75.00	80.00	38.57
	Soil	NaFe(III)EDTA	-6.25	-11.76	70	-746.15
	Water	NaFe(III)EDTA	21.57	19.61	1.16	-27.91
CA	Soil	H ₂ O ₂	96.07	87.86	99.51	99.49
	Water	H ₂ O ₂	99.38	99.36	99.94	99.94
	Soil	NaFe(III)EDTA	82.95	-11.36	79.00	50.00
	Water	NaFe(III)EDTA	21.43	21.43	35.23	14.77

The highest removal efficiency was seen with hydrogen peroxide activated persulfate. The results show that with two applications (after 6 days) of hydrogen peroxide activated persulfate, the highest removal efficiency for TCA ranged from 80% to 98.70%, and that for CA it ranged from 99.51 to 99.94%. On the other hand, the lowest removal efficiency for TCA ranged from 32.00% to 38.57%, and that for CA it ranged from 99.49 to 99.94%. This indicates that the hydrogen peroxide activated persulfate was very effective in treating the target COI in both groundwater and soil after two applications of the oxidant. This shows that oxidant demand is close to 42g sodium persulfate per Kg of soil and 60 g hydrogen peroxide per Kg of soil.

Conclusions

The following conclusions can be drawn from these tests:

1. The site-specific COI can be oxidized by sodium persulfate activated with hydrogen peroxide.
2. Iron activated sodium persulfate was not efficient in treating the site-specific COI.
3. The estimated oxidant demand for the soil is 42 g sodium persulfate per Kg of soil and 60 g hydrogen peroxide per Kg of soil.

Please feel free to call the undersigned if there are any questions or if we can be of any further assistance.

Yours truly,

Adventus Americas, Inc.

Fayaz Lakhwala, Ph.D.
Director, Remedial Design and Engineering Services

Adventus Remediation Technologies, Inc.

Eva Dmitrovic
Project Manager

cc: Dr. J. Mueller – (Adventus, Chicago)
Dr. Alan Seech – (Adventus, Mississauga)

EHCTM is a trademark of Adventus Intellectual Property Inc.

Appendix A

Natural Oxidant Demand (NOD) Test Procedure (Modified from REMLAB-01 VER 1.3)

Purpose: To determine the amount of potassium permanganate required to meet the NOD of the soil

Procedure:

- 1) Homogenize soil sample using a stainless steel spoon. Minimize handling time to minimize volatile losses.
- 2) Prepare a 1N potassium permanganate solution ($=0.2\text{M}$, 31.61 g KMnO_4 in 1L).
- 3) Label seven 125-mL glass jars with the date, project number, amount and concentration of potassium permanganate and sequence number. Place a 100-mL graduated cylinder in front of each jar.

Summary of NOD jars

Jar Number	Volume 1N KMnO_4 (mL)	Volume Water (mL)	Dosage (mg KMnO_4 /g soil)	Concentration (mg/L)
1	0.0	75.0	0.00	0
2	0.5	74.5	0.32	211
3	1.5	73.5	0.95	632
4	5.0	70.0	3.16	2,107
5	15.0	60.0	9.50	6,323
6	50.0	25.0	31.61	21,073
7	75.0	0.0	47.42	31,610

- 4) Weigh out 50 g of soil into each of the seven jars. Record weight of soil in each jar.
- 5) Pipette the appropriate volume of 1N potassium permanganate solution into each of six graduated cylinders. Note that the first cylinder is for the control and thus does not receive any potassium permanganate. Top up each graduated cylinder, except for number seven, with de-ionized water to a final volume of 75-mL.
- 6) Add the contents of each graduated cylinder to the corresponding jar. Seal each jar and invert several times to mix the soil and liquid. Record date and time the experiment was started.
- 7) Invert the jars daily several times to mix the soil and liquid for the duration of the experiment (48 hours or 7 days). Prior to inverting the jars, record any changes in colour of the samples.
- 8) After 7 days, record the colour in the jars.

-
- 9) Sample the supernatant from the control, the jar that has the lowest potassium permanganate concentration (lightest purple colour) and the jar with the next lowest concentration
 - 10) Measure the absorbance of the samples with a spectrophotometer (wavelength set at 525 nm).
 - 11) Prepare a calibration curve in the concentration range of the samples and quantify the permanganate concentrations in the samples.

Appendix B - Initial Characterization Results

Parameter	Soil Initial		Soil Initial Dup		Water Initial	
	39287	units	39288	units	39289	units
Dichlorodifluoromethane	ND (120)	ug/kg	ND (120)	ug/kg	ND (1)	ug/L
Chloromethane	ND (120)	ug/kg	ND (120)	ug/kg	ND (1)	ug/L
Vinyl chloride	ND (120)	ug/kg	ND (120)	ug/kg	ND (1)	ug/L
Bromomethane	ND (120)	ug/kg	ND (120)	ug/kg	ND (1)	ug/L
Chloroethane	ND (120)	ug/kg	ND (120)	ug/kg	4.8	ug/L
Trichlorofluoromethane	ND (120)	ug/kg	ND (120)	ug/kg	ND (1)	ug/L
1,1-Dichloroethene	ND (120)	ug/kg	ND (120)	ug/kg	ND (1)	ug/L
Carbon disulfide	ND (120)	ug/kg	ND (120)	ug/kg	ND (5)	ug/L
Acetone	ND (230)	ug/kg	ND (240)	ug/kg	ND (5)	ug/L
Methylene chloride	ND (120)	ug/kg	ND (120)	ug/kg	ND (1)	ug/L
trans-1,2-Dichloroethene	ND (120)	ug/kg	ND (120)	ug/kg	ND (1)	ug/L
Methyl-tert-butyl-ether (MTBE)	ND (120)	ug/kg	ND (120)	ug/kg	ND (1)	ug/L
1,1-Dichloroethane	170	ug/kg	880	ug/kg	1.0	ug/L
2,2-Dichloropropane	ND (120)	ug/kg	ND (120)	ug/kg	ND (1)	ug/L
cis-1,2-Dichloroethene	ND (120)	ug/kg	ND (120)	ug/kg	ND (1)	ug/L
2-Butanone (MEK)	ND (120)	ug/kg	ND (120)	ug/kg	ND (2)	ug/L
Bromoform	ND (120)	ug/kg	ND (120)	ug/kg	ND (1)	ug/L
Chloroform	ND (120)	ug/kg	ND (120)	ug/kg	ND (1)	ug/L
1,1,1-Trichloroethane	41,000	ug/kg	230,000	ug/kg	ND (1)	ug/L
1,1-Dichloropropene	ND (120)	ug/kg	ND (120)	ug/kg	ND (1)	ug/L
Carbon tetrachloride	ND (120)	ug/kg	ND (120)	ug/kg	ND (1)	ug/L
Benzene	ND (29)	ug/kg	ND (29)	ug/kg	ND (1)	ug/L
1,2-Dichloroethane	ND (120)	ug/kg	ND (120)	ug/kg	ND (1)	ug/L
Trichloroethene	ND (29)	ug/kg	120	ug/kg	ND (1)	ug/L
1,2-Dichloropropane	ND (120)	ug/kg	ND (120)	ug/kg	ND (1)	ug/L
Dibromomethane	ND (120)	ug/kg	ND (120)	ug/kg	ND (1)	ug/L
Bromodichloromethane	ND (120)	ug/kg	ND (120)	ug/kg	ND (1)	ug/L
cis-1,3-Dichloropropene	ND (120)	ug/kg	ND (120)	ug/kg	ND (1)	ug/L
4-Methyl-2-pentanone (MIBK)	ND (120)	ug/kg	ND (120)	ug/kg	ND (5)	ug/L
Toluene	550	ug/kg	1,100	ug/kg	ND (1)	ug/L
trans-1,3-Dichloropropene	ND (120)	ug/kg	ND (120)	ug/kg	ND (1)	ug/L
1,1,2-Trichloroethane	ND (120)	ug/kg	ND (120)	ug/kg	ND (1)	ug/L
Tetrachloroethene	ND (120)	ug/kg	160	ug/kg	ND (1)	ug/L
1,3-Dichloropropane	ND (120)	ug/kg	ND (120)	ug/kg	ND (1)	ug/L
2-Hexanone	ND (120)	ug/kg	ND (120)	ug/kg	ND (5)	ug/L
Dibromochloromethane	ND (120)	ug/kg	ND (120)	ug/kg	ND (1)	ug/L
1,2-Dibromoethane (EDB)	ND (120)	ug/kg	ND (120)	ug/kg	ND (1)	ug/L
Chlorobenzene	ND (120)	ug/kg	ND (120)	ug/kg	ND (1)	ug/L
1,1,1,2-Tetrachloroethane	ND (120)	ug/kg	ND (120)	ug/kg	ND (1)	ug/L
Ethylbenzene	49	ug/kg	71	ug/kg	ND (1)	ug/L
m&p-Xylenes	220	ug/kg	310	ug/kg	ND (2)	ug/L
o-Xylene	97	ug/kg	130	ug/kg	ND (1)	ug/L
Styrene	ND (120)	ug/kg	ND (120)	ug/kg	ND (1)	ug/L
Bromoform	ND (120)	ug/kg	ND (120)	ug/kg	ND (1)	ug/L
Isopropylbenzene	ND (120)	ug/kg	ND (120)	ug/kg	ND (1)	ug/L
Bromobenzene	ND (120)	ug/kg	ND (120)	ug/kg	ND (1)	ug/L
1,1,2,2-Tetrachloroethane	ND (120)	ug/kg	ND (120)	ug/kg	ND (1)	ug/L
1,2,3-Trichloropropane	ND (120)	ug/kg	ND (120)	ug/kg	ND (1)	ug/L
n-Propylbenzene	ND (120)	ug/kg	ND (120)	ug/kg	ND (1)	ug/L
2-Chlorotoluene	ND (120)	ug/kg	ND (120)	ug/kg	ND (1)	ug/L
1,3,5-Trimethylbenzene	ND (120)	ug/kg	ND (120)	ug/kg	ND (1)	ug/L
4-Chlorotoluene	ND (120)	ug/kg	ND (120)	ug/kg	ND (1)	ug/L
tert-Butylbenzene	ND (120)	ug/kg	ND (120)	ug/kg	ND (1)	ug/L
1,2,4-Trimethylbenzene	ND (120)	ug/kg	ND (120)	ug/kg	ND (1)	ug/L
sec-Butylbenzene	ND (120)	ug/kg	ND (120)	ug/kg	ND (1)	ug/L
1,3-Dichlorobenzene	ND (120)	ug/kg	ND (120)	ug/kg	ND (1)	ug/L
p-Isopropyltoluene	ND (120)	ug/kg	160	ug/kg	ND (1)	ug/L
1,4-Dichlorobenzene	ND (120)	ug/kg	ND (120)	ug/kg	ND (1)	ug/L
n-Butylbenzene	ND (120)	ug/kg	ND (120)	ug/kg	ND (1)	ug/L
1,2-Dichlorobenzene	ND (120)	ug/kg	ND (120)	ug/kg	ND (1)	ug/L
1,2-Dibromo-3-chloropropane	ND (120)	ug/kg	ND (120)	ug/kg	ND (1)	ug/L
1,2,4-Trichlorobenzene	ND (120)	ug/kg	ND (120)	ug/kg	ND (1)	ug/L
Hexachlorobutadiene	ND (120)	ug/kg	ND (120)	ug/kg	ND (1)	ug/L
Naphthalene	120	ug/kg	ND (120)	ug/kg	ND (1)	ug/L
1,2,3-Trichlorobenzene	ND (120)	ug/kg	ND (120)	ug/kg	ND (1)	ug/L
1,3,5-Trichlorobenzene	ND (120)	ug/kg	ND (120)	ug/kg	ND (1)	ug/L
% Solids, solid	86.2	%	84.8	%	n/a	
% Moisture, Solids	13.8	%	15.2	%	n/a	
COD	19,000	mg/kg	17,000	mg/kg	33	mg/L
TOC	4,500	mg/kg	6,000	mg/kg	11	mg/L

Appendix C - Day 2 Analytical Data (Water)

Analyte	Units	Jar 1			Jar 2			Jar 3			Jar 7			Jar 8			Jar 9		
		Control			6.3 g Na2S2O8 + H2O2 (Day 2)			6.3 g Na2S2O8 + H2O2 (Day 2)			Control			6.3 g Na2S2O8 + NaFe(III)EDTA (Day 2)			6.3 g Na2S2O8 + NaFe(III)EDTA (Day 2)		
		39713	Qualifier	DL	39714	Qualifier	DL	39715	Qualifier	DL	39716	Qualifier	DL	39717	Qualifier	DL	39718	Qualifier	DL
Chemical Oxygen Demand (COD)	mg/L	310		50	350		50	260		50	220		50	210		50	220		50
Dichlorodifluoromethane	ug/L	20	U	20	1.0	U	1.0	1.0	U	1.0	20	U	20	20	U	20	20	U	20
Chloromethane	ug/L	20	U	20	1.0	U	1.0	1.0	U	1.0	20	U	20	20	U	20	20	U	20
Vinyl chloride	ug/L	20	U	20	1.0	U	1.0	1.0	U	1.0	20	U	20	20	U	20	20	U	20
Bromomethane	ug/L	20	U*	20	1.0	U*	1.0	1.0	U*	1.0	20	U*	20	20	U*	20	20	U*	20
Chloroethane	ug/L	14000		200	89		1.0	87		1.0	14000		200	14000		200	14000		200
Trichlorofluoromethane	ug/L	20	U	20	1.0	U	1.0	1.0	U	1.0	20	U	20	20	U	20	20	U	20
1,1-Dichloroethene	ug/L	20	U	20	1.0	U	1.0	1.0	U	1.0	20	U	20	20	U	20	20	U	20
Carbon disulfide	ug/L	100	U	100	1.8	J	5.0	2.0	JH	5.0	100	U	100	100	U	100	100	U	100
Acetone	ug/L	100	U	100	770	A	50	750		500	100	U	100	100	U	100	100	U	100
Methylene chloride	ug/L	30		20	2.7		1.0	10	H	1.0	30	H	20	27	20	28	20	20	
trans-1,2-Dichloroethene	ug/L	20	U	20	1.0	U	1.0	1.0	U	1.0	20	U	20	20	U	20	20	U	20
Methyl-tert-butyl-ether (MTBE)	ug/L	20	U	20	1.0	U	1.0	1.0	U	1.0	20	U	20	20	U	20	20	U	20
1,1-Dichloroethane	ug/L	100		20	21		1.0	27	H	1.0	190		20	170		20	160		20
2,2-Dichloropropane	ug/L	20	U*	20	1.0	U*	1.0	1.0	U*	1.0	20	U*	20	20	U*	20	20	U*	20
cis-1,2-Dichloroethene	ug/L	20	U	20	1.0	U	1.0	1.0	U	1.0	20	U	20	20	U	20	20	U	20
2-Butanone	ug/L	100	U	100	5.0		5.0	8.9	H	5.0	100	U	100	100	U	100	100	U	100
Bromochloromethane	ug/L	20	U	20	1.0	U	1.0	1.0	U	1.0	20	U	20	20	U	20	20	U	20
Chloroform	ug/L	20	U	20	1.0	U	1.0	1.0	U	1.0	20	U	20	20	U	20	20	U	20
1,1,1-Trichloroethane	ug/L	440		20	300		10	770		100	510		20	400		20	410		20
1,1-Dichloropropene	ug/L	20	U	20	1.0	U	1.0	1.0	U	1.0	20	U	20	20	U	20	20	U	20
Carbon tetrachloride	ug/L	20	U	20	1.0	U	1.0	1.0	U	1.0	20	U	20	20	U	20	20	U	20
Benzene	ug/L	16	J	20	1.0	U	1.0	1.0	U	1.0	1.0	U	20	20	U	20	20	U	20
1,2-Dichloroethane	ug/L	20	U	20	1.0	U	1.0	1.0	U	1.0	20	U	20	20	U	20	20	U	20
Trichloroethene	ug/L	20	U	20	1.0	U	1.0	1.0	U	1.0	20	U	20	20	U	20	20	U	20
1,2-Dichloropropane	ug/L	20	U	20	1.0	U	1.0	1.0	U	1.0	20	U	20	20	U	20	20	U	20
Dibromomethane	ug/L	20	U	20	1.0	U	1.0	1.0	U	1.0	20	U	20	20	U	20	20	U	20
Bromodichloromethane	ug/L	20	U	20	1.0	U	1.0	1.0	U	1.0	20	U	20	20	U	20	20	U	20
cis-1,3-Dichloropropene	ug/L	20	U	20	1.0	U	1.0	1.0	U	1.0	20	U	20	20	U	20	20	U	20
4-Methyl-2-pentanone (MIBK)	ug/L	100	U*	100	5.0	U*	5.0	5.0	U*	5.0	100	U*	100	100	U*	100	100	U*	100
Toluene	ug/L	20	U	20	1.0	U	1.0	1.0	U	1.0	20	U	20	20	U	20	20	U	20
trans-1,3-Dichloropropene	ug/L	20	U	20	1.0	U	1.0	1.0	U	1.0	20	U	20	20	U	20	20	U	20
1,1,2-Trichloroethane	ug/L	20	U	20	1.0	U	1.0	1.0	U	1.0	20	U	20	20	U	20	20	U	20
Tetrachloroethene	ug/L	20	U	20	1.0	U	1.0	1.0	U	1.0	20	U	20	20	U	20	20	U	20
1,3-Dichloropropane	ug/L	20	U	20	1.0	U	1.0	1.0	U	1.0	20	U	20	20	U	20	20	U	20
2-Hexanone	ug/L	100	U	100	5.0	U	5.0	5.0	U	5.0	100	U	100	100	U	100	100	U	100
Dibromochloromethane	ug/L	20	U	20	1.0	U	1.0	1.0	U	1.0	20	U	20	20	U	20	20	U	20
1,2-Dibromoethane (EDB)	ug/L	20	U	20	1.0	U	1.0	1.0	U	1.0	20	U	20	20	U	20	20	U	20
Chlorobenzene	ug/L	20	U	20	1.0	U	1.0	1.0	U	1.0	20	U	20	20	U	20	20	U	20
1,1,2-Tetrachloroethane	ug/L	20	U	20	1.0	U	1.0	1.0	U	1.0	20	U	20	20	U	20	20	U	20

Appendix C - Day 2 Analytical Data (Water)

Analyte	Units	Jar 1			Jar 2			Jar 3			Jar 7			Jar 8			Jar 9		
		Control			6.3 g Na2S2O8 + H2O2 (Day 2)			6.3 g Na2S2O8 + H2O2 (Day 2)			Control			6.3 g Na2S2O8 + NaFe(II)EDTA (Day 2)			6.3 g Na2S2O8 + NaFe(II)EDTA (Day 2)		
		39715	Qualifier	DL	39714	Qualifier	DL	39715	Qualifier	DL	39716	Qualifier	DL	39717	Qualifier	DL	39718	Qualifier	DL
Ethylbenzene	ug/L	20	U	20	1.0	U	1.0	20	U	20	20	U	20	20	U	20	20	U	20
m,p-Xylenes	ug/L	40	U	40	2.0	U	2.0	40	U	40	40	U	40	40	U	40	40	U	40
o-Xylene	ug/L	20	U	20	1.0	U	1.0	20	U	20	20	U	20	20	U	20	20	U	20
Syrene	ug/L	20	U	20	1.0	U	1.0	20	U	20	20	U	20	20	U	20	20	U	20
Bromoform	ug/L	20	U	20	1.0	U	1.0	20	U	20	20	U	20	20	U	20	20	U	20
Isopropylbenzene	ug/L	20	U	20	1.0	U	1.0	20	U	20	20	U	20	20	U	20	20	U	20
Bromobenzene	ug/L	20	U	20	1.0	U	1.0	20	U	20	20	U	20	20	U	20	20	U	20
1,1,2,2-Tetrachloroethane	ug/L	20	U	20	1.0	U	1.0	20	U	20	20	U	20	20	U	20	20	U	20
1,2,3-Trichloropropane	ug/L	20	U	20	1.0	U	1.0	20	U	20	20	U	20	20	U	20	20	U	20
n-Propylbenzene	ug/L	20	U	20	1.0	U	1.0	20	U	20	20	U	20	20	U	20	20	U	20
2-Chlorotoluene	ug/L	20	U	20	1.0	U	1.0	20	U	20	20	U	20	20	U	20	20	U	20
1,3,5-Trimethylbenzene	ug/L	20	U	20	1.0	U	1.0	20	U	20	20	U	20	20	U	20	20	U	20
4-Chlorotoluene	ug/L	20	U	20	1.0	U	1.0	20	U	20	20	U	20	20	U	20	20	U	20
tert-Butylbenzene	ug/L	20	U	20	1.0	U	1.0	20	U	20	20	U	20	20	U	20	20	U	20
1,2,4-Trimethylbenzene	ug/L	20	U	20	1.0	U	1.0	20	U	20	20	U	20	20	U	20	20	U	20
sec-Butylbenzene	ug/L	20	U	20	1.0	U	1.0	20	U	20	20	U	20	20	U	20	20	U	20
t,3-Dichlorobenzene	ug/L	20	U	20	1.0	U	1.0	20	U	20	20	U	20	20	U	20	20	U	20
p-Isopropyltoluene	ug/L	20	U	20	1.0	U	1.0	20	U	20	20	U	20	20	U	20	20	U	20
1,4-Dichlorobenzene	ug/L	20	U	20	1.0	U	1.0	20	U	20	20	U	20	20	U	20	20	U	20
t-Butylbenzene	ug/L	20	U*	20	L*	U*	1.0	L*	U*	1.0	20	U*	20	20	U*	20	20	U*	20
1,2-Dichlorobenzene	ug/L	20	U	20	1.0	U	1.0	20	U	20	20	U	20	20	U	20	20	U	20
1,2-Dibromo-3-chloropropane	ug/L	20	U	20	1.0	U	1.0	20	U	20	20	U	20	20	U	20	20	U	20
1,3,5-Trichlorobenzene	ug/L	20	U	20	1.0	U	1.0	20	U	20	20	U	20	20	U	20	20	U	20
1,2,4-Trichlorobenzene	ug/L	20	U	20	1.0	U	1.0	20	U	20	20	U	20	20	U	20	20	U	20
Hexachlorobutadiene	ug/L	20	U	20	1.0	U	1.0	20	U	20	20	U	20	20	U	20	20	U	20
Naphthalene	ug/L	20	U	20	1.0	U	1.0	20	U	20	20	U	20	20	U	20	20	U	20
1,2,3-Trichlorobenzene	ug/L	20	U	20	1.0	U	1.0	20	U	20	20	U	20	20	U	20	20	U	20

Appendix C - Day 2 Analytical Data (Soil)

Analyte	Units	Jar 1			Jar 2			Jar 3			Jar 7			Jar 8			Jar 9			
		Control	39719 Qualifier	DL	39720 Qualifier	DL	39721 Qualifier	DL	39722 Qualifier	DL	39723 Qualifier	DL	39724 Qualifier	DL	39725 Qualifier	DL	39726 Qualifier	DL		
Chemical Oxygen Demand (COD)	mg/Kg	20000		690	7500		370	9600		390	26000		810	16000		610	8200		260	
% Solids	%	75.7		0.10	78.7		0.10	77.5		0.10	77.2		0.10	78.0		0.10	82.8		0.10	
Dichlorodifluoromethane	ug/Kg	6.6	U	6.6	6.4	U	6.4	6.5	U	6.5	6.5	U	6.5	6.4	U	6.4	6.0	U	6.0	
Chloromethane	ug/Kg	6.6	U	6.6	6.4	U	6.4	6.5	U	6.5	6.5	U	6.5	6.4	U	6.4	6.0	U	6.0	
Vinyl chloride	ug/Kg	6.6	U	6.6	6.4	U	6.4	6.5	U	6.5	6.5	U	6.5	6.4	U	6.4	6.0	U	6.0	
Bromomethane	ug/Kg	6.6	U	6.6	6.4	U	6.4	6.5	U	6.5	6.5	U	6.5	6.4	U	6.4	6.0	U	6.0	
Chloroethane	ug/Kg	1400		130	55		6.4	170		6.5	800	H	130	900		130	150		60	
Trichlorofluoromethane	ug/Kg	6.6	U	6.6	6.4	U	6.4	6.5	U	6.5	6.5	U	6.5	6.4	U	6.4	6.0	U	6.0	
1,1-Dichloroethene	ug/Kg	6.6	U	6.6	6.4	U	6.4	6.5	U	6.5	6.5	U	6.5	6.4	U	6.4	6.0	U	6.0	
Carbon disulfide	ug/Kg	6.6	U	6.6	6.4	U	6.4	6.5	U	6.5	6.5	U	6.5	5.8	J*	6.4	6.0	U	6.0	
Acetone	ug/Kg	21	*	6.6	440		250	390		260	79	*	6.5	79	*	6.4	120	*	6.0	
Methylene chloride	ug/Kg	6.6	U	6.6	9.9		6.4	16		6.5	12	M	6.5	6.4	U	6.4	17		6.0	
trans-1,2-Dichloroethene	ug/Kg	6.6	U	6.6	6.4	U	6.4	6.5	U	6.5	6.5	U	6.5	6.4	U	6.4	6.0	U	6.0	
Methyl-tert-butyl-ether (MTBE)	ug/Kg	6.6	U	6.6	6.4	U	6.4	6.5	U	6.5	6.5	U	6.5	6.4	U	6.4	6.0	U	6.0	
1,1-Dichloroethane	ug/Kg	48		6.6	3.9	J*	6.4	15		6.5	19		6.5	34		6.4	86		6.0	
2,2-Dichloropropane	ug/Kg	6.6	U	6.6	6.4	U	6.4	6.5	U	6.5	6.5	U	6.5	6.4	U	6.4	6.0	U	6.0	
cis-1,2-Dichloroethene	ug/Kg	6.6	U	6.6	6.4	U	6.4	6.5	U	6.5	6.5	U	6.5	6.4	U	6.4	6.0	U	6.0	
2-Butanone (MEK)	ug/Kg	6.6	U	6.6	24		6.4	57		6.5	65	U	6.5	6.4	U	6.4	6.0	U	6.0	
Bromoform	ug/Kg	6.6	U	6.6	6.4	U	6.4	6.5	U	6.5	6.5	U	6.5	6.4	U	6.4	6.0	U	6.0	
1,1,1-Trichloroethane	ug/Kg	1300		66	120		6.4	1500		65	1600		65	1700		64	1800		60	
1,1-Dichloropropene	ug/Kg	6.6	U	6.6	6.4	U	6.4	6.5	U	6.5	6.5	U	6.5	6.4	U	6.4	6.0	U	6.0	
Carbon tetrachloride	ug/Kg	6.6	U	6.6	6.4	U	6.4	6.5	U	6.5	6.5	U	6.5	6.4	U	6.4	6.0	U	6.0	
Benzene	ug/Kg	6.6	U	6.6	6.4	U	6.4	84		6.5	65	U	6.5	6.4	U	6.4	6.0	U	6.0	
1,2-Dichloroethane	ug/Kg	6.6	U	6.6	6.4	U	6.4	6.5	U	6.5	65	U	6.5	6.4	U	6.4	6.0	U	6.0	
Trichloroethene	ug/Kg	6.6	U	6.6	6.4	U	6.4	6.5	U	6.5	65	U	6.5	6.4	U	6.4	6.0	U	6.0	
1,2-Dichloropropane	ug/Kg	6.6	U	6.6	6.4	U	6.4	6.5	U	6.5	65	U	6.5	6.4	U	6.4	6.0	U	6.0	
Dibromomethane	ug/Kg	6.6	U	6.6	6.4	U	6.4	6.5	U	6.5	65	U	6.5	6.4	U	6.4	6.0	U	6.0	
Bromodichloromethane	ug/Kg	6.6	U	6.6	6.4	U	6.4	6.5	U	6.5	65	U	6.5	6.4	U	6.4	6.0	U	6.0	
cis-1,3-Dichloropropene	ug/Kg	6.6	U	6.6	6.4	U	6.4	6.5	U	6.5	65	U	6.5	6.4	U	6.4	6.0	U	6.0	
4-Methyl-2-pentanone (MIBK)	ug/Kg	6.6	U	6.6	6.4	U	6.4	6.5	U	6.5	65	U	6.5	6.4	U	6.4	6.0	U	6.0	
Toluene	ug/Kg	6.6	J*	Ja	6.6		6.4	6.5		6.5	65		6.5	65		6.4	59		Ja	6.0
trans-1,3-Dichloropropene	ug/Kg	6.6	U	6.6	6.4	U	6.4	6.5	U	6.5	65	U	6.5	6.4	U	6.4	6.0	U	6.0	
1,1,2-Trichloroethane	ug/Kg	6.6	U	6.6	6.4	U	6.4	6.5	U	6.5	65	U	6.5	6.4	U	6.4	6.0	U	6.0	
Tetrachloroethene	ug/Kg	3.5	Ja	6.6	6.4	U	6.4	6.5	U	6.5	65	U	6.5	6.4	U	6.4	3.2	Ja	6.0	
1,3-Dichloropropane	ug/Kg	6.6	U	6.6	6.4	U	6.4	6.5	U	6.5	65	U	6.5	6.4	U	6.4	6.0	U	6.0	
2-Hexanone	ug/Kg	6.6	U	6.6	6.4	U	6.4	6.5	U	6.5	65	U	6.5	6.4	U	6.4	6.0	U	6.0	
Dibromochloromethane	ug/Kg	6.6	U	6.6	6.4	U	6.4	6.5	U	6.5	65	U	6.5	6.4	U	6.4	6.0	U	6.0	
1,2-Dibromoethane (EDB)	ug/Kg	6.6	U	6.6	6.4	U	6.4	6.5	U	6.5	65	U	6.5	6.4	U	6.4	6.0	U	6.0	
Chlorobenzene	ug/Kg	6.6	U	6.6	6.4	U	6.4	6.5	U	6.5	65	U	6.5	6.4	U	6.4	6.0	U	6.0	

Appendix C - Day 2 Analytical Data (Soil)

Analyte	Units	Jar 1			Jar 2			Jar 3			Jar 7			Jar 8			Jar 9		
		Control			6.3 g Na2S2O8 + H2O2 (Day 2)			6.3 g Na2S2O8 + H2O2 (Day 2)			Control			6.3 g Na2S2O8 + NaFe(III)EDTA (Day 2)			6.3 g Na2S2O8 + NaFe(III)EDTA (Day 2)		
		39719	Qualifier	DL	39720	Qualifier	DL	39721	Qualifier	DL	39722	Qualifier	DL	39723	Qualifier	DL	39724	Qualifier	DL
1,1,1,2-Tetrachloroethane	ug/Kg	6.6	U	6.6	6.4	U	6.4	6.5	U	6.5	6.4	U	6.4	6.0	U	6.0			
Ethylbenzene	ug/Kg	6.6	U	6.6	6.4	U	6.4	6.5	U	6.5	6.4	U	6.4	6.0	U	6.0			
m,p-Xylenes	ug/Kg	13	U	13	13	U	13	13	U	13	13	U	13	12	U	12			
<i>o</i> -Xylene	ug/Kg	6.6	U	6.6	6.4	U	6.4	6.5	U	6.5	6.5	U	6.5	3.5	Ja	6.4	3.7	Ja	6.0
Styrene	ug/Kg	6.6	U	6.6	6.4	U	6.4	6.5	U	6.5	6.5	U	6.5	6.4	U	6.4	6.0	U	6.0
Bromofom	ug/Kg	6.6	U	6.6	6.4	U	6.4	6.5	U	6.5	6.5	U	6.5	6.4	U	6.4	6.0	U	6.0
Isopropylbenzene	ug/Kg	6.6	U	6.6	6.4	U	6.4	6.5	U	6.5	6.5	U	6.5	6.4	U	6.4	6.0	U	6.0
Bromobenzene	ug/Kg	6.6	U	6.6	6.4	U	6.4	6.5	U	6.5	6.5	U	6.5	6.4	U	6.4	6.0	U	6.0
1,1,2,2-Tetrachloroethane	ug/Kg	6.6	U	6.6	6.4	U	6.4	6.5	U	6.5	6.5	U	6.5	6.4	U	6.4	6.0	U	6.0
1,2,2-Trichloropropane	ug/Kg	6.6	U	6.6	6.4	U	6.4	6.5	U	6.5	6.5	U	6.5	6.4	U	6.4	6.0	U	6.0
n-Propylbenzene	ug/Kg	6.6	U	6.6	6.4	U	6.4	6.5	U	6.5	6.5	U	6.5	6.4	U	6.4	6.0	U	6.0
2-Chlorotoluene	ug/Kg	6.6	U	6.6	6.4	U	6.4	6.5	U	6.5	6.5	U	6.5	6.4	U	6.4	6.0	U	6.0
1,3,5-Trimethylbenzene	ug/Kg	6.6	U	6.6	6.4	U	6.4	6.5	U	6.5	6.5	U	6.5	6.4	U	6.4	6.0	U	6.0
4-Chlorotoluene	ug/Kg	6.6	U	6.6	6.4	U	6.4	6.5	U	6.5	6.5	U	6.5	6.4	U	6.4	6.0	U	6.0
tert-Butylbenzene	ug/Kg	6.6	U	6.6	6.4	U	6.4	6.5	U	6.5	6.5	U	6.5	6.4	U	6.4	6.0	U	6.0
1,2,4-Trimethylbenzene	ug/Kg	6.6	U	6.6	6.4	U	6.4	6.5	U	6.5	6.5	U	6.5	6.4	U	6.4	6.0	U	6.0
sec-Butylbenzene	ug/Kg	6.6	U	6.6	6.4	U	6.4	6.5	U	6.5	6.5	U	6.5	6.4	U	6.4	6.0	U	6.0
1,3-Dichlorobenzene	ug/Kg	6.6	U	6.6	6.4	U	6.4	6.5	U	6.5	6.5	U	6.5	6.4	U	6.4	6.0	U	6.0
Isopropyltoluene	ug/Kg	6.6	U	6.6	6.4	U	6.4	6.5	U	6.5	6.5	U	6.5	6.4	U	6.4	6.0	U	6.0
4-Dichlorobenzene	ug/Kg	6.6	U	6.6	6.4	U	6.4	6.5	U	6.5	6.5	U	6.5	6.4	U	6.4	6.0	U	6.0
<i>n</i> -Butylbenzene	ug/Kg	6.6	U	6.6	6.4	U	6.4	6.5	U	6.5	6.5	U	6.5	6.4	U	6.4	6.0	U	6.0
1,2-Dichlorobenzene	ug/Kg	6.6	U	6.6	6.4	U	6.4	6.5	U	6.5	6.5	U	6.5	6.4	U	6.4	6.0	U	6.0
1,2-Dibromo-3-chloropropane	ug/Kg	6.6	U	6.6	6.4	U	6.4	6.5	U	6.5	6.5	U	6.5	6.4	U	6.4	6.0	U	6.0
1,3,5-Trichlorobenzene	ug/Kg	6.6	U	6.6	6.4	U	6.4	6.5	U	6.5	6.5	U	6.5	6.4	U	6.4	6.0	U	6.0
1,2,4-Trichlorobenzene	ug/Kg	6.6	U	6.6	6.4	U	6.4	6.5	U	6.5	6.5	U	6.5	6.4	U	6.4	6.0	U	6.0
Hexachlorobutadiene	ug/Kg	6.6	U	6.6	6.4	U	6.4	6.5	U	6.5	6.5	U	6.5	6.4	U	6.4	6.0	U	6.0
Naphthalene	ug/Kg	6.6	U	6.6	6.4	U	6.4	6.5	U	6.5	6.5	U	6.5	6.4	U	6.4	6.0	U	6.0
1,2,3-Trichlorobenzene	ug/Kg	6.6	U	6.6	6.4	U	6.4	6.5	U	6.5	6.5	U	6.5	6.4	U	6.4	6.0	U	6.0

U

analyte was not detected at or above the stated limit

H

Alternate peak selection upon analytical review

M

manually integrated compound

J

result is an estimated value below the reporting limit or a tentatively identified compound (TIC)

•

Batch QC is greater than reporting limit

Appendix D - Day 6 Analytical Data (Water)

Analyte	Units	Jar 4			Jar 5			Jar 6			Jar 10			Jar 11			Jar 12		
		Control	39725 Qualifier	DL	39726 Qualifier	DL	39727 Qualifier	DL	39728 Qualifier	DL	39729 Qualifier	DL	39730 Qualifier	DL	39731 Qualifier	DL	39732 Qualifier	DL	
Chemical Oxygen Demand (COD)	mg/L	300	50	350	50	370	50	250	50	1100	50	1000	50	1000	50	1000	50	1000	50
Dichlorodifluoromethane	ug/L	10	U	10	1.0	U	1.0	1.0	U	1.0	1.0	U	1.0	1.0	U	1.0	1.0	U	1.0
Chloromethane	ug/L	10	U	10	1.0	U	1.0	1.0	U	1.0	10	2.7	H	1.0	4.5	H	1.0		
Vinyl chloride	ug/L	10	U	10	1.0	U	1.0	1.0	U	1.0	9.3	J	10	1.0	1.0	H	1.0		
Bromomethane	ug/L	10	U	10	1.0	U	1.0	2.5	U	1.0	1.0	U	1.0	1.0	U	3.0	H	1.0	
Chloroethane	ug/L	13000	H	200	7.8		7.2	1.0	8800		500	5700		100	2500		200		
Trichlorofluoromethane	ug/L	10	U	10	1.0	U	1.0	1.0	U	1.0	10	1.0	U	1.0	1.0	U	1.0		
1,1-Dichloroethene	ug/L	10	U	10	1.0	U	1.0	1.0	U	1.0	10	1.0	U	1.0	1.0	U	1.0		
Carbon disulfide	ug/L	50	U	50	7.9		5.0	8.6	5.0	50	50	13	H	5.0	14	H	5.0		
Acetone	ug/L	50	U	50	390	M	520	M	100	50	50	40	H*	5.0	43	H*	5.0		
Methylene chloride	ug/L	20	U	10	6.1		6.9	1.0	20		10	25	H	1.0	27	H	1.0		
trans-1,2-Dichloroethene	ug/L	10	U	10	1.0	U	1.0	1.0	U	1.0	10	1.0	U	1.0	1.0	U	1.0		
Methyl-tert-butyl-ether (MTBE)	ug/L	10	U	10	1.0	U	1.0	1.0	U	1.0	10	1.0	U	1.0	1.0	U	1.0		
1,1-Dichloroethane	ug/L	170	U	10	4.2		3.9	1.0	170		10	140		100	150		100		
2,2-Dichloropropane	ug/L	10	U	10	1.0	U	1.0	1.0	U	1.0	10	1.0	U	1.0	1.0	U	1.0		
cis-1,2-Dichloroethene	ug/L	10	U	10	1.0	U	1.0	1.0	U	1.0	10	1.0	U	1.0	1.0	U	1.0		
2-Butanone (MEK)	ug/L	50	U	50	15		5.0	17	5.0	50	50	27	H	5.0	30	H	5.0		
Bromoform	ug/L	10	U	10	1.0	U	1.0	1.0	U	1.0	10	1.0	U	1.0	1.0	U	1.0		
Chloroform	ug/L	10	U	10	1.0	U	1.0	1.0	U	1.0	10	1.0	U	1.0	1.0	U	1.0		
1,1,1-Trichloroethane	ug/L	700	U	10	430		10	140	H	20	860		10	850		100	1100		100
1,1-Dichloropropene	ug/L	10	U	10	1.0	U	1.0	1.0	U	1.0	10	1.0	U	1.0	1.0	U	1.0		
Carbon tetrachloride	ug/L	10	U	10	1.0	U	1.0	1.0	U	1.0	10	1.0	U	1.0	1.0	U	1.0		
Benzene	ug/L	22	U	10	1.0	U	1.0	1.0	U	1.0	10	3.8		1.0	3.8		1.0		
1,2-Dichloroethane	ug/L	10	U	10	1.0	U	1.0	1.0	U	1.0	10	1.0	U	1.0	1.0	U	1.0		
Trichloroethene	ug/L	10	U	10	1.0	U	1.0	1.0	U	1.0	10	1.0	U	1.0	1.0	U	1.0		
1,2-Dichloropropane	ug/L	10	U	10	1.0	U	1.0	1.0	U	1.0	10	1.0	U	1.0	1.0	U	1.0		
Dibromomethane	ug/L	10	U	10	1.0	U	1.0	1.0	U	1.0	10	1.0	U	1.0	1.0	U	1.0		
Bromodichloromethane	ug/L	10	U	10	1.0	U	1.0	1.0	U	1.0	10	1.0	U	1.0	1.0	U	1.0		
cis-1,3-Dichloropropene	ug/L	10	U	10	1.0	U	1.0	1.0	U	1.0	10	1.0	U	1.0	1.0	U	1.0		
4-Methyl-2-pentanone (MIBK)	ug/L	50	U	50	5.0	U	5.0	5.0	U	5.0	50	50	50	5.0	5.0	U	5.0		
Toluene	ug/L	3.1	J*	10	0.98	J*	1.0	0.93	J*	1.0	8.6	J*	10	1.3	1.0	1.2		1.0	
trans-1,3-Dichloropropene	ug/L	10	U	10	1.0	U	1.0	1.0	U	1.0	10	1.0	U	1.0	1.0	U	1.0		
1,1,2-Trichloroethane	ug/L	10	U	10	1.0	U	1.0	1.0	U	1.0	10	1.0	U	1.0	1.0	U	1.0		
Tetrachloroethene	ug/L	10	U	10	1.0	U	1.0	1.0	U	1.0	10	1.0	U	1.0	1.0	U	1.0		
1,3-Dichloropropane	ug/L	10	U	10	1.0	U	1.0	1.0	U	1.0	10	1.0	U	1.0	1.0	U	1.0		
2-Hexanone	ug/L	50	U	50	5.0	U	5.0	5.0	U	5.0	50	50	50	5.0	5.0	U	5.0		
Dibromochloromethane	ug/L	10	U	10	1.0	U	1.0	1.0	U	1.0	10	1.0	U	1.0	1.0	U	1.0		
1,2-Dibromoethane (EDB)	ug/L	10	U	10	1.0	U	1.0	1.0	U	1.0	10	1.0	U	1.0	1.0	U	1.0		
Chlorobenzene	ug/L	10	U	10	1.0	U	1.0	1.0	U	1.0	10	1.0	U	1.0	1.0	U	1.0		
1,1,1,2-Tetrachloroethane	ug/L	10	U	10	1.0	U	1.0	1.0	U	1.0	10	1.0	U	1.0	1.0	U	1.0		

Appendix D - Day 6 Analytical Data (Water)

	Jar 4		Jar 5		Jar 6		Jar 10		Jar 11		Jar 12	
	Control	12.6 g Na ₂ S ₂ O ₈ + H ₂ O ₂ (Day 6)	Control	12.6 g Na ₂ S ₂ O ₈ + H ₂ O ₂ (Day 6)	Control	12.6 g Na ₂ S ₂ O ₈ + NaFe(III)EDTA (Day 6)	Control	12.6 g Na ₂ S ₂ O ₈ + NaFe(III)EDTA (Day 6)				
Ethylbenzene	ug/L	19	10	1.0	U	1.0	10	U	10	1.0	U	1.0
m,p-Xylenes	ug/L	9.8	J	20	2.0	U	2.0	20	U	20	2.0	U
o-Xylene	ug/L	3.0	J#	10	1.0	U	1.0	10	U	10	1.0	U
Styrene	ug/L	10	U	10	1.0	U	1.0	10	U	10	1.0	U
Bromoform	ug/L	10	U	10	1.0	U	1.0	10	U	10	1.0	U
Isopropylbenzene	ug/L	10	U	10	1.0	U	1.0	10	U	10	1.0	U
Bromobenzene	ug/L	10	U	10	1.0	U	1.0	10	U	10	1.0	U
1,1,2,2-Tetrachloroethane	ug/L	10	U	10	1.0	U	1.0	10	U	10	1.0	U
1,2,3-Trichloropropane	ug/L	10	U	10	1.0	U	1.0	10	U	10	1.0	U
n-Propylbenzene	ug/L	10	U	10	1.0	U	1.0	10	U	10	1.0	U
2-Chlorotoluene	ug/L	10	U	10	1.0	U	1.0	10	U	10	1.0	U
1,3,5-Trimethylbenzene	ug/L	10	U	10	1.0	U	1.0	10	U	10	1.0	U
4-Chlorotoluene	ug/L	10	U	10	1.0	U	1.0	10	U	10	1.0	U
tert-Butylbenzene	ug/L	10	U	10	1.0	U	1.0	10	U	10	1.0	U
1,2,4-Trimethylbenzene	ug/L	10	U	10	1.0	U	1.0	10	U	10	1.0	U
sec-Butylbenzene	ug/L	10	U	10	1.0	U	1.0	10	U	10	1.0	U
1,3-Dichlorobenzene	ug/L	10	U	10	1.0	U	1.0	10	U	10	1.0	U
p-Isopropyltoluene	ug/L	10	U	10	1.0	U	1.0	10	U	10	1.0	U
1,4-Dichlorobenzene	ug/L	10	U	10	1.0	U	1.0	10	U	10	1.0	U
n-Butylbenzene	ug/L	10	U	10	1.0	U	1.0	10	U	10	1.0	U
1,2-Dichlorobenzene	ug/L	10	U	10	1.0	U	1.0	10	U	10	1.0	U
1,2-Dibromo-3-chloropropane	ug/L	10	U	10	1.0	U	1.0	10	U	10	1.0	U
1,3,5-Trichlorobenzene	ug/L	10	U	10	1.0	U	1.0	10	U	10	1.0	U
1,2,4-Trichlorobenzene	ug/L	10	U	10	1.0	U	1.0	10	U	10	1.0	U
Hexachlorobutadiene	ug/L	10	U	10	1.0	U	1.0	10	U	10	1.0	U
Naphthalene	ug/L	10	U	10	1.0	U	1.0	10	U	10	1.0	U
1,2,3-Trichlorobenzene	ug/L	10	U	10	1.0	U	1.0	10	U	10	1.0	U

Appendix D - Day 6 Analytical Data (Soil)

Analyte	Units	Jar 4			Jar 5			Jar 6			Jar 10			Jar 11			Jar 12		
		Control			12.6 g Na2S2O8 + H2O2 (Day 6)			12.6 g Na2S2O8 + H2O2 (Day 6)			Control			12.6 g Na2S2O8 + NaFe(II)EDTA (Day 6)			12.6 g Na2S2O8 + NaFe(II)EDTA (Day 6)		
		39731	Qualifier	DL	39732	Qualifier	DL	39733	Qualifier	DL	39734	Qualifier	DL	39735	Qualifier	DL	39736	Qualifier	DL
Chemical Oxygen Demand (COD)	mg/Kg	9100		680	4500		730	5200		450	6500		330	15000		460	7000		300
% Solids	%	77.8		0.10	84.9		0.10	82.3		0.10	80.2		0.10	80.3		0.10	83.0		0.10
Dichlorodifluoromethane	ug/Kg	6.4	U	6.4	5.9	U	5.9	6.1	U	6.1	6.2	U	6.2	6.2	U	6.2	6.0	U	6.0
Chloromethane	ug/Kg	6.4	U	6.4	5.9	U	5.9	6.1	U	6.1	6.2	U	6.2	6.2	U	6.2	6.0	U	6.0
Vinyl chloride	ug/Kg	6.4	U	6.4	5.9	U	5.9	6.1	U	6.1	6.2	U	6.2	6.2	U	6.2	6.0	U	6.0
Bromomethane	ug/Kg	6.4	U	6.4	5.9	U	5.9	6.1	U	6.1	6.2	U	6.2	6.2	U	6.2	6.0	U	6.0
Chloroethane	ug/Kg	1200		64	5.9	U	5.9	6.1	U	6.1	1000		62	240		6.2	500		120
Trichlorofluoromethane	ug/Kg	6.4	U*	6.4	5.9	U*	5.9	6.1	U*	6.1	6.2	U*	6.2	6.2	U*	6.2	6.0	U*	6.0
1,1-Dichloroethene	ug/Kg	6.4	U	6.4	5.9	U	5.9	6.1	U	6.1	6.2	U	6.2	6.2	U	6.2	6.0	U	6.0
Carbon disulfide	ug/Kg	6.4	U	6.4	5.9	U	5.9	7.1		6.1	6.2	U	6.2	6.2	U	6.2	9.8		6.0
Acetone	ug/Kg	6.6		6.4	150		5.9	130		6.1	150		6.2	91		6.2	43		6.0
Methylene chloride	ug/Kg	5.5	J*	6.4	5.9	U	5.9	12		6.1	19		6.2	7.5		6.2	6.9		6.0
trans-1,2-Dichloroethene	ug/Kg	6.4	U	6.4	5.9	U	5.9	6.1	U	6.1	6.2	U	6.2	6.2	U	6.2	6.0	U	6.0
Methyl-tert-butyl-ether (MTBE)	ug/Kg	6.4	U	6.4	5.9	U	5.9	6.1	U	6.1	6.2	U	6.2	6.2	U	6.2	6.0	U	6.0
1,1-Dichloroethane	ug/Kg	53		6.4	5.9	U	5.9	6.1	U	6.1	42		6.2	8.1		6.2	30		6.0
2,2-Dichloropropane	ug/Kg	6.4	U	6.4	5.9	U	5.9	6.1	U	6.1	6.2	U	6.2	6.2	U	6.2	6.0	U	6.0
cis-1,2-Dichloroethene	ug/Kg	6.4	U	6.4	5.9	U	5.9	6.1	U	6.1	6.2	U	6.2	6.2	U	6.2	6.0	U	6.0
2-Butanone (MEK)	ug/Kg	6.4	U	6.4	5.9	U	5.9	6.1	U	6.1	6.2	U	6.2	6.2	U	6.2	6.0	U	6.0
Bromochloromethane	ug/Kg	6.4	U	6.4	5.9	U	5.9	6.1	U	6.1	6.2	U	6.2	6.2	U	6.2	6.0	U	6.0
Chloroform	ug/Kg	6.4	U	6.4	5.9	U	5.9	6.1	U	6.1	6.2	U	6.2	6.2	U	6.2	6.0	U	6.0
1,1,1-Trichloroethane	ug/Kg	1000		64	15		5.9	600		61	1000		62	390		62	3000		60
1,1-Dichloropropene	ug/Kg	6.4	U	6.4	5.9	U	5.9	6.1	U	6.1	6.2	U	6.2	6.2	U	6.2	6.0	U	6.0
Carbon tetrachloride	ug/Kg	6.4	U	6.4	5.9	U	5.9	6.1	U	6.1	6.2	U	6.2	6.2	U	6.2	6.0	U	6.0
Benzene	ug/Kg	6.4	U	6.4	5.9	U	5.9	6.1	U	6.1	6.2	U	6.2	6.2	U	6.2	6.0	U	6.0
1,2-Dichloroethane	ug/Kg	6.4	U	6.4	5.9	U	5.9	6.1	U	6.1	6.2	U	6.2	6.2	U	6.2	6.0	U	6.0
Trichloroethene	ug/Kg	6.4	U	6.4	5.9	U	5.9	6.1	U	6.1	6.2	U	6.2	6.2	U	6.2	6.0	U	6.0
1,2-Dichloropropane	ug/Kg	6.4	U	6.4	5.9	U	5.9	6.1	U	6.1	6.2	U	6.2	6.2	U	6.2	6.0	U	6.0
Dibromomethane	ug/Kg	6.4	U	6.4	5.9	U	5.9	6.1	U	6.1	6.2	U	6.2	6.2	U	6.2	6.0	U	6.0
Bromodichloromethane	ug/Kg	6.4	U	6.4	5.9	U	5.9	6.1	U	6.1	6.2	U	6.2	6.2	U	6.2	6.0	U	6.0
cis-1,3-Dichloropropene	ug/Kg	6.4	U	6.4	5.9	U	5.9	6.1	U	6.1	6.2	U	6.2	6.2	U	6.2	6.0	U	6.0
4-Methyl-2-pentanone (MIBK)	ug/Kg	6.4	U	6.4	5.9	U	5.9	6.1	U	6.1	6.2	U	6.2	6.2	U	6.2	6.0	U	6.0
Toluene	ug/Kg	6.4	U	6.4	5.9	U	5.9	6.1	U	6.1	6.2	U	6.2	6.2	U	6.2	6.0	U	6.0
trans-1,3-Dichloropropene	ug/Kg	6.4	U	6.4	5.9	U	5.9	6.1	U	6.1	6.2	U	6.2	6.2	U	6.2	6.0	U	6.0

Appendix D - Day 6 Analytical Data (Soil)

Analyte	Unit	Jar 4			Jar 5			Jar 6			Jar 10			Jar 11			Jar 12		
		Control			12.6 g Na2S2O8 + H2O2 (Day 6)			12.6 g Na2S2O8 + H2O2 (Day 6)			Control			12.6 g Na2S2O8 + NaFe(III)EDTA (Day 6)			12.6 g Na2S2O8 + NaFe(III)EDTA (Day 6)		
		39731	Qualifier	DL	39732	Qualifier	DL	39733	Qualifier	DL	39734	Qualifier	DL	39735	Qualifier	DL	39736	Qualifier	DL
1,1,2-Trichloroethane	ug/Kg	6.4	U	6.4	5.9	U	5.9	6.1	U	6.1	6.2	U	6.2	6.2	U	6.2	6.0	U	6.0
Tetrachloroethene	ug/Kg	3.7	J _A	6.4	5.9	U	5.9	6.1	U	6.1	3.5	J _A	6.2	6.2	U	6.2	6.0	U	6.0
1,3-Dichloropropane	ug/Kg	6.4	U	6.4	5.9	U	5.9	6.1	U	6.1	6.2	U	6.2	6.2	U	6.2	6.0	U	6.0
2-Hexanone	ug/Kg	6.4	U	6.4	5.9	U	5.9	6.1	U	6.1	6.2	U	6.2	6.2	U	6.2	6.0	U	6.0
Dibromochloromethane	ug/Kg	6.4	U	6.4	5.9	U	5.9	6.1	U	6.1	6.2	U	6.2	6.2	U	6.2	6.0	U	6.0
1,2-Dibromoethane (EDB)	ug/Kg	6.4	U	6.4	5.9	U	5.9	6.1	U	6.1	6.2	U	6.2	6.2	U	6.2	6.0	U	6.0
Chlorobenzene	ug/Kg	6.4	U	6.4	5.9	U	5.9	6.1	U	6.1	6.2	U	6.2	6.2	U	6.2	6.0	U	6.0
1,1,2-Tetrachloroethane	ug/Kg	6.4	U	6.4	5.9	U	5.9	6.1	U	6.1	6.2	U	6.2	6.2	U	6.2	6.0	U	6.0
Ethylbenzene	ug/Kg	6.4	U	6.4	5.9	U	5.9	6.1	U	6.1	6.2	U	6.2	6.2	U	6.2	6.0	U	6.0
m,p-Xylenes	ug/Kg	13	U	13	12	U	12	12	U	12	12	U	12	12	U	12	12	U	12
o-Xylene	ug/Kg	6.4	U	6.4	5.9	U	5.9	6.1	U	6.1	6.2	U	6.2	6.2	U	6.2	6.0	U	6.0
Sterene	ug/Kg	6.4	U	6.4	5.9	U	5.9	6.1	U	6.1	6.2	U	6.2	6.2	U	6.2	6.0	U	6.0
Bromoform	ug/Kg	6.4	U	6.4	5.9	U	5.9	6.1	U	6.1	6.2	U	6.2	6.2	U	6.2	6.0	U	6.0
Isopropylbenzene	ug/Kg	6.4	U	6.4	5.9	U	5.9	6.1	U	6.1	6.2	U	6.2	6.2	U	6.2	6.0	U	6.0
Bromobenzene	ug/Kg	6.4	U	6.4	5.9	U	5.9	6.1	U	6.1	6.2	U	6.2	6.2	U	6.2	6.0	U	6.0
1,1,2,2-Tetrachloroethane	ug/Kg	6.4	U	6.4	5.9	U	5.9	6.1	U	6.1	6.2	U	6.2	6.2	U	6.2	6.0	U	6.0
1,2,3-Trichloropropane	ug/Kg	6.4	U	6.4	5.9	U	5.9	6.1	U	6.1	6.2	U	6.2	6.2	U	6.2	6.0	U	6.0
n-Propylbenzene	ug/Kg	6.4	U	6.4	5.9	U	5.9	6.1	U	6.1	6.2	U	6.2	6.2	U	6.2	6.0	U	6.0
2-Chlorotoluene	ug/Kg	6.4	U	6.4	5.9	U	5.9	6.1	U	6.1	6.2	U	6.2	6.2	U	6.2	6.0	U	6.0
1,3,5-Trimethylbenzene	ug/Kg	6.4	U	6.4	5.9	U	5.9	6.1	U	6.1	6.2	U	6.2	6.2	U	6.2	6.0	U	6.0
4-Chlorotoluene	ug/Kg	6.4	U	6.4	5.9	U	5.9	6.1	U	6.1	6.2	U	6.2	6.2	U	6.2	6.0	U	6.0
tert-Butylbenzene	ug/Kg	6.4	U	6.4	5.9	U	5.9	6.1	U	6.1	6.2	U	6.2	6.2	U	6.2	6.0	U	6.0
1,2,4-Trimethylbenzene	ug/Kg	6.4	U	6.4	5.9	U	5.9	6.1	U	6.1	6.2	U	6.2	6.2	U	6.2	6.0	U	6.0
sec-Butylbenzene	ug/Kg	6.4	U	6.4	5.9	U	5.9	6.1	U	6.1	6.2	U	6.2	6.2	U	6.2	6.0	U	6.0
1,3-Dichlorobenzene	ug/Kg	6.4	U	6.4	5.9	U	5.9	6.1	U	6.1	6.2	U	6.2	6.2	U	6.2	6.0	U	6.0
p-Isopropyltoluene	ug/Kg	6.4	U	6.4	5.9	U	5.9	6.1	U	6.1	6.2	U	6.2	6.2	U	6.2	6.0	U	6.0
1,4-Dichlorobenzene	ug/Kg	6.4	U	6.4	5.9	U	5.9	6.1	U	6.1	6.2	U	6.2	6.2	U	6.2	6.0	U	6.0
n-Butylbenzene	ug/Kg	6.4	U	6.4	5.9	U	5.9	6.1	U	6.1	6.2	U	6.2	6.2	U	6.2	6.0	U	6.0
1,2-Dichlorobenzene	ug/Kg	6.4	U	6.4	5.9	U	5.9	6.1	U	6.1	6.2	U	6.2	6.2	U	6.2	6.0	U	6.0
1,2-Dibromo-3-chloropropane	ug/Kg	6.4	U	6.4	5.9	U	5.9	6.1	U	6.1	6.2	U	6.2	6.2	U	6.2	6.0	U	6.0
1,3,5-Trichlorobenzene	ug/Kg	6.4	U	6.4	5.9	U	5.9	6.1	U	6.1	6.2	U	6.2	6.2	U	6.2	6.0	U	6.0
1,2,4-Trichlorobenzene	ug/Kg	6.4	U	6.4	5.9	U	5.9	6.1	U	6.1	6.2	U	6.2	6.2	U	6.2	6.0	U	6.0
Hexachlorobutadiene	ug/Kg	6.4	U	6.4	5.9	U	5.9	6.1	U	6.1	6.2	U	6.2	6.2	U	6.2	6.0	U	6.0
Naphthalene	ug/Kg	6.4	U	6.4	5.9	U	5.9	6.1	U	6.1	6.2	U	6.2	6.2	U	6.2	6.0	U	6.0

U
H
M
J

analyte was not detected at or above the stated limit
Alternate peak selection upon analytical review
manually integrated compound
result is an estimated value below the reporting limit or a tentatively identified compound (TIC)
Batch QC is greater than reporting limit

Appendix E: Sodium Persulfate Titrations

June 23/05 - Sampling #1 (Day 2)

Sample ID	Burette Start (mL)	Burette End (mL)	mL of KMnO ₄ used to titrate the blank	mL of KMnO ₄ used to titrate the sample	Normality of KMnO ₄ solution used	Volume of sample (mL)	g/L sodium persulfate	g/L sodium persulfate consumed
Blank	0	19.7	19.7					
Control (Jar 1)	0	19.9	19.7	19.9	0.5	20	-0.6	control
6.3 g Na ₂ S ₂ O ₈ + H ₂ O ₂ (Jar 2)	0	19.9	19.7	19.9	0.5	20	-0.6	0
6.3 g Na ₂ S ₂ O ₈ + H ₂ O ₂ (Jar 3)	19.9	39.6	19.7	19.7	0.5	20	0.0	0
Control (Jar 7)	0	19.9	19.7	19.9	0.5	20	-0.6	control
6.3 g Na ₂ S ₂ O ₈ + NaFe(III)EDTA (Jar 8)	19.9	37.9	19.7	18	0.5	20	5.1	1.2
6.3 g Na ₂ S ₂ O ₈ + NaFe(III)EDTA (Jar 9)	0	18	19.7	18	0.5	20	5.1	1.2

June 27/05 - Sampling #2 (Day 6 from start of expt., Day 4 from 2nd persulfate application)

Sample ID	Burette Start (mL)	Burette End (mL)	mL of KMnO ₄ used to titrate the blank	mL of KMnO ₄ used to titrate the sample	Normality of KMnO ₄ solution used	Volume of sample (mL)	g/L sodium persulfate	g/L sodium persulfate
Blank	0	19.5	19.5					
Control (Jar 4)	20	39.5	19.5	19.5	0.5	20	0.0	control
12.6 g Na ₂ S ₂ O ₈ + H ₂ O ₂ (Jar 5)	0	19.8	19.5	19.8	0.5	20	-0.9	0
12.6 g Na ₂ S ₂ O ₈ + H ₂ O ₂ (Jar 6)	21	41.4	19.5	20.4	0.5	20	-2.7	0
Control (Jar 10)	1	20.5	19.5	19.5	0.5	20	0.0	control
12.6 g Na ₂ S ₂ O ₈ + NaFe(III)EDTA (Jar 11)	20.5	36.2	19.5	15.7	0.5	20	11.3	1.3
12.6 g Na ₂ S ₂ O ₈ + NaFe(III)EDTA (Jar 12)	28.3	44.5	19.5	16.2	0.5	20	9.8	2.8
12.6 g Na ₂ S ₂ O ₈ + NaFe(III)EDTA (Jar 11) Repeated	0	16	19.5	16.0	0.5	20	10.4	2.2
12.6 g Na ₂ S ₂ O ₈ + NaFe(III)EDTA (Jar 12) Repeated	16.1	32.2	19.5	16.1	0.5	20	10.1	2.5

APPENDIX H
LABORATORY DATA QA/QC REVIEW

DATA VALIDATION REVIEW
PROJECT: COLUMBIA CEMENT, FREEPORT, LONG ISLAND, NY
DATE SAMPLES COLLECTED: SEPTEMBER 20 AND 21, 2005
JOB NO.: 38546433

LAB REPORT No: J10451

1.0 INTRODUCTION

This Data Validation Review has been performed in accordance with the requirements specified in the USEPA Region II standard operating procedures (SOP) based on the Draft USEPA Contract Laboratory Program Scope of work (CLP SOW): Volatile Organics Analysis of Ambient Air in Canisters, dated December 1991, Revision VCAA01.0, and USEPA TO-15 methodology. The data validation review requirements are applied such that specifications of the methods take precedence over the specifications of the USEPA Region II data review guidelines in those instances where the specifications differ.

The objective of the review was to assess data usability and compliance with the New York State Department of Environmental Conservation (NYSDEC) Analytical Service Protocol (ASP) Category B data deliverable requirements. The Data Validation Review provides an interpretation of data usability based on the reported quality control parameters. Thirteen ambient air summa canister samples were collected by URS Corporation – Cranford, New Jersey, and submitted to Accutest Laboratories of Dayton, New Jersey (NYSDEC Certification No. 10983). Section 2.0 of this report summarizes the samples included in this review and the analyses performed. The samples were analyzed following USEPA TO-15 methodology. The laboratory analytical data set contained herein was prepared in accordance with NYSDEC ASP Category B Data Deliverable Format (Exhibit B).

The organic data quality review is based on the following parameters:

- * • Hold Times
 - * • Blank Contamination
 - * • GC/MS Performance Check (Tuning) Summaries
 - * • System Monitoring Compound (Surrogate) Recoveries
 - Internal Standard Area Performance
 - * • Initial and Continuing Calibration Results
 - * • Blank Spike (BS) and Blank Spike Duplicate (BSD) Summaries
 - Matrix Duplicate Summaries
 - * • Summa Canister Cleaning Certificaion
 - * • Target Compound Identification and Quantitation
- * All criteria were met for this parameter.

This report was prepared to provide a critical review of the laboratory analysis and reported chemical results. Overall, the data quality is acceptable. The results of the Data Validation Review are presented in Section 3.0. Data qualifiers, when applicable, are placed next to the

results so that the data user can assess the qualitative and/or quantitative reliability of the reported result.

2.0 SAMPLES INCLUDED IN REVIEW

Lab Report No. J10451

<u>Sample ID</u>	<u>Lab ID</u>	<u>Date Collected</u>	<u>Test Requested</u>
SG-05-07	J10451-01	9/21/05	TO-15
SG-05-05	J10451-02	9/21/05	TO-15
SG-05-03	J10451-03	9/21/05	TO-15
SG-05-11	J10451-04	9/21/05	TO-15
SG-05-04	J10451-05	9/21/05	TO-15
SG-05-01	J10451-06	9/21/05	TO-15
SG-05-02	J10451-07	9/20/05	TO-15
SG-05-AMB-W	J10451-08	9/20/05	TO-15
SG-05-08	J10451-09	9/20/05	TO-15
SG-05-09	J10451-10	9/20/05	TO-15
SG-05-AMB-E	J10451-11	9/20/05	TO-15
SG-05-10	J10451-12	9/20/05	TO-15
SG-05-06	J10451-13	9/21/05	TO-15

Legend:

TO-15 = Toxic Organic Compounds (Volatile Organic Compounds) following USEPA Method TO-15.

3.0 RESULTS

3.1 GENERAL COMMENTS

With regard to the data package deliverables, most of the NYSDEC ASP Category B Data Deliverable format requirements were met, with the exception of one correctable deficiency. Please note that this deficiency does not impact data usability.

- In the VOA analysis of Data Set J10451, the laboratory did not include the manual integration for the target compounds methyl ethyl ketone and 1,4-dioxane associated with the initial calibration standard 0.5 PPBV dated 9/26/05 at 15:41 (file ID 2W4556). The laboratory was contacted and the missing raw data was forwarded to URS. No further action is required from the laboratory.

3.2 ORGANIC QUALIFIERS

Hold Times: Technical hold times were assessed by comparing the sample dates with that of the preparation dates and/or analysis dates.

- The project samples associated with Data Set J10451 were analyzed within the required hold time for VOA analyses. No qualifier is required.

Blank Contamination: Laboratory method blank is an unused, certified canister that has not left the laboratory. The blank canister is pressurized with humidified, ultra-pure zero air and carried through the same analytical procedure as the investigative sample. Air canister

laboratory method blanks are used to identify whether the investigative samples have been contaminated during sample preparation, sample analysis or from a previous sample (instrument carry-over).

- No VOA target compound contaminants were detected in the laboratory method blanks associated with the reviewed data set. No qualifier is required.

GC/MS Performance Check (Tuning) Summary: Gas chromatograph/mass spectrometer (GC/MS) instrument tuning and performance checks are performed to ensure the instrument's ability to provide appropriate mass-resolution, identification and sensitivity.

- The bromofluorobenzene (BFB) tuning compound mass-ion abundance criteria for the volatile organic compound analyses were reported within control limits. No qualifier is required.

System Monitoring Compound (Surrogate) Recoveries: System monitoring compounds (surrogates) are those compounds, which are not expected to be detected in the investigative samples but are chemically similar to the analytes of interest. Surrogate compound percent recoveries are used to assess extraction efficiencies, possible matrix effects and overall analytical accuracy.

- The VOA surrogate recoveries fell within control limits for the reviewed project samples. No qualifier is required.

Internal Standards Area Performance: Internal standards are analytes of interest, which are added to the investigative samples prior to analysis to ensure that GC/MS sensitivity and responses remain stable. Internal standards are reported with the VOA analyses.

- The area count of the VOA internal standard, chlorobenzene-d5 (CBZ), fell outside the upper control limit for sample SG-05-01 (Data Set J10451). Due to the target compound concentrations exceeding the linear calibration range requirements, the sample was re-analyzed at a 1:200 dilution and the CBZ area count fell within control limits. The initial analysis of sample SG-05-01 was reported by the laboratory and deemed usable. The reported positive m/p-xylene and xylenes (total) results in this sample quantitated using the internal standard CBZ are regarded as estimated values and are flagged (J) estimated on the laboratory summary pages and on the summary table. There is no impact on the non-detected VOA results in sample SG-05-01 quantitated using this internal standard and no qualifier is required.
- The VOA internal standard area counts and retention times fell within control limits for the remaining project samples of Data Set J10451. No qualifier is required.

Initial and Continuing Calibration Results: Control limits for initial and continuing instrument calibrations are established to ensure that the instrument is capable of producing accurate quantitative data at the beginning and throughout each of the analyses.

- The VOA target compound initial and continuing calibration response factors, percent relative standard deviations (%RSD) and percent differences (%D)

associated with the reviewed project samples fell within acceptable control limits. No qualifier is required.

Blank Spike (BS) and Blank Spike Duplicate (BSD) Summaries: Blank spikes are blank samples fortified (spiked) with known concentrations of analytes of interest. The percent recoveries and/or duplicate results of the blank spike and their duplicates are used to assess extraction efficiencies, and overall analytical accuracy and precision.

- The VOA BS/BSD results (recoveries and relative percent differences or RPD) associated with Data Set J10451 fell within control limits providing a positive indication of the overall accuracy and precision associated with these analyses. No qualifier is required.

Matrix Duplicate Summaries: Duplicate samples are used to demonstrate acceptable laboratory method precision at the time of analysis. Duplicate results are used to assess possible matrix effects, and overall analytical accuracy and precision.

- The VOA SG-05-AMB-E Duplicate (DUP) RPD associated with sample SG-05-AMB-W and SG-05-AMB-E and the dilution analyses of samples SG-05-04, SG-05-10 and SG-05-06 (Data Set J10451) fell outside the control limits for ethanol. The positive ethanol results in samples SG-05-AMB-W and SG-05-AMB-E are regarded as estimated values and are flagged (J) on the laboratory summary pages and on the summary table. There is no impact on the data quality of ethanol in the dilution analyses of samples SG-05-04, SG-05-10 and SG-05-06 since ethanol results are reported from the initial analysis for these samples. No qualifier is required.
- The VOA DUP RPD fell within control limits for the remaining project samples of Data Set J10451. No qualifier is required.

Summa Canister Cleaning Certification: Each canister is evacuated and then pressurized with humidified ultra-pure zero air. This procedure is repeated a total of three times for each canister in the batch. One canister is randomly selected from the batch and then analyzed for clean test. Summa Canister Cleaning Certification verifies that the canister used to certify the canister batch is clean and free of any contaminants before sample collection.

- No VOA target compound contaminants were detected in the batch of canisters associated with the reviewed data set. No qualifier is required.

Target Compound Identification and Quantitation: The laboratory calculations are verified and compound identifications are reviewed and assessed by the data reviewer.

- Samples SG-05-07, SG-05-03, SG-05-08 and SG-05-09 (Data Set J10451) were analyzed at 1:4 and 1:2 dilutions, respectively, for VOA, resulting in elevated detection limits, due to target compound concentrations exceeding linear calibration range requirements. No qualifier is required.
- The following project samples were re-analyzed at elevated dilutions for VOA due to the target compound concentrations exceeding the linear calibration range

requirements. The VOA results reported on the summary tables are hybrid of both the initial and dilution analyses. No qualifier is required.

Data Set	Associated Sample and Dilution
J10451	SG-05-05 (1:8 and 1:20) SG-05-11 (1:8 and 1:200) SG-05-04 (1:8 and 1:200) SG-05-01 (1:40 and 1:200) SG-05-02 (1:8 and 1:80) SG-05-10 (1:8 and 1:20) SG-05-06 (1:8 and 1:20)

- The GC/MS raw data (quantitation reports, chromatograms and mass-spectra) were provided for review. No laboratory calculation errors were noted for samples selected for verification during the Data Validation Review. No further action is required from the laboratory.

Additional Comments

- As per the requirements, values calculated below the Reporting Limit (RL) should be considered estimated and are flagged (J) on the summary table.

4.0 CONCLUSIONS

Overall, the data quality is acceptable. The Data Validation Review has identified aspects of the analytical data that require qualification. Data qualifiers, when applicable, are placed next to the results so that the data user can assess the qualitative and/or quantitative reliability of the reported results. The laboratory analytical data contained herein are deemed usable and in compliance with the NYSDEC ASP Category B Data Deliverable format requirements. To confidently use any of the data within the data set, the data user should understand the limitations and qualifications presented.

DATA VALIDATION REVIEW
PROJECT: COLUMBIA CEMENT, FREEPORT, LONG ISLAND, NY
DATE SAMPLES COLLECTED: OCTOBER 6, 7 AND 8, 2004
JOB NO.: 38546433

LAB REPORT No: N80188

1.0 INTRODUCTION

This Data Validation Review has been performed in accordance with the requirements specified in the standard operating procedures for the validation of volatile organic data using USEPA Region II SW-846 Method 8260B, SOP HW-24, Rev. 1, dated June 1999 and SW-846 methodologies. The data validation review requirements are applied such that specifications of the methods take precedence over the specifications of the USEPA Region II data review guidelines in those instances where the specifications differ.

The objective of the review was to assess data usability and compliance with New York State Department of Environmental Conservation (NYSDEC) Analytical Service Protocol (ASP) Category B data deliverable requirements. The Data Validation Review provides an interpretation of data usability based on the reported quality control parameters. Soil samples and field-blank and trip-blank samples were collected by URS Corporation – Cranford, New Jersey, and submitted to Accutest Laboratories of Dayton, New Jersey (NYSDEC Certification No. 10983). Fifty-five soil samples, one field-blank sample and one trip-blank sample from Accutest Data Set N80188 were selected for data validation review to assess the overall data quality. Section 2.0 of this report summarizes the samples included in this review and the analyses performed. The samples were analyzed following USEPA SW-846 methodologies. The laboratory analytical data set contained herein was prepared in accordance with NYSDEC ASP Category B Data Deliverable Format (Exhibit B).

The organic data quality review is based on the following parameters:

- Hold Times
- Blank Contamination
- * GC/MS Performance Check (Tuning) Summaries
- * System Monitoring Compound (Surrogate) Recoveries
- * Internal Standard Area Performance
- Initial and Continuing Calibration Results
- * Matrix Spike (MS) and Matrix Spike Duplicate (MSD) Summaries
- * Target Compound Identification and Quantitation
- Tentatively Identified Compounds
- * All criteria were met for this parameter.

This report was prepared to provide a critical review of the laboratory analysis and reported chemical results. Overall, the data quality is acceptable. The results of the Data Validation Review are presented in Section 3.0. Data qualifiers, when applicable, are placed next to the results so that the data user can assess the qualitative and/or quantitative reliability of the reported result.

2.0 SAMPLES INCLUDED IN REVIEW

<u>Sample ID</u>	<u>Lab ID</u>	<u>Date Collected</u>	<u>Test Requested</u>
Lab Report No. N80188			
D-07-10-12	N80188-01	10/6/04	TCL VOA+10
D-07-16-18	N80188-02	10/6/04	TCL VOA+10
D-07-20-22	N80188-03	10/6/04	TCL VOA+10
T-01-16-18	N80188-06	10/6/04	TCL VOA+10
T-01-20-22	N80188-07	10/6/04	TCL VOA+10
T-02-16-18	N80188-10	10/6/04	TCL VOA+10
T-02-20-22	N80188-11	10/6/04	TCL VOA+10
T-02-24-26	N80188-12	10/6/04	TCL VOA+10
T-02-28-30	N80188-13	10/6/04	TCL VOA+10
T-03-16-18	N80188-14	10/6/04	TCL VOA+10
T-03-20-22	N80188-15	10/6/04	TCL VOA+10
T-03-24-26	N80188-16	10/6/04	TCL VOA+10
T-03-28-30	N80188-17	10/6/04	TCL VOA+10
T-04-16-18	N80188-18	10/6/04	TCL VOA+10
T-04-20-22	N80188-19	10/6/04	TCL VOA+10
T-05-16-18	N80188-22	10/6/04	TCL VOA+10
T-05-20-22	N80188-23	10/6/04	TCL VOA+10
T-06-16-18	N80188-26	10/6/04	TCL VOA+10
T-06-20-22	N80188-27	10/6/04	TCL VOA+10
T-07-16-18	N80188-30	10/7/04	TCL VOA+10
T-07-20-22	N80188-31	10/7/04	TCL VOA+10
T-07-24-26	N80188-32	10/7/04	TCL VOA+10
T-07-28-30	N80188-33	10/7/04	TCL VOA+10
T-08-16-18	N80188-34	10/7/04	TCL VOA+10
T-08-20-22	N80188-35	10/7/04	TCL VOA+10
T-09-16-18	N80188-38	10/7/04	TCL VOA+10
T-09-20-22	N80188-39	10/7/04	TCL VOA+10
T-08-14-15	N80188-42	10/7/04	TCL VOA+10
T-10-16-18	N80188-43	10/7/04	TCL VOA+10
T-10-20-22	N80188-44	10/7/04	TCL VOA+10
D-01-10-12	N80188-47	10/7/04	TCL VOA+10
D-01-16-18	N80188-48	10/7/04	TCL VOA+10
D-01-20-22	N80188-49	10/7/04	TCL VOA+10
D-02-10-12	N80188-52	10/7/04	TCL VOA+10
D-02-16-18	N80188-53	10/7/04	TCL VOA+10
D-02-20-22	N80188-54	10/7/04	TCL VOA+10
D-03-10-12	N80188-58	10/7/04	TCL VOA+10
D-03-16-18	N80188-59	10/8/04	TCL VOA+10
D-03-20-22	N80188-60	10/8/04	TCL VOA+10
D-04-10-12	N80188-63	10/8/04	TCL VOA+10
D-04-16-18	N80188-64	10/8/04	TCL VOA+10
D-04-20-22	N80188-65	10/8/04	TCL VOA+10
D-05-10-12	N80188-68	10/8/04	TCL VOA+10
D-05-16-18	N80188-69	10/8/04	TCL VOA+10
D-05-20-22	N80188-70	10/8/04	TCL VOA+10
D-06-10-12	N80188-73	10/8/04	TCL VOA+10
D-06-16-18	N80188-74	10/8/04	TCL VOA+10
D-06-20-22	N80188-75	10/8/04	TCL VOA+10
D-08-10-12	N80188-78	10/8/04	TCL VOA+10
D-08-16-18	N80188-79	10/8/04	TCL VOA+10
D-08-20-22	N80188-80	10/8/04	TCL VOA+10
D-08-24-26	N80188-81	10/8/04	TCL VOA+10
D-03-10-12	N80188-83	10/8/04	TCL VOA+10

<u>Sample ID</u>	<u>Lab ID</u>	<u>Date Collected</u>	<u>Test Requested</u>
Lab Report No. N80188 (continued)			
TRIP BLANK	N80188-84	10/8/04	TCL VOA+10
FIELD BLANK	N80188-85	10/8/04	TCL VOA+10
D-09-12-14	N80188-86	10/8/04	TCL VOA+10
D-09-14-16	N80188-87	10/8/04	TCL VOA+10

Legend:

TCL VOA +10 = Target Compound List Volatile Organic Compounds plus Forward Library Searches following USEPA SW-846 Method 8260B.

3.0 RESULTS

3.1 GENERAL COMMENTS

With regard to the data package deliverables, most of the NYSDEC ASP Category B Data Deliverable format requirements were met, with the exception of the following correctable deficiencies. Please note that these deficiencies do not impact data usability.

- In the TCL VOA analysis of Data Set N80188, the trip-blank sample (Trip Blank) collection date and time were reported incorrectly as 10/8/04 and 14:20, respectively, on the Sample Summary (page 6), Sample Preparation and Analysis Summary (page 209) and Internal Sample Tracking Chronicle (page 242). Based on a review of the associated Chain-of-Custody (page 218), the correct collection date and time are 10/4/04 and 18:00, respectively. This reviewer has corrected and initialed these transcriptional errors on the appropriate pages. No further action is required from the laboratory.
- In the TCL VOA analysis of sample D-08-10-12 (Data Set N80188), the result summary for the second dilution analysis (file ID S68042) was omitted from the result summary section. However, it was reported in the GC/MS sample data section 1-B. This reviewer has copied the associated pages (pages 1376 and 1377) and inserted them in the result summary section as pages 184A and 184B. No further action is required from the laboratory.

3.2 ORGANIC QUALIFIERS

Hold Times: Technical hold times were assessed by comparing the sample dates with that of the preparation dates and/or analysis dates.

- The following samples were analyzed 3 to 5 days outside the 14-day hold time requirement for TCL VOA. The positive and non-detected TCL VOA results in these samples are regarded as estimated values and are flagged (J) and (UJ), respectively, on the laboratory summary pages and on the summary table.

Data Set	Associated Sample
N80188	5 days: T-02-24-26, T-02-28-30, T-03-24-26 and T-03-28-30; 4 days: T-07-24-26 and T-07-28-30 and 3 days: D-08-24-26

- The remaining project samples associated with Data Set N80188 were analyzed within the required hold time for TCL VOA analyses. No qualifier is required.
- The sample cooler temperatures upon laboratory verified time of sample receipt (VTSR) fell within the 4°C (+2°C) requirement. No qualifier is required.

Blank Contamination: Laboratory method blanks are clean liquid and/or solid matrix samples prepared by the analytical laboratory and analyzed in the same manner as the investigative samples. Water laboratory method blanks are used to identify whether investigative samples have been contaminated during sample preparation, sample analysis or from a previous sample (instrument carry-over).

Field-blanks consist of deionized water poured over or through decontaminated sampling equipment and collected into the sample bottles. Field-blanks measure contamination potentially caused by inadequate decontamination of sampling equipment. Trip-blanks are carbon-free deionized water samples that accompany volatile investigative samples during each stage of shipment, storage and analysis. Trip-blanks are used to assess the potential for artificial introduction of volatile compounds into the investigative samples during the transportation and sample handling processes.

- No TCL VOA contaminants were detected in the laboratory method blanks, as well as in the storage blank, field-blank and trip-blank samples associated with the reviewed project samples. No qualifier is required.
- VOA Tentatively Identified Compounds (TICs), consisting of pentafluorobenzene, was tentatively identified in the laboratory method blanks (VBLK23, VBLK24 and VBLK25) associated with Data Set N80188. The positive pentafluorobenzene TICs tentatively identified in the following project samples, eluting at similar retention times, are qualitatively questionable. These TICs are negated on the laboratory summary pages and on the total estimated VOA TICs reported on the summary table.

Associated samples

D-07-20-22, T-04-20-22, T-05-20-22, T-06-16-18,
T-06-20-22, T-07-16-18, T-07-20-22, T-08-20-22,
T-09-16-18 and T-09-20-22

- VOA TICs consisting of 1,4-dichlorobenzene-d4, was tentatively identified in the laboratory method blank (VBLK26) associated with Data Set N80188. The positive 1,4-dichlorobenzene TICs, eluting at similar retention times and tentatively identified in samples T-03-16-18, D-04-16-18, D-04-20-22 and D-05-10-12, are qualitatively questionable. These TICs are negated on the laboratory summary pages and on the total estimated VOA TICs reported on the summary table.

GC/MS Performance Check (Tuning) Summary: Gas chromatograph/mass spectrometer (GC/MS) instrument tuning and performance checks are performed to ensure the instrument's ability to provide appropriate mass-resolution, identification and sensitivity.

- The bromofluorobenzene (BFB) tuning compound mass-ion abundance criteria for the volatile organic compound analyses were reported within control limits. No qualifier is required.

System Monitoring Compound (Surrogate) Recoveries: System monitoring compounds (surrogates) are those compounds, which are not expected to be detected in the investigative samples but which are chemically similar to the analytes of interest. Surrogate compound percent recoveries are used to assess extraction efficiencies, possible matrix effects and overall analytical accuracy.

- The VOA surrogate recoveries fell within control limits for the reviewed project samples of Data Set N80188. No qualifier is required.

Internal Standards Area Performance: Internal standards are analytes of interest, which are added to the investigative samples prior to analysis to ensure that GC/MS sensitivity and responses remain stable. Internal standards are reported with the volatile analysis.

- The TCL VOA internal standard area counts and retention times fell within control limits for the reviewed project samples associated with Data Set N80188. No qualifier is required.

Initial and Continuing Calibration Results: Control limits for initial and continuing instrument calibrations are established to ensure that the instrument is capable of producing accurate quantitative data at the beginning and throughout each of the analyses.

- The TCL VOA target compound initial and continuing calibration response factors associated with the reviewed project samples fell within acceptable control limits. No qualifier is required.
- High percent relative standard deviation (%RSD >15 but <50) was reported for the initial calibration response factors for the TCL VOA compound, acetone, associated with the reviewed project samples of Data Set N80188 (with the exception of samples D-07-10-12, T-03-20-22, Trip Blank, Field Blank, D-07-10-12 DL, T-03-16-18 DL, T-03-20-22 DL, T-08-16-18 DL, D-01-16-18 DL and D-08-16-18 DL). The positive acetone results in the referenced project samples are regarded as estimated values and are flagged (J) on the laboratory summary pages and on the summary tables. There is no impact on the non-detected acetone results in the associated project samples and no qualifier is required.
- A high percent difference (%D >20 but <90) was reported between the initial and continuing calibration response factors for the following TCL VOA compounds associated with the reviewed project samples. The positive and non-detected TCL VOA results are regarded as estimated values and are flagged (J) and (UJ), respectively, on the laboratory summary pages and on the summary tables.

Data Set	Compounds	Associated Samples
N80188	Acetone, 2-Butanone and 2-Hexanone	T-09-16-18, T-08-14-15, T-10-20-22, D-01-10-12, D-01-20-22, D-02-10-12, D-02-20-22, T-02-20-22 DL, T-07-20-22 DL, T-02-16-18, T-10-16-18, D-02-16-18, D-03-10-12, D-06-10-12, D-08-20-22 and D-03-10-12
	Acetone and 2-Hexanone	T-03-16-18, D-03-16-18, D-03-20-22, D-04-10-12, D-04-16-18, D-04-20-22, D-05-10-12, D-05-16-18, D-05-20-22, D-06-16-18, D-06-20-22, D-08-16-18, D-09-12-14 and D-09-14-16
	2-Hexanone	T-08-16-18, D-01-16-18, D-08-10-12 and T-02-16-18 DL
	Acetone and 4-Methyl-2-Pentanone	T-08-16-18 DL, D-01-16-18 DL and D-08-10-12 DL
	Acetone and 2-Butanone	T-03-20-22 DL

Matrix Spike (MS) and Matrix Spike Duplicate (MSD) Summaries: Matrix spikes are samples spiked with known concentrations of analytes of interest. The MS/MSD percent recoveries and duplicate results are used to assess extraction efficiencies, possible matrix effects, and overall analytical accuracy and precision.

Blank spikes (BS) are blank samples fortified (spiked) with known concentrations of compounds of interest. The blank spike percent recoveries are used to assess extraction efficiencies and overall analytical accuracy.

- The TCL VOA MS/MSD/BS results (recoveries and relative percent difference or RPD) associated with Data Set N80188 fell within acceptable control limits providing a positive indication of the overall accuracy and precision associated with these analyses. No qualifier is required.

Target Compound Identification and Quantitation: The laboratory calculations are verified and compound identifications are reviewed and assessed by the data reviewer.

- The following project samples were re-analyzed at elevated dilutions for TCL VOA due to the target compound concentrations exceeding the linear calibration range requirements. Both the TCL VOA initial and dilution analysis results are reported on the laboratory summary pages. No qualifier is required.

Data Set	Associated Sample and Dilution
N80188	T-02-16-18 (undiluted and 1:2) T-02-20-22 (undiluted and 1:5) T-07-20-22 (undiluted and 1:5)

- The following project samples were re-analyzed at elevated dilutions (as a medium level soil) for TCL VOA due to the target compound concentrations exceeding the linear calibration range requirements. Both the TCL VOA initial and dilution

analysis results are reported on the laboratory summary pages. No qualifier is required.

Data Set	Associated Sample and Dilution
N80188	D-07-10-12 (1:50 and 1:500) T-03-16-18 (1:10 and 1:100) T-03-20-22 (1:250 and 1:12,500) T-08-16-18 (1:5 and 1:500) D-01-16-18 (1:10, 1:1,000 and 1:2,000) D-08-10-12 (1:10, 1:500 and 1:2,500)

- Although no target compounds exceeded linear calibration range requirements, sample D-04-10-12 was analyzed at a 1:5 dilution for TCL VOA resulting in elevated detection limits. A review of the sample chromatogram indicates high extraneous chromatographic peaks, which requires the dilution. No qualifier is required.
- The GC/MS raw data (quantitation reports, chromatograms and mass-spectra) were provided for review. No laboratory calculation errors were noted for samples selected for verification during the data validation review. No further action is required from the laboratory.

Tentatively Identified Compounds: In addition to the specific target compounds identified, 10 non-target volatile organic compounds of greatest apparent concentration were tentatively identified by a computerized search of the National Bureau of Standards (NBS) mass-spectral library. A mass-spectral interpretation specialist compares the sample mass-spectrum to the library search and assigns a tentative identification. The validity of the TICs was evaluated based upon the identifications made by the laboratory, and the following comments are offered:

- The majority of the VOA TICs identified in the samples associated with Data Set N80188 are alkyl benzenes, alkylated cycloalkanes, cycloalkanes/alkenes, alkylated alkanes, alkanes, alkenes, substituted alkanes, polynuclear aromatic hydrocarbons (PAH), diethyl sulfide, diethyl disulfide and unknowns.
- Indane, 1,4-dichlorobenzene, naphthalene, 2-methyl naphthalene and/or 1-methyl naphthalene were tentatively identified in samples T-01-16-18, T-02-16-18, T-02-20-22, T-03-16-18, T-04-16-18, D-01-16-18, D-02-10-12 and D-04-10-12. It should be noted that the aforementioned compounds are Base Neutral (BN) target compounds and since BN analysis was not requested for the project samples, these TIC identifications are deemed acceptable and are included in the total estimated VOA TICs reported on the summary table.

Additional Comments

- As per the requirements, values calculated below the Reporting Limit (RL) should be considered estimated and are flagged (J) on the summary table.

4.0 CONCLUSIONS

Overall, the data quality is acceptable. The Data Validation Review has identified aspects of the analytical data that require qualification. Data qualifiers, when applicable, are placed next to the results so that the data user can assess the qualitative and/or quantitative reliability of the reported results. The laboratory analytical data contained herein are deemed usable and in compliance with the NYSDEC ASP Category B Deliverable Format requirements. To confidently use any of the data within the data set, the data user should understand the limitations and qualifications presented.

DATA VALIDATION REVIEW
PROJECT: COLUMBIA CEMENT, FREEPORT, LONG ISLAND, NY
DATE SAMPLES COLLECTED: SEPTEMBER 20 AND 21, 2005
JOB NO.: 38546433

LAB REPORT No: J10451

1.0 INTRODUCTION

This Data Validation Review has been performed in accordance with the requirements specified in the USEPA Region II standard operating procedures (SOP) based on the Draft USEPA Contract Laboratory Program Scope of work (CLP SOW): Volatile Organics Analysis of Ambient Air in Canisters, dated December 1991, Revision VCAA01.0, and USEPA TO-15 methodology. The data validation review requirements are applied such that specifications of the methods take precedence over the specifications of the USEPA Region II data review guidelines in those instances where the specifications differ.

The objective of the review was to assess data usability and compliance with the New York State Department of Environmental Conservation (NYSDEC) Analytical Service Protocol (ASP) Category B data deliverable requirements. The Data Validation Review provides an interpretation of data usability based on the reported quality control parameters. Thirteen ambient air summa canister samples were collected by URS Corporation – Cranford, New Jersey, and submitted to Accutest Laboratories of Dayton, New Jersey (NYSDEC Certification No. 10983). Section 2.0 of this report summarizes the samples included in this review and the analyses performed. The samples were analyzed following USEPA TO-15 methodology. The laboratory analytical data set contained herein was prepared in accordance with NYSDEC ASP Category B Data Deliverable Format (Exhibit B).

The organic data quality review is based on the following parameters:

- * • Hold Times
 - * • Blank Contamination
 - * • GC/MS Performance Check (Tuning) Summaries
 - * • System Monitoring Compound (Surrogate) Recoveries
 - Internal Standard Area Performance
 - * • Initial and Continuing Calibration Results
 - * • Blank Spike (BS) and Blank Spike Duplicate (BSD) Summaries
 - Matrix Duplicate Summaries
 - * • Summa Canister Cleaning Certificaion
 - * • Target Compound Identification and Quantitation
- * All criteria were met for this parameter.

This report was prepared to provide a critical review of the laboratory analysis and reported chemical results. Overall, the data quality is acceptable. The results of the Data Validation Review are presented in Section 3.0. Data qualifiers, when applicable, are placed next to the

results so that the data user can assess the qualitative and/or quantitative reliability of the reported result.

2.0 SAMPLES INCLUDED IN REVIEW

Lab Report No. J10451

<u>Sample ID</u>	<u>Lab ID</u>	<u>Date Collected</u>	<u>Test Requested</u>
SG-05-07	J10451-01	9/21/05	TO-15
SG-05-05	J10451-02	9/21/05	TO-15
SG-05-03	J10451-03	9/21/05	TO-15
SG-05-11	J10451-04	9/21/05	TO-15
SG-05-04	J10451-05	9/21/05	TO-15
SG-05-01	J10451-06	9/21/05	TO-15
SG-05-02	J10451-07	9/20/05	TO-15
SG-05-AMB-W	J10451-08	9/20/05	TO-15
SG-05-08	J10451-09	9/20/05	TO-15
SG-05-09	J10451-10	9/20/05	TO-15
SG-05-AMB-E	J10451-11	9/20/05	TO-15
SG-05-10	J10451-12	9/20/05	TO-15
SG-05-06	J10451-13	9/21/05	TO-15

Legend:

TO-15 = Toxic Organic Compounds (Volatile Organic Compounds) following USEPA Method TO-15.

3.0 RESULTS

3.1 GENERAL COMMENTS

With regard to the data package deliverables, most of the NYSDEC ASP Category B Data Deliverable format requirements were met, with the exception of one correctable deficiency. Please note that this deficiency does not impact data usability.

- In the VOA analysis of Data Set J10451, the laboratory did not include the manual integration for the target compounds methyl ethyl ketone and 1,4-dioxane associated with the initial calibration standard 0.5 PPBV dated 9/26/05 at 15:41 (file ID 2W4556). The laboratory was contacted and the missing raw data was forwarded to URS. No further action is required from the laboratory.

3.2 ORGANIC QUALIFIERS

Hold Times: Technical hold times were assessed by comparing the sample dates with that of the preparation dates and/or analysis dates.

- The project samples associated with Data Set J10451 were analyzed within the required hold time for VOA analyses. No qualifier is required.

Blank Contamination: Laboratory method blank is an unused, certified canister that has not left the laboratory. The blank canister is pressurized with humidified, ultra-pure zero air and carried through the same analytical procedure as the investigative sample. Air canister

laboratory method blanks are used to identify whether the investigative samples have been contaminated during sample preparation, sample analysis or from a previous sample (instrument carry-over).

- No VOA target compound contaminants were detected in the laboratory method blanks associated with the reviewed data set. No qualifier is required.

GC/MS Performance Check (Tuning) Summary: Gas chromatograph/mass spectrometer (GC/MS) instrument tuning and performance checks are performed to ensure the instrument's ability to provide appropriate mass-resolution, identification and sensitivity.

- The bromofluorobenzene (BFB) tuning compound mass-ion abundance criteria for the volatile organic compound analyses were reported within control limits. No qualifier is required.

System Monitoring Compound (Surrogate) Recoveries: System monitoring compounds (surrogates) are those compounds, which are not expected to be detected in the investigative samples but are chemically similar to the analytes of interest. Surrogate compound percent recoveries are used to assess extraction efficiencies, possible matrix effects and overall analytical accuracy.

- The VOA surrogate recoveries fell within control limits for the reviewed project samples. No qualifier is required.

Internal Standards Area Performance: Internal standards are analytes of interest, which are added to the investigative samples prior to analysis to ensure that GC/MS sensitivity and responses remain stable. Internal standards are reported with the VOA analyses.

- The area count of the VOA internal standard, chlorobenzene-d5 (CBZ), fell outside the upper control limit for sample SG-05-01 (Data Set J10451). Due to the target compound concentrations exceeding the linear calibration range requirements, the sample was re-analyzed at a 1:200 dilution and the CBZ area count fell within control limits. The initial analysis of sample SG-05-01 was reported by the laboratory and deemed usable. The reported positive m/p-xylene and xylenes (total) results in this sample quantitated using the internal standard CBZ are regarded as estimated values and are flagged (J) estimated on the laboratory summary pages and on the summary table. There is no impact on the non-detected VOA results in sample SG-05-01 quantitated using this internal standard and no qualifier is required.
- The VOA internal standard area counts and retention times fell within control limits for the remaining project samples of Data Set J10451. No qualifier is required.

Initial and Continuing Calibration Results: Control limits for initial and continuing instrument calibrations are established to ensure that the instrument is capable of producing accurate quantitative data at the beginning and throughout each of the analyses.

- The VOA target compound initial and continuing calibration response factors, percent relative standard deviations (%RSD) and percent differences (%D)

associated with the reviewed project samples fell within acceptable control limits. No qualifier is required.

Blank Spike (BS) and Blank Spike Duplicate (BSD) Summaries: Blank spikes are blank samples fortified (spiked) with known concentrations of analytes of interest. The percent recoveries and/or duplicate results of the blank spike and their duplicates are used to assess extraction efficiencies, and overall analytical accuracy and precision.

- The VOA BS/BSD results (recoveries and relative percent differences or RPD) associated with Data Set J10451 fell within control limits providing a positive indication of the overall accuracy and precision associated with these analyses. No qualifier is required.

Matrix Duplicate Summaries: Duplicate samples are used to demonstrate acceptable laboratory method precision at the time of analysis. Duplicate results are used to assess possible matrix effects, and overall analytical accuracy and precision.

- The VOA SG-05-AMB-E Duplicate (DUP) RPD associated with sample SG-05-AMB-W and SG-05-AMB-E and the dilution analyses of samples SG-05-04, SG-05-10 and SG-05-06 (Data Set J10451) fell outside the control limits for ethanol. The positive ethanol results in samples SG-05-AMB-W and SG-05-AMB-E are regarded as estimated values and are flagged (J) on the laboratory summary pages and on the summary table. There is no impact on the data quality of ethanol in the dilution analyses of samples SG-05-04, SG-05-10 and SG-05-06 since ethanol results are reported from the initial analysis for these samples. No qualifier is required.
- The VOA DUP RPD fell within control limits for the remaining project samples of Data Set J10451. No qualifier is required.

Summa Canister Cleaning Certification: Each canister is evacuated and then pressurized with humidified ultra-pure zero air. This procedure is repeated a total of three times for each canister in the batch. One canister is randomly selected from the batch and then analyzed for clean test. Summa Canister Cleaning Certification verifies that the canister used to certify the canister batch is clean and free of any contaminants before sample collection.

- No VOA target compound contaminants were detected in the batch of canisters associated with the reviewed data set. No qualifier is required.

Target Compound Identification and Quantitation: The laboratory calculations are verified and compound identifications are reviewed and assessed by the data reviewer.

- Samples SG-05-07, SG-05-03, SG-05-08 and SG-05-09 (Data Set J10451) were analyzed at 1:4 and 1:2 dilutions, respectively, for VOA, resulting in elevated detection limits, due to target compound concentrations exceeding linear calibration range requirements. No qualifier is required.
- The following project samples were re-analyzed at elevated dilutions for VOA due to the target compound concentrations exceeding the linear calibration range

requirements. The VOA results reported on the summary tables are hybrid of both the initial and dilution analyses. No qualifier is required.

Data Set	Associated Sample and Dilution
J10451	SG-05-05 (1:8 and 1:20) SG-05-11 (1:8 and 1:200) SG-05-04 (1:8 and 1:200) SG-05-01 (1:40 and 1:200) SG-05-02 (1:8 and 1:80) SG-05-10 (1:8 and 1:20) SG-05-06 (1:8 and 1:20)

- The GC/MS raw data (quantitation reports, chromatograms and mass-spectra) were provided for review. No laboratory calculation errors were noted for samples selected for verification during the Data Validation Review. No further action is required from the laboratory.

Additional Comments

- As per the requirements, values calculated below the Reporting Limit (RL) should be considered estimated and are flagged (J) on the summary table.

4.0 CONCLUSIONS

Overall, the data quality is acceptable. The Data Validation Review has identified aspects of the analytical data that require qualification. Data qualifiers, when applicable, are placed next to the results so that the data user can assess the qualitative and/or quantitative reliability of the reported results. The laboratory analytical data contained herein are deemed usable and in compliance with the NYSDEC ASP Category B Data Deliverable format requirements. To confidently use any of the data within the data set, the data user should understand the limitations and qualifications presented.

DATA VALIDATION REVIEW
PROJECT: COLUMBIA CEMENT, FREEPORT, LONG ISLAND, NY
DATE SAMPLES COLLECTED: JUNE 10, 2004
JOB NO.: 38546433

**LAB REPORT No: N69045, N69045A, N69045X, N69150, N69150A, N69150X,
N69286, N69286A, N69286AX, N69400, N69400A & N69400AX**

1.0 INTRODUCTION

This Data Validation Review has been performed in accordance with the requirements specified in: (1) the standard operating procedures for the validation of volatile organic data using USEPA Region II SW-846 Method 8260B, SOP HW-24, Rev. 1, dated June 1999; (2) CLP Organics Data Review and Preliminary Data Review, SOP HW-6, Revision 12, dated March 1993; Evaluation of Metals Data for the CLP Program, SOP HW-2, Revision 11, dated January 1992; and SW-846, 600 Series and Standard Methods for the Evaluation of Water and Wastewater, 18th Edition (Standard Methods) methodologies. The quality assurance review requirements are applied such that specifications of the methods take precedence over the specifications of the USEPA Region II data review guidelines in those instances where the specifications differ.

The objective of the review was to assess data usability and compliance with New York Department of Environmental Conservation (NYSDEC) ASP Category B deliverable requirements. The Data Validation Review provides an interpretation of data usability based on the reported quality control parameters. Groundwater samples and field-blank samples were collected by URS Corporation – Cranford, New Jersey, and submitted to Accutest Laboratories of Dayton, New Jersey (NYSDEC Certification No. 10983). The Divalent Manganese samples submitted to Accutest were sub-contracted to Microseeps Laboratory of Pittsburgh, Pennsylvania. Seventeen groundwater samples and one field-blank sample from Accutest Data Sets N69045, N69045A, N69045X, N69150, N69150A, N69150X, N69286, N69286A, N69286X, N69400, N69400A and N69400AX were selected for quality assurance review to assess the overall data quality. Section 2.0 of this report summarizes the samples included in this review and the analyses performed. The groundwater samples were analyzed following USEPA SW846, 600 Series and Standard Methodologies. The laboratory analytical data set contained herein was prepared in accordance with NYDEC ASP Category B Data Deliverable Format (Exhibit B).

The organic data quality review is based on the following parameters:

- * Hold Times
- * Blank Contamination
- * GC/MS Performance Check (Tuning) Summaries
- * System Monitoring Compound (Surrogate) Recoveries
- * Internal Standard Area Performance
- * Initial and Continuing Calibration Results
- * Matrix Spike (MS) and Matrix Spike Duplicate (MSD) Summaries
- * Target Compound Identification and Quantitation
- Tentatively Identified Compounds

The inorganic and conventional parameter data quality review is based on the following parameters:

- * Hold Times
- * Blank Contamination
- * Instrument Calibration and Verifications
- * Inductively Coupled Plasma (ICP) Interference Check Sample (ICS) Results
- * Laboratory Control Sample (LCS) Results
- * Matrix Spike (MS) and Duplicate (DU) Summaries
- * ICP Serial Dilution Results
- * Target Analyte Identification and Quantitation

- * All criteria were met for this parameter

This report was prepared to provide a critical review of the laboratory analysis and reported chemical results. Overall, the data quality is acceptable. The results of the Data Validation Review are presented in Section 3.0. Data qualifiers, when applicable, are placed next to the results so that the data user can assess the qualitative and/or quantitative reliability of the reported result.

2.0 SAMPLES INCLUDED IN REVIEW

<u>Sample ID</u>	<u>Lab ID</u>	<u>Date Collected</u>	<u>Test Requested</u>
Lab Report No. N69045A			
MW-1S	N69045-1	6/07/04	TCL VOA+10
MW-1D-97	N69045-2	6/07/04	TCL VOA+10
Lab Report No. N69045			
MW-1S	N69045-1A	6/07/04	(total) Iron, Dissolved Gases & Conventional Parameters
MW-1D-97	N69045-2A	6/07/04	(total) Iron, (total) Manganese Dissolved Gases & Conventional Parameters
Lab Report No. N69045X			
MW-1D-97	N69045-2X	6/07/04	Divalent Manganese
Lab Report No. N69150A			
MW-97-1S	N69150-1	6/08/04	TCL VOA+10
MW-98-9D	N69150-2	6/08/04	TCL VOA+10
MW-9D-98D	N69150-3	6/08/04	TCL VOA+10
MW-97-2S	N69150-4	6/08/04	TCL VOA+10
MW-98-10D	N69150-5	6/08/04	TCL VOA+10

Lab Report No. N69150

MW-97-1S	N69150-1A	6/08/04	(total) Iron, (total) Manganese Dissolved Gases & Conventional Parameters
MW-98-9D	N69150-2A	6/08/04	(total) Iron, (total) Manganese Dissolved Gases & Conventional Parameters
MW-9D-98D	N69150-3A	6/08/04	(total) Iron, (total) Manganese Dissolved Gases & Conventional Parameters
MW-97-2S	N69150-4A	6/08/04	(total) Iron, (total) Manganese Dissolved Gases & Conventional Parameters
MW-98-10D	N69150-5A	6/08/04	(total) Iron, (total) Manganese Dissolved Gases & Conventional Parameters

Lab Report No. N69150X

MW-97-1S	N69150-1X	6/08/04	Divalent Manganese
MW-98-9D	N69150-2X	6/08/04	Divalent Manganese
MW-9D-98D	N69150-3X	6/08/04	Divalent Manganese
MW-97-2S	N69150-4X	6/08/04	Divalent Manganese

Lab Report No. N69286

FB060904	N69286-1	6/09/04	TCL VOA+10
MW-97-6S	N69286-2	6/09/04	TCL VOA+10
MW-97-7S	N69286-3	6/09/04	TCL VOA+10
MW-97-3S	N69286-4	6/09/04	TCL VOA+10
MW-97-8D	N69286-5	6/09/04	TCL VOA+10
MW-97-8S	N69286-6	6/09/04	TCL VOA+10
MW-00-11A	N69286-7	6/09/04	TCL VOA+10

Lab Report No. N69286A

MW-97-6S	N69286-2A	6/09/04	(total) Iron, (total) Manganese Dissolved Gases & Conventional Parameters
MW-97-3S	N69286-4A	6/09/04	(total) Iron, (total) Manganese Dissolved Gases & Conventional Parameters
MW-98-8D	N69286-5A	6/09/04	(total) Iron, (total) Manganese Dissolved Gases & Conventional Parameters
MW-98-8S	N69286-6A	6/09/04	(total) Iron, (total) Manganese Dissolved Gases & Conventional Parameters

Lab Report No. N69286AX

MW-97-6S	N69286-2X	6/09/04	Divalent Manganese
MW-97-3S	N69286-4X	6/09/04	Divalent Manganese
MW-98-8D	N69286-5X	6/09/04	Divalent Manganese
MW-98-8S	N69286-6X	6/09/04	Divalent Manganese

Lab Report No. N69400

MW-03-3S	N69400-1	6/10/04	TCL VOA+10
MW-00-12D	N69400-2	6/10/04	TCL VOA+10
MW-97-4S	N69400-3	6/10/04	TCL VOA+10
MW-97-5S	N69400-4	6/10/04	TCL VOA+10

Lab Report No. N69400A

MW-03-3S	N69400-1A	6/10/04	(total) Iron, (total) Manganese Dissolved Gases & Conventional Parameters
MW-00-12D	N69400-2A	6/10/04	(total) Iron, Dissolved Gases & Conventional Parameters
MW-97-4S	N69400-3A	6/10/04	(total) Iron, Dissolved Gases & Conventional Parameters
MW-97-5S	N69400-4A	6/10/04	(total) Iron, Manganese, Dissolved Gases & Conventional Parameters

Lab Report No. N69400AX

MW-03-3S	N69400-1X	6/10/04	Divalent Manganese
MW-97-5S	N69400-4X	6/10/04	Divalent Manganese

Legend:

TCL VOA +10	= Target Compound List Volatile Organic Compounds plus Forward Library Searches following USEPA SW-846 Method 8260B.
Dissolved Gases	= Consisting of Methane, Ethane & Ethene following SW846 Method 8015.
(total) Iron	= USEPA Method 200.7 and SW846 Method 6010B.
(total) Manganese	= USEPA Method 200.7 and SW846 Method 6010B.
Conventional Parameters	= Alkalinity, Nitrate, Chloride, Sulfate, Ferrous Iron, Divalent Manganese and Total Organic Carbon (TOC) following USEPA 600 Series Methodologies (Alkalinity by USEPA Method 310.1, Nitrate by USEPA Method 353.2 and Standard Methods for the Analysis of Water & Waster 18 th Edition, Chloride, sulfate & divalent manganese by USEPA Method 300 and SW846 Method 9056, TOC by USEPA Method 415.1 and Ferrous Iron by Standard Methods for the Analysis of Water & Wastewater 18 th Edition).

3.0 RESULTS

3.1 GENERAL COMMENTS

With regard to the data package deliverables, most of the NYSDEC ASP Category B Data Deliverable format requirements were met, with the exception of the following correctable deficiencies. Please note that these deficiencies, for the most part, do not impact data usability. The laboratory was contacted and this report may be amended upon the receipt of the lab corrections.

- A transcription error was identified during review of the ferrous iron analyses for project samples associated with Accutest Data Set N69045. The date of analysis reported (6/4/04) by the laboratory on the results summary pages (pp. 16, 19, 375 &

376) and analysis run log (page 537) is incorrect. Based on review of the raw data, the correct date of analysis is 6/7/04. The laboratory was contacted and the corrected data was submitted to URS. No further action is required from the laboratory.

- In the divalent manganese analysis of Accutest Data Sets N69045X, N69150X, N69286X and N69400AX, the raw data (ion chromatographs) were omitted from the data sets reviewed. The laboratory was contacted and the required data were submitted to URS. No further action is required from the laboratory.
- On the chain-of-custody (COC) for project samples associated with Accutest Data Set N69045X, it is indicated that the analysis of divalent manganese be performed on project sample MW-1D-97 only. Upon sub-contracting the divalent manganese analysis to Microseeps Laboratory, Accutest indicated the analysis of divalent manganese be performed for both projects samples, MW-1D-97 and MW-1S. Results of divalent manganese were reported for both project samples.
- On the COC associated with Accutest Data Set N69286, the sampling time for project sample MW-00-11A was omitted. No qualifier is required since this has minimal impact on the sample analysis hold time.
- On the laboratory's sample login summary sheet (page 29) of the reports associated with Accutest Data Sets N69286, N69286A and N69286X, it is documented that the labels on the sample bottles do not agree with the COC. The laboratory contacted URS regarding the discrepancies and the corrections were forwarded to Accutest. No qualifier is required.
- It should be noted that on the laboratory's sample log-in summary sheet (page 32) of the reports associated with Accutest Data Sets N69150, N69150A and N69150X, it is documented that the sample custody seals were absent upon receipt of the sample coolers. There is no impact on the data quality and no further action is required from the laboratory.
- A transcription error was identified during review of the volatile analyses for project samples associated with Accutest Data Sets N69045A, N69150A, N69286 and N69400. The GC column reported (EB-624) in each of the aforementioned reports is incorrect. Based on review of the results summary sheets (Form 1), the correct column label should be ZB-624. The column name has been corrected and initialed by this reviewer on the associated case narrative pages. No qualifier is required.
- In the nitrate analysis of Accutest Data Set N69045, project sample MW-1S appears to be omitted from the raw data (chromatogram). The laboratory was contacted and the required data was forwarded to URS. No further action is required from the laboratory.
- In the ferrous iron analysis of project samples MW-97-1S, MW-98-9D, MW-9D-98D, MW-97-2S and MW-98-10D associated with Accutest Data Set N69150, a transcription error was made for the dilution factor on the results summary forms. The dilution factor reported on the results summary forms was 50. Based on review of the laboratory worksheets, the correct dilution factor is 5. The laboratory was

contacted and the corrected results summary pages were submitted to URS. No further action is required from the laboratory.

- In the ferrous iron analysis associated with Accutest Data Set N69400, the initial and continuing calibration standard (ICV/CCV) results form (pp. 560) was incomplete. The laboratory was contacted and the required data was forwarded to URS. No further action is required from the laboratory.

3.2 ORGANIC QUALIFIERS

Hold Times: Technical hold times were assessed by comparing the sample dates with that of the preparation dates and/or analysis dates.

- The groundwater samples were analyzed within the required hold time for TCL VOA and Dissolved Gases (methane, ethane & ethene) analyses. No qualifier is required.
- The sample cooler temperatures upon verified time of sample receipt (VTSR) in the laboratory fell within the 4°C (+2°C) requirement. No qualifier is required.

Blank Contamination: Laboratory method blanks are clean liquid and/or solid matrix samples prepared by the analytical laboratory and analyzed in the same manner as the investigative samples. Water laboratory method blanks are used to identify whether investigative samples have been contaminated during sample preparation, sample analysis or from a previous sample (instrument carry-over).

Field-blanks consist of deionized water poured over or through decontaminated sampling equipment and collected into the sample bottles. Field-blanks measure contamination potentially caused by improper decontamination of sampling equipment. Trip-blanks are carbon-free deionized water samples that accompany volatile investigative samples during all stages of shipment, storage and analysis. The trip-blanks are used to assess the potential for artificial introduction of volatile compounds into the investigative samples during transportation and sample handling processes.

- No TCL VOA and/or Dissolved Gases contaminants were detected in the laboratory method blanks, as well as the storage and field-blanks associated with the reviewed project field samples. No qualifier is required.

GC/MS Performance Check (Tuning) Summary: Gas chromatograph/mass spectrometer (GC/MS) instrument tuning and performance checks are performed to ensure the instrument's ability to provide appropriate mass-resolution, identification and sensitivity.

- The bromofluorobenzene (BFB) tuning compound mass-ion abundance criteria for the volatile organic compound analyses were reported within control limits. No qualifier is required.

System Monitoring Compound (Surrogate) Recoveries: System monitoring compounds (surrogates) are those compounds, which are not expected to be detected in the investigative samples but which are chemically similar to analytes of interest. Surrogate compound percent recoveries are used to assess extraction efficiencies, possible matrix effects and overall analytical accuracy.

- The volatile surrogate recoveries fell within control limits for the reviewed project samples with the exception of project sample MW-97-4S associated with Accutest Data Set N69400. The initial analysis of sample MW-97-4S, the surrogate recoveries fell within control limits. The sample was reanalyzed at a 1:2 dilution due to chloroethane concentration exceeding the linear calibration range. However, the recovery of volatile surrogate, BFB, fell outside control limits (low). The laboratory performed a reanalysis of the 1:2 dilution and the surrogate recovery of BFB and Toluene-d8 fell outside control limits (low). The positive chloroethane result reported from the 1:2 dilution analysis of sample MW-97-4S is regarded as an estimated value and is flagged (J) on the laboratory summary pages and on the summary table. There is no impact on the data quality for the other TCL VOA results from the undiluted analysis and no qualifier is required.
- There are no surrogates associated with the analysis of dissolved gases (methane, ethane and ethane) by SW846 Method 8015. Therefore, no comments are offered regarding possible matrix effects and overall analytical accuracy. No qualifier is required.

Internal Standards Area Performance: Internal standards are analytes of interest, which are added to the investigative samples prior to analysis to ensure that GC/MS sensitivity and responses remain stable. Internal standards are reported with the volatile analysis.

- The TCL VOA internal standard area counts and retention times fell within control limits for the reviewed project samples associated with Accutest Data Sets N69045A, N69150A, N69286 and N69400. No qualifier is required.

Initial and Continuing Calibration Results: Control limits for initial and continuing instrument calibrations are established to ensure that the instrument is capable of producing accurate quantitative data at the beginning and throughout each of the analyses.

- The TCL VOA target compound initial and continuing calibration response factors, percent relative standard deviations (%RSD) and percent differences (%D) associated with the reviewed project samples fell within acceptable control limits. No qualifier is required.
- The Dissolved Gases target compound initial and continuing calibration response factors, %RSD and %D associated with the reviewed project samples fell within acceptable control limits. No qualifier is required.

Matrix Spike (MS) and Matrix Spike Duplicate (MSD) Summaries: Matrix spikes are samples spiked with known concentrations of analytes of interest. The MS/MSD percent recoveries and duplicate results are used to assess extraction efficiencies, possible matrix effects, and overall analytical accuracy and precision.

Blank spikes (BS) are blank samples fortified (spiked) with known concentrations of analytes of interest. The percent recoveries and/or duplicate results of the blank spike and their duplicates (BSD) are used to assess extraction efficiencies, and overall analytical accuracy and precision.

- The TCL VOA MS/MSD/BS results (recoveries and relative percent difference or RPD) associated with Accutest Data Sets N69045A, N69150A, N69286 and N69400 fell within acceptable control limits providing a positive indication of the overall accuracy and precision associated with these analyses. No qualifier required.
- The Dissolved Gases BS and duplicate (DU) results (recoveries and RPD) associated with Accutest Data Sets N69045, N69150, N69286A and N69400A fell within acceptable control limits providing a positive indication of the overall accuracy and precision associated with these analyses. No qualifier required.

Target Compound Identification and Quantitation: The laboratory calculations are verified and compound identifications are reviewed and assessed by the data reviewer.

- The following samples were analyzed at elevated dilutions resulting in elevated detection limits, due to target concentrations exceeding the linear calibration range requirements. No qualifier is required.

Data Set	Parameter	Compound	Associated Sample (Dilution Factor)
N69045A	TCL VOA	chloroethane/ methylene chloride	MW-1S (1:100)
N69045	Dis. Gases	methane/ethane	MW-1S (1:10)
N69150A	TCL VOA	chloroethane	MW-97-1S (1:5) MW-98-9D (1:5) MW-9D-98D (1:5)
N69150	Dis. Gases	methane	MW-97-1S (1:5) MW-98-9D (1:5) MW-9D-98D (1:5) MW-97-2S (1:5) MW-98-10D (1:5)
N69286	TCL VOA	chloroethane	MW-97-6S (1:5)
N69286A	Dis. Gases	methane	MW-97-6S (1:5) MW-97-3S (1:5) MW-98-8D (1:2.5) MW-98-8S (1:2.5)
N69400	TCL VOA	chloroethane	MW-97-4S (1:2)
N69400A	Dis. Gases	methane	MW-03-3S (1:5) MW-97-5S (1:5)

- Samples MW-1S (Accutest Data Set N69045A); MW-97-1S, MW-98-9D and MW-9D-98D (Accutest Data Set N69150A); MW-97-6S (Accutest Data Set N69286) and MW-97-4S (Accutest Data Set N69400) were re-analyzed at the dilutions specified above due to target compound, chloroethane, concentrations exceeding the linear

calibration range requirements. Both TCL VOA initial and dilution analysis results are reported on the laboratory summary pages. No qualifier is required.

- Samples MW-1S (Accutest Data Set N69045); MW-97-1S, MW-98-9D, MW-9D-98D, MW-97-2S and MW-98-10D (Accutest Data Set N69150); MW-97-6S, MW-97-3S, MW-98-8D and MW-98-8S (Accutest Data Set N69286A) MW-03-3S and MW-97-5S (Accutest Data Set N69400A) were re-analyzed at the dilutions specified above due to target compound, methane, concentrations exceeding the linear calibration range requirements. The Dissolved Gases results reported on the laboratory summary pages are hybrid of both the initial and dilution analyses. No qualifier is required.
- The GC and GC/MS raw data (quantitation reports, chromatograms and GC/MS mass-spectra) were provided for review. No laboratory calculation errors were noted for samples selected for verification during the quality assurance review. No further action is required from the laboratory.

Tentatively Identified Compounds: In addition to the specific target compounds identified, 10 non-target volatile organic compounds of greatest apparent concentration were tentatively identified by a computerized search of the National Bureau of Standards (NBS) mass-spectral library. A mass-spectral interpretation specialist compares the sample mass-spectrum to the library search and assigns a tentative identification. The validity of the tentatively identified compounds (TICs) was evaluated based upon the identifications made by the laboratory, and the following comments are offered:

- The majority of the VOA TICs identified in samples associated with Accutest Data Sets N69045A, N69150A, N69286 and N69400 are alkanes, cycloalkanes, diethyl sulfide and unknowns.
- The compound, 2-methoxy-2-methylpropane (m/e 73), was tentatively identified in the volatile library search of sample MW-03-3S (pp. 50) associated with Accutest Data Set N69400. Since this compound is not found in the associated blanks and is a suspected artifact, the TIC result of 2-methoxy-2-methylpropane is regarded as unusable and is flagged (R) on the laboratory summary pages and on the summary tables.

Additional Comments

- As per the requirements, all values calculated below the Reporting Limit (RL) should be considered estimated and are flagged (J) on the summary table.

3.3 INORGANIC AND CONVENTIONAL PARAMETER QUALIFIERS

Hold Times: Technical hold times are assessed by comparing the sampling dates with that of the preparation dates and/or analysis dates.

- The reviewed project samples were prepared and/or analyzed within the required hold time for (total) iron, (total) manganese and conventional parameter analyses. No qualifier is required.

Blank Contamination: Laboratory method blanks are clean liquid and/or solid matrix samples prepared by the analytical laboratory and analyzed in the same manner as the investigative samples. Water laboratory method blanks are used to ensure that the investigative samples are not contaminated during the sample preparation, sample analysis or from previous sample (instrument carry-over).

Field-blanks consist of deionized water poured over or through decontaminated sampling equipment and collected into the sample bottles. Field-blanks measure contamination potentially caused by improper decontamination of sampling equipment

- No (total) iron, (total) manganese, and/or conventional parameter contaminants were detected in the laboratory method and/or instrument blanks, and in the field-blank sample associated with the reviewed project samples. No qualifier is required.

Instrument Calibration and Verifications: Control limits for initial and continuing calibration verifications (ICV and (CCV) are established to ensure that the instrument is capable of producing accurate quantitative data at the beginning and throughout each of the analyses.

- The initial and continuing calibration verification (ICV/CCV) standard recoveries for (total) iron and (total) manganese fell within control limits. No qualifier is required.
- The initial and continuing calibration verification (ICV/CCV) standard recoveries for the conventional parameters fell within control limits. No qualifier is required.

Inductively Coupled Plasma (ICP) Interference Check Sample (ICS) Results: The interference check sample (ICS) verifies the laboratory's ICP inter-element and background correction factors.

- The interference check sample (ICS) analysis fell within control limits for (total) iron and (total) manganese associated with Accutest Data Sets N69045, N69150, N69286A and N69400A. No qualifier is required.

Laboratory Control Sample (LCS) Results: The laboratory control sample (LCS) is a blank sample fortified (spiked) with known concentrations of analytes of interest. The percent recoveries are used to assess extraction efficiencies and overall analytical accuracy.

- The laboratory control sample (LCS) recoveries fell within control limits for (total) iron, (total) manganese and/or conventional parameter analyses. No qualifier is required.

Matrix Spike (MS) and Duplicate (DU) Summaries: Matrix spikes are samples spiked with known concentrations of analytes of interest. The spiked sample analysis is designed to provide information about the effect of the sample matrix on the sample preparation procedures and the measurement of the methodology. Duplicate samples are used to demonstrate acceptable method precision from the laboratory at the time of analysis. The percent recoveries and duplicate results are used to assess digestion efficiencies, possible matrix effects, and overall analytical accuracy and precision.

- The MS/MSD and/or DU (recoveries and RPD) fell within control limits for (total) iron and (total) manganese with the exception of (total) iron associated with Accutest Data Sets N69150, N69286A and N69400A. The recovery of (total) iron in the aforementioned Data Sets fell outside control limits. No qualifier is required since the concentration found in the unspiked sample is greater than 4 times the spike concentration added.
- The MS/MSD and/or DU (recoveries and RPD) fell within control limits for conventional parameter analyses with the exception of nitrate (Accutest Data Sets N69045, N69150 and N69400A) and chloride/sulfate (Accutest Data Set N69400A) analysis. The RPD of nitrate and chloride/sulfate analyses associated with the aforementioned Data Sets fell outside control limits due to low sample and duplicate concentrations (<RL). No qualifier is required.

ICP Serial Dilution Results: The ICP Serial dilution of samples demonstrated whether or not significant physical or chemical interference exist due to sample matrix.

- The ICP serial dilution analyses of (total) iron and (total) manganese fell within control limits. No qualifier is required.

Target Analyte Identification and Quantitation: The laboratory calculations are verified and compound identifications are assessed by the data reviewer.

- The metals [(total) iron & (total) manganese] and conventional parameter raw data and/or laboratory worksheets were provided for review (as required under the NYSDEC ASP B Data Deliverable format). No laboratory calculation errors were noted for samples selected for verification during the quality assurance review. No further action is required from the laboratory.

4.0 CONCLUSIONS

Overall, the data quality is acceptable. The Quality Assurance Review has identified aspects of the analytical data that require qualification. Data qualifiers, when applicable, are placed next to the results so that the data user can assess the qualitative and/or quantitative reliability of the reported results. The laboratory analytical data contained herein are deemed usable and in compliance with the New York ASP B Deliverable Format requirements. To confidently use any of the data within the data set, the data user should understand the limitations and qualifications presented.

QUALITY ASSURANCE REVIEW
PROJECT: COLUMBIA CEMENT, FREEPORT, LONG ISLAND, NY
DATE SAMPLES COLLECTED: JUNE 7, 8, 9 &10, 2004
JOB NO.: 38546433

**LAB REPORT No: N69045, N69045A, N69045X, N69150, N69150A, N69150X,
N69286, N69286A, N69286X, N69400, N69400A & N69400AX**

1.0 INTRODUCTION

This Quality Assurance Review has been performed in accordance with: (1) the requirements specified in the New Jersey Department of Environmental Protection (NJDEP) Technical Requirements for Site Remediation N.J.A.C., 7:26E, dated June 7, 1993, and amended July 2, 1999; and (2) NJDEP's Standard Operating Procedures (SOP) for the Quality Assurance Data Validation of Analytical Deliverables, TCL Organics, SOP No. 5.A.13 (October 2001 revision) based on USEPA CLP SOW OLM04.2 (with revisions) and USEPA 600 Series methodologies. The quality assurance requirements are applied such that specifications and/or modifications of the methods take precedence over the specifications of NJDEP Technical Requirement guidelines in those instances where the specifications differ.

The objective of the review was to assess data usability and compliance with New York Department of Environmental Conservation (NYSDEC) ASP Category B deliverable requirements. The Quality Assurance Review provides an interpretation of data usability based on the reported quality control parameters. Groundwater samples and field-blank samples were collected by URS Corporation – Cranford, New Jersey, and submitted to Accutest Laboratories of Dayton, New Jersey (NY Certification No. 10983). The Divalent Manganese samples submitted to Accutest were sub-contracted to Microseeps of (Certification No.). Seventeen groundwater samples and one field-blank sample were selected for quality assurance review to assess the overall data quality. Section 2.0 of this report summarizes the samples included in this review and the analyses performed. The groundwater samples were analyzed following SW-846 Methodologies. The laboratory analytical data set contained herein was prepared in accordance with NYSDEC ASP Category B Data Deliverable Format (Exhibit B).

The organic data quality review is based on the following parameters:

- * Hold Times
- * Blank Contamination
- * GC/MS Performance Check (Tuning) Summaries
- * System Monitoring Compound (Surrogate) Recoveries
- * Internal Standard Area Performance
- * Initial and Continuing Calibration Results
- * Matrix Spike (MS) and Matrix Spike Duplicate (MSD) Summaries
- * Target Compound Identification and Quantitation
- * Tentatively Identified Compounds

The inorganic and conventional parameter data quality review is based on the following parameters:

- * Hold Times
- * Blank Contamination
- * Instrument Calibration and Verifications
- * Inductively Coupled Plasma (ICP) Interference Check Sample (ICS) Analysis Results
- * Laboratory Control Sample (LCS) Results
- * Matrix Spike (MS) and Duplicate (DU) Summaries
- * ICP Serial Dilution Results
- * Target Analyte Identification and Quantitation

- * All criteria were met for this parameter

This report was prepared to provide a critical review of the laboratory analysis and reported chemical results. Overall, the data quality is acceptable. The results of the Quality Assurance Review are presented in Section 3.0. Data qualifiers, when applicable, are placed next to the results so that the data user can assess the qualitative and/or quantitative reliability of the reported result.

2.0 SAMPLES INCLUDED IN REVIEW

<u>Sample ID</u>	<u>Lab ID</u>	<u>Date Collected</u>	<u>Test Requested</u>
Lab Report No. N69045			
MW-1S	N69045-1	6/07/04	TCL VOA+10
MW-1D-97	N69045-2	6/07/04	TCL VOA+10
Lab Report No. N69045A			
MW-1S	N69045-1A	6/07/04	TOC, dissolved gases & conventional parameters
MW-1D-97	N69045-2A	6/07/04	TOC, dissolved gases & conventional parameters
Lab Report No. N69045X			
MW-1D-97	N69045-2X	6/07/04	divalent manganese
Lab Report No. N69150			
MW-97-1S	N69150-1	6/08/04	TCL VOA+10
MW-98-9D	N69150-2	6/08/04	TCL VOA+10
MW-9D-98D	N69150-3	6/08/04	TCL VOA+10
MW-97-2S	N69150-4	6/08/04	TCL VOA+10

MW-98-10D	N69150-5	6/08/04	TCL VOA+10
-----------	----------	---------	------------

Lab Report No. N69150A

MW-97-1S	N69150-1A	6/08/04	TOC, dissolved gases & conventional parameters
MW-98-9D	N69150-2A	6/08/04	TOC, dissolved gases & conventional parameters
MW-9D-98D	N69150-3A	6/08/04	TOC, dissolved gases & conventional parameters
MW-97-2S	N69150-4A	6/08/04	TOC, dissolved gases & conventional parameters
MW-98-10D	N69150-5A	6/08/04	TOC, dissolved gases & conventional parameters

Lab Report No. N69150X

MW-97-1S	N69150-1X	6/08/04	divalent manganese
MW-98-9D	N69150-2X	6/08/04	divalent manganese
MW-9D-98D	N69150-3X	6/08/04	divalent manganese
MW-97-2S	N69150-4X	6/08/04	divalent manganese

Lab Report No. N69286

FB060904	N69286-1	6/09/04	TCL VOA+10
MW-97-6S	N69286-2	6/09/04	TCL VOA+10
MW-97-7S	N69286-3	6/09/04	TCL VOA+10
MW-97-3S	N69286-4	6/09/04	TCL VOA+10
MW-97-8D	N69286-5	6/09/04	TCL VOA+10
MW-97-8S	N69286-6	6/09/04	TCL VOA+10
MW-00-11A	N69286-7	6/09/04	TCL VOA+10

Lab Report No. N69286A

FB060904	N69286-1A	6/09/04	TOC, dissolved gases & conventional parameters
MW-97-6S	N69286-2A	6/09/04	TOC, dissolved gases & conventional parameters
MW-97-7S	N69286-3A	6/09/04	TOC, dissolved gases & conventional parameters
MW-97-3S	N69286-4A	6/09/04	TOC, dissolved gases & conventional parameters
MW-98-8D	N69286-5A	6/09/04	TOC, dissolved gases & conventional parameters
MW-98-8S	N69286-6A	6/09/04	TOC, dissolved gases & conventional parameters
MW-00-11A	N69286-7A	6/09/04	TOC, dissolved gases & conventional parameters

Lab Report No. N69286AX

MW-97-6S	N69286-2X	6/09/04	divalent manganese
MW-97-3S	N69286-4X	6/09/04	divalent manganese
MW-98-8D	N69286-5X	6/09/04	divalent manganese
MW-98-8S	N69286-6X	6/09/04	divalent manganese

Lab Report No. N69400

MW-03-3S	N69400-1	6/10/04	TCL VOA+10
MW-00-12D	N69400-2	6/10/04	TCL VOA+10
MW-97-4S	N69400-3	6/10/04	TCL VOA+10
MW-97-5S	N69400-4	6/10/04	TCL VOA+10

Lab Report No. N69400A

MW-03-3S	N69400-1A	6/10/04	TOC, methane, ethane, ethene, chloride, sulfate, nitrate, iron, alkalinity, total manganese
MW-00-12D	N69400-2A	6/10/04	TOC, methane, ethane, ethene, chloride, sulfate, nitrate, iron, alkalinity, total manganese
MW-97-4S	N69400-3A	6/10/04	TOC, methane, ethane, ethene, chloride, sulfate, nitrate, iron, alkalinity, total manganese
MW-97-5S	N69400-4A	6/10/04	TOC, methane, ethane, ethene, chloride, sulfate, nitrate, iron, alkalinity, total manganese

Lab Report No. N69400AX

MW-03-3S	N69400-1X	6/10/04	divalent manganese
MW-97-5S	N69400-4X	6/10/04	divalent manganese

Legend:

TCL VOA +10 = Target Compound List Volatile Organic Compounds plus Forward Library Searches following USEPA SW-846 Method 8260B.

Dissolved Gas = Methane, ethane & ethene following USEPA SW846 Method 8015.

Iron = USEPA Method 200.7 and SW-846 Method 6010B.

Manganese = USEPA Method 200.7 and SW-846 Method 6010B.

Conventional Parameters = Alkalinity, nitrate, chloride, sulfate, ferrous iron, divalent manganese and TOC following USEPA 600 Series Methodologies (Nitrate by USEPA

3.0 RESULTS

3.1 GENERAL COMMENTS

With regard to the data package deliverables, most of the NYDEC ASP Category B Data Deliverable format requirements were met, with the exception of the following correctable deficiencies. Please note that these deficiencies, for the most part, do not impact data usability. The laboratory was contacted and this report may be amended upon the receipt of the lab corrections.

3.2 ORGANIC QUALIFIERS

Hold Times: Technical hold times were assessed by comparing the sample dates with that of the preparation dates and/or analysis dates.

- The groundwater samples were analyzed within the required hold time for TCL VOA analysis. No qualifier is required.
- The sample cooler temperature upon verified time of sample receipt (VTSR) in the laboratory fell within the 4°C (+2°C) requirement. No qualifier is required.

Blank Contamination: Laboratory method blanks are clean liquid and/or solid matrix samples prepared by the analytical laboratory and analyzed in the same manner as the investigative samples. Water laboratory method blanks are used to identify whether investigative samples have been contaminated during sample preparation, sample analysis or from a previous sample (instrument carry-over).

Field-blanks consist of deionized water poured over or through decontaminated sampling equipment and collected into the sample bottles. Field-blanks measure contamination potentially caused by improper decontamination of sampling equipment. Trip-blanks are carbon-free deionized water samples that accompany volatile investigative samples during all stages of shipment, storage and analysis. The trip-blanks are used to assess the potential for artificial introduction of volatile compounds into the investigative samples during transportation and sample handling processes.

- No VOA contaminants were detected in the laboratory method blanks, as well as the field and trip-blanks associated with the reviewed project field samples. No qualifier is required.

GC/MS Performance Check (Tuning) Summary: Gas chromatograph/mass spectrometer (GC/MS) instrument tuning and performance checks are performed to ensure the instrument's ability to provide appropriate mass-resolution, identification and sensitivity.

- The bromofluorobenzene (BFB) tuning compound mass-ion abundance criteria for the volatile organic compound analyses were reported within control limits. No qualifier is required.

System Monitoring Compound (Surrogate) Recoveries: System monitoring compounds (surrogates) are those compounds which are not expected to be detected in the investigative samples but which are chemically similar to analytes of interest. Surrogate compound percent recoveries are used to assess extraction efficiencies, possible matrix effects and overall analytical accuracy.

- The volatile surrogate recoveries fell within control limits for the reviewed project samples. No qualifier is required.

Internal Standards Area Performance: Internal standards are analytes of interest, which are added to the investigative samples prior to analysis to ensure that GC/MS sensitivity and responses remain stable. Internal standards are reported with the volatile analysis.

- The VOA internal standard area counts and retention times fell within control limits for the reviewed project samples. No qualifier is required.

Initial and Continuing Calibration Results: Control limits for initial and continuing instrument calibrations are established to ensure that the instrument is capable of producing accurate quantitative data at the beginning and throughout each of the analyses.

- The VOA target compound initial calibration response factors and percent relative standard deviations (%RSD) fell within acceptable control limits. No qualifier is required.
- The VOA target compound continuing calibration response factors and percent differences (%RSD) fell within acceptable control limits with the exception of . No qualifier is required.

Matrix Spike (MS) and Matrix Spike Duplicate (MSD) Summaries: Matrix spikes are samples spiked with known concentrations of analytes of interest. The MS/MSD percent recoveries and duplicate results are used to assess extraction efficiencies, possible matrix effects, and overall analytical accuracy and precision.

Blank spikes are blank samples fortified (spiked) with known concentrations of analytes of interest. The percent recoveries and/or duplicate results of the blank spike and their duplicates (BSD) are used to assess extraction efficiencies, and overall analytical accuracy and precision.

- In the VOA analysis, the MS/MSD analyses were performed; however, the laboratory reports only the MS recovery results, which fell within control limits

(MSD not required under USEPA Method 624), providing a positive indication of the overall accuracy associated with these analyses. Since the MSD results were not provided, no comments can be offered regarding the precision associated with the VOA analyses. It should be noted that the blank spike recoveries were reported and the benzene, toluene and ethylbenzene compound recoveries fell within control limits.

Target Compound Identification and Quantitation: The laboratory calculations are verified and compound identifications are reviewed and assessed by the data reviewer.

- Samples MW-2A (1:50), MW-7 (1:5), MW-10 (1:50), MW-12 (1:10), MW-13 (1:50), and MW-14 (1:5) (Data Set I352) were analyzed at elevated dilutions for BTEX/MTBE/TBA, resulting in elevated detection limits, due to these target compounds exceeding the linear calibration range requirement. No qualifier is required.
- The GC/MS raw data (quantitation reports, chromatograms and mass-spectra) were provided for review. No laboratory calculation errors were noted for samples selected for verification during the quality assurance review. No further action is required from the laboratory.

Additional Comments

- As per the requirements, all values calculated below the method detection limit should be considered estimated and are flagged (J) on the summary table.

3.3 INORGANIC AND CONVENTIONAL PARAMETER QUALIFIERS

Hold Times: Technical hold times are assessed by comparing the sampling dates with that of the preparation dates and/or analysis dates.

- All samples were prepared and/or analyzed within the required hold time for lead, carbon dioxide (CO₂) and alkalinity analyses. No qualifier is required.

Blank Contamination: Laboratory method blanks are clean liquid and/or solid matrix samples prepared by the analytical laboratory and analyzed in the same manner as the investigative samples. Water laboratory method blanks are used to ensure that the investigative samples are not contaminated during the sample preparation, sample analysis or from previous sample (instrument carry-over).

Field-blanks consist of deionized water poured over or through decontaminated sampling equipment and collected into the sample bottles. Field-blanks measure contamination potentially caused by improper decontamination of sampling equipment

- No magnesium, alkalinity and/or CO₂ contaminants were detected in the laboratory method and instrument blanks, and in the field-blank samples associated with the reviewed project samples. No qualifier is required.

Instrument Calibration and Verifications: Control limits for initial and continuing calibration verifications (ICV and CCV) are established to ensure that the instrument is capable of producing accurate quantitative data at the beginning and throughout each of the analyses.

- The initial and continuing calibration verification (ICV/CCV) standard recoveries for lead fell within control limits. No qualifier is required.

Inductively Coupled Plasma (ICP) Interference Check Sample (ICS) Results: The interference check sample (ICS) verifies the laboratory's ICP inter-element and background correction factors.

- The interference check sample (ICS) analysis fell within control limits. No qualifier is required.

Laboratory Control Sample (LCS) Results: The laboratory control sample (LCS) is a blank sample fortified (spiked) with known concentrations of analytes of interest. The percent recoveries are used to assess extraction efficiencies and overall analytical accuracy.

- The laboratory control sample (LCS) analysis fell within control limits. No qualifier is required.

Matrix Spike (MS) and Duplicate (DU) Summaries: Matrix spikes are samples spiked with known concentrations of analytes of interest. The spiked sample analysis is designed to provide information about the effect of the sample matrix on the sample preparation procedures and the measurement of the methodology. Duplicate samples are used to demonstrate acceptable method precision from the laboratory at the time of analysis. The percent recoveries and duplicate results are used to assess digestion efficiencies, possible matrix effects, and overall analytical accuracy and precision.

- The matrix spike recoveries and duplicate relative percent differences (RPD) fell within control limits for lead, alkalinity and CO₂, providing a positive indication of the precision and accuracy associated with these analyses. No qualifier is required.

ICP Serial Dilution Results: The ICP Serial dilution of samples demonstrated whether or not significant physical or chemical interference exist due to sample matrix.

- The ICP serial dilution analyses of lead fell within control limits. No qualifier is required.

Target Analyte Identification and Quantitation: The laboratory calculations are verified and compound identifications are assessed by the data reviewer.

- The metals (lead) raw data, alkalinity and CO₂ laboratory worksheets were not provided for review (not required under the NJDEP Reduced Data Deliverable format). The quantitative validity of the reported concentrations cannot be calculated and verified. It is assumed that the results are correct as reported and no further action is required from the laboratory.

4.0 CONCLUSIONS

Overall, the data quality is acceptable and no qualifiers are required. Based on the Quality Assurance Review, the New Jersey Data Deliverable Format requirements were met and no further action is required by the laboratory. To confidently use any of the data within the data set, the data user should understand the limitations and qualifications presented.

DATA VALIDATION REVIEW
PROJECT: COLUMBIA CEMENT, FREEPORT, LONG ISLAND, NY
DATE SAMPLES COLLECTED: JUNE 6 THROUGH 9, 2006
JOB NO.: 38546433

LAB REPORT NOs. T011, T020, T124, and T126

1.0 INTRODUCTION

This Data Validation Review has been performed in accordance with the requirements specified in the standard operating procedures for the validation of volatile organic data using USEPA Region II Contract Laboratory Program (CLP) Organics Data Review and Preliminary Data Review, SOP HW-6, Revision 12, dated March 2001; evaluation of Metals data for USEPA Region II Contract Laboratory Program (CLP), SOP HW-2, Rev. 13; dated September 2005 and SW-846, 600 Series and Standard Methods for the Evaluation of Water and Wastewater, 18th Edition (Standard Methods) methodologies. The quality assurance review requirements are applied such that specifications of the methods take precedence over the specifications of the USEPA Region II data review guidelines in those instances where the specifications differ.

The objective of the review was to assess data usability and compliance with New York State Department of Environmental Conservation (NYSDEC) ASP Category B deliverable requirements. The Data Validation Review provides an interpretation of data usability based on the reported quality control parameters. A total of eighteen groundwater samples, one blind field duplicate groundwater sample, one field-blank sample, and three trip-blank samples were collected by URS Corporation, Cranford, New Jersey, office personnel and submitted to Severn Trent Laboratories (STL-Edison) of Edison, New Jersey (NYSDEC Certification No. 11452). Six groundwater samples, one blind field duplicate groundwater sample, and one trip-blank sample from Data Set T020 were selected for data validation review to assess the overall data quality. Section 2.0 of this report summarizes the samples included in this review and the analyses performed. The groundwater samples were analyzed following USEPA SW846, 600 Series, and Standard Methodologies. The laboratory analytical data set contained herein was prepared in accordance with NYSDEC ASP Category B Data Deliverable Format (Exhibit B).

The organic data quality review is based on the following parameters:

- * Hold Times
- * Blank Contamination
- * GC/MS Performance Check (Tuning) Summaries
- * System Monitoring Compound (Surrogate) Recoveries
- * Internal Standard Area Performance
- * Initial and Continuing Calibration Results
- * Matrix Spike (MS) and Matrix Spike Duplicate (MSD) Summaries
- * Target Compound Identification and Quantitation
- * Tentatively Identified Compounds

The inorganic and conventional parameter data quality review is based on the following parameters:

- * Hold Times
- Blank Contamination
- * Instrument Calibration and Verifications
- * Inductively Coupled Plasma (ICP) Interference Check Sample (ICS) Results
- * Laboratory Control Sample (LCS) Results
- * Matrix Spike (MS) and Duplicate (DU) Summaries
- * ICP Serial Dilution Results
- * Target Analyte Identification and Quantitation

*All criteria were met for this parameter

This report was prepared to provide a critical review of the laboratory analysis and reported chemical results. Overall, the data quality is acceptable. The results of the Data Validation Review are presented in Section 3.0. Data qualifiers, when applicable, are placed next to the results so that the data user can assess the qualitative and/or quantitative reliability of the reported result.

2.0 SAMPLES INCLUDED IN REVIEW

Lab Report No. T020

<u>Sample ID</u>	<u>Lab ID</u>	<u>Date Collected</u>	<u>Test Requested</u>
MW-1S	743167	6/7/06	TCL VOA+10, Methane/Ethane/Ethene, (total) Iron, Alkalinity, Sulfate, Chloride and TOC
MW-1D-97	743168	6/7/06	TCL VOA+10, Methane/Ethane/Ethene, (total) Iron, Alkalinity, Sulfate, Chloride and TOC
MW-00-11A	743169	6/7/06	TCL VOA+10, Methane/Ethane/Ethene, (total) Iron, Alkalinity, Sulfate, Chloride and TOC
MW-98-8S	743170	6/7/06	TCL VOA+10, Methane/Ethane/Ethene, (total) Iron, Alkalinity, Sulfate, Chloride and TOC
MW-98-8D	743171	6/7/06	TCL VOA+10, Methane/Ethane/Ethene, (total) Iron, Alkalinity, Sulfate, Chloride and TOC
MW-97-1S	743172	6/7/06	TCL VOA+10, Methane/Ethane/Ethene, (total) Iron, Alkalinity, Sulfate, Chloride and TOC
TB-060706	743173	6/7/06	TCL VOA+10
DUP060706	743174	6/7/06	TCL VOA+10, Methane/Ethane/Ethene, (total) Iron, Alkalinity, Sulfate, Chloride and TOC
MW-1S	743175	6/7/06	(dissolved) Iron
MW-1D-97	743176	6/7/06	(dissolved) Iron
MW-00-11A	743177	6/7/06	(dissolved) Iron
MW-98-8S	743178	6/7/06	(dissolved) Iron

MW-98-8D	743179	6/7/06	(dissolved) Iron
MW-97-1S	743180	6/7/06	(dissolved) Iron
DUP060706	743181	6/7/06	(dissolved) Iron

Legend:

TCL VOA+10	=	Target Compound List Volatile Organic Compounds plus Forward Library Searches following USEPA Method 624.
Methane/Ethane/ Ethene	=	Analyzed following USEPA SW-846 Method 3810.
(total) Iron	=	Analyzed following USEPA Method 200.7.
(dissolved) Iron	=	Analyzed following USEPA Method 200.7.
Alkalinity	=	Analyzed following USEPA Methods 310.1.
Sulfate	=	Analyzed following USEPA Method 375.4.
Chloride	=	Analyzed following Standard Methods for the Examination of Water & Wastewater 18 th Edition Method 4500-Cl B.
TOC	=	Total Organic Carbon following USEPA Method 415.1.

3.0 RESULTS

3.1 GENERAL COMMENTS

With regard to the data package deliverables, most of the NYSDEC ASP Category B Data Deliverable format requirements were met, with the exception of the following correctable deficiencies. Please note that these deficiencies, for the most part, do not impact data usability. The laboratory was contacted and the missing information requested. As of this writing, STL-Edison has not provided the required information. This report may be amended upon the receipt of the laboratory corrections.

- The laboratory did not include the Internal chain-of-custody (COC) as required under NYSDEC ASP Category B Data Deliverable format requirements.
- The laboratory did not include the Instrument Detection Limits (IDLs) for TCL VOA, Methane/Ethane/Ethene, Metals, and conventional parameters.
- The laboratory included extra pages 5 through 10 in section-1 sample preparation and analysis summary that are not associated with the reviewed data set. This reviewer has disregarded these pages. No further action is required from the laboratory.
- On the sample identification and analytical requirement summary associated with Data Set T020, the laboratory incorrectly reported that trip-blank sample TB060706 was analyzed for Methane/Ethane/Ethene, Metals, and conventional parameters. Based on a review of the associated COC and supporting data, the trip-blank sample

was only requested and analyzed for TCL VOA. The laboratory was contacted and a revised sample identification and analytical requirement summary was requested.

- On the sample preparation and analysis summary associated with Data Set T020, the laboratory incorrectly reported that trip-blank sample TB060706 was analyzed for Methane/Ethane/Ethene and sulfate analyses. Based on a review of the associated COC and supporting data, the trip-blank sample was only requested and analyzed for TCL VOA. The laboratory was contacted and a revised sample preparation and analysis summary was requested.
- In the alkalinity analysis, the laboratory work sheet associated with the Laboratory Control Sample (LCS) was not included in the data package received for review. Similarly, in the chloride analysis, the laboratory work sheet associated with the Matrix Spike and Matrix Spike Duplicate (MS/MSD) was not included in the data package received for review.
- In the chloride and sulfate analyses, the correlation coefficient (r) was reported as 1.0 on the associated calibration raw data. Based on a calculation, these values are 0.990 (chloride) and 0.996 (sulfate). The laboratory was contacted and the corrected calibration raw data was requested.

3.2 ORGANIC QUALIFIERS

Hold Times: Technical hold times were assessed by comparing the sample dates with that of the preparation dates and/or analysis dates.

- The samples were analyzed within the required 14-day hold time for TCL VOA and Methane/Ethane/Ethene analyses. Additionally, the laboratory cooler receipt temperature associated with the reviewed project samples fell within the 4°C ($\pm 2^\circ \text{ C}$) requirement. No qualifier is required.

Blank Contamination: Laboratory method blanks are clean liquid and/or solid matrix samples prepared by the analytical laboratory and analyzed in the same manner as the investigative samples. Water laboratory method blanks are used to identify whether investigative samples have been contaminated during sample preparation, sample analysis or from a previous sample (instrument carry-over).

Trip-blanks are carbon-free deionized water samples that accompany volatile investigative samples during all stages of shipment, storage and analysis. The trip-blanks are used to assess the potential for artificial introduction of volatile compounds into the investigative samples during transportation and sample handling processes.

- No TCL VOA and Methane/Ethane/Ethene contaminants were identified in the laboratory method blank and/or in the trip-blank sample associated with the groundwater samples received and reviewed. No qualifier is required.

GC/MS Performance Check (Tuning) Summary: Gas chromatograph/mass spectrometer (GC/MS) instrument tuning and performance checks are performed to ensure the instrument's ability to provide appropriate mass-resolution, identification, and sensitivity.

- The bromofluorobenzene (BFB) tuning compound mass-ion abundance criteria for the volatile organic compound analyses were reported within control limits. No qualifier is required.

System Monitoring Compound (Surrogate) Recoveries: System monitoring compounds (surrogates) are those compounds, which are not expected to be detected in the investigative samples but which are chemically similar to the analytes of interest. Surrogate compound percent recoveries are used to assess extraction efficiencies, possible matrix effects, and overall analytical accuracy.

- The TCL VOA surrogate recoveries fell within control limits for the project samples received and reviewed. No qualifier is required.
- Volatile surrogate compounds are not associated with Methane/Ethane/Ethene analyses. Therefore, no comments are offered regarding possible matrix effects and overall analytical accuracy. No qualifier is required.

Internal Standards Area Performance: Internal standards are analytes of interest, which are added to the investigative samples prior to analysis to ensure that GC/MS sensitivity and responses remain stable. Internal standards are reported with the volatile analysis.

- The volatile internal standard area counts and retention times fell within control limits for the project samples received and reviewed for TCL VOA analyses. No qualifier is required.

Initial and Continuing Calibration Results: Control limits for initial and continuing instrument calibrations are established to ensure that the instrument is capable of producing accurate quantitative data at the beginning and throughout each of the analyses.

- The TCL VOA target compound initial and continuing calibration response factors, percent relative standard deviations (%RSD), and percent differences (%D) associated with the reviewed project samples fell within acceptable control limits. No qualifier is required.
- The Methane/Ethane/Ethene target compounds initial and continuing calibration response factors, %RSD, and %D associated with the reviewed project samples fell within acceptable control limits. No qualifier is required.

Matrix Spike (MS) and Matrix Spike Duplicate (MSD) Summaries: Matrix spikes are samples spiked with known concentrations of analytes of interest. The MS/MSD percent recoveries and duplicate results are used to assess extraction efficiencies, possible matrix effects, and overall analytical accuracy and precision.

Blank spikes (BS) are blank samples fortified (spiked) with known concentrations of analytes of interest. The blank spike percent recoveries results are used to assess extraction efficiencies, and overall analytical accuracy and precision.

Field duplicate samples are taken and analyzed as an indication of overall precision. These analyses measure both field and laboratory precision. Therefore, results may have more variability than laboratory duplicates, which measure only laboratory performance.

- In the TCL VOA analysis, the MS/MSD analyses were performed. However, the laboratory reports only the MS recovery results, which fell within control limits (MSD not required under USEPA Method 624), providing a positive indication of the overall accuracy associated with these analyses. Since the MSD results were not provided, no comments can be offered regarding the precision associated with the TCL VOA analyses. The blank spike recoveries were reported by the laboratory and the reported volatile compound recoveries fell within control limits. No qualifier is required.
- The Methane/Ethane/Ethene MS/MSD results (recoveries and relative percent differences or RPD) and BS recoveries associated with Data Set T020 fell within acceptable control limits providing a positive indication of the overall accuracy and precision associated with these analyses. No qualifier is required.
- Sample DUP060706 (Data Set T020) was collected and submitted as a blind field duplicate of sample MW-97-1S. The reproducibility of the TCL VOA and Methane/Ethane/Ethene results is good, providing a positive indication of the overall accuracy and precision associated with this analysis. No qualifier is required.

Target Compound Identification and Quantitation: The laboratory calculations are verified and compound identifications are reviewed and assessed by the data reviewer.

- Sample MW-1S was analyzed at a 1:20 dilution for TCL VOA resulting in elevated detection limits, due to the target compound chloroethane concentration exceeding the linear calibration range requirements. No qualifier is required.
- The following samples were analyzed at elevated dilutions for Methane/Ethane/Ethene resulting in elevated detection limits, due to the target compound methane concentrations exceeding the linear calibration range requirements. No qualifier is required.

Data Set	Associated Sample and Dilution
T020	MW-1S (1:20) MW-1D-97 (1:20) MW-98-8S (1:100) MW-98-8D (1:100) MW-97-1S (1:200) DUP060706 (1:200)

- The GC and GC/MS raw data (quantitation reports, chromatograms and GC/MS mass-spectra) were provided for review. Except where noted in Section 3.1, no other

laboratory calculation errors were noted for samples selected for verification during the Data Validation Review. No further action is required from the laboratory.

Tentatively Identified Compounds: In addition to the specific target compounds identified, 10 non-target volatile organic compounds of greatest apparent concentration were tentatively identified by a computerized search of the National Bureau of Standards (NBS) mass-spectral library. A mass-spectral interpretation specialist compares the sample mass-spectrum to the library search and assigns a tentative identification. The validity of the tentatively identified compounds (TICs) was evaluated based upon the identifications made by the laboratory, and the following comments are offered:

- The majority of the VOA TICs identified in samples MW-1S, MW-1D-97, MW-97-1S, and DUP060706 are an alkane, unknown aromatics, diethyl sulfide, indane, and unknowns.

Additional Comments

- As per the requirements, values calculated below the Reporting Limit (RL) should be considered estimated and are flagged (J) on the summary table.

3.3 INORGANIC AND CONVENTIONAL PARAMETER QUALIFIERS

Hold Times: Technical hold times are assessed by comparing the sampling dates with that of the preparation dates and/or analysis dates.

- The reviewed project samples were prepared and/or analyzed within the required hold time for (total and dissolved) iron and conventional parameters (alkalinity, chloride, sulfate, and TOC) analyses. No qualifier is required.

Blank Contamination: Laboratory method blanks are clean liquid and/or solid matrix samples prepared by the analytical laboratory and analyzed in the same manner as the investigative samples. Water laboratory method blanks are used to identify whether investigative samples have been contaminated during sample preparation, sample analysis, or from a previous sample (instrument carry-over).

- A trace iron concentration (above IDL but less than RL) was detected in the laboratory method (prep) blank associated with Data Set T020. The positive (dissolved) iron results (above IDL but less than RL) in samples MW-98-8S, MW-98-8D, MW-97-1S, and DUP060706 are flagged (U) reporting limit on the laboratory summary pages and on the summary table.
- No conventional parameter contaminants were detected in the laboratory method and/or instrument blanks associated with the reviewed project samples. No qualifier is required.

Instrument Calibration and Verifications: Control limits for initial and continuing calibration verifications (ICV and CCV) are established to ensure that the instrument is capable of producing accurate quantitative data at the beginning and throughout each of the analyses.

- The initial and continuing calibration verification (ICV/CCV) standard recoveries for (total and dissolved) iron fell within control limits. No qualifier is required.
- The initial and continuing calibration verification (ICV/CCV) standard recoveries for the conventional parameters fell within control limits. No qualifier is required.

Inductively Coupled Plasma (ICP) Interference Check Sample Results: The interference check sample (ICS) verifies the laboratory's ICP inter-element and background correction factors.

- The ICS analysis fell within control limits for (total and dissolved) iron associated with Data Set T020. No qualifier is required.

Laboratory Control Sample Results: The laboratory control sample (LCS) is a blank sample fortified (spiked) with known concentrations of analytes of interest. The percent recoveries are used to assess extraction efficiencies and overall analytical accuracy.

- LCS recoveries fell within control limits for (total and dissolved) iron and conventional parameter analyses. No qualifier is required.

Matrix Spike (MS) and Duplicate (DU) Summaries: Matrix spikes are samples spiked with known concentrations of analytes of interest. The spiked sample analysis is designed to provide information about the sample matrix effect on the sample preparation procedures and the measurement methodology. Duplicate samples are used to demonstrate acceptable method precision from the laboratory at the time of analysis. The percent recoveries and duplicate results are used to assess digestion efficiencies, possible matrix effects, and overall analytical accuracy and precision.

Field duplicate samples are taken and analyzed as an indication of overall precision. These analyses measure both field and laboratory precision. Therefore, results may have more variability than laboratory duplicates, which measure only laboratory performance.

- The (total and dissolved) iron MS recovery and DU RPD associated with Data Set T020 fell within control limits, providing a positive indication of the overall accuracy and precision associated with this analysis. No qualifier is required.
- The conventional parameters MS/MSD and/or DU (recoveries and RPD) fell within control limits providing a positive indication of the overall accuracy and precision associated with these analyses. No qualifier is required.
- Sample DUP060706 (Data Set T020) was collected and submitted as a blind field duplicate of sample MW-97-1S. The reproducibility of the (total and dissolved) iron and conventional parameters results is good, providing a positive indication of the overall accuracy and precision associated with this analysis. No qualifier is required.

ICP Serial Dilution Results: The ICP Serial dilution of samples demonstrates whether or not significant physical or chemical interference exist due to sample matrix.

- The ICP serial dilution analyses of (total and dissolved) iron fell within control limits. No qualifier is required.

Target Analyte Identification and Quantitation: The laboratory calculations are verified and compound identifications assessed by the data reviewer.

- The metals [(total and dissolved) iron] and conventional parameter raw data and/or laboratory worksheets were provided for review (as required under the NYSDEC ASP B Data Deliverable format). Except where noted in Section 3.1, no other laboratory calculation errors were noted for samples selected for verification during the Data Validation Review. No further action is required from the laboratory.

Additional Comments

- Metals were analyzed by ICP instrument; therefore, the Graphite Furnace Atomic Absorption (GFAA) QC data are not required for the project samples received and reviewed. No further action is required from the laboratory.

4.0 CONCLUSIONS

Overall, the data quality is acceptable. The Data Validation Review has identified aspects of the analytical data that require qualification. Data qualifiers, when applicable, are placed next to the results so that the data user can assess the qualitative and/or quantitative reliability of the reported results. Except where noted, the laboratory analytical data contained herein are deemed usable and in compliance with the NYSDEC ASP B Data Deliverable Format requirements. To confidently use any of the data within the data set, the data user should understand the limitations and qualifications presented.

DATA VALIDATION REVIEW
PROJECT: COLUMBIA CEMENT, FREEPORT, NY
DATE SAMPLES COLLECTED: AUGUST 27 THROUGH SEPTEMBER 15, 2004
JOB NO.: 38546433

LAB REPORT NOS: N76706, N76856, N77152 and N78141

1.0 INTRODUCTION

This Data Validation Review has been performed in accordance with the requirements specified in the standard operating procedures (SOP) for the validation of volatile organic and semi-volatile organic data using USEPA Region II SW-846 Method 8260B, SOP HW-24, Rev. 1, dated June 1999 and Method 8270C, SOP HW-22, Rev. 2, dated June 2001, respectively, and SW-846 methodologies. The data validation review requirements are applied such that specifications of the methods take precedence over the specifications of the USEPA Region II SW-846 Method SOP Organic Data Review guidelines in those instances where the specifications differ.

The objective of the review was to assess data usability and compliance with the modified New York State Department of Environmental Conservation (NYSDEC) Analytical Service Protocol (ASP) Category B data deliverable requirements. The Data Validation Review provides an interpretation of data usability based on the reported quality control parameters. A total of 21 soil samples, one field-blank and 4 trip-blank samples were collected by URS Corporation – Cranford, New Jersey, and submitted to Accutest Laboratories of Dayton, New Jersey (NYSDEC Certification No. 10983). Six soil samples and one trip-blank sample from Accutest Data Set N78141 were selected for data validation review to assess the overall data quality. Section 2.0 of this report summarizes the samples included in this review and the analyses performed. The samples were analyzed following USEPA SW-846 methodologies. The laboratory analytical data set contained herein was prepared in accordance with NYSDEC ASP Category B Data Deliverable Format (Exhibit B).

The organic data quality review is based on the following parameters:

- * • Hold Times
- * • Blank Contamination
- * • GC/MS Performance Check (Tuning) Summaries
- System Monitoring Compound (Surrogate) Recoveries
- * • Internal Standard Area Performance
- Initial and Continuing Calibration Results
- Matrix Spike (MS) and Matrix Spike Duplicate (MSD) Summaries
- * • Target Compound Identification and Quantitation
- * • Tentatively Identified Compounds

*All criteria were met for this parameter

This report was prepared to provide a critical review of the laboratory analysis and reported chemical results. Overall, the data quality is acceptable. The results of the Data Validation Review are presented in Section 3.0. Data qualifiers, when applicable, are placed next to the

results so that the data user can assess the qualitative and/or quantitative reliability of the reported result.

2.0 SAMPLES INCLUDED IN REVIEW

<u>Sample ID</u>	<u>Lab ID</u>	<u>Date Collected</u>	<u>Test Requested</u>
Lab Report No. N78141			
DRUM-1	N78141-01	9/15/04	TCL VOA+10
PIPE-1	N78141-02	9/15/04	TCL VOA+10
PIPE-2	N78141-03	9/15/04	TCL VOA+10
PIPE-3	N78141-04	9/15/04	TCL VOA+10
PILE-1	N78141-05	9/15/04	TCL VOA+10
DRAIN-1	N78141-06	9/15/04	TCL VOA+10 and TCL BNA+15
TB091504	N78141-07	9/15/04	TCL VOA+10

Legend:

TCL VOA+10 = Target Compound List Volatile Organic Compounds plus Forward Library Searches following USEPA SW-846 Method 8260B.

TCL BNA+15 = Target Compound List Semi-volatile (Base/Neutral and Acid-Extractable) Organic Compounds plus Forward Library Searches following USEPA SW-846 Method 8270C.

3.0 RESULTS

3.1 GENERAL COMMENTS

With regard to the data package deliverables, most of the NYSDEC ASP Category B Data Deliverable format requirements were met, with the exception of the following correctable deficiencies. Please note that these deficiencies do not impact data usability.

- In the TCL VOA analysis of Data Set N78141, the GC column was reported incorrectly as EB-624 on the Case Narrative, page 11. Based on a review of the results summary sheets (Form 1), the correct column label should be ZB-624. This reviewer has corrected and initialed this transcriptional error on the case narrative page. No further action is required from the laboratory.
- In the TCL BNA analysis of Data Set N78141, the extraction log was not included in the data package received for review. The laboratory was contacted and the missing extraction log was forwarded to URS. No further action is required from the laboratory.

3.2 ORGANIC QUALIFIERS

Hold Times: Technical hold times were assessed by comparing the sample dates with that of the preparation dates and/or analysis dates.

- The project samples associated with Data Set N78141 were analyzed within the required hold time for TCL VOA and TCL BNA analyses. No qualifier is required.

- The sample cooler temperatures upon laboratory verified time of sample receipt (VTSR) fell within the 4°C (+2°C) requirement. No qualifier is required.

Blank Contamination: Laboratory method blanks are clean liquid and/or solid matrix samples prepared by the analytical laboratory and analyzed in the same manner as the investigative samples. Water laboratory method blanks are used to identify whether investigative samples have been contaminated during sample preparation, sample analysis or from a previous sample (instrument carry-over).

Trip-blanks are carbon-free deionized water samples that accompany volatile investigative samples during each stage of shipment, storage and analysis. Trip-blanks are used to assess the potential for artificial introduction of volatile compounds into the investigative samples during the transportation and sample handling processes.

- No TCL VOA and TCL BNA contaminants were detected in the laboratory method blanks and/or in the trip-blank sample associated with the reviewed project samples. No qualifier is required.
- BNA tentatively identified compounds (TICs) consisting of system artifacts and/or aldol condensation products or ACP were tentatively identified in the laboratory method blank (OP18078-MB1) associated with Data Set N78141. There is no impact on the data quality of sample DRAIN-1 since TICs were not detected in this sample around the retention time at which these system artifacts and/or ACP TICs eluted. No qualifier is required.

GC/MS Performance Check (Tuning) Summary: Gas chromatograph/mass spectrometer (GC/MS) instrument tuning and performance checks are performed to ensure the instrument's ability to provide appropriate mass-resolution, identification and sensitivity.

- The bromofluorobenzene (BFB) tuning compound mass-ion abundance criteria for the volatile organic compound analyses and the decafluorotriphenylphosphine (DFTPP) tuning compound mass-ion abundance criteria for the semi-volatile (base/neutral and acid-extractable) organic compound analyses were reported within control limits for the reviewed data set. No qualifier is required.

System Monitoring Compound (Surrogate) Recoveries: System monitoring compounds (surrogates) are those compounds, which are not expected to be detected in the investigative samples but which are chemically similar to the analytes of interest. Surrogate compound percent recoveries are used to assess extraction efficiencies, possible matrix effects and overall analytical accuracy.

- The VOA surrogate, toluene-d8 (TOL), fell outside the control limits (high) for the initial analysis (1:50 dilution) of sample PIPE-3 (Data Set N78141). Additionally, TOL was also recovered high for the matrix spike/matrix spike duplicate of sample PIPE-3, which suggests possible matrix effects. Sample PIPE-3 was re-analyzed at a 1:1000 dilution due to the target compound concentrations exceeding the linear calibration range requirements. The positive VOA results of the initial analysis (1:50 dilution) of sample PIPE-3 may be biased high and are flagged (J) estimated on the

laboratory summary pages. There is no impact on the data quality of the non-detected VOA results and no qualifier is required.

- With the exception of sample PIPE-3 previously described, the VOA surrogate recoveries fell within control limits for the reviewed project samples of Data Set N78141. No qualifier is required.
- The BNA surrogate recoveries fell within control limits for the reviewed project sample DRAIN-1 associated with Data Set N78141. No qualifier is required.

Internal Standards Area Performance: Internal standards are analytes of interest, which are added to the investigative samples prior to analysis to ensure that GC/MS sensitivity and responses remain stable. Internal standards are reported with VOA and BNA analyses.

- The TCL VOA and TCL BNA internal standard area counts and retention times fell within control limits for the reviewed project samples associated with Data Set N78141. No qualifier is required.

Initial and Continuing Calibration Results: Control limits for initial and continuing instrument calibrations are established to ensure that the instrument is capable of producing accurate quantitative data at the beginning and throughout each of the analyses.

- High percent relative standard deviation (%RSD >15 but <50) was reported for the initial calibration response factors for the TCL VOA compound, acetone, associated with the reviewed project samples of Data Set N78141 (with the exception of trip-blank sample TB091504). There is no impact on the data quality of the acetone results since acetone is non-detected in these samples and no qualifier is required.
- High %RSD (%RSD >15 but <50) was reported for the initial calibration response factors for the TCL VOA compound, 2-hexanone, associated with the reviewed project samples of Data Set N78141 (with the exception of sample PIPE-3 and trip-blank sample TB091504). There is no impact on the data quality of the 2-hexanone results since 2-hexanone is non-detected in the associated project samples and no qualifier is required.
- Due to the high percent difference (%D >20 but <90) between the initial and continuing calibration response factors for the TCL VOA compounds, 2-butanone and 2-hexanone, associated with the trip-blank sample TB091504 (Data Set N78141), the non-detected 2-butanone and 2-hexanone results are regarded as estimated values and are flagged (UJ) on the laboratory summary pages and on the summary table.
- With the exception of acetone, 2-hexanone and 2-butanone noted previously, the TCL VOA and TCL BNA initial and continuing calibration response factors, %RSD and/or correlation coefficient (*r*) and %D or percent drift fell within acceptable control limits associated with the reviewed project samples. No qualifier is required.

Matrix Spike (MS) and Matrix Spike Duplicate (MSD) Summaries: Matrix spikes are samples spiked with known concentrations of analytes of interest. The MS/MSD percent recoveries and duplicate results are used to assess extraction efficiencies, possible matrix effects, and overall analytical accuracy and precision.

Blank spikes (BS) are blank samples fortified (spiked) with known concentrations of compounds of interest. The blank spike percent recoveries are used to assess extraction efficiencies and overall analytical accuracy.

- The recovery of the TCL VOA spiking compound, toluene, fell outside the control limits (low) for the PIPE-3 MSD sample associated with sample PIPE-3 (Data Set N78141). Additionally, the Relative Percent Difference or RPD fell outside the control limits for toluene. There is minimal impact on the data quality of toluene in sample PIPE-3 since the MS recovery of toluene fell within control limits. Additionally, the associated BS recoveries fell within control limits. No qualifier is required.
- The TCL VOA MS/MSD/BS results (recoveries and RPD) associated with the remaining project samples of Data Set N78141 fell within acceptable control limits providing a positive indication of the overall accuracy and precision associated with these analyses. No qualifier is required.
- The TCL BNA spiking compound, 2,4-dinitrophenol, was not recovered for the N77876-25 MS/MSD (non-project) samples associated with Data Set N78141. Additionally, the MS and MSD recovery of di-n-octylphthalate fell outside the control limits (high). There is minimal impact on the BNA data quality of sample DRAIN-1 since the MS/MSD samples are non-project samples. Additionally, the associated BS recoveries fell within control limits. No qualifier is required.

Target Compound Identification and Quantitation: The laboratory calculations are verified and compound identifications are reviewed and assessed by the data reviewer.

- Sample PIPE-3 (Data Set N78141) was initially analyzed at a 1:50 dilution (as a medium level soil) for TCL VOA. Due to the target compound concentrations exceeding the linear calibration range requirements, sample PIPE-3 was re-analyzed at a 1:1000 dilution (as a medium level soil). Both the TCL VOA initial and dilution analysis results are reported on the laboratory summary pages. No qualifier is required.
- The GC/MS raw data (quantitation reports, chromatograms and mass-spectra) were provided for review. No laboratory calculation errors were noted for samples selected for verification during the Data Validation Review. No further action is required from the laboratory.

Tentatively Identified Compounds: In addition to the specific target compounds identified, up to 25 non-target organic compounds of greatest apparent concentration (10 for VOA and 15 for BNA) were tentatively identified by a computerized search of the National Bureau of Standards (NBS) mass-spectral library. A mass-spectral interpretation specialist compares the sample mass-spectrum to the library search and assigns a tentative identification. The

validity of the TICs were evaluated based upon the identifications made by the laboratory, and the following comments are offered:

- Volatile TICs were tentatively identified only in samples PIPE-3, PILE-1 and DRAIN-1 (Data Set N78141). VOA TICs associated with sample PIPE-3 consist of alkanes, alkylated cycloalkanes, cycloalkanes/alkenes, an alkylated alkane and an unknown. An unknown was tentatively identified in samples PILE-1 and DRAIN-1.
- BNA TICs were not tentatively identified in sample DRAIN-1 associated with Data Set N78141. No qualifier is required.

Additional Comments

- As per the requirements, values calculated below the Reporting Limit (RL) should be considered estimated and are flagged (J) on the summary table.

4.0 CONCLUSIONS

Overall, the data quality is acceptable. The Data Validation Review has identified aspects of the analytical data that require qualification. Data qualifiers, when applicable, are placed next to the results so that the data user can assess the qualitative and/or quantitative reliability of the reported results. The laboratory analytical data contained herein are deemed usable and in compliance with the NYSDEC ASP Category B Deliverable Format requirements. To confidently use any of the data within the data set, the data user should understand the limitations and qualifications presented.