



April 21, 2015

Transmitted: PDF File Transmission and 1st Class USPS Mail to CC List

Mr. Kent Johnson
Senior Engineering Geologist
New York State Dept. of Environmental Conservation
Division of Environmental Remediation
Remedial Section B – Remedial Bureau E
625 Broadway
Albany, NY 12233-7017

**SUBJECT: Post-Injection and Q1 2015 Groundwater Monitoring Program Report
Safety-Kleen Service Center – 60 Seabro Avenue
North Amityville, New York**

Dear Mr. Johnson:

This letter serves as the Safety-Kleen Systems, Inc. (Safety-Kleen) first quarter 2015 groundwater monitoring report for the referenced site (**Attachment 1 – Site Map**). This letter also serves as a post-injection remedial program (BOS 200®) monitoring report.

Groundwater sampling was conducted on March 9 and 10, 2015. The samples were sent to Test America, Inc. (TA). TA's Edison, NJ laboratory performed both the Mineral Spirit Range Organics (MSRO) as well as the Volatile Organic Compound (VOC) analyses. Monitored Natural Attenuation (MNA) parameter analysis was conducted by TA's laboratories in Edison, NJ, Buffalo, NY, and Nashville, TN. TA holds both NY NELAP and NYSDOH ELAP certifications.

Test America (Edison, NJ) continued to analyze MSRO by EPA Method 8260. Safety-Kleen directed the laboratory to begin the method studies (for soil and water) required to calibrate EPA Method 8015 to Safety-Kleen's 105 mineral spirits formulation as the standard. That documentation was previously submitted for your consideration. Once the studies are approved by the Department, Safety-Kleen will begin using Method 8015 for the detection of MSRO.

1.0 POST-INJECTION and QUARTERLY GROUNDWATER SAMPLING PROGRAM

The following was performed during the monitoring event (as required):

- Prior to sampling, the ORC-A® filter socks were removed from wells GT-1, GT-3, GT-5, VP-A and VP-B. Following the equilibration of the water table, field and laboratory samples were then collected. Post sampling, filter socks were reinstalled;
- Measurement of the depth to water (DTW) at each monitoring well, four vapor points and one catch basin/drywell;
- Monitoring point development for groundwater field/lab parameter measurement;

- Collection of groundwater samples from site monitoring points; and
- Packing (on ice) and delivery of the sample set to a TA sample collection location, TA courier, or shipment to the laboratory via overnight commercial courier.

1.1 Monitoring Point Field Parameter Collection & Summary

Monitoring wells GT-1 through GT-7, VE-5, VP-A, VP-B, and DW-1 were gauged and field indicator parameters were collected at the wells during the March 2015 sampling event. VE-1R was inaccessible and not sampled in March 2015.

Temperature, pH, conductivity, dissolved oxygen (DO), oxidation/reduction potential (ORP), and visual turbidity were recorded. The field/sampling data from the March 2015 sampling event is included as **Attachment 2**. The historic to current field data are presented as **Attachment 3 - Table 1**.

Depth-to-water ranged from 15.42 (GT-4) to 17.39 (GT-5) feet below grade in March 2015 in exterior wells. Comparatively, the water table was on average approximately 1 foot shallower than reported for the previous quarter, December 2014.

The depth-to-water at selected site monitoring wells is presented below as **Figure 1**. The historical data indicate that the water table is deeper now than reported historically and continues to trend deeper.






Figure 2 depicts the flow conditions for March 2015. The direction of groundwater flow was south-southeasterly and generally consistent with historic trends. The average gradient was measured at 0.16 %, similar to that reported for December 2014.



The DO concentrations ranged between 3.42 mg/l at GT-1 to over 100 mg/l at DW-1, VP-A and VP-B in March 2015. Six wells (GT-1, GT-3, GT-5, VE-1R, VP-A and VP-B) have ORC-A® filter socks installed. The DO concentrations in VP-A and VP-B were significantly higher than reported for December 2014 (15.20 and 11.48 mg/l, respectively). The DO at other site monitoring wells was similar to historic levels. **Figure 3** shows the historic trend in DO concentrations in GT-1, GT-3, GT-5, and VP-B.



The pH across the site (**Figure 4**) ranged from 5.82 (GT-1) to 9.42 (GT-4) in March 2015. Higher pH, shown since August 2013, is a known side effect from the ORC-A® dissolution and has occurred at other Safety-Kleen sites that also utilize ORC-A®. With the exception of GT-4 and the most recent detection in GT-3, the pH levels have shown a reducing trend since the August 2014 sampling event in the target GT-1 area and pH levels appear to be returning to pre-August 2013 levels or lower, possibly affected by metabolic byproducts of the October 2014 remedial injection (refer to **Section 4**).



1.2 Groundwater Sampling

Monitoring wells GT-1, GT-2, GT-3, GT-5, GT-6, GT-7, vapor extraction/monitoring points VE-5, VP-A, VP-B and catch basin/drywell DW-1 were purged of 3 to 5 well volumes (conditions permitting) of groundwater with a bailer, whale pump, or peristaltic pump prior to sampling.

Groundwater samples were collected with dedicated, disposable polyethylene bailers or tubing and placed into glass containers provided by TA as specified for each analysis. A duplicate sample was collected for quality assurance purposes from GT-6 (GW-DUP) and from DW-1 (DW-1 DUP). Also, an equipment rinse blank was prepared in the field and submitted to the laboratory for analysis.

Samples were kept cool during transport to the laboratory, accompanied by chain-of-custody documents and a trip blank. The samples arrived at the laboratory within acceptable USEPA and NYSDEC holding times and preservation requirements.



TA analyzed the samples for VOCs via EPA Method 8260B, and for MSRO via Modified EPA Method 8260B.

2.0 ANALYTICAL RESULTS

Historic data through March 2015 are presented in **Attachment 3 - Table 2**. The laboratory analytical report is included as **Attachment 4** (on CD, Executive Summary in print).

VOCs: VOCs were not detected above the reporting limits (EPA Method 8260B) or the respective standards in any groundwater samples. A summary of detections can be found in the laboratory report Executive Summary (**Attachment 4**).

MSRO: MSRO was not detected in groundwater collected during the March 2015 sampling events at GT-1, GT-2, GT-3, GT-4, GT-5, GT-7, VP-A, VP-B, VE-5 and DW-1. MSRO was detected in the primary and duplicate groundwater samples for GT-6 (240 ppb and 350 ppb, respectively) during the March 2015 sampling event. The concentration of MSRO detected in GT-6 during the March 2015 sampling event was reduced from the previous sampling events. MSRO concentrations for the Warehouse Area, the primary business portion of the site, are presented in **Figure 5** and MSRO concentrations for the GT-1/VE-1R and down gradient area GT-6 are presented in **Figure 6**.





Monitored Natural Attenuation (MNA): As part of the pre-injection and post-injection sampling effort, natural attenuation parameters including; iron (dissolved), manganese (dissolved), nitrate (NO₃), nitrite (NO₂), ammonia (total; NH₃+NH₄), sulfate (SO₄), total organic carbon (TOC), carbon dioxide (CO₂), alkalinity, bicarbonate (HCO₃), hydrogen sulfide (H₂S), methane (CH₄), and phosphate (PO₄); were analyzed to assess groundwater conditions prior to the remedial injection program as well as the post-injection condition. The MNA parameters of most importance for monitoring the progress of the BOS 200® remedial injection program are concentrations of nitrate, nitrite, and sulfate. The BOS 200® injected slurry will initially increase the concentration of nitrate and sulfate in the injection area. As the slurry begins to react, the oxygen in the system is depleted, and nitrate acts as the primary electron receptor, nitrate concentrations drop and nitrite should be observed.

The target remedial injection area (GT-1) showed a slight increase in DO concentration from 2.06 ppm in December 2014 to 3.42 ppm in March 2015. Nitrate/Nitrite concentrations in GT-1 both increased from a total of 3.4 ppm in December 2014 (60 days post-injection) to 25.5 ppm in March 2015. As the process extends, DO, nitrate and nitrite should be consumed and concentrations should fall back to pre-injection levels. The last step in the process is the reduction of sulfate from the system, as other electron receptors are depleted.

DO, nitrate/nitrite, and sulfate concentrations for GT-1, VE-1R, and GT-6 are presented in **Figure 7** and the results of all MNA sampling is presented in **Attachment 3 - Table 3**. (Note that VE-1R was not sampled in March 2015; therefore, the figure represents MNA concentrations through December 2014.)

FIGURE 7: Select MNA Parameters - GT-1/VE-1R/GT-6 Area - (mg/L)





3.0 SUMMARY

1. Groundwater elevations in March 2015 were higher on average than recorded in December 2014. Overall, the direction and magnitude of groundwater flow is similar to historic trends.
2. DO concentrations in wells with ORC-A® filter socks were elevated when compared to historic levels. DO in other site wells had concentrations similar to historic trends.
3. The pH at wells where ORC-A® socks are installed had been predictably higher; however, pH in most wells has recently dropped, possibly affected by metabolic byproducts of the October 2014 remedial injection.
4. MSRO was not detected at concentrations above the laboratory reporting limit in the GT-1/VE-1 area. Concentrations of MSRO were only detected in groundwater collected from GT-6 and its duplicate sample (240 ppb and 350 ppb, respectively) above the requisite standards; however, the concentration was an order of magnitude lower than the previous sampling event in December 2014.
5. MSRO was detected in only one of the two down-gradient monitoring wells (GT-6) at concentrations above the requisite standard during the March 2015 sampling event. It was not detected at GT-7, located east of GT-6, suggesting that the offsite expression of MSRO is limited.
6. MSRO was not detected above the laboratory reporting limit in the drywell DW-1 groundwater sample collected in March 2015.

4.0 RECOMMENDATIONS

In early October 2014, the BOS 200® remedial injection program was completed. Post-injection groundwater sampling results indicate the presence of MSRO above the requisite standard offsite in well GT-6; however, the concentration is significantly lower than previously detected in the well. Safety-Kleen will continue to deploy oxygen releasing compound filter socks at GT-1, GT-3, GT-5, VE-1R, VP-A and VP-B, and recommends continued quarterly groundwater monitoring in agreement with the Department's letter of April 6, 2015.

I am available to discuss the results with you at your convenience. Please do not hesitate to contact me at (513) 275-3960. As always, Safety-Kleen appreciates the Department's assistance with this site.

Sincerely,

Safety-Kleen Systems, Inc.



Stephen D. Fleming, P.E., CHMM
Senior Remediation Manager

FIGURES (in text)

- 1 Depth to Water Across the Site
- 2 Groundwater Contour Map
- 3 Dissolved Oxygen Across the Site
- 4 pH Across the Site
- 5 MSRO – Warehouse Area (Former R/F)
- 6 MSRO - GT-1/VE-1/GT-6 Area
- 7 Select MNA Parameters - GT-1/VE-1/GT-6 Area

ATTACHMENTS

- 1 Site Map
- 2 Media Sampling - Field Parameter and Lab Sampling Summaries
- 3 Tables
 - Table 1 – Historic Groundwater Field Data Summary (to Current)
 - Table 2 – Groundwater Monitoring Results Summary (to Current)
 - Table 3 – Groundwater Natural Attenuation Parameters Summary
- 4 Laboratory Analytical Report (on CD) – Executive Summary Attached


Distribution

Person/Department	Method of Transmission
E. Badaracco, Town of Babylon, HW Dept., Lindenhurst, NY	hard copy – 1 st Class Mail
C. Horan, NYSDEC, Central Office, Albany, NY	e-copy
M. Leary, NYSDEC, Albany, NY	e-copy
K. Murphy, NYSDEC Region 1, Stony Brook, NY	e-copy
A. Everett, USEPA Region II, New York, NY	hard copy – 1 st Class Mail
T. Cowans, Safety-Kleen, N. Amityville, NY	e-copy
Branch General Manager, Safety-Kleen, N. Amityville, NY	e-copy
N. Nelhuebel, VP Env. Liabilities, Clean Harbors, Norwell, MA	compact disk – 1 st Class Mail
Woodard & Curran, Cheshire, CT	e-copy
AST Environmental, Midway, KY	e-copy


Note: e-copies transmitted via E-Mail – S. Fleming, SK to List.

ATTACHMENT 1 - SITE MAP


LONG ISLAND RAILROAD (CENTRAL BRANCH)



SOURCE:
MAP BASED ON SAFETY KLEEN BASE MAP
ENTITLED "SITE PLAN EXISTING" DATED
8/26/00; DRAWING NO. 7039-SPOO-001,
REV. 1 BY RM - SCALE: 1"=20'



- LEGEND
- GT-3 MONITORING WELL LOCATION
 - DRYWELL (ADDRESSED IN CLOSURE)
 - 23 DRYWELL (EXISTING)
 - CB-2B OVER-FLOW POOL
 - NEW PROPOSED BORING
 - ALREADY COMPLETED BORING
 - 6" LINE CONNECTING OFF TO DRYWELL
 - PROPERTY LINE
 - VE/VP-x Vapor Extraction Well



Basile Environmental Solutions, LLC 1188 Hillside Dr. Cortland, NY 13045		5/23/12
SCALE: AS SHOWN		7039-1A
CAD FILE:		
DRAWN BY: JB		
CHECKED BY: J.B.	TITLE: SITE PLAN	
FIGURE No: 1	CLIENT: SAFETY-KLEEN SYSTEMS INC. 60 SEABRO AVENUE NORTH AMITYVILLE, NY	

ATTACHMENT 2 - MEDIA SAMPLING

Field Parameter and Lab Sampling Summaries

SAMPLING INSTRUCTIONS & FIELD OBSERVATION LOG

GROUNDWATER SAMPLING RECORD

SITE NAME	Safety-Kleen Service Center	DATE	3/9/2015; 3/10/2015									
	60 Seabro Ave, N.Amityville, NY	Weather	50-53 deg F, clear, melting; 42-45 deg F, overcast, showers									
Sampler Jonathon Wylie												
Well Name / ID	GT-1	GT-2	GT-3	GT-4	DW-1	GT-5	GT-6	GT-7	VE-1R	VE-5	warehouse	
Lab Analysis - EPA 8260b VOCs	Collect Samples as listed on the pre-printed Chain-of-Custody. Questions, contact Melissa Haas at Tel 203.944.1310.											
Lab Analysis - EPA 8260b MSRO												
Natural Attenuation Parameters												
RPI Labs - Split Samples	Collect Samples as Directed by AST Environmental, Inc. Project Manager - Nathan Thacker - Separate Cooler Provided, with glassware, by RPI Labs. Questions Call Nathan at 859-608-1811 (mobile)											
Duplicate Sample:	Collect Samples as listed on the pre-printed Chain-of-Custody. Questions, contact Melissa Haas.											
Sample Equipment Rinse Blank												
MS/MSD												
Collect Field Parameters	Yes	Yes	Yes	Yes-Only	Yes	Yes	Yes	Yes	Yes	yes	Yes	Yes
Diameter of Well Casing	2 in	2 in	2 in	2 in	Manhole	2 in	2 in	2 in	4 in	1 in	2 in	2 in
Depth of Well (ft.)	26.0	27.40	27.48	26.18	10.50	21.2	26.46	28.3	24.80	24.80	27.5	23.0
Depth to Groundwater (ft.)	17.09	16.99	16.06	15.42	9.71	17.39	17.32	17.02	--	16.56	18.45	16.98
Water Column Height (ft.)	8.91	10.41	11.42	10.76		3.81	9.14	11.28	--	8.24	9.05	6.02
Volume Purged (gal)	19.00	5.25	5.75	--	--	12.00	5.75	5.75	--	1.25	4.50	3.00
Purging Method	Whale Pump	Bailer	Bailer	Bailer	Peristaltic	Whale Pump if needed.	Bailer	Bailer	Whale Pump	Bailer	Bailer	Bailer
Purge till carbon in-solution clears at wells GT-1, GT-5 and VE-1R												
Sampling Time	16:00	19:30	17:30	--	11:52	15:20	12:51	13:56	--	18:30	9:15	10:15
Sample date	3/10/15	3/10/15	3/10/15	--	3/10/15	3/10/15	3/10/15	3/10/15	--	3/10/15	3/10/15	3/10/15
GW Visual Observations												
color	Black	Grey	Grey	Orange	Grey	Clear	Clear	Tan	--	Tan	Tan	Lt Brown
sheen (slight, moderate, heavy)	No	No	No	No	No	No	No	No	--	No	No	No
odor (slight, moderate, heavy)	Heavy	No	No	No	No	No	No	No	--	No	No	No
particulates/settled matter (lo, med, high)	High	Low	Med	High	High	Low	Low	Med	--	Med	Low	Low
Field Parameters												
Temperature (C)	11.66	11.68	8.09	12.28	4.43	12.50	12.90	12.23	--	10.71	13.9	14.0
pH	5.82	6.85	7.88	9.42	6.34	6.53	7.04	6.46	--	7.18	8.26	6.74
Conductivity in uS	502.00	513.00	86.00	57.00	442.00	245.00	342.00	304.00	--	215.00	323	250
Dissolved Oxygen (mg/L)	3.42	5.10	13.37	10.90	146.20	5.42	3.70	4.36	--	8.06	107.00	100.30
ORP (Eh (Mv))	-224.70	-198.90	-203.40	-178.00	-215.60	-207.30	-234.10	-212.60	--	-198.50	-178	-175
Turbidity (visual / NTU)	Cloudy	Slightly Cloudy	Cloudy	Cloudy	Cloudy	Clear	Clear	Cloudy	--	Cloudy	Cloudy	Cloudy
									Not Accessible			
Comments	Notify laboratory prior to shipping, in the event that pulverized carbon settles-out in any sampling container. Contact Melissa Haas at Tel 203.944.1310											
	Purge Method: Whale pump maybe used to purge wells at any location the pump can be deployed. Order of Purge for decon purposes - GT-1, VE-1R, GT-5. Decon between all locations withalconox and water wash, with water rinse. Containerize all fluids as directed by Terri Cowans at the facility, Tel: 631.443.4509 (cell). Coordinate with Terri in regards to moving all IDW back to the facility from wells GT-6 & GT-7. Under no circumstances are drums or debris to be left near wells GT-6 & 7. Both wells are located off-site. SK/consultants have permission from the property owner to access the wells.											
	On-arrival at the facility, check-in at the main office, and notify Terri you are on-site. Follow all facility rules, and any direction with regard to well access, facility access,											
	Sample Collection Equipment: Collect samples with dedicated disposable bailers. DW-1 Soil Bottom Sample - Collect with Hand-Auger.											

ATTACHMENT 3 - TABLES

Table 1 – Historic Groundwater Field Data Summary (to Current)

Table 2 – Groundwater Monitoring Results Summary (to Current)

Table 3 – Groundwater Natural Attenuation Parameters Summary

Table 1 - Historic Groundwater Field Data Summary (to Current)

KEY

Temperature recorded in C
 Conductivity measured in uS
 Dissolved Oxygen measured in mg/l
 Eh measured in Mv
 Ozone measured in mg/l
 Duplicate sample analysis is in parentheses.

GT-1	PARAMETER								
	Depth to water (ft)	Groundwater Elevation (ft)	Temp	pH	Cond.	D.O.	Eh	Ozone	MSRO
			°C		uS	mg/L	mV		ug/L
12-Mar-09	16.47	37.64	12.2	7.00	459	2.96	163	ND	500
17-Jun-09	15.73	38.38	13.5	7.75	381	5.20	48	0.10	50
22-Sep-09	17.05	37.06	17.0	7.65	224	4.40	-29	0.10	530
30-Dec-09	16.49	37.62	15.0	6.85	182	2.80	91	0.08	1,300
02-Feb-10	16.75	37.36	13.5	7.03	179	7.35	45	0.00	1,000
24-Mar-10	13.80	40.31	12.0	7.08	603	31.50	165	0.60	6,400
22-Jun-10	15.30	38.81	15.5	7.03	182	6.57	32	0.00	3,000
22-Sep-10	18.70	35.41	17.8	7.08	176	3.98	28	n/m	18,000
15-Dec-10	19.28	34.83	15.3	7.13	157	2.95	10	0.00	12,000
24-Mar-11	17.83	36.28	13.0	7.60	198	3.21	25	0.00	18,000
16-Jun-11	17.01	37.10	14.7	7.03	259	3.68	20	0.02	8,500
15-Sep-11	15.88	38.23	19.0	7.06	197	3.62	-62	0.00	12,000
16-Dec-11	16.40	37.71	16.0	7.03	186	3.45	-55	0.00	15,000
14-Mar-12	17.65	36.46	14.2	7.06	136	2.95	-60	0.00	16,000
20-Jun-12	17.48	36.63	16.8	7.06	138	2.88	-45	0.00	9,200
28-Aug-12	18.46	35.65	18.0	7.18	118	2.80	-75	0.00	15,000
25-Oct-12	19.18	34.93	18.0	7.12	196	4.22	11	0.20	23,000
20-Dec-12	19.38	34.73	15.7	7.12	119	2.88	-50	0.00	12,000
14-Mar-13	17.57	36.54	12.1	7.30	137	2.90	-20	0.00	22,000
20-Jun-13	16.23	37.88	14.8	7.02	213	3.87	-11	0.00	16,000
24-Sep-13	19.07	35.04	17.1	11.00	637	8.22	25	0.00	41,000
18-Dec-13	20.28	33.83	16.5	10.62	1070	7.88	n/m	0.00	5,700
25-Feb-14	19.42	34.69	13.7	9.80	249	5.49	30	0.00	6,100
11-Jun-14	17.32	36.79	13.8	11.01		9.29	38.5	0.00	1,400
26-Aug-14	17.64	36.47	17.5	8.58	414	6.01	41	n/m	520
13-Nov-14	19.51	34.60	17.0	7.20	477	1.08	162	0.00	120
15-Dec-14	17.99	36.12	15.6	6.45	541	2.06	24	n/m	
10-Mar-15	17.09	37.02	11.7	5.82	502	3.42	-224.7	n/m	

Table 1 - Historic Groundwater Field Data Summary (to Current)

KEY

Temperature recorded in C
 Conductivity measured in uS
 Dissolved Oxygen measured in mg/l
 Eh measured in Mv
 Ozone measured in mg/l
 Duplicate sample analysis is in parentheses.

GT-2	PARAMETER								
	Depth to water (ft)	Groundwater Elevation (ft)	Temp °C	pH	Cond. uS	D.O. mg/L	Eh mV	Ozone	MSRO ug/L
12-Mar-09	16.38	37.75	12.9	7.14	500	0.77	167	ND	
17-Jun-09	15.63	38.50	13.0	7.63	270	3.29	57	0.06	
22-Sep-09	16.95	37.18	17.0	7.01	711	2.00	77	0.40	
30-Dec-09	16.40	37.73	14.2	6.95	427	2.05	95	0.02	
02-Feb-10	16.66	37.47	12.8	7.14	330	2.84	232	0.00	
24-Mar-10	13.70	40.43	12.7	7.11	452	2.00	92	0.00	
22-Jun-10	15.10	39.03	16.5	7.14	1064	1.17	-29	0.00	
22-Sep-10	18.61	35.52	17.0	7.09	302	2.55	-33	n/m	
15-Dec-10	19.22	34.91	13.8	7.09	384	2.80	-40	0.00	
24-Mar-11	17.77	36.36	11.6	7.05	530	3.14	-25	0.00	
16-Jun-11	16.90	37.23	16.0	7.02	667	3.36	-30	0.00	
15-Sep-11	15.77	38.36	19.0	7.06	644	2.92	-141	0.00	
16-Dec-11	16.33	37.80	15.1	7.10	476	3.05	-105	0.00	
13-Mar-12	17.57	36.56	14.0	7.05	403	3.00	-55	0.00	
20-Jun-12	17.40	36.73	16.8	7.08	426	2.68	-38	0.00	
28-Aug-12	18.36	35.77	18.5	7.17	398	3.07	-40	0.00	
25-Oct-12	19.10	35.03	17.5	7.06	315	2.11	-10	0.00	
20-Dec-12	19.30	34.83	15.3	7.42	319	3.50	-55	0.00	
14-Mar-13	17.50	36.63	12.1	7.32	317	3.05	-40	0.00	
20-Jun-13	16.13	38.00	16.0	7.11	350	2.31	-21	0.00	
24-Sep-13	19.00	35.13	17.2	7.05	404	2.04	-2	0.00	
18-Dec-13	20.21	33.92	14.6	7.05	288	2.47	4	0.00	
25-Feb-14	19.37	34.76	12.2	8.11	187	3.50	240	0.00	
11-Jun-14	17.22	36.91	14.5	6.07		3.76	200.4	0.00	
26-Aug-14	17.61	36.52	17.5	7.58	647	3.07	189	n/m	
12-Nov-14	19.38	34.75	16.2	7.30	575	2.98	156	0.00	
16-Dec-14	17.86	36.27	13.8	6.69	619	8.26	110	n/m	
10-Mar-15	16.99	37.14	11.7	6.85	513	5.10	-198.9	n/m	

Table 1 - Historic Groundwater Field Data Summary (to Current)

KEY

Temperature recorded in C
 Conductivity measured in uS
 Dissolved Oxygen measured in mg/l
 Eh measured in Mv
 Ozone measured in mg/l
 Duplicate sample analysis is in parentheses.

GT-3	PARAMETER								
	Depth to water (ft)	Groundwater Elevation (ft)	Temp °C	pH	Cond. uS	D.O. mg/L	Eh mV	Ozone	MSRO ug/L
12-Mar-09	15.28	38.24	11.7	7.36	214	6.60	125	0.20	
17-Jun-09	14.52	39.00	13.3	7.69	219	6.30	68	0.10	
22-Sep-09	15.83	37.69	18.0	7.25	300	6.70	50	0.01	
30-Dec-09	15.31	38.21	14.4	6.95	186	4.22	97	0.05	
02-Feb-10	15.58	37.94	13.2	7.13	215	7.68	243	0.05	
24-Mar-10	12.63	40.89	10.9	7.08	174	8.24	118	0.00	
22-Jun-10	14.11	39.41	16.0	7.10	226	6.30	49	0.00	
22-Sep-10	17.49	36.03	18.0	7.07	176	2.00	55	n/m	
15-Dec-10	18.15	35.37	14.2	7.07	120	2.18	15	0.00	
24-Mar-11	16.84	36.68	10.7	7.60	160	7.36	15	0.00	
16-Jun-11	16.00	37.52	14.0	7.44	226	7.85	21	0.00	
15-Sep-11	14.85	38.67	19.0	7.02	158	6.99	-37	0.00	
16-Dec-11	15.37	38.15	16.0	7.06	189	4.95	-42	0.00	
14-Mar-12	16.65	36.87	14.0	7.04	191	3.58	-30	0.00	
20-Jun-12	16.49	37.03	16.0	7.21	82	3.54	-10	0.00	
28-Aug-12	17.41	36.11	20.2	7.05	402	6.01	-11	0.00	
25-Oct-12	18.15	35.37	18.4	7.43	134	3.18	-11	0.00	
20-Dec-12	18.37	35.15	15.3	7.85	97	3.81	25	0.00	
14-Mar-13	16.54	36.98	11.1	7.35	314	3.10	9	0.00	
20-Jun-13	15.21	38.31	15.6	7.16	135	6.15	7	0.00	
24-Sep-13	18.03	35.49	17.5	7.66	189	4.01	14	0.00	120
18-Dec-13	19.29	34.23	13.8	7.59	293	4.28	11	0.00	81
25-Feb-14	18.42	35.10	11.6	8.69	306	8.06	206	0.00	
11-Jun-14	16.28	37.24	13.0	8.29		10.62	182.4	0.00	
26-Aug-14	16.66	36.86	17.0	8.40	300	7.95	106	n/m	
12-Nov-14	18.45	35.07	16.3	7.18	615	4.88	170	0.00	
15-Dec-14	16.93	36.59	17.0	6.73	224	6.34	72	n/m	
10-Mar-15	16.06	37.46	8.1	7.88	86	13.37	-203.4	n/m	

Table 1 - Historic Groundwater Field Data Summary (to Current)

KEY

Temperature recorded in C
 Conductivity measured in uS
 Dissolved Oxygen measured in mg/l
 Eh measured in Mv
 Ozone measured in mg/l
 Duplicate sample analysis is in parentheses.

GT-4	PARAMETER								
	Depth to water (ft)	Groundwater Elevation (ft)	Temp °C	pH	Cond. uS	D.O. mg/L	Eh mV	Ozone	MSRO ug/L
30-Dec-09	14.85	37.45	15.0	7.75	171	2.05	75	over range	
02-Feb-10	15.11	37.19	11.9	7.11	268	5.26	76	over range	
24-Mar-10	12.14	40.16	11.8	7.03	160	6.88	22	over range	
22-Jun-10	13.61	38.69	14.0	7.08	73	3.01	65	over range	
22-Sep-10	17.12	35.18	16.9	7.04	212	2.82	49	n/m	
15-Dec-10	17.65	34.65	16.8	7.02	232	3.05	50	0	
24-Mar-11	16.20	36.10	12.8	7.70	190	4.20	50	0	
16-Jun-11	15.42	36.88	13.5	7.03	130	3.50	30	0	
15-Sep-11	14.31	37.99	17.0	7.32	154	3.85	15	0	
16-Dec-11	14.73	37.57	16.8	7.13	177	3.58	10	over range	
14-Mar-12	16.03	36.27	14.3	7.03	197	3.95	11	over range	
20-Jun-12	15.89	36.41	15.2	7.05	188	4.20	15	over range	
28-Aug-12	16.90	35.40	17.2	7.10	190	2.60	10	over range	
25-Oct-12	17.57	34.73	18.0	7.14	150	3.55	20	over range	
20-Dec-12	17.73	34.57	16.5	8.20	119	4.05	-22	0.00	
14-Mar-13	15.96	36.34	13.3	7.88	121	4.00	-10	0.00	
20-Jun-13	14.65	37.65	14.0	8.14	143	3.05	-5	0.00	
24-Sep-13	17.50	34.80	15.9	7.41	119	3.22	1		
18-Dec-13	18.64	33.66	16.0	7.48	143	3.80	5	0.00	
25-Feb-14	17.78	34.52	12.6	8.28	98	6.28	176	0.00	
11-Jun-14	15.68	36.62	12.2	5.62		4.30	206	0.00	
26-Aug-14	16.02	36.28	16.5	7.55		5.88	-55	n/m	
12-Nov-14	17.90	34.40	18.0	7.60	156	4.55	-60	0.00	
15-Dec-14	16.27	36.03	17.0	6.73	224	6.34	72	n/m	
10-Mar-15	15.42	36.88	12.3	9.42	57	10.90	-178	n/m	

Table 1 - Historic Groundwater Field Data Summary (to Current)

KEY

Temperature recorded in C
 Conductivity measured in uS
 Dissolved Oxygen measured in mg/l
 Eh measured in Mv
 Ozone measured in mg/l
 Duplicate sample analysis is in parentheses.

GT-5	PARAMETER								
	Depth to water (ft)	Groundwater Elevation (ft)	Temp °C	pH	Cond. uS	D.O. mg/L	Eh mV	Ozone	MSRO ug/L
12-Mar-09	16.75	37.54	13.2	7.14	190	5.44	127	0.10	
17-Jun-09	16.03	38.26	14.5	7.11	221	7.30	50	0.15	
22-Sep-09	17.4	36.89	15.0	7.71	452	6.51	34	0.09	
30-Dec-09	16.81	37.48	12.5	6.92	231	4.96	112	0.10	
02-Feb-10	17.03	37.26	12.9	7.13	315	6.21	113	0.00	
24-Mar-10	14.10	40.19	13.0	7.12	218	5.95	217	0.00	
22-Jun-10	15.61	38.68	15.0	7.09	207	8.02	-46	0.00	
22-Sep-10	19.08	35.21	15.4	7.07	294	4.25	-35	n/m	
15-Dec-10	19.61	34.68	14.8	7.07	243	3.55	-10	0.00	
24-Mar-11	18.18	36.11	13.9	7.34	326	4.08	-15	0.00	
16-Jun-11	17.33	36.96	15.0	7.05	236	4.00	-10	0.00	
15-Sep-11	16.23	38.06	17.0	7.38	142	6.95	6	0.00	
16-Dec-11	16.68	37.61	15.7	7.09	173	5.20	10	0.00	
14-Mar-12	18.00	36.29	15.2	7.07	302	4.02	15	0.00	
20-Jun-12	17.81	36.48	15.8	7.07	315	4.00	15	0.00	
28-Aug-12	18.81	35.48	16.1	7.80	186	5.59	11	0.00	
25-Oct-12	19.51	34.78	15.8	7.15	232	3.95	14	0.00	
20-Dec-12	19.71	34.58	15.0	7.84	110	3.70	40	0.00	
14-Mar-13	17.90	36.39	12.0	7.25	516	2.88	-8	0.00	
20-Jun-13	16.56	37.73	15.1	7.90	129	6.03	2	0.00	570
24-Sep-13	19.42	34.87	15.0	10.98	991	6.88	10		0
18-Dec-13	20.60	33.69	15.1	9.81	410	6.81	14	0.00	0
25-Feb-14	19.73	34.56	11.0	9.06	306	7.46	60	0.00	
11-Jun-14	17.62	36.67	14.1	11.27		12.54	-6.7		140
26-Aug-14	17.97	36.32	17.0	8.80	324	8.01	59	n/m	300
12-Nov-14	19.80	34.49	16.0	6.98	596	2.88	70	0.00	
15-Dec-14	18.24	36.05	12.1	6.30	336	6.76	123	n/m	
10-Mar-15	17.39	36.90	12.5	6.53	245	5.42	-207.3	n/m	

Table 1 - Historic Groundwater Field Data Summary (to Current)

KEY

Temperature recorded in C
 Conductivity measured in uS
 Dissolved Oxygen measured in mg/l
 Eh measured in Mv
 Ozone measured in mg/l
 Duplicate sample analysis is in parentheses.

VE-1	PARAMETER								
	Depth to water (ft)	Groundwater Elevation (ft)	Temp °C	pH	Cond. uS	D.O. mg/L	Eh mV	Ozone	MSRO ug/L
12-Mar-09	16.57	--	12.0	6.94	212	5.63	178	0.11	8,000
17-Jun-09	15.53	--	17.0	7.84	388	1.97	-109	over range	23,000
22-Sep-09	17.15	--	19.2	7.64	547	1.60	-123	0.03	8,400
30-Dec-09	16.59	--	12.0	6.75	334	1.66	-49	0.09	23,000
02-Feb-10	16.83	--	12.0	7.09	221	2.60	-15	0.02	43,000
24-Mar-10	13.90	--	12.1	7.39	392	34.70	202	over range	5,400
22-Jun-10	15.36	--	17.1	7.08	261	3.93	-60	0.00	8,100
22-Sep-10	DRY	--							
15-Dec-10	DRY	--							
24-Mar-11	17.95	--	11.8	7.10	267	4.42	-10	0.00	8,300
16-Jun-11	17.13	--	16.8	7.02	251	3.26	-15	0.00	13,000
15-Sep-11	16.00	--	19.5	7.09	184	1.61	-122	0.00	680
16-Dec-11	16.51	--	14.2	7.00	181	1.88	-104	0.00	10,000
14-Mar-12	17.78	--	14.6	7.20	205	1.80	-120	0.00	2,600
20-Jun-12	17.62	--	18.5	7.10	229	2.10	-105	0.00	
28-Aug-12	Dry	--							
25-Oct-12	18.90	--	19.2	7.17	232	3.95	14	0.18	20,000
20-Dec-12	19.10	--	16.2	7.02	141	1.88	-50	0.00	32,000
14-Mar-13	17.29	--	12.0	7.21	169	2.05	-50	0.00	9,900
20-Jun-13	16.03	--	14.5	7.07	234	2.20	-10	0.00	9,900
24-Sep-13	18.75	--	17.8	10.73	492	6.90	18	0.00	22,000
18-Dec-13	20.00	--	16.6	9.43	225	6.98	20	0.00	42,000
25-Feb-14	19.11	--	10.9	9.97	463	5.07	-10	0.00	44,000
11-Jun-14	17.02	--	13.7	8.66		5.40	-102	0.00	14,000
26-Aug-14	17.38	--	18.0	8.66	487	6.04	65	n/m	18,000
12-Nov-14	19.28	--	17.0	7.28	2839	3.98	163	0.00	36,000
16-Dec-14	17.63	--	12.6	6.56	703	1.52	119.1	n/m	110

Table 1 - Historic Groundwater Field Data Summary (to Current)

KEY

Temperature recorded in C
 Conductivity measured in uS
 Dissolved Oxygen measured in mg/l
 Eh measured in Mv
 Ozone measured in mg/l
 Duplicate sample analysis is in parentheses.

VE-5	PARAMETER								
	Depth to water (ft)	Groundwater Elevation (ft)	Temp °C	pH	Cond. uS	D.O. mg/L	Eh mV	Ozone mg/l	MSRO ug/L
12-Mar-09	15.94	--	12.0	6.94	212	5.63	178	0.11	190
17-Jun-09	15.20	--	15.5	8.01	259	5.60	55	0.06	390
22-Sep-09	16.53	--	19.0	7.50	313	9.65	30	0.01	
30-Dec-09	15.97	--	13.0	6.55	249	5.22	131	over range	
02-Feb-10	16.23	--	12.5	7.12	252	8.00	382	over range	
24-Mar-10	13.26	--	12.5	7.13	218	8.20	153	over range	
22-Jun-10	14.76	--	16.8	7.10	275	8.16	-36	over range	
22-Sep-10	18.20	--	19.0	7.04	210	3.20	-40	n/m	
15-Dec-10	18.80	--	15.0	7.08	221	3.05	20	0	
24-Mar-11	17.33	--	11.9	7.12	188	6.02	5	0	
16-Jun-11	16.50	--	15.8	7.04	255	6.15	7	over range	
14-Sep-11	15.38	--	18.0	7.04	184	4.70	37	0	
16-Dec-11	15.90	--	14.6	7.08	220	3.85	25	over range	
14-Mar-12	17.14	--	14.8	7.07	188	3.25	10	over range	
20-Jun-12	17.00	--	18.0	7.07	162	3.05	2	over range	
28-Aug-12	17.95	--	18.4	7.15	205	5.20	10	over range	
25-Oct-12	N/S	--							
20-Dec-12	18.90	--	15.0	7.03	163	3.80	11	0.00	
14-Mar-13	17.07	--	11.0	7.20	163	3.71	18	0.00	
20-Jun-13	15.57	--	17.4	7.40	257	6.70	14	0.00	
24-Sep-13	18.59	--	17.8	7.62	180	4.01	5	0.00	
18-Dec-13	19.83	--	13.8	8.01	119	3.82	2	0.00	
14-Feb-14	18.95	--	8.9	7.55	316	2.09	235	0.00	
11-Jun-14	16.83	--	14.4	6.96		8.27	241.2	0.00	
26-Aug-14	17.25	--	18.5	7.48	165	3.04	79	n/m	
13-Nov-14	19.07	--	17.5	7.50	205	3.35	85	0.00	
16-Dec-14	17.44	--	13.2	7.25	254	17.92	138	n/m	
10-Mar-15	16.56	--	10.7	7.18	215	8.06	-198.5	n/m	

Table 1 - Historic Groundwater Field Data Summary (to Current)

KEY

Temperature recorded in C
 Conductivity measured in uS
 Dissolved Oxygen measured in mg/l
 Eh measured in Mv
 Ozone measured in mg/l
 Duplicate sample analysis is in parentheses.

DW-1	PARAMETER								
	Depth to water (ft)	Groundwater Elevation (ft)	Temp °C	pH	Cond. uS	D.O. mg/L	Eh mV	Ozone mg/L	MSRO ug/L
24-Mar-05			7.7	7.51	543	5.8	95	n/c	
27-Jun-05			20.6	6.53	105	1.94	125	0	
20-Sep-05	9.50		25.5	6.27	110	1.87	-35	0	
13-Dec-05	6.95		12.0	7.41	43	11.21	45	0	
15-Mar-06	10.36		8.6	7.78	97	7.41	102	0.1	
22-Jun-06	8.90		18.5	7.46	66	7.00	88	-0.08	
26-Sep-06	8.36		22.4	7.03	65	3.74	34	0.05	
19-Dec-06	10.35		12.5	7.31	94	4.25	-41	-0.01	
27-Mar-07	8.70		8.5	7.16	209	5.2	-60	-0.08	
26-Jun-07	8.98		21.3	7.13	67	4.80	-25	0.10	
20-Sep-07	9.58		23.0	7.08	63	6.70	-46	0.07	
20-Dec-07	7.65		8.5	7.02	72	5.28	25	NA	
27-Mar-08	7.90		8.1	7.21	82	4.85	-123	ND	
19-Jun-08	4.30		22.4	7.13	56	6.55	-10	0.08	
25-Sep-08	DRY		n/a	n/a	n/a	n/a	n/a	n/a	
18-Dec-08	DRY	soil sample coll.	n/a	n/a	n/a	n/a	n/a	n/a	
12-Mar-09	10.48	soil sample coll.	13.0	7.30	65	6.55	-8	ND	
17-Jun-09	DRY	soil sample coll.	n/a	n/a	n/a	n/a	n/a	n/a	
22-Sep-09	DRY	soil sample coll.	n/a	n/a	n/a	n/a	n/a	n/a	
30-Dec-09	DRY	soil sample coll.	n/a	n/a	n/a	n/a	n/a	n/a	
02-Feb-10	DRY	soil sample coll.	n/a	n/a	n/a	n/a	n/a	n/a	
24-Mar-10	DRY	soil sample coll.	n/a	n/a	n/a	n/a	n/a	n/a	
22-Jun-10	DRY	soil sample coll.	n/a	n/a	n/a	n/a	n/a	n/a	
22-Sep-10	DRY	soil sample coll.	n/a	n/a	n/a	n/a	n/a	n/a	
15-Dec-10	DRY	soil sample coll.	n/a	n/a	n/a	n/a	n/a	n/a	
24-Mar-11	9.82		8.5	7.10	25	10.50	80	0.00	
16-Jun-11	8.58		22.0	7.09	67	5.60	45	0.00	
15-Sep-11	DRY	soil sample coll.							
16-Dec-11	DRY	soil sample coll.							
14-Mar-12	DRY	soil sample coll.							
20-Jun-12	DRY	soil sample coll.							
28-Aug-12	N/S								
25-Oct-12	DRY	soil sample coll.							
14-Mar-13	DRY	soil sample coll.							
20-Jun-13	DRY	soil sample coll.							
24-Sep-13	DRY	soil sample coll.							
18-Dec-13	DRY	soil sample coll.							
25-Feb-14	DRY	soil sample coll.							
11-Jun-14	DRY	soil sample coll.							
26-Aug-14	DRY	soil sample coll.							
12-Nov-14	DRY	soil sample coll.							
16-Dec-14	DRY	soil sample coll.							
10-Mar-15	9.71		4.4	6.34	442	146.20	-215.6	n/m	

Table 1 - Historic Groundwater Field Data Summary (to Current)

KEY

Temperature recorded in C
 Conductivity measured in uS
 Dissolved Oxygen measured in mg/l
 Eh measured in Mv
 Ozone measured in mg/l
 Duplicate sample analysis is in parentheses.

VP-A	PARAMETER								
	Depth to water (ft)	Groundwater Elevation (ft)	Temp °C	pH	Cond. uS	D.O. mg/L	Eh mV	Ozone	MSRO ug/L
30-Dec-09		Not Accessible							99
02-Feb-10	18.13		14.1	7.11	350	9.15	224	0.00	
24-Mar-10	15.18		13.5	7.11	271	9.66	144	over range	
22-Jun-10	16.50		15.5	7.13	188	10.23	-60	over range	
22-Sep-10	20.05		17.5	7.11	376	3.95	-45	n/m	
15-Dec-10	20.68		16.0	7.06	292	3.55	-35	0	
24-Mar-11	19.20		13.5	7.10	255	6.10	-20	0	
16-Jun-11	18.40		13.8	7.57	318	8.30	-12	0	
15-Sep-11	17.30		18.0	7.07	90	7.30	28	0	
16-Dec-11	17.79		16.6	7.06	233	5.88	15	0	
14-Mar-12	19.06		14.8	7.03	254	4.01	20	0	
20-Jun-12	18.90		15.5	7.04	294	3.55	18	0	
28-Aug-12	19.84		16.8	7.16	367	6.20	8	0	
25-Oct-12	N/S								
20-Dec-12	20.78		16.0	7.02	255	1.80	-22	0.00	
14-Mar-13	17.07		11.0	7.20	163	3.71	18	0.00	
20-Jun-13	17.63		14.1	7.28	250	7.05	-1	0.00	
24-Sep-13	20.49		16.9	7.70	156	5.01	-10	0.00	100
18-Dec-13	21.69		14.7	7.05	277	4.92	-5	0.00	110
25-Feb-14	20.84		12.7	7.78	326	4.20	247	0.00	
11-Jun-14	18.71		12.9	8.88		11.39	168.4	0.00	
26-Aug-14	19.16		17.0	8.59	477	5.33	46	n/m	
13-Nov-14	18.50		17.8	7.85	485	3.88	125	0.00	
15-Dec-14	19.32		15.7	6.77	337	15.20	101	n/m	
10-Mar-15	18.45		13.9	8.26	323	107.00	-178	n/m	

Table 1 - Historic Groundwater Field Data Summary (to Current)

KEY

Temperature recorded in C
 Conductivity measured in uS
 Dissolved Oxygen measured in mg/l
 Eh measured in Mv
 Ozone measured in mg/l
 Duplicate sample analysis is in parentheses.

VP-B	PARAMETER								
	Depth to water (ft)	Groundwater Elevation (ft)	Temp °C	pH	Cond. uS	D.O. mg/L	Eh mV	Ozone	MSRO ug/L
30-Dec-09	16.28		15.1	7.53	211	1.79	170	0.03	58
02-Feb-10	16.55		14.1	7.04	340	9.01	190	over range	66
24-Mar-10	13.68		13.8	7.09	229	7.14	137	over range	120
22-Jun-10	15.08		15.5	7.13	245	9.40	12	over range	
22-Sep-10	18.61		17.0	7.09	370	4.00	16	n/m	
15-Dec-10	19.20		14.9	7.03	370	2.97	20	0	
24-Mar-11	17.75		13.8	7.57	196	5.95	-15	0	
16-Jun-11	16.92		14.0	7.02	161	8.39	-19	over range	
15-Sep-11	15.81		17.5	7.30	96	7.40	-27	0	
16-Dec-11	16.30		16.3	7.56	171	4.99	-30	over range	
14-Mar-12	17.57		14.5	7.05	198	3.91	-15	over range	
20-Jun-12	17.40		15.8	7.03	150	3.88	-10	over range	
28-Aug-12	18.39		17.0	7.18	164	5.88	-25	over range	
25-Oct-12	N/S								
20-Dec-12	19.30		16.0	7.03	183	2.55	-30	0.00	
14-Mar-13	17.53		13.2	7.51	503	2.80	-22	0.00	
20-Jun-13	16.16		13.7	7.64	157	6.72	-10	0.00	
24-Sep-13	19.00		16.8	7.77	170	4.80	-2	0.00	100
18-Dec-13	20.21		14.6	7.19	191	4.01	-1	0.00	93
25-Feb-14	19.35		14.0	7.87	189	7.41	239	0.00	
11-Jun-14	17.21		12.9	7.93		9.80	219.9	0.00	
26-Aug-14	17.67		16.2	8.22	332	6.52	94	n/m	
13-Nov-14	19.35		17.5	7.91	395	4.01	105	0.00	
15-Dec-14	17.81		15.9	6.60	312	11.48	109	n/m	
10-Mar-15	16.98		14.0	6.74	250	100.30	-175	n/m	
GT-6	PARAMETER								
	Depth to Water (ft)	Groundwater Elevation (ft)	Temp °C	pH	Cond. uS	D.O. mg/L	Eh mV	Ozone	MSRO ug/L
26-Aug-14	17.35	36.91	Meters did not stabilize. Data not considered reliable.						3600
12-Nov-14	19.74	34.52	16.9	7.33	603	2.20	130	n/m	1300
15-Dec-14	18.16	36.10	15.4	6.24	708	4.61	33.8	n/m	3600
10-Mar-15	17.32	36.94	12.9	7.04	342	3.70	-234.1	n/m	240 (350)
GT-7	PARAMETER								
	Depth to Water (ft)	Groundwater Elevation (ft)	Temp °C	pH	Cond. uS	D.O. mg/L	Eh mV	Ozone	MSRO ug/L
26-Aug-14	17.41	36.37	Meter did not stabilize. Data not considered reliable.						
12-Nov-14	19.40	34.38	17.0	7.58	547	3.20	162	n/m	
15-Dec-14	17.83	35.95	15.3	6.29	400	2.70	107	n/m	
10-Mar-15	17.02	36.76	12.2	6.46	304	4.36	-212.6	n/m	

Table 2
Groundwater Monitoring Results Summary (to Current)
Safety-Kleen Systems, Inc. - Corrective Action Program
N. Amityville, New York Facility
(Recorded At/Above the T.O.G.S. 1.1.1 Standards or Project-Specific Reporting Limits)
(See Laboratory Report for all Compounds Detected Above the Method Detection Limit)

Monitor-ing Location	Sample Date	Detected Compound	Acetone	Benzene	Toluene	Ethyl- benzene	Xylenes	PCE	Chloro- benzene	1,2- DCB	1,3- DCB	1,4- DCB	1,2- DCE	1,1,1- TCA	trans -1,2- DCE	Mineral Spirit RO	Total VOCs
		Units	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)
		TOGS-STD->	50	1	5	5	5	5	5	3	3	3	5	5	5	50	n/a
GT-1	3/14/1994					51	410		170		21	81				NS	733
	2/9/1996					5	49		19	13		12				444	98
	5/28/1996						16		24	10		13				186	63
	5/28/1996	Duplicate					16		23			13	11			244	63
	8/22/1996					8	76		41	20	5	23				588	173
	12/2/1996						42		18	10		10				NS	80
	2/27/1997						34		16	7		8				113	65
	2/27/1997	Split				1	29		17	9	3	13				170	71.8
	5/28/1997					6	52		22	12		11					103
	5/28/1997	Duplicate				6	52		22	12		11					103
	5/28/1997	Split				6	47		20	9		10				51	92
	9/9/1997					22	167		73	33	9	38				308	342.6
	9/9/1997	Duplicate				19	150		65	29	9	33				277	303.6
	9/9/1997	Split				17	130		62	33	9	38				5,000	289
	12/18/1997					9	62		26	16	4	18				43	135
	12/18/1997	Duplicate				8	61		26	14	4	16				33	129
	6/25/1998						23		16	17		16				51	71.7
	6/25/1998	Duplicate					23		16	17		15				55	70
	6/25/1998	Split					18			19		16					53
	10/13/1998					9	70		37	15		21				96	152.9
	10/13/1998	Duplicate				7	56		25	14		17				113	118.5
	12/4/1998					9	51		27	16		17				128	119.1
	12/4/1998	Duplicate				9	48		26	16		16				115	114.3
	6/16/1999					10	54		29	31	8	37				820	167.5
	6/16/1999	Duplicate				6	37		18	27	8	35				335	129.2
	9/30/1999					14	71		45	31	7	34					203.6
	9/30/1999	Duplicate				16	80		49	37	9	41					232.4
	12/22/1999					9	43		23	22	6	26				2,480	128.5
	3/15/2000																
	3/15/2000	Split				1	9		5	4	1	4	0			250	24.3
	6/28/2000					7	36		19	13		13				92	0.0944
	6/28/2000	Split			0	5	37		19	17	4	19	2			38	0.1083
	9/20/2000						25		11	13		15				118	0.0639
	9/20/2000	Split					10		5	6	2	10	1			23	34
	12/20/2000						8		6	7		8				87	28.2
	12/20/2000	Split														4	
	3/15/2001						8		7	6		6					0.0267
	3/15/2001	Split					17		8	9		8				3	0.042
	8/23/2001	m. mal.				5	20		8	13		12				186	57.5

Monitor-ing Location	Sample Date	Detected Compound	Acetone	Benzene	Toluene	Ethyl- benzene	Xylenes	PCE	Chloro- benzene	1,2- DCB	1,3- DCB	1,4- DCB	1,2- DCE	1,1,1- TCA	trans -1,2- DCE	Mineral Spirit RO	Total VOCs
		Units	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)
		TOGS-STD->	50	1	5	5	5	5	5	3	3	3	5	5	5	50	n/a
GT-1	8/23/2001	Split				5	22		8	18			1			450	53.8
	11/6/2001					7	35		15	25		24				100	106
	11/6/2001	Split				5	27		11	20		18				110	81
	2/5/2002						120			98		92				120,000	310
	2/5/2002	Split					170			160		160				140,000	490
	4/16/2002						53			68		57				360,000	178
	4/17/2002	Split					63			77		66				490,000	206
	10/11/2002					5	17			20	4	18				130	64
	10/11/2002	Duplicate				5	19		5	22	4	21				880	76
	1/23/2003						10			15		13				340	38
	1/23/2003	Duplicate					8			14		12				800	34
	4/22/2003						11			20	4	18				310	53
	4/22/2003	Duplicate					6			19	3	17				240	45
	7/22/2003						15			27	5	22					69
	7/22/2003	Duplicate					12			21	4	18					55
	12/9/2003					5	22		13	33	9	40				560	122
	12/9/2003	Duplicate				5	22		14	34	9	42				710	126
	3/25/2004 *						19		8	44	9	41				490	121
	3/25/2004 *	Duplicate					18		9	42	9	43					121
	6/29/2004									8		9				510	17
	6/29/2004	Duplicate					5			13		14					32
	10/4/2004								6	5		8					19
	10/4/2004	Duplicate					5		10	10	3	14					42
	12/28/2004						6		11	11	3	16				320	47
	3/24/2005											6				440	6
	7/6/2005											4				56	9
	7/6/2005	Duplicate															
	9/20/2005								4	9	3	13				180	29
	12/13/2005						8		10	17	6	32				1,400	73
	3/15/2006						6		9	26	5	26				2,600	72
	6/22/2006						6		9	24	9	29				3,300	77
	9/26/2006									15	3	15				3,100	33
	12/19/2006						7			23	4	20				2,500	54
	12/19/2006	Duplicate					5			17	3	16				2,700	41
	3/27/2007									12		12				1,600	24
	3/27/2007	Duplicate								13		13				1,400	26
	6/26/2007									10		12				880	22
	6/26/2007	Duplicate								8		9				1,400	17
	9/20/2007						5			18	5	20				2,400	48
	9/20/2007	Duplicate					7			24	5	24				3,000	60
	10/16/2007											4				200	4
	10/18/2007						8		6	24	7	31				2,800	76
	12/20/2007									7		7				720	14
	12/20/2007	Duplicate								7		7				550	14
	3/27/2008									6		8				480	14
	3/27/2008	Duplicate								6		9				1,300	15

Monitor-ing Location	Sample Date	Detected Compound	Acetone	Benzene	Toluene	Ethyl- benzene	Xylenes	PCE	Chloro- benzene	1,2- DCB	1,3- DCB	1,4- DCB	1,2- DCE	1,1,1- TCA	trans -1,2- DCE	Mineral Spirit RO	Total VOCs
		Units	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)
		TOGS-STD->	50	1	5	5	5	5	5	3	3	3	5	5	5	50	n/a
GT-1	6/19/2008									7		10				1,900	17
	6/19/2008	Duplicate								8		10				1,900	18
	9/25/2008									18	4	20				3,100	42
	9/25/2008	Duplicate								18	4	21				3,000	43
	12/18/2008									9		11				1,300	19.7
	12/18/2008	Duplicate								9		11				1300/4800	19.6
	3/12/2009				PCE-5.7					6		10				500	22
	3/12/2009				PCE-6.3					6		9				710	21.3
		Duplicate	Note: 5.7 and 6.3 ug/L of tetrachloroethene was also detected in sample and X-2, respectively. This parameter total is included in the Total VOCs.														
	6/17/2009															50	
	6/17/2009	Duplicate														73	
	9/22/2009									4		6				530	9.7
	9/22/2009	Duplicate								3		6				680	8.9
	12/30/2009	Sample														1,300	
		Duplicate (X-1)														1,300	
	2/2/2010	Sample														1,000	
		Duplicate (X-1)														1,100	
	3/24/2010	Sample										3.5 & 4.1				6,400	3.5 & 4.1
		Duplicate (X-1)										3.5 & 4.2				4,500	3.5 & 4.2
	6/22/2010	Sample														3,000	
		Duplicate (X-1)														2,400	
	9/22/2010	Sample								4.9		10.0				18,000	14.9
		Duplicate (X-1)								4.9		11.0				16,000	15.9
	12/15/2010	Sample								9.1	5.2	21.0				12,000	35.3
		Duplicate (X-1)								9.1	5.1	20.0				39,000	34.2
	3/24/2011	Sample								6.8	4.0	15.0				18,000	25.8
		Duplicate (X-1)								6.9	4.1	15.0				24,000	26
	6/16/2011	Sample										6.5				8,500	6.5
		Duplicate (X-1)										7.2				11,000	7.2
	9/15/2011	Sample										5.5				12,000	5.5
		Duplicate (X-1)															
	12/16/2011	Sample										5.6				15,000	5.6
		Duplicate (X-1)										4.0				7,400	4.0
	3/14/2012	Sample										6.4				16,000	6.4
												6.1				14,000	6.1
	6/20/2012		Info Only H.T.E.									4.0				15,000	4.0
		Duplicate (X-1)	Info Only H.T.E.									4.0				12,000	4.0
	8/28/2012											4.5				9,200	4.5
		Duplicate (X-1)										4.8				10,000	4.8
	10/25/2012									4.7	4.2	13.0				23,000	21.9
		Duplicate								4.8	4.5	13.0				21,000	22.3
	12/20/2012									4.0	3.6	11.0				24,000	18.6
		Duplicate								3.9	3.5	11.0				32,000	18.4
	3/14/2013											3.6				22,000	3.6
		Duplicate										3.8				21,000	3.8
	6/20/2013															16,000	

Table 2

Monitor-ing Location	Sample Date	Detected Compound	Acetone	Benzene	Toluene	Ethyl- benzene	Xylenes	PCE	Chloro- benzene	1,2- DCB	1,3- DCB	1,4- DCB	1,2- DCE	1,1,1- TCA	trans -1,2- DCE	Mineral Spirit RO	Total VOCs
		Units	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)
		TOGS-STD->	50	1	5	5	5	5	5	3	3	3	5	5	5	50	n/a
GT-1		Duplicate														15,000	
	9/24/2013											4.0				41,000	4.0
		Duplicate										4.1				42,000	4.1
	12/18/2013															5,700	
		Duplicate														5,100	
	2/25/2014															6,100	
		Duplicate														6,100	
	6/11/2014															1,400	
		Duplicate														1,400	
	8/26/2014															520	
		Duplicate														1,500	
	11/13/2014															120	
GT-2		Duplicate															
	12/15/2014																
	3/10/2015																
	3/14/1994																
	2/9/1996																
	5/28/1996																
	8/22/1996																
	12/2/1996																
	2/27/1997																
	5/28/1997																
	9/9/1997																
	12/18/1997																
	6/25/1998																
	10/13/1998																
	12/4/1998																
	6/16/1999																
	9/30/1999																
	12/22/1999																
	3/15/2000																
	6/28/2000																
	9/20/2000																
	12/20/2000																
	3/15/2001																
	8/23/2001	m.malf															
	11/6/2001																
	2/5/2002																
	4/16/2002																
	10/11/2002																
	1/23/2003																
	4/22/2003			NS	NS	NS	NS		NS	NS	NS	NS	NS	NS	NS	NS	NS
	7/22/2003																
	12/9/2003																
	4/22/2004																
	6/29/2004																

Monitor-ing Location	Sample Date	Detected Compound	Acetone	Benzene	Toluene	Ethyl- benzene	Xylenes	PCE	Chloro- benzene	1,2- DCB	1,3- DCB	1,4- DCB	1,2- DCE	1,1,1- TCA	trans -1,2- DCE	Mineral Spirit RO	Total VOCs
		Units	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)
		TOGS-STD->	50	1	5	5	5	5	5	3	3	3	5	5	5	50	n/a
GT-2	10/4/2004																
	12/28/2004																7
	3/24/2005																
	3/24/2005	Duplicate															
	7/6/2005																
	9/20/2005																
	12/13/2005																
	3/15/2006																
	6/22/2006																
	9/26/2006																
	12/19/2006																
	3/27/2007																
	6/26/2007																
	9/20/2007																
	12/20/2007																
	3/27/2008																
	6/19/2008																
	9/25/2008																
	12/18/2008																
	3/12/2009																
	6/17/2009																
	9/22/2009																
	12/30/2009																
	2/2/2010															67	
	3/24/2010																
	6/22/2010																
	9/22/2010																
	12/15/2010																
	3/24/2011																
	6/16/2011																
	9/15/2011																
	12/16/2011																
	3/14/2012																
	6/20/2012	Info Only H.T.E.															
	8/28/2012																
	10/25/2012																
	12/20/2012																
	3/14/2013																
	6/20/2013																
	9/24/2013																
	12/18/2013		84														84
	2/25/2014																
	6/11/2014																
	8/26/2014																
	11/12/2014																

Monitor-ing Location	Sample Date	Detected Compound	Acetone	Benzene	Toluene	Ethyl- benzene	Xylenes	PCE	Chloro- benzene	1,2- DCB	1,3- DCB	1,4- DCB	1,2- DCE	1,1,1- TCA	trans -1,2- DCE	Mineral Spirit RO	Total VOCs
		Units	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)
		TOGS-STD->	50	1	5	5	5	5	5	3	3	3	5	5	5	50	n/a
GT- 2 GT-3	12/16/2014																
	3/10/2015																
	3/14/1994															NS	
	2/9/1996																
	5/28/1996																
	8/22/1996																
	8/22/1996	Split															
	12/2/1996																
	12/2/1996	Split															
	2/27/1997																
	5/28/1997																
	9/9/1997																
	12/18/1997																
	6/25/1998																
	10/13/1998																
	10/13/1998	Split															
	12/4/1998																
	6/16/1999																
	6/16/1999	Split														1	
	9/30/1999																
	9/30/1999	Split															
	12/22/1999																
	3/15/2000																
	6/28/2000																
	9/20/2000																
	12/20/2000																
	3/15/2001																
	8/23/2001	m. malf.															
	11/6/2001																
	2/5/2002																
	4/16/2002																
	10/11/2002																
	1/23/2003															170	
	2/27/2003																
	2/27/2003	Duplicate															
	4/22/2003																
	7/22/2003																
	12/9/2003																
	4/22/2004																
	6/29/2004																
	10/4/2004																
	12/28/2004																
	3/24/2005																
	7/6/2005																
	12/13/2005																
	3/15/2006																

Monitor-ing Location	Sample Date	Detected Compound	Acetone	Benzene	Toluene	Ethyl- benzene	Xylenes	PCE	Chloro- benzene	1,2- DCB	1,3- DCB	1,4- DCB	1,2- DCE	1,1,1- TCA	trans -1,2- DCE	Mineral Spirit RO	Total VOCs
		Units	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)
		TOGS-STD->	50	1	5	5	5	5	5	3	3	3	5	5	5	50	n/a
GT-3	6/22/2006																
	9/26/2006																
	12/19/2006									8							8
	3/27/2007																
	6/26/2007																
	9/20/2007																
	12/20/2007																
	3/27/2008																
	6/19/2008																
	9/25/2008																
	12/18/2008																
	3/12/2009																
	6/17/2009																
	9/22/2009																
	12/30/2009																
	2/2/2010																
	3/24/2010																
	6/22/2010																
	9/22/2010																
	12/15/2010																
	3/24/2011																
	6/16/2011																
	9/15/2011																
	12/16/2011																
	3/14/2012																
	6/20/2012	Info Only H.T.E.															
	8/28/2012																
	10/25/2012																
	12/20/2012																
	3/14/2013																
	6/20/2013																
	9/24/2013															120	
	12/18/2013															81	
	2/25/2014																
	6/11/2014																
	8/26/2014																
	11/12/2014																
	12/16/2014																
	3/10/2015																
GT-4	3/14/1994																
	2/9/1996																
	5/28/1996																
	8/22/1996																
	12/2/1996																
	2/27/1997																
	5/28/1997																

Monitor-ing Location	Sample Date	Detected Compound	Acetone	Benzene	Toluene	Ethyl- benzene	Xylenes	PCE	Chloro- benzene	1,2- DCB	1,3- DCB	1,4- DCB	1,2- DCE	1,1,1- TCA	trans -1,2- DCE	Mineral Spirit RO	Total VOCs
		Units	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)
		TOGS-STD->	50	1	5	5	5	5	5	3	3	3	5	5	5	50	n/a
GT-4	9/9/1997																
	12/18/1997																
	6/25/1998																
	10/13/1998																
	12/4/1998																
	6/16/1999																
	9/30/1999																
	12/22/1999																
	3/15/2000																
	6/28/2000																
	9/20/2000																
	12/20/2000																
	3/15/2001																
	8/23/2001	m malf.															
	11/6/2001																
	2/5/2002																
	4/16/2002																
	10/11/2002																
	1/23/2003																
	4/22/2003																
	7/22/2003																
	12/9/2003																
	4/22/2004																
	6/29/2004																
	10/4/2004																
	12/28/2004																
	3/24/2005																
	9/20/2005																
	12/13/2005																
	3/15/2006	N/S															
	6/22/2006	N/S															
	9/26/2006	N/S															
	12/19/2006	N/S															
	3/27/2007	N/S															
	6/26/2007	N/S															
	9/20/2007	N/S															
	12/20/2007	N/S															
	3/27/2008	N/S															
	6/19/2008	N/S															
	9/25/2008	N/S															
	12/18/2008	N/S															
	3/12/2009	N/S															
	6/17/2009	N/S															
	9/22/2009	N/S															
	12/30/2009	N/S															
	2/2/2010	N/S															

Monitor-ing Location	Sample Date	Detected Compound	Acetone	Benzene	Toluene	Ethyl- benzene	Xylenes	PCE	Chloro- benzene	1,2- DCB	1,3- DCB	1,4- DCB	1,2- DCE	1,1,1- TCA	trans -1,2- DCE	Mineral Spirit RO	Total VOCs
		Units	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)
		TOGS-STD->	50	1	5	5	5	5	5	3	3	3	5	5	5	50	n/a
GT-4	3/24/2010	N/S															
	6/22/2010	N/S															
	9/22/2010	N/S															
	12/15/2010	N/S															
	3/24/2011	N/S															
	6/16/2011	N/S															
	9/15/2011	N/S															
	12/16/2011	N/S															
	3/14/2012	N/S															
	6/20/2012	N/S	Info Only H.T.E.														
	8/28/2012	N/S															
	10/25/2012	N/S															
	12/20/2012	N/S															
	3/14/2013	N/S															
	6/20/2013	N/S															
	9/24/2013	N/S															
	12/18/2013	N/S															
	2/25/2014	N/S															
	6/11/2014	N/S															
	8/26/2014	N/S															
	11/12/2014	N/S															
	12/16/2014	N/S															
	3/10/2015	N/S															
GT-5	3/14/1994												27			NS	27
	2/9/1996																
	5/28/1996												18				18
	5/28/1996	Split											27				27
	8/22/1996												83				83
	8/22/1996	Duplicate											112				112
	12/2/1996																
	12/2/1996																
	2/27/1997												33		33		33
	2/27/1997	Duplicate											28		28		28
	5/28/1997												11		11		11
	9/9/1997												38		38		38
	12/18/1997												2				2
	6/25/1998																
	10/13/1998									8			5		5		13
	12/4/1998																
	6/16/1999												15				15
	9/30/1999					5			17	13			13				49
	12/22/1999																
	12/22/1999	Duplicate															
	3/15/2000												9				9
	3/15/2000	Duplicate											11				11
	6/28/2000									18							

Table 2

Monitor-ing Location	Sample Date	Detected Compound	Acetone	Benzene	Toluene	Ethyl- benzene	Xylenes	PCE	Chloro- benzene	1,2- DCB	1,3- DCB	1,4- DCB	1,2- DCE	1,1,1- TCA	trans -1,2- DCE	Mineral Spirit RO	Total VOCs
		Units	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)
		TOGS-STD->	50	1	5	5	5	5	5	3	3	3	5	5	5	50	n/a
GT-5	6/28/2000	Duplicate								16							
	9/20/2000								11	14							
	9/20/2000	Duplicate							7	10							17
	12/20/2000																
	12/20/2000	Duplicate															
	3/15/2001																
	3/15/2001	Duplicate															
	8/23/2001	m malf.															
	8/23/2001	Duplicate															
	11/6/2001																
	2/5/2002	DRY															
	4/16/2002	DRY															
	10/11/2002	DRY															
	1/23/2003																
	4/22/2003																
	7/22/2003																
	12/9/2003																
	3/25/2004																
	6/29/2004																
	10/4/2004																
	12/28/2004																
	3/24/2005																
	7/6/2005																
	9/20/2005																
	9/20/2005	Duplicate															
	12/13/2005																
	3/15/2006																
	3/15/2006	Duplicate															
	6/22/2006																
	9/26/2006																
	12/19/2006																
	3/27/2007																
	6/26/2007																
	9/20/2007																
	12/20/2007																
	3/27/2008																
	6/19/2008																
	9/25/2008																
	12/18/2008																
	3/12/2009																
	6/17/2009																
	9/22/2009																
	12/30/2009																
	2/2/2010																
	3/24/2010																
	6/22/2010																

Monitor-ing Location	Sample Date	Detected Compound	Acetone	Benzene	Toluene	Ethyl- benzene	Xylenes	PCE	Chloro- benzene	1,2- DCB	1,3- DCB	1,4- DCB	1,2- DCE	1,1,1- TCA	trans -1,2- DCE	Mineral Spirit RO	Total VOCs
		Units	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)
		TOGS-STD->	50	1	5	5	5	5	5	3	3	3	5	5	5	50	n/a
GT-5	9/22/2010																
	12/15/2010																
	3/24/2011																
	6/16/2011																
	9/15/2011																
	12/16/2011																
	3/14/2012																
	6/20/2012	Info Only H.T.E.															
	8/28/2012																
	10/25/2012																
	12/20/2012																
	3/14/2013																
	9/24/2013																
	9/24/2013	Duplicate															
	12/18/2013																
	2/25/2014																
	6/11/2014															140	
	8/26/2014															300	
	11/12/2014																
	12/15/2014																
	3/10/2015																
GT-6	8/26/2014															3,400	
	11/12/2013															1,300	
	12/15/2014											3.3				3,600	3.3
	3/10/2015															240	
	3/10/2015	Duplicate														350	
GT-7	8/26/2014																
	11/12/2014																
	12/15/2014																
	3/10/2015																
VE-1	3/30/2005											64				2,900	64
	7/6/2005						5			41	7	27				5,600	80
	9/20/2005	Dry															
	12/13/2005						18			97	72	71				24,000	258
	3/15/2006						19J1M			98J1M	83J1M	83J1M			6-cis 1,2 DC	39,000	289
	6/22/2006						9			57		61				17,000	127
	9/26/2006									18	8	26				8,600	52
	dup									21	5	20				3,900	46
	12/19/2006									37	12	45				27,000	94
	3/27/2007									21	9	31				34,000	61
	6/26/2007									27	13	40				30,000	80
	9/20/2007									6	4	12				9,500	22
	12/20/2007									9	7	19				33,000	35
	3/27/2008									9	7	18				430	78 ¹
	6/19/2008									6	5	12				21,000	23
	9/25/2008															23,000	

Monitor-ing Location	Sample Date	Detected Compound	Acetone	Benzene	Toluene	Ethyl- benzene	Xylenes	PCE	Chloro- benzene	1,2- DCB	1,3- DCB	1,4- DCB	1,2- DCE	1,1,1- TCA	trans -1,2- DCE	Mineral Spirit RO	Total VOCs
		Units	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)
		TOGS-STD->	50	1	5	5	5	5	5	3	3	3	5	5	5	50	n/a
VE-1	12/18/2008											7.2				15,000	20.2
	3/12/2009											3.9				8,000	3.9
			Note: 13 ppb of isopropylbenzene was also detected. This parameter total is included in the Total VOCs column.														
	6/17/2009											6.0				23,000	6
	9/22/2009															8,400	
	12/30/2009															23,000	
	2/2/2010															43,000	
	3/24/2010															5,400	
	6/22/2010															8,100	
	9/22/2010	Dry															
	12/15/2010	Dry															
	3/24/2011															8,300	
	6/16/2011															13,000	
	9/15/2011															680	
	12/16/2011															10,000	
	3/14/2012															2,600	
	6/20/2012	Info Only H.T.E.														2,400	
	8/28/2012																
	10/25/2012	VE-1R														20,000	
	12/20/2012															12,000	
	3/14/2013															9,900	
	6/20/2013															22,000	
	9/24/2013															42,000	
	12/18/2013															44,000	
	2/25/2014															14,000	
	6/11/2014															18,000	
	8/26/2014															36,000	
	11/13/2014															110	
	12/16/2014																
	3/10/2015	N/S															
VE-5	12/28/2004																
	3/24/2005																
	7/6/2005																
	9/20/2005																
	12/13/2005																
	3/15/2006																
	6/22/2006																
	9/26/2006																
	12/19/2006																
	3/27/2007																
	6/26/2007																
	9/20/2007																
	12/20/2007																
	3/27/2008															60	
	6/19/2008																
	9/25/2008																

Monitor-ing Location	Sample Date	Detected Compound	Acetone	Benzene	Toluene	Ethyl- benzene	Xylenes	PCE	Chloro- benzene	1,2- DCB	1,3- DCB	1,4- DCB	1,2- DCE	1,1,1- TCA	trans -1,2- DCE	Mineral Spirit RO	Total VOCs
		Units	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)
		TOGS-STD->	50	1	5	5	5	5	5	3	3	3	5	5	5	50	n/a
VE-5	12/18/2008																
	3/12/2009																
	6/17/2009																
	9/22/2009																
	12/30/2009															190	
	2/2/2010															390	
	3/24/2010																
	6/22/2010																
	9/22/2010																
	12/15/2010																
	3/24/2011																
	6/16/2011																
	9/15/2011																
	12/16/2011																
	3/14/2012																
	6/20/2012	Info Only H.T.E.															
	8/28/2012																
	10/25/2012																
	3/14/2013																
	6/20/2013																
	9/24/2013																
	12/18/2013																
	2/25/2014																
	6/11/2014																
	8/26/2014																
	11/13/2014																
	12/16/2014																
	3/10/2015																
VP-A	12/30/2009	Not Accessible															
	2/2/2010															99	
	3/24/2010																
	6/22/2010																
	9/22/2010																
	12/15/2010																
	3/24/2011																
	6/16/2011																
	9/15/2011																
	12/16/2011																
	3/14/2012																
	6/20/2012	Info Only H.T.E.															
	8/28/2012																
	10/25/2012																
	3/14/2013																
	6/20/2013																
	9/24/2013															100	
	12/18/2013															110	

Monitor-ing Location	Sample Date	Detected Compound	Acetone	Benzene	Toluene	Ethyl- benzene	Xylenes	PCE	Chloro- benzene	1,2- DCB	1,3- DCB	1,4- DCB	1,2- DCE	1,1,1- TCA	trans -1,2- DCE	Mineral Spirit RO	Total VOCs
		Units	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)
		TOGS-STD->	50	1	5	5	5	5	5	3	3	3	5	5	5	50	n/a
VP-A	2/25/2014																
	6/11/2014																
	8/26/2014																
	11/13/2014																
	12/16/2014																
	3/10/2015																
VP-B	12/30/2009															58	
	2/2/2010															66	
	3/24/2010		130 & 110													120	130 & 110
	6/22/2010																
	9/22/2010																
	12/15/2010																
	3/24/2011																
	6/16/2011																
	9/15/2011																
	12/16/2011																
	3/14/2012																
	6/20/2012	Info Only H.T.E.															
	8/28/2012																
	10/25/2012																
	3/14/2013																
	6/20/2013																
	9/24/2013															100	
	12/18/2013															93	
	2/25/2014																
	6/11/2014																
	8/26/2014																
	11/13/2014																
	12/16/2014																
	3/10/2015																
DW-1 SOIL	7/22/2003																
	12/9/2003																
	3/25/2004																
	6/29/2004																
	10/4/2004																
	12/28/2004																
	3/24/2005																
	7/6/2005																
	9/20/2005															370	
	12/13/2005																
	12/13/2005	Duplicate															
	3/15/2006																
	6/22/2006																
	9/26/2006																
	12/19/2006																
	3/27/2007																

Monitor-ing Location	Sample Date	Detected Compound	Acetone	Benzene	Toluene	Ethyl- benzene	Xylenes	PCE	Chloro- benzene	1,2- DCB	1,3- DCB	1,4- DCB	1,2- DCE	1,1,1- TCA	trans -1,2- DCE	Mineral Spirit RO	Total VOCs
		Units	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)
		TOGS-STD->	50	1	5	5	5	5	5	3	3	3	5	5	5	50	n/a
DW-1 SOIL	6/26/2007																
	9/20/2007																
	12/20/2007																
	3/27/2008																
	6/19/2008																
	9/25/2008			dry - N/S			DRY										
	12/18/2008			Dry - Soil sample and duplicate collected. ND for all parameters													
	3/12/2009																0
	6/17/2009			Dry - Soil sample & duplicate collected. ND for all parameters													
	9/22/2009			Dry - Soil sample & duplicate collected. ND for all parameters													
	12/30/2009	Sample															
		Duplicate															
	2/2/2010	Sample															
		Duplicate															
	3/24/2010	Sample															
		Duplicate															
	6/22/2010	Sample															
		Duplicate															
	9/22/2010	Sample															
		Duplicate															
	12/15/2010	Sample															
		Duplicate															
	9/15/2011	Sample															
		Duplicate															
	12/16/2011	Sample															
	3/14/2012	Sample															
		Duplicate															
	6/20/2012	Sample															
		Duplicate															
	8/28/2012																
	10/25/2012															14,000	
	12/20/2012	Sample															
		Duplicate	Methylene Chloride: 59			STD: 50											
	3/21/2013	Sample														23,000	
		Duplicate														19,000	
	6/20/2013	Sample														9,600	
		Duplicate														13,000	
	9/24/2013	Sample															
		Duplicate															
	12/18/2013	Sample														20,000	
		Duplicate														10,000	
	2/25/2014	Sample															
		Duplicate															
	6/11/2014	Sample															
		Duplicate															
	8/26/2014	Sample														16,000	

Monitor-ing Location	Sample Date	Detected Compound	Acetone	Benzene	Toluene	Ethyl- benzene	Xylenes	PCE	Chloro- benzene	1,2- DCB	1,3- DCB	1,4- DCB	1,2- DCE	1,1,1- TCA	trans -1,2- DCE	Mineral Spirit RO	Total VOCs
		Units	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)	(ug/l)
		TOGS-STD->	50	1	5	5	5	5	5	3	3	3	5	5	5	50	n/a
DW-1 SOIL		Duplicate														12,000	
	11/13/2014	Sample															
		Duplicate															
	12/16/2014	Sample															
		Duplicate															
DW-1 WATER	12/30/2009	No standing water															
	2/2/2010	No standing water															
	3/24/2010	sampled															
	6/22/2010	No standing water															
	9/22/2010	No standing water															
	12/15/2010	No standing water															
	3/24/2011	sampled															
	6/16/2011	sampled															
	9/15/2011	No standing water															
	12/16/2011	No standing water															
	3/14/2012	No standing water															
	6/20/2012	No standing water															
	8/28/2012	No standing water															
	10/25/2012	No standing water															
	12/20/2012	No standing water															
	3/21/2013	No standing water															
	6/20/2013	No standing water															
	9/24/2013	No standing water															
	12/18/2013	No standing water															
	2/25/2014	No standing water															
	6/11/2014	No standing water															
	8/26/2014	No standing water															
	11/13/2014	No standing water															
	12/16/2014	No standing water															
	3/10/2015	Sample															
	3/10/2015	Duplicate															

Notes

BDL = Not detected above the method detection limit

ND = Not Detected (reported in micrograms per liter (ug/l))

NS = Not Sampled

NA = Not Applicable

TOC = Top of Casing (measured in feet above MSL)

DO = Dissolved Oxygen (reported in milligrams per liter (mg/l))

J1M = Lab estimated concentration

Number that is in **BOLD** exceeds the New York State Class GA Groundwater Standards

GW Standards for Class GA groundwater (NYSDEC TOGS 1.1.1, 10/22/93, Rev. 6/98)

Notes:

1. Tetrachloroethane was detected at a concentration of 5.7 and 6.3 ug/L in sample GT-1 and X-2, respectively.

Target Compound Abbreviations

1,2-DCB = 1,2-Dichlorobenzene

1,3-DCB = 1,3-Dichlorobenzene

1,4-DCB = 1,4-Dichlorobenzene

1,2-DCE = 1,2-Dichloroethene

1,1,1-TCA = 1,1,1-Trichloroethane

Trans-1,2-DCE = Trans-1,2-Dichloroethene

Table 3
Groundwater Natural Attenuation Parameters Summary
Safety-Kleen Systems, Inc. - Corrective Action Program
N. Amityville, New York Facility

Monitoring Location	Sample Date	Compound	Dissolved Oxygen	Dissolved Iron	Dissolved Manganese	Nitrate / Nitrite	Nitrate (NO3)	Nitrite (NO2)	Ammonia (NH3+NH4)	Sulfate (SO4)	Total Organic Carbon	Carbon Dioxide	Alkalinity	Bicarbonate (HCO3)	Hydrogen Sulfide	Methane	Phosphate (PO4)
		Units		(µg/l)	(µg/l)	(mg/l)	(mg/l)	(mg/l)	(mg/l)	(mg/l)	(mg/l)	(mg/l)	(mg/l)	(mg/l)	(mg/l)	(mg/l)	(mg/l)
GT-1	8/26/2014		6.01			1.3	1.3	--	0.35	15.3	9.8		127			0.27	3.1
	11/13/2014		1.08		41.6	5.3	4.1	1.2	8.3	1200	3.1	6.5 HF	109	109		0.072	9.6
	11/13/2014	Duplicate			39.2	5.4	4.4	1.0	7.4	1190	0.92	8.0 HF	112	112		0.094	102
	12/15/2014		2.06		41.9	3.4	3.0	0.44	7.1	196	0.73 J		87.3	87.3		0.14	19.6
	3/10/2015				52.3	25.5	15.4	10.1 J	1.9	262	0.61 J	32.8 HF	124	124		2.3	29.5
GT-2	8/26/2014				65.4	5.7	4.7	1.0	1.90	99.1	3.7	136 HF	114	114			3.5
	11/12/2014			2540	236	5.6	5.6		0.10	65.2	2.1	31.5 HF	80.5	80.5			13.2
	12/16/2014				8.0 J	6.1	6.1			87.6	2.2	53.7 HF	88.1	88.1		0.0027 J	4.0
	3/10/2015					8.73	8.73			88.8	1.9	68.9 HF	91.7	91.7			0.5
GT-3	8/26/2014				49.3	1.4	1.4		0.34	11.4	1.2		56.2	49.6			0.86
	11/12/2014				81.0	3.3	3.3			18.6	1.2		70.6	58.0			5.2
	12/16/2014				66.4	2.4	2.4			14.9	1.3		46.4	46.4			0.6
	3/10/2015			231	6.2 J	1.68	1.06	0.61 J	0.11	12.2	1.6		38.7	38.7			0.25
GT-5	8/26/2014				75.0	0.56	0.56		1.9	17.9		1.4	70.6	51.3			0.44
	11/12/2014				1090	5.9	5.2	0.67	6.2	134	1.4	13.4 HF	74.9	74.9			16.4
	12/15/2014				404	3.8	3.7	0.14	0.33	34.3	0.85 J		49.3	49.3		0.0037 J	2.3
	3/10/2015				158	2.92	2.92			26.5	0.49 J	16.8 HF	43.2	43.2			0.68
GT-6	8/26/2014		3.88		434	0.45	0.45	--		14.4	4.8	47.4 HF	54.8	54.8		0.74	1.8
	11/12/2014		2.20		164	8.2	7.8	0.42	13.7	132	2.7	33.3 HF	36.3	36.3		0.0096	6.1
	12/15/2014		4.61	1590	52.3	2.4	2.4	0.044 J	20.8	145	2.3	23.7 HF	60.8	60.8		0.071	0.33
	3/10/2015				31.7	6.39	5.1	1.29	7.0 B	83.5	1.1	19.9 HF	45.4	45.4		0.12	0.14
	3/10/2015	Duplicate			30	5.99	5.27	0.72 J	7.2 B	92.6	1.1	19.1 HF	46.9	46.9		0.079	0.17
GT-7	8/26/2014				55.4	1.0	1.0		0.14	14.5	0.58 J	45.4 HF	14.3	14.3			2.6
	11/12/2014				98.5	7.3	6.8	0.49	9.5	130	3.1	20.5	27.0	27.0			15.4
	12/15/2014				33.3	3.7	3.4	0.26	2.6	48.0	1.2	16.5 HF	25.6	25.6		0.0031 J	5.0
	3/10/2015				14.1 J	2.45	1.77	0.68 J	0.58 B	19.3	1.3	24.3 HF	25.2	25.2			1.8
VE-1R	8/26/2014		6.04			1.8	1.7	0.059 J	0.21	47.3	2.4		76.6	68.6		0.26	1.5
	8/26/2014	Duplicate				1.2	1.2		0.39	16.3	9.6		126			0.26	6.5
	11/13/2014		3.98		38.4	40.2	33.2	7.0	45.1	1180	1.8	9.0 HF	144	144		0.028	13.6
	12/16/2014		1.52		35.0	28.5	25.6	2.9	17.5	448	0.62 J	18.6 HF	148	148		0.25	2.2
	12/16/2014	Duplicate			34.1	28.9	25.8	3.1	18.0	477	0.87 J	15.7 HF	139	139		0.25	2.7
VE-5	8/26/2014					0.92	0.92			7.7	1.1	17.4 HF	29.0	29.0		0.0050	1.9
	11/13/2014					3.3	3.3	0.013 J		24.7	2.2	10.7 HF	42.0	42.0		0.0034 J	2.1
	12/16/2014					2.4	2.4			15.2	1.0	5.8 HF	41.3	41.3		0.0033 J	0.23
	3/10/2015					2.98	2.98			22.4	1.3	30.8 HF	40.1	40.1			0.3
VP-A	8/26/2014			761	8.0 J	1.7	1.7		0.14	29.5	1.1		60.9	26.5			1.6
	11/13/2014				15.3	2.4	2.4		0.083 J	25.2	1.7		69.1	69.1		0.0035 J	0.79
	12/16/2014				13.0	2.9	2.9			18.9	1.8		55.8	55.8		0.0056	4.5
	3/10/2015				5.8 J	3.18	3.18			26.7	1.3	11.6 HF	45.7	45.7			1.1
VP-B	8/26/2014				5.4	1.5	1.5		0.12	24.8	0.80 J	7.8 HF	40.3	40.3			1.1
	11/13/2014				10.4	2.1	2.1		0.087 J	26.4	3.3	5.7 HF	54.8	54.8		0.0051	1.2
	12/16/2014				4.6 J	2.6	2.6			16.9	1.0		44.8	44.8			0.84
	3/10/2015				5.0 J	4.29	3.21	1.08 J		23.1	1.2	14.6 HF	36.3	36.3			0.58

J = Sample result is greater than the MDL but below the CRDL

HF = Field parameter with a holding time of 15 minutes. Test performed by laboratory at the clients request

ATTACHMENT 4- LABORATORY ANALYTICAL REPORT

Executive Summary and Report (on CD)

EXECUTIVE SUMMARY - Detections

Client: Safety-Kleen Systems, Inc

Job Number: 460-91450-1

Lab Sample ID Analyte	Client Sample ID	Result	Qualifier	Reporting Limit	Units	Method
460-91450-1	GT-6					
1,2-Dichlorobenzene		0.28	J	3.0	ug/L	8260C
1,3-Dichlorobenzene		0.49	J	3.0	ug/L	8260C
1,4-Dichlorobenzene		1.6	J	3.0	ug/L	8260C
Mineral Spirit Range Organics		240		50	ug/L	8260B
Methane		0.12		0.0050	mg/L	RSK-175
Ammonia		7.0	B	0.50	mg/L	4500 NH3 H
Bicarbonate Alkalinity as CaCO3		45.4		5.0	mg/L	SM 2320B
Alkalinity		45.4		5.0	mg/L	SM 2320B
Carbon Dioxide, Free		19.9	HF	5.0	mg/L	SM 4500 CO2 D
Phosphate as PO4		0.14		0.030	mg/L	SM 4500 P E
Total Organic Carbon		1.1		1.0	mg/L	SM 5310B
Sulfate		83.5		6.00	mg/L	300.0
Nitrate as N		5.10		1.00	mg/L	300.0
Nitrate Nitrite as N		6.39		1.00	mg/L	300.0
Nitrite as N		1.29		1.20	mg/L	300.0
<i>Dissolved</i>						
Manganese		31.7		15.0	ug/L	200.7 Rev 4.4
460-91450-2	GT-7					
Ammonia		0.58	B	0.10	mg/L	4500 NH3 H
Bicarbonate Alkalinity as CaCO3		25.2		5.0	mg/L	SM 2320B
Alkalinity		25.2		5.0	mg/L	SM 2320B
Carbon Dioxide, Free		24.3	HF	5.0	mg/L	SM 4500 CO2 D
Phosphate as PO4		1.8		0.060	mg/L	SM 4500 P E
Total Organic Carbon		1.3		1.0	mg/L	SM 5310B
Sulfate		19.3		6.00	mg/L	300.0
Nitrate as N		1.77		1.00	mg/L	300.0
Nitrate Nitrite as N		2.45		1.00	mg/L	300.0
Nitrite as N		0.68	J	1.20	mg/L	300.0
<i>Dissolved</i>						
Manganese		14.1	J	15.0	ug/L	200.7 Rev 4.4

EXECUTIVE SUMMARY - Detections

Client: Safety-Kleen Systems, Inc

Job Number: 460-91450-1

Lab Sample ID Analyte	Client Sample ID	Result	Qualifier	Reporting Limit	Units	Method
460-91450-3	VP-A					
Tetrachloroethene		0.40	J	5.0	ug/L	8260C
Bicarbonate Alkalinity as CaCO3		45.7		5.0	mg/L	SM 2320B
Alkalinity		45.7		5.0	mg/L	SM 2320B
Carbon Dioxide, Free		11.6	HF	5.0	mg/L	SM 4500 CO2 D
Phosphate as PO4		1.1		0.030	mg/L	SM 4500 P E
Total Organic Carbon		1.3		1.0	mg/L	SM 5310B
Sulfate		26.7		6.00	mg/L	300.0
Nitrate as N		3.18		1.00	mg/L	300.0
Nitrate Nitrite as N		3.18		1.00	mg/L	300.0
<i>Dissolved</i>						
Manganese		5.8	J	15.0	ug/L	200.7 Rev 4.4
460-91450-4	VP-B					
Chloroform		0.26	J	7.0	ug/L	8260C
Tetrachloroethene		0.75	J	5.0	ug/L	8260C
Bicarbonate Alkalinity as CaCO3		36.3		5.0	mg/L	SM 2320B
Alkalinity		36.3		5.0	mg/L	SM 2320B
Carbon Dioxide, Free		14.6	HF	5.0	mg/L	SM 4500 CO2 D
Phosphate as PO4		0.58		0.030	mg/L	SM 4500 P E
Total Organic Carbon		1.2		1.0	mg/L	SM 5310B
Sulfate		23.1		6.00	mg/L	300.0
Nitrate as N		3.21		1.00	mg/L	300.0
Nitrate Nitrite as N		4.29		1.00	mg/L	300.0
Nitrite as N		1.08	J	1.20	mg/L	300.0
<i>Dissolved</i>						
Manganese		5.0	J	15.0	ug/L	200.7 Rev 4.4

EXECUTIVE SUMMARY - Detections

Client: Safety-Kleen Systems, Inc

Job Number: 460-91450-1

Lab Sample ID Analyte	Client Sample ID	Result	Qualifier	Reporting Limit	Units	Method
460-91450-5	GW-DUP					
1,3-Dichlorobenzene		0.54	J	3.0	ug/L	8260C
1,4-Dichlorobenzene		1.6	J	3.0	ug/L	8260C
Mineral Spirit Range Organics		350		50	ug/L	8260B
Methane		0.079		0.0050	mg/L	RSK-175
Ammonia		7.2	B	1.0	mg/L	4500 NH3 H
Bicarbonate Alkalinity as CaCO3		46.9		5.0	mg/L	SM 2320B
Alkalinity		46.9		5.0	mg/L	SM 2320B
Carbon Dioxide, Free		19.1	HF	5.0	mg/L	SM 4500 CO2 D
Phosphate as PO4		0.17		0.030	mg/L	SM 4500 P E
Total Organic Carbon		1.1		1.0	mg/L	SM 5310B
Sulfate		92.6		6.00	mg/L	300.0
Nitrate as N		5.27		1.00	mg/L	300.0
Nitrate Nitrite as N		5.99		1.00	mg/L	300.0
Nitrite as N		0.72	J	1.20	mg/L	300.0
<i>Dissolved</i>						
Manganese		30.0		15.0	ug/L	200.7 Rev 4.4
460-91450-7	DW-1					
Acetone		18	J	50	ug/L	8260C
4-Methyl-2-pentanone (MIBK)		0.69	J	5.0	ug/L	8260C
460-91450-8	DW-1 DUP					
Acetone		18	J	50	ug/L	8260C
460-91508-1	GT-1					
Methane		2.3		0.10	mg/L	RSK-175
Ammonia		1.9		0.10	mg/L	4500 NH3 H
Bicarbonate Alkalinity as CaCO3		124		5.0	mg/L	SM 2320B
Alkalinity		124		5.0	mg/L	SM 2320B
Carbon Dioxide, Free		32.8	HF	5.0	mg/L	SM 4500 CO2 D
Phosphate as PO4		29.5		0.60	mg/L	SM 4500 P E
Total Organic Carbon		0.61	J	1.0	mg/L	SM 5310B
Sulfate		262		60.0	mg/L	300.0
Nitrate as N		15.4		10.0	mg/L	300.0
Nitrate Nitrite as N		25.5		10.0	mg/L	300.0
Nitrite as N		10.1	J	12.0	mg/L	300.0
<i>Dissolved</i>						
Manganese		52.3		15.0	ug/L	200.7 Rev 4.4

EXECUTIVE SUMMARY - Detections

Client: Safety-Kleen Systems, Inc

Job Number: 460-91450-1

Lab Sample ID Analyte	Client Sample ID	Result	Qualifier	Reporting Limit	Units	Method
460-91508-2	GT-2					
Tetrachloroethene		0.94	J	5.0	ug/L	8260C
Bicarbonate Alkalinity as CaCO3		91.7		5.0	mg/L	SM 2320B
Alkalinity		91.7		5.0	mg/L	SM 2320B
Carbon Dioxide, Free		68.9	HF	5.0	mg/L	SM 4500 CO2 D
Phosphate as PO4		0.48		0.030	mg/L	SM 4500 P E
Total Organic Carbon		1.9		1.0	mg/L	SM 5310B
Sulfate		88.8		6.00	mg/L	300.0
Nitrate as N		8.73		1.00	mg/L	300.0
Nitrate Nitrite as N		8.73		1.00	mg/L	300.0
460-91508-3	GT-3					
Acetone		5.9	J	50	ug/L	8260C
Ammonia		0.11		0.10	mg/L	4500 NH3 H
Bicarbonate Alkalinity as CaCO3		38.7		5.0	mg/L	SM 2320B
Alkalinity		38.7		5.0	mg/L	SM 2320B
Phosphate as PO4		0.25		0.030	mg/L	SM 4500 P E
Total Organic Carbon		1.6		1.0	mg/L	SM 5310B
Sulfate		12.2		6.00	mg/L	300.0
Nitrate as N		1.06		1.00	mg/L	300.0
Nitrate Nitrite as N		1.68		1.00	mg/L	300.0
Nitrite as N		0.61	J	1.20	mg/L	300.0
<i>Dissolved</i>						
Iron		231		150	ug/L	200.7 Rev 4.4
Manganese		6.2	J	15.0	ug/L	200.7 Rev 4.4
460-91508-4	GT-5					
Bicarbonate Alkalinity as CaCO3		43.2		5.0	mg/L	SM 2320B
Alkalinity		43.2		5.0	mg/L	SM 2320B
Carbon Dioxide, Free		16.8	HF	5.0	mg/L	SM 4500 CO2 D
Phosphate as PO4		0.68		0.030	mg/L	SM 4500 P E
Total Organic Carbon		0.49	J	1.0	mg/L	SM 5310B
Sulfate		26.5		6.00	mg/L	300.0
Nitrate as N		2.92		1.00	mg/L	300.0
Nitrate Nitrite as N		2.92		1.00	mg/L	300.0
<i>Dissolved</i>						
Manganese		158		15.0	ug/L	200.7 Rev 4.4

EXECUTIVE SUMMARY - Detections

Client: Safety-Kleen Systems, Inc

Job Number: 460-91450-1

Lab Sample ID	Client Sample ID			Reporting		
Analyte		Result	Qualifier	Limit	Units	Method
460-91508-5	VE-5					
Bicarbonate Alkalinity as CaCO ₃		40.1		5.0	mg/L	SM 2320B
Alkalinity		40.1		5.0	mg/L	SM 2320B
Carbon Dioxide, Free		30.8	HF	5.0	mg/L	SM 4500 CO ₂ D
Phosphate as PO ₄		0.30		0.030	mg/L	SM 4500 P E
Total Organic Carbon		1.3		1.0	mg/L	SM 5310B
Sulfate		22.4		6.00	mg/L	300.0
Nitrate as N		2.98		1.00	mg/L	300.0
Nitrate Nitrite as N		2.98		1.00	mg/L	300.0