

Supplemental Remedial Investigation Report

Former NOW Corporation Facility (Site No. 314008)

New York State Department of Environmental Conservation

Project number: 60631041

December 2025

A thick, light green curved line starts from the bottom left, curves upwards and to the right, and then curves downwards and to the right, ending at the bottom right edge of the page.

Certification

I, Lindsay M. Mitchell, certify that I am currently a New York State (NYS) registered professional engineer as defined in 6 NYCRR Part 375 and that this Supplemental Remedial Investigation Report was prepared in accordance with all applicable statutes and regulations and in substantial conformance with the Division of Environmental Remediation Technical Guidance for Site Investigation and Remediation (DER-10) and DER Green Remediation (DER-31) and that all activities were performed in full accordance with the DER-approved work plan and any DER-approved modifications.

Respectfully submitted,

AECOM USA, Inc.



Signature

Date

December 23, 2025

Lindsay M. Mitchell


Name

088995

NYS PE Number


Quality Information

Prepared by



Christopher French
Geologist

Checked by



Eleanor Vivaudou, P.E.
Senior Engineer

Reviewed by



Matthew Zenker,
P.E.
Senior Engineer

Verified by



Robert Montione
Sr. Environmental Scientist

Approved by



Lindsay Mitchell, P.E.
Project Manager

Revision History

Revision	Revision date	Details	Authorized	Name	Position

Distribution List

# Hard Copies	PDF Required	Association / Company Name

Prepared for:

New York State Department of Environmental Conservation
Division of Environmental Remediation
625 Broadway, 12th Floor
Albany, NY 12233-7012

Prepared by:

AECOM
40 British American Boulevard
Latham, NY 12110
aecom.com

Copyright © 2025 by AECOM

All rights reserved. No part of this copyrighted work may be reproduced, distributed, or transmitted in any form or by any means without the prior written permission of AECOM.

Table of Contents

1.	Introduction and Project Background.....	1
1.1	Site Description.....	1
1.2	Site Geology	1
1.3	Site Hydrogeology	1
1.4	Remedial History	1
1.4.1	Bedrock Vapor Extraction System	3
1.4.2	Groundwater Treatment System.....	3
1.5	Conceptual Site Model	4
2.	Objectives	5
3.	Supplemental Remedial Investigation Activities	6
3.1	Underground Utility Clearance	6
3.2	Bedrock Investigations	6
3.2.1	Borehole Geophysics	6
3.2.2	Bedrock Outcrop Mapping	6
3.3	Soil Gas Survey	7
3.4	Fracture Trace Analysis	8
3.5	Investigation-Derived Waste Management.....	8
3.6	DER-31 Green and Sustainable Remediation.....	8
4.	Results and Conclusions	10
4.1	Underground Utility Clearance	10
4.2	Bedrock Investigation	10
4.2.1	Borehole Geophysics	10
4.2.2	Bedrock Outcrop Mapping	11
4.3	Soil Gas Survey	11
4.4	Fracture Trace Analysis	12
4.5	Conclusions and Revision to Conceptual Site Model.....	13
5.	Recommendations	14
6.	References.....	16

Figures

Figure 1	Site Location with Topography
Figure 2	Site Plan and Treatment System Details
Figure 3	TW-2A tVOC Concentrations
Figure 4	Borehole Geophysics Locations
Figure 5	Bedrock Outcrop Locations
Figure 6	Bedrock Outcrop Strike/Dip
Figure 7	Soil Gas Survey Points
Figure 8	Fracture Trace Analysis
Figure 9	1980 Site Aerial Photograph
Figure 10	1990 Site Aerial Photograph

Tables

Table 1	Bedrock Outcrop Mapping Data Summary
Table 2	Soil Gas Survey Mass Results
Table 3	Borehole Geophysics Three-Arm Caliper Data Summary

Appendices

Appendix A	Daily Inspection Reports
Appendix B	Enviroprobe Service, Inc. Geophysical Investigation Report
Appendix C	Advanced Geological Services Geophysical Logging Results
Appendix D	Community Air Monitoring Data
Appendix E	Green Remediation Best Management Practices
Appendix F	Beacon Environmental Soil Gas Analysis Reports

Acronyms

AECOM	AECOM USA, Inc.
AGS	Advanced Geological Services, Inc.
bgs	below ground surface
CAMP	Community Air Monitoring Plan
cis-1,2-DCE	cis-1,2-dichloroethene
COC	contaminant of concern
CSM	conceptual site model
1,1-DCE	1,1-dichloroethene
1,2-DCE	1,2-dichloroethene
DER	Division of Environmental Remediation
Enviroprobe	Enviroprobe Service, Inc.
ERD	enhanced reductive dechlorination
ERS	Earth Remediation Services
EVO	emulsified vegetable oil
GAC	granular activated carbon
gpm	gallon per minute
GPR	ground-penetrating radar
GPS	Global Positioning System
GSR	green and sustainable remediation
HASP	Health and Safety Plan
IDW	investigation-derived waste
ISCO	in situ chemical oxidation
ISM	in situ microcosm
LiDAR	light detection and ranging
MIP	membrane interface probing
NAPL	non-aqueous phase liquid
ng	nanograms
NYSDEC	New York State Department of Environmental Conservation
NYSDOH	New York State Department of Health
NYSODP	New York Statewide Digital Orthoimagery Program
OM&M	operation, maintenance and monitoring
OU	operational unit
PCE	tetrachloroethene
PFAS	per- and polyfluoroalkyl substances
PID	photoionization detector
POE	point-of-entry
ppb	parts per billion
PRR	Periodic Review Report
PVC	polyvinyl chloride
RI	remedial investigation
RI/FS	remedial investigation and feasibility study
ROD	Record of Decision
SEFA	Spreadsheets for Environmental Footprint Analysis
SMP	Site Management Plan
SRI	supplemental remedial investigation
SRIR	Supplemental Remedial Investigation Report
1,1,1-TCA	1,1,1-trichloroethane
TCE	trichloroethene
trans-1,2-DCE	trans-1,2-dichloroethene
tVOC	total volatile organic compound
US EPA	United States Environmental Protection Agency
VE	vapor extraction
VOC	volatile organic compound

1. Introduction and Project Background

AECOM USA, Inc. (AECOM) has prepared this Supplemental Remedial Investigation Report (SRIR) for the New York State Department of Environmental Conservation (NYSDEC) to summarize the findings of the supplemental remedial investigation (SRI) performed at the Former NOW Corporation Facility (“the Site”) located in the Town of Clinton, Dutchess County, New York.

This SRIR has been prepared in accordance with NYSDEC requirements as outlined in Division of Environmental Remediation (DER) Technical Guidance for Site Investigation and Remediation (DER-10) (NYSDEC, 2010) and Green Remediation (DER-31) (NYSDEC, 2011), and incorporates information gathered during previous remedial investigations (RI) and remedial activities performed at the Site.

1.1 Site Description

The Former NOW Corporation Facility (Site No. 314008) is located in the Town of Clinton, Dutchess County, New York. The Site is approximately 9 acres in size and is an active manufacturing facility. The Site location with topography is presented on **Figure 1**.

The Site is an active mixed commercial and manufacturing facility located at 2092 Route 9G in Clinton, Dutchess County, New York (refer to **Figure 1**). The property is currently owned by Andrea M. Patierno, John J. Patierno and others under 2092 Route 9G LLC, and consists of approximately nine acres of a 94.5-acre parcel. The Site is located in a primarily residential area, near the intersection of Route 9G and South Creek Road (**Figure 2**). Crum Elbow Creek is present to the northwest of the Site, west of Route 9G.

Based on the December 2022 Periodic Review Report (PRR) for the Site (AECOM, 2022), there are a number of tenants occupying the main building on-site which perform a range of functions.

1.2 Site Geology

The Site is located in a broad northeast-trending valley, with bedrock outcrops exposed along the eastern portion of the valley. Depth to bedrock ranges from zero feet below ground surface (bgs) to approximately 35 feet bgs. The bedrock consists of dark gray phyllite and metamorphosed dark gray sandstone of the Austin Glen Formation. Published geologic maps and reports indicate that the rocks in the area have undergone extensive folding and faulting. Where observed, the phyllite appeared highly fractured with closely spaced fractures along bedding and cleavage planes (Engineering-Science, Inc., 1995).

Locally, the unconsolidated materials are variable in thickness and composition. In the southern portion of the Site, a relatively thin brown silt and clay unit (5 to 10 feet thick) overlies approximately twenty feet of fine to coarse sand and gravel. Throughout the central and northern portions of the Site, a brown silt unit overlies a dense, gray till of variable thickness of 0 to 14 feet (Engineering-Science, Inc., 1995). According to the RI, unconsolidated materials were observed to be unsaturated.

1.3 Site Hydrogeology

Groundwater flow at the Site occurs under semi-confined conditions along zones of secondary porosity in the fractured bedrock aquifer. The natural direction of groundwater flow is generally from the relatively high elevations and hillsides in the eastern portion of the Site to the lower western portion. Pumping test data indicated that the groundwater flow direction is strongly influenced by the occurrence and orientation of the bedrock fractures, especially under pumping/drawdown conditions.

1.4 Remedial History

The Site was added to the NYSDEC Registry of Inactive Hazardous Waste Disposal Sites in December 1983 as a Class 2a site, due to allegations of on-site disposal of tank rinsing solutions. A fire in a warehouse may have resulted in further contamination of the Site due to water runoff during firefighting efforts. Samples of runoff water and potable water from three nearby residences collected after the fire in

February 1989 contained low levels of benzene, toluene, ethylbenzene, trichloroethene (TCE) and 1,1,1-trichloroethane (1,1,1-TCA). Subsequent residential well sampling in April 1989 determined that volatile organic compounds (VOCs) were present in two wells. In October 1989, the NYSDEC began sending bottled water to House #1, and in February 1990, a granular activated carbon (GAC) system was installed on their water system (refer to **Figure 2**). Point-of-Entry (POE) GAC systems were also installed at residences on Route 9G farther southwest of the Site in the mid-1990s, for House #3 (located on South Creek Road) in 1996, and for House #2 in 2002.

In August 1990, the Site was reclassified to Class 2, signifying that the Site presents a significant threat to public health and/or the environment and action is required. An RI was conducted in two phases, beginning in July 1992. The first phase consisted of a review of historical documents, magnetic survey, site-wide soil gas survey, test pitting, soil boring program, monitoring well installation and sampling, sediment and surface water sampling, and nearby homeowner well sampling. This phase identified the primary contaminants of concern (COCs) related to the Site, as well as approximate concentrations. The second phase of the RI was initiated in April 1994, for the purpose of gathering information for the development of remedial alternatives. This work consisted of a treatability study for groundwater via GAC and a separate treatability study involving a vapor extraction (VE) system for treating contamination in dewatered bedrock.

The Remedial Investigation/Feasibility Study (RI/FS) Report was completed by Engineering-Science, Inc. in January 1995 under the State Superfund Program. A Record of Decision (ROD) was issued in March 1995 (NYSDEC, 1995) for impacted groundwater, denoted as Operational Unit (OU) 1, and in March 1996 for impacted soil, denoted as OU2 (NYSDEC, 1996).

VOCs have been identified as the primary COCs for the Site. The COCs listed in the ROD for OU1 (NYSDEC, 1995) include:

- Benzene
- Chloroethane
- 1,1-Dichloroethene (1,1-DCE)
- 1,2-Dichloroethene (1,2-DCE)
- Tetrachloroethene (PCE)
- 1,1,1-TCA
- TCE
- Vinyl chloride.

The selected remedy for groundwater contamination per the ROD for OU1 (NYSDEC, 1995) consisted of:

- Groundwater extraction and treatment, and vapor recovery and treatment from impacted bedrock;
- Re-infiltration of a portion of the treated groundwater in order to prevent over-pumping of the potable wells of nearby homes and businesses;
- Institutional controls and restrictions on groundwater use;
- Maintenance of existing POE carbon filters on impacted homeowner wells; and
- Long-term monitoring.

The COCs listed in the ROD for OU2 include chlorinated compounds, specifically TCE and DCE (NYSDEC, 1996).

The selected remedy for soil contamination per the ROD for OU2 (NYSDEC, 1996) consisted of:

- Excavation of soil containing more than 700 parts per billion (ppb) of TCE located near the northeast corner of the building, along the drainage ditch near the northern corner of the building, and the south corner of the concrete pad;

- Excavation of weathered bedrock containing more than 700 ppb of TCE; and
- On-site treatment of excavated soils and weathered bedrock by low temperature thermal desorption or comparable technology.

The remediation of both operable units was implemented concurrently under a single set of contract documents. Earth Remediation Services (ERS) began construction of the groundwater remediation system in August 1997. In accordance with the ROD, highly impacted soils and weathered bedrock were removed from several areas and treated on-site via low temperature thermal desorption between September 1997 and January 1998. According to the Final Remediation Report (Rust Environment and Infrastructure, March 1999), a total of 1,013 tons of contaminated soil was excavated and treated on-site, not including test burns. Post-excavation soil samples were collected from the excavation floors and walls. The treated soil was used on-site as backfill. Remediation efforts in the area located southwest of the manufacturing building (Area D) were not considered to be cost-effective, as discussed in the ROD for OU2 (NYSDEC, 1996).

In February 1998, a VE system and a groundwater recovery, treatment and injection system became operational. In 1999, the Site was reclassified to Class 4.

1.4.1 Bedrock Vapor Extraction System

The locations of the four VE wells (VE-1, VE-2, TW-1 and TW-2A) are shown on **Figure 2**. Following initial system start-up in 1998, VOC removal generally occurred at an asymptotic rate. Extraction wells VE-1 and VE-2 have not been operational since February 2004, when the well screens were inundated by a high water table. On November 2, 2005, the VE system was completely shut down when the vapor blower motor ceased operation. The system was taken off-line permanently with NYSDEC approval because the system was not significantly reducing VOC concentrations in bedrock beneath the Site. The carbon vessels associated with the VE system were also removed from the process in November 2005.

The VE system removed approximately 48 pounds of total VOCs from the subsurface over the eight-year period of operation. Historical VE system sampling data and trend figures can be found in the November 2010 PRR (AECOM, 2010).

While no longer used for vapor extraction, TW-1 and TW-2A continued to act as groundwater extraction wells between 2005 and 2020.

1.4.2 Groundwater Treatment System

The Site groundwater treatment system began operation in February 1998 and was shut down in November 2020 as described below. During the lifespan of the groundwater treatment system, it was run without significant downtime except for a ten-month period from 2000 to 2001, a seven-month period from 2011 to 2012, and other brief periods. A standby submersible well pump, effluent sump pump and float switch were maintained in the treatment building so that if the equipment failed, the spare unit could be installed, minimizing interruptions.

The groundwater recovery system consisted of three groundwater recovery wells (TW-1, TW-2A, and TW-3), from which contaminated groundwater was pumped to a treatment building containing an air stripper for removal of VOCs. The treatment building location is provided on **Figure 2**. In January 2000, the air stripper discharge treatment train was modified to eliminate the carbon polish by directing exhaust through an 8-inch polyvinyl chloride (PVC) stack on the roof of the building. The air stripper exhaust manifold is fitted with dual mist eliminators to prevent water from being drawn by vacuum into the exhaust system. The GAC adsorbers were taken off-line and the carbon was disposed off-site, leaving the empty carbon vessels in-place.

Treated groundwater was collected in a three-chamber precast concrete settling tank, which is located beneath metal grates in the floor of the treatment building. The pumping system utilized a transfer pump, controlled by high and low level indicators in the third chamber of the settling tank. A sand filter was also utilized in the earlier years of system operation.

Prior to circa 2005, treated effluent was pumped to a distribution pit from which water flowed by gravity to two injection wells (IW-1 and IW-2). A portion of the treated groundwater was re-injected into the subsurface via the injection wells. When effluent flow exceeded the infiltration capacity of the two wells, water would rise to the distribution pit and overflow by gravity via subsurface piping to an outfall on Crum Elbow Creek (**Figure 2**). However, the reinjection system was shut down circa 2005 due to the accumulation of scale within the distribution pit and injection wells. The system was not repaired because homeowner wells were never drawn down significantly, and because the injection wells are within the approximate capture zone of the system. There are no plans to repair or restart the reinjection system. Effluent from the groundwater treatment system flowed through the distribution pit to the outfall at Crum Elbow Creek. Per NYSDEC directive, the groundwater treatment system was turned off by AECOM on November 30, 2020.

1.5 Conceptual Site Model

A conceptual site model (CSM) based on available data was provided in the December 2022 PRR (AECOM, 2022) and illustrates AECOM's understanding of current Site conditions. The CSM indicates that the majority of groundwater contamination appears to be present in the fractured bedrock beneath the Site. The available historical data does not provide the horizontal and vertical extents of the VOC plume.

Operation, maintenance and monitoring (OM&M) of the groundwater treatment system is not currently required by NYSDEC. AECOM turned the system off in November 2020 as instructed by NYSDEC. The OM&M Plan (Earth Tech Northeast, Inc., 2006), and a Site Management Plan (SMP) (AECOM, 2014) are available for the Site.

2. Objectives

The objectives for the SRI are to:

1. Determine if a non-aqueous phase liquid (NAPL) contamination source still exists on-site.
2. If a source is identified, delineate its extent with particular emphasis on bedrock fractures.
3. Propose remedial action to treat the identified source.

Several VOC spills are associated with the Site. A RI was previously performed to delineate the extent of the VOC impacts associated with these spills and remedial actions were designed and deployed based on the findings of that RI. After running the groundwater treatment system for over twenty years, it appears that a NAPL source remains on-site that was not delineated in the RI. An un-delineated NAPL source is inferred by high concentrations of 1,1,1-TCA found in TW-2A, which remained relatively stable for the last six years of operation. TW-2A total VOC (tVOC) concentrations from 2014 through November 2020 are plotted on **Figure 3**.

3. Supplemental Remedial Investigation Activities

This section describes the activities conducted during the supplemental remedial investigation. Daily inspection reports summarizing the activities performed on-site in August and September 2024 can be found in **Appendix A**.

3.1 Underground Utility Clearance

Prior to the initiation of intrusive field work, AECOM contacted UDig NY (811) to arrange for the location and marking of public underground utilities in the vicinity of the proposed soil gas survey locations. Following review of the utilities in the Site area, AECOM used a private surveyor, Enviroprobe Service, Inc. (Enviroprobe), for a ground-penetrating radar (GPR) survey to locate underground structures (e.g., vaults, sumps, or dry wells) and underground electric, gas, or other utilities in the proposed work area using geophysical methods. The GPR survey was conducted on August 20, 2024. Enviroprobe's Geophysical Investigation Report can be found in **Appendix B**. During the survey, Enviroprobe was to record any instances where depth to bedrock was distinguishable from overburden; however, due to subsurface conditions, Enviroprobe was unable to differentiate between overburden and bedrock so depth to bedrock was not recorded during the geophysical survey. In addition to locating utilities, Enviroprobe also identified unknown underground structures.

3.2 Bedrock Investigations

Given the shallow nature of bedrock at the Site, the presence of impacts in the overburden soil, and the detection of groundwater impacts in multiple bedrock wells (especially the presence of significant concentrations of 1,1,1-TCA in TW-2A), additional bedrock investigation activities were performed during the SRI. The sections below describe these activities, including collection of borehole geophysics data from select bedrock wells, review of published geologic information for the area in the vicinity of the Site, review of available boring/well/geophysical logs for the Site and surrounding areas, fracture trace analysis of the Site and surrounding areas, and collection of strike and dip measurements for any planar features found in bedrock outcroppings.

3.2.1 Borehole Geophysics

Borehole geophysics evaluations were performed on six on-site wells: TW-1, TW-2, TW-2A, TW-3, IW-1, and IW-2 from August 6, 2024, through August 12, 2024, by AECOM subcontractor Advanced Geological Services, Inc. (AGS). Logging runs were performed through the entirety of the unscreened bedrock portions of the wells. The locations of the wells are shown on **Figure 4**. These wells were selected based on their construction as unscreened bedrock wells with an eight-inch diameter. Remaining on-site monitoring and observation wells are two inches in diameter, a size which (along with the presence of well screens) would not accommodate the required down-hole instrumentation. The suite of geophysical logs run in TW-1, TW-2, TW-2A and TW-3 were three-arm caliper, natural gamma ray, fluid temperature, fluid conductivity, single point resistance, short (16-inch) and long (64-inch) normal resistivity, spontaneous potential, acoustic televiewer, optical televiewer, and heat pulse flowmeter readings under ambient conditions. While reinjection wells IW-1 and IW-2 had the required borehole diameters, reinjection piping in the casings of these two points limited the instrumentation that could be utilized. As a result, the acoustic televiewer, optical televiewer and heat pulse flowmeter could not be run in IW-1 and IW-2. AGS provided a report of their detailed logging results in **Appendix C**.

3.2.2 Bedrock Outcrop Mapping

AECOM field staff performed a site walk, in conjunction with soil gas survey sample retrieval (refer to Section 3.3 below), on September 5, 2024 to locate any bedrock outcrops in the vicinity of the Site that were not already known to AECOM. Three bedrock outcrops were found on-site and an additional two were located off-site (denoted as bedrock outcrops #1 through #5 on **Figure 5**). On September 23, 2024, AECOM geologists mobilized to the Site to map the bedrock outcrops. Upon arrival at a given bedrock outcrop location, the coordinates were recorded with a handheld Global Positioning System (GPS) unit, it

was photographed with a measuring rod to provide scale, and it was examined for structural trends. Planar features (bedding planes, fractures, faults) identified were then measured for their strike and dip with a Brunton pocket transit. Strike and dip measurements, GPS coordinates and other field observations were recorded in a field notebook. The strike and dip measurements are presented on **Figure 6** and in **Table 1**.

3.3 Soil Gas Survey

Due to the limited data currently available related to historical remedial investigations, the 1,1,1-TCA plume origin, and other VOC impacts on-site, AECOM field staff performed a soil gas survey using passive samplers around the perimeter of the on-site building and in specific areas of interest. AECOM began installation of the passive soil gas samplers on August 21, 2024 and completed the installation on August 23, 2024. The soil gas survey consisted of 191 discrete sampling locations. A large portion of the surveyed area was set up in an approximately 30-foot, offset grid. The area in the vicinity of recovery well TW-2A (which contains the highest known concentration of VOCs on-site, including a high proportion of 1,1,1-TCA) was surveyed with an approximately 15-foot, offset grid. The soil gas survey point locations are displayed on **Figure 7**.

Sampling points were located by AECOM field staff with a GPS unit, figures from the Supplemental Remedial Investigation Work Plan (AECOM, 2024a) and measuring tape. Once the sample location was verified and marked with spray paint or flagging, an AECOM technician used a rotary hammer drill to advance a 1 3/8-inch diameter hole to a depth of twelve to fourteen inches. A 1/2-inch diameter hole was then drilled from the bottom of the existing hole to a depth of three feet. Upon completion of the borehole, AECOM field staff used a photoionization detector (PID) to take a headspace reading at top of the hole, noting it on the chain of custody provided by the AECOM subcontracted laboratory, Beacon Environmental. A 12-inch-long aluminum pipe was inserted into the borehole with a tapping dowel provided by the laboratory until it was approximately 1/4- to 1/2-inch below ground surface. Once the installation of the aluminum pipe was complete, the cap was removed from the passive sampler and replaced with one containing a mesh screen. The sampler was lowered into the hole, the wire was looped around the aluminum pipe, and a plug of aluminum foil was inserted into the top of the boring, forming a seal. The borehole was then covered with soil or a thin concrete patch, depending on the surrounding ground surface. Upon completion of the passive soil gas sampling point, its location was recorded with a centimeter-grade GPS unit operated by AECOM field staff. The sample location was marked with a pin flag, spray-painted markings, or both.

The soil gas surveying work required AECOM personnel to drill a large quantity of holes to depths of more than three feet, which was a ground-intrusive activity requiring pre-clearing (refer to Section 3.1 above) and air monitoring. Therefore, AECOM followed the New York State Department of Health (NYSDOH) Generic Community Air Monitoring Plan (CAMP), the Supplemental Remedial Investigation Work Plan for the field activities (AECOM, 2024a), and AECOM's site-specific Health and Safety Plan (HASP) for the Site (AECOM, 2024b). The air monitoring program included particulate monitoring using DustTrak™ II Aerosol Monitors and VOC monitoring using RAE Systems MiniRAE 3000 PIDs both upwind and downwind of the work zone. These meters were run on a continuous basis with datalogging during passive soil gas sampler installation activities. Additionally, periodic monitoring for VOCs was performed in the work zone using a PID. As described above, AECOM personnel also used a PID for headspace screening at each borehole while performing the sampling point installation work. None of the downwind PID or aerosol data exceeded the criteria requiring a stop to work activities or dust suppression as specified in the CAMP or HASP. The CAMP data is provided in **Appendix D**.

The passive samplers were left to equilibrate to ambient soil gas conditions for a range of twelve to fifteen days (dependent upon sampler installation and collection dates). Retrieval of the samplers began on September 4, 2024, and concluded on September 5, 2024.

For each location, the soil or concrete cap was removed, followed by the aluminum foil plug. The sample was then retrieved using its wire tether. Once removed from the borehole, the wire mesh cap on the sampler was removed and replaced with a solid, airtight cap. Each boring was then backfilled with granular bentonite and capped at the surface with either soil or concrete depending on the surrounding

surface material. Field duplicates, which were co-located within each sampler setup and for which analysis could be requested on the laboratory chain of custody as needed, were submitted at a rate of one per twenty samples, for a total of ten duplicates. Samples were placed in a plastic bag in a cooler and shipped under established chain of custody procedures to Beacon Environmental. One trip blank was placed in each of the plastic bags containing the samples. Use of ice or other preservative was not necessary. Sampler installation (“start”) dates and times, retrieval (“stop”) dates and times, headspace PID readings and any deviations from standard procedures were recorded on the chain of custody.

The passive samplers were analyzed for seven VOCs: vinyl chloride, 1,1-DCE, trans-1,2-dichloroethene (trans-1,2-DCE), cis-1,2-dichloroethene (cis-1,2-DCE), 1,1,1-TCA, TCE, and PCE.

3.4 Fracture Trace Analysis

Fracture trace analysis was performed on the Site and its surrounding area using light detection and ranging (LiDAR) and orthoimagery obtained from the New York Statewide Digital Orthoimagery Program (NYSDOP). The fracture trace analysis was performed by identifying and recording photolinear features (any linear pattern seen on an aerial photograph or other remotely sensed imagery). The identified photolinear features were then scrutinized to ascertain if they met the established criteria to be a lineament, which is a feature that is likely the result of underlying zones of fractured bedrock. The criteria for a lineament include:

- Aligned topographic features,
- Straight stream segments,
- Aligned gaps in ridges, and
- Vegetation and soil tonal alignment.

While all the above criteria are important to consider when constructing lineaments, some are more heavily weighted to accurately identify the lineaments. The list below qualifies the criteria and also ranks them by importance:

- Straightness of the feature,
- Precise, sharp, narrowly defined valleys, stream segments or gaps in ridges,
- Features that cut a regional geologic structure,
- Soil tonal variation, and
- Anomalous vegetation height.

This fracture trace analysis relied heavily on topographic maps and LiDAR imagery. The Site locality is not extensively agriculturally cultivated, and existing vegetation is almost entirely mixed northern hardwood forest. These conditions make differentiation of soil and vegetative tonal alignment difficult.

3.5 Investigation-Derived Waste Management

Investigation-derived waste (IDW) generated during the SRI was collected in a properly labeled 55-gallon drum. The borehole geophysics work was the only activity to generate IDW, which consisted of a small volume of decontamination water from cleaning of the downhole instruments. The drum was placed within the treatment building for security. The liquids will be profiled and disposed by an AECOM waste disposal subcontractor along with purge water and decontamination water generated during recent groundwater monitoring activities.

3.6 DER-31 Green and Sustainable Remediation

This work was completed using sustainable practices, to the extent feasible, in accordance with the goals of the DER-31 Green Remediation Guidance (January 2011 and November 2023 Memorandum). A summary of green and sustainable remediation (GSR) principles utilized for site investigation activities is presented in **Appendix E**.

During the completion of this work, the following GSR efforts were incorporated into field activities:

- Vehicle idling was reduced wherever practicable.
- GPR was used as a non-invasive method to clear for utilities and identify potential and/or previously unidentified underground structures.
- Existing bedrock wells with appropriate construction were used for borehole geophysics, eliminating the need for drilling activities and their associated impacts on the environment during this phase of work.
- Field tasks were combined and conducted concurrently whenever possible, minimizing vehicle use to and from the Site. Field tasks such as the soil gas survey and a site walk to locate bedrock outcrops were conducted concurrently.
- IDW drums will be removed from the Site in a single event.
- A passive soil gas survey was conducted in lieu of soil/bedrock borings during this phase of work, eliminating the need for drilling techniques that produce more IDW and use more consumables.
- When applicable, visits to stores to purchase field supplies and other travel was limited or combined to save energy, reduce emissions, reduce localized noise, vibration, and wear and tear on roads.

During the remedy selection stage or as requested by NYSDEC, AECOM is prepared to conduct an environmental footprint analysis using the SiteWise™ tool and/or the United States Environmental Protection Agency (US EPA) Spreadsheets for Environmental Footprint Analysis (SEFA). These tools produce metrics that help estimate the overall environmental footprint of each action to aid in the remedy selection process. This analysis should consider all relevant data (such as energy consumption, materials used, labor, etc.) for each potential remedy evaluated. This evaluation should be integrated with other site-specific considerations, such as implementation, efficacy, cost, and community implications, to formulate a sustainable approach for site cleanup.

4. Results and Conclusions

This section summarizes the results of the supplemental remedial investigation activities along with conclusions that can be drawn from the data collected.

4.1 Underground Utility Clearance

During the geophysical survey, Enviroprobe located electrical, communications, sewer, and storm drainage utilities, as well as an unknown utility. The unknown utility's location leading to or from the on-site building corresponded with detections of 1,1,1-TCA from the soil gas survey (refer to **Table 2** and **Appendix F**). It is not known if the location contains residual source material or if the unknown utility has acted as a preferential pathway for soil gas migration. Based on the findings of the GPR survey, the on-site contaminant source is not believed to be from an unidentified underground structure. No unknown underground structures other than this utility were identified during the survey. Enviroprobe's geophysical investigation report is provided as **Appendix B**.

4.2 Bedrock Investigation

4.2.1 Borehole Geophysics

As described in Section 3.2.1, of the six wells selected for borehole geophysics, only four (recovery wells TW-1, TW-2, TW-2A and TW-3) could accommodate the complete suite of geophysics testing. Injection wells IW-1 and IW-2 each contained reinjection pipes through the side of the well casing that could not accommodate some of the larger-diameter instrumentation. The AGS geophysical logging results report can be found in **Appendix C**.

Fractures within the boreholes were classified based on feature type (bedding parting fracture, fracture partially open, fracture partially or slightly open, fracture discontinuous or fracture open) and were measured for their dip azimuth, dip angle and depth bgs. Many of the measured fractures were only partially open and likely bedding partings, and are therefore logged as bedding parting/fractures in the AGS report. Recovery well TW-1 contained no open fractures and only two partially open fractures at 77.5 feet and 93.2 feet. The remaining features were bedding parting fractures. TW-2 contained one open fracture at 17.9 feet, which may have been due to drilling operations as it is located just below the surface casing and therefore near the overburden-bedrock interface. Partially open fractures were seen at 37.3 feet, 62.7 feet, 76.7 feet and 95.3 feet. Additionally, TW-2 had high conductivity readings especially in the upper portion of the well. It is suspected that these high conductivity readings are due to the storage of deicing salt in the proximity of the well.

Recovery well TW-2A, which historically could sustain the highest pumping rate when the groundwater treatment system was operational, had an open fracture at 87.5 feet. Partially or slightly open fractures were found at 30.7 feet, 56.5 feet, 58.2 feet, 66.9 feet, 94.5 feet, 101.3 feet and 110.1 feet bgs. TW-3 contained only bedding parting fractures. Additionally, the dip azimuth and dip angle were also measured. The strike of fractures logged in the TW-1, TW-2, TW-2A and TW-3 boreholes were calculated by AECOM from dip azimuth measurements obtained by AGS. A summary of this data can be found in **Table 3**.

Bedding partings in TW-1, TW-2, TW-2A and TW-3 had a wide range of strikes; however, generally strikes were to the north-northeast matching the strikes measured when mapping the bedrock outcrops (Section 4.2.2). Partially open or open fractures in TW-1, TW-2, TW-2A and TW-3 also had a wide range of strikes. Partially open or open fractures in TW-1 and TW-2 had moderate correlation with the strikes and dips measured while mapping the bedrock outcrops or with the trends observed from the fracture trace analysis. TW-2A had partially open or open fractures with strikes that correlated with the fracture trends seen in the fracture trace analysis. A more complete discussion of the correlation between the fracture trace analysis and strike/dips logged from the borehole geophysics can be found in Section 4.4 below.

AGS used a heat pulse flow meter to measure the volume of flow in gallons per minute (gpm) within the boreholes of the four recovery wells. Flow conditions within all measured wells were very low or not measurable. TW-2A had no measurable flow, while TW-1 and TW-3 had flows measured below the

instrument's calibration range. Only TW-2 had flow rates greater than the instrument's calibration range but were still very low. The lack of measurable flow conditions in TW-2A indicates that it is unconfined with open communication to the atmosphere and little to no head differential exists within the well. The observed flow conditions in wells TW-1, TW-2 and TW-3 show a slight indication of the wells existing in a partially confined system. In addition to the flow rates, the AGS report indicates direction of flow upward or downward within the borehole. Groundwater within a well will move due to head differential, from areas of high head to areas of lower head. In this case the head differential likely exists between different fractures or fracture systems. Using this data, which fractures or fracture systems are an entrance for groundwater into the well boring and which are exits can be inferred.

Recovery well TW-1 displays a minor but consistent upward flow starting at 115 feet and ending after 100 feet. This upward flow suggests groundwater is entering the well from fractures near the bottom of the boring and moving upward to eventually exit at the fractures located between 90 and 95 feet. Well TW-2, which exhibited the strongest flow of any well measured, had downward flow from 20 feet to 75 feet, though no flow was detected at 65 feet. Minor upward flow was measured from 155 feet to 85 feet. It appears that the fractures at 60 to 80 feet are being fed primarily from above and to a lesser extent from below. The open fracture at 17.9 feet, which is associated with the highest flow rate measured (-0.052 gpm), may be the most significant entrance for groundwater into TW-2. Depth to water within TW-2 was measured at approximately 8.5 feet below the top of casing. This is also supported by the very high conductivity seen in TW-2. TW-3 showed upward flow, below the instrument's calibration range, from 50 to 30 feet. This suggests that water is entering the boring at the bedding parting fracture located at 53.5 feet and exiting at the bedding parting fractures seen at 20 to 23 feet.

4.2.2 Bedrock Outcrop Mapping

AECOM conducted a site walk on September 5, 2024 to locate bedrock outcrops on and adjacent to the Site. On September 23, 2024, AECOM mobilized to the Site and collected structural trend data in the form of strike and dip measurements from five identified outcrops. Outcrops #1, #2 and #3 are located on the Site property while outcrops #4 and #5 are located off-site. On-site bedrock outcrop bedding planes had strikes ranging from 4° to 30° (north to north-northeast) and dip magnitudes ranging from 56° to 68°. Off-site outcrops had bedding plane strikes ranging from 4° to 185°. The bedding interface measured to have a strike of 185° was taken from a road cut and displayed signs of possibly being altered during the road cut's construction; therefore, this measurement's accuracy is questionable. Removing the 185° bedding plane, the off-site bedding planes had strikes ranging from 4° to 17° and dips ranging from 76° to 85°. A summary of the bedrock outcrop mapping data is displayed in **Table 1**, while mapped bedrock locations are displayed on **Figure 5** and strike/dip measurements are shown on **Figure 6**.

Bedding planes/interfaces on and adjacent to the Site have a general strike to the north-northeast and dip somewhat steeply to the east-southeast. Outcrops were composed of greywacke and, in the case of outcrop #5, the greywacke is underlain by shale.

4.3 Soil Gas Survey

The soil gas survey was conducted from August 21, 2024 to September 5, 2024. Sampling locations are provided on **Figure 7** and in **Appendix F** (Figure 1). **Appendix F** also contains the laboratory reports including chains of custody and isopleth maps for cis-1,2-DCE, 1,1,1-TCA, and TCE (Figures 2 through 4). The soil gas mass analysis results are presented in **Table 2**.

The data suggests four primary areas of contamination: the western parking area, the southeastern side of the former building slab, the vicinity of TW-2A and the northern ditch. These areas roughly coincide with OU2 soil remediation areas A through D (shown on **Figure 7**). Areas A, B and C were excavated to the top of bedrock and the soil was thermally treated on-site and then used for backfill. Based on the results of the soil gas survey, the excavations failed to encompass all VOC impacts, or the source of the soil gas had penetrated the bedrock and was not removed by excavation. The soil gas screening results in the vicinity of soil remediation Area C indicate that a source of VOCs may still exist in the overburden. Soil gas sampling points N3 and O4 were located adjacent to historical soil remediation Area C. While

point N3 contained no detections of any of the seven compounds analyzed, point O4 contained 51 ng of TCE and 21 ng of cis-1,2-DCE. Soil gas mass results surrounding Area 3 were elevated:

- Soil gas sampling point N4, located directly northeast of N3, contained a TCE mass result of 5,150 nanograms (ng), as well as 3,460 ng of 1,1,1-TCA, 176 ng of cis-1,2-DCE, 2,140 ng of 1,1-DCE, 138 ng of PCE, 32 ng of trans-1,2-DCE, and 332 ng of vinyl chloride.
- N5, also located northeast of N3, contained 15,200 ng of TCE, 12,400 ng of 1,1,1-TCA, 673 ng of cis-1,2-DCE, 9,290 ng of 1,1-DCE, 84 ng of PCE, 119 ng of trans-1,2-DCE, and 866 ng of vinyl chloride.
- Points N1 and N2 (to the southwest of Area C) had TCE mass values of 149 ng and 167 ng, respectively; several other VOCs were detected, but with mass values of less than 40 ng each.
- M3, located to the west-northwest of Area C, had a TCE mass of 9,990 ng, while 2,230 ng of 1,1,1-TCA, 365 ng of cis-1,2-DCE, 1,650 ng of 1,1-DCE, 88 ng of PCE, 70 ng of trans-1,2-DCE, and 339 ng of vinyl chloride were also detected in the sample.
- The soil gas TCE result for location M4 was 987 ng, while 1,1,1-TCA (521 ng) and 1,1-DCE (346 ng) were also found at elevated levels. With the exception of trans-1,2-DCE, the other VOCs analyzed for by Beacon Environmental were detected in M4, albeit at lower mass values.

Detections of analyzed VOCs were highest to the northeast of Area C, and appear to be localized along the edge of the concrete slab. This is also the area with the highest 1,1,1-TCA mass results, as indicated on Figure 3 of **Appendix F**.

1,1,1-TCA is of particular interest because it was a significant component of the VOC fingerprint in recovery well TW-2A while the groundwater treatment system was operational. The previous excavation activities at Area A appear to have been moderately successful in removing and treating VOCs. As noted on Figure 3 of **Appendix F**, 1,1,1-TCA soil gas values in the vicinity of Area A were low or non-detect. While other VOCs were present in soil gas within the excavated area (with TCE ranging from a low of 272 ng at location AA2 to a high of 1,010 ng at V2), the highest mass was noted just to the southeast of Area A, at point BB1. This location contained a TCE mass value of 38,300 ng and a cis-1,2-DCE result of 5,730 ng, along with significantly lower or non-detect concentrations of the other VOCs analyzed. Based on available data, it is likely that a considerable portion of the source of the elevated soil gas values lies under the slab of the existing building.

The area surrounding soil remediation Area B contained the fewest detections of analyzed VOCs. Point S1, located to the southeast of Area B, contained elevated mass values for TCE (4,470 ng) and cis-1,2-DCE (259 ng). Additionally, the soil gas from Point A6, located to the northwest of Area B, contained 2,390 ng of TCE and 303 ng of cis-1,2-DCE. Immediately adjacent to Area B, soil gas sample B7 (on the northwestern end of the excavation) contained a TCE mass value of 741 ng and a cis-1,2-DCE mass of 43 ng. Similarly, Q1, on the southeastern end of the excavation, contained 605 ng of TCE, 32 ng of cis-1,2-DCE, and 12 ng of 1,1-DCE.

Area D did not undergo soil excavation, and displays moderate VOC mass in the soil gas results. Area D was also not fully horizontally delineated, and it appears a significant portion of the plume may reside outside of the soil gas survey area.

The soil gas screening samples collected to the northeast of Area C displayed the highest mass detections of 1,1,1-TCA within the surveyed area. Fracture trace analysis indicates the majority of fractures near this area of the Site trend from the south-southwest to the north-northeast. Additionally, open or partially open fractures logged within the TW-2A borehole showing strikes to the north indicate that this may be a source for the detections found in TW-2A. The plume has historically traveled to the north, despite groundwater contours indicating that it should generally flow to the west-northwest.

4.4 Fracture Trace Analysis

While very few lineaments were located on-site (the result of the relatively small size of the Site and limits in imagery resolution), a wider search over the local region provided substantially more data. For the

purpose of this discussion, the regions around the Site within which fracture trace analysis was conducted will be categorized as the eastern area and the western area, based upon their locations relative to the Site.

The overwhelming majority of lineaments identified in both the western and eastern areas trended from the south-southwest to the north-northeast. The eastern area possessed more lineaments in closer proximity to the Site than the western area. Additionally, the lineaments in the eastern area were longer, more strongly indicating the presence of fractures. Fracture trace analysis of the Site locality heavily indicate fractures trending from the south-southwest to the north-northeast, with a much smaller percentage of fractures trending from the east-southeast to the west-northwest. The western area lineaments were shorter and more widely spaced than their eastern counterparts, indicating an area with fewer fractures and/or faults present. Several lineaments identified do not follow the trend of south-southwest to north-northeast directionality. These lineaments have an east-southeast to west-northwest orientation, making their trace roughly perpendicular to the regional fracture trace trend. **Figure 8** displays the results of the fracture trace analysis.

The fracture traces identified correlate with the bedding planes mapped during the bedrock outcrop mapping conducted on September 23, 2024. The bedding plane strikes measured on September 23, 2024 generally varied from 4° to 30°. The fracture traces also correlated, though less strongly, with the fractures identified by the borehole geophysics. TW-1 had weak correlation, with one fracture having a strike of 79° and the other having a strike of 215°. TW-2 had several fractures with strikes of 14°, 206°, 219° and 195° matching with the south-southwest to north-northeast fractures seen in the trace analysis. TW-2 also had an open fracture at 270°, coinciding with the less common fracture traces seen running from the east-southeast to the west-northwest. TW-2A had fractures with strikes of 41°, 53°, 183°, 185°, 197°, 183°, 181°, 193° and 205°, strongly correlating with the general fracture trace directions.

4.5 Conclusions and Revision to Conceptual Site Model

The soil gas screening samples collected to the northeast of historical soil remediation Area C, along the edge of the slab for the former building, contained the largest 1,1,1-TCA mass values within the soil gas survey area. Historical aerial photographs from 1980 and 1990 (**Figures 9** and **10**, respectively) show a small path and a ponded area in the immediate vicinity of the elevated soil gas values, which suggest a potential disposal area. Fracture trace analysis identified the majority of fractures in the area trending from the south-southwest to the north-northeast, with several in the vicinity of the Site trending from the south-southeast to the north-northwest. Open or partially open fractures were logged within the recovery well TW-2A borehole and were identified with strikes running north-northeast to south-southwest or south-southwest to north-northeast. The fracture trace analysis combined with the fractures logged in TW-2A indicate that the area along the edge of the slab may be a source area for the detections found in TW-2A, and possibly for the off-site detections as well.

The groundwater plume has historically traveled to the north toward the properties on South Creek Road, despite groundwater elevations in on-site and off-site monitoring wells indicating flow should generally move to the west-northwest. The fractures identified during the fracture trace analysis, the fractures logged during the borehole geophysics work, and the bedding planes located during the bedrock outcrop mapping indicate that bedrock fractures are likely acting as conduits for impacts to migrate to the north in the direction of TW-2A and beyond.

Thus, the soil gas survey data collected in August and September 2024 indicate a potential source in the soil or top of bedrock along the eastern side of the former building foundation, which is directly upgradient of the impacts in the bedrock at TW-2A and off-site private properties. This suggests that a source of 1,1,1-TCA and TCE in the overburden is contributing to VOCs observed in the deeper bedrock fracture system. This fracture system may create a preferential pathway which causes the plume to move to the north.

5. Recommendations

Based on the current data collected from the utility scan and geophysical survey, the bedrock investigation including the bedrock outcrop mapping and the borehole geophysics, the soil gas survey, and the fracture trace analysis, AECOM has identified potential sources and described plausible transport mechanisms consistent with the observed behavior of the contaminant plume.

To implement a more cost-effective remediation process, however, additional conceptual site model data gaps remain at the Site. These data gaps and recommended activities to address them are listed below.

Spatial and Vertical Distribution of COCs in Overburden Soils

The Beacon Environmental soil gas data only qualitatively measures the presence of chlorinated VOCs in the vadose zone and does not yield information on vertical distribution. In addition, this study did not extend to some areas of the Site (e.g., western parking lot, beneath building slabs). Several additional investigation activities are available to address these data gaps. Potential activities could include:

- Soil sampling of the vadose zone and saturated zone to quantify the concentrations of COCs (e.g., chlorinated VOCs, 1,4-dioxane, and per- and polyfluoroalkyl substances [PFAS]). These data would provide information on the presence of COCs at the sampled depth and would also be compared to state soil standards to evaluate the need for future remediation.
- High resolution profiling of the overburden using membrane interface probing (MIP). Note that the depth of advancement of this tooling would be limited to the depth of bedrock (approximately 7 to 10 feet bgs).
- Sub-slab soil vapor sampling within Site buildings. The Beacon Environmental data indicates that source material is potentially located beneath existing building. Sub-slab soil vapor sampling points would create minimal disturbance to building tenants and could be repeatedly sampled. Due to the potential for ambient contamination due to tenant activities, these sampling points would need to be located under a helium shroud.

Vertical Distribution of COCs in Bedrock and Groundwater

- Installation of shallow bedrock monitoring wells. Several shallow monitoring wells (total depth of approximately 25 feet bgs) would be installed within hotspot areas to evaluate the presence of COCs at this depth interval. Example locations may be near TW-2A and/or near soil gas screening points H5 and N5/N6. Each well would be logged for soil/rock type, field screened for VOCs using a PID and subjected to slug testing to measure hydraulic conductivity of the screened portion.
- Packer testing of recovery well TW-2A. Historical monitoring data indicate that well TW-2A can pump a significant amount of water (approximately 10 gpm) and contains the highest observed chlorinated VOC impacts. However, recent geophysical data described herein show only minimal presence of open fractures and non-detectable vertical flow. Packer testing can be applied to isolate sections of this well to evaluate the hydraulic response and presence of chlorinated VOCs.
- Passive flux meter testing of well TW-2A. Like packer testing, a passive flux meter can be utilized to measure the vertical distribution of COC mass flux and groundwater flow. A passive flux meter consists of a permeable sock containing activated carbon and a soluble groundwater tracer. When deployed within the saturated zone of a well, the activated carbon will sorb organic compounds, while the tracer will solubilize into groundwater. After a deployment interval, the passive flux meter is retrieved and analyzed for sorption of COCs and loss of the soluble tracer. These analyses are then utilized to calculate the Darcy flux and COC mass flux at specific vertical intervals. Additional information on passive flux meters is available at <<<https://enviroflux.com/>>>.

Efficacy of Remedial Technologies

Common remedial techniques for chlorinated ethenes/ethanes include enhanced reductive dechlorination (ERD) or in situ chemical oxidation (ISCO). Due to the presence of PFAS at the Site, use of ISCO is not recommended due to the potential for precursor oxidation. Therefore, a field study to evaluate the efficacy

of ERD can be implemented. This would involve the use of an In Situ Microcosm (ISM), as provided by Microbial Insights, Inc. <<https://microbe.com/in-situ-microcosms/>>. An ISM is 'baited' with a remedial amendment and placed within an impacted well. For ERD, the ISM can be baited with an organic substrate such as emulsified vegetable oil (EVO) and a dechlorinating microbial culture. The ISM is incubated in the well for several weeks and then extracted for analysis. The different components of the ISM are analyzed for dechlorinating bacteria and reaction byproducts, the results of which are utilized to evaluate the effectiveness of the amendment. These ISMs can be deployed within an existing or newly installed well.

The above-mentioned recommendations will help ascertain the depth and breadth of COCs on-site. Once the locations of the effective amendment are defined and the amendment is deployed, additional groundwater sampling will be required to monitor COC concentrations. Depending on the distribution of PFAS and 1,4-dioxane, additional remediation may be necessary to address those emerging contaminants.

6. References

AECOM, 2010. Periodic Review Report. Former NOW Corporation Facility. Site 3-14-008. November 2010.

AECOM, 2014. Site Management Plan. Former NOW Corporation Facility. NYSDEC Site No. 3-14-008, Clinton, Dutchess County, New York. March 2014.

AECOM, 2022. Three-Year Periodic Review Report, July 2019 – June 2022. Former NOW Corporation Facility. Site No. 3-14-008. December 2022.

AECOM, 2024a. Supplemental Remedial Investigation Work Plan, Former NOW Corporation Facility. Site No. 3-14-008. August 2024.

AECOM, 2024b. Operation, Monitoring, and Maintenance for Pump and Treat Operations/Site Management Health and Safety Plan. Northeast Alloys & Metals, Inc. Site No. 633045, Utica/Oneida County, NY and NOW Corporation Site No. 314008, Clinton/Dutchess County, NY. May 2024.

Earth Tech Northeast, Inc., 2006. Operation, Maintenance and Monitoring Plan. Former NOW Corporation Facility. Site 3-14-008. May 2006.

Engineering-Science, Inc., 1995. Remedial Investigation/Feasibility Study Report, NOW Corporation Site, Town of Clinton, Dutchess County. January 1995.


NYSDEC, 1995. New York State Superfund Record of Decision. Former NOW Corporation Site Operable Unit 1, Dutchess County, New York, Site Number 3-14-008. March 1995.

NYSDEC, 1996. New York State Superfund Record of Decision. Former NOW Corporation Site Operable Unit 2, Dutchess County, New York, Site Number 3-14-008. March 1996.

NYSDEC, 2010. Division of Environmental Remediation (DER)-10 / Technical Guidance for Site Investigation and Remediation. May 2010; revised April 2019.

NYSDEC, 2011. DER-31 Green Remediation. January 2011. Rust Environment and Infrastructure of New York, Inc., 1999. Final Remedial Report. NOW Corporation Site Number 3-14-008, Volume I. March 1999.

Figures



LEGEND:

 NOW CORPORATION SITE LOCATION

NOTES:

MAP IS NOT TO SCALE

REFERENCED FROM NYSDEC ENVIRONMENTAL RESOURCE
MAPPER 2024


AECOM

40 British American Boulevard
Latham, NY 12110
T: (518) 951-2200

FIGURE 1
SITE LOCATION WITH TOPOGRAPHY


NYSDEC
FORMER NOW CORPORATION FACILITY
TOWN OF CLINTON - DUTCHESS COUNTY, NEW YORK

D:\NOW Corp\January 2025\NOW Corp Site Plan and Treatment System Details Figure 2 January 2025.dwg User:carrie.szczepanski Jan 23, 2025 - 3:12pm




AECOM	40 British American Boulevard Latham, NY 12110 T: (518) 951-2200
FIGURE 2 SITE PLAN AND TREATMENT SYSTEM DETAILS	
NYSDEC FORMER NOW CORPORATION FACILITY TOWN OF CLINTON - DUTCHESS COUNTY, NEW YORK	
JANUARY 2025	60631041


Figure 3
TW-2A tVOC Concentrations
Former NOW Corporation Site
Site No. 3-14-008



D:\NOW Corp\January 2025\NOW Corp Borehole Geophysics Locations Figure 4 January 2025.dwg User: carrie.szczepanski Jan 29, 2025 - 2:47pm




D:\NOW Corp\January 2025\New Corp Bedrock Outcrop Locations Figure 5 January 2025.dwg User:carrie.szczepanski Jan 29, 2025 - 2:42pm



LEGEND:
Bedrock Outcrop Locations

NOTES:
1. Not to scale
2. Locations are approximate
3. Image referenced from Google Earth

AECOM	40 British American Boulevard Latham, NY 12110 T: (518) 951-2200
FIGURE 5 BEDROCK OUTCROP LOCATIONS	
NYSDEC FORMER NOW CORPORATION FACILITY TOWN OF CLINTON - DUTCHESS COUNTY, NEW YORK	
JANUARY 2025	60631041



LEGEND:

- MAGENTA BEDROCK OUTCROP #1 STRIKE/DIP
- GREEN BEDROCK OUTCROP #3 STRIKE/DIP
- YELLOW BEDROCK OUTCROP #4 STRIKE/DIP
- ORANGE BEDROCK OUTCROP #5 STRIKE DIP

NOTES:

1. Not to scale
2. Locations are approximate
3. Image referenced from Google Earth


AECOM


40 British American Boulevard
Latham, NY 12110
T: (518) 951-2200

FIGURE 6
BEDROCK OUTCROP STRIKE/DIP

NYSDEC
FORMER NOW CORPORATION FACILITY
TOWN OF CLINTON - DUTCHESS COUNTY, NEW YORK

D:\NOW Corp\January 2025\New folder\NOW Corp Soil Gas Survey Points Figure 7 January 2025.dwg User:carrie.szczepanski Jan 31, 2025 -- 10:58am





- LEGEND:
- SITE BUILDING
 - LINEAMENTS
 - CRUM ELBOW CREEK

AECOM

40 British American Boulevard
Latham, NY 12110
T: (518) 951-2200

FIGURE 8
FRACTURE TRACE ANALYSIS

NYSDEC
FORMER NOW CORPORATION FACILITY
TOWN OF CLINTON - DUTCHES COUNTY, NEW YORK

Figure 9
1980 Site Aerial Photograph
Former NOW Corporation Facility
Site No. 3-14-008



Figure 10
1990 Site Aerial Photograph
Former NOW Corporation Facility
Site No. 3-14-008



Tables

Table 1
Bedrock Outcrop Mapping Data Summary
Supplemental Remedial Investigation
Former NOW Corporation Facility (Site No. 314008), Town of Clinton, New York

Outcrop ID	Coordinates		Lithology	Strike (azimuth degrees)	Dip (degrees)	Comments
#1	41.8506696° N	-73.8859947° W	Austin Glen Formation: Greywacke	30°	63°	Strike measured by sighting trace of outcrop, dip is approximate
#2	41.8509208° N	-73.8858666° W	Austin Glen Formation: Greywacke	Not Measured		No measurable bedding planes or fractures located in outcrop
#3	41.8512150° N	-73.8857979° W	Austin Glen Formation: Greywacke	21°	68°	
				28°	64°	
				28°	67°	
				4°	56°	
				6°	56°	
#4	41.8566479° N	-73.8838077° W	Austin Glen Formation: Greywacke	4°	77°	Located off-site Road Cut
				8°	76°	
#5	41.8584881° N	-73.8836451° W	Austin Glen Formation: Greywacke underlain by Shale	184°	66°	Located off-site Road Cut First set of readings taken from bedding plane that may have been disturbed from original position by construction of road cut
				185°	65°	
				17°	82°	
				16°	85°	

Notes:

Coordinates taken with handheld GPS device and are approximate

Strikes and dips with similar shading within an outcrop (blue or gray, above) were taken from the same bedding plane by different geologists

All measured strikes and dips are of bedding planes, no measurable fractures or faults found

Table 2
Soil Gas Survey Mass Results
Supplemental Remedial Investigation
Former NOW Corporation Facility (Site No. 314008), Town of Clinton, New York



Sample Name	SGP-A1	SGP-A2	SGP-A3	SGP-A4	SGP-A5	SGP-A6	SGP-A7	SGP-A8	SGP-B1	SGP-B1-DUP	SGP-B2	SGP-B3	SGP-B4	SGP-B5	SGP-B6	SGP-B7
Installation Date	08/21/2024	08/21/2024	08/21/2024	08/21/2024	08/21/2024	08/21/2024	08/21/2024	08/21/2024	08/21/2024	08/21/2024	08/21/2024	08/21/2024	08/21/2024	08/21/2024	08/21/2024	08/21/2024
Retrieval Date	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024
Received	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024
Matrix	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas
Analyte (ng)																
1,1,1-Trichloroethane	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10
1,1-Dichloroethene	<10	<10	<10	<10	<10	28	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10
cis-1,2-Dichloroethene	<10	<10	<10	<10	<10	303	<10	<10	<10	<10	<10	<10	<10	13	<10	43
Tetrachloroethene	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10
trans-1,2-Dichloroethene	<10	<10	<10	<10	<10	50	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10
Trichloroethene	<10	<10	<10	36	<10	2,390	<10	<10	<10	<10	<10	<10	<10	140	<10	741
Vinyl Chloride	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10

Sample Name	SGP-B8	SGP-B9	SGP-C1	SGP-C2	SGP-C3	SGP-C4	SGP-C5	SGP-C6	SGP-C7	SGP-C8	SGP-C9	SGP-C10	SGP-D1	SGP-D2	SGP-E1	SGP-E2
Installation Date	08/21/2024	08/21/2024	08/21/2024	08/21/2024	08/21/2024	08/21/2024	08/21/2024	08/21/2024	08/21/2024	08/21/2024	08/21/2024	08/21/2024	08/22/2024	08/22/2024	08/22/2024	08/22/2024
Retrieval Date	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024
Received	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024
Matrix	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas
Analyte (ng)																
1,1,1-Trichloroethane	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10
1,1-Dichloroethene	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	258	<10
cis-1,2-Dichloroethene	<10	<10	<10	<10	<10	<10	23	<10	<10	<10	<10	<10	<10	<10	767	<10
Tetrachloroethene	<10	<10	<10	<10	<10	<10	1,060	<10	<10	<10	<10	<10	<10	<10	<10	<10
trans-1,2-Dichloroethene	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	129	<10
Trichloroethene	20	<10	<10	<10	<10	<10	282	<10	27	<10	<10	<10	<10	<10	1,300	<10
Vinyl Chloride	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	153	<10

Sample Name	SGP-E3	SGP-F1	SGP-F2	SGP-G1	SGP-G2	SGP-H1	SGP-H2	SGP-H3	SGP-H4	SGP-H5	SGP-H6	SGP-H6-DUP	SGP-H7	SGP-H8	SGP-I1	SGP-I2
Installation Date	08/22/2024	08/22/2024	08/22/2024	08/22/2024	08/22/2024	08/22/2024	08/22/2024	08/22/2024	08/22/2024	08/22/2024	08/22/2024	08/22/2024	08/22/2024	08/22/2024	08/22/2024	08/22/2024
Retrieval Date	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024
Received	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024
Matrix	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas
Analyte (ng)																
1,1,1-Trichloroethane	<10	<10	<10	<10	<10	45	1,710	289	<10	<10	<10	<10	<10	<10	141	106
1,1-Dichloroethene	<10	31	<10	18	<10	47	1,120	300	36	171	<10	<10	281	<10	116	95
cis-1,2-Dichloroethene	<10	164	<10	3,280	104	15	471	238	799	2,810	97	91	2,520	915	31	17
Tetrachloroethene	<10	<10	<10	<10	<10	<10	14	<10	<10	<10	<10	<10	<10	<10	<10	<10
trans-1,2-Dichloroethene	<10	27	<10	484	14	<10	76	43	98	351	25	23	303	103	<10	<10
Trichloroethene	<10	1,180	<10	1,140	285	282	8,050	2,500	287	5,580	396	385	899	18	377	232
Vinyl Chloride	<10	11	<10	20	<10	13	310	96	27	93	32	35	534	55	23	34

Note:
1) Detected mass results
are shown in bold typeface,
in units of nanograms (ng).

Table 2
Soil Gas Survey Mass Results
Supplemental Remedial Investigation
Former NOW Corporation Facility (Site No. 314008), Town of Clinton, New York

Sample Name	SGP-I3	SGP-I4	SGP-I5	SGP-I6	SGP-I7	SGP-I8	SGP-J0	SGP-J00	SGP-J1	SGP-J2	SGP-J3	SGP-J4	SGP-J5	SGP-J6	SGP-J7	SGP-K0
Installation Date	08/22/2024	08/22/2024	08/22/2024	08/22/2024	08/22/2024	08/22/2024	08/23/2024	08/23/2024	08/22/2024	08/22/2024	08/22/2024	08/22/2024	08/22/2024	08/22/2024	08/22/2024	08/23/2024
Retrieval Date	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/05/2024
Received	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024
Matrix	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas
Analyte (ng)																
1,1,1-Trichloroethane	<10	<10	<10	<10	<10	614	48	<10	<10	<10	11	<10	22	18	<10	<10
1,1-Dichloroethene	<10	18	<10	<10	<10	527	33	<10	<10	<10	19	15	30	25	13	<10
cis-1,2-Dichloroethene	30	46	<10	<10	<10	55	<10	<10	<10	<10	352	39	<10	38	<10	<10
Tetrachloroethene	<10	16	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10
trans-1,2-Dichloroethene	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	39	<10	<10	<10	<10	<10
Trichloroethene	457	847	21	20	<10	<10	<10	<10	<10	<10	988	76	27	671	45	<10
Vinyl Chloride	<10	<10	<10	<10	<10	190	11	<10	<10	<10	<10	<10	<10	<10	<10	<10

Sample Name	SGP-K00	SGP-K1	SGP-K1-DUP	SGP-K2	SGP-K3	SGP-K4	SGP-K5	SGP-K6	SGP-K7	SGP-K8	SGP-L1	SGP-L2	SGP-L3	SGP-L4	SGP-L5	SGP-L6
Installation Date	08/23/2024	08/22/2024	08/22/2024	08/22/2024	08/22/2024	08/22/2024	08/22/2024	08/22/2024	08/22/2024	08/22/2024	08/22/2024	08/22/2024	08/22/2024	08/22/2024	08/22/2024	08/22/2024
Retrieval Date	09/05/2024	09/05/2024	09/05/2024	09/05/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/05/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024
Received	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024
Matrix	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas
Analyte (ng)																
1,1,1-Trichloroethane	<10	<10	<10	<10	94	152	30	<10	27	57	34	32	161	159	27	27
1,1-Dichloroethene	<10	<10	<10	<10	77	119	37	57	35	37	37	27	101	123	43	45
cis-1,2-Dichloroethene	<10	10	<10	<10	<10	<10	10	595	45	47	<10	<10	<10	<10	64	12
Tetrachloroethene	<10	<10	<10	<10	<10	<10	<10	10	<10	56	<10	<10	<10	<10	<10	<10
trans-1,2-Dichloroethene	<10	<10	<10	<10	<10	<10	<10	109	<10	<10	<10	<10	<10	<10	11	<10
Trichloroethene	<10	<10	<10	<10	25	14	152	4,140	520	543	18	<10	43	<10	442	81
Vinyl Chloride	<10	<10	<10	<10	35	44	12	55	14	32	31	11	41	43	33	22

Sample Name	SGP-L7	SGP-M0	SGP-M1	SGP-M1-DUP	SGP-M2	SGP-M3	SGP-M4	SGP-M5	SGP-M6	SGP-M7	SGP-M8	SGP-N1	SGP-N2	SGP-N3	SGP-N4	SGP-N5
Installation Date	08/22/2024	08/23/2024	08/22/2024	08/22/2024	08/22/2024	08/22/2024	08/22/2024	08/22/2024	08/22/2024	08/22/2024	08/22/2024	08/22/2024	08/22/2024	08/22/2024	08/22/2024	08/22/2024
Retrieval Date	09/04/2024	09/05/2024	09/05/2024	09/05/2024	09/05/2024	09/05/2024	09/05/2024	09/05/2024	09/05/2024	09/05/2024	09/05/2024	09/05/2024	09/05/2024	09/05/2024	09/05/2024	09/05/2024
Received	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024
Matrix	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas
Analyte (ng)																
1,1,1-Trichloroethane	23	26	17	24	44	2,230	521	2,450	170	147	198	<10	22	<10	3,460	12,400
1,1-Dichloroethene	58	35	<10	<10	29	1,650	346	1,260	216	189	244	19	22	<10	2,140	9,290
cis-1,2-Dichloroethene	707	31	<10	11	13	365	41	236	275	1,340	583	24	15	<10	176	673
Tetrachloroethene	486	<10	<10	<10	<10	88	24	30	<10	<10	28	<10	<10	<10	138	84
trans-1,2-Dichloroethene	81	<10	<10	<10	<10	70	<10	42	41	143	89	<10	<10	<10	32	119
Trichloroethene	477	402	144	165	163	9,990	987	5,580	1,900	2,110	5,020	149	167	<10	5,150	15,200
Vinyl Chloride	483	27	<10	<10	13	339	99	323	117	289	163	18	32	<10	332	866

Note:
1) Detected mass results are shown in bold typeface, in units of nanograms (ng).

Table 2
Soil Gas Survey Mass Results
Supplemental Remedial Investigation
Former NOW Corporation Facility (Site No. 314008), Town of Clinton, New York

Sample Name	SGP-N6	SGP-N7	SGP-O1	SGP-O2	SGP-O3	SGP-O4	SGP-O5	SGP-O6	SGP-O7	SGP-O8	SGP-O8-DUP	SGP-O9	SGP-O10	SGP-O11	SGP-O12	SGP-O13
Installation Date	08/22/2024	08/22/2024	08/23/2024	08/23/2024	08/23/2024	08/23/2024	08/23/2024	08/23/2024	08/23/2024	08/23/2024	08/23/2024	08/23/2024	08/23/2024	08/23/2024	08/23/2024	08/23/2024
Retrieval Date	09/05/2024	09/05/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024
Received	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024
Matrix	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas
Analyte (ng)																
1,1,1-Trichloroethane	3,510	4,670	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10
1,1-Dichloroethene	4,520	2,640	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10
cis-1,2-Dichloroethene	1,600	666	<10	<10	<10	21	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10
Tetrachloroethene	44	69	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10
trans-1,2-Dichloroethene	249	116	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10
Trichloroethene	13,300	15,100	<10	<10	<10	51	26	27	<10	<10	<10	<10	<10	<10	<10	<10
Vinyl Chloride	588	411	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10

Sample Name	SGP-O14	SGP-P1	SGP-P2	SGP-P3	SGP-P4	SGP-P4-DUP	SGP-P5	SGP-Q1	SGP-Q2	SGP-Q3	SGP-R1	SGP-R2	SGP-R3	SGP-R4	SGP-R4-DUP	SGP-S1
Installation Date	08/23/2024	08/23/2024	08/23/2024	08/23/2024	08/23/2024	08/23/2024	08/23/2024	08/23/2024	08/23/2024	08/23/2024	08/23/2024	08/23/2024	08/23/2024	08/23/2024	08/23/2024	08/23/2024
Retrieval Date	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024
Received	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024
Matrix	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas
Analyte (ng)																
1,1,1-Trichloroethane	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	1,230	<10	<10	<10	<10	<10
1,1-Dichloroethene	<10	<10	<10	<10	<10	<10	<10	12	<10	<10	3,300	<10	<10	<10	<10	36
cis-1,2-Dichloroethene	<10	10	<10	<10	<10	<10	<10	32	<10	<10	<10	<10	<10	<10	<10	259
Tetrachloroethene	<10	<10	<10	<10	<10	<10	17	<10	<10	<10	<10	<10	<10	<10	<10	<10
trans-1,2-Dichloroethene	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	79
Trichloroethene	<10	105	<10	<10	<10	<10	<10	605	28	<10	<10	<10	<10	<10	<10	4,470
Vinyl Chloride	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	249	<10	<10	<10	<10	29

Sample Name	SGP-S2	SGP-S3	SGP-T1	SGP-T2	SGP-T3	SGP-U1	SGP-U2	SGP-U3	SGP-V1	SGP-V2	SGP-V3	SGP-W1	SGP-W2	SGP-X1	SGP-X2	SGP-Y1
Installation Date	08/23/2024	08/23/2024	08/23/2024	08/23/2024	08/23/2024	08/23/2024	08/23/2024	08/23/2024	08/23/2024	08/23/2024	08/23/2024	08/23/2024	08/23/2024	08/23/2024	08/23/2024	08/23/2024
Retrieval Date	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024
Received	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024
Matrix	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas
Analyte (ng)																
1,1,1-Trichloroethane	<10	<10	<10	<10	<10	130	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10
1,1-Dichloroethene	<10	<10	20	<10	<10	243	13	<10	<10	13	<10	<10	<10	<10	<10	<10
cis-1,2-Dichloroethene	13	<10	26	<10	<10	131	34	<10	36	29	<10	<10	<10	<10	<10	<10
Tetrachloroethene	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10
trans-1,2-Dichloroethene	<10	<10	<10	<10	<10	43	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10
Trichloroethene	107	<10	368	<10	<10	624	587	<10	834	1,010	<10	<10	<10	29	<10	<10
Vinyl Chloride	<10	<10	12	<10	<10	132	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10

Note:
1) Detected mass results are shown in bold typeface, in units of nanograms (ng).

Table 2
Soil Gas Survey Mass Results
Supplemental Remedial Investigation
Former NOW Corporation Facility (Site No. 314008), Town of Clinton, New York

Sample Name	SGP-Y2	SGP-Z1	SGP-Z2	SGP-Z3	SGP-AA1	SGP-AA1-DUP	SGP-AA2	SGP-AA3	SGP-BB1	SGP-BB2	SGP-BB3	SGP-CC1	SGP-CC2	SGP-CC3	SGP-CC4	SGP-CC5
Installation Date	08/23/2024	08/23/2024	08/23/2024	08/23/2024	08/21/2024	08/21/2024	08/21/2024	08/21/2024	08/21/2024	08/21/2024	08/21/2024	08/21/2024	08/21/2024	08/21/2024	08/21/2024	08/21/2024
Retrieval Date	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024
Received	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024
Matrix	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas
Analyte (ng)																
1,1,1-Trichloroethane	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10
1,1-Dichloroethene	<10	<10	<10	<10	<10	<10	<10	15	436	15	27	<10	23	<10	27	<10
cis-1,2-Dichloroethene	<10	17	<10	<10	83	74	30	40	5,730	68	127	<10	933	103	258	<10
Tetrachloroethene	<10	<10	<10	<10	<10	<10	<10	<10	79	<10	<10	<10	<10	28	<10	<10
trans-1,2-Dichloroethene	<10	<10	<10	<10	13	12	<10	<10	635	13	24	<10	94	15	51	<10
Trichloroethene	<10	306	<10	<10	748	715	272	708	38,300	1,330	1,920	118	2,320	777	2,330	41
Vinyl Chloride	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10

Sample Name	SGP-CC5-DUP	SGP-DD1	SGP-DD2	SGP-DD3	SGP-DD4	SGP-DD5	SGP-DD6	SGP-EE1	SGP-EE2	SGP-EE3	SGP-EE4	SGP-EE5	SGP-EE6	SGP-FF1	SGP-FF2	SGP-FF3
Installation Date	08/21/2024	08/21/2024	08/21/2024	08/21/2024	08/21/2024	08/21/2024	08/21/2024	08/21/2024	08/21/2024	08/21/2024	08/21/2024	08/21/2024	08/21/2024	08/21/2024	08/21/2024	08/21/2024
Retrieval Date	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024
Received	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024
Matrix	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas
Analyte (ng)																
1,1,1-Trichloroethane	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10
1,1-Dichloroethene	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10
cis-1,2-Dichloroethene	<10	<10	57	21	<10	<10	<10	<10	<10	<10	<10	<10	<10	21	<10	<10
Tetrachloroethene	<10	<10	<10	<10	<10	11	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10
trans-1,2-Dichloroethene	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10
Trichloroethene	41	95	759	122	11	62	<10	49	19	<10	<10	20	<10	89	<10	<10
Vinyl Chloride	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10

Sample Name	SGP-FF3-DUP	SGP-FF4	SGP-FF5	SGP-GG1	SGP-GG2	SGP-GG3	SGP-GG4	SGP-HH1	SGP-HH2	SGP-HH3	SGP-II1	SGP-II2	SGP-II3	SGP-II4	SGP-JJ1	SGP-JJ2
Installation Date	08/21/2024	08/21/2024	08/21/2024	08/21/2024	08/21/2024	08/21/2024	08/21/2024	08/21/2024	08/21/2024	08/21/2024	08/21/2024	08/21/2024	08/21/2024	08/21/2024	08/21/2024	08/21/2024
Retrieval Date	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024
Received	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024
Matrix	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas
Analyte (ng)																
1,1,1-Trichloroethane	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	86	<10	<10	<10	<10	<10
1,1-Dichloroethene	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	60	<10	<10	<10	<10	<10
cis-1,2-Dichloroethene	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	83	<10
Tetrachloroethene	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	16	<10	<10	<10	<10	<10
trans-1,2-Dichloroethene	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	10	<10
Trichloroethene	<10	<10	15	46	<10	<10	<10	<10	<10	<10	32	54	<10	<10	36	<10
Vinyl Chloride	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	20	<10	<10	<10	<10	<10

Note:
1) Detected mass results are shown in bold typeface, in units of nanograms (ng).

Table 2
Soil Gas Survey Mass Results
Supplemental Remedial Investigation
Former NOW Corporation Facility (Site No. 314008), Town of Clinton, New York

Sample Name	SGP-KK1	SGP-KK2	SGP-LL1	SGP-MM1	SGP-MM2	SGP-MM3	SGP-NN1	SGP-NN2	SGP-NN3	Trip 1	Trip 2	Trip 3	Trip 4	Trip 5
Installation Date	08/21/2024	08/21/2024	08/21/2024	08/23/2024	08/23/2024	08/23/2024	08/23/2024	08/23/2024	08/23/2024					
Retrieval Date	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024	09/04/2024					
Received	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024	09/06/2024
Matrix	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Soil Gas	Air	Air	Air	Air	Air
Analyte (ng)														
1,1,1-Trichloroethane	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10
1,1-Dichloroethene	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10
cis-1,2-Dichloroethene	15	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10
Tetrachloroethene	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10
trans-1,2-Dichloroethene	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10
Trichloroethene	113	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10
Vinyl Chloride	39	<10	19	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10

Note:
1) Detected mass results
are shown in bold typeface,
in units of nanograms (ng).

Table 3
Borehole Geophysics Three-Arm Caliper Data Summary
Supplemental Remedial Investigation
Former NOW Corporation Facility (Site No. 314008), Town of Clinton, New York



TW-1			TW-2			TW-2A			TW-3		
Dip Azimuth (Degrees)	Strike ¹ (Degrees)	Fracture Type	Dip Azimuth (Degrees)	Strike ¹ (Degrees)	Fracture Type	Dip Azimuth (Degrees)	Strike ¹ (Degrees)	Fracture Type	Dip Azimuth (Degrees)	Strike ¹ (Degrees)	Fracture Type
111	21	Bedding parting	0	270	Fracture open	131	41	Fracture slightly open	92	2	Bedding parting
139	49	Bedding parting	358	268	Bedding parting	110	20	Bedding parting	101	11	Bedding parting
99	9	Bedding parting	82	352	Bedding parting	118	28	Bedding parting	124	34	Bedding parting
115	25	Bedding parting	104	14	Fracture slightly open	143	53	Fracture discontinuous	117	27	Bedding parting
112	22	Bedding parting	91	1	Bedding parting	273	183	Fracture slightly open	120	30	Bedding parting
118	28	Bedding parting	128	38	Bedding parting	275	185	Fracture slightly open	110	20	Bedding parting
169	79	Fracture slightly open	34	304	Bedding parting	102	12	Bedding parting	148	58	Bedding parting
118	28	Bedding parting	165	75	Bedding parting	287	197	Fracture slightly open	78	348	Bedding parting
108	18	Bedding parting	108	18	Bedding parting	139	49	Bedding parting	103	13	Bedding parting
305	215	Fracture slightly open	248	158	Fracture slightly open	273	183	Fracture open	--	--	--
93	3	Bedding parting	73	343	Bedding parting	271	181	Fracture slightly open	--	--	--
107	17	Bedding parting	94	4	Bedding parting	283	193	Fracture slightly open	--	--	--
122	32	Bedding parting	94	4	Bedding parting	295	205	Fracture slightly open	--	--	--
--	--	--	296	206	Fracture slightly open	--	--	--	--	--	--
--	--	--	89	359	Bedding parting	--	--	--	--	--	--
--	--	--	309	219	Fracture slightly open	--	--	--	--	--	--
--	--	--	89	359	Bedding parting	--	--	--	--	--	--
--	--	--	285	195	Fracture discontinuous	--	--	--	--	--	--

Note:

¹ - Strike of fracture calculated from dip azimuth measured via three-arm caliper by Advanced Geological Services, Inc.

Appendix A – Daily Inspection Reports

DAILY INSPECTION REPORT - No. 01
Former NOW Corporation Facility No. 314008

Date: 08/06/2024

NYSDEC Division of Environmental Remediation		 NEW YORK STATE OF OPPORTUNITY		Department of Environmental Conservation		Contract No. D009803-19	
						DEC PM – Payson Long	
Site Location: 2092 Route 9G, Clinton, Dutchess County, New York						Consultant PM – Lindsay Mitchell	
Weather Conditions						Consultant Inspector – Mike Izdebski	
General Description	Cloudy	AM	Cloudy	PM			
Temperature	63	AM	74	PM			
Wind	Calm	AM	Calm	PM			
Health & Safety							
If any box below is checked "Yes", provide explanation under "Health & Safety Comments".							
Were there any changes to the Health & Safety Plan?					*Yes	No	NA
Were there any exceedances of the perimeter air monitoring reported on this date?					*Yes	No	NA
Were there any nuisance issues reported/observed on this date?					*Yes	No	NA
Health & Safety Comments							
Tailgate meeting in the morning.							
Summary of Work Performed		Arrived at site:	0800	Departed Site:	1715		
- AECOM removed pumps from TW-1, TW-2A, and TW-3. - AECOM and Advanced Geological Services (AGS) reviewed Health and Safety and scope of work. - AGS began work at IW-2. - AGS had to leave the site for a portion of the day due to computer issues (met someone halfway from AGS's office in Pennsylvania to obtain a new laptop). - AGS completed three-armed caliper (well diameter) and polyprobe survey at IW-2. Bottom of well located at approx. 80 feet bgs.							
Equipment/Material Tracking							
If any box below is checked "Yes", provide explanation under "Material Tracking Comments".							
Were there any vehicles which did not display proper D.O.T numbers and placards?					*Yes	No	NA
Were there any vehicles which were not tarped?					* Yes	No	NA
Were there any vehicles which were not decontaminated prior to exiting the work site?					* Yes	No	NA
Personnel and Equipment							
Individual	Company	Trade	Total Hours				
Michael Izdebski	AECOM	Geologist	9.25				
Don Jagel	AGS	Geophysicist	4.25				
Ray Heller	AECOM	Environmental Engineer	4.5				
Steve Gray	AECOM	Technician	6.75				
Lindsay Mitchell	AECOM	Project Manager	2.25				
Equipment Description	Contractor/Vendor	Quantity	Used				
AGS Geophysics Truck with Logging Equipment	AGS	1	Yes				

DAILY INSPECTION REPORT - No. 01

Former NOW Corporation Facility No. 314008

Date: 08/06/2024

[illegible]

*On-Site scale for off-site shipment, delivery ticket for material received

Equipment/Material Tracking Comments:

Visitors to Site

[illegible]

Site Representatives

Name	Representing



Department of
Environmental
Conservation

Project Schedule Comments

Anticipated finish date for bedrock geophysics work is 8/13/2024.


Issues Pending

None

Interaction with Public, Property Owners, Media, etc.

Checked in with John and Andrea Patierno (owners) and reviewed proposed field activities. No major concerns were brought up regarding the upcoming work.

Include (insert) figures with markups showing location of work and job progress



Site Photographs (Descriptions Below)



Three-armed caliper probe.



Reel utilized for controlled ascent/descent of probes into wells.



Exterior view of IW-2 during geophysics work.



Interior view of AGS geophysics truck.

DAILY INSPECTION REPORT - No. 01
Former NOW Corporation Facility No. 314008

Date: 08/06/2024



AGS employee decontaminating three-armed caliper.



AGS employee assembling polyprobe.

Site Inspector(s): Michael Izdebski (AECOM)

Date: 08/06/2024

Videos of discreet operations have been provided to the DEC Project Manager to facilitate understanding of the ongoing work? Yes ☐

REMEDIAL ACTIVITIES AT PROPERTIES

On-Site Waste Storage

Drums, roll offs and piles are staged in secure areas?	Yes ☒	No ☐	N/A ☐
Liners and berms have been installed if necessary to prevent cross contamination of clean areas?	Yes ☐	No ☐	N/A ☒
Containers are in good condition or properly overpacked?	Yes ☒	No ☐	N/A ☐
Waste materials are scheduled to be properly characterized and disposed of prior to demobilization?	Yes ☒	No ☐	N/A ☐
Complying with RCRA 90 day storage limitation for hazardous waste?	Yes ☐	No ☐	N/A ☒
Piles are securely covered when not in use?	Yes ☐	No ☐	N/A ☒
Containers are closed when not in use?	Yes ☒	No ☐	N/A ☐
Staging areas should be inspected periodically and any issues addressed immediately?	Yes ☐	No ☐	N/A ☒
Signage and labeling comply with RCRA requirements for all staging areas and containers?	Yes ☐	No ☐	N/A ☒
If any issues noted, has Contractor been notified?	Yes ☐	No ☐	N/A ☒
<u>Comments:</u> 			

NUISANCE CHECKLIST

Were there any community complaints related to work on this date?	Yes ☐	No ☒	N/A ☐
Were there any odors detected on this date?	Yes ☐	No ☒	N/A ☐
Was noise outside specification and/or above background on this date?	Yes ☐	No ☒	N/A ☐
Were vibration readings outside specification and/or above background on this date?	Yes ☐	No ☒	N/A ☐
Any visible dust observed beyond the work perimeter on this date?	Yes ☐	No ☒	N/A ☐
Any visible contrast (turbidity) beyond engineering controls observed on this date?	Yes ☐	No ☒	N/A ☐
Was turbidity checked at the outfall(s)?	AM ☐	PM ☐	N/A ☒
Were any property owners NOT provided advance notice for work performed on this property on this date?	Yes ☐	No ☒	N/A ☐
Was the temporary fabric structure closed at the end of the day?	Yes ☐	No ☐	N/A ☒
Has Contractor failed to protect all foundations and structures adjacent to and adjoining the site which are affected by the excavations or other operations connected with performance of the Work?	Yes ☐	No ☐	N/A ☒
If yes, has Contractor been notified?	Yes ☐	No ☐	N/A ☒

DAILY INSPECTION REPORT - No. 01
Former NOW Corporation Facility No. 314008

Date: 08/06/2024

Comments:

RESILIENCE/GREEN REMEDIATION CHECKLIST

Is site power procured from renewable energy sources (e.g., solar, wind, geothermal, biomass and biogas)?	Yes ☐	No ☒	N/A ☐
Is the Contractor employing 2007 or newer or retrofitted (BART*) diesel on-road trucks and non-road equipment?	Yes ☐	No ☐	N/A ☒
Is vehicle idling adequately reduced per 6NYCRR Part 217-3?	Yes ☒	No ☐	N/A ☐
Have equipment operators been trained in the idling requirements of 6NYCRR Part 217-3?	Yes ☐	No ☐	N/A ☒
Is BART-equipped equipment properly maintained and working?	Yes ☐	No ☐	N/A ☒
Is work being sequenced to avoid double handling?	Yes ☐	No ☐	N/A ☒
Is there an onsite recycling program for CONTRACTOR-generated wastes and is it complied with?	Yes ☐	No ☐	N/A ☒
Are office trailer heating and cooling systems maintained at efficient set points, have programable thermostats been installed?	Yes ☐	No ☐	N/A ☒
Are products and materials used in performance of the work appropriately certified (e.g., LEED, Energy Star, Sustainable Forestry Initiative®, etc.)?	Yes ☐	No ☐	N/A ☒
Are resiliency features included in the design, or completed remedy properly installed and/or maintained (flood control, storm water controls, erosion measures, etc.)?	Yes ☐	No ☐	N/A ☒
Are green remediation elements included in the design, or completed remedy properly installed and/or maintained (e.g., porous pavement, geothermal, variable speed drives, native plantings, natural stream bank restoration, etc.)?	Yes ☐	No ☐	N/A ☒
Are appropriate metrics documented for inclusion on Form A, Summary of Green Remediation Metrics, by the CONTRACTOR?	Yes ☐	No ☐	N/A ☒
Has Contractor been notified of any deficiencies?	Yes ☐	No ☐	N/A ☒
<u>Comments:</u>			

* BART – Best Available Retrofit Technology

DAILY INSPECTION REPORT - No. 02
Former NOW Corporation Facility No. 314008

Date: 08/07/2024

NYSDEC Division of Environmental Remediation				Department of Environmental Conservation		Contract No. D009803-19 DEC PM – Payson Long Consultant PM – Lindsay Mitchell Consultant Inspector – Mike Izdebski	
Site Location: 2092 Route 9G, Clinton, Dutchess County, New York							
Weather Conditions							
General Description	Light precipitation	AM	Light precipitation	PM			
Temperature	61	AM	74	PM			
Wind	Calm	AM	Calm	PM			
Health & Safety If any box below is checked “Yes”, provide explanation under “Health & Safety Comments”.							
Were there any changes to the Health & Safety Plan?				*Yes	No	NA	
Were there any exceedances of the perimeter air monitoring reported on this date?				*Yes	No	NA	
Were there any nuisance issues reported/observed on this date?				*Yes	No	NA	
Health & Safety Comments Tailgate meeting in the morning.							
Summary of Work Performed		Arrived at site:	0800	Departed Site:	1715		
- AGS was not able to use some of their equipment in IW-2 due to an obstruction presumably caused by the water re-injection piping in the well at approx. 11 feet below the top of casing. - AGS was unable to complete any additional survey work at IW-2. - AGS began and completed all surveys at TW-2.							
Equipment/Material Tracking If any box below is checked “Yes”, provide explanation under “Material Tracking Comments”.							
Were there any vehicles which did not display proper D.O.T numbers and placards?				*Yes	No	NA	
Were there any vehicles which were not tarped?				* Yes	No	NA	
Were there any vehicles which were not decontaminated prior to exiting the work site?				* Yes	No	NA	
Personnel and Equipment							
Individual	Company		Trade		Total Hours		
Michael Izdebski	AECOM		Geologist		9.0		
Don Jagel	AGS		Geophysicist		9.25		
Equipment Description	Contractor/Vendor			Quantity	Used		
AGS Geophysics Truck with Logging Equipment	AGS			1	Yes		
Material Description	Imported/ Delivered to Site	Exported off Site	Waste Profile (If Applicable)	Source or Disposal Facility (If Applicable)	Daily Loads	Daily Weight (tons)*	

DAILY INSPECTION REPORT - No. 02
Former NOW Corporation Facility No. 314008

Date: 08/07/2024

*On-Site scale for off-site shipment, delivery ticket for material received

Equipment/Material Tracking Comments:

Visitors to Site

Name	Representing	Entered Exclusion/CRZ Zone	
		Yes	No
		Yes	No
		Yes	No
		Yes	No
		Yes	No
		Yes	No
		Yes	No
		Yes	No
		Yes	No
		Yes	No

Site Representatives

Name	Representing

Project Schedule Comments

Anticipated finish date for bedrock geophysics work is 8/13/2024.


Issues Pending

None


Interaction with Public, Property Owners, Media, etc.

Spoke with property owner – no large-scale pumping was occurring which may interfere with the geophysics data.

Include (insert) figures with markups showing location of work and job progress



Site Photographs (Descriptions Below)



Obstruction observed approximately 11' below top of casing in IW-2.



AGS set up at IW-2 in the morning.



AGS setting up at TW-2.



AGS employee inserting probe into TW-2 to conduct acoustic televiewer survey.

DAILY INSPECTION REPORT - No. 02
Former NOW Corporation Facility No. 314008

Date: 08/07/2024



AGS employee preparing heat pulse probe for survey.

Site Inspector(s): Michael Izdebski (AECOM)

Date: 08/07/2024

Videos of discreet operations have been provided to the DEC Project Manager to facilitate understanding of the ongoing work? Yes ☐

REMEDIAL ACTIVITIES AT PROPERTIES

On-Site Waste Storage

Drums, roll offs and piles are staged in secure areas?	Yes ☒	No ☐	N/A ☐
Liners and berms have been installed if necessary to prevent cross contamination of clean areas?	Yes ☐	No ☐	N/A ☒
Containers are in good condition or properly overpacked?	Yes ☒	No ☐	N/A ☐
Waste materials are scheduled to be properly characterized and disposed of prior to demobilization?	Yes ☒	No ☐	N/A ☐
Complying with RCRA 90 day storage limitation for hazardous waste?	Yes ☐	No ☐	N/A ☒
Piles are securely covered when not in use?	Yes ☐	No ☐	N/A ☒
Containers are closed when not in use?	Yes ☒	No ☐	N/A ☐
Staging areas should be inspected periodically and any issues addressed immediately?	Yes ☐	No ☐	N/A ☒
Signage and labeling comply with RCRA requirements for all staging areas and containers?	Yes ☐	No ☐	N/A ☒
If any issues noted, has Contractor been notified?	Yes ☐	No ☐	N/A ☒
<u>Comments:</u> 			

NUISANCE CHECKLIST

Were there any community complaints related to work on this date?	Yes ☐	No ☒	N/A ☐
Were there any odors detected on this date?	Yes ☐	No ☒	N/A ☐
Was noise outside specification and/or above background on this date?	Yes ☐	No ☒	N/A ☐
Were vibration readings outside specification and/or above background on this date?	Yes ☐	No ☒	N/A ☐
Any visible dust observed beyond the work perimeter on this date?	Yes ☐	No ☒	N/A ☐
Any visible contrast (turbidity) beyond engineering controls observed on this date?	Yes ☐	No ☒	N/A ☐
Was turbidity checked at the outfall(s)?	AM ☐	PM ☐	N/A ☒
Were any property owners NOT provided advance notice for work performed on this property on this date?	Yes ☐	No ☒	N/A ☐
Was the temporary fabric structure closed at the end of the day?	Yes ☐	No ☐	N/A ☒
Has Contractor failed to protect all foundations and structures adjacent to and adjoining the site which are affected by the excavations or other operations connected with performance of the Work?	Yes ☐	No ☐	N/A ☒
If yes, has Contractor been notified?	Yes ☐	No ☐	N/A ☒

DAILY INSPECTION REPORT - No. 02
Former NOW Corporation Facility No. 314008

Date: 08/07/2024

Comments:

RESILIENCE/GREEN REMEDIATION CHECKLIST

Is site power procured from renewable energy sources (e.g., solar, wind, geothermal, biomass and biogas)?	Yes ☐	No ☒	N/A ☐
Is the Contractor employing 2007 or newer or retrofitted (BART*) diesel on-road trucks and non-road equipment?	Yes ☐	No ☐	N/A ☒
Is vehicle idling adequately reduced per 6NYCRR Part 217-3?	Yes ☒	No ☐	N/A ☐
Have equipment operators been trained in the idling requirements of 6NYCRR Part 217-3?	Yes ☐	No ☐	N/A ☒
Is BART-equipped equipment properly maintained and working?	Yes ☐	No ☐	N/A ☒
Is work being sequenced to avoid double handling?	Yes ☐	No ☐	N/A ☒
Is there an onsite recycling program for CONTRACTOR-generated wastes and is it complied with?	Yes ☐	No ☐	N/A ☒
Are office trailer heating and cooling systems maintained at efficient set points, have programable thermostats been installed?	Yes ☐	No ☐	N/A ☒
Are products and materials used in performance of the work appropriately certified (e.g., LEED, Energy Star, Sustainable Forestry Initiative®, etc.)?	Yes ☐	No ☐	N/A ☒
Are resiliency features included in the design, or completed remedy properly installed and/or maintained (flood control, storm water controls, erosion measures, etc.)?	Yes ☐	No ☐	N/A ☒
Are green remediation elements included in the design, or completed remedy properly installed and/or maintained (e.g., porous pavement, geothermal, variable speed drives, native plantings, natural stream bank restoration, etc.)?	Yes ☐	No ☐	N/A ☒
Are appropriate metrics documented for inclusion on Form A, Summary of Green Remediation Metrics, by the CONTRACTOR?	Yes ☐	No ☐	N/A ☒
Has Contractor been notified of any deficiencies?	Yes ☐	No ☐	N/A ☒
<u>Comments:</u>			

* BART – Best Available Retrofit Technology

DAILY INSPECTION REPORT - No. 03
Former NOW Corporation Facility No. 314008

Date: 08/08/2024

NYSDEC Division of Environmental Remediation				Department of Environmental Conservation		Contract No. D009803-19 DEC PM – Payson Long Consultant PM – Lindsay Mitchell Consultant Inspector – Mike Izdebski	
Site Location: 2092 Route 9G, Clinton, Dutchess County, New York							
Weather Conditions							
General Description	Cloudy	AM	Heavy Precipitation	PM			
Temperature	62	AM	69	PM			
Wind	Calm	AM	Calm	PM			
Health & Safety If any box below is checked “Yes”, provide explanation under “Health & Safety Comments”.							
Were there any changes to the Health & Safety Plan?				*Yes	☒ No	NA	
Were there any exceedances of the perimeter air monitoring reported on this date?				*Yes	☐ No	☒ NA	
Were there any nuisance issues reported/observed on this date?				*Yes	☒ No	NA	
Health & Safety Comments Tailgate meeting in the morning.							
Summary of Work Performed		Arrived at site:	0800	Departed Site:	1545		
- AGS began and completed all surveys at TW-1. - AGS began surveys at TW-3 and completed the three-armed caliper and polyprobe surveys.							
Equipment/Material Tracking If any box below is checked “Yes”, provide explanation under “Material Tracking Comments”.							
Were there any vehicles which did not display proper D.O.T numbers and placards?				*Yes	☐ No	☒ NA	
Were there any vehicles which were not tarped?				* Yes	☐ No	☒ NA	
Were there any vehicles which were not decontaminated prior to exiting the work site?				* Yes	☐ No	☒ NA	
Personnel and Equipment							
Individual	Company	Trade	Total Hours				
Michael Izdebski	AECOM	Geologist	7.5				
Don Jagel	AGS	Geophysicist	7.75				
Equipment Description	Contractor/Vendor		Quantity	Used			
AGS Geophysics Truck with Logging Equipment	AGS		1	Yes			
Material Description	Imported/ Delivered to Site	Exported off Site	Waste Profile (If Applicable)	Source or Disposal Facility (If Applicable)	Daily Loads	Daily Weight (tons)*	

DAILY INSPECTION REPORT - No. 03
Former NOW Corporation Facility No. 314008

Date: 08/08/2024

*On-Site scale for off-site shipment, delivery ticket for material received

Equipment/Material Tracking Comments:

Visitors to Site

Name	Representing	Entered Exclusion/CRZ Zone	
		Yes	No
		Yes	No
		Yes	No
		Yes	No
		Yes	No
		Yes	No
		Yes	No
		Yes	No
		Yes	No
		Yes	No

Site Representatives

Name	Representing

Project Schedule Comments


Anticipated finish date for bedrock geophysics work is 8/13/2024.

Issues Pending

None

Interaction with Public, Property Owners, Media, etc.

Include (insert) figures with markups showing location of work and job progress



Site Photographs (Descriptions Below)



AGS employee setting up equipment at TW-1.



AGS set up at TW-1 in the morning.



AGS utilizing contractor bags to continue work during precipitation.



AGS employee removing heat pulse probe from TW-1.

DAILY INSPECTION REPORT - No. 03
Former NOW Corporation Facility No. 314008

Date: 08/08/2024

	
AGS starting work at TW-3.	
Site Inspector(s): Michael Izdebski (AECOM)	Date: 08/08/2024

Videos of discreet operations have been provided to the DEC Project Manager to facilitate understanding of the ongoing work? Yes ☐

REMEDIAL ACTIVITIES AT PROPERTIES

On-Site Waste Storage

Drums, roll offs and piles are staged in secure areas?	Yes ☒	No ☐	N/A ☐
Liners and berms have been installed if necessary to prevent cross contamination of clean areas?	Yes ☐	No ☐	N/A ☒
Containers are in good condition or properly overpacked?	Yes ☒	No ☐	N/A ☐
Waste materials are scheduled to be properly characterized and disposed of prior to demobilization?	Yes ☒	No ☐	N/A ☐
Complying with RCRA 90 day storage limitation for hazardous waste?	Yes ☐	No ☐	N/A ☒
Piles are securely covered when not in use?	Yes ☐	No ☐	N/A ☒
Containers are closed when not in use?	Yes ☒	No ☐	N/A ☐
Staging areas should be inspected periodically and any issues addressed immediately?	Yes ☐	No ☐	N/A ☒
Signage and labeling comply with RCRA requirements for all staging areas and containers?	Yes ☐	No ☐	N/A ☒
If any issues noted, has Contractor been notified?	Yes ☐	No ☐	N/A ☒
<u>Comments:</u> 			

NUISANCE CHECKLIST

Were there any community complaints related to work on this date?	Yes ☐	No ☒	N/A ☐
Were there any odors detected on this date?	Yes ☐	No ☒	N/A ☐
Was noise outside specification and/or above background on this date?	Yes ☐	No ☒	N/A ☐
Were vibration readings outside specification and/or above background on this date?	Yes ☐	No ☒	N/A ☐
Any visible dust observed beyond the work perimeter on this date?	Yes ☐	No ☒	N/A ☐
Any visible contrast (turbidity) beyond engineering controls observed on this date?	Yes ☐	No ☒	N/A ☐
Was turbidity checked at the outfall(s)?	AM ☐	PM ☐	N/A ☒
Were any property owners NOT provided advance notice for work performed on this property on this date?	Yes ☐	No ☒	N/A ☐
Was the temporary fabric structure closed at the end of the day?	Yes ☐	No ☐	N/A ☒
Has Contractor failed to protect all foundations and structures adjacent to and adjoining the site which are affected by the excavations or other operations connected with performance of the Work?	Yes ☐	No ☐	N/A ☒
If yes, has Contractor been notified?	Yes ☐	No ☐	N/A ☒

DAILY INSPECTION REPORT - No. 03
Former NOW Corporation Facility No. 314008

Date: 08/08/2024

Comments:

RESILIENCE/GREEN REMEDIATION CHECKLIST

Is site power procured from renewable energy sources (e.g., solar, wind, geothermal, biomass and biogas)?	Yes ☐	No ☒	N/A ☐
Is the Contractor employing 2007 or newer or retrofitted (BART*) diesel on-road trucks and non-road equipment?	Yes ☐	No ☐	N/A ☒
Is vehicle idling adequately reduced per 6NYCRR Part 217-3?	Yes ☒	No ☐	N/A ☐
Have equipment operators been trained in the idling requirements of 6NYCRR Part 217-3?	Yes ☐	No ☐	N/A ☒
Is BART-equipped equipment properly maintained and working?	Yes ☐	No ☐	N/A ☒
Is work being sequenced to avoid double handling?	Yes ☐	No ☐	N/A ☒
Is there an onsite recycling program for CONTRACTOR-generated wastes and is it complied with?	Yes ☐	No ☐	N/A ☒
Are office trailer heating and cooling systems maintained at efficient set points, have programable thermostats been installed?	Yes ☐	No ☐	N/A ☒
Are products and materials used in performance of the work appropriately certified (e.g., LEED, Energy Star, Sustainable Forestry Initiative®, etc.)?	Yes ☐	No ☐	N/A ☒
Are resiliency features included in the design, or completed remedy properly installed and/or maintained (flood control, storm water controls, erosion measures, etc.)?	Yes ☐	No ☐	N/A ☒
Are green remediation elements included in the design, or completed remedy properly installed and/or maintained (e.g., porous pavement, geothermal, variable speed drives, native plantings, natural stream bank restoration, etc.)?	Yes ☐	No ☐	N/A ☒
Are appropriate metrics documented for inclusion on Form A, Summary of Green Remediation Metrics, by the CONTRACTOR?	Yes ☐	No ☐	N/A ☒
Has Contractor been notified of any deficiencies?	Yes ☐	No ☐	N/A ☒
<u>Comments:</u>			

* BART – Best Available Retrofit Technology

DAILY INSPECTION REPORT - No. 04
Former NOW Corporation Facility No. 314008

Date: 08/09/2024

NYSDEC Division of Environmental Remediation				NEW YORK STATE OF OPPORTUNITY Department of Environmental Conservation		Contract No. D009803-19 DEC PM – Payson Long Consultant PM – Lindsay Mitchell Consultant Inspector – Mike Izdebski	
Site Location: 2092 Route 9G, Clinton, Dutchess County, New York							
Weather Conditions							
General Description	Cloudy	AM	Precipitation	PM			
Temperature	66	AM	78	PM			
Wind	Breezy	AM	Breezy	PM			
Health & Safety If any box below is checked “Yes”, provide explanation under “Health & Safety Comments”.							
Were there any changes to the Health & Safety Plan?				*Yes	☒ No	NA	
Were there any exceedances of the perimeter air monitoring reported on this date?				*Yes	☐ No	☒ NA	
Were there any nuisance issues reported/observed on this date?				*Yes	☒ No	NA	
Health & Safety Comments Tailgate meeting in the morning.							
Summary of Work Performed		Arrived at site:	0800	Departed Site:	1300		
- AGS continued and completed all surveys at TW-3.							
Equipment/Material Tracking If any box below is checked “Yes”, provide explanation under “Material Tracking Comments”.							
Were there any vehicles which did not display proper D.O.T numbers and placards?				*Yes	☐ No	☒ NA	
Were there any vehicles which were not tarped?				* Yes	☐ No	☒ NA	
Were there any vehicles which were not decontaminated prior to exiting the work site?				* Yes	☐ No	☒ NA	
Personnel and Equipment							
Individual		Company		Trade		Total Hours	
Michael Izdebski		AECOM		Geologist		5	
Don Jagel		AGS		Geophysicist		5	
Equipment Description		Contractor/Vendor			Quantity	Used	
AGS Geophysics Truck with Logging Equipment		AGS			1	Yes	
Material Description		Imported/Delivered to Site	Exported off Site	Waste Profile (If Applicable)	Source or Disposal Facility (If Applicable)	Daily Loads	Daily Weight (tons)*

DAILY INSPECTION REPORT - No. 04
Former NOW Corporation Facility No. 314008

Date: 08/09/2024

*On-Site scale for off-site shipment, delivery ticket for material received

Equipment/Material Tracking Comments:

Visitors to Site

Name	Representing	Entered Exclusion/CRZ Zone	
		Yes	No
		Yes	No
		Yes	No
		Yes	No
		Yes	No
		Yes	No
		Yes	No
		Yes	No
		Yes	No

Site Representatives

Name	Representing

Project Schedule Comments


Anticipated finish date for bedrock geophysics work is 8/13/2024.

Issues Pending

None

Interaction with Public, Property Owners, Media, etc.

Include (insert) figures with markups showing location of work and job progress



Site Photographs (Descriptions Below)



AGS staging equipment in treatment building to facilitate work during wet conditions.



AGS inserting optical televiewer into TW-3.



AGS employee deconstructing acoustic televiewer.



AGS employee rinsing heat pulse probe before inserting it into TW-3.

DAILY INSPECTION REPORT - No. 04
Former NOW Corporation Facility No. 314008

Date: 08/09/2024



AGS employee wiping off heat pulse probe after completing survey at TW-3.

Site Inspector(s): Michael Izdebski (AECOM)

Date: 08/09/2024

Videos of discreet operations have been provided to the DEC Project Manager to facilitate understanding of the ongoing work? Yes ☐

REMEDIAL ACTIVITIES AT PROPERTIES

On-Site Waste Storage

Drums, roll offs and piles are staged in secure areas?	Yes ☒	No ☐	N/A ☐
Liners and berms have been installed if necessary to prevent cross contamination of clean areas?	Yes ☐	No ☐	N/A ☒
Containers are in good condition or properly overpacked?	Yes ☒	No ☐	N/A ☐
Waste materials are scheduled to be properly characterized and disposed of prior to demobilization?	Yes ☒	No ☐	N/A ☐
Complying with RCRA 90 day storage limitation for hazardous waste?	Yes ☐	No ☐	N/A ☒
Piles are securely covered when not in use?	Yes ☐	No ☐	N/A ☒
Containers are closed when not in use?	Yes ☒	No ☐	N/A ☐
Staging areas should be inspected periodically and any issues addressed immediately?	Yes ☐	No ☐	N/A ☒
Signage and labeling comply with RCRA requirements for all staging areas and containers?	Yes ☐	No ☐	N/A ☒
If any issues noted, has Contractor been notified?	Yes ☐	No ☐	N/A ☒
<u>Comments:</u> 			

NUISANCE CHECKLIST

Were there any community complaints related to work on this date?	Yes ☐	No ☒	N/A ☐
Were there any odors detected on this date?	Yes ☐	No ☒	N/A ☐
Was noise outside specification and/or above background on this date?	Yes ☐	No ☒	N/A ☐
Were vibration readings outside specification and/or above background on this date?	Yes ☐	No ☒	N/A ☐
Any visible dust observed beyond the work perimeter on this date?	Yes ☐	No ☒	N/A ☐
Any visible contrast (turbidity) beyond engineering controls observed on this date?	Yes ☐	No ☒	N/A ☐
Was turbidity checked at the outfall(s)?	AM ☐	PM ☐	N/A ☒
Were any property owners NOT provided advance notice for work performed on this property on this date?	Yes ☐	No ☒	N/A ☐
Was the temporary fabric structure closed at the end of the day?	Yes ☐	No ☐	N/A ☒
Has Contractor failed to protect all foundations and structures adjacent to and adjoining the site which are affected by the excavations or other operations connected with performance of the Work?	Yes ☐	No ☐	N/A ☒
If yes, has Contractor been notified?	Yes ☐	No ☐	N/A ☒

DAILY INSPECTION REPORT - No. 04
Former NOW Corporation Facility No. 314008

Date: 08/09/2024

Comments:

RESILIENCE/GREEN REMEDIATION CHECKLIST

Is site power procured from renewable energy sources (e.g., solar, wind, geothermal, biomass and biogas)?	Yes ☐	No ☒	N/A ☐
Is the Contractor employing 2007 or newer or retrofitted (BART*) diesel on-road trucks and non-road equipment?	Yes ☐	No ☐	N/A ☒
Is vehicle idling adequately reduced per 6NYCRR Part 217-3?	Yes ☒	No ☐	N/A ☐
Have equipment operators been trained in the idling requirements of 6NYCRR Part 217-3?	Yes ☐	No ☐	N/A ☒
Is BART-equipped equipment properly maintained and working?	Yes ☐	No ☐	N/A ☒
Is work being sequenced to avoid double handling?	Yes ☐	No ☐	N/A ☒
Is there an onsite recycling program for CONTRACTOR-generated wastes and is it complied with?	Yes ☐	No ☐	N/A ☒
Are office trailer heating and cooling systems maintained at efficient set points, have programable thermostats been installed?	Yes ☐	No ☐	N/A ☒
Are products and materials used in performance of the work appropriately certified (e.g., LEED, Energy Star, Sustainable Forestry Initiative®, etc.)?	Yes ☐	No ☐	N/A ☒
Are resiliency features included in the design, or completed remedy properly installed and/or maintained (flood control, storm water controls, erosion measures, etc.)?	Yes ☐	No ☐	N/A ☒
Are green remediation elements included in the design, or completed remedy properly installed and/or maintained (e.g., porous pavement, geothermal, variable speed drives, native plantings, natural stream bank restoration, etc.)?	Yes ☐	No ☐	N/A ☒
Are appropriate metrics documented for inclusion on Form A, Summary of Green Remediation Metrics, by the CONTRACTOR?	Yes ☐	No ☐	N/A ☒
Has Contractor been notified of any deficiencies?	Yes ☐	No ☐	N/A ☒
<u>Comments:</u>			

* BART – Best Available Retrofit Technology

DAILY INSPECTION REPORT - No. 05
Former NOW Corporation Facility No. 314008

Date: 08/12/2024

NYSDEC Division of Environmental Remediation				Contract No. D009803-19 DEC PM – Payson Long Consultant PM – Lindsay Mitchell Consultant Inspector – Mike Izdebski	
Site Location: 2092 Route 9G, Clinton, Dutchess County, New York					
Weather Conditions					
General Description	Partly cloudy	AM	Partly cloudy	PM	
Temperature	55	AM	75	PM	
Wind	Breezy	AM	Breezy	PM	
Health & Safety If any box below is checked “Yes”, provide explanation under “Health & Safety Comments”.					
Were there any changes to the Health & Safety Plan?				*Yes	☒ No ☐ NA
Were there any exceedances of the perimeter air monitoring reported on this date?				*Yes	☐ No ☒ NA
Were there any nuisance issues reported/observed on this date?				*Yes	☒ No ☐ NA
Health & Safety Comments					
Tailgate meeting in the morning.					
Summary of Work Performed		Arrived at site:	0800	Departed Site:	1600
- AGS completed three-armed caliper (well diameter) and polyprobe survey at IW-1. AGS was not able to use some of their equipment in IW-1 due to an obstruction presumably caused by the water re-injection piping in the well, similarly to IW-2. - AGS completed all surveys at TW-2A. - AECOM returned piping and wiring which had been temporarily removed from TW-1, TW-2A, and TW-3. Pumps were left in the treatment building per AECOM PM instructions. - AGS demobilized.					
Equipment/Material Tracking If any box below is checked “Yes”, provide explanation under “Material Tracking Comments”.					
Were there any vehicles which did not display proper D.O.T numbers and placards?				*Yes	☐ No ☒ NA
Were there any vehicles which were not tarped?				* Yes	☐ No ☒ NA
Were there any vehicles which were not decontaminated prior to exiting the work site?				* Yes	☐ No ☒ NA
Personnel and Equipment					
Individual	Company	Trade	Total Hours		
Michael Izdebski	AECOM	Geologist	8		
Don Jagel	AGS	Geophysicist	8		
Equipment Description	Contractor/Vendor	Quantity	Used		
AGS Geophysics Truck with Logging Equipment	AGS	1	Yes		

DAILY INSPECTION REPORT - No. 05

Former NOW Corporation Facility No. 314008

Date: 08/12/2024

[illegible]

*On-Site scale for off-site shipment, delivery ticket for material received

Equipment/Material Tracking Comments:

Visitors to Site

[illegible]

Site Representatives

Name	Representing



Department of
Environmental
Conservation

Project Schedule Comments

Geophysical survey completed one day ahead of schedule on 8/12/2024.


Issues Pending


None

Interaction with Public, Property Owners, Media, etc.

AECOM let property owners know that the geophysical survey was complete and that the AECOM project manager would be in contact regarding upcoming work.

Include (insert) figures with markups showing location of work and job progress



Site Photographs (Descriptions Below)	
	
Obstruction observed in IW-1. AGS was able to complete three-armed caliper and polyprobe surveys at this location.	AGS preparing equipment for surveys at IW-1.
	
AGS employee deploying three-armed caliper in location IW-1.	AGS employee preparing equipment for geophysics work at TW-2A.

DAILY INSPECTION REPORT - No. 05
Former NOW Corporation Facility No. 314008

Date: 08/12/2024



AGS deconning heat pulse probe following TW-2A survey.



TW-2A secured with hose, wiring, and transducer returned to its interior.

Site Inspector(s): Michael Izdebski (AECOM)

Date: 08/12/2024

Videos of discreet operations have been provided to the DEC Project Manager to facilitate understanding of the ongoing work? Yes ☐

REMEDIAL ACTIVITIES AT PROPERTIES

On-Site Waste Storage

Drums, roll offs and piles are staged in secure areas?	Yes ☒	No ☐	N/A ☐
Liners and berms have been installed if necessary to prevent cross contamination of clean areas?	Yes ☐	No ☐	N/A ☒
Containers are in good condition or properly overpacked?	Yes ☒	No ☐	N/A ☐
Waste materials are scheduled to be properly characterized and disposed of prior to demobilization?	Yes ☒	No ☐	N/A ☐
Complying with RCRA 90 day storage limitation for hazardous waste?	Yes ☐	No ☐	N/A ☒
Piles are securely covered when not in use?	Yes ☐	No ☐	N/A ☒
Containers are closed when not in use?	Yes ☒	No ☐	N/A ☐
Staging areas should be inspected periodically and any issues addressed immediately?	Yes ☐	No ☐	N/A ☒
Signage and labeling comply with RCRA requirements for all staging areas and containers?	Yes ☐	No ☐	N/A ☒
If any issues noted, has Contractor been notified?	Yes ☐	No ☐	N/A ☒
<u>Comments:</u> 			

NUISANCE CHECKLIST

Were there any community complaints related to work on this date?	Yes ☐	No ☒	N/A ☐
Were there any odors detected on this date?	Yes ☐	No ☒	N/A ☐
Was noise outside specification and/or above background on this date?	Yes ☐	No ☒	N/A ☐
Were vibration readings outside specification and/or above background on this date?	Yes ☐	No ☒	N/A ☐
Any visible dust observed beyond the work perimeter on this date?	Yes ☐	No ☒	N/A ☐
Any visible contrast (turbidity) beyond engineering controls observed on this date?	Yes ☐	No ☒	N/A ☐
Was turbidity checked at the outfall(s)?	AM ☐	PM ☐	N/A ☒
Were any property owners NOT provided advance notice for work performed on this property on this date?	Yes ☐	No ☒	N/A ☐
Was the temporary fabric structure closed at the end of the day?	Yes ☐	No ☐	N/A ☒
Has Contractor failed to protect all foundations and structures adjacent to and adjoining the site which are affected by the excavations or other operations connected with performance of the Work?	Yes ☐	No ☐	N/A ☒
If yes, has Contractor been notified?	Yes ☐	No ☐	N/A ☒

DAILY INSPECTION REPORT - No. 05
Former NOW Corporation Facility No. 314008

Date: 08/12/2024

Comments:

RESILIENCE/GREEN REMEDIATION CHECKLIST

Is site power procured from renewable energy sources (e.g., solar, wind, geothermal, biomass and biogas)?	Yes ☐	No ☒	N/A ☐
Is the Contractor employing 2007 or newer or retrofitted (BART*) diesel on-road trucks and non-road equipment?	Yes ☐	No ☐	N/A ☒
Is vehicle idling adequately reduced per 6NYCRR Part 217-3?	Yes ☒	No ☐	N/A ☐
Have equipment operators been trained in the idling requirements of 6NYCRR Part 217-3?	Yes ☐	No ☐	N/A ☒
Is BART-equipped equipment properly maintained and working?	Yes ☐	No ☐	N/A ☒
Is work being sequenced to avoid double handling?	Yes ☐	No ☐	N/A ☒
Is there an onsite recycling program for CONTRACTOR-generated wastes and is it complied with?	Yes ☐	No ☐	N/A ☒
Are office trailer heating and cooling systems maintained at efficient set points, have programable thermostats been installed?	Yes ☐	No ☐	N/A ☒
Are products and materials used in performance of the work appropriately certified (e.g., LEED, Energy Star, Sustainable Forestry Initiative®, etc.)?	Yes ☐	No ☐	N/A ☒
Are resiliency features included in the design, or completed remedy properly installed and/or maintained (flood control, storm water controls, erosion measures, etc.)?	Yes ☐	No ☐	N/A ☒
Are green remediation elements included in the design, or completed remedy properly installed and/or maintained (e.g., porous pavement, geothermal, variable speed drives, native plantings, natural stream bank restoration, etc.)?	Yes ☐	No ☐	N/A ☒
Are appropriate metrics documented for inclusion on Form A, Summary of Green Remediation Metrics, by the CONTRACTOR?	Yes ☐	No ☐	N/A ☒
Has Contractor been notified of any deficiencies?	Yes ☐	No ☐	N/A ☒
<u>Comments:</u>			

* BART – Best Available Retrofit Technology

DAILY INSPECTION REPORT - No. 06
Former NOW Corporation Facility No. 314008

Date: 08/20/2024

NYSDEC Division of Environmental Remediation				Department of Environmental Conservation		Contract No. D009803-19 DEC PM – Payson Long Consultant PM – Lindsay Mitchell Consultant Inspector – Mike Izdebski	
Site Location: 2092 Route 9G, Clinton, Dutchess County, New York							
Weather Conditions							
General Description	Partly cloudy	AM	Partly cloudy	PM			
Temperature	53	AM	70	PM			
Wind	Breezy	AM	Breezy	PM			
Health & Safety If any box below is checked “Yes”, provide explanation under “Health & Safety Comments”.							
Were there any changes to the Health & Safety Plan?					*Yes	☒ No	NA
Were there any exceedances of the perimeter air monitoring reported on this date?					*Yes	No	☒ NA
Were there any nuisance issues reported/observed on this date?					*Yes	☒ No	NA
Health & Safety Comments Tailgate meeting in the morning.							
Summary of Work Performed		Arrived at site:	0830	Departed Site:	1430		
- Enviroprobe Service, Inc. completed an underground utility investigation/survey in the soil vapor work area (green shaded area in attached figure). - AECOM oversaw the underground utility investigation. - AECOM began marking out proposed soil vapor sampling locations.							
Equipment/Material Tracking If any box below is checked “Yes”, provide explanation under “Material Tracking Comments”.							
Were there any vehicles which did not display proper D.O.T numbers and placards?					*Yes	No	☒ NA
Were there any vehicles which were not tarped?					* Yes	No	☒ NA
Were there any vehicles which were not decontaminated prior to exiting the work site?					* Yes	No	☒ NA
Personnel and Equipment							
Individual	Company	Trade	Total Hours				
Michael Izdebski	AECOM	Geologist	6				
Kris Swanson	Enviroprobe Service, Inc.	GPR Technician	5.5				
Equipment Description	Contractor/Vendor			Quantity	Used		
Utility Detection Radar	Enviroprobe Service, Inc.			1	Yes		
Electromagnetic Locator	Enviroprobe Service, Inc.			1	Yes		

DAILY INSPECTION REPORT - No. 06

Former NOW Corporation Facility No. 314008

Date: 08/20/2024

[illegible]

*On-Site scale for off-site shipment, delivery ticket for material received

Equipment/Material Tracking Comments:

Visitors to Site

[illegible]

Site Representatives

Name	Representing



Department of
Environmental
Conservation

Project Schedule Comments

Anticipated completion date for soil gas passive sampling point installation is 08/23/2024.


Issues Pending

None

Interaction with Public, Property Owners, Media, etc.

AECOM field staff checked in with the property owner in the morning and provided an overview of the work activities for the week.

Include (insert) figures with markups showing location of work and job progress



Site Photographs (Descriptions Below)



AECOM marked out the boundary of the GPR survey using a white dashed line.



Enviroprobe Service, Inc. employee using the utility detection radar.



Stacked logs on the right side of the photo illustrate potentially inaccessible soil vapor points.



AECOM began marking out proposed soil vapor points with spray paint.

DAILY INSPECTION REPORT - No. 06
Former NOW Corporation Facility No. 314008

Date: 08/20/2024



Enviroprobe Service, Inc. employee using the utility detection radar.



Enviroprobe Service, Inc. employee tracing out a utility line using an electromagnetic locator.

Site Inspector(s): Michael Izdebski (AECOM)

Date: 08/20/2024

Videos of discreet operations have been provided to the DEC Project Manager to facilitate understanding of the ongoing work? Yes ☐

REMEDIAL ACTIVITIES AT PROPERTIES

On-Site Waste Storage

Drums, roll offs and piles are staged in secure areas?	Yes ☐	No ☐	N/A ☒
Liners and berms have been installed if necessary to prevent cross contamination of clean areas?	Yes ☐	No ☐	N/A ☒
Containers are in good condition or properly overpacked?	Yes ☐	No ☐	N/A ☒
Waste materials are scheduled to be properly characterized and disposed of prior to demobilization?	Yes ☐	No ☐	N/A ☒
Complying with RCRA 90 day storage limitation for hazardous waste?	Yes ☐	No ☐	N/A ☒
Piles are securely covered when not in use?	Yes ☐	No ☐	N/A ☒
Containers are closed when not in use?	Yes ☐	No ☐	N/A ☒
Staging areas should be inspected periodically and any issues addressed immediately?	Yes ☐	No ☐	N/A ☒
Signage and labeling comply with RCRA requirements for all staging areas and containers?	Yes ☐	No ☐	N/A ☒
If any issues noted, has Contractor been notified?	Yes ☐	No ☐	N/A ☒
<u>Comments:</u> 			

NUISANCE CHECKLIST

Were there any community complaints related to work on this date?	Yes ☐	No ☒	N/A ☐
Were there any odors detected on this date?	Yes ☐	No ☒	N/A ☐
Was noise outside specification and/or above background on this date?	Yes ☐	No ☒	N/A ☐
Were vibration readings outside specification and/or above background on this date?	Yes ☐	No ☒	N/A ☐
Any visible dust observed beyond the work perimeter on this date?	Yes ☐	No ☒	N/A ☐
Any visible contrast (turbidity) beyond engineering controls observed on this date?	Yes ☐	No ☒	N/A ☐
Was turbidity checked at the outfall(s)?	AM ☐	PM ☐	N/A ☒
Were any property owners NOT provided advance notice for work performed on this property on this date?	Yes ☐	No ☒	N/A ☐
Was the temporary fabric structure closed at the end of the day?	Yes ☐	No ☐	N/A ☒
Has Contractor failed to protect all foundations and structures adjacent to and adjoining the site which are affected by the excavations or other operations connected with performance of the Work?	Yes ☐	No ☐	N/A ☒
If yes, has Contractor been notified?	Yes ☐	No ☐	N/A ☒

DAILY INSPECTION REPORT - No. 06
Former NOW Corporation Facility No. 314008

Date: 08/20/2024

Comments:

RESILIENCE/GREEN REMEDIATION CHECKLIST

Is site power procured from renewable energy sources (e.g., solar, wind, geothermal, biomass and biogas)?	Yes ☐	No ☒	N/A ☐
Is the Contractor employing 2007 or newer or retrofitted (BART*) diesel on-road trucks and non-road equipment?	Yes ☐	No ☐	N/A ☒
Is vehicle idling adequately reduced per 6NYCRR Part 217-3?	Yes ☒	No ☐	N/A ☐
Have equipment operators been trained in the idling requirements of 6NYCRR Part 217-3?	Yes ☐	No ☐	N/A ☒
Is BART-equipped equipment properly maintained and working?	Yes ☐	No ☐	N/A ☒
Is work being sequenced to avoid double handling?	Yes ☐	No ☐	N/A ☒
Is there an onsite recycling program for CONTRACTOR-generated wastes and is it complied with?	Yes ☐	No ☐	N/A ☒
Are office trailer heating and cooling systems maintained at efficient set points, have programable thermostats been installed?	Yes ☐	No ☐	N/A ☒
Are products and materials used in performance of the work appropriately certified (e.g., LEED, Energy Star, Sustainable Forestry Initiative®, etc.)?	Yes ☐	No ☐	N/A ☒
Are resiliency features included in the design, or completed remedy properly installed and/or maintained (flood control, storm water controls, erosion measures, etc.)?	Yes ☐	No ☐	N/A ☒
Are green remediation elements included in the design, or completed remedy properly installed and/or maintained (e.g., porous pavement, geothermal, variable speed drives, native plantings, natural stream bank restoration, etc.)?	Yes ☐	No ☐	N/A ☒
Are appropriate metrics documented for inclusion on Form A, Summary of Green Remediation Metrics, by the CONTRACTOR?	Yes ☐	No ☐	N/A ☒
Has Contractor been notified of any deficiencies?	Yes ☐	No ☐	N/A ☒
<u>Comments:</u>			

* BART – Best Available Retrofit Technology

DAILY INSPECTION REPORT - No. 07
Former NOW Corporation Facility No. 314008

Date: 08/21/2024

NYSDEC Division of Environmental Remediation				Contract No. D009803-19 DEC PM – Payson Long Consultant PM – Lindsay Mitchell Consultant Inspector – Mike Izdebski	
Site Location: 2092 Route 9G, Clinton, Dutchess County, New York					
Weather Conditions					
General Description	Partly cloudy	AM	Partly cloudy	PM	
Temperature	49	AM	74	PM	
Wind	Breezy	AM	Breezy	PM	
Health & Safety If any box below is checked “Yes”, provide explanation under “Health & Safety Comments”.					
Were there any changes to the Health & Safety Plan?				*Yes	No
Were there any exceedances of the perimeter air monitoring reported on this date?				*Yes	No
Were there any nuisance issues reported/observed on this date?				*Yes	No
Health & Safety Comments Tailgate meeting in the morning. Reviewed THAs					
Summary of Work Performed		Arrived at site:	0800	Departed Site:	1800
- AECOM began installing soil vapor sampling points, completing a total of 71 locations at points specified in the attached figure (work area shaded in orange). All 15-foot spacing locations (blue points) were completed, along with some of the 30-foot spacing locations (orange points). - AECOM surveyed locations of installed soil vapor samples with a hand-held GPS unit. - AECOM continued marking out soil vapor sampling point locations. - AECOM collected CAMP data.					
Equipment/Material Tracking If any box below is checked “Yes”, provide explanation under “Material Tracking Comments”.					
Were there any vehicles which did not display proper D.O.T numbers and placards?				*Yes	No
Were there any vehicles which were not tarped?				* Yes	No
Were there any vehicles which were not decontaminated prior to exiting the work site?				* Yes	No
Personnel and Equipment					
Individual	Company	Trade	Total Hours		
Michael Izdebski	AECOM	Geologist	10		
Chris French	AECOM	Geologist	10		
Andrew Dietz	AECOM	Geologist	10		
Steve Gray	AECOM	Senior Technician	10		
Equipment Description	Contractor/Vendor	Quantity	Used		
Hammer Drill	AECOM	2	Yes		
Generator	AECOM	1	Yes		
Trimble GPS	Waypoint Technology Group, LLC	1	Yes		
CAMP Units	Pine Environmental	2	Yes		
PID	Pine Environmental	1	Yes		

DAILY INSPECTION REPORT - No. 07

Former NOW Corporation Facility No. 314008

Date: 08/21/2024

[illegible]

*On-Site scale for off-site shipment, delivery ticket for material received

Equipment/Material Tracking Comments:

Visitors to Site

[illegible]

Site Representatives

Name	Representing



Department of
Environmental
Conservation

Project Schedule Comments

Anticipated completion date for soil gas sample installation is 08/23/2024.


Issues Pending

None

Interaction with Public, Property Owners, Media, etc.

AECOM field staff checked in with the property owner during the day and provided updates on work activities for the week.

Include (insert) figures with markups showing location of work and job progress



Site Photographs (Descriptions Below)



AECOM employee hammer drilling to prepare ground for soil vapor passive sampling point.



AECOM employee inserting soil vapor sampling media in the ground.



AECOM employee GPS surveying sampling locations.



AECOM employees installing soil vapor sampling media.

DAILY INSPECTION REPORT - No. 07
Former NOW Corporation Facility No. 314008

Date: 08/21/2024

	
Soil vapor sampling points were marked with spray paint and/or flagged depending upon surface material.	View of soil vapor sampling location spacing (see flags).
Site Inspector(s): Michael Izdebski (AECOM)	Date: 08/21/2024

Videos of discreet operations have been provided to the DEC Project Manager to facilitate understanding of the ongoing work? Yes ☐

REMEDIAL ACTIVITIES AT PROPERTIES

On-Site Waste Storage

Drums, roll offs and piles are staged in secure areas?	Yes ☒	No ☐	N/A ☐
Liners and berms have been installed if necessary to prevent cross contamination of clean areas?	Yes ☐	No ☐	N/A ☒
Containers are in good condition or properly overpacked?	Yes ☒	No ☐	N/A ☐
Waste materials are scheduled to be properly characterized and disposed of prior to demobilization?	Yes ☒	No ☐	N/A ☐
Complying with RCRA 90 day storage limitation for hazardous waste?	Yes ☐	No ☐	N/A ☒
Piles are securely covered when not in use?	Yes ☐	No ☐	N/A ☒
Containers are closed when not in use?	Yes ☒	No ☐	N/A ☐
Staging areas should be inspected periodically and any issues addressed immediately?	Yes ☒	No ☐	N/A ☐
Signage and labeling comply with RCRA requirements for all staging areas and containers?	Yes ☐	No ☐	N/A ☒
If any issues noted, has Contractor been notified?	Yes ☐	No ☐	N/A ☒
<u>Comments:</u> 			

NUISANCE CHECKLIST

Were there any community complaints related to work on this date?	Yes ☐	No ☒	N/A ☐
Were there any odors detected on this date?	Yes ☐	No ☒	N/A ☐
Was noise outside specification and/or above background on this date?	Yes ☐	No ☒	N/A ☐
Were vibration readings outside specification and/or above background on this date?	Yes ☐	No ☒	N/A ☐
Any visible dust observed beyond the work perimeter on this date?	Yes ☐	No ☒	N/A ☐
Any visible contrast (turbidity) beyond engineering controls observed on this date?	Yes ☐	No ☒	N/A ☐
Was turbidity checked at the outfall(s)?	AM ☐	PM ☐	N/A ☒
Were any property owners NOT provided advance notice for work performed on this property on this date?	Yes ☐	No ☒	N/A ☐
Was the temporary fabric structure closed at the end of the day?	Yes ☐	No ☐	N/A ☒
Has Contractor failed to protect all foundations and structures adjacent to and adjoining the site which are affected by the excavations or other operations connected with performance of the Work?	Yes ☐	No ☐	N/A ☒
If yes, has Contractor been notified?	Yes ☐	No ☐	N/A ☒

DAILY INSPECTION REPORT - No. 07
Former NOW Corporation Facility No. 314008

Date: 08/21/2024

Comments:

RESILIENCE/GREEN REMEDIATION CHECKLIST

Is site power procured from renewable energy sources (e.g., solar, wind, geothermal, biomass and biogas)?	Yes ☐	No ☒	N/A ☐
Is the Contractor employing 2007 or newer or retrofitted (BART*) diesel on-road trucks and non-road equipment?	Yes ☐	No ☐	N/A ☒
Is vehicle idling adequately reduced per 6NYCRR Part 217-3?	Yes ☒	No ☐	N/A ☐
Have equipment operators been trained in the idling requirements of 6NYCRR Part 217-3?	Yes ☐	No ☐	N/A ☒
Is BART-equipped equipment properly maintained and working?	Yes ☐	No ☐	N/A ☒
Is work being sequenced to avoid double handling?	Yes ☐	No ☐	N/A ☒
Is there an onsite recycling program for CONTRACTOR-generated wastes and is it complied with?	Yes ☐	No ☐	N/A ☒
Are office trailer heating and cooling systems maintained at efficient set points, have programable thermostats been installed?	Yes ☐	No ☐	N/A ☒
Are products and materials used in performance of the work appropriately certified (e.g., LEED, Energy Star, Sustainable Forestry Initiative®, etc.)?	Yes ☐	No ☐	N/A ☒
Are resiliency features included in the design, or completed remedy properly installed and/or maintained (flood control, storm water controls, erosion measures, etc.)?	Yes ☐	No ☐	N/A ☒
Are green remediation elements included in the design, or completed remedy properly installed and/or maintained (e.g., porous pavement, geothermal, variable speed drives, native plantings, natural stream bank restoration, etc.)?	Yes ☐	No ☐	N/A ☒
Are appropriate metrics documented for inclusion on Form A, Summary of Green Remediation Metrics, by the CONTRACTOR?	Yes ☐	No ☐	N/A ☒
Has Contractor been notified of any deficiencies?	Yes ☐	No ☐	N/A ☒
<u>Comments:</u>			

* BART – Best Available Retrofit Technology

DAILY INSPECTION REPORT - No. 08
Former NOW Corporation Facility No. 314008

Date: 08/22/2024

NYSDEC Division of Environmental Remediation				Contract No. D009803-19 DEC PM – Payson Long Consultant PM – Lindsay Mitchell Consultant Inspector – Mike Izdebski	
Site Location: 2092 Route 9G, Clinton, Dutchess County, New York					
Weather Conditions					
General Description	Sunny	AM	Sunny	PM	
Temperature	49°F	AM	75°F	PM	
Wind	Breezy	AM	Breezy	PM	
Health & Safety If any box below is checked “Yes”, provide explanation under “Health & Safety Comments”.					
Were there any changes to the Health & Safety Plan?				*Yes	No
Were there any exceedances of the perimeter air monitoring reported on this date?				*Yes	No
Were there any nuisance issues reported/observed on this date?				*Yes	No
Health & Safety Comments Tailgate health and safety meeting in the morning.					
Summary of Work Performed		Arrived at site:	0800	Departed Site:	1800
- AECOM continued installing soil vapor sampling points, completing an additional 63 locations at 30-foot spacing intervals. 134 total soil vapor point locations have been installed to date. - AECOM surveyed locations of installed soil vapor samples with Trimble GPS unit. - AECOM continued marking out soil vapor locations. - AECOM collected CAMP data.					
Equipment/Material Tracking If any box below is checked “Yes”, provide explanation under “Material Tracking Comments”.					
Were there any vehicles which did not display proper D.O.T numbers and placards?				*Yes	No
Were there any vehicles which were not tarped?				* Yes	No
Were there any vehicles which were not decontaminated prior to exiting the work site?				* Yes	No
Personnel and Equipment					
Individual	Company	Trade	Total Hours		
Michael Izdebski	AECOM	Geologist	10		
Steve Gray	AECOM	Senior Technician	10		
Andrew Dietz	AECOM	Geologist	10		
Ray Heller	AECOM	Environmental Engineer	10		
Equipment Description	Contractor/Vendor	Quantity	Used		
Hammer Drill	AECOM	2	Yes		
Generator	AECOM	1	Yes		
Trimble GPS	Waypoint Technology Group, LLC	1	Yes		
CAMP Stations (PIDs and DustTraks)	Pine Environmental	2	Yes		
PID	Pine Environmental	1	Yes		

DAILY INSPECTION REPORT - No. 08

Former NOW Corporation Facility No. 314008

Date: 08/22/2024

[illegible]

*On-Site scale for off-site shipment, delivery ticket for material received

Equipment/Material Tracking Comments:

Visitors to Site

[illegible]

Site Representatives

Name	Representing



Department of
Environmental
Conservation

Project Schedule Comments

Anticipated completion date for soil gas sample installation is 08/23/2024.


Issues Pending


None

Interaction with Public, Property Owners, Media, etc.

AECOM field staff checked in with the property owner during the day and provided updates on work activities for the week.

Include (insert) figures with markups showing location of work and job progress



Site Photographs (Descriptions Below)	
	
AECOM employee presenting two samplers, one with a sampling cap (black) and the other with a shipping cap (white).	AECOM employee inserting soil vapor sampler into pipe.
	
Surface markings following the installation and surveying of soil vapor sampling media.	Handheld PID unit used to read headspace of subsurface installation points following hammer drilling activities.

DAILY INSPECTION REPORT - No. 08
Former NOW Corporation Facility No. 314008

Date: 08/22/2024



AECOM employee mixing a batch of concrete for use as a seal above soil vapor sampling media installed in concrete.



CAMP unit setup during field activities.

Site Inspector(s): Michael Izdebski (AECOM)

Date: 08/22/2024

Videos of discreet operations have been provided to the DEC Project Manager to facilitate understanding of the ongoing work? Yes ☐

REMEDIAL ACTIVITIES AT PROPERTIES

On-Site Waste Storage

Drums, roll offs and piles are staged in secure areas?	Yes ☒	No ☐	N/A ☐
Liners and berms have been installed if necessary to prevent cross contamination of clean areas?	Yes ☐	No ☐	N/A ☒
Containers are in good condition or properly overpacked?	Yes ☒	No ☐	N/A ☐
Waste materials are scheduled to be properly characterized and disposed of prior to demobilization?	Yes ☒	No ☐	N/A ☐
Complying with RCRA 90 day storage limitation for hazardous waste?	Yes ☐	No ☐	N/A ☒
Piles are securely covered when not in use?	Yes ☐	No ☐	N/A ☒
Containers are closed when not in use?	Yes ☒	No ☐	N/A ☐
Staging areas should be inspected periodically and any issues addressed immediately?	Yes ☒	No ☐	N/A ☐
Signage and labeling comply with RCRA requirements for all staging areas and containers?	Yes ☐	No ☐	N/A ☒
If any issues noted, has Contractor been notified?	Yes ☐	No ☐	N/A ☒
<u>Comments:</u> 			

NUISANCE CHECKLIST

Were there any community complaints related to work on this date?	Yes ☐	No ☒	N/A ☐
Were there any odors detected on this date?	Yes ☐	No ☒	N/A ☐
Was noise outside specification and/or above background on this date?	Yes ☐	No ☒	N/A ☐
Were vibration readings outside specification and/or above background on this date?	Yes ☐	No ☒	N/A ☐
Any visible dust observed beyond the work perimeter on this date?	Yes ☐	No ☒	N/A ☐
Any visible contrast (turbidity) beyond engineering controls observed on this date?	Yes ☐	No ☒	N/A ☐
Was turbidity checked at the outfall(s)?	AM ☐	PM ☐	N/A ☒
Were any property owners NOT provided advance notice for work performed on this property on this date?	Yes ☐	No ☒	N/A ☐
Was the temporary fabric structure closed at the end of the day?	Yes ☐	No ☐	N/A ☒
Has Contractor failed to protect all foundations and structures adjacent to and adjoining the site which are affected by the excavations or other operations connected with performance of the Work?	Yes ☐	No ☐	N/A ☒
If yes, has Contractor been notified?	Yes ☐	No ☐	N/A ☒

DAILY INSPECTION REPORT - No. 08
Former NOW Corporation Facility No. 314008

Date: 08/22/2024

Comments:

RESILIENCE/GREEN REMEDIATION CHECKLIST

Is site power procured from renewable energy sources (e.g., solar, wind, geothermal, biomass and biogas)?	Yes ☐	No ☒	N/A ☐
Is the Contractor employing 2007 or newer or retrofitted (BART*) diesel on-road trucks and non-road equipment?	Yes ☐	No ☐	N/A ☒
Is vehicle idling adequately reduced per 6NYCRR Part 217-3?	Yes ☒	No ☐	N/A ☐
Have equipment operators been trained in the idling requirements of 6NYCRR Part 217-3?	Yes ☐	No ☐	N/A ☒
Is BART-equipped equipment properly maintained and working?	Yes ☐	No ☐	N/A ☒
Is work being sequenced to avoid double handling?	Yes ☐	No ☐	N/A ☒
Is there an onsite recycling program for CONTRACTOR-generated wastes and is it complied with?	Yes ☐	No ☐	N/A ☒
Are office trailer heating and cooling systems maintained at efficient set points, have programable thermostats been installed?	Yes ☐	No ☐	N/A ☒
Are products and materials used in performance of the work appropriately certified (e.g., LEED, Energy Star, Sustainable Forestry Initiative®, etc.)?	Yes ☐	No ☐	N/A ☒
Are resiliency features included in the design, or completed remedy properly installed and/or maintained (flood control, storm water controls, erosion measures, etc.)?	Yes ☐	No ☐	N/A ☒
Are green remediation elements included in the design, or completed remedy properly installed and/or maintained (e.g., porous pavement, geothermal, variable speed drives, native plantings, natural stream bank restoration, etc.)?	Yes ☐	No ☐	N/A ☒
Are appropriate metrics documented for inclusion on Form A, Summary of Green Remediation Metrics, by the CONTRACTOR?	Yes ☐	No ☐	N/A ☒
Has Contractor been notified of any deficiencies?	Yes ☐	No ☐	N/A ☒
<u>Comments:</u>			

* BART – Best Available Retrofit Technology

DAILY INSPECTION REPORT - No. 09
Former NOW Corporation Facility No. 314008

Date: 08/23/2024

NYSDEC Division of Environmental Remediation				Contract No. D009803-19 DEC PM – Payson Long Consultant PM – Lindsay Mitchell Consultant Inspector – Mike Izdebski	
Site Location: 2092 Route 9G, Clinton, Dutchess County, New York					
Weather Conditions					
General Description	Sunny	AM	Sunny	PM	
Temperature	50°F	AM	79°F	PM	
Wind	Calm	AM	Calm	PM	
Health & Safety If any box below is checked “Yes”, provide explanation under “Health & Safety Comments”.					
Were there any changes to the Health & Safety Plan?				*Yes	No
Were there any exceedances of the perimeter air monitoring reported on this date?				*Yes	No
Were there any nuisance issues reported/observed on this date?				*Yes	No
Health & Safety Comments Tailgate health and safety meeting in the morning.					
Summary of Work Performed		Arrived at site:	0800	Departed Site:	1530
- AECOM completed installing soil vapor sampling points, totaling 191 locations over the course of three days. Nine locations were relocated either due to an inability to clear utilities or immovable obstructions. Locations were chosen based on observable data gaps in the field or near areas of elevated PID headspace readings. - AECOM surveyed locations of installed soil vapor samples with Trimble GPS unit. - AECOM collected CAMP data. - AECOM demobilized off-site.					
Equipment/Material Tracking If any box below is checked “Yes”, provide explanation under “Material Tracking Comments”.					
Were there any vehicles which did not display proper D.O.T numbers and placards?				*Yes	No
Were there any vehicles which were not tarped?				* Yes	No
Were there any vehicles which were not decontaminated prior to exiting the work site?				* Yes	No
Personnel and Equipment					
Individual	Company	Trade	Total Hours		
Michael Izdebski	AECOM	Geologist	7.5		
Steve Gray	AECOM	Senior Technician	7.5		
Andrew Dietz	AECOM	Geologist	7.25		
Ray Heller	AECOM	Environmental Engineer	7.25		
Equipment Description	Contractor/Vendor	Quantity	Used		
Hammer Drill	AECOM	2	Yes		
Generator	AECOM	1	Yes		
Trimble GPS	Waypoint Technology Group, LLC	1	Yes		
CAMP Stations (PIDs and DustTraks)	Pine Environmental	2	Yes		
PID	Pine Environmental	1	Yes		
Metal Detector	AECOM	1	Yes		

DAILY INSPECTION REPORT - No. 09
Former NOW Corporation Facility No. 314008

Date: 08/23/2024

[illegible]

*On-Site scale for off-site shipment, delivery ticket for material received

Equipment/Material Tracking Comments:

Visitors to Site

[illegible]

Site Representatives

Name	Representing



Department of
Environmental
Conservation

Project Schedule Comments

Soil gas sample installation complete.


Issues Pending

None

Interaction with Public, Property Owners, Media, etc.

AECOM field staff checked in with the property owner at the end of the day, updating them on project status.

Include (insert) figures with markups showing location of work and job progress



Site Photographs (Descriptions Below)



AECOM employee installing soil vapor sample media.



AECOM employee surveying soil vapor sample location.



AECOM employee drilling hole for soil vapor sample media installation.



AECOM employee marking soil vapor sample location following installation.

DAILY INSPECTION REPORT - No. 09
Former NOW Corporation Facility No. 314008

Date: 08/23/2024



Location "J0" was added to the southwest portion of the property due to an immovable obstruction at another proposed location.



Location "J00" was added to the southwest portion of the property due to an immovable obstruction at another proposed location.

Site Inspector(s): Michael Izdebski (AECOM)

Date: 08/23/2024

Videos of discreet operations have been provided to the DEC Project Manager to facilitate understanding of the ongoing work? Yes ☐

REMEDIAL ACTIVITIES AT PROPERTIES

On-Site Waste Storage

Drums, roll offs and piles are staged in secure areas?	Yes ☒	No ☐	N/A ☐
Liners and berms have been installed if necessary to prevent cross contamination of clean areas?	Yes ☐	No ☐	N/A ☒
Containers are in good condition or properly overpacked?	Yes ☒	No ☐	N/A ☐
Waste materials are scheduled to be properly characterized and disposed of prior to demobilization?	Yes ☒	No ☐	N/A ☐
Complying with RCRA 90 day storage limitation for hazardous waste?	Yes ☐	No ☐	N/A ☒
Piles are securely covered when not in use?	Yes ☐	No ☐	N/A ☒
Containers are closed when not in use?	Yes ☒	No ☐	N/A ☐
Staging areas should be inspected periodically and any issues addressed immediately?	Yes ☒	No ☐	N/A ☐
Signage and labeling comply with RCRA requirements for all staging areas and containers?	Yes ☐	No ☐	N/A ☒
If any issues noted, has Contractor been notified?	Yes ☐	No ☐	N/A ☒
<u>Comments:</u> 			

NUISANCE CHECKLIST

Were there any community complaints related to work on this date?	Yes ☐	No ☒	N/A ☐
Were there any odors detected on this date?	Yes ☐	No ☒	N/A ☐
Was noise outside specification and/or above background on this date?	Yes ☐	No ☒	N/A ☐
Were vibration readings outside specification and/or above background on this date?	Yes ☐	No ☒	N/A ☐
Any visible dust observed beyond the work perimeter on this date?	Yes ☐	No ☒	N/A ☐
Any visible contrast (turbidity) beyond engineering controls observed on this date?	Yes ☐	No ☒	N/A ☐
Was turbidity checked at the outfall(s)?	AM ☐	PM ☐	N/A ☒
Were any property owners NOT provided advance notice for work performed on this property on this date?	Yes ☐	No ☒	N/A ☐
Was the temporary fabric structure closed at the end of the day?	Yes ☐	No ☐	N/A ☒
Has Contractor failed to protect all foundations and structures adjacent to and adjoining the site which are affected by the excavations or other operations connected with performance of the Work?	Yes ☐	No ☐	N/A ☒
If yes, has Contractor been notified?	Yes ☐	No ☐	N/A ☒

DAILY INSPECTION REPORT - No. 09
Former NOW Corporation Facility No. 314008

Date: 08/23/2024

Comments:

RESILIENCE/GREEN REMEDIATION CHECKLIST

Is site power procured from renewable energy sources (e.g., solar, wind, geothermal, biomass and biogas)?	Yes ☐	No ☒	N/A ☐
Is the Contractor employing 2007 or newer or retrofitted (BART*) diesel on-road trucks and non-road equipment?	Yes ☐	No ☐	N/A ☒
Is vehicle idling adequately reduced per 6NYCRR Part 217-3?	Yes ☒	No ☐	N/A ☐
Have equipment operators been trained in the idling requirements of 6NYCRR Part 217-3?	Yes ☐	No ☐	N/A ☒
Is BART-equipped equipment properly maintained and working?	Yes ☐	No ☐	N/A ☒
Is work being sequenced to avoid double handling?	Yes ☐	No ☐	N/A ☒
Is there an onsite recycling program for CONTRACTOR-generated wastes and is it complied with?	Yes ☐	No ☐	N/A ☒
Are office trailer heating and cooling systems maintained at efficient set points, have programable thermostats been installed?	Yes ☐	No ☐	N/A ☒
Are products and materials used in performance of the work appropriately certified (e.g., LEED, Energy Star, Sustainable Forestry Initiative®, etc.)?	Yes ☐	No ☐	N/A ☒
Are resiliency features included in the design, or completed remedy properly installed and/or maintained (flood control, storm water controls, erosion measures, etc.)?	Yes ☐	No ☐	N/A ☒
Are green remediation elements included in the design, or completed remedy properly installed and/or maintained (e.g., porous pavement, geothermal, variable speed drives, native plantings, natural stream bank restoration, etc.)?	Yes ☐	No ☐	N/A ☒
Are appropriate metrics documented for inclusion on Form A, Summary of Green Remediation Metrics, by the CONTRACTOR?	Yes ☐	No ☐	N/A ☒
Has Contractor been notified of any deficiencies?	Yes ☐	No ☐	N/A ☒
<u>Comments:</u>			

* BART – Best Available Retrofit Technology

DAILY INSPECTION REPORT - No. 10
Former NOW Corporation Facility No. 314008

Date: 09/04/2024

NYSDEC Division of Environmental Remediation				Contract No. D009803-19 DEC PM – Payson Long Consultant PM – Lindsay Mitchell Consultant Inspector – Mike Izdebski	
Site Location: 2092 Route 9G, Clinton, Dutchess County, New York					
Weather Conditions					
General Description	Sunny	AM	Sunny	PM	
Temperature	53°F	AM	76°F	PM	
Wind	Calm	AM	Breezy	PM	
Health & Safety If any box below is checked “Yes”, provide explanation under “Health & Safety Comments”.					
Were there any changes to the Health & Safety Plan?				*Yes	(No)
Were there any exceedances of the perimeter air monitoring reported on this date?				*Yes	(No) (NA)
Were there any nuisance issues reported/observed on this date?				*Yes	(No) (NA)
Health & Safety Comments Tailgate meeting in the morning.					
Summary of Work Performed		Arrived at site:	0800	Departed Site:	1900
- AECOM collected soil gas passive sampling vials from 170 of the 191 locations. All piping, tin foil, wiring and flagging was disposed of with municipal waste. - Completed locations were backfilled with bentonite and restored to grade.					
Equipment/Material Tracking If any box below is checked “Yes”, provide explanation under “Material Tracking Comments”.					
Were there any vehicles which did not display proper D.O.T numbers and placards?				*Yes	(No) (NA)
Were there any vehicles which were not tarped?				* Yes	(No) (NA)
Were there any vehicles which were not decontaminated prior to exiting the work site?				* Yes	(No) (NA)
Personnel and Equipment					
Individual	Company	Trade	Total Hours		
Michael Izdebski	AECOM	Geologist	10.5		
Steve Gray	AECOM	Senior Technician	11.0		
Ray Heller	AECOM	Environmental Engineer	11.0		
Equipment Description	Contractor/Vendor	Quantity	Used		
Metal Detector	AECOM	1	Yes		

DAILY INSPECTION REPORT - No. 10

Former NOW Corporation Facility No. 314008

Date: 09/04/2024

[illegible]

*On-Site scale for off-site shipment, delivery ticket for material received

Equipment/Material Tracking Comments:

Visitors to Site

[illegible]

Site Representatives

Name	Representing



Department of
Environmental
Conservation

Project Schedule Comments

Anticipated soil gas sampling vial removal/site restoration completion date is 09/05/2024.


Issues Pending

None

Interaction with Public, Property Owners, Media, etc.

AECOM field staff checked in with the property owner.

Include (insert) figures with markups showing location of work and job progress



Site Photographs (Descriptions Below)



AECOM employee uncovering soil gas passive sampling location.



AECOM employee using bull point to chip through concrete seal at soil gas sample location.



AECOM employee cleaning soil gas sample vial with provided gauze.



AECOM employees removing all flagging, piping, wiring, and tin foil for disposal.



AECOM employee backfilling soil gas sample locations with bentonite chips.



AECOM employee(s) capped soil gas samples with solid caps and labeled them using a ballpoint pen.

Site Inspector(s): Michael Izdebski (AECOM)

Date: 09/04/2024

Videos of discreet operations have been provided to the DEC Project Manager to facilitate understanding of the ongoing work? Yes ☐

REMEDIAL ACTIVITIES AT PROPERTIES

On-Site Waste Storage

Drums, roll offs and piles are staged in secure areas?	Yes ☒	No ☐	N/A ☐
Liners and berms have been installed if necessary to prevent cross contamination of clean areas?	Yes ☐	No ☐	N/A ☒
Containers are in good condition or properly overpacked?	Yes ☒	No ☐	N/A ☐
Waste materials are scheduled to be properly characterized and disposed of prior to demobilization?	Yes ☒	No ☐	N/A ☐
Complying with RCRA 90 day storage limitation for hazardous waste?	Yes ☐	No ☐	N/A ☒
Piles are securely covered when not in use?	Yes ☐	No ☐	N/A ☒
Containers are closed when not in use?	Yes ☒	No ☐	N/A ☐
Staging areas should be inspected periodically and any issues addressed immediately?	Yes ☒	No ☐	N/A ☐
Signage and labeling comply with RCRA requirements for all staging areas and containers?	Yes ☐	No ☐	N/A ☒
If any issues noted, has Contractor been notified?	Yes ☐	No ☐	N/A ☒
<u>Comments:</u> 			

NUISANCE CHECKLIST

Were there any community complaints related to work on this date?	Yes ☐	No ☒	N/A ☐
Were there any odors detected on this date?	Yes ☐	No ☒	N/A ☐
Was noise outside specification and/or above background on this date?	Yes ☐	No ☒	N/A ☐
Were vibration readings outside specification and/or above background on this date?	Yes ☐	No ☒	N/A ☐
Any visible dust observed beyond the work perimeter on this date?	Yes ☐	No ☒	N/A ☐
Any visible contrast (turbidity) beyond engineering controls observed on this date?	Yes ☐	No ☒	N/A ☐
Was turbidity checked at the outfall(s)?	AM ☐	PM ☐	N/A ☒
Were any property owners NOT provided advance notice for work performed on this property on this date?	Yes ☐	No ☒	N/A ☐
Was the temporary fabric structure closed at the end of the day?	Yes ☐	No ☐	N/A ☒
Has Contractor failed to protect all foundations and structures adjacent to and adjoining the site which are affected by the excavations or other operations connected with performance of the Work?	Yes ☐	No ☐	N/A ☒
If yes, has Contractor been notified?	Yes ☐	No ☐	N/A ☒

DAILY INSPECTION REPORT - No. 10
Former NOW Corporation Facility No. 314008

Date: 09/04/2024

Comments:

RESILIENCE/GREEN REMEDIATION CHECKLIST

Is site power procured from renewable energy sources (e.g., solar, wind, geothermal, biomass and biogas)?	Yes ☐	No ☒	N/A ☐
Is the Contractor employing 2007 or newer or retrofitted (BART*) diesel on-road trucks and non-road equipment?	Yes ☐	No ☐	N/A ☒
Is vehicle idling adequately reduced per 6NYCRR Part 217-3?	Yes ☒	No ☐	N/A ☐
Have equipment operators been trained in the idling requirements of 6NYCRR Part 217-3?	Yes ☐	No ☐	N/A ☒
Is BART-equipped equipment properly maintained and working?	Yes ☐	No ☐	N/A ☒
Is work being sequenced to avoid double handling?	Yes ☐	No ☐	N/A ☒
Is there an onsite recycling program for CONTRACTOR-generated wastes and is it complied with?	Yes ☐	No ☐	N/A ☒
Are office trailer heating and cooling systems maintained at efficient set points, have programable thermostats been installed?	Yes ☐	No ☐	N/A ☒
Are products and materials used in performance of the work appropriately certified (e.g., LEED, Energy Star, Sustainable Forestry Initiative®, etc.)?	Yes ☐	No ☐	N/A ☒
Are resiliency features included in the design, or completed remedy properly installed and/or maintained (flood control, storm water controls, erosion measures, etc.)?	Yes ☐	No ☐	N/A ☒
Are green remediation elements included in the design, or completed remedy properly installed and/or maintained (e.g., porous pavement, geothermal, variable speed drives, native plantings, natural stream bank restoration, etc.)?	Yes ☐	No ☐	N/A ☒
Are appropriate metrics documented for inclusion on Form A, Summary of Green Remediation Metrics, by the CONTRACTOR?	Yes ☐	No ☐	N/A ☒
Has Contractor been notified of any deficiencies?	Yes ☐	No ☐	N/A ☒
<u>Comments:</u>			

* BART – Best Available Retrofit Technology

DAILY INSPECTION REPORT - No. 11
Former NOW Corporation Facility No. 314008

Date: 09/05/2024

NYSDEC Division of Environmental Remediation				Contract No. D009803-19 DEC PM – Payson Long Consultant PM – Lindsay Mitchell Consultant Inspector – Mike Izdebski	
Site Location: 2092 Route 9G, Clinton, Dutchess County, New York					
Weather Conditions					
General Description	Sunny	AM	Sunny	PM	
Temperature	59°F	AM	77°F	PM	
Wind	Calm	AM	Calm	PM	
Health & Safety If any box below is checked “Yes”, provide explanation under “Health & Safety Comments”.					
Were there any changes to the Health & Safety Plan?				*Yes	No
Were there any exceedances of the perimeter air monitoring reported on this date?				*Yes	No
Were there any nuisance issues reported/observed on this date?				*Yes	No
Health & Safety Comments					
Tailgate meeting in the morning.					
Summary of Work Performed		Arrived at Site:	0830	Departed Site:	1315
- AECOM collected soil gas passive sampling vials from the remaining 21 locations, completing all 191 locations. All piping, tin foil, wiring and flagging was disposed of with municipal waste. - Completed locations were backfilled with bentonite. - AECOM patched all project-related disturbed asphalt and concrete. - AECOM scouted bedrock locations for strike and dip survey. - AECOM shipped samples to Beacon Environmental via FedEx.					
Equipment/Material Tracking If any box below is checked “Yes”, provide explanation under “Material Tracking Comments”.					
Were there any vehicles which did not display proper D.O.T numbers and placards?				*Yes	No
Were there any vehicles which were not tarped?				* Yes	No
Were there any vehicles which were not decontaminated prior to exiting the work site?				* Yes	No
Personnel and Equipment					
Individual	Company	Trade	Total Hours		
Michael Izdebski	AECOM	Geologist	4.75		
Ray Heller	AECOM	Environmental Engineer	4.75		
Equipment Description	Contractor/Vendor	Quantity	Used		
Metal Detector	AECOM	1	No		

DAILY INSPECTION REPORT - No. 11

Former NOW Corporation Facility No. 314008


Date: 09/05/2024

[illegible]

DAILY INSPECTION REPORT - No. 11
Former NOW Corporation Facility No. 314008

Date: 09/05/2024

Project Schedule Comments	
Soil gas sampling event completed.	
Issues Pending	
None	
Interaction with Public, Property Owners, Media, etc.	
AECOM field staff checked in with the property owner at the end of the day regarding project status.	



Site Photographs (Descriptions Below)	
	
Soil gas passive sampling vial broke during retrieval. Vial contents were immediately transferred to a sealed plastic bag and later transferred to a new vial.	AECOM employees patched all project-related asphalt and concrete disturbances.
	
AECOM employee removing soil gas sample.	AECOM scouted bedrock outcrops for strike and dip measurements.



AECOM placed all sealed samplers in individually labeled small plastic bags supplied by the laboratory. These bags were then placed inside a larger bag. For each large bag, one trip blank and one adsorbent pack was included.



AECOM secured sample transport kit with a custody seal.

Site Inspector(s): Michael Izdebski (AECOM)

Date: 09/05/2024

Videos of discreet operations have been provided to the DEC Project Manager to facilitate understanding of the ongoing work? Yes ☐

REMEDIAL ACTIVITIES AT PROPERTIES

On-Site Waste Storage

Drums, roll offs and piles are staged in secure areas?	Yes ☒	No ☐	N/A ☐
Liners and berms have been installed if necessary to prevent cross contamination of clean areas?	Yes ☐	No ☐	N/A ☒
Containers are in good condition or properly overpacked?	Yes ☒	No ☐	N/A ☐
Waste materials are scheduled to be properly characterized and disposed of prior to demobilization?	Yes ☒	No ☐	N/A ☐
Complying with RCRA 90 day storage limitation for hazardous waste?	Yes ☐	No ☐	N/A ☒
Piles are securely covered when not in use?	Yes ☐	No ☐	N/A ☒
Containers are closed when not in use?	Yes ☒	No ☐	N/A ☐
Staging areas should be inspected periodically and any issues addressed immediately?	Yes ☒	No ☐	N/A ☐
Signage and labeling comply with RCRA requirements for all staging areas and containers?	Yes ☐	No ☐	N/A ☒
If any issues noted, has Contractor been notified?	Yes ☐	No ☐	N/A ☒
<u>Comments:</u> 			

NUISANCE CHECKLIST

Were there any community complaints related to work on this date?	Yes ☐	No ☒	N/A ☐
Were there any odors detected on this date?	Yes ☐	No ☒	N/A ☐
Was noise outside specification and/or above background on this date?	Yes ☐	No ☒	N/A ☐
Were vibration readings outside specification and/or above background on this date?	Yes ☐	No ☒	N/A ☐
Any visible dust observed beyond the work perimeter on this date?	Yes ☐	No ☒	N/A ☐
Any visible contrast (turbidity) beyond engineering controls observed on this date?	Yes ☐	No ☒	N/A ☐
Was turbidity checked at the outfall(s)?	AM ☐	PM ☐	N/A ☒
Were any property owners NOT provided advance notice for work performed on this property on this date?	Yes ☐	No ☒	N/A ☐
Was the temporary fabric structure closed at the end of the day?	Yes ☐	No ☐	N/A ☒
Has Contractor failed to protect all foundations and structures adjacent to and adjoining the site which are affected by the excavations or other operations connected with performance of the Work?	Yes ☐	No ☐	N/A ☒
If yes, has Contractor been notified?	Yes ☐	No ☐	N/A ☒

DAILY INSPECTION REPORT - No. 11
Former NOW Corporation Facility No. 314008

Date: 09/05/2024

Comments:

RESILIENCE/GREEN REMEDIATION CHECKLIST

Is site power procured from renewable energy sources (e.g., solar, wind, geothermal, biomass and biogas)?	Yes ☐	No ☒	N/A ☐
Is the Contractor employing 2007 or newer or retrofitted (BART*) diesel on-road trucks and non-road equipment?	Yes ☐	No ☐	N/A ☒
Is vehicle idling adequately reduced per 6NYCRR Part 217-3?	Yes ☒	No ☐	N/A ☐
Have equipment operators been trained in the idling requirements of 6NYCRR Part 217-3?	Yes ☐	No ☐	N/A ☒
Is BART-equipped equipment properly maintained and working?	Yes ☐	No ☐	N/A ☒
Is work being sequenced to avoid double handling?	Yes ☐	No ☐	N/A ☒
Is there an onsite recycling program for CONTRACTOR-generated wastes and is it complied with?	Yes ☐	No ☐	N/A ☒
Are office trailer heating and cooling systems maintained at efficient set points, have programable thermostats been installed?	Yes ☐	No ☐	N/A ☒
Are products and materials used in performance of the work appropriately certified (e.g., LEED, Energy Star, Sustainable Forestry Initiative®, etc.)?	Yes ☐	No ☐	N/A ☒
Are resiliency features included in the design, or completed remedy properly installed and/or maintained (flood control, storm water controls, erosion measures, etc.)?	Yes ☐	No ☐	N/A ☒
Are green remediation elements included in the design, or completed remedy properly installed and/or maintained (e.g., porous pavement, geothermal, variable speed drives, native plantings, natural stream bank restoration, etc.)?	Yes ☐	No ☐	N/A ☒
Are appropriate metrics documented for inclusion on Form A, Summary of Green Remediation Metrics, by the CONTRACTOR?	Yes ☐	No ☐	N/A ☒
Has Contractor been notified of any deficiencies?	Yes ☐	No ☐	N/A ☒
<u>Comments:</u>			

* BART – Best Available Retrofit Technology

DAILY INSPECTION REPORT - No. 15
Former NOW Corporation Facility No. 314008

Date: 09/23/2024

NYSDEC Division of Environmental Remediation				Department of Environmental Conservation		Contract No. D009803-19 DEC PM – Payson Long Consultant PM – Lindsay Mitchell Consultant Inspector – Chris French	
Site Location: 2092 Route 9G, Clinton, Dutchess County, New York							
Weather Conditions							
General Description	Cloudy	AM	Cloudy	PM			
Temperature	64°F	AM	69°F	PM			
Wind	Calm	AM	Calm	PM			
Health & Safety If any box below is checked “Yes”, provide explanation under “Health & Safety Comments”.							
Were there any changes to the Health & Safety Plan?					*Yes	☒ No	NA
Were there any exceedances of the perimeter air monitoring reported on this date?					*Yes	No	☒ NA
Were there any nuisance issues reported/observed on this date?					*Yes	☒ No	NA
Health & Safety Comments Tailgate meeting in the morning.							
Summary of Work Performed		Arrived at Site:	1205	Departed Site:	1630		
- AECOM performed annual site inspection. - AECOM collected GPS coordinates for site monitoring wells. - AECOM collected strike and dip measurements of bedding planes from five bedrock outcrops, three of which were on-site and two of which were off-site.							
Equipment/Material Tracking If any box below is checked “Yes”, provide explanation under “Material Tracking Comments”.							
Were there any vehicles which did not display proper D.O.T numbers and placards?					*Yes	No	☒ NA
Were there any vehicles which were not tarped?					* Yes	No	☒ NA
Were there any vehicles which were not decontaminated prior to exiting the work site?					* Yes	No	☒ NA
Personnel and Equipment							
Individual	Company	Trade	Total Hours				
Chris French	AECOM	Geologist	4.5				
Andrew Dietz	AECOM	Geologist	4.5				
Steve Gray	AECOM	Technician	4.5				
Equipment Description	Contractor/Vendor			Quantity	Used		

DAILY INSPECTION REPORT - No. 15

Former NOW Corporation Facility No. 314008

Date: 09/23/2024

[illegible]

*On-Site scale for off-site shipment, delivery ticket for material received

Equipment/Material Tracking Comments:

Visitors to Site

[illegible]

Site Representatives

Name	Representing



Department of
Environmental
Conservation

DAILY INSPECTION REPORT - No. 15
Former NOW Corporation Facility No. 314008

Date: 09/23/2024

Project Schedule Comments
None
Issues Pending
None
Interaction with Public, Property Owners, Media, etc.
AECOM field staff informed property owner of work being performed on site upon arrival.
Include (insert) figures with markups showing location of work and job progress

Site Photographs (Descriptions Below)



Photo 1 – South – Outcrop #1.



Photo 2 – South – Outcrop #2.



Photo 3 – East – Outcrop #3.



Photo 4 – Southwest – Outcrop #4.



Photo 5 – Southwest – AECOM measuring strike of bedding plane in outcrop #4.



Photo 6 – Southwest – Outcrop #5.



Photo 7 – South – AECOM measuring dip of shale/greywacke interface.



Photo 8 – West – Shale/greywacke interface.



Photo 9 – West – Outcrop where shale/greywacke interface was found.

DAILY INSPECTION REPORT - No. 15
Former NOW Corporation Facility No. 314008

Date: 09/23/2024

Site Inspector(s): Chris French (AECOM)	Date: 09/23/2024

Videos of discreet operations have been provided to the DEC Project Manager to facilitate understanding of the ongoing work? Yes ☐

REMEDIAL ACTIVITIES AT PROPERTIES

On-Site Waste Storage

Drums, roll offs and piles are staged in secure areas?	Yes ☒	No ☐	N/A ☐
Liners and berms have been installed if necessary to prevent cross contamination of clean areas?	Yes ☐	No ☐	N/A ☒
Containers are in good condition or properly overpacked?	Yes ☒	No ☐	N/A ☐
Waste materials are scheduled to be properly characterized and disposed of prior to demobilization?	Yes ☐	No ☒	N/A ☐
Complying with RCRA 90 day storage limitation for hazardous waste?	Yes ☐	No ☐	N/A ☒
Piles are securely covered when not in use?	Yes ☐	No ☐	N/A ☒
Containers are closed when not in use?	Yes ☒	No ☐	N/A ☐
Staging areas should be inspected periodically and any issues addressed immediately?	Yes ☒	No ☐	N/A ☐
Signage and labeling comply with RCRA requirements for all staging areas and containers?	Yes ☐	No ☐	N/A ☒
If any issues noted, has Contractor been notified?	Yes ☐	No ☐	N/A ☒
<u>Comments:</u> Since the groundwater treatment system is not currently operational, waste drums will be sampled and removed from the site by a qualified contractor following demobilization.			

NUISANCE CHECKLIST

Were there any community complaints related to work on this date?	Yes ☐	No ☒	N/A ☐
Were there any odors detected on this date?	Yes ☐	No ☒	N/A ☐
Was noise outside specification and/or above background on this date?	Yes ☐	No ☒	N/A ☐
Were vibration readings outside specification and/or above background on this date?	Yes ☐	No ☒	N/A ☐
Any visible dust observed beyond the work perimeter on this date?	Yes ☐	No ☒	N/A ☐
Any visible contrast (turbidity) beyond engineering controls observed on this date?	Yes ☐	No ☒	N/A ☐
Was turbidity checked at the outfall(s)?	AM ☐	PM ☐	N/A ☒
Were any property owners NOT provided advance notice for work performed on this property on this date?	Yes ☐	No ☒	N/A ☐
Was the temporary fabric structure closed at the end of the day?	Yes ☐	No ☐	N/A ☒
Has Contractor failed to protect all foundations and structures adjacent to and adjoining the site which are affected by the excavations or other operations connected with performance of the Work?	Yes ☐	No ☐	N/A ☒
If yes, has Contractor been notified?	Yes ☐	No ☐	N/A ☒

DAILY INSPECTION REPORT - No. 15
Former NOW Corporation Facility No. 314008

Date: 09/23/2024

Comments:

RESILIENCE/GREEN REMEDIATION CHECKLIST

Is site power procured from renewable energy sources (e.g., solar, wind, geothermal, biomass and biogas)?	Yes ☐	No ☒	N/A ☐
Is the Contractor employing 2007 or newer or retrofitted (BART*) diesel on-road trucks and non-road equipment?	Yes ☐	No ☐	N/A ☒
Is vehicle idling adequately reduced per 6NYCRR Part 217-3?	Yes ☒	No ☐	N/A ☐
Have equipment operators been trained in the idling requirements of 6NYCRR Part 217-3?	Yes ☐	No ☐	N/A ☒
Is BART-equipped equipment properly maintained and working?	Yes ☐	No ☐	N/A ☒
Is work being sequenced to avoid double handling?	Yes ☐	No ☐	N/A ☒
Is there an onsite recycling program for CONTRACTOR-generated wastes and is it complied with?	Yes ☐	No ☐	N/A ☒
Are office trailer heating and cooling systems maintained at efficient set points, have programable thermostats been installed?	Yes ☐	No ☐	N/A ☒
Are products and materials used in performance of the work appropriately certified (e.g., LEED, Energy Star, Sustainable Forestry Initiative®, etc.)?	Yes ☐	No ☐	N/A ☒
Are resiliency features included in the design, or completed remedy properly installed and/or maintained (flood control, storm water controls, erosion measures, etc.)?	Yes ☐	No ☐	N/A ☒
Are green remediation elements included in the design, or completed remedy properly installed and/or maintained (e.g., porous pavement, geothermal, variable speed drives, native plantings, natural stream bank restoration, etc.)?	Yes ☐	No ☐	N/A ☒
Are appropriate metrics documented for inclusion on Form A, Summary of Green Remediation Metrics, by the CONTRACTOR?	Yes ☐	No ☐	N/A ☒
Has Contractor been notified of any deficiencies?	Yes ☐	No ☐	N/A ☒
<u>Comments:</u>			

* BART – Best Available Retrofit Technology

Appendix B - Enviroprobe Service, Inc. Geophysical Investigation Report



GEOPHYSICAL INVESTIGATION REPORT

PERFORMED AT:

**2092 NY-9G
Clinton, NY 12580**

PREPARED FOR:

**Lindsay Mitchell
AECOM Northeast Environment
40 British American Boulevard
Latham, NY 12110**

PREPARED BY:

**Kris Swanson
Geophysical Technician
Enviroprobe Service, Inc.
81 Marter Avenue
Mount Laurel, NJ 08054
(856) 858-8584
(800) 596-7472**

August 22, 2024

1.0 INTRODUCTION

Enviroprobe Service, Inc. (Enviroprobe) is an environmental investigation services firm which provides monitoring well installation (HSA), Geoprobe (DPT) drilling services and Environmental & Engineering Geophysics (EEG) services to the environmental consulting and engineering community.

Enviroprobe conducted a subsurface geophysical investigation at the subject property within client-specified areas of concern. Due to conditions and objectives, the investigation utilized a GSSI UtilityScan HS cart-mounted Ground Penetrating Radar (GPR) unit with a 350 MHz antenna, a Fisher TW-6 metallic locator, a Radiodetection RD7000TX3 multi-frequency transmitter, and a Radiodetection RD7000PXL receiver.

Ground penetrating radar (commonly called GPR) is a geophysical method that has been developed over the past thirty years for shallow, high-resolution, subsurface investigations of the earth. GPR uses high frequency pulsed electromagnetic waves (generally 10 MHz to 2,000 MHz) to acquire subsurface information. An EM wave is propagated downward into the ground by a transmitting antenna. Where abrupt changes in electrical properties occur in the subsurface, a portion of the energy is reflected back to the surface. This reflected wave is detected by a receiver antenna and transmitted to a control unit for real time processing and display. The penetration depth of the GSSI unit varies from several inches to tens of feet according to site-specific conditions. The penetration depth decreases with increased soil conductivity. The penetration depth is the greatest in ice, dry sands, and fine gravels. Clayey, highly saline or saturated soils, areas covered by concrete, foundry slag, or other highly conductive materials greatly reduce GPR penetration. GPR is a method that is commonly used for environmental, engineering, archaeological, and other shallow investigations.

The Fisher TW-6 metallic locator is designed to find pipes, cables and other metallic objects such as underground storage tanks (USTs). The TW-6 transmitter generates an electromagnetic field that induces electrical currents in the subsurface. These currents produce a secondary electromagnetic field that is measured by the TW-6 receiver. One surveyor can carry both the transmitter and receiver together to search for underground metallic objects, although the TW-6 response can also be affected by the electrical properties of non-metallic materials in the subsurface.

The Radiodetection (RD) transmitter and receiver are commonly used for pipe and cable locating. The multi-frequency transmitter can be directly connected, clamped, or used to induce a signal in a target line while the multi-frequency receiver is used to measure the signal from energized lines.

2.0 SCOPE OF WORK

On August 20, 2024, a geophysical technician from Enviroprobe Service Inc. was mobilized to the subject property to perform a geophysical investigation. The purpose of the investigation was to detect possible anomalies, and designate underground conduits/utilities in the client selected exterior portions of the subject property. The ground surface of the survey area consisted of asphalt, concrete, and natural soil surfaces.

3.0 SURVEY RESULTS

The survey was conducted using a cart-mounted GPR unit, a Fisher TW-6 metallic locator, and a RD unit. The RD unit was used to trace common utilities from sources in and around the survey area. The RD receiver was also used in the passive mode to search for live underground electrical power cables and other utilities emitting 60Hz electromagnetic signals. When possible, the locations of utilities were confirmed with the GPR. Designated utilities were marked on-site with spray paint using the following colors: blue – water, red – electric, orange – communications, green – sanitary sewer & storm drainage, pink – unknown utilities(See Figure Below).

The GPR and TW-6 were used in a grid pattern over all client specified areas of the site. Based on the results of the GPR and TW-6 surveys, no metallic anomalies which typically are consistent with a UST, vent piping, or product piping were detected on site (See Figure Below).




Figure 1: Designate the utilities(approximate location).

4.0 LIMITATIONS

The client-selected areas contained obstructions including containers, materials and vehicles. These objects prevented a thorough investigation of the spaces beneath and immediately adjacent to them.

Due to surface conditions and subsurface content, the GPR signal penetration was estimated at less than 4 ft in the majority of the survey area. This penetration was reduced in areas of concrete cover.

The TW-6 survey was kept up to 6 feet away from above ground objects containing metals depending on the sizes, shapes and positions of the metal objects. The TW-6 survey was not effective in areas with reinforced concrete.

Due to the dielectric properties of the subsurface, clay, plastic polymer, and fiberglass utilities may not have been detected.

All field services were conducted in compliance with the industry standard of care guidelines found in ASCE 38-02 (Level B).

5.0 WARRANTIES

The field observations and measurements reported herein are considered sufficient in detail and scope for this project. Enviroprobe Service, Inc. warrants that the findings and conclusions contained herein have been promulgated in accordance with generally accepted environmental engineering methods. There is a possibility that conditions may exist which could not be identified within the scope of this project and were not apparent during the site activities performed for this project.

Enviroprobe represents that the services were performed in a manner consistent with that level of care and skill ordinarily exercised by environmental consultants under similar circumstances. No other representations to Client, express or implied, and no warranty or guarantee is included or intended in this agreement, or in any report, document, or otherwise.

Enviroprobe Service, Inc. believes that the information provided in this report is reliable. However, Enviroprobe cannot warrant or guarantee that the information provided by others is complete or accurate. No other warranties or guarantees are implied or expressed.

GPR data is subject to signal anomalies and operator interpretation. The GPR data is intended to provide the locations of areas of concern requiring additional investigation or the approximate location of underground structures and utilities. Great care must be utilized when excavating and/or drilling around underground structures and utilities since GPR data can only be used for estimation purposes and GPR data is subject to

misinterpretation. Enviroprobe can not guarantee that utilities, post-tension cables, and/or rebar will not be incurred during drilling, cutting, coring, or excavating activities.

This report was prepared pursuant to the contract Enviroprobe has with the Client. That contractual relationship included an exchange of information about the property that was unique and between Enviroprobe and its client and serves as the basis upon which this report was prepared. Because of the importance of the communication between Enviroprobe and its client, reliance or any use of this report by anyone other than the Client, for whom it was prepared, is prohibited and therefore not foreseeable to Enviroprobe.

Reliance or use by any such third party without explicit authorization in the report does not make said third party a third party beneficiary to Enviroprobe contract with the Client. Any such unauthorized reliance on or use of this report, including any of its information or conclusions, will be at the third party's risk. For the same reasons, no warranties or representations, expressed or implied in this report, are made to any such third party.

Appendix C - Advanced Geological Services Geophysical Logging Results



3 Mystic Lane
Malvern, PA 19355
(610) 722-5500 (ph.)
(610) 722-0250 (fax)

August 25, 2024
Reference: 24-161-1

Ms. Lindsay Mitchell
AECOM
40 British American Boulevard
Latham, NY 12110

Subject: Geophysical Logging Results
Former NOW Corporation Facility
2092 Route 9G
Staatsburg, New York

Dear Ms. Mitchell:

Advanced Geological Services (AGS) is pleased to present this letter report to AECOM summarizing the results of geophysical borehole logging of six existing wells the the Former NOW Corporation Facility. Wells logged included TW-1, TW-2, TW-2A, TW-3, IW-1, and IW-2. Borehole logging activities were completed between August 6 and August 12, 2024.

The objective of geophysical logging was to characterize well conditions and identify features such as fractures or open bedding partings.

The suite of geophysical logs completed within the wells were:

- 3-arm Caliper
- Natural Gamma Ray
- Fluid Temperature
- Fluid Conductivity
- Single Point Resistance (SPR)
- Short (16-inch) and Long (64-inch) Normal Resistivity
- Spontaneous Potential (SP)
- Acoustic televiewer (ACTV)
- Optical televiewer (OPTV)
- Heat pulse flowmeter (HPF) (ambient conditions)

All logs were acquired with a Mount Sopris Matrix logging system.

1.0 RESULTS AND DISCUSSION

A suite of logs was completed in six wells to characterize well conditions and identify features such as fractures or open bedding partings. The geophysical well logs are attached to the end of this report. All wells were 8 inches in diameter and steel cased. Depths of all wells were

measure relative to the top of casing (TOC). Wells TW-1, TW-2A, and TW-3 had an outer and inner casing, and in those instances the depths were measure from the TOC of the inner steel casing. The complete suite of logs were collected in wells TW-1, TW-2, TW-2A, and TW-3.

The acoustic televiewer, optical televiewer, and heat pulse flowmeter could not be completed in wells IW-1 and IW-2 because of the presence of a metal pipe protruding into the well casings. The presence of this obstruction does not allow the ability to lower tools requiring the use of centralizers, and also creates the potential for catching and damaging the tools or the logging cable. During the initial logging of well IW-2 the caliper tool did jamb and took some effort to release and recover the tool.

The pumps in wells TW-1, TW-2A, and TW-3 were removed by AECOM personnel prior to completion of logging.

The ACTV and OPTV in conjunction with the 3-arm caliper tool were used to identify open or partially open fractures or bedding partings. The ACTV and OPTV logs also provide dip azimuth and dip angle information of interpreted fractures or partings. Only structures that appeared partially open or open were identified from the logs. Closed, tight bedding planes that did not appear to be open or partially open were not individually called out.

Heat pulse flowmeter data were collected under non-pumping, ambient conditions. The measuring range of the heat pulse flowmeter is specified by the manufacturer to be 0.03 to 1.0 gallons per minute (gpm). Flow rates of less than 0.03 gpm can sometimes be recognized, and if repeatable over several measurements, may indicate minimal flow and flow directions within the well. If measurements of less than 0.03 gpm are not repeatable over a number of measurements, then the measured response is interpreted to indicate No Flow (NF).

The logging results of of each of the wells are summarized below. All depths noted on the attached well logs and referenced below are measured from TOC.

Well TW-1

Well diameter: 8 inches

Total depth: 120.5 feet

Casing: 8-inch steel casing to 31 feet

Casing stick-up height: 2.55 feet (inner casing)

Water level: 25 feet (approximate)

Overall, the resistivity response in well TW-1 was relatively low throughout that length of the well. The resistivity and gamma curves indicate slight variations consistent with the expected from a shale or graywacke sequence. The caliper, ACTV, and OPTV do not indicate the presence of any large fractures within the well. Several small, partially open bedding plane fractures or partings were noted in the logs that generally dip steeply towards the southeast between 60° to 80°. Two other non-bedding fractures were noted in the well at depths of 73.5

and 93.2 feet. Dip azimuth and dip angle orientations of fractures identified from the ACTV and OPTV logs are summarized in Table 1.

Table 1: Well TW-1 Structure Orientations

Mean Depth of Feature (feet)	Dip Azimuth (degrees)	Dip Angle (degrees)	Feature Type
42.3	111	75	Bedding parting/fracture; partially open
46.8	139	82	Bedding parting/fracture; partially open
52.9	99	73	Bedding parting/fracture; partially open
69.3	115	69	Bedding parting/fracture; partially open
70.8	112	79	Bedding parting/fracture; partially open
71.4	118	80	Bedding parting/fracture; partially open
77.5	169	62	Fracture; partially or slightly open
89.1	118	73	Bedding parting/fracture; partially open
93.1	108	64	Bedding parting/fracture; partially open
93.2	305	54	Fracture; partially or slightly open
108.4	93	81	Bedding parting/fracture; partially open
112.3	107	80	Bedding parting/fracture; partially open
117.9	122	69	Bedding parting/fracture; partially open

Heat pulse flowmeter data were collected in TW-1 under ambient (non-pumping) conditions. No flow was detected at depth intervals between 40 feet and 90 feet. Minor but consistent upward flow below the calibrated instrument range was detected at a depth intervals of 100, 110, and 115 feet. This minor upward flow suggests that water may be migrating upward from a fracture near the bottom of the well, and exiting the borehole at the fractures between 90 and 95 feet. The tabulated heat pulse flowmeter data are summarized below in Table 2.

Table 2: Well TW-1 Ambient Heat Pulse Flowmeter Results

Depth (ft)	Flow Direction	Flow (gpm) ¹
40	--	NF
50	--	NF
60	--	NF
70	--	NF
80	--	NF
90	--	NF
100	Upward	0.010
110	Upward	0.007
115	Upward	0.008

¹ NF=No Flow. Values in orange are outside of the calibration range of the instrument and are shown for qualitative purposes only.

Well TW-2

Well diameter: 8 inches

Total depth: 160 feet

Casing: 8-inch steel casing to 16 feet

Casing stick-up height: 2.15 feet

Water level: 8.5 feet (approximate)

The natural gamma and resistivity responses in well TW-2 were of similar magnitude to those encountered in well TW-1, and are consistent with the presence of shale or fine grain graywacke. Review of the OPTV and ACTV logs indicate that the bedding orientation generally dips towards the east-southeast.

Distinct horizontal gray to dark gray banding that does not directly coincide with bedding or structures is observed in the OPTV log from a depth of approximately 115 feet to the bottom of the well. The cause of this observed banding is unknown. Light colored annealed(?) and mineralized bedding planes are also observed within the same interval. The 3-arm caliper tool indicates that the well diameter narrows from a depth of approximately 140 feet to the bottom of the well. It is possible that clayey sediment accumulated at the bottom of the well may have kept the arms of the caliper tool from opening fully when upward logging was started until it washed off, thus allowing the arms to fully extend at a depth of 140 feet.

The fluid conductivity within this well was extremely high. From the top of the water column until a depth of 45 feet the fluid conductivity was greater than 50,000 uS/cm. Below 45 feet the conductivity decreased and leveled out to approximately 2,650 uS/cm, which is still high. This conductivity response was observed during the downward and upward runs of the conductivity tool. During completion of the logging it was observed that a number of buckets containing de-icing salt were stored close to the location of well TW-2 which could be the source of the high fluid conductivity in the well, particularly if additional pallets of de-icing salt and spreading equipment are stored in this area during the winter months.

Most of the identified fractures appear to be bedding plane partings or fractures. Most of the fractures observed are noted at depths of approximately 95 feet or less. Based on the combined caliper and ACTV response, the largest potential fracture is located between 16 and 18 feet, immediately below the bottom of the casing. This fracture zone may be the result of rock breakage during drilling and installation of the casing. The depth and orientations of the identified fractures are summarized below in Table 3.

Table 3: Well TW-2 Structure Orientations

Mean Depth of Feature (feet)	Dip Azimuth (degrees)	Dip Angle (degrees)	Feature Type
17.9	0	52	Fracture; open
28.4	358	18	Bedding parting/fracture; partially open
33.1	82	55	Bedding parting/fracture; partially open
37.3	104	28	Fracture; partially or slightly open
40.0	91	61	Bedding parting/fracture; partially open
41.8	128	73	Bedding parting/fracture; partially open
43.5	34	33	Bedding parting/fracture; partially open
53.0	165	44	Bedding parting/fracture; partially open
62.6	108	74	Bedding parting/fracture; partially open
62.7	248	60	Fracture; partially or slightly open
65.7	73	73	Bedding parting/fracture; partially open
68.4	94	66	Bedding parting/fracture; partially open
75.1	94	67	Bedding parting/fracture; partially open
76.7	296	66	Fracture; partially or slightly open
82.6	89	62	Bedding parting/fracture; partially open
95.3	309	62	Fracture; partially or slightly open
116.6	89	68	Bedding parting/fracture; partially open
145.4	285	84	Fracture; discontinuous

Heat pulse flowmeter data were collected within well TW-2 under ambient conditions. Downward flow was detected at sampled intervals between the bottom of casing and a depth of 75 feet, with the exception of the interval at 65 feet, where no flow was detected. The no flow condition at the sample interval of 65 feet may be caused by the presence of fractures in close proximity to that depth. Minor upward flow outside of the calibration range of the instrument was detected in sampled depths of 85 feet and deeper. Based on the heat pulse flowmeter results, it appears the fractures situated between 60 feet and 80 feet are likely receiving water primarily from fractures above and minimally from deeper fractures. The tabulated ambient (non-pumping) heat pulse flowmeter results are provided below in Table 4.

Table 4: Well TW-2 Ambient Heat Pulse Flowmeter Results

Depth (ft)	Flow Direction	Flow (gpm) ¹
20	Downward	-0.052
30	Downward	-0.034
40	Downward	-0.029
55	Downward	-0.032
65	--	NF
75	Downward	-0.028
85	Upward	0.010
95	Upward	0.010

Depth (ft)	Flow Direction	Flow (gpm) ¹
105	Upward	0.011
125	Upward	0.010
145	Upward	0.007
155	Upward	0.007

¹ NF=No Flow. Values in orange are outside of the calibration range of the instrument and are shown for qualitative purposes only.

Well TW-2A

Well diameter: 8 inches

Total depth: 115 feet

Casing: 8-inch steel casing 20.7 feet

Casing stick-up height: 0.45 feet (inner casing)

Water level: 8 feet (approximate)

The bedding observed in well TW-2A generally dips eastward. Few bedding plane partings or bedding fractures were observed within the length of the well. Several fractures that dip westward were identified in well TW-2A, the largest being at a depth of 87.5 feet, and smaller fractures at 66.9 feet and 101.3 feet. Dip angle and dip azimuth orientations of identified fractures are summarized in Table 5.

Table 5: Well TW-2A Structure Orientations

Mean Depth of Feature (feet)	Dip Azimuth (degrees)	Dip Angle (degrees)	Feature Type
30.7	131	47	Fracture; partially or slightly open
40.9	110	74	Bedding parting/fracture; partially open
43.5	118	76	Bedding parting/fracture; partially open
46.5	143	85	Fracture; discontinuous
56.5	273	49	Fracture; partially or slightly open
58.2	275	58	Fracture; partially or slightly open
65.3	102	70	Bedding parting/fracture; partially open
66.9	287	57	Fracture; partially or slightly open
73.1	139	77	Bedding parting/fracture; partially open
87.5	273	62	Fracture; open
94.5	271	57	Fracture; partially or slightly open
101.3	283	64	Fracture; partially or slightly open
110.1	295	13	Fracture; partially or slightly open

Heat pulse flowmeter data collected in well TW-2A did not identify any upward or downward flow under ambient, non-pumping conditions. However, slight changes in the fluid conductivity observed at the fractures at depths of 87.5 feet and 101.3 feet suggests that these fractures may be capable of producing water if they were stressed by pumping of the well.

The tabulated ambient (non-pumping) heat pulse flowmeter results are provided below in Table 6.

Table 6: Well TW-2A Ambient Heat Pulse Flowmeter Results

Depth (ft)	Flow Direction	Flow (gpm) ¹
30	--	NF
40	--	NF
50	--	NF
60	--	NF
70	--	NF
80	--	NF
90	--	NF
100	--	NF
105	--	NF

¹ NF=No Flow. Values in orange are outside of the calibration range of the instrument and are shown for qualitative purposes only.

Well TW-3

Well diameter: 8 inches

Total depth: 110.5 feet

Casing: 8-inch steel casing 11 feet

Casing stick-up height: 0.9 feet (inner casing)

Water level: 9 feet (approximate)

Bedding in well TW-3 generally dips eastward throughout the length of the open wellbore. The caliper response indicates a slight increase in borehole diameter from the bottom of casing to a depth of approximately 28 feet that could indicate the presence of softer or more weathered rock within this zone. Several potential bedding plane partings or fractures were noted in the caliper, ACTV, and OPTV logs at depths shallower than 55 feet. Bedding parting or fractures were also observed between 98 and 104 feet. The dip angle and dip azimuth orientations of identified fractures are summarized in Table 7 below.

Table 7: Well TW-3 Structure Orientations

Mean Depth of Feature (feet)	Dip Azimuth (degrees)	Dip Angle (degrees)	Feature Type
20.6	92	72	Bedding parting/fracture; partially open
21.4	101	74	Bedding parting/fracture; partially open
34.2	124	67	Bedding parting/fracture; partially open
41.1	117	74	Bedding parting/fracture; partially open
45.5	120	71	Bedding parting/fracture; partially open
48.9	110	71	Bedding parting/fracture; partially open
53.5	148	74	Bedding parting/fracture; partially open
98.7	78	72	Bedding parting/fracture; partially open
102.6	103	60	Bedding parting/fracture; partially open

Heat pulse flowmeter data collected in well TW-3 indicated minor upward flow at values outside of the calibration range of the instrument between sampling depth intervals of 30 to 50 feet. These results suggest that water may be entering the wellbore at the fracture at 53.5 feet and exiting the wellbore at fractures between 20 and 23 feet deep. A slight inflection of the fluid conductivity at the fracture at 53.5 feet further indicates that water may be entering the wellbore at this depth. The tabulated ambient (non-pumping) heat pulse flowmeter results are provided below in Table 8.

Table 8: Well TW-3 Ambient Heat Pulse Flowmeter Results

Depth (ft)	Flow Direction	Flow (gpm) ¹
20	--	NF
30	Upward	0.015
40	Upward	0.009
50	Upward	0.013
60	--	NF
70	--	NF
80	--	NF
90	--	NF
100	--	NF

¹ NF=No Flow. Values in orange are outside of the calibration range of the instrument and are shown for qualitative purposes only.

Well IW-1

Well diameter: 8 inches
Total depth: 76.5 ft.
Casing: 8-inch steel casing 21 feet
Casing stick-up height: 3.1 feet
Water level: 27.5 feet (approximate)

During logging of this well it was discovered that a pipe protrudes into the well casing creating an obstruction at a depth of 12 feet as can be seen on the caliper log. It was not possible to complete ACTV, OPTV, or heat pulse flowmeter logs in this well because of the need to install centralizers on these tools that would not allow the tools to be lowered beyond the obstruction, and also the high risk that the tools may become entangled or damaged by the protruding pipe.

The natural gamma and resistivity logs are similar in character to those collected in the other wells at this site, and are consistent with the presence of shale and fine grained graywacke. The caliper log shows a widening of the wellbore immediately beneath the base of the casing that is probably caused by the installation of the well casing. Fractures identified from the caliper log are present at depths of 25, 33-34.5, 52.3, and 55 feet. An inflection of the fluid conductivity log that corresponds to the fracture zone at 33-34.5 feet suggests that this could be a water producing zone if this well is stressed by pumping.

Well IW-2

Well diameter: 8 inches
Total depth: 76.5 ft.
Casing: 8-inch steel casing 21 feet
Casing stick-up height: 3.1 feet
Water level: 27.5 feet (approximate)

It was found that well IW-2 had a pipe protruding through the casing at a depth of approximately 11 feet, similar to that observed in well IW-1. As a result, ACTV, OPTV, and heat pulse flowmeter logs could not be collected in the well.

The natural gamma and resistivity logs were similar in character to the logs collected in the other wells at this site. Review of the gamma and resistivity logs does indicate that a slightly coarser grained or less weather rock zone is present from 54 feet to 64 feet. Caliper data does show an increase in borehole diameter directly beneath the bottom of casing that is likely caused by the installation of the casing. One significant fracture zone was noted in the caliper

log between 69.5 and 71 feet. No additional significant fractures were noted from the caliper results.

2.0 CLOSING

The data collection and interpretation methodologies used in this investigation are consistent with standard practices applied to similar geophysical investigations. The correlation of geophysical responses with probable subsurface features is based on the past results of similar surveys although it is possible that some variation could exist at this site.

Please contact us if you have any questions or would like to discuss the logging results. We appreciate your business and look forward to working with you again.

Sincerely,



Donald Jagel
Principal Geophysicist



Christopher Call, P.G.
Senior Geophysicist

Attachment: Geophysical Well Logs of TW-1, TW-2, TW-2A, TW-3, IW-1, and IW-2

Date: 8/8/2024


Client: AECOM
Well ID: TW-1


Site: Former NOW Corporation Facility
2092 Route 9G
Staatsburg, NY


Depth Datum: Top of Casing (TOC)
Borehole Dia.: 8 in.
Total Depth: 120.5 ft.
Casing Type: Steel
Casing Depth: 31 ft.
Casing Stickup Ht.: 2.55 ft. (inner casing)
Water Level: 25 ft. (approx.)

Remarks: Heat pulse flowmeter values of less than +/-0.03 gpm outside of the calibration limits of the instrument. NF indicates that No Flow was detected at that measurement depth.

Structure Colors:
Magenta = Open fracture
Orange = Partially open fracture or joint
Yellow = Open or partially open bedding plane fracture or parting
Cyan = Discontinuous fracture







Date: 8/7/2024


Client: AECOM
Well ID: TW-2


Site: Former NOW Corporation Facility
2092 Route 9G
Staatsburg, NY


Depth Datum: Top of Casing (TOC)
Borehole Dia.: 8 in.
Total Depth: 160 ft.
Casing Type: Steel
Casing Depth: 16 ft.
Casing Stickup Ht.: 2.15 ft.
Water Level: 8.5 ft. (approx).


Remarks: Heat pulse flowmeter values of less than +/-0.03 gpm outside of the calibration limits of the instrument. NF indicates that No Flow was detected at that measurement depth.

Structure Colors:
Magenta = Open fracture
Orange = Partially open fracture or joint
Yellow = Open or partially open bedding plane fracture or parting
Cyan = Discontinuous fracture









Date: 8/12/2024

Client: AECOM
Well ID: TW-2A

Site: Former NOW Corporation Facility
2092 Route 9G
Staatsburg, NY

Depth Datum: Top of Casing (TOC)
Borehole Dia.: 8 in.
Total Depth: 114 ft.
Casing Type: Steel
Casing Depth: 20.7 ft.
Casing Stickup Ht.: 0.45 ft. (inner casing)
Water Level: 8 ft. (approx.)

Remarks: Heat pulse flowmeter values of less than +/-0.03 gpm outside of the calibration limits of the instrument. NF indicates that No Flow was detected at that measurement depth.


Structure Colors:


Magenta = Open fracture


Orange = Partially open fracture or joint

Yellow = Open or partially open bedding plane fracture or parting

Cyan = Discontinuous fracture







Client: **AECOM**
Well ID: **TW-3**

Site: **Former NOW Corporation Facility**
2092 Route 9G
Staatsburg, NY

Date: 8/8/2024 & 8/9/2024

Depth Datum: Top of Casing (TOC)
Borehole Dia.: 8 in.
Total Depth: 110.5 ft.
Casing Type: Steel
Casing Depth: 11 ft.
Casing Stickup Ht.: 0.9 ft. (inner casing)
Water Level: 9 ft. (approx.)

Remarks: Heat pulse flowmeter values of less than ± 0.03 gpm outside of the calibration limits of the instrument. NF indicates that No Flow was detected at that measurement depth.


Structure Colors:


Magenta = Open fracture


Orange = Partially open fracture or joint

Yellow = Open or partially open bedding plane fracture or parting

Cyan = Discontinuous fracture









AGS Project No.: 24-161-1


Client: AECOM
Well ID: IW-1


Site: Former NOW Corporation Facility
2092 Route 9G
Staatsburg, NY

Date: 8/12/2024

Depth Datum: Top of Casing (TOC)
Borehole Dia.: 8 in.
Total Depth: 76.5 ft.
Casing Type: Steel
Casing Depth: 21 ft.
Casing Stickup Ht.: 3.1 ft.
Water Level: 27.5 ft.

Remarks: Acoustic televiwer, optical televiwer, and heat pulse flowmeter data could not be collected in this well because of a pipe protruding into the cased portion of the well at a depth of 12 feet.







AGS Project No.: 24-161-1


Client: AECOM
Well ID: IW-2


Site: Former NOW Corporation Facility
2092 Route 9G
Staatsburg, NY

Date: 8/6/24

Depth Datum: Top of Casing (TOC)
Borehole Dia.: 8 in.
Total Depth: 78.5 ft.
Casing Type: Steel
Casing Depth: 26.5 ft.
Casing Stickup Ht.: 4.55 ft.
Water Level: 34 ft. (approx.)

Remarks: Acoustic televiwer, optical televiwer, and heat pulse flowmeter data could not be collected in this well because of a pipe protruding into the cased portion of the well at a depth of 11 feet.
Note that the 3-arm caliper did become jammed by this pipe and required some effort to safely retrieve the tool.





Appendix D - Community Air Monitoring Data

8/21/2024

Instrument Name	DustTrak II		
Model Number	8530		
Serial Number	8530113202		
Firmware Version	3.1		
Calibration Date	7/9/2024		
Test Name	MANUAL_001		
Test Start Time	8:50:46 AM		
Test Start Date	8/21/2024		
Test Length [D:H:M]	0:08:30		
Test Interval [M:S]	15:00		
Mass Average [mg/m3]	0.009		
Mass Minimum [mg/m3]	0.004		
Mass Maximum [mg/m3]	0.015		
Mass TWA [mg/m3]	0.009		
Photometric User Cal	1		
Flow User Cal	0		
Errors			
Number of Samples	34		
Elapsed Time [s]	Mass [mg/m3]	Alarms	Errors
900	0.008		
1800	0.004		
2700	0.004		
3600	0.005		
4500	0.009		
5400	0.005		
6300	0.006		
7200	0.012		
8100	0.008		
9000	0.009		
9900	0.008		
10800	0.012		
11700	0.01		
12600	0.01		
13500	0.01		
14400	0.01		
15300	0.008		
16200	0.011		
17100	0.011		
18000	0.011		
18900	0.009		
19800	0.008		
20700	0.009		
21600	0.009		
22500	0.009		
23400	0.009		
24300	0.009		
25200	0.007		
26100	0.013		
27000	0.009		
27900	0.014		
28800	0.015		
29700	0.009		
30600	0.009		

8/22/2024

Instrument Name	DustTrak II		
Model Number	8530		
Serial Number	8530113202		
Firmware Version	3.1		
Calibration Date	7/9/2024		
Test Name	MANUAL_002		
Test Start Time	8:31:26 AM		
Test Start Date	8/22/2024		
Test Length [D:H:M]	0:09:15		
Test Interval [M:S]	15:00		
Mass Average [mg/m3]	0.011		
Mass Minimum [mg/m3]	0.004		
Mass Maximum [mg/m3]	0.015		
Mass TWA [mg/m3]	0.011		
Photometric User Cal	1		
Flow User Cal	0		
Errors			
Number of Samples	37		
Elapsed Time [s]	Mass [mg/m3]	Alarms	Errors
900	0.014		
1800	0.005		
2700	0.004		
3600	0.004		
4500	0.005		
5400	0.006		
6300	0.007		
7200	0.008		
8100	0.008		
9000	0.009		
9900	0.009		
10800	0.01		
11700	0.011		
12600	0.01		
13500	0.011		
14400	0.011		
15300	0.011		
16200	0.012		
17100	0.012		
18000	0.013		
18900	0.013		
19800	0.013		
20700	0.013		
21600	0.014		
22500	0.015		
23400	0.015		
24300	0.015		
25200	0.015		
26100	0.014		
27000	0.014		
27900	0.014		
28800	0.014		
29700	0.014		
30600	0.015		
31500	0.015		
32400	0.015		
33300	0.014		

8/23/2024

[illegible]

8/21/2024

Instrument Name	DustTrak II		
Model Number	8530		
Serial Number	8530110313		
Firmware Version	3.1		
Calibration Date	7/1/2024		
Test Name	MANUAL_001		
Test Start Time	8:52:10 AM		
Test Start Date	8/21/2024		
Test Length [D:H:M]	0:08:30		
Test Interval [M:S]	15:00		
Mass Average [mg/m3]	0.008		
Mass Minimum [mg/m3]	0.004		
Mass Maximum [mg/m3]	0.018		
Mass TWA [mg/m3]	0.008		
Photometric User Cal	1		
Flow User Cal	0		
Errors			
Number of Samples	34		
Elapsed Time [s]	Mass [mg/m3]	Alarms	Errors
900	0.018		
1800	0.006		
2700	0.005		
3600	0.004		
4500	0.005		
5400	0.007		
6300	0.006		
7200	0.007		
8100	0.008		
9000	0.008		
9900	0.008		
10800	0.008		
11700	0.008		
12600	0.009		
13500	0.009		
14400	0.009		
15300	0.008		
16200	0.008		
17100	0.008		
18000	0.008		
18900	0.008		
19800	0.008		
20700	0.008		
21600	0.008		
22500	0.008		
23400	0.008		
24300	0.007		
25200	0.007		
26100	0.009		
27000	0.008		
27900	0.007		
28800	0.008		
29700	0.008		
30600	0.008		

8/22/2024

Instrument Name	DustTrak II		
Model Number	8530		
Serial Number	8530110313		
Firmware Version	3.1		
Calibration Date	7/1/2024		
Test Name	MANUAL_002		
Test Start Time	8:34:11 AM		
Test Start Date	8/22/2024		
Test Length [D:H:M]	0:09:00		
Test Interval [M:S]	15:00		
Mass Average [mg/m3]	0.016		
Mass Minimum [mg/m3]	0.007		
Mass Maximum [mg/m3]	0.029		
Mass TWA [mg/m3]	0.015		
Photometric User Cal	1		
Flow User Cal	0		
Errors			
Number of Samples	36		
Elapsed Time [s]	Mass [mg/m3]	Alarms	Errors
900	0.009		
1800	0.008		
2700	0.007		
3600	0.009		
4500	0.013		
5400	0.009		
6300	0.015		
7200	0.01		
8100	0.01		
9000	0.011		
9900	0.015		
10800	0.012		
11700	0.013		
12600	0.013		
13500	0.013		
14400	0.029		
15300	0.015		
16200	0.015		
17100	0.015		
18000	0.02		
18900	0.015		
19800	0.027		
20700	0.016		
21600	0.017		
22500	0.017		
23400	0.017		
24300	0.018		
25200	0.017		
26100	0.019		
27000	0.024		
27900	0.018		
28800	0.018		
29700	0.018		
30600	0.019		
31500	0.023		
32400	0.02		

8/23/2024

[illegible]

=====
24/08/21 09:18

Summary

Unit Name MiniRAE 3000 +(PGM-7320)

Unit SN 592-927758

Unit Firmw V2.22A

Running Mode Hygiene Mode

Datalog Mode Auto

Diagnostic No

Stop Reason Power Down

Site ID RAE00000

User ID USER0000

Begin 8/21/2024 9:18

End 8/21/2024 17:19

Sample Period 60

Number of 481

Sensor PID(ppm)

Sensor SN S023030115B6

Measure Type Min; Avg; Max; Real

Span 100

Span 2 1000

Low Alarm 50

High Alarm 100

Over Alarm 15000

STEL Alarm 25

TWA Alarm 10

Measurement Isobutylene

Calibration 8/13/2024 10:59

Peak 13.2

Min 0

Average 0.3

Datalog

Index	Date/Time	PID(ppm) (Min)	PID(ppm) (Avg)	PID(ppm) (Max)	PID(ppm) (Real)
1	8/21/2024 9:19	0	2.6	12.4	1.2
2	8/21/2024 9:20	0	0.4	1.1	0

NYSDEC Site No. 314008

3	8/21/2024 9:21	0	0	0.5	0.5
4	8/21/2024 9:22	0	0	0.6	0
5	8/21/2024 9:23	0	0	0	0
6	8/21/2024 9:24	0	0	0	0
7	8/21/2024 9:25	0	0	0	0
8	8/21/2024 9:26	0	2.9	7.4	0
9	8/21/2024 9:27	0	0	0	0
10	8/21/2024 9:28	0	0	0	0
11	8/21/2024 9:29	0	0	0	0
12	8/21/2024 9:30	0	0	0	0
13	8/21/2024 9:31	0	0	0	0
14	8/21/2024 9:32	0	0	0	0
15	8/21/2024 9:33	0	0	0	0
16	8/21/2024 9:34	0	0	0	0
17	8/21/2024 9:35	0	0	0	0
18	8/21/2024 9:36	0	0	0	0
19	8/21/2024 9:37	0	0	0	0
20	8/21/2024 9:38	0	0	0	0
21	8/21/2024 9:39	0	0.2	3.3	3.3
22	8/21/2024 9:40	0	1.1	4	0
23	8/21/2024 9:41	0	0	0	0
24	8/21/2024 9:42	0	0	0	0
25	8/21/2024 9:43	0	0	0	0
26	8/21/2024 9:44	0	0.5	2.1	0
27	8/21/2024 9:45	0	0	0	0
28	8/21/2024 9:46	0	0	0	0
29	8/21/2024 9:47	0	0	0	0
30	8/21/2024 9:48	0	0	0	0
31	8/21/2024 9:49	0	2.7	7.9	0.1
32	8/21/2024 9:50	0	0	0.1	0
33	8/21/2024 9:51	0	0	0	0
34	8/21/2024 9:52	0	0	0	0
35	8/21/2024 9:53	0	0.9	5	3.9
36	8/21/2024 9:54	0	0.1	2.9	0
37	8/21/2024 9:55	0	0	0	0
38	8/21/2024 9:56	0	0	0	0
39	8/21/2024 9:57	0	0	0	0
40	8/21/2024 9:58	0	0	0	0
41	8/21/2024 9:59	0	0	0	0
42	8/21/2024 10:00	0	0	0	0
43	8/21/2024 10:01	0	0	0	0
44	8/21/2024 10:02	0	1.2	5.5	5.5
45	8/21/2024 10:03	0	0.7	5.6	0
46	8/21/2024 10:04	0	0	0.3	0

NYSDEC Site No. 314008

47	8/21/2024 10:05	0	0	0.2	0
48	8/21/2024 10:06	0	0	0	0
49	8/21/2024 10:07	0	0	0	0
50	8/21/2024 10:08	0	0	0	0
51	8/21/2024 10:09	0	2.2	6.7	0.2
52	8/21/2024 10:10	0	0.1	0.2	0
53	8/21/2024 10:11	0	0	0.1	0
54	8/21/2024 10:12	0	0	0.1	0
55	8/21/2024 10:13	0	0	0	0
56	8/21/2024 10:14	0	0	0	0
57	8/21/2024 10:15	0	0.2	0.7	0
58	8/21/2024 10:16	0	0	0	0
59	8/21/2024 10:17	0	0	0	0
60	8/21/2024 10:18	0	0.1	0.5	0
61	8/21/2024 10:19	0	0	0	0
62	8/21/2024 10:20	0	0	0	0
63	8/21/2024 10:21	0	0.1	0.4	0
64	8/21/2024 10:22	0	0	0	0
65	8/21/2024 10:23	0	0	0	0
66	8/21/2024 10:24	0	0	0.1	0.1
67	8/21/2024 10:25	0	0	0.1	0
68	8/21/2024 10:26	0	0.3	1.7	0.1
69	8/21/2024 10:27	0	0	0.1	0
70	8/21/2024 10:28	0	0	0	0
71	8/21/2024 10:29	0	0	0	0
72	8/21/2024 10:30	0	0	0	0
73	8/21/2024 10:31	0	0	0	0
74	8/21/2024 10:32	0	0.4	2	0.1
75	8/21/2024 10:33	0	0	0	0
76	8/21/2024 10:34	0	0	0	0
77	8/21/2024 10:35	0	0	0	0
78	8/21/2024 10:36	0	0.2	1.7	0.4
79	8/21/2024 10:37	0	0	0.3	0
80	8/21/2024 10:38	0	0	0.1	0.1
81	8/21/2024 10:39	0	0.1	0.2	0
82	8/21/2024 10:40	0	0.1	0.1	0.1
83	8/21/2024 10:41	0	0	0.1	0
84	8/21/2024 10:42	0	0	0	0
85	8/21/2024 10:43	0	0.3	0.9	0
86	8/21/2024 10:44	0	0	0	0
87	8/21/2024 10:45	0	0	0.1	0
88	8/21/2024 10:46	0	0.3	1.3	0
89	8/21/2024 10:47	0	0.5	2.2	0
90	8/21/2024 10:48	0	0	0	0

NYSDEC Site No. 314008

91	8/21/2024 10:49	0	0	0	0
92	8/21/2024 10:50	0	0	0.3	0.3
93	8/21/2024 10:51	0	0.1	0.3	0
94	8/21/2024 10:52	0	0	0.1	0
95	8/21/2024 10:53	0	0	0.1	0
96	8/21/2024 10:54	0	0	0	0
97	8/21/2024 10:55	0	0	0	0
98	8/21/2024 10:56	0	0	0	0
99	8/21/2024 10:57	0	0	0	0
100	8/21/2024 10:58	0	0	0	0
101	8/21/2024 10:59	0	0	0.1	0.1
102	8/21/2024 11:00	0	0.1	0.1	0.1
103	8/21/2024 11:01	0.1	0.2	1	1
104	8/21/2024 11:02	0.1	0.4	1.1	0.1
105	8/21/2024 11:03	0.1	0.1	0.2	0.1
106	8/21/2024 11:04	0.1	0.1	0.4	0.1
107	8/21/2024 11:05	0	0.1	0.4	0
108	8/21/2024 11:06	0	0	0.1	0.1
109	8/21/2024 11:07	0	0	0.1	0.1
110	8/21/2024 11:08	0	0.5	1.6	0.1
111	8/21/2024 11:09	0	0	0.1	0
112	8/21/2024 11:10	0	0	0	0
113	8/21/2024 11:11	0	1.5	3	0.2
114	8/21/2024 11:12	0	0.1	0.2	0.1
115	8/21/2024 11:13	0.1	0.1	0.2	0.1
116	8/21/2024 11:14	0.1	0.9	3.7	0.1
117	8/21/2024 11:15	0	0.1	0.1	0
118	8/21/2024 11:16	0	0.3	0.8	0
119	8/21/2024 11:17	0	0	0.1	0
120	8/21/2024 11:18	0	0	0.1	0
121	8/21/2024 11:19	0	0.1	0.1	0
122	8/21/2024 11:20	0	0	0.1	0
123	8/21/2024 11:21	0	0	0	0
124	8/21/2024 11:22	0	0	0.1	0
125	8/21/2024 11:23	0	0	0.1	0
126	8/21/2024 11:24	0	0	0.1	0
127	8/21/2024 11:25	0	0.2	0.8	0.1
128	8/21/2024 11:26	0	0.1	0.1	0
129	8/21/2024 11:27	0	0	0	0
130	8/21/2024 11:28	0	2.4	5.9	1.7
131	8/21/2024 11:29	0.1	0.3	1.2	0.1
132	8/21/2024 11:30	0.1	0.1	0.2	0.1
133	8/21/2024 11:31	0.1	0.1	0.1	0.1
134	8/21/2024 11:32	0	0.1	0.1	0.1

NYSDEC Site No. 314008

135	8/21/2024 11:33	0	0	0.1	0.1
136	8/21/2024 11:34	0	0.1	0.1	0
137	8/21/2024 11:35	0	0	0	0
138	8/21/2024 11:36	0	0	0	0
139	8/21/2024 11:37	0	0	0	0
140	8/21/2024 11:38	0	0	0	0
141	8/21/2024 11:39	0	0	0	0
142	8/21/2024 11:40	0	0.1	0.1	0
143	8/21/2024 11:41	0	0	0.1	0
144	8/21/2024 11:42	0	0	0	0
145	8/21/2024 11:43	0	0	0	0
146	8/21/2024 11:44	0	0	0	0
147	8/21/2024 11:45	0	0	0	0
148	8/21/2024 11:46	0	0	0	0
149	8/21/2024 11:47	0	0	0.1	0.1
150	8/21/2024 11:48	0	0.1	0.1	0.1
151	8/21/2024 11:49	0.1	0.1	0.1	0.1
152	8/21/2024 11:50	0.1	0.1	0.1	0.1
153	8/21/2024 11:51	0.1	0.1	0.1	0.1
154	8/21/2024 11:52	0.1	0.1	0.2	0.1
155	8/21/2024 11:53	0.1	0.1	0.1	0.1
156	8/21/2024 11:54	0	0.1	0.1	0
157	8/21/2024 11:55	0	0	0	0
158	8/21/2024 11:56	0	0	0	0
159	8/21/2024 11:57	0	0	0	0
160	8/21/2024 11:58	0	0	0	0
161	8/21/2024 11:59	0	0	0	0
162	8/21/2024 12:00	0	0	0	0
163	8/21/2024 12:01	0	0	0	0
164	8/21/2024 12:02	0	0	0	0
165	8/21/2024 12:03	0	0	0.3	0.3
166	8/21/2024 12:04	0	0.1	0.3	0
167	8/21/2024 12:05	0	0	0	0
168	8/21/2024 12:06	0	0	0	0
169	8/21/2024 12:07	0	0	0	0
170	8/21/2024 12:08	0	0	0	0
171	8/21/2024 12:09	0	0	0	0
172	8/21/2024 12:10	0	0	0	0
173	8/21/2024 12:11	0	0	0	0
174	8/21/2024 12:12	0	0	0	0
175	8/21/2024 12:13	0	0	0	0
176	8/21/2024 12:14	0	0	0	0
177	8/21/2024 12:15	0	0	0	0
178	8/21/2024 12:16	0	0	0	0

NYSDEC Site No. 314008

179	8/21/2024 12:17	0	0	0	0
180	8/21/2024 12:18	0	0	0	0
181	8/21/2024 12:19	0	0	0	0
182	8/21/2024 12:20	0	0	0	0
183	8/21/2024 12:21	0	0	0.1	0.1
184	8/21/2024 12:22	0	0.1	0.1	0
185	8/21/2024 12:23	0	0	0.1	0
186	8/21/2024 12:24	0	0.1	0.1	0.1
187	8/21/2024 12:25	0	0.1	0.1	0
188	8/21/2024 12:26	0	0	0	0
189	8/21/2024 12:27	0	0.1	0.1	0.1
190	8/21/2024 12:28	0	0	0.1	0
191	8/21/2024 12:29	0	0	0	0
192	8/21/2024 12:30	0	0	0.1	0
193	8/21/2024 12:31	0	0	0	0
194	8/21/2024 12:32	0	0	0	0
195	8/21/2024 12:33	0	0	0	0
196	8/21/2024 12:34	0	0	0	0
197	8/21/2024 12:35	0	0	0	0
198	8/21/2024 12:36	0	0	0	0
199	8/21/2024 12:37	0	0	0	0
200	8/21/2024 12:38	0	0	0	0
201	8/21/2024 12:39	0	0	0	0
202	8/21/2024 12:40	0	0	0.1	0
203	8/21/2024 12:41	0	0	0.1	0
204	8/21/2024 12:42	0	0.1	0.1	0
205	8/21/2024 12:43	0	0.1	0.2	0.1
206	8/21/2024 12:44	0	0.1	0.2	0.1
207	8/21/2024 12:45	0	0	0.3	0.2
208	8/21/2024 12:46	0	71.2	237.6	1.8
209	8/21/2024 12:47	0.3	0.6	1.6	0.3
210	8/21/2024 12:48	0.2	0.3	0.5	0.4
211	8/21/2024 12:49	0.1	0.3	1.3	0.1
212	8/21/2024 12:50	0.1	0.8	3.1	1.3
213	8/21/2024 12:51	0.2	0.8	2.3	2.1
214	8/21/2024 12:52	0.1	0.4	1.6	0.3
215	8/21/2024 12:53	0.1	0.4	1.7	0.2
216	8/21/2024 12:54	0.2	0.9	3.1	1.3
217	8/21/2024 12:55	0.2	0.9	3.7	0.2
218	8/21/2024 12:56	0.2	0.9	2.5	1.8
219	8/21/2024 12:57	0.2	0.7	4.1	0.4
220	8/21/2024 12:58	0.3	0.3	0.6	0.3
221	8/21/2024 12:59	0.2	23.9	85	1.3
222	8/21/2024 13:00	0.4	0.7	1.6	1.5

NYSDEC Site No. 314008

223	8/21/2024 13:01	0.2	0.5	1.2	0.3
224	8/21/2024 13:02	0.2	0.3	0.8	0.2
225	8/21/2024 13:03	0.1	0.3	1.1	0.8
226	8/21/2024 13:04	0.1	0.3	1.5	0.1
227	8/21/2024 13:05	0.1	0.2	0.4	0.2
228	8/21/2024 13:06	0.1	1.7	6.5	0.2
229	8/21/2024 13:07	0.1	0.1	0.4	0.1
230	8/21/2024 13:08	0	0.1	0.1	0
231	8/21/2024 13:09	0	0.1	0.2	0.2
232	8/21/2024 13:10	0	0.1	0.2	0.1
233	8/21/2024 13:11	0	0	0.1	0
234	8/21/2024 13:12	0	0.1	0.2	0.2
235	8/21/2024 13:13	0.1	0.2	0.3	0.2
236	8/21/2024 13:14	0.1	0.5	1.9	0.2
237	8/21/2024 13:15	0.2	0.2	0.3	0.2
238	8/21/2024 13:16	0.2	0.3	0.6	0.4
239	8/21/2024 13:17	0.2	0.4	3.9	3.9
240	8/21/2024 13:18	0.3	3.8	13.7	0.3
241	8/21/2024 13:19	0.2	0.3	0.3	0.2
242	8/21/2024 13:20	0.1	0.2	0.2	0.1
243	8/21/2024 13:21	0.1	0.2	0.3	0.1
244	8/21/2024 13:22	0.1	0.3	2.5	2.5
245	8/21/2024 13:23	0.2	0.6	2.4	0.7
246	8/21/2024 13:24	0.2	0.4	0.7	0.3
247	8/21/2024 13:25	0.2	0.4	0.9	0.3
248	8/21/2024 13:26	0.1	0.1	0.3	0.1
249	8/21/2024 13:27	0.1	0.1	0.2	0.1
250	8/21/2024 13:28	0	0.1	0.1	0.1
251	8/21/2024 13:29	0.1	0.1	0.2	0.2
252	8/21/2024 13:30	0.1	0.2	0.4	0.1
253	8/21/2024 13:31	0.1	0.1	0.1	0.1
254	8/21/2024 13:32	0.1	0.1	0.3	0.3
255	8/21/2024 13:33	0.1	0.2	0.3	0.1
256	8/21/2024 13:34	0.1	0.1	0.1	0.1
257	8/21/2024 13:35	0	0.1	0.1	0.1
258	8/21/2024 13:36	0.1	0.1	0.1	0.1
259	8/21/2024 13:37	0.1	0.1	0.2	0.1
260	8/21/2024 13:38	0.1	0.1	0.1	0.1
261	8/21/2024 13:39	0.1	0.1	0.1	0.1
262	8/21/2024 13:40	0	3	5.4	0.4
263	8/21/2024 13:41	0.2	0.2	0.4	0.2
264	8/21/2024 13:42	0.2	0.2	0.3	0.2
265	8/21/2024 13:43	0.2	0.2	0.3	0.2
266	8/21/2024 13:44	0.1	0.2	0.2	0.2

NYSDEC Site No. 314008

267	8/21/2024 13:45	0.2	0.3	1	0.2
268	8/21/2024 13:46	0.2	0.2	0.2	0.2
269	8/21/2024 13:47	0.1	0.1	0.2	0.1
270	8/21/2024 13:48	0.1	0.2	0.4	0.1
271	8/21/2024 13:49	0.1	0.1	0.2	0.1
272	8/21/2024 13:50	0.1	0.2	0.2	0.2
273	8/21/2024 13:51	0.1	0.2	0.2	0.2
274	8/21/2024 13:52	0.1	0.1	0.2	0.1
275	8/21/2024 13:53	0.1	0.1	0.1	0.1
276	8/21/2024 13:54	0.1	0.9	3.3	0.2
277	8/21/2024 13:55	0.1	0.2	0.2	0.1
278	8/21/2024 13:56	0.1	0.1	0.2	0.1
279	8/21/2024 13:57	0.1	0.1	0.2	0.1
280	8/21/2024 13:58	0.1	0.4	1.2	1.2
281	8/21/2024 13:59	0.1	0.2	1.4	0.1
282	8/21/2024 14:00	0.1	0.1	0.1	0.1
283	8/21/2024 14:01	0	0	0.1	0
284	8/21/2024 14:02	0	0	0	0
285	8/21/2024 14:03	0	0	0.1	0.1
286	8/21/2024 14:04	0	0.1	0.1	0
287	8/21/2024 14:05	0	0	0.1	0
288	8/21/2024 14:06	0	0	0.1	0
289	8/21/2024 14:07	0	0	0	0
290	8/21/2024 14:08	0	0	0	0
291	8/21/2024 14:09	0	0.1	0.3	0.1
292	8/21/2024 14:10	0.1	0.1	0.1	0.1
293	8/21/2024 14:11	0.1	0.1	0.2	0.1
294	8/21/2024 14:12	0.1	0.1	0.2	0.2
295	8/21/2024 14:13	0.1	0.6	1.7	0.1
296	8/21/2024 14:14	0.1	0.2	0.3	0.2
297	8/21/2024 14:15	0.1	0.1	0.2	0.1
298	8/21/2024 14:16	0	0.1	0.1	0
299	8/21/2024 14:17	0	0.1	0.1	0.1
300	8/21/2024 14:18	0.1	0.4	1.6	0.5
301	8/21/2024 14:19	0.1	0.1	0.3	0.1
302	8/21/2024 14:20	0.1	0.7	1.9	0.3
303	8/21/2024 14:21	0.1	0.2	0.7	0.1
304	8/21/2024 14:22	0.1	0.1	0.4	0.1
305	8/21/2024 14:23	0.1	0.1	0.3	0.1
306	8/21/2024 14:24	0.1	0.1	0.4	0.1
307	8/21/2024 14:25	0.1	0.1	0.2	0.1
308	8/21/2024 14:26	0.1	0.1	0.1	0.1
309	8/21/2024 14:27	0.1	0.1	0.2	0.2
310	8/21/2024 14:28	0.1	0.3	1.1	0.1

NYSDEC Site No. 314008

311	8/21/2024 14:29	0.1	0.1	0.1	0.1
312	8/21/2024 14:30	0.1	0.1	0.1	0.1
313	8/21/2024 14:31	0	0.4	9	9
314	8/21/2024 14:32	0.1	2.5	10.4	0.1
315	8/21/2024 14:33	0.1	0.1	0.1	0.1
316	8/21/2024 14:34	0.1	0.1	0.1	0.1
317	8/21/2024 14:35	0.1	0.1	0.1	0.1
318	8/21/2024 14:36	0.1	0.1	0.1	0.1
319	8/21/2024 14:37	0.1	0.1	0.1	0.1
320	8/21/2024 14:38	0.1	0.1	0.4	0.1
321	8/21/2024 14:39	0.1	0.1	0.1	0.1
322	8/21/2024 14:40	0.1	0.1	0.1	0.1
323	8/21/2024 14:41	0.1	0.1	0.1	0.1
324	8/21/2024 14:42	0.1	0.1	0.2	0.1
325	8/21/2024 14:43	0.1	0.1	0.1	0.1
326	8/21/2024 14:44	0.1	0.3	2.5	2.5
327	8/21/2024 14:45	0.1	0.6	2.6	0.1
328	8/21/2024 14:46	0.1	0.1	0.1	0.1
329	8/21/2024 14:47	0.1	0.1	0.1	0.1
330	8/21/2024 14:48	0.1	0.1	0.1	0.1
331	8/21/2024 14:49	0.1	0.1	0.1	0.1
332	8/21/2024 14:50	0.1	0.1	0.1	0.1
333	8/21/2024 14:51	0.1	0.1	0.1	0.1
334	8/21/2024 14:52	0.1	0.1	0.1	0.1
335	8/21/2024 14:53	0.1	0.1	0.1	0.1
336	8/21/2024 14:54	0.1	0.1	0.1	0.1
337	8/21/2024 14:55	0.1	0.1	0.1	0.1
338	8/21/2024 14:56	0.1	0.1	0.1	0.1
339	8/21/2024 14:57	0.1	0.1	0.1	0.1
340	8/21/2024 14:58	0.1	0.1	0.1	0.1
341	8/21/2024 14:59	0.1	0.1	0.1	0.1
342	8/21/2024 15:00	0.1	0.1	0.1	0.1
343	8/21/2024 15:01	0.1	0.1	0.2	0.2
344	8/21/2024 15:02	0.1	0.2	0.3	0.1
345	8/21/2024 15:03	0.1	0.1	0.1	0.1
346	8/21/2024 15:04	0.1	0.1	0.1	0.1
347	8/21/2024 15:05	0.1	0.1	0.1	0.1
348	8/21/2024 15:06	0.1	0.1	0.1	0.1
349	8/21/2024 15:07	0.1	0.1	0.1	0.1
350	8/21/2024 15:08	0.1	0.1	0.1	0.1
351	8/21/2024 15:09	0.1	0.1	0.1	0.1
352	8/21/2024 15:10	0.1	0.1	0.1	0.1
353	8/21/2024 15:11	0.1	0.1	0.1	0.1
354	8/21/2024 15:12	0.1	0.1	0.1	0.1

NYSDEC Site No. 314008

355	8/21/2024 15:13	0.1	0.1	0.3	0.1
356	8/21/2024 15:14	0.1	0.1	0.1	0.1
357	8/21/2024 15:15	0.1	0.1	0.1	0.1
358	8/21/2024 15:16	0	0.1	0.1	0.1
359	8/21/2024 15:17	0	0.1	0.1	0.1
360	8/21/2024 15:18	0	0.1	0.2	0.1
361	8/21/2024 15:19	0	0.2	0.6	0.2
362	8/21/2024 15:20	0	0.1	0.2	0
363	8/21/2024 15:21	0	0.2	0.7	0.7
364	8/21/2024 15:22	0	0.1	0.6	0.1
365	8/21/2024 15:23	0	0.1	0.2	0.1
366	8/21/2024 15:24	0.1	0.2	0.5	0.1
367	8/21/2024 15:25	0.1	0.1	0.2	0.1
368	8/21/2024 15:26	0.1	0.1	0.1	0.1
369	8/21/2024 15:27	0	0.1	0.3	0.1
370	8/21/2024 15:28	0	0.1	0.1	0.1
371	8/21/2024 15:29	0	0.2	0.5	0.1
372	8/21/2024 15:30	0	0.1	0.3	0.3
373	8/21/2024 15:31	0	0.1	0.3	0.1
374	8/21/2024 15:32	0.1	0.2	0.4	0.1
375	8/21/2024 15:33	0	0.1	0.1	0
376	8/21/2024 15:34	0	0.2	0.5	0.1
377	8/21/2024 15:35	0.1	0.1	0.2	0.2
378	8/21/2024 15:36	0.1	0.1	0.2	0.1
379	8/21/2024 15:37	0.1	0.1	0.1	0.1
380	8/21/2024 15:38	0.1	0.1	0.1	0.1
381	8/21/2024 15:39	0.1	0.1	0.2	0.1
382	8/21/2024 15:40	0	0.3	1.7	1.2
383	8/21/2024 15:41	0.1	0.1	1	0.1
384	8/21/2024 15:42	0	0.1	0.1	0.1
385	8/21/2024 15:43	0.1	0.1	0.1	0.1
386	8/21/2024 15:44	0.1	0.3	1	0.1
387	8/21/2024 15:45	0	0.1	0.1	0.1
388	8/21/2024 15:46	0	0.1	0.2	0.1
389	8/21/2024 15:47	0	0.1	0.2	0.1
390	8/21/2024 15:48	0	0.1	0.2	0
391	8/21/2024 15:49	0	0.4	9.3	9.3
392	8/21/2024 15:50	0.1	1.8	11.8	0.1
393	8/21/2024 15:51	0.1	0.1	0.1	0.1
394	8/21/2024 15:52	0.1	0.1	0.1	0.1
395	8/21/2024 15:53	0.1	0.4	1.8	0.1
396	8/21/2024 15:54	0.1	0.1	0.1	0.1
397	8/21/2024 15:55	0.1	0.1	0.1	0.1
398	8/21/2024 15:56	0.1	0.1	0.1	0.1

NYSDEC Site No. 314008

399	8/21/2024 15:57	0.1	0.1	0.1	0.1
400	8/21/2024 15:58	0.1	0.1	0.1	0.1
401	8/21/2024 15:59	0.1	0.1	0.1	0.1
402	8/21/2024 16:00	0.1	0.1	0.1	0.1
403	8/21/2024 16:01	0.1	0.1	0.1	0.1
404	8/21/2024 16:02	0.1	0.1	0.1	0.1
405	8/21/2024 16:03	0.1	0.1	0.1	0.1
406	8/21/2024 16:04	0.1	0.2	1	0.1
407	8/21/2024 16:05	0	0.1	0.1	0.1
408	8/21/2024 16:06	0.1	0.1	0.1	0.1
409	8/21/2024 16:07	0	0.1	0.1	0.1
410	8/21/2024 16:08	0.1	0.1	0.1	0.1
411	8/21/2024 16:09	0	0.3	1.3	0.2
412	8/21/2024 16:10	0.1	0.1	0.2	0.1
413	8/21/2024 16:11	0.1	0.1	0.1	0.1
414	8/21/2024 16:12	0.1	0.1	0.1	0.1
415	8/21/2024 16:13	0.1	0.1	0.2	0.1
416	8/21/2024 16:14	0	0.2	0.7	0.1
417	8/21/2024 16:15	0.1	0.1	0.1	0.1
418	8/21/2024 16:16	0.1	0.1	0.2	0.1
419	8/21/2024 16:17	0.1	0.1	0.8	0.8
420	8/21/2024 16:18	0.1	0.6	1.4	0.3
421	8/21/2024 16:19	0.1	0.2	0.3	0.2
422	8/21/2024 16:20	0.1	0.1	0.2	0.1
423	8/21/2024 16:21	0.1	0.2	1	0.1
424	8/21/2024 16:22	0.1	0.1	0.2	0.1
425	8/21/2024 16:23	0.1	0.1	0.1	0.1
426	8/21/2024 16:24	0.1	0.1	0.2	0.1
427	8/21/2024 16:25	0.1	0.1	0.2	0.1
428	8/21/2024 16:26	0.1	0.1	0.1	0.1
429	8/21/2024 16:27	0.1	0.1	0.1	0.1
430	8/21/2024 16:28	0.1	0.1	0.1	0.1
431	8/21/2024 16:29	0.1	0.1	0.1	0.1
432	8/21/2024 16:30	0.1	0.1	0.1	0.1
433	8/21/2024 16:31	0.1	3.1	12.1	0.1
434	8/21/2024 16:32	0.1	0.3	0.5	0.3
435	8/21/2024 16:33	0.1	0.2	0.4	0.2
436	8/21/2024 16:34	0.1	0.3	1.2	1.2
437	8/21/2024 16:35	0.4	1.1	2.1	0.8
438	8/21/2024 16:36	0.2	0.7	1.2	0.2
439	8/21/2024 16:37	0.2	0.5	0.9	0.7
440	8/21/2024 16:38	0.4	0.7	1.3	0.8
441	8/21/2024 16:39	0.1	0.2	0.9	0.1
442	8/21/2024 16:40	0.1	0.1	0.1	0.1

NYSDEC Site No. 314008

443	8/21/2024 16:41	0.1	0.1	0.1	0.1
444	8/21/2024 16:42	0.1	2.5	12.6	0.1
445	8/21/2024 16:43	0.1	0.2	0.2	0.2
446	8/21/2024 16:44	0.1	0.2	0.2	0.2
447	8/21/2024 16:45	0.1	0.1	0.2	0.1
448	8/21/2024 16:46	0.1	0.1	0.1	0.1
449	8/21/2024 16:47	0.1	0.1	0.1	0.1
450	8/21/2024 16:48	0.1	0.1	0.1	0.1
451	8/21/2024 16:49	0.1	0.2	0.4	0.2
452	8/21/2024 16:50	0.1	0.1	0.2	0.2
453	8/21/2024 16:51	0.1	0.1	0.2	0.2
454	8/21/2024 16:52	0.1	0.2	0.2	0.1
455	8/21/2024 16:53	0.1	0.1	0.2	0.1
456	8/21/2024 16:54	0.1	0.2	0.2	0.1
457	8/21/2024 16:55	0.1	0.6	1.9	0.2
458	8/21/2024 16:56	0.2	0.3	0.7	0.4
459	8/21/2024 16:57	0.3	0.3	0.4	0.3
460	8/21/2024 16:58	0.2	0.4	1.2	1.1
461	8/21/2024 16:59	0.2	0.3	1.1	0.2
462	8/21/2024 17:00	0.2	0.3	0.4	0.3
463	8/21/2024 17:01	0.2	0.3	0.3	0.2
464	8/21/2024 17:02	0.2	0.2	0.3	0.2
465	8/21/2024 17:03	0.2	2.4	13.2	13.2
466	8/21/2024 17:04	0.3	2.7	13.1	7.7
467	8/21/2024 17:05	1.8	3.2	7.5	1.8
468	8/21/2024 17:06	1.5	1.9	2.1	2
469	8/21/2024 17:07	0.5	6.9	22.3	0.6
470	8/21/2024 17:08	0.4	0.5	0.6	0.4
471	8/21/2024 17:09	0.3	0.3	0.4	0.3
472	8/21/2024 17:10	0.2	0.3	0.3	0.2
473	8/21/2024 17:11	0.2	0.2	0.2	0.2
474	8/21/2024 17:12	0.2	0.2	0.2	0.2
475	8/21/2024 17:13	0.2	0.2	0.2	0.2
476	8/21/2024 17:14	0.1	0.2	0.2	0.2
477	8/21/2024 17:15	0.1	1	3.8	0.3
478	8/21/2024 17:16	0.2	0.2	0.3	0.2
479	8/21/2024 17:17	0.2	0.2	0.2	0.2
480	8/21/2024 17:18	0.2	0.6	1.7	0.3
481	8/21/2024 17:19	0.2	0.2	0.3	0.2
Peak		1.8	71.2	237.6	13.2
Min		0	0	0	0
Average		0.1	0.4	1.5	0.3

NYSDEC Site No. 314008

TWA/STEL

Index	Date/Time	PID(ppm) (TWA)	PID(ppm) (STEL)
1	8/21/2024 9:19	0	---
2	8/21/2024 9:20	0	---
3	8/21/2024 9:21	0	---
4	8/21/2024 9:22	0	---
5	8/21/2024 9:23	0	---
6	8/21/2024 9:24	0	---
7	8/21/2024 9:25	0	---
8	8/21/2024 9:26	0	---
9	8/21/2024 9:27	0	---
10	8/21/2024 9:28	0	---
11	8/21/2024 9:29	0	---
12	8/21/2024 9:30	0	---
13	8/21/2024 9:31	0	---
14	8/21/2024 9:32	0	---
15	8/21/2024 9:33	0	0.1
16	8/21/2024 9:34	0	0.1
17	8/21/2024 9:35	0	0
18	8/21/2024 9:36	0	0
19	8/21/2024 9:37	0	0
20	8/21/2024 9:38	0	0
21	8/21/2024 9:39	0	0.2
22	8/21/2024 9:40	0	0.2
23	8/21/2024 9:41	0	0.2
24	8/21/2024 9:42	0	0.2
25	8/21/2024 9:43	0	0.2
26	8/21/2024 9:44	0	0.2
27	8/21/2024 9:45	0	0.2
28	8/21/2024 9:46	0	0.2
29	8/21/2024 9:47	0	0.2
30	8/21/2024 9:48	0	0.2
31	8/21/2024 9:49	0	0.2
32	8/21/2024 9:50	0	0.2
33	8/21/2024 9:51	0	0.2
34	8/21/2024 9:52	0	0.2
35	8/21/2024 9:53	0	0.5
36	8/21/2024 9:54	0	0.5
37	8/21/2024 9:55	0	0.3
38	8/21/2024 9:56	0	0.3
39	8/21/2024 9:57	0	0.3
40	8/21/2024 9:58	0	0.3
41	8/21/2024 9:59	0	0.3

NYSDEC Site No. 314008

42	8/21/2024 10:00	0	0.3
43	8/21/2024 10:01	0	0.3
44	8/21/2024 10:02	0	0.6
45	8/21/2024 10:03	0	0.6
46	8/21/2024 10:04	0	0.6
47	8/21/2024 10:05	0	0.6
48	8/21/2024 10:06	0	0.6
49	8/21/2024 10:07	0	0.6
50	8/21/2024 10:08	0	0.6
51	8/21/2024 10:09	0	0.4
52	8/21/2024 10:10	0	0.4
53	8/21/2024 10:11	0	0.4
54	8/21/2024 10:12	0	0.4
55	8/21/2024 10:13	0	0.4
56	8/21/2024 10:14	0	0.4
57	8/21/2024 10:15	0	0.4
58	8/21/2024 10:16	0	0.4
59	8/21/2024 10:17	0	0.4
60	8/21/2024 10:18	0	0
61	8/21/2024 10:19	0	0
62	8/21/2024 10:20	0	0
63	8/21/2024 10:21	0	0
64	8/21/2024 10:22	0	0
65	8/21/2024 10:23	0	0
66	8/21/2024 10:24	0	0
67	8/21/2024 10:25	0	0
68	8/21/2024 10:26	0	0
69	8/21/2024 10:27	0	0
70	8/21/2024 10:28	0	0
71	8/21/2024 10:29	0	0
72	8/21/2024 10:30	0	0
73	8/21/2024 10:31	0	0
74	8/21/2024 10:32	0	0
75	8/21/2024 10:33	0	0
76	8/21/2024 10:34	0	0
77	8/21/2024 10:35	0	0
78	8/21/2024 10:36	0	0
79	8/21/2024 10:37	0	0
80	8/21/2024 10:38	0	0.1
81	8/21/2024 10:39	0	0.1
82	8/21/2024 10:40	0	0.1
83	8/21/2024 10:41	0	0.1
84	8/21/2024 10:42	0	0
85	8/21/2024 10:43	0	0

NYSDEC Site No. 314008

86	8/21/2024 10:44	0	0
87	8/21/2024 10:45	0	0
88	8/21/2024 10:46	0	0
89	8/21/2024 10:47	0	0
90	8/21/2024 10:48	0	0
91	8/21/2024 10:49	0	0
92	8/21/2024 10:50	0	0.1
93	8/21/2024 10:51	0	0.1
94	8/21/2024 10:52	0	0
95	8/21/2024 10:53	0	0
96	8/21/2024 10:54	0	0
97	8/21/2024 10:55	0	0
98	8/21/2024 10:56	0	0
99	8/21/2024 10:57	0	0
100	8/21/2024 10:58	0	0
101	8/21/2024 10:59	0	0
102	8/21/2024 11:00	0	0
103	8/21/2024 11:01	0	0.1
104	8/21/2024 11:02	0	0.1
105	8/21/2024 11:03	0	0.1
106	8/21/2024 11:04	0	0.1
107	8/21/2024 11:05	0	0.1
108	8/21/2024 11:06	0	0.1
109	8/21/2024 11:07	0	0.1
110	8/21/2024 11:08	0	0.1
111	8/21/2024 11:09	0	0.1
112	8/21/2024 11:10	0	0.1
113	8/21/2024 11:11	0	0.1
114	8/21/2024 11:12	0	0.1
115	8/21/2024 11:13	0	0.1
116	8/21/2024 11:14	0	0.2
117	8/21/2024 11:15	0	0.1
118	8/21/2024 11:16	0	0.1
119	8/21/2024 11:17	0	0.1
120	8/21/2024 11:18	0	0.1
121	8/21/2024 11:19	0	0.1
122	8/21/2024 11:20	0	0.1
123	8/21/2024 11:21	0	0.1
124	8/21/2024 11:22	0	0
125	8/21/2024 11:23	0	0
126	8/21/2024 11:24	0	0
127	8/21/2024 11:25	0	0
128	8/21/2024 11:26	0	0
129	8/21/2024 11:27	0	0

NYSDEC Site No. 314008

130	8/21/2024 11:28	0	0.1
131	8/21/2024 11:29	0	0.1
132	8/21/2024 11:30	0	0.1
133	8/21/2024 11:31	0	0.1
134	8/21/2024 11:32	0	0.1
135	8/21/2024 11:33	0	0.2
136	8/21/2024 11:34	0	0.2
137	8/21/2024 11:35	0	0.2
138	8/21/2024 11:36	0	0.2
139	8/21/2024 11:37	0	0.2
140	8/21/2024 11:38	0	0.2
141	8/21/2024 11:39	0	0.2
142	8/21/2024 11:40	0	0.2
143	8/21/2024 11:41	0	0.1
144	8/21/2024 11:42	0	0.1
145	8/21/2024 11:43	0	0.1
146	8/21/2024 11:44	0	0
147	8/21/2024 11:45	0	0
148	8/21/2024 11:46	0	0
149	8/21/2024 11:47	0	0
150	8/21/2024 11:48	0	0
151	8/21/2024 11:49	0	0
152	8/21/2024 11:50	0	0
153	8/21/2024 11:51	0	0
154	8/21/2024 11:52	0	0
155	8/21/2024 11:53	0	0
156	8/21/2024 11:54	0	0
157	8/21/2024 11:55	0	0
158	8/21/2024 11:56	0	0
159	8/21/2024 11:57	0	0
160	8/21/2024 11:58	0	0
161	8/21/2024 11:59	0	0
162	8/21/2024 12:00	0	0
163	8/21/2024 12:01	0	0
164	8/21/2024 12:02	0	0
165	8/21/2024 12:03	0	0.1
166	8/21/2024 12:04	0	0.1
167	8/21/2024 12:05	0	0
168	8/21/2024 12:06	0	0
169	8/21/2024 12:07	0	0
170	8/21/2024 12:08	0	0
171	8/21/2024 12:09	0	0
172	8/21/2024 12:10	0	0
173	8/21/2024 12:11	0	0

NYSDEC Site No. 314008

174	8/21/2024 12:12	0	0
175	8/21/2024 12:13	0	0
176	8/21/2024 12:14	0	0
177	8/21/2024 12:15	0	0
178	8/21/2024 12:16	0	0
179	8/21/2024 12:17	0	0
180	8/21/2024 12:18	0	0
181	8/21/2024 12:19	0	0
182	8/21/2024 12:20	0	0
183	8/21/2024 12:21	0	0
184	8/21/2024 12:22	0	0
185	8/21/2024 12:23	0	0
186	8/21/2024 12:24	0	0
187	8/21/2024 12:25	0	0
188	8/21/2024 12:26	0	0
189	8/21/2024 12:27	0	0
190	8/21/2024 12:28	0	0
191	8/21/2024 12:29	0	0
192	8/21/2024 12:30	0	0
193	8/21/2024 12:31	0	0
194	8/21/2024 12:32	0	0
195	8/21/2024 12:33	0	0
196	8/21/2024 12:34	0	0
197	8/21/2024 12:35	0	0
198	8/21/2024 12:36	0	0
199	8/21/2024 12:37	0	0
200	8/21/2024 12:38	0	0
201	8/21/2024 12:39	0	0
202	8/21/2024 12:40	0	0
203	8/21/2024 12:41	0	0
204	8/21/2024 12:42	0	0
205	8/21/2024 12:43	0	0
206	8/21/2024 12:44	0	0
207	8/21/2024 12:45	0	0
208	8/21/2024 12:46	0	0.1
209	8/21/2024 12:47	0.1	0.2
210	8/21/2024 12:48	0.1	0.2
211	8/21/2024 12:49	0.1	0.2
212	8/21/2024 12:50	0.1	0.3
213	8/21/2024 12:51	0.1	0.4
214	8/21/2024 12:52	0.1	0.4
215	8/21/2024 12:53	0.1	0.5
216	8/21/2024 12:54	0.1	0.5
217	8/21/2024 12:55	0.1	0.6

NYSDEC Site No. 314008

218	8/21/2024 12:56	0.1	0.7
219	8/21/2024 12:57	0.1	0.7
220	8/21/2024 12:58	0.1	0.7
221	8/21/2024 12:59	0.1	0.8
222	8/21/2024 13:00	0.1	0.9
223	8/21/2024 13:01	0.1	0.9
224	8/21/2024 13:02	0.1	0.8
225	8/21/2024 13:03	0.1	0.8
226	8/21/2024 13:04	0.1	0.8
227	8/21/2024 13:05	0.1	0.8
228	8/21/2024 13:06	0.1	0.7
229	8/21/2024 13:07	0.1	0.6
230	8/21/2024 13:08	0.1	0.6
231	8/21/2024 13:09	0.1	0.6
232	8/21/2024 13:10	0.1	0.5
233	8/21/2024 13:11	0.1	0.5
234	8/21/2024 13:12	0.1	0.4
235	8/21/2024 13:13	0.1	0.4
236	8/21/2024 13:14	0.1	0.4
237	8/21/2024 13:15	0.1	0.3
238	8/21/2024 13:16	0.1	0.2
239	8/21/2024 13:17	0.1	0.5
240	8/21/2024 13:18	0.1	0.5
241	8/21/2024 13:19	0.1	0.4
242	8/21/2024 13:20	0.1	0.4
243	8/21/2024 13:21	0.1	0.4
244	8/21/2024 13:22	0.1	0.6
245	8/21/2024 13:23	0.1	0.6
246	8/21/2024 13:24	0.1	0.6
247	8/21/2024 13:25	0.1	0.6
248	8/21/2024 13:26	0.1	0.6
249	8/21/2024 13:27	0.1	0.7
250	8/21/2024 13:28	0.1	0.6
251	8/21/2024 13:29	0.1	0.6
252	8/21/2024 13:30	0.1	0.6
253	8/21/2024 13:31	0.1	0.6
254	8/21/2024 13:32	0.1	0.6
255	8/21/2024 13:33	0.1	0.4
256	8/21/2024 13:34	0.1	0.4
257	8/21/2024 13:35	0.1	0.4
258	8/21/2024 13:36	0.1	0.4
259	8/21/2024 13:37	0.1	0.4
260	8/21/2024 13:38	0.1	0.2
261	8/21/2024 13:39	0.1	0.2

NYSDEC Site No. 314008

262	8/21/2024 13:40	0.1	0.2
263	8/21/2024 13:41	0.1	0.2
264	8/21/2024 13:42	0.1	0.2
265	8/21/2024 13:43	0.1	0.2
266	8/21/2024 13:44	0.1	0.2
267	8/21/2024 13:45	0.1	0.2
268	8/21/2024 13:46	0.1	0.2
269	8/21/2024 13:47	0.1	0.2
270	8/21/2024 13:48	0.1	0.2
271	8/21/2024 13:49	0.1	0.2
272	8/21/2024 13:50	0.1	0.2
273	8/21/2024 13:51	0.1	0.2
274	8/21/2024 13:52	0.1	0.2
275	8/21/2024 13:53	0.1	0.2
276	8/21/2024 13:54	0.1	0.2
277	8/21/2024 13:55	0.1	0.2
278	8/21/2024 13:56	0.1	0.2
279	8/21/2024 13:57	0.1	0.2
280	8/21/2024 13:58	0.1	0.2
281	8/21/2024 13:59	0.1	0.2
282	8/21/2024 14:00	0.1	0.2
283	8/21/2024 14:01	0.1	0.2
284	8/21/2024 14:02	0.1	0.2
285	8/21/2024 14:03	0.1	0.2
286	8/21/2024 14:04	0.1	0.2
287	8/21/2024 14:05	0.1	0.2
288	8/21/2024 14:06	0.1	0.2
289	8/21/2024 14:07	0.1	0.1
290	8/21/2024 14:08	0.1	0.1
291	8/21/2024 14:09	0.1	0.1
292	8/21/2024 14:10	0.1	0.1
293	8/21/2024 14:11	0.1	0.1
294	8/21/2024 14:12	0.1	0.1
295	8/21/2024 14:13	0.1	0.1
296	8/21/2024 14:14	0.1	0.1
297	8/21/2024 14:15	0.1	0.1
298	8/21/2024 14:16	0.1	0.1
299	8/21/2024 14:17	0.1	0.1
300	8/21/2024 14:18	0.1	0.1
301	8/21/2024 14:19	0.1	0.1
302	8/21/2024 14:20	0.1	0.1
303	8/21/2024 14:21	0.1	0.1
304	8/21/2024 14:22	0.1	0.1
305	8/21/2024 14:23	0.1	0.1

NYSDEC Site No. 314008

306	8/21/2024 14:24	0.1	0.2
307	8/21/2024 14:25	0.1	0.2
308	8/21/2024 14:26	0.1	0.2
309	8/21/2024 14:27	0.1	0.2
310	8/21/2024 14:28	0.1	0.2
311	8/21/2024 14:29	0.1	0.2
312	8/21/2024 14:30	0.1	0.1
313	8/21/2024 14:31	0.1	0.7
314	8/21/2024 14:32	0.1	0.7
315	8/21/2024 14:33	0.1	0.7
316	8/21/2024 14:34	0.1	0.7
317	8/21/2024 14:35	0.1	0.7
318	8/21/2024 14:36	0.1	0.7
319	8/21/2024 14:37	0.1	0.7
320	8/21/2024 14:38	0.1	0.7
321	8/21/2024 14:39	0.1	0.7
322	8/21/2024 14:40	0.1	0.7
323	8/21/2024 14:41	0.1	0.7
324	8/21/2024 14:42	0.1	0.7
325	8/21/2024 14:43	0.1	0.7
326	8/21/2024 14:44	0.1	0.9
327	8/21/2024 14:45	0.1	0.9
328	8/21/2024 14:46	0.1	0.9
329	8/21/2024 14:47	0.1	0.3
330	8/21/2024 14:48	0.1	0.3
331	8/21/2024 14:49	0.1	0.3
332	8/21/2024 14:50	0.1	0.3
333	8/21/2024 14:51	0.1	0.3
334	8/21/2024 14:52	0.1	0.3
335	8/21/2024 14:53	0.1	0.3
336	8/21/2024 14:54	0.1	0.3
337	8/21/2024 14:55	0.1	0.3
338	8/21/2024 14:56	0.1	0.3
339	8/21/2024 14:57	0.1	0.3
340	8/21/2024 14:58	0.1	0.3
341	8/21/2024 14:59	0.1	0.3
342	8/21/2024 15:00	0.1	0.1
343	8/21/2024 15:01	0.1	0.1
344	8/21/2024 15:02	0.1	0.1
345	8/21/2024 15:03	0.1	0.1
346	8/21/2024 15:04	0.1	0.1
347	8/21/2024 15:05	0.1	0.1
348	8/21/2024 15:06	0.1	0.1
349	8/21/2024 15:07	0.1	0.1

NYSDEC Site No. 314008

350	8/21/2024 15:08	0.1	0.1
351	8/21/2024 15:09	0.1	0.1
352	8/21/2024 15:10	0.1	0.1
353	8/21/2024 15:11	0.2	0.1
354	8/21/2024 15:12	0.2	0.1
355	8/21/2024 15:13	0.2	0.1
356	8/21/2024 15:14	0.2	0.1
357	8/21/2024 15:15	0.2	0.1
358	8/21/2024 15:16	0.2	0.1
359	8/21/2024 15:17	0.2	0.1
360	8/21/2024 15:18	0.2	0.1
361	8/21/2024 15:19	0.2	0.1
362	8/21/2024 15:20	0.2	0.1
363	8/21/2024 15:21	0.2	0.1
364	8/21/2024 15:22	0.2	0.1
365	8/21/2024 15:23	0.2	0.1
366	8/21/2024 15:24	0.2	0.1
367	8/21/2024 15:25	0.2	0.1
368	8/21/2024 15:26	0.2	0.1
369	8/21/2024 15:27	0.2	0.1
370	8/21/2024 15:28	0.2	0.1
371	8/21/2024 15:29	0.2	0.1
372	8/21/2024 15:30	0.2	0.2
373	8/21/2024 15:31	0.2	0.2
374	8/21/2024 15:32	0.2	0.2
375	8/21/2024 15:33	0.2	0.2
376	8/21/2024 15:34	0.2	0.2
377	8/21/2024 15:35	0.2	0.2
378	8/21/2024 15:36	0.2	0.2
379	8/21/2024 15:37	0.2	0.1
380	8/21/2024 15:38	0.2	0.1
381	8/21/2024 15:39	0.2	0.1
382	8/21/2024 15:40	0.2	0.2
383	8/21/2024 15:41	0.2	0.2
384	8/21/2024 15:42	0.2	0.2
385	8/21/2024 15:43	0.2	0.2
386	8/21/2024 15:44	0.2	0.2
387	8/21/2024 15:45	0.2	0.2
388	8/21/2024 15:46	0.2	0.2
389	8/21/2024 15:47	0.2	0.2
390	8/21/2024 15:48	0.2	0.2
391	8/21/2024 15:49	0.2	0.8
392	8/21/2024 15:50	0.2	0.8
393	8/21/2024 15:51	0.2	0.8

NYSDEC Site No. 314008

394	8/21/2024 15:52	0.2	0.8
395	8/21/2024 15:53	0.2	0.8
396	8/21/2024 15:54	0.2	0.8
397	8/21/2024 15:55	0.2	0.8
398	8/21/2024 15:56	0.2	0.7
399	8/21/2024 15:57	0.2	0.7
400	8/21/2024 15:58	0.2	0.7
401	8/21/2024 15:59	0.2	0.7
402	8/21/2024 16:00	0.2	0.7
403	8/21/2024 16:01	0.2	0.7
404	8/21/2024 16:02	0.2	0.7
405	8/21/2024 16:03	0.2	0.7
406	8/21/2024 16:04	0.2	0.7
407	8/21/2024 16:05	0.2	0.1
408	8/21/2024 16:06	0.2	0.1
409	8/21/2024 16:07	0.2	0.1
410	8/21/2024 16:08	0.2	0.1
411	8/21/2024 16:09	0.2	0.1
412	8/21/2024 16:10	0.2	0.1
413	8/21/2024 16:11	0.2	0.1
414	8/21/2024 16:12	0.2	0.1
415	8/21/2024 16:13	0.2	0.1
416	8/21/2024 16:14	0.2	0.1
417	8/21/2024 16:15	0.2	0.1
418	8/21/2024 16:16	0.2	0.1
419	8/21/2024 16:17	0.2	0.2
420	8/21/2024 16:18	0.2	0.2
421	8/21/2024 16:19	0.2	0.2
422	8/21/2024 16:20	0.2	0.2
423	8/21/2024 16:21	0.2	0.2
424	8/21/2024 16:22	0.2	0.2
425	8/21/2024 16:23	0.2	0.2
426	8/21/2024 16:24	0.2	0.2
427	8/21/2024 16:25	0.2	0.2
428	8/21/2024 16:26	0.2	0.2
429	8/21/2024 16:27	0.2	0.2
430	8/21/2024 16:28	0.2	0.2
431	8/21/2024 16:29	0.2	0.2
432	8/21/2024 16:30	0.2	0.2
433	8/21/2024 16:31	0.2	0.2
434	8/21/2024 16:32	0.2	0.2
435	8/21/2024 16:33	0.2	0.1
436	8/21/2024 16:34	0.2	0.2
437	8/21/2024 16:35	0.2	0.2

NYSDEC Site No. 314008

438	8/21/2024 16:36	0.2	0.3
439	8/21/2024 16:37	0.2	0.3
440	8/21/2024 16:38	0.2	0.3
441	8/21/2024 16:39	0.2	0.3
442	8/21/2024 16:40	0.2	0.3
443	8/21/2024 16:41	0.2	0.3
444	8/21/2024 16:42	0.2	0.3
445	8/21/2024 16:43	0.2	0.3
446	8/21/2024 16:44	0.2	0.4
447	8/21/2024 16:45	0.2	0.4
448	8/21/2024 16:46	0.2	0.4
449	8/21/2024 16:47	0.2	0.4
450	8/21/2024 16:48	0.2	0.3
451	8/21/2024 16:49	0.2	0.3
452	8/21/2024 16:50	0.2	0.3
453	8/21/2024 16:51	0.2	0.2
454	8/21/2024 16:52	0.2	0.2
455	8/21/2024 16:53	0.2	0.2
456	8/21/2024 16:54	0.2	0.1
457	8/21/2024 16:55	0.2	0.1
458	8/21/2024 16:56	0.2	0.2
459	8/21/2024 16:57	0.2	0.2
460	8/21/2024 16:58	0.2	0.2
461	8/21/2024 16:59	0.2	0.2
462	8/21/2024 17:00	0.2	0.3
463	8/21/2024 17:01	0.2	0.3
464	8/21/2024 17:02	0.2	0.3
465	8/21/2024 17:03	0.2	1.1
466	8/21/2024 17:04	0.3	1.6
467	8/21/2024 17:05	0.3	1.8
468	8/21/2024 17:06	0.3	1.9
469	8/21/2024 17:07	0.3	1.9
470	8/21/2024 17:08	0.3	1.9
471	8/21/2024 17:09	0.3	1.9
472	8/21/2024 17:10	0.3	1.9
473	8/21/2024 17:11	0.3	1.9
474	8/21/2024 17:12	0.3	1.9
475	8/21/2024 17:13	0.3	1.9
476	8/21/2024 17:14	0.3	1.9
477	8/21/2024 17:15	0.3	1.9
478	8/21/2024 17:16	0.3	1.9
479	8/21/2024 17:17	0.3	1.9
480	8/21/2024 17:18	0.3	1.9
481	8/21/2024 17:19	0.3	1

=====
24/08/22 08:08

Summary

Unit Name MiniRAE 3000 +(PGM-7320)

Unit SN 592-927758

Unit Firmw V2.22A

Running Mode Hygiene Mode

Datalog Mode Auto

Diagnostic No

Stop Reason Power Down

Site ID RAE00000

User ID USER0000

Begin 8/22/2024 8:08

End 8/22/2024 8:08

Sample Period 60

Number of 0

Sensor PID(ppm)

Sensor SN S023030115B6

Measure Type Min; Avg; Max; Real

Span 100

Span 2 1000

Low Alarm 50

High Alarm 100

Over Alarm 15000

STEL Alarm 25

TWA Alarm 10

Measurement Isobutylene

Calibration 8/13/2024 10:59

Datalog

0 record.

=====
24/08/22 08:09

Summary

Unit Name MiniRAE 3000 +(PGM-7320)

Unit SN 592-927758

Unit Firmw V2.22A

Running Mode Hygiene Mode

Datalog Mode Auto

Diagnostic No

Stop Reason Power Down

Site ID RAE00000

User ID USER0000

Begin 8/22/2024 8:09

End 8/22/2024 8:10

Sample Period 60

Number of 0

Sensor PID(ppm)

Sensor SN S023030115B6

Measure Type Min; Avg; Max; Real

Span 100

Span 2 1000

Low Alarm 50

High Alarm 100

Over Alarm 15000

STEL Alarm 25

TWA Alarm 10

Measurement Isobutylene

Calibration 8/13/2024 10:59

Datalog

0 record.

=====
24/08/22 08:10

Summary

Unit Name MiniRAE 3000 +(PGM-7320)

Unit SN 592-927758

Unit Firmw V2.22A

Running Mode Hygiene Mode
Datalog Mode Auto
Diagnostic No
Stop Reason Power Down

Site ID RAE00000
User ID USER0000

Begin 8/22/2024 8:10
End 8/22/2024 17:48
Sample Period 60
Number of 577

Sensor PID(ppm)
Sensor SN S023030115B6
Measure Type Min; Avg; Max; Real
Span 100
Span 2 1000
Low Alarm 50
High Alarm 100
Over Alarm 15000
STEL Alarm 25
TWA Alarm 10
Measurement Isobutylene
Calibration 8/13/2024 10:59
Peak 0.2
Min 0
Average 0

Datalog

Index	Date/Time	PID(ppm) (Min)	PID(ppm) (Avg)	PID(ppm) (Max)	PID(ppm) (Real)
1	8/22/2024 8:11	0	0	0	0
2	8/22/2024 8:12	0	0	0	0
3	8/22/2024 8:13	0	0	0	0
4	8/22/2024 8:14	0	0	0	0
5	8/22/2024 8:15	0	0	0	0
6	8/22/2024 8:16	0	0	0	0
7	8/22/2024 8:17	0	0	0	0
8	8/22/2024 8:18	0	0	0	0
9	8/22/2024 8:19	0	0	0	0
10	8/22/2024 8:20	0	0	0	0

NYSDEC Site No. 314008

11	8/22/2024 8:21	0	0	0	0
12	8/22/2024 8:22	0	0	0	0
13	8/22/2024 8:23	0	0	0	0
14	8/22/2024 8:24	0	0	0	0
15	8/22/2024 8:25	0	0	0	0
16	8/22/2024 8:26	0	0	0	0
17	8/22/2024 8:27	0	0	0	0
18	8/22/2024 8:28	0	0	0	0
19	8/22/2024 8:29	0	0	0	0
20	8/22/2024 8:30	0	0	0	0
21	8/22/2024 8:31	0	0	0	0
22	8/22/2024 8:32	0	0	0	0
23	8/22/2024 8:33	0	0	0	0
24	8/22/2024 8:34	0	0	0	0
25	8/22/2024 8:35	0	0	0	0
26	8/22/2024 8:36	0	0	0	0
27	8/22/2024 8:37	0	0	0	0
28	8/22/2024 8:38	0	0	0	0
29	8/22/2024 8:39	0	0	0	0
30	8/22/2024 8:40	0	0	0	0
31	8/22/2024 8:41	0	0	0	0
32	8/22/2024 8:42	0	0	0	0
33	8/22/2024 8:43	0	0	0	0
34	8/22/2024 8:44	0	0	0	0
35	8/22/2024 8:45	0	0	0	0
36	8/22/2024 8:46	0	0	0	0
37	8/22/2024 8:47	0	0	0	0
38	8/22/2024 8:48	0	0	0	0
39	8/22/2024 8:49	0	0	0	0
40	8/22/2024 8:50	0	0	0	0
41	8/22/2024 8:51	0	0	0	0
42	8/22/2024 8:52	0	0	0	0
43	8/22/2024 8:53	0	0	0	0
44	8/22/2024 8:54	0	0	0	0
45	8/22/2024 8:55	0	0	0	0
46	8/22/2024 8:56	0	0	0	0
47	8/22/2024 8:57	0	0	0	0
48	8/22/2024 8:58	0	0	0	0
49	8/22/2024 8:59	0	0	0	0
50	8/22/2024 9:00	0	0	0	0
51	8/22/2024 9:01	0	0	0	0
52	8/22/2024 9:02	0	0	0	0
53	8/22/2024 9:03	0	0	0	0
54	8/22/2024 9:04	0	0	0	0

NYSDEC Site No. 314008

55	8/22/2024 9:05	0	0	0	0
56	8/22/2024 9:06	0	0	0	0
57	8/22/2024 9:07	0	0	0	0
58	8/22/2024 9:08	0	0	0	0
59	8/22/2024 9:09	0	0	0	0
60	8/22/2024 9:10	0	0	0	0
61	8/22/2024 9:11	0	0	0	0
62	8/22/2024 9:12	0	0	0	0
63	8/22/2024 9:13	0	0	0	0
64	8/22/2024 9:14	0	0	0	0
65	8/22/2024 9:15	0	0	0	0
66	8/22/2024 9:16	0	0	0	0
67	8/22/2024 9:17	0	0	0	0
68	8/22/2024 9:18	0	0	0	0
69	8/22/2024 9:19	0	0	0	0
70	8/22/2024 9:20	0	0	0	0
71	8/22/2024 9:21	0	0	0	0
72	8/22/2024 9:22	0	0	0	0
73	8/22/2024 9:23	0	0	0	0
74	8/22/2024 9:24	0	0	0	0
75	8/22/2024 9:25	0	0	0	0
76	8/22/2024 9:26	0	0	0	0
77	8/22/2024 9:27	0	0	0	0
78	8/22/2024 9:28	0	0	0	0
79	8/22/2024 9:29	0	0	0	0
80	8/22/2024 9:30	0	0	0	0
81	8/22/2024 9:31	0	0	0	0
82	8/22/2024 9:32	0	0	0	0
83	8/22/2024 9:33	0	0	0	0
84	8/22/2024 9:34	0	0	0	0
85	8/22/2024 9:35	0	0	0	0
86	8/22/2024 9:36	0	0	0	0
87	8/22/2024 9:37	0	0	0	0
88	8/22/2024 9:38	0	0	0	0
89	8/22/2024 9:39	0	0	0	0
90	8/22/2024 9:40	0	0	0	0
91	8/22/2024 9:41	0	0	0	0
92	8/22/2024 9:42	0	0	0	0
93	8/22/2024 9:43	0	0	0	0
94	8/22/2024 9:44	0	0	0	0
95	8/22/2024 9:45	0	0	0	0
96	8/22/2024 9:46	0	0	0	0
97	8/22/2024 9:47	0	0	0	0
98	8/22/2024 9:48	0	0	0	0

NYSDEC Site No. 314008

99	8/22/2024 9:49	0	0	0	0
100	8/22/2024 9:50	0	0	0	0
101	8/22/2024 9:51	0	0	0	0
102	8/22/2024 9:52	0	0	0	0
103	8/22/2024 9:53	0	0	0	0
104	8/22/2024 9:54	0	0	0	0
105	8/22/2024 9:55	0	0	0	0
106	8/22/2024 9:56	0	0	0	0
107	8/22/2024 9:57	0	0	0	0
108	8/22/2024 9:58	0	0	0	0
109	8/22/2024 9:59	0	0	0	0
110	8/22/2024 10:00	0	0	0	0
111	8/22/2024 10:01	0	0	0.2	0.2
112	8/22/2024 10:02	0	0.1	0.6	0
113	8/22/2024 10:03	0	0	0	0
114	8/22/2024 10:04	0	0	0	0
115	8/22/2024 10:05	0	0	0	0
116	8/22/2024 10:06	0	0	0	0
117	8/22/2024 10:07	0	0	0	0
118	8/22/2024 10:08	0	0	0	0
119	8/22/2024 10:09	0	0	0	0
120	8/22/2024 10:10	0	0	0	0
121	8/22/2024 10:11	0	0	0	0
122	8/22/2024 10:12	0	0	0	0
123	8/22/2024 10:13	0	0	0	0
124	8/22/2024 10:14	0	0	0	0
125	8/22/2024 10:15	0	0	0	0
126	8/22/2024 10:16	0	0	0	0
127	8/22/2024 10:17	0	0	0	0
128	8/22/2024 10:18	0	0	0	0
129	8/22/2024 10:19	0	0	0	0
130	8/22/2024 10:20	0	0	0	0
131	8/22/2024 10:21	0	0	0	0
132	8/22/2024 10:22	0	0	0	0
133	8/22/2024 10:23	0	0	0	0
134	8/22/2024 10:24	0	0	0	0
135	8/22/2024 10:25	0	0	0	0
136	8/22/2024 10:26	0	0	0	0
137	8/22/2024 10:27	0	0	0	0
138	8/22/2024 10:28	0	0	0	0
139	8/22/2024 10:29	0	0	0	0
140	8/22/2024 10:30	0	0	0	0
141	8/22/2024 10:31	0	0	0	0
142	8/22/2024 10:32	0	0	0	0

NYSDEC Site No. 314008

143	8/22/2024 10:33	0	0	0	0
144	8/22/2024 10:34	0	0	0	0
145	8/22/2024 10:35	0	0	0	0
146	8/22/2024 10:36	0	0	0	0
147	8/22/2024 10:37	0	0	0	0
148	8/22/2024 10:38	0	0	0	0
149	8/22/2024 10:39	0	0	0	0
150	8/22/2024 10:40	0	0	0	0
151	8/22/2024 10:41	0	0	0	0
152	8/22/2024 10:42	0	0	0	0
153	8/22/2024 10:43	0	0	0	0
154	8/22/2024 10:44	0	0	0	0
155	8/22/2024 10:45	0	0	0	0
156	8/22/2024 10:46	0	0	0	0
157	8/22/2024 10:47	0	0	0	0
158	8/22/2024 10:48	0	0	0	0
159	8/22/2024 10:49	0	0	0	0
160	8/22/2024 10:50	0	0	0	0
161	8/22/2024 10:51	0	0	0	0
162	8/22/2024 10:52	0	0	0	0
163	8/22/2024 10:53	0	0	0	0
164	8/22/2024 10:54	0	0	0	0
165	8/22/2024 10:55	0	0	0	0
166	8/22/2024 10:56	0	0	0	0
167	8/22/2024 10:57	0	0	0	0
168	8/22/2024 10:58	0	0	0	0
169	8/22/2024 10:59	0	0	0	0
170	8/22/2024 11:00	0	0	0	0
171	8/22/2024 11:01	0	0	0	0
172	8/22/2024 11:02	0	0	0	0
173	8/22/2024 11:03	0	0	0	0
174	8/22/2024 11:04	0	0	0	0
175	8/22/2024 11:05	0	0	0	0
176	8/22/2024 11:06	0	0	0	0
177	8/22/2024 11:07	0	0	0	0
178	8/22/2024 11:08	0	0	0	0
179	8/22/2024 11:09	0	0	0	0
180	8/22/2024 11:10	0	0	0	0
181	8/22/2024 11:11	0	0	0	0
182	8/22/2024 11:12	0	0	0	0
183	8/22/2024 11:13	0	0	0	0
184	8/22/2024 11:14	0	0	0	0
185	8/22/2024 11:15	0	0	0	0
186	8/22/2024 11:16	0	0	0	0

NYSDEC Site No. 314008

187	8/22/2024 11:17	0	0	0	0
188	8/22/2024 11:18	0	0	0	0
189	8/22/2024 11:19	0	0	0	0
190	8/22/2024 11:20	0	0	0	0
191	8/22/2024 11:21	0	0	0	0
192	8/22/2024 11:22	0	0	0	0
193	8/22/2024 11:23	0	0	0	0
194	8/22/2024 11:24	0	0	0	0
195	8/22/2024 11:25	0	0	0	0
196	8/22/2024 11:26	0	0	0	0
197	8/22/2024 11:27	0	0	0	0
198	8/22/2024 11:28	0	0	0	0
199	8/22/2024 11:29	0	0	0	0
200	8/22/2024 11:30	0	0	0	0
201	8/22/2024 11:31	0	0	0	0
202	8/22/2024 11:32	0	0	0	0
203	8/22/2024 11:33	0	0	0	0
204	8/22/2024 11:34	0	0	0	0
205	8/22/2024 11:35	0	0	0	0
206	8/22/2024 11:36	0	0	0	0
207	8/22/2024 11:37	0	0	0	0
208	8/22/2024 11:38	0	0	0	0
209	8/22/2024 11:39	0	0	0	0
210	8/22/2024 11:40	0	0	0	0
211	8/22/2024 11:41	0	0	0	0
212	8/22/2024 11:42	0	0	0	0
213	8/22/2024 11:43	0	0	0	0
214	8/22/2024 11:44	0	0	0	0
215	8/22/2024 11:45	0	0	0	0
216	8/22/2024 11:46	0	0	0	0
217	8/22/2024 11:47	0	0	0	0
218	8/22/2024 11:48	0	0	0	0
219	8/22/2024 11:49	0	0	0	0
220	8/22/2024 11:50	0	0	0	0
221	8/22/2024 11:51	0	0	0	0
222	8/22/2024 11:52	0	0	0	0
223	8/22/2024 11:53	0	0	0	0
224	8/22/2024 11:54	0	0	0	0
225	8/22/2024 11:55	0	0	0	0
226	8/22/2024 11:56	0	0	0	0
227	8/22/2024 11:57	0	0	0	0
228	8/22/2024 11:58	0	0	0	0
229	8/22/2024 11:59	0	0	0	0
230	8/22/2024 12:00	0	0	0	0

NYSDEC Site No. 314008

231	8/22/2024 12:01	0	0	0	0
232	8/22/2024 12:02	0	0	0	0
233	8/22/2024 12:03	0	0	0	0
234	8/22/2024 12:04	0	0	0	0
235	8/22/2024 12:05	0	0	0	0
236	8/22/2024 12:06	0	0	0	0
237	8/22/2024 12:07	0	0	0	0
238	8/22/2024 12:08	0	0	0	0
239	8/22/2024 12:09	0	0	0	0
240	8/22/2024 12:10	0	0	0	0
241	8/22/2024 12:11	0	0	0	0
242	8/22/2024 12:12	0	0	0	0
243	8/22/2024 12:13	0	0	0	0
244	8/22/2024 12:14	0	0	0	0
245	8/22/2024 12:15	0	0	0	0
246	8/22/2024 12:16	0	0	0	0
247	8/22/2024 12:17	0	0	0	0
248	8/22/2024 12:18	0	0	0	0
249	8/22/2024 12:19	0	0	0	0
250	8/22/2024 12:20	0	0	0	0
251	8/22/2024 12:21	0	0	0	0
252	8/22/2024 12:22	0	0	0	0
253	8/22/2024 12:23	0	0	0	0
254	8/22/2024 12:24	0	0	0	0
255	8/22/2024 12:25	0	0	0	0
256	8/22/2024 12:26	0	0	0	0
257	8/22/2024 12:27	0	0	0	0
258	8/22/2024 12:28	0	0	0	0
259	8/22/2024 12:29	0	0	0	0
260	8/22/2024 12:30	0	0	0	0
261	8/22/2024 12:31	0	0	0	0
262	8/22/2024 12:32	0	0	0	0
263	8/22/2024 12:33	0	0	0	0
264	8/22/2024 12:34	0	0	0	0
265	8/22/2024 12:35	0	0	0	0
266	8/22/2024 12:36	0	0	0	0
267	8/22/2024 12:37	0	0	0	0
268	8/22/2024 12:38	0	0	0	0
269	8/22/2024 12:39	0	0	0	0
270	8/22/2024 12:40	0	0	0	0
271	8/22/2024 12:41	0	0	0	0
272	8/22/2024 12:42	0	0	0	0
273	8/22/2024 12:43	0	0	0	0
274	8/22/2024 12:44	0	0	0	0

NYSDEC Site No. 314008

275	8/22/2024 12:45	0	0	0	0
276	8/22/2024 12:46	0	0	0	0
277	8/22/2024 12:47	0	0	0	0
278	8/22/2024 12:48	0	0	0	0
279	8/22/2024 12:49	0	0	0	0
280	8/22/2024 12:50	0	0	0	0
281	8/22/2024 12:51	0	0	0	0
282	8/22/2024 12:52	0	0	0	0
283	8/22/2024 12:53	0	0	0	0
284	8/22/2024 12:54	0	0	0	0
285	8/22/2024 12:55	0	0	0	0
286	8/22/2024 12:56	0	0	0	0
287	8/22/2024 12:57	0	0	0	0
288	8/22/2024 12:58	0	0	0	0
289	8/22/2024 12:59	0	0	0	0
290	8/22/2024 13:00	0	0	0	0
291	8/22/2024 13:01	0	0	0	0
292	8/22/2024 13:02	0	0	0	0
293	8/22/2024 13:03	0	0	0	0
294	8/22/2024 13:04	0	0	0	0
295	8/22/2024 13:05	0	0	0	0
296	8/22/2024 13:06	0	0	0	0
297	8/22/2024 13:07	0	0	0	0
298	8/22/2024 13:08	0	0	0	0
299	8/22/2024 13:09	0	0	0	0
300	8/22/2024 13:10	0	0	0	0
301	8/22/2024 13:11	0	0	0	0
302	8/22/2024 13:12	0	0	0	0
303	8/22/2024 13:13	0	0	0	0
304	8/22/2024 13:14	0	0	0	0
305	8/22/2024 13:15	0	0	0	0
306	8/22/2024 13:16	0	0	0	0
307	8/22/2024 13:17	0	0	0	0
308	8/22/2024 13:18	0	0	0	0
309	8/22/2024 13:19	0	0	0	0
310	8/22/2024 13:20	0	0	0	0
311	8/22/2024 13:21	0	0	0	0
312	8/22/2024 13:22	0	0	0	0
313	8/22/2024 13:23	0	0	0	0
314	8/22/2024 13:24	0	0	0	0
315	8/22/2024 13:25	0	0	0	0
316	8/22/2024 13:26	0	0	0	0
317	8/22/2024 13:27	0	0	0	0
318	8/22/2024 13:28	0	0	0	0

NYSDEC Site No. 314008

319	8/22/2024 13:29	0	0	0	0
320	8/22/2024 13:30	0	0	0	0
321	8/22/2024 13:31	0	0	0	0
322	8/22/2024 13:32	0	0	0	0
323	8/22/2024 13:33	0	0	0	0
324	8/22/2024 13:34	0	0	0	0
325	8/22/2024 13:35	0	0	0	0
326	8/22/2024 13:36	0	0	0	0
327	8/22/2024 13:37	0	0	0	0
328	8/22/2024 13:38	0	0	0	0
329	8/22/2024 13:39	0	0	0	0
330	8/22/2024 13:40	0	0	0	0
331	8/22/2024 13:41	0	0	0	0
332	8/22/2024 13:42	0	0	0	0
333	8/22/2024 13:43	0	0	0	0
334	8/22/2024 13:44	0	0	0	0
335	8/22/2024 13:45	0	0	0	0
336	8/22/2024 13:46	0	0	0	0
337	8/22/2024 13:47	0	0	0	0
338	8/22/2024 13:48	0	0	0	0
339	8/22/2024 13:49	0	0	0	0
340	8/22/2024 13:50	0	0	0	0
341	8/22/2024 13:51	0	0	0	0
342	8/22/2024 13:52	0	0	0	0
343	8/22/2024 13:53	0	0	0	0
344	8/22/2024 13:54	0	0	0	0
345	8/22/2024 13:55	0	0	0	0
346	8/22/2024 13:56	0	0	0	0
347	8/22/2024 13:57	0	0	0	0
348	8/22/2024 13:58	0	0	0	0
349	8/22/2024 13:59	0	0	0	0
350	8/22/2024 14:00	0	0	0	0
351	8/22/2024 14:01	0	0	0	0
352	8/22/2024 14:02	0	0	0	0
353	8/22/2024 14:03	0	0	0	0
354	8/22/2024 14:04	0	0	0	0
355	8/22/2024 14:05	0	0	0	0
356	8/22/2024 14:06	0	0	0	0
357	8/22/2024 14:07	0	0	0	0
358	8/22/2024 14:08	0	0	0	0
359	8/22/2024 14:09	0	0	0	0
360	8/22/2024 14:10	0	0	0	0
361	8/22/2024 14:11	0	0	0	0
362	8/22/2024 14:12	0	0	0	0

NYSDEC Site No. 314008

363	8/22/2024 14:13	0	0	0	0
364	8/22/2024 14:14	0	0	0	0
365	8/22/2024 14:15	0	0	0	0
366	8/22/2024 14:16	0	0	0	0
367	8/22/2024 14:17	0	0	0	0
368	8/22/2024 14:18	0	0	0	0
369	8/22/2024 14:19	0	0	0	0
370	8/22/2024 14:20	0	0	0	0
371	8/22/2024 14:21	0	0	0	0
372	8/22/2024 14:22	0	0	0	0
373	8/22/2024 14:23	0	0	0	0
374	8/22/2024 14:24	0	0	0	0
375	8/22/2024 14:25	0	0	0	0
376	8/22/2024 14:26	0	0	0	0
377	8/22/2024 14:27	0	0	0	0
378	8/22/2024 14:28	0	0	0	0
379	8/22/2024 14:29	0	0	0	0
380	8/22/2024 14:30	0	0	0	0
381	8/22/2024 14:31	0	0	0	0
382	8/22/2024 14:32	0	0	0	0
383	8/22/2024 14:33	0	0	0	0
384	8/22/2024 14:34	0	0	0	0
385	8/22/2024 14:35	0	0	0	0
386	8/22/2024 14:36	0	0	0	0
387	8/22/2024 14:37	0	0	0	0
388	8/22/2024 14:38	0	0	0	0
389	8/22/2024 14:39	0	0	0	0
390	8/22/2024 14:40	0	0	0	0
391	8/22/2024 14:41	0	0	0	0
392	8/22/2024 14:42	0	0	0	0
393	8/22/2024 14:43	0	0	0	0
394	8/22/2024 14:44	0	0	0	0
395	8/22/2024 14:45	0	0	0	0
396	8/22/2024 14:46	0	0	0	0
397	8/22/2024 14:47	0	0	0	0
398	8/22/2024 14:48	0	0	0	0
399	8/22/2024 14:49	0	0	0	0
400	8/22/2024 14:50	0	0	0	0
401	8/22/2024 14:51	0	0	0	0
402	8/22/2024 14:52	0	0	0	0
403	8/22/2024 14:53	0	0	0	0
404	8/22/2024 14:54	0	0	0	0
405	8/22/2024 14:55	0	0	0	0
406	8/22/2024 14:56	0	0	0	0

NYSDEC Site No. 314008

407	8/22/2024 14:57	0	0	0	0
408	8/22/2024 14:58	0	0	0	0
409	8/22/2024 14:59	0	0	0	0
410	8/22/2024 15:00	0	0	0	0
411	8/22/2024 15:01	0	0	0	0
412	8/22/2024 15:02	0	0	0	0
413	8/22/2024 15:03	0	0	0	0
414	8/22/2024 15:04	0	0	0	0
415	8/22/2024 15:05	0	0	0	0
416	8/22/2024 15:06	0	0	0	0
417	8/22/2024 15:07	0	0	0	0
418	8/22/2024 15:08	0	0	0	0
419	8/22/2024 15:09	0	0	0	0
420	8/22/2024 15:10	0	0	0	0
421	8/22/2024 15:11	0	0	0	0
422	8/22/2024 15:12	0	0	0	0
423	8/22/2024 15:13	0	0	0	0
424	8/22/2024 15:14	0	0	0	0
425	8/22/2024 15:15	0	0	0	0
426	8/22/2024 15:16	0	0	0	0
427	8/22/2024 15:17	0	0	0	0
428	8/22/2024 15:18	0	0	0	0
429	8/22/2024 15:19	0	0	0	0
430	8/22/2024 15:20	0	0	0	0
431	8/22/2024 15:21	0	0	0	0
432	8/22/2024 15:22	0	0	0	0
433	8/22/2024 15:23	0	0	0	0
434	8/22/2024 15:24	0	0	0	0
435	8/22/2024 15:25	0	0	0	0
436	8/22/2024 15:26	0	0	0	0
437	8/22/2024 15:27	0	0	0	0
438	8/22/2024 15:28	0	0	0	0
439	8/22/2024 15:29	0	0	0	0
440	8/22/2024 15:30	0	0	0	0
441	8/22/2024 15:31	0	0	0	0
442	8/22/2024 15:32	0	0	0	0
443	8/22/2024 15:33	0	0	0	0
444	8/22/2024 15:34	0	0	0	0
445	8/22/2024 15:35	0	0	0	0
446	8/22/2024 15:36	0	0	0	0
447	8/22/2024 15:37	0	0	0	0
448	8/22/2024 15:38	0	0	0	0
449	8/22/2024 15:39	0	0	0	0
450	8/22/2024 15:40	0	0	0	0

NYSDEC Site No. 314008

451	8/22/2024 15:41	0	0	0	0
452	8/22/2024 15:42	0	0	0	0
453	8/22/2024 15:43	0	0	0	0
454	8/22/2024 15:44	0	0	0	0
455	8/22/2024 15:45	0	0	0	0
456	8/22/2024 15:46	0	0	0	0
457	8/22/2024 15:47	0	0	0	0
458	8/22/2024 15:48	0	0	0	0
459	8/22/2024 15:49	0	0	0	0
460	8/22/2024 15:50	0	0	0	0
461	8/22/2024 15:51	0	0	0	0
462	8/22/2024 15:52	0	0	0	0
463	8/22/2024 15:53	0	0	0	0
464	8/22/2024 15:54	0	0	0	0
465	8/22/2024 15:55	0	0	0	0
466	8/22/2024 15:56	0	0	0	0
467	8/22/2024 15:57	0	0	0	0
468	8/22/2024 15:58	0	0	0	0
469	8/22/2024 15:59	0	0	0	0
470	8/22/2024 16:00	0	0	0	0
471	8/22/2024 16:01	0	0	0	0
472	8/22/2024 16:02	0	0	0	0
473	8/22/2024 16:03	0	0	0	0
474	8/22/2024 16:04	0	0	0	0
475	8/22/2024 16:05	0	0	0	0
476	8/22/2024 16:06	0	0	0	0
477	8/22/2024 16:07	0	0	0	0
478	8/22/2024 16:08	0	0	0	0
479	8/22/2024 16:09	0	0	0.1	0
480	8/22/2024 16:10	0	0	0	0
481	8/22/2024 16:11	0	0	0	0
482	8/22/2024 16:12	0	0	0	0
483	8/22/2024 16:13	0	0	0	0
484	8/22/2024 16:14	0	0	0	0
485	8/22/2024 16:15	0	0	0	0
486	8/22/2024 16:16	0	0	0	0
487	8/22/2024 16:17	0	0	0	0
488	8/22/2024 16:18	0	0	0	0
489	8/22/2024 16:19	0	0	0	0
490	8/22/2024 16:20	0	0	0	0
491	8/22/2024 16:21	0	0	0	0
492	8/22/2024 16:22	0	0	0	0
493	8/22/2024 16:23	0	0	0	0
494	8/22/2024 16:24	0	0	0	0

NYSDEC Site No. 314008

495	8/22/2024 16:25	0	0	0	0
496	8/22/2024 16:26	0	0	0	0
497	8/22/2024 16:27	0	0	0	0
498	8/22/2024 16:28	0	0	0	0
499	8/22/2024 16:29	0	0	0	0
500	8/22/2024 16:30	0	0	0	0
501	8/22/2024 16:31	0	0	0	0
502	8/22/2024 16:32	0	0	0	0
503	8/22/2024 16:33	0	0	0	0
504	8/22/2024 16:34	0	0	0	0
505	8/22/2024 16:35	0	0	0	0
506	8/22/2024 16:36	0	0	0	0
507	8/22/2024 16:37	0	0	0	0
508	8/22/2024 16:38	0	0	0	0
509	8/22/2024 16:39	0	0	0	0
510	8/22/2024 16:40	0	0	0	0
511	8/22/2024 16:41	0	0	0	0
512	8/22/2024 16:42	0	0	0	0
513	8/22/2024 16:43	0	0	0	0
514	8/22/2024 16:44	0	0	0	0
515	8/22/2024 16:45	0	0	0	0
516	8/22/2024 16:46	0	0	0	0
517	8/22/2024 16:47	0	0	0	0
518	8/22/2024 16:48	0	0	0	0
519	8/22/2024 16:49	0	0	0	0
520	8/22/2024 16:50	0	0	0	0
521	8/22/2024 16:51	0	0	0	0
522	8/22/2024 16:52	0	0	0	0
523	8/22/2024 16:53	0	0	0	0
524	8/22/2024 16:54	0	0	0	0
525	8/22/2024 16:55	0	0	0	0
526	8/22/2024 16:56	0	0	0	0
527	8/22/2024 16:57	0	0	0	0
528	8/22/2024 16:58	0	0	0	0
529	8/22/2024 16:59	0	0	0	0
530	8/22/2024 17:00	0	0	0	0
531	8/22/2024 17:01	0	0	0	0
532	8/22/2024 17:02	0	0	0	0
533	8/22/2024 17:03	0	0	0	0
534	8/22/2024 17:04	0	0	0	0
535	8/22/2024 17:05	0	0	0	0
536	8/22/2024 17:06	0	0	0	0
537	8/22/2024 17:07	0	0	0	0
538	8/22/2024 17:08	0	0	0	0

NYSDEC Site No. 314008

539	8/22/2024 17:09	0	0	0	0
540	8/22/2024 17:10	0	0	0	0
541	8/22/2024 17:11	0	0	0	0
542	8/22/2024 17:12	0	0	0	0
543	8/22/2024 17:13	0	0	0	0
544	8/22/2024 17:14	0	0	0	0
545	8/22/2024 17:15	0	0	0	0
546	8/22/2024 17:16	0	0	0	0
547	8/22/2024 17:17	0	0	0	0
548	8/22/2024 17:18	0	0	0	0
549	8/22/2024 17:19	0	0	0	0
550	8/22/2024 17:20	0	0	0	0
551	8/22/2024 17:21	0	0	0	0
552	8/22/2024 17:22	0	0	0	0
553	8/22/2024 17:23	0	0	0	0
554	8/22/2024 17:24	0	0	0	0
555	8/22/2024 17:25	0	0	0	0
556	8/22/2024 17:26	0	0	0	0
557	8/22/2024 17:27	0	0	0	0
558	8/22/2024 17:28	0	0	0	0
559	8/22/2024 17:29	0	0	0	0
560	8/22/2024 17:30	0	0	0	0
561	8/22/2024 17:31	0	0	0	0
562	8/22/2024 17:32	0	0	0	0
563	8/22/2024 17:33	0	0	0	0
564	8/22/2024 17:34	0	0	0	0
565	8/22/2024 17:35	0	0	0	0
566	8/22/2024 17:36	0	0	0	0
567	8/22/2024 17:37	0	0	0	0
568	8/22/2024 17:38	0	0	0	0
569	8/22/2024 17:39	0	0	0	0
570	8/22/2024 17:40	0	0	0	0
571	8/22/2024 17:41	0	0	0	0
572	8/22/2024 17:42	0	0	0	0
573	8/22/2024 17:43	0	0	0	0
574	8/22/2024 17:44	0	0	0	0
575	8/22/2024 17:45	0	0	0	0
576	8/22/2024 17:46	0	0	0	0
577	8/22/2024 17:47	0	0	0	0
Peak		0	0.1	0.6	0.2
Min		0	0	0	0
Average		0	0	0	0

TWA/STEL

Index	Date/Time	PID(ppm) (TWA)	PID(ppm) (STEL)
1	8/22/2024 8:11	0	---
2	8/22/2024 8:12	0	---
3	8/22/2024 8:13	0	---
4	8/22/2024 8:14	0	---
5	8/22/2024 8:15	0	---
6	8/22/2024 8:16	0	---
7	8/22/2024 8:17	0	---
8	8/22/2024 8:18	0	---
9	8/22/2024 8:19	0	---
10	8/22/2024 8:20	0	---
11	8/22/2024 8:21	0	---
12	8/22/2024 8:22	0	---
13	8/22/2024 8:23	0	---
14	8/22/2024 8:24	0	---
15	8/22/2024 8:25	0	0
16	8/22/2024 8:26	0	0
17	8/22/2024 8:27	0	0
18	8/22/2024 8:28	0	0
19	8/22/2024 8:29	0	0
20	8/22/2024 8:30	0	0
21	8/22/2024 8:31	0	0
22	8/22/2024 8:32	0	0
23	8/22/2024 8:33	0	0
24	8/22/2024 8:34	0	0
25	8/22/2024 8:35	0	0
26	8/22/2024 8:36	0	0
27	8/22/2024 8:37	0	0
28	8/22/2024 8:38	0	0
29	8/22/2024 8:39	0	0
30	8/22/2024 8:40	0	0
31	8/22/2024 8:41	0	0
32	8/22/2024 8:42	0	0
33	8/22/2024 8:43	0	0
34	8/22/2024 8:44	0	0
35	8/22/2024 8:45	0	0
36	8/22/2024 8:46	0	0
37	8/22/2024 8:47	0	0
38	8/22/2024 8:48	0	0
39	8/22/2024 8:49	0	0
40	8/22/2024 8:50	0	0
41	8/22/2024 8:51	0	0

NYSDEC Site No. 314008

42	8/22/2024 8:52	0	0
43	8/22/2024 8:53	0	0
44	8/22/2024 8:54	0	0
45	8/22/2024 8:55	0	0
46	8/22/2024 8:56	0	0
47	8/22/2024 8:57	0	0
48	8/22/2024 8:58	0	0
49	8/22/2024 8:59	0	0
50	8/22/2024 9:00	0	0
51	8/22/2024 9:01	0	0
52	8/22/2024 9:02	0	0
53	8/22/2024 9:03	0	0
54	8/22/2024 9:04	0	0
55	8/22/2024 9:05	0	0
56	8/22/2024 9:06	0	0
57	8/22/2024 9:07	0	0
58	8/22/2024 9:08	0	0
59	8/22/2024 9:09	0	0
60	8/22/2024 9:10	0	0
61	8/22/2024 9:11	0	0
62	8/22/2024 9:12	0	0
63	8/22/2024 9:13	0	0
64	8/22/2024 9:14	0	0
65	8/22/2024 9:15	0	0
66	8/22/2024 9:16	0	0
67	8/22/2024 9:17	0	0
68	8/22/2024 9:18	0	0
69	8/22/2024 9:19	0	0
70	8/22/2024 9:20	0	0
71	8/22/2024 9:21	0	0
72	8/22/2024 9:22	0	0
73	8/22/2024 9:23	0	0
74	8/22/2024 9:24	0	0
75	8/22/2024 9:25	0	0
76	8/22/2024 9:26	0	0
77	8/22/2024 9:27	0	0
78	8/22/2024 9:28	0	0
79	8/22/2024 9:29	0	0
80	8/22/2024 9:30	0	0
81	8/22/2024 9:31	0	0
82	8/22/2024 9:32	0	0
83	8/22/2024 9:33	0	0
84	8/22/2024 9:34	0	0
85	8/22/2024 9:35	0	0

NYSDEC Site No. 314008

86	8/22/2024 9:36	0	0
87	8/22/2024 9:37	0	0
88	8/22/2024 9:38	0	0
89	8/22/2024 9:39	0	0
90	8/22/2024 9:40	0	0
91	8/22/2024 9:41	0	0
92	8/22/2024 9:42	0	0
93	8/22/2024 9:43	0	0
94	8/22/2024 9:44	0	0
95	8/22/2024 9:45	0	0
96	8/22/2024 9:46	0	0
97	8/22/2024 9:47	0	0
98	8/22/2024 9:48	0	0
99	8/22/2024 9:49	0	0
100	8/22/2024 9:50	0	0
101	8/22/2024 9:51	0	0
102	8/22/2024 9:52	0	0
103	8/22/2024 9:53	0	0
104	8/22/2024 9:54	0	0
105	8/22/2024 9:55	0	0
106	8/22/2024 9:56	0	0
107	8/22/2024 9:57	0	0
108	8/22/2024 9:58	0	0
109	8/22/2024 9:59	0	0
110	8/22/2024 10:00	0	0
111	8/22/2024 10:01	0	0
112	8/22/2024 10:02	0	0
113	8/22/2024 10:03	0	0
114	8/22/2024 10:04	0	0
115	8/22/2024 10:05	0	0
116	8/22/2024 10:06	0	0
117	8/22/2024 10:07	0	0
118	8/22/2024 10:08	0	0
119	8/22/2024 10:09	0	0
120	8/22/2024 10:10	0	0
121	8/22/2024 10:11	0	0
122	8/22/2024 10:12	0	0
123	8/22/2024 10:13	0	0
124	8/22/2024 10:14	0	0
125	8/22/2024 10:15	0	0
126	8/22/2024 10:16	0	0
127	8/22/2024 10:17	0	0
128	8/22/2024 10:18	0	0
129	8/22/2024 10:19	0	0

NYSDEC Site No. 314008

130	8/22/2024 10:20	0	0
131	8/22/2024 10:21	0	0
132	8/22/2024 10:22	0	0
133	8/22/2024 10:23	0	0
134	8/22/2024 10:24	0	0
135	8/22/2024 10:25	0	0
136	8/22/2024 10:26	0	0
137	8/22/2024 10:27	0	0
138	8/22/2024 10:28	0	0
139	8/22/2024 10:29	0	0
140	8/22/2024 10:30	0	0
141	8/22/2024 10:31	0	0
142	8/22/2024 10:32	0	0
143	8/22/2024 10:33	0	0
144	8/22/2024 10:34	0	0
145	8/22/2024 10:35	0	0
146	8/22/2024 10:36	0	0
147	8/22/2024 10:37	0	0
148	8/22/2024 10:38	0	0
149	8/22/2024 10:39	0	0
150	8/22/2024 10:40	0	0
151	8/22/2024 10:41	0	0
152	8/22/2024 10:42	0	0
153	8/22/2024 10:43	0	0
154	8/22/2024 10:44	0	0
155	8/22/2024 10:45	0	0
156	8/22/2024 10:46	0	0
157	8/22/2024 10:47	0	0
158	8/22/2024 10:48	0	0
159	8/22/2024 10:49	0	0
160	8/22/2024 10:50	0	0
161	8/22/2024 10:51	0	0
162	8/22/2024 10:52	0	0
163	8/22/2024 10:53	0	0
164	8/22/2024 10:54	0	0
165	8/22/2024 10:55	0	0
166	8/22/2024 10:56	0	0
167	8/22/2024 10:57	0	0
168	8/22/2024 10:58	0	0
169	8/22/2024 10:59	0	0
170	8/22/2024 11:00	0	0
171	8/22/2024 11:01	0	0
172	8/22/2024 11:02	0	0
173	8/22/2024 11:03	0	0

NYSDEC Site No. 314008

174	8/22/2024 11:04	0	0
175	8/22/2024 11:05	0	0
176	8/22/2024 11:06	0	0
177	8/22/2024 11:07	0	0
178	8/22/2024 11:08	0	0
179	8/22/2024 11:09	0	0
180	8/22/2024 11:10	0	0
181	8/22/2024 11:11	0	0
182	8/22/2024 11:12	0	0
183	8/22/2024 11:13	0	0
184	8/22/2024 11:14	0	0
185	8/22/2024 11:15	0	0
186	8/22/2024 11:16	0	0
187	8/22/2024 11:17	0	0
188	8/22/2024 11:18	0	0
189	8/22/2024 11:19	0	0
190	8/22/2024 11:20	0	0
191	8/22/2024 11:21	0	0
192	8/22/2024 11:22	0	0
193	8/22/2024 11:23	0	0
194	8/22/2024 11:24	0	0
195	8/22/2024 11:25	0	0
196	8/22/2024 11:26	0	0
197	8/22/2024 11:27	0	0
198	8/22/2024 11:28	0	0
199	8/22/2024 11:29	0	0
200	8/22/2024 11:30	0	0
201	8/22/2024 11:31	0	0
202	8/22/2024 11:32	0	0
203	8/22/2024 11:33	0	0
204	8/22/2024 11:34	0	0
205	8/22/2024 11:35	0	0
206	8/22/2024 11:36	0	0
207	8/22/2024 11:37	0	0
208	8/22/2024 11:38	0	0
209	8/22/2024 11:39	0	0
210	8/22/2024 11:40	0	0
211	8/22/2024 11:41	0	0
212	8/22/2024 11:42	0	0
213	8/22/2024 11:43	0	0
214	8/22/2024 11:44	0	0
215	8/22/2024 11:45	0	0
216	8/22/2024 11:46	0	0
217	8/22/2024 11:47	0	0

NYSDEC Site No. 314008

218	8/22/2024 11:48	0	0
219	8/22/2024 11:49	0	0
220	8/22/2024 11:50	0	0
221	8/22/2024 11:51	0	0
222	8/22/2024 11:52	0	0
223	8/22/2024 11:53	0	0
224	8/22/2024 11:54	0	0
225	8/22/2024 11:55	0	0
226	8/22/2024 11:56	0	0
227	8/22/2024 11:57	0	0
228	8/22/2024 11:58	0	0
229	8/22/2024 11:59	0	0
230	8/22/2024 12:00	0	0
231	8/22/2024 12:01	0	0
232	8/22/2024 12:02	0	0
233	8/22/2024 12:03	0	0
234	8/22/2024 12:04	0	0
235	8/22/2024 12:05	0	0
236	8/22/2024 12:06	0	0
237	8/22/2024 12:07	0	0
238	8/22/2024 12:08	0	0
239	8/22/2024 12:09	0	0
240	8/22/2024 12:10	0	0
241	8/22/2024 12:11	0	0
242	8/22/2024 12:12	0	0
243	8/22/2024 12:13	0	0
244	8/22/2024 12:14	0	0
245	8/22/2024 12:15	0	0
246	8/22/2024 12:16	0	0
247	8/22/2024 12:17	0	0
248	8/22/2024 12:18	0	0
249	8/22/2024 12:19	0	0
250	8/22/2024 12:20	0	0
251	8/22/2024 12:21	0	0
252	8/22/2024 12:22	0	0
253	8/22/2024 12:23	0	0
254	8/22/2024 12:24	0	0
255	8/22/2024 12:25	0	0
256	8/22/2024 12:26	0	0
257	8/22/2024 12:27	0	0
258	8/22/2024 12:28	0	0
259	8/22/2024 12:29	0	0
260	8/22/2024 12:30	0	0
261	8/22/2024 12:31	0	0

NYSDEC Site No. 314008

262	8/22/2024 12:32	0	0
263	8/22/2024 12:33	0	0
264	8/22/2024 12:34	0	0
265	8/22/2024 12:35	0	0
266	8/22/2024 12:36	0	0
267	8/22/2024 12:37	0	0
268	8/22/2024 12:38	0	0
269	8/22/2024 12:39	0	0
270	8/22/2024 12:40	0	0
271	8/22/2024 12:41	0	0
272	8/22/2024 12:42	0	0
273	8/22/2024 12:43	0	0
274	8/22/2024 12:44	0	0
275	8/22/2024 12:45	0	0
276	8/22/2024 12:46	0	0
277	8/22/2024 12:47	0	0
278	8/22/2024 12:48	0	0
279	8/22/2024 12:49	0	0
280	8/22/2024 12:50	0	0
281	8/22/2024 12:51	0	0
282	8/22/2024 12:52	0	0
283	8/22/2024 12:53	0	0
284	8/22/2024 12:54	0	0
285	8/22/2024 12:55	0	0
286	8/22/2024 12:56	0	0
287	8/22/2024 12:57	0	0
288	8/22/2024 12:58	0	0
289	8/22/2024 12:59	0	0
290	8/22/2024 13:00	0	0
291	8/22/2024 13:01	0	0
292	8/22/2024 13:02	0	0
293	8/22/2024 13:03	0	0
294	8/22/2024 13:04	0	0
295	8/22/2024 13:05	0	0
296	8/22/2024 13:06	0	0
297	8/22/2024 13:07	0	0
298	8/22/2024 13:08	0	0
299	8/22/2024 13:09	0	0
300	8/22/2024 13:10	0	0
301	8/22/2024 13:11	0	0
302	8/22/2024 13:12	0	0
303	8/22/2024 13:13	0	0
304	8/22/2024 13:14	0	0
305	8/22/2024 13:15	0	0

NYSDEC Site No. 314008

306	8/22/2024 13:16	0	0
307	8/22/2024 13:17	0	0
308	8/22/2024 13:18	0	0
309	8/22/2024 13:19	0	0
310	8/22/2024 13:20	0	0
311	8/22/2024 13:21	0	0
312	8/22/2024 13:22	0	0
313	8/22/2024 13:23	0	0
314	8/22/2024 13:24	0	0
315	8/22/2024 13:25	0	0
316	8/22/2024 13:26	0	0
317	8/22/2024 13:27	0	0
318	8/22/2024 13:28	0	0
319	8/22/2024 13:29	0	0
320	8/22/2024 13:30	0	0
321	8/22/2024 13:31	0	0
322	8/22/2024 13:32	0	0
323	8/22/2024 13:33	0	0
324	8/22/2024 13:34	0	0
325	8/22/2024 13:35	0	0
326	8/22/2024 13:36	0	0
327	8/22/2024 13:37	0	0
328	8/22/2024 13:38	0	0
329	8/22/2024 13:39	0	0
330	8/22/2024 13:40	0	0
331	8/22/2024 13:41	0	0
332	8/22/2024 13:42	0	0
333	8/22/2024 13:43	0	0
334	8/22/2024 13:44	0	0
335	8/22/2024 13:45	0	0
336	8/22/2024 13:46	0	0
337	8/22/2024 13:47	0	0
338	8/22/2024 13:48	0	0
339	8/22/2024 13:49	0	0
340	8/22/2024 13:50	0	0
341	8/22/2024 13:51	0	0
342	8/22/2024 13:52	0	0
343	8/22/2024 13:53	0	0
344	8/22/2024 13:54	0	0
345	8/22/2024 13:55	0	0
346	8/22/2024 13:56	0	0
347	8/22/2024 13:57	0	0
348	8/22/2024 13:58	0	0
349	8/22/2024 13:59	0	0

NYSDEC Site No. 314008

350	8/22/2024 14:00	0	0
351	8/22/2024 14:01	0	0
352	8/22/2024 14:02	0	0
353	8/22/2024 14:03	0	0
354	8/22/2024 14:04	0	0
355	8/22/2024 14:05	0	0
356	8/22/2024 14:06	0	0
357	8/22/2024 14:07	0	0
358	8/22/2024 14:08	0	0
359	8/22/2024 14:09	0	0
360	8/22/2024 14:10	0	0
361	8/22/2024 14:11	0	0
362	8/22/2024 14:12	0	0
363	8/22/2024 14:13	0	0
364	8/22/2024 14:14	0	0
365	8/22/2024 14:15	0	0
366	8/22/2024 14:16	0	0
367	8/22/2024 14:17	0	0
368	8/22/2024 14:18	0	0
369	8/22/2024 14:19	0	0
370	8/22/2024 14:20	0	0
371	8/22/2024 14:21	0	0
372	8/22/2024 14:22	0	0
373	8/22/2024 14:23	0	0
374	8/22/2024 14:24	0	0
375	8/22/2024 14:25	0	0
376	8/22/2024 14:26	0	0
377	8/22/2024 14:27	0	0
378	8/22/2024 14:28	0	0
379	8/22/2024 14:29	0	0
380	8/22/2024 14:30	0	0
381	8/22/2024 14:31	0	0
382	8/22/2024 14:32	0	0
383	8/22/2024 14:33	0	0
384	8/22/2024 14:34	0	0
385	8/22/2024 14:35	0	0
386	8/22/2024 14:36	0	0
387	8/22/2024 14:37	0	0
388	8/22/2024 14:38	0	0
389	8/22/2024 14:39	0	0
390	8/22/2024 14:40	0	0
391	8/22/2024 14:41	0	0
392	8/22/2024 14:42	0	0
393	8/22/2024 14:43	0	0

NYSDEC Site No. 314008

394	8/22/2024 14:44	0	0
395	8/22/2024 14:45	0	0
396	8/22/2024 14:46	0	0
397	8/22/2024 14:47	0	0
398	8/22/2024 14:48	0	0
399	8/22/2024 14:49	0	0
400	8/22/2024 14:50	0	0
401	8/22/2024 14:51	0	0
402	8/22/2024 14:52	0	0
403	8/22/2024 14:53	0	0
404	8/22/2024 14:54	0	0
405	8/22/2024 14:55	0	0
406	8/22/2024 14:56	0	0
407	8/22/2024 14:57	0	0
408	8/22/2024 14:58	0	0
409	8/22/2024 14:59	0	0
410	8/22/2024 15:00	0	0
411	8/22/2024 15:01	0	0
412	8/22/2024 15:02	0	0
413	8/22/2024 15:03	0	0
414	8/22/2024 15:04	0	0
415	8/22/2024 15:05	0	0
416	8/22/2024 15:06	0	0
417	8/22/2024 15:07	0	0
418	8/22/2024 15:08	0	0
419	8/22/2024 15:09	0	0
420	8/22/2024 15:10	0	0
421	8/22/2024 15:11	0	0
422	8/22/2024 15:12	0	0
423	8/22/2024 15:13	0	0
424	8/22/2024 15:14	0	0
425	8/22/2024 15:15	0	0
426	8/22/2024 15:16	0	0
427	8/22/2024 15:17	0	0
428	8/22/2024 15:18	0	0
429	8/22/2024 15:19	0	0
430	8/22/2024 15:20	0	0
431	8/22/2024 15:21	0	0
432	8/22/2024 15:22	0	0
433	8/22/2024 15:23	0	0
434	8/22/2024 15:24	0	0
435	8/22/2024 15:25	0	0
436	8/22/2024 15:26	0	0
437	8/22/2024 15:27	0	0

NYSDEC Site No. 314008

438	8/22/2024 15:28	0	0
439	8/22/2024 15:29	0	0
440	8/22/2024 15:30	0	0
441	8/22/2024 15:31	0	0
442	8/22/2024 15:32	0	0
443	8/22/2024 15:33	0	0
444	8/22/2024 15:34	0	0
445	8/22/2024 15:35	0	0
446	8/22/2024 15:36	0	0
447	8/22/2024 15:37	0	0
448	8/22/2024 15:38	0	0
449	8/22/2024 15:39	0	0
450	8/22/2024 15:40	0	0
451	8/22/2024 15:41	0	0
452	8/22/2024 15:42	0	0
453	8/22/2024 15:43	0	0
454	8/22/2024 15:44	0	0
455	8/22/2024 15:45	0	0
456	8/22/2024 15:46	0	0
457	8/22/2024 15:47	0	0
458	8/22/2024 15:48	0	0
459	8/22/2024 15:49	0	0
460	8/22/2024 15:50	0	0
461	8/22/2024 15:51	0	0
462	8/22/2024 15:52	0	0
463	8/22/2024 15:53	0	0
464	8/22/2024 15:54	0	0
465	8/22/2024 15:55	0	0
466	8/22/2024 15:56	0	0
467	8/22/2024 15:57	0	0
468	8/22/2024 15:58	0	0
469	8/22/2024 15:59	0	0
470	8/22/2024 16:00	0	0
471	8/22/2024 16:01	0	0
472	8/22/2024 16:02	0	0
473	8/22/2024 16:03	0	0
474	8/22/2024 16:04	0	0
475	8/22/2024 16:05	0	0
476	8/22/2024 16:06	0	0
477	8/22/2024 16:07	0	0
478	8/22/2024 16:08	0	0
479	8/22/2024 16:09	0	0
480	8/22/2024 16:10	0	0
481	8/22/2024 16:11	0	0

NYSDEC Site No. 314008

482	8/22/2024 16:12	0	0
483	8/22/2024 16:13	0	0
484	8/22/2024 16:14	0	0
485	8/22/2024 16:15	0	0
486	8/22/2024 16:16	0	0
487	8/22/2024 16:17	0	0
488	8/22/2024 16:18	0	0
489	8/22/2024 16:19	0	0
490	8/22/2024 16:20	0	0
491	8/22/2024 16:21	0	0
492	8/22/2024 16:22	0	0
493	8/22/2024 16:23	0	0
494	8/22/2024 16:24	0	0
495	8/22/2024 16:25	0	0
496	8/22/2024 16:26	0	0
497	8/22/2024 16:27	0	0
498	8/22/2024 16:28	0	0
499	8/22/2024 16:29	0	0
500	8/22/2024 16:30	0	0
501	8/22/2024 16:31	0	0
502	8/22/2024 16:32	0	0
503	8/22/2024 16:33	0	0
504	8/22/2024 16:34	0	0
505	8/22/2024 16:35	0	0
506	8/22/2024 16:36	0	0
507	8/22/2024 16:37	0	0
508	8/22/2024 16:38	0	0
509	8/22/2024 16:39	0	0
510	8/22/2024 16:40	0	0
511	8/22/2024 16:41	0	0
512	8/22/2024 16:42	0	0
513	8/22/2024 16:43	0	0
514	8/22/2024 16:44	0	0
515	8/22/2024 16:45	0	0
516	8/22/2024 16:46	0	0
517	8/22/2024 16:47	0	0
518	8/22/2024 16:48	0	0
519	8/22/2024 16:49	0	0
520	8/22/2024 16:50	0	0
521	8/22/2024 16:51	0	0
522	8/22/2024 16:52	0	0
523	8/22/2024 16:53	0	0
524	8/22/2024 16:54	0	0
525	8/22/2024 16:55	0	0

NYSDEC Site No. 314008

526	8/22/2024 16:56	0	0
527	8/22/2024 16:57	0	0
528	8/22/2024 16:58	0	0
529	8/22/2024 16:59	0	0
530	8/22/2024 17:00	0	0
531	8/22/2024 17:01	0	0
532	8/22/2024 17:02	0	0
533	8/22/2024 17:03	0	0
534	8/22/2024 17:04	0	0
535	8/22/2024 17:05	0	0
536	8/22/2024 17:06	0	0
537	8/22/2024 17:07	0	0
538	8/22/2024 17:08	0	0
539	8/22/2024 17:09	0	0
540	8/22/2024 17:10	0	0
541	8/22/2024 17:11	0	0
542	8/22/2024 17:12	0	0
543	8/22/2024 17:13	0	0
544	8/22/2024 17:14	0	0
545	8/22/2024 17:15	0	0
546	8/22/2024 17:16	0	0
547	8/22/2024 17:17	0	0
548	8/22/2024 17:18	0	0
549	8/22/2024 17:19	0	0
550	8/22/2024 17:20	0	0
551	8/22/2024 17:21	0	0
552	8/22/2024 17:22	0	0
553	8/22/2024 17:23	0	0
554	8/22/2024 17:24	0	0
555	8/22/2024 17:25	0	0
556	8/22/2024 17:26	0	0
557	8/22/2024 17:27	0	0
558	8/22/2024 17:28	0	0
559	8/22/2024 17:29	0	0
560	8/22/2024 17:30	0	0
561	8/22/2024 17:31	0	0
562	8/22/2024 17:32	0	0
563	8/22/2024 17:33	0	0
564	8/22/2024 17:34	0	0
565	8/22/2024 17:35	0	0
566	8/22/2024 17:36	0	0
567	8/22/2024 17:37	0	0
568	8/22/2024 17:38	0	0
569	8/22/2024 17:39	0	0

NYSDEC Site No. 314008

570	8/22/2024 17:40	0	0
571	8/22/2024 17:41	0	0
572	8/22/2024 17:42	0	0
573	8/22/2024 17:43	0	0
574	8/22/2024 17:44	0	0
575	8/22/2024 17:45	0	0
576	8/22/2024 17:46	0	0
577	8/22/2024 17:47	0	0

=====

24/08/23 08:09

Summary

Unit Name MiniRAE 3000 +(PGM-7320)

Unit SN 592-927758

Unit Firmw V2.22A

Running Mode Hygiene Mode

Datalog Mode Auto

Diagnostic No

Stop Reason Power Down

Site ID RAE00000

User ID USER0000

Begin 8/23/2024 8:09

End 8/23/2024 14:30

Sample Period 60

Number of 380

Sensor PID(ppm)

Sensor SN S023030115B6

Measure Type Min; Avg; Max; Real

Span 100

Span 2 1000

Low Alarm 50

High Alarm 100

Over Alarm 15000

STEL Alarm 25

TWA Alarm 10

Measurement Isobutylene

Calibration 8/13/2024 10:59

Peak 0.3

Min 0

Average 0

Datalog

Index	Date/Time	PID(ppm) (Min)	PID(ppm) (Avg)	PID(ppm) (Max)	PID(ppm) (Real)
1	8/23/2024 8:10	0	0	0	0
2	8/23/2024 8:11	0	0	0	0
3	8/23/2024 8:12	0	0	0	0
4	8/23/2024 8:13	0	0	0	0
5	8/23/2024 8:14	0	0	0	0
6	8/23/2024 8:15	0	0	0	0
7	8/23/2024 8:16	0	0	0	0
8	8/23/2024 8:17	0	0	0	0
9	8/23/2024 8:18	0	0	0	0
10	8/23/2024 8:19	0	0	0	0
11	8/23/2024 8:20	0	0	0	0
12	8/23/2024 8:21	0	0	0	0
13	8/23/2024 8:22	0	0	0	0
14	8/23/2024 8:23	0	0	0	0
15	8/23/2024 8:24	0	0	0	0
16	8/23/2024 8:25	0	0	0	0
17	8/23/2024 8:26	0	0	0	0
18	8/23/2024 8:27	0	0	0	0
19	8/23/2024 8:28	0	0	0	0
20	8/23/2024 8:29	0	0	0	0
21	8/23/2024 8:30	0	0	0	0
22	8/23/2024 8:31	0	0	0	0
23	8/23/2024 8:32	0	0	0	0
24	8/23/2024 8:33	0	0	0	0
25	8/23/2024 8:34	0	0	0	0
26	8/23/2024 8:35	0	0	0	0
27	8/23/2024 8:36	0	0	0	0
28	8/23/2024 8:37	0	0	0	0
29	8/23/2024 8:38	0	0	0	0
30	8/23/2024 8:39	0	0	0	0
31	8/23/2024 8:40	0	0	0	0
32	8/23/2024 8:41	0	0	0	0
33	8/23/2024 8:42	0	0	0	0
34	8/23/2024 8:43	0	0	0	0
35	8/23/2024 8:44	0	0	0	0
36	8/23/2024 8:45	0	0	0	0
37	8/23/2024 8:46	0	0	0	0
38	8/23/2024 8:47	0	0	0.1	0

NYSDEC Site No. 314008

39	8/23/2024 8:48	0	0	0	0
40	8/23/2024 8:49	0	0	0	0
41	8/23/2024 8:50	0	0	0	0
42	8/23/2024 8:51	0	0	0	0
43	8/23/2024 8:52	0	0	0	0
44	8/23/2024 8:53	0	0	0	0
45	8/23/2024 8:54	0	0	0	0
46	8/23/2024 8:55	0	0	0.1	0
47	8/23/2024 8:56	0	0	0.1	0.1
48	8/23/2024 8:57	0	0	0.1	0
49	8/23/2024 8:58	0	0	0	0
50	8/23/2024 8:59	0	0	0	0
51	8/23/2024 9:00	0	0	0.1	0
52	8/23/2024 9:01	0	0	0.1	0
53	8/23/2024 9:02	0	0	0.1	0
54	8/23/2024 9:03	0	0	0.1	0
55	8/23/2024 9:04	0	0	0.1	0
56	8/23/2024 9:05	0	0	0.1	0
57	8/23/2024 9:06	0	0	0	0
58	8/23/2024 9:07	0	0	0.1	0.1
59	8/23/2024 9:08	0	0	0.1	0
60	8/23/2024 9:09	0	0	0.1	0.1
61	8/23/2024 9:10	0	0.1	0.1	0.1
62	8/23/2024 9:11	0	0.1	0.1	0.1
63	8/23/2024 9:12	0	0.1	0.1	0
64	8/23/2024 9:13	0	0	0.1	0
65	8/23/2024 9:14	0	0	0.1	0
66	8/23/2024 9:15	0	0	0.1	0
67	8/23/2024 9:16	0	0	0.1	0
68	8/23/2024 9:17	0	0	0	0
69	8/23/2024 9:18	0	0	0.1	0
70	8/23/2024 9:19	0	0.1	0.1	0.1
71	8/23/2024 9:20	0	0.1	0.2	0
72	8/23/2024 9:21	0	0	0.1	0
73	8/23/2024 9:22	0	0	0.1	0.1
74	8/23/2024 9:23	0	0.1	0.1	0.1
75	8/23/2024 9:24	0	0	0.1	0
76	8/23/2024 9:25	0	0	0.1	0
77	8/23/2024 9:26	0	0	0.1	0.1
78	8/23/2024 9:27	0	0	0.1	0
79	8/23/2024 9:28	0	0	0.1	0
80	8/23/2024 9:29	0	0	0.1	0
81	8/23/2024 9:30	0	0.1	0.1	0.1
82	8/23/2024 9:31	0	0	0.1	0

NYSDEC Site No. 314008

83	8/23/2024 9:32	0	0	0.1	0.1
84	8/23/2024 9:33	0	0	0.1	0
85	8/23/2024 9:34	0	0	0.1	0.1
86	8/23/2024 9:35	0	0.1	0.1	0.1
87	8/23/2024 9:36	0	0.1	0.1	0.1
88	8/23/2024 9:37	0	0.1	0.1	0.1
89	8/23/2024 9:38	0	0.1	0.1	0.1
90	8/23/2024 9:39	0	0.1	0.1	0
91	8/23/2024 9:40	0	0	0.1	0
92	8/23/2024 9:41	0	0.3	1.5	0.1
93	8/23/2024 9:42	0	0.1	0.2	0.1
94	8/23/2024 9:43	0	0.1	0.2	0.1
95	8/23/2024 9:44	0	0.1	0.1	0.1
96	8/23/2024 9:45	0	0.1	0.3	0.3
97	8/23/2024 9:46	0.1	0.3	0.4	0.2
98	8/23/2024 9:47	0.2	0.4	0.7	0.2
99	8/23/2024 9:48	0.1	0.1	0.2	0.1
100	8/23/2024 9:49	0.1	0.1	0.1	0.1
101	8/23/2024 9:50	0.1	0.1	0.2	0.1
102	8/23/2024 9:51	0.1	0.1	0.1	0.1
103	8/23/2024 9:52	0.1	0.1	0.2	0.2
104	8/23/2024 9:53	0.1	0.2	0.3	0.1
105	8/23/2024 9:54	0.1	0.1	0.3	0.2
106	8/23/2024 9:55	0.1	0.1	0.2	0.1
107	8/23/2024 9:56	0	0.1	0.1	0
108	8/23/2024 9:57	0	0.1	0.1	0.1
109	8/23/2024 9:58	0	0.1	0.1	0.1
110	8/23/2024 9:59	0	0.1	0.1	0
111	8/23/2024 10:00	0	0	0.1	0
112	8/23/2024 10:01	0	0	0.1	0
113	8/23/2024 10:02	0	0	0.1	0
114	8/23/2024 10:03	0	0	0.1	0
115	8/23/2024 10:04	0	0	0	0
116	8/23/2024 10:05	0	0	0	0
117	8/23/2024 10:06	0	0	0	0
118	8/23/2024 10:07	0	0	0	0
119	8/23/2024 10:08	0	0	0	0
120	8/23/2024 10:09	0	0	0	0
121	8/23/2024 10:10	0	0	0	0
122	8/23/2024 10:11	0	0	0	0
123	8/23/2024 10:12	0	0	0	0
124	8/23/2024 10:13	0	0	0	0
125	8/23/2024 10:14	0	0	0	0
126	8/23/2024 10:15	0	0	0	0

NYSDEC Site No. 314008

127	8/23/2024 10:16	0	0	0	0
128	8/23/2024 10:17	0	0	0	0
129	8/23/2024 10:18	0	0	0	0
130	8/23/2024 10:19	0	0	0	0
131	8/23/2024 10:20	0	0	0	0
132	8/23/2024 10:21	0	0	0	0
133	8/23/2024 10:22	0	0	0	0
134	8/23/2024 10:23	0	0	0	0
135	8/23/2024 10:24	0	0	0	0
136	8/23/2024 10:25	0	0	0	0
137	8/23/2024 10:26	0	0	0	0
138	8/23/2024 10:27	0	0	0	0
139	8/23/2024 10:28	0	0	0	0
140	8/23/2024 10:29	0	0	0	0
141	8/23/2024 10:30	0	0	0	0
142	8/23/2024 10:31	0	0	0	0
143	8/23/2024 10:32	0	0	0	0
144	8/23/2024 10:33	0	0	0	0
145	8/23/2024 10:34	0	0	0	0
146	8/23/2024 10:35	0	0	0	0
147	8/23/2024 10:36	0	0	0	0
148	8/23/2024 10:37	0	0	0	0
149	8/23/2024 10:38	0	0	0	0
150	8/23/2024 10:39	0	0	0	0
151	8/23/2024 10:40	0	0	0	0
152	8/23/2024 10:41	0	0	0	0
153	8/23/2024 10:42	0	0	0	0
154	8/23/2024 10:43	0	0	0	0
155	8/23/2024 10:44	0	0	0	0
156	8/23/2024 10:45	0	0	0	0
157	8/23/2024 10:46	0	0	0	0
158	8/23/2024 10:47	0	0	0	0
159	8/23/2024 10:48	0	0	0	0
160	8/23/2024 10:49	0	0	0	0
161	8/23/2024 10:50	0	0	0	0
162	8/23/2024 10:51	0	0	0	0
163	8/23/2024 10:52	0	0	0	0
164	8/23/2024 10:53	0	0.1	0.1	0.1
165	8/23/2024 10:54	0	0	0.1	0
166	8/23/2024 10:55	0	0	0	0
167	8/23/2024 10:56	0	0	0	0
168	8/23/2024 10:57	0	0	0	0
169	8/23/2024 10:58	0	0	0	0
170	8/23/2024 10:59	0	0	0	0

NYSDEC Site No. 314008

171	8/23/2024 11:00	0	0	0	0
172	8/23/2024 11:01	0	0	0	0
173	8/23/2024 11:02	0	0	0	0
174	8/23/2024 11:03	0	0	0	0
175	8/23/2024 11:04	0	0	0	0
176	8/23/2024 11:05	0	0	0	0
177	8/23/2024 11:06	0	0	0	0
178	8/23/2024 11:07	0	0	0.1	0
179	8/23/2024 11:08	0	0	0	0
180	8/23/2024 11:09	0	0	0	0
181	8/23/2024 11:10	0	0	0	0
182	8/23/2024 11:11	0	0	0	0
183	8/23/2024 11:12	0	0	0	0
184	8/23/2024 11:13	0	0	0	0
185	8/23/2024 11:14	0	0	0	0
186	8/23/2024 11:15	0	0	0	0
187	8/23/2024 11:16	0	0	0	0
188	8/23/2024 11:17	0	0	0	0
189	8/23/2024 11:18	0	0	0	0
190	8/23/2024 11:19	0	0	0	0
191	8/23/2024 11:20	0	0	0	0
192	8/23/2024 11:21	0	0	0	0
193	8/23/2024 11:22	0	0	0	0
194	8/23/2024 11:23	0	0	0	0
195	8/23/2024 11:24	0	0	0	0
196	8/23/2024 11:25	0	0	0	0
197	8/23/2024 11:26	0	0	0	0
198	8/23/2024 11:27	0	0	0	0
199	8/23/2024 11:28	0	0	0	0
200	8/23/2024 11:29	0	0	0	0
201	8/23/2024 11:30	0	0	0	0
202	8/23/2024 11:31	0	0	0	0
203	8/23/2024 11:32	0	0	0	0
204	8/23/2024 11:33	0	0	0	0
205	8/23/2024 11:34	0	0	0	0
206	8/23/2024 11:35	0	0	0	0
207	8/23/2024 11:36	0	0	0	0
208	8/23/2024 11:37	0	0	0	0
209	8/23/2024 11:38	0	0	0	0
210	8/23/2024 11:39	0	0	0	0
211	8/23/2024 11:40	0	0	0	0
212	8/23/2024 11:41	0	0	0	0
213	8/23/2024 11:42	0	0	0	0
214	8/23/2024 11:43	0	0	0	0

NYSDEC Site No. 314008

215	8/23/2024 11:44	0	0	0	0
216	8/23/2024 11:45	0	0	0	0
217	8/23/2024 11:46	0	0	0	0
218	8/23/2024 11:47	0	0	0	0
219	8/23/2024 11:48	0	0	0	0
220	8/23/2024 11:49	0	0	0	0
221	8/23/2024 11:50	0	0	0	0
222	8/23/2024 11:51	0	0	0	0
223	8/23/2024 11:52	0	0	0	0
224	8/23/2024 11:53	0	0	0	0
225	8/23/2024 11:54	0	0	0	0
226	8/23/2024 11:55	0	0	0	0
227	8/23/2024 11:56	0	0	0	0
228	8/23/2024 11:57	0	0	0	0
229	8/23/2024 11:58	0	0	0	0
230	8/23/2024 11:59	0	0	0	0
231	8/23/2024 12:00	0	0	0	0
232	8/23/2024 12:01	0	0	0	0
233	8/23/2024 12:02	0	0	0	0
234	8/23/2024 12:03	0	0	0	0
235	8/23/2024 12:04	0	0	0	0
236	8/23/2024 12:05	0	0	0	0
237	8/23/2024 12:06	0	0	0	0
238	8/23/2024 12:07	0	0	0	0
239	8/23/2024 12:08	0	0	0	0
240	8/23/2024 12:09	0	0	0	0
241	8/23/2024 12:10	0	0	0	0
242	8/23/2024 12:11	0	0	0	0
243	8/23/2024 12:12	0	0	0	0
244	8/23/2024 12:13	0	0	0	0
245	8/23/2024 12:14	0	0	0	0
246	8/23/2024 12:15	0	0	0	0
247	8/23/2024 12:16	0	0	0	0
248	8/23/2024 12:17	0	0	0	0
249	8/23/2024 12:18	0	0	0	0
250	8/23/2024 12:19	0	0	0	0
251	8/23/2024 12:20	0	0	0	0
252	8/23/2024 12:21	0	0	0	0
253	8/23/2024 12:22	0	0	0	0
254	8/23/2024 12:23	0	0	0	0
255	8/23/2024 12:24	0	0	0	0
256	8/23/2024 12:25	0	0	0	0
257	8/23/2024 12:26	0	0	0	0
258	8/23/2024 12:27	0	0	0	0

NYSDEC Site No. 314008

259	8/23/2024 12:28	0	0	0	0
260	8/23/2024 12:29	0	0	0	0
261	8/23/2024 12:30	0	0	0	0
262	8/23/2024 12:31	0	0	0	0
263	8/23/2024 12:32	0	0	0	0
264	8/23/2024 12:33	0	0	0	0
265	8/23/2024 12:34	0	0	0	0
266	8/23/2024 12:35	0	0	0	0
267	8/23/2024 12:36	0	0	0	0
268	8/23/2024 12:37	0	0	0	0
269	8/23/2024 12:38	0	0	0	0
270	8/23/2024 12:39	0	0	0	0
271	8/23/2024 12:40	0	0	0	0
272	8/23/2024 12:41	0	0	0.1	0
273	8/23/2024 12:42	0	0	0	0
274	8/23/2024 12:43	0	0	0	0
275	8/23/2024 12:44	0	0	0	0
276	8/23/2024 12:45	0	0	0	0
277	8/23/2024 12:46	0	0	0	0
278	8/23/2024 12:47	0	0.1	0.4	0
279	8/23/2024 12:48	0	0	0	0
280	8/23/2024 12:49	0	0	0	0
281	8/23/2024 12:50	0	0	0	0
282	8/23/2024 12:51	0	0	0	0
283	8/23/2024 12:52	0	0	0	0
284	8/23/2024 12:53	0	0.1	0.3	0
285	8/23/2024 12:54	0	0	0.1	0.1
286	8/23/2024 12:55	0	0.4	1.4	0
287	8/23/2024 12:56	0	0	0	0
288	8/23/2024 12:57	0	0	0	0
289	8/23/2024 12:58	0	0	0	0
290	8/23/2024 12:59	0	0	0	0
291	8/23/2024 13:00	0	0	0	0
292	8/23/2024 13:01	0	0	0	0
293	8/23/2024 13:02	0	0	0	0
294	8/23/2024 13:03	0	0	0	0
295	8/23/2024 13:04	0	0	0	0
296	8/23/2024 13:05	0	0	0	0
297	8/23/2024 13:06	0	0	0	0
298	8/23/2024 13:07	0	0	0	0
299	8/23/2024 13:08	0	0	0	0
300	8/23/2024 13:09	0	0	0	0
301	8/23/2024 13:10	0	0	0	0
302	8/23/2024 13:11	0	0	0	0

NYSDEC Site No. 314008

303	8/23/2024 13:12	0	0	0	0
304	8/23/2024 13:13	0	0	0	0
305	8/23/2024 13:14	0	0	0	0
306	8/23/2024 13:15	0	0	0	0
307	8/23/2024 13:16	0	0	0	0
308	8/23/2024 13:17	0	0	0	0
309	8/23/2024 13:18	0	0	0	0
310	8/23/2024 13:19	0	0	0	0
311	8/23/2024 13:20	0	0	0	0
312	8/23/2024 13:21	0	0	0	0
313	8/23/2024 13:22	0	0	0	0
314	8/23/2024 13:23	0	0	0	0
315	8/23/2024 13:24	0	0	0	0
316	8/23/2024 13:25	0	0	0	0
317	8/23/2024 13:26	0	0	0	0
318	8/23/2024 13:27	0	0	0	0
319	8/23/2024 13:28	0	0	0	0
320	8/23/2024 13:29	0	0	0	0
321	8/23/2024 13:30	0	0	0	0
322	8/23/2024 13:31	0	0	0	0
323	8/23/2024 13:32	0	0	0	0
324	8/23/2024 13:33	0	0	0	0
325	8/23/2024 13:34	0	0	0	0
326	8/23/2024 13:35	0	0	0	0
327	8/23/2024 13:36	0	0	0	0
328	8/23/2024 13:37	0	0	0	0
329	8/23/2024 13:38	0	0	0	0
330	8/23/2024 13:39	0	0	0	0
331	8/23/2024 13:40	0	0	0	0
332	8/23/2024 13:41	0	0	0	0
333	8/23/2024 13:42	0	0	0	0
334	8/23/2024 13:43	0	0	0	0
335	8/23/2024 13:44	0	0	0	0
336	8/23/2024 13:45	0	0	0	0
337	8/23/2024 13:46	0	0	0	0
338	8/23/2024 13:47	0	0	0	0
339	8/23/2024 13:48	0	0	0	0
340	8/23/2024 13:49	0	0	0	0
341	8/23/2024 13:50	0	0	0	0
342	8/23/2024 13:51	0	0	0	0
343	8/23/2024 13:52	0	0	0	0
344	8/23/2024 13:53	0	0	0	0
345	8/23/2024 13:54	0	0	0	0
346	8/23/2024 13:55	0	0	0	0

NYSDEC Site No. 314008

347	8/23/2024 13:56	0	0	0	0
348	8/23/2024 13:57	0	0	0	0
349	8/23/2024 13:58	0	0	0	0
350	8/23/2024 13:59	0	0	0	0
351	8/23/2024 14:00	0	0	0	0
352	8/23/2024 14:01	0	0	0	0
353	8/23/2024 14:02	0	0	0	0
354	8/23/2024 14:03	0	0	0	0
355	8/23/2024 14:04	0	0	0	0
356	8/23/2024 14:05	0	0	0	0
357	8/23/2024 14:06	0	0	0	0
358	8/23/2024 14:07	0	0	0	0
359	8/23/2024 14:08	0	0	0	0
360	8/23/2024 14:09	0	0	0	0
361	8/23/2024 14:10	0	0	0	0
362	8/23/2024 14:11	0	0	0	0
363	8/23/2024 14:12	0	0	0	0
364	8/23/2024 14:13	0	0	0	0
365	8/23/2024 14:14	0	0	0	0
366	8/23/2024 14:15	0	0	0	0
367	8/23/2024 14:16	0	0	0	0
368	8/23/2024 14:17	0	0	0	0
369	8/23/2024 14:18	0	0	0	0
370	8/23/2024 14:19	0	0	0	0
371	8/23/2024 14:20	0	0	0	0
372	8/23/2024 14:21	0	0	0	0
373	8/23/2024 14:22	0	0	0	0
374	8/23/2024 14:23	0	0	0	0
375	8/23/2024 14:24	0	0	0	0
376	8/23/2024 14:25	0	0	0	0
377	8/23/2024 14:26	0	0	0	0
378	8/23/2024 14:27	0	0	0	0
379	8/23/2024 14:28	0	0	0	0
380	8/23/2024 14:29	0	0	0	0
Peak		0.2	0.4	1.5	0.3
Min		0	0	0	0
Average		0	0	0	0

TWA/STEL

Index	Date/Time	PID(ppm) (TWA)	PID(ppm) (STEL)
1	8/23/2024 8:10	0	---
2	8/23/2024 8:11	0	---

NYSDEC Site No. 314008

3	8/23/2024 8:12	0	---
4	8/23/2024 8:13	0	---
5	8/23/2024 8:14	0	---
6	8/23/2024 8:15	0	---
7	8/23/2024 8:16	0	---
8	8/23/2024 8:17	0	---
9	8/23/2024 8:18	0	---
10	8/23/2024 8:19	0	---
11	8/23/2024 8:20	0	---
12	8/23/2024 8:21	0	---
13	8/23/2024 8:22	0	---
14	8/23/2024 8:23	0	---
15	8/23/2024 8:24	0	0
16	8/23/2024 8:25	0	0
17	8/23/2024 8:26	0	0
18	8/23/2024 8:27	0	0
19	8/23/2024 8:28	0	0
20	8/23/2024 8:29	0	0
21	8/23/2024 8:30	0	0
22	8/23/2024 8:31	0	0
23	8/23/2024 8:32	0	0
24	8/23/2024 8:33	0	0
25	8/23/2024 8:34	0	0
26	8/23/2024 8:35	0	0
27	8/23/2024 8:36	0	0
28	8/23/2024 8:37	0	0
29	8/23/2024 8:38	0	0
30	8/23/2024 8:39	0	0
31	8/23/2024 8:40	0	0
32	8/23/2024 8:41	0	0
33	8/23/2024 8:42	0	0
34	8/23/2024 8:43	0	0
35	8/23/2024 8:44	0	0
36	8/23/2024 8:45	0	0
37	8/23/2024 8:46	0	0
38	8/23/2024 8:47	0	0
39	8/23/2024 8:48	0	0
40	8/23/2024 8:49	0	0
41	8/23/2024 8:50	0	0
42	8/23/2024 8:51	0	0
43	8/23/2024 8:52	0	0
44	8/23/2024 8:53	0	0
45	8/23/2024 8:54	0	0
46	8/23/2024 8:55	0	0

NYSDEC Site No. 314008

47	8/23/2024 8:56	0	0
48	8/23/2024 8:57	0	0
49	8/23/2024 8:58	0	0
50	8/23/2024 8:59	0	0
51	8/23/2024 9:00	0	0
52	8/23/2024 9:01	0	0
53	8/23/2024 9:02	0	0
54	8/23/2024 9:03	0	0
55	8/23/2024 9:04	0	0
56	8/23/2024 9:05	0	0
57	8/23/2024 9:06	0	0
58	8/23/2024 9:07	0	0
59	8/23/2024 9:08	0	0
60	8/23/2024 9:09	0	0
61	8/23/2024 9:10	0	0
62	8/23/2024 9:11	0	0
63	8/23/2024 9:12	0	0
64	8/23/2024 9:13	0	0
65	8/23/2024 9:14	0	0
66	8/23/2024 9:15	0	0
67	8/23/2024 9:16	0	0
68	8/23/2024 9:17	0	0
69	8/23/2024 9:18	0	0
70	8/23/2024 9:19	0	0
71	8/23/2024 9:20	0	0
72	8/23/2024 9:21	0	0
73	8/23/2024 9:22	0	0
74	8/23/2024 9:23	0	0
75	8/23/2024 9:24	0	0
76	8/23/2024 9:25	0	0
77	8/23/2024 9:26	0	0
78	8/23/2024 9:27	0	0
79	8/23/2024 9:28	0	0
80	8/23/2024 9:29	0	0
81	8/23/2024 9:30	0	0
82	8/23/2024 9:31	0	0
83	8/23/2024 9:32	0	0
84	8/23/2024 9:33	0	0
85	8/23/2024 9:34	0	0
86	8/23/2024 9:35	0	0
87	8/23/2024 9:36	0	0.1
88	8/23/2024 9:37	0	0.1
89	8/23/2024 9:38	0	0.1
90	8/23/2024 9:39	0	0.1

NYSDEC Site No. 314008

91	8/23/2024 9:40	0	0.1
92	8/23/2024 9:41	0	0.1
93	8/23/2024 9:42	0	0.1
94	8/23/2024 9:43	0	0.1
95	8/23/2024 9:44	0	0.1
96	8/23/2024 9:45	0	0.1
97	8/23/2024 9:46	0	0.1
98	8/23/2024 9:47	0	0.1
99	8/23/2024 9:48	0	0.1
100	8/23/2024 9:49	0	0.1
101	8/23/2024 9:50	0	0.1
102	8/23/2024 9:51	0	0.1
103	8/23/2024 9:52	0	0.1
104	8/23/2024 9:53	0	0.1
105	8/23/2024 9:54	0	0.1
106	8/23/2024 9:55	0	0.1
107	8/23/2024 9:56	0	0.1
108	8/23/2024 9:57	0	0.1
109	8/23/2024 9:58	0	0.1
110	8/23/2024 9:59	0	0.1
111	8/23/2024 10:00	0	0.1
112	8/23/2024 10:01	0	0.1
113	8/23/2024 10:02	0	0.1
114	8/23/2024 10:03	0	0.1
115	8/23/2024 10:04	0	0.1
116	8/23/2024 10:05	0	0.1
117	8/23/2024 10:06	0	0.1
118	8/23/2024 10:07	0	0.1
119	8/23/2024 10:08	0	0
120	8/23/2024 10:09	0	0
121	8/23/2024 10:10	0	0
122	8/23/2024 10:11	0	0
123	8/23/2024 10:12	0	0
124	8/23/2024 10:13	0	0
125	8/23/2024 10:14	0	0
126	8/23/2024 10:15	0	0
127	8/23/2024 10:16	0	0
128	8/23/2024 10:17	0	0
129	8/23/2024 10:18	0	0
130	8/23/2024 10:19	0	0
131	8/23/2024 10:20	0	0
132	8/23/2024 10:21	0	0
133	8/23/2024 10:22	0	0
134	8/23/2024 10:23	0	0

NYSDEC Site No. 314008

135	8/23/2024 10:24	0	0
136	8/23/2024 10:25	0	0
137	8/23/2024 10:26	0	0
138	8/23/2024 10:27	0	0
139	8/23/2024 10:28	0	0
140	8/23/2024 10:29	0	0
141	8/23/2024 10:30	0	0
142	8/23/2024 10:31	0	0
143	8/23/2024 10:32	0	0
144	8/23/2024 10:33	0	0
145	8/23/2024 10:34	0	0
146	8/23/2024 10:35	0	0
147	8/23/2024 10:36	0	0
148	8/23/2024 10:37	0	0
149	8/23/2024 10:38	0	0
150	8/23/2024 10:39	0	0
151	8/23/2024 10:40	0	0
152	8/23/2024 10:41	0	0
153	8/23/2024 10:42	0	0
154	8/23/2024 10:43	0	0
155	8/23/2024 10:44	0	0
156	8/23/2024 10:45	0	0
157	8/23/2024 10:46	0	0
158	8/23/2024 10:47	0	0
159	8/23/2024 10:48	0	0
160	8/23/2024 10:49	0	0
161	8/23/2024 10:50	0	0
162	8/23/2024 10:51	0	0
163	8/23/2024 10:52	0	0
164	8/23/2024 10:53	0	0
165	8/23/2024 10:54	0	0
166	8/23/2024 10:55	0	0
167	8/23/2024 10:56	0	0
168	8/23/2024 10:57	0	0
169	8/23/2024 10:58	0	0
170	8/23/2024 10:59	0	0
171	8/23/2024 11:00	0	0
172	8/23/2024 11:01	0	0
173	8/23/2024 11:02	0	0
174	8/23/2024 11:03	0	0
175	8/23/2024 11:04	0	0
176	8/23/2024 11:05	0	0
177	8/23/2024 11:06	0	0
178	8/23/2024 11:07	0	0

NYSDEC Site No. 314008

179	8/23/2024 11:08	0	0
180	8/23/2024 11:09	0	0
181	8/23/2024 11:10	0	0
182	8/23/2024 11:11	0	0
183	8/23/2024 11:12	0	0
184	8/23/2024 11:13	0	0
185	8/23/2024 11:14	0	0
186	8/23/2024 11:15	0	0
187	8/23/2024 11:16	0	0
188	8/23/2024 11:17	0	0
189	8/23/2024 11:18	0	0
190	8/23/2024 11:19	0	0
191	8/23/2024 11:20	0	0
192	8/23/2024 11:21	0	0
193	8/23/2024 11:22	0	0
194	8/23/2024 11:23	0	0
195	8/23/2024 11:24	0	0
196	8/23/2024 11:25	0	0
197	8/23/2024 11:26	0	0
198	8/23/2024 11:27	0	0
199	8/23/2024 11:28	0	0
200	8/23/2024 11:29	0	0
201	8/23/2024 11:30	0	0
202	8/23/2024 11:31	0	0
203	8/23/2024 11:32	0	0
204	8/23/2024 11:33	0	0
205	8/23/2024 11:34	0	0
206	8/23/2024 11:35	0	0
207	8/23/2024 11:36	0	0
208	8/23/2024 11:37	0	0
209	8/23/2024 11:38	0	0
210	8/23/2024 11:39	0	0
211	8/23/2024 11:40	0	0
212	8/23/2024 11:41	0	0
213	8/23/2024 11:42	0	0
214	8/23/2024 11:43	0	0
215	8/23/2024 11:44	0	0
216	8/23/2024 11:45	0	0
217	8/23/2024 11:46	0	0
218	8/23/2024 11:47	0	0
219	8/23/2024 11:48	0	0
220	8/23/2024 11:49	0	0
221	8/23/2024 11:50	0	0
222	8/23/2024 11:51	0	0

NYSDEC Site No. 314008

223	8/23/2024 11:52	0	0
224	8/23/2024 11:53	0	0
225	8/23/2024 11:54	0	0
226	8/23/2024 11:55	0	0
227	8/23/2024 11:56	0	0
228	8/23/2024 11:57	0	0
229	8/23/2024 11:58	0	0
230	8/23/2024 11:59	0	0
231	8/23/2024 12:00	0	0
232	8/23/2024 12:01	0	0
233	8/23/2024 12:02	0	0
234	8/23/2024 12:03	0	0
235	8/23/2024 12:04	0	0
236	8/23/2024 12:05	0	0
237	8/23/2024 12:06	0	0
238	8/23/2024 12:07	0	0
239	8/23/2024 12:08	0	0
240	8/23/2024 12:09	0	0
241	8/23/2024 12:10	0	0
242	8/23/2024 12:11	0	0
243	8/23/2024 12:12	0	0
244	8/23/2024 12:13	0	0
245	8/23/2024 12:14	0	0
246	8/23/2024 12:15	0	0
247	8/23/2024 12:16	0	0
248	8/23/2024 12:17	0	0
249	8/23/2024 12:18	0	0
250	8/23/2024 12:19	0	0
251	8/23/2024 12:20	0	0
252	8/23/2024 12:21	0	0
253	8/23/2024 12:22	0	0
254	8/23/2024 12:23	0	0
255	8/23/2024 12:24	0	0
256	8/23/2024 12:25	0	0
257	8/23/2024 12:26	0	0
258	8/23/2024 12:27	0	0
259	8/23/2024 12:28	0	0
260	8/23/2024 12:29	0	0
261	8/23/2024 12:30	0	0
262	8/23/2024 12:31	0	0
263	8/23/2024 12:32	0	0
264	8/23/2024 12:33	0	0
265	8/23/2024 12:34	0	0
266	8/23/2024 12:35	0	0

NYSDEC Site No. 314008

267	8/23/2024 12:36	0	0
268	8/23/2024 12:37	0	0
269	8/23/2024 12:38	0	0
270	8/23/2024 12:39	0	0
271	8/23/2024 12:40	0	0
272	8/23/2024 12:41	0	0
273	8/23/2024 12:42	0	0
274	8/23/2024 12:43	0	0
275	8/23/2024 12:44	0	0
276	8/23/2024 12:45	0	0
277	8/23/2024 12:46	0	0
278	8/23/2024 12:47	0	0
279	8/23/2024 12:48	0	0
280	8/23/2024 12:49	0	0
281	8/23/2024 12:50	0	0
282	8/23/2024 12:51	0	0
283	8/23/2024 12:52	0	0
284	8/23/2024 12:53	0	0
285	8/23/2024 12:54	0	0
286	8/23/2024 12:55	0	0
287	8/23/2024 12:56	0	0
288	8/23/2024 12:57	0	0
289	8/23/2024 12:58	0	0
290	8/23/2024 12:59	0	0
291	8/23/2024 13:00	0	0
292	8/23/2024 13:01	0	0
293	8/23/2024 13:02	0	0
294	8/23/2024 13:03	0	0
295	8/23/2024 13:04	0	0
296	8/23/2024 13:05	0	0
297	8/23/2024 13:06	0	0
298	8/23/2024 13:07	0	0
299	8/23/2024 13:08	0	0
300	8/23/2024 13:09	0	0
301	8/23/2024 13:10	0	0
302	8/23/2024 13:11	0	0
303	8/23/2024 13:12	0	0
304	8/23/2024 13:13	0	0
305	8/23/2024 13:14	0	0
306	8/23/2024 13:15	0	0
307	8/23/2024 13:16	0	0
308	8/23/2024 13:17	0	0
309	8/23/2024 13:18	0	0
310	8/23/2024 13:19	0	0

NYSDEC Site No. 314008

311	8/23/2024 13:20	0	0
312	8/23/2024 13:21	0	0
313	8/23/2024 13:22	0	0
314	8/23/2024 13:23	0	0
315	8/23/2024 13:24	0	0
316	8/23/2024 13:25	0	0
317	8/23/2024 13:26	0	0
318	8/23/2024 13:27	0	0
319	8/23/2024 13:28	0	0
320	8/23/2024 13:29	0	0
321	8/23/2024 13:30	0	0
322	8/23/2024 13:31	0	0
323	8/23/2024 13:32	0	0
324	8/23/2024 13:33	0	0
325	8/23/2024 13:34	0	0
326	8/23/2024 13:35	0	0
327	8/23/2024 13:36	0	0
328	8/23/2024 13:37	0	0
329	8/23/2024 13:38	0	0
330	8/23/2024 13:39	0	0
331	8/23/2024 13:40	0	0
332	8/23/2024 13:41	0	0
333	8/23/2024 13:42	0	0
334	8/23/2024 13:43	0	0
335	8/23/2024 13:44	0	0
336	8/23/2024 13:45	0	0
337	8/23/2024 13:46	0	0
338	8/23/2024 13:47	0	0
339	8/23/2024 13:48	0	0
340	8/23/2024 13:49	0	0
341	8/23/2024 13:50	0	0
342	8/23/2024 13:51	0	0
343	8/23/2024 13:52	0	0
344	8/23/2024 13:53	0	0
345	8/23/2024 13:54	0	0
346	8/23/2024 13:55	0	0
347	8/23/2024 13:56	0	0
348	8/23/2024 13:57	0	0
349	8/23/2024 13:58	0	0
350	8/23/2024 13:59	0	0
351	8/23/2024 14:00	0	0
352	8/23/2024 14:01	0	0
353	8/23/2024 14:02	0	0
354	8/23/2024 14:03	0	0

NYSDEC Site No. 314008

355	8/23/2024 14:04	0	0
356	8/23/2024 14:05	0	0
357	8/23/2024 14:06	0	0
358	8/23/2024 14:07	0	0
359	8/23/2024 14:08	0	0
360	8/23/2024 14:09	0	0
361	8/23/2024 14:10	0	0
362	8/23/2024 14:11	0	0
363	8/23/2024 14:12	0	0
364	8/23/2024 14:13	0	0
365	8/23/2024 14:14	0	0
366	8/23/2024 14:15	0	0
367	8/23/2024 14:16	0	0
368	8/23/2024 14:17	0	0
369	8/23/2024 14:18	0	0
370	8/23/2024 14:19	0	0
371	8/23/2024 14:20	0	0
372	8/23/2024 14:21	0	0
373	8/23/2024 14:22	0	0
374	8/23/2024 14:23	0	0
375	8/23/2024 14:24	0	0
376	8/23/2024 14:25	0	0
377	8/23/2024 14:26	0	0
378	8/23/2024 14:27	0	0
379	8/23/2024 14:28	0	0
380	8/23/2024 14:29	0	0

24/08/21 08:56

Summary

Unit Name MiniRAE 3000(PGM-7320)
Unit SN 592-904349
Unit Firmware Ver V2.22A

Running Mode Hygiene Mode
Datalog Mode Auto
Diagnostic Mode No
Stop Reason Power Down

Site ID 1
User ID 1

Begin 8/21/2024 8:56
End 8/21/2024 17:35
Sample Period(s) 60
Number of Records 519

Sensor PID(ppm)
Sensor SN S023030247C5
Measure Type Min; Avg; Max; Real
Span 100
Span 2 1000
Low Alarm 50
High Alarm 100
Over Alarm 15000
STEL Alarm 25
TWA Alarm 10
Measurement Gas Isobutylene
Calibration Time 8/13/2024 10:27
Peak 0
Min 0
Average 0

Datalog

Index	Date/Time	PID(ppm) (Min)	PID(ppm) (Avg)	PID(ppm) (Max)	PID(ppm) (Real)
1	8/21/2024 8:57	0	0	0	0
2	8/21/2024 8:58	0	0	0	0

NYSDEC Site No. 314008

3	8/21/2024 8:59	0	0	0	0
4	8/21/2024 9:00	0	0	0	0
5	8/21/2024 9:01	0	0	0	0
6	8/21/2024 9:02	0	0	0	0
7	8/21/2024 9:03	0	0	0	0
8	8/21/2024 9:04	0	0	0	0
9	8/21/2024 9:05	0	0	0	0
10	8/21/2024 9:06	0	0	0	0
11	8/21/2024 9:07	0	0	0	0
12	8/21/2024 9:08	0	0	0	0
13	8/21/2024 9:09	0	0	0	0
14	8/21/2024 9:10	0	0	0	0
15	8/21/2024 9:11	0	0	0	0
16	8/21/2024 9:12	0	0	0	0
17	8/21/2024 9:13	0	0	0	0
18	8/21/2024 9:14	0	0	0	0
19	8/21/2024 9:15	0	0	0	0
20	8/21/2024 9:16	0	0	0	0
21	8/21/2024 9:17	0	0	0	0
22	8/21/2024 9:18	0	0	0	0
23	8/21/2024 9:19	0	0	0	0
24	8/21/2024 9:20	0	0	0	0
25	8/21/2024 9:21	0	0	0	0
26	8/21/2024 9:22	0	0	0	0
27	8/21/2024 9:23	0	0	0	0
28	8/21/2024 9:24	0	0	0	0
29	8/21/2024 9:25	0	0	0	0
30	8/21/2024 9:26	0	0	0	0
31	8/21/2024 9:27	0	0	0	0
32	8/21/2024 9:28	0	0	0	0
33	8/21/2024 9:29	0	0	0	0
34	8/21/2024 9:30	0	0	0	0
35	8/21/2024 9:31	0	0	0	0
36	8/21/2024 9:32	0	0	0	0
37	8/21/2024 9:33	0	0	0	0
38	8/21/2024 9:34	0	0	0	0
39	8/21/2024 9:35	0	0	0	0
40	8/21/2024 9:36	0	0	0	0
41	8/21/2024 9:37	0	0	0	0
42	8/21/2024 9:38	0	0	0	0
43	8/21/2024 9:39	0	0	0	0
44	8/21/2024 9:40	0	0	0	0
45	8/21/2024 9:41	0	0	0	0
46	8/21/2024 9:42	0	0	0	0

NYSDEC Site No. 314008

47	8/21/2024 9:43	0	0	0	0
48	8/21/2024 9:44	0	0	0	0
49	8/21/2024 9:45	0	0	0	0
50	8/21/2024 9:46	0	0	0	0
51	8/21/2024 9:47	0	0	0	0
52	8/21/2024 9:48	0	0	0	0
53	8/21/2024 9:49	0	0	0	0
54	8/21/2024 9:50	0	0	0	0
55	8/21/2024 9:51	0	0	0	0
56	8/21/2024 9:52	0	0	0	0
57	8/21/2024 9:53	0	0	0	0
58	8/21/2024 9:54	0	0	0	0
59	8/21/2024 9:55	0	0	0	0
60	8/21/2024 9:56	0	0	0	0
61	8/21/2024 9:57	0	0	0	0
62	8/21/2024 9:58	0	0	0	0
63	8/21/2024 9:59	0	0	0	0
64	8/21/2024 10:00	0	0	0	0
65	8/21/2024 10:01	0	0	0	0
66	8/21/2024 10:02	0	0	0	0
67	8/21/2024 10:03	0	0	0	0
68	8/21/2024 10:04	0	0	0	0
69	8/21/2024 10:05	0	0	0	0
70	8/21/2024 10:06	0	0	0	0
71	8/21/2024 10:07	0	0	0	0
72	8/21/2024 10:08	0	0	0	0
73	8/21/2024 10:09	0	0	0	0
74	8/21/2024 10:10	0	0	0	0
75	8/21/2024 10:11	0	0	0	0
76	8/21/2024 10:12	0	0	0	0
77	8/21/2024 10:13	0	0	0	0
78	8/21/2024 10:14	0	0	0	0
79	8/21/2024 10:15	0	0	0	0
80	8/21/2024 10:16	0	0	0	0
81	8/21/2024 10:17	0	0	0	0
82	8/21/2024 10:18	0	0	0	0
83	8/21/2024 10:19	0	0	0	0
84	8/21/2024 10:20	0	0	0	0
85	8/21/2024 10:21	0	0	0	0
86	8/21/2024 10:22	0	0	0	0
87	8/21/2024 10:23	0	0	0	0
88	8/21/2024 10:24	0	0	0	0
89	8/21/2024 10:25	0	0	0	0
90	8/21/2024 10:26	0	0	0	0

91	8/21/2024 10:27	0	0	0	0
92	8/21/2024 10:28	0	0	0	0
93	8/21/2024 10:29	0	0	0	0
94	8/21/2024 10:30	0	0	0	0
95	8/21/2024 10:31	0	0	0	0
96	8/21/2024 10:32	0	0	0	0
97	8/21/2024 10:33	0	0	0	0
98	8/21/2024 10:34	0	0	0	0
99	8/21/2024 10:35	0	0	0	0
100	8/21/2024 10:36	0	0	0	0
101	8/21/2024 10:37	0	0	0	0
102	8/21/2024 10:38	0	0	0	0
103	8/21/2024 10:39	0	0	0	0
104	8/21/2024 10:40	0	0	0	0
105	8/21/2024 10:41	0	0	0	0
106	8/21/2024 10:42	0	0	0	0
107	8/21/2024 10:43	0	0	0	0
108	8/21/2024 10:44	0	0	0	0
109	8/21/2024 10:45	0	0	0	0
110	8/21/2024 10:46	0	0	0	0
111	8/21/2024 10:47	0	0	0	0
112	8/21/2024 10:48	0	0	0	0
113	8/21/2024 10:49	0	0	0	0
114	8/21/2024 10:50	0	0	0	0
115	8/21/2024 10:51	0	0	0	0
116	8/21/2024 10:52	0	0	0	0
117	8/21/2024 10:53	0	0	0	0
118	8/21/2024 10:54	0	0	0	0
119	8/21/2024 10:55	0	0	0	0
120	8/21/2024 10:56	0	0	0	0
121	8/21/2024 10:57	0	0	0	0
122	8/21/2024 10:58	0	0	0	0
123	8/21/2024 10:59	0	0	0	0
124	8/21/2024 11:00	0	0	0	0
125	8/21/2024 11:01	0	0	0	0
126	8/21/2024 11:02	0	0	0	0
127	8/21/2024 11:03	0	0	0	0
128	8/21/2024 11:04	0	0	0	0
129	8/21/2024 11:05	0	0	0	0
130	8/21/2024 11:06	0	0	0	0
131	8/21/2024 11:07	0	0	0	0
132	8/21/2024 11:08	0	0	0	0
133	8/21/2024 11:09	0	0	0	0
134	8/21/2024 11:10	0	0	0	0

NYSDEC Site No. 314008

135	8/21/2024 11:11	0	0	0	0
136	8/21/2024 11:12	0	0	0	0
137	8/21/2024 11:13	0	0	0	0
138	8/21/2024 11:14	0	0	0	0
139	8/21/2024 11:15	0	0	0	0
140	8/21/2024 11:16	0	0	0	0
141	8/21/2024 11:17	0	0	0	0
142	8/21/2024 11:18	0	0	0	0
143	8/21/2024 11:19	0	0	0	0
144	8/21/2024 11:20	0	0	0	0
145	8/21/2024 11:21	0	0	0	0
146	8/21/2024 11:22	0	0	0	0
147	8/21/2024 11:23	0	0	0	0
148	8/21/2024 11:24	0	0	0	0
149	8/21/2024 11:25	0	0	0	0
150	8/21/2024 11:26	0	0	0	0
151	8/21/2024 11:27	0	0	0	0
152	8/21/2024 11:28	0	0	0	0
153	8/21/2024 11:29	0	0	0	0
154	8/21/2024 11:30	0	0	0	0
155	8/21/2024 11:31	0	0	0	0
156	8/21/2024 11:32	0	0	0	0
157	8/21/2024 11:33	0	0	0	0
158	8/21/2024 11:34	0	0	0	0
159	8/21/2024 11:35	0	0	0	0
160	8/21/2024 11:36	0	0	0	0
161	8/21/2024 11:37	0	0	0	0
162	8/21/2024 11:38	0	0	0	0
163	8/21/2024 11:39	0	0	0	0
164	8/21/2024 11:40	0	0	0	0
165	8/21/2024 11:41	0	0	0	0
166	8/21/2024 11:42	0	0	0	0
167	8/21/2024 11:43	0	0	0	0
168	8/21/2024 11:44	0	0	0	0
169	8/21/2024 11:45	0	0	0	0
170	8/21/2024 11:46	0	0	0	0
171	8/21/2024 11:47	0	0	0	0
172	8/21/2024 11:48	0	0	0	0
173	8/21/2024 11:49	0	0	0	0
174	8/21/2024 11:50	0	0	0	0
175	8/21/2024 11:51	0	0	0	0
176	8/21/2024 11:52	0	0	0	0
177	8/21/2024 11:53	0	0	0	0
178	8/21/2024 11:54	0	0	0	0

NYSDEC Site No. 314008

179	8/21/2024 11:55	0	0	0	0
180	8/21/2024 11:56	0	0	0	0
181	8/21/2024 11:57	0	0	0	0
182	8/21/2024 11:58	0	0	0	0
183	8/21/2024 11:59	0	0	0	0
184	8/21/2024 12:00	0	0	0	0
185	8/21/2024 12:01	0	0	0	0
186	8/21/2024 12:02	0	0	0	0
187	8/21/2024 12:03	0	0	0	0
188	8/21/2024 12:04	0	0	0	0
189	8/21/2024 12:05	0	0	0	0
190	8/21/2024 12:06	0	0	0	0
191	8/21/2024 12:07	0	0	0	0
192	8/21/2024 12:08	0	0	0	0
193	8/21/2024 12:09	0	0	0	0
194	8/21/2024 12:10	0	0	0	0
195	8/21/2024 12:11	0	0	0	0
196	8/21/2024 12:12	0	0	0	0
197	8/21/2024 12:13	0	0	0	0
198	8/21/2024 12:14	0	0	0	0
199	8/21/2024 12:15	0	0	0	0
200	8/21/2024 12:16	0	0	0	0
201	8/21/2024 12:17	0	0	0	0
202	8/21/2024 12:18	0	0	0	0
203	8/21/2024 12:19	0	0	0	0
204	8/21/2024 12:20	0	0	0	0
205	8/21/2024 12:21	0	0	0	0
206	8/21/2024 12:22	0	0	0	0
207	8/21/2024 12:23	0	0	0	0
208	8/21/2024 12:24	0	0	0	0
209	8/21/2024 12:25	0	0	0	0
210	8/21/2024 12:26	0	0	0	0
211	8/21/2024 12:27	0	0	0	0
212	8/21/2024 12:28	0	0	0	0
213	8/21/2024 12:29	0	0	0	0
214	8/21/2024 12:30	0	0	0	0
215	8/21/2024 12:31	0	0	0	0
216	8/21/2024 12:32	0	0	0	0
217	8/21/2024 12:33	0	0	0	0
218	8/21/2024 12:34	0	0	0	0
219	8/21/2024 12:35	0	0	0	0
220	8/21/2024 12:36	0	0	0	0
221	8/21/2024 12:37	0	0	0	0
222	8/21/2024 12:38	0	0	0	0

NYSDEC Site No. 314008

223	8/21/2024 12:39	0	0	0	0
224	8/21/2024 12:40	0	0	0	0
225	8/21/2024 12:41	0	0	0	0
226	8/21/2024 12:42	0	0	0	0
227	8/21/2024 12:43	0	0	0	0
228	8/21/2024 12:44	0	0	0	0
229	8/21/2024 12:45	0	0	0	0
230	8/21/2024 12:46	0	0	0	0
231	8/21/2024 12:47	0	0	0	0
232	8/21/2024 12:48	0	0	0	0
233	8/21/2024 12:49	0	0	0	0
234	8/21/2024 12:50	0	0	0	0
235	8/21/2024 12:51	0	0	0	0
236	8/21/2024 12:52	0	0	0	0
237	8/21/2024 12:53	0	0	0	0
238	8/21/2024 12:54	0	0	0	0
239	8/21/2024 12:55	0	0	0	0
240	8/21/2024 12:56	0	0	0	0
241	8/21/2024 12:57	0	0	0	0
242	8/21/2024 12:58	0	0	0	0
243	8/21/2024 12:59	0	0	0	0
244	8/21/2024 13:00	0	0	0	0
245	8/21/2024 13:01	0	0	0	0
246	8/21/2024 13:02	0	0	0	0
247	8/21/2024 13:03	0	0	0	0
248	8/21/2024 13:04	0	0	0	0
249	8/21/2024 13:05	0	0	0	0
250	8/21/2024 13:06	0	0	0	0
251	8/21/2024 13:07	0	0	0	0
252	8/21/2024 13:08	0	0	0	0
253	8/21/2024 13:09	0	0	0	0
254	8/21/2024 13:10	0	0	0	0
255	8/21/2024 13:11	0	0	0	0
256	8/21/2024 13:12	0	0	0	0
257	8/21/2024 13:13	0	0	0	0
258	8/21/2024 13:14	0	0	0	0
259	8/21/2024 13:15	0	0	0	0
260	8/21/2024 13:16	0	0	0	0
261	8/21/2024 13:17	0	0	0	0
262	8/21/2024 13:18	0	0	0	0
263	8/21/2024 13:19	0	0	0	0
264	8/21/2024 13:20	0	0	0	0
265	8/21/2024 13:21	0	0	0	0
266	8/21/2024 13:22	0	0	0	0

NYSDEC Site No. 314008

267	8/21/2024 13:23	0	0	0	0
268	8/21/2024 13:24	0	0	0	0
269	8/21/2024 13:25	0	0	0	0
270	8/21/2024 13:26	0	0	0	0
271	8/21/2024 13:27	0	0	0	0
272	8/21/2024 13:28	0	0	0	0
273	8/21/2024 13:29	0	0	0	0
274	8/21/2024 13:30	0	0	0	0
275	8/21/2024 13:31	0	0	0	0
276	8/21/2024 13:32	0	0	0	0
277	8/21/2024 13:33	0	0	0	0
278	8/21/2024 13:34	0	0	0	0
279	8/21/2024 13:35	0	0	0	0
280	8/21/2024 13:36	0	0	0	0
281	8/21/2024 13:37	0	0	0	0
282	8/21/2024 13:38	0	0	0	0
283	8/21/2024 13:39	0	0	0	0
284	8/21/2024 13:40	0	0	0	0
285	8/21/2024 13:41	0	0	0	0
286	8/21/2024 13:42	0	0	0	0
287	8/21/2024 13:43	0	0	0	0
288	8/21/2024 13:44	0	0	0	0
289	8/21/2024 13:45	0	0	0	0
290	8/21/2024 13:46	0	0	0	0
291	8/21/2024 13:47	0	0	0	0
292	8/21/2024 13:48	0	0	0	0
293	8/21/2024 13:49	0	0	0	0
294	8/21/2024 13:50	0	0	0	0
295	8/21/2024 13:51	0	0	0	0
296	8/21/2024 13:52	0	0	0	0
297	8/21/2024 13:53	0	0	0	0
298	8/21/2024 13:54	0	0	0	0
299	8/21/2024 13:55	0	0	0	0
300	8/21/2024 13:56	0	0	0	0
301	8/21/2024 13:57	0	0	0	0
302	8/21/2024 13:58	0	0	0	0
303	8/21/2024 13:59	0	0	0	0
304	8/21/2024 14:00	0	0	0	0
305	8/21/2024 14:01	0	0	0	0
306	8/21/2024 14:02	0	0	0	0
307	8/21/2024 14:03	0	0	0	0
308	8/21/2024 14:04	0	0	0	0
309	8/21/2024 14:05	0	0	0	0
310	8/21/2024 14:06	0	0	0	0

NYSDEC Site No. 314008

311	8/21/2024 14:07	0	0	0	0
312	8/21/2024 14:08	0	0	0	0
313	8/21/2024 14:09	0	0	0	0
314	8/21/2024 14:10	0	0	0	0
315	8/21/2024 14:11	0	0	0	0
316	8/21/2024 14:12	0	0	0	0
317	8/21/2024 14:13	0	0	0	0
318	8/21/2024 14:14	0	0	0	0
319	8/21/2024 14:15	0	0	0	0
320	8/21/2024 14:16	0	0	0	0
321	8/21/2024 14:17	0	0	0	0
322	8/21/2024 14:18	0	0	0	0
323	8/21/2024 14:19	0	0	0	0
324	8/21/2024 14:20	0	0	0	0
325	8/21/2024 14:21	0	0	0	0
326	8/21/2024 14:22	0	0	0	0
327	8/21/2024 14:23	0	0	0	0
328	8/21/2024 14:24	0	0	0	0
329	8/21/2024 14:25	0	0	0	0
330	8/21/2024 14:26	0	0	0	0
331	8/21/2024 14:27	0	0	0	0
332	8/21/2024 14:28	0	0	0	0
333	8/21/2024 14:29	0	0	0	0
334	8/21/2024 14:30	0	0	0	0
335	8/21/2024 14:31	0	0	0	0
336	8/21/2024 14:32	0	0	0	0
337	8/21/2024 14:33	0	0	0	0
338	8/21/2024 14:34	0	0	0	0
339	8/21/2024 14:35	0	0	0	0
340	8/21/2024 14:36	0	0	0	0
341	8/21/2024 14:37	0	0	0	0
342	8/21/2024 14:38	0	0	0	0
343	8/21/2024 14:39	0	0	0	0
344	8/21/2024 14:40	0	0	0	0
345	8/21/2024 14:41	0	0	0	0
346	8/21/2024 14:42	0	0	0	0
347	8/21/2024 14:43	0	0	0	0
348	8/21/2024 14:44	0	0	0	0
349	8/21/2024 14:45	0	0	0	0
350	8/21/2024 14:46	0	0	0	0
351	8/21/2024 14:47	0	0	0	0
352	8/21/2024 14:48	0	0	0	0
353	8/21/2024 14:49	0	0	0	0
354	8/21/2024 14:50	0	0	0	0

NYSDEC Site No. 314008

355	8/21/2024 14:51	0	0	0	0
356	8/21/2024 14:52	0	0	0	0
357	8/21/2024 14:53	0	0	0	0
358	8/21/2024 14:54	0	0	0	0
359	8/21/2024 14:55	0	0	0	0
360	8/21/2024 14:56	0	0	0	0
361	8/21/2024 14:57	0	0	0	0
362	8/21/2024 14:58	0	0	0	0
363	8/21/2024 14:59	0	0	0	0
364	8/21/2024 15:00	0	0	0	0
365	8/21/2024 15:01	0	0	0	0
366	8/21/2024 15:02	0	0	0	0
367	8/21/2024 15:03	0	0	0	0
368	8/21/2024 15:04	0	0	0	0
369	8/21/2024 15:05	0	0	0	0
370	8/21/2024 15:06	0	0	0	0
371	8/21/2024 15:07	0	0	0	0
372	8/21/2024 15:08	0	0	0	0
373	8/21/2024 15:09	0	0	0	0
374	8/21/2024 15:10	0	0	0	0
375	8/21/2024 15:11	0	0	0	0
376	8/21/2024 15:12	0	0	0	0
377	8/21/2024 15:13	0	0	0	0
378	8/21/2024 15:14	0	0	0	0
379	8/21/2024 15:15	0	0	0	0
380	8/21/2024 15:16	0	0	0	0
381	8/21/2024 15:17	0	0	0	0
382	8/21/2024 15:18	0	0	0	0
383	8/21/2024 15:19	0	0	0	0
384	8/21/2024 15:20	0	0	0	0
385	8/21/2024 15:21	0	0	0	0
386	8/21/2024 15:22	0	0	0	0
387	8/21/2024 15:23	0	0	0	0
388	8/21/2024 15:24	0	0	0	0
389	8/21/2024 15:25	0	0	0	0
390	8/21/2024 15:26	0	0	0	0
391	8/21/2024 15:27	0	0	0	0
392	8/21/2024 15:28	0	0	0	0
393	8/21/2024 15:29	0	0	0	0
394	8/21/2024 15:30	0	0	0	0
395	8/21/2024 15:31	0	0	0	0
396	8/21/2024 15:32	0	0	0	0
397	8/21/2024 15:33	0	0	0	0
398	8/21/2024 15:34	0	0	0	0

NYSDEC Site No. 314008

399	8/21/2024 15:35	0	0	0	0
400	8/21/2024 15:36	0	0	0	0
401	8/21/2024 15:37	0	0	0	0
402	8/21/2024 15:38	0	0	0	0
403	8/21/2024 15:39	0	0	0	0
404	8/21/2024 15:40	0	0	0	0
405	8/21/2024 15:41	0	0	0	0
406	8/21/2024 15:42	0	0	0	0
407	8/21/2024 15:43	0	0	0	0
408	8/21/2024 15:44	0	0	0	0
409	8/21/2024 15:45	0	0	0	0
410	8/21/2024 15:46	0	0	0	0
411	8/21/2024 15:47	0	0	0	0
412	8/21/2024 15:48	0	0	0	0
413	8/21/2024 15:49	0	0	0	0
414	8/21/2024 15:50	0	0	0	0
415	8/21/2024 15:51	0	0	0	0
416	8/21/2024 15:52	0	0	0	0
417	8/21/2024 15:53	0	0	0	0
418	8/21/2024 15:54	0	0	0	0
419	8/21/2024 15:55	0	0	0	0
420	8/21/2024 15:56	0	0	0	0
421	8/21/2024 15:57	0	0	0	0
422	8/21/2024 15:58	0	0	0	0
423	8/21/2024 15:59	0	0	0	0
424	8/21/2024 16:00	0	0	0	0
425	8/21/2024 16:01	0	0	0	0
426	8/21/2024 16:02	0	0	0	0
427	8/21/2024 16:03	0	0	0	0
428	8/21/2024 16:04	0	0	0	0
429	8/21/2024 16:05	0	0	0	0
430	8/21/2024 16:06	0	0	0	0
431	8/21/2024 16:07	0	0	0	0
432	8/21/2024 16:08	0	0	0	0
433	8/21/2024 16:09	0	0	0	0
434	8/21/2024 16:10	0	0	0	0
435	8/21/2024 16:11	0	0	0	0
436	8/21/2024 16:12	0	0	0	0
437	8/21/2024 16:13	0	0	0	0
438	8/21/2024 16:14	0	0	0	0
439	8/21/2024 16:15	0	0	0	0
440	8/21/2024 16:16	0	0	0	0
441	8/21/2024 16:17	0	0	0	0
442	8/21/2024 16:18	0	0	0	0

NYSDEC Site No. 314008

443	8/21/2024 16:19	0	0	0	0
444	8/21/2024 16:20	0	0	0	0
445	8/21/2024 16:21	0	0	0	0
446	8/21/2024 16:22	0	0	0	0
447	8/21/2024 16:23	0	0	0	0
448	8/21/2024 16:24	0	0	0	0
449	8/21/2024 16:25	0	0	0	0
450	8/21/2024 16:26	0	0	0	0
451	8/21/2024 16:27	0	0	0	0
452	8/21/2024 16:28	0	0	0	0
453	8/21/2024 16:29	0	0	0	0
454	8/21/2024 16:30	0	0	0	0
455	8/21/2024 16:31	0	0	0	0
456	8/21/2024 16:32	0	0	0	0
457	8/21/2024 16:33	0	0	0	0
458	8/21/2024 16:34	0	0	0	0
459	8/21/2024 16:35	0	0	0	0
460	8/21/2024 16:36	0	0	0	0
461	8/21/2024 16:37	0	0	0	0
462	8/21/2024 16:38	0	0	0	0
463	8/21/2024 16:39	0	0	0	0
464	8/21/2024 16:40	0	0	0	0
465	8/21/2024 16:41	0	0	0	0
466	8/21/2024 16:42	0	0	0	0
467	8/21/2024 16:43	0	0	0	0
468	8/21/2024 16:44	0	0	0	0
469	8/21/2024 16:45	0	0	0	0
470	8/21/2024 16:46	0	0	0	0
471	8/21/2024 16:47	0	0	0	0
472	8/21/2024 16:48	0	0	0	0
473	8/21/2024 16:49	0	0	0	0
474	8/21/2024 16:50	0	0	0	0
475	8/21/2024 16:51	0	0	0	0
476	8/21/2024 16:52	0	0	0	0
477	8/21/2024 16:53	0	0	0	0
478	8/21/2024 16:54	0	0	0	0
479	8/21/2024 16:55	0	0	0	0
480	8/21/2024 16:56	0	0	0	0
481	8/21/2024 16:57	0	0	0	0
482	8/21/2024 16:58	0	0	0	0
483	8/21/2024 16:59	0	0	0	0
484	8/21/2024 17:00	0	0	0	0
485	8/21/2024 17:01	0	0	0	0
486	8/21/2024 17:02	0	0	0	0

NYSDEC Site No. 314008

487	8/21/2024 17:03	0	0	0	0
488	8/21/2024 17:04	0	0	0	0
489	8/21/2024 17:05	0	0	0	0
490	8/21/2024 17:06	0	0	0	0
491	8/21/2024 17:07	0	0	0	0
492	8/21/2024 17:08	0	0	0	0
493	8/21/2024 17:09	0	0	0	0
494	8/21/2024 17:10	0	0	0	0
495	8/21/2024 17:11	0	0	0	0
496	8/21/2024 17:12	0	0	0	0
497	8/21/2024 17:13	0	0	0	0
498	8/21/2024 17:14	0	0	0	0
499	8/21/2024 17:15	0	0	0	0
500	8/21/2024 17:16	0	0	0	0
501	8/21/2024 17:17	0	0	0	0
502	8/21/2024 17:18	0	0	0	0
503	8/21/2024 17:19	0	0	0	0
504	8/21/2024 17:20	0	0	0	0
505	8/21/2024 17:21	0	0	0	0
506	8/21/2024 17:22	0	0	0	0
507	8/21/2024 17:23	0	0	0	0
508	8/21/2024 17:24	0	0	0	0
509	8/21/2024 17:25	0	0	0	0
510	8/21/2024 17:26	0	0	0	0
511	8/21/2024 17:27	0	0	0	0
512	8/21/2024 17:28	0	0	0	0
513	8/21/2024 17:29	0	0	0	0
514	8/21/2024 17:30	0	0	0	0
515	8/21/2024 17:31	0	0	0	0
516	8/21/2024 17:32	0	0	0	0
517	8/21/2024 17:33	0	0	0	0
518	8/21/2024 17:34	0	0	0	0
519	8/21/2024 17:35	0	0	0	0
Peak		0	0	0	0
Min		0	0	0	0
Average		0	0	0	0

TWA/STEL

Index	Date/Time	PID(ppm) (TWA)	PID(ppm) (STEL)
1	8/21/2024 8:57	0	---
2	8/21/2024 8:58	0	---
3	8/21/2024 8:59	0	---

NYSDEC Site No. 314008

4	8/21/2024 9:00	0	---
5	8/21/2024 9:01	0	---
6	8/21/2024 9:02	0	---
7	8/21/2024 9:03	0	---
8	8/21/2024 9:04	0	---
9	8/21/2024 9:05	0	---
10	8/21/2024 9:06	0	---
11	8/21/2024 9:07	0	---
12	8/21/2024 9:08	0	---
13	8/21/2024 9:09	0	---
14	8/21/2024 9:10	0	---
15	8/21/2024 9:11	0	0
16	8/21/2024 9:12	0	0
17	8/21/2024 9:13	0	0
18	8/21/2024 9:14	0	0
19	8/21/2024 9:15	0	0
20	8/21/2024 9:16	0	0
21	8/21/2024 9:17	0	0
22	8/21/2024 9:18	0	0
23	8/21/2024 9:19	0	0
24	8/21/2024 9:20	0	0
25	8/21/2024 9:21	0	0
26	8/21/2024 9:22	0	0
27	8/21/2024 9:23	0	0
28	8/21/2024 9:24	0	0
29	8/21/2024 9:25	0	0
30	8/21/2024 9:26	0	0
31	8/21/2024 9:27	0	0
32	8/21/2024 9:28	0	0
33	8/21/2024 9:29	0	0
34	8/21/2024 9:30	0	0
35	8/21/2024 9:31	0	0
36	8/21/2024 9:32	0	0
37	8/21/2024 9:33	0	0
38	8/21/2024 9:34	0	0
39	8/21/2024 9:35	0	0
40	8/21/2024 9:36	0	0
41	8/21/2024 9:37	0	0
42	8/21/2024 9:38	0	0
43	8/21/2024 9:39	0	0
44	8/21/2024 9:40	0	0
45	8/21/2024 9:41	0	0
46	8/21/2024 9:42	0	0
47	8/21/2024 9:43	0	0

NYSDEC Site No. 314008

48	8/21/2024 9:44	0	0
49	8/21/2024 9:45	0	0
50	8/21/2024 9:46	0	0
51	8/21/2024 9:47	0	0
52	8/21/2024 9:48	0	0
53	8/21/2024 9:49	0	0
54	8/21/2024 9:50	0	0
55	8/21/2024 9:51	0	0
56	8/21/2024 9:52	0	0
57	8/21/2024 9:53	0	0
58	8/21/2024 9:54	0	0
59	8/21/2024 9:55	0	0
60	8/21/2024 9:56	0	0
61	8/21/2024 9:57	0	0
62	8/21/2024 9:58	0	0
63	8/21/2024 9:59	0	0
64	8/21/2024 10:00	0	0
65	8/21/2024 10:01	0	0
66	8/21/2024 10:02	0	0
67	8/21/2024 10:03	0	0
68	8/21/2024 10:04	0	0
69	8/21/2024 10:05	0	0
70	8/21/2024 10:06	0	0
71	8/21/2024 10:07	0	0
72	8/21/2024 10:08	0	0
73	8/21/2024 10:09	0	0
74	8/21/2024 10:10	0	0
75	8/21/2024 10:11	0	0
76	8/21/2024 10:12	0	0
77	8/21/2024 10:13	0	0
78	8/21/2024 10:14	0	0
79	8/21/2024 10:15	0	0
80	8/21/2024 10:16	0	0
81	8/21/2024 10:17	0	0
82	8/21/2024 10:18	0	0
83	8/21/2024 10:19	0	0
84	8/21/2024 10:20	0	0
85	8/21/2024 10:21	0	0
86	8/21/2024 10:22	0	0
87	8/21/2024 10:23	0	0
88	8/21/2024 10:24	0	0
89	8/21/2024 10:25	0	0
90	8/21/2024 10:26	0	0
91	8/21/2024 10:27	0	0

NYSDEC Site No. 314008

92	8/21/2024 10:28	0	0
93	8/21/2024 10:29	0	0
94	8/21/2024 10:30	0	0
95	8/21/2024 10:31	0	0
96	8/21/2024 10:32	0	0
97	8/21/2024 10:33	0	0
98	8/21/2024 10:34	0	0
99	8/21/2024 10:35	0	0
100	8/21/2024 10:36	0	0
101	8/21/2024 10:37	0	0
102	8/21/2024 10:38	0	0
103	8/21/2024 10:39	0	0
104	8/21/2024 10:40	0	0
105	8/21/2024 10:41	0	0
106	8/21/2024 10:42	0	0
107	8/21/2024 10:43	0	0
108	8/21/2024 10:44	0	0
109	8/21/2024 10:45	0	0
110	8/21/2024 10:46	0	0
111	8/21/2024 10:47	0	0
112	8/21/2024 10:48	0	0
113	8/21/2024 10:49	0	0
114	8/21/2024 10:50	0	0
115	8/21/2024 10:51	0	0
116	8/21/2024 10:52	0	0
117	8/21/2024 10:53	0	0
118	8/21/2024 10:54	0	0
119	8/21/2024 10:55	0	0
120	8/21/2024 10:56	0	0
121	8/21/2024 10:57	0	0
122	8/21/2024 10:58	0	0
123	8/21/2024 10:59	0	0
124	8/21/2024 11:00	0	0
125	8/21/2024 11:01	0	0
126	8/21/2024 11:02	0	0
127	8/21/2024 11:03	0	0
128	8/21/2024 11:04	0	0
129	8/21/2024 11:05	0	0
130	8/21/2024 11:06	0	0
131	8/21/2024 11:07	0	0
132	8/21/2024 11:08	0	0
133	8/21/2024 11:09	0	0
134	8/21/2024 11:10	0	0
135	8/21/2024 11:11	0	0

NYSDEC Site No. 314008

136	8/21/2024 11:12	0	0
137	8/21/2024 11:13	0	0
138	8/21/2024 11:14	0	0
139	8/21/2024 11:15	0	0
140	8/21/2024 11:16	0	0
141	8/21/2024 11:17	0	0
142	8/21/2024 11:18	0	0
143	8/21/2024 11:19	0	0
144	8/21/2024 11:20	0	0
145	8/21/2024 11:21	0	0
146	8/21/2024 11:22	0	0
147	8/21/2024 11:23	0	0
148	8/21/2024 11:24	0	0
149	8/21/2024 11:25	0	0
150	8/21/2024 11:26	0	0
151	8/21/2024 11:27	0	0
152	8/21/2024 11:28	0	0
153	8/21/2024 11:29	0	0
154	8/21/2024 11:30	0	0
155	8/21/2024 11:31	0	0
156	8/21/2024 11:32	0	0
157	8/21/2024 11:33	0	0
158	8/21/2024 11:34	0	0
159	8/21/2024 11:35	0	0
160	8/21/2024 11:36	0	0
161	8/21/2024 11:37	0	0
162	8/21/2024 11:38	0	0
163	8/21/2024 11:39	0	0
164	8/21/2024 11:40	0	0
165	8/21/2024 11:41	0	0
166	8/21/2024 11:42	0	0
167	8/21/2024 11:43	0	0
168	8/21/2024 11:44	0	0
169	8/21/2024 11:45	0	0
170	8/21/2024 11:46	0	0
171	8/21/2024 11:47	0	0
172	8/21/2024 11:48	0	0
173	8/21/2024 11:49	0	0
174	8/21/2024 11:50	0	0
175	8/21/2024 11:51	0	0
176	8/21/2024 11:52	0	0
177	8/21/2024 11:53	0	0
178	8/21/2024 11:54	0	0
179	8/21/2024 11:55	0	0

NYSDEC Site No. 314008

180	8/21/2024 11:56	0	0
181	8/21/2024 11:57	0	0
182	8/21/2024 11:58	0	0
183	8/21/2024 11:59	0	0
184	8/21/2024 12:00	0	0
185	8/21/2024 12:01	0	0
186	8/21/2024 12:02	0	0
187	8/21/2024 12:03	0	0
188	8/21/2024 12:04	0	0
189	8/21/2024 12:05	0	0
190	8/21/2024 12:06	0	0
191	8/21/2024 12:07	0	0
192	8/21/2024 12:08	0	0
193	8/21/2024 12:09	0	0
194	8/21/2024 12:10	0	0
195	8/21/2024 12:11	0	0
196	8/21/2024 12:12	0	0
197	8/21/2024 12:13	0	0
198	8/21/2024 12:14	0	0
199	8/21/2024 12:15	0	0
200	8/21/2024 12:16	0	0
201	8/21/2024 12:17	0	0
202	8/21/2024 12:18	0	0
203	8/21/2024 12:19	0	0
204	8/21/2024 12:20	0	0
205	8/21/2024 12:21	0	0
206	8/21/2024 12:22	0	0
207	8/21/2024 12:23	0	0
208	8/21/2024 12:24	0	0
209	8/21/2024 12:25	0	0
210	8/21/2024 12:26	0	0
211	8/21/2024 12:27	0	0
212	8/21/2024 12:28	0	0
213	8/21/2024 12:29	0	0
214	8/21/2024 12:30	0	0
215	8/21/2024 12:31	0	0
216	8/21/2024 12:32	0	0
217	8/21/2024 12:33	0	0
218	8/21/2024 12:34	0	0
219	8/21/2024 12:35	0	0
220	8/21/2024 12:36	0	0
221	8/21/2024 12:37	0	0
222	8/21/2024 12:38	0	0
223	8/21/2024 12:39	0	0

NYSDEC Site No. 314008

224	8/21/2024 12:40	0	0
225	8/21/2024 12:41	0	0
226	8/21/2024 12:42	0	0
227	8/21/2024 12:43	0	0
228	8/21/2024 12:44	0	0
229	8/21/2024 12:45	0	0
230	8/21/2024 12:46	0	0
231	8/21/2024 12:47	0	0
232	8/21/2024 12:48	0	0
233	8/21/2024 12:49	0	0
234	8/21/2024 12:50	0	0
235	8/21/2024 12:51	0	0
236	8/21/2024 12:52	0	0
237	8/21/2024 12:53	0	0
238	8/21/2024 12:54	0	0
239	8/21/2024 12:55	0	0
240	8/21/2024 12:56	0	0
241	8/21/2024 12:57	0	0
242	8/21/2024 12:58	0	0
243	8/21/2024 12:59	0	0
244	8/21/2024 13:00	0	0
245	8/21/2024 13:01	0	0
246	8/21/2024 13:02	0	0
247	8/21/2024 13:03	0	0
248	8/21/2024 13:04	0	0
249	8/21/2024 13:05	0	0
250	8/21/2024 13:06	0	0
251	8/21/2024 13:07	0	0
252	8/21/2024 13:08	0	0
253	8/21/2024 13:09	0	0
254	8/21/2024 13:10	0	0
255	8/21/2024 13:11	0	0
256	8/21/2024 13:12	0	0
257	8/21/2024 13:13	0	0
258	8/21/2024 13:14	0	0
259	8/21/2024 13:15	0	0
260	8/21/2024 13:16	0	0
261	8/21/2024 13:17	0	0
262	8/21/2024 13:18	0	0
263	8/21/2024 13:19	0	0
264	8/21/2024 13:20	0	0
265	8/21/2024 13:21	0	0
266	8/21/2024 13:22	0	0
267	8/21/2024 13:23	0	0

NYSDEC Site No. 314008

268	8/21/2024 13:24	0	0
269	8/21/2024 13:25	0	0
270	8/21/2024 13:26	0	0
271	8/21/2024 13:27	0	0
272	8/21/2024 13:28	0	0
273	8/21/2024 13:29	0	0
274	8/21/2024 13:30	0	0
275	8/21/2024 13:31	0	0
276	8/21/2024 13:32	0	0
277	8/21/2024 13:33	0	0
278	8/21/2024 13:34	0	0
279	8/21/2024 13:35	0	0
280	8/21/2024 13:36	0	0
281	8/21/2024 13:37	0	0
282	8/21/2024 13:38	0	0
283	8/21/2024 13:39	0	0
284	8/21/2024 13:40	0	0
285	8/21/2024 13:41	0	0
286	8/21/2024 13:42	0	0
287	8/21/2024 13:43	0	0
288	8/21/2024 13:44	0	0
289	8/21/2024 13:45	0	0
290	8/21/2024 13:46	0	0
291	8/21/2024 13:47	0	0
292	8/21/2024 13:48	0	0
293	8/21/2024 13:49	0	0
294	8/21/2024 13:50	0	0
295	8/21/2024 13:51	0	0
296	8/21/2024 13:52	0	0
297	8/21/2024 13:53	0	0
298	8/21/2024 13:54	0	0
299	8/21/2024 13:55	0	0
300	8/21/2024 13:56	0	0
301	8/21/2024 13:57	0	0
302	8/21/2024 13:58	0	0
303	8/21/2024 13:59	0	0
304	8/21/2024 14:00	0	0
305	8/21/2024 14:01	0	0
306	8/21/2024 14:02	0	0
307	8/21/2024 14:03	0	0
308	8/21/2024 14:04	0	0
309	8/21/2024 14:05	0	0
310	8/21/2024 14:06	0	0
311	8/21/2024 14:07	0	0

NYSDEC Site No. 314008

312	8/21/2024 14:08	0	0
313	8/21/2024 14:09	0	0
314	8/21/2024 14:10	0	0
315	8/21/2024 14:11	0	0
316	8/21/2024 14:12	0	0
317	8/21/2024 14:13	0	0
318	8/21/2024 14:14	0	0
319	8/21/2024 14:15	0	0
320	8/21/2024 14:16	0	0
321	8/21/2024 14:17	0	0
322	8/21/2024 14:18	0	0
323	8/21/2024 14:19	0	0
324	8/21/2024 14:20	0	0
325	8/21/2024 14:21	0	0
326	8/21/2024 14:22	0	0
327	8/21/2024 14:23	0	0
328	8/21/2024 14:24	0	0
329	8/21/2024 14:25	0	0
330	8/21/2024 14:26	0	0
331	8/21/2024 14:27	0	0
332	8/21/2024 14:28	0	0
333	8/21/2024 14:29	0	0
334	8/21/2024 14:30	0	0
335	8/21/2024 14:31	0	0
336	8/21/2024 14:32	0	0
337	8/21/2024 14:33	0	0
338	8/21/2024 14:34	0	0
339	8/21/2024 14:35	0	0
340	8/21/2024 14:36	0	0
341	8/21/2024 14:37	0	0
342	8/21/2024 14:38	0	0
343	8/21/2024 14:39	0	0
344	8/21/2024 14:40	0	0
345	8/21/2024 14:41	0	0
346	8/21/2024 14:42	0	0
347	8/21/2024 14:43	0	0
348	8/21/2024 14:44	0	0
349	8/21/2024 14:45	0	0
350	8/21/2024 14:46	0	0
351	8/21/2024 14:47	0	0
352	8/21/2024 14:48	0	0
353	8/21/2024 14:49	0	0
354	8/21/2024 14:50	0	0
355	8/21/2024 14:51	0	0

NYSDEC Site No. 314008

356	8/21/2024 14:52	0	0
357	8/21/2024 14:53	0	0
358	8/21/2024 14:54	0	0
359	8/21/2024 14:55	0	0
360	8/21/2024 14:56	0	0
361	8/21/2024 14:57	0	0
362	8/21/2024 14:58	0	0
363	8/21/2024 14:59	0	0
364	8/21/2024 15:00	0	0
365	8/21/2024 15:01	0	0
366	8/21/2024 15:02	0	0
367	8/21/2024 15:03	0	0
368	8/21/2024 15:04	0	0
369	8/21/2024 15:05	0	0
370	8/21/2024 15:06	0	0
371	8/21/2024 15:07	0	0
372	8/21/2024 15:08	0	0
373	8/21/2024 15:09	0	0
374	8/21/2024 15:10	0	0
375	8/21/2024 15:11	0	0
376	8/21/2024 15:12	0	0
377	8/21/2024 15:13	0	0
378	8/21/2024 15:14	0	0
379	8/21/2024 15:15	0	0
380	8/21/2024 15:16	0	0
381	8/21/2024 15:17	0	0
382	8/21/2024 15:18	0	0
383	8/21/2024 15:19	0	0
384	8/21/2024 15:20	0	0
385	8/21/2024 15:21	0	0
386	8/21/2024 15:22	0	0
387	8/21/2024 15:23	0	0
388	8/21/2024 15:24	0	0
389	8/21/2024 15:25	0	0
390	8/21/2024 15:26	0	0
391	8/21/2024 15:27	0	0
392	8/21/2024 15:28	0	0
393	8/21/2024 15:29	0	0
394	8/21/2024 15:30	0	0
395	8/21/2024 15:31	0	0
396	8/21/2024 15:32	0	0
397	8/21/2024 15:33	0	0
398	8/21/2024 15:34	0	0
399	8/21/2024 15:35	0	0

NYSDEC Site No. 314008

400	8/21/2024 15:36	0	0
401	8/21/2024 15:37	0	0
402	8/21/2024 15:38	0	0
403	8/21/2024 15:39	0	0
404	8/21/2024 15:40	0	0
405	8/21/2024 15:41	0	0
406	8/21/2024 15:42	0	0
407	8/21/2024 15:43	0	0
408	8/21/2024 15:44	0	0
409	8/21/2024 15:45	0	0
410	8/21/2024 15:46	0	0
411	8/21/2024 15:47	0	0
412	8/21/2024 15:48	0	0
413	8/21/2024 15:49	0	0
414	8/21/2024 15:50	0	0
415	8/21/2024 15:51	0	0
416	8/21/2024 15:52	0	0
417	8/21/2024 15:53	0	0
418	8/21/2024 15:54	0	0
419	8/21/2024 15:55	0	0
420	8/21/2024 15:56	0	0
421	8/21/2024 15:57	0	0
422	8/21/2024 15:58	0	0
423	8/21/2024 15:59	0	0
424	8/21/2024 16:00	0	0
425	8/21/2024 16:01	0	0
426	8/21/2024 16:02	0	0
427	8/21/2024 16:03	0	0
428	8/21/2024 16:04	0	0
429	8/21/2024 16:05	0	0
430	8/21/2024 16:06	0	0
431	8/21/2024 16:07	0	0
432	8/21/2024 16:08	0	0
433	8/21/2024 16:09	0	0
434	8/21/2024 16:10	0	0
435	8/21/2024 16:11	0	0
436	8/21/2024 16:12	0	0
437	8/21/2024 16:13	0	0
438	8/21/2024 16:14	0	0
439	8/21/2024 16:15	0	0
440	8/21/2024 16:16	0	0
441	8/21/2024 16:17	0	0
442	8/21/2024 16:18	0	0
443	8/21/2024 16:19	0	0

NYSDEC Site No. 314008

444	8/21/2024 16:20	0	0
445	8/21/2024 16:21	0	0
446	8/21/2024 16:22	0	0
447	8/21/2024 16:23	0	0
448	8/21/2024 16:24	0	0
449	8/21/2024 16:25	0	0
450	8/21/2024 16:26	0	0
451	8/21/2024 16:27	0	0
452	8/21/2024 16:28	0	0
453	8/21/2024 16:29	0	0
454	8/21/2024 16:30	0	0
455	8/21/2024 16:31	0	0
456	8/21/2024 16:32	0	0
457	8/21/2024 16:33	0	0
458	8/21/2024 16:34	0	0
459	8/21/2024 16:35	0	0
460	8/21/2024 16:36	0	0
461	8/21/2024 16:37	0	0
462	8/21/2024 16:38	0	0
463	8/21/2024 16:39	0	0
464	8/21/2024 16:40	0	0
465	8/21/2024 16:41	0	0
466	8/21/2024 16:42	0	0
467	8/21/2024 16:43	0	0
468	8/21/2024 16:44	0	0
469	8/21/2024 16:45	0	0
470	8/21/2024 16:46	0	0
471	8/21/2024 16:47	0	0
472	8/21/2024 16:48	0	0
473	8/21/2024 16:49	0	0
474	8/21/2024 16:50	0	0
475	8/21/2024 16:51	0	0
476	8/21/2024 16:52	0	0
477	8/21/2024 16:53	0	0
478	8/21/2024 16:54	0	0
479	8/21/2024 16:55	0	0
480	8/21/2024 16:56	0	0
481	8/21/2024 16:57	0	0
482	8/21/2024 16:58	0	0
483	8/21/2024 16:59	0	0
484	8/21/2024 17:00	0	0
485	8/21/2024 17:01	0	0
486	8/21/2024 17:02	0	0
487	8/21/2024 17:03	0	0

NYSDEC Site No. 314008

488	8/21/2024 17:04	0	0
489	8/21/2024 17:05	0	0
490	8/21/2024 17:06	0	0
491	8/21/2024 17:07	0	0
492	8/21/2024 17:08	0	0
493	8/21/2024 17:09	0	0
494	8/21/2024 17:10	0	0
495	8/21/2024 17:11	0	0
496	8/21/2024 17:12	0	0
497	8/21/2024 17:13	0	0
498	8/21/2024 17:14	0	0
499	8/21/2024 17:15	0	0
500	8/21/2024 17:16	0	0
501	8/21/2024 17:17	0	0
502	8/21/2024 17:18	0	0
503	8/21/2024 17:19	0	0
504	8/21/2024 17:20	0	0
505	8/21/2024 17:21	0	0
506	8/21/2024 17:22	0	0
507	8/21/2024 17:23	0	0
508	8/21/2024 17:24	0	0
509	8/21/2024 17:25	0	0
510	8/21/2024 17:26	0	0
511	8/21/2024 17:27	0	0
512	8/21/2024 17:28	0	0
513	8/21/2024 17:29	0	0
514	8/21/2024 17:30	0	0
515	8/21/2024 17:31	0	0
516	8/21/2024 17:32	0	0
517	8/21/2024 17:33	0	0
518	8/21/2024 17:34	0	0
519	8/21/2024 17:35	0	0

=====

24/08/22 08:11

Summary

Unit Name	MiniRAE 3000(PGM-7320)
Unit SN	592-904349
Unit Firmware Ver	V2.22A

Running Mode	Hygiene Mode
Datalog Mode	Auto
Diagnostic Mode	No

Site ID	1
User ID	1

Sensor	PID(ppm)
Sensor SN	S023030247C5
Measure Type	Min; Avg; Max; Real
Span	100
Span 2	1000
Low Alarm	50
High Alarm	100
Over Alarm	15000
STEL Alarm	25
TWA Alarm	10
Measurement Gas	Isobutylene
Calibration Time	8/13/2024 10:27
Peak	0
Min	0
Average	0

Index	Date/Time	PID(ppm) (Min)	PID(ppm) (Avg)	PID(ppm) (Max)	PID(ppm) (Real)
1	8/22/2024 8:12	0	0	0	0
2	8/22/2024 8:13	0	0	0	0
3	8/22/2024 8:14	0	0	0	0
4	8/22/2024 8:15	0	0	0	0
5	8/22/2024 8:16	0	0	0	0
6	8/22/2024 8:17	0	0	0	0
7	8/22/2024 8:18	0	0	0	0
8	8/22/2024 8:19	0	0	0	0
9	8/22/2024 8:20	0	0	0	0
10	8/22/2024 8:21	0	0	0	0
11	8/22/2024 8:22	0	0	0	0
12	8/22/2024 8:23	0	0	0	0
13	8/22/2024 8:24	0	0	0	0
14	8/22/2024 8:25	0	0	0	0

NYSDEC Site No. 314008

15	8/22/2024 8:26	0	0	0	0
16	8/22/2024 8:27	0	0	0	0
17	8/22/2024 8:28	0	0	0	0
18	8/22/2024 8:29	0	0	0	0
19	8/22/2024 8:30	0	0	0	0
20	8/22/2024 8:31	0	0	0	0
21	8/22/2024 8:32	0	0	0	0
22	8/22/2024 8:33	0	0	0	0
23	8/22/2024 8:34	0	0	0	0
24	8/22/2024 8:35	0	0	0	0
25	8/22/2024 8:36	0	0	0	0
26	8/22/2024 8:37	0	0	0	0
27	8/22/2024 8:38	0	0	0	0
28	8/22/2024 8:39	0	0	0	0
29	8/22/2024 8:40	0	0	0	0
30	8/22/2024 8:41	0	0	0	0
31	8/22/2024 8:42	0	0	0	0
32	8/22/2024 8:43	0	0	0	0
33	8/22/2024 8:44	0	0	0	0
34	8/22/2024 8:45	0	0	0	0
35	8/22/2024 8:46	0	0	0	0
36	8/22/2024 8:47	0	0	0	0
37	8/22/2024 8:48	0	0	0	0
38	8/22/2024 8:49	0	0	0	0
39	8/22/2024 8:50	0	0	0	0
40	8/22/2024 8:51	0	0	0	0
41	8/22/2024 8:52	0	0	0	0
42	8/22/2024 8:53	0	0	0	0
43	8/22/2024 8:54	0	0	0	0
44	8/22/2024 8:55	0	0	0	0
45	8/22/2024 8:56	0	0	0	0
46	8/22/2024 8:57	0	0	0	0
47	8/22/2024 8:58	0	0	0	0
48	8/22/2024 8:59	0	0	0	0
49	8/22/2024 9:00	0	0	0	0
50	8/22/2024 9:01	0	0	0	0
51	8/22/2024 9:02	0	0	0	0
52	8/22/2024 9:03	0	0	0	0
53	8/22/2024 9:04	0	0	0	0
54	8/22/2024 9:05	0	0	0	0
55	8/22/2024 9:06	0	0	0	0
56	8/22/2024 9:07	0	0	0	0
57	8/22/2024 9:08	0	0	0	0
58	8/22/2024 9:09	0	0	0	0

59	8/22/2024 9:10	0	0	0	0
60	8/22/2024 9:11	0	0	0	0
61	8/22/2024 9:12	0	0	0	0
62	8/22/2024 9:13	0	0	0	0
63	8/22/2024 9:14	0	0	0	0
64	8/22/2024 9:15	0	0	0	0
65	8/22/2024 9:16	0	0	0	0
66	8/22/2024 9:17	0	0	0	0
67	8/22/2024 9:18	0	0	0	0
68	8/22/2024 9:19	0	0	0	0
69	8/22/2024 9:20	0	0	0	0
70	8/22/2024 9:21	0	0	0	0
71	8/22/2024 9:22	0	0	0	0
72	8/22/2024 9:23	0	0	0	0
73	8/22/2024 9:24	0	0	0	0
74	8/22/2024 9:25	0	0	0	0
75	8/22/2024 9:26	0	0	0	0
76	8/22/2024 9:27	0	0	0	0
77	8/22/2024 9:28	0	0	0	0
78	8/22/2024 9:29	0	0	0	0
79	8/22/2024 9:30	0	0	0	0
80	8/22/2024 9:31	0	0	0	0
81	8/22/2024 9:32	0	0	0	0
82	8/22/2024 9:33	0	0	0	0
83	8/22/2024 9:34	0	0	0	0
84	8/22/2024 9:35	0	0	0	0
85	8/22/2024 9:36	0	0	0	0
86	8/22/2024 9:37	0	0	0	0
87	8/22/2024 9:38	0	0	0	0
88	8/22/2024 9:39	0	0	0	0
89	8/22/2024 9:40	0	0	0	0
90	8/22/2024 9:41	0	0	0	0
91	8/22/2024 9:42	0	0	0	0
92	8/22/2024 9:43	0	0	0	0
93	8/22/2024 9:44	0	0	0	0
94	8/22/2024 9:45	0	0	0	0
95	8/22/2024 9:46	0	0	0	0
96	8/22/2024 9:47	0	0	0	0
97	8/22/2024 9:48	0	0	0	0
98	8/22/2024 9:49	0	0	0	0
99	8/22/2024 9:50	0	0	0	0
100	8/22/2024 9:51	0	0	0	0
101	8/22/2024 9:52	0	0	0	0
102	8/22/2024 9:53	0	0	0	0

103	8/22/2024 9:54	0	0	0	0
104	8/22/2024 9:55	0	0	0	0
105	8/22/2024 9:56	0	0	0	0
106	8/22/2024 9:57	0	0	0	0
107	8/22/2024 9:58	0	0	0	0
108	8/22/2024 9:59	0	0	0	0
109	8/22/2024 10:00	0	0	0	0
110	8/22/2024 10:01	0	0	0	0
111	8/22/2024 10:02	0	0	0	0
112	8/22/2024 10:03	0	0	0	0
113	8/22/2024 10:04	0	0	0	0
114	8/22/2024 10:05	0	0	0	0
115	8/22/2024 10:06	0	0	0	0
116	8/22/2024 10:07	0	0	0	0
117	8/22/2024 10:08	0	0	0	0
118	8/22/2024 10:09	0	0	0	0
119	8/22/2024 10:10	0	0	0	0
120	8/22/2024 10:11	0	0	0	0
121	8/22/2024 10:12	0	0	0	0
122	8/22/2024 10:13	0	0	0	0
123	8/22/2024 10:14	0	0	0	0
124	8/22/2024 10:15	0	0	0	0
125	8/22/2024 10:16	0	0	0	0
126	8/22/2024 10:17	0	0	0	0
127	8/22/2024 10:18	0	0	0	0
128	8/22/2024 10:19	0	0	0	0
129	8/22/2024 10:20	0	0	0	0
130	8/22/2024 10:21	0	0	0	0
131	8/22/2024 10:22	0	0	0	0
132	8/22/2024 10:23	0	0	0	0
133	8/22/2024 10:24	0	0	0	0
134	8/22/2024 10:25	0	0	0	0
135	8/22/2024 10:26	0	0	0	0
136	8/22/2024 10:27	0	0	0	0
137	8/22/2024 10:28	0	0	0	0
138	8/22/2024 10:29	0	0	0	0
139	8/22/2024 10:30	0	0	0	0
140	8/22/2024 10:31	0	0	0	0
141	8/22/2024 10:32	0	0	0	0
142	8/22/2024 10:33	0	0	0	0
143	8/22/2024 10:34	0	0	0	0
144	8/22/2024 10:35	0	0	0	0
145	8/22/2024 10:36	0	0	0	0
146	8/22/2024 10:37	0	0	0	0

147	8/22/2024 10:38	0	0	0	0
148	8/22/2024 10:39	0	0	0	0
149	8/22/2024 10:40	0	0	0	0
150	8/22/2024 10:41	0	0	0	0
151	8/22/2024 10:42	0	0	0	0
152	8/22/2024 10:43	0	0	0	0
153	8/22/2024 10:44	0	0	0	0
154	8/22/2024 10:45	0	0	0	0
155	8/22/2024 10:46	0	0	0	0
156	8/22/2024 10:47	0	0	0	0
157	8/22/2024 10:48	0	0	0	0
158	8/22/2024 10:49	0	0	0	0
159	8/22/2024 10:50	0	0	0	0
160	8/22/2024 10:51	0	0	0	0
161	8/22/2024 10:52	0	0	0	0
162	8/22/2024 10:53	0	0	0	0
163	8/22/2024 10:54	0	0	0	0
164	8/22/2024 10:55	0	0	0	0
165	8/22/2024 10:56	0	0	0	0
166	8/22/2024 10:57	0	0	0	0
167	8/22/2024 10:58	0	0	0	0
168	8/22/2024 10:59	0	0	0	0
169	8/22/2024 11:00	0	0	0	0
170	8/22/2024 11:01	0	0	0	0
171	8/22/2024 11:02	0	0	0	0
172	8/22/2024 11:03	0	0	0	0
173	8/22/2024 11:04	0	0	0	0
174	8/22/2024 11:05	0	0	0	0
175	8/22/2024 11:06	0	0	0	0
176	8/22/2024 11:07	0	0	0	0
177	8/22/2024 11:08	0	0	0	0
178	8/22/2024 11:09	0	0	0	0
179	8/22/2024 11:10	0	0	0	0
180	8/22/2024 11:11	0	0	0	0
181	8/22/2024 11:12	0	0	0	0
182	8/22/2024 11:13	0	0	0	0
183	8/22/2024 11:14	0	0	0	0
184	8/22/2024 11:15	0	0	0	0
185	8/22/2024 11:16	0	0	0	0
186	8/22/2024 11:17	0	0	0	0
187	8/22/2024 11:18	0	0	0	0
188	8/22/2024 11:19	0	0	0	0
189	8/22/2024 11:20	0	0	0	0
190	8/22/2024 11:21	0	0	0	0

NYSDEC Site No. 314008

191	8/22/2024 11:22	0	0	0	0
192	8/22/2024 11:23	0	0	0	0
193	8/22/2024 11:24	0	0	0	0
194	8/22/2024 11:25	0	0	0	0
195	8/22/2024 11:26	0	0	0	0
196	8/22/2024 11:27	0	0	0	0
197	8/22/2024 11:28	0	0	0	0
198	8/22/2024 11:29	0	0	0	0
199	8/22/2024 11:30	0	0	0	0
200	8/22/2024 11:31	0	0	0	0
201	8/22/2024 11:32	0	0	0	0
202	8/22/2024 11:33	0	0	0	0
203	8/22/2024 11:34	0	0	0	0
204	8/22/2024 11:35	0	0	0	0
205	8/22/2024 11:36	0	0	0	0
206	8/22/2024 11:37	0	0	0	0
207	8/22/2024 11:38	0	0	0	0
208	8/22/2024 11:39	0	0	0	0
209	8/22/2024 11:40	0	0	0	0
210	8/22/2024 11:41	0	0	0	0
211	8/22/2024 11:42	0	0	0	0
212	8/22/2024 11:43	0	0	0	0
213	8/22/2024 11:44	0	0	0	0
214	8/22/2024 11:45	0	0	0	0
215	8/22/2024 11:46	0	0	0	0
216	8/22/2024 11:47	0	0	0	0
217	8/22/2024 11:48	0	0	0	0
218	8/22/2024 11:49	0	0	0	0
219	8/22/2024 11:50	0	0	0	0
220	8/22/2024 11:51	0	0	0	0
221	8/22/2024 11:52	0	0	0	0
222	8/22/2024 11:53	0	0	0	0
223	8/22/2024 11:54	0	0	0	0
224	8/22/2024 11:55	0	0	0	0
225	8/22/2024 11:56	0	0	0	0
226	8/22/2024 11:57	0	0	0	0
227	8/22/2024 11:58	0	0	0	0
228	8/22/2024 11:59	0	0	0	0
229	8/22/2024 12:00	0	0	0	0
230	8/22/2024 12:01	0	0	0	0
231	8/22/2024 12:02	0	0	0	0
232	8/22/2024 12:03	0	0	0	0
233	8/22/2024 12:04	0	0	0	0
234	8/22/2024 12:05	0	0	0	0

NYSDEC Site No. 314008

235	8/22/2024 12:06	0	0	0	0
236	8/22/2024 12:07	0	0	0	0
237	8/22/2024 12:08	0	0	0	0
238	8/22/2024 12:09	0	0	0	0
239	8/22/2024 12:10	0	0	0	0
240	8/22/2024 12:11	0	0	0	0
241	8/22/2024 12:12	0	0	0	0
242	8/22/2024 12:13	0	0	0	0
243	8/22/2024 12:14	0	0	0	0
244	8/22/2024 12:15	0	0	0	0
245	8/22/2024 12:16	0	0	0	0
246	8/22/2024 12:17	0	0	0	0
247	8/22/2024 12:18	0	0	0	0
248	8/22/2024 12:19	0	0	0	0
249	8/22/2024 12:20	0	0	0	0
250	8/22/2024 12:21	0	0	0	0
251	8/22/2024 12:22	0	0	0	0
252	8/22/2024 12:23	0	0	0	0
253	8/22/2024 12:24	0	0	0	0
254	8/22/2024 12:25	0	0	0	0
255	8/22/2024 12:26	0	0	0	0
256	8/22/2024 12:27	0	0	0	0
257	8/22/2024 12:28	0	0	0	0
258	8/22/2024 12:29	0	0	0	0
259	8/22/2024 12:30	0	0	0	0
260	8/22/2024 12:31	0	0	0	0
261	8/22/2024 12:32	0	0	0	0
262	8/22/2024 12:33	0	0	0	0
263	8/22/2024 12:34	0	0	0	0
264	8/22/2024 12:35	0	0	0	0
265	8/22/2024 12:36	0	0	0	0
266	8/22/2024 12:37	0	0	0	0
267	8/22/2024 12:38	0	0	0	0
268	8/22/2024 12:39	0	0	0	0
269	8/22/2024 12:40	0	0	0	0
270	8/22/2024 12:41	0	0	0	0
271	8/22/2024 12:42	0	0	0	0
272	8/22/2024 12:43	0	0	0	0
273	8/22/2024 12:44	0	0	0	0
274	8/22/2024 12:45	0	0	0	0
275	8/22/2024 12:46	0	0	0	0
276	8/22/2024 12:47	0	0	0	0
277	8/22/2024 12:48	0	0	0	0
278	8/22/2024 12:49	0	0	0	0

NYSDEC Site No. 314008

279	8/22/2024 12:50	0	0	0	0
280	8/22/2024 12:51	0	0	0	0
281	8/22/2024 12:52	0	0	0	0
282	8/22/2024 12:53	0	0	0	0
283	8/22/2024 12:54	0	0	0	0
284	8/22/2024 12:55	0	0	0	0
285	8/22/2024 12:56	0	0	0	0
286	8/22/2024 12:57	0	0	0	0
287	8/22/2024 12:58	0	0	0	0
288	8/22/2024 12:59	0	0	0	0
289	8/22/2024 13:00	0	0	0	0
290	8/22/2024 13:01	0	0	0	0
291	8/22/2024 13:02	0	0	0	0
292	8/22/2024 13:03	0	0	0	0
293	8/22/2024 13:04	0	0	0	0
294	8/22/2024 13:05	0	0	0	0
295	8/22/2024 13:06	0	0	0	0
296	8/22/2024 13:07	0	0	0	0
297	8/22/2024 13:08	0	0	0	0
298	8/22/2024 13:09	0	0	0	0
299	8/22/2024 13:10	0	0	0	0
300	8/22/2024 13:11	0	0	0	0
301	8/22/2024 13:12	0	0	0	0
302	8/22/2024 13:13	0	0	0	0
303	8/22/2024 13:14	0	0	0	0
304	8/22/2024 13:15	0	0	0	0
305	8/22/2024 13:16	0	0	0	0
306	8/22/2024 13:17	0	0	0	0
307	8/22/2024 13:18	0	0	0	0
308	8/22/2024 13:19	0	0	0	0
309	8/22/2024 13:20	0	0	0	0
310	8/22/2024 13:21	0	0	0	0
311	8/22/2024 13:22	0	0	0	0
312	8/22/2024 13:23	0	0	0	0
313	8/22/2024 13:24	0	0	0	0
314	8/22/2024 13:25	0	0	0	0
315	8/22/2024 13:26	0	0	0	0
316	8/22/2024 13:27	0	0	0	0
317	8/22/2024 13:28	0	0	0	0
318	8/22/2024 13:29	0	0	0	0
319	8/22/2024 13:30	0	0	0	0
320	8/22/2024 13:31	0	0	0	0
321	8/22/2024 13:32	0	0	0	0
322	8/22/2024 13:33	0	0	0	0

NYSDEC Site No. 314008

323	8/22/2024 13:34	0	0	0	0
324	8/22/2024 13:35	0	0	0	0
325	8/22/2024 13:36	0	0	0	0
326	8/22/2024 13:37	0	0	0	0
327	8/22/2024 13:38	0	0	0	0
328	8/22/2024 13:39	0	0	0	0
329	8/22/2024 13:40	0	0	0	0
330	8/22/2024 13:41	0	0	0	0
331	8/22/2024 13:42	0	0	0	0
332	8/22/2024 13:43	0	0	0	0
333	8/22/2024 13:44	0	0	0	0
334	8/22/2024 13:45	0	0	0	0
335	8/22/2024 13:46	0	0	0	0
336	8/22/2024 13:47	0	0	0	0
337	8/22/2024 13:48	0	0	0	0
338	8/22/2024 13:49	0	0	0	0
339	8/22/2024 13:50	0	0	0	0
340	8/22/2024 13:51	0	0	0	0
341	8/22/2024 13:52	0	0	0	0
342	8/22/2024 13:53	0	0	0	0
343	8/22/2024 13:54	0	0	0	0
344	8/22/2024 13:55	0	0	0	0
345	8/22/2024 13:56	0	0	0	0
346	8/22/2024 13:57	0	0	0	0
347	8/22/2024 13:58	0	0	0	0
348	8/22/2024 13:59	0	0	0	0
349	8/22/2024 14:00	0	0	0	0
350	8/22/2024 14:01	0	0	0	0
351	8/22/2024 14:02	0	0	0	0
352	8/22/2024 14:03	0	0	0	0
353	8/22/2024 14:04	0	0	0	0
354	8/22/2024 14:05	0	0	0	0
355	8/22/2024 14:06	0	0	0	0
356	8/22/2024 14:07	0	0	0	0
357	8/22/2024 14:08	0	0	0	0
358	8/22/2024 14:09	0	0	0	0
359	8/22/2024 14:10	0	0	0	0
360	8/22/2024 14:11	0	0	0	0
361	8/22/2024 14:12	0	0	0	0
362	8/22/2024 14:13	0	0	0	0
363	8/22/2024 14:14	0	0	0	0
364	8/22/2024 14:15	0	0	0	0
365	8/22/2024 14:16	0	0	0	0
366	8/22/2024 14:17	0	0	0	0

NYSDEC Site No. 314008

367	8/22/2024 14:18	0	0	0	0
368	8/22/2024 14:19	0	0	0	0
369	8/22/2024 14:20	0	0	0	0
370	8/22/2024 14:21	0	0	0	0
371	8/22/2024 14:22	0	0	0	0
372	8/22/2024 14:23	0	0	0	0
373	8/22/2024 14:24	0	0	0	0
374	8/22/2024 14:25	0	0	0	0
375	8/22/2024 14:26	0	0	0	0
376	8/22/2024 14:27	0	0	0	0
377	8/22/2024 14:28	0	0	0	0
378	8/22/2024 14:29	0	0	0	0
379	8/22/2024 14:30	0	0	0	0
380	8/22/2024 14:31	0	0	0	0
381	8/22/2024 14:32	0	0	0	0
382	8/22/2024 14:33	0	0	0	0
383	8/22/2024 14:34	0	0	0	0
384	8/22/2024 14:35	0	0	0	0
385	8/22/2024 14:36	0	0	0	0
386	8/22/2024 14:37	0	0	0	0
387	8/22/2024 14:38	0	0	0	0
388	8/22/2024 14:39	0	0	0	0
389	8/22/2024 14:40	0	0	0	0
390	8/22/2024 14:41	0	0	0	0
391	8/22/2024 14:42	0	0	0	0
392	8/22/2024 14:43	0	0	0	0
393	8/22/2024 14:44	0	0	0	0
394	8/22/2024 14:45	0	0	0	0
395	8/22/2024 14:46	0	0	0	0
396	8/22/2024 14:47	0	0	0	0
397	8/22/2024 14:48	0	0	0	0
398	8/22/2024 14:49	0	0	0	0
399	8/22/2024 14:50	0	0	0	0
400	8/22/2024 14:51	0	0	0	0
401	8/22/2024 14:52	0	0	0	0
402	8/22/2024 14:53	0	0	0	0
403	8/22/2024 14:54	0	0	0	0
404	8/22/2024 14:55	0	0	0	0
405	8/22/2024 14:56	0	0	0	0
406	8/22/2024 14:57	0	0	0	0
407	8/22/2024 14:58	0	0	0	0
408	8/22/2024 14:59	0	0	0	0
409	8/22/2024 15:00	0	0	0	0
410	8/22/2024 15:01	0	0	0	0

NYSDEC Site No. 314008

411	8/22/2024 15:02	0	0	0	0
412	8/22/2024 15:03	0	0	0	0
413	8/22/2024 15:04	0	0	0	0
414	8/22/2024 15:05	0	0	0	0
415	8/22/2024 15:06	0	0	0	0
416	8/22/2024 15:07	0	0	0	0
417	8/22/2024 15:08	0	0	0	0
418	8/22/2024 15:09	0	0	0	0
419	8/22/2024 15:10	0	0	0	0
420	8/22/2024 15:11	0	0	0	0
421	8/22/2024 15:12	0	0	0	0
422	8/22/2024 15:13	0	0	0	0
423	8/22/2024 15:14	0	0	0	0
424	8/22/2024 15:15	0	0	0	0
425	8/22/2024 15:16	0	0	0	0
426	8/22/2024 15:17	0	0	0	0
427	8/22/2024 15:18	0	0	0	0
428	8/22/2024 15:19	0	0	0	0
429	8/22/2024 15:20	0	0	0	0
430	8/22/2024 15:21	0	0	0	0
431	8/22/2024 15:22	0	0	0	0
432	8/22/2024 15:23	0	0	0	0
433	8/22/2024 15:24	0	0	0	0
434	8/22/2024 15:25	0	0	0	0
435	8/22/2024 15:26	0	0	0	0
436	8/22/2024 15:27	0	0	0	0
437	8/22/2024 15:28	0	0	0	0
438	8/22/2024 15:29	0	0	0	0
439	8/22/2024 15:30	0	0	0	0
440	8/22/2024 15:31	0	0	0	0
441	8/22/2024 15:32	0	0	0	0
442	8/22/2024 15:33	0	0	0	0
443	8/22/2024 15:34	0	0	0	0
444	8/22/2024 15:35	0	0	0	0
445	8/22/2024 15:36	0	0	0	0
446	8/22/2024 15:37	0	0	0	0
447	8/22/2024 15:38	0	0	0	0
448	8/22/2024 15:39	0	0	0	0
449	8/22/2024 15:40	0	0	0	0
450	8/22/2024 15:41	0	0	0	0
451	8/22/2024 15:42	0	0	0	0
452	8/22/2024 15:43	0	0	0	0
453	8/22/2024 15:44	0	0	0	0
454	8/22/2024 15:45	0	0	0	0

NYSDEC Site No. 314008

455	8/22/2024 15:46	0	0	0	0
456	8/22/2024 15:47	0	0	0	0
457	8/22/2024 15:48	0	0	0	0
458	8/22/2024 15:49	0	0	0	0
459	8/22/2024 15:50	0	0	0	0
460	8/22/2024 15:51	0	0	0	0
461	8/22/2024 15:52	0	0	0	0
462	8/22/2024 15:53	0	0	0	0
463	8/22/2024 15:54	0	0	0	0
464	8/22/2024 15:55	0	0	0	0
465	8/22/2024 15:56	0	0	0	0
466	8/22/2024 15:57	0	0	0	0
467	8/22/2024 15:58	0	0	0	0
468	8/22/2024 15:59	0	0	0	0
469	8/22/2024 16:00	0	0	0	0
470	8/22/2024 16:01	0	0	0	0
471	8/22/2024 16:02	0	0	0	0
472	8/22/2024 16:03	0	0	0	0
473	8/22/2024 16:04	0	0	0	0
474	8/22/2024 16:05	0	0	0	0
475	8/22/2024 16:06	0	0	0	0
476	8/22/2024 16:07	0	0	0	0
477	8/22/2024 16:08	0	0	0	0
478	8/22/2024 16:09	0	0	0	0
479	8/22/2024 16:10	0	0	0	0
480	8/22/2024 16:11	0	0	0	0
481	8/22/2024 16:12	0	0	0	0
482	8/22/2024 16:13	0	0	0	0
483	8/22/2024 16:14	0	0	0	0
484	8/22/2024 16:15	0	0	0	0
485	8/22/2024 16:16	0	0	0	0
486	8/22/2024 16:17	0	0	0	0
487	8/22/2024 16:18	0	0	0	0
488	8/22/2024 16:19	0	0	0	0
489	8/22/2024 16:20	0	0	0	0
490	8/22/2024 16:21	0	0	0	0
491	8/22/2024 16:22	0	0	0	0
492	8/22/2024 16:23	0	0	0	0
493	8/22/2024 16:24	0	0	0	0
494	8/22/2024 16:25	0	0	0	0
495	8/22/2024 16:26	0	0	0	0
496	8/22/2024 16:27	0	0	0	0
497	8/22/2024 16:28	0	0	0	0
498	8/22/2024 16:29	0	0	0	0

499	8/22/2024 16:30	0	0	0	0
500	8/22/2024 16:31	0	0	0	0
501	8/22/2024 16:32	0	0	0	0
502	8/22/2024 16:33	0	0	0	0
503	8/22/2024 16:34	0	0	0	0
504	8/22/2024 16:35	0	0	0	0
505	8/22/2024 16:36	0	0	0	0
506	8/22/2024 16:37	0	0	0	0
507	8/22/2024 16:38	0	0	0	0
508	8/22/2024 16:39	0	0	0	0
509	8/22/2024 16:40	0	0	0	0
510	8/22/2024 16:41	0	0	0	0
511	8/22/2024 16:42	0	0	0	0
512	8/22/2024 16:43	0	0	0	0
513	8/22/2024 16:44	0	0	0	0
514	8/22/2024 16:45	0	0	0	0
515	8/22/2024 16:46	0	0	0	0
516	8/22/2024 16:47	0	0	0	0
517	8/22/2024 16:48	0	0	0	0
518	8/22/2024 16:49	0	0	0	0
519	8/22/2024 16:50	0	0	0	0
520	8/22/2024 16:51	0	0	0	0
521	8/22/2024 16:52	0	0	0	0
522	8/22/2024 16:53	0	0	0	0
523	8/22/2024 16:54	0	0	0	0
524	8/22/2024 16:55	0	0	0	0
525	8/22/2024 16:56	0	0	0	0
526	8/22/2024 16:57	0	0	0	0
527	8/22/2024 16:58	0	0	0	0
528	8/22/2024 16:59	0	0	0	0
529	8/22/2024 17:00	0	0	0	0
530	8/22/2024 17:01	0	0	0	0
531	8/22/2024 17:02	0	0	0	0
532	8/22/2024 17:03	0	0	0	0
533	8/22/2024 17:04	0	0	0	0
534	8/22/2024 17:05	0	0	0	0
535	8/22/2024 17:06	0	0	0	0
536	8/22/2024 17:07	0	0	0	0
537	8/22/2024 17:08	0	0	0	0
538	8/22/2024 17:09	0	0	0	0
539	8/22/2024 17:10	0	0	0	0
540	8/22/2024 17:11	0	0	0	0
541	8/22/2024 17:12	0	0	0	0
542	8/22/2024 17:13	0	0	0	0

NYSDEC Site No. 314008

543	8/22/2024 17:14	0	0	0	0
544	8/22/2024 17:15	0	0	0	0
545	8/22/2024 17:16	0	0	0	0
546	8/22/2024 17:17	0	0	0	0
547	8/22/2024 17:18	0	0	0	0
548	8/22/2024 17:19	0	0	0	0
549	8/22/2024 17:20	0	0	0	0
550	8/22/2024 17:21	0	0	0	0
551	8/22/2024 17:22	0	0	0	0
552	8/22/2024 17:23	0	0	0	0
553	8/22/2024 17:24	0	0	0	0
554	8/22/2024 17:25	0	0	0	0
555	8/22/2024 17:26	0	0	0	0
556	8/22/2024 17:27	0	0	0	0
557	8/22/2024 17:28	0	0	0	0
558	8/22/2024 17:29	0	0	0	0
559	8/22/2024 17:30	0	0	0	0
560	8/22/2024 17:31	0	0	0	0
561	8/22/2024 17:32	0	0	0	0
562	8/22/2024 17:33	0	0	0	0
563	8/22/2024 17:34	0	0	0	0
564	8/22/2024 17:35	0	0	0	0
565	8/22/2024 17:36	0	0	0	0
566	8/22/2024 17:37	0	0	0	0
567	8/22/2024 17:38	0	0	0	0
568	8/22/2024 17:39	0	0	0	0
569	8/22/2024 17:40	0	0	0	0
570	8/22/2024 17:41	0	0	0	0
571	8/22/2024 17:42	0	0	0	0
572	8/22/2024 17:43	0	0	0	0
573	8/22/2024 17:44	0	0	0	0
574	8/22/2024 17:45	0	0	0	0
575	8/22/2024 17:46	0	0	0	0
576	8/22/2024 17:47	0	0	0	0
577	8/22/2024 17:48	0	0	0	0
578	8/22/2024 17:49	0	0	0	0
579	8/22/2024 17:50	0	0	0	0
580	8/22/2024 17:51	0	0	0	0
581	8/22/2024 17:52	0	0	0	0
582	8/22/2024 17:53	0	0	0	0
Peak		0	0	0	0
Min		0	0	0	0
Average		0	0	0	0

TWA/STEL

		PID(ppm)	PID(ppm)
Index	Date/Time	(TWA)	(STEL)
1	8/22/2024 8:12	0	---
2	8/22/2024 8:13	0	---
3	8/22/2024 8:14	0	---
4	8/22/2024 8:15	0	---
5	8/22/2024 8:16	0	---
6	8/22/2024 8:17	0	---
7	8/22/2024 8:18	0	---
8	8/22/2024 8:19	0	---
9	8/22/2024 8:20	0	---
10	8/22/2024 8:21	0	---
11	8/22/2024 8:22	0	---
12	8/22/2024 8:23	0	---
13	8/22/2024 8:24	0	---
14	8/22/2024 8:25	0	---
15	8/22/2024 8:26	0	0
16	8/22/2024 8:27	0	0
17	8/22/2024 8:28	0	0
18	8/22/2024 8:29	0	0
19	8/22/2024 8:30	0	0
20	8/22/2024 8:31	0	0
21	8/22/2024 8:32	0	0
22	8/22/2024 8:33	0	0
23	8/22/2024 8:34	0	0
24	8/22/2024 8:35	0	0
25	8/22/2024 8:36	0	0
26	8/22/2024 8:37	0	0
27	8/22/2024 8:38	0	0
28	8/22/2024 8:39	0	0
29	8/22/2024 8:40	0	0
30	8/22/2024 8:41	0	0
31	8/22/2024 8:42	0	0
32	8/22/2024 8:43	0	0
33	8/22/2024 8:44	0	0
34	8/22/2024 8:45	0	0
35	8/22/2024 8:46	0	0
36	8/22/2024 8:47	0	0
37	8/22/2024 8:48	0	0
38	8/22/2024 8:49	0	0
39	8/22/2024 8:50	0	0
40	8/22/2024 8:51	0	0

NYSDEC Site No. 314008

41	8/22/2024 8:52	0	0
42	8/22/2024 8:53	0	0
43	8/22/2024 8:54	0	0
44	8/22/2024 8:55	0	0
45	8/22/2024 8:56	0	0
46	8/22/2024 8:57	0	0
47	8/22/2024 8:58	0	0
48	8/22/2024 8:59	0	0
49	8/22/2024 9:00	0	0
50	8/22/2024 9:01	0	0
51	8/22/2024 9:02	0	0
52	8/22/2024 9:03	0	0
53	8/22/2024 9:04	0	0
54	8/22/2024 9:05	0	0
55	8/22/2024 9:06	0	0
56	8/22/2024 9:07	0	0
57	8/22/2024 9:08	0	0
58	8/22/2024 9:09	0	0
59	8/22/2024 9:10	0	0
60	8/22/2024 9:11	0	0
61	8/22/2024 9:12	0	0
62	8/22/2024 9:13	0	0
63	8/22/2024 9:14	0	0
64	8/22/2024 9:15	0	0
65	8/22/2024 9:16	0	0
66	8/22/2024 9:17	0	0
67	8/22/2024 9:18	0	0
68	8/22/2024 9:19	0	0
69	8/22/2024 9:20	0	0
70	8/22/2024 9:21	0	0
71	8/22/2024 9:22	0	0
72	8/22/2024 9:23	0	0
73	8/22/2024 9:24	0	0
74	8/22/2024 9:25	0	0
75	8/22/2024 9:26	0	0
76	8/22/2024 9:27	0	0
77	8/22/2024 9:28	0	0
78	8/22/2024 9:29	0	0
79	8/22/2024 9:30	0	0
80	8/22/2024 9:31	0	0
81	8/22/2024 9:32	0	0
82	8/22/2024 9:33	0	0
83	8/22/2024 9:34	0	0
84	8/22/2024 9:35	0	0

NYSDEC Site No. 314008

85	8/22/2024 9:36	0	0
86	8/22/2024 9:37	0	0
87	8/22/2024 9:38	0	0
88	8/22/2024 9:39	0	0
89	8/22/2024 9:40	0	0
90	8/22/2024 9:41	0	0
91	8/22/2024 9:42	0	0
92	8/22/2024 9:43	0	0
93	8/22/2024 9:44	0	0
94	8/22/2024 9:45	0	0
95	8/22/2024 9:46	0	0
96	8/22/2024 9:47	0	0
97	8/22/2024 9:48	0	0
98	8/22/2024 9:49	0	0
99	8/22/2024 9:50	0	0
100	8/22/2024 9:51	0	0
101	8/22/2024 9:52	0	0
102	8/22/2024 9:53	0	0
103	8/22/2024 9:54	0	0
104	8/22/2024 9:55	0	0
105	8/22/2024 9:56	0	0
106	8/22/2024 9:57	0	0
107	8/22/2024 9:58	0	0
108	8/22/2024 9:59	0	0
109	8/22/2024 10:00	0	0
110	8/22/2024 10:01	0	0
111	8/22/2024 10:02	0	0
112	8/22/2024 10:03	0	0
113	8/22/2024 10:04	0	0
114	8/22/2024 10:05	0	0
115	8/22/2024 10:06	0	0
116	8/22/2024 10:07	0	0
117	8/22/2024 10:08	0	0
118	8/22/2024 10:09	0	0
119	8/22/2024 10:10	0	0
120	8/22/2024 10:11	0	0
121	8/22/2024 10:12	0	0
122	8/22/2024 10:13	0	0
123	8/22/2024 10:14	0	0
124	8/22/2024 10:15	0	0
125	8/22/2024 10:16	0	0
126	8/22/2024 10:17	0	0
127	8/22/2024 10:18	0	0
128	8/22/2024 10:19	0	0

NYSDEC Site No. 314008

129	8/22/2024 10:20	0	0
130	8/22/2024 10:21	0	0
131	8/22/2024 10:22	0	0
132	8/22/2024 10:23	0	0
133	8/22/2024 10:24	0	0
134	8/22/2024 10:25	0	0
135	8/22/2024 10:26	0	0
136	8/22/2024 10:27	0	0
137	8/22/2024 10:28	0	0
138	8/22/2024 10:29	0	0
139	8/22/2024 10:30	0	0
140	8/22/2024 10:31	0	0
141	8/22/2024 10:32	0	0
142	8/22/2024 10:33	0	0
143	8/22/2024 10:34	0	0
144	8/22/2024 10:35	0	0
145	8/22/2024 10:36	0	0
146	8/22/2024 10:37	0	0
147	8/22/2024 10:38	0	0
148	8/22/2024 10:39	0	0
149	8/22/2024 10:40	0	0
150	8/22/2024 10:41	0	0
151	8/22/2024 10:42	0	0
152	8/22/2024 10:43	0	0
153	8/22/2024 10:44	0	0
154	8/22/2024 10:45	0	0
155	8/22/2024 10:46	0	0
156	8/22/2024 10:47	0	0
157	8/22/2024 10:48	0	0
158	8/22/2024 10:49	0	0
159	8/22/2024 10:50	0	0
160	8/22/2024 10:51	0	0
161	8/22/2024 10:52	0	0
162	8/22/2024 10:53	0	0
163	8/22/2024 10:54	0	0
164	8/22/2024 10:55	0	0
165	8/22/2024 10:56	0	0
166	8/22/2024 10:57	0	0
167	8/22/2024 10:58	0	0
168	8/22/2024 10:59	0	0
169	8/22/2024 11:00	0	0
170	8/22/2024 11:01	0	0
171	8/22/2024 11:02	0	0
172	8/22/2024 11:03	0	0

NYSDEC Site No. 314008

173	8/22/2024 11:04	0	0
174	8/22/2024 11:05	0	0
175	8/22/2024 11:06	0	0
176	8/22/2024 11:07	0	0
177	8/22/2024 11:08	0	0
178	8/22/2024 11:09	0	0
179	8/22/2024 11:10	0	0
180	8/22/2024 11:11	0	0
181	8/22/2024 11:12	0	0
182	8/22/2024 11:13	0	0
183	8/22/2024 11:14	0	0
184	8/22/2024 11:15	0	0
185	8/22/2024 11:16	0	0
186	8/22/2024 11:17	0	0
187	8/22/2024 11:18	0	0
188	8/22/2024 11:19	0	0
189	8/22/2024 11:20	0	0
190	8/22/2024 11:21	0	0
191	8/22/2024 11:22	0	0
192	8/22/2024 11:23	0	0
193	8/22/2024 11:24	0	0
194	8/22/2024 11:25	0	0
195	8/22/2024 11:26	0	0
196	8/22/2024 11:27	0	0
197	8/22/2024 11:28	0	0
198	8/22/2024 11:29	0	0
199	8/22/2024 11:30	0	0
200	8/22/2024 11:31	0	0
201	8/22/2024 11:32	0	0
202	8/22/2024 11:33	0	0
203	8/22/2024 11:34	0	0
204	8/22/2024 11:35	0	0
205	8/22/2024 11:36	0	0
206	8/22/2024 11:37	0	0
207	8/22/2024 11:38	0	0
208	8/22/2024 11:39	0	0
209	8/22/2024 11:40	0	0
210	8/22/2024 11:41	0	0
211	8/22/2024 11:42	0	0
212	8/22/2024 11:43	0	0
213	8/22/2024 11:44	0	0
214	8/22/2024 11:45	0	0
215	8/22/2024 11:46	0	0
216	8/22/2024 11:47	0	0

NYSDEC Site No. 314008

217	8/22/2024 11:48	0	0
218	8/22/2024 11:49	0	0
219	8/22/2024 11:50	0	0
220	8/22/2024 11:51	0	0
221	8/22/2024 11:52	0	0
222	8/22/2024 11:53	0	0
223	8/22/2024 11:54	0	0
224	8/22/2024 11:55	0	0
225	8/22/2024 11:56	0	0
226	8/22/2024 11:57	0	0
227	8/22/2024 11:58	0	0
228	8/22/2024 11:59	0	0
229	8/22/2024 12:00	0	0
230	8/22/2024 12:01	0	0
231	8/22/2024 12:02	0	0
232	8/22/2024 12:03	0	0
233	8/22/2024 12:04	0	0
234	8/22/2024 12:05	0	0
235	8/22/2024 12:06	0	0
236	8/22/2024 12:07	0	0
237	8/22/2024 12:08	0	0
238	8/22/2024 12:09	0	0
239	8/22/2024 12:10	0	0
240	8/22/2024 12:11	0	0
241	8/22/2024 12:12	0	0
242	8/22/2024 12:13	0	0
243	8/22/2024 12:14	0	0
244	8/22/2024 12:15	0	0
245	8/22/2024 12:16	0	0
246	8/22/2024 12:17	0	0
247	8/22/2024 12:18	0	0
248	8/22/2024 12:19	0	0
249	8/22/2024 12:20	0	0
250	8/22/2024 12:21	0	0
251	8/22/2024 12:22	0	0
252	8/22/2024 12:23	0	0
253	8/22/2024 12:24	0	0
254	8/22/2024 12:25	0	0
255	8/22/2024 12:26	0	0
256	8/22/2024 12:27	0	0
257	8/22/2024 12:28	0	0
258	8/22/2024 12:29	0	0
259	8/22/2024 12:30	0	0
260	8/22/2024 12:31	0	0

NYSDEC Site No. 314008

261	8/22/2024 12:32	0	0
262	8/22/2024 12:33	0	0
263	8/22/2024 12:34	0	0
264	8/22/2024 12:35	0	0
265	8/22/2024 12:36	0	0
266	8/22/2024 12:37	0	0
267	8/22/2024 12:38	0	0
268	8/22/2024 12:39	0	0
269	8/22/2024 12:40	0	0
270	8/22/2024 12:41	0	0
271	8/22/2024 12:42	0	0
272	8/22/2024 12:43	0	0
273	8/22/2024 12:44	0	0
274	8/22/2024 12:45	0	0
275	8/22/2024 12:46	0	0
276	8/22/2024 12:47	0	0
277	8/22/2024 12:48	0	0
278	8/22/2024 12:49	0	0
279	8/22/2024 12:50	0	0
280	8/22/2024 12:51	0	0
281	8/22/2024 12:52	0	0
282	8/22/2024 12:53	0	0
283	8/22/2024 12:54	0	0
284	8/22/2024 12:55	0	0
285	8/22/2024 12:56	0	0
286	8/22/2024 12:57	0	0
287	8/22/2024 12:58	0	0
288	8/22/2024 12:59	0	0
289	8/22/2024 13:00	0	0
290	8/22/2024 13:01	0	0
291	8/22/2024 13:02	0	0
292	8/22/2024 13:03	0	0
293	8/22/2024 13:04	0	0
294	8/22/2024 13:05	0	0
295	8/22/2024 13:06	0	0
296	8/22/2024 13:07	0	0
297	8/22/2024 13:08	0	0
298	8/22/2024 13:09	0	0
299	8/22/2024 13:10	0	0
300	8/22/2024 13:11	0	0
301	8/22/2024 13:12	0	0
302	8/22/2024 13:13	0	0
303	8/22/2024 13:14	0	0
304	8/22/2024 13:15	0	0

NYSDEC Site No. 314008

305	8/22/2024 13:16	0	0
306	8/22/2024 13:17	0	0
307	8/22/2024 13:18	0	0
308	8/22/2024 13:19	0	0
309	8/22/2024 13:20	0	0
310	8/22/2024 13:21	0	0
311	8/22/2024 13:22	0	0
312	8/22/2024 13:23	0	0
313	8/22/2024 13:24	0	0
314	8/22/2024 13:25	0	0
315	8/22/2024 13:26	0	0
316	8/22/2024 13:27	0	0
317	8/22/2024 13:28	0	0
318	8/22/2024 13:29	0	0
319	8/22/2024 13:30	0	0
320	8/22/2024 13:31	0	0
321	8/22/2024 13:32	0	0
322	8/22/2024 13:33	0	0
323	8/22/2024 13:34	0	0
324	8/22/2024 13:35	0	0
325	8/22/2024 13:36	0	0
326	8/22/2024 13:37	0	0
327	8/22/2024 13:38	0	0
328	8/22/2024 13:39	0	0
329	8/22/2024 13:40	0	0
330	8/22/2024 13:41	0	0
331	8/22/2024 13:42	0	0
332	8/22/2024 13:43	0	0
333	8/22/2024 13:44	0	0
334	8/22/2024 13:45	0	0
335	8/22/2024 13:46	0	0
336	8/22/2024 13:47	0	0
337	8/22/2024 13:48	0	0
338	8/22/2024 13:49	0	0
339	8/22/2024 13:50	0	0
340	8/22/2024 13:51	0	0
341	8/22/2024 13:52	0	0
342	8/22/2024 13:53	0	0
343	8/22/2024 13:54	0	0
344	8/22/2024 13:55	0	0
345	8/22/2024 13:56	0	0
346	8/22/2024 13:57	0	0
347	8/22/2024 13:58	0	0
348	8/22/2024 13:59	0	0

NYSDEC Site No. 314008

349	8/22/2024 14:00	0	0
350	8/22/2024 14:01	0	0
351	8/22/2024 14:02	0	0
352	8/22/2024 14:03	0	0
353	8/22/2024 14:04	0	0
354	8/22/2024 14:05	0	0
355	8/22/2024 14:06	0	0
356	8/22/2024 14:07	0	0
357	8/22/2024 14:08	0	0
358	8/22/2024 14:09	0	0
359	8/22/2024 14:10	0	0
360	8/22/2024 14:11	0	0
361	8/22/2024 14:12	0	0
362	8/22/2024 14:13	0	0
363	8/22/2024 14:14	0	0
364	8/22/2024 14:15	0	0
365	8/22/2024 14:16	0	0
366	8/22/2024 14:17	0	0
367	8/22/2024 14:18	0	0
368	8/22/2024 14:19	0	0
369	8/22/2024 14:20	0	0
370	8/22/2024 14:21	0	0
371	8/22/2024 14:22	0	0
372	8/22/2024 14:23	0	0
373	8/22/2024 14:24	0	0
374	8/22/2024 14:25	0	0
375	8/22/2024 14:26	0	0
376	8/22/2024 14:27	0	0
377	8/22/2024 14:28	0	0
378	8/22/2024 14:29	0	0
379	8/22/2024 14:30	0	0
380	8/22/2024 14:31	0	0
381	8/22/2024 14:32	0	0
382	8/22/2024 14:33	0	0
383	8/22/2024 14:34	0	0
384	8/22/2024 14:35	0	0
385	8/22/2024 14:36	0	0
386	8/22/2024 14:37	0	0
387	8/22/2024 14:38	0	0
388	8/22/2024 14:39	0	0
389	8/22/2024 14:40	0	0
390	8/22/2024 14:41	0	0
391	8/22/2024 14:42	0	0
392	8/22/2024 14:43	0	0

NYSDEC Site No. 314008

393	8/22/2024 14:44	0	0
394	8/22/2024 14:45	0	0
395	8/22/2024 14:46	0	0
396	8/22/2024 14:47	0	0
397	8/22/2024 14:48	0	0
398	8/22/2024 14:49	0	0
399	8/22/2024 14:50	0	0
400	8/22/2024 14:51	0	0
401	8/22/2024 14:52	0	0
402	8/22/2024 14:53	0	0
403	8/22/2024 14:54	0	0
404	8/22/2024 14:55	0	0
405	8/22/2024 14:56	0	0
406	8/22/2024 14:57	0	0
407	8/22/2024 14:58	0	0
408	8/22/2024 14:59	0	0
409	8/22/2024 15:00	0	0
410	8/22/2024 15:01	0	0
411	8/22/2024 15:02	0	0
412	8/22/2024 15:03	0	0
413	8/22/2024 15:04	0	0
414	8/22/2024 15:05	0	0
415	8/22/2024 15:06	0	0
416	8/22/2024 15:07	0	0
417	8/22/2024 15:08	0	0
418	8/22/2024 15:09	0	0
419	8/22/2024 15:10	0	0
420	8/22/2024 15:11	0	0
421	8/22/2024 15:12	0	0
422	8/22/2024 15:13	0	0
423	8/22/2024 15:14	0	0
424	8/22/2024 15:15	0	0
425	8/22/2024 15:16	0	0
426	8/22/2024 15:17	0	0
427	8/22/2024 15:18	0	0
428	8/22/2024 15:19	0	0
429	8/22/2024 15:20	0	0
430	8/22/2024 15:21	0	0
431	8/22/2024 15:22	0	0
432	8/22/2024 15:23	0	0
433	8/22/2024 15:24	0	0
434	8/22/2024 15:25	0	0
435	8/22/2024 15:26	0	0
436	8/22/2024 15:27	0	0

NYSDEC Site No. 314008

437	8/22/2024 15:28	0	0
438	8/22/2024 15:29	0	0
439	8/22/2024 15:30	0	0
440	8/22/2024 15:31	0	0
441	8/22/2024 15:32	0	0
442	8/22/2024 15:33	0	0
443	8/22/2024 15:34	0	0
444	8/22/2024 15:35	0	0
445	8/22/2024 15:36	0	0
446	8/22/2024 15:37	0	0
447	8/22/2024 15:38	0	0
448	8/22/2024 15:39	0	0
449	8/22/2024 15:40	0	0
450	8/22/2024 15:41	0	0
451	8/22/2024 15:42	0	0
452	8/22/2024 15:43	0	0
453	8/22/2024 15:44	0	0
454	8/22/2024 15:45	0	0
455	8/22/2024 15:46	0	0
456	8/22/2024 15:47	0	0
457	8/22/2024 15:48	0	0
458	8/22/2024 15:49	0	0
459	8/22/2024 15:50	0	0
460	8/22/2024 15:51	0	0
461	8/22/2024 15:52	0	0
462	8/22/2024 15:53	0	0
463	8/22/2024 15:54	0	0
464	8/22/2024 15:55	0	0
465	8/22/2024 15:56	0	0
466	8/22/2024 15:57	0	0
467	8/22/2024 15:58	0	0
468	8/22/2024 15:59	0	0
469	8/22/2024 16:00	0	0
470	8/22/2024 16:01	0	0
471	8/22/2024 16:02	0	0
472	8/22/2024 16:03	0	0
473	8/22/2024 16:04	0	0
474	8/22/2024 16:05	0	0
475	8/22/2024 16:06	0	0
476	8/22/2024 16:07	0	0
477	8/22/2024 16:08	0	0
478	8/22/2024 16:09	0	0
479	8/22/2024 16:10	0	0
480	8/22/2024 16:11	0	0

NYSDEC Site No. 314008

481	8/22/2024 16:12	0	0
482	8/22/2024 16:13	0	0
483	8/22/2024 16:14	0	0
484	8/22/2024 16:15	0	0
485	8/22/2024 16:16	0	0
486	8/22/2024 16:17	0	0
487	8/22/2024 16:18	0	0
488	8/22/2024 16:19	0	0
489	8/22/2024 16:20	0	0
490	8/22/2024 16:21	0	0
491	8/22/2024 16:22	0	0
492	8/22/2024 16:23	0	0
493	8/22/2024 16:24	0	0
494	8/22/2024 16:25	0	0
495	8/22/2024 16:26	0	0
496	8/22/2024 16:27	0	0
497	8/22/2024 16:28	0	0
498	8/22/2024 16:29	0	0
499	8/22/2024 16:30	0	0
500	8/22/2024 16:31	0	0
501	8/22/2024 16:32	0	0
502	8/22/2024 16:33	0	0
503	8/22/2024 16:34	0	0
504	8/22/2024 16:35	0	0
505	8/22/2024 16:36	0	0
506	8/22/2024 16:37	0	0
507	8/22/2024 16:38	0	0
508	8/22/2024 16:39	0	0
509	8/22/2024 16:40	0	0
510	8/22/2024 16:41	0	0
511	8/22/2024 16:42	0	0
512	8/22/2024 16:43	0	0
513	8/22/2024 16:44	0	0
514	8/22/2024 16:45	0	0
515	8/22/2024 16:46	0	0
516	8/22/2024 16:47	0	0
517	8/22/2024 16:48	0	0
518	8/22/2024 16:49	0	0
519	8/22/2024 16:50	0	0
520	8/22/2024 16:51	0	0
521	8/22/2024 16:52	0	0
522	8/22/2024 16:53	0	0
523	8/22/2024 16:54	0	0
524	8/22/2024 16:55	0	0

NYSDEC Site No. 314008

525	8/22/2024 16:56	0	0
526	8/22/2024 16:57	0	0
527	8/22/2024 16:58	0	0
528	8/22/2024 16:59	0	0
529	8/22/2024 17:00	0	0
530	8/22/2024 17:01	0	0
531	8/22/2024 17:02	0	0
532	8/22/2024 17:03	0	0
533	8/22/2024 17:04	0	0
534	8/22/2024 17:05	0	0
535	8/22/2024 17:06	0	0
536	8/22/2024 17:07	0	0
537	8/22/2024 17:08	0	0
538	8/22/2024 17:09	0	0
539	8/22/2024 17:10	0	0
540	8/22/2024 17:11	0	0
541	8/22/2024 17:12	0	0
542	8/22/2024 17:13	0	0
543	8/22/2024 17:14	0	0
544	8/22/2024 17:15	0	0
545	8/22/2024 17:16	0	0
546	8/22/2024 17:17	0	0
547	8/22/2024 17:18	0	0
548	8/22/2024 17:19	0	0
549	8/22/2024 17:20	0	0
550	8/22/2024 17:21	0	0
551	8/22/2024 17:22	0	0
552	8/22/2024 17:23	0	0
553	8/22/2024 17:24	0	0
554	8/22/2024 17:25	0	0
555	8/22/2024 17:26	0	0
556	8/22/2024 17:27	0	0
557	8/22/2024 17:28	0	0
558	8/22/2024 17:29	0	0
559	8/22/2024 17:30	0	0
560	8/22/2024 17:31	0	0
561	8/22/2024 17:32	0	0
562	8/22/2024 17:33	0	0
563	8/22/2024 17:34	0	0
564	8/22/2024 17:35	0	0
565	8/22/2024 17:36	0	0
566	8/22/2024 17:37	0	0
567	8/22/2024 17:38	0	0
568	8/22/2024 17:39	0	0

NYSDEC Site No. 314008

569	8/22/2024 17:40	0	0
570	8/22/2024 17:41	0	0
571	8/22/2024 17:42	0	0
572	8/22/2024 17:43	0	0
573	8/22/2024 17:44	0	0
574	8/22/2024 17:45	0	0
575	8/22/2024 17:46	0	0
576	8/22/2024 17:47	0	0
577	8/22/2024 17:48	0	0
578	8/22/2024 17:49	0	0
579	8/22/2024 17:50	0	0
580	8/22/2024 17:51	0	0
581	8/22/2024 17:52	0	0
582	8/22/2024 17:53	0	0

24/08/23 08:16

Summary

Unit Name MiniRAE 3000(PGM-7320)

Unit SN 592-904349

Unit Firmware Ver V2.22A

Running Mode Hygiene Mode

Datalog Mode Auto

Diagnostic Mode No

Stop Reason Power Down

Site ID 1

User ID 1

Begin 8/23/2024 8:16

End 8/23/2024 14:37

Sample Period(s) 60

Number of Records 381

Sensor PID(ppm)

Sensor SN S023030247C5

Measure Type Min; Avg; Max; Real

Span 100

Span 2 1000

Low Alarm 50

High Alarm 100

Over Alarm 15000

NYSDEC Site No. 314008

STEL Alarm 25

TWA Alarm 10

Measurement Gas Isobutylene

Calibration Time 8/13/2024 10:27

Peak 0.2

Min 0

Average 0

Datalog

		PID(ppm)	PID(ppm)	PID(ppm)	PID(ppm)
Index	Date/Time	(Min)	(Avg)	(Max)	(Real)
1	8/23/2024 8:17	0	0	0	0
2	8/23/2024 8:18	0	0	0	0
3	8/23/2024 8:19	0	0	0	0
4	8/23/2024 8:20	0	0	0	0
5	8/23/2024 8:21	0	0	0	0
6	8/23/2024 8:22	0	0	0	0
7	8/23/2024 8:23	0	0	0	0
8	8/23/2024 8:24	0	0	0	0
9	8/23/2024 8:25	0	0	0	0
10	8/23/2024 8:26	0	0	0	0
11	8/23/2024 8:27	0	0	0	0
12	8/23/2024 8:28	0	0	0	0
13	8/23/2024 8:29	0	0	0	0
14	8/23/2024 8:30	0	0	0	0
15	8/23/2024 8:31	0	0	0	0
16	8/23/2024 8:32	0	0	0	0
17	8/23/2024 8:33	0	0	0	0
18	8/23/2024 8:34	0	0	0	0
19	8/23/2024 8:35	0	0	0	0
20	8/23/2024 8:36	0	0	0	0
21	8/23/2024 8:37	0	0	0	0
22	8/23/2024 8:38	0	0	0	0
23	8/23/2024 8:39	0	0	0	0
24	8/23/2024 8:40	0	0	0	0
25	8/23/2024 8:41	0	0	0	0
26	8/23/2024 8:42	0	0	0	0
27	8/23/2024 8:43	0	0	0	0
28	8/23/2024 8:44	0	0	0	0
29	8/23/2024 8:45	0	0	0	0
30	8/23/2024 8:46	0	0	0	0
31	8/23/2024 8:47	0	0	0	0
32	8/23/2024 8:48	0	0	0	0

NYSDEC Site No. 314008

33	8/23/2024 8:49	0	0	0	0
34	8/23/2024 8:50	0	0	0	0
35	8/23/2024 8:51	0	0	0	0
36	8/23/2024 8:52	0	0	0	0
37	8/23/2024 8:53	0	0	0	0
38	8/23/2024 8:54	0	0	0	0
39	8/23/2024 8:55	0	0	0	0
40	8/23/2024 8:56	0	0	0	0
41	8/23/2024 8:57	0	0	0	0
42	8/23/2024 8:58	0	0	0	0
43	8/23/2024 8:59	0	0	0	0
44	8/23/2024 9:00	0	0	0	0
45	8/23/2024 9:01	0	0	0	0
46	8/23/2024 9:02	0	0	0	0
47	8/23/2024 9:03	0	0	0	0
48	8/23/2024 9:04	0	0	0	0
49	8/23/2024 9:05	0	0	0	0
50	8/23/2024 9:06	0	0	0	0
51	8/23/2024 9:07	0	0	0	0
52	8/23/2024 9:08	0	0	0	0
53	8/23/2024 9:09	0	0	0	0
54	8/23/2024 9:10	0	0	0	0
55	8/23/2024 9:11	0	0	0	0
56	8/23/2024 9:12	0	0	0	0
57	8/23/2024 9:13	0	0	0	0
58	8/23/2024 9:14	0	0	0	0
59	8/23/2024 9:15	0	0	0	0
60	8/23/2024 9:16	0	0	0	0
61	8/23/2024 9:17	0	0	0	0
62	8/23/2024 9:18	0	0	0	0
63	8/23/2024 9:19	0	0	0	0
64	8/23/2024 9:20	0	0	0	0
65	8/23/2024 9:21	0	0	0	0
66	8/23/2024 9:22	0	0	0	0
67	8/23/2024 9:23	0	0	0	0
68	8/23/2024 9:24	0	0	0	0
69	8/23/2024 9:25	0	0	0	0
70	8/23/2024 9:26	0	0	0	0
71	8/23/2024 9:27	0	0	0	0
72	8/23/2024 9:28	0	0	0	0
73	8/23/2024 9:29	0	0	0	0
74	8/23/2024 9:30	0	0	0	0
75	8/23/2024 9:31	0	0	0	0
76	8/23/2024 9:32	0	0	0	0

77	8/23/2024 9:33	0	0	0	0
78	8/23/2024 9:34	0	0	0	0
79	8/23/2024 9:35	0	0	0	0
80	8/23/2024 9:36	0	0	0	0
81	8/23/2024 9:37	0	0	0	0
82	8/23/2024 9:38	0	0	0	0
83	8/23/2024 9:39	0	0	0	0
84	8/23/2024 9:40	0	0	0	0
85	8/23/2024 9:41	0	0	0	0
86	8/23/2024 9:42	0	0	0	0
87	8/23/2024 9:43	0	0	0	0
88	8/23/2024 9:44	0	0	0	0
89	8/23/2024 9:45	0	0	0	0
90	8/23/2024 9:46	0	0	0	0
91	8/23/2024 9:47	0	0	0	0
92	8/23/2024 9:48	0	0	0	0
93	8/23/2024 9:49	0	0	0	0
94	8/23/2024 9:50	0	0	0	0
95	8/23/2024 9:51	0	0	0	0
96	8/23/2024 9:52	0	0	0	0
97	8/23/2024 9:53	0	0	0	0
98	8/23/2024 9:54	0	0	0	0
99	8/23/2024 9:55	0	0	0	0
100	8/23/2024 9:56	0	0	0	0
101	8/23/2024 9:57	0	0	0	0
102	8/23/2024 9:58	0	0	0	0
103	8/23/2024 9:59	0	0	0	0
104	8/23/2024 10:00	0	0	0	0
105	8/23/2024 10:01	0	0	0	0
106	8/23/2024 10:02	0	0	0	0
107	8/23/2024 10:03	0	0	0	0
108	8/23/2024 10:04	0	0	0	0
109	8/23/2024 10:05	0	0	0	0
110	8/23/2024 10:06	0	0	0	0
111	8/23/2024 10:07	0	0	0	0
112	8/23/2024 10:08	0	0	0	0
113	8/23/2024 10:09	0	0	0	0
114	8/23/2024 10:10	0	0	0	0
115	8/23/2024 10:11	0	0	0	0
116	8/23/2024 10:12	0	0	0	0
117	8/23/2024 10:13	0	0	0	0
118	8/23/2024 10:14	0	0	0	0
119	8/23/2024 10:15	0	0	0	0
120	8/23/2024 10:16	0	0	0	0

NYSDEC Site No. 314008

121	8/23/2024 10:17	0	0	0	0
122	8/23/2024 10:18	0	0	0	0
123	8/23/2024 10:19	0	0	0	0
124	8/23/2024 10:20	0	0	0	0
125	8/23/2024 10:21	0	0	0	0
126	8/23/2024 10:22	0	0	0	0
127	8/23/2024 10:23	0	0	0	0
128	8/23/2024 10:24	0	0	0	0
129	8/23/2024 10:25	0	0	0	0
130	8/23/2024 10:26	0	0	0	0
131	8/23/2024 10:27	0	0	0	0
132	8/23/2024 10:28	0	0	0	0
133	8/23/2024 10:29	0	0	0	0
134	8/23/2024 10:30	0	0	0	0
135	8/23/2024 10:31	0	0	0	0
136	8/23/2024 10:32	0	0	0	0
137	8/23/2024 10:33	0	0	0	0
138	8/23/2024 10:34	0	0	0	0
139	8/23/2024 10:35	0	0	0	0
140	8/23/2024 10:36	0	0	0	0
141	8/23/2024 10:37	0	0	0	0
142	8/23/2024 10:38	0	0	0	0
143	8/23/2024 10:39	0	0	0	0
144	8/23/2024 10:40	0	0	0	0
145	8/23/2024 10:41	0	0	0	0
146	8/23/2024 10:42	0	0	0	0
147	8/23/2024 10:43	0	0	0	0
148	8/23/2024 10:44	0	0	0	0
149	8/23/2024 10:45	0	0	0	0
150	8/23/2024 10:46	0	0	0	0
151	8/23/2024 10:47	0	0	0	0
152	8/23/2024 10:48	0	0	0	0
153	8/23/2024 10:49	0	0	0	0
154	8/23/2024 10:50	0	0	0	0
155	8/23/2024 10:51	0	0	0	0
156	8/23/2024 10:52	0	0	0	0
157	8/23/2024 10:53	0	0	0	0
158	8/23/2024 10:54	0	0	0	0
159	8/23/2024 10:55	0	0	0	0
160	8/23/2024 10:56	0	0	0	0
161	8/23/2024 10:57	0	0	0	0
162	8/23/2024 10:58	0	0	0	0
163	8/23/2024 10:59	0	0	0	0
164	8/23/2024 11:00	0	0	0	0

NYSDEC Site No. 314008

165	8/23/2024 11:01	0	0	0	0
166	8/23/2024 11:02	0	0	0	0
167	8/23/2024 11:03	0	0	0	0
168	8/23/2024 11:04	0	0	0	0
169	8/23/2024 11:05	0	0	0	0
170	8/23/2024 11:06	0	0	0	0
171	8/23/2024 11:07	0	0	0	0
172	8/23/2024 11:08	0	0	0	0
173	8/23/2024 11:09	0	0	0	0
174	8/23/2024 11:10	0	0	0	0
175	8/23/2024 11:11	0	0	0	0
176	8/23/2024 11:12	0	0	0	0
177	8/23/2024 11:13	0	0	0	0
178	8/23/2024 11:14	0	0	0	0
179	8/23/2024 11:15	0	0	0	0
180	8/23/2024 11:16	0	0	0	0
181	8/23/2024 11:17	0	0	0	0
182	8/23/2024 11:18	0	0	0	0
183	8/23/2024 11:19	0	0	0	0
184	8/23/2024 11:20	0	0	0	0
185	8/23/2024 11:21	0	0	0	0
186	8/23/2024 11:22	0	0	0	0
187	8/23/2024 11:23	0	0	0	0
188	8/23/2024 11:24	0	0	0	0
189	8/23/2024 11:25	0	0	0	0
190	8/23/2024 11:26	0	0	0	0
191	8/23/2024 11:27	0	0	0	0
192	8/23/2024 11:28	0	0	0	0
193	8/23/2024 11:29	0	0	0	0
194	8/23/2024 11:30	0	0	0	0
195	8/23/2024 11:31	0	0	0	0
196	8/23/2024 11:32	0	0	0	0
197	8/23/2024 11:33	0	0	0	0
198	8/23/2024 11:34	0	0	0.3	0.2
199	8/23/2024 11:35	0	0	0.2	0
200	8/23/2024 11:36	0	0	0	0
201	8/23/2024 11:37	0	0	0	0
202	8/23/2024 11:38	0	0	0	0
203	8/23/2024 11:39	0	0	0	0
204	8/23/2024 11:40	0	0	0	0
205	8/23/2024 11:41	0	0	0	0
206	8/23/2024 11:42	0	0	0	0
207	8/23/2024 11:43	0	0	0	0
208	8/23/2024 11:44	0	0	0	0

209	8/23/2024 11:45	0	0	0	0
210	8/23/2024 11:46	0	0	0	0
211	8/23/2024 11:47	0	0	0	0
212	8/23/2024 11:48	0	0	0	0
213	8/23/2024 11:49	0	0	0	0
214	8/23/2024 11:50	0	0	0	0
215	8/23/2024 11:51	0	0	0	0
216	8/23/2024 11:52	0	0	0	0
217	8/23/2024 11:53	0	0	0	0
218	8/23/2024 11:54	0	0	0	0
219	8/23/2024 11:55	0	0	0	0
220	8/23/2024 11:56	0	0	0	0
221	8/23/2024 11:57	0	0	0	0
222	8/23/2024 11:58	0	0	0	0
223	8/23/2024 11:59	0	0	0	0
224	8/23/2024 12:00	0	0	0	0
225	8/23/2024 12:01	0	0	0	0
226	8/23/2024 12:02	0	0	0	0
227	8/23/2024 12:03	0	0	0	0
228	8/23/2024 12:04	0	0	0	0
229	8/23/2024 12:05	0	0	0.1	0
230	8/23/2024 12:06	0	0	0	0
231	8/23/2024 12:07	0	0	0	0
232	8/23/2024 12:08	0	0	0	0
233	8/23/2024 12:09	0	0	0	0
234	8/23/2024 12:10	0	0	0	0
235	8/23/2024 12:11	0	0	0	0
236	8/23/2024 12:12	0	0	0	0
237	8/23/2024 12:13	0	0	0	0
238	8/23/2024 12:14	0	0	0	0
239	8/23/2024 12:15	0	0	0	0
240	8/23/2024 12:16	0	0	0	0
241	8/23/2024 12:17	0	0	0	0
242	8/23/2024 12:18	0	0	0	0
243	8/23/2024 12:19	0	0	0	0
244	8/23/2024 12:20	0	0	0	0
245	8/23/2024 12:21	0	0	0	0
246	8/23/2024 12:22	0	0	0	0
247	8/23/2024 12:23	0	0	0	0
248	8/23/2024 12:24	0	0	0	0
249	8/23/2024 12:25	0	0	0	0
250	8/23/2024 12:26	0	0	0	0
251	8/23/2024 12:27	0	0	0	0
252	8/23/2024 12:28	0	0	0	0

253	8/23/2024 12:29	0	0	0	0
254	8/23/2024 12:30	0	0	0	0
255	8/23/2024 12:31	0	0	0	0
256	8/23/2024 12:32	0	0	0	0
257	8/23/2024 12:33	0	0	0	0
258	8/23/2024 12:34	0	0	0	0
259	8/23/2024 12:35	0	0	0	0
260	8/23/2024 12:36	0	0	0	0
261	8/23/2024 12:37	0	0	0	0
262	8/23/2024 12:38	0	0	0	0
263	8/23/2024 12:39	0	0	0	0
264	8/23/2024 12:40	0	0	0	0
265	8/23/2024 12:41	0	0	0	0
266	8/23/2024 12:42	0	0	0	0
267	8/23/2024 12:43	0	0	0	0
268	8/23/2024 12:44	0	0	0	0
269	8/23/2024 12:45	0	0	0	0
270	8/23/2024 12:46	0	0	0	0
271	8/23/2024 12:47	0	0	0	0
272	8/23/2024 12:48	0	0	0	0
273	8/23/2024 12:49	0	0	0	0
274	8/23/2024 12:50	0	0	0	0
275	8/23/2024 12:51	0	0	0	0
276	8/23/2024 12:52	0	0	0	0
277	8/23/2024 12:53	0	0	0	0
278	8/23/2024 12:54	0	0	0	0
279	8/23/2024 12:55	0	0	0	0
280	8/23/2024 12:56	0	0	0	0
281	8/23/2024 12:57	0	0	0	0
282	8/23/2024 12:58	0	0	0	0
283	8/23/2024 12:59	0	0	0	0
284	8/23/2024 13:00	0	0	0	0
285	8/23/2024 13:01	0	0	0	0
286	8/23/2024 13:02	0	0	0	0
287	8/23/2024 13:03	0	0	0	0
288	8/23/2024 13:04	0	0	0	0
289	8/23/2024 13:05	0	0	0	0
290	8/23/2024 13:06	0	0	0	0
291	8/23/2024 13:07	0	0	0	0
292	8/23/2024 13:08	0	0	0	0
293	8/23/2024 13:09	0	0	0	0
294	8/23/2024 13:10	0	0	0	0
295	8/23/2024 13:11	0	0	0	0
296	8/23/2024 13:12	0	0	0	0

NYSDEC Site No. 314008

297	8/23/2024 13:13	0	0	0	0
298	8/23/2024 13:14	0	0	0	0
299	8/23/2024 13:15	0	0	0	0
300	8/23/2024 13:16	0	0	0	0
301	8/23/2024 13:17	0	0	0	0
302	8/23/2024 13:18	0	0	0	0
303	8/23/2024 13:19	0	0	0	0
304	8/23/2024 13:20	0	0	0	0
305	8/23/2024 13:21	0	0	0	0
306	8/23/2024 13:22	0	0	0	0
307	8/23/2024 13:23	0	0	0	0
308	8/23/2024 13:24	0	0	0	0
309	8/23/2024 13:25	0	0	0	0
310	8/23/2024 13:26	0	0	0	0
311	8/23/2024 13:27	0	0	0	0
312	8/23/2024 13:28	0	0	0	0
313	8/23/2024 13:29	0	0	0	0
314	8/23/2024 13:30	0	0	0	0
315	8/23/2024 13:31	0	0	0	0
316	8/23/2024 13:32	0	0	0	0
317	8/23/2024 13:33	0	0	0	0
318	8/23/2024 13:34	0	0	0	0
319	8/23/2024 13:35	0	0	0	0
320	8/23/2024 13:36	0	0	0	0
321	8/23/2024 13:37	0	0	0	0
322	8/23/2024 13:38	0	0	0	0
323	8/23/2024 13:39	0	0	0	0
324	8/23/2024 13:40	0	0	0	0
325	8/23/2024 13:41	0	0	0	0
326	8/23/2024 13:42	0	0	0	0
327	8/23/2024 13:43	0	0	0	0
328	8/23/2024 13:44	0	0	0	0
329	8/23/2024 13:45	0	0	0	0
330	8/23/2024 13:46	0	0	0	0
331	8/23/2024 13:47	0	0	0	0
332	8/23/2024 13:48	0	0	0	0
333	8/23/2024 13:49	0	0	0	0
334	8/23/2024 13:50	0	0	0	0
335	8/23/2024 13:51	0	0	0	0
336	8/23/2024 13:52	0	0	0	0
337	8/23/2024 13:53	0	0	0	0
338	8/23/2024 13:54	0	0	0	0
339	8/23/2024 13:55	0	0	0	0
340	8/23/2024 13:56	0	0	0	0

NYSDEC Site No. 314008

341	8/23/2024 13:57	0	0	0	0
342	8/23/2024 13:58	0	0	0	0
343	8/23/2024 13:59	0	0	0	0
344	8/23/2024 14:00	0	0	0	0
345	8/23/2024 14:01	0	0	0	0
346	8/23/2024 14:02	0	0	0	0
347	8/23/2024 14:03	0	0	0	0
348	8/23/2024 14:04	0	0	0	0
349	8/23/2024 14:05	0	0	0	0
350	8/23/2024 14:06	0	0	0	0
351	8/23/2024 14:07	0	0	0	0
352	8/23/2024 14:08	0	0	0	0
353	8/23/2024 14:09	0	0	0	0
354	8/23/2024 14:10	0	0	0	0
355	8/23/2024 14:11	0	0	0	0
356	8/23/2024 14:12	0	0	0	0
357	8/23/2024 14:13	0	0	0	0
358	8/23/2024 14:14	0	0	0	0
359	8/23/2024 14:15	0	0	0	0
360	8/23/2024 14:16	0	0	0	0
361	8/23/2024 14:17	0	0	0	0
362	8/23/2024 14:18	0	0	0	0
363	8/23/2024 14:19	0	0	0	0
364	8/23/2024 14:20	0	0	0	0
365	8/23/2024 14:21	0	0	0	0
366	8/23/2024 14:22	0	0	0	0
367	8/23/2024 14:23	0	0	0	0
368	8/23/2024 14:24	0	0	0	0
369	8/23/2024 14:25	0	0	0	0
370	8/23/2024 14:26	0	0	0	0
371	8/23/2024 14:27	0	0	0	0
372	8/23/2024 14:28	0	0	0	0
373	8/23/2024 14:29	0	0	0	0
374	8/23/2024 14:30	0	0	0	0
375	8/23/2024 14:31	0	0	0	0
376	8/23/2024 14:32	0	0	0	0
377	8/23/2024 14:33	0	0	0	0
378	8/23/2024 14:34	0	0	0	0
379	8/23/2024 14:35	0	0	0	0
380	8/23/2024 14:36	0	0	0	0
381	8/23/2024 14:37	0	0	0	0
Peak		0	0	0.3	0.2
Min		0	0	0	0
Average		0	0	0	0

TWA/STEL

Index	Date/Time	PID(ppm) (TWA)	PID(ppm) (STEL)
1	8/23/2024 8:17	0	---
2	8/23/2024 8:18	0	---
3	8/23/2024 8:19	0	---
4	8/23/2024 8:20	0	---
5	8/23/2024 8:21	0	---
6	8/23/2024 8:22	0	---
7	8/23/2024 8:23	0	---
8	8/23/2024 8:24	0	---
9	8/23/2024 8:25	0	---
10	8/23/2024 8:26	0	---
11	8/23/2024 8:27	0	---
12	8/23/2024 8:28	0	---
13	8/23/2024 8:29	0	---
14	8/23/2024 8:30	0	---
15	8/23/2024 8:31	0	0
16	8/23/2024 8:32	0	0
17	8/23/2024 8:33	0	0
18	8/23/2024 8:34	0	0
19	8/23/2024 8:35	0	0
20	8/23/2024 8:36	0	0
21	8/23/2024 8:37	0	0
22	8/23/2024 8:38	0	0
23	8/23/2024 8:39	0	0
24	8/23/2024 8:40	0	0
25	8/23/2024 8:41	0	0
26	8/23/2024 8:42	0	0
27	8/23/2024 8:43	0	0
28	8/23/2024 8:44	0	0
29	8/23/2024 8:45	0	0
30	8/23/2024 8:46	0	0
31	8/23/2024 8:47	0	0
32	8/23/2024 8:48	0	0
33	8/23/2024 8:49	0	0
34	8/23/2024 8:50	0	0
35	8/23/2024 8:51	0	0
36	8/23/2024 8:52	0	0
37	8/23/2024 8:53	0	0
38	8/23/2024 8:54	0	0
39	8/23/2024 8:55	0	0

NYSDEC Site No. 314008

40	8/23/2024 8:56	0	0
41	8/23/2024 8:57	0	0
42	8/23/2024 8:58	0	0
43	8/23/2024 8:59	0	0
44	8/23/2024 9:00	0	0
45	8/23/2024 9:01	0	0
46	8/23/2024 9:02	0	0
47	8/23/2024 9:03	0	0
48	8/23/2024 9:04	0	0
49	8/23/2024 9:05	0	0
50	8/23/2024 9:06	0	0
51	8/23/2024 9:07	0	0
52	8/23/2024 9:08	0	0
53	8/23/2024 9:09	0	0
54	8/23/2024 9:10	0	0
55	8/23/2024 9:11	0	0
56	8/23/2024 9:12	0	0
57	8/23/2024 9:13	0	0
58	8/23/2024 9:14	0	0
59	8/23/2024 9:15	0	0
60	8/23/2024 9:16	0	0
61	8/23/2024 9:17	0	0
62	8/23/2024 9:18	0	0
63	8/23/2024 9:19	0	0
64	8/23/2024 9:20	0	0
65	8/23/2024 9:21	0	0
66	8/23/2024 9:22	0	0
67	8/23/2024 9:23	0	0
68	8/23/2024 9:24	0	0
69	8/23/2024 9:25	0	0
70	8/23/2024 9:26	0	0
71	8/23/2024 9:27	0	0
72	8/23/2024 9:28	0	0
73	8/23/2024 9:29	0	0
74	8/23/2024 9:30	0	0
75	8/23/2024 9:31	0	0
76	8/23/2024 9:32	0	0
77	8/23/2024 9:33	0	0
78	8/23/2024 9:34	0	0
79	8/23/2024 9:35	0	0
80	8/23/2024 9:36	0	0
81	8/23/2024 9:37	0	0
82	8/23/2024 9:38	0	0
83	8/23/2024 9:39	0	0

NYSDEC Site No. 314008

84	8/23/2024 9:40	0	0
85	8/23/2024 9:41	0	0
86	8/23/2024 9:42	0	0
87	8/23/2024 9:43	0	0
88	8/23/2024 9:44	0	0
89	8/23/2024 9:45	0	0
90	8/23/2024 9:46	0	0
91	8/23/2024 9:47	0	0
92	8/23/2024 9:48	0	0
93	8/23/2024 9:49	0	0
94	8/23/2024 9:50	0	0
95	8/23/2024 9:51	0	0
96	8/23/2024 9:52	0	0
97	8/23/2024 9:53	0	0
98	8/23/2024 9:54	0	0
99	8/23/2024 9:55	0	0
100	8/23/2024 9:56	0	0
101	8/23/2024 9:57	0	0
102	8/23/2024 9:58	0	0
103	8/23/2024 9:59	0	0
104	8/23/2024 10:00	0	0
105	8/23/2024 10:01	0	0
106	8/23/2024 10:02	0	0
107	8/23/2024 10:03	0	0
108	8/23/2024 10:04	0	0
109	8/23/2024 10:05	0	0
110	8/23/2024 10:06	0	0
111	8/23/2024 10:07	0	0
112	8/23/2024 10:08	0	0
113	8/23/2024 10:09	0	0
114	8/23/2024 10:10	0	0
115	8/23/2024 10:11	0	0
116	8/23/2024 10:12	0	0
117	8/23/2024 10:13	0	0
118	8/23/2024 10:14	0	0
119	8/23/2024 10:15	0	0
120	8/23/2024 10:16	0	0
121	8/23/2024 10:17	0	0
122	8/23/2024 10:18	0	0
123	8/23/2024 10:19	0	0
124	8/23/2024 10:20	0	0
125	8/23/2024 10:21	0	0
126	8/23/2024 10:22	0	0
127	8/23/2024 10:23	0	0

NYSDEC Site No. 314008

128	8/23/2024 10:24	0	0
129	8/23/2024 10:25	0	0
130	8/23/2024 10:26	0	0
131	8/23/2024 10:27	0	0
132	8/23/2024 10:28	0	0
133	8/23/2024 10:29	0	0
134	8/23/2024 10:30	0	0
135	8/23/2024 10:31	0	0
136	8/23/2024 10:32	0	0
137	8/23/2024 10:33	0	0
138	8/23/2024 10:34	0	0
139	8/23/2024 10:35	0	0
140	8/23/2024 10:36	0	0
141	8/23/2024 10:37	0	0
142	8/23/2024 10:38	0	0
143	8/23/2024 10:39	0	0
144	8/23/2024 10:40	0	0
145	8/23/2024 10:41	0	0
146	8/23/2024 10:42	0	0
147	8/23/2024 10:43	0	0
148	8/23/2024 10:44	0	0
149	8/23/2024 10:45	0	0
150	8/23/2024 10:46	0	0
151	8/23/2024 10:47	0	0
152	8/23/2024 10:48	0	0
153	8/23/2024 10:49	0	0
154	8/23/2024 10:50	0	0
155	8/23/2024 10:51	0	0
156	8/23/2024 10:52	0	0
157	8/23/2024 10:53	0	0
158	8/23/2024 10:54	0	0
159	8/23/2024 10:55	0	0
160	8/23/2024 10:56	0	0
161	8/23/2024 10:57	0	0
162	8/23/2024 10:58	0	0
163	8/23/2024 10:59	0	0
164	8/23/2024 11:00	0	0
165	8/23/2024 11:01	0	0
166	8/23/2024 11:02	0	0
167	8/23/2024 11:03	0	0
168	8/23/2024 11:04	0	0
169	8/23/2024 11:05	0	0
170	8/23/2024 11:06	0	0
171	8/23/2024 11:07	0	0

NYSDEC Site No. 314008

172	8/23/2024 11:08	0	0
173	8/23/2024 11:09	0	0
174	8/23/2024 11:10	0	0
175	8/23/2024 11:11	0	0
176	8/23/2024 11:12	0	0
177	8/23/2024 11:13	0	0
178	8/23/2024 11:14	0	0
179	8/23/2024 11:15	0	0
180	8/23/2024 11:16	0	0
181	8/23/2024 11:17	0	0
182	8/23/2024 11:18	0	0
183	8/23/2024 11:19	0	0
184	8/23/2024 11:20	0	0
185	8/23/2024 11:21	0	0
186	8/23/2024 11:22	0	0
187	8/23/2024 11:23	0	0
188	8/23/2024 11:24	0	0
189	8/23/2024 11:25	0	0
190	8/23/2024 11:26	0	0
191	8/23/2024 11:27	0	0
192	8/23/2024 11:28	0	0
193	8/23/2024 11:29	0	0
194	8/23/2024 11:30	0	0
195	8/23/2024 11:31	0	0
196	8/23/2024 11:32	0	0
197	8/23/2024 11:33	0	0
198	8/23/2024 11:34	0	0
199	8/23/2024 11:35	0	0
200	8/23/2024 11:36	0	0
201	8/23/2024 11:37	0	0
202	8/23/2024 11:38	0	0
203	8/23/2024 11:39	0	0
204	8/23/2024 11:40	0	0
205	8/23/2024 11:41	0	0
206	8/23/2024 11:42	0	0
207	8/23/2024 11:43	0	0
208	8/23/2024 11:44	0	0
209	8/23/2024 11:45	0	0
210	8/23/2024 11:46	0	0
211	8/23/2024 11:47	0	0
212	8/23/2024 11:48	0	0
213	8/23/2024 11:49	0	0
214	8/23/2024 11:50	0	0
215	8/23/2024 11:51	0	0

NYSDEC Site No. 314008

216	8/23/2024 11:52	0	0
217	8/23/2024 11:53	0	0
218	8/23/2024 11:54	0	0
219	8/23/2024 11:55	0	0
220	8/23/2024 11:56	0	0
221	8/23/2024 11:57	0	0
222	8/23/2024 11:58	0	0
223	8/23/2024 11:59	0	0
224	8/23/2024 12:00	0	0
225	8/23/2024 12:01	0	0
226	8/23/2024 12:02	0	0
227	8/23/2024 12:03	0	0
228	8/23/2024 12:04	0	0
229	8/23/2024 12:05	0	0
230	8/23/2024 12:06	0	0
231	8/23/2024 12:07	0	0
232	8/23/2024 12:08	0	0
233	8/23/2024 12:09	0	0
234	8/23/2024 12:10	0	0
235	8/23/2024 12:11	0	0
236	8/23/2024 12:12	0	0
237	8/23/2024 12:13	0	0
238	8/23/2024 12:14	0	0
239	8/23/2024 12:15	0	0
240	8/23/2024 12:16	0	0
241	8/23/2024 12:17	0	0
242	8/23/2024 12:18	0	0
243	8/23/2024 12:19	0	0
244	8/23/2024 12:20	0	0
245	8/23/2024 12:21	0	0
246	8/23/2024 12:22	0	0
247	8/23/2024 12:23	0	0
248	8/23/2024 12:24	0	0
249	8/23/2024 12:25	0	0
250	8/23/2024 12:26	0	0
251	8/23/2024 12:27	0	0
252	8/23/2024 12:28	0	0
253	8/23/2024 12:29	0	0
254	8/23/2024 12:30	0	0
255	8/23/2024 12:31	0	0
256	8/23/2024 12:32	0	0
257	8/23/2024 12:33	0	0
258	8/23/2024 12:34	0	0
259	8/23/2024 12:35	0	0

NYSDEC Site No. 314008

260	8/23/2024 12:36	0	0
261	8/23/2024 12:37	0	0
262	8/23/2024 12:38	0	0
263	8/23/2024 12:39	0	0
264	8/23/2024 12:40	0	0
265	8/23/2024 12:41	0	0
266	8/23/2024 12:42	0	0
267	8/23/2024 12:43	0	0
268	8/23/2024 12:44	0	0
269	8/23/2024 12:45	0	0
270	8/23/2024 12:46	0	0
271	8/23/2024 12:47	0	0
272	8/23/2024 12:48	0	0
273	8/23/2024 12:49	0	0
274	8/23/2024 12:50	0	0
275	8/23/2024 12:51	0	0
276	8/23/2024 12:52	0	0
277	8/23/2024 12:53	0	0
278	8/23/2024 12:54	0	0
279	8/23/2024 12:55	0	0
280	8/23/2024 12:56	0	0
281	8/23/2024 12:57	0	0
282	8/23/2024 12:58	0	0
283	8/23/2024 12:59	0	0
284	8/23/2024 13:00	0	0
285	8/23/2024 13:01	0	0
286	8/23/2024 13:02	0	0
287	8/23/2024 13:03	0	0
288	8/23/2024 13:04	0	0
289	8/23/2024 13:05	0	0
290	8/23/2024 13:06	0	0
291	8/23/2024 13:07	0	0
292	8/23/2024 13:08	0	0
293	8/23/2024 13:09	0	0
294	8/23/2024 13:10	0	0
295	8/23/2024 13:11	0	0
296	8/23/2024 13:12	0	0
297	8/23/2024 13:13	0	0
298	8/23/2024 13:14	0	0
299	8/23/2024 13:15	0	0
300	8/23/2024 13:16	0	0
301	8/23/2024 13:17	0	0
302	8/23/2024 13:18	0	0
303	8/23/2024 13:19	0	0

NYSDEC Site No. 314008

304	8/23/2024 13:20	0	0
305	8/23/2024 13:21	0	0
306	8/23/2024 13:22	0	0
307	8/23/2024 13:23	0	0
308	8/23/2024 13:24	0	0
309	8/23/2024 13:25	0	0
310	8/23/2024 13:26	0	0
311	8/23/2024 13:27	0	0
312	8/23/2024 13:28	0	0
313	8/23/2024 13:29	0	0
314	8/23/2024 13:30	0	0
315	8/23/2024 13:31	0	0
316	8/23/2024 13:32	0	0
317	8/23/2024 13:33	0	0
318	8/23/2024 13:34	0	0
319	8/23/2024 13:35	0	0
320	8/23/2024 13:36	0	0
321	8/23/2024 13:37	0	0
322	8/23/2024 13:38	0	0
323	8/23/2024 13:39	0	0
324	8/23/2024 13:40	0	0
325	8/23/2024 13:41	0	0
326	8/23/2024 13:42	0	0
327	8/23/2024 13:43	0	0
328	8/23/2024 13:44	0	0
329	8/23/2024 13:45	0	0
330	8/23/2024 13:46	0	0
331	8/23/2024 13:47	0	0
332	8/23/2024 13:48	0	0
333	8/23/2024 13:49	0	0
334	8/23/2024 13:50	0	0
335	8/23/2024 13:51	0	0
336	8/23/2024 13:52	0	0
337	8/23/2024 13:53	0	0
338	8/23/2024 13:54	0	0
339	8/23/2024 13:55	0	0
340	8/23/2024 13:56	0	0
341	8/23/2024 13:57	0	0
342	8/23/2024 13:58	0	0
343	8/23/2024 13:59	0	0
344	8/23/2024 14:00	0	0
345	8/23/2024 14:01	0	0
346	8/23/2024 14:02	0	0
347	8/23/2024 14:03	0	0

NYSDEC Site No. 314008

348	8/23/2024 14:04	0	0
349	8/23/2024 14:05	0	0
350	8/23/2024 14:06	0	0
351	8/23/2024 14:07	0	0
352	8/23/2024 14:08	0	0
353	8/23/2024 14:09	0	0
354	8/23/2024 14:10	0	0
355	8/23/2024 14:11	0	0
356	8/23/2024 14:12	0	0
357	8/23/2024 14:13	0	0
358	8/23/2024 14:14	0	0
359	8/23/2024 14:15	0	0
360	8/23/2024 14:16	0	0
361	8/23/2024 14:17	0	0
362	8/23/2024 14:18	0	0
363	8/23/2024 14:19	0	0
364	8/23/2024 14:20	0	0
365	8/23/2024 14:21	0	0
366	8/23/2024 14:22	0	0
367	8/23/2024 14:23	0	0
368	8/23/2024 14:24	0	0
369	8/23/2024 14:25	0	0
370	8/23/2024 14:26	0	0
371	8/23/2024 14:27	0	0
372	8/23/2024 14:28	0	0
373	8/23/2024 14:29	0	0
374	8/23/2024 14:30	0	0
375	8/23/2024 14:31	0	0
376	8/23/2024 14:32	0	0
377	8/23/2024 14:33	0	0
378	8/23/2024 14:34	0	0
379	8/23/2024 14:35	0	0
380	8/23/2024 14:36	0	0
381	8/23/2024 14:37	0	0

Appendix E - Green Remediation Best Management Practices



Green Remediation Best Management Practices: Site Investigation

Office of Superfund Remediation and Technology Innovation

Quick Reference Fact Sheet

The U.S. Environmental Protection Agency (EPA) *Principles for Greener Cleanups* outline the Agency's policy for evaluating and minimizing the environmental "footprint" of activities undertaken when cleaning up a contaminated site.¹ Use of the best management practices (BMPs) recommended in EPA's series of green remediation fact sheets can help project managers and other stakeholders apply the principles on a routine basis, while maintaining the cleanup objectives, ensuring protectiveness of a remedy, and improving its environmental outcome.²

Overview

The need for site investigation is common to cleanups under any regulatory program. An investigation can occur at all points in the cleanup process, from initial site assessment through waste site closeout. A site investigation generally is undertaken to:

- Confirm the presence or absence of specific contaminants
- Delineate the nature and extent of environmental contamination
- Identify contaminant sources
- Provide the data necessary to assess potential risk to human health and/or the environment
- Gather the data needed to determine if a remedial action should be taken
- Understand site characteristics impacting the remedy design, construction, or operation and closeout, and
- Evaluate performance of a remedial action.

Site investigations typically involve sampling of soil and groundwater using various drilling and well installation technologies and analysis of samples at offsite laboratories. Investigations also may include sampling of sediment, surface water, soil gas, or indoor air; searching for underground storage tanks (USTs) or other buried objects; or evaluating demolition material containing asbestos, lead-based paint, or other toxic products.

Planning for Site Investigation

Consideration of green remediation options early during the project design phase will help reduce cumulative environmental footprints of a cleanup. Effective planning will include identification of investigative decision points in context of a site's unique contamination scenario and logistics, while accounting for potential remedies and anticipated site reuse.

At each decision point, strategies and methods can be evaluated to determine which are likely to best address the core elements of a green cleanup:

- Reducing total energy use and increasing renewable energy use
- Reducing air pollutants and greenhouse gas (GHG) emissions
- Reducing water use and negative impacts on water resources
- Improving materials management and waste reduction efforts, and
- Enhancing land management and ecosystems protection.



A green site investigation relies on information gained from a thorough preliminary assessment that identifies target areas and site conditions through minimally intrusive techniques. Use of innovative field analytics and direct sensing tools can reduce the environmental footprint of follow-on characterization or cleanup activities, particularly by limiting mobilizations in the field and increasing the density of analytical data. More targeted remedial actions and "surgical" removal actions also can be achieved through use of high resolution sampling tools during site investigations.

Initial BMPs for a site investigation include:

- Evaluating feasibility of using a mobile laboratory, field analytical methods, or direct sensing tools
- Scheduling activities for appropriate seasons to reduce delays caused by weather conditions and fuel needed for heating or cooling
- Identifying local sources of energy efficient machinery and vehicles and alternative fuels
- Establishing electronic networks for data transfers and deliverables, team decisions, and document preparation, and selecting electronic products on the basis of comparisons available in the Electronic Product Environmental Assessment Tool (EPEAT®)
- Selecting facilities with green policies, for worker accommodations and periodic meetings
- Reducing travel through increased teleconferencing, compressed work hours, and flexible work locations, and
- Identifying options for integrating renewable energy resources, including those extending throughout cleanup activities.





Portable electricity generators equipped with photovoltaic panels and batteries can be used to power investigative equipment such as chilling or heating units.

Procurement of goods and services offers other opportunities for conserving natural resources:

- Incorporate green specifications into solicitations and contracts, with respect to environmentally preferred purchasing of materials, awards to contractors with green policies and procedures (such as routine use of water efficient and Energy Star® equipment) and periodic reporting of resource reductions
- Select service providers, product suppliers, and analytical laboratories from the local area and coordinate service and delivery schedules, to reduce fuel consumption and associated air emissions, and
- Specify laboratory analytical methods generating less waste and solvents, such as solid phase micro extraction (SPME), pressurized fluid extraction, microwave extraction, and supercritical fluid extraction, if comparable accuracies can be achieved; for example, SPME provides a single-step process that can reduce sample preparation time by as much as 70% while using little or no solvents.

Collection of representative data during the first round of field activities reduces the need for subsequent sampling. Development of a well conceived site sampling plan can help assure that collected data truly represent a site. Systematic planning, a critical component of optimized strategies for investigating hazardous waste sites, involves identifying key decisions to be made, developing a conceptual site model (CSM) to support decision making, and evaluating decision uncertainty along with approaches for actively managing that uncertainty. The CSM combines analytical data with historical information to identify data gaps and allows for refinement as additional data become available.

Collecting information dynamically and in real time and adjusting the work according to the field findings will minimize mobilizations. Dynamic work strategies that employ data visualization, dynamic sampling programs, and quality controls to minimize uncertainties reduce the need for repeated mobilizations and additional sampling. Use of the Triad approach can help project managers integrate systematic planning, dynamic working strategies, and deployment of these real-time measurement tools.³

Energy Use & Renewable Energy

Fewer field mobilizations can result in significant savings of fossil fuel and minimized emission of GHG and other air pollutants. Real-time field measurements can immediately provide data to help determine the next course of action during a single sampling event. Real-time data collection technologies include:

- Direct sensing technology such as the membrane interface probe, laser-induced fluorescence (LIF) sensor, and cone penetrometer testing (CPT)
- X-ray fluorescence analyzers for metals
- Soil gas surveys for volatile organic compounds (VOCs)
- Portable gas chromatography/mass spectrometry for fuel-related compounds and VOCs in soil and groundwater
- Field test kits for analyzing soil and groundwater contaminants such as petroleum, metals, polychlorinated biphenyls, pesticides, explosives, and inorganics, and
- Geophysical surveys for locating USTs, buried steel drums, and boundaries of disposal areas.

Profile: McGuire Air Force Base, C-17 Hangar Site, New Hanover, NJ

- *Used a Triad decision making approach to complete characterization of VOC contamination of soil and groundwater ahead of schedule, consequently reducing the fuel consumption, land disturbance, and dust generation associated with additional sampling days*
- *Used investigative tools such as CPT and fuel fluorescence detectors to generate over 4,500 analytical results in real time, which expedited decision making in the field and avoided fuel use associated with transporting samples to an offsite laboratory*
- *Determined through real-time measurements that natural attenuation of halogenated VOCs was occurring, and avoided excess land disturbance and fuel consumption by incorporating monitored natural attenuation into the remedy*
- *Precisely identified a smear zone of Stoddard solvent, allowing it to be surgically excavated with minimal land disturbance and fuel consumption*

Recommended BMPs for selecting other equipment and processes that minimize fuel and energy consumption include:

- Limiting the number of vehicles deployed onsite, and renting electric, hybrid, or hydrogen fuel cell vehicles
- Instituting idle reduction plans, such as machinery shutdown after three minutes of non-use
- Compressing shipments to offsite laboratories whenever feasible
- Using in situ data loggers wherever appropriate to monitor water levels and water quality parameters

- Using solar-powered telemetry systems to remotely transmit logging data directly to project offices
- Using rechargeable batteries for handheld data loggers and other field instruments
- Using direct-push technology (DPT) for well drilling, which is 50-60% more time efficient than rotary drill rigs and avoids drill cuttings that require assessment and disposal of investigation-derived waste (IDW)
- Segregating soil and groundwater collected from different areas; in many states, media analytically determined to be clean can be deposited onsite rather than transported for offsite disposal, and
- Disposing IDW at the nearest permitted facility.

Air Pollutants & GHG Emissions

Air emissions from mobile sources can be reduced through use of various new technologies. Diesel emission control filters, for example, can reduce particulate matter emissions by as much as 89% and nitrogen oxide emissions by as much as 80%. Switching from low-sulfur to ultralow-sulfur fuels will reduce emissions of sulfur dioxide (an acid rain-causing air pollutant) and also allows use of emission control systems that would be damaged by fuels with a higher sulfur content. Ultralow-sulfur diesel has become the standard in most states; it contains no more than 15 ppm sulfur (S), in comparison to the 500 ppm S in low-sulfur diesel.

Any technology that reduces duration of drilling and groundwater pumping or purging helps reduce the cumulative amounts of pollutants released to the air. Examples include sonic drilling and passive (diffusion-based) sampling devices.


Deployment of diesel-powered machinery, vehicles, and equipment over six months of investigations could emit nearly 32,000 pounds of CO₂, based on a consumption of more than 1,400 gallons of diesel.⁴

Relative Diesel Consumption of Common Investigative Activities over Six Months (gallons)	
Transportation, operation, and support for a rotary drilling rig for four weeks	293
Groundwater sampling with a submersible pump driven by a 2.5-hp gasoline-powered generator	45
Deployment of a truck-mounted DPT rig for subsurface sampling	400
Operation of utility trucks for equipment maintenance, groundwater and soil sampling, and oversight	300
Periodic truck delivery of small equipment and supplies and disposal of nonhazardous waste	260
IDW transfer to a disposal facility by way of tractor trailer	125
Total diesel consumed: 1,423 gallons	

Water Use & Impacts on Water Resources

Green remediation strategies help reduce consumption of fresh water, reclaim or reuse uncontaminated water, minimize potential for waterborne contamination, and minimize introduction of toxic processing materials during a site investigation. Recommended best practices include:

- Using waterless drilling techniques such as DPT
- Exploring options for reusing operational graywater and capturing rainwater for tasks such as irrigation or dust control
- Returning unused clean water to surface water bodies rather than discharging it to a public sewer system
- Using low-flow sampling equipment wherever possible during monitoring, to minimize purge volumes and energy consumption while producing little IDW



Use of passive diffusion bag samplers reduces or eliminates purge water associated with well sampling; multiple vertically-placed samplers can provide a vertical profile of groundwater samples at one-foot intervals.

- Steam-cleaning or using phosphate-free detergents instead of organic solvents or acids to decontaminate sampling equipment
- Containing decontamination fluids and preventing their entrance into storm drains or the ground surface
- Treating potentially contaminated purge water through use of appropriate treatment techniques such as activated carbon filtration prior to discharge to storm drains or waterways
- Using closed-loop cleaning systems relying on graywater to wash non-sampling related machinery and equipment
- Using biodegradable hydraulic fluids on hydraulic equipment such as drill rigs
- Selecting groundwater monitoring equipment made of noncorrosive material, to avoid potential cross-contamination and equipment replacement, and
- Quickly restoring any vegetated areas disrupted by equipment or vehicles, to control stormwater runoff and avoid soil transport to surface water bodies.

Integrating the needs of remedial and monitoring phases during design of sampling wells will help reduce subsurface drilling throughout the life of a cleanup. Well designs also can accommodate a site's potential cleanup remedy(s) and reuse goals, in ways that meet the site's future demand for water while preserving any portions of the property targeted for specific use.

Materials Management & Waste Reduction

Site investigation procedures typically involve use of an assortment of manufactured products such as personal protective equipment (PPE), sample containers, and routine business materials. Green purchasing considers product lifecycles and gives preference to:

- Products with recycled and biobased contents such as agricultural or forestry waste instead of petroleum-based ingredients
- Products, packing material, and disposable equipment with reuse or recycling potential, and
- Products manufactured through processes involving nontoxic chemical alternatives.

IDW generation and management account for a significant portion of the environmental footprints of site investigation. IDW includes drill cuttings, well purge water, spent carbon from filtration equipment, reagents used with environmental field test kits, contaminated PPE, and solutions for decontaminating non-disposable PPE and equipment.

Reducing the volume of generated IDW will decrease the need for related containers such as plastic disposal bags and 55-gallon storage drums, and for treatment or disposal of IDW in an appropriate hazardous or nonhazardous waste facility. Recommended BMPs to reduce the volume of routine waste or IDW and decrease materials consumption include:

- Recycling cardboard boxes and beverage bottles
- Reducing use of single-use plastic bags
- Reducing the number of sampling days
- Using onsite analysis and other real-time measurement technologies to reduce needs for sample packing materials
- Selecting test kits that generate less waste, such as soil samplers with reusable handles for coring syringes, and
- Segregating drill cuttings by appropriately stockpiling next to a borehole and awaiting analytical results; under many cleanup programs, clean soil may be distributed near boreholes or backfilled into a boring.

Explore Web-based calculators, software models, and other **Footprint Assessment** tools accessible on Green Remediation Focus (<http://www.cluin.org/greenremediation>), such as the:

- CICA Compliance Summary Tool, to evaluate construction impacts on land, ecosystems, and water
- Energy & Materials Flow & Cost Tracker (EMFACT™), to track materials, energy use, wastes, and costs
- Greenhouse Gas Protocol, to quantify and manage GHG emissions
- MotorMaster+, to select energy efficient motors, and
- Water Evaluation and Planning System (WEAP), to conduct integrated water resource planning

Land Management & Ecosystem Protection

Site investigation activities can disturb a significant amount of land in order to gather the necessary data. Project managers should consider technologies resulting in limited subsurface intrusion and minimal land impacts:

- Ground penetrating radar or other geophysical methods can identify subsurface anomalies such as USTs and buried drums without disturbing land.
- DPT for soil and groundwater sampling do not result in drill cuttings or excess soil waste and related IDW.
- A wide range of direct sensing tools such as the LIF sensor are now available to develop a nearly continuous vertical profile of some volatile and semi-volatile contaminants in the subsurface, both above and below the water table.
- Soil gas surveys are minimally invasive and can provide relatively rapid and cost-effective information about the presence, composition, and distribution of contaminants in the vadose zone and water table.

A Sampling of Success Measures for Site Investigation

- *Reduced fuel consumption and GHG emissions through integrated planning of field activities*
- *Increased use of solar energy-driven auxiliary equipment and small devices*
- *Reduced generation of wastewater from well drilling and sampling*
- *Reduced subsurface and ecosystem disturbance through more use of advanced sampling technologies and visualizing techniques*
- *Fewer soil and groundwater samples needing offsite laboratory analysis*

References [Web accessed: 2009, November 30]

- ¹ U.S. EPA; *Principles for Greener Cleanups*; August 27, 2009; <http://www.epa.gov/oswer/greencleanups>
- ² U.S. EPA; *Green Remediation: Incorporating Sustainable Environmental Practices into Remediation of Contaminated Sites*; EPA 542-R-08-002, April 2008; <http://www.cluin.org/greenremediation>
- ³ Interstate Technology & Regulatory Council; *Technical and Regulatory Guidance for the Triad Approach: A New Paradigm for Environmental Project Management*; December 2003; <http://www.triadcentral.org/>
- ⁴ U.S. EPA; *Emission Facts: Average Carbon Dioxide Emissions Resulting from Gasoline and Diesel Fuel*; EPA420-F-05-001

Visit **Green Remediation Focus** online:
<http://www.cluin.org/greenremediation>

For more information, contact:
Carlos Pachon, OSWER/OSRTI (pachon.carlos@epa.gov)
U.S. Environmental Protection Agency

Appendix F – Beacon Environmental Soil Gas Analysis Reports



Beacon Environmental

526 Underwood Lane
Bel Air, MD 21014 USA
1.410.838.8780

CERTIFICATE OF ANALYSIS

Beacon Proposal No.: 240312R01

Laboratory Work Order: 0007994

Project Description:

NOW Corporation
Stratsburg, NY

Client PO No.: 60631041-.07.01F

Prepared for:

Chris French

AECOM

40 British American Boulevard

Latham, NY 12110

Ryan W. Schneider
Senior Project Manager

September 17, 2024

All data meet requirements as specified in the Beacon Environmental Quality Assurance Project Plan and the results relate only to the samples reported. The work performed was in accordance with ISO/IEC 17025:2017, except samples were analyzed within a 24-hour tune window. This report shall not be reproduced, except in full, without written approval of the laboratory. Release of the data contained in this data package has been authorized by the Laboratory Director or his signee, as verified by the following signatures:

Steven C. Thornley
Laboratory Director

Peter B. Kelly
Quality Manager

Table of Contents

Cover Page	1
Sample Summary	11
Case Narrative	21
Analytical Results	24
Summary of Compound Detections	25
Data Summary Table	56
Detailed Analytical Results	57
0007994-01 - Trip 1	58
0007994-02 - Trip 2	59
0007994-03 - Trip 3	60
0007994-04 - Trip 4	61
0007994-05 - Trip 5	62
0007994-06 - SGP-A1	63
0007994-07 - SGP-A2	64
0007994-08 - SGP-A3	65
0007994-09 - SGP-A4	66
0007994-10 - SGP-A5	67
0007994-11 - SGP-A6	68
0007994-12 - SGP-A7	69
0007994-13 - SGP-A8	70
0007994-14 - SGP-B1	71
0007994-15 - SGP-B1-DUP	72
0007994-16 - SGP-B2	73
0007994-17 - SGP-B3	74
0007994-18 - SGP-B4	75

Table of Contents (continued)

0007994-19 - SGP-B5	76
0007994-20 - SGP-B6	77
0007994-21 - SGP-B7	78
0007994-22 - SGP-B8	79
0007994-23 - SGP-B9	80
0007994-24 - SGP-C1	81
0007994-25 - SGP-C2	82
0007994-26 - SGP-C3	83
0007994-27 - SGP-C4	84
0007994-28 - SGP-C5	85
0007994-29 - SGP-C6	86
0007994-30 - SGP-C7	87
0007994-31 - SGP-C8	88
0007994-32 - SGP-C9	89
0007994-33 - SGP-C10	90
0007994-34 - SGP-D1	91
0007994-35 - SGP-D2	92
0007994-36 - SGP-E1	93
0007994-37 - SGP-E2	94
0007994-38 - SGP-E3	95
0007994-39 - SGP-F1	96
0007994-40 - SGP-F2	97
0007994-41 - SGP-G1	98
0007994-42 - SGP-G2	99
0007994-43 - SGP-H1	100

Table of Contents (continued)

0007994-44 - SGP-H2	101
0007994-45 - SGP-H3	102
0007994-46 - SGP-H4	103
0007994-47 - SGP-H5	104
0007994-48 - SGP-H6	105
0007994-49 - SGP-H6-DUP	106
0007994-50 - SGP-H7	107
0007994-51 - SGP-H8	108
0007994-52 - SGP-I1	109
0007994-53 - SGP-I2	110
0007994-54 - SGP-I3	111
0007994-55 - SGP-I4	112
0007994-56 - SGP-I5	113
0007994-57 - SGP-I6	114
0007994-58 - SGP-I7	115
0007994-59 - SGP-I8	116
0007994-60 - SGP-J0	117
0007994-61 - SGP-J00	118
0007994-62 - SGP-J1	119
0007994-63 - SGP-J2	120
0007994-64 - SGP-J3	121
0007994-65 - SGP-J4	122
0007994-66 - SGP-J5	123
0007994-67 - SGP-J6	124
0007994-68 - SGP-J7	125

Table of Contents (continued)

0007994-69 - SGP-K0	126
0007994-70 - SGP-K00	127
0007994-71 - SGP-K1	128
0007994-72 - SGP-K1-DUP	129
0007994-73 - SGP-K2	130
0007994-74 - SGP-K3	131
0007994-75 - SGP-K4	132
0007994-76 - SGP-K5	133
0007994-77 - SGP-K6	134
0007994-78 - SGP-K7	135
0007994-79 - SGP-K8	136
0007994-80 - SGP-L1	137
0007994-81 - SGP-L2	138
0007994-82 - SGP-L3	139
0007994-83 - SGP-L4	140
0007994-84 - SGP-L5	141
0007994-85 - SGP-L6	142
0007994-86 - SGP-L7	143
0007994-87 - SGP-M0	144
0007994-88 - SGP-M1	145
0007994-89 - SGP-M1-DUP	146
0007994-90 - SGP-M2	147
0007994-91 - SGP-M3	148
0007994-92 - SGP-M4	149
0007994-93 - SGP-M5	150

Table of Contents (continued)

0007994-94 - SGP-M6	151
0007994-95 - SGP-M7	152
0007994-96 - SGP-M8	153
0007994-97 - SGP-N1	154
0007994-98 - SGP-N2	155
0007994-99 - SGP-N3	156
0007994-AA - SGP-N4	157
0007994-AB - SGP-N5	158
0007994-AC - SGP-N6	159
0007994-AD - SGP-N7	160
0007994-AE - SGP-O1	161
0007994-AF - SGP-O2	162
0007994-AG - SGP-O3	163
0007994-AH - SGP-O4	164
0007994-AI - SGP-O5	165
0007994-AJ - SGP-O6	166
0007994-AK - SGP-O7	167
0007994-AL - SGP-O8	168
0007994-AM - SGP-O8-DUP	169
0007994-AN - SGP-O9	170
0007994-AO - SGP-O10	171
0007994-AP - SGP-O11	172
0007994-AQ - SGP-O12	173
0007994-AR - SGP-O13	174
0007994-AS - SGP-O14	175

Table of Contents (continued)

0007994-AT - SGP-P1	176
0007994-AU - SGP-P2	177
0007994-AV - SGP-P3	178
0007994-AW - SGP-P4	179
0007994-AX - SGP-P4-DUP	180
0007994-AY - SGP-P5	181
0007994-AZ - SGP-Q1	182
0007994-BA - SGP-Q2	183
0007994-BB - SGP-Q3	184
0007994-BC - SGP-R1	185
0007994-BD - SGP-R2	186
0007994-BE - SGP-R3	187
0007994-BF - SGP-R4	188
0007994-BG - SGP-R4-DUP	189
0007994-BH - SGP-S1	190
0007994-BI - SGP-S2	191
0007994-BJ - SGP-S3	192
0007994-BK - SGP-T1	193
0007994-BL - SGP-T2	194
0007994-BM - SGP-T3	195
0007994-BN - SGP-U1	196
0007994-BO - SGP-U2	197
0007994-BP - SGP-U3	198
0007994-BQ - SGP-V1	199
0007994-BR - SGP-V2	200

Table of Contents (continued)

0007994-BS - SGP-V3	201
0007994-BT - SGP-W1	202
0007994-BU - SGP-W2	203
0007994-BV - SGP-X1	204
0007994-BW - SGP-X2	205
0007994-BX - SGP-Y1	206
0007994-BY - SGP-Y2	207
0007994-BZ - SGP-Z1	208
0007994-CA - SGP-Z2	209
0007994-CB - SGP-Z3	210
0007994-CC - SGP-AA1	211
0007994-CD - SGP-AA1-DUP	212
0007994-CE - SGP-AA2	213
0007994-CF - SGP-AA3	214
0007994-CG - SGP-BB1	215
0007994-CH - SGP-BB2	216
0007994-CI - SGP-BB3	217
0007994-CJ - SGP-CC1	218
0007994-CK - SGP-CC2	219
0007994-CL - SGP-CC3	220
0007994-CM - SGP-CC4	221
0007994-CN - SGP-CC5	222
0007994-CO - SGP-CC5-DUP	223
0007994-CP - SGP-DD1	224
0007994-CQ - SGP-DD2	225

Table of Contents (continued)

0007994-CR - SGP-DD3	226
0007994-CS - SGP-DD4	227
0007994-CT - SGP-DD5	228
0007994-CU - SGP-DD6	229
0007994-CV - SGP-EE1	230
0007994-CW - SGP-EE2	231
0007994-CX - SGP-EE3	232
0007994-CY - SGP-EE4	233
0007994-CZ - SGP-EE5	234
0007994-DA - SGP-EE6	235
0007994-DB - SGP-FF1	236
0007994-DC - SGP-FF2	237
0007994-DD - SGP-FF3	238
0007994-DE - SGP-FF3-DUP	239
0007994-DF - SGP-FF4	240
0007994-DG - SGP-FF5	241
0007994-DH - SGP-GG1	242
0007994-DI - SGP-GG2	243
0007994-DJ - SGP-GG3	244
0007994-DK - SGP-GG4	245
0007994-DL - SGP-HH1	246
0007994-DM - SGP-HH2	247
0007994-DN - SGP-HH3	248
0007994-DO - SGP-II1	249
0007994-DP - SGP-II2	250

Table of Contents (continued)

0007994-DQ - SGP-II3	251
0007994-DR - SGP-II4	252
0007994-DS - SGP-JJ1	253
0007994-DT - SGP-JJ2	254
0007994-DU - SGP-KK1	255
0007994-DV - SGP-KK2	256
0007994-DW - SGP-LL1	257
0007994-DX - SGP-MM1	258
0007994-DY - SGP-MM2	259
0007994-DZ - SGP-MM3	260
0007994-EA - SGP-NN1	261
0007994-EB - SGP-NN2	262
0007994-EC - SGP-NN3	263
QC Summaries	264
Additional QC Information	281
Certifications	282
Notes and Definitions	283
Sample Management Records	284
Chain of Custody	285

AECOM
 40 British American Boulevard
 Latham, NY 12110

Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French

Beacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Sample Summary

Lab Sample ID	Client Sample ID	Received	Analysis	Matrix
0007994-01 Sampler Type:	Trip 1 Beacon Passive Sampler	09/06/2024	EPA 8260C	Air
0007994-02 Sampler Type:	Trip 2 Beacon Passive Sampler	09/06/2024	EPA 8260C	Air
0007994-03 Sampler Type:	Trip 3 Beacon Passive Sampler	09/06/2024	EPA 8260C	Air
0007994-04 Sampler Type:	Trip 4 Beacon Passive Sampler	09/06/2024	EPA 8260C	Air
0007994-05 Sampler Type:	Trip 5 Beacon Passive Sampler	09/06/2024	EPA 8260C	Air
0007994-06 Sampler Type:	SGP-A1 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-07 Sampler Type:	SGP-A2 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-08 Sampler Type:	SGP-A3 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-09 Sampler Type:	SGP-A4 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-10 Sampler Type:	SGP-A5 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-11 Sampler Type:	SGP-A6 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-12 Sampler Type:	SGP-A7 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-13 Sampler Type:	SGP-A8 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-14 Sampler Type:	SGP-B1 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-15 Sampler Type:	SGP-B1-DUP Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-16 Sampler Type:	SGP-B2 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-17 Sampler Type:	SGP-B3 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-18 Sampler Type:	SGP-B4 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-19 Sampler Type:	SGP-B5 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-20 Sampler Type:	SGP-B6 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas

AECOM
 40 British American Boulevard
 Latham, NY 12110

Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French

Beacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID	Client Sample ID	Received	Analysis	Matrix
0007994-21 Sampler Type:	SGP-B7 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-22 Sampler Type:	SGP-B8 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-23 Sampler Type:	SGP-B9 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-24 Sampler Type:	SGP-C1 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-25 Sampler Type:	SGP-C2 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-26 Sampler Type:	SGP-C3 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-27 Sampler Type:	SGP-C4 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-28 Sampler Type:	SGP-C5 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-29 Sampler Type:	SGP-C6 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-30 Sampler Type:	SGP-C7 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-31 Sampler Type:	SGP-C8 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-32 Sampler Type:	SGP-C9 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-33 Sampler Type:	SGP-C10 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-34 Sampler Type:	SGP-D1 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-35 Sampler Type:	SGP-D2 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-36 Sampler Type:	SGP-E1 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-37 Sampler Type:	SGP-E2 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-38 Sampler Type:	SGP-E3 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-39 Sampler Type:	SGP-F1 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-40 Sampler Type:	SGP-F2 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-41 Sampler Type:	SGP-G1 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas

AECOM
 40 British American Boulevard
 Latham, NY 12110

Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French

Beacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID	Client Sample ID	Received	Analysis	Matrix
0007994-42 Sampler Type:	SGP-G2 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-43 Sampler Type:	SGP-H1 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-44 Sampler Type:	SGP-H2 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-45 Sampler Type:	SGP-H3 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-46 Sampler Type:	SGP-H4 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-47 Sampler Type:	SGP-H5 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-48 Sampler Type:	SGP-H6 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-49 Sampler Type:	SGP-H6-DUP Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-50 Sampler Type:	SGP-H7 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-51 Sampler Type:	SGP-H8 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-52 Sampler Type:	SGP-I1 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-53 Sampler Type:	SGP-I2 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-54 Sampler Type:	SGP-I3 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-55 Sampler Type:	SGP-I4 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-56 Sampler Type:	SGP-I5 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-57 Sampler Type:	SGP-I6 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-58 Sampler Type:	SGP-I7 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-59 Sampler Type:	SGP-I8 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-60 Sampler Type:	SGP-J0 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-61 Sampler Type:	SGP-J00 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-62 Sampler Type:	SGP-J1 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas

AECOM
 40 British American Boulevard
 Latham, NY 12110

Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French

Beacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID	Client Sample ID	Received	Analysis	Matrix
0007994-63 Sampler Type:	SGP-J2 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-64 Sampler Type:	SGP-J3 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-65 Sampler Type:	SGP-J4 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-66 Sampler Type:	SGP-J5 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-67 Sampler Type:	SGP-J6 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-68 Sampler Type:	SGP-J7 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-69 Sampler Type:	SGP-K0 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-70 Sampler Type:	SGP-K00 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-71 Sampler Type:	SGP-K1 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-72 Sampler Type:	SGP-K1-DUP Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-73 Sampler Type:	SGP-K2 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-74 Sampler Type:	SGP-K3 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-75 Sampler Type:	SGP-K4 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-76 Sampler Type:	SGP-K5 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-77 Sampler Type:	SGP-K6 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-78 Sampler Type:	SGP-K7 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-79 Sampler Type:	SGP-K8 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-80 Sampler Type:	SGP-L1 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-81 Sampler Type:	SGP-L2 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-82 Sampler Type:	SGP-L3 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-83 Sampler Type:	SGP-L4 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas

AECOM
 40 British American Boulevard
 Latham, NY 12110

Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French

Beacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID	Client Sample ID	Received	Analysis	Matrix
0007994-84 Sampler Type:	SGP-L5 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-85 Sampler Type:	SGP-L6 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-86 Sampler Type:	SGP-L7 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-87 Sampler Type:	SGP-M0 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-88 Sampler Type:	SGP-M1 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-89 Sampler Type:	SGP-M1-DUP Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-90 Sampler Type:	SGP-M2 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-91 Sampler Type:	SGP-M3 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-92 Sampler Type:	SGP-M4 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-93 Sampler Type:	SGP-M5 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-94 Sampler Type:	SGP-M6 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-95 Sampler Type:	SGP-M7 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-96 Sampler Type:	SGP-M8 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-97 Sampler Type:	SGP-N1 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-98 Sampler Type:	SGP-N2 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-99 Sampler Type:	SGP-N3 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-AA Sampler Type:	SGP-N4 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-AB Sampler Type:	SGP-N5 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-AC Sampler Type:	SGP-N6 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-AD Sampler Type:	SGP-N7 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-AE Sampler Type:	SGP-O1 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas

AECOM
 40 British American Boulevard
 Latham, NY 12110

Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French

Beacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID	Client Sample ID	Received	Analysis	Matrix
0007994-AF Sampler Type:	SGP-O2 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-AG Sampler Type:	SGP-O3 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-AH Sampler Type:	SGP-O4 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-AI Sampler Type:	SGP-O5 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-AJ Sampler Type:	SGP-O6 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-AK Sampler Type:	SGP-O7 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-AL Sampler Type:	SGP-O8 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-AM Sampler Type:	SGP-O8-DUP Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-AN Sampler Type:	SGP-O9 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-AO Sampler Type:	SGP-O10 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-AP Sampler Type:	SGP-O11 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-AQ Sampler Type:	SGP-O12 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-AR Sampler Type:	SGP-O13 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-AS Sampler Type:	SGP-O14 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-AT Sampler Type:	SGP-P1 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-AU Sampler Type:	SGP-P2 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-AV Sampler Type:	SGP-P3 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-AW Sampler Type:	SGP-P4 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-AX Sampler Type:	SGP-P4-DUP Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-AY Sampler Type:	SGP-P5 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-AZ Sampler Type:	SGP-Q1 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas

AECOM
 40 British American Boulevard
 Latham, NY 12110

Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French

Beacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID	Client Sample ID	Received	Analysis	Matrix
0007994-BA Sampler Type:	SGP-Q2 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-BB Sampler Type:	SGP-Q3 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-BC Sampler Type:	SGP-R1 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-BD Sampler Type:	SGP-R2 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-BE Sampler Type:	SGP-R3 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-BF Sampler Type:	SGP-R4 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-BG Sampler Type:	SGP-R4-DUP Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-BH Sampler Type:	SGP-S1 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-BI Sampler Type:	SGP-S2 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-BJ Sampler Type:	SGP-S3 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-BK Sampler Type:	SGP-T1 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-BL Sampler Type:	SGP-T2 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-BM Sampler Type:	SGP-T3 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-BN Sampler Type:	SGP-U1 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-BO Sampler Type:	SGP-U2 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-BP Sampler Type:	SGP-U3 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-BQ Sampler Type:	SGP-V1 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-BR Sampler Type:	SGP-V2 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-BS Sampler Type:	SGP-V3 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-BT Sampler Type:	SGP-W1 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-BU Sampler Type:	SGP-W2 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas

AECOM
 40 British American Boulevard
 Latham, NY 12110

Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French

Beacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID	Client Sample ID	Received	Analysis	Matrix
0007994-BV Sampler Type:	SGP-X1 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-BW Sampler Type:	SGP-X2 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-BX Sampler Type:	SGP-Y1 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-BY Sampler Type:	SGP-Y2 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-BZ Sampler Type:	SGP-Z1 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-CA Sampler Type:	SGP-Z2 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-CB Sampler Type:	SGP-Z3 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-CC Sampler Type:	SGP-AA1 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-CD Sampler Type:	SGP-AA1-DUP Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-CE Sampler Type:	SGP-AA2 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-CF Sampler Type:	SGP-AA3 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-CG Sampler Type:	SGP-BB1 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-CH Sampler Type:	SGP-BB2 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-CI Sampler Type:	SGP-BB3 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-CJ Sampler Type:	SGP-CC1 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-CK Sampler Type:	SGP-CC2 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-CL Sampler Type:	SGP-CC3 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-CM Sampler Type:	SGP-CC4 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-CN Sampler Type:	SGP-CC5 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-CO Sampler Type:	SGP-CC5-DUP Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-CP Sampler Type:	SGP-DD1 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas

AECOM
 40 British American Boulevard
 Latham, NY 12110

Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French

Beacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID	Client Sample ID	Received	Analysis	Matrix
0007994-CQ Sampler Type:	SGP-DD2 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-CR Sampler Type:	SGP-DD3 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-CS Sampler Type:	SGP-DD4 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-CT Sampler Type:	SGP-DD5 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-CU Sampler Type:	SGP-DD6 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-CV Sampler Type:	SGP-EE1 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-CW Sampler Type:	SGP-EE2 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-CX Sampler Type:	SGP-EE3 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-CY Sampler Type:	SGP-EE4 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-CZ Sampler Type:	SGP-EE5 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-DA Sampler Type:	SGP-EE6 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-DB Sampler Type:	SGP-FF1 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-DC Sampler Type:	SGP-FF2 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-DD Sampler Type:	SGP-FF3 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-DE Sampler Type:	SGP-FF3-DUP Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-DF Sampler Type:	SGP-FF4 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-DG Sampler Type:	SGP-FF5 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-DH Sampler Type:	SGP-GG1 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-DI Sampler Type:	SGP-GG2 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-DJ Sampler Type:	SGP-GG3 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-DK Sampler Type:	SGP-GG4 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas

AECOM
 40 British American Boulevard
 Latham, NY 12110

Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French

Beacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID	Client Sample ID	Received	Analysis	Matrix
0007994-DL Sampler Type:	SGP-HH1 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-DM Sampler Type:	SGP-HH2 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-DN Sampler Type:	SGP-HH3 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-DO Sampler Type:	SGP-II1 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-DP Sampler Type:	SGP-II2 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-DQ Sampler Type:	SGP-II3 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-DR Sampler Type:	SGP-II4 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-DS Sampler Type:	SGP-JJ1 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-DT Sampler Type:	SGP-JJ2 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-DU Sampler Type:	SGP-KK1 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-DV Sampler Type:	SGP-KK2 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-DW Sampler Type:	SGP-LL1 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-DX Sampler Type:	SGP-MM1 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-DY Sampler Type:	SGP-MM2 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-DZ Sampler Type:	SGP-MM3 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-EA Sampler Type:	SGP-NN1 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-EB Sampler Type:	SGP-NN2 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas
0007994-EC Sampler Type:	SGP-NN3 Beacon Passive Sampler	09/06/2024	EPA 8260C	Soil Gas

Project Completeness
Samples Received: 206
Samples Analyzed: 206

AECOM
40 British American Boulevard
Latham, NY 12110

Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French

Beacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Case Narrative

U.S. EPA Method 8260C

All samples were analyzed using thermal desorption-gas chromatography/mass spectrometry (TD-GC/MS) instrumentation following U.S. EPA Method 8260C, with laboratory results provided in nanograms (ng). Laboratory QA/QC procedures included internal standards, surrogates, and blanks based on EPA Method 8260C. Analyses and reporting were in accordance with BEACON's Quality Assurance Project Plan.

Passive Soil-Gas Survey Notes

If sample locations are covered with or near the edge of an impervious surface (*e.g.*, asphalt or concrete), the concentrations of compounds in soil gas are higher than if the surfacing was not present. Therefore, the sample location conditions should be considered when comparing results between locations.

Survey findings are exclusive to this project and when the spatial relationships are compared with results of other BEACON Surveys it is necessary to incorporate information from both investigations (*e.g.*, depth to sources, soil types, porosity, soil moisture, presence of impervious surfacing, sample collection times).

Reporting Limits

The RLs represent a baseline above which results meet laboratory-determined limits of precision and accuracy. Field sample measurements above the upper calibration standard are estimated; however, these values are reported without qualifiers because all reported measurements are relative to each other and are appropriate to meet the survey objectives of locating source areas and vapor intrusion pathways and defining the lateral extent of the contamination.

Project Details

Samples were received in proper condition and laboratory control parameters were met unless otherwise noted below. The work performed was in accordance with ISO/IEC 17025:2017, except samples were analyzed within a 24-hour tune window.

AECOM
40 British American Boulevard
Latham, NY 12110

Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French

Beacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

AECOM
40 British American Boulevard
Latham, NY 12110

Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French

Beacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

AECOM
40 British American Boulevard
Latham, NY 12110

Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French

Beacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Analytical Results

AECOM
40 British American Boulevard
Latham, NY 12110

Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French

Beacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Summary of Compound Detections - Mass

Lab Sample ID:	0007994-09	SGP-A4	Method:	EPA 8260C
Soil Gas				

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
Trichloroethene	79-01-6	36		4.258	10	09/09/2024 18:07	S24090913.D

Lab Sample ID:	0007994-11	SGP-A6	Method:	EPA 8260C
Soil Gas				

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
1,1-Dichloroethene	75-35-4	28		2.205	10	09/09/2024 19:14	S24090915.D
trans-1,2-Dichloroethene	156-60-5	50		2.609	10	09/09/2024 19:14	S24090915.D
cis-1,2-Dichloroethene	156-59-2	303		3.198	10	09/09/2024 19:14	S24090915.D
Trichloroethene	79-01-6	2,390		4.255	10	09/09/2024 19:14	S24090915.D

Lab Sample ID:	0007994-19	SGP-B5	Method:	EPA 8260C
Soil Gas				

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
cis-1,2-Dichloroethene	156-59-2	13		3.198	10	09/09/2024 23:27	S24090923.D
Trichloroethene	79-01-6	140		4.258	10	09/09/2024 23:27	S24090923.D

Lab Sample ID:	0007994-21	SGP-B7	Method:	EPA 8260C
Soil Gas				

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
cis-1,2-Dichloroethene	156-59-2	43		3.198	10	09/10/2024 01:34	S24090927.D
Trichloroethene	79-01-6	741		4.255	10	09/10/2024 01:34	S24090927.D

AECOM
40 British American Boulevard
Latham, NY 12110

Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French

Beacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID:	0007994-22	SGP-B8	Method:	EPA 8260C
Soil Gas				

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
Trichloroethene	79-01-6	20		4.255	10	09/10/2024 02:05	S24090928.D

Lab Sample ID:	0007994-28	SGP-C5	Method:	EPA 8260C
Soil Gas				

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
cis-1,2-Dichloroethene	156-59-2	23		3.199	10	09/10/2024 05:12	S24090934.D
Trichloroethene	79-01-6	282		4.255	10	09/10/2024 05:12	S24090934.D
Tetrachloroethene	127-18-4	1,060		5.771	10	09/10/2024 05:12	S24090934.D

Lab Sample ID:	0007994-30	SGP-C7	Method:	EPA 8260C
Soil Gas				

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
Trichloroethene	79-01-6	27		4.258	10	09/10/2024 06:15	S24090936.D

Lab Sample ID:	0007994-36	SGP-E1	Method:	EPA 8260C
Soil Gas				

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	153		1.616	10	09/10/2024 09:23	S24090942.D
1,1-Dichloroethene	75-35-4	258		2.205	10	09/10/2024 09:23	S24090942.D
trans-1,2-Dichloroethene	156-60-5	129		2.609	10	09/10/2024 09:23	S24090942.D
cis-1,2-Dichloroethene	156-59-2	767		3.198	10	09/10/2024 09:23	S24090942.D
Trichloroethene	79-01-6	1,300		4.255	10	09/10/2024 09:23	S24090942.D

AECOM
 40 British American Boulevard
 Latham, NY 12110

Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French

Beacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID:	0007994-39	SGP-F1	Method:	EPA 8260C
Soil Gas				

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	11		1.616	10	09/10/2024 10:59	S24090945.D
1,1-Dichloroethene	75-35-4	31		2.202	10	09/10/2024 10:59	S24090945.D
trans-1,2-Dichloroethene	156-60-5	27		2.603	10	09/10/2024 10:59	S24090945.D
cis-1,2-Dichloroethene	156-59-2	164		3.198	10	09/10/2024 10:59	S24090945.D
Trichloroethene	79-01-6	1,180		4.255	10	09/10/2024 10:59	S24090945.D

Lab Sample ID:	0007994-41	SGP-G1	Method:	EPA 8260C
Soil Gas				

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	20		1.57	10	09/09/2024 22:10	C24090917.D
1,1-Dichloroethene	75-35-4	18		2.16	10	09/09/2024 22:10	C24090917.D
trans-1,2-Dichloroethene	156-60-5	484		2.566	10	09/09/2024 22:10	C24090917.D
cis-1,2-Dichloroethene	156-59-2	3,280		3.162	10	09/09/2024 22:10	C24090917.D
Trichloroethene	79-01-6	1,140		4.222	10	09/09/2024 22:10	C24090917.D

Lab Sample ID:	0007994-42	SGP-G2	Method:	EPA 8260C
Soil Gas				

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
trans-1,2-Dichloroethene	156-60-5	14		2.563	10	09/09/2024 22:45	C24090918.D
cis-1,2-Dichloroethene	156-59-2	104		3.159	10	09/09/2024 22:45	C24090918.D
Trichloroethene	79-01-6	285		4.222	10	09/09/2024 22:45	C24090918.D

AECOM
 40 British American Boulevard
 Latham, NY 12110

Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French

Beacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID:	0007994-43	SGP-H1	Method:	EPA 8260C
Soil Gas				

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	13		1.57	10	09/09/2024 23:20	C24090919.D
1,1-Dichloroethene	75-35-4	47		2.16	10	09/09/2024 23:20	C24090919.D
cis-1,2-Dichloroethene	156-59-2	15		3.16	10	09/09/2024 23:20	C24090919.D
1,1,1-Trichloroethane	71-55-6	45		3.489	10	09/09/2024 23:20	C24090919.D
Trichloroethene	79-01-6	282		4.219	10	09/09/2024 23:20	C24090919.D

Lab Sample ID:	0007994-44	SGP-H2	Method:	EPA 8260C
Soil Gas				

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	310		1.57	10	09/09/2024 23:55	C24090920.D
1,1-Dichloroethene	75-35-4	1,120		2.16	10	09/09/2024 23:55	C24090920.D
trans-1,2-Dichloroethene	156-60-5	76		2.566	10	09/09/2024 23:55	C24090920.D
cis-1,2-Dichloroethene	156-59-2	471		3.163	10	09/09/2024 23:55	C24090920.D
1,1,1-Trichloroethane	71-55-6	1,710		3.492	10	09/09/2024 23:55	C24090920.D
Trichloroethene	79-01-6	8,050		4.222	10	09/09/2024 23:55	C24090920.D
Tetrachloroethene	127-18-4	14		5.739	10	09/09/2024 23:55	C24090920.D

Lab Sample ID:	0007994-45	SGP-H3	Method:	EPA 8260C
Soil Gas				

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	96		1.57	10	09/10/2024 00:30	C24090921.D
1,1-Dichloroethene	75-35-4	300		2.16	10	09/10/2024 00:30	C24090921.D
trans-1,2-Dichloroethene	156-60-5	43		2.566	10	09/10/2024 00:30	C24090921.D
cis-1,2-Dichloroethene	156-59-2	238		3.163	10	09/10/2024 00:30	C24090921.D
1,1,1-Trichloroethane	71-55-6	289		3.493	10	09/10/2024 00:30	C24090921.D
Trichloroethene	79-01-6	2,500		4.222	10	09/10/2024 00:30	C24090921.D

AECOM
40 British American Boulevard
Latham, NY 12110Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris FrenchBeacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-46

SGP-H4

Method:

EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	27		1.57	10	09/10/2024 01:05	C24090922.D
1,1-Dichloroethene	75-35-4	36		2.16	10	09/10/2024 01:05	C24090922.D
trans-1,2-Dichloroethene	156-60-5	98		2.566	10	09/10/2024 01:05	C24090922.D
cis-1,2-Dichloroethene	156-59-2	799		3.163	10	09/10/2024 01:05	C24090922.D
Trichloroethene	79-01-6	287		4.222	10	09/10/2024 01:05	C24090922.D

Lab Sample ID: 0007994-47

SGP-H5

Method:

EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	93		1.573	10	09/10/2024 01:41	C24090923.D
1,1-Dichloroethene	75-35-4	171		2.16	10	09/10/2024 01:41	C24090923.D
trans-1,2-Dichloroethene	156-60-5	351		2.566	10	09/10/2024 01:41	C24090923.D
cis-1,2-Dichloroethene	156-59-2	2,810		3.163	10	09/10/2024 01:41	C24090923.D
Trichloroethene	79-01-6	5,580		4.222	10	09/10/2024 01:41	C24090923.D

Lab Sample ID: 0007994-48

SGP-H6

Method:

EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	32		1.57	10	09/10/2024 02:16	C24090924.D
trans-1,2-Dichloroethene	156-60-5	25		2.566	10	09/10/2024 02:16	C24090924.D
cis-1,2-Dichloroethene	156-59-2	97		3.162	10	09/10/2024 02:16	C24090924.D
Trichloroethene	79-01-6	396		4.222	10	09/10/2024 02:16	C24090924.D

AECOM
40 British American Boulevard
Latham, NY 12110

Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French

Beacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID:	0007994-49	SGP-H6-DUP	Method:	EPA 8260C
Soil Gas				

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	35		1.573	10	09/10/2024 02:51	C24090925.D
trans-1,2-Dichloroethene	156-60-5	23		2.563	10	09/10/2024 02:51	C24090925.D
cis-1,2-Dichloroethene	156-59-2	91		3.163	10	09/10/2024 02:51	C24090925.D
Trichloroethene	79-01-6	385		4.219	10	09/10/2024 02:51	C24090925.D

Lab Sample ID:	0007994-50	SGP-H7	Method:	EPA 8260C
Soil Gas				

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	534		1.573	10	09/10/2024 03:26	C24090926.D
1,1-Dichloroethene	75-35-4	281		2.16	10	09/10/2024 03:26	C24090926.D
trans-1,2-Dichloroethene	156-60-5	303		2.566	10	09/10/2024 03:26	C24090926.D
cis-1,2-Dichloroethene	156-59-2	2,520		3.162	10	09/10/2024 03:26	C24090926.D
Trichloroethene	79-01-6	899		4.219	10	09/10/2024 03:26	C24090926.D

Lab Sample ID:	0007994-51	SGP-H8	Method:	EPA 8260C
Soil Gas				

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	55		1.573	10	09/10/2024 04:02	C24090927.D
trans-1,2-Dichloroethene	156-60-5	103		2.563	10	09/10/2024 04:02	C24090927.D
cis-1,2-Dichloroethene	156-59-2	915		3.162	10	09/10/2024 04:02	C24090927.D
Trichloroethene	79-01-6	18		4.222	10	09/10/2024 04:02	C24090927.D

AECOM
40 British American Boulevard
Latham, NY 12110

Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French

Beacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID:	0007994-52	SGP-I1	Method:	EPA 8260C
Soil Gas				

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	23		1.573	10	09/10/2024 04:37	C24090928.D
1,1-Dichloroethene	75-35-4	116		2.157	10	09/10/2024 04:37	C24090928.D
cis-1,2-Dichloroethene	156-59-2	31		3.163	10	09/10/2024 04:37	C24090928.D
1,1,1-Trichloroethane	71-55-6	141		3.493	10	09/10/2024 04:37	C24090928.D
Trichloroethene	79-01-6	377		4.222	10	09/10/2024 04:37	C24090928.D

Lab Sample ID:	0007994-53	SGP-I2	Method:	EPA 8260C
Soil Gas				

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	34		1.573	10	09/10/2024 05:12	C24090929.D
1,1-Dichloroethene	75-35-4	95		2.163	10	09/10/2024 05:12	C24090929.D
cis-1,2-Dichloroethene	156-59-2	17		3.166	10	09/10/2024 05:12	C24090929.D
1,1,1-Trichloroethane	71-55-6	106		3.489	10	09/10/2024 05:12	C24090929.D
Trichloroethene	79-01-6	232		4.219	10	09/10/2024 05:12	C24090929.D

Lab Sample ID:	0007994-54	SGP-I3	Method:	EPA 8260C
Soil Gas				

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
cis-1,2-Dichloroethene	156-59-2	30		3.166	10	09/10/2024 05:47	C24090930.D
Trichloroethene	79-01-6	457		4.219	10	09/10/2024 05:47	C24090930.D

AECOM
40 British American Boulevard
Latham, NY 12110

Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French

Beacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID:	0007994-55	SGP-I4	Method:	EPA 8260C
Soil Gas				

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
1,1-Dichloroethene	75-35-4	18		2.16	10	09/10/2024 06:22	C24090931.D
cis-1,2-Dichloroethene	156-59-2	46		3.162	10	09/10/2024 06:22	C24090931.D
Trichloroethene	79-01-6	847		4.222	10	09/10/2024 06:22	C24090931.D
Tetrachloroethene	127-18-4	16		5.739	10	09/10/2024 06:22	C24090931.D

Lab Sample ID:	0007994-56	SGP-I5	Method:	EPA 8260C
Soil Gas				

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
Trichloroethene	79-01-6	21		4.222	10	09/10/2024 06:58	C24090932.D

Lab Sample ID:	0007994-57	SGP-I6	Method:	EPA 8260C
Soil Gas				

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
Trichloroethene	79-01-6	20		4.219	10	09/10/2024 07:33	C24090933.D

Lab Sample ID:	0007994-59	SGP-I8	Method:	EPA 8260C
Soil Gas				

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	190		1.57	10	09/10/2024 08:43	C24090935.D
1,1-Dichloroethene	75-35-4	527		2.16	10	09/10/2024 08:43	C24090935.D
cis-1,2-Dichloroethene	156-59-2	55		3.163	10	09/10/2024 08:43	C24090935.D
1,1,1-Trichloroethane	71-55-6	614		3.493	10	09/10/2024 08:43	C24090935.D

AECOM
40 British American Boulevard
Latham, NY 12110Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris FrenchBeacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID:	0007994-60	SGP-J0	Method:	EPA 8260C
Soil Gas				

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	11		1.573	10	09/10/2024 09:18	C24090936.D
1,1-Dichloroethene	75-35-4	33		2.163	10	09/10/2024 09:18	C24090936.D
1,1,1-Trichloroethane	71-55-6	48		3.493	10	09/10/2024 09:18	C24090936.D

Lab Sample ID:	0007994-64	SGP-J3	Method:	EPA 8260C
Soil Gas				

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
1,1-Dichloroethene	75-35-4	19		2.208	10	09/10/2024 16:02	S24091008.D
trans-1,2-Dichloroethene	156-60-5	39		2.609	10	09/10/2024 16:02	S24091008.D
cis-1,2-Dichloroethene	156-59-2	352		3.201	10	09/10/2024 16:02	S24091008.D
1,1,1-Trichloroethane	71-55-6	11		3.526	10	09/10/2024 16:02	S24091008.D
Trichloroethene	79-01-6	988		4.255	10	09/10/2024 16:02	S24091008.D

Lab Sample ID:	0007994-65	SGP-J4	Method:	EPA 8260C
Soil Gas				

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
1,1-Dichloroethene	75-35-4	15		2.205	10	09/10/2024 16:33	S24091009.D
cis-1,2-Dichloroethene	156-59-2	39		3.198	10	09/10/2024 16:33	S24091009.D
Trichloroethene	79-01-6	76		4.258	10	09/10/2024 16:33	S24091009.D

Lab Sample ID:	0007994-66	SGP-J5	Method:	EPA 8260C
Soil Gas				

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
1,1-Dichloroethene	75-35-4	30		2.205	10	09/10/2024 17:04	S24091010.D
1,1,1-Trichloroethane	71-55-6	22		3.533	10	09/10/2024 17:04	S24091010.D
Trichloroethene	79-01-6	27		4.259	10	09/10/2024 17:04	S24091010.D

AECOM
40 British American Boulevard
Latham, NY 12110

Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French

Beacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID:	0007994-67	SGP-J6	Method:	EPA 8260C
Soil Gas				

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
1,1-Dichloroethene	75-35-4	25		2.205	10	09/10/2024 17:35	S24091011.D
cis-1,2-Dichloroethene	156-59-2	38		3.198	10	09/10/2024 17:35	S24091011.D
1,1,1-Trichloroethane	71-55-6	18		3.529	10	09/10/2024 17:35	S24091011.D
Trichloroethene	79-01-6	671		4.255	10	09/10/2024 17:35	S24091011.D

Lab Sample ID:	0007994-68	SGP-J7	Method:	EPA 8260C
Soil Gas				

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
1,1-Dichloroethene	75-35-4	13		2.205	10	09/10/2024 18:06	S24091012.D
Trichloroethene	79-01-6	45		4.259	10	09/10/2024 18:06	S24091012.D

Lab Sample ID:	0007994-71	SGP-K1	Method:	EPA 8260C
Soil Gas				

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
cis-1,2-Dichloroethene	156-59-2	10		3.198	10	09/10/2024 19:42	S24091015.D

Lab Sample ID:	0007994-74	SGP-K3	Method:	EPA 8260C
Soil Gas				

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	35		1.616	10	09/10/2024 21:16	S24091018.D
1,1-Dichloroethene	75-35-4	77		2.205	10	09/10/2024 21:16	S24091018.D
1,1,1-Trichloroethane	71-55-6	94		3.53	10	09/10/2024 21:16	S24091018.D
Trichloroethene	79-01-6	25		4.255	10	09/10/2024 21:16	S24091018.D

AECOM
40 British American Boulevard
Latham, NY 12110

Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French

Beacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID:	0007994-75	SGP-K4	Method:	EPA 8260C
Soil Gas				

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	44		1.613	10	09/10/2024 21:47	S24091019.D
1,1-Dichloroethene	75-35-4	119		2.205	10	09/10/2024 21:47	S24091019.D
1,1,1-Trichloroethane	71-55-6	152		3.533	10	09/10/2024 21:47	S24091019.D
Trichloroethene	79-01-6	14		4.255	10	09/10/2024 21:47	S24091019.D

Lab Sample ID:	0007994-76	SGP-K5	Method:	EPA 8260C
Soil Gas				

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	12		1.613	10	09/10/2024 22:18	S24091020.D
1,1-Dichloroethene	75-35-4	37		2.208	10	09/10/2024 22:18	S24091020.D
cis-1,2-Dichloroethene	156-59-2	10		3.201	10	09/10/2024 22:18	S24091020.D
1,1,1-Trichloroethane	71-55-6	30		3.529	10	09/10/2024 22:18	S24091020.D
Trichloroethene	79-01-6	152		4.255	10	09/10/2024 22:18	S24091020.D

Lab Sample ID:	0007994-77	SGP-K6	Method:	EPA 8260C
Soil Gas				

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	55		1.616	10	09/10/2024 22:49	S24091021.D
1,1-Dichloroethene	75-35-4	57		2.202	10	09/10/2024 22:49	S24091021.D
trans-1,2-Dichloroethene	156-60-5	109		2.609	10	09/10/2024 22:49	S24091021.D
cis-1,2-Dichloroethene	156-59-2	595		3.198	10	09/10/2024 22:49	S24091021.D
Trichloroethene	79-01-6	4,140		4.258	10	09/10/2024 22:49	S24091021.D
Tetrachloroethene	127-18-4	10		5.77	10	09/10/2024 22:49	S24091021.D

AECOM
40 British American Boulevard
Latham, NY 12110

Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French

Beacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID:	0007994-78	SGP-K7	Method:	EPA 8260C
Soil Gas				

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	14		1.616	10	09/10/2024 23:21	S24091022.D
1,1-Dichloroethene	75-35-4	35		2.202	10	09/10/2024 23:21	S24091022.D
cis-1,2-Dichloroethene	156-59-2	45		3.198	10	09/10/2024 23:21	S24091022.D
1,1,1-Trichloroethane	71-55-6	27		3.529	10	09/10/2024 23:21	S24091022.D
Trichloroethene	79-01-6	520		4.255	10	09/10/2024 23:21	S24091022.D

Lab Sample ID:	0007994-79	SGP-K8	Method:	EPA 8260C
Soil Gas				

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	32		1.613	10	09/10/2024 23:52	S24091023.D
1,1-Dichloroethene	75-35-4	37		2.205	10	09/10/2024 23:52	S24091023.D
cis-1,2-Dichloroethene	156-59-2	47		3.198	10	09/10/2024 23:52	S24091023.D
1,1,1-Trichloroethane	71-55-6	57		3.529	10	09/10/2024 23:52	S24091023.D
Trichloroethene	79-01-6	543		4.255	10	09/10/2024 23:52	S24091023.D
Tetrachloroethene	127-18-4	56		5.771	10	09/10/2024 23:52	S24091023.D

Lab Sample ID:	0007994-80	SGP-L1	Method:	EPA 8260C
Soil Gas				

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	31		1.616	10	09/11/2024 00:24	S24091024.D
1,1-Dichloroethene	75-35-4	37		2.205	10	09/11/2024 00:24	S24091024.D
1,1,1-Trichloroethane	71-55-6	34		3.529	10	09/11/2024 00:24	S24091024.D
Trichloroethene	79-01-6	18		4.258	10	09/11/2024 00:24	S24091024.D

AECOM
40 British American Boulevard
Latham, NY 12110

Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French

Beacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID:	0007994-81	SGP-L2	Method:	EPA 8260C
Soil Gas				

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	11		1.616	10	09/11/2024 01:59	S24091027.D
1,1-Dichloroethene	75-35-4	27		2.205	10	09/11/2024 01:59	S24091027.D
1,1,1-Trichloroethane	71-55-6	32		3.533	10	09/11/2024 01:59	S24091027.D

Lab Sample ID:	0007994-82	SGP-L3	Method:	EPA 8260C
Soil Gas				

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	41		1.616	10	09/11/2024 02:31	S24091028.D
1,1-Dichloroethene	75-35-4	101		2.205	10	09/11/2024 02:31	S24091028.D
1,1,1-Trichloroethane	71-55-6	161		3.53	10	09/11/2024 02:31	S24091028.D
Trichloroethene	79-01-6	43		4.258	10	09/11/2024 02:31	S24091028.D

Lab Sample ID:	0007994-83	SGP-L4	Method:	EPA 8260C
Soil Gas				

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	43		1.616	10	09/11/2024 03:04	S24091029.D
1,1-Dichloroethene	75-35-4	123		2.205	10	09/11/2024 03:04	S24091029.D
1,1,1-Trichloroethane	71-55-6	159		3.532	10	09/11/2024 03:04	S24091029.D

AECOM
40 British American Boulevard
Latham, NY 12110

Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French

Beacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID:	0007994-84	SGP-L5	Method:	EPA 8260C
Soil Gas				

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	33		1.616	10	09/11/2024 03:36	S24091030.D
1,1-Dichloroethene	75-35-4	43		2.205	10	09/11/2024 03:36	S24091030.D
trans-1,2-Dichloroethene	156-60-5	11		2.61	10	09/11/2024 03:36	S24091030.D
cis-1,2-Dichloroethene	156-59-2	64		3.198	10	09/11/2024 03:36	S24091030.D
1,1,1-Trichloroethane	71-55-6	27		3.533	10	09/11/2024 03:36	S24091030.D
Trichloroethene	79-01-6	442		4.259	10	09/11/2024 03:36	S24091030.D

Lab Sample ID:	0007994-85	SGP-L6	Method:	EPA 8260C
Soil Gas				

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	22		1.616	10	09/11/2024 04:07	S24091031.D
1,1-Dichloroethene	75-35-4	45		2.205	10	09/11/2024 04:07	S24091031.D
cis-1,2-Dichloroethene	156-59-2	12		3.198	10	09/11/2024 04:07	S24091031.D
1,1,1-Trichloroethane	71-55-6	27		3.529	10	09/11/2024 04:07	S24091031.D
Trichloroethene	79-01-6	81		4.255	10	09/11/2024 04:07	S24091031.D

Lab Sample ID:	0007994-86	SGP-L7	Method:	EPA 8260C
Soil Gas				

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	483		1.616	10	09/11/2024 04:38	S24091032.D
1,1-Dichloroethene	75-35-4	58		2.208	10	09/11/2024 04:38	S24091032.D
trans-1,2-Dichloroethene	156-60-5	81		2.609	10	09/11/2024 04:38	S24091032.D
cis-1,2-Dichloroethene	156-59-2	707		3.202	10	09/11/2024 04:38	S24091032.D
1,1,1-Trichloroethane	71-55-6	23		3.533	10	09/11/2024 04:38	S24091032.D
Trichloroethene	79-01-6	477		4.255	10	09/11/2024 04:38	S24091032.D
Tetrachloroethene	127-18-4	486		5.771	10	09/11/2024 04:38	S24091032.D

AECOM
40 British American Boulevard
Latham, NY 12110

Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French

Beacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID:	0007994-87	SGP-M0	Method:	EPA 8260C
Soil Gas				

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	27		1.616	10	09/11/2024 05:09	S24091033.D
1,1-Dichloroethene	75-35-4	35		2.208	10	09/11/2024 05:09	S24091033.D
cis-1,2-Dichloroethene	156-59-2	31		3.202	10	09/11/2024 05:09	S24091033.D
1,1,1-Trichloroethane	71-55-6	26		3.533	10	09/11/2024 05:09	S24091033.D
Trichloroethene	79-01-6	402		4.259	10	09/11/2024 05:09	S24091033.D

Lab Sample ID:	0007994-88	SGP-M1	Method:	EPA 8260C
Soil Gas				

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
1,1,1-Trichloroethane	71-55-6	17		3.53	10	09/11/2024 05:42	S24091034.D
Trichloroethene	79-01-6	144		4.255	10	09/11/2024 05:42	S24091034.D

Lab Sample ID:	0007994-89	SGP-M1-DUP	Method:	EPA 8260C
Soil Gas				

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
cis-1,2-Dichloroethene	156-59-2	11		3.198	10	09/11/2024 06:13	S24091035.D
1,1,1-Trichloroethane	71-55-6	24		3.529	10	09/11/2024 06:13	S24091035.D
Trichloroethene	79-01-6	165		4.255	10	09/11/2024 06:13	S24091035.D

AECOM
40 British American Boulevard
Latham, NY 12110

Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French

Beacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID:	0007994-90	SGP-M2	Method:	EPA 8260C
Soil Gas				

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	13		1.616	10	09/11/2024 06:45	S24091036.D
1,1-Dichloroethene	75-35-4	29		2.208	10	09/11/2024 06:45	S24091036.D
cis-1,2-Dichloroethene	156-59-2	13		3.198	10	09/11/2024 06:45	S24091036.D
1,1,1-Trichloroethane	71-55-6	44		3.529	10	09/11/2024 06:45	S24091036.D
Trichloroethene	79-01-6	163		4.255	10	09/11/2024 06:45	S24091036.D

Lab Sample ID:	0007994-91	SGP-M3	Method:	EPA 8260C
Soil Gas				

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	339		1.613	10	09/11/2024 07:17	S24091037.D
1,1-Dichloroethene	75-35-4	1,650		2.205	10	09/11/2024 07:17	S24091037.D
trans-1,2-Dichloroethene	156-60-5	70		2.609	10	09/11/2024 07:17	S24091037.D
cis-1,2-Dichloroethene	156-59-2	365		3.198	10	09/11/2024 07:17	S24091037.D
1,1,1-Trichloroethane	71-55-6	2,230		3.533	10	09/11/2024 07:17	S24091037.D
Trichloroethene	79-01-6	9,990		4.258	10	09/11/2024 07:17	S24091037.D
Tetrachloroethene	127-18-4	88		5.77	10	09/11/2024 07:17	S24091037.D

Lab Sample ID:	0007994-92	SGP-M4	Method:	EPA 8260C
Soil Gas				

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	99		1.616	10	09/11/2024 07:50	S24091038.D
1,1-Dichloroethene	75-35-4	346		2.205	10	09/11/2024 07:50	S24091038.D
cis-1,2-Dichloroethene	156-59-2	41		3.198	10	09/11/2024 07:50	S24091038.D
1,1,1-Trichloroethane	71-55-6	521		3.529	10	09/11/2024 07:50	S24091038.D
Trichloroethene	79-01-6	987		4.255	10	09/11/2024 07:50	S24091038.D
Tetrachloroethene	127-18-4	24		5.767	10	09/11/2024 07:50	S24091038.D

AECOM
 40 British American Boulevard
 Latham, NY 12110

Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French

Beacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID:	0007994-93	SGP-M5	Method:	EPA 8260C
Soil Gas				

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	323		1.613	10	09/11/2024 08:22	S24091039.D
1,1-Dichloroethene	75-35-4	1,260		2.205	10	09/11/2024 08:22	S24091039.D
trans-1,2-Dichloroethene	156-60-5	42		2.609	10	09/11/2024 08:22	S24091039.D
cis-1,2-Dichloroethene	156-59-2	236		3.198	10	09/11/2024 08:22	S24091039.D
1,1,1-Trichloroethane	71-55-6	2,450		3.533	10	09/11/2024 08:22	S24091039.D
Trichloroethene	79-01-6	5,580		4.258	10	09/11/2024 08:22	S24091039.D
Tetrachloroethene	127-18-4	30		5.771	10	09/11/2024 08:22	S24091039.D

Lab Sample ID:	0007994-94	SGP-M6	Method:	EPA 8260C
Soil Gas				

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	117		1.613	10	09/11/2024 08:53	S24091040.D
1,1-Dichloroethene	75-35-4	216		2.205	10	09/11/2024 08:53	S24091040.D
trans-1,2-Dichloroethene	156-60-5	41		2.609	10	09/11/2024 08:53	S24091040.D
cis-1,2-Dichloroethene	156-59-2	275		3.198	10	09/11/2024 08:53	S24091040.D
1,1,1-Trichloroethane	71-55-6	170		3.529	10	09/11/2024 08:53	S24091040.D
Trichloroethene	79-01-6	1,900		4.255	10	09/11/2024 08:53	S24091040.D

Lab Sample ID:	0007994-95	SGP-M7	Method:	EPA 8260C
Soil Gas				

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	289		1.613	10	09/11/2024 09:25	S24091041.D
1,1-Dichloroethene	75-35-4	189		2.205	10	09/11/2024 09:25	S24091041.D
trans-1,2-Dichloroethene	156-60-5	143		2.609	10	09/11/2024 09:25	S24091041.D
cis-1,2-Dichloroethene	156-59-2	1,340		3.198	10	09/11/2024 09:25	S24091041.D
1,1,1-Trichloroethane	71-55-6	147		3.533	10	09/11/2024 09:25	S24091041.D
Trichloroethene	79-01-6	2,110		4.255	10	09/11/2024 09:25	S24091041.D

AECOM
40 British American Boulevard
Latham, NY 12110

Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French

Beacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID:	0007994-96	SGP-M8	Method:	EPA 8260C
Soil Gas				

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	163		1.613	10	09/11/2024 09:57	S24091042.D
1,1-Dichloroethene	75-35-4	244		2.205	10	09/11/2024 09:57	S24091042.D
trans-1,2-Dichloroethene	156-60-5	89		2.613	10	09/11/2024 09:57	S24091042.D
cis-1,2-Dichloroethene	156-59-2	583		3.198	10	09/11/2024 09:57	S24091042.D
1,1,1-Trichloroethane	71-55-6	198		3.533	10	09/11/2024 09:57	S24091042.D
Trichloroethene	79-01-6	5,020		4.255	10	09/11/2024 09:57	S24091042.D
Tetrachloroethene	127-18-4	28		5.77	10	09/11/2024 09:57	S24091042.D

Lab Sample ID:	0007994-97	SGP-N1	Method:	EPA 8260C
Soil Gas				

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	18		1.616	10	09/11/2024 10:29	S24091043.D
1,1-Dichloroethene	75-35-4	19		2.208	10	09/11/2024 10:29	S24091043.D
cis-1,2-Dichloroethene	156-59-2	24		3.198	10	09/11/2024 10:29	S24091043.D
Trichloroethene	79-01-6	149		4.255	10	09/11/2024 10:29	S24091043.D

Lab Sample ID:	0007994-98	SGP-N2	Method:	EPA 8260C
Soil Gas				

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	32		1.613	10	09/11/2024 11:01	S24091044.D
1,1-Dichloroethene	75-35-4	22		2.205	10	09/11/2024 11:01	S24091044.D
cis-1,2-Dichloroethene	156-59-2	15		3.198	10	09/11/2024 11:01	S24091044.D
1,1,1-Trichloroethane	71-55-6	22		3.533	10	09/11/2024 11:01	S24091044.D
Trichloroethene	79-01-6	167		4.255	10	09/11/2024 11:01	S24091044.D

AECOM
 40 British American Boulevard
 Latham, NY 12110

Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French

Beacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID:	0007994-AA	SGP-N4	Method:	EPA 8260C
Soil Gas				

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	332		1.613	10	09/11/2024 12:05	S24091046.D
1,1-Dichloroethene	75-35-4	2,140		2.205	10	09/11/2024 12:05	S24091046.D
trans-1,2-Dichloroethene	156-60-5	32		2.609	10	09/11/2024 12:05	S24091046.D
cis-1,2-Dichloroethene	156-59-2	176		3.198	10	09/11/2024 12:05	S24091046.D
1,1,1-Trichloroethane	71-55-6	3,460		3.533	10	09/11/2024 12:05	S24091046.D
Trichloroethene	79-01-6	5,150		4.255	10	09/11/2024 12:05	S24091046.D
Tetrachloroethene	127-18-4	138		5.771	10	09/11/2024 12:05	S24091046.D

Lab Sample ID:	0007994-AB	SGP-N5	Method:	EPA 8260C
Soil Gas				

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	866		1.57	10	09/10/2024 16:18	C24091005.D
1,1-Dichloroethene	75-35-4	9,290		2.16	10	09/10/2024 16:18	C24091005.D
trans-1,2-Dichloroethene	156-60-5	119		2.566	10	09/10/2024 16:18	C24091005.D
cis-1,2-Dichloroethene	156-59-2	673		3.163	10	09/10/2024 16:18	C24091005.D
1,1,1-Trichloroethane	71-55-6	12,400		3.493	10	09/10/2024 16:18	C24091005.D
Trichloroethene	79-01-6	15,200		4.226	10	09/10/2024 16:18	C24091005.D
Tetrachloroethene	127-18-4	84		5.739	10	09/10/2024 16:18	C24091005.D

AECOM
40 British American Boulevard
Latham, NY 12110Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris FrenchBeacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID:	0007994-AC	SGP-N6	Method:	EPA 8260C
Soil Gas				

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	588		1.57	10	09/10/2024 16:53	C24091006.D
1,1-Dichloroethene	75-35-4	4,520		2.16	10	09/10/2024 16:53	C24091006.D
trans-1,2-Dichloroethene	156-60-5	249		2.566	10	09/10/2024 16:53	C24091006.D
cis-1,2-Dichloroethene	156-59-2	1,600		3.162	10	09/10/2024 16:53	C24091006.D
1,1,1-Trichloroethane	71-55-6	3,510		3.492	10	09/10/2024 16:53	C24091006.D
Trichloroethene	79-01-6	13,300		4.225	10	09/10/2024 16:53	C24091006.D
Tetrachloroethene	127-18-4	44		5.738	10	09/10/2024 16:53	C24091006.D

Lab Sample ID:	0007994-AD	SGP-N7	Method:	EPA 8260C
Soil Gas				

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	411		1.573	10	09/10/2024 17:28	C24091007.D
1,1-Dichloroethene	75-35-4	2,640		2.16	10	09/10/2024 17:28	C24091007.D
trans-1,2-Dichloroethene	156-60-5	116		2.566	10	09/10/2024 17:28	C24091007.D
cis-1,2-Dichloroethene	156-59-2	666		3.163	10	09/10/2024 17:28	C24091007.D
1,1,1-Trichloroethane	71-55-6	4,670		3.493	10	09/10/2024 17:28	C24091007.D
Trichloroethene	79-01-6	15,100		4.226	10	09/10/2024 17:28	C24091007.D
Tetrachloroethene	127-18-4	69		5.739	10	09/10/2024 17:28	C24091007.D

Lab Sample ID:	0007994-AH	SGP-O4	Method:	EPA 8260C
Soil Gas				

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
cis-1,2-Dichloroethene	156-59-2	21		3.163	10	09/10/2024 19:48	C24091011.D
Trichloroethene	79-01-6	51		4.219	10	09/10/2024 19:48	C24091011.D

AECOM
40 British American Boulevard
Latham, NY 12110

Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French

Beacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID:	0007994-AI	SGP-O5	Method:	EPA 8260C
Soil Gas				

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
Trichloroethene	79-01-6	26		4.219	10	09/10/2024 20:24	C24091012.D

Lab Sample ID:	0007994-AJ	SGP-O6	Method:	EPA 8260C
Soil Gas				

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
Trichloroethene	79-01-6	27		4.222	10	09/10/2024 20:59	C24091013.D

Lab Sample ID:	0007994-AT	SGP-P1	Method:	EPA 8260C
Soil Gas				

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
cis-1,2-Dichloroethene	156-59-2	10		3.162	10	09/11/2024 02:51	C24091023.D
Trichloroethene	79-01-6	105		4.222	10	09/11/2024 02:51	C24091023.D

Lab Sample ID:	0007994-AY	SGP-P5	Method:	EPA 8260C
Soil Gas				

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
Tetrachloroethene	127-18-4	17		5.739	10	09/11/2024 07:01	C24091030.D

Lab Sample ID:	0007994-AZ	SGP-Q1	Method:	EPA 8260C
Soil Gas				

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
1,1-Dichloroethene	75-35-4	12		2.163	10	09/11/2024 07:36	C24091031.D
cis-1,2-Dichloroethene	156-59-2	32		3.162	10	09/11/2024 07:36	C24091031.D
Trichloroethene	79-01-6	605		4.222	10	09/11/2024 07:36	C24091031.D

AECOM
40 British American Boulevard
Latham, NY 12110

Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French

Beacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID:	0007994-BA	SGP-Q2	Method:	EPA 8260C
Soil Gas				

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
Trichloroethene	79-01-6	28		4.225	10	09/11/2024 08:11	C24091032.D

Lab Sample ID:	0007994-BC	SGP-R1	Method:	EPA 8260C
Soil Gas				

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	249		1.57	10	09/11/2024 09:22	C24091034.D
1,1-Dichloroethene	75-35-4	3,300		2.16	10	09/11/2024 09:22	C24091034.D
1,1,1-Trichloroethane	71-55-6	1,230		3.492	10	09/11/2024 09:22	C24091034.D

Lab Sample ID:	0007994-BH	SGP-S1	Method:	EPA 8260C
Soil Gas				

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	29		1.616	10	09/11/2024 16:12	S24091107.D
1,1-Dichloroethene	75-35-4	36		2.205	10	09/11/2024 16:12	S24091107.D
trans-1,2-Dichloroethene	156-60-5	79		2.609	10	09/11/2024 16:12	S24091107.D
cis-1,2-Dichloroethene	156-59-2	259		3.198	10	09/11/2024 16:12	S24091107.D
Trichloroethene	79-01-6	4,470		4.255	10	09/11/2024 16:12	S24091107.D

Lab Sample ID:	0007994-BI	SGP-S2	Method:	EPA 8260C
Soil Gas				

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
cis-1,2-Dichloroethene	156-59-2	13		3.202	10	09/11/2024 16:43	S24091108.D
Trichloroethene	79-01-6	107		4.255	10	09/11/2024 16:43	S24091108.D

AECOM
40 British American Boulevard
Latham, NY 12110Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris FrenchBeacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID:	0007994-BK	SGP-T1	Method:	EPA 8260C
Soil Gas				

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	12		1.613	10	09/11/2024 17:46	S24091110.D
1,1-Dichloroethene	75-35-4	20		2.205	10	09/11/2024 17:46	S24091110.D
cis-1,2-Dichloroethene	156-59-2	26		3.198	10	09/11/2024 17:46	S24091110.D
Trichloroethene	79-01-6	368		4.255	10	09/11/2024 17:46	S24091110.D

Lab Sample ID:	0007994-BN	SGP-U1	Method:	EPA 8260C
Soil Gas				

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	132		1.616	10	09/11/2024 19:22	S24091113.D
1,1-Dichloroethene	75-35-4	243		2.205	10	09/11/2024 19:22	S24091113.D
trans-1,2-Dichloroethene	156-60-5	43		2.609	10	09/11/2024 19:22	S24091113.D
cis-1,2-Dichloroethene	156-59-2	131		3.198	10	09/11/2024 19:22	S24091113.D
1,1,1-Trichloroethane	71-55-6	130		3.529	10	09/11/2024 19:22	S24091113.D
Trichloroethene	79-01-6	624		4.255	10	09/11/2024 19:22	S24091113.D

Lab Sample ID:	0007994-BO	SGP-U2	Method:	EPA 8260C
Soil Gas				

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
1,1-Dichloroethene	75-35-4	13		2.212	10	09/11/2024 19:54	S24091114.D
cis-1,2-Dichloroethene	156-59-2	34		3.202	10	09/11/2024 19:54	S24091114.D
Trichloroethene	79-01-6	587		4.255	10	09/11/2024 19:54	S24091114.D

AECOM
40 British American Boulevard
Latham, NY 12110

Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French

Beacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID:	0007994-BQ	SGP-V1	Method:	EPA 8260C
Soil Gas				

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
cis-1,2-Dichloroethene	156-59-2	36		3.199	10	09/11/2024 20:58	S24091116.D
Trichloroethene	79-01-6	834		4.255	10	09/11/2024 20:58	S24091116.D

Lab Sample ID:	0007994-BR	SGP-V2	Method:	EPA 8260C
Soil Gas				

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
1,1-Dichloroethene	75-35-4	13		2.205	10	09/11/2024 21:29	S24091117.D
cis-1,2-Dichloroethene	156-59-2	29		3.198	10	09/11/2024 21:29	S24091117.D
Trichloroethene	79-01-6	1,010		4.255	10	09/11/2024 21:29	S24091117.D

Lab Sample ID:	0007994-BV	SGP-X1	Method:	EPA 8260C
Soil Gas				

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
Trichloroethene	79-01-6	29		4.255	10	09/11/2024 23:36	S24091121.D

Lab Sample ID:	0007994-BZ	SGP-Z1	Method:	EPA 8260C
Soil Gas				

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
cis-1,2-Dichloroethene	156-59-2	17		3.198	10	09/12/2024 02:26	S24091127.D
Trichloroethene	79-01-6	306		4.258	10	09/12/2024 02:26	S24091127.D

AECOM
40 British American Boulevard
Latham, NY 12110

Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French

Beacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID:	0007994-CC	SGP-AA1	Method:	EPA 8260C
Soil Gas				

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
trans-1,2-Dichloroethene	156-60-5	13		2.609	10	09/12/2024 03:55	S24091130.D
cis-1,2-Dichloroethene	156-59-2	83		3.198	10	09/12/2024 03:55	S24091130.D
Trichloroethene	79-01-6	748		4.255	10	09/12/2024 03:55	S24091130.D

Lab Sample ID:	0007994-CD	SGP-AA1-DUP	Method:	EPA 8260C
Soil Gas				

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
trans-1,2-Dichloroethene	156-60-5	12		2.609	10	09/12/2024 04:25	S24091131.D
cis-1,2-Dichloroethene	156-59-2	74		3.201	10	09/12/2024 04:25	S24091131.D
Trichloroethene	79-01-6	715		4.258	10	09/12/2024 04:25	S24091131.D

Lab Sample ID:	0007994-CE	SGP-AA2	Method:	EPA 8260C
Soil Gas				

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
cis-1,2-Dichloroethene	156-59-2	30		3.201	10	09/12/2024 04:55	S24091132.D
Trichloroethene	79-01-6	272		4.255	10	09/12/2024 04:55	S24091132.D

Lab Sample ID:	0007994-CF	SGP-AA3	Method:	EPA 8260C
Soil Gas				

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
1,1-Dichloroethene	75-35-4	15		2.202	10	09/12/2024 05:24	S24091133.D
cis-1,2-Dichloroethene	156-59-2	40		3.201	10	09/12/2024 05:24	S24091133.D
Trichloroethene	79-01-6	708		4.255	10	09/12/2024 05:24	S24091133.D

AECOM
40 British American Boulevard
Latham, NY 12110

Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French

Beacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID:	0007994-CG	SGP-BB1	Method:	EPA 8260C
Soil Gas				

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
1,1-Dichloroethene	75-35-4	436		2.205	10	09/12/2024 05:54	S24091134.D
trans-1,2-Dichloroethene	156-60-5	635		2.61	10	09/12/2024 05:54	S24091134.D
cis-1,2-Dichloroethene	156-59-2	5,730		3.202	10	09/12/2024 05:54	S24091134.D
Trichloroethene	79-01-6	38,300		4.284	10	09/12/2024 05:54	S24091134.D
Tetrachloroethene	127-18-4	79		5.771	10	09/12/2024 05:54	S24091134.D

Lab Sample ID:	0007994-CH	SGP-BB2	Method:	EPA 8260C
Soil Gas				

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
1,1-Dichloroethene	75-35-4	15		2.205	10	09/12/2024 06:23	S24091135.D
trans-1,2-Dichloroethene	156-60-5	13		2.613	10	09/12/2024 06:23	S24091135.D
cis-1,2-Dichloroethene	156-59-2	68		3.198	10	09/12/2024 06:23	S24091135.D
Trichloroethene	79-01-6	1,330		4.255	10	09/12/2024 06:23	S24091135.D

Lab Sample ID:	0007994-CI	SGP-BB3	Method:	EPA 8260C
Soil Gas				

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
1,1-Dichloroethene	75-35-4	27		2.202	10	09/12/2024 06:53	S24091136.D
trans-1,2-Dichloroethene	156-60-5	24		2.613	10	09/12/2024 06:53	S24091136.D
cis-1,2-Dichloroethene	156-59-2	127		3.198	10	09/12/2024 06:53	S24091136.D
Trichloroethene	79-01-6	1,920		4.255	10	09/12/2024 06:53	S24091136.D

Lab Sample ID:	0007994-CJ	SGP-CC1	Method:	EPA 8260C
Soil Gas				

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
Trichloroethene	79-01-6	118		4.258	10	09/12/2024 07:23	S24091137.D

AECOM
40 British American Boulevard
Latham, NY 12110

Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French

Beacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID:	0007994-CK	SGP-CC2	Method:	EPA 8260C
Soil Gas				

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
1,1-Dichloroethene	75-35-4	23		2.205	10	09/12/2024 07:53	S24091138.D
trans-1,2-Dichloroethene	156-60-5	94		2.612	10	09/12/2024 07:53	S24091138.D
cis-1,2-Dichloroethene	156-59-2	933		3.198	10	09/12/2024 07:53	S24091138.D
Trichloroethene	79-01-6	2,320		4.258	10	09/12/2024 07:53	S24091138.D

Lab Sample ID:	0007994-CL	SGP-CC3	Method:	EPA 8260C
Soil Gas				

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
trans-1,2-Dichloroethene	156-60-5	15		2.613	10	09/12/2024 08:22	S24091139.D
cis-1,2-Dichloroethene	156-59-2	103		3.202	10	09/12/2024 08:22	S24091139.D
Trichloroethene	79-01-6	777		4.255	10	09/12/2024 08:22	S24091139.D
Tetrachloroethene	127-18-4	28		5.767	10	09/12/2024 08:22	S24091139.D

Lab Sample ID:	0007994-CM	SGP-CC4	Method:	EPA 8260C
Soil Gas				

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
1,1-Dichloroethene	75-35-4	27		2.205	10	09/12/2024 08:52	S24091140.D
trans-1,2-Dichloroethene	156-60-5	51		2.61	10	09/12/2024 08:52	S24091140.D
cis-1,2-Dichloroethene	156-59-2	258		3.198	10	09/12/2024 08:52	S24091140.D
Trichloroethene	79-01-6	2,330		4.258	10	09/12/2024 08:52	S24091140.D

Lab Sample ID:	0007994-CN	SGP-CC5	Method:	EPA 8260C
Soil Gas				

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
Trichloroethene	79-01-6	41		4.255	10	09/12/2024 09:22	S24091141.D

AECOM
40 British American Boulevard
Latham, NY 12110Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris FrenchBeacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID:	0007994-CO	SGP-CC5-DUP	Method:	EPA 8260C
Soil Gas				

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
Trichloroethene	79-01-6	41		4.255	10	09/12/2024 09:52	S24091142.D

Lab Sample ID:	0007994-CP	SGP-DD1	Method:	EPA 8260C
Soil Gas				

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
Trichloroethene	79-01-6	95		4.258	10	09/12/2024 10:21	S24091143.D

Lab Sample ID:	0007994-CQ	SGP-DD2	Method:	EPA 8260C
Soil Gas				

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
cis-1,2-Dichloroethene	156-59-2	57		3.198	10	09/12/2024 10:51	S24091144.D
Trichloroethene	79-01-6	759		4.255	10	09/12/2024 10:51	S24091144.D

Lab Sample ID:	0007994-CR	SGP-DD3	Method:	EPA 8260C
Soil Gas				

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
cis-1,2-Dichloroethene	156-59-2	21		3.202	10	09/12/2024 11:20	S24091145.D
Trichloroethene	79-01-6	122		4.258	10	09/12/2024 11:20	S24091145.D

Lab Sample ID:	0007994-CS	SGP-DD4	Method:	EPA 8260C
Soil Gas				

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
Trichloroethene	79-01-6	11		4.258	10	09/12/2024 11:49	S24091146.D

AECOM
 40 British American Boulevard
 Latham, NY 12110

Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French

Beacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID:	0007994-CT	SGP-DD5	Method:	EPA 8260C
Soil Gas				

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
Trichloroethene	79-01-6	62		4.222	10	09/11/2024 13:42	C24091105.D
Tetrachloroethene	127-18-4	11		5.742	10	09/11/2024 13:42	C24091105.D

Lab Sample ID:	0007994-CV	SGP-EE1	Method:	EPA 8260C
Soil Gas				

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
Trichloroethene	79-01-6	49		4.219	10	09/11/2024 14:52	C24091107.D

Lab Sample ID:	0007994-CW	SGP-EE2	Method:	EPA 8260C
Soil Gas				

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
Trichloroethene	79-01-6	19		4.219	10	09/11/2024 15:27	C24091108.D

Lab Sample ID:	0007994-CZ	SGP-EE5	Method:	EPA 8260C
Soil Gas				

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
Trichloroethene	79-01-6	20		4.222	10	09/11/2024 17:12	C24091111.D

Lab Sample ID:	0007994-DB	SGP-FF1	Method:	EPA 8260C
Soil Gas				

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
cis-1,2-Dichloroethene	156-59-2	21		3.163	10	09/11/2024 18:22	C24091113.D
Trichloroethene	79-01-6	89		4.222	10	09/11/2024 18:22	C24091113.D

AECOM
40 British American Boulevard
Latham, NY 12110

Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French

Beacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID:	0007994-DG	SGP-FF5	Method:	EPA 8260C
Soil Gas				

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
Trichloroethene	79-01-6	15		4.222	10	09/11/2024 21:19	C24091118.D

Lab Sample ID:	0007994-DH	SGP-GG1	Method:	EPA 8260C
Soil Gas				

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
Trichloroethene	79-01-6	46		4.222	10	09/11/2024 21:54	C24091119.D

Lab Sample ID:	0007994-DO	SGP-III	Method:	EPA 8260C
Soil Gas				

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	20		1.57	10	09/12/2024 03:12	C24091128.D
1,1-Dichloroethene	75-35-4	60		2.16	10	09/12/2024 03:12	C24091128.D
1,1,1-Trichloroethane	71-55-6	86		3.492	10	09/12/2024 03:12	C24091128.D
Trichloroethene	79-01-6	32		4.222	10	09/12/2024 03:12	C24091128.D
Tetrachloroethene	127-18-4	16		5.739	10	09/12/2024 03:12	C24091128.D

Lab Sample ID:	0007994-DP	SGP-II2	Method:	EPA 8260C
Soil Gas				

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
Trichloroethene	79-01-6	54		4.222	10	09/12/2024 03:47	C24091129.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID:	0007994-DS	SGP-JJ1	Method:	EPA 8260C
Soil Gas				

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
trans-1,2-Dichloroethene	156-60-5	10		2.566	10	09/12/2024 05:33	C24091132.D
cis-1,2-Dichloroethene	156-59-2	83		3.163	10	09/12/2024 05:33	C24091132.D
Trichloroethene	79-01-6	36		4.219	10	09/12/2024 05:33	C24091132.D

Lab Sample ID:	0007994-DU	SGP-KK1	Method:	EPA 8260C
Soil Gas				

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	39		1.573	10	09/12/2024 06:43	C24091134.D
cis-1,2-Dichloroethene	156-59-2	15		3.162	10	09/12/2024 06:43	C24091134.D
Trichloroethene	79-01-6	113		4.222	10	09/12/2024 06:43	C24091134.D

Lab Sample ID:	0007994-DW	SGP-LL1	Method:	EPA 8260C
Soil Gas				

Analyte	CAS#	Result (ng)	Q	RT	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	19		1.573	10	09/12/2024 07:53	C24091136.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024***Data Summary Table- Mass***

Compound	Frequency	LOQ (ng)	Max Value (ng)
Vinyl Chloride	49	10	866
1,1-Dichloroethene	61	10	9,290
trans-1,2-Dichloroethene	35	10	635
cis-1,2-Dichloroethene	71	10	5,730
1,1,1-Trichloroethane	39	10	12,400
Trichloroethene	97	10	38,300
Tetrachloroethene	19	10	1,060

AECOM
40 British American Boulevard
Latham, NY 12110

Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French

Beacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Detailed Analytical Results

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-01

Trip 1

Method: EPA 8260C

Air

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/09/2024 13:53	S24090905.D
1,1-Dichloroethene	75-35-4	<10		10	09/09/2024 13:53	S24090905.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/09/2024 13:53	S24090905.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/09/2024 13:53	S24090905.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/09/2024 13:53	S24090905.D
Trichloroethene	79-01-6	<10		10	09/09/2024 13:53	S24090905.D
Tetrachloroethene	127-18-4	<10		10	09/09/2024 13:53	S24090905.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-02

Trip 2

Method: EPA 8260C

Air

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/09/2024 14:25	S24090906.D
1,1-Dichloroethene	75-35-4	<10		10	09/09/2024 14:25	S24090906.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/09/2024 14:25	S24090906.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/09/2024 14:25	S24090906.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/09/2024 14:25	S24090906.D
Trichloroethene	79-01-6	<10		10	09/09/2024 14:25	S24090906.D
Tetrachloroethene	127-18-4	<10		10	09/09/2024 14:25	S24090906.D

AECOM
40 British American Boulevard
Latham, NY 12110

Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French

Beacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-03

Trip 3

Method: EPA 8260C

Air

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/09/2024 14:57	S24090907.D
1,1-Dichloroethene	75-35-4	<10		10	09/09/2024 14:57	S24090907.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/09/2024 14:57	S24090907.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/09/2024 14:57	S24090907.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/09/2024 14:57	S24090907.D
Trichloroethene	79-01-6	<10		10	09/09/2024 14:57	S24090907.D
Tetrachloroethene	127-18-4	<10		10	09/09/2024 14:57	S24090907.D

AECOM
40 British American Boulevard
Latham, NY 12110

Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French

Beacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-04

Trip 4

Method: EPA 8260C

Air

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/09/2024 15:29	S24090908.D
1,1-Dichloroethene	75-35-4	<10		10	09/09/2024 15:29	S24090908.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/09/2024 15:29	S24090908.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/09/2024 15:29	S24090908.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/09/2024 15:29	S24090908.D
Trichloroethene	79-01-6	<10		10	09/09/2024 15:29	S24090908.D
Tetrachloroethene	127-18-4	<10		10	09/09/2024 15:29	S24090908.D



CERTIFICATE OF ANALYSIS

526 Underwood Lane
Bel Air, MD 21014 USA
1.410.838.8780

AECOM
40 British American Boulevard
Latham, NY 12110

Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French

Beacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-05	Trip 5	Method: EPA 8260C
Air		

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/09/2024 16:00	S24090909.D
1,1-Dichloroethene	75-35-4	<10		10	09/09/2024 16:00	S24090909.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/09/2024 16:00	S24090909.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/09/2024 16:00	S24090909.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/09/2024 16:00	S24090909.D
Trichloroethene	79-01-6	<10		10	09/09/2024 16:00	S24090909.D
Tetrachloroethene	127-18-4	<10		10	09/09/2024 16:00	S24090909.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-06

SGP-A1

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/09/2024 16:32	S24090910.D
1,1-Dichloroethene	75-35-4	<10		10	09/09/2024 16:32	S24090910.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/09/2024 16:32	S24090910.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/09/2024 16:32	S24090910.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/09/2024 16:32	S24090910.D
Trichloroethene	79-01-6	<10		10	09/09/2024 16:32	S24090910.D
Tetrachloroethene	127-18-4	<10		10	09/09/2024 16:32	S24090910.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-07

SGP-A2

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/09/2024 17:03	S24090911.D
1,1-Dichloroethene	75-35-4	<10		10	09/09/2024 17:03	S24090911.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/09/2024 17:03	S24090911.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/09/2024 17:03	S24090911.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/09/2024 17:03	S24090911.D
Trichloroethene	79-01-6	<10		10	09/09/2024 17:03	S24090911.D
Tetrachloroethene	127-18-4	<10		10	09/09/2024 17:03	S24090911.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-08

SGP-A3

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/09/2024 17:35	S24090912.D
1,1-Dichloroethene	75-35-4	<10		10	09/09/2024 17:35	S24090912.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/09/2024 17:35	S24090912.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/09/2024 17:35	S24090912.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/09/2024 17:35	S24090912.D
Trichloroethene	79-01-6	<10		10	09/09/2024 17:35	S24090912.D
Tetrachloroethene	127-18-4	<10		10	09/09/2024 17:35	S24090912.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-09

SGP-A4

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/09/2024 18:07	S24090913.D
1,1-Dichloroethene	75-35-4	<10		10	09/09/2024 18:07	S24090913.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/09/2024 18:07	S24090913.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/09/2024 18:07	S24090913.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/09/2024 18:07	S24090913.D
Trichloroethene	79-01-6	36		10	09/09/2024 18:07	S24090913.D
Tetrachloroethene	127-18-4	<10		10	09/09/2024 18:07	S24090913.D

AECOM
40 British American Boulevard
Latham, NY 12110

Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French

Beacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-10

SGP-A5

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/09/2024 18:39	S24090914.D
1,1-Dichloroethene	75-35-4	<10		10	09/09/2024 18:39	S24090914.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/09/2024 18:39	S24090914.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/09/2024 18:39	S24090914.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/09/2024 18:39	S24090914.D
Trichloroethene	79-01-6	<10		10	09/09/2024 18:39	S24090914.D
Tetrachloroethene	127-18-4	<10		10	09/09/2024 18:39	S24090914.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-11

SGP-A6

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/09/2024 19:14	S24090915.D
1,1-Dichloroethene	75-35-4	28		10	09/09/2024 19:14	S24090915.D
trans-1,2-Dichloroethene	156-60-5	50		10	09/09/2024 19:14	S24090915.D
cis-1,2-Dichloroethene	156-59-2	303		10	09/09/2024 19:14	S24090915.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/09/2024 19:14	S24090915.D
Trichloroethene	79-01-6	2,390		10	09/09/2024 19:14	S24090915.D
Tetrachloroethene	127-18-4	<10		10	09/09/2024 19:14	S24090915.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-12

SGP-A7

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/09/2024 19:46	S24090916.D
1,1-Dichloroethene	75-35-4	<10		10	09/09/2024 19:46	S24090916.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/09/2024 19:46	S24090916.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/09/2024 19:46	S24090916.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/09/2024 19:46	S24090916.D
Trichloroethene	79-01-6	<10		10	09/09/2024 19:46	S24090916.D
Tetrachloroethene	127-18-4	<10		10	09/09/2024 19:46	S24090916.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-13

SGP-A8

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/09/2024 20:18	S24090917.D
1,1-Dichloroethene	75-35-4	<10		10	09/09/2024 20:18	S24090917.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/09/2024 20:18	S24090917.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/09/2024 20:18	S24090917.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/09/2024 20:18	S24090917.D
Trichloroethene	79-01-6	<10		10	09/09/2024 20:18	S24090917.D
Tetrachloroethene	127-18-4	<10		10	09/09/2024 20:18	S24090917.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-14

SGP-B1

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/09/2024 20:51	S24090918.D
1,1-Dichloroethene	75-35-4	<10		10	09/09/2024 20:51	S24090918.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/09/2024 20:51	S24090918.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/09/2024 20:51	S24090918.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/09/2024 20:51	S24090918.D
Trichloroethene	79-01-6	<10		10	09/09/2024 20:51	S24090918.D
Tetrachloroethene	127-18-4	<10		10	09/09/2024 20:51	S24090918.D

AECOM
40 British American Boulevard
Latham, NY 12110Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris FrenchBeacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-15

SGP-B1-DUP

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/09/2024 21:22	S24090919.D
1,1-Dichloroethene	75-35-4	<10		10	09/09/2024 21:22	S24090919.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/09/2024 21:22	S24090919.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/09/2024 21:22	S24090919.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/09/2024 21:22	S24090919.D
Trichloroethene	79-01-6	<10		10	09/09/2024 21:22	S24090919.D
Tetrachloroethene	127-18-4	<10		10	09/09/2024 21:22	S24090919.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-16

SGP-B2

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/09/2024 21:53	S24090920.D
1,1-Dichloroethene	75-35-4	<10		10	09/09/2024 21:53	S24090920.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/09/2024 21:53	S24090920.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/09/2024 21:53	S24090920.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/09/2024 21:53	S24090920.D
Trichloroethene	79-01-6	<10		10	09/09/2024 21:53	S24090920.D
Tetrachloroethene	127-18-4	<10		10	09/09/2024 21:53	S24090920.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-17

SGP-B3

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/09/2024 22:25	S24090921.D
1,1-Dichloroethene	75-35-4	<10		10	09/09/2024 22:25	S24090921.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/09/2024 22:25	S24090921.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/09/2024 22:25	S24090921.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/09/2024 22:25	S24090921.D
Trichloroethene	79-01-6	<10		10	09/09/2024 22:25	S24090921.D
Tetrachloroethene	127-18-4	<10		10	09/09/2024 22:25	S24090921.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-18

SGP-B4

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/09/2024 22:56	S24090922.D
1,1-Dichloroethene	75-35-4	<10		10	09/09/2024 22:56	S24090922.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/09/2024 22:56	S24090922.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/09/2024 22:56	S24090922.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/09/2024 22:56	S24090922.D
Trichloroethene	79-01-6	<10		10	09/09/2024 22:56	S24090922.D
Tetrachloroethene	127-18-4	<10		10	09/09/2024 22:56	S24090922.D

AECOM
40 British American Boulevard
Latham, NY 12110Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris FrenchBeacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-19

SGP-B5

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/09/2024 23:27	S24090923.D
1,1-Dichloroethene	75-35-4	<10		10	09/09/2024 23:27	S24090923.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/09/2024 23:27	S24090923.D
cis-1,2-Dichloroethene	156-59-2	13		10	09/09/2024 23:27	S24090923.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/09/2024 23:27	S24090923.D
Trichloroethene	79-01-6	140		10	09/09/2024 23:27	S24090923.D
Tetrachloroethene	127-18-4	<10		10	09/09/2024 23:27	S24090923.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-20

SGP-B6

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/09/2024 23:58	S24090924.D
1,1-Dichloroethene	75-35-4	<10		10	09/09/2024 23:58	S24090924.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/09/2024 23:58	S24090924.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/09/2024 23:58	S24090924.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/09/2024 23:58	S24090924.D
Trichloroethene	79-01-6	<10		10	09/09/2024 23:58	S24090924.D
Tetrachloroethene	127-18-4	<10		10	09/09/2024 23:58	S24090924.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-21

SGP-B7

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/10/2024 01:34	S24090927.D
1,1-Dichloroethene	75-35-4	<10		10	09/10/2024 01:34	S24090927.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/10/2024 01:34	S24090927.D
cis-1,2-Dichloroethene	156-59-2	43		10	09/10/2024 01:34	S24090927.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/10/2024 01:34	S24090927.D
Trichloroethene	79-01-6	741		10	09/10/2024 01:34	S24090927.D
Tetrachloroethene	127-18-4	<10		10	09/10/2024 01:34	S24090927.D

AECOM
40 British American Boulevard
Latham, NY 12110Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris FrenchBeacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-22

SGP-B8

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/10/2024 02:05	S24090928.D
1,1-Dichloroethene	75-35-4	<10		10	09/10/2024 02:05	S24090928.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/10/2024 02:05	S24090928.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/10/2024 02:05	S24090928.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/10/2024 02:05	S24090928.D
Trichloroethene	79-01-6	20		10	09/10/2024 02:05	S24090928.D
Tetrachloroethene	127-18-4	<10		10	09/10/2024 02:05	S24090928.D

AECOM
40 British American Boulevard
Latham, NY 12110Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris FrenchBeacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-23

SGP-B9

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/10/2024 02:36	S24090929.D
1,1-Dichloroethene	75-35-4	<10		10	09/10/2024 02:36	S24090929.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/10/2024 02:36	S24090929.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/10/2024 02:36	S24090929.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/10/2024 02:36	S24090929.D
Trichloroethene	79-01-6	<10		10	09/10/2024 02:36	S24090929.D
Tetrachloroethene	127-18-4	<10		10	09/10/2024 02:36	S24090929.D



CERTIFICATE OF ANALYSIS

526 Underwood Lane
Bel Air, MD 21014 USA
1.410.838.8780

AECOM
40 British American Boulevard
Latham, NY 12110

Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French

Beacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-24	SGP-C1	Method: EPA 8260C
Soil Gas		

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/10/2024 03:07	S24090930.D
1,1-Dichloroethene	75-35-4	<10		10	09/10/2024 03:07	S24090930.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/10/2024 03:07	S24090930.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/10/2024 03:07	S24090930.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/10/2024 03:07	S24090930.D
Trichloroethene	79-01-6	<10		10	09/10/2024 03:07	S24090930.D
Tetrachloroethene	127-18-4	<10		10	09/10/2024 03:07	S24090930.D



CERTIFICATE OF ANALYSIS

526 Underwood Lane
Bel Air, MD 21014 USA
1.410.838.8780

AECOM
40 British American Boulevard
Latham, NY 12110

Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French

Beacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-25	SGP-C2	Method: EPA 8260C
Soil Gas		

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/10/2024 03:38	S24090931.D
1,1-Dichloroethene	75-35-4	<10		10	09/10/2024 03:38	S24090931.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/10/2024 03:38	S24090931.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/10/2024 03:38	S24090931.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/10/2024 03:38	S24090931.D
Trichloroethene	79-01-6	<10		10	09/10/2024 03:38	S24090931.D
Tetrachloroethene	127-18-4	<10		10	09/10/2024 03:38	S24090931.D

AECOM
40 British American Boulevard
Latham, NY 12110

Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French

Beacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-26

SGP-C3

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/10/2024 04:09	S24090932.D
1,1-Dichloroethene	75-35-4	<10		10	09/10/2024 04:09	S24090932.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/10/2024 04:09	S24090932.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/10/2024 04:09	S24090932.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/10/2024 04:09	S24090932.D
Trichloroethene	79-01-6	<10		10	09/10/2024 04:09	S24090932.D
Tetrachloroethene	127-18-4	<10		10	09/10/2024 04:09	S24090932.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-27

SGP-C4

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/10/2024 04:41	S24090933.D
1,1-Dichloroethene	75-35-4	<10		10	09/10/2024 04:41	S24090933.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/10/2024 04:41	S24090933.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/10/2024 04:41	S24090933.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/10/2024 04:41	S24090933.D
Trichloroethene	79-01-6	<10		10	09/10/2024 04:41	S24090933.D
Tetrachloroethene	127-18-4	<10		10	09/10/2024 04:41	S24090933.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-28

SGP-C5

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/10/2024 05:12	S24090934.D
1,1-Dichloroethene	75-35-4	<10		10	09/10/2024 05:12	S24090934.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/10/2024 05:12	S24090934.D
cis-1,2-Dichloroethene	156-59-2	23		10	09/10/2024 05:12	S24090934.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/10/2024 05:12	S24090934.D
Trichloroethene	79-01-6	282		10	09/10/2024 05:12	S24090934.D
Tetrachloroethene	127-18-4	1,060		10	09/10/2024 05:12	S24090934.D

AECOM
40 British American Boulevard
Latham, NY 12110

Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French

Beacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-29

SGP-C6

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/10/2024 05:44	S24090935.D
1,1-Dichloroethene	75-35-4	<10		10	09/10/2024 05:44	S24090935.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/10/2024 05:44	S24090935.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/10/2024 05:44	S24090935.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/10/2024 05:44	S24090935.D
Trichloroethene	79-01-6	<10		10	09/10/2024 05:44	S24090935.D
Tetrachloroethene	127-18-4	<10		10	09/10/2024 05:44	S24090935.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-30

SGP-C7

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/10/2024 06:15	S24090936.D
1,1-Dichloroethene	75-35-4	<10		10	09/10/2024 06:15	S24090936.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/10/2024 06:15	S24090936.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/10/2024 06:15	S24090936.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/10/2024 06:15	S24090936.D
Trichloroethene	79-01-6	27		10	09/10/2024 06:15	S24090936.D
Tetrachloroethene	127-18-4	<10		10	09/10/2024 06:15	S24090936.D



CERTIFICATE OF ANALYSIS

526 Underwood Lane
Bel Air, MD 21014 USA
1.410.838.8780

AECOM 40 British American Boulevard Latham, NY 12110	Site Name: NOW Corporation Site Location: Stratsburg, NY Project Manager: Chris French	Beacon Proposal: 240312R01 Lab Work Order: 0007994 Reported: 09/17/2024
---	---	--

Lab Sample ID: 0007994-31	SGP-C8	Method: EPA 8260C
Soil Gas		

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/10/2024 06:47	S24090937.D
1,1-Dichloroethene	75-35-4	<10		10	09/10/2024 06:47	S24090937.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/10/2024 06:47	S24090937.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/10/2024 06:47	S24090937.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/10/2024 06:47	S24090937.D
Trichloroethene	79-01-6	<10		10	09/10/2024 06:47	S24090937.D
Tetrachloroethene	127-18-4	<10		10	09/10/2024 06:47	S24090937.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-32

SGP-C9

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/10/2024 07:18	S24090938.D
1,1-Dichloroethene	75-35-4	<10		10	09/10/2024 07:18	S24090938.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/10/2024 07:18	S24090938.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/10/2024 07:18	S24090938.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/10/2024 07:18	S24090938.D
Trichloroethene	79-01-6	<10		10	09/10/2024 07:18	S24090938.D
Tetrachloroethene	127-18-4	<10		10	09/10/2024 07:18	S24090938.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-33

SGP-C10

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/10/2024 07:49	S24090939.D
1,1-Dichloroethene	75-35-4	<10		10	09/10/2024 07:49	S24090939.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/10/2024 07:49	S24090939.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/10/2024 07:49	S24090939.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/10/2024 07:49	S24090939.D
Trichloroethene	79-01-6	<10		10	09/10/2024 07:49	S24090939.D
Tetrachloroethene	127-18-4	<10		10	09/10/2024 07:49	S24090939.D

AECOM
40 British American Boulevard
Latham, NY 12110Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris FrenchBeacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-34

SGP-D1

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/10/2024 08:20	S24090940.D
1,1-Dichloroethene	75-35-4	<10		10	09/10/2024 08:20	S24090940.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/10/2024 08:20	S24090940.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/10/2024 08:20	S24090940.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/10/2024 08:20	S24090940.D
Trichloroethene	79-01-6	<10		10	09/10/2024 08:20	S24090940.D
Tetrachloroethene	127-18-4	<10		10	09/10/2024 08:20	S24090940.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-35

SGP-D2

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/10/2024 08:52	S24090941.D
1,1-Dichloroethene	75-35-4	<10		10	09/10/2024 08:52	S24090941.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/10/2024 08:52	S24090941.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/10/2024 08:52	S24090941.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/10/2024 08:52	S24090941.D
Trichloroethene	79-01-6	<10		10	09/10/2024 08:52	S24090941.D
Tetrachloroethene	127-18-4	<10		10	09/10/2024 08:52	S24090941.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-36

SGP-E1

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	153		10	09/10/2024 09:23	S24090942.D
1,1-Dichloroethene	75-35-4	258		10	09/10/2024 09:23	S24090942.D
trans-1,2-Dichloroethene	156-60-5	129		10	09/10/2024 09:23	S24090942.D
cis-1,2-Dichloroethene	156-59-2	767		10	09/10/2024 09:23	S24090942.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/10/2024 09:23	S24090942.D
Trichloroethene	79-01-6	1,300		10	09/10/2024 09:23	S24090942.D
Tetrachloroethene	127-18-4	<10		10	09/10/2024 09:23	S24090942.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-37

SGP-E2

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/10/2024 09:54	S24090943.D
1,1-Dichloroethene	75-35-4	<10		10	09/10/2024 09:54	S24090943.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/10/2024 09:54	S24090943.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/10/2024 09:54	S24090943.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/10/2024 09:54	S24090943.D
Trichloroethene	79-01-6	<10		10	09/10/2024 09:54	S24090943.D
Tetrachloroethene	127-18-4	<10		10	09/10/2024 09:54	S24090943.D

AECOM
40 British American Boulevard
Latham, NY 12110

Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French

Beacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-38

SGP-E3

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/10/2024 10:26	S24090944.D
1,1-Dichloroethene	75-35-4	<10		10	09/10/2024 10:26	S24090944.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/10/2024 10:26	S24090944.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/10/2024 10:26	S24090944.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/10/2024 10:26	S24090944.D
Trichloroethene	79-01-6	<10		10	09/10/2024 10:26	S24090944.D
Tetrachloroethene	127-18-4	<10		10	09/10/2024 10:26	S24090944.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-39

SGP-F1

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	11		10	09/10/2024 10:59	S24090945.D
1,1-Dichloroethene	75-35-4	31		10	09/10/2024 10:59	S24090945.D
trans-1,2-Dichloroethene	156-60-5	27		10	09/10/2024 10:59	S24090945.D
cis-1,2-Dichloroethene	156-59-2	164		10	09/10/2024 10:59	S24090945.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/10/2024 10:59	S24090945.D
Trichloroethene	79-01-6	1,180		10	09/10/2024 10:59	S24090945.D
Tetrachloroethene	127-18-4	<10		10	09/10/2024 10:59	S24090945.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-40

SGP-F2

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/10/2024 11:30	S24090946.D
1,1-Dichloroethene	75-35-4	<10		10	09/10/2024 11:30	S24090946.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/10/2024 11:30	S24090946.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/10/2024 11:30	S24090946.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/10/2024 11:30	S24090946.D
Trichloroethene	79-01-6	<10		10	09/10/2024 11:30	S24090946.D
Tetrachloroethene	127-18-4	<10		10	09/10/2024 11:30	S24090946.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-41

SGP-G1

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	20		10	09/09/2024 22:10	C24090917.D
1,1-Dichloroethene	75-35-4	18		10	09/09/2024 22:10	C24090917.D
trans-1,2-Dichloroethene	156-60-5	484		10	09/09/2024 22:10	C24090917.D
cis-1,2-Dichloroethene	156-59-2	3,280		10	09/09/2024 22:10	C24090917.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/09/2024 22:10	C24090917.D
Trichloroethene	79-01-6	1,140		10	09/09/2024 22:10	C24090917.D
Tetrachloroethene	127-18-4	<10		10	09/09/2024 22:10	C24090917.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-42

SGP-G2

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/09/2024 22:45	C24090918.D
1,1-Dichloroethene	75-35-4	<10		10	09/09/2024 22:45	C24090918.D
trans-1,2-Dichloroethene	156-60-5	14		10	09/09/2024 22:45	C24090918.D
cis-1,2-Dichloroethene	156-59-2	104		10	09/09/2024 22:45	C24090918.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/09/2024 22:45	C24090918.D
Trichloroethene	79-01-6	285		10	09/09/2024 22:45	C24090918.D
Tetrachloroethene	127-18-4	<10		10	09/09/2024 22:45	C24090918.D

AECOM
40 British American Boulevard
Latham, NY 12110Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris FrenchBeacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-43

SGP-H1

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	13		10	09/09/2024 23:20	C24090919.D
1,1-Dichloroethene	75-35-4	47		10	09/09/2024 23:20	C24090919.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/09/2024 23:20	C24090919.D
cis-1,2-Dichloroethene	156-59-2	15		10	09/09/2024 23:20	C24090919.D
1,1,1-Trichloroethane	71-55-6	45		10	09/09/2024 23:20	C24090919.D
Trichloroethene	79-01-6	282		10	09/09/2024 23:20	C24090919.D
Tetrachloroethene	127-18-4	<10		10	09/09/2024 23:20	C24090919.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-44

SGP-H2

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	310		10	09/09/2024 23:55	C24090920.D
1,1-Dichloroethene	75-35-4	1,120		10	09/09/2024 23:55	C24090920.D
trans-1,2-Dichloroethene	156-60-5	76		10	09/09/2024 23:55	C24090920.D
cis-1,2-Dichloroethene	156-59-2	471		10	09/09/2024 23:55	C24090920.D
1,1,1-Trichloroethane	71-55-6	1,710		10	09/09/2024 23:55	C24090920.D
Trichloroethene	79-01-6	8,050		10	09/09/2024 23:55	C24090920.D
Tetrachloroethene	127-18-4	14		10	09/09/2024 23:55	C24090920.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-45

SGP-H3

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	96		10	09/10/2024 00:30	C24090921.D
1,1-Dichloroethene	75-35-4	300		10	09/10/2024 00:30	C24090921.D
trans-1,2-Dichloroethene	156-60-5	43		10	09/10/2024 00:30	C24090921.D
cis-1,2-Dichloroethene	156-59-2	238		10	09/10/2024 00:30	C24090921.D
1,1,1-Trichloroethane	71-55-6	289		10	09/10/2024 00:30	C24090921.D
Trichloroethene	79-01-6	2,500		10	09/10/2024 00:30	C24090921.D
Tetrachloroethene	127-18-4	<10		10	09/10/2024 00:30	C24090921.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-46

SGP-H4

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	27		10	09/10/2024 01:05	C24090922.D
1,1-Dichloroethene	75-35-4	36		10	09/10/2024 01:05	C24090922.D
trans-1,2-Dichloroethene	156-60-5	98		10	09/10/2024 01:05	C24090922.D
cis-1,2-Dichloroethene	156-59-2	799		10	09/10/2024 01:05	C24090922.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/10/2024 01:05	C24090922.D
Trichloroethene	79-01-6	287		10	09/10/2024 01:05	C24090922.D
Tetrachloroethene	127-18-4	<10		10	09/10/2024 01:05	C24090922.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-47

SGP-H5

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	93		10	09/10/2024 01:41	C24090923.D
1,1-Dichloroethene	75-35-4	171		10	09/10/2024 01:41	C24090923.D
trans-1,2-Dichloroethene	156-60-5	351		10	09/10/2024 01:41	C24090923.D
cis-1,2-Dichloroethene	156-59-2	2,810		10	09/10/2024 01:41	C24090923.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/10/2024 01:41	C24090923.D
Trichloroethene	79-01-6	5,580		10	09/10/2024 01:41	C24090923.D
Tetrachloroethene	127-18-4	<10		10	09/10/2024 01:41	C24090923.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-48

SGP-H6

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	32		10	09/10/2024 02:16	C24090924.D
1,1-Dichloroethene	75-35-4	<10		10	09/10/2024 02:16	C24090924.D
trans-1,2-Dichloroethene	156-60-5	25		10	09/10/2024 02:16	C24090924.D
cis-1,2-Dichloroethene	156-59-2	97		10	09/10/2024 02:16	C24090924.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/10/2024 02:16	C24090924.D
Trichloroethene	79-01-6	396		10	09/10/2024 02:16	C24090924.D
Tetrachloroethene	127-18-4	<10		10	09/10/2024 02:16	C24090924.D

AECOM
40 British American Boulevard
Latham, NY 12110Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris FrenchBeacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-49

SGP-H6-DUP

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	35		10	09/10/2024 02:51	C24090925.D
1,1-Dichloroethene	75-35-4	<10		10	09/10/2024 02:51	C24090925.D
trans-1,2-Dichloroethene	156-60-5	23		10	09/10/2024 02:51	C24090925.D
cis-1,2-Dichloroethene	156-59-2	91		10	09/10/2024 02:51	C24090925.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/10/2024 02:51	C24090925.D
Trichloroethene	79-01-6	385		10	09/10/2024 02:51	C24090925.D
Tetrachloroethene	127-18-4	<10		10	09/10/2024 02:51	C24090925.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-50

SGP-H7

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	534		10	09/10/2024 03:26	C24090926.D
1,1-Dichloroethene	75-35-4	281		10	09/10/2024 03:26	C24090926.D
trans-1,2-Dichloroethene	156-60-5	303		10	09/10/2024 03:26	C24090926.D
cis-1,2-Dichloroethene	156-59-2	2,520		10	09/10/2024 03:26	C24090926.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/10/2024 03:26	C24090926.D
Trichloroethene	79-01-6	899		10	09/10/2024 03:26	C24090926.D
Tetrachloroethene	127-18-4	<10		10	09/10/2024 03:26	C24090926.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-51

SGP-H8

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	55		10	09/10/2024 04:02	C24090927.D
1,1-Dichloroethene	75-35-4	<10		10	09/10/2024 04:02	C24090927.D
trans-1,2-Dichloroethene	156-60-5	103		10	09/10/2024 04:02	C24090927.D
cis-1,2-Dichloroethene	156-59-2	915		10	09/10/2024 04:02	C24090927.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/10/2024 04:02	C24090927.D
Trichloroethene	79-01-6	18		10	09/10/2024 04:02	C24090927.D
Tetrachloroethene	127-18-4	<10		10	09/10/2024 04:02	C24090927.D

AECOM
 40 British American Boulevard
 Latham, NY 12110

Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French

Beacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-52

SGP-I1

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	23		10	09/10/2024 04:37	C24090928.D
1,1-Dichloroethene	75-35-4	116		10	09/10/2024 04:37	C24090928.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/10/2024 04:37	C24090928.D
cis-1,2-Dichloroethene	156-59-2	31		10	09/10/2024 04:37	C24090928.D
1,1,1-Trichloroethane	71-55-6	141		10	09/10/2024 04:37	C24090928.D
Trichloroethene	79-01-6	377		10	09/10/2024 04:37	C24090928.D
Tetrachloroethene	127-18-4	<10		10	09/10/2024 04:37	C24090928.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-53

SGP-I2

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	34		10	09/10/2024 05:12	C24090929.D
1,1-Dichloroethene	75-35-4	95		10	09/10/2024 05:12	C24090929.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/10/2024 05:12	C24090929.D
cis-1,2-Dichloroethene	156-59-2	17		10	09/10/2024 05:12	C24090929.D
1,1,1-Trichloroethane	71-55-6	106		10	09/10/2024 05:12	C24090929.D
Trichloroethene	79-01-6	232		10	09/10/2024 05:12	C24090929.D
Tetrachloroethene	127-18-4	<10		10	09/10/2024 05:12	C24090929.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-54

SGP-I3

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/10/2024 05:47	C24090930.D
1,1-Dichloroethene	75-35-4	<10		10	09/10/2024 05:47	C24090930.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/10/2024 05:47	C24090930.D
cis-1,2-Dichloroethene	156-59-2	30		10	09/10/2024 05:47	C24090930.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/10/2024 05:47	C24090930.D
Trichloroethene	79-01-6	457		10	09/10/2024 05:47	C24090930.D
Tetrachloroethene	127-18-4	<10		10	09/10/2024 05:47	C24090930.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-55

SGP-I4

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/10/2024 06:22	C24090931.D
1,1-Dichloroethene	75-35-4	18		10	09/10/2024 06:22	C24090931.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/10/2024 06:22	C24090931.D
cis-1,2-Dichloroethene	156-59-2	46		10	09/10/2024 06:22	C24090931.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/10/2024 06:22	C24090931.D
Trichloroethene	79-01-6	847		10	09/10/2024 06:22	C24090931.D
Tetrachloroethene	127-18-4	16		10	09/10/2024 06:22	C24090931.D

AECOM
40 British American Boulevard
Latham, NY 12110Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris FrenchBeacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-56

SGP-I5

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/10/2024 06:58	C24090932.D
1,1-Dichloroethene	75-35-4	<10		10	09/10/2024 06:58	C24090932.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/10/2024 06:58	C24090932.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/10/2024 06:58	C24090932.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/10/2024 06:58	C24090932.D
Trichloroethene	79-01-6	21		10	09/10/2024 06:58	C24090932.D
Tetrachloroethene	127-18-4	<10		10	09/10/2024 06:58	C24090932.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-57

SGP-I6

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/10/2024 07:33	C24090933.D
1,1-Dichloroethene	75-35-4	<10		10	09/10/2024 07:33	C24090933.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/10/2024 07:33	C24090933.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/10/2024 07:33	C24090933.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/10/2024 07:33	C24090933.D
Trichloroethene	79-01-6	20		10	09/10/2024 07:33	C24090933.D
Tetrachloroethene	127-18-4	<10		10	09/10/2024 07:33	C24090933.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-58

SGP-I7

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/10/2024 08:08	C24090934.D
1,1-Dichloroethene	75-35-4	<10		10	09/10/2024 08:08	C24090934.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/10/2024 08:08	C24090934.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/10/2024 08:08	C24090934.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/10/2024 08:08	C24090934.D
Trichloroethene	79-01-6	<10		10	09/10/2024 08:08	C24090934.D
Tetrachloroethene	127-18-4	<10		10	09/10/2024 08:08	C24090934.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-59

SGP-I8

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	190		10	09/10/2024 08:43	C24090935.D
1,1-Dichloroethene	75-35-4	527		10	09/10/2024 08:43	C24090935.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/10/2024 08:43	C24090935.D
cis-1,2-Dichloroethene	156-59-2	55		10	09/10/2024 08:43	C24090935.D
1,1,1-Trichloroethane	71-55-6	614		10	09/10/2024 08:43	C24090935.D
Trichloroethene	79-01-6	<10		10	09/10/2024 08:43	C24090935.D
Tetrachloroethene	127-18-4	<10		10	09/10/2024 08:43	C24090935.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-60

SGP-J0

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	11		10	09/10/2024 09:18	C24090936.D
1,1-Dichloroethene	75-35-4	33		10	09/10/2024 09:18	C24090936.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/10/2024 09:18	C24090936.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/10/2024 09:18	C24090936.D
1,1,1-Trichloroethane	71-55-6	48		10	09/10/2024 09:18	C24090936.D
Trichloroethene	79-01-6	<10		10	09/10/2024 09:18	C24090936.D
Tetrachloroethene	127-18-4	<10		10	09/10/2024 09:18	C24090936.D

AECOM
40 British American Boulevard
Latham, NY 12110Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris FrenchBeacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-61

SGP-J00

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/10/2024 14:29	S24091005.D
1,1-Dichloroethene	75-35-4	<10		10	09/10/2024 14:29	S24091005.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/10/2024 14:29	S24091005.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/10/2024 14:29	S24091005.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/10/2024 14:29	S24091005.D
Trichloroethene	79-01-6	<10		10	09/10/2024 14:29	S24091005.D
Tetrachloroethene	127-18-4	<10		10	09/10/2024 14:29	S24091005.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-62

SGP-J1

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/10/2024 15:00	S24091006.D
1,1-Dichloroethene	75-35-4	<10		10	09/10/2024 15:00	S24091006.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/10/2024 15:00	S24091006.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/10/2024 15:00	S24091006.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/10/2024 15:00	S24091006.D
Trichloroethene	79-01-6	<10		10	09/10/2024 15:00	S24091006.D
Tetrachloroethene	127-18-4	<10		10	09/10/2024 15:00	S24091006.D

AECOM
40 British American Boulevard
Latham, NY 12110

Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French

Beacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-63

SGP-J2

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/10/2024 15:31	S24091007.D
1,1-Dichloroethene	75-35-4	<10		10	09/10/2024 15:31	S24091007.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/10/2024 15:31	S24091007.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/10/2024 15:31	S24091007.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/10/2024 15:31	S24091007.D
Trichloroethene	79-01-6	<10		10	09/10/2024 15:31	S24091007.D
Tetrachloroethene	127-18-4	<10		10	09/10/2024 15:31	S24091007.D

AECOM
 40 British American Boulevard
 Latham, NY 12110

Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French

Beacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-64

SGP-J3

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/10/2024 16:02	S24091008.D
1,1-Dichloroethene	75-35-4	19		10	09/10/2024 16:02	S24091008.D
trans-1,2-Dichloroethene	156-60-5	39		10	09/10/2024 16:02	S24091008.D
cis-1,2-Dichloroethene	156-59-2	352		10	09/10/2024 16:02	S24091008.D
1,1,1-Trichloroethane	71-55-6	11		10	09/10/2024 16:02	S24091008.D
Trichloroethene	79-01-6	988		10	09/10/2024 16:02	S24091008.D
Tetrachloroethene	127-18-4	<10		10	09/10/2024 16:02	S24091008.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-65

SGP-J4

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/10/2024 16:33	S24091009.D
1,1-Dichloroethene	75-35-4	15		10	09/10/2024 16:33	S24091009.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/10/2024 16:33	S24091009.D
cis-1,2-Dichloroethene	156-59-2	39		10	09/10/2024 16:33	S24091009.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/10/2024 16:33	S24091009.D
Trichloroethene	79-01-6	76		10	09/10/2024 16:33	S24091009.D
Tetrachloroethene	127-18-4	<10		10	09/10/2024 16:33	S24091009.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-66

SGP-J5

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/10/2024 17:04	S24091010.D
1,1-Dichloroethene	75-35-4	30		10	09/10/2024 17:04	S24091010.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/10/2024 17:04	S24091010.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/10/2024 17:04	S24091010.D
1,1,1-Trichloroethane	71-55-6	22		10	09/10/2024 17:04	S24091010.D
Trichloroethene	79-01-6	27		10	09/10/2024 17:04	S24091010.D
Tetrachloroethene	127-18-4	<10		10	09/10/2024 17:04	S24091010.D

AECOM
40 British American Boulevard
Latham, NY 12110Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris FrenchBeacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-67

SGP-J6

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/10/2024 17:35	S24091011.D
1,1-Dichloroethene	75-35-4	25		10	09/10/2024 17:35	S24091011.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/10/2024 17:35	S24091011.D
cis-1,2-Dichloroethene	156-59-2	38		10	09/10/2024 17:35	S24091011.D
1,1,1-Trichloroethane	71-55-6	18		10	09/10/2024 17:35	S24091011.D
Trichloroethene	79-01-6	671		10	09/10/2024 17:35	S24091011.D
Tetrachloroethene	127-18-4	<10		10	09/10/2024 17:35	S24091011.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-68

SGP-J7

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/10/2024 18:06	S24091012.D
1,1-Dichloroethene	75-35-4	13		10	09/10/2024 18:06	S24091012.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/10/2024 18:06	S24091012.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/10/2024 18:06	S24091012.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/10/2024 18:06	S24091012.D
Trichloroethene	79-01-6	45		10	09/10/2024 18:06	S24091012.D
Tetrachloroethene	127-18-4	<10		10	09/10/2024 18:06	S24091012.D

AECOM
 40 British American Boulevard
 Latham, NY 12110

Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French

Beacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-69

SGP-K0

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/10/2024 18:39	S24091013.D
1,1-Dichloroethene	75-35-4	<10		10	09/10/2024 18:39	S24091013.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/10/2024 18:39	S24091013.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/10/2024 18:39	S24091013.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/10/2024 18:39	S24091013.D
Trichloroethene	79-01-6	<10		10	09/10/2024 18:39	S24091013.D
Tetrachloroethene	127-18-4	<10		10	09/10/2024 18:39	S24091013.D

AECOM
40 British American Boulevard
Latham, NY 12110

Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French

Beacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-70

SGP-K00

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/10/2024 19:10	S24091014.D
1,1-Dichloroethene	75-35-4	<10		10	09/10/2024 19:10	S24091014.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/10/2024 19:10	S24091014.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/10/2024 19:10	S24091014.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/10/2024 19:10	S24091014.D
Trichloroethene	79-01-6	<10		10	09/10/2024 19:10	S24091014.D
Tetrachloroethene	127-18-4	<10		10	09/10/2024 19:10	S24091014.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-71

SGP-K1

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/10/2024 19:42	S24091015.D
1,1-Dichloroethene	75-35-4	<10		10	09/10/2024 19:42	S24091015.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/10/2024 19:42	S24091015.D
cis-1,2-Dichloroethene	156-59-2	10		10	09/10/2024 19:42	S24091015.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/10/2024 19:42	S24091015.D
Trichloroethene	79-01-6	<10		10	09/10/2024 19:42	S24091015.D
Tetrachloroethene	127-18-4	<10		10	09/10/2024 19:42	S24091015.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-72

SGP-K1-DUP

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/10/2024 20:14	S24091016.D
1,1-Dichloroethene	75-35-4	<10		10	09/10/2024 20:14	S24091016.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/10/2024 20:14	S24091016.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/10/2024 20:14	S24091016.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/10/2024 20:14	S24091016.D
Trichloroethene	79-01-6	<10		10	09/10/2024 20:14	S24091016.D
Tetrachloroethene	127-18-4	<10		10	09/10/2024 20:14	S24091016.D

AECOM
40 British American Boulevard
Latham, NY 12110

Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French

Beacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-73

SGP-K2

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/10/2024 20:45	S24091017.D
1,1-Dichloroethene	75-35-4	<10		10	09/10/2024 20:45	S24091017.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/10/2024 20:45	S24091017.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/10/2024 20:45	S24091017.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/10/2024 20:45	S24091017.D
Trichloroethene	79-01-6	<10		10	09/10/2024 20:45	S24091017.D
Tetrachloroethene	127-18-4	<10		10	09/10/2024 20:45	S24091017.D

AECOM
40 British American Boulevard
Latham, NY 12110Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris FrenchBeacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-74

SGP-K3

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	35		10	09/10/2024 21:16	S24091018.D
1,1-Dichloroethene	75-35-4	77		10	09/10/2024 21:16	S24091018.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/10/2024 21:16	S24091018.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/10/2024 21:16	S24091018.D
1,1,1-Trichloroethane	71-55-6	94		10	09/10/2024 21:16	S24091018.D
Trichloroethene	79-01-6	25		10	09/10/2024 21:16	S24091018.D
Tetrachloroethene	127-18-4	<10		10	09/10/2024 21:16	S24091018.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-75

SGP-K4

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	44		10	09/10/2024 21:47	S24091019.D
1,1-Dichloroethene	75-35-4	119		10	09/10/2024 21:47	S24091019.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/10/2024 21:47	S24091019.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/10/2024 21:47	S24091019.D
1,1,1-Trichloroethane	71-55-6	152		10	09/10/2024 21:47	S24091019.D
Trichloroethene	79-01-6	14		10	09/10/2024 21:47	S24091019.D
Tetrachloroethene	127-18-4	<10		10	09/10/2024 21:47	S24091019.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-76

SGP-K5

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	12		10	09/10/2024 22:18	S24091020.D
1,1-Dichloroethene	75-35-4	37		10	09/10/2024 22:18	S24091020.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/10/2024 22:18	S24091020.D
cis-1,2-Dichloroethene	156-59-2	10		10	09/10/2024 22:18	S24091020.D
1,1,1-Trichloroethane	71-55-6	30		10	09/10/2024 22:18	S24091020.D
Trichloroethene	79-01-6	152		10	09/10/2024 22:18	S24091020.D
Tetrachloroethene	127-18-4	<10		10	09/10/2024 22:18	S24091020.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-77

SGP-K6

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	55		10	09/10/2024 22:49	S24091021.D
1,1-Dichloroethene	75-35-4	57		10	09/10/2024 22:49	S24091021.D
trans-1,2-Dichloroethene	156-60-5	109		10	09/10/2024 22:49	S24091021.D
cis-1,2-Dichloroethene	156-59-2	595		10	09/10/2024 22:49	S24091021.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/10/2024 22:49	S24091021.D
Trichloroethene	79-01-6	4,140		10	09/10/2024 22:49	S24091021.D
Tetrachloroethene	127-18-4	10		10	09/10/2024 22:49	S24091021.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-78

SGP-K7

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	14		10	09/10/2024 23:21	S24091022.D
1,1-Dichloroethene	75-35-4	35		10	09/10/2024 23:21	S24091022.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/10/2024 23:21	S24091022.D
cis-1,2-Dichloroethene	156-59-2	45		10	09/10/2024 23:21	S24091022.D
1,1,1-Trichloroethane	71-55-6	27		10	09/10/2024 23:21	S24091022.D
Trichloroethene	79-01-6	520		10	09/10/2024 23:21	S24091022.D
Tetrachloroethene	127-18-4	<10		10	09/10/2024 23:21	S24091022.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-79

SGP-K8

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	32		10	09/10/2024 23:52	S24091023.D
1,1-Dichloroethene	75-35-4	37		10	09/10/2024 23:52	S24091023.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/10/2024 23:52	S24091023.D
cis-1,2-Dichloroethene	156-59-2	47		10	09/10/2024 23:52	S24091023.D
1,1,1-Trichloroethane	71-55-6	57		10	09/10/2024 23:52	S24091023.D
Trichloroethene	79-01-6	543		10	09/10/2024 23:52	S24091023.D
Tetrachloroethene	127-18-4	56		10	09/10/2024 23:52	S24091023.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-80

SGP-L1

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	31		10	09/11/2024 00:24	S24091024.D
1,1-Dichloroethene	75-35-4	37		10	09/11/2024 00:24	S24091024.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/11/2024 00:24	S24091024.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/11/2024 00:24	S24091024.D
1,1,1-Trichloroethane	71-55-6	34		10	09/11/2024 00:24	S24091024.D
Trichloroethene	79-01-6	18		10	09/11/2024 00:24	S24091024.D
Tetrachloroethene	127-18-4	<10		10	09/11/2024 00:24	S24091024.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-81

SGP-L2

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	11		10	09/11/2024 01:59	S24091027.D
1,1-Dichloroethene	75-35-4	27		10	09/11/2024 01:59	S24091027.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/11/2024 01:59	S24091027.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/11/2024 01:59	S24091027.D
1,1,1-Trichloroethane	71-55-6	32		10	09/11/2024 01:59	S24091027.D
Trichloroethene	79-01-6	<10		10	09/11/2024 01:59	S24091027.D
Tetrachloroethene	127-18-4	<10		10	09/11/2024 01:59	S24091027.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-82

SGP-L3

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	41		10	09/11/2024 02:31	S24091028.D
1,1-Dichloroethene	75-35-4	101		10	09/11/2024 02:31	S24091028.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/11/2024 02:31	S24091028.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/11/2024 02:31	S24091028.D
1,1,1-Trichloroethane	71-55-6	161		10	09/11/2024 02:31	S24091028.D
Trichloroethene	79-01-6	43		10	09/11/2024 02:31	S24091028.D
Tetrachloroethene	127-18-4	<10		10	09/11/2024 02:31	S24091028.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-83

SGP-L4

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	43		10	09/11/2024 03:04	S24091029.D
1,1-Dichloroethene	75-35-4	123		10	09/11/2024 03:04	S24091029.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/11/2024 03:04	S24091029.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/11/2024 03:04	S24091029.D
1,1,1-Trichloroethane	71-55-6	159		10	09/11/2024 03:04	S24091029.D
Trichloroethene	79-01-6	<10		10	09/11/2024 03:04	S24091029.D
Tetrachloroethene	127-18-4	<10		10	09/11/2024 03:04	S24091029.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-84

SGP-L5

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	33		10	09/11/2024 03:36	S24091030.D
1,1-Dichloroethene	75-35-4	43		10	09/11/2024 03:36	S24091030.D
trans-1,2-Dichloroethene	156-60-5	11		10	09/11/2024 03:36	S24091030.D
cis-1,2-Dichloroethene	156-59-2	64		10	09/11/2024 03:36	S24091030.D
1,1,1-Trichloroethane	71-55-6	27		10	09/11/2024 03:36	S24091030.D
Trichloroethene	79-01-6	442		10	09/11/2024 03:36	S24091030.D
Tetrachloroethene	127-18-4	<10		10	09/11/2024 03:36	S24091030.D

AECOM
40 British American Boulevard
Latham, NY 12110

Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French

Beacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-85

SGP-L6

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	22		10	09/11/2024 04:07	S24091031.D
1,1-Dichloroethene	75-35-4	45		10	09/11/2024 04:07	S24091031.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/11/2024 04:07	S24091031.D
cis-1,2-Dichloroethene	156-59-2	12		10	09/11/2024 04:07	S24091031.D
1,1,1-Trichloroethane	71-55-6	27		10	09/11/2024 04:07	S24091031.D
Trichloroethene	79-01-6	81		10	09/11/2024 04:07	S24091031.D
Tetrachloroethene	127-18-4	<10		10	09/11/2024 04:07	S24091031.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-86

SGP-L7

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	483		10	09/11/2024 04:38	S24091032.D
1,1-Dichloroethene	75-35-4	58		10	09/11/2024 04:38	S24091032.D
trans-1,2-Dichloroethene	156-60-5	81		10	09/11/2024 04:38	S24091032.D
cis-1,2-Dichloroethene	156-59-2	707		10	09/11/2024 04:38	S24091032.D
1,1,1-Trichloroethane	71-55-6	23		10	09/11/2024 04:38	S24091032.D
Trichloroethene	79-01-6	477		10	09/11/2024 04:38	S24091032.D
Tetrachloroethene	127-18-4	486		10	09/11/2024 04:38	S24091032.D

AECOM
40 British American Boulevard
Latham, NY 12110Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris FrenchBeacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-87

SGP-M0

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	27		10	09/11/2024 05:09	S24091033.D
1,1-Dichloroethene	75-35-4	35		10	09/11/2024 05:09	S24091033.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/11/2024 05:09	S24091033.D
cis-1,2-Dichloroethene	156-59-2	31		10	09/11/2024 05:09	S24091033.D
1,1,1-Trichloroethane	71-55-6	26		10	09/11/2024 05:09	S24091033.D
Trichloroethene	79-01-6	402		10	09/11/2024 05:09	S24091033.D
Tetrachloroethene	127-18-4	<10		10	09/11/2024 05:09	S24091033.D

AECOM
40 British American Boulevard
Latham, NY 12110

Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French

Beacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-88

SGP-M1

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/11/2024 05:42	S24091034.D
1,1-Dichloroethene	75-35-4	<10		10	09/11/2024 05:42	S24091034.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/11/2024 05:42	S24091034.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/11/2024 05:42	S24091034.D
1,1,1-Trichloroethane	71-55-6	17		10	09/11/2024 05:42	S24091034.D
Trichloroethene	79-01-6	144		10	09/11/2024 05:42	S24091034.D
Tetrachloroethene	127-18-4	<10		10	09/11/2024 05:42	S24091034.D

AECOM
40 British American Boulevard
Latham, NY 12110Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris FrenchBeacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-89

SGP-M1-DUP

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/11/2024 06:13	S24091035.D
1,1-Dichloroethene	75-35-4	<10		10	09/11/2024 06:13	S24091035.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/11/2024 06:13	S24091035.D
cis-1,2-Dichloroethene	156-59-2	11		10	09/11/2024 06:13	S24091035.D
1,1,1-Trichloroethane	71-55-6	24		10	09/11/2024 06:13	S24091035.D
Trichloroethene	79-01-6	165		10	09/11/2024 06:13	S24091035.D
Tetrachloroethene	127-18-4	<10		10	09/11/2024 06:13	S24091035.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-90

SGP-M2

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	13		10	09/11/2024 06:45	S24091036.D
1,1-Dichloroethene	75-35-4	29		10	09/11/2024 06:45	S24091036.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/11/2024 06:45	S24091036.D
cis-1,2-Dichloroethene	156-59-2	13		10	09/11/2024 06:45	S24091036.D
1,1,1-Trichloroethane	71-55-6	44		10	09/11/2024 06:45	S24091036.D
Trichloroethene	79-01-6	163		10	09/11/2024 06:45	S24091036.D
Tetrachloroethene	127-18-4	<10		10	09/11/2024 06:45	S24091036.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-91

SGP-M3

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	339		10	09/11/2024 07:17	S24091037.D
1,1-Dichloroethene	75-35-4	1,650		10	09/11/2024 07:17	S24091037.D
trans-1,2-Dichloroethene	156-60-5	70		10	09/11/2024 07:17	S24091037.D
cis-1,2-Dichloroethene	156-59-2	365		10	09/11/2024 07:17	S24091037.D
1,1,1-Trichloroethane	71-55-6	2,230		10	09/11/2024 07:17	S24091037.D
Trichloroethene	79-01-6	9,990		10	09/11/2024 07:17	S24091037.D
Tetrachloroethene	127-18-4	88		10	09/11/2024 07:17	S24091037.D

AECOM
40 British American Boulevard
Latham, NY 12110Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris FrenchBeacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-92

SGP-M4

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	99		10	09/11/2024 07:50	S24091038.D
1,1-Dichloroethene	75-35-4	346		10	09/11/2024 07:50	S24091038.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/11/2024 07:50	S24091038.D
cis-1,2-Dichloroethene	156-59-2	41		10	09/11/2024 07:50	S24091038.D
1,1,1-Trichloroethane	71-55-6	521		10	09/11/2024 07:50	S24091038.D
Trichloroethene	79-01-6	987		10	09/11/2024 07:50	S24091038.D
Tetrachloroethene	127-18-4	24		10	09/11/2024 07:50	S24091038.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-93

SGP-M5

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	323		10	09/11/2024 08:22	S24091039.D
1,1-Dichloroethene	75-35-4	1,260		10	09/11/2024 08:22	S24091039.D
trans-1,2-Dichloroethene	156-60-5	42		10	09/11/2024 08:22	S24091039.D
cis-1,2-Dichloroethene	156-59-2	236		10	09/11/2024 08:22	S24091039.D
1,1,1-Trichloroethane	71-55-6	2,450		10	09/11/2024 08:22	S24091039.D
Trichloroethene	79-01-6	5,580		10	09/11/2024 08:22	S24091039.D
Tetrachloroethene	127-18-4	30		10	09/11/2024 08:22	S24091039.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-94

SGP-M6

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	117		10	09/11/2024 08:53	S24091040.D
1,1-Dichloroethene	75-35-4	216		10	09/11/2024 08:53	S24091040.D
trans-1,2-Dichloroethene	156-60-5	41		10	09/11/2024 08:53	S24091040.D
cis-1,2-Dichloroethene	156-59-2	275		10	09/11/2024 08:53	S24091040.D
1,1,1-Trichloroethane	71-55-6	170		10	09/11/2024 08:53	S24091040.D
Trichloroethene	79-01-6	1,900		10	09/11/2024 08:53	S24091040.D
Tetrachloroethene	127-18-4	<10		10	09/11/2024 08:53	S24091040.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-95

SGP-M7

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	289		10	09/11/2024 09:25	S24091041.D
1,1-Dichloroethene	75-35-4	189		10	09/11/2024 09:25	S24091041.D
trans-1,2-Dichloroethene	156-60-5	143		10	09/11/2024 09:25	S24091041.D
cis-1,2-Dichloroethene	156-59-2	1,340		10	09/11/2024 09:25	S24091041.D
1,1,1-Trichloroethane	71-55-6	147		10	09/11/2024 09:25	S24091041.D
Trichloroethene	79-01-6	2,110		10	09/11/2024 09:25	S24091041.D
Tetrachloroethene	127-18-4	<10		10	09/11/2024 09:25	S24091041.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-96

SGP-M8

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	163		10	09/11/2024 09:57	S24091042.D
1,1-Dichloroethene	75-35-4	244		10	09/11/2024 09:57	S24091042.D
trans-1,2-Dichloroethene	156-60-5	89		10	09/11/2024 09:57	S24091042.D
cis-1,2-Dichloroethene	156-59-2	583		10	09/11/2024 09:57	S24091042.D
1,1,1-Trichloroethane	71-55-6	198		10	09/11/2024 09:57	S24091042.D
Trichloroethene	79-01-6	5,020		10	09/11/2024 09:57	S24091042.D
Tetrachloroethene	127-18-4	28		10	09/11/2024 09:57	S24091042.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-97

SGP-N1

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	18		10	09/11/2024 10:29	S24091043.D
1,1-Dichloroethene	75-35-4	19		10	09/11/2024 10:29	S24091043.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/11/2024 10:29	S24091043.D
cis-1,2-Dichloroethene	156-59-2	24		10	09/11/2024 10:29	S24091043.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/11/2024 10:29	S24091043.D
Trichloroethene	79-01-6	149		10	09/11/2024 10:29	S24091043.D
Tetrachloroethene	127-18-4	<10		10	09/11/2024 10:29	S24091043.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-98

SGP-N2

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	32		10	09/11/2024 11:01	S24091044.D
1,1-Dichloroethene	75-35-4	22		10	09/11/2024 11:01	S24091044.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/11/2024 11:01	S24091044.D
cis-1,2-Dichloroethene	156-59-2	15		10	09/11/2024 11:01	S24091044.D
1,1,1-Trichloroethane	71-55-6	22		10	09/11/2024 11:01	S24091044.D
Trichloroethene	79-01-6	167		10	09/11/2024 11:01	S24091044.D
Tetrachloroethene	127-18-4	<10		10	09/11/2024 11:01	S24091044.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-99

SGP-N3

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/11/2024 11:33	S24091045.D
1,1-Dichloroethene	75-35-4	<10		10	09/11/2024 11:33	S24091045.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/11/2024 11:33	S24091045.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/11/2024 11:33	S24091045.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/11/2024 11:33	S24091045.D
Trichloroethene	79-01-6	<10		10	09/11/2024 11:33	S24091045.D
Tetrachloroethene	127-18-4	<10		10	09/11/2024 11:33	S24091045.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-AA

SGP-N4

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	332		10	09/11/2024 12:05	S24091046.D
1,1-Dichloroethene	75-35-4	2,140		10	09/11/2024 12:05	S24091046.D
trans-1,2-Dichloroethene	156-60-5	32		10	09/11/2024 12:05	S24091046.D
cis-1,2-Dichloroethene	156-59-2	176		10	09/11/2024 12:05	S24091046.D
1,1,1-Trichloroethane	71-55-6	3,460		10	09/11/2024 12:05	S24091046.D
Trichloroethene	79-01-6	5,150		10	09/11/2024 12:05	S24091046.D
Tetrachloroethene	127-18-4	138		10	09/11/2024 12:05	S24091046.D

AECOM
40 British American Boulevard
Latham, NY 12110Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris FrenchBeacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-AB

SGP-N5

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	866		10	09/10/2024 16:18	C24091005.D
1,1-Dichloroethene	75-35-4	9,290		10	09/10/2024 16:18	C24091005.D
trans-1,2-Dichloroethene	156-60-5	119		10	09/10/2024 16:18	C24091005.D
cis-1,2-Dichloroethene	156-59-2	673		10	09/10/2024 16:18	C24091005.D
1,1,1-Trichloroethane	71-55-6	12,400		10	09/10/2024 16:18	C24091005.D
Trichloroethene	79-01-6	15,200		10	09/10/2024 16:18	C24091005.D
Tetrachloroethene	127-18-4	84		10	09/10/2024 16:18	C24091005.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-AC

SGP-N6

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	588		10	09/10/2024 16:53	C24091006.D
1,1-Dichloroethene	75-35-4	4,520		10	09/10/2024 16:53	C24091006.D
trans-1,2-Dichloroethene	156-60-5	249		10	09/10/2024 16:53	C24091006.D
cis-1,2-Dichloroethene	156-59-2	1,600		10	09/10/2024 16:53	C24091006.D
1,1,1-Trichloroethane	71-55-6	3,510		10	09/10/2024 16:53	C24091006.D
Trichloroethene	79-01-6	13,300		10	09/10/2024 16:53	C24091006.D
Tetrachloroethene	127-18-4	44		10	09/10/2024 16:53	C24091006.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-AD

SGP-N7

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	411		10	09/10/2024 17:28	C24091007.D
1,1-Dichloroethene	75-35-4	2,640		10	09/10/2024 17:28	C24091007.D
trans-1,2-Dichloroethene	156-60-5	116		10	09/10/2024 17:28	C24091007.D
cis-1,2-Dichloroethene	156-59-2	666		10	09/10/2024 17:28	C24091007.D
1,1,1-Trichloroethane	71-55-6	4,670		10	09/10/2024 17:28	C24091007.D
Trichloroethene	79-01-6	15,100		10	09/10/2024 17:28	C24091007.D
Tetrachloroethene	127-18-4	69		10	09/10/2024 17:28	C24091007.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-AE

SGP-O1

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/10/2024 18:03	C24091008.D
1,1-Dichloroethene	75-35-4	<10		10	09/10/2024 18:03	C24091008.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/10/2024 18:03	C24091008.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/10/2024 18:03	C24091008.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/10/2024 18:03	C24091008.D
Trichloroethene	79-01-6	<10		10	09/10/2024 18:03	C24091008.D
Tetrachloroethene	127-18-4	<10		10	09/10/2024 18:03	C24091008.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-AF

SGP-O2

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/10/2024 18:38	C24091009.D
1,1-Dichloroethene	75-35-4	<10		10	09/10/2024 18:38	C24091009.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/10/2024 18:38	C24091009.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/10/2024 18:38	C24091009.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/10/2024 18:38	C24091009.D
Trichloroethene	79-01-6	<10		10	09/10/2024 18:38	C24091009.D
Tetrachloroethene	127-18-4	<10		10	09/10/2024 18:38	C24091009.D

AECOM
40 British American Boulevard
Latham, NY 12110

Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French

Beacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-AG

SGP-O3

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/10/2024 19:13	C24091010.D
1,1-Dichloroethene	75-35-4	<10		10	09/10/2024 19:13	C24091010.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/10/2024 19:13	C24091010.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/10/2024 19:13	C24091010.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/10/2024 19:13	C24091010.D
Trichloroethene	79-01-6	<10		10	09/10/2024 19:13	C24091010.D
Tetrachloroethene	127-18-4	<10		10	09/10/2024 19:13	C24091010.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-AH

SGP-O4

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/10/2024 19:48	C24091011.D
1,1-Dichloroethene	75-35-4	<10		10	09/10/2024 19:48	C24091011.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/10/2024 19:48	C24091011.D
cis-1,2-Dichloroethene	156-59-2	21		10	09/10/2024 19:48	C24091011.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/10/2024 19:48	C24091011.D
Trichloroethene	79-01-6	51		10	09/10/2024 19:48	C24091011.D
Tetrachloroethene	127-18-4	<10		10	09/10/2024 19:48	C24091011.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-AI

SGP-O5

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/10/2024 20:24	C24091012.D
1,1-Dichloroethene	75-35-4	<10		10	09/10/2024 20:24	C24091012.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/10/2024 20:24	C24091012.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/10/2024 20:24	C24091012.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/10/2024 20:24	C24091012.D
Trichloroethene	79-01-6	26		10	09/10/2024 20:24	C24091012.D
Tetrachloroethene	127-18-4	<10		10	09/10/2024 20:24	C24091012.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-AJ

SGP-O6

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/10/2024 20:59	C24091013.D
1,1-Dichloroethene	75-35-4	<10		10	09/10/2024 20:59	C24091013.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/10/2024 20:59	C24091013.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/10/2024 20:59	C24091013.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/10/2024 20:59	C24091013.D
Trichloroethene	79-01-6	27		10	09/10/2024 20:59	C24091013.D
Tetrachloroethene	127-18-4	<10		10	09/10/2024 20:59	C24091013.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-AK

SGP-O7

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/10/2024 21:34	C24091014.D
1,1-Dichloroethene	75-35-4	<10		10	09/10/2024 21:34	C24091014.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/10/2024 21:34	C24091014.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/10/2024 21:34	C24091014.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/10/2024 21:34	C24091014.D
Trichloroethene	79-01-6	<10		10	09/10/2024 21:34	C24091014.D
Tetrachloroethene	127-18-4	<10		10	09/10/2024 21:34	C24091014.D

AECOM
40 British American Boulevard
Latham, NY 12110Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris FrenchBeacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-AL

SGP-O8

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/10/2024 22:10	C24091015.D
1,1-Dichloroethene	75-35-4	<10		10	09/10/2024 22:10	C24091015.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/10/2024 22:10	C24091015.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/10/2024 22:10	C24091015.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/10/2024 22:10	C24091015.D
Trichloroethene	79-01-6	<10		10	09/10/2024 22:10	C24091015.D
Tetrachloroethene	127-18-4	<10		10	09/10/2024 22:10	C24091015.D

AECOM
40 British American Boulevard
Latham, NY 12110Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris FrenchBeacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-AM

SGP-O8-DUP

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/10/2024 22:45	C24091016.D
1,1-Dichloroethene	75-35-4	<10		10	09/10/2024 22:45	C24091016.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/10/2024 22:45	C24091016.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/10/2024 22:45	C24091016.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/10/2024 22:45	C24091016.D
Trichloroethene	79-01-6	<10		10	09/10/2024 22:45	C24091016.D
Tetrachloroethene	127-18-4	<10		10	09/10/2024 22:45	C24091016.D

AECOM
40 British American Boulevard
Latham, NY 12110

Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French

Beacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-AN

SGP-O9

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/10/2024 23:20	C24091017.D
1,1-Dichloroethene	75-35-4	<10		10	09/10/2024 23:20	C24091017.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/10/2024 23:20	C24091017.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/10/2024 23:20	C24091017.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/10/2024 23:20	C24091017.D
Trichloroethene	79-01-6	<10		10	09/10/2024 23:20	C24091017.D
Tetrachloroethene	127-18-4	<10		10	09/10/2024 23:20	C24091017.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-AO

SGP-O10

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/10/2024 23:55	C24091018.D
1,1-Dichloroethene	75-35-4	<10		10	09/10/2024 23:55	C24091018.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/10/2024 23:55	C24091018.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/10/2024 23:55	C24091018.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/10/2024 23:55	C24091018.D
Trichloroethene	79-01-6	<10		10	09/10/2024 23:55	C24091018.D
Tetrachloroethene	127-18-4	<10		10	09/10/2024 23:55	C24091018.D

AECOM
40 British American Boulevard
Latham, NY 12110

Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French

Beacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-AP

SGP-O11

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/11/2024 00:30	C24091019.D
1,1-Dichloroethene	75-35-4	<10		10	09/11/2024 00:30	C24091019.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/11/2024 00:30	C24091019.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/11/2024 00:30	C24091019.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/11/2024 00:30	C24091019.D
Trichloroethene	79-01-6	<10		10	09/11/2024 00:30	C24091019.D
Tetrachloroethene	127-18-4	<10		10	09/11/2024 00:30	C24091019.D

AECOM
40 British American Boulevard
Latham, NY 12110

Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French

Beacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-AQ

SGP-O12

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/11/2024 01:05	C24091020.D
1,1-Dichloroethene	75-35-4	<10		10	09/11/2024 01:05	C24091020.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/11/2024 01:05	C24091020.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/11/2024 01:05	C24091020.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/11/2024 01:05	C24091020.D
Trichloroethene	79-01-6	<10		10	09/11/2024 01:05	C24091020.D
Tetrachloroethene	127-18-4	<10		10	09/11/2024 01:05	C24091020.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-AR

SGP-O13

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/11/2024 01:41	C24091021.D
1,1-Dichloroethene	75-35-4	<10		10	09/11/2024 01:41	C24091021.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/11/2024 01:41	C24091021.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/11/2024 01:41	C24091021.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/11/2024 01:41	C24091021.D
Trichloroethene	79-01-6	<10		10	09/11/2024 01:41	C24091021.D
Tetrachloroethene	127-18-4	<10		10	09/11/2024 01:41	C24091021.D

AECOM
40 British American Boulevard
Latham, NY 12110

Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French

Beacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-AS

SGP-O14

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/11/2024 02:16	C24091022.D
1,1-Dichloroethene	75-35-4	<10		10	09/11/2024 02:16	C24091022.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/11/2024 02:16	C24091022.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/11/2024 02:16	C24091022.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/11/2024 02:16	C24091022.D
Trichloroethene	79-01-6	<10		10	09/11/2024 02:16	C24091022.D
Tetrachloroethene	127-18-4	<10		10	09/11/2024 02:16	C24091022.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-AT

SGP-P1

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/11/2024 02:51	C24091023.D
1,1-Dichloroethene	75-35-4	<10		10	09/11/2024 02:51	C24091023.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/11/2024 02:51	C24091023.D
cis-1,2-Dichloroethene	156-59-2	10		10	09/11/2024 02:51	C24091023.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/11/2024 02:51	C24091023.D
Trichloroethene	79-01-6	105		10	09/11/2024 02:51	C24091023.D
Tetrachloroethene	127-18-4	<10		10	09/11/2024 02:51	C24091023.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-AU

SGP-P2

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/11/2024 03:26	C24091024.D
1,1-Dichloroethene	75-35-4	<10		10	09/11/2024 03:26	C24091024.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/11/2024 03:26	C24091024.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/11/2024 03:26	C24091024.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/11/2024 03:26	C24091024.D
Trichloroethene	79-01-6	<10		10	09/11/2024 03:26	C24091024.D
Tetrachloroethene	127-18-4	<10		10	09/11/2024 03:26	C24091024.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-AV

SGP-P3

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/11/2024 05:16	C24091027.D
1,1-Dichloroethene	75-35-4	<10		10	09/11/2024 05:16	C24091027.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/11/2024 05:16	C24091027.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/11/2024 05:16	C24091027.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/11/2024 05:16	C24091027.D
Trichloroethene	79-01-6	<10		10	09/11/2024 05:16	C24091027.D
Tetrachloroethene	127-18-4	<10		10	09/11/2024 05:16	C24091027.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-AW

SGP-P4

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/11/2024 05:51	C24091028.D
1,1-Dichloroethene	75-35-4	<10		10	09/11/2024 05:51	C24091028.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/11/2024 05:51	C24091028.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/11/2024 05:51	C24091028.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/11/2024 05:51	C24091028.D
Trichloroethene	79-01-6	<10		10	09/11/2024 05:51	C24091028.D
Tetrachloroethene	127-18-4	<10		10	09/11/2024 05:51	C24091028.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-AX

SGP-P4-DUP

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/11/2024 06:26	C24091029.D
1,1-Dichloroethene	75-35-4	<10		10	09/11/2024 06:26	C24091029.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/11/2024 06:26	C24091029.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/11/2024 06:26	C24091029.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/11/2024 06:26	C24091029.D
Trichloroethene	79-01-6	<10		10	09/11/2024 06:26	C24091029.D
Tetrachloroethene	127-18-4	<10		10	09/11/2024 06:26	C24091029.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-AY

SGP-P5

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/11/2024 07:01	C24091030.D
1,1-Dichloroethene	75-35-4	<10		10	09/11/2024 07:01	C24091030.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/11/2024 07:01	C24091030.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/11/2024 07:01	C24091030.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/11/2024 07:01	C24091030.D
Trichloroethene	79-01-6	<10		10	09/11/2024 07:01	C24091030.D
Tetrachloroethene	127-18-4	17		10	09/11/2024 07:01	C24091030.D

AECOM
40 British American Boulevard
Latham, NY 12110

Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French

Beacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-AZ

SGP-Q1

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/11/2024 07:36	C24091031.D
1,1-Dichloroethene	75-35-4	12		10	09/11/2024 07:36	C24091031.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/11/2024 07:36	C24091031.D
cis-1,2-Dichloroethene	156-59-2	32		10	09/11/2024 07:36	C24091031.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/11/2024 07:36	C24091031.D
Trichloroethene	79-01-6	605		10	09/11/2024 07:36	C24091031.D
Tetrachloroethene	127-18-4	<10		10	09/11/2024 07:36	C24091031.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-BA

SGP-Q2

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/11/2024 08:11	C24091032.D
1,1-Dichloroethene	75-35-4	<10		10	09/11/2024 08:11	C24091032.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/11/2024 08:11	C24091032.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/11/2024 08:11	C24091032.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/11/2024 08:11	C24091032.D
Trichloroethene	79-01-6	28		10	09/11/2024 08:11	C24091032.D
Tetrachloroethene	127-18-4	<10		10	09/11/2024 08:11	C24091032.D

AECOM
40 British American Boulevard
Latham, NY 12110

Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French

Beacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-BB

SGP-Q3

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/11/2024 08:47	C24091033.D
1,1-Dichloroethene	75-35-4	<10		10	09/11/2024 08:47	C24091033.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/11/2024 08:47	C24091033.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/11/2024 08:47	C24091033.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/11/2024 08:47	C24091033.D
Trichloroethene	79-01-6	<10		10	09/11/2024 08:47	C24091033.D
Tetrachloroethene	127-18-4	<10		10	09/11/2024 08:47	C24091033.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-BC

SGP-R1

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	249		10	09/11/2024 09:22	C24091034.D
1,1-Dichloroethene	75-35-4	3,300		10	09/11/2024 09:22	C24091034.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/11/2024 09:22	C24091034.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/11/2024 09:22	C24091034.D
1,1,1-Trichloroethane	71-55-6	1,230		10	09/11/2024 09:22	C24091034.D
Trichloroethene	79-01-6	<10		10	09/11/2024 09:22	C24091034.D
Tetrachloroethene	127-18-4	<10		10	09/11/2024 09:22	C24091034.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-BD

SGP-R2

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/11/2024 09:57	C24091035.D
1,1-Dichloroethene	75-35-4	<10		10	09/11/2024 09:57	C24091035.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/11/2024 09:57	C24091035.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/11/2024 09:57	C24091035.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/11/2024 09:57	C24091035.D
Trichloroethene	79-01-6	<10		10	09/11/2024 09:57	C24091035.D
Tetrachloroethene	127-18-4	<10		10	09/11/2024 09:57	C24091035.D

AECOM
40 British American Boulevard
Latham, NY 12110

Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French

Beacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-BE

SGP-R3

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/11/2024 10:32	C24091036.D
1,1-Dichloroethene	75-35-4	<10		10	09/11/2024 10:32	C24091036.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/11/2024 10:32	C24091036.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/11/2024 10:32	C24091036.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/11/2024 10:32	C24091036.D
Trichloroethene	79-01-6	<10		10	09/11/2024 10:32	C24091036.D
Tetrachloroethene	127-18-4	<10		10	09/11/2024 10:32	C24091036.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-BF

SGP-R4

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/11/2024 15:09	S24091105.D
1,1-Dichloroethene	75-35-4	<10		10	09/11/2024 15:09	S24091105.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/11/2024 15:09	S24091105.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/11/2024 15:09	S24091105.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/11/2024 15:09	S24091105.D
Trichloroethene	79-01-6	<10		10	09/11/2024 15:09	S24091105.D
Tetrachloroethene	127-18-4	<10		10	09/11/2024 15:09	S24091105.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-BG

SGP-R4-DUP

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/11/2024 15:41	S24091106.D
1,1-Dichloroethene	75-35-4	<10		10	09/11/2024 15:41	S24091106.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/11/2024 15:41	S24091106.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/11/2024 15:41	S24091106.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/11/2024 15:41	S24091106.D
Trichloroethene	79-01-6	<10		10	09/11/2024 15:41	S24091106.D
Tetrachloroethene	127-18-4	<10		10	09/11/2024 15:41	S24091106.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-BH

SGP-S1

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	29		10	09/11/2024 16:12	S24091107.D
1,1-Dichloroethene	75-35-4	36		10	09/11/2024 16:12	S24091107.D
trans-1,2-Dichloroethene	156-60-5	79		10	09/11/2024 16:12	S24091107.D
cis-1,2-Dichloroethene	156-59-2	259		10	09/11/2024 16:12	S24091107.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/11/2024 16:12	S24091107.D
Trichloroethene	79-01-6	4,470		10	09/11/2024 16:12	S24091107.D
Tetrachloroethene	127-18-4	<10		10	09/11/2024 16:12	S24091107.D

AECOM
40 British American Boulevard
Latham, NY 12110Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris FrenchBeacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-B1

SGP-S2

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/11/2024 16:43	S24091108.D
1,1-Dichloroethene	75-35-4	<10		10	09/11/2024 16:43	S24091108.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/11/2024 16:43	S24091108.D
cis-1,2-Dichloroethene	156-59-2	13		10	09/11/2024 16:43	S24091108.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/11/2024 16:43	S24091108.D
Trichloroethene	79-01-6	107		10	09/11/2024 16:43	S24091108.D
Tetrachloroethene	127-18-4	<10		10	09/11/2024 16:43	S24091108.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-BJ

SGP-S3

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/11/2024 17:15	S24091109.D
1,1-Dichloroethene	75-35-4	<10		10	09/11/2024 17:15	S24091109.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/11/2024 17:15	S24091109.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/11/2024 17:15	S24091109.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/11/2024 17:15	S24091109.D
Trichloroethene	79-01-6	<10		10	09/11/2024 17:15	S24091109.D
Tetrachloroethene	127-18-4	<10		10	09/11/2024 17:15	S24091109.D

AECOM
40 British American Boulevard
Latham, NY 12110Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris FrenchBeacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-BK

SGP-T1

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	12		10	09/11/2024 17:46	S24091110.D
1,1-Dichloroethene	75-35-4	20		10	09/11/2024 17:46	S24091110.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/11/2024 17:46	S24091110.D
cis-1,2-Dichloroethene	156-59-2	26		10	09/11/2024 17:46	S24091110.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/11/2024 17:46	S24091110.D
Trichloroethene	79-01-6	368		10	09/11/2024 17:46	S24091110.D
Tetrachloroethene	127-18-4	<10		10	09/11/2024 17:46	S24091110.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-BL

SGP-T2

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/11/2024 18:18	S24091111.D
1,1-Dichloroethene	75-35-4	<10		10	09/11/2024 18:18	S24091111.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/11/2024 18:18	S24091111.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/11/2024 18:18	S24091111.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/11/2024 18:18	S24091111.D
Trichloroethene	79-01-6	<10		10	09/11/2024 18:18	S24091111.D
Tetrachloroethene	127-18-4	<10		10	09/11/2024 18:18	S24091111.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-BM

SGP-T3

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/11/2024 18:51	S24091112.D
1,1-Dichloroethene	75-35-4	<10		10	09/11/2024 18:51	S24091112.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/11/2024 18:51	S24091112.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/11/2024 18:51	S24091112.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/11/2024 18:51	S24091112.D
Trichloroethene	79-01-6	<10		10	09/11/2024 18:51	S24091112.D
Tetrachloroethene	127-18-4	<10		10	09/11/2024 18:51	S24091112.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-BN

SGP-U1

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	132		10	09/11/2024 19:22	S24091113.D
1,1-Dichloroethene	75-35-4	243		10	09/11/2024 19:22	S24091113.D
trans-1,2-Dichloroethene	156-60-5	43		10	09/11/2024 19:22	S24091113.D
cis-1,2-Dichloroethene	156-59-2	131		10	09/11/2024 19:22	S24091113.D
1,1,1-Trichloroethane	71-55-6	130		10	09/11/2024 19:22	S24091113.D
Trichloroethene	79-01-6	624		10	09/11/2024 19:22	S24091113.D
Tetrachloroethene	127-18-4	<10		10	09/11/2024 19:22	S24091113.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-BO

SGP-U2

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/11/2024 19:54	S24091114.D
1,1-Dichloroethene	75-35-4	13		10	09/11/2024 19:54	S24091114.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/11/2024 19:54	S24091114.D
cis-1,2-Dichloroethene	156-59-2	34		10	09/11/2024 19:54	S24091114.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/11/2024 19:54	S24091114.D
Trichloroethene	79-01-6	587		10	09/11/2024 19:54	S24091114.D
Tetrachloroethene	127-18-4	<10		10	09/11/2024 19:54	S24091114.D

AECOM
40 British American Boulevard
Latham, NY 12110

Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French

Beacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-BP

SGP-U3

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/11/2024 20:26	S24091115.D
1,1-Dichloroethene	75-35-4	<10		10	09/11/2024 20:26	S24091115.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/11/2024 20:26	S24091115.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/11/2024 20:26	S24091115.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/11/2024 20:26	S24091115.D
Trichloroethene	79-01-6	<10		10	09/11/2024 20:26	S24091115.D
Tetrachloroethene	127-18-4	<10		10	09/11/2024 20:26	S24091115.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-BQ

SGP-V1

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/11/2024 20:58	S24091116.D
1,1-Dichloroethene	75-35-4	<10		10	09/11/2024 20:58	S24091116.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/11/2024 20:58	S24091116.D
cis-1,2-Dichloroethene	156-59-2	36		10	09/11/2024 20:58	S24091116.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/11/2024 20:58	S24091116.D
Trichloroethene	79-01-6	834		10	09/11/2024 20:58	S24091116.D
Tetrachloroethene	127-18-4	<10		10	09/11/2024 20:58	S24091116.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-BR

SGP-V2

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/11/2024 21:29	S24091117.D
1,1-Dichloroethene	75-35-4	13		10	09/11/2024 21:29	S24091117.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/11/2024 21:29	S24091117.D
cis-1,2-Dichloroethene	156-59-2	29		10	09/11/2024 21:29	S24091117.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/11/2024 21:29	S24091117.D
Trichloroethene	79-01-6	1,010		10	09/11/2024 21:29	S24091117.D
Tetrachloroethene	127-18-4	<10		10	09/11/2024 21:29	S24091117.D

AECOM
40 British American Boulevard
Latham, NY 12110

Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French

Beacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-BS

SGP-V3

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/11/2024 22:01	S24091118.D
1,1-Dichloroethene	75-35-4	<10		10	09/11/2024 22:01	S24091118.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/11/2024 22:01	S24091118.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/11/2024 22:01	S24091118.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/11/2024 22:01	S24091118.D
Trichloroethene	79-01-6	<10		10	09/11/2024 22:01	S24091118.D
Tetrachloroethene	127-18-4	<10		10	09/11/2024 22:01	S24091118.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-BT

SGP-W1

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/11/2024 22:34	S24091119.D
1,1-Dichloroethene	75-35-4	<10		10	09/11/2024 22:34	S24091119.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/11/2024 22:34	S24091119.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/11/2024 22:34	S24091119.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/11/2024 22:34	S24091119.D
Trichloroethene	79-01-6	<10		10	09/11/2024 22:34	S24091119.D
Tetrachloroethene	127-18-4	<10		10	09/11/2024 22:34	S24091119.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-BU

SGP-W2

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/11/2024 23:05	S24091120.D
1,1-Dichloroethene	75-35-4	<10		10	09/11/2024 23:05	S24091120.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/11/2024 23:05	S24091120.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/11/2024 23:05	S24091120.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/11/2024 23:05	S24091120.D
Trichloroethene	79-01-6	<10		10	09/11/2024 23:05	S24091120.D
Tetrachloroethene	127-18-4	<10		10	09/11/2024 23:05	S24091120.D

AECOM
40 British American Boulevard
Latham, NY 12110Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris FrenchBeacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-BV

SGP-X1

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/11/2024 23:36	S24091121.D
1,1-Dichloroethene	75-35-4	<10		10	09/11/2024 23:36	S24091121.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/11/2024 23:36	S24091121.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/11/2024 23:36	S24091121.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/11/2024 23:36	S24091121.D
Trichloroethene	79-01-6	29		10	09/11/2024 23:36	S24091121.D
Tetrachloroethene	127-18-4	<10		10	09/11/2024 23:36	S24091121.D

AECOM
40 British American Boulevard
Latham, NY 12110

Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French

Beacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-BW

SGP-X2

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/12/2024 00:07	S24091122.D
1,1-Dichloroethene	75-35-4	<10		10	09/12/2024 00:07	S24091122.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/12/2024 00:07	S24091122.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/12/2024 00:07	S24091122.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/12/2024 00:07	S24091122.D
Trichloroethene	79-01-6	<10		10	09/12/2024 00:07	S24091122.D
Tetrachloroethene	127-18-4	<10		10	09/12/2024 00:07	S24091122.D

AECOM
40 British American Boulevard
Latham, NY 12110

Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French

Beacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-BX

SGP-Y1

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/12/2024 00:39	S24091123.D
1,1-Dichloroethene	75-35-4	<10		10	09/12/2024 00:39	S24091123.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/12/2024 00:39	S24091123.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/12/2024 00:39	S24091123.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/12/2024 00:39	S24091123.D
Trichloroethene	79-01-6	<10		10	09/12/2024 00:39	S24091123.D
Tetrachloroethene	127-18-4	<10		10	09/12/2024 00:39	S24091123.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-BY

SGP-Y2

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/12/2024 01:11	S24091124.D
1,1-Dichloroethene	75-35-4	<10		10	09/12/2024 01:11	S24091124.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/12/2024 01:11	S24091124.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/12/2024 01:11	S24091124.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/12/2024 01:11	S24091124.D
Trichloroethene	79-01-6	<10		10	09/12/2024 01:11	S24091124.D
Tetrachloroethene	127-18-4	<10		10	09/12/2024 01:11	S24091124.D

AECOM
40 British American Boulevard
Latham, NY 12110Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris FrenchBeacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-BZ

SGP-Z1

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/12/2024 02:26	S24091127.D
1,1-Dichloroethene	75-35-4	<10		10	09/12/2024 02:26	S24091127.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/12/2024 02:26	S24091127.D
cis-1,2-Dichloroethene	156-59-2	17		10	09/12/2024 02:26	S24091127.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/12/2024 02:26	S24091127.D
Trichloroethene	79-01-6	306		10	09/12/2024 02:26	S24091127.D
Tetrachloroethene	127-18-4	<10		10	09/12/2024 02:26	S24091127.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-CA

SGP-Z2

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/12/2024 02:55	S24091128.D
1,1-Dichloroethene	75-35-4	<10		10	09/12/2024 02:55	S24091128.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/12/2024 02:55	S24091128.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/12/2024 02:55	S24091128.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/12/2024 02:55	S24091128.D
Trichloroethene	79-01-6	<10		10	09/12/2024 02:55	S24091128.D
Tetrachloroethene	127-18-4	<10		10	09/12/2024 02:55	S24091128.D

AECOM
40 British American Boulevard
Latham, NY 12110

Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French

Beacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-CB

SGP-Z3

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/12/2024 03:25	S24091129.D
1,1-Dichloroethene	75-35-4	<10		10	09/12/2024 03:25	S24091129.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/12/2024 03:25	S24091129.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/12/2024 03:25	S24091129.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/12/2024 03:25	S24091129.D
Trichloroethene	79-01-6	<10		10	09/12/2024 03:25	S24091129.D
Tetrachloroethene	127-18-4	<10		10	09/12/2024 03:25	S24091129.D

AECOM
40 British American Boulevard
Latham, NY 12110Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris FrenchBeacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-CC

SGP-AA1

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/12/2024 03:55	S24091130.D
1,1-Dichloroethene	75-35-4	<10		10	09/12/2024 03:55	S24091130.D
trans-1,2-Dichloroethene	156-60-5	13		10	09/12/2024 03:55	S24091130.D
cis-1,2-Dichloroethene	156-59-2	83		10	09/12/2024 03:55	S24091130.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/12/2024 03:55	S24091130.D
Trichloroethene	79-01-6	748		10	09/12/2024 03:55	S24091130.D
Tetrachloroethene	127-18-4	<10		10	09/12/2024 03:55	S24091130.D

AECOM
40 British American Boulevard
Latham, NY 12110Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris FrenchBeacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-CD

SGP-AA1-DUP

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/12/2024 04:25	S24091131.D
1,1-Dichloroethene	75-35-4	<10		10	09/12/2024 04:25	S24091131.D
trans-1,2-Dichloroethene	156-60-5	12		10	09/12/2024 04:25	S24091131.D
cis-1,2-Dichloroethene	156-59-2	74		10	09/12/2024 04:25	S24091131.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/12/2024 04:25	S24091131.D
Trichloroethene	79-01-6	715		10	09/12/2024 04:25	S24091131.D
Tetrachloroethene	127-18-4	<10		10	09/12/2024 04:25	S24091131.D

AECOM
40 British American Boulevard
Latham, NY 12110Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris FrenchBeacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-CE

SGP-AA2

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/12/2024 04:55	S24091132.D
1,1-Dichloroethene	75-35-4	<10		10	09/12/2024 04:55	S24091132.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/12/2024 04:55	S24091132.D
cis-1,2-Dichloroethene	156-59-2	30		10	09/12/2024 04:55	S24091132.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/12/2024 04:55	S24091132.D
Trichloroethene	79-01-6	272		10	09/12/2024 04:55	S24091132.D
Tetrachloroethene	127-18-4	<10		10	09/12/2024 04:55	S24091132.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-CF

SGP-AA3

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/12/2024 05:24	S24091133.D
1,1-Dichloroethene	75-35-4	15		10	09/12/2024 05:24	S24091133.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/12/2024 05:24	S24091133.D
cis-1,2-Dichloroethene	156-59-2	40		10	09/12/2024 05:24	S24091133.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/12/2024 05:24	S24091133.D
Trichloroethene	79-01-6	708		10	09/12/2024 05:24	S24091133.D
Tetrachloroethene	127-18-4	<10		10	09/12/2024 05:24	S24091133.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-CG

SGP-BB1

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/12/2024 05:54	S24091134.D
1,1-Dichloroethene	75-35-4	436		10	09/12/2024 05:54	S24091134.D
trans-1,2-Dichloroethene	156-60-5	635		10	09/12/2024 05:54	S24091134.D
cis-1,2-Dichloroethene	156-59-2	5,730		10	09/12/2024 05:54	S24091134.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/12/2024 05:54	S24091134.D
Trichloroethene	79-01-6	38,300		10	09/12/2024 05:54	S24091134.D
Tetrachloroethene	127-18-4	79		10	09/12/2024 05:54	S24091134.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-CH

SGP-BB2

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/12/2024 06:23	S24091135.D
1,1-Dichloroethene	75-35-4	15		10	09/12/2024 06:23	S24091135.D
trans-1,2-Dichloroethene	156-60-5	13		10	09/12/2024 06:23	S24091135.D
cis-1,2-Dichloroethene	156-59-2	68		10	09/12/2024 06:23	S24091135.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/12/2024 06:23	S24091135.D
Trichloroethene	79-01-6	1,330		10	09/12/2024 06:23	S24091135.D
Tetrachloroethene	127-18-4	<10		10	09/12/2024 06:23	S24091135.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-C1

SGP-BB3

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/12/2024 06:53	S24091136.D
1,1-Dichloroethene	75-35-4	27		10	09/12/2024 06:53	S24091136.D
trans-1,2-Dichloroethene	156-60-5	24		10	09/12/2024 06:53	S24091136.D
cis-1,2-Dichloroethene	156-59-2	127		10	09/12/2024 06:53	S24091136.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/12/2024 06:53	S24091136.D
Trichloroethene	79-01-6	1,920		10	09/12/2024 06:53	S24091136.D
Tetrachloroethene	127-18-4	<10		10	09/12/2024 06:53	S24091136.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-CJ

SGP-CC1

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/12/2024 07:23	S24091137.D
1,1-Dichloroethene	75-35-4	<10		10	09/12/2024 07:23	S24091137.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/12/2024 07:23	S24091137.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/12/2024 07:23	S24091137.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/12/2024 07:23	S24091137.D
Trichloroethene	79-01-6	118		10	09/12/2024 07:23	S24091137.D
Tetrachloroethene	127-18-4	<10		10	09/12/2024 07:23	S24091137.D

AECOM
40 British American Boulevard
Latham, NY 12110

Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French

Beacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-CK

SGP-CC2

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/12/2024 07:53	S24091138.D
1,1-Dichloroethene	75-35-4	23		10	09/12/2024 07:53	S24091138.D
trans-1,2-Dichloroethene	156-60-5	94		10	09/12/2024 07:53	S24091138.D
cis-1,2-Dichloroethene	156-59-2	933		10	09/12/2024 07:53	S24091138.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/12/2024 07:53	S24091138.D
Trichloroethene	79-01-6	2,320		10	09/12/2024 07:53	S24091138.D
Tetrachloroethene	127-18-4	<10		10	09/12/2024 07:53	S24091138.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-CL

SGP-CC3

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/12/2024 08:22	S24091139.D
1,1-Dichloroethene	75-35-4	<10		10	09/12/2024 08:22	S24091139.D
trans-1,2-Dichloroethene	156-60-5	15		10	09/12/2024 08:22	S24091139.D
cis-1,2-Dichloroethene	156-59-2	103		10	09/12/2024 08:22	S24091139.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/12/2024 08:22	S24091139.D
Trichloroethene	79-01-6	777		10	09/12/2024 08:22	S24091139.D
Tetrachloroethene	127-18-4	28		10	09/12/2024 08:22	S24091139.D

AECOM
40 British American Boulevard
Latham, NY 12110

Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French

Beacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-CM

SGP-CC4

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/12/2024 08:52	S24091140.D
1,1-Dichloroethene	75-35-4	27		10	09/12/2024 08:52	S24091140.D
trans-1,2-Dichloroethene	156-60-5	51		10	09/12/2024 08:52	S24091140.D
cis-1,2-Dichloroethene	156-59-2	258		10	09/12/2024 08:52	S24091140.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/12/2024 08:52	S24091140.D
Trichloroethene	79-01-6	2,330		10	09/12/2024 08:52	S24091140.D
Tetrachloroethene	127-18-4	<10		10	09/12/2024 08:52	S24091140.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-CN

SGP-CC5

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/12/2024 09:22	S24091141.D
1,1-Dichloroethene	75-35-4	<10		10	09/12/2024 09:22	S24091141.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/12/2024 09:22	S24091141.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/12/2024 09:22	S24091141.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/12/2024 09:22	S24091141.D
Trichloroethene	79-01-6	41		10	09/12/2024 09:22	S24091141.D
Tetrachloroethene	127-18-4	<10		10	09/12/2024 09:22	S24091141.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-CO

SGP-CC5-DUP

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/12/2024 09:52	S24091142.D
1,1-Dichloroethene	75-35-4	<10		10	09/12/2024 09:52	S24091142.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/12/2024 09:52	S24091142.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/12/2024 09:52	S24091142.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/12/2024 09:52	S24091142.D
Trichloroethene	79-01-6	41		10	09/12/2024 09:52	S24091142.D
Tetrachloroethene	127-18-4	<10		10	09/12/2024 09:52	S24091142.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-CP

SGP-DD1

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/12/2024 10:21	S24091143.D
1,1-Dichloroethene	75-35-4	<10		10	09/12/2024 10:21	S24091143.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/12/2024 10:21	S24091143.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/12/2024 10:21	S24091143.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/12/2024 10:21	S24091143.D
Trichloroethene	79-01-6	95		10	09/12/2024 10:21	S24091143.D
Tetrachloroethene	127-18-4	<10		10	09/12/2024 10:21	S24091143.D

AECOM
40 British American Boulevard
Latham, NY 12110Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris FrenchBeacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-CQ

SGP-DD2

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/12/2024 10:51	S24091144.D
1,1-Dichloroethene	75-35-4	<10		10	09/12/2024 10:51	S24091144.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/12/2024 10:51	S24091144.D
cis-1,2-Dichloroethene	156-59-2	57		10	09/12/2024 10:51	S24091144.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/12/2024 10:51	S24091144.D
Trichloroethene	79-01-6	759		10	09/12/2024 10:51	S24091144.D
Tetrachloroethene	127-18-4	<10		10	09/12/2024 10:51	S24091144.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-CR

SGP-DD3

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/12/2024 11:20	S24091145.D
1,1-Dichloroethene	75-35-4	<10		10	09/12/2024 11:20	S24091145.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/12/2024 11:20	S24091145.D
cis-1,2-Dichloroethene	156-59-2	21		10	09/12/2024 11:20	S24091145.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/12/2024 11:20	S24091145.D
Trichloroethene	79-01-6	122		10	09/12/2024 11:20	S24091145.D
Tetrachloroethene	127-18-4	<10		10	09/12/2024 11:20	S24091145.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-CS

SGP-DD4

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/12/2024 11:49	S24091146.D
1,1-Dichloroethene	75-35-4	<10		10	09/12/2024 11:49	S24091146.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/12/2024 11:49	S24091146.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/12/2024 11:49	S24091146.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/12/2024 11:49	S24091146.D
Trichloroethene	79-01-6	11		10	09/12/2024 11:49	S24091146.D
Tetrachloroethene	127-18-4	<10		10	09/12/2024 11:49	S24091146.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-CT

SGP-DD5

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/11/2024 13:42	C24091105.D
1,1-Dichloroethene	75-35-4	<10		10	09/11/2024 13:42	C24091105.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/11/2024 13:42	C24091105.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/11/2024 13:42	C24091105.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/11/2024 13:42	C24091105.D
Trichloroethene	79-01-6	62		10	09/11/2024 13:42	C24091105.D
Tetrachloroethene	127-18-4	11		10	09/11/2024 13:42	C24091105.D

AECOM
40 British American Boulevard
Latham, NY 12110

Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French

Beacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-CU

SGP-DD6

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/11/2024 14:17	C24091106.D
1,1-Dichloroethene	75-35-4	<10		10	09/11/2024 14:17	C24091106.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/11/2024 14:17	C24091106.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/11/2024 14:17	C24091106.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/11/2024 14:17	C24091106.D
Trichloroethene	79-01-6	<10		10	09/11/2024 14:17	C24091106.D
Tetrachloroethene	127-18-4	<10		10	09/11/2024 14:17	C24091106.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-CV

SGP-EE1

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/11/2024 14:52	C24091107.D
1,1-Dichloroethene	75-35-4	<10		10	09/11/2024 14:52	C24091107.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/11/2024 14:52	C24091107.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/11/2024 14:52	C24091107.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/11/2024 14:52	C24091107.D
Trichloroethene	79-01-6	49		10	09/11/2024 14:52	C24091107.D
Tetrachloroethene	127-18-4	<10		10	09/11/2024 14:52	C24091107.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-CW

SGP-EE2

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/11/2024 15:27	C24091108.D
1,1-Dichloroethene	75-35-4	<10		10	09/11/2024 15:27	C24091108.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/11/2024 15:27	C24091108.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/11/2024 15:27	C24091108.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/11/2024 15:27	C24091108.D
Trichloroethene	79-01-6	19		10	09/11/2024 15:27	C24091108.D
Tetrachloroethene	127-18-4	<10		10	09/11/2024 15:27	C24091108.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-CX

SGP-EE3

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/11/2024 16:02	C24091109.D
1,1-Dichloroethene	75-35-4	<10		10	09/11/2024 16:02	C24091109.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/11/2024 16:02	C24091109.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/11/2024 16:02	C24091109.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/11/2024 16:02	C24091109.D
Trichloroethene	79-01-6	<10		10	09/11/2024 16:02	C24091109.D
Tetrachloroethene	127-18-4	<10		10	09/11/2024 16:02	C24091109.D

AECOM
40 British American Boulevard
Latham, NY 12110

Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French

Beacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-CY

SGP-EE4

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/11/2024 16:37	C24091110.D
1,1-Dichloroethene	75-35-4	<10		10	09/11/2024 16:37	C24091110.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/11/2024 16:37	C24091110.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/11/2024 16:37	C24091110.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/11/2024 16:37	C24091110.D
Trichloroethene	79-01-6	<10		10	09/11/2024 16:37	C24091110.D
Tetrachloroethene	127-18-4	<10		10	09/11/2024 16:37	C24091110.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-CZ

SGP-EE5

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/11/2024 17:12	C24091111.D
1,1-Dichloroethene	75-35-4	<10		10	09/11/2024 17:12	C24091111.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/11/2024 17:12	C24091111.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/11/2024 17:12	C24091111.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/11/2024 17:12	C24091111.D
Trichloroethene	79-01-6	20		10	09/11/2024 17:12	C24091111.D
Tetrachloroethene	127-18-4	<10		10	09/11/2024 17:12	C24091111.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-DA

SGP-EE6

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/11/2024 17:47	C24091112.D
1,1-Dichloroethene	75-35-4	<10		10	09/11/2024 17:47	C24091112.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/11/2024 17:47	C24091112.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/11/2024 17:47	C24091112.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/11/2024 17:47	C24091112.D
Trichloroethene	79-01-6	<10		10	09/11/2024 17:47	C24091112.D
Tetrachloroethene	127-18-4	<10		10	09/11/2024 17:47	C24091112.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-DB

SGP-FF1

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/11/2024 18:22	C24091113.D
1,1-Dichloroethene	75-35-4	<10		10	09/11/2024 18:22	C24091113.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/11/2024 18:22	C24091113.D
cis-1,2-Dichloroethene	156-59-2	21		10	09/11/2024 18:22	C24091113.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/11/2024 18:22	C24091113.D
Trichloroethene	79-01-6	89		10	09/11/2024 18:22	C24091113.D
Tetrachloroethene	127-18-4	<10		10	09/11/2024 18:22	C24091113.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-DC

SGP-FF2

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/11/2024 18:58	C24091114.D
1,1-Dichloroethene	75-35-4	<10		10	09/11/2024 18:58	C24091114.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/11/2024 18:58	C24091114.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/11/2024 18:58	C24091114.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/11/2024 18:58	C24091114.D
Trichloroethene	79-01-6	<10		10	09/11/2024 18:58	C24091114.D
Tetrachloroethene	127-18-4	<10		10	09/11/2024 18:58	C24091114.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-DD

SGP-FF3

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/11/2024 19:34	C24091115.D
1,1-Dichloroethene	75-35-4	<10		10	09/11/2024 19:34	C24091115.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/11/2024 19:34	C24091115.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/11/2024 19:34	C24091115.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/11/2024 19:34	C24091115.D
Trichloroethene	79-01-6	<10		10	09/11/2024 19:34	C24091115.D
Tetrachloroethene	127-18-4	<10		10	09/11/2024 19:34	C24091115.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-DE

SGP-FF3-DUP

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/11/2024 20:09	C24091116.D
1,1-Dichloroethene	75-35-4	<10		10	09/11/2024 20:09	C24091116.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/11/2024 20:09	C24091116.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/11/2024 20:09	C24091116.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/11/2024 20:09	C24091116.D
Trichloroethene	79-01-6	<10		10	09/11/2024 20:09	C24091116.D
Tetrachloroethene	127-18-4	<10		10	09/11/2024 20:09	C24091116.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-DF

SGP-FF4

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/11/2024 20:44	C24091117.D
1,1-Dichloroethene	75-35-4	<10		10	09/11/2024 20:44	C24091117.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/11/2024 20:44	C24091117.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/11/2024 20:44	C24091117.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/11/2024 20:44	C24091117.D
Trichloroethene	79-01-6	<10		10	09/11/2024 20:44	C24091117.D
Tetrachloroethene	127-18-4	<10		10	09/11/2024 20:44	C24091117.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-DG

SGP-FF5

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/11/2024 21:19	C24091118.D
1,1-Dichloroethene	75-35-4	<10		10	09/11/2024 21:19	C24091118.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/11/2024 21:19	C24091118.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/11/2024 21:19	C24091118.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/11/2024 21:19	C24091118.D
Trichloroethene	79-01-6	15		10	09/11/2024 21:19	C24091118.D
Tetrachloroethene	127-18-4	<10		10	09/11/2024 21:19	C24091118.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-DH

SGP-GG1

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/11/2024 21:54	C24091119.D
1,1-Dichloroethene	75-35-4	<10		10	09/11/2024 21:54	C24091119.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/11/2024 21:54	C24091119.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/11/2024 21:54	C24091119.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/11/2024 21:54	C24091119.D
Trichloroethene	79-01-6	46		10	09/11/2024 21:54	C24091119.D
Tetrachloroethene	127-18-4	<10		10	09/11/2024 21:54	C24091119.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-D1

SGP-GG2

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/11/2024 22:29	C24091120.D
1,1-Dichloroethene	75-35-4	<10		10	09/11/2024 22:29	C24091120.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/11/2024 22:29	C24091120.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/11/2024 22:29	C24091120.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/11/2024 22:29	C24091120.D
Trichloroethene	79-01-6	<10		10	09/11/2024 22:29	C24091120.D
Tetrachloroethene	127-18-4	<10		10	09/11/2024 22:29	C24091120.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-DJ

SGP-GG3

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/11/2024 23:04	C24091121.D
1,1-Dichloroethene	75-35-4	<10		10	09/11/2024 23:04	C24091121.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/11/2024 23:04	C24091121.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/11/2024 23:04	C24091121.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/11/2024 23:04	C24091121.D
Trichloroethene	79-01-6	<10		10	09/11/2024 23:04	C24091121.D
Tetrachloroethene	127-18-4	<10		10	09/11/2024 23:04	C24091121.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-DK

SGP-GG4

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/11/2024 23:40	C24091122.D
1,1-Dichloroethene	75-35-4	<10		10	09/11/2024 23:40	C24091122.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/11/2024 23:40	C24091122.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/11/2024 23:40	C24091122.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/11/2024 23:40	C24091122.D
Trichloroethene	79-01-6	<10		10	09/11/2024 23:40	C24091122.D
Tetrachloroethene	127-18-4	<10		10	09/11/2024 23:40	C24091122.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-DL

SGP-HH1

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/12/2024 00:15	C24091123.D
1,1-Dichloroethene	75-35-4	<10		10	09/12/2024 00:15	C24091123.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/12/2024 00:15	C24091123.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/12/2024 00:15	C24091123.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/12/2024 00:15	C24091123.D
Trichloroethene	79-01-6	<10		10	09/12/2024 00:15	C24091123.D
Tetrachloroethene	127-18-4	<10		10	09/12/2024 00:15	C24091123.D

AECOM
40 British American Boulevard
Latham, NY 12110

Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French

Beacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-DM

SGP-HH2

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/12/2024 00:50	C24091124.D
1,1-Dichloroethene	75-35-4	<10		10	09/12/2024 00:50	C24091124.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/12/2024 00:50	C24091124.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/12/2024 00:50	C24091124.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/12/2024 00:50	C24091124.D
Trichloroethene	79-01-6	<10		10	09/12/2024 00:50	C24091124.D
Tetrachloroethene	127-18-4	<10		10	09/12/2024 00:50	C24091124.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-DN

SGP-HH3

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/12/2024 02:37	C24091127.D
1,1-Dichloroethene	75-35-4	<10		10	09/12/2024 02:37	C24091127.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/12/2024 02:37	C24091127.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/12/2024 02:37	C24091127.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/12/2024 02:37	C24091127.D
Trichloroethene	79-01-6	<10		10	09/12/2024 02:37	C24091127.D
Tetrachloroethene	127-18-4	<10		10	09/12/2024 02:37	C24091127.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-DO

SGP-III

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	20		10	09/12/2024 03:12	C24091128.D
1,1-Dichloroethene	75-35-4	60		10	09/12/2024 03:12	C24091128.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/12/2024 03:12	C24091128.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/12/2024 03:12	C24091128.D
1,1,1-Trichloroethane	71-55-6	86		10	09/12/2024 03:12	C24091128.D
Trichloroethene	79-01-6	32		10	09/12/2024 03:12	C24091128.D
Tetrachloroethene	127-18-4	16		10	09/12/2024 03:12	C24091128.D

AECOM
40 British American Boulevard
Latham, NY 12110Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris FrenchBeacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-DP

SGP-II2

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/12/2024 03:47	C24091129.D
1,1-Dichloroethene	75-35-4	<10		10	09/12/2024 03:47	C24091129.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/12/2024 03:47	C24091129.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/12/2024 03:47	C24091129.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/12/2024 03:47	C24091129.D
Trichloroethene	79-01-6	54		10	09/12/2024 03:47	C24091129.D
Tetrachloroethene	127-18-4	<10		10	09/12/2024 03:47	C24091129.D

AECOM
40 British American Boulevard
Latham, NY 12110

Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French

Beacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-DQ

SGP-II3

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/12/2024 04:22	C24091130.D
1,1-Dichloroethene	75-35-4	<10		10	09/12/2024 04:22	C24091130.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/12/2024 04:22	C24091130.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/12/2024 04:22	C24091130.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/12/2024 04:22	C24091130.D
Trichloroethene	79-01-6	<10		10	09/12/2024 04:22	C24091130.D
Tetrachloroethene	127-18-4	<10		10	09/12/2024 04:22	C24091130.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-DR

SGP-II4

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/12/2024 04:57	C24091131.D
1,1-Dichloroethene	75-35-4	<10		10	09/12/2024 04:57	C24091131.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/12/2024 04:57	C24091131.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/12/2024 04:57	C24091131.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/12/2024 04:57	C24091131.D
Trichloroethene	79-01-6	<10		10	09/12/2024 04:57	C24091131.D
Tetrachloroethene	127-18-4	<10		10	09/12/2024 04:57	C24091131.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-DS

SGP-JJ1

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/12/2024 05:33	C24091132.D
1,1-Dichloroethene	75-35-4	<10		10	09/12/2024 05:33	C24091132.D
trans-1,2-Dichloroethene	156-60-5	10		10	09/12/2024 05:33	C24091132.D
cis-1,2-Dichloroethene	156-59-2	83		10	09/12/2024 05:33	C24091132.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/12/2024 05:33	C24091132.D
Trichloroethene	79-01-6	36		10	09/12/2024 05:33	C24091132.D
Tetrachloroethene	127-18-4	<10		10	09/12/2024 05:33	C24091132.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-DT

SGP-JJ2

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/12/2024 06:08	C24091133.D
1,1-Dichloroethene	75-35-4	<10		10	09/12/2024 06:08	C24091133.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/12/2024 06:08	C24091133.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/12/2024 06:08	C24091133.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/12/2024 06:08	C24091133.D
Trichloroethene	79-01-6	<10		10	09/12/2024 06:08	C24091133.D
Tetrachloroethene	127-18-4	<10		10	09/12/2024 06:08	C24091133.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-DU

SGP-KK1

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	39		10	09/12/2024 06:43	C24091134.D
1,1-Dichloroethene	75-35-4	<10		10	09/12/2024 06:43	C24091134.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/12/2024 06:43	C24091134.D
cis-1,2-Dichloroethene	156-59-2	15		10	09/12/2024 06:43	C24091134.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/12/2024 06:43	C24091134.D
Trichloroethene	79-01-6	113		10	09/12/2024 06:43	C24091134.D
Tetrachloroethene	127-18-4	<10		10	09/12/2024 06:43	C24091134.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-DV

SGP-KK2

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/12/2024 07:18	C24091135.D
1,1-Dichloroethene	75-35-4	<10		10	09/12/2024 07:18	C24091135.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/12/2024 07:18	C24091135.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/12/2024 07:18	C24091135.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/12/2024 07:18	C24091135.D
Trichloroethene	79-01-6	<10		10	09/12/2024 07:18	C24091135.D
Tetrachloroethene	127-18-4	<10		10	09/12/2024 07:18	C24091135.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-DW

SGP-LL1

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	19		10	09/12/2024 07:53	C24091136.D
1,1-Dichloroethene	75-35-4	<10		10	09/12/2024 07:53	C24091136.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/12/2024 07:53	C24091136.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/12/2024 07:53	C24091136.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/12/2024 07:53	C24091136.D
Trichloroethene	79-01-6	<10		10	09/12/2024 07:53	C24091136.D
Tetrachloroethene	127-18-4	<10		10	09/12/2024 07:53	C24091136.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-DX

SGP-MM1

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/12/2024 08:29	C24091137.D
1,1-Dichloroethene	75-35-4	<10		10	09/12/2024 08:29	C24091137.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/12/2024 08:29	C24091137.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/12/2024 08:29	C24091137.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/12/2024 08:29	C24091137.D
Trichloroethene	79-01-6	<10		10	09/12/2024 08:29	C24091137.D
Tetrachloroethene	127-18-4	<10		10	09/12/2024 08:29	C24091137.D

AECOM
40 British American Boulevard
Latham, NY 12110

Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French

Beacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-DY

SGP-MM2

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/12/2024 09:04	C24091138.D
1,1-Dichloroethene	75-35-4	<10		10	09/12/2024 09:04	C24091138.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/12/2024 09:04	C24091138.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/12/2024 09:04	C24091138.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/12/2024 09:04	C24091138.D
Trichloroethene	79-01-6	<10		10	09/12/2024 09:04	C24091138.D
Tetrachloroethene	127-18-4	<10		10	09/12/2024 09:04	C24091138.D

AECOM
40 British American Boulevard
Latham, NY 12110

Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French

Beacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-DZ

SGP-MM3

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/12/2024 09:39	C24091139.D
1,1-Dichloroethene	75-35-4	<10		10	09/12/2024 09:39	C24091139.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/12/2024 09:39	C24091139.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/12/2024 09:39	C24091139.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/12/2024 09:39	C24091139.D
Trichloroethene	79-01-6	<10		10	09/12/2024 09:39	C24091139.D
Tetrachloroethene	127-18-4	<10		10	09/12/2024 09:39	C24091139.D

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-EA

SGP-NN1

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/12/2024 10:15	C24091140.D
1,1-Dichloroethene	75-35-4	<10		10	09/12/2024 10:15	C24091140.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/12/2024 10:15	C24091140.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/12/2024 10:15	C24091140.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/12/2024 10:15	C24091140.D
Trichloroethene	79-01-6	<10		10	09/12/2024 10:15	C24091140.D
Tetrachloroethene	127-18-4	<10		10	09/12/2024 10:15	C24091140.D

AECOM
40 British American Boulevard
Latham, NY 12110

Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French

Beacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-EB

SGP-NN2

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/12/2024 10:50	C24091141.D
1,1-Dichloroethene	75-35-4	<10		10	09/12/2024 10:50	C24091141.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/12/2024 10:50	C24091141.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/12/2024 10:50	C24091141.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/12/2024 10:50	C24091141.D
Trichloroethene	79-01-6	<10		10	09/12/2024 10:50	C24091141.D
Tetrachloroethene	127-18-4	<10		10	09/12/2024 10:50	C24091141.D

AECOM
40 British American Boulevard
Latham, NY 12110

Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French

Beacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Lab Sample ID: 0007994-EC

SGP-NN3

Method: EPA 8260C

Soil Gas

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10		10	09/12/2024 11:25	C24091142.D
1,1-Dichloroethene	75-35-4	<10		10	09/12/2024 11:25	C24091142.D
trans-1,2-Dichloroethene	156-60-5	<10		10	09/12/2024 11:25	C24091142.D
cis-1,2-Dichloroethene	156-59-2	<10		10	09/12/2024 11:25	C24091142.D
1,1,1-Trichloroethane	71-55-6	<10		10	09/12/2024 11:25	C24091142.D
Trichloroethene	79-01-6	<10		10	09/12/2024 11:25	C24091142.D
Tetrachloroethene	127-18-4	<10		10	09/12/2024 11:25	C24091142.D

AECOM
40 British American Boulevard
Latham, NY 12110

Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French

Beacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

QC Information/Summary

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024*Soil-Gas Sample Analysis by EPA Method 8260C - Quality Control Summary***24I0016-BLK1 (Lab Blank) File ID: C24090902a.D**

Analyzed: 9/9/24 12:47

Sampler: Beacon Passive Sampler		Result	LOQ	
Analyte	CAS#	(ng)	(ng)	Q
Vinyl Chloride	75-01-4	<10	10	U
1,1-Dichloroethene	75-35-4	<10	10	U
trans-1,2-Dichloroethene	156-60-5	<10	10	U
cis-1,2-Dichloroethene	156-59-2	<10	10	U
1,1,1-Trichloroethane	71-55-6	<10	10	U
Trichloroethene	79-01-6	<10	10	U
Tetrachloroethene	127-18-4	<10	10	U

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024*Soil-Gas Sample Analysis by EPA Method 8260C - Quality Control Summary***24I0020-BLK1 (Lab Blank) File ID: C24091003.D**

Analyzed: 9/10/24 15:07

Sampler: Beacon Passive Sampler		Result	LOQ	
Analyte	CAS#	(ng)	(ng)	Q
Vinyl Chloride	75-01-4	<10	10	U
1,1-Dichloroethene	75-35-4	<10	10	U
trans-1,2-Dichloroethene	156-60-5	<10	10	U
cis-1,2-Dichloroethene	156-59-2	<10	10	U
1,1,1-Trichloroethane	71-55-6	<10	10	U
Trichloroethene	79-01-6	<10	10	U
Tetrachloroethene	127-18-4	<10	10	U

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024*Soil-Gas Sample Analysis by EPA Method 8260C - Quality Control Summary***24I0023-BLK1 (Lab Blank) File ID: C24091102.D**

Analyzed: 9/11/24 11:55

Sampler: Beacon Passive Sampler		Result	LOQ	
Analyte	CAS#	(ng)	(ng)	Q
Vinyl Chloride	75-01-4	<10	10	U
1,1-Dichloroethene	75-35-4	<10	10	U
trans-1,2-Dichloroethene	156-60-5	<10	10	U
cis-1,2-Dichloroethene	156-59-2	<10	10	U
1,1,1-Trichloroethane	71-55-6	<10	10	U
Trichloroethene	79-01-6	<10	10	U
Tetrachloroethene	127-18-4	<10	10	U

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024*Soil-Gas Sample Analysis by EPA Method 8260C - Quality Control Summary***24I0015-BLK1 (Lab Blank) File ID: S24090902.D**

Analyzed: 9/9/24 12:19

Sampler: Beacon Passive Sampler		Result	LOQ	
Analyte	CAS#	(ng)	(ng)	Q
Vinyl Chloride	75-01-4	<10	10	U
1,1-Dichloroethene	75-35-4	<10	10	U
trans-1,2-Dichloroethene	156-60-5	<10	10	U
cis-1,2-Dichloroethene	156-59-2	<10	10	U
1,1,1-Trichloroethane	71-55-6	<10	10	U
Trichloroethene	79-01-6	<10	10	U
Tetrachloroethene	127-18-4	<10	10	U

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024*Soil-Gas Sample Analysis by EPA Method 8260C - Quality Control Summary***24I0019-BLK1 (Lab Blank) File ID: S24091003.D**

Analyzed: 9/10/24 13:25

Sampler: Beacon Passive Sampler		Result	LOQ	
Analyte	CAS#	(ng)	(ng)	Q
Vinyl Chloride	75-01-4	<10	10	U
1,1-Dichloroethene	75-35-4	<10	10	U
trans-1,2-Dichloroethene	156-60-5	<10	10	U
cis-1,2-Dichloroethene	156-59-2	<10	10	U
1,1,1-Trichloroethane	71-55-6	<10	10	U
Trichloroethene	79-01-6	<10	10	U
Tetrachloroethene	127-18-4	<10	10	U

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024*Soil-Gas Sample Analysis by EPA Method 8260C - Quality Control Summary***24I0022-BLK1 (Lab Blank) File ID: S24091102.D**

Analyzed: 9/11/24 13:34

Sampler: Beacon Passive Sampler		Result	LOQ	
Analyte	CAS#	(ng)	(ng)	Q
Vinyl Chloride	75-01-4	<10	10	U
1,1-Dichloroethene	75-35-4	<10	10	U
trans-1,2-Dichloroethene	156-60-5	<10	10	U
cis-1,2-Dichloroethene	156-59-2	<10	10	U
1,1,1-Trichloroethane	71-55-6	<10	10	U
Trichloroethene	79-01-6	<10	10	U
Tetrachloroethene	127-18-4	<10	10	U

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Sample Duplicate RPD Summary
Soil-Gas Sample Analysis by EPA Method 8260C

Duplicate Sample: SGP-B1-DUP Sample: SGP-B1 Average RPD: 0.00%

Analyte	CAS#	Duplicate Result (ng)	LOQ (ng)	Sample Result (ng)	LOQ (ng)	RPD (%)
Vinyl Chloride	75-01-4	<10	10	<10	10	0.0
1,1-Dichloroethene	75-35-4	<10	10	<10	10	0.0
trans-1,2-Dichloroethene	156-60-5	<10	10	<10	10	0.0
cis-1,2-Dichloroethene	156-59-2	<10	10	<10	10	0.0
1,1,1-Trichloroethane	71-55-6	<10	10	<10	10	0.0
Trichloroethene	79-01-6	<10	10	<10	10	0.0
Tetrachloroethene	127-18-4	<10	10	<10	10	0.0

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Sample Duplicate RPD Summary
Soil-Gas Sample Analysis by EPA Method 8260C

Duplicate Sample: SGP-H6-DUP Sample: SGP-H6 Average RPD: 3.80%

Analyte	CAS#	Duplicate Result (ng)	LOQ (ng)	Sample Result (ng)	LOQ (ng)	RPD (%)
Vinyl Chloride	75-01-4	35.0	10	32.0	10	9.0
1,1-Dichloroethene	75-35-4	<10	10	<10	10	0.0
trans-1,2-Dichloroethene	156-60-5	23.0	10	25.0	10	8.3
cis-1,2-Dichloroethene	156-59-2	91.0	10	97.0	10	6.4
1,1,1-Trichloroethane	71-55-6	<10	10	<10	10	0.0
Trichloroethene	79-01-6	385	10	396	10	2.8
Tetrachloroethene	127-18-4	<10	10	<10	10	0.0

AECOM
40 British American Boulevard
Latham, NY 12110

Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French

Beacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Sample Duplicate RPD Summary
Soil-Gas Sample Analysis by EPA Method 8260C

Duplicate Sample: SGP-K1-DUP Sample: SGP-K1 Average RPD: 0.00%

Analyte	CAS#	Duplicate Result (ng)	LOQ (ng)	Sample Result (ng)	LOQ (ng)	RPD (%)
Vinyl Chloride	75-01-4	<10	10	<10	10	0.0
1,1-Dichloroethene	75-35-4	<10	10	<10	10	0.0
trans-1,2-Dichloroethene	156-60-5	<10	10	<10	10	0.0
cis-1,2-Dichloroethene	156-59-2	<10	10	10.0	10	0.0
1,1,1-Trichloroethane	71-55-6	<10	10	<10	10	0.0
Trichloroethene	79-01-6	<10	10	<10	10	0.0
Tetrachloroethene	127-18-4	<10	10	<10	10	0.0

AECOM
 40 British American Boulevard
 Latham, NY 12110

Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French

Beacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Sample Duplicate RPD Summary
Soil-Gas Sample Analysis by EPA Method 8260C

Duplicate Sample: SGP-M1-DUP Sample: SGP-M1 Average RPD: 8.20%

Analyte	CAS#	Duplicate Result (ng)	LOQ (ng)	Sample Result (ng)	LOQ (ng)	RPD (%)
Vinyl Chloride	75-01-4	<10	10	<10	10	0.0
1,1-Dichloroethene	75-35-4	<10	10	<10	10	0.0
trans-1,2-Dichloroethene	156-60-5	<10	10	<10	10	0.0
cis-1,2-Dichloroethene	156-59-2	11.0	10	<10	10	9.5
1,1,1-Trichloroethane	71-55-6	24.0	10	17.0	10	34.1
Trichloroethene	79-01-6	165	10	144	10	13.6
Tetrachloroethene	127-18-4	<10	10	<10	10	0.0

AECOM 40 British American Boulevard Latham, NY 12110	Site Name: NOW Corporation Site Location: Stratsburg, NY Project Manager: Chris French	Beacon Proposal: 240312R01 Lab Work Order: 0007994 Reported: 09/17/2024
---	---	--

Sample Duplicate RPD Summary
Soil-Gas Sample Analysis by EPA Method 8260C

Duplicate Sample: SGP-08-DUP Sample: SGP-08 Average RPD: 0.00%

Analyte	CAS#	Duplicate Result (ng)	LOQ (ng)	Sample Result (ng)	LOQ (ng)	RPD (%)
Vinyl Chloride	75-01-4	<10	10	<10	10	0.0
1,1-Dichloroethene	75-35-4	<10	10	<10	10	0.0
trans-1,2-Dichloroethene	156-60-5	<10	10	<10	10	0.0
cis-1,2-Dichloroethene	156-59-2	<10	10	<10	10	0.0
1,1,1-Trichloroethane	71-55-6	<10	10	<10	10	0.0
Trichloroethene	79-01-6	<10	10	<10	10	0.0
Tetrachloroethene	127-18-4	<10	10	<10	10	0.0

AECOM
 40 British American Boulevard
 Latham, NY 12110

Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French

Beacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Sample Duplicate RPD Summary
Soil-Gas Sample Analysis by EPA Method 8260C

Duplicate Sample: SGP-P4-DUP Sample: SGP-P4 Average RPD: 0.00%

Analyte	CAS#	Duplicate Result (ng)	LOQ (ng)	Sample Result (ng)	LOQ (ng)	RPD (%)
Vinyl Chloride	75-01-4	<10	10	<10	10	0.0
1,1-Dichloroethene	75-35-4	<10	10	<10	10	0.0
trans-1,2-Dichloroethene	156-60-5	<10	10	<10	10	0.0
cis-1,2-Dichloroethene	156-59-2	<10	10	<10	10	0.0
1,1,1-Trichloroethane	71-55-6	<10	10	<10	10	0.0
Trichloroethene	79-01-6	<10	10	<10	10	0.0
Tetrachloroethene	127-18-4	<10	10	<10	10	0.0

AECOM
 40 British American Boulevard
 Latham, NY 12110

Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French

Beacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Sample Duplicate RPD Summary
Soil-Gas Sample Analysis by EPA Method 8260C

Duplicate Sample: SGP-R4-DUP Sample: SGP-R4 Average RPD: 0.00%

Analyte	CAS#	Duplicate Result (ng)	LOQ (ng)	Sample Result (ng)	LOQ (ng)	RPD (%)
Vinyl Chloride	75-01-4	<10	10	<10	10	0.0
1,1-Dichloroethene	75-35-4	<10	10	<10	10	0.0
trans-1,2-Dichloroethene	156-60-5	<10	10	<10	10	0.0
cis-1,2-Dichloroethene	156-59-2	<10	10	<10	10	0.0
1,1,1-Trichloroethane	71-55-6	<10	10	<10	10	0.0
Trichloroethene	79-01-6	<10	10	<10	10	0.0
Tetrachloroethene	127-18-4	<10	10	<10	10	0.0

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Sample Duplicate RPD Summary
Soil-Gas Sample Analysis by EPA Method 8260C

Duplicate Sample: SGP-AA1-DUP Sample: SGP-AA1 Average RPD: 3.40%

Analyte	CAS#	Duplicate Result (ng)	LOQ (ng)	Sample Result (ng)	LOQ (ng)	RPD (%)
Vinyl Chloride	75-01-4	<10	10	<10	10	0.0
1,1-Dichloroethene	75-35-4	<10	10	<10	10	0.0
trans-1,2-Dichloroethene	156-60-5	12.0	10	13.0	10	8.0
cis-1,2-Dichloroethene	156-59-2	74.0	10	83.0	10	11.5
1,1,1-Trichloroethane	71-55-6	<10	10	<10	10	0.0
Trichloroethene	79-01-6	715	10	748	10	4.5
Tetrachloroethene	127-18-4	<10	10	<10	10	0.0

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Sample Duplicate RPD Summary
Soil-Gas Sample Analysis by EPA Method 8260C

Duplicate Sample: SGP-CC5-DUP Sample: SGP-CC5 Average RPD: 0.00%

Analyte	CAS#	Duplicate Result (ng)	LOQ (ng)	Sample Result (ng)	LOQ (ng)	RPD (%)
Vinyl Chloride	75-01-4	<10	10	<10	10	0.0
1,1-Dichloroethene	75-35-4	<10	10	<10	10	0.0
trans-1,2-Dichloroethene	156-60-5	<10	10	<10	10	0.0
cis-1,2-Dichloroethene	156-59-2	<10	10	<10	10	0.0
1,1,1-Trichloroethane	71-55-6	<10	10	<10	10	0.0
Trichloroethene	79-01-6	41.0	10	41.0	10	0.0
Tetrachloroethene	127-18-4	<10	10	<10	10	0.0

AECOM
 40 British American Boulevard
 Latham, NY 12110

Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French

Beacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Sample Duplicate RPD Summary
Soil-Gas Sample Analysis by EPA Method 8260C

Duplicate Sample: SGP-FF3-DUP Sample: SGP-FF3 Average RPD: 0.00%

Analyte	CAS#	Duplicate Result (ng)	LOQ (ng)	Sample Result (ng)	LOQ (ng)	RPD (%)
Vinyl Chloride	75-01-4	<10	10	<10	10	0.0
1,1-Dichloroethene	75-35-4	<10	10	<10	10	0.0
trans-1,2-Dichloroethene	156-60-5	<10	10	<10	10	0.0
cis-1,2-Dichloroethene	156-59-2	<10	10	<10	10	0.0
1,1,1-Trichloroethane	71-55-6	<10	10	<10	10	0.0
Trichloroethene	79-01-6	<10	10	<10	10	0.0
Tetrachloroethene	127-18-4	<10	10	<10	10	0.0

AECOM
40 British American Boulevard
Latham, NY 12110

Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French

Beacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Additional QC Information

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024*Laboratory Certification List*

Certification ID	Certification No.	Description	Expires	Project Required
Alaska CS-LAP	19-002	Alaska Department of Environmental Conservation	12/30/2024	
Colorado	MD010912023	Colorado Division of Oil and Public Safety	11/23/2024	
DoD-ELAP	72690/L22-563	United States Department of Defense Environmental Laboratory Accreditation	11/30/2024	
ISO/IEC 17025:2017	72690/L22-563	General Requirements for the Competence of Testing and Calibration Laboratories	11/30/2024	
NEFAP	72690/L22-564	TNI National Environmental Field Activities Program (NEFAP)	11/30/2024	
NY-NELAP	12097	New York Department of Health	04/01/2025	
Utah-NELAP	MD010912024-15	Utah Department of Health	12/31/2024	
Washington State	C1085	The State of Washington Department of Ecology	05/23/2025	

AECOM
40 British American Boulevard
Latham, NY 12110**Site Name:** NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Qualifiers/Notes and Definitions

General Definitions:

DF	Dilution Factor
DL	Detection Limit
LOD	Limit of Detection
LOQ	Limit of Quantitation
NA	Not Applicable
Q	Qualifier
%RE	Percent Relative Error
RPD	Relative Percent Difference
RT	Retention Times in Minutes
RRT	Evaluation of Relative Retention Times in RRT Units (qualified if outside ± 0.06 control limits)
RV	Calibration reference value
VISL	EPA Vapor Intrusion Screening Level
3σ	Uncertainty
∉	Compound not on scope of accreditation
+	values are outside method/contract required QC limits
∅	Compound not on scope of accreditation and analyzed with a one-point calibration

AECOM
40 British American Boulevard
Latham, NY 12110

Site Name: NOW Corporation
Site Location: Stratsburg, NY
Project Manager: Chris French

Beacon Proposal: 240312R01
Lab Work Order: 0007994
Reported: 09/17/2024

Sample Management Records

Project Information				Client Information			
Site Name: <u>NOW Corporation</u>				Company Name: <u>AECOM</u>		Project Manager: <u>Lindsay Mitchell</u>	
Site Location: <u>2092 Route 9G, Staatsburg, NY</u>				Office Location: <u>Latham, NY</u>		Client PO: <u>1667120</u>	
				Submitted by: <u>Mike Izdebski</u>		Turn around time (check one):	
				Email: <u>Lindsay.Mitchell@aecom.com</u>		☒ Normal ☐ Rush (specify) _____ days	
Field Sample ID	Start Date	Start Time	Stop Date	Stop Time	Sampling Hole Depth ☐ cm ☒ inches	Surface Type (Soil, Asphalt, Concrete, Gravel)	Optional Information (Location Description, Sample Condition, PID / FID Readings, etc)
SGP-AA1	8/21/24	0935	9/4/24	1304	36"	Soil	7.6 ppm
SGP-AA2		0943	9/4/24	1310			4.0 ppm
SGP-AA3		0948	9/4/24	1312			2.1 ppm
SGP-BB1		0952	9/4/24	1313			7.7 ppm
SGP-BB2		0957	9/4/24	1315			5.0 ppm
SGP-BB3		1005	9/4/24	1316			5.6 ppm
SGP-CC1		1016	9/4/24	1317			6.4 ppm
SGP-CC2		1019	9/4/24	1318			0.6 ppm
SGP-CC3		1022	9/4/24	1319			0.5 ppm
SGP-CC4		1026	9/4/24	1320			0.4 ppm
SGP-CC5		1030	9/4/24	1321			1.7 ppm
SGP-DD1		1036	9/4/24	1323			2.0 ppm
SGP-DD2		1045	9/4/24	1325			1.7 ppm
SGP-DD3		1048	9/4/24	1326			0.2 ppm
SGP-DD4	V	1050	9/4/24	1327	V	V	0.8 ppm
Special Instructions: <u>SGP-MS vial broke at ~ 1013 on 9/5/24, contents immediately bagged and placed in poly bottle. Contents transferred to transport vial at ~ 1515 on 9/5/24. Milwaukee brand ultra fine pen accidentally used on 10 samples. All 10 samples bagged separately with trip blank #5.</u>							
Relinquished by (signature): <u>Mike Izdebski</u>		Date / Time: <u>9/5/24 1400</u>		Received by (signature): <u>Antonia Anderson</u>		Date / Time: <u>9/6/24 10:59</u>	
Relinquished by (signature):		Date / Time:		Received by (signature):		Date / Time:	
For Lab Use Only		Beacon Job No: <u>7994</u>		Beacon Proposal: <u>240312R01</u>		Analytical Method: <u>8260C</u>	
Courier Name: <u>Fedex</u>		Shipment Condition: <u>good</u>		Custody Seal Intact: ☒ Yes ☐ No ☐ n/a		Custody Seal No: <u>6393614</u>	

Project Information				Client Information			
Site Name: <u>Now Corp</u>				Company Name: <u>AECOM</u>		Project Manager: <u>Lindsay Mitchell</u>	
Site Location: <u>2092 Route 96, Staatsburg, NY</u>				Office Location: <u>Latham, NY</u>		Client PO: <u>1667128</u>	
Submitted by: <u>Mike Izdebski</u>				Turn around time (check one):			
Email: <u>lindsay.mitchell@aecom.com</u>				☒ Normal ☐ Rush (specify) _____ days			
Field Sample ID	Start Date	Start Time	Stop Date	Stop Time	Sampling Hole Depth cm inches	Surface Type (Soil, Asphalt, Concrete, Gravel)	Optional Information (Location Description, Sample Condition, PID / FID Readings, etc)
SGP-DD5	8/21/24	1041054	9/4/24	1328	36"	Soil	2.2 ppm
SGP-DD6		1059	9/4/24	1330			6.3 ppm
SGP-DD SGP-EE1		1112	9/4/24	1332			1.1 ppm 2.6 ppm
SGP-EE2		1115	9/4/24	1333			0.4 ppm 1.1 ppm
SGP-EE3		1120	9/4/24	1334			0.4 ppm
SGP-EE4		1124	9/4/24	1335			3.0 ppm
SGP-EE5		1128	9/4/24	1337			2.7 ppm
SGP-EE6		1131	9/4/24	1338			0.8 ppm
SGP-FF1		1134	9/4/24	1418			0.7 ppm
SGP-FF2		1138	9/4/24	1420			5.9 ppm
SGP-FF3		1251	9/4/24	1421		↓	232.8 ppm High PID could be from fuel.
SGP-FF4		1304	9/4/24	1423		Gravel	83.5 ppm High PID could be from fuel.
SGP-FF5		1309	9/4/24	1424		Gravel	6.5 ppm
SGP-GG1		1315	9/4/24	1426		Soil	0.1 ppm
SGP-GG2		1318	9/4/24	1427		Soil	1.9 ppm
SGP-GG3		1321	9/4/24	1428	↓	Soil	13.4 ppm
SGP-GG4		1327	9/4/24	1430	33"	Gravel	2.5 ppm
SGP-HH1		1334	9/4/24	1438	36"	Soil	0.4 ppm
SGP-HH2		1342	9/4/24	1440	36"	Soil	4.4 ppm
SGP-HH3	✓	1349	9/4/24	1441	33"	Gravel	1.0 ppm
Special Instructions:							
For Lab Use Only		Beacon Job No: <u>7994</u>		Beacon Proposal: <u>240312R01</u>		Analytical Method: <u>8260C</u>	

Project Information				Client Information			
Site Name: Now Corporation		Company Name: AECOM		Project Manager: Lindsay Mitchell			
Site Location: 2092, Route 96, Staatsburg, NY		Office Location: Latham, NY		Client PO: 1667120			
		Submitted by: Mike Idebski		Turn around time (check one):			
		Email: lindsay.mitchell@aecom.com		☒ Normal ☐ Rush (specify) _____ days			
Field Sample ID	Start Date	Start Time	Stop Date	Stop Time	Sampling Hole Depth ■ cm ☒ inches	Surface Type (Soil, Asphalt, Concrete, Gravel)	Optional Information (Location Description, Sample Condition, PID / FID Readings, etc)
SGP- II3 ^{II4} II1 ^{II2}	8/21/24	1355	9/1/24	1447	36"	gravel	3.3 ppm
SGP-II7		1410	9/1/24	1443	36"	concrete	0.3 ppm
SGP-II2		1416	9/1/24	1444	36"	Soil	1.7 ppm
SGP-II3		1425	9/1/24	1446	36"	Soil gravel	1.2 ppm
SGP-JJ1		1435	9/1/24	1450	36"	Soil	1.1 ppm
SGP-JJ2		1440	9/1/24	1452	36"	Soil	10.3 ppm
SGP-KK1		1445	9/1/24	1448	36"	Soil	0.1 ppm
SGP-KK2		1450	9/1/24	1449	36"	Soil	0.2 ppm
SGP-LL1		1455	9/1/24	1453	36"	Soil	2.6 ppm
SGP-A1		1522	9/1/24	1144	36"	Soil	0.6 ppm
SGP-A2		1525	9/1/24	1113	36"	Soil	0.7 ppm
SGP-A3		1528	9/1/24	1111	36"	Soil	0.5 ppm
SGP-B1		1531	9/1/24	1115	36"	Soil	0.3 ppm
SGP-B2		1533	9/1/24	1116	36"	Soil	0.5 ppm
SGP-B3		1535	9/1/24	1117	36"	Soil	0.4 ppm
SGP-B4		1537	9/1/24	1118	36"	Soil	0.5 ppm
SGP-C1		1543	9/1/24	1129	36"	Soil Asphalt	1.7 ppm
SGP-C2		1545	9/1/24	1132	36"	Soil	1.0 ppm
SGP-C3		1549	9/1/24	1136	36"	Soil	0.5 ppm
SGP-C4	✓	1555	9/1/24	1137	36"	Soil	11.9 ppm
Special Instructions:							
For Lab Use Only		Beacon Job No: 7994		Beacon Proposal: 240312R01		Analytical Method: 8260C	

Project Information				Client Information			
Site Name: <u>Now Corporation.</u>		Company Name: <u>AECOM</u>		Project Manager: <u>Lindsay Mitchell</u>			
Site Location: <u>2092 Route 96</u> <u>Staatsburg, NY</u>		Office Location: <u>Latham, NY</u>		Client PO: <u>1667120</u>			
		Submitted by: <u>Mike Izdebski</u>		Turn around time (check one):			
		Email: <u>lindsay.mitchell@aecom.com</u>		☒ Normal ☐ Rush (specify) _____ days			
Field Sample ID	Start Date	Start Time	Stop Date	Stop Time	Sampling Hole Depth ■ cm ■ inches	Surface Type (Soil, Asphalt, Concrete, Gravel)	Optional Information (Location Description, Sample Condition, PID / FID Readings, etc)
SGP-C5	8/21/24	1600	9/4/24	1138	36"	Asphalt	1.8 ppm
SGP-C6		1606	9/4/24	1146	36"	Soil	1.0 ppm
SGP-C7		1613	9/4/24	1141	36"	Soil	1.3 ppm
SGP-A4		1616	9/4/24	1108	36"	Asphalt (Broken)	0.6 ppm
SGP-A5		1620	9/4/24	1106	36"	Soil	0.9 ppm
SGP-A6		1625	9/4/24	1105	36"	Soil	1.0 ppm
SGP-B5		1629	9/4/24	1121	36"	Asphalt	0.5 ppm
SGP-B6		1636	9/4/24	1130	36"	Asphalt	12.1 ppm
SGP-A7		1647	9/4/24	1103	36"	Soil	12.6 ppm
SGP-A8		1651	9/4/24	1102	36"	Soil	0.4 ppm
SGP-B7		1658	9/4/24	1051	36"	Soil	1.9 ppm
SGP-B8		1701	9/4/24	1050	36"	Soil	1.2 ppm
SGP-B9		1706	9/4/24	1049	36"	Soil	13.2 ppm
SGP-C10		1713	9/4/24	1047	36"	Soil	22.6 ppm
SGP-C8		1718	9/4/24	1036	36"	Soil	3.8 ppm
SGP-C9		1721	9/4/24	1043	36"	Soil	1.6 ppm
SGP-D2	8/22/24	0915	9/4/24	1631	36"	Soil	0.7 ppm
SGP-D1		0920	9/4/24	1632	36"	Asphalt	0.8 ppm
SGP-E3		0932	9/4/24	1633	36"	Soil	0.2 ppm
SGP-E2		0940	9/4/24	1634	36"	Soil	0.6 ppm
Special Instructions:							
For Lab Use Only		Beacon Job No: <u>7994</u>		Beacon Proposal: <u>240312R01</u>		Analytical Method: <u>8260C</u>	

Project Information				Client Information			
Site Name: <u>Now Corporation</u>				Company Name: <u>AECOM</u>		Project Manager: <u>Lindsay Mitchell</u>	
Site Location: <u>2092 Route 96 Staatsburg, NY</u>				Office Location: <u>Latham, NY</u>		Client PO: <u>1667120</u>	
				Submitted by: <u>Mike Izdebski</u>		Turn around time (check one):	
				Email: <u>lindsay-mitchell@aecom.com</u>		☒ Normal ☐ Rush (specify) _____ days	
Field Sample ID	Start Date	Start Time	Stop Date	Stop Time	Sampling Hole Depth ■ cm ▲ inches	Surface Type (Soil, Asphalt, Concrete, Gravel)	Optional Information (Location Description, Sample Condition, PID / FID Readings, etc)
SGP-E1	8/22/24	0947	9/4/24	1636	36"	Asphalt	8.2 ppm
SGP-F2		0955	9/4/24	1638	36"	Soil	1.5 ppm
SGP-F1		1002	9/4/24	1640	36"	Asphalt	2.1 ppm
SGP-G2		1015	9/4/24	1643	36"	Asphalt	2.6 ppm
SGP-G1		1020	9/4/24	1649	36"	Asphalt	4.1 ppm
SGP-H8		1037	9/4/24	1650	36"	Soil	1.2 ppm
SGP-H7		1042	9/4/24	1652	36"	Asphalt	1.7 ppm
SGP-H6		1047	9/4/24	1654	36"	Asphalt	130.9 ppm
SGP-H5		1107	9/4/24	1657	36"	Asphalt	38.4 ppm
SGP-H4		1125	9/4/24	1705	36"	Asphalt	3.7 ppm
SGP-H3		1130	9/4/24	1705	36"	Asphalt	1.6 ppm
SGP-H2		1140	9/4/24	1706	36"	Asphalt	1.9 ppm
SGP-H1		1145	9/4/24	1702	36"	Asphalt	0.9 ppm
SGP-I1		1150	9/4/24	1723	36"	Asphalt	1.4 ppm
SGP-I2		1157	9/4/24	1718	36"	Asphalt	0.7 ppm
SGP-I3		1201	9/4/24	1715	36"	Asphalt	5.0 ppm
SGP-I4		1204	9/4/24	1714	36"	Asphalt	2.4 ppm
SGP-I5		1208	9/4/24	1711	36"	Asphalt	1.9 ppm
SGP-I6		1257	9/4/24	1709	36"	Soil	2.9 ppm
SGP-I7	✓	1305	9/4/24	1708	36"	Soil	0.5 ppm
Special Instructions:							
For Lab Use Only		Beacon Job No: <u>7994</u>		Beacon Proposal: <u>240312R01</u>		Analytical Method: <u>8260C</u>	

Project Information				Client Information			
Site Name: Now Corporation		Company Name: AECOM		Project Manager: Lindsay Mitchell			
Site Location: 2042 Route 46, Staatsburg, NY		Office Location: Latham, NY		Client PO: 1667120			
		Submitted by: Mike Izdebski		Turn around time (check one):			
		Email: lindsay.mitchell@aecom.com		☒ Normal ☐ Rush (specify) _____ days			
Field Sample ID	Start Date	Start Time	Stop Date	Stop Time	Sampling Hole Depth ■ cm X inches	Surface Type (Soil, Asphalt, Concrete, Gravel)	Optional Information (Location Description, Sample Condition, PID / FID Readings, etc)
SGP-I8	8/22/24	1310	9/14/24	1707	36"	Gravel	3.2 ppm
SGP-J7		1316	9/14/24	1747	36"	Concrete	0.2 ppm
SGP-K8		1325	9/14/24	1749	36"	concrete.	0.7 ppm
SGP-K7		1333	9/14/24	1752	36"	concrete	1.0 ppm
SGP-K6		1344	9/14/24	1757	30"	concrete	8.4 ppm
SGP-J6		1349	9/14/24	1742	36"	concrete	0.5 ppm
SGP-J5		1357	9/14/24	1740	36"	concrete	0.9 ppm
SGP-K5		1405	9/14/24	1803	36"	Concrete	0.7 ppm
SGP-J4		1412	9/14/24	1737	36"	Concrete	1.0 ppm
SGP-K4		1420	9/14/24	1806	36"	concrete	0.5 ppm
SGP-K3		1429	9/4/24	1809	36"	concrete	3.0 ppm
SGP-J3		1436	9/4/24	1735	36"	Concrete	2.9 ppm
SGP-L4		1442	9/14/24	1818	36"	concrete	1.1 ppm
SGP-L3		1445	9/14/24	1817	36"	concrete.	1.9 ppm
SGP-L2		1451	9/14/24	1813	36"	Soil	5.9 ppm
SGP-L6		1505	9/14/24	1825	36"	Concrete	1.3 ppm
SGP-L7		1503	9/14/24	1828	36"	Concrete	1.1 ppm
SGP-L5		1510	9/14/24	1822	36"	concrete	0.8 ppm
SGP-M8		1515	9/15/24	0956	36"	concrete	17.3 ppm
SGP-M7		1519	9/15/24	0956	36"	concrete	2.3 ppm
Special Instructions:							
For Lab Use Only		Beacon Job No: 7994		Beacon Proposal: 240312R01		Analytical Method: 8260C	

Project Information				Client Information			
Site Name: Now Corporation				Company Name: AECOM		Project Manager: Lindsay Mitchell	
Site Location: 2092 Route 96, Staatsburg, NY				Office Location: Catham, NY		Client PO: 1667126	
				Submitted by: Mike Izdebski		Turn around time (check one):	
				Email: lindsay.mitchell@aecom.com		☒ Normal ☐ Rush (specify) _____ days	

Field Sample ID	Start Date	Start Time	Stop Date	Stop Time	Sampling Hole Depth cm ☐ inches ☒	Surface Type (Soil, Asphalt, Concrete, Gravel)	Optional Information (Location Description, Sample Condition, PID / FID Readings, etc)
SGP-M6	8/22/24	1525	9/5/24	1005	36"	concrete	1.9 ppm
SGP-M5		1547	9/5/24	1013	36"	concrete	2.6 ppm
SGP-M4		1555	9/5/24	1021	36"	concrete	1.9 ppm
SGP-M3		1603	9/5/24	1025	36"	concrete	1.9 ppm
SGP-N3		1606	9/5/24	1031	36"	concrete	1.3 ppm
SGP-N4		1610	9/5/24	1033	36"	concrete	2.1 ppm
SGP-N5		1614	9/5/24	1040	36"	concrete	3.0 ppm
SGP-N6		1620	9/5/24	1042	36"	concrete	6.1 ppm
SGP-N7		1633	9/5/24	1046	36"	concrete	16.2 ppm
SGP-J2		1652	9/4/24	1731	36"	soil	1.0 ppm
SGP-J1		1700	9/4/24	1729	36"	gravel	3.0 ppm
SGP-K2		1704	9/5/24	1102	36"	soil	0.9 ppm
SGP-K1		1708	9/5/24	1105	36"	gravel	9.4 ppm
SGP-L1		1717	9/5/24	1101	36"	soil	2.3 ppm
SGP-M1		1719	9/5/24	1114	36"	gravel	19.0 ppm
SGP-M2		1724	9/5/24	1056	36"	soil	2.8 ppm
SGP-N1		1731	9/5/24	1125	36"	gravel	2.8 ppm
SGP-N2		1734	9/5/24	1053	36"	soil	93.9 ppm
SGP-Q1	8/13/24	0858	9/4/24	1530	36"	soil	2.2 ppm
SGP-P1	1	0900	9/4/24	1529	36"	soil	9.0 ppm


Special Instructions:

For Lab Use Only	Beacon Job No: 7994	Beacon Proposal: 240312R01	Analytical Method: 8260C
------------------	----------------------------	-----------------------------------	---------------------------------

Project Information				Client Information			
Site Name: now corporation				Company Name: AECOM		Project Manager: Lindsay Mitchell	
Site Location: 2092 Route 46 Stearnsbury, NY				Office Location: Latham, NY		Client PO: 1667120	
				Submitted by: Mike Izdebski		Turn around time (check one):	
				Email: lindsay.mitchell@aecom.com		☒ Normal ☐ Rush (specify) _____ days	
Field Sample ID	Start Date	Start Time	Stop Date	Stop Time	Sampling Hole Depth cm ☐ inches ☒	Surface Type (Soil, Asphalt, Concrete, Gravel)	Optional Information (Location Description, Sample Condition, PID / FID Readings, etc)
SGP-02	8/23/24	0905	9/4/24	1559	36"	gravel	2.8 ppm
SGP-P2		0910	9/4/24	1527	36"	Soil	4.5 ppm
SGP-03		0912	9/4/24	1600	36"	soil/gravel	0.7 ppm
SGP-P3		0917	9/4/24	1523	36"	Soil	1.8 ppm
SGP-04		0916	9/4/24	1602	36"	gravel	0.7 ppm
SGP-05		0918	9/4/24	1604	36"	gravel	1.3 ppm
SGP-06		0920	9/4/24	1605	36"	soil	1.2 ppm
SGP-07		0922	9/4/24	1606	36"	soil	2.8 ppm
SGP-08		0924	9/4/24	1607	36"	soil	1.7 ppm
SGP-09		0926	9/4/24	1608	36"	soil	7.3 ppm
SGP-010		0930	9/4/24	1609	36"	soil	0.6 ppm
SGP-011		0934	9/4/24	1517	36"	soil	1.4 ppm
SGP-P4		0939	9/4/24	1520	36"	soil	5.1 ppm
SGP-P5		0941	9/4/24	1519	36"	soil	1.8 ppm
SGP-012		0943	9/4/24	1515	36"	gravel	1.5 ppm
SGP-013		0947	9/4/24	1517	36"	asphalt	2.4 ppm
SGP-014		0949	9/4/24	1518	36"	soil	1.2 ppm
SGP-NN1		1030	9/4/24	1506	36"	soil	3.4 ppm
SGP-NN2		1037	9/4/24	1508	36"	soil	2.1 ppm
SGP-NN3		1039	9/4/24	1509	36"	soil	3.4 ppm
Special Instructions:							
For Lab Use Only		Beacon Job No: 7994		Beacon Proposal: 240312R01		Analytical Method: B2600C	

Project Information				Client Information			
Site Name: NOW Corporation.		Company Name: AECOM		Project Manager: Lindsay Mitchell			
Site Location: 2042 Route 96 Staatsburg, NY		Office Location: Latham, NY		Client PO: 1667120			
Submitted by: Mike Izdebski		Email: lindsay.mitchell@aecom.com lindsay.mitchell@aecom.com		Turn around time (check one): ☒ Normal ☐ Rush (specify) _____ days			
Field Sample ID	Start Date	Start Time	Stop Date	Stop Time	Sampling Hole Depth ☐ cm ☒ inches	Surface Type (Soil, Asphalt, Concrete, Gravel)	Optional Information (Location Description, Sample Condition, PID / FID Readings, etc)
SGP-MM1	08/23/29	1043	9/4/24	1456	36"	Gravel/Dirt	2.6 ppm
SGP-MM2		1046	9/4/24	1459	36"	Dirt	0.5 ppm
SGP-MM3		1052	9/4/24	1503	36"	Dirt	0.6 ppm
SGP-Z3		1058	9/4/24	1434	36"	Dirt	5.0 ppm
SGP- Z1 Z1		1100	9/4/24	1432	36"	Dirt	2.0 ppm
SGP-Z2		1104	9/4/24	0920 1433	36"	Dirt	3.6 ppm
SGP-Y1		1108	9/4/24	0911	36"	Dirt	1.2 ppm
SGP-Y2		1116	9/4/24	0920	36"	Dirt	2.6 ppm
SGP-X1		1120	9/4/24	0925	36"	Dirt	6.2 ppm
SGP-X2		1125	9/4/24	0928	36"	Dirt	0.7 ppm
SGP-W1		1127		0931	36"	Dirt	0.5 ppm
SGP-W2		1130		0950	36"	Soil	2.6 ppm
SGP-V1		1134		0932	36"	Soil	3.4 ppm
SGP-V2		1132		0934	36"	Soil	1.9 ppm
SGP-V3		1137		0936	36"	Soil	3.2 ppm
SGP-U3		1142		0953	36"	Soil	2.1 ppm
SGP-U2		1145		0958	36"	Soil	3.8 ppm
SGP-U1		1148		0937	36"	Soil	1.9 ppm
SGP-T1		1153		0942	36"	Soil	2.6 ppm
SGP-T2		1156		0943	36"	Soil	1.0 ppm
Special Instructions:							
For Lab Use Only		Beacon Job No: 7994		Beacon Proposal: 240312R01		Analytical Method: 8260C	

Project Information				Client Information			
Site Name: <u>Now Corporation</u>		Company Name: <u>AECOM</u>		Project Manager: <u>Lindsay Mittle</u>			
Site Location: <u>2092 Route 96, Staatsburg, NY</u>		Office Location: <u>Latham, NY</u>		Client PO: <u>1667120</u>			
Submitted by: <u>Mike Izdebski</u>		Email: <u>lindsay.mittle@aecom.com</u>		Turn around time (check one): ☒ Normal ☐ Rush (specify) _____ days			
Field Sample ID	Start Date	Start Time	Stop Date	Stop Time	Sampling Hole Depth ☐ cm ☒ inches	Surface Type (Soil, Asphalt, Concrete, Gravel)	Optional Information (Location Description, Sample Condition, PID / FID Readings, etc)
SGP-T3	08/23/24	1206	9/04/24	0949	30"	Soil	7.3 ppm
SGP-S1		1252	9/4/24	0948	36"	Soil	1.0 ppm
SGP-S2		1254	9/4/24	0956	36"	Soil	2.0 ppm
SGP-S3		1256	9/4/24	0959	30"	Soil	6.3 ppm
SGP-R1		1300	9/4/24	1005	36"	Soil	2.0 ppm
SGP-R2		1301	9/4/24	1007	36"	Soil	0.8 ppm
SGP-R3		1305	9/4/24	1008	30"	Soil	34.4 ppm
SGP-R4		1321	9/4/24	1030	36"	Soil	11.2 ppm - 11.2
SGP-Q1		1308	9/4/24	1011	36"	Soil	6.9 ppm
SGP-Q2		1311	9/4/24	1014	36"	Soil	5.4 ppm
SGP-Q3		1315	9/4/24	1035	36"	Soil	2.1 ppm
SGP-MØ		1345	9/5/24	1121	36"	Soil	1.0 ppm
SGP-KØ		1355	9/5/24	1113	36"	asphalt	5.0 ppm
SGP-KØØ		1356	9/5/24	1153	36"	asphalt	5.0 ppm
SGP-JØ		1400	9/4/24	1729	36"	Dirt	4.1 ppm
SGP-JØØ		1405	9/4/24	1728	36"	Dirt	2.2 ppm
SGP-FF3-DUP	8/21/24	1251	9/4/24	1421	36"	Soil	See SGP-FF3
SGP-AA1-DUP	8/21/24	0935	9/4/24	1308	36"	Soil	See SGP-AA1
SGP-CC5-DUP	8/21/24	1030	9/4/24	1324	36"	Soil	See see SGP-CC6
SGP-M1-DUP	8/22/24	1119 1119	9/5/24	1119	36"	gravel	See SGP-M1
Special Instructions:							
For Lab Use Only		Beacon Job No: <u>7994</u>		Beacon Proposal: <u>240312R01</u>		Analytical Method: <u>8260C</u>	

Project Information				Client Information			
Site Name: <u>Now corporation</u>				Company Name: <u>AECOM</u>		Project Manager: <u>Lindsay Mitchell</u>	
Site Location: <u>2092 Route 46, Staatsburg, NY</u>				Office Location: <u>Latham, NY</u>		Client PO: <u>1667126</u>	
Submitted by: <u>Mike Izdebski</u>				Email: <u>lindsay.mitchell@aecom.com</u>		Turn around time (check one): ☒ Normal ☐ Rush (specify) _____ days	
Field Sample ID	Start Date	Start Time	Stop Date	Stop Time	Sampling Hole Depth ☐ cm ☒ inches	Surface Type (Soil, Asphalt, Concrete, Gravel)	Optional Information (Location Description, Sample Condition, PID / FID Readings, etc)
SGP-H6-DUP	8/22/24	1047	9/4/24	1654	36"	asphalt	see SGP-H6
SGP-P4-DUP	8/23/24	0939	9/4/24	1520	36"	Soil	see SGP-P4
SGP-R4-DUP	8/23/24	1321	9/4/24	1636	36"	Soil	see SGP-R4
SGP-O8-DUP	8/23/24	0924	9/4/24	1607	36"	Soil	see SGP-O8
SGP-K1-DUP	8/22/24	1708	9/5/24	1105	36"	gravel	see SGP-K1
SGP-B1-DUP	8/21/24	1531	9/4/24	1115	36"	Soil	see SGP-B1
Trip1	-	-	-	-	-	-	<u>Added 9/6/24 AA</u> 
Trip2	-	-	-	-	-	-	
Trip3	-	-	-	-	-	-	
Trip4	-	-	-	-	-	-	
Trip5	-	-	-	-	-	-	
Special Instructions:							
For Lab Use Only		Beacon Job No: <u>7994</u>		Beacon Proposal: <u>240312R01</u>		Analytical Method: <u>8260C</u>	



Beacon Environmental

526 Underwood Lane
Bel Air, MD 21014 USA
1.410.838.8780

CERTIFICATE OF ANALYSIS

Beacon Proposal No.: 240312R01

Beacon Project No.: 0007994

Project Description:

Project Site: NOW Corporation
Stratsburg, NY

Client PO No.: 60631041-.07.01F

Prepared for:

Chris French

AECOM

40 British American Boulevard

Latham, NY 12110

Ryan W. Schneider
Senior Project Manager

September 20, 2024

All data meet requirements as specified in the Beacon Environmental Services, Inc. Quality Assurance Project Plan and the results relate only to the samples reported. The work performed was in accordance with ISO/IEC 17025:2017 requirements, except samples were analyzed within a 24-hour tune window. This report shall not be reproduced, except in full, without written approval of the laboratory. Release of the data contained in this data package has been authorized by the Laboratory Director or his signee, as verified by the following signatures:

Steven C. Thornley
Laboratory Director

Peter B. Kelly
Quality Manager

AECOM
40 British American Boulevard
Latham, NY 12110**Project Site:** NOW Corporation
Project Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Beacon Project No.: 0007994
Reported: 09/20/2024***Summary of Compound Detections- Mass***

Lab Sample ID: 0007994-09	SGP-A4 Soil Gas	Method: EPA 8260C
---------------------------	---------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
Trichloroethene	79-01-6	36		10	S24090913.D

Lab Sample ID: 0007994-11	SGP-A6 Soil Gas	Method: EPA 8260C
---------------------------	---------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
1,1-Dichloroethene	75-35-4	28		10	S24090915.D
trans-1,2-Dichloroethene	156-60-5	50		10	S24090915.D
cis-1,2-Dichloroethene	156-59-2	303		10	S24090915.D
Trichloroethene	79-01-6	2,390		10	S24090915.D

Lab Sample ID: 0007994-19	SGP-B5 Soil Gas	Method: EPA 8260C
---------------------------	---------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
cis-1,2-Dichloroethene	156-59-2	13		10	S24090923.D
Trichloroethene	79-01-6	140		10	S24090923.D

Lab Sample ID: 0007994-21	SGP-B7 Soil Gas	Method: EPA 8260C
---------------------------	---------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
cis-1,2-Dichloroethene	156-59-2	43		10	S24090927.D
Trichloroethene	79-01-6	741		10	S24090927.D

AECOM
40 British American Boulevard
Latham, NY 12110**Project Site:** NOW Corporation
Project Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Beacon Project No.: 0007994
Reported: 09/20/2024*Summary of Compound Detections- Mass*

Lab Sample ID: 0007994-22	SGP-B8 Soil Gas	Method: EPA 8260C
---------------------------	---------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
Trichloroethene	79-01-6	20		10	S24090928.D

Lab Sample ID: 0007994-28	SGP-C5 Soil Gas	Method: EPA 8260C
---------------------------	---------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
cis-1,2-Dichloroethene	156-59-2	23		10	S24090934.D
Trichloroethene	79-01-6	282		10	S24090934.D
Tetrachloroethene	127-18-4	1,060		10	S24090934.D

Lab Sample ID: 0007994-30	SGP-C7 Soil Gas	Method: EPA 8260C
---------------------------	---------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
Trichloroethene	79-01-6	27		10	S24090936.D

Lab Sample ID: 0007994-36	SGP-E1 Soil Gas	Method: EPA 8260C
---------------------------	---------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
Vinyl Chloride	75-01-4	153		10	S24090942.D
1,1-Dichloroethene	75-35-4	258		10	S24090942.D
trans-1,2-Dichloroethene	156-60-5	129		10	S24090942.D
cis-1,2-Dichloroethene	156-59-2	767		10	S24090942.D
Trichloroethene	79-01-6	1,300		10	S24090942.D

AECOM
40 British American Boulevard
Latham, NY 12110**Project Site:** NOW Corporation
Project Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Beacon Project No.: 0007994
Reported: 09/20/2024*Summary of Compound Detections- Mass*

Lab Sample ID: 0007994-39	SGP-F1 Soil Gas	Method: EPA 8260C
---------------------------	---------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
Vinyl Chloride	75-01-4	11		10	S24090945.D
1,1-Dichloroethene	75-35-4	31		10	S24090945.D
trans-1,2-Dichloroethene	156-60-5	27		10	S24090945.D
cis-1,2-Dichloroethene	156-59-2	164		10	S24090945.D
Trichloroethene	79-01-6	1,180		10	S24090945.D

Lab Sample ID: 0007994-41	SGP-G1 Soil Gas	Method: EPA 8260C
---------------------------	---------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
Vinyl Chloride	75-01-4	20		10	C24090917.D
1,1-Dichloroethene	75-35-4	18		10	C24090917.D
trans-1,2-Dichloroethene	156-60-5	484		10	C24090917.D
cis-1,2-Dichloroethene	156-59-2	3,280		10	C24090917.D
Trichloroethene	79-01-6	1,140		10	C24090917.D

Lab Sample ID: 0007994-42	SGP-G2 Soil Gas	Method: EPA 8260C
---------------------------	---------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
trans-1,2-Dichloroethene	156-60-5	14		10	C24090918.D
cis-1,2-Dichloroethene	156-59-2	104		10	C24090918.D
Trichloroethene	79-01-6	285		10	C24090918.D

AECOM
40 British American Boulevard
Latham, NY 12110

Project Site: NOW Corporation
Project Location: Stratsburg, NY
Project Manager: Chris French

Beacon Proposal: 240312R01
Beacon Project No.: 0007994
Reported: 09/20/2024

Summary of Compound Detections- Mass

Lab Sample ID: 0007994-43	SGP-H1 Soil Gas	Method: EPA 8260C
---------------------------	---------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
Vinyl Chloride	75-01-4	13		10	C24090919.D
1,1-Dichloroethene	75-35-4	47		10	C24090919.D
cis-1,2-Dichloroethene	156-59-2	15		10	C24090919.D
1,1,1-Trichloroethane	71-55-6	45		10	C24090919.D
Trichloroethene	79-01-6	282		10	C24090919.D

Lab Sample ID: 0007994-44	SGP-H2 Soil Gas	Method: EPA 8260C
---------------------------	---------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
Vinyl Chloride	75-01-4	310		10	C24090920.D
1,1-Dichloroethene	75-35-4	1,120		10	C24090920.D
trans-1,2-Dichloroethene	156-60-5	76		10	C24090920.D
cis-1,2-Dichloroethene	156-59-2	471		10	C24090920.D
1,1,1-Trichloroethane	71-55-6	1,710		10	C24090920.D
Trichloroethene	79-01-6	8,050		10	C24090920.D
Tetrachloroethene	127-18-4	14		10	C24090920.D

Lab Sample ID: 0007994-45	SGP-H3 Soil Gas	Method: EPA 8260C
---------------------------	---------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
Vinyl Chloride	75-01-4	96		10	C24090921.D
1,1-Dichloroethene	75-35-4	300		10	C24090921.D
trans-1,2-Dichloroethene	156-60-5	43		10	C24090921.D
cis-1,2-Dichloroethene	156-59-2	238		10	C24090921.D
1,1,1-Trichloroethane	71-55-6	289		10	C24090921.D
Trichloroethene	79-01-6	2,500		10	C24090921.D

AECOM
40 British American Boulevard
Latham, NY 12110**Project Site:** NOW Corporation
Project Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Beacon Project No.: 0007994
Reported: 09/20/2024***Summary of Compound Detections- Mass***

Lab Sample ID: 0007994-46	SGP-H4 Soil Gas	Method: EPA 8260C
---------------------------	---------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
Vinyl Chloride	75-01-4	27		10	C24090922.D
1,1-Dichloroethene	75-35-4	36		10	C24090922.D
trans-1,2-Dichloroethene	156-60-5	98		10	C24090922.D
cis-1,2-Dichloroethene	156-59-2	799		10	C24090922.D
Trichloroethene	79-01-6	287		10	C24090922.D

Lab Sample ID: 0007994-47	SGP-H5 Soil Gas	Method: EPA 8260C
---------------------------	---------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
Vinyl Chloride	75-01-4	93		10	C24090923.D
1,1-Dichloroethene	75-35-4	171		10	C24090923.D
trans-1,2-Dichloroethene	156-60-5	351		10	C24090923.D
cis-1,2-Dichloroethene	156-59-2	2,810		10	C24090923.D
Trichloroethene	79-01-6	5,580		10	C24090923.D

Lab Sample ID: 0007994-48	SGP-H6 Soil Gas	Method: EPA 8260C
---------------------------	---------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
Vinyl Chloride	75-01-4	32		10	C24090924.D
trans-1,2-Dichloroethene	156-60-5	25		10	C24090924.D
cis-1,2-Dichloroethene	156-59-2	97		10	C24090924.D
Trichloroethene	79-01-6	396		10	C24090924.D

AECOM
40 British American Boulevard
Latham, NY 12110

Project Site: NOW Corporation
Project Location: Stratsburg, NY
Project Manager: Chris French

Beacon Proposal: 240312R01
Beacon Project No.: 0007994
Reported: 09/20/2024

Summary of Compound Detections- Mass

Lab Sample ID: 0007994-49	SGP-H6-DUP Soil Gas	Method: EPA 8260C
---------------------------	-------------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
Vinyl Chloride	75-01-4	35		10	C24090925.D
trans-1,2-Dichloroethene	156-60-5	23		10	C24090925.D
cis-1,2-Dichloroethene	156-59-2	91		10	C24090925.D
Trichloroethene	79-01-6	385		10	C24090925.D

Lab Sample ID: 0007994-50	SGP-H7 Soil Gas	Method: EPA 8260C
---------------------------	---------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
Vinyl Chloride	75-01-4	534		10	C24090926.D
1,1-Dichloroethene	75-35-4	281		10	C24090926.D
trans-1,2-Dichloroethene	156-60-5	303		10	C24090926.D
cis-1,2-Dichloroethene	156-59-2	2,520		10	C24090926.D
Trichloroethene	79-01-6	899		10	C24090926.D

Lab Sample ID: 0007994-51	SGP-H8 Soil Gas	Method: EPA 8260C
---------------------------	---------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
Vinyl Chloride	75-01-4	55		10	C24090927.D
trans-1,2-Dichloroethene	156-60-5	103		10	C24090927.D
cis-1,2-Dichloroethene	156-59-2	915		10	C24090927.D
Trichloroethene	79-01-6	18		10	C24090927.D

AECOM
 40 British American Boulevard
 Latham, NY 12110

Project Site: NOW Corporation
Project Location: Stratsburg, NY
Project Manager: Chris French

Beacon Proposal: 240312R01
Beacon Project No.: 0007994
Reported: 09/20/2024

Summary of Compound Detections- Mass

Lab Sample ID: 0007994-52	SGP-I1 Soil Gas	Method: EPA 8260C
---------------------------	---------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
Vinyl Chloride	75-01-4	23		10	C24090928.D
1,1-Dichloroethene	75-35-4	116		10	C24090928.D
cis-1,2-Dichloroethene	156-59-2	31		10	C24090928.D
1,1,1-Trichloroethane	71-55-6	141		10	C24090928.D
Trichloroethene	79-01-6	377		10	C24090928.D

Lab Sample ID: 0007994-53	SGP-I2 Soil Gas	Method: EPA 8260C
---------------------------	---------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
Vinyl Chloride	75-01-4	34		10	C24090929.D
1,1-Dichloroethene	75-35-4	95		10	C24090929.D
cis-1,2-Dichloroethene	156-59-2	17		10	C24090929.D
1,1,1-Trichloroethane	71-55-6	106		10	C24090929.D
Trichloroethene	79-01-6	232		10	C24090929.D

Lab Sample ID: 0007994-54	SGP-I3 Soil Gas	Method: EPA 8260C
---------------------------	---------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
cis-1,2-Dichloroethene	156-59-2	30		10	C24090930.D
Trichloroethene	79-01-6	457		10	C24090930.D

AECOM
40 British American Boulevard
Latham, NY 12110**Project Site:** NOW Corporation
Project Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Beacon Project No.: 0007994
Reported: 09/20/2024***Summary of Compound Detections- Mass***

Lab Sample ID: 0007994-55	SGP-I4 Soil Gas	Method: EPA 8260C
---------------------------	---------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
1,1-Dichloroethene	75-35-4	18		10	C24090931.D
cis-1,2-Dichloroethene	156-59-2	46		10	C24090931.D
Trichloroethene	79-01-6	847		10	C24090931.D
Tetrachloroethene	127-18-4	16		10	C24090931.D

Lab Sample ID: 0007994-56	SGP-I5 Soil Gas	Method: EPA 8260C
---------------------------	---------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
Trichloroethene	79-01-6	21		10	C24090932.D

Lab Sample ID: 0007994-57	SGP-I6 Soil Gas	Method: EPA 8260C
---------------------------	---------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
Trichloroethene	79-01-6	20		10	C24090933.D

Lab Sample ID: 0007994-59	SGP-I8 Soil Gas	Method: EPA 8260C
---------------------------	---------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
Vinyl Chloride	75-01-4	190		10	C24090935.D
1,1-Dichloroethene	75-35-4	527		10	C24090935.D
cis-1,2-Dichloroethene	156-59-2	55		10	C24090935.D
1,1,1-Trichloroethane	71-55-6	614		10	C24090935.D

AECOM
40 British American Boulevard
Latham, NY 12110**Project Site:** NOW Corporation
Project Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Beacon Project No.: 0007994
Reported: 09/20/2024*Summary of Compound Detections- Mass*

Lab Sample ID: 0007994-60	SGP-J0 Soil Gas	Method: EPA 8260C
---------------------------	---------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
Vinyl Chloride	75-01-4	11		10	C24090936.D
1,1-Dichloroethene	75-35-4	33		10	C24090936.D
1,1,1-Trichloroethane	71-55-6	48		10	C24090936.D

Lab Sample ID: 0007994-64	SGP-J3 Soil Gas	Method: EPA 8260C
---------------------------	---------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
1,1-Dichloroethene	75-35-4	19		10	S24091008.D
trans-1,2-Dichloroethene	156-60-5	39		10	S24091008.D
cis-1,2-Dichloroethene	156-59-2	352		10	S24091008.D
1,1,1-Trichloroethane	71-55-6	11		10	S24091008.D
Trichloroethene	79-01-6	988		10	S24091008.D

Lab Sample ID: 0007994-65	SGP-J4 Soil Gas	Method: EPA 8260C
---------------------------	---------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
1,1-Dichloroethene	75-35-4	15		10	S24091009.D
cis-1,2-Dichloroethene	156-59-2	39		10	S24091009.D
Trichloroethene	79-01-6	76		10	S24091009.D

Lab Sample ID: 0007994-66	SGP-J5 Soil Gas	Method: EPA 8260C
---------------------------	---------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
1,1-Dichloroethene	75-35-4	30		10	S24091010.D
1,1,1-Trichloroethane	71-55-6	22		10	S24091010.D
Trichloroethene	79-01-6	27		10	S24091010.D

AECOM
40 British American Boulevard
Latham, NY 12110**Project Site:** NOW Corporation
Project Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Beacon Project No.: 0007994
Reported: 09/20/2024*Summary of Compound Detections- Mass*

Lab Sample ID: 0007994-67	SGP-J6 Soil Gas	Method: EPA 8260C
---------------------------	---------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
1,1-Dichloroethene	75-35-4	25		10	S24091011.D
cis-1,2-Dichloroethene	156-59-2	38		10	S24091011.D
1,1,1-Trichloroethane	71-55-6	18		10	S24091011.D
Trichloroethene	79-01-6	671		10	S24091011.D

Lab Sample ID: 0007994-68	SGP-J7 Soil Gas	Method: EPA 8260C
---------------------------	---------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
1,1-Dichloroethene	75-35-4	13		10	S24091012.D
Trichloroethene	79-01-6	45		10	S24091012.D

Lab Sample ID: 0007994-71	SGP-K1 Soil Gas	Method: EPA 8260C
---------------------------	---------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
cis-1,2-Dichloroethene	156-59-2	10		10	S24091015.D

Lab Sample ID: 0007994-74	SGP-K3 Soil Gas	Method: EPA 8260C
---------------------------	---------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
Vinyl Chloride	75-01-4	35		10	S24091018.D
1,1-Dichloroethene	75-35-4	77		10	S24091018.D
1,1,1-Trichloroethane	71-55-6	94		10	S24091018.D
Trichloroethene	79-01-6	25		10	S24091018.D

AECOM
40 British American Boulevard
Latham, NY 12110

Project Site: NOW Corporation
Project Location: Stratsburg, NY
Project Manager: Chris French

Beacon Proposal: 240312R01
Beacon Project No.: 0007994
Reported: 09/20/2024

Summary of Compound Detections- Mass

Lab Sample ID: 0007994-75	SGP-K4 Soil Gas	Method: EPA 8260C
---------------------------	---------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
Vinyl Chloride	75-01-4	44		10	S24091019.D
1,1-Dichloroethene	75-35-4	119		10	S24091019.D
1,1,1-Trichloroethane	71-55-6	152		10	S24091019.D
Trichloroethene	79-01-6	14		10	S24091019.D

Lab Sample ID: 0007994-76	SGP-K5 Soil Gas	Method: EPA 8260C
---------------------------	---------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
Vinyl Chloride	75-01-4	12		10	S24091020.D
1,1-Dichloroethene	75-35-4	37		10	S24091020.D
cis-1,2-Dichloroethene	156-59-2	10		10	S24091020.D
1,1,1-Trichloroethane	71-55-6	30		10	S24091020.D
Trichloroethene	79-01-6	152		10	S24091020.D

Lab Sample ID: 0007994-77	SGP-K6 Soil Gas	Method: EPA 8260C
---------------------------	---------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
Vinyl Chloride	75-01-4	55		10	S24091021.D
1,1-Dichloroethene	75-35-4	57		10	S24091021.D
trans-1,2-Dichloroethene	156-60-5	109		10	S24091021.D
cis-1,2-Dichloroethene	156-59-2	595		10	S24091021.D
Trichloroethene	79-01-6	4,140		10	S24091021.D
Tetrachloroethene	127-18-4	10		10	S24091021.D

AECOM
40 British American Boulevard
Latham, NY 12110**Project Site:** NOW Corporation
Project Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Beacon Project No.: 0007994
Reported: 09/20/2024*Summary of Compound Detections- Mass*

Lab Sample ID: 0007994-78	SGP-K7 Soil Gas	Method: EPA 8260C
---------------------------	---------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
Vinyl Chloride	75-01-4	14		10	S24091022.D
1,1-Dichloroethene	75-35-4	35		10	S24091022.D
cis-1,2-Dichloroethene	156-59-2	45		10	S24091022.D
1,1,1-Trichloroethane	71-55-6	27		10	S24091022.D
Trichloroethene	79-01-6	520		10	S24091022.D

Lab Sample ID: 0007994-79	SGP-K8 Soil Gas	Method: EPA 8260C
---------------------------	---------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
Vinyl Chloride	75-01-4	32		10	S24091023.D
1,1-Dichloroethene	75-35-4	37		10	S24091023.D
cis-1,2-Dichloroethene	156-59-2	47		10	S24091023.D
1,1,1-Trichloroethane	71-55-6	57		10	S24091023.D
Trichloroethene	79-01-6	543		10	S24091023.D
Tetrachloroethene	127-18-4	56		10	S24091023.D

Lab Sample ID: 0007994-80	SGP-L1 Soil Gas	Method: EPA 8260C
---------------------------	---------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
Vinyl Chloride	75-01-4	31		10	S24091024.D
1,1-Dichloroethene	75-35-4	37		10	S24091024.D
1,1,1-Trichloroethane	71-55-6	34		10	S24091024.D
Trichloroethene	79-01-6	18		10	S24091024.D

AECOM
 40 British American Boulevard
 Latham, NY 12110

Project Site: NOW Corporation
Project Location: Stratsburg, NY
Project Manager: Chris French

Beacon Proposal: 240312R01
Beacon Project No.: 0007994
Reported: 09/20/2024

Summary of Compound Detections- Mass

Lab Sample ID: 0007994-81	SGP-L2 Soil Gas	Method: EPA 8260C
---------------------------	---------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
Vinyl Chloride	75-01-4	11		10	S24091027.D
1,1-Dichloroethene	75-35-4	27		10	S24091027.D
1,1,1-Trichloroethane	71-55-6	32		10	S24091027.D

Lab Sample ID: 0007994-82	SGP-L3 Soil Gas	Method: EPA 8260C
---------------------------	---------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
Vinyl Chloride	75-01-4	41		10	S24091028.D
1,1-Dichloroethene	75-35-4	101		10	S24091028.D
1,1,1-Trichloroethane	71-55-6	161		10	S24091028.D
Trichloroethene	79-01-6	43		10	S24091028.D

Lab Sample ID: 0007994-83	SGP-L4 Soil Gas	Method: EPA 8260C
---------------------------	---------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
Vinyl Chloride	75-01-4	43		10	S24091029.D
1,1-Dichloroethene	75-35-4	123		10	S24091029.D
1,1,1-Trichloroethane	71-55-6	159		10	S24091029.D

AECOM
40 British American Boulevard
Latham, NY 12110

Project Site: NOW Corporation
Project Location: Stratsburg, NY
Project Manager: Chris French

Beacon Proposal: 240312R01
Beacon Project No.: 0007994
Reported: 09/20/2024

Summary of Compound Detections- Mass

Lab Sample ID: 0007994-84	SGP-L5 Soil Gas	Method: EPA 8260C
---------------------------	---------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
Vinyl Chloride	75-01-4	33		10	S24091030.D
1,1-Dichloroethene	75-35-4	43		10	S24091030.D
trans-1,2-Dichloroethene	156-60-5	11		10	S24091030.D
cis-1,2-Dichloroethene	156-59-2	64		10	S24091030.D
1,1,1-Trichloroethane	71-55-6	27		10	S24091030.D
Trichloroethene	79-01-6	442		10	S24091030.D

Lab Sample ID: 0007994-85	SGP-L6 Soil Gas	Method: EPA 8260C
---------------------------	---------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
Vinyl Chloride	75-01-4	22		10	S24091031.D
1,1-Dichloroethene	75-35-4	45		10	S24091031.D
cis-1,2-Dichloroethene	156-59-2	12		10	S24091031.D
1,1,1-Trichloroethane	71-55-6	27		10	S24091031.D
Trichloroethene	79-01-6	81		10	S24091031.D

Lab Sample ID: 0007994-86	SGP-L7 Soil Gas	Method: EPA 8260C
---------------------------	---------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
Vinyl Chloride	75-01-4	483		10	S24091032.D
1,1-Dichloroethene	75-35-4	58		10	S24091032.D
trans-1,2-Dichloroethene	156-60-5	81		10	S24091032.D
cis-1,2-Dichloroethene	156-59-2	707		10	S24091032.D
1,1,1-Trichloroethane	71-55-6	23		10	S24091032.D
Trichloroethene	79-01-6	477		10	S24091032.D
Tetrachloroethene	127-18-4	486		10	S24091032.D

AECOM
40 British American Boulevard
Latham, NY 12110

Project Site: NOW Corporation
Project Location: Stratsburg, NY
Project Manager: Chris French

Beacon Proposal: 240312R01
Beacon Project No.: 0007994
Reported: 09/20/2024

Summary of Compound Detections- Mass

Lab Sample ID: 0007994-87	SGP-M0 Soil Gas	Method: EPA 8260C
---------------------------	---------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
Vinyl Chloride	75-01-4	27		10	S24091033.D
1,1-Dichloroethene	75-35-4	35		10	S24091033.D
cis-1,2-Dichloroethene	156-59-2	31		10	S24091033.D
1,1,1-Trichloroethane	71-55-6	26		10	S24091033.D
Trichloroethene	79-01-6	402		10	S24091033.D

Lab Sample ID: 0007994-88	SGP-M1 Soil Gas	Method: EPA 8260C
---------------------------	---------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
1,1,1-Trichloroethane	71-55-6	17		10	S24091034.D
Trichloroethene	79-01-6	144		10	S24091034.D

Lab Sample ID: 0007994-89	SGP-M1-DUP Soil Gas	Method: EPA 8260C
---------------------------	-------------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
cis-1,2-Dichloroethene	156-59-2	11		10	S24091035.D
1,1,1-Trichloroethane	71-55-6	24		10	S24091035.D
Trichloroethene	79-01-6	165		10	S24091035.D

Lab Sample ID: 0007994-90	SGP-M2 Soil Gas	Method: EPA 8260C
---------------------------	---------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
Vinyl Chloride	75-01-4	13		10	S24091036.D
1,1-Dichloroethene	75-35-4	29		10	S24091036.D
cis-1,2-Dichloroethene	156-59-2	13		10	S24091036.D
1,1,1-Trichloroethane	71-55-6	44		10	S24091036.D
Trichloroethene	79-01-6	163		10	S24091036.D

AECOM
 40 British American Boulevard
 Latham, NY 12110

Project Site: NOW Corporation
Project Location: Stratsburg, NY
Project Manager: Chris French

Beacon Proposal: 240312R01
Beacon Project No.: 0007994
Reported: 09/20/2024

Summary of Compound Detections- Mass

Lab Sample ID: 0007994-91	SGP-M3 Soil Gas	Method: EPA 8260C
---------------------------	---------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
Vinyl Chloride	75-01-4	339		10	S24091037.D
1,1-Dichloroethene	75-35-4	1,650		10	S24091037.D
trans-1,2-Dichloroethene	156-60-5	70		10	S24091037.D
cis-1,2-Dichloroethene	156-59-2	365		10	S24091037.D
1,1,1-Trichloroethane	71-55-6	2,230		10	S24091037.D
Trichloroethene	79-01-6	9,990		10	S24091037.D
Tetrachloroethene	127-18-4	88		10	S24091037.D

Lab Sample ID: 0007994-92	SGP-M4 Soil Gas	Method: EPA 8260C
---------------------------	---------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
Vinyl Chloride	75-01-4	99		10	S24091038.D
1,1-Dichloroethene	75-35-4	346		10	S24091038.D
cis-1,2-Dichloroethene	156-59-2	41		10	S24091038.D
1,1,1-Trichloroethane	71-55-6	521		10	S24091038.D
Trichloroethene	79-01-6	987		10	S24091038.D
Tetrachloroethene	127-18-4	24		10	S24091038.D

Lab Sample ID: 0007994-93	SGP-M5 Soil Gas	Method: EPA 8260C
---------------------------	---------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
Vinyl Chloride	75-01-4	323		10	S24091039.D
1,1-Dichloroethene	75-35-4	1,260		10	S24091039.D
trans-1,2-Dichloroethene	156-60-5	42		10	S24091039.D
cis-1,2-Dichloroethene	156-59-2	236		10	S24091039.D
1,1,1-Trichloroethane	71-55-6	2,450		10	S24091039.D
Trichloroethene	79-01-6	5,580		10	S24091039.D
Tetrachloroethene	127-18-4	30		10	S24091039.D

AECOM
40 British American Boulevard
Latham, NY 12110**Project Site:** NOW Corporation
Project Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Beacon Project No.: 0007994
Reported: 09/20/2024*Summary of Compound Detections- Mass*

Lab Sample ID: 0007994-94	SGP-M6 Soil Gas	Method: EPA 8260C
---------------------------	---------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
Vinyl Chloride	75-01-4	117		10	S24091040.D
1,1-Dichloroethene	75-35-4	216		10	S24091040.D
trans-1,2-Dichloroethene	156-60-5	41		10	S24091040.D
cis-1,2-Dichloroethene	156-59-2	275		10	S24091040.D
1,1,1-Trichloroethane	71-55-6	170		10	S24091040.D
Trichloroethene	79-01-6	1,900		10	S24091040.D

Lab Sample ID: 0007994-95	SGP-M7 Soil Gas	Method: EPA 8260C
---------------------------	---------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
Vinyl Chloride	75-01-4	289		10	S24091041.D
1,1-Dichloroethene	75-35-4	189		10	S24091041.D
trans-1,2-Dichloroethene	156-60-5	143		10	S24091041.D
cis-1,2-Dichloroethene	156-59-2	1,340		10	S24091041.D
1,1,1-Trichloroethane	71-55-6	147		10	S24091041.D
Trichloroethene	79-01-6	2,110		10	S24091041.D

Lab Sample ID: 0007994-96	SGP-M8 Soil Gas	Method: EPA 8260C
---------------------------	---------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
Vinyl Chloride	75-01-4	163		10	S24091042.D
1,1-Dichloroethene	75-35-4	244		10	S24091042.D
trans-1,2-Dichloroethene	156-60-5	89		10	S24091042.D
cis-1,2-Dichloroethene	156-59-2	583		10	S24091042.D
1,1,1-Trichloroethane	71-55-6	198		10	S24091042.D
Trichloroethene	79-01-6	5,020		10	S24091042.D
Tetrachloroethene	127-18-4	28		10	S24091042.D

AECOM
40 British American Boulevard
Latham, NY 12110**Project Site:** NOW Corporation
Project Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Beacon Project No.: 0007994
Reported: 09/20/2024***Summary of Compound Detections- Mass***

Lab Sample ID: 0007994-97	SGP-N1 Soil Gas	Method: EPA 8260C
---------------------------	---------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
Vinyl Chloride	75-01-4	18		10	S24091043.D
1,1-Dichloroethene	75-35-4	19		10	S24091043.D
cis-1,2-Dichloroethene	156-59-2	24		10	S24091043.D
Trichloroethene	79-01-6	149		10	S24091043.D

Lab Sample ID: 0007994-98	SGP-N2 Soil Gas	Method: EPA 8260C
---------------------------	---------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
Vinyl Chloride	75-01-4	32		10	S24091044.D
1,1-Dichloroethene	75-35-4	22		10	S24091044.D
cis-1,2-Dichloroethene	156-59-2	15		10	S24091044.D
1,1,1-Trichloroethane	71-55-6	22		10	S24091044.D
Trichloroethene	79-01-6	167		10	S24091044.D

Lab Sample ID: 0007994-AA	SGP-N4 Soil Gas	Method: EPA 8260C
---------------------------	---------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
Vinyl Chloride	75-01-4	332		10	S24091046.D
1,1-Dichloroethene	75-35-4	2,140		10	S24091046.D
trans-1,2-Dichloroethene	156-60-5	32		10	S24091046.D
cis-1,2-Dichloroethene	156-59-2	176		10	S24091046.D
1,1,1-Trichloroethane	71-55-6	3,460		10	S24091046.D
Trichloroethene	79-01-6	5,150		10	S24091046.D
Tetrachloroethene	127-18-4	138		10	S24091046.D

AECOM
40 British American Boulevard
Latham, NY 12110

Project Site: NOW Corporation
Project Location: Stratsburg, NY
Project Manager: Chris French

Beacon Proposal: 240312R01
Beacon Project No.: 0007994
Reported: 09/20/2024

Summary of Compound Detections- Mass

Lab Sample ID: 0007994-AB	SGP-N5 Soil Gas	Method: EPA 8260C
---------------------------	---------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
Vinyl Chloride	75-01-4	866		10	C24091005.D
1,1-Dichloroethene	75-35-4	9,290		10	C24091005.D
trans-1,2-Dichloroethene	156-60-5	119		10	C24091005.D
cis-1,2-Dichloroethene	156-59-2	673		10	C24091005.D
1,1,1-Trichloroethane	71-55-6	12,400		10	C24091005.D
Trichloroethene	79-01-6	15,200		10	C24091005.D
Tetrachloroethene	127-18-4	84		10	C24091005.D

Lab Sample ID: 0007994-AC	SGP-N6 Soil Gas	Method: EPA 8260C
---------------------------	---------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
Vinyl Chloride	75-01-4	588		10	C24091006.D
1,1-Dichloroethene	75-35-4	4,520		10	C24091006.D
trans-1,2-Dichloroethene	156-60-5	249		10	C24091006.D
cis-1,2-Dichloroethene	156-59-2	1,600		10	C24091006.D
1,1,1-Trichloroethane	71-55-6	3,510		10	C24091006.D
Trichloroethene	79-01-6	13,300		10	C24091006.D
Tetrachloroethene	127-18-4	44		10	C24091006.D

AECOM
40 British American Boulevard
Latham, NY 12110

Project Site: NOW Corporation
Project Location: Stratsburg, NY
Project Manager: Chris French

Beacon Proposal: 240312R01
Beacon Project No.: 0007994
Reported: 09/20/2024

Summary of Compound Detections- Mass

Lab Sample ID: 0007994-AD	SGP-N7 Soil Gas	Method: EPA 8260C
---------------------------	---------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
Vinyl Chloride	75-01-4	411		10	C24091007.D
1,1-Dichloroethene	75-35-4	2,640		10	C24091007.D
trans-1,2-Dichloroethene	156-60-5	116		10	C24091007.D
cis-1,2-Dichloroethene	156-59-2	666		10	C24091007.D
1,1,1-Trichloroethane	71-55-6	4,670		10	C24091007.D
Trichloroethene	79-01-6	15,100		10	C24091007.D
Tetrachloroethene	127-18-4	69		10	C24091007.D

Lab Sample ID: 0007994-AH	SGP-O4 Soil Gas	Method: EPA 8260C
---------------------------	---------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
cis-1,2-Dichloroethene	156-59-2	21		10	C24091011.D
Trichloroethene	79-01-6	51		10	C24091011.D

Lab Sample ID: 0007994-AI	SGP-O5 Soil Gas	Method: EPA 8260C
---------------------------	---------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
Trichloroethene	79-01-6	26		10	C24091012.D

Lab Sample ID: 0007994-AJ	SGP-O6 Soil Gas	Method: EPA 8260C
---------------------------	---------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
Trichloroethene	79-01-6	27		10	C24091013.D

AECOM
40 British American Boulevard
Latham, NY 12110**Project Site:** NOW Corporation
Project Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Beacon Project No.: 0007994
Reported: 09/20/2024***Summary of Compound Detections- Mass***

Lab Sample ID: 0007994-AT	SGP-P1 Soil Gas	Method: EPA 8260C
---------------------------	---------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
cis-1,2-Dichloroethene	156-59-2	10		10	C24091023.D
Trichloroethene	79-01-6	105		10	C24091023.D

Lab Sample ID: 0007994-AY	SGP-P5 Soil Gas	Method: EPA 8260C
---------------------------	---------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
Tetrachloroethene	127-18-4	17		10	C24091030.D

Lab Sample ID: 0007994-AZ	SGP-Q1 Soil Gas	Method: EPA 8260C
---------------------------	---------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
1,1-Dichloroethene	75-35-4	12		10	C24091031.D
cis-1,2-Dichloroethene	156-59-2	32		10	C24091031.D
Trichloroethene	79-01-6	605		10	C24091031.D

Lab Sample ID: 0007994-BA	SGP-Q2 Soil Gas	Method: EPA 8260C
---------------------------	---------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
Trichloroethene	79-01-6	28		10	C24091032.D

AECOM
40 British American Boulevard
Latham, NY 12110**Project Site:** NOW Corporation
Project Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Beacon Project No.: 0007994
Reported: 09/20/2024*Summary of Compound Detections- Mass*

Lab Sample ID: 0007994-BC	SGP-R1 Soil Gas	Method: EPA 8260C
---------------------------	---------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
Vinyl Chloride	75-01-4	249		10	C24091034.D
1,1-Dichloroethene	75-35-4	3,300		10	C24091034.D
1,1,1-Trichloroethane	71-55-6	1,230		10	C24091034.D

Lab Sample ID: 0007994-BH	SGP-S1 Soil Gas	Method: EPA 8260C
---------------------------	---------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
Vinyl Chloride	75-01-4	29		10	S24091107.D
1,1-Dichloroethene	75-35-4	36		10	S24091107.D
trans-1,2-Dichloroethene	156-60-5	79		10	S24091107.D
cis-1,2-Dichloroethene	156-59-2	259		10	S24091107.D
Trichloroethene	79-01-6	4,470		10	S24091107.D

Lab Sample ID: 0007994-BI	SGP-S2 Soil Gas	Method: EPA 8260C
---------------------------	---------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
cis-1,2-Dichloroethene	156-59-2	13		10	S24091108.D
Trichloroethene	79-01-6	107		10	S24091108.D

Lab Sample ID: 0007994-BK	SGP-T1 Soil Gas	Method: EPA 8260C
---------------------------	---------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
Vinyl Chloride	75-01-4	12		10	S24091110.D
1,1-Dichloroethene	75-35-4	20		10	S24091110.D
cis-1,2-Dichloroethene	156-59-2	26		10	S24091110.D
Trichloroethene	79-01-6	368		10	S24091110.D

AECOM
40 British American Boulevard
Latham, NY 12110

Project Site: NOW Corporation
Project Location: Stratsburg, NY
Project Manager: Chris French

Beacon Proposal: 240312R01
Beacon Project No.: 0007994
Reported: 09/20/2024

Summary of Compound Detections- Mass

Lab Sample ID: 0007994-BN	SGP-U1 Soil Gas	Method: EPA 8260C
---------------------------	---------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
Vinyl Chloride	75-01-4	132		10	S24091113.D
1,1-Dichloroethene	75-35-4	243		10	S24091113.D
trans-1,2-Dichloroethene	156-60-5	43		10	S24091113.D
cis-1,2-Dichloroethene	156-59-2	131		10	S24091113.D
1,1,1-Trichloroethane	71-55-6	130		10	S24091113.D
Trichloroethene	79-01-6	624		10	S24091113.D

Lab Sample ID: 0007994-BO	SGP-U2 Soil Gas	Method: EPA 8260C
---------------------------	---------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
1,1-Dichloroethene	75-35-4	13		10	S24091114.D
cis-1,2-Dichloroethene	156-59-2	34		10	S24091114.D
Trichloroethene	79-01-6	587		10	S24091114.D

Lab Sample ID: 0007994-BQ	SGP-V1 Soil Gas	Method: EPA 8260C
---------------------------	---------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
cis-1,2-Dichloroethene	156-59-2	36		10	S24091116.D
Trichloroethene	79-01-6	834		10	S24091116.D

Lab Sample ID: 0007994-BR	SGP-V2 Soil Gas	Method: EPA 8260C
---------------------------	---------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
1,1-Dichloroethene	75-35-4	13		10	S24091117.D
cis-1,2-Dichloroethene	156-59-2	29		10	S24091117.D
Trichloroethene	79-01-6	1,010		10	S24091117.D

AECOM
40 British American Boulevard
Latham, NY 12110

Project Site: NOW Corporation
Project Location: Stratsburg, NY
Project Manager: Chris French

Beacon Proposal: 240312R01
Beacon Project No.: 0007994
Reported: 09/20/2024

Summary of Compound Detections- Mass

Lab Sample ID: 0007994-BV	SGP-X1 Soil Gas	Method: EPA 8260C
---------------------------	---------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
Trichloroethene	79-01-6	29		10	S24091121.D

Lab Sample ID: 0007994-BZ	SGP-Z1 Soil Gas	Method: EPA 8260C
---------------------------	---------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
cis-1,2-Dichloroethene	156-59-2	17		10	S24091127.D
Trichloroethene	79-01-6	306		10	S24091127.D

Lab Sample ID: 0007994-CC	SGP-AA1 Soil Gas	Method: EPA 8260C
---------------------------	----------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
trans-1,2-Dichloroethene	156-60-5	13		10	S24091130.D
cis-1,2-Dichloroethene	156-59-2	83		10	S24091130.D
Trichloroethene	79-01-6	748		10	S24091130.D

Lab Sample ID: 0007994-CD	SGP-AA1-DUP Soil Gas	Method: EPA 8260C
---------------------------	--------------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
trans-1,2-Dichloroethene	156-60-5	12		10	S24091131.D
cis-1,2-Dichloroethene	156-59-2	74		10	S24091131.D
Trichloroethene	79-01-6	715		10	S24091131.D

AECOM
40 British American Boulevard
Latham, NY 12110**Project Site:** NOW Corporation
Project Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Beacon Project No.: 0007994
Reported: 09/20/2024*Summary of Compound Detections- Mass*

Lab Sample ID: 0007994-CE	SGP-AA2 Soil Gas	Method: EPA 8260C
---------------------------	----------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
cis-1,2-Dichloroethene	156-59-2	30		10	S24091132.D
Trichloroethene	79-01-6	272		10	S24091132.D

Lab Sample ID: 0007994-CF	SGP-AA3 Soil Gas	Method: EPA 8260C
---------------------------	----------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
1,1-Dichloroethene	75-35-4	15		10	S24091133.D
cis-1,2-Dichloroethene	156-59-2	40		10	S24091133.D
Trichloroethene	79-01-6	708		10	S24091133.D

Lab Sample ID: 0007994-CG	SGP-BB1 Soil Gas	Method: EPA 8260C
---------------------------	----------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
1,1-Dichloroethene	75-35-4	436		10	S24091134.D
trans-1,2-Dichloroethene	156-60-5	635		10	S24091134.D
cis-1,2-Dichloroethene	156-59-2	5,730		10	S24091134.D
Trichloroethene	79-01-6	38,300		10	S24091134.D
Tetrachloroethene	127-18-4	79		10	S24091134.D

Lab Sample ID: 0007994-CH	SGP-BB2 Soil Gas	Method: EPA 8260C
---------------------------	----------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
1,1-Dichloroethene	75-35-4	15		10	S24091135.D
trans-1,2-Dichloroethene	156-60-5	13		10	S24091135.D
cis-1,2-Dichloroethene	156-59-2	68		10	S24091135.D
Trichloroethene	79-01-6	1,330		10	S24091135.D

AECOM
40 British American Boulevard
Latham, NY 12110**Project Site:** NOW Corporation
Project Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Beacon Project No.: 0007994
Reported: 09/20/2024***Summary of Compound Detections- Mass***

Lab Sample ID: 0007994-CI	SGP-BB3 Soil Gas	Method: EPA 8260C
---------------------------	----------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
1,1-Dichloroethene	75-35-4	27		10	S24091136.D
trans-1,2-Dichloroethene	156-60-5	24		10	S24091136.D
cis-1,2-Dichloroethene	156-59-2	127		10	S24091136.D
Trichloroethene	79-01-6	1,920		10	S24091136.D

Lab Sample ID: 0007994-CJ	SGP-CC1 Soil Gas	Method: EPA 8260C
---------------------------	----------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
Trichloroethene	79-01-6	118		10	S24091137.D

Lab Sample ID: 0007994-CK	SGP-CC2 Soil Gas	Method: EPA 8260C
---------------------------	----------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
1,1-Dichloroethene	75-35-4	23		10	S24091138.D
trans-1,2-Dichloroethene	156-60-5	94		10	S24091138.D
cis-1,2-Dichloroethene	156-59-2	933		10	S24091138.D
Trichloroethene	79-01-6	2,320		10	S24091138.D

Lab Sample ID: 0007994-CL	SGP-CC3 Soil Gas	Method: EPA 8260C
---------------------------	----------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
trans-1,2-Dichloroethene	156-60-5	15		10	S24091139.D
cis-1,2-Dichloroethene	156-59-2	103		10	S24091139.D
Trichloroethene	79-01-6	777		10	S24091139.D
Tetrachloroethene	127-18-4	28		10	S24091139.D

AECOM
40 British American Boulevard
Latham, NY 12110**Project Site:** NOW Corporation
Project Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Beacon Project No.: 0007994
Reported: 09/20/2024*Summary of Compound Detections- Mass*

Lab Sample ID: 0007994-CM	SGP-CC4 Soil Gas	Method: EPA 8260C
---------------------------	----------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
1,1-Dichloroethene	75-35-4	27		10	S24091140.D
trans-1,2-Dichloroethene	156-60-5	51		10	S24091140.D
cis-1,2-Dichloroethene	156-59-2	258		10	S24091140.D
Trichloroethene	79-01-6	2,330		10	S24091140.D

Lab Sample ID: 0007994-CN	SGP-CC5 Soil Gas	Method: EPA 8260C
---------------------------	----------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
Trichloroethene	79-01-6	41		10	S24091141.D

Lab Sample ID: 0007994-CO	SGP-CC5-DUP Soil Gas	Method: EPA 8260C
---------------------------	--------------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
Trichloroethene	79-01-6	41		10	S24091142.D

Lab Sample ID: 0007994-CP	SGP-DD1 Soil Gas	Method: EPA 8260C
---------------------------	----------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
Trichloroethene	79-01-6	95		10	S24091143.D

Lab Sample ID: 0007994-CQ	SGP-DD2 Soil Gas	Method: EPA 8260C
---------------------------	----------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
cis-1,2-Dichloroethene	156-59-2	57		10	S24091144.D
Trichloroethene	79-01-6	759		10	S24091144.D

AECOM
40 British American Boulevard
Latham, NY 12110**Project Site:** NOW Corporation
Project Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Beacon Project No.: 0007994
Reported: 09/20/2024*Summary of Compound Detections- Mass*

Lab Sample ID: 0007994-CR	SGP-DD3 Soil Gas	Method: EPA 8260C
---------------------------	----------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
cis-1,2-Dichloroethene	156-59-2	21		10	S24091145.D
Trichloroethene	79-01-6	122		10	S24091145.D

Lab Sample ID: 0007994-CS	SGP-DD4 Soil Gas	Method: EPA 8260C
---------------------------	----------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
Trichloroethene	79-01-6	11		10	S24091146.D

Lab Sample ID: 0007994-CT	SGP-DD5 Soil Gas	Method: EPA 8260C
---------------------------	----------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
Trichloroethene	79-01-6	62		10	C24091105.D
Tetrachloroethene	127-18-4	11		10	C24091105.D

Lab Sample ID: 0007994-CV	SGP-EE1 Soil Gas	Method: EPA 8260C
---------------------------	----------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
Trichloroethene	79-01-6	49		10	C24091107.D

Lab Sample ID: 0007994-CW	SGP-EE2 Soil Gas	Method: EPA 8260C
---------------------------	----------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
Trichloroethene	79-01-6	19		10	C24091108.D

AECOM
40 British American Boulevard
Latham, NY 12110**Project Site:** NOW Corporation
Project Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Beacon Project No.: 0007994
Reported: 09/20/2024***Summary of Compound Detections- Mass***

Lab Sample ID: 0007994-CZ	SGP-EE5 Soil Gas	Method: EPA 8260C
---------------------------	----------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
Trichloroethene	79-01-6	20		10	C24091111.D

Lab Sample ID: 0007994-DB	SGP-FF1 Soil Gas	Method: EPA 8260C
---------------------------	----------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
cis-1,2-Dichloroethene	156-59-2	21		10	C24091113.D
Trichloroethene	79-01-6	89		10	C24091113.D

Lab Sample ID: 0007994-DG	SGP-FF5 Soil Gas	Method: EPA 8260C
---------------------------	----------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
Trichloroethene	79-01-6	15		10	C24091118.D

Lab Sample ID: 0007994-DH	SGP-GG1 Soil Gas	Method: EPA 8260C
---------------------------	----------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
Trichloroethene	79-01-6	46		10	C24091119.D

AECOM
40 British American Boulevard
Latham, NY 12110**Project Site:** NOW Corporation
Project Location: Stratsburg, NY
Project Manager: Chris French**Beacon Proposal:** 240312R01
Beacon Project No.: 0007994
Reported: 09/20/2024*Summary of Compound Detections- Mass*

Lab Sample ID: 0007994-DO	SGP-III Soil Gas	Method: EPA 8260C
---------------------------	----------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
Vinyl Chloride	75-01-4	20		10	C24091128.D
1,1-Dichloroethene	75-35-4	60		10	C24091128.D
1,1,1-Trichloroethane	71-55-6	86		10	C24091128.D
Trichloroethene	79-01-6	32		10	C24091128.D
Tetrachloroethene	127-18-4	16		10	C24091128.D

Lab Sample ID: 0007994-DP	SGP-II2 Soil Gas	Method: EPA 8260C
---------------------------	----------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
Trichloroethene	79-01-6	54		10	C24091129.D

Lab Sample ID: 0007994-DS	SGP-JJ1 Soil Gas	Method: EPA 8260C
---------------------------	----------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
trans-1,2-Dichloroethene	156-60-5	10		10	C24091132.D
cis-1,2-Dichloroethene	156-59-2	83		10	C24091132.D
Trichloroethene	79-01-6	36		10	C24091132.D

Lab Sample ID: 0007994-DU	SGP-KK1 Soil Gas	Method: EPA 8260C
---------------------------	----------------------------	-------------------

Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
Vinyl Chloride	75-01-4	39		10	C24091134.D
cis-1,2-Dichloroethene	156-59-2	15		10	C24091134.D
Trichloroethene	79-01-6	113		10	C24091134.D

AECOM
40 British American Boulevard
Latham, NY 12110

Project Site: NOW Corporation
Project Location: Stratsburg, NY
Project Manager: Chris French

Beacon Proposal: 240312R01
Beacon Project No.: 0007994
Reported: 09/20/2024

Summary of Compound Detections- Mass


Lab Sample ID: 0007994-DW		SGP-LL1		Method:	EPA 8260C
		Soil Gas			
Analyte	CAS#	Result (ng)	Q	LOQ (ng)	File ID
Vinyl Chloride	75-01-4	19		10	C24091136.D

AECOM 40 British American Boulevard Latham, NY 12110	Project Site: NOW Corporation Project Location: Stratsburg, NY Project Manager: Chris French	Beacon Proposal: 240312R01 Beacon Project No.: 0007994 Reported: 09/20/2024
---	---	--

Map Data Summary Table

Sample locations are shown on **Figure 1**. The following table lists number of detections on field samples from the current survey, the reporting limit, and the maximum value for each mapped compound. The table also includes the transformation and interpolation method for the compound distribution maps provided.

Figure No.	Compound	Number of Detections	LOQ (ng)	Max Value (ng)	Transformation Method	Interpolation Method
2	cis-1,2-Dichloroethene	71	10	5,730	Log	Kriging
3	1,1,1-Trichloroethane	39	10	12,400	Log	Kriging
4	Trichloroethene	97	10	38,300	Log	Kriging



System: State Plane
Zone: New York East
Datum: NAD83(2011) / (EPSG:6537)
Coordinate Units: (ftUS)

LEGEND

▲ PASSIVE SOIL-GAS SAMPLE LOCATION





Figure 1
Passive Soil-Gas Survey
Sample Locations


NOW Corporation
Stratsburg, NY



526 Underwood Lane, Bel Air, MD 21014 USA
www.Beacon-USA.com 1-410-838-8780
Beacon Project No. 7994, September 2024


Figure 2
Passive Soil-Gas Survey
cis-1,2-Dichloroethene

NOW Corporation
Stratsburg, NY




System: State Plane
Zone: New York East
Datum: NAD83(2011) / (EPSG:6537)
Coordinate Units: (ftUS)

LEGEND
1,000 NANOGRAMS/SAMPLER
▲ PASSIVE SOIL-GAS SAMPLE LOCATION



BEACON
ENVIRONMENTAL
526 Underwood Lane, Bel Air, MD 21014 USA
www.Beacon-USA.com 1-410-838-8780
Beacon Project No. 7994, September 2024

Figure 3
Passive Soil-Gas Survey
1,1,1-Trichloroethane
NOW Corporation
Stratsburg, NY



System: State Plane
Zone: New York East
Datum: NAD83(2011) / (EPSG:6537)
Coordinate Units: (ftUS)

LEGEND
1,000 NANOGRAMS/SAMPLER
▲ PASSIVE SOIL-GAS SAMPLE LOCATION




Figure 4
Passive Soil-Gas Survey
Trichloroethene

NOW Corporation
Stratsburg, NY