



SUB-SLAB DEPRESSURIZATION SYSTEM DESIGN DOCUMENT

**65 Albany Avenue
Kingston, Ulster County, New York 12401**

August 24, 2022

DEC SITE NUMBER 356060

Prepared by: Bellucci Engineering, PLLC
27 Belcrest Road, West Hartford, CT 06107

August 24, 2022

Mr. Michael Kilmer

New York State Department of Environmental Conservation

Division of Environmental Remediation

21 South Putt Corners Road

New Paltz, New York 12561

RE: *Sub-Slab Depressurization System Design Document*

65 Albany Avenue

Kingston, Ulster County, New York

Site No.: 356060

Dear Mr. Kilmer:

Bellucci Engineering, PLLC is pleased to present this *Sub-Slab Depressurization System Design Document* for the above referenced property. This report specifies the proposed design and installation procedures for a SSDS at the property located at 65 Albany Avenue in Kingston, Ulster County, New York (herein the Site). This SSDS Design Document is being submitted to NYSDEC and NYSDOH for approval. If you should have any questions or require additional information, please contact our office.

Respectfully submitted,



Daniel Bellucci, P.E.
Bellucci Engineering, PLLC



Deborah Thompson
Senior Geologist

CERTIFICATION

I, Daniel Bellucci, certify that I am currently a NYS registered professional engineer as defined in 6 NYCRR Part 375 and that this Sub-slab Depressurization System Design, was prepared in accordance with all applicable statutes and regulations and in substantial conformance with the DER Technical Guidance for Site Investigation and Remediation (DER-10) and that all activities were performed in full accordance with the DER-approved work plan and any DER-approved modifications.

Daniel Bellucci, P.E.
Professional Engineer #099470

Daniel Bellucci

Signature



08/24/2022

Date

Table of Contents

1.0 INTRODUCTION AND BACKGROUND.....	1
2.0 SITE SETTING.....	5
2.1 Site Soil and Bedrock Geology.....	5
2.2 Site Hydrogeological Conditions.....	5
3.0 SSDS PILOT TEST SUMMARY	6
4.0 SSDS DESIGN.....	7
4.1 SSDS Design Parameters	7
4.1.1 Eastern Portion of Building.....	7
4.1.2 Central Portion of Building	8
4.1.3 Western Portion of Building	8
4.2 Piping and System Components	9
4.3 Roof / Sidewall Penetrations & Sealing.....	10
4.4 Fan Mounting & Exterior Piping.....	10
4.5 Electrical	11
4.6 AERSCREEN Evaluation	11
4.7 Sealing of Cracks and Joints.....	12
4.8 Chemical Inventory Survey	12
5.0 TESTING, OPERATION & MAINTENANCE	13
5.1 System Startup Testing.....	13
5.2 Post System Startup Testing – 1 Week	13
5.3 Post System Startup Testing – 1 Month.....	13
5.4 Quarterly Operation & Maintenance	14
6.0 SSDS INSTALLATION SUPPORT ACTIVITIES.....	15
6.1 Community Air Monitoring Plan.....	15
6.2 Health & Safety Plan.....	15
6.3 Tenant Communication.....	15
6.4 Waste Handling	15
7.0 REPORTING & SCHEDULE	16

FIGURES, TABLES & APPENDICES

FIGURES

FIGURE 1	SITE LOCATION PLAN
FIGURE 2	SITE BASE MAP
FIGURE 3	IRM SAMPLING AND TESTING LOCATION MAP
FIGURE 4	RADIUS OF INFLUENCE MAP
FIGURE 5	SSDS INSTALLATION - PLAN VIEW
FIGURE 6A	SSDS PROCESS FLOW – EW-1 & EW-4
FIGURE 6B	SSDS PROCESS FLOW – EW-5 & PROPOSED EW
FIGURE 6C	SSDS PROCESS FLOW – EW-2, EW-3 & PROPOSED EW
FIGURE 7	INSTALLATION DETAILS AND NOTES
FIGURE 8	ROOF INSTALLATION PLAN

TABLES

TABLE 1	PILOT TEST EXTRACTION WELL SYSTEM DATA
TABLE 2	PILOT TEST VACUUM MONITORING POINT DATA
TABLE 3	PILOT TEST MASS REMOVAL
TABLE 4	AERSCREEN MODEL INPUT AND OUTPUT DATA

APPENDICES

APPENDIX A	EQUIPMENT & MATERIALS SPECIFICATIONS SHEETS
APPENDIX B	COMMUNITY AIR MONITORING PLAN
APPENDIX C	HEALTH & SAFETY PLAN
APPENDIX D	PILOT TEST LABORATORY ANALYTICAL REPORTS
APPENDIX E	AERSCREEN MODEL – DATA INPUTS
APPENDIX F	NEW YORK STATE DEPARTMENT OF HEALTH INDOOR AIR QUALITY QUESTIONNAIRE AND BUILDING INVENTORY FORM

1.0 INTRODUCTION AND BACKGROUND

The Subject Property is located at 65 Albany Avenue in the City of Kingston, Ulster County, New York (heretofore referenced as the Site or Subject Property). Refer to Figures 1 & 2 for a Site Location and Surrounding Land Use maps, respectively. The Site is not currently listed in the Registry of Inactive Hazardous Waste Disposal Sites in New York State (the Registry). Prior investigation activities have been conducted on the Site and the results of those investigations were submitted to the Department. Based upon these results, the Department has designated the Site as Site Number 356060 with a Classification of “P” pursuant to ECL 27-1305.

The Subject Property contains an irregular shaped lot which encompasses an area of approximately 1.90 acres. The Site is identified as Parcel ID 48.80-1-10.100 by the City of Kingston and is improved with a partial two-story slab-on-grade +/- 21,216-ft² structure. Records indicate that the commercial use of the Site dates back to the 1920s. Areas surrounding the building include asphalt paved parking surfaces, concrete walkways and landscape spaces. The current use of the Subject Property includes the rental of professional office spaces in two buildings designated as follows:

Designated Tenant Space	Occupant
<i>Building 1 – Ground Floor</i>	
Suite A	All State Insurance Company
Suite B	Spectrum Behavioral Health
Suite C	Mainly Pilates
Suite D/E	New York State Department of Building Standards and Codes
<i>Building 1 – Second Floor</i>	
Suite G	Landmark Development
<i>Building 2</i>	
51 Albany Avenue	New York Blood Center
53 Albany Avenue	Tri-County Care
55 Albany Avenue	Rose & Kieman, Inc.

The area surrounding the Subject Property is primarily characterized by commercial development. The following table lists the abutting properties:

Location	Occupant
North	Undeveloped land, NYS Interstate 587, and a residence (67 Albany Avenue)
South	Albany Avenue and residences

East	Commercial retail spaces, residential property, First Baptist Church
West	Commercial property: WMC Heath Alliance – Dialysis Center/Diabetes Center

Site topography is generally level and at grade with surrounding roadway, with a moderate slope to the north within the northern section of the parcel. There resides an unnamed pond, which borders the Subject Property to the north, while the Esopus Creek is located approximately 1,700 feet north of the Site. Electric and gas services is supplied by Central Hudson Gas & Electric, while potable water and sanitary services are supplied by The City of Kingston (Municipal). No groundwater supply wells were observed by representatives of this office during site inspections and no groundwater supply wells are known to be present or used on adjoining or nearby properties. Surface water runoff enters catch basins located throughout the property which appear to be dry well systems.

Several environmental assessments were conducted by various contractors on behalf of historical and current property owners of the Site in 2020. As a result of a Phase I Environmental Site Assessment (ESA) performed by Team Environmental Consultants (TEAM) of Monroe, New York, the following areas of potential environmental concern and/or "recognized environmental conditions (REC)" were identified and are associated with the subject property:

- The historic operation of a dry cleaner and the on-Site use of dry-cleaning solvents represent a REC. City directory records list Pride Cleaners at 51 Albany Avenue from 1964 - 1986. Other historical documentation reflects that a commercial dry-cleaning establishment existed in the western most tenant space of the current building in 1957.

Two Site characterization field studies have also been performed on the Subject Property to investigate the REC identified during the Phase I ESA. These include the following:

1. Site Investigation, January 31, 2020, prepared by Northeastern Environmental Technologies Corp. (NETC)

The NETC subsurface investigation included collection of soil, groundwater, ambient air and sub-slab soil gas samples. Pertinent findings documented in the NETC's field study include the following:

- Low concentrations of chlorinated volatile organic compounds (cVOCs) were detected in each of the soil samples collected during the Limited Phase II ESA. The relative concentrations indicated higher detections of the parent dry cleaning chemical tetrachloroethylene (PCE) were present at the rear services entrance of the tenant space historically occupied by Pride Cleaners. Of note, PCE was detected in one soil sample at a concentration of 5.1 micrograms per kilogram ($\mu\text{g}/\text{kg}$) above the New York State Department of Environmental Conservation (NYSDEC) Unrestricted Use Soil Cleanup Objective (SCO) of 1.3 $\mu\text{g}/\text{kg}$. However, the concentration of PCE in soil did not exceed the Commercial SCO of 150 $\mu\text{g}/\text{kg}$. Additional cVOCs detected in subsurface soil did not surpass Unrestricted Use or Commercial Use SCOs;

- Dissolved phase chlorinated volatile organic compounds (cVOCs) cVOCs were also reported by the laboratory in each groundwater sample provided. Of note, concentrations of PCE detected (15 – 110 ug/L) were found to exceed the NYSDEC groundwater quality standard of 5 ug/L as denoted in Technical and Operational Guidance Series (TOGS) 1.1.1; and
- Reportable values of PCE were documented in a sub-slab soil gas samples ranging in concentrations from 148 – 7,460 micrograms per cubic meter (µg/m³) throughout the study area. These detections are above the New York State Department of Health (NYSDOH) mitigation threshold when compared to Matrix B, as appropriate. Other cVOCs were detected at low levels in soil gas that do not warrant mitigation when compared to the NYSDOH matrices.

2. Subsurface Site Characterization Report, September 9, 2020, prepared by DT Consulting Services, Inc. (DTCS)

The DTCS Site Characterization Report included collection of soil, groundwater, ambient air and sub-slab soil gas samples. Pertinent findings documented in the DTCS's field study include the following:

- To provide additional data on current subsurface soil conditions, a total of four soil borings were advanced at the Subject Property. Upon review of analytical testing, DTCS concluded that most all soil boring locations were returned with either non-detectable concentrations of VOCs or with reported values which met unrestricted use SCOs;
- A total of four groundwater samples were obtained to characterize groundwater quality. Analysis of Site wells revealed minimal exceedances for PCE when compared to regulatory standards in two of the four wells sampled. The two remaining wells were either returned with non-detect or with low level dissolved phase cVOC concentrations which met or were below groundwater quality standards as referenced in TOGS 1.1.1.; and
- The results of soil vapor sampling indicate concentrations of cVOCs are present in each of the five soil gas and the two air samples collected from the Site. Concentrations of cVOCs including, but not limited to Trichloroethylene (TCE), 1,1-Dichloroethene (1-1 DCE), Carbon Tetrachloride and PCE were reported in sub-slab soil gas samples collected on-Site. When compared with indoor air concentrations, the sub-slab PCE soil gas concentrations warrant "Mitigation" based on evaluation of the applicable NYSDOH Final Guidance on Soil Vapor Intrusion matrices.

A report titled, *Additional Site Characterization and SSDS Pilot Test Report*, dated May 26, 2022, summarizing the additional site characterization and SSDS pilot testing procedures and findings is currently pending approval by the Department. Additional soil gas sampling along the western property boundary is proposed and will be submitted to NYSDEC and DOH under a separate work plan. A complete chemical inventory survey could not be completed during the interior soil sampling program as the tenants were not present at that time. Typical commercially available cleaning products (i.e. generic household cleaners, soaps, detergents, etc.) are present in the Site building. Evidence of chemicals which could be a potential source of the contaminants of concern (cVOCs) were not identified in the limited areas observed by the on-Site field staff.

This SSDS Design Document has been prepared for the proposed installation of a SSDS as a mitigation measure designed to be protective of public health.

2.0 SITE SETTING

2.1 SITE SOIL AND BEDROCK GEOLOGY

Site soils are composed of brown to light brown native fine sand within increased silt documented around 25-feet below ground surface (bgs) in previous soil borings. Sub-slab soils encountered during installation of pilot testing extraction wells consisted of packed gravel, underlain by silt and fine sand. The geology of the area is identified as Lacustrine deposits. Bedrock has not been encountered in prior investigations to a maximum exploration depth of 30-feet below bgs.

2.2 SITE HYDROGEOLOGICAL CONDITIONS

Shallow groundwater has been measured across the Site at depths ranging from 22.0 to 24.90 feet bgs during the most recent April 2022 sampling event.

3.0 SSDS PILOT TEST SUMMARY

The purpose of the pilot test was to evaluate the effectiveness of a SSDS as a potential mitigation measure for cVOCs in soil vapor identified beneath the building. Field activities were conducted on April 2 and 3, 2022. **Tables 1, 2 and 3** include the tabulated data collected during the pilot test. **Figure 3** depicts the locations of the extraction wells and soil gas/vacuum monitoring points utilized during the pilot test program. **Figure 4** shows the estimated radius of influence generated during each of the nine tests conducted at the Site. A complete description of the SSDS extraction well installation, vacuum monitoring point installation and other pilot/diagnostic test work is presented in the *Additional Site Characterization and SSDS Pilot Study Report*, dated May 26, 2022.

SSDS pilot testing indicates the majority of building is underlain by low permeability soils which require high vacuum, low air flow blowers to extend the radius of influence from each extraction well. Average vacuum readings greater -0.004 in- H_2O were recorded in eight of the twelve vacuum monitoring points. The measured average vacuum in these locations ranged from -0.005 to -0.127 in- H_2O . Based on an analysis of the pilot study data, two new extraction wells, in addition to the five existing extractions, will be required to mitigate vapor intrusion beneath the space.

Elevated concentrations of PCE were detected in each of the effluent samples ranging from 1,000 to 71,000 $\mu g/m^3$. The highest concentration was detected in EW-3 installed in the approximate location of the former dry cleaner tenant space. The predicted effluent concentrations, as generated using the AERSCREEN dispersion modeling (PCE, TCE and methylene chloride), did not exceed the concentration values for contaminants of concern listed within the SGC and AGC values. Accordingly, effluent concentrations that will be generated by the SSDS do not require treatment prior to atmospheric discharge.

4.0 SSDS DESIGN

The SSD system design presented herein is proposed to depressurize the entire footprint of Site building. As noted in the *Additional Site Characterization and SSDS Pilot Study Report*, potential gaps in the ROI demonstrated during pilot testing are present and must be addressed through installation of two additional extraction wells. The absence of vacuum at SG-4 and low-level vacuum at SG-6 in the southern/ central portion of the building will be addressed through installation of a new extraction well in that portion of the building during system installation. Similarly, the absence of vacuum at SG-8 in the northwestern portion of the building will be addressed through installation of an extraction well in that portion of the building.

Prior to installation of the SSDS, a Commercial Building Permit will be obtained through the City of Kingston Building Department.


4.1 SSDS DESIGN PARAMETERS

The SSDS design for the will utilizes the five existing extraction wells (EW-1 through EW-5), along with two new proposed extraction wells. The proposed well locations are depicted on **Figure 5, SSDS Installation Plan View**. The proposed extraction well details are depicted in **Figure 7, Detail 1**. Conditions of low air flow and high vacuum were observed at wells EW-1 through EW-4 during pilot testing. High air flow and low vacuum was observed at EW-5 located in the central portion of the building during pilot testing. According to site personnel, sub-slab utilities are present in the central hallway corridor. The presence of such utilities can create conditions of high air flow and low vacuum. It is anticipated that the well on the southern/ central portion of the building will exhibit conditions of high air flow and low vacuum. Conversely, it is anticipated that the proposed well in the northwestern portion of the building will exhibit conditions of low air flow and high vacuum. Based on pilot testing data, a total of three SSDS fans will be required to mitigate the building, as described in Sections 4.1.1 through 4.1.3 below.

4.1.1 Eastern Portion of Building

EW-1 and EW-4 will be connected to one (1) GBR 76UD high vacuum fan (cumulative system air flow 66 CFM). Operating at the maximum projected applied vacuum 22.5 in-H₂O, the cumulative air flow falls under the fan curve for a 120-volt Obar® GBR 76UD fan.


Figure 4.1.1 - GBR 76UD @ 120V



4.1.2 Central Portion of Building

EW-5 and the proposed well in the southern/ central portion of the building will be connected to one (1) GBR 89HA high air flow fan (cumulative system air flow 180 CFM assuming the proposed extraction well is similar to EW-5). Operating at the maximum projected applied vacuum 10.3 in-H₂O, the cumulative air flow falls under the fan curve for a 120-volt Obar® GBR 89HA fan.


Figure 4.1.2 - GBR89 @ 120V



4.1.3 Western Portion of Building

EW-2, EW-3 and the proposed extraction well in the northwestern portion of the building will be connected to one (1) GBR 76UD high vacuum fan (cumulative system air flow 102 CFM assuming the proposed extraction well is similar to EW-2 & EW-3). Operating at the maximum projected applied vacuum 36 in-H₂O, the cumulative air flow falls under the fan curve for a 120-volt Obar® GBR 76UD fan.

Figure 4.1.3 - GBR 76UD @ 120V



The existing and proposed well locations are depicted in **Figure 5**. **Figure 6A** is a process flow diagram depicting the proposed equipment and generalized piping layout within the building. **Figure 8** includes a roof view showing the locations of the proposed riser pipe roof penetrations, fan/ exhaust locations and potential HVAC air intake locations. All piping/ fan locations are subject to change based on site conditions observed during installation, and will be made in consultation with the engineer of record.

4.2 PIPING AND SYSTEM COMPONENTS

All wells connected to the GBR 76UD fans (EW-1, EW-2, EW-3, EW-4 and the proposed EW in the northwestern portion of the building) will consist of 3-inch schedule 40 PVC. The wells connected to the GBR 89HA fan (EW-5 and the proposed EW in the southern/central portion of the building) will consist of 4-inch schedule 40 PVC. The proposed well in the northwestern portion of the space will include an approximate 3 & 1/2 -inch slab core and will follow the design specifications in **Figure 7, Detail 1**. The proposed well in the southern/central portion of the space will include an approximate 4 & 1/2 -inch slab core and will follow the design specifications in **Figure 7, Detail 1**. All PVC risers will be connected to each extraction well and extended vertically above the drop ceiling. All interior PVC may be foam or solid core schedule 40. All exterior PVC must be solid core schedule 40.

A nylon ball valve will be installed at a height of approximately 4-5-feet above the slab on each riser pipe. The purpose of the valve is to allow for collection of system operational data, including air flow, temperature, vacuum, PID readings and effluent laboratory samples. See **Figure 7, Detail 3** for the sample ball valve installation specifications.

A SSDS label will be placed on each riser pipe at a height of approximately 5-feet above the slab. The label will read, "THIS IS A COMPONENT OF A SUB-SLAB VENTING SYSTEM. DO NOT TAMPER WITH OR DISCONNECT."

An Obar® GBR 25 vacuum gauge and visual / audible alarm will be installed on a wall proximal to select wells (See **Figures 6A, 6B and 6C**). Note, the location of the alarm may be changed to a different extraction well within the units based on building occupant and ownership consultation. A total of three alarms (one per fan) s will be connected to dedicated outlets to be installed by the electrician. The outlets will be outfitted with a protective cover and tamper proof lock to prevent tenant from mistakenly disconnecting the alarm. Tubing will connect the alarm to the sample port installed on the extraction well. The visual/ audible alarm will be preset to trigger if the vacuum within the riser pipes fall below 1-in H₂O. The screen of the gauge will provide a real-time digital output of system vacuum. All remaining wells will be outfitted with wall mounted Dwyer® Minihelic vacuum gauges for real-time vacuum monitoring. The vacuum gauges for EW-1, EW-2, EW-3, EW-4 and the proposed well in the northwestern portion of the space will have a threshold of 0 to 40 in H₂O. The vacuum gauges for EW-5 and the proposed well in the southern/ central portion of the space will have a threshold of 0 to 20 in H₂O. Specifications for the Obar® GBR 25 vacuum gauge and visual / audible alarm and Dwyer® Minihelic vacuum gauge are included in **Appendix A**.

Inline PVC ball valves will be installed on the vertical pipe prior to the drop ceiling for system balancing purposes. The ball valves should be located at a height such that it cannot be easily tampered with by the tenants/ occupants of the space (7-8 feet above slab grade).

Each of the extraction wells will be connected above the drop ceiling using smooth T junctions. The combined pipe runs will be directed to the locations of proposed roof penetrations (See **Figure 8, Roof Installation Plan**). The PVC pipe will be secured with steel clevis hangers or approved equivalents, spaced every 8 to 10-feet. The hangers will be secured to the roof decking/ supports with either wood anchors or C-clamps. All horizontal piping will be installed with an approximate 1% pitch towards each extraction well to promote condensate drainage. All coupler and elbow connections will be made with medium duty PVC primer and glue.

4.3 ROOF / SIDEWALL PENETRATIONS & SEALING

A roofing contractor will be retained to install penetrations for the 3 and 4-inch schedule 40 PVC riser pipes through the roof. A total of three penetrations are proposed (one for each SSDS fan). A watertight rubber boot seal will be installed around each pipe. (See **Figure 7, Detail 7**).

Sidewall penetrations may be made as an alternative to roof penetrations to route the PVC piping outside of the building. An approximate 3 ½ or 4 ½-inch core will be made in the exterior wall and the pipe(s) will be routed through the wall to the exterior. A fire rated foam will be applied inside the structure and the exterior wall will be sealed with a cement/ mortar (See **Figure 7, Detail 4**).

4.4 FAN MOUNTING & EXTERIOR PIPING

The piping from each extraction wells will be routed directly from the roof penetration into the intake of the SSDS fan(s). No horizontal roof piping is currently proposed. However, if horizontal roof piping is required, the PVC will be mounted to DuraBlock® roof supports (approximate 10-

foot spacing) and secured with galvanized pipe strut clamps. All horizontal piping will have a 1% pitch towards the extraction well for condensation drainage.

The SSDS fan(s) will be mounted to an Obar GBR® roof mount set on foam piers. The effluent discharge of each fan will be terminated a minimum of 3-feet above the roofline and a minimum of 10-feet or more from any HVAC intake, windows or other building opening. Copies of the DuraBlock® roof support specification sheets are included in **Appendix A**. A copy of the Obar GBR® roof mount technical specifications is included in **Appendix A**.

4.5 ELECTRICAL

The fans will be wired (120V) to a dedicated breaker in the house panel by a City of Kingston licensed electrician and in accordance with local, county and state electrical codes. A dedicated outlet will also be installed in proximity to each Obar® GBR 25 vacuum gauge and visual / audible alarm.

4.6 AERSCREEN EVALUATION

The sub-slab samples collected during pilot testing from each extraction well were analyzed for VOCs to evaluate the toxicity and impacts on the receptors downwind using a dispersion model (AERSCREEN). AERSCREEN is a screening model based on the U.S. EPA AERMOD air quality dispersion model to predict ambient air concentrations attributed to a single source. The input parameters including total VOC concentrations, effluent loading rates, stack height, flow rates, temperature, velocity and the distance to the receptor (Estimated at 10 feet) were compared to the NYSDEC DAR Air Guidance (DAR-1) Guidelines for the Control of Toxic Ambient Air Contaminants, AERSCREEN computer program (**Table 4**). The average flow for each extraction well during pilot testing was used in the AERSCREEN model. The generated concentrations were compared with Short-term Guideline Concentrations (SGCs) and Average-Annual Guidance Criteria (AGCs). A scenario was run for combined effluent assuming use of each of the five pilot test extraction wells. The model's predicted results for PCE, TCE and methylene chloride, did not exceed the concentration values for contaminants of concern listed within the SGC and AGC values. The pilot testing laboratory analytical data utilized in the AERSCREEN Model is included in **Appendix D**. The raw data inputs for the AERSCREEN model are included in **Appendix E**.

Accordingly, the results of pilot testing and the AERSCREEN model indicate that the levels to be discharged from the Site are acceptable for direct discharge to the atmosphere without vapor control during the full-scale SSD system operation. It should be noted that the pilot testing data used for the model are considered conservative as they were collected only 30 minutes after each pump test occurred. Effluent concentrations typically decrease significantly after the first month of operation in the absence of a significant groundwater plume or soil source areas. Effluent concentrations are expected to decrease with time based on the following factors:

- Cessation of on-Site dry-cleaning operations;
- The absence of a significant soil or groundwater source of cVOCs;

If additional testing indicates exceedance of ACGs/ SCGs, emissions controls will be considered for the Site.

4.7 SEALING OF CRACKS AND JOINTS

Any visible expansion joints or slab cracks in the Site building will be sealed. Generally, extensive cracking has not been observed throughout the building slab. Cracks will be sealed with a low-VOC caulk sealant. Any openings into the slab, such as those that may occur around conduit pipe penetrations through the slab, will be cleaned and sealed with low-VOC caulk.

4.8 CHEMICAL INVENTORY SURVEY

A building chemical inventory survey will be conducted in conjunction with the SSDS installation. The survey will include notation of chemical types, quantities and locations within the building. A copy of the NYSDOH Indoor Air Quality Questionnaire and Building Inventory Form is included in **Appendix F**.

5.0 TESTING, OPERATION & MAINTENANCE

The system will be monitored for a period of 1-year after startup as described in this section. Only the testing, operation and maintenance proposed within the first year of system operation are included in this design document. Long term testing, operation and maintenance of the SSDS beyond the first year will be outlined in a Site Management Plan (SMP) which will be prepared following completion of additional remedial actions proposed for the Site. If the SMP has not been completed within 1 year of the SSDS installation, a standalone SSDS Operation & Maintenance Plan will be prepared. During each of the inspections described in the section, any deficiency observed will be corrected as needed by the field team. These will be noted in monthly status reports prepared for the Site.

5.1 SYSTEM STARTUP TESTING

Immediately following the SSDS installation and system startup, Bellucci Engineering will collect system data including:

- Extraction well vacuum (in-H₂O)
- Extraction well temperature (°F)
- Extraction well velocity (FPM) – to be converted for CFM
- Sub-slab vacuum (in-H₂O)

System balancing will be performed during initial testing and the collected data will be evaluated against pilot testing data.

5.2 POST SYSTEM STARTUP TESTING – 1 WEEK

Approximately one week after system startup, Bellucci Engineering will revisit the site for a 1-week post-system inspection. During this inspection, Bellucci Engineering will collect system data including:

- Extraction well vacuum (in-H₂O)
- Extraction well temperature (°F)
- Extraction well velocity (FPM) – to be converted for CFM
- Sub-slab vacuum (in-H₂O)

A sample will be collected from each of the seven (7) proposed extraction wells. The samples will be collected using batch clean SUMMA canisters. The extracted vapor samples will be sent to an NYSDOH-approved laboratory and analyzed for VOCs by EPA method TO-15. The extracted vapor sample results will be compared with the respective AGC and SGC values and the AERSCREEN model will be updated to determine if a vapor control system is required.

5.3 POST SYSTEM STARTUP TESTING – 1 MONTH

Approximately one month after system startup, Bellucci Engineering will revisit the site for a post system testing. During this inspection Bellucci Engineering will collect system data including:

- Extraction well vacuum (in-H₂O)
- Extraction well temperature (°F)
- Extraction well velocity (FPM) – to be converted for CFM
- Sub-slab vacuum (in-H₂O)

It is anticipated that elevated concentrations of cVOCs in indoor air detected within the tenant spaces will begin to decrease immediately following system startup. Indoor air testing at each of the five (5) prior indoor air test locations and within Suites A and B, not previously tested, (See **Figure 3, IRM Sampling and Testing Location Map**) will be conducted approximately 1-month after system startup. A total of seven (7) indoor and one (1) outdoor ambient air samples will be collected from the Site. The outdoor ambient air sample will be collected from and upwind location on the property. Each sample will be collected at a height of 3-5 feet from the ground within the approximate breathing zone. Parameters including indoor and outdoor air temperature, wind direction and relative humidity will be noted during the sampling event.

The air samples will be collected for analysis in batch clean SUMMA canisters equipped with a laboratory calibrated flow control device to facilitate the collection of the samples for an 8-hour sample duration time. Following sampling, the pressure of the SUMMA canisters will be recorded. A sample log sheet will be maintained summarizing sample identification, date and time of sample collection, sampling depth, identity of samplers, sampling methods and devices, vacuum of canisters before and after the samples are collected, and chain of custody protocols.

The air samples will be submitted to a NYSDOH-approved laboratory for analysis of VOCs by EPA Method TO-15.

5.4 QUARTERLY OPERATION & MAINTENANCE

Following the first month of operation, the SSDS will be monitored on a quarterly basis for the first year, unless startup testing indicates more frequent monitoring is required. During each quarterly monitoring event, Bellucci Engineering will collect system data including:

- Extraction well vacuum (in-H₂O)
- Extraction well temperature (°F)
- Extraction well velocity (FPM) – to be converted for CFM
- Sub-slab vacuum (in-H₂O)

Indoor air samples will be collected from each tenant space as described in Section 5.3 during each quarterly monitoring event for the first year of operation. The monitoring frequency may be adjusted pending the results of initial testing. Long term testing, operation and maintenance will be determined based on the evaluation of the first year of operational data and will be made in consultation with NYSDEC and NYSDOH. This will be documented in the SMP or as a standalone SSDS Operation & Maintenance Plan if the SMP/ Final Engineering Report is not completed within 1 year of the system installation.

6.0 SSDS INSTALLATION SUPPORT ACTIVITIES

6.1 COMMUNITY AIR MONITORING PLAN

A site-specific Community Air Monitoring Plan (CAMP) has been prepared for the Site and has been placed in **Appendix B**. This document will be employed during all ground intrusive indoor Site activities. It should be noted that the proposed design includes minimal sub-grade excavation. All concrete disturbance activities will include the use of wet concrete cutting methods.

6.2 HEALTH & SAFETY PLAN

A Site and contaminant specific Health and Safety Plan (HASP) has been prepared for the Site and is included as **Appendix C**. Field personnel will be outfitted in the appropriate health and safety equipment (i.e., nitrile gloves, level D personal protective equipment) and be educated on Site-specific hazards.

6.3 TENANT COMMUNICATION

Prior to system installation, each of the ground floor tenants will be notified. All ground intrusive work will be conducted during weekend hours while the tenants are not present. After installation of the SSD system, an information package will be prepared and provided to the tenants. The information package will provide a description of the SSDS, a summary of the proposed testing, operation and maintenance of the SSDS, how the tenant can confirm the system is operating properly, and contact information in case of system failure or other questions. A copy of the tenant information package will be submitted to NYSDEC and NYSDOH and will be memorialized in the Construction Completion Report (CCR).

6.4 WASTE HANDLING

All investigation/installation-derived waste (IDW) will be contained on-Site in a secure area for appropriate characterization and disposal. Soil, personal protective equipment, and spent disposable sampling materials will be segregated by waste type and placed in DOT-approved 55-gallon steel drums. Waste construction materials such as scrap PVC pipe will be discarded in appropriate containers as general construction waste. All decontamination water will be stored in 55-gallon drums as necessary. Field staff will maintain an inventory of all waste storage vessels. All storage vessels will be appropriately labeled with the contents, generator, location, and date.

7.0 REPORTING & SCHEDULE

The SSDS will be installed within 60-days of receipt of the Department's approval of this Design Document, pending approval of local permitting requirements.


A CCR will be prepared and submitted to NYSDEC and NYSDOH following installation and startup of the SSDS. The report will include a summary of the first month of testing, operation and maintenance. The CCR will include a description of the SSDS as constructed, modifications to the system design, the data collected, and record drawings. The CCR will be stamped, certified and signed by a New York State licensed professional engineer.

It is anticipated that the CCR will be completed within 3 months of system startup. A Site Management Plan or a standalone SSDS Operation & Maintenance Plan (if the Final Engineering Report is not complete) will be prepared and submitted approximately 1 year after system installation.

The following table summarizes the anticipated schedule for the Site:

Milestone	Anticipated Date
NYSDEC and NYSDOH approved of SSDS Design Document	August 2022
Installation of SSDS/ System Startup and Testing	October 2022
1-Week Post System Startup Testing	October/ November 2022
1-Month Post System Startup Testing	December 2022
Construction Completion Report	January/ February 2023
Quarterly O&M	March, June, September & December 2023
SSDS Operation & Maintenance Plan or SMP/ Final Engineering Report	Winter/ Spring of 2024

FIGURES



Client: MMJD Equities, LLC

Site: 65 Albany Avenue, Kingston, New York



Site No.:
 356060

Drawn by:
 DJT

Scale:
 Graphic

Site Location Plan

Figure No: 1



Client: MMJD Equities, LLC

Site: 65 Albany Avenue, Kingston, New York


Site No.:
356060

Drawn by:
DJT

Scale:
Graphic


Surrounding Land Use


Figure No: 2



PE Seal/ Certification







Bellucci Engineering PLLC

Client: MMJD Equities LLC

Location: 65 Albany Avenue, Kingston, Ulster County, New York

Title: SSDS Installation - Plan View

Scale: Graphic


Base Map By: D.T.


Site #: 356060


P.E. Certification/ Seal





Figure 5




Prepared by: Bellucci Engineering PLLC	P.E. Certification/ Seal 	Location: 65 Albany Avenue Kingston, New York	PROCESS FLOW DIAGRAM - EW-1 & EW-4		
NOT TO SCALE		Client: MMJD Equities LLC	PE/PG DB	Site Number 356060	Figure 6A
			Project Manager DT	Drafter DB	




Prepared by: Bellucci Engineering PLLC	P.E. Certification/ Seal 	Location: 65 Albany Avenue Kingston, New York	PROCESS FLOW DIAGRAM-EW-5 & PROPOSED EW		
NOT TO SCALE		Client: MMJD Equities LLC	PE/PG DB	Site Number 356060	Figure 6B
			Project Manager DT	Drafter DB	




Prepared by: Bellucci Engineering PLLC	P.E. Certification/ Seal 	Location: 65 Albany Avenue Kingston, New York	PROCESS FLOW DIAGRAM-EW-2, EW-3 & PROPOSED EW		
NOT TO SCALE		Client: MMJD Equities LLC	PE/PG DB	Site Number 356060	Figure 6C
			Project Manager DT	Drafter DB	


DETAIL 1 - SSDS EXTRACTION WELL DESIGN



DETAIL 4 - EXTERIOR WALL PIPE PENETRATION




DETAIL 6 - EXTERIOR WALL PIPE MOUNTING




- GENERAL INSTALLATION NOTES
1. ALL PVC JOINTS SHALL BE SEALED WITH PLUMBERS CEMENT (OR SIMILAR PRODUCT) TO BE APPLIED ACCORDING TO THE MANUFACTURERS SPECIFICATIONS.
 2. HORIZONTAL PIPING SHALL BE PITCHED DOWN FROM THE RISER PIPE TOWARDS EXTRACTION WELL AT ~ 1 /8 PER FOOT (1 % SLOPE) TO FACILITATE CONDENSATION DRAINAGE.
 - 3.FANS HARD WIRED BY A CITY OF KINGSTON LICENSED ELECTRICAL CONTRACTOR IN ACCORDANCE WITH CITY OF KINGSTON CONSTRUCTION CODE AND ANY OTHER APPLICABLE CODE AND REGULATIONS UTILIZING A HARDWIRED ELECTRICAL CONNECTION WITH A DEDICATED AND BREAKER FROM HOUSE PANEL. DEDICATED OUTLET FOR AUDIBLE/ VISUAL ALARM TO BE COORDINATED BY ENGINEER W/ ELECTRICIAN.
 4. THE ROOFING CONTRACTOR IS RESPONSIBLE FOR WEATHER-TIGHT PROTECTION OF ROOFING AT ALL TIMES DURING THE WORK.


DETAIL 2 - VACUUM MONITORING POINT DESIGN




DETAIL 3 - SAMPLE PORT INSTALLATION



DETAIL 5 - TYPICAL HANGER



DETAIL 7 - ROOF PENETRATION DETAIL



P.E. Certification/ Seal




DT Consulting Services, Inc.
&
Bellucci Engineering, PLLC


Installation Details & Notes

Project
**65 Albany Avenue
Kingston, New York**


Site Number	356060	Figure
PE/PG	DB	Drafter
	DT	DB



Explanation Block



Fan Roof Mount Location



HVAC Air Handler

NOTES:

*Maintain minimum distance of 10-feet from air handlers/ building intakes, door and windows

**All piping & roof penetrations subject to change based on field conditions. All changes must be approved with the engineer of record.

P.E. Certification/ Seal



Bellucci Engineering PLLC

Roof Installation Plan

Project
65 Albany Avenue
Kingston, New York

Site Number	356060	Figure	8
PE/PG	DB	Drafter	DB

APPROXIMATE SCALE
(FEET)

TABLES

TABLE 1
EXTRACTION WELL DATA- SSDS PILOT TEST
65 Albany Avenue, Kingston, NY
Site #356060

Test #	Time	Pump Well Number	Fan/ Blower	Potential-meter %	Velocity (FPS)	Flow Rate (CFM)	Vacuum (in-Hg)	Vacuum (in-H ₂ O)	Temp (°F)	PID (ppm) Pre Carbon	PID (ppm) Post-Carbon
Test # 1	9:30	EW-1	89HA	50	60	20.1	0.440	6.0	53.5	0.5	0.0
	9:50		89HA	73	245	21.4	0.551	7.5	52.3	0.0	0.0
	9:55		89HA	89	239	20.8	0.734	10.0	55.0	0.0	0.0
	10:00		89HA	100	300	26.2	0.882	12.0	53.9	0.1	0.0
	10:05		89HA	89	240	20.9	0.734	10.0	53.8	0.1	0.0
	10:10		89HA	90	220	19.2	0.734	10.0	54.3	0.1	0.0
Test #2	10:30		HS5000	N/A	680	34.3	2.277	31.0	54.8	0.1	0.0
Average					283	23.3	0.907	12.4	53.9	0.1	0.0
Test # 3	11:10	EW-2	89HA	100	230	20.1	0.882	12.0	65.5	0.6	0.0
Test # 4	11:20		HS5000	N/A	950	47.9	2.792	38.0	70.8	1.0	0.0
	11:30		HS5000	N/A	760	38.3	2.792	38.0	72.3	1.0	0.0
	11:40		HS5000	N/A	950	47.9	2.756	37.5	75.1	1.4	0.0
Average					723	39	2.306	31.4	70.9	1.0	0.0
Test # 5	12:10	EW-3	HS5000	N/A	660	33.3	2.682	36.5	74.0	3.0	0.0
	12:20		HS5000	N/A	730	36.8	2.682	36.5	76.8	2.6	0.0
	12:30		HS5000	N/A	630	31.8	2.645	36.0	77.8	2.6	0.0
Average					673	34.0	2.670	36.3	76.2	2.7	0.0
Test # 6	13:30	EW-5	89HA	100	1140	99.4	0.882	12.0	65.8	0.8	0.0
	13:40		89HA	100	1150	100.3	0.882	12.0	61.8	1.0	0.0
	13:50		89HA	100	1250	109.0	0.882	12.0	62.0	0.8	0.0
Test # 7	14:00		HS5000	N/A	1050	53.0	0.368	5.0	61.8	0.7	0.0
Average					1148	90.4	0.753	10.3	62.9	0.8	0.0
Test # 8	14:30	EW-4	89HA	100	250	21.8	0.882	12.0	60.0	0.3	0.0
Test # 9	14:50		HS5000	N/A	950	47.9	1.911	26.0	66.3	0.2	0.0
	15:00		HS5000	N/A	930	46.9	1.911	26.0	64.3	0.1	0.0
	15:10		HS5000	N/A	1100	55.5	1.911	26.0	65.9	0.1	0.0
Average					808	43.0	1.654	22.5	64.1	0.2	0.0

Notes:

in-Hg = inches of mercury

in-H₂O = Inches of water

CFM = cubic feet per minute

ppm = parts per million

TABLE 2
VACUUM MONITORING POINT DATA - SSDS PILOT TEST
65 Albany Avenue, Kingston, NY
Site #356060

Test #	Test Well	Time	Vacuum Response (in-H ₂ O)											
			SG-1	SG-2	SG-3	SG-4	SG-5	SG-6	SG-7	SG-8	TSG-1	TSG-2	SG-9	SG-10
Test #1	EW-1	9:30	NT	-0.003	NT	NT	NT	NT	NT	NT	NT	NT	NT	0.000
		9:50	NT	-0.009	NT	NT	NT	NT	NT	NT	NT	NT	NT	-0.003
		9:55	NT	-0.012	NT	NT	NT	NT	NT	NT	NT	NT	NT	-0.003
		10:00	NT	-0.008	NT	NT	NT	NT	NT	NT	NT	NT	NT	-0.001
		10:05	NT	-0.010	NT	NT	NT	NT	NT	NT	NT	NT	NT	0.000
		10:10	NT	-0.011	NT	NT	NT	NT	NT	NT	NT	NT	NT	-0.001
AVERAGE			NT	-0.009	NT	NT	NT	NT	NT	NT	NT	NT	-0.001	
Test # 2	EW-1	10:30	NT	-0.035	NT	NT	NT	NT	NT	NT	NT	NT	-0.005	
AVERAGE			NT	-0.035	NT	NT	NT	NT	NT	NT	NT	NT	-0.005	
Test # 3	EW-2	11:10	NT	NT	NT	0.000	NT ¹	-0.001	NT	NT	NT	NT	NT	NT
AVERAGE			NT	NT	NT	0.000	NT ¹	-0.001	NT	NT	NT	NT	NT	NT
Test # 4	EW-2	11:20	NT	NT	NT	0.000	NT	-0.004	NT	NT	NT	NT	NT	NT
		11:30	NT	NT	NT	0.000	NT	-0.004	NT	NT	NT	NT	NT	NT
		11:40	NT	NT	NT	-0.003	NT	-0.002	NT	NT	NT	NT	NT	NT
AVERAGE			NT	NT	NT	-0.001	NT	-0.003	NT	NT	NT	NT	NT	NT
Test # 5	EW-3	12:10	NT	NT	NT	NT	NT	NT	-0.006	0.000	-0.044	NT	NT	NT
		12:20	NT	NT	NT	NT	NT	NT	-0.005	0.000	-0.046	NT	NT	NT
		12:30	NT	NT	NT	NT	NT	NT	-0.006	0.000	-0.044	NT	NT	NT
AVERAGE			NT	NT	NT	NT	NT	NT	-0.006	0.000	-0.045	NT	NT	NT
Test #6	EW-5	13:30	NT	NT	-0.009	0.000	NT	NT	-0.130	NT	NT	-0.044	NT	NT
		13:40	NT	NT	-0.010	-0.002	NT	NT	-0.125	NT	NT	-0.045	NT	NT
		13:50	NT	NT	-0.007	-0.001	NT	NT	-0.125	NT	NT	-0.042	NT	NT
AVERAGE			NT	NT	-0.009	-0.001	NT	NT	-0.127	NT	NT	-0.044	NT	NT
Test # 7	EW-5	14:00	NT	NT	-0.002	-0.001	NT	NT	N/A	NT	NT	-0.016	NT	NT
AVERAGE			NT	NT	-0.007	-0.001	NT	NT	N/A	NT	NT	-0.016	NT	NT
Test # 8	EW-4	14:30	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT	-0.034	NT
AVERAGE			NT	NT	NT	NT	NT	NT	NT	NT	NT	NT	-0.034	NT
Test # 9	EW-4	14:50	-0.052	-0.009	NT	NT	NT	NT	NT	NT	NT	NT	-0.082	NT
		15:00	-0.048	-0.007	NT	NT	NT	NT	NT	NT	NT	NT	-0.091	NT
		15:10	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT	-0.095	NT
AVERAGE			-0.050	-0.008	NT	NT	NT	NT	NT	NT	NT	NT	-0.067	NT

Notes:

in-H₂O = Inches of water

Vacuum monitoring point measurements taken with Infiltec DMI Micro Manometer with a detection limit of 0.001
NT - Not tested. Only selected points were tested during each pilot test based on anticipated ROI and the building layout.

NT¹ - Cannot test SG-5 during Test #3 & 4 because space is locked.

Average vacuum greater than target value of -0.004 in-H₂O

Average vacuum less than target value of -0.004 in-H₂O but greater than 0.000 in-H₂O

TABLE 3
MASS REMOVAL CALCULATIONS -LABORATORY ANALYTICAL DATA
65 Albany Avenue, Kingston, NY
Site #356060

Sample Location	Sample Starting Period	Sample Ending Period	Sample Duration (minutes)	Average Flow Rate (CFM)	Temp. (°F)	Temp. (R)	In-Hg	Atm. (Relative)	Atm. (Corrected)	V=nRT/p	lb mole	Volume of Removed Soil Vapor (CF)	PCE (ppmv)	TCE (ppmv)	Methylene Chloride (ppm)	PCE Mass Removed (lbs)	TCE Mass Removed (lbs)	Methylene Chloride Mass Removed (lbs)	Total Mass Removed (lbs)
EW-1	4/3/22 10:30 AM	4/3/22 11:00 AM	30	23.3	53.9	513.9	0.907	0.030	0.970	387.0	0.00258	698	0.15	0.00000	0.0033	4.40E-05	0.00E+00	5.05E-07	4.45E-05
EW-2	4/3/22 11:20 AM	4/3/22 11:50 AM	30	38.6	70.9	530.9	2.306	0.077	0.923	420.0	0.00238	1157	0.35	0.00050	0.0780	1.60E-04	1.82E-07	1.82E-05	1.78E-04
EW-3	4/3/22 12:00 PM	4/3/22 12:30 PM	30	34.0	76.2	536.2	2.670	0.089	0.911	429.9	0.00233	1019	10	0.0029	0.0064	3.93E-03	9.03E-07	1.29E-06	3.93E-03
EW-4	4/3/2022 14:40:00 PM	4/3/2022 15:10:00 PM	30	43.0	64.1	524.1	1.654	0.055	0.945	405.1	0.00247	1291	0.20	0.00036	0.0018	1.06E-04	1.51E-07	4.87E-07	1.06E-04
EW-5	4/3/2022 13:20:00 PM	4/3/2022 13:50:00 PM	30	90.4	62.9	522.9	0.753	0.025	0.975	391.6	0.00255	2,713	0.63	0.00052	0.012	7.24E-04	4.73E-07	7.06E-06	7.31E-04
Total			150									6,878				4.96E-03	1.71E-06	2.76E-05	4.99E-03
Mass Removal Rate (lbs/day)																			4.79E-02

Notes:

Where: V = volume of the gas; P = pressure of the gas; n = l lb-mole; R = Ideal Gas Constant (0.7302); T = Absolute Temperature (°F+460)

$V=nRT/p$

Mass Removed = [(1 / Volume of gas) x (time elapsed) x (Flow) x (Concentration CVOC) x (molecular weight CVOC)] / 1x10⁶

Molecular weights (g/mole): PCE 165.83, TCE 131.39, Methylene Chloride 84.93

CFM = cubic foot per minute

ppmv = parts per million by volume

lbs = pounds

1-in-Hg = 0.033421 atm

TABLE 4
AERSCREEN Model Input and Output Data
65 Albany Avenue, Kingston, NY
Site # 356060

Compound	Projected System Flow (CFM)	Average Temp. (°F)	Pilot Test Mass Removed (lbs/Hr)	Maximum 1-Hour Concentration (AERSCREEN Model Output)	ACG	SCG	Exceeds ACG/SCG ?
PCE	320	65.6	9.93E-03	0.832	3.8	300	No
TCE	320	65.6	3.42E-06	0.00286	0.21	20	No
Methylene Chloride	320	65.6	5.52E-05	0.0463	46	1400	No

Notes

Projected flow rates based on pilot testing data.

Temperature readings are an average of pilot testing extracted vapor temperatures

Mass removed is based on laboratory analytical data.

Each pilot test was run for an approximate 30 minute duration. Table 10 includes the projected mass removal during each 30 minute pilot test. Those values were multiplied by 2 for AERSCREEN modeling in lbs/hour.

APPENDIX A
EQUIPMENT & MATERIALS SPECIFICATIONS SHEETS

THE OBAR GBR76

COMPACT RADIAL BLOWER



Based on 25 years of experience and 2 years of research and development, the patent pending GBR series of compact radial blowers provide the perfect combination of performance and design.

PERFORMANCE

- GBR76 SOE 16" WC @ 0 Max flow 155 CFM.
- GBR76 UD 40" WC @ 0 Max flow 195 CFM.
- Built in speed control to customize performance.
- Condensate bypass built in.
- 12 month warranty - 40,000 hr sealed bearings.



GBR76 WITH ROOF MOUNT

DESIGN

- Our modular design means the blower and manifold assembly can be removed and replaced as a unit. This makes repairs cost effective and easy and allows contractors to upgrade systems simply by swapping assemblies.
- The GBR series is based on a bypass blower designed to handle combustible materials.
- The housing is not required to be air tight, so you can add gauges and alarms without compromising the system.
- Built in condensate bypass.
- Built in speed control.
- Quick disconnect electrical harness.
- All UL listed components including UL listed enclosure for outside use.
- Wall fastening lugs included.
- GBR series roof and wall mounts available to quickly configure the blowers for your installation while providing a custom built look.
- Compact design 16"x 14"x 8" weighing only 18 lbs.
- 3" schedule 40 inlet and exhaust.
- Universal Drive model accepts voltage from 120-240V without alteration

COST

GBR76 SOE

GBR76 UD

COMPLETE UNIT
3 YEAR WARRANTY

\$1289.00
\$450.00

\$1489.00
\$550.00

GBR76 SOE	0"	2"	4"	6"	8"	10"	12"	16"	Wattage
SOE 16	150	140	129	118	105	90	75	35	150-320
SOE 12	125	115	100	83	62	39	0		110-200
SOE 8	105	90	70	42	0				60-120
SOE 4	75	50	0						37-50

GBR SOE performance using built in potentiometer set at sealed vacuums of 16, 12, 8, and 4" WC

GBR76 UD	0"	10"	20"	30"	37"	Wattage
110V	195	158	118	63	20	700-870
220V	197	162	130	89	50	800-1100

Blower Specifications

Notes:

- **Input Voltage Range:** 108-132 Volts AC RMS, 50/60 Hz, single phase.
 - **Input Current:** 6 amps AC RMS
 - **Operating Temperature (Ambient Air and Working Air):** 0°C to 50°C
 - **Storage Temperature:** -40°C to 85°C
 - **Dielectric Testing:** 1500 Volts AC RMS 60 Hz applied for one second between input pins and ground, 3mA leakage maximum.
 - **Speed Control Methods:** PWM (Pulse Width Modulation) (1 kHz to 10 kHz)
0 to 10 VDC speed control.
- Mechanical: A potentiometer is available for speed control of the blower. The potentiometer can be preset for a specific speed. Access for speed adjustment located in motor housing.
- **Approximate Weight:** 4.8 Lbs. / 2.2 Kg
 - **Regulatory Agency Certification:** Underwriters Laboratories Inc. UL507 Recognized under File E94403 and compliant under the CE Low Voltage Directive 2006/95/EC.
 - **Design Features:** Designed to provide variable airflow for low NOx & CO emission in high efficiency gas fired combustion systems. Built with non-sparking materials. Blower housing assembly constructed of die cast aluminum. Impeller constructed from hardened aluminum. Rubber isolation mounts built into blower construction to dampen vibration within the motor. Two piece blower housing assembly sealed with O-ring gasket for combustion applications. Customer is responsible to check for any leakage once the blower is installed into the final application.
 - **Miscellaneous:** Blower inlet, discharge, and all motor cooling inlet and discharge vents must not be obstructed. Motor ventilation air to be free of oils and other foreign particles, (i.e. breathing quality air). Blower is to be mounted so ventilation air cannot be re-circulated.
- POWER CONNECTION:** Blower connector, AMP Universal MATE-N-LOK, part no. 1-350943-0.
SPEED CONNECTION: Blower connector, Molex Mini-Fit Jr., part no. 39-30-3056.
Mating harnesses available upon request.

Enclosure Specifications

Ratings:

Ingress Protection (EN 60529): 66/67

Electrical insulation: Totally insulated

Halogen free (DIN/VDE 0472, Part 815): yes


UV resistance: UL 508

Flammability Rating (UL 746 C 5): complies with UL 508


Glow Wire Test (IEC 695-2-1) °C: 960

NEMA Class: UL Type 4, 4X, 6, 6P, 12 and 13

Certificates: Underwriters Laboratories




Screw cover



Top View - cover removed

GBR76-UD 120

Test date
3/22/13



THE OBAR GBR89

COMPACT RADIAL BLOWER



Based on 25 years of experience and 2 years of research and development, the patent pending GBR series of compact radial blowers provide the perfect combination of performance and design.

PERFORMANCE

- GBR89 HA 14" WC at 100CFM max flow 500 CFM.
- Built in speed control to customize performance.
- Condensate bypass built in.
- 12 month warranty 40,000 hr sealed bearings.



GBR89 WITH ROOF MOUNT

DESIGN

- Our modular design means the blower and manifold assembly can be removed and replaced as a unit. This makes repairs cost effective and easy and allows contractors to upgrade systems simply by swapping assemblies.
- The GBR series is based on a bypass blower designed to handle combustible materials.
- The housing is not required to be air tight so you can add gauges and alarms without compromising the system.
- Built in condensate bypass.
- Built in speed control.
- Quick disconnect electrical harness.
- All UL listed components including UL listed enclosure for outside use.
- Wall fastening lugs included.
- GBR series roof and wall mounts available to quickly configure the blowers for your installation while providing a custom built look.
- Compact design 18"x 16"x 10" weighing only 18 lbs.
- 4" schedule 40 inlet and 6" schedule 40 exhaust.

1. COST

GBR89 HA

COMPLETE UNIT	\$ 1,789.00
3 YEAR WARRANTY	\$650.00

Enclosure Specifications

Rating:

Ingress Protection (EN 60529): 66/67

Electrical insulation: Totally insulated

Halogen free (DIN/VDE 0472, Part 815): yes


UV resistance: UL 508

Flammability Rating (UL 746 C 5): complies with UL 508

Glow Wire Test (IEC 695-2-1) °C: 960

NEMA Class: UL Type 4, 4X, 6, 6P, 12 and 13

Certificates: Underwriters Laboratories




High Voltage Brushless DC Blowers

Nautilair (TM) 8.9" (226mm) Variable Speed Blower

240 Volt AC Input, Single Phase, High Output

Nautilair



		Part/ Model Number		
Specification	Units	150240	150241	150242
Speed Control	-	Mechanical	0-10 VDC	PWM

Notes:

- Input Voltage Range:** 216 - 264 Volts AC RMS, 50/60 Hz, single phase.
 - Input Current:** 10 amps AC RMS
 - Operating Temperature (Ambient Air and Working Air):** 0°C to 50°C
 - Storage Temperature:** -40°C to 85°C
 - Dielectric Testing:** 1800 Volts AC RMS 60 Hz applied for one second between input pins and ground, 3mA leakage maximum.
 - Speed Control Methods:** PWM (Pulse Width Modulation). Speed control input signal of 15 - 45 VDC @ 500 Hz - 10 kHz, and tachometer output (2 Pulses / Revolution).
Optional tachometer output (3 Pulses / Revolution).
0 to 10 VDC with a speed control input current of 5 mA to 20 mA at 10 VDC Input with multi-turn potentiometer set to minimum resistance (fully clockwise).
Mechanical: A potentiometer is available for speed control of the blower. The potentiometer can be preset for a specific speed. Access for speed adjustment located in motor housing.
4-20mA speed control available.
 - Approximate Weight:** 9.3 Lbs. / 4.2 Kg.
 - Option Card available for Customization**
 - Regulatory Agency Certification:** Underwriters Laboratories Inc. UL507 Recognized under File E94403 and CSA C22.2#133 under File LR43448
 - Design Features:** Designed to provide variable airflow for low NOx & CO emission in high efficiency gas fired combustion systems. Built with non-sparking materials. Blower housing assembly constructed of die cast aluminum. Impeller constructed from hardened aluminum. Rubber isolation mounts built into blower construction to dampen vibration within the motor. Two piece blower housing assembly sealed with O-ring gasket for combustion applications. Customer is responsible to check for any leakage once the blower is installed into the final application.
 - Miscellaneous:** Blower inlet, discharge, and all motor cooling inlet and discharge vents must not be obstructed. Motor ventilation air to be free of oils and other foreign particles, (i.e. breathing quality air). Blower is to be mounted so ventilation air cannot be re-circulated.
- POWER CONNECTION (3 CAVITY):** Blower connector, AMP Universal MATE-N-LOK, part no. 1-480701-0.
- POWER CONNECTION (5 CAVITY):** Blower connector, AMP Universal MATE-N-LOK, part no. 350810-1.
- SPEED CONNECTION (5 CAVITY):** Blower connector, Molex Mini-Fit Jr., part no. 39-01-4057.
- Mating harnesses available upon request.

This document is for informational purposes only and should not be considered as a binding description of the products or their performance in all applications. The performance data on this page depicts typical performance under controlled laboratory conditions. AMETEK is not responsible for blowers driven beyond factory specified speed, temperature, pressure, flow or without proper alignment. Actual performance will vary depending on the operating environment and application. AMETEK products are not designed for and should not be used in medical life support applications. AMETEK reserves the right to revise its products without notification. The above characteristics represent standard products. For product designed to meet specific applications, contact AMETEK Technical & Industrial Products Sales department.

AMETEK TECHNICAL & INDUSTRIAL PRODUCTS

627 Lake Street, Kent OH 44240


USA: +1 215-256-6601 - Europe: +44 (0) 845 366 9664 - Asia: +86 21 5763 1258

www.ametektip.com

B 47

AMETEK
PRECISION MOTION CONTROL

Typical Performance




Data presented represents blower performance at STANDARD AIR DENSITY, .075 lb/ft³ (29.92" Hg, Sea Level, 68° F)
Vacuum performance available upon request.

This document is for informational purposes only and should not be considered as a binding description of the products or their performance in all applications. The performance data on this page depicts typical performance under controlled laboratory conditions. AMETEK is not responsible for blowers driven beyond factory specified speed, temperature, pressure, flow or without proper alignment. Actual performance will vary depending on the operating environment and application. AMETEK products are not designed for and should not be used in medical life support applications. AMETEK reserves the right to revise its products without notification. The above characteristics represent standard products. For product designed to meet specific applications, contact AMETEK Technical & Industrial Products Sales department.

GBR89 HA tested at full voltage with 8 feet of 4" inlet (Blue Lines) and 6" Inlet (Green lines)

Maximum airflow with no exhaust piping and 8' of 6" piping is 529 CFM

GBR89 MA tested with speed control set to half the wattage consumption (Red Line)



GBR 25 Mini Digital Differential Pressure Gauge With Alarm



System alarms and monitoring made simple and affordable.

Finally a product that has what you need and can be easily installed.

The GBR 25 is a compact stand alone system gauge with an audible and visual alarm that works for VOC and Radon systems operating at system pressures greater than 2" wc. Included is a second relay that can be used to trigger additional alarms.

Includes Power supply

Optional 4-20 MA or 0-10 outputs can be used to monitor system pressure.

Contact OBAR for a quote to build custom alarm panels for your needs.

Applications and features

- Scale 0-40 inches WC eliminates need for multiple gauges.
- Visual and audible alarm included and factory set at 1" WC
The alarm set point can be changed in the field.
- Second adjustable relay for triggering additional alarms.
- Optional 4-20 MA or 0-10 output for data.
- Accuracy is up to $\pm 1\%$ FS, with large LCD display.
- Function keys: zero reset, units select, display update time, automatic sleep time, alarm, etc.

Specifications

Medium: Non-combustible, non-corrosive air, insensitive to moisture, dust, condensation and oil

Working Temp.: 20~70°C

Medium Temp.: 0~60°C

Temp. Compensation: 0~50°C

Working Pressure: overload 10xFS, burst 15xFS

Display: 5 bits LCD, with engineering unit & backlight

Output: 0-10V / 4-20mA (3 wires)

Output load: $\leq 500\Omega$ (current), $\geq 2K\Omega$ (voltage)

Relay Output: 2xSPST, 3A/30VDC, 3A/250VAC or 1xBuzzer

Accuracy: up to $\pm 1.0\%$ FS ($\pm 2.0\%$ FS @ 25Pa range)

Long term stability: $\pm 0.5\%$ FS / Year

Thermal effect: $< 0.05\%$ FS/°C (zero), $< 0.08\%$ FS/°C (FS)

Power type 16~28VDC/AC

24V Power Supply included


Process Connection: 5mm ID tubing, two pairs (left/back)

Keys: 3 touch buttons

Protection: IP54

Approval: CE

Display update time: selectable for 0.5/1/5/10s (default 1s)




Pricing: \$125 per unit

Add \$20 for 4-20 mA / 0-10V version

Custom options and bulk order pricing available. Call or email for details.

Other OBAR products you may be interested in.

DPT(DPT-F Flush Mount) Differential Pressure Transmitter





Roll over image to zoom.

DWYER

Differential Pressure Gauge: 15 to 0 to 15 in wc, Dual Side-Side or Back, 1/8 in NPT Female

Item # 1W465
UNSPSC # 41112403

Mfr. Model # 2330
Catalog Page # 575

Country of Origin USA. Country of Origin is subject to change.

☐ Compare this product

Product Image Feedback


Technical Specs


Item	Differential Pressure Gauge
Process Connection Gender	Female
Process Connection Location	Dual Side or Back
Process Connection Size	1/8 in
Process Connection Type	NPT
Hazardous Location Rating	Not Rated
Nominal Dial Size	4 in
Accuracy	+/-2.0%
Maximum Working Static Pressure	80 psig
Pressure Range	15 to 0 to 15 in wc
Series	2000 Magnehelic, Magnehelic
Sensor Material	Silicone Rubber
Pressure Gauge Type	Differential Pressure Gauge
Gauge Case Material	Aluminum
IP/NEMA Rating	IP67
Compatible Process Media	Cleanroom
Rated Total Pressure	-20 in Hg to 15 psi
Application	Clean Rooms, Fan Pressure Indication, Filtration Monitoring, Flow Measurement, HVAC/R, Vacuum Applications
Accuracy Details	+/-2% (-HA model +/-1) of FS, +/-3% (-HA +/-1.5%) on -0, -100PA, -125PA, -10MM, +/-4% (-HA +/-2%) on -00, -60PA, -6MM ranges throughout range at 70 Degrees F (21.1 Degrees C).
Adjustable Set Points	No
Ambient Operating Temperature Range	20 Degrees to 140 Degrees F
Bezel Material	Die Cast Aluminum
Bezel Mounting Type	Flush
Blowout Safety Back	Yes
Bolt Circle Diameter	4.125 in

Technical Specs Feedback

Case Color	Gray
Case Construction	Corrosion Resistant
Case Depth	1.687 in
Case Diameter	4.75 in
Case Finish	Die Cast
Case Shape	Round
Dial Color	White
Dial Face Material	Plastic
Housing Material	Die Cast Aluminum
Includes	Instructions, Three Mounting Adapters with Screws, Two 1/8 in NPT Plugs, Two 1/8 in NPT to 3/16 in ID Rubber Tubing Adapters
Includes Calibration Certificate	No
Includes Mounting Hardware	Yes
Includes Vent Plug	Yes
Manufacturer Warranty Length	5 yr
Mounting Hardware Included	Flange
Mounting Orientation	Upright Only
Mounting Type	Flush-Mount
Non-Sparking	No
Over-Pressure Limit	1.72 bar
Panel Mount Characteristics	3 L Dia Holes on E Dia Bolt Circle
Panel-Mountable	Yes
Pointer Characteristics	Red Tipped Pointer of Heat Treated Aluminum Tubing is easy to see
Pointer Material	Aluminum
Removable Bezel	No
Sensor Type	Diaphragm
Standards	EU Directive 2011/65/EU (RoHS II)

1 pc. - 1 3/4" long Square ends



<p>Detail of:</p> <p>Alum. Frame - Fan Box</p> <p>Free Standing Unit</p>	<p>Project Name & Location:</p>	<p>Contractor:</p> <p>OBAR Systems</p>	<p>Architect:</p>	<p>Architect's Drawing Reference:</p>
<p>PRECISION WELDING</p> <p>"Quality Metal Fabricators"</p> <p>845 Bankshire Valley Road Wharton, NJ 07885 (973) 214-1065 (973) 985-1308 eFax</p> <p></p> <p>www.precisionweld.com</p>				

DURA-BLOK™ Rooftop Supports



Our DURA-BLOK products gives you a versatile and long-term solution for all your roof top support needs. Designed with flexibility in mind, DURA-BLOK is ideal for roof top support applications such as pipe, HVAC, duct, conduit, cable tray, and roof walkways.

Manufactured to provide years of service in harsh, roof top environments, DURA-BLOK is made from 100% recycled rubber, require no supplemental rubber pads, and will not float or blow away. 1" (25.4) gaps between blocks allow water to flow freely around longer assemblies. For added strength, the DURA-BLOK support channel is through bolted on all sizes. For added visibility, a reflective strip is incorporated on both sides of each DURA-BLOK.

Beyond product durability, DURA-BLOK helps to dampen vibration, are not sharp or abrasive and require no roof penetration to maximize existing roof life - and roof structural and environmental integrity.

Recommended Torque (In channels)

Bolt Size	1/4"-20	5/16"-18	3/8"-16	1/2"-13
Foot/Lbs.	6	11	19	50
Nm	8	15	26	68

Bolt Size	M6x1	M8 x1.25	M10 x 1.5	M12x1.75
Nm	12	17	36	62
Foot/Lbs.	9	13	27	46

Materials & Finishes

See appropriate fitting pages.
Alternative finishes available upon request.

Metric

Metric dimensions are shown in parentheses.
Unless noted, all metric dimensions are in millimeters.

DURA-BLOK™ Rooftop Supports

Support Bases Only

- Base only - see chart for height, width and length.
- 100% recycled rubber, UV resistant.
- Load Rating - Ultimate Uniform Load (See Chart Below)*
- DURA-BLOK channel support is designed as an economical support for piping systems, cable tray, HVAC equipment and many other applications. The DURA-BLOK is UV resistant and suitable for any type of roofing material or other flat surfaces. Material effectively accepts screw fasteners for securing accessories.



Part No.	Height x Width x Length		Wt./Each		Load Rating	
	In.	mm	Lbs.	kg	Lbs.	kN
DBM	4" x 6" x 4.8"	(101.6 x 152.4 x 121.9)	2.35	(1.07)	200	(0.89)
DBP	4" x 6" x 9.6"	(101.6 x 152.4 x 243.8)	4.48	(2.03)	500	(2.22)

DB Series - Support Bases with B44 Channel

- Base with 14 ga. (1.9mm) galvanized channel 1" high (25.4mm) - see chart for height, width and length.
- 100% recycled rubber, UV resistant.
- Load Rating - Ultimate Uniform Load (See Chart Below)*
- DURA-BLOK DB-Series channel support is designed for superior support of piping systems, cable tray, HVAC equipment, walkway systems and many other applications. The DURA-BLOK is UV resistant and suitable for installation on any type of roofing material or other flat surfaces. (For pipe straps/clamps, rollers and roller supports that can be used with these DURA-BLOK supports, see page 159)
- For sloped roofs use B634 adjustable hinge fittings (see page 85).



Part No.	Height x Width x Length		Wt./Each		Load Rating	
	In.	mm	Lbs.	kg	Lbs.	kN
DB5	5" x 6" x 4.8"	(127.0 x 152.4 x 121.9)	2.75	(125)	200	(0.89)
DB10	5" x 6" x 9.6"	(127.0 x 152.4 x 243.8)	5.28	(2.39)	500	(2.22)
DB20	5" x 6" x 20.2"	(127.0 x 152.4 x 513.1)	10.63	(4.82)	1000	(4.45)
DB30	5" x 6" x 30.8"	(127.0 x 152.4 x 782.3)	15.99	(7.25)	1500	(6.67)
DB40	5" x 6" x 41.4"	(127.0 x 152.4 x 1051.5)	21.34	(9.68)	2000	(8.89)
DB48	5" x 6" x 52.0"	(127.0 x 152.4 x 1320.8)	26.70	(12.40)	2500	(11.12)

DB6 Series - Support Base with B12 Channel

- Base with 12 ga. (2.6mm) galvanized channel 27/16" high (61.9mm) - see chart for height, width and length.
- 100% recycled rubber, UV resistant.
- Load Rating - Ultimate Uniform Load (See Chart Below)*
- DURA-BLOK DB-Series channel support is designed for superior support of piping systems, cable tray, HVAC equipment, walkway systems and many other applications. The DURA-BLOK is UV resistant and suitable for installation on any type of roofing material or other flat surfaces. (For pipe straps/clamps, rollers and roller supports that can be used with these DURA-BLOK supports, see page 159)
- For sloped roofs use B634 adjustable hinge fittings (see page 85).



Part No.	Height x Width x Length		Wt./Each		Load Rating	
	In.	mm	Lbs.	kg	Lbs.	kN
DB610	67/16" x 6" x 9.6"	(163.5 x 152.4 x 243.8)	6.36	(2.88)	500	(2.22)
DB620	67/16" x 6" x 20.2"	(163.5 x 152.4 x 513.1)	12.90	(5.85)	1000	(4.45)
DB630	67/16" x 6" x 30.8"	(163.5 x 152.4 x 782.3)	19.45	(8.82)	1500	(6.67)
DB640	67/16" x 6" x 41.4"	(163.5 x 152.4 x 1051.5)	26.00	(11.79)	2000	(8.89)
DB648	67/16" x 6" x 52.0"	(163.5 x 152.4 x 1320.8)	32.55	(14.76)	2500	(11.12)

* **General Note:** Consult roofing manufacturer or engineer for roof load capacity.
The weakest point may be the insulation board beneath the rubber membrane.

Reference page 153 for general fitting and standard finish specifications.

DURA-BLOK™ Rooftop Supports

DB10 SERIES

Support Bases with B22 Channel

- Two (2) bases bridged with 12 ga. (2.6mm) galvanized channel 1⁵/₈" high (41.3mm) - see chart for height, width and length.
- 100% recycled rubber, UV resistant.
- Load Rating: 1000 lbs. (4.45kN) (Uniform Load)*
- DURA-BLOK DB10-Series channel support is designed for superior support of piping systems, cable tray, HVAC equipment, walkway systems and many other applications. The DURA-BLOK is UV resistant and suitable for installation on any type of roofing material or other flat surfaces. (For pipe straps/clamps, rollers and roller supports that can be used with these DURA-BLOK supports, see page 159)



DB10-36

Part No.	Height x Width x Length In. mm	Wt./Each Lbs. kg
DB10-28	5 ⁵ / ₈ " x 6" x 28" (142.9 x 152.4 x 711.2)	13.16 (5.97)
DB10-36	5 ⁵ / ₈ " x 6" x 36" (142.9 x 152.4 x 914.4)	14.36 (6.51)
DB10-42	5 ⁵ / ₈ " x 6" x 42" (142.9 x 152.4 x 1066.8)	15.52 (7.04)
DB10-50	5 ⁵ / ₈ " x 6" x 50" (142.9 x 152.4 x 1270.0)	16.45 (7.46)
DB10-60	5 ⁵ / ₈ " x 6" x 60" (142.9 x 152.4 x 1524.0)	17.94 (8.14)




DB10-50

DBM SERIES

Support Base with Riser Rod & Clamp

- Base with 3/8"-16 threaded rod and B3198H clamp - see chart for height, width and length
- 100% recycled rubber, UV resistant.
- Load Rating** 50 lbs. (0.22kN) (Ultimate Load)*
- DURA-BLOK DBM-Series pipe/tubing support is designed for support of single piping systems where elevation adjustment is needed. The DURA-BLOK is UV resistant and suitable for installation on any type of roofing material or other flat surfaces.



DBM-2CT

DBM-1

Part No.	Clamp Part No.†	Block -Height x Width x Length In. mm	Height** Min.-Max. In. mm	Wt./Each Lbs. kg
DBM-1/2CT	B3198HCT-1/2	4" x 6" x 4.8" (101.6 x 152.4 x 121.9)	9.69"-11.19" (246.1-284.2)	2.75 (1.25)
DBM-3/4CT	B3198HCT-3/4	4" x 6" x 4.8" (101.6 x 152.4 x 121.9)	9.84"-11.34" (249.9-2288.0)	2.76 (1.25)
DBM-1CT	B3198HCT-1	4" x 6" x 4.8" (101.6 x 152.4 x 121.9)	9.95"-11.45" (252.7-290.8)	2.84 (1.29)
DBM-1 ¹ / ₄ CT	B3198HCT-1 ¹ / ₄	4" x 6" x 4.8" (101.6 x 152.4 x 121.9)	10.13"-11.63" (257.3-295.4)	2.95 (1.34)
DBM-1 ¹ / ₂ CT	B3198HCT-1 ¹ / ₂	4" x 6" x 4.8" (101.6 x 152.4 x 121.9)	10.28"-11.78" (261.1-299.2)	2.96 (1.34)
DBM-2CT	B3198HCT-2	4" x 6" x 4.8" (101.6 x 152.4 x 121.9)	10.53"-12.03" (267.4-305.5)	3.03 (1.37)
DBM-1/2	B3198H-1/2	4" x 6" x 4.8" (101.6 x 152.4 x 121.9)	9.86"-11.36" (250.4-288.5)	2.78 (1.26)
DBM-3/4	B3198H-3/4	4" x 6" x 4.8" (101.6 x 152.4 x 121.9)	10.06"-11.56" (255.5-293.6)	2.84 (1.29)
DBM-1	B3198H-1	4" x 6" x 4.8" (101.6 x 152.4 x 121.9)	10.14"-11.64" (257.5-295.6)	2.86 (1.30)
DBM-1 ¹ / ₄	B3198H-1 ¹ / ₄	4" x 6" x 4.8" (101.6 x 152.4 x 121.9)	10.25"-11.75" (260.3-298.4)	2.93 (1.33)
DBM-1 ¹ / ₂	B3198H-1 ¹ / ₂	4" x 6" x 4.8" (101.6 x 152.4 x 121.9)	10.42"-11.92" (264.6-302.7)	2.99 (1.36)
DBM-2	B3198H-2	4" x 6" x 4.8" (101.6 x 152.4 x 121.9)	10.66"-12.16" (270.7-308.8)	3.10 (1.41)

† See Pipe Hanger Catalog for dimensions and specifications. ** From bottom of rubber block to center of pipe/tubing.

* **General Note:** Consult roofing manufacturer or engineer for roof load capacity.
The weakest point may be the insulation board beneath the rubber membrane.

Reference page 153 for general fitting and standard finish specifications.

DURA-BLOK™ Rooftop Supports

DBE Series Support Base with Rod Risers & Channel



- Base with (2) 1/2" electro zinc all threaded rod risers - Top channel is 1" (25.4mm) tall. See chart for adjustable height x wide x length.
- 100% recycled rubber, UV resistant.
- Load Rating* 200 lbs. (0.89kN) (To increase load capacity use load distribution plate CLDP10)
- DURA-BLOK DBE-Series channel support is designed as a superior support of piping systems, cable tray, HVAC equipment and many other applications where elevation adjustment is critical. The DURA-BLOK is UV resistant and suitable for installation on any type of roofing material or other flat surfaces. (For pipe straps/clamps, rollers and roller supports that can be used with these DURA-BLOK supports, see page 159)



Part No.	Adjustable Height x Width x Length In. mm	Wt./Each Lbs. kg
DBE10-8	5 1/2-8" x 6" x 9.6" (139.7-152.4 x 152.4 x 243.8)	5.68 (2.58)
DBE10-12	5 1/2-12" x 6" x 9.6" (139.7-304.8 x 152.4 x 243.8)	5.72 (2.59)
DBE10-16	5 1/2-16" x 6" x 9.6" (139.7-406.4 x 152.4 x 243.8)	5.76 (2.61)

DBR Series Support Base with Rod Risers & Pipe Roll



- Base with (2) 1/2" electro zinc all threaded rod risers and a B3114-3 1/2 pipe roll with sockets - base is 4" (101.6mm) high x 6" (152.4mm) wide x 9.6" (243.8mm) long. Overall height is 12" (304.8mm) from bottom of base to contact point on roller.
- Pipe roll & sockets for up to 3 1/2" (90) pipe sizes.
- 100% recycled rubber, UV resistant.
- Load Rating* 200 lbs. (0.89kN) (To increase load capacity use load distribution plate CLDP10)
- DURA-BLOK DBR-Series support is designed to support pipe up to 3 1/2" (90) nominal size where difference in elevation is required and longitudinal movement is expected. The DURA-BLOK is UV resistant and approved for installation on any type of roofing material or other flat surfaces.




Part No.	Adjustable Height x Width x Length In. mm	Wt./Each Lbs. kg
DBR10-12	up to 12" x 6" x 9.6" (up to 304.8 x 152.4 x 243.8)	8.20 (3.72)

CLDP10 Load Distribution Plate

- 11 ga. (3.0mm) steel plate with slots.
- Dimensions: 15 5/8" (41.3mm) wide x 9 1/2" (241.3mm) long.
- DURA-BLOK CLDP10 load bearing stabilizer plate increases load ratings for DBE Series and DBR Series by allowing the load from the threaded rods to be distributed over the length of the base instead of the point load where the rods attach to the base.

Part No.	Thickness x Width x Length In. mm	Wt./Each Lbs. kg
CLDP10	11 Ga. x 15 5/8" x 9 1/2" (3.0 x 41.3 x 241.3)	0.53 (0.24)



Loosen hex nuts and slide plate under the flat washers

Retighten the hex nuts with plate in place




* **General Note:** Consult roofing manufacturer or engineer for roof load capacity. The weakest point may be the insulation board beneath the rubber membrane.

Reference page 153 for general fitting and standard finish specifications.

DURA-BLOK™ Rooftop Supports

DB_DS Series Support Bases with B22SH Vertical & Horizontal Channel Members

- Product is shipped unassembled.
- Two (2) DB20 bases with 14 ga. (1.9mm) galvanized channel 1" high (25.4mm) - Bases are 5" (127.0mm) high x 6" (152.4mm) wide x 20.2" (513.1mm) long. Vertical & Horizontal Riser Channels (SH Style) - 1⁵/₈" (41.3mm) x 1⁵/₈" (41.3mm) x 12 ga. (2.6mm) Fittings & Hardware - Electro-Plated Steel
- 100% recycled rubber, UV resistant.
- Ultimate Load Rating: 1000 lbs. (4.45kN) (Uniform Load)*
- DURA-BLOK DB_DS-Series channel support with risers is designed for superior support of piping systems, cable tray, HVAC equipment, walkway systems and many other applications. The DURA-BLOK is UV resistant and suitable for installation on any type of roofing material or other flat surfaces. (For pipe straps/clamps, rollers and roller supports that can be used with these DURA-BLOK supports, see page 159)



* **General Note:** Consult roofing manufacturer or engineer for roof load capacity.
The weakest point may be the insulation board beneath the rubber membrane.

Reference page 153 for general fitting and standard finish specifications.

DURA-BLOK™ Rooftop Supports

DB_DS Series cont.

Part No.	A Min. to Max.		B	
	In.	mm	In.	mm
DB2318DS	10.56"	to 20.75"	(268 to 527)	13 ¹ / ₂ " (343)
DB2918DS	10.56"	to 26.75"	(268 to 679)	13 ¹ / ₂ " (343)
DB4118DS	10.56"	to 38.75"	(268 to 984)	13 ¹ / ₂ " (343)
DB5318DS	10.56"	to 50.75"	(268 to 1289)	13 ¹ / ₂ " (343)
DB2324DS	10.56"	to 20.75"	(268 to 527)	19 ¹ / ₂ " (495)
DB2924DS	10.56"	to 26.75"	(268 to 679)	19 ¹ / ₂ " (495)
DB4124DS	10.56"	to 38.75"	(268 to 984)	19 ¹ / ₂ " (495)
DB5324DS	10.56"	to 50.75"	(268 to 1289)	19 ¹ / ₂ " (495)
DB2336DS	10.56"	to 20.75"	(268 to 527)	31 ¹ / ₂ " (800)
DB2936DS	10.56"	to 26.75"	(268 to 679)	31 ¹ / ₂ " (800)
DB4136DS	10.56"	to 38.75"	(268 to 984)	31 ¹ / ₂ " (800)
DB5336DS	10.56"	to 50.75"	(268 to 1289)	31 ¹ / ₂ " (800)
DB2348DS	10.56"	to 20.75"	(268 to 527)	43 ¹ / ₂ " (1105)
DB2948DS	10.56"	to 26.75"	(268 to 679)	43 ¹ / ₂ " (1105)
DB4148DS	10.56"	to 38.75"	(268 to 984)	43 ¹ / ₂ " (1105)
DB5348DS	10.56"	to 50.75"	(268 to 1289)	43 ¹ / ₂ " (1105)

Part No.	Height (overall)		Width (overall)		Length (overall)		Wt./Each	
	In.	mm	In.	mm	In.	mm	lbs.	kg
DB2318DS	23"	(584)	25 ⁵ / ₈ "	(651)	20.2"	(513)	33.31	(15.11)
DB2918DS	29"	(736)	25 ⁵ / ₈ "	(651)	20.2"	(513)	35.00	(15.88)
DB4118DS	41"	(1041)	25 ⁵ / ₈ "	(651)	20.2"	(513)	38.40	(17.42)
DB5318DS	53"	(1346)	25 ⁵ / ₈ "	(651)	20.2"	(513)	41.80	(18.96)
DB2324DS	23"	(584)	31 ⁵ / ₈ "	(803)	20.2"	(513)	34.15	(15.49)
DB2924DS	29"	(736)	31 ⁵ / ₈ "	(803)	20.2"	(513)	35.84	(16.26)
DB4124DS	41"	(1041)	31 ⁵ / ₈ "	(803)	20.2"	(513)	39.25	(17.80)
DB5324DS	53"	(1346)	31 ⁵ / ₈ "	(803)	20.2"	(513)	42.65	(19.34)
DB2336DS	23"	(584)	43 ⁵ / ₈ "	(1108)	20.2"	(513)	35.84	(16.26)
DB2936DS	29"	(736)	43 ⁵ / ₈ "	(1108)	20.2"	(513)	37.56	(17.03)
DB4136DS	41"	(1041)	43 ⁵ / ₈ "	(1108)	20.2"	(513)	40.95	(18.57)
DB5336DS	53"	(1346)	43 ⁵ / ₈ "	(1108)	20.2"	(513)	44.34	(20.11)
DB2348DS	23"	(584)	55 ⁵ / ₈ "	(1415)	20.2"	(513)	37.55	(17.03)
DB2948DS	29"	(736)	55 ⁵ / ₈ "	(1415)	20.2"	(513)	39.25	(17.80)
DB4148DS	41"	(1041)	55 ⁵ / ₈ "	(1415)	20.2"	(513)	42.65	(19.34)
DB5348DS	53"	(1346)	55 ⁵ / ₈ "	(1415)	20.2"	(513)	46.03	(20.88)

A = Adjustable height from bottom of DURA-BLOK to top of horizontal channel.
 B = Space between fittings that support horizontal channel.
 Height (overall) = Distance from bottom of DURA-BLOK to top of upright channel.
 Width (overall) = Distance from outside-to-outside of DURA-BLOK supports.
 Length (overall) = Distance from end-to-end of DURA-BLOK supports.

Reference page 153 for general fitting and standard finish specifications.

DURA-BLOK™ Rooftop Supports

DBR Series Support Bases with B42 Channel & Pipe Roller

- Base with 14 ga. (1.9mm) galvanized channel 1" high (25.4mm) tall - see chart for height, width and length.
- 100% recycled rubber, UV resistant.
- Load Rating: (See Chart Below)*
- DURA-BLOK DBR-Series support is designed to support pipe where longitudinal movement is expected. The DURA-BLOK is UV resistant and approved for installation on any type of roofing material or other flat surfaces.



DBR4-6




DBR16-20

Part No.	Roller Part No.†	Block & Channel -Height x Width x Length In. mm	Height** In. mm	Wt./Each		Load Rating	
				Lbs.	kg	Lbs.	kN
DBR2-3 1/2	B3126-2 to 3 1/2	5" x 6" x 9.6" (127.0 x 152.4 x 243.8)	7.09" (180)	5.28	(2.39)	500	(2.22)
DBR4-6	B3126-4 to 6	5" x 6" x 9.6" (127.0 x 152.4 x 243.8)	7.09" (180)	10.63	(4.82)	500	(2.22)
DBR8-10	B3126-8-10	5" x 6" x 20.2" (127.0 x 152.4 x 513.1)	8.34" (212)	15.99	(7.25)	1000	(4.45)
DBR12-14	B3126-12-14	5" x 6" x 20.2" (127.0 x 152.4 x 513.1)	9.38" (238)	21.34	(9.68)	1000	(4.45)
DBR16-20	B3126-16-20	5" x 6" x 20.2" (127.0 x 152.4 x 513.1)	9.78" (248)	26.70	(12.11)	1000	(4.45)

† See Pipe Hanger Catalog for dimensions and specifications. ** From bottom of rubber block to bottom of pipe/tubing.

Compatible Components Available to make DURA-BLOK bases more versatile



Above rollers can be mounted on DB Series, DB6 Series, and DB10 Series units.

Reference page 153 for general fitting and standard finish specifications.

DURA-BLOK™ Rooftop Supports

Rooftop Applications




DURA-BLOK™ Rooftop Supports

Rooftop Supports In Walkway Applications



- Safety Grating is available with slip resistant GRATE-LOCK™, helping provide a safe walkway for foot traffic on the roof.
- Easy to install, elevated design, creates an identifiable path for foot traffic helping prevent wear and tear to the roof surface.
- The cross-over design offers safe passage over existing cabling, piping, cable tray or any other interference on the rooftop.
- The self cleaning pattern allows water and dirt to easily flow through, helping make the grating an ideal walkway in all weather conditions.
- Handrail options are available



[illegible]

DURA-BLOK Supports

PARKER

Ball Valve, Polypropylene, Inline, 2-Piece, Pipe Size 3/8 in, Tube Size 1/4 in

Item # 5UMX8

UNSPSC # 40142613

Mfr. Model # LFPP4VMC6

Catalog Page # N/A

Country of Origin USA. Country of Origin is subject to change.

This ball valve features polypropylene construction. Polypropylene is a durable and flexible thermoplastic polymer. Polypropylene valves are often lightweight and easy to install, and are also resistant to corrosion.

☐ Compare this product



Roll over image to zoom.

 Product Image Feedback

Technical Specs

Item	Ball Valve
Body Material	Polypropylene
Body Style	Inline
General Connection Type	Male NPT
Valve Structure	2-Piece
Pipe Size	3/8 in
Tube Size	1/4 in
Connection Type	MNPT x Push
Port	Full
Max. Pressure	150 psi CWP
Temp. Range	35 Degrees to 200 Degrees F
Ball Material	Polysulfone

Seat Material	EPDM
Stem Type	1-Piece Stem
Handle Type	Lever
Handle Material	Nylon
Stem Material	Polysulfone
Body Seal Material	EPDM
Features	Self-Cleaning
Ball Valve Product Group	Manual
Valve Basic Body Material	Plastic
Standards	FDA and RoHS Compliant, NSF-51 and 61 Certified
Overall Length	2.4 in

APPENDIX B
COMMUNITY AIR MONITORING PLAN

Community Air Monitoring Plan

Job Name/Site Number: 65 Albany Avenue, Kingston NY /356060

Revision #1

1.0 INTRODUCTION

This Community Air Monitoring Plan (CAMP) has been prepared by Bellucci Engineering to support the implementation of the Interim Remedial Measure (IRM) activity associated with the Sub-Slab Depressurization System or SSDS installation at the Subject Property located at 65 Albany Avenue in Kingston, Ulster County, New York. A Site Plan is provided as Figure 1. Details related to this IRM activity is presented in the SSDS Design Document, Bellucci Engineering, PLLC dated July 2022, to which this CAMP is included as an attachment and as a supporting plan. This CAMP fulfills the routine monitoring requirements provided in the New York State Department of Environmental Conservation (NYSDEC) document entitled Division of Environmental Remediation *Technical Guidance for Site Investigation and Remediation* (DER-10) issued on May 3, 2010. Appendix 1A of DER-10 provides general guidance and protocols for the preparation and implementation of a CAMP. Appendix 1B of DER-10 supplements the contents of Appendix 1A of DER-10 and provides additional requirements for fugitive dust/particulate monitoring. Special requirements have also been deemed necessary by the NYSDEC and New York State Department of Health (NYSDOH) as work will be conducted within 20 feet of potentially exposed individuals or structures. A copy of these CAMP requirements (as outlined in DER-10) has been placed in Attachment A for reference. This CAMP identifies the required air monitoring to protect on-Site workers and the community during the implementation of proposed investigative activities. Note that all IRM remedial activities will be performed inside the Site structure during times when the tenanted spaces are unoccupied.

1.1 CAMP Objectives

The overall objective of the CAMP is to establish requirements for protection measures from potential airborne releases of constituents of concern during intrusive and/or potential dust generating Site activities. As summarized in the SSDS Design Document, laboratory analysis indicates that constituents of concern at the Site include volatile organic compounds (VOCs). This CAMP identifies potential air emissions, and describes air monitoring procedures, the monitoring schedule, data collection, and reporting requirements for the mitigation actions to be completed by the environmental team. Bellucci Engineering and DT Consulting Services, Inc. will implement this CAMP and will provide all labor, materials, and equipment necessary to implement the monitoring program specified in this CAMP, as well as any required contractor worker documentation and monitoring described in the Environmental Health and Safety Plan prepared for the implementation of the

project.

1.2 Revisions to the CAMP

Any changes to the scope or procedures in this CAMP will be formally documented as a revision to this document. A revision number will be indicated on the front page of any revised document and will serve as a historical record of any and all revisions made to the document. For changes requiring immediate resolution during the implementation of this CAMP, approval will be secured from the NYSDEC and, if applicable, the Responsible Party.

1.3 Potential Air Emissions Related to Remedial Activities

Intrusive Sub-Slab Depressurization (SSDS) remedial activities have the potential to generate localized impacts to air quality. Remedial construction components that are considered intrusive for the purposes of this CAMP and that have the potential to generate air emissions are anticipated to include, but may not be limited to the following:

- ✓ Installation of SSDS;
- ✓ Installation and pilot testing of additional extraction wells, vacuum monitoring points ;
- ✓ Soil vapor/soil gas sampling.

2.0 AIR QUALITY MONITORING AND ACTION LEVELS

Air monitoring will be conducted in accordance with a CAMP and is designed to protect the community and the onsite workers.

2.1 Monitoring During Site Operations

Prior to commencement of planned remedial activities the following will be conducted:

- Background readings will be obtained with a photoionization detector (PID) for VOCs in parts per million (ppm). Any unusual background readings will be discussed with NYSDEC/NYSDOH prior to commencement of work;

As deemed necessary, the use of engineering controls including but not limited to special ventilation, the employment of granular activated carbon (GAC) to polish soil vapor extracted during pilot testing procedures prior to external atmospheric discharge, and vapor/dust barriers will be utilized during the performance of the SSDS installation(s).

During Site work involving disturbance of fill and/or native soil, real time air monitoring will be conducted for VOCs. A PID will be used to monitor concentrations of VOCs at personnel breathing-zone height. Dust/particulate monitoring will be accomplished with an aerosol monitor. Air monitoring will be the responsibility of the HSO or designee. Air monitoring will be conducted continuously during ground intrusive activities in the work zone on the project Site. All manufacturers' instructions for instrumentation and calibration will be available on-Site.

2.1.1 Volatile Organic Compounds

Monitoring with a PID, such as a MiniRAE 2000 (10.6v) or equivalent will occur continuously during the execution of the IRM work plan. Colormetric Indicator Tubes for tetrachloroethylene (i.e Draeger® tubes) may be used as backup for the PID, if measurements remain above background monitor every 2 hours. Instrumentation action levels to be utilized are as follows:

Action Levels for Organic Vapors

Instrument	Action Level	Action Required
Outdoor Action Levels		
PID	Background to 5 ppm	No further action required.
	> 5 ppm for > 5 minutes	1. Temporarily discontinue all activities and evaluate potential causes of the excessive readings. If these levels persist and cannot be mitigated (i.e., by slowing drilling or excavation activities), contact HSO to review conditions and determine source and appropriate response action. 2. If PID readings remain above 5 ppm, temporarily discontinue work. 3. If sustained PID readings fall below 1 ppm, no

		further action required.
	> 5 ppm but < 150 ppm for > 5 minutes	1. Discontinue all work; all workers shall move outside of the work zone. 2. Evaluate potential causes of the excessive readings and allow work area to vent until VOC concentrations fall below 5 ppm.
	> 30 ppm (steady state condition) within work zone	Stop Work / Suppress Emissions / Evacuate and re-evaluate.
	> 150 ppm	Evacuate the work zone
Special Requirements for Work Within 20 Feet of Potentially Exposure Individuals or Structures		
	> 1 ppm above background. Opposite the walls of occupied structures or next to intake vents. Collect background readings within adjacent occupied spaces prior to commencement of planned work.	Monitoring will be performed within the occupied (tenanted) space, the nearest potentially exposed individuals and in the location of ventilation intakes for nearby structures. Response actions may include but are not limited to: <ol style="list-style-type: none"> 1. Cessation of onsite work until source of VOCs is determined; 2. Use of engineering control (i.e. exhaust fan(s), vapor barriers) within exclusion zone; 3. Deployment of Air Purifying Units

In accordance with the Special Requirements for Work Withing 20-feet of Potentially Exposed Individuals or Structures, all ground intrusive and piping work conducted within will be during off business hour when the tenants are not present. Non-intrusive work such as system diagnostic testing and sampling may be conducted during business hours while the spaces are occupied. These activities do not result in fugitive dust or VOC emissions to indoor air.

Notes:

1. 1 ppm level based on OSHA Permissible Exposure Limit (PEL) for benzene.
2. 5 ppm level based on OSHA Short Term Exposure Limit (STEL) maximum exposure for vinyl chloride for any 15 minute period.
3. 150 ppm level based on NIOSH Immediately Dangerous to Life and Health (IDLH) for tetrachloroethylene.

2.1.2 Fugitive Dust and Particulate Monitoring

During invasive procedures which have the potential for creating airborne dust,

such as excavation of dry soils, a real time airborne dust monitor such as a Mini-Ram must be used to monitor for air particulates. The particulate monitoring will be performed using real-time monitoring equipment capable of measuring particulate matter less than 10 micrometers in size (PM-10) and will be equipped with an audible alarm to indicate exceedance of the action level. In addition, fugitive dust migration should be visually assessed during all work activities. The HSO will continuously monitor for particulates during all ground intrusive activities. Instrument action levels to be utilized for dust monitoring are as follows:

Action Levels for Particulates

Instrument	Action Level	Level of Protection/Action Required
Outdoor Action Levels		
Total Dust Aerosol Monitor	> 0.100 mg/m ³ above BKD (steady state condition) at work zone for 15-minutes or visible dust.	Stop Work/Implement dust control. Continue dust monitoring if dust levels are less than 150 mg/m ³ .
	< 0.150 mg/m ³ above BKD (following dust suppression measures).	Stop Work/implement dust control, continue work once levels are <150 mg/m ³ .
Special Requirements for Work Within 20 Feet of Potentially Exposure Individuals or Structures		
	> 0.150 mg/m ³ Opposite the walls of occupied structures or next to intake vents.	Work activities will be suspended until controls are implemented and are successful in reducing the total particulate concentration to 0.150 mg/m ³ or less at the monitoring point.

2.2 Periodic Monitoring for Odors

During work hours, hourly or more frequent walks around the perimeter of the work area will be performed to qualitatively monitor for the presence and intensity of Site-related odors. Perimeter checks will be performed more

frequently, as necessary, depending on the nature and location of work being performed. If odors are noted at the perimeter of the work area, work will continue and odor, vapor, and dust controls will be employed to abate emissions. Additionally, construction techniques will be evaluated and modified, if necessary and appropriate, and more frequent checks of the perimeter of the work area will be performed. If odors persist at the perimeter of the work area at an unacceptable intensity, work will be stopped while activities are re-evaluated. The source or cause of the odors will be identified and additional odor, vapor, and dust controls will be employed. Work will resume provided that the controls are successful in mitigating the intensity of odors at the perimeter of the work area.

2.3 Instrument Calibration

Calibration of the VOC and PM-10, instrumentation will be conducted in accordance with each of the equipment manufacturer's calibration and quality assurance requirements. The VOC and PM-10 monitoring equipment will be calibrated or zeroed, respectively, daily (at a minimum), and such calibrations will be recorded in the field logbook.

3.0 MONITORING SCHEDULE/DATA COLLECTION/REPORTING

The following identifies the monitoring schedule and data collection/reporting requirements.

3.1 Monitoring Schedule

Air monitoring will be conducted prior to initiating remedial Site activities to establish adequate baseline data and until such time that intrusive and/or potential dust generating activities are complete. The frequency of construction air monitoring will be relative to the level of Site work activities being conducted and may be adjusted as the work proceeds and in consideration of the monitoring results. VOC and particulate monitoring will be conducted continuously during all ground-intrusive work.

3.2 Data Collection and Reporting

Results of the air monitoring for total organic vapors and particulates (both instantaneous readings and 15-minute average concentrations) will be

recorded by the on-Site HSO or designee. Upon executing the approved IRM, a CAMP report will be generated to include, but not be limited to, the following:


- A brief memorandum summarizing the air monitoring work activities and results for the monitoring period. A summary of the qualitative monitoring for the presence and intensity of Site-related odors will also be included.

In the event that an exceedance of an air monitoring action level (for either VOCs or PM-10), the HSO or designee will notify DEC (via telephone) as soon as possible (i.e., real time). Within 24 hours of the observed exceedance, the HSO or designee will send a follow-up e-mail to DEC's representative, and the Responsible Party summarizing the data, the cause of the exceedance, and any corrective measures implemented (or to be implemented) as a result of the exceedance. The information will also be documented in the CAMP report. Odor complaints received from the public will be evaluated and verified based on the following:

- Date and time of complaint;
- Location and nature of work activities being performed at the Site;
- Location and nature of non-project-related work activities being performed in the surrounding community; and
- Prevailing wind direction and other local meteorological conditions.

Regardless of the outcome of this evaluation, all associated parties will be notified of odor complaints within 24 hours. In response to a verified odor complaint, perimeter monitoring will continue and additional odor, vapor, and dust controls will be employed to mitigate Site-related odor emissions. Construction techniques will also be evaluated and modified, if necessary and appropriate.

FIGURES



Bellucci Engineering PLLC

Client: MMJD Equities LLC

Location: 65 Albany Avenue, Kingston, Ulster County, New York

Title: SSDS Installation - Plan View

Scale: Graphic

Base Map By: D.T.

Site #: 356060

P.E. Certification/ Seal

Figure 1

DT CONSULTING SERVICES, INC.

ATTACHMENTS

DT CONSULTING SERVICES, INC.

ATTACHMENT A

**NYSDEC DER-10 TECHNICAL GUIDANCE FOR SITE INVESTIGATION
AND REMEDIATION (DER-10) MAY 3, 2010.**

APPENDIX 1A OF DER-10

Appendix 1A

New York State Department of Health Generic Community Air Monitoring Plan

Overview

A Community Air Monitoring Plan (CAMP) requires real-time monitoring for volatile organic compounds (VOCs) and particulates (i.e., dust) at the downwind perimeter of each designated work area when certain activities are in progress at contaminated sites. The CAMP is not intended for use in establishing action levels for worker respiratory protection. Rather, its intent is to provide a measure of protection for the downwind community (i.e., off-site receptors including residences and businesses and on-site workers not directly involved with the subject work activities) from potential airborne contaminant releases as a direct result of investigative and remedial work activities. The action levels specified herein require increased monitoring, corrective actions to abate emissions, and/or work shutdown. Additionally, the CAMP helps to confirm that work activities did not spread contamination off-site through the air.

The generic CAMP presented below will be sufficient to cover many, if not most, sites. Specific requirements should be reviewed for each situation in consultation with NYSDOH to ensure proper applicability. In some cases, a separate site-specific CAMP or supplement may be required. Depending upon the nature of contamination, chemical- specific monitoring with appropriately-sensitive methods may be required. Depending upon the proximity of potentially exposed individuals, more stringent monitoring or response levels than those presented below may be required. Special requirements will be necessary for work within 20 feet of potentially exposed individuals or structures and for indoor work with co-located residences or facilities. These requirements should be determined in consultation with NYSDOH.

Reliance on the CAMP should not preclude simple, common-sense measures to keep VOCs, dust, and odors at a minimum around the work areas.

Community Air Monitoring Plan

Depending upon the nature of known or potential contaminants at each site, real-time air monitoring for VOCs and/or particulate levels at the perimeter of the exclusion zone or work area will be necessary. Most sites will involve VOC and particulate monitoring; sites known to be contaminated with heavy metals alone may only require particulate monitoring. If radiological contamination is a concern, additional monitoring requirements may be necessary per consultation with appropriate DEC/NYSDOH staff.

Continuous monitoring will be required for all ground intrusive activities and during the demolition of contaminated or potentially contaminated structures. Ground intrusive activities include, but are not limited to, soil/waste excavation and handling, test pitting or trenching, and the installation of soil borings or monitoring wells.

Periodic monitoring for VOCs will be required during non-intrusive activities such as the collection of soil and sediment samples or the collection of groundwater samples from existing monitoring wells. "Periodic" monitoring during sample collection might reasonably consist of taking a reading upon arrival at a sample location, monitoring while opening a well cap or

overturning soil, monitoring during well baling/purging, and taking a reading prior to leaving a sample location. In some instances, depending upon the proximity of potentially exposed individuals, continuous monitoring may be required during sampling activities. Examples of such situations include groundwater sampling at wells on the curb of a busy urban street, in the midst of a public park, or adjacent to a school or residence.

VOC Monitoring, Response Levels, and Actions

Volatile organic compounds (VOCs) must be monitored at the downwind perimeter of the immediate work area (i.e., the exclusion zone) on a continuous basis or as otherwise specified. Upwind concentrations should be measured at the start of each workday and periodically thereafter to establish background conditions, particularly if wind direction changes. The monitoring work should be performed using equipment appropriate to measure the types of contaminants known or suspected to be present. The equipment should be calibrated at least daily for the contaminant(s) of concern or for an appropriate surrogate. The equipment should be capable of calculating 15-minute running average concentrations, which will be compared to the levels specified below.

1. If the ambient air concentration of total organic vapors at the downwind perimeter of the work area or exclusion zone exceeds 5 parts per million (ppm) above background for the 15-minute average, work activities must be temporarily halted and monitoring continued. If the total organic vapor level readily decreases (per instantaneous readings) below 5 ppm over background, work activities can resume with continued monitoring.
2. If total organic vapor levels at the downwind perimeter of the work area or exclusion zone persist at levels in excess of 5 ppm over background but less than 25 ppm, work activities must be halted, the source of vapors identified, corrective actions taken to abate emissions, and monitoring continued. After these steps, work activities can resume provided that the total organic vapor level 200 feet downwind of the exclusion zone or half the distance to the nearest potential receptor or residential/commercial structure, whichever is less - but in no case less than 20 feet, is below 5 ppm over background for the 15-minute average.
3. If the organic vapor level is above 25 ppm at the perimeter of the work area, activities must be shutdown.
4. All 15-minute readings must be recorded and be available for State (DEC and NYSDOH) personnel to review. Instantaneous readings, if any, used for decision purposes should also be recorded.

Particulate Monitoring, Response Levels, and Actions

Particulate concentrations should be monitored continuously at the upwind and downwind perimeters of the exclusion zone at temporary particulate monitoring stations. The particulate monitoring should be performed using real-time monitoring equipment capable of measuring particulate matter less than 10 micrometers in size (PM-10) and capable of integrating over a period of 15 minutes (or less) for comparison to the airborne particulate action level. The equipment must be equipped with an audible alarm to indicate exceedance of the action level. In addition, fugitive dust migration should be visually assessed during all work activities.

1. If the downwind PM-10 particulate level is 100 micrograms per cubic meter (mcg/m^3) greater than background (upwind perimeter) for the 15-minute period or if airborne dust is observed leaving the work area, then dust suppression techniques must be employed. Work may continue with dust suppression techniques provided that downwind PM-10 particulate levels do not exceed $150 \text{ mcg}/\text{m}^3$ above the upwind level and provided that no visible dust is migrating from the work area.

2. If, after implementation of dust suppression techniques, downwind PM-10 particulate levels are greater than $150 \text{ mcg}/\text{m}^3$ above the upwind level, work must be stopped and a re-evaluation of activities initiated. Work can resume provided that dust suppression measures and other controls are successful in reducing the downwind PM-10 particulate concentration to within $150 \text{ mcg}/\text{m}^3$ of the upwind level and in preventing visible dust migration.

3. All readings must be recorded and be available for State (DEC and NYSDOH) and County Health personnel to review.

December 2009

APPENDIX 1B OF DER-10

Appendix 1B

Fugitive Dust and Particulate Monitoring

A program for suppressing fugitive dust and particulate matter monitoring at hazardous waste sites is a responsibility on the remedial party performing the work. These procedures must be incorporated into appropriate intrusive work plans. The following fugitive dust suppression and particulate monitoring program should be employed at sites during construction and other intrusive activities which warrant its use:

1. Reasonable fugitive dust suppression techniques must be employed during all site activities which may generate fugitive dust.
2. Particulate monitoring must be employed during the handling of waste or contaminated soil or when activities on site may generate fugitive dust from exposed waste or contaminated soil. Remedial activities may also include the excavation, grading, or placement of clean fill. These control measures should not be considered necessary for these activities.
3. Particulate monitoring must be performed using real-time particulate monitors and shall monitor particulate matter less than ten microns (PM₁₀) with the following minimum performance standards:
 - (a) Objects to be measured: Dust, mists or aerosols;
 - (b) Measurement Ranges: 0.001 to 400 mg/m³ (1 to 400,000 :ug/m³);
 - (c) Precision (2-sigma) at constant temperature: +/- 10 :g/m³ for one second averaging; and +/- 1.5 g/m³ for sixty second averaging;
 - (d) Accuracy: +/- 5% of reading +/- precision (Referred to gravimetric calibration with SAE fine test dust (mmd= 2 to 3 :m, g= 2.5, as aerosolized);
 - (e) Resolution: 0.1% of reading or 1g/m³, whichever is larger;
 - (f) Particle Size Range of Maximum Response: 0.1-10;
 - (g) Total Number of Data Points in Memory: 10,000;
 - (h) Logged Data: Each data point with average concentration, time/date and data point number
 - (i) Run Summary: overall average, maximum concentrations, time/date of maximum, total number of logged points, start time/date, total elapsed time (run duration), STEL concentration and time/date occurrence, averaging (logging) period, calibration factor, and tag number;
 - (j) Alarm Averaging Time (user selectable): real-time (1-60 seconds) or STEL (15 minutes), alarms required;
 - (k) Operating Time: 48 hours (fully charged NiCd battery); continuously with charger;
 - (l) Operating Temperature: -10 to 50° C (14 to 122° F);
 - (m) Particulate levels will be monitored upwind and immediately downwind at the working site and integrated over a period not to exceed 15 minutes.
4. In order to ensure the validity of the fugitive dust measurements performed, there must be appropriate Quality Assurance/Quality Control (QA/QC). It is the responsibility of the remedial party to adequately supplement QA/QC Plans to include the following critical features: periodic instrument calibration, operator training, daily instrument performance (span) checks, and a record keeping plan.
5. The action level will be established at 150 ug/m³ (15 minutes average). While conservative,

this short-term interval will provide a real-time assessment of on-site air quality to assure both health and safety. If particulate levels are detected in excess of 150 ug/m³, the upwind background level must be confirmed immediately. If the working site particulate measurement is greater than 100 ug/m³ above the background level, additional dust suppression techniques must be implemented to reduce the generation of fugitive dust and corrective action taken to protect site personnel and reduce the potential for contaminant migration. Corrective measures may include increasing the level of personal protection for on-site personnel and implementing additional dust suppression techniques (see paragraph 7). Should the action level of 150 ug/m³ continue to be exceeded work must stop and DER must be notified as provided in the site design or remedial work plan. The notification shall include a description of the control measures implemented to prevent further exceedances.

6. It must be recognized that the generation of dust from waste or contaminated soil that migrates off-site, has the potential for transporting contaminants off-site. There may be situations when dust is being generated and leaving the site and the monitoring equipment does not measure PM₁₀ at or above the action level. Since this situation has the potential to allow for the migration of contaminants off-site, it is unacceptable. While it is not practical to quantify total suspended particulates on a real-time basis, it is appropriate to rely on visual observation. If dust is observed leaving the working site, additional dust suppression techniques must be employed. Activities that have a high dusting potential--such as solidification and treatment involving materials like kiln dust and lime--will require the need for special measures to be considered.

7. The following techniques have been shown to be effective for the controlling of the generation and migration of dust during construction activities:

- (a) Applying water on haul roads;
- (b) Wetting equipment and excavation faces;
- (c) Spraying water on buckets during excavation and dumping;
- (d) Hauling materials in properly tarped or watertight containers;
- (e) Restricting vehicle speeds to 10 mph;
- (f) Covering excavated areas and material after excavation activity ceases; and
- (g) Reducing the excavation size and/or number of excavations.

Experience has shown that the chance of exceeding the 150ug/m³ action level is remote when the above-mentioned techniques are used. When techniques involving water application are used, care must be taken not to use excess water, which can result in unacceptably wet conditions. Using atomizing sprays will prevent overly wet conditions, conserve water, and provide an effective means of suppressing the fugitive dust.

8. The evaluation of weather conditions is necessary for proper fugitive dust control. When extreme wind conditions make dust control ineffective, as a last resort remedial actions may need to be suspended. There may be situations that require fugitive dust suppression and particulate monitoring requirements with action levels more stringent than those provided above. Under some circumstances, the contaminant concentration and/or toxicity may require additional monitoring to protect site personnel and the public. Additional integrated sampling and chemical analysis of the dust may also be in order. This must be evaluated when a health and safety plan is developed and when appropriate suppression and monitoring requirements are established for protection of health and the environment.

Special Requirements for Work Within 20 Feet of Potentially Exposed Individuals or Structures

When work areas are within 20 feet of potentially exposed populations or occupied structures, the continuous monitoring locations for VOCs and particulates must reflect the nearest potentially exposed individuals and the location of ventilation system intakes for nearby structures. The use of engineering controls such as vapor/dust barriers, temporary negative-pressure enclosures, or special ventilation devices should be considered to prevent exposures related to the work activities and to control dust and odors. Consideration should be given to implementing the planned activities when potentially exposed populations are at a minimum, such as during weekends or evening hours in non-residential settings.

- If total VOC concentrations opposite the walls of occupied structures or next to intake vents exceed 1 ppm, monitoring should occur within the occupied structure(s). Depending upon the nature of contamination, chemical-specific colorimetric tubes of sufficient sensitivity may be necessary for comparing the exposure point concentrations with appropriate pre-determined response levels (response actions should also be pre-determined). Background readings in the occupied spaces must be taken prior to commencement of the planned work. Any unusual background readings should be discussed with NYSDOH prior to commencement of the work.
- If total particulate concentrations opposite the walls of occupied structures or next to intake vents exceed 150 mcg/m³, work activities should be suspended until controls are implemented and are successful in reducing the total particulate concentration to 150 mcg/m³ or less at the monitoring point.
- Depending upon the nature of contamination and remedial activities, other parameters (e.g., explosivity, oxygen, hydrogen sulfide, carbon monoxide) may also need to be monitored. Response levels and actions should be pre-determined, as necessary, for each site.

Special Requirements for Indoor Work With Co-Located Residences or Facilities

Unless a self-contained, negative-pressure enclosure with proper emission controls will encompass the work area, all individuals not directly involved with the planned work must be absent from the room in which the work will occur. Monitoring requirements shall be as stated above under “Special Requirements for Work Within 20 Feet of Potentially Exposed Individuals or Structures” except that in this instance “nearby/occupied structures” would be adjacent occupied rooms. Additionally, the location of all exhaust vents in the room and their discharge points, as well as potential vapor pathways (openings, conduits, etc.) relative to adjoining rooms, should be understood and the monitoring locations established accordingly. In these situations, it is strongly recommended that exhaust fans or other engineering controls be used to create negative air pressure within the work area during remedial activities. Additionally, it is strongly recommended that the planned work be implemented during hours (e.g. weekends or evenings) when building occupancy is at a minimum.

APPENDIX C
HEALTH & SAFETY PLAN

Environmental Services Health & Safety Plan

Job Name: 65 Albany Avenue, Kingston, New York
Site #: 356060

DT CONSULTING SERVICES, INC

1.0 Introduction

2.0 Organizational Structure

2.1 Safety and Health Manager

2.2 Site Safety and Health Office

2.2.1 Responsibilities

3.0 Personal Protective Equipment

3.1 Protection Levels

3.1.1 Level A

3.1.2 Level B

3.1.3 Level C

3.1.4 Level D

4.0 Work Zones

4.1 Exclusion Zone

4.2 Contamination Reduction Zone

4.3 Support Zone

5.0 Air Monitoring

6.0 Site Communications

7.0 Emergency Procedures

7.1 Injury in the exclusion zone

7.2 Injury in the support zone

7.3 Fire or explosion

7.4 Protective equipment failure

8.0 Standard Safety Practices

9.0 Daily Safety Meetings

10.0 Site Specific Plan

10.1 Detailed Site information

10.2 Contaminants on Site/Action Levels

10.3 Emergency Information

10.3.1 Emergency Responders

10.3.1.1 Hospital

10.3.1.2 Emergency telephone numbers

DT CONSULTING SERVICES, INC

- 10.3.1.3 Regulatory agencies
- 10.4 First Aid
- 10.5 Work Zones
 - 10.5.1 Command post
- 10.6 Site Communications
 - 10.6.1 Telephone
 - 10.6.2 Hand Signals
- 10.7 Environmental Monitoring
- 10.8 Personal Protective Equipment
 - 10.8.1 Exclusion zone
 - 10.8.2 Contamination reduction corridor
- 10.9 Decontamination
 - 10.9.1 Decontamination Procedure
- 11.0 Key Personnel
- 12.0 Work Plan
 - 12.1 Job objective / Detailed work plan

DT CONSULTING SERVICES, INC

1.0 INTRODUCTION

DT Consulting Services, Inc. (DTCS) has designed a safety and health program to provide its employees and subcontractors with the guidelines necessary to ensure their own safety and health as well as that of the surrounding community. The goal of this plan is to minimize the risk of injury during the installation of the proposed Sub-slab Depressurization Systems (SSDSs) on-Site.

2.0 ORGANIZATIONAL STRUCTURE

2.1 SAFETY AND HEALTH MANAGER

It is the responsibility of the safety and health manager to develop the comprehensive safety and health plan. The safety and health manager will be appraised of any changes in the comprehensive safety and health plan as well as all Site-specific procedural determinations. The safety and health manager for this project will be Ms. Deborah Thompson.

2.1.1 RESPONSIBILITIES

- a) Initial Site evaluation
- b) Hazard identification
- c) Determination of appropriate protection levels
- d) Conduct daily safety and health meetings
- e) Supervision of Site sampling and monitoring
- f) Supervision of decontamination procedures
- g) Designate work zones to maintain Site integrity

3.0 PERSONAL PROTECTIVE EQUIPMENT

The proper personal protective equipment is chosen by the Site safety and health officer in consultation with the safety and health manager. The level of protection is dependent on the hazards that are likely to be encountered on-Site.

3.1 PROTECTION LEVELS

DTCS utilizes four levels of protection as set forth in the OSHA guidelines, Appendix B of 1910.120.

3.1.1 Level A

Level A provides the greatest level of skin, respiratory, and eye protection with the following minimum equipment:

- Full face, self-contained breathing apparatus (SCBA) or supplied air with escape SCBA
- Fully encapsulated chemical resistant suit
- Chemical resistant boots
- Chemical resistant inner and outer gloves

3.1.2 Level B

Level B provides the greatest level of respiratory protection, but a lower level of skin protection than Level A with the following minimum equipment:

- Full face SCBA or supplied air with escape SCBA
- Chemical resistant clothing
- Chemical resistant inner and out gloves
- Chemical resistant boots

3.1.3 Level C

Level C provides the same level of skin protection as Level B, but a lower level of respiratory protection with the following minimum equipment:

- Full face piece air purifying respirator with appropriate cartridge. Cartridges are chosen based on knowledge of hazardous material
- Chemical resistant clothing
- Chemical resistant inner and outer gloves
- Chemical resistant boots

3.1.4 Level D

Level D provides the lowest level of skin protection and no respiratory protection with the following minimum equipment:

- Coveralls
- Safety boots
- Gloves
- Safety glasses or splash goggles

4.0 WORK ZONES

DTCS utilizes the standard three-zone approach to Site control. These zones are the exclusion zone, the contamination reduction zone and the support zone. Movement of personnel and equipment through these zones shall be strictly regulated in order to prevent contamination of clean environments and to protect workers in the support zone from possible exposure.

4.1 EXCLUSION ZONE

The exclusion zone is the area of highest contamination. All personnel entering this zone must wear the appropriate level of protection as prescribed in the Site specific safety plan. The outer boundary of the exclusion zone, referred to as the Hotline, shall be determined based upon such considerations as; extent of surface contamination, safe distance in the case of fire or explosion, physical area necessary for workers to conduct operations in a safe manner and safe distance in the event of vapor or gas emissions. Upon determination, the Hotline shall be visibly marked and secured to prevent accidental entry by unauthorized personnel.

4.2 CONTAMINATION REDUCTION ZONE

The Contamination Reduction Zone is the area between the exclusion zone and the support zone. Its purpose is to protect the clean environment from contamination as workers enter and exit the exclusion zone. The outer boundary of this zone is referred to as the Coldline and shall be clearly marked. Decontamination stations shall be set up in this zone in a line known as the contamination reduction corridor. All personnel exiting the exclusion zone must follow the steps as prescribed in the decontamination procedures prior to re-entering the support zone.

4.3 SUPPORT ZONE

The support zone is the area furthest away from the exclusion zone. It is considered a clean, non-contaminated area where workers need not wear any protective equipment. The command post, equipment trailer, first aid station and lavatory facilities are all located in this area. This area is not, however, open to traffic. Only authorized personnel may enter.

5.0 AIR MONITORING

As the initial Site evaluation work plan entails minimal Site intrusive activities, specific air monitoring procedures would include only the periodic recording of total volatile organic compound or VOC concentrations with a Photoionization Detector (PID) or equivalent during Site activities.

6.0 SITE COMMUNICATIONS

Various methods of communication will be employed based upon Site conditions and work zones. Regardless of method of communication, personnel working in the exclusion zone will remain within constant view of support crews.

DTCS has a network of devices to aid in communications. All or some of the following devices may be used depending upon job Site requirements; hand held radios, headset transistor walkie-talkies and cellular telephones.

The following hand signals shall be standardized for use in emergencies and in event of radio communication breakdown.

Hand gripping throat - out of air, can't breathe
Grip partner's wrist - leave area immediately
Hands on top of head - need assistance
Thumbs up - I am all right, okay
Thumbs down - no, negative

Horn blasts may be used to gain the immediate attention of crews to indicate that dangerous conditions exist.

7.0 EMERGENCY PROCEDURES

The following procedures shall be followed by all Site personnel in the event of an emergency. Any changes to this procedure shall be noted in the Site-specific plan. In all situations where there has been an evacuation of exclusion zone, reentry shall not be permitted until the following conditions have been met; the cause of the emergency has been determined and corrected, the Site hazards have been reassessed, the safety plan has been reviewed and all personnel have been apprised of any changes.

7.1 INJURY IN THE EXCLUSION ZONE

In the event of an injury in the exclusion zone, the emergency signal shall be sounded. All personnel in the exclusion zone will assemble at the contamination reduction corridor. First aid procedures will begin on-Site and if necessary, an ambulance will be called. No personnel will be allowed to re-enter the exclusion zone until the exact nature and cause of the injury has been determined.

7.2 INJURY IN THE SUPPORT ZONE

In the event of an injury in the support zone, on-Site first aid procedures will begin immediately and an ambulance called if necessary. The Site safety and health officer shall determine if the nature and cause of the injury or loss of the injured person will jeopardize the smooth running of the operations. If so, the emergency signal will be sounded and all personnel will follow the same procedure as outline above.

7.3 FIRE OR EXPLOSION

In the event of fire or explosion, the emergency signal shall be sounded and all personnel will assemble at the contamination reduction corridor. The fire department will be called and all personnel will be evacuated to a safe distance.

7.4 PROTECTIVE EQUIPMENT FAILURE

In the event of protective equipment failure, the affected worker and his/her buddy will leave the exclusion zone immediately. In the event of any other equipment failure, the Site safety and health officer will determine if this failure affects the operation. If so, the emergency signal will be sounded and all personnel will leave the exclusion zone until such time as it is deemed safe.

8.0 STANDARD SAFETY PRACTICES

The following guidelines will be followed by all personnel at all times; any changes must be approved by the safety and health manager.

- All employees will attend the daily safety meetings prior to Site entry.

DT CONSULTING SERVICES, INC

- The buddy system will be utilized at all times.
- There will be no eating, drinking, smoking, or use of smoking material (i.e. matches) within the work area(s).
- Only authorized personnel will be allowed in designated work zones and will wear the proper personal protective clothing and equipment as prescribed in the Site safety plan.
- The Site safety and health officer will be appraised of any unusual circumstances immediately.

Such circumstances include but are not limited to the following; unusual odors, emissions, signs of chemical reaction, and discovery of conditions or substances not mentioned in the Site safety plan. The Site safety officer will then determine if these conditions warrant a shut down of operations.

9.0 DAILY SAFETY MEETINGS

Daily safety meetings will be conducted by the Site safety and health officer prior to commencement of work. All personnel, regardless of job classification are required to attend.

9.1 DISCUSSIONS

1. Overview of safety and health plan.
2. Detailed discussion of substances of concern with emphasis on exposure limits, exposure symptoms and exposure hazards.
3. Review of standard safety precautions and work practices.
4. Review of work plan.
5. Review of hand signals and emergency signals.

Personnel will sign a daily attendance sheet, which shall include an overview of the topics discussed.

10.0 SITE SPECIFIC PLAN

DT CONSULTING SERVICES, INC

10.1 DETAILED SITE INFORMATION

- **Plan Date** TBA
- **Job Name** 65 Albany Avenue
- **Client** MMJD Equities LLC
- **Client Contact** Joseph Douek
- **Site Address** 65 Albany Avenue
Kingston, New York 12401
- **Cross Street** Maiden Lane
- **Site Access** Direct

10.2 CONTAMINANTS ON SITE/ACTION LEVELS

The following substances are known or suspected to be on Site, primarily in Site wastes. The primary hazards of each are identified, associated primarily with direct skin contact and inhalation.

SUBSTANCE	PRIMARY HAZARDS
<i>Volatile Organics</i>	
Trichloroethene (TCE) Tetrachloroethene (PCE)	Eye, skin and respiratory irritation. Nausea, vomiting, headache
Cis-1,2-Dichloroethylene	Skin irritation, gastrointestinal or respiratory tract irritation.
Methylene chloride	Acute affects - central nervous system, or neurotoxicity

Action Levels

Action levels shall be determined by monitoring of work zone breathing space with a portable Photoionization detector (PID) or comparable instrument. Measurement of a sustained concentration above ambient (background) conditions shall initiate action. The following criteria shall be used to determine appropriate action:

VOCs in Breathing Zone (sustained and above	Level of Respiratory Protection
--	------------------------------------

DT CONSULTING SERVICES, INC

background)	
0 – 5 ppm	Level D
5 – 200 ppm	Level C
200 – 1000 ppm	Level B - air line
1000+ ppm	Level B - SCBA

If the above criteria indicate the need to increase from Level D to a higher level of personal protection, all work in that particular Site area will be immediately suspended until the required protective equipment is made available, or until Level D conditions return.

10.3 EMERGENCY INFORMATION

10.3.1 EMERGENCY RESPONDERS

10.3.1.1 HOSPITAL

Name: Kingston Hospital

Address & Telephone Number:

396 Broadway, Kingston, NY 12401
(845) 331-3131

Distance from Site: 0.5 Miles

10.3.1.2 EMERGENCY TELEPHONE NUMBERS

Police	<u>911 on Cellular Phone</u>
Fire	<u>911 on Cellular Phone</u>
Ambulance	<u>911 on Cellular Phone</u>

10.3.1.3 REGULATORY AGENCIES

EPA Telephone Number 1-800-424-8802

NYSDEC Spills Hotline 1-800-457-7362

DT CONSULTING SERVICES, INC

10.4 FIRST AID

First Aid available at the following stations:

First Aid Kit TRUCK

Emergency Eye Wash TRUCK & ON SITE

10.5 WORK ZONES

10.5.1 COMMAND POST

Command post will be mobile.

10.6 SITE COMMUNICATIONS

10.6.1 TELEPHONE

Command Post Telephone - Cellular Phone
Number (845)943-0159

10.6.2 HAND SIGNALS

See Section 6.0

10.7 ENVIRONMENTAL MONITORING

10.7.1 MONITORING EQUIPMENT

Refer to RI Work Plan

10.8 PERSONAL PROTECTIVE EQUIPMENT

10.8.1 EXCLUSION ZONE, PROTECTION LEVEL

PROTECTIVE EQUIPMENT:	Level D
RESPIRATORY	None
HANDS	Nitrile or Leather
FEET	Steel Toed Boots
SUIT	None

**10.8.2 CONTAMINATION REDUCTION
CORRIDOR (DECON LINE)**

PROTECTIVE EQUIPMENT:	Level D
RESPIRATORY	None
HANDS	Nitrile or Leather
FEET	Steel Toed
SUIT	None

10.9 DECONTAMINATION

10.9.1 DECONTAMINATION PROCEDURE

STATION 1 SOAPY WATER

STATION 2 WATER

11.0 KEY PERSONNEL

SAFETY AND HEALTH MANAGER / ON-SITE SUPERVISOR

Deborah J. Thompson

FOREMEN

TBA

FIELD PERSONNEL


Will Vary

12.0 WORK PLAN

12.1 JOB OBJECTIVE

The objective is to execute the SSDS Design Document prepared for the Site by Bellucci Engineering, PLLC dated July 2022. Upon completion of field work, a Construction Completion Report or CCR will be prepared and submitted to NYSDEC and NYSDOH following installation and startup of the SSDS. The report will include a summary of the first month of testing, operation and maintenance. The CCR will include a description of the SSDS as constructed, modifications to the system design, the data collected, and record drawings.

APPENDIX D
PILOT TEST LABORATORY ANALYTICAL REPORTS



Technical Report

prepared for:

DT Consulting Services
1291 Old Post Road
Ulster Park NY, 12487
Attention: Deborah Thompson

Report Date: 04/18/2022

Client Project ID: 356060 65 Albany Avenue Kingston, New York
York Project (SDG) No.: 22D0083

CT Cert. No. PH-0723

New Jersey Cert. No. CT005 and NY037



New York Cert. Nos. 10854 and 12058

PA Cert. No. 68-04440

120 RESEARCH DRIVE
www.YORKLAB.com

STRATFORD, CT 06615
(203) 325-1371

132-02 89th AVENUE
FAX (203) 357-0166

RICHMOND HILL, NY 11418
ClientServices@yorklab.com

Report Date: 04/18/2022
Client Project ID: 356060 65 Albany Avenue Kingston, New York
York Project (SDG) No.: 22D0083

DT Consulting Services
1291 Old Post Road
Ulster Park NY, 12487
Attention: Deborah Thompson

Purpose and Results

This report contains the analytical data for the sample(s) identified on the attached chain-of-custody received in our laboratory on April 04, 2022 and listed below. The project was identified as your project: **356060 65 Albany Avenue Kingston, New York**.

The analyses were conducted utilizing appropriate EPA, Standard Methods, and ASTM methods as detailed in the data summary tables.

All samples were received in proper condition meeting the customary acceptance requirements for environmental samples except those indicated under the Sample and Analysis Qualifiers section of this report.

All analyses met the method and laboratory standard operating procedure requirements except as indicated by any data flags, the meaning of which are explained in the Sample and Data Qualifiers Relating to This Work Order section of this report and case narrative if applicable.

The results of the analyses, which are all reported on dry weight basis (soils) unless otherwise noted, are detailed in the following pages.

Please contact Client Services at 203.325.1371 with any questions regarding this report.

<u>York Sample ID</u>	<u>Client Sample ID</u>	<u>Matrix</u>	<u>Date Collected</u>	<u>Date Received</u>
22D0083-01	EW-1	Soil Vapor	04/03/2022	04/04/2022
22D0083-02	EW-2	Soil Vapor	04/03/2022	04/04/2022
22D0083-03	EW-3	Soil Vapor	04/03/2022	04/04/2022
22D0083-04	EW-4	Soil Vapor	04/03/2022	04/04/2022
22D0083-05	EW-5	Soil Vapor	04/03/2022	04/04/2022

General Notes for York Project (SDG) No.: 22D0083

1. The RLs and MDLs (Reporting Limit and Method Detection Limit respectively) reported are adjusted for any dilution necessary due to the levels of target and/or non-target analytes and matrix interference. The RL(REPORTING LIMIT) is based upon the lowest standard utilized for the calibration where applicable.
2. Samples are retained for a period of thirty days after submittal of report, unless other arrangements are made.
3. York's liability for the above data is limited to the dollar value paid to York for the referenced project.
4. This report shall not be reproduced without the written approval of York Analytical Laboratories, Inc.
5. All analyses conducted met method or Laboratory SOP requirements. See the Sample and Data Qualifiers Section for further information.
6. It is noted that no analyses reported herein were subcontracted to another laboratory, unless noted in the report.
7. This report reflects results that relate only to the samples submitted on the attached chain-of-custody form(s) received by York.
8. Analyses conducted at York Analytical Laboratories, Inc. Stratford, CT are indicated by NY Cert. No. 10854; those conducted at York Analytical Laboratories, Inc., Richmond Hill, NY are indicated by NY Cert. No. 12058.

Approved By: 

Date: 04/18/2022

Cassie L. Mosher
Laboratory Manager





Sample Information

Client Sample ID: EW-1

York Sample ID: 22D0083-01

York Project (SDG) No.

Client Project ID

Matrix

Collection Date/Time

Date Received

22D0083

356060 65 Albany Avenue Kingston, New York

Soil Vapor

April 3, 2022 10:23 am

04/04/2022

Volatile Organics, EPA TO15 Full List

Log-in Notes:

Sample Notes:

Sample Prepared by Method: EPA TO15 PREP

CAS No.	Parameter	Result	Flag	Units	Reported to LOQ	Dilution	Reference Method	Date/Time Prepared	Date/Time Analyzed	Analyst
630-20-6	* 1,1,1,2-Tetrachloroethane	ND		ug/m ³	2.3	3.328	EPA TO-15 Certifications:	04/17/2022 02:00	04/17/2022 11:56	LLJ
71-55-6	1,1,1-Trichloroethane	ND		ug/m ³	1.8	3.328	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 11:56	LLJ
79-34-5	1,1,2,2-Tetrachloroethane	ND		ug/m ³	2.3	3.328	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 11:56	LLJ
76-13-1	1,1,2-Trichloro-1,2,2-trifluoroethane (Freon 113)	ND		ug/m ³	2.6	3.328	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 11:56	LLJ
79-00-5	1,1,2-Trichloroethane	ND		ug/m ³	1.8	3.328	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 11:56	LLJ
75-34-3	1,1-Dichloroethane	ND		ug/m ³	1.3	3.328	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 11:56	LLJ
75-35-4	1,1-Dichloroethylene	ND		ug/m ³	0.33	3.328	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 11:56	LLJ
120-82-1	1,2,4-Trichlorobenzene	ND		ug/m ³	2.5	3.328	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 11:56	LLJ
95-63-6	1,2,4-Trimethylbenzene	ND		ug/m ³	1.6	3.328	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 11:56	LLJ
106-93-4	1,2-Dibromoethane	ND		ug/m ³	2.6	3.328	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 11:56	LLJ
95-50-1	1,2-Dichlorobenzene	ND		ug/m ³	2.0	3.328	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 11:56	LLJ
107-06-2	1,2-Dichloroethane	ND		ug/m ³	1.3	3.328	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 11:56	LLJ
78-87-5	1,2-Dichloropropane	ND		ug/m ³	1.5	3.328	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 11:56	LLJ
76-14-2	1,2-Dichlorotetrafluoroethane	ND		ug/m ³	2.3	3.328	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 11:56	LLJ
108-67-8	1,3,5-Trimethylbenzene	ND		ug/m ³	1.6	3.328	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 11:56	LLJ
106-99-0	1,3-Butadiene	ND		ug/m ³	2.2	3.328	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 11:56	LLJ
541-73-1	1,3-Dichlorobenzene	ND		ug/m ³	2.0	3.328	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 11:56	LLJ
142-28-9	* 1,3-Dichloropropane	ND		ug/m ³	1.5	3.328	EPA TO-15 Certifications:	04/17/2022 02:00	04/17/2022 11:56	LLJ
106-46-7	1,4-Dichlorobenzene	ND		ug/m ³	2.0	3.328	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 11:56	LLJ
123-91-1	1,4-Dioxane	ND		ug/m ³	2.4	3.328	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 11:56	LLJ
78-93-3	2-Butanone	1.4		ug/m ³	0.98	3.328	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 11:56	LLJ
591-78-6	* 2-Hexanone	ND		ug/m ³	2.7	3.328	EPA TO-15 Certifications:	04/17/2022 02:00	04/17/2022 11:56	LLJ



Sample Information

Client Sample ID: EW-1

York Sample ID: 22D0083-01

York Project (SDG) No.

Client Project ID

Matrix

Collection Date/Time

Date Received

22D0083

356060 65 Albany Avenue Kingston, New York

Soil Vapor

April 3, 2022 10:23 am

04/04/2022

Volatile Organics, EPA TO15 Full List

Log-in Notes:

Sample Notes:

Sample Prepared by Method: EPA TO15 PREP

CAS No.	Parameter	Result	Flag	Units	Reported to LOQ	Dilution	Reference Method	Date/Time Prepared	Date/Time Analyzed	Analyst
107-05-1	3-Chloropropene	ND		ug/m ³	5.2	3.328	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 11:56	LLJ
108-10-1	4-Methyl-2-pentanone	ND		ug/m ³	1.4	3.328	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 11:56	LLJ
67-64-1	Acetone	10		ug/m ³	1.6	3.328	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 11:56	LLJ
107-13-1	Acrylonitrile	ND		ug/m ³	0.72	3.328	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 11:56	LLJ
71-43-2	Benzene	ND		ug/m ³	1.1	3.328	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 11:56	LLJ
100-44-7	Benzyl chloride	ND		ug/m ³	1.7	3.328	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 11:56	LLJ
75-27-4	Bromodichloromethane	ND		ug/m ³	2.2	3.328	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 11:56	LLJ
75-25-2	Bromoform	ND		ug/m ³	3.4	3.328	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 11:56	LLJ
74-83-9	Bromomethane	ND		ug/m ³	1.3	3.328	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 11:56	LLJ
75-15-0	Carbon disulfide	ND		ug/m ³	1.0	3.328	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 11:56	LLJ
56-23-5	Carbon tetrachloride	ND		ug/m ³	0.52	3.328	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 11:56	LLJ
108-90-7	Chlorobenzene	ND		ug/m ³	1.5	3.328	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 11:56	LLJ
75-00-3	Chloroethane	ND		ug/m ³	0.88	3.328	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 11:56	LLJ
67-66-3	Chloroform	10		ug/m ³	1.6	3.328	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 11:56	LLJ
74-87-3	Chloromethane	ND		ug/m ³	0.69	3.328	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 11:56	LLJ
156-59-2	cis-1,2-Dichloroethylene	ND		ug/m ³	0.33	3.328	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 11:56	LLJ
10061-01-5	cis-1,3-Dichloropropylene	ND		ug/m ³	1.5	3.328	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 11:56	LLJ
110-82-7	Cyclohexane	ND		ug/m ³	1.1	3.328	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 11:56	LLJ
124-48-1	Dibromochloromethane	ND		ug/m ³	2.8	3.328	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 11:56	LLJ
75-71-8	Dichlorodifluoromethane	340		ug/m ³	1.6	3.328	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 11:56	LLJ
141-78-6	* Ethyl acetate	ND		ug/m ³	2.4	3.328	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 11:56	LLJ
100-41-4	Ethyl Benzene	ND		ug/m ³	1.4	3.328	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 11:56	LLJ
87-68-3	Hexachlorobutadiene	ND		ug/m ³	3.5	3.328	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 11:56	LLJ



Sample Information

Client Sample ID: EW-1

York Sample ID: 22D0083-01

York Project (SDG) No.

Client Project ID

Matrix

Collection Date/Time

Date Received

22D0083

356060 65 Albany Avenue Kingston, New York

Soil Vapor

April 3, 2022 10:23 am

04/04/2022

Volatile Organics, EPA TO15 Full List

Log-in Notes:

Sample Notes:

Sample Prepared by Method: EPA TO15 PREP

CAS No.	Parameter	Result	Flag	Units	Reported to LOQ	Dilution	Reference Method	Date/Time Prepared	Date/Time Analyzed	Analyst
67-63-0	Isopropanol	ND		ug/m ³	1.6	3.328	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 11:56	LLJ
80-62-6	Methyl Methacrylate	ND		ug/m ³	1.4	3.328	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 11:56	LLJ
1634-04-4	Methyl tert-butyl ether (MTBE)	ND		ug/m ³	1.2	3.328	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 11:56	LLJ
75-09-2	Methylene chloride	11		ug/m ³	2.3	3.328	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 11:56	LLJ
142-82-5	n-Heptane	ND		ug/m ³	1.4	3.328	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 11:56	LLJ
110-54-3	n-Hexane	ND		ug/m ³	1.2	3.328	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 11:56	LLJ
95-47-6	o-Xylene	ND		ug/m ³	1.4	3.328	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 11:56	LLJ
179601-23-1	p- & m- Xylenes	2.9		ug/m ³	2.9	3.328	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 11:56	LLJ
622-96-8	* p-Ethyltoluene	ND		ug/m ³	1.6	3.328	EPA TO-15 Certifications:	04/17/2022 02:00	04/17/2022 11:56	LLJ
115-07-1	* Propylene	ND		ug/m ³	0.57	3.328	EPA TO-15 Certifications:	04/17/2022 02:00	04/17/2022 11:56	LLJ
100-42-5	Styrene	ND		ug/m ³	1.4	3.328	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 11:56	LLJ
127-18-4	Tetrachloroethylene	1000		ug/m ³	2.3	3.328	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 11:56	LLJ
109-99-9	* Tetrahydrofuran	8.0		ug/m ³	2.0	3.328	EPA TO-15 Certifications:	04/17/2022 02:00	04/17/2022 11:56	LLJ
108-88-3	Toluene	ND		ug/m ³	1.3	3.328	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 11:56	LLJ
156-60-5	trans-1,2-Dichloroethylene	ND		ug/m ³	1.3	3.328	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 11:56	LLJ
10061-02-6	trans-1,3-Dichloropropylene	ND		ug/m ³	1.5	3.328	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 11:56	LLJ
79-01-6	Trichloroethylene	ND		ug/m ³	0.45	3.328	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 11:56	LLJ
75-69-4	Trichlorofluoromethane (Freon 11)	3.9		ug/m ³	1.9	3.328	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 11:56	LLJ
108-05-4	Vinyl acetate	ND		ug/m ³	1.2	3.328	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 11:56	LLJ
593-60-2	Vinyl bromide	ND		ug/m ³	1.5	3.328	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 11:56	LLJ
75-01-4	Vinyl Chloride	ND		ug/m ³	0.43	3.328	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 11:56	LLJ



Sample Information

Client Sample ID: EW-2

York Sample ID: 22D0083-02

York Project (SDG) No.

Client Project ID

Matrix

Collection Date/Time

Date Received

22D0083

356060 65 Albany Avenue Kingston, New York

Soil Vapor

April 3, 2022 11:40 am

04/04/2022

Volatile Organics, EPA TO15 Full List

Log-in Notes:

Sample Notes:

Sample Prepared by Method: EPA TO15 PREP

CAS No.	Parameter	Result	Flag	Units	Reported to LOQ	Dilution	Reference Method	Date/Time Prepared	Date/Time Analyzed	Analyst
630-20-6	* 1,1,1,2-Tetrachloroethane	ND		ug/m ³	11	16.7	EPA TO-15 Certifications:	04/15/2022 09:00	04/16/2022 08:48	LLJ
71-55-6	1,1,1-Trichloroethane	ND		ug/m ³	9.1	16.7	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/15/2022 09:00	04/16/2022 08:48	LLJ
79-34-5	1,1,2,2-Tetrachloroethane	ND		ug/m ³	11	16.7	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/15/2022 09:00	04/16/2022 08:48	LLJ
76-13-1	1,1,2-Trichloro-1,2,2-trifluoroethane (Freon 113)	ND		ug/m ³	13	16.7	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/15/2022 09:00	04/16/2022 08:48	LLJ
79-00-5	1,1,2-Trichloroethane	ND		ug/m ³	9.1	16.7	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/15/2022 09:00	04/16/2022 08:48	LLJ
75-34-3	1,1-Dichloroethane	ND		ug/m ³	6.8	16.7	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/15/2022 09:00	04/16/2022 08:48	LLJ
75-35-4	1,1-Dichloroethylene	ND		ug/m ³	1.7	16.7	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/15/2022 09:00	04/16/2022 08:48	LLJ
120-82-1	1,2,4-Trichlorobenzene	ND		ug/m ³	12	16.7	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/15/2022 09:00	04/16/2022 08:48	LLJ
95-63-6	1,2,4-Trimethylbenzene	ND		ug/m ³	8.2	16.7	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/15/2022 09:00	04/16/2022 08:48	LLJ
106-93-4	1,2-Dibromoethane	ND		ug/m ³	13	16.7	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/15/2022 09:00	04/16/2022 08:48	LLJ
95-50-1	1,2-Dichlorobenzene	ND		ug/m ³	10	16.7	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/15/2022 09:00	04/16/2022 08:48	LLJ
107-06-2	1,2-Dichloroethane	ND		ug/m ³	6.8	16.7	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/15/2022 09:00	04/16/2022 08:48	LLJ
78-87-5	1,2-Dichloropropane	ND		ug/m ³	7.7	16.7	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/15/2022 09:00	04/16/2022 08:48	LLJ
76-14-2	1,2-Dichlorotetrafluoroethane	ND		ug/m ³	12	16.7	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/15/2022 09:00	04/16/2022 08:48	LLJ
108-67-8	1,3,5-Trimethylbenzene	ND		ug/m ³	8.2	16.7	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/15/2022 09:00	04/16/2022 08:48	LLJ
106-99-0	1,3-Butadiene	ND		ug/m ³	11	16.7	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/15/2022 09:00	04/16/2022 08:48	LLJ
541-73-1	1,3-Dichlorobenzene	ND		ug/m ³	10	16.7	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/15/2022 09:00	04/16/2022 08:48	LLJ
142-28-9	* 1,3-Dichloropropane	ND		ug/m ³	7.7	16.7	EPA TO-15 Certifications:	04/15/2022 09:00	04/16/2022 08:48	LLJ
106-46-7	1,4-Dichlorobenzene	ND		ug/m ³	10	16.7	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/15/2022 09:00	04/16/2022 08:48	LLJ
123-91-1	1,4-Dioxane	ND		ug/m ³	12	16.7	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/15/2022 09:00	04/16/2022 08:48	LLJ
78-93-3	2-Butanone	ND		ug/m ³	4.9	16.7	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/15/2022 09:00	04/16/2022 08:48	LLJ
591-78-6	* 2-Hexanone	ND		ug/m ³	14	16.7	EPA TO-15 Certifications:	04/15/2022 09:00	04/16/2022 08:48	LLJ
107-05-1	3-Chloropropene	ND		ug/m ³	26	16.7	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/15/2022 09:00	04/16/2022 08:48	LLJ



Sample Information

Client Sample ID: EW-2

York Sample ID: 22D0083-02

York Project (SDG) No.

Client Project ID

Matrix

Collection Date/Time

Date Received

22D0083

356060 65 Albany Avenue Kingston, New York

Soil Vapor

April 3, 2022 11:40 am

04/04/2022

Volatile Organics, EPA TO15 Full List

Log-in Notes:

Sample Notes:

Sample Prepared by Method: EPA TO15 PREP

CAS No.	Parameter	Result	Flag	Units	Reported to LOQ	Dilution	Reference Method	Date/Time Prepared	Date/Time Analyzed	Analyst
108-10-1	4-Methyl-2-pentanone	ND		ug/m ³	6.8	16.7	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/15/2022 09:00	04/16/2022 08:48	LLJ
67-64-1	Acetone	17		ug/m ³	7.9	16.7	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/15/2022 09:00	04/16/2022 08:48	LLJ
107-13-1	Acrylonitrile	ND		ug/m ³	3.6	16.7	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/15/2022 09:00	04/16/2022 08:48	LLJ
71-43-2	Benzene	ND		ug/m ³	5.3	16.7	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/15/2022 09:00	04/16/2022 08:48	LLJ
100-44-7	Benzyl chloride	ND		ug/m ³	8.6	16.7	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/15/2022 09:00	04/16/2022 08:48	LLJ
75-27-4	Bromodichloromethane	ND		ug/m ³	11	16.7	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/15/2022 09:00	04/16/2022 08:48	LLJ
75-25-2	Bromoform	ND		ug/m ³	17	16.7	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/15/2022 09:00	04/16/2022 08:48	LLJ
74-83-9	Bromomethane	ND		ug/m ³	6.5	16.7	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/15/2022 09:00	04/16/2022 08:48	LLJ
75-15-0	Carbon disulfide	ND		ug/m ³	5.2	16.7	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/15/2022 09:00	04/16/2022 08:48	LLJ
56-23-5	Carbon tetrachloride	ND		ug/m ³	2.6	16.7	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/15/2022 09:00	04/16/2022 08:48	LLJ
108-90-7	Chlorobenzene	ND		ug/m ³	7.7	16.7	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/15/2022 09:00	04/16/2022 08:48	LLJ
75-00-3	Chloroethane	ND		ug/m ³	4.4	16.7	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/15/2022 09:00	04/16/2022 08:48	LLJ
67-66-3	Chloroform	ND		ug/m ³	8.2	16.7	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/15/2022 09:00	04/16/2022 08:48	LLJ
74-87-3	Chloromethane	ND		ug/m ³	3.4	16.7	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/15/2022 09:00	04/16/2022 08:48	LLJ
156-59-2	cis-1,2-Dichloroethylene	ND		ug/m ³	1.7	16.7	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/15/2022 09:00	04/16/2022 08:48	LLJ
10061-01-5	cis-1,3-Dichloropropylene	ND		ug/m ³	7.6	16.7	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/15/2022 09:00	04/16/2022 08:48	LLJ
110-82-7	Cyclohexane	ND		ug/m ³	5.7	16.7	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/15/2022 09:00	04/16/2022 08:48	LLJ
124-48-1	Dibromochloromethane	ND		ug/m ³	14	16.7	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/15/2022 09:00	04/16/2022 08:48	LLJ
75-71-8	Dichlorodifluoromethane	48		ug/m ³	8.3	16.7	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/15/2022 09:00	04/16/2022 08:48	LLJ
141-78-6	* Ethyl acetate	ND		ug/m ³	12	16.7	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/15/2022 09:00	04/16/2022 08:48	LLJ
100-41-4	Ethyl Benzene	ND		ug/m ³	7.3	16.7	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/15/2022 09:00	04/16/2022 08:48	LLJ
87-68-3	Hexachlorobutadiene	ND		ug/m ³	18	16.7	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/15/2022 09:00	04/16/2022 08:48	LLJ
67-63-0	Isopropanol	ND		ug/m ³	8.2	16.7	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/15/2022 09:00	04/16/2022 08:48	LLJ



Sample Information

Client Sample ID: EW-2

York Sample ID: 22D0083-02

York Project (SDG) No.

Client Project ID

Matrix

Collection Date/Time

Date Received

22D0083

356060 65 Albany Avenue Kingston, New York

Soil Vapor

April 3, 2022 11:40 am

04/04/2022

Volatile Organics, EPA TO15 Full List

Log-in Notes:

Sample Notes:

Sample Prepared by Method: EPA TO15 PREP

CAS No.	Parameter	Result	Flag	Units	Reported to LOQ	Dilution	Reference Method	Date/Time Prepared	Date/Time Analyzed	Analyst
80-62-6	Methyl Methacrylate	ND		ug/m ³	6.8	16.7	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/15/2022 09:00	04/16/2022 08:48	LLJ
1634-04-4	Methyl tert-butyl ether (MTBE)	ND		ug/m ³	6.0	16.7	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/15/2022 09:00	04/16/2022 08:48	LLJ
75-09-2	Methylene chloride	270		ug/m ³	12	16.7	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/15/2022 09:00	04/16/2022 08:48	LLJ
142-82-5	n-Heptane	ND		ug/m ³	6.8	16.7	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/15/2022 09:00	04/16/2022 08:48	LLJ
110-54-3	n-Hexane	10		ug/m ³	5.9	16.7	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/15/2022 09:00	04/16/2022 08:48	LLJ
95-47-6	o-Xylene	ND		ug/m ³	7.3	16.7	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/15/2022 09:00	04/16/2022 08:48	LLJ
179601-23-1	p- & m- Xylenes	ND		ug/m ³	15	16.7	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/15/2022 09:00	04/16/2022 08:48	LLJ
622-96-8	* p-Ethyltoluene	ND		ug/m ³	8.2	16.7	EPA TO-15 Certifications:	04/15/2022 09:00	04/16/2022 08:48	LLJ
115-07-1	* Propylene	ND		ug/m ³	2.9	16.7	EPA TO-15 Certifications:	04/15/2022 09:00	04/16/2022 08:48	LLJ
100-42-5	Styrene	ND		ug/m ³	7.1	16.7	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/15/2022 09:00	04/16/2022 08:48	LLJ
127-18-4	Tetrachloroethylene	2300		ug/m ³	11	16.7	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/15/2022 09:00	04/16/2022 08:48	LLJ
109-99-9	* Tetrahydrofuran	ND		ug/m ³	9.9	16.7	EPA TO-15 Certifications:	04/15/2022 09:00	04/16/2022 08:48	LLJ
108-88-3	Toluene	ND		ug/m ³	6.3	16.7	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/15/2022 09:00	04/16/2022 08:48	LLJ
156-60-5	trans-1,2-Dichloroethylene	ND		ug/m ³	6.6	16.7	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/15/2022 09:00	04/16/2022 08:48	LLJ
10061-02-6	trans-1,3-Dichloropropylene	ND		ug/m ³	7.6	16.7	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/15/2022 09:00	04/16/2022 08:48	LLJ
79-01-6	Trichloroethylene	2.7		ug/m ³	2.2	16.7	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/15/2022 09:00	04/16/2022 08:48	LLJ
75-69-4	Trichlorofluoromethane (Freon 11)	9.4		ug/m ³	9.4	16.7	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/15/2022 09:00	04/16/2022 08:48	LLJ
108-05-4	Vinyl acetate	ND		ug/m ³	5.9	16.7	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/15/2022 09:00	04/16/2022 08:48	LLJ
593-60-2	Vinyl bromide	ND		ug/m ³	7.3	16.7	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/15/2022 09:00	04/16/2022 08:48	LLJ
75-01-4	Vinyl Chloride	ND		ug/m ³	2.1	16.7	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/15/2022 09:00	04/16/2022 08:48	LLJ



Sample Information

Client Sample ID: EW-3

York Sample ID: 22D0083-03

York Project (SDG) No.

Client Project ID

Matrix

Collection Date/Time

Date Received

22D0083

356060 65 Albany Avenue Kingston, New York

Soil Vapor

April 3, 2022 1:09 pm

04/04/2022

Volatile Organics, EPA TO15 Full List

Log-in Notes:

Sample Notes:

Sample Prepared by Method: EPA TO15 PREP

CAS No.	Parameter	Result	Flag	Units	Reported to LOQ	Dilution	Reference Method	Date/Time Prepared	Date/Time Analyzed	Analyst
630-20-6	* 1,1,1,2-Tetrachloroethane	ND		ug/m ³	12	17.85	EPA TO-15 Certifications:	04/15/2022 09:00	04/16/2022 09:35	LLJ
71-55-6	1,1,1-Trichloroethane	ND		ug/m ³	9.7	17.85	EPA TO-15 Certifications:	04/15/2022 09:00	04/16/2022 09:35	LLJ
79-34-5	1,1,2,2-Tetrachloroethane	ND		ug/m ³	12	17.85	EPA TO-15 Certifications:	04/15/2022 09:00	04/16/2022 09:35	LLJ
76-13-1	1,1,2-Trichloro-1,2,2-trifluoroethane (Freon 113)	ND		ug/m ³	14	17.85	EPA TO-15 Certifications:	04/15/2022 09:00	04/16/2022 09:35	LLJ
79-00-5	1,1,2-Trichloroethane	ND		ug/m ³	9.7	17.85	EPA TO-15 Certifications:	04/15/2022 09:00	04/16/2022 09:35	LLJ
75-34-3	1,1-Dichloroethane	ND		ug/m ³	7.2	17.85	EPA TO-15 Certifications:	04/15/2022 09:00	04/16/2022 09:35	LLJ
75-35-4	1,1-Dichloroethylene	ND		ug/m ³	1.8	17.85	EPA TO-15 Certifications:	04/15/2022 09:00	04/16/2022 09:35	LLJ
120-82-1	1,2,4-Trichlorobenzene	ND		ug/m ³	13	17.85	EPA TO-15 Certifications:	04/15/2022 09:00	04/16/2022 09:35	LLJ
95-63-6	1,2,4-Trimethylbenzene	ND		ug/m ³	8.8	17.85	EPA TO-15 Certifications:	04/15/2022 09:00	04/16/2022 09:35	LLJ
106-93-4	1,2-Dibromoethane	ND		ug/m ³	14	17.85	EPA TO-15 Certifications:	04/15/2022 09:00	04/16/2022 09:35	LLJ
95-50-1	1,2-Dichlorobenzene	ND		ug/m ³	11	17.85	EPA TO-15 Certifications:	04/15/2022 09:00	04/16/2022 09:35	LLJ
107-06-2	1,2-Dichloroethane	ND		ug/m ³	7.2	17.85	EPA TO-15 Certifications:	04/15/2022 09:00	04/16/2022 09:35	LLJ
78-87-5	1,2-Dichloropropane	ND		ug/m ³	8.2	17.85	EPA TO-15 Certifications:	04/15/2022 09:00	04/16/2022 09:35	LLJ
76-14-2	1,2-Dichlorotetrafluoroethane	ND		ug/m ³	12	17.85	EPA TO-15 Certifications:	04/15/2022 09:00	04/16/2022 09:35	LLJ
108-67-8	1,3,5-Trimethylbenzene	ND		ug/m ³	8.8	17.85	EPA TO-15 Certifications:	04/15/2022 09:00	04/16/2022 09:35	LLJ
106-99-0	1,3-Butadiene	ND		ug/m ³	12	17.85	EPA TO-15 Certifications:	04/15/2022 09:00	04/16/2022 09:35	LLJ
541-73-1	1,3-Dichlorobenzene	ND		ug/m ³	11	17.85	EPA TO-15 Certifications:	04/15/2022 09:00	04/16/2022 09:35	LLJ
142-28-9	* 1,3-Dichloropropane	ND		ug/m ³	8.2	17.85	EPA TO-15 Certifications:	04/15/2022 09:00	04/16/2022 09:35	LLJ
106-46-7	1,4-Dichlorobenzene	ND		ug/m ³	11	17.85	EPA TO-15 Certifications:	04/15/2022 09:00	04/16/2022 09:35	LLJ
123-91-1	1,4-Dioxane	ND		ug/m ³	13	17.85	EPA TO-15 Certifications:	04/15/2022 09:00	04/16/2022 09:35	LLJ
78-93-3	2-Butanone	13		ug/m ³	5.3	17.85	EPA TO-15 Certifications:	04/15/2022 09:00	04/16/2022 09:35	LLJ
591-78-6	* 2-Hexanone	ND		ug/m ³	15	17.85	EPA TO-15 Certifications:	04/15/2022 09:00	04/16/2022 09:35	LLJ
107-05-1	3-Chloropropene	ND		ug/m ³	28	17.85	EPA TO-15 Certifications:	04/15/2022 09:00	04/16/2022 09:35	LLJ



Sample Information

Client Sample ID: EW-3

York Sample ID: 22D0083-03

York Project (SDG) No.

Client Project ID

Matrix

Collection Date/Time

Date Received

22D0083

356060 65 Albany Avenue Kingston, New York

Soil Vapor

April 3, 2022 1:09 pm

04/04/2022

Volatile Organics, EPA TO15 Full List

Log-in Notes:

Sample Notes:

Sample Prepared by Method: EPA TO15 PREP

CAS No.	Parameter	Result	Flag	Units	Reported to LOQ	Dilution	Reference Method	Date/Time Prepared	Date/Time Analyzed	Analyst
108-10-1	4-Methyl-2-pentanone	ND		ug/m ³	7.3	17.85	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/15/2022 09:00	04/16/2022 09:35	LLJ
67-64-1	Acetone	33		ug/m ³	8.5	17.85	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/15/2022 09:00	04/16/2022 09:35	LLJ
107-13-1	Acrylonitrile	ND		ug/m ³	3.9	17.85	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/15/2022 09:00	04/16/2022 09:35	LLJ
71-43-2	Benzene	ND		ug/m ³	5.7	17.85	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/15/2022 09:00	04/16/2022 09:35	LLJ
100-44-7	Benzyl chloride	ND		ug/m ³	9.2	17.85	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/15/2022 09:00	04/16/2022 09:35	LLJ
75-27-4	Bromodichloromethane	ND		ug/m ³	12	17.85	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/15/2022 09:00	04/16/2022 09:35	LLJ
75-25-2	Bromoform	ND		ug/m ³	18	17.85	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/15/2022 09:00	04/16/2022 09:35	LLJ
74-83-9	Bromomethane	ND		ug/m ³	6.9	17.85	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/15/2022 09:00	04/16/2022 09:35	LLJ
75-15-0	Carbon disulfide	ND		ug/m ³	5.6	17.85	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/15/2022 09:00	04/16/2022 09:35	LLJ
56-23-5	Carbon tetrachloride	ND		ug/m ³	2.8	17.85	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/15/2022 09:00	04/16/2022 09:35	LLJ
108-90-7	Chlorobenzene	ND		ug/m ³	8.2	17.85	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/15/2022 09:00	04/16/2022 09:35	LLJ
75-00-3	Chloroethane	ND		ug/m ³	4.7	17.85	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/15/2022 09:00	04/16/2022 09:35	LLJ
67-66-3	Chloroform	ND		ug/m ³	8.7	17.85	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/15/2022 09:00	04/16/2022 09:35	LLJ
74-87-3	Chloromethane	ND		ug/m ³	3.7	17.85	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/15/2022 09:00	04/16/2022 09:35	LLJ
156-59-2	cis-1,2-Dichloroethylene	ND		ug/m ³	1.8	17.85	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/15/2022 09:00	04/16/2022 09:35	LLJ
10061-01-5	cis-1,3-Dichloropropylene	ND		ug/m ³	8.1	17.85	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/15/2022 09:00	04/16/2022 09:35	LLJ
110-82-7	Cyclohexane	ND		ug/m ³	6.1	17.85	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/15/2022 09:00	04/16/2022 09:35	LLJ
124-48-1	Dibromochloromethane	ND		ug/m ³	15	17.85	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/15/2022 09:00	04/16/2022 09:35	LLJ
75-71-8	Dichlorodifluoromethane	71		ug/m ³	8.8	17.85	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/15/2022 09:00	04/16/2022 09:35	LLJ
141-78-6	* Ethyl acetate	ND		ug/m ³	13	17.85	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/15/2022 09:00	04/16/2022 09:35	LLJ
100-41-4	Ethyl Benzene	ND		ug/m ³	7.8	17.85	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/15/2022 09:00	04/16/2022 09:35	LLJ
87-68-3	Hexachlorobutadiene	ND		ug/m ³	19	17.85	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/15/2022 09:00	04/16/2022 09:35	LLJ
67-63-0	Isopropanol	ND		ug/m ³	8.8	17.85	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/15/2022 09:00	04/16/2022 09:35	LLJ



Sample Information

Client Sample ID: EW-3

York Sample ID: 22D0083-03

York Project (SDG) No.

Client Project ID

Matrix

Collection Date/Time

Date Received

22D0083

356060 65 Albany Avenue Kingston, New York

Soil Vapor

April 3, 2022 1:09 pm

04/04/2022

Volatile Organics, EPA TO15 Full List

Log-in Notes:

Sample Notes:

Sample Prepared by Method: EPA TO15 PREP

CAS No.	Parameter	Result	Flag	Units	Reported to LOQ	Dilution	Reference Method	Date/Time Prepared	Date/Time Analyzed	Analyst
80-62-6	Methyl Methacrylate	ND		ug/m ³	7.3	17.85	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/15/2022 09:00	04/16/2022 09:35	LLJ
1634-04-4	Methyl tert-butyl ether (MTBE)	ND		ug/m ³	6.4	17.85	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/15/2022 09:00	04/16/2022 09:35	LLJ
75-09-2	Methylene chloride	22		ug/m ³	12	17.85	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/15/2022 09:00	04/16/2022 09:35	LLJ
142-82-5	n-Heptane	ND		ug/m ³	7.3	17.85	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/15/2022 09:00	04/16/2022 09:35	LLJ
110-54-3	n-Hexane	ND		ug/m ³	6.3	17.85	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/15/2022 09:00	04/16/2022 09:35	LLJ
95-47-6	o-Xylene	ND		ug/m ³	7.8	17.85	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/15/2022 09:00	04/16/2022 09:35	LLJ
179601-23-1	p- & m- Xylenes	19		ug/m ³	16	17.85	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/15/2022 09:00	04/16/2022 09:35	LLJ
622-96-8	* p-Ethyltoluene	ND		ug/m ³	8.8	17.85	EPA TO-15 Certifications:	04/15/2022 09:00	04/16/2022 09:35	LLJ
115-07-1	* Propylene	ND		ug/m ³	3.1	17.85	EPA TO-15 Certifications:	04/15/2022 09:00	04/16/2022 09:35	LLJ
100-42-5	Styrene	ND		ug/m ³	7.6	17.85	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/15/2022 09:00	04/16/2022 09:35	LLJ
127-18-4	Tetrachloroethylene	71000		ug/m ³	170	255.8	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 12:43	LLJ
109-99-9	* Tetrahydrofuran	54		ug/m ³	11	17.85	EPA TO-15 Certifications:	04/15/2022 09:00	04/16/2022 09:35	LLJ
108-88-3	Toluene	ND		ug/m ³	6.7	17.85	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/15/2022 09:00	04/16/2022 09:35	LLJ
156-60-5	trans-1,2-Dichloroethylene	ND		ug/m ³	7.1	17.85	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/15/2022 09:00	04/16/2022 09:35	LLJ
10061-02-6	trans-1,3-Dichloropropylene	ND		ug/m ³	8.1	17.85	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/15/2022 09:00	04/16/2022 09:35	LLJ
79-01-6	Trichloroethylene	15		ug/m ³	2.4	17.85	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/15/2022 09:00	04/16/2022 09:35	LLJ
75-69-4	Trichlorofluoromethane (Freon 11)	ND		ug/m ³	10	17.85	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/15/2022 09:00	04/16/2022 09:35	LLJ
108-05-4	Vinyl acetate	ND		ug/m ³	6.3	17.85	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/15/2022 09:00	04/16/2022 09:35	LLJ
593-60-2	Vinyl bromide	ND		ug/m ³	7.8	17.85	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/15/2022 09:00	04/16/2022 09:35	LLJ
75-01-4	Vinyl Chloride	ND		ug/m ³	2.3	17.85	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/15/2022 09:00	04/16/2022 09:35	LLJ



Sample Information

Client Sample ID: EW-4

York Sample ID: 22D0083-04

York Project (SDG) No.

Client Project ID

Matrix

Collection Date/Time

Date Received

22D0083

356060 65 Albany Avenue Kingston, New York

Soil Vapor

April 3, 2022 2:12 pm

04/04/2022

Volatile Organics, EPA TO15 Full List

Log-in Notes:

Sample Notes:

Sample Prepared by Method: EPA TO15 PREP

CAS No.	Parameter	Result	Flag	Units	Reported to LOQ	Dilution	Reference Method	Date/Time Prepared	Date/Time Analyzed	Analyst
630-20-6	* 1,1,1,2-Tetrachloroethane	ND		ug/m ³	6.1	8.955	EPA TO-15 Certifications:	04/17/2022 02:00	04/17/2022 13:30	LLJ
71-55-6	1,1,1-Trichloroethane	9.8		ug/m ³	4.9	8.955	EPA TO-15 Certifications:	04/17/2022 02:00	04/17/2022 13:30	LLJ
79-34-5	1,1,2,2-Tetrachloroethane	ND		ug/m ³	6.1	8.955	EPA TO-15 Certifications:	04/17/2022 02:00	04/17/2022 13:30	LLJ
76-13-1	1,1,2-Trichloro-1,2,2-trifluoroethane (Freon 113)	ND		ug/m ³	6.9	8.955	EPA TO-15 Certifications:	04/17/2022 02:00	04/17/2022 13:30	LLJ
79-00-5	1,1,2-Trichloroethane	ND		ug/m ³	4.9	8.955	EPA TO-15 Certifications:	04/17/2022 02:00	04/17/2022 13:30	LLJ
75-34-3	1,1-Dichloroethane	ND		ug/m ³	3.6	8.955	EPA TO-15 Certifications:	04/17/2022 02:00	04/17/2022 13:30	LLJ
75-35-4	1,1-Dichloroethylene	ND		ug/m ³	0.89	8.955	EPA TO-15 Certifications:	04/17/2022 02:00	04/17/2022 13:30	LLJ
120-82-1	1,2,4-Trichlorobenzene	ND		ug/m ³	6.6	8.955	EPA TO-15 Certifications:	04/17/2022 02:00	04/17/2022 13:30	LLJ
95-63-6	1,2,4-Trimethylbenzene	ND		ug/m ³	4.4	8.955	EPA TO-15 Certifications:	04/17/2022 02:00	04/17/2022 13:30	LLJ
106-93-4	1,2-Dibromoethane	ND		ug/m ³	6.9	8.955	EPA TO-15 Certifications:	04/17/2022 02:00	04/17/2022 13:30	LLJ
95-50-1	1,2-Dichlorobenzene	ND		ug/m ³	5.4	8.955	EPA TO-15 Certifications:	04/17/2022 02:00	04/17/2022 13:30	LLJ
107-06-2	1,2-Dichloroethane	ND		ug/m ³	3.6	8.955	EPA TO-15 Certifications:	04/17/2022 02:00	04/17/2022 13:30	LLJ
78-87-5	1,2-Dichloropropane	ND		ug/m ³	4.1	8.955	EPA TO-15 Certifications:	04/17/2022 02:00	04/17/2022 13:30	LLJ
76-14-2	1,2-Dichlorotetrafluoroethane	ND		ug/m ³	6.3	8.955	EPA TO-15 Certifications:	04/17/2022 02:00	04/17/2022 13:30	LLJ
108-67-8	1,3,5-Trimethylbenzene	ND		ug/m ³	4.4	8.955	EPA TO-15 Certifications:	04/17/2022 02:00	04/17/2022 13:30	LLJ
106-99-0	1,3-Butadiene	ND		ug/m ³	5.9	8.955	EPA TO-15 Certifications:	04/17/2022 02:00	04/17/2022 13:30	LLJ
541-73-1	1,3-Dichlorobenzene	ND		ug/m ³	5.4	8.955	EPA TO-15 Certifications:	04/17/2022 02:00	04/17/2022 13:30	LLJ
142-28-9	* 1,3-Dichloropropane	ND		ug/m ³	4.1	8.955	EPA TO-15 Certifications:	04/17/2022 02:00	04/17/2022 13:30	LLJ
106-46-7	1,4-Dichlorobenzene	ND		ug/m ³	5.4	8.955	EPA TO-15 Certifications:	04/17/2022 02:00	04/17/2022 13:30	LLJ
123-91-1	1,4-Dioxane	ND		ug/m ³	6.5	8.955	EPA TO-15 Certifications:	04/17/2022 02:00	04/17/2022 13:30	LLJ
78-93-3	2-Butanone	12		ug/m ³	2.6	8.955	EPA TO-15 Certifications:	04/17/2022 02:00	04/17/2022 13:30	LLJ
591-78-6	* 2-Hexanone	ND		ug/m ³	7.3	8.955	EPA TO-15 Certifications:	04/17/2022 02:00	04/17/2022 13:30	LLJ
107-05-1	3-Chloropropene	ND		ug/m ³	14	8.955	EPA TO-15 Certifications:	04/17/2022 02:00	04/17/2022 13:30	LLJ



Sample Information

Client Sample ID: EW-4

York Sample ID: 22D0083-04

York Project (SDG) No.

Client Project ID

Matrix

Collection Date/Time

Date Received

22D0083

356060 65 Albany Avenue Kingston, New York

Soil Vapor

April 3, 2022 2:12 pm

04/04/2022

Volatile Organics, EPA TO15 Full List

Log-in Notes:

Sample Notes:

Sample Prepared by Method: EPA TO15 PREP

CAS No.	Parameter	Result	Flag	Units	Reported to LOQ	Dilution	Reference Method	Date/Time Prepared	Date/Time Analyzed	Analyst
108-10-1	4-Methyl-2-pentanone	ND		ug/m ³	3.7	8.955	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 13:30	LLJ
67-64-1	Acetone	14		ug/m ³	4.3	8.955	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 13:30	LLJ
107-13-1	Acrylonitrile	ND		ug/m ³	1.9	8.955	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 13:30	LLJ
71-43-2	Benzene	ND		ug/m ³	2.9	8.955	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 13:30	LLJ
100-44-7	Benzyl chloride	ND		ug/m ³	4.6	8.955	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 13:30	LLJ
75-27-4	Bromodichloromethane	ND		ug/m ³	6.0	8.955	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 13:30	LLJ
75-25-2	Bromoform	ND		ug/m ³	9.3	8.955	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 13:30	LLJ
74-83-9	Bromomethane	ND		ug/m ³	3.5	8.955	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 13:30	LLJ
75-15-0	Carbon disulfide	ND		ug/m ³	2.8	8.955	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 13:30	LLJ
56-23-5	Carbon tetrachloride	ND		ug/m ³	1.4	8.955	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 13:30	LLJ
108-90-7	Chlorobenzene	ND		ug/m ³	4.1	8.955	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 13:30	LLJ
75-00-3	Chloroethane	ND		ug/m ³	2.4	8.955	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 13:30	LLJ
67-66-3	Chloroform	ND		ug/m ³	4.4	8.955	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 13:30	LLJ
74-87-3	Chloromethane	ND		ug/m ³	1.8	8.955	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 13:30	LLJ
156-59-2	cis-1,2-Dichloroethylene	ND		ug/m ³	0.89	8.955	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 13:30	LLJ
10061-01-5	cis-1,3-Dichloropropylene	ND		ug/m ³	4.1	8.955	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 13:30	LLJ
110-82-7	Cyclohexane	ND		ug/m ³	3.1	8.955	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 13:30	LLJ
124-48-1	Dibromochloromethane	ND		ug/m ³	7.6	8.955	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 13:30	LLJ
75-71-8	Dichlorodifluoromethane	7.1		ug/m ³	4.4	8.955	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 13:30	LLJ
141-78-6	* Ethyl acetate	14		ug/m ³	6.5	8.955	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 13:30	LLJ
100-41-4	Ethyl Benzene	19		ug/m ³	3.9	8.955	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 13:30	LLJ
87-68-3	Hexachlorobutadiene	ND		ug/m ³	9.6	8.955	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 13:30	LLJ
67-63-0	Isopropanol	ND		ug/m ³	4.4	8.955	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 13:30	LLJ



Sample Information

Client Sample ID: EW-4

York Sample ID: 22D0083-04

York Project (SDG) No.

Client Project ID

Matrix

Collection Date/Time

Date Received

22D0083

356060 65 Albany Avenue Kingston, New York

Soil Vapor

April 3, 2022 2:12 pm

04/04/2022

Volatile Organics, EPA TO15 Full List

Log-in Notes:

Sample Notes:

Sample Prepared by Method: EPA TO15 PREP

CAS No.	Parameter	Result	Flag	Units	Reported to LOQ	Dilution	Reference Method	Date/Time Prepared	Date/Time Analyzed	Analyst
80-62-6	Methyl Methacrylate	ND		ug/m ³	3.7	8.955	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 13:30	LLJ
1634-04-4	Methyl tert-butyl ether (MTBE)	ND		ug/m ³	3.2	8.955	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 13:30	LLJ
75-09-2	Methylene chloride	6.2		ug/m ³	6.2	8.955	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 13:30	LLJ
142-82-5	n-Heptane	ND		ug/m ³	3.7	8.955	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 13:30	LLJ
110-54-3	n-Hexane	ND		ug/m ³	3.2	8.955	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 13:30	LLJ
95-47-6	o-Xylene	16		ug/m ³	3.9	8.955	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 13:30	LLJ
179601-23-1	p- & m- Xylenes	76		ug/m ³	7.8	8.955	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 13:30	LLJ
622-96-8	* p-Ethyltoluene	ND		ug/m ³	4.4	8.955	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 13:30	LLJ
115-07-1	* Propylene	ND		ug/m ³	1.5	8.955	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 13:30	LLJ
100-42-5	Styrene	ND		ug/m ³	3.8	8.955	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 13:30	LLJ
127-18-4	Tetrachloroethylene	1300		ug/m ³	6.1	8.955	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 13:30	LLJ
109-99-9	* Tetrahydrofuran	5.8		ug/m ³	5.3	8.955	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 13:30	LLJ
108-88-3	Toluene	ND		ug/m ³	3.4	8.955	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 13:30	LLJ
156-60-5	trans-1,2-Dichloroethylene	ND		ug/m ³	3.6	8.955	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 13:30	LLJ
10061-02-6	trans-1,3-Dichloropropylene	ND		ug/m ³	4.1	8.955	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 13:30	LLJ
79-01-6	Trichloroethylene	1.9		ug/m ³	1.2	8.955	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 13:30	LLJ
75-69-4	Trichlorofluoromethane (Freon 11)	ND		ug/m ³	5.0	8.955	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 13:30	LLJ
108-05-4	Vinyl acetate	ND		ug/m ³	3.2	8.955	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 13:30	LLJ
593-60-2	Vinyl bromide	ND		ug/m ³	3.9	8.955	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 13:30	LLJ
75-01-4	Vinyl Chloride	ND		ug/m ³	1.1	8.955	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 13:30	LLJ



Sample Information

Client Sample ID: EW-5

York Sample ID: 22D0083-05

York Project (SDG) No.

Client Project ID

Matrix

Collection Date/Time

Date Received

22D0083

356060 65 Albany Avenue Kingston, New York

Soil Vapor

April 3, 2022 3:00 pm

04/04/2022

Volatile Organics, EPA TO15 Full List

Log-in Notes:

Sample Notes:

Sample Prepared by Method: EPA TO15 PREP

CAS No.	Parameter	Result	Flag	Units	Reported to LOQ	Dilution	Reference Method	Date/Time Prepared	Date/Time Analyzed	Analyst
630-20-6	* 1,1,1,2-Tetrachloroethane	ND		ug/m ³	12	17.45	EPA TO-15 Certifications:	04/17/2022 02:00	04/17/2022 14:16	LLJ
71-55-6	1,1,1-Trichloroethane	ND		ug/m ³	9.5	17.45	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 14:16	LLJ
79-34-5	1,1,2,2-Tetrachloroethane	ND		ug/m ³	12	17.45	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 14:16	LLJ
76-13-1	1,1,2-Trichloro-1,2,2-trifluoroethane (Freon 113)	ND		ug/m ³	13	17.45	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 14:16	LLJ
79-00-5	1,1,2-Trichloroethane	ND		ug/m ³	9.5	17.45	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 14:16	LLJ
75-34-3	1,1-Dichloroethane	ND		ug/m ³	7.1	17.45	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 14:16	LLJ
75-35-4	1,1-Dichloroethylene	ND		ug/m ³	1.7	17.45	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 14:16	LLJ
120-82-1	1,2,4-Trichlorobenzene	ND		ug/m ³	13	17.45	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 14:16	LLJ
95-63-6	1,2,4-Trimethylbenzene	ND		ug/m ³	8.6	17.45	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 14:16	LLJ
106-93-4	1,2-Dibromoethane	ND		ug/m ³	13	17.45	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 14:16	LLJ
95-50-1	1,2-Dichlorobenzene	ND		ug/m ³	10	17.45	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 14:16	LLJ
107-06-2	1,2-Dichloroethane	ND		ug/m ³	7.1	17.45	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 14:16	LLJ
78-87-5	1,2-Dichloropropane	ND		ug/m ³	8.1	17.45	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 14:16	LLJ
76-14-2	1,2-Dichlorotetrafluoroethane	ND		ug/m ³	12	17.45	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 14:16	LLJ
108-67-8	1,3,5-Trimethylbenzene	ND		ug/m ³	8.6	17.45	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 14:16	LLJ
106-99-0	1,3-Butadiene	ND		ug/m ³	12	17.45	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 14:16	LLJ
541-73-1	1,3-Dichlorobenzene	ND		ug/m ³	10	17.45	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 14:16	LLJ
142-28-9	* 1,3-Dichloropropane	ND		ug/m ³	8.1	17.45	EPA TO-15 Certifications:	04/17/2022 02:00	04/17/2022 14:16	LLJ
106-46-7	1,4-Dichlorobenzene	ND		ug/m ³	10	17.45	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 14:16	LLJ
123-91-1	1,4-Dioxane	ND		ug/m ³	13	17.45	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 14:16	LLJ
78-93-3	2-Butanone	5.7		ug/m ³	5.1	17.45	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 14:16	LLJ
591-78-6	* 2-Hexanone	ND		ug/m ³	14	17.45	EPA TO-15 Certifications:	04/17/2022 02:00	04/17/2022 14:16	LLJ
107-05-1	3-Chloropropene	ND		ug/m ³	27	17.45	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 14:16	LLJ



Sample Information

Client Sample ID: EW-5

York Sample ID: 22D0083-05

York Project (SDG) No.

Client Project ID

Matrix

Collection Date/Time

Date Received

22D0083

356060 65 Albany Avenue Kingston, New York

Soil Vapor

April 3, 2022 3:00 pm

04/04/2022

Volatile Organics, EPA TO15 Full List

Log-in Notes:

Sample Notes:

Sample Prepared by Method: EPA TO15 PREP

CAS No.	Parameter	Result	Flag	Units	Reported to LOQ	Dilution	Reference Method	Date/Time Prepared	Date/Time Analyzed	Analyst
108-10-1	4-Methyl-2-pentanone	ND		ug/m ³	7.1	17.45	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 14:16	LLJ
67-64-1	Acetone	12		ug/m ³	8.3	17.45	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 14:16	LLJ
107-13-1	Acrylonitrile	ND		ug/m ³	3.8	17.45	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 14:16	LLJ
71-43-2	Benzene	ND		ug/m ³	5.6	17.45	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 14:16	LLJ
100-44-7	Benzyl chloride	ND		ug/m ³	9.0	17.45	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 14:16	LLJ
75-27-4	Bromodichloromethane	ND		ug/m ³	12	17.45	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 14:16	LLJ
75-25-2	Bromoform	ND		ug/m ³	18	17.45	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 14:16	LLJ
74-83-9	Bromomethane	ND		ug/m ³	6.8	17.45	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 14:16	LLJ
75-15-0	Carbon disulfide	ND		ug/m ³	5.4	17.45	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 14:16	LLJ
56-23-5	Carbon tetrachloride	ND		ug/m ³	2.7	17.45	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 14:16	LLJ
108-90-7	Chlorobenzene	ND		ug/m ³	8.0	17.45	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 14:16	LLJ
75-00-3	Chloroethane	ND		ug/m ³	4.6	17.45	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 14:16	LLJ
67-66-3	Chloroform	ND		ug/m ³	8.5	17.45	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 14:16	LLJ
74-87-3	Chloromethane	ND		ug/m ³	3.6	17.45	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 14:16	LLJ
156-59-2	cis-1,2-Dichloroethylene	ND		ug/m ³	1.7	17.45	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 14:16	LLJ
10061-01-5	cis-1,3-Dichloropropylene	ND		ug/m ³	7.9	17.45	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 14:16	LLJ
110-82-7	Cyclohexane	ND		ug/m ³	6.0	17.45	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 14:16	LLJ
124-48-1	Dibromochloromethane	ND		ug/m ³	15	17.45	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 14:16	LLJ
75-71-8	Dichlorodifluoromethane	22		ug/m ³	8.6	17.45	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 14:16	LLJ
141-78-6	* Ethyl acetate	ND		ug/m ³	13	17.45	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 14:16	LLJ
100-41-4	Ethyl Benzene	ND		ug/m ³	7.6	17.45	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 14:16	LLJ
87-68-3	Hexachlorobutadiene	ND		ug/m ³	19	17.45	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 14:16	LLJ
67-63-0	Isopropanol	ND		ug/m ³	8.6	17.45	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 14:16	LLJ



Sample Information

Client Sample ID: EW-5

York Sample ID: 22D0083-05

York Project (SDG) No.

Client Project ID

Matrix

Collection Date/Time

Date Received

22D0083

356060 65 Albany Avenue Kingston, New York

Soil Vapor

April 3, 2022 3:00 pm

04/04/2022

Volatile Organics, EPA TO15 Full List

Log-in Notes:

Sample Notes:

Sample Prepared by Method: EPA TO15 PREP

CAS No.	Parameter	Result	Flag	Units	Reported to LOQ	Dilution	Reference Method	Date/Time Prepared	Date/Time Analyzed	Analyst
80-62-6	Methyl Methacrylate	ND		ug/m ³	7.1	17.45	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 14:16	LLJ
1634-04-4	Methyl tert-butyl ether (MTBE)	ND		ug/m ³	6.3	17.45	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 14:16	LLJ
75-09-2	Methylene chloride	42		ug/m ³	12	17.45	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 14:16	LLJ
142-82-5	n-Heptane	ND		ug/m ³	7.2	17.45	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 14:16	LLJ
110-54-3	n-Hexane	ND		ug/m ³	6.2	17.45	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 14:16	LLJ
95-47-6	o-Xylene	ND		ug/m ³	7.6	17.45	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 14:16	LLJ
179601-23-1	p- & m- Xylenes	ND		ug/m ³	15	17.45	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 14:16	LLJ
622-96-8	* p-Ethyltoluene	ND		ug/m ³	8.6	17.45	EPA TO-15 Certifications:	04/17/2022 02:00	04/17/2022 14:16	LLJ
115-07-1	* Propylene	ND		ug/m ³	3.0	17.45	EPA TO-15 Certifications:	04/17/2022 02:00	04/17/2022 14:16	LLJ
100-42-5	Styrene	ND		ug/m ³	7.4	17.45	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 14:16	LLJ
127-18-4	Tetrachloroethylene	4300		ug/m ³	12	17.45	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 14:16	LLJ
109-99-9	* Tetrahydrofuran	ND		ug/m ³	10	17.45	EPA TO-15 Certifications:	04/17/2022 02:00	04/17/2022 14:16	LLJ
108-88-3	Toluene	ND		ug/m ³	6.6	17.45	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 14:16	LLJ
156-60-5	trans-1,2-Dichloroethylene	ND		ug/m ³	6.9	17.45	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 14:16	LLJ
10061-02-6	trans-1,3-Dichloropropylene	ND		ug/m ³	7.9	17.45	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 14:16	LLJ
79-01-6	Trichloroethylene	2.8		ug/m ³	2.3	17.45	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 14:16	LLJ
75-69-4	Trichlorofluoromethane (Freon 11)	12		ug/m ³	9.8	17.45	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 14:16	LLJ
108-05-4	Vinyl acetate	ND		ug/m ³	6.1	17.45	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 14:16	LLJ
593-60-2	Vinyl bromide	ND		ug/m ³	7.6	17.45	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 14:16	LLJ
75-01-4	Vinyl Chloride	ND		ug/m ³	2.2	17.45	EPA TO-15 Certifications: NELAC-NY12058,NJDEP-Queens	04/17/2022 02:00	04/17/2022 14:16	LLJ



Analytical Batch Summary

Batch ID: BD20955 **Preparation Method:** EPA TO15 PREP **Prepared By:** LLJ

YORK Sample ID	Client Sample ID	Preparation Date
22D0083-02	EW-2	04/15/22
22D0083-03	EW-3	04/15/22
BD20955-BLK1	Blank	04/15/22
BD20955-BS1	LCS	04/15/22
BD20955-DUP1	Duplicate	04/15/22

Batch ID: BD21003 **Preparation Method:** EPA TO15 PREP **Prepared By:** LLJ

YORK Sample ID	Client Sample ID	Preparation Date
22D0083-01	EW-1	04/17/22
22D0083-03RE1	EW-3	04/17/22
22D0083-04	EW-4	04/17/22
22D0083-05	EW-5	04/17/22
BD21003-BLK1	Blank	04/17/22
BD21003-BS1	LCS	04/17/22
BD21003-DUP1	Duplicate	04/17/22



Volatile Organic Compounds in Air by GC/MS - Quality Control Data

York Analytical Laboratories, Inc.

Analyte	Result	Reporting Limit	Units	Spike Level	Source* Result	%REC	%REC Limits	Flag	RPD	RPD Limit	Flag
---------	--------	--------------------	-------	----------------	-------------------	------	----------------	------	-----	--------------	------

Batch BD20955 - EPA TO15 PREP

Blank (BD20955-BLK1)

Prepared & Analyzed: 04/15/2022

1,1,1,2-Tetrachloroethane	ND	0.69	ug/m ³
1,1,1-Trichloroethane	ND	0.55	"
1,1,2,2-Tetrachloroethane	ND	0.69	"
1,1,2-Trichloro-1,2,2-trifluoroethane (Freon 113)	ND	0.77	"
1,1,2-Trichloroethane	ND	0.55	"
1,1-Dichloroethane	ND	0.40	"
1,1-Dichloroethylene	ND	0.099	"
1,2,4-Trichlorobenzene	ND	0.74	"
1,2,4-Trimethylbenzene	ND	0.49	"
1,2-Dibromoethane	ND	0.77	"
1,2-Dichlorobenzene	ND	0.60	"
1,2-Dichloroethane	ND	0.40	"
1,2-Dichloropropane	ND	0.46	"
1,2-Dichlorotetrafluoroethane	ND	0.70	"
1,3,5-Trimethylbenzene	ND	0.49	"
1,3-Butadiene	ND	0.66	"
1,3-Dichlorobenzene	ND	0.60	"
1,3-Dichloropropane	ND	0.46	"
1,4-Dichlorobenzene	ND	0.60	"
1,4-Dioxane	ND	0.72	"
2-Butanone	ND	0.29	"
2-Hexanone	ND	0.82	"
3-Chloropropene	ND	1.6	"
4-Methyl-2-pentanone	ND	0.41	"
Acetone	ND	0.48	"
Acrylonitrile	ND	0.22	"
Benzene	ND	0.32	"
Benzyl chloride	ND	0.52	"
Bromodichloromethane	ND	0.67	"
Bromoform	ND	1.0	"
Bromomethane	ND	0.39	"
Carbon disulfide	ND	0.31	"
Carbon tetrachloride	ND	0.16	"
Chlorobenzene	ND	0.46	"
Chloroethane	ND	0.26	"
Chloroform	ND	0.49	"
Chloromethane	ND	0.21	"
cis-1,2-Dichloroethylene	ND	0.099	"
cis-1,3-Dichloropropylene	ND	0.45	"
Cyclohexane	ND	0.34	"
Dibromochloromethane	ND	0.85	"
Dichlorodifluoromethane	ND	0.49	"
Ethyl acetate	ND	0.72	"
Ethyl Benzene	ND	0.43	"
Hexachlorobutadiene	ND	1.1	"
Isopropanol	ND	0.49	"
Methyl Methacrylate	ND	0.41	"
Methyl tert-butyl ether (MTBE)	ND	0.36	"
Methylene chloride	ND	0.69	"



Volatile Organic Compounds in Air by GC/MS - Quality Control Data

York Analytical Laboratories, Inc.

Analyte	Result	Reporting Limit	Units	Spike Level	Source* Result	%REC	%REC Limits	Flag	RPD	RPD Limit	Flag
---------	--------	-----------------	-------	-------------	----------------	------	-------------	------	-----	-----------	------

Batch BD20955 - EPA TO15 PREP

Blank (BD20955-BLK1)

Prepared & Analyzed: 04/15/2022

n-Heptane	ND	0.41	ug/m ³
n-Hexane	ND	0.35	"
o-Xylene	ND	0.43	"
p- & m- Xylenes	ND	0.87	"
p-Ethyltoluene	ND	0.49	"
Propylene	ND	0.17	"
Styrene	ND	0.43	"
Tetrachloroethylene	ND	0.68	"
Tetrahydrofuran	ND	0.59	"
Toluene	ND	0.38	"
trans-1,2-Dichloroethylene	ND	0.40	"
trans-1,3-Dichloropropylene	ND	0.45	"
Trichloroethylene	ND	0.13	"
Trichlorofluoromethane (Freon 11)	ND	0.56	"
Vinyl acetate	ND	0.35	"
Vinyl bromide	ND	0.44	"
Vinyl Chloride	ND	0.13	"

LCS (BD20955-BS1)

Prepared & Analyzed: 04/15/2022

1,1,1,2-Tetrachloroethane	10.5		ppbv	10.0	105	70-130
1,1,1-Trichloroethane	10.9		"	10.0	109	70-130
1,1,2,2-Tetrachloroethane	10.2		"	10.0	102	70-130
1,1,2-Trichloro-1,2,2-trifluoroethane (Freon 113)	11.1		"	10.0	111	70-130
1,1,2-Trichloroethane	10.3		"	10.0	103	70-130
1,1-Dichloroethane	10.1		"	10.0	101	70-130
1,1-Dichloroethylene	10.4		"	10.0	104	70-130
1,2,4-Trichlorobenzene	8.80		"	10.0	88.0	70-130
1,2,4-Trimethylbenzene	9.99		"	10.0	99.9	70-130
1,2-Dibromoethane	10.1		"	10.0	101	70-130
1,2-Dichlorobenzene	10.7		"	10.0	107	70-130
1,2-Dichloroethane	10.3		"	10.0	103	70-130
1,2-Dichloropropane	9.50		"	10.0	95.0	70-130
1,2-Dichlorotetrafluoroethane	9.50		"	10.0	95.0	70-130
1,3,5-Trimethylbenzene	10.0		"	10.0	100	70-130
1,3-Butadiene	9.60		"	10.0	96.0	70-130
1,3-Dichlorobenzene	11.0		"	10.0	110	70-130
1,3-Dichloropropane	9.65		"	10.0	96.5	70-130
1,4-Dichlorobenzene	11.1		"	10.0	111	70-130
1,4-Dioxane	9.74		"	10.0	97.4	70-130
2-Butanone	9.81		"	10.0	98.1	70-130
2-Hexanone	9.48		"	10.0	94.8	70-130
3-Chloropropene	10.3		"	10.0	103	70-130
4-Methyl-2-pentanone	9.19		"	10.0	91.9	70-130
Acetone	8.85		"	10.0	88.5	70-130
Acrylonitrile	9.98		"	10.0	99.8	70-130
Benzene	10.4		"	10.0	104	70-130
Benzyl chloride	8.69		"	10.0	86.9	70-130
Bromodichloromethane	10.3		"	10.0	103	70-130
Bromoform	11.4		"	10.0	114	70-130
Bromomethane	11.0		"	10.0	110	70-130
Carbon disulfide	10.3		"	10.0	103	70-130



Volatile Organic Compounds in Air by GC/MS - Quality Control Data

York Analytical Laboratories, Inc.

Analyte	Result	Reporting Limit	Units	Spike Level	Source* Result	%REC	%REC Limits	Flag	RPD	RPD Limit	Flag
---------	--------	--------------------	-------	----------------	-------------------	------	----------------	------	-----	--------------	------

Batch BD20955 - EPA TO15 PREP

LCS (BD20955-BS1)

Prepared & Analyzed: 04/15/2022

Carbon tetrachloride	11.7		ppbv	10.0		117	70-130				
Chlorobenzene	9.91		"	10.0		99.1	70-130				
Chloroethane	10.5		"	10.0		105	70-130				
Chloroform	10.6		"	10.0		106	70-130				
Chloromethane	8.81		"	10.0		88.1	70-130				
cis-1,2-Dichloroethylene	10.0		"	10.0		100	70-130				
cis-1,3-Dichloropropylene	10.1		"	10.0		101	70-130				
Cyclohexane	10.2		"	10.0		102	70-130				
Dibromochloromethane	10.8		"	10.0		108	70-130				
Dichlorodifluoromethane	10.4		"	10.0		104	70-130				
Ethyl acetate	10.1		"	10.0		101	70-130				
Ethyl Benzene	9.83		"	10.0		98.3	70-130				
Hexachlorobutadiene	11.2		"	10.0		112	70-130				
Isopropanol	9.32		"	10.0		93.2	70-130				
Methyl Methacrylate	9.51		"	10.0		95.1	70-130				
Methyl tert-butyl ether (MTBE)	10.5		"	10.0		105	70-130				
Methylene chloride	9.00		"	10.0		90.0	70-130				
n-Heptane	10.1		"	10.0		101	70-130				
n-Hexane	10.5		"	10.0		105	70-130				
o-Xylene	9.87		"	10.0		98.7	70-130				
p- & m- Xylenes	20.1		"	20.0		100	70-130				
p-Ethyltoluene	10.3		"	10.0		103	70-130				
Propylene	9.52		"	10.0		95.2	70-130				
Styrene	10.5		"	10.0		105	70-130				
Tetrachloroethylene	8.93		"	10.0		89.3	70-130				
Tetrahydrofuran	8.11		"	10.0		81.1	70-130				
Toluene	9.69		"	10.0		96.9	70-130				
trans-1,2-Dichloroethylene	10.4		"	10.0		104	70-130				
trans-1,3-Dichloropropylene	10.0		"	10.0		100	70-130				
Trichloroethylene	9.98		"	10.0		99.8	70-130				
Trichlorofluoromethane (Freon 11)	11.0		"	10.0		110	70-130				
Vinyl acetate	10.1		"	10.0		101	70-130				
Vinyl bromide	11.2		"	10.0		112	70-130				
Vinyl Chloride	9.16		"	10.0		91.6	70-130				



Volatile Organic Compounds in Air by GC/MS - Quality Control Data

York Analytical Laboratories, Inc.

Analyte	Result	Reporting Limit	Units	Spike Level	Source* Result	%REC	%REC Limits	Flag	RPD	Limit	Flag
Batch BD20955 - EPA TO15 PREP											
Duplicate (BD20955-DUP1)	*Source sample: 22D0767-01 (Duplicate)						Prepared: 04/15/2022 Analyzed: 04/16/2022				
1,1,1,2-Tetrachloroethane	ND	0.69	ug/m ³		ND					25	
1,1,1-Trichloroethane	2.9	0.55	"		3.5				20.3	25	
1,1,2,2-Tetrachloroethane	ND	0.69	"		ND					25	
1,1,2-Trichloro-1,2,2-trifluoroethane (Freon 113)	1.6	0.77	"		2.0				21.3	25	
1,1,2-Trichloroethane	ND	0.55	"		ND					25	
1,1-Dichloroethane	0.45	0.40	"		0.57				24.0	25	
1,1-Dichloroethylene	ND	0.099	"		ND					25	
1,2,4-Trichlorobenzene	ND	0.74	"		ND					25	
1,2,4-Trimethylbenzene	0.64	0.49	"		0.64				0.00	25	
1,2-Dibromoethane	ND	0.77	"		ND					25	
1,2-Dichlorobenzene	ND	0.60	"		ND					25	
1,2-Dichloroethane	ND	0.40	"		ND					25	
1,2-Dichloropropane	ND	0.46	"		ND					25	
1,2-Dichlorotetrafluoroethane	ND	0.70	"		ND					25	
1,3,5-Trimethylbenzene	ND	0.49	"		ND					25	
1,3-Butadiene	ND	0.66	"		ND					25	
1,3-Dichlorobenzene	ND	0.60	"		ND					25	
1,3-Dichloropropane	ND	0.46	"		ND					25	
1,4-Dichlorobenzene	ND	0.60	"		ND					25	
1,4-Dioxane	ND	0.72	"		ND					25	
2-Butanone	2.2	0.29	"		2.3				3.97	25	
2-Hexanone	ND	0.82	"		ND					25	
3-Chloropropene	ND	1.6	"		ND					25	
4-Methyl-2-pentanone	0.74	0.41	"		0.66				11.8	25	
Acetone	39	0.48	"		40				2.11	25	
Acrylonitrile	ND	0.22	"		ND					25	
Benzene	0.73	0.32	"		0.77				4.26	25	
Benzyl chloride	ND	0.52	"		ND					25	
Bromodichloromethane	ND	0.67	"		ND					25	
Bromoform	ND	1.0	"		ND					25	
Bromomethane	ND	0.39	"		ND					25	
Carbon disulfide	ND	0.31	"		ND					25	
Carbon tetrachloride	0.44	0.16	"		0.44				0.00	25	
Chlorobenzene	ND	0.46	"		ND					25	
Chloroethane	ND	0.26	"		ND					25	
Chloroform	2.1	0.49	"		2.5				14.7	25	
Chloromethane	0.35	0.21	"		0.35				0.00	25	
cis-1,2-Dichloroethylene	0.20	0.099	"		0.28				33.3	25	Non-dir.
cis-1,3-Dichloropropylene	ND	0.45	"		ND					25	
Cyclohexane	0.55	0.34	"		0.62				11.8	25	
Dibromochloromethane	ND	0.85	"		ND					25	
Dichlorodifluoromethane	4.0	0.49	"		3.2				21.9	25	
Ethyl acetate	1.4	0.72	"		1.4				2.53	25	
Ethyl Benzene	1.6	0.43	"		1.8				12.7	25	
Hexachlorobutadiene	ND	1.1	"		ND					25	
Isopropanol	24	0.49	"		19				25.8	25	Non-dir.
Methyl Methacrylate	ND	0.41	"		ND					25	
Methyl tert-butyl ether (MTBE)	ND	0.36	"		ND					25	
Methylene chloride	1.4	0.69	"		0.94				41.2	25	Non-dir.
n-Heptane	0.70	0.41	"		0.70				0.00	25	



Volatile Organic Compounds in Air by GC/MS - Quality Control Data

York Analytical Laboratories, Inc.

Analyte	Result	Reporting Limit	Units	Spike Level	Source* Result	%REC	%REC Limits	Flag	RPD	RPD Limit	Flag
---------	--------	-----------------	-------	-------------	----------------	------	-------------	------	-----	-----------	------

Batch BD20955 - EPA TO15 PREP

Duplicate (BD20955-DUP1)		*Source sample: 22D0767-01 (Duplicate)				Prepared: 04/15/2022 Analyzed: 04/16/2022					
n-Hexane	1.5	0.35	ug/m ³		1.8				15.1	25	
o-Xylene	1.7	0.43	"		1.9				9.76	25	
p- & m- Xylenes	5.5	0.87	"		6.3				13.2	25	
p-Ethyltoluene	0.54	0.49	"		0.54				0.00	25	
Propylene	ND	0.17	"		ND					25	
Styrene	0.47	0.43	"		0.51				8.70	25	
Tetrachloroethylene	38	0.68	"		43				13.3	25	
Tetrahydrofuran	0.77	0.59	"		0.80				3.77	25	
Toluene	12	0.38	"		13				6.28	25	
trans-1,2-Dichloroethylene	ND	0.40	"		ND					25	
trans-1,3-Dichloropropylene	ND	0.45	"		ND					25	
Trichloroethylene	11	0.13	"		14				21.9	25	
Trichlorofluoromethane (Freon 11)	1.3	0.56	"		1.6				23.1	25	
Vinyl acetate	ND	0.35	"		ND					25	
Vinyl bromide	ND	0.44	"		ND					25	
Vinyl Chloride	ND	0.13	"		ND					25	

Batch BD21003 - EPA TO15 PREP

Blank (BD21003-BLK1)		Prepared & Analyzed: 04/17/2022									
1,1,1,2-Tetrachloroethane	ND	0.69	ug/m ³								
1,1,1-Trichloroethane	ND	0.55	"								
1,1,2,2-Tetrachloroethane	ND	0.69	"								
1,1,2-Trichloro-1,2,2-trifluoroethane (Freon 113)	ND	0.77	"								
1,1,2-Trichloroethane	ND	0.55	"								
1,1-Dichloroethane	ND	0.40	"								
1,1-Dichloroethylene	ND	0.099	"								
1,2,4-Trichlorobenzene	ND	0.74	"								
1,2,4-Trimethylbenzene	ND	0.49	"								
1,2-Dibromoethane	ND	0.77	"								
1,2-Dichlorobenzene	ND	0.60	"								
1,2-Dichloroethane	ND	0.40	"								
1,2-Dichloropropane	ND	0.46	"								
1,2-Dichlorotetrafluoroethane	ND	0.70	"								
1,3,5-Trimethylbenzene	ND	0.49	"								
1,3-Butadiene	ND	0.66	"								
1,3-Dichlorobenzene	ND	0.60	"								
1,3-Dichloropropane	ND	0.46	"								
1,4-Dichlorobenzene	ND	0.60	"								
1,4-Dioxane	ND	0.72	"								
2-Butanone	ND	0.29	"								
2-Hexanone	ND	0.82	"								
3-Chloropropene	ND	1.6	"								
4-Methyl-2-pentanone	ND	0.41	"								
Acetone	ND	0.48	"								
Acrylonitrile	ND	0.22	"								
Benzene	ND	0.32	"								
Benzyl chloride	ND	0.52	"								
Bromodichloromethane	ND	0.67	"								
Bromoform	ND	1.0	"								
Bromomethane	ND	0.39	"								



Volatile Organic Compounds in Air by GC/MS - Quality Control Data

York Analytical Laboratories, Inc.

Analyte	Result	Reporting Limit	Units	Spike Level	Source* Result	%REC	%REC Limits	Flag	RPD	RPD Limit	Flag
---------	--------	--------------------	-------	----------------	-------------------	------	----------------	------	-----	--------------	------

Batch BD21003 - EPA TO15 PREP

Blank (BD21003-BLK1)

Prepared & Analyzed: 04/17/2022

Carbon disulfide	ND	0.31	ug/m ³
Carbon tetrachloride	ND	0.16	"
Chlorobenzene	ND	0.46	"
Chloroethane	ND	0.26	"
Chloroform	ND	0.49	"
Chloromethane	ND	0.21	"
cis-1,2-Dichloroethylene	ND	0.099	"
cis-1,3-Dichloropropylene	ND	0.45	"
Cyclohexane	ND	0.34	"
Dibromochloromethane	ND	0.85	"
Dichlorodifluoromethane	ND	0.49	"
Ethyl acetate	ND	0.72	"
Ethyl Benzene	ND	0.43	"
Hexachlorobutadiene	ND	1.1	"
Isopropanol	ND	0.49	"
Methyl Methacrylate	ND	0.41	"
Methyl tert-butyl ether (MTBE)	ND	0.36	"
Methylene chloride	ND	0.69	"
n-Heptane	ND	0.41	"
n-Hexane	ND	0.35	"
o-Xylene	ND	0.43	"
p- & m- Xylenes	ND	0.87	"
p-Ethyltoluene	ND	0.49	"
Propylene	ND	0.17	"
Styrene	ND	0.43	"
Tetrachloroethylene	ND	0.68	"
Tetrahydrofuran	ND	0.59	"
Toluene	ND	0.38	"
trans-1,2-Dichloroethylene	ND	0.40	"
trans-1,3-Dichloropropylene	ND	0.45	"
Trichloroethylene	ND	0.13	"
Trichlorofluoromethane (Freon 11)	ND	0.56	"
Vinyl acetate	ND	0.35	"
Vinyl bromide	ND	0.44	"
Vinyl Chloride	ND	0.13	"



Volatile Organic Compounds in Air by GC/MS - Quality Control Data

York Analytical Laboratories, Inc.

Analyte	Result	Reporting Limit	Units	Spike Level	Source* Result	%REC	%REC Limits	Flag	RPD	RPD Limit	Flag
Batch BD21003 - EPA TO15 PREP											
LCS (BD21003-BS1)						Prepared & Analyzed: 04/17/2022					
1,1,1,2-Tetrachloroethane	11.4		ppbv	10.0		114	70-130				
1,1,1-Trichloroethane	11.6		"	10.0		116	70-130				
1,1,2,2-Tetrachloroethane	11.0		"	10.0		110	70-130				
1,1,2-Trichloro-1,2,2-trifluoroethane (Freon 113)	12.1		"	10.0		121	70-130				
1,1,2-Trichloroethane	11.1		"	10.0		111	70-130				
1,1-Dichloroethane	11.4		"	10.0		114	70-130				
1,1-Dichloroethylene	11.7		"	10.0		117	70-130				
1,2,4-Trichlorobenzene	7.00		"	10.0		70.0	70-130				
1,2,4-Trimethylbenzene	11.1		"	10.0		111	70-130				
1,2-Dibromoethane	11.1		"	10.0		111	70-130				
1,2-Dichlorobenzene	11.4		"	10.0		114	70-130				
1,2-Dichloroethane	11.6		"	10.0		116	70-130				
1,2-Dichloropropane	10.6		"	10.0		106	70-130				
1,2-Dichlorotetrafluoroethane	11.8		"	10.0		118	70-130				
1,3,5-Trimethylbenzene	11.1		"	10.0		111	70-130				
1,3-Butadiene	11.6		"	10.0		116	70-130				
1,3-Dichlorobenzene	11.9		"	10.0		119	70-130				
1,3-Dichloropropane	10.8		"	10.0		108	70-130				
1,4-Dichlorobenzene	11.9		"	10.0		119	70-130				
1,4-Dioxane	9.70		"	10.0		97.0	70-130				
2-Butanone	10.8		"	10.0		108	70-130				
2-Hexanone	9.58		"	10.0		95.8	70-130				
3-Chloropropene	11.1		"	10.0		111	70-130				
4-Methyl-2-pentanone	9.96		"	10.0		99.6	70-130				
Acetone	10.1		"	10.0		101	70-130				
Acrylonitrile	10.7		"	10.0		107	70-130				
Benzene	11.3		"	10.0		113	70-130				
Benzyl chloride	8.19		"	10.0		81.9	70-130				
Bromodichloromethane	11.4		"	10.0		114	70-130				
Bromoform	11.9		"	10.0		119	70-130				
Bromomethane	12.6		"	10.0		126	70-130				
Carbon disulfide	11.5		"	10.0		115	70-130				
Carbon tetrachloride	12.4		"	10.0		124	70-130				
Chlorobenzene	11.1		"	10.0		111	70-130				
Chloroethane	11.7		"	10.0		117	70-130				
Chloroform	11.7		"	10.0		117	70-130				
Chloromethane	11.0		"	10.0		110	70-130				
cis-1,2-Dichloroethylene	11.1		"	10.0		111	70-130				
cis-1,3-Dichloropropylene	10.8		"	10.0		108	70-130				
Cyclohexane	11.0		"	10.0		110	70-130				
Dibromochloromethane	11.8		"	10.0		118	70-130				
Dichlorodifluoromethane	12.1		"	10.0		121	70-130				
Ethyl acetate	10.8		"	10.0		108	70-130				
Ethyl Benzene	11.0		"	10.0		110	70-130				
Hexachlorobutadiene	11.1		"	10.0		111	70-130				
Isopropanol	10.1		"	10.0		101	70-130				
Methyl Methacrylate	10.5		"	10.0		105	70-130				
Methyl tert-butyl ether (MTBE)	11.5		"	10.0		115	70-130				
Methylene chloride	10.1		"	10.0		101	70-130				
n-Heptane	11.1		"	10.0		111	70-130				



Volatile Organic Compounds in Air by GC/MS - Quality Control Data

York Analytical Laboratories, Inc.

Analyte	Result	Reporting Limit	Units	Spike Level	Source* Result	%REC	%REC Limits	Flag	RPD	RPD Limit	Flag
---------	--------	-----------------	-------	-------------	----------------	------	-------------	------	-----	-----------	------

Batch BD21003 - EPA TO15 PREP

LCS (BD21003-BS1)

Prepared & Analyzed: 04/17/2022

n-Hexane	11.3		ppbv	10.0		113	70-130				
o-Xylene	11.1		"	10.0		111	70-130				
p- & m- Xylenes	22.4		"	20.0		112	70-130				
p-Ethyltoluene	11.5		"	10.0		115	70-130				
Propylene	10.9		"	10.0		109	70-130				
Styrene	11.5		"	10.0		115	70-130				
Tetrachloroethylene	9.70		"	10.0		97.0	70-130				
Tetrahydrofuran	9.06		"	10.0		90.6	70-130				
Toluene	10.9		"	10.0		109	70-130				
trans-1,2-Dichloroethylene	11.4		"	10.0		114	70-130				
trans-1,3-Dichloropropylene	10.6		"	10.0		106	70-130				
Trichloroethylene	11.2		"	10.0		112	70-130				
Trichlorofluoromethane (Freon 11)	12.4		"	10.0		124	70-130				
Vinyl acetate	10.5		"	10.0		105	70-130				
Vinyl bromide	12.2		"	10.0		122	70-130				
Vinyl Chloride	11.3		"	10.0		113	70-130				

Duplicate (BD21003-DUP1)

*Source sample: 22D0395-05 (Duplicate)

Prepared & Analyzed: 04/17/2022

1,1,1,2-Tetrachloroethane	ND	0.63	ug/m ³		ND					25	
1,1,1-Trichloroethane	ND	0.50	"		ND					25	
1,1,2,2-Tetrachloroethane	ND	0.63	"		ND					25	
1,1,2-Trichloro-1,2,2-trifluoroethane (Freon 113)	ND	0.71	"		ND					25	
1,1,2-Trichloroethane	ND	0.50	"		ND					25	
1,1-Dichloroethane	ND	0.37	"		ND					25	
1,1-Dichloroethylene	ND	0.091	"		ND					25	
1,2,4-Trichlorobenzene	ND	0.68	"		ND					25	
1,2,4-Trimethylbenzene	0.59	0.45	"		0.54				8.00	25	
1,2-Dibromoethane	ND	0.71	"		ND					25	
1,2-Dichlorobenzene	ND	0.55	"		ND					25	
1,2-Dichloroethane	ND	0.37	"		ND					25	
1,2-Dichloropropane	ND	0.43	"		ND					25	
1,2-Dichlorotetrafluoroethane	ND	0.65	"		ND					25	
1,3,5-Trimethylbenzene	ND	0.45	"		ND					25	
1,3-Butadiene	0.082	0.61	"		ND					25	
1,3-Dichlorobenzene	ND	0.55	"		ND					25	
1,3-Dichloropropane	ND	0.43	"		ND					25	
1,4-Dichlorobenzene	ND	0.55	"		ND					25	
1,4-Dioxane	ND	0.67	"		ND					25	
2-Butanone	1.0	0.27	"		0.98				2.74	25	
2-Hexanone	ND	0.76	"		ND					25	
3-Chloropropene	ND	1.4	"		ND					25	
4-Methyl-2-pentanone	0.34	0.38	"		ND					25	
Acetone	7.1	0.44	"		7.1				0.927	25	
Acrylonitrile	ND	0.20	"		ND					25	
Benzene	0.74	0.29	"		0.74				0.00	25	
Benzyl chloride	ND	0.48	"		ND					25	
Bromodichloromethane	ND	0.62	"		ND					25	
Bromoform	ND	0.95	"		ND					25	
Bromomethane	ND	0.36	"		ND					25	
Carbon disulfide	ND	0.29	"		ND					25	
Carbon tetrachloride	0.46	0.15	"		0.52				11.8	25	




Volatile Organic Compounds in Air by GC/MS - Quality Control Data

York Analytical Laboratories, Inc.

Analyte	Result	Reporting Limit	Units	Spike Level	Source* Result	%REC	%REC Limits	Flag	RPD	RPD Limit	Flag
---------	--------	-----------------	-------	-------------	----------------	------	-------------	------	-----	-----------	------

Batch BD21003 - EPA TO15 PREP

Duplicate (BD21003-DUP1)		*Source sample: 22D0395-05 (Duplicate)				Prepared & Analyzed: 04/17/2022					
Chlorobenzene	ND	0.42	ug/m ³		ND					25	
Chloroethane	ND	0.24	"		ND					25	
Chloroform	ND	0.45	"		ND					25	
Chloromethane	1.7	0.19	"		1.3				27.5	25	Non-dir.
cis-1,2-Dichloroethylene	ND	0.091	"		ND					25	
cis-1,3-Dichloropropylene	ND	0.42	"		ND					25	
Cyclohexane	0.38	0.32	"		0.38				0.00	25	
Dibromochloromethane	ND	0.79	"		ND					25	
Dichlorodifluoromethane	2.9	0.46	"		2.7				6.56	25	
Ethyl acetate	0.27	0.67	"		0.27				0.00	25	
Ethyl Benzene	0.60	0.40	"		0.60				0.00	25	
Hexachlorobutadiene	ND	0.98	"		ND					25	
Isopropanol	1.1	0.45	"		0.82				30.6	25	Non-dir.
Methyl Methacrylate	0.19	0.38	"		ND					25	
Methyl tert-butyl ether (MTBE)	ND	0.33	"		ND					25	
Methylene chloride	3.2	0.64	"		3.1				1.02	25	
n-Heptane	0.53	0.38	"		0.53				0.00	25	
n-Hexane	0.78	0.33	"		0.78				0.00	25	
o-Xylene	0.72	0.40	"		0.68				5.71	25	
p- & m- Xylenes	2.1	0.80	"		2.0				5.94	25	
p-Ethyltoluene	0.54	0.45	"		0.50				8.70	25	
Propylene	ND	0.16	"		ND					25	
Styrene	ND	0.39	"		ND					25	
Tetrachloroethylene	0.44	0.63	"		0.50				13.3	25	
Tetrahydrofuran	0.63	0.54	"		0.60				4.44	25	
Toluene	4.0	0.35	"		3.9				3.51	25	
trans-1,2-Dichloroethylene	ND	0.37	"		ND					25	
trans-1,3-Dichloropropylene	ND	0.42	"		ND					25	
Trichloroethylene	ND	0.12	"		ND					25	
Trichlorofluoromethane (Freon 11)	1.5	0.52	"		1.6				3.39	25	
Vinyl acetate	ND	0.32	"		ND					25	
Vinyl bromide	ND	0.40	"		ND					25	
Vinyl Chloride	ND	0.12	"		ND					25	





Sample and Data Qualifiers Relating to This Work Order

- QR-02 The RPD result exceeded the QC control limits; however, both percent recoveries were acceptable. Sample results for the QC batch were accepted based on percent recoveries and completeness of QC data.
- QR-01 Analyses are not controlled on RPD values from sample concentrations less than 10 times the reporting limit. QC batch accepted based on LCS and/or LCSD QC results.

Definitions and Other Explanations

- * Analyte is not certified or the state of the samples origination does not offer certification for the Analyte.
- ND NOT DETECTED - the analyte is not detected at the Reported to level (LOQ/RL or LOD/MDL)
- RL REPORTING LIMIT - the minimum reportable value based upon the lowest point in the analyte calibration curve.
- LOQ LIMIT OF QUANTITATION - the minimum concentration of a target analyte that can be reported within a specified degree of confidence. This is the lowest point in an analyte calibration curve that has been subjected to all steps of the processing/analysis and verified to meet defined criteria. This is based upon NELAC 2009 Standards and applies to all analyses.
- LOD LIMIT OF DETECTION - a verified estimate of the minimum concentration of a substance in a given matrix that an analytical process can reliably detect. This is based upon NELAC 2009 Standards and applies to all analyses conducted under the auspices of EPA SW-846.
- MDL METHOD DETECTION LIMIT - a statistically derived estimate of the minimum amount of a substance an analytical system can reliably detect with a 99% confidence that the concentration of the substance is greater than zero. This is based upon 40 CFR Part 136 Appendix B and applies only to EPA 600 and 200 series methods.
- Reported to This indicates that the data for a particular analysis is reported to either the LOD/MDL, or the LOQ/RL. In cases where the "Reported to" is located above the LOD/MDL, any value between this and the LOQ represents an estimated value which is "J" flagged accordingly. This applies to volatile and semi-volatile target compounds only.
- NR Not reported
- RPD Relative Percent Difference
- Wet The data has been reported on an as-received (wet weight) basis
- Low Bias Low Bias flag indicates that the recovery of the flagged analyte is below the laboratory or regulatory lower control limit. The data user should take note that this analyte may be biased low but should evaluate multiple lines of evidence including the LCS and site-specific MS/MSD data to draw bias conclusions. In cases where no site-specific MS/MSD was requested, only the LCS data can be used to evaluate such bias.
- High Bias High Bias flag indicates that the recovery of the flagged analyte is above the laboratory or regulatory upper control limit. The data user should take note that this analyte may be biased high but should evaluate multiple lines of evidence including the LCS and site-specific MS/MSD data to draw bias conclusions. In cases where no site-specific MS/MSD was requested, only the LCS data can be used to evaluate such bias.
- Non-Dir. Non-dir. flag (Non-Directional Bias) indicates that the Relative Percent Difference (RPD) (a measure of precision) among the MS and MSD data is outside the laboratory or regulatory control limit. This alerts the data user where the MS and MSD are from site-specific samples that the RPD is high due to either non-homogeneous distribution of target analyte between the MS/MSD or indicates poor reproducibility for other reasons.


If EPA SW-846 method 8270 is included herein it is noted that the target compound N-nitrosodiphenylamine (NDPA) decomposes in the gas chromatographic inlet and cannot be separated from diphenylamine (DPA). These results could actually represent 100% DPA, 100% NDPA or some combination of the two. For this reason, York reports the combined result for n-nitrosodiphenylamine and diphenylamine for either of these compounds as a combined concentration as Diphenylamine.

If Total PCBs are detected and the target aroclors reported are "Not detected", the Total PCB value is reported due to the presence of either or both Aroclors 1262 and 1268 which are non-target aroclors for some regulatory lists.

2-chloroethylvinyl ether readily breaks down under acidic conditions. Samples that are acid preserved, including standards will exhibit breakdown. The data user should take note.

Certification for pH is no longer offered by NYDOH ELAP.

Semi-Volatile and Volatile analyses are reported down to the LOD/MDL, with values between the LOD/MDL and the LOQ being "J" flagged as estimated results.



For analyses by EPA SW-846-8270D, the Limit of Quantitation (LOQ) reported for benzidine is based upon the lowest standard used for calibration and is not a verified LOQ due to this compound's propensity for oxidative losses during extraction/concentration procedures and non-reproducible chromatographic performance.



York Analytical Laboratories, Inc.
120 Research Drive
Stratford, CT 06615
clientservices@yorklab.com
www.yorklab.com

Field Chain-of-Custody Record - AIR

YORK Project No.
2200083

NOTE: YORK's Standard Terms & Conditions are listed on the back side of this document.
This document serves as your written authorization for YORK to proceed with the analyses requested below.
signature binds you to YORK's Standard Terms & Conditions.

Your

Page 1 of 1

YOUR INFORMATION		Report To:		Invoice To:		YOUR Project Number		Turn-Around Time	
Company:	OT Consulting Services Inc	Company:	Same	Company:	Same	356060		RUSH - Next Day	
Address:		Address:		Address:				RUSH - Two Day	
Phone:		Phone:		Phone:				RUSH - Three Day	
Contact:		Contact:		Contact:				RUSH - Four Day	
E-mail:		E-mail:		E-mail:				Standard (5-7 Day)	
Deborah Thompson		Deborah Thompson		Deborah Thompson		66 Albany Avenue Kingston, New York		X	
Please print clearly and legibly. All information must be complete. Samples will not be logged in and the turn-around-time clock will not begin until any questions by YORK are resolved.		Air Matrix Codes		Samples From		Report / EDD Type (circle selections)		YORK Reg. Comp.	
		AI - Indoor Ambient Air		New York		CT RCP		Compared to the following Regulation(s): (please fill in)	
		AO - Outdoor Ambient Air		New Jersey		CT RCP DQA/DUE		Standard Excel EDD	
		AE - Vapor Extraction Well/Process Gas/Effluent		Connecticut		NJDEP Reduced Deliv.		EQUIS (Standard)	
		AS - Soil Vapor/Sub-Slab		Pennsylvania		NY ASP A Package		NYSDEC EQUIS	
				Other		NY ASP B Package		NJDEP SRP HazSite	
				Other:					
Certified Canisters: Batch 1 Individual		Please enter the following REQUIRED Field Data							
Sample Identification	Date/Time Sampled	Air Matrix	Canister Vacuum Before Sampling (in Hg)	Canister Vacuum After Sampling (in Hg)	Canister ID	Flow Cont. ID	Reporting Units: ug/m ³ ppbv ppmv	Analysis Requested	
EW-1	4/3/22 10:23 AM	AS	-30	-7	10748			TO-15	
EW-2	11:40 AM		-26	-6	18307				
EW-3	1:09 PM		-30	-8	3793				
EW-4	2:12 PM		-30	-7	10613				
EW-5	3:04 PM		-30	-8	16976				
Comments:									
Detection Limits Required									
≤ 1 ug/m ³ NYSEDEC V1 Limits									
Routine Survey Other									
Sampling Media									
6 Liter Canister Tedlar Bag									
Date/Time									
4/4/22 11:13 Andrew S. Gore									
Date/Time									
4/4/22 14:43									

APPENDIX E
AERSCREEN MODEL DATA INPUTS

Appendix D - AERSCREEN MODEL DATA INPUT - METHYLENE CHLORIDE

Max 1- Hour Concentr ation [µg/m³]	Distance [m]	Elevation [m]	Season/ Month	Surface Roughnes s Sector Number	Date	Heat Flux [W/m²]	Friction Velocity [m/s]	Convectiv e Velocity [m/s]	Lapse Rate [K/m]	Convectiv e Mixing Height [m]	Mechanic al Mixing Height [m]	Monin- Obukhov Length [m]	Surface Roughnes s Length [m]	Bowen Ratio	Albedo	Wind Speed [m/s]	Anemom eter Height [m]	Temperat ure [°K]	Height of Temperat ure [m]
1.66E-02	3.05	0	Summer	0	10021812	330.06	0.193	1.8	0.02	673	195	-2.1	1	2	0.16	0.5	10	310	2
4.63E-02	5	0	Summer	0	10021812	330.06	0.193	1.8	0.02	673	195	-2.1	1	2	0.16	0.5	10	310	2
1.46E-02	25	0	Winter	0	10011201	-1.3	0.043	-9	0.02	-999	208	6	1	1.5	0.35	0.5	10	310	2

Appendix D - AERSCREEN MODEL DATA INPUT - PCE

Max 1-Hour Concentration [µg/m³]	Distance [m]	Elevation [m]	Season/ Month	Surface Roughness Sector Number	Date	Heat Flux [W/m²]	Friction Velocity [m/s]	Convective Velocity [m/s]	Lapse Rate [K/m]	Convective Mixing Height [m]	Mechanical Mixing Height [m]	Monin-Obukhov Length [m]	Surface Roughness Length [m]	Bowen Ratio	Albedo	Wind Speed [m/s]	Anemometer Height [m]	Temperature [°K]	Height of Temperature [m]
2.99E+00	3.05	0	Summer	0	10021812	330.06	0.193	1.8	0.02	673	195	-2.1	1	2	0.16	0.5	10	310	2
8.32E+00	5	0	Summer	0	10021812	330.06	0.193	1.8	0.02	673	195	-2.1	1	2	0.16	0.5	10	310	2
2.63E+00	25	0	Winter	0	10011201	-1.3	0.043	-9	0.02	-999	208	6	1	1.5	0.35	0.5	10	310	2

Appendix D - AERSCREEN MODEL DATA INPUT - TCE

Max 1- Hour Concentr ation [µg/m³]	Distance [m]	Elevation [m]	Season/ Month	Surface Roughnes s Sector Number	Date	Heat Flux [W/m²]	Friction Velocity [m/s]	Convectiv e Velocity [m/s]	Lapse Rate [K/m]	Convectiv e Mixing Height [m]	Mechanic al Mixing Height [m]	Monin- Obukhov Length [m]	Surface Roughnes s Length [m]	Bowen Ratio	Albedo	Wind Speed [m/s]	Anemom eter Height [m]	Temperat ure [°K]	Height of Temperat ure [m]
1.03E-03	3.05	0	Summer	0	10021812	330.06	0.193	1.8	0.02	673	195	-2.1	1	2	0.16	0.5	10	310	2
2.87E-03	5	0	Summer	0	10021812	330.06	0.193	1.8	0.02	673	195	-2.1	1	2	0.16	0.5	10	310	2
9.06E-04	25	0	Winter	0	10011201	-1.3	0.043	-9	0.02	-999	208	6	1	1.5	0.35	0.5	10	310	2

APPENDIX F
NYSDOH INDOOR AIR QUALITY QUESTIONNAIRE AND BUILDING INVENTORY
FORM

**NEW YORK STATE DEPARTMENT OF HEALTH
INDOOR AIR QUALITY QUESTIONNAIRE AND BUILDING INVENTORY
CENTER FOR ENVIRONMENTAL HEALTH**

This form must be completed for each residence involved in indoor air testing.

Preparer's Name _____ Date/Time Prepared _____

Preparer's Affiliation _____ Phone No. _____

Purpose of Investigation _____

1. OCCUPANT:

Interviewed: Y / N

Last Name: _____ First Name: _____

Address: _____

County: _____

Home Phone: _____ Office Phone: _____

Number of Occupants/persons at this location _____ Age of Occupants _____

2. OWNER OR LANDLORD: (Check if same as occupant ____)

Interviewed: Y / N

Last Name: _____ First Name: _____

Address: _____

County: _____

Home Phone: _____ Office Phone: _____

3. BUILDING CHARACTERISTICS

Type of Building: (Circle appropriate response)

Residential
Industrial

School
Church

Commercial/Multi-use
Other: _____

If the property is residential, type? (Circle appropriate response)

Ranch	2-Family	3-Family
Raised Ranch	Split Level	Colonial
Cape Cod	Contemporary	Mobile Home
Duplex	Apartment House	Townhouses/Condos
Modular	Log Home	Other: _____

If multiple units, how many? _____

If the property is commercial, type?

Business Type(s) _____

Does it include residences (i.e., multi-use)? Y / N If yes, how many? _____

Other characteristics:

Number of floors _____ Building age _____

Is the building insulated? Y / N How air tight? Tight / Average / Not Tight

4. AIRFLOW

Use air current tubes or tracer smoke to evaluate airflow patterns and qualitatively describe:

Airflow between floors

Airflow near source

Outdoor air infiltration

Infiltration into air ducts

5. BASEMENT AND CONSTRUCTION CHARACTERISTICS (Circle all that apply)

- a. Above grade construction: wood frame concrete stone brick
- b. Basement type: full crawlspace slab other _____
- c. Basement floor: concrete dirt stone other _____
- d. Basement floor: uncovered covered covered with _____
- e. Concrete floor: unsealed sealed sealed with _____
- f. Foundation walls: poured block stone other _____
- g. Foundation walls: unsealed sealed sealed with _____
- h. The basement is: wet damp dry moldy
- i. The basement is: finished unfinished partially finished
- j. Sump present? Y / N
- k. Water in sump? Y / N / not applicable

Basement/Lowest level depth below grade: _____(feet)

Identify potential soil vapor entry points and approximate size (e.g., cracks, utility ports, drains)

6. HEATING, VENTING and AIR CONDITIONING (Circle all that apply)

Type of heating system(s) used in this building: (circle all that apply – note primary)

Hot air circulation	Heat pump	Hot water baseboard	
Space Heaters	Stream radiation	Radiant floor	
Electric baseboard	Wood stove	Outdoor wood boiler	Other _____

The primary type of fuel used is:

Natural Gas	Fuel Oil	Kerosene
Electric	Propane	Solar
Wood	Coal	

Domestic hot water tank fueled by: _____

Boiler/furnace located in: Basement Outdoors Main Floor Other _____

Air conditioning: Central Air Window units Open Windows None

Are there air distribution ducts present? Y / N

Describe the supply and cold air return ductwork, and its condition where visible, including whether there is a cold air return and the tightness of duct joints. Indicate the locations on the floor plan diagram.

7. OCCUPANCY

Is basement/lowest level occupied? Full-time Occasionally Seldom Almost Never

Level **General Use of Each Floor (e.g., familyroom, bedroom, laundry, workshop, storage)**

Basement	<hr/>
1 st Floor	<hr/>
2 nd Floor	<hr/>
3 rd Floor	<hr/>
4 th Floor	<hr/>

8. FACTORS THAT MAY INFLUENCE INDOOR AIR QUALITY

- | | |
|--|------------------------------------|
| a. Is there an attached garage? | Y / N |
| b. Does the garage have a separate heating unit? | Y / N / NA |
| c. Are petroleum-powered machines or vehicles stored in the garage (e.g., lawnmower, atv, car) | Y / N / NA
Please specify <hr/> |
| d. Has the building ever had a fire? | Y / N When? <hr/> |
| e. Is a kerosene or unvented gas space heater present? | Y / N Where? <hr/> |
| f. Is there a workshop or hobby/craft area? | Y / N Where & Type? <hr/> |
| g. Is there smoking in the building? | Y / N How frequently? <hr/> |
| h. Have cleaning products been used recently? | Y / N When & Type? <hr/> |
| i. Have cosmetic products been used recently? | Y / N When & Type? <hr/> |

- j. Has painting/staining been done in the last 6 months? Y / N Where & When? _____
- k. Is there new carpet, drapes or other textiles? Y / N Where & When? _____
- l. Have air fresheners been used recently? Y / N When & Type? _____
- m. Is there a kitchen exhaust fan? Y / N If yes, where vented? _____
- n. Is there a bathroom exhaust fan? Y / N If yes, where vented? _____
- o. Is there a clothes dryer? Y / N If yes, is it vented outside? Y / N
- p. Has there been a pesticide application? Y / N When & Type? _____

Are there odors in the building?

Y / N

If yes, please describe: _____

Do any of the building occupants use solvents at work?

Y / N

(e.g., chemical manufacturing or laboratory, auto mechanic or auto body shop, painting, fuel oil delivery, boiler mechanic, pesticide application, cosmetologist)

If yes, what types of solvents are used? _____

If yes, are their clothes washed at work?

Y / N

Do any of the building occupants regularly use or work at a dry-cleaning service? (Circle appropriate response)

Yes, use dry-cleaning regularly (weekly)

No

Yes, use dry-cleaning infrequently (monthly or less)

Unknown

Yes, work at a dry-cleaning service

Is there a radon mitigation system for the building/structure? Y / N Date of Installation: _____

Is the system active or passive? Active/Passive

9. WATER AND SEWAGE

Water Supply: Public Water Drilled Well Driven Well Dug Well Other: _____

Sewage Disposal: Public Sewer Septic Tank Leach Field Dry Well Other: _____

10. RELOCATION INFORMATION (for oil spill residential emergency)

a. Provide reasons why relocation is recommended: _____

b. Residents choose to: remain in home relocate to friends/family relocate to hotel/motel


c. Responsibility for costs associated with reimbursement explained? Y / N

d. Relocation package provided and explained to residents? Y / N


11. FLOOR PLANS

Draw a plan view sketch of the basement and first floor of the building. Indicate air sampling locations, possible indoor air pollution sources and PID meter readings. If the building does not have a basement, please note.

Basement:




First Floor:



12. OUTDOOR PLOT

Draw a sketch of the area surrounding the building being sampled. If applicable, provide information on spill locations, potential air contamination sources (industries, gas stations, repair shops, landfills, etc.), outdoor air sampling location(s) and PID meter readings.

Also indicate compass direction, wind direction and speed during sampling, the locations of the well and septic system, if applicable, and a qualifying statement to help locate the site on a topographic map.



13. PRODUCT INVENTORY FORM

Make & Model of field instrument used: _____

List specific products found in the residence that have the potential to affect indoor air quality.

[illegible]

* Describe the condition of the product containers as **Unopened (UO)**, **Used (U)**, or **Deteriorated (D)**

**** Photographs of the front and back of product containers can replace the handwritten list of chemical ingredients. However, the photographs must be of good quality and ingredient labels must be legible.**