# SITE MANAGEMENT PLAN

# NORTHEASTERN INDUSTRIAL PARK AREA OF CONCERN 1 (Southern Landfill) AREA OF CONCERN 7 (Triangular Disposal Area)

# **GUILDERLAND, NEW YORK**

Contract Number: W912WJ-12-C-0006 FUDS Property No. CO2NY00203 NYSDEC Site No. 401009

# August 2014

# Prepared for:

Department of Army New England District, Corps of Engineers 696 Virginia Road Concord, Massachusetts 01742-2751



# Prepared by:

H2H Associates, LLC 179 River Street Troy, New York 12180



# TABLE OF CONTENTS

1.0	IN	TRODUCTION	. 1-1
	1.1	OBJECTIVES	1-1
2.0	SI	TE SUMMARY	2-1
	2.1	SITE DESCRIPTION AND BACKGROUND	2-1
	2.1	.1 Site History	
	2.2	NATURE AND EXTENT OF CONTAMINATION	
	2.3	REMEDIAL ACTION OBJECTIVES	2-3
	2.4	PREVIOUS INVESTIGATIONS	
	2.5	DESCRIPTION OF THE SELECTED REMEDY FROM THE DECISION	
		DOCUMENT	2-4
	2.6	REMEDIAL ACTION	
3.0	EN	IGINEERING AND INSTITUTIONAL CONTROLS	3-1
	3.1	ENGINEERING CONTROLS	3-1
	3.2	INSTITUTIONAL CONTROLS	3-1
4.0	GF	ROUNDWATER MONITORING PLAN	4-1
	4.1	INTRODUCTION	4-1
	4.2	GROUNDWATER SAMPLING METHODOLOGY	4-3
5.0	OF	PERATION AND MAINTENANCE PLAN	5-1
	5.1	COVER INSPECTION	
	5.2	GRASS COVER/TOPSOIL LAYER	5-1
	5.3	COVER SOIL AND CAP COMPONENTS	5-2
	5.4	COVER REPAIR PROTOCOL	5-3
	5.4	.1 Surface Cracks	5-3
	5.4	.2 Vegetative Growth	5-3
	5.4	.3 Responsibility: USACE (or in its absence due to funding considerations, the	
		property owner). Vector Penetration	5-3
	5.4	.4 Settlement	5-3
	5.4	5 Erosion	5-4
	5.5	RESPONSIBILITY: ANY INDIVIDUAL OR CONCERN ASSOCIATED WITH	I
		PROPERTY OWNER.STORMWATER MANAGEMENT SYSTEM	5-5
6.0	$\mathbf{M}_{\mathbf{A}}$	AINTENANCE ACTIVITIES	. 6-1
	6.1	REPORTING	
	6.2	NOTIFICATIONS	6-2
	6.3	SITE CLOSEOUT	6-2
7.0	RE	FERENCES	7-1

# LIST OF TABLES

	Table 1	AOC 1 I	Long-Term l	Mon	itoring	W	ells	S
--	---------	---------	-------------	-----	---------	---	------	---

Specifics for Laboratory Analyses for Groundwater Sampling at AOC 1 Table 2

# LIST OF FIGURES

Figure 1	Site Location Map
Figure 2	Site Layout Map

Figure 3 Monitoring Well Locations

# LIST OF APPENDICES

Appendix A	Monitoring Well Logs and Monitoring Well Construction Data
Appendix B	IC/EC Certification Form
Appendix C	Landfill Cap/Soil Cover Inspection Forms
Appendix D	Environmental Easement
Appendix E	Record Drawing As-Built – Area of Concern 1 – Landfill Cap/Soil Cover
Appendix F	Responsibilities of Owner and Remedial Party

#### LIST OF ACRONYMS and ABBREVIATIONS

AOC Area of Concern

APP Accident Prevention Plan

ARARs Applicable or Relevant and Appropriate Requirements

CERCLA Comprehensive Environmental Restoration, Compensation, and Liability

Act of 1980

CFR Code of Federal Regulations
COC Contaminants of Concern

DCA Dichloroethane
DCE Dichloroethene

DERP-FUDS Defense Environmental Restoration Program-Formerly Used Defense Sites

DD Decision Document
DoD Department of Defense
DOR Designer of Record
DTB Depth to Bottom
DTW Depth to Water

EC Engineering Controls

EC/IC Engineering Control/Institutional Control

ECS Engineering Control System
EDD Electronic Data Deliverable
EPP Environmental Protection Plan

FS Feasibility Study
FSP Field Sampling Plan
H2H H2H Associates, LLC.
HGL HydroGeologic, Inc.

HHRA Human Health Risk Assessment

IC Institutional Controls

LLDPE Linear Low-Density Polyethylene

LUC Land Use Controls

MCL Maximum Contaminant Level MNA Monitored Natural Attenuation

MS/MSD Matrix Spike/Matrix Spike Duplicate

NEIP Northeast Industrial Park

NWP Nationwide Permit

NYSDEC New York State Department of Environmental Conservation

NYSDOH New York State Department of Health

O&M Operation and Maintenance

PAHs Polycyclic Aromatic Hydrocarbon

PDI Pre-Design Investigation

PM Project Manager

PRR Periodic Review Report

QA Quality Assurance

QAPP Quality Assurance Project Plan

QC Quality Control

QEP Qualified Environmental Professional

RI Remedial Investigation

SADVA Schenectady Army Depot-Voorheesville Area

SAP Sampling and Analysis Plan

SARA Superfund Amendments and Reauthorization Act

SCGs Standards, Criteria and Guidance

SLERA Screening Level Ecological Risk Assessment

SMP Site Management Plan

SSHO Site Safety and Health Officer SSHP Site Safety and Health Plan

SOW Statement of Work TCE Trichloroethene

μg/kg Microgram per Kilogram μg/l Microgram per Liter

USACE United States Army Corps of Engineers

USEPA United States Environmental Protection Agency

VC Vinyl Chloride

VOC Volatile Organic Compound

### 1.0 INTRODUCTION

This Site Management Plan (SMP) has been prepared for the Former Schenectady Army Depot (aka Northeastern Industrial Park), Area of Concern 1 – "Southern Landfill" Site (Site), located in the Town of Guilderland, New York. This SMP was prepared for the United States Army Corps of Engineers (USACE) New York District for FUDS Property No. CO2NY00203, New York State Department of Environmental Conservation (NYSDEC) Site No. 401009. The Site location is shown on Figure 1. The installation of the cap and cover remedy at AOC 1 was completed in 2013; AOC 7 (Triangular Disposal Area) is identified in this SMP due to its proximity to AOC 1, and its inclusion in the area covered by the environmental easement.

This SMP has been prepared in accordance with 6 New York Codes, Rules and Regulations (NYCRR) Part 375 and includes an Engineering Control/Institutional Controls (EC/IC) plan, a Groundwater Monitoring Plan, and an Operations and Maintenance (O&M) Plan. The SMP is part of the selected response action, after the construction of the landfill cap and soil cover, in the Area of Concern (AOC 1) Decision Document (DD). This SMP has been prepared to document the requirements and procedures for the Engineering Controls (ECs) and Institutional Controls (ICs) for the remediated portion of the AOC 1 as shown in Figure 2. This SMP does not supersede any federal, state, or local statutes, regulations, or ordinances pertaining to the environment, and current and future holders of interests of property within the Site will remain obligated to comply with the same.

This SMP has been prepared as a mechanism to assure that consistent and effective inspection and maintenance and enforcement activities are occurring and will occur in the future throughout the Site. These objectives and those detailed below will be achieved primarily through the implementation of EC/ICs, the groundwater monitoring plan and the maintenance practices defined in this SMP. As part of the ICs of the SMP, an Environmental Easement will be utilized to impose land use and groundwater use limitations on the AOC 1 and 7 site, to protect the present and future owners from potential environmental contamination. The environmental easement will reference the SMP. The United States Army Corps of Engineers (USACE) and the present owner and any future owners of the Site will be bound by the provisions of this SMP relevant to the portion of the property they own or control on the Site. Note that USACE responsibilities under this SMP will be executed subject to availability of funds.

#### 1.1 OBJECTIVES

The specific objectives of this SMP are as follows:

- To describe ECs/ICs to be implemented to maintain the short-term and long-term effectiveness of the remedy established in the DD.
- To establish controls on groundwater use.
- To identify the specific mechanisms that will be used to establish and enforce the ECs/ICs contained in this SMP.
- To define the monitoring requirements.
- To outline the maintenance and inspection requirements for the Site.

### 2.0 SITE SUMMARY

### 2.1 SITE DESCRIPTION AND BACKGROUND

The Former Schenectady Army Depot-Voorheesville Area (SADVA) (also known as the former Voorheesville (Army) Depot) is located in the Town of Guilderland, one quarter mile southeast of the hamlet of Guilderland Center, Albany County, New York (refer to Figure 1). The Department of Defense (DoD) used the SADVA property primarily as a warehouse and storage complex from 1941 through 1969. The site was originally constructed as a regulating station and a holding and reconsignment point, and later became a general depot for the U.S. Department of the Army. The principal mission of the installation was the receipt, storage, maintenance, and distribution of supply items.

The SADVA site is now privately owned and known as the Northeastern Industrial Park or NEIP. AOC 1 is the former U.S. Army Southern Landfill located in the southeastern portion of NEIP (refer to Figure 2). AOC 7 is a triangular-shaped disposal area located on dry, open ground between existing and former railroad tracks at the south end of SADVA.

## 2.1.1 **Site History**

A 1980 report by the Albany County Environmental Management Council (ACEMC) prompted environmental concern at the SADVA property (ACEMC, 1980). This report described aerial photographs showing excavation and disposal activities that occurred in the southeastern areas of the SADVA. Most excavation and disposal activities occurred during the time SADVA was operated by DoD. However, according to a report by the U.S. Army Toxic and Materials Agency (1980), no written records were found that would indicate that disposal of wastes occurred at the former depot. For this reason, historical aerial photos were utilized to help identify periods of site disturbance that could correspond to waste disposal activities. In its report, Albany County discussed observations of an approximately 15-acre dump that was referred to as the U.S. Army Southern Landfill (later AOC 1), located in the southern part of SADVA (Figure 2). Next to the dumpsite was a 3-acre pond, which was located at the southwest edge of the dumpsite. The County also noted a (possible) 1.5-acre storage container and/or debris area at the northwest edge of this site.

The Southern Landfill (AOC 1) reportedly contains construction and demolition debris, industrial and domestic wastes, and wastes from the former burn pit area. The landfill boundaries have previously been determined by past investigations conducted from the early 1990's through 2007 by URS, Inc., Malcolm Pirnie and Parsons at the request of the USACE. Impacts by Volatile Organic Compounds (VOCs), Polycyclic Aromatic Hydrocarbons (PAHs) and/or metals in surface soil, subsurface soil and groundwater have been documented, particularly in the southern section. Prior to implementation of the remedy, direct contact with the surface soils, surface water, and sediment was considered the most likely exposure pathway for the contaminants of concern (COCs). A potential COC migration pathway considered was that groundwater may be discharging to, and impacting, adjacent surface water and sediment in the pond whose overflow ultimately flows to Black Creek, which flows to Watervliet Reservoir, a local public drinking water supply. The reservoir is located approximately four (4) miles downstream of the southern portion of the NEIP property.

#### 2.2 NATURE AND EXTENT OF CONTAMINATION

AOCs 1 and 7 were included in a remedial investigation (RI) for the SADVA conducted by Parsons under contract to the USACE during the period 1999-2007. In addition, the AOC 1 was the subject of a separate RI completed in 1996 by Malcolm Pirnie and URS, Inc. under contract to the USACE. Based on these RIs conducted in 1997 (Malcolm Pirnie) and 2007 (Parsons), the primary COCs identified in soil at AOC 1

were PAHs, including benzo(a)pyrene, and the metal, arsenic. The COCs identified for groundwater at AOC 1 are chlorinated hydrocarbons: trichloroethene (TCE), 1,2-dichlorothene-Total (cis- and trans-1,2 DCE), 1,2-dichloroethane (1,2-DCA), and vinyl chloride (VC). This mix of VOC suggests that anaerobic dechlorination may be an active process at AOC 1. Meeting groundwater applicable or relevant and appropriate requirements (ARARs) is the primary driver in the remedial action.

The 1997 RI by Malcolm Pirnie identified the presence of a VOC groundwater plume beneath the southern part of the Southern Landfill. Subsequent sampling in June 2000 indicated that the VOC compounds detected in groundwater were limited to the same area of AOC 1 that was identified in 1997; however, benzene, toluene, ethylbenzene and xylene (BTEX) and acetone were not detected in the same wells in 2000.

Three shallow monitoring wells (GW-12, GW-13, and GW-14) were installed along the east side of AOC 1 in 2004 (see Figure 3 for monitoring well locations). The sampling results led to the conclusion that VOCs are not migrating offsite to the east in the shallow water table. Similarly, VOCs were not detected in these three wells during the 2006 sampling event. Furthermore, the multiple rounds of groundwater sampling and VOC analyses indicate that VOC concentrations within the plume area declined significantly between the 1997 RI and the 2006 sampling event. VOC degradation appears to be an active natural process at the site.

The primary objective of the human health risk assessment (HHRA) performed during the RI was to quantitatively characterize the human health risk associated with current and potential future exposure to contaminated media at AOC 1 and 7. All potentially complete exposure pathways for the site were evaluated based on more protective exposure scenarios (*e.g.*, the residential scenarios provide very conservative (health-protective) estimates for standard site worker scenarios). The HHRA concluded the following:

- AOC 7 poses no unacceptable health risk with respect to soil, groundwater, surface water and sediment exposures. In addition, the vegetative cover over AOC 7 is intact, and all soil sample concentrations within the limits of AOC 7 are below the Part 375 industrial land use cleanup objectives. Therefore, AOC 7 is not considered in the remedial action objectives.
- AOC 1 poses no unacceptable health risks with respect to surface water and sediment exposures. AOC 1 does not meet the minimum criteria for established ARARs with respect to groundwater, if used as a drinking water source. The calculated health risk for soils at AOC 1 was within the acceptable range; however, the soils/wastes in the center of the landfill were not fully characterized. In addition, soils at AOC 1 may exceed the NYSDEC Part 375 industrial land use criteria. Therefore, soils and groundwater at AOC 1 have been considered in the remedial action objectives.

After the HHRA was completed, the New York Department of Environmental Conservation (NYSDEC) promulgated new risk-based soil cleanup objectives under Title 6 NYCRR. Subsequent to the HHRA, NYSDEC requested that soil concentrations at AOC 1 be compared with the soil cleanup objectives. The concentrations of PAHs and/or arsenic were above the Part 375 industrial land use cleanup objectives for seven grab soil samples collected within the limits of AOC 1. Even though concentrations reported from some grab samples exceeded the Part 375 decision limits/cleanup goals, it is unknown whether a significant portion of the landfill exceeds these decision limits; the volume of material in the landfill that exceeds the cleanup goals was not quantified.

No buildings currently exist at AOC 1; however, a vapor intrusion screening was completed to assess the potential for a vapor intrusion health risk should a building be constructed in the area in the future. The

screening suggested that vapor intrusion could pose a risk if new buildings will be constructed within the lateral limits of the VOC groundwater plume emanating from the southern portion of the AOC 1 landfill.

The RI characterization found no contamination at AOC 7 that required remedial action.

#### 2.3 REMEDIAL ACTION OBJECTIVES

Remedial action objectives were developed for the purpose of evaluating the applicability of remedial technologies and the effectiveness of remedial alternatives. These objectives consist of media-specific goals for protecting human health and the environment, and for meeting ARARs in a cost-effective manner.

Groundwater ARARs				
Chemical Parameter	6 NYCRR 703.5 (f), Table 1			
1,2-Dichloroethane (1,2-DCA)	0.6			
1,2-Dichloroethene (total 1,2-DCE)	5			
	Federal MCL – 40 CFR 141.61			
Trichloroethene (TCE)	5			
Vinyl Chloride (VC)	2			
Soil A	RARs			
Chemical Parameter	6 NYCRR 375-6.8(b)			
Benzo(a)pyrene (PAH)*	1,100			
Total PAHs	1,000,000			
Arsenic	16,000			
Others	ARARs			
Landfill Requirements for Closure/Post-Closure Care	U.S. Environmental Protection Agency 40 CFR 264.310			

Note: all concentrations are in:

ug/L -  $micrograms\ per\ liter\ (groundwater)$ 

ug/kg - micrograms per kilogram (soil)

MCL - maximum contaminant level

A screening-level ecological risk assessment (SLERA) was conducted during the RI to evaluate potential adverse impacts to the ecological receptors at SADVA due to the presence of hazardous contaminants in soil, sediment, and surface water. The objective of the SLERA was to evaluate whether unacceptable adverse risks may be present, or if risks may be posed to ecological receptors in the future. The qualitative ecological risk assessment concluded that although there are chemicals in various media onsite that could pose a risk to aquatic and terrestrial wildlife, the AOC 1 site appears to support wildlife typical for the area and for the commercial/industrial setting that the site has retained for over 60 years. The results of the ecological risk assessment indicate there is no unacceptable risk to the environment and that remedial action is not warranted.

The remedial action objectives were established based on site-specific information, including the nature and extent of chemical constituents, existing site conditions, and future land use plans. Remedial action objectives typically focus on controlling exposure of receptors (for example, workers at AOC 1) to chemicals of concern via exposure routes such as dermal contact, ingestion, and inhalation. The remedial action objectives also focus on controlling the release of hazardous substances into the environment.

Remedial action objectives for AOC 1 were as follows:

<sup>\*</sup> PAHs - polycyclic aromatic hydrocarbons

- Eliminate or minimize the human health risks posed by trichloroethene, VC, 1,2-DCA and total-1,2-DCE in groundwater within the landfill by satisfying the Class GA groundwater standards ARARs for these analytes;
- Eliminate the soil exposure pathway;
- Mitigate the potential for future releases of contaminants in the landfill to groundwater; and
- Mitigate the potential for movement and offsite migration of TCE, VC, 1,2-DCA, and Total-1,2-DCE from the groundwater plume within the landfill.

#### 2.4 PREVIOUS INVESTIGATIONS

The following is the history of investigations and reports prepared for the Site and upon which the SMP for AOC 1, Guilderland, New York was based:

- H2H, LLC, 2014 (In Preparation), Final Engineering Report, Landfill Cap and Soil Cover, Area of Concern, Northeast Industrial Park, Guilderland, New York (Pending)
- H2H, LLC, 2013, 100% Design Analysis Report Landfill Cap and Soil Cover Design Area of Concern 1, Northeast Industrial Park, Guilderland, NY, June 2013
- H2H, LLC, 2013, Final Pre-Design Investigation Report Pre-Design Field Program, Northeast Industrial Park, Area of Concern 1, Guilderland, New York. January 2013
- Malcolm-Pirnie, 1997. "Final Limited Remedial Investigation Report, Former Voorheesville Army Depot, U.S. Army Southern Disposal Landfill, Guilderland, New York", prepared for USACE-Baltimore District, April.
- Parsons, 2007. Remedial Investigation Report, Former Schenectady Army Depot Voorheesville Area. May 2007.
- Parsons, 2010. Focused Feasibility Study, Former Schenectady Army Depot Voorheesville Area.
- ACEMC, 1980. Albany County Environmental Management Council, "Northeastern Industrial Park (Voorheesville Depot) and Vicinity, Closed Landfill Study", June 25, 1980.
- Metcalf and Eddy, Inc., 1988. Engineering Final Report Site Investigation. Contamination Evaluation at the Former Schenectady Army Depot, New York by Metcalf & Eddy, Inc. February 1988.
- ERM-Northeast, 1990. "Report of Findings Environmental Liability Review Northeastern Industrial Park" dated March 15, 1990.
- OHM Remediation Services Corp, 1991. Phase II Draft Report, Schenectady Army Depot Site, Voorheesville, Guilderland, New York. April 1991.
- URS, March 1996. Final Chemical Data Acquisition Plan. Remedial Investigation at the Former
- Voorheesville Army Depot, U.S. Army Southern Disposal Landfill Guilderland, New York.
- Quantum Geophysics, Inc., 1997. Geophysical Investigation. April 1997.
- Malcolm-Pirnie, 1997 "Final Limited Remedial Investigation Report, Former Voorheesville Army Depot, U.S. Army Southern Disposal Landfill, Guilderland, New York", prepared for USACE-Baltimore District, April 97.
- EAEST, 2003. EA Engineering, Science and Technology "Final Investigation Report. Archival Search Former Schenectady Army Depot Voorheesville Area", dated May 2003.
- Galesi Group 2005. Draft Generic Environmental Impact Statement, Northeastern Industrial Park, June 2005.

# 2.5 DESCRIPTION OF THE SELECTED REMEDY FROM THE DECISION DOCUMENT

Based on the evaluation presented in the FS and the Proposed Plan, the selected alternative for AOC 1 was Alternative 3 from the Feasibility Study – Landfill Cover and Cap / Groundwater Monitored Natural Attenuation (MNA)/Land Use Controls (LUCs). This alternative will institute the Containment Presumptive Remedy for the landfill, will provide the best balance of the threshold, primary balancing and modifying criteria, and will satisfy the remedial action objectives for this site, which are:

- Eliminate or minimize the human health risks posed by TCE, VC, 1,2-DCA, and total-1,2-DCE in groundwater within the landfill by satisfying the Class GA groundwater standards applicable or ARARs for these analytes. This remedial action objective will be satisfied by prohibiting potable use of groundwater in the vicinity of AOCs 1 & 7 (the VOC ARARs will be satisfied with a groundwater use easement granted by the property owner; the easement is considered an institutional control), and supplemented with groundwater MNA (and monitoring of VOC concentrations). Metals (arsenic, vanadium, selenium and antimony) also pose an unacceptable risk in groundwater. The presence of these metals will be addressed by the environmental easement prohibiting potable use of groundwater at AOC 1. Metals are not included as COCs for groundwater because the concentrations are not expected to be treated by MNA and therefore will not be monitored over time, as will be the case with VOCs;
- Although soils have not been completely characterized, the remedial action will eliminate the soil exposure pathway because the landfill cap and cover will prevent physical access to the affected soil;
- Mitigate the potential for future releases of contaminants in the landfill to groundwater. This remedial action objective will be satisfied with the landfill cap over the groundwater plume. If it is discovered that the landfill cap and soil cover system has been damaged, the need to resume groundwater monitoring activities will be reevaluated, and;
- Mitigate the potential for movement and offsite migration of TCE, VC, 1,2-DCA, and total-1,2-DCE from the groundwater plume within the landfill. This remedial action objective will be satisfied with the landfill cap over the groundwater plume.

## 2.6 REMEDIAL ACTION

The remediation was performed pursuant to the USACE Decision Document for the Northeastern Industrial Park AOC 1 Site, dated 11 October 2011.

In June 2012, H2H Associates, LLC (H2H) prepared bid documents for the selected remedy. Remedial construction of the preferred alternative was awarded to H2H (Contractor) on 17 July 2012. HydroGeoLogic, Inc. (HGL) was subcontracted to be the Designer of Record (DOR) for the project. Maxymillian Technologies (Maxy) was subcontracted to construct the Impermeable Landfill Cap and Soil Cover while H2H, LLC oversaw construction and performed all other work associated with the contract documents.

Prior to design of the landfill cap/soil cover for AOC 1, additional information was needed. The pre-design investigation (PDI) was conducted October through December 2012. The purpose of the PDI was to collect information required to develop a final landfill cap and soil cover Remedial Design for AOC 1. A summary of activities conducted for this phase of the project:

- Mowing and Clearing
- Utility Clearance
- Pre-Design Topographic Survey and Mapping;
- Vibration Analysis;
- Rare Endangered Species Identification; and,
- Wetlands permit/V-19 Boundary Verification

- Landfill Gas Monitoring
- Pre-Design Sampling and Analysis

The pre-design field investigation was designed to achieve several objectives for the intended purpose: 1.) to refine the characterization of the nature and extent of groundwater contamination at the site through additional sampling of monitoring wells; 2.) to establish a base map for planning and design purposes; and 3.) conduct such investigations necessary to finalize the design of the landfill cap and soil cover. Results from the PDI investigation were incorporated into the final design of the cap and soil cover for AOC 1.

The Landfill Cover and Cap and Soil Cover Systems were designed by HGL for H2H under contract to the USACE New England District and under project management by the USACE New York District. The criteria used for final landfill cap and soil cover system design included compliance with relevant and appropriate sections of New York State codes and industry standards for environmental protection, Code of Federal Regulations (CFR), Title 40, Parts 264.310 and 258.2.

Two types of cap/cover systems were constructed. The landfill cap system included approximately 2.8 acres of final cover constructed on the southern portion of the site. The soil cover system included approximately 8 acres constructed on the northern portion of the site. Prior to the installation of the cap, approximately 10,400 cubic yards of fill material was brought to the site to bring the existing grade up to meet the 4% minimum grade requirement.

The landfill cap system in the southern portion of the site incorporated the following:

- A topsoil layer of at least 6 inches.
- A 2-ft thick protective layer, composed of silty sand material with the lower 6-inches free of stones larger than ½ inch.
- A subsurface drainage system consisting of a drainage geocomposite.
- A low-permeability layer consisting of a 40-mil thick textured linear low-density polyethylene (LLDPE) geosynthetic membrane.
- A 10-ounce per square yard (oz/yd²) nonwoven geotextile blanket layer.
- A 6-inch minimum thickness soil subbase layer for the composite liner system that was free of rocks greater than ½-inch in diameter.

A topsoil layer of at least 6 inches was graded on top of the final cover layer to allow for vegetation growth. The final cover area was graded to allow for adequate drainage and vegetation growth. The slope was at least 4% (4 ft vertical fall per 100 ft of horizontal run) to adequately drain the surface water and meet the requirements of NYCRR Part 360-2. The final cover was vegetated with a blend of warm and cool season grasses and vegetation to prevent erosion of the protective layer of the final cover (i.e., upper 2 ft).

A majority of water that infiltrates through the protective layer will be captured and drain along the subdrain layer above the LLDPE geomembrane. The subdrain layer consists of drainage geocomposite material with single-sided textured nonwoven 6-oz/yd² geotextile. The low permeability layer consists of a 40-mil thick textured LLDPE geosynthetic membrane. LLDPE provides optimum serviceability and flexibility to allow the material to perform while differential settlement of the waste occurs.

Underneath the LLDPE there is a 10-oz/yd² nonwoven geotextile blanket layer. This layer provides a cushion for the low-permeability LLDPE geosynthetic membrane. The age, limited volume, and composition of the waste, along with recent soil gas sampling, indicate that landfill gas is not being generated at the site. Therefore, a waiver from inclusion of a gas management layer was requested from and granted by the NYSDEC via a letter dated 18 March 2013. The 6-inch thick soil subgrade layer provides a smooth foundation for the composite final cover, free of deleterious and protruding material.

The soil cover system in the northern portion of the site incorporated the following:

- A topsoil layer of at least 6-inches.
- A 1-ft thick protective layer.
- A gravel access road to allow limited vehicle access to the area and to the (southern area) landfill cap.

The soil cover system was constructed in the soil cover area by first clearing and grubbing the existing vegetation. Then a 1-ft thick soil protective layer was installed with an additional 6-inch thick topsoil layer placed on top and seeded for vegetative growth.

A gravel access road was constructed in the soil cover area to allow vehicle access through the soil cover system and to the landfill cap system. The road is approximately 12 ft wide, constructed in the location of the former access road by adding an 8-inch layer of crushed gravel (size 2 inches or less) over non-woven geotextile. The gravel was placed over an 8-inch compacted protective soil layer giving the access road a final elevation higher than the surrounding soil.

Particulate air monitoring was conducted from 6 June 2013 to 6 September 2013 during construction and ground intrusive activities, which included but were not limited to soil excavation and handling, or trenching. The perimeter air monitoring locations were random and were established with one (1) upwind and two (2) downwind of the active work area(s). Particulate air monitoring was performed and checked at a minimum of once per day, when site conditions changed (visual observance) or when a new task was started or the task(s) being performed changed. All air monitoring results were recorded daily in an air monitoring log. These air monitoring results are part of the project record.

During the remediation process, a total of 12 monitoring wells were decommissioned due to their locations being within the limits of work. All wells that were decommissioned during the remediation process were decommissioned in conformance with ASTM D 5299 – Standard Guide for Decommissioning of Groundwater Wells, Vadose Zone Monitoring Devices, Boreholes, and Other Devices for Environmental Activities. Any cuttings generated from the well decommissioning were placed in drums for proper disposal. A composite soil sample was collected from each drum of soil cuttings to determine if the soil was hazardous. The analysis concluded that the soil was non-hazardous. The soil cuttings were transported to CWM Chemical Services, LLC (Model City, NY) for proper disposal (Waste manifests are located in Appendix A). Any groundwater generated during the decommissioning process was disposed of adjacent to the borehole with NYSDEC approval. Care was taken so that there was no run-off into surface water bodies.

No equipment or other facilities were left in place at the completion of the project, and the site was restored as an open, grass-covered landfill, except for a gravel drive.

The Final Engineering Report documents construction activities for the Landfill Capping/Soil Cover Contract and provides certification that the construction, excavation, and backfill activities associated with the soil cover and landfill cap installation at the Site were performed in substantial conformance with the contract documents. The Final Engineering Report includes as-built drawings prepared by the Contractor, as well as well decommissioning logs from the well abandonment process, analytical data, copies of daily field/safety reports and photographs, and other detailed information.

### 3.0 ENGINEERING AND INSTITUTIONAL CONTROLS

The Owner, or USACE, and a Professional Engineer (P.E.) or the Qualified Environmental Professional (QEP), must review and complete the IC/EC Certification Form, sign the IC/EC Certifications Signature Page, and submit it as part of the Annual Certification Report to the NYSDEC. The Certification Form was developed based on NYS Division of Environmental Remediation (DER) DER-10 Technical Guidance for Site Investigation and Remediation (May 2010) and verifies that all Engineering Controls and Institutional Controls have been inspected annually and are considered applicable and complete. If there is any corrective action that is needed, this is noted and completed, followed by a subsequent inspection to verify the corrective measure has been implemented. Appendix B contains the IC/EC Certification Form for AOC 1.

#### 3.1 ENGINEERING CONTROLS

Engineering Controls are physical mechanisms which restrict access to the Site and Site contaminants. Engineering Controls include any physical barrier or methods employed to actively or passively contain, stabilize, or monitor hazardous waste, restrict the movement of hazardous waste to ensure the long-term effectiveness of a remedial program, or eliminate potential exposure pathways to hazardous waste.

Engineering controls for this site include, but are not limited to:

- <u>Site Access Controls</u> The existing six foot high chain link fence surrounding the NEIP property that will be maintained by the property owner as part of the engineering control plan. There is a locking gate at the entrance of the site.
- <u>Signage</u> "Posted" signs will be placed on the perimeter fence and at the AOC 1 site entrance gate to notify the community that the Site has restricted access and that no trespassing is allowed.
- <u>Monitoring Well Replacement</u> Three of the monitoring wells decommissioned during the Site remediation have been replaced to monitor the effectiveness of the remedial program on the groundwater at the Site.
- <u>Groundwater Monitoring</u>. The USACE will monitor groundwater quality at each of the Site monitoring wells (refer to Section 4) until data indicate that groundwater standards have been achieved. Each of the Site wells will be sampled annually during the first 5 years, to obtain a post-remediation baseline data set. The rate of sampling will then be re-evaluated in the 5 year Periodic Review Report and USACE will evaluate the need for continuing annual monitoring.

### 3.2 INSTITUTIONAL CONTROLS

Institutional controls are non-physical mechanisms which restrict the use of a site, limit human exposure, and prevent any actions which would threaten the effectiveness or operation and maintenance of a remedy at or pertaining to the site. Under NYSDEC policy, institutional controls apply when contaminants remain at a site at levels above the Standards, Criteria, and Guidance (SCGs) that would otherwise allow unrestricted human use of AOC 1. Institutional controls may include restrictions on the use of structures, land and groundwater as well as deed notices and covenants.

Institutional controls to protect human health and the environment will be implemented at the Site through an Environmental Easement prepared by the USACE and approved by the NYSDEC and presented in

Appendix D. The following institutional controls will be implemented and enforced through an Environmental Easement which will be granted by the current property owner:

- 1. <u>Site Use Restriction</u>. Only authorized use of the Controlled Property will be permitted. No intrusive ground disturbing activities will be permitted within the controlled property. No load bearing use will be permitted on the cap and covered area of the landfill. (See Appendix D for an enlarged figure depicting the capped and covered area of the AOC 1 landfill). Construction of buildings in the controlled area are prohibited. Included in Appendix D is a figure depicting the controlled property (Environmental Easement Description and Record Legal Description). The Environmental Easement shall be binding on all future owners of the property and will consign consent to enforcement by the NYSDEC of all prohibitions and restrictions and agreement not to contest the authority of the NYSDEC to seek enforcement.
- 2. <u>Soil Management</u>. Further excavation of soils at AOC 1 or removal of soil from the property will be prohibited.
- 3. <u>Vapor Intrusion</u>: Vapor intrusion risks must be considered during planning for any new (future) construction of buildings in the near vicinity of the VOC groundwater plume at AOC 1.
- 4. <u>Groundwater Use Restriction</u>. The use of groundwater, as defined by the easement boundary, will be prohibited until deemed acceptable by the NYSDEC.
- 5. <u>Annual Certification Report</u>: The Site owner will certify on a yearly basis that the institutional controls are in place and remain effective for the protection of public health and the environment. The USACE will identify any activities undertaken pursuant to the SMP during the past year, and identify anticipated forthcoming activities that may require implementation of the SMP.

The annual certification report will be prepared by a QEP, which must certify that the institutional controls and/or engineering controls employed are unchanged from the previous certification, unless otherwise approved by the Department; in place and effective; performing as designed; and that nothing has occurred that would impair the ability of the controls to protect the public health and environment; or constitute a violation or failure to comply with any maintenance plan for such controls. The report will include:

- 1. Groundwater monitoring and any other analytical results;
- 2. Analysis of groundwater contamination concentrations;
- 3. Description of site conditions and maintenance activities;
- 4. Recommendations for any corrective measures or changes in the Site Maintenance Plan.

The certification report will be distributed to:

NYSDEC Heather Bishop Project Manager Division of Environmental Remediation, Bureau A 625 Broadway – 11<sup>th</sup> Floor Albany, NY 12233-7015

Dean Brammer
Technical Leader
U.S. Army Corps of Engineers,
New England District (CENAE-EP-GE)
696 Virginia Road,
Concord, MA 01742-2751

Gregory J. Goepfert, P.E., PMP, Project Manager U.S. Army Corps of Engineers, New York District, Room 1811 (CENAN-PP-E), 26 Federal Plaza, New York, NY 10278

Town of Guilderland Town Supervisor, Kenneth D. Runion Guilderland Town Hall – 2nd Floor 5209 Western Turnpike Guilderland, NY 12084

Ms. Bridget Boyd Public Health Specialist II Bureau of Environmental Exposure Investigation New York State Department of Health Empire State Plaza, Corning Tower, Room 1787 Albany, NY 12237

After the property owner executes the Environmental Easement, it will be recorded and filed with the Albany County Clerk, and proof of the recording and filing will be submitted to the NYSDEC within thirty days of the NYSDEC's approval of the Environmental Easement.

### 4.0 GROUNDWATER MONITORING PLAN

#### 4.1 INTRODUCTION

The Groundwater Monitored Natural Attenuation remedial action is intended to address the potential health risks related to groundwater exposure and includes the following components:

- Perform annual low flow groundwater sampling of groundwater plume at AOC 1 to evaluate and monitor attenuation of contaminants. Analyze samples for TCE, 1,2-DCA, Total 1,2-DCE and VC and natural attenuation parameters (see Table 2).
- Provide an annual report to USACE and NYSDEC including sample locations and methods, analytical results, comparison to baseline and previous sampling events.
- Continue monitoring until the designated volatile COCs meet the NYSDEC Class GA standards, that is, trichloroethene (standard 5 micrograms per liter ( $\mu$ g/l)), cis-1,2-dichloroethene (5  $\mu$ g/l), 1,2-dichloroethane (0.6  $\mu$ g/l) and vinyl chloride (2  $\mu$ g/l) .

To monitor the effectiveness of the remedial action and the Site's groundwater quality, selected monitoring wells will be sampled annually for the first 5 years after completion of the remedial action. The contractor will sample a total of 9 (nine) wells for long-term monitoring of the groundwater in the vicinity of the landfill; four Landfill Cap area monitoring wells (GW-12, MW-13-01, MW-13-02, and MW-13-03) and five Soil Cover area monitoring wells (GW-03, ACE-3, ACE-4, ACE-5, and GW-13). Three new monitoring wells, located along the perimeter of the landfill cap were drilled as part of the remediation and are included in the sampling scope (Refer to Figure 3). These wells are as follows:

- Well MW-13-01, located near the former AMW-4 located on the southern edge of the landfill cap.
- Well MW-13-02, located near the former AMW-3 located on the western edge of the landfill cap.
- Well MW-13-03, located near the former AMW-1 and AMW-2 located on the northeastern edge of the landfill cap.

Table 1
AOC 1 Long-Term Monitoring Wells

Monitoring Well ID	Rationale for Sampling	Easting	Northing
Landfill Cap Area			
GW-12	Assess Groundwater Quality	641507.22	1400557.37
MW-13-01	Assess Groundwater Quality	641294.2	1400330
MW-13-02	Assess Groundwater Quality	641073.3	1400500
MW-13-03	Assess Groundwater Quality	641398.5	1400687
Soil Cover Area			
GW-03	Assess Groundwater Quality	640427.01	1401197.67
ACE-3	Assess Groundwater Quality	640050.67	1402036.90
ACE-4	Assess Groundwater Quality	640007.28	1402347.53
ACE-5	Assess Groundwater Quality	640494.65	1402133.51
GW-13	Assess Groundwater Quality	641010.73	1401331.93

Well logs and well construction information, including well depths and screened intervals are locate in Appendix A.

The groundwater samples will be analyzed for the following VOC and MNA parameters:

- Volatile Organic Compounds Method 8260
- Total Organic Carbon Method 9060
- Dissolved Gases Methane, Ethane, Ethene Method RSK 175
- Nitrate Method 353.2
- Nitrite Method SM4500NO3-F
- Sulfate Method 300.0 by Ion Chromatography
- Total Sulfide Method 9030B
- Chloride Method 300.0 by Ion Chromatography
- Total Alkalinity Method SM2320B
- Total Manganese Method 6010
- Iron Speciation (Total and Ferrous) Method 6010.0/SM3500-FE

#### Field Measurements will include:

- Oxygen-Reduction Potential
- Dissolved Oxygen
- pH
- Temperature
- Specific Conductance

In addition, five (5) Quality Assurance samples (trip blank, field blank, blind duplicate, Matrix Spike/Matrix Spike Duplicate (MS/MSD)) will be collected for each round. A total of 16 samples with be analyzed for each annual sampling event (including the QC samples).

USACE will submit a report for each annual sampling round to the NYSDEC. The report will include a description of sampling methodology, results, discussion, conclusions, and any recommendations for the next sampling round. Appended to the report will be any new boring and well construction logs, a summary table of well construction details, tabulated water level measurements, well hydrographs when applicable, groundwater contour map, a table of cumulative analytical results, laboratory report with chain of custody forms, and projections for key analytes for reaching remedial goals.

A Five-Year Periodic Review Report (PRR) will be submitted to the NYSDEC by USACE every 5 years, beginning fifteen months after the Certificate of Completion or equivalent document is issued. This report will evaluate and suggest revisions to the monitoring schedule if deemed appropriate. The Monitoring program schedule is as follows for the first 5 years of monitoring:

<b>Monitoring Program</b>	Frequency*	Matrix	Analysis	Reporting
Groundwater Well Monitoring Network to be sampled (GW-12, MW-13- 01, MW-13-02, MW-13-03, GW-03, ACE-3, ACE-4, ACE-5, GW-13)	Annually beginning spring 2014  Spring 2014  Summer 2015  Fall 2016  Winter 2017  Spring 2018	Water	Volatile Organic Compounds - Method 8260 Total Organic Carbon - Method 9060 Dissolved Gases - Methane, Ethane, Ethene - Method RSK 175 Nitrate - Method 353.2 Nitrite - Method SM4500NO3-F Sulfate - Method 300.0 by Ion Chromatography Total Sulfide - Method 9030B Chloride - Method 300.0 by Ion Chromatography Total Alkalinity - Method SM2320B Total Manganese - Method 6010 Iron Speciation (Total and Ferrous) - Method 6010.0/SM3500-FE	Annual Reports to be submitted to the USACE, NYSDEC and NYSDOH 90 days after sample collection. Summer 2014 Summer 2015 Summer 2016 Summer 2017 Periodic Review Report to be submitted: Summer 2018
Site Inspections	Annually	NA	NA	
* The frequency of events wi achieved.				

## 4.2 GROUNDWATER SAMPLING METHODOLOGY

Prior to each sampling event, depth to water (DTW) and depth to bottom of well (DTB) will be gauged with a decontaminated electronic water level probe to determine the static water level, and will be measured to the nearest 0.01 feet. All water levels will be recorded in a field book then transferred to sampling logs. These levels will be utilized to construct a water table map for the sampling date.

Groundwater samples will be collected from nine (9) monitoring wells listed on Table 1. Each well will be purged and sampled using a low-flow purging and sampling technique following the United States Environmental Protection Agency's (EPA's) Low-Flow (Minimal Drawdown) Ground-Water Sampling Procedures, EPA/540/S-95/504, dated April 1996, where possible. A bladder pump outfitted with dedicated Teflon-lined tubing will be used to purge and sample the monitoring wells. The tubing will be lowered into the well to the targeted sample point at the middle of the water column within the screen interval.

The wells will be purged at a target rate of less than 0.5 liter/minute. During purging, the water level will be monitored with the water level indicator to measure well drawdown and to guide the adjustment of purge rate to minimize drawdown while purging.

During purging, field water quality parameters, including pH, temperature, specific conductance, oxidation-reduction potential, dissolved oxygen, and turbidity, will be measured to determine when stabilization of the groundwater is achieved. All measurements will be recorded in a field logbook. Field parameters will be measured every 3 to 5 minutes during purging. Field parameters are considered stabilized when at least the pH, temperature, and specific conductance substantially stabilized for three successive readings within the following limits:

• pH: ±0.1 pH units

• Temperature: ±1 degree Celsius (°C)

• Specific Conductance: ±3%

• Turbidity: ±10%

• Dissolved oxygen: ±10%

Table 1
Specifics for Laboratory Analyses for Groundwater Sampling at AOC 1

Analyses	Methods	Container	Vol.	Preservative	Holding Time
Alkalinity	SM2320B	Plastic, no headspace	250 ml	4° C	14 Days
Chloride	300.0	Plastic	250 ml	4° C	28 Days
Nitrate	353.2	Plastic	250 ml	4° C	48 Hours
Nitrite	SM4500NO <sub>3</sub> -F	Plastic	250 ml	4° C	48 Hours
Sulfate	300.0	Plastic	250 ml	4° C	28 Days
Sulfide	9030B	Plastic	(2) 250 ml	ZnOAC, NaOH, pH>9, 4° C	7 Days
Iron Speciation (Total, Ferric, Ferrous)	6010.0 Total iron SM3500-Fe D Ferric by subtraction	Plastic	500 ml	4° C	(24hr HT on Ferric)
Total Organic Carbon (TOC)	9060	Amber Glass	(2) 40 ml VOA Vials	H₂SO₄, pH<2, 4° C	28 Days
Dissolved Gases	RSKSOP-175	Amber Glass, Teflon Lined	(2) 20 ml VOA Vials	HCL, pH<2, 4° C. If CO <sub>2</sub> , 4° C.	14 Days preserved; 7 Days Unpreserved
Volatile Organics - 8260	8260C	Amber Glass, Teflon Lined	(3) 40 ml VOA Vials	HCL, pH<2, 4° C	14 Days
Manganese, Total	6010C	Plastic	500 ml	HNO₃, pH<2, 4° C	180 Days, Hg 28 days

Upon stabilization of field parameters, groundwater samples will be collected and placed directly into the appropriate (pre-preserved, as applicable) sample containers. All field parameters will be recorded on Groundwater Field Data Logs.

For wells that cannot be sampled using low-flow techniques, each well will be purged using a peristaltic pump a minimum of three well volumes prior to sample collection. During purging, field water quality parameters will measured as described above. It may not be possible to achieve the stabilization criteria outlined above using a peristaltic pump.

Groundwater samples will be collected and placed in laboratory supplied containers labeled with well number, date/time of sample collection, and method of analysis. Sample containers will then be placed in ice-filled coolers and prepared for shipment/delivery to the analytical laboratory, Alpha Analytical of Westborough, Massachusetts. Five (5) QC samples will be collected for each sampling event:

- Field Duplicates One field duplicate will be collected per sampling round
- MS/MSD One MS/MSD will be collected per sampling round.
- Blind Duplicate One blind duplicate will be collected per sampling round.
- Trip Blanks One trip blank will be collected per sampling round.

An ASP Category B Level data package will be requested for all groundwater analysis and data validation will conducted by a qualified third party validator. Data will be evaluated and qualification applied in accordance with the *USEPA Contract Laboratory Program National Functional Guidelines for Superfund Organic Methods Data Review*, USEPA-540-R-07-003, July 2007 and *USEPA Contract Laboratory Program National Functional Guidelines for Inorganic Data Review*, EPA-540-R-04-004, October 2004, as they applied to the analytical methods employed. A Data Usability Summary Report (DUSR) will be generated in accordance with USEPA Region II guidelines. All analytical data will be submitted to the New York State Department of Environmental Conservation (NYSDEC) in the standardized electronic data deliverable (EDD) format that is required for all data submitted, and this will be noted on the Chain of Custody.

The report will include a description of sampling methodology, results, discussion, conclusions, and recommendations for the next sampling round. Appended to the report will be any new boring and well construction logs, a summary table of well construction details, tabulated water level measurements, well hydrographs, groundwater contour map, a table of cumulative analytical results, graphs of cumulative concentrations for trend analysis, laboratory report with chain of custody forms, and projections for key analytes for reaching remedial goals.

The first Annual Report will include a Photolog in the appendices, showing each monitoring well in its current condition. In addition, a file with the Keyhole Markup Language – zipped (KMZ) for each will be provided so that the monitoring wells can be viewed in Google Earth Pro.

Each of the site wells are proposed to be sampled annually for the first five years to obtain a post-remediation baseline data set with the frequency of sampling being evaluated in the 5 year Periodic Review Report. The analytical parameters will be changed if deemed appropriate by the USACE or NYSDEC. Based on analytical results, select wells may be chosen to be sampled at a more or less frequent interval.

Data from the annual samplings will assist in further evaluating the post remedial aquifer conditions and determine the primary direction of groundwater flow. In addition, analytical data for the contaminants of concern in the groundwater at the site will be tabulated and graphed to assess the effectiveness of the monitored natural attenuation remedy for the groundwater. Any increasing or decreasing trends will be noted and related to the site groundwater flow conditions. Due to the varying nature of the flow at the site, modeling is not considered a good evaluation technique for determining the effectiveness of the remediation. Statistical analysis will be implemented if deemed appropriate based on the volume and nature of the data.

Per the DD for AOC 1, groundwater monitoring will continue until volatile COCs meet the NYSDEC Class GA standards, which are TCE (5 micrograms per liter ( $\mu g/l$ )), cis-1,2-DCE (5  $\mu g/l$ ) and VC (2  $\mu g/l$ ). If it is determined by the USACE, in coordination with the NYSDEC, that the criteria presented above has been met, then, monitoring of the groundwater beneath the landfill cap/soil cover will be terminated. All monitoring results will be provided to the property owner, NYSDEC, NYSDOH and the Albany County Health Department.

## 5.0 OPERATION AND MAINTENANCE PLAN

This Operation and Maintenance (O&M) Plan is intended to serve as a summary and guide for all the post-closure monitoring and maintenance at the Site. All aspects of the Site inspection and maintenance procedures shall be performed in accordance with this O&M Plan for the AOC 1 Landfill Cap/Soil Cover Site. O&M will be performed by USACE or its designee, subject to availability of funds. O&M will be undertaken by the property owner, in the event USACE is not funded to do so.

O&M shall be conducted following the monitoring, inspection, and maintenance procedures described in detail below, unless otherwise approved by the USACE and concurred by NYSDEC. Repairs to the cover system shall be performed with the materials of construction specified in the Closure Design Drawings and Specifications. The materials of construction, site grades, or construction methodology will not be modified without the approval of the USACE, unless otherwise directed in the O&M Plan.

All necessary equipment, personnel and materials to perform the monitoring, inspection, and maintenance of the landfill cover system will be utilized. Only equipment relative to the site O&M may be stored onsite. Care shall be taken to avoid damage to the site due to operations including, but not limited to, signs, fencing, vegetation (including trees and shrubs), wells, stormwater structures, landfill cover systems, etc.

If damage to the geosynthetic liner and underlying soil component is suspected, the affected area shall be exposed to allow for inspection and assessment of damage. Any damage to the geosynthetic layer or other cover materials must be repaired immediately by the party responsible for causing the damage. Specific monitoring, inspection, and maintenance procedures for the landfill cap system components are presented below.

#### 5.1 COVER INSPECTION

Appendix C contains a site inspection checklist for the final cover system (Form-1) addressing the various operations and maintenance components for the cover system. Figure 3 shows the landfill area. The USACE shall establish a permanent marking system at the site clearly delineating the inspection area, and inspect that area on an annual basis for the first 5 years after closure. While the landfill cover and cap inspections will be conducted for the foreseeable future, the frequency will be modified based on recommendations to be presented in the 5 year PRR for the site, and subject to availability of funds.

The inspector shall perform the work in an orderly fashion completing all of the items in the inspection area. The USACE shall follow the inspection procedures described on Form -1 and the reporting procedures presented below. All significant deficiencies shall be recorded on a 24-inch by 36-inch, as built O&M Drawing of the site. The locations shall be surveyed or accurately measured from known features at the site and the information shown to scale on the Drawings.

#### 5.2 GRASS COVER/TOPSOIL LAYER

The USACE shall visually inspect the grass cover on an annual basis using the approved inspection checklists (Appendix C, Form-1) for the first 5 years after closure per the DD, and with the inspection frequency modified based on any NYSDEC approved PRR recommendations, to continue for the foreseeable future, and subject to availability of funds.

The visual inspection shall include, but not be limited to, erosion, sinkholes, bare spots, dead species, and undesirable species. Bare or dead areas of vegetation shall be further examined for the possibility of leachate, erosion, or burrowing animals. The apparent cause of any damage shall be recorded in the inspection report.

The grass cover at the Site should only be mowed, at most, once yearly in the late fall. A two year rotation where one half of site is mowed each year would be optimal. Mowing should not be conducted when grass is wet. Trimming around existing features such as fences, equipment, drainage ditches, and other areas that cannot be reached with a mower, shall be completed as necessary with smaller (portable) equipment which will not damage the features (i.e., weed whips or grass trimmers). Additionally, vegetation greater than 2 inches in diameter shall be cut and treated with an approved herbicide. Mowers shall mulch grass and clippings shall be left in place. All other materials (i.e., cut vegetation) shall be properly disposed of offsite by the O&M Contractor, USACE contractor or the site owner.

If a need for fertilization is noted during the inspections, a soil test will utilized to determine what kind of fertilizer or liming may be needed. Only granular fertilizer shall be applied to maintain growth of the vegetation on the cover system. No liquid fertilizers shall be used. No fertilizer shall be applied within 10 feet of the stormwater drainage ditches or surface water. Application of herbicides and pesticides to control undesirable species shall not be permitted without written approval of USACE and the property owner. Any use of pesticides (i.e. herbicides and insecticides) shall be by a NYS licensed pesticide applicator.

Reseeding of the cover system shall be performed when deemed appropriate.

Sparsely vegetated areas shall be vegetated during the current or next planting season, as appropriate (e.g., if sparse vegetation is noted during the winter monitoring period, vegetation shall be initiated in the spring planting season). If seeding is not possible due to seasonal constraints, straw shall be spread over the sparsely vegetated areas to help control erosion. Vegetation shall be watered when required by the O&M Contractor to prevent loss due to drought conditions.

Insect infestation shall be addressed by USACE via contract with qualified licensed exterminators. Undesirable species discovered during visual inspections shall be exterminated if the USACE determines that their presence negatively impacts the integrity of the cover system. Insecticides shall not be applied until the insecticide contents have been approved by USACE and the property owner.

## 5.3 COVER SOIL AND CAP COMPONENTS

Similar to the grass cover, the cover soil and cap components shall also be visually inspected by USACE on an annual basis for the first 5 years after closure and per NYSDEC approved recommendations in the PRR for the foreseeable future, and subject to USACE's availability of funds. If damage to the geosynthetic and underlying soil component is suspected, the affected area shall be exposed to allow for inspection and assessment of damage. The inspection shall cover, but not be limited to, the following elements:

- Surface cracks and irregularities in the cover system;
- Presence and condition of vegetative growth;
- Presence of burrowing animals;
- Evidence of significant settlement, bulging or sinkholes;
- Signs of erosion damage;
- Signs of unstable conditions;
- Signs of leachate or waste breakthrough;
- Presence of ponded water or seepage;
- Evidence of unauthorized access such as vehicular tracks or disturbed cover soil;
- Presence of unauthorized dumping or vandalism; and,
- Damage to the underlying geosynthetic and soil components.
- Inundation caused by beaver activity

USACE shall complete the inspection checklist, Form-1 in Appendix C. Based on the inspection reports,

and the discretion of USACE, repairs to, or replacement of, the cover soil or cap components may be necessary. All repairs and/or replacements shall be made in accordance with USACE protocol in the Drawings and Specifications.

#### 5.4 COVER REPAIR PROTOCOL

The USACE (or in its absence due to funding considerations, the property owner) shall exercise care in performing repair work to or over the geosynthetic materials installed in the cover system. Criteria for the materials and placement procedures, including equipment restrictions over the geosynthetics, are described in the Drawings and Specifications. The USACE (or in its absence due to funding considerations, the property owner) would be responsible for conducting any repair work in compliance with these Specifications. The cover repair protocol for listed items is described below.

## 5.4.1 Surface Cracks

When surface cracks are observed, investigate cracks for depth and length. Note orientation with respect to the slope. Cracks that are greater than about 10 feet long, 8 inches deep and 2 inches wide that are parallel to the slope should be noted on the checklist and immediately reported to the USACE. Refer to the procedures below for Slope Stability to repair cracks deeper than 12 inches that are on mild slopes (i.e., slopes of 10% or less), and which appear to be the result of localized settlement or dry conditions. Repair cracks not related to general slope movement by filling with like material, compacting and reseeding area in accordance with the Specifications.

Responsibility: USACE (or in its absence due to funding considerations, the property owner).

# 5.4.2 **Vegetative Growth**

When vegetative stress is observed, visually check for cause (i.e. gas odors, leachate seepage, insect infestation, extreme dry periods, etc.). If grasses are stressed due to lack of fertilization, apply fertilizer as needed. If stressed due to lack of water, reseed affected area after dry period ends, only if stand has not reestablished itself within 2 months.

# 5.4.3 Responsibility: USACE (or in its absence due to funding considerations, the property owner). Vector Penetration

When burrow holes are observed, check area for damage to geosynthetics by carefully hand excavating test pit near burrow holes. Note and repair any damage to geosynthetics in accordance with Specifications. Replace original soil materials and hand compact. Reseed if necessary. If significant damage is observed, notify USACE and contract with exterminator to remove burrowing animals subject to USACE approval.

Responsibility: USACE (or in its absence due to funding considerations, the property owner).

### 5.4.4 **Settlement**

When settlement which begins to pond water is observed, determine extent of affected area. Record areas of settlement on the O&M Drawings. Categorize as small or large depressions and repair accordingly as described below:

## **Small Depressions**

In general, repair of small depressions (less than 1000 sq. ft, and capable of ponding 3 to 6 inches of water after a rainfall event) shall be as follows:

- 1. Clear vegetation.
- 2. Fill to grade with clean topsoil.
- 3. Compact with hand tools or a backhoe
- 4. Reseed.

## **Large Depressions**

In general, repair or large depressions created by settlement or general surface sloughing, (greater than 1000 sq. ft and/or capable of ponding more than 6 inches of water), not erosion, shall be as follows:

- 1. Remove final cover layers with a backhoe and hand tools.
- 2. Stockpile layers separately.
- 3. Carefully cut any geocomposite drainage layer with "hook" blades so as not to damage any LLDPE liner beneath.
- 4. Roll back geosynthetic drainage layer.
- 5. Examine the LLDPE liner. If LLDPE liner is damaged, call LLDPE liner contractor and proceed as follows: If LLDPE liner is undamaged, proceed to Step 9.
- 6. Remove damaged LLDPE liner and regrade the subsoil layer beneath it to match the grades in the adjacent undamaged areas. Ensure that the prepared surface grades to drain. Place and compact subsoil materials in accordance with the Specifications.
- 7. Repair LLDPE liner in accordance with the Drawings and Specifications, and as recommended by the vendor.
- 8. Roll back any geocomposite drainage layer or install new geocomposite drainage layer.
- 9. Tie geocomposite where cut with cable ties spaced at 5-foot intervals. Overlay geotextiles as required in the Specifications.
- 10. Replace excavated barrier protection soil.
- 11. Replace excavated topsoil and match surrounding grade.
- 12. Reseed.
- 13. Install hay bales above the remediated area when on a side slope.
- 14. Remove hay bales after grass has grown 6 inches.

Responsibility: USACE (or in its absence due to funding considerations, the property owner).

#### **5.4.5 Erosion**

Erosion may indicate that some portion of the stormwater management system is not functioning correctly. Examples of this could be sediment impeding water flow through culverts or differential settlement along drainage ditches contributing to stormwater overtopping the drainage systems. When erosion is identified, investigate these or other possible causes. Record areas of erosion on the O&M Drawings.

Responsibility: USACE (or in its absence due to funding considerations, the property owner).

When erosion rills or gullies are observed at least 4 inches in depth and at least 10 feet in length, repair will be made utilizing best management practices made on a case by case basis.

Responsibility: USACE (or in its absence due to funding considerations, the property owner).

If general sloughing is associated with the erosion, or it is expected that the geosynthetics may have been

damaged, repair in conformance with "large depressions".

Responsibility: USACE (or in its absence due to funding considerations, the property owner).

## **Slope Stability**

Any observable slope movement is serious in nature. Due to the low angle of slope at the AOC 1 site, slope movement is not considered a concern.

#### Seepage

Seepage is the subsurface movement of water from under the edge of the landfill cap. When seepage is observed by any party, notify the USACE and USACE (or in its absence due to funding considerations, the property owner) will repair this condition. Hand excavate materials to the level of the geosynthetics following the seepage path and check integrity of the membrane liner at the point of seepage origin. Take care not to damage geosynthetics during uncovering operations.

Responsibility: USACE (or in its absence due to funding considerations, the property owner).

# **Vandalism**

Report any vandalism, illegal dumping, or off road vehicle use to the local police authorities immediately. Concurrently, inform owner's security personnel of each occurrence (Northeastern Industrial Park Security Office/Front Gate telephone number is: 518- 861-5103). Repair damage from vandals to original condition. Refer to Specifications for materials and methods of construction.

# 5.5 RESPONSIBILITY: ANY INDIVIDUAL OR CONCERN ASSOCIATED WITH PROPERTY OWNER.STORMWATER MANAGEMENT SYSTEM

During site closure, erosion and sediment transport off-site was minimized by proper land grading, stockpiling of materials, and vegetative practices. Sediment transport off-site is minimized by the installation of silt barriers (e.g., silt fence and straw bales), proper stabilization of waterways, and stabilized construction entrances. Upon reaching final grade, the construction area was seeded and mulched to provide final stabilization of all disturbed areas.

The USACE (or in its absence due to funding considerations, the property owner) shall perform the monitoring, inspection, and maintenance of the stormwater management cover system. Care shall be taken to avoid damage to the site including, but not limited to, placement of signs, fencing, vegetation (including trees and shrubs), wells, stormwater structures, landfill cover systems, etc.

Appendix C contains a checklist and associated instructions for performing inspections of the stormwater management system (Form-2).

### 6.0 MAINTENANCE ACTIVITIES

The existing site perimeter fencing, including gates and signs, shall be inspected annually to ensure security. Any damage that is observed shall be recorded and repaired immediately by restoring or replacing the damaged materials.

In addition, all monitoring wells will be inspected annually. If there is any damage to the casings or well, this will be repaired.

Responsibility: USACE (or in its absence due to funding considerations, the property owner)

#### 6.1 REPORTING

All groundwater data generated during the reporting periods will be sent to NYSDEC in digital format (EDD) in accordance to the NYSDEC database standard.

A letter report shall be generated within 90 days of completion of each monitoring event which will summarize the groundwater analytical results. Monitoring reports shall present a comparison of the latest groundwater conditions with the New York State groundwater quality regulations. Additionally, all current and historical data generated in association with this SMP shall be presented in graphical and/or tabular format to highlight any groundwater quality trends that may arise.

The annual certification report will be generated to summarize the results of the long-term monitoring Program and O&M activities (e.g.: mowing, erosion control, week control, repairs to fence) performed. The objective of the Annual Report will be to confirm that the conditions of the IC/ECs are being met. An IC/EC Certification From and inspection form have been developed for the site for the assessment of overall site conditions or IC/EC's conditions, such as monitoring well and fence conditions (see Appendix B and C). These completed forms will be included with each annual report. The first annual report shall be submitted 90 days following the completion of the annual groundwater sampling event and inspection.

### **Periodic Review Report**

A Periodic Review Report (PRR) will be submitted every five years after the start of annual sampling (anticpated to begin April 2014), unless the frequency is changed in a subsequent PRR. The PRR will be prepared in accordance with NYSDEC DER-10 and submitted within 45 days of the end of each certification period. Groundwater sampling results will also incorporated into the PRR. The report will include:

- Identification, assessment and certification of all ECs/ICs required by the remedy for the Site;
- Results of the required annual Site inspections and severe condition inspections, if applicable;
- All applicable inspection forms and other records generated for the Site during the reporting period in electronic format;
- Data summary tables and graphical representations of contaminants of concern which include a listing of all compounds analyzed, along with the applicable standards, with all exceedances highlighted. These will include a presentation of past data as part of an evaluation of contaminant concentration trends:
- Results of all analyses, copies of all laboratory data sheets, and the required laboratory data deliverables for all samples collected during the reporting period will be submitted electronically in a NYSDEC-approved format;
- A Site evaluation, which includes the following:

- The compliance of the remedy with the requirements of the Site-specific Decision Document;
- Any new conclusions or observations regarding Site contamination based on inspections or data generated for the groundwater being monitored;
- Recommendations regarding any necessary changes to the remedy and/or SMP; and
- The overall performance and effectiveness of the remedy.

The PRR will be submitted, in electronic format, to the USACE-New York District, the site owner, NYSDEC Central Office and the NYSDOH.

#### 6.2 NOTIFICATIONS

Notifications will be submitted by the property owner to the NYSDEC as needed for the following reasons:

- 60-day advance notice of any proposed changes in site use that are required under the terms of 6 NYCRR Part 375, and/or Environmental Conservation Law.
- Notice within 48-hours of any damage or defect to any engineering control that reduces or has the potential to reduce the effectiveness of an Engineering Control and likewise any action to be taken to mitigate the damage or defect.
- Verbal notice by noon of the following day of any emergency, such as a fire, flood, or earthquake that reduces or has the potential to reduce the effectiveness of Engineering Controls in place at the site, with written confirmation within 7 days that includes a summary of actions taken, or to be taken, and the potential impact to the environment and the public.
- Follow-up status reports on actions taken to respond to any emergency event requiring ongoing responsive action shall be submitted to the NYSDEC within 45 days and shall describe and document actions taken to restore the effectiveness of the ECs.
- Any change in the ownership of the site or the responsibility for implementing this SMP will include the following notifications:

At least 30 days prior to the change, the NYSDEC will be notified in writing of the proposed change. This will include a certification that the prospective purchaser has been provided with a copy of the Decision Document and all approved work plans and reports, including this SMP. Within 15 days after the transfer of all or part of the site, the new owner's name, contact representative, and contact information will be confirmed in writing.

A summary of the responsibilities of the Owner and the Remedial Party is presented in Appendix F.

### 6.3 SITE CLOSEOUT

The remediation goals, as stated in the Decision Document for the AOC 1 Site, were as follows:

To eliminate to the extent practicable:

• Eliminate or minimize the human health risks posed by TCE, VC, 1,2-DCA, and total-1,2-DCE in groundwater within the landfill by satisfying the Class GA groundwater standards ARARs for these analytes. This remedial action objective will be satisfied by prohibiting potable use of groundwater in the vicinity of AOC 1 (the VOC ARARs will be satisfied with a groundwater use easement granted by the property owner; the easement is considered an institutional control), and supplemented with groundwater MNA (and monitoring of VOC concentrations). Metals (arsenic, vanadium, selenium and antimony) also pose an unacceptable risk in groundwater. The presence of these metals will be

addressed by the environmental easement prohibiting potable use of groundwater at AOC 1. Metals are not included as COCs for groundwater because the concentrations are not expected to be treated by MNA and therefore will not be monitored over time, as will be the case with VOCs;

- Although soils have not been completely characterized, the remedial action will eliminate the soil
  exposure pathway because the landfill cap and cover will prevent physical access to the affected soil;
- Mitigate the potential for future releases of contaminants in the landfill to groundwater. This remedial action objective will be satisfied with the landfill cap over the groundwater plume. If it is discovered that the landfill cap and soil cover systems has been damaged, the need to resume groundwater monitoring activities will be reevaluated, and,
- Mitigate the potential for movement and offsite migration of TCE, VC, 1,2-DCA, and total-1,2-DCE from the groundwater plume within the landfill. This remedial action objective will be satisfied with the landfill cap over the groundwater plume.

To analyze the effectiveness of the remediation, groundwater monitoring and inspections will be conducted as presented in this SMP. Per the DD for AOC 1, groundwater monitoring will continue until volatile COCs meet the NYSDEC Class GA standards, which are TCE (5 micrograms per liter ( $\mu$ g/l)), Total-1,2-DCE (5  $\mu$ g/l) and VC (2  $\mu$ g/l).

If it is determined that the criteria presented above has been met, utilizing NYSDEC approved statistical validation, USACE, (in coordination with NYSDEC and NYSDOH), will terminate monitoring the groundwater beneath the landfill cap/soil cover. USACE will notify the NYSDEC, NYSDOH and the Albany County Health Department, when and if, groundwater monitoring activities are terminated. Inspections of the landfill cap and soil cover will be performed by USACE (or in its absence due to funding considerations, the property owner) for the foreseeable future. If it is discovered that the landfill cap and soil cover systems has been damaged, the need to resume groundwater monitoring activities will be reevaluated.

#### 7.0 REFERENCES

ACEMC, 1980. Albany County Environmental Management Council. "Northeast Industrial Park (Voorheesville Depot) and Vicinity, Closed Landfill Study", June 25, 1980.

EAEST, 1999. EA Engineering, Science and Technology "Revised Draft Investigation Report. Archival Search Former Schenectady Army Depot - Voorheesville Area", dated August 1999. EA, 2003. Archive Search Report.

H2H Associates, LLC, 2014, Final Engineering Report, Landfill Cap and Soil Cover, Area of Concern 1, Northeast Industrial Park, Guilderland, New York, January 2014 (Pending).

H2H Associates, LLC, 2012, Pre-Design Investigation Work Plan Northeast Industrial Park Area of Concern 1 & 7, November 2012.

Parsons ES, 1998. "Final Preliminary Assessment Report Voorheesville Depot", prepared by Parsons Engineering Science, Inc., December 1998.

Parsons, 2007. Remedial Investigation Report, Former Schenectady Army Depot Voorheesville Area. May 2007.

Parsons, 2010. Focused Feasibility Study for Areas of Concern 1 and 7 Former Schenectady Army Depot Voorheesville Area Guilderland, New York. June 2010.

Parsons, 2011. Proposed Plan For Areas Of Concern 1 And 7 Former Schenectady Army Depot Voorheesville Area Guilderland, New York. February 2011.


URS, March 1996. Final Chemical Data Acquisition Plan. Remedial Investigation at the Former Voorheesville Army Depot, U.S. Army Southern Disposal Landfill Guilderland, New York.


USACE, 1999. "Draft Phase II Work Plan for Former Schenectady Army Depot – Voorheesville Area", prepared by USACE Baltimore District, June 1999.

USACE, 2011. Final Decision Document, Former Schenectady Army Depot Areas Of Concern 1 And 7: U.S. Army Southern Landfill And Triangular Disposal Area Formerly Used Defense Site.

U.S. Army Toxic and Hazardous Materials Agency, 1980. "Historical Summary and Report of Findings at Schenectady General Depot, Guilderland, New York, July 1980.

# **FIGURES**





# APPENDIX A

**Monitoring Well Logs and Monitoring Well Construction Data** 

TABLE 1

# Monitoring Well Survey and Construction Details AOC 1 - Site Management Plan Northeastern Industrial Park, Guilderland, New York


WELL I.D.	Hydrogeologic Unit	Boring Depth* (feet below ground surface)	Screen Length (in feet)	EASTING	NORTHING	GR. Elevation (feet AMSL)	MP Elevation (feet AMSL)	TOC Elevation (feet AMSL)
2BMW-9	Shallow (Till)	25	15	640359.70	1401828.14	325.9	330.07	330.32
ACE-3	Shallow (Glaciolacustrine)	15	10	640050.67	1402036.90	321.6	324.24	324.43
ACE-4	Shallow (Glaciolacustrine)	15	10	640007.28	1402347.53	323.1	325.54	325.77
ACE-5	Shallow (Till)	15	10	640494.65	1402133.51	321.0	322.72	323.17
ACE-6	Shallow (Till)	20	10	641038.60	1400791.15	328.3	330.59	331.49
GW-03	Shallow (Till)	25	5	640427.01	1401197.67	321.2	323.99	324.16
GW-11R	Bedrock (Upper 55')	142	Open Hole	641037.73	1400806.54	328.3	329.81	332.23
GW-12	Shallow (Till)	8	5	641507.22	1400557.37	323.5	325.11	326.71
GW-13	Shallow (Till)	8	5	641010.73	1401331.93	320.8	323.53	323.77
GW-14	Shallow (Till)	8	5	640794.77	1401668.21	320.4	323.74	323.85
MW-13-01 **	Shallow (Till)	10.3	5	641294.20	1400330.00	326.8	329.53	329.73
MW-13-02 **	Shallow (Till)	11	5	641010.73	1401331.93	325.7	328.17	328.46
MW-13-03 **	Shallow (Till)	13.6	10	640794.77	1401668.21	322.0	324.01	324.94

AMSL - Above Mean Sea Level

Survey data based on H2H topographic survey dated November 2012

<sup>\*</sup> Based on original boring logs.


<sup>\*\*</sup> Well drilled after remediation.



	<del></del>	HTW DRILLIN	G LOG				HOLENO.
1. COM	PANYNAME CO.	Neultants, Inc. 200	UFFA/C	Drilling	Comis	gv i	SHEET 1 OF 3 SHEETS
3. PROJ	er Voorhesuill	L. Army Deput-Southern i	ANDFILL 6	wilder la	J. Ne.	w Year	4
5. NAME	- OF OBILLER	ANDNER	6. MAI	CME-5	GNATION OF DRI	ш	
	SAND TYPES OF DRILLING : SAMPLING EQUIPMENT	- 41/4-inch HSA		E LOCATION			
		- 2-inch CArbon Split-slow SAM		RFACE ELEVATION	29 F	est 1	AMSL
		0. 1	10. DAT	E STARTED   16	11.	DATE COMPLE	196
12. OVER	RBURDEN THICKNESS	at Determined	15. DEP ~5.	TH GROUNDWATER	be ow	land so	orface (bis)
13. DEPTI		ot Applicable	4.14	TH TOWATER AND E	our days	After	COMPLETED
14. TOTAL		5.0 Feet	17. OTH	ER WATER LEVEL ME	EASUREMENTS (	SPECIFY)	0
18. GEOTI	ECHNICAL SAMPLES  N.C.VE	: DISTURBED . UN	IDISTURBED 19.	TOTAL NUMBER OF	CORE BOXES		
20. SAMP	LES FOR CHEMICAL ANALYS	SIS 70C METALS	OTHER (SPECI	FY) OTHER (SPE	CIFY) OTH	ER (SPECIFY)	21. TOTAL CORE RECOVERY
22. DISPO	NONE DITION OF HOLE	BACKFILLED  MONITORING V	VELL OTHER (SPECI	FY) : 23. SIGNAT	TURE OF INSPEC	TOR	**
	OSITION OF HOLE  ORING WEI	Screens 4.0-14A		Dar	me /	(d. 1	lella
ELEV.	DEPTH b	DESCRIPTION OF MATERIALS	FIELD SCREENING	GEOTECH SAMPLE OR CORE BOX NO.		BLOW COUNTS 9	REMARKS h
	=Brown	N regraded silty SAND	ŝ			5	
	- AND	sandy silt, some evel and wood g ments	/			_	
-	= UCA	avel and wood	1.8				DRY
	1 - J.	a ments	0.0			15	
		1					
		1	/			32	E
	2-						
			,	El .		36	
			0.0	UONE	VONE	27	E
	3=			2	?		
			0.0			16	CLIF
	= 7	un mottled silty	<b>/</b>			13	.Slight = Sulfur odon =
	4 = 16	on money sing					
	/ = CP4/*	. Medium Stiff.	0.0/			4	F
,		1	0.0		1 1	5	
_	5 =	↓		<u> </u>			
		Scuttery Langell	esuille ARM	Y Deget INVESTICA	+ +101	HOLENO.	ACE-3
98F-07711 (	CE I HTWEL	Jan Jany W		,	•		

PROJECT DENTHEESVILLE	( 4 )				I	HOLENO. ACE-3	
, , , , , , , , , , , , , , , , , , , ,	PROJECT FORMER VOLVE HEEN: ILE ARMY PEROJ - LANDRILL DANIEL M. Shellow						
ELEV. DEPTH	DESCRIPTION OF MATERIALS	FIELD SCREENING RESULTS d	GEOTECH SAMPLE OR CORE BOX NO. e	ANALYTICAL SAMPLE NO.	BLOW COUNTS	REMARKS h	
· · · · · · · · · · · · · · · · · · ·	brown sand sitty silty sand seams.				5	WETATSO FEET	
6 - Loose	to Medium Dense				4		
	( <i>St</i> 1)				4		
7-		0.0/		7	5		
		10.0			9		
					7		
	- Trace to Some Chy			j	Ч		
a = -	<u></u>	0.0/			3	- WET	
6 RAY	I SANDY Chy(SC). to Very SOFT.	0.0			2		
, =	1 1809 3011.		NE	- 3NE	3		
/0 ==	·		No	/\/			
12					<del></del>		
/2- <u>-</u>							
13—	,						
	·	0.0			/		
14	POJECT: FORMER VEIGTHERSU: TI	10.0	Defet	-	Z HOLENO.	ACE-3	


ROJECT	,,	HTW DRILLING	INSPECTOR				HOLE NO. ACE -3
UMCI	e Verivi	heesville ARMY PEROJ-LANDFILL	DANIE FIELD SCREENING	GEOTECH SAMPLE		BLOW	OF 3 SHEETS
LEV.	DEPTH b	DESCRIPTION OF MATERIALS c	RESULTS	OR CORE BOX NO.	SAMPLE NO.	COUNTS	REMARKS h
	$\exists$	GRAY SAND, Clay, AS ABJUE (SC)		NONE	NONE	1	
	rs —	Borny Completed at					
		IE a Fact. Installed					
		2" 000000000000000000000000000000000000		•			
		Borny Completed At 15.0 Feet. Installed 2" PVC Monitoring well. Well screenED From 4-14 F.					4
		Mell 201 sever 110M 4 - 14 Et					
	=		·				
	=				·		
	$\exists$						
į.	=						
			·				
1	=	<u> </u>					
1			<u> </u>				



		HOLENO. ACE-4					
PROJECT FORMEI	n Veriri	heesville Alany DEGOT-LANDRILL	INSPECTOR DANIE	ELM. S.	helder	,	OF 3 SHEETS
ELEV.	DEPTH b	DESCRIPTION OF MATERIALS C	FIELD SCREENING RESULTS d	GEOTECH SAMPLE OR CORE BOX NO.	ANALYTICAL SAMPLE NO.	BLOW COUNTS	REMARKS h
		Chy, AS ABOVE		JONE	NONE	1	
	15 = = = = = = = = = = = = = = = = = = =	Borry Completed At 15.0 Feet. Installed 2" PUC MONITORING Well Well ScreenED From 4-14 F	7	-			
-				·			
				·		•	
				•			
	F 2/HTWDL	PROJECT: FURMED VECTIVES	: II.a. ARM	Delet		HOLEN	a. ACE-4

URSF-077/2 OF 2/HTWDL

PROJECT: FIRMER Verringsville ARMY Defet



HTW DRILLING LOG	HOLENO. ACE-5
1. COMPANY NAMES CONSULTANTS INC. 2 DEBLING SUBCONTRACTOR DVILLAGE COMPANY	SHEET 1 OF 3 SHEETS
3 PROJECT FORMER VOW WESU ! L. Army Regut - Southern LANGE! 4 LOCATION ( Out Her LANGE, New York to	τ
5. NAME OF DRULER  JOESSE GRANDON OF DRILL  6. MANUFACTURERS DESIGNATION OF DRILL  ME-55	
7. SIZES AND TYPES OF DRILLING : 84 HOLELOCATION AND SAMPLING EQUIPMENT - 444-inch HSA Northeast portion of landt	
- 2-inch captain steel 9. SURFACE ELEVATION SOLIT-GOOD SAMPLED 318.52 Feet A	
10. DATE STAPTED 11. DATE COMPLE 6/2	
12. OVERBURDEN THICKNESS NOT DETERMINED 15. DEPTH GROUNDWATER ENCOUNTERED WET At ~ 8.0 Feet	
13. DEPTH DRILLED INTO ROCK Nort Applicable 16. DEPTH TO WATER AND ELAPSED TIME AFTER DRILLING 13. 30 Pt. b/s 14 hrs. After	COMPLETED
14. TOTAL DEPTH OF HOLE  15. 0 Feet  17. OTHER WATER LEVEL MEASUREMENTS (SPECIFY)  2. 75 F1. (TON) ON 7/23/9	76
18. GEOTECHNICAL SAMPLES DISTURBED UNDISTURBED 19. TOTAL NUMBER OF CORE BOXES	
N C.JE  20. SAMPLES FOR CHEMICAL ANALYSIS  VOC  METALS  OTHER (SPECIFY)  OTHER (SPECIFY)	21. TOTAL CORE
NONE	RECOVERY 2%
22. DISPOSITION OF HOLE  BACKFILLED XMONITORING WELL OTHER (SPECIFY)  23. SIGNATURE OF INSPECTOR  SCREAUSO  1	11/0
1 Gentle Well S-15 Pt. Janua Mil. C	Lelie
ELEV. DEPTH DESCRIPTION OF MATERIALS RESULTS OR CORE BOX NO. SAMPLE NO. COUNTS  a b c         3	REMARKS h
=Gravel AND Silt.	Moist-WET
- LOOSE.	·
=Brown sandy s; It, some 00	E
1 - medium to Coarse grave!	
= Few F-C SAND MAHMYS 10.0	E
TRACE Clay. Dense /	
Z= to Very Dense (Till)	E
	F
5M-GM 22 17	244
3 = /	
$=$ $\left  \begin{array}{c c} & \\ \hline \end{array} \right  \left  \begin{array}{c c} 27 \\ \hline \end{array} \right $	=
= 35	E
4 = Color charge	
togray of 0.0/ 17	
= 4.0 Feet	F
= $0.0$ $18$	E
==OJECT! FORMER VOUR HEESV! HE ARMY DEGET HOLENO.	


LASE-07711 OF CHINDL

	HTW DRILLIN	G LOG				HOLENO.ACE-4
1. COMPANY NAME CON	sultants INC. 1	HLING SUBCONTRAC	Drilling	- Com	MN4	SHEET 1 OF 3 SHEETS
3. PROJECT Former Vow hesuille	Army Degot - Southern L	AND FILL	OU; Der LA	wil, Ne	ow You !	ć
5. NAME OF DELLER  JOESPE CO	•	6.	MANUFACTURER'S DES	SIGNATION OF D	AILL	
7. SIZES AND TYPES OF DRILLING : AND SAMPLING EQUIPMENT	- 41/4-iNCL HSA	8.	HOLE LOCATION			
<u></u>	- )-INCL (Arbon Stell Mit-Spon SAM	les	SURFACE ELEVATION 32	0.68	feet H	MSL
<u></u>	0 0	10.	DATE STAPTED 6/4	6	DATE COMPLE	196
2. OVERBURDEN THICKNESS NO	+ DetermineD	15.	S.O. F.J. be		SWFARE	(6/3)
	+ Applicable	16. 2.	DEPTH TO WATER AND 91 F4. (TOA)	FOUR A		er drilling
A TOTAL DEDTU OF MOLE	.o Fæt	17.	OTHER WATER LEVEL N	MEASUREMENT	S (SPECIFY)	<b>U</b>
8. GEOTECHNICAL SAMPLES	DISTURBED U	NDISTURBED	19. TOTAL NUMBER O	F CORE BOXES		
0. SAMPLES FOR CHEMICAL ANALYSIS	S VOC METALS	OTHER (S	PECIFY) OTHER (SF	PECIFY) O	THER (SPECIFY)	21. TOTAL CORE RECOVERY
NONE	BACKFILLED #MONITORING	WELL OTHER (S	PECIEVA 23 SIGNA	ATURE OF INSP	ECTOR	*
Z. DISPOSITION OF HOLE  TAX talled 2 PV	Screene 40-14.0	0	D	nīu		lella
LEV. DEPTH	DESCRIPTION OF MATERIALS	FIELD SCREEN	GEOTECH SAMPLE OR CORE BOX NO	E ANALYTICAL SAMPLE NO		REMARKS h
= F://a	rearabed Nonk	11042-19			ч	
- ares	regraded DAAK SAND, silt AND el. Loose to Dium Dense	0.0/	/			
= 0 / 1	el loose to	0.0/	į		2	DAY
1 = me	Dium Dense				12	
= /	1	10.0			7	
=		/			/	
2 =		i 	_			
=		!			17	
=		0.0/		VE VE	'	
	<u> </u>	_ /	NONE	NONE	10	
= 711	WN mother chyes	, /0.0	? ?		9	
= c.14	UN mottles chyen	D)				i
= 311) = MEA	Dium STIFF (ML	<b>S</b>			10	
4 = 1		/	,		7	
		0.0/			ا د	•
- =		10.0			4	
7 -	PROJECT: FORMER VOURHE	resuille A	RMY DEROT	<u>i</u>	HOLE NO.	ACE-4
-077/1 OF 2.HTWDL	Scuttern LANDFILL	Ne media	1 INVEST	gation		• •

		HTW DRILLING					HOLENO. ACE-4
PROJECT CAMC!	n Verri	heaville Army Pigoj-LANDFII	INSPECTOR DANIE	C M. S	heldos		SHEET 2 OF 3 SHEETS
ELEV.	DEPTH	DESCRIPTION OF MATERIALS	RESULTS	GEOTECH SAMPLE OR CORE BOX NO.	ANALYTICAL SAMPLE NO. (	BLOW COUNTS g	REMARKS h
		Brown SANdy si H with				3	WETAT S.O'
		Brown SANDY S; H with Some F-C S; Hy SAND PARTNYS AND SEAMS			·	7	
	6-	(ML/SM)				5	-
			0.0				
	7 =					5	
			0.0			6	
	$\mathcal{B} = \overline{\overline{\overline{\overline{\overline{\overline{\overline{\overline{\overline{\overline{\overline{\overline{\overline{\overline{\overline{\overline{\overline{\overline$		/			7	
			00/			7	
	9-			(,)		4	
			0.0	VANE	NONE	7	
,	/o-=	\( \sqrt{-} -			~		Claves
		GRAY (lay, some Sitty sand seams (U-SC)					Clayey drill cuttings at 10 Ft.
	,, =	Sitty sand semms (U-Sc)					At 10 Ff.
/	// = = = = = = = = = = = = = = = = = =						
						•	
1	/z						
	7=					<u> </u>	
			0.0			,	
	14 =	PROJECT! FIRMER Veriture:			1	ı	

		HTW DRILLI					HOLENO. ACE-5
PROJECT	n Veurh	esville ARMY DEGOT-LAND	INSPECTOR  DANIE	CM. S.	heldo:		SHEET Z. OF 3 SHEETS
ELEV.	DEPTH	DESCRIPTION OF MATERIALS	FIELD SCREENING RESULTS d	GEOTECH SAMPLE OR CORE BOX NO. e	ANALYTICAL SAMPLE NO. f	BLOW COUNTS 9	REMARKS
		As ABOVE	_			21	· · · · · · · · · · · · · · · · · · ·
	6 —		0.0			21	PArting 5.5 to 6.0 Fact
	7		0.0			<i>31 33</i>	
	8		0.0			17 15	WET
	/		0.0	- NONE	- NONE	7Z 30	
	//					<u> </u>	
	ルー:			-			
	3 = = = = = = = = = = = = = = = = = = =		0.0/			9	Slightly Moist
F-077/2 O	F 2/HTWDL	PROJECT: FORMER VOICTA	WESU: He ARMY	Defet		HOLENC	ACE-5

	HTW DRILLING					HOLENO. ACE-S
PROJECT Formen Voor	heesville ARMY PEROT-LANDFILL	nspector <i>Dan i E</i>	GEOTECH SAMPLE	heldo.		SHEET OF SHEETS
ELEV. DEPTH	DESCRIPTION OF MATERIALS  C	FIELD SCREENING RESULTS d	GEOTECH SAMPLE OR CORE BOX NO. e	SAMPLE NO.	COUNTS	REMARKS
	AS ABOVE		NONE	NONE	29 31	Moist F-C SAND Partings 14.3-15.0 Feet
	Baring Complated At  15.0 Ft. Dry Upon  Completion. Installed  2" PUC MONITORING Well  SCREENED From 5-15 FT.		•			
-0777/2 OF 2/HTWDL	PROJECT: FORMER VOOThesuil	le AKMY	Delot		HOLENO	ACE-S



	HTW DRILLI	NG LOG	<del></del>		HOLENG HOE-G
1. COMPANY NAME		OBBLING SUBCONTRACTOR	rilliale (	Company	SHEET 1 OF 3 SHEETS
3. PROJECT FORMER VCOV hesu.//	L. Army Digot-Southern	LANDEN 6. MANU	FACTURER'S DESIGNAT	New Yor	
7. SIZES AND TYPES OF DRILLING AND SAMPLING EQUIPMENT	- 414-INCH HSA - 7-INCH CAYBON. Glit-GOON SA	Steel Adjace	LOCATION,  LOCATION  ACE ELEVATION	ting well H	
	0 0	10. DATE		11. DATE COMPLE 6/25	
12. OVERBURDEN THICKNESS	et Determined	15. DEPTI	GROUNDWATER ENCE NOT EN	CONTERED FOR	
	of Applicable	16. DEPTI-	TO WATER AND ELAPS	SED TIME AFTER DRILLING	COMPLETED
14. TOTAL DEPTH OF HOLE	20.0 Feet	8.15		ON 7/23/9	16
18. GEOTECHNICAL SAMPLES  N. C. NE	DISTURBED		OTAL NUMBER OF COR		A TOTAL CORE
20. SAMPLES FOR CHEMICAL ANALYS	SIS /OC META	LS OTHER (SPECIFY	OTHER (SPECIF)	OTHER (SPECIFY)	21. TOTAL CORE RECOVERY
22 DISPOSITION OF HOLE " PV C FACE TO/LES 2" PV C MONITORINI WELL		cd	23. SIGNATURE	OF INSPECTOR	lella
ELEV. DEPTH b	DESCRIPTION OF MATERIALS c	FIELD SCREENING I G RESULTS JAMES	EOTECH SAMPLE AN OR CORE BOX NO. SA e	IALYTICAL BLOW MPLE NO. COUNTS f g	REMARKS h
Fill	3 regraded brown			4	
- SANO - MAN	ly silt AND Silty Score concrete.	0.0		//	
1 - Orau	ly silt And silty some concrete, el and wood Fragmen Dium Dense.	ts. 10.0		8	
ME	Dium Dense.			10	
2—				9	
=		0.0/		7	
3 —		10.0		13	
<u></u> 		/		14	
4 =		0.0/	<u> </u> 	10	
<u> </u>		0.0		18	
3 — RSF-077/1 OF 2.HTVCL	Southern LANDFIL	Heesville ARM	Negot Negot	HOLE NO.	ACE-6

URSE-077/1 OF 2.HTWCL

	<del></del>	HTW DRILLING	LOG				HOLENO. ACE-6
PROJECT	n Verri	heesville Alany PEGOT - LANDFILL	INSPECTOR DANIE	EL M. S.	helde:		SHEET Z OF 3 SHEETS
ELEV.	DEPTH b	DESCRIPTION OF MATERIALS C	FIELD SCREENING RESULTS	GEOTECH SAMPLE OR CORE BOX NO.	ANALYTICAL SAMPLE NO. 1	BLOW COUNTS g	REMARKS h
a	6 7 8 9 10 11 12 13 14	DENSE to Very Densie brown sandy silt, some gravel of varying lithologies (Till)  SM-GM	0.0/	- NONE	NONE -	24 29 69 67 77/3	Augeral to lost for Next sample.  -Slightly Moist  Very hard:  14 Feet,  15-16.5  Feet.
ISF-077/2 O	F 2/HTWDL	PROJECT: FRAMER VERY NOTO	IE HKMT	OCTOT	•	HOLENO	ACE-6

		HTW DRILLING					HOLENO. ACE-6
PROJECT Former	n Voor	neesville Army PEROJ-LANDFILL	INSPECTOR  DANIE	C M. S	heldo:		SHEET 3 OF 3 SHEETS
ELEV.	DEPTH b	DESCRIPTION OF MATERIALS	FIELD SCREENING RESULTS	GEOTECH SAMPLE OR CORE BOX NO.	ANALYTICAL SAMPLE NO.	BLOW COUNTS	REMARKS
		As Above, color charge to bank gray At 1884.					
•	15		0.0			30	DRY
	17————————————————————————————————————		/	NONE	NONE	- 24	
	/9————————————————————————————————————		0.0				Day to Slightly Moist
		Borns completed At 20.0 Feet. Auger refusal At 19.5 ft. Installed 2" PUC Well screened from		-			
	F 2/HTWDL	Well Screened from 7-17 Feet. Well dry  your completion.  PROJECT: FORMER VOOR NEED: FORMER LANDER	Alm			HOLENO	ACE-6

				OFM REMEDIATIO	n services corp.		PAG	8 1 OF	3	
PROJ	ECT NU	1BER 92	85					E HOLE NO.	<del></del>	
CLIE	NT Sch	nenectad	y 1		LOCATION Guilderland, New York					
DRIL	LING O	NIRACIO	R OHM		DRILLING EQUIPMENT Mobile Drill B-53					
HYDR	OGEOLO	IST To	kes Adesi	da	DRILLER Carlos	Puente				
DATE 10/4	START /90	/ TIME 8:30	<b>DA</b> 10	TR FINISH / TIME /4/90 12:10	SURFACE TOTAL ELEVATION 323.39 DEPTH 25'				,	
WELL	CASIN	SOH 4	0 80	REZEN TYPE SCH 40	LENGIH 15		SL	<b>T</b> 20		
			GROUNDHAT	gr ·		CASING	CORE	SAMPLER	TUBE	
DAT	В	TIME	DEPIH	DEPTH VEATHER TYPE PVC SS						
10/5/9	90	12:15	23.0′	SUNNY	DIAMETER	4"				
REMAI	RKS				HAMMER WEIGHT			140 lb.		
				·	PALL			30′		
	CAMPA	BLOW			BORE HOLE	LOG			GRAPHIC	
DEPTH	NO.		RECOVERY	LITHOLOGIC	C DESCRIPTION		R	MARKS	LOG	
-	S-1	6, 6, 7, 8	12"	0-2.0': Loose dark goccasional medium-cost	gray silty sand, arse gravel, nume	erous	12" R PID <b>=N</b>	ecovery )		
1 -				Tools					0f SCH 40 PVC casing	
-										
2 -	S-2	8, 7, 8, 8	NR	2.0'-4.0': Loose dan occasional medium-coa roots	ck gray silty sar arse gravel, nume	nd, erous				
3 -										
4	S-3	2, 2, 2, 2, 2	12"	4.0'-6.0': Dark blac medium-coarse SAND be clay some medium-coar occasional decomposed	ck-brown clayey s ecoming dark gray se sand layer, s l roots.	ilt with	Moist at 5.0 PID⊨NI	– wet )/ )		
5 —										
6 -	<b>S</b> –5	5,10, 13,17	10"	6.0'-8.0': Gray silt medium sand, few medi	y clay, trace fi um-coarse quartz	ne- gravel	Slight PID=N	ly wet		
7 —			·						15' of .020 slot	
8 <del>-</del> - - - 9 <del>-</del>	S-5	19,27, 37,50	10"	8.0'-10.0': Gray sil medium sand, few medi becoming light compace mottled	ty clay, trace f um-coarse quartz t silty sand wit	ine- gravel, h gravel	Slight Auger 15.0'	ly wet down to	SCH 40 PVC	
10—	·							·		

PAGE 2 OF 3

PROJECT NUMBER 9285

BORE HOLE NO. 2BMW-9

CLIENT Schenectady 1

LOCATION Guilderland, New York

	CAMDI D	BLOW	RECOVERY	BORE HOLE LOG		CRAPHIC
DEPTH	NO.	PER 6"	RECOVERY	LITHOLOGIC DESCRIPTION	REMARKS	GRAPHIC LOG
·						
-						
11						
12—						
12—		·				
13-	·					
13—					.*	
-						
14-			·			
-						
15—		70/3"	۵	15.0′-17.0′:	Continue	
-				Coarse quartz gravel	augering, formation very tight.	
16—						
-						
17			·			
-						
18						
-						
_	•					
19						
_						
20 <u> </u>		26,37 50/2"	6"	20.0'-22.0': Brown-black silty sand with very gravel becoming gray hard very-fine sandy silt	Moist at 20.5' At 24.0' drilling very hard PID=0.4 ppm	
=		Ì	-		PID=0.4 ppm	
21—		ł				
-	77.04					
22—	}					
-	ļ					
23_						

PAGE 3 OF 3

BORE HOLE NO. 2BMV-9

PROJECT NUMBER 9285

CLIENT Schenectady 1

LOCATION Guilderland, New York

	SAMPLE	BLOW			BORE HOLE LOG		CRAPHIC
DEPTH	NO.	PER 6"	RECOVERY	IJ	THOLOGIC DESCRIPTION	REMARKS	LOG
24— - - - - - 25—		40, 100/3"	6"	24.0'-26.0': gravel	Dark gray very stiff silty	PID in augers= 100 ppm No water in hole. Decided to set well with sand pack and wait to see any recovery into the well.	
26— - - 27—						Set PVC screen 7'-22' PVC casing 7.0' to surface with 3.0' stick up. Sand pack from bottom up to 5'. Allow well to recover. Move to another location to drill 2BMW-10. 10/4/90 3:30 8" of water inside PVC	
28 - - 29 - -						3:30 8" of water inside PVC decided to complete well with the bentonite seal from 3'-5' Allow to set for 1 hour then cement-bentonite grout to the surface.	
11						Surface.	
3							

				OHM REMEDIATIO	IN SERVICES CORP.		PAG	E 1 OF	_6			
PRO	iect nu	MBEER 92	285				BOR	E HOLE NO.	AMW-11			
an	NT Sc	henectac	ły 1		LOCATION Guile	derland,	New York	k				
DRII	LING O	ONIRACIO	IR 1)OHM	2)ECD & Boring, Inc.	DRILLING EQUIPMENT 1)Mobile Drill B-53 2)CME 75							
HYDE	OCEOFO	GIST A	ron A. E	ssel	DRILLER 1)Carlos Puente 2)Larry Fredericks							
DATE 10/6	START 5/90	/ TIME 10:20	) <b>D</b>	ATE FINISH / TIME 10/11/90 1300	SURFACE ELEVATION		TO	TOTAL DEPIH 75'				
WELL	CASTN	G	St	REEN TYPE	LENGIH		SI	or				
			CROUNDWAY	TER .		CASTING	CORE	SAMPLER	TUBE			
DAT	DATE TIME DEPTH			WRATHER	TYPE	SS	DTCB	SS				
10/6	10/6/90 1300 13'			Surmy	DIAMETER	4"	2 1/8"					
REMA	RKS D	rilling	activitie	es was performed in Crisco was used to	HAMMER WEIGHT		N/A	140 lb				
lubr	icate a	uger jo	ints.	LIISCO WAS USED to	FALL		N/A	30′				
	CAMDI	BLOW COUNT			BORE HOLE	LOG			GRAPHIC			
DEPTH	NO.	PER 6"	RECOVERS	LITHOLOGI	C DESCRIPTION		RI	MARKS	LOG			
-		5 17		Dark brown fine-medi- traces of wood chips (dry, dense)	um sand, some sil and gravels	lt,	PID-NI SM	) .				
1 -	<b>C_1</b>		6"	(al), delec								
-												
_		21				*		•				
2 _		21		Dark brown, medium-co trace of silt	oarse sand, some	PID-NI SC	)					
_		24		(dry, dense)								
3 —	S-2	24	4"									
_		30										
, -				Come to boom time or		aile and	DID M	•	4" SS			
4		24		Gray to brown fine me gravels	•	STIL SIN	SC	•	casing			
-		27		(dry, very dense)					3" NW casing			
5 —	S-3	29	-5"						Casing			
-		34										
6 —				Dark brown fine-mediu	m cand some cil	t and	PID-0.	6 ppm				
_		20	·	gravels (dry, very dense)	an School School SII	COLAL	Odor SC	○ bhu				
-		23		(al), very delse)			<b>∞</b>					
7 —	S-4	30	. 7"									
-		45										
8 _							PID-0.	5 nom				
_		40					SC	was added				
_		20					to hel	p the	1			
9 _	S-5	30	8"	Same lithology (dry, dense)			activi	ties				
-		38		(ary) dense)								
ŀ									1			

10—

PAGE 2 OF 6

BORE HOLE NO. AMV-11

PROJECT NUMBER 9285

CLIENT Schenectady 1

LOCATION Guilderland, NY

s	AMPLE	BLOW		BORE HOLE LOG				
	NO.	PER 6"	RECOVERY	LITHOLOGIC DESCRIPTION	REMARKS	GRAPHIC LOG		
11— S-	S-6							
13-	-	20 25	18"	Gray fine-medium sand, some silt and clay, traces of fine to medium gravels (moist, dense)	PID-3.0 ppm Odor SC			
14— 5	S-6	15 20		Gray fine medium sand, some silt and clay,	PID-55 ppm Sustain reading in the borehole. Air Monitoring- 0.2 ppm			
-1	S-7	21 70/6	4"	Gray fine-medium sand, some silt and clay, traces of gravels, sandstone and shale fragments (wet, very dense)				
17—								
-  -  -  -  -								
20   S	S-8	110/0"	NR	Once and the A OI E force	Augered down 8" and installed 4" diameter stain- less steel casing Grout with Port- land cement/ bentonite mix and	3" NW casin		
22—				Start coring at 21.5 feet  Time elasped first foot core run - 3.5 min. Time elasped 2nd foot core run - 2 min. Time elasped 3rd foot core run - 2 min. Time elasped 4th foot core run - 2 1/2 min. Time elasped 5th foot core run - 2 1/2 min.	allowed to set for twenty-four hours.			

## OHM REMEDILATION SERVICES CORP. PAGE **OF** 6 PROJECT NUMBER 9285 BORE HOLE NO. AMV-11 LOCATION Guilderland, NY CLIENT Schenectady 1 REMARKS BLOW COUNT PER 6" RECOVERY BORE HOLE LOG SAMPLE NO. GRAPHIC LOG DEPTH LITHOLOGIC DESCRIPTION REMARKS stone, shale, siltstone fragments and dark brown glacial till 24-25-26-27-28-Glacial Till 29-3" NW Casing 30-31-33-

35-

PAGE 4 OF 6

BORE HOLE NO. AMV-11

PROJECT NUMBER 9285

CLIENT Schenectady 1

LOCATION Quilderland, NY

	G1) Pr =	BLOW		BORE HOLE LOG				
DEPTH	SAMPLE NO.	PER 6"	RECOVERY	LITHOLOGIC DESCRIPTION	REMARKS	GRAPHIC LOG		
- - 36—	·							
-								
37—				Start coring at 38.0 feet	OHM installed			
38—	·			Time elasped first foot core run - 5 min. Time elasped 2nd foot core run - 2 1/2 min. Time elasped 3rd foot core run - 2 min. Time elasped 4th foot core run - 2 min. Time elasped 5th foot core run - 2 1/2 min.	NW casing - 38' Core: 21.5'-26.5' 38.0'-43.0' East Coast Drilling Incorporated resumed the drilling	-		
39—				Top of core recovery consisted of 6" sand- stone, shale, siltstone fragments and dark gray glacial till	activities 10/10/90 from 38'. The process involved install- ation of NW			
40-					casing and coring at 68".	·		
-								
41—						3"NW Casing		
<u>-</u>								
42								
<u>-</u>								
43—				#				
· -								
44								
- - -			·					
45					·			
46 <u> </u>				Glacial Till				
47—								

PAGE 5 0F 6

PROJECT NUMBER 9285

BORE HOLE NO. AMV-11

CLIENT Schenectady 1

LOCATION Guilderland, NY

R	D'	Μ	R	K.

	SAMPI P	BLOW	RECOVERY	BORE BOLE LOG		CRAPHIT
EPIH	NO.	PER 6"	RECOVERY	LITHOLOGIC DESCRIPTION	REMARKS	GRAPHIC LOG
<del>-</del>						
- 48—						
<u>-</u>						
-						
9—						
-						
o	·	-				
=						ı
1—						
-					·	
2_						3" NL
- -						3" NW Casin
, -   -				Martal Mill	-	
3— -				Glacial Till		
=						
<del>-</del>						
-						
5_						
-						
5						
-						
,_						
_						
, -   -		ļ			Floating purchase	
B—  -					Floating product on the drilling water.	
-					WILLIAM .	
9_						

PAGE 6 OF 6

PROJECT NUMBER 9285

BORE HOLE NO. AMV-11

CLIENT Schenectady 1

LOCATION Guilderland, NY

	T	RIOU	T .	BORE HOLE LOG		<del></del>
DEPTH	SAMPLE NO.	COUNT PER 6"	RECOVERY	LITHOLOGIC DESCRIPTION	REMARKS	GRAPHIC LOG
60—				Glacial Till		3" NW Casing
63—						
66—				Start coring at 68'  Time elasped 1st foot core rum - 2 min. Time elasped 2nd foot core rum - 2 1/2 min. Time elasped 3rd foot core rum - 2 min. Time elasped 4th foot core rum - 2 1/2 min. Time elasped 5th foot core rum - 2 min. Core recovery consisted of dark gray shale. ROD - 97% Rock quality was excellent	Bottom of NW casing at 68' Bottom of bore-hole - 75'	
70				ROCK QUALITY WAS excellent		

					PARSONS	BORING/	Sheet 1 of 3
Contract	or:	American Au	ger	_	DRILLING RECORD	WELL NO. GW	
Driller:		Rocky Baye			•,	Location Description:	
Inspector	*	Scott Dillman		_	PROJECT NAME: Schenestady Depot AOC-1	Located in AOC1	on the west
Rig Type	2	Ingersel Rank	1	_	PROJECT NUMBER: 736741.03005	side of the pond.	
	ROUNDW	ATER OBSER	VATION	S		Location Plan	4
Water					Weather: Day to Day	· ·	¥
Level		ļ	<b>-</b>	1			
Date		ļ		<del> </del>	Date/Time Start: July 10th, 2008 at 10:00 a.m.	See Site Plan	
Time		ļ	-	<del> </del>		ĺ	
Meas.				Ī	Date/Time Finish: June 11th, 2000 at 6:00 p.m.		
From	C	SPT	%	PID	STOLD IDENTIFICATION OF BLACKSTON	000000000	COLORADO
Sample Depth	Sample LD.	SEI	Rec.	(ppm)	FIELD IDENTIFICATION OF MATERIAL	SCHEMATIC	COMMENTS
+9	2427%	<b>-</b>	- 2022	(ppsus)			
- · ·			+	╁──┈			
+6		1					
		<u> </u>	<b>†</b>				Locking Cap
+3		i	1				B" Steel
			1				
0							
		MR					*
3		MR					
		MR		0			
6		MR	<u> </u>	ļ			
		MR	ļ	<b> </b>			
9		MR	├─	<b></b>	We like at any large at the last the same and the last th		
12	****	MR MR	┼──	ļ	Drilled using a Mud Rotary technique through the overburden.  According to soil borings in the area, the overburden is sitty till.		
1.6		MR	<del> </del>		According to say oxings in the mester, the overdiment is say up.		
15		MR	<del> </del>	0			Comentilihotoolia
<del></del>		MR	-				Grout (C* > 72")
18		MR					<b>4</b>
		MR	1				
21		MR	1				
		MR					
24		MR			V		
		MR		0			
27		MR			· ·		\$ look Steel Casing
		MR					(+3* - 72*)
30		MR					
		MR			,		
33		MR	<b> </b>	0	ş*		
36		MR MR	<b> </b>	U			
- <del></del>		MR	<del>                                     </del>				
39		MR	<b> </b>				
<del></del>		MR					
42		MR			,		
		MR					
45		MR		0.1			
		MR					
48		MR					
		MR					
51		MR	<u> </u>				
		MR					
54		MR	L				
					COMMENTS:		
	AMPLING N				MR = Musl Rotary Defining	MARKET THE PARTY OF THE PARTY O	
	s = split s - Auger (				WR = Wet Rolary Drilling		
	: = CORED	AL HINGS					

L					1	PARSONS		BORING		Sheet 2 of 3
Contract	or:	American A		_ `		DRILLING RECORD		WELL N		-11R
Driller:		Rocky Baye		-				Location D		
Inspector		Scott Dilin		-		ctady Depot AOC-1			in AOC1 or	n the west
Rig Type	<del></del>	Ingersol Ra	nd	-	PROJECT NUMBER: 736741.	.03005	·	side of	the pond.	
<del></del>	ROINDW	ATER OBSE	RVATION	JC	·			Location P	len	
Water		1	T	Ĭ	Weather: Day to	Dav		IJUCALION 1		A N
Level							<del></del>	1		1
Date			1	1	Date/Time Start: July 10t	h, 2000 at 10:00 a.m.		So	e Site Plan	
Time								1		
Меаз.	[				Date/Time Finish: June 11	th, 2000 at 6:00 p.m.		1		
From			ļ			·				
Sample	Sample	SPT	%	PID	FIELD IDE	NTIFICATION OF MATERIAL		SCHE	MATIC	COMMENTS
Depth	I.D.		Rec.	(ppm)						
57		MR MR	+	-	Difficult identifying overburden due	to the drilling technique			8	
		MR	1		Diricult mentalying over better due	to the thirmy technique.			9	Coment/Bernanite
60		MR	1	<b></b>						Grout  0' - 72'}
		MR	<del> </del>	<b></b>					0	
63		MR	1						Ø	
		MR	T .					1 0		
66		MR							8	
- (0		MR	ļ	ļ	Top of bedrock at 67 feet.	_				
69		MR	ļ		Dark gray to black Shale, angular chi	īps.			<b>8</b>	8 Inch Steel Casing
70		MR	_		As a second of					(+3" - 72")
72		WR WR	1		Set casing at 72 feet in competent bec	Trock.			<u>ل</u> اقط	
75		WR								
		WR								
78		WR								
		WR								
81		WR								
		WR								
84		WR								
87		WR WR								
0/		WR								
90		WR								S inch open hole
		WR								in competent bedrock
93		WR								(72° - 142°)
		WR								
96		WR								
00		WR								
99		WR		<del></del> i						
102		WR WR	<del> </del>					İ		
102		WR						1		
105		WR								
		WR					ļ			
108		WR								
		WR								
111		WR	$\vdash$							
114	ĺ	WR			•		*			
114		WR WR	<del></del>				į			
117		WR	- 1	-			ŀ			4
	1	WR					]			
<del></del>			<del></del>		COMMENTS:					
s	AMPLING M	ETHOD			MR = Mud Rotary Drilling					
s	s = split s	POON			WR = Wet Retary Drilling					
	A = AUGER (	CUTTINGS								·
	COPED := *									

Contractor: American Auger					PARSONS	BORING/	Sheet 3 of 3	
Driller:		American Auger Rocky Baye Scott Dillman Ingereol Rand			DRILLING RECORD	WELL NO. GW-11R Located in AOC1 on the west tide of the pond.		
Inspector	-				PROJECT NAME: Scheneciady Depot AOC-1			
Rig Type					PROJECT NUMBER: 736741,03005			
		milosoci stati	******	-	13001 I TOROLOGY 13001, COO	ESEC OF the politic.		
	GROUNDW	ATER OBSE	RVATION	S		Location Plan	4	
Water			T		Weather: Day to Day		Ŋ	
Level				1		1	I	
Date					Date/Time Start: July 10th, 2000 at 10:00 a.m.	See Site Plan		
Time	<u> </u>	<u></u>						
Meas.					Date/Time Finish: June 11th, 2000 at 6:00 p.m.			
From	8	<u> </u>	<del> </del>	-				
Sample Depth	Sample LD.	SPT	% Rec.	PID (ppm)	FIELD IDENTIFICATION OF MATERIAL	SCHEMATIC	COMMENTS	
120	1,117	WR	EDS-M	(hham)		<del>                                     </del>		
		WR		<del> </del>				
123		WR	+	<del> </del>				
		WR	1	<del> </del>		}		
126		WR	1	1		1 1 1		
		WR				1 1 1	5 inch open hole	
129		WR			Competent Bedrock		in compelent bedrock	
		WR					(72 - 142)	
132		WR	<u> </u>					
105	·	WR	<b>_</b>	<b> </b>				
135		WR	<del></del>	ļ				
138		WR WR	-	<del> </del>				
136		WR	<del> </del>		·			
141		WR	╅					
		WR	<del> </del>					
144	***************************************		1			L		
Ì				*************	Boring terminated at 142 feet.			
147								
150			<u> </u>					
182			<b></b>					
153			-					
156								
150			1					
159								
t		14,						
162		****	1					
165								
						ļ		
168			1					
191				<b></b>				
171	-					•		
174			1			· I	1	
*14			1	<del>  </del>			1	
177								
						ļ	J	
180								
183								
					COMMENTS:			
	lampling M				MR = Mud Rotary Dailling			
	s - split sp				WR - Wet Rodary Dulling			
A	- AUGER C	UTTINGS						

	***************************************				PARSONS	BORING/	Shect 1 of 1			
Contractor: NorthStar Drilling, Inc.				nc.	DRILLING RECORD	WELL NO GW-12				
Driller: Scott Breeds Inspector: Scott Dillman				_	DDA WOW MINER	ption:				
	e: <u>Scor</u>			-	PROJECT NAME: AOC-1, Schenectandy Army Depot PROJECT NUMBER: 743440,00000	See site plan				
[ ]	122 122 1	- LITT	100	***	1 KORECI SIGNEDAKI 74344GROSOS	-	·			
	UNDWAT	ER OB	SERVA:	TIONS		Location Plan				
Water					Weather: Sunny, High 50's	4				
Level Date	Dry 12/07/04	<del>                                     </del>	<del> </del>	<del> </del>	Date/Time Start: November 23, 2004	See site plan				
Time	-		<b>-</b>	<del>                                     </del>	Dasi Ind. State. 14070(1100) 23, 2004	4				
Meas.					Date/Time Finish: November 23, 2004					
From	TOC	COMM	<del> </del>	<del> </del>			4			
Sample Depth	Sample I.D.	SPT	Rec.	PID (ppm)	FIELD IDENTIFICATION OF MATERIAL	SCHEMATIC	COMMENTS			
		<b> </b>	<u> </u>	(PE)			Locking Steel Cover			
							PVC Well Cap			
					· ·					
				<u> </u>	1		2-inch ID PVC Riser			
			<u> </u>	<b> </b>			(+2.5'-3')			
0			<u> </u>	<del> </del>	M. O. V					
1		3	75	1	0'-2": Soft, tan, Silt, some clay, vegetation thin, wet, lots of gravel and cobbles on ground, native material.					
-		5	<del> </del>	<del> </del>	2"-2": Dark gray, Silt, trace sand, little coarse sand to fine gravel, little to trace clay,		Congrete (0'-1.5")			
2		9	<del> </del>		stiff, (Till), damp, no odor or stain.		Bentonite Seal (1,5'-2,5')			
		8	100	8*	2'-4': Dark gray, Till, silt, little clay, little coarse sand to fine gravel, dense, damp,		accession non (am and )			
3		13			stiff, no oder er stein.					
		15								
4		18		ļ						
	GW12C	6	80	8*	4'-6': Till as above, trace coarse gravel in bottom of sample, no odor or stain.					
5		10								
6		14					U.S. Silica Filter Sand			
		16 20	30	8*	6'-8': Till as above,		(NS#0) (2.5'-8')			
7		24	20	- B-	V-6. 111 23 0009%,					
<u>_</u>		32					2-in Sch, 40 PVC			
8		30					0.01-in. slot well screen			
		A		-	Augored 8'-10'.		(3'-8')			
9		A					· · · · · · · · · · · · · · · · · · ·			
		Λ.								
10		Α								
11		10 14	100	2504	10-12': Till as above.					
		20								
12		22								
		A	-	-	Angered 12'-14'.		•			
13		Α								
		Α.			·	1				
14						1				
15		13	75	8*	14'-15.4': Dark gray, Till, silt, little clay, little coarse sand to fine gravel, damp, dense,					
13		15 50/.4			stiff, no odor or stain.					
16		207.4			Terminated soil boring at 15.5 feet bgs.					
			1		Moved rig north ~ 8 feet. Redrilled to 8 feet and set well,					
17					g	. [	and the state of t			
						uk inkushirik				
18										
					COMMENTS:					
	SAMPLING S = SPLIT S		)D		* Elevated PID measurement potentially caused by water vapor in sample container at the time of measurement by the large property of the sample of the large property of the lar					
	is – specie L= Auger		GS		Grouted harehala up to surface, moved drill rig approximately 8 feet away, and re-drilled borehole to install well as shown above.  Collected soil sample from 4-6' bgs for VOC, SVOC, Peaficides, PCBs, and TAL briefal analysis.					
	F = GEOPF			JSH	The state of the s					

					PARSONS	BORING/ Sheet 1 of 2		
	Contractor: NorthStar Drilling, Inc.			IC.	DRILLING RECORD	WELL NO GW-13		
Driller:	Driller: Scott Breeds inspector: Scott Dillman			_		Location Description:		
				-	PROJECT NAME: AOC-1, Scheneotandy Army Depot	See site plan		
Rig Typ	se: ATV	-CME-	45B	-	PROJECT NUMBER: 743440,00000			
CROT	JNDWAT	מס ממי	CT2D374	770170				
Water	INDWAL	ER UB	SER VA	LIUNS	Weather: Partly Cloudy, light winds, 40's	Location Plan		
ı	3.51				Framer: Family Cloudy, agent winds, 403	See site plan		
Date	12/07/04		1	_	Date/Time Start: November 22, 2004	See site plan		
Time	-		1	1	Term 2 Into Drink is Attornition 22, 220-7	7		
Mcas.		***************************************		1	Date/Time Finish: November 22, 2004			
From.	TOC			1		1		
Sample	1	SPT	Rec.	PID	FIELD IDENTIFICATION OF MATERIAL	SCHEMATIC	COMMENTS	
Depth	I,D.		1 %	(ppm)				
			ļ	<del> </del>			Locking Steel Cover	
				L			PVC Well Cap	
			<u> </u>	<u> </u>			·	
			<u>L</u>				2-inch ID PVC Riser	
			<u> </u>			1 11 1	(+2.5'-3 ')	
0								
		1	90	0.2	0°-2": Brown topsoil.			
1		2			2°-2': Tan, Silt, some clay, little coarse sand to fine gravel, moist, no odor or stain.		Concrete (0'-1.5')	
		3			*		***************************************	
2		2					Bentonite Seel (1.5'-2.5')	
		10	95	0.8	2'-4': Tan, Silt, very dense, little clay, little coarse sand to fine gravel, moist, (Till),		,	
3		18			no odor or stain.			
	1	22						
4		44						
		14	100	11	4'-6': Till as above grading to dark gray till, same as above, trace coarse gravel,	I ∭ <del>   </del>  ∭		
5		22			damp.			
-		20	<b></b>		warde		U.S. Silica Filter Sand	
6		22						
		34	100	400*	6'-8': Tili as above.	🕪 🗕 🗎	(NS#0) (2.5-8')	
7		32	100	744.7	V-U. Thi da abutu.			
		30			•		2-in Sch, 40 PVC	
8		37		<b></b>	·		0.01-in. sint well screen	
				<b></b>	\$ \$ en 181			
9	<del>}</del>	A	****		Augereiled 8'-10'.	1	(3'-8')	
3		A		-				
10	<del>-  </del>	A						
10		Α .		2522	501 300 4 - 3 - 4 3 - 9701 4 - 4	ļ · · · · · · · · · · · · · · · · · · ·		
17		16	80	250*	10'-12': As above, dark gray Till, no odor or stain.			
11		18		$\vdash \vdash \vdash$				
12		21		$\vdash \vdash \vdash$				
12		28		<b></b>	4		ļ	
13		<u> </u>	-		Augered 12-14'.	1	1	
12		A				1	·	
1/		<u> </u>					1	
14		A					I	
<del>,,</del> +		16	100	240*	14'-16': As above, dense Till,			
15		22						
- 1		28						
16		30						
<del></del> +		A			Augered 16'-18'.	[		
17		<u> </u>				į	İ	
		A					•	
18	<u>l</u>	A					<u>w.</u>	
					COMMENTS:		-	
	ampling		Œ		* = Elevated PID reading potentially caused by water vapor in the sample container headspace at the time	***************************************		
	S=SPLITS		ICE		Grouted bereliols up to surface, moved drill rig approximately 8 feet away, and re-drilled borehole to ins	tall well as shown abov	<u>ve</u>	
	\ = AUGER IP = OEOPR			ush		***************************************		
				- WAA		***************************************		

Contractor NorthStar Drilling, Inc.					PARSONS	BORING/ Sheet 2 of 2		
1				ic.	DRILLING RECORD	WELL NO GY		
Driller		Breeds		-	DECEMBER ACCIDENT ACCIDENT	Location Descrip	tion:	
	pe: ATV				PROJECT NAME: AGC-1, Scheneotandy Army Depot	See site plan		
Kig 1y	he: All v	-CIVIE-	- AC	_	PROJECT NUMBE 743440.00000			
GROU	JNDWA'	TER OF	SERVA	TIONS		Location Plan		
Water	T		T	1	Weather: Partly Cloudy, light winds, 40's	1/044134311 1 8211		
	3.51					See site plan		
Date	12/07/04				Date/Time Start: November 22, 2004			
Time	-					1		
Meas.					Date/Time Finish: November 22, 2004	].		
	TOC					<u> </u>		
	Sample	SPT	Rec.	PID	FIELD IDENTIFICATION OF MATERIAL	SCHEMATIC	COMMENTS	
Depth	LD.		%	(ppm)	18-20': As above. Dense Till, damp.		,	
19		A IS	100	60*	16-20; As move. Dense the manp.			
		18	1 250	- 00				
20		22	<del>                                     </del>					
		30						
21					•	]		
					Boring terminated at 20 feet bgs. Grouted to surface.			
22			<u> </u>	<u> </u>	Moved approximately 10 feet and drilled monitoring			
- 32			<u> </u>	<u> </u>	well boring to 8 feet and installed well.	]		
23			ļ					
24		• • •	<del> </del>					
24			<b></b>					
						ļ ·		
					•	ĺ		
						1		
<u></u>						·		
						.		
┯┼				——		1	·	
	<u></u>				COMMENTS:			
8	AMPLING	3 METH	op		* = Elevated PID measurement potentially caused by moisture content in the sir at the time of collect	ion.		
	s = split				Grouted borshole up to surface, moved drill rig approximately 3 feet away, and re-drilled borshole to		bove.	
	= AUGEE							
	$m = cm c_{\rm P}$	DANDE I	ATTO PROPERTY	FTOTA				

		***********		***************************************	PARSONS	BORING/	Sheel 1 of 2
Contra	ctor: Nort	hStar Di	rilling, h	BC.	DRILLING RECORD	WELL NO G	
Driller: Scott Breeds				_	Location Description:		
	or: Scott			_	PROJECT NAME: AGC-I, Schenectandy Army Depot	See site plan	
Rig Ty		-CME-		-	PROJECT NUMBER: 743440.00000		
				_			
GRO	UNDWAI	ER OB	SERVA	TIONS		Location Plan	
Water			1	ĺ	Weather: Cloudy, 40's to low 50's		
Level	Dry		<u> </u>			See site plan	
Date	12/07/04		<u> </u>	<u> </u>	Date/Time Start: November 19, 2004	_	
Time	<u> -</u>		<del> </del>	<del> </del>			
Meas. From	TOC				Date/Time Finish: November 22, 2004	-	
	Sample	SPT	Rec.	PID	EFFE D INFARMING A PROMOTE AND THE PROPERTY	COURSELTE	COMMENTS
Depth	I.D.	SPI	%	(ppm)	FIELD IDENTIFICATION OF MATERIAL	SCHEMATIC	COMMENTS
Dopti	1		<del> </del>	Chiuni		<del> </del>	Locking Steel Cover
			-	╁┈──		-	······································
			<del> </del>	├			PVC Well Cap
	ļ		<del> </del>	<del> </del>			
	ļ		<del> </del>	<del> </del>			
			<u> </u>	<u> </u>			2-incls ID PVC Riser
			<u> </u>	<u> </u>	·		(+2.5°-3°)
0			<u> </u>	ļ			
		1	75	0.3	0°-2": Brown Silt (topsoil)		
1		2	<u> </u>	<u></u>	2"-2": Tan, Silt, little to some clay, little coarse rounded sand to fine gravel,		Concrete (0'-1.5')
	<u> </u>	2			weathered till, no odor or stain.		
2		3					Bentonite Saal (1.5'-2.5')
		2	90	0.3	2'4': Same as above grading to Silt to very flue Sand, little coarse rounded sand to		***************************************
3		3		i —	fine gravel, dense, damp, stiff, (Till), no odor or stain.		
		16					
4		16	l		•		
		16	80	200*	4'-6': Till as above grading to dark gray Till, dense, similar materials, stiff,		
5		22			dry to damp, no odor or stain.	) <b>%</b>	
		24			ing to many, as the or punit.		U.S. Silica Filler Saud
6		20		<b></b>			
	GW14DE	24	90	1504	6-8: As above.		(NS#0) (2.5'-8')
7	3W14DE		70	1301	C-D. 1/2 400/46'	I ≫——∭ I	
,		38					
		45					2-in Sch. 40 PVC
8		25					0,01-in, slot well screen
		8	50	250*	8'-10": Dense dark gray Till as above.		(3'-8')
9	<b></b>	16		ļl			
		22				1	NOTE;
10		22				1	Boring was drilled to
		10	100	45	10-12; Dense dark gray Till, silt to very fine sand, little clay, little coarsc		32 feet. The boring was
11		12		]	rounded sand to fine gravel, damp, trace coarse gravel, damp, un odor.		grouted to the ground.
	ĵ.	12			ox stain.	1	surface. A new horing
12		16			•	1	was drilled to 8 feet
T		14	100	200*	12'-14': As above.		for well GW-14.
13		22					
		22				1	
14		29				1	
		12	50	134	14'-16': Dense dark gray Till as above, damp.		
15		15					
		22				]	
16		22 ·					1
		22	5	0	16'-18': Dark gray Till as above, damp to dry.		]
17	<del></del>		<del></del>	<del></del> -	No you want from the north antitude mile		
		24					
18		28				anne de la constante de la con	
10		28			COMMETTE.	<u>L</u>	
	CAREDI INI	Legers	nn.		COMMENTS:		:
	Sampling SS = Split		/1J		<ul> <li>Elevated PID measurement potentially caused by water vapor in the sample container headspace.</li> <li>Grouted borelude up to surface, moved drill rig approximately 8 feet away, and re-drilled borelude to in</li> </ul>	المستعدد والمستالة	
	A≖AUGER		īGS		Collected soil sample from 6-10 bgs for VOC, SVOC, Pesticides, PCBs, and TAL Metal analysis.	STATE ALCH US SHOWN BOOM	
GP = GEOPROBE - DIRECT PUSH							

					PARSONS	BORING/	BORING/ Sheet 2 of 2		
Contractor: NorthStar Drilling, Inc.			illing, H	ic.	DRILLING RECORD	WELL NO. GW-14			
Drillera	Scot	Breeds		_		Location Description:			
Inspect	Inspector: 6cott Dillman			_	PROJECT NAME: AOC-1, Scheneckindy Army Depet	Sec site plan			
Rig Typ	e: ATV	-CME-	ISB	_	PROJECT NUMBER: 743440,00000				
	UNDWAT	TER OB	SERVA	TIONS	j ·	Location Plan			
Water		1		l	Weather: Cloudy, 40's to low 50's	_			
Level	Dry	<del> </del>	<del> </del>			See site plan			
Date	12/07/04	<b></b>	<del> </del>	<b>-</b>	Date/Time Start: November 19, 2004	-			
Time	-	<u> </u>	<del> </del>	<del> </del>	D ( W) 27 1 20 000				
Meas. From	тос	ĺ	1	1	Date/Time Finish: November 22, 2004	-			
Sample		SPT	Rec.	PID	FIELD IDENTIFICATION OF MATERIAL	SCHEMATIC	COMMENTS		
Depth	LD.		%	(ppm)	3	bellman	COMMINITO		
		10	100	0	18'-20': Dense dark gray Till, stiff, silt, little clay, little to some coerse send to	†			
19		10			fine gravel, damp, no odor, no stain.				
		14	<del>                                     </del>	<del> </del>	And the state of t				
20	<del> </del>	16	<del>                                     </del>	<del>                                     </del>		1			
-20		8	<del> </del>	<del> </del>	ON 201. At				
21	<u> </u>		╁╌	<del>  -</del>	20'-22'; As above.		270000		
21	<b> </b>	12	<b>├</b> ──	ļ			NOTE:		
		15	<u> </u>	ļ			Boring was drilled to		
22		20	<b> </b>	ļ			32 feet. The boting was		
		22	100	D	22-24': As above.		grouted to the ground.		
23		27					marface. A new boring		
		38	ļ			1	was drilled to 8 feet		
24		25				ļ	for well GW-14.		
		12	100	0	24'-26': As above.				
25		14							
		22	`				·		
26		20					'		
		30	100	0	26-28': As above.				
27		28							
		40	<u> </u>		, ,				
28		40							
		16	160	0	26-30': As above.				
29		18				1			
		30							
30		40							
		20	100	0	30'-32': As above.				
31		20	100	Ť	JV-JZ 1 1.10 MIX 936				
- 51		35							
32				-		1.			
32		50			P				
					Terminated soil boring at 32 feet bgs.	1			
				<b></b>					
						, ,			
				<b></b>		1			
	[					]			
]									
		,,			COMMENTS:				
	Sampling	METHO	Ð						
	SS = SPLIT								
	A = AUGER								
+	OP = GEOPROBE - DIRECT PUSH								

					PARSONS	BORING/ Sheet 1 of 2		
Contrac		North Star I		-	DRILLING RECORD	WELL NO. GW-01		
Driller:	***************************************	Scott Breed		-	TROUBLE OF THE PARTY OF THE PAR	Location Description:  Located at the northern end of AO		
Inspect		Scott Dillm		-	PROJECT NAME: Schencotady Depot AOC-7	<del></del>		
Rig Typ	ie:	CME-45B A	II V		PROJECT NUMBER: 743440.03000	between the dirt roa	d and the	
<del>                                     </del>	GROUNDWA	TED OBCCO	VATTON	167		woods near AOC-7. Location Plan	<u> </u>	
Water	TAN CINCOLL	TEK OBSEK	AVITOR	1	Weather: Cloudy clearing later in day, temperature 60's to 80, breezy	<del></del>	<b>↑</b>	
Level	ĺ		1	l	Weather, Canady seeming man in they, temperature out sto au, treezy		, r	
Date		<b>†</b>	†	<del> </del>	Date/Time Start: 14 June 2004, 1200	See Site Plan		
Time		<u> </u>	1	1		2-0,		
Meas.				1	Date/Time Finish: 14 June 2004, 1700			
From								
Sample		SPT	%	PID	FIELD IDENTIFICATION OF MATERIAL	SCHEMATIC	COMMENTS	
Depth	1.D.		Rec.	(ppm)				
+3			╄——	ļ			Locking steets	
+2		ļ	<del>- </del> -	ļ	•	│ ┃┌ <del>┉</del> ╟╌┼		
12		ļ	<del> </del>	<del> </del>			PVC well cap	
+1			<del> </del>		,			
	******		<b> </b>					
0			1					
	SD-65GW01-6-0.5	4	100	0	Gray-brown Silt, some fine to medium gravel, dense, no odor, no stain.			
1		6					Concrete Apron	
		5					{3 - 43	
2		6					2-inch ID PVC Right	
		3	75	0.1	Greenish with reddish varigations grading to yellowish-orange-light brown Silt,		(+2.6° + S)	
3		3	<del> </del>		some elay, sandy lense, trace coarse sand, semi-stiff, moist. Till.			
4		<u>3</u> 5	╀	<u> </u>				
		3	75	1.3	An about many manuals market and sense stiller terror countries them and atter			
3		7	13	1.5	As above, upper sample moist and semi-stiff, lower sample damp and stiff.  No odor, no stain.			
		10	<del> </del>		140 SAM; BU SIZIU.		Bentonite Office	
6		15	1				(# - 7.5)	
		16	100	2.3	Yellowish-orange-light brown Silt to very fine Sand, some clay, stiff, damp.		,,	
7		18	1		No odor, no stain.			
		18						
8		20						
		25	100	1.6	Yellowish-orange-light brown Silt-Sand, trace gravel, shale cobbles, dense,		US Silica #0	
9		35 500 3			stiff, damp, Till		Sand Pack	
10		50/0.3 A					(7,5 - 17)	
10	.,	46	90	2.1	Silt-Sand, little clay, gravel and cobbles, soft. Water dripping from split spnon, wet.		≱ineb IO	
11		50/0.3	- 70		Tough drilling. Free water in august at 9.3' below GL.		PVC well actions	
		A		——	,		5.01 inch aloc	
12		A			•		(St-14)	
	SD-830W91-12-14	13	90	1.6	Dark gray Silt, little to some gravel, trace clay, dense, stiff. Moist in upper sample			
13		20			and damp in lower sample. Till.			
		28		]				
14		34	0.0				PVC earld coop.	
		15 18	90	2.7	Dark gray Till as above.			
15		25					1	
16		28			·		1	
		26	40	3.0	Dark gray till as above		·	
17		34			~			
		49					Native Material	
18		45						
					COMMENTS:			
	Sampling Me	тнор			PID readings effected by moisture.			
	SS = SPLJT SPO							
	A = AUGER CUT	TIINGS						
	C=CORED					·		

			PARSONS	BORING/ Sheet 2 of 2					
Contractor: North Star Drilling		_	DRILLING RECORD	WELL NO. GW-01					
Driller: Scott Breeds		-		Location Description:					
Inspecto		Scott Dillim		_	PROJECT NAME: Schenectady Depot AOC-7				
Rig Type	e;	CME-45B	VTV	-	PROJECT NUMBER: 743440.03000	between the dirt ro			
						woods near AOC-7			
	ROUNDWA	TER OBSER	VATION	\$ T		Location Plan	<u>‡</u>		
Water		1		ł	Weather: Cloudy cleaning later in day, temperature 60's to 80, breezy		N I		
Level		1	-	-	D . TH. 11		•		
Date		<del> </del>	<del> </del>	-	Date/Time Starts 14 June 2004, 1200	See Site Plan	)		
Time		<u> </u>	<del> </del>	ļ	Date/Time Finish: 14 June 2004, 1700				
Meas. From			l		Date/Time Finish: 14 June 2004, 1700				
Sample	Sample	SPT	%	PID	FIELD IDENTIFICATION OF MATERIAL	SCHEMATIC	COMMENTS		
Depth	i.D.	134.1	Rec.	(ppm)	FIELD IDENTIFICATION OF MAIDRIAD	WALLEST AND THE STATE OF THE ST	COMMINICAL		
22 447 442		15	60	3.0	Dark gray Till as abovo.		Native Material		
19		17	+	1					
<u> </u>		28	1						
20		35	<del> </del>						
			T	1		Emm!			
21					Boring tenninated at 20 feet.				
22			<u> </u>				,		
			<u> </u>						
23			<u> </u>						
			<del>                                     </del>						
24		<del> </del>	<del></del>						
25			<del> </del>	ļI					
43		}	<del></del>						
26		<del> </del>	<del> </del>	<u> </u>					
-20	***************************************	<del> </del>			·				
27			<del> </del>						
		_	<del>                                     </del>						
28		<u> </u>	<b>1</b>						
29									
30			ļ						
		<u> </u>	<u> </u>						
31			<del> </del>		•				
32			<b> </b>						
32			ļ						
33			<del> </del>						
				-					
34									
35			I						
36									
			<u> </u>						
37						l			
	· · · · · · · · · · · · · · · · · · ·								
38									
39			ļl						
33				<b></b>					
		<u> </u>	1		COMMENTS:				
	SAMPLING M	ernos			PID readings effected by moisture.				
	SS = SPLIT SPC								
	A = AUGER CL								
	C=CORED								

	· · · · · · · · · · · · · · · · · · ·				PARSONS	BORING/	Sheet 1 of 2
Contra		North Star		_	DRILLING RECORD	WELL NO. GW	-03
Driller		Scott Breed		-		Location Description	d:
Inspect		Scott Dillm			PROJECT NAME: Schenectady Depot AOC-2	Near orest of hill.	North of big lone tree
Rig Ty	ре:	CME-45B	ATV	-	PROJECT NUMBER: 743440,03000	and east of bottle d	isposal area.
	GROUNDWA	TER OBSER	RVATION	vs		Location Plan	4
Water		1	<u> </u>		Weather: Light rain, 70 degrees, calm.		j.
Level		<u> </u>					•
Date	ļ				Date/Time Start: June 17, 2004 0800	See Site Plan	
Time	<u> </u>			ļ			
Meas. From	тос				Date/Time Finish: June 17, 2004 1530		
Sample	<del></del>	SPT	%	PID	FIELD IDENTIFICATION OF MATERIAL	SCHEMATIC	COMMENTS
Depth	LD.		Res.	(ppm)	THE DAMES AND THE PROPERTY OF THE PERSON OF	COMEDIATIO	COMPARINE
+3							
			<del> </del>	-			
+2		ļ		<u> </u>			
+1		<del> </del>		<del>                                     </del>			
· · ·	<b> </b>			+			farbles t ->
0			<del>                                     </del>	1			no guis, L grissou Esse sensi
		3	60	0.7	Brown Sift (0-8°)		Flash Mount Visit
1		4			Tan-brown silt, trace coarse sand-very fine gravel, trace clay, moist, dense,		Cover end Contrale
		6			semi-stiff. Wenthered till.		Apen
2		4			No odor, no stain.		
		5	95	0.8	Tan silty till as above, damp, no odor, no stain, stiff.		3-inch ID PVC Nisar
3		7		$\vdash$			(-0.57 - 207;
4		8 12	<del> </del>	<del> </del>			
		6	75	1.0	Tan-light brown silt, some gravel, trace clay, dense, stiff, damp. Till		
5		9	,,-	1-1-4	No odor, no stain.		
		10	1				Cemen# <i>Sent</i> on/le
6		14					Grant (-1" - 14.5")
		20	95	0.9	As above		
7		22					
		26	<del> </del>				
8		30 8	100	0,6	As above		
9		15	100	0.0	AS acove		
		15	<del> </del>	<del>  </del>			•
10		24	1				
		22	95	1.1	As above		
11		17					
10		18	1				
12		24 24	100	<del></del>	Australia		
13		28	100	1.1	As above Hard drilling with augers.		
		30	<del> </del>	<del>  </del>	emo anng was augus.		
14		30	<del> </del>	<b></b>			
		10	100	0.9	As above. Dense, stiff.		
15		15					
		17					
16		25 23	100	13	A value of an illustration of the United Kanasan Ships and the state of the state o		
17		33 33	100	1.2	As above grading to tan-light brown silt, trace coarse sand,		Bantonila Chips
1,		32	$\vdash \vdash \vdash$		damp-moist, stiff. Till		(14.5" - 17.5}
18		29					
	······		ليحسيك	l	COMMENTS:		
	Sampling me	THOD			•		
	SS = SPLIT SPO						
	A = AUGER CU	TINGS					
	C=CORED						

					PARSONS	BORING/	Sheet 2 of 2
Contrac	tor <u>:</u>	North Star I	Orilling	_	DRILLING RECORD	WELL NO. GW	
Driller:		Scott Breeds		_		Location Description	
Inspecto		Scott Dillma			PROJECT NAME: Schenectady Depot AOC-2		North of big lone tree
Rig Type	e:	CME-45B A	TV	_	PROJECT NUMBER: 743440.03000	and east of bottle di	isposal area.
_			<u> </u>				
	ROUNDWA	TER OBSER	VATION	<u> </u>		Location Plan	4
Water					Weather: Light rain, 70 degrees, calm.	-	N I
Level Date		-	+	<b></b>	Date/TErra Shart June 12 2004 0000	See Site Plan	•
Time			<del></del>	<del> </del> -	Date/Time Start: June 17, 2004 0800	3ee Site Fian	<u>.</u>
Meas.			1	<del>                                     </del>	Date/Time Finish: June 17, 2004 1530		
From			i		2450 I HILL I HILL II, 2001 1330	1	
Sample	Sample	SPT	%	PID	FIELD IDENTIFICATION OF MATERIAL	SCHEMATIC	COMMENTS
Depth	I.D.		Rec.	(ppm)			
		- 10	100	0,6	Tan-light brown Silt, trace coarse sand, damp-moist, stiff grading		,
19		50/0.3			to tan-brown Silt, some gravel, dense, stiff, damp. Till		
20						1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	No. G Sand
20		20	100	0.8	T 1 Cil 11 1 -1 -1 1 1		(17.5' - 26.2')
21	· · · · · · · · · · · · · · · · · · ·	55	100	0.8	Tan-brown Silt, some sand and gravel, shale cobbles, wet lenses.  Black-dark gray weathered Shale in end of sampler from cobble.		
		50/0.3	1		~1.5 feet of free water in angers.		
22		- 50,0.5	+		1.5 Tool of troe Military III Imports.		2-inch ID PVC
		12	89	1,4	Gray-dark gray Silt, some gravel and cobbles, moist, dense. Till		O.OS Slot Well
23		35	1		Wet lenses.	1 1. 🗀 - 1	Screen (20 - 25)
		50/0.1	1		•		
24							
		100/0.2	100	2.0	Dark gray Shale, wet, thin horizontal bedding. Bedroek.		
25						1,	PVC End Cap (25)
26			<u> </u>			] [ ] [ ] [ ]	
26		100/0.2	100	0.5	As above.		
27	,	100/0.2	100	<u> </u>	Boring terminated at 26.2 feet.	<del>                                   </del>	
	-		†				
28	···					•	
29			<u> </u>			ŀ	
20			<u> </u>				
30			<del> </del>				
31							
7.						]	
32						1	
33					•	]	
						i	
34			-	——		.	
35							
-33							
36				-		i	
			<u> </u>				
37							
						]	
38			ļ	╙┈┤			
30			ļ	<b> </b>			
39			<u> </u>				
					COMMENTS:	<u> </u>	
s	AMPLING M	ETHOD					
	S = SPLIT SPC						
,	A = AUGER CU	TTINGS					
,	- conen						

Н	2H Associate	es	Ne <sup>r</sup> Tel:	River Stree w York, 12 : 518.270-1 : 518.270-	180 1620	Borin	g Log	Boring No. MW-13-01		
PROJEC	CT: NEIP/AO	C 1 Landfill C	ар			Sheet 1 of 1				
CLIENT	: USACE							Job No. 650.40		
DRILLIN	IG CONTRAC	CTOR: Zebra	Environmenta	al				Meas. Pt. Elev: N/A		
PURPO	SE: Environm	nental Investig	ation					Ground Elev: N/A		
DRILLIN	IG METHOD:	Direct Push			SAMPLE	CORE	CASING	Datum: N/A		
DRILL R	RIG TYPE: Ge	eoprobe 7822[	OT	Туре	Macro Core			Date Started: 8/19/2013		
GROUN	DWATER DE	PTH: N/A		Diam.	1.5 inch			Date Finished: 8/19/2013		
MEASU	RING POINT	: N/A		Weight	N/A	Discret closed p		Driller: Zack Fordly		
DATE O	F MEASURE	MENT: N/A		Fall	N/A	core with a 5 foo	ot barrei length.	Inspector: Matt Montario		
Depth (feet)	Run	Recovery (%)	PID (PPM)	USC		G	eologic Descripti	on		
							. Silty Sand. Dk.			
	1	67% 3.3'/5.0'	0.0		Very Fine			e gravel. Lt Brown. Damp.		
_ 5							No Recovery.			
-	2	85% 4.3'/5.0'	0.0				Lt. Brown. Damp	ce coarse gravel.		
10					Fine to			e gravel. Brown. Moist.		
					Gravelly Till.	Very fine to me	avely Sand. Bla dium grianed sa Brown.	nd with some gravel. Grayish		
_ _ 15	3	42% 2.1'/5.0'	0.0		No Recovery.					
-					End of Boring. Sampled to 15'. Auger refusal @ ~10.5'					
20										

H2	2H Associate	es	Ne <sup>.</sup> Tel	River Stree w York, 12 : 518.270-1 : 518.270-	180 1620	Borin	g Log	Boring No. MW-13-02			
PROJEC	CT: NEIP/AO	C 1 Landfill C	 ар					Sheet 1 of 1			
CLIENT:	: USACE			Job No. 650.40							
DRILLIN	IG CONTRAC	CTOR: Zebra I	Environmenta	al				Meas. Pt. Elev: N/A			
PURPOS	SE: Environm	nental Investig	ation			Ground Elev: N/A					
DRILLIN	IG METHOD:	Direct Push			SAMPLE	CORE	CASING	Datum: N/A			
DRILL R	RIG TYPE: Ge	eoprobe 7822[	)T	Type	Macro Core			Date Started: 8/19/2013			
GROUN	DWATER DE	EPTH: N/A		Diam.	1.5 inch			Date Finished: 8/20/2013			
MEASU	RING POINT	: N/A		Weight	N/A	Discret closed p		Driller: Zack Fordly			
DATE O	F MEASURE	MENT: N/A		Fall	N/A	core with a 5 foo	ot barrel length.	Inspector: Matt Montario			
Depth (feet)	Run	Recovery (%)	PID (PPM)	USC		Ge	eologic Descripti	on			
(1003)		(1.2)	,			Topsoil	. Silty Sand, Dk.	Brown.			
- - - - 5	1	75% 3.8'/5.0'	0.0			Silt with very fine sand, trace clay and gravel. Mott  Silty Sand with Trace gravel and cobble  No Recovery.					
- - - - 10	2	93% 4.7'/5.0'	0.0			Silty Sand with 1	race gravel and  No Recovery.	cobbles. Brown			
"						Silty Sand with 1		cobbles Brown			
	3	73% 3.7'/5.0'	0.0		Silty Sand with Trace gravel and cobbles. Brown  Very Fine sand and silt with some weathered shale throughout, ver  Dk. Gray to Black.						
15				<u> </u>		gor refusal @ 11'					
_ _ _ _ _ 20					End of Boring. Sampled to 15'. Auger refusal @ ~11'						

H	2H Associate	es	Ne <sup>s</sup> Tel:	River Stree w York, 12 : 518.270-1	180 1620	Borin	g Log	Boring No. MW-13-03
		C 1 Landfill C		: 518.270-	1672			
	: USACE	C I Landilli C	ар 				Sheet 1 of 1	
			Job No. 650.40					
		CTOR: Zebra I		<b>1</b> 1				Meas. Pt. Elev: N/A
		nental Investig	ation		0.1.451.5	0005	0.4.011.10	Ground Elev: N/A
	IG METHOD:			Ι	SAMPLE	CORE	CASING	Datum: N/A
		eoprobe 7822[	)	Туре	Macro Core			Date Started: 8/19/2013
	IDWATER DE	•		Diam.	1.5 inch	Discret aloos du	intan manu	Date Finished: 8/19/2013
	RING POINT			Weight	N/A	Discret closed p core with a 5 foo		Driller: Zack Fordly
DATE O	F MEASURE	MENT: N/A		Fall	N/A			Inspector: Matt Montario
Depth (feet)	Run	Recovery (%)	PID (PPM)	USC			eologic Descripti	
	1	73% 3.7'/5.0'	0.0					vel and silt. Lt. Brown up to 1.5 inches in size. Dk.
_ _ _ _ 10	2	90% 4.5'/5.0'	0.0		Tilll, silt with	n very fine sand a	and trace gravel Gray No Recovery.	up to 1.5 inches in size. Dk.
_ _ _ _ _ 15	3	90% 4.5'/5.0'	0.0		Tilll, silt with	up to 1.5 inches in size. Dk.		
_ _ _ _ 20					En	er Refusal @ ~13.6'		



# **WELL CONSTRUCTION LOG**

Facility/Project Name: NEI	P/ACO 1 Landfill Cap			Well Name: MW-13-01
Facility License Number:	Well GPS Location:	Lat.:	Long.:	Type of Well: Ground Water Monitoring ✓ Piezometer  RPOC  ROC
Date Well Installed: 8/19/13	3			aste source: South
Distance from waste source Well Installed By: (name a First Name: Zach Company Name: Zebra Environmental	-	Upgradient [	☐ Downgradie	ent Side-gradient Unknown Side-gradient
	on: ft. MSL	ı	<b>—</b>	1. Cap and lock? Yes V No
<ul><li>A. Protective pipe, top elevation</li><li>B. Well casing, top elevation:</li></ul>	ft. MSL	7		2. Protective cover pipe:
C. Land Surface Elevation:	ft. MSL			a. Inside diameter: 4 in.
D. Surface seal, bottom:	ft. MSL	200		b. Length: 5 ft.
12. USCS classification of soi				c. Material: Steel
GP ☐ GM ☐ GC ☐ G		[-		Other: N/A
SC SW ML M		튌		3. Surface seal: Bentonite Concrete
Bedrock _		18		Other: N/A  4. Material btw. well casing and protective pipe:
13. Sieve analysis attached?	Yes □ No 🗸			Bentonite Annular space seal
14. Drilling method used: Rota	ary 🗸 HSA 🔲	6		Other: PDS/1 bag
Other: Auger		į.		5. Annular space seal:
15. Drilling fluid used: N/A		£		a. Granular benonite
Water Air Drillin	g Mud None None			b. N/A lbs/gal mud weightbentonite/sand slurry
16. Drilling additives used? Y	′es  No ✓			c. N/A lbs/gal mud weightbentonite slurry
Specify: N/A			8 83	d. N/A % bentonitebentonite/cement grout
17: Source of water: N/A				e. N/A ft <sup>3</sup> volume added for any of the above
E. Bentonite seal: top 0.5	ft. BGS	E	8 🖼	f. How installed: Tremie Tremie pumped
F. Fine sand: top 2.5	ft. BGS			Gravity 🗸
G. Filter pack: top 2.5	ft.BGS	\		6. Bentonite seal: Bentonite granules
H. Screen joint: top 3.62	ft. BGS			☐ ½ in. ☐ 3/8 in. ☐ ½ in. Bentonite pellets ☑ Other: N/A
I. Well bottom: top 8.62	ft. BGS			7. Fine sand material: (Manufacturer, product name, mesh size)
J. Filter pack: bottom 10.3	ft. BGS			N/A
K. Borehole: bottom 10.3	ft. BGS			Volume added: N/A ft <sup>3</sup>
L. Borehole diameter: 8	in.			8. Filter pack material: (Manufacturer, product name, mesh size) Fill Pro/US Silica Company #0
M. O.D. well casing: 2.25	in.	. ///		Volume added: 4.5 50 lbs bags ft <sup>3</sup>
N. I.D. well casing: 2	in.	/ /		9. Well casing: Flush-threaded Sch 40 PVC
				Flush-threaded Sch 80 PVC
CERTIFICATION: I hereby certify that the inform	action on this form is true			Other: N/A
and correct to the best of my k		1		10. Screen material:
				a. Screen type: factory cut 🔽 continuous slot 🗌
(Signature)		-		Other: N/A
H2H Associates, LLC			\	b. Manufacturer: Unknown
(Company Name)		-	`	c. Slot size: 0. 10 in.
				d. Slotted length: 5 ft.
				11. Backfill material: N/A or None 🔽



# **WELL CONSTRUCTION LOG**

Facility/Project Name: NEI	P/ACO 1 Landfill Cap			Well Name: MW-13-02
Facility License Number:	Well GPS Location:	Lat.:	Long.:	<b>Type of Well:</b> Ground Water Monitoring   Piezometer   RPOC   RPOC □
<b>Date Well Installed:</b> 8/20/13	3		_	aste source: West
Distance from waste source Well Installed By: (name a First Name: Zach Company Name: Zebra Environmental		Upgradient _	Downgradie	nt Side-gradient Unknown
A. Protective pipe, top elevation	on: ft. MSL	Ī		1. Cap and lock? Yes V No
B. Well casing, top elevation:	ft. MSL			2. Protective cover pipe:     a. Inside diameter: 4 in.
C. Land Surface Elevation:	ft. MSL		-	b. Length: 5 ft.
D. Surface seal, bottom:	ft. MSL	100		c. Material: Steel
12. USCS classification of soil	l near screen:	34.50	No.	Other: N/A
GP GM GC G	W 🔲 SP 🔲 SM 🔲	Ì		3. Surface seal: Bentonite Concrete
SC SW ML M	H□ CL□ CH□	<b>*</b>		Other: N/A
Bedrock				4. Material btw. well casing and protective pipe:
13. Sieve analysis attached? Y	— — I	₩		Bentonite 🗹 Annular space seal 🗌
14. Drilling method used: Rota	ary 🗸 HSA 🔲	<b>S</b>		Other: PDS/0.5 bag
Other: Auger		i i		5. Annular space seal:
15. Drilling fluid used: N/A		8		a. Granular benonite 🗸
Water Air Drillin				b. N/A lbs/gal mud weightbentonite/sand slurry
16. Drilling additives used? Y	es No 🗸	2000 1000 1000	<b>XX</b>	c. N/A lbs/gal mud weightbentonite slurry
Specify: N/A				d. N/A % bentonitebentonite/cement grout
17: Source of water: N/A	o DCC	8		e. $N/A$ $ft^3$ volume added for any of the above
E. Bentonite seal: top 0.0	ft. BGS		***	f. How installed: Tremie Tremie pumped
F. Fine sand: top 1.0	ft. BGS			Gravity 🔽
G. Filter pack: top 1.0	ft.BGS	\		6. Bentonite seal: Bentonite granules
H. Screen joint: top 5.72	ft. BGS			☐ ¼ in. ☐ 3/8 in. ☐ ½ in. Bentonite pellets ✔ Other: N/A
I. Well bottom: top 10.72	ft. BGS			7. Fine sand material: (Manufacturer, product name, mesh size)
J. Filter pack: bottom 11.0	ft. BGS			N/A
K. Borehole: bottom 11.0	ft. BGS			Volume added: N/A ft <sup>3</sup>
L. Borehole diameter: 6.0	in.			8. Filter pack material: (Manufacturer, product name, mesh
M. O.D. well casing: 2.25	in.			size) Fill Pro/US Silica Company #0  Volume added: 4.5 50 lbs bags ft <sup>3</sup>
N. I.D. well casing: 2.0	in.			9. Well casing: Flush-threaded Sch 40 PVC
				Flush-threaded Sch 80 PVC
CERTIFICATION: I hereby certify that the inform	ation on this form is true			Other: N/A
and correct to the best of my k				10. Screen material:
				a. Screen type: factory cut 🗸 continuous slot 🗌
(Signature)		-		Other: N/A
H2H Associates, LLC			/	b. Manufacturer: Unknown
(Company Name)		-	\	c. Slot size: 0. 10 in.
(25mpony Lone)				d. Slotted length: 5 ft.
				11. Backfill material: N/A or None 🗸



# **WELL CONSTRUCTION LOG**

Facility/Project Name: NEI	P/ACO 1 Landfill Cap			Well Name: MW-13-03
Facility License Number:	Well GPS Location:	Lat.:	Long.:	<b>Type of Well:</b> Ground Water Monitoring ✓ Piezometer ☐ RPOC ☐
<b>Date Well Installed:</b> 8/19/13	3		_	aste source: North East
Distance from waste source Well Installed By: (name a First Name: Zach Company Name: Zebra Environmental		Upgradient [	Downgradie	nt Side-gradient Unknown
A. Protective pipe, top elevation	on: ft. MSL	Ī		1. Cap and lock? Yes V No
B. Well casing, top elevation:	ft. MSL			2. Protective cover pipe:
C. Land Surface Elevation:	ft. MSL			<ul><li>a. Inside diameter: 4 in.</li><li>b. Length: 5 ft.</li></ul>
D. Surface seal, bottom:	ft. MSL			c. Material: Steel
12. USCS classification of soil	l near screen:			Other: N/A
GP GM GC G	W 🔲 SP 🔲 SM 🔲	F		3. Surface seal: Bentonite Concrete
SC SW ML M	H□ CL□ CH□			Other: N/A
Bedrock		<b>E</b>		4. Material btw. well casing and protective pipe:
13. Sieve analysis attached? Y	Yes □ No 🗸	Ø		Bentonite 🗸 Annular space seal 🗌
14. Drilling method used: Rota	ary 🗸 HSA 🔲	<b>[</b> 8		Other: PDS/0.5 bag
Other: Auger		<u> </u>		5. Annular space seal:
15. Drilling fluid used: N/A		i i		a. Granular benonite
Water Air Drillin				b. N/A lbs/gal mud weightbentonite/sand slurry
16. Drilling additives used? Y	es No 🗸	\$53 800 800		c. N/A lbs/gal mud weightbentonite slurry
Specify: N/A		<b>8</b>		d. N/A % bentonitebentonite/cement grout
17: Source of water: N/A				e. N/A ft <sup>3</sup> volume added for any of the above
E. Bentonite seal: top 0	ft. BGS			f. How installed: Tremie Tremie pumped
F. Fine sand: top 2.0	ft. BGS	835		Gravity 🗸
G. Filter pack: top 2.0	ft.BGS	\		6. Bentonite seal: Bentonite granules
-				☐ ¼ in. ☐ 3/8 in. ☐ ½ in. Bentonite pellets ✔
H. Screen joint: top 3.16/8.1		<u> </u>		Other: N/A
I. Well bottom: top 13.16	ft. BGS			7. Fine sand material: (Manufacturer, product name, mesh size)
J. Filter pack: bottom 13.16	ft. BGS			N/A
K. Borehole: bottom 13.6	ft. BGS			Volume added: N/A ft <sup>3</sup>
L. Borehole diameter: 8	in.			<ul> <li>8. Filter pack material: (Manufacturer, product name, mesh size) Fill Pro/US Silica Company #0</li> </ul>
M. O.D. well casing: 2.25	in.			Volume added: 6.0 50 lbs bags ft <sup>3</sup>
N. I.D. well casing: 2	in.			9. Well casing: Flush-threaded Sch 40 PVC
				Flush-threaded Sch 80 PVC
CERTIFICATION: I hereby certify that the inform	nation on this form is true			Other: N/A
and correct to the best of my k				10. Screen material:
				a. Screen type: factory cut 🔽 continuous slot 🗌
(Signature)		-	\	Other: N/A
H2H Associates, LLC			\	b. Manufacturer: Unknown
(Company Name)		-	'	c. Slot size: 0. 10 in.
				d. Slotted length: 10 ft.
		1		11. Backfill material: N/A or None 🗸

# Monitoring Well Development Log

	Project/No.		50 7	70		10/-11	M1 1 17 A	D-1-	Page	of
	Piojecvivo.		50,7	Casing		_vveii /	MW-13-01	_	<u>O9/2</u> Method	1/13-> 10/1/13
	Total Depth	11.8		_Diameter	(inches)	2		i uige	Centrifug	al
	Water Level	6.5		_Well Volu	ıme (gal)	0.8			Submers	ible
	Water Colum	<u>n 5.</u>	22	_Total Vol	ume Purged		gal		Other	
	Pump On			<b></b>	Pump Off		P	Develo	ped By	
	gallon/foot		Well Casi 1-¼" = 0.0 1-½" = 0.0		2" = 0.1 2-½" =		3" = 0 3-½"=		4" = 0.65 6" = 1.47	
	Time	Minutes Elapsed	Rate (gpm) (mL/min)	DTW (ft)	Gallons Purged	рН	Specific Conductance (mS/cm)	Temp. (C) (F)	Turbidity (NTU)	REMARKS (PID readings, color, odor, etc.)
9/27/13 -	1130	0	+ <sub>Septiment</sub> coming	6.58	0.0	- Anna Carlotte	- 144000-14400-14400-14400-14400-14400-14400-14400-14400-14400-14400-14400-14400-14400-14400-14400-14400-14400		1580 White Horizona	Start
	1215	45	National Control of the Control of t	*	5.0	- Address of the Addr	weekleening saaraan oo oo oo oo oo oo oo oo oo oo oo oo oo	vi gazante littoria.	E3	· ·
	1245	75	**************************************	11.50	0.5		Talan sayasesisisis	**************************************	E2	recharge = . 05/mi
9/30/13 -	1345	0	~earthroids-size	8.50	0.0		4466460000000	en angenet en sen en  E3	Start	
	1430	45	*American Cont	10.82	2.0	.gumpigaticiinibiliibiliibilii	Helpsterates and production (ISSN 100%)	зунатрайстванной	E2	
	1500	75		11.60	0.5	- Martin State Control of the Contro			700	
	1615	- pagasanti donino	/partitionings	10.57		galleconstantialisticalistic	er geschiebterten sein	gett galaktiken alb	*/папринципана	Surged
10/1/13 -	0925	· constanting to		6.79		-ggspelittiggsschrotz	-0499-499-499-499-499-499-499-499-499-49		**************************************	Surged
	0945	0	- Monte de la constante de la	6.79	0,0	saddinedalasida.com	· Cristalina del Constantino d	+oggregolisida		Start
	1020	35	1-9-5500 ang ang ang ang ang ang ang ang ang ang	11. 35	3.5				230	
	1130	0	Quegoral (SSSS) de la companya (SSSS) de la	9.82	0.0				1100	Start
	1200	30	- Augustic Control of the Control of	11.38	1.5		cognition and administration administration and administration and administration administration administration and administration admini		170	
a property and the second seco										
L				1			L			

# Monitoring Well Development Log

									Page	of
	Project/No.	6	50.70	2		_Well /	MW-13-02	Date	09/27	113->10/1/13
	Total Depth	/3.	0	Casing Diameter	r (inches)	2	?	Purge	Method Centrifug	al
	Water Level	5.4	P	_ _Well Volu	ıme (gal)	***************************************	?2		Submers	timintalities validate dale schere derevaldate careful p
	Water Colum	n 7.5	72	_ _Total Vol	ume Purged		25 gal.		Other	emboreomerone-negativor-leaf/difficulty
	Pump On	Carlos and the control of the contro			Pump Off			Develo	pped By	DLW
	gallon/foot		Well Casi 1-¼" = 0.0 1-½" = 0.0		s 2" = 0.1 2-½" =		3" = 0 3-½" =		4" = 0.65 6" = 1.47	
	Time	Minutes	Rate	DTW	Gallons	pН	Specific	Temp.	Turbidity	REMARKS
		Elapsed	(gpm) (mL/min)	(ft)	Purged		Conductance (mS/cm)	(C) (F)	(NTU)	(PID readings, color, odor, etc.)
09/27/13 -	0930	0	C	5.48	0.0	*-2000-0000		entre de la constante de la co		Start
	1030	60	Owner Company of the	*>-datasemples	5.0			ALLEGATION CONTRACTOR	E3	
	1/00	90	**************************************	12.81	2.0		-ygan-grandersteiner,	**************************************	E3	
								n o vin o communitati po vincentri, profesione		
	1330		Vacqueroning .	11.48		-	Callageamprisations			Surged
			WWW.deleter							
09/30/13 -	1215	0	· Commence	10.44	0.0		And the second second	**************************************	E3	Start
	1245	30		12.11	1.75		Of the second se		E3	
	/330	75	-	13.0	0.25	PMCQUADrawing,		S. Marketonian and Marketonian	E2	
	1600		***************************************	12.51			,,440°03113411341144			Surged
10/1/13 -	0900	***************************************		12.23	-	**************************************	**************************************	***************************************		Surged
					uniopis uzamny second the double bridge from sph					**************************************
a de la companya de l	1/10	0		12.20	0.0	- Andrewson of the Control of the Co	***************************************	- management	w quantita wayyaya	Start
	1130	20	* Steffen Association	12.42	0.125			, processing to the second	E3	
or and a second										
t	-									

# Monitoring Well Development Log

									Page	of
	Project/No.	6	50.7	0		_Well /	MW-13-03	Date	09/26/	113-10/1/13
	Total Depth	15.0	)	Casing _Diameter	(inches)		2	Purge	Method Centrifug	al
	Water Level	4.7	<u> </u>	_Well Volu	ıme (gal)	1.6	66		Submers	ible
	Water Colum	n 10.	24	_Total Vol	ume Purged	7.	5		Other	
	Pump On			-	Pump Off		74-9-25 - Commission of the Co	Develo	ped By	DLW
	gallon/foot		Well Cash 1-1/4" = 0.0 1-1/2" = 0.0		2" = 0.1 2-½" = (	-	3" = 0. 3-½" =		4" = 0.65 6" = 1.47	
	Time	Minutes Elapsed	Rate (gpm) (mL/min)	DTW (ft)	Gallons Purged	рН	Specific Conductance (mS/cm)	Temp. (C) (F)	Turbidity (NTU)	REMARKS  (PID readings, color, odor, etc.)
09/26/13 -	1230	0	· American	4.76	0.0	N/Attingments	-territoriores-way	- Annual Printers	**************************************	Start
	1330	60	***************************************	45-Jackson-Statisting	3.5		честве в поставления в поставления в поставления в поставления в поставления в поставления в поставления в пос В поставления в	· semmentally	E3	
	1430	120	***CSOSSIUMS	13.11	1.5	ний байстаний.	Vaccinements/sectioning	7.max.ess	E3	
	1545	*	patie that the second participates are the second particip	11.73		-	***	~corondoscolomos		Surged
	1600	0		11.73	0.0		**Brazonias-postaria**		- Management	Start
	1620	20		13.95	0.25	**************************************			E3	
à .										
09/27/13 -	1300	:	*/2000000000000000000000000000000000000	12.48	* Agenda Andreas	«аномонуватальног»	Vaccourie-majorary	************	***************************************	Surged
	1400	0		9.82	0.0		100000000000000000000000000000000000000	Жетоннай разви	*-Attornoons	Stort
	1430	30	**************************************	13.31	0.5	**************************************	Capacity of the Control of the Contr		E3	
,										
09/30/13 -	1000	0		11.31	0.0	Carrie and Carrie and	Sample of the Sa	-management destructions	E3	Start
	1100	60		13.71	1.0	**************************************	**************************************		E3	
	1200	120	учения	14.49	0.5	*Shriumoni**	Guarante e e e e e e e e e e e e e e e e e e	\u00e400000000	E3	
	1545		Commence of the Commence of th	14.22	-	-communication	10000000000000000000000000000000000000		(Shareters)	Surged
10/1/13 -	0845	V		13.82			~	Sections	*Westermanne	Surged
, , , ,										
	1035	0	e Managara (Malanda)	13.82	0.0		Carried States		E3	Start
	1100	25	Tarabana Caranta da Para da Pa	14.21	0.25		Circle of the Control		E3	

# Summary of Water Level Measurements (September 26, 2013) NEIP AOC 1 7

Guilderland, New York

Well ID	Time	Depth to Water (ft btoc)	Well ID	Time	Depth to Water (ft btoc)
ACE-6	1000	6.71			
GW-11R	1010	7.84			
2BMW-9	1050	10.21			
MW-13-01	0930	6.58			
MW-13-02	0945	5.48			
MW-13-03	0900	4.76			
GW-03	1040	7.95			
GW-12	0920	3.90			
GW-13	1215	3.45			
GW-14	1200	4.44			
ACE-3	1100	8.14			
ACE-4	1120	6.79			
ACE-5	1135	3.25			
		and the second s			
				-	
· · · · · · · · · · · · · · · · · · ·					

### Notes:

- 1. btoc = below top of casing (measuring point is top of PVC riser)
- 2. All measurements expressed in feet.

# APPENDIX B IC/EC Certification Form

## **Enclosure 1**

## NEW YORK STATE DEPARTMENT OF ENVIRONMENTAL CONSERVATION Site Management Periodic Review Report Notice Institutional and Engineering Controls Certification Form

City/To County Curren	ame ddress: own:	Guilderland Albany County None	Site Details Park – AOCs 1 & 7 Zip Code: 12085	Во	x 1
V	<sup>v</sup> erificat	ion of Site Details		Bo	
				YES	NO
1.	Are the	Site Details above con	rrect?		
		are changes handwritte e sheet?	en above or included on a		
2. underg		<u> </u>	operty been sold, subdivided, merged, ce the initial/last certification?	or	
3.		<del>-</del>	r local permits (e.g. building, dischargince the initial/last certification?	ge) hav	e been
		, is documentation or e ted included with this o	evidence that documentation has been certification?	previo	usly
4.	If YES	•	since the initial/last certification? evidence that documentation has been certification?	□ previo	usly
5.	ECL 27 The Qu valid? If YES	7-1415.7(c), has any negalitative Exposure Ass , is the new information	ownfield Cleanup Program Sites subjects information revealed that assumption sessment for offsite contamination is not evidence that new information had with this Certification?	ons ma io long	
6.	1415.70 (must b	(c), are the assumption be certified every five y are changes in the asso	ownfield Cleanup Program Sites subjets in the Qualitative Exposure Assessnowears)? essment included with this		

	ITE NO. 401009 Box 3 Description of Institutional Control Control Certification		
Northeast Inc	lustrial Park – AOCs 1 and 7	YES	NO
Guilderland, N	NY		
Enviro	nmental Easement		
	Site Use Restriction		
	Ground Water Use Restriction		
	Land Use Restriction		
_	f Engineering Control lustrial Park – AOCs 1 and 7	Control Cer	Box 4 rtification
	onmental Easement	YES	NO
	Fencing/Access Control (Adjacent to AOCs 1 & 7)		
	Signage		
	Monitoring Wells		
	entation if IC/ECs cannot be certified or why lso see instructions)	IC/ECs are no lo	onger
	Control Certification Statemen	nt	
	ational or Engineering control listed above, I certificatements are true:	y by checking "Yo	es" that all of
(a)	The Institutional Control and/or Engineering Conunchanged since the date that the Control was pu		
(b)	by the Department; Nothing has occurred that would impair the ability	ey of such Control	, to protect
(c)	public health and the environment; Nothing occurred that would constitute a violatio Site Management Plan for this Control; and	n or failure to cor	nply with the
(d)	Access to the site will continue to be provided to remedy, including access to evaluate the continue		
(e)	If a financial assurance mechanism is required by site, the mechanism remains valid and sufficient established in the document.	the oversight doo	cument for the

## IC/EC CERTIFICATIONS SITE NO. 401009

		Box 5
SITE OWNER OR DESIGNATED		
I certify that all information and statements in Bo		
statement made herein is punishable as a Class "A	A" misdemeanor, pursuant to Section	210.45 of
the Penal Law.		
Iat		,
print name	print business address	
am certifying as	(Owner or Reme	edial Party)
For the Site named in the Site Details Section of	this form.	•
Signature of Overson on Domadial Bouty Dandania	Contification Data	
Signature of Owner or Remedial Party Rendering	g Certification Date	
		Box 6
QUALIFIED ENVIRONMENTAL P	ROFFSSIONAL (OFP) SIGNAT	THRE
QUALITIED ENVIRONMENTAL I	ROTESSIONAL (QLI) SIGNA	ICKE
I certify that al information and statements in	Box 4 are true. I understand that a	a false
statement made herein punishable as a Class		
210.45 of the Penal Law.	, F	
I at		
print name	print business address	
am certifying as a Qualified Environmental F	Professional for the	
(Owner or Remedial Party) for the Site Name		
(O What of Itemsoulur I wroj) for the Site I want	20 11 010 2100 2 000111 2 0 0011 2 01 01 01 01 01 01 01 01 01 01 01 01 01	.5 101111
Signature of Qualified Environmental Profession	Ctamp	Dete
Signature of Qualified Environmental Profession		Date
for the Owner or Remedial Party, Rendering	(If required)	
Certification		

#### **Enclosure 2**

# **Certification of Institutional Controls/ Engineering Controls (IC/ECs) Step-by-Step Instructions, Certification Requirements and Definitions**

The Owner, or Remedial Party, and when necessary, a Professional Engineer (P.E.), or the Qualified Environmental Professional (QEP), must review and complete the IC/EC Certification Form, sign the IC/EC Certifications Signature Page, and return it, along with Annual Sampling Report, within 45 days of the date of this notice.

Please use the following instructions to complete the IC/EC Certification.

### **I. Verification of Site Details** (Box 1 and Box 2):

1. Answer the six questions in the Verification of Site Details Section. Questions 5 and 6 only refer to sites in the Brownfield Cleanup Program. Environmental Conservation Law (ECL) Section 27-1415-7(c) is included in Section IV. IC/EC Certification Requirements, below. The owner and/or your P.E. or QEP may include handwritten changes and/or other supporting documentation, as necessary.

### **II. Verification of Institutional/ Engineer Controls** (Box 3 and Box 4)

- 1. Review the listed IC/ ECs, confirming that all exiting controls are listed, and that all existing controls are still applicable. If there is a control that is no longer applicable the Owner/ Remedial Party is to petition the Department requesting approval to remove the control.
- 2. Select "YES" or "NO" for **Control Certification** for each IC/EC, based on Sections (a)-(e) of the **Control Certification Statement.**
- 3. If you cannot certify "YES" for each Control, please continue to complete the remainder of this **Control Certification** form. Attach supporting documentation that explains why the **Control Certification** cannot be rendered, as well as a statement of proposed corrective measures, and an associated schedule for completing the corrective measures. Note that this **Control Certification** form must be submitted even if an IC or EC cannot be certified; however, the certification process will not be considered complete until corrective action is conducted.

If the Department concurs with the explanation, the corrective measures, and the proposed schedule, a letter authorizing the implementation of those corrective measures will be issued by the Project Manager. Once the corrective measures are complete, a new IC/EC Certification is to be submitted within 45 days to the Department. If the Department has any questions or concerns regarding the IC/EC Certification, the Project Manager will contact you.

### **III. IC/EC Certification by Signature** (Box 5 and Box 6):

1. If you certified "YES" for each Control, please complete and sign the IC/EC Certification page. To determine WHO signs the IC/EC Certification, please use Table 1, Signature Requirements for the IC/EC Certification, below.

Table 1. Signature Requirements for Control Certification Page			
Type of Control	Example of IC/EC	Required Signatures	
IC	Environmental Easement Deed Restriction.	A site or property owner or remedial party	
EC which does not include a treatment system or engineered caps.	Fence, Clean Soil Cover, Individual House Water treatment System, Vapor Mitigation System	A site or property owner or remedial part, and a QEP. (P.E. license not required)	
EC that includes treatment system or an engineered cap.	Pump & Treat System providing hydraulic control of a plume, Part 360 Cap.	A site or property owner or remedial party, and a QEP with a P.E. license.	

### **IV. IC/EC Certification Requirements:**

ECL requires periodic certification of IC(s) and EC(s) as follows:

<u>Environmental Restoration Program (ERP):</u> ECL Section 56-0503. (Environmental restoration projects; state assistance)

State Superfund Program (SSF): ECL 27-1318. (Institutional and engineering controls)

<u>Brownfields Cleanup Program (BCP):</u> ECL Section 27-1415. (Remedial program requirements)

#### ECL Section 27-1415(c) states:

"At non-significant threat sites where contaminants in groundwater at the site boundary contravene drinking water standards, certification shall also certify that no new information has come to the owner's attention, including groundwater monitoring data from wells locates at the site boundary, if any, to indicate that the assumptions made in the qualitative exposure assessment of offsite contamination are no longer valid. Every five years the owners at such sites shall certify that the assumptions made in the qualitative exposure assessment remain valid. The requirement to provide such certifications may be terminated by a written determination by the Commissioner in consultation with the Commissioner of Health, after notice to the parties on the brownfield site contact list

Voluntary Cleanup Program (VCP): Applicable program guidance

<u>Response Program – Petroleum Remediation</u>: Applicable program guidance.

Federal Brownfields Program: Applicable program guidance.

<u>Manufactures Gas Plant (MGP) Projects:</u> Applicable division guidance (including non-registry listed MGPs).

WHERE to mail the signed Certification Form:

New York State Department of Environmental Conservation
Division of Environmental Remediation

Remedial Bureau A, 625 Broadway, 11th Floor, Albany, NY 12233-7015

Attn: Heather Bishop, Project Manager

Please note that extra postage may be required.

### V. Definitions

"Engineer Control" (EC) means any physical barrier or method employed to actively or passively contain, stabilize, or monitor contamination, restrict the movement of contamination to ensure the long-term effectiveness of a remedial program, or eliminate potential exposure pathways to contamination. Engineering controls include, but are not limited to, pavement, caps, covers, subsurface barriers, vapor barriers, slurry walls, building ventilation systems, fences, access controls, and provision of alternative water supplies via connection to an existing public water supply, adding treatment technologies to such water supplies, and installing filtration devices on private water supplies.

**"Institutional Control"** (IC) means any non-physical means of enforcing a restriction on the use of real property that limits human and environmental exposure, restricts the use of groundwater, provides notice to potential owners, operators, or members of the public, or prevents actions that would interfere with the effectiveness of a remedial program or with the effectiveness and/or integrity of operation, maintenance, or monitoring activities at or pertaining to a remedial site.

**"Professional Engineer"** (P.E.) means an individual or firm licensed, or otherwise authorized under article 145 of the Education Law of the State of New York, to practice engineering.

**"Property Owner"** means, for purposes of an IC/EC certification, the actual owner of a property. If the site has multiple properties with different owners, the Department requires that the owners be represented by a single representative to sign the IC/EC Certification.

"Oversight Document" means any document the Department issues pursuant to each Remedial Program to define the role of a person participating in the investigation and/or remediation of a site or area(s) of concern. Examples for the various programs are:

**BCP** (after approval of the BCP application by Department) - Brownfield Site Cleanup Agreement.

**ERP** (after approval of the ERP application by Department) - State Assistance Contract.

**Federal Superfund Sites** - Federal Consent Decrees, Administrative Orders on Consent or Unilateral Orders issued pursuant to CERCLA.

**Response Program** - Order on Consent, or Stipulation pursuant to Article 12 of the Navigation Law (and the ECL).

**SSF Program** - Administrative Consent Order, Record of Decision.

**VCP** (after approval of the VCP application by Department) - Voluntary Cleanup Agreement.

**RCRA Corrective Action Sites**- Federal Consent Decrees, Administrative Orders on Consent or permit conditions issued pursuant to RCRA.

- "Qualified Environmental Professional" (QEP) means a person who possesses sufficient specific education, training, and experience necessary to exercise professional judgment to develop opinions and conclusions regarding the presence of releases or threatened releases to the surface or subsurface of a property or off-site areas, sufficient to meet the objectives and performance factors for the areas of practice identified by this Part. Such a person must:
- (1) Hold a current professional engineer's or a professional geologist's license or registration issued by the State or another state, and have the equivalent of three years of full-time relevant experience in site investigation and remediation of the type detailed in this Part; or
- (2) Be a site remediation professional licensed or certified by the federal government, a state or a recognized accrediting agency, to perform investigation or remediation tasks consistent with Department guidance, and have the equivalent of three years of full-time relevant experience.
- "Qualitative Exposure Assessment" means a qualitative assessment to determine the route, intensity, frequency, and duration of actual or potential exposures of humans and/or fish and wildlife to contaminants.
- **"Remedial Party"** means a person implementing a remedial program at a remedial site pursuant to an order, agreement or State assistance contract with the Department.
- **"Site Management"** (SM) means the activities undertaken as the last phase of the remedial program at a site, which continue after a Certificate of Completion is issued. Site management is conducted in accordance with a site management plan, which identifies and implements the IC/ECs required for a site, as well as any necessary monitoring and/or operation and maintenance of the remedy.
- "Site Management Plan" (SMP) means a document which details the steps necessary to assure that the institutional and engineering controls required for a site are in-place, and any physical components of the remedy are operated, maintained and monitored to assure their continued effectiveness, developed pursuant to Section 6 of DER-10, *Technical Guidance for Site Investigation and Remediation*.
- **"Site Owner"** means the actual owner of a site. If the site has multiple owners of multiple properties with ICs and/or ECs, the Department requires that the owners designate a single representative for IC/EC Certification activities.

# APPENDIX C Landfill Cap/Soil Cover Inspection Forms



## **COVER SHEET**

# LANDFILL CAP/SOIL COVER INSPECTION AOC 1, Northeast Industrial Park, Guilderland, New York

FORM	DESCRIPTION	COMPLETED?	DATE COMPLETED
Form -1	Final Cover/Cap System		
Form -2	Stormwater Drainage Ditches		
Form -3	<b>Deficiencies and Problems</b>		

Notes:	
Attach and complete all Forms listed above.	Check and date each Form at the time of completion.
WEATHER CONDITIONS:	
Inspection Date:	INSPECTOR:
inspection Date.	SIGNATURE:



## FORM: Form-1

# FINAL COVER/CAP SYSTEM – INSPECTION CHECKLIST AOC 1, Northeast Industrial Park, Guilderland, New York

ITEM ITEM		Inspection Area	
NO.	TITLE	Landfill Cap	Soil Cover
1	Surface Cracks		
2	Vegetative Growth		
3	Vector Penetration		
4	Settlement		
5	Erosion		
6	Slope Stability		
7	Seepage		
8	Condition of Fencing and Gates		
9	Condition of Monitoring Wells		
10	Vandalism and Illegal entry/use		



11	Change in Land Use since Last Inspection	
12	Wildlife Observations (Beaver Activity)	

### **Notes:**

- 1. Check  $(\checkmark)$ : Area has been inspected for this condition and no problems were reported pertaining to the final cover system.
- 2. Not Satisfactory (NS): Area has been inspected for this condition and problems have been identified. \* = viewed as a minor Not Satisfactory condition. A description of deficiencies is provided on Form 3.

<b>Inspection Date:</b>	INSPECTOR:
	SIGNATURE:



## FORM: Form-2

# STORMWATER MANAGEMENT SYSTEM – INSPECTION CHECKLIST AOC 1, Northeast Industrial Park, Guilderland, New York

ITEM	ITEM TITLE	Inspection Area	
NO.		Landfill Cap	Soil Cover
1	Overgrown Vegetation		
2	Standing Water		
3	Sediments and Debris		
4	Erosion/Washouts		
5	Culvert (where present)		
6	Damage to riprap (where applicable)		

### **Notes:**

- 1. Check  $(\checkmark)$ : Area has been inspected for this condition and no problems were reported pertaining to the stormwater management system.
- 2. Not Satisfactory (NS): Area has been inspected for this condition and problems have been identified. . \* = viewed as a minor Not Satisfactory condition. A description of deficiencies is provided on Form-3.

Inspection Date:	INSPECTOR:
	SIGNATURE:



# FORM: Form-3

# **DESCRIPTION OF DEFICIENCIES AND PROBLEMS AOC 1, Northeast Industrial Park, Guilderland, New York**

	_

<b>Inspection Date:</b>	INSPECTOR:	
_		
	<b>SIGNATURE</b> :	

## APPENDIX D

## **Environmental Easement**

Pending

# ENVIRONMENTAL EASEMENT GRANTED PURSUANT TO ARTICLE 71, TITLE 36 OF THE NEW YORK STATE ENVIRONMENTAL CONSERVATION LAW

THIS INDENTURE made this 21 st day of July , 2015, between Owner(s) Northeastern IP Holdings, Inc., having an office at 695 Rotterdam Industrial Park, Schenectady, New York 12306, County of Albany, State of New York (the "Grantor"), and The People of the State of New York (the "Grantee."), acting through their Commissioner of the Department of Environmental Conservation (the "Commissioner", or "NYSDEC" or "Department" as the context requires) with its headquarters located at 625 Broadway, Albany, New York 12233,

WHEREAS, the Legislature of the State of New York has declared that it is in the public interest to encourage the remediation of abandoned and likely contaminated properties ("sites") that threaten the health and vitality of the communities they burden while at the same time ensuring the protection of public health and the environment; and

WHEREAS, the Legislature of the State of New York has declared that it is in the public interest to establish within the Department a statutory environmental remediation program that includes the use of Environmental Easements as an enforceable means of ensuring the performance of operation, maintenance, and/or monitoring requirements and the restriction of future uses of the land, when an environmental remediation project leaves residual contamination at levels that have been determined to be safe for a specific use, but not all uses, or which includes engineered structures that must be maintained or protected against damage to perform properly and be effective, or which requires groundwater use or soil management restrictions; and

WHEREAS, the Legislature of the State of New York has declared that Environmental Easement shall mean an interest in real property, created under and subject to the provisions of Article 71, Title 36 of the New York State Environmental Conservation Law ("ECL") which contains a use restriction and/or a prohibition on the use of land in a manner inconsistent with engineering controls which are intended to ensure the long term effectiveness of a site remedial program or eliminate potential exposure pathways to hazardous waste or petroleum; and

WHEREAS, Grantor, is the owner of real property located at the address of 2 Van Buren Blvd in the Town of Guilderland, County of Albany and State of New York, known and designated on the tax map of the County Clerk of Albany as tax map parcel numbers: Section 50 Block 1 Lot 14.21, being the same as that property conveyed to Grantor by deed dated September 30, 2001 and recorded in the Albany County Clerk's Office in Liber and Page 2720/1002. The property subject to this Environmental Easement (the "Controlled Property") comprises approximately 26.062 +/-acres, and is hereinafter more fully described in the Land Title Survey dated January 2, 2013 and last revised on March 31, 2014 prepared by Bruce W. Snyder, Delta Engineers, Architects, & Land Surveyors, which will be attached to the Site Management Plan. The Controlled Property description is set forth in and attached hereto as Schedule A; and

WHEREAS, the Department accepts this Environmental Easement in order to ensure the protection of public health and the environment and to achieve the requirements for remediation established for the Controlled Property until such time as this Environmental Easement is

extinguished pursuant to ECL Article 71, Title 36; and

NOW THEREFORE, in consideration of the mutual covenants contained herein, Grantor conveys to Grantee a permanent Environmental Easement pursuant to ECL Article 71, Title 36 in, on, over, under, and upon the Controlled Property as more fully described herein ("Environmental Easement")

- 1. <u>Purposes</u>. Grantor and Grantee acknowledge that the Purposes of this Environmental Easement are: to convey to Grantee real property rights and interests that will run with the land in perpetuity in order to provide an effective and enforceable means of encouraging the reuse and redevelopment of this Controlled Property at a level that has been determined to be safe for a specific use while ensuring the performance of operation, maintenance, and/or monitoring requirements; and to ensure the restriction of future uses of the land that are inconsistent with the above-stated purpose.
- 2. <u>Institutional and Engineering Controls.</u> The controls and requirements listed in the Department approved Site Management Plan ("SMP") including any and all Department approved amendments to the SMP are incorporated into and made part of this Environmental Easement. These controls and requirements apply to the use of the Controlled Property, run with the land, are binding on the Grantor and the Grantor's successors and assigns, and are enforceable in law or equity against any owner of the Controlled Property, any lessees and any person using the Controlled Property.
  - A. (1) The controlled property is currently zoned for industrial uses as described in 6 NYCRR Part 375-1.8 (g)(2)(iv) and Guilderland Code 280-23.I. The controlled property is subject to additional restrictions as set forth in this Environmental Easement and Site Management Plan.
- (2) All Engineering Controls must be operated and maintained as specified in the Site Management Plan (SMP);
- (3) All Engineering Controls must be inspected at a frequency and in a manner defined in the SMP;
- (4) The use of groundwater underlying the property is prohibited without necessary water quality treatment as determined by the NYSDOH or the Albany County Department of Health to render it safe for use as drinking water or for industrial purposes, and the user must first notify and obtain written approval to do so from the Department;
- (5) Groundwater and other environmental or public health monitoring must be performed as defined in the SMP;
- (6) Data and information pertinent to Site Management of the Controlled Property must be reported at the frequency and in a manner defined in the SMP;

(7) All future activities on the property that will disturb remaining contaminated

material must be conducted in accordance with the SMP;

- (8) Monitoring to assess the performance and effectiveness of the remedy must be performed as defined in the SMP;
- (9) Operation, maintenance, monitoring, inspection, and reporting of any mechanical or physical components of the remedy shall be performed as defined in the SMP;
- (10) Access to the site must be provided to agents, employees or other representatives of the State of New York with reasonable prior notice to the property owner to assure compliance with the restrictions identified by this Environmental Easement.
- B. The Controlled Property shall not be used for Residential or Restricted Residential purposes as defined in 6NYCRR 375-1.8(g)(2)(i) and (ii), and the above-stated engineering controls may not be discontinued without an amendment or extinguishment of this Environmental Easement.
- C. The SMP describes obligations that the Grantor assumes on behalf of Grantor, its successors and assigns. The Grantor's assumption of the obligations contained in the SMP which may include sampling, monitoring, and/or operating a treatment system, and providing certified reports to the NYSDEC, is and remains a fundamental element of the Department's determination that the Controlled Property is safe for a specific use, but not all uses. The SMP may be modified in accordance with the Department's statutory and regulatory authority. The Grantor and all successors and assigns, assume the burden of complying with the SMP and obtaining an up-to-date version of the SMP from:

Site Control Section Division of Environmental Remediation NYSDEC 625 Broadway Albany, New York 12233 Phone: (518) 402-9553

- D. Grantor must provide all persons who acquire any interest in the Controlled Property a true and complete copy of the SMP that the Department approves for the Controlled Property and all Department-approved amendments to that SMP.
- E. Grantor covenants and agrees that until such time as the Environmental Easement is extinguished in accordance with the requirements of ECL Article 71, Title 36 of the ECL, the property deed and all subsequent instruments of conveyance relating to the Controlled Property shall state in at least fifteen-point bold-faced type:

This property is subject to an Environmental Easement held by the New York State Department of Environmental Conservation

# pursuant to Title 36 of Article 71 of the Environmental Conservation Law.

- F. Grantor covenants and agrees that this Environmental Easement shall be incorporated in full or by reference in any leases, licenses, or other instruments granting a right to use the Controlled Property.
- G. Grantor covenants and agrees that it shall, at such time as NYSDEC may require, submit to NYSDEC a written statement by an expert the NYSDEC may find acceptable certifying under penalty of perjury, in such form and manner as the Department may require, that:
  - (1) the inspection of the site to confirm the effectiveness of the institutional and engineering controls required by the remedial program was performed under the direction of the individual set forth at 6 NYCRR Part 375-1.8(h)(3).
    - (2) the institutional controls and/or engineering controls employed at such site:
      - (i) are in-place;
    - (ii) are unchanged from the previous certification, or that any identified changes to the controls employed were approved by the NYSDEC and that all controls are in the Department-approved format; and
    - (iii) that nothing has occurred that would impair the ability of such control to protect the public health and environment;
  - (3) the owner will continue to allow access to such real property to evaluate the continued maintenance of such controls;
  - (4) nothing has occurred that would constitute a violation or failure to comply with any site management plan for such controls;
  - (5) the report and all attachments were prepared under the direction of, and reviewed by, the party making the certification;
  - (6) to the best of his/her knowledge and belief, the work and conclusions described in this certification are in accordance with the requirements of the site remedial program, and generally accepted engineering practices; and
    - (7) the information presented is accurate and complete.
- 3. <u>Right to Enter and Inspect</u>. Grantee, its agents, employees, or other representatives of the State may enter and inspect the Controlled Property in a reasonable manner and at reasonable times to assure compliance with the above-stated restrictions.
- 4. <u>Reserved Grantor's Rights.</u> Grantor reserves for itself, its assigns, representatives, and successors in interest with respect to the Property, all rights as fee owner of the Property, including:
- A. Use of the Controlled Property for all purposes not inconsistent with, or limited by the terms of this Environmental Easement;
- B. The right to give, sell, assign, or otherwise transfer part or all of the underlying fee interest to the Controlled Property, subject and subordinate to this Environmental Easement;

### 5. Enforcement

- A. This Environmental Easement is enforceable in law or equity in perpetuity by Grantor, Grantee, or any affected local government, as defined in ECL Section 71-3603, against the owner of the Property, any lessees, and any person using the land. Enforcement shall not be defeated because of any subsequent adverse possession, laches, estoppel, or waiver. It is not a defense in any action to enforce this Environmental Easement that: it is not appurtenant to an interest in real property; it is not of a character that has been recognized traditionally at common law; it imposes a negative burden; it imposes affirmative obligations upon the owner of any interest in the burdened property; the benefit does not touch or concern real property; there is no privity of estate or of contract; or it imposes an unreasonable restraint on alienation.
- B. If any person violates this Environmental Easement, the Grantee may revoke the Certificate of Completion with respect to the Controlled Property.
- C. Grantee shall notify Grantor of a breach or suspected breach of any of the terms of this Environmental Easement. Such notice shall set forth how Grantor can cure such breach or suspected breach and give Grantor a reasonable amount of time from the date of receipt of notice in which to cure. At the expiration of such period of time to cure, or any extensions granted by Grantee, the Grantee shall notify Grantor of any failure to adequately cure the breach or suspected breach, and Grantee may take any other appropriate action reasonably necessary to remedy any breach of this Environmental Easement, including the commencement of any proceedings in accordance with applicable law.
- D. The failure of Grantee to enforce any of the terms contained herein shall not be deemed a waiver of any such term nor bar any enforcement rights.
- 6. <u>Notice</u>. Whenever notice to the Grantee (other than the annual certification) or approval from the Grantee is required, the Party providing such notice or seeking such approval shall identify the Controlled Property by referencing the following information:

County, NYSDEC Site Number, NYSDEC Brownfield Cleanup Agreement, State Assistance Contract or Order Number, and the County tax map number or the Liber and Page or computerized system identification number.

Parties shall address correspondence to: Site Number: 401009

Office of General Counsel

NYSDEC 625 Broadway

Albany New York 12233-5500

With a copy to: Site Control Section

Division of Environmental Remediation

NYSDEC 625 Broadway Albany, NY 12233

All notices and correspondence shall be delivered by hand, by registered mail or by Certified mail and return receipt requested. The Parties may provide for other means of receiving and communicating notices and responses to requests for approval.

- 7. <u>Recordation</u>. Grantor shall record this instrument, within thirty (30) days of execution of this instrument by the Commissioner or her/his authorized representative in the office of the recording officer for the county or counties where the Property is situated in the manner prescribed by Article 9 of the Real Property Law.
- 8. <u>Amendment</u>. Any amendment to this Environmental Easement may only be executed by the Commissioner of the New York State Department of Environmental Conservation or the Commissioner's Designee, and filed with the office of the recording officer for the county or counties where the Property is situated in the manner prescribed by Article 9 of the Real Property Law.
- 9. <u>Extinguishment</u>. This Environmental Easement may be extinguished only by a release by the Commissioner of the New York State Department of Environmental Conservation, or the Commissioner's Designee, and filed with the office of the recording officer for the county or counties where the Property is situated in the manner prescribed by Article 9 of the Real Property Law.
- 10. <u>Joint Obligation</u>. If there are two or more parties identified as Grantor herein, the obligations imposed by this instrument upon them shall be joint and several.

**IN WITNESS WHEREOF,** Grantor has caused this instrument to be signed in its name.

Northeastern IP Holdings, Inc.:

By:

Print Name: David M. Buicko

Title: Execting Pres/COO Date: 7/21/15

### Grantor's Acknowledgment

STATE OF NEW YORK	)
COUNTY OF Schenectad	(Y) ss

Adulu D. Under Notary Public - State of New York

SANDRA D. ANDI
Notary Public, State of New York
No. 4737914
Qualified in Albany County
Commission Expires November 30, 20

THIS ENVIRONMENTAL EASEMENT IS HEREBY ACCEPTED BY THE PEOPLE OF THE STATE OF NEW YORK, Acting By and Through the Department of Environmental Conservation as Designee of the Commissioner,
Robert W. Schick, Director Division of Environmental Remediation
Grantee's Acknowledgment
STATE OF NEW YORK ) ) ss: COUNTY OF ALBANY )
On the day of, in the year 20, before me, the undersigned, personally appeared Robert W. Schick, personally known to me or proved to me on the basis of satisfactory evidence to be the individual(s) whose name is (are) subscribed to the within instrument and acknowledged to me that he/she/ executed the same in his/her/ capacity as Designee of the Commissioner of the State of New York Department of Environmental Conservation, and that by his/her/ signature on the instrument, the individual, or the person upon behalf of which the individual acted, executed the instrument.
Notary Public - State of New York

# SCHEDULE "A" PROPERTY DESCRIPTION

See Attached.

# **LOCATION MAP:** NOT TO SCALE

PROPOSED DESCRIPTION OF A PORTION OF THE LANDS OF NORTHEASTERN IP HOLDINGS, INC.

DEPOT ROAD, TOWN OF GUILDERLAND, ALBANY COUNTY

# "ENVIRONMENTAL EASEMENT PARCEL"

AND DESCRIBED AS FOLLOWS:

Subject to a 15 ft. wide permanent easement, reserved to the United States of America, its successors and assigns, for joint use with the Town of Guilderland Urban Renewal Agency, its successors and assigns, of the existing railroad tracks, together with an easement for the installation, construction,

# **ENVIRONMENTAL EASEMENT DESCRIPTION:**

ALL THAT TRACT OR PARCEL OF LAND SITUATE IN THE TOWN OF GUILDERLAND, COUNTY OF ALBANY AND STATE OF NEW YORK, BOUNDED

Beginning at a point on the northerly highway boundary of Stone Road (Depot Road) (Voorheesville - Guilderland Center County Road #201), said point standing at the intersection of the northerly highway boundary of Stone Road (Depot Road) (Voorheesville - Guilderland Center County Road #201) with the westerly boundary of the lands of CSX Transportation, Inc. (Reputed Owner) (New York Central Railroad Company - Now or Formerly) (West Shore Railroad); thence \$89°03'21"W 176.16 feet along the northerly highway boundary of Stone Road (Depot Road) (Voorheesville - Guilderland Center County Road #201) to a metal fence post; thence N88°25'41"W 300.02 feet continuing along the northerly highway boundary of Stone Road (Depot Road) (Voorheesville - Guilderland Center County Road #201) to a metal fence post; thence N80° 53'43"W 66.23 feet to a metal fence post; thence N81°55'11"W 88.99 feet to an iron rod; thence N03°09'49"E 1.00 feet to an iron rod; thence N87°55'11"W 70.55 feet still along the northerly highway boundary of Stone Road (Depot Road) (Voorheesville - Guilderland Center County Road #201) to an iron rod: thence N33°25'31"W 1.046.57 feet to an iron rod: thence northerly 487.89 feet along a curve to the left with a radius of 410.00 feet, a delta angle of 68°10'48" and a chord bearing and distance of N01°40'04"E 459.61 feet to an iron rod, thence N32°25'20"W 785.00 feet to an iron rod; thence N70°57'28"E 343.83 feet to an iron rod standing on the westerly boundary of the lands reputedly owned by CSX Transportation, Inc.; thence S32°25'20"E 2,534.68 feet along the westerly boundary of the lands of reputedly owned by CSX Transportation, Inc. to the point and place of beginning.

The above described Environmental Easement parcel containing 26.062 Acres (1,135,281.3 sq.ft.) more or less.

maintenance, replacement, or relocation and patrol of such facilities, in, on, over, and through the above referenced premises.

Also subject to any other easements, covenants or restrictions of record.

## the point and place of beginning. Remaining Lands Of Northeastern IP Holdings , INC. — land 15 feet in width, the center line of which are described as follows: (Now or Formerly) Liber 2720 / Page 1002 Being Part Of Tax Parcel 50.00-1-14.21 "263.4± ACRES" By Tax Mapping circle curving to the left, having a central angle of 7°0', a radius of 490.51 feet for an arc distance of 59.92 feet; 1.00' Bench Tie Set In Niagara ohawk Power Pole 14 Remaining Lands Of vation = 330,33 (NAVD 8 —— Northeastern IP Holdings , INC. —— (318.9945 Meters) (Now or Formerly) 1046.57' N33°25'31"W Liber 2720 / Page 1002 N81°55'11"W Being Part Of Tax Parcel 50.00-1-14.21 — Wooded And — "263.4± ACRES" Overgrown Area RESERVING To The United States Of America, Its Successors And Assigns. A Permanent Easement For Joint Use With Town of Guilderland By Tax Mapping Metal pproximate Limits Of Wetland Area By Railroad Tracks, Together With An Easement For The Installation, Fence Post -Construction, Maintenance, Replacement, Or Relocation And Patrol Of Such N80°53'43"W Facilities, In, On, Over, And Through Two Strips Of Land 15 Feet In Width. 66.23' **INSERT 'A'** N32°25'20"W N88°25'41"W **Existing Split** 300.02'-Rail Fence Line — (91.4461 Meters) Northerly Highway Boundary Stone Road By Map Reference #1 Existing Chain Link Fence Line S89°03'21"W ederal Wetland "PUBHh" E 176.16' Federal Wetland Map Overlay (53.6935 Meters) -At Property Corner $\sim$ POND $\sim$ (Located On December 11, 2013) N70°57'28"E 343.83' (104.7994 Meters) S32°25'20"E 2534.68' 26.062± Acre Parce CSX TRANSPORTATION. INC.ederal Wetland "PEM1E" By Existing Railroad Tracks— (Reputed Owner) Federal Wetland Map Overlay Bench Tie Set In Niagara (FORMER - NEW YORK CENTRAL RAILROAD COMPANY Mohawk Power Pole 11-1 (WEST SHORE RAILROAD) Elevation = 339.57 (NAVD 88

# **LEGEND:**

- ® Denotes Existing Iron Rod
- SIR O Denotes Set Iron Rod
- SIR Denotes Set Metal Survey Marker
- Denotes Existing Power Pole ——— || ——— Denotes Overhead Power Pole Line
  - FHO Denotes Existing Fire Hydrant
  - GW 12 ♦ Denotes Existing Monitoring Well MW 13 03 ♦ Denotes Existing Monitoring Well
- Denotes Existing Bollard Denotes Existing Street Sign **— — — — — Denotes Location Of Landfill Cap Area**
- By Map Reference #2 - - - - Denotes Location Of Soil Cover Area By Map Reference #2
  - AOC 7 Denotes Location Of Area Of Concern

Unauthorized Alteration Or Addition To A Survey Map Bearing A Licensed Land Surveyor's Seal Is A Violation Of Section 7209-2, Of The New York State Education Law. Only Copies From The Original Of This Survey Marked With The Land Surveyor's

Signature And An Original Embossed Or Ink Seal Shall Be Considered Valid True Copies.

# **DEED REFERENCE:**

Northeastern Industrial Park, Inc.

(D.R. #1) Northeastern IP Holdings, Inc. Quit Claim Deed - Dated: September 30, 2002 Liber 2720 Of Deeds At Page 1002

Subject to any state of facts a current Abstract of Title may show.

Subject to any other Easements, Covenants or Restrictions of Record

# **MAP REFERENCES:**

"Survey And Map Of Lands Leased To Northeastern Industrial Park, Inc. Showing Buildings, Easements And Exceptions" By Richard Danskin, P.C., Dated August 15, 1980, Revised On October 2, 1980 And Last Revised On May 19, 2003

(M.R. #2)

Northeast Industrial Park Area Of Concern 1 Landfill Cap / Soil Cover Site Plan" Town Of Guilderland - Albany County - State Of New York By U.S. Army Corps Of Engineers, New England District

Concord, Massachusetts Dated January 23, 2014

# **SCALE: 1" = 120 FEET**

# **SCALE: 1" = 36.58 METERS**

# 36,58 M 73,15 M 109,73 N

# **STATEMENT OF ENCROACHMENTS:**

A Existing Railroad Tracks Encroach Over The Northwest Property Line Of The "Environmental Easement" Onto The Remaining Lands Of Northeastern IP Holdings, INC. A Distance Of 2.5 Feet By 1272.89 Feet.

**TOTAL ACREAGE ENVIRONMENTAL EASEMENT IS "26.062± ACRES"** 

# **RECORD LEGAL DESCRIPTION:**

ALL THAT CERTAIN TRACT, PIECE OR PARCEL OF LAND situate lying and being in the Town of Guilderland, County of Albany, and State of New York, more particularly bounded and described as follows:

BEGINNING at the intersection of the westerly right-of-way line of the New York Central Railroad (West Shore Branch) with the northeasterly side of County Highway #201 and runs thence northwesterly and northerly along said highway to following courses and distances: S89°03'21"W, 176.16 feet: N88°25'41"W, 300.02 feet: N80°53'43"W, 66.23 feet; N87°55'11"W, 88 feet; N3°09'49"E, 1.0 feet; N87°55'11"W, 1,108.00 feet; N74°10'13"W, 293.00 feet; N67°26'13"W, 129.0 feet; N57°59'04"W, 272.37 feet; N58°02'00"W, 885.00 feet; N61°50'00"W, 38.95 feet; S73°37'00"W, 19.15 feet; N58°25'00"W, 113.27 feet; N76°03'00"W, 640.46 feet; N76°13'21"W, 301.67 feet; N63°07'21"W, 648.15 feet; N49°16'21 W, 244.51 feet; N41°34'21"W, 273.19 feet; N30°45'21"W, 135.55 feet; N31°33'21"W, 132.80 feet; N16°09'21"W, 447.43 feet; N16°17'20"W, 90.02 feet; N78°55'50"E, 1.0 feet; N00°11'50"E, 918.07 feet N03°23'50"E, 251.00 feet: N00°43'10"W, 604.00 feet: N9°23'00"W, 381.31 feet: N21°16'10"W, 1.155.00 feet: N74°05'10"W, 1.0 feet: N11°53'53"W, 293.54 feet; N19°19'08"W, 225.67 feet; N30°43'12"W, 314.53 feet to the lands formerly of Iva Bloomingdale, now of Central School District No. 2 of the Town of Guilderland, Bethlehem, and New Scotland; thence along said School District lands the following four courses and distances: (1) N59°03'08"E, 234.61 feet; (2) S85°10'41"E, 353.57 feet; (3) N14°36'26"E, 2,665.08 feet; (4) N27°32'54"W. 294.50 feet: thence N24°22'06"E, crossing Black Creek, 27.50 feet to the easterly side thereof: thence S35°04'32"E along the northeasterly side of said Creek, 408.00 feet; thence S66°27'29"E, 1,053.02 feet; thence N13°43'19"E, 621.61 feet; thence N13°46'50"W, 334.21 feet; thence N75°27'26"E, 45.70 feet to the westerly boundary of the New York Central Railroad right-of-way (West Shore Branch); thence along said right-of-way the 7 following courses and distances: (1) S14°07'00"E, 235.15 feet: (2) N75°53'00"E, 13.00 feet; (3) S14°07'00", 4,848.91 feet; (4) thence southerly on the arc of a circle curving to the left having a radius of 4,649.56 feet, a central angle of 5°11'25" for an arc distance of 421.19 feet; (5) thence S19°18"35"E, a distance of 993.53 feet; (6) thence on the arc of a circle, curving to the left having a radius of 1,369.70 feet, a central angle of 13°06'45" for an arc distance of 313.46 feet; (7) thence S32°25'20"E, a distance of 3,607.10 feet to the point and place of beginning.

As shown on a map entitled Survey and Map of Lands Leased to Northeastern Industrial Park, Inc., showing buildings, easements, and exceptions prepared by Richard Danskin, P.C., dated August 15, 1980, and revised October 2, 1980, last revised January 26,

EXCEPTING AND RESERVING, therefrom, all the tract or parcel of land, situate in the Town of Guilderland, County of Albany, and State of New York, bounded and described as follows: BEGINNING at the centerline of a concrete monument on the easterly side of County Highway #201 at the northwesterly corner of the herein described parcel and runs thence N80°20'39"E, a distance of 923.58 feet; thence S19°39'21"E, along present fence a distance of 253.58 feet; thence S06°31'21"E, a distance of 91.43 feet; thence S5°40'39"W, a distance of 121.01 feet; thence S8°49'39"W, 211.50 feet; thence S6°57'39"W, a distance of 100.96 to a fence corner; thence N72°42'39"E, a distance of 360.02 feet; thence S53°16'21"E, a distance of 24.88 feet; thence N61°37'39"E, a distance of 130.32 feet; thence N89°15'39"E, a distance of 120.52 feet: thence S32°46'35"E, a distance of 909.79 feet to a fence corner; thence S75°18'36"W, a distance of 536.75 feet to the easterly side of County Highway #201; thence continuing along County Highway #201 marked by concrete monuments at all angle point the following 7 courses and distances: (1) N76°13'21"W, a distance of 301.67 feet; (2) N63°07'21"W, a distance of 648.15 feet; (3) N49°16'21"W, a distance of 244.51 feet; (4) N41°34'21"W, a distance of 273.19 feet; (5) N30°45'21"W, a distance of 135.55 feet; (6) N31°33'21"W, a distance of 132.80 feet; (7) N16°09'21"W, a distance of 447.43 feet to

RESERVING to the United States of America, its successors and assigns, a permanent easement for joint use with Town of Guilderland Urban Renewal Agency, its successors and assigns, of the existing railroad tracks, together with an easement for the installation, construction, maintenance, replacement, or relocation and patrol of such facilities, in, on, over, and through two strips of

BEGINNING at a point on the center line of tracks of GSA PMDS Depot where it joins the east bound main line of the N.Y.C.R.R. and runs: thence southwesterly on the arc of a circle curving to the right, having a central angle of 6° and 5', radius of 608.60 feet for an arc distance of 64.61 feet; thence S8°08'E, a distance of 53.28 feet; thence on the arc of a circle curving to the left having a central angle of 1° 3' a radius of 2,223.94 feet for an arc distance of 40.11 feet; thence S9°11'E, a distance of 171.83 feet; thence on the arc of a County Route #201 (Depot Road) thence N45°43'00"W along said roadway a distance of 113.27 feet to a concrete monument, circle curving to the right having a central angle of 1°51', a radius of 1,349.14 feet for an arc distance of 39.24 feet; thence S7°20'E, a thence N63°21'00"W continuing along the northwesterly line of said road a distance of 640.46 feet to the point and place of distance of 36.27 feet; thence on the arc of a circle curving to the left, having a central angle of 6°53', a radius of 463.07 feet for an arc beginning. distance of 55.62 feet; thence S14°13'E, a distance of 74.60 feet; thence on the arc or a circle curving to the right, having a central angle of 6°58', a radius of 465.41 feet for an arc distance of 56.72 feet; thence S7°13'E, a distance of 45.49 feet; thence on the arc of a

> ALSO EXCEPTING AND RESERVING THEREFROM All that parcel of land situated in the Town of Guilderland, County of Albany. State of New York as follows:

distance of 83.01 feet to the point and place of beginning.

Depot Voorheesville Area.

Beginning at a point in the easterly right of way line of County Route 201 with its intersection with the division line between the lands now or formerly of the United States of America on the South and the lands now or formerly of Northeastern Industrial Park, Inc. on the North, thence from said point of beginning along said easterly highway right of way line the following three (3) courses; (1) North 16 degrees 17 minutes 20 seconds West, 90.02 feet, (2) North 78 degrees 55 minutes 50 seconds East, 1.0 feet, (3) North 00 degrees 11 minutes 50 seconds East, 675.42 feet to a point; thence through the lands of said Northeastern

thence S14°13'E, for a distance of 3,215.54 feet; thence on the arc of a circle curving to the left, having a central angle of 2°50',

a radius of 4,014.15 feet, for an arc distance of 198.49 feet; thence S17°03'E, a distance of 291.54 feet; thence on the arc of a circle curving to the left, having a central angle of 7°24', a radius of 498.22 feet for an arc distance of 64.34 feet; thence

S24°27'E, a distance of 40.40 feet; thence on the arc of a circle curving to the right, having a central angle of 7°24', a radius of

480.28 feet for an arc distance of 62.02 feet; thence S17°03'E, a distance of 49.14 feet; thence on the arc of a circle curving to

the left, having central angle of 7° and 24', a radius of 474.71 feet for an arc distance of 61.30 feet; thence S17°03'E, a distance

of 1,554.40 feet; thence on the arc of a circle curving to the left, having a central angle of 15°30', a radius of 1,909.61 feet for an

arc distance of 516.58 feet; thence S32°33'E, a distance of 223.83 feet to a point of intersection of the central line of tracks

traveling from said point of intersection in a northwesterly direction; thence S32°33'E, a distance of 1,444.16 feet to the end of

the tracks. All the above courses herein mentioned are along the center line of the tracks used by the GSA PMDS Depot,

BEGINNING at a point on the center line of the tracks at the point of intersection of said center line of said tracks as above

mentioned and running thence on the arc of a circle curving to the left, having a central angle of 42°, a radius of 611.39 feet for

an arc distance of 455.63 feet; thence N75°15" W. a distance of 24.56 feet; thence on the arc of a circle curving to the left.

having a central angle of 14°59', a radius of 463.99 feet for an arc distance of 121.33 feet; thence S89°46'W, a distance of

77.05 feet; thence the arc of a circle, curving to the left having a central angle of 6°2', a radius of 618.97 feet for an arc distance

of 65.18 feet; thence S83°44'W, a distance of 73.74 feet; thence on the arc of a circle curving to the right having a central angle

of 6°9', a radius of 1,680.04 feet for an arc distance of 180.31 feet; thence S89°53'W, a distance of 1,407.16 feet; thence on an

arc of a circle curving to the left, having a central angle of 47°02', a radius of 401.16 feet for an arc distance of 329.30 feet to

the easterly line of a 35 acre parcel to be deeded by GSA PMDS Depot Voorheesville Area, said last mentioned point being at a

point near Gate 13. All of the above courses herein mentioned are along the center line of the tracks in use by the GSA PMDS

THE ABOVE excluded parcel and two strips of land are shown on a survey entitled "Survey and Map of Lands Leased to

Northeastern Industrial Park, Inc.", showing buildings, easements and exceptions prepared by Richard Danskin, P.C., dated

ALSO, EXCEPTING AND RESERVING therefrom, all that tract or parcel of land situate in the Town of Guilderland, County of

Albany, and State of New York and being located at or near Guilderland Center, New York, and more particularly described as

BEGINNING at the northwest corner of the herein described parcel, said point being S18°24'11"E, a distance of 885.65 feet

from the northeast corner of lands leased to Central School District No. 2 (Town of Guilderland, Bethlehem and New Scotland),

by the Urban Renewal Agency, said course making an interior angle of 45°48' with the easterly boundary of the aforementioned

lands of Central School District No. 2; thence through lands of the Urban Renewal Agency for the following 12 courses and

distances: (1) N87°48'26"E, a distance of 252.77 feet to a point; (2) N80°53'51"E, a distance of 105.69 feet to a point; (3)

S61°51'22"E. a distance of 175.63 feet to a point; (4) S23°37'56"E, a distance of 264.35 feet to a point; (5) S04°18'20"E, a

distance of 181.43 feet to a point; (6) S48°07'12"W, a distance of 170.27 feet to a point; (7) N71°38'14"W, a distance of 184.88

feet to a point; (8) S70°34'30"W, a distance of 233.20 feet to a point; (9) N67°29'04"W, a distance of 125.08 feet to a point; (10)

N01°54'14"W, a distance of 341.96 feet to a point; (11) N02°17'36"W, a distance of 164.04 feet to a point; (12) N20°43'14"E, a

ALSO EXCEPTING AND RESERVING therefrom, All that piece or parcel of land, situate, lying and being in the Town of

Guilderland, County of Albany and State of New York, bounded and described as follows: Beginning at a point on the

northwesterly line of Albany County Route #201 (Depot Road) as it is intersected by the southerly line of Lands of the United

States Government and runs thence N85°22'00"E along said southerly line a distance of 716.48 feet; thence S1°37'00"E along

a reserved 60 foot roadway a distance of 419.70 feet, thence S86°19'00"W a distance of 72.63 feet to a point on the Albany

THE CLOSING INSTRUMENT ONLY - NOT INSURED: Containing 353,260 square feet of 8.1 acres of land, more or less, and

being shown as a parcel described upon a survey of the lands to be acquired by the Town of Guilderland from the Town of

Guilderland Urban Renewal Agency, Scale - 1 inch equals 100 feet, dated October 18, 1971, map and survey by Selee and

Excepting from the above those parcels conveyed to American Real Estate Investment, LP by deed recorded 5/14/98 in Liber

Carpenter, Land Surveyors and Planners, One Alton Road, Albany, New York and designated as Sheet 2 of 4.

August 15, 1980, and revised October 2, 1980, last revised January 26, 1998.

Industrial Park, Inc., the following four (4) courses: (1) North 80 degrees 03 minutes 50 seconds East, 76.19 feet, (2) South 00 degrees 11 minutes 50 seconds West, 513.82 feet, (3) South 89 degrees 48 minutes 12 seconds East, 95.00 feet, (4) South 00 degrees 11 minutes 55 seconds West, 236.26 feet to a point in the first mentioned division line; thence South 80 degrees 20 minutes 39 seconds West, 147.61 feet along said division line to the point of beginning

EXCEPTING AND RESERVING THEREFROM All that certain plot, piece or parcel of land, situate, lying and being in the Town of Guilderland, County of Albany and State of New York, with the buildings and improvements thereon erected bounded and

Beginning at a point in the division line between the lands now or formerly of the Central School District No. 2, Towns of Guilderland, Bethlehem and New Scotland on the Northwest and lands now or formerly of the United States of America (Schenectady General Depot-Voorheesville Area) on the Southeast, said point being 148.76 feet distant southwesterly measured along said division line from the most northerly corner of lands of the United States of America as the same is shown on a map entitled, "Schenectady General Depot-Voorheesville Area-Survey Utilities, Boundary Railroads-Boundary and Property Line", dated March 27, 1952, and made by E.W. Boutelle and Son; thence southwesterly along said division line 1,000.00 feet to a point; thence southeasterly with an interior angle on 90 deg. and through the lands now or formerly of the United States of America, a distance of 252.59 feet to a point; thence northeasterly with an interior angle of 111 deg. 14'44" continuing through lands now or formerly of the United States of America, a distance of 296.41 feet to a point; thence northeasterly with an interior angle of 158 deg. 45'16" along a line parallel to the aforementioned division line and continuing through the lands now or formerly of the United States of America for a distance of 613.67 feet to a point; thence northwesterly with the interior angle of 107 deg. 00'00" and continuing through the lands now or formerly of the United States of America, a distance of 376.45 feet to the point of beginning, the last mentioned course making an interior angle of 73 deg. 00'00" with the

# "ENVIRONMENTAL EASEMENT"

Portion Of The Lands Of Northeastern IP Holdings, Inc.

> Town Of Guilderland - Albany County **State Of New York**

> > Surveyor's Certification

TO: New York State Department Of Environmental Conservation

THE UNDERSIGNED HEREBY CERTIFIES THAT THIS IS

AN ACCURATE MAP OF AN ACTUAL FIELD SURVEY

January 2, 2013

THAT BOTH MAP AND SURVEY ARE CORRECT.

Druce W. Snede Bruce W. Snyder Registered Land Surveyor No.050195 In The State Of New York Date Of Survey: January 2, 2013

Project Number: 2013.453.001

Date Of Last Revision: March 31, 2014




# APPENDIX E

Record Drawing As-Built – Area of Concern 1 – Landfill Cap/Soil Cover

# RECORD DRAWING AS-BUILT - H2H ASSOCIATES, LLC. CONTRACT NO. W912WJ-12-C-0006 USACE - NORTHEAST INDUSTRIAL PARK AREA OF CONCERN 1 - LANDFILL CAP/SOIL COVER GUILDERLAND, NEW YORK

# NORTHEAST INDUSTRIAL PARK



	DR	AWING INDEX
SHEET	DWG	DESCRIPTION
1	T-1	TITLE SHEET
2	C-1	SITE PLAN
3	C-2	FINAL COVER PLAN - LANDFILL CAP
4	C-3	FINAL COVER PLAN - SOIL COVER
5	C-4	GEOMEMBRANE LAYOUT - LANDFILL CAP
6	D-1	LANDFILL CAP DETAILS
7	D-2	SOIL COVER DETAILS
8	D-3	MISC. DETAILS
9	D-4	EROSION AND SEDIMENT CONTROL DETAILS

# LOCATION MAP





			,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,			THE PARTY OF THE P
APP	DATE	DESCRIPTION	MARK	APPR.	DATE APPR. MARK	DESCRIPTION
					01-23-2014	ADDED SHEET C-4, ADDED WELL TABLE TO C1 01-23-2014
						AS-BUILT RECORD DRAWINGS

SOLICITATION NO: W912WJ-12-R-0005 CONTRACT NO: W912WJ-12-C-0006 : FILE NUMBER: FILE NO	MPS  DWN BY:  CKD BY:  MVF  SUBMITTED BY:  AGH  PLOT SCALE:  NTS  O1-23-2014  SIZE:  FILE NAME:	SUBMITTED BY: AGH PLOT SCALE: PI SIZE: FILE
	MPS D BY: E: PLOT DATE: 01-23-2014 FILE NAME:	
CONTRACT NO.: W912WJ-12-C-0006	BY:	SUBMITTED AGH
SOLICITATION NO.: W912WJ-12-R-0005	CKD BY: MPS	DWN BY: MVF
01-23-2014		MPS

U.S. ARMY CORPS OF ENGINEERS MPS

NEW ENGLAND DISTRICT

CONCORD, MASSACHUSETTS

SUBMIT


AGH

PLOT SI


NTS


NORTHEAST INDUSTRIAL PARK
AREA OF CONCERN 1
LANDFILL CAP/SOIL COVER
TITLE SHEET

SHEET IDENTIFICATION T-1




IDENTIFICATION






P=31 P17 P=30 P11 P1 P9 , PARQ P10 P15 | P14 | P13 | P16 P18 P27






# **DETAIL B**




DOUBLE FUSION WELD N.T.S.


# DETAIL C



EXTRUSION FILLET WELD N.T.S.



**BOOT DETAIL** 



S. ARMY CORPS	U.S. ARMY CORPS OF ENGINEERS	DESIGNED BY:	ву:	DATE: 01-23-201
NEW ENGLAND DISTRICT	ND DISTRICT	DWN BY: MVF	CKD BY: MPS	SOLICIT/ W912WJ-
		SUBMITTED BY:	BY:	CONTRA
		AGH		W912WJ-
	3	PLOT SCAL	PLOT SCALE: PLOT DATE:	FILE NUN
J リ に	の は の の の の の の の の の の の の の	1"=60'-0"	01-23-2014	FILE_NO
Hydroteol.og.C. rng	NY www.ebalezorky.com	SIZE:	FILE NAME:	
		ANSI_D	01-23-2014_AB_NEIP_AOC_1_	IP_AOC_1_

NORTHEAST INDUSTRIAL PARK
AREA OF CONCERN 1
LANDFILL CAP/SOIL COVER
GEOMEMBRANE LAYOUT - LANDFILL CAP

SHEET IDENTIFICATION C-4

LEGEND:

PANEL IDENTIFICATION NUMBER


——— APPROXIMATE LOCATION OF LINER LIMIT


REPAIR LOCATION


DESTRUCTIVE SEAM SAMPLE LOCATION


# NOTES:


- 1. GEOMEMBRANE MATERIAL: SOLMAX TEXTURED 40-MIL LLDPE.
- 2. TYPICAL PANEL WIDTH IS 22.3'.
- 3. TYPICAL PANEL OVERLAP FOR DOUBLE FUSION WELD IS 5".
- 4. PRIMARY METHOD OF PANEL SEAMING FOR REPAIRS AND PENETRATIONS: EXTRUSION FILLET WELD, DETAIL C.
- 5. PIPE PENETRATIONS BUILT IN ACCORDANCE WITH CONTRACT DRAWINGS, SEE BOOT DETAIL.














SHEET IDENTIFICATION

SILT FENCE

**END DETAIL** 

# APPENDIX F

Responsibilities of Owner and Remedial Party

### **RESPONSIBILITIES of**

### **OWNER and REMEDIAL PARTY**

The responsibilities for implementing the Site Management Plan ("SMP") for AOCs 1 and 7, Northeastern Industrial Park, Guilderland, New York site (the "site"), NYSDEC site # 401009, are divided between the site owner(s) and a Remedial Party, as defined below. The owner(s) is/are currently listed as:

Northeast Industrial Park (the "owner").

Solely for the purposes of this document and based upon the facts related to a particular site, Remedial Party (RP) is designated as:

The United States Army Corps of Engineers (USACE), New York District, 26 Federal Plaza, New York, NY 10278

Nothing on this page shall supersede the provisions of an Environmental Easement, Consent Order, Consent Decree, agreement, or other legally binding document that affects rights and obligations relating to the site.

### **Site Owner's Responsibilities:**

- 1) The owner shall follow the provisions of the SMP as they relate to future construction and excavation at the site.
- 2) In accordance with a periodic time frame determined by the NYSDEC, the owner shall periodically certify, in writing, that all Institutional Controls set forth in an Environmental Easement remain in place and continue to be complied with. The owner shall provide a written certification to the RP, upon the RP's request, in order to allow the RP to include the certification in the site's Periodic Review Report (PRR) certification to the NYSDEC.
- 3) In the event the site is delisted, the owner remains bound by the Environmental Easement and shall submit, upon request by the NYSDEC, a written certification that the Environmental Easement is still in place and has been complied with.
- 4) The owner shall grant access to the site to the RP and the NYSDEC and its agents for the purposes of performing activities required under the SMP and assuring compliance with the SMP.
- 5) The owner is responsible for assuring the security of the remedial components located on its property to the best of its ability. In the event that damage to the remedial components or vandalism is evident, the owner shall notify the site's RP and NYSDEC in accordance with the timeframes indicated in Section 6.2 Notifications.
- 6) In the event some action or inaction by the owner adversely impacts the site, the owner must notify the site's RP and the NYSDEC in accordance with the time frame indicated in Section 6.2 Notifications and coordinate the performance of necessary corrective actions with the RP.
- 7) The owner must notify the RP and the NYSDEC of any change in ownership of the site property (identifying the tax map numbers in any correspondence) and provide contact information for the new owner of the site property. 6 NYCRR Part contains notification requirements applicable to any construction or activity changes and changes in ownership. Among the notification requirements is the following: Sixty days prior written notification must be made to the NYSDEC. Notification is to be submitted to the

NYSDEC Division of Environmental Remediation's Site Control Section. Notification requirements for a change in use are detailed in Section 6.2 of the SMP. A 60-Day Advance Notification Form and Instructions are found at http://www.dec.ny.gov/chemical/76250.html.

8) Coordination between the owner and the RP will be conducted to maintain fences, access gates and conduct annual mowing on behalf of the RP. The RP remains ultimately responsible for maintaining the engineering controls, subject to the availability of funds.

### **Remedial Party Responsibilities**

- 1) The RP must follow the SMP provisions regarding any construction and/or excavation it undertakes at the site.
- 2) The RP shall report to the NYSDEC all activities required for remediation, operation, maintenance, monitoring, and reporting. Such reporting includes, but is not limited to, periodic review reports and certifications, electronic data deliverables, corrective action work plans and reports, and updated SMPs.
- 3) Before accessing the site property to undertake a specific activity, the RP shall provide the owner advance notification that shall include an explanation of the work expected to be completed. The RP shall provide to (i) the owner, upon the owner's request, (ii) the NYSDEC, and (iii) other entities, if required by the SMP, a copy of any data generated during the site visit and/or any final report produced.
- 4) If the NYSDEC determines that an update of the SMP is necessary, the RP shall update the SMP and provide the update to the NYSDEC. Within 5 business days after NYSDEC receipt of the updated SMP, the RP shall submit a copy of the updated SMP to the owner(s).
- 5) The RP shall notify the NYSDEC and the owner of any changes in RP ownership and/or control and of any changes in the party/entity responsible for the operation, maintenance, and monitoring of and reporting with respect to any remedial system (Engineering Controls). The RP shall provide contact information for the new party/entity. Such activity constitutes a Change of Use pursuant to 375-1.11(d) and requires 60-days prior notice to the NYSDEC. A 60-Day Advance Notification Form and Instructions are found at http://www.dec.ny.gov/chemical/76250.html.
- 6) The RP shall notify the NYSDEC of any damage to or modification of the systems as required under Section 6.2 Notifications of the SMP.
- 7) Prior to a change in use that impacts the remedial system or requirements and/or responsibilities for implementing the SMP, the RP shall submit an amended SMP to the NYSDEC.
- 8) Any change in use, change in ownership, change in site classification (*e.g.*, delisting), reduction or expansion of remediation, and other significant changes related to the site may result in a change in responsibilities and, therefore, necessitate an update to the SMP and/or updated legal documents. The RP shall contact the Department to discuss the need to update such documents.

Change in RP control and/or site ownership does not affect the RP's responsibilities under this SMP.

Future site owners and their successors and assigns are required to carry out the activities set forth above. USACE will carry out their responsibilities under this SMP, subject to availability of funds.