

ENGINEERING INVESTIGATIONS AT
INACTIVE HAZARDOUS WASTE SITES
IN THE STATE OF NEW YORK
PHASE II INVESTIGATION

QUEENSBURY LANDFILL
SITE NO. 557005
QUEENSBURY (T), WARREN (C)

VOLUME II
APPENDICES A - J

APRIL 1992

Performed Under
NYSDEC CONTRACT NO. D002340
NYSDEC WORK ASSIGNMENT NO. D002340-3

By
URS CONSULTANTS, INC.
282 DELAWARE AVENUE
BUFFALO, NEW YORK 14202

For
DIVISION OF HAZARDOUS WASTE REMEDIATION
NEW YORK STATE DEPARTMENT OF ENVIRONMENTAL CONSERVATION

LIST OF APPENDICES

<u>Appendix</u>	<u>Description</u>
A	Geophysical Survey Report
B	Soil Boring Logs
C	Geotechnical Soil Testing Results
D	Monitoring Well Construction Details
E	Well Development/Purge Logs
F	Hydraulic Conductivity Testing Results
G	Analytical Testing Results from Previous Investigations
Ga	Dunn Geoscience - NYSDEC RCRA Open Dump Inventory Groundwater Quality Evaluation Analytical Testing Results
Gb	Town of Queensbury Quarterly and Annual Testing Analytical Results
Gc	NYSDEC Sampling of Inactive Hazardous Waste Site Analytical Testing Results
Gd	NYDOH Homeowner Well Groundwater Samples Analytical Testing Results (10/25/90 and 1/28/91)
Ge	NYSDEC Leachate Sampling Analytical Results (1/16/91)
H	Analytical Sample Descriptions
I	Phase II Analytical Testing Results
J	Additions/Changes to Registry of Inactive Hazardous Waste Disposal Sites

APPENDIX A
GEOPHYSICAL SURVEY REPORT
RESULTS OF QUEENSBURY LANDFILL



Weston Geophysical CORPORATION

August 23, 1990

Mr. James Lanzo
Ms. Phyllis Retke
URS Consultants, Inc.
570 Delaware Avenue
Buffalo, New York 14202-1207

Subject: Results from Geophysical Surveys at
Numerous Well Locations
Halfmoon, Queensbury, and Saratoga Springs Landfills

Dear Mr. Lanzo and Ms. Retke:

In accordance with your authorization, Weston Geophysical conducted EM-31 and magnetometry surveys during the weeks of July 16 and 23, 1990 at 17 proposed monitoring well locations at the Halfmoon, Queensbury, and Saratoga Springs landfills, New York. The purpose of this investigation was to locate possible buried objects which might impede drilling and installation of monitoring wells. The methodologies employed and results of investigations are summarized below.

LOCATION AND SURVEY CONTROL

Geophysical data were typically acquired within a 20 by 20-foot grid, with the proposed well location centered in the middle of the grid (i.e. Line 0+10, Station 0+10). EM-31 terrain conductivity or magnetometry data were collected along south-north traverses spaced 2 feet apart; data were acquired digitally at 2 foot increments.

METHODS OF INVESTIGATION

The Geonics EM-31D terrain conductivity meter measures the electrical conductivity of earth materials to depths of 15 to 20 feet. The technique utilizes the principal of electromagnetic induction to measure the strength of a secondary magnetic field generated in the presence of a conductor, such as a metallic object. "Negative" conductivity values, or "polarity reversals" may be observed in the presence of metallic objects, making them readily detectable by the EM-31. Data are recorded digitally and transferred to a portable computer in the field for immediate evaluation. An expanded discussion of the electromagnetic terrain conductivity method may be found in Appendix A.

A total-field proton precession magnetometer was used to obtain magnetic readings at selected well locations. This instrument measures the earth's total magnetic field at any one location. Ferrous metallic objects (i.e. iron or steel) are readily detectable because they cause perturbations of the earth's ambient magnetic field. Because the methodology measures the total magnetic field, it is also susceptible to magnetic and electrical (i.e. lightning) storms. Appendix B discusses the magnetometry method in greater detail.

Mr. James Lanzo
Ms. Phyllis Retke

August 23, 1990
Page Two

RESULTS

Halfmoon Landfill

Magnetometry data were acquired at wells MW-1 through MW-3; because of thunderstorm activity (which influences magnetic data), an EM-31 terrain conductivity meter was used to evaluate wells MW-4 through MW-6. Both magnetic and conductivity data indicate all six wells are in metal-free areas, although MW-1 is in proximity to a metal fence which influenced the data. Table 1 summarizes these results.

Queensbury Landfill

The EM-31 terrain conductivity meter was used to evaluate all five wells at the Queensbury Landfill. Conductivity values were generally low (less than 5 millimhos per meter (mmho/m)) in areas "upgradient" (i.e. MW-1 and MW-5), while values exceeded 30 mmhos/m in "down gradient" wells. Conductivity variations noted could be due to changes in lithology, moisture content, or other non-metallic sources; anomalies associated with buried metallic objects were not detected at any of the five wells, as summarized in Table 1.


Saratoga Springs Landfill

Conductivity data were also acquired at all six wells at Saratoga Springs Landfill. High conductivities observed at well SC-6 are believed to be indicative of a groundwater plume, as the well is situated at the toe of the landfill and is surrounded by swamp and open water on all sides. Anomalies indicative of buried metal objects were not detected at Wells SC-1, SC-2, SC-4, and SC-6. Well SC-5 is also believed to be free of buried metal objects, although conductivity data appeared slightly anomalous because of the well's proximity to overhead powerlines. Some small metal objects (scrap metal) may be located in the vicinity of Well SC-3; we recommend that this well be relocated 5 feet to the east. Table 1 summarizes these results.


We will be pleased to provide any additional information that you may require. We appreciate providing our geophysical services to URS Consultants and welcome any future opportunities to serve you again.

Sincerely,

Weston Geophysical Corporation



Doria L. Kutrubes
Geophysicist



Mark Blackey
Manager, Geophysical Services

TABLE 1

SUMMARY OF GEOPHYSICAL WELL-CLEARING SURVEYS
HALFMOON, QUEENSBURY, AND SARATOGA SPRINGS LANDFILLS

LOCATION	WELL	SURVEY METHOD	COMMENTS
Halfmoon	SC-1	MAG	Ok- fence
Halfmoon	SC-2	MAG	Ok
Halfmoon	SC-3	MAG	Ok
Halfmoon	SC-4	EM-31	Ok
Halfmoon	SC-5	EM-31	Ok
Halfmoon	SC-6	EM-31	Ok
Queensbury	MW-1	EM-31	Ok
Queensbury	MW-2	EM-31	Ok
Queensbury	MW-3	EM-31	Ok
Queensbury	MW-4	EM-31	Ok
Queensbury	MW-5	EM-31	Ok
Saratoga Springs	SC-1	EM-31	Ok
Saratoga Springs	SC-2	EM-31	Ok
Saratoga Springs	SC-3	EM-31	Move 5' E
Saratoga Springs	SC-4	EM-31	Ok
Saratoga Springs	SC-5	EM-31	Ok- power line.
Saratoga Springs	SC-6	EM-31	Ok

APPENDIX A

ELECTROMAGNETIC TERRAIN CONDUCTIVITY
METHOD OF INVESTIGATION

GENERAL CONSIDERATIONS

The electromagnetic terrain conductivity [EM] survey is a method of obtaining subsurface information through "remote" inductive electric measurements made at the surface of the earth. Although limited in application, the EM method has significant advantage in speed and definition for certain problems. The parameter measured with this technique is the apparent conductivity of the subsurface. The conductivity meter consists of receiver coil and a separate transmitter coil which induces an electrical source field [a circular eddy current loop] in the earth [Figure 1]. Each current loop generates a magnetic field proportional to the value of the current flowing within the loop. Part of the magnetic field from each current loop is intercepted by the receiver coil and converted to an output voltage which is linearly related to terrain conductivity. EM instrument readings are in millimhos per meter.

Geologic materials can be characterized by their electrical characteristics; lateral variations in conductivity values generally indicate a change in subsurface conditions. The relative conductivity of earth materials is particularly sensitive to water content and dissolved salts or ions. Accordingly, dry sands and gravels, and massive rock formations have low conductivity values; conversely, most clays and materials with a high ion content have high conductivity values.

FIELD PROCEDURE FOR DATA ACQUISITION

Weston Geophysical generally uses two common terrain conductivity meters: the Geonics EM-31 and the EM-34-3. The EM-31 has a fixed intercoil spacing of 3.7 meters and an effective depth of penetration of approximately 6 meters. The EM-34-3 has two coils which can be separated by 10, 20, or 40 meters and can be oriented in either the horizontal or vertical dipole modes. Intercoil separations increase the effective depth of investigation as shown below.

<u>Intercoil Spacing</u> [meters]	<u>Depth of Investigation [meters]</u>	
	Horizontal Dipoles	Vertical Dipoles
10	7.5	15
20	15	30
40	30	60


The coil orientation [horizontal or vertical] allows the EM-34-3 to respond to materials of different depths.

Conductivity measurements obtained with the EM-31 and/or the EM-34-3 can be obtained at any spacing along a survey line. EM-31 readings have the added flexibility of being recorded on a continuous chart recorder providing continuous data along a survey line.

DATA INTERPRETATION

EM data interpretation is generally subjective, that is measured EM values are contoured or profiled to identify high or low conductivity locations. Conductivity values obtained by an EM survey are relative values and depth estimates to conductive surface or bodies are best accomplished with an on-site calibration.

The EM-31 and EM-34-3 measure terrain conductivity in millimhos/meter. These values can be converted to resistivity [ohm/meters] for comparison with resistivity results by dividing the conductivity values into 1000.



Horizontal coplanar configuration (vertical dipole mode)

APPENDIX B

**MAGNETOMETER (TOTAL FIELD) MEASUREMENTS
FOR DETECTION OF BURIED METAL OBJECTS
METHOD OF INVESTIGATION**

INTRODUCTION

The magnetic method is a versatile, relatively inexpensive, geophysical exploration technique. Aeromagnetic surveys and deep water marine studies are commonly used as a reconnaissance tool for tracing large-scale geologic structure. Land and coastal water marine data are more useful in tracing smaller, more localized geologic structures, such as mineral and ore deposits. Land and marine surveys yield more detail and higher resolution, since the measurements are taken closer to the anomaly source. Land and shallow water magnetic data is commonly used to locate larger buried, man-made objects such as pipelines, barrels or other buried metal objects, and smaller objects such as involved in archaeological prospecting.

EARTH MAGNETISM

Magnetics is a "potential field" method. For a given magnetic field, the magnetic force in a given direction is equal to the derivative of the magnetic potential in that direction. The source of the earth's magnetic potential is its own magnetic field and the induction effect this field has on magnetic objects or bodies above and below the surface. The earth's field is a vector quantity having a unique magnitude and direction at every point on the earth's surface. This magnetic field is defined in three dimensions by angular quantities known as declination and inclination. Declination is defined as the angle between geographic north and magnetic north, and inclination is the angle between the direction of the earth's field and the horizontal [Figure 1]. The earth's magnetic field is measured in "gammas" [where 1 gamma = 10^{-5} Oersted]; the total field ranges from about 25,000 gammas near the equator to 70,000 gammas near the poles.

The earth's magnetic field is not completely stable. It undergoes long-term [secular] variations over centuries; small, daily [diurnal] variations [less than 1% of the total field magnitude]; and transient fluctuations called magnetic storms resulting from solar flare phenomena.

The earth's ambient magnetic field is modified locally by both naturally- occurring and man-made magnetic materials. Iron or steel objects act as "local" dipoles, which are generally oriented differently than the earth's external magnetic field.

The iron or steel objects represents a local perturbation in the main earth field. The net field in the vicinity of this perturbation is simply the vector sum of the induced and earth fields. Thus, the induced field is a function of the "susceptibility" of the material, or its ability to act like a magnet.

Remanent magnetization is produced in materials which have been heated above the Curie point allowing magnetic minerals in the material to become aligned with the earth's field before cooling. The remanent field direction is not always parallel to the earth's present field, and can often be completely reversed. The remanent field combines vectorially with the ambient and induced field components. The contribution of the remanent components must be considered in magnetic interpretations.

INSTRUMENTATION

At present, the most widely used magnetometer is the "proton precession" type. This device utilizes the precession of spinning protons of the hydrogen atoms in a sample of fluid [kerosene, alcohol, or water] to measure total magnetic field intensity.

Protons spinning in an atomic nucleus behave like magnetic dipoles, which are aligned [polarized] in a uniform magnetic field. The protons initially aligned themselves parallel to the earth's field. A second, much stronger magnetic field is produced approximately perpendicular to the earth's field by introducing currents through a coil of wire. The protons become temporarily aligned with this stronger secondary field. When this secondary field is removed, the protons tend to realign [precess] themselves parallel to the earth's field direction. The precessing protons will generate a small electric signal in the same coil used to polarize them with a frequency [about 2,000 Hz]



proportional to the total magnetic field intensity but independent of the coil orientation. By measuring the signal frequency, the absolute value of the total earth field intensity can be obtained to a 1 gamma accuracy. The total magnetic field value measured by the proton precession magnetometer is the net vector sum of the ambient earth's field and any local induced and/or remanent perturbations.

A total field proton precession magnetometer can be made portable and does not require orientation or leveling. There are a few limitations associated with the precession system. The precession signal can be severely degraded in the presence of large field gradients [greater than 200 gammas per foot] near 60-cycle A/C power lines. Also, the interpretation of total field data is sometimes more complicated than vertical field data which, however, is more time consuming to take.

FIELD TECHNIQUES

The field operator must avoid or note any sources of high magnetic gradients and alternating currents, such as power lines, buildings, and any large iron or steel objects. Readings are taken at a predetermined interval which depends on the nature of the survey, the accuracy required, and the gradients encountered. Base station readings, if required, are usually made several times a day to check for diurnal variations and magnetic storms.

INTERPRETATION


Lateral variations in susceptibility and/or remanent magnetization in crustal rocks give rise to localized anomalies in the measured total magnetic field intensity. Geologic structural features [faults, contacts, intrusions, etc.] and metal objects will cause magnetic anomalies, which can be interpreted to define the location of the causative source.

After diurnal effects and regional gradients have been removed, magnetic anomalies can be studied in detail with derivative operations and frequency filtering employed to define depth and shape.

Because it is a potential field method, there are a number of possible source configurations for any given magnetic anomaly. There is also an inherent complexity in magnetic dipole behavior. If the various magnetic field parameters [inclination, declination, and susceptibility] are well defined, and some reasonable assumptions can be made regarding the nature of the source, an accurate source model can generally be derived.

Magnetic anomalies can be analyzed both qualitatively and quantitatively. The physical dimensions of an anomaly [slope, wave-length, amplitude, etc.] often reveal enough to draw some general qualitative conclusions regarding the location and depth of the causative source.

Precise interpretation must be done quantitatively and requires prior knowledge of earth and remanent magnetic field parameters. Modeling can be performed by various approximation methods, whereby one reduces the source to a system of poles or dipoles, or assumes it to be one of several simple, geometric forms [vertical prism, horizontal slab, step, etc.]. The magnetic properties for this simplified model can be rather easily defined mathematically. Simple formulas can be derived which relate readily measurable anomaly parameters, such as slope, width, and amplitude ratios, to the general dimensions of the anomaly source, including depth to top, thickness, dip, and width normal to strike. Since these methods involve very limiting geometric assumptions, the results can be treated as good approximations only for very simplified sources.



I = Inclination

D = Declination

H = Horizontal Field Strength

F = Total Magnetic Force

ELEMENTS OF THE EARTH'S MAGNETIC FIELD

APPENDIX B
SOIL BORING LOGS

URS CONSULTANTS, Inc.

TEST BORING LOG

BORING NO. MW-1

PROJECT: QUEENSBURY LANDFILL PHASE II INVESTIGATION

SHEET NO. 1 OF 3

CLIENT: NEW YORK STATE DEPARTMENT OF ENVIRONMENTAL CONSERVATION

JOB NO.: 35231.05

BORING CONTRACTOR: CONSTRUCTION DRILLING SERVICES (CDS)

BORING LOCATION: UPRADIANT

GROUND WATER:

CAS ~~SAMP~~ CORE ~~TUBE~~

GROUND ELEVATION: 482.59 FT.

DATE TIME LEV TYPE TYPE

DATE STARTED: 10-11-90

10/16 11:00AM 157 GRD. DRILLER STAGE DIA

DATE FINISHED: 10-17-90

10/26 12:50PM 160.64 Top of Rise WT

DRILLER: JOHN COYLE, DICK MILLER

11-2 4:10PM 160.68 T.O.P. of Rise FALL

GEOLOGIST: SCOTT SWANSON

11-8 3:40PM 160.74 T.O.P. of Rise

REVIEWED BY:

* POCKET PENETROMETER READING

DEPTH FT	STRATA	SAMPLE				DESCRIPTION				REMARKS
		NO.	TYPE	BLOWS PER 5"	RECOVERY RCD %	COLOR	CONSISTENCY HARDNESS	MATERIAL DESCRIPTION	SCALE VALUE	
0								10-11-90 2:00PM COMMENCE DRILLING		
10								COBBLES		DUSTY DRILLING
20						GRAY WHITE		GRAVELS, ANGULAR GROUND UP COBBLES 3/16" - 1/2"		
30						GRAY		BOULDER AT 30'		VERY DUSTY DISCHARGE
40						GRAY Brown		SANDY GRAVELS @ 35' fine - coarse sand brown COBBLES		
50										
60										10-12-90 START @ 61'
70						Brown		SAND @ 67' coarse - fine	SW	MOIST

COMMENTS: TUBEX & AIR ROTARY DRILLING METHOD - SAMPLES OR CUTTINGS DESCRIBED AS DISCHARGED BY AIR AT SURFACE
TUBEX ADVANCES CASING WHILE DRILLING

PROJECT NO.

35231.05

BORING NO.

MW-1

URS CONSULTANTS, Inc.

TEST BORING LOG
BORING NO.

MW-1

PROJECT: QUEENSBURY LANDFILL PHASE II

SHEET NO. 2 OF 3

CLIENT: NEW YORK STATE DEPT. OF ENVIRONMENTAL

JOB NO.: 35231.05

DEPTH FT	STRATA	SAMPLE				CONSERVATION DESCRIPTION				REMARKS
		NO.	TYPE	BLOWS PER 6"	RECOVERY RQD %	COLOR	CONSISTENCY HARDNESS	MATERIAL DESCRIPTION	CLASS USCS	
	0.0	NO SPLIT SPOOLS				BRN		SAND AND COBBLES		
	0.0					WH. GRAY				
80						BRN.		SAND fine-med. @ 76'	SP	MOIST LESS DUST IN DISCHARGE
90						BRN.		SANDY GRAVELS @ 86' L COBBLES		
100						MULTI- COLOR		COARSE SANDS, SOME FINE GRAVELS GRAVEL SIZE 97' LARGER MULTI-COLOR GRAVELS	94' SP	DUST INCREASE DRY COBBLE ZONE
110						BRN.		@ 110' fine moist sand 2' of fine becoming coarser	SP	
120						AT 112' CASING NO LONGER BEING ADVANCED - JOINT SNAPPED DOWN HOLE, PULLED ALL CASING & DRILL STRING AND REDRILL ON 10-15-90				
						@ 116' DUSTY AGAIN, FINE GRAVELS				
130								SANDY GRAVELS 1/4" - 3/8" ROUNDED	GP	SLIGHTLY MOIST
140										
150										

COMMENTS TUBEX & AIR ROTARY DRILLING METHOD - TRUCK
MOUNTED TH-60 FINGERSOLL-RAND RIGPROJECT NO.
BORING NO.35231.05
MW-1

URS CONSULTANTS, Inc.

TEST BORING LOG

BORING NO.

MW-1

PROJECT: QUEESBURY LAND FILL PHASE II INVESTIGATION

SHEET NO. 3 OF 3

CLIENT: NYSDEC

JOB NO.: 35231.05

DEPTH FT	STRATA	SAMPLE				DESCRIPTION				REMARKS
		NO.	TYPE	BLOWS PER 6"	RECOVERY RQD %	COLOR	CONSISTENCY HARDNESS	MATERIAL DESCRIPTION	CLASS USCS	
160						BN.		SANDY GRAVELS	GP	
170						BRN.		V. COARSE SAND	SP	WATER MIST OF WATER STEAM AT DISCHARGE TOOK GRAIN SIZE SAMPLE
180								- 171' DRILL AHEAD ON 10-16-90		
								TOTAL DEPTH 180' DRILLER MEASURES WATER @ 157' GRD.		

COMMENTS

TUBEX & AIR ROTARY DRILLING METHOD

PROJECT NO.

BORING NO.

35231.05

MW-1

URS CONSULTANTS, Inc.

TEST BORING LOG

BORING NO.

MW-2

PROJECT: QUEENSBURY MANDELL PHASE II INVESTIGATION

SHEET NO. 1 OF 2

CLIENT: NEW YORK STATE DEPARTMENT OF ENVIRONMENTAL CONSERVATION

JOB NO.: 35231.05

BORING CONTRACTOR: CONSTRUCTION DRILLING SERVICES (CDS)

BORING LOCATION: DOWNGRADE OF CIBA-GEIGY FACILITY

GROUND WATER:

CAS. SAMP. CORE TUBE

GROUND ELEVATION: 437.22

DATE TIME LEV TYPE TYPE

DATE STARTED: 10-30-90

10-31 11:44AM 115.32 GROUND DIA

DATE FINISHED: 11-1-90

10-31 1:00 113.5 GROUND WT

DRILLER: JOHN COYLE

11-1 10:44AM 113.6 GROUND FALL

GEOLOGIST: SCOTT SWANSON

11-2 3:30PM 116.08 Top of Riser

* POCKET PENETROMETER READINGS

REVIEWED BY:

DEPTH FT	STRATA	SAMPLE				DESCRIPTION				REMARKS
		NO.	TYPE	BLOWS PER 5"	RECOVERY RCD %	COLOR	CONSISTENCY HARDNESS	MATERIAL DESCRIPTION	TEST USED	
0						LT. B2N		MED - CS SAND SOME 1/4" PEBBLES THROUGHOUT	SP	8:37AM COMMENCE DRILLING DRY - SL. DAMP.
10										
20										
30										
40										
50						BROWN		FINE - MED SAND NO PEBBLES	SP	MOIST, NO DUST
60						GRAY- BRN		@62' MED-CS SAND GRAY COLOR 62-67' yellow-brn fn-Md Sand		HELPER S-MEL-S ODCS, H ₂ O SEWAGE & CUTTINGS
70						GRAY yellow-Brown		fine-Md Sand, some pebbles	SP	DUSTY DRY MOIST

COMMENTS

TUBEX & AIR ROTARY DRILLING METHOD
RIG: TRUCK-MOUNTED INgersoll-RAND TH-60

PROJECT NO.

35231.05

BORING NO.

MW-2

MW-2

SHEET NO. 2 OF 2

JOB NO. : 36231.05

MW'-2

URS CONSULTANTS, Inc.

TEST BORING LOG

BORING NO.

MW-3 A

PROJECT: QUEENSBURY MANDELL PHASE II INVESTIGATION

SHEET NO. 1 OF 3

CLIENT: NEW YORK STATE DEPARTMENT OF ENVIRONMENTAL CONSERVATION

JOB NO.: 35231.05

BORING CONTRACTOR: CONSTRUCTION DRILLING SERVICES (CDS)

BORING LOCATION:

GROUND WATER:

CAS.

SAMP

CORE

TUBE

GROUND ELEVATION: NOT MEASURED

DATE

TIME

LEV

TYPE

TYPE

DATE STARTED: 10-17-90

DATE FINISHED: 10-22-90

DRILLER: JOHN COYLE

GEOLOGIST: SCOTT SWANSON

REVIEWED BY:

DEPTH FT	STRATA	SAMPLE				DESCRIPTION				REMARKS
		NO.	TYPE	BLOWS PER 5'	RECOVERY %	COLOR	CONSISTENCY HARDNESS	MATERIAL DESCRIPTION	CLASS	
10	0.0					LT. GRAY		1ST ATTEMPT HIT FILL - BAD ODORS ABANDONED MOVED LOCATION 2nd Attempt COBBLES - ANGULAR GRAVELS 1/2" - 1"		GARBAGE @ 3 1/2'
20	0.0					BRN. GRAY		AT 16' V. COARSE SANDY GRAVELS ANGULAR GRAVELS 1/4" - 1/2"	GP	DRY DUSTY DISCHARGE
30	0.0							AT 31.5' SAND AND GS FINE GRAVELS	GP	WET ZONE DRY, DUSTY
40	0.0					BRN. GRAY		FINE SAND, FEW GRAVELS	SP	
50	0.0					BRN		COBBLES		DRY
60	0.0							FINE-MED SAND TR. FINE PEBBLES FINE-MED SAND NO PEBBLES LIKE MASON'S SAND FINE-MED SAND SOME ADDED FINE PEBBLES	SP	NO DUST MOIST MOIST
70	0.0							FINE GRAVELS	GP	BECOMING DUSTY

COMMENTS

THIS BORING WAS ABANDONED DUE TO CASING JOINTS
SNAPPING OFF AT DEPTH PREVENTING CASING TO BE FURTHER
ADVANCED WHILE DRILLING. SEE MN-3 FOR

PROJECT NO.

35231.05

BORING NO.

MW-3A

URS CONSULTANTS, Inc.

TEST BORING LOG

BORING NO.

MW-3A

PROJECT: QUEENSBURY LANDFILL PHASE II

SHEET NO. 2 OF 3

CLIENT: NEW YORK STATE DEPT. OF ENVIRONMENTAL CONSERVATION

JOB NO.: 35231-05

DEPTH FT	STRATA	SAMPLE				CONSERVATION DESCRIPTION				REMARKS
		NO.	TYPE	BLOWS PER 6"	RECOVERY RQD %	COLOR	CONSISTENCY HARDNESS	MATERIAL DESCRIPTION	CLASS USCS	
								FINE GRAVELS	GP	DRY $H_{nu}=0$ DOWNHOLE
						BRN.		FN-MED SAND	SP	MOIST LEL 0%
80										@ 81
						BRN.		FINE-COARSE SAND FEW ROUNDED PEBBLES PULLED UP CASING AND WENT TO WINCH - BLEW OUT BOTTOM TO CHECK FOR ANY ACCUMULATING WATER - NONE	SW	VERY DUSTY MOIST AGAIN
90						LT. GRAY		COBBLE		DRY, DUSTY
						BRN.		FINE SAND ALTERNATING FINE-COARSE	SW SP	MOIST
100										
						MULTI-COLORED		COARSE GRAVEL COBBLES		
110										
						BRN.		ROUNDED PEBBLES TO COARSE SAND		DRY DUSTY
120						GRY.		COBBLES AT 121' NO AIR RETURN VACUUM, CHUTE FLAT		$H_{nu}=0$ ppm LEL = 0%
130								-131' AIR CIRCULATING AGAIN COBBLES		V. DUSTY
140										
150						BRN.		FINE SAND, FEW GRAVELS FINE-MED SAND	SP	V. MOIST MOIST

COMMENTS

PROJECT NO.

35231-05

BORING NO.

MW-3A

MW-3A

SHEET NO. 3 OF 3

JOB NO. : 35231.05

COMMENTS

35231.05

MW-3A

URS CONSULTANTS, Inc.

TEST BORING LOG

BORING NO.

MW-3

PROJECT: QUEENSBURY LANDFILL PHASE II INVESTIGATION

SHEET NO. 1 OF 3

CLIENT: NEW YORK STATE DEPARTMENT OF ENVIRONMENTAL CONSERVATION

JOB NO.: 35231.05

BORING CONTRACTOR: CONSTRUCTION DRILLING SERVICES (CDS)

BORING LOCATION:

GROUND WATER:

CAS.

SAMP CORE

TUBE

GROUND ELEVATION: 483.18

DATE

TIME

LEV

TYPE

TYPE

DATE STARTED: 11-5-90

11-6

4:15 PM

162'

GRAVEL

DIA.

DATE FINISHED: 11-8-90

11-9

8:30 AM

164.5'

T.O. RISER

WT.

DRILLER: DICK MILLER

FALL

GEOLOGIST: SCOTT SWANSON

* POCKET PENETROMETER READING

REVIEWED BY:

DEPTH FT	STRATA	SAMPLE				DESCRIPTION				REMARKS
		NO.	TYPE	BLOWS PER 6"	RECOVERY REC %	COLOR	CONSISTENCY HARDNESS	MATERIAL DESCRIPTION	TESTS	
								SEE MW-3A LOG FOR DETAILED DESCRIPTION		11:40AM START DRILLING
10			NO SPLIT					COBBLE		
			SPOONS					ZONE		
20										
30										
40										
								FINE-MED SAND	SP	
50										
60										
70										

COMMENTS

TUBEX AIR-ROTARY DRILLING METHOD

RIG: TRUCK MOUNT ENCKSOLL-RAND TH-60

PROJECT NO.

35231.05

BORING NO.

MW-3

URS CONSULTANTS, Inc.

TEST BORING LOG

BORING NO.

MW-3

PROJECT: QUEENSBURY LANDFILL PHASE II INVESTIGATION

SHEET NO. 3 OF 3

CLIENT: NYSDOT

JOB NO.: 35231.05

DEPTH FT	STRATA	SAMPLE				DESCRIPTION				REMARKS
		NO.	TYPE	BLOWS PER 6"	RECOVERY ROD %	COLOR	CONSISTENCY HARDNESS	MATERIAL DESCRIPTION	CLASS USCS	
			NO. SPLIT					FINE SAND	SP	DAMP
160			SPOONS					MEASURED WATER @ 162 - FINE-MED SAND W/LITTLE COARSE - 166 water observed top casing	SP	wet
170								100K GEOTECH GRAIN SIZE		SAMPLES
180								TOTAL DEPTH 182'		

COMMENTS

PROJECT NO.

35231.05

BORING NO.

MW-3

APPENDIX D
MONITORING WELL CONSTRUCTION DETAILS



STATE OF NEW YORK DEPARTMENT OF HEALTH

Corning Tower The Governor Nelson A. Rockefeller Empire State Plaza Albany, New York 12237

David Axelrod M.D.
Commissioner

OFFICE OF PUBLIC HEALTH

Linda A. Randolph M.D. M.P.H.
Director

William F. Leavy
Executive Deputy Director

March 4, 1991



RE: Queensbury Landfill
Queensbury(T), Warren County
Site ID #557005



On January 28, 1991 I collected water samples at your home in the Town of Queensbury. I am pleased to report that there were no detected volatile organic compounds and for all inorganic metals analyzed, the concentrations are within the the expected background range.

The samples were submitted to the NYS Department of Health's Wadsworth Center for Laboratories and Research for analysis. I have also included an explanation sheet which may help you interpret the sample results. If you have any questions, I can be reached at (518) 458-6306.

Sincerely,

Stanley J. Kilmer
Program Research Specialist I
Bureau of Environmental Exposure
Investigation

sjk/10630690

Attachment

cc: R. Tramontano/G. Litwin, w/o att.
P. Smith, CRU, w/o att.
B. Fear, GFDO, w/o att.
D. Steenberge, DEC-Reg. 5, w/att.
M. Brand, DEC, w/att.

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER FOR LABORATORIES AND RESEARCH

PAGE 1

RESULTS OF EXAMINATION

FINAL REPORT

SAMPLE ID: 910450 SAMPLE RECEIVED: 91/01/28/ CHARGE: 19.00
 PROGRAM: 110: STATE SUPERFUND ANALYTICAL SERVICES
 SOURCE ID: DRAINAGE BASIN: 10 GAZETTEER CODE: 5657
 POLITICAL SUBDIVISION: QUEENSBURY COUNTY: WARREN
 LATITUDE: LONGITUDE: Z DIRECTION:
 LOCATION: 557005 QUEENSBURY LANDFILL
 DESCRIPTION: 15 [REDACTED]
 REPORTING LAB: TOX: LAB FOR ORGANIC ANALYTICAL CHEMISTRY
 TEST PATTERN: VOL3-KET: PURGEABLES & KETONES
 SAMPLE TYPE: 120: PRIVATE WATER SUPPLY - DRILLED WELL
 TIME OF SAMPLING: 91/01/28 12: DATE PRINTED: 91/02/22

ANALYSIS: VHO5021 VOLATILE HALOGENATED ORGANICS (DES 310-29)
 DATE REPORTED: 91/02/20 REPORT RAILED OUT

-----PARAMETER-----	-----RESULT-----
CHLOROMETHANE	< 0.5 MCG/L
BROMOMETHANE	< 0.5 MCG/L
VINYL CHLORIDE	< 0.5 MCG/L
DICHLORODIFLUOROMETHANE (FREON-12)	< 0.5 MCG/L
CHLOROETHANE	< 0.5 MCG/L
METHYLENE CHLORIDE (DICHLOROMETHANE)	< 0.5 MCG/L
TRICHLOROFLUOROMETHANE (FREON-11)	< 0.5 MCG/L
1,1-DICHLOROETHENE	< 0.5 MCG/L
1,1-DICHLOROETHANE	< 0.5 MCG/L
TRANS-1,2-DICHLOROETHENE	< 0.5 MCG/L
CIS-1,2-DICHLOROETHENE	< 0.5 MCG/L
CHLOROFORM	< 0.5 MCG/L
1,2-DICHLOROETHANE	< 0.5 MCG/L
DIBROMOMETHANE	< 0.5 MCG/L
1,1,1-TRICHLOROETHANE	< 0.5 MCG/L
CARBON TETRACHLORIDE	< 0.5 MCG/L
BROMODICHLOROMETHANE	< 0.5 MCG/L
2,3-DICHLOROPROPENE	< 0.5 MCG/L
1,2-DICHLOROPROPANE	< 0.5 MCG/L
CIS-1,3-DICHLOROPROPENE	< 0.5 MCG/L
TRICHLOROETHENE	< 0.5 MCG/L
1,3-DICHLOROPROPANE	< 0.5 MCG/L
DIBROMOCHLOROMETHANE	< 0.5 MCG/L
TRANS-1,3-DICHLOROPROPENE	< 0.5 MCG/L
1,1,2-TRICHLOROETHANE	< 0.5 MCG/L
1,2-DIBROMOETHANE (EDB)	< 0.5 MCG/L
2-CHLOROETHYL VINYL ETHER	< 0.5 MCG/L
BROMOFORM	< 0.5 MCG/L
1,1,1,2-TETRACHLOROETHANE	< 0.5 MCG/L
1,2,3-TRICHLOROPROPANE	< 0.5 MCG/L

**** CONTINUED ON NEXT PAGE ****

COPIES SENT TO: CO(3), RO(0), LPHE(1), FED(), INFO-P(), INFO-L()

RONALD TRAMONTANO, PE
 BUR. ENVIRONMENTAL EXPOSURE INVESTIGAT.
 NY STATE DEP'T. HEALTH
 II UNIVERSITY PLACE
 ALBANY, NY 12237 INTERAGENCY MAIL

SUBMITTED BY: KILMER

NEW YORK STATE DEPARTMENT OF HEALTH
HADSWORTH CENTER FOR LABORATORIES AND RESEARCH

PAGE 2

RESULTS OF EXAMINATION

FINAL REPORT

SAMPLE ID: 910458 SAMPLE RECEIVED: 91/01/28/ CHARGE: 19.00
 POLITICAL SUBDIVISION: QUEENSBURY COUNTY: WARREN
 LOCATION: 557005 QUEENSBURY LANDFILL
 TIME OF SAMPLING: 91/01/28 12: DATE PRINTED: 91/02/22

PARAMETER	RESULT
1,1,2,2-TETRACHLOROETHANE	< 0.5 MCG/L
TETRACHLOROETHENE	< 0.5 MCG/L
PENTACHLOROETHANE	< 0.5 MCG/L
1-CHLOROCYCLOHEXENE-1	< 0.5 MCG/L
CHLOROBENZENE	< 0.5 MCG/L
BIS(2-CHLOROETHYL)ETHER	< 0.5 MCG/L
1,2-DIBROMO-3-CHLOROPROPANE	< 0.5 MCG/L
BROMOBENZENE	< 0.5 MCG/L
O-CHLOROTOLUENE	< 0.5 MCG/L
BIS(2-CHLOROISOPROPYL)ETHER	< 0.5 MCG/L
1,3-DICHLOROBENZENE	< 0.5 MCG/L
1,2-DICHLOROBENZENE	< 0.5 MCG/L
1,4-DICHLOROBENZENE	< 0.5 MCG/L

ANALYSIS: 5031 AROMATIC PURGEABLES, EPA METHOD 503.1 (DES 310-22)
 DATE PRINTED: 91/02/22 FINAL REPORT

PARAMETER	RESULT
BENZENE	< 0.5 MCG/L
TOLUENE	< 0.5 MCG/L
ETHYLBENZENE	< 0.5 MCG/L
P-XYLENE	< 0.5 MCG/L
M-XYLENE	< 0.5 MCG/L
O-XYLENE	< 0.5 MCG/L
ISOPROPYLBENZENE (CUMENE)	< 0.5 MCG/L
STYRENE	< 0.5 MCG/L
P-BROMOFLUOROBENZENE	< 0.5 MCG/L
N-PROPYLBENZENE	< 0.5 MCG/L
TERT-BUTYLBENZENE	< 0.5 MCG/L
P-CHLOROTOLUENE	< 0.5 MCG/L
M-CHLOROTOLUENE	< 0.5 MCG/L
1,3,5-TRIMETHYLBENZENE	< 0.5 MCG/L
1,2,4-TRIMETHYLBENZENE	< 0.5 MCG/L
4-ISOPROPYLTOLUENE (P-CYMENE)	< 0.5 MCG/L
CYCLOPROPYLBENZENE	< 0.5 MCG/L
SEC-BUTYLBENZENE	< 0.5 MCG/L
N-BUTYLBENZENE	< 0.5 MCG/L
2,3-BENZOFURAN	< 0.5 MCG/L
HEXACHLOROBUTADIENE (C-46)	< 0.5 MCG/L
1,2,4-TRICHLOROBENZENE	< 0.5 MCG/L
NAPHTHALENE	< 0.5 MCG/L
1,2,3-TRICHLOROBENZENE	< 0.5 MCG/L
PH OF AROMATIC ALIQUOT	1
PH WAS NOT AS LOW AS REQUIRED BY METHOD	YES
**** CONTINUED ON NEXT PAGE ****	

0599

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER FOR LABORATORIES AND RESEARCH

PAGE 3

RESULTS OF EXAMINATION

FINAL REPORT

SAMPLE ID: 910458 SAMPLE RECEIVED: 91/01/28/ CHARGE: 19.00
POLITICAL SUBDIVISION: QUEENSBURY COUNTY: WARREN
LOCATION: 557005 QUEENSBURY LANDFILL
TIME OF SAMPLING: 91/01/28 12: DATE PRINTED: 91/02/22

ANALYSIS: KET KETONES - PURGE & TRAP TECHNIQUE (DES 310-25)
DATE REPORTED: 91/02/08 REPORT MAILED OUT

-----PARAMETER-----	-----RESULT-----
2-BUTANONE (METHYL ETHYL KETONE)	< 10. MCG/L
4-METHYL-2-PENTANONE (MYBK)	< 10. MCG/L
ACETONE	< 10. MCG/L
METHYL TERT BUTYL ETHER	< 10. MCG/L

**** END OF REPORT ****



STATE OF NEW YORK DEPARTMENT OF HEALTH

Corning Tower The Governor Nelson A. Rockefeller Empire State Plaza Albany, New York 12237

David Axelrod M.D.
Commissioner

OFFICE OF PUBLIC HEALTH

Linda A. Randolph M.D., M.P.H.
Director

William F. Leavy
Executive Deputy Director

March 4, 1991

DEPARTMENT OF HEALTH
DIVISION OF HAZARDOUS
WASTE REMEDIATION

RE: Queensbury Landfill
Queensbury(T), Warren County
Site ID #557005

On January 28, 1991 I collected water samples at your home in the Town of Queensbury. I am pleased to report that there were no detected volatile organic compounds and for all inorganic metals analyzed, the concentrations are within the the expected background range.

The samples were submitted to the NYS Department of Health's Wadsworth Center for Laboratories and Research for analysis. I have also included an explanation sheet which may help you interpret the sample results. If you have any questions, I can be reached at (518) 458-6306.

Sincerely,

Stanley J. Kilmer
Program Research Specialist I
Bureau of Environmental Exposure
Investigation

sjk/10630667

Attachment

cc: R. Tramontano/G. Litwin, w/o att.
P. Smith, CRU, w/o att.
B. Fear, GFDO, w/o att.
D. Steenberge, DEC-Reg. 5, w/att.
M. Brand, DEC, w/att.

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER FOR LABORATORIES AND RESEARCH

PAGE 1

RESULTS OF EXAMINATION

FINAL REPORT

SAMPLE ID: 910457 SAMPLE RECEIVED: 91/01/28/ CHARGE: 19.00
 PROGRAM: 110: STATE SUPERFUND ANALYTICAL SERVICES
 SOURCE ID: DRAINAGE BASIN: 10 GAZETTEER CODE: 5657
 POLITICAL SUBDIVISION: QUEENSBURY COUNTY: WARREN
 LATITUDE: LONGITUDE: 2 DIRECTION:
 LOCATION: 557005 QUEENSBURY LANDFILL
 DESCRIPTION: [REDACTED]
 REPORTING LAB: TOXILAB FOR ORGANIC ANALYTICAL CHEMISTRY
 TEST PATTERN: VOL3-KET: PURGEABLES & KETONES
 SAMPLE TYPE: 120: PRIVATE WATER SUPPLY - DRILLED WELL
 TIME OF SAMPLING: 91/01/28 11:45 DATE PRINTED: 91/02/22

ANALYSIS: VHO5021 VOLATILE HALOGENATED ORGANICS (DES 310-29)
 DATE REPORTED: 91/02/20 REPORT MAILED OUT

PARAMETER	RESULT
CHLOROMETHANE	< 0.5 MCG/L
BROMOMETHANE	< 0.5 MCG/L
VINYL CHLORIDE	< 0.5 MCG/L
DICHLORODIFLUOROMETHANE (FREON-12)	< 0.5 MCG/L
CHLOROETHANE	< 0.5 MCG/L
METHYLENE CHLORIDE (DICHLOROMETHANE)	< 0.5 MCG/L
TRICHLOROFLUOROMETHANE (FREON-11)	< 0.5 MCG/L
1,1-DICHLOROETHENE	< 0.5 MCG/L
1,1-DICHLOROETHANE	< 0.5 MCG/L
TRANS-1,2-DICHLOROETHENE	< 0.5 MCG/L
CIS-1,2-DICHLOROETHENE	< 0.5 MCG/L
CHLOROFORM	< 0.5 MCG/L
1,2-DICHLOROETHANE	< 0.5 MCG/L
DIBROMOMETHANE	< 0.5 MCG/L
1,1,1-TRICHLOROETHANE	< 0.5 MCG/L
CARBON TETRACHLORIDE	< 0.5 MCG/L
BROMODICHLOROMETHANE	< 0.5 MCG/L
2,3-DICHLOROPROPENE	< 0.5 MCG/L
1,2-DICHLOROPROPANE	< 0.5 MCG/L
CIS-1,3-DICHLOROPROPENE	< 0.5 MCG/L
TRICHLOROETHENE	< 0.5 MCG/L
1,3-DICHLOROPROPANE	< 0.5 MCG/L
DIBROMOCHLOROMETHANE	< 0.5 MCG/L
TRANS-1,3-DICHLOROPROPENE	< 0.5 MCG/L
1,1,2-TRICHLOROETHANE	< 0.5 MCG/L
1,2-DIBROMOETHANE (EDB)	< 0.5 MCG/L
2-CHLOROETHYL VINYL ETHER	< 0.5 MCG/L
BROMOFORM	< 0.5 MCG/L
1,1,1,2-TETRACHLOROETHANE	< 0.5 MCG/L
1,2,3-TRICHLOROPROPANE	< 0.5 MCG/L

*** CONTINUED ON NEXT PAGE ***

COPIES SENT TO: CO(3), RO(0), LPHE(1), FED(), INFO-P(), INFO-L()

RONALD TRAMONTANO, PE
 BUR. ENVIRONMENTAL EXPOSURE INVESTIGAT.
 NY STATE DEP'T. HEALTH
 11 UNIVERSITY PLACE
 ALBANY, NY 12237 INTERAGENCY MAIL

SUBMITTED BY: KILMER

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER FOR LABORATORIES AND RESEARCH

PAGE 2

RESULTS OF EXAMINATION

FINAL REPORT

SAMPLE ID: 910457 SAMPLE RECEIVED: 91/01/28/ CHARGE: 19.00
POLITICAL SUBDIVISION: QUEENSBURY COUNTY: WARREN
LOCATION: 557005 QUEENSBURY LANDFILL
TIME OF SAMPLING: 91/01/28 11:45 DATE PRINTED: 91/02/22

PARAMETER	RESULT
1,1,2,2-TETRACHLOROETHANE	< 0.5 MCG/L
TETRACHLOROETHENE	< 0.5 MCG/L
PENTACHLOROETHANE	< 0.5 MCG/L
1-CHLOROCYCLOHEXENE-1	< 0.5 MCG/L
CHLOROBENZENE	< 0.5 MCG/L
CIS(2-CHLOROETHYL)ETHER	< 0.5 MCG/L
1,2-DIBROMO-3-CHLOROPROPANE	< 0.5 MCG/L
BROMOBENZENE	< 0.5 MCG/L
O-CHLOROTOLUENE	< 0.5 MCG/L
BIS(2-CHLOROISOPROPYL)ETHER	< 0.5 MCG/L
1,3-DICHLOROBENZENE	< 0.5 MCG/L
1,2-DICHLOROBENZENE	< 0.5 MCG/L
1,4-DICHLOROBENZENE	< 0.5 MCG/L

ANALYSIS: 5031 AROMATIC PURGEABLES, EPA METHOD 503.1 (DES 310-22)
DATE PRINTED: 91/02/22 FINAL REPORT

PARAMETER	RESULT
BENZENE	< 0.5 MCG/L
TOLUENE	< 0.5 MCG/L
ETHYLBENZENE	< 0.5 MCG/L
P-XYLENE	< 0.5 MCG/L
M-XYLENE	< 0.5 MCG/L
O-XYLENE	< 0.5 MCG/L
ISOPROPYLBENZENE (CUMENE)	< 0.5 MCG/L
STYRENE	< 0.5 MCG/L
P-BROMOFLUOROBENZENE	< 0.5 MCG/L
N-PROPYLBENZENE	< 0.5 MCG/L
TERT-BUTYLBENZENE	< 0.5 MCG/L
P-CHLOROTOLUENE	< 0.5 MCG/L
M-CHLOROTOLUENE	< 0.5 MCG/L
1,3,5-TRIMETHYLBENZENE	< 0.5 MCG/L
1,2,4-TRIMETHYLBENZENE	< 0.5 MCG/L
4-ISOPROPYLTOLUENE (P-CYMENE)	< 0.5 MCG/L
CYCLOPROPYLBENZENE	< 0.5 MCG/L
SEC-BUTYLBENZENE	< 0.5 MCG/L
N-BUTYLBENZENE	< 0.5 MCG/L
2,3-BENZOFURAN	< 0.5 MCG/L
HEXACHLOROBUTADIENE (C-46)	< 0.5 MCG/L
1,2,4-TRICHLOROBENZENE	< 0.5 MCG/L
NAPHTHALENE	< 0.5 MCG/L
1,2,3-TRICHLOROBENZENE	< 0.5 MCG/L
PH OF AROMATIC ALIQUOT	7
PH WAS NOT AS LOW AS REQUIRED BY METHOD	YES

**** CONTINUED ON NEXT PAGE ****

0590

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER FOR LABORATORIES AND RESEARCH

PAGE 3

RESULTS OF EXAMINATION

FINAL REPORT

SAMPLE ID: 910457 SAMPLE RECEIVED: 91/01/28/ CHARGE: 19.00
POLITICAL SUBDIVISION: QUEENSBURY COUNTY: WARREN
LOCATION: 557005 QUEENSBURY LANDFILL
TIME OF SAMPLING: 91/01/28 11:45 DATE PRINTED: 91/02/22

ANALYSIS: KET KETONES - PURGE & TRAP TECHNIQUE (DES 310-25)
DATE REPORTED: 91/02/08 REPORT MAILED OUT

-----PARAMETER-----	-----RESULT-----
2-BUTANONE (METHYL ETHYL KETONE)	< 10. MCG/L
4-METHYL-2-PENTANONE (MIBK)	< 10. MCG/L
ACEONE	< 10. MCG/L
METHYL TERT BUTYL ETHER	< 10. MCG/L

**** END OF REPORT ****

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER FOR LABORATORIES AND RESEARCH

PAGE 1

RESULTS OF EXAMINATION

FINAL REPORT

SAMPLE ID: 911000204 SAMPLE RECEIVED: 91/01/29/ CHARGE: 5.00
PROGRAM: 110: STATE SUPERFUND ANALYTICAL SERVICES
SOURCE ID: DRAINAGE BASIN: 10 GAZETTEER CODE: 5657
POLITICAL SUBDIVISION: QUEENSBURY COUNTY: WARREN
LATITUDE: LONGITUDE: Z DIRECTION:
LOCATION: 557005 QUEENSBURY LANDFILL
DESCRIPTION: [REDACTED]
REPORTING LAB: 10: LABORATORY OF INORGANIC ANALYTICAL CHEMISTRY - ALBANY
TEST PATTERN: 10-001: SAFE DRINKING WATER ACT - METALS ONLY
SAMPLE TYPE: 120: PRIVATE WATER SUPPLY - DRILLED WELL
TIME OF SAMPLING: 91/01/28 11:45 DATE PRINTED: 91/02/26

ANALYSIS: ICP-1 ICP GROUPING 1

-----PARAMETER-----

-----RESULT-----

MERCURY	< 0.2 MCG/L
ARSENIC	< 10. MCG/L
SELENIUM	< 5. MCG/L
LEAD	< 10. MCG/L
BERYLLIUM	< 1. MCG/L
SILVER	< 10. MCG/L
BARIUM	32. MCG/L
CADMIUM	< 5. MCG/L
COBALT	< 5. MCG/L
CHROMIUM	< 5. MCG/L
COPPER	35. MCG/L
IRON	261. MCG/L
MANGANESE	6. MCG/L
NICKEL	< 5. MCG/L
STRONTIUM	291. MCG/L
TITANIUM	< 5. MCG/L
VANADIUM	< 5. MCG/L
ZINC	20. MCG/L
MOLYBDENUM	< 20. MCG/L
ANTIMONY	< 80. MCG/L
TIN	< 50. MCG/L
THALLIUM	< 80. MCG/L
ALUMINUM	< 100. MCG/L
CALCIUM	36.3 MG/L
POTASSIUM	1.2 MG/L
MAGNESIUM	15.7 MG/L
SODIUM	3.4 MG/L

**** END OF REPORT ****

COPIES SENT TO: CO(3), RO(0), LPHE(1), FED(), INFO-P(), INFO-L()

RONALD TRAMONTANO, PE
BUR. ENVIRONMENTAL EXPOSURE INVESTIGAT.
NY STATE DEP'T. HEALTH
II UNIVERSITY PLACE
ALBANY, NY 12237 INTERAGENCY MAIL

SUBMITTED BY: KILMER

APPENDIX G (e)

NYSDEC LEACHATE SAMPLING ANALYTICAL RESULTS (1/16/91)

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER FOR LABORATORIES AND RESEARCH

PAGE 1

RESULTS OF EXAMINATION

FINAL REPORT

SAMPLE ID: 911005005 SAMPLE RECEIVED: 91/01/18/11 CHARGE: 18.32
 PROGRAM: 6505: DIV. SOLID WASTE - BUREAU FACILITIES MANAGEMENT
 SOURCE ID: DRAINAGE BASIN: 10 GAZETTEER CODE: 5657
 POLITICAL SUBDIVISION: QUEENSBURY COUNTY: WARREN
 LATITUDE: LONGITUDE: Z DIRECTION:
 LOCATION: QUEENSBURY LANDFILL LEACHATE HOLDING POND
 DESCRIPTION: DEC SAMPLE #R590-57S10-SW1
 REPORTING LAB: 10: LABORATORY OF INORGANIC ANALYTICAL CHEMISTRY - ALBANY
 TEST PATTERN: 10-181: DEC - BUREAU OF MUN. WASTE - II
 SAMPLE TYPE: 240: LEACHATE
 TIME OF SAMPLING: 91/01/16 10:30 DATE PRINTED: 91/02/22

ANALYSIS: 10-181 DEC - BUREAU OF MUN. WASTE - II

PARAMETER	RESULT
NITROGEN, AMMONIA, AS N	97. MG/L
NITROGEN, NITRATE (+NO2) AS N	0.06 MG/L
C.O.D.	260. MG/L
CARBON, TOTAL ORGANIC	70. MG/L
SOLIDS, TOTAL DISSOLVED, 180 C	1730. MG/L
SULFATE AS SO4	2.3 MG/L
ALKALINITY TO PH 4.5	1530. MG/L
PHENOLS	20. MCG/L
CHLORIDE	291. MG/L
HARDNESS, TOTAL AS CaCO3	702. MG/L
TURBIDITY	OPAQUE
B.O.D. 5 DAY	24. SR MG/L
COLOR, APPARENT	[NA]
CYANIDES, HYDROLYZABLE	0.004 MG/L
BORON	1.5 MG/L
SULFIDE	1.4 MG/L
NITROGEN, KJELDAHL, AS N	106. MG/L
CHROMIUM, HEXAVALENT	< 5.0 MCG/L

ANALYSIS: ICP-2 ICP GROUPING 2 - TOTAL RECOVERABLE

PARAMETER	RESULT
MERCURY	0.3 MCG/L
ARSENIC, TOTAL RECOVERABLE	< 10. MCG/L
SELENIUM, TOTAL RECOVERABLE	< 5. MCG/L
LEAD, TOTAL RECOVERABLE	< 10. MCG/L
BERYLLIUM, TOTAL RECOVERABLE	< 1. MCG/L
SILVER, TOTAL RECOVERABLE	< 10. MCG/L
BARIUM, TOTAL RECOVERABLE	298. MCG/L
CADMIUM, TOTAL RECOVERABLE	< 5. MCG/L
COBALT, TOTAL RECOVERABLE	11. MCG/L

**** CONTINUED ON NEXT PAGE ****

COPIES SENT TO: CO(1), RO(), LPHE(), FED(), INFO-P(), INFO-L()

RICH BALDWIN
 NY STATE DEPT ENVIRON. CONSERVATION
 DIV. SOLID WASTES (RM. 422)
 50 WOLF RD.
 ALBANY, NY

SUBMITTED BY: BERES

1010

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER FOR LABORATORIES AND RESEARCH

PAGE 2

RESULTS OF EXAMINATION

FINAL REPORT

SAMPLE ID: 911005005

SAMPLE RECEIVED: 91/01/18/11

CHARGE: 18.32

POLITICAL SUBDIVISION: QUEENSBURY

COUNTY: WARREN

LOCATION: QUEENSBURY LANDFILL LEACHATE HOLDING POND

TIME OF SAMPLING: 91/01/16 10:30

DATE PRINTED: 91/02/22

PARAMETER	RESULT
CHROMIUM, TOTAL RECOVERABLE	11. MCG/L
COPPER, TOTAL RECOVERABLE	6. MCG/L
IRON, TOTAL RECOVERABLE	45700. MCG/L
MANGANESE, TOTAL RECOVERABLE	654. MCG/L
NICKEL, TOTAL RECOVERABLE	29. MCG/L
STRONTIUM, TOTAL RECOVERABLE	1440. MCG/L
TITANIUM, TOTAL RECOVERABLE	24. MCG/L
VANADIUM, TOTAL RECOVERABLE	< 5. MCG/L
ZINC, TOTAL RECOVERABLE	18. MCG/L
MOLYBDENUM, TOTAL RECOVERABLE	< 20. MCG/L
ANTIMONY, TOTAL RECOVERABLE	< 80. MCG/L
TIN, TOTAL RECOVERABLE	< 50. MCG/L
THALLIUM, TOTAL RECOVERABLE	< 60. MCG/L
ALUMINUM, TOTAL RECOVERABLE	309. MCG/L
CALCIUM, TOTAL RECOVERABLE	194. MG/L
POTASSIUM, TOTAL RECOVERABLE	92.0 MG/L
MAGNESIUM, TOTAL RECOVERABLE	67.0 MG/L
SODIUM, TOTAL RECOVERABLE	230. MG/L
DIG OF H2O-RECOVERABLE METALS	DONE

FOLLOWING PARAMETERS NOT PART OF TEST PATTERN

PARAMETER	RESULT
COLOR, TRUE	100.

**** END OF REPORT ****

APPENDIX H
ANALYTICAL SAMPLE DESCRIPTIONS

SAMPLE ID	DATE SAMPLED	SAMPLE TYPE	DESCRIPTION	LOCATION
MW-1	11/30/90	Groundwater	Clear, no odor	West side of site near the intersection of Ridge and Jenkinsville Roads
MW-2	11/29/90	Groundwater	Clear, no odor	West side of site adjacent to N.E. corner of Ciba-Geigy Secure Landfill
MW-3	11/30/90	Groundwater	Clear, no odor	South of active fill area near Esker Ridge
MW-4	11/29/90	Groundwater	Clear, no odor	S.E. portion of site near Mud Pond
MW-5	11/28/90	Groundwater	Clear, no odor	North central portion of site in north part of Torrington Pit
E-1	11/28/90	Groundwater	Clear, no odor	West portion of site near Landfill Office
E-2	11/29/90	Groundwater	Clear, no odor	S.E. portion of site near Mud Pond
E-3	11/28/90	Groundwater	Clear, no odor	South central portion of Torrington Pit
L-1	11/28/90	Leachate	Orange-red color, metallic odor	S.E. portion of site near containment berm
L-2	11/29/90	Leachate	Orange-red color, metallic odor	S.E. portion of site near roadway
SW-1	11/29/90	Surface Water	Clear, no odor	S.E. portion of site, taken next to Mud Pond stream gauge
SED-1	11/29/90	Sediment	Brown-black color with organics, gravelly	S.E. portion of site, taken near Mud Pond Stream gauge

APPENDIX I
PHASE II ANALYTICAL TESTING RESULTS

ANALYTICAL DATA ASSESSMENT
FOR
PHASE II CHEMICAL ANALYSES AT QUEENSBURY LANDFILL

Performed By:
VERSAR LABORATORIES, INC.

Prepared For:
NEW YORK STATE DEPARTMENT OF ENVIRONMENTAL CONSERVATION

By:
URS CONSULTANTS, INC.

JUNE 1991

INTRODUCTION: This assessment represents the best judgement of URS Consultants, Inc. (URS) concerning the useability of the chemical data produced by Versar Laboratories, Inc. a subcontractor to URS, as part of the Phase II Investigation at Queensbury Landfill site in Albany County, New York. This project is being funded by the New York State Department of Environmental Conservation (NYSDEC). The data being evaluated is from the sampling of surface waters, stream sediments, leachate and groundwater samples. All analyses performed by Versar Laboratories Inc., were subject to NYSDEC Analytical Services Protocol - September 1989.

Data documentation and chain-of-custody procedures were performed in accordance with NYSDEC Analytical Services Protocol - September 1989. Data validation and determination of useability were performed in accordance with the level of effort discussed in the transmittals between URS and the NYSDEC which stated each site would be screened for compliance with analytical holding times, surrogate and spike recovery criteria, method blank requirements, and initial and continuing calibration requirements. The primary importance of this chemical data is to allow an accurate assessment of sites and to determine if further study is required prior to reclassification and/or delisting.

CATEGORIES: The following tables summarize our assessment of data useability on a sample-by-sample and fraction-by-fraction basis. In evaluating this data, we have established three (3) categories which are,


for the most part, gradational in nature. The categories are defined as follows:

Category 1a - Data Useable - Fully useable, although some minor deviations from NYSDEC ASP criteria are possible.

Category 1b - Data Useable with Caution - Cumulative deviations from NYSDEC ASP criteria are greater than Category 1a (e.g., holding time violations, internal standard and surrogate recovery outliers, poor chromatography, calibration standards not within QC limits, etc.). However, TCL compounds were detected at or above the quantitation limit or deviations are not considered significant enough as to jeopardize the chemical representativeness of the sample results. Deviations are explained in the note section of each data useability table.

Category 2a - Rejected Fraction Due to Significant NYSDEC ASP Deviations - Did not comply with NYSDEC ASP or USEPA CLP holding time requirements or low surrogate recoveries indicate poor method efficiency resulting in low bias of analytical data. In either case no TCL compounds were detected at or above the quantitation limit.

Summary Assessment: We recommend acceptance and use of all data in Category 1a. The use of Category 1b data involves some risk in the event of a legalistic challenge based upon non-compliance with strict NYSDEC ASP criteria. However, given the purpose of the Phase II studies, we cautiously recommend the use of the data categorized as 1b. We recommend rejection of all data in Category 2a.


James Lanzo
Project Manager


Thomas Knickerbocker
QA/QC Officer

TABLE 1

QUEENSBURY LANDFILL

ANALYTICAL DATA ASSESSMENT SUMMARY

MATRIX: Groundwater, Surface Water, Stream Sediments, Leachate

SAMPLE DELIVERY GROUP: 3881/4014/4022

ASSESSMENT CATEGORIES: 1a, 1b, 2a

Sample ID	VOA	SVOA	Pest/PCB	Metals	CN	Notes
Drill Water	1b	1a	1a	1a	1a	1
Trip Blank	1b	-	-	-	-	1
HOLD BLK-11/9	2a	-	-	-	-	
E-1-GW	1a	1a	1a	1b	1a	2
E-2-GW	1a	1a	1a	1a	1a	
E-3-GW	1a	1a	1a	1b	1a	2
L-1	1a	1a	1a	1b	1a	2
L-2	1a	1a	1a	1a	1a	
MW-1-GW	1a	1a	1a	1a	1a	
MW-2-GW	1a	1a	1a	1a	1a	
MW-3-GW	1a	1a	1a	1a	1a	
MW-4-GW	1a	1a	1a	1a	1a	
MW-5-GW	1a	1a	1a	1b	1a	2
SED-1	1a	1b	1b	1b	1a	2,3,4
SED-1-MS	1a	1b	1b	1b	1a	2,3,4
SED-1-MSD	1a	1b	1b	-	-	3,4
SED-1-MSB	1a	1a	1a	-	-	
SED-1-DUP	-	-	-	1b	1a	2
TB-1	1a	-	-	-	-	
HOLD BLK-11/30	1a	-	-	-	-	
HOLD BLK-12/3	1a	-	-	-	-	
RB-MW-4	1a	1a	1a	1a	1a	
SW-1	1a	1a	1a	1a	1a	
SW-1-MS	1a	1a	1a	1a	1a	
SW-1-MSD	1a	1a	1a	-	-	
SW-1-MSB	1a	1a	1a	-	-	
SW-1-DUP	-	-	-	1a	1a	

TABLE 1 (Continued)

QUEENSBURY LANDFILL

Sample ID	VOA	SVOA	Pest/PCB	Metals	CN	Notes
TB-A	1a	-	-	-	-	
TB-B	1a	-	-	-	-	
TB-C	1a	-	-	-	-	

Abbreviation/Legend:

VOA - Target Compound List (TCL) Volatile

SVOA - TCL Semivolatiles

Pest/PCB - TCL Pesticides/PCBs

Metals - Target Analyte List (TAL) Metals

CN - Cyanide

MSB - Matrix Spike Blank

TB - Trip Blank

RB - Rinse Blank

SW - Surface Water

SED - Sediment

L - Leachate Seep

MS - Matrix Spike

MSD - Matrix Spike Duplicate

DUP - Duplicate

GW - Groundwater

E - Existing Well

MW - Monitoring Well

NOTES FOR TABLE 1

- 1) The volatile sample was not analyzed within NYSDEC ASP holding time requirements but, was analyzed within USEPA CLP holding time requirements.
- 2) The metals analysis for mercury was completed after the NYSDEC ASP holding time had been exceeded, but it was still inside the USEPA CLP analysis holding time. All other metal analyses were completed within the NYSDEC ASP holding time.
- 3) The semivolatile sample was not extracted within NYSDEC ASP holding times, but, the sample was extracted within USEPA CLP holding time requirements.
- 4) The pesticide/PCB sample was not extracted within NYSDEC ASP holding times, but, the sample was extracted within USEPA CLP holding time requirements.

1A
VOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

DRILL_WATER

Lab Name: VERSAR INC. Contract: _____

Lab Code: VERSAR Case No.: 3881 SAS No.: _____ SDG No.: 1

Matrix: (soil/water) WATER Lab Sample ID: 36333

Sample wt/vol: 5.0 (g/mL) ML Lab File ID: V6734

Level: (low/med) LOW Date Received: 11/09/90

% Moisture: not dec. _____ Date Analyzed: 11/17/90

Column: (pack/cap) CAP PACK Dilution Factor: 1.0

CAS NO. COMPOUND CONCENTRATION UNITS:
(ug/L or ug/Kg) UG/L Q

74-87-3	Chloromethane	10	U
74-83-9	Bromomethane	10	U
75-01-4	Vinyl chloride	10	U
75-00-3	Chloroethane	10	U
75-09-2	Methylene chloride	5	U
67-64-1	Acetone	10	U
75-15-0	Carbon disulfide	5	U
75-35-4	1,1-Dichloroethene	5	U
75-34-3	1,1-Dichloroethane	5	U
540-59-0	1,2-Dichloroethene (total)	5	U
67-66-3	Chloroform	5	U
107-06-2	1,2-Dichloroethane	5	U
78-93-3	2-Butanone	10	U
71-55-6	1,1,1-Trichloroethane	5	U
56-23-5	Carbon tetrachloride	5	U
108-05-4	Vinyl acetate	10	U
75-27-4	Bromodichloromethane	5	U
78-87-5	1,2-Dichloropropane	5	U
10061-01-5	cis-1,3-Dichloropropene	5	U
79-01-6	Trichloroethene	5	U
124-48-1	Dibromochloromethane	5	U
79-00-5	1,1,2-Trichloroethane	5	U
71-43-2	Benzene	5	U
10061-02-6	Trans-1,3-dichloropropene	5	U
75-25-2	Bromoform	5	U
108-10-1	4-Methyl-2-pentanone	10	U
591-78-6	2-Hexanone	10	U
127-18-4	Tetrachloroethene	5	U
79-34-5	1,1,2,2-Tetrachloroethane	5	U
108-88-3	Toluene	5	U
108-90-7	Chlorobenzene	5	U
100-41-4	Ethylbenzene	5	U
100-42-5	Styrene	5	U
1330-20-7	Total xylenes	5	U

1E
VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

EPA SAMPLE NO.

DRILL_WATER

Lab Name: VERSAR INC. Contract: _____
Lab Code: VERSAR Case No.: 3881 SAS No.: _____ SDG No.: 1
Matrix: (soil/water) WATER Lab Sample ID: 36333
Sample wt/vol: 5.0 (g/mL) ML Lab File ID: V6734
Level: (low/med) LOW Date Received: 11/09/90
% Moisture: not dec. _____ Date Analyzed: 11/17/90
Column (pack/cap) CAP PACK Dilution Factor: 1.0

Number TICs found: 0 CONCENTRATION UNITS:
(ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
=====	=====	=====	=====	=====

1B
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

DRILLWATER

I Name: VERSAR INC. Contract: _____

Lab Code: VERSAR Case No.: 3881A SAS No.: _____ SDG No.: 1

Matrix: (soil/water) WATER Lab Sample ID: 36335

Sample wt/vol: 1010 (g/mL) ML Lab File ID: T5280

Level: (low/med) LOW Date Received: 11/09/90

% Moisture: not dec. _____ dec. _____ Date Extracted: 11/13/90

Extraction: (SepF/Cont/Sonc) CONT Date Analyzed: 12/12/90

GPC Cleanup: (Y/N) N pH: _____ Dilution Factor: 1.00

CAS NO. COMPOUND CONCENTRATION UNITS:
(ug/L or ug/Kg) UG/L Q

108-95-2-----	Phenol	10	U
111-44-4-----	bis(2-Chloroethyl) ether	10	U
95-57-8-----	2-Chlorophenol	10	U
541-73-1-----	1,3-Dichlorobenzene	10	U
106-46-7-----	1,4-Dichlorobenzene	10	U
100-51-6-----	Benzyl alcohol	10	U
95-50-1-----	1,2-Dichlorobenzene	10	U
95-48-7-----	2-Methylphenol	10	U
108-60-1-----	bis(2-Chloroisopropyl) ether	10	U
106-44-5-----	4-Methylphenol	10	U
621-64-7-----	N-Nitroso-di-n-propylamine	10	U
67-72-1-----	Hexachloroethane	10	U
98-95-3-----	Nitrobenzene	10	U
78-59-1-----	Isophorone	10	U
88-75-5-----	2-Nitrophenol	10	U
105-67-9-----	2,4-Dimethylphenol	10	U
65-85-0-----	Benzoic Acid	50	U
111-91-1-----	bis(2-Chloroethoxy) methane	10	U
120-83-2-----	2,4-Dichlorophenol	10	U
120-82-1-----	1,2,4-Trichlorobenzene	10	U
91-20-3-----	Naphthalene	10	U
106-47-8-----	4-Chloroaniline	10	U
87-68-3-----	Hexachlorobutadiene	10	U
59-50-7-----	4-Chloro-3-methylphenol	10	U
91-57-6-----	2-Methylnaphthalene	10	U
77-47-4-----	Hexachlorocyclopentadiene	10	U
88-06-2-----	2,4,6-Trichlorophenol	10	U
95-95-4-----	2,4,5-Trichlorophenol	50	U
91-58-7-----	2-Chloronaphthalene	10	U
88-74-4-----	2-Nitroaniline	50	U
131-11-3-----	Dimethylphthalate	10	U
208-96-8-----	Acenaphthylene	10	U
606-20-2-----	2,6-Dinitrotoluene	10	U

1C
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

DRILLWATER

L Name: VERSAR INC. Contract: _____

Lab Code: VERSAR Case No.: 3881A SAS No.: _____ SDG No.: 1

Matrix: (soil/water) WATER Lab Sample ID: 36335

Sample wt/vol: 1010 (g/mL) ML Lab File ID: T5280

Level: (low/med) LOW Date Received: 11/09/90

% Moisture: not dec. _____ dec. _____ Date Extracted: 11/13/90

Extraction: (SepF/Cont/Sonc) CONT Date Analyzed: 12/12/90

GPC Cleanup: (Y/N) N pH: _____ Dilution Factor: 1.00

CONCENTRATION UNITS:
(ug/L or ug/Kg) UG/L Q

CAS NO.	COMPOUND	CONCENTRATION UNITS: (ug/L or ug/Kg) <u>UG/L</u>	Q
99-09-2-----	3-Nitroaniline	50	U
83-32-9-----	Acenaphthene	10	U
51-28-5-----	2,4-Dinitrophenol	50	U
100-02-7-----	4-Nitrophenol	50	U
132-64-9-----	Dibenzofuran	10	U
121-14-2-----	2,4-Dinitrotoluene	10	U
84-66-2-----	Diethylphthalate	10	U
7005-72-3-----	4-Chlorophenyl-phenylether	10	U
86-73-7-----	Fluorene	10	U
100-01-6-----	4-Nitroaniline	50	U
534-52-1-----	4,6-Dinitro-2-methylphenol	50	U
86-30-6-----	N-nitrosodiphenylamine (1)	10	U
101-55-3-----	4-Bromophenyl-phenylether	10	U
118-74-1-----	Hexachlorobenzene	10	U
87-86-5-----	Pentachlorophenol	50	U
85-01-8-----	Phenanthrene	10	U
120-12-7-----	Anthracene	10	U
84-74-2-----	Di-n-butylphthalate	10	U
206-44-0-----	Fluoranthene	10	U
129-00-0-----	Pyrene	10	U
85-68-7-----	Butylbenzylphthalate	10	U
91-94-1-----	3,3'-Dichlorobenzidine	20	U
56-55-3-----	Benzo(a)anthracene	10	U
218-01-9-----	Chrysene	10	U
117-81-7-----	bis(2-Ethylhexyl)phthalate	10	U
117-84-0-----	Di-n-octyl phthalate	10	U
205-99-2-----	Benzo(b)fluoranthene	10	U
207-08-9-----	Benzo(k)fluoranthene	10	U
50-32-8-----	Benzo(a)pyrene	10	U
193-39-5-----	Indeno(1,2,3-cd)pyrene	10	U
53-70-3-----	Dibenz(a,h)anthracene	10	U
191-24-2-----	Benzo(g,h,i)perylene	10	U

(1) - Cannot be separated from Diphenylamine

1F
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

EPA SAMPLE NO.

DRILLWATER

Lab Name: VERSAR INC. Contract: _____

Lab Code: VERSAR Case No.: 3881A SAS No.: _____ SDG No.: 1

Matrix: (soil/water) WATER Lab Sample ID: 36335

Sample wt/vol: 1010 (g/mL) ML Lab File ID: T5280

Level: (low/med) LOW Date Received: 11/09/90

% Moisture: not dec. _____ dec. _____ Date Extracted: 11/13/90

Extraction: (SepF/Cont/Sonc) CONT Date Analyzed: 12/12/90

GPC Cleanup: (Y/N) N pH: _____ Dilution Factor: 1.00

Number TICs found: 1 CONCENTRATION UNITS:
(ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1.	UNKNOWN	2.42	7.9	J

D

1D

EPA SAMPLE NO.

PESTICIDE ORGANICS ANALYSIS DATA SHEET

DRILLWATER

Lab Name: _____ VERSAR, INC. _____ Contract: _____

Lab Code: VERSAR Case No.: URSQUEEN SAS No.: _____ SDG No.: _____

Matrix: (soil/water) WATER Lab Sample ID: __36336

Sample wt/vol: 1000 (g/ml) ML Lab File ID: _____

Level: (low/med) __LOW__ Date Received: __11/09/90

% Moisture: not dec. _____ dec. _____ Date Extracted: __11/13/90

Extraction: (SepF/Cont/Sonc) _____ CONT Date Analyzed: __11/29/90

GPC Cleanup: (Y/N) __N__ pH: _____ Dilution Factor: 1.0

CONCENTRATION UNITS:
(ug/L or ug/Kg) _UG/L

CAS NO.	COMPOUND	CONCENTRATION UNITS: (ug/L or ug/Kg) _UG/L	Q
319-84-6	alpha-BHC	0.05	U
319-85-7	beta-BHC	0.05	U
319-86-8	delta-BHC	0.05	U
58-89-9	gamma-BHC (Lindane)	0.05	U
76-44-8	Heptachlor	0.05	U
309-00-2	Aldrin	0.05	U
1024-57-3	Heptachlor Epoxide	0.05	U
959-98-8	Endosulfan I	0.05	U
60-57-1	Dieldrin	0.10	U
72-55-9	4,4'-DDE	0.10	U
72-20-8	Endrin	0.10	U
33213-65-9	Endosulfan II	0.10	U
72-54-8	4,4'-DDD	0.10	U
1031-07-8	Endosulfan Sulfate	0.10	U
50-29-3	4,4'-DDT	0.10	U
72-43-5	Methoxychlor	0.50	U
53494-70-5	Endrin Ketone	0.10	U
5103-71-9	alpha-Chlordane	0.50	U
5103-74-2	gamma-Chlordane	0.50	U
8001-35-2	Toxaphene	1.0	U
12674-11-2	Aroclor-1016	0.50	U
11104-28-2	Aroclor-1221	0.50	U
11141-16-5	Aroclor-1232	0.50	U
53469-21-9	Aroclor-1242	0.50	U
12672-29-6	Aroclor-1248	0.50	U
11097-69-1	Aroclor-1254	1.0	U
11096-82-5	Aroclor-1260	1.0	U

PE 4/30/90

D

100000

U.S. EPA - CLP

1
INORGANIC ANALYSES DATA SHEET

EPA SAMPLE NO.

DRILL

Lab Name: VERSAR LABORATORIES INC. Contract: 35216.03

Lab Code: VERSAR Case No.: 3881 SAS No.: SDG No.: DRILL

Matrix (soil/water): WATER Lab Sample ID: 36337

Level (low/med): LOW Date Received: 11/09/90

% Solids: 0.0

Concentration Units (ug/L or mg/kg dry weight): UG/L

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum	984	—	—	P
7440-36-0	Antimony	30.0	U	—	P
7440-38-2	Arsenic	3.0	U	—	F
7440-39-3	Barium	12.2	B	—	P
7440-41-7	Beryllium	1.0	U	—	P
7440-43-9	Cadmium	5.0	U	—	P
7440-70-2	Calcium	8580	—	—	P
7440-47-3	Chromium	6.0	U	—	P
7440-48-4	Cobalt	6.0	U	—	P
7440-50-8	Copper	5.8	B	—	P
7439-89-6	Iron	433	—	—	P
7439-92-1	Lead	2.6	B	—	F
7439-95-4	Magnesium	835	B	—	P
7439-96-5	Manganese	4.2	B	—	P
7439-97-6	Mercury	0.20	U	—	CV
7440-02-0	Nickel	12.0	U	—	P
7440-09-7	Potassium	1010	B	—	P
7782-49-2	Selenium	3.0	U	—	F
7440-22-4	Silver	5.0	U	—	P
7440-23-5	Sodium	12400	—	—	P
7440-28-0	Thallium	3.0	U	W	F
7440-62-2	Vanadium	4.0	U	—	P
7440-66-6	Zinc	14.4	B	—	P
	Cyanide	10.0	U	—	AS

Color Before: COLORLESS Clarity Before: CLEAR Texture:

Color After: COLORLESS Clarity After: CLEAR Artifacts:

Comments:

THE CYANIDE LAB SAMPLE ID NUMBER IS 36338; THE EPA SAMPLE NUMBER SUFFIX
IS "WATER";

1A
VOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

QL-MW-1GW

L Name: VERSAR INC. Contract: _____

Lab Code: VERSAR Case No.: 4022 SAS No.: _____ SDG No.: 3

Matrix: (soil/water) WATER Lab Sample ID: 38764

Sample wt/vol: 5.0 (g/mL) ML Lab File ID: S1251

Level: (low/med) LOW Date Received: 12/01/90

% Moisture: not dec. _____ Date Analyzed: 12/06/90

Column: (pack/cap) CAP Dilution Factor: 1.0

CAS NO. COMPOUND CONCENTRATION UNITS:
(ug/L or ug/Kg) UG/L Q

74-87-3-----	Chloromethane	10	U
74-83-9-----	Bromomethane	10	U
75-01-4-----	Vinyl chloride	10	U
75-00-3-----	Chloroethane	10	U
75-09-2-----	Methylene chloride	5	U
67-64-1-----	Acetone	10	U
75-15-0-----	Carbon disulfide	5	U
75-35-4-----	1,1-Dichloroethene	5	U
75-34-3-----	1,1-Dichloroethane	5	U
540-59-0-----	1,2-Dichloroethene (total)	5	U
67-66-3-----	Chloroform	5	U
107-06-2-----	1,2-Dichloroethane	5	U
78-93-3-----	2-Butanone	10	U
71-55-6-----	1,1,1-Trichloroethane	5	U
56-23-5-----	Carbon tetrachloride	5	U
108-05-4-----	Vinyl acetate	10	U
75-27-4-----	Bromodichloromethane	5	U
78-87-5-----	1,2-Dichloropropane	5	U
10061-01-5-----	cis-1,3-Dichloropropene	5	U
79-01-6-----	Trichloroethene	5	U
124-48-1-----	Dibromochloromethane	5	U
79-00-5-----	1,1,2-Trichloroethane	5	U
71-43-2-----	Benzene	5	U
10061-02-6-----	Trans-1,3-dichloropropene	5	U
75-25-2-----	Bromoform	5	U
108-10-1-----	4-Methyl-2-pentanone	10	U
591-78-6-----	2-Hexanone	10	U
127-18-4-----	Tetrachloroethene	5	U
79-34-5-----	1,1,2,2-Tetrachloroethane	5	U
108-88-3-----	Toluene	5	U
108-90-7-----	Chlorobenzene	5	U
100-41-4-----	Ethylbenzene	5	U
100-42-5-----	Styrene	5	U
1330-20-7-----	Total xylenes	5	U

1E
VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

EPA SAMPLE NO.

QL-MW-1GW

Lab Name: VERSAR INC. Contract: _____

Lab Code: VERSAR Case No.: 4022 SAS No.: _____ SDG No.: 3

Matrix: (soil/water) WATER Lab Sample ID: 38764

Sample wt/vol: 5.0 (g/mL) ML Lab File ID: S1251

Level: (low/med) LOW Date Received: 12/01/90

% Moisture: not dec. _____ Date Analyzed: 12/06/90

Column (pack/cap) CAP Dilution Factor: 1.0

Number TICs found: 0 CONCENTRATION UNITS:
(ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
=====	=====	=====	=====	=====

1B
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

QLMW1GW

I Name: VERSAR INC. Contract: _____

Lab Code: VERSAR Case No.: 4022A SAS No.: _____ SDG No.: B3

Matrix: (soil/water) WATER Lab Sample ID: 38775

Sample wt/vol: 1050 (g/mL) ML Lab File ID: T5500

Level: (low/med) LOW Date Received: 12/01/90

% Moisture: not dec. _____ dec. _____ Date Extracted: 12/05/90

Extraction: (SepF/Cont/Sonc) CONT Date Analyzed: 12/31/90

GPC Cleanup: (Y/N) N pH: _____ Dilution Factor: 1.00

CAS NO. COMPOUND CONCENTRATION UNITS:
(ug/L or ug/Kg) UG/L Q

108-95-2-----	Phenol	10	U
111-44-4-----	bis(2-Chloroethyl)ether	10	U
95-57-8-----	2-Chlorophenol	10	U
541-73-1-----	1,3-Dichlorobenzene	10	U
106-46-7-----	1,4-Dichlorobenzene	10	U
100-51-6-----	Benzyl alcohol	10	U
95-50-1-----	1,2-Dichlorobenzene	10	U
95-48-7-----	2-Methylphenol	10	U
108-60-1-----	bis(2-Chloroisopropyl)ether	10	U
106-44-5-----	4-Methylphenol	10	U
621-64-7-----	N-Nitroso-di-n-propylamine	10	U
67-72-1-----	Hexachloroethane	10	U
98-95-3-----	Nitrobenzene	10	U
78-59-1-----	Isophorone	10	U
88-75-5-----	2-Nitrophenol	10	U
105-67-9-----	2,4-Dimethylphenol	10	U
65-85-0-----	Benzoic Acid	48	U
111-91-1-----	bis(2-Chloroethoxy)methane	10	U
120-83-2-----	2,4-Dichlorophenol	10	U
120-82-1-----	1,2,4-Trichlorobenzene	10	U
91-20-3-----	Naphthalene	10	U
106-47-8-----	4-Chloroaniline	10	U
87-68-3-----	Hexachlorobutadiene	10	U
59-50-7-----	4-Chloro-3-methylphenol	10	U
91-57-6-----	2-Methylnaphthalene	10	U
77-47-4-----	Hexachlorocyclopentadiene	10	U
88-06-2-----	2,4,6-Trichlorophenol	10	U
95-95-4-----	2,4,5-Trichlorophenol	48	U
91-58-7-----	2-Chloronaphthalene	10	U
88-74-4-----	2-Nitroaniline	48	U
131-11-3-----	Dimethylphthalate	10	U
208-96-8-----	Acenaphthylene	10	U
606-20-2-----	2,6-Dinitrotoluene	10	U

1C
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

QLMW1GW

I Name: VERSAR INC. Contract: _____

Lab Code: VERSAR Case No.: 4022A SAS No.: _____ SDG No.: B3

Matrix: (soil/water) WATER Lab Sample ID: 38775

Sample wt/vol: 1050 (g/mL) ML Lab File ID: T5500

Level: (low/med) LOW Date Received: 12/01/90

% Moisture: not dec. _____ dec. _____ Date Extracted: 12/05/90

Extraction: (SepF/Cont/Sonc) CONT Date Analyzed: 12/31/90

GPC Cleanup: (Y/N) N pH: _____ Dilution Factor: 1.00

CAS NO. COMPOUND CONCENTRATION UNITS:
(ug/L or ug/Kg) UG/L Q

99-09-2-----	3-Nitroaniline	48	U
83-32-9-----	Acenaphthene	10	U
51-28-5-----	2,4-Dinitrophenol	48	U
100-02-7-----	4-Nitrophenol	48	U
132-64-9-----	Dibenzofuran	10	U
121-14-2-----	2,4-Dinitrotoluene	10	U
84-66-2-----	Diethylphthalate	10	U
7005-72-3-----	4-Chlorophenyl-phenylether	10	U
86-73-7-----	Fluorene	10	U
100-01-6-----	4-Nitroaniline	48	U
534-52-1-----	4,6-Dinitro-2-methylphenol	48	U
86-30-6-----	N-nitrosodiphenylamine (1)	10	U
101-55-3-----	4-Bromophenyl-phenylether	10	U
118-74-1-----	Hexachlorobenzene	10	U
87-86-5-----	Pentachlorophenol	48	U
85-01-8-----	Phenanthrene	10	U
120-12-7-----	Anthracene	10	U
84-74-2-----	Di-n-butylphthalate	10	U
206-44-0-----	Fluoranthene	10	U
129-00-0-----	Pyrene	10	U
85-68-7-----	Butylbenzylphthalate	10	U
91-94-1-----	3,3'-Dichlorobenzidine	19	U
56-55-3-----	Benzo(a)anthracene	10	U
218-01-9-----	Chrysene	10	U
117-81-7-----	bis(2-Ethylhexyl)phthalate	10	U
117-84-0-----	Di-n-octyl phthalate	10	U
205-99-2-----	Benzo(b)fluoranthene	10	U
207-08-9-----	Benzo(k)fluoranthene	10	U
50-32-8-----	Benzo(a)pyrene	10	U
193-39-5-----	Indeno(1,2,3-cd)pyrene	10	U
53-70-3-----	Dibenz(a,h)anthracene	10	U
191-24-2-----	Benzo(g,h,i)perylene	10	U

(1) - Cannot be separated from Diphenylamine

1F
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

EPA SAMPLE NO.

QLMW1GW

Name: VERSAR INC. Contract: _____
Lab Code: VERSAR Case No.: 4022A SAS No.: _____ SDG No.: B3
Matrix: (soil/water) WATER Lab Sample ID: 38775
Sample wt/vol: 1050 (g/mL) ML Lab File ID: T5500
Level: (low/med) LOW Date Received: 12/01/90
% Moisture: not dec. _____ dec. _____ Date Extracted: 12/05/90
Extraction: (SepF/Cont/Sonc) CONT Date Analyzed: 12/31/90
GPC Cleanup: (Y/N) N pH: _____ Dilution Factor: 1.00

CONCENTRATION UNITS:
(ug/L or ug/Kg) UG/L

Number TICs found: 1

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1.	UNKNOWN	3.37	51	BJ

1D
PESTICIDE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

QLMW1GW

Lab Name: _____ VERSAR, INC. _____ Contract: _____

b Code: VERSAR Case No.: URSQUEEN SAS No.: _____ SDG No.: _____

Matrix: (soil/water) WATER

Lab Sample ID: __38785

Sample wt/vol: 1050 (g/ml) ML

Lab File ID: _____

Level: (low/med) __LOW__

Date Received: __12/01/90

% Moisture: not dec. _____ dec. _____

Date Extracted: __12/05/90

Extraction: (SepF/Cont/Sonc) _____ CONT

Date Analyzed: __01/05/91

GPC Cleanup: (Y/N) __N__ pH: _____

Dilution Factor: 1.0

CAS NO.	COMPOUND	CONCENTRATION UNITS:	
		(ug/L or ug/Kg) _UG/L	Q
319-84-6	alpha-BHC	0.05	1U
319-85-7	beta-BHC	0.05	1U
319-86-8	delta-BHC	0.05	1U
58-89-9	gamma-BHC (Lindane)	0.05	1U
76-44-8	Heptachlor	0.05	1U
309-00-2	Aldrin	0.05	1U
1024-57-3	Heptachlor Epoxide	0.05	1U
959-98-8	Endosulfan I	0.05	1U
60-57-1	Dieldrin	0.10	1U
72-55-9	4,4'-DDE	0.10	1U
72-20-8	Endrin	0.10	1U
33213-65-9	Endosulfan II	0.10	1U
72-54-8	4,4'-DDD	0.10	1U
1031-07-8	Endosulfan Sulfate	0.10	1U
50-29-3	4,4'-DDT	0.10	1U
72-43-5	Methoxychlor	0.48	1U
53494-70-5	Endrin Ketone	0.10	1U
5103-71-9	alpha-Chlordane	0.48	1U
5103-74-2	gamma-Chlordane	0.48	1U
8001-35-2	Toxaphene	0.95	1U
12674-11-2	Aroclor-1016	0.48	1U
11104-28-2	Aroclor-1221	0.48	1U
11141-16-5	Aroclor-1232	0.48	1U
53469-21-9	Aroclor-1242	0.48	1U
12672-29-6	Aroclor-1248	0.48	1U
11097-69-1	Aroclor-1254	0.95	1U
11096-82-5	Aroclor-1260	0.95	1U

ga
1/7/91

U.S. EPA - CLP

1
INORGANIC ANALYSES DATA SHEET

EPA SAMPLE NO.

MW-1GW

Lab Name: VERSAR LABORATORIES INC. Contract: 35216.03

Lab Code: VERSAR Case No.: 4014 SAS No.: SDG No.: E-1

Matrix (soil/water): WATER Lab Sample ID: 38795

Level (low/med): LOW Date Received: 12/01/90

% Solids: 0.0

Concentration Units (ug/L or mg/kg dry weight): UG/L

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum	870	-		P
7440-36-0	Antimony	23.0	U		P
7440-38-2	Arsenic	3.0	U		F
7440-39-3	Barium	55.4	B		P
7440-41-7	Beryllium	1.0	U		P
7440-43-9	Cadmium	5.0	U		P
7440-70-2	Calcium	118000			P
7440-47-3	Chromium	5.0	U		P
7440-48-4	Cobalt	9.8	B		P
7440-50-8	Copper	8.2	B		P
7439-89-6	Iron	3990			P
7439-92-1	Lead	6.1			F
7439-95-4	Magnesium	23200			P
7439-96-5	Manganese	103			P
7439-97-6	Mercury	0.20	U		CV
7440-02-0	Nickel	13.0	U		P
7440-09-7	Potassium	503	U		P
7782-49-2	Selenium	3.0	U	WN	F
7440-22-4	Silver	3.0	U		P
7440-23-5	Sodium	28300			P
7440-28-0	Thallium	10.0	U		F
7440-62-2	Vanadium	5.0	U		P
7440-66-6	Zinc	22.1			P
	Cyanide	10.0	U		AS

Color Before: GREY Clarity Before: CLOUDY Texture:

Color After: COLORLESS Clarity After: CLEAR Artifacts:

Comments:

THE CYANIDE LAB SAMPLE ID NUMBER IS 38804; THE EPA SAMPLE NUMBER
 PREFIX IS "Q/L";

1A
VOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

QL-MW-2GW

L Name: VERSAR INC. Contract: _____
 Lab Code: VERSAR Case No.: 4022 SAS No.: _____ SDG No.: 3
 Matrix: (soil/water) WATER Lab Sample ID: 38765
 Sample wt/vol: 5.0 (g/mL) ML Lab File ID: S1252
 Level: (low/med) LOW Date Received: 12/01/90
 % Moisture: not dec. _____ Date Analyzed: 12/06/90
 Column: (pack/cap) CAP Dilution Factor: 1.0

CONCENTRATION UNITS:
(ug/L or ug/Kg) UG/L

CAS NO. COMPOUND Q

74-87-3	Chloromethane	10	U
74-83-9	Bromomethane	10	U
75-01-4	Vinyl chloride	10	U
75-00-3	Chloroethane	10	U
75-09-2	Methylene chloride	5	U
67-64-1	Acetone	10	U
75-15-0	Carbon disulfide	5	U
75-35-4	1,1-Dichloroethene	5	U
75-34-3	1,1-Dichloroethane	3	JX
540-59-0	1,2-Dichloroethene (total)	5	U
67-66-3	Chloroform	5	U
107-06-2	1,2-Dichloroethane	5	U
78-93-3	2-Butanone	10	U
71-55-6	1,1,1-Trichloroethane	5	U
56-23-5	Carbon tetrachloride	5	U
108-05-4	Vinyl acetate	10	U
75-27-4	Bromodichloromethane	5	U
78-87-5	1,2-Dichloropropane	5	U
10061-01-5	cis-1,3-Dichloropropene	5	U
79-01-6	Trichloroethene	5	U
124-48-1	Dibromochloromethane	5	U
79-00-5	1,1,2-Trichloroethane	5	U
71-43-2	Benzene	5	U
10061-02-6	Trans-1,3-dichloropropene	5	U
75-25-2	Bromoform	5	U
108-10-1	4-Methyl-2-pentanone	10	U
591-78-6	2-Hexanone	10	U
127-18-4	Tetrachloroethene	5	U
79-34-5	1,1,2,2-Tetrachloroethane	5	U
108-88-3	Toluene	5	U
108-90-7	Chlorobenzene	5	U
100-41-4	Ethylbenzene	5	U
100-42-5	Styrene	5	U
1330-20-7	Total xylenes	5	U

1E
VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

EPA SAMPLE NO.

QL-MW-2GW

Lab Name: VERSAR INC. Contract: _____

Lab Code: VERSAR Case No.: 4022 SAS No.: _____ SDG No.: 3

Matrix: (soil/water) WATER Lab Sample ID: 38765

Sample wt/vol: 5.0 (g/mL) ML Lab File ID: S1252

Level: (low/med) LOW Date Received: 12/01/90

% Moisture: not dec. _____ Date Analyzed: 12/06/90

Column (pack/cap) CAP Dilution Factor: 1.0

Number TICs found: 0 CONCENTRATION UNITS:
(ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
=====	=====	=====	=====	=====

1B
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

QLMW2GW

L Name: VERSAR INC. Contract: _____

Lab Code: VERSAR Case No.: 4022A SAS No.: _____ SDG No.: B3

Matrix: (soil/water) WATER Lab Sample ID: 38776

Sample wt/vol: 1050 (g/mL) ML Lab File ID: T5501

Level: (low/med) LOW Date Received: 12/01/90

% Moisture: not dec. _____ dec. _____ Date Extracted: 12/05/90

Extraction: (SepF/Cont/Sonc) CONT Date Analyzed: 12/31/90

GPC Cleanup: (Y/N) N pH: _____ Dilution Factor: 1.00

CONCENTRATION UNITS:

CAS NO. COMPOUND (ug/L or ug/Kg) UG/L Q

108-95-2-----	Phenol	10	U
111-44-4-----	bis(2-Chloroethyl) ether	10	U
95-57-8-----	2-Chlorophenol	10	U
541-73-1-----	1,3-Dichlorobenzene	10	U
106-46-7-----	1,4-Dichlorobenzene	10	U
100-51-6-----	Benzyl alcohol	10	U
95-50-1-----	1,2-Dichlorobenzene	10	U
95-48-7-----	2-Methylphenol	10	U
108-60-1-----	bis(2-Chloroisopropyl) ether	10	U
106-44-5-----	4-Methylphenol	10	U
621-64-7-----	N-Nitroso-di-n-propylamine	10	U
67-72-1-----	Hexachloroethane	10	U
98-95-3-----	Nitrobenzene	10	U
78-59-1-----	Isophorone	10	U
88-75-5-----	2-Nitrophenol	10	U
105-67-9-----	2,4-Dimethylphenol	10	U
65-85-0-----	Benzoic Acid	48	U
111-91-1-----	bis(2-Chloroethoxy) methane	10	U
120-83-2-----	2,4-Dichlorophenol	10	U
120-82-1-----	1,2,4-Trichlorobenzene	10	U
91-20-3-----	Naphthalene	10	U
106-47-8-----	4-Chloroaniline	10	U
87-68-3-----	Hexachlorobutadiene	10	U
59-50-7-----	4-Chloro-3-methylphenol	10	U
91-57-6-----	2-Methylnaphthalene	10	U
77-47-4-----	Hexachlorocyclopentadiene	10	U
88-06-2-----	2,4,6-Trichlorophenol	10	U
95-95-4-----	2,4,5-Trichlorophenol	48	U
91-58-7-----	2-Chloronaphthalene	10	U
88-74-4-----	2-Nitroaniline	48	U
131-11-3-----	Dimethylphthalate	10	U
208-96-8-----	Acenaphthylene	10	U
606-20-2-----	2,6-Dinitrotoluene	10	U

1C
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

QLMW2GW

L Name: VERSAR INC. Contract: _____

Lab Code: VERSAR Case No.: 4022A SAS No.: _____ SDG No.: B3

Matrix: (soil/water) WATER Lab Sample ID: 38776

Sample wt/vol: 1050 (g/mL) ML Lab File ID: T5501

Level: (low/med) LOW Date Received: 12/01/90

% Moisture: not dec. _____ dec. _____ Date Extracted: 12/05/90

Extraction: (SepF/Cont/Sonc) CONT Date Analyzed: 12/31/90

GPC Cleanup: (Y/N) N pH: _____ Dilution Factor: 1.00

CONCENTRATION UNITS:
(ug/L or ug/Kg) UG/L

CAS NO.

COMPOUND

Q

99-09-2-----	3-Nitroaniline	48	U
83-32-9-----	Acenaphthene	10	U
51-28-5-----	2,4-Dinitrophenol	48	U
100-02-7-----	4-Nitrophenol	48	U
132-64-9-----	Dibenzofuran	10	U
121-14-2-----	2,4-Dinitrotoluene	10	U
84-66-2-----	Diethylphthalate	10	U
7005-72-3-----	4-Chlorophenyl-phenylether	10	U
86-73-7-----	Fluorene	10	U
100-01-6-----	4-Nitroaniline	48	U
534-52-1-----	4,6-Dinitro-2-methylphenol	48	U
86-30-6-----	N-nitrosodiphenylamine (1)	10	U
101-55-3-----	4-Bromophenyl-phenylether	10	U
118-74-1-----	Hexachlorobenzene	10	U
87-86-5-----	Pentachlorophenol	48	U
85-01-8-----	Phenanthrene	10	U
120-12-7-----	Anthracene	10	U
84-74-2-----	Di-n-butylphthalate	10	U
206-44-0-----	Fluoranthene	10	U
129-00-0-----	Pyrene	10	U
85-68-7-----	Butylbenzylphthalate	10	U
91-94-1-----	3,3'-Dichlorobenzidine	19	U
56-55-3-----	Benzo(a)anthracene	10	U
218-01-9-----	Chrysene	10	U
117-81-7-----	bis(2-Ethylhexyl)phthalate	10	U
117-84-0-----	Di-n-octyl phthalate	10	U
205-99-2-----	Benzo(b)fluoranthene	10	U
207-08-9-----	Benzo(k)fluoranthene	10	U
50-32-8-----	Benzo(a)pyrene	10	U
193-39-5-----	Indeno(1,2,3-cd)pyrene	10	U
53-70-3-----	Dibenz(a,h)anthracene	10	U
191-24-2-----	Benzo(g,h,i)perylene	10	U

(1) - Cannot be separated from Diphenylamine

1F
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

EPA SAMPLE NO.

QLMW2GW

Lab Name: VERSAR INC. Contract: _____
Lab Code: VERSAR Case No.: 4022A SAS No.: _____ SDG No.: B3
Matrix: (soil/water) WATER Lab Sample ID: 38776
Sample wt/vol: 1050 (g/mL) ML Lab File ID: T5501
Level: (low/med) LOW Date Received: 12/01/90
% Moisture: not dec. _____ dec. _____ Date Extracted: 12/05/90
Extraction: (SepF/Cont/Sonc) CONT Date Analyzed: 12/31/90
GPC Cleanup: (Y/N) N pH: _____ Dilution Factor: 1.00

Number TICs found: 7 CONCENTRATION UNITS:
(ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1.	UNKNOWN	3.37	11	BJ
2.	UNKNOWN	3.58	21	BJ
3.	UNKNOWN	4.25	11	J
4.	UNKNOWN KETONE	4.50	9.5	J
5.	UNKNOWN	17.79	17	J
6.	UNK ORGANIC ACID ESTER	18.50	5.7	J
7.	UNKNOWN	18.64	11	J

1D
PESTICIDE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

QLMW2GW

Lab Name: _____ VERSAR, INC. _____ Contract: _____

Code: VERSAR Case No.: URSQUEEN SAS No.: _____ SDG No.: _____

Matrix: (soil/water) WATER Lab Sample ID: __38786

Sample wt/vol: 1050 (g/ml) ML Lab File ID: ____

Level: (low/med) __LOW__ Date Received: __12/01/90

% Moisture: not dec. _____ dec. _____ Date Extracted: __12/05/90

Extraction: (SepF/Cont/Sonc) ____CONT Date Analyzed: __01/05/91

GPC Cleanup: (Y/N) __N__ pH: ____ Dilution Factor: 1.0

		CONCENTRATION UNITS:	
CAS NO.	COMPOUND	(ug/L or ug/Kg) UG/L	Q
319-84-6	alpha-BHC	0.05	1U
319-85-7	beta-BHC	0.05	1U
319-86-8	delta-BHC	0.05	1U
58-89-9	gamma-BHC (Lindane)	0.05	1U
76-44-8	Heptachlor	0.05	1U
309-00-2	Aldrin	0.05	1U
1024-57-3	Heptachlor Epoxide	0.05	1U
959-98-8	Endosulfan I	0.05	1U
60-57-1	Dieldrin	0.10	1U
72-55-9	4,4'-DDE	0.10	1U
72-20-8	Endrin	0.10	1U
33213-65-9	Endosulfan II	0.10	1U
72-54-8	4,4'-DDD	0.10	1U
1031-07-8	Endosulfan Sulfate	0.10	1U
50-29-3	4,4'-DDT	0.10	1U
72-43-5	Methoxychlor	0.48	1U
53494-70-5	Endrin Ketone	0.10	1U
5103-71-9	alpha-Chlordane	0.48	1U
5103-74-2	gamma-Chlordane	0.48	1U
8001-35-2	Toxaphene	0.95	1U
12674-11-2	Aroclor-1016	0.48	1U
11104-28-2	Aroclor-1221	0.48	1U
11141-16-5	Aroclor-1232	0.48	1U
53469-21-9	Aroclor-1242	0.48	1U
12672-29-6	Aroclor-1248	0.48	1U
11097-69-1	Aroclor-1254	0.95	1U
11096-82-5	Aroclor-1260	0.95	1U

ga
1/10/91

10 0029

U.S. EPA - CLP

1
INORGANIC ANALYSES DATA SHEET

EPA SAMPLE NO.

MW-2GW

Lab Name: VERSAR LABORATORIES INC. Contract: 35216.03

Lab Code: VERSAR Case No.: 4014 SAS No.: SDG No.: E-1

Matrix (soil/water): WATER Lab Sample ID: 38796

Level (low/med): LOW Date Received: 12/01/90

% Solids: 0.0

Concentration Units (ug/L or mg/kg dry weight): UG/L

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum	1720	-		P
7440-36-0	Antimony	23.0	U		P
7440-38-2	Arsenic	3.0	U		F
7440-39-3	Barium	240			P
7440-41-7	Beryllium	1.0	U		P
7440-43-9	Cadmium	5.0	U		P
7440-70-2	Calcium	216000			P
7440-47-3	Chromium	5.0	U		P
7440-48-4	Cobalt	8.0	U		P
7440-50-8	Copper	6.6	B		P
7439-89-6	Iron	4340			P
7439-92-1	Lead	3.9		S	F
7439-95-4	Magnesium	79900			P
7439-96-5	Manganese	716			P
7439-97-6	Mercury	0.20	U		CV
7440-02-0	Nickel	28.4	B		P
7440-09-7	Potassium	7220			P
7782-49-2	Selenium	30.0	U	N	F
7440-22-4	Silver	3.0	U		P
7440-23-5	Sodium	110000			P
7440-28-0	Thallium	10.0	U		F
7440-62-2	Vanadium	7.3	B		P
7440-66-6	Zinc	29.7			P
	Cyanide	10.0	U		AS

Color Before: GREY Clarity Before: CLOUDY Texture:

Color After: COLORLESS Clarity After: CLEAR Artifacts:

Comments:

THE CYANIDE LAB SAMPLE ID NUMBER IS 38805; THE EPA SAMPLE NUMBER
PREFIX IS "Q/L";

1A
VOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

QL-MW-3GW

L Name: VERSAR INC. Contract: _____

Lab Code: VERSAR Case No.: 4022 SAS No.: _____ SDG No.: 3

Matrix: (soil/water) WATER Lab Sample ID: 38767

Sample wt/vol: 5.0 (g/mL) ML Lab File ID: S1254

Level: (low/med) LOW Date Received: 12/01/90

% Moisture: not dec. _____ Date Analyzed: 12/06/90

Column: (pack/cap) CAP Dilution Factor: 1.0

CONCENTRATION UNITS:
(ug/L or ug/Kg) UG/L Q

CAS NO.	COMPOUND	CONCENTRATION UNITS: (ug/L or ug/Kg) <u>UG/L</u>	Q
74-87-3	Chloromethane	10	U
74-83-9	Bromomethane	10	U
75-01-4	Vinyl chloride	10	U
75-00-3	Chloroethane	10	U
75-09-2	Methylene chloride	5	U
67-64-1	Acetone	10	U
75-15-0	Carbon disulfide	5	U
75-35-4	1,1-Dichloroethene	5	U
75-34-3	1,1-Dichloroethane	18	
540-59-0	1,2-Dichloroethene (total)	5	U
67-66-3	Chloroform	4	J
107-06-2	1,2-Dichloroethane	5	U
78-93-3	2-Butanone	10	U
71-55-6	1,1,1-Trichloroethane	15	
56-23-5	Carbon tetrachloride	5	U
108-05-4	Vinyl acetate	10	U
75-27-4	Bromodichloromethane	5	U
78-87-5	1,2-Dichloropropane	5	U
10061-01-5	cis-1,3-Dichloropropene	5	U
79-01-6	Trichloroethene	5	U
124-48-1	Dibromochloromethane	5	U
79-00-5	1,1,2-Trichloroethane	5	U
71-43-2	Benzene	5	U
10061-02-6	Trans-1,3-dichloropropene	5	U
75-25-2	Bromoform	5	U
108-10-1	4-Methyl-2-pentanone	10	U
591-78-6	2-Hexanone	10	U
127-18-4	Tetrachloroethene	5	U
79-34-5	1,1,2,2-Tetrachloroethane	5	U
108-88-3	Toluene	5	U
108-90-7	Chlorobenzene	5	U
100-41-4	Ethylbenzene	5	U
100-42-5	Styrene	5	U
1330-20-7	Total xylenes	5	U

1E
VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

EPA SAMPLE NO.

QL-MW-3GW

L Name: VERSAR INC. Contract: _____

Lab Code: VERSAR Case No.: 4022 SAS No.: _____ SDG No.: 3

Matrix: (soil/water) WATER Lab Sample ID: 38767

Sample wt/vol: 5.0 (g/mL) ML Lab File ID: S1254

Level: (low/med) LOW Date Received: 12/01/90

% Moisture: not dec. _____ Date Analyzed: 12/06/90

Column (pack/cap) CAP Dilution Factor: 1.0

Number TICs found: 1 CONCENTRATION UNITS:
(ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1. 75-43-4	METHANE, DICHLOROFLUORO-	2.90	17	J

1B
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

QLMW3GW

L Name: VERSAR INC. Contract: _____

Lab Code: VERSAR Case No.: 4022A SAS No.: _____ SDG No.: B3

Matrix: (soil/water) WATER Lab Sample ID: 38778

Sample wt/vol: 1050 (g/mL) ML Lab File ID: T5503

Level: (low/med) LOW Date Received: 12/01/90

% Moisture: not dec. _____ dec. _____ Date Extracted: 12/05/90

Extraction: (SepF/Cont/Sonc) CONT Date Analyzed: 12/31/90

GPC Cleanup: (Y/N) N pH: _____ Dilution Factor: 1.00

CONCENTRATION UNITS:
(ug/L or ug/Kg) UG/L

CAS NO.

COMPOUND

Q

108-95-2-----	Phenol	10	U
111-44-4-----	bis(2-Chloroethyl) ether	10	U
95-57-8-----	2-Chlorophenol	10	U
541-73-1-----	1,3-Dichlorobenzene	10	U
106-46-7-----	1,4-Dichlorobenzene	10	U
100-51-6-----	Benzyl alcohol	10	U
95-50-1-----	1,2-Dichlorobenzene	10	U
95-48-7-----	2-Methylphenol	10	U
108-60-1-----	bis(2-Chloroisopropyl) ether	10	U
106-44-5-----	4-Methylphenol	10	U
621-64-7-----	N-Nitroso-di-n-propylamine	10	U
67-72-1-----	Hexachloroethane	10	U
98-95-3-----	Nitrobenzene	10	U
78-59-1-----	Isophorone	10	U
88-75-5-----	2-Nitrophenol	10	U
105-67-9-----	2,4-Dimethylphenol	10	U
65-85-0-----	Benzoic Acid	48	U
111-91-1-----	bis(2-Chloroethoxy) methane	10	U
120-83-2-----	2,4-Dichlorophenol	10	U
120-82-1-----	1,2,4-Trichlorobenzene	10	U
91-20-3-----	Naphthalene	10	U
106-47-8-----	4-Chloroaniline	10	U
87-68-3-----	Hexachlorobutadiene	10	U
59-50-7-----	4-Chloro-3-methylphenol	10	U
91-57-6-----	2-Methylnaphthalene	10	U
77-47-4-----	Hexachlorocyclopentadiene	10	U
88-06-2-----	2,4,6-Trichlorophenol	10	U
95-95-4-----	2,4,5-Trichlorophenol	48	U
91-58-7-----	2-Chloronaphthalene	10	U
88-74-4-----	2-Nitroaniline	48	U
131-11-3-----	Dimethylphthalate	10	U
208-96-8-----	Acenaphthylene	10	U
606-20-2-----	2,6-Dinitrotoluene	10	U

1C
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

QLMW3GW

L Name: VERSAR INC. Contract: _____

Lab Code: VERSAR Case No.: 4022A SAS No.: _____ SDG No.: B3

Matrix: (soil/water) WATER Lab Sample ID: 38778

Sample wt/vol: 1050 (g/mL) ML Lab File ID: T5503

Level: (low/med) LOW Date Received: 12/01/90

% Moisture: not dec. _____ dec. _____ Date Extracted: 12/05/90

Extraction: (SepF/Cont/Sonc) CONT Date Analyzed: 12/31/90

GPC Cleanup: (Y/N) N pH: _____ Dilution Factor: 1.00

CONCENTRATION UNITS:
(ug/L or ug/Kg) UG/L Q

99-09-2-----3-Nitroaniline	48	U
83-32-9-----Acenaphthene	10	U
51-28-5-----2,4-Dinitrophenol	48	U
100-02-7-----4-Nitrophenol	48	U
132-64-9-----Dibenzofuran	10	U
121-14-2-----2,4-Dinitrotoluene	10	U
84-66-2-----Diethylphthalate	10	U
7005-72-3-----4-Chlorophenyl-phenylether	10	U
86-73-7-----Fluorene	10	U
100-01-6-----4-Nitroaniline	48	U
534-52-1-----4,6-Dinitro-2-methylphenol	48	U
86-30-6-----N-nitrosodiphenylamine (1)	10	U
101-55-3-----4-Bromophenyl-phenylether	10	U
118-74-1-----Hexachlorobenzene	10	U
87-86-5-----Pentachlorophenol	48	U
85-01-8-----Phenanthrene	10	U
120-12-7-----Anthracene	10	U
84-74-2-----Di-n-butylphthalate	10	U
206-44-0-----Fluoranthene	10	U
129-00-0-----Pyrene	10	U
85-68-7-----Butylbenzylphthalate	10	U
91-94-1-----3,3'-Dichlorobenzidine	19	U
56-55-3-----Benzo(a)anthracene	10	U
218-01-9-----Chrysene	10	U
117-81-7-----bis(2-Ethylhexyl)phthalate	10	U
117-84-0-----Di-n-octyl phthalate	10	U
205-99-2-----Benzo(b)fluoranthene	10	U
207-08-9-----Benzo(k)fluoranthene	10	U
50-32-8-----Benzo(a)pyrene	10	U
193-39-5-----Indeno(1,2,3-cd)pyrene	10	U
53-70-3-----Dibenz(a,h)anthracene	10	U
191-24-2-----Benzo(g,h,i)perylene	10	U

(1) - Cannot be separated from Diphenylamine

1F
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

EPA SAMPLE NO.

QLMW3GW

Name: VERSAR INC. Contract: _____

Lab Code: VERSAR Case No.: 4022A SAS No.: _____ SDG No.: B3

Matrix: (soil/water) WATER Lab Sample ID: 38778

Sample wt/vol: 1050 (g/mL) ML Lab File ID: T5503

Level: (low/med) LOW Date Received: 12/01/90

% Moisture: not dec. _____ dec. _____ Date Extracted: 12/05/90

Extraction: (SepF/Cont/Sonc) CONT Date Analyzed: 12/31/90

GPC Cleanup: (Y/N) N pH: _____ Dilution Factor: 1.00

Number TICs found: 7

CONCENTRATION UNITS:
(ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1.	UNKNOWN	3.37	25	BJ
2.	UNKNOWN	3.58	28	BJ
3.	UNKNOWN	4.23	23	J
4.	UNKNOWN	4.48	9.5	J
5.	UNKNOWN	12.00	7.6	J
6.	UNKNOWN	17.79	23	J
7.	UNKNOWN	18.65	9.5	J

1D
PESTICIDE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

QLMW3GW

Lab Name: _____ VERSAR, INC. _____ Contract: _____

b Code: VERSAR Case No.: URSQUEEN SAS No.: _____ SDG No.: _____

Matrix: (soil/water) WATER

Lab Sample ID: __38788

Sample wt/vol: 1050 (g/ml) ML

Lab File ID: ____

Level: (low/med) __LOW__

Date Received: __12/01/90

% Moisture: not dec. _____ dec. _____

Date Extracted: __12/05/90

Extraction: (SepF/Cont/Sonc) ____CONT

Date Analyzed: __01/05/91

GPC Cleanup: (Y/N) __N__ pH: ____

Dilution Factor: 1.0

CAS NO.	COMPOUND	CONCENTRATION UNITS:	
		(ug/L or ug/Kg)_UG/L	Q
319-84-6	alpha-BHC	0.05	1U
319-85-7	beta-BHC	0.05	1U
319-86-8	delta-BHC	0.05	1U
58-89-9	gamma-BHC (Lindane)	0.05	1U
76-44-8	Heptachlor	0.05	1U
309-00-2	Aldrin	0.05	1U
1024-57-3	Heptachlor Epoxide	0.05	1U
959-98-8	Endosulfan I	0.05	1U
60-57-1	Dieldrin	0.10	1U
72-55-9	4,4'-DDE	0.10	1U
72-20-8	Endrin	0.10	1U
33213-65-9	Endosulfan II	0.10	1U
72-54-8	4,4'-DDD	0.10	1U
1031-07-8	Endosulfan Sulfate	0.10	1U
50-29-3	4,4'-DDT	0.10	1U
72-43-5	Methoxychlor	0.48	1U
53494-70-5	Endrin Ketone	0.10	1U
5103-71-9	alpha-Chlordane	0.48	1U
5103-74-2	gamma-Chlordane	0.48	1U
8001-35-2	Toxaphene	0.95	1U
12674-11-2	Aroclor-1016	0.48	1U
11104-28-2	Aroclor-1221	0.48	1U
11141-16-5	Aroclor-1232	0.48	1U
53469-21-9	Aroclor-1242	0.48	1U
12672-29-6	Aroclor-1248	0.48	1U
11097-69-1	Aroclor-1254	0.95	1U
11096-82-5	Aroclor-1260	0.95	1U

Jo
11/7/91

U.S. EPA - CLP

1
INORGANIC ANALYSES DATA SHEET

EPA SAMPLE NO.

MW-3GW

Lab Name: VERSAR LABORATORIES INC. Contract: 35216.03

Lab Code: VERSAR Case No.: 4014 SAS No.: SDG No.: E-1

Matrix (soil/water): WATER Lab Sample ID: 38798

Level (low/med): LOW Date Received: 12/01/90

% Solids: 0.0

Concentration Units (ug/L or mg/kg dry weight): UG/L

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum	8280	-		P
7440-36-0	Antimony	23.0	U		P
7440-38-2	Arsenic	3.2	B		F
7440-39-3	Barium	206			P
7440-41-7	Beryllium	1.0	U		P
7440-43-9	Cadmium	5.0	U		P
7440-70-2	Calcium	245000			P
7440-47-3	Chromium	5.0	U		P
7440-48-4	Cobalt	78.4			P
7440-50-8	Copper	59.5			P
7439-89-6	Iron	37700			P
7439-92-1	Lead	14.1			F
7439-95-4	Magnesium	96000			P
7439-96-5	Manganese	1710			P
7439-97-6	Mercury	0.20	U		CV
7440-02-0	Nickel	137			P
7440-09-7	Potassium	5600			P
7782-49-2	Selenium	30.0	U	WN	F
7440-22-4	Silver	4.6	B		P
7440-23-5	Sodium	178000			P
7440-28-0	Thallium	2.0	U		F
7440-62-2	Vanadium	31.0	B		P
7440-66-6	Zinc	83.8			P
	Cyanide	10.0	U		AS

Color Before: BROWN Clarity Before: OPAQUE Texture:

Color After: COLORLESS Clarity After: CLEAR Artifacts:

Comments:

THE CYANIDE LAB SAMPLE ID NUMBER IS 38807; THE EPA SAMPLE NUMBER
PREFIX IS "Q/L";

1A
VOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

QL-MW-4GW

L Name: VERSAR INC. Contract: _____
 Lab Code: VERSAR Case No.: 4022 SAS No.: _____ SDG No.: 3
 Matrix: (soil/water) WATER Lab Sample ID: 38768
 Sample wt/vol: 5.0 (g/mL) ML Lab File ID: Y5174
 Level: (low/med) LOW Date Received: 12/01/90
 % Moisture: not dec. _____ Date Analyzed: 12/07/90
 Column: (pack/cap) CAP Dilution Factor: 1.0

CAS NO. COMPOUND CONCENTRATION UNITS:
 (ug/L or ug/Kg) UG/L Q

74-87-3-----	Chloromethane	10	U
74-83-9-----	Bromomethane	10	U
75-01-4-----	Vinyl chloride	10	U
75-00-3-----	Chloroethane	10	U
75-09-2-----	Methylene chloride	8	B
67-64-1-----	Acetone	10	U
75-15-0-----	Carbon disulfide	5	U
75-35-4-----	1,1-Dichloroethene	5	U
75-34-3-----	1,1-Dichloroethane	5	U
540-59-0-----	1,2-Dichloroethene (total)	5	U
67-66-3-----	Chloroform	5	U
107-06-2-----	1,2-Dichloroethane	5	U
78-93-3-----	2-Butanone	10	U
71-55-6-----	1,1,1-Trichloroethane	5	U
56-23-5-----	Carbon tetrachloride	5	U
108-05-4-----	Vinyl acetate	10	U
75-27-4-----	Bromodichloromethane	5	U
78-87-5-----	1,2-Dichloropropane	5	U
10061-01-5-----	cis-1,3-Dichloropropene	5	U
79-01-6-----	Trichloroethene	5	U
124-48-1-----	Dibromochloromethane	5	U
79-00-5-----	1,1,2-Trichloroethane	5	U
71-43-2-----	Benzene	5	U
10061-02-6-----	Trans-1,3-dichloropropene	5	U
75-25-2-----	Bromoform	5	U
108-10-1-----	4-Methyl-2-pentanone	10	U
591-78-6-----	2-Hexanone	10	U
127-18-4-----	Tetrachloroethene	5	U
79-34-5-----	1,1,2,2-Tetrachloroethane	5	U
108-88-3-----	Toluene	5	U
108-90-7-----	Chlorobenzene	5	U
100-41-4-----	Ethylbenzene	5	U
100-42-5-----	Styrene	5	U
1330-20-7-----	Total xylenes	5	U

1E
VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

EPA SAMPLE NO.

QL-MW-4GW

Lab Name: VERSAR INC. Contract: _____

Lab Code: VERSAR Case No.: 4022 SAS No.: _____ SDG No.: 3

Matrix: (soil/water) WATER Lab Sample ID: 38768

Sample wt/vol: 5.0 (g/mL) ML Lab File ID: Y5174

Level: (low/med) LOW Date Received: 12/01/90

% Moisture: not dec. _____ Date Analyzed: 12/07/90

Column (pack/cap) CAP Dilution Factor: 1.0

Number TICs found: 0 CONCENTRATION UNITS:
(ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
=====	=====	=====	=====	=====

1B
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

QLMW4GW

Name: VERSAR INC. Contract: _____

Lab Code: VERSAR Case No.: 4022A SAS No.: _____ SDG No.: B3

Matrix: (soil/water) WATER Lab Sample ID: 38779

Sample wt/vol: 1050 (g/mL) ML Lab File ID: T5504

Level: (low/med) LOW Date Received: 12/01/90

% Moisture: not dec. _____ dec. _____ Date Extracted: 12/05/90

Extraction: (SepF/Cont/Sonc) CONT Date Analyzed: 12/31/90

CPC Cleanup: (Y/N) N pH: _____ Dilution Factor: 1.00

CONCENTRATION UNITS:

CAS NO. COMPOUND (ug/L or ug/Kg) UG/L Q

108-95-2-----	Phenol	10	U
111-44-4-----	bis(2-Chloroethyl) ether	10	U
95-57-8-----	2-Chlorophenol	10	U
541-73-1-----	1,3-Dichlorobenzene	10	U
106-46-7-----	1,4-Dichlorobenzene	10	U
100-51-6-----	Benzyl alcohol	10	U
95-50-1-----	1,2-Dichlorobenzene	10	U
95-48-7-----	2-Methylphenol	10	U
108-60-1-----	bis(2-Chloroisopropyl) ether	10	U
106-44-5-----	4-Methylphenol	10	U
621-64-7-----	N-Nitroso-di-n-propylamine	10	U
67-72-1-----	Hexachloroethane	10	U
98-95-3-----	Nitrobenzene	10	U
78-59-1-----	Isophorone	10	U
88-75-5-----	2-Nitrophenol	10	U
105-67-9-----	2,4-Dimethylphenol	10	U
65-85-0-----	Benzoic Acid	48	U
111-91-1-----	bis(2-Chloroethoxy) methane	10	U
120-83-2-----	2,4-Dichlorophenol	10	U
120-82-1-----	1,2,4-Trichlorobenzene	10	U
91-20-3-----	Naphthalene	10	U
106-47-8-----	4-Chloroaniline	10	U
87-68-3-----	Hexachlorobutadiene	10	U
59-50-7-----	4-Chloro-3-methylphenol	10	U
91-57-6-----	2-Methylnaphthalene	10	U
77-47-4-----	Hexachlorocyclopentadiene	10	U
88-06-2-----	2,4,6-Trichlorophenol	10	U
95-95-4-----	2,4,5-Trichlorophenol	48	U
91-58-7-----	2-Chloronaphthalene	10	U
88-74-4-----	2-Nitroaniline	48	U
131-11-3-----	Dimethylphthalate	10	U
208-96-8-----	Acenaphthylene	10	U
606-20-2-----	2,6-Dinitrotoluene	10	U

1C
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

QLMW4GW

L Name: VERSAR INC. Contract: _____

Lab Code: VERSAR Case No.: 4022A SAS No.: _____ SDG No.: B3

Matrix: (soil/water) WATER Lab Sample ID: 38779

Sample wt/vol: 1050 (g/mL) ML Lab File ID: T5504

Level: (low/med) LOW Date Received: 12/01/90

% Moisture: not dec. _____ dec. _____ Date Extracted: 12/05/90

Extraction: (SepF/Cont/Sonc) CONT Date Analyzed: 12/31/90

GPC Cleanup: (Y/N) N pH: _____ Dilution Factor: 1.00

CONCENTRATION UNITS:

CAS NO. COMPOUND (ug/L or ug/Kg) UG/L Q

99-09-2-----3-Nitroaniline	48	U
83-32-9-----Acenaphthene	10	U
51-28-5-----2,4-Dinitrophenol	48	U
100-02-7-----4-Nitrophenol	48	U
132-64-9-----Dibenzofuran	10	U
121-14-2-----2,4-Dinitrotoluene	10	U
84-66-2-----Diethylphthalate	10	U
7005-72-3-----4-Chlorophenyl-phenylether	10	U
86-73-7-----Fluorene	10	U
100-01-6-----4-Nitroaniline	48	U
534-52-1-----4,6-Dinitro-2-methylphenol	48	U
86-30-6-----N-nitrosodiphenylamine (1)	10	U
101-55-3-----4-Bromophenyl-phenylether	10	U
118-74-1-----Hexachlorobenzene	10	U
87-86-5-----Pentachlorophenol	48	U
85-01-8-----Phenanthrene	10	U
120-12-7-----Anthracene	10	U
84-74-2-----Di-n-butylphthalate	10	U
206-44-0-----Fluoranthene	10	U
129-00-0-----Pyrene	10	U
85-68-7-----Butylbenzylphthalate	10	U
91-94-1-----3,3'-Dichlorobenzidine	19	U
56-55-3-----Benzo(a)anthracene	10	U
218-01-9-----Chrysene	10	U
117-81-7-----bis(2-Ethylhexyl)phthalate	10	U
117-84-0-----Di-n-octyl phthalate	10	U
205-99-2-----Benzo(b)fluoranthene	10	U
207-08-9-----Benzo(k)fluoranthene	10	U
50-32-8-----Benzo(a)pyrene	10	U
193-39-5-----Indeno(1,2,3-cd)pyrene	10	U
53-70-3-----Dibenz(a,h)anthracene	10	U
191-24-2-----Benzo(g,h,i)perylene	10	U

(1) - Cannot be separated from Diphenylamine

1F
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

EPA SAMPLE NO.

QLMW4GW

I Name: VERSAR INC. Contract: _____

Lab Code: VERSAR Case No.: 4022A SAS No.: _____ SDG No.: B3

Matrix: (soil/water) WATER Lab Sample ID: 38779

Sample wt/vol: 1050 (g/mL) ML Lab File ID: T5504

Level: (low/med) LOW Date Received: 12/01/90

% Moisture: not dec. _____ dec. _____ Date Extracted: 12/05/90

Extraction: (SepF/Cont/Sonc) CONT Date Analyzed: 12/31/90

GPC Cleanup: (Y/N) N pH: _____ Dilution Factor: 1.00

Number TICs found: 4 CONCENTRATION UNITS:
(ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1.	UNKNOWN	3.37	42	BJ
2.	UNKNOWN	3.58	25	BJ
3.	UNKNOWN	4.48	9.5	J
4.	UNKNOWN	17.74	17	J

1D
PESTICIDE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

QLMW4GW

Lab Name: _____ VERSAR, INC. _____ Contract: _____

Code: VERSAR Case No.: URSQUEEN SAS No.: _____ SDG No.: _____

Matrix: (soil/water) WATER Lab Sample ID: __38789

Sample wt/vol: 1050 (g/ml) ML Lab File ID: ____

Level: (low/med) __LOW__ Date Received: __12/01/90

% Moisture: not dec. _____ dec. _____ Date Extracted: __12/05/90

Extraction: (SepF/Cont/Sonc) ____CONT Date Analyzed: __01/05/91

GPC Cleanup: (Y/N) __N__ pH: ____ Dilution Factor: 1.0

CONCENTRATION UNITS:
(ug/L or ug/Kg) _UG/L

CAS NO.	COMPOUND	Q
319-84-6	alpha-BHC	0.05 IU
319-85-7	beta-BHC	0.05 IU
319-86-8	delta-BHC	0.05 IU
58-89-9	gamma-BHC (Lindane)	0.05 IU
76-44-8	Heptachlor	0.05 IU
309-00-2	Aldrin	0.05 IU
1024-57-3	Heptachlor Epoxide	0.05 IU
959-98-8	Endosulfan I	0.05 IU
60-57-1	Dieldrin	0.10 IU
72-55-9	4,4'-DDE	0.10 IU
72-20-8	Endrin	0.10 IU
33213-65-9	Endosulfan II	0.10 IU
72-54-8	4,4'-DDD	0.10 IU
1031-07-8	Endosulfan Sulfate	0.10 IU
50-29-3	4,4'-DDT	0.10 IU
72-43-5	Methoxychlor	0.48 IU
53494-70-5	Endrin Ketone	0.10 IU
5103-71-9	alpha-Chlordane	0.48 IU
5103-74-2	gamma-Chlordane	0.48 IU
8001-35-2	Toxaphene	0.95 IU
12674-11-2	Aroclor-1016	0.48 IU
11104-28-2	Aroclor-1221	0.48 IU
11141-16-5	Aroclor-1232	0.48 IU
53469-21-9	Aroclor-1242	0.48 IU
12672-29-6	Aroclor-1248	0.48 IU
11097-69-1	Aroclor-1254	0.95 IU
11096-82-5	Aroclor-1260	0.95 IU

ja
1/10/91

U.S. EPA - CLP

1
INORGANIC ANALYSES DATA SHEET

EPA SAMPLE NO.

MW-4GW

Lab Name: VERSAR LABORATORIES INC. _____ Contract: 35216.03 _____

Lab Code: VERSAR Case No.: 4014 _____ SAS No.: _____ SDG No.: E-1 _____

Matrix (soil/water): WATER _____ Lab Sample ID: 38799 _____

Level (low/med): LOW _____ Date Received: 12/01/90

% Solids: _____ 0.0

Concentration Units (ug/L or mg/kg dry weight): UG/L

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum	1720	—		P
7440-36-0	Antimony	23.0	U		P
7440-38-2	Arsenic	13.1	—		F
7440-39-3	Barium	407	—		P
7440-41-7	Beryllium	1.8	B		P
7440-43-9	Cadmium	5.0	U		P
7440-70-2	Calcium	156000	—		P
7440-47-3	Chromium	5.0	U		P
7440-48-4	Cobalt	8.7	B		P
7440-50-8	Copper	10.1	B		P
7439-89-6	Iron	21000	—		P
7439-92-1	Lead	3.1	—		F
7439-95-4	Magnesium	34500	—		P
7439-96-5	Manganese	518	—		P
7439-97-6	Mercury	0.20	U		CV
7440-02-0	Nickel	13.0	U		P
7440-09-7	Potassium	9810	—		P
7782-49-2	Selenium	30.0	U	N	F
7440-22-4	Silver	3.0	U		P
7440-23-5	Sodium	51800	—		P
7440-28-0	Thallium	2.0	U		F
7440-62-2	Vanadium	8.2	B		P
7440-66-6	Zinc	19.6	B		P
	Cyanide	10.0	U		AS

Color Before: GREY _____ Clarity Before: CLOUDY Texture: _____

Color After: COLORLESS Clarity After: CLEAR _____ Artifacts: _____

Comments:

THE CYANIDE LAB SAMPLE ID NUMBER IS 38808; THE EPA SAMPLE NUMBER _____

PREFIX IS "Q/L"; _____

1A
VOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

QLMW5GW

Name: VERSAR INC. Contract: _____

Lab Code: VERSAR Case No.: 4014A SAS No.: _____ SDG No.: B2

Matrix: (soil/water) WATER Lab Sample ID: 38588

Sample wt/vol: 5.0 (g/mL) ML Lab File ID: S1248

Level: (low/med) LOW Date Received: 11/30/90

% Moisture: not dec. _____ Date Analyzed: 12/06/90

Column: (pack/cap) CAP Dilution Factor: 1.0

CAS NO. COMPOUND CONCENTRATION UNITS:
(ug/L or ug/Kg) UG/L Q

74-87-3-----	Chloromethane	10	U
74-83-9-----	Bromomethane	10	U
75-01-4-----	Vinyl chloride	10	U
75-00-3-----	Chloroethane	10	U
75-09-2-----	Methylene chloride	5	U
67-64-1-----	Acetone	10	U
75-15-0-----	Carbon disulfide	5	U
75-35-4-----	1,1-Dichloroethene	5	U
75-34-3-----	1,1-Dichloroethane	5	U
540-59-0-----	1,2-Dichloroethene (total)	5	U
67-66-3-----	Chloroform	5	U
107-06-2-----	1,2-Dichloroethane	5	U
78-93-3-----	2-Butanone	10	U
71-55-6-----	1,1,1-Trichloroethane	5	U
56-23-5-----	Carbon tetrachloride	5	U
108-05-4-----	Vinyl acetate	10	U
75-27-4-----	Bromodichloromethane	5	U
78-87-5-----	1,2-Dichloropropane	5	U
10061-01-5-----	cis-1,3-Dichloropropene	5	U
79-01-6-----	Trichloroethene	5	U
124-48-1-----	Dibromochloromethane	5	U
79-00-5-----	1,1,2-Trichloroethane	5	U
71-43-2-----	Benzene	5	U
10061-02-6-----	Trans-1,3-dichloropropene	5	U
75-25-2-----	Bromoform	5	U
108-10-1-----	4-Methyl-2-pentanone	10	U
591-78-6-----	2-Hexanone	10	U
127-18-4-----	Tetrachloroethene	5	U
79-34-5-----	1,1,2,2-Tetrachloroethane	5	U
108-88-3-----	Toluene	5	U
108-90-7-----	Chlorobenzene	5	U
100-41-4-----	Ethylbenzene	5	U
100-42-5-----	Styrene	5	U
1330-20-7-----	Total xylenes	5	U

1E
VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

EPA SAMPLE NO.

QLMW5GW

Name: VERSAR INC. Contract: _____

Lab Code: VERSAR Case No.: 4014A SAS No.: _____ SDG No.: B2

Matrix: (soil/water) WATER Lab Sample ID: 38588

Sample wt/vol: 5.0 (g/mL) ML Lab File ID: S1248

Level: (low/med) LOW Date Received: 11/30/90

% Moisture: not dec. _____ Date Analyzed: 12/06/90

Column (pack/cap) CAP Dilution Factor: 1.0

Number TICs found: 0 CONCENTRATION UNITS:
(ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
=====	=====	=====	=====	=====

1B
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

QLMW5GW

I Name: VERSAR INC. Contract: _____

Lab Code: VERSAR Case No.: 4014 SAS No.: _____ SDG No.: 2

Matrix: (soil/water) WATER Lab Sample ID: 38593

Sample wt/vol: 1050 (g/mL) ML Lab File ID: Z6890

Level: (low/med) LOW Date Received: 11/30/90

% Moisture: not dec. _____ dec. _____ Date Extracted: 12/03/90

Extraction: (SepF/Cont/Sonc) CONT Date Analyzed: 12/14/90

GPC Cleanup: (Y/N) N pH: _____ Dilution Factor: 1.00

CONCENTRATION UNITS:
(ug/L or ug/Kg) UG/L

CAS NO. COMPOUND Q

108-95-2-----	Phenol	10	U
111-44-4-----	bis(2-Chloroethyl) ether	10	U
95-57-8-----	2-Chlorophenol	10	U
541-73-1-----	1,3-Dichlorobenzene	10	U
106-46-7-----	1,4-Dichlorobenzene	10	U
100-51-6-----	Benzyl alcohol	10	U
95-50-1-----	1,2-Dichlorobenzene	10	U
95-48-7-----	2-Methylphenol	10	U
108-60-1-----	bis(2-Chloroisopropyl) ether	10	U
106-44-5-----	4-Methylphenol	10	U
621-64-7-----	N-Nitroso-di-n-propylamine	10	U
67-72-1-----	Hexachloroethane	10	U
98-95-3-----	Nitrobenzene	10	U
78-59-1-----	Isophorone	10	U
88-75-5-----	2-Nitrophenol	10	U
105-67-9-----	2,4-Dimethylphenol	10	U
65-85-0-----	Benzoic Acid	48	U
111-91-1-----	bis(2-Chloroethoxy) methane	10	U
120-83-2-----	2,4-Dichlorophenol	10	U
120-82-1-----	1,2,4-Trichlorobenzene	10	U
91-20-3-----	Naphthalene	10	U
106-47-8-----	4-Chloroaniline	10	U
87-68-3-----	Hexachlorobutadiene	10	U
59-50-7-----	4-Chloro-3-methylphenol	10	U
91-57-6-----	2-Methylnaphthalene	10	U
77-47-4-----	Hexachlorocyclopentadiene	10	U
88-06-2-----	2,4,6-Trichlorophenol	10	U
95-95-4-----	2,4,5-Trichlorophenol	48	U
91-58-7-----	2-Chloronaphthalene	10	U
88-74-4-----	2-Nitroaniline	48	U
131-11-3-----	Dimethylphthalate	10	U
208-96-8-----	Acenaphthylene	10	U
606-20-2-----	2,6-Dinitrotoluene	10	U

1C
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

QLMW5GW

I Name: VERSAR INC. Contract: _____

Lab Code: VERSAR Case No.: 4014 SAS No.: _____ SDG No.: 2

Matrix: (soil/water) WATER Lab Sample ID: 38593

Sample wt/vol: 1050 (g/mL) ML Lab File ID: Z6890

Level: (low/med) LOW Date Received: 11/30/90

% Moisture: not dec. _____ dec. _____ Date Extracted: 12/03/90

Extraction: (SepF/Cont/Sonc) CONT Date Analyzed: 12/14/90

GPC Cleanup: (Y/N) N pH: _____ Dilution Factor: 1.00

CONCENTRATION UNITS:
(ug/L or ug/Kg) UG/L

CAS NO.	COMPOUND	Q
---------	----------	---

99-09-2-----	3-Nitroaniline	48	U
83-32-9-----	Acenaphthene	10	U
51-28-5-----	2,4-Dinitrophenol	48	U
100-02-7-----	4-Nitrophenol	48	U
132-64-9-----	Dibenzofuran	10	U
121-14-2-----	2,4-Dinitrotoluene	10	U
84-66-2-----	Diethylphthalate	10	U
7005-72-3-----	4-Chlorophenyl-phenylether	10	U
86-73-7-----	Fluorene	10	U
100-01-6-----	4-Nitroaniline	48	U
534-52-1-----	4,6-Dinitro-2-methylphenol	48	U
86-30-6-----	N-nitrosodiphenylamine (1)	10	U
101-55-3-----	4-Bromophenyl-phenylether	10	U
118-74-1-----	Hexachlorobenzene	10	U
87-86-5-----	Pentachlorophenol	48	U
85-01-8-----	Phenanthrene	10	U
120-12-7-----	Anthracene	10	U
84-74-2-----	Di-n-butylphthalate	10	U
206-44-0-----	Fluoranthene	10	U
129-00-0-----	Pyrene	10	U
85-68-7-----	Butylbenzylphthalate	10	U
91-94-1-----	3,3'-Dichlorobenzidine	19	U
56-55-3-----	Benzo(a)anthracene	10	U
218-01-9-----	Chrysene	10	U
117-81-7-----	bis(2-Ethylhexyl)phthalate	10	U
117-84-0-----	Di-n-octyl phthalate	10	U
205-99-2-----	Benzo(b)fluoranthene	10	U
207-08-9-----	Benzo(k)fluoranthene	10	U
50-32-8-----	Benzo(a)pyrene	10	U
193-39-5-----	Indeno(1,2,3-cd)pyrene	10	U
53-70-3-----	Dibenz(a,h)anthracene	10	U
191-24-2-----	Benzo(g,h,i)perylene	10	U

(1) - Cannot be separated from Diphenylamine

1F
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

EPA SAMPLE NO.

QLMW5GW

L Name: VERSAR INC. Contract: _____
Lab Code: VERSAR Case No.: 4014 SAS No.: _____ SDG No.: 2
Matrix: (soil/water) WATER Lab Sample ID: 38593
Sample wt/vol: 1050 (g/mL) ML Lab File ID: Z6890
Level: (low/med) LOW Date Received: 11/30/90
% Moisture: not dec. _____ dec. _____ Date Extracted: 12/03/90
Extraction: (SepF/Cont/Sonc) CONT Date Analyzed: 12/14/90
GPC Cleanup: (Y/N) N pH: _____ Dilution Factor: 1.00

Number TICs found: 4

CONCENTRATION UNITS:
(ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1.	UNKNOWN	3.72	9.5	J
2.	UNKNOWN	11.84	9.5	J
3.	UNKNOWN	16.84	9.5	J
1.	UNKNOWN	17.99	15	J

1D
PESTICIDE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

QLMW5GW

Lab Name: _____ VERSAR, INC. _____ Contract: _____

Lab Code: VERSAR Case No.: URSQUEEN SAS No.: _____ SDG No.: _____

Matrix: (soil/water) WATER Lab Sample ID: __38597

Sample wt/vol: 1050 (g/ml) ML Lab File ID: _____

Level: (low/med) __LOW__ Date Received: __11/30/90

Moisture: not dec. _____ dec. _____ Date Extracted: __12/03/90

Extraction: (SepF/Cont/Sonc) _____ CONT Date Analyzed: __12/30/90

GPC Cleanup: (Y/N) __N__ pH: _____ Dilution Factor: 1.0

CAS NO.	COMPOUND	CONCENTRATION UNITS: (ug/L or ug/Kg) _UG/L	Q
319-84-6	alpha-BHC	0.05	1U
319-85-7	beta-BHC	0.05	1U
319-86-8	delta-BHC	0.05	1U
58-89-9	gamma-BHC (Lindane)	0.05	1U
76-44-8	Heptachlor	0.05	1U
309-00-2	Aldrin	0.05	1U
1024-57-3	Heptachlor Epoxide	0.05	1U
959-98-8	Endosulfan I	0.05	1U
60-57-1	Dieldrin	0.10	1U
72-55-9	4,4'-DDE	0.10	1U
72-20-8	Endrin	0.10	1U
33213-65-9	Endosulfan II	0.10	1U
72-54-8	4,4'-DDD	0.10	1U
1031-07-8	Endosulfan Sulfate	0.10	1U
50-29-3	4,4'-DDT	0.10	1U
72-43-5	Methoxychlor	0.48	1U
53494-70-5	Endrin Ketone	0.10	1U
5103-71-9	alpha-Chlordane	0.48	1U
5103-74-2	gamma-Chlordane	0.48	1U
8001-35-2	Toxaphene	0.95	1U
12674-11-2	Aroclor-1016	0.48	1U
11104-28-2	Aroclor-1221	0.48	1U
11141-16-5	Aroclor-1232	0.48	1U
53469-21-9	Aroclor-1242	0.48	1U
12672-29-6	Aroclor-1248	0.48	1U
11097-69-1	Aroclor-1254	0.95	1U
11096-82-5	Aroclor-1260	0.95	1U

U.S. EPA - CLP

1
INORGANIC ANALYSES DATA SHEET

EPA SAMPLE NO.

MW-5 GW

Lab Name: VERSAR LABORATORIES INC. Contract: 35216.03

Lab Code: VERSAR Case No.: 4014 SAS No.: SDG No.: E-1

Matrix (soil/water): WATER Lab Sample ID: 38601

Level (low/med): LOW Date Received: 11/30/90

% Solids: 0.0

Concentration Units (ug/L or mg/kg dry weight): UG/L

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum	599	-		P
7440-36-0	Antimony	23.0	U		P
7440-38-2	Arsenic	3.0	U		F
7440-39-3	Barium	38.0	B		P
7440-41-7	Beryllium	4.9	B		P
7440-43-9	Cadmium	5.5	-		P
7440-70-2	Calcium	75300	U		P
7440-47-3	Chromium	5.0	U		P
7440-48-4	Cobalt	8.0	U		P
7440-50-8	Copper	4.9	B		P
7439-89-6	Iron	1800	-		P
7439-92-1	Lead	2.5	B	W	F
7439-95-4	Magnesium	19200	-		P
7439-96-5	Manganese	42.0	-		P
7439-97-6	Mercury	0.20	U		CV
7440-02-0	Nickel	13.0	U		P
7440-09-7	Potassium	1280	B		P
7782-49-2	Selenium	3.0	U	WN	F
7440-22-4	Silver	3.0	U		P
7440-23-5	Sodium	14800	-		P
7440-28-0	Thallium	10.0	U		F
7440-62-2	Vanadium	5.0	U		P
7440-66-6	Zinc	15.7	B		P
	Cyanide	10.0	U		AS

Color Before: COLORLESS Clarity Before: CLEAR Texture:

Color After: COLORLESS Clarity After: CLEAR Artifacts:

Comments:

THE CYANIDE LAB SAMPLE ID NUMBER IS 38605; THE EPA SAMPLE NUMBER
PREFIX IS "Q/L";

1A
VOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

QLE1GW

Lab Name: VERSAR INC. Contract: _____

Lab Code: VERSAR Case No.: 4014A SAS No.: _____ SDG No.: B2

Matrix: (soil/water) WATER Lab Sample ID: 38590

Sample wt/vol: 5.0 (g/mL) ML Lab File ID: S1246

Level: (low/med) LOW Date Received: 11/30/90

% Moisture: not dec. _____ Date Analyzed: 12/06/90

Column: (pack/cap) CAP Dilution Factor: 1.0

CAS NO. COMPOUND CONCENTRATION UNITS:
(ug/L or ug/Kg) UG/L Q

74-87-3-----	Chloromethane	10	U
74-83-9-----	Bromomethane	10	U
75-01-4-----	Vinyl chloride	10	U
75-00-3-----	Chloroethane	10	U
75-09-2-----	Methylene chloride	5	U
67-64-1-----	Acetone	10	U
75-15-0-----	Carbon disulfide	5	U
75-35-4-----	1,1-Dichloroethene	5	U
75-34-3-----	1,1-Dichloroethane	5	U
540-59-0-----	1,2-Dichloroethene (total)	5	U
67-66-3-----	Chloroform	5	U
107-06-2-----	1,2-Dichloroethane	5	U
78-93-3-----	2-Butanone	10	U
71-55-6-----	1,1,1-Trichloroethane	5	U
56-23-5-----	Carbon tetrachloride	5	U
108-05-4-----	Vinyl acetate	10	U
75-27-4-----	Bromodichloromethane	5	U
78-87-5-----	1,2-Dichloropropane	5	U
10061-01-5-----	cis-1,3-Dichloropropene	5	U
79-01-6-----	Trichloroethene	5	U
124-48-1-----	Dibromochloromethane	5	U
79-00-5-----	1,1,2-Trichloroethane	5	U
71-43-2-----	Benzene	5	U
10061-02-6-----	Trans-1,3-dichloropropene	5	U
75-25-2-----	Bromoform	5	U
108-10-1-----	4-Methyl-2-pentanone	10	U
591-78-6-----	2-Hexanone	10	U
127-18-4-----	Tetrachloroethene	5	U
79-34-5-----	1,1,2,2-Tetrachloroethane	5	U
108-88-3-----	Toluene	5	U
108-90-7-----	Chlorobenzene	5	U
100-41-4-----	Ethylbenzene	5	U
100-42-5-----	Styrene	5	U
1330-20-7-----	Total xylenes	5	U

1E
VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

EPA SAMPLE NO.

QLE1GW

Lab Name: VERSAR INC. Contract: _____

Lab Code: VERSAR Case No.: 4014A SAS No.: _____ SDG No.: B2

Matrix: (soil/water) WATER Lab Sample ID: 38590

Sample wt/vol: 5.0 (g/mL) ML Lab File ID: S1246

Level: (low/med) LOW Date Received: 11/30/90

% Moisture: not dec. _____ Date Analyzed: 12/06/90

Column (pack/cap) CAP Dilution Factor: 1.0

Number TICs found: 0 CONCENTRATION UNITS:
(ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
=====	=====	=====	=====	=====

1B
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

QLE1GW

L Name: VERSAR INC. Contract: _____

Lab Code: VERSAR Case No.: 4014 SAS No.: _____ SDG No.: 2

Matrix: (soil/water) WATER Lab Sample ID: 38595

Sample wt/vol: 1050 (g/mL) ML Lab File ID: Z6892

Level: (low/med) LOW Date Received: 11/30/90

% Moisture: not dec. _____ dec. _____ Date Extracted: 12/03/90

Extraction: (SepF/Cont/Sonc) CONT Date Analyzed: 12/14/90

GPC Cleanup: (Y/N) N pH: _____ Dilution Factor: 1.00

CONCENTRATION UNITS:
(ug/L or ug/Kg) UG/L

CAS NO.	COMPOUND	Q
---------	----------	---

108-95-2-----	Phenol	10	U
111-44-4-----	bis(2-Chloroethyl)ether	10	U
95-57-8-----	2-Chlorophenol	10	U
541-73-1-----	1,3-Dichlorobenzene	10	U
106-46-7-----	1,4-Dichlorobenzene	10	U
100-51-6-----	Benzyl alcohol	10	U
95-50-1-----	1,2-Dichlorobenzene	10	U
95-48-7-----	2-Methylphenol	10	U
108-60-1-----	bis(2-Chloroisopropyl) ether	10	U
106-44-5-----	4-Methylphenol	10	U
621-64-7-----	N-Nitroso-di-n-propylamine	10	U
67-72-1-----	Hexachloroethane	10	U
98-95-3-----	Nitrobenzene	10	U
78-59-1-----	Isophorone	10	U
88-75-5-----	2-Nitrophenol	10	U
105-67-9-----	2,4-Dimethylphenol	10	U
65-85-0-----	Benzoic Acid	48	U
111-91-1-----	bis(2-Chloroethoxy)methane	10	U
120-83-2-----	2,4-Dichlorophenol	10	U
120-82-1-----	1,2,4-Trichlorobenzene	10	U
91-20-3-----	Naphthalene	10	U
106-47-8-----	4-Chloroaniline	10	U
87-68-3-----	Hexachlorobutadiene	10	U
59-50-7-----	4-Chloro-3-methylphenol	10	U
91-57-6-----	2-Methylnaphthalene	10	U
77-47-4-----	Hexachlorocyclopentadiene	10	U
88-06-2-----	2,4,6-Trichlorophenol	10	U
95-95-4-----	2,4,5-Trichlorophenol	48	U
91-58-7-----	2-Chloronaphthalene	10	U
88-74-4-----	2-Nitroaniline	48	U
131-11-3-----	Dimethylphthalate	10	U
208-96-8-----	Acenaphthylene	10	U
606-20-2-----	2,6-Dinitrotoluene	10	U

1C
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

QLE1GW

L Name: VERSAR INC. Contract: _____

Lab Code: VERSAR Case No.: 4014 SAS No.: _____ SDG No.: 2

Matrix: (soil/water) WATER Lab Sample ID: 38595

Sample wt/vol: 1050 (g/mL) ML Lab File ID: Z6892

Level: (low/med) LOW Date Received: 11/30/90

% Moisture: not dec. _____ dec. _____ Date Extracted: 12/03/90

Extraction: (SepF/Cont/Sonc) CONT Date Analyzed: 12/14/90

GPC Cleanup: (Y/N) N pH: _____ Dilution Factor: 1.00

CONCENTRATION UNITS:
(ug/L or ug/Kg) UG/L

CAS NO.	COMPOUND	Q
---------	----------	---

99-09-2-----	3-Nitroaniline	48	U
83-32-9-----	Acenaphthene	10	U
51-28-5-----	2,4-Dinitrophenol	48	U
100-02-7-----	4-Nitrophenol	48	U
132-64-9-----	Dibenzofuran	10	U
121-14-2-----	2,4-Dinitrotoluene	10	U
84-66-2-----	Diethylphthalate	10	U
7005-72-3-----	4-Chlorophenyl-phenylether	10	U
86-73-7-----	Fluorene	10	U
100-01-6-----	4-Nitroaniline	48	U
534-52-1-----	4,6-Dinitro-2-methylphenol	48	U
86-30-6-----	N-nitrosodiphenylamine (1)	10	U
101-55-3-----	4-Bromophenyl-phenylether	10	U
118-74-1-----	Hexachlorobenzene	10	U
87-86-5-----	Pentachlorophenol	48	U
85-01-8-----	Phenanthrene	10	U
120-12-7-----	Anthracene	10	U
84-74-2-----	Di-n-butylphthalate	10	U
206-44-0-----	Fluoranthene	10	U
129-00-0-----	Pyrene	10	U
85-68-7-----	Butylbenzylphthalate	10	U
91-94-1-----	3,3'-Dichlorobenzidine	19	U
56-55-3-----	Benzo(a)anthracene	10	U
218-01-9-----	Chrysene	10	U
117-81-7-----	bis(2-Ethylhexyl)phthalate	10	U
117-84-0-----	Di-n-octyl phthalate	10	U
205-99-2-----	Benzo(b)fluoranthene	10	U
207-08-9-----	Benzo(k)fluoranthene	10	U
50-32-8-----	Benzo(a)pyrene	10	U
193-39-5-----	Indeno(1,2,3-cd)pyrene	10	U
53-70-3-----	Dibenz(a,h)anthracene	10	U
191-24-2-----	Benzo(g,h,i)perylene	10	U

(1) - Cannot be separated from Diphenylamine

200012

1F
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

EPA SAMPLE NO.

QLE1GW

L Name: VERSAR INC. Contract: _____
Lab Code: VERSAR Case No.: 4014 SAS No.: _____ SDG No.: 2
Matrix: (soil/water) WATER Lab Sample ID: 38595
Sample wt/vol: 1050 (g/mL) ML Lab File ID: 26892
Level: (low/med) LOW Date Received: 11/30/90
% Moisture: not dec. _____ dec. _____ Date Extracted: 12/03/90
Extraction: (SepF/Cont/Sonc) CONT Date Analyzed: 12/14/90
GPC Cleanup: (Y/N) N pH: _____ Dilution Factor: 1.00

Number TICs found: 1

CONCENTRATION UNITS:
(ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1.	UNKNOWN	3.72	13	J

1D
PESTICIDE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

QLE1

Name: _____ VERSAR, INC. _____ Contract: _____

Lab Code: VERSAR Case No.: URSQUEEN SAS No.: _____ SDG No.: _____

Matrix: (soil/water) WATER Lab Sample ID: __38599

Sample wt/vol: 1050 (g/ml) ML Lab File ID: _____

Level: (low/med) __LOW__ Date Received: __11/30/90

% Moisture: not dec. _____ dec. _____ Date Extracted: __12/03/90

Extraction: (SepF/Cont/Sonc) _____ CONT Date Analyzed: __12/30/90

GPC Cleanup: (Y/N) __N__ pH: _____ Dilution Factor: 1.0

CAS NO.	COMPOUND	CONCENTRATION UNITS: (ug/L or ug/Kg) _UG/L	Q
319-84-6	alpha-BHC	0.05	IU
319-85-7	beta-BHC	0.05	IU
319-86-8	delta-BHC	0.05	IU
58-89-9	gamma-BHC (Lindane)	0.05	IU
76-44-8	Heptachlor	0.05	IU
309-00-2	Aldrin	0.05	IU
1024-57-3	Heptachlor Epoxide	0.05	IU
959-98-8	Endosulfan I	0.05	IU
60-57-1	Dieldrin	0.10	IU
72-55-9	4,4'-DDE	0.10	IU
72-20-8	Endrin	0.10	IU
33213-65-9	Endosulfan II	0.10	IU
72-54-8	4,4'-DDD	0.10	IU
1031-07-8	Endosulfan Sulfate	0.10	IU
50-29-3	4,4'-DDT	0.10	IU
72-43-5	Methoxychlor	0.48	IU
53494-70-5	Endrin Ketone	0.10	IU
5103-71-9	alpha-Chlordane	0.48	IU
5103-74-2	gamma-Chlordane	0.48	IU
8001-35-2	Toxaphene	0.95	IU
12674-11-2	Aroclor-1016	0.48	IU
11104-28-2	Aroclor-1221	0.48	IU
11141-16-5	Aroclor-1232	0.48	IU
53469-21-9	Aroclor-1242	0.48	IU
12672-29-6	Aroclor-1248	0.48	IU
11097-69-1	Aroclor-1254	0.95	IU
11096-82-5	Aroclor-1260	0.95	IU

1/3/91

U.S. EPA - CLP

1
INORGANIC ANALYSES DATA SHEET

EPA SAMPLE NO.

E-1 GW

Lab Name: VERSAR LABORATORIES INC. Contract: 35216.03

Lab Code: VERSAR Case No.: 4014 SAS No.: SDG No.: E-1

Matrix (soil/water): WATER Lab Sample ID: 38603

Level (low/med): LOW Date Received: 11/30/90

% Solids: 0.0

Concentration Units (ug/L or mg/kg dry weight): UG/L

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum	10.0	U		P
7440-36-0	Antimony	23.0	U		P
7440-38-2	Arsenic	3.0	U		F
7440-39-3	Barium	477			P
7440-41-7	Beryllium	4.9	B		P
7440-43-9	Cadmium	5.5			P
7440-70-2	Calcium	33300			P
7440-47-3	Chromium	5.0	U		P
7440-48-4	Cobalt	8.0	U		P
7440-50-8	Copper	5.3	B		P
7439-89-6	Iron	149			P
7439-92-1	Lead	1.0	U		F
7439-95-4	Magnesium	16500			P
7439-96-5	Manganese	13.9	B		P
7439-97-6	Mercury	0.20	U		CV
7440-02-0	Nickel	13.0	U		P
7440-09-7	Potassium	503	U		P
7782-49-2	Selenium	3.0	U	WN	F
7440-22-4	Silver	3.0	U		P
7440-23-5	Sodium	17800			P
7440-28-0	Thallium	10.0	U		F
7440-62-2	Vanadium	5.0	U		P
7440-66-6	Zinc	108			P
	Cyanide	10.0	U		AS

Color Before: COLORLESS Clarity Before: CLEAR Texture:

Color After: COLORLESS Clarity After: CLEAR Artifacts:

Comments:

THE CYANIDE LAB SAMPLE ID NUMBER IS 38607; THE EPA SAMPLE NUMBER
PREFIX IS "Q/L";

1A
VOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

QL-E-2GW

L Name: VERSAR INC. Contract: _____

Lab Code: VERSAR Case No.: 4022 SAS No.: _____ SDG No.: 3

Matrix: (soil/water) WATER Lab Sample ID: 38771

Sample wt/vol: 5.0 (g/mL) ML Lab File ID: Y5176

Level: (low/med) LOW Date Received: 12/01/90

% Moisture: not dec. _____ Date Analyzed: 12/07/90

Column: (pack/cap) CAP Dilution Factor: 1.0

CAS NO. COMPOUND CONCENTRATION UNITS:
(ug/L or ug/Kg) UG/L Q

74-87-3-----	Chloromethane	10	U
74-83-9-----	Bromomethane	10	U
75-01-4-----	Vinyl chloride	10	U
75-00-3-----	Chloroethane	10	U
75-09-2-----	Methylene chloride	9	B
67-64-1-----	Acetone	10	U
75-15-0-----	Carbon disulfide	5	U
75-35-4-----	1,1-Dichloroethene	5	U
75-34-3-----	1,1-Dichloroethane	5	U
540-59-0-----	1,2-Dichloroethene (total)	5	U
67-66-3-----	Chloroform	5	U
107-06-2-----	1,2-Dichloroethane	5	U
78-93-3-----	2-Butanone	10	U
71-55-6-----	1,1,1-Trichloroethane	5	U
56-23-5-----	Carbon tetrachloride	5	U
108-05-4-----	Vinyl acetate	10	U
75-27-4-----	Bromodichloromethane	5	U
78-87-5-----	1,2-Dichloropropane	5	U
10061-01-5-----	cis-1,3-Dichloropropene	5	U
79-01-6-----	Trichloroethene	5	U
124-48-1-----	Dibromochloromethane	5	U
79-00-5-----	1,1,2-Trichloroethane	5	U
71-43-2-----	Benzene	5	U
10061-02-6-----	Trans-1,3-dichloropropene	5	U
75-25-2-----	Bromoform	5	U
108-10-1-----	4-Methyl-2-pentanone	10	U
591-78-6-----	2-Hexanone	10	U
127-18-4-----	Tetrachloroethene	5	U
79-34-5-----	1,1,2,2-Tetrachloroethane	5	U
108-88-3-----	Toluene	5	U
108-90-7-----	Chlorobenzene	5	U
100-41-4-----	Ethylbenzene	5	U
100-42-5-----	Styrene	5	U
1330-20-7-----	Total xylenes	5	U

1E
VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

EPA SAMPLE NO.

QL-E-2GW

L Name: VERSAR INC. Contract: _____
Lab Code: VERSAR Case No.: 4022 SAS No.: _____ SDG No.: 3
Matrix: (soil/water) WATER Lab Sample ID: 38771
Sample wt/vol: 5.0 (g/mL) ML Lab File ID: Y5176
Level: (low/med) LOW Date Received: 12/01/90
% Moisture: not dec. _____ Date Analyzed: 12/07/90
Column (pack/cap) CAP Dilution Factor: 1.0

Number TICs found: 0

CONCENTRATION UNITS:
(ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
=====	=====	=====	=====	=====

1B
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

QLE2GW

I Name: VERSAR INC. Contract: _____

Lab Code: VERSAR Case No.: 4022A SAS No.: _____ SDG No.: B3

Matrix: (soil/water) WATER Lab Sample ID: 38782

Sample wt/vol: 1050 (g/mL) ML Lab File ID: T5512

Level: (low/med) LOW Date Received: 12/01/90

% Moisture: not dec. _____ dec. _____ Date Extracted: 12/05/90

Extraction: (SepF/Cont/Sonc) CONT Date Analyzed: 01/02/91

GPC Cleanup: (Y/N) N pH: _____ Dilution Factor: 1.00

CONCENTRATION UNITS:

CAS NO. COMPOUND (ug/L or ug/Kg) UG/L Q

108-95-2-----	Phenol	10	U
111-44-4-----	bis(2-Chloroethyl) ether	10	U
95-57-8-----	2-Chlorophenol	10	U
541-73-1-----	1,3-Dichlorobenzene	10	U
106-46-7-----	1,4-Dichlorobenzene	10	U
100-51-6-----	Benzyl alcohol	10	U
95-50-1-----	1,2-Dichlorobenzene	10	U
95-48-7-----	2-Methylphenol	10	U
108-60-1-----	bis(2-Chloroisopropyl) ether	10	U
106-44-5-----	4-Methylphenol	10	U
621-64-7-----	N-Nitroso-di-n-propylamine	10	U
67-72-1-----	Hexachloroethane	10	U
98-95-3-----	Nitrobenzene	10	U
78-59-1-----	Isophorone	10	U
88-75-5-----	2-Nitrophenol	10	U
105-67-9-----	2,4-Dimethylphenol	10	U
65-85-0-----	Benzoic Acid	48	U
111-91-1-----	bis(2-Chloroethoxy) methane	10	U
120-83-2-----	2,4-Dichlorophenol	10	U
120-82-1-----	1,2,4-Trichlorobenzene	10	U
91-20-3-----	Naphthalene	10	U
106-47-8-----	4-Chloroaniline	10	U
87-68-3-----	Hexachlorobutadiene	10	U
59-50-7-----	4-Chloro-3-methylphenol	10	U
91-57-6-----	2-Methylnaphthalene	10	U
77-47-4-----	Hexachlorocyclopentadiene	10	U
88-06-2-----	2,4,6-Trichlorophenol	10	U
95-95-4-----	2,4,5-Trichlorophenol	48	U
91-58-7-----	2-Chloronaphthalene	10	U
88-74-4-----	2-Nitroaniline	48	U
131-11-3-----	Dimethylphthalate	10	U
208-96-8-----	Acenaphthylene	10	U
606-20-2-----	2,6-Dinitrotoluene	10	U

1C
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

QLE2GW

I Name: VERSAR INC. Contract: _____

Lab Code: VERSAR Case No.: 4022A SAS No.: _____ SDG No.: B3

Matrix: (soil/water) WATER Lab Sample ID: 38782

Sample wt/vol: 1050 (g/mL) ML Lab File ID: T5512

Level: (low/med) LOW Date Received: 12/01/90

% Moisture: not dec. _____ dec. _____ Date Extracted: 12/05/90

Extraction: (SepF/Cont/Sonc) CONT Date Analyzed: 01/02/91

GPC Cleanup: (Y/N) N pH: _____ Dilution Factor: 1.00

CONCENTRATION UNITS:
(ug/L or ug/Kg) UG/L Q

CAS NO.	COMPOUND	CONCENTRATION UNITS: (ug/L or ug/Kg) <u>UG/L</u>	Q
99-09-2-----	3-Nitroaniline	48	U
83-32-9-----	Acenaphthene	10	U
51-28-5-----	2,4-Dinitrophenol	48	U
100-02-7-----	4-Nitrophenol	48	U
132-64-9-----	Dibenzofuran	10	U
121-14-2-----	2,4-Dinitrotoluene	10	U
84-66-2-----	Diethylphthalate	10	U
7005-72-3-----	4-Chlorophenyl-phenylether	10	U
86-73-7-----	Fluorene	10	U
100-01-6-----	4-Nitroaniline	48	U
534-52-1-----	4,6-Dinitro-2-methylphenol	48	U
86-30-6-----	N-nitrosodiphenylamine (1)	10	U
101-55-3-----	4-Bromophenyl-phenylether	10	U
118-74-1-----	Hexachlorobenzene	10	U
87-86-5-----	Pentachlorophenol	48	U
85-01-8-----	Phenanthrene	10	U
120-12-7-----	Anthracene	10	U
84-74-2-----	Di-n-butylphthalate	10	U
206-44-0-----	Fluoranthene	10	U
129-00-0-----	Pyrene	10	U
85-68-7-----	Butylbenzylphthalate	10	U
91-94-1-----	3,3'-Dichlorobenzidine	19	U
56-55-3-----	Benzo(a)anthracene	10	U
218-01-9-----	Chrysene	10	U
117-81-7-----	bis(2-Ethylhexyl)phthalate	10	U
117-84-0-----	Di-n-octyl phthalate	10	U
205-99-2-----	Benzo(b)fluoranthene	10	U
207-08-9-----	Benzo(k)fluoranthene	10	U
50-32-8-----	Benzo(a)pyrene	10	U
193-39-5-----	Indeno(1,2,3-cd)pyrene	10	U
53-70-3-----	Dibenz(a,h)anthracene	10	U
191-24-2-----	Benzo(g,h,i)perylene	10	U

(1) - Cannot be separated from Diphenylamine

1F
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

EPA SAMPLE NO.

QLE2GW

Name: VERSAR INC. Contract: _____
Lab Code: VERSAR Case No.: 4022A SAS No.: _____ SDG No.: B3
Matrix: (soil/water) WATER Lab Sample ID: 38782
Sample wt/vol: 1050 (g/mL) ML Lab File ID: T5512
Level: (low/med) LOW Date Received: 12/01/90
% Moisture: not dec. _____ dec. _____ Date Extracted: 12/05/90
Extraction: (SepF/Cont/Sonc) CONT Date Analyzed: 01/02/91
GPC Cleanup: (Y/N) N pH: _____ Dilution Factor: 1.00

Number TICs found: 4 CONCENTRATION UNITS:
(ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1.	UNKNOWN	3.35	40	BJ
2.	UNKNOWN	3.57	19	BJ
3.	UNKNOWN	4.48	9.5	J
4.	UNKNOWN SILOXANE	28.92	89	J

1D
PESTICIDE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

QLE2GW

Lab Name: _____ VERSAR, INC. _____ Contract: _____

Code: VERSAR Case No.: URSQUEEN SAS No.: _____ SDG No.: _____

Matrix: (soil/water) WATER

Lab Sample ID: __38792

Sample wt/vol: 1050 (g/ml) ML

Lab File ID: ____

Level: (low/med) __LOW__

Date Received: __12/01/90

% Moisture: not dec. _____ dec. _____

Date Extracted: __12/05/90

Extraction: (SepF/Cont/Sonc) _____ CONT

Date Analyzed: __01/05/91

GPC Cleanup: (Y/N) __N__ pH: _____

Dilution Factor: 1.0

CAS NO.	COMPOUND	CONCENTRATION UNITS:	
		(ug/L or ug/Kg) _UG/L	Q
319-84-6	alpha-BHC	0.05	1U
319-85-7	beta-BHC	0.05	1U
319-86-8	delta-BHC	0.05	1U
58-89-9	gamma-BHC (Lindane)	0.05	1U
76-44-8	Heptachlor	0.05	1U
309-00-2	Aldrin	0.05	1U
1024-57-3	Heptachlor Epoxide	0.05	1U
959-98-8	Endosulfan I	0.05	1U
60-57-1	Dieldrin	0.10	1U
72-55-9	4,4'-DDE	0.10	1U
72-20-8	Endrin	0.10	1U
33213-65-9	Endosulfan II	0.10	1U
72-54-8	4,4'-DDD	0.10	1U
1031-07-8	Endosulfan Sulfate	0.10	1U
50-29-3	4,4'-DDT	0.10	1U
72-43-5	Methoxychlor	0.48	1U
53494-70-5	Endrin Ketone	0.10	1U
5103-71-9	alpha-Chlordane	0.48	1U
5103-74-2	gamma-Chlordane	0.48	1U
8001-35-2	Toxaphene	0.95	1U
12674-11-2	Aroclor-1016	0.48	1U
11104-28-2	Aroclor-1221	0.48	1U
11141-16-5	Aroclor-1232	0.48	1U
53469-21-9	Aroclor-1242	0.48	1U
12672-29-6	Aroclor-1248	0.48	1U
11097-69-1	Aroclor-1254	0.95	1U
11096-82-5	Aroclor-1260	0.95	1U

ga
1/10/91

U.S. EPA - CLP

1
INORGANIC ANALYSES DATA SHEET

EPA SAMPLE NO.

E-2GW

Lab Name: VERSAR LABORATORIES INC. Contract: 35216.03

Lab Code: VERSAR Case No.: 4014 SAS No.: SDG No.: E-1

Matrix (soil/water): WATER Lab Sample ID: 38802

Level (low/med): LOW Date Received: 12/01/90

% Solids: 0.0

Concentration Units (ug/L or mg/kg dry weight): UG/L

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum	10.0	U		P
7440-36-0	Antimony	23.0	U		P
7440-38-2	Arsenic	14.4		S	F
7440-39-3	Barium	313			P
7440-41-7	Beryllium	1.9	B		P
7440-43-9	Cadmium	5.0	U		P
7440-70-2	Calcium	158000			P
7440-47-3	Chromium	5.0	U		P
7440-48-4	Cobalt	8.0	U		P
7440-50-8	Copper	4.0	U		P
7439-89-6	Iron	23700			P
7439-92-1	Lead	1.0	U		F
7439-95-4	Magnesium	41500			P
7439-96-5	Manganese	574			P
7439-97-6	Mercury	0.26			CV
7440-02-0	Nickel	13.0	U		P
7440-09-7	Potassium	8160			P
7782-49-2	Selenium	15.0	U	WN	F
7440-22-4	Silver	3.2	B		P
7440-23-5	Sodium	49200			P
7440-28-0	Thallium	2.0	U		F
7440-62-2	Vanadium	5.0	U		P
7440-66-6	Zinc	5.0	U		P
	Cyanide	10.0	U		AS

Color Before: COLORLESS Clarity Before: CLEAR Texture: _____

Color After: COLORLESS Clarity After: CLEAR Artifacts: _____

Comments:

THE CYANIDE LAB SAMPLE ID NUMBER IS 38811; THE EPA SAMPLE NUMBER _____

PREFIX IS "Q/L"; _____

1A
VOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

QLE3GW

Lab Name: VERSAR INC. Contract: _____

Lab Code: VERSAR Case No.: 4014A SAS No.: _____ SDG No.: B2

Matrix: (soil/water) WATER Lab Sample ID: 38589

Sample wt/vol: 5.0 (g/mL) ML Lab File ID: S1247

Level: (low/med) LOW Date Received: 11/30/90

% Moisture: not dec. _____ Date Analyzed: 12/06/90

Column: (pack/cap) CAP Dilution Factor: 1.0

CAS NO. COMPOUND CONCENTRATION UNITS:
(ug/L or ug/Kg) UG/L Q

74-87-3-----	Chloromethane	10	U
74-83-9-----	Bromomethane	10	U
75-01-4-----	Vinyl chloride	10	U
75-00-3-----	Chloroethane	10	U
75-09-2-----	Methylene chloride	5	U
67-64-1-----	Acetone	10	U
75-15-0-----	Carbon disulfide	5	U
75-35-4-----	1,1-Dichloroethene	5	U
75-34-3-----	1,1-Dichloroethane	5	U
540-59-0-----	1,2-Dichloroethene (total)	5	U
67-66-3-----	Chloroform	5	U
107-06-2-----	1,2-Dichloroethane	5	U
78-93-3-----	2-Butanone	10	U
71-55-6-----	1,1,1-Trichloroethane	5	U
56-23-5-----	Carbon tetrachloride	5	U
108-05-4-----	Vinyl acetate	10	U
75-27-4-----	Bromodichloromethane	5	U
78-87-5-----	1,2-Dichloropropane	5	U
10061-01-5-----	cis-1,3-Dichloropropene	5	U
79-01-6-----	Trichloroethene	5	U
124-48-1-----	Dibromochloromethane	5	U
79-00-5-----	1,1,2-Trichloroethane	5	U
71-43-2-----	Benzene	5	U
10061-02-6-----	Trans-1,3-dichloropropene	5	U
75-25-2-----	Bromoform	5	U
108-10-1-----	4-Methyl-2-pentanone	10	U
591-78-6-----	2-Hexanone	10	U
127-18-4-----	Tetrachloroethene	5	U
79-34-5-----	1,1,2,2-Tetrachloroethane	5	U
108-88-3-----	Toluene	5	U
108-90-7-----	Chlorobenzene	5	U
100-41-4-----	Ethylbenzene	5	U
100-42-5-----	Styrene	5	U
1330-20-7-----	Total xylenes	5	U

1E
VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

EPA SAMPLE NO.

QLE3GW

1, Name: VERSAR INC.

Contract: _____

Lab Code: VERSAR

Case No.: 4014A

SAS No.: _____

SDG No.: B2

Matrix: (soil/water) WATER

Lab Sample ID: 38589

Sample wt/vol: 5.0 (g/mL) ML

Lab File ID: S1247

Level: (low/med) LOW

Date Received: 11/30/90

% Moisture: not dec. _____

Date Analyzed: 12/06/90

Column (pack/cap) CAP

Dilution Factor: 1.0

Number TICs found: 0

CONCENTRATION UNITS:
(ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
=====	=====	=====	=====	=====

1B
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

QLE3GW

L Name: VERSAR INC. Contract: _____

Lab Code: VERSAR Case No.: 4014 SAS No.: _____ SDG No.: 2

Matrix: (soil/water) WATER Lab Sample ID: 38594

Sample wt/vol: 1050 (g/mL) ML Lab File ID: Z6891

Level: (low/med) LOW Date Received: 11/30/90

% Moisture: not dec. _____ dec. _____ Date Extracted: 12/03/90

Extraction: (SepF/Cont/Sonc) CONT Date Analyzed: 12/14/90

GPC Cleanup: (Y/N) N pH: _____ Dilution Factor: 1.00

CONCENTRATION UNITS:
(ug/L or ug/Kg) UG/L Q

108-95-2-----Phenol	10	U
111-44-4-----bis(2-Chloroethyl) ether	10	U
95-57-8-----2-Chlorophenol	10	U
541-73-1-----1,3-Dichlorobenzene	10	U
106-46-7-----1,4-Dichlorobenzene	10	U
100-51-6-----Benzyl alcohol	10	U
95-50-1-----1,2-Dichlorobenzene	10	U
95-48-7-----2-Methylphenol	10	U
108-60-1-----bis(2-Chloroisopropyl) ether	10	U
106-44-5-----4-Methylphenol	10	U
621-64-7-----N-Nitroso-di-n-propylamine	10	U
67-72-1-----Hexachloroethane	10	U
98-95-3-----Nitrobenzene	10	U
78-59-1-----Isophorone	10	U
88-75-5-----2-Nitrophenol	10	U
105-67-9-----2,4-Dimethylphenol	10	U
65-85-0-----Benzoic Acid	48	U
111-91-1-----bis(2-Chloroethoxy) methane	10	U
120-83-2-----2,4-Dichlorophenol	10	U
120-82-1-----1,2,4-Trichlorobenzene	10	U
91-20-3-----Naphthalene	10	U
106-47-8-----4-Chloroaniline	10	U
87-68-3-----Hexachlorobutadiene	10	U
59-50-7-----4-Chloro-3-methylphenol	10	U
91-57-6-----2-Methylnaphthalene	10	U
77-47-4-----Hexachlorocyclopentadiene	10	U
88-06-2-----2,4,6-Trichlorophenol	10	U
95-95-4-----2,4,5-Trichlorophenol	48	U
91-58-7-----2-Chloronaphthalene	10	U
88-74-4-----2-Nitroaniline	48	U
131-11-3-----Dimethylphthalate	10	U
208-96-8-----Acenaphthylene	10	U
606-20-2-----2,6-Dinitrotoluene	10	U

1C
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

QLE3GW

I Name: VERSAR INC. Contract: _____

Lab Code: VERSAR Case No.: 4014 SAS No.: _____ SDG No.: 2

Matrix: (soil/water) WATER Lab Sample ID: 38594

Sample wt/vol: 1050 (g/mL) ML Lab File ID: 26891

Level: (low/med) LOW Date Received: 11/30/90

% Moisture: not dec. _____ dec. _____ Date Extracted: 12/03/90

Extraction: (SepF/Cont/Sonc) CONT Date Analyzed: 12/14/90

GPC Cleanup: (Y/N) N pH: _____ Dilution Factor: 1.00

CONCENTRATION UNITS:
(ug/L or ug/Kg) UG/L

CAS NO. COMPOUND Q

99-09-2-----3-Nitroaniline	48	U
83-32-9-----Acenaphthene	10	U
51-28-5-----2,4-Dinitrophenol	48	U
100-02-7-----4-Nitrophenol	48	U
132-64-9-----Dibenzofuran	10	U
121-14-2-----2,4-Dinitrotoluene	10	U
84-66-2-----Diethylphthalate	10	U
7005-72-3-----4-Chlorophenyl-phenylether	10	U
86-73-7-----Fluorene	10	U
100-01-6-----4-Nitroaniline	48	U
534-52-1-----4,6-Dinitro-2-methylphenol	48	U
86-30-6-----N-nitrosodiphenylamine (1)	10	U
101-55-3-----4-Bromophenyl-phenylether	10	U
118-74-1-----Hexachlorobenzene	10	U
87-86-5-----Pentachlorophenol	48	U
85-01-8-----Phenanthrene	10	U
120-12-7-----Anthracene	10	U
84-74-2-----Di-n-butylphthalate	10	U
206-44-0-----Fluoranthene	10	U
129-00-0-----Pyrene	10	U
85-68-7-----Butylbenzylphthalate	10	U
91-94-1-----3,3'-Dichlorobenzidine	19	U
56-55-3-----Benzo(a)anthracene	10	U
218-01-9-----Chrysene	10	U
117-81-7-----bis(2-Ethylhexyl)phthalate	10	U
117-84-0-----Di-n-octyl phthalate	10	U
205-99-2-----Benzo(b)fluoranthene	10	U
207-08-9-----Benzo(k)fluoranthene	10	U
50-32-8-----Benzo(a)pyrene	10	U
193-39-5-----Indeno(1,2,3-cd)pyrene	10	U
53-70-3-----Dibenz(a,h)anthracene	10	U
191-24-2-----Benzo(g,h,i)perylene	10	U

(1) - Cannot be separated from Diphenylamine

1F
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

EPA SAMPLE NO.

QLE3GW

L Name: VERSAR INC. Contract: _____

Lab Code: VERSAR Case No.: 4014 SAS No.: _____ SDG No.: 2

Matrix: (soil/water) WATER Lab Sample ID: 38594

Sample wt/vol: 1050 (g/mL) ML Lab File ID: Z6891

Level: (low/med) LOW Date Received: 11/30/90

% Moisture: not dec. _____ dec. _____ Date Extracted: 12/03/90

Extraction: (SepF/Cont/Sonc) CONT Date Analyzed: 12/14/90

GPC Cleanup: (Y/N) N pH: _____ Dilution Factor: 1.00

CONCENTRATION UNITS:
(ug/L or ug/Kg) UG/L

Number TICs found: 3

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1.	UNKNOWN	3.72	13	J
2.	UNKNOWN	14.67	9.5	J
3.	UNKNOWN	18.02	13	J

1D
PESTICIDE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

QLE3GW

Lab Name: _____ VERSAR, INC. _____ Contract: _____

Lab Code: VERSAR Case No.: URSQUEEN SAS No.: _____ SDG No.: _____

Matrix: (soil/water) WATER

Lab Sample ID: __38598

Sample wt/vol: 1050 (g/ml) ML

Lab File ID: ____

Level: (low/med) __LOW__

Date Received: __11/30/90

Moisture: not dec. _____ dec. _____

Date Extracted: __12/03/90

Extraction: (SepF/Cont/Sonc) ____CONT

Date Analyzed: __12/30/90

PC Cleanup: (Y/N) __N__ pH: ____

Dilution Factor: 1.0

CAS NO. COMPOUND CONCENTRATION UNITS:
(ug/L or ug/Kg) _UG/L Q

319-84-6	alpha-BHC	0.05	1U
319-85-7	beta-BHC	0.05	1U
319-86-8	delta-BHC	0.05	1U
58-89-9	gamma-BHC (Lindane)	0.05	1U
76-44-8	Heptachlor	0.05	1U
309-00-2	Aldrin	0.05	1U
1024-57-3	Heptachlor Epoxide	0.05	1U
959-98-8	Endosulfan I	0.05	1U
60-57-1	Dieldrin	0.10	1U
72-55-9	4,4'-DDE	0.10	1U
72-20-8	Endrin	0.10	1U
33213-65-9	Endosulfan II	0.10	1U
72-54-8	4,4'-DDD	0.10	1U
1031-07-8	Endosulfan Sulfate	0.10	1U
50-29-3	4,4'-DDT	0.10	1U
72-43-5	Methoxychlor	0.48	1U
53494-70-5	Endrin Ketone	0.10	1U
5103-71-9	alpha-Chlordane	0.48	1U
5103-74-2	gamma-Chlordane	0.48	1U
8001-35-2	Toxaphene	0.95	1U
12674-11-2	Aroclor-1016	0.48	1U
11104-28-2	Aroclor-1221	0.48	1U
11141-16-5	Aroclor-1232	0.48	1U
53469-21-9	Aroclor-1242	0.48	1U
12672-29-6	Aroclor-1248	0.48	1U
11097-69-1	Aroclor-1254	0.95	1U
11096-82-5	Aroclor-1260	0.95	1U

U.S. EPA - CLP

1
INORGANIC ANALYSES DATA SHEET

EPA SAMPLE NO.

E-3 GW

Lab Name: VERSAR LABORATORIES INC. Contract: 35216.03

Lab Code: VERSAR Case No.: 4014 SAS No.: SDG No.: E-1

Matrix (soil/water): WATER Lab Sample ID: 38602

Level (low/med): LOW Date Received: 11/30/90

% Solids: 0.0

Concentration Units (ug/L or mg/kg dry weight): UG/L

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum	10.0	U		P
7440-36-0	Antimony	23.0	U		P
7440-38-2	Arsenic	3.9	B		F
7440-39-3	Barium	275			P
7440-41-7	Beryllium	2.8	B		P
7440-43-9	Cadmium	5.0	U		P
7440-70-2	Calcium	144000			P
7440-47-3	Chromium	5.0	U		P
7440-48-4	Cobalt	8.0	U		P
7440-50-8	Copper	4.0	U		P
7439-89-6	Iron	9430			P
7439-92-1	Lead	1.0	U	W	F
7439-95-4	Magnesium	51100			P
7439-96-5	Manganese	471			P
7439-97-6	Mercury	0.20	U		CV
7440-02-0	Nickel	17.8	B		P
7440-09-7	Potassium	35300			P
7782-49-2	Selenium	3.0	U	WN	F
7440-22-4	Silver	3.0	U		P
7440-23-5	Sodium	92900			P
7440-28-0	Thallium	10.0	U		F
7440-62-2	Vanadium	8.8	B		P
7440-66-6	Zinc	38.0			P
	Cyanide	10.0	U		AS

Color Before: COLORLESS Clarity Before: CLEAR Texture: _____

Color After: COLORLESS Clarity After: CLEAR Artifacts: _____

Comments:

THE CYANIDE LAB SAMPLE ID NUMBER IS 38606; THE EPA SAMPLE NUMBER _____

PREFIX IS "Q/L"; _____

1A
VOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

QL-SW-1

L Name: VERSAR INC. Contract: _____

Lab Code: VERSAR Case No.: 4022 SAS No.: _____ SDG No.: 3

Matrix: (soil/water) WATER Lab Sample ID: 38772

Sample wt/vol: 5.0 (g/mL) ML Lab File ID: Y5166

Level: (low/med) LOW Date Received: 12/01/90

% Moisture: not dec. _____ Date Analyzed: 12/06/90

Column: (pack/cap) CAP Dilution Factor: 1.0

CONCENTRATION UNITS:

CAS NO. COMPOUND (ug/L or ug/Kg) UG/L Q

74-87-3	Chloromethane	10	U
74-83-9	Bromomethane	10	U
75-01-4	Vinyl chloride	10	U
75-00-3	Chloroethane	10	U
75-09-2	Methylene chloride	8	B
67-64-1	Acetone	10	U
75-15-0	Carbon disulfide	5	U
75-35-4	1,1-Dichloroethene	5	U
75-34-3	1,1-Dichloroethane	5	U
540-59-0	1,2-Dichloroethene (total)	5	U
67-66-3	Chloroform	5	U
107-06-2	1,2-Dichloroethane	5	U
78-93-3	2-Butanone	10	U
71-55-6	1,1,1-Trichloroethane	5	U
56-23-5	Carbon tetrachloride	5	U
108-05-4	Vinyl acetate	10	U
75-27-4	Bromodichloromethane	5	U
78-87-5	1,2-Dichloropropane	5	U
10061-01-5	cis-1,3-Dichloropropene	5	U
79-01-6	Trichloroethene	5	U
124-48-1	Dibromochloromethane	5	U
79-00-5	1,1,2-Trichloroethane	5	U
71-43-2	Benzene	5	U
10061-02-6	Trans-1,3-dichloropropene	5	U
75-25-2	Bromoform	5	U
108-10-1	4-Methyl-2-pentanone	10	U
591-78-6	2-Hexanone	10	U
127-18-4	Tetrachloroethene	5	U
79-34-5	1,1,2,2-Tetrachloroethane	5	U
108-88-3	Toluene	5	U
108-90-7	Chlorobenzene	5	U
100-41-4	Ethylbenzene	5	U
100-42-5	Styrene	5	U
1330-20-7	Total xylenes	5	U

1E
VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

EPA SAMPLE NO.

QL-SW-1

Lab Name: VERSAR INC. Contract: _____

Lab Code: VERSAR Case No.: 4022 SAS No.: _____ SDG No.: 3

Matrix: (soil/water) WATER Lab Sample ID: 38772

Sample wt/vol: 5.0 (g/mL) ML Lab File ID: Y5166

Level: (low/med) LOW Date Received: 12/01/90

% Moisture: not dec. _____ Date Analyzed: 12/06/90

% column (pack/cap) CAP Dilution Factor: 1.0

Number TICs found: 0

CONCENTRATION UNITS:
(ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
=====	=====	=====	=====	=====

1D
PESTICIDE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.:

QLSW1

Lab Name: _____ VERSAR, INC. _____ Contract: _____

Code: VERSAR Case No.: URSQUEEN SAS No.: _____ SDG No.: _____

Matrix: (soil/water) WATER

Lab Sample ID: __38793

Sample wt/vol: 1000 (g/ml) ML

Lab File ID: ____

Level: (low/med) __LOW__

Date Received: __12/01/90

% Moisture: not dec. _____ dec. _____

Date Extracted: __12/05/90

Extraction: (SepF/Cont/Sonc) ____CONT

Date Analyzed: __01/05/91

GPC Cleanup: (Y/N) __N__ pH: ____

Dilution Factor: 1.0

CAS NO.	COMPOUND	CONCENTRATION UNITS: (ug/L or ug/Kg) _UG/L	Q
---------	----------	---	---

319-84-6	alpha-BHC	0.05	IU
319-85-7	beta-BHC	0.05	IU
319-86-8	delta-BHC	0.05	IU
58-89-9	gamma-BHC (Lindane)	0.05	IU
76-44-8	Heptachlor	0.05	IU
309-00-2	Aldrin	0.05	IU
1024-57-3	Heptachlor Epoxide	0.05	IU
959-98-8	Endosulfan I	0.05	IU
60-57-1	Dieldrin	0.10	IU
72-55-9	4,4'-DDE	0.10	IU
72-20-8	Endrin	0.10	IU
33213-65-9	Endosulfan II	0.10	IU
72-54-8	4,4'-DDD	0.10	IU
1031-07-8	Endosulfan Sulfate	0.10	IU
50-29-3	4,4'-DDT	0.10	IU
72-43-5	Methoxychlor	0.50	IU
53494-70-5	Endrin Ketone	0.10	IU
5103-71-9	alpha-Chlordane	0.50	IU
5103-74-2	gamma-Chlordane	0.50	IU
8001-35-2	Toxaphene	1.0	IU
12674-11-2	Aroclor-1016	0.50	IU
11104-28-2	Aroclor-1221	0.50	IU
11141-16-5	Aroclor-1232	0.50	IU
53469-21-9	Aroclor-1242	0.50	IU
12672-29-6	Aroclor-1248	0.50	IU
11097-69-1	Aroclor-1254	1.0	IU
11096-82-5	Aroclor-1260	1.0	IU

ja
1/10/91

U.S. EPA - CLP

1
INORGANIC ANALYSES DATA SHEET

EPA SAMPLE NO.

SW-1

Lab Name: VERSAR LABORATORIES INC. Contract: 35216.03

Lab Code: VERSAR Case No.: 4014 SAS No.: SDG No.: E-1

Matrix (soil/water): WATER Lab Sample ID: 38803

Level (low/med): LOW Date Received: 12/01/90

% Solids: 0.0

Concentration Units (ug/L or mg/kg dry weight): UG/L

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum	27.8	B		P
7440-36-0	Antimony	23.0	U		P
7440-38-2	Arsenic	3.0	U		F
7440-39-3	Barium	158	B		P
7440-41-7	Beryllium	4.9	B		P
7440-43-9	Cadmium	5.0	U		P
7440-70-2	Calcium	113000			P
7440-47-3	Chromium	5.0	U		P
7440-48-4	Cobalt	8.0	U		P
7440-50-8	Copper	4.0	U		P
7439-89-6	Iron	3240			P
7439-92-1	Lead	1.0	U		F
7439-95-4	Magnesium	27200			P
7439-96-5	Manganese	321			P
7439-97-6	Mercury	0.20	U		CV
7440-02-0	Nickel	13.0	U		P
7440-09-7	Potassium	5050			P
7782-49-2	Selenium	3.0	U	WN	F
7440-22-4	Silver	3.0	U		P
7440-23-5	Sodium	29900			P
7440-28-0	Thallium	2.0	U		F
7440-62-2	Vanadium	5.0	U		P
7440-66-6	Zinc	19.8	B		P
	Cyanide	10.0	U		AS

Color Before: COLORLESS Clarity Before: CLEAR Texture:

Color After: COLORLESS Clarity After: CLEAR Artifacts:

Comments:

THE CYANIDE LAB SAMPLE ID NUMBER IS 38812; THE EPA SAMPLE NUMBER
PREFIX IS "Q/L";

1A
VOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

QL-SED-1

L Name: VERSAR INC. Contract: _____

Lab Code: VERSAR Case No.: 4022 SAS No.: _____ SDG No.: 3

Matrix: (soil/water) SOIL Lab Sample ID: 38773

Sample wt/vol: 5.0 (g/mL) G Lab File ID: U6538

Level: (low/med) LOW Date Received: 12/01/90

% Moisture: not dec. 24 Date Analyzed: 12/06/90

Column: (pack/cap) PACK Dilution Factor: 1.0

CONCENTRATION UNITS:
(ug/L or ug/Kg) UG/KG

CAS NO.

COMPOUND

Q

74-87-3-----	Chloromethane	13	U
74-83-9-----	Bromomethane	13	U
75-01-4-----	Vinyl chloride	13	U
75-00-3-----	Chloroethane	13	U
75-09-2-----	Methylene chloride	7	U
67-64-1-----	Acetone	23	
75-15-0-----	Carbon disulfide	7	U
75-35-4-----	1,1-Dichloroethene	7	U
75-34-3-----	1,1-Dichloroethane	7	U
540-59-0-----	1,2-Dichloroethene (total)	7	U
67-66-3-----	Chloroform	7	U
107-06-2-----	1,2-Dichloroethane	7	U
78-93-3-----	2-Butanone	5	J
71-55-6-----	1,1,1-Trichloroethane	7	U
56-23-5-----	Carbon tetrachloride	7	U
108-05-4-----	Vinyl acetate	13	U
75-27-4-----	Bromodichloromethane	7	U
78-87-5-----	1,2-Dichloropropane	7	U
10061-01-5-----	cis-1,3-Dichloropropene	7	U
79-01-6-----	Trichloroethene	7	U
124-48-1-----	Dibromochloromethane	7	U
79-00-5-----	1,1,2-Trichloroethane	7	U
71-43-2-----	Benzene	7	U
10061-02-6-----	Trans-1,3-dichloropropene	7	U
75-25-2-----	Bromoform	7	U
108-10-1-----	4-Methyl-2-pentanone	13	U
591-78-6-----	2-Hexanone	13	U
127-18-4-----	Tetrachloroethene	7	U
79-34-5-----	1,1,2,2-Tetrachloroethane	7	U
108-88-3-----	Toluene	7	U
108-90-7-----	Chlorobenzene	7	U
100-41-4-----	Ethylbenzene	7	U
100-42-5-----	Styrene	7	U
1330-20-7-----	Total xylenes	7	U

1E
VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

EPA SAMPLE NO.

QL-SED-1

Name: VERSAR INC. Contract: _____

Lab Code: VERSAR Case No.: 4022 SAS No.: _____ SDG No.: 3

Matrix: (soil/water) SOIL Lab Sample ID: 38773

Sample wt/vol: 5.0 (g/mL) G Lab File ID: U6538

Level: (low/med) LOW Date Received: 12/01/90

* Moisture: not dec. 24 Date Analyzed: 12/06/90

Column (pack/cap) PACK Dilution Factor: 1.0

Number TICs found: 0

CONCENTRATION UNITS:
(ug/L or ug/Kg) UG/KG

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
=====	=====	=====	=====	=====

1B
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

QLSED1

1 Name: VERSAR INC. Contract: _____

Lab Code: VERSAR Case No.: 4022A SAS No.: _____ SDG No.: B3

Matrix: (soil/water) SOIL Lab Sample ID: 38784

Sample wt/vol: 30.2 (g/mL) G Lab File ID: T5518

Level: (low/med) LOW Date Received: 12/01/90

% Moisture: not dec. 27 dec. _____ Date Extracted: 12/07/90

Extraction: (SepF/Cont/Sonc) SONC Date Analyzed: 01/02/91

CPC Cleanup: (Y/N) N pH: _____ Dilution Factor: 1.1

CONCENTRATION UNITS:
(ug/L or ug/Kg) UG/KG

CAS NO. COMPOUND Q

108-95-2-----	Phenol	500	U
111-44-4-----	bis(2-Chloroethyl) ether	500	U
95-57-8-----	2-Chlorophenol	500	U
541-73-1-----	1,3-Dichlorobenzene	500	U
106-46-7-----	1,4-Dichlorobenzene	500	U
100-51-6-----	Benzyl alcohol	500	U
95-50-1-----	1,2-Dichlorobenzene	500	U
95-48-7-----	2-Methylphenol	500	U
108-60-1-----	bis(2-Chloroisopropyl) ether	500	U
106-44-5-----	4-Methylphenol	500	U
621-64-7-----	N-Nitroso-di-n-propylamine	500	U
67-72-1-----	Hexachloroethane	500	U
98-95-3-----	Nitrobenzene	500	U
78-59-1-----	Isophorone	500	U
88-75-5-----	2-Nitrophenol	500	U
105-67-9-----	2,4-Dimethylphenol	500	U
65-85-0-----	Benzoic Acid	2400	U
111-91-1-----	bis(2-Chloroethoxy) methane	500	U
120-83-2-----	2,4-Dichlorophenol	500	U
120-82-1-----	1,2,4-Trichlorobenzene	500	U
91-20-3-----	Naphthalene	500	U
106-47-8-----	4-Chloroaniline	500	U
87-68-3-----	Hexachlorobutadiene	500	U
59-50-7-----	4-Chloro-3-methylphenol	500	U
91-57-6-----	2-Methylnaphthalene	500	U
77-47-4-----	Hexachlorocyclopentadiene	500	U
88-06-2-----	2,4,6-Trichlorophenol	500	U
95-95-4-----	2,4,5-Trichlorophenol	2400	U
91-58-7-----	2-Chloronaphthalene	500	U
88-74-4-----	2-Nitroaniline	2400	U
131-11-3-----	Dimethylphthalate	500	U
208-96-8-----	Acenaphthylene	500	U
606-20-2-----	2,6-Dinitrotoluene	500	U

1C
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

QLSED1

L Name: VERSAR INC. Contract: _____

Lab Code: VERSAR Case No.: 4022A SAS No.: _____ SDG No.: B3

Matrix: (soil/water) SOIL Lab Sample ID: 38784

Sample wt/vol: 30.2 (g/mL) G Lab File ID: T5518

Level: (low/med) LOW Date Received: 12/01/90

% Moisture: not dec. 27 dec. _____ Date Extracted: 12/07/90

Extraction: (SepF/Cont/Sonc) SONC Date Analyzed: 01/02/91

GPC Cleanup: (Y/N) N pH: _____ Dilution Factor: 1.1

CONCENTRATION UNITS:
(ug/L or ug/Kg) UG/KG

CAS NO.	COMPOUND	CONCENTRATION UNITS: (ug/L or ug/Kg) <u>UG/KG</u>	Q
99-09-2-----	3-Nitroaniline	2400	U
83-32-9-----	Acenaphthene	500	U
51-28-5-----	2,4-Dinitrophenol	2400	U
100-02-7-----	4-Nitrophenol	2400	U
132-64-9-----	Dibenzofuran	500	U
121-14-2-----	2,4-Dinitrotoluene	500	U
84-66-2-----	Diethylphthalate	500	U
7005-72-3-----	4-Chlorophenyl-phenylether	500	U
86-73-7-----	Fluorene	500	U
100-01-6-----	4-Nitroaniline	2400	U
534-52-1-----	4,6-Dinitro-2-methylphenol	2400	U
86-30-6-----	N-nitrosodiphenylamine (1)	500	U
101-55-3-----	4-Bromophenyl-phenylether	500	U
118-74-1-----	Hexachlorobenzene	500	U
87-86-5-----	Pentachlorophenol	2400	U
85-01-8-----	Phenanthrene	500	U
120-12-7-----	Anthracene	500	U
84-74-2-----	Di-n-butylphthalate	500	U
206-44-0-----	Fluoranthene	500	U
129-00-0-----	Pyrene	500	U
85-68-7-----	Butylbenzylphthalate	500	U
91-94-1-----	3,3'-Dichlorobenzidine	990	U
56-55-3-----	Benzo(a)anthracene	500	U
218-01-9-----	Chrysene	500	U
117-81-7-----	bis(2-Ethylhexyl)phthalate	500	U
117-84-0-----	Di-n-octyl phthalate	500	U
205-99-2-----	Benzo(b)fluoranthene	500	U
207-08-9-----	Benzo(k)fluoranthene	500	U
50-32-8-----	Benzo(a)pyrene	500	U
193-39-5-----	Indeno(1,2,3-cd)pyrene	500	U
53-70-3-----	Dibenz(a,h)anthracene	500	U
191-24-2-----	Benzo(g,h,i)perylene	500	U

(1) - Cannot be separated from Diphenylamine

1F
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

EPA SAMPLE NO.

QLSED1

I Name: VERSAR INC. Contract: _____

Lab Code: VERSAR Case No.: 4022A SAS No.: _____ SDG No.: B3

Matrix: (soil/water) SOIL Lab Sample ID: 38784

Sample wt/vol: 30.2 (g/mL) G Lab File ID: T5518

Level: (low/med) LOW Date Received: 12/01/90

% Moisture: not dec. 27 dec. _____ Date Extracted: 12/07/90

Extraction: (SepF/Cont/Sonc) SONC Date Analyzed: 01/02/91

GPC Cleanup: (Y/N) N pH: _____ Dilution Factor: 1.1

Number TICs found: 20

CONCENTRATION UNITS:
(ug/L or ug/Kg) UG/KG

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1.	UNKNOWN	3.38	5700	BJ
2.	UNKNOWN	3.53	400	BJ
3.	UNKNOWN HYDROCARBON	3.62	660	BJ
4.	UNKNOWN HYDROCARBON	3.70	450	BJ
5.	UNKNOWN	4.43	1400	J
6.	UNKNOWN KETONE	4.65	1600	BJ
7.	UNKNOWN KETONE	4.77	760	J
8.	UNKNOWN	5.20	1500	J
9.	UNKNOWN	5.97	1600	J
10.	UNKNOWN	13.04	250	J
11. 10544-50-0	SULFUR, MOL. (S8)	16.17	2700	J
12.	UNKNOWN	20.70	450	J
13.	UNKNOWN	21.59	450	J
14.	UNKNOWN ALDEHYDE	22.09	400	J
15.	UNKNOWN HYDROCARBON	22.75	1000	J
16.	UNKNOWN HYDROCARBON	25.74	450	J
17.	UNKNOWN	26.84	300	J
18.	UNKNOWN	27.09	350	J
19.	UNKNOWN	29.26	300	J
20.	UNKNOWN	30.04	250	J

1D
PESTICIDE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

QLSED1DL

Lab Name: _____ VERSAR, INC. _____ Contract: _____

Code: VERSAR Case No.: URSQUEEN SAS No.: _____ SDG No.: _____

Matrix: (soil/water) SOIL Lab Sample ID: __38784

Sample wt/vol: 30.18 (g/ml) G Lab File ID: _____

Level: (low/med) __LOW__ Date Received: __12/01/91

% Moisture: not dec. 26.6 dec. _____ Date Extracted: __12/07/90

Extraction: (SepF/Cont/Sonc) _____ SONC Date Analyzed: __01/09/91

GPC Cleanup: (Y/N) __N__ pH: _____ 7.05 Dilution Factor: 10.0

CONCENTRATION UNITS:
(ug/L or ug/Kg) _ (UG/KG) Q

CAS NO.	COMPOUND	CONCENTRATION UNITS: (ug/L or ug/Kg) _ (UG/KG)	Q
319-84-6	alpha-BHC	54	U
319-85-7	beta-BHC	54	U
319-86-8	delta-BHC	54	U
58-89-9	gamma-BHC (Lindane)	54	U
76-44-8	Heptachlor	54	U
309-00-2	Aldrin	54	U
1024-57-3	Heptachlor Epoxide	54	U
959-98-8	Endosulfan I	54	U
60-57-1	Dieldrin	110	U
72-55-9	4,4'-DDE	110	U
72-20-8	Endrin	110	U
33213-65-9	Endosulfan II	110	U
72-54-8	4,4'-DDD	110	U
1031-07-8	Endosulfan Sulfate	110	U
50-29-3	4,4'-DDT	110	U
72-43-5	Methoxychlor	540	U
53494-70-5	Endrin Ketone	110	U
5103-71-9	alpha-Chlordane	540	U
5103-74-2	gamma-Chlordane	540	U
8001-35-2	Toxaphene	1100	U
12674-11-2	Aroclor-1016	540	U
11104-28-2	Aroclor-1221	540	U
11141-16-5	Aroclor-1232	540	U
53469-21-9	Aroclor-1242	540	U
12672-29-6	Aroclor-1248	540	U
11097-69-1	Aroclor-1254	1100	U
11096-82-5	Aroclor-1260	1100	U

U.S. EPA - CLP

1
INORGANIC ANALYSES DATA SHEET

EPA SAMPLE NO.

SED-1

Lab Name: VERSAR LABORATORIES INC. Contract: 35216.03

Lab Code: VERSAR Case No.: 4014 SAS No.: SDG No.: E-1

Matrix (soil/water): SOIL Lab Sample ID: 38813

Level (low/med): LOW Date Received: 12/01/90

% Solids: 75.5

Concentration Units (ug/L or mg/kg dry weight): MG/KG

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum	3120			P
7440-36-0	Antimony	5.3	U	N	P
7440-38-2	Arsenic	3.7			F
7440-39-3	Barium	19.1	B		P
7440-41-7	Beryllium	0.59	B		P
7440-43-9	Cadmium	1.2	U	N	P
7440-70-2	Calcium	45100			P
7440-47-3	Chromium	2.7			P
7440-48-4	Cobalt	2.7	B		P
7440-50-8	Copper	2.7	B		P
7439-89-6	Iron	6720			P
7439-92-1	Lead	4.1		N	F
7439-95-4	Magnesium	6800		E*	P
7439-96-5	Manganese	102			P
7439-97-6	Mercury	0.13	U		CV
7440-02-0	Nickel	6.6	B		P
7440-09-7	Potassium	333	B		P
7782-49-2	Selenium	0.74	U	W	F
7440-22-4	Silver	0.83	B		P
7440-23-5	Sodium	95.1	B		P
7440-28-0	Thallium	0.50	U		F
7440-62-2	Vanadium	10.1	B		P
7440-66-6	Zinc	16.4			P
	Cyanide	0.65	U	N	AS

Color Before: BLACK Clarity Before: Texture: COARSE

Color After: YELLOW Clarity After: CLEAR Artifacts:

Comments:

_THE_EPA_SAMPLE_NUMBER_PREFIX_IS_"Q/L_";

1A
VOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

QLL1

I Name: VERSAR INC. Contract: _____

Lab Code: VERSAR Case No.: 4014A SAS No.: _____ SDG No.: B2

Matrix: (soil/water) WATER Lab Sample ID: 38587

Sample wt/vol: 5.0 (g/mL) ML Lab File ID: S1249

Level: (low/med) LOW Date Received: 11/30/90

% Moisture: not dec. _____ Date Analyzed: 12/06/90

Column: (pack/cap) CAP Dilution Factor: 1.0

CONCENTRATION UNITS:

CAS NO. COMPOUND (ug/L or ug/Kg) UG/L Q

74-87-3-----	Chloromethane	10	U
74-83-9-----	Bromomethane	10	U
75-01-4-----	Vinyl chloride	10	U
75-00-3-----	Chloroethane	10	U
75-09-2-----	Methylene chloride	5	U
67-64-1-----	Acetone	10	U
75-15-0-----	Carbon disulfide	5	U
75-35-4-----	1,1-Dichloroethene	5	U
75-34-3-----	1,1-Dichloroethane	5	U
540-59-0-----	1,2-Dichloroethene (total)	5	U
67-66-3-----	Chloroform	5	U
107-06-2-----	1,2-Dichloroethane	5	U
78-93-3-----	2-Butanone	10	U
71-55-6-----	1,1,1-Trichloroethane	5	U
56-23-5-----	Carbon tetrachloride	5	U
108-05-4-----	Vinyl acetate	10	U
75-27-4-----	Bromodichloromethane	5	U
78-87-5-----	1,2-Dichloropropane	5	U
10061-01-5-----	cis-1,3-Dichloropropene	5	U
79-01-6-----	Trichloroethene	5	U
124-48-1-----	Dibromochloromethane	5	U
79-00-5-----	1,1,2-Trichloroethane	5	U
71-43-2-----	Benzene	6	
10061-02-6-----	Trans-1,3-dichloropropene	5	U
75-25-2-----	Bromoform	5	U
108-10-1-----	4-Methyl-2-pentanone	10	U
591-78-6-----	2-Hexanone	10	U
127-18-4-----	Tetrachloroethene	5	U
79-34-5-----	1,1,2,2-Tetrachloroethane	5	U
108-88-3-----	Toluene	5	
108-90-7-----	Chlorobenzene	20	
100-41-4-----	Ethylbenzene	26	
100-42-5-----	Styrene	5	U
1330-20-7-----	Total xylenes	56	

1E
VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

EPA SAMPLE NO.

QLL1

1 Name: VERSAR INC. Contract: _____
Lab Code: VERSAR Case No.: 4014A SAS No.: _____ SDG No.: B2
Matrix: (soil/water) WATER Lab Sample ID: 38587
Sample wt/vol: 5.0 (g/mL) ML Lab File ID: S1249
Level: (low/med) LOW Date Received: 11/30/90
% Moisture: not dec. _____ Date Analyzed: 12/06/90
Column (pack/cap) CAP Dilution Factor: 1.0

Number TICs found: 2

CONCENTRATION UNITS:
(ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1.	UNKNOWN	6.22	7.0	J
2. 167-49-7	FURAN, TETRAHYDRO-	8.37	13	J

1B
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

QLL1

L. Name: VERSAR INC. Contract: _____

Lab Code: VERSAR Case No.: 4014 SAS No.: _____ SDG No.: 2

Matrix: (soil/water) WATER Lab Sample ID: 38592

Sample wt/vol: 980 (g/mL) ML Lab File ID: Z6916

Level: (low/med) LOW Date Received: 11/30/90

% Moisture: not dec. _____ dec. _____ Date Extracted: 12/03/90

Extraction: (SepF/Cont/Sonc) CONT Date Analyzed: 12/15/90

GPC Cleanup: (Y/N) N pH: _____ Dilution Factor: 1.00

CONCENTRATION UNITS:
(ug/L or ug/Kg) UG/L

CAS NO. COMPOUND Q

108-95-2-----	Phenol	10	U
111-44-4-----	bis(2-Chloroethyl) ether	10	U
95-57-8-----	2-Chlorophenol	10	U
541-73-1-----	1,3-Dichlorobenzene	10	U
106-46-7-----	1,4-Dichlorobenzene	10	U
100-51-6-----	Benzyl alcohol	10	U
95-50-1-----	1,2-Dichlorobenzene	10	U
95-48-7-----	2-Methylphenol	10	U
108-60-1-----	bis(2-Chloroisopropyl) ether	10	U
106-44-5-----	4-Methylphenol	10	U
621-64-7-----	N-Nitroso-di-n-propylamine	10	U
67-72-1-----	Hexachloroethane	10	U
98-95-3-----	Nitrobenzene	10	U
78-59-1-----	Isophorone	10	U
88-75-5-----	2-Nitrophenol	10	U
105-67-9-----	2,4-Dimethylphenol	10	U
65-85-0-----	Benzoic Acid	51	U
111-91-1-----	bis(2-Chloroethoxy) methane	10	U
120-83-2-----	2,4-Dichlorophenol	10	U
120-82-1-----	1,2,4-Trichlorobenzene	10	U
91-20-3-----	Naphthalene	10	U
106-47-8-----	4-Chloroaniline	10	U
87-68-3-----	Hexachlorobutadiene	10	U
59-50-7-----	4-Chloro-3-methylphenol	10	U
91-57-6-----	2-Methylnaphthalene	10	U
77-47-4-----	Hexachlorocyclopentadiene	10	U
88-06-2-----	2,4,6-Trichlorophenol	10	U
95-95-4-----	2,4,5-Trichlorophenol	51	U
91-58-7-----	2-Chloronaphthalene	10	U
88-74-4-----	2-Nitroaniline	51	U
131-11-3-----	Dimethylphthalate	10	U
208-96-8-----	Acenaphthylene	10	U
606-20-2-----	2,6-Dinitrotoluene	10	U

1C
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

QLL1

I Name: VERSAR INC. Contract: _____

Lab Code: VERSAR Case No.: 4014 SAS No.: _____ SDG No.: 2

Matrix: (soil/water) WATER Lab Sample ID: 38592

Sample wt/vol: 980 (g/mL) ML Lab File ID: Z6916

Level: (low/med) LOW Date Received: 11/30/90

% Moisture: not dec. _____ dec. _____ Date Extracted: 12/03/90

Extraction: (SepF/Cont/Sonc) CONT Date Analyzed: 12/15/90

GPC Cleanup: (Y/N) N pH: _____ Dilution Factor: 1.00

CONCENTRATION UNITS:

CAS NO. COMPOUND (ug/L or ug/Kg) UG/L Q

99-09-2-----	3-Nitroaniline	51	U
83-32-9-----	Acenaphthene	10	U
51-28-5-----	2,4-Dinitrophenol	51	U
100-02-7-----	4-Nitrophenol	51	U
132-64-9-----	Dibenzofuran	10	U
121-14-2-----	2,4-Dinitrotoluene	10	U
84-66-2-----	Diethylphthalate	10	U
7005-72-3-----	4-Chlorophenyl-phenylether	10	U
86-73-7-----	Fluorene	10	U
100-01-6-----	4-Nitroaniline	51	U
534-52-1-----	4,6-Dinitro-2-methylphenol	51	U
86-30-6-----	N-nitrosodiphenylamine (1)	10	U
101-55-3-----	4-Bromophenyl-phenylether	10	U
118-74-1-----	Hexachlorobenzene	10	U
87-86-5-----	Pentachlorophenol	51	U
85-01-8-----	Phenanthrene	10	U
120-12-7-----	Anthracene	10	U
84-74-2-----	Di-n-butylphthalate	10	U
206-44-0-----	Fluoranthene	10	U
129-00-0-----	Pyrene	10	U
85-68-7-----	Butylbenzylphthalate	10	U
91-94-1-----	3,3'-Dichlorobenzidine	20	U
56-55-3-----	Benzo(a)anthracene	10	U
218-01-9-----	Chrysene	10	U
117-81-7-----	bis(2-Ethylhexyl)phthalate	10	U
117-84-0-----	Di-n-octyl phthalate	10	U
205-99-2-----	Benzo(b)fluoranthene	10	U
207-08-9-----	Benzo(k)fluoranthene	10	U
50-32-8-----	Benzo(a)pyrene	10	U
193-39-5-----	Indeno(1,2,3-cd)pyrene	10	U
53-70-3-----	Dibenz(a,h)anthracene	10	U
191-24-2-----	Benzo(g,h,i)perylene	10	U

(1) - Cannot be separated from Diphenylamine

1F
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

EPA SAMPLE NO.

QLL1

L Name: VERSAR INC. Contract: _____

Lab Code: VERSAR Case No.: 4014 SAS No.: _____ SDG No.: 2

Matrix: (soil/water) WATER Lab Sample ID: 38592

Sample wt/vol: 980 (g/mL) ML Lab File ID: Z6916

Level: (low/med) LOW Date Received: 11/30/90

% Moisture: not dec. _____ dec. _____ Date Extracted: 12/03/90

Extraction: (SepF/Cont/Sonc) CONT Date Analyzed: 12/15/90

GPC Cleanup: (Y/N) N pH: _____ Dilution Factor: 1.00

CONCENTRATION UNITS:

(ug/L or ug/Kg) UG/L

Number TICs found: 15

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1.	UNKNOWN	2.80	31	J
2.	UNKNOWN	3.43	10	J
3.	UNKNOWN SUBSTITUTED BENZENE	3.68	20	J
4.	UNKNOWN SUBSTITUTED BENZENE	4.07	24	J
5.	UNKNOWN SUBSTITUTED BENZENE	5.35	14	J
6.	UNKNOWN KETONE	7.35	20	J
7. 540-97-6	CYCLOHEXASILOXANE, DODECAMET	9.24	33	J
8.	UNKNOWN	10.32	12	J
9.	UNKNOWN SILOXANE	11.07	16	J
10. 134-62-3	BENZAMIDE, N,N-DIETHYL-3-MET	12.14	18	J
11.	UNKNOWN	13.02	16	J
12.	UNKNOWN	14.62	14	J
13.	UNKNOWN	15.20	8.2	J
14.	UNKNOWN	18.07	27	J
15.	UNKNOWN	18.80	8.2	J

1D
PESTICIDE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

QLL1

Lab Name: _____ VERSAR, INC. _____ Contract: _____

Lab Code: VERSAR Case No.: URSQUEEN SAS No.:

SDG No.: _____

Matrix: (soil/water) WATER

Lab Sample ID: __38596

Sample wt/vol: 1050 (g/ml) ML

Lab File ID: ____

Level: (low/med) __LOW__

Date Received: __11/30/90

Moisture: not dec. _____ dec. _____

Date Extracted: __12/03/90

Extraction: (SepF/Cont/Sonc) _____ CONT

Date Analyzed: __12/29/90

GPC Cleanup: (Y/N) __N__ pH: _____

Dilution Factor: 1.0

CAS NO.	COMPOUND	CONCENTRATION UNITS: (ug/L or ug/Kg) _UG/L	Q
---------	----------	---	---

319-84-6	alpha-BHC	0.05	IU
319-85-7	beta-BHC	0.05	IU
319-86-8	delta-BHC	0.05	IU
58-89-9	gamma-BHC (Lindane)	0.05	IU
76-44-8	Heptachlor	0.05	IU
309-00-2	Aldrin	0.05	IU
1024-57-3	Heptachlor Epoxide	0.05	IU
959-98-8	Endosulfan I	0.05	IU
60-57-1	Dieldrin	0.10	IU
72-55-9	4,4'-DDE	0.10	IU
72-20-8	Endrin	0.10	IU
33213-65-9	Endosulfan II	0.10	IU
72-54-8	4,4'-DDD	0.10	IU
1031-07-8	Endosulfan Sulfate	0.10	IU
50-29-3	4,4'-DDT	0.10	IU
72-43-5	Methoxychlor	0.48	IU
53494-70-5	Endrin Ketone	0.10	IU
5103-71-9	alpha-Chlordane	0.48	IU
5103-74-2	gamma-Chlordane	0.48	IU
8001-35-2	Toxaphene	0.95	IU
12674-11-2	Aroclor-1016	0.48	IU
11104-28-2	Aroclor-1221	0.48	IU
11141-16-5	Aroclor-1232	0.48	IU
53469-21-9	Aroclor-1242	0.48	IU
12672-29-6	Aroclor-1248	0.48	IU
11097-69-1	Aroclor-1254	0.95	IU
11096-82-5	Aroclor-1260	0.95	IU

U.S. EPA - CLP

1
INORGANIC ANALYSES DATA SHEET

EPA SAMPLE NO.

~~E-1~~
L-1

Lab Name: VERSAR LABORATORIES INC. Contract: 35216.03
 Lab Code: VERSAR Case No.: 4014 SAS No.: SDG No.: E-1
 Matrix (soil/water): WATER Lab Sample ID: 38600
 Level (low/med): LOW Date Received: 11/30/90
 % Solids: 0.0

Concentration Units (ug/L or mg/kg dry weight): UG/L

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum	885	—		P
7440-36-0	Antimony	23.0	U		P
7440-38-2	Arsenic	11.9	—		F
7440-39-3	Barium	2030	—		P
7440-41-7	Beryllium	4.6	B		P
7440-43-9	Cadmium	5.0	U		P
7440-70-2	Calcium	203000	—		P
7440-47-3	Chromium	5.0	U		P
7440-48-4	Cobalt	18.2	B		P
7440-50-8	Copper	4.3	B		P
7439-89-6	Iron	206000	—		P
7439-92-1	Lead	14.1	—		F
7439-95-4	Magnesium	60100	—		P
7439-96-5	Manganese	918	—		P
7439-97-6	Mercury	0.20	U		CV
7440-02-0	Nickel	32.6	B		P
7440-09-7	Potassium	108000	—		P
7782-49-2	Selenium	3.0	U	WN	F
7440-22-4	Silver	28.4	—		P
7440-23-5	Sodium	269000	—		P
7440-28-0	Thallium	10.0	U		F
7440-62-2	Vanadium	13.1	B		P
7440-66-6	Zinc	68.7	—		P
	Cyanide	10.0	U		AS

Color Before: BROWN Clarity Before: CLOUDY Texture: _____
 Color After: YELLOW Clarity After: CLEAR Artifacts: _____

Comments:

THE CYANIDE LAB SAMPLE ID NUMBER IS 38604; THE EPA SAMPLE NUMBER
 PREFIX IS "Q/L";

1A
VOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

QL-L-2

L Name: VERSAR INC. Contract: _____

Lab Code: VERSAR Case No.: 4022 SAS No.: _____ SDG No.: 3

Matrix: (soil/water) WATER Lab Sample ID: 38769

Sample wt/vol: 5.0 (g/mL) ML Lab File ID: Y5175

Level: (low/med) LOW Date Received: 12/01/90

% Moisture: not dec. _____ Date Analyzed: 12/07/90

Column: (pack/cap) CAP Dilution Factor: 1.0

CAS NO. COMPOUND CONCENTRATION UNITS:
(ug/L or ug/Kg) UG/L Q

74-87-3-----	Chloromethane	10	U
74-83-9-----	Bromomethane	10	U
75-01-4-----	Vinyl chloride	10	U
75-00-3-----	Chloroethane	10	U
75-09-2-----	Methylene chloride	9	B
67-64-1-----	Acetone	10	U
75-15-0-----	Carbon disulfide	5	U
75-35-4-----	1,1-Dichloroethene	5	U
75-34-3-----	1,1-Dichloroethane	5	U
540-59-0-----	1,2-Dichloroethene (total)	5	U
67-66-3-----	Chloroform	5	U
107-06-2-----	1,2-Dichloroethane	5	U
78-93-3-----	2-Butanone	10	U
71-55-6-----	1,1,1-Trichloroethane	5	U
56-23-5-----	Carbon tetrachloride	5	U
108-05-4-----	Vinyl acetate	10	U
75-27-4-----	Bromodichloromethane	5	U
78-87-5-----	1,2-Dichloropropane	5	U
10061-01-5-----	cis-1,3-Dichloropropene	5	U
79-01-6-----	Trichloroethene	5	U
124-48-1-----	Dibromochloromethane	5	U
79-00-5-----	1,1,2-Trichloroethane	5	U
71-43-2-----	Benzene	5	U
10061-02-6-----	Trans-1,3-dichloropropene	5	U
75-25-2-----	Bromoform	5	U
108-10-1-----	4-Methyl-2-pentanone	10	U
591-78-6-----	2-Hexanone	10	U
127-18-4-----	Tetrachloroethene	5	U
79-34-5-----	1,1,2,2-Tetrachloroethane	5	U
108-88-3-----	Toluene	5	U
108-90-7-----	Chlorobenzene	5	U
100-41-4-----	Ethylbenzene	5	U
100-42-5-----	Styrene	5	U
1330-20-7-----	Total xylenes	5	U

1E
VOLATILE ORGANICS ANALYSIS DATA SHEET
TENTATIVELY IDENTIFIED COMPOUNDS

EPA SAMPLE NO.

QL-L-2

Lab Name: VERSAR INC. Contract: _____

Lab Code: VERSAR Case No.: 4022 SAS No.: _____ SDG No.: 3

Matrix: (soil/water) WATER Lab Sample ID: 38769

Sample wt/vol: 5.0 (g/mL) ML Lab File ID: Y5175

Level: (low/med) LOW Date Received: 12/01/90

% Moisture: not dec. _____ Date Analyzed: 12/07/90

Column (pack/cap) CAP Dilution Factor: 1.0

Number TICs found: 1 CONCENTRATION UNITS:
(ug/L or ug/Kg) UG/L

CAS NUMBER	COMPOUND NAME	RT	EST. CONC.	Q
1.	UNKNOWN	8.13	6.0	J

1B
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

QLL2

I Name: VERSAR INC. Contract: _____

Lab Code: VERSAR Case No.: 4022A SAS No.: _____ SDG No.: B3

Matrix: (soil/water) WATER Lab Sample ID: 38780

Sample wt/vol: 1050 (g/mL) ML Lab File ID: T5556

Level: (low/med) LOW Date Received: 12/01/90

% Moisture: not dec. _____ dec. _____ Date Extracted: 12/05/90

Extraction: (SepF/Cont/Sonc) CONT Date Analyzed: 01/04/91

GPC Cleanup: (Y/N) N pH: _____ Dilution Factor: 1.00

CAS NO. COMPOUND CONCENTRATION UNITS:
(ug/L or ug/Kg) UG/L Q

108-95-2-----	Phenol	10	U
111-44-4-----	bis(2-Chloroethyl) ether	10	U
95-57-8-----	2-Chlorophenol	10	U
541-73-1-----	1,3-Dichlorobenzene	10	U
106-46-7-----	1,4-Dichlorobenzene	10	U
100-51-6-----	Benzyl alcohol	10	U
95-50-1-----	1,2-Dichlorobenzene	10	U
95-48-7-----	2-Methylphenol	10	U
108-60-1-----	bis(2-Chloroisopropyl) ether	10	U
106-44-5-----	4-Methylphenol	10	U
621-64-7-----	N-Nitroso-di-n-propylamine	10	U
67-72-1-----	Hexachloroethane	10	U
98-95-3-----	Nitrobenzene	10	U
78-59-1-----	Isophorone	10	U
88-75-5-----	2-Nitrophenol	10	U
105-67-9-----	2,4-Dimethylphenol	10	U
65-85-0-----	Benzoic Acid	36	JX
111-91-1-----	bis(2-Chloroethoxy) methane	10	U
120-83-2-----	2,4-Dichlorophenol	10	U
120-82-1-----	1,2,4-Trichlorobenzene	10	U
91-20-3-----	Naphthalene	10	U
106-47-8-----	4-Chloroaniline	10	U
87-68-3-----	Hexachlorobutadiene	10	U
59-50-7-----	4-Chloro-3-methylphenol	10	U
91-57-6-----	2-Methylnaphthalene	10	U
77-47-4-----	Hexachlorocyclopentadiene	10	U
88-06-2-----	2,4,6-Trichlorophenol	10	U
95-95-4-----	2,4,5-Trichlorophenol	48	U
91-58-7-----	2-Chloronaphthalene	10	U
88-74-4-----	2-Nitroaniline	48	U
131-11-3-----	Dimethylphthalate	10	U
208-96-8-----	Acenaphthylene	10	U
606-20-2-----	2,6-Dinitrotoluene	10	U

1C
SEMIVOLATILE ORGANICS ANALYSIS DATA SHEET

EPA SAMPLE NO.

QLL2

Name: VERSAR INC. Contract: _____

Lab Code: VERSAR Case No.: 4022A SAS No.: _____ SDG No.: B3

Matrix: (soil/water) WATER Lab Sample ID: 38780

Sample wt/vol: 1050 (g/mL) ML Lab File ID: T5556

Level: (low/med) LOW Date Received: 12/01/90

% Moisture: not dec. _____ dec. _____ Date Extracted: 12/05/90

Extraction: (SepF/Cont/Sonc) CONT Date Analyzed: 01/04/91

CPC Cleanup: (Y/N) N pH: _____ Dilution Factor: 1.00

CONCENTRATION UNITS:

CAS NO. COMPOUND (ug/L or ug/Kg) UG/L Q

99-09-2-----	3-Nitroaniline	48	U
83-32-9-----	Acenaphthene	10	U
51-28-5-----	2,4-Dinitrophenol	48	U
100-02-7-----	4-Nitrophenol	48	U
132-64-9-----	Dibenzofuran	10	U
121-14-2-----	2,4-Dinitrotoluene	10	U
84-66-2-----	Diethylphthalate	10	U
7005-72-3-----	4-Chlorophenyl-phenylether	10	U
86-73-7-----	Fluorene	10	U
100-01-6-----	4-Nitroaniline	48	U
534-52-1-----	4,6-Dinitro-2-methylphenol	48	U
86-30-6-----	N-nitrosodiphenylamine (1)	10	U
101-55-3-----	4-Bromophenyl-phenylether	10	U
118-74-1-----	Hexachlorobenzene	10	U
87-86-5-----	Pentachlorophenol	48	U
85-01-8-----	Phenanthrene	10	U
120-12-7-----	Anthracene	10	U
84-74-2-----	Di-n-butylphthalate	10	U
206-44-0-----	Fluoranthene	10	U
129-00-0-----	Pyrene	10	U
85-68-7-----	Butylbenzylphthalate	10	U
91-94-1-----	3,3'-Dichlorobenzidine	19	U
56-55-3-----	Benzo(a)anthracene	10	U
218-01-9-----	Chrysene	10	U
117-81-7-----	bis(2-Ethylhexyl)phthalate	10	U
117-84-0-----	Di-n-octyl phthalate	10	U
205-99-2-----	Benzo(b)fluoranthene	10	U
207-08-9-----	Benzo(k)fluoranthene	10	U
50-32-8-----	Benzo(a)pyrene	10	U
193-39-5-----	Indeno(1,2,3-cd)pyrene	10	U
53-70-3-----	Dibenz(a,h)anthracene	10	U
191-24-2-----	Benzo(g,h,i)perylene	10	U

(1) - Cannot be separated from Diphenylamine

U.S. EPA - CLP

1
INORGANIC ANALYSES DATA SHEET

EPA SAMPLE NO.

L-2

Lab Name: VERSAR LABORATORIES INC. _____

Contract: 35216.03 _____

Lab Code: VERSAR Case No.: 4014 _____

SAS No.: _____

SDG No.: E-1 _____

Matrix (soil/water): WATER _____

Lab Sample ID: 38800 _____

Level (low/med): LOW _____

Date Received: 12/01/90

% Solids: 0.0

Concentration Units (ug/L or mg/kg dry weight): UG/L _____

CAS No.	Analyte	Concentration	C	Q	M
7429-90-5	Aluminum	6220	—	—	P
7440-36-0	Antimony	23.0	U	—	P
7440-38-2	Arsenic	3.7	B	—	F
7440-39-3	Barium	601	—	—	P
7440-41-7	Beryllium	2.4	B	—	P
7440-43-9	Cadmium	5.0	U	—	P
7440-70-2	Calcium	321000	—	—	P
7440-47-3	Chromium	5.0	U	—	P
7440-48-4	Cobalt	27.3	B	—	P
7440-50-8	Copper	28.1	—	—	P
7439-89-6	Iron	58700	—	—	P
7439-92-1	Lead	17.4	—	—	F
7439-95-4	Magnesium	114000	—	—	P
7439-96-5	Manganese	1220	—	—	P
7439-97-6	Mercury	0.20	U	—	CV
7440-02-0	Nickel	55.7	—	—	P
7440-09-7	Potassium	198000	—	—	P
7782-49-2	Selenium	30.0	U	WN	F
7440-22-4	Silver	6.5	B	—	P
7440-23-5	Sodium	440000	—	—	P
7440-28-0	Thallium	2.0	U	—	F
7440-62-2	Vanadium	22.6	B	—	P
7440-66-6	Zinc	96.1	—	—	P
	Cyanide	10.0	U	—	AS

Color Before: COLORLESS

Clarity Before: CLEAR _____

Texture: _____

Color After: YELLOW _____

Clarity After: CLEAR _____

Artifacts: _____

Comments:

THE CYANIDE LAB SAMPLE ID NUMBER IS 38809; THE EPA SAMPLE NUMBER
PREFIX IS "Q/L";

APPENDIX J
ADDITIONS/CHANGES TO REGISTRY OF
INACTIVE HAZARDOUS WASTE DISPOSAL SITES

NEW YORK STATE DEPARTMENT OF ENVIRONMENTAL CONSERVATION
DIVISION OF HAZARDOUS WASTE REMEDIATIONOriginal—BHSU
Copy—REGION
Copy—DEE
Copy—DOH
Copy—PREPARERADDITIONS/CHANGES TO REGISTRY
OF INACTIVE HAZARDOUS WASTE DISPOSAL SITES

1. SITE NAME Queensbury Landfill		2. SITE NO. 517005	3. TOWN Queensbury	4. COUNTY Warren
5. REGION 5	6. CLASSIFICATION Current <u>2a</u> / Proposed _____		7. ACTIVITY ☐ Add ☐ Reclassify ☐ Delist ☐ Modify _____	
8a. DESCRIBE LOCATION OF SITE (Attach U.S.G.S. Topographic Map showing site location). Exit 20 off I-87, north on Route 9 to Route 149 east to Ridge Road (Route 96), turn right on (South) for 1 mile on left.				
b. Quadrangle <u>Dutnam Mtn.</u> c. Site Latitude <u>43°23'27"</u> Longitude <u>73°37'14"</u> d. Tax Map Number _____				
9a. BRIEFLY DESCRIBE THE SITE (Attach site plan showing disposal/sampling locations). The Queensbury Landfill is an active municipal landfill. A sand and gravel operation is currently ongoing in the northwest portion of the property.				
b. Area <u>approximately 50</u> acres c. EPA ID Number <u>NYD000512590</u> d. PA/SI ☐ Yes ☐ No				
e. Completed: ☒ Phase I ☒ Phase II ☐ PSA ☐ Sampling				
10. BRIEFLY LIST THE TYPE AND QUANTITY OF THE HAZARDOUS WASTE AND THE DATES THAT IT WAS DISPOSED OF AT THIS SITE An unknown quantity of paint sludge, paper sludge and alleged PCB capacitors were disposed of onsite. Dates of disposal are unknown.				
11a. SUMMARIZED SAMPLING DATA ATTACHED ☐ Air ☒ Groundwater ☒ Surface Water ☐ Soil ☐ Waste ☐ EP Tox ☐ TCLP				
b. List contravened parameters and values Groundwater: 1,1,1-trichloroethane, 15 ppb, Iron, 21,000 ppb, Manganese 1,710 ppb, Sodium, 178,000 ppb				
12. SITE IMPACT DATA				
a. Nearest surface water: Distance <u>400</u> ft. Direction <u>South</u> Classification <u>A</u>				
b. Nearest groundwater: Depth <u>30</u> ft. Flow Direction <u>South-southeast</u> ☐ Sole Source ☐ Primary ☐ Principal				
c. Nearest water supply: Distance <u>1000</u> ft. Direction _____ Active ☐ Yes ☐ No				
d. Nearest building: Distance <u>onsite</u> ft. Direction _____ Use <u>landfill office trailer</u>				
e. Crops or livestock on site? ☐ Yes ☒ No				
f. Exposed hazardous waste? ☐ Yes ☒ No				
g. Controlled site access? ☐ Yes ☒ No				
h. Documented fish or wildlife mortality? ☐ Yes ☒ No				
i. Impact on special status fish or wildlife resource? ☐ Yes ☒ No				
j. Within a State Economic Development Zone? ☐ Yes ☒ No				
k. For Class 2a: Code _____ Health Model Score _____				
l. For Class 2: Priority Category _____				
m. HRS Score <u>Sm=24.78</u> , Sfc=0.00, SDC=25.00				
n. Significant Threat ☐ Yes ☒ No				
13. SITE OWNERS NAME Town of Queensbury		14. ADDRESS Bay and Haviland Rd., Queensbury		15. TELEPHONE NUMBER NY 518-792-5832
16. PREPARER Phyllis Rettke/Geologist/URS Consultants, Inc.				
Name, Title and Organization <u>Phyllis A. Rettke</u>				
Date <u>3/26/91</u>				
Signature <u>Phyllis A. Rettke</u>				
17. APPROVED				
Name, Title and Organization				

DRILLING SUMMARY

Geologist:

Scott Swanson

Drilling Company:

C.D.S.

Driller:

John Coyle

Date:


10/11/90-10/17/90

GEOLOGIC LOG

depth(ft.)	lithology
0-35	cobbles, boulders
35-67	gravelly, sandy cobbles
67-72	fine-coarse sand
72-76	sandy cobbles
76-86	fine-medium sand
86-94	gravelly, sandy cobbles
94-97	coarse sand
110-116	fine sand
116-160	sandy gravel
160-180	very coarse, multi-colored sands

WELL DESIGN

CASING MATERIAL		SCREEN MATERIAL		SEAL MATERIAL	
Surface:	Steel	Type:	PVC	Seal #1 Type:	Benseal Slurry
				Setting:	19-150'
Monitor:	PVC	Slot Size:	0.010 inch	Seal #2 Type:	Cement Grout
				Setting:	0-19'
FILTER MATERIAL		ROCK CORING		LEGEND	
Type:	#1 Silica Sand	Cored Interval:			Cement/Bentonite Grout
		Core Diameter:			Bentonite Seal
Setting:	150-175'	Reamed Diameter:			Silica Sandpack
Client:	NYSDEC Phase 2	Project:	Queensbury Landfill	Project Number:	35231.05
URS Consultants Inc.		Monitoring Well Constuction Details		Well Number:	MW-1




CASING MATERIAL		SCREEN MATERIAL		SEAL MATERIAL	
Surface:	Steel	Type:	PVC	Seal #1 Type	Bentonite Pellets
				Setting:	104.5-107'
Monitor:	PVC	Slot Size:	0.010 inch	Seal #2 Type	Benseal Slurry
				Setting:	3-104.5'
				Seal #3 Type	Portland Cement
				Setting:	0-3'
FILTER MATERIAL		ROCK CORING		LEGEND	
Type:	#1 Silica Sand	Cored Interval:			Cement/Bentonite Grout
		Core Diameter:			Bentonite Seal
Setting:	107-135'	Reamed Diameter:			Silica Sandpack
Client: NYSDEC Phase 2		Project: Queensbury Landfill		Project Number: 35231.05	
URS Consultants Inc.		Monitoring Well Constuction Details		Well Number: MW-2	

DRILLING SUMMARY
Geologist: Scott Swanson
Drilling Company: C.D.S.
Driller: Dick Miller
Date: 11/5/90-11/8/90

GEOLOGIC LOG

depth(ft.)	lithology
0-16	cobbles
16-42	gravelly, sandy cobbles
42-70	fine-medium sand
70-73	fine gravel
73-91	fine-coarse sand
91-94	cobbles
94-101	fine sand
101-145	sandy cobbles, boulder zone
145-165	fine-medium sand
165-182	fine-medium sand with a little coarse sand

WELL DESIGN



CASING MATERIAL		SCREEN MATERIAL	SEAL MATERIAL
Surface: Steel		Type: PVC	Seal #1 Type: Benseal Slurry Setting: 24-155'
Monitor: PVC		Slot Size: 0.010 inch	Seal #2 Type: Portland Cement Setting: 0-24'
FILTER MATERIAL		ROCK CORING	LEGEND
Type: #1 Silica Sand		Cored Interval:	 Cement/Bentonite Grout
Setting: 155-180'		Core Diameter:	 Bentonite Seal
		Reamed Diameter:	 Silica Sandpack
Client: NYSDEC Phase 2	Project: Queensbury Landfill	Project Number: 35231.05	
URS Consultants Inc.	Monitoring Well Construction Details	Well Number: MW-3	

DRILLING SUMMARY

Geologist:

Scott Swanson

Drilling Company:

C.D.S.

Driller:

John Coyle

Date:

11/2/90

GEOLOGIC LOG

depth(ft.)	lithology
0-22	sandy gravel, some silt

WELL DESIGN**CASING MATERIAL**

Surface: Steel

Monitor: PVC

SCREEN MATERIAL

Type: PVC

Slot Size: 0.010 inch

SEAL MATERIALSeal #1 Type: Bentonite Pellets
Setting: 2-2.5'Seal #2 Type: Portland Cement
Setting: 0-2'**FILTER MATERIAL**

Type: #1 Silica Sand


Setting: 2.5-22'

ROCK CORING

Cored Interval:

Core Diameter:

Reamed Diameter:

LEGEND Cement/Bentonite Grout Bentonite Seal Silica SandpackD
E
P
T
H

Elevation 327.77'

Elevation 325.18'

Protective casing and lockable cap

Ground Level

BOREHOLE

7-3/8 inch dia.

22 feet length

2'

2.5'

3'

WELL RISER

2 inch dia.

5.59 feet length

WELL SCREEN

2 inch dia.

18 feet length

21'

22'

Client: NYSDEC Phase 2

Project: Queensbury Landfill

Project Number: 35231.05

URS
Consultants Inc.Monitoring Well
Constuction Details

Well Number: MW-4

DRILLING SUMMARY

Geologist:

Scott Swanson

Drilling Company:

C.D.S.

Driller:


John Coyle

Date:

10/23/90-10/29/90

GEOLOGIC LOG

depth(ft.)	lithology
0-50	cobbles, boulders
50-92	gravelly, sandy cobbles
92-111	sandy gravel

WELL DESIGN**CASING MATERIAL**

Surface: Steel

Monitor: PVC

SCREEN MATERIAL

Type: PVC

Slot Size: 0.010 inch

SEAL MATERIAL

Seal #1 Type Bentonite Pellets

Setting: 81-86'

Seal #2 Type Benseal Slurry

Setting: 16-81'

Seal #3 Type Portland Cement

Setting: 0-16'

FILTER MATERIAL

Type: #1 Silica Sand

Setting: 86-111'

ROCK CORING

Cored Interval:

Core Diameter:

Reamed Diameter:

LEGEND

	Cement/Bentonite Grout
	Bentonite Seal
	Silica Sandpack

Client: NYSDEC Phase 2

Project: Queensbury Landfill

Project Number: 35231.05

URS
Consultants Inc.Monitoring Well
Constuction Details

Well Number: MW-5

APPENDIX E
WELL DEVELOPMENT/PURGING LOGS

PROJECT TITLE: NYSDEC PHASE II QUEENSBURY LANDFILL

PROJECT NO.: 35231.05

STAFF: SCOTT SWANSON

DATE: 11-8-90

WELL NO.: MW-1

① TOTAL CASING AND SCREEN LENGTH (FT.): 177.23

② CASING INTERNAL DIAMETER (in.): 2"

③ WATER LEVEL BELOW TOP OF CASING (FT.) 160.74

④ VOLUME OF WATER IN CASING (GAL.) 2.7

WELL I.D.	VOL. GAL./FT.
1"	0.04
2"	0.17
3"	0.38
4"	0.66
5"	1.04
6"	1.50
8"	2.60

$$V = 0.0408 \left(\frac{\text{inches}^2}{\text{RADIUS}} \right) \times (\text{①} - \text{③}) = \underline{8.08} \text{ GAL. (3 casings)}$$

$$\left[(1) \times (16.49 \times 12 \text{ inches}) \right] =$$

PARAMETERS	ACCUMULATED VOLUME PURGED (GALLONS)									
	0	8.5	24.1	42.1	68.5					
pH	7.2		7.0	7.0	7.0					
Spec. Cond. (umho)	300		300	300	300					
Turbidity (NTU)	>200		>200	23.1	12.6					
Temperature (°C)	10.7		8.5	8.0	8.0					
TIME	3:55	4:04	4:17	4:30	4:45	5:07				

RATE GAL./MIN. 1.75/min 1.2

COMMENTS:

EQUIPMENT USED - WATERQA HYDROLIFT INERTIAL PUMP
POWERED BY 2000 WATT GENERATOR
High-capacity 1" O.D. High-density polyethylene tubing

WELL DEVELOPMENT/PURGING LOG

PROJECT TITLE: NYSDOC PHASE II QUEENSBURY LANDFILL

PROJECT NO.: 35231-05

STAFF: SCOTT SWANSON

DATE: 11/9 & 10/90

WELL NO.: MW-2

WELL I.D. VOL.
GAL./FT.

① TOTAL CASING AND SCREEN LENGTH (FT.): 133.58

② CASING INTERNAL DIAMETER (in.): 2

③ WATER LEVEL BELOW TOP OF CASING (FT.) 116.20

④ VOLUME OF WATER IN CASING (GAL.) 2.84

1"	0.04
2"	0.17
3"	0.38
4"	0.66
5"	1.04
6"	1.50
8"	2.60

$$V = 0.0408 \left(\frac{2}{2} \right)^2 \times (1 - 3) = 8.51 \text{ GAL. (3 casings)}$$

$$0.0408 \text{ (RADIUS (1") } \times (17.38' \times 12 \text{ in.}) =$$

PARAMETERS	ACCUMULATED VOLUME PURGED (GALLONS)									
	0	21	53	0	14.25	39				
PH	6.8	CLOSED VALVE	6.8	6.8	CLOSED VALVE	6.8				
Spec. Cond. (umho)	1300		1200	1200/1300		1300				
Turbidity (NTU)	>200		>200	359		178.5				
Temperature (°C)	12.1		12.0	12.0		12.0				
TIME	4:09	4:30	5:03 - 5:35	11:10	11:29	12:01 - 12:34				
RATE GAL/MIN.	1	1		.75						

COMMENTS:

STANDARD 5/8" O.D. polyethylene tubing used

PROJECT TITLE: NYSDC PHASE II QUEENSBURY LANDFILL

PROJECT NO.: 35231.05

STAFF: STEVE FRANK

DATE: 11-15-90

WELL NO.: MW-2

WELL I.D.

VOL.
GAL./FT.

① TOTAL CASING AND SCREEN LENGTH (FT.): 133.58

1" 0.04

② CASING INTERNAL DIAMETER (in.): 2

2" 0.17

③ WATER LEVEL BELOW TOP OF CASING (FT.) 116.13

3" 0.38

④ VOLUME OF WATER IN CASING (GAL.) 2.85

4" 0.66

5" 1.04

6" 1.50

8" 2.60

$$V = 0.0408 (\text{RADIUS})^2 \times (\text{①} - \text{③}) = \underline{8.54} \text{ GAL. (3 casings)}$$

$$0.0408 (1)^2 \times (17.45)(12 \text{ in}) =$$

PARAMETERS	ACCUMULATED VOLUME PURGED (GALLONS)										
	0	20	40	60	80	100	120	140	160	180	200
pH	6.54	6.85	6.97	6.64	6.68	6.78	6.95	6.98	6.85	7.11	6.99
Spec. Cond. (µmho)	2660	3420	3170	3430	3700	3340	3500	3320	2900	2560	2580
Turbidity (NTU)	>100	>100	>100	>100	>100	>100	>100	>100	>100	>100	67
Temperature (°C)	TEMP.	PROBE	NOT	WORKING							

COMMENTS: HYDROLIFT
WATERM PUMP USED IN PUMPING

Standard 5/8" O.D. polyethylene tubing

PROJECT TITLE: NYSDOE PHASE II QUEENSBURY LANDFILL

PROJECT NO.: 35231-05

STAFF: SCOTT SWANSON

DATE: 11-9-90

WELL NO.: MW-3

WELL I.D.

VOL.
GAL./FT.

① TOTAL CASING AND SCREEN LENGTH (FT.): 182.5

1"

0.04

2"

0.17

② CASING INTERNAL DIAMETER (in.): 2

3"

0.38

4"

0.66

③ WATER LEVEL BELOW TOP OF CASING (FT.) 164.57

5"

1.04

6"

1.50

④ VOLUME OF WATER IN CASING (GAL.) 2.94

8"

2.60

$$V = 0.0408 \left(\frac{2}{12} \right)^2 \times (182.5 - 164.57) = 8.81 \text{ GAL. (3 casings)}$$

RADIUS INCHES
AGITATE & SURGE

PARAMETERS	ACCUMULATED VOLUME PURGED (GALLONS)									
	0	24.75	43.5	59.5	64.9	67.9	89.65	122.65	179.85	
pH	7.0	7.1	7.0/7.1	7.1		7.2	7.1	7.1/7.2	7.1/7.2	
Spec. Cond. (umho)	800	800-900	900	800/900		900/1000	800	900	1000	
Turbidity (NTU)	>200	>200	199.5	>200		>200	>200	>200	>200	
Temperature (°C)	12.0	12.2	12.4	12.4		13.8	12.0	11.7	16.0	
TIME	10:42	11:15	11:40	12:00	12:08-12:17	12:25	12:54	1:24	2:16	
RATE GAL./MIN	.75	.75	1	1	.6	.75	1.1	1.1		

COMMENTS: EQUIPMENT - WATERM HYDROLIFT INERTIAL PUMP
POWER - 2000 WATT GENERATOR

WELL DEVELOPMENT/PURGING LOG

PROJECT TITLE: NY SDEC PHASE II QUEENSBURY LANDFILL

PROJECT NO.: 35231.05

STAFF: SCOTT SWANSON

DATE: 11-9-90

WELL NO.: MW-4

WELL I.D.

VOL.
GAL./FT.

① TOTAL CASING AND SCREEN LENGTH (FT.): 23.58

1" 0.04

② CASING INTERNAL DIAMETER (in.): 2

2" 0.17

③ WATER LEVEL BELOW TOP OF CASING (FT.) 6.125

3" 0.38

④ VOLUME OF WATER IN CASING (GAL.) 2.85

4" 0.66

5" 1.04

6" 1.50

8" 2.60

$$V = 0.0408 \left(\overset{\text{RADIUS}}{2} \right)^2 \times (1) \times (1) = \underline{8.55} \text{ GAL. (3 casings)}$$

$$0.0408 (1)^2 (17.45 \times 12 \text{ in})$$

PARAMETERS	ACCUMULATED VOLUME PURGED (GALLONS)									
	0	8.8	13.2	18.7		24.2	28.6	31.9	35.2	
pH	6.9	6.8/6.9	6.8/6.9	6.8/6.9	AGITATE AND	6.9	6.9	6.8/6.9	6.8/6.9	
Spec. Cond. (umho)	600	600	600	700	SURGE WELL	700	700	700	706	
Turbidity (NTU)	7200	241	94.5	16.2		>200	264	73.5	35.7	
Temperature (°C)	11.1	11.2	11.1	11.0		11.0	11.0	10.9	10.9	
TIME	3:03	3:11	3:15	3:20	3:24	3:25	3:29	3:32	3:35	
RATE GAL/MIN	1.1	1.1	1.1	1.1	1.1	1.1	1.1	1.1	1.1	

COMMENTS:

WELL DEVELOPMENT/PURGING LOG

PROJECT TITLE: NYSDEC PHASE II QUEENSBURY WANDRILL

PROJECT NO.: 35231.05

STAFF: SCOTT SWANSON

DATE: 11-8-90

WELL NO.: MW-5

WELL I.D. VOL.
GAL./FT.

① TOTAL CASING AND SCREEN LENGTH (FT.):	<u>112.1</u>	1"	0.04
② CASING INTERNAL DIAMETER (in.):	<u>2"</u>	2"	0.17
③ WATER LEVEL BELOW TOP OF CASING (FT.)	<u>93.52</u>	3"	0.38
④ VOLUME OF WATER IN CASING (GAL.)	<u>3.03</u>	4"	0.66
		5"	1.04
		6"	1.50
		8"	2.60

$$V = 0.0408 (\textcircled{2})^2 \times (\textcircled{1} - \textcircled{3}) = \underline{9.09} \text{ GAL. (3 casings)}$$

(1) (18.58 x 12 in.)

PARAMETERS	ACCUMULATED VOLUME PURGED (GALLONS)									
	0	80	AGITATE	120						
pH	6.6	7.2	well surge	7.2						
Spec. Cond. (umho)	200	200		200						
Turbidity (NTU)	>200	4.2		33.6						
Temperature (°C)	9.2	9.2		8.8						
Time	1:35	2:47		3:20						
RATE	1.2 gal / min. EQUIPMENT = WATERRA									

COMMENTS:

HYDROLIFT
INERTIAL
PUMP

POWER: 2000 WATT GENERATOR

PROJECT TITLE: QUEENSBURY LANDFILL NYSDOC PHASE II

PROJECT NO.: 35231.05

STAFF: STEVE FRANK, SCOTT SWANSON

DATE: 11-30-90

WELL NO.: MW-1

WELL I.D.

VOL.
GAL./FT.

① TOTAL CASING AND SCREEN LENGTH (FT.): 177.23

1" 0.04

② CASING INTERNAL DIAMETER (in.): 2"

2" 0.17

RADIUS = 1"

③ WATER LEVEL BELOW TOP OF CASING (FT.) 160

3" 0.38

4" 0.66

④ VOLUME OF WATER IN CASING (GAL.) 2.81

5" 1.04

6" 1.50

8" 2.60

$$V = 0.0408 (\text{RADIUS})^2 \times (\text{①} - \text{③}) = 8.44 \text{ GAL. (3 casings)}$$

$$0.0408 \left\{ (1)^2 (17.23)(12") \right\}$$

PARAMETERS	ACCUMULATED VOLUME PURGED (GALLONS)									
	0	1	35							
pH		7.10	7.10							
Spec. Cond. (µmho)		1125	810							
Turbidity (NTU)		>100	38							
Temperature (°C)		10.6	8.8							
TIME	8:04 AM		9:06							

RATE .6 gpm

COMMENTS:



WELL DEVELOPMENT/PURGING LOG

PROJECT TITLE: QUEENSBURY LANDFILL NYSDEC PHASE II

PROJECT NO.: 35231.05

STAFF: STEVE FRANK, SCOTT SWANSON

DATE: 11-29-90

WELL NO.: MW-2

WELL I.D.

VOL.
GAL./FT.

① TOTAL CASING AND SCREEN LENGTH (FT.): 133.58

1"

0.04

② CASING INTERNAL DIAMETER (in.): 2"

2"

0.17

③ WATER LEVEL BELOW TOP OF CASING (FT.) 116.28

3"

0.38

4"

0.66

④ VOLUME OF WATER IN CASING (GAL.) 2.82

5"

1.04

6"

1.50

8"

2.60

$$V = 0.0408 (2)^2 \times (1 - 3) = 8.47 \text{ GAL. (3 casings)}$$
$$.0408 \{ (1)^2 (17.3') (12 \text{ in.}) \}$$

PARAMETERS	ACCUMULATED VOLUME PURGED (GALLONS)									
	0	3.5	10							
pH		6.90	6.85							
Spec. Cond. (umho)		2900	2600							
Turbidity (NTU)		80	35							
Temperature (°C)		11.8	10.6							

COMMENTS:

PROJECT TITLE: QUEENSBURY LANDFILL NYSDEC PHASE II

PROJECT NO.: 35231.05

STAFF: STEVE FRANK, SCOTT SWANSON

DATE: 11-30-90

WELL NO.: MW-3

① TOTAL CASING AND SCREEN LENGTH (FT.): 182.5

② CASING INTERNAL DIAMETER (in.): 2
RADIUS 1"

③ WATER LEVEL BELOW TOP OF CASING (FT.) 164.25

④ VOLUME OF WATER IN CASING (GAL.) 2.99

WELL I.D.	VOL. GAL./FT.
1"	0.04
2"	0.17
3"	0.38
4"	0.66
5"	1.04
6"	1.50
8"	2.60

$$V = 0.0408 \left(\overset{\text{Radius}}{2} \right)^2 \times \left(\overset{\text{Inches}}{1} \right) \times (① - ③) = \underline{8.94} \text{ GAL. (3 casings)}$$

$$0.0408 \left[(1)^2 \times (182.5' \times 12 \text{ in}) \right]$$

PARAMETERS	ACCUMULATED VOLUME PURGED (GALLONS)									
	0	1	25							
pH		7.13	7.17							
Spec. Cond. (µmho)		2600	2530							
Turbidity (NTU)		7100	45							
Temperature (°C)		11.6	11.3							

RATE: 0.5 gpm

COMMENTS:

PROJECT TITLE: QUEENSBURY LANDFILL NYSDEC PHASE II

PROJECT NO.: 35231.05

STAFF: STEVE FRANK, SCOTT SWANSON

DATE: 11-29-96

WELL NO.: MW-4

WELL I.D. VOL.
GAL./FT.

① TOTAL CASING AND SCREEN LENGTH (FT.): 23.58

1" 0.04

② CASING INTERNAL DIAMETER (in.): 2"

2" 0.17

③ WATER LEVEL BELOW TOP OF CASING (FT.) 6.10

3" 0.38

STREAM GAUGE = 2.24'

4" 0.66

④ VOLUME OF WATER IN CASING (GAL.) 2.85

5" 1.04

6" 1.50

8" 2.60

CTOR
1.4 = π x 3 $V = 0.0408 (\frac{2}{2})^2 \times ((1) - (3)) = 8.55$ GAL. (3 casings)
- in/gal $0.0408 (\text{Radius})^2 (23.58 - 6.10) (12 \text{ in})$

PARAMETERS	ACCUMULATED VOLUME PURGED (GALLONS)										
	0	2	10								
pH		6.85	6.78								
Spec. Cond. (umho)		1450	1450								
Turbidity (NTU)		18	52								
Temperature (°C)		10.3	88								

COMMENTS: SAMPLED @ 8.45 AM



WELL DEVELOPMENT/PURGING LOG

PROJECT TITLE: QUEENSBURY LANDFILL NYSDEC PHASE II

PROJECT NO.: 35231.05

STAFF: STEVE FRANK, SCOTT SWANSON

DATE: 11-28-90

WELL NO.: MW-5

WELL I.D. VOL.
GAL./FT.

① TOTAL CASING AND SCREEN LENGTH (FT.): 112.1

1" 0.04

② CASING INTERNAL DIAMETER (in.): 2"

2" 0.17

③ WATER LEVEL BELOW TOP OF CASING (FT.) 93.53

3" 0.38

④ VOLUME OF WATER IN CASING (GAL.) 3.03

4" 0.66

5" 1.04

6" 1.50

8" 2.60

$$V = 0.0408 (\text{RADIUS})^2 \times (\text{①} - \text{③}) = \underline{9.09} \text{ GAL. (3 casings)}$$

$0.0408 (\text{RADIUS})^2 (18.57 \times 12")$

PARAMETERS	ACCUMULATED VOLUME PURGED (GALLONS)									
	0	.5	15							
pH		6.88	6.85							
Spec. Cond. (umho)		1260	1240							
Turbidity (NTU)		100+	41							
Temperature (°C)		11.8	9.9							
Time	1:48pm									

COMMENTS: SAMPLED WELL @ 2:20 PM

PROJECT TITLE: QUEENSBURY LANDFILL NYSDEC PHASE II

PROJECT NO.: 35231.05

STAFF: STEVE FRANK, SCOTT SWANSON

DATE: 11-29-90

WELL NO.: E-2

WELL I.D.

VOL.
GAL./FT.

① TOTAL CASING AND SCREEN LENGTH (FT.): 20

1" 0.04

② CASING INTERNAL DIAMETER (in.): 2"

2" 0.17

③ WATER LEVEL BELOW TOP OF CASING (FT.) 5.25

3" 0.38

④ VOLUME OF WATER IN CASING (GAL.) 2.41

4" 0.66

5" 1.04

6" 1.50

8" 2.60

$$V = 0.0408 (2)^2 \times (20 - 5.25) = \underline{7.22} \text{ GAL. (3 casings)}$$

$$= 0.0408 [(1)^2 (20 - 5.25)(12 \text{ in.})]$$

PARAMETERS	ACCUMULATED VOLUME PURGED (GALLONS)									
	0	60								
pH		6.85								
Spec. Cond. (umho)		1708								
Turbidity (NTU)		10								
Temperature (°C)		9.8								
TIME	9:15 AM	10:15								
RATE	1 gpm									

COMMENTS:



WELL DEVELOPMENT/PURGING LOG

PROJECT TITLE: QUEENSBURY LANDFILL NYSDEC PHASE II

PROJECT NO.: 35231.05

STAFF: STEVE FRANK, SCOTT SWANSON

DATE: 11-28-90

WELL NO.: E-3 (TORRINGTON CONST. EXISTING WELL)	WELL I.D.	VOL. GAL./FT.
① TOTAL CASING AND SCREEN LENGTH (FT.): <u>135</u>	1"	0.04
② CASING INTERNAL DIAMETER (in.): <u>2"</u>	2"	0.17
③ WATER LEVEL BELOW TOP OF CASING (FT.) <u>89.73</u>	3"	0.38
	4"	0.66
④ VOLUME OF WATER IN CASING (GAL.) <u>66.5</u>	5"	1.04
	6"	1.50
	8"	2.60

$$V = 0.0408 (\text{radius})^2 \times (\text{length}) = 0.0408 \left(\frac{2 \text{ inches}}{2} \right)^2 \times (135 - 89.73)(12") = 200 \text{ GAL. (3 casings)}$$

PARAMETERS	ACCUMULATED VOLUME PURGED (GALLONS)										
	0	1350									
pH		6.78									
Spec. Cond. (umho)		5400									
Turbidity (NTU)		4.5									
Temperature (°C)		11.4									
Time	2:00	3:30pm	pumped ran	15 gpm	Torrington rep submersible pump for 1 1/2 hr.						

COMMENTS: SAMPLED & LABELED G/LE-3 GW

APPENDIX F
HYDRAULIC CONDUCTIVITY TESTING RESULTS

BOUWER AND RICE METHOD FOR INTERPRETATION OF SLUG TESTS: FOR UNCONFINED AND LEAKY CONFINED AQUIFERS.
 TO UTILIZE THIS WORKSHEET, ENTER YOUR DATA AT LOCATIONS MARKED BY AN "*".
 PROGRAM CAN INCLUDE EFFECTS OF SANDPACK DEWATERING (ASSUMING WATER IS RISING WITHIN THE SANDPACK).


#	*TIME min (X)	*DEPTH TO WATER Ft.	DRAWDOWN (Y)	TIME sec (X')	LN (Y)
1	0.020	-0.10	0.100	1.2	-2.3026
2	0.023	-0.08	0.080	1.4	-2.5257
3	0.027	-0.07	0.070	1.6	-2.6593
4	0.083	-0.04	0.040	5.0	-3.2189
5	0.100	-0.02	0.020	6.0	-3.9120
6	0.133	-0.01	0.010	8.0	-4.6052
7	0.183	0.00	0.000	11.0	ERR

*PROJECT NAME	:QUEENSBURY LANDFILL
*PROJECT NO	:35231.05
*WELL NO	:MW-1 (SLUG OUT)
*ANALYST	:MOELLER
*DATE COLLECTED	:12/19/90
*RISER PIPE (ID):	(2 r sub c) = 2.0 in. = 0.0833 (radius in ft.)
*EFFECTIVE SCREEN DIAMETER:	(2 r sub w) = 2.0 in. = 0.0833 (radius in ft.)
*EFFECTIVE SCREEN LENGTH:	(L) = 17.00 Ft.
*MAX DRAWDOWN (IN SUBSET):	(Ymax) = 0.10 Ft.
*STATIC WATER LEVEL:	(SWL) = 0.00 Ft.
*DEPTH FROM SWL TO EFF. SCREEN BOTTOM:	(H) = 17.00 Ft.
*EST. AQUIFER DEPTH (SWL TO AQUIFER BOTTOM):	(D) = 37.00 Ft.
*INCLUDE SANDPACK DEWATERING (ENTER 1 IF YES, 0 IF NO)?	0
*SANDPACK'S SPECIFIC YIELD (Sy) =	0.25

BOUWER AND RICE CURVE COEFFICIENTS:	
RATIO OF L/(r sub w) =	204.00
---LOG OF L/(r sub w) =	2.3096
FOR PARTIALLY PENETRATING WELLS--	
A =	5.97
B =	1.24
FOR FULLY PENETRATING WELLS--	
C =	6.92
---EVALUATION OF LN(Re/(r sub w)):	
CONST.1 =	0.2068
CONST.2 =	5.4806
LN(Re/(r sub w)) =	3.71
EFFECTIVE r sub c (for sandpack dewatering) = 0.0833	
(1/T)(LN(Yo/Yt)) (SLOPE) =	8.26E-02 sec ⁻¹
HYDRAULIC CONDUCTIVITY (K) =	6.26E-05 ft/sec
	1.91E-03 cm/sec
Regression Output:	
Constant	-1.09
Std Err of Y Est	1.78E-01
R Squared	0.9670
No. of Observations	3.0000
Degrees of Freedom	1
X Coefficient(s)	-0.45
Std Err of Coef.	8.26E-02

RATE OF RECOVERY TEST: WELL MW-1

(SLUG OUT)



BOUWER AND RICE METHOD FOR INTERPRETATION OF SLUG TESTS: FOR UNCONFINED AND LEAKY CONFINED AQUIFERS.
 TO UTILIZE THIS WORKSHEET, ENTER YOUR DATA AT LOCATIONS MARKED BY AN "*".
 PROGRAM CAN INCLUDE EFFECTS OF SANDPACK DEWATERING (ASSUMING WATER IS RISING WITHIN THE SANDPACK).

#	*TIME min (X)	*DEPTH TO WATER Ft.	DRAWDOWN (Y)	TIME sec (X')	LN (Y)
1	0.05	-0.76	0.750	3.0	-0.2877
2	0.06	-0.69	0.680	3.6	-0.3857
3	0.08	-0.59	0.580	4.8	-0.5447
4	0.10	-0.50	0.490	6.0	-0.7133
5	0.11	-0.42	0.410	6.6	-0.8916
6	0.13	-0.37	0.360	7.8	-1.0217
7	0.15	-0.32	0.310	9.0	-1.1712
8	0.16	-0.29	0.280	9.6	-1.2730
9	0.18	-0.27	0.260	10.8	-1.3471
10	0.20	-0.24	0.230	12.0	-1.4697
11	0.21	-0.23	0.220	12.6	-1.5141
12	0.23	-0.22	0.210	13.8	-1.5606
13	0.25	-0.20	0.190	15.0	-1.6607
14	0.26	-0.19	0.180	15.6	-1.7148
15	0.28	-0.18	0.170	16.8	-1.7720
16	0.30	-0.17	0.160	18.0	-1.8326
17	0.33	-0.16	0.150	19.8	-1.8971
18	0.41	-0.13	0.120	24.6	-2.1203
19	0.50	-0.11	0.100	30.0	-2.3026
20	0.58	-0.09	0.080	34.8	-2.5257
21	0.66	-0.08	0.070	39.6	-2.6593
22	0.75	-0.07	0.060	45.0	-2.8134
23	0.91	-0.06	0.050	54.6	-2.9957
24	1.16	-0.05	0.040	69.6	-3.2189
25	1.41	-0.04	0.030	84.6	-3.5066
26	1.83	-0.03	0.020	109.8	-3.9120
27	3.00	-0.01	0.000	180.0	ERR

*PROJECT NAME	:QUEENSBURY LANDFILL
*PROJECT NO	:35231.05
*WELL NO	:MW-2 (SLUG OUT)
*ANALYST	:MOELLER
*DATE COLLECTED	:12/19/90
*RISER PIPE (ID):	(2 r sub c) = 2.0 in. = 0.0833 (radius in ft.)
*EFFECTIVE SCREEN DIAMETER:	(2 r sub w) = 7.4 in. = 0.3073 (radius in ft.)
*EFFECTIVE SCREEN LENGTH:	(L) = 19.52 Ft.
*MAX DRAWDOWN (IN SUBSET):	(Ymax) = 0.75 Ft.
*STATIC WATER LEVEL:	(SWL) = -0.01 Ft.
*DEPTH FROM SWL TO EFF. SCREEN BOTTOM:	(H) = 19.52 Ft.
*EST. AQUIFER DEPTH (SWL TO AQUIFER BOTTOM):	(D) = 39.52 Ft.
*INCLUDE SANDPACK DEWATERING (ENTER 1 IF YES, 0 IF NO)?	1
*SANDPACK'S SPECIFIC YIELD (Sy)	= 0.25


BOUWER AND RICE CURVE COEFFICIENTS:	
RATIO OF L/(r sub w)	= 63.52
---LOG OF L/(r sub w)	= 1.8029
FOR PARTIALLY PENETRATING WELLS--	
A =	3.47
B =	0.53
FOR FULLY PENETRATING WELLS--	
C =	3.14
---EVALUATION OF LN(Re/(r sub w)):	
CONST.1 =	0.2650
CONST.2 =	4.1757
LN(Re/(r sub w)) =	2.82
EFFECTIVE r sub c (for sandpack dewatering) = 0.1698	
(1/T)(LN(Yo/Yt)) (SLOPE) =	5.17E-04 sec ⁻¹

HYDRAULIC CONDUCTIVITY (K)	= 1.08E-06 ft/sec	<=====
	3.28E-05 cm/sec	<=====

Regression Output:	
Constant	-2.01
Std Err of Y Est	3.07E-02
R Squared	0.9965
No. of Observations	6.0000
Degrees of Freedom	4
X Coefficient(s)	-0.02
Std Err of Coef.	5.17E-04

RATE OF RECOVERY TEST: WELL MW-2

(SLUG OUT)



BOUWER AND RICE METHOD FOR INTERPRETATION OF SLUG TESTS: FOR UNCONFINED AND LEAKY CONFINED AQUIFERS.

TO UTILIZE THIS WORKSHEET, ENTER YOUR DATA AT LOCATIONS MARKED BY AN "*".

PROGRAM CAN INCLUDE EFFECTS OF SANDPACK DEWATERING (ASSUMING WATER IS RISING WITHIN THE SANDPACK).

#	*TIME min (X)	*DEPTH TO WATER Ft.	DRAWDOWN (Y)	TIME sec (X')	LN (Y)
1	0.13	-0.12	0.120	7.8	-2.1203
2	0.15	-0.07	0.070	9.0	-2.6593
3	0.16	-0.06	0.060	9.6	-2.8134
4	0.18	-0.04	0.040	10.8	-3.2189
5	0.21	-0.03	0.030	12.6	-3.5066
6	0.25	-0.02	0.020	15.0	-3.9120
7	0.41	-0.01	0.010	24.6	-4.6052
8	0.58	0.00	0.000	34.8	ERR

*PROJECT NAME	:QUEENSBURY LANDFILL
*PROJECT NO	:35231.05
*WELL NO	:MW-3 (SLUG OUT)
*ANALYST	:MOELLER
*DATE COLLECTED	:12/19/90
*RISER PIPE (ID):	(2 r sub c) = 2.0 in. = 0.0833 (radius in ft.)
*EFFECTIVE SCREEN DIAMETER:	(2 r sub w) = 2.0 in. = 0.0833 (radius in ft.)
*EFFECTIVE SCREEN LENGTH:	(L) = 16.82 Ft.
*MAX DRAWDOWN (IN SUBSET):	(Ymax) = 0.12 Ft.
*STATIC WATER LEVEL:	(SWL) = 0.00 Ft.
*DEPTH FROM SWL TO EFF. SCREEN BOTTOM:	(H) = 16.82 Ft.
*EST. AQUIFER DEPTH (SWL TO AQUIFER BOTTOM):	(D) = 36.82 Ft.
*INCLUDE SANDPACK DEWATERING (ENTER 1 IF YES, 0 IF NO)?	0
*SANDPACK'S SPECIFIC YIELD (Sy) =	0.25

BOUWER AND RICE CURVE COEFFICIENTS:	
RATIO OF L/(r sub w) =	201.84
---LOG OF L/(r sub w) =	2.3050
FOR PARTIALLY PENETRATING WELLS--	
A =	5.94
B =	1.23
FOR FULLY PENETRATING WELLS--	
C =	6.88
---EVALUATION OF LN(Re/(r sub w)):	
CONST.1 =	0.2073
CONST.2 =	5.4806
LN(Re/(r sub w)) =	3.70
EFFECTIVE r sub c (for sandpack dewatering) = 0.0833	
(1/T)(LN(Yo/Yt)) (SLOPE) =	1.86E-02 sec ⁽⁻¹⁾

HYDRAULIC CONDUCTIVITY (K) =	1.42E-05 ft/sec	<=====
	4.33E-04 cm/sec	<=====

Regression Output:	
Constant	-0.86
Std Err of Y Est	9.07E-02
R Squared	0.9763
No. of Observations	5.0000
Degrees of Freedom	3
X Coefficient(s)	-0.21
Std Err of Coef.	1.86E-02

APPENDIX G

ANALYTICAL TESTING RESULTS FROM PREVIOUS INVESTIGATIONS

MI INVENTORY GROUNDWATER QUALITY EVALUATION
ANALYTICAL TESTING RESULTS

ENERGY RESOURCES CO. INC

INORGANIC ANALYSIS

- Report Sheet -

Analyzed for: New York DEC

ERCO ID	CLIENT ID	Cl (mg/l)	F (mg/l)	SO ₄ (mg/l)	TDS (g/l)	COND (umhos/cm)	pH	COLOR (color units)	ODOR (threshold units)	TOC (mg/l)
51-931	57S10-D01	22	<0.10	6	0.47	720	7.2	<5	140	2.0
51-932	57S10-D02	38	0.13	16	0.50	710	7.2	10	6	4.0
51-933	57S10-GWINUPS	44	0.76	15	0.37	580	7.5	<5	ND	2.0

If customer has any questions regarding analysis,
refer to sample in question by its ERCO ID#.

Sample Rcvd. 7/28/81Reported by naL

Date Analysis

Completed 8/25/81Checked by Kale

APPENDIX G (b)

TOWN OF QUEENSBURY QUARTERLY AND ANNUAL TESTING ANALYTICAL RESULTS

QUEENSBURY LANDFILL

Summary of results, quarterly testing.

1980, 1981

*File
Queensbury*

RECEIVED

AUG 19 1982

STATE DEPT. OF HEALTH
GLENS FALLS DISTRICT OFFICE

Office Well

	<u>pH</u>	<u>Chloride, mg/l</u>	<u>Conductivity, us</u>	<u>Iron, mg/l</u>	<u>TOC, mg/l</u>	<u>TDS, mg/l</u>
June 5, 1980	7.9	1.0	265	0.35	7	-
October 24, 1980	8.0	3.4	260	0.40	7	-
January 22, 1981	8.0	2.5	265	0.18	5	154
April 15, 1981	7.9	2.4	250	0.25	5	168
July 14, 1981	8.0	2.5	252	0.15	3	205

Well #2--

June 5, 1980	7.1	15	300	14	11	-
October 24, 1980	6.9	23	700	11	25	-
January 22, 1981	7.3	126	750	7.7	60	-
April 15, 1981	7.1	20	550	13	2	-
July 14, 1981	7.1	28	650	7.0	8	-

Well #3

June 5, 1980	7.3	18	750	27	21	-
October 24, 1980	7.2	19	600	16	6	-
January 22, 1981	7.4	300	550	37	62	-
April 15, 1981	7.6	27	550	165	5	-
July 14, 1981	7.6	21	500	55	10	-

QUEENSBURY LANDFILL

Summary of results, quarterly testing.

1980, 1981

Pond

	<u>pH</u>	<u>Chloride, mg/l</u>	<u>Conductivity, us</u>	<u>Iron, mg/l</u>	<u>TOC, mg/l</u>	<u>TDS, mg/l</u>
March 21, 1980	7.2	21	700	0.90	8	-

Landfill Leachate (Manhole)

March 21, 1980	6.4	22	225	1.8	17	
----------------	-----	----	-----	-----	----	--

Yearly Testing

Parameter	Results, mg/l					
	Office Well		Well #2		Well #3	
	7/21/80	4/15/81	7/21/80	4/15/81	7/21/80	4/15/81
Sulfate, as SO ₄	4	5	15	8	8	20
Nitrite, as N	<0.02	<0.02	<0.02	<0.02	<0.02	<0.02
Nitrate, as N	0.04	<0.02	0.13	0.04	0.15	0.1
Ammonia, as N	<0.06	<0.06	<0.06	<0.06	<0.06	<0.06
TXH	0.06	0.11	0.55	0.40	0.24	4.3
Total Phosphate, as P	<0.04	<0.04	<0.04	0.06	<0.04	<0.04
Phenols	<0.004	----	<0.004	----	<0.004	----
Chromium	<0.005	<0.005	0.1	<0.05	0.1	0.2
Copper	<0.1	0.004	<0.1	0.020	<0.1	0.1
Lead	0.01	<0.01	0.1	<0.1	0.1	0.1
Mercury	<0.001	0.0015	0.0055	<0.0004	0.0042	<0.001
Potassium	1.0	1.6	4.6	1.3	4.1	23
Sodium	11.5	10.5	6.0	11.0	10.2	11
Zinc	1.1	0.63	0.07	<0.05	0.06	0.1
Cyanide	----	<0.003	----	0.005	----	<0.001

MSD-4288-81

May 26, 1981

Subject: Analytical Results

[REDACTED]

Attention: [REDACTED]

Dear [REDACTED]:

The following results were obtained when your samples, received on April 15, 1981, were analyzed following procedures outlined in the 14th Edition of "Standard Methods".

Parameter	Results		
	Well #1	Well #2	Well #3
<u>Quarterly Testing</u>			
pH	7.9	7.1	7.6
Total Dissolved Solids, mg/l	168		
Chloride, mg/l	2.4	20	27
TOC, mg/l	5	2	5
Conductivity, us	260	650	550
Iron, mg/l	0.25	13.0	165
<u>Annual Testing</u>			
Sulfate, mg/l as SO ₄	5	8.5	19.5
Nitrite, mg/l as N	< 0.01	< 0.01	< 0.01
Nitrate, mg/l as N	< 0.01	0.04	0.02
Ammonia, mg/l as N	< 0.06	< 0.06	< 0.06
TKN, mg/l as N	0.11	0.40	4.6
Phosphate, mg/l as P	< 0.03	0.06	< 0.03
Cyanide, mg/l	< 0.003	0.005	< 0.003
Chromium, mg/l	< 0.005	< 0.05	0.28
Copper, mg/l	0.004	0.020	0.27
Lead, mg/l	< 0.01	< 0.1	0.2
Mercury, ug/l	1.5	< 0.4	< 0.4
Potassium	1.55	1.80	28.5
Sodium, mg/l	10.5	11.0	11.5
Zinc, mg/l	0.63	< 0.05	0.60

Sincerely,

Alison E. Carter

Alison E. Carter, Ph.D.
Laboratory Supervisor
Measurement Services Division

Approved

M. Kawahata
M. Kawahata, Ph.D., Mgr., MSD

256-711.0

July 31, 1981

Subject: Analysis of Water

[REDACTED]

The following results were obtained when your samples, received on July 14, 1981, were analyzed following procedures outlined in the 14th Edition of "Standard Methods".

	<u>Office Well</u>	<u>Landfill #1</u>	<u>Wells #2</u>
pH	8.0	7.1	7.6
Total Dissolved Solids, mg/l	205		
Chloride, mg/l	2.5	27.8	23.8
TOC, mg/l	3	8	18
Conductivity, us	262	650	600
Iron, mg/l	0.15	7.0	55

Sincerely,

Alison E. Carter P.S.

Alison E. Carter, Ph.D.
Laboratory Supervisor
Measurement Services Division

Approved

M. Kawahata
M. Kawahata, Ph.D.
Manager
Measurement Services Division

256-119.50

MSD-4691-81

November 25, 1981

Reference: Our quotation 7110-3-3669

Subject: Analysis of Water Samples



The following results were obtained when your samples received 10/19/81, were analyzed following procedures outlined in the 14th Edition of "Standard Methods".

<u>Parameter</u>	<u>Landfill Well #1</u>	<u>Landfill Well #2</u>	<u>Office Well</u>
pH	7.1	7.7	8.1
Chloride, mg/l	28.3	20.7	1.7
TOC, mg/l	28	7	< 1
Conductivity, us	590	680	280
Iron, mg/l	54	22	1.2
Total dissolved solids, mg/l	-	-	163

Sincerely,

Alison E. Carter

Alison E. Carter, Ph.D.
Laboratory Supervisor
Measurement Services Division

Approved

M. Kawahata

M. Kawahata, Ph.D.
Manager
Measurement Services Division

MSD-4910-82

February 22, 1982

Subject: Analysis of Water Samples



The following results were obtained when your samples, received on January 25, 1982, were analyzed following procedures outlined in the 14th Edition of "Standard Methods".

Parameter	Results		
	Well #2	Well #3	Office Well
pH	6.9	7.5	8.0
Total dissolved solids, mg/l			532
Iron, mg/l	22.5	105	0.65
Chloride, mg/l	54.2	59.1	3.5
TOC, mg/l	42	48	<1
Conductivity, us, 25C	900	800	278

Sincerely,

Alison E. Carter


Alison E. Carter, Ph.D.
Laboratory Supervisor
Measurement Services Division

Approved

M. Kawahara

M. Kawahara, Ph.D.
Manager
Measurement Services Division

256-150.00



APPENDIX G (c)

NYSDEC SAMPLING OF INACTIVE HAZARDOUS WASTE SITES
ANALYTICAL TESTING RESULTS

CLIENT NYS DEC
CLIENT ID RH-084-006-001
ERCO ID 22-4652
SAMPLE RECEIVED 6/15/84
ANALYSIS COMPLETED 7/12/84
RESULTS IN ppb (ug/l)

Queensbury Mud pond
ERCO / ENERGY RESOURCES CO. INC.

SUMMARY OF
ORGANIC PRIORITY POLLUTANT ANALYSIS

ACID COMPOUNDS			BASE/NEUTRAL COMPOUNDS		
21A	2,4,6-trichlorophenol	ND	42B	bis(2-chloroisopropyl)ether	ND
22A	p-chloro-m-cresol	ND	43B	bis(2-chloroethoxy)methane	ND
24A	2-chlorophenol	ND	52B	hexachlorobutadiene	ND
31A	2,4-dichlorophenol	ND	53B	hexachlorocyclopentadiene	ND
34A	2,4-dimethylphenol	ND	54B	isophorone	ND
57A	2-nitrophenol	ND	55B	naphthalene	ND
58A	4-nitrophenol	ND	56B	nitrobenzene	ND
59A	2,4-dinitrophenol	ND	61B	N-nitrosodimethylamine	ND
60A	4,6-dinitro-o-cresol	ND	62B	N-nitrosodiphenylamine	ND
64A	pentachlorophenol	ND	63B	N-nitrosodi-n-propylamine	ND
65A	phenol	ND	66B	bis(2-ethylhexyl)phthalate	ND
			67B	butyl benzyl phthalate	ND
			68B	di-n-butyl phthalate	ND
			69B	di-n-octyl phthalate	ND
			70B	diethyl phthalate	ND
			71B	dimethyl phthalate	ND
			72B	benzo(a)anthracene	ND
			73B	benzo(a)pyrene	ND
			74B	3,4-benzofluoranthene	ND
			75B	benzo(k)fluoranthene	ND
			76B	chrysene	ND
			77B	acenaphthylene	ND
			78B	anthracene	ND
			79B	benzo(ghi)perylene	ND
			80B	fluorene	ND
			81B	phenanthrene	ND
			82B	dibenzo(a,h)anthracene	ND
			83B	indeno(1,2,3-cd)pyrene	ND
			84B	pyrene	ND
			129B	2,3,7,8-tetrachlorodibenzo-p-dioxin	ND
BASE/NEUTRAL COMPOUNDS					
1B	acenaphthene	ND			
5B	benzidine	ND			
8B	1,2,4-trichlorobenzene	ND			
9B	hexachlorobenzene	ND			
12B	hexachloroethane	ND			
18B	bis(2-chloroethyl)ether	ND			
20B	2-chloronaphthalene	ND			
25B	1,2-dichlorobenzene	ND			
26B	1,3-dichlorobenzene	ND			
27B	1,4-dichlorobenzene	ND			
28B	3,3-dichlorobenzidine	ND			
35B	2,4-dinitrotoluene	ND			
36B	2,6-dinitrotoluene	ND			
37B	1,2-diphenylhydrazine	ND			
39B	fluoranthene	ND			
40B	4-chlorophenyl phenyl ether	ND			
41B	4-bromophenyl phenyl ether	ND			

ND = None detected above the average
reporting limit of 10ppb for acids
and 10ppb for B/N.

NA = Not applicable.

*Trace concentrations detected below
the average reporting limit.

Reported by: JK
Checked by: JK

Queensbury Lf.
557005

SURROGATE RECOVERIES (%): ACID d₆-phenol 28 BASE/NEUTRAL d₅-nitrobenzene 52

ORGANICS ANALYSIS DATA SHEET

ERCO / ENERGY RESOURCES CO. INC.

CLIENT NYS DEC

CLIENT I.D. RH-084-006-001

ERCO I.D. 22 - 4652

COMPOUND NAME	FRACTION	SCAN NO. OR RETENTION TIME	ESTIMATED CONCENTRATION (ug/kg)
---------------	----------	----------------------------------	---------------------------------------

No unknowns in Acid or B/N fraction

CLIENT NYS DEC
 CLIENT ID RH-084-006-002
 ERCO ID 22-4663S
 SAMPLE RECEIVED 6/15/84
 ANALYSIS COMPLETED
 RESULTS IN ppb (ug/l)

ERCO / ENERGY RESOURCES CO. INC.

SUMMARY OF
 ORGANIC PRIORITY POLLUTANT ANALYSIS

ACID COMPOUNDS			BASE/NEUTRAL COMPOUNDS		
21A	2,4,6-trichlorophenol	ND	42B	bis(2-chloroisopropyl)ether	ND
22A	p-chloro-m-cresol ----- 6% ^a *3		43B	bis(2-chloroethoxy)methane	ND
24A	2-chlorophenol ----- 72% ^a 36		52B	hexachlorobutadiene	ND
31A	2,4-dichlorophenol	ND	53B	hexachlorocyclopentadiene	ND
34A	2,4-dimethylphenol	ND	54B	isophorone	ND
57A	2-nitrophenol	ND	55B	naphthalene	ND
58A	4-nitrophenol ----- 90% ^a 45		56B	nitrobenzene	ND
59A	2,4-dinitrophenol	ND	61B	N-nitrosodimethylamine	ND
60A	4,6-dinitro-o-cresol	ND	62B	N-nitrosodiphenylamine	ND
64A	pentachlorophenol ----- 6% ^a 3*		63B	N-nitrosodi-n-propylamine 318% ^a 159	
65A	phenol ----- 370% ^a 555		66B	bis(2-ethylhexyl)phthalate ----- 42	
			67B	butyl benzyl phthalate ----- *	
			68B	di-n-butyl phthalate ----- 98% ^a 48	
			69B	di-n-octyl phthalate ----- *	
			70B	diethyl phthalate ----- 81	
			71B	dimethyl phthalate	ND
			72B	benzo(a)anthracene	ND
			73B	benzo(a)pyrene	ND
			74B	3,4-benzofluoranthene	ND
			75B	benzo(k)fluoranthene	ND
			76B	chrysene	ND
			77B	acenaphthylene	ND
			78B	anthracene	ND
			79B	benzo(ghi)perylene	ND
			80B	fluorene	ND
			81B	phenanthrene	ND
			82B	dibenzo(a,h)anthracene	ND
			83B	indeno(1,2,3-cd)pyrene	ND
			84B	pyrene ----- 102% ^a 51	
			129B	2,3,7,8-tetrachlorodibenzo-p-dioxin	ND
BASE/NEUTRAL COMPOUNDS					
1B	acenaphthene ----- 144% ^a 72				
5B	benzidine	ND			
8B	1,2,4-trichlorobenzene ---- 78% ^a 39				
9B	hexachlorobenzene	ND			
12B	hexachloroethane	ND			
18B	bis(2-chloroethyl)ether	ND			
20B	2-chloronaphthalene	ND			
25B	1,2-dichlorobenzene	ND			
26B	1,3-dichlorobenzene	ND			
27B	1,4-dichlorobenzene ----- 60% ^a 30				
28B	3,3-dichlorobenzidine	ND			
35B	2,4-dinitrotoluene ----- 180% ^a 90				
36B	2,6-dinitrotoluene	ND			
37B	1,2-diphenylhydrazine	ND			
39B	fluoranthene	ND			
40B	4-chlorophenyl phenyl ether	ND			
41B	4-bromophenyl phenyl ether	ND			

ND = None detected above the average reporting limit of 30ppb for acids and 30ppb for B/N.

NA = Not applicable.

* Trace concentrations detected below the average reporting limit.

^a Recovery of matrix spiked compounds.

SURROGATE RECOVERIES (%): ACID

** d₆-phenol 102

Reported by: KC
 Checked by: J. J.

BASE/NEUTRAL

d₅-nitrobenzene 114

CLIENT NYS DEC
CLIENT ID RH-084-006-002
ERCO ID 22-4663S
SAMPLE RECEIVED 6/15/84
ANALYSIS COMPLETED 7/17/84
RESULTS IN ppb (ug/l)

ERCO / ENERGY RESOURCES CO. INC.

SUMMARY OF
ORGANIC PRIORITY POLLUTANT ANALYSIS

COMMENTS

Recovery of several matrix spiked compounds could not be accurately determined because:

- 1) phenol (370%) - Phenol is present at extremely high concentration in the original unspiked sample.
- 2) 2,4-Dinitrotoluene (180%) - This compound was quantitated by its characteristic ion at m/z 89, which was also ions generated by the aliphatic acid background.
- 3) N-nitrosodi-n-propylamine - This compound was quantitated by its characteristic ion at m/z 70, which was also ions generated by the aliphatic acid background.

ORGANICS ANALYSIS DATA SHEET

ERCO / ENERGY RESOURCES CO. INC.

CLIENT NYS DEC

CLIENT I.D. _____

ERCO I.D. 22 - 4663S

COMPOUND NAME	FRACTION	SCAN NO. OR RETENTION TIME	ESTIMATED CONCENTRATION (ug/l)
cyclohexane	B/N	363	60
aliphatic acid isomer	B/N	476	700
aliphatic acid isomer	B/N	530	75
aliphatic acid isomer	B/N	554	40
aliphatic acid isomer	B/N	608	4900
aliphatic acid isomer	B/N	634	450
aliphatic acid isomer	B/N	688	1800
aliphatic acid isomer	B/N	763	1300
aliphatic acid isomer	B/N	777	900
aliphatic acid isomer	B/N	795	3000
aliphatic acid isomer	B/N	830	350
aliphatic acid isomer	B/N	838	600
benzene butanoic acid, 2,5-dimethyl	B/N	1049	150
1H-purine-2,6-dione, 3,7-dihydro- 1,3,7-trimethyl	B/N	1240	50
sulfur, mol	B/N	1368	300
4-methylphenol	B/N	604	100

ORGANICS ANALYSIS DATA SHEET

ERCO / ENERGY RESOURCES CO. INC.

CLIENT NYS DEC

CLIENT I.D. _____

ERCO I.D. 22 - 4663S acid

COMPOUND NAME	FRACTION	SCAN NO. OR RETENTION TIME	ESTIMATED CONCENTRATION (ug/l)
propanoic acid	acid	363	6100
3-pentanol, 3-methyl	acid	370	50
pentanol, methyl isomer	acid	373	40
pentanol, methyl isomer	acid	379	60
aliphatic acid isomer	acid	390	190
aliphatic acid isomer	acid	395	90
aliphatic acid isomer	acid	419	50
aliphatic acid isomer	acid	430	40
aliphatic acid isomer	acid	439	60
aliphatic acid isomer	acid	455	60
aliphatic acid isomer	acid	458	80
aliphatic acid isomer	acid	466	100
aliphatic acid isomer	acid	468	60
aliphatic acid isomer	acid	473	30
aliphatic acid isomer	acid	479	50
aliphatic acid isomer	acid	506	12000
aliphatic acid isomer	acid	535	1800
aliphatic acid isomer	acid	539	170
aliphatic acid isomer	acid	566	4700
aliphatic acid isomer	acid	571	40
aliphatic acid isomer	acid	579	100
aliphatic acid isomer	acid	583	80
aliphatic acid isomer	acid	618	21000
aliphatic acid isomer	acid	630	5000
aliphatic acid isomer	acid	640	900
aliphatic acid isomer	acid	653	30
aliphatic acid isomer	acid	658	50
aliphatic acid isomer	acid	660	80
aliphatic acid isomer	acid	665	80
aliphatic acid isomer	acid	668	40
aliphatic acid isomer	acid	702	20000
aliphatic acid isomer	acid	709	2500
aliphatic acid isomer	acid	713	60
aliphatic acid isomer	acid	719	1300
aliphatic acid isomer	acid	736	7400
aliphatic acid isomer	acid	741	220
cyclohexane carboxylic acid	acid	753	1700
aliphatic acid isomer	acid	786	4600
aliphatic acid isomer	acid	836	140
benzenepropanoic acid	acid	909	1400
aliphatic acid isomer	acid	913	40

CLIENT NYS DEC
 CLIENT ID RH-084-006-002
 ERCO ID 22-4653
 SAMPLE RECEIVED 6/15/84
 ANALYSIS COMPLETED 7/17/184
 RESULTS IN ppb (ug/l)

ERCO / ENERGY RESOURCES CO. INC.

SUMMARY OF
 ORGANIC PRIORITY POLLUTANT ANALYSIS

ACID COMPOUNDS

21A	2,4,6-trichlorophenol	ND
22A	p-chloro-m-cresol	ND
24A	2-chlorophenol	ND
31A	2,4-dichlorophenol	ND
34A	2,4-dimethylphenol	ND
57A	2-nitrophenol	ND
58A	4-nitrophenol	ND
59A	2,4-dinitrophenol	ND
60A	4,6-dinitro-o-cresol	ND
64A	pentachlorophenol	ND
65A	phenol -----	370

BASE/NEUTRAL COMPOUNDS

1B	acenaphthene	ND
5B	benzidine	ND
8B	1,2,4-trichlorobenzene	ND
9B	hexachlorobenzene	ND
12B	hexachloroethane	ND
18B	bis(2-chloroethyl)ether	ND
20B	2-chloronaphthalene	ND
25B	1,2-dichlorobenzene	ND
26B	1,3-dichlorobenzene	ND
27B	1,4-dichlorobenzene	ND
28B	3,3-dichlorobenzidine	ND
35B	2,4-dinitrotoluene	ND
36B	2,6-dinitrotoluene	ND
37B	1,2-diphenylhydrazine	ND
39B	fluoranthene	ND
40B	4-chlorophenyl phenyl ether	ND
41B	4-bromophenyl phenyl ether	ND

BASE/NEUTRAL COMPOUNDS

42B	bis(2-chloroisopropyl)ether	ND
43B	bis(2-chloroethoxy)methane	ND
52B	hexachlorobutadiene	ND
53B	hexachlorocyclopentadiene	ND
54B	isophorone	ND
55B	naphthalene	ND
56B	nitrobenzene	ND
61B	N-nitrosodimethylamine	ND
62B	N-nitrosodiphenylamine	ND
63B	N-nitrosodi-n-propylamine	ND
66B	bis(2-ethylhexyl)phthalate	72
67B	butyl benzyl phthalate -----	*
68B	di-n-butyl phthalate	ND
69B	di-n-octyl phthalate	ND
70B	diethyl phthalate -----	48
71B	dimethyl phthalate	ND
72B	benzo(a)anthracene	ND
73B	benzo(a)pyrene	ND
74B	3,4-benzofluoranthene	ND
75B	benzo(k)fluoranthene	ND
76B	chrysene	ND
77B	acenaphthylene	ND
78B	anthracene	ND
79B	benzo(ghi)perylene	ND
80B	fluorene	ND
81B	phenanthrene	ND
82B	dibenzo(a,h)anthracene	ND
83B	indeno(1,2,3-cd)pyrene	ND
84B	pyrene	ND
129B	2,3,7,8-tetrachlorodibenzo-p-dioxin	ND

ND = None detected above the average
 reporting limit of 30ppb for acids
 and 30ppb for B/N.

Reported by: KC
 Checked by: me

NA = Not applicable.

*Trace concentrations detected below
 the average reporting limit.

SURROGATE RECOVERIES (%): ACID

**	d ₆ -phenol	<u>60</u>
**	2-fluorophenol	<u>48</u>

BASE/NEUTRAL

d ₅ -nitrobenzene	<u>60</u>
fluorobiphenyl	<u>54</u>

ORGANICS ANALYSIS DATA SHEET

ERCO / ENERGY RESOURCES CO. INC.

CLIENT NYS DEC

CLIENT I.D. _____

ERCO I.D. 22 - 4653 B/N

COMPOUND NAME	FRACTION	SCAN NO. OR RETENTION TIME	ESTIMATED CONCENTRATION (ug/l)
cyclopentanol, 2-methyl	B/N	357	30
aliphatic acid isomer	B/N	438	100
aliphatic acid isomer	B/N	457	300
aliphatic acid isomer	B/N	674	700
cyclohexane carboxylic acid	B/N	697	150
aliphatic acid isomer	B/N	751	430
aliphatic acid isomer	B/N	781	1400
aliphatic acid isomer	B/N	826	450
benzene propanoic acid	B/N	877	110
benzene butanoic acid, 2,5-dimethyl	B/N	1047	70
1H-purine-2,6-dione, 3,7-dihydro-1,3,7-trimethyl	B/N	1245	50
sulfor, mol	B/N	1367	130

Gary A. Litwin, Section Chief

X SAMPLE #8 - [REDACTED]

[REDACTED]
[REDACTED]
[REDACTED]
Analysis: Organic compounds - 502.1, 503.1, PCBs, priority
pollutants and ketones. Inorganic compounds - HSL metals.
Results: trichloethene - 2. ppb, iron - 5140 ppb.

Please note attachments: 1) USGS Map locating site. 2) Area sketch
of sampling locations.

sjk/03510626

Attachment

cc: R. Tramontano, w/att.
Dr. N. Kim, w/att.
P. Smith, CRU, w/att.
B. Fear, DOH, w/att.



STATE OF NEW YORK
DEPARTMENT OF HEALTH

Corning Tower The Governor Nelson A. Rockefeller Empire State Plaza Albany, New York 12237

David Axelrod, M.D.
Commissioner

OFFICE OF PUBLIC HEALTH

Linda A. Randolph, M.D., M.P.H.
Director

William F. Leavy
Executive Deputy Director

December 18, 1990

DEC 21 1990

RE: Queensbury Landfill
Queensbury(T), Warren County
Site ID #557005

On October 25, 1990 I collected water samples at your home in the Town of Queensbury, Warren County. The sample was submitted to the NYS Department of Health's Wadsworth Center for Laboratories and Research for analysis of volatile organic compounds and inorganic trace metals. The enclosed report gives the results of the analysis. I have also included an explanation sheet for the NYS Dept. of Health's Analytical Report.

This report indicates that for all inorganic metals analyzed, the concentrations are within the expected background range. Iron exceeds the New York State Department of Health's Drinking Water Standards (Part 5 Secondary Contaminants) of 300 ppb. This is a naturally occurring compound and there is no health significance. This is a secondary standard for aesthetic purposes and may cause turbidity, stains on plumbing fixtures, equipment and laundry.

One anomaly we would like to investigate is the detection of trichloroethene. The level detected of this organic compound is below NYS Department of Health's Drinking Water Standards. I will resample your drinking water to determine the validity of this result.

If you have any questions, I can be reached at (518) 458-6306.

Sincerely,

Stanley J. Kilmer
Program Research Specialist I
Bureau of Environmental Exposure
Investigation

sms/03510963

Attachment

cc: R. Tramontano/G. Litwin, w/o att.
P. Smith, CRU, w/att.
B. Fear, GFDO, w/o att.
D. Steenberge, DEC, Reg.5, w/att.
~~M. Brand, DEC, w/att~~
C. Crandall, RD #1, Box 1376
Lake George, NY 12845

1227

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER FOR LABORATORIES AND RESEARCH

PAGE 2

RESULTS OF EXAMINATION

FINAL REPORT(REV)

SAMPLE ID: 901002554

SAMPLE RECEIVED: 90/10/26/11

CHARGE:

5.10

POLITICAL SUBDIVISION: QUEENSBURY

COUNTY: WARREN

LOCATION: QUEENSBURY LANDFILL SITE #557005

TIME OF SAMPLING: 90/10/25 14:45

DATE PRINTED: 90/12/12

REVISION DATE 90/12/10, FOLLOWING PARAMETERS ADDED AFTER SAMPLE REPORTED

FOLLOWING PARAMETERS NOT PART OF TEST PATTERN

-----PARAMETER-----

-----RESULT-----

CO PHONED MO DAY TIME

12-5 JD

**** END OF REPORT ****

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER FOR LABORATORIES AND RESEARCH

PAGE 1

RESULTS OF EXAMINATION

FINAL REPORT

SAMPLE ID: 903730 SAMPLE RECEIVED: 90/10/25/ CHARGE: 35.50
 PROGRAM: 110: STATE SUPERFUND ANALYTICAL SERVICES
 SOURCE ID: DRAINAGE BASIN: 10 GAZETTEER CODE: 5657
 POLITICAL SUBDIVISION: QUEENSBURY COUNTY: WARREN
 LATITUDE: LONGITUDE: Z DIRECTION:
 LOCATION: QUEENSBURY LANDFILL SITE #557005

REPORTING LAB: TOX: LAB FOR ORGANIC ANALYTICAL CHEMISTRY
 TEST PATTERN: AQUEOUS-1: VOLATILES, KETONES, PESTICIDES, PCB'S, PRIORITY POLLUTANT
 SAMPLE TYPE: 120: PRIVATE WATER SUPPLY - DRILLED WELL
 TIME OF SAMPLING: 90/10/25 14:45 DATE PRINTED: 90/12/11

ANALYSIS: VHO5021 VOLATILE HALOGENATED ORGANICS (DES 310-29)
 DATE REPORTED: 90/11/13 REPORT MAILED OUT

-----PARAMETER-----	-----RESULT-----
CHLOROMETHANE	< 0.5 MCG/L
BROMOMETHANE	< 0.5 MCG/L
VINYL CHLORIDE	< 0.5 MCG/L
DICHLORODIFLUOROMETHANE (FREON-12)	< 0.5 MCG/L
CHLOROETHANE	< 0.5 MCG/L
METHYLENE CHLORIDE (DICHLOROMETHANE)	< 0.5 MCG/L
TRICHLOROFLUOROMETHANE (FREON-11)	< 0.5 MCG/L
1,1-DICHLOROETHENE	< 0.5 MCG/L
1,1-DICHLOROETHANE	< 0.5 MCG/L
TRANS-1,2-DICHLOROETHENE	< 0.5 MCG/L
CIS-1,2-DICHLOROETHENE	< 0.5 MCG/L
CHLOROFORM	< 0.5 MCG/L
1,2-DICHLOROETHANE	< 0.5 MCG/L
DIBROMOMETHANE	< 0.5 MCG/L
1,1,1-TRICHLOROETHANE	< 0.5 MCG/L
CARBON TETRACHLORIDE	< 0.5 MCG/L
BROMODICHLOROMETHANE	< 0.5 MCG/L
2,3-DICHLOROPROPENE	< 0.5 MCG/L
1,2-DICHLOROPROPANE	< 0.5 MCG/L
CIS-1,3-DICHLOROPROPENE	< 0.5 MCG/L
TRICHLOROETHENE	2. MCG/L
1,3-DICHLOROPROPANE	< 0.5 MCG/L
DIBROMOCHLOROMETHANE	< 0.5 MCG/L
TRANS-1,3-DICHLOROPROPENE	< 0.5 MCG/L
1,1,2-TRICHLOROETHANE	< 0.5 MCG/L
1,2-DIBROMOETHANE (EDB)	< 0.5 MCG/L
2-CHLOROETHYL VINYL ETHER	< 0.5 MCG/L
BROMOFORM	< 0.5 MCG/L
1,1,1,2-TETRACHLOROETHANE	< 0.5 MCG/L
1,2,3-TRICHLOROPROPANE	< 0.5 MCG/L

**** CONTINUED ON NEXT PAGE ****

COPIES SENT TO: CO(3), RO(0), LPHE(1), FED(), INFO-P(), INFO-L()

RONALD TRAMONTANO, PE
 BUR. ENVIRONMENTAL EXPOSURE INVESTIGAT.
 NY STATE DEP'T. HEALTH
 11 UNIVERSITY PLACE
 ALBANY, NY 12237 INTERAGENCY MAIL

SUBMITTED BY: KILMER

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER FOR LABORATORIES AND RESEARCH

PAGE 2

RESULTS OF EXAMINATION

FINAL REPORT

SAMPLE ID: 903730 SAMPLE RECEIVED: 90/10/25/ CHARGE: 35.50
POLITICAL SUBDIVISION: QUEENSBURY COUNTY: WARREN
LOCATION: QUEENSBURY LANDFILL SITE #557005
TIME OF SAMPLING: 90/10/25 14:45 DATE PRINTED: 90/12/11

PARAMETER	RESULT
1,1,2,2-TETRACHLOROETHANE	< 0.5 MCG/L
TETRACHLOROETHENE	< 0.5 MCG/L
PENTACHLOROETHANE	< 0.5 MCG/L
1-CHLOROCYCLOHEXENE-1	< 0.5 MCG/L
CHLOROBENZENE	< 0.5 MCG/L
BIS(2-CHLOROETHYL)ETHER	< 0.5 MCG/L
1,2-DIBROMO-3-CHLOROPROPANE	< 0.5 MCG/L
BROMOBENZENE	< 0.5 MCG/L
O-CHLOROTOLUENE	< 0.5 MCG/L
BIS(2-CHLOROISOPROPYL)ETHER	< 0.5 MCG/L
1,3-DICHLOROBENZENE	< 0.5 MCG/L
1,2-DICHLOROBENZENE	< 0.5 MCG/L
1,4-DICHLOROBENZENE	< 0.5 MCG/L

ANALYSIS: 5031 AROMATIC PURGEABLES, EPA METHOD 503.1 (DES 310-22)
DATE REPORTED: 90/11/08 REPORT MAILED OUT

PARAMETER	RESULT
BENZENE	< 0.5 MCG/L
TOLUENE	< 0.5 MCG/L
ETHYLBENZENE	< 0.5 MCG/L
P-XYLENE	< 0.5 MCG/L
M-XYLENE	< 0.5 MCG/L
O-XYLENE	< 0.5 MCG/L
ISOPROPYLBENZENE (CUMENE)	< 0.5 MCG/L
STYRENE	< 0.5 MCG/L
P-BROMOFLUOROBENZENE	< 0.5 MCG/L
N-PROPYLBENZENE	< 0.5 MCG/L
TERT-BUTYLBENZENE	< 0.5 MCG/L
P-CHLOROTOLUENE	< 0.5 MCG/L
M-CHLOROTOLUENE	< 0.5 MCG/L
1,3,5-TRIMETHYLBENZENE	< 0.5 MCG/L
1,2,4-TRIMETHYLBENZENE	< 0.5 MCG/L
4-ISOPROPYLTOLUENE (P-CYMELE)	< 0.5 MCG/L
CYCLOPROPYLBENZENE	< 0.5 MCG/L
SEC-BUTYLBENZENE	< 0.5 MCG/L
N-BUTYLBENZENE	< 0.5 MCG/L
2,3-BENZOFURAN	< 0.5 MCG/L
HEXACHLOROCYCLODIENE (C-46)	< 0.5 MCG/L
1,2,4-TRICHLOROBENZENE	< 0.5 MCG/L
NAPHTHALENE	< 0.5 MCG/L
1,2,3-TRICHLOROBENZENE	< 0.5 MCG/L
PH OF AROMATIC ALIQUOT	2

**** CONTINUED ON NEXT PAGE ****

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER FOR LABORATORIES AND RESEARCH

PAGE 3

RESULTS OF EXAMINATION

FINAL REPORT

SAMPLE ID: 903730 SAMPLE RECEIVED: 90/10/25/ CHARGE: 35.50
POLITICAL SUBDIVISION: QUEENSBURY COUNTY: WARREN
LOCATION: QUEENSBURY LANDFILL SITE #557005
TIME OF SAMPLING: 90/10/25 14:45 DATE PRINTED: 90/12/11

ANALYSIS: KET KETONES - PURGE & TRAP TECHNIQUE (DES 310-25)
DATE PRINTED: 90/12/11 FINAL REPORT

PARAMETER	RESULT
2-BUTANONE (METHYL ETHYL KETONE)	< 10. MCG/L
4-METHYL-2-PENTANONE (MIBK)	< 10. MCG/L
ACETONE	< 10. MCG/L
METHYL TERT BUTYL ETHER	< 10. MCG/L

ANALYSIS: XFEST-PCB ORGANOCHLORINE PESTICIDES & PCB'S (DES310-2)
DATE REPORTED: 90/11/27 REPORT MAILED OUT

PARAMETER	RESULT
HCH, ALPHA	< 0.04 MCG/L
HCH, BETA	< 0.04 MCG/L
HCH, GAMMA (LINDANE)	< 0.04 MCG/L
HCH, DELTA	< 0.04 MCG/L
HEPTACHLOR	< 0.05 MCG/L
ALDRIN	< 0.02 MCG/L
HEPTACHLOR EPOXIDE	< 0.05 MCG/L
ENDOSULFAN I	< 0.05 MCG/L
4,4'-DDE	< 0.05 MCG/L
DIELDRIN	< 0.02 MCG/L
ENDRIN	< 0.02 MCG/L
4,4'-DDD	< 0.05 MCG/L
ENDOSULFAN II	< 0.05 MCG/L
ENDRIN ALDEHYDE	< 0.02 MCG/L
ENDOSULFAN SULFATE	< 0.05 MCG/L
4,4'-DDT	< 0.05 MCG/L
METHOXYCHLOR	< 0.5 MCG/L
TOXAPHENE	< 1.0 MCG/L
CHLORDANE	< 0.1 MCG/L
MIREX	< 0.05 MCG/L
PCB, AROCLOR 1221	< 0.05 MCG/L
PCB, AROCLOR 1016/1242	< 0.05 MCG/L
PCB, AROCLOR 1248	< 0.05 MCG/L
PCB, AROCLOR 1254	< 0.05 MCG/L
PCB, AROCLOR 1260	< 0.05 MCG/L

ANALYSIS: GC-FID-A PRIORITY POLLUTANTS*ACIDS*GC/FID RESULTS
DATE REPORTED: 90/11/27 REPORT MAILED OUT

PARAMETER	RESULT
PHENOL	< 10. MCG/L
2-CHLOROPHENOL	< 10. MCG/L
2-NITROPHENOL	< 10. MCG/L
2,4-DIMETHYLPHENOL	< 10. MCG/L
2,4-DICHLOROPHENOL	< 10. MCG/L
4-CHLORO-3-METHYLPHENOL	< 10. MCG/L

**** CONTINUED ON NEXT PAGE ****

NEW YORK STATE DEPARTMENT OF HEALTH
 WADSWORTH CENTER FOR LABORATORIES AND RESEARCH

PAGE 4

RESULTS OF EXAMINATION

FINAL REPORT

SAMPLE ID: 903730 SAMPLE RECEIVED: 90/10/25/ CHARGE: 35.50
 POLITICAL SUBDIVISION: QUEENSBURY COUNTY: WARREN
 LOCATION: QUEENSBURY LANDFILL SITE #557005
 TIME OF SAMPLING: 90/10/25 14:45 DATE PRINTED: 90/12/11

-----PARAMETER-----

2,4,6-TRICHLOROPHENOL
 2,4,5-TRICHLOROPHENOL
 2,4-DINITROPHENOL
 4-NITROPHENOL
 2-METHYL-4,6-DINITROPHENOL
 PENTACHLOROPHENOL

-----RESULT-----

< 10. MCG/L
 < 10. MCG/L
 < 10. MCG/L
 < 10. MCG/L
 < 10. MCG/L
 < 10. MCG/L

ANALYSIS: GC-FID-BN

PRIORITY POLLUTANTS*BASE/NEUTRALS*GC/FID RESULTS

DATE REPORTED: 90/11/27

REPORT MAILED OUT

-----PARAMETER-----

N-NITROSODI-N-PROPYLAMINE
 HEXACHLOROETHANE
 NITROBENZENE
 ISOPHURONE
 BIS(2-CHLOROETHOXY)METHANE
 HEXACHLOROCYCLOPENTADIENE (C-56)
 2-CHLORONAPHTHALENE
 2,6-DINITROTOLUENE
 ACENAPHTHYLENE
 DIMETHYLPHTHALATE
 ACENAPHTHENE
 2,4-DINITROTOLUENE

-----RESULT-----

< 10. MCG/L
 < 10. MCG/L
 < 10. MCG/L
 < 10. MCG/L
 < 10. MCG/L
 < 10. MCG/L
 < 10. MCG/L
 < 10. MCG/L
 < 10. MCG/L
 < 10. MCG/L
 < 10. MCG/L
 < 10. MCG/L

DIETHYLPHTHALATE

< 10. MCG/L

FLUORENE

< 10. MCG/L

N-NITROSODIPHENYLAMINE

< 10. MCG/L

1,2-DIPHENYLHYDRAZINE

< 10. MCG/L

4-BROMOPHENYL PHENYL ETHER

< 10. MCG/L

HEXACHLOROPOBENZENE

< 10. MCG/L

PHENANTHRENE

< 10. MCG/L

ANTHRACENE

< 10. MCG/L

DI-N-BUTYL PHTHALATE

< 10. MCG/L

FLUORANTHENE

< 10. MCG/L

PYRENE

< 10. MCG/L

BENZIDINE

< 30. MCG/L

BUTYL BENZYL PHTHALATE

< 30. MCG/L

BENZO(A)ANTHRACENE

< 10. MCG/L

3,3'-DICHLOROBENZIDINE

< 10. MCG/L

CHRYSENE

< 10. MCG/L

BIS(2-ETHYLHEXYL)PHTHALATE

< 30. MCG/L

DI-N-OCTYL PHTHALATE

< 30. MCG/L

BENZO(B)FLUORANTHENE

< 20. MCG/L

BENZO(K)FLUORANTHENE

< 20. MCG/L

BENZO(A)PYRENE

< 20. MCG/L

INDENO(1,2,3-CD)PYRENE

< 20. MCG/L

DIBENZO(AH)ANTHRACENE

< 20. MCG/L

BENZO(GHI)PERYLENE

< 20. MCG/L

**** END OF REPORT ****



STATE OF NEW YORK
DEPARTMENT OF HEALTH

Corning Tower The Governor Nelson A. Rockefeller Empire State Plaza Albany, New York 12237

David Axelrod, M.D.
Commissioner

OFFICE OF PUBLIC HEALTH

Linda A. Randolph, M.D., M.P.H.
Director

William F. Leavy
Executive Deputy Director

December 18, 1990

DEC 29 1990

RE: Queensbury Landfill
Queensbury(T), Warren County
Site ID #557005

On October 25, 1990 I collected water samples at your home in the Town of Queensbury, Warren County. The sample was submitted to the NYS Department of Health's Wadsworth Center for Laboratories and Research for analysis of volatile organic compounds and inorganic trace metals. The enclosed report gives the results of the analysis. I have also included an explanation sheet for the NYS Dept. of Health's Analytical Report.

This report indicates that for all parameters analyzed, the concentrations are within the expected background range. Sodium exceeds the New York State Department of Health's Drinking Water Standards (Part 5 Secondary Contaminants). Although there are no designated limits, water containing more than 20 part per million of sodium should not be used for drinking by people on severely restricted sodium diets. Water containing more than 270 mg/L of sodium should not be used for drinking by people on moderately restricted sodium diets.

If you have any questions, I can be reached at (518) 458-6306.

Sincerely,

Stanley J. Kilmer
Program Research Specialist I
Bureau of Environmental Exposure
Investigation

sms/03510903

Attachment

cc: R. Tramontano/G. Litwin, w/o att.
P. Smith, CRU, w/att.
B. Fear, GFDO, w/o att.
D. Steenberge, DEC, Reg.5, w/att.
~~W. Branch, DEC, w/att.~~

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER FOR LABORATORIES AND RESEARCH

PAGE 1

RESULTS OF EXAMINATION

FINAL REPORT

SAMPLE ID: 903729 SAMPLE RECEIVED: 90/10/25/ CHARGE: 19.00
PROGRAM: 110: STATE SUPERFUND ANALYTICAL SERVICES
SOURCE ID: DRAINAGE BASIN: 10 GAZETTEER CODE: 5657
POLITICAL SUBDIVISION: QUEENSBURY COUNTY: WARREN
LATITUDE: LONGITUDE: Z DIRECTION:
LOCATION: QUEENSBURY LANDFILL SITE 1557005
REPORTING LAB: TOX: LAB FOR ORGANIC ANALYTICAL CHEMISTRY
TEST PATIENT: VOL3-KET: PURGEABLES & KETONES
SAMPLE TYPE: 120: PRIVATE WATER SUPPLY - DRILLED WELL
TIME OF SAMPLING: 90/10/25 14:30 DATE PRINTED: 90/12/11

ANALYSIS: VHO5021 VOLATILE HALOGENATED ORGANICS (DES 310-29)
DATE REPORTED: 90/11/13 REPORT MAILED OUT

-----PARAMETER-----	-----RESULT-----
CHLOROMETHANE	< 0.5 MCG/L
BROMOMETHANE	< 0.5 MCG/L
VINYL CHLORIDE	< 0.5 MCG/L
DICHLORODIFLUOROMETHANE (FREON-12)	< 0.5 MCG/L
CHLOROETHANE	< 0.5 MCG/L
METHYLENE CHLORIDE (DICHLOROMETHANE)	< 0.5 MCG/L
TRICHLOROFLUOROMETHANE (FREON-11)	< 0.5 MCG/L
1,1-DICHLOROETHENE	< 0.5 MCG/L
1,1-DICHLOROETHANE	< 0.5 MCG/L
TRANS-1,2-DICHLOROETHENE	< 0.5 MCG/L
CIS-1,2-DICHLOROETHENE	< 0.5 MCG/L
CHLOROFORM	< 0.5 MCG/L
1,2-DICHLOROETHANE	< 0.5 MCG/L
DIBROMOMETHANE	< 0.5 MCG/L
1,1,1-TRICHLOROETHANE	< 0.5 MCG/L
CARBON TETRACHLORIDE	< 0.5 MCG/L
BROMODICHLOROMETHANE	< 0.5 MCG/L
2,3-DICHLOROPROPENE	< 0.5 MCG/L
1,2-DICHLOROPROPANE	< 0.5 MCG/L
CIS-1,3-DICHLOROPROPENE	< 0.5 MCG/L
TRICHLOROETHENE	< 0.5 MCG/L
1,3-DICHLOROPROPANE	< 0.5 MCG/L
DIBROMOCHLOROMETHANE	< 0.5 MCG/L
TRANS-1,3-DICHLOROPROPENE	< 0.5 MCG/L
1,1,2-TRICHLOROETHANE	< 0.5 MCG/L
1,2-DIBROMOETHANE (EDB)	< 0.5 MCG/L
2-CHLOROETHYL VINYL ETHER	< 0.5 MCG/L
BROMOFORM	< 0.5 MCG/L
1,1,1,2-TETRACHLOROETHANE	< 0.5 MCG/L
1,2,3-TRICHLOROPROPANE	< 0.5 MCG/L

**** CONTINUED ON NEXT PAGE ****

COPIES SENT TO: CO(3), RO(0), LPHE(1), FED(), INFO-P(), INFO-L()

RONALD TRAMONTANO, PE
BUR. ENVIRONMENTAL EXPOSURE INVESTIGAT.
NY STATE DEP'T. HEALTH
11 UNIVERSITY PLACE
ALBANY, NY 12237 INTERAGENCY MAIL

SUBMITTED BY: KILMER

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER FOR LABORATORIES AND RESEARCH

PAGE 2

RESULTS OF EXAMINATION

FINAL REPORT

SAMPLE ID: 903729 SAMPLE RECEIVED: 90/10/25/ CHARGE: 19.00
POLITICAL SUBDIVISION: QUEENSBURY COUNTY: WARREN
LOCATION: QUEENSBURY LANDFILL SITE #557005
TIME OF SAMPLING: 90/10/25 14:30 DATE PRINTED: 90/12/11

PARAMETER	RESULT
1,1,2,2-TETRACHLOROETHANE	< 0.5 MCG/L
TETRACHLOROETHENE	< 0.5 MCG/L
PENTACHLOROETHANE	< 0.5 MCG/L
1-CHLOROCYCLOHEXENE-1	< 0.5 MCG/L
CHLOROBENZENE	< 0.5 MCG/L
BIS(2-CHLOROETHYL)ETHER	< 0.5 MCG/L
1,2-DIBROMO-3-CHLOROPROPANE	< 0.5 MCG/L
BROMOBENZENE	< 0.5 MCG/L
O-CHLOROTOLUENE	< 0.5 MCG/L
BIS(2-CHLOROISOPROPYL)ETHER	< 0.5 MCG/L
1,3-DICHLOROBENZENE	< 0.5 MCG/L
1,2-DICHLOROBENZENE	< 0.5 MCG/L
1,4-DICHLOROBENZENE	< 0.5 MCG/L

ANALYSIS: 5031 AROMATIC PURGEABLES, EPA METHOD 503.1 (DES 310-22)
DATE REPORTED: 90/11/08 REPORT MAILED OUT

PARAMETER	RESULT
BENZENE	< 0.5 MCG/L
TOLUENE	< 0.5 MCG/L
ETHYLBENZENE	< 0.5 MCG/L
P-XYLENE	< 0.5 MCG/L
M-XYLENE	< 0.5 MCG/L
O-XYLENE	< 0.5 MCG/L
ISOPROPYLBENZENE (CUMENE)	< 0.5 MCG/L
STYRENE	< 0.5 MCG/L
P-BROMOFLUOROBENZENE	< 0.5 MCG/L
N-PROPYLBENZENE	< 0.5 MCG/L
TERT-BUTYLBENZENE	< 0.5 MCG/L
P-CHLOROTOLUENE	< 0.5 MCG/L
M-CHLOROTOLUENE	< 0.5 MCG/L
1,3,5-TRIMETHYLBENZENE	< 0.5 MCG/L
1,2,4-TRIMETHYLBENZENE	< 0.5 MCG/L
4-ISOPROPYLTOLUENE (P-CYMENE)	< 0.5 MCG/L
CYCLOPPROPYLBENZENE	< 0.5 MCG/L
SEC-BUTYLBENZENE	< 0.5 MCG/L
N-BUTYLBENZENE	< 0.5 MCG/L
2,3-BENZOFURAN	< 0.5 MCG/L
HEXACHLOROBUTADIENE (C-46)	< 0.5 MCG/L
1,2,4-TRICHLOROBENZENE	< 0.5 MCG/L
NAPHTHALENE	< 0.5 MCG/L
1,2,3-TRICHLOROBENZENE	< 0.5 MCG/L
PH OF AROMATIC ALIQUOT	2

**** CONTINUED ON NEXT PAGE ****

1265

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER FOR LABORATORIES AND RESEARCH

PAGE 3

RESULTS OF EXAMINATION

FINAL REPORT

SAMPLE ID: 903729 SAMPLE RECEIVED: 90/10/25/ CHARGE: 19.00
POLITICAL SUBDIVISION: QUEENSBURY COUNTY: WARREN
LOCATION: QUEENSBURY LANDFILL SITE #557005
TIME OF SAMPLING: 90/10/25 14:30 DATE PRINTED: 90/12/11

ANALYSIS: KET KETONES - PURGE & TRAP TECHNIQUE (DES 310-25)
DATE PRINTED: 90/12/11 FINAL REPORT

-----PARAMETER-----	-----RESULT-----
2-BUTANONE (METHYL ETHYL KETONE)	< 10. MCG/L
4-METHYL-2-PENTANONE (MIBK)	< 10. MCG/L
ACETONE	< 10. MCG/L
METHYL TERT BUTYL ETHER	< 10. MCG/L

**** END OF REPORT ****

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER FOR LABORATORIES AND RESEARCH

PAGE 1

RESULTS OF EXAMINATION

FINAL REPORT

SAMPLE ID: 901002553 SAMPLE RECEIVED: 90/10/26/11 CHARGE: 5.00
PROGRAM: 110: STATE SUPERFUND ANALYTICAL SERVICES
SOURCE ID: DRAINAGE BASIN: 10 GAZETTEER CODE: 5657
POLITICAL SUBDIVISION: QUEENSBURY COUNTY: WARREN
LATITUDE: LONGITUDE: Z DIRECTION:
LOCATION: QUEENSBURY LANDFILL SITE #557005

REPORTING LAB: 10: LABORATORY OF INORGANIC ANALYTICAL CHEMISTRY - ALBANY
TEST PATTERN: 10-001: SAFE DRINKING WATER ACT - METALS ONLY
SAMPLE TYPE: 120: PRIVATE WATER SUPPLY - DRILLED WELL
TIME OF SAMPLING: 90/10/25 14:30 DATE PRINTED: 90/11/28

ANALYSIS: ICP-1 ICP GROUPING 1

-----PARAMETER-----	-----RESULT-----
MERCURY	< 0.2 MCG/L
ARSENIC	< 10. MCG/L
SELENIUM	< 5. MCG/L
LEAD	< 10. MCG/L
BERYLLIUM	< 1. MCG/L
SILVER	< 10. MCG/L
BARIUM	< 5. MCG/L
CADMIUM	< 5. MCG/L
COBALT	< 5. MCG/L
CHROMIUM	< 5. MCG/L
COPPER	< 5. MCG/L
IRON	< 10. MCG/L
MANGANESE	< 5. MCG/L
NICKEL	< 5. MCG/L
STRONTIUM	< 50. MCG/L
TITANIUM	< 5. MCG/L
VANADIUM	< 5. MCG/L
ZINC	14. MCG/L
MOLYBDENUM	< 20. MCG/L
ANTIMONY	< 80. MCG/L
TIN	< 50. MCG/L
THALLIUM	< 80. MCG/L
ALUMINUM	< 100. MCG/L
CALCIUM	0.56 MG/L
POTASSIUM	< 1. MG/L
MAGNESIUM	< 1. MG/L
SODIUM	139. MG/L

**** END OF REPORT ****

COPIES SENT TO: CO(3), RO(0), LPHE(1), FED(), INFO-P(), INFO-L()

RONALD TRAMONTANO, PE
BUR. ENVIRONMENTAL EXPOSURE INVESTIGAT.
NY STATE DEP'T. HEALTH
II UNIVERSITY PLACE
ALBANY, NY 12237 INTERAGENCY MAIL

SUBMITTED BY: KILMER



MR. BRAND
STATE OF NEW YORK
DEPARTMENT OF HEALTH

Corning Tower The Governor Nelson A. Rockefeller Empire State Plaza Albany, New York 12237

David Axelrod, M.D.
Commissioner

OFFICE OF PUBLIC HEALTH

Linda A. Randolph, M.D., M.P.H.
Director

William F. Leavy
Executive Deputy Director

December 18, 1990

DEC 2 1990

[REDACTED]

RE: Queensbury Landfill
Queensbury(T), Warren County
Site ID #557005

[REDACTED]

On October 25, 1990 I collected water samples at your home in the Town of Queensbury, Warren County. The sample was submitted to the NYS Department of Health's Wadsworth Center for Laboratories and Research for analysis of volatile organic compounds and inorganic trace metals. The enclosed report gives the results of the analysis. I have also included an explanation sheet for the NYS Dept. of Health's Analytical Report.

This report indicates that for all inorganic metals analyzed, the concentrations are within the expected background range. Iron exceeds the New York State Department of Health's Drinking Water Standards (Part 5 Secondary Contaminants) of 300 ppb for each metal and 500 ppb for the combination. These are naturally occurring compounds and there is no health significance. This is a secondary standard for aesthetic purposes and may cause turbidity, stains on plumbing fixtures, equipment and laundry.

One anomaly we would like to investigate is the detection of 1,1-dichloroethane. The level detected of this organic compound is below the NYS Department of Health's Drinking Water Standards. I will resample your drinking water to determine the validity of this result.

If you have any questions, I can be reached at (518) 458-6306.

Sincerely,

Stanley J. Kilmer
Program Research Specialist I
Bureau of Environmental Exposure
Investigation

sms/03510532

Attachment

cc: R. Tramontano/G. Litwin, w/o att.
P. Smith, CRU, w/att.
B. Fear, GFDO, w/o att.
D. Steenberge, DEC, Reg.5, w/att.
~~██████████~~ ██████████, DEC, w/att.

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER FOR LABORATORIES AND RESEARCH

PAGE 1

RESULTS OF EXAMINATION

FINAL REPORT(REV)

SAMPLE ID: 901002549 SAMPLE RECEIVED: 90/10/26/11 CHARGE: 5.10
PROGRAM: 110: STATE SUPERFUND ANALYTICAL SERVICES
SOURCE ID: DRAINAGE BASIN: 10 GAZETTEER CODE: 5657
POLITICAL SUBDIVISION: QUEENSBURY COUNTY: WARREN
LATITUDE: LONGITUDE: 2 DIRECTION:
LOCATION: QUEENSBURY LANDFILL SITE #557005

REPORTING LAB: 10: LABORATORY OF INORGANIC ANALYTICAL CHEMISTRY - ALBANY
TEST PATTERN: 10-001: SAFE DRINKING WATER ACT - METALS ONLY
SAMPLE TYPE: 120: PRIVATE WATER SUPPLY - DRILLED WELL
TIME OF SAMPLING: 90/10/25 12:45 DATE PRINTED: 90/12/12

ANALYSIS: ICP-1 ICP GROUPING 1

-----PARAMETER-----	-----RESULT-----
MERCURY	< 0.2 MCG/L
ARSENIC	< 10. MCG/L
SELENIUM	< 5. MCG/L
LEAD	< 10. MCG/L
BERYLLIUM	< 1. MCG/L
SILVER	< 10. MCG/L
BARIUM	216. MCG/L
CADMIUM	< 5. MCG/L
COBALT	< 5. MCG/L
CHROMIUM	< 5. MCG/L
COPPER	< 5. MCG/L
IRON	1820. MCG/L
MANGANESE	2060. MCG/L
NICKEL	8. MCG/L
STRONTIUM	526. MCG/L
TITANIUM	< 5. MCG/L
VANADIUM	< 5. MCG/L
ZINC	< 10. MCG/L
MOLYBDENUM	< 20. MCG/L
ANTIMONY	< 80. MCG/L
TIN	< 50. MCG/L
THALLIUM	< 80. MCG/L
ALUMINUM	< 100. MCG/L
CALCIUM	123. MG/L
POTASSIUM	1.8 MG/L
MAGNESIUM	39.1 MG/L
SODIUM	17.5 MG/L

**** CONTINUED ON NEXT PAGE ****

COPIES SENT TO: CO(3), RO(0), LPHE(1), FED(), INFO-P(), INFO-L()

RONALD TRAMONTANO, PE
BUR. ENVIRONMENTAL EXPOSURE INVESTIGAT.
NY STATE DEP'T. HEALTH
II UNIVERSITY PLACE
ALBANY, NY 12237 INTERAGENCY MAIL

SUBMITTED BY: KILMER

1215

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER FOR LABORATORIES AND RESEARCH

PAGE 2

RESULTS OF EXAMINATION

FINAL REPORT(REV)

SAMPLE ID: 901002549

SAMPLE RECEIVED: 90/10/26/11

CHARGE: 5.10

POLITICAL SUBDIVISION: QUEENSBURY

COUNTY: WARREN

LOCATION: QUEENSBURY LANDFILL SITE #557005

TIME OF SAMPLING: 90/10/25 12:45

DATE PRINTED: 90/12/12

REVISION DATE 90/12/10, FOLLOWING PARAMETERS ADDED AFTER SAMPLE REPORTED

FOLLOWING PARAMETERS NOT PART OF TEST PATTERN

-----PARAMETER-----

CO PHONED NO DAY TIME

-----RESULT-----

12-5 JD

**** END OF REPORT ****

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER FOR LABORATORIES AND RESEARCH

PAGE 1

RESULTS OF EXAMINATION

FINAL REPORT

SAMPLE ID: 903726 SAMPLE RECEIVED: 90/10/25/ CHARGE: 19.00
PROGRAM: 110: STATE SUPERFUND ANALYTICAL SERVICES
SOURCE ID: DRAINAGE BASIN: 110 GAZETTEER CODE: 5657
POLITICAL SUBDIVISION: QUEENSBURY COUNTY: WARREN
LATITUDE: LONGITUDE: Z DIRECTION:
LOCATION: QUEENSBURY LANDFILL, SITE #557005
DESCRIPTION: [REDACTED]
REPORTING LAB: TOX: LAB FOR ORGANIC ANALYTICAL CHEMISTRY
TEST PATTERN: VOL3-KET: PURGEABLES & KETONES
SAMPLE TYPE: 120: PRIVATE WATER SUPPLY - DRILLED WELL
TIME OF SAMPLING: 90/10/25 12:45 DATE PRINTED: 90/12/11

ANALYSIS: VHC5021 VOLATILE HALOGENATED ORGANICS (DES 310-29)
DATE REPORTED: 90/11/21 REPORT MAILED OUT

-----PARAMETER-----	-----RESULT-----
CHLOROMETHANE	< 0.5 MCG/L
BROMOMETHANE	< 0.5 MCG/L
VINYL CHLORIDE	< 0.5 MCG/L
DICHLORODIFLUOROMETHANE (FREON-12)	< 0.5 MCG/L
CHLOROETHANE	< 0.5 MCG/L
METHYLENE CHLORIDE (DICHLOROMETHANE)	< 0.5 MCG/L
TRICHLOROFLUOROMETHANE (FREON-11)	< 0.5 MCG/L
1,1-DICHLOROETHENE	< 0.5 MCG/L
1,1-DICHLOROETHANE	1. MCG/L
TRANS-1,2-DICHLOROETHENE	< 0.5 MCG/L
CIS-1,2-DICHLOROETHENE	< 0.5 MCG/L
CHLOROFORM	< 0.5 MCG/L
1,2-DICHLOROETHANE	< 0.5 MCG/L
DIBROMOMETHANE	< 0.5 MCG/L
1,1,1-TRICHLOROETHANE	< 0.5 MCG/L
CARBON TETRACHLORIDE	< 0.5 MCG/L
BROMODICHLOROMETHANE	< 0.5 MCG/L
2,3-DICHLOROPROPENE	< 0.5 MCG/L
1,2-DICHLOROPROPANE	< 0.5 MCG/L
CIS-1,3-DICHLOROPROPENE	< 0.5 MCG/L
TRICHLOROETHENE	< 0.5 MCG/L
1,3-DICHLOROPROPANE	< 0.5 MCG/L
DIBROMOCHLOROMETHANE	< 0.5 MCG/L
TRANS-1,3-DICHLOROPROPENE	< 0.5 MCG/L
1,1,2-TRICHLOROETHANE	< 0.5 MCG/L
1,2-DIBROMOETHANE (EDB)	< 0.5 MCG/L
2-CHLOROETHYL VINYL ETHER	< 0.5 MCG/L
BROMOFORM	< 0.5 MCG/L
1,1,1,2-TETRACHLOROETHANE	< 0.5 MCG/L
1,2,3-TRICHLOROPROPANE	< 0.5 MCG/L

*** CONTINUED ON NEXT PAGE ***

COPIES SENT TO: CO(3), RO(0), LPHE(1), FED(), INFO-P(), INFO-L()

RONALD TRAMONTANO, PE
BUR. ENVIRONMENTAL EXPOSURE INVESTIGAT.
NY STATE DEP'T. HEALTH
11 UNIVERSITY PLACE
ALBANY, NY 12237 INTERAGENCY MAIL

SUBMITTED BY: KILMER

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER FOR LABORATORIES AND RESEARCH

PAGE 2

RESULTS OF EXAMINATION

FINAL REPORT

SAMPLE ID: 903726 SAMPLE RECEIVED: 90/10/25/ CHARGE: 19.00
 POLITICAL SUBDIVISION: QUEENSBURY COUNTY: WARREN
 LOCATION: QUEENSBURY LANDFILL, SITE 1557005
 TIME OF SAMPLING: 90/10/25 12:45 DATE PRINTED: 90/12/11

PARAMETER	RESULT
1,1,2,2-TETRACHLOROETHANE	< 0.5 MCG/L
TETRACHLOROETHENE	< 0.5 MCG/L
PENTACHLOROETHANE	< 0.5 MCG/L
1-CHLOROXYCLOHEXANE-1	< 0.5 MCG/L
CHLOROBENZENE	< 0.5 MCG/L
BIS(2-CHLOROETHYL)ETHER	< 0.5 MCG/L
1,2-DIBROMO-3-CHLOROPROPANE	< 0.5 MCG/L
BROMOBENZENE	< 0.5 MCG/L
O-CHLOROTOLUENE	< 0.5 MCG/L
BIS(2-CHLOROPROPYL)ETHER	< 0.5 MCG/L
1,3-DICHLOROBENZENE	< 0.5 MCG/L
1,2-DICHLOROBENZENE	< 0.5 MCG/L
1,4-DICHLOROBENZENE	< 0.5 MCG/L

ANALYSIS: 5031 AROMATIC PURGEABLES, EPA METHOD 503.1 (DES 310-22)
 DATE REPORTED: 90/11/08 REPORT MAILED OUT

PARAMETER	RESULT
BENZENE	< 0.5 MCG/L
TOLUENE	< 0.5 MCG/L
ETHYLBENZENE	< 0.5 MCG/L
P-XYLENE	< 0.5 MCG/L
M-XYLENE	< 0.5 MCG/L
O-XYLENE	< 0.5 MCG/L
ISOPROPYLBENZENE (CUMENE)	< 0.5 MCG/L
STYRENE	< 0.5 MCG/L
P-BROMOFLUOROBENZENE	< 0.5 MCG/L
N-PROPYLBENZENE	< 0.5 MCG/L
TERT-BUTYLBENZENE	< 0.5 MCG/L
P-CHLOROTOLUENE	< 0.5 MCG/L
M-CHLOROTOLUENE	< 0.5 MCG/L
1,3,5-TRIMETHYLBENZENE	< 0.5 MCG/L
1,2,4-TRIMETHYLBENZENE	< 0.5 MCG/L
4-ISOPROPYLTOLUENE (P-CYME)	< 0.5 MCG/L
CYCLOPROPYLBENZENE	< 0.5 MCG/L
SEC-BUTYLBENZENE	< 0.5 MCG/L
N-BUTYLBENZENE	< 0.5 MCG/L
2,3-BENZOFURAN	< 0.5 MCG/L
HEXACHLOROBUTADIENE (C-46)	< 0.5 MCG/L
1,2,4-TRICHLOROBENZENE	< 0.5 MCG/L
NAPHTHALENE	< 0.5 MCG/L
1,2,3-TRICHLOROBENZENE	< 0.5 MCG/L
PH OF AROMATIC ALIQUOT	2

*** CONTINUED ON NEXT PAGE ***

1241

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER FOR LABORATORIES AND RESEARCH

PAGE 3

RESULTS OF EXAMINATION

FINAL REPORT

SAMPLE ID: 903726 SAMPLE RECEIVED: 90/10/25/ CHARGE: 19.00
POLITICAL SUBDIVISION: QUEENSBURY COUNTY: WARREN
LOCATION: QUEENSBURY LANDFILL, SITE #557005
TIME OF SAMPLING: 90/10/25 12:45 DATE PRINTED: 90/12/11

ANALYSIS: KET KETONES - PURGE & TRAP TECHNIQUE (DES 310-25)
DATE PRINTED: 90/12/11 FINAL REPORT

-----PARAMETER-----	-----RESULT-----
2-BUTANONE (METHYL ETHYL KETONE)	< 10. MCG/L
4-METHYL-2-PENTANONE (MIBK)	< 10. MCG/L
ACEPHONE	< 10. MCG/L
METHYL TERT BUTYL ETHER	< 10. MCG/L

**** END OF REPORT ****



MR. BRAND
STATE OF NEW YORK
DEPARTMENT OF HEALTH

Corning Tower The Governor Nelson A. Rockefeller Empire State Plaza Albany, New York 12237

David Axelrod, M.D.
Commissioner

OFFICE OF PUBLIC HEALTH

Linda A. Randolph, M.D., M.P.H.
Director

William F. Leavy
Executive Deputy Director

December 18, 1990

DEC 2 1990



RE: Queensbury Landfill
Queensbury(T), Warren County
Site ID #557005



On October 25, 1990 I collected water samples at your home in the Town of Queensbury, Warren County. Landfill Office. The sample was submitted to the NYS Department of Health's Wadsworth Center for Laboratories and Research for analysis of volatile organic compounds and inorganic trace metals. The enclosed report gives the results of the analysis. I have also included an explanation sheet for the NYS Dept. of Health's Analytical Report.

This report indicates that for all parameters analyzed, the concentrations are within the expected background range. Iron exceeds the New York State Department of Health's Drinking Water Standards (Part 5 Secondary Contaminants) of 300 ppb. This is a naturally occurring compound and there is no health significance. This is a secondary standard for aesthetic purposes and may cause turbidity, stains on plumbing fixtures, equipment and laundry.

If you have any questions, I can be reached at (518) 458-6306.

Sincerely,

Stanley J. Kilmer
Program Research Specialist I
Bureau of Environmental Exposure
Investigation

sms/03511009

Attachment

WALTER BRANTON BROWN

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER FOR LABORATORIES AND RESEARCH

PAGE 1

RESULTS OF EXAMINATION

FINAL REPORT(REV)

SAMPLE ID: 901002550 SAMPLE RECEIVED: 90/10/26/11 CHARGE: 5.10
PROGRAM: 110: STATE SUPERFUND ANALYTICAL SERVICES
SOURCE ID: DRAINAGE BASIN: 10 GAZETTEER CODE: 5657
POLITICAL SUBDIVISION: QUEENSBURY COUNTY: WARREN
LATITUDE: LONGITUDE: Z DIRECTION:
LOCATION: QUEENSBURY LANDFILL SITE #557005
[REDACTED] [REDACTED] [REDACTED] [REDACTED] [REDACTED]
REPORTING LAB: 10: LABORATORY OF INORGANIC ANALYTICAL CHEMISTRY - ALBANY
TEST PATTERN: 10-001: SAFE DRINKING WATER ACT - METALS ONLY
SAMPLE TYPE: 120: PRIVATE WATER SUPPLY - DRILLED WELL
TIME OF SAMPLING: 90/10/25 13:15 DATE PRINTED: 90/12/12

ANALYSIS: ICP-1 ICP GROUPING 1

-----PARAMETER-----	-----RESULT-----
MERCURY	< 0.2 MCG/L
ARSENIC	< 10. MCG/L
SELENIUM	< 5. MCG/L
LEAD	< 10. MCG/L
BERYLLIUM	< 1. MCG/L
SILVER	< 10. MCG/L
BARIUM	26. MCG/L
CADMIUM	< 5. MCG/L
COBALT	< 5. MCG/L
CHROMIUM	< 5. MCG/L
COPPER	< 5. MCG/L
IRON	441. MCG/L
MANGANESE	36. MCG/L
NICKEL	< 5. MCG/L
STRONTIUM	267. MCG/L
TITANIUM	< 5. MCG/L
VANADIUM	< 5. MCG/L
ZINC	< 10. MCG/L
MOLYBDENUM	< 20. MCG/L
ANTIMONY	< 80. MCG/L
TIN	< 50. MCG/L
THALLIUM	< 80. MCG/L
ALUMINUM	< 100. MCG/L
CALCIUM	44.2 MG/L
POTASSIUM	1.0 MG/L
MAGNESIUM	16.0 MG/L
SODIUM	3.8 MG/L

*** CONTINUED ON NEXT PAGE ***

COPIES SENT TO: CO(3), RO(0), LPHE(1), FED(0), INFO-P(0), INFO-L(1)

RONALD TRAMONTANO, PE
BUR. ENVIRONMENTAL EXPOSURE INVESTIGAT.
NY STATE DEP'T. HEALTH
11 UNIVERSITY PLACE
ALBANY, NY 12237 INTERAGENCY MAIL

SUBMITTED BY: KILMER

1223

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER FOR LABORATORIES AND RESEARCH

PAGE 2

RESULTS OF EXAMINATION

FINAL REPORT(REV)

SAMPLE ID: 901002550 SAMPLE RECEIVED: 90/10/26/11 CHARGE: 5.10
POLITICAL SUBDIVISION: QUEENSBURY COUNTY: WARREN
LOCATION: QUEENSBURY LANDFILL SITE #557005
TIME OF SAMPLING: 90/10/25 13:15 DATE PRINTED: 90/12/12

REVISION DATE 90/12/10, FOLLOWING PARAMETERS ADDED AFTER SAMPLE REPORTED

FOLLOWING PARAMETERS NOT PART OF TEST PATTERN

-----PARAMETER-----	-----RESULT-----
CO PHONED NO DAY TIME	12-5 JD
**** END OF REPORT ****	

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER FOR LABORATORIES AND RESEARCH

PAGE 1

RESULTS OF EXAMINATION

FINAL REPORT

SAMPLE ID: 903727 SAMPLE RECEIVED: 90/10/25/ CHARGE: 19.00
PROGRAM: 110: STATE SUPERFUND ANALYTICAL SERVICES
SOURCE ID: DRAINAGE BASIN: 10 GAZETTEER CODE: 5657
POLITICAL SUBDIVISION: QUEENSBURY COUNTY: WARREN
LATITUDE: LONGITUDE: Z DIRECTION:
LOCATION: QUEENSBURY LANDFILL, SITE #557005
DESCRIPTION: [REDACTED]
REPORTING LAB: TOX: LAB FOR ORGANIC ANALYTICAL CHEMISTRY
TEST PATTERN: VOL3-KET: PURGEABLES & KETONES
SAMPLE TYPE: 120: PRIVATE WATER SUPPLY - DRILLED WELL
TIME OF SAMPLING: 90/10/25 13:15 DATE PRINTED: 90/12/11

ANALYSIS: VHO5021 VOLATILE HALOGENATED ORGANICS (DES 310-29)
DATE REPORTED: 90/11/21 REPORT MAILED OUT

-----PARAMETER-----	-----RESULT-----
CHLOROMETHANE	< 0.5 MCG/L
BROMOMETHANE	< 0.5 MCG/L
VINYL CHLORIDE	< 0.5 MCG/L
DICHLORODIFLUOROMETHANE (FREON-12)	< 0.5 MCG/L
CHLOROETHANE	< 0.5 MCG/L
METHYLENE CHLORIDE (DICHLOROMETHANE)	< 0.5 MCG/L
TRICHLOROFLUOROMETHANE (FREON-11)	< 0.5 MCG/L
1,1-DICHLOROETHENE	< 0.5 MCG/L
1,1-DICHLOROETHANE	< 0.5 MCG/L
TRANS-1,2-DICHLOROETHENE	< 0.5 MCG/L
CIS-1,2-DICHLOROETHENE	< 0.5 MCG/L
CHLOROFORM	< 0.5 MCG/L
1,2-DICHLOROETHANE	< 0.5 MCG/L
DIBROMOMETHANE	< 0.5 MCG/L
1,1,1-TRICHLOROETHANE	< 0.5 MCG/L
CARBON TETRACHLORIDE	< 0.5 MCG/L
BROMODICHLOROMETHANE	< 0.5 MCG/L
2,3-DICHLOROPROPENE	< 0.5 MCG/L
1,2-DICHLOROPROPANE	< 0.5 MCG/L
CIS-1,3-DICHLOROPROPENE	< 0.5 MCG/L
TRICHLOROETHENE	< 0.5 MCG/L
1,3-DICHLOROPROPANE	< 0.5 MCG/L
DIBROMOCHLOROMETHANE	< 0.5 MCG/L
TRANS-1,3-DICHLOROPROPENE	< 0.5 MCG/L
1,1,2-TRICHLOROETHANE	< 0.5 MCG/L
1,2-DIBROMOETHANE (EDB)	< 0.5 MCG/L
2-CHLOROETHYL VINYL ETHER	< 0.5 MCG/L
BROMOFORM	< 0.5 MCG/L
1,1,1,2-TETRACHLOROETHANE	< 0.5 MCG/L
1,2,3-TRICHLOROPROPANE	< 0.5 MCG/L

*** CONTINUED ON NEXT PAGE ***

COPIES SENT TO: CO(3), RO(0), LPHE(1), FED(), INFO-P(), INFO-L()

RONALD TRAMONTANO, PE
BUR. ENVIRONMENTAL EXPOSURE INVESTIGAT.
NY STATE DEP'T. HEALTH
II UNIVERSITY PLACE
ALBANY, NY 12237 INTERAGENCY MAIL

SUBMITTED BY: KILMER

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER FOR LABORATORIES AND RESEARCH

PAGE 2

RESULTS OF EXAMINATION

FINAL REPORT

SAMPLE ID: 903727 SAMPLE RECEIVED: 90/10/25/ CHARGE: 19.00
POLITICAL SUBDIVISION: QUEENSBURY COUNTY: WARREN
LOCATION: QUEENSBURY LANDFILL, SITE #557005
TIME OF SAMPLING: 90/10/25 13:15 DATE PRINTED: 90/12/11

-----PARAMETER-----

-----RESULT-----

1,1,2,2-TETRACHLOROETHANE	< 0.5 MCG/L
TETRACHLOROETHENE	< 0.5 MCG/L
PENTACHLOROETHANE	< 0.5 MCG/L
1-CHLOROCCYCLOHEXENE-1	< 0.5 MCG/L
CHLOROBENZENE	< 0.5 MCG/L
BIS(2-CHLOROETHYL)ETHER	< 0.5 MCG/L
1,2-DIBROMO-3-CHLOROPROPANE	< 0.5 MCG/L
BROMOBENZENE	< 0.5 MCG/L
O-CHLOROTOLUENE	< 0.5 MCG/L
PIS(2-CHLOROISOPROPYL)ETHER	< 0.5 MCG/L
1,3-DICHLOROBENZENE	< 0.5 MCG/L
1,2-DICHLOROBENZENE	< 0.5 MCG/L
1,4-DICHLOROBENZENE	< 0.5 MCG/L

ANALYSIS: 5031 AROMATIC PURGEABLES, EPA METHOD 503.1 (DES 310-22)
DATE REPORTED: 90/11/08 REPORT MAILED OUT

-----PARAMETER-----

-----RESULT-----

BENZENE	< 0.5 MCG/L
TOLUENE	< 0.5 MCG/L
ETHYLBENZENE	< 0.5 MCG/L
P-XYLENE	< 0.5 MCG/L
M-XYLENE	< 0.5 MCG/L
O-XYLENE	< 0.5 MCG/L
ISOPROPYLBENZENE (CUMENE)	< 0.5 MCG/L
STYRENE	< 0.5 MCG/L
P-BROMOFLUOROBENZENE	< 0.5 MCG/L
N-PROPYLBENZENE	< 0.5 MCG/L
TERT-BUTYLBENZENE	< 0.5 MCG/L
P-CHLOROTOLUENE	< 0.5 MCG/L
M-CHLOROTOLUENE	< 0.5 MCG/L
1,3,5-TRIMETHYLBENZENE	< 0.5 MCG/L
1,2,4-TRIMETHYLBENZENE	< 0.5 MCG/L
4-ISOPROPYLTOLUENE (P-CYMENE)	< 0.5 MCG/L
CYCLOPROPYLBENZENE	< 0.5 MCG/L
SEC-BUTYLBENZENE	< 0.5 MCG/L
N-BUTYLBENZENE	< 0.5 MCG/L
2,3-BENZOFURAN	< 0.5 MCG/L
HEXACHLOROBUTADIENE (C-46)	< 0.5 MCG/L
1,2,4-TRICHLOROBENZENE	< 0.5 MCG/L
NAPHTHALENE	< 0.5 MCG/L
1,2,3-TRICHLOROBENZENE	< 0.5 MCG/L
PH OF AROMATIC ALIQUOT	2

*** CONTINUED ON NEXT PAGE ***

1247

NEW YORK STATE DEPARTMENT OF HEALTH
NORTH CENTER FOR LABORATORIES AND RESEARCH

PAGE 3

RESULTS OF EXAMINATION

FINAL REPORT

SAMPLE ID: 903727 SAMPLE RECEIVED: 90/10/25/ CHARGE: 19.00
POLITICAL SUBDIVISION: QUEENSBURY COUNTY: WARREN
LOCATION: QUEENSBURY LANDFILL, SITE #557005
TIME OF SAMPLING: 90/10/25 13:15 DATE PRINTED: 90/12/11

ANALYSIS: KET KETONES - PURGE & TRAP TECHNIQUE (DES 310-25)
DATE PRINTED: 90/12/11 FINAL REPORT

-----PARAMETER-----	-----RESULT-----
2-BUTANONE (METHYL ETHYL KETONE)	< 10. MCG/L
4-METHYL-2-PENTANONE (MIBK)	< 10. MCG/L
ACETONE	< 10. MCG/L
METHYL TERT BUTYL ETHER	< 10. MCG/L

**** END OF REPORT ****



STATE OF NEW YORK
DEPARTMENT OF HEALTH

MR. BRAND

Corning Tower The Governor Nelson A. Rockefeller Empire State Plaza Albany, New York 12237

David Axelrod, M.D.
Commissioner

OFFICE OF PUBLIC HEALTH

Linda A. Randolph, M.D., M.P.H.
Director

William F. Leavy
Executive Deputy Director

December 18, 1990

DEC 2 1990



RE: Queensbury Landfill
Queensbury(T), Warren County
Site ID #557005



On October 25, 1990 I collected water samples at the Ridge Jeninsville Park in the Town of Queensbury, Warren County. The sample was submitted to the NYS Department of Health's Wadsworth Center for Laboratories and Research for analysis of volatile organic compounds and inorganic trace metals. The enclosed report gives the results of the analysis. I have also included an explanation sheet for the NYS Dept. of Health's Analytical Report.

This report indicates that for all parameters analyzed, the concentrations are within the expected background range. Sodium exceeds the New York State Department of Health's Drinking Water Standards (Part 5 Secondary Contaminants). Although there are no designated limits, water containing more than 20 part per million of sodium should not be used for drinking by people on severely restricted sodium diets. Water containing more than 270 (ppm) of sodium should not be used for drinking by people on moderately restricted sodium diets.

If you have any questions, I can be reached at (518) 458-6306.


Sincerely,

Stanley J. Kilmer
Program Research Specialist I
Bureau of Environmental Exposure
Investigation

sms/03510722

Attachment

~~CONFIDENTIAL~~



STATE OF NEW YORK
DEPARTMENT OF HEALTH

Corning Tower The Governor Nelson A. Rockefeller Empire State Plaza Albany, New York 12237

David Axelrod, M.D.
Commissioner

OFFICE OF PUBLIC HEALTH

Linda A. Randolph, M.D., M.P.H.
Director

William F. Leavy
Executive Deputy Director

December 18, 1990

DEC 21 1990



RE: Queensbury Landfill
Queensbury(T), Warren County
Site ID #557005



On October 25, 1990 I collected water samples at your home in the Town of Queensbury, Warren County. The sample was submitted to the NYS Department of Health's Wadsworth Center for Laboratories and Research for analysis of volatile organic compounds and inorganic trace metals. The enclosed report gives the results of the analysis. I have also included an explanation sheet for the NYS Dept. of Health's Analytical Report.

This report indicates that for all parameters analyzed, the concentrations are within the expected background range. Iron exceeds the New York State Department of Health's Drinking Water Standards (Part 5 Secondary Contaminants) of 300 ppb. This is a naturally occurring compound and there is no health significance. This is a secondary standard for aesthetic purposes and may cause turbidity, stains on plumbing fixtures, equipment and laundry.

If you have any questions, I can be reached at (518) 458-6306.

Sincerely,

Stanley J. Kilmer
Program Research Specialist I
Bureau of Environmental Exposure
Investigation

sms/03511003

Attachment

cc: R. Tramontano/G. Litwin, w/o att.
P. Smith, CRU, w/att.
B. Fear, GFDO, w/o att.
D. Steenberge, DEC, Reg.5, w/att.
~~W. Leavy, DEC, w/att.~~

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER FOR LABORATORIES AND RESEARCH

PAGE 1

RESULTS OF EXAMINATION

FINAL REPORT(REV)

SAMPLE ID: 901002547 SAMPLE RECEIVED: 90/10/26/11 CHARGE: 5.10
PROGRAM: 110: STATE SUPERFUND ANALYTICAL SERVICES
SOURCE ID: DRAINAGE BASIN: 10 GAZETTEER CODE: 5657
POLITICAL SUBDIVISION: QUEENSBURY COUNTY: WARREN
LATITUDE: LONGITUDE: Z DIRECTION:
LOCATION: QUEENSBURY LANDFILL SITE #557005

REPORTING LAB: 10: LABORATORY OF INORGANIC ANALYTICAL CHEMISTRY - ALBANY
TEST PATTERN: 10-001: SAFE DRINKING WATER ACT - METALS ONLY
SAMPLE TYPE: 120: PRIVATE WATER SUPPLY - DRILLED WELL
TIME OF SAMPLING: 90/10/25 11:30 DATE PRINTED: 90/12/12

ANALYSIS: ICP-1 ICP GROUPING 1

-----PARAMETER-----	-----RESULT-----
MERCURY	< 0.2 MCG/L
ARSENIC	< 10. MCG/L
SELENIUM	< 5. MCG/L
LEAD	< 10. MCG/L
BERYLLIUM	< 1. MCG/L
SILVER	< 10. MCG/L
BARIUM	225. MCG/L
CADMIUM	< 5. MCG/L
COBALT	< 5. MCG/L
CHROMIUM	< 5. MCG/L
COPPER	< 5. MCG/L
IRON	1940. MCG/L
MANGANESE	66. MCG/L
NICKEL	< 5. MCG/L
STRONTIUM	624. MCG/L
TITANIUM	< 5. MCG/L
VANADIUM	< 5. MCG/L
ZINC	< 10. MCG/L
MOLYBDENUM	< 20. MCG/L
ANTIMONY	< 80. MCG/L
TIN	< 50. MCG/L
THALLIUM	< 80. MCG/L
ALUMINUM	< 100. MCG/L
CALCIUM	73.8 MG/L
POTASSIUM	1.8 MG/L
MAGNESIUM	37.1 MG/L
SODIUM	16.2 MG/L

**** CONTINUED ON NEXT PAGE ****

COPIES SENT TO: CO(3), RO(0), LPHE(1), FED(), INFO-P(), INFO-L()

RONALD TRAMONTANO, PE
BUR. ENVIRONMENTAL EXPOSURE INVESTIGAT.
NY STATE DEP'T. HEALTH
II UNIVERSITY PLACE
ALBANY, NY 12237 INTERAGENCY MAIL

SUBMITTED BY: KILMER

1211

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER FOR LABORATORIES AND RESEARCH

PAGE 2

RESULTS OF EXAMINATION

FINAL REPORT(REV)

SAMPLE ID: 901002547

SAMPLE RECEIVED: 90/10/26/11

CHARGE:

5.10

POLITICAL SUBDIVISION: QUEENSBURY

COUNTY: WARREN

LOCATION: QUEENSBURY LANDFILL SITE 9557005

TIME OF SAMPLING: 90/10/25 11:30

DATE PRINTED: 90/12/12

REVISION DATE 90/12/10, FOLLOWING PARAMETERS ADDED AFTER SAMPLE REPORTED

FOLLOWING PARAMETERS NOT PART OF TEST PATTERN

-----PARAMETER-----

-----RESULT-----

CO PHONED MO DAY TIME

12-5 JD

**** END OF REPORT ****

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER FOR LABORATORIES AND RESEARCH

PAGE 1

RESULTS OF EXAMINATION

FINAL REPORT

SAMPLE ID: 903724 SAMPLE RECEIVED: 90/10/25/ CHARGE: 35.50
PROGRAM: 110: STATE SUPERFUND ANALYTICAL SERVICES
SOURCE ID: DRAINAGE BASIN: 10 GAZETTEER CODE: 5657
POLITICAL SUBDIVISION: QUEENSBURY COUNTY: WARREN
LATITUDE: LONGITUDE: Z DIRECTION:
LOCATION: QUEENSBURY LANDFILL, SITE #557005

REPORTING LAB: TOX: LAB FOR ORGANIC ANALYTICAL CHEMISTRY
TEST PATTERN: AQUEOUS-1: VOLATILES, KETONES, PESTICIDES, PCB'S, PRIORITY POLLUTANTS
SAMPLE TYPE: 120: PRIVATE WATER SUPPLY - DRILLED WELL
TIME OF SAMPLING: 90/10/25 11:30 DATE PRINTED: 90/12/11

ANALYSIS: VHO5021 VOLATILE HALOGENATED ORGANICS (DES 310-29)
DATE REPORTED: 90/11/21 REPORT MAILED OUT

-----PARAMETER-----	-----RESULT-----
CHLOROMETHANE	< 0.5 MCG/L
BROMOMETHANE	< 0.5 MCG/L
VINYL CHLORIDE	< 0.5 MCG/L
DICHLORODIFLUOROMETHANE (FREON-12)	< 0.5 MCG/L
CHLOROETHANE	< 0.5 MCG/L
METHYLENE CHLORIDE (DICHLOROMETHANE)	< 0.5 MCG/L
TRICHLOROFLUOROMETHANE (FREON-11)	< 0.5 MCG/L
1,1-DICHLOROETHENE	< 0.5 MCG/L
1,1-DICHLOROETHANE	< 0.5 MCG/L
TRANS-1,2-DICHLOROETHENE	< 0.5 MCG/L
CIS-1,2-DICHLOROETHENE	< 0.5 MCG/L
CHLOROFORM	< 0.5 MCG/L
1,2-DICHLOROETHANE	< 0.5 MCG/L
DIBROMOMETHANE	< 0.5 MCG/L
1,1,1-TRICHLOROETHANE	< 0.5 MCG/L
CARBON TETRACHLORIDE	< 0.5 MCG/L
BROMODICHLOROMETHANE	< 0.5 MCG/L
2,3-DICHLOROPROPENE	< 0.5 MCG/L
1,2-DICHLOROPROPANE	< 0.5 MCG/L
CIS-1,3-DICHLOROPROPENE	< 0.5 MCG/L
TRICHLOROETHENE	< 0.5 MCG/L
1,3-DICHLOROPROPANE	< 0.5 MCG/L
DIBROMOCHLOROMETHANE	< 0.5 MCG/L
TRANS-1,3-DICHLOROPROPENE	< 0.5 MCG/L
1,1,2-TRICHLOROETHANE	< 0.5 MCG/L
1,2-DIBROMOETHANE (EDB)	< 0.5 MCG/L
2-CHLOROETHYL VINYL ETHER	< 0.5 MCG/L
BROMOFORM	< 0.5 MCG/L
1,1,1,2-TETRACHLOROETHANE	< 0.5 MCG/L
1,2,3-TRICHLOROPROPANE	< 0.5 MCG/L

*** CONTINUED ON NEXT PAGE ***

COPIES SENT TO: CO(3), RO(0), LPHE(1), FED(), INFO-P(), INFO-L()

RONALD TRAMONTANO, PE
BUR. ENVIRONMENTAL EXPOSURE INVESTIGAT.
NY STATE DEP'T. HEALTH
II UNIVERSITY PLACE
ALBANY, NY 12237 INTERAGENCY MAIL

SUBMITTED BY: KILMER

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER FOR LABORATORIES AND RESEARCH

PAGE 2

RESULTS OF EXAMINATION

FINAL REPORT

SAMPLE ID: 903724 SAMPLE RECEIVED: 90/10/25/ CHARGE: 35.50
POLITICAL SUBDIVISION: QUEENSBURY COUNTY: WARREN
LOCATION: QUEENSBURY LANDFILL, SITE #557005
TIME OF SAMPLING: 90/10/25 11:30 DATE PRINTED: 90/12/11

PARAMETER	RESULT
1,1,2,2-TETRACHLOROETHANE	< 0.5 MCG/L
TETRACHLOROETHENE	< 0.5 MCG/L
PENTACHLOROETHANE	< 0.5 MCG/L
1-CHLOROCYCLOHEXENE-1	< 0.5 MCG/L
CHLOROBENZENE	< 0.5 MCG/L
BIS(2-CHLOROETHYL)ETHER	< 0.5 MCG/L
1,2-DIBROMO-3-CHLOROPROPANE	< 0.5 MCG/L
BROMOBENZENE	< 0.5 MCG/L
O-CHLOROTOLUENE	< 0.5 MCG/L
BIS(2-CHLOROISOPROPYL)ETHER	< 0.5 MCG/L
1,3-DICHLOROBENZENE	< 0.5 MCG/L
1,2-DICHLOROBENZENE	< 0.5 MCG/L
1,4-DICHLOROBENZENE	< 0.5 MCG/L

ANALYSIS: 5031 AROMATIC PURGEABLES, EPA METHOD 503.1 (DES 310-22)
DATE REPORTED: 90/11/02 REPORT MAILED OUT

PARAMETER	RESULT
BENZENE	< 0.5 MCG/L
TOLUENE	< 0.5 MCG/L
ETHYLBENZENE	< 0.5 MCG/L
P-XYLENE	< 0.5 MCG/L
M-XYLENE	< 0.5 MCG/L
O-XYLENE	< 0.5 MCG/L
ISOPROPYLBENZENE (CUMENE)	< 0.5 MCG/L
STYRENE	< 0.5 MCG/L
P-BROMOFLUOROBENZENE	< 0.5 MCG/L
N-PROPYLBENZENE	< 0.5 MCG/L
TERT-BUTYLBENZENE	< 0.5 MCG/L
P-CHLOROTOLUENE	< 0.5 MCG/L
M-CHLOROTOLUENE	< 0.5 MCG/L
1,3,5-TRIMETHYLBENZENE	< 0.5 MCG/L
1,2,4-TRIMETHYLBENZENE	< 0.5 MCG/L
4-ISOPROPYLTOLUENE (P-CYME)	< 0.5 MCG/L
CYCLOPROPYLBENZENE	< 0.5 MCG/L
SEC-BUTYLBENZENE	< 0.5 MCG/L
N-BUTYLBENZENE	< 0.5 MCG/L
2,3-BENZOFURAN	< 0.5 MCG/L
HEXACHLOROBUTADIENE (C-46)	< 0.5 MCG/L
1,2,4-TRICHLOROBENZENE	< 0.5 MCG/L
NAPHTHALENE	< 0.5 MCG/L
1,2,3-TRICHLOROBENZENE	< 0.5 MCG/L
PH OF AROMATIC ALIQUOT	2.

**** CONTINUED ON NEXT PAGE ****

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER FOR LABORATORIES AND RESEARCH

PAGE 3

RESULTS OF EXAMINATION

FINAL REPORT

SAMPLE ID: 903724 SAMPLE RECEIVED: 90/10/25/ CHARGE: 35.50
POLITICAL SUBDIVISION: QUEENSBURY COUNTY: WARREN
LOCATION: QUEENSBURY LANDFILL, SITE #557005
TIME OF SAMPLING: 90/10/25 11:30 DATE PRINTED: 90/12/11

ANALYSIS: KET KETONES - PURGE & TRAP TECHNIQUE (DES 310-25)
DATE PRINTED: 90/12/11 FINAL REPORT

PARAMETER	RESULT
2-BUTANONE (METHYL ETHYL KETONE)	< 10. MCG/L
4-METHYL-2-PENTANONE (MIBK)	< 10. MCG/L
ACETONE	< 10. MCG/L
METHYL TERT BUTYL ETHER	< 10. MCG/L

ANALYSIS: XPEST-PCB ORGANOCHLORINE PESTICIDES & PCB'S (DES 310-2)
DATE REPORTED: 90/11/27 REPORT MAILED OUT

PARAMETER	RESULT
HCH, ALPHA	< 0.04 MCG/L
HCH, BETA	< 0.04 MCG/L
HCH, GAMMA (LINDANE)	< 0.04 MCG/L
HCH, DELTA	< 0.04 MCG/L
HEPTACHLOR	< 0.05 MCG/L
ALDRIN	< 0.02 MCG/L
HEPTACHLOR EPOXIDE	< 0.05 MCG/L
ENDOSULFAN I	< 0.05 MCG/L
4,4'-DDE	< 0.05 MCG/L
DIELDRIN	< 0.02 MCG/L
ENDRIN	< 0.02 MCG/L
4,4'-DDD	< 0.05 MCG/L
ENDOSULFAN II	< 0.05 MCG/L
ENDRIN ALDEHYDE	< 0.02 MCG/L
ENDOSULFAN SULFATE	< 0.05 MCG/L
4,4'-DDT	< 0.05 MCG/L
METHOXYCHLOR	< 0.5 MCG/L
TOXAPHENE	< 1.0 MCG/L
CHLORDANE	< 0.1 MCG/L
MIREX	< 0.05 MCG/L
PCB, AROCLOR 1221	< 0.05 MCG/L
PCB, AROCLOR 1016/1242	< 0.05 MCG/L
PCB, AROCLOR 1248	< 0.05 MCG/L
PCB, AROCLOR 1254	< 0.05 MCG/L
PCB, AROCLOR 1260	< 0.05 MCG/L

ANALYSIS: GC-FID-A PRIORITY POLLUTANTS*ACIDS*GC/FID RESULTS
DATE REPORTED: 90/11/27 REPORT MAILED OUT

PARAMETER	RESULT
PHENOL	< 10. MCG/L
2-CHLOROPHENOL	< 10. MCG/L
2-NITROPHENOL	< 10. MCG/L
2,4-DIMETHYLPHENOL	< 10. MCG/L
2,4-DICHLOROPHENOL	< 10. MCG/L
4-CHLORO-3-METHYLPHENOL	< 10. MCG/L

*** CONTINUED ON NEXT PAGE ***

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER FOR LABORATORIES AND RESEARCH

PAGE 4

RESULTS OF EXAMINATION

FINAL REPORT

SAMPLE ID: 903724 SAMPLE RECEIVED: 90/10/25/ CHARGE: 35.50
POLITICAL SUBDIVISION: QUEENSBURY COUNTY: WARREN
LOCATION: QUEENSBURY LANDFILL, SITE #557005
TIME OF SAMPLING: 90/10/25 11:30 DATE PRINTED: 90/12/11

-----PARAMETER-----	-----RESULT-----
2,4,6-TRICHLOROPHENOL	< 10. MCG/L
2,4,5-TRICHLOROPHENOL	< 10. MCG/L
2,4-DINITROPHENOL	< 10. MCG/L
4-NITROPHENOL	< 10. MCG/L
2-METHYL-4,6-DINITROPHENOL	< 10. MCG/L
PENTACHLOROPHENOL	< 10. MCG/L

ANALYSIS: GC-FID-BN PRIORITY POLLUTANTS*BASE/NEUTRALS*GC/FID RESULTS
DATE REPORTED: 90/11/27 REPORT MAILED OUT

-----PARAMETER-----	-----RESULT-----
N-NITROSODI-N-PROPYLAMINE	< 10. MCG/L
HEXACHLOROETHANE	< 10. MCG/L
NITROBENZENE	< 10. MCG/L
ISOPHORONE	< 10. MCG/L
BIS(2-CHLOROETHOXY)METHANE	< 10. MCG/L
HEXACHLOROCYCLOPENTADIENE (C-56)	< 10. MCG/L
2-CHLORONAPHTHALENE	< 10. MCG/L
2,6-DINITROTOLUENE	< 10. MCG/L
ACENAPHTHYLENE	< 10. MCG/L
DIMETHYLPHTHALATE	< 10. MCG/L
ACENAPHTHENE	< 10. MCG/L
2,4-DINITROTOLUENE	< 10. MCG/L
DIETHYLPHTHALATE	< 10. MCG/L
FLUORENE	< 10. MCG/L
N-NITROSODIPHENYLAMINE	< 10. MCG/L
1,2-DIPHENYLHYDRAZINE	< 10. MCG/L
4-BROMOPHENYL PHENYL ETHER	< 10. MCG/L
HEXACHLOROBENZENE	< 10. MCG/L
PHENANTHRENE	< 10. MCG/L
ANTHRACENE	< 10. MCG/L
DI-N-BUTYL PHTHALATE	< 10. MCG/L
FLUORANTHENE	< 10. MCG/L
PYRENE	< 10. MCG/L
BENZIDINE	< 30. MCG/L
BUTYL BENZYL PHTHALATE	< 30. MCG/L
BENZO(A)ANTHRACENE	< 10. MCG/L
3,3'-DICHLOBENZIDINE	< 10. MCG/L
CHRYSENE	< 10. MCG/L
BIS(2-ETHYLHEXYL)PHTHALATE	< 30. MCG/L
DI-N-OCTYL PHTHALATE	< 30. MCG/L
BENZO(B)FLUORANTHENE	< 20. MCG/L
BENZO(K)FLUORANTHENE	< 20. MCG/L
BENZO(A)PYRENE	< 20. MCG/L
INDENO(1,2,3-CD)PYRENE	< 20. MCG/L
DIBENZO(AH)ANTHRACENE	< 20. MCG/L
BENZO(GHI)PERYLENE	< 20. MCG/L

**** END OF REPORT ****



MR. BRAND
STATE OF NEW YORK
DEPARTMENT OF HEALTH

Corning Tower The Governor Nelson A. Rockefeller Empire State Plaza Albany, New York 12237

David Axelrod, M.D.
Commissioner

OFFICE OF PUBLIC HEALTH

Linda A. Randolph, M.D. M.P.H.
Director

William F. Leavy
Executive Deputy Director

December 18, 1990

DEC 2 1990

RE: Queensbury Landfill
Queensbury(T), Warren County
Site ID #557005

On October 25, 1990 I collected water samples at the Town of Queensbury Landfill Office. The sample was submitted to the NYS Department of Health's Wadsworth Center for Laboratories and Research for analysis of volatile organic compounds and inorganic trace metals. The enclosed report gives the results of the analysis. I have also included an explanation sheet for the NYS Dept. of Health's Analytical Report.

This report indicates that for all inorganic metals analyzed, the concentrations are within the expected background range. Iron exceeds the New York State Department of Health's Drinking Water Standards (Part 5 Secondary Contaminants) of 300 ppb. This is a naturally occurring compound and there is no health significance. This is a secondary standard for aesthetic purposes and may cause turbidity, stains on plumbing fixtures, equipment and laundry.

One anomaly we would like to investigate is the detection of trichloroethene. The level detected of this organic compound is below NYS Department of Health's Drinking Water Standards. I will resample your drinking water to determine the validity of this result.

If you have any questions, I can be reached at (518) 458-6306.

Sincerely,

Stanley J. Kilmer
Program Research Specialist I
Bureau of Environmental Exposure
Investigation

sms/03510488

Attachment

cc: R. Tramontano/G. Litwin, w/o att.
P. Smith, CRU, w/att.
B. Fear, GFDO, w/o att.
D. Steenberge, DEC Reg.5, w/att.
M. Brand, DEC, w/att.

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER FOR LABORATORIES AND RESEARCH

PAGE 1

RESULTS OF EXAMINATION

FINAL REPORT(REV)

SAMPLE ID: 901002546 SAMPLE RECEIVED: 90/10/26/11 CHARGE: 5.10
PROGRAM: 110: STATE SUPERFUND ANALYTICAL SERVICES
SOURCE ID: DRAINAGE BASIN: 10 GAZETTEER CODE: 5657
POLITICAL SUBDIVISION: QUEENSBURY COUNTY: WARREN
LATITUDE: LONGITUDE: Z DIRECTION:
LOCATION: QUEENSBURY LANDFILL SITE #557005
DESCRIPTION: #1 QUEENSBURY LANDFILL OFFICE KIT TAP
REPORTING LAB: 10: LABORATORY OF INORGANIC ANALYTICAL CHEMISTRY - ALBANY
TEST PATTERN: 10-001: SAFE DRINKING WATER ACT - METALS ONLY
SAMPLE TYPE: 120: PRIVATE WATER SUPPLY - DRILLED WELL
TIME OF SAMPLING: 90/10/25 10:30 DATE PRINTED: 90/12/12

ANALYSIS: ICP-1 ICP GROUPING 1

-----PARAMETER-----	-----RESULT-----
MERCURY	< 0.2 MCG/L
ARSENIC	< 10. MCG/L
SELENIUM	< 5. MCG/L
LEAD	< 10. MCG/L
BERYLLIUM	< 1. MCG/L
SILVER	< 10. MCG/L
BARIUM	464. MCG/L
CADMIUM	< 5. MCG/L
COBALT	< 5. MCG/L
CHROMIUM	< 5. MCG/L
COPPER	< 5. MCG/L
IRON	344. MCG/L
MANGANESE	15. MCG/L
NICKEL	< 5. MCG/L
STRONTIUM	1460. MCG/L
TITANIUM	< 5. MCG/L
VANADIUM	< 5. MCG/L
ZINC	628. MCG/L
MOLYBDENUM	< 20. MCG/L
ANTIMONY	< 80. MCG/L
TIN	< 50. MCG/L
THALLIUM	< 80. MCG/L
ALUMINUM	< 100. MCG/L
CALCIUM	36.1 MG/L
POTASSIUM	1.6 MG/L
MAGNESIUM	18.2 MG/L
SODIUM	18.4 MG/L

**** CONTINUED ON NEXT PAGE ****

COPIES SENT TO: CO(3), RO(0), LPHE(1), FED(), INFO-P(), INFO-L()

RONALD TRAMONTANO, PE
BUR. ENVIRONMENTAL EXPOSURE INVESTIGAT.
NY STATE DEP'T, HEALTH
11 UNIVERSITY PLACE
ALBANY, NY 12237 INTERAGENCY MAIL

SUBMITTED BY: KILMER

1203

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER FOR LABORATORIES AND RESEARCH

PAGE 2

RESULTS OF EXAMINATION

FINAL REPORT(REV)

SAMPLE ID: 901002546 SAMPLE RECEIVED: 90/10/26/11 CHARGE: 5.10
POLITICAL SUBDIVISION: QUEENSBURY COUNTY: WARREN
LOCATION: QUEENSBURY LANDFILL SITE #557005
TIME OF SAMPLING: 90/10/25 10:30 DATE PRINTED: 90/12/12

REVISION DATE 90/12/10, FOLLOWING PARAMETERS ADDED AFTER SAMPLE REPORTED

FOLLOWING PARAMETERS NOT PART OF TEST PATTERN

-----PARAMETER-----

-----RESULT-----

CU PHONED NO DAY TIME

12-5 JD

**** END OF REPORT ****

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER FOR LABORATORIES AND RESEARCH

PAGE 1

RESULTS OF EXAMINATION

FINAL REPORT

SAMPLE ID: 903723 SAMPLE RECEIVED: 90/10/25/ CHARGE: 35.50
 PROGRAM: 110: STATE SUPERFUND ANALYTICAL SERVICES
 SOURCE ID: DRAINAGE BASIN: 10 GAZETTEER CODE: 5657
 POLITICAL SUBDIVISION: QUEENSBURY COUNTY: WARREN
 LATITUDE: LONGITUDE: Z DIRECTION:
 LOCATION: QUEENSBURY LANDFILL, SITE #557005
 DESCRIPTION: #1, QUEENSBURY LANDFILL OFFICE, KITCHEN TAP
 REPORTING LAB: TOX: LAB FOR ORGANIC ANALYTICAL CHEMISTRY
 TEST PATTERN: AQUEOUS-1: VOLATILES, KETONES, PESTICIDES, PCB'S, PRIORITY POLLUTANT
 SAMPLE TYPE: 120: PRIVATE WATER SUPPLY - DRILLED WELL
 TIME OF SAMPLING: 90/10/25 10:30 DATE PRINTED: 90/12/11

ANALYSIS: VHC5021 VOLATILE HALOGENATED ORGANICS (DES 310-29)
 DATE REPORTED: 90/11/21 REPORT MAILED OUT

-----PARAMETER-----	-----RESULT-----
CHLOROMETHANE	< 0.5 MCG/L
BROMOMETHANE	< 0.5 MCG/L
VINYL CHLORIDE	< 0.5 MCG/L
DICHLORODIFLUOROMETHANE (FREON-12)	< 0.5 MCG/L
CHLOROETHANE	< 0.5 MCG/L
METHYLENE CHLORIDE (DICHLOROMETHANE)	< 0.5 MCG/L
TRICHLOROFLUOROMETHANE (FREON-11)	< 0.5 MCG/L
1,1-DICHLOROETHENE	< 0.5 MCG/L
1,1-DICHLOROETHANE	< 0.5 MCG/L
TRANS-1,2-DICHLOROETHENE	< 0.5 MCG/L
CIS-1,2-DICHLOROETHENE	< 0.5 MCG/L
CHLOROFORM	< 0.5 MCG/L
1,2-DICHLOROETHANE	< 0.5 MCG/L
DIBROMOMETHANE	< 0.5 MCG/L
1,1,1-TRICHLOROETHANE	< 0.5 MCG/L
CARBON TETRACHLORIDE	< 0.5 MCG/L
BROMODICHLOROMETHANE	< 0.5 MCG/L
2,3-DICHLOROPROPENE	< 0.5 MCG/L
1,2-DICHLOROPROPANE	< 0.5 MCG/L
CIS-1,3-DICHLOROPROPENE	< 0.5 MCG/L
TRICHLOROETHENE	2. MCG/L
1,3-DICHLOROPROPANE	< 0.5 MCG/L
DIBROMOCHLOROMETHANE	< 0.5 MCG/L
TRANS-1,3-DICHLOROPROPENE	< 0.5 MCG/L
1,1,2-TRICHLOROETHANE	< 0.5 MCG/L
1,2-DIBROMOETHANE (EDB)	< 0.5 MCG/L
2-CHLOROETHYL VINYL ETHER	< 0.5 MCG/L
BROMOFORM	< 0.5 MCG/L
1,1,1,2-TETRACHLOROETHANE	< 0.5 MCG/L
1,2,3-TRICHLOROPROPANE	< 0.5 MCG/L

**** CONTINUED ON NEXT PAGE ****

COPIES SENT TO: CO(3), RO(0), LPHE(1), FED(), INFO-P(), INFO-L()

RONALD TRAMONTANO, PE
 BUR. ENVIRONMENTAL EXPOSURE INVESTIGAT.
 NY STATE DEP'T. HEALTH
 11 UNIVERSITY PLACE
 ALBANY, NY 12237 INTERAGENCY MAIL

SUBMITTED BY: KILMER

NEW YORK STATE DEPARTMENT OF HEALTH
WATSWORTH CENTER FOR LABORATORIES AND RESEARCH

PAGE 2

RESULTS OF EXAMINATION

FINAL REPORT

SAMPLE ID: 903723 SAMPLE RECEIVED: 90/10/25/ CHARGE: 35.50
POLITICAL SUBDIVISION: QUEENSBURY COUNTY: WARREN
LOCATION: QUEENSBURY LANDFILL, SITE #557005
TIME OF SAMPLING: 90/10/25 10:30 DATE PRINTED: 90/12/11

-----PARAMETER-----	-----RESULT-----
1,1,2,2-TETRACHLOROETHANE	< 0.5 MCG/L
TETRACHLOROETHENE	< 0.5 MCG/L
PENTACHLOROETHANE	< 0.5 MCG/L
1-CHLOROCYCLOHEXENE-1	< 0.5 MCG/L
CHLOROBENZENE	< 0.5 MCG/L
BIS(2-CHLOROETHYL)ETHER	< 0.5 MCG/L
1,2-DIBROMO-3-CHLOROPROPANE	< 0.5 MCG/L
BROMOBENZENE	< 0.5 MCG/L
O-CHLOROTOLUENE	< 0.5 MCG/L
BIS(2-CHLOROISOPROPYL)ETHER	< 0.5 MCG/L
1,3-DICHLOROBENZENE	< 0.5 MCG/L
1,2-DICHLOROBENZENE	< 0.5 MCG/L
1,4-DICHLOROBENZENE	< 0.5 MCG/L

ANALYSIS: 5031 AROMATIC PURGEABLES, EPA METHOD 503.1 (DES 310-22)
DATE REPORTED: 90/11/02 REPORT MAILED OUT

-----PARAMETER-----	-----RESULT-----
BENZENE	< 0.5 MCG/L
TOLUENE	< 0.5 MCG/L
ETHYLBENZENE	< 0.5 MCG/L
P-XYLENE	< 0.5 MCG/L
M-XYLENE	< 0.5 MCG/L
O-XYLENE	< 0.5 MCG/L
ISOPROPYLBENZENE (CUMENE)	< 0.5 MCG/L
STYRENE	< 0.5 MCG/L
P-BROMOFLUOROBENZENE	< 0.5 MCG/L
N-PROPYLBENZENE	< 0.5 MCG/L
TERT-BUTYLBENZENE	< 0.5 MCG/L
P-CHLOROTOLUENE	< 0.5 MCG/L
M-CHLOROTOLUENE	< 0.5 MCG/L
1,3,5-TRIMETHYLBENZENE	< 0.5 MCG/L
1,2,4-TRIMETHYLBENZENE	< 0.5 MCG/L
4-ISOPROPYLTOLUENE (P-CYMENE)	< 0.5 MCG/L
CYCLOPROPYLBENZENE	< 0.5 MCG/L
SEC-BUTYLBENZENE	< 0.5 MCG/L
N-BUTYLBENZENE	< 0.5 MCG/L
2,3-BENZOFURAN	< 0.5 MCG/L
HEXACHLOROCYCLOPENTADIENE (C-46)	< 0.5 MCG/L
1,2,4-TRICHLOROBENZENE	< 0.5 MCG/L
NAPHTHALENE	< 0.5 MCG/L
1,2,3-TRICHLOROBENZENE	< 0.5 MCG/L
PH OF AROMATIC ALIQUOT	2.

**** CONTINUED ON NEXT PAGE ****

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER FOR LABORATORIES AND RESEARCH

PAGE 3

RESULTS OF EXAMINATION

FINAL REPORT

SAMPLE ID: 903723 SAMPLE RECEIVED: 90/10/25/ CHARGE: 35.50
POLITICAL SUBDIVISION: QUEENSBURY COUNTY: WARREN
LOCATION: QUEENSBURY LANDFILL, SITE #557005
TIME OF SAMPLING: 90/10/25 10:30 DATE PRINTED: 90/12/11

ANALYSIS: KET KETONES - PURGE & TRAP TECHNIQUE (DES 310-25)
DATE PRINTED: 90/12/11 FINAL REPORT

-----PARAMETER-----	-----RESULT-----
2-BUTANONE (METHYL ETHYL KETONE)	< 10. MCG/L
4-METHYL-2-PENTANONE (MIBK)	< 10. MCG/L
ACETONE	< 10. MCG/L
METHYL TERT BUTYL ETHER	< 10. MCG/L

ANALYSIS: XREST-PCB ORGANOCHLORINE PESTICIDES & PCB'S (DES310-2)
DATE REPORTED: 90/11/27 REPORT MAILED OUT

-----PARAMETER-----	-----RESULT-----
HCH, ALPHA	< 0.04 MCG/L
HCH, BETA	< 0.04 MCG/L
HCH, GAMMA (LINAPNE)	< 0.04 MCG/L
HCH, DELTA	< 0.04 MCG/L
HEPTACHLOR	< 0.05 MCG/L
ALDRIN	< 0.02 MCG/L
HEPTACHLOR EPOXIDE	< 0.05 MCG/L
ENDOSULFAN I	< 0.05 MCG/L
4,4'-DDE	< 0.05 MCG/L
DIELDRIN	< 0.02 MCG/L
ENDRIN	< 0.02 MCG/L
4,4'-DDD	< 0.05 MCG/L
ENDOSULFAN II	< 0.05 MCG/L
ENDRIN ALDEHYDE	< 0.02 MCG/L
ENDOSULFAN SULFATE	< 0.05 MCG/L
4,4'-DDT	< 0.05 MCG/L
METHOXYCHLOR	< 0.5 MCG/L
TOXAPHENE	< 1.0 MCG/L
CHLORDANE	< 0.1 MCG/L
MIREX	< 0.05 MCG/L
PCB, AROCLOR 1221	< 0.05 MCG/L
PCB, AROCLOR 1016/1242	< 0.05 MCG/L
PCB, AROCLOR 1248	< 0.05 MCG/L
PCB, AROCLOR 1254	< 0.05 MCG/L
PCB, AROCLOR 1260	< 0.05 MCG/L

ANALYSIS: GC-FID-A PRIORITY POLLUTANTS*ACIDS*GC/FID RESULTS
DATE REPORTED: 90/11/27 REPORT MAILED OUT

-----PARAMETER-----	-----RESULT-----
PHENOL	< 10. MCG/L
2-CHLOROPHENOL	< 10. MCG/L
2-NITROPHENOL	< 10. MCG/L
2,4-DIMETHYLPHENOL	< 10. MCG/L
2,4-DICHLOROPHENOL	< 10. MCG/L
4-CHLORO-3-METHYLPHENOL	< 10. MCG/L

**** CONTINUED ON NEXT PAGE ****

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER FOR LABORATORIES AND RESEARCH

PAGE 4

RESULTS OF EXAMINATION

FINAL REPORT


SAMPLE ID: 903723 SAMPLE RECEIVED: 90/10/25/ CHARGE: 35.50
POLITICAL SUBDIVISION: QUEENSBURY COUNTY: WARREN
LOCATION: QUEENSBURY LANDFILL, SITE #557005
TIME OF SAMPLING: 90/10/25 10:30 DATE PRINTED: 90/12/11

PARAMETER	RESULT
2,4,6-TRICHLOROPHENOL	< 10. MCG/L
2,4,5-TRICHLOROPHENOL	< 10. MCG/L
2,4-DINITROPHENOL	< 10. MCG/L
4-NITROPHENOL	< 10. MCG/L
2-METHYL-4,6-DINITROPHENOL	< 10. MCG/L
PENTACHLOROPHENOL	< 10. MCG/L

ANALYSIS: GC-FID-BN PRIORITY POLLUTANTS*BASE/NEUTRALS*GC/FID RESULTS
DATE REPORTED: 90/11/27 REPORT MAILED OUT

PARAMETER	RESULT
N-NITROSODI-N-PROPYLAMINE	< 10. MCG/L
HEXACHLOROETHANE	< 10. MCG/L
NITROBENZENE	< 10. MCG/L
ISOPHORONE	< 10. MCG/L
BIS(2-CHLOROETHOXY)METHANE	< 10. MCG/L
HEXACHLOROCYCLOPENTADIENE (C-56)	< 10. MCG/L
2-CHLORONAPHTHALENE	< 10. MCG/L
2,6-DINITROTOLUENE	< 10. MCG/L
ACENAPHTHYLENE	< 10. MCG/L
DIMETHYLPHTHALATE	< 10. MCG/L
ACENAPHTHENE	< 10. MCG/L
2,4-DINITROTOLUENE	< 10. MCG/L
DIETHYLPHTHALATE	< 10. MCG/L
FLUORENE	< 10. MCG/L
N-NITROSODIPHENYLAMINE	< 10. MCG/L
1,2-DIPHENYLHYDRAZINE	< 10. MCG/L
4-BROMOPHENYL PHENYL ETHER	< 10. MCG/L
HEXACHLOROBENZENE	< 10. MCG/L
PHENANTHRENE	< 10. MCG/L
ANTHRACENE	< 10. MCG/L
DI-N-BUTYL PHTHALATE	< 10. MCG/L
FLUORANTHENE	< 10. MCG/L
PYRENE	< 10. MCG/L
BENZIDINE	< 30. MCG/L
BUTYL BENZYL PHTHALATE	< 30. MCG/L
BENZO(A)ANTHRACENE	< 10. MCG/L
3,3'-DICHLOROBENZIDINE	< 10. MCG/L
CHRYSENE	< 10. MCG/L
BIS(2-ETHYLHEXYL)PHTHALATE	< 30. MCG/L
DI-N-OCTYL PHTHALATE	< 30. MCG/L
BENZO(B)FLUORANTHENE	< 20. MCG/L
BENZO(K)FLUORANTHENE	< 20. MCG/L
BENZO(A)PYRENE	< 20. MCG/L
INDENO(1,2,3-CD)PYRENE	< 20. MCG/L
DIBENZO(AH)ANTHRACENE	< 20. MCG/L
BENZO(GHI)PERYLENE	< 20. MCG/L

**** END OF REPORT ****



STATE OF NEW YORK DEPARTMENT OF HEALTH

Corning Tower The Governor Nelson A. Rockefeller Empire State Plaza Albany, New York 12237

David Axelrod, M.D.
Commissioner

OFFICE OF PUBLIC HEALTH

Linda A. Randolph, M.D., MPH
Director

William F. Leavy
Executive Deputy Director

December 18, 1990

DEC 2 1990

[REDACTED]

RE: Queensbury Landfill
Queensbury(T), Warren County
Site ID #557005

[REDACTED]

On October 25, 1990 I collected water samples at your home in the Town of Queensbury, Warren County. The sample was submitted to the NYS Department of Health's Wadsworth Center for Laboratories and Research for analysis of volatile organic compounds and inorganic trace metals. The enclosed report gives the results of the analysis. I have also included an explanation sheet for the NYS Dept. of Health's Analytical Report.

I am pleased to report that for all parameters analyzed, the concentrations are within the expected background range.

If you have any questions, I can be reached at (518) 458-6306.

Sincerely,

Stanley J. Kilmer
Program Research Specialist I
Bureau of Environmental Exposure
Investigation

sms/03510658

Attachment

cc: R. Tramontano/G. Litwin, w/o att.
P. Smith, CRU, w/att.
B. Fear, GFDO, w/o att.
D. Steenberge, DEC Reg.5, w/att.
~~W. Brand~~, DEC, w/att.

NEW YORK STATE DEPARTMENT OF HEALTH
WALSHORTH CENTER FOR LABORATORIES AND RESEARCH

PAGE 1

RESULTS OF EXAMINATION

FINAL REPORT

SAMPLE ID: 901002548 SAMPLE RECEIVED: 90/10/26/11 CHARGE: 5.00
PROGRAM: 110: STATE SUPERFUND ANALYTICAL SERVICES
SOURCE ID: DRAINAGE BASIN: 10 GAZETTEER CODE: 5657
POLITICAL SUBDIVISION: QUEENSBURY COUNTY: WARREN
LATITUDE: LONGITUDE: Z DIRECTION:
LOCATION: QUEENSBURY LANDFILL SITE #557005
[REDACTED]
REPORTING LAB: 10: LABORATORY OF INORGANIC ANALYTICAL CHEMISTRY - ALBANY
TEST PATTERN: 10-001: SAFE DRINKING WATER ACT - METALS ONLY
SAMPLE TYPE: 120: PRIVATE WATER SUPPLY - DRILLED WELL
TIME OF SAMPLING: 90/10/25 12:15 DATE PRINTED: 90/11/28

ANALYSIS: ICP-1 ICP GROUPING 1

-----PARAMETER-----	-----RESULT-----
MERCURY	< 0.2 MCG/L
ARSENIC	< 10. MCG/L
SELENIUM	< 5. MCG/L
LEAD	< 10. MCG/L
BERYLLIUM	< 1. MCG/L
SILVER	< 10. MCG/L
BARIUM	35. MCG/L
CADMIUM	< 5. MCG/L
COBALT	< 5. MCG/L
CHROMIUM	< 5. MCG/L
COPPER	8. MCG/L
IRON	162. MCG/L
MANGANESE	< 5. MCG/L
NICKEL	< 5. MCG/L
STRONTIUM	265. MCG/L
TITANIUM	< 5. MCG/L
VANADIUM	< 5. MCG/L
ZINC	< 10. MCG/L
MOLYBDENUM	< 20. MCG/L
ANTIMONY	< 80. MCG/L
TIN	< 50. MCG/L
THALLIUM	< 80. MCG/L
ALUMINUM	< 100. MCG/L
CALCIUM	71.5 MG/L
POTASSIUM	1.6 MG/L
MAGNESIUM	29.7 MG/L
SODIUM	5.9 MG/L

**** END OF REPORT ****

COPIES SENT TO: CO(3), RO(0), LPHE(1), FED(), INFO-P(), INFO-L()

RONALD TRAMONTANO, PE
BUR. ENVIRONMENTAL EXPOSURE INVESTIGAT.
NY STATE DEP'T. HEALTH
II UNIVERSITY PLACE
ALBANY, NY 12237 INTERAGENCY MAIL

SUBMITTED BY: KILMER

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER FOR LABORATORIES AND RESEARCH

PAGE 1

RESULTS OF EXAMINATION

FINAL REPORT

SAMPLE ID: 903725 SAMPLE RECEIVED: 90/10/25/ CHARGE: 19.00
PROGRAM: 110: STATE SUPERFUND ANALYTICAL SERVICES
SOURCE ID: DRAINAGE BASIN: 10 GAZETTEER CODE: 5657
POLITICAL SUBDIVISION: QUEENSBURY COUNTY: WARREN
LATITUDE: LONGITUDE: Z DIRECTION:
LOCATION: QUEENSBURY LANDFILL, SITE #557005
DESCRIPTION: [REDACTED] AP
REPORTING LAB: TOX: LAB FOR ORGANIC ANALYTICAL CHEMISTRY
TEST PATTERN: VOL3-KET: PURGEABLES & KETONES
SAMPLE TYPE: 120: PRIVATE WATER SUPPLY - DRILLED WELL
TIME OF SAMPLING: 90/10/25 12:15 DATE PRINTED: 90/12/11

ANALYSIS: VHC5021 VOLATILE HALOGENATED ORGANICS (DES 310-29)
DATE REPORTED: 90/11/21 REPORT MAILED OUT

-----PARAMETER-----	-----RESULT-----
CHLOROMETHANE	< 0.5 MCG/L
BROMOMETHANE	< 0.5 MCG/L
VINYL CHLORIDE	< 0.5 MCG/L
DICHLORODIFLUOROMETHANE (FREON-12)	< 0.5 MCG/L
CHLOROETHANE	< 0.5 MCG/L
METHYLENE CHLORIDE (DICHLOROMETHANE)	< 0.5 MCG/L
TRICHLOROFLUOROMETHANE (FREON-11)	< 0.5 MCG/L
1,1-DICHLOROETHENE	< 0.5 MCG/L
1,1-DICHLOROETHANE	< 0.5 MCG/L
TRANS-1,2-DICHLOROETHENE	< 0.5 MCG/L
CIS-1,2-DICHLOROETHENE	< 0.5 MCG/L
CHLOROFORM	< 0.5 MCG/L
1,2-DICHLOROETHANE	< 0.5 MCG/L
DIBROMOMETHANE	< 0.5 MCG/L
1,1,1-TRICHLOROETHANE	< 0.5 MCG/L
CARBON TETRACHLORIDE	< 0.5 MCG/L
BROMODICHLOROMETHANE	< 0.5 MCG/L
2,3-DICHLOROPROPENE	< 0.5 MCG/L
1,2-DICHLOROPROPANE	< 0.5 MCG/L
CIS-1,3-DICHLOROPROPENE	< 0.5 MCG/L
TRICHLOROETHENE	< 0.5 MCG/L
1,3-DICHLOROPROPANE	< 0.5 MCG/L
DIBROMOCHLOROMETHANE	< 0.5 MCG/L
TRANS-1,3-DICHLOROPROPENE	< 0.5 MCG/L
1,1,2-TRICHLOROETHANE	< 0.5 MCG/L
1,2-DIBROMOETHANE (EDB)	< 0.5 MCG/L
2-CHLOROETHYL VINYL ETHER	< 0.5 MCG/L
BROMOFORM	< 0.5 MCG/L
1,1,1,2-TETRACHLOROETHANE	< 0.5 MCG/L
1,2,3-TRICHLOROPROPANE	< 0.5 MCG/L

*** CONTINUED ON NEXT PAGE ***

COPIES SENT TO: CO(3), RO(0), LPHE(1), FED(), INFO-P(), INFO-L()

RONALD TRAMONTANO, PE
BUR. ENVIRONMENTAL EXPOSURE INVESTIGAT.
NY STATE DEP'T. HEALTH
11 UNIVERSITY PLACE
ALBANY, NY 12237 INTERAGENCY MAIL

SUBMITTED BY: KILMER

NEW YORK STATE DEPARTMENT OF HEALTH
WATSWORTH CENTER FOR LABORATORIES AND RESEARCH

PAGE 2

RESULTS OF EXAMINATION

FINAL REPORT

SAMPLE ID: 903725 SAMPLE RECEIVED: 90/10/25/ CHARGE: 19.00
 POLITICAL SUBDIVISION: QUEENSBURY COUNTY: WARREN
 LOCATION: QUEENSBURY LANDFILL, SITE #557005
 TIME OF SAMPLING: 90/10/25 12:15 DATE PRINTED: 90/12/11

PARAMETER	RESULT
1,1,2,2-TETRACHLOROETHANE	< 0.5 MCG/L
TETRACHLOROETHENE	< 0.5 MCG/L
PENTACHLOROETHANE	< 0.5 MCG/L
1-CHLOROCYCLOHEXENE-1	< 0.5 MCG/L
CHLOROBENZENE	< 0.5 MCG/L
BIS(2-CHLOROPHTHYL)ETHER	< 0.5 MCG/L
1,2-DIBROMO-3-CHLOROPROPANE	< 0.5 MCG/L
BROMOBENZENE	< 0.5 MCG/L
O-CHLOROTOLUENE	< 0.5 MCG/L
BIS(2-CHLOROISOPROPYL)ETHER	< 0.5 MCG/L
1,3-DICHLOROBENZENE	< 0.5 MCG/L
1,2-DICHLOROBENZENE	< 0.5 MCG/L
1,4-DICHLOROBENZENE	< 0.5 MCG/L

ANALYSIS: 5031 AROMATIC PURGEABLES, EPA METHOD 503.1 (DES 310-22)
 DATE REPORTED: 90/11/08 REPORT MAILED OUT

PARAMETER	RESULT
BENZENE	< 0.5 MCG/L
TOLUENE	< 0.5 MCG/L
ETHYLBENZENE	< 0.5 MCG/L
P-XYLENE	< 0.5 MCG/L
M-XYLENE	< 0.5 MCG/L
O-XYLENE	< 0.5 MCG/L
ISOPROPYLBENZENE (CUMENE)	< 0.5 MCG/L
STYRENE	< 0.5 MCG/L
P-BROMOFLUOROBENZENE	< 0.5 MCG/L
N-PROPYLBENZENE	< 0.5 MCG/L
TERT-BUTYLBENZENE	< 0.5 MCG/L
P-CHLOROTOLUENE	< 0.5 MCG/L
M-CHLOROTOLUENE	< 0.5 MCG/L
1,3,5-TRIMETHYLBENZENE	< 0.5 MCG/L
1,2,4-TRIMETHYLBENZENE	< 0.5 MCG/L
4-ISOPROPYLTOLUENE (P-CYMENE)	< 0.5 MCG/L
CYCLOPROPYLBENZENE	< 0.5 MCG/L
SEC-BUTYLBENZENE	< 0.5 MCG/L
N-BUTYLBENZENE	< 0.5 MCG/L
2,3-BENZOFURAN	< 0.5 MCG/L
HEXACHLOROCYCLODIENE (C-46)	< 0.5 MCG/L
1,2,4-TRICHLOROBENZENE	< 0.5 MCG/L
NAPHTHALENE	< 0.5 MCG/L
1,2,3-TRICHLOROBENZENE	< 0.5 MCG/L
PH OF AROMATIC ALIQUOT	2

**** CONTINUED ON NEXT PAGE ****

1229 .

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER FOR LABORATORIES AND RESEARCH

PAGE 3

RESULTS OF EXAMINATION

FINAL REPORT

SAMPLE ID: 903725 SAMPLE RECEIVED: 90/10/25/ CHARGE: 19.00
POLITICAL SUBDIVISION: QUEENSBURY COUNTY: WARREN
LOCATION: QUEENSBURY LANDFILL, SITE #557005
TIME OF SAMPLING: 90/10/25 12:15 DATE PRINTED: 90/12/11

ANALYSIS: KET KETONES - PURGE & TRAP TECHNIQUE (DES 310-25)
DATE PRINTED: 90/12/11 FINAL REPORT

-----PARAMETER-----	-----RESULT-----
2-BUTANONE (METHYL ETHYL KETONE)	< 10. MCG/L
4-METHYL-2-PENTANONE (MIBK)	< 10. MCG/L
ACETONE	< 10. MCG/L
METHYL TERT BUTYL ETHER	< 10. MCG/L

**** END OF REPORT ****

STATE OF NEW YORK - DEPARTMENT OF HEALTH
INTEFOFFICE MEMORANDUM

TO: Gary A. Litwin, Section Chief
Bureau of Environmental Exposure Investigation

FROM: Stanley J. Kilmer, Program Research Specialist I
Bureau of Environmental Exposure Investigation

SUBJECT: Resample Private Drinking Water Wells
Queensbury Landfill
Queensbury (T), Warren County
Site ID #557005

DATE: March 25, 1991

This is an addition to memorandum dated December 19, 1990 concerning drinking water sampling events around the Queensbury Landfill. Please note a new site map locating the additional sampling points.

On January 28, 1991 I traveled to the Queensbury area for the purpose of resampling resident's drinking water. All samples were transported in an iced cooler with three field blanks and delivered to the NYS Dept. of Health Wadsworth Center for Laboratories and Research in Albany for Analysis.

Analytical results of drinking water samples from residential wells in the area adjacent to the landfill were mailed to homeowners on March 4, 1991. Chlorinated compounds were detected in one of the wells and the field blank at levels ranging from 1 to 2 ppb. I will resample the Town of Queensbury Landfill Office because of the detection of trichloroethene in the first sample and detection in the field blank on the second sampling event. I will resample the [REDACTED] because of the detection of 1,1-dichloroethane in both samples. I will also try to resample the [REDACTED] because of the detection trichloroethene in sample taken October 25, 1990.

SAMPLING NOTES AND LABORATORY RESULTS:

SAMPLE #1 - [REDACTED]

Analysis: Organic Compounds - 502.1.
Results: None detected.

SAMPLE #4 - [REDACTED]

Analysis: Organic compounds - 502.1.
Results: 1,1-dichloroethane - 2. ppb.

Gary A. Litwin, Section Chief

SAMPLE #9 - [REDACTED]

Analysis: Organic compounds - 502.1, 503.1 and ketones. Inorganic compounds - HSL metals.

Results: None detected or within background range.

SAMPLE #10 - [REDACTED]

Analysis: Organic compounds - 502.1, 503.1 and ketones. Inorganic compounds - HSL metals.

Results: sodium - 45.2 ppm.

SAMPLE #11 - [REDACTED]

Analysis: Organic compounds - 502.1, 503.1 and ketones. Inorganic compounds - HSL metals.

Results: None detected or within background range.

Please note attachment: 1) Area sketch of sampling locations.

sjk/10790416

Attachment


cc: R. Tramontano, w/att.
Dr. N. Kim, w/att.
P. Smith, CRU, w/att.
B. Fear, GFDO, w/att.

QUEENSBURY LANDFILL - Warren County

Site #557005

□ on
#11 on
RL 149

DRINKING WATER SURVEY - SAMPLING LOCATIONS



NOT TO SCALE

SJK07-11/01/90

REV 03/12/91



STATE OF NEW YORK DEPARTMENT OF HEALTH

Corning Tower The Governor Nelson A. Rockefeller Empire State Plaza Albany, New York 12237

David Axelrod, M.D.
Commissioner

OFFICE OF PUBLIC HEALTH

Linda A. Randolph, M.D., M.P.H.
Director

William F. Leavy
Executive Deputy Director

March 4, 1991

[REDACTED]

RE: Queensbury Landfill
Queensbury(T), Warren County
Site ID #557005

Dear [REDACTED]:

On January 28, 1991 I collected water samples at your home in the Town of Queensbury. This report indicates the detection of 1,1-dichloroethane. The level detected of this organic compound is below the NYS Department of Health's Public Drinking Water Standards. We would like to further investigate the detection of this chlorinated compound. The installation of new monitoring wells at the landfill will help determine the extent of the off site contamination. Until that data is available, I will resample your drinking water.

The samples were submitted to the NYS Department of Health's Wadsworth Center for Laboratories and Research for analysis. I have also included an explanation sheet which may help you interpret the sample results. If you have any questions, I can be reached at (518) 458-6306.

Sincerely,

Stanley J. Kilmer
Program Research Specialist I
Bureau of Environmental Exposure
Investigation

sjk/10631182

Attachment

cc: R. Tramontano/G. Litwin, w/o att.
P. Smith, CRU, w/o att.
B. Fear, GFDO, w/o att.
D. Steenberge, DEC-Reg. 5, w/att.
M. Brand, DEC, w/att.

PAGE 1

RESULTS OF EXAMINATION

FINAL REPORT

SAMPLE ID: 910459 SAMPLE RECEIVED: 91/01/28/ CHARGE: 8.00
 PROGRAM: 110: STATE SUPERFUND ANALYTICAL SERVICES
 SOURCE ID: DRAINAGE BASIN: 10 GAZETTEER CODE: 5657
 POLITICAL SUBDIVISION: QUEENSBURY COUNTY: WARREN
 LATITUDE: LONGITUDE: 2 DIRECTION:
 LOCATION: 557005 QUEENSBURY LANDFILL
 DESCRIPTION: [REDACTED]
 REPORTING LAB: TOX: LAB FOR ORGANIC ANALYTICAL CHEMISTRY
 TEST PATTERN: VHO5021: VOLATILE HALOGENATED ORGANICS
 SAMPLE TYPE: 120: PRIVATE WATER SUPPLY - DRILLED WELL
 TIME OF SAMPLING: 91/01/28 11:30 DATE PRINTED: 91/02/20

ANALYSIS: VHO5021 VOLATILE HALOGENATED ORGANICS (DES 310-29)
 DATE PRINTED: 91/02/20 FINAL REPORT

PARAMETER	RESULT
CHLOROMETHANE	< 0.5 MCG/L
BROMOMETHANE	< 0.5 MCG/L
VINYL CHLORIDE	< 0.5 MCG/L
DICHLORODIFLUOROMETHANE (FREON-12)	< 0.5 MCG/L
CHLOROETHANE	< 0.5 MCG/L
METHYLENE CHLORIDE (DICHLOROMETHANE)	< 0.5 MCG/L
TRICHLOROFLUOROMETHANE (FREON-11)	< 0.5 MCG/L
1,1-DICHLOROETHENE	< 0.5 MCG/L
1,1-DICHLOROETHANE	2. MCG/L
TRANS-1,2-DICHLOROETHENE	< 0.5 MCG/L
CIS-1,2-DICHLOROETHENE	< 0.5 MCG/L
CHLOROFORM	< 0.5 MCG/L
1,2-DICHLOROETHANE	< 0.5 MCG/L
DIBROMOMETHANE	< 0.5 MCG/L
1,1,1-TRICHLOROETHANE	< 0.5 MCG/L
CARBON TETRACHLORIDE	< 0.5 MCG/L
BROMODICHLOROMETHANE	< 0.5 MCG/L
2,3-DICHLOROPROPENE	< 0.5 MCG/L
1,2-DICHLOROPROPANE	< 0.5 MCG/L
CIS-1,3-DICHLOROPROPENE	< 0.5 MCG/L
TRICHLOROETHENE	< 0.5 MCG/L
1,3-DICHLOROPROPANE	< 0.5 MCG/L
DIBROMOCHLOROMETHANE	< 0.5 MCG/L
TRANS-1,3-DICHLOROPROPENE	< 0.5 MCG/L
1,1,2-TRICHLOROETHANE	< 0.5 MCG/L
1,2-DIBROMOETHANE (EDB)	< 0.5 MCG/L
2-CHLOROETHYL VINYL ETHER	< 0.5 MCG/L
BROMOFORM	< 0.5 MCG/L
1,1,1,2-TETRACHLOROETHANE	< 0.5 MCG/L
1,2,3-TRICHLOROPROPANE	< 0.5 MCG/L

*** CONTINUED ON NEXT PAGE ***

COPIES SENT TO: CO(3), RO(0), LPHE(1), PED(), INFO-P(), INFO-L()

RONALD TRAMONTANO, PE

BUR. ENVIRONMENTAL EXPOSURE INVESTIGAT.

NY STATE DEPT. HEALTH

11 UNIVERSITY PLACE

ALBANY, NY 12237 INTERAGENCY MAIL

SUBMITTED BY: KILMER

PAGE 2

RESULTS OF EXAMINATION

FINAL REPORT

SAMPLE ID: 910459 SAMPLE RECEIVED: 91/01/28/ CHARGE: 8.00
POLITICAL SUBDIVISION: QUEENSBURY COUNTY: WARREN
LOCATION: 557005 QUEENSBURY LANDFILL
TIME OF SAMPLING: 91/01/28 11:30 DATE PRINTED: 91/02/20

-----PARAMETER-----	-----RESULT-----
1,1,2,2-TETRACHLOROETHANE	< 0.5 MCG/L
TETRACHLOROETHENE	< 0.5 MCG/L
PENTACHLOROETHANE	< 0.5 MCG/L
1-CHLOROCYCLOHEXENE-1	< 0.5 MCG/L
CHLOROBENZENE	< 0.5 MCG/L
BIS(2-CHLOROPHYL)ETHER	< 0.5 MCG/L
1,2-DIBROMO-3-CHLOROPROPANE	< 0.5 MCG/L
BROMOBENZENE	< 0.5 MCG/L
O-CHLOROTOLUENE	< 0.5 MCG/L
BIS(2-CHLOROISOPROPYL)ETHER	< 0.5 MCG/L
1,3-DICHLOROBENZENE	< 0.5 MCG/L
1,2-DICHLOROBENZENE	< 0.5 MCG/L
1,4-DICHLOROBENZENE	< 0.5 MCG/L

**** END OF REPORT ****



STATE OF NEW YORK DEPARTMENT OF HEALTH

Corning Tower The Governor Nelson A. Rockefeller Empire State Plaza Albany, New York 12237

David Axelrod M.D.
Commissioner

OFFICE OF PUBLIC HEALTH

Linda A. Randolph M.D. M.P.H.
Director

William F. Leavy
Executive Deputy Director

March 4, 1991

[REDACTED]

RE: Queensbury Landfill
Queensbury(T), Warren County
Site ID #557005

[REDACTED]:

On January 28, 1991 I collected water samples at the Town of Queensbury Landfill Office. I am pleased to report that there were no detected volatile organic compounds.

The sample was submitted to the NYS Department of Health's Wadsworth Center for Laboratories and Research for analysis. I have also included an explanation sheet which may help you interpret the sample results. If you have any questions, I can be reached at (518) 458-6306.

Sincerely,

Stanley J. Kilmer
Program Research Specialist I
Bureau of Environmental Exposure
Investigation

sjk/10600761

Attachment

cc: R. Tramontano/G. Litwin, w/o att.
P. Smith, CRU, w/o att.
B. Fear, GFDO, w/o att.
D. Steenberge, DEC-Reg. 5, w/att.
M. Brand, DEC, w/att.

PAGE 1

RESULTS OF EXAMINATION

FINAL REPORT

SAMPLE ID: 910460 SAMPLE RECEIVED: 91/01/28/ CHARGE: 8.00
PROGRAM: 110: STATE SUPERFUND ANALYTICAL SERVICES
SOURCE ID: DRAINAGE BASIN: 10 GAZETTEER CODE: 5657
POLITICAL SUBDIVISION: QUEENSBURY COUNTY: WARREN
LATITUDE: LONGITUDE: Z DIRECTION:
LOCATION: 557005 QUEENSBURY LANDFILL
DESCRIPTION: #1 QUEENSBURY LANDFILL OFFICE, [REDACTED]
REPORTING LAB: TOX: LAB FOR ORGANIC ANALYTICAL CHEMISTRY
TEST PATTERN: VHO5021: VOLATILE HALOGENATED ORGANICS
SAMPLE TYPE: 120: PRIVATE WATER SUPPLY - DRILLED WELL
TIME OF SAMPLING: 91/01/28 10:45 DATE PRINTED: 91/02/20

ANALYSIS: VHO5021 VOLATILE HALOGENATED ORGANICS (DES 310-29)
DATE PRINTED: 91/02/20 FINAL REPORT

-----PARAMETER-----	-----RESULT-----
CHLOROMETHANE	< 0.5 MCG/L
BROMOMETHANE	< 0.5 MCG/L
VINYL CHLORIDE	< 0.5 MCG/L
DICHLORODIFLUOROMETHANE (FREON-12)	< 0.5 MCG/L
CHLOROETHANE	< 0.5 MCG/L
METHYLENE CHLORIDE (DICHLOROMETHANE)	< 0.5 MCG/L
TRICHLOROFLUOROMETHANE (FREON-11)	< 0.5 MCG/L
1,1-DICHLOROETHENE	< 0.5 MCG/L
1,1-DICHLOROETHANE	< 0.5 MCG/L
TRANS-1,2-DICHLOROETHENE	< 0.5 MCG/L
CIS-1,2-DICHLOROETHENE	< 0.5 MCG/L
CHLOROFORM	< 0.5 MCG/L
1,2-DICHLOROETHANE	< 0.5 MCG/L
DIBROMOMETHANE	< 0.5 MCG/L
1,1,1-TRICHLOROETHANE	< 0.5 MCG/L
CARBON TETRACHLORIDE	< 0.5 MCG/L
BROMODICHLOROMETHANE	< 0.5 MCG/L
2,3-DICHLOROPROPENE	< 0.5 MCG/L
1,2-DICHLOROPROPANE	< 0.5 MCG/L
CIS-1,3-DICHLOROPROPENE	< 0.5 MCG/L
TRICHLOROETHENE	< 0.5 MCG/L
1,3-DICHLOROPROPANE	< 0.5 MCG/L
DIBROMOCHLOROMETHANE	< 0.5 MCG/L
TRANS-1,3-DICHLOROPROPENE	< 0.5 MCG/L
1,1,2-TRICHLOROETHANE	< 0.5 MCG/L
1,2-DIBROMOETHANE (EDB)	< 0.5 MCG/L
2-CHLOROETHYL VINYL ETHER	< 0.5 MCG/L
BROMOFORM	< 0.5 MCG/L
1,1,1,2-TETRACHLOROETHANE	< 0.5 MCG/L
1,2,3-TRICHLOROPROPANE	< 0.5 MCG/L

**** CONTINUED ON NEXT PAGE ****

COPIES SENT TO: CO(3), RO(0), LPHE(1), FED(), INFO-P(), INFO-L()

RONALD TRAMONTANO, PE
BUR. ENVIRONMENTAL EXPOSURE INVESTIGAT.
NY STATE DEPT. HEALTH
11 UNIVERSITY PLACE
ALBANY, NY 12237 INTERAGENCY MAIL

SUBMITTED BY: KILNER

PAGE 2

RESULTS OF EXAMINATION

FINAL REPORT

SAMPLE ID: 910460 SAMPLE RECEIVED: 91/01/28/ CHARGE: 8.00
POLITICAL SUBDIVISION: QUEENSBURY COUNTY: WARREN
LOCATION: 557005 QUEENSBURY LANDFILL
TIME OF SAMPLING: 91/01/28 10:45 DATE PRINTED: 91/02/20

-----PARAMETER-----	-----RESULT-----
1,1,2,2-TETRACHLOROETHANE	< 0.5 MCG/L
TETRACHLOROETHENE	< 0.5 MCG/L
PENTACHLOROETHANE	< 0.5 MCG/L
1-CHLOROCYCLOHEXENE-1	< 0.5 MCG/L
CHLOROBENZENE	< 0.5 MCG/L
BIS(2-CHLOROETHYL)ETHER	< 0.5 MCG/L
1,2-DIBROMO-3-CHLOROPROPANE	< 0.5 MCG/L
BROMOBENZENE	< 0.5 MCG/L
O-CHLOROTOLUENE	< 0.5 MCG/L
BIS(2-CHLOROISOPROPYL)ETHER	< 0.5 MCG/L
1,3-DICHLOROBENZENE	< 0.5 MCG/L
1,2-DICHLOROBENZENE	< 0.5 MCG/L
1,4-DICHLOROBENZENE	< 0.5 MCG/L

**** END OF REPORT ****



STATE OF NEW YORK DEPARTMENT OF HEALTH

Corning Tower The Governor Nelson A. Rockefeller Empire State Plaza Albany, New York 12237

David Axelrod, M.D.
Commissioner

OFFICE OF PUBLIC HEALTH

Linda A. Randolph, M.D., M.P.H.
Director

William F. Leavy
Executive Deputy Director

March 4, 1991



RE: Queensbury Landfill
Queensbury(T), Warren County
Site ID #557005



On January 28, 1991 I collected water samples at your store in the Town of Queensbury. I am pleased to report that there were no detected volatile organic compounds and for all inorganic metals analyzed, the concentrations are within the the expected background range. Sodium exceeds the New York State Department of Health's Public Drinking Water Standards (Part 5 Secondary Contaminants). Although there are no designated limits, water containing more than 20 part per million of sodium should not be use for drinking by people on severely restricted sodium.

The samples were submitted to the NYS Department of Health's Wadsworth Center for Laboratories and Research for analysis. I have also included an explanation sheet which may help you interpret the sample results. If you have any questions, I can be reached at (518) 458-6306.

Sincerely,

Stanley J. Kilmer
Program Research Specialist I
Bureau of Environmental Exposure
Investigation

sjk/10630876

Attachment

cc: R. Tramontano/G. Litwin, w/o att.
P. Smith, CRU, w/o att.
B. Fear, GFDO, w/o att.
D. Steenberge, DEC-Reg. 5, w/att.
M. Brand, DEC, w/att.

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER FOR LABORATORIES AND RESEARCH

PAGE 1

RESULTS OF EXAMINATION

FINAL REPORT

SAMPLE ID: 910456 SAMPLE RECEIVED: 91/01/28/ CHARGE: 19.00
 PROGRAM: 110: STATE SUPERFUND ANALYTICAL SERVICES
 SOURCE ID: DRAINAGE BASIN: 10 GAZETTEER CODE: 5657
 POLITICAL SUBDIVISION: QUEENSBURY COUNTY: WARREN
 LATITUDE: LONGITUDE: Z DIRECTION:
 LOCATION: 557005 QUEENSBURY LANDFILL
 DESCRIPTION: #2 [REDACTED]
 REPORTING LAB: TOX: LAB FOR ORGANIC ANALYTICAL CHEMISTRY
 TEST PATTERN: VOL3-KET: PURGEABLES & KETONES
 SAMPLE TYPE: 120: PRIVATE WATER SUPPLY - DRILLED WELL
 TIME OF SAMPLING: 91/01/28 11:45 DATE PRINTED: 91/02/25

ANALYSIS: VHC5021 VOLATILE HALUGENATED ORGANICS (DES 310-29)
 DATE REPORTED: 91/02/20 REPORT MAILED OUT

PARAMETER	RESULT
CHLOROMETHANE	< 0.5 MCG/L
BROMOMETHANE	< 0.5 MCG/L
VINYL CHLORIDE	< 0.5 MCG/L
DICHLORODIFLUOROMETHANE (FREON-12)	< 0.5 MCG/L
CHLOROETHANE	< 0.5 MCG/L
METHYLENE CHLORIDE (DICHLOROMETHANE)	< 0.5 MCG/L
TRICHLOROFLUOROMETHANE (FREON-11)	< 0.5 MCG/L
1,1-DICHLOROETHENE	< 0.5 MCG/L
1,1-DICHLOROETHANE	< 0.5 MCG/L
TRANS-1,2-DICHLOROETHENE	< 0.5 MCG/L
CIS-1,2-DICHLOROETHENE	< 0.5 MCG/L
CHLOROFORM	< 0.5 MCG/L
1,2-DICHLOROETHANE	< 0.5 MCG/L
DIBROMOMETHANE	< 0.5 MCG/L
1,1,1-TRICHLOROETHANE	< 0.5 MCG/L
CARBON TETRACHLORIDE	< 0.5 MCG/L
BROMODICHLOROMETHANE	< 0.5 MCG/L
2,3-DICHLOROPROPENE	< 0.5 MCG/L
1,2-DICHLOROPROPANE	< 0.5 MCG/L
CIS-1,3-DICHLOROPROPENE	< 0.5 MCG/L
TRICHLOROETHENE	< 0.5 MCG/L
1,3-DICHLOROPROPANE	< 0.5 MCG/L
DIBROMOCHLOROMETHANE	< 0.5 MCG/L
TRANS-1,3-DICHLOROPROPENE	< 0.5 MCG/L
1,1,2-TRICHLOROETHANE	< 0.5 MCG/L
1,2-DIBROMOETHANE (EDB)	< 0.5 MCG/L
2-CHLOROETHYL VINYL ETHER	< 0.5 MCG/L
BROMOFORM	< 0.5 MCG/L
1,1,1,2-TETRACHLOROETHANE	< 0.5 MCG/L
1,2,3-TRICHLOROPROPANE	< 0.5 MCG/L

**** CONTINUED ON NEXT PAGE ****

COPIES SENT TO: CO(3), RO(0), LPHE(1), FED(), INFO-P(), INFO-L()

RONALD TRAMONTANO, PE
 BUR. ENVIRONMENTAL EXPOSURE INVESTIGAT.
 NY STATE DEPT. HEALTH
 11 UNIVERSITY PLACE
 ALBANY, NY 12237 INTERAGENCY MAIL

SUBMITTED BY: KILMER

PAGE 2

RESULTS OF EXAMINATION

FINAL REPORT

SAMPLE ID: 910456 SAMPLE RECEIVED: 91/01/28/ CHARGE: 19.00
POLITICAL SUBDIVISION: QUEENSBURY COUNTY: WARREN
LOCATION: 557005 QUEENSBURY LANDFILL
TIME OF SAMPLING: 91/01/28 11:45 DATE PRINTED: 91/02/25

-----PARAMETER-----

1,1,2,2-TETRACHLOROETHANE
TETRACHLOROETHENE
PENTACHLOROETHANE
1-CHLOROCYCLOHEXENE-1
CHLOROBENZENE
BIS(2-CHLOROETHYL)ETHER
1,2-DIBROMO-3-CHLOROPROPANE
BROMOBENZENE
O-CHLOROTOLUENE
BIS(2-CHLOROISOPROPYL)ETHER
1,3-DICHLOROBENZENE
1,2-DICHLOROBENZENE
1,4-DICHLOROBENZENE

-----RESULT-----

< 0.5 MCG/L
< 0.5 MCG/L
< 0.5 MCG/L
< 0.5 MCG/L
< 0.5 MCG/L
< 0.5 MCG/L
< 0.5 MCG/L
< 0.5 MCG/L
< 0.5 MCG/L
< 0.5 MCG/L
< 0.5 MCG/L
< 0.5 MCG/L
< 0.5 MCG/L

ANALYSIS: 5031 AROMATIC PURGEABLES, EPA METHOD 503.1 (DES 310-22)
DATE PRINTED: 91/02/25 FINAL REPORT

-----PARAMETER-----

BENZENE
TOLUENE
ETHYLBENZENE
P-XYLENE
M-XYLENE
O-XYLENE
ISOPROPYLBENZENE (CUMENE)
STYRENE
P-BROMOFLUOROBENZENE
N-PROPYLBENZENE
TERT-BUTYLBENZENE
P-CHLOROTOLUENE
M-CHLOROTOLUENE
1,3,5-TRIMETHYLBENZENE
1,2,4-TRIMETHYLBENZENE
4-ISOPROPYLTOLUENE (P-CYMENE)
CYCLOPROPYLBENZENE
SEC-BUTYLBENZENE
N-BUTYLBENZENE
2,3-BENZOFURAN
HEXACHLOROBUTADIENE (C-46)
1,2,4-TRICHLOROBENZENE
NAPHTHALENE
1,2,3-TRICHLOROBENZENE
PH OF AROMATIC ALIQUOT

-----RESULT-----

< 0.5 MCG/L
< 0.5 MCG/L
< 0.5 MCG/L
< 0.5 MCG/L
< 0.5 MCG/L
< 0.5 MCG/L
< 0.5 MCG/L
< 0.5 MCG/L
< 0.5 MCG/L
< 0.5 MCG/L
< 0.5 MCG/L
< 0.5 MCG/L
< 0.5 MCG/L
< 0.5 MCG/L
< 0.5 MCG/L
< 0.5 MCG/L
< 0.5 MCG/L
< 0.5 MCG/L
< 0.5 MCG/L
< 0.5 MCG/L
< 0.5 MCG/L
< 0.5 MCG/L
7

PH WAS NOT AS LOW AS REQUIRED BY METHOD YES

*** CONTINUED ON NEXT PAGE ***

NEW YORK STATE DEPARTMENT OF HEALTH
MAJ SWORTH CENTER FOR LABORATORIES AND RESEARCH

PAGE 3

RESULTS OF EXAMINATION

FINAL REPORT

SAMPLE ID: 910456 SAMPLE RECEIVED: 91/01/28/ CHARGE: 19.00
POLITICAL SUBDIVISION: QUEENSBURY COUNTY: WARREN
LOCATION: 557005 QUEENSBURY LANDFILL
TIME OF SAMPLING: 91/01/28 11:45 DATE PRINTED: 91/02/25

ANALYSIS: KET KETONES - PURGE & TRAP TECHNIQUE (DES 310-25)
DATE REPORTED: 91/02/08 REPORT MAILED OUT

-----PARAMETER-----	-----RESULT-----
2-BUTANONE (METHYL ETHYL KETONE)	< 10. MCG/L
4-METHYL-2-PENTANONE (MIBK)	< 10. MCG/L
ACETONE	< 10. MCG/L
METHYL TERT BUTYL ETHER	< 10. MCG/L

**** END OF REPORT ****

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER FOR LABORATORIES AND RESEARCH

PAGE 1

RESULTS OF EXAMINATION

FINAL REPORT

SAMPLE ID: 911000206 SAMPLE RECEIVED: 91/01/29/ CHARGE: 5.00
PROGRAM: 110: STATE SUPERFUND ANALYTICAL SERVICES
SOURCE ID: DRAINAGE BASIN: 10 GAZETTEER CODE: 5657
POLITICAL SUBDIVISION: QUEENSBURY COUNTY: WARREN
LATITUDE: LONGITUDE: Z DIRECTION:
LOCATION: 557005 QUEENSBURY LANDFILL
DESCRIPTION: #2 [REDACTED]
REPORTING LAB: 10: LABORATORY OF INORGANIC ANALYTICAL CHEMISTRY - ALBAN.
TEST PATTERN: 10-001: SAFE DRINKING WATER ACT - METALS ONLY
SAMPLE TYPE: 120: PRIVATE WATER SUPPLY - DRILLED WELL
TIME OF SAMPLING: 91/01/28 11:45 DATE PRINTED: 91/02/26

ANALYSIS: ICP-1 ICP GROUPING 1

-----PARAMETER-----	-----RESULT-----
MERCURY	< 0.2 MCG/L
ARSENIC	< 10. MCG/L
SELENIUM	< 5. MCG/L
LEAD	< 10. MCG/L
BERYLLIUM	< 1. MCG/L
SILVER	< 10. MCG/L
BARIUM	174. MCG/L
CADMIUM	< 5. MCG/L
COBALT	< 5. MCG/L
CHROMIUM	< 5. MCG/L
COPPER	18. MCG/L
IRON	149. MCG/L
MANGANESE	127. MCG/L
NICKEL	< 5. MCG/L
STRONTIUM	1150. MCG/L
TITANIUM	< 5. MCG/L
VANADIUM	< 5. MCG/L
ZINC	664. MCG/L
MOLYBDENUM	< 20. MCG/L
ANTIMONY	< 80. MCG/L
TIN	< 50. MCG/L
THALLIUM	< 80. MCG/L
ALUMINUM	< 100. MCG/L
CALCIUM	38.2 MG/L
POTASSIUM	1.2 MG/L
MAGNESIUM	17.9 MG/L
SODIUM	45.2 MG/L

**** END OF REPORT ****

COPIES SENT TO: CO(3), RO(0), LPHE(1), FED(), INFO-P(), INFO-L()

RONALD TRAMONTANO, PE
BUR. ENVIRONMENTAL EXPOSURE INVESTIGAT.
NY STATE DEP'T. HEALTH
II UNIVERSITY PLACE
ALBANY, NY 12237 INTERAGENCY MAIL

SUBMITTED BY: KILMER