# NEW YORK STATE DEPARTMENT OF



# ENVIRONMENTAL CONSERVATION

Erin M. Crotty, Commissioner

General Electric
Fort Edward Outfall 004
Operable Unit 4
Inactive Hazardous Waste
Disposal Site

### Main Document Repository

Washington County Office
Building
Upper Broadway
Fort Edward, NY

### For More Information:

NYSDEC Central Office 625 Broadway, 12<sup>th</sup> Floor Albany, NY 12233-7013 Attn: Gerard Burke, P.E. Project Engineer (518) 402-9814

NYSDOH
Flanigan Square
547 River St
Troy, NY 12180-2216
Attn: Don Miles
(518) 402-7850
1-800-458-1158 ext 27850

Public Availability Session April 24, 2003 7:00 p.m.

Washington County Office Building -Rm B036
Upper Broadway, NYS Route 4
Village of Fort Edward

Remedial Construction Start
General Electric - Fort Edward
Site No. 5-58-004 - Operable Unit 4
Outfall 004
River Bank Excavation and Removal

The New York State Department of Environmental Conservation (DEC) is holding a Public Availability Session at 7:00 p.m. on April 24, 2003 in Room B036 at the Washington County Office Building to provide information on commencement of Remedial Construction activities for the General Electric Fort Edward Outfall 004 Inactive Hazardous Waste Disposal Site (Site Number 5-58-004), located along the banks of the Hudson River below Hudson Street, Fort Edward, Washington County, New York (see map). The New York State Department of Environmental Conservation and the New York State Department of Health (NYSDOH) are pleased to announce the beginning of the remedial construction activities.

### **Site History And Description**

GE's Fort Edward plant is located on a 32-acre tract along Route 4 in the Town of Fort Edward extending from the Hudson River to Upper Broadway, just south of the Washington County Office building complex. General Electric has manufactured capacitors at this location since the late 1940s. PCBs were used in capacitor manufacture until 1976. Other chemicals used on the site include solvents such as trichloroethane and kerosene.

GE has been conducting extensive on-site and off-site remedial investigation and monitoring activities. For management purposes the site has been divided into four parts called **operable units** as follows:

- -Operable Unit 1 (OU1) consists of off-site overburden contaminated groundwater. In accordance with a 1984 Order on Consent, GE established an off-site groundwater recovery system and conducts monitoring. This effort is complete and was successful. GE continues to provide operation and maintenance.
- Operable Unit 2 (OU2) consists of on-site contaminated soil and groundwater. The Remedial Investigation/Feasibility Study (RI/FS) conducted from 1984 to 1990

concluded that an expansion of the overburden groundwater recovery system was needed on-site; PCB oil recovery from the bedrock beneath the site was also needed and provided for through the use of two recovery wells with off-site disposal of recovered product. PCB-contaminated soils from the railroad off-loading area were also removed and properly disposed off-site.

- Operable Unit 3 (OU3) consists of the main portion of the site, including the contaminated groundwater and soil beneath the facility. The Record of Decision (ROD) for OU-3 stated that contaminated groundwater and product will be collected through a collection trench system, pretreated via separation and then treated at the facility's existing treatment plant to remove the VOCs and PCBs in groundwater above groundwater standards. This treatment includes an expanded PCB oil recovery system to address dense phase non-aqueous liquid under the employee parking lot. Treated groundwater is discharged to the Hudson River through the existing permitted outfall.
- Operable Unit 4 (OU4) consists of contaminated soil along the riverbank adjacent to the former 004 outfall on the east shore of the Hudson River. The ROD calls for the removal and off-site disposal of all PCB contaminated material from along the shoreline of the Hudson River in the vicinity of the former 004 outfall area.

OU-4 soil samples were collected from borings at selected locations and found to predominantly contain PCBs with some additional volatile and semivolatile organic compounds. The PCB contaminated soils were found on and along the banks of the River. Almost two hundred soil and sediment samples were collected from locations along and below the shoreline and below the surface of the Hudson River North and South of the former 004 discharge pipe. Soils immediately downstream from the former outfall contain very high concentrations of PCB; concentrations diminish with distance from the outfall. A considerable volume of contaminated soil exists in the river along the eastern shoreline. Surface water sampling results from upstream and downstream of the 004 outfall area indicate that the site is an ongoing source of PCB to the Hudson River.

# Remedial Construction Activity Summary

The Remedial Action at this site is consistent with what was outlined in the ROD. The DEC through its Contractor will excavate and dispose of an estimated 15,500 tons of contaminated soils from the river bank starting near the outfall and proceeding south approximately 1,200 feet. The Contractor will install a temporary coffer dam in the river to divert flow away from the river bank. The Contractor will install an access road down to the river beginning at the end of Hudson Street. The Contractor will also install a water treatment system to handle construction related water. The Contractor will conduct air monitoring for the protection of the downwind community from potential airborne contaminant releases associated with the remedial work activities. The Construction activities will occur from May 2003 through November 2003.

#### Citizen Participation Summary

As part of its responsibility to inform and involve the public, the DEC has, and continues to carry out, citizen participation measures at this site. These activities include: public meetings to describe RI/FS Work Plans; public meetings to describe the results of RI/FS work; and public meetings to present the proposed remedial action plans and receive public comments on the proposed plans. The last of the public meetings for this site was in March 1999 to present the remedy for Operable Units 3 and 4. This availability meeting is the latest step for keeping the public informed.

<u>Repositories:</u> Below are listed the places where the public can review relevant public documents regarding information about this site:

Washington Co. Office Bldg Upper Broadway Avenue Fort Edward, NY 12828 NYSDEC Central Office 625 Broadway, 12th Floor Albany, NY 12233-7013 Attn: Gerard Burke, P.E.

For More Information: Please contact the individuals identified on the cover sheet of this Notice.



