

# WehranEnviroTech

FINAL ENGINEERING DESIGN REPORT FOR THE CLOSURE ACTION OF THE BROOME COUNTY COLESVILLE LANDFILL REMEDIAL DESIGN

**Prepared for** 

BROOME COUNTY DIVISION OF SOLID WASTE MANAGEMENT Broome County, New York and GAF CORPORATION Wayne, New Jersey

Prepared by

WEHRAN-NEW YORK, INC. 666 East Main Street Middletown, New York 10940

WE Project No. 02260.CS

April 1994

Revised July 1994

It is a violation of Section 7209, Subdivision 2, of the New York State Education Law for any person unless acting under the direction of a licensed Professional Engineer or Land Surveyor to alter, in any way, Plans, Specifications, Plats or Report to which the seal of a Professional Engineer or Land Surveyor has been applied.

Quinda

Joseph J. Gurda

Yely 13, 1994

۰.

N.Y.P.E. License No. 51494

100

in a s

200

1.0		1-1
2.0	SITE INFORMATION	2-1
	2.1 LAND USE 2.2 TOPOGRAPHY AND SURFACE DRAINAGE PATTERNS	
3.0	WETLAND IMPACTS AND MITIGATION	3-1
4.0	LANDFILL DESIGN	4-1
	<ul> <li>4.1 GENERAL</li> <li>4.2 CONSTRUCTION LIMITS</li> <li>4.3 FINAL COVER DESIGN</li> </ul>	4-1
	<ul> <li>4.3.1 General</li> <li>4.3.2 Subgrade Preparation</li> <li>4.3.3 Gas Venting Layer</li> <li>4.3.4 Flexible Membrane Liner</li> <li>4.3.5 Barrier Protection Layer</li> <li>4.3.6 Topsoil</li> </ul>	4-2 4-2 4-4 4-4
	4.4 STRUCTURAL INTEGRITY OF THE LANDFILL	4-5
	4.4.1       Stability Analysis         4.4.2       Settlement Analysis	
	4.5 STORMWATER MANAGEMENT	4-7
	4.5.1General4.5.2Landfill Vegetation4.5.3Surface Drainage Controls	4-8
	4.6 ON-SITE SOIL BORROW EVALUATION	4-11
5.0		5-1
	5.1GENERAL5.2CONSTRUCTION PROCEDURES5.3DEVELOPMENT OF THE BORROW AREA5.4SCHEDULE	5-1 5-2

.

.0 PE		6-1
.0 QL	JALITY ASSURANCE AND QUALITY CONTROL PLAN	7-1
7.1		7-2
	7.1.1 Project Engineer	
7.2	2 QUALITY ASSURANCE AND QUALITY CONTROL PERSONNEL	7-4
	<ul> <li>7.2.1 Project Principal .</li> <li>7.2.2 Project Manager</li> <li>7.2.3 Construction Coordinator .</li> <li>7.2.4 Geotechnical Construction Observer</li> <li>7.2.5 Geosynthetic Construction Observer .</li> </ul>	7-5 7-6 7-7
7.3	QUALITY ASSURANCE AND QUALITY CONTROL LABORATORIES	7-10
	<ul> <li>7.3.1 Geotechnical Quality Assurance and Quality Control Laboratory</li> <li>7.3.2 Geosynthetic Quality Assurance and Quality Control Laboratory</li> </ul>	
7.4 7.5	PROTOCOLS	····· 7-11 ···· 7-12 ···· 7-13
.0 CC		8-1
8.1 8.2		
	<ul> <li>8.2.1 Emergency Coordinators and Chain-of-Command</li> <li>8.2.2 Duties and Responsibilities of the Emergency Coordinator</li> <li>8.2.3 Internal Communication/Warning System</li> <li>8.2.4 External Communication/Warning System</li> </ul>	8-2 8-5

.

10.006.4/94.02260.CS

-

100

400

		8.2.6   8.2.7   8.2.8 /	Evacuation Plan for Facility Personnel         Emergency Equipment         Medical Emergencies/First Aid         Available Emergency Services         ITIAL REMEDIAL ACTIONS DURING CLOSURE OPERATIONS	8-6 8-7 8-7
	8.3	PUTEN	THAL REMEDIAL ACTIONS DURING CLOSDRE OPERATIONS	0-7
		8.3.2   8.3.3   8.3.4   8.3.5   8.3.6	Fires	8-8 8-8 8-9 8-9 8-9
9.0	COS	ST EST	IMATES	9-1
	9.1 9.2	GENER CLOSU	RAL	
		9.2.1 9.2.2 9.2.3 9.2.4 9.2.5 9.2.6 9.2.7 9.2.8 9.2.9 9.2.10 9.2.11 9.2.12 9.2.13 9.2.14 9.2.15 9.2.16 9.2.17 9.2.18 9.2.19 9.2.20 9.2.21	Mobilization and General ConditionsSurveyClearing and GrubbingSoil Erosion and Sediment ControlSubgrade PreparationGas Venting LayerFlexible Membrane LinerDrainage LayerGeotextileBarrier Protection LayerTopsoilSeeding and MulchGrass-Lined Drainage ChannelsRip-Rap-Lined Drainage ChannelsGabion-Lined ChannelsStep DownchuteEnergy Dissipator PadsCulvertsSediment BasinWetland Mitigation	9-1 9-2 9-2 9-2 9-2 9-3 9-3 9-3 9-3 9-3 9-3 9-3 9-4 9-4 9-4 9-4 9-4 9-4 9-4 9-4

10.006.4/94.02260.CS

				age mber
	9.2.22 9.2.23	Perimeter Fence		
9.3	POST-C		• • •	<del>9</del> -5
	9.3.1 9.3.2 9.3.3 9.3.4 9.3.5 9.3.6 9.3.7	Final Cover/Vegetative Maintenance Fertilizing Mowing Drainage System Inspection and Repair Annual Survey Wetland Mitigation Inspection and Repair Inspection and Certification	· · · ·	9-6 9-6 9-6 9-6 9-6

## **APPENDICES**

Appendix A	_	Wetland Mitigation Plan
Appendix B	-	Stability and Settlement Analysis
Appendix C	-	Stormwater Drainage Design
Appendix D	-	Soil Analysis
Appendix E	-	Permit Application and Variance Application
Appendix F	-	Emergency Contact Listing
Appendix G	-	Gas Venting Layer Equivalency
Appendix H	-	VLDPE Chemical Resistance

10.006.4/94.02260.CS

-

# **1.0 INTRODUCTION**

·

## **1.0 INTRODUCTION**

This Final Engineering Design Report was developed in accordance with the September 1991 Design Statement of Work for the Broome County Colesville Landfill Remedial Design and is based on comments received from NYSDEC and USEPA on the Preliminary Design Report submitted August 1992, and Pre-Final Engineering Design Report submitted February 1993. This work has been performed by Wehran-New York, Inc. for the Broome County Division of Solid Waste Management (Broome County, New York), and GAF Corporation (Wayne, New Jersey).

The Colesville Landfill site is located in Broome County, New York (see Figure 1-1). It is a Superfund site that has been the subject of a Remedial Investigation/Feasibility Study performed by Wehran-New York, Inc. The remedy for this site includes the following major components:

- Landfill final cover
- Collection of contaminated groundwater in the glacial outwash aquifer downgradient of the landfill using wells outside of the landfill and within the landfill
- Seep collection
- Collected water (groundwater and seep) treatment
- Discharge of treated effluent to surface water

This Engineering Design Report addresses the general features of the Remedial Design and related design criteria of the final cover. The areas related to design of the final remedy of the Colesville Landfill site included in this report are:

- Final Cover
- Limit of Waste
- Borrow Areas
- Stormwater Management

The design of the pumping and treatment systems are described in separate documents titled, Engineering Design Report for Groundwater Treatment System, also prepared by Wehran-New York, Inc.

The Final Engineering Design Report should be reviewed in conjunction with the Post-Closure Operations and Maintenance Plan, Construction Plans, and Final Technical Specifications for the Colesville Landfill prepared by Wehran-New York, Inc., dated April 1994.

The Landfill Closure Design also incorporates site data and information from the Remedial Investigation Report, dated April 1988; and the Conceptual Design Report, dated June 1992, both prepared by Wehran-New York, Inc.

# 2.0 SITE INFORMATION

## 2.0 SITE INFORMATION

#### 2.1 LAND USE

The Colesville Landfill site is situated within an area characterized as rural, with large tracts of undeveloped woodlands. Developed lands include large-scale agricultural tracts and scattered residential parcels. The largest, and nearest grouping of residential development is found in Doraville, located approximately one-half mile south of the site.

### 2.2 TOPOGRAPHY AND SURFACE DRAINAGE PATTERNS

Surface elevations within the Colesville landfill site range from approximately 1,400 feet above mean sea level (msl) in the undeveloped eastern section, to about 970 feet above msl along the western site boundary. Elevations on the Susquehanna River lowland vary between approximately 940 feet msl to 970 feet msl. The Susquehanna River in the vicinity of the site is at an elevation of approximately 940 feet msl.

Site drainage is primarily westward toward the Susquehanna River. However, the terrace upon which the landfill has been developed is dissected by streams on the north, east, and south. Accordingly, a dendritic pattern of surface water runoff has been developed. Drainage to the south occurs by overland flow shortly after the streams enter the lowland.

## 3.0 WETLAND IMPACTS AND MITIGATION

## 3.0 WETLAND IMPACTS

Remedial construction activities, including capping and borrow operations, discharge of treated effluent, stormwater discharge, and groundwater withdrawal, will affect the wetlands on and around the Colesville Landfill.

The impact to affected wetlands and the wetland mitigation are included in the Colesville Landfill Wetland Mitigation Compensation Wetlands Plan, prepared by Wehran-New York, Inc. and Wetlands Research Associates, Inc., dated March 1994 (see Appendix A).

The Plan describes the proposed action and has been approved by USEPA.

4.0 LANDFILL DESIGN

in a

٣

## 4.0 LANDFILL DESIGN

#### 4.1 GENERAL

A final cover system is to be utilized in the remediation of the Colesville Landfill. The final cover system will incorporate gas venting, flexible membrane liner, barrier protection layer, topsoil, and stormwater controls.

The gas venting system will intercept, collect, and passively vent landfill gas to the atmosphere.

The flexible membrane liner, barrier protection layer, topsoil, and the stormwater controls will minimize the infiltration and percolation of stormwater through the waste. This will minimize the release of contaminants into the groundwater.

#### 4.2 CONSTRUCTION LIMITS

A determination of the limit of waste was performed based upon interpretation of aerial photographs for visible disturbance. To more accurately define the limit of waste placement, a test pit investigation was performed by Wehran-New York, Inc., between July 22 and July 24, 1992.

The extent of waste placement was verified by excavating test pits across the site. The test pits were performed under the supervision of Wehran-New York, Inc. field personnel. Approximately 100 test pits were excavated and those that represented the edge of waste are shown on Figure 4.2.1. For areas not represented by test pits, visual observation of waste and historical data was relied on to define the limit of waste placement.

Interpretation of the data collected during this investigation has moderately changed the boundary of the proposed final cover. The new boundary is shown on Sheet 2 of 9 of the Construction Plans.

#### 4.3 FINAL COVER DESIGN

#### 4.3.1 General

The goal of the final cover construction is to reduce leachate generation within the landfill. The final cover and associated stormwater management features will greatly reduce

the amount of water infiltrating; into the waste by providing an impermeable barrier in addition to reducing surface portding.

The final cover system proposed for this site is designed to fulfill the requirements of 6 NYCRR Part 360-2.13(p-s), effective December 31, 1988, revised May 28, 1991. The final cover system, from top to bottom includes a 6-inch topsoil layer, 24-inch barrier protection layer, 40 mil flexible membrane liner (FML), and a gas venting layer.

Two alternatives are presented in the Construction Plans for the barrier protection layer. Alternative 1 has a 12-inch drainage layer consisting of granular material, and a 12-inch soil layer of clean fill material with geotextile separating the two layers.

In Alternative 2, the 12-inch drainage layer has been replaced by a geosynthetic drainage layer. The geosynthetic drainage layer will be a geocomposite drain comprised of HDPE netting with geotextile bonded to each side. For this alternative, the barrier protection layer would be 24 inches thick and consist of fill material obtained from the on-site borrow.

The two final cover options are considered equivalent in function. Since the two alternatives are equivalent, the decision of which option to choose is basically economic. As such, the final cover alternative will be effectively determined by the option chosen by the successful low bidder for the project.

#### 4.3.2 Subgrade Preparation

The existing cover soils will require regrading to provide a smooth, uniform surface to facilitate placement of the low permeability barrier cover (FML) and to effect positive drainage. Fill will be required to eliminate existing depressions or to contour slopes, as necessary. Cutting into the existing soil will be limited as much as possible to eliminate the risk of exposing any in-place waste. Once a suitable surface is prepared, the remainder of the construction will proceed.

#### 4.3.3 Gas Venting Layer

The final cover system includes a gas venting layer beneath the FML barrier. The Colesville site has been dormant since 1984 and the average age of the in-place waste is estimated to be approximately 1/4 years old. As a result of the relatively long period since waste was deposited, gas generation at the site is expected to have diminished significantly.

Combustible gas migration surveys performed around the perimeter of the landfill indicate combustible gas is not currently migrating laterally from the landfill. As such, the 12-inch layer of granular gas venting material over the entire site is not necessary.

In recognition of the reduced amount of gas production at the site and the continued need for collection, various alternatives were investigated. The alternatives were evaluated on the basis of equivalency for the requirements found in 6 NYCRR Part 360, as well as for economical reasons.

Two alternatives for the gas venting (collection) layer have been proposed in place of the 12-inch soil layer required in 6 NYCRR Part 360. Since each alternate differs from the requirements of 6 NYCRR Part 360, a variance application is required (see Appendix E). The variance application discusses the equivalency of the alternates in relation to Part 360.

Alternate 1 consists of a geocomposite venting layer, a geonet with filter fabric bonded to both sides, and 6-inch slotted pipes trenched into the existing grade; Alternate 2 consists of 6-inch soil layer with 6-inch slotted pipes trenched into the existing grade. In order to determine the equivalency of the proposed alternatives to Part 360-2.13(p) requirements, equivalency calculations have been performed. Calculations are based upon the hydraulic transmissivity of each of the layers. The equivalency calculations performed are attached (see Appendix G).

The equivalency calculations for Alternate 1 shows the ability of the geocomposite layer to significantly exceed the capabilities of the required 12-inch soil layer in regard to transmissivity. The geocomposite in Alternate 1 is manufactured from polyethylene and resists degradation from chemical breakdown uniformly with the proposed 40 mil flexible membrane liner (FML). The geocomposite will be placed directly beneath the FML. As such, clogging of this layer is not anticipated. The liquid flow required as the mechanism for fines transport is away from this interface and not towards it. The relatively thick cross-section (fabric/net/fabric) of the geocomposite drain will perform as a cushion between the prepared landfill subgrade and the FML.

The equivalency calculations for Alternate 2 shows the 6-inch soil layer with increased minimum permeability requirements,  $2 \times 10^{-3}$  cm/sec, to be equivalent to the required 12-inch soil layer. The addition of collection pipes trenched within the layer will increase the layer's ability to control and collect gas. Due to the layer's similarity with the required soil venting layer, performance of the alternative in regard to chemical degradation,

performance under loading, and impact on FML placement will be consistent with the required soil venting layer.

For these reasons, the gas venting layer alternatives will provide equivalent performance to the required 12-inch gas venting layer.

Each of the alternates will also include the installation of passive vents, as shown in the Construction Plans. The passive vents will consist of 6-inch diameter Schedule 40 PVC pipe which is placed vertically into the refuse to a depth of 3 feet. The vertical pipe will be connected to the slotted corrugated polyethylene pipe within the trench. The passive vents will be fitted with a gooseneck cap and extend a minimum of 8 feet above final grade.

#### 4.3.4 Flexible Membrane Liner

The low permeability barrier cover for the landfill will be constructed of a flexible membrane liner (FML). The FML will consist of a 40 mil geomembrane in conformance with Part 360-2.13(r). The FML will be very low density polyethylene (VLDPE). This material is resistant to the constituents routinely found in the leachate and decomposition gases of municipal solic waste landfills.

#### 4.3.5 Barrier Protection Layer

The barrier protection layer will consist of 24 inches of soil material suitable to protect the integrity of the low permeability barrier cover. In addition, the barrier protection layer will remove excess head buildup by draining the cover soils, thereby enhancing the stability of the final cover system. Drainage from above the low permeability barrier cover will be achieved by two different means, depending on the final cover alternative selected.

Final Cover Alternative 1, incorporates a 12-inch drainage layer as the lower portion of the 24-inch barrier protection layer. This material will most likely be a sand with a transmissivity on the order of  $1 \ge 10^{-3}$  cm/sec.

The barrier protection layer for Alternative 2 includes a geosynthetic drainage layer overlain by 24 inches of soil. The geosynthetic drainage layer with a high in-plane transmissivity will be placed above the low permeability barrier cover.

Drainage pipes will be  $p_i$  acced near the low permeability barrier cover. These pipes will be placed incrementally across the slope and spaced approximately 50 feet apart. The

pipes will intercept water flowing through the drainage layer and discharge it to stormwater channels at the surface. The pipes will be slotted corrugated polyethylene pipe wrapped by a woven geotextile. The geotextile maintains filter separation between the protection layer soil and the pipe slots, reducing potential sedimentation and enhancing long-term performance.

The barrier protection layer will be capable of supporting root growth but has no specific requirements in terms of permeability or gradation. However, it must be free of material which will damage the geosynthetic components of the final cover system.

Details of the final cover alternatives are shown on the Construction Plans.

#### 4.3.6 Topsoil

The topsoil layer will be six inches thick and will be of the proper pH and nutrient content to sustain the growth of perennial grasses. The topsoil will be spread in a single lift and vegetation will be established. Landfill vegetation is described in detail in Section 4.5 this report.

#### 4.4 STRUCTURAL INTEGRITY OF THE LANDFILL

#### 4.4.1 Stability Analysis

A stability analysis was performed to assess the integrity of the final cover system. The analysis was performed on a typical cross-section through the the final cover on a maximum 33 percent slope. The interface between the barrier protection layer and the geomembrane is considered critical because of the lower interface friction angle.

The stability analysis was performed utilizing a  $\phi = 23.5$  degrees, C = 200 psf shear strength of the geotextile/textured membrane interface and  $\phi = 30$  degrees for the barrier protection layer soils. Given the use of drains in combination with a high "in plane" permeability geosynthetic, no accumulation of water over the membrane was included in the model. The resulting factor of safety is 1.7.

#### 4.4.2 Settlement Analysis

The proposed grading plan for the site utilizes slopes shallower than four percent as required by 6 NYCRR Part 360-2.13(r)(2)(ii). The proposed grading plan depicts a minimum slope of two percent in the western portion of the site. The proposed shallower slopes are utilized in order to preclude excavation of the in-place waste and minimize filling to achieve design grades. Excavation or relocation of waste at the site was deemed undesirable due to the nature of the materials deposited and prohibitive cost associated with waste relocation. Filling of the existing grades was limited in order to minimize the off-site impact of developing a borrow area.

Calculations were performed in order to assess the long-term effect of settlement on the proposed grades. The settlement of the waste was estimated at two stages – immediately after placing the final cover (short-term), and 30 years following the capping (long-term settlement of the waste). The immediate settlement is a combination of elastic and consolidation settlements due to weight of the equipment or fill soil which comprises the final cap. The long-term settlement occurs due to the decomposition of waste with time.

The settlements were computed using a computer program developed by Wehran. Parameters for the immediate and long-term settlement of waste were obtained from published values and Wehran's previous work on landfill settlement prediction.

The critical areas were identified in the western portion of the site in regard to settlement. The first location (Cross-section AA) represents the minimum proposed slope, the second location (Cross-section BB) represents the largest thickness of waste in the area of slopes shallower than those required. Settlement calculations for these two areas are included in Appendix B, along with figure drawings showing the orientation of the cross-sections.

As shown by the settlement calculations included with the cross-sections, the expected settlement is relatively minor. The values are 1.1 feet and 0.7 feet for short-term settlement and 1.0 feet and 1.9 feet for long-term settlement across Cross-sections AA and BB, respectively. The expected settlement for Cross-section AA will result in a grade effecting positive drainage. The calculations for Cross-section BB depict differential settlement developing over the existing waste trench in the southwestern portion of the site; however, due to the orientation of the slope, positive drainage will still be maintained. Therefore, due to the limited differential settlement predicted for the areas of slopes shallower than those required, overfilling at this time is not recommended. If localized depressions are identified by the long-term site inspection and maintenance program, regrading of the final cover soils in the localized areas will be performed.

Since the proposed grading over a portion of the site is less than 4 percent as required by NYSDEC Part 360 regulations, a variance application has been prepared and is included in Appendix E. Additionally, an annual survey will be performed to document the cap slope. If the annual survey identifies areas which have settled and are ponding water, the affected area will be prepared and regraded.

#### 4.5 STORMWATER MANAGEMENT

#### 4.5.1 General

Construction of the landfill final cover and development of the on-site soil borrow area will require the construction of surface water drainage controls to manage stormwater runoff and sediment transport.

Runoff from the site will be enhanced during construction as a result of the disturbance to cover soils and existing vegetation. To prevent uncontrolled runoff from leaving the site, a surface drainage control system is proposed. The surface drainage system will consist of drainage swales and a sediment basin.

The sediment basin receives the drainage from the eastern one-third of the landfill and from the entire borrow area. The basin traps sediment, and provides a controlled discharge of runoff into existing stream channels. The western two-thirds of the site is collected into drainage swales which discharge to an existing stream channel via a step (tumbling flow) downchute. The discharge from both drainage areas will provide discrete points for future monitoring of off-site stormwater discharge.

Design of the basin is in accordance with the New York Guidelines for Urban Erosion and Sediment Control, October 1991, Section 5A.33. Due to both topographic and available property limitations the sediment basin, in the location shown in the Construction Plans, can collect runoff from approximately 9 of the 28 acres within the area to be capped. The basin will collect all runoff from the borrow area. The more favorable location for the basin at the western end of the site is limited by available property and existing steep terrain. These constraints only allow the sediment basin to be located at the high (east) end of the site, limiting its tributary area.

In developing the borrow area, the existing surface drainage will be affected. Presently, there are two intermittent streams existing within the limits of the proposed borrow area. These streams will have to be redirected in order to allow for removal of the borrow material.

A third existing stream located between the capping and borrow area will be cordoned off during construction with silt fence to prevent silt from entering the water course. The stream will flow through a culvert along the western edge of the sediment basin and discharge into the existing stream bed.

The surface drainage system is principally required for the control of sediment during construction. Upon completion of construction and establishment of vegetation, sediment controls will not be required. The sediment basin will be retained after construction as a component of on-site wetland mitigation.

In addition to the sediment basin and drainage channel modifications, other sediment barriers will be implemented during construction. These barriers will include hay bales and/or silt fence, and will be used to limit sediment transport from the 21 acres of shallow sloped areas not draining to the sediment basin.

#### 4.5.2 Landfill Vegetation

The primary purposes for establishment of vegetation on the landfill final cover are to protect slopes from erosion, enhance evapotranspiration, and improve aesthetics. If efforts to establish vegetation needed for adequate erosion protection are successful, then the vegetation requirements for evapotranspiration and aesthetics are also satisfied.

Three general varieties of vegetation for erosion protection are as follows:

- 1. Temporary vegetation
- 2. Permanent vegetation
- 3. Drainage channel vegetation

Temporary vegetation is established with winter rye grass in topsoiled areas where permanent cover cannot be established until the following planting season. Temporary vegetation should be employed on all areas that will remain uncovered, with no ongoing activity in excess of 30 days to control runoff and prevent soil erosion. Permanent vegetation should be placed on all areas as soon as possible after they reach final grades. Permanent vegetation has been selected based upon localized specialization factors including slope steepness and orientation, the physical and chemical properties of the topsoil to ensure that the species of vegetation best suited for a particular environment may be established, and for aesthetic reasons.

Two suggested seed mixtures for vegetation of the proposed site are as follows:

Temporary Seedings			
Туре	Amount (Ibs/acre)		
Ryegrass (annual or perennial)	30		
Certified Arostock	100		
Winter Rye (use winter rye if seeding in October/November			
Permanent Seedings			
Туре	Amount (Ibs/acre)		
Empire Birdsfoot Trefoil <sup>1</sup> or Common White Clover <sup>1</sup>	8		
Tall Fescue	20		
Redtop or Ryegrass	5		
<ol> <li>Inoculate legume seeds immediately prior to seeding.</li> <li>Source: New York State Guidelines for Urban Erosion Control. October 1991.</li> </ol>			

Permanent vegetation should be planted between March 15 to May 15 or from August 15 to October 15.

Drainage channel vegetation protects the channel bottom and sides by increasing the roughness coefficients of the channel thereby reducing the flow velocity. Additionally, the root mat of the vegetation will hold the underlying soil in place. Vegetation planted in drainage channels is the same as species noted for permanent vegetation. Drainage channel vegetation should be placed in all drainage channels as soon as possible after final grading.

Seed will be hydraulically planted with mulch applied on steeper slopes. A binder will be applied with the mulch to hold it in place while seed is germinating.

#### 4.5.3 Surface Drainage Controls

The diversion swales, downchutes, stilling basins, perimeter channels, and culverts are designed to accommodate stormwater runoff from the 25-year, 24-hour, Type II storm as determined using methods from the Soil Conservation Service, Technical Release No. 55. The sediment basin and basin outlet channel are designed for the 10-year, 24-hour, Type II storm using methods from the same reference. The proposed surface drainage system will minimize leachate generation and soil erosion, and will control sediment transportation and peak runoff rates. The final landfill grades have been designed to provide diversion of overland runoff through swales and downchutes to minimize soil erosion.

#### **Diversion Swales**

Diversion swales have been designed to convey runoff to the downchutes, as shown in the Construction Plans. The diversion swales are grass-lined if the design flow is less than 3 fps.. If the design flow is between 3 fps and 4 fps, grass lining with an erosion control mat will be utilized. In reaches of the diversion channels with flow velocities in excess of 4 fps, rip-rap lining shall be utilized.

#### Culverts

Culverts are provided for routing stormwater under the access roads. The culvert inlets and outlets are protected with rip-rap or gabions, as shown in the Construction Plans.

#### **Downchutes**

Downchutes are trapezoidal in section and are rip-rap-lined, as shown in the Construction Plans. Downchutes convey runoff from the diversion swales down the sideslope of the landfill or borrow area. The downchutes will discharge into existing streams. Step gabions are used to dissipate energy, reduce the flow velocity, and limit the potential for scouring at the discharge points.

#### Sediment Basin

The sediment basin has been designed to accommodate sediment storage volume and detention storage during construction, and become a component of the required wetland mitigation after construction. The sediment storage volume has been designed in accordance with the New York Guidelines for Urban Erosion and Sediment Control. The combined principal/emergency spillway has been sized to pass the 100-year, 24-hour, Type II peak storm event and consists of a trapezoidal gabion-lined channel.

The spillway is designed as a trapezoidal gabion-lined channel. This supersedes the spillway referenced in the Wetland Mitigation Plan, which includes a spillway with an adjustable weir to modify the water level. If the water level within the basin requires adjustment, the spillway will be reconstructed to raise or lower the standing water elevation.

#### 4.6 ON-SITE SOIL BORROW EVALUATION

Planimetric calculations were performed to determine if an adequate volume of soil borrow materials exist on Broome County property adjacent to the landfill. In order to determine the amount of fill required for site regrading, the grading plan was prepared assuming the following requirements:

- No cutting of in-place materials
- Fill will be minimized
- Final slopes will vary between a minimum of 2 percent and a maximum of 33 percent.

The resultant grading plan shows filling to both smooth out irregularities in the landfill surface and to effect positive drainage without surface ponding.

For the purpose of performing an estimate of the quantity of soils required to be borrowed from on site, the assumption that no cutting will be performed within the limit of landfilling represents a conservative approach. The actual quantity required may be less if in-place soil material is moderately regraded. Based upon a comparison of the proposed grading plan to the existing topography, approximately 65,000 cy of material will be required to bring the site to grade.

Construction activity on site is expected to induce settlement of the surface topography. Additional fill will be required to offset any settlement. Settlement calculations were performed to estimate the effect of loading the in-place waste with the final cover system. Assuming fill is required in only the shallow portions of the site where settlement may affect drainage results in approximately 50,000 cy of material. These areas

4-11

would be principally those with slopes of less than four percent. The anticipated settlement within areas with surface slopes of four percent or greater is not expected to significantly affect drainage.

It is anticipated that settlement will occur differentially across the site with most areas requiring no fill while some areas will require concentrated filling. The geophysical investigation performed for the site identified the waste to be shallowest in the areas of existing shallow slopes, therefore significant settlement is no longer a concern. Subsequently, the amount of fill required to offset settlement effects is reduced.

The total quantity of sois required for subgrade fill are estimated to be 115,000 cy including 65,000 cy of fill for regrading and 50,000 cy of fill to offset settlement.

The other component of the final cover system which may be obtained from on-site borrow is the material for the barrier protection layer. The amount of material required will depend upon the actual final cover alternative chosen. For Alternative No. 1, 46,000 cy of material will be required, whereas 92,000 cy of material will be required to complete Alternative No. 2. It is anticipated that the on-site soils will require screening before being used as barrier protection material. It is also anticipated that, in the screening process, the useable fraction of borrowed soil will be reduced, possibly by as much as 50 percent. However, at least a portion of the screenings may be used as subgrade fill, particularly for the unfilled trench located in the south center portion of the site.

To summarize the volume needs, Alternative No. 1 requires 46,000 cy of barrier protective layer soil, 65,000 cy of subgrade fill and 50,000 cy of fill to offset settlement. Assuming all screenings can be used as subgrade fill, approximately 161,000 cy of soil need to be borrowed.

Alternative No. 2 requires 92,000 cy for barrier protection layer soil, 65,000 cy of subgrade fill and 50,000 cy of fill to offset settlement. Again, assuming all screenings may be used as subgrade fill, approximately 207,000 cy of soil need to be borrowed.

To determine the quantity of borrow material available, the logs of test pits located on the eastern portion of the property were reviewed. Test pits TP-1 through TP-8 consistently report 15 to 18 feet of glacial till extending down from the surface. This is considered acceptable soil for the cap's barrier protection soil and subgrade fill. The groundwater table was also examined and found to be an average of 25 feet below existing grade. A proposed grading plan for the borrow area was developed based upon the need to obtain 207,000 cy of material. Grading of the borrow area was held to maximum slopes of 3 horizontal to 1 vertical as shown on Sheet 4 of 11 on the Construction Plans. The assumption that slopes may be cut to 3 horizontal to 1 vertical based upon our observation of similar existing features proximate to the proposed borrow.

The borrow area is currently forested and will require clearing and grubbing in association with borrow area development. Topsoil will be stripped and stockpiled. Upon completion of the capping activities, the site will be reclaimed. Reclamation will entail grading of the site, replacement of topsoil, and revegetation.

As a result of the investigation, it appears the volume of soil available from on-site borrow is adequate for a portion of the site final cover needs, assuming capping to the limits shown. Table 4.4-1 indicates the soils required for final cover construction, the estimated quantity of each soil type, and whether the soil is available on site or would need to come from off site.

Material requirements for the various soil layers are discussed in the Technical Specifications.

# TABLE 4.4-1 COLESVILLE LANDFILL REMEDIAL DESIGN ENGINEERING DESIGN REPORT CAPPING MATERIAL REQUIREMENTS

Cap Component	Alt 1	Alt 2	Available On Site
Topsoil	23,000 cy	23,000 cy	0
Barrier Proection Soil	46,000 cy	92,000 cy	92,000 cy
Drainage Sand	46,000 cy	N/A	0
Geosynthetic Drainage	N/A	1,250,000 sf	0
40 mil FML	1,250,000 sf	1,250,000 sf	0
Gas Venting Soil Layer	N/A	23,000 cy	0
Gas Venting Geocomposite Drain Layer	1,250,000 sf	N/A	0
Fill for Site Regrading	65,000 cy	65,000 cy	65,000 cy
Fill to Offset Settlement	50,000 cy	50,000 cy	50,000 cy

10.006.4/94.02260.CS

# 5.0 LANDFILL CONSTRUCTION

.

## 5.0 LANDFILL CONSTRUCTION

#### 5.1 GENERAL

As a component of the closure design for the existing landfill, Construction Plans and detailed Technical Specifications have been prepared jointly with this report and submitted to the department for approval and issuance of a permit to construct.

The Construction Plans detail the closure of the site at the level of detail suitable for implementation of the approved design.

The materials and methods of construction are fully described in the Technical Specifications. The specifications present the acceptance criteria for all construction materials including all testing requirements for conformance to the established design parameters and testing frequency in accordance with the solid waste regulations. Acceptance criteria are based upon the certification requirements stated within the 6 NYCRR Part 360 for the individual components of construction.

The Quality Assurance and Quality Control (QA/QC) Plan provides procedures to assure and document that design and regulatory requirements are properly implemented during construction. The QA/QC Plan presents the management organization, personnel and laboratory requirements as well as requirements for documentation to demonstrate that construction of the landfill closure will be performed in accordance with the applicable regulatory requirements.

#### 5.2 CONSTRUCTION PROCEDURES

The components of the final cover design are described in Section 4.3. The construction will involve preparing the existing cover soil in preparation for final cover. A gas venting system, comprised of vents and collection piping, will be installed. The installation of 40 mil textured FML will then commence. FML panels will be deployed over the area and overlapped in the downslope direction a minimum of 4 inches.

Adjacent panels will be welded together either by an extrusion or hot-air welding device. The FML will be temporarily anchored down by the use of sandbags. Additionally, the FML edges, at the limit of the landfill cap, will be placed in a trench and anchored by soil. Drainage control features, including diversion swales, downchutes, culverts and a sediment basin, will be utilized t $\omega$  handle the stormwater runoff. Rip-rap, gabions, and filter fabric will be installed as shown in the drawings to the required depths. The materials used will conform to the specifications.

Pipe culverts will be installed as shown on the drawings, with the required bedding material. Pipe trenches will be carefully backfilled with clean granular material, and hand-tamped around the pipe to ensure it is compact and free of voids. Backfill will be placed in a maximum of 6-inch lifts to the top of the pipe, and 12-inch lifts thereafter. Backfill over the pipe will be clean compacted material, free of material over 8 inches in any dimension. Headwalls and inflow/outfall protection will be constructed as shown in the drawings.

Erosion protection will be installed as soon as possible after construction of the drainage structure. Any damage caused by delay will be rectified prior to placement of protection.

Fertilization and seeding will be in accordance with the specifications, and will be protected and maintained until a good vegetative stand is developed.

All drainage structures will be protected from the inflow of sediment during construction by use of hay bales, silt fences or diversion ditches, and will be left clean and clear of sediment following completion of construction.

#### 5.3 DEVELOPMENT OF THE BORROW AREA

As shown on the Construction Plans, a portion of the property directly east of the landfill is a proposed borrow area. As discussed in Section 4.6, closure of the landfill will require a significant quantity of soil. It is anticipated that a mined land use plan and a mining permit will be required.

Before excavation of maxerial, the proposed borrow area will need to be cleared. Topsoil stripping may then commence with the material being stockpiled on-site. The underlying layers will be excavated to the grades shown on the Construction Plans. The recovery of material will need to be staged along with the progress of closure construction such that the material amounts are provided in a continuous manner. The borrow area will be reclaimed and seeded in accordance with the provisions of the mined land use plan and the mining permit.

5-2


## 5.4 SCHEDULE

A schedule has been prepared for the implementation of the closure construction activities. Figure 5-1 shows the overall schedule for closure of the site while Figure 5-2 shows the anticipated schedule for completion of individual construction items.

Wohran Envirotech
â

j:\proj\02260-cs\ps-003-a.m/4

FIGURE 5-1 COLESVILLE LANDFILL REMEDIAL DESIGN CONTRACT NO. 1 PROJECT SCHEDULE



# FIGURE 5-2 COLESVILLE LANDFILL FINAL COVER

CONTRACT NO. 1 PROPOSED CONSTRUCTION SCHEDULE

Page 1 of 1

Task Description	Weeks	1 2	3	3 4	5	6	7	8	9 1	0 1	11 12	13 1	4 15 10	6 17	18	19 20	21 22	2 2	3 24	25 26	27 28	29 30
Moblization			•				<b>1</b>		<b>I</b>		_			;			I					
Prepare Submittals			•																			
Rec. Submittal Approval			_																			
Provide Survey			_				•										(·····			0		
Soil Erosion Control			-			•																•
Clearing and Grubbing																						
Sediment Basin Const.								•														
Subgrade Preparation					-		-		-													
Install Gas Venting Sys.																						
Install FML								_														
Install 12" Drainage Layer												_										
Install Type A Geotext.											-	_								•		
Install 12" Protect. Layer												1										
Install 6" of Topsoil																F						
Install Seed and Mulch																						
Const. Gravel Access Road																	-	_	-			
Const. Grass Lined Channels																						
Const. Rip-Rap Channels																						
Const. Step Downchute																	-	_	_			
Const. Energy Diss. Pads																				u		
Install RCP Culverts			-																			
Wetland Mitigation																						
Install Perimeter Fence																						



# 6.0 PERMITS AND EQUIVALENCIES

# 6.0 PERMIT EQUIVALENCY REQUIREMENTS

Table 6-1 shows the permit equivalency application status related to this Contract.

# TABLE 6-1 COLESVILLE LANDFILL REGULATORY PERMIT EQUIVALENCY REQUIREMENTS FOR REMEDIAL ACTIVITIES (Based on Final Design)

Agency	Regulatory Compliance Requirement/ Permit Compliance	Remediation Activity	Permit Equivalency Status
NYSDEC – Solid Waste	Facility Closure/Post-Closure Requirements	Closure Post-Closure	Engineering Design Plans, Specifications, Design Report, and O&M Plan will address this requirement
NYSDEC – Water Resources	State Pollutant Discharge Elimination System (SPDES) Permit Equivalencies	Stormwater runoff (Construction/Post-Closure)	The Notice of Intent to apply for this permit equivalency is under preparation
NYSDEC – Water Resources	Protection of Waters Permit Equivalency	Construction affecting protected stream	It is currently understood that this permit equivalency will be required due to the NYSDEC C(T) designation of the North Stream
NYSDEC – Water Resources	Water Quality Certificate Equivalency	Construction affecting protected stream/wetlands	Water Quality Certificate equivalency will be sought in conjunction with the Notification made to the ACOE regarding Nationwide Permit #38

Page 1 of 2

# TABLE 6-1 COLESVILLE LANDFILL REGULATORY PERMIT EQUIVALENCY REQUIREMENTS FOR REMEDIAL ACTIVITIES (Based on Final Design)

Agency	Regulatory Compliance Requirement/ Permit Compliance	Remediation Activity	Permit Equivalency Status
ACOE	Nationwide Permit #38 (Cleanup of Hazardous and Toxic Waste)	Construction affecting wetlands	A Notification Package is being prepared for the ACOE District Engineer which will consist of a brief fetter of notification identifying the project, appropriate drawings/plans (i.e., site plan, remedial design drawings, grading plan for borrow area), a copy of the wetland delineation and mitigation plans

# Notes:

3

1

s

• A determination was made by the NYSDEC that the permit equivalencies originally identified for the removal of borrow area soils would not be necessary.

E

1

1

10.006.4/94.02260.CS

L

7.0 QUALITY ASSURANCE AND QUALITY CONTROL PLAN

# 7.0 QUALITY ASSURANCE AND QUALITY CONTROL PLAN

The Quality Assurance and Quality Control (QA/QC) Plan for the Colesville Landfill addresses the requirements for construction of the landfill. The Plan has been prepared to meet the requirements of 6 NYCRR Part 360, Section 2.8, effective December 31, 1988, last revised May 28, 1991.

Quality Assurance and Quality Control have been defined in 6 NYCRR Part 360, as follows:

- Quality assurance means the application of standards and procedures to ensure that a product or facility meets or exceeds desired performance criteria and documentation to verify the results obtained. Quality assurance includes quality control, and refers to actions taken to assure conformity of the construction with the department-approved quality assurance plan, engineering plans, reports, and specifications.
- Quality control means those actions which provide a means to measure and regulate the characteristics of an item or service to contractual and regulatory requirements. Quality control includes those actions taken before construction to ensure that the materials chosen and workmanship comply with the department-approved quality control plan, engineering plans, reports, and specifications.

The purpose of the Quality Assurance/Quality Control Plan is to develop systematic procedures to assure and document that design and permit requirements are properly implemented during construction. The QA/QC Plan presents procedures that will be used during the construction of the following elements:

- Landfill final cover
- Landfill gas venting layer
- Groundwater collection system
- Borrow area
- Final cover stormwater control

- Sediment basin
- Access roads
- Culverts
- Maintenance facilities

The QA/QC Plan present: the management organization, personnel and laboratory requirements, testing protocols, and requirements for documentation and recordkeeping to demonstrate that construction of the landfill will be completed in conformance with 6 NYCRR, Part 360 Section 360-2.13 of the Solid Waste Management Facilities Regulations.

During construction of the Landfill, a number of quality control measures will be employed by the Construction Contractor and any subcontractors to provide self-monitoring of construction activities. These self-monitoring activities are not addressed in this Plan. The QA/QC Plan for construction of the Landfill addresses the procedures that will be employed by the Project Engineer and other parties independent of the Contractor and subcontractors to assure and document that the design and permit requirements are properly implemented. The Quality Control measures for the construction of the above-listed items will be outlined and described in the Technical Specifications for construction, submitted under separate cover.

QA/QC procedures related to environmental monitoring activities are outlined in the Environmental Monitoring Plan, submitted under separate cover.

# 7.1 MANAGEMENT ORGANIZATION

The Owner will retain a licensed professional engineering firm knowledgeable in landfill design and construction to serve as the Project Engineer for the construction. In accordance with Section 360-1.2 (b)(111) of 6 NYCRR Part 360, the Project Engineer shall be licensed to practice engineering in the State of New York and will be responsible for observing, documenting, and certifying that activities related to the quality assurance of the construction of the landfill and related facilities conform to approved construction plans and specifications, and conditions of the permit to construct.

Representatives of the Project Engineer will be responsible for implementing the requirements of the QA/QC  $P_{a}$  . The Project Engineer will also be responsible for supervising the activities of the QA/QC laboratories.

7-2

The Quality Assurance and Quality Control management organization to be used for construction at the Landfill is shown in Figure 7-1 and described below.

The party responsible for implementing the QA/QC Plan will be the Project Engineer.

### 7.1.1 Project Engineer

The Project Engineer will provide qualified personnel to serve in the following capacities:

- The **Project Principal** will serve as the official representative of the Project Engineer, and will have overall responsibility for the implementation of the QA/QC Plan.
- The **Project Manager** will report directly to the Project Principal, and will be responsible for overall coordination of construction and QA/QC activities with the Owner, the Contractor, any subcontractors, QA/QC Laboratories, and the other representatives of the Project Engineer.
- The **Construction Coordinator** will report directly to the Project Manager, and will be responsible for coordination of the activities of the Geotechnical and Geosynthetic Construction Observers, and the QA/QC laboratories.
- The **Geosynthetic and Geotechnical Construction Observers** will report to the Construction Coordinator, and will be responsible for observing, testing, and documenting construction activities on a daily basis.

The responsibilities of these personnel are described in further detail in Section 8.2.

### 7.1.2 Quality Assurance and Quality Control Laboratories

The services of Quality Assurance and Quality Control Laboratories will be secured by the Project Engineer to complete the testing requirements presented in the Technical Specifications. The QA/QC laboratories may be affiliated with the Project Engineer or subcontracted by the Project Engineer. If the services of the Geotechnical QA/QC laboratory are subcontracted, the laboratory must be independent of the Contractor, subcontractors, or material suppliers. If the services of the Geosynthetic QA/QC laboratory are subcontracted, the laboratory  $\pi_i$  ust be independent of the manufacturer, fabricator, or installer of geosynthetics at the site.

The Geotechnical QA/QC laboratory will complete the required geotechnical testing as directed by the Project Engineer.

The Geosynthetic QA/QC laboratory will complete the required geosynthetic testing as directed by the Project Engineer.

# 7.2 QUALITY ASSURANCIE AND QUALITY CONTROL PERSONNEL

The Project Engineer will have responsibility for implementation of the QA/QC Plan for construction at the Landfill. The qualifications and experience requirements and responsibilities of each representative of the Project Engineer, are presented below.

The project personnel will have construction-related responsibilities in addition to the QA/QC responsibilities listed below. Additional responsibilities, and qualifications and experience requirements have not been included for work activities to be performed in addition to the implementation  $\varphi$ f the QA/QC Plan.

# 7.2.1 Project Principal


## **Qualifications and Experience**


The Project Principal must be a Professional Engineer registered in New York State. The Project Principal must demonstrate past experience in a position of significant responsibility for landfill construction projects of similar magnitude and complexity to this landfill project and must be knowledgeable of the project requirements and objectives, and must be familiar with the Construction Plans and Technical Specifications.

## Responsibilities

The Project Principal will have the following responsibilities in the implementation of the QA/QC Plan:

- Serve as the official representative of the Project Engineer.
- Has ultimate responsibility for the implementation of the QA/QC Plan.
- Ensure that appropriate technical review is completed by qualified representatives of the Project Engineer for Construction Plans, Technical





,

Specifications, any modifications to the Plans and Specifications and the Construction Certification Report.

- Review and approve all design documentation, including the Construction Plans and Technical Specifications.
- Review and approve modifications to the Construction Plans and Technical Specifications during construction.
- Review and endorse the Construction Certification Report.

# 7.2.2 Project Manager

#### **Qualifications and Experience**

The Project Manager must be a registered Professional Engineer. The Project Manager must have extensive experience with construction projects of similar magnitude and complexity to this Landfill project. The Project Manager must have a thorough familiarity with the project, and be familiar with the Construction Plans and Technical Specifications.

#### Responsibilities

The Project Manager will have the following responsibilities in the implementation of the QA/QC Plan:

- Serve as the primary contact person for the Project Engineer. Maintain contact with the Owner, Contractor and subcontractors regarding conformance with the requirements of this Plan.
- Provide overall coordination of the activities of the Geotechnical and Geosynthetic Construction Observers and the Construction Coordinator.
- Provide assistance to the Construction Coordinator in the review and interpretation of field and QA/QC laboratory quality control testing results.
- Provide assistance to the Construction Coordinator in the review of shop drawings and other submittals from Contractors and subcontractors.
- Perform periodic site visits to review progress and QA/QC procedures.
- Determine acceptance of installed portion of work to permit further construction

- Ensure that the Construction Coordinator and Construction Observers are notified of any noted deficiencies in quality control testing results or procedures so that corrective actions can be taken.
- Review the Weekly Construction Summary Reports.
- Compile the Construction Certification Report with the Construction Coordinator, and the Geotechnical and Geosynthetic Construction Observers.

# 7.2.3 Construction Coordinator

## **Qualifications and Experience**

The Construction Coordinator must have a Bachelor of Science Degree in Engineering or an Associates Degree in Engineering Technology. The Construction Coordinator must have previous experience with landfill construction activities of similar magnitude and complexity to this Landfill project. The Construction Coordinator must have a thorough familiarity with the project, and have a thorough familiarity with the Construction Plans and Technical Specifications. The Construction Coordinator must also have a working knowledge of the quality control testing procedures included in the Technical Specifications.

#### **Responsibilities**

The Construction Coordinator will have the following responsibilities in the implementation of the QA/QC Plan:

- Serve as the daily contact person for the Project Engineer. Maintain routine contact with the Owner, Contractor, and subcontractors regarding conformance with quality control testing requirements.
- Coordinate the daily activities of the Geotechnical and Geosynthetic Construction Observer.
- Review all shop drawings and other submittals from the Contractors and subcontractors for conformance with the Technical Specifications.
- Review all field and QA/QC laboratory quality control testing results for conformance with the Technical Specifications and provide interpretation of data to determine areas to be reworked or repaired.

- Organize all field quality control testing data to facilitate preparation of weekly Construction Summary Reports, and the Construction Certification Report.
- Review all Daily Construction Reports prepared by the Construction Observers.
- Prepare the Weekly Construction Summary reports.
- Monitor delivery of appropriate samples to the QA/QC laboratory for quality control testing.
- Coordinate with Project Manager and Construction Observers to establish proper sampling procedures including proper sample location, sample size, sample collection protocol, and sample numbering system.
- Receive and organize all quality control testing results from the QA/QC laboratories and check for compliance with specifications. Notify Project Manager and Construction Observers of results and review test results with Project Manager to make determination of areas to be reworked or repaired.
- Perform routine site visits to review progress and QA/QC procedures.
- Notify Construction Observers, Contractors and subcontractors of acceptance of installed portion of work to permit further construction.
- Prepare Construction Certification Report

### 7.2.4 Geotechnical Construction Observer

#### **Qualifications and Experience**

Through a combination of formal education, training and experience, the Geotechnical Construction Observer must have a demonstrated knowledge of landfill construction including earthwork, installation of granular fills, aggregates, low permeability soil liners, and applicable testing methods. The Geotechnical Construction Observer must also have a demonstrated knowledge of installation of manholes, pumping and piping systems.

The Geotechnical Construction Observer must be familiar with and trained in the use of nuclear moisture-density meters.

#### **Responsibilities**

The Geotechnical Construction Observer will have the following responsibilities in the implementation of the QA/QC Plan:

- Visually observe construction materials such as soils and piping delivered to the site to determine general conformance with material specifications.
- Observe and record procedures used for site preparation clearing and grubbing.
- Observe and record<sub>i</sub>procedures used for excavation and filling of subgrade to required elevations.
- Observe and record procedures for placement of fill, groundwater collection system drainage soil, barrier protection soil and top soil, including:
  - Compacted life thickness
  - Method of moisture addition
  - Proofcolling
  - Fine grading
- Perform moisture and density testing, as established in the Technical Specifications.
- Assign locations and collect samples of other soils for quality control testing.
- Provide for delivery of samples to the QA/QC laboratory or the Construction Coordinator.
- Record any on-site activities that could result in damage to any earthwork or site improvements, such as compacted subgrade, and report these activities to the Contractor, Subcontractor and the Construction Coordinator.
- Prepare daily construction report as described in Section 7.5.

### 7.2.5 Geosynthetic Construction Observer

#### **Qualifications and Experience**

Through a combination of formal education and experience, the Geosynthetic Construction Observer must have a demonstrated knowledge of landfill construction including manufacturing, installation, and testing of geosynthetics.

#### **Responsibilities**

The Geosynthetic Construction Observer will have the following responsibilities in the implementation of the QA/QC Plan:

- Visually observe construction materials such as geomembranes, geotextiles, geonet, and geocomposite drain delivered to the site to determine general conformance with the material specifications.
- Observe and record condition of subgrade prior to placement of all geomembranes.
- Observe and record procedures for stockpiling, storage and handling.
- Observe and record procedures used for installation of geosynthetics.
- Visually observe all geosynthetics after installation for failure to comply with the Technical Specifications.
- Observe and record procedures used for installation of all liner penetrations.
- Conduct final inspection of membranes prior to drainage layer placement.
- Observe that panel placement is in accordance with the approved panel plan.
- Observe that permanent and temporary anchoring procedures are followed.
- Observe and record procedures used for seaming. Observe and record that the area of seam is clean, supported, and overlap and seam width are in accordance with the Technical Specifications.
- Observe and record that all required field seaming tests are performed. Observe and record that all areas with deficient seams are marked for repair.
- Observe and record procedures used for all repairs.
- Assign locations for collection of all samples for quality control testing.
- Observe and record procedures used to repair areas where samples are taken.
- Provide for delivery of samples to the QA/QC laboratory or the Construction Coordinator.
- Record any on-site activities that could result in damage to the various geosynthetics and report these activities to the Contractor, Subcontractor, and the Construction Coordinator.
- Prepare daily construction report.

# 7.3 QUALITY ASSURANCE AND QUALITY CONTROL LABORATORIES

# 7.3.1 Geotechnical Quality Assurance and Quality Control Laboratory Experience and Qualifications

The Geotechnical QA/QC Laboratory shall have experience in testing granular fills and aggregates, and shall be familiar with ASTM test standards and Army Corps of Engineers test procedures as required in the Technical Specifications. The Geotechnical QA/QC Laboratory shall be capable of providing permeability test results within 48 hours of receipt of sample. The laboratory shall be capable of providing all other test results within four days of receipt of samples.

The Geotechnical QA/QC laboratory must submit an acceptable QA/QC Plan to the Project Manager to demonstrate that the laboratory has the capability to complete the quality control testing required in the Technical Specifications.

#### **Responsibilities**

The Geotechnical Quality Assurance Laboratory is responsible for performing all tests and formally submitting results to the Project Engineer as required in the Technical Specifications.

# 7.3.2 Geosynthetic Quality Assurance and Quality Control Laboratory Experience and Qualitications

The Geosynthetic QA/QC Laboratory shall have experience in testing geosynthetics, and must conform with ASTN, NSF, GRI, and other applicable test standards. The Geosynthetic QA/QC Laboratory shall be capable of providing test results within 48 hours of receipt of samples.

The Geotechnical QA/QC laboratory must submit an acceptable QA/QC Plan to the Project Manager to demonstrate that the laboratory has the capability to complete the quality control testing required in the Technical Specifications.

#### Responsibilities

The Geosynthetic Quality Assurance Laboratory is responsible for performing all test procedures in accordance with the Technical Specifications and formally submitting results to the Project Engineer.

# 7.4 QUALITY ASSURANCE AND QUALITY CONTROL TESTING PROTOCOLS

The Quality Assurance and Quality Control Testing Protocols to be used during construction of this Landfill will be presented in the Technical Specifications. The Specifications will address the following elements of construction:

- Earthwork and related soil materials
- Geosynthetics
- Piping and appurtenances
- Mechanical equipment
- Electrical requirements

Where applicable, the Specifications describe the following testing requirements for each of the elements of construction:

- Field testing procedures to be used
- Field testing equipment to be used
- Frequency of field testing
- Sampling procedures to be used
- Sampling equipment to be used
- Frequency of sampling for laboratory testing
- Procedures to be used for laboratory testing
- Acceptable limits for field and laboratory testing

### 7.5 DOCUMENTATION AND RECORDKEEPING

Records of construction progress and quality control activities will be maintained throughout the construction at the Landfill. The following reports will be prepared by the Project Engineer retained to oversee these activities:

- Daily Construction Report
- Weekly Construction Summary Report
- Construction Certification Report

# 7.5.1 Daily Construction Report

Daily construction reports will be prepared by the Geotechnical Construction Observers and the Geosynthetic Construction Observers at the conclusion of every day construction activities occur at the site.

The daily construction reports will include the following:

- Date.
- Weather conditions, including daily high and low temperature, wind conditions, and precipitation, if any.
- General description of work activities at the site.
- List of personnel and equipment operating on site, number of hours worked, number of hours on standby, and work activities completed. Include names of key QA/QC and construction personnel.
- Description of work completed for the day, referencing stationing and grid coordinates.
- Identification of areas worked including lift number, panel number, and seam number.
- Drawings, sketches, and maps showing work completed.
- Summary of QA/QC procedures used for the day.
- Results of all quality control testing.
- Drawings, sketches, and maps showing all quality control testing areas. Passing and failing areas of the geomembrane panels and seams will be recorded.
- Reworked and repair areas will be recorded with all quality control testing results.
- Identification of all samples collected for quality control testing at the QA/QC laboratories, including sample number, location, and testing to be performed.
- Identify any in-field modifications.
- Documentation of discussions, decisions or recommendations involving the Contractor, Subcontractor, the Owner, NYSDEC, and representatives of the Project Engineer.

The Daily Construction Report will be submitted to the Construction Coordinator for review and inclusion in the project file.

# 7.5.2 Weekly Construction Summary Report

Weekly construction summary reports will be prepared by the Construction Coordinator at the end of every working week. The weekly reports will summarize construction progress and quality control testing based on the following:

- Daily construction reports for the work.
- Results from the geotechnical and geosynthetic QA/QC laboratories.
- Shop drawings and other submittals from the Contractor and subcontractors.

The weekly construction summary reports will include the following:

- General description of work activities completed at the site for the week.
- Specific description of work completed for the week, referencing stationing and grid coordinates.
- Identification of areas worked for the week, lift thickness, panel number, and seam number.
- Drawings, sketches, and maps showing work completed for the week.
- Summary of QA/QC procedures used for the week.
- Summary of quality control testing results for the week.
- Summary of reworked areas and repairs completed for the week.
- Summary of shop drawings and submittals received from the Contractor and subcontractors during the week, and disposition of same.
- Summary of results received from the geotechnical and geosynthetic QA/QC laboratories during the week.
- Summary of in-field modifications.
- Summary of decisions and recommendations as a result of discussions with the Contractor, subcontractors, the Owner, NYSDEC, and representatives of the Project Engineer.

The Weekly Construction Summary Report will be included in the project file.

# 7.5.3 Construction Certification Report

Upon completion of coustruction activities, the Project Engineer will prepare a construction certification report. The report will be prepared under the direction of, and endorsed by, the Project Principal.

The certification report will document construction in accordance with construction plans and specifications, with any exceptions noted. The certification report will include the following:

- Narrative description of the construction completed at the site.
- Description of deviations from construction plans and specifications and reasons for such cl<sub>i</sub>anges.
- Description of quality control testing procedures.
- Summary of quality control test data.
- Drawings showing quality control test locations.
- Descriptions of procedures used to rework or repair areas with failing quality control test results.
- As appropriate, raw data sheets and worksheets related to quality control testing.
- QA/QC Plans submitted to the Project Engineer by the Geotechnical and Geosynthetic QA/C/C laboratories.
- A series of color photographs of major project features.
- Record drawings of the completed construction.
- Certification statement of completion of construction in accordance with the Construction Plans and Technical Specifications.

# 8.0 CONTINGENCY PLAN

•

# 8.0 CONTINGENCY PLAN

# 8.1 GENERAL

The purpose of this Contingency Plan is to present an organized, planned, coordinated, as well as technically and financially feasible course of action to be taken in responding to contingencies during the closure of the landfill. This plan should be carried out whenever emergency situations develop which endanger human health and safety or the environment.

#### 8.2 PERSONNEL AND USER SAFETY

An emergency response program will be established for the Colesville Landfill to address safety in the event of the occurrence of emergency situations. The program will include:

- Identification of Emergency Coordinators
- Identification of Duties and Responsibilities of the Emergency Coordinator
- Identification of Communication Systems
- Development of Evacuation Plan
- Summary of First Aid Available for Selected Medical Emergencies
- Summary of Available Emergency Services

#### 8.2.1 Emergency Coordinators and Chain-of-Command

Prior to commencement of closure at the landfill, the Owner, Engineer, and Contractor will appoint emergency coordinators to direct an organized response to emergency situations. If an emergency situation occurs at the landfill, field personnel must contact the designated Emergency Coordinators.

At all times during hours of site construction, there will be at least one Emergency Coordinator on site or on call, with the authority to commit the necessary resources of to carry out the provisions of this Contingency Plan.

# 8.2.2 Duties and Responsibilities of the Emergency Coordinator Contingency Plan Implementation

The decision to implement the Contingency Plan at the landfill will depend upon whether or not a fire, explosion, or other emergency incident could potentially endanger human health and safety, or the environment. The following information provides the Emergency Coordinator with criteria to assist in making this decision.

The Contingency Plan should be implemented in the following situations:

## Fire or Explosion

- The fire spreads and could possibly ignite materials at other locations on site or could cause heau-induced explosions.
- The fire could possibly spread to off-site areas.
- Use of water and/or chemical fire suppressant could result in contaminated runoff.
- An imminent danger exists that an explosion could occur, causing a safety hazard.
- An imminent danger exists that an explosion could ignite other materials at the facility.
- An explosion has occurred.

## Material Release or Spill

- The material release spill could result in release of flammable, ignitable, or combustible liquids or vapors, thus causing fire or gas explosion hazard.
- The material release spill can be contained on site, but the potential exists for groundwater contamination.
- The material release spill cannot be contained on site, resulting in off-site soil contamination and "or ground or surface water pollution.

## Emergency Response Procedures

Whenever there is any type of incident at the landfill, the Emergency Coordinator must immediately notify field personnel, identify and assess the source and extent of the emergency, and take action to control the situation.

#### Notification

In the event of an imminent or actual emergency occurrence, the first person on the scene should notify the Emergency Coordinator, who, in turn will initiate a proper response to the situation in question. Notification of the Emergency Coordinator may be performed second only to notification of on-site personnel and/or site evacuation, depending on the emergency situation.

Having been apprised of the situation, the Emergency Coordinator will proceed to notify all facility personnel by initiating the internal communications system, (if not previously initiated), and aid in evacuation, if necessary. Progression of notification will continue to any local, State, and Federal response agencies deemed appropriate by the Emergency Coordinator.

A list of the Designated Emergency Coordinators will be posted in a conspicuous location at the site office. In addition, a list of the Emergency Response Agencies and Contacts is included in Appendix F and will be posted conspicuously at the same location.

#### Identification

Whenever there is a fire and/or explosion, spill or release, or other incident presenting a potential threat to the human health and safety or the environment, the Emergency Coordinator must immediately identify the source and extent of the emergency.

#### Assessment

In case of an emergency situation, an assessment of the possible hazard must be made. If the Emergency Coordinator determines that the facility has had a fire and/or explosion, spill or release, or other incident that presents a possible hazard to public health and safety, and/or the environment, and initiates the Contingency Plan, contact with local authorities must be made informing them of situations when an evacuation of the surrounding area is necessary. The New York State Department of Environmental Conservation (NYSDEC) should also be advised of all the pertinent facts regarding the incident.

When making a report to the NYSDEC, the following information must be provided:

- Name and telephone number of person making the report
- Name of the facility
- Type and time of incident occurrence
- Name and quantity of material(s) involved, to the extent known

- Extent of any injur.es
- Possible hazards to public health and safety, and/or the environment surrounding the facility

## **Control Procedures**

The nature of work carnied out during landfill closure makes the occurrence of emergency situations a possibility, no matter how infrequently they may actually happen. Emergencies can happen quickly and unexpectedly, requiring immediate response.

In the event of any emergency situation, the Emergency Coordinator must take all reasonable measures to prevent the occurrence, recurrence, or spread of a fire or explosion or unplanned releases to other portions of the facility.

A broad-based emergency response network will be established to respond to any incidents at the facility. If an emergency occurs, fully trained response personnel should be contacted as soon as possible.

Requests for assistance should always include:

- Name, address, and telephone number of the facility
- Type and time of incident occurrence
- Extent of any injur.es
- Possible hazard to public health and safety, and/or the environment surrounding the facility
- Type and quantities of materials involved, if known

Immediate action by ou-site personnel should concentrate on preventing any fire/explosion, or spill/leak situation that occurs from spreading to other areas of the facility, and immediate emergency medical attention should be given to injured personnel, if possible. Any possible sources of ignition should be removed from the incident area, if this can be done without risk, and vehicular traffic should be suspended and work ceased until the fire or inciden; can be safely contained or controlled.

#### Storage and Disposal of Released Materials

Immediately after an emergency situation, the Emergency Coordinator must make arrangements for the storage, or disposal of any recovered wastes, water, or any contaminated materials resulting from the incident.

#### Post-Emergency Equipment Maintenance

Following an emergency incident, all emergency response equipment used must be cleaned and made fit for reuse, or replaced as necessary, so that the equipment will be available when construction operations resume. An inspection of all equipment must take place before operations resume to ensure that each item is in proper working condition. Remedial activities as a result of this inspection may include recharging of fire extinguishers, restocking first aid kits, replacement of personal protective gear, and restocking of disposable items.

# 8.2.3 Internal Communication/Warning System

An internal communication system consisting of telephones and two-way radios will be available at the landfill for notifying field personnel in the event of an emergency episode. Units are located in readily accessible areas at the site office, in vehicles, and in the equipment. In addition, units may be carried by field personnel. This system provides facility personnel with immediate emergency notification and necessary instructions in the event of an incident.

#### 8.2.4 External Communication/Warning System

A network of emergency response agencies are available and field personnel that can be contacted in the event of an incident at the landfill. Designated Emergency Coordinators and Emergency Response Agencies and Contacts will be notified by telephone for assistance in an emergency.

Lists including these names and telephone numbers will be displayed prominently at site office for easy employee accessibility in the event of an emergency.

#### 8.2.5 Evacuation Plan for Facility Personnel

In an emergency situation, and when time permits, the Emergency Coordinator will be the individual responsible for determining when evacuation of the facility is required. Imminent or actual dangers that constitute a situation requiring evacuation include:

- A generalized fire or threat of generalized fire that cannot be avoided.
- An explosion or the threat of explosion that cannot be averted.
- A major spill or leak that cannot be contained and constitutes a threat to human health.

When time permits and evacuation is required, the following procedures should be followed:

- Alert all field personnel and support personnel using the telephone and/or two-way radio system.
- Alert and request assistance from local emergency response agencies.
- Shut down all facility equipment.
- All field personnel should proceed to a designated meeting point. Once assembled at this designated meeting point, a determination and identification of any missing persons should be made. In the event that any personnel cannot be accounted for, assembled personnel should not reenter the facility. Instead, all personnel should await the arrival of local emergency response agencies and standby to afford assistance, if and as needed.

# 8.2.6 Emergency Equipment

Various emergency equipynent is available at the landfill facility as described below.

#### Firefighting Equipment

The landfill facility will maintain several types of equipment on site that may be used in firefighting efforts. Earth-moving equipment that is utilized on a regular basis for landfill closure may be used to move and apply material for fire control. A tank truck will be available for use in controlling fires.

The facility will also maintain a supply of fire extinguishers that may be used in the event of an emergency incident. These extinguishers will be located at strategic points at the site. Fire extinguishers will also be located on the construction equipment for use in cases of field emergencies. Extinguishers will be maintained in conformance with State and local fire codes and regulations.

#### First Aid/Safety Equipment

First aid and safety equipment will also be located in strategic locations on the site, and some items may be kept in construction equipment. First aid kits will be located in the landfill site office and will contain a full range of items necessary to care for minor injuries needing prompt attention. First aid kits will be easily and immediately accessible to personnel.

8-6

#### 8.2.7 Medical Emergencies/First Aid

In cases of medical emergency, trained medical response personnel should be contacted immediately. First aid administered by on-site facility personnel should continue until professional assistance arrives.

First aid is the immediate care of a person who has been injured or has suddenly taken ill. It is intended to prevent death or further illness and injury, and to relieve pain until additional, professional medical aid can be obtained. The objectives of first-aid are:

- To control conditions that might endanger life.
- To prevent further injury.
- To relieve pain, prevent contamination, and treat for shock.
- To make the patient as comfortable as possible.

The initial responsibility for first-aid rests with the first person at the scene who must react quickly, but in a calm and reassuring manner. The person assuming responsibility should immediately summon medical assistance, being as explicit as possible in reporting suspected types of injury or illness. The injured person should not be moved, except where necessary, to prevent further injury.

#### 8.2.8 Available Emergency Services

In the event of an emergency at the landfill, the agencies listed in Appendix F – Emergency Contact Listing, are available.

# 8.3 POTENTIAL REMEDIAL ACTIONS DURING CLOSURE OPERATIONS

Conditions may be encountered at the site during normal landfilling activities that will require response actions that are not included as part of typical daily site operations.

#### 8.3.1 Fires

The possibility of a fire, whether in the landfilled waste or within a piece of equipment, is a potential hazard associated with the closure operation of the landfill.

The earth-moving equipment to be used in the closure activity will be capable of moving and applying the amount of material needed.

Water can be used to supplement the use of cover soil or serve as an alternative means of controlling fires. The Contractor will have a water truck available for use during emergency situations. Water can be obtained from the sediment basin or on-site water supply. For larger or more serious outbreaks, the local fire department would be contacted. Additionally, portable fire extinguishers will be kept in all vehicles and buildings as a precautionary measure.

The contingency program's described below should be followed when encountering a ground fire and below cover fire:

- The application of cover soil by landfill earth-moving equipment, or the application of water by the on-site water tank truck to extinguish the blaze, can be carried out.
- Any vehicles and any equipment in the fire zone should be sprayed with water, while working to quench the fire.
- Precaution should be taken throughout the entire firefighting operation.
- If, at any time, additional assistance is required, local firefighting units should be contacted as soon as possible.

## 8.3.2 Landfill Gas

Decomposition of organ c waste is generally accompanied by the production of landfill gas. Landfill gas produced at municipal solid waste disposal sites is generally composed of approximately 50 percent methane and 50 percent carbon dioxide and when mixed with oxygen at the proper proportion and exposed to an ignition source can present a fire and/or explosion hazard. Recognizing the potential explosive hazard, a plan will be developed to identify the source extent of impact, and outline remedial actions to protect landfill personnel and the environment. In the event of combustible gas detection in any enclosed structures, the structure will be immediately evacuated, the emergency coordinator notified, and a plan developed to identify the source of the combustible gas, and outline remedial actions.

#### 8.3.3 Dust Control

During dry periods, fugitive dust may be a nuisance resulting from the landfill closure operation. The access roads and working areas of the site are generally removed from residential areas. Under these conditions, dust problems are typically localized and can generally be managed with on-site equipment. The following measures may be employed wherever a potential problem exists:

- Applying water on haul roads.
- Wetting equipment and excavation faces.
- Spraying water on buckets during excavation and dumping.
- Hauling materials in properly tarped or watertight containers.
- Restricting vehicle speeds to 10 mph.
- Covering excavated areas and material after excavation activity ceases.
- Reducing the excavation size and/or number of excavations.

# 8.3.4 Litter Control

The tasks of excavation for the gas collection trenches or cover regrading may expose the waste to wind and potentially produce litter. Every practicable measure will be taken to contain litter as close to the working area as possible. Activities which have the potential to expose waste will be restricted to as small an area as possible. The Contractor's employees will manually pick up litter as required. If activities begin to distrub waste, the work will be evaluated and modified, if possible, to avoid further waste disturbance.

# 8.3.5 Odor Control

Odors from closed landfills generally result from the generation of landfill gas and upon exposure of waste. Due to the limited quantity and age of the waste, the amount of landfill gas expected to be generated is minimal. If odors become an off-site problem, the source must be determined and proper mitigative actions taken. The following contingency steps can be taken:

- Application of additional cover soils
- Use of odor masking agents
- Modification of landfill gas control system

Waste disturbance is anticipated only during gas vent installation. Therefore, any odor associated with this activity will be of limited and controlled time duration.

# 8.3.6 Noise Control

The major source of noise in the area of the landfill during closure will be the construction equipment. Since the construction will occur during daylight hours and will be generally removed from local residences, the noise generated from landfill operations are

not expected to be an off-site problem. All landfill equipment working at the site will have muffler systems to further diminish any potential nuisance from noise.

If noise conditions present a problem, mufflers on all landfill vehicles should be inspected and replaced if inadequate. If unsatisfactory conditions persist and noise levels are detected in violation of the effective solid waste management or local regulations, operational procedures will be modified or appropriate noise barriers should be constructed.

#### 8.3.7 Vector Control

As in the case of litter control, the amount of waste exposed during any time will be kept to the smallest area practical. Prompt covering of the waste should eliminate problems with insect, bird, and animal pests. Vectors are greatly discouraged when waste materials are not easily available.

If vector control presents a problem at the site, waste exposure will be more closely controlled and monitored. However, if a problem persists with vectors such as insects or rodents, an extermination program can be initiated. This program would be in strict accordance with requirements of the New York State Departments of Health and Environmental Conservation.

# 9.0 COST ESTIMATES

# 9.0 COST ESTIMATES

# 9.1 GENERAL

Closure and post-closure estimates have been prepared to reflect the anticipated cost of closure and post-closure monitoring and maintenance for the final cover action of the Colesville Landfill Remedial Design. The closure cost estimate has been prepared based upon the construction items necessary for closure as detailed in the Construction Plans, prepared by Wehran-New York, Inc., dated April 1994. The post-closure cost estimate is based on maintenance schedules obtained from other landfill projects.

All costs are presented in 1993 dollars without adjustment for cost escalation with time. Where possible, unit prices for materials have been obtained from quotes received from suppliers or material manufacturers. Where actual costs were not readily available, costs from cost estimating guides were used. These costs are based upon the best information available at the present time. These estimates are subject to change based upon market conditions at the actual time of closure construction and post-closure activity.

# 9.2 CLOSURE COST ESTIMATE

A description of the closure construction items that are addressed in this report are presented below.

# 9.2.1 Mobilization and General Conditions

This cost has been estimated as 10 percent of the total project cost and includes Contractor mobilization, site facilities, insurance, bonds and other administrative costs.

#### 9.2.2 Survey

The survey cost reflects the cost for survey work required for layout of the work and survey-associated payment requests, and layer thickness determinations.

#### 9.2.3 Clearing and Grubbing

The cost for clearing and grubbing reflects the cost for clearing the on-site areas of woody vegetation in preparation for soil borrow and final cover construction.

#### 9.2.4 Soil Erosion and Sediment Control

The cost for soil erosion and sediment control includes the installation of hay bales and silt fence, construction of temporary sediment impoundments and flexible pipe downslope drain, as well as other temporary soil erosion and sediment control measures throughout construction.

#### 9.2.5 Subgrade Preparation

The cost for subgrade preparation includes regrading of the existing landfill cover to provide a surface suitable for placement of the final cover materials and to achieve the grades depicted on the Construction Plans once all appropriate layers are placed. Fill for subgrade preparation is assumed to come from the on-site borrow area.

#### 9.2.6 Gas Venting Layer

The gas venting layer will consist of either 6 inches of drainage sand or a geocomposite layer. Both a ternatives include 18-inch deep collection trenches. Additionally, crushed recycled glass may be substituted for the subangular stone within the collection trenches. The estimated cost for this layer includes cost for material purchased from an off-site source and placement,

Gas vent risers will be cor<sub>i</sub>structed at a frequency of one vent riser per area as shown in the Plans. The vents will extend above the final cover a minimum of 6 feet, and in the waste a minimum of 3 feet.

#### 9.2.7 Flexible Membrane Liner

A 40 mil VLDPE flexible membrane liner (FML) will be installed as a low permeability barrier layer over an area of approximately 28 acres. The estimated cost for this item includes material and installation costs for both the smooth and textured FML components.

#### 9.2.8 Drainage Layer

The drainage layer will consist of a minimum of 12 inches of drainage sand over the geomembrane layer. Alternately, a geocomposite may be substituted for the sand drainage layer. The 12-inch sand drainage layer is assumed to be more expensive and therefore more

9-2

conservative from the perspective of cost. The estimated cost for this layer includes cost for material purchased from an off-site source and placement.

4-Inch diameter slotted corrugated polyethylene pipe wrapped in geotextile will be placed within the drainage layer across the slope, and spaced approximately every 50 feet across the slope, with drain pipe outlets spaced every 50 feet apart. The pipes will intercept water in the drainage layer and discharge it to stormwater channels at the surface. The estimated cost for this item includes material and installation costs.

### 9.2.9 Geotextile

Geotextile Type A, may be included if the drainage sand the barrier protection layer do not demonstrate filter compatibility.

### 9.2.10 Barrier Protection Layer

A 12-inch soil layer, along with the 12-inch drainage layer, completes the requirement for the 24-inch protective barrier protection layer required by Part 360. (Alternately, if a geocomposite drain is substituted for the soil drainage layer, then the barrier protection layer will be 24 inches thick.) Cost for placement of a 12-inch soil layer to accompany the 12-inch sand drainage layer includes placement and purchase of material from an off-site source.

### 9.2.11 Topsoil

Soil suitable to sustain vegetation (i.e., topsoil) will be placed in a 6-inch lift and will cover approximately 28 acres. Material is assumed to be required from off-site.

### 9.2.12 Seeding and Mulch

Cost includes seeding and mulching of the 28 acres of soil suitable to sustain vegetation as well as other disturbed areas.

## 9.2.13 Gravel Access Road

This item represents the cost to build the gravel access road on-site to provide access for post-closure maintenance and monitoring activities.

## 9.2.14 Grass-Lined Drainage Channels

Construction of the diversion swales includes placement of a soil berm lined with geomembrane, filter fabric, and a seeded topsoil layer. The quantity of 4,270 linear feet for this item includes diversion swales as shown in the Construction Plans. The topsoil and seeding costs are not included under this item but are included elsewhere in the Closure Construction Cost Estimate.

## 9.2.15 Rip-Rap-Lined Drainage Channels

The cost for rip-rap-line( drainage channels includes all earthwork to form the channels and the placement of grotextile and rip-rap, as shown on the Plans.

#### 9.2.16 Gabion-Lined Channels

This item includes the cost for earthwork to form the channels, gabion basket assembly and placement, and stone filling.

## 9.2.17 Step Downchute

The cost for downchute construction includes the placement of a geomembrane lining, filter fabric, concrete elements, and rip-rap stone. The quantity for this item includes the step downchute to the North Creek, as shown on the Construction Plans.

### 9.2.18 Energy Dissipator Pads

The cost for this item includes all earthwork, gabion basket assembly and placement, and stone filling.

## 9.2.19 Culverts

Pipe culverts will be installed to allow access to the borrow area and the treatment plant. The estimated cost for these items include trench excavation, supply, and installation of the pipe as well as backfill.

### 9.2.20 Sediment Basin

The cost for this item includes the earthwork required to excavate, and build the basin embankment and basin spillway.

## 9.2.21 Wetland Mitigation

This item includes the preparation of the wetland mitigation portion of borrow area, including placement of low permeability soil liner in the sediment basin, spreading of topsoil outside of the basin, and planting of wetland vegetation.

## 9.2.22 Perimeter Fence

The cost for this item includes construction of perimeter fence and gates around the final covered areas, as shown on the Plans.

## 9.2.23 Inspection and Certification

During construction, an engineering firm will be employed to observe construction and document compliance with the approved Construction Plans and NYSDEC regulations. Upon completion of the closure construction, an engineering certification report will be prepared describing the landfill closure construction. The report will be submitted to NYSDEC. The estimated cost for this item assumes that all closure construction will be completed in one nine-month construction season. This item includes the cost for required on-site construction observation, daily record keeping, and appropriate geosynthetic and geotechnical testing.

## 9.3 POST-CLOSURE COST ESTIMATE

Post-closure activities at the site will include routine inspection and maintenance, as well as remedial activities. Anticipated post-closure activities that will be conducted during the 30-year post-closure period are summarized in the following sections.

### 9.3.1 Final Cover/Vegetative Maintenance

Regular inspections will be conducted to determine the need to repair the final cover and vegetation. Repairs will be conducted, as necessary to ensure the integrity of the landfill cover. Based on observations of similar landfill sites, it is estimated that approximately 1/8 of the final cover will require maintenance over the closure period. It is estimated that 3 percent will be repaired the first year, 2 percent the second through fourth years, 1 percent for the fifth year, and ½ percent for the sixth through the tenth year of the post-closure period.

## 9.3.2 Fertilizing

During the initial 10 years of vegetation establishment, fertilizer will be applied annually.

### 9.3.3 Mowing

Mowing of vegetation, approximately two times per year, will be completed to prevent the establishment of deep-rooted vegetation.

### 9.3.4 Drainage System Inspection and Repair

The surface water system composed of diversion swales, access road swale, downchutes and energy dissipators, will be inspected on a regular basis. Repair, including cleaning, revegetation and regading, will be conducted as necessary. Based upon observations of similar projects, it is assumed that maintenance will be equivalent to the replacement of approximately 1/3 of the drainage system. The repair schedule is similar to the schedule for final cover maintenance.

### 9.3.5 Annual Survey

An annual survey will be performed to verify the final cover slope, and identify any areas of differential settlement or ponding. The annual survey will assist in the determination of which areas of final cover will require repair.

### 9.3.6 Wetland Mitigation Inspection and Repair

The wetland mitigation area will be inspected semi-annually (spring and fall) for the first two years, starting from the completion of the first planting, to assess the effectiveness of the wetland mitigation. Vegetation will be replanted and sediment basin water elevation will be adjusted as necessary, to comply with the Wetland Mitigation Plan.

### 9.3.7 Inspection and Certification

Engineering inspections and certifications will be completed and summarized in engineering reports that will be prepared by a professional engineer registered in New York. It is estimated that the reports will be prepared annually for the first 5 years, and then the equivalent of once every other year for the remainder of the 30-year closure period.

		Approxim Quantitie	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	ESTIM	ATED COST
ltem		quainne		UNIT	<u></u>
No.	Item	Quantity	Unit	PRICE	COST
1	Mobilization and General Conditions	1	LS	500,000.00	500,000.00
2	Survey	1	LS	100,000.00	100,000.00
3	Clearing and Grubbing				
	a. First 13 Ac	13	Ac	2,500.00	32,500.00
	b. Over 13 Ac	2	Ac	2,500.00	5,000.00
4	Soil Erosion and Sediment Control	1	LS	20,000.00	20,000.00
5	Subgrade Preparation, Fill Soils,				
•	and Fine Grading				
	a. First 158,000 SY	158,000	SY	2.20	347,600.00
	b. Over 158,000 SY	16,000	SY	2.20	35,200.00
6.1	Alternate 1 Gas Venting Layer (6 inches Sand)				
	a. First 139,000 SY	139,000	SY	3.50	486,500.00
	b. Over 139,000 SY	14,000	SY	3.50	49,000.00
6.2	Alternate 2 Gas Venting Layer				
	(Geocomposite Drain)				
	a. First 1,250,000 SF	1,250,000	SF	0.70	875,000.00
	b. Over 1,250,000 SF	125,000	SF	0.70	87,500.00
7	Slotted Corrugated Polyethylene Gas Pipe,				
	Subangular Stone, Geotextile Type B, and				
	Gas Vents	1	LS	45,000.00	45,000.00
8	40 mil Flexible Membrane Liner				
-	a. First 1,250,000 SF	1,250,000	SF	0.46	575,000.00
	b. Over 1,250,000 SF	125,000	SF	0.46	57,500.00

		Approxim Quantities	(a) 1.5 day	FSTIM	ATED COST
ltem		Quantitie		UNIT	<u> </u>
No.	Item	Quantity	Unit		COST
9.1	Alternate 1 Drainage Layer (12 inches Sand)				
	a. First 139,000 SY	139,000	SY	7.50	1,042,500.00
	b. Over 139,000 SY	14,000	SY	7.50	105,000.00
9.2	Alternate 2 Drainage Laye				
	(Geocomposite Drain)				
	a. First 1,250,000 SF	1,250,000	SF	0.70	875,000.00
	b. Over 1,250,000 SF	125,000	SF	0.70	87,500.00
10.1	Alternate 1 Geotextile Type A				
	a. First 1,250,000 SF	1,250,000	SF	0.10	125,000.00
	b. Over 1,250,000 SF	125,000	SF	0.10	12,500.00
11.1	Alternate 1 Barrier Protective Layer 12 inches)				
	a. First 139,000 SY	139,000	SY	1.30	180,700.00
	b. Over 139,000 SY	14,000	SY	1.30	18,200.00
11.2	Alternate 2 Barrier Protective Layer (24 inches)				
	a. First 139,000 SY	139,000	SY	2.60	361,400.00
	b. Over 139,000 SY	14,000	SY	2.60	36,400.00
12	Topsoil (6 inches)				
	a. First 139,000 SY	139,000	SY	3.40	472,600.00
	b. Over 139,000 SY	14,000	SY	3.40	47,600.00
13	Seeding and Mulch				
	a. First 42 AC	42	AC	3,200.00	134,400.00
	b. Over 42 AC	5	AC	3,200.00	14,400.00

04/20/94 📟

			Approxim Quantities		FSTIM	ATED COST
Item					UNIT	
No.		ltem states and states	Quantity	Unit	PRICE	COST
14	Gravel Acces	s Road				
	a. First	4,300 LF	4300	LF	19.00	81,700.00
	b. Over	4,300 LF	430	LF	19.00	8,170.00
15	Grass-Lined	Drainage Channel				. <u> </u>
1	a. First	4,300 LF	4,300	LF	14.50	62,350.00
	b. Over	4,300 LF	430	LF	14.50	6,235.00
16	Rip-Rap Line	d Drainage Channel				
	a. First	260 LF	260	LF	20.00	5,200.00
	b. Over	260 LF	30	LF	20.00	600.00
17	Gabion-Line	d Channel				
	a. First	120 LF	120	LF	110.00	13,200.00
	b. Over	120 LF	12	LF	110.00	1,320.00
18	Step Downch	ute				
	a. First	130 LF	130	LF	145.00	18,850.00
	b. Over	130 LF	15	LF	145.00	2,175.00
19	Energy Dissip	ator Pads	2	EA	250.00	500.00
20	Dual 36-Inch	Diameter RCP Culvert				
	a. First	150 LF	150	LF	200.00	30,000.00
	b. Over	150 LF	15	LF	200.00	3,000.00

		Approxim Quantities	<u>.</u> 9	ESTIMA	TED COST
Item No.	Item	Quantity	Unit	UNIT PRICE	COST
21	18–Inch Diameter RCP Culvert				
	a. First 70 LF	70	LF	50.00	3,500.00
	b. Over 70 LF	10	LF	50.00	500.00
22	Sediment Basin	1	LS	25,000.00	25,000.00
23	Wetland Mitigation	1	LS	57,200.00	57,200.00
24	Perimeter Fence				
	a. First 5,200 LF	5,200	LF	14.75	76,700.00
	b. Over 5,200 LF	520	LF	14.75	7,670.00
25	Engineering Inspection & Certification	1	LS	150,000.00	150,000.00

			Approxim Quantitie:		ESTIM	
Item No.	ltem		Quantity	Unit	UNIT PRICE	COST
1/1	Final Cover Alternate 1 & Gas Venting Layer Alternate 1 Base Items Overages Total Bid	_ `				4,586,000.00 374,070.00 4,960,070.00
1/2	Final Cover Alternate 1 & Gas Venting Layer Alternate 2 Base Items Overages Total Bid					4,974,500.00 412,570.00 5,387,070.00
2/1	Final Cover Alternate 2 & Gas Venting Layer Alternate 1 Base Items Overages Total Bid					4,474,200.00 362,270.00 4,836,470.00
2/2	Final Cover Alternate 2 & Gas Venting Layer Alternate 2 Base Items Overages Total Bid					4,862,700.00 400,770.00 5,263,470.00

Notes:

- 1 Overages are approximately 10% of the Estimated Quantities.
- 2 Mobilization based on 10% of Base Item and Overage costs.
- Alternative 1/1 includes all Item Nos. exclusive of Item Nos. 6.2, 9.2 and 11.2
   Alternative 1/2 includes all Item Nos. exclusive of Item Nos. 6.1, 9.2 and 11.2
   Alternative 2/1 includes all Item Nos. exclusive of Item Nos. 6.2, 9.1, 10.1 and 11.1
   Alternative 2/2 includes all Item Nos. exclusive of Item Nos. 6.1, 9.1, 10.1 and 11.1
- 4 Units are as follows: AC Acre LS Lump Sum CY – Cubic Yard SF – Square Foot EA – Each SY – Square Yard LF – Linear Foot

BROOME COUNTY DIVISION OF SOLID WASTE MANAGEMENT / GAF CORPORATION BROOME COUNTY COLESVILLE LANDFILL REMEDIAL DESIGN POST-CLOSURE COST ESTIMATE **APRIL 1994** 

Item Final Cover Repair											and the second se	
Final Cover Repair	Year 1	Year 2	Year 3	Year 4	Year 5	Year 6	Year 7	Year 8	Year 9	Year 10	Years 11 to 30	TOTAL COST
	60,123	40,082	40,082	40,082	20,041	10,021	10,021	10,021	10,021	10,021	0	250,515
Vegetative Repair	4,512	3,008	3,008	3,008	1,504	752	752	752	752	752	0	18,800
Fertilizing	2,850	2,850	2,850	2,850	2,850	2,850	2,850	2,850	2,850	2,850	0	28,500
Mowing	1,400	1,400	1,400	1,400	1,400	1,400	1,400	1,400	1,400	1,400	1,400	42,000
Drainage System Inspection and Repair	3,236	2,158	2,158	2,158	1,079	539	539	239	539	539	0	13,484
Wetland Mitigation Inspection and Repair	7,750	7,750	2,000	2,000	2,000	0	0	0	0	0	0	21,500
Survey	3,500	3,500	3,500	3,500	3,500	3,500	3,500	3,500	3,500	3,500	3,500	105,000
Engineering Inspection and Certification	6,100	6,100	6,100	6,100	6,100	3,050	3,050	3,050	3,050	3,050	3,050	106,750
TOTALS (\$)	89,471	66,848	61,098	61,098	38,474	22,112	22,112	22,112	22,112	22,112	7,950	586,549

NOTES: (1) All costs are in 1993 dollars.

(2) Costs are constant from year 11 to 30.

# APPENDICES

Sale of the second s

- Alas

. Biographics

.

## APPENDIX A WETLAND MITIGATION PLAN

•

COLESVILLE LANDFILL WETLAND MITIGATION COMPENSATION WETLANDS PLAN

Prepared For BROOME COUNTY DIVISION OF SOLID WASTE MANAGEMENT Broome County, New York

and

GAF CORPORATION Wayne, New Jersey

March 1994

Wehran-New York, Inc. Middletown, New York

and

Wetlands Research Associates, Inc. Newark, Delaware

Environmental Engineers • Scientists • Constructors

.

## TABLE OF CONTENTS

1.0		•••••	1-1
	1.1 PURPOSE		1-1
2.0		· · · · · ·	2-1
	2.1 SITE CONDITIONS2.2 SITE WETLANDS		2-1 2-1
3.0	WETLANDS IMPACTS	• • • • • •	3-1
	3.1 IMPACTS	••••	3-1
4.0		••••	4-1
	4.1 RESTORATION PLAN OBJECTIVES4.2 CONCEPTUAL DESIGN		4-1 4-2
5.0		••••	5-1
5.0	COMPENSATION SITE FEASIBILITY5.1TOPOGRAPHY AND DRAINAGE5.2SOILS5.3HYDROLOGY5.4VEGETATION5.5WILDLIFE5.6SITE FEASIBILITY		5-1 5-1 5-2 5-3 5-3
5.0	5.1TOPOGRAPHY AND DRAINAGE5.2SOILS5.3HYDROLOGY5.4VEGETATION5.5WILDLIFE		5-1 5-1 5-2 5-3 5-3 5-3

-

# **1.0 INTRODUCTION**

## **1.0 INTRODUCTION**

### 1.1 PURPOSE

The purpose of this report is to provide a conceptual plan for the creation of compensation wetlands as part of permit requirements for remedial actions at the Colesville Landfill, Broome County, New York.

These plans have been based on wetlands information provided in Remedial Design – Conceptual Design Report (June 1992), Pre-Final Engineering Design Report – Remedial Design of Final Cover and Groundwater Collection Systems (February 1993), correspondence documents with USEPA, and a brief site reconnaissance (November 1993).

It is the goal of Broome County and GAF Corporation to maintain the integrity of the compensation site and the environmental benefits provided by this site. Therefore, the County will not allow farming, silviculture or ranching activities to occur on the compensation site. However, the compensation site may be used in the future for educational purposes and non-intrusive features. Roads and structures will not be constructed in the compensation sites, unless a permit under Section 404 of the Clean Water Act is first obtained.

# 2.0 EXISTING CONDITIONS

## 2.0 EXISTING CONDITIONS

## 2.1 SITE CONDITIONS

The Colesville Landfill site is located 1,400 feet from the eastern bank of the Susquehanna River, 18 miles east of Binghamton, in eastern Broome County (Figure 1). Elevations on the landfill vary from 1,150 to 960 feet above sea level, while the river elevation is 930 feet above sea level. Two streams, on the east and west sides of the landfill, drain directly into the river. Soils in the landfill area are predominantly Braceville, Chenango and Howard, and Mardin channery series (Figure 2). Unadilla and Wayland series are the dominant soils of the floodplain along the river.

Vegetation on the landfill is a mixture of herbaceous weed and grass species. Some areas are sparsely vegetated with barren soil and rock fragments visible. Species included asters (<u>Aster</u> spp.), goldenrods (<u>Solidago</u> spp.), sweet fern (<u>Comptonia peregrina</u>), ragweed (<u>Abrosia artemisiifolia</u>), foxtail (<u>Alopecurus</u> spp.), broomsedge (<u>Andropogon virginicus</u>), and various grasses.


Upland forest occurs along the eastern and southern sides of the site. Species encountered in the forested areas include oaks (<u>Ouercus</u> spp.), shagbark hickory (<u>Carya ovata</u>), beech (<u>Fagus grandifolia</u>), sugar maple (<u>Acer saccharum</u>), white pine (<u>Pinus strobus</u>), and black cherry (<u>Prunus serotina</u>). Areas along streams and seeps (i.e., wetlands) were dominated by hemlock (<u>Tsuga canadensis</u>), red maple (<u>Acer rubrum</u>), and hornbeam (<u>Carpinus caroliniana</u>). Agricultural fields are located along the northern landfill boundary (hayfield) and approximately 200 feet southeast of the landfill (plowed field adjacent to East Windsor Road).

## 2.2 SITE WETLANDS

#### Landfill and Vicinity Wetlands

The following description of site wetlands is from the Remedial Design – Conceptual Design Report (June 1992).

The March 1991 Record of Decision for the site required that a wetlands survey, based on the "three-parameter method", be conducted during the remedial design phase. Wehran conducted a wetland delineation to identify and map wetland areas occurring on



the site, and in the immediate vicinity of the site, which could potentially receive impact by remedial construction activities.

On April 6 and 7, 1992 and December 14, 1993, biologists from Wehran flagged the wetland boundaries in the field using the three-parameter approach described in the Wetland Delineation Manual (Corps of Engineers, January 1987). Surveying of the wetland boundaries was performed by Wehran on April 9 and 10, 1992, and in December 1993.

Review of NYSDEC00 Freshwater Wetland Maps for the Colesville area indicate that there are no State-regulated wetlands on or near the site (see Figure 3). A review of National Wetland Inventory Maps indicates that three wetlands occur within the study area (Figure 4). These include two palustrine, unconsolidated bottom excavations (PUBH; i.e., ponds), and one palustrine forested wetland (PFO1).

#### Wetland Descriptions


Several wetlands were flagged within the study area (see Sheet 1 of 1). These wetlands range in size from 0.04 to 0.84 acres. Wetland A is a small depression. Wetlands B and H are associated with the streams previously described. Others originate as groundwater or leachate seeps (Wetlands C, D, E, F, G). All of the wetlands along the southern side of the study area are part of a larger wetland located further south. Only the upper portions of these areas, which originate as seeps and which may be impacted by remedial activities, were flagged as part of this study.


Several small wetland microhabitats were also noted on the landfilled section of the site. These microhabitats are all isolated depressions less than 0.1 acre in size and were not included in the mapping presented on Sheet 1 of 1. Although hydrophytic vegetation was present in these areas, standing water and saturated soil conditions are believed to be present only after storm events.


Following is a description of each wetland area flagged as part of this study. Data sheets and photographs of each wetland are included in Appendix B.

#### Wetland A

This wetland is located on adjacent property near the north central landfill border. The wetland is a small depressional area which receives drainage from the east, south, and west. A small outlet is located to the north. The wetland consists of an open water area,







1 to 2 feet deep; surrounded by a concentric ring of emergent vegetation 5 to 20 feet wide. Some hydrophytic shrubs and trees are located adjacent to the emergent zone. These shrub species include witch-hazel (<u>Hamamelis virginiana</u>, FAC-), speckled alder (<u>Alnus rugosa</u>, FACW+), hornbeam (FAC), buttonbush (<u>Cephalanthus occidentalis</u>, OBL) and red maple (FAC). Herbaceous species noted in the emergent zone consist of wool grass (<u>Scirpus</u> <u>cyperinus</u>, FACW+), soft rush (<u>Juncus effusus</u>, FACW+), tearthumb (<u>Polygonum sagittatum</u>, OBL), and sensitive fern (<u>Onoclea sensibilis</u>, FACW).

Soils in the vicinity of Wetland A are mapped by the Soil Conservation Service (SCS) as Volusia channery silt loams. These soils consist of deep, poorly drained, loamy soils formed in dense till. Soil samples retrieved within the wetland boundary from depths up to 12 inches were both mottled and gleyed. Mottle colors were generally found to range from orange to red (2.5 YR 4/8 to 2.5 YR 5/8). Gley colors were typically 5GY 7/1. Soils within the wetland boundary were inundated or saturated to the surface. This wetland is 0.76 acres in size.

#### Wetland B

This wetland is a small (0.2169 acres) linear wetland associated with a ditched tributary on the east side of the landfill. The wetland ranges from approximately 2 to 10 feet wide in certain areas. Characteristic plants include willow, rush, and sedge along the stream channel. Flowing water (2 to 3 inches deep) was present in the drainage channel.

### Wetlands C, D, E, F, and G

Wetlands C through G originate as groundwater seeps on the south facing slope, approximately 400 to 500 feet south (below) of the landfill. Several of these wetlands have visible leachate discharges in the upper sections of the wetlands. All of these areas start out as small linear rivulets or seeps, and drain south into a larger wetland complex. The areas flagged represent fingers of the same wetland which extend up the hillside. All wetland flagging was terminated at an access road which runs along the base of the hill. No physical wetland impacts are expected below this road; subsequently, these areas will not be disturbed. not flagged because no impacts are anticipated in this area. As the stream proceeds west, steep hemlock covered banks are encountered. The wetland area in this section is limited to the rock covered stream bottom. Further along the stream, deciduous trees become dominant in more of a floodplain type environment.

Soil samples were only obtained in the upper sections of Wetland H due to the prevalence of rock in the stream bed. Also, the wetland was typically defined as the stream channel in the lower reaches.

#### Borrow Area Wetlands Y, Z, and BWA

The wetlands occurring in the borrow area are predominantly streamside corridor wetlands. They are generally linear and narrow, sometimes only 3 to 4 feet wide. Near the streams, dominant woody vegetation consists of red maple (<u>Acer rubrum</u>, FAC), hornbeam (<u>Carpinus caroliniana</u>, FAC), yellow birch (<u>Betula alleghaniensis</u>, FAC), and witch hazel (<u>Hamamelis virginiana</u>, FAC-). Areas of more moderate elevation change where the stream corridor and wetland widened included hawthorn (<u>Crataegus</u> spp.), red-osier dogwood (<u>Cornus stolonifera</u>, FACW+), and elderberry (<u>Sambucus canadensis</u>, FACW).

While no formal evaluation of wetland functions and values has been conducted, the value of much of the delineated wetlands is restricted to stormwater conveyance and microhabitat for amphibians.

Other wetland functions typically identified as occurring in wetlands are of unknown, or at least minimal, value for the wetlands in the borrow area. Characteristics of the subject wetlands which contribute to the lesser importance of their functions include the following:

- Small aerial extent of wetland acreage. (The larger the wetland, the greater the potential to store stormwater and reduce flooding.)
- Linear shape, with some cross-sections 3 to 4 feet. (Wide wetlands allow greater dissipation of storm flow and increased frictional resistance of vegetation to filter sediments.)
- Position in the landscape. (Wetlands high in the watershed have limited opportunity for many of the documented wetland functions.)
- No receptors of function. (No downstream development.)

# 3.0 WETLANDS IMPACTS

## 3.0 WETLANDS IMPACTS

### 3.1 IMPACTS

Remedial construction activities at the Colesville Landfill which will potentially affect on-site and nearby wetlands will include: capping of the waste areas, groundwater withdrawal and treatment, disturbance of borrow areas, discharge of treated effluent, and discharge of non-contact stormwater from the capped areas.

Precise conclusions concerning the impacts of drawdown are difficult given the complexity of wetland/groundwater interactions. However, impacts to wetland environments around the landfill will be offset by the enhanced protection of water resources and by remediation of the site.

Wetlands found on the landfill and in the surrounding area are identified on the Wetland Delineation Map (see Sheet 1 of 1). Presented below is a description of potential impacts to each wetland.

#### Wetland H (North Stream)

Wetland H consists of small fringe wetlands located along the North Stream. This stream and associated wetlands are currently fed by surface water flowing from higher topographic areas and from discharging groundwater. Current remedial design plans call for the placement of several pumping wells and an impermeable cap along the western end of the landfill, which will reduce the amount of discharging groundwater to the stream. The result of this loss to the stream hydrology may decrease the flow rates in the lower section of the stream. Drawdown in that same area also raises the potential for the water way to become a losing stream (i.e., contributing to groundwater).

Leachate Seeps 1 and 3, located adjacent to the North Stream, will be intercepted by a collection system. The collection system, consisting of geosynthetic clay, composite, subangular stone, slotted polyethylene pipe, and a pump station will be located in those positions currently occupied by the seeps. Construction of the seep collection system is expected to physically impact the stream bank. However, backfilling of the collection system excavation upon completion will mean that the physical disturbance will be temporary. Further, Leachate Seeps 1 and 3 should dry up over a period of time resulting in an overall improvement in water quality for the North Stream. The stream's losing wate: balance may be compensated by the addition of treated effluent and non-contact stormwater runoff that will be directed to it from the landfill cap. Runoff will enter the stream via a step downchute located off the western end of the landfill. The step downchute can reduce the velocity of the flow by approximately 25 percent and allow some suspended particles associated with the stormwater to settle out.

Based on the pre-final design for the groundwater treatment system, treated effluent will be discharged to the North Stream. The effluent will enter DC-1-3 (diversion swale) from the treatment plan: and enter the stream via the energy dissapating downchute. This discharge will be at a maximum rate of 80 gpm (gallons per minute), and an average temperature of 50 to 55°F. A hydrological evaluation of the waterway utilizing the Soil Conservation Service's Technical Release No. 55 method, indicates that the peak discharge rate is far greater than the treated effluent discharge rate of 80 gpm (0.18 cfs) and will therefore not impact the existing drainage capacity of the North Stream.

#### Wetland A

Wetland A is an isolated wetland on the north side of the landfill. This wetland receives surface flow and groundwater discharge from higher topographic areas. Drainage from the wetland flows to the west into the North Stream. This wetland is not expected to be impacted by capping and borrow activities because it is essentially upgradient or cross-gradient of all operations. Drawdown should also have little affect since the wetland is underlain by a highly impermeable till and receives overland flow from an upslope origin that will not be affected by remedial construction activities. Accordingly, the vertical leakage from Wetland A has been calculated at 0.07 gallons/day per square foot (22,194 gallons/day) based upon a 20-year model of groundwater drawdown of 4 feet in the vicinity of Wetland A. This vertical leakage will be an increase of 7.8 percent from the present day vertical leakage of 20,583 gallons/day (see Appendix B). These numbers equate to a loss of approximately 1,611 gallons/day to the surface water flow leaving the wetland and entering the North Stream.

### Wetland B

Wetland B is comprised of a small narrow ditch corridor on the eastern (uphill) side of the site. In order to protect the integrity of the cap in that area, the stream corridor (Wetland B) will be rip-rapped along its length on the eastern end of the landfill and pass through a culvert near the southeast corner of the landfill.

Drainage from the sediment basin will be discharged to this drainage corridor following the removal of sediment.

### Wetlands C, D, E, F, and G

Wetland Areas C, D, E, F, and G will likely be affected by drawdown along the southerly portion of the landfill. These wetlands occur as seeps which are driven by the hydraulic head from that area. Drawdown is necessary in the southern portion of the landfill to help control flow from Leachate Seep 2 located immediately upslope of Wetlands C, D, E, F, and G. It is anticipated that these wetland areas will be lost as a result of remedial activities.

### Wetlands I, J, K, L, M, N, O, P

Capping activities will also require the filling of several small wetlands located directly on top of the landfill. Wetlands I, J, K, L, M, N, O, P, and Q currently exist as small, depressional, emergent wetlands, of which some originate as leachate seeps. The loss of these areas is unavoidable as capping is required to reduce the infiltration of precipitation into underlying waste strata.

Remedial construction activities, including capping and borrow operations, discharge of treated effluent, stormwater discharge, and groundwater withdrawal, will affect the wetlands on and around the Colesville Landfill. Those wetlands expected to be impacted minimally include Wetland Areas A and H. These wetlands comprise 1.60 acres. Wetland B comprising 0.22 acres, will receive impacts by construction activities that include placing rip-rap in the stream channel and passing the stream through a culvert. Wetland Areas C, D, E, F, and G, totaling 0.39 acres, are expected to be eliminated as a result of drawdown. Wetland Areas I, J, K, L, M, N, O, P, and Q, on top of the existing landfill and comprising 0.48 acres, will be lost because of capping operations.

## Borrow Area Wetlands: Y, Z, and BWA


Wetlands within the boxrow area will be removed during material excavation (Figures 5 and 6). Stream corridors will be re-established according to the mitigation plan, and may have wetland characteristics. All wetland impacts are addressed in the following compensation plan.


EPA has required that wetland impacts be compensated as follows:

IMPACT AN	TABLE 1 D COMPENS	ATION SUMMARY	
Wetland Impact Areas	Acres	Replacement Ratio	Compensation Acres
Landfill Surface and Southern Slope	1.1	1.0	1.1
Borrow Area	0.992	2.0	1.98
Total	2.092		3.08

Compensation Wetland Community Types	Acres
Open Water and Emergents	0.55
Emergents	0.85
Scrub,/Shrub	0.6
Forested	1.1
Total	3.08

10.006.3/94.02260.WT





4.0 PROPOSED CONCEPTUAL PLAN

•

.

## 4.0 PROPOSED CONCEPTUAL PLAN

The restoration plan for the mitigation site includes the following elements:

- 1. Topographic map of existing conditions and proposed contours for grading/excavation.
- 2. Revegetation plan describing species to be planted, density, and distribution throughout the mitigation area.
- 3. Monitoring as necessary to determine the success of the grading and revegetation plan.

## 4.1 **RESTORATION PLAN OBJECTIVES**

The restoration plan seeks to replace wetland habitat lost as a result of the remedial actions on the landfill site. Wetlands receiving impacts from the remedial actions consist of emergent wetlands located on the existing landfill surface and forested wetlands on the slope woodland, south of the landfill and in the borrow area. These wetlands serve to improve water quality, desynchronize flood flows, moderate base flows, and provide wildlife habitat. The proposed compensation program seeks to mitigate for these losses by restoring a greater acreage of wetland habitat on the site within the borrow area.

Specifically, the restoration plan will:

- 1. Create emergent, scrub shrub and forested wetlands in the lower area of the borrow area, adjacent to the sediment basin.
- 2. Revegetate the upper borrow area with an assemblage of forest tree species.
- 3. Increase wildlife habitat in the restored borrow area through increasing habitat diversity to include open water, emergent marsh, scrub shrub, forested wetlands, and restored upland forest.
- 4. Permanently preserve and protect wetlands through site ownership and maintenance.

The success of the restoration effort will be measured against these objectives.

### 4.2 CONCEPTUAL DESIGN

The current wetland design is based upon a pond for dependable hydrology in the margin wetland and a mixture of emergent, scrub/shrub, and forested wetland community types as commensurate in-kind replacement for the wetland impact areas on site.

The creation of wetland hydrology on site may be achieved immediately adjacent to the proposed sediment basin in the borrow area on the eastern edge of the landfill (Figure 5). Specifically, wetland hydrology may be created on a expanded shoreline margin on the north and eastern borders of the sediment basin. It is anticipated that approximately up to 30 feet of soils and glacial fill will be removed throughout the borrow area in order to provide sufficient material for the new landfill cap. Approximately 0.5 acre of pond margin will be created by excavation into the hillside in addition to the sediment basin area. The compensation wetland area will be comprised of the 0.55 acre permanent pond (initial sediment basin), 0.85 acre emergent wetland, 0.6 acre scrub/shrub wetland, and 1.1 acre palustrine forested wetland.

The primary source of water will be the stream within the borrow area and the surface runoff from the southern portion of the new landfill cap area. Groundwater elevations within the borrow area have not been determined, but may be assumed from boring data to be at streambed elevations in the stream between the landfill and borrow area or about 20 feet below the existing land surface. Water elevation within the basin and wetland margin will be set by a riser or weir and discharge structure.


The final construction specifications will describe the over-excavation (1 foot deeper) of the wetland margin area. This will allow for the addition of ½-foot depth of hydric soils from the stream and swale corridors of the borrow area, to bring the surface of the wetland up to the desired elevations. Hydric soils in the created wetland will enhance the growth of wetland plants through their associated soil moisture capacity, nutrients, and seed bank.

It is anticipated that the elevation of saturation in the margin wetland will be higher than the pond water elevation due to both capillary rise within the soil and the downgradient subsurface flow of water from the upper borrow area. Capillary rise even in pure sands may constitute 6 inches and the site till should exhibit greater capillary rise. These factors are expected to bring about saturated soil conditions (at least seasonally) within the root zone of the forested wetland area. Forested wetland community soils characteristically display a significant drawdown over the growing season. Four channels (two intermittent stream channels and two ditches) will cross the wetland area. In the event that sufficient wetland hydrology is not achieved during the monitoring period, check dams may be placed in these channels to back up flow and increase soil saturation in adjacent areas.

The wetland margin will include shallow water habitat, emergent marsh, scrub/shrub and forested wetland areas. Wetland communities within the area are: shallow water and emergent marsh (-0.5 to +0.5 feet above pond water elevation), scrub shrub (+0.5 to 1.0 feet), and wetland forest (1.0 to 2.0 feet). Figure 7 presents a diagrammatic layout of the planting area. The actual borders between communities will be blended and irregular as in natural communities. Calculations for the 10-year, 24-hour storm event indicate that basin elevations will extend to the mid elevations of the forested wetlands (1056.5 feet). The basin/pond discharge structure will be developed to allow for the adjustment of basin water elevation. The proposed water control structure is not active in nature. A dam or weir is proposed with a wooden plank face. Adjustment to the pond water level could be made as warranted by removing, adding, or changing the size of planks. At the end of the monitoring period the overflow level would be permanently set by either rip rap or fill. The permanent basin elevation will be set to achieve the desired hydrology within the margin wetland communities.

Plant species suggested for the wetland area are given in Table 1. All species are native plants either commonly found on-site or within the region. All plant material may be purchased from regional wetland nurseries.

4-3



5.0 COMPENSATION SITE FEASIBILITY

# 5.0 COMPENSATION SITE FEASIBILITY

# 5.1 TOPOGRAPHY AND DRAINAGE

The sediment basin, compensation wetland, and borrow area is located adjacent to the east end of the landfill. The site lies on a hillside that slopes moderately to the southwest, and is heavily wooded. The area is drained by a swale and two streams that eventually drain into the Susquehanna River, approximately one-half mile to the west. The elevation at the upper end of the proposed borrow area is 1,150 feet above sea level, and the lower elevation (near the proposed sediment basin) is 1,040 feet.

# 5.2 SOILS

The soil mapped in the borrow/compensation wetland area is Volusia channery silt loam, a deep, somewhat poorly drained, loamy soil. The Volusia series is listed as a soil with potential hydric inclusions. Hydric soil types in the vicinity that may occur as inclusions in Volusia soil at the site include Alden-Chippewa complex and Wayland soils.

AcA	Alden and Chippewa	Hydric	Deep, very poorly drained in depressions and along drainage ways
Wd	Wayland	Hydric	Deep, poorly to somewhat poorly drained
Unc	Unadilla silt loam	Non-Hydric	
Chc	Chenango and Howard	Non-Hydric	
Wa	Wallington silt loam	Hydric Inclusions	Deep, acid, somewhat poorly drained in slight depressions, sometimes ponded
MhD			
WIIID	Mardin	Non-Hydric	
Sc	Mardin Scio silt loam	Non-Hydric Non-Hydric	

Soil data collected in the area of the sediment basin are presented below with auger locations given in Figure 5.

Auger	Depth	Description (Value/Chroma)
1	D-5" \$-10" 1D-15" 15-20"	5/1, 4/1 10YR, Fe Ox roots 5/1, 4/1, 6/2 10YR 5/1, 6/1 5Y, Fe Ox Ag. 6/1 5Y, 6/8 10YR, Fe Ox Ag.
2	ָר-5" 5-20"	3/1 10YR 3/1, 5/3 10YR, 6/1 5Y, Fe Ox Ag.
3	0-5" \$-10" 10-20"	5/5, 4/2 10YR 5/4 2.5Y 5/4, 6/4 2.5Y
4	D-5" \$-10" 1D-20"	5/5, 4/2 10YR 5/4 2.5Y 5/4, 6/4 2.5Y
5	ר-5" 5-20"	3/1 10YR 3/1, 5/3 10YR, 6/1 5Y, Fe Ox Ag.
6	0-5" \$-10" 10-20"	5/5, 4/2 10YR 5/4 2.5Y 5/4, 6/4 2.5Y

# 5.3 HYDROLOGY

The area of the proposed sediment basin and compensation wetland is heavily influenced by surface flow from the upper watersheds to the north and east. Stream B, which flows in a channelized ditch west of and adjacent to the proposed basin and wetland, does not presently contribute directly to the surface flow. There are two swales and a small stream that converge in the southwest corner of the area, then join Stream B and flow south. Although the drainage area is moderately steeply sloped, the entire area is forested with adequate cover to stabilize surface flows.

Limited information is available on groundwater in the borrow area. Groundwater elevations as shown in drawing details are based on one boring log and the assumption that groundwater elevations are near the streambed of Stream B or about 1,050 feet in elevation, between the landfill and the borrow area. The boring log record from the borrow area indicates groundwater at about 20 feet below the surface. One may assume that in the vicinity of the proposed sediment basin, groundwater may seasonally reach the bottom of the basin at an elevation of 1,050 feet. Water budget calculations suggest wetland hydrology will usually be achieved (Appendix C).

5-2

## 5.4 VEGETATION

The proposed sediment basin and compensation wetland area is now predominantly second growth, mixed hardwood and pine forest. The upper elevations are dominated by white oak (<u>Quercus alba</u>), shagbark hickory, (<u>Carya ovata</u>), and white pine (<u>Pinus strobus</u>) with a sparse understory including black cherry (<u>Serotina Prunus</u>). The lower elevations are dominated by red oak (<u>Quercus rubra</u>), white pine (<u>Pinus strobus</u>), and red maple (<u>Acer rubrum</u>). Throughout the study area in lesser amounts were American beech (<u>Fagus grandifolia</u>), poplar (<u>Populus sp.</u>), birch (<u>Betula sp.</u>), hornbeam (<u>Carpinus carolinianus</u>), and red osier dogwood (<u>Cornus stolonifera</u>).

### 5.5 WILDLIFE

As second growth deciduous forest, the study area presumably supports diverse wildlife populations. During the November site visit, tracks and signs were observed for white-tailed deer, wild turkey, eastern cottontail, and canids. Red-tailed hawks and many passerine birds including, nuthatch, chickadee, fox sparrow, white throated sparrow, cardinals, and crow were observed on the site.

### 5.6 SITE FEASIBILITY

The sediment basin in the borrow area will be designed as a permanent wet basin or pond with a 5-foot water depth overall. This open water area, with associated water control structure, can provide a stable hydrology for the establishment of a wetland margin along the water's edge.

Grading of the margin around the north and east of the basin can easily be achieved assuming the representation of the Boring Log 9 data to this location. Slightly steeper slopes will be required immediately upslope of the wetland border to achieve the original borrow area contours and cut volumes. Grading in the margin wetland will require a 1 percent slope, from 0.5 below to 2.0 above, the design water elevation.

The source of water for the margin wetland will be the surface water stream through the borrow area, subsurface soil moisture flow in the borrow area, and runoff from the southeastern portion of the new cap landfill surface. Diversion of the adjacent stream (Wetland B) could be considered. The relocation of hydric topsoil from the borrow area to the margin wetland will ensure greater and enhanced growth of wetland plants. 6.0 PLANTING DESIGN AND SPECIFICATIONS

# 6.0 PLANTING DESIGN AND SPECIFICATIONS

The objective of the re-vegetation plan is to introduce species that can initiate the re-establishment of a diverse wetland and surrounding upland ecosystem. This will be achieved through:

- Use of hydric soils from the impact areas to provide a seed source for "volunteer" wetland plant colonizers.
- 2. Planting with emergent and woody plants.

### 6.1 PALUSTRINE FORESTED WETLANDS

The dominant tree species of the area forested wetlands are red maple, green ash and hemlock, with an understory of spice bush and ironwood. The compensation site plan will emphasize these dominants and add select species found elsewhere to enhance diversity. Site diversity will also increase as the dominants mature providing greater shade and protection. Dominant species, such as red maple tend to be hardier, have wider moisture tolerances, and may survive better than less common species during the initial stages of the restoration. Additional wetland species will be selected both for being fast growing or otherwise less susceptible to grazing. A relatively rapidly formed canopy will allow for colonization by the shade tolerant wetland species not easily established in the open early stages of the compensation wetland development.

# 6.2 SCRUB-SHRUB WETLANDS

Shrub species will be planted within the forested areas at a equal density to tree species (Planting Specifications). The scrub/shrub wetland has been included in anticipation of the formation of a natural scrub/shrub community in this zone as a transition between the forested and emergent wetland communities. Shrub species will be planted in clumps on the border of the forested wetland areas; therefore, preference will be for shade intolerant species. Willow cuttings and clumps of alder will be located along banks or the waters edge wherever possible.

# 6.3 EMERGENT WETLANDS

A portion of the compensation wetland area will be planted with emergent species. The wettest of these areas may remain in solely emergent species, but in most areas there will probably be an invasion of tree and shrub species. In time these areas may develop into forest communities.

Emergent wetland species will be located in areas where soils are probably saturated throughout the growing season. Although selected species will be planted from bare root stocks and seeding, many species of sedges, rushes and broadleaved plants will invade and colonize these areas. It is expected that seeds and rootstocks in the hydric soils used as backfill will also provide a source of plant propagules.

Many emergent wetland plant species can tolerate considerably dry, as well as wet conditions. These more hardy and facultative species will be located on berm slopes of the lower elevations, which will experience greater extremes in conditions.

# 6.4 BERM AREAS

Facultative grass species available in seed stock for basin berm areas include: <u>Agrostis alba</u> (redtop), <u>Agrostis tenuis</u>, <u>Agrostis palustris</u> (bentgrasses), <u>Poa trivalis</u> (rough bluegrass), and <u>Alopercus pratensis</u> (meadow foxtail). All exposed soil will be seeded with this mixture.

### 6.5 UPLAND FOREST

Well drained, higher elevations of the sites will be planted with trees to establish an upland buffer to the wetland. Trees planted will be representative of adjacent uplands with an added emphasis on mast crops for enhanced wildlife value.

# 6.6 PLANTING SPECIFICATIONS

Plant species to be used are shown in Table 1. Planting details for trees and shrubs are discussed below. Trees to be used will be purchased at a height of 1 to 2 feet, and planted in density equivalent to 10 feet on center; although planting location will be on a random basis. Species will be chosen randomly in each community group. Shrubs will be purchased at 1 to 2 feet in height and planted in groups of 3, 5, and 7, of the same species. In the case of a scrub-shrub community, these groupings will be in a density equivalent to 10 feet on center.

The plan is based on the use of native "wet-cultured" plants grown especially for wetland conditions. Nurseries that specialize in native wetland species should be contacted. Other nurseries tend to grow trees and shrubs for landscaping in upland conditions and the plants from these companies will not have been adapted to wetland conditions. If suitable plants are not available, it may be necessary to have them grown by nurseries under contract. All trees should be at least one year old prior to planting.

The location for the installation of various plant species will be shown on a detailed planting plan to accompany the final engineering drawings and specifications. These habitat and wetland types are shown in Figure 7. Emergent wetland species will be planted at the lowest elevation, where ponding is expected to occur the longest or soil saturation the longest throughout the year. Forested wetland species will be planted in the area having a seasonally wet hydroperiod, generally from December to late May. FACW species will be distributed in wetter areas than FAC species. Upland species will be planted in areas that have a water table generally below 24 inches or, when higher, it only saturates the upper soil profile for brief periods of time.

Assuming that the cap construction is completed in 1994, emergent species will be planted in the spring of 1995. Although seeding with facultative grasses is most needed to stabilize erodible surfaces, seeding may be carried out over the entire compensation site to hasten ground cover development with wetland species. A rapid natural colonization of the areas of hydric soils should be expected from the transported seed bed and wind born seeds. No additional watering is anticipated.

TABLE 1 WETLAND SPECIES FOR PLANTING					
Species Name	Common Name	<b>Number</b> <sup>1</sup>	Indicator Status		
	EMERGENTS	5			
<u>Carex stricta</u>	tussock sedge	415 b.r.	OBL		
Juncus effusus	soft rush	415 b.r.	FACW+		
<u>Onoclea sensibilis</u>	sensitive fern	200 qt.	FACW		

6-3

TABLE 1         WETLAND SPECIES FOR PLANTING					
Species Name	Common Name	<i>Number</i> <sup>1</sup>	Indicator Status		
<u>Sagittaria latifolia</u>	duck potato	200 qt.	OBL		
Scirpus cyperinus	wool grass	415 b.r.	FACW+		
<u>Sparganium</u> americanum	eastern bur-reed	200 qt.	OBL		
	SHRUBS				
<u>Alnus rugosa</u>	spackled alder	6	FACW+		
<u>Cephalanthus</u> occidentalis	bu;ton bush	6	OBL		
Cornus stolonifera	recl-osier dogwood	6	FACW+		
<u>Salix purpurea</u>	streamco willow	6	-		
Sambucus canadensis	elderberry	6	FACW+		
	TREES				
Acer rubrum	rec maple	40	FAC		
<u>Fraxinus</u> pennsylvanicus	green ash	20	FACW		
<u>Salix nigra</u>	black willow	10	FACW+		

<sup>1</sup> Plant material type: b.r. = bare root, qt. = quart container

6-4

# 7.0 PROPOSED SCHEDULE

.

# 7.0 PROPOSED SCHEDULE

# 7.1 PLANTING SCHEDULE

### **General Schedule**

Planting of aquatic or emergent wetland species will occur between April 1 and June 1, preferably during April. Fall planting of trees and shrubs will occur between September 1 and October 30. Planting will not occur when the ground is frozen, snow-covered, or in an otherwise unsuitable condition for planting. Propagules will be planted in the proportions determined above in this plan. All balled, burlapped, and container grown plants will be handled and moved only by the ball or container.

Holes for planting will be dug to produce vertical sides and flat bottoms. When pits are dug with an auger and the sides of the pits become glazed and smooth, the glazed surfaces will be scarified. The depth of the holes will be 6 inches deeper than the root ball. The width of the holes will allow a minimum distance between the ball, and the sides of the hole of 6 inches for shrubs and 12 inches for trees. Loosen the bottom 4 inches of the hole with a shovel prior to planting. One part peat moss with four parts soil should be mixed to use as a soil amendment to support the root ball in the hole.

Plants will be set plumb and manually held in position until sufficient soil has been firmly placed around roots or ball. Plants are to be set at the same depth at which they were grown in the nursery or container.

Balled and burlapped stock will be backfilled with soil to approximately half the depth of the ball, then tamped and watered. Burlap and tying materials will be carefully removed or opened and folded back. Plastic wrap will be completely removed before the placement of backfill. The remainder of backfill will be tamped and watered.

Willow and alder cuttings may be made in winter to early spring and transplanted along the water's edge of the compensation wetland before leaf out. Willow cuttings can be planted on 2-foot centers. Emergent plant species rhizomes can be planted in early spring as available from the supplier.

## 7.2 WATERING

All plants will be watered by flooding the backfilled hole within the same working day upon which they were planted. During and immediately after watering, all plants will

# 8.0 MONITORING

.

-

# 8.0 **MONITORING**

# 8.1 GOALS OF THE MONITORING PROGRAM

The monitoring program will be conducted to document the Permit Special Conditions. These permit conditions will be documented over a period of 2 years, starting from the completion of the first planting within the compensation wetlands.

Monitoring will be conducted during each year of the monitoring period. Progress and formal reports will document the status of wetland site conditions using the following monitoring methodology. The final monitoring report will provide a summary of monitoring data trends and compare current wetland status with compensatory wetland goals.

## 8.2 MONITORING PROGRAM COMPONENTS

### 8.2.1 Photographs

The compensatory wetland will be documented through fixed point photos with range poles or objects for scaling and reference. Location and number of photographs will be sufficient to cover the entire compensation site. Photographs will be taken from the same point and in the same direction each sampling period. Significant changes in the wetland structure, including events such as storm damage, will be documented by these photos.

### 8.2.2 Precipitation Gauge

Local recording precipitation gauges will be located near the mitigation area to provide better estimates of watershed precipitation than distant weather station records. Daily records of precipitation will be maintained during the period of monitoring and these data will be included in the annual monitoring reports.

### 8.2.3 Surface and Groundwater Monitoring

Shallow groundwater piezometers will be maintained in the compensatory wetland. Reference will be made to other groundwater elevation records. Groundwater and surface water records will be continued for the duration of the monitoring program and data summaries provided in the annual reports.

### 8.2.4 Base Map

A base map or plan view will be provided illustrating the location of photo points, piezometers, and sampling areas.

### 8.2.5 Vegetation Assessment

Vegetation is generally indicative of the structure of wetlands and a quantitative assessment of vegetative cover and survival is required by the permit conditions. The composition of each wetland vegetation community will be adequately characterized. The following general methods will be followed with an allowance for site or minor modifications. Sampling will be conducted during late spring and early fall periods of each monitoring year to best identify dominant plant species and assess seasonal biomass.

**Forested Wetlands** – A belt transect or line intercept method will be employed for sampling areas where tree species (with a secondary shrub layer) are to be dominant. Transects will be positioned so that each vegetation zone or category is sampled. Transects will also be located along wetland basin moisture gradients, extend into forest buffer vegetation and into undisturbed upland vegetation adjacent to the compensatory wetland.

**Scrub/Shrub Wetlands** - Replicate quadrat sampling will be used in areas to be dominated by shrub species. The number and average height of woody individuals within quadrats and the DBH of the largest individuals of each taxa recorded. Paired 3-meter by 3-meter quadrats are recommended.

**Emergent Wetlands** – Emergent vegetation areas to be dominated by herbaceous plant species are to sampled using replicate quadrats. The percent cover and average height of individuals of each taxa within the major height strata will be recorded. Each major herbaceous plant zone will be sampled. Seven replicate 1-meter by 1-meter quadrats are recommended.

### 8.2.6 Habitat Enhancement

Observational data will be collected on wildlife observed during seasonal vegetation assessments in the compensatory wetland area. Notes will also be kept on the grazing or predation of wetland vegetation.

## 8.3 IDENTIFICATION OF PROBLEMS AND RECOMMENDATIONS

As indicated through the monitoring program or otherwise noted by monitoring and facility staff, problems arising during the monitoring period will be communicated by the applicant to the District Corps of Engineers. Recommendations will be developed to compensate for problems or otherwise direct site management toward the goals of the wetland compensation program.

## 8.4 MAINTENANCE OF DOMINANT WETLAND VEGETATION

Wetland compensation program goals are the establishment and limited maintenance of forested and emergent wetland plant communities. Compensatory Wetland Plan specifications have been developed to enhance the establishment of such communities as quickly as possible. The persistence of these wetland communities may not depend upon a consistency of wetland community species composition as initially established on the site. Rather, wetlands are among the most dynamic of landscape features and their plant community assemblages reflect such temporal change. The influence of climatic variation, the natural colonization by native plants, and the natural development of site wetland hydrology and nutrient regimes may likely lead to a wetland that differs in community structure, but adequately meets program goals. Maintenance and management of the site will be directed towards establishing a natural wetland community over time. APPENDICES

.

# APPENDIX A DATA SHEETS AND PHOTOGRAPHS

#### WETLAND DETERMINATION

Applica Name:	int		Application	L	Proje Name:	Colesvi	<u>  c</u> Landfill
State:	NY	County:	Broome Legal Desc	ription:			
Date:	4/6/	92	Plot No.: <u>A-1</u>		Section:		
	/ /		wetland				

<u>Vegetation</u> [list the three <u>dominant</u> species in each vegetation layer (5 if only 1 or 2 layers)]. Indicate species with observed morphological or known physiological adaptations with an asterisk.

1

1

ſ

Ĺ

Ĺ

Ĺ

Ĺ

Ĺ

Ć

	Indicator		Indicator	•
Species	Status	Species	Status	-
Trees		Herbs		1 1
1.		7. Polya	jonum sagit	tatum O.BL
2.	·	8. Scirpus	cyperinus	FAC.W+
3.		9. Juneus	ettusus	FACW+ FACW+
Saplings/shrubs		Woody vines		
4. Salix discolor	FACW	10. Rubus	hispidus	FACW
5. Cephalanthus c	occidentalis OB	SL 11.		
6. Spirea latifolic	2 FAC+	12.		
% of species that are	BOBL, FACW, and/c	or FAC: <u>&gt;50</u> % Oth	er indicators:	·
Hydrophytic vegetatio	on: Yes X No	Basis:_>5	0% FAC or we	Her.
Soil	- 1			
Series and phase:	lusia	On hydric soils	list? Yes;	; No $\underline{\times}$ .
Mottled: Yes X; I	No Mottle d	color: <u>2.5/R 5/8</u>	Matrix color:	
Gleyed: Yes X No		icators: <u>56</u>	Y 7/1	
Gleyed: Yes <u>X</u> N Hydric soils: Yes <u></u>	X; Basi	s: MoHling and	Saturated Cor	dition.
Hydrology				
Inundated: Yes $X$	; No Depth	of standing wate	er: at surfa	<u>ce</u> .
Saturated soils: Yes	s <u>X;</u> No	Depth to saturat	ted soil: <u>44 S</u>	wface.
Other indicators:				<u> </u> .
Wetland hydrology:	Yes_X; No	. Basis:		·
Atypical situation:	Yes; No			
Normal Circumstances				
Wetland Determination	<u>n</u> : Wetland $Y_{f}$	<u>25     ;</u> N	onwetland	•
Comments:				

Decermined by: Dave Tompkins / Joe Kopalek

# WETLAND DETERMINATION

	r: Project Colesville Land	1.71
Name: Number		rr 1]
	l Description: Township:Range:	
Date: 4/6/92 Plot No.: T	Al Section:	
<u> </u>		
Vegetation [list the three dominant species		-
	es with observed morphological or known	· I
physiological adaptations with an aste		
Indicator Species Status	Indicator Species <u>Status</u>	
Trees	Verbe	1
1. Quercus alba FACU-	7. Lycopodium clavatum FAC	-
2. Carya ovata FACU-	8.	]
3. Pinus Strobus FACU	9.	-
Saplings/shrubs	Woody vines	4
4. Ostrya Virginiana FACV	10.	and the second second
5. Pinus strobus FACU	11.	
6.	12.	
<b>Z</b> of species that are QBL, FAC $J$ , and/o		
Hydrophytic vegetation: Yes No	X. Basis: < 50% of Plants FACor	્ય
	weller on Indicator List.	
$\frac{Soll}{2}$	Hloam	
	H loam On hydric soils list? Yes; No_X.	Constraints of the second s
Mottled: Yes; No_X Mottle of	color:; Matrix color:;	
Gleyed: Yes No X Other ind:		1
Hydric soils: Yes NoX_; Bas:	is: No hydric soil indicators.	
Hydrology	1 . 1	
inundated: Yes; No_X. Depth	of standing water: <u>noneobservel</u> .	
Saturated soils: Yes ; No $X$ .	Depth to saturated soil: Move a beerve	1
Other indicators:		
wetland hydrology: Yes:; No X	. Basis: No saturded soi / evidance.	
Atypical situation: Yes; No X		1
Normal Circumstances? Yes No X	Vor	
Wetland Determination: Wetlanc	; Nonwetland // ·····	7
	ed in upland northof wetland H	
on a 1090 slope.	Determined by: Dave Tompkins / Joe Kopale	
	Decermined by: Jave 10mpkins / Joe Ropa 121	-
	B2	

### WETLAND DETERMINATION

ľ

Ĺ

ĺ

C

ſ

(

ſ

C

C

C

C

I

Applicant	Application	Project	sville Landfill
Name:	Number:	Name: Color	
	No.: TAZ Wetland Transcot	Township:Range Section:	

<u>Vegetation</u> [list the three <u>dominant</u> species in each vegetation layer (5 if only 1 or 2 layers)]. Indicate species with observed morphological or known physiological adaptations with an asterisk.

0	Indicator	<b>.</b> .	Indicator
Species	Status	Species	Status
1. Acer rubrum	FAC		Jusus FACWt
2. Betula lenta	FACV	8. Sphagnum	<u>r spp.</u> NA
3.		9. Onoclea e	<u>n spp.</u> NA sensibilis FACW
Saplings/shrubs		Woody vines	
4. Alnus rugosa	FACWA	10.	
5.		11.	
6.		12.	
Z of species that are	OBL, FACW, and/	or FAC:-50% Other	indicators: .
			Han 50% FAC or wetter
<u>Soil</u>			
Series and phase: Volu	isia chamery sill be	On hydric soils lis	st? Yes; No_ $X$ .
Mottled: Yes; No			
Gleyed: Yes No			
Hydric soils: Yes_X	No; Bas	is: <u>Mottling and</u>	Saturated Soil.
Hydrology			
Inundated: Yes $X$ ;	No . Depth	of standing water:	at surface .
Saturated soils: Yes			
Other indicators:			
Wetland hydrology: Ye	es X ; No	. Basis:	:
Atypical situation:			
Normal Circumstances?	Yes X No	<b>.</b>	
Normal Circumstances? Wetland Determination	: Wetland YE	; Nonwe	etland .
Comments: Part of -	transect for	wetland 4	
		Determined by: Day	e Tompkins / Joe Kopalek

Ĵ

### WETLAND DETERMINATION

سراWET	AND DETERMINATION		
	pplication umber:	Project Name: Colesville Land	df:11 🚘
State: NY County: Broome	Legal Description:	Township:Range:	
Date: 4/6/92 Plot No .:	<u>TA</u> 3 s	ection:	
	(wetland)		
Vegetation [list the three dominate	nt species in each v	egetation layer (5 if	
only 1 or 2 layers)]. Indicate s	ecies with observed	morphological or known	
physiological adaptations, with an	asterisk.		
Indicator		Indicator	
Species Status	Species	Status	
Trees	Herbs	m sagitatum OBL	
1.	· rolygon	in sagrification English	
2.	8. Unouza	sensibilis FACW	
3.		cyperinus FACW+	
Saplings/shrubs	Woody vines	hispidus FACW	
4. Hamamelis virginiana FA		NSpice	
5. Alnus rugasa FAC	$\omega + 11.$		
7 of species that are OBL, FACW,			
			***
Hydrophytic vegetation: Yes X	Δα <u>.</u> . Βα ει ε. <u>()/</u>	wetter.	
So11	Ũ		
Series and phase: Olusia chunnery Si	How on hydric soil	list? Yes : No X	
Mottled: Yes; No Mot	the color: 2.57R 4/	R: Matrix color:	
Gleyed: Yes X No Other			13
Hydric soils: Yes X No;			
Hydrology			
Inundated: Yes $X$ ; No	opth of standing wat	ter: at surface.	
Inundated: Yes_X; No D Saturated soils: Yes_X; No	Depth to satura	ated soil: At Surface	
Other indicators:	·	·	
Wetland hydrology: Yes X; No	Basis: <u>Soi</u> ]	Saturated.	<b>.</b> .
Atypical situation: Yes; No_			
Normal Circumstances? Yes X N	0		
Normal Circumstances? Yes X N Wetland Determination: Wetland	YES ;	Nonwetland	
<u>Comments</u> : Transect point in			
	Determined by	: Dave Tompkins / Joe Kopale	ek ]

TAY - option went of method A

#### DATA FORM 1

#### WETLAND DETERMINATION

Applicant Name:	Application Number:	Name: Colesville Landfill
State: _/	1.Y County: Broome_Legal Description:	Township:Range:
Date:	1/6/92 Plot No.: TA4	Section:
	<u>///</u>	

<u>Vegetation</u> [list the three <u>dominant</u> species in each vegetation layer (5 if only 1 or 2 layers)]. Indicate species with observed morphological or known physiological adaptations with an asterisk.

Ì.

Ĺ

Ĺ

L

Í.

Ĺ

C

Species	Status	Speci	es	Status	
<u>Trees</u> 1. <u>Pinus Strobus</u> 2. <u>Acer rubrum</u> 3. <u>Qvercus rubra</u> <u>Saplings/shrubs</u> 4. <u>Hamamalis virgin</u> 5.	FACU FACU- FACU-	Herbs	podium	<u>clavatum</u>	
<ol> <li>f species that are</li> </ol>			/ 00h /		
4 of species that are Hydrophytic vegetation			: Less that		!
Soil					
Series and phase: $\bigvee_{\mathcal{U}}$	lusia silt loan	n On hydric s	soils list	t? Yes; No <u></u> .	
Mottled: Yes; N					
Gleved: Yes No.	X Other in	dicators:			
Hydric soils: Yes	<u> </u>	sis: <u>No ind</u>	icators	of hydric soils.	
Hydrology Inundated: Yes;	No X . Dept	h of <b>standin</b>	g water:_	·	
Saturated soils: Yes	; No X.	Depth to sa	aturated :	soil: Non observed	
Other indicators:				·	
Wetland hydrology: Y	es ; No X	. Basis:		•	
Atypical situation:					
Normal Circumstances?				,	
Wetland Determination			_; Nonwe	tland les	
Comments:					

Decermined by: Dave Tompkins / Joe Kopalek

.

### WETLAND DETERMINATION

					. <u>(</u>
Applicant Name:	Applicat: Number:	ion	Projeci Name:	ColesvilleLa	ndfilt
	y: Broome Legal De	escription:			
Date: 4/6/92	Plot No .: A-(		Section:		ي ا
	Wetla	nd			
Vegetation [list the	three <u>dominant</u> spec:	ies in each	vegetation la	ayer (5 if	
only 1 or 2 layers)].	Indicate species	with observe	ed morphologic	al or known	
physiological adaptat	ioms with an asteria	sk.			
<b>.</b> .	Indicator		Ind	icator	ک روپ
Species	Status	Species	Sta	atus	
1. Carpinus caroli	iniana FAC.	rbs			
	Milling Philo	7. <u>Sphas</u>	cyperinu	EAC W+	_
2.		8. Scirpus	- COPERINA	inum FACV	and the second se
3.			um again		24
Saplings/shrubs 4. Tsuga Canaders		ody vines	· hisaid	lus FACW	
5.		10. <u>KUDA</u>	s <u>hispid</u>		
		12.			. 🖷
<pre>6. 7 of species that are</pre>		_			
Hydrophytic vegetatio	-		etter on pla	es parcor.	2
So11					
Series and phase:	Jusie Channes sitt lanon	budric coi	la list? Ves	· No X	
Mottled: Yes_X;		and a 540	A. Marrix co		
Gleyed: Yes X No					
Hydric soils: Yes	X No : Basis:	moHLen	and shenge	soilanditions	
$\rightarrow$	, · · · · · · · · · · · · · · · · ·				. 44
Hydrology					39
Inundated: Yes X	; No Depth of	standing w	ater: Af Sk	rface.	3 ل
Saturated soils: Ye					
Other indicators:					
Wetland hydrology:	Y <b>es_X_</b> ; Nc	Basis: Sto	nine Wate	present.	4=
Atypical situation:			0	T	. 19
Normal Circumstances	? Yes X No .				
Wetland Determination	<u>n</u> : Wetland $Yes$	<u>;                                    </u>	Nonwetland	<u> </u>	
Comments: - Onla m					
	•				
	Г	etermined b	y: Dave Tomp	Kins/Jae Kopa	ICK 1
		B2	•	, ,	

#### WETLAND DETERMINATION

	Application Number: Broome_Legal Des Plot No.: Watland.	cription: Tow		Landfill 
Vegetation [list the th only 1 or 2 layers)]. physiological adaptatio	Indicate species wi	th observed mo		
I	ndicator Status	<u>Species</u>	Indicator Status	
<u>1. Acer rubrum</u> 2.	FAC 7	. Symplocarpu Polusticha	us foetidus O	BL S FACU-
3. Saplings/shrubs	9 <u>Wood</u>	ly vines		
4. Carpinus carolini 5. <u>Hama melis virginiana</u> 6. Lindera <u>benzoin</u>		•		

% of species that are OBL, FACW, and/or FAC:>50%. Other indicators: Hydrophytic vegetation: Yes X No \_\_\_. Basis: >50% of Planti 1:5kd. Or FAC or wetter

<u>So11</u>	
Series and phase: (houghoo	On hydric soils list? Yes; No
Mottled: Yes X ; No	On hydric soils list? Yes; No color:2.578 48; Matrix color:257 4/2.
Gleyed: Yes X No Other in	dicators: Gley Calor 57 4/1
Hydric soils: Yes No; Ba	sis: Sample is molted and sleyed.

### Hydrology

Inundated: Yes X; No \_\_\_. Depth of standing water: 10 \_\_\_\_\_. Saturated soils: Yes X; No \_\_\_. Depth to saturated soil: Surface. Other indicators: Stream Channel present dine wate Soils Atypical situation: Yes ; No X Normal Circumstances? Yes X No\_ Yes Wetland Determination: Wetland ; Nonwetland Comments:

Determined by: Dave Tompkins / Joe Kopalek

\_]

1

][

	WITLAND D	ETERMINATION		-
Applicant Name:	Applic Number		Project Name: Coles	ville Landfill
		Description: Tow		
Date: 4/6/92		nd between sect		
<u> </u>	Cand	D		
Vegetation [list the	three <u>dominant</u> sp	ecies in each vege	tation layer (5	if 🗖
only 1 or 2 layers)].	Indicate specie	s with observed mo	rphological or k	nown
physiological adaptat	ions with an aste	risk.		
Species	Indicator Status	Species	Indicator Status	
Trees		Herbs		
1. Quercus reibra	FAC V-	7. Lycopodium	Clavartum	FAC _
2. Acer rubrum	FAC.	8.	-	
3. Canya ovata	FAC)-	9.		
Saplings/shrubs		Woody vines		
4. Carpinus Carolin	iang FAC	10.		
s. Pinus Strobu	S FACU	11.		
6. Fague grandifel	4 FACV	12.		
7 of species that are	BL, FACW, and/c	or FAC:	indicators:	·
Hydrophytic vegetatio	on: Yes 💢 No _	<u>X</u> . Basis: <u>- 50</u>	& of plant Spe	cier.
	ì	listed	as FAC or we	tler _
Soil	, c.11	Class Lagra		_
Series and phase:	Chango - Silt;	On hydric soils li	.st? Yes; 1	lo_X.
Mottled: Yes; H	No_X. Mottle c	color: <u>Nohl</u> ; M	atrix color:	
Gleyed: Yes No	) X Other ind	leators: No		·
Hydric soils: Yes	No $\chi$ ; Bast	ls: No hydric !	soil indicator	<u>·s</u> . <b>_2</b>
	÷	1		1.
Hydrology				
Inundated: Yes				<u> </u>
Saturated soils: Ye	s; No_X.	Depth to saturated	soil: <u>Name O</u>	hserve
Other indicators:	N			
Wetland hydrology: Atypical situation:	Yes; Nc	. Basis:		·
Normal Circumstances	? YesNo_X	_·	. /	
Wetland Determinatio	n: Wetland	; Non	vetland 105	· 11
Comments:				

Determined by: Dave Tompkins / Joe Kopalek B2

### WETLAND DETERMINATION

Applicar Name:	nt'	Application	Name: Colesville Landfill
State:	N.YCounty: <u>F</u>	coome_Legal Description	
Date:	4/6/92 P1	ot No.:_D2A	Section:

Vegetation [list the three dominant species in each vegetation layer (5 if only 1 or 2 layers)]. Indicate species with observed morphological or known physiological adaptations with an asterisk.

	Indicator			Indicator	
Species	Status	S	pecies	Status	
Trees 1. Acer rubrum	FAC	Herbs 7 S	molocaro	us fortidus	OBL
2. Betula allegha	niensis FAC	8.	ympic carp		
3. Tsuga Canaden	<u>sis</u> FACU	9.			
Saplings/shrubs		Woody v	ines		
4. Lindera Denzo	in FACW-	10.			
5. Carpinus carolin	iana FAC	11.			
6. Hamamelis virgi	niana FAC-	12.			
I of species that ar	e OBL, FACW, and/	or FAC:	50% Other i	indicators:	<u> </u>
Hydrophytic vegetati	on: Yes 🔀 No	Ва	asis:		<u> </u>
A	/				

Series and phase: ///////// On hydric soils list? Yes; No;	<u>×</u> .
Mottled: Yes ×; No Mottle color: 2.57 4/2; Matrix color: 54R	48
Gleyed: Yes X No Other indicators:	
Hydric soils: Yes X No ; Basis: Mottled and glaged Soilindi	<u>cators</u>

### Hydrology

]

Û

Ŭ

Inundated: Yes\_\_\_\_; No\_\_\_\_. Depth of standing water: Some in depressions\_. Saturated soils: Yes\_X; No\_\_\_\_. Depth to saturated soil:\_\_\_\_ Other indicators: None Wetland hydrology: Yes X; No \_\_\_\_. Basis: Standing water and Saturated. Atypical situation: Yes \_\_\_; No \_\_\_\_. Soil. Normal Circumstances? Yes X No\_\_\_\_. Wetland Determination: Wetland Yes; Nonwetland\_\_\_\_\_. Comments:

Determined by: Dave Tompkins / Joe Kopalek B2

#### WETLAND DETERMINATION

Applicant Name:	Application Number:	Project Name: Colesville Landfill
State: Date:	Y County: Broome Legal Description 4/16/92 Plot No.: E 7	
	/ •	· · · · · · · · · · · · · · · · · · ·

Vegetation [list the three dowinant species in each vegetation layer (5 if only 1 or 2 layers)]. Indicate species with observed morphological or known physiological adaptations with an asterisk.

Indicator		Indicator
Species Status	Species	Status
Trees	Herbs	0
1. Fraxings amoricana FACU	7. Symplocarpi	is toetidus OBL
2.*Acer rubrum FAC	8. Viola spr	<b>)</b> .
3. Tsuca canadensis FACU	9.	
Saplings/shrubs	Woody vines	
4. Carpinus caroliniana FAC	10.	
	11.	·
	12.	
% of species that are QBL, FACW, and/		
Hydrophytic vegetation: Yes Y No	Basis: <u>&gt;50%</u> are F	of plant species.
<u>So11</u>		
Series and phase: howange - Silly Sand	On hydric soils 11	st? Yes; No_X.
Series and phase: <u>how sugars</u> Mottled: Yes X; No	color: red-brown; M	atrix color: <u>7.54 5</u>
Gleyed: Yes No X Other ind	icators:	
Hydric soils: Yes X No ; Bas	is: Mottled Soil C	ondition
Hydrology		
Inundated: Yes $\chi$ ; No Depth		
Saturated soils: Yes; No	Depth to saturated	soil: <u>Surface</u> .
Other indicators: fouring_ we	iter (slow)	•
Wetland hydrology: Yes X; Ny	. Basis:	·
Atypical situation: Yes_; $N_{\psi}$	÷	
Normal Circumstances? Yes No		
Wetland Determination: Wetland	(; Nons	vetland
Comments:		

B2

Determined by: Dave Tompkins / Joe Kopalek

# WETLAND DETERMINATION

Applicant Name:	Application	Project Name: <u>Colesville</u> Landfill
State: NY Con	nty: Broome_Legal Description:	Township:Range:
Date: 4/6/92	Plot No.: Upland between E and F wetlands	Section:
	E and F wetlands	
Vegetation [list th	e three <u>dominant</u> species in each	vegetation layer (5 if
- lu l an l levens	Teddooro encodoo udah ohoomu	d mamphalaniani an known

only 1 or 2 layers)]. Indicate species with observed morphological or known physiological adaptations with an asterisk.

-

and the second

.

A LOUGH

U

U

J

	Indicator		Indicator
Species	Status	Species	Status
Trees	-	Herbs	
1. Acer rubrum	FAC	7.	
2. Quercus rubra	FACUS	8.	
3. Fraxinus ameri	cana FACU	9.	
Saplings/shrubs	-	Woody vines	
4. Carpinus carolin	niana FAC	10. Gaultheria	procumbens FACU
5. Fagus granditoli	a FACU	11.	
6. Pinus strobus	FAC U	12.	
% of species that ar	e OBL, FACW, and/	or FAC: <u>&lt;50</u> % Other	indicators: <u>None</u> .
Hydrophytic vegetati	on: Yes No	X Basis: <50 %	o of plant species.
		are FA	corwetter.
<u>Soil</u>	1		
Series and phase:	enango-Sandy lour	<b>4On hydric soils li</b>	st? Yes; No_ $X$ .
Mottled: Yes;	No <u>×</u> . Mottle	color:; M	atrix color: <u>Yellow - Arown</u>
Cloved: Yes N	a V Other ind	icatore:	
Hydric soils: Yes	<u>Νο χ</u> ; Bas	is: No mottling o	r glered condition.
	•		<i>.</i> ,
Hydrology			
			None observed.
Saturated soils: Ye	s; No_ <u>√</u> .	Depth to saturated	soil: Now abserved
Other indicators:			·
Wetland hydrology:	Yes; No	. Basis:	·
Atypical situation:	Y <b>es;</b> No_∠	.•	
Normal Circumstances	? Yes No_🔀		,
<u>Wetland Determinatio</u>	n: Wetland	; Nony	retland 18 .
Comments: Hrea	is a souther	rn slope.	
		Determined by: Da	ve Tompkins / Joe Kopalek
	-	2	

### WETLAND DETERMINATION

Applicant Name:	Application Number:	Project Name: Colesville	Landfil
State: $NY$ County Date: $4//92$	Broome Legal Description: Plot No.: <u>G194</u> Wolland	Township: Range:	•
Vegetation [list the t	hrec dominant species in each	vegetation layer (5 if	•

only 1 or 2 layers)]. Indicate species with observed morphological or known physiological adaptations with an asterisk.

	Indicator		Indicator	
Species	Status	Species	Status	
Trees	Her	bs	Salidua Del	
1. Carpinus carolini	ana FAIC	7. Symplocarpu	stockidus OBL	_
2. Acer rubrum		8. Juncus ettu	sas FACWt	1
3. Jassafras albid	um FACU-	9. Carex Spp.		
Saplings/shrubs	Woo	dy vines		1
4. Carpinus carolinia	na FAC 1	.0.		
5. Ilex verticula	FACINT	.1.		_
		.2.		
% of species that are	OBL, FACW, and/or F	AC: >50% Other i	Indicators: Hummoul veg	etatte.
Hydrophytic vegetation	n: Yes <u>X</u> No			5
		is li	sted as FAC or we the	
Soil	11			_
Series and phase: B	raseville on	hydric soils list	? Yes; No	
Mottled: Yes $\chi$ ; N	o Mottle cold	or: Red ; Mat	rix color:	
Gleyed: Yes_X_ No	Other indicat	cors: Gray Gl	Vine	
Hydric soils: Yes	(; Basis:;	Soil mothed	2 Gleged.	
<i>'</i>		,		
Hydrology				
Inundated: Yes X;	Nc Depth of	standing water:	<u> </u>	
Saturated soils: Yes				1
Other indicators:				
Wetland hydrology: Y	es_X_; No 1	Basis: Satura	let soil and Standing u	an.
Atypical situation:	Yes X; No.		5	
Normal Circumstances?	Yes X No /.			
Wetland Determination	: Wetland 105	; Nonwe	tland	
Comments:				
		_		
	De	etermined by: <u>Dave</u>	Tompkins / Joe Kopali	:K 📕

#### WETLAND DETERMINATION

Applicant	Application	Project
Name:	Number:	Name: <u>Colesville</u> Landfill
	Plot No.: <u>H</u> - 2 (wetland)	

Vegetation [list the three dominant species in each vegetation layer (5 if only 1 or 2 layers)]. Indicate species with observed morphological or known physiological adaptations with an asterisk.

ſ

ŀ

Ĺ

Ĺ

IJ

IJ

IJ

U

U

	Indicator			Indicator	
Species	Status		Species	Status	
Trees		Herbs			
1.		7.	Solidago	SAO.	
2.	· .	8.			
3.		9.			
Saplings/shrubs		Woody	vines		
4. Salix discolor	FACW	10.			
4. Salix discolor 5. Cornus stolonitor	FACUT	11.			
6. Spirea alba	FACULT	12.			
Z of species that are	OBL, FACW, and/o	or FAC		indicators: edge of streer plant species das FAC or wetter	n
Hydrophytic vegetation	1: Yes <u>X</u> No		Basis: >50%	plant species.	
			liste	das FAC or wetter	
<u>Soil</u>		1			
Series and phase:	nd (hipppup (4. A)	On hyd	dric șoils li	st? Yes_X; No	
Mottled: Yes; No	Mottle (	color:	Red ; M	atrix color:	
Gleyed: Yes No	X Other ind:	icator	B:	·	
Hydric soils: Yes $\chi$	No; Bas:	1s: Hy	dric soils lis	st and muttling.	
		///		0	
Hydrology					
Inundated: Yes;	No <u>X</u> . Depth	of st	anding water:	None	
Saturated soils: Yes	<u>; No</u> .	Depth	to saturated	soil: le inches.	
Other indicators: AM	a adjused	40 - La	wine Amen	<b>)</b> .	
Wetland hydrology: Ye	es; No	. Bas	1s: <u>Satura</u>	da seis	
Atypical situation:	(es; No	·		/	
Normal Circumstances?	Yes X No	<u> </u>			
Wetland Determination	: Wetland	<u>    X  </u>	; Nonw	vetland	
Comments:		/			

Determined by: Dave Tompkins / Joe Kopalek

•

# WETLAND DETERMINATION

Applicant Name:	Application Number:	Project Name:	
	come Legal Description		
	Voland		
Vegetation [list the :hree	dominant species in each	vegetation la	ayer (5 if
only 1 or 2 layers)]. Indi	cate species with obser	ved morphologic	al or known
physiological adaptations w	vith an asterisk.		
Indic Species Stat		_	lcator atus
Trees	Herbs		
1. THEY TROTTE	re 7. Solia		
2. Botula lenta FA	8. Aster	spp.	
3.	9.		
Saplings/shrubs 4. Quarces alba FH	CU- Woody vines		
	-1.1.F		
J. (17/14)			
6.	12.		/
Z of species that are OBL,		_	
Hydrophytic vegetation: Ye	es No _X. Basis:	<50% of 2	specic ore.
	/	EAC or m	etter
<u>Soil</u>			
Series and phase: Minan			
Mottled: Yes; No			lor:
Gleyed: Yes NoK		Vone	··
Hydric soils: YesN	$p_{\star}; Basis: No h$	drie in die	ators.
	preser	~+.	
Hydrology			
Inundated: Yes; No	$\underline{X}$ . Depth of standing	water: 101h	<u>·</u>
Saturated soils: Yes	; No $X$ . Depth to sat	urated soil: <u>//</u>	ine observed.
Other indicators: //ohu			•
Wetland hydrology: Yes	; No X. Basis: No	Standing un	les or .
Atypical situation: Yes	$_; No \underline{\Lambda}$ . Sat	when soil C	MOLT TO US.
Normal Circumstances? Xes			(100
Wetland Determination: We	tland	; Nonwetland	yes
Comments:			/
		$\cap \top$	
	Determined	by: the lomp	Kins/Joe Kopalek
	· B2		· •

í

B2



Figure 1: North-facing view of Wetland A shows open water area, emergent zone, and scrub/shrub area (left).



Figure 2: East-facing view of Wetland A. Dominant herbaceous plants in the emergent zone include wool grass, sensitive fern, and soft rush.

Ĵ

]

J

]



Figure 3: Close-up of small tributary comprising Wetland B. Shrubs are pussy willow and red-osier dogwood. This wetland ranges from two to several feet wide.



Figure 4: Photograph shows Wetland B descending down the Landfill along tree line.



Figure 5: Part of Wetland E. This area is similar to photo described below. Shade in foreground is caused by dense hemlocks which prevail further down the slope.



Figure 6: Part of Wetland F located on south-facing slope below the Landfill. Surface soils are black muck. The most common herbaceous plant is skunk cabbage. Dominant trees are red maple and hornbeam.





Ĩ.

Figure 7: Soil sample showing commonly encountered gleyed and mottled colors. This soil sample was retrieved from Wetland A.

# BORROW AREA WETLANDS PHOTOGRAPH DESCRIPTION

- #1. Continuation of stream corridor (facing north) from wetland B. Location of outlet from wetlands BWA and Z on right.
- #2. Photo taken near flag Z6B (east). Wetland in this area is restricted to just stream channel. Shrub area in background is a larger wetland area.
- #3. Upland area facing south from flag Z9A.
- #4. Larger flat wetland area near flag Z12A. This is the only area where significant herbaceous vegetation is present. Some disturbance (test pits) is visibly nearby.
- #5. Upgradient section of wetland Z-2.





DATA FORM ROUTINE WETLAND DETERMINATION (1987 CCE Wetlands Delineation Manual)

\*

Project/Site: Colesville - Bonow Area	Date: i x/14/9_3
Acolicant/Cwner:	County: <u>Broome</u>
Investigator: D. Tompkins	State: NY
Do Normal Circumstances exist on the site? Is the site significantly disturbed (Atypical Situation)? Yes No Is the area a potential Problem Area? Yes No (If needed, explain on reverse.)	Community ID: Transect ID: Plot ID: TH1

#### VEGETATION

.

17

.

. •

· .

.

Dominant Plant Species Stratum Indicator 1. Acer rubrum OS Fac 2. Pinus Strobus US FACU 3. Hamomelis Virginiana Shr FAC - 4. Betula lenta Shr FACU 5. Connus Stalonifera GL FACU 6. Onoclea Sensibilis GL FACU 7. Solidaro spp. GL -	Dominant Plant Scecies         Stratum         Indicator           9					
8. unidentified grass GL - Percent of Dominant Species that ere OBL. FACW or FAC (excluding FAC-).	16.					
Romerks: No woody vegetation within 3-5 meters. Goldenrod and grass (clear dominant speries) not identificable in present condition, but only seen to be in wetland.						

#### HYDROLOGY

...

Recorded Data (Describa in Remarks): Stream, Lake, or Tide Gauge Aerial Photographs Other No Recorded Data Available Field Observetions: Depth of Surface Water: Depth to Free Water in Pit: Cepth to Saturated Soil: Cepth to Saturated Soil:	Wetland Hydrology Indicators: Primary Indicators: Inundated Seturated in Upper 12 Inches Water Merks Drift Lines Sediment Deposits Dreinege Patterns in Wetlands Secondary Indicators (2 or more required): Oxidized Root Channels in Upper 12 Inches Water-Stained Leaves Local Soil Survey Data FAC-Neutral Test Other (Explain in Remarks)
Remarks: Fle present on ground	l surface

SOILS

Map Unit Name (Series and Phase): Taxonomy (Subgroup):		Drainage ( Field Obse Confirm	
$\begin{array}{c c} \frac{\text{Profile Description:}}{\text{Deptn}} & \text{Matrix Color} \\ \frac{\text{(inches)}}{\text{(inches)}} & \frac{\text{Horizon}}{\text{(Munseil Moist)}} \\ \hline 0 - 8 & A - 10 \text{YR} \frac{3/1}{3/1} \\ \hline & & \\ \hline 8 - 19 & B & 10 \text{YR} \frac{4/2}{3} \end{array}$	Mottle Colors Munsell Moisti NA 7.5 ViR 5/8	Mottle <u>Abundance/Contrast</u> NA Lommon	Sardy Clay
		throughout	
Hydric Soil Indicators: — Histosol — Histic Epipedon — Sulfidic Odor Aquic Moisture Regime Reducing Conditions Gleyed or Low-Chroma Colors		ncretions In Organic Content in Si ganic Streaking in Sandy ted on Local Hydric Soil ted on National Hydric S her (Explain in Remarks)	s List Soils List
Romarks: difficult to accor routs present to	approx 8	ien nursell "depth	Color, too cloudy

#### WETLAND DETERMINATION

Hydrophytic Vegetation Present? Wetland Hydrology Present? Hydric Soils Present? Yes No Yes No	(Circle) Is this Sampling Point Within a Wetland? Yes No
Romarks: Wetland represents a the sloping landscope.	in consider accorning on a

Approved by HOUSACE 3/92

DATA FORM ROUTINE WETLAND DETERMINATION (1987 CCE Wetlands Delineation Manual)

Project/Site: Colesville-Bonow Area Applicant/Owner: Investigator: D. TompKins		Date: 12/1 County: 310 State: 1	y/93
Do Normal Circumstances exist on the site? Is the site significantly disturbed (Atypical Situation)? Is the area a potential Problem Area? (If needed, explain on reverse.)	Yes No Yes No Yes No	Community ID Transect ID: Plot ID:	<u> </u>

### VEGETATION

. .

Dominant Plant Species Stratum Indicator	Dominant Plant Soecies Stratum Indicator
1. Acar rubrum OS FAC	9.
2. Pinin strobus US FACU	10
3. Frazinus Americana Shr FACU	11
4. Fagus grandifolia Shr FACU	12
5. Rubus flagellaris GL NI	13
5. Lycopadium clavatum GL FAC	14
The copodium observen GL FACU	15
8. Dryopteris Spinulosa GL FACT	16
Percent of Dominant Species that are OBL, FACW or FAC (excluding FAC-).	3/0 = 38%
Romarks: Higher elevations are do	minated by Acer Saccharimin (FAR
Faith developed woody ground	minated by Acer Saccharimin (FAR)

#### HYDROLOGY

• • •

Recorded Data (Describe in Remarks): Stream, Lake, or Tida Gauge Aerial Photographs Othar No Recorded Data Available	Wetland Hydrology Indicators: Primary Indicators: Inundated Saturated in Upper 12 Inches Water Merks Drift Lines
Field Observations:Depth of Surface Water:Depth to Free Water in Pit: $21$ (in.)Depth to Saturated Soil:	NOVE Sediment Deposits Drainege Patterns in Wetlands Secondary Indicators (2 or more required): Oxidized Root Channels in Upper 12 Inches Water-Stained Leaves Local Soil Survey Data FAC-Neutral Test Other (Explain in Remarks)
Remerks:	

-

SOILS

Map Unit Name (Series and Phase):	Crainage Class: Field Observations Contirm Mapped Type? Mes No
$\begin{array}{c c} \hline Drofile Cescription: \\ \hline Deptn \\ \hline Munsel Moist! \\ \hline O \\ \hline O \\ \hline A \\ \hline A \\ \hline B \\ \hline B \\ \hline B \\ \hline G $	Mottle Cajors Munseil Moisti Mottle Abundance:Contrast Texture, Concretions, Structure, etc. Orgonic Claype silt SVR 5/8 Slight Clay J
Hydric Soil Indicators: — Histosol — Histic Epipedon — Sulfidic Odor — Aquic Moisture Regime — Reducing Conditions — Gleyed or Low-Chroma Colors Remarks:	Concretions High Organic Content in Surface Layer in Sandy Soils Organic Streaking in Sandy Soils Listed on Local Hydric Soils List Listed on National Hydric Soils List Other (Explain in Remarks)

#### WETLAND DETERMINATION

Hydrophytic Vegetation Present? Wetland Hydrology Present? Hydric Soils Present?	Yes (No) (Circ Yes (No) Yes (No)	ls this Sempling Point Within a Wetland?	(Circle) Yes No
Remarks:		· · · · · · · · · · · · · · · · · · ·	

Approved by HQUSACE 3/92

# APPENDIX B WETLAND A VERTICAL LEAKAGE ESTIMATE

.

By GHM LDate 1/26 JOB NO. 12260 EC WEHRAN ENGINEERING Chkd. by Date 1127 NS Engineers & Scientists Subject Operville - Pre Final Engineering Sheet No.\_\_ Report ppen hix artica Wetland cokage in petrage in Wettend A, ► the vertical H can be determined based on Davcy's Law and internation 05 trined on-site mon foring wells trom e. Wfollow 5 1 - 10Hz-Hi there  $\mathbf{u}$ 1ertical Teakage through up por alacal 1.41 permeability of appe KE AVErage clacia site Monitoring wells measuredin On-Hi li and W-10 W+Q 10-7 water table elevation in Н. present da nn - si ta monitoring well w-10 1015.71 44 water sur face elivation setland A in 1016.80 ft Thickness of glacial till layer underlying Wetland A as determined from boring log of monitoring well W-10 311+1 = surface area of Wetland A = 33, 119 59. 64. Accordingly: apresent = 3.5 × 10-5 Ft /min (1015.71-1062.8041) 37 day 20,583 Gallous / day 7 -0.62 gallows day / 42

1945 - A**R** 

0

**D** 

Ĵ

D.

O

Ū.

0

Ŋ

Ø

Ø

JOB NO. ULLOU.E Chkd. by Gold Date 1135 Subject Lale Sville nt No. 7 eroA Subject An estimate of the leakage rate 20 - years in 11\_ in Wetland A is given by: 1/4 sed upon (Hz-d)-H, X·= When drawdow n = 44 Accordingly : 2.5×10 4/min ((1015.71-4)-1066.80(+) = 2.2, 184 gallows / day i l ) = 0.67 gallons / day / 6+2 The ground water recovery system for 20 - years will have on the pakage pate from wetland at is given by TT\_ Gzv-year - a precent = A day 31 where A = change is lealing rate Accordingly: A = 22, 194-20 = 83 ][ = 1611 gallons/day = 0.049 gallow: / day/fFz = 7.8% increase in leatrage rate Ţ

# APPENDIX C WATER BUDGET FOR COLESVILLE, NEW YORK

# Water Budget Estimate Colesville Landfill Compensation Wetlands Site

Water budget estimates were developed for the proposed Compensation Wetlands adjacent to the Colesville Landfill, Broome County, NY. Monthly water budget values were calculated based on temperature and precipitation data from Binghamton, NY. Estimates of potential evapotranspiration used in the budget were calculated by the Thornthwaite and Mather method (Thornthwaite and Mather, 1957). The budget form calculates monthly output values for: soil moisture storage, surplus, actual evapotranspiration and soil moisture deficit.

Water budget calculations require assumptions on the amount of water in the soil available for loss to the atmosphere (soil moisture capacity) and the ease with which this water may be withdrawn from the soil (soil moisture depletion function). The estimate of soil moisture capacity was based on data on typical bulk density and porosity data for hydric soils. Generally hydric soils have about 45% of their volume available for water storage at saturation. Rooting depth in wetland soils is typically limited to within the upper 15 inches of soil and this therefore corresponds to 6.85 inches of soil moisture storage from saturation. This corresponds to the available soil moisture capacity of 36 inches of Volusia soils (data from the Broome County Soil Survey) for unsaturated conditions. The soil moisture depletion function for heavy silty soils was used as an approximation of the Volusia soils.

Water budgets were run for average weather conditions of the last 20 years and the wettest (1976) and driest year (1964) within this period. Under average conditions there is a surplus of water (for runoff) through April. Then there is a drawdown of soil moisture reaching a maximum of 10 inches in soil depth in August. Recharge begins in September and is completed by October, when there is again a surplus of water. Under the wettest year conditions, the maximum soil moisture drawdown was to a depth of 1.5 inches. In contrast the driest year brought a drawdown of 11.8 inches in August. The estimated drawdown from this range of climatic extremes can be seen to be within an acceptable rooting depth range for wetland forest and shrub species.

The water budget estimates above do not account for an input of surface water from the watershed above the proposed wetland compensation area. The compensation wetland plan calls for the input of surface water to the wetland basin, whose elevation is set by the basin outfall elevation. Monthly estimates were made of stream flow for the project area watershed (borrow area and a portion of the landfill) from stream flow data for Newtown Creek at Elmira, NY (provided by USGS). These data suggest that under average conditions, 13.1, 7.1, and 6.0 ft. of water (for a 1 acre wetland/pond basin) is available each month during June, July and August respectively. During the driest year (1964) these months were estimated to have corresponding values of 4.2, 2.9, and 1.8 ft. for the months June July and August.

It can be seen from these estimates of soil moisture drawdown from the water budget and stream flow input additions, that sufficient hydrology should be available for wetland conditions. This is also based on the assumption that infiltration rates for the wetland/pond basin will be sufficiently low.

# WATER BUDGET CALCULATIONS

Colesville, NY

YEAR IS AVERAGE

MO	TEMP	UPE	APE	PREC	DIFF	ST	DST	AE	DEF	SURP
1	-3.6	0	0	65	65	174	0	0	0	65
2	1.3	2	2	59	57	174	0	2	0	57
3	4.8	14	14	75	61	174	0	14	Ō	61
4	11.9	46	52	78	26	174	0	52	0	26
5	20.2	94	118	81	-37	141	-33	114	4	0
6	20.6	96	122	91	-31	118	-23	114	8	0
7	21.8	104	133	88	-45	91	-27	115	18	0
8	22.1	106	126	85	-41	72	-19	104	22	0
9	20.1	93	96	84	-12	67	-5	89	7	0
10	12.1	47	45	76	31	98	31	45	0	0
11	4.7	13	11	77	66	164	66	11	0	0
12	1.2	2	2	74	72	174	10	2	0	63
YEAR	LY TOTAI	S	720	933				661	59	272

# TERMS

UPE = UNADJUSTED POT. EVAPO	PREC = PRECIPITATION
APE = POTENTIAL EVAPOTRANSPIRATION	SURP = SURPLUS (RUNOFF)
AE = ACTUAL EVAPOTRANSPIRATION	$TEMP = TEMPERATURE \cdot$
DST = CHANGE IN SOIL STORAGE	DIFF = PREC-APE
ST = SOIL MOISTURE STORAGE	DEF = DEFICIT (APE-AE)

-


# WATER BUDGET CALCULATIONS


# Colesville, NY


YEAR IS 1976


MO	TEMP	UPE	APE	PREC	DIFF	ST	DST	AE	DEF	SURP	
1	-8.4	0	0	94	94	174	0	0	0	94	
2	<b></b> 9 <sup>°</sup>	0	0	73	73	174	0	0	0	73	
3	1.9	9	9	71	62	174	0	9	0	62	
4	8.3	40	44	68	24	174	0	44	0	24	
5	11.6	57	71	64	-7	167	° <b>-</b> 7	71	0	0	
6	19.4	97	123	112	-11	157	-10	122	1	0	
7	18.7	93	120	163	43	174	17	120	0	26	
8	18.6	93	110	172	62	174	0	110	0	62	
9	14.1	69	72	<b>98</b>	26	174	0	72	0	26	
10	6.5	31	29	160	131	174	0	29	0	131	
11	5	0	0	28	28	174	0	0	0	28	
12	-6.5	0	0	43	43	174	0	0	0	43	
YEAR	LY TOTA	LS	578	11 <sub>1</sub> 46				577	· 1	569	
YEAR	IS 1964	l									
MO	TEMP	UPE	APE	PREC	DIFF	ST	DST	AE	DEF	SURP	
1	-4.4	0	0	76	76	174	27	0	0	49	
2	-7.3	0	0	51	51	174	0	0	0	51	
3	1	0	0	116	116	174	0	0	0	116	
4	6.1	27	30	129	99	174	0	30	0	99	
5	14.7	70	88	51	-37	141	-33	84	4	0	
6	16.7	81	102	31	-71	93	-48	79	24	0	
7	21.3	106	136	122	-14	86	-7	129	7	0	
8	18.4	90	107	47	-60	61	-25	72	35	0	
9	16.2	78	<b>8</b> 0	17	-63	42	-19	36	45	0	
10	9.1	41	39	27	-12	39	-3	30	9	0	
11	6.1 <sup>,</sup>	27	21	48	27	66	27	21	0	0	
12	-2.2	0	0	81	81	147	81	0	0	0	
YEARI	LY TOTAI	LS	603	7;96				481	123	315	1

-












\_\_\_\_ Stream flow BASED ON USGS DATA \_\_\_\_ SURP BASED ON WATER BUDGET



÷.





## **REMEDIAL DESIGN PROJECT**

# Wetland Survey Coordinates

	<u> </u>	-
Location	Northing	Easting
Z27B	788697.2720	771226.6785
Z17B	788707.8619	771222.8570
Z268	788735.1807	771271.7693
Z18B	788775.6505	771297.8734
Z 1 9B	788829.5800	771346.7255
Z248	788852.5495	771375.6420
Z20B	788858.0126	771374.5358
Z21B	788872.0310	771422.4085
Z21B	788926.0058	771480.7839
Z23B	788872.4279	771422.4881
Z25B	788777.3791	771318.3158
SPKJC	788773.6623	771140.8853
TNW	788742.4969	771155.0083
¥1	788542.9432	771079.5897
Y2	788632.0721	771012.5161
Y3	788614,9089	770993.0040
ТРРКВ	768607.2083	770998.1730
Y10	788608.5638	771034.7033
Y9	788561.7428	770966.4230
Y8 ·	788589.4258	770920.1916
Y7	788565.2290	770859.3101
Y7A	788550.5900	770815.8879
Y6A	788554.7737	770807.0686
YS	788581.5962	770860.9848
Y5	788618.3780	770905.2643
¥4	788620.9374	770955.8878
P-1	788992.9323	771216.9462
P-2	788992.7925	771204.9661
P-53	788966.5759	771215.5280
P-52	788962 <b>.68</b> 78	771216.3855
P-54	788966.4190	771205.9183
P-51	788962.0628	771200.2625
P-3	788961.3400	771192.6956
P-4	788953.2300	771188.1027
P-5	788937.0096	771173.1735
P-50	788932.5036	771175.3975
P-49	788915.2811	771127.6853
P-6	788918.3110	771125.8609
P-7	788918.1292	771096.1902
P-48	788908.8537	771093.4828



# **REMEDIAL DESIGN PROJECT**

# Wetland Survey Coordinates

_		
Location	Northing	Easting
P-47	788911.3039	771067.2462
P-8	788912.3267	771056.9424
P-9	788899.0547	771022.2258
P-46	788896.3326	771025.8280
P-10	788874.0610	770990.5684
P-45	788859.5648	770991.7980
P-11	788850.7973	770973.4876
P-12	788819.3616	770936.4771
P-44	788805.8310	770930.2823
P-43	788789.7016	770914.1590
P-13	788784.2731	770899.2714
P-42	788743.6460	770873.4670
P-14	788732.3860	770857.2007
P-41	788708.2185	770853.4793
P-15	788680.0596	770833.1042
P-40	788644.3280	770825.9919
P-39	788623.3379	770820.8942
P-16	788625.3124	770815.2067
P-17	788597.6059	770797.6080
P-18	788562.3295	770785.1546
P-38	788569.4720	770798.7770
P-37	788535.7885	770785.2855
P-19	788518.2380	770775.2852
P-36	788494.0447	770771.6455
P-35	788483.1380	770760.9295
P-34	788461.3044	770757.9936
P-20	788471.8354	770750.5726
P-33	788438.8686	770749.8306
P-21	788392.3107	770720.6886
P-32	788378.8648	770737.6713
P-22	788324.4647	770692.5633
P-31	788296.1777	770707.8103
P-23	788265.4221	770679.2749
P-30	788260.7530	770685.0857
P-29	788241.8895	770689.3702
P-28	788225.1700	770705.5158
P-24	788219.8391	770695.5805
P-28	788192.7565	770710.9973
P-25	788173.1403	770712.8768

# REMEDIAL DESIGN PROJECT

# Wetland Survey Coordinates

Location	Northing	Easting
Z49A	788113.1723	771160.7974
Z50A	788164.8692	771135.0989
Z51A	788229.7370	771140.4222
Z52A	788259.7418	771163.0827
Z53A	788293.8852	771212.2412
Z54A	788332,6990	771222.6832
Z55A	788391.6227	771269.5053
Z56A	788385,9821	771282.1589
Z57A	788408.6676	771322.9941
Z58A	788428.7123	771331.9578
Z59A	788427.5400	771323,2036
Z52A	788290.6447	771153.8355
Z34B	788279.8007	771096.5845
Z338	788298.5817	771053.9602
Z9B	788312.1600	771028.8500
TPPKS	788391.0528	770994.4595
Z328	788346.8163	771058.8375
Z31B	788428.9124	771057.5064
Z30B	788554.6964	771129.8973
Z14B	788561.8676	771113.8063
Z13B	788509.3933	771086.7602
Z12B	788434.6293	771035.1426
211B	788378 5254	771011.2799
Z10B	788348.2218	771003.3478
BWA3B	788387.6414	770929.8443
BWA4B	788332.4938	770883.8282
BWASA	788308,5431	770840.5705
BWA4A	788352.6429	770879.4976
BWA3A	788396.9745	770912.1005
BWAZA	788454.3665	770955.5700
BWA2B	788454.1029	770969.6375
BWA1AB	788504.9583	770998.5367
ТРРКБ	788640.8562	771172.7430
ТРРК7	788690,9086	771204.7614
Z15B	788579.6598	771154.2251
Z29B	788609.1210	771187.8261
Z28B	788644.8206	771227.6745
Z16B	788653.2364	771202.4554
Z27B	788697.2720	771226.6785

#### **REMEDIAL DESIGN PROJECT**

# Wetland Survey Coordinates

Location	Northing	Easting
BWA8B	788193.3181	770791.5978
BWA7B	788208.8139	770803.7244
BWA7A	788216.8646	770796.2558
BWATH1	788240.6462	770814.5802
BWA6B	788234.1729	770822.6612
BWAGA	788248.6808	770807.7144
BWASB	788294.3576	770851.7477
TPTJ1	788164.0645	770892.8449
BWA9A	788133.2057	770776.7330
BWASA	788185.7365	770786.4822
Z2B	788137.0169	770828.0312
Z2A	788141.1484	770841.2602
Z3A	788150.3856	770848.5149
Z3B	788155.9508	770843.3578
Z4B	788178.0139	770870.1902
Z4A	788178.3451	770885.5214
Z 5B	788209.3830	770904.3965
Z5A	788199.9401	770907.1175
Z6B	788238.9912	770946.3911
ZGA	788224.1403	770950.6684
Z7A	788247.5727	770980.6479
Z7B	788258.0401	770985.5309
Z8B	788272.7570	771019.1868
Z8A	788265.8564	771033.0281
TPTJ2	788177.0662	771087.0290
Z9A	788266.4353	771041.7466
Z10A	788234.8925	771087.3906
Z11A	788225.5664	771097.7529
Z12A	788169.9858	771053.1700
Z13A	788162.0899	771092.1788
Z 1 4A	788100.3500	771127.7697
Z40A	787985.8933	771165.3752
Z41A	788055.8294	771189.6080
Z42A	788101-0392	771229.6728
Z45A	788139.5868	771354.6973
Z44A	788124.8956	771354.9728
Z 46A	788132.4825	771288.6653
Z43A	788110.6034	771284.8364
Z47A	788124.4517	771243.5911
Z48A	788116.3483	771200.6375



# REMEDIAL DESIGN PROJECT

# Wetland Survey Coordinates

Location	Northing	Easting
P-27 P-26	788158.7475 788155.8519	770722.8278 770714.0058
1 20		~

- .

·

.

### APPENDIX B STABILITY AND SETTLEMENT ANALYSIS

CROSS-SECTION AA SETTLEMENT CALCULATIONS

#### \*\*\*\* INPUT DATA \*\*\*\*


LIFT TIME TIME AND	THICKNESS C ASSUMED FOR		RESSION		4 4.0 .25 8.00 .00	YRS	
BEYOND	THE OPERATI	ONAL LIFE OF	EXPANSION:				
	EMENTS COMI INTERVALS S	PUTED UPTO SETTLEMENTS CC	MPUTED	= =	30.00 30.00		
WASTE P	ARAMETERS:				•		
COEFF COEFF UNIT UNIT	VICIENT OF S WEIGHT OF I WEIGHT OF I	PRIMARY COMPRE SECONDARY COMP EXISTING SOLID EXISTING FINAL PROPOSED CAPPI	RESSION WASTE COVER	= = = =		PCF PCF	
	RAMETERS:	NOI OBLD OATTI		-	12010		
COEFF		COMPRESSION		= =	.000	PCF	
THICKNE	SSES OF DI	FFERENT LAYERS	5:				
POINT NO.	PEAT THICKNESS (FT)	EXISTING WASTE THICKNESS (FT)	F. COVER	CAP			
1 2 3 4	.0 .0 .0	5.0 13.0 21.0 29.0	. 0 . C . 0 . 0	4.( 4.( 4.( 1.)	)		

#### \*\*\* SETTLEMENTS DURING CAPPING \*\*\*\*

POINT NO.	PEAT CONSOLD. (FT)	ELASTIC SETTLMT. (FT)	FRIMARY COMPRES. (FT)	SECONDARY COMPRES. (FT)	TOTAL SETTLEMENT (FT)
1 2 3 4	.00 .00 .00	.10 .27 .44 .60	.29 .42 .48 .51	.00 .00 .00 .00	.40 .69 .91 1.11

# \*\*\* SETTLEMENTS 30.0 YEARS AFTER CAPPING \*\*\*\*

POINT NO.	SETTLEMENTS DURING CAPPING	SETTLEMENTS FOLLOWING CAPPING	TOTAL SETTLEMENT
	(FT)	(FT)	(FT)
1	.40	.13	.53
2	.69	.35	1.04
3	.91	.58	1.49
4	1.11	.80	1.91



CROSS-SECTION BB SETTLEMENT ¢ALCULATIONS

\*\*\*\* INPUT DATA \*\*\*\*

NUMBER OF SETTLEMENT POINTS LIFT THICKNESS OF PROPOSED CAP TIME ASSUMED FOR PRIMARY COMPRESSION TIME ELAPSE BETWEEN THE PRIOR CLOSURE AND PROPOSED CAPPING TIME REQUIRED FRO CAPFING		0.00	
BEYOND CAPPING:			
	= =	30.00 YRS 30.00 YRS	
WASTE PARAMETERS:		•	
STRAIN FACTOR COEFFICIENT OF PRIMARY COMPRESSION COEFFICIENT OF SECONDARY COMPRESSION UNIT WEIGHT OF EXISTING SOLID WASTE UNIT WEIGHT OF EXISTING FINAL COVER UNIT WEIGHT OF PROPOSED CAP	=	.100 .050 65.0 PCF	
PEAT PARAMETERS:			
COEFFICIENT OF COMPRESSION UNIT WEIGHT	=	.000 .0 PCF	

THICKNESSES OF DIFFERENT LAYERS:

POINT NO.	PEAT THICKNESS	EXISTING WASTE THICKNESS	EXISTING F. COVER THICKNESS	PROPOSED CAP THICKNESS
1	(FT)	(FT) 14.0	(FT)	(FT) 4.0
101 33	.0 .0	$   \begin{array}{c}     14.0 \\     21.0 \\     12.0   \end{array} $	.0 .0 .0	4.0 4.0


#### SETTLEMENT CALCULATIONS

\*\*\* SETTLEMENTS CAPPING \*\*\*\*

#### POINT PEAT ELASTIC PRIMARY SECONDARY TOTAL NO. CONSOLD. SETTLMT. COMPRES. COMPRES. SETTLEMENT POINT PEAT (FT) (FT) (FT) (FT)(FT) .00.29.00.44.00.23 .43 .48 .41 .00 .72 1 .00 .91 2 .00 .66 3

#### \*\*\* SETTLEMENTS 30.0 YEARS BEYOND REACHING FINAL GRADES \*\*\*\*

POINT NO.	SETTLEMENTS DURING CAPPING (FT)	SETTLEMENTS FOLLOWING CAPPING (FT)	TOTAL SETTLEMENT
1	.72	.38	1.10
2	.91	.58	1.49
3	.66	.33	.98



By <u>N</u> K Chkd. by Subject		<b>Wehran</b> EnviroTech	Job No	of

C	ROSS	5 - 5	4 6	T1	0 ~	AA

•	\$01N7	WASTE THICKNESS (FT)	COVER SOIL THICKNESS (FT)	TOTAL BETTLEMENT (Ft.)
	1	5	4	0,53
	z	13	ц, <sup>с</sup>	1.04
<b>445</b>	3	२।	4	1.49
	4	29	5	1.91

CROSS-SECTION BB

•	POIN 7	WASTE THICKNESS (FT)	COVER SOIL THICKNESS (FT)	SETTEMENT CFL)
•	i -	14	3	1.10
•	R	Q.I	4	1,49
•	Σ	12	4	0.98

.

NOTE: WASTE FILLING BETWEEN 1969-84

By	Date	
Chkd. by	Date	
Subject		

١

### SETTLEMENT - A ELEVATIONS

CROSS - SECTION AN


POINT	THITCH	FLEPELTRIJ SETTILEMENT	ENU Žlau
N	1046	0,53	1045.47
2	1054	1.64	1052.96
3	1058	1.19	1056.51
Ч	1061	),41	1059.09


Nichran Enviroliech Job No. \_\_\_\_\_ of \_\_\_\_

•

## CROSS-SECTION BB

١	1055	1.10	1053.90	:
2	1055	1.49	1053.51	
3	1055	0.48	1054.02	: 







# **COLESVILLE LANDFILL**

# **REMEDIAL INVESTIGATION REPORT**

**Prepared For** 

# **BROOME COUNTY DEPARTMENT OF PUBLIC WORKS**

**BROOME COUNTY, NEW YORK** 

And

# **GAF CORPORATION**

WAYNE, NEW JERSEY

**VOLUME 1 – REPORT** 

**APRIL 1988** 



-

#### 3.0 SITE HISTORY

#### 3.1 OVERVIEW

The Colesville Landfill is located in the Town of Colesville, Broome County, New York, just north of Doraville (see Figure 3.1.1). The area evaluated as part of this remedial investigation report is generally bounded by East Windsor Road to the west, and by unnamed streams to the north, east and south, and consists of approximately 113 acres. Of this area, only about 35 acres have been used for disposal of solid waste. A detailed description of the environmental setting of this area is presented in Section 5.0.

#### 3.2 LANDFILL OPERATIONS

Waste disposal operations commenced at the Colesville site in 1969. The landfill was owned and operated by the Town of Colesville between 1969 and 1971. Broome County took ownership of the site in 1971, and operated the landfill from 1971 to 1984. The landfill has been closed since 1984. Waste placement occurred primarily within excavated three trenches. Area landfilling was also performed in the northeastern portion of the site.

As part of this remedial investigation report, a review of available aerial photographs of the Colesville site was performed. This evaluation considered the extent and progression of historic landfill operations. The following photographs were analyzed utilizing stereoscopic projections, which allowed for a three-dimensional evaluation of site grading as related to onsite landfilling methods.

Photo Date	Scale	Approximate Disturbed <u>Area (%)</u>	Figure Number
July 4, 1955	1:1000	0	Figure 3.2.1
October 19, 1965	1:1000	6	Figure 3.2.2
May 26, 1977	1:1000	69	Figure 3.2. <u>3</u>
April 28, 1982	1:1000	96	Figure 3.2.4
November 23, 1987	1:500	100	Figure 3.2.5

10.4/88.07522

3-1

All photos were obtained from the United States Department of Agriculture (USDA), Aerial Photograph Field Office, Salt Lake City, Utah, with the exception of the 1987 photos, which were obtained from R. M. Keddal and Associates, Inc., Library, Pennsylvania.

A general description of site conditions over time based on these photographs, is as follows:

#### July 4, 1955

Pre-landfill conditions existed; qpen fields without scattered trees and no sign of excavations. This photograph indicates the fields were utilized for agricultural purposes (see Figure 3.2.1)

#### October 19, 1965

Some form of construction and/or disturbance had occurred. An access road had been built on western and northern perimeter of property. Excavations and stockpiling of material was evident along the north-central property line. The areal extent of disruption activities encompassed just over two acres. The farm fields were fallow, and it appeared that farming activities had ceased (see Figure 3.2.2).

#### May 26, 1977

The landfill was in full operation. The first active disposal trench is identified, running east to wes: through the center of the landfill property, with refuse piled at the western end. An active borrow area was located at the northeastern corner of the site. Access roads existed throughout the site with the major road ending at the refuse pile. The associated landfill area had increased to 24 acres (see Figure 3.2.3).

#### April 28, 1982

Landfill operations had continued. A second trench, running east to west, existed along southern border of property. The primary borrow area still appeared to be located on the northeast section. Disposal activities appeared contained only within the trench (see Figure 3.2.4).

10.4/88.07522

#### November 23, 1987

The landfill is closed (see Figure 3.2.5). Remnant access roads exist across site. A third, open trench exists running east to west along the southern border of landfill. Refuse is exposed on the north face of the trench (based on visual field examination). Borrow areas are now covered with vegetation.

In summary, landfill operations at the Colesville site began along the northern property border of the site, with refuse disposed of in east to west trending trenches. As trenches were filled, new trenches were excavated to the south, adjacent to active filling. A total of three trenches were identified. Borrow areas were identified on the north-central area during early landfill stages and in the northeast corner in later stages. Wastes appeared to be dumped in the trenches and then covered with borrow material from onsite sources. At no time did it appear that the limits of refuse exceed the property boundary. No major facility, such as an office or maintenance garage, was identified on the landfill property, although a small, shed-like structure exists along the western edge of the property. Overall, approximately 35 acres were used for landfilling purposes.

#### 3.3 WASTE DISPOSAL PRACTICES

Throughout its operational life, the Colesville Landfill was used for the disposal of municipal solid waste (MSW). Between 1973 to 1975, industrial wastes were also disposed of at the facility with concurrence of the NYSDEC.

Table 3-1 lists the nature of industrial wastes disposed of at the site along with the estimated amount of each waste type received per month.

Interviews conducted with site personnel familiar with landfill procedures at the time of operation, indicate that disposal practices were quite varied. For example, it has been reported that wastes received in drums were randomly codisposed of with MSW and disposed in segregated areas. Moreover, depending upon the particular operator on duty at the time the wastes were received, the drums were either buried intact, or punctured and crushed prior to burial.

10.4/88.07522

3-3

By <u>K?#</u> Date <u>11142</u> Chkd. by <u>Date</u>		WehranEnviroTech	Job No
Subject	ЗĘ.	Comesville LIANDFill	

#### SETTLE MIENT CROSS SECTIONS

- -----

USING BORING LOGS DRURLOP RALATIONSHIP BRTWREN RECORDED CONDUCTIVITY LEVIRLS AND ACTUAL WASTIC THICKNESS .

BORING LOCATION	CONDUCTIVITY LEVEL	WASTE DEPTH	CONDUCTIVITY/WASTEDEPTHO
PW-12	36	7.0	5.1
PW-13	33	15	2.2
N-1	42	27	1.6

- 3MMHOS/FT OF WASTE

-

\* EXAMPLE (UN:DUCTUITY ( BUTC OF 60 => 20' WASTE

PROJECT: (					esign				P	ROJECT NO:	02260HG		GS ELEV: A	
CLIENT: <i>BI</i>				F					R	IG: <i>CME-75</i>			1	r. <b>788,462.54</b> r. 769,640.70
		GROUP	OWATER	DATA (	leet)				CASING	SAMPLE	TUBE	CORE		N: 1064.3711.
DATE		<u>GW Dep</u>	TH (	GW ELEV	_	INTAKE		TYPE	HSA/steel	SS			1	ied: <b>1/7/92</b> Hed: 1/13/92
								DIAN	4"	2" 140#			OPERATOR	
			-					FALL		30"			geologist:	D.R.L./B.A.O.
WELL	ст	DEPTH (feet)	SAMPLE NUMBER	SAMPLE & TYPE	RECOVERY (feel)	N-VALUE	100	UNIFIED			DESCRIPTIO			REMARKS
	Æ	<u> </u>	1	$\square$	0.7	8			SOIL FILL Brown of SAN	0, little Silt	& Clay, trace	e (+) fm Grav	el, koose,	
	$\mathbf{k}$	E							moist.					
		-0	2	$\boxtimes$	0.8	40								
$\Box \vdash$	$\mathbb{R}$	40	3		0.0	27	· .							
	Æ		4	$\bigcirc$	0.3	100								
	N-	45	5	$\square$	0.0	50							0.	
	Į		6	$\bigotimes$	0.5	17			<u>REFUSE</u> w/ FILL, tire,	plastic, woo	d, paper, gla	ass, slight od	or, wet.	
		-20	7		0.4	20			@ 20" Saturat	ed.				
			8	$\bigotimes$	0.6	54								
	₽	-25	9	$\overline{\mathbf{A}}$	0.0	9								
	$\mathbf{k}$		ю	$\square$	0.2	28								
	$\mathbb{R}$	-30	Π	$\overline{\mathbf{X}}$	٤0	28						30	).0'	
	$\mathbb{F}$		12	$\square$	0.8 }	24			<u>TILL</u> Grayish-brow dense, moist.	n SILT & CI	ay and cf Si	and, little mf	Gravel, m	
		-35	13	$\boxtimes$	0.0	28	000		@ 37.0' Gravis	h-hrou- f-		f Graund Ara	<b>ce</b> ()	
			14	$\boxtimes$	18	24	000	1	e 37.0 Grays Silt, dry.		JANU, ILUE	, Gravel, ua	ue (-/	
¥∰ ₿	<b>P</b>	40	15	$\boxtimes$	13	20	`		GLACIAL OUT		_	. 40		Permanent 6" steel casing to 41D.g.s.
			16	$\boxtimes$	10	20			Gray fc SAND dry.		n Gravel, tra	ce (+) Silt, m	dense,	Switched from 4" Augers to 4" casing
		45	17 18	$\bigotimes$	10 0.7	17 25			@ 44.5' Beco	nes moisi.				41.
	:  E		19	$\bigotimes$	12	27								
		-50	20	$\bowtie$	0.9	24			e 50'Become: moist.	s Grayish-b	rown f SAND	and Silt, m o	iense,	
	:   -		21	$\square$	18	21	· · ·							
	:  E	-55	22	$\square$	2.0	39		1					i.Oʻ	

į

ļ

# Wehran EnviroTech

# BORING/WELL NO. PW-13

SHEET 2 of 2

								SHEET 2 of 2
PROJECT: COLESVILE CLIENT: BROOME COU	NTY/GAF	al Design		,		PROJECT NO: 02260HG		788,462.54
CONTRACTOR: EMPIRE	SOILS			<u> </u>	·	RIG: CME-75	E-W COORD:	769,640.70
WELL CONSTRUCT HIdad	SAMPLE NUMBER SAMPLE	S TYPE RECOVERY (feet)	N-VALUE	503	UNIF IED	FIELD DESCRIPTION (Modified Burmister)		REMARKS
-60 -60 -65 -70 -70 -75 -80	5 ₹ 24 25 26 27 28 29 30 31 32 33 34	5 w ₩ = 11 1.4 1.3 1.6 1.5 1.3 1.4 1.6 1.7 1.9	2 57 39 50 39 52 39 61 26 36 39 53		3	© 80'becomes Brown laminated SILT and f Sa © 84' Brown f SAND and Silt grading to Light SILT and f Sand, w/ f Sand partings. © 70' Brown SILT and f Sand, soft, dense, lat w/<0.25'' Clay seam © 715'. © 78.0'Green-brown SILT, some (+) f Sand, s Red Clay seam © 79.5'. © 80' End Of Boring.	Green-brown yered,	
- 85 - 90 - 95 - 100 - 105 - 10 - 105 - 115 - 120							. <b>*</b>	

	DLESVILE DOME COU			al Des	51gn									SELEV: 1058.4ft. -SCOORD: 788,469.78		
	R: EMPIRE								5. 769, 177. 32							
	GROU	OWATER	DATA (	feet)					CASING	SAMPLE	ML REF ELEY: 1060.4211. DATE STARTED: 1/6/92					
DATE	GW DEP	Ш	GWELEV	L	INTAKE			_	HSA/steel	<u>SS</u>			DATE FINIS	HED: 1/10/92		
			_				WEI			140#			1	S. Ereeas . J. Gilbert		
							FA	L.		30"						
WELL ONSTRUC	DEPTH (feet)	SAMPLE NUMBER	SAMPLE & TYPE	RECOVERY (feet)	N-VALUE	901	UNIFIED				DESCRIPTI			REMARKS		
		1	X	0.8	13		-		TOPSOIL/SOI Brown SILT, s Gravel, organ	some (+) fmc	: Sand, little	(-) fm suban	iguiar			
	75 77	2	$\mathbf{X}$	0.5	25		4	-	REFUSE Plastics, wood	1 odorous. v		5	.o <sup>.</sup>			
		3		1.0	18	$\Delta^{\Delta}_{\Delta}$ $\Delta^{\Delta}_{\Delta}$ $\Delta^{\Delta}_{\Lambda}$										
N N	F	4	$\boxtimes$	1.3	28	00	51		TILL				.0'	20', 6.5"0.D.		
		5		1.0	31			$\uparrow$	Red-Brown C Sand, dense, -@ 15.0' Brown Sand, plastici	dry to dama Clayey SIL	D. Tand(−)fπ	ic Gravel, sor		Permanent Casing @ 14.4'. Switched from 4" Augers to casing @ 14'.		
	-20 	6	$\boxtimes$	14	44		2020		@ 20' m densi	2.						
	- 25	7	$\boxtimes$	1.0	53											
	-30	8	X	0.8	58				e 30.0' Browi finc Sand, we		LT, som <del>e</del> (+)	fmc Gravel,	some ()			
	- 35	9		° 14	42		2						5.0'	-		
88	Ē	10	Ŕ	13	35				<u>OUTWASH</u> Brown cmf S/	ND, trace (	+) Silt, trace	-				
	-40	n	$\bigotimes$	14	24											
	-	12	$\bigotimes$	12	29								*			
	F .r	13	$\square$	1.6	26				@ 43' Gray-t odor, wet.	lack fmc SA	ND, trace (	-) Gravei, sl.	chemical			
	-45 -	14	$\square$	12	26	:										
	E	15	$\boxtimes$	0.0	32	1.										
	-50	16	$\boxtimes$		38		1									
	E		$\boxtimes$			÷., .										
	-55	_	$\bowtie$						6 55' Dark G	av fm SAN	), some (-) S	5it, w/ Sit so	rted, wet.			
	- 50 - - - - - 55			0.0 0.5 16 16 16					@ 55' Dark Gi	ay fm SANC	), some (-) S	5it, ₩/ Sit sc	rted, wet.			

# Wehran EnviroTech

# BORING/WELL NO. PW-12

SHEET 2 of 2

PROJECT: COLESVILE CLIENT: BROOME COUR CONTRACTOR: EMPIRE	VTY/GAF					PROJECT NO: <i>02260HG</i> RIG: <i>CME-850</i>		958.411. : 788,469.78 : 769,177.32
WELL CONSTRUCT H (1999)	SAMPLE NUMBER SAMPLE	6 TYPE RECOVERY (feel)	N-VALUE	1 OG	UNIF IEU	FIELD DESCRIPTION (Modified Burmister)		REMARKS
B B B B B B B B B B B B B B B B B B B	Max     20     21     22     23     24     25     26     27     28     29     30     31     32	113 2.0 1.7 2.0 1.0 2.0 1.8 1.7 2.0 2.5 2.5 2.5 2.5 2.5 2.5 2.5 2.5 2.5 2.5	>- 			(Modified Burmister) @ 58' Silt seams w/ Red Silty Clay seam. @ 648' Red Silty Clay seam, high dilatancy, we @ 11' becomes dense. GLACIOLACUSTRINE DEPOSIT Brown SILT and f Sand, dense, w/ <0.25'' Red 755. @ 19' high dilatanty, wet, w/ 0.25'' Red Silty f @83' 0.5'' Red Silty Clay seam w/ silt seam: @ 183.0' End Of Boring.	t. 75.0° ed Clay seam @ Clay seam.	

$\nabla \mathcal{N}$	g we	RA	N B	GN	ering							TEST BORING LOG
VL.	CONS	UING	eng	NEERS								BORING NO. W-5
ROJEC	<b>T</b> : _ :	: 5. )		Ē i	<u>سار اکر د</u> ر نظ							SHEET NO. 1 OF -
LIENT	:		Ē :	:	•							JOB NO. 0127 2290
					HSTAR	<u> </u>	·- INC					ELEVATION 1249 57
ROUND	WATER		<u>~~</u>	<u></u>				CAS.	SAMP.	CORE	TUBE	DATE STARTED STOLYS
ATE	TIME	WA	TER	<u> </u>	SCR	LEN	DIA.		<u> </u>			DATE FINISHED
_							WT.					INSPECTOR T Para
							FALL					INSPECTOR / / Aspar
<u> </u>			_				FALL					·
W	ELL	Et		SAI	APLE							
ONST	RUCTION		NO.	TYPE	BLOWS PER			SSIF				REMARKS
	<u> </u>	<b>-</b> •										
		11					CLEA1	V Fil	22			
	1	1										
		-5				1						
											70	
							GLAS	INL T.	26			
										~0		
		1 1				brew	n 5327 e <sup>(4)</sup> =	and				
i		++0			47	1. #1		OFAVC/			ن رز	
1		L	_'_	55.	<u> </u>			TWACK			11. 2	
		t I				e"	bernes string	- de roun	m-E	SAND		
						1.000	E . 5,7				13.0	
		11				• .	6140	IAL TI	,			
		<b>h</b>	-		88	- n	1 SAND	Som	F 61	ave/		
			2	<u>م</u> که ا	2 8 10		ر	•				
						171	ر ع		~/			
•		11										]
,		11										
		20	-		9_17	SIA	7 - 54	A'/ -:	11 = -	2		]
	- 1	1-1	3	<u>ک ن</u>	_ 12		1 14	in F.	11: 31	a 124		
	•	11					· , ///					
3	4											Frequent (Jesie: Ind
												Frequent (Sester The
	2	28			12 13	F. m	JAND	Som	= S H	C/A	/	Boulders To 28
	ž	1 1	4	11	12 13	1-11	,, F 6	ine vel				
:											28	
	$\sim$						0117	VASH				
		1_1		,		-						
		30	_		87	m	- AN	5 j 1. <del>.</del>	12 5			
		H	5	5.5	é							
		11										
									-			
	123		4		69	-	IN'N'	م دست د	- ·	•		ľ
				25	- 8			-				1
		11					-					
· e,	-11-	1_1										
	Ψ	· [***]	7		6 ?							
· •	<b>.</b>	F	/	2.2	6 ?							
		1 1										
,												
	<b>-</b>											
-		48										
		F 1										

----

	I ENG	GINEERING RS			BORING LOG NG NO. W- 5	, •
PROJECT : COLES.				SHEFT		
CLIENT : Poom	5 - 10	water .		JOB NO	NO. 2 OF 2 . 01273290	
	e					
	NQ. TY	PE BLOWS PER	C LASSIFICAT	ION	REMARKS	
	3 5	<u>: 10 12</u> <u>- 15</u>	· · · · ·			-
					202 972	-
50	<i>ą _</i>	- 8 //	51.1	10-	S. Turater	
						-
		- 7 10				_
e e	// -	- //				-
· · ·						
	11 =	: 7 / - 73 	END OF BOKING OT	<u> </u>		
			2		Well Fully developer	٩
65					Pletian	
[]						
70						
75						
-00		,				
-						
- 90						
90						
-   -						
95						
<b>_</b>						

PROJE	ڪ : ۲۵:	CON	<b>SULING</b> 25-5 V	<b>S ENG</b>									TEST BORING LOG BORING NO. 11-13 SHEET NO. 1 OF 2
CLIEN					nunt								JOB NO. 0/273290
				) <b>R</b> :	dor	th star	Deg it sug	-16					ELEVATION 1051.4
GROU				<b>TFD</b>	<b>(</b> )		/	TYDE	CAS.	SAMP	CORE	TUBE	DATE STARTED STARTED
DATE		INE.		ICR	EL.		EEN	DIA.	مری للر تق	کسان ام			DATE FINISHED
	+							WT.		140 141			INSPECTOR - Syrer
			1					FALL		20			
			<u> </u>		6 4 1		r			_*5			
CONS	TRUC	_	METH PEET	NO.	TYPE	BLOWS PER		CL	<b>1 5 5   F</b>				REMARKS
	$\uparrow$	11	<b>†</b> °	7	5.5	86			IAL T				
						64			SILT				
			+				F m	Grave	1, 1.41-	· F-C	Sand	-	
			ŀ										
			-8-			30 <i>51</i> 46 37	(ر بر سر	GRAV	EL Sa	me si	14 + 6	lay	
			ŀ	Z	5.5	46 27	1.410	c · /	Sand				
					<u>├──</u>		,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,						
							1						
							·	-	1 L.	un F	C SA	ND	
			-10-	_	1	14 18	Gradii 1;412	ny to n 41	· CA 010		ці. (	. <u>.</u>	
		L		3	. ح د	14 18	1;4/e	F-r	71 61A		د عرب		
		2					2 Clay	-					· ·
		6,0						-		. , '			
			4		<u> </u>		layer	of cobe	ies 6.	- 6-			evidence of Forder
			<u>ا</u>	j.	ي ج	2 /2							condentre que pe
	1	2		7	<u> </u>	8 2							
		2											
		C					ł						
İ			20		├──		<u> </u>						ur,
	•	2		ک	. ود	65	1	GLACI	AL OU	TWASH	<b>—</b> .	-	[
İ	Š	5				0 7	<b>e</b> 20.3	' F.C	SAND	, Trace	Silt	me	
ļ	Ì	100					F Gr	nuel, g	rading	TO VE	ry F.	SAND	
							Some	SIL					
	. <u>v</u>		-25	·		66							
	2			6	.ح.ح	7 10	med	brown	F SAN	NO, Tra	e si	4	
i're	20				[				,				
1. in	è		[			•							
240	:		-30				,	. To To	e sanl	) som	e 5,1	4	
9x	$\sim$			-	<i></i>	10 8	Presel ;	م م م مد مد م	میں رورہ م اسمی رورہ م	adine .	TO F.	SMAR	
J. 0	Ι	00	<u> </u>		F.J.	10 10	74.7 1			1			
*		000	• •				Troce	5*					
:		-	$\mathbf{F}$				ł		<u>,</u> ,		TI	H/r (4)	
	<u>-</u> ¥_	- · ·	·  - 35	·	{	0 1	- ُ ک کے 🖉	36 m	ed bro	يرد بري	1		
	_		·  -	З	2.2	8 6	F-C	, טיההב	Trace	F 674	ve 1		
· [	_		F		ł	<u> 7</u>	esí'	beceme	محد ۲ ک	NO, 11.	tle Si	<i></i>	
, Ţ		· .											,
3.	_	·	·ト				tl		-				1st encourtered.
<i>.</i> ₹.⊢			-40			, , , , , , , , , , , , , , , , , , ,	moll	rown s	ILT a	nd F.	SAND		Seturation in Sump
-			1	́.	• • •	· · · · · ·	1174	errie e	= the	brown	, - <i>, , ,</i>		
× -		Ι.	1		· ·		1400	1. H/+	5.14	Satur	ut-d		
$\mathbb{N}^{d}$		· ·	Γ				1						
A.L		1.	[				1						
			<b>_</b> _ <b>→</b>		1		1						

₩₽				EERING			BORING LOG
					· · · · · · · · · · · · · · · · · · ·		IG NO. w-13
IENT 1 Ir	<u>/                                    </u>		e 6	and .	· · · · · · · · · · · · · · · · · · ·	JOB NO	NO. DOF
					· · · · · · · · · · · · · · · · · · ·		
WELL	DEPTH	NQ	TYPE	BLOWS PER 6 INCHES	C L & SSIFICATI	ON	REMARKS
	-		100	10 9	GLACIAL OUTWASH		
<u>-</u> ۲-		70	22.	15 21	med brown stating F.	SAND	
·   · ·	$\left  \right $				med brown syle city i	1	
. <sup>·</sup> ·					Irrequier voives Setura les	$\sim$	
a speck		,,	<i>د.د</i>	9 11			
		<u></u>		13 22	5.10 of 12 mine of 52 '		
					END OF Boring at 52'		
					· .		
	-66						
					:		
	•••		l				ar Britisha .
	ti		1				
					_		
	-						
	65						
	Ľ						
			1				
	70						
	ŀ						
	75						
	$\mathbf{b}$						
			Ι,				
	-00		'				
						•	
	ŀ				-		
	ł				-		
	1						
	•6						
	+						
	ł		1				
	ł				1		
	90						
	F						
	ł				4		
	ŀ				1		
	- 95				1		
	r .	1	1		1		

$\mathbb{W}$			N B S ENG	NGIN INEERS	EERING							TEST BORING LOG
					ANG							BORING NO. W-4
LIENT	ERO				in and							SHEET NO. 1 OF
BORING	CONTR	ACT		<u></u>	th star	· · · · · ·						JOB NO. 21273270
ROUN	WATER	2 3	7.4		1 2/20	1		CAS.	SAMP	CORF	TURE	ELEVATION 1245.97
ATE	TIME	WA	TER	EL	SCR	EEN	TYPE		55		1000	DATE FINISHED
							DIA.		à			DRILLER JEST TA-N
							WT.		149 16:			INSPECTOR T Roepe
							FALL		351			· · · · · · · · · · · · · · · · · · ·
w		I.		SAI	NPLE							
	RUCTION		NO.	TYPE	BLOWS PER 6 INCHES		СГЛ	ASSIF		ION		REMARKS
×		t٩	7	1.	4 4							
		[	<u>                                     </u>	2.2	6		CLEAN	V F:	L L			
	:										3.0	
							C	-				
1 1	:			L			F•;:-2 :	, =	,			
		$\left  \right $	Z	ز ت	3 7						50	
		1-1		1			<del>ن م ک</del> ر د م کر	CIAL T	16 (-	-)		
		$\left  \right $									F	
'		+				Sa,	nd , 1.1	4/c `-`	F Gru	sel.		
		+10										
i l		F	3	نہ تک	23 22 72	510	T, so	ne E -	m' sai	nd, 1	.H/e'+1	
'		F		1		F 6	stalet.					
*		$\left  \right $									13.0	
		F										
0				<u> </u>	13 2	@ 15	5 710	de: To	F-M.	SAND, T	-acc (a)	
U I		Ł.	4		É							
		1				<i>ב</i> יי בי ד						
	1											
і. 											300	
		20			7 4	-	GLAC	176	TI		- 0	
-	<	H	-		2				14-			
							00	T ivip	بنر <del>ک</del>			
ε.	د											
а <u>н</u> т	~											
	1		6		76	GART	Prown	m-F	AND,	Trace	5,15	
ł	1	F		· ·								
:	1.											
;												
	10	المعا										
1	6.		2	ز ک	79							
<u> </u>					8							
	ۍ <del>د</del>											
· ;		11										
	<u> </u>							5				<u>م</u> دد
:- 	· • • •		?	- :	22	Grad	TO TO	رەر -	0, 1.1	110		
· · ·	`	F										1.1 - 374
		$\left  \right $										
-		F										Saturated
	1				2 ()	F			<b>.</b>			SATURATER
·	11	Ŀ	2	نہ تھ	7 12	^ ^	AND, .	some	5,1+			
Y	!	FT										
-	à											
-		+										
1	n: (	48										
		+ 1		1								

]

J

]

SHEE	RING NO. W-4
	T NO. 2 OF 2
	NO. 01273290
SSIFICATION	REMARKS
ence of the	
Mar and a service	
FNG at SIS	
	and Fully down , and
	is the air up "
	With air up: ""
·	
	1
	1
_	
	en = 35

-

1

					ERING							TEST BORING	NO. 2	v-1	
OJEC					LANDEI	<u> </u>	_					SHEET NO.		2	
IENT		RACTO		6001	ty	Des ilse	· Tak					JOB NO. 01273290 ELEVATION 10≤9.20			
OUN	D WATE	R 4	5	YOFI	<u> </u>			CAS.	SAMP.	CORE	TUBE	DATE STARTED 6/6/83			
TE	TIME	WA	TER	EL.	SCR	EEN	TYPE		5.5.			DATE FINIS	SHED 67	6/83	
							DIA.		2 "			DRILLER O			
		-					WT.		140 140			INSPECTOR	7. RC	peper	
							FALL		30'						
w	ELL	×.		SAN	APLE										
	RUCTION	PEET H	NO.	TYPE	BLOWS PER		CLASSIFICATION					REMARKS			
	~		<u> </u>					_							
		F													
							CLEA	N FI	LL						
						1									
		- *													
		[									70				
		Ļ						<b>.</b>					•		
							REFUS	=/							
		- 10													
		$\mathbf{F}$													
	į.	ŀ													
		ŀ													
		-15													
	3	F													
	;	-			_	1									
	i														
						1									
		-20				1									
	<b>X</b> :	[													
	2														
	2	-25													
	シント														
•				,											
1	Bentoni	30				4									
ţ	3														
:		<b>`</b> }				•									
											34.0				
	°.)	1.					1.LA	CIAL 7	TILL				*~		
<b>:</b> ;;;;;;;;;;;;;;;;;;;;;;;;;;;;;;;;;;;;			,		14 26				(4						
i		. <b>†</b>	/	5.	14 26	m-F	GRA d li	VEL, S	ome	C	-				
	. \	5. [		[		501	d li	H/c <sup>(+)</sup>	5,1+	۰ ۲۰ م	1				
:		ž.					,								
:	*	].[													
	; `	₹. <b>[</b> •••	2	66	10 19										
	<u>- </u>	s [	<u> </u>	<u>, c c</u>	17										
-	- ::- :	[													
		]:5						•			4 <u>4.</u> 0				
		·	l				20	WASA							
	- 31. \	3.1	1			N						L			

	RA			<b>FRING</b>		TEST	BORING LOG	
	ATING	G ENG	NEERS			BORIN	G NO. 20-1	
PROJECT : CO.							NO. 2 OF 2	
	001	ηE	COU	inty .			01273290	
WELL	<b>.</b>		SAI	MPLE				
WELL CONSTRUCTION	527	NQ.	TYPE	BLOWS PER	CL4SSIFICATIO	N	REMARKS	
	45	3		88	<u> </u>	_		
	F	3	3.2		C-E SAND, I.HIE + F	Gravel	Caturated	
	ŀ				Trane S. 14 + Clay		52.000	
	ŀ							
		u	55	64	8 30'- 51' 511+ + LIAY C	ontent		
	F	+			Increases To I. HIE			
	ŀ							
	Ì							
· · · · · ·		5	5.5	8 9 11	=- C SANS INHIE SAF Traise F Gravel	/		
collepsed	-	-			FARE Gravel			
-0115	ŀ					-		
					m-a sand little -' =14			
	-	6	٢ ٢	25	M- & SAND FRANCE STRAVES JECA Clay, Trace F STRAVES JECA <u>f" lense JF SILT - Clay</u> END OF BORING		61.5	
	F				END OF BORING		in the device of	
	t						Nell Fully developed	
	65						with air upor so-	
	ł						r - +10	
	Ł							
	ļ.						•	
	70	{		<u> </u>	-			
	ł							
	[							
	$\mathbf{F}$							
	78				•			
	[				1			
	ł				-			
	ł		,		-			
	-00				1			
	[				-			
	ŀ				•			
	1				1			
		'			1		-	
	ł				-			
	ł				-			
	90				1			
	1				8		•	
	ŀ				1			
	[				1			
	.98				4			
					1			
	[				1			1

.

- -- -

. .

-

-----

- ---

www.weistan.ex.

#### APPENDIX C STORMWATER DRAINAGE DESIGN

ţ

_Date
Date

<b>lehran</b> Envir	ote
---------------------	-----

V

\_ of \_

TR-55	DESIGN	DATA
TR-55	DESIGN	DATA

MANNING'S 'A"

CHANNEL VELOCITY STORM INTESITY

STORM TYPE

Subject

ر ب ک

MANNINKS "" VALUE FOR RIP RAP

N= .0395 050 ℃

RRF. DESIGN OF STABLE CHANNELS AND FLEXIBLIZ LININGS

H.E.C # 15 Hydraulic CIRCULAR

D3-0 n 31 .031 .033 4" 6" .035 .037 8\* .038 10" .040 12"




Figure 3-1 .- Average velocities for estimating gravel time for shallow concentrated flow.


New York Guideling Erosion and Sedimen

(210-VI-TR-55, Second Ed., June 1986)

3-2


Exhibit 10.1








# New York Rainfall Maps for Different Rainfall Frequencies



October 1991 - Third Printing

New York Guidelines for Urban Erosion and Sediment Control



New York Guidelines for Urban Erosion and Sediment Control October 1991 - Third Printing




Figure B-2.—Approximate geographic boundaries for 808 rainfall distributions.

(210-VI-TR-55 Second Ed., June 1986)

By	Date
Chkd. by	
Subject	

Date \_\_\_





Sheet No. \_\_\_\_\_ of \_\_\_\_\_

....

Hereite the second state of the second state of the second state of the second state of the second state of the

TRIANGULAR AND TRAPEZOIDAL


# CHANNEL DESIGN

and a second water in the second second second

.

.

CNANNEL	BRAINARE HREA (AL)	CHANNEL SLOPE(9/0)	דאותד גובע	ouriet Filev	(FT) (FT)	FLOW (CFS)	(EPS)	TYPE	DEPTH (FT)	(10,20)	GABION THICHTSS (IN)	
DC-1-1	ū Ķ	ن م نک ا	1062 5 1053 5	0.9401 2.8201	25.5	3,0 3,0	01	6i2nss GRASS	2.0 2.0	1 1	۱,	
×-1-2	23	S S	644	5 7401	0 <b>,011</b>	5.0	2.5	GRASS	1.5	1	1	
DX-1-3	13.1	1:5	1049	0.(-20)	220.0	28.0	6.4	RIPRAP	L L	e. c	)	
Dc - 2	11.6	15.0	1062.5	1056.0	1300.0	26.0	2.5	GRA 55	2.5	1	l	
۲۲-2A	11.6	0 1	1056,0	5.2201	0.001	26.0	25	GRASS	2.5	۱	J	
K-2-INET	9.11	33 o	1055.5	10 50.0	او، ح	26.0	1.7	CABION	۲	١	, Q	
bc-3	0	0.5	IONZ.S	ופלויל	230.0	3.0	07	GRASS	2.0	1	1	
K-4-1	۲. ۶	3.0	2.1801	10 56.3	830.0	14.0	3.0	62455	/,2 .	۱	۱	
Dc - 4 - 2	9.01	S.0	2.9501	1051.0	1050.0	24.0	2.5	66455	2 2	١	1	
K-5-1	35.8	ہ ہ	1150,0	1146.0	884.0	61.0	3.0	6RASS	2.5	1	ſ	
K- 6	t:	<b>מ</b> ס	109013	1058.01	430.0	32.0	2.5	くいろうひ	3.0	[	1	
X-6- 1111ET	Ц. Т.	0 80	3201	1020.0	24.0	320	7.6	GABION	, S <sup>-</sup>	١	; 9	
SEDIMENT BASIN OUTLET SSPILLMAY	34.7	33.0	1055	ୟଞ	60	2 t	وط	GABION	<u>با</u>	1	- 0.81 -	



GRASS LINED CHANNEL/DIVERSION DESIGN

Channel ID:  $\square C - I - !$ Peak Flow, Q =  $\_3CFS$ Ave. Slope, s =  $\_0.5\%$ 

Select Basic Channel Geometry

Triangular, bottom width = 0 ft or Trapazoidal, bottom width = \_\_\_\_

Channel Side Slope (z:1),  $\chi = 3$ 

#### Determine Required Lining

Max. Velocity for Grass Only = 3 FPS Max. Velocity for Jute Lining = \_\_\_\_\_ Max. Velocity for Erosion Control Mat = \_\_\_\_

From Table D at the given slope and flow, Velocity  $\leq 1.0$  Frs Therefore use: Grass, Jute, or Erosion Control Mat (circle one)

Determine Channel Depth:

- For Max. Velocity using Table D

$$Q = 4.8$$
 at  $V = 1.0$  and  $d = 1.3$ 

- For Max. Capacity using Table C

$$Q = 3.6$$
 at  $V = 0.5$  and  $d = 1.5$ 

Therefore set Total Depth =  $2.^{\circ}$  inc. Freeboard and Settlement

PREPARED IN ACCORDANCE WITH THE SCS ENGINEERING FIELD MANUAL FOR CONSERVATION PRACTICES AND **GRASS LINED CHANNEL/DIVERSION WORKSHHET** Table C

THE STANDARDS FOR SOIL EROSION AND SEDIMENT CONTROL IN NEW JERSEY

**m** 0 BOTTOM WIDTH (B) = RETARDANCE 'C' SIDE SLOPE (z:1)

									_	-		
	σ	500	210	:	96.8	69.2	59.2	47.4	42.6	34.8	25.1	18.4
6.0	σ	5.3	3.4	2.6	2.3	2.0	<b>1</b> .8	1.6	1.5	1.4	1.2	1.0
	œ	2.50	1.62	1.22	1.10	0.93	0.86	0.7	0.73	0.66	0.56	0.48
	σ	280	122	73.5	57.7	73.5	57.7	73.5	57.7	73.5	57.7	73.5
5.0	р	4.3	2.8	2.2	2.0	2.2	2.0	2.2	2.0	2.2	2.0	2.2
	œ	2.05	1.35	1.05	0.93	1.05	0.93	1.05	0.93	1.05	0.93	1.05
	σ	199	93.8	57.6	46.5	35.6	30.2	25.3	22.3	19.5	13.8	10.6
4.5	d,	3.8	2.6	2.1	1.9	1.6	1.5	1.4	1.3	1.2	1.0	0.9
	æ	1.82	1.25	0.98	0.88	0.77	0.71	0.65	0.61	0.57	0.48	0.42
	σ	145	66.9	44.2	35.9	27.6	23.9	19.8	17.9	15.0	11.3	8.5
4.0	р	3.5	2.4	1.9	1.7	1.5	1.4	1.3	1.2	÷	1.0	0.8
	æ	1.65	1.12	0.91	0.82	0.72	0.67	0.61	0.58	0.53	0.46	0.40
	σ	••••	51.5	32.9	27.0	20.9	19.1	15.7	14.1	12.1	8.6	6.7
3.5	р	3.2	2.2	1.8	1.6	1.4	1.3	1:2	1.2	÷	0.9	0.8
	α	1.50	1.05	0.84	0.76	0.67	0.64	0.58	0.55	0.51	0.43	0.38
	σ	72.9	35.3	23.7	19.6	15.4	13.9	11.2	10.4	9.2	6.7	5.2
3.0	P	2.8	2.0	1.6	1.5	1.3	1.2	1.1	1.1	1.0	0.9	0.8
	æ	1.35	0.94	0.77	0.70	0.62	0.59	0.53	0.51	0.48	0.41	0.36
	σ	46.4	24.7	16.8	14.1	11.2	10.5	8.3	7.7	6.7	5.1	4.1
2.5	ρ	2.5	1.8	1.5	1.4	1.2	1.2	1.1	1.0	0.9	0.8	0.7
	æ	1.18	0.86	0.71	0.65	0.58	0.56	0.50	0.48	0.45	0.39	0.35
	σ	29.4	16.6	11.3	9.6	7.8	7.2	5.9	5.4	4.7	3.7	2.7
2.0	p	2.2	1.7	1.4	1.3	:-		1.0	0.9	0.9	0.8	0.7
	æ	1.05	0.79	0.65	0.60	0.54	0.52	0.47	0.45	0.42	0.37	0.32
	σ	18.0	10.4	7.0	6.3	5.0	4.6	3.9	3.5	3.0	2.4	1.9
1.5	р	2.0	1.5	1.2	1.2	1.1	1.0	0.9	0.9	0.8	0.7	0.7
	œ	0.95	0.72	0.59	0.56	0.50	0.48	0.44	0.42	0.39	0.35	0.31
	σ	9.6	7.7	3.7	3.3	2.8	2.6	2.1	1.9	1.8	1.4	1.0
1.0	Ρ	1.8	1.6	1.1	:-	1.0	0.9	0.8	0.8	0.8	0.7	0.6
	α	0.85	0.76	0.53	0.50	0.46	0.44	0.40	0.38	0.37	0.32	0.28
VELOCITY	SLOPE	0.5%	1.0%	1.5%	2.0%	2.5%	3.0%	3.5%	4.0%	5.0%	7.0% 0.32	10.0% 0.28

# Norte: @ 0.5% and 0.5 pps , R= 0.73, d= 1.5, and Q= 3.6 cFS

**VELOCITY IN FPS** 

R = HYDRAULIC RADIUS FROM FIGURE A6-2 d = Depth of channel in feet (not including allowances for freeboard, lining installation, or settlement) Q = FLOW IN CFS

RETARDANCE 'C; 01/22/93 (file: jhf disc: tools:retard'c.wk1)

PREPARED IN ACCORDANCE WITH THE SCS ENGINEERING FIELD MANUAL FOR CONSERVATION PRACTICES AND THE STANDARDS FOR SOIL EROSION AND SEDIMENT CONTROL IN NEW JERSEY **GRASS LINED CHANNEL/DIVERSION WORKSHHET** 

Table D

RETARDANCE 'D' SIDE SLOPE (z:1) BOTTOM WIDTH (B) =

**ω** 0

VELOCITY	1.	0		1.5			2.0			2.5			3.0			3.5			0.	_	4	4.5		5.0			6.0	
	R	σ	œ	q	σ	œ	σ	σ	œ	σ	σ	œ	σ	σ	œ	σ	a	æ	P	ļ	æ	о р	æ	P	a	æ	۳	a
0.5% 0	0.6 1.3	3 4.8	8 0.73	1.5	10.7	0.86	1.8	19.7	1.00	2.1	33.3	1.15	2.4	52.9	1.33			.51	3.2		.70	6 17	3 1.95	5 4.1	254	1 2.40	5.1	461
1.0% 0.44	44 0.9		5 0.53	-	5.6	0.62	1.3	10.3	0.70	1.5	_	0.79	1.7		0.90	1.9	1 8.71		2.1 5		10 2	3 72		3 2.6		_		
1.5% 0.	36 0.	8 1.8		0.0	_	_		6.7	0.56	1.2	10.5	0.64	1.3	_	0.70		2.9 0		1.7 3		.86	8 44		5 2.0		_	_	
2.0% 0.				0.8	3.0		0.9	5.4	0.51	1.1	8.7	0.57					2.9 0				76 1	6 34		4 1.8	3 47.0			
2.5% 6.		_	0.5	_		~	Ú.Ů	<b>4</b> .1	U.44	0.9	6.5	0.58					3.6 0				.65 1	4 25		1 1.5	33.6		_	
3.0% 0.28			_		2.1	0.37		3.7	3.7 0.42	0.9	5.9	0.46	1.0	8.5			2.1 0				60	3 21		7 1.4	53.5		1.6	48.7
3.5% 0.		_		_				2.9	0.38	0.8	4.7	0.41					9.5 0				54 1	1 17		8	22.7		_	
4.0% 0.	24 0.5	5 0.8	3 0.28	0.6	1.6	0.32	0.7	2.6	0.35	0.7	4.1	0.39	0.8		_		8.6				51 1	1 15		5   1.2	20.	_	1.3	<u> </u>
0.0%	0.22 0.3	1.1.2	0.26	<u>, 0</u>			.0.P	2.4	0.33	0.7	3.6	0.36	0.8	5.2	0.40	0.8	7.3 0	0.43	6.0	9.9 0	0.47 1.0	0 13.3	3 0.51	1	17.3	0.59		27.8
7.0%			0.23	0.5		0.26	0.5	1.8	0.28	0.6	2.6	0.31	0.7				5.4 0				39	6		20.0	11.8	_	-0.	18.4
10.0%	_	_	_	_		0.24	0.5	1.5	1.5 0.24	0.5	1.9	0.26	0.5		_		3.7 0				33 0	2		5 0.7	8.2	_	_	

VELOCITY IN FPS

R = HYDRAULIC RADIUS FROM FIGURE A6-3

d = DEPTH OF CHANNEL IN FEET (NOT INCLUDING ALLOWANCES FOR FREEBOARD, LINING INSTALLATION, OR SETTLEMENT) Q = FLOW IN CFS

RETARDANCE 'D; 01/22/93 (file: jhf disc: tools:retard'd.wk1)

	TR Project : COLESVILLE LA County : BROOME Subtitle: CHANNEL DC-1-	NDFILL	PHICAL	DISCHAR( NY	Us	OD er: KPH ed: 1954		VERSION 1. ate: 01-14- ate: <u>//22/</u>
	Data: Drainage Area Runoff Curve Nur Time of Concent: Rainfall Type Pond and Swamp 2	mber : ration: ;	80 * 0.46 II					
	Storm Number	1	2	3		5	6	-
۲	Frequency (yrs)	2	5	10	25	50	100	
	24-Hr Rainfall (in)	2.8	3.5	4.3	4.9	5.3	5.9	
	Ia/P Ratio	0.18	0.14	0.12	0.10	0.09	0.08	
	Used	0.18	0.14	0.12	0.10	0.10	0.10	
-	Runoff (in)	1.10	1.64	.2.29	2.81	3.16	3.69	
-	Unit Peak Discharge (cfs/acre/in)	0.806	0.832	0.851	0.861	0.863	0.863	
<b>.</b>	Pond and Swamp Factor 0.0% Ponds Used	1.00	1.00	1.00	1.00	1.00	1.00	
	Peak Discharge (cfs)	1	2	3	3	4	4	_

\* - Value(s) provided from TR-55 system routines

1.11 4**-**93 193

Project : ( County : H Subtitle: (	COLESVILLI BROOME	E LANDFIL	L	U SUBAREA : NY		IPUTATION User: KPH ecked:	-	VERSION Date: 01-1 Date: <u>مرا</u>	L4-93 <sup>—</sup>
Flow Type	2 year rain	Length (ft)		Surface code				Velocity (ft/sec)	
Sheet Open Channe		190 400	.01	E		Time of (	Concent	1.2 tration = ( =	0.364 0.093 0.46*
A Smoot B Fallo C Cult D Cult E Grass	- Sheet Fi th Surface ow (No Res ivated < 2 ivated > 2 s-Range, S	e s.) 20 % Res. 20 % Res. Short	F Gra G Gra H Woo I Woo	ss, Dense ss, Burmud ds, Light ds, Dense	da		Surfa P Pa	oncentrated ce Codes aved npaved	  

\* - Generated for use by GRAPHIC method

----

TR-55 CURVE NUMBER C Project : COLESVILLE LANDFILL County : BROOME State: NY Subtitle: CHANNEL DC-1-1	Use	r: KPH	Date	ERSION 1. 2: 01-14- 2: <u>1/44/13</u>
COVER DESCRIPTION	Α	Hydrologic B Acres	С	
FULLY DEVELOPED URBAN AREAS (Veg Estab.) Open space (Lawns,parks etc.) Good condition; grass cover > 75%	-	<b>_</b> ·		1.3(80
Total Area (by Hydrologic Soil Group)				1.3 ====
TOTAL DRAINAGE AREA: 1.3 A	cres	WEIGHTED	CURVE	NUMBER: 8
<ul> <li>* - Generated for use by GRAPHIC method</li> </ul>				
* - Generated for use by GRAPHIC method				
* - Generated for use by GRAPHIC method				
* - Generated for use by GRAPHIC method			·	

By 44 Date 4/19/94	Wehran EnviroTech	Job No. 02260 CS
Chkd. by Date		Sheet No of
Subject	Colesui, Le Drainage Design	

CHANNEL DC-IA

THANNE DC-IR WAS DESIGNED TO CONVEY WATTER THROUGH THE CHANGE IN SLOPE CAUSED BY FINEL COVER CONSTRUCTION. CHARMEN DC-IN 15 I AN UPGRECOID and SECTION FOR THE ORGINALLY DESIGNED CHANNEL DC-I-I. SINCE THE CHANNEL DC-IN HAS THE FERRET TRIBUTARY AREA OF CHANNEL DC-I-I THE TR-SS INFORMATION (IIC FLOW= 3CES) WAS UTILIZED FOR THE DESIGN.

By AIK DATE 4/18/54 CHIR KOK DATE 4/19/64

# DIVERSION CHANNEL DESIGN - RIP-RAP LINING

JOB NO. 02260 CS

COLESVILLE LANDFILL CHANNEL DC-1A

CHANNEL SIDESLOPE       LEFT SIDE (HORIZ/VERT)	
MANNING'S ROUGHNESS COÈFFICIENT, n	3.0 ).136 3.0 3.0
	0.0 ).040 0.5
   BEGIN CALCULATIONS AT CHANNEL DEPTH (FT)	0.0

CHANNEL DEPTH (FT)	X-SECT AREA (SQ FT)	TOP WIDTH (FT)	HYDRAULIC RADIUS DIS (FT)	SCHARGE VI (CFS)	ELOCITY NU (FPS)	FROUDE IMBER Nf
0.0	0.0	0.0	0.00	0.0	0.0	0.00
0.1	0.0	0.6	0.05	0.1	1.8	1.42
0.2	0.1	1.2	0.09	0.3	2.9	1.59
0.3	0.3	1.8	0.14	1.0	3.7	1.70
0.4	0.5	2.4	0.19	2.2	4.5	1.79
0.5	0.8	3.0	0.24	3.9	5.3	1.85
0.6	1.1	3.6	0.28	6.4	5.9	1.91
0.7	1.5	4.2	0.33	9.7	6.6	1.96
0.8	1.9	4.8	0.38	13.8	7.2	2.01
0.9	2.4	5.4	0.43	18.9	7.8	2.05
1.0	3.0	6.0	0.47	25.1	8.4	2.08

DESIGN DEPTH OF FLOW, D (FT)	0.5
VELOCITY, V (FPS) .	5.3
TOTAL DEPTH INCLUDING FREEBOARD (FT)	1.0
RIP-RAP SIZE, d50 (IN)	4.0

By: 74 Date: 1/22/93

Chk: KPN Date: 1-25-93

GRASS LINED CHANNEL/DIVERSION DESIGN

Channel ID:  $\underline{PC-I-I}$ Peak Flow, Q =  $\underline{S\cdot o} CFS$ Ave. Slope, s =  $\underline{3\cdot 5}$ %

Select Basic Channel Geometry

Triangular, bottom width = 0 ft or Trapazoidal, bottom width = 3Channel Side Slope (z:1),  $\overline{z} = 3$ 

Determine Required Lining

Max. Velocity for Grass On y = 3 Frs Max. Velocity for Jute Lining =  $\sqrt{A}$ Max. Velocity for Erosion Control Mat =  $\sqrt{A}$ 

From Table D at the given slope and flow, Velocity  $\leq 2.5$  From Therefore use: Frase Jute, or Erosion Control Mat (circle one)

Determine Channel Depth:

- For Max. Velocity using Table D

$$Q = 5.9$$
 at  $V = 2.5$  and  $d = 0.5$ 

- For Max. Capacity using Table C

Q = 
$$6.9$$
 at V =  $2.0$  and d =  $0.7$   
Therefore set Total Depth =:  $16$  inc. Freeboard and Settlement

Table D

PREPARED IN ACCORDANCE WITH THE SCS ENGINEERING FIELD MANUAL FOR CONSERVATION PRACTICES AND THE STANDARDS FOR SOIL EROSION AND SEDIMENT CONTROL IN NEW JERSEY **GRASS LINED CHANNEL/DIVERSION WORKSHHET** 

SIDE SLOPE (z:1) BOTTOM WIDTH (B) = RETARDANCE 'D'

ოო

VELOCITY		1.0	-		1.5			2.0			2.5			3.0		e,	3.5		4	~		4.5			5.0			6.0	
SLOPE	<u>م</u>	P	σ	œ	P	σ	<u>م</u>	P	σ	Œ	P	a	æ	P	е В	P	a	æ	ס	σ	œ	9	σ	œ	P	a	æ	Ð	a
0.5%	0.6	0.9	5.3 0	0.73	1.2	11.4 0	0.86	1.4 2	20.6 1	1.00	1.7 34		1.15 2	2.0 54	54.0 1.3	.33 2	2.4 83.6	6 1.51	1	7 123	3 1.70	0.3.1	174	1.95	3.6	254	2.40	4.6	461
1.0% (	_	0.6	3.1	0.53	0.8	6.4 0	0.62	1.0 1	11.2 0	0.70	1.1	17.5 0.	0.79	1.3 26	26.3 0.90		1.5 39.3		0 1.7	7 54.9	9 1.10	0 1.9	74.3		2.2	102	1.50	2.7	182
	0.36	0.5	2.2		0.6	4.4 0	0.50	0.7	_	_	0.8 11	11.7 0.	0.64	1.0 17	17.8 0.70		1.1 24.5			35.1	1 0.86	6 1.4	46.3	0.95	1.6	62.2	1.10	1.9	99.0
2.0%	0.33	0.4	1.9 0		0.5	_			_		0.8	9.9 0.	0.57 0		.5 0.62		1.0 19.6	6 0.6	9 1.1		3 0.76	6 1.2	36.7	_	1.4	49.2	1.00	1.7	82.4
2.5% (		0.4	1.6 0						_		0.6 7	_	0.58		14.9 0.54	_	8 15	.3 0.60			1 0.6	5 1.0	27.5	_	_	_		1.4	60.4
3.0%6	0.28		1.5 0	_	0.4	2.8	_	0.5	4.6 0	0.42 0		7.1 0.	0.46 0	0.7 9	_	_	0.8 13.9	9 0.5	6 0.8		7 0.60		23.8			32.3	0.78	1.3	51.4
3.5%		0.3	1.3 0	_		_			_	_	0.5	_	0.41		8.2 0.45		9	.2 0.50		7 15.3	3 0.5	4 0.8	_	0.58	_	24.9	0.67	÷	38.8
4.0%		0.3	1.2		0.4	_					_	5.3 0.	0.39 0	_	7.5 0.43		6 10	.3 0.47		7 13.7		1 0.8	17.8	0.55	0.8	22.6	0.63	1.0	34.6
5.0% (	_	0.3	1.1	0.26	0.3	_	0.30		_	0.33	0.4 4	4.8 0.	0.36 (	0.5 6	6.6 0.40			9.0 0.4		3 11.8	_	7 0.7	15.5	0.51	0.8	19.8	0.59	0.9	30.8
7.0%			5		0.3	1.7 0		0.3	2.7 0	0.28		3.7 0.	0.31		5.2 0.34		0.5 7	7.0 0.37	7 0.5	5 9.2	2 0.39	9 0.5	11.3	0.42	-	14.2	0.48	0.7	21.4
10.0%					_	3	0.24	0.5	1.5 0.24		0.3	2.9 0.	0.26	0.3 4	4.0 0.28	_	0.4 5	5.2 0.31	1 0.4	6.9	9 0.3	0.33 0.4		8.4 0.35	0.5	10.5 0.40		90	15.7

VELOCITY IN FPS R = HYDRAULIC RADIUS FROM FIGURE A6-3

d = DEPTH OF CHANNEL IN FEET (NOT INCLUDING ALLOWANCES FOR FREEBOARD, LINING INSTALLATION, OR SETTLEMENT)

Q = FLOW IN CFS

RETARDANCE 'D; 01/22/93 (file: jhf disc: tools:retard'd.wk1)

**GRASS LINED CHANNEL/DIVERSION WORKSHHET** Table C

PREPARED IN ACCORDANCE WITH THE SCS ENGINEERING FIELD MANUAL FOR CONSERVATION PRACTICES AND THE STANDARDS FOR SOIL EROSION AND SEDIMENT CONTROL IN NEW JERSEY

RETARDANCE 'C' SIDE SLOPE (z:1) BOTTOM WIDTH (B) =

**ო** ო

SLOPE R d	9		1.5			2.0			2.5			3.0		ო	3.5		4.0	0		4.5			5.0			6.0	
	5	R	σ	a	œ	P	σ	æ	Ρ	σ	æ	σ	σ	ш		а В	P	a	æ	σ	a	œ	σ	σ	æ	σ	a
0.5% 0.85 1.4	4 10	.1 0.95	1.6	18.7	7 1.05	1.8	30.2	1.18	2.1	47.3	1.35	2.4	73.8 1.	.50	2.7 **	•• 1.6	.65 3.0	0 146	6 1.82	2 3.4	199	2.05	3.9	281	2.50	4.8	500
1.0% 0.76 1.2	8	8.2 0.72	:	11.1	0.79	1.3	17.5	0.86	4.1	25.7 (	0.94	1.6	36.6 1.	1.05 1	1.8 52	52.8 1.12	1.9	9 68.4	4 1.25	5 2.2	95.2	1.35	2.4	123	1.62	3.0	211
1.5% 0.53 0.8		4.2 0.59	0.0	7.7	0.65	1.0	12.2	0.71	÷	18.0	0.77	1.2	25.1 0.	0.84 1	1.4 34	34.5 0.91	1.5	5 45.9	9 0.98	8 1.7	59.5	1.05	1.8	75.4	1.22	2.1	* * * *
2.0% 0.50 0.7	7 3	3.8 0.56	0.8		0.60	0.9	10.6	0.65	1.0	15.3 ] (	0.70	1.1	21.0 0.	0.76	1.2 28	28.6 0.82	2 1.3	3 37.6		8 15	48.4	9.92	<u> </u>	<b>58</b> .8	\$.18	8.5	38.E
2.5% 0.40 U.1	-,	3.3 0.50	0.7	5.7	7 0.54	·	8.8	0.58	6.0	12.4 (	0.62	1.0	16.8 0.	0.67 1	1.1 22	22.6 0.72	1.1	1 29.5	5 0.77	7 1.2	37.6	1.05	1.8	75.4	0.93	1.6	71.7
3.0% 0.44 0.6		.1 0.48	0.7	5.3	3 0.52	0.8	8.2	0.56	0.8	11.7 0	0.59	0.9	15.4 0.	0.64 1	1.0 20	20.8 0.67	37 1.1	1 25.8	8 0.71		32.4	0.93	1.6	59.8	0.86	1.4	61.8
3.5% 0.40 0.6		2.6 0.44	0.6	4.6		0.7	6.9	0.50	0.7	9.6	0.53	0.8	12.7 0.	0.58 0	0.9 17	17.4 0.61	51 0.9	9 21.8		5 1.0	27.5	1.05	1.8	75.4	0.71	1.2	50.2
4.0% 0.38 0.5		_	0.6	_	3 0.45	0.6	6.4	0.48	0.7	_	0.51	0.8	11.9 0.	0.55 0		15.8 0.58	<u>60</u> 85	9 19 9	9   0 Å1		24.5	0.0	9	50.5	0.78	¢.	1.04
3.0% 0.37 0.5	5 23	3 0.39	0.5	3.8		0.6	5.7	0.45	9.0	8.0	0.48				0.8 13	13.9 0.53	53 0.8	8 16.9	9 0.57	7 0.9	21.7	1.05	1.8	75.4	0.66	<del>.</del>	37.7
7.0% 0.32 0.4		1.8 0.35	0.5	3.2	2 0.37	0.5	4.6	0.39	0.5	6.3	0.41	0.6	8.2 0.	0.43 0	0.6 10	10.3 0.46	16 0.7	7 13.2	2 0.48	8 0.7	16.0	0.93	1.6	59.8	0.56	0.8	28.0
10.0% 0.28 0.4	_	1.5 0.31	0.4	2.6	3 0.32	0.7	2.7	0.35	0.5	5.3 (	0.36	0.5	6.6 0.	0.38 0	0.5 8	8.4 0.40	9.0	6 10.5	5 0.42	2 0.6	12.8	1.05	1.8	75.4	0.48	0.7	21.4

VELOCITY IN FPS

R = HYDRAULIC RADIUS FROM FIGURE A6-2

d = DEPTH OF CHANNEL IN FEET (NOT INCLUDING ALLOWANCES FOR FREEBOARD, LINING INSTALLATION, OR SETTLEMENT) Q = FLOW IN CFS

RETARDANCE 'C; 01/22/93 (file: jhf disc: tools:retard'c.wk1)

TR-55 GRAPHICAL DISCHARGE METHOD Project : COLESVILLE LANDFILL County : BROOME Subtitle: CHANNEL DC-1-2

State: NY

User: KPH Checked:

VERS	SION 1.11
Date:	01-14-93
Date:	1/22/13

Data:	Drainage Area	:	2.3 * Acres
	Runoff Curve Number	:	80 *
	Time of Concentratio	n:	0.48 * Hours
	Rainfall Type	:	II
	Pond and Swamp Area	:	NONE

	Storm Number	1	2	3	4	5	6
	Frequency (yrs)	2	5	10	25	50	100
-	24-Hr Rainfall (in)	2.8	3.5	4.3	4.5	5.3	5.9
-	Ia/P Ratio	0.18	0.14	0.12	0.11	0.09	0.08
	Used	0.18	0.14	0.12	0.11	0.10	0.10
•	Runoff (in)	1.10	1.64	2.29	2.46	3.16	3.69
•	Unit Peak Discharge (cfs/acre/in)	0.788	0.814	0.833	0.836	0.844	0.844
-	Pond and Swamp Factor 0.0% Ponds Used	1.00	1.00	1.00	1.00	1.00	1.00
	Peak Discharge (cfs)	2	3	4	5	6	7

\* - Value(s) provided from TR-55 system routines

County :	COLESVILLI	E LANDFIL	L .	V SUBAREA ; NY	(PUTAT User: ecked:	KP	н	VERSIC Date: 01 Date: 1	
Flow Type	2 year rain	Length (ft)		Surface code			Wp (ft)		-
Sheet Open Chanr Open Chanr		190 270 400	.01	E	 Time	of	Concent	3.0 1.2 tration =	0.0934
A Smoo B Fall C Cult	- Sheet Fi oth Surface low (No Res ivated < 2 ivated > 2	e 5.) 20 % Res.	F Gra G Gra H Woo	\$s, Dense \$s, Burmud		Sha	Surfac P Pa	oncentrat ce Codes aved npaved	ed

E Grass-Range, Short \* - Generated for use by GRAPHIC method

COVER DESCRIPTIO FULLY DEVELOPED URBAN ARI Open space (Lawns,parks e Good condition; grass o	EAS (Veg Estab.)	A	Hydrologi B Acres	С	Group D
Open space (Lawns, parks e	etc.)				
			-	-	2.3(80)
Total Area (by Hydrologic	c Soil Group)				2.3 
TOTAL DR	AINAGE AREA: 2.3	Acres	WEIGHTED	CURVE	NUMBER:80
<ul> <li>* - Generated for use by</li> </ul>	GRAPHIC method				

By 21 Date 1/22/3 Chkd. KPH Date 1-22-93

DIVERSION CHANNEL DESIGN - RIP-RAP LINING JOB NO. 02260 CS COLESVILLE LANDFILL CHANNEL DC-1-3 ----- INPUT -----28.0 0.051 CHANNEL SIDESLOPE - LEFT SIDE (HORIZ/VERT) . . . . . . 3.0 CHANNEL SIDESLOPE - RIGHT SIDE (HORIZ/VERT) . . . . . . 3.0 6.0 0.035 0.5 BEGIN CALCULATIONS AT CHANNEL DEPTH (FT) . . . . . . . 0.5 \_\_\_\_\_\_

	CHANNEL DEPTH (FT)	X-SECT AREA (SQ FT)	TOP WIDTH (FT)	HYDRAULIC RADIUS (FT)	DISCHARGE (CFS)	VELOCITY (FPS)	FROUDE NUMBER Nf
==			,				
	0.5	3.8	9.0	0.41	19.9	5.3	1.45
	0.6	4.7	9.6	0.48	27.5	5.9	1.48
	0.7	5.7	10.2	0.54	36.3	6.4	1.51
	0.8	6.7	10.8	0.61	46.3	6.9	1.54
	0.9	7.8	11.4	0.67	57.6	7.4	1.56 📟
	1.0	9.0	12.0	0.73	70.2	7.8	1.59
	1.1	10.2	12.6	0.79	84.0	8.2	1.61
	1.2	11.5	13.2	0.85	99.2	8.6	1.62 🕳
	1.3	12.9	13.8	0.90	115.8	9.0	1.64
	1.4	14.3	14.4	0.96	133.7	9.4	1.66
	1.5	15.8	15.0	1.02	153.1	9.7	1.67

DESIGN DEPTH OF FLOW, D (FT)	•		0.7
VELOCITY, V (FPS)	•	•	6.4
TOTAL DEPTH INCLUDING FREEBOARD (FT)	•	•	1.2
RIP-RAP SIZE, $d50$ (IN)	•	•	6.0

Project :	COLESVILLE LANDFILL		
County :	BROOME	State:	NY
Subtitle:	CHANNEL DC-1-3		

User: KPH Checked:

Date: 01-14-93 Date: <u>//22/43</u>

Data:	Drainage Area	:	13.1 * Acres
	Runoff Curve Number	:	80 *
	Time of Concentratio	n:	0.58 * Hours
	Rainfall Type	:	II
	Pond and Swamp Area	:	NONE

Storm Number	1	. 2	3	4	5	6
Frequency (yrs)	2	5	10	25	50	100
24-Hr Rainfall (in)	2.8	3.5	4.3	4.9	5.3	5.9
Ia/P Ratio	0.18	0.14	0.12	0.10	0.09	0.08
Used	0.18	0.14	0.12	0.10	0.10	0.10
Runoff (in)	1.10	1.64	2.29	2.81	3.16	3.69
Unit Peak Discharge (cfs/acre/in)	0.712	0.736	0.754	0.763	0.765	0.765
Pond and Swamp Factor 0.0% Ponds Used	1.00	1.00	1.00	1.00	1.00	1.00
Peak Discharge (cfs)	10	16	23	28	32	37

\* - Value(s) provided from TR-55 system routines

Project : County : Subtitle:	BROOME		L State	: NY	User: KPH cked:	-	Date: 01-1 Date: <u>//22/</u>	
Flow Type	2 year rain	Length (ft)					Velocity (ft/sec)	
Sheet Open Chann		300 1470	.040	E	 Time of C	concent	1.47 tration = 0	0.302 0.278
A Smoo B Fall C Cult D Cult	- Sheet Fl th Surface ow (No Res ivated < 2 ivated > 2 s-Range, S	.) 0 % Res. 0 % Res. hort	F Gra G Gra H Wood I Wood	ss, Dense ss, Burmud ds, Light ds, Dense		Surfac P Pa	oncentrated ce Codes aved npaved	• •

\* - Generated for use by GRAPHIC method

-

## TRAVEL TIME WORKSHEET OPEN CHANNEL FLOW SEGMENTS FOR USE IN DETERMINATION OF TIME OF CONCENTRATION

## COLESVILLE LANDFILL CHANNEL TIME OF CONCENTRATION DC-4 SEGMENTS

FLOW SEGMENT I.D.	FLOW SEGMENT DESCRIPTION	FLOW SEGMENT LENGTH (FT)	SLOPE (%)	VELOCITY (FPS)	TIME (HR)
1	DC-4-1	200	3.000	3.00	0.019
2	DC-4-2	1,050	0.050	1.20	0.243
3	DC-1-3	220	6.100	4.00	0.015
4					0.000
5					0.000
6					0.000
		********* <b>*</b> *			
	TOTALS =	1,470			0.277

AVERAGE VELOCITY 1.47 FPS

This worksheet is used to determine the the average velocity of flow in a series of open channel flow segments. This is required when the time of concentration or travel time flow path contains more than two segments, which is the maximum accepted by the SCS TR-55 method. The average velocity is determined using a weighted average based upon the velocity in each flow segment and the travel time for each segment.

Project : COLESVILLE LANDFILL County : BROOME Subtitle: CHANNEL DC-1-3	, State: NY	User: Checked:	крн <b>јЪ<sup>-</sup>ђ</b>	Date: 01-1 Date: <u>//2</u>	
COVER DESCRIPTION		Hy A	drologic B Acres (	Soil Group C (CN)	D -
FULLY DEVELOPED URBAN AREAS (Ve Open space (Lawns,parks etc.) Good condition; grass cover >		-	_	- 13.1(	(80)
Total Area (by Hydrologic Soil	Group)			13.1 ====	-
TOTAL DRAINAGE	AREA: 13.1 Acr	es W	EIGHTED C	URVE NUMBER	R:80*
* - Generated for use by GRAPHI	C method				 

•

٩

By: 17:1 Date: 1/22/93 Chk: KPH Date: 1-25-9.3

GRASS LINED CHANNEL/DIVERSION DESIGN

Channel ID: PC-2 Peak Flow, Q = 26Ave. Slope, s = -0.5%

Select Basic Channel Geometry

Triangular, bottom width = 0 ftor Trapazoidal, bottom width = \_

Determine Required Lining

Max. Velocity for Grass Only = 3 F/sMax. Velocity for Jute Lining = \_\_\_\_A Max. Velocity for Erosion Control Mat = NA

From Table D at the given slope and flow, Velocity  $\leq 2.5 \neq 7$ Therefore use; Grass Jute, or Erosion Control Mat (circle one)

**Determine Channel Depth:** 

- For Max. Velocity using Table D

$$Q = 333$$
 at  $V = 2.5$  and  $d = 2.1$ 

- For Max. Capacity using Table C

$$Q = \frac{29.4}{4}$$
 at  $V = \frac{2.6}{2.6}$  and  $d = \frac{2.2}{4}$ 

Therefore set Total Depth = 2.5 inc. Freeboard and Settlement

SUPHILL SCOPE WILL BE THE Channel Side Slope (z:1), Z = 3 [ Scope of Frunc cover, Arroy. 14:1, THEREFORE THIS CALC WILL BE CONSERVATIVE FOR BOTH MAY. DEM VELOCITY

GRASS LINED CHANNEL/DIVERSION WORKSHHET PREPARED IN ACCORDANCE WITH THE SCS ENGINEERING FIELD MANUAL FOR CONSERVATION PRACTICES AND THE STANDARDS FOR SOIL EROSION AND SEDIMENT CONTROL IN NEW JERSEY

Table C

RETARDANCE 'C' SIDE SLOPE (2:1) BOTTOM WIDTH (B) =

	2.0	
		1
		'
	1.5	
		1
<b>со</b> 0		
3) =	1.0	
: (z:1) DTH (I		-
DE SLOPE (z:1) )TTOM WIDTH (B) =		

VELOCITY		1.0			1.5			2.0			2.5			3.0		.,	3.5		4	4.0		4.5			5.0			6.0	
SLOPE	α	Ð	a	æ	τ	σ	œ	τ	σ	œ	Ð	a	œ	τ	σ	Œ	Ð	a	В		œ	P	σ	œ	Ρ	a	œ	σ	σ
0.5%	0.85	1.8	9.6	0.95	5.0 2.0	18.0	1.05	2.2	9.4	.18	2.5 4	46.4 1	1.35	2.8 7	72.9 1	.50	3.2 **		1.65 3	3.5 14	145 1.82	2 3.8		_	4.3	280	2.50	5.3	
1.0%	0.76	1.6	7.7	0.72	1.5	10.4 0	0.79	1.7 1	16.6 0	0.86	1.8	24.7 0		2.0 3		1.05	5		_	4 66	9 1.25	2.6	93.6	_	2.8	122	1.62		210
1.5% (	0.53	1.1	3.7	0.59	1.2	7.0	0.65	1.4 1	11.3 0	17	1.5 1	16.8 0	1	1.6 2		_	<u>8</u>			1.9 44		8 5	57.6	_	2.2	73.5	1.22	2.6	
2.0%	0.50		3.3	0.56	1.2	6.3	0.60	1.3	9.6	1.65	1.4 1	4.1 0	.70	1.5		0.76	9		0.82	7 35			46.5	_		57.7	1.10	2.3	
2.5%	G.46	9.7 S	2.8	6.58	*.	5.6	6.54		7.5 0	0.55	2	ii.2   û	Ũ.Ô2	1.3 1	15.4 0	~—	1.4 2	20.9 0.		1.5 27.6		7 1.6	35.6	i 1.05 i	5 2.2	73.5	~		69.2
3.0%	0.44	0.9	2.6	0.48	1.0	4.6	0.52	:	7.2 0	0.56	1.2 1	0.5 0		1.2		0.64	€. ±			4 23			30.5	_		57.7			
3.5%	0.40	0.8	2.1	0.44	0.9	3.9	0.47	1.0	5.9 0	0.50	1:1	8.3					₩ 19				_	5 1.4	52.3			_	_	1.6	
4.0%	0.38	0.8	1.9	0.42	0.9	3.5	0.45 0	0.9	5.4 0	0.48	1.0	7.7 0		_			2 7			2 17.9			22.3	_	50			1.5	42.6
- X:2:2	<del>6.6</del> 7	9.9 9	;0	0.35	نه د	3.5	0.42	<u>.</u>	4.7 5	0.45		<u>6.7  </u> 0	.4 <u>8</u>				<u>-</u>		0.53	1.1 [15	0 0.57	1-1-2	6	_		73.5	·		—
7.0% 0.32	0.32	0.7	1.4	0.35	0.7	2.4	0.37	0.8	3.7 0	0.39	0.8	5.1 0	.41	_		0.43	6.0					<del>7</del>	13.6	0.9	2.0		0.56	1.2	25.1
10.0%	0.28	0.6	1.0	0.31	0.7	1.9	0.32	0.7	2.7 0	0.35	0.7	4.1	0.36	0.8	5.2 0			6.7 0.			8.5 0.42	2 0.9	10.6	1.0	2.2	73.5	0.48	1.0	18.4

d = DEPTH OF CHANNEL IN FEET (NOT INCLUDING ALLOWANCES FOR FREEBOARD, LINING INSTALLATION, OR SETTLEMENT) R = HYDRAULIC RADIUS FROM FIGURE A6-2 **VELOCITY IN FPS** Q = FLOW IN CFS

RETARDANCE 'C; 01/22/93 (file: jhf disc: tools:retard'c.wk1)

GRASS LINED CHANNEL/DIVERSION WORKSHHET PREPARED IN ACCORDANCE WITH THE SCS ENGINEERING FIELD MANUAL FOR CONSERVATION PRACTICES AND THE STANDARDS FOR SOIL EROSION AND SEDIMENT CONTROL IN NEW JERSEY Table D

	e	0
RETARDANCE 'D'	SIDE SLOPE (z:1)	BOTTOM WIDTH (B)

VELOCITY		1.0		-	S		2.0	~		2.5			3.0	-	_	3.5			4.0			4.5			5.0		Ŭ	6.0
SLOPE	æ	P	a	R	σ	R R	P	σ	œ	σ	σ	æ	σ	σ	œ	σ	σ	æ	Ð	σ	œ	τ	σ	æ	Ð	σ	œ	p
0.5%	0.6	1.3	4.8	0.73 1.	5 10	10.7 0.86	36 1.8	3 19.7	7 1.00	2.1	33.3	1.15	2.4	52.9	1.33	2.8	82.5	1.51	3.2	122	1.70	3.6	173 1	.95 4	5	254 2	2.40	.1 461
	0.44	6.0	2.6 0.	0.53 1.1	_	5.6 0.62	32 1.3	3 10.3	3 0.70	1.5	16.3	0.79	1:	25.0	0.90	1.9	37.8	1.00	2.1	53.3	1.10	2.3	72.6 1	1.23 2	5.6	100	1.50	3.2 180
1.5% 0	0.36 0	0.8	1.8 0.	0.43 0.9		3.7 0.50	1.1		7 0.56		10.5	0.64	1.3	16.4	0.70	1.5	22.9	0.79	1.7	33.3	0.86	1.8	44.4 0	0.95 2	2.0 6	60.2 1	1.10	2.3 96.8
2.0% (		0.7	1.5 0.3	0.39 0.8		_			_		8.7	0.57	1.2	13.0	0.62	1.3	17.9	0.69	1.5	25.4	0.76	1.6	34.7 0	0.84 1	1.8 4	47.0 1	00.1	2.1 80.0
2.5% (		0.6	_		_			8 4.1	_		6.5	0.58	1.2	13.5	0.54	-	13.6	0.60	1.3	19.2	0.65	1.4	25.3 0	1	1.5 3	33.6 0	0.85	1.8 57.8
3.0% (			1.0 0.1	33 0.7		2.1 0.3	_		7 0.42		5.9	0.46	1.0	8.5	0.51		12.1	0.56	_	_	0.60	1.3	21.6 0	0.67 1	1.4 2	29.9 0	0.78	1.6 48.7
3.5% 0.25		0.5	0.8	0.29 0.		.7 0.33	33 0.7		_		4.7	0.41	0.9	6.7	0.45	0.9	9.5	0.50	1.1	13.3	0.54	1.1	17.5 0	0.58 1	1.2 2	22.4 0	0.67	1.4 35.9
4.0% (			0.8 0.3	28 0.6	_	1.6 0.3			6 0.35	_	4.1	0.39	0.8	6.1	0.43	0.9	8.6	0.47	1.0	11.8	0.51		15.6 0	0.55 1	1.2 2	20.2 0	0.63	1.3 31.8
5.0% 0		0.5	0.7 0.	0.26 0.5	_	1.4 0.30	30 0.6	6 2.4		<u>`</u>	3.6	0.36	0.8	5.2	0.40	0.8	7.3	0.43	0.9	9.9	0.47	- -	13.3 0	0.51 1		17.3 0	0.59	1.2 27.8
7.0%	_		ö	0.23 0.5		1.1 0.26	26 0.5		8 0.28	9.0	2.6	0.31	0.7	3.8	0.34	0.7	5.4	0.37	0.8	7.3	0.39	0.8	9.1	0.42 0	0.9 1	11.8 0	0.48	1.0 18.4
10.0%						0.5	0.24 0.5		1.5 0.24	1 0.5	1.9	0.26	0.5	2.7	0.28	0.6	3.7	0.31	0.7	5.1	0.33	0.7	6.3	0.35 0	0.7	8.2 0	0.40	0.8 12.8

**VELOCITY IN FPS** 

R = HYDRAULIC RADIUS FROM FIGURE A6-3 d= Depth of channel in feet (not including allowances for freeboard, lining installation, or settlement) Q = FLOW IN CFS


RETARDANCE 'D; 01/22/93 (file: jhf disc: tools:retard'd.wk1)

By: **17:** Date: 1/24 • > Chk: <u>KPH</u> Date: 1-26-93

## GRASS LINED CHANNEL/DIVERSION DESIGN

Channel ID: <u>PC-2A-</u> Peak Flow, Q = 26 CF5 Ave. Slope, s = \_\_\_\_\_ %

Select Basic Channel Geometry



Determine Required Lining

Max. Velocity for Grass Orily = \_\_\_\_\_ Max. Velocity for Jute Lining = \_\_\_\_A Max. Velocity for Erosion Control Mat = NA-

From Table D at the given slope and flow, Velocity  $\leq 2.5$  Fps Therefore use: Grass, Jute, or Erosion Control Mat (circle one)

**Determine Channel Depth:** 

- For Max. Velocity using Table D

$$Q = 34.3$$
 at  $V = 2.5$  and  $d = 1.7$ 

- For Max. Capacity using Table C

$$Q = 30.2$$
 at  $V = 20$  and  $d = 1.8$ 

Therefore set Total Depth = 2.5 inc. Freeboard and Settlement

GRASS LINED CHANNEL/DIVERSION WORKSHHET PREPARED IN ACCORDANCE WITH THE SCS ENGINEERING FIELD MANUAL FOR CONSERVATION PRACTICES AND THE STANDARDS FOR SOIL EROSION AND SEDIMENT CONTROL IN NEW JERSEY Table C

RETARDANCE 'C' SIDE SLOPE (z:1)

**ო** ო BOTTOM WIDTH (B) =

VELOCITY		1.0			1.5			2.0			2.5			3.0			3.5			4.0			4.5			5.0		9	6.0
SLOPE	æ	σ	σ	ж	σ	σ	æ	σ	σ	æ	P	σ	æ	σ	σ	æ	Ð	σ	æ	σ	σ	æ	P	σ	æ	P	σ	۳ ۳	
0.5%	0.85	1.4	10.1	0.95	1.6	18.7	1.05	1.8	30.2	1.18	2.1	47.3	1.35	2.4	73.8	1.50	2.7		1.65	3.0	146 1	1.82	3.4	199 2	2.05	3.9 2	281 2.	2.50 4	4.8 500
1.0% 0	0.76	1.2	8.2	0.72	1.1	11.1	0.79	1.3 1	17.5 0	0.86	1.4	25.7 (	0.94	1.6	36.6	1.05	1.8	52.8	1.12	1.9	68.4 1	1.25	2.2	95.2 1	1.35	2.4 1	123 1.	1.62 3	3.0 2
1.5%	0.53	0.8	4.2	0.59	0.9	7.7	0.65	1.0	12.2	0.71	1.1	18.0 0	0.77	1.2	25.1	0.84	4.	34.5	0.91		45.9 0	0.98	1.7 5	59.5 1	1.05	1.8 75	75.4 1.	1.22 2.1	
2.0%	0.50	0.7	3.8	0.56	0.8	7.0	0.60	0.9 1	10.6 0	0.65	1.0	15.3	0.70	1.1	21.0	0.76	1.	_	0.82	1.3	37.6 0	0.88	1.5 4	48.4 0	0.93	1.6 59	59.8 1.	1.10 1	1.9 99
2.5%	0.46	0.7	3.3	0.50	0.7	5.7	0.54	0.8	8.8	0.58	0.9	12.4 (	0.62	1.0	16.8	0.67	-	22.6	0.72	7	29.5 0	0.7	1.2 3	37.6 1	1.05	1.8 75	75.4 0.	0.93 1	1.6 71.7
3.0%	0.44	0.6	3.1	0.48	0.7	5.3	0.52	0.8	8.2	0.56	0.8	11.7 0	0.59	0.9	15.4	0.64	0.1	20.8	0.67	1.1	25.8 0	0.71	1.1 3	32.4 0	0.93	1.6 59	59.8 0.	0.86 1	1.4 61.8
3.5%	0.40	0.6	2.6	0.44	0.6	4.6	0.47	0.7	6.9	0.50	0.7	9.6	0.53	0.8	12.7	0.58	6.0	17.4	0.61	0.9	21.8 0	0.65	1.0 2	27.5 1	1.05	1.8 75	75.4 0.	0.77	1.2 50.2
4.0% 0.38	0.38	0.5	2.4	0.42	0.6	4.3	0.45	0.6	6.4	0.48	0.7	8.9	0.51	0.8	11.9	0.55	8.0	15.8	0.58	0.9	19.9 0	0.61 0	0.9 2	24.5 0	0.93	1.6 55	59.8 0.	0.73 1	1.2 45.4
5.0%	0.37	0.5	2.3	0.39	0.5	3.8	0.42	0.6	5.7	0.45	0.6	8.0	0.48	0.7	10.7	0.51	0.8	13.9	0.53	0.8	16.9 0	0.57 (	0.9 2	21.7 1	1.05	1.8 75	75.4 0.	0.66 1	1.0 37.7
7.0% 0.32	0.32	0.4	1.8	0.35	0.5	3.2	0.37	0.5	4.6	0.39	0.5	6.3	0.41	9.0	8.2	0.43	0.6	10.3	0.46	_	13.2 0	0.48	0.7 1	16.0 0	0.93	1.6 59	59.8 0.	0.56 0	0.8 28.0
10.0% 0.28	0.28	0.4	1.5	0.31	0.4	2.6	0.32	0.7	2.7	0.35	0.5	5.3	0.36	0.5	6.6	0.38	0.5	8.4	0.40	0.6	10.5 0	0.42	0.6	12.8 1	1.05	1.8 75	75.4 0.	0.48 0	0.7 21.4

**VELOCITY IN FPS** 

R = HYDRAULIC RADIUS FROM FIGURE A6-2

d = DEPTH OF CHANNEL IN FEET (NOT INCLUDING ALLOWANCES FOR FREEBOARD, LINING INSTALLATION, OR SETTLEMENT) Q = FLOW IN CFS

RETARDANCE 'C; 01/22/93 (file: jhf disc: tools:retard'c.wk1)

Table D

GRASS LINED CHANNEL/DIVERSION WORKSHHET PREPARED IN ACCORDANCE WITH THE SCS ENGINEERING FIELD MANUAL FOR CONSERVATION PRACTICES AND THE STANDARDS FOR SOIL EROSION AND SEDIMENT CONTROL IN NEW JERSEY

RETARDANCE 'D' SIDE SLOPE (2:1) BOTTOM WIDTH (B)

e

"	0		
1			
		•	

SLOPE R				2			D'N	_	J	2.1		,	2		C.D			4.0			4.0			0.0			9.0	
	σ	σ	œ	σ	σ	æ	P	σ	а	F	ч о	ш	о Р	α α	σ	σ	æ	σ	σ	æ	p	σ	æ	τ	σ	H	p	σ
0.5% 0.6		5.3	0.73	1.2	<u> </u>	0.86	1.4	20.6 1	1.00	1.7 34	·	1.15 2	2.0 54.0	.0 1.33	3 2.4	83.6	3 1.51	2.7	123	1.70	3.1		1.95	3.6		2.40	4.6	461
1.0% 0.44		3.1	0.53	_	6.4	0.62	1.0	_	0.70 1		17.5 0.7		1.3 26.3	.3 0.90	1.5	39.3	3 1.00	1.7	54.9	1.10	6.	74.3	1.23	2.2	102 1	1.50	2.7	182
1.5% 0.36	0.5	2.2			4.4			7.6 0	0.56 0		.7 0.64		1.0 17.8	.8 0.70		24.5	5 0.79	1.3	35.1	0.86	4.1	46.3 0	0.95	1.6	62.2	1.10	1.9 9	0.66
2.0% 0.33	0.4	1.9	_	0.5	3.8 (	0.45	0.6	6.4 0		0.8	9.0 0.6	0.57 0	0.9 14.5	.5 0.62	1.0	19.6	_	=	27.3	0.76	_	36.7	·	1,4 4	49,2 1		1.7 8	82.4
2.5% 0.29			<b>-</b>	~	3.0	<u> </u>	~	-		_	_	0.58 0	0.9 14.				3 0.60	0.9	21.1	_		_	_	1.1	36.0 0			0.4
3.0% 0.28		1.5	_		2.8			4.6 0			7.1 0.4	0.46 0	0.7 9.	9.9 0.51	0.8	_	9 0.56	0.8	18.7	0.60	6.0	23.8	0.67	1.1	32.3 0		1.3 5	51.4
3.5% 0.25	0.3	1.3	0.29		2.3		0.4		0.38 0	_	_			8.2 0.45		11.2	0.50	0.7	15.3	0.54	0.8			0.9	24.9 0	_	1.1 3	38.8
4.0% 0.24		_	_	_	2.2	_		_			5.3 0.3		0.5 7.	_				0.7	_	0.51	0.8	17.8 0			<u>'</u>	0.63	1.0.13	34.6
3.0% 0.22		7			2.0	.—	.—	3.3 0			8 0.36			6.6 0.40	0.6			0.6		0.47			0.51	0.8	19.8 0		0.9 3	30.8
7.0%				0.3	1.7			_	0.28 0	0.4 3	3.7 0.3		0.4 5.	5.2 0.34	1 0.5	7.0	0.37	0.5	9.2	0.39	0.5	11.3	0.42		14.2 0	0.48	0.7 2	21.4
10.0%					-	0.24	0.5	1.5 0	0.24 0		2.9 0.2			4.0 0.28		5.2		0.4	6.9	0.33	0.4	8.4	_	0.5	_	_	0.6	15.7

**VELOCITY IN FPS** 

d = DEPTH OF CHANNEL IN FEET (NOT INCLUDING ALLOWANCES FOR FREEBOARD, LINING INSTALLATION, OR SETTLEMENT) Q = FLOW IN CFS R = HYDRAULIC RADIUS FROM FIGURE A6-3

RETARDANCE 'D; 01/22/93 (file: jhf disc: tools:retard'd.wk1)

By 100 Date 1-21-93 Chkd. 12.14 Date 1/22/13

DIVERSION CHANNEL DESIGN - GABION LINING JOB NO. 00000 XX

COLESVILLE LANDFILL CHANNEL DC-2 INLET CHANNEL

\_\_\_\_\_\_ 26.0 3.0 CHANNEL SIDESLOPE - RIGHT SIDE (HORIZ/VERT) . . . . . . . 3.0 3.0 0.025 6.0 0.5 BEGIN CALCULATIONS AT CHANNEL DEPTH (FT) . . . . . . . . 0.5 

CHANNEL DEPTH (FT)	X-SECT AREA (SQ FT)	TOP WIDTH (FT)	HYDRAULIC RADIUS (FT)	DISCHARGE (CFS)	VELOCITY (FPS)	FROUDE NUMBER Nf
0.5	2.3	6.0	0.37	12.4	5.5	1.59
0.6	2.9	6.6	0.42	17.6	6.1	1.63
0.7	3.6	7.2	0.48	23.7	6.6	1.66
0.8	4.3	7.8	0.54	30.9	7.1	1.69
0.9	5.1	8.4	0.59	39.1	7.6	1.72
1.0	6.0	9.0	0.64	48.4	8.1	1.74
1.1	6.9	9.6	0.70	58.9	8.5	1.76
1.2	7.9	10.2	0.75	70.6	8.9	1.78
1.3	9.0	10.8	0.80	83.6	9.3	1.80
1.4	10.1	11.4	0.85	97.9	9.7	1.82
1.5	11.3	12.0	0.90	113.6	10.1	1.84

DESIGN DEPTH OF FLOW, D (FT)	0.8
VELOCITY, V (FPS)	7.1
TOTAL DEPTH INCLUDING FREEBOARD (FT)	1.3
GABION THICKNESS, t (IN)	6.0
FILLING STONE SIZE, d50 (IN)	3.0

TR-55 GRAPHICAL DISCHARGE METHOD Project : COLESVILLE LANDFILL User: KPH County : BROOME State: NY Checked: VERSION 1.11 Date: 01-14-93 Date: <u>//22/93</u>

Data:	Drainage Area	:	11.6 * Acres
	Runoff Curve Number	:	80 *
	Time of Concentration	1:	0.55 * Hours
	Rainfall Type	:	II
	Pond and Swamp Area	:	NONE

Storm Number	1	2	3	4	5	6
Frequency (yrs)	2	5	10	25	50	100
24-Hr Rainfall (in)	2.8	3.5	4.3	4.9	5.3	5.9
Ia/P Ratio	0.18	0.14	0.12	0.10	0.09	0.08
Used	0.18	0.14	0.12	0.10	0.10	0.10
Runoff (in)	1.10	1.64	2.29	2.81	3.16	3.69
Unit Peak Discharge (cfs/acre/in)	0.733	0.757	0.775	0.785	0.787	0.787
Pond and Swamp Factor 0.0% Ponds Used	1.00	1.00	1.00	1.00	1.00	1.00
Peak Discharge (cfs)	9	14	21	26	29	34

\* - Value(s) provided from TR-55 system routines

-----

¥	Project : County : Subtitle:	COLESVILLE	E LANDFIL		U SUBAREA : NY		PUTATION User: KPI ecked:	н	VERSION Date: 01- Date: //22	14-93
	Flow Type	2 year rain	Length (ft)		Surface code	n	Area (sq/ft)	_	Velocity (ft/sec)	Time (hr)
•	Sheet Open Chann	2.8 Nel	120 1300	.01	E		Time of (	Concent	1.2 tration = (	0.252 0.301 0.55*
	A Smoo B Fall C Cult D Cult	- Sheet Fl oth Surface ow (No Res ivated < 2 ivated > 2 s-Range, S	2 5.) 20 % Res. 20 % Res.	F Gra: G Gra: H Wood	ss, Dense ss, Burmu ds, Light ds, Dense	da	Sha: 	Surfac P Pa	oncentrated ce Codes aved npaved	1 

\* - Generated for use by GRAPHIC method

TR-55 CURVE NUMBER Project : COLESVILLE LANDFILL County : BROOME State: NY Subtitle: CHANNEL DC-2	User:	<sup>крн</sup> <b>}#</b> Ъ	VERSION 1.1 Date: 01-14-9 Date: 1/22/92	3
COVER DESCRIPTION	Ну А	drologic B Acres (	Soil Group C D CN)	
FULLY DEVELOPED URBAN AREAS (Veg Estab.) Open space (Lawns,parks etc.) Good condition; grass cover > 75%	-	-	- 11.6(80)	•
Total Area (by Hydrologic Soil Grour <sub>/</sub> )			11.6 ====	
TOTAL DRAINAGE AREA: 11.	6 Acres W	EIGHTED C	URVE NUMBER:80	* 🖤
<ul> <li>* - Generated for use by GRAPHIC method</li> </ul>	·			

By: 12: Date: 1/23/93 Chk: KPII Date: 1-25-93

### GRASS LINED CHANNEL/DIVERSION DESIGN

Channel ID: pc - 3Peak Flow, Q = 3cF5Ave. Slope, s = 0.5%

Select Basic Channel Geometry

Triangular, bottom width = 0 ft

Trapazoidal, bottom width = \_\_\_\_\_

Channel Side Slope (z:1), Z = \_\_\_\_

**Determine Required Lining** 

Max. Velocity for Grass Only =  $3 \bullet$  FPS Max. Velocity for Jute Lining = NAMax. Velocity for Erosion Control Mat = NA

From Table D at the given slope and flow, Velocity  $\leq 1.0$  Frs Therefore use: Grass, Jute, or Erosion Control Mat (circle one)

**Determine Channel Depth:** 

- For Max. Velocity using Table D

 $Q = \frac{4.8}{1.0}$  at  $V = \frac{1.0}{1.0}$  and  $d = \frac{1.3}{1.3}$ 

- For Max. Capacity using Table C

Q = 3.6 at V = 0.5 and d = 1.5

Therefore set Total Depth = 2.0 inc. Freeboard and Settlement

PREPARED IN ACCORDANCE WITH THE SCS ENGINEERING FIELD MANUAL FOR CONSERVATION PRACTICES AND THE STANDARDS FOR SOIL EROSION AND SEDIMENT CONTROL IN NEW JERSEY **GRASS LINED CHANNEL/DIVERSION WORKSHHET** Table C

RETARDANCE 'C' SIDE SLOPE (z:1)

**ω** Ο BOTTOM WIDTH (B) =

VELOCITY		1.0			1.5			2.0			2.5		e	3.0		3.5			4.0			4.5			5.0			6.0	
SLOPE	æ	þ	σ	æ	Ð	σ	æ	Ð	σ	Ē	-	σ	œ	о Р	æ	P	σ	œ	Ρ	σ	œ	P	σ	α	Ð	σ	œ	τ	σ
0.5%	0.85	1.8	9.6	0.95	2.0 1	18.0 1.	1.05	2.2 2	29.4 1	.18 2	.5 46	46.4 1.	1.35 2	2.8 72	72.9 1.50	3.2	:	1.65	3.5	145	1.82	3.8	199	2.05	4.3	280	2.50	5.3	500
1.0%	0.76	1.6	7.7	0.72	1.5 1	10.4 0.	0.79	1.7	16.6 0	0.86 1	.8	24.7 0.9	0.94 2	2.0 35.3	.3 1.05		51.5	5 1.12	2.4	66.9	1.25		93.8	1.35	2.8	122	1.62	3.4	210
1.5%	0.53		3.7	0.59	1.2	7.0 0.	0.65	1.4 1	11.3 0	0.71	.5 16			1.6 23.7	.7 0.84	4 1.8	32.9	9 0.91	1.9	44.2		2.1	_	1.05	2.2	73.5	1.22	2.6	
2.0%	0.50		3.3	0.56	1.2	6.3 0.	0.60	1.3	9.6	0.65 1	4 14	14.1 0.	0.70	.5 19.6	.6 0.76	5 1.6		0 0.82	1.7	_			_	0.93	2.0	57.7	01.10	2.3	<u>96.8</u>
2.596	2 596 0.46	20	2.8	0.50	÷.,	€.8 8.	6.54		7.5 0	0.56	بة ت		~		-	۰ <u></u>	~	·	. <u> </u>	·—	_	_		1.05	2.2	73.5		2.0	69.2
3.0%	0.44	6.0	2.6	0.48	1.0	4.6 0.	0.52	1.1	7.2 0	0.56 1	1.2 10								1.4		_	1.5	_	0.93	2.0	57.7		1.8	59.2
3.5%	3.5% 0.40	0.8	5.1	0.44	6.0	3.9 0.	0.47	1.0	5.9 0	0.50 1	1.	_		1.1 11		8 1.2	_	7 0.61		19.8	_	_		1.05	2.2	73.5	_		47.4
4.0%	0.38	0.8	1.9	0.42	0.9	3.5 0.	0.45 0	6.0	5.4 0	0.48 1	1.0 7	7.7 0.51					_	_	1.2	_	_	_		0.93	2.0	_	0.73	, 1 2	42 G
Y DOL	1.27	0) C)	¢,		ç; ç;	<del>0.0</del>	5.42	5.3	4.7.16	Ú.45 0	0.9	o./ 0.			.2 0.51		<u> </u>	<u> </u>		·	0.57		19.5	1.05	22		0.66	1.4	34.8
7.0%	7.0% 0.32	0.7	1.4	0.35	0.7	2.4 0.	0.37 0	0.8	3.7 0	0.39 0	0.8 5			0.9 6.0	6.7 0.45	3 0.9	_	5 0.46		11.3		1.0		0.93	2.0	57.7	0.56	1.2	25.1
10.0% 0.28	0.28	0.6	1.0	0.31	0.7	1.9 0.	0.32	0.7	2.7 0.35		0.7 4	4.1 0.5	0.36 0		5.2 0.38	3 0.8	8 6.7	7 0.40			_			1.05	2.2	_		1.0	18.4
		1			•				¢																				

@ 0.5% and 0.5 fps , K= ,73, J= 1.5, and Q= 3.6 CFS Note:

d = DEPTH OF CHANNEL IN FEET (NOT INCLUDING ALLOWANCES FOR FREEBOARD, LINING INSTALLATION, OR SETTLEMENT) R = HYDRAULIC RADIUS FROM FIGURE A6-2 **VELOCITY IN FPS** Q = FLOW IN CFS

RETARDANCE 'C; 01/22/93 (file: jhf disc: tools:retard'c.wk1)

PREPARED IN ACCORDANCE WITH THE SCS ENGINEERING FIELD MANUAL FOR CONSERVATION PRACTICES AND THE STANDARDS FOR SOIL EROSION AND SEDIMENT CONTROL IN NEW JERSEY **GRASS LINED CHANNEL/DIVERSION WORKSHHET** Table D

**m** 0 RETARDANCE 'D' SIDE SLOPE (z:1) BOTTOM WIDTH (B) =

VELOCITY		1.0			1.5			2.0			2.5			3.0			3.5			4.0		4	4.5		ŝ	o		9	o,
SLOPE	щ	σ	σ	ч	Ρ	σ	æ	Ρ	σ	æ	σ	σ	æ	τ	σ	æ	Ρ	σ	œ	p	σ	E.	P	σ	æ	P	σ	æ	o F
0.5%	0.6	1.3	4.8	0.73	1.5	10.7	0.86	8	19.7	1.00	2.1	33.3	1.15	2.4	52.9	1.33	2.8	82.5	1.51	3.2	122 1	.70 3	3.6 1	1.23	1.95 4	م ج-	54 2.	40 5	.1 46
1.0%	0.44	0.9	2.6	0.53	1.1	5.6	0.62	1.3	10.3	0.70	1.5	16.3	0.79	1.7	25.0	06.0	1.9	37.8	1.00	2.1	53.3 1	1.10 2	2.3 7		1.23 2	2.6 1	100 1.	1.50 3	2 180
1.5%	0.36	0.8	1.8	0.43	0.9	3.7	0.50	1.1	_	0.56	2.1	10.5	0.64	1.3	_	0.70	1.5	_	0.79	1.7	33.3 0	0.86		44.4		2.0 6(	60.2 1.	1.10 2	2.3 96.
2.0%	0.33	0.7	1.5	0.39	0.8	3.0	0.45	0.9	5.4	0.51	:	8.7	0.57	1.2	_	0.62	1.3	17.9 0	0.69	1.5	25.4 0	0.76 1	1.6 3		0.84 1	1.8	47.0 1.	1.00 2.1	1 80.0
2.5%	0.29	0.6	÷	0.34	0.7	2.3	0.39	0.8	4.1	0.44	0.9	6.5	0.58	1.2		0.54		_	0.60		_	0.65 1			0.71	1.5 3:	33.6 0.	0.85 1	1.8 57.
3.0%	0.28	0.6	1.0	0.33	0.7	2.1	0.37		3.7	0.42	0.9	5.9	0.46	1.0	8.5	0.51	÷		0.56		16.7 0	.60			_	1.4 29	29.9 0.		1.6 48.7
3.5%	0.25	0.5	0.8	0.29	0.6	1.7	0.33	0.7	2.9	0.38	0.8	4.7	0.41	6.0	6.7	0.45	_		0.50	-					0.58 1	1.2	22.4 0.	0.67 1	1.4 35.9
4.0%	0.24	0.5	0.8	0.28	0.6	1.6	0.32		2.6	0.35	0.7	4.1	0.39	0.8	6.1	0.43	6.0	8.6	0.47	1.0	11.8 0	0.51 1			0.55 1	1.2 2	20.2 0.	0.63 1	1.3 31.8
5.0% (	0.22	0.5	0.7	0.26	0.5	4.1	0.30	9.0	2.4	0.33	0.7	3.6	0.36	0.8	5.2	0.40	0.8	7.3	0.43	0.9	9.9	0.47 1			0.51 1	1.1	17.3 0.	0.59 1	1.2 27.8
7.0%				0.23	0.5		0.26	0.5	1.8	0.28	0.6		0.31	0.7	3.8	0.34	0.7	5.4	0.37	0.8	7.3 0	_	0.8	9.1	0.42 0	0.9	11.8 0.	0.48 1	1.0 18.4
10.0%							0.24	0.5	1.5	0.24	0.5	1.9	0.26	0.5	2.7	0.28	0.6	3.7	0.31	0.7	5.10	0.33	0.7	6.3 0	0.35 0	0.7	8.2 0.	0.40	0.8   12.8

**VELOCITY IN FPS** 

R = HYDRAULIC RADIUS FROM FIGURE A6-3 d = DEPTH OF CHANNEL IN FEET (NOT INCLUDING ALLOWANCES FOR FREEBOARD, LINING INSTALLATION, OR SETTLEMENT) Q = FLOW IN CFS

RETARDANCE 'D; 01/22/93 (file: jhf disc: tools:retard'd.wk1)

TR-55 GRAPHICAL DISCHARGE METHOD Project : COLESVILLE LANDFILL County : BROOME State: NY Subtitle: CHANNEL DC-3

User: KPH Checked:

VERSION 1.11 Date: 01-14-93 Date: 1/23/13

Data: Drainage Area : .8 \* Acres Runoff Curve Number : **80** \* Time of Concentration: 0.14 \* Hours Rainfall Type II : Pond and Swamp Area : NONE

Storm Number	1	2	3	=======   4	====== 5	=======   6
Frequency (yrs)	2	5	10	25	50	100
24-Hr Rainfall (in)	2.8	3.5	4.3	4.9	5.3	5.9
Ia/P Ratio	0.18	0.14	0.12	0.10	0.09	0.08
Used	0.18	0.14	0.12	0.10	0.10	0.10
Runoff (in)	1.10	1.64	2.29	2.81	3.16	3.69
Unit Peak Discharge (cfs/acre/in)	1.364	1.390	1.409	1.420	1.421	1.421
Pond and Swamp Factor 0.0% Ponds Used	1.00	1.00	1.00	1.00	1.00	1.00
Peak Discharge (cfs)	1	2	3	3	4	4

\* - Value(s) provided from TR-55 system routines

•	Project : COLL County : BROO Subtitle: CHAN	ESVILLE L O <mark>ME</mark>	ANDFILL		J SUBAREA		PUTATION User: KPI cked:		VERSION Date: 01- Date: <u>//2</u>	14-93
č.		-	ength (ft)	Slope (ft/ft)	Surface code	n	Area (sq/ft)	_	Velocity (ft/sec)	Time (hr)
<b>.</b>	Sheet 2 Open Channel		100 230	.11	E		Time of (	Concent	1.2 tration = (	0.084 0.053 0.14*
	Sh A Smooth S B Fallow C Cultivat D Cultivat E Grass-Ra	(No Res.) ted < 20 ted > 20	% Res. % Res. rt	F Gras G Gras H Wood	s, Dense s, Burmud ls, Light ls, Dense		Sha] 	Surfac P Pa	oncentrated ce Codes aved npaved	1 

\* - Generated for use by GRAPHIC method

TR-55 CURVE NUMBER CO Project : COLESVILLE LANDFILL County : BROOME State: NY Subtitle: CHANNEL DC-3	User:	<sup>крн</sup> <del> }**</del> ү	VERSION 1.11 Date: 01-14-93 Date: <u>//2&gt;//}</u>
COVER DESCRIPTION	ну А	drologic B Acres	
FULLY DEVELOPED URBAN AREAS (Weg Estab.) Open space (Lawns,parks etc.) Good condition; grass cover > 75%	-	-	8(80)
Total Area (by Hydrologic Soil Group)	•		.8
TOTAL DRAINAGE AREA: .8 Acr	es W	EIGHTED	CURVE NUMBER:80*
* - Generated for use by GRAPHIC method			_

By: 121 Date: 1/22/93 Chk: KON Date: 1-25-93

#### GRASS LINED CHANNEL/DIVERSION DESIGN

Channel ID: PC - 4 - 1Peak Flow, Q = M (F) Ave. Slope, s = 3 - 7

Select Basic Channel Geometry

Triangular, bottom width = 0 ft rapazoidal, bottom width = **7'** Channel Side Slope (z:1), Z = **3** 

# **Determine Required Lining**

Max. Velocity for Grass Only = <u>3</u>F/3 Max. Velocity for Jute Lining = <u>JUA</u> Max. Velocity for Erosion Control Mat = <u>MA</u>

From Table D at the given slope and flow, Velocity  $\leq 30$ Therefore use: Grass, Jute, or Erosion Control Mat (circle one)

#### Determine Channel Depth:

- For Max. Velocity using Table D

$$Q = \frac{14.5}{14.5}$$
 at V = 30 and d = 0.6

- For Max. Capacity using Table C

$$Q = 16.0$$
 at  $V = 2.5$  and  $d = 0.7$ 

Therefore set Total Depth = 10 inc. Freeboard and Settlement

GRASS LINED CHANNEL/DIVERSION WORKSHHET PREPARED IN ACCORDANCE WITH THE SCS ENGINEERING FIELD MANUAL FOR CONSERVATION PRACTICES AND THE STANDARDS FOR SOIL EROSION AND SEDIMENT CONTROL IN NEW JERSEY Table D

RETARDANCE 'D' SIDE SLOPE (z:1) BOTTOM WIDTH (B) =

**σ** Γ

	1.0	_		1.5		- •	2.0			2.5			3.0			3.5		4	4.0		4.5	5		5.0	•		6.0	
SLOPE R	p	σ	œ	P	σ	æ	P	a	œ	σ	σ	æ	σ	- 0	н	P	a a	е Ш		а В	P ~	σ	œ	Ρ	a	œ	P	σ
	0.8		0.73	1.0 1	14.4 0	0.86		24.9 1	1.00	_	39.9 1	.15	1.7 6(	60.9 1.	33	2.0 91	.1.	.51 2	2.3 13	132 1.7	.70 2.7	7 185	5 1.95	3.2	266	3 2.40	4.1	474
	0.5		0.53		8.9	0.62 0	_	_	0.70			0.79	1.1 3	32.5 0.	0.90	1.2 46	46.9 1.(	.00	.4 63	63.9 1.1	1.10 1.6	<b>84.6</b>	5 1.23	8. - 8.	113	3 1.50	2.3	196
1.5% 0.36	0.4	3.5 0	0.43	0.5		0.50		_	0.56 (		_	0.64	0.8	23.5 0.	0.70 0	0.9 31	31.4 0.7	0.79 1	1.1 43	43.4 0.86	36 1.2	2 56.0	0.95	5 1.3	3 73.3	3 1.10	1.6	113
				,				9.4 0	_		14.0 0			19,7 0,	<u> </u>		26.1 0.6		0.9 35.1	1 0.76	76 1.0	45.9	10.84	1 3.3	6 65	001	_,_	95,9
	0.3	2.6 0							_			0.58	0.7 20		0.54 0	0.7 21	21.3 0.60		.8 28.4	.4 0.65	<b>55 0.8</b>	36.0	0.71	0.0	45.8	3 0.85	1.2	73.2
			0.33	0.4	4.6	0.37 0	4.0	_	0.42	0.5		0.46	0.6 1		0.51 0	0.6 19	9.6 0.56		0.7 25.7	.7 0.60	0.8	31.9	9 0.67	0.0	41.9	9 0.78		
	_		_									0.41	0.5 13		0.45 0	0.5 16	16.4 0.5	0.50 0	0.6 21.8	.8 0.54	54 0.7	7 27.4	1 0.58	3 0.7	33.8	3 0.67	0.0	50.3
4.0% 0.24	0.3	2.10	0.28	<u> </u>	<u> </u>			5.9 0			8.4 0	0.39	0.5 1	11.6 0.	0.43 0	0.5 11	15.4 0.47	—,-	0.6 20	20.0 0.51	1 0 R	25.0	0 0 55	۲ u J	31.0	0.63		AF B
0.22									-				0.4 10				3.8 0.43		0.5 17	17.7 0.47	17 0.6	5 22.5		0.6	3 28.0	0.59	0.7	41.5
7.0%		0	0.23		_	_		4.6 0	0.28 0		6.3 0	0.31	0.4	8.6 0.	0.34 0	0.4 11	11.3 0.3	0.37 0	0.4 14	14.4 0.39	39 0.5	5 17.4	1 0.42	0.5	21.4	1 0.48	0.6	30.9
10.0%	_				-	0.24 (	0.5	1.5 0	0.24 (		5.2 0	0.26	0.3	6.9 0.	0.28 0	0.3	8.8 0.31		0.4 11	11.5 0.33	33 0.4	13.7	7 0.35	5 0.4	16.8	3 0.40	0.5	24.0

VELOCITY IN FPS R = HYDRAULIC RADIUS FROM FIGURE A6-3 d = DEPTH OF CHANNEL IN FEET (NOT INCLUDING ALLOWANCES FOR FREEBOARD, LINING INSTALLATION, OR SETTLEMENT) Q = FLOW IN CFS

RETARDANCE 'D; 01/22/93 (file: )hf disc: tools:retard'd.wk1)

GRASS LINED CHANNEL/DIVERSION WORKSHHET PREPARED IN ACCORDANCE WITH THE SCS ENGINEERING FIELD MANUAL FOR CONSERVATION PRACTICES AND THE STANDARDS FOR SOIL EROSION AND SEDIMENT CONTROL IN NEW JERSEY Table C

3 BOTTOM WIDTH (B) = RETARDANCE 'C' SIDE SLOPE (z:1)

			_									
	σ	512	225	135	113	84.9	74.6	62.5	57.4	49.2	38.5	
9.0 9	Ð	4.3	2.6	1.8	1.6	1.3	1.2	1.0	1.0	0.9	0.7	\$
	æ	2.50	1.62	1.22	1.10	0.93	0.86	0.7	0.73	0.66	0.56	
	σ	292	135	86.8	70.7	86.8	70.7	86.8	70.7	86.8	70.7	0.00
5.0	p	3.4	2.0	1.5	1.3	1.5	1.3	1.5	1.3	1.5	1.3	,
	æ	2.05	1.35	1.05	0.93		0.93	1.05	0.93	1.05	0.93	
	σ	210	106	69.5	58.1		41.3	36.0	32.7	29.6	23.1	
4.5	p	2.9	1.9	1.4	1.2	1.0	0.9	0.8	0.8	0.7	0.6	
	œ	1.82	1.25	0.98	0.88	0.7	0.71	0.65	0.61	0.57	0.48	
	σ	155	77.6	54.6	46.1	37.5	33.5	29.1	27.0	23.7	19.4	
4.0	đ	2.6	1.6	1.3	:-	1.0	0.9	0.8	0.7	0.7	0.6	
	æ	1.65	1.12	0.91	0.82	0.72	0.67	0.61	0.58	0.53	0.46	
	σ	114	60.7	41.9	35.7	29.3	27.4	23.6	21.9	19.6	15.4	
3.5	σ	2.3	1.5	1:1	1.0	0.9	0.8	0.7	0.7	0.6	0.5	
	œ	1.50	1.05	0.84	0.76	0.67	0.64	0.58	0.55	0.51	0.43	
	σ	80.8	43.2	31.2	26.9	22.4	20.8	17.8	16.8	15.4	12.4	
3.0	p	2.0	1.3	1.0	6.0	0.8	0.7	0.7	0.6	0.6	0.5	
	ч	1.35	0.94	0.7	0.70	0.62	0.59	0.53	0.51	0.48	0.41	
	ð	53.1	31.1	22.9	20.0	16.9	16.0	13.6	12.9	11.7	9.7	,
2.5	σ	1.7	1.2	0.9	0.8	0.7	0.7	0.6	0.6	0.5	0.5	
	œ	1.18	0.86	0.71	0.65		0.56			0.45	0.39	
	σ	34.7	21.7	16.0	14.2	12.2	11.5	10.0	9.4	8.5	7.2	
20	σ	1.5	:	0.8	0.8	0.7	0.6	0.6	0.5	0.5	0.4	
	œ	1.05	0.79	0.65	0.60		0.52	0.47	0.45	0.42	0.37	
	σ	22.0	14.1	10.4	9.6	8.2	7.7	6.8	6.4	5.8	5.0	
1.5	σ	1.3	1.0	0.7	0.7	0.6	0.6		0.5	0.5	0.4	
	œ	0.95	0.72	0.59	0.56	0.50	0.48	0.44	0.42	0.39	0.35	
	σ	12.2	10.2		5.4	4.8	4.6	4.0	_	3.6		
1.0	σ	1.2	1.0	0.7	0.6	0.6	0.5	0.5	0.4	0.4		
	œ	0.85	0.76	0.53	0.50	0.46	0.44	0.40	0.38	0.37	0.32	
/ELOCITY	SLOPE	0.5%	1.0%	1.5% (	2.0%	2.5%	3.0%	3.5%	4.0%	5.0%	7.0%	

VELOCITY IN FPS

R = HYDRAULIC RADIUS FROM FIGURE 46-2 d = DEPTH OF CHANNEL IN FEET (NOT INCLUDING ALLOWANCES FOR FREEBOARD, LINING INSTALLATION, OR SETTLEMENT)

Q = FLOW IN CFS

RETARDANCE 'C; 01/22/93 (file: jhf disc: tools:retard'c.wk1)

Project : COLESVILLE LANDFILL County : BROOME State: NY Subtitle: CHANNEL DC-4-1

User: KPH Checked:

Date: 01-14-93 Date: //12/13

Data:	Drainage Area	:	4.9 * Acres
	Runoff Curve Number	:	80 *
	Time of Concentration	n:	0.32 * Hours
	Rainfall Type	:	II
	Pond and Swamp Area	:	NONE

Storm Number	1	; <b>_</b> _   2	3		======================================	======= 6
Frequency (yrs)	2	<del>;-</del> 5	10	25	 50	100
24-Hr Rainfall (in)	2.8	3.5	4.3	4.9	5.3	5.9
Ia/P Ratio	0.18	0.14	0.12	0.10	0.09	0.08
Used	0.18	0.14	0.12	0.10	0.10	0.10
Runoff (in)	1.10	1.64	2.29	2.81	3.16	3.69
Unit Peak Discharge (cfs/acre/in)	0.964	0.992	1.013	1.025	1.026	1.026
Pond and Swamp Factor 0.0% Ponds Used	1.00	1.00	1.00	1.00	1.00	1.00
Peak Discharge (cfs)	5	<del></del> 8:	11	14	16	19

\* - Value(s) provided from TR-55 system routines

Project : ( County : H Subtitle: (	BROOME		State	: NY		er: KPI ed: #7	-	Date: 01-1 Date: <u>1/1-</u>	
Flow Type	2 year rain	Length (ft)	_	Surface code		Area sq/ft)		Velocity (ft/sec)	Time (hr)
Sheet Open Channe		300 200	.040	Е Е	Tir	me of (		3.0 tration = ( =	0.302 0.019 0.32*
A Smoot B Fallc C Culti D Culti	- Sheet Fl ch Surface ow (No Res vated < 2 vated > 2 s-Range, S	e 5.) 20 % Res. 20 % Res. Short	F Gra: G Gra: H Wood I Wood	ss, Dense ss, Burmu ds, Light ds, Dense	da		Surfac P Pa	oncentrated ce Codes avéd npaved	a 

.

.

\* - Generated for use by GRAPHIC method

Project : COLESVILLE LANDFILL County : BROOME State: NY Subtitle: CHANNEL DC-4-1	User: Checked:	крн <b>/////</b>	Date: 01-14-93 Date: <u>//22/93</u>	
COVER DESCRIPTION	Hy A	drologio B Acres	c Soil Group C D (CN)	-
FULLY DEVELOPED URBAN AREAS (Veg Estab.) Open space (Lawns,parks etc.) Good condition; grass cover > 75%	-	-	- 4.9(80)	
Total Area (by Hydrologic Soil Grour)			4.9	-
TOTAL DRAINAGE AREA: 4.9 Acres	s W	EIGHTED	CURVE NUMBER:80*	-
<ul> <li>* - Generated for use by GRAPHIC method</li> </ul>				_

By: **11** Date: **1/23**/**13** Chk: <u>KPN</u> Date: <u>1-25-1</u>3

GRASS LINED CHANNEL/DIVERSION DESIGN

Channel ID: PC-4-2Peak Flow, Q = 24 CFS Ave. Slope, s =  $O_15$ %

Select Basic Channel Geometry

Triangular, bottom width = 0 ft or Trapazoidal, bottom width = \_\_\_\_

Channel Side Slope (z:1), Z = 3

# **Determine Required Lining**

Max. Velocity for Grass Only = <u>3.0</u> Max. Velocity for Jute Lining = <u>...</u> Max. Velocity for Erosion Control Mat = <u>...</u>

From Table D at the given slope and flow, Velocity  $= \frac{2.5}{1000}$  Fres Therefore use: Grass Jute, or Erosion Control Mat (circle one)

### **Determine Channel Depth:**

- For Max. Velocity using Table D

$$Q = 33.3$$
 at  $V = 2.5$  and  $d = 2.1$ 

- For Max. Capacity using Table C

$$Q = 29.4$$
 at  $V = 2.0$  and  $d = 2.2$ 

Therefore set Total Depth = 25 inc. Freeboard and Settlement

GRASS LINED CHANNEL/DIVERSION WORKSHHET PREPARED IN ACCORDANCE WITH THE SCS ENGINEERING FIELD MANUAL FOR CONSERVATION PRACTICES AND THE STANDARDS FOR SOIL EROSION AND SEDIMENT CONTROL IN NEW JERSEY

Table C

RETARDANCE 'C' SIDE SLOPE (z:1) BOTTOM WIDTH (B) =

**с** о

VELOCITY		1.0			1.5			2.0			2.5			3.0			3.5			4.0		4.5	S		5.0	0		6.0	~	
SLOPE	æ	P	σ	æ	Ρ	σ	œ	σ	σ	œ	Ρ	σ	æ	Ρ	σ	œ	P	σ	œ	P		В	o I	æ	p	о _	æ	σ	a	
0.5% 0	0.85	1.8	9.6	0.95	2.0	18.0	1.05	2.2	29.4	1.18	2.5	46.4	1.35	2.8	72.9	1.50	3.2	-	.65	3.5 1	145 1.	.82 3.	3.8 19	199 2.05	5 4.3	3 280	0 2.50	0 5.3	20 20	0
1.0% 0	0.76	1.6	7.7	0.72	1.5	10.4	0.79	1.7	16.6	0.86	1.8	24.7 (	0.94	2.0	35.3	1.05	2.2	1.5 1	1.12	2.4 6	66.9 1.	1.25 2.6	6 93.8	8 1.35	5 2.8	8 122	2 1.62	3.4	1 21	0
1.5%	0.53	1.1	3.7	0.59	1.2	7.0	0.65	1.4	11.3	0.71	1.5	16.8 (	0.7	1.6	23.7 (	0.84	1.8 3	32.9 0	0.91	1.9 4	44.2 0.	0.98 2.1	1 57.6	6 1.05	5 2.2	2 73.5	5 1.22	2 2.6	:	
2.0%	0.50	1:		0.56	1.2	6.3	09.0	1.3	9.6	0.65		14.1	0.70	1.5	19.6 0	0.76	1.6 2	27.0 0	0.82	1.7 3	35.9 0.	0.88 1.	9 46.5	5 0,93		0 57.7	7   1,10	0 2.3	3 96.8	8
2.5%		3. j	40 47			5.0	5	:	8.7	0.58	1.2	11.2 0	0.62	1.3	15.4 (	0.67	1.4 2	20.9 0	0.72	1.5 2	27.6 0.	7 1.6	_		5 2.2	2 73.5	5 0.93	3 2.0	0 69.2	2
3.0%	0.44	0.9	2.6	0.48	1.0	4.6	0.52		7.2	0.56		10.5 (	0.59	1.2	13.9 (	0.64	1.3 1	19.1 0	0.67	1.4 2	23.9 0.	0.71 1.5	5 30.2	2 0.93	3 2.0	0 57.7	7 0.86	6 1.8	3 59.2	2
3.5%	0.40	0.8	2.1	0.44	0.9	_	0.47	1.0	5.9	0.50	:-	8.3	0.53	-	11.2 0	0.58	1.2 1	15.7 0	0.61	1.3 1	19.8 0.	0.65 1.4	4 25.3	3 1.05	5 2.2	2 73.5	5 0.77	7 1.6	5 47.4	4
4.0%	4.0% 0.38	0.8	1.9	0.42	0.9	3.5	0.45	0.9	-	0.48	1.0	_	0.51			0.55	1.2 1			1.2 1	17.9 0.	0.61 1.3	3 22.3		3 2.0	0 57.7	7 0 73	3 1 5	5 42 F	י צ
20.0	0.37	¢.0	0	0.39	с a	3:0		6.0	4.7	0.45	6.0	6.7 0	0.48	1.0	9.2	0.51	1.1	12.1 0	0.53	1.1				19.5 1.05	_	_	5 0.66	- -	4 34.8	8
2.0%	7.0% 0.32	0.7	1.4	0.35	0.7	2.4	0.37	0.8		0.39	0.8	5.1	0.41	0.9	6.7	0.43	0.9	8.6 0	0.46	1.0	11.3 0.	0.48 1.	1.0 13	13.8 0.93	3 2.0	0 57.7	7 0.56	6 1.2	52.2	-
10.0%	0.28	0.6	1.0	0.31	0.7	1.9 (	0.32	0.7	2.7	0.35	0.7	4.1	0.36	0.8	5.2 (	0.38	0.8	6.7 0	0.40	0.8	8.5 0.	0.42 0.	0.9 10	10.6 1.05	5 2.2	2 73.5	5 0.48	8 1.0	0 18.4	4

**VELOCITY IN FPS** 

R = HYDRAULIC RADIUS FROM FIGURE A6-2

d = DEPTH OF CHANNEL IN FEET (NOT INCLUDING ALLOWANCES FOR FREEBOARD, LINING INSTALLATION, OR SETTLEMENT) Q = FLOW IN CFS

RETARDANCE 'C; 01/22/93 (file: jhf disc: tools:retard'c.wk1)

GRASS LINED CHANNEL/DIVERSION WORKSHHET PREPARED IN ACCORDANCE WITH THE SCS ENGINEERING FIELD MANUAL FOR CONSERVATION PRACTICES AND THE STANDARDS FOR SOIL EROSION AND SEDIMENT CONTROL IN NEW JERSEY Table D

**т** 0 BOTTOM WIDTH (B) = RETARDANCE 'D' SIDE SLOPE (z:1)

	?			- 0			2.0			2.5			3.0	_		3.5			4.0		4	4.5		5.0	0		6.0	_
SLUFE H	p	σ	œ	Ð	σ	α	q	σ	α	σ	σ	œ	σ	σ	æ	P	σ	œ	p	σ	æ	P	σ	E E	Ø	E C		a
0.5% 0.6	1.3	4.8	0.73	1.5	10.7	0.86	1.8	19.7	1.00	2.1	33.3	1.15	2.4	52.9	1.33	2.8	82.5	1.51	3.2	122 1	.70	3.6	173 1.	1.95 4.	1 254	54 2.40	0 5.1	-
1.0% 0.44	6.0	2.6	0.53	:	5.6	0.62	1.3	10.3	0.70	1.5	_	0.79	1.7	25.0	0.90	1.9	37.8	1.00	2.1	53.3 1	_	2.3 7			2.6 10	100 1.50	0 3.2	
1.5% 0.36	0.8	1.8	0.43	0.9	3.7	0.50	1.1	6.7	0.56	1.2	10.5 (	0.64	1.3	16.4	0.70	1.5	_	0.79	1.7		0.86		44.4 0.		2.0 60.2	.2 1.10		0,
2.0% 0.33	0.7	1.5	0.39	0.8		0.45	0.9	5.4 0	0.51	1:1	_	0.57	2	13.0	0.62	1.3		0.69	1.5	5.4 0	1.76			0.84 1.			0 2.1	
2.5% 0.29	0.6		0.34	0.7		0.39	0.8	4.1	0.44	<b>6</b> .0		0.58	1.2	13.5	0.54			0.60		9.2	1.65 1							
3.0% 0.28	0.6	1.0	0.33	0.7	2.1	0.37	0.8	3.7	0.42	0.9	5.9	0.46	1.0 8.5	8.5	0.51	:	12.1	0.56	1.2	16.7 0	0.60 1.3			0.67 1.	1.4 29.9			3 48.7
3.5% 0.25	0.5	0.8	0.29	0.6		0.33	0.7	2.9	0.38	0.8		0.41	0.9	6.7	0.45	0.9	9.5	0.50	1.1	13.3 0	0.54					.4 0.67		
4.0% 0.24	0.5	0.8	0.28	0.6	1.6	0.32	0.7	2.6	0.35	0.7		0.39	0.8	6.1	0.43	0.9	_	0.47	1.0		0.51 1			_	1.2 20.2	_	3 1.3	_
5.0% 0.22	0.5	0.7	0.26	0.5	1.4	0.30	0.6	2.4	0.33	0.7	3.6	0.36	0.8	5.2	0.40	0.8	7.3 (	_		6.6		_		_				
7.0%	_		0.23	0.5		0.26	0.5	<del>1</del> .8	0.28	0.6	_	0.31	0.7	3.8	0.34	0.7	5.4	0.37	0.8			0.8		_				
10.0%						0.24	0.5	1.5 0.24	0.24	0.5	1.9	0.26	0.5	2.7	0.28	0.6	3.7	0.31	0.7	5.1 0		0.7	6.3 0.	0.35 0.	0.7 8.	8.2 0.40		

**VELOCITY IN FPS** 

R = HYDRAULIC RADIUS FROM FIGURE A6-3 d = DEPTH OF CHANNEL IN FEET (NOT INCLUDING ALLOWANCES FOR FREEBOARD, LINING INSTALLATION, OR SETTLEMENT)

Q = FLOW IN CFS

RETARDANCE 'D; 01/22/93 (file: jhf disc: tools:retard'd.wk1)

Project : COLESVILLE LANDFILL County : BROOME State: NY Subtitle: CHANNEL DC-4-2 User: KPH Checked:

Date: 01-14-93 Date: 1/2/97

Data:	Drainage Area	:	10.9	*	Acres
	Runoff Curve Number	:	80 *		
	Time of Concentratio	n:	0.56	*	Hours
	Rainfall Type	:	II		
	Pond and Swamp Area	:	NONE		

======================================	1	2	3	<b>4</b>	<b>5</b>	6
Frequency (yrs)	2	5	10	25	50	100
24-Hr Rainfall (in)	2.8	3.5	4.3	4.9	5.3	5.9
Ia/P Ratio	0.18	0.14	0.12	0.10	0.09	0.08
Used	0.18	0.14	0.12	0.10	0.10	0.10
Runoff (in)	1.10	1.64	2.29	2.81	3.16	3.69
Unit Peak Discharge (cfs/acre/in)	0.726	0.750	0.768	0.778	0.779	0.779
Pond and Swamp Factor 0.0% Ponds Used	1.00	1.00	1.00	1.00	1.00	1.00
Peak Discharge (cfs)	9	13	19	24	27	31

\* - Value(s) provided from TR-55 system routines

Project : COLH County : BROC Subtitle: CHAN		State:	NY	User: Checked:		Date: 01-: Date://	
	year Length cain (ft)	Slope (ft/ft)		n Area (sq/f	Wp t) (ft)	Velocity (ft/sec)	Time (hr)
Sheet 2 Open Channel Open Channel	2.8 300 200 1050	.04	E	Time o	f Concent	3.0 1.2 tration = (	
<ul> <li>A Smooth S</li> <li>B Fallow (</li> <li>C Cultivat</li> <li>D Cultivat</li> </ul>	neet Flow Surfac Surface (No Res.) ced < 20 % Res. ced > 20 % Res. ange, Short	F Grass G Grass H Woods	s, Dense s, Burmud		Surfac P Pa	oncentrated ce Codes aved npaved	1 

\* - Generated for use by GRAPHIC method

Project : COLESVILLE LANDFILL County : BROOME State: NY Subtitle: CHANNEL DC-4-2	User: KPH Date: 01-14-93 Checked: 71 Date: 1/22/93
COVER DESCRIPTION	Hydrologic Soil Group A B C D Acres (CN)
FULLY DEVELOPED URBAN AREAS (Veg Estab.) Open space (Lawns,parks etc.) Good condition; grass cover > 75%	10.9(80)
Total Area (by Hydrologic Soil Group)	10.9
TOTAL DRAINAGE AREA: 10.9	Acres WEIGHTED CURVE NUMBER:80*
<ul> <li>* - Generated for use by GRAPHIC method</li> </ul>	

.

By: 122/13 Chk: KPN Date: 1-25-93

GRASS LINED CHANNEL/DIVERSION DESIGN

Channel ID:  $\mathcal{P}C - 6$ Peak Flow, Q = 32 CP5 Ave. Slope, s = 0.5%

Select Basic Channel Geometry

Griangular, bottom width = 0 ft or Trapazoidal, bottom width = \_\_\_\_\_ Channel Side Slope (z:1), Z = 3

**Determine Required Lining** 

Max. Velocity for Grass Only = \_\_\_\_\_ Max. Velocity for Jute Lining = \_\_\_\_A Max. Velocity for Erosion Control Mat = \_\_\_\_\_

From Table D at the given slope and flow, Velocity  $\leq 2.5$  from Table D at the given slope and flow, Velocity Therefore use: Grass, Jute, or Erosion Control Mat (circle one)

**Determine Channel Depth:** 

- For Max. Velocity using Table D

$$Q = 33.3$$
 at  $V = 2.5$  and  $d = 2.7$ 

- For Max. Capacity using Table C

$$Q = \frac{46.4}{1}$$
 at  $V = \frac{2.5}{1}$  and  $d = \frac{2.5}{1}$ 

Therefore set Total Depth = 3.0 inc. Freeboard and Settlement

GRASS LINED CHANNEL/DIVERSION WORKSHHET PREPARED IN ACCORDANCE WITH THE SCS ENGINEERING FIELD MANUAL FOR CONSERVATION PRACTICES AND THE STANDARDS FOR SOIL EROSION AND SEDIMENT CONTROL IN NEW JERSEY Table D

RETARDANCE 'D' SIDE SLOPE (z:1) BOTTOM WIDTH (B) =

ς δ

VELOCITY		1.0			1.5			2.0			2.5			3.0			3.5			4.0		4	4.5		ŝ	5.0	-	Ö	0
SLOPE	æ	Ð	σ	н	Ρ	σ	œ	p	σ	œ	σ	σ	œ	σ	σ	æ	σ	σ	æ	τ	σ	æ	Ð	- 0	Ē	o D	а а	р ~	σ
0.5%	0.6	1.3	4.8 (	0.73	1.5		0.86	1.8	19.7	1.00	2.1	33.3	1.15	2.4	52.9	1.33	2.8	82.5	1.51	3.2	-	.70	3.6 1	173 1.	.95 4.	1 254	54 2.40	0 5.1	1 461
1.0% (	0.44	0.9	5.6	0.53	Ξ	5.6	0.62	1.3	10.3	0.70	1. 15	16.3	0.79	1.7	25.0	06.0	6.1	37.8	00.1	2.1	53.3 1	1.10 2	2.3 7:	_	1.23 2.	2.6 10	100 1.50	0 3.2	2 180
1.5% (	0.36	0.8	1.8	0.43	0.9	3.7	0.50	:-	6.7	0.56	1.2	10.5	0.64	1.3	16.4	0.70	1.5	22.9 (	0.79	1.7 3	33.3 0	0.86	1.8 4		0.95 2.	2.0 60.2	.2 1.10	0 2.3	3 96.8
2.0% 0.33		0.7	1.5		0.8	3.0	0.45	0.9	5.4	0.51		8.7	0.57	1.2	13.0	0.62	1.3	<u> </u>	0.69	1.5 2	25.4 0	0.76 1	1.6 3.		0.844 1	18 47.0	0017	0 2.1	,
2.5%							0.39	0.8	4.1		0.9		0.58	1.2	_	0.54		13.6 (	0.60		_	0.65 1		25.3 0.		1.5 33.6	.6 0.85	1.8	8 57.8
3.0% (		0.6	0.1	_	0.7		0.37	0.8		0.42	0.9	5.9	0.46	1.0	8.5	0.51	-		0.56	1.2	16.7 0	0.60 1	1.3 2	_	0.67 1.	1.4 29.9	.9 0.78	8 1.6	8 48.7
3.5% (		0.5	0.8	0.29	0.6	1.7	0.33	0.7	2.9	0.38	0.8	4.7	0.41	0.9	6.7	0.45	0.9	9.5 (	0.50		13.3 0	0.54 1	11	17.5 0.	0.58 1	1.2 22.4	.4 0.67	1.4	4 35.9
4.0%		0.5	0.8	0.28	0.6	1.6	0.32	0.7		0.35	0.7		0.39	0.8		0.43	0.9		7.47		11.8 0	0.51 1	<del>;</del> ;	15.6 n	0 55 1	1 0 0	20.2 D.63	6 7	2 2
5.0%		0.5	·	0.26	0.5		0.30	0.6		0.33	0.7	3.6	0.36	0.8	5.2	0.40	0.8		0.43	0.9		0.47 1	1.0	13.3 0.	0.51 1	1.1 17	17.3 0.59	9 1.2	2 27.8
7.0%		_	-	0.23	0.5	1.1	0.26	0.5	1.8	0.28	0.6	2.6 2.6	0.31	0.7	3.8	0.34	0.7	5.4 (	0.37	0.8	7.3 0	0.39 0	0.8	9.1 0.	0.42 0	0.9 11	11.8 0.48	1.0	0 18.4
10.0%	_			_			0.24	0.5	1.5 0.24	0.24	0.5	1.9	0.26	0.5	2.7	0.28	0.6	3.7 (	0.31	0.7	5.1 6	0.33 0	0.7	6.3 0.	0.35 0	0.7 8	8.2 0.40	0.8	8 12.8

**VELOCITY IN FPS** 

R = HYDRAULIC RADIUS FROM FIGURE A6-3

d = DEPTH OF CHANNEL IN FEET (NOT INCLUDING ALLOWANCES FOR FREEBOARD, LINING INSTALLATION, OR SETTLEMENT) Q = FLOW IN CFS

RETARDANCE 'D; 01/22/93 (file: jhf disc: tools:retard'd.wk1)

Table C

GRASS LINED CHANNEL/DIVERSION WORKSHHET PREPARED IN ACCORDANCE WITH THE SCS ENGINEERING FIELD MANUAL FOR CONSERVATION PRACTICES AND THE STANDARDS FOR SOIL EROSION AND SEDIMENT CONTROL IN NEW JERSEY

22 - 24.4 4C.4 - 33		x - + +	
	с	0	
RETARDANCE 'C'	SIDE SLOPE (z:1)	BOTTOM WIDTH (B) =	

VELOCITY		1.0			1.5			2.0			2.5			3.0			3.5			4.0			4.5		-	5.0		G	6.0
SLOPE	н	P	σ	æ	P	σ	α	p	σ	æ	P	σ	æ	Ρ	σ	œ	σ	σ	œ	σ	σ	œ	τ	a	æ	P	σ	Е	0
0.5%	0.85	1.8	9.6	0.95	2.0	18.0	1.05	2.2	29.4	1.18	2.5	46.4	1.35	2.8	72.9	1.50	3.2	* * * *	1.65	3.5	145	1.82	3.8	199 2	2.05 4	4.3 2	280 2.	2.50 5	5.3 500
1.0%	0.76	1.6	7.7	0.72	1.5	10.4	0.79	1.7	16.6	0.86	8.		0.94	2.0	35.3	1.05	2.2	51.5	1.12	2.4	6.99	1.25	2.6 9	93.8 1	1.35	2.8 1	122 1.	1.62 3.	3.4 210
1.5%	0.53	1.1	3.7	0.59	1.2	7.0	0.65	4.1	11.3	0.71	1.5	16.8	0.77	1.6	23.7	0.84	1.8	32.9	0.91	1.9	44.2	0.98	2.1 5	57.6 1	1.05	2.2	73.5 1.	1.22 2	2.6 ****
2.0%	0.50		3.3	0.56	1.2	6.3	0.60	1.3	9.6	0.65	4.1	14.1 0.70	0.70	1.5	19.6	0.76	_	_	0.82	1.7	35.9 (	0.88	1.9 4	46.5 0	0.93	2.0 57	57.7 1.	1.10 2	2.3 96.
2.5%	0.46	1.0	2.8	0.50		5.0	0.54	1.1	7.8	0.58	1.	11.2 0	0.62	1.3	15.4	0.67	1.4	20.9	0.72	1.5	27.6	0.71	1.6 35.6	35.6 1	1.05	2.2 73.5	3.5 0.	0.93 2	0 69.2
3.0%	0.44	0.9	2.6	0.48	1.0	4.6	0.52	7	7.2	0.56	1.2	10.5	0.59	1.2	13.9	0.64	1.3	19.1	0.67	4.1		0.71 1.5 30.2	1.5	30.2 0	0.93	0 5	7.7 0.	0.86 1	1.8 59.2
3.5%	0.40	0.8	2.1	0.44	0.9	3.9	0.47	1.0	5.9	0.50	÷	8.3 0.53	0.53	÷	11.2	0.58	1.2	15.7	0.61	1.3		0.65	1.4	25.3 1	1.05	2.2 73	73.5 0.	0.77 1.6	
4.0%	0.38	0.8	1.9	0.42	0.9	3.5	0.45	0.9	5.4	0.48	1.0	7.7 0.51	0.51	÷	10.4	0.55	1.2		0.58	1.2	17.9 (	0.61	1.3	22.3	0.93	2.0 57	57.7 0.	0.73 1.	1.5 42.6
5.0%	0.37	0.8	1.8	0.39	0.8	3.0	0.42	0.9	4.7	0.45	0.9	6.7	0.48	1.0	9.2	0.51		12.1	0.53		15.0	0.57	1.2 19.5		1.05	2.2	73.5 0.	0.66 1.	1.4 34.8
7.0% 0.32	0.32	0.7	1.4	0.35	0.7	2.4	0.37	0.8	3.7	0.39	0.8	5.1 0.41	0.41	6.0	6.7	0.43	6.0	8.6	0.46	1.0	11.3	0.48	1.0	0.48 1.0 13.8 0.93		2.0 57	57.7 0.	0.56 1.	1.2 25.1
10.0% 0.28	0.28	0.6	1.0	0.31	0.7	1.9 0.32	0.32	0.7	2.7	0.35	0.7	4.1	4.1 0.36	0.8	0.8 5.2	0.38	0.8	6.7 0.40	0.40	<b>8</b> .0	8.5	0.42	0.9	0.8 8.5 0.42 0.9 10.6 1.05 2.2	.02 .02		73.5 0.	0.48 1.0	0 18.4

VELOCITY IN FPS

R = HYDRAULIC RADIUS FROM FIGURE A6-2

d = DEPTH OF CHANNEL IN FEET (NOT INCLUDING ALLOWANCES FOR FREEBOARD, LINING INSTALLATION, OR SETTLEMENT) Q = FLOW IN CFS

RETARDANCE 'C; 01/22/93 (file: jhf disc: tools:retard'c.wk1)

By KPH Date 1-21-93 Chkd. 11 Date 1/22/9;

DIVERSION CHANNEL DESIGN - GABION LINING JOB NO. 00000 XX COLESVILLE LANDFILL CHANNEL DC-6 INLET CHANNEL ----- INPUT -----32.0 0.033 CHANNEL SIDESLOPE - LEFT SIDE (HORIZ/VERT) . . . . . . 3.0 CHANNEL SIDESLOPE - RIGH? SIDE (HORIZ/VERT) . . . . . . 3.0 CHANNEL BOTTOM WIDTH, B (FT)........ 3.0 MANNING'S ROUGHNESS COEFFICIENT, n GABION MATTRESS THICKNESS, t (IN) (USE 6, 9, 12 OR 18) FREEBOARD (FT) 0.025 6.0 0.5 BEGIN CALCULATIONS AT CHANNEL DEPTH (FT) . . . . . . . 0.5 \_\_\_\_\_\_

-	HANNEL DEPTH (FT)	X-SECT AREA (SQ FT)	ТФР WIDTH (FT)	HYDRAULIC RADIUS (FT)	DISCHARGE (CFS)	VELOCITY (FPS)	FROUDE NUMBER- Nf
	0.5	2.3	5.0	0.37	12.4	5.5	1.59
	0.6	2.9	5.6	0.42	17.6	6.1	1.63
	0.7	3.6	7.2	0.48	23.7	6.6	1.66
	0.8	4.3	7.8	0.54	30.9	7.1	1.69
	0.9	5.1	3.4	0.59	39.1	7.6	1.72
	1.0	6.0	9.0	0.64	48.4	8.1	1.74
	1.1	6.9	9.6	0.70	58.9	8.5	1.76
	1.2	7.9	10.2	0.75	70.6	8.9	1.78
	1.3	9.0	10.8	0.80	83.6	9.3	1.80
	1.4	10.1	11.4	0.85	97.9	9.7	1.82
	1.5	11.3	12.0	0.90	113.6	10.1	1.84

DESIGN DEPTH OF FLOW, D (FT)	0.9
VELOCITY, V (FPS) $\ldots$	7.6
TOTAL DEPTH INCLUDING FREEBOARD (FT)	1.4
GABION THICKNESS, t (IN)	6.0
FILLING STONE SIZE, d50 (IN)	3.0

TR-55 GRAPHICAL DISCHARGE METHOD Project : COLESVILLE LANDFILL County : BROOME State: NY Checked: Subtitle: CHANNEL DC-6

VERSION 1.11 Date: 01-14-93 Date: 1/21/43

User: KPH

11

Data:	Drainage Area	:	17.7 * Acres
	Runoff Curve Number		
	Time of Concentration	n:	0.73 * Hours
	Rainfall Type	:	II
	Pond and Swamp Area	:	NONE

Storm Number	1	2	3	4	5	6
Frequency (yrs)	2	5	10	25	50	100
24-Hr Rainfall (in)	2.8	3.5	4.3	4.9	5.3	5.9
Ia/P Ratio	0.19	0.15	0.12	0.11	0.10	0.09
Used	0.19	0.15	0.12	0.11	0.10	0.10
Runoff (in)	1.04	1.57	2.21	2.72	3.06	3.59
Unit Peak Discharge (cfs/acre/in)	0.619	0.642	0.659	0.668	0.673	0.673
Pond and Swamp Factor 0.0% Ponds Used	1.00	1.00	1.00	1.00	1.00	1.00
Peak Discharge (cfs)	11	18	26	32	36	43

\* - Value(s) provided from TR-55 system routines

TR-55 Tc and Ft THRU SUBAREA COMPUTATIONVERSION 1.11Project : COLESVILLE LANDFILLUser: KPHDate: 01-14-93County : BROOMEState: NYChecked: 1/2+/93Subtitle: CHANNEL DC-6Date: 1/2+/93

Flow Type	2 year rain	Length (ft)	Slope (ft/ft)	Surface code	n	Area (sq/ft)	Wp (ft)	Velocity (ft/sec)	Time (hr) 🕳
Sheet Shallow Con Open Channe		300 1210 430	.25 .25	I U	r I	lime of C	oncent	1.2 ration = (	0.584 0.042 0.100 0.73*
A Smoot B Fallc C Culti D Culti	Sheet Fl h Surface w (No Res vated < 2 vated > 2 -Range, S	2 5.) 20 % Res. 20 % Res. Short	F Gra G Gra H Wood I Wood	ss, Dense ss, Burmuda ds, Light ds, Dense		Shal 	Surfac P Pa	oncentrated ce Codes ved paved	1 <b></b>

Project : COLI County : BROG Subtitle: CHAN	TR-55 C ESVILLE LANDFILI OME NNEL DC-6	URVE NUMBER ' State: NY	lice	Y KDH	VERSION 1. Date: 01-14- Date: <u> /22/¶</u>
COVE	R DESCRIPTION		A	Hydrologio B Acres	C Soil Group C D (CN)
OTHER AGRICULT Woods	TURAL LANDS	fair	-	· _	- 17.7(79
Total Area (by	y Hydrologic Soi	l Group)			17.7
	TOTAL DRAINAG	E AREA: 17.7	Acres	WEIGHTED	CURVE NUMBER:7

	Bv	Date			Job No	
	Chkd. by	Date	_ <b>@</b> "	ehran EnviroTech	Sheet No	of
	Subject					
-						
-						
			•			
			TUMBLING	FLOW DOWNCHLTTE DE	SIGN	
<b>49</b>						
			Nor	TH CRERK DOWNCHUTE		
				-		
						-
-						
-						
_						

			5							
Notest		DRAINBOR CHANNAL INLET OUTLET. AREA (AL) SLOPE (%) RUEV. ELEV.	THERT OUTIFT	סטרוגד. ערגע	LEWGTH (FT)	(5=3) (5=3)	LERNGTH FLOW ELEMENT CHANNEL (ET) (CES) MENHT(FT) LINGIS OFFIT	TH FLOW ELEMENT CHANNEL (CES) ARIGHT (CES) ARIGHT (CES)	LRNETIS BRINGRN RLRMRNTS	ουτυε τ ναιοιάγ (FPS)
D6-5-2	40.0	233	7511	451	120	67.0	٥Ľ٩	£.C	6.0	6.3 NoT in Cuntract
<u> Ттречно 58.1</u> Stize <b>m</b> m	28.1	0.6	9 <b>1</b> []]	the second	908	95.0	0 L 0	30	•ری	e.5 Not in Cantrater
NRTH (REEL DWWWHNT	13.9	25.0	٥.٢٤٩١	066	180	27.0	01.0	2.5	0	5.9

TUMBLING FLOW DOWNCHUTE DRSIGN SUMMARY

MEPLENALLOLEGY 100 NO. 02260- CS



Subject \_ Date +25-53 Сика. by by Ком

	Date			Sheet No	of
Subject		CORSVILLE	LANDE.11		
	NORTH	CRICEK SITEP C	NONNENUTE_		
	THE DESI	EN OF THIS CHA	NNIEL IS BASI	to on the	
7	UMDING (-LOW /	METNOD ALS PRE	SENTED IN	NT NOVATIONS IN	V
	-				
	FORMWATTER MA	WAGEMENT FOR	- LAND FILL CL	osu <u>re</u> by	
·		A = 1 + 1/1 / 1/1 - 38 =	100	FALLANT TO S.	
	TILVEN GAN	NELSKY, VIGE PRE	3101207, 200		
	THE ABOUND	CONSISTS OF A	TRACT TO AL	ALASE LAST	•
	Ditsie	CONSISTS OF A	TRAPE ZOIDAC CI	and with	
C	CRETTE BLOCKS	NSTALLED WITHIN	THR CHANNEL	BOTTOM TO ACT	•
Con	CRRTTL BLOCKS I	NSTALLED WITHIN	THR CHANNEL	Воттом то Аст	-
					_
		NSTALLED WITHIN			_
<b>f</b> ts	INDIVIOUSL ENER	264 DISSIPATOR FLR	EMENTS, SPACED	EVENLY THROU	6 NOUT
<b>f</b> ts	INDIVIOUSL ENER		EMENTS, SPACED	EVENLY THROU	6 NOUT
THE	INDIVIOUGL ENER ENANNEL THE	264 DISSIPATOR FLR	EMÆNTS, SPACEO IS A LOW VRO	EVENLY THROU	6 NOUT
THE	INDIVIOUGL ENER ENANNEL THE	264 DISSIPATOR FLE L DESIGN PROVIDE	EMÆNTS, SPACEO IS A LOW VRO	EVENLY THROU	6 NOUT
THE Dide	INDIVIOUAL ENER ENANNEL THE HARGE INTO TH	264 DISSIPATOR FLE L DESIGN PROVIDE	EMÆNTS, SPACEG IS A LOW VRG ANN/RL	EVENLY THROU	6 NOUT
TNIE Disc	INDIVIDUAL ENER CHANNEL. THE HARGE INTO THE EQUATIONS TH	REY DISSIPATOR FLE L DESIGN PROVIDE NE RELISTING CHA NET GAVERN THE	EMÆNTS, SPACES ES A LOW VRG ANN/RL. D <b>E</b> SIG <b>N</b> /	EVENLY THROU	6 NOUT
TNIE Disc	INDIVIDUAL ENER CHANNEL. THE HARGE INTO THE EQUATIONS TH	REY DISSIPATOR FLE L DESIGN PROVIDE NE RELISTING CHA NET GAVERN THE	EMÆNTS, SPACES ES A LOW VRG ANN/RL. D <b>E</b> SIG <b>N</b> /	EVENLY THROU	6 NOUT
TNIE Disc	INDIVIDUAL ENER CHANNEL THE HARGE INTO THE EQUATIONS THE G = (16	REY DISSIPATER FLE L DESIGN PROVIDE NR RELISTING CHA NAT GAUERN THR 5.5 - 0.206 5) K	EMÆNTS, SPACES ES A LOW VRG ANN/RL. D <b>E</b> SIG <b>N</b> /	EVENLY THROU	6 NOUT
TNIE Disc	INDIVIDUAL ENER CHANNEL THE HARGE INTO THE EQUATIONS THE G = (16	REY DISSIPATER FLE L DESIGN PROVIDE NR RELISTING CHA NAT COVERN THR 5.5 - 0.206 5) K	EMÆNTS, SPACES ES A LOW VRG ANN/RL. D <b>E</b> SIG <b>N</b> /	EVENLY THROU	6 NOUT
TNIE Disc	INDIVIOUGL ENFER CHANNEL THE HARGE INTO THE EQUATIONS THE G = (16 Y1 = 0.	264 DISSIPATOR FLE L DIESIGN PROVIDE NR. REXISTING CHA NAT. COVERN THR 5.5 - 0.206.5)K 35. 2/3	EMÆNTS, SPACES ES A LOW VRG ANN/RL. D <b>E</b> SIG <b>N</b> /	EVENLY THROU	6 NOUT
TNIE Disc	INDIVIOUGL ENFER CHANNEL THE HARGE INTO THE EQUATIONS THE G = (16 Y1 = 0.	264 DISSIPATOR FLE L DIESIGN PROVIDE NR. REXISTING CHA NAT. COVERN THR 5.5 - 0.206.5)K 35. 2/3	EMÆNTS, SPACES ES A LOW VRG ANN/RL. D <b>E</b> SIG <b>N</b> /	EVENLY THROU	6 NOUT
TNIE Disc	INDIVIDUAL ENFER CHANNEL. THE HARGE INTO THE FEQUATIONS THE G = (16 Y1 = 0. V2 = (9)	L DESIGN PROVIDE L DESIGN PROVIDE NR RELISTING CHA NAT COVERN THR 35 243 4) 1/3	EMÆNTS, SPACES ES A LOW VRG ANN/RL. D <b>E</b> SIG <b>N</b> /	EVENLY THROU	6 NOUT
TNIE Disc	INDIVIDUAL ENFER CHANNEL. THE HARGE INTO THE FEQUATIONS THE G = (16 Y1 = 0. V2 = (9)	264 DISSIPATOR FLE L DIESIGN PROVIDE NR. REXISTING CHA NAT. COVERN THR 5.5 - 0.206.5)K 35. 2/3	EMÆNTS, SPACES ES A LOW VRG ANN/RL. D <b>E</b> SIG <b>N</b> /	EVENLY THROU	6 NOUT
TNIE Disc	INDIVIDUAL ENFER CHANNEL. THE HARGE INTO THE FEQUATIONS THE G = (16 Y1 = 0. V2 = (9)	L DESIGN PROVIDE L DESIGN PROVIDE NR RELISTING CHA NAT COVERN THR 35 243 4) 1/3	EMÆNTS, SPACES IS A LOW VRG ANN/RL. D <b>E</b> SIG <b>N</b> /	EVENLY THROU	6 NOUT

GE UNIT DISCHARGE ( CES/FT OF BASE WIDTH(b)) S = CHANNEL SLOPFE (0/0) K = HEIGHT OF ELEMENT (ET) G = 32.2 = T/SEC Y/1 = CONTROL DEPTH ON MAXIMUM RISE OF WATER OVER REFINITINT (FT) VC = CRITICAL VELOCITY - (ALSO OUTLET VELOCITY (FPS)) L = LENGTH BETHERN FREEMENTS Chkd. by 12th Date 1/2010 Subject 1/2010

ColESVILLE LANDFILL

Ву <u>КРН</u> Date <u>1-20-93</u> Chkd. by <u>1211</u>, Date <u>1/2011</u>? **Wehran** EnviroTech Job No. <u>02260.CS</u> Sheet No. \_\_\_\_\_ of \_\_\_\_

Desion;

$$g = \frac{q_{25}}{b} = \frac{29.0}{4.5} = \frac{6.44}{5}$$

$$g = (16.5 - .2065) (K^{3/2}) \quad \text{Solve For K}$$

$$K = \left[\frac{q}{(16.5 - .2065)}\right]^{\frac{2}{3}} = \left(\frac{6.44}{16.5 - .206(25)}\right)^{\frac{2}{3}}$$

$$K = .69$$

DETERMINE DEPTH OF WATTER ABOVE BLOCK

$$Y_1 = .35 e^{2/3} = .35 (6.44)^{2/3}$$
  
 $Y_1 = 1.21 =$ 


DETERMINE SPACING BETWEEN FLEMENTS

$$4K = 8.5 \pm 0.10$$
 L=8.5(K) = 5.5(69) + 5.87  
L=10.0(K) 10(69) = 6.9

DETERMINE CRITICAL VELOCITY (VC) - ALSO OUTLET VELOCITY

$$V_{c} = (q q)^{V_{3}}$$
  
- (32.2 644)  $V_{3}$   
 $V_{c} = 5.92 = PS$ 

By <u>KPH</u> Date <u>1-20-93</u> Chkd. by <u>Lip</u> Date <u>1/12-18</u> <b>Wehran</b> EnviroTech Sheet No of Subject
NORTH CREEK STEP DOWNCHUTE
Y, WRATH OF WATER WRAELEMENT 122
ELEMENT NEGENT 169
CHANNEL DEPTH 2.41. $\Rightarrow 2.5'$ CHANNEL LINING! EITHER - 6" GABION MATTERSS $4/D_{50}=3''$ F.Hing $-D_{50}=5''$ Rip Rap



rowsment. The values in table 2 are derived from model tests conducted in 1982-83 (Hydrautics Laboratory Engineering Research Center, Colorado State University - Fort Collins - U.S.A.) which are described later. This research has also quantified the advantages that derive from containment of the fill material by mesh when compared with loose rip rap protection.

It has been snown that Reno mattress linings have double the stability of rip rap of the same stone grading against bed tractions. Furthermore, it was verified that, for a given velocity of flow, the Reno mattress needs only be 1 3 to 1:4 as thick as a rip rap lining. ment, du revetement des berges.

La vitesse critique, element de cette table, est egale à la vitesse que le revelement peut supporter en toute securité sans mouvement de la pierre à l'intérieur du mateias Reno: la vitesse limite correspond à la vitesse acceptable mais entraînant de légères déformations du mateias Reno dues au tassement de la pierre.

Les donnees de la table 2 découlent des essais sur maquette datant de 1982-1983 et exécutés par Hydraulics Laboratory Engineering Research Center Colorado State University - Fort Collins - U.S.A.

Ces essais seront decrits par la suite. L'étude que nous venons de citer a entre autre permis de quantifier les avantages de l'action de rétention du matériau de remplissage exercée par le grillage, par rapport aux revétements en enrochements. Il a été démontré que le revétement en matérias Reno est stable en présence de charriage de fond dont les tensions sont

de tondo pero con buena aproxima también para aquellos de las ortilas. En esta tabla por-velocidad criticaentiende la que puede soportar revestimiento con seguridad sin movim tos de pindras en el interior del colo Reno: por «velocidad limite» se entienc que puede ser aceptada admitie modestas deformaciones del colchón Fi causadas por el movimiento de la pie Los valores de la tabla 2 derivan de prue efectuadas sobre modelo en 1982/1 (Hydraulics Laboratory Engineering search Center Colorado State Universi Fort Collins - USA) que serán descri: más adeiante.

Esta búsqueda ha cuantificado además. ventajas que derivar: de la acción contención ejercitada:por la red-metá sobre el material de retieno con respeclos revestimientos:admaterial suelto ( rap). Se ha demostradarque el revestimir en colchones Reno-er-estable para fuer

Tab. 2 - Indicative Reno Mattress and gabion thicknesses in relation to water velocities

New Ca


Tab. 2 - Epaisseurs approximatives des revêtements en mateias Reno et en gabions en fonction de la vitesse du courant Tab. 2 - Espesores indicativos de los revestimientos en colchones Reno y e gaviones en función de la velocidad d la corriente

Туре	Thickness Epsisseur	Filling st Pierraille de re Pedrisco de	emplissage	-	Critical velo Vitesse criti	tique -	Limit velocity Vitesse limite	
Type Tipo	Espesor	Stone size Granulometrie Dimensiones	d <sub>30</sub>		Velocidad ci	ntica -	Velocidad I	imite
	m - in		11	<u>~  </u>	m/s	FPS	m/s	EP.
	0.15 0.17	70 - 100	0.085	3	3.5	11	4.2	12
Reno mattress	0.15 - 0.17	70 - 150	0.110	4	4.2	14	4.5	1:
	0.02, 0.05	70 - 100	0.085 -	31	3.6	12	5.5	١٩
Matelas Reno Colchones Reno	0.23 - 0.25 A	70 - 150	0.120	5	4.5	15	6.1	ac
	2.00	70 - 120	0.100	41	4.2	14	5.5	16
	0.30	100 - 150	0.1 <b>25</b>	51	5.0	ile	6.4	a
Gabions	2	100 - 200		ا هـ	5.8	19	7.6	25
Gabions Gaviones	0.50	120 - 250	0.190 7	.5	6.4	21	8.0	a



Fig. 15-U.S.A. - New York - Bank prosection near Bulle Fig. 15 - U.S.A. - New York - Revisionment de bang realise en proximité de la ville de Bullaio.

Fig. 15 - U.S.A. - New York - Delense de un dique en



Source: Hydraulic Design of Stilling Basins and Energy Dissipators

.....

Project : COLESVILLE LAN County : BROOME Subtitle: NORTH CREEK DO		State: E	NY		er: KPH ed: <b>}7</b> 4		ate: ate:
Data: Drainage Area Runoff Curve Nur Time of Concent Rainfall Type Pond and Swamp A	mber : ration: ;	80 * 0.59 : II					
Storm Number	1	2	3	4		<b>6</b>	=
Frequency (yrs)	2	5	10	25	50	100	
24-Hr Rainfall (in)	2.8	3.5	4.3	4.9	5.3	5.9	
Ia/P Ratio	0.18	0.14	0.12	0.10	0.09	0.08	
Used	0.18	0.14	0.12	0.10	0.10	0.10	
Runoff (in)	1.10	1.64	2.29	2.81	3.16	3.69	
Unit Peak Discharge (cfs/acre/in)	0.705	0.729	0.747	0.756	0.758	0.758	
<ul> <li>Pond and Swamp Factor</li> <li>0.0% Ponds Used</li> </ul>	1.00	1.00	1.00	1.00	1.00	1.00	
Peak Discharge (cfs)	11	17	24	29	33	39	· 

\* - Value(s) provided from TR-55 system routines

Date: 01-14-93 Date: <u>|(121(1)</u>

Project : COLESVILLE LANDFILL County : BROOME State: NY Subtitle: NORTH CREEK DOWNCHUTE		: крн <sup>1:</sup> 19:57	Date: 01-14-93 Date: <u>//22/13</u>	•••
COVER DESCRIPTION	H A	Hydrologic B Acres	Soil Group C D (CN)	-
FULLY DEVELOPED URBAN AREAS (Veg Estab.) Open space (Lawns,parks etc.) Good condition; grass cover > 75%	-	-	- 13.9(80)	
Total Area (by Hydrologic Soil Group)			13.9 	-
TOTAL DRAINAGE AREA: 13.9 Acre				
<ul> <li>* - Generated for use by GRAPHIC method</li> </ul>				

Project : County : : Subtitle:	BROOME		State	: NY	Use: Checke	с: крн d: <del>17</del>	-	Date: 01-: Date: <u>  </u> 2	
Flow Type	2 year rain	Length (ft)		Surface code		rea g/ft)		Velocity (ft/sec)	Time (hr)
Sheet Open Chann Open Chann		300 180 1470	.04	E	Time	e of C	Concent	8.0 1.47 tration = (	
A Smoo B Fall C Cult D Cult	- Sheet Fl th Surface ow (No Res ivated < 2 ivated > 2 s-Range, S	e 5.) 20 % Res. 20 % Res.	F Gras G Gras H Wood	ss, Dense ss, Burmu ds, Light ds, Dense	da		Surfac P Pa	oncentrated ce Codes aved npaved	1 

\* - Generated for use by GRAPHIC method

.

. .

Wehran Envirolech Job No. \_\_\_\_\_ of \_\_\_ By\_\_\_ Date Chkd. by \_\_\_\_\_Date \_ Subject \_\_\_\_\_ CULVERT DESIGN BY-PASS CULVERT TREATMENT PLANT ACCESS ROAD CULVERT

. 

ByKPN Chkd. by Subject	Date _ <sup></sup> ∑5-93 Date		<b>lehran</b> EnviroTec			<u>0276</u> 	
		angenerative de la constante en an		1-18"RC12	2-36"RLP	турд	
e , ne t .	nya ana ang ang ang ang ang ang ang ang an		99 Mar (2009), 1997, 2007, 2007, 2007, 2007, 2007, 2007, 2007	T.P. ALLESS ROAD	By. Pass	CLVRRT	en an gen ann an Ang
				5.0	٥,2%	925	
	·· · 2. 2 · 7	una na rusuu		2.9	6.7	SLOPA (%)	
				49	150	UEweth (Fr)	
				1050.9	1061.0	INLET ALRV.	
. 、			· · · · ·	1649.0	1050.80	outert	
				1.3	3.75	NEADWATER (FT)	-
				1054.2	1065.0	TOP OF HA	

aowa ll

 By
 KPH
 Date
 1/19-53
 Image: Subject
 Date
 1/122-19
 Image: Subject
 Subject
 Job No.
 02260 C 5
 Sheet No.
 of
 Subject
 Sheet No.
 of
 Sheet No.
 of
 Sheet No.
 tht

By-PASS CULURRT

CLUERT DESIGNED TO PASS THE 25 Yr 24 Hr STORM. CULVERT CONVEYS FLOW FROM IMPROVED STREAM CHANNEL AROUND THE PROPOSED SEDIMENT POND AND DISCHARGE INTO THE RELISTING STREAM CHANNEL. OUTLET PROTRETION/ WILL DE PROVIDED TO PROVIDE A SMOOTH TRANSITION INTO THE STREAM CHANNEL.

Q25 = 95 CFS SLOPE = CONSTRUCTIVELY ASSUME 6.7% LEWOTH = 150'

 $I_{N}I_{RT} = G_{N}T_{R0} = 7RY T_{M}I_{N} = 36" CPC (47.5 cFS/c-LART)$   $\frac{N_{N}}{D} = 1.25 \qquad N_{W} = 1.2 (3) = 3.75' (CNART 1)$   $O_{UTLRT} = G_{M}T_{R0} = 3.75' (CNART 1)$ 

$$H = 1.8 (CHART 5) \\ d_{C} = 2.3 (CHART 4) \\ h_{0} = \frac{d_{C} + \Delta}{2} \frac{2.3 + 3}{2} = 2.65$$

INPAT CONTRols HW= 3.75'

P.PL CAPACITY 
$$Q = \frac{1.44}{n} A(R)^{\frac{2}{3}} (5)^{\frac{1}{2}}$$
  
=  $\frac{1.44}{n} \frac{\Pi D^2}{4} \left(\frac{Q}{4}\right)^{\frac{2}{3}} (5)^{\frac{1}{2}} = \frac{1.44}{4^2} \frac{\Pi D^2}{4} \left(\frac{3}{4}\right)^{\frac{2}{3}} (\rho G7)^{\frac{1}{2}}$   
 $Q CAP GRC_{17Y} = 187.6 > 47.5$ 

.

•

# **TABLE 12 - ENTRANCE LOSS COEFFICIENTS**

Outlet Control, Full or Partly Full Entrance head loss

 $\left(\frac{\mathbf{V}^2}{2\mathbf{g}}\right)$  $H_e = k_e$ 

••

#### Type of Structure and Design of Entrance

A ....

. . . 1 . .

. .

.

Coefficient k.

- -

#### Pipe, Concrete

. . . . .

\_

Projecting from fill, socket end (groove-end)	0.2
Projecting from fill, sq. cut end	0.5
Headwall or headwall and wingwalls	
Socket end of pipe (groove-end)	0.2
Square-edge	0.5
Rounded (radius = $1/12D$ )	0.2
Mitered to conform to fill slope	0.7
*End-Section conforming to fill slope	0.5
Beveled edges, 33.7° or 45° bevels	0.2
Side-or slope-tapered inlet	0.2
Pipe, or Pipe-Arch, Corrugated Metal	
Projecting from fill (no headwall)	0.9
Headwall or headwall and wingwalls square-edge	0.5
Mitered to conform to fill slope, paved or unpaved slope	0.7
*End-Section conforming to fill slope	0.5
Beveled edges, 33.7° or 45° bevels	0.2
Side-or slope-tapered inlet	0.2
Box. Reinforced Concrete	
Headwall parallel to embankment (no wingwalls)	
Square-edged on 3 edges	0.5
Rounded on 3 edges to radius of 1/12 barrel	
dimension, or beveled edges on 3 sides	0.2
Wingwalls at 30° to 75° to barrel	
Square-edged at crown	0.4
Crown edge rounded to radius of 1/12 barrel	
dimension, or beveled top edge	0.2
Wingwall at 10° to 25° to barrel	
Square-edged at crown	0.5
Wingwalls parallel (extension of sides)	
Square-edged at crown	0.7
Side-or slope-tapered inlet	0.2

\*Note:

<u>ال</u>

25


**2** 

28

25


ŧ

The section conforming to fill slope," made of either metal or concrete, are the sections commonly available from manufacturers. From limited hydraulic tests they are equivalent in operation to a headwall in both inlet and outlet control. Some end sections, incorporating a closed taper in their design have a superior hydraulic performance. These latter sections can be



CRITICAL DE PTH CIRCULAR PIPE


184



u

U

CHART 5



CONCRETE PIPE CULVERTS FLOWING FULL n=0.012

BUREAU OF PUBLIC ROADS JAN. 1943

185

45 45 45	TR-55 GRAPHICAL DISCHARGE METHOD       VERSION 1.11         Project : COLESVILLE LANDFILL       User: KPH         County : BROOME       State: NY       Checked:         Subtitle: BY-PASS CULVERT       State: NY       Checked:         Data: Drainage Area       : 58.1 * Acres         Runoff Curve Number       : 79 *         Time of Concentration:       0.87 * Hours         Rainfall Type       : II         Pond and Swamp Area       : NONE								
8.6			=======		========			=	
	Storm Number	1	2	3	4	5	6 		
-	Frequency (yrs)	2	5	10	25	50	100		
	24-Hr Rainfall (in)	2.8	3.5	4.3	4.9	5.3	5.9		
	Ia/P Ratio	0.19	0.15	0.12	0.11	0.10	0.09		
	Used	0.19	0.15	0.12	0.11	0.10	0.10		
	Runoff (in)	1.04	1.57	2.21	2.72	3.06	3.59		
	Unit Peak Discharge (cfs/acre/in)	0.558	0.579	0.595	0.603	0.607	0.608		
•	Pond and Swamp Factor 0.0% Ponds Used	1.00	1.00	1.00	1.00	1.00	1.00		
-	Peak Discharge (cfs)	34	53	76	95	108	127	_	

\* - Value(s) provided from TR-55 system routines

TR-55 TC and TT THRU SUBAREA COMPUTATION VERSION 1.11 Project : COLESVILLE LANDFILL User: KPH, Date: 01-14-93 County : BROOME State: NY Checked: Date: 1/12/13 Subtitle: BY-PASS CULVERT Flow Type 2 year Length Slope Surface n Area Wp Velocity Time rain (ft) (ft/ft) code (sq/ft) (ft) (ft/sec) (hr) = \_\_\_\_\_ \_\_\_\_ \_\_\_\_\_\_ \_\_\_\_ 
 Sheet
 2.8
 300
 .25
 I


 Shallow Concent'd
 884
 .25
 U


 Open Channel
 884
 .25
 U
 0.584 0.030 Open Channel Open Channel 884 1.2 0.205 940 5.0 0.052 Time of Concentration = 0.87\* \_\_\_\_ --- Sheet Flow Surface Codes ---A Smooth SurfaceF Grass, Dense--- Shallow Concentrated ---B Fallow (No Res.)G Grass, Burmuda--- Surface Codes ---C Cultivated < 20 % Res.</td>H Words, LightP PavedD Cultivated > 20 % Res.I Words, DenseU Unpaved E Grass-Range, Short

\* - Generated for use by GRAPHIC method

County	ct : COLES y : BROOM tle: BY-PA	E			NY		Us Check	er: ed:	крн	Date	ERSION 2: 01- 2: <u>  22</u>	14-9
	COVER	DESCRIE					A		drologia	С		D
OTHER Woods	AGRICULTU	RAL LAN		fair			-			-	58.1	(79)
Total	Area (by 1	Hydrold	ogic Soil	Group)							58.1 ====	
		TOTAL	DRAINAGE		58.1	Acre	es			CURVE	NUMBE	R:79
* - Ge	enerated f	or use	by GRAPH	IIC meth	lod							

By KPN Date 1-21-93 Wehran Environech Job No. 62260 CS Chkd. by 14 Date 1/22/93 Wehran Environech Schutz Sheet No. \_\_\_\_\_ of \_\_ Subject / TRRATMENT PLANT ACCESS ROAD CULVERT - CULVERT LOCATED IN CHANNEL DC-1-2 TO Allow VENICLE TRAFFIC TO TREATMENT PLANT Q25: 5.0 CFS (FROM X-1-2 CHANNEL SIZING) 5 = 2.9, % L " 67 FT 1-18" RCP CULVERT TRY INIET CONDITION CHART 1 Hw = .85 Hw = .85(1.5') = 1.3' OUTLET CONDITION CHART 5 H = 0.2' h = de+D or Tw CHARF 4 de . 0.8' 0.8+1.5: 1.15 > 0.7 (FROM Q-1-2 FLOW DEPTIH ) Hu= H- L(50) - ho 0.2-67(.029) - 1.15 HN= O INTER CONDITION COVERAS 1-w= 1.3' CHREK PIPE CAPACITY  $Q_{Lap}^{=} \frac{1.49}{Q} A (R)^{2/3} (S)^{1/2}$ Quar = 1.49 (11.52) (1.5) 2/3 (0290) 1/2 QLAP 19.4 7 5.0 OK





REWISED MAY 1964 WITH INLET CONTROL


12

BUREAU OF PUBLIC ROADS JARL 1963

181

-

CHART 5



BUREAU OF PUBLIC ROADS JAK 1963

185

n = 0.012

#### TABLE 12 - ENTRANCE LOSS COEFFICIENTS

Outlet Control, Full or Partly Full Entrance head loss

$$H_{e} = k_{e} \quad \left(\frac{\underline{v}^{2}}{2g}\right)$$

Type of Structure and Design of Entrance

Coefficient k.

Pipe. Concrete

Projecting from fill, socket end (gioove-en Projecting from fill, sq. cut end Headwall or headwall and wingwalls									•	0.2 0.5
Socket end of pipe (groove-end)										0.2
Square-edge										0.5
Rounded (radius = $1/12D$ ) .										0.2
Mitered to conform to fill slope										0.7
*End-Section conforming to fill slope										0.5
Beveled edges, 33.7° or 45" bevels										0.2
Side-or slope-tapered inlet										0.2
Pipe, or Pipe-Arch. Corrugated Metal										
Projecting from fill (no headwall)										0.9
Headwall or headwall and wingwalls square	re-e	dge								0.5
Mitered to conform to fill slope, paved or										0.7
*End-Section conforming to fill slope .										0.5
Beveled edges, 33.7° or 45° bevels			•							0.2
Side-or slope-tapered inlet		•	•	•	•	•	•	•	•	0.2
Box. Reinforced Concrete										
Headwall parallel to embankment (no wing										
Square-edged on 3 edges	•	•	•	•		•	•	•	•	0.5
Rounded on 3 edges to radius of 1/12 t	11.80	ei								
dimension, or beveled edges on 3 sid	les		•	•	•	•	•	•	•	0.2
Wingwalls at 30° to 75° to barrel										
Square-edged at crown				•	•	•	•	•	•	0.4
Crown edge rounded to radius of 1/12										
dimension, or beveled top edge .	•	•	•	•	•	•	•	•	•	0.2
Wingwall at 10° to 25° to barrel										
Square-edged at crown	•	•	•	•	•	•	•	•	•	0.5
Wingwalls parallel (extension of sides)										
Square-edged at crown		•	•	•	•	•	•	•	•	0.7
Side-or slope-tapered inlet	•	•	•	•	•	٠	•	•	•	0.2

\*Note: "End Section conforming to fill slope," made of either metal or concrete, are the sections commonly available from manufacturers. From limited hydraulic tests they are equivalent in operation to a headwall in both inlet and outlet control. Some end sections, incorporating a <u>closed</u> taper in their design have a superior hydraulic performance. These latter sections can be

TR-55 GRAPHICAL DISCHARGE METHOD Project : COLESVILLE LANDFILL County : BROOME Subtitle: CHANNEL DC-1-2

State: NY

User: KPH Checked:

VER	SION 1.11
Date:	01-14-93
Date:	1/22/13

•	Data:	Drainage Area	:	2.3 * Acres
		Runoff Curve Number	:	80 *
		Time of Concentration	n:	0.48 * Hours
-		Rainfall Type	:	II
		Pond and Swamp Area	:	NONE

•			=======   2			========   5	
	Frequency (yrs)	2	5	10	25	50	100
-	24-Hr Rainfall (in)	2.8	3.5	4.3	4.5	5.3	5.9
-	Ia/P Ratio	0.18	0.14	0.12	0.11	0.09	0.08
	Used	0.18	0.14	0.12	0.11	0.10	0.10
-	Runoff (in)	1.10	1.64	2.29	2.46	3.16	3.69
	Unit Peak Discharge (cfs/acre/in)	0.788	0.814	0.833	0.836	0.844	0.844
<b></b>	Pond and Swamp Factor 0.0% Ponds Used	1.00	1.00	1.00	1.00	1.00	1.00
-	Peak Discharge (cfs)	2	3	4	5	6	7

.

\* - Value(s) provided from TR-55 system routines

TR-55 TC and Tt THRU SUBAREA COMPUTATION VERSION 1.11 Project : COLESVILLE LANDFILL User: KPH Date: 01-14-93 County : BROOME State: NY Checked: Date: 1/22/93 Subtitle: CHANNEL DC-1-2

Flow Type	2 year rain	Length (ft)	Slope (ft/ft)	Surface code	n	Area (sq/ft)	Wp (ft)	Velocity (ft/sec)	Time (hr)
Sheet Open Channe Open Channe		190 270 400	.01	E	 Т	ime of (	Concent	3.0 1.2 cration =	0.364 0.025 0.093 0.48*
A Smoot B Fallc C Culti	- Sheet Fi th Surface w (No Res ivated < 2 ivated > 2	e s.) 20 % Res.	F Gras G Gras H Wood	us, Dense us, Burmuda us, Light us, Dense		Sha] 	Surfac P Pa	oncentrate ce Codes aved apaved	d 

E Grass-Range, Short

\* - Generated for use by GRAPHIC method

TR-55 CURVE NUMBER COM Project : COLESVILLE LANDFILL County : BROOME State: NY Subtitle: CHANNEL DC-1-2	Us		VERSION Date: 01- Date: <u>1/2</u>	14-9
COVER DESCRIPTION	A		C Soil Group C (CN)	D
<pre>FULLY DEVELOPED URBAN AREAS (Veg Estab.) Open space (Lawns,parks etc.) Good condition; grass cover &gt; 75%</pre>		<del>-</del> .	- 2.3	(80)
Total Area (by Hydrologic Soil Group)			2.3	I
TOTAL DRAINAGE AREA: 2.3 Acr	:es	WEIGHTED	CURVE NUMBE	R:80
* - Generated for use by GRAPHIC method				
· · ·				

.....

By Chkd. by Subject	Date Date	<b>Wehran</b> Envirolech	Job No Of Sheet No of

CULVERT OUTLET PROTECTION

CULURAT OUTLET PROTECTION

COLRESVILLE LANDFILL

By KPH

OUTLET PROTECTION WAS DESKNED TO INSURE CHANNEL PROTECTION BEYOND THE DISCHARCE POINT OF THE CULURATS UNTIL FLOW VIELOCITIES ARTE REDUCED TO A CRUTEL CONSISTENT WITH A STABLE DOWN STRRAM CONDITION.

THE DESIGN PROCEDURE IS FROM THE NEW YORK STATE GUIDLINES FOR URBAR REPOSION AND SEDIMENT CONTROL (NYSGURSC)

CULVERT	DIAM	TA. I WATTER	BRSIGN CONDITION
BY-PASS	B6"RCP	0.8	TW & 0.50D.
T.P ALLESS	18 RCA	0.5 - 0.7 '	TW & 0.50 D

1. TAILWATTER ASSUNTED TO BE APPROX. DEPTH OF UPSTRICAN FLOW. FOR BY BY POSS CULVERT. ALRAI DOWNSTREAM. CHANNEL DEPTH (DC-1-2) USRO FOR T.P ACTESS WIVERT

By KPH Date 1-21-93			Emplemente	Job No0226	0.65
By         KPH         Date         1-21-93           Chkd. by         Date	-	Trental	IENVIROUEGU	Sheet No	of
Subject		ColESVILLE	LANDFILL		
	,				

#### OUTLELT PROTECTION

THE DESIGN CHARTS PROVIDED IN THE NYSGUESC REQUIRE FULL PAPE FLOW. SINCE THIS CONDITION DORS NOT REIST THE DEPTH OF FLOW AND VELOCITY AT THE OUTLET MUST BE USED.

#### DESIGN STRPS

1. CALCULATE & FOR & FULL FLOWING PIPE USING MANNING: EQN


# Q= 1.49 A (R) 2/3 (5/2

- 2 DETRRMINE do RATION FROM ATTACHED REFERENCE
- 3. DRITERMINE VIVELII USING REFERENCE
- 4. CALCULATE VELIL FROM GELIL (TOTAL AREA.
- 5. FIND VALT FROM VALT /VAIL
- 6. CAILULATE Quanyimph 2 VACTUAL + AACTUAL

USING depth of FLOW AS DIAMETTER.

7. DETERMINE OUTLET PROTECTION FROM GRAPH

Figure 5B.12 Outlet Protection Design - Minimum Tailwater Condition (Design of Outlet Protection from a Round Pipe Flowing Full, Minimum Tailwater Condition: T<sub>w</sub> < 0.5D<sub>o</sub>)



Ву <del>КАД</del> Chkd. by Subject		<b>Wehran</b> EnviroTech	Job No Sheet No	02260.<5 of	
,	· · · ·				

	CULVERT	OUTLANT	PROTTECTION	DESIGN	SUMMARY
- 1 mini 10 m	in. nitranæræk	సాదికి సంసం లోయునువింగా		e se la companya	n e n n
CULVERT	QNOM.	D50 REAU	REO LI	ENGTH OF	APRON
BY-PASS	20.0	D50=2		0	
T.P. ACLESS		ک <sub>50</sub> =۵		N/A	

ACCORDING TO DRISIGN PROCEDURE NO OUTLET PROTECTION IS REQUIRED.

12.5.62

DUR TO REPECTRO VRIOCITIRS THROUGH CUIVERT GUTLET PROTRECTION WIll be PROVIDED CONSISTING OF 20' LONG LEVEL APRIL WITH THE IST 9LF WILL be 18" GABION, THE REMAINDER d\_50 = 6"


REFER TO CULVERT BUTLET PROTECTION DETHIL IN PLAN SET

	By_KPH	_Date <u>⊢ 2 ⊢ 93</u> //)) _Date <u>1/22/63</u>				roTech	Job No	02260	. (5	_
	Chkd. by 174 Subject	Date _//22//63	Colitsu		۵۲٬۱۵۲ ۱٬۶۲۰ <u>مم</u>		Sheet No			
_		 1	w	ې						_
		Queri : Virer Virer	VPull 3	SHE REF	Stat Culvert	2 E	T.P. Access	BY PASS	CUNRRT	
		Act nd dupth of 4		APPRNDIX	ولال معاولا		21.0 CFS	188 CFS 67%	QEUI D	
-		Fee		19.2	Fur		3.4 %	6.7°%	SLOPE	
-		· · · ·	、		CAPACITY		- 09 :	36"	D Đ	0
-					CR ICULATION		Sces	47.5	QACT	OUTLIET P
•	•				11	-	U. 39	<b>o</b> 39	e d're	PROTECTION
-							0.59	71.1	هـ	
-							0.69	0.89	ชั้นกาย เป็	DRSIGN
-							11.88 FPS	26£ Frs	(金)	
-							8.2 FPS	18.4 Fis	VACTUAI	
-	·						2.2 CFS	20 CFS	Q Q nomactorish	

#### **APPENDICES**

# APPENDIX 19.C: Circular Channel Rat<sup>i</sup>os

Experiments have shown that n varies slightly with depth. This figure gives ''elocity and flow rate ratios for varying n (solid line) and constant n (broken line) assumptions.



APPENDICES

¥

*L***⊅**-∀

PROFESSIONAL PUBLICATIONS, INC. • Beimont, CA

Ву	Date
Chkd. by	
Subject	

SEDIMENT BASIN

DRSIGN STORM

SPILLWAY SIZING

SEDIMENT STORAGE

By KPH Date 1-20-93 Wehran EnviroTech Job No. 02266 CS Date 1/22/193 Chkd. by Sheet No. \_\_\_\_\_ of \_ COLRSVILLE LANDFILL SEDIMENT BASIN DESIGN STORM 10 yr 24hr STORM Q15 2 6B CFS (FROM TR-55) SIZE GABION SPILLWAY TO PASS ONE HUNDRED YEAR STORM ALONE AND ALLOW CONSTRUCTION OF THE SEDIMENT BASIN WITH ONE WTLET TOP ELEV 1658.8 ELEV 1055.0 - 12.0 FT ----SEDIMENT STULAGE 39.7 ALRES - 1800 LEIMERE -11,460CF = STURACE STORAGE FLEVATION & 1054.4 (SAR VOLUME CALC) MAXIMUM WATER ELEVATION 1056.5 ELEN 1058 1 OF FREEBUARD Ă 7 SPREMAY RET 1055.0 fe (105 or Myx SEDIMENT STOKAGE RLRU 1054.4

### DIVERSION CHANNEL DESIGN - GABION LINING

# JOB NO. 02260 CS

# COLESVILLE LANDFILL CLOSURE .SEDIMENT BASIN SPILLWAY

CHANNEL DEPTH (FT)	X-SECT AREA (SQ FT)	TOP WIDTH (FT)	HYDRAULIC RADIUS (FT)	DISCHARGE (CFS)	VELOCITY (FPS)	FROUDE NUMBER Nf
0.0	0.0	12.0	0.00	0.0	0.0	0.00
0.1	1.2	12.4	0.10	7.4	6.1	3.40
0.2	2.5	12.8	0.19	23.6	9.5	3.80
0.3	3.8	13.2	0.28	46.5	12.3	4.05
0.4	5.1	13.6	0.37	75.4	14.7	4.23
0.5	6.5	14.0	0.46	109.9	16.9	4.37
0.6	7.9	14.4	0.54	149.7	18.9	4.49
0.7	9.4	14.8	0.62	194.5	20.7	4.59
0.8	10.9	15.2	0.70	244.3	22.5	4.68
0.9	12.4	15.6	0.78	299.0	24.1	4.75
1.0	14.0	16.0	0.85	358.4	25.6	4.82

DESIGN DEPTH OF FLOW, D (FT)	0.5
VELOCITY, V (FPS)	16.9
TOTAL DEPTH INCLUDING FREEBOARD (FT)	1.5
GABION THICKNESS, t (IN)	18.0
FILLING STONE SIZE, d50 (IN)	6.0

S/N: 88020972

#### COLESVILLE LANDFILL SEDIMENT POND VOLUME

# CALCULATED 01-22-1993 16:25:46 DISK FILE : B:COLEVILL.VOL

#### Planimeter scale: 1 inch = 50 ft.

Elevation	Planimeter	Area	A1+A2+sqr(A1*A2)	Volume	Volume Sum	-
(ft)	(sq.in.)	(acres)	(acres)	(acre-ft)	(acre-ft)	
1,050.00	5.26	0.30	0.00	0.00	0.00	-
1,052.00	*I*	0.37	1.01	0.67	0.67	
1,054.00	*I*	0.45	1.12	1.50	1.50	
1,054.40	*I*	0.47	1.15	1.68 (73,	1.68	
1,058.00	11.00	0.63	1.37	3.65	3.65	

\*I\* ---> Interpolated area from closest two planimeter readings.

IA = (sq.rt(Area1) + ((Ei-E1)/(E2-E1))\*(sq.rt(Area2)-sq.rt(Area1)))
where: E1, E2 = Closest two elevations with planimeter data
 Ei = Elevation at which to interpolate area
 Area1,Area2 = Areas computed for E1, E2, respectively
 IA = Interpolated area for Ei

\* Incremental volume computed hy the Conic Method for Reservoir Volumes. Volume = (1/3) \* (EL2-EL1) \* (Area1 + Area2 + sq.rt.(Area1\*Area2)) where: EL1, EL2 = Lower and upper elevations of the increment Area1,Area2 = Areas computed for EL1, EL2, respectively Volume = Incremental volume between EL1 and EL2

2

TR-55 GRAPHICAL DISCHARGE METHOD Project : COLESVILLE LANDFILL County : BROOME State: NY Subtitle: SEDIMENT BASIN

VERSION 1.11 Date: 01-14-93 Date: 1/22/93

User: KPH

Checked:

Data:	Drainage Area	:	39.7	*	Acres
	Runoff Curve Number	:	83 *		
	Time of Concentration	n:	0.73	×	Hours
	Rainfall Type	:	II		
	Pond and Swamp Area	:	NONE		

Storm Number	1	2	3	4	5	6
Frequency (yrs)	2	5	10	25	50	100
24-Hr Rainfall (in)	2.8	3.5	4.3	4.9	5.3	5.9
Ia/P Ratio	0.15	0.12	0.10	0.08	0.08	0.07
Used	0.15	0.12	0.10	0.10	0.10	0.10
Runoff (in)	1.29	1.86	2.55	3.08	3.45	4.00
Unit Peak Discharge (cfs/acre/in)	0.645	0.663	0.673	0.673	0.673	0.673
Pond and Swamp Factor 0.0% Ponds Used	1.00	1.00	1.00	1.00	1.00	1.00
Peak Discharge (cfs)	33	49	68	82	92	107

\* - Value(s) provided from TR-55 system routines

Project : County : Subtitle:	COLESVILLE	E LANDFILI		J SUBAREA : NY		: КРН		VERSION Date: 01- Date: 1/2	14-93
Flow Type				Surface code				Velocity (ft/sec)	
Sheet Shallow Co Open Chann			.25 .25		Time	e of C	oncent	1.2 tration = (	0.584 0.042 0.100 0.73*
A Smoo B Fall C Cult D Cult E Gras	- Sheet Fl oth Surface low (No Res livated < 2 livated > 2 s-Range, S ited for us	e 5.) 20 % Res. 20 % Res. Short	F Gra; G Gra; H Woo; I Woo;	ss, Dense ss, Burmud ds, Light ds, Dense	la	-	Surfa P Pa	oncentrated ce Codes aved npaved	a 

.

TR-55 CURVE NUMBER CO Project : COLESVILLE LANDFILL County : BROOME State: NY Subtitle: SEDIMENT BASIN	User	: КРН	VERSION 1.11 Date: 01-14-93 Date: <u>  22193</u>
COVER DESCRIPTION	H A	Iydrologio B Acres	C Soil Group C D (CN)
<pre>FULLY DEVELOPED URBAN AREAS (Veg Estab.) Open space (Lawns,parks etc.) Poor condition; grass cover &lt; 50% Good condition; grass cover &gt; 75%</pre>	-	- - -	- 16.6(89) - 11.6(80)
OTHER AGRICULTURAL LANDS Woods fair	-	-	- 11.5(79)
Total Area (by Hydrologic Soil Group)			39.7 ====
TOTAL DRAINAGE AREA: 39.7 A	cres	WEIGHTED	CURVE NUMBER:83*
* - Generated for use by GRAPHIC method			

Ву	Date _
Chkd. by	
Subject	





ENERGY DISSAPATOR PAD

By KPH Date 1-21-	<u>73</u>		Job No.	02260.65
Chkd. by 124 Date 1/224	93 -	<b>Wehran</b> EnviroTech	Sheet No	) of
Chkd. by <u>124</u> Date <u>1/224</u> Subject		ColRSulla CANOFIL		

ENERGY DISSARTOR PAL

ENERGY DISSAPATOR PAOS ARE DESIGNED ON FLOW PROM CHANNEL DG-G (SER ATTACHED). BOTH INLET CHANNELS (DC-2-INLET & DC-G-INLET) WILL HAVE PADS AT THE INTRESECTION OF THE CHANNEL AND BASIN FLOOR.

PADS ARE PROVIDED AT POINTS WHERE CHANNELIZED FLOW WIll UNDERGO HYDRAULIC JUMP AND THE POTENTIAL FOR SEDURIMOR THE SUBGRADE IS PROBABLE.

THE DESIGN METHOD IS IN ACCORDANCE WITH PROCEDURES OUTLINED IN " NYDRAULIC DESIGN OF STILLING BASING AND RENTERGY DISSAPATORS " PUBLISHED by THE BUREAU OF RECLAMATION. NYDRAULIC JUMP CAICULATION'S BASED UPON PROCEDURES DISCUSSED IN "NANDBOOK OF NYDRAULICS " by BRATER AND KING

By KP11 Date -21-93		Job No. <u>02260 &lt;3</u>
Chkd. by 1/2/19 Date _1/22/193	<b>Wehran</b> Envirolech Collect LANDEIII	Sheet No of _
Subject //	 COIRSVILLE LANDFILL	

\_\_\_\_ of \_\_

ENERGY DISSAPATOR PAD DESIGN

\$\$ = 32.0 CFS V. = 7.6 FPS GENERATED FROM TR-55 AND CHANNEL SIZING SHERT REFER TO CHANNEL DC-6-INLET

DESIGN

1. DETERMINE FROUDE # + FOR FOLMULA REFER  $F = \frac{V_1}{\sqrt{3}D_1} = \frac{7.6}{\sqrt{32.2(0.9)}}$  TO ATTINCHED SHT F.6.7 F=1.41

2. DRITTRAMINTE CONJUGATE DRATH AFTER HUPRAULIC LUMP (02)  $\frac{D_2}{D_1} = \frac{1}{2} \int \sqrt{1 + 8F_1^2} - 1$  $D_2 = \frac{0.9}{2} \int \sqrt{1 + 8(1.41)^2} - 1$  $D_2 = 1.41$ 

3. DETERMINE LENGTH OF JUMP FROM FIG.7

For  $F_1 = 1.41$  <u>L</u> = 3.6 3.6(1.41) D

L= 5.0'

USE LENGTH 6.0' GABION PROTTECTION 12" THICK WIDTH 12.0' D50=6" F.Ilink




FIGURE 7.-Length of jump in terms of D<sub>1</sub> (Basin I).

the Federal Institute of Technology, Zurich, Switzerland, on a flume 0.6 of a meter wide and 7 meters long. The curve numbers are the same as the reference numbers in the "Bibliography" which refer to the work.

As can be observed from Figure 7, the test results from Flumes B, C, D, E, and F plot sufficiently well to establish a single curve. The five points from Flume A, denoted by squares, appear somewhat erratic and plot to the right of the general curve. Henceforth, reference to Figure 7 will concern only the recommended curve, which is considered applicable for general use.

#### Energy Absorption in Jump

With the experimental information available, the energy absorbed in the jump may be computed. Columns 14 through 18, Table 1, list the computations, and the symbols may be defined by consulting the specific energy diagram in Figure 4. Column 14 lists the total energy, E<sub>1</sub>, entering the jump at Section 1 for each test. This is simply the depth of flow, D<sub>1</sub>, plus the velocity head computed at the point of measurement. The energy leaving the jump, which is the depth of flow plus the velocity head at Section 2, is tabulated in Column 15. The differences in the values of Columns 14 and 15 constitute the loss of energy, in feet of water, attributed to the conversion, Column 16. Column 18 lists the percentage of energy lost in the jump, EL, to the total energy entering the jump, E1. This percentage is plotted with respect to the Froude number and is shown as the curve to the left on Figure 8. For a Froude number of 2.0, which would correspond to a relatively thick jet entering the jump at low velocity, the curve shows the

# UNIVERSAL SOIL LOSS CALCULATIONS

.

.

By <u>KPH</u> Date <u>3-22-13</u> Chkd. by <u>/71</u> Date <u>3/23/03</u> Subject <u>Date 3/23/03</u> **Wehran** Environech Job No. <u>62260 CS</u> Sheet No. \_\_\_\_\_ of \_\_\_\_

UNIVERSAL SOIL LOSS EQUATIONS (USLE)

- CALCULATIONS -

USLE WAS PERFORMED ON TWO DISTINCT AREAS, THE FILST AREA CONSSISTS OF THE PORTION OF THE SITE TRIBUTARY TO THE SEDIMENT POND THE SECOND AREA CONSISTS OF THE AREA TO BE CAPPED THAT IS NOT TRIBUTARY TO THE SEDIMENT POND.

FOR RACH AREA THE SOIL LOSS AND SEDIMENT VIELD WAS CALLIATED ASSUMED CONDITIONS, TOTAL SCARIFICATION AND TOTAL VIEGRITISTIONS

FOR THE AREA TRIBUTARY TO THE SEDIMENT FUND THE ASSUMPTION OF ENTIRE SCARIFICATION WAS USED TO CHECK THE SEDIMENT STORACE CAPTICITY OF THE POND ON A WORST CASE SITUATION. AS SHOWN ON THE SUMMARY TABLE THE **MAILABLE** SEDIMENT STORAGE EXCERDS THE PREDICTED YIELD FROM THE WORST CASE SCANERIO, THE USLE WAS PERFORMED FOR THE SECOND AREA, NOT TRIBUTARY TO THE SEDIMENT POND, ASSUMING TO THE SCANERIO, THE SEDIMENT POND, ASSUMING TO THE SCANERIO, THE SEDIMENT YIELD RECERDS THE RECOMMENDED VALUE IT MUST BE RECOGNIZED THAT BASED UPON THE EXISTING SITE TOPOGRAPY, TYPICAL FINAL OVER CONSTRUCTION PROCEDURE AND PROPOSED STORMULATER CONTROL MERSURES IT IS EXTERMENT UNLIKELY THAT THIS CAN OR WILL OCCUR DURING THE CONSTRUCTION SEQUENCE,

ву_ <u>крк</u>	Date <u>3-22-93</u>	$\sim$		<b>ran</b> Envirotech Lawe, //	Job No	ozza u cs
Chkd. by	Date <u>3/23/93</u>	-			Sheet No	of
Subject // /			Colasvilia	LANDF,11	_	

UNIVERSAL SOIL LOSS EQUATION

THE UNNERSAL SOIL LOSS REQUATION (USLE) IS UTILIZED TO RETIMATE SOIL PROSION DUE TO STURMMATTER RUNOFF FROM SPRCIFIC FIELD ARRAS, THE USLE PREDICTS SOIL LOSS AS A PRODUCT OF SIX VARIABLES NUMERICULLY REPRESENTED, THE USLE is JUBSTANTIAlly less ACURATE IN PREDICTING SHORT TERM VARIATION IN SOUL IUSS AND IS BEST USED AS A MRANS FOR PRECICTING LONG TERM AURRACES. THR USUR CALLULATRS SOIL, LOSS DUR TO THE EROSIUR FORCE OF RAINFAIL (GROSS FERDSION), THE EQUATION DORS NOT TAKE INTO CONSIDERATION SEDIMENT DEPOSITION WITHIN THE WATERSHIED. A SEDIMENT YIELD FACTOR HAS been USED TO Adjust THE GROSS REDSION OKELEING TO WHAT ACTUALLY MICRATES OFF SITE. THE VIELD FACTOR TAKES INTO ACCOUNT RELIRE OF MATERSHED, CHANNELIZATION OF STURMMATER WATERS, HED SIZE AND SUIL CHARACTERISTICS. DUR TO THE LARGE DECLEE OF UNKERTHINTY WITH THE PARAMETERS AN ESTIMATE WAS MADE BASED ON RECHENDATIONS IN THE NEW YORK STATE GLIDUNES FOR URBAN EROSION AND SEDIMENT CONTRol.

THE USLEWAS ALSO PERFORMED FOR BOTH WATERSHEDS ASSUMING POST CONSTRUCTION CONDITION OF TOTAL VEGETATION. AS SHOWN ON THR SUMMARY TABLE THE SEDIMENT YIELD FOR BOTH ARRAS is WITHIN ACCAPTABLE LIMITS (ILSS THEN 2.0 TONS/ARELY). SINCE THE REMOVAL OF THE SEDIMENT POND IS CONTINGENT -----UPON THE RETABLISHMENT OF VELETATION IN THE BORROW ARRA THR HIGH SEDIMENT VIELDS FROM THIS ARRA W.II be HANDLED BY THE SEDIMENT POND. FOR THE AREA NOT TRIBUTARY TO THE SEDIMENT POND; SEDIMENT YIELD CAN BE REPECTED TO BE LIESS THEN THE 2.0 TOW / ACRES VR RECORDED SINKER THE AREA SCARIFIED WIll be only A lim, TED PORTION OF THE TUTAL AREA WITH THE REST OF THE AREA BLING UNDISTURBED OR MUICHED FOR FINAL COVER

Colesville

By KPH

Subject 2

Chkd. by 1 20 Date 3/23/13

\_\_\_\_\_Date 3-22-93

Wehran EnviroTech Job No. 02263 CS

LANDFILL

Sheet No.

	NOT ENTERING INTO ENTERLY 16.8 233 SEMMENT PASINI SAMERICO (AREA = 13.9.4.4.)	ENTRELY 4.76 189.0 VELETHTRD .	ENTERING INTO ENTERLY 95,2 3779 SEDIMENT BASIN SCARIFIED (AREA=39,7AC)	AILAGE AREA COVIRE GROSS EROSION/YE DESCRIPTION PARAC TOTAL DESCRIPTION PARAC TOTAL (TUNS/AC) (TONS)	UNINERSAL SE
.25	5.0	647	38.1	TASIR SRDIMENT PERAL	Soil Loss Equa
μ Υ	69.9	75.4	1511.6	VIELD /VR. Totac	A TTOK
≿/ <del>4</del>	N//#	N/#	£ 681	POND SUMBI (TONS) (TUTHL)	
N/A	~/4	N/A	645	POND SEDIMENT STORAGE (TONS) (TUTAL) (CLEARIOUT LEVIL)	


By KON Date 3.22-93 Wehran EnviroTech Job No. 62240.CS Chkd. by 1/22 Date 3/22/43 Wehran EnviroTech Sheet No. \_\_\_\_\_ of \_\_\_\_

By KPH Date 3/19/93 Chkd. by 12:1 Date 3/23/93 Subject C 7	Wehran Envirolech Job No. <u>2260 CS</u> Sheet No of
U	WIVERSAL SOIL LOSS EQUATION
ARRA E	ENTERING INTO RELLAIMED SEDIMENT BASIN.
EQUATION A	RKLSC
COMPUTE	SOIL LOSS ASSUMING REASTABLISHMENT OF
UEGETATION II	VALL AREAS.
R=10 K=0 * LS= C=	1.2B
CALCULATIS	A = TONS/ACRE YEAR
<i>i</i> t = 10	00 (0.28) (3.4) (0.05) = 4.76 Tous /ALRE YEAR
A 23	PRASENTS SOIL LOSS . ACTUAL SEDIMENT VIELD
RANGES	FROM 10 70 70% OF LOSSES
CONSERATIVEL	Y ASSUME 40% OF SOLL MOVIES OFF SITTL.
1-550 ~ P	TION RASED UPON RELATIVELY MILD SLOPES
AT P	ELIMETER OF DRAINAGE AREA AND CURLESPONDING

Sac DEPOSITION,


H.76 TIMS / ALLE YEAR & 0.40 = 1.90 TONS/ACER YEAR

1.9 T/ACYT - ACTUAL OFFSITTE SOIL LOAD.



Chkd. by 114 Subject	Date <u></u>		(olesville	DETOTIVAEN (	Sheet No	of
		UNIVERSAL	Soil La	55 EQUATION		
				·		
	Eq	A = R x	КШ			
		A- COMP	JAED SUIL	loss per acri	E IN TONS	
		R= Rain	JFAIL INT	ENSITY FACTOR		
				TH FACTUR		
		<b>2</b> - 3 tot		IN FACIOR		
		S = Slut	PR_ GRAD	IENT FACTOR		
	<u> </u>					
	COMPUTE	2011 102	s for	IYRAK		
		R= 100				
	# to			<b>20</b> 2		
	DISTURBED A	REA ELTERI SEDIMENT		= 39,7 KRE	<b>&gt;</b> -	
<i>.</i>		-		JT - 10%		
		AURPACE	SLOPE	LENGTH = 600	o '	
		V				·
		K VALUE		tial Till - eca	KSE SLUTY N/ PH	is use of the
			K= 0.	28		
		LS VALUM	l (se i -	TABLE B.Y) 3	.4	
	A =	100 (0.28)	£ 3.4)(39.7)	= 3,779 · -	ONS	
					1	
				DENSITY 135 1		
	3-	179 JUNS + 20	للـــــــــــــــــــــــــــــــــــ	$\frac{1}{2} = 2074$	Cy/YR	
			Tim	CF		

\* FOR ARTIA NOT ENTERING INTO THE SEDIMENT POND AREA. 13.9 AR R=100, L= 200', K= 0.28 SLOPE - 4% LS: 0.6 A= 100 (0.28)(0.6)(13.9) • 233TONS/YR 233TONS/REEE - 2000/05 • 168 • 204 The 13515 • 205 = 1284/YR



Appendix 5A	EKUSIUN AND SEDIMENT TIELD	LAIELU					391
Table 5.A.1 Typical C Factor Values Reported in the Literature.*         Condition	Table 5.A.2.	C Factors for Mechanically Prepared Woodland Sites.	epared W	/oodlar	nd Site	4.	
	Demont of coil collemn with maidue						
6-8 inches			Soil Condition and Weed Cover	n and W	/eed Co	ver	
						(	
ĥ		Excellent	읽		a		X
gh			NC WC	NC NC	MC MC	NC	MC MC
	0 NOICE NOICE A Disked raked or hedded1.2.	\$7 20	LC CL			04	۶K
cross slope	ć	.25 .10	.26 .10		12	45	21
		.07				.29	Ξ
	10% Co						
unprepared seedbed		.33 .15			.24	.60	.26
	e e	.23 .10			Ξ.	.36	.16
onths chemical	C. Drum chopped <sup>3</sup> .	.07	.16 .07		80.	.23	.10
sted	20% Cc						
	A.	.24 .12			.20	.44	5
xcept scraped	.30 B.	.19 .10	.19 .10		Ξ.	.27	.14
0	15.	.12 .06		6 . I4	.07	.18	S.
sawdust 2 inches deep, disked in	40% Cc	:					
	÷.		.23 .14		- <u></u>	<u>.</u>	61.
۵	J.019 B. Burned <sup>2</sup>					2	:5
000 gauons/acre							2
IIS/acre	00%	11		10			2
Dust binder		0. 00	00 60 C		1 80		38
		0.05				-0	Ö
1 210 gallons/acre	SION CO						
Unter circinicais 1000 h Ether alone router with 20 150 millions losse 001 - 0		.05 .04				.10	ŏ
	E EI	.04 .04	.05 .04			8	<u>.</u> 05
v 70–10 nercent cover	4 C. Drum chopped <sup>3</sup> .			3 .03	.03	\$	ġ
c	. 						
	an I. Mul	g values to accou	int for su	irface ro	oughnes		
-Tack		on runoff and sed	iment sto	orage,		:	
slines 1400 lk/scre fresh	depressions greater than 6 inches	inches			•	.40	
	Moderate Moderate				•	.65	
	Smooth, minor surface sediment storage, depressions	liment storage, d	epression	s			
temporary 0 to 60 days <sup>2</sup> 0.40						.90	
e E	2.	the first year fol	lowing tr	catmen	t. For	A typ	e site
	5 Comments of the Sears of a multiply C value by ./ to accound for aging. For sites 4 to 6 Sears of the Sears	value by ./ to	account veare old	nor agu uee Tal	lg. ror hle 5 7	siles 4	2
	-			nac 1 a			
If plantings are used with mulches, use the minimum C values.	3.	eas are for the fi	rst 3 year	s follow	ving tre	atmen	t. Fo
It dry weather occurs at planting and emergence is a problem, extend the		se Table 5.6. Fo	or sites to	reated 1	more t	han 8	year
U-bu days to a period when rainfall normally occurs.	ago use Table 5.7. 4 Soil Conservation Service (1077)						

č

## Table B.3 (cont'd)Approximated K Values for Some Representative Soils InConstruction Sites in New York

Depositional Unit, Family Textural Class				Erodibility C K Valu	llass & K Values ues <sup>3,4</sup>
and Representative Series	Horizon <sup>1</sup>	Texture <sup>2</sup>	<u>Class</u>	Range	Norm.
I. Glacial Till (cond't)					
Cazenovia	Α	sil	High	0.37-0.49	0.43
	Bt	sicl	High	0.37-0.49	0.43
	С	gsil	Medium	0.24-0.32	0.28
Nunda	Ар	ch sil	High	0.37-0.49	0.43
	B2	ch sil	High	0.37-0.49	0.49
	IIB2t	gcl	Medium	0.24-0.32	0.28
	IIC	gl	Medium	0.24-0.32	0.28
FINE		-			
Hornell	Α	sil	Medium	0.24-0.32	0.28
	В	sic	High	0.37-0.49	0.43
	С	sh sic	Mcdium	0.24-0.32	0.28
	R	,	Shale bedroci	k 20 to 40" below	surface.
Remsen	Α	sic	High	0.37-0.49	0.43
	Bt	c	Medium	0.24-0.32	0.28
	С	c	High	0.37-0.49	0.43
Churchville	Α	sil	High	0.37-0.49	0.43
	Bt	sic	Medium	0.24-0.32	0.28
	IIC	gl	Mcdium	0.24-0.32	0.28
COARSE LOAMY, NO PAN					
Charlton	Α	fsl	Low	0.10-0.20	0.17
	В	fsl	High	0.37-0.49	0.43
	С	gfs1	Medium	0.24-0.32	0.28
Nellis	Α	1	Medium	0.24-0.32	0.28
	В	1	High	0.37-0.49	0.43
	С	gl	Medium	0.24-0.32	0.28
Pittsfield	Α	1	Mcdium	0.24-0.32	0.28
	В	gfı∥l	Low	0.10-0.20	0.17
	С	gfsi	High	0.37-0.49	0.43
COARSE LOAMY/SANDY o	r SANDY SKEL	ETAL,			
Canton	Α	fsl	Medium	0.24-0.32	0.28
	В	fsl	Very High	0.55-0.78	0.64
	IIC	vgis	Low	0.10-0.20	0.17
COARSE SILTY w/PAN					
Canaseraga	Α	sil	High	0.37-0.49	0.43
	B	sil	Very High	0.55-0.78	0.46
	IIBx & C	ch	High	037-0.49	0.43

Section 11

## Table B.4 Slope-Effect Table

	100	25.7	31.5	36.4	40.7	44.6												
	50	6.9	8.4	9.7	10.9	11.9	12.9	13.8	15.4	16.9	21.8							
	40	4.6	5.6	6.4	7.2	7.9	8.5	9.1	10.2	11.2	14.4	20.4	24.9			_		
	35	3.6	4.4	5.0	5.6	6.1	6.7	7.1	8.0	8.7	11.3	15.9	19.5	22.6	25.2			_
	30	2.7	3.3	3.8	4.3	4.7	5.1	5.4	6.0	6.6	8.5	12.1	14.8	17.1	19.1	20.9	24.1	
	25	2.0	2.4	2.8	3.1	3.4	3.7	3.9	4.4	4.8	6.2	8.7	10.7	12.4	13.8	15.1	17.5	19.5
	20	1.3	1.6	1.9	2.1	2.3	2.5	2.7	3.0	3.3	4.2	5.9	7.3	8.4	9.4	10.3	11.9	13.3
Value ope(s)	18	1.1	1.4	1.6	1.7	1.9	2.1	2.2	2.4	2.7	3.5	5.0	5.9	6.0	7.6	8.3	9.6	10.8
LS Value X Slope(s)	16	6.	1.1	1.3	1.4	1.6	1.7	1.8	2.0	2.2	2.8	4.0	5.0	5.0	6.4	7.0	8.1	9.1
	14		6.	1.5	1.2	1.3	1.4	1.5	1.7	1.8	2.3	3.3	4.0	4.7	5.2	5.7	6.7	7.4
	12	<b>9</b> .		.8	6.	1.0	1.1	1.2	1.3	1.4	1.8	2.6	3.2	3.6	4.1	4.5	5.1	5.8
	10	4.	.5	••	.7	8.	8.	6.	1.0	1.1	1.4	2.0	2.4	2.8	3.1	3.4	3.9	4.4
	æ	.3	.4	.4	•5	.5	•6	•6	.,	8.	1.0	1.4	1.7	2.0	2.2	2.4	2.8	3.14
	9	.2	.3	.3	.3	4.	.4	.4	••			1.0	1.2	1.4	1.5	1.7	1.9	2.1
	4	-	.2	.2	.2	.2	.2			•3	4.	9.	۲.	8.	6•	1.0	1.2	1.3
	2	-	.1	-		.1	.1	.2	.2	.2	.2	.3	•4	4.	.5	••	••	
Slope Length	(T)	10	15	20	25	30	35	40	50	60	100	200	300	400	500	600	800	1000

(LS) =  $\frac{V L}{X} (.76 + .53s = .076s^2)$ 

October 1991 - Third Printing

Section 11

## Table B.3 (cont'd)Approximated K Values for Some Representative Solis on<br/>Construction Sites in New York

						-
Depositional Unit, Family Textural Class				Érodibility C K Valu	lass & K Values 1es <sup>3,4</sup>	
and Representative Series	Horizon <sup>1</sup>	Texture <sup>2</sup>	Class	Range	Norm	-
L Clasic III (condit)						
I. Glacial Till (cond't) LOAMY SKELETAL						-
Manlius	A	sh	Medium	0.24-0.32	0.28	
	B	vsh sil	Low	0.10-0.20	0.17	
	C	fract'd	Low	0.10-0.20	0.17	
		shales w/ silty	y fines			
	R		Shale bedro	ck 20 to 40" below	surface.	
FINE LOAMY w/PAN						-
Volusia	A	ch sil	Low	0.10-0.20	0.17	
	Bx	ch sil	High	0.37-0.49	0.43	
	C	vch l	Medium	0.24-0.32	0.28	
FINE LOAMY, NO PAN						
Kendaia	A	sil	Medium	0.24-0.32 /	0.28	في
	B	gsil	Medium	0.24-0.32	0.28 /	
	C	gl	Medium	0.24-0.32	0.28	
II. Glacial Outwash and Wate	er Worked Morain	aic Deposits				
SANDY SKELETAL						
Hinckley	A	ls	Low	0.10-0.20	0.17	
	B	gls	Low	0.10-0.20	0.17	-
	C	vgs	Low	0.10-0.20	0.17	
SANDY						-
Colonie	A	lfs	Medium	0.24-0.32	0.28	_
	Б	fs	Low	0.10-0.20	0.17	
	c	fs	Low	0.10-0.20	0.17	
LOAMY SKELETAL						
Chenango	A	gl	Low	0.10-0.20	0.17	
	B	vgl	Low	0.10-0.20	0.17	
	¢	gis	Low	0.10-0.20	0.17	
FINE LOAMY/SANDY or S	•		_			
Palmyra	*	gl	Low	0.10-0.20	0.17	
	B	gl	Medium	0.24-0.32	0.28	
	¥С	g & s	Low	0.10-0.20	0.17	-
LOAMY SKELETAL/CLAY						-
Varysburg	A	gl	Low	0.10-0.20	0.17	
	₿2t	vgi	Low	0.10-0.20	0.17	
	liB2t	sic	Medum	0.24-0.32	0.28	
	<b>IIC</b>	layered	High	0.37-0.49	0.43	
		sic,sil sicl				


.


## APPENDIX D SOIL ANALYSIS


·


· ·


. .

















.....





**,** 




e











-----














\_\_\_\_







.....


•










-----











	(	GR	<b>A</b> ]	٢N	١	S	Ι	Ζ	Έ	-	1	D	Ι	S	57	ΓF	7:	I	B		רן	Γ.	Ι	0	N		٦	ΓE	Ξ	5	Т	F	RE	Ē	כן	DI	7	Т			
10	00	6 In.			2 IN. 1-1/2 1	1 tn.	3/4 In.		1/4 Ju.				5			<b>A</b> 10			120		070		#60					£200													
	30							:																																	
	30-																																								
	70																		:																						
ЧЕН	50																							I																	
LL.	50																																								
JCE	40																																_								
-	30																																								
	20																																								
	10																									_								$\parallel$							
	0																																								
	20	10 1	00					1	0	. 0						(		. C A ]		5	5I.	ZE		_	ពា៣		. 1						0	. 0	1				(	D.C	001
5. • 5-		<b>%+</b> 7	_		;	<b>x</b> e	5 <b>R</b> A 0.		EL	_				_			_			54 6 .											<b>%</b> 2	SI 5.			_			<mark>% (</mark> 8	. 0		
									_							_	-							_			_										_				
	LL		F	PI				085	_	T			060	_			_	)5(		Ţ	_	_	D3		_	_		21!			_	D1			_	C,				C.	_
•				_			0.	30	)		C	).	19	}			).	16	<u> </u>	+	0	. (	06	50	╡	0.	0	13	38		<u>).</u>	00	69		2	. 6	5		2	8.	0
			_	_		MAT	FEF		AL		DE	s	R	IP		ION	N		_				_	_		_	-	T	A	ST	M	В	JURI	MI	ST	EF	1		AS	нт	0
-	llty	) / 58	nd																											SM								A-	-2-	4 (	0)
Proj Proj Clie • Sa	)ect ent:	:: С ВЯ		SV IE	ILL COL	LE UNT	∟А ГҮ.									Da									17				E C R	nt he em	er Icki Iari	ed ed ks	ed by by E	/: /:	к Я	. H I. S	1. 5.4	١.	14	. 05	ĸ
					١		HER			Ð	łG	I	NE	12	R	IN	G												F	ig	ur	e	NO	•							















-







-








\_




ي ا



\_\_\_\_

.



-

-

APPENDIX E PERMIT APPLICATION AND VARIANCE APPLICATION

DEPARTMENT OF ENVIRONMENTAL	CONCERNATION	PROTECT NO.	
APPLICATION FOR VARIANCE			DATE RECEIVED
EE APPLICATION INSTRUCTIONS ON REVERSE SIDE	NOR O RIGHT SUU	DEPARTMENT ACTION	DATE
. OWNER'S NAME	2. ADDRESS (Street, City, State, Zip Code		3. Telephone No.
Broome County	P.O. Box 1766, Binghamt		(607)-778-2482
OPERATOR'S NAME	5. ADDRESS (Street, City, State, Zip Code		6. Telephone No.
Broome County	P.O. Box 1766, Binghamt 8. ADDRESS (Street, City, State, Zip Code		(607)-778-2482
ENGINEER'S NAME Wehran-New York, Inc.	666 East Main Street, Mi		9. Telephone No. 40 (914)-343-0660
D. PROJECT/FACILITY NAME	ooo Last Main Street, Mi		40 (314/-343-0000
Colesville Landfill			
1. PROJECT STATUS	12. COUNTY IN WHICH FACILITY IS LOCA	ATED 13. ENVIRON	MENTAL CONSERVATION REGIO
Public Private Proposed Existing     A. DESCRIBE SPECIFIC LOCATION OF FACILITY	Broome County		
The Colesville Landfill is located o East Windsor Road, 150 feet east o	n a 117-acre parcel of land ou f the intersection of Dyer Fla	wned by the Count at Road.	y of Broome on
5. TYPE OF PROJECT FACILITIES: Composiing T Resource Recovery-Energy Resource Recov 6. BRIEFLY DESCRIBE THE PROJECT INCLUDING THE BA	verv-materials 🗍 Other	Sanitary Landfill 📋 Incin	eration 📑 Pyrolysis
The proposed construction includes accordance with 6NYCRR Part 360 provide final cover soils within the	the installation of landfill fir Regulations. Additionally, a	nal cover over the a 17–acre borrow a	entire 31–acre site in rea will be developed t
7. SPECIFIC PROVISION OF 6 NYCRR 360 FROM WHICH	A VARIANCE IS REQUESTED: Section 360-2.1	3 (P)(2)(i)	ariance Request No.
8. BRIEFLY DESCRIBE PROPOSED VARIANCE The proposed gas venting layer will or a geocomposite drain, with 12-in 12-inch layer. The proposed alterna sufficient protection to the overlyin	ich collection trenches in eac atives have equivalent or bett	h alternative inste	ad of the required
The proposed gas venting layer will or a geocomposite drain, with 12-in 12-inch layer. The proposed alterna	ich collection trenches in each atives have equivalent or bett ng flexible membrane liner. ign Report Appendix G for Ga	h alternative inste ter venting capabil	ad of the required ities while providing
The proposed gas venting layer will or a geocomposite drain, with 12-in 12-inch layer. The proposed alterna sufficient protection to the overlyin Refer to the Final Engineering Desi 9. IMPACTS OF VARIANCE APPROVAL OR DISAPPROVA a. Environmental Impact: No environmental impact is associa	ach collection trenches in each atives have equivalent or bett ng flexible membrane liner. ign Report Appendix G for Ga L:	h alternative inste ter venting capabil as Venting Layer E	ad of the required ities while providing quivalency Calculation
The proposed gas venting layer will or a geocomposite drain, with 12-in 12-inch layer. The proposed alterna sufficient protection to the overlyin Refer to the Final Engineering Desi 9. IMPACTS OF VARIANCE APPROVAL OR DISAPPROVAL a. Environmental Impact:	ach collection trenches in each atives have equivalent or bett ng flexible membrane liner. ign Report Appendix G for Ga L:	h alternative inste ter venting capabil as Venting Layer E	ad of the required ities while providing quivalency Calculation
The proposed gas venting layer will or a geocomposite drain, with 12-in 12-inch layer. The proposed alterna sufficient protection to the overlyin Refer to the Final Engineering Desi 9. IMPACTS OF VARIANCE APPROVAL OR DISAPPROVA a. Environmental Impact: No environmental impact is associa	ach collection trenches in each atives have equivalent or bett ng flexible membrane liner. ign Report Appendix G for Ga  ted with the variance. Each enting layer.	h alternative inste ter venting capabil as Venting Layer E alternative has bee	ad of the required ities while providing quivalency Calculation 

DEPARTMENT OF ENVIRONMENT APPLICATION FOR VARIANC SEE APPLICATION INSTRUCTIONS ON REVERSE SIDE . OWNER'S NAME		PROJECT NO.	DATE RECEIVED
EE APPLICATION INSTRUCTIONS ON REVERSE SIDE	L I ROM O RICAN 300		
		DEPARTMENT ACTION	DATE
	2. ADDRESS (Street, City, State, Zip	Approved Disa	
Broome County	P.O. Box 1766, Binghar		3. Telephone No. (607)-778-2482
OPERATOR'S NAME	5. ADDRESS (Street, City, State, Zip		6. Telephone No.
Broome County	P.O. Box 1766, Binghar	nton, NY 13902	(607)-778-2482
ENGINEER'S NAME	8. ADDRESS (Street, City, State, Zip	Code)	9. Telephone No.
Wehran-New York, Inc.	666 East Main Street,	Middletown, NY 1094	<u>0 (914)-343-0660</u>
0. PROJECT/FACILITY NAME Colesville Landfill			
1. PROJECT STATUS	12. COUNTY IN WHICH FACILITY IS	LOCATED 13. ENVIRO	NMENTAL CONSERVATION REGION
🕱 Public 📋 Private 📋 Proposed 📋 Existing	Broome County		
4. DESCRIBE SPECIFIC LOCATION OF FACILITY The Colesville Landfill is located East Windsor Road, 150 feet eas			ty of Broome on
5. TYPE OF PROJECT FACILITIES: Composiing	] Transter 📋 Shredding 📋 Baling	XX Sanitary Landfill 🔄 Incir	neration 🗌 Pyrolysis
Resource Recovery-Energy Resource Recovery-Energy			
6. BRIEFLY DESCRIBE THE PROJECT INCLUDING THE The proposed construction including			entiro 31-aoro sito in
accordance with 6NYCRR Part a provide final cover soils within t	360 Regulations. Additions he 117-acre parcel.	llly, a 17-acre borrow	
7. SPECIFIC PROVISION OF 6 NYCRR 360 FROM WHIC	H A VARIANCE IS REQUESTED: Section	.13 (r)(2)(11)	ariance Request No.
	w area to fill over the existence 1984		
Additionally, since the site has n localized areas at the site. Refer to the Final Engineering D	ot received waste since 1984 Design Report Appendix B fo	; only minor settleme	nt is expected in
Additionally, since the site has n localized areas at the site. Refer to the Final Engineering D 9. IMPACTS OF VARIANCE APPROVAL OR DISAPPROV a. Environmental Impact:	ot received waste since 1984 Design Report Appendix B fo	; only minor settleme	nt is expected in Evaluation.
Additionally, since the site has n localized areas at the site. Refer to the Final Engineering D 9. IMPACTS OF VARIANCE APPROVAL OR DISAPPROV	ot received waste since 1984 Design Report Appendix B for AL: Expected with the variance our after final closure of the site will be performed to ditionally, a maintenance pro- spections of the final cover riance will result in signification	s only minor settleme r landfill Settlement e. Analysis of the site site. To minimize the effect early indicatio rogram will be implem and rapidly restore lan ant environmental imp	nt is expected in Evaluation. e predicts only minimal e potential for adverse n of settlement and its nented to address any ndfill grade and pacts due to either
Additionally, since the site has n localized areas at the site. Refer to the Final Engineering D 9. IMPACTS OF VARIANCE APPROVAL OR DISAPPROV a. Environmental Impact: Limited environmental impact is amounts of settlements will occu impact, regular inspections of th potential impact to the site. Ad deficiencies identified during ins drainage. Disapproval of the van relocation of the in-place waste	ot received waste since 1984 Design Report Appendix B for AL: Expected with the variance our after final closure of the site will be performed to ditionally, a maintenance pro- spections of the final cover riance will result in signification	s only minor settleme r landfill Settlement e. Analysis of the site site. To minimize the effect early indicatio rogram will be implem and rapidly restore lan ant environmental imp	nt is expected in Evaluation. e predicts only minimal e potential for adverse n of settlement and its nented to address any ndfill grade and pacts due to either

NEW YORK STATE DEPARTMENT OF ENVIRONMENTAL CONSERVATION DIVISION OF SOLID WASTE DEPARTMENT USE ONLY DEC APPLICATION NUMBER


FACILITY CODE

# APPLICATION FOR A SOLID WASTE MANAGEMENT FACILITY PERMIT

Please read all instructions before completing this application

Please TYPE or PRINT cl	clearly
-------------------------	---------

1. TYPE OF APPLICATION (Check All Ap	plicable Boxes):			2. APPLICANT IS THE	l:
Permit to Construct	🗌 Initial (New)	=	newai	I Facility Owner	
Permit to Operate	Subsequent Stage (Ne	ew) 🗌 Mo	dification	X Facility Operator	
3. FACILITY OWNER'S NAME Broome County	•		E	5. ENGINEER'S NAME A Barry J. Chene	
Address P.O. Box 1766				Firm Name Wehran-New Y	ork, Inc.
City Binghamton	City Binghamton		Address 666 East Main St	reet	
State/Zip Code New York 13902	State/Zip Co New York			City/State/Zip Code Middletown, NY 10940	
Telephone Number ( 607 ) 778-2482		778-2482	2482 Telephone Number (914) 343-0660		-0660
6 FACILITY NAME AND LOCATION (Atta Name Colesville Landfil		ing exact location	n)	7. SITE OWNER'S NAME Broome Cou	
Street East Windsor Ro	ad			Address P.O. Box 176	6
City, State, Zip Code				City Binghamtor	
Town Colesville	County Broom	e		State/Zip Code New York 1390	2
Coordinates NYTM-E 770000	NYTM-N 789000	0		Telephone (607) 778-248	2
8. TYPE OF FACILITY (Check all application of the second s	ole boxes) rfund			TION BEING FILED BY OR OF A MUNICIPALITY?	10. FEE AMOUNT ENCLOSED
Research, Development and Demon	stration		🛣 Yes	No If yes, name.	
Land Application	Transfer Stati	lon			
Solid Waste Incineration	🗌 Medical Wast	e	Broom	e County	\$
Refuse Derived Fuel Processing	☐ Waste Tire St	orage	11. NAME(S) O	F ALL MUNICIPALITIES SEP	RVED
	Landfill Gas F	Recovery	Site c	losed	
Recyclables Handling and Recovery	Waste Oil				
Other (Describe)					
12. SOLID WASTE HANDLED		13. PROVIDE T	HE FOLLOWING	INFORMATION WHERE APP	
a. List wastes to be acceptedN	/A		ea proposed in th		<u>31.0</u> acres 31.0
		b. Facility area ultimately planned		acres	
b. Quantity (Specify Units)	NI / A	c. Ultimate f	acility height abo	ve existing ground level	N/A feet
Existing "approved design capacity		d. Total site area <u>11.7.0</u> a			
Proposed "approved design capaci	ty" <u>N/A</u>	e. Existing la	Indfill area on this	s site and adjacent propertie	es <u>31.0</u> acres
14. IS A VARIANCE REQUESTED FROM A	ANY PROVISION OF 6 NY	CRR PART 360?			
Yes 🗌 No If yes, cit	e the specific provision(s)		-2.13(P)(2)(i -2.13(r)(2)(ii		
15. CERTIFICATION: I hereby affirm under penalty of per under my supervision and direction a	nd is true to the best of				
to sign this application pursuant to 6 h pursuant to Section 210.45 of the Penal	NYCRR Part 360. I am awa		statement made	herein is punishable as a	
Date	Sig	nature		Print Na	ame
	REGIONAL	DRA COPY			



\_

# APPENDIX F EMERGENCY CONTACT LISTING

.

# **EMERGENCY RESPONSE AGENCIES AND CONTACTS**

Regulatory Agencies - (Mandatory Within 2 Hours After Spill)

New York State Department of Environmental Conservation

(800) 457-7362

## Oil and Hazardous Materiai Ciean-up Contractors (if required)

IT Corporation, Stratford, CT	(203) 386-0100
Hitchcock, Bridgeport, CT	(203) 334-2161
Clean Harbors, Albany, NY	(518) 434-0149

# Local Agencies (if required)

Broome County Sheriff, Binghamton, NY	(607) 778-1911
New York State Police, Binghamton, NY	(607) 775-1241
Local Police, Harpursville, NY	(607) 772-1010
Fire Department, Harpursville, NY	(607) 772-1010
Lourdes Hospital, Binghamton, NY	(607) 798-5231
Ambulance/Rescue Squad, Harpursville, NY	(607) 772-1010

Broome County (within 24 hours) Deputy for Engineering Services (Mike McElhare, Director)

(607) 778-2482

# APPENDIX G GAS VENTING LAYER EQUIVALENCY

By KPN Date 12/15/92	Wehran EnviroTech	22.02550 ON dol
Chkd. by Date		Sheet No of
Subject	COLESVILLE LANDFILL	

GAS CONFECTION ALTERNATIVE DESILAS

CHECK PROPOSED ALTIERNATIVES FOR REQUINALENCY

with REQUIRED WHITCH LAYER.

I. - REQUIRED ALTERNATIVE, 12" SAND LAYER

I GEOCOMPOSITE LAYER WITH CONNECTION PIPES IN TEENCHES


II 6" SAND LAYER WITH CONFECTION PIPES IN TRENCHES

THE FULLOWING REQUIVEREDUCE CALCULATIONS ARE BOSED UPON THE HUDRAULIC TRANSMISSIVITY OF THE LAYER WHICH HAS BERN SHOWN TO CORRELING LITH GAS TRANSMISSIVITY AND CONPACTSON CAN BE MADEL REGARDLESS OF GRADIENT. TO SAND LAYER

prizmenbility = 1+103 cm/sec

I PASSIVIE VIENT/ ACRIZ

OPERATE WITHOUT CLOGGING



TRANSMISSIVITY Q = KT= 1 10<sup>-3</sup> cm/s<sub>-c</sub> (3048 cm) = ,0305 cm/sec

By FYM	Date (2-13-7	<b>Wehran</b> EnviroTech	Job No. <u>62264.C5</u> Sheet No. 2 of 3
Subject			

DETERMINE FLOW, RATTES FOR ALTERINATIVITS

I . II FOR KOMPARISON TO PART 360 REQUIRGATIONT

I GEOCOMPOSITE LAYER WITH TRANCHED CONNECTION PIPES

(REFRIZ TO SCRITCH ON PRECERDING PAGE FOR UNIT AREA) (=0.04 (SLL PRECEDUC PAGE)

(SILA ATTACHED GENPH)

\* GRADIRNI OF L . 02 USED AS & CONSERVATIVE DASIGN

APPRONTCH, AS Shown ON THE ATTACHED GRAPH LOWAR GRADIENTS VIELDS LOWER TRANSMISSIVITY

QGEOCOMPOSITE 20 cm²/SEL = 655.74 QSAND -12" .0305 cm²/SEL = 655.74

TTE 6" SAND LAYER WITH TRENCHED COLLECTION PIPES

(REFER TO SKETIH ON PRECERDING PAGE FOR UNIT AREA)

t= 6" = 15.24


K= 2+10-3 cm/SEC

 $Q = KT = 2 - 10^{-3} \text{ cm/}_{0.22} + 15.24 \text{ cm}$ 

Q= .0305 w1/52c

Q SAND 12" ,0305 CAPSEL = /





ML

# APPENDIX H VLDPE CHEMICAL RESISTANCE

### MDPE/VLDPE MATERIALS DEVELOPMENT

A. NICHOLAS, J.I. APSE, W.A. HOFFMAN, W.M. SONG Union Carbide Chemicals and Plastics Company Inc. 1 Riverview Drive Somerset, New Jersey 08875

#### ABSTRACT

Medium density polyethylenes (MDPE) and very low density polyolefins (VLDPE) are becoming the materials of choice in a wide range of geomembrane applications. Excellent inherent properties in chemical resistance and mechanical strength make MDPE the preferred material for demanding chemical environments. VLDPE's unique combination of toughness and flexibility enables the design of systems that can provide outstanding durability even under extreme climatic conditions. This paper describes key material properties of MDPEs and VLDPEs and discusses their influence on field performance.

## INTRODUCTION

Over the last ten years, the use of geomembranes has experienced rapid growth in waste containment applications. Synthetic, flexible membrane lining systems are increasingly proving to be one of the most cost effective and environmentally sound options for efficient waste management and for the conservation of natural resources. In 1990, approximately 500MM ft<sup>2</sup> of geomembranes are projected to be installed, a 66% increase over 1987 [1, 2].

In parallel with this growth, the industry has aggressively pursued the development of products and services to meet current and emerging performance requirements. With the emphasis on durability and with the leadership of the EPA, industry members are individually and collectively working to advance the state of technol and ensure system integrity throughout the designed life an installation. An integral part of this effort is the development of analytical and testing tools that will enable the industry to more quantitatively predict field performance. This technology will play a key role in continually improving our products and services as well as addressing public concerns for long-term environmental protection.

The wide acceptance of MDPE, and more recently of VLDPE, in geomembrane applications is largely the result of their outstanding inherent properties. Understanding the properties and their effects on field performance enables designers and installers to select and utilize materials that best fulfill the requirements of the application. The paper discusses MDPEs and VLDPEs relative to key material properties and their influence on field performance.

## MEDIUM DENSITY POLYETHYLENES (MDPE)

The initial MDPE product technology for geomembranes was derived from the pipe industry where these materials have been successfully utilized for over 30 years. More recently, the technology and field experience accumulated in pipe is providing the geomembrane industry with the foundation to better quantify the durability of geomembra f installations. At the same time, the unique requirements of geomembrane applications are becoming increasingly evident and are resulting in the development of advanced resins a compounds specifically tailored for geomembranes.

MDPE geomembranes, which are erroneously being called HDPE geomembranes, are based on medium density polyethylene with densities up to 0.940 g/cc. Most commercial grades range from 0.936 to 0.939 g/cc. These resins are manufactured by a number of different processes utilizing various catalysts, comonomers and operating conditions. Although all MDPEs have similar, linear molecular structures, their properties can vary significantly depending on the specific combination of the above manufacturing variables. Overall, MDPEs offer high mechanical strength with excellent environmental resistance. Formulated with the appropriate type, concentration and dispersion of carbon black, MDPEs also provide superior resistance to ultraviolet (UV) light.

However, MDPE's key inherent advantage is its outstanding resistance to a broad range of chemicals. The absence of polar functional groups, in conjunction with about 60% crystallinity, results in very low permeability to water and to aqueous solutions of acids, bases and salts, as well as most organic chemicals. Although some chemical compounds, such as aromatics and halocarbons, can swell the polymer structure and increase permeability, the MDPE polymer chains themselves are not degraded [3].

<u>.</u>

The stress crack resistance of MDPE and its potential influence on the durability of an installation is one of the technology areas receiving increased attention. Several accelerated tests designed to project field performance (e.g. pipe hydrostatic burst test, compressed ring test, etc.) have been developed and are widely used in the pipe industry. In geomembranes, the Constant Tensile Load (CTL) test appears to be the leading candidate. Programs are underway at GRI, ASTM (D35), UCC&P and other industry members to define test procedures and conditions. This is a much needed tool for assessing long-term product performance as well as setting improved standards for new product development.

The stress crack resistance of polyethylenes is a strong function of density. It is also dependent on a number of other variables controlled by the manufacturing process. These include molecular weight, molecular weight distribution, branching distribution and comonomer type and concentration. Collectively, these variables can substantially affect stress crack resistance even at constant density. Figure 1 presents the relative performance of different MDPEs under CTL conditions.




Figure 1. Relative Crack Propagation for Different MDPEs

The test measures the crack propagation time required for a notched specimen to fail in a brittle mode at elevated temperatures (usually 50°C) and sub-yield stresses (30 to 80%). The test results show that for seemingly similar resins (equivalent densities), the crack propagation resistance can vary significantly by an order of magnitude or higher. Similar results have been previously reported with both MDPE and HDPE [4]. Therefore, selecting a resin by convenient index properties (e.g. density, MI, etc.) alone, will likely be insufficient for assessing stress crack performance under sustained, low stress levels. CTL is one of the preferred, available tools for evaluating the effect of these low field stresses. Inclusion of such data in the material selection process will further enhance the industry's excellent field experience with MDPE.

## VERY LOW DENSITY POLYOLEFINS (VLDPE)

VLDPE is the most recent olefinic entry into the geomembranes market where it is experiencing wide acceptance in a variety of applications including canals, leach pads, tunnel linings and landfill caps. It represents a new class of ethylene copolymers that have bridged the gap between the tough polyethylenes and the flexible rubbers (Figure 2).




Figure 2. Olefin Polymers

VLDPE is manufactured in a process similar to that used for MDPE and, as with MDPE, has a linear molecular structure and short chain branching. Through comonomer incorporation, the branching frequency is increased while density and crystallinity are substantially decreased. VLDPE densities range from 0.880 to 0.915 g/cc and crystallinities from about 10 to 30 %.

It is the combined effect of the non-polar, linear molecule, the low crystallinity and the higher alpha olefin comonomer(s) that results in VLDPE's unique balance of properties in toughness, chemical resistance, low temperature flexibility, elongational behavior, stress crack resistance and mechanical strength. Figure 3 illustrates the strength-density envelope for FLEXOMER<sup>TM</sup> gas phase VLDPEs. The high tensile strengths attained are equivalent to or higher than those of existing materials, such as CPE, CSPE and PVC, and competitive with MDPE. This enables the designer to utilize the performance advantages of VLDPEs without compromising mechanical strength.




Figure 3. Strength-Density Envelope for FLEXOMER<sup>TM</sup> VLDPEs

During and after installation, many geomembrane systems are exposed to extreme environmental conditions that could limit the utility and performance of a material. Figure 4 presents the dynamic elastic modulus of three commercial

-244-

grade polymers, VLDPE, PVC and MDPE, as a function of temperature.




Figure 4. VLDPE/MDPE/PVC Dynamic Elastic Modulus (DMA)

With PVC, the data show that stiffness will change dramatically as ambient temperatures change from cold to hot. As temperature approaches 0°C (32°F), PVC rapidly becomes stiffer and more brittle due to its high glass transition temperature. At high temperatures, conversely, the high plasticizer content substantially reduces PVC's modulus and results in low dimensional rigidity. With VLDPE, however, modulus changes are small and gradual. VLDPE's low glass transition temperature, low crystallinity and absence of plasticizer result in a product that is more flexible at low temperatures and has higher dimensional rigidity at high temperatures. Relative to MDPE, VLDPE at -20°C is still more flexible than MDPE at 25°C. Consequently, VLDPE geomembranes can be readily installed throughout the year under extreme climatic conditions and without the risk of failures due to brittleness.

For applications where subsidence of underlying

-245-

material(s) is possible [e.g. landfill caps) the deformation characteristics of the polymer are essential. Figure 5 presents the uniaxial elongation of commercial VLDPE, PVC and HDPE as a function of temperature.




Figure 5. WLDPE/MDPE/PVC Elongation vs Temperature

At ambient conditions all three materials have sufficient elongation to sustain substantial subsidence. At  $-18^{\circ}C$ (0°F), however, the elongation of VLDPE remains essentially the same while that of PVC is reduced by more than 75%. Although the field deformation process will likely be three-dimensional, the data illustrate VLDPE's outstanding elongational performance at temperatures frequently encountered in geomembrane installations.

The stress crack resistance of VLDPE has also been evaluated with excellent results. In the constant strain, bent strip ESCR test: (ASTM D 1693), no stress cracking of VLDPE has occurred. Likewise, in ongoing CTL tests, the crack propagation resistance of VLDPE is already several times higher than of the best commercial MDPEs. It appears that, largely due to the low crystallinity and high branching frequency, the stress crack resistance of VLDPEs is outstanding. Work in this area is continuing. Nonetheless, our data strongly suggest that VLDPEs will enable the designer to engineer systems that have superior long-term resistance to cracking.

As with all polyolefins, VLDPE can be formulated to provide UV resistance. Partly due to the higher branching frequency, however, VLDPE has different stabilization requirements than MDPE. Stabilization systems to further enhance VLDPE's UV performance have been identified and long-term verification testing is in progress. In the interim, VLDPEs are recommended for geomembranes that have limited exposure to sunlight.

Finally, VLDPE shares the same alkane chemistry (inert, non-polar) and structure (linear) that gives MDPE its outstanding chemical resistance. It is nearly impermeable to water and to aqueous solutions of inorganics, though, due to its lower crystallinity, VLDPE shows higher swell and permeability to organics. Relative to PVC, VLDPE offers improved overall resistance to a wide range of chemicals (Table 1). Material selection for a given application, however, should be based on direct evaluations with the involved chemical solution, as recommended by the EPA.

# Table 1Chemical Exposure Data

Methane (cc-mil/m <sup>2</sup> -24hrs-atm)	<u>PERMEABILITY (ASTM</u> <u>VLDPE</u> 23	<u> </u>
$H_20$ (MVT) (g-mil/m <sup>2</sup> -24hrs-atm)	16	50

	VLDPE	PVC
Methyl Ethyl Ketone	+3.2	dissolved
Motor Oll	+4.3	-8.2
10% NaOH (aq.)	-0.2	-0.3
Gasoline	+41.4	-27.1
95% H₂SO₄ (aq.)	-0.1	+2.5

~ / -

% Weight Change (ASTM D 543)

## CONCLUSIONS

The broad chemical resistance of MDPE, coupled with its high mechanical strength and weathering resistance, makes it a material that provides excellent field performance.

The stress crack resistance of seemingly "equivalent" MDPEs can vary significantly. Thus, material selection should not rely on index properties alone.

Accelerated tests, such as the CTL, should be developed and implemented to more quantitatively predict the long-term performance of geomembranes and help direct new product development.

VLDPE represents a new class of high performance materials that are both tough and flexible. VLDPE's outstanding low temperature properties, stress crack resistance and elongational characteristics facilitate geomembrane installation and substantially improve system durability.

### ACKNOWLEDGMENTS

Special thanks to Mr. L.C. Rundlof for his valuable input and support.

~ . ~

#### REFERENCES

- 1. Koerner, R.M., <u>Designing With Geosynthetics</u>, Prentice-Hall, New Jersey, 1986, pp. 20.
- Koerner, R.M., Geosynthetics in Waste Containment Systems. North American Geosynthetics Society, Philadelphia, April 1990.
- Apse, J.I., Polyethylene Resins for Geomembrane Applications. In <u>Durability and Aging of Geosynthetics</u>, ed. R.M. Koerner, Elsevier Applied Science Publishers, London, 1989, pp. 159-176.
- Peggs, I.D., Carlson, D.S. and Peggs, S.J., Understanding and Preventing Shattering Failures of Polyethylene Geomembranes, <u>In 4th International Conference on</u> <u>Geotexiles, Geomembranes and Related Products</u>, ed. G.D. Hoedt, A.A. Balkema, Rotterdam, May 1990.

# THE DURABILITY OF POLYETHYLENE, IN PARTICULAR VERY LOW DENSITY POLYETHYLENE (VLDPE)

Polyethylene has become the material of choice for applications requiring durability. This is because of its appropriate blend of chemical resistance, ultraviolet light resistance, biological resistance, and stress crack resistance. As such it has become the material of choice for undersea telephone cables, gas transmission pipelines, agriculture and household chemical sales, modern automotive gasoline tanks, low level radioactive waste disposal drums, and hazardous waste containment.

#### Chemical Resistance

Polyethylene is naturally inert to a wide range of different chemicals, including acids, bases, heavy metals, hydrocarbons, inorganic salts, detergents, natural fats and oils, chlorinated hydrocarbons, and others. Its chemical resistance is proven by a large amount of testing in many different industries. Therefore, its use in many different chemical containment applications is unmatched.

## Biological Resistance

Many liners contain plasticizers and other soluble constituents which impart flexibility and processability to the material. Oils or plasticizers are extractable materials which tend to leach out, causing stiffening and brittleness of the membrane. This extraction process occurs in the presence of common household solvents and even in normal soil. The embrittled material can then result in cracking of the liner.

Plasticized liners are known to be eaten or gnawed through by rodents in addition to being able to support fungus and microorganism growth. Microorganisms can also cause embrittling of the liner as they feed on the plasticizers. Polyethylene is inherently flexible and, therefore, contains no plasticizer additives. It consequently will not lose its flexibility due to extraction of the additives over time. The fact that it has no plasticizers and is made of polyethylene means that VLDPE tends to be resistant to rodents and does not support microorganisms. Rodents have been shown to avoid polyethylene membranes positioned so as to directly obstruct their burrowing.

#### Stress Crack Resistance

Modern polyethylene resins have excellent resistance to stress cracking. VLDPE is extremely ductile and is therefore not susceptible to brittle failures such as environmental stress cracking.

**T-085** 

# CHEMICAL RESISTANCE OF VLDPE

# <u>REAGENT</u>

VLDPE

Acetaldehyde
Acetic acid, 1-80%
Acetic acid, 80-100%
Acetic acid, glacial
Acetic anhydride
Acetone
Acetphenetidine
Acetophenone
Acrylic emulsions
Allyl alcohol
Allyl chloride
Aluminum bromide, sat. sol.
Aluminum chloride, dil. sol.
Aluminum chloride, conc. sol.
Aluminum fluoride, conc. sol.
Aluminum hydroxide
Aluminum sulfate, concl. sol.
Alums (all types) conc. sol.
Ammonia, 100% dry gas
Ammonium carbonate
Ammonium chloride, sat. sol.
Ammonium fluoride, 20%
Ammonium hydroxide
Ammonium metanhosnbate sat sol
Ammonium metaphosphate, sat. sol.
Ammonium nitrate, sat. sol.
Ammonium oxalate
Ammonium parsulfate, sat. sol.
Ammonium phosphate, 75%
Ammonium sulfate, sat. sol.
Ammonium sulfide, sat. sol.
Ammonium thiocyanate, sat. sol.
Amyl acetate, 100%
Amyl alcohol, 100%
Amyl chloride, 100%
Aniline, 100%
Antimony chloride
Apple juice
Aqua regia
Argyrol
Arsenic acid, 100%
Aspirin
Atabrine
Automotive oil
Barium carbonate, sat. sol.
Barium chloride, sat. sol.
Barium hydroxide
Barium sulfate, sat. sol.
Barium sulfide, sat. sol.

## REAGENT

£ ::

S U

U

S

S

U

s s

S

S

S U

S

S

U

U

U S

S

U

S

U

U U

S

S

s S

S S

S

S

U

S

S S

U

S

U S

S

US

U U

U U U

U

U

S S

Beer Benzaldehyde Benzene Benzene sulfonic acid Benzoic acid Benzyl alcohol Bismuth carbonate, sat. sol. Bleach lye Black liquor Borax, cold, sat. sol. Boric acid, sol. Brake fluid Brandy Bromic acid, 10% Bromine, liq. Bromine water Bromobenzene Butanedoil, 1-100% Butter Butyl acetate Butyl alcohol, 100% n-Butylamine Butyraldehyde Bulyfic acid Calcium bisulfide Calcium carbonate, sat. sol. Calcium chlorate, sat. sol. Calcium chloride, sat. søl. Calcium hydroxide Calcium hypochlorite, bleach sol. Calcium nitrate, 50% Calcium sulfate Camphor oil Carbon dioxide, 100% dry Carbon dioxide, 100% wet Carbon dioxide, cold, sat. sol. Carbon disulfide Carbon monoxide Carbon tetrachloride Carbonic acid Castor oil, conc. Cetane Cheese Chloracetic acid Chlorine, 100% dry gas Chlorine, moist gas Chlorine, liq. Chlorobenzene Chloroform Chlorosulfonic acid, 100%

Chocolate syrup

Chrome alum. sat.

#### REAGENT

S

D

Chromic acid, 1-50% Chromic acid + sulfuric acid (cleaning solution) Cider Citric acid, sat. sol. Clove oil Coconut oil alcohols Cola concentrates Copper chloride, sat. sol. Copper cyanide, sat. sol. Copper fluoride, 2% Copper nitrate, sat. sol. Copper sulfate, dil. sol. Corn seed oil Cottonseed oil Cresol Cresylic acids, 50% Cuprous chloride, sat. sol. Cyclohexane Cyclohexanol Cyclohexanone Cyclohexylamine

Decahydronaphthalene n-Decane Decyl alcohol Detergents, synthetic Developers, photographic Dextrin, sat. sol. Dextrose, sat. sol. Diazo salts Di-n-butylamine Di-n-butylether Dibutyl phthalate Dichloroethylene Diethylene glycol Diethyl uther Dighycolic acid Dihydronaphthalene Disobutylene Disopropyl ketone Dimethylamine Dipermine Disinfectant (pine) Disinfectant eucalyptus Disodium phosphate

S S S S S S S S S S S S U υ S U D U U U U U S S S

> S S U U D U S U S U U U U U U υ S

VLDPE

Eggs Ethyl acetate Ethyl alcohol, 35% Ethyl alcohol, 100% Ethyl aniline Ethyl butyrate Ethyl butyrate Ethyl chloride Ethylene Ethylene Ethylene dichloride Ethylene glycol	SUSSUUUU- DUS
Fabric conditioner Ferric chloride, sat. sol. Ferric nitrate, sat. sol. Ferric sulfate Ferrous chloride, sat. sol. Ferrus sulfate Fish solubles Fluoboric acid Fluorine Fluosilicic acid, 32% Fluosilicic acid, conc. Formaldehyde, 40% Formanide Formic acid, 0-20% Formic acid, 20-50% Formic acid, 100% Frutcose, sat. sol. Fruit pulp Fuel oil Furfural Furfuryl alcohol	\$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$
Gallic acid, sat. sol. Gasoline Gin Glucose Glycerine Glycol Glycolic acid, 30% Grape juice Grape syrup	S D D S S S S S S S S S S
Hair shampoo Hand creams Heptane Hexachlorophene tart-Hexanol	S S U S S

S

S

S

S

S

S

S

S

S

S

S

s s

D

S

s s

S

S

U

U

S

D

s s

D

U

U S

S

U S

U U

s s

s s

S

U

S

S

S

S

Honey Hydrazine hydrate Hydrobromic acid, 50% Hydrochloric acid, 10% Hydrochloric acid, 35% Hydrochloric acid, conc. Hydrochloric acid, sat. sol. Hydrofluoric acid, 40% Hydrofluoric acid, 60% Hydrofluoric acid, 75% Hydrogen, 100% Hydrogen chloride, gas, dry Hydrogen peroxide, 30% Hydrogen peroxide, 90% Hydrogen phosphide, 100% Hydroquinone Hydrogen sulfide, dry gas Hypochlorous acid, conc. Inks Iodine, potassium iodide sol. conc. Iodine tincture Jams and jellies Kerosene Lactic acid, 10-90% Latex Lard Lauryl alcohol Lauryl sulfate Lead acetate, sat. sol. Lemon syrup Linseed oil Liqueur Lube oil Lysol Magnesium carbonate, sat. sol. Magnesium chloride, sat. sol. Magnesium hydroxide, sat. sol. Magnesium nitrate, sat. sol. Magnesium sulfate, sat. sol. Margarine Malsic acid Mercuric chloride, sat. sol. Mercuric cyanide, sat. sol.

Mercurous nitrate, sat. sol.

<u>.</u>...

S

U U

S U

U

U

U

υ

U

υ

U

S

S

U

S

U

U

S

S

S

S

S

S

s s

U

U

U

S

S

U

U

U

U

s

S

S U

S

-U

S

U

U S

S

Mercury Methallyl chloride Methane Methyl alcohol, 100% Methylated spirits Methyl bromide Methyl chloride Methylene chloride Methyl ethyl ketone Methyl formate Methyl Isobutyl ketcne Methyl salicylate Methylsulfuric acid Milk Mineral oils Molasses Naphtha Naphthalene Nickel chloride, sat. sol. Nickel nitrate, conc. sol. Nickel sulfate, sat. sol. Nicotine, dil. sol. Nicotinic acid Nitric acid, 0-30% Nitric acid, 30-50% Nitric acid, 70% Nitric acid, 95-98% Nitric acid, fuming Nitrobenzene Nitroethane Nitromethane Octyl alcohol Octyl cresol Oleic acid Oleum Olive oil Orange extract Orange syrup Oxalic acid, sat. sol. Ozone, 100% Paper mill liquors Peanut oil n-Pentane Perchloric\_acid, 10% Petrol Petroleum ether Phosphoric acid, 30% Phosphoric acid, 90%

S

U

s s

S

S

S

S

U

S

U

S

S

S

S

S

S

S

S

S

S

S

S

S

S

S

S

S

S

S

S

S

S

S

S

S

U

S

S

S

S

S

S

S

υ

S

S

S

Phosphorus, yellow, 100% Phosphorus oxychloride Phosphorus pentoxide Phosphorus trichloride Photographic solutions Pickling baths (H2SO4, HCl) Picric acid Pineapple juice Pine oil Plating solutions (brass, cadmium, copper, gold, indium, lead, nickel, silver tin, zinc) Plating solutions (chromium) Plumbing cleaner Potato chips Potassium bicarbonate, sat. sol. Potassium borate, 1% Potassium bromate, 10% Potassium bromide, sat. sol. Potassium carbonate Potassium chlorate, sat. sol. Potassium chloride, sat. sol. Potassium chromate, 40% Potassium cyanide, sat. sol. Potassium dichromate, 40% Potassium fluoride Potassium hydroxide, dil. sol. Potassium hydroxide, conc. sol. Potassium nitrate, sat. sol. Potassium perborate, sat. sol. Potassium perchlorate, 10% Potassium permanganate, 20% Potassium persulfide, sat. sol. Potassium sulfate, conc. sol. Potassium sulfide, conc. sol. Potassium sulfite, conc. sol. Propargyl alcohol Propyl alcohol Propylene dichloride Propylene glycol Rayon coagulating bath Rum Sea water Selenic acid Shortening Silicic acid Silicone oil Silver nitrate sol. Soap sol., all conc. Sodium acetate, sat. sol.

Sodium benzoate, 35% Sodium bicarbonate, sat. scl. Soidum bisulfate, sat. sol. Sodium bisulfite, sat. sol. Sodium borate Sodium bromide, dil. sol. Sodium carbonate, conc. sol. Sodium carbonate Sodium chlorate, sat. sol. Sodium chloride, sat, sol. Sodium cyanide Sodium dichromate, sat. sol Sodium ferricyanide, sat. sol. Sodium ferrocyanide, sat. sol. Sodium fluoride, sat. sol. Sodium hydroxide, dil. sol. Sodium hydroxide, conc. scl. Sodium Hyperchlorite Sodium hypochlorite, 20% Sodium nitrate Sodium nitrite Sodium sulfate Sodium sulfide, 25% Sodium sulfite, sat, sol. Soy bean oil Stannic chloride, sat. sol. Stannous chloride, sat. spl. Starch solution, sat. sol. Stearic acid, 100% Sugar sol., 50% Sulfur Sulfuric acid, 0-50% Sulfuric acid, 80% Sulfuric acid, 98% Sulfuric acid, fuming Sulfurous acid Sulfur dioxide Sulfur trioxide Sulfuryl chloride Tallow Tannic acid, 10% Tanning extracts, comm. Tartaric acid Tea Tetrachloroethane Tetrachlorethylene Tetrahydrofurane Tetrahydronaphthalene Toluene Tomato sauce Transformer oil Trichlorobenzene

S -S S S S S S S S U U S S S U S S S S S U U U U U S U U

Trichloroethylene	U
Triethanolamine	U
Trisodium phosphate, sat. sol.	S
Turpentine	U
Urea, D-30%	S
Urine	S
Vegetable oil	บ
Vinegar, comm.	ร
Vanilla extract	ร
Water	s
Wax	s
Whiskey	d
Wines	s
Wine vinegar	v
Worchestershire sauce	v
Xylene	U
Yeast	S
Zinc chloride, sat. sol.	s
Zinc fluoride	s
Zinc sulfate, sat. sol.	s

KEY TO RATING:

- S Satisfactory
   D Limited recommendation (many applications possible depending on mil thickness, temperature and package design.
- U Unsatisfactory

# VLDPE plugs a gap in PE's density spectrum

Very low-density polyethylene is coming in as a cost-effective nonpolar replacement for polar resits such as PVC, EVA, and thermoplastic polyurethanes in such applications as film, sheet, and tubing. Going for VLDPE is a combination of flexibility, toughness, high use temperatures, and relative processing ease.

### Stuart J. Kurtz Union Carbide Corporation Bound Brook, New Jersey

y combining flexibility and strength in a linear, nonpolar polymer, very low-density polyethylene (VLDPE) fills the long-existing gap between low-modulus, low-density ethvlene propylene rubber (EPR) and high-modulus, low-density polyethylene (LDPE) (Table 1). VLDPE's linear structure and molecular weight-the key to the resin's low density and physical properties-are achieved through a polymerization process similar to that of linear low-density polyethylene (LLDPE) (see the Bux, page \$9). Through the choice of catalysts, suppliers can alter molecular weight distribution to produce changes in physical properties. VLDPE's nonpolar naturethe result of an exclusively hydrocarbon composition-means resistance to po-

<i>Table 1.</i> Properties of representation nonpolar polyethylene resins.					
Resit	Donsity, grams por cubic contimotor	Secant modalus; 18-pst-			
HDPE LLDPE LDPE VLDPE EPR•	0.94 to 0.97 0.915 to 0.93 0.915 to 0.93 0.900 to 0.906 0.875	80 to 1 <sup>12</sup> 5 30 to 50 20 to 30 11 to 17 0.5 to 1.0			
	ni elongation ropylene rubbeni				
•					

lar solvents (like water) and good tensile property values. Two VLDPE grades are now on the market (more are forthcoming); both have met with excellent results, Already, they are being used in applications ranging from gaskets to soft films, displacing ethylene vinyl acetate copolymers (EVA), PVC, and thermoplastic polyurethanes—polar polymers that have long benefited from the density/modulus void now plugged by VLDPE.

**Materials** 

### Structure and properties

For VLDPE—as with all polymers—the arrangement of molecules into various structures and configurations determines the resin's properties, which in turn affect its processing characteristics and ultimately its end uses.

## Polymerization and molecular weight

The linear structure and lack of longchain branching in both LLDPE and VLDPE arise from their similar polynierization mechanisms. In the low-pressure polymerization of LLDPE, the random incorporation of alpha olefin comonomers produces sufficient shortchain branching to yield densities in the range of 0.915 to 0.930 gram-per cubic gentimeter. The even lower densities of VLDPE resins are achieved by adding short-chain branching than occurs in LLDPE, and thus a lower level of crystallinity) and using proprietary catalysts and reactor technology. No external plasticizers are used in the production of VLDPE. Catalysts are available to produce VLDPE of both narrow molecular weight distribution (MWD = 4) as well as broader molecular weight distribution (MWD = 8). Molecular weight values and trade designations for the resins used in this analysis are given in the *Table* below.

Resins 🔜		Molecular wel	ght values	
Notation	Trade designation	10-* number average	10 <sup>-*</sup> weight average	Distri- bution
LDPE	DYNH-9	0.235	2.12	9.0
LLDPE	GRSN-7047	0.275	1.14	4.1
VLDPE-1	DFDA-1137	0.311	1.37	4.4
VLDFE-2	DFDA-1138	0.187	1.55	8.3

T\_060

Materials

Table 2. Typical molding and extrusion properties of YLDPE grades and other ethylene-based resins.

Structure. VLDPE can be characterized as a linear polymer (vinually no long-chain branching) with a narrow molecular weight distribution. The amount of short-chain branching, because it exceeds that of LLDPE, vields a lower level of crystallinity, giving rise, to densities below 0.915 gram per cubic centimeter-less than that of LLDPE and even LDPE (Table 1). The molecular weight distribution of VLDPE (and of LLDPE)-narrower than that of LDPE (Fig. 1)-combined with its linear structure gives rise to different crystalline structures and different degrees of entanglements than are found in LDPE. The presence of numerous shon-chain branches in VLDPE diminishes the formation of crystalline regions in the backbone of the polymer. Where crystalline regions are formed, they are distorted (made imperfect) by the presence of the branching. The longer chains of LDPE create even greater crystal distortion. At the same level of crystallinity, the crystalline structures of VLDPE and LDPE are sufficiently different so as to yield distinctly different physical properties in the fin-

	Test	Resias m				
Property	method	VLDPE-1.	VLDPE-2	LOPE	LLDPE	EYA.
Density, grams per cubic centimeter	D1505	0.906	0.900	0.920	0.920	0.930
Melt index, grams per 10 minutes	D1238	0.8	0.4	2.0	0.8	2.0
Tensile strength, 10 <sup>9</sup> psi	D638	2.8	2.4	2.0	2.3	2.5
Ultimate elongation, percent	D638	900	800	600	800	800
Secant modulus, 10 <sup>a</sup> psi <sup>a</sup>	D638	17	13	21	30	13
Environmental stress crack resistance after 500 hours, percent failure	D1693	<b>0</b>	0	100=	0	75
Flexural failure, 10° cycles	Note	1.2	4.0	0.01	0.5	0.7
Tensile impact resis- tance, 10 <sup>a</sup> foot- pounds per cubic inch <sup>a</sup>	Note <sup>4</sup>	9	10	4	9	-
Brittleness at -100°C. percent failure	D746	0	0	50°	0	50 1
Melting point. *C	Note	118	116	108	120	<b>96</b> .

<sup>4</sup> Ali resins made by Union Carbide: trade designations and molecular-weight values appear in the Box, page 59 <sup>6</sup> Ethiviene vinyl acetate copolymers of LDPE, with vinyl acetate comonomer content of 10 percent <sup>6</sup> One percent elongation. <sup>6</sup> 20 hour test time.

\* 0.5- by 0.05-inch specimens, flexed 180 degrees, tested at 300 cycles per minute at room temperature. \* Union Carbide test method. \* At room: temperature. \* At =90° C. \* At =90° C. \* At =95° C. \* Determined by differential scanning calonimetry.





Figure 1. The molecular weight distribution of both NLDPE grades is narrower than that of LDPE. Differences in the distribution of the NLDPE resins are largely due to the choice of catalyst used during polymerization NLDE's narrow molecular weight, combined with its linear structure, give rise to different crystalline structures and different degrees of entanglements than are found with LDPE



Floate 2. The fewer imperfections in AUDI E's crystalline structure account for its high melting point and higher use temperature vertethan are frund with EVA copalyment, where still groups assum the resin's crystalling structure and true source its melting point. (2014) 5.5 modulus is in a range not otherwise available to nonpolar polyethylenes.

### Materials


Structure. VLDPE can be characterized as a linear polymer (virtually no long-chain branching) with a narrow molecular weight distribution. The amount of short-chain branching, because it exceeds that of LLDPE, yields a lower level of crystallinity, giving rise. to densities below 0.915 gram per cubic centimeter-less than that of LLDPE and even LDPE (Table 1). The molecular weight distribution of VLDPE (and of LLDPE)-narrower than that of LDPE (Fig. 1)-combined with its linear structure gives rise to different crystalline structures and different degrees of entanglements than are found in LDPE. The presence of numerous short-chain branches in VLDPE diminishes the formation of crystalline regions in the backbone of the polymer. Where crystalline regions are formed, they are distoned (made imperfect) by the presence of the branching. The longer chains of LDPE create even greater crystal distortion. At the same level of crystallinity, the crystalline structures of VLDPE and LDPE are sufficiently different so as to yield distinctly different physical properties in the fin-

ethylene-based resins.						
Property	Test method	Resias m VLDPE-1	VLDPE-2-	LOPE	LLDPE	EYA•
Density, grams per cubic centimeter	D1505	0.906	0.900	0.920	<b>0.92</b> 0	0.930
Melt index, grams per 10 minutes	D1238	0.8	0.4	2.0	0.8	2.0
Tensile sujength, 10 <sup>a</sup> psi	D638	2.8	2.4	2.0	2.3	2.5
Ultimate elongation percent	D638	900	800	600	<b>80</b> 0	800
Secant modulus, 10 psi	D638	17	13	21	30	13
Environmental stress crack resistance after 500 hours, percent failure	D1693	0	0	100*	0	75
Flexural failure, 10 cycles	Note	1.2	4.0	0.01	0.5	0.7
Tensile impact resis- tance, 10° foot- pounds per cubic inche	Note	9	10	4	9	
Brittleness at -100 °C, percent failure	D746	0	0	50°	0	50
Melting point, *C	Note'	118	116	108	120	<del>9</del> 6
All resins nucle by Union Carbid and molecular-weight values appear Ethylene varyl accuse copplyment accuse compnomer content of 10 pt One percent elongation.	of LDPE, with	ne 59 na 3 h vinyi Lir * At	5- by 0.05-inch sp 00 cycles per mir uon Carbide test room temperatu 90° C.	method.	sed 180 deg temperature	rees. writed

Table 2. Typical mojding and extrusion properties of VLDPE grades and other

20-hour sen time.

AL -95°C. Determined by differential scanning calorimetry






Figure 1. The molecular weight distribution of both VLDPE grades as narrower than that of LDPE. Differences in the distribution of the VIDPE resins are largely due to the choice of catalyst used during polymerization VIDE's narrow molecular weight, combined with its linear structure, give rise to different crystalline structures and different degrees of entanglements than are found with LDPE.

Floure 2. The fearer imperfections in N2DPE's crystalline structure account for its high reduing point and higher use temperature range then are found with EVA copulations, a inde side groups assist the resin's crustalling structure and thus lower its melting point MIDPE's modulus is in a range not otherwise available to nonpolar polycibvienes.




Figure 3. The melt shear characteristics of both VLDPE grades fall between those of 1 and 2 melt index LLDPE resins, in the range normally encountered in film extrusion. VLDPE can thus be processed on extrusion equipment designed for LLDPE with only minor modifications of processing parameters. At moderate rates, VLDPE can even be processed on equipment not designed for LLDPE.

Table 3. Typical film properties of VLDPE versus those for competitive materials.

Property	Test Method	Resin <b>ma</b> VLDPE-1•	VLDPE-2	LDPE		EVA
Material properties						
Density, grams per cubic centimeter	D1505	0.906	0.900	0.918	0.918	0.930
Melt index, grams per 10 minutes	D1238	0.8	0.4	2.0	1.0	2.5
Film Properties						
Average gage, mils	_	1.2	1.3	1.2	1.3	1.4
Tensile strength, 10 <sup>s</sup> psi	D882					
Machine direction		4.3	4.6	2.9	4.5	3.3
Transverse direction		4.0	3.5	2.7	4.0	3.5
Elongation, percent	D882					
Machine direction		560	590	300	600	<del>4</del> 70
Transverse direction		8+0	700	500	600	550
Tensile impact resistance. 10 <sup>2</sup> foot-pounds per cubic inch	Note					
Machine direction		11	15	4	9	-
Transverse direction		8	13	6.5	-	_
Dan drop impact resistance, grams	D1-09	350	370	90	100	-
Elmendorf tear strength. grams per mil	D1922					
Machine direction		130	60	260	90	80
Transverse direction		320	3+0	160	340	105
Secant modulus, 10 <sup>9</sup> psi <sup>4</sup>	D\$82					
Machine direction		15	11	19	24	11
Transverse direction		14	13	24.1	29	11
Puncture resistance, inch- pounds per mil	Note	16	16	8	10	_

All resins made by Union Carbide, unde designations and molecular weight values appear in the Bux, page 55 Ethylene sinyl acetate coposymers of LDPE, with sinyl acetate comonomer content of 10 percent.

Biowup ratio 2 to 1 Union Carbide test method

\* One-nercent elongation

ر در از ۲۰ مدین ۲۵٬۵۰ میکی کردی کاری کاری میشوند میکویند کاری از ۲۰ میلید. میکور از مراجع از مراجع از مراجع

ished products (as seen in the processing and film properties listed in *Tables* 2 and 3).

Differences in the degree of crystallinuv, in crystal size, and the number and kinds of imperfections affect the melting point of the polymer. The fewer significant imperfections in the crystalline structure of the short-chain branched VLDPE compared to that of the long-chain branched LDPE, for insuance, result in the former's higher melling point" (Fig. 2). The considerably higher melting point of VLDPE compared to that of EVA copolymers (whose side groups also distort the crystalline structure) translates into higher use temperatures for products made from VLDPE resins.

Modulus Structure (and density) also affect modulus, as shown in Fig. 2, where secani modulus as a function of density is plotted for a resin with shortchain branches (VLDPE), a resin with long chain branches (LDPE), and EVA (copolymers of LDPE with a vinyl acetate comonomer content of 4 to 18 percent). The modulus versus density curve for VLDPE is in a range not previously available with a nonpolar polyethylene material.

Reeology: As with other narrow molecular weight distribution polymers, VLDPE tends to resist shear and exhibit a higher viscosity than the broad molecular weight distribution, long-chain branched resins it seeks to replace, but the melt is free of their strong strainhardening behavior (resistance to stretching). The melt shear characteristics of 1 melt index, narrow molecular weight distribution VLDPE-1 and 0.4 melt index, broader molecular weight distribution VLDPE-2, for instance, fall between those of 1 and 2 melt index LLDPE resins (Fig. 3) in the shear rate range normally encountered in film extrusion. Figure 3 also indicates that, since VLDPE's rheological profile falls within LLDPE's range. VLDPE can be accommodated in LLDPE extrusion equipment. At moderate rates, VLDPE resins can even be processed on extrusion equipment not designed for LLDPE resins.

VLDPE resins exhibit higher extensional viscosity than LLDPE resins (*Fig.* 4), which roughly translates into higher melt tension and better blown-film fabrication stability. Still, since VLDPE melt does not strain-harden in the melt, blown-film processing technology appropriate for LLDPE works well with VLDPE.

Other properties. Being nonpolar. VLDPE polymers are tougher and more

\* As determined by differential scanning calorimetry

PLBSTICS /Santember '85

### Materials

chemically resistant than their polar competitors like PVC, EVA, and ethylene ethyl acrylate. As for optical properties, gloss increases and haze decreases with narrowing molecular weight distribution; contact claritygood regardless of molecular weight distribution-improves further with decreasing density. VLDPE either equals or exceeds LLDPE, LDPE, and EVA in low-temperature performance, environmental stress crack resistance. flexural life, and tensile strength. (Molding and extrusion properties for VLDPE and related materials are given in Table 2: Table 3 compares film properties of VLDPE to those of various competitive resins.)

### **Processing parameters**

With marked rheological similarity to LLDPE, it's no surprise that VLDPE can be processed in most machines being used for other polyethylenes (extruders, small-part injection-molding machines), and blowmolding machines). Film extrusion characteristics for VLDPE are similar to those for 2 melt index LLDPE or 0.5 melt index LDPE. Melt temperatures of 205 to 235°C have been found to yield the most optimal properties.

VLDPE's pumping efficiency is very good. Output per screw revolution is in fact greater than for LDPE, although screw torque is higher (but still generally within the operating range of most commercial equipment). For an LLDPEcompatible screw, the barrel temperature profile when extruding VLDPE should begin with a 175°C feed zone, increasing to 210°C at the screw tip. The transfer line and die should be roughly 215°C.

For blown-film processing, low-pressure-drop dies with die gaps of 0.035 to 0.040 inch are preferred. Blowup ratios of 2 to 1 or greater yield optimal properties. Dual-lip air rings yield up to 0.54 kilogram per hour-centimeter more output, the result of better bubble stability. The use of stabilizer bars and cages also contributes to higher blown-film processing rates.

• For large-part extrusion-blowmolding and for tubing extrusion, a melt temperature of 235 to 250°C is preferred; for injection molding and injection-blowmolding. a minimum stock temperature of 275°C is suggested. Owing to its low crystallinity. VLDPE mold




Figure 4. The higher extensional viscosity of VLDPE resins compared to that of LLDPE translates into higher melt tension and better blown film fabrication stability. Since VLDPE does not strain-burden in the melt, blown film processing technology appropriate for LLDPE works well with VLDPE.

shrinkage is about one-half that of 0.92density. LLDPE or LDPE. Changes in mold design and size may thus be necessary. Longer molding cycles are also needed to obtain sufficient shrinkage for ejection of the VLDPE part from the mold.

### Applications and pricing

In many cases, significant cost saving can be obtained by using VLDPE. At 62 cents per pound (hopper car price), VLDPE is a strong candidate to replace or is competitive with thermoplastic polyunethanes (roughly \$1 per pound), EVA (anywhere from 45 to 75 cents per pound), and other resins in such applications as squeeze tubes and bottles, liners for drums, boxes, and cartons, caps, cap liners, and closures, and sheet and profile. VLDPE is also replacing medical-grade FVC (roughly 80 cents per pound) in flexible tubing and other applications in which PVC tends to embrittle with time. VLDPE also yields more volume per pound than the much denser PVC, an additional bonus. VLDPE is replacing other polyethylenes (as well as PVC) in a wide range of shrink and streigh wraps and in wire and cable applications. Other uses include monofilaments, toys, gaskets, and pond liners; other applications are under study

VLIDPE-1 and VLDPE-2 are the two

fully commercialized grades of the resins. In the sample stage are two more VLDPEs: one with an even lower density (0.890 gram per cubic centimeter) is expected to carry a premium price; the other is of even higher melt index than VLDPE-1 and has a density of 0.900 gram per cubic centimeter. Also forthcoming are coextruded film and blend combinations that will synergistically produce properties better than either of the component resins exhibit alone. Blends of VLDPE with either polypropylene. HDPE, or LLDPE hold the greatest promise.

### Seminar Information

Now is the time to review your goals and plan your continuing education with SPE seminars. Whether you are a novice interested in entry-level training or an experienced practitioner looking to expand your know-how, SPE seminars can satisfy your needs. Topics covered include: applications. management, materials, processing, and theory and technology. For more information contact Vincent McElhone (Programs Department) at (203) 775-0471 or (212) 931-1230.

> PLESTICS Engineering/September '85

# TABLE 4.5 GENERAL CHEMICAL RESISTANCE GUIDELINES OF COMMONLY USED GEOMEMBRANES<sup>4</sup>

Geomembrane type

	Butyl rubber		Chlorinated polyethylene (CPE)	nated ylene E)	sulfonated polyethylene (CSPE)	nated nylene PE)	Elasticized polyolefin		Epichlorohydrin rubber	ohydrin xer	diene monomer (EPDM)		Polychloroprene (neoprene)	rene)	polyethylene	ylene	Polyvin chlorid (PVC)	Polyvinyl chloride (PVC)
Chemical 1	100°F 1	158°F	100°F	158°F	100°F	158°F	100°F	158°F	100°F	158°F	100°F	158°F	100°F	158°F 100°F	100°F	158°F 100°F	100°F	158°F
General:																		
Aliphatic hydrocarbons			×	×			×		×	×			×	×	×	×		
Aromatic														:		:		
hydrocarbons							×	•	×	×			×	×	×	×		
Chlorinated																		
solvents	×	×					×		×	×	×		×		×	×		
Oxygenated																		
solvents	×	×					×		×		×	×	×	×	×	×		
Crude petroleum																		
solvents			×	×			×		×	×			×	×	×	×		
Alcohols	×	×	×	×			×		×	×	×	×	×	×	×	×	×	×
Acids:																		
Organic	×	×	×	×	×		×		×		×	×	×	×	×	×	×	×
Inorganic	×	×	×	×	×		×		×		×	×	×	×	×	×	×	×
Bases:																		
Organic	×	×	×	×	×		×		×	×	×	×	×	×	×	×	×	×
Inorganic	×	×	×	×	×		×		×	×	×	×	×	×	×	×	×	×
Heavy metals	×	×	×	×	×		×	×	×	×	×	×	×	×	×	×	×	×
Salts	×	×	×	×	×		×	×	×	×	×	×	×	×	×	×	×	×

SOURCE! DESIGNING WITH GEOSYMMETICS

「たきたます

# Solid Waste

# Chemical compatibility testing of geomembranes and piping materials exposed to landfill leachate

### Bruce E. Dudzik, Daniel E. Oman, and Keith A. Bowden

Will leachate from a land fill chemically degrade geomembranes and piping?

In the pulp and paper industry, landfills have been used to dispose of mill wastes for many years. In the past, the disposal areas may not have been engineered facilities. Current regulations not only require that laudfills be engineered, but usually they specify the use of composite liners of clay and geomembrane (plastic).

The New York State Department, of Environmental Control has regulatory authority for the design, construction, and operation of industrial solic-waste facilities as detailed in Title 6 of Part 360 of the New York Compilation of Rules and Regulations (1). Among other items Part 360 now requires the following:

- Municipal solid-waste facilities must have μ doublecomposite liner, with each liner having a minimum of a 60-mil geomembrane in combination with ε, primary liner of 45.7 cm (18 in.) or a secondary liner of 61.0 cm (24 in.) of compacted, low-permeability soils.
- All industrial landfills must have at least one composite liner and a leachate collection system to transport leachate out of the landfill cell and minimize the quantity of liquid allowed to collect on the landfill liner.
- Documentation must be submitted to demonstrate that the geomembrane and leachate collection pipe are chemically compatible with the leachate expected to be generated in the landfill.

The following three tests are commonly performed on geomembranes and piping used in land ill liner applications:

- Conformance testing demonstrates that the geomembrane liner meets the specifications of the solid waste facility.
- Chemical compatibility testing determines whether the

Parameter		Concen tration
Alkalinity, mg/L as CaC	.O <sub>2</sub>	5. 2500
COD, mg/L	-3	3900
Chloride, mg/L		46
Conductivity, µmhos/cr	n at 25°C	4700
Total hardness, mg/L a		2300
Dil and grease, mg/L		45
Solids, mg/L	- 11. A. 18	
Total dissolved		2500
Total suspended		830
Sulfate, mg/L	그렇게 가지 가지 않는	£ 1 50 x 50
OC, mg/L		1200
30D <sub>5</sub> , mg/L	5.15	₹ <u>5</u> 660
H 🥪		7.3
Calcium, mg/L		3 610
ron, mg/L		110
lagnesium, mg/L		73
langanese, mg/L	and the second second	- <b>C</b> 20
Potassium, mg/L		190
Sodium, mg/L		47
Acetone, µg/L	•	1300
2-butanone, µg/L		2600
foluene, µg/L		1200
henol, μg/L		180
2-methylphenol, μg/L		560
4-methylphenol, μg/L		

geomembrane is compatible with the leachate expected to be generated.

• Quality assurance/quality control testing (QA/QC) assures that the installation of the liner meets all specifications and regulatory requirements.

Dudzik is senior project engineer and Oman is vicepresident/program manager, RMT, Inc., 744 Heartland Trail, P.O. Box 8923, Madison, Wis. 53708-8923. Bowden is manager, safety and environmental, Champion International Corp., Anderson Ave., Deferiet, N.Y. 13628.

II. Tests performed on HDPE geomembranes

.

Test	Test method	Comments
Carbon black content	ASTM D1603	
Carbon black dispersion	ASTM D3015	Appendix A1
Crystallinity (DSC)	ASTM E793	20°C/min scan rate
Dimensional changes	Method 9090	Section 7.6
Extractables	ASTM D4321	•••
Gauge thickness	ASTM D374	Method C
Hardness	ASTM D2240	Shore Durometer Type D
Infrared spectroscopy	KBr pellet sampling method	Thin-layer microtome of sample, 12-min scan rate
Mass (water absorption)	Method 9090	Section 7.6
Melt index	ASTM D1238	Condition E
Modulus of elasticity	ASTM D638	Type IV specimen and 2 in./min extension rate
Mullen burst	ASTM D3787	
Oxidative induction temperature (OIT)		Using a Perkin-Elmer DSC-4, 20°C/min scan rate, 30-psi air atmosphere
Puncture resistance	FTMS 101C	Method 2065
Seam peel strength	ASTM D413	•••
Seam shear strength	ASTM D882	
Specific gravity	ASTM D792	•••
Tear resistance	ASTM D1004	•••
Tensile properties	ASTM D638	Type IV specimen and 2 in./min extension rate
Thermal gravimetric analysis (TGA)	Method in Earnest (6)	40°C/min scan rate and a 30-psi nitrogen atmosphere
ASTM = American Society for Testing and Materials.		
FMTS = Federal Test Method Standard.		
		5 

111.	Tests	for	PVC	piping	samples

Test	Test method	Comments
Dimensions and mass	Method 9090	Section 7.6
Infrared spectroscopy	KBr pellet sampling method	Thin-layer microtome of sample, 12-min scan rate
Oxidative induction temperature (OIT)		Using a Perkin-Elmer DSC-4, 20°C/min scan rate, 30-psi air atmosphere
Pipe joint strength	NSF No. 54	Appendix A, modified version of ASTM D4437. Transverse dogbone specimens of joint are tested using ASTM D638 with a crosshead speed of 2 in./min
Stiffness	ASTM D2412	•••
Thermal gravimetric anlaysis (TGA)	Method in Earnest (6)	40°C/min scan rate and a 30-psi nitrogen atmosphere
Thickness	ASTM D374C	

### Material selection

The three geomembranes tested in this program were manufactured from polyethylene, a semicrystalline polymer that has been used in geomembranes for approximately 30 years because of its excellent chemical resistance.

Originally, we considered only high-density polyethylene (HDPE) as the material for the piping in a leachate collection system. Because HDPE geomembranes are similar in material composition to HDPE piping, no compatibility testing of HDPE piping was performed.

A cost evaluation indicated, however, that the use of polyvinyl chloride (PVC) pipe could substantially reduce the installation cost of the leachate collection system. Since pure PVC is a rigid, amorphous (no crystalline structure) plastic with chemical resistance properties that are better than average, it was considered suitable for use at a piping material and was added to the compatibility testing program. Because the quantity of leachate was limited, only one manufacturer's product could be tested.

The compatibility testing of the geomembranes and piping was conducted using leachate obtained from the existing solid-waste disposal facility at Deferiet Mill. This facility is approximately 12 miles from the new facility constructed in the Town of LeRay, New York.

Approximately 375 L of leachate was collected and shipped to the testing laboratory. The program of detailed inorganic and organic testing conducted on the leachate encompassed the entire priority pollutant list.

Detailed leachate characterization data are presented in **Table I**. These characterization data compared well with previous leachate testing at the Deferiet Mill (2) and with studies of the New York paper industry (3).

### Compatibility testing procedures

The objective of chemical compatibility testing is to simulate in the laboratory the exposure to leachate that geomembranes would reasonably be expected to experience during the operation of a landfill and after it is closed. Therefore, compatibility testing requires a reproducible method for exposing geomembrane specimens to leachate and a way to assess the long-term effects of that exposure.

Both of these requirements have been met in an EPA test method commonly referred to as Method 9090 (4), published in 1986. Method 9090 first defines a procedure for conducting the immersion of geomembrane samples in representative leachate. Second, to assess the long-term use of the geomembranes, Method 9090 specifies that the testing be conducted at normal ambient temperature (23°C) and at 50°C. The testing temperature of 50°C was chosen to simulate 20 years of leachate exposure under average conditions. Third, Method 9090 defines the tests to assess geomembrane performance and the time intervals for conducting the tests. Performance is assessed by observing trends in test results conducted over time including the results obtained on unexposed samples.

Method 9090 involves immersing geomembrane samples in leachate at temperatures of 23°C and 50°C for periods of 30, 60, 90, and 120 days. After each exposure period, samples are removed and tested. The method specifies the type of immersion vessel, its size, and the degree of mixing required to ensure that the leachate completely immerses each sample throughout the testing periods. In addition, Method 9090 also recommends that the leachate in each immersion cell be drained and replaced after each 30-day exposure to ensure against the loss of volatile organics.

The EPA method also specifies sample preparation and the physical and mechanical tests to be performed. The following tests were run on the geomembranes in the Deferiet program. The first two are specified in Method 9090, and the third was recommended by the project consultant:

- Physical tests: "nondestructive" tests that measure physical properties of the sample, such as thickness and dimensional stability
- Mechanical tests: "destructive" tests that measure the strength properties of the sample, such as tear resistance
- Chemical tests: tests that measure chemical properties of the sample by techniques such as infrared spectroscopy, differential scanning calorimetry (DSC), and thermal gravimetric analysis (TGA).

It is beyond our scope here to describe the test procedures or how their results are interpreted. The Deferiet Materials Conformance and Compatibility Test Report contains a more detailed description of the tests (5).

Table II lists the tests performed on the three HDPE geomembranes. Table III lists the tests performed on the PVC leachate collection piping.

### Geomembrane test results

Variations in test results on exposed and unexposed samples can be due to either material degradation or material variability. However, in evaluating the results of Method 9090 testing, the Environmental Protection Agency has recognized only degradation as the cause of variation in results. The EPA methods for interpreting results of Method 9090 testing need to take into account the variability of the material. Careful interpretation, analysis, and comparison of results of nondestructive, destructive, and chemical tests can be used to differentiate between changes caused by material variation and those caused by degradation.

In interpreting the results of Method 9090 testing, the general practice in industry and regulatory agencies is to conclude that changes of less than 50% in the results of physical and mechanical testing indicate that no degradation of the material occurred as a result of leachate exposure. When changes in physical and mechanical properties exceed 50%, then problems with the material could be experienced as the result of material variability or degradation, or a combination of the two. For chemical testing results (expressed in °C), values within  $\pm 20^{\circ}$ C are generally considered to be within normal ranges.

Only five of the 22 tests in Table II are discussed here, because they are the most useful ones in making the distinction between material variability and degradation.

### Differential scanning calorimetry

Tests performed by DSC are used to assess a material's molecular structure and resistance to oxidation. Table


Solid Waste

	Initial	After 1	After 120 days	
Property		23°C	50°C	
Manu	Jacturer A			
Crystallinity, %	48.3	42.6	44.4	
Max. energy absorption, °C	125.2	124.4	124.7	
Oxidative induction temp.				
(OIT), °C	264.7	263.8	260.4	
Onset of endotherm, °C	117.6	117.0	118.3	
Manu	facturer B			
Crystallinity, %	47.9	44.4	44.(	
Max. energy absorption, °C	124.6	125.3	125.2	
Oxidative induction temp.				
(OIT), °C	263.3	267.1	268.2	
Onset of endotherm, °C	117.4	118.0	117.5	
Manu	facturer C			
Crystallinity, %	45.6	45.5	45.8	
Max. energy absorption, °C	126.8	126.2	126.7	
Oxidative induction temp.				
(OIT), °C	262.1	262.0	262.3	
Onset of endotherm, °C	118.3	118.9	119.3	


V. Results of tensile properties tests on unexposed geomembranes

		Manufacture	
Test	A	В	C
<u> </u>	Machine direction	1	
Yield strength, MPa	17.4	17.1	17.4
Yield elongation, %	14.8	17.5	16.5
Break strength, MPa	28.1	25.2	27.2
Break elongation, %	1126	1130	1194
	Cross direction		
Yield strength, MPa	18.4	18.4	18.1
Yield elongation, %	15.1	15.3	16.2
Break strength, MPa	31.8	26.0	30.5
Break elongation, %	1286	1224	1280

1. MD yield strengths for geomembranes from Manufacturers A, B, and C at 23°C and 50°C




2. MD yield elongation for geomembranes from Manufacturers A, B, and C at 23°C and 50°C



.

-





Solid Waste

MD break elongation for geomembranes from Manufacturers A,

4.

B, and C at 23°C and 50°C

IV summarizes all of the testing performed by DSC. For each of the three HDPE geomembranes, data were collected on crystallinity, temperature at maximum energy absorption. oxidative induction temperature (OIT), and the temperature of the onset of endotherm. Table IV includes the data for both the 23°C and 50°C immersion temperatures.

The results of tests performed on exposed samples at 120 days and on unexposed samples are very consistent, with the exception of the crystallinity values between the geomembrane samples for Manufacturers A and B. For these two geomembranes, the reductions in crystallinity values compared with those of the initial, unexposed samples are an indication of manufacturing variability, not of material degradation from leachate exposure. (Note that the crystallinity for Manufacturer C does not change.)

### Infrared spectroscopy

Infrared spectroscopy is used to assess the structure of the polymer, including the presence of additives. The method is used to identify specific degradation processes, which would be identifiable by the presence of new spectral bands in the samples exposed for 120 days. A principal degradation process would be oxidation of the polymer, which would be indicated by the presence of ar O-H bond peak in the IR scan in the wavelength range of 1600–1800 cm<sup>-1</sup>. On the IR scans after 120 days, no new bands were present, including even no new O-H bands.

The comparison of the results for the three 120-day


VI. Moduli of elasticity of unexposed membranes

Manufac- turer	Modulus of elasticity, MPa		
	Average	Minimum	<550
	Machine	direction	
A	560	464	3
<b>B</b> -	391	328	. 5
C	403	354	5.
	Cross-mach	nine direction	
A	544	459	2
<b>B</b>	444	415	5
С	428	358	5


samples with the results of the unexposed samples is important. The comparison shows, in combination with the OIT results, that no degradation of the geomembranes has taken place in the Method 9090 tests. In addition, the IR results indicate that leachate organic constituents have not been absorbed into the geomembrane polymer matrices.

### **Tensile properties**

Tensile properties define the mechanical strength of finished products. As defined by ASTM D638, tensile prop-



 Piping stiffness at 23°C and 50°C for deflection values of 5%, 10%, and 30%



erties of geomembranes are defined by the following tests:

- Yield stress, MPa
- Yield elongation, %
- Break stress, MPa
- Break elongation, %
- Modulus of elasticity, psi.

Stress and elongation at yield and at break. Yield stress is specifically defined as the stress corresponding to the first point on the stress-strain curve at which there is a large increase in strain for no increase in stress (7). The elongation at yield is the stretched length of the specimen at the yield point and is measured as a percentage of original specimen length. Break stress is the force required to break or rupture the specimen, and the break elongation is the length at the break point as a percentage of original length.

Table V summarizes the results of the tests for tensile properties of unexposed samples. The values tabulated are mean values based on the results of ten tests—five replications at each of the two immersion temperatures. Samples were tested in both the machine direction and the cross-machine direction.

National Sanitation Foundation, Standard No. 54 (8) requires that 60-mil HDPE geomembranes have a yield strength of at least 13.8 MPa, a yield elongation of at least 10%, a minimum break stress of 20.7 MPa, and a minimum break elongation of 500%.

The results for the three HDPE geomembranes are summarized below, based on the average values calculated for each test (from Table V):

- All of these test values for tensile strength at yield are above the minimum of 13.8 MPa.
- All of the test values for elongation at yield are above the minimum 10% value. The unexposed values for Manufacturer A are low, whereas test results throughout the 120-day exposure testing are more typical of the product. The low values for unexposed samples combined with normal values during the immersion testing account for all of the large percent changes in Fig. 4.
- All of the test values for tensile strength at break are above the minimum of 20.7 MPa.
- All of the test values for elongation at break are above the minimum 500% value.
- The three geomembranes are functionally equivalent in terms of their relative merits, based on the tensile properties tests.
- No trends with respect to either time or temperature were noted in the compatibility test results.

**Figures 1-4** present the test results in terms of percent change over the 120-day leachate exposure period for yield strength, yield elongation, break strength, and break elongation in the machine direction (MD).

Modulus of elasticity. The modulus of elasticity is the ratio of stress change to the corresponding strain change.

Solid Waste

It is defined as the slope of the initial linear portion of the uniaxial stress-strain curve. It is a constant for a given material and is a measure of the material's stiffness. The modulus of elasticity was determined by using the tangent method of ASTM D638, which requires five replicate samples per direction per geomembrane.

Table VI summarizes the modulus-of-elasticity data for both the machine and cross-machine directions for unexposed samples of the three geomembranes. NSF No. 54 specifies a value of 550 MPa as the minimum acceptable value for modulus of elasticity. The geomembrane from Manufacturer A is the only product tested that had an average modulus of elasticity above this value in the machine direction.

Normally, the modulus test (and any other test for measuring strength) will have lower results for the cross direction than for the machine direction. While this is true for Manufacturer A's geomembrane, both of the other geomembranes exhibited the opposite results. The moduli of elasticity for Manufacturers B and C indicate, along with melt flow index and specific gravity, that they are manufactured from a resin of lower density that that used by Manufacturer A.

Figure 5 graphs the machine-direction results for the 120-day compatibility testing. The graphs show no clear time-dependent trends for any of the three geomembranes, further substantiating that no degradation of the materials is taking place from leachate exposure.

### Thermogravimetric analysis

Thermogravimetric analysis (TGA) defines the composition on a percent-by-weight basis, and it is useful in assessing the thermal properties of finished products. None of the TGA compositional data show the presence of two or more polymer fractions for the geomembranes. The presence of two or more polymer fractiqns can be indicative of the manufacturer's use of regrind (grinding off-spec product and adding it back into the extruder to make new product). This practice often leads to higherthan-average molecular weight distributions in the manufactured product.


In addition to percent composition, results are presented for the onset-of-decomposition temperature and the temperature at the maximum rate of weight loss. Significant changes in these two parameters are helpful in assessing structural changes of the geomemorane.

Overall, the results of the TGA analysis, including the data for percent composition and the onset-ofdecomposition temperature, were that all three geomembranes showed little change in composition after 120 days of immersion in leachate. These results are also consistent with those obtained from the DSC analyses. Geomembranes A and C showed little change in both composition and decomposition temperatures. However, the geomembrane from Manufacturer B did exhibit some reduction in the onset-of-decomposition temperature and the temperature of the rate of maximum decomposition. Such changes are more likely associated with material variability than with material degradation.

### VII. PVC piping DSC and TGA results

Test	Unexposed sample	120-day exposure	
		23°C	50°C
	DSC		
Oxidative induction			
temperature, °C	286.39	286.35	286.00
	TGA	، معرضه ،	
Composition, %			.*
Volatiles	0.52	0.55	0.54
Polymer 1	57.70	57.18	:57.65
Polymer 2	23.03	16.94	17.72
Residue	18.74	25.32	24.08
Onset-of-decomposition	سرب بر سر		ALL ST
temp., °C	271.35	266.89	268.07
Temp. at max. rate			
of weight loss, °C	285.00	289.00	276.28

 Results of the wall thickness tests at immersion cell temperatures of 23°C and 50°C



### Piping test results

### Compressive strength (stiffness)

ASTM D2412 is the test method used to determine the compressive strength (stiffness) of the pipe and is thus analogous to the tensile properties test performed on the geomembrane. This method is based on determining the pipe stiffness in megapascals at 5%, 10%, and 30% deflection. The stiffness is used to assess the ability of the pipe to withstand the load imposed by the weight of the wastes stored in the landfill cell.

Compressive strengths are expressed in megapascals, which are the units obtained by dividing the load (kilograms) by the cross-sectional area normal to the load. The cross-sectional area is the specimen length times deflection. The ratio of loads required to go from one deflection to a greater deflection (in percent) is almost always less than the ratios of the respective deflections. Therefore, the resulting strengths in MPa at 10% deflection, for example, will be less than those at 5% deflection. The same analysis applies to values obtained at 30% deflection. .

Figure 6 shows the consistency of the stiffness results throughout the 120-day period for both the 23°C and 50°C tests. The results show larger percent decreases occurring at the 120-day interval for all three deflection values at both temperatures. However, the magnitude of the changes is well below the values usually considered to indicate actual changes in piping material properties.

### Differential scanning calorimetry

Oxidative induction temperature data are presented in Table VII for both the 23°C and 50°C immersion samples. The results are consistent throughout the immersion periods and show no indication of polymer degradation.

### Infrared spectroscopy

A comparison of results for unexposed and 120-day samples shows, in conjunction with the OIT results, that the pipe has not been degraded from leachate exposure. In addition, the IR results indicate that organic constituents of the leachate have not been absorbed into the piping polymer matrix.

### Thermogravimetric analysis

The TGA data in Table VII show excellent consistency in all three tests conducted (composition, onset-ofdecomposition temperature, and temperature at the maximum rate of weight loss). The presence of two polymer fractions in the PVC piping is normal. The onsetof-decomposition temperatures are consistent with those obtained for oxidative induction temperature, showing insignificant decomposition or interaction with leachate.

### Wall thickness

Wall thickness is a nondestructive test to determine if swelling or shrinkage of the material is occurring from exposure to leachate. This test is the counterpart of the dimensional change test on the geomembranes.

Results of the test are shown in Fig. 7. The changes are less than  $\pm 5\%$ , which places them within the range of precision and bias of the tests. Therefore, the changes in this figure are statistically insignificant, and the data show no apparent trends for the two immersion cell temperatures in the Method 9090 testing. In addition, the changes in Fig. 7 are not as extreme in range as those shown for the destructive piping stiffness test in Fig. 6.

### Conclusions

The results of the conformance and compatibility testing indicate that the geomembranes and the PVC piping tested would be suitable for use in the Deferiet solid-waste management facility. In addition, the geomembranes all met the minimum requirements as specified in NSF Standard No. 54.

These conclusions are supported by the evidence that exposure to leachate did not cause material degradation. Changes in test results were found to be caused by material variability, not degradation, for the following reasons:

• The results of the IR spectroscopy and OIT tests show that after immersion in the leachate for 120 days, oxidation or absorption of leachate constituents into the samples did not occur.

- The results of the crystallinity test, in combination with those for specific gravity, hardness, and tensile strength, showed that plasticization or crosslinking of the polyethylene geomembranes did not occur.
- None of the physical, mechanical, or chemical test results showed any trends over the 120 days of leachate exposure.
- The results for piping stiffness (where material differences and degradation are variables) were compared with the results for wall thickness (where material degradation is the only variable). This comparison emphasized that changes in the Method 9090 test results for both the geomembrane and piping materials were attributable to material variations. These variations arise from differences in the raw resins used to manufacture the material or from the manufacturing processes themselves.

The results of the compatibility testing of the HDPE geomembranes also showed their suitability for use in the landfill leachate collection pipe. The testing of both HDPE and PVC leachate collection pipe allowed Champion to choose between the two, solely on the basis of cost.

It is recommended that chemical testing (IR, DSC, and TGA) be incorporated into any compatibility testing program to provide direct evaluation of degradation mechanisms that affect materials. The use of chemical testing will help evaluate Method 9090 test results to identify changes caused by material variability and those caused by degradation from leachate exposure.

### Literature cited

- 1. Solid waste management facilities, Title 6 of NYCRR, Part 360, New York State Dept. of Environmental Conservation, Dec. 31, 1988.
- 2. Permit application nonhazardous industrial solid waste management facility for Champion International, Town of Le Ray, RMT, August 1989.
- 3. New York industry solid waste characterization, Malcolm Pirnie, Inc., Buffalo, New York, June 1988.
- Method 9090—compatibility test for wastes and membrane liners, U.S. EPA, Sept. 1986.
- 5. Material conformance and compatibility testing for Deferiet Paper Mill, RMT, November 1990 (Champion International).
- 6. Earnest. C., Analytical Chemistry 56(13): 1471A(1984).
- Byars, E. and Snyder, R., Engineering Mechanics of Deformable Bodies, International Textbook Co., Scranton, Penn., 1967.
- 8. Flexible membrane liners, Standard No. 54, last revision, National Sanitation Foundation, November 1985.

Received for review Jan. 18, 1991.

Accepted April 30, 1991.

Presented at the TAPPI 1991 Environmental Conference.

·

-

. .