

New York State Department of Environmental Conservation
Division of Environmental Remediation
 Remedial Bureau C, 11th Floor
 Inspection Unit

DAILY INSPECTION REPORT

Site Code #: 706010	Date: September 14, 2017	Report #:
----------------------------	---------------------------------	------------------

Site Name: Auburn McMaster St. MGP
Location: Auburn
PRP Proj. Mgr.: Tracy Blazicek.
DEC Proj. Mgr.: John Spellman P.E.
Consultant Proj. Mgr.: Shane Blavalt
Proj. Contr.: Severson Environmental Services
Site Phone & Fax: N/A

	AM	PM
Weather	Rain	
Temperature	60s	
Wind Direction	calm	

Description of work performed by contr. this report period:

On-site 9:20 am

SES crew of about 6

Met with Chester Adams of Severson and Ron Prohaska of Parsons to discuss newly observed NAPL coming out of the bedrock. Upper 2' or so of rock is blocky, sits on harder layer. Where NAPL was observed it was at interface of looser and harder rock. Freckles of sheen observed on top of upper rock. I'm told the rock surface was pressure washed and sheet spots appeared later. At south bank there was a question of how far to chase NAPL inward. There was a mild odor in the streambed. SES wants to use hoe ram to remove all loose rock and place hydraulic cement at tar areas. I said ram use is ok, would have to get back to NYSEG with the cement. Also, mentioned I'm skeptical of its cement use; should try to find source of NAPL

10:30-11am I left site to get camera batteries

11 am I stopped at the farmer's market adjacent lot on the e side for odor check. No odors.

11:20 SES placing boulders along prison wall near girder bridge crossing. Told being done to shore up wall. SES doing satisfactory job of collecting water within the streambed.

At Clark Street the temporary storage pad was under construction. No activity there this morning.

Off-site at 12:20

Site Representative: John Spellman

Date: September 14, 2017

Representative's signature:









