

LIMITED SITE DATA

SOUTH HILL DUMP

**TOWN OF CORTLANDVILLE, CORTLAND COUNTY,
NEW YORK**

SITE NO. 712009

These documents that follow are **NOT** part of the Contract Documents for the remedial work at the South Hill Dump Site. The Department neither represents that the Site conditions will be the same as in the attached document nor considers the attached documents as being comprehensive and an actual description of the site conditions. The Contractor shall be responsible for performing the remediation work based on the existing conditions at the Site.

TABLE OF CONTENTS

Reports

Test Pit Report

Figures

Tables

Contaminants and Remediation Goals

Groundwater Data

Surface Water Data

Sediment Data

Soil Data

Appendices

Appendix A – Photographs

Appendix B – Soil Boring Logs and Well Construction Diagrams

Appendix C – Inactive Hazardous Waste Disposal Sites Database Site Summary

Appendix D – Selected Appendices from RI Report

REPORTS

TEST PIT REPORT

The Test Pit Report depicts site conditions as they were known to have existed in November 2010. This information is being offered for consideration when planning the remedial work.

South Hill Dump Site

Site No. 712009

South Hill Road, Cortlandville, NY

report.hw712009.2011-01-25.S.Hill_Dump_Inspection_Report

	AM	PM
Weather:	Light Rain	Light Rain
Temp (deg. F):	48	45
Wind (mph):	SSW 18	W 17
Total precipitation: trace		

Contractor: Empire GEO Services

Engineer conducting oversight: MACTEC Engineering and Consulting (Phil Muller).

This report prepared by MACTEC: Byanna Stiles Checked by: Mark Stelmack
Philip Muller w/permission by P.J.M. Mark Stelmack

Report No. 1

Date: 11/17/10

General Description of Work Performed:

The contractor conducted eleven test pits to delineate the limit of solid waste boundary at the northwest side (road side) of the site.

Meetings:

Health and Safety tailgate meeting between the contractor and MACTEC.

Contractor's Personnel

Classification	No.	Hours	Notes
Operator	1	6	

Contractor's Equipment

Description	Size	No.	Hours	Other
Backhoe	Ford 555E	1	6	

Description of Tests/Inspections Performed:

Eleven test pits were conducted as shown on the attached mark-up of the remedial design Existing Condition Plan, Drawing C-101. Also attached are test pit logs and sketches.

The Global Positioning System (GPS) was used to identify limits of waste in the areas where the test pits were conducted. The GPS unit used was a Trimble GeoXT which typically provides accuracy to within approximately three feet.

Materials Received: None

Equipment Calibration: None

Acceptance of Work and/or Corrective Actions:

The contractor performed the items identified in the Test Pitting Services Scope of Work, October 19, 2010.

Photo Log:



Photo 7577. TP-2, looking toward landfill from toe of slope (South Hill Road). Test pit uncovered weathered bedrock and bedrock immediately below the surface. Solid waste located approximately 60 ft from toe of slope.



Photo 7579. Solid waste uncovered at TP-2, within 1 ft of the surface.



Photo 7585. TP-3, looking toward landfill from toe of slope (South Hill Road). Test pit uncovered shallow weathered bedrock. Waste located approximately 80 ft from toe of slope.



Photo 7595. Solid waste uncovered at TP-1D, which extended into the adjacent berm.



Photo 7603. TP-4 looking toward slope, which contained sand and gravel. At the toe of the slope there was a thin layer of solid waste, visible on the right side of this test pit.



Photo 7605. Solid waste layer (approximately 2 ft thick) in TP-5, looking toward slope.



Photo 7611. No solid waste layer in TP-6, looking toward slope.



Photo 7613. No solid waste layer in TP-6, from toe of slope.



Test Pit Log	Test Pit No.: TP- 1A
--------------	----------------------

Test Pit No.: TP- 1A

Project No.: 3612092133

Logged by: PJM

Client Name: NYSDEC

Project Name: South Hill Dump

Date: 11/17/2010

Contractor: SJB

Method: Backhoe

Equip. Type: Ford 555E

Operators Name: Randy Steiner

Total Depth: 2.4

25

Water Level (BGS)	3.6		
-------------------	-----	--	--

N/A

Ground Elevation: 14

N/A

Proportions: (-) Amount (+)

(-) Amount (+)

Abbreviations:

Trace (tr)	0-10%
------------	-------

0-10%

[illegible]

Little (I)	10-20%
------------	--------

10-20%

m = medium

Some (80)	20-35%
-----------	--------

20-35%

11

35-50%

35-50%

RECEIVED

bn = brown

Soil / Rock Description:	Elevation	Remarks

Question:

Appendix

2" leaf litter / grass / organic

grey, sandy silt, pieces of weathered

bedrock (2-2.5' thick)

25' bags - Pack

Notes:

See Page 2 for Test Plot Sketch

MACTEC

Created by: RRM

Checked by: *DM*

© 2005 Blackwell Publishing Ltd *Journal of Internal Medicine* 258: 105–112

Test Pit Sketch		Test Pit No. TP- 1A
Project No.: 3612092133	Logged By: PJM	
Client Name: NYSDEC	Project Name: South Hill Dump	
Date: 8/11/10		
Contractor: SJB	Method: Backhoe	Equip. Type: Ford 555E
Operators Name: Randy Steiner		

5' 10'

organic
grey, sandy silt, and
weathered bedrock

rock

0'

5'

15'

Created by: PJM

Checked by: PJM

See Page 2 for Test Plot Sketch

Test Pit Sketch

Test Pit No. TP- 13

Project No.: 3612092133

Logged By: PJM

Client Name: NYSDEC

Project Name: South Hill Dump


Date: 8/17/10

Contractor: SJB

Method: Backhoe

Equip. Type: Ford 555E

Operators Name: Randy Steiner



MACTEC

Created by: PJM
Checked by: PJM

[illegible]

MACTEC

►ADMINISTRATIVE FORMS and Formslist Files & Sheet Templates

Test Pit Sketch

Test Pit No. TP- 1C

Project No.: 3612092133

Logged By: PJM

Client Name: NYSDEC

Project Name: South Hill Dump


Date: 11/17/10

Contractor: SJB

Method: Backhoe

Equip. Type: Ford 555E

Operators Name: Randy Steiner



MACTEC

Created by: PJM
Checked by: JPM

See Page 2 for Test Pit Sketch

Test Pit Sketch

Test Pit No. TP- 1D

Project No.: 3612092133

Logged By: PJM

Client Name: NYSDEC

Project Name: South Hill Dump


Date: 8/17/10

Contractor: SJB

Method: Backhoe

Equip. Type: Ford 555E

Operators Name: Randy Steiner



MACTEC

Created by: PJM
Checked by: JPM

[illegible]

MACTEC

Created by: PSM
Checked by: JPM

Test Pit Sketch

Test Pit No. TP- 2

Project No.: 3612092133

Logged By: PJM

Client Name: NYSDEC

Project Name: South Hill Dump


Date: 8/17/10

Contractor: SJB

Method: Backhoe

Equip. Type: Ford 555E

Operators Name: Randy Steiner



MACTEC

Created by: PJM
Checked by: PJM

[illegible]

MACTEC

Created by: f3m
Checked by: km

Test Pit Sketch

Test Pit No. TP- 3

Project No.: 3612092133

Logged By: PJM

Client Name: NYSDEC

Project Name: South Hill Dump


Date: 8/17/10

Contractor: SJB

Method: Backhoe

Equip. Type: Ford 555E

Operators Name: Randy Steiner



MACTEC

Created by: PJM
Checked by: PJM

[illegible]

MACTEC

Created by: RJM
Checked by: JPM

Test Pit Sketch

Test Pit No. TP- 4

Project No.: 3612092133

Logged By: PJM

Client Name: NYSDEC

Project Name: South Hill Dump


Date: 4/17/10

Contractor: SJB

Method: Backhoe

Equip. Type: Ford 555E

Operators Name: Randy Steiner



MACTEC

Created by: BM
Checked by: BPM

Test Pit Log						Test Pit No.: TP- 5		
Project No.: 3612092133					Logged by: PJM			
Client Name: NYSDEC					Project Name: South Hill Dump			
Date: 11/17/2010								
Contractor: SJB					Method: Backhoe		Equip. Type: Ford 555E	
Operators Name: Randy Sleiner								
Total Depth: 5'					Water Level (BGS) N/A		Ground Elevation: N/A	
Depth (feet) Below Ground Surface	Sample ID Number	Headspace (ppm)	Water Content	Soil Class	Proportions: (-) Amount (+) Trace (tr) 0-10% Little (l) 10-20% Some (so) 20-35% 35-50%	Abbreviations: f = fine m = medium c = coarse gr = gray bn = brown blk = black	Elevation (feet)	Remarks:
					Soil / Rock Description:			
0					gray sandy silt and gravel			
1								
2								
3								
4					Solid waste (glass, metal, plastic, bottles)			
5					dk brown silt and f. sand			
					Bottom of Test Pit @ 5' Lys			

Notes:

See Page 2 for Test Pit Sketch

 MACTEC

Test Pit Sketch

Test Pit No. TP- 5

Project No.: 3612092133

Logged By: PJM

Client Name: NYSDEC

Project Name: South Hill Dump


Date: 11/17/10

Contractor: SJB

Method: Backhoe

Equip. Type: Ford 555E

Operators Name: Randy Steiner



MACTEC

Created by: PJM
Checked by: PJM

Test Pit Sketch

Test Pit No. TP- 6

Project No.: 3612092133

Logged By: PJM

Client Name: NYSDEC

Project Name: South Hill Dump


Date: 4/17/10

Contractor: SJB

Method: Backhoe

Equip. Type: Ford 555E

Operators Name: Randy Steiner



MACTEC

Created by: PJM
Checked by: PJM

Test Pit Sketch

Test Pit No. TP- 7

Project No.: 3612092133

Logged By: PJM

Client Name: NYSDEC

Project Name: South Hill Dump


Date: 11/17/10

Contractor: SJB

Method: Backhoe

Equip. Type: Ford 555E

Operators Name: Randy Steiner



MACTEC

Created by: PJM
Checked by: PJM

Test Pit Log						Test Pit No.: TP- 8	
Project No.: 3612092133					Logged by: PJM		
Client Name: NYSDEC					Project Name: South Hill Dump		
Date: 11/17/2010							
Contractor: SJB					Method: Backhoe		Equip. Type: Ford 555E
Operators Name: Randy Steiner							
Total Depth: 6'			Water Level (BGS): N/A			Ground Elevation: N/A	
Depth (feet) Below Ground Surface	Sample ID/Number	Headspace (ppm)	Water Content	Soil Class	Proportions: (-) Amount (+)		Abbreviations:
					Trace (tr)	0-10%	
					Little (l)	10-20%	f = fine
					Some (so)	20-35%	m = medium
						35-50%	c = coarse
							gr = gray
							bn = brown
							blk = black
					Soil / Rock Description:		
0					6" grass + topsoil		
1					grey sandy S.H. and Gravel		
2							
3							
4							
5							
6					End of Test Pit @ 6' bgs		

Notes: 1 fire found in top 2' of TP; rusted soil @ 3' bgs in isolated location
 No layer of soil waste uncovered.

See Page 2 for Test Pit Sketch

 MACTEC

Created by: PJM
 Checked by: PJM

Test Pit Sketch

Test Pit No. TP- 8

Project No.: 3612092133

Logged By: PJM

Client Name: NYSDEC

Project Name: South Hill Dump


Date: 11/17/10

Contractor: SJB

Method: Backhoe

Equip. Type: Ford 555E

Operators Name: Randy Steiner



MACTEC

Created by: PJM
Checked by: PJM

FIGURES

SITE MAPS/SITE FEATURES

The enclosed figures are taken from historical South Hill Dump site investigation reports. In general, the figures depict onsite and nearby area conditions observed at various times between 2003 and 2006. The intent of each figure is to illustrate site conditions as they were known to have existed at the time the figure was generated. This information is being offered for consideration when planning the remedial work.



SOUTH HILL DUMP
CORTLANDVILLE, CORTLAND COUNTY, NEW YORK
SITE No. 7-12-009

New York State Department of
Environmental Conservation




FILE: DRAWING: DRAWN FROM SPENCER F. THEW, PE - LS BASE MAP
BY: BAB

SITE MAP

DATE: 5/16/03

FIGURE I



SOUTH HILL DUMP
CORTLANDVILLE, CORTLAND COUNTY, NEW YORK
SITE No. 7-12-009


New York State Department of
Environmental Conservation

FILE: DRAWING: DRAWN FROM SPENCER F. THEW, PE - LS BASE MAP
BY: BAB

SITE SURVEY

DATE: 5/16/03

FIGURE 2



SOUTH HILL DUMP
CORTLANDVILLE, CORTLAND COUNTY, NEW YORK
SITE No. 7-12-009



New York State Department of
Environmental Conservation

FILE: DRAWING: DRAWN FROM SPENCER F. THEW, PE - LS BASE MAP
BY: BAB



TEST PIT LOCATIONS

DATE: 5/16/03

FIGURE 3



SOUTH HILL DUMP SITE Town of Cortlandville, Cortland County, New York Site No. 7-12-009	
New York State Department of Environmental Conservation 	
FILE: South Hill RL.DWG	DRAWING: Survey by Spencer F. Thew PE-L.S. Modified by NYSDEC
SHALLOW GROUNDWATER ELEVATIONS	
DATE: 12/24/87	DRAWING 5



SOUTH HILL DUMP SITE

Town of Cortlandville, Cortland County, New York

Site No. 7-12-009

New York State Department of
Environmental Conservation

FILE: South Hill R.DWG


DRAWING: Survey by Spencer F. Thaw PE-LS,
Modified by NYDEC

BEDROCK GROUNDWATER ELEVATIONS

DATE: 12/24/97

DRAWING 6

2003 orthophoto imagery obtained from New York State GIS Clearinghouse at: www.nysgis.state.ny.us



Prepared/Date: BRP 10/18/05
Checked/Date: RTB 10/18/05


NYSDEC
South Hill Dump Site
Cortland, NY



Site Location
Project 3612-05-2032
Figure 1.1

Document: P:\Projects\NYSDEC\1\PROJECTS\South Hill Dump 7-12-009\4.0 Project Deliverables\4.5 Databases\GIS\MapDocuments\SiteLocationMap.mxd PDF: P:\Projects\NYSDEC\1\PROJECTS\South Hill Dump 7-12-009\4.0 Project Deliverables\4.3 Drawings\Feeability Study\Figure 1.2.pdf 10/18/2005 3:26 PM bnpeters

2003 orthophoto imagery obtained from
New York State GIS Clearinghouse at:
www.nysgis.state.ny.us





Prepared/Date: BRP 10/18/05
Checked/Date: RTB 10/18/05

NYSDEC
South Hill Dump Site
Cortland, NY



Site Features
Project 3612-05-2032
Figure 1.2





NOTE:
CROSS-SECTION INFORMATION DERIVED FROM
REMEDIAL INVESTIGATION FOR THE SOUTH
HILL DUMP (NYSDEC, 2003)

LEGEND

- EXISTING GROUND
- - - BOTTOM OF FILL
- . - . - BEDROCK SURFACE (ESTIMATED)
- . . - GROUNDWATER TABLE

SCALE:
VERT: 1" = 12'
HORIZ: 1" = 60'

Prepared/Date: RHH 10/12/05
Checked/Date: RTB 10/14/05

South Hill Dump Site, NYSDEC Site No. 712009
County of Cortland, Courtlandville, NY



Cross Section of Site

Project 3612-05-2032
Figure 1.4

TABLES

The enclosed tables are taken from historical South Hill Dump Site investigation reports. In general, the tables depict onsite and nearby area conditions observed at various times between 1997 and 2001. The intent of the tables is to depict onsite and nearby area contaminant concentrations for the following site media:

- contaminants and remediation goals
- groundwater
- surface water
- sediment
- soil

Contaminant concentrations presented on the tables are those reported at the time the table was generated. This information is being offered for consideration when planning the remedial work.

CONTAMINANTS AND REMEDIATION GOALS TABLES

Table 2.1: Contaminants of Concern

	UNITS	CHEMICAL- SPECIFIC SCG VALUES	MIN DETECT	MAX DETECT	NO OF SAMPLES	FREQUENCY OF EXCEEDANCE	BACK- GROUND
TEST PIT SOILS							
VOLATILES							
None	mg/Kg						
SEMIVOLATILES							
Benzo(a)anthracene	mg/Kg	0.224/MDL	ND	0.76	24	13%	ND
Benzo(a)pyrene	mg/Kg	0.061/MDL	ND	0.78	24	33%	ND
Chrysene	mg/Kg	0.4	ND	0.81	24	8%	ND
Phenol	mg/Kg	0.03/MDL	ND	1.4	24	13%	ND
PESTICIDES/PCBs							
None	mg/Kg						
TCLP VOLATILES							
None	mg/L						
TCLP SEMIVOLATILES							
None	mg/L						
TCLP PESTICIDES							
None	mg/L						
TCLP HERBICIDES							
None	mg/L						
INORGANICS							
Aluminum	mg/Kg	SB	6610	32900	24	21%	16200
Antimony	mg/Kg	SB	1.7	24	24	100%	1.6
Arsenic	mg/Kg	7.5 or SB	4.8	40.7	24	50%	7.9
Barium	mg/Kg	300 or SB	45.6	904	24	13%	89.8
Beryllium	mg/Kg	0.16 or SB	ND	0.7	24	8%	0.6
Cadmium	mg/Kg	1 or SB	ND	49.8	24	63%	N/A
Calcium	mg/Kg	SB	688	61900	24	75%	1135
Chromium	mg/Kg	10 or SB	11.8	435	24	71%	21.85
Cobalt	mg/Kg	30 or SB	6	34.2	24	8%	15.75
Copper	mg/Kg	25 or SB	11.8	1820	24	63%	19.1
Iron	mg/Kg	2000 or SB	17100	569000	24	54%	33550
Lead	mg/Kg	SB	7.5	2910	24	75%	14.3
Magnesium	mg/Kg	SB	1650	9510	24	21%	6085
Manganese	mg/Kg	SB	304	3490	24	29%	918
Mercury	mg/Kg	0.1	ND	0.79	24	46%	ND
Nickel	mg/Kg	13 or SB	15.3	249	24	50%	34.5
Potassium	mg/Kg	SB	519	4950	24	63%	1270
Sodium	mg/Kg	SB	185	2440	24	100%	167
Thallium	mg/Kg	SB	ND	2.1	24	17%	ND
Zinc	mg/Kg	20 or SB	50.7	4130	24	88%	69.25
Total Cyanide	mg/Kg	(see Note 1)	ND	3.01	24	17%	ND
TCLP METALS							
None	mg/L						
SURFACE WATER							
VOLATILES							
1,2-Dichloroethene (total)	µg/L	5	ND	180	6	17%	NA
Trichloroethene	µg/L	40	ND	530	6	17%	NA
Vinyl Chloride	µg/L	2	ND	2	6	17%	NA
SEMIVOLATILES							
bis(2-Ethylhexyl)phthalate	µg/L	0.6	ND	18	6	83%	NA
PESTICIDES/PCBs							
None	µg/L						
INORGANICS							

Table 2.1: Contaminants of Concern

	UNITS	CHEMICAL-SPECIFIC SCG VALUES	MIN DETECT	MAX DETECT	NO OF SAMPLES	FREQUENCY OF EXCEEDANCE	BACK-GROUND
Aluminum	µg/L	100	137	283000	6	100%	NA
Antimony	µg/L	6	ND	105	6	33%	NA
Barium	µg/L	2000	19.9	4830	6	33%	NA
Beryllium	µg/L	11, 1100*	ND	12.6	6		NA
Cadmium	µg/L	(see Note 2)	ND	16.2	6		NA
Chromium	µg/L	(see Note 2)	ND	457	6		NA
Cobalt	µg/L	5	ND	237	6	83%	NA
Copper	µg/L	(see Note 2)	2.9	595	6		NA
Iron	µg/L	300	105	2420000	6	83%	NA
Lead	µg/L	(see Note 2)	ND	2970	6		NA
Magnesium	µg/L	35,000	3710	102000	6	33%	NA
Manganese	µg/L	600	4.9	11000	6	83%	NA
Mercury	µg/L	0.0007	ND	2.8	6	83%	NA
Nickel	µg/L	(see Note 2)	ND	819	6		NA
Silver	µg/L	0.1**	ND	11	6	33%	NA
Sodium	µg/L	(see Note 2)	8690	26700	6		NA
Vanadium	µg/L	14	ND	405	6	83%	NA
Zinc	µg/L	(see Note 2)	9.4	14500	6		NA
Total Cyanide	µg/L	5.2***	ND	32	6	17%	NA
SEDIMENT (see Note 3)							
VOLATILES							
None	mg/Kg						
SEMIVOLATILES							
None	mg/Kg						
PESTICIDES/PCBs							
4,4'-DDT	mg/Kg	0.1	ND	0.2	7	14%	NA
INORGANICS							
Antimony	mg/Kg	2	ND	8.4	7	43%	NA
Arsenic	mg/Kg	6	ND	7.3	7	43%	NA
Cadmium	mg/Kg	0.6	ND	8.3	7	43%	NA
Chromium	mg/Kg	26	15.4	97.7	7	29%	NA
Copper	mg/Kg	16	13.6	60.5	7	71%	NA
Iron	mg/Kg	20,000	26100	167000	7	100%	NA
Lead	mg/Kg	31	15.5	334	7	57%	NA
Manganese	mg/Kg	460	521	1970	7	100%	NA
Nickel	mg/Kg	16	27.7	91.5	7	100%	NA
Silver	mg/Kg	1	ND	2.4	7	14%	NA
Zinc	mg/Kg	120	170	1240	7	100%	NA
TCLP METALS							
None	mg/L						
SOIL BORINGS (see Note 4)							
VOLATILES							
None	mg/Kg						
SEMIVOLATILES							
None	mg/Kg						
PESTICIDES/PCBs							
None	mg/Kg						
INORGANICS							
Aluminum	mg/Kg	SB	11800	17900	6	17%	16200
Antimony	mg/Kg	SB	0.55	2	6	67%	1.6
Arsenic	mg/Kg	7.5 or SB	6.6	10.6	6	50%	7.9

Table 2.1: Contaminants of Concern

	UNITS	CHEMICAL- SPECIFIC SCG VALUES	MIN DETECT	MAX DETECT	NO OF SAMPLES	FREQUENCY OF EXCEEDANCE	BACK- GROUND
Beryllium	mg/Kg	0.16 or SB	0.46	0.73	6	17%	0.6
Calcium	mg/Kg	SB	782	50300	6	83%	1135
Chromium	mg/Kg	10 or SB	15.8	24.1	6	17%	21.85
Iron	mg/Kg	2000 or SB	25300	40000	6	17%	33550
Lead	mg/Kg	SB	5.7	22.9	6	33%	14.3
Magnesium	mg/Kg	SB	4130	9070	6	50%	6085
Nickel	mg/Kg	13 or SB	25.4	37.6	6	17%	34.5
Potassium	mg/Kg	SB	1140	2220	6	83%	1270
Sodium	mg/Kg	SB	ND	298	6	33%	167
Thallium	mg/Kg	SB	ND	0.97	6	33%	ND
Zinc	mg/Kg	20 or SB	57.6	87.2	6	50%	69.25
Total Cyanide	mg/Kg	****	ND	2.23	6	17%	ND
GROUNDWATER (see Note 5)							
VOLATILES							
1,2-Dichloroethene (total)	µg/L	5	ND	56	7	29%	ND
Trichloroethene	µg/L	5	ND	540	7	29%	ND
SEMIVOLATILES							
None	µg/L						
PESTICIDES/PCBs							
None	µg/L						
METALS							
Aluminum	µg/L	2000	463	4490	6	67%	12850
Iron	µg/L	300	811	47600	6	133%	23150
Manganese	µg/L	300	25	622	6	50%	767
Sodium	µg/L	20000	1900	23600	6	33%	3880

Prepared/Date: RTB 10/20/2005
 Checked/Date: MJS 10/20/2005

Notes:

1. Site-specific forms of cyanide should be evaluated in determining soil cleanup objective
 2. Standard or guidance values for inorganics in surface water are dependent upon hardness. Refer to Table B.4 for more info
 3. Sediment Screening Values presented for organic contaminants in sediment calculated for organic content of 1%, and should be adjusted according to site-specific values.
 4. Min and max detected values, number of samples, and frequency of detection do not include monitoring well data for back wells MW-1S and MW-1B
 5. Min and max detected values, number of samples, and frequency of detection do not include data for samples MW1B and
- *standard for beryllium is 11 ug/L for hardness less than or equal to 75 mg/L, 1100 ug/L for greater than 75 mg/L
- **applies to ionic silver
- ***cyanide criteria for free cyanide, the sum of HCN and CN- expressed as CN.
- ****site-specific forms of cyanide should be evaluated in determining cleanup objective
- MDL = method detection limit
- µg/L = micrograms per liter
- mg/kg = milligrams per kilogram
- ND = non detect

Table 3.1: Remediation Goals

	UNITS	MAX DETECT	REMEDIATION GOAL
SURFACE SOIL			
No Data Available			
SOIL			
Chrysene	mg/Kg	0.81	0.4
Phenol	mg/Kg	1.4	0.03/MDL
SURFACE WATER			
Mercury	µg/L	2.8	0.0026
SEDIMENT (see Note 1)			
4,4'-DDT	mg/Kg	0.2	0.1
Antimony	mg/Kg	8.4	2
Arsenic	mg/Kg	7.3	6
Cadmium	mg/Kg	8.3	0.6
Chromium	mg/Kg	97.7	26
Copper	mg/Kg	60.5	16
Iron	mg/Kg	167000	20,000
Lead	mg/Kg	334	31
Manganese	mg/Kg	1970	460
Nickel	mg/Kg	91.5	16
Silver	mg/Kg	2.4	1
Zinc	mg/Kg	1240	120
GROUNDWATER			
None			

Prepared/Date: RTB 10/20/05

Checked/Date: MJS 10/20/05

Notes:

1. Sediment Screening Values presented for organic contaminants in sediment calculated for organic content of one percent, and should be adjusted according to site-specific values.

MDL = method detection limit

µg/L = micrograms per liter

mg/kg = milligrams per kilogram

Table 3.2: Contamination Requiring Remediation

LOCATION	DEPTH (FT) (see Note 1)	MATRIX	UNITS	COMPOUND (see Note 2)	CONCENTRATION (see Note 4)	REMEDIALTION GOAL
TP-1	5	Soil	mg/Kg	chrysene	0.81	0.4
TP-11	12	Soil	mg/Kg	phenol	0.45	0.03/MDL
TP-18	8	Soil	mg/Kg	phenol	1.4	0.03/MDL
TP-38	2	Soil	mg/Kg	phenol	0.25	0.03/MDL
TP-39	1	Soil	mg/Kg	chrysene	0.58	0.4
SW002	NA	Surface water	µg/L	mercury	2.8	0.0026
SW003	NA	Surface water	µg/L	mercury	0.9	0.0026
SW004	NA	Surface water	µg/L	mercury	1	0.0026
SW005	NA	Surface water	µg/L	mercury	0.08	0.0026
SW006	NA	Surface water	µg/L	mercury	0.07	0.0026
SD001	NA	Sediment	mg/Kg	inorganics	-	-
SD002	NA	Sediment	mg/Kg	inorganics	-	-
SD003	NA	Sediment	mg/Kg	4,4'-DDT	0.2	0.1
SD003	NA	Sediment	mg/Kg	inorganics	-	-
SD004	NA	Sediment	mg/Kg	inorganics	-	-
SD005	NA	Sediment	mg/Kg	inorganics	-	-
SD006	NA	Sediment	mg/Kg	inorganics	-	-
SD007	NA	Sediment	mg/Kg	inorganics	-	-

Prepared/Date: RTB 10/20/05
Checked/Date: MJS 10/20/05

Notes:

1. MW-2B, MW-3B, and MW-4B are bedrock wells consisting of sealed open bore hole, no screen. Depth listed is top of bedrock. Refer to Monitoring Well Construction Logs in Appendix C of the RI. water SCG) values.
 2. refer to Table B.5 for specific inorganic contaminants above RG (equivalent to sediment SCG) values.
- B2EHP = bis(2-ethylhexyl)phthalate

GROUNDWATER DATA TABLES

TABLE 5

GROUNDWATER ANALYTICAL DATA SUMMARY

GROUNDWATER SAMPLES - 1997

SOUTH HILL DUMP SITE VALIDATED GROUNDWATER SAMPLE RESULTS DETECTED COMPOUND SUMMARY		SAMPLE ID: LAB ID: SOURCE: SDG: MATRIX: SAMPLED: VALIDATED: UNITS:	GROUNDWATER STANDARD TOGS 1.1.1	MW002B 3134509 NYTEST SHD8 WATER 5/22/97 7/25/97	MW003S 3134510 NYTEST SHD8 WATER 5/22/97 7/25/97	MW003B 3134511 NYTEST SHD8 WATER 5/22/97 7/25/97	MW004S 3134506 NYTEST SHD8 WATER 5/22/97 7/25/97	MW004B 3134507 NYTEST SHD8 WATER 5/22/97 7/25/97
COMPOUND								
VOLATILES								
1,2-Dichloroethene (total)		ug/L	5	-	18	56	-	-
Trichloroethene		ug/L	5	4 J	80	540	-	4 J
SEMIVOLATILES								
4-Chloroaniline		ug/L	5	R	R	R	R	R
bis(2-Ethylhexyl)phthalate		ug/L	50	-	2 J	1 J	2 J	2 J
PESTICIDES/PCBs								
NONE				-	-	-	-	-
METALS								
Aluminum		ug/L	100	4270 J	948 J	936 J	463 J	1180 J
Arsenic		ug/L	25	5.5 J	-	-	-	-
Barium		ug/L	1000	135 J	48.3 J	121 J	27 J	86.8 J
Beryllium		ug/L	3(G)	-	-	-	-	-
Cadmium		ug/L	10	-	-	-	-	2.6 J
Calcium		ug/L		43900 J	57800 J	75200 J	22200 J	39200 J
Chromium		ug/L	50	27.6	-	-	-	-
Cobalt		ug/L	5	7.1 J	-	-	-	-
Copper		ug/L	200	43.4	3 J	3.9 J	2.3 J	4.8 J
Iron		ug/L	300	47600	2000	3850	811	3160
Lead		ug/L	25	12.6 J	-	-	-	1.8 J
Magnesium		ug/L	35000(G)	8690	13700	14900	3450 J	8630
Manganese		ug/L	300	622 J	46.8 J	231 J	25 J	46.3 J
Mercury		ug/L	2	-	-	-	-	-
Nickel		ug/L		45	-	6.4 J	-	4.5 J
Potassium		ug/L		-	9140	1980 J	-	-
Sodium		ug/L	20000	3230 J	20900	23600	1900 J	3690 J
Vanadium		ug/L	14	6.2 J	-	-	-	-
Zinc		ug/L	300	40.2 J	34.3 J	23.9 J	62.6 J	19.9 J

SOUTH HILL DUMP SITE VALIDATED GROUNDWATER SAMPLE RESULTS DETECTED COMPOUND SUMMARY		DUP of MW001B					
COMPOUND	SAMPLE ID:	GROUNDWATER	MW001S	MW001B	MW005	MW002S	MW002D
VOLATILES	LAB ID:	STANDARD	3134501	3134502	3134505	3134518	3134508
1,2-Dichloroethene (total)	SOURCE:	TOGS 1.1.1	NYTEST	NYTEST	NYTEST	NYTEST	NYTEST
Trichloroethene	SDG:		SHD8	SHD8	SHD8	SHD8	SHD8
SEMIVOLATILES	MATRIX:		WATER	WATER	WATER	WATER	WATER
4-Chloroaniline	SAMPLED:		5/22/97	5/22/97	5/22/97	5/22/97	5/22/97
bis(2-Ethylhexyl)phthalate	VALIDATED:		7/25/97	7/25/97	7/25/97	7/25/97	7/25/97
PESTICIDES/PCBs	UNITS:						
NONE							
METALS							
Aluminum	ug/L	100	11500 J	11400 J	14200 J		4490 J
Arsenic	ug/L	25	-	7.1 J	11.4		-
Barium	ug/L	1000	97.6 J	132 J	151 J		70.7 J
Beryllium	ug/L	3(G)	0.32 J	0.33 J	0.39 J		-
Cadmium	ug/L	10	-	-	-		-
Calcium	ug/L		20700 J	22900 J	23600 J		46300 J
Chromium	ug/L	50	19.2	24.7	22.7		7.6 J
Cobalt	ug/L	5	8 J	8.5 J	10.2 J		2.8 J
Copper	ug/L	200	21.9 J	25.5 J	25.5		7.4 J
Iron	ug/L	300	21000	21400	25300		8620
Lead	ug/L	25	6.8 J	11.3 J	11.4 J		3.1 J
Magnesium	ug/L	35000(G)	8120	8220	9110		12400
Manganese	ug/L	300	658 J	784 J	876 J		200 J
Mercury	ug/L	2	-	0.12 J	0.09 J		-
Nickel	ug/L		23.1 J	35.9 J	30.1 J		8.6 J
Potassium	ug/L		4010 J	2760 J	3330 J		2830 J
Sodium	ug/L	20000	3580 J	4140 J	4180 J		4300 J
Vanadium	ug/L	14	13.7 J	14.2 J	17.7 J		5.2 J
Zinc	ug/L	300	167 J	88.4 J	72.6 J		37 J

GROUNDWATER SAMPLES - 2001

New York State - DEC		
Brad Brown		
625 Broadway, 11th Floor		
Albany, NY 12233-7017		
Project:	BRAD BROWN	
Sampled:	27-Sep-01	
Source:	SOUTH HILL DUMP MW-1S	
Lab ID:	L77138-1	
Analysis	Result	Units
ASP 95-1		
Chloromethane	U	ug/l
Bromomethane	U	ug/l
Vinyl chloride	U	ug/l
Chloroethane	U	ug/l
Methylene chloride	U	ug/l
Acetone	U	ug/l
Carbon disulfide	U	ug/l
1,1-Dichloroethene	U	ug/l
trans-1,2-Dichloroethene	U	ug/l
1,1-Dichloroethane	U	ug/l
cis-1,2-Dichloroethene	U	ug/l
MEK(2-Butanone)	U	ug/l
Chloroform	U	ug/l
1,1,1-Trichloroethane	U	ug/l
Carbon tetrachloride	U	ug/l
Benzene	U	ug/l
1,2-Dichloroethane	U	ug/l
Trichloroethene	U	ug/l
1,2-Dichloropropane	U	ug/l
Bromodichloromethane	U	ug/l
cis-1,3-Dichloropropene	U	ug/l
MIBK(4-Methyl-2-pentanone)	U	ug/l
Toluene	U	ug/l
trans-1,3-Dichloropropene	U	ug/l
1,1,2-Trichloroethane	U	ug/l
Tetrachloroethene	U	ug/l
2-Hexanone	U	ug/l
Dibromochloromethane	U	ug/l
Chlorobenzene	U	ug/l
Ethylbenzene	U	ug/l
p-Xylene/m-Xylene	U	ug/l
o-Xylene	U	ug/l
Styrene	U	ug/l
Bromoform	U	ug/l
1,1,2,2-Tetrachloroethane	U	ug/l

New York State - DEC		
Brad Brown		
625 Broadway, 11th Floor		
Albany, NY 12233-7017		
Project:	BRAD BROWN	
Sampled:	37161	
Source:	SOUTH HILL DUMP MW-1B	
Lab ID:	L77138-2	
Analysis	Result	Units
ASP 95-1		
Chloromethane	U	ug/l
Bromomethane	U	ug/l
Vinyl chloride	U	ug/l
Chloroethane	U	ug/l
Methylene chloride	U	ug/l
Acetone	U	ug/l
Carbon disulfide	U	ug/l
1,1-Dichloroethene	U	ug/l
trans-1,2-Dichloroethene	U	ug/l
1,1-Dichloroethane	U	ug/l
cis-1,2-Dichloroethene	U	ug/l
MEK(2-Butanone)	U	ug/l
Chloroform	U	ug/l
1,1,1-Trichloroethane	U	ug/l
Carbon tetrachloride	U	ug/l
Benzene	U	ug/l
1,2-Dichloroethane	U	ug/l
Trichloroethene	U	ug/l
1,2-Dichloropropane	U	ug/l
Bromodichloromethane	U	ug/l
cis-1,3-Dichloropropene	U	ug/l
MIBK(4-Methyl-2-pentanone)	U	ug/l
Toluene	U	ug/l
trans-1,3-Dichloropropene	U	ug/l
1,1,2-Trichloroethane	U	ug/l
Tetrachloroethene	U	ug/l
2-Hexanone	U	ug/l
Dibromochloromethane	U	ug/l
Chlorobenzene	U	ug/l
Ethylbenzene	U	ug/l
p-Xylene/m-Xylene	U	ug/l
o-Xylene	U	ug/l
Styrene	U	ug/l
Bromoform	U	ug/l
1,1,2,2-Tetrachloroethane	U	ug/l

New York State - DEC		
Brad Brown		
625 Broadway, 11th Floor		
Albany, NY 12233-7017		
Project:	BRAD BROWN	
Sampled:	37161	
Source:	SOUTH HILL DUMP MW-2S	
Lab ID:	L77138-3	
Analysis	Result	Units
ASP 95-1		
Chloromethane	U	ug/l
Bromomethane	U	ug/l
Vinyl chloride	U	ug/l
Chloroethane	U	ug/l
Methylene chloride	U	ug/l
Acetone	U	ug/l
Carbon disulfide	U	ug/l
1,1-Dichloroethene	U	ug/l
trans-1,2-Dichloroethene	U	ug/l
1,1-Dichloroethane	U	ug/l
cis-1,2-Dichloroethene	U	ug/l
MEK(2-Butanone)	U	ug/l
Chloroform	U	ug/l
1,1,1-Trichloroethane	U	ug/l
Carbon tetrachloride	U	ug/l
Benzene	U	ug/l
1,2-Dichloroethane	U	ug/l
Trichloroethene	U	ug/l
1,2-Dichloropropane	U	ug/l
Bromodichloromethane	U	ug/l
cis-1,3-Dichloropropene	U	ug/l
MIBK(4-Methyl-2-pentanone)	U	ug/l
Toluene	U	ug/l
trans-1,3-Dichloropropene	U	ug/l
1,1,2-Trichloroethane	U	ug/l
Tetrachloroethene	U	ug/l
2-Hexanone	U	ug/l
Dibromochloromethane	U	ug/l
Chlorobenzene	U	ug/l
Ethylbenzene	U	ug/l
p-Xylene/m-Xylene	U	ug/l
o-Xylene	U	ug/l
Styrene	U	ug/l
Bromoform	U	ug/l
1,1,2,2-Tetrachloroethane	U	ug/l

New York State - DEC		
Brad Brown		
625 Broadway, 11th Floor		
Albany, NY 12233-7017		
Project:	BRAD BROWN	
Sampled:	37161	
Source:	SOUTH HILL DUMP MW-2B	
Lab ID:	L77138-4	
Analysis	Result	Units
ASP 95-1		
Chloromethane	U	ug/l
Bromomethane	U	ug/l
Vinyl chloride	U	ug/l
Chloroethane	U	ug/l
Methylene chloride	U	ug/l
Acetone	U	ug/l
Carbon disulfide	U	ug/l
1,1-Dichloroethene	U	ug/l
trans-1,2-Dichloroethene	U	ug/l
1,1-Dichloroethane	U	ug/l
cis-1,2-Dichloroethene	U	ug/l
MEK(2-Butanone)	U	ug/l
Chloroform	U	ug/l
1,1,1-Trichloroethane	U	ug/l
Carbon tetrachloride	U	ug/l
Benzene	U	ug/l
1,2-Dichloroethane	U	ug/l
Trichloroethene	U	ug/l
1,2-Dichloropropane	U	ug/l
Bromodichloromethane	U	ug/l
cis-1,3-Dichloropropene	U	ug/l
MIBK(4-Methyl-2-pentanone)	U	ug/l
Toluene	U	ug/l
trans-1,3-Dichloropropene	U	ug/l
1,1,2-Trichloroethane	U	ug/l
Tetrachloroethene	U	ug/l
2-Hexanone	U	ug/l
Dibromochloromethane	U	ug/l
Chlorobenzene	U	ug/l
Ethylbenzene	U	ug/l
p-Xylene/m-Xylene	U	ug/l
o-Xylene	U	ug/l
Styrene	U	ug/l
Bromoform	U	ug/l
1,1,2,2-Tetrachloroethane	U	ug/l

New York State - DEC		
Brad Brown		
625 Broadway, 11th Floor		
Albany, NY 12233-7017		
Project:	BRAD BROWN	
Sampled:	27-Sep-01	
Source:	SOUTH HILL DUMP MW-2D	
Lab ID:	L77138-5	
Analysis	Result	Units
ASP 95-1		
Chloromethane	U	ug/l
Bromomethane	U	ug/l
Vinyl chloride	U	ug/l
Chloroethane	U	ug/l
Methylene chloride	U	ug/l
Acetone	U	ug/l
Carbon disulfide	U	ug/l
1,1-Dichloroethene	U	ug/l
trans-1,2-Dichloroethene	U	ug/l
1,1-Dichloroethane	U	ug/l
cis-1,2-Dichloroethene	U	ug/l
MEK(2-Butanone)	U	ug/l
Chloroform	U	ug/l
1,1,1-Trichloroethane	U	ug/l
Carbon tetrachloride	U	ug/l
Benzene	U	ug/l
1,2-Dichloroethane	U	ug/l
Trichloroethene	U	ug/l
1,2-Dichloropropane	U	ug/l
Bromodichloromethane	U	ug/l
cis-1,3-Dichloropropene	U	ug/l
MIBK(4-Methyl-2-pentanone)	U	ug/l
Toluene	U	ug/l
trans-1,3-Dichloropropene	U	ug/l
1,1,2-Trichloroethane	U	ug/l
Tetrachloroethene	U	ug/l
2-Hexanone	U	ug/l
Dibromochloromethane	U	ug/l
Chlorobenzene	U	ug/l
Ethylbenzene	U	ug/l
p-Xylene/m-Xylene	U	ug/l
o-Xylene	U	ug/l
Styrene	U	ug/l
Bromoform	U	ug/l
1,1,2,2-Tetrachloroethane	U	ug/l

New York State - DEC		
Brad Brown		
625 Broadway, 11th Floor		
Albany, NY 12233-7017		
Project:	BRAD BROWN	
Sampled:	27-Sep-01	
Source:	SOUTH HILL DUMP MW-3S	
Lab ID:	L77138-6	
Analysis	Result	Units
ASP 95-1		
Chloromethane	U	ug/l
Bromomethane	U	ug/l
Vinyl chloride	U	ug/l
Chloroethane	U	ug/l
Methylene chloride	U	ug/l
Acetone	U	ug/l
Carbon disulfide	U	ug/l
1,1-Dichloroethene	U	ug/l
trans-1,2-Dichloroethene	U	ug/l
1,1-Dichloroethane	U	ug/l
cis-1,2-Dichloroethene	264	ug/l
MEK(2-Butanone)	U	ug/l
Chloroform	U	ug/l
1,1,1-Trichloroethane	U	ug/l
Carbon tetrachloride	U	ug/l
Benzene	U	ug/l
1,2-Dichloroethane	U	ug/l
Trichloroethene	200	ug/l
1,2-Dichloropropane	U	ug/l
Bromodichloromethane	U	ug/l
cis-1,3-Dichloropropene	U	ug/l
MIBK(4-Methyl-2-pentanone)	U	ug/l
Toluene	U	ug/l
trans-1,3-Dichloropropene	U	ug/l
1,1,2-Trichloroethane	U	ug/l
Tetrachloroethene	U	ug/l
2-Hexanone	U	ug/l
Dibromochloromethane	U	ug/l
Chlorobenzene	U	ug/l
Ethylbenzene	U	ug/l
p-Xylene/m-Xylene	U	ug/l
o-Xylene	U	ug/l
Styrene	U	ug/l
Bromoform	U	ug/l
1,1,2,2-Tetrachloroethane	U	ug/l

New York State - DEC		
Brad Brown		
625 Broadway, 11th Floor		
Albany, NY 12233-7017		
Project:	BRAD BROWN	
Sampled:	27-Sep-01	
Source:	SOUTH HILL DUMP MW-3B	
Lab ID:	L77138-7	
Analysis	Result	Units
ASP 95-1		
Chloromethane	U	ug/l
Bromomethane	U	ug/l
Vinyl chloride	U	ug/l
Chloroethane	U	ug/l
Methylene chloride	U	ug/l
Acetone	U	ug/l
Carbon disulfide	U	ug/l
1,1-Dichloroethene	U	ug/l
trans-1,2-Dichloroethene	U	ug/l
1,1-Dichloroethane	U	ug/l
cis-1,2-Dichloroethene	97	ug/l
MEK(2-Butanone)	U	ug/l
Chloroform	U	ug/l
1,1,1-Trichloroethane	U	ug/l
Carbon tetrachloride	U	ug/l
Benzene	U	ug/l
1,2-Dichloroethane	U	ug/l
Trichloroethene	360	ug/l
1,2-Dichloropropane	U	ug/l
Bromodichloromethane	U	ug/l
cis-1,3-Dichloropropene	U	ug/l
MIBK(4-Methyl-2-pentanone)	U	ug/l
Toluene	U	ug/l
trans-1,3-Dichloropropene	U	ug/l
1,1,2-Trichloroethane	U	ug/l
Tetrachloroethene	U	ug/l
2-Hexanone	U	ug/l
Dibromochloromethane	U	ug/l
Chlorobenzene	U	ug/l
Ethylbenzene	U	ug/l
p-Xylene/m-Xylene	U	ug/l
o-Xylene	U	ug/l
Styrene	U	ug/l
Bromoform	U	ug/l
1,1,2,2-Tetrachloroethane	U	ug/l

New York State - DEC		
Brad Brown		
625 Broadway, 11th Floor		
Albany, NY 12233-7017		
Project:	BRAD BROWN	
Sampled:	27-Sep-01	
Source:	SOUTH HILL DUMP MW-4S	
Lab ID:	L77138-10	
Analysis	Result	Units
ASP 95-1		
Chloromethane	U	ug/l
Bromomethane	U	ug/l
Vinyl chloride	U	ug/l
Chloroethane	U	ug/l
Methylene chloride	U	ug/l
Acetone	U	ug/l
Carbon disulfide	U	ug/l
1,1-Dichloroethene	U	ug/l
trans-1,2-Dichloroethene	U	ug/l
1,1-Dichloroethane	U	ug/l
cis-1,2-Dichloroethene	U	ug/l
MEK(2-Butanone)	U	ug/l
Chloroform	U	ug/l
1,1,1-Trichloroethane	U	ug/l
Carbon tetrachloride	U	ug/l
Benzene	U	ug/l
1,2-Dichloroethane	U	ug/l
Trichloroethene	U	ug/l
1,2-Dichloropropane	U	ug/l
Bromodichloromethane	U	ug/l
cis-1,3-Dichloropropene	U	ug/l
MIBK(4-Methyl-2-pentanone)	U	ug/l
Toluene	U	ug/l
trans-1,3-Dichloropropene	U	ug/l
1,1,2-Trichloroethane	U	ug/l
Tetrachloroethene	U	ug/l
2-Hexanone	U	ug/l
Dibromochloromethane	U	ug/l
Chlorobenzene	U	ug/l
Ethylbenzene	U	ug/l
p-Xylene/m-Xylene	U	ug/l
o-Xylene	U	ug/l
Styrene	U	ug/l
Bromoform	U	ug/l
1,1,2,2-Tetrachloroethane	U	ug/l

New York State - DEC		
Brad Brown		
625 Broadway, 11th Floor		
Albany, NY 12233-7017		
Project:	BRAD BROWN	
Sampled:	27-Sep-01	
Source:	SOUTH HILL DUMP MW-4B	
Lab ID:	L77138-11	
Analysis	Result	Units
ASP 95-1		
Chloromethane	U	ug/l
Bromomethane	U	ug/l
Vinyl chloride	U	ug/l
Chloroethane	U	ug/l
Methylene chloride	U	ug/l
Acetone	U	ug/l
Carbon disulfide	U	ug/l
1,1-Dichloroethene	U	ug/l
trans-1,2-Dichloroethene	U	ug/l
1,1-Dichloroethane	U	ug/l
cis-1,2-Dichloroethene	U	ug/l
MEK(2-Butanone)	U	ug/l
Chloroform	U	ug/l
1,1,1-Trichloroethane	U	ug/l
Carbon tetrachloride	U	ug/l
Benzene	U	ug/l
1,2-Dichloroethane	U	ug/l
Trichloroethene	7 J	ug/l
1,2-Dichloropropane	U	ug/l
Bromodichloromethane	U	ug/l
cis-1,3-Dichloropropene	U	ug/l
MIBK(4-Methyl-2-pentanone)	U	ug/l
Toluene	U	ug/l
trans-1,3-Dichloropropene	U	ug/l
1,1,2-Trichloroethane	U	ug/l
Tetrachloroethene	U	ug/l
2-Hexanone	U	ug/l
Dibromochloromethane	U	ug/l
Chlorobenzene	U	ug/l
Ethylbenzene	U	ug/l
p-Xylene/m-Xylene	U	ug/l
o-Xylene	U	ug/l
Styrene	U	ug/l
Bromoform	U	ug/l
1,1,2,2-Tetrachloroethane	U	ug/l

Table B.2: TP-40 Aqueous Sample Results

	SAMPLE ID:	TP40W	40SEEP
	LAB ID:	3080901	3082304
	SOURCE:	NYTEST	NYTEST
	SDG:	30809	SHD3
	MATRIX:	WATER	WATER
	SAMPLED:	3/17/97	3/19/97
	VALIDATED:	7/25/97	7/25/97
	UNITS:		
COMPOUND			
VOLATILES			
Acetone	µg/L	33	8 J
Benzene	µg/L	2 J	-
1,2-Dichloroethene (total)	µg/L	1,400	540
Toluene	µg/L	4 J	-
Trichloroethene	µg/L	560	420
Vinyl Chloride	µg/L	190	58
SEMIVOLATILES			
4-Methylphenol	µg/L		24
2,4,5-Trichlorophenol	µg/L		2 J
PESTICIDES/PCBs			
NONE	µg/L		-
INORGANICS			
Aluminum	µg/L		4,530 J
Barium	µg/L		196 J
Cadmium	µg/L		1 J
Calcium	µg/L		70,800
Chromium	µg/L		5 J
Cobalt	µg/L		3 J
Copper	µg/L		16 J
Iron	µg/L		8,680
Lead	µg/L		36 J
Magnesium	µg/L		17,700
Manganese	µg/L		756
Nickel	µg/L		17 J
Potassium	µg/L		14,000
Sodium	µg/L		25,000
Vanadium	µg/L		7 J
Zinc	µg/L		361
Total Cyanide	µg/L		30

Notes:
 ug/L = micrograms per liter
 J = estimated value

Prepared/Date: RTB 10/20/05
 Checked/Date: MJS 10/20/05

Table B.7: 1997 Groundwater Sample Results

	SAMPLE ID:	AMBIENT WATER	MW001S	MW001B
	LAB ID:	QUALITY STANDARD	3134501	3134502
	SOURCE:	OR GUIDANCE	NYTEST	NYTEST
	SDG:	VALUE	SHD8	SHD8
	MATRIX:	(see Note 1)	WATER	WATER
	SAMPLED:		5/22/97	5/22/97
	VALIDATED:		7/25/97	7/25/97
COMPOUND	UNITS:			
VOLATILES				
1,2-Dichloroethene (total)	µg/L	5	-	-
Trichloroethene	µg/L	5	-	-
SEMIVOLATILES				
4-Chloroaniline	µg/L	5	-	-
bis(2-Ethylhexyl)phthalate	µg/L	5	3 J	2 J
PESTICIDES/PCBs				
NONE			-	-
METALS				
Aluminum	µg/L	2000(E)	11500 J	11400 J
Arsenic	µg/L	25	-	7.1 J
Barium	µg/L	1000	97.6 J	132 J
Beryllium	µg/L	3(G)	0.32 J	0.33 J
Cadmium	µg/L	5	-	-
Calcium	µg/L	NL	20700 J	22900 J
Chromium	µg/L	50	19.2	24.7
Cobalt	µg/L	NL	8 J	8.5 J
Copper	µg/L	200	21.9 J	25.5 J
Iron	µg/L	300	21000	21400
Lead	µg/L	25	6.8 J	11.3 J
Magnesium	µg/L	35000(G)	8120	8220
Manganese	µg/L	300	658 J	784 J
Mercury	µg/L	0.7	-	0.12 J
Nickel	µg/L	100	23.1 J	35.9 J
Potassium	µg/L	NL	4010 J	2760 J
Sodium	µg/L	20000	3580 J	4140 J
Vanadium	µg/L	NL	13.7 J	14.2 J
Zinc	µg/L	2000(G)	167 J	88.4 J

Notes:

1. Cleanup objectives from TOGS 1.1.1, Class GA groundwater standard or guidance value (G). Where numbers were not available, NYSDEC Div. of Water "Generic Effluent Criteria for Surface Water Discharges" (E) was utilized.

Highlighted values greater than standard or guidance value

NL = no groundwater criteria listed

µg/L = micrograms per liter

J = estimated value

R = Data Rejected

Table B.7: 1997 Groundwater Sample Results

COMPOUND	SAMPLE ID:	AMBIENT WATER	DUP of MW001B	
			MW005	MW002S
	LAB ID:	QUALITY STANDARD	3134505	3134518
	SOURCE:	OR GUIDANCE	NYTEST	NYTEST
	SDG:	VALUE	SHD8	SHD8
	MATRIX:	(see Note 1)	WATER	WATER
	SAMPLED:		5/22/97	5/22/97
	VALIDATED:		7/25/97	7/25/97
	UNITS:			
VOLATILES				
1,2-Dichloroethene (total)	µg/L	5	-	-
Trichloroethene	µg/L	5	-	-
SEMIVOLATILES				
4-Chloroaniline	µg/L	5	-	
bis(2-Ethylhexyl)phthalate	µg/L	5	2 J	
PESTICIDES/PCBs				
NONE			-	
METALS				
Aluminum	µg/L	2000(E)	14200 J	
Arsenic	µg/L	25	11.4	
Barium	µg/L	1000	151 J	
Beryllium	µg/L	3(G)	0.39 J	
Cadmium	µg/L	5	-	
Calcium	µg/L	NL	23600 J	
Chromium	µg/L	50	22.7	
Cobalt	µg/L	NL	10.2 J	
Copper	µg/L	200	25.5	
Iron	µg/L	300	25300	
Lead	µg/L	25	11.4 J	
Magnesium	µg/L	35000(G)	9110	
Manganese	µg/L	300	876 J	
Mercury	µg/L	0.7	0.09 J	
Nickel	µg/L	100	30.1 J	
Potassium	µg/L	NL	3330 J	
Sodium	µg/L	20000	4180 J	
Vanadium	µg/L	NL	17.7 J	
Zinc	µg/L	2000(G)	72.6 J	

Notes:

1. Cleanup objectives from TOGS 1.1.1, Class GA groundwater standard value (G). Where numbers were not available, NYSDEC Div. of Water Effluent Criteria for Surface Water Discharges" (E) was utilized.

Highlighted values greater than standard or guidance value

NL = no groundwater criteria listed

µg/L = micrograms per liter

J = estimated value

R = Data Rejected

Table B.7: 1997 Groundwater Sample Results

	SAMPLE ID:	AMBIENT WATER	MW002D	MW002B
	LAB ID:	QUALITY STANDARD	3134508	3134509
	SOURCE:	OR GUIDANCE	NYTEST	NYTEST
	SDG:	VALUE	SHD8	SHD8
	MATRIX:	(see Note 1)	WATER	WATER
	SAMPLED:		5/22/97	5/22/97
	VALIDATED:		7/25/97	7/25/97
COMPOUND	UNITS:			
VOLATILES				
1,2-Dichloroethene (total)	µg/L	5	-	-
Trichloroethene	µg/L	5	-	4 J
SEMIVOLATILES				
4-Chloroaniline	µg/L	5	R	R
bis(2-Ethylhexyl)phthalate	µg/L	5	1 J	-
PESTICIDES/PCBs				
NONE			-	-
METALS				
Aluminum	µg/L	2000(E)	4490 J	4270 J
Arsenic	µg/L	25	-	5.5 J
Barium	µg/L	1000	70.7 J	135 J
Beryllium	µg/L	3(G)	-	-
Cadmium	µg/L	5	-	-
Calcium	µg/L	NL	46300 J	43900 J
Chromium	µg/L	50	7.6 J	27.6
Cobalt	µg/L	NL	2.8 J	7.1 J
Copper	µg/L	200	7.4 J	43.4
Iron	µg/L	300	8620	47600
Lead	µg/L	25	3.1 J	12.6 J
Magnesium	µg/L	35000(G)	12400	8690
Manganese	µg/L	300	200 J	622 J
Mercury	µg/L	0.7	-	-
Nickel	µg/L	100	8.6 J	45
Potassium	µg/L	NL	2830 J	-
Sodium	µg/L	20000	4300 J	3230 J
Vanadium	µg/L	NL	5.2 J	6.2 J
Zinc	µg/L	2000(G)	37 J	40.2 J

Notes:

1. Cleanup objectives from TOGS 1.1.1, Class GA groundwater standard value (G). Where numbers were not available, NYSDEC Div. of Water Effluent Criteria for Surface Water Discharges" (E) was utilized.

Highlighted values greater than standard or guidance value

NL = no groundwater criteria listed

µg/L = micrograms per liter

J = estimated value

R = Data Rejected

Table B.7: 1997 Groundwater Sample Results

	SAMPLE ID:	AMBIENT WATER	MW003S	MW003B
	LAB ID:	QUALITY STANDARD	3134510	3134511
	SOURCE:	OR GUIDANCE	NYTEST	NYTEST
	SDG:	VALUE	SHD8	SHD8
	MATRIX:	(see Note 1)	WATER	WATER
	SAMPLED:		5/22/97	5/22/97
	VALIDATED:		7/25/97	7/25/97
COMPOUND	UNITS:			
VOLATILES				
1,2-Dichloroethene (total)	µg/L	5	18	56
Trichloroethene	µg/L	5	80	540
SEMIVOLATILES				
4-Chloroaniline	µg/L	5	R	R
bis(2-Ethylhexyl)phthalate	µg/L	5	2 J	1 J
PESTICIDES/PCBs				
NONE				
METALS				
Aluminum	µg/L	2000(E)	948 J	936 J
Arsenic	µg/L	25	-	-
Barium	µg/L	1000	48.3 J	121 J
Beryllium	µg/L	3(G)	-	-
Cadmium	µg/L	5	-	-
Calcium	µg/L	NL	57800 J	75200 J
Chromium	µg/L	50	-	-
Cobalt	µg/L	NL	-	-
Copper	µg/L	200	3 J	3.9 J
Iron	µg/L	300	2000	3850
Lead	µg/L	25	-	-
Magnesium	µg/L	35000(G)	13700	14900
Manganese	µg/L	300	46.8 J	231 J
Mercury	µg/L	0.7	-	-
Nickel	µg/L	100	-	6.4 J
Potassium	µg/L	NL	9140	1980 J
Sodium	µg/L	20000	20900	23600
Vanadium	µg/L	NL	-	-
Zinc	µg/L	2000(G)	34.3 J	23.9 J

Notes:

1. Cleanup objectives from TOGS 1.1.1, Class GA groundwater standard value (G). Where numbers were not available, NYSDEC Div. of Water Effluent Criteria for Surface Water Discharges" (E) was utilized.

Highlighted values greater than standard or guidance value

NL = no groundwater criteria listed

µg/L = micrograms per liter

J = estimated value

R = Data Rejected

Table B.7: 1997 Groundwater Sample Results

	SAMPLE ID:	AMBIENT WATER	MW004S	MW004B
	LAB ID:	QUALITY STANDARD	3134506	3134507
	SOURCE:	OR GUIDANCE	NYTEST	NYTEST
	SDG:	VALUE	SHD8	SHD8
	MATRIX:	(see Note 1)	WATER	WATER
	SAMPLED:		5/22/97	5/22/97
	VALIDATED:		7/25/97	7/25/97
COMPOUND	UNITS:			
VOLATILES				
1,2-Dichloroethene (total)	µg/L	5	-	-
Trichloroethene	µg/L	5	-	4 J
SEMIVOLATILES				
4-Chloroaniline	µg/L	5	R	R
bis(2-Ethylhexyl)phthalate	µg/L	5	2 J	2 J
PESTICIDES/PCBs				
NONE			-	-
METALS				
Aluminum	µg/L	2000(E)	463 J	1180 J
Arsenic	µg/L	25	-	-
Barium	µg/L	1000	27 J	86.8 J
Beryllium	µg/L	3(G)	-	-
Cadmium	µg/L	5	-	2.6 J
Calcium	µg/L	NL	22200 J	39200 J
Chromium	µg/L	50	-	-
Cobalt	µg/L	NL	-	-
Copper	µg/L	200	2.3 J	4.8 J
Iron	µg/L	300	811	3160
Lead	µg/L	25	-	1.8 J
Magnesium	µg/L	35000(G)	3450 J	8630
Manganese	µg/L	300	25 J	46.3 J
Mercury	µg/L	0.7	-	-
Nickel	µg/L	100	-	4.5 J
Potassium	µg/L	NL	-	-
Sodium	µg/L	20000	1900 J	3690 J
Vanadium	µg/L	NL	-	-
Zinc	µg/L	2000(G)	62.6 J	19.9 J

Notes:

1. Cleanup objectives from TOGS 1.1.1, Class GA groundwater standard value (G). Where numbers were not available, NYSDEC Div. of Water Effluent Criteria for Surface Water Discharges" (E) was utilized.

Highlighted values greater than standard or guidance value

NL = no groundwater criteria listed

µg/L = micrograms per liter

J = estimated value

R = Data Rejected

Prepared/Date: RTB 10/17/2005

Checked/Date: MJS 10/20/05

Table B.8: 2001 Groundwater Sample Results

	SAMPLE ID:	AMBIENT WATER	MW001S	MW001B	MW002S	MW002B	MW002D
	LAB ID:	QUALITY STANDARD	L77138-1	L77138-2	L77138-3	L77138-4	L77138-5
	SOURCE:	OR GUIDANCE					
	SDG:	VALUE					
	MATRIX:	(see Note 1)	WATER	WATER	WATER	WATER	WATER
	SAMPLED:		9/27/2001	9/27/2001	9/27/2001	9/27/2001	9/27/2001
	VALIDATED:						
COMPOUND	UNITS:						
VOLATILES							
cis-1,2-Dichloroethene	µg/L	5	-	-	-	-	-
Trichloroethene	µg/L	5	-	-	-	-	-

Notes:

1. Cleanup objectives from TOGS 1.1.1, Class GA groundwater standard

Highlighted values greater than standard or guidance value

µg/L = micrograms per liter

J = estimated value

Table B.8: 2001 Groundwater Sample Results

COMPOUND	SAMPLE ID:	AMBIENT WATER	MW003S	MW003B	MW004S	MW004B
	LAB ID:	QUALITY STANDARD	L77138-6	L77138-7	L77138-10	L77138-11
	SOURCE:	OR GUIDANCE				
	SDG:	VALUE				
	MATRIX:	(see Note 1)	WATER	WATER	WATER	WATER
	SAMPLED:		9/27/2001	9/27/2001	9/27/2001	9/27/2001
	VALIDATED:					
UNITS:						
VOLATILES						
cis-1,2-Dichloroethene	µg/L	5	264	97	-	-
Trichloroethene	µg/L	5	200	360	-	7 J

Notes:

1. Cleanup objectives from TOGS 1.1.1, Class GA groundwater standard

Highlighted values greater than standard or guidance value

µg/L = micrograms per liter

J = estimated value

Prepared/Date: RTB 10/17/05

Checked/Date: MJS 10/20/05

SURFACE WATER DATA TABLES

TABLE 2

SURFACE WATER ANALYTICAL DATA SUMMARY

SOUTH HILL DUMP SITE VALIDATED SURFACE WATER SAMPLE RESULT DETECTED COMPOUND SUMMARY			SAMPLE ID:	SURFACE WATER	SW001	SW002	SW003	SW004	SW005	SW006
			LAB ID:	STANDARD	3134512	3134513	3134514	3134515	3134516	3134517
			SOURCE:	TOGS 1.1.1*	NYTEST	NYTEST	NYTEST	NYTEST	NYTEST	NYTEST
			SDG:		SHD8	SHD8	SHD8	SHD8	SHD8	SHD8
			MATRIX:		WATER	WATER	WATER	WATER	WATER	WATER
			SAMPLED:		5/22/97	5/22/97	5/22/97	5/22/97	5/22/97	5/22/97
			VALIDATED:		7/25/97	7/25/97	7/25/97	7/25/97	7/25/97	7/25/97
			UNITS:							
COMPOUND										
VOLATILES										
1,2-Dichloroethene (total)			ug/L	5	-	-	2 J	180	-	-
Trichloroethene			ug/L	11(G)	-	-	-	530	4 J	7 J
Vinyl Chloride			ug/L	0.7	-	-	-	32	-	-
SEMIVOLATILES										
4-Chloroaniline			ug/L		-	R	-	-	-	-
Di-n-butylphthalate			ug/L	50	-	-	-	-	-	4 J
1,4-Dichlorobenzene			ug/L	5	-	1 J	1 J	-	-	-
Diethylphthalate			ug/L	50	-	6 J	-	-	3 J	-
Fluoranthene			ug/L	10	-	-	-	-	2 J	-
N-Nitrosodiphenylamine			ug/L	10	-	-	-	2 J	-	-
Pyrene			ug/L	10	-	-	-	-	2 J	-
bis(2-Ethylhexyl)phthalate			ug/L	0.6	-	2 J	4 J	5 J	18 J	14 J
PESTICIDES/PCBs										
NONE			ug/L		-	-	-	-	-	R
INORGANICS										
Aluminum			ug/L	100	137 J	283000 J	14500 J	81200 J	11100 J	12900 J
Antimony			ug/L	10	-	105	-	11.6 J	-	-
Arsenic			ug/L	190	-	85.9	-	51.1	-	7.8 J
Barium			ug/L	1000	19.9 J	4830	304	2820	236	217
Beryllium			ug/L	1,100	-	12.6	.55 J	3.4 J	0.48 J	0.49 J
Cadmium			ug/L	1.2	-	12.5	-	16.2	1.3 J	-
Calcium			ug/L		18100 J	230000 J	92000 J	117000 J	60500 J	52200 J
Chromium			ug/L	207	-	457	18.9	152	21.5	18.4
Cobalt			ug/L	5	-	237	16.3 J	80.4	10.8 J	8.2 J
Copper			ug/L	24	2.9 J	590	30.8	595	33.2	26
Iron			ug/L	300	105	2420000	91100	286000	20700	21300
Lead			ug/L	4	-	1040 J	27.7 J	2970 J	69.9 J	36.4 J
Magnesium			ug/L	35,000	3710 J	102000	15800	45500	12700	14100
Manganese			ug/L	300	4.9 J	11000 J	2130 J	7990 J	1900 J	1130 J
Mercury			ug/L	0.2(G)	-	2.8	0.09 J	1	0.08 J	0.07 J
Nickel			ug/L	96	-	819	70.1	291	37.9 J	29.3 J
Potassium			ug/L		-	12900	7170	17700	4300 J	6550
Silver			ug/L	0.1	-	11	-	6.8 J	-	-
Sodium			ug/L		8690	13000	14200	26700	12200	17100
Vanadium			ug/L	14	-	405	19.4 J	201	16.2 J	17.6 J
Zinc			ug/L	30	9.4 J	9470 J	413 J	14500 J	581 J	323 J
Total Cyanide			ug/L	5.2	-	32 J	-	-	-	-

* Numbers shown represent the Class C surface water standard.
Where numbers were not available, NYSDEC Div. of Water
"Generic Effluent Criteria for Surface Water Discharges" was utilized.

Table B.4: Surface Water Sample Results

COMPOUND	SAMPLE ID:	AMBIENT WATER	SW001	SW002	SW003	SW004	SW005	SW006
	LAB ID:	QUALITY STANDARD	3134512	3134513	3134514	3134515	3134516	3134517
	SOURCE:	OR GUIDANCE	NYTEST	NYTEST	NYTEST	NYTEST	NYTEST	NYTEST
	SDG:	VALUE	SHD8	SHD8	SHD8	SHD8	SHD8	SHD8
	MATRIX:	(see Note 1)	WATER	WATER	WATER	WATER	WATER	WATER
	SAMPLED:		5/22/97	5/22/97	5/22/97	5/22/97	5/22/97	5/22/97
	VALIDATED:		7/25/97	7/25/97	7/25/97	7/25/97	7/25/97	7/25/97
	UNITS:							
VOLATILES								
1,2-Dichloroethene (total)	ug/L	5 (E)	-	-	2 J	180	-	-
Trichloroethene	ug/L	40	-	-	-	530	4 J	7 J
Vinyl Chloride	ug/L	2 (E)	-	-	-	32	-	-
SEMI-VOLATILES								
4-Chloroaniline	ug/L	5(E)	-	R	-	-	-	-
Di-n-butylphthalate	ug/L	50(E)	-	-	-	-	-	4 J
1,4-Dichlorobenzene	ug/L	5*	-	1 J	1 J	-	-	-
Diethylphthalate	ug/L	50(E)	-	6 J	-	-	3 J	-
Fluoranthene	ug/L	50(E)	-	-	-	-	2 J	-
N-Nitrosodiphenylamine	ug/L	50(E)	-	-	-	2 J	-	-
Pyrene	ug/L	4.6 (G)	-	-	-	-	2 J	-
bis(2-Ethylhexyl)phthalate	ug/L	0.6	-	2 J	4 J	5 J	18 J	14 J
PESTICIDES/PCBs								
NONE	ug/L		-	-	-	-	-	R
INORGANICS								
Aluminum	ug/L	100	137 J	283000 J	14500 J	81200 J	11100 J	12900 J
Antimony	ug/L	6(E)	-	105	-	11.6 J	-	-
Arsenic	ug/L	150**	-	85.9	-	51.1	-	7.8 J
Barium	ug/L	2000(E)	19.9 J	4830	304	2820	236	217
Beryllium	ug/L	11, 1100***	-	12.6	.55 J	3.4 J	0.48 J	0.49 J
Cadmium	ug/L	(see Note 2)	-	12.5	-	16.2	1.3 J	-
Calcium	ug/L	NL	18100 J	230000 J	92000 J	117000 J	60500 J	52200 J
Chromium	ug/L	(see Note 3)	-	457	18.9	152	21.5	18.4
Cobalt	ug/L	5	-	237	16.3 J	80.4	10.8 J	8.2 J
Copper	ug/L	(see Note 4)	2.9 J	590	30.8	595	33.2	26
Iron	ug/L	300	105	2420000	91100	286000	20700	21300
Lead	ug/L	(see Note 5)	-	1040 J	27.7 J	2970 J	69.9 J	36.4 J
Magnesium	ug/L	35,000(E)	3710 J	102000	15800	45500	12700	14100
Manganese	ug/L	600(E)	4.9 J	11000 J	2130 J	7990 J	1900 J	1130 J
Mercury	ug/L	0.0007	-	2.8	0.09 J	1	0.08 J	0.07 J
Nickel	ug/L	(see Note 6)	-	819	70.1	291	37.9 J	29.3 J
Potassium	ug/L	NL	-	12900	7170	17700	4300 J	6550
Silver	ug/L	0.1****	-	11	-	6.8 J	-	-
Sodium	ug/L	(see Note 7)(E)	8690	13000	14200	26700	12200	17100
Vanadium	ug/L	14	-	405	19.4 J	201	16.2 J	17.6 J
Zinc	ug/L	(see Note 8)	9.4 J	9470 J	413 J	14500 J	581 J	323 J
Total Cyanide	ug/L	5.2*****	-	32 J	-	-	-	-

Notes

1. Cleanup objectives from TOGS 1.1.1, Class C surface water standard or guidance value (G). Where numbers were not available, NYSDDEC Div. of Water "Generic Effluent Criteria for Surface Water Discharges" (E) was utilized
2. Cadmium criteria lesser of $(0.85)\exp(0.7852[\ln(\text{ppm hardness})]-2.715)$ or $(0.85)\exp(1.128[\ln(\text{ppm hardness})]-3.6867)$
3. Chromium criteria lesser of $(0.86)\exp(0.819[\ln(\text{ppm hardness})]+0.6848)$ or $(0.316)\exp(0.819[\ln(\text{ppm hardness})]+3.7256)$
4. Copper criteria lesser of $(0.96)\exp(0.8545[\ln(\text{ppm hardness})]-1.702)$ or $(0.96)\exp(0.9422[\ln(\text{ppm hardness})]-1.7)$
5. Lead criteria lesser of $\{1.46203-[\ln(\text{hardness}) (0.145712)]\}\exp(1.273[\ln(\text{hardness})]-4.297)$ or $\{1.46203-[\ln(\text{hardness}) (0.145712)]\}\exp(1.273[\ln(\text{hardness})]-1.502)$
6. Nickel criteria lesser of $(0.997)\exp(0.846[\ln(\text{hardness})]+0.0584)$ or $(0.998)\exp(0.846[\ln(\text{hardness})]+2.255)$
7. Sodium criteria to be determined on a case-by-case basis.
8. Zinc criteria lesser of $\exp(0.85[\ln(\text{ppm hardness})]+0.5)$ or $0.978\exp(0.8473[\ln(\text{ppm hardness})]+0.884)$

Highlighted values greater than standard or guidance value

* applies to sum of 1,2-, 1,3-, and 1,4-dichlorobenzene

**applies to dissolved form of arsenic

***standard for beryllium is 11 ug/L for hardness less than or equal to 75 mg/L, 1100 ug/L for

****applies to ionic silver

*****cyanide criteria for free cyanide, the sum of HCN and CN expressed as CN.

ug/L = micrograms per liter

J = estimated value

NL = not listed

Prepared/Date: RTB 10/20/05

Checked/Date: MJS 10/20/05

TABLE 3

SEDIMENT ANALYTICAL DATA SUMMARY

SOUTH HILL DUMP SITE VALIDATED SEDIMENT SAMPLE RESULTS DETECTED COMPOUND SUMMARY	SAMPLE ID: LAB ID: SOURCE: SDG: MATRIX: SAMPLED: VALIDATED:	DFW SEDIMENT CRITERIA	[DUP of SD001]							
			SD001	SD008	SD002	SD003	SD004	SD005	SD006	SD007
			3134101	3134108	3134104	3134109	3134105	3134106	3134110	3134107
			NYTEST SHD7 SEDIMENT 5/22/97 7/25/97	NYTEST SHD7 SEDIMENT 5/22/97 7/25/97	NYTEST SHD7 SEDIMENT 5/22/97 7/25/97	NYTEST SHD7 SEDIMENT 5/22/97 7/25/97	NYTEST SHD7 SEDIMENT 5/22/97 7/25/97	NYTEST SHD7 SEDIMENT 5/22/97 7/25/97	NYTEST SHD7 SEDIMENT 5/22/97 7/25/97	NYTEST SHD7 SEDIMENT 5/22/97 7/25/97
COMPOUND	UNITS:									
VOLATILES										
1,2-Dichloroethene (total)	mg/Kg		-	-	-	0.009 J	-	-	-	-
Trichloroethene	mg/Kg		-	-	-	0.017	-	-	-	-
SEMIVOLATILES										
Acenaphthene	mg/Kg	140	-	-	-	0.32 J	-	-	-	-
Anthracene	mg/Kg		-	-	-	0.36 J	0.089 J	-	-	-
Benzo(a)anthracene	mg/Kg		-	-	-	0.93 J	0.35 J	-	-	-
Benzo(a)pyrene	mg/Kg	1.3	-	-	-	0.59 J	0.15 J	-	-	-
Benzo(b)fluoranthene	mg/Kg		-	-	-	0.62 J	0.32 J	-	-	-
Benzo(k)fluoranthene	mg/Kg		-	-	-	0.79 J	0.25 J	-	-	-
Carbazole	mg/Kg		-	-	-	0.26 J	-	-	-	-
Chrysene	mg/Kg		-	-	-	0.96 J	0.39 J	-	-	-
Fluoranthene	mg/Kg	1,020	-	-	-	2.2	0.75 J	-	-	-
Fluorene	mg/Kg		-	-	-	0.26 J	-	-	-	-
Naphthalene	mg/Kg		-	-	-	0.23 J	-	-	-	-
Phenanthrene	mg/Kg	120	-	-	-	1.9	0.12 J	-	-	-
Pyrene	mg/Kg		-	-	-	1.2 J	0.78 J	-	-	-
bis(2-Ethylhexyl)phthalate	mg/Kg	199.5	0.2 J	0.2 J	0.13 J	4.9	2.2 J	0.75 J	0.1 J	0.53
PESTICIDES/PCBs										
4,4'-DDD	mg/Kg	0.01	-	-	-	0.012 JN	-	-	-	-
4,4'-DDE	mg/Kg	0.01	-	-	-	0.055	-	0.0057 J	-	-
4,4'-DDT	mg/Kg	0.01	-	-	-	0.2	0.0073 J	0.0048 JN	-	-
Endosulfan II	mg/Kg	0.03	-	-	-	0.0053 J	0.0044 JN	-	-	-
Endrin	mg/Kg	0.8	-	-	-	-	0.015 J	-	-	-
alpha-Chlordane	mg/Kg	0.001	-	-	-	0.0017 J	-	-	-	-
INORGANICS										
Aluminum	mg/Kg		10200 J	9770 J	15200 J	11100 J	14700 J	13200 J	843 J	13400 J
Antimony	mg/Kg	2	6.6 J	6.2 J	-	2.8 J	-	-	8.4 J	1.3 J
Arsenic	mg/Kg	6	3.9 J	3.6 J	4	7.3	7.3 J	5.5 J	-	6.1
Barium	mg/Kg		207 J	180 J	128 J	411 J	141 J	180 J	147 J	130 J
Beryllium	mg/Kg		0.42 J	0.4 J	0.54 J	0.42 J	0.57 J	0.53 J	-	0.51 J
Cadmium	mg/Kg	0.6	-	-	0.08 J	1.4	1.1 J	0.6 J	8.3	0.13 J
Calcium	mg/Kg		6010 J	5390 J	2060 J	8150 J	5200 J	5660 J	267000 J	2750 J
Chromium	mg/Kg	26	15.4 J	16.4 J	18.6	23.8	33.2 J	19.2 J	97.7	19.8
Cobalt	mg/Kg		12.7 J	11.5 J	10.2	11.1	10.6 J	11.8 J	3.5 J	11.7
Copper	mg/Kg	16	22 J	19.4 J	13.6 J	60.5 J	26.9 J	19.8 J	37 J	15.9 J
Iron	mg/Kg	20,000	167000 J	136000 J	44600 J	29700 J	26900 J	26100 J	148000 J	28300 J
Lead	mg/Kg	31	33 J	28.2 J	15.5 J	334 J	75.4 J	28.9 J	20.3 J	31.8 J
Magnesium	mg/Kg		3410 J	3160 J	3740 J	3760 J	4140 J	4030 J	16200 J	4080 J
Manganese	mg/Kg	460	927 J	913 J	521 J	876 J	733 J	1970 J	1010 J	1290 J
Mercury	mg/Kg	0.15	0.08 J	0.08 J	0.05 J	0.08 J	0.11 J	0.06 J	-	0.07 J
Nickel	mg/Kg	16	33.9 J	30.9 J	35 J	31 J	34.3 J	33 J	91.5 J	27.7 J
Potassium	mg/Kg		957 J	1040 J	1210	1230	1230 J	1210 J	143 J	1080
Silver	mg/Kg	1	-	-	-	-	-	-	2.4 J	-
Sodium	mg/Kg		186 J	182 J	142 J	349 J	250 J	162 J	1280	123 J
Vanadium	mg/Kg		18.4 J	17.2 J	21.6	24.1	23.5 J	20.9 J	3.8 J	19.3
Zinc	mg/Kg	120	581 J	500 J	290 J	1240 J	403 J	271 J	170 J	172 J
Total Cyanide	mg/Kg		-	-	-	0.71	-	-	3.8	-
ICLIP METALS										
Barium	mg/L	100				1.8			0.63	
Cadmium	mg/L	1				0.013			0.0081	
Lead	mg/L	5				0.25			-	

SEDIMENT DATA TABLES

Table 1.4: Determination of Sediment Screening Values for Organic Contaminants

COMPOUND	SAMPLE ID: LAB ID: SOURCE: SDG: MATRIX: SAMPLED: VALIDATED: UNITS:	HUMAN HEALTH BIOACCUM- ULATION µg/g OC	BENTHIC AQUATIC LIFE ACUTE TOXICITY µg/g OC	BENTHIC AQUATIC LIFE CHRONIC TOXICITY µg/g OC	WILDLIFE BIOACCUM- ULATION µg/g OC	SEDIMENT SCREENING VALUE mg/kg (see Note 1)
VOLATILES						
1,2-Dichloroethene (total)	mg/Kg	NL	NL	NL	NL	NL
Trichloroethene	mg/Kg	2	NL	NL	NL	20
SEMIVOLATILES						
Acenaphthene	mg/Kg	NL	NL	140	NL	1400
Anthracene	mg/Kg	NL	986	107	NL	1070
Benzo(a)anthracene	mg/Kg	1.3	NL	NL	NL	13
Benzo(a)pyrene	mg/Kg	1.3	NL	NL	NL	13
Benzo(b)fluoranthene	mg/Kg	1.3	NL	NL	NL	13
Benzo(k)fluoranthene	mg/Kg	1.3	NL	NL	NL	13
Carbazole	mg/Kg	NL	NL	NL	NL	NL
Chrysene	mg/Kg	1.3	NL	NL	NL	13
Fluoranthene	mg/Kg	NL	NL	NL	1020	10200
Fluorene	mg/Kg	NL	73	8	NL	80
Naphthalene	mg/Kg	NL	258	30	NL	300
Phenanthrene	mg/Kg	NL	NL	120	NL	1200
Pyrene	mg/Kg	NL	8775	961	NL	9610
bis(2-Ethylhexyl)phthalate	mg/Kg	NL	NL	199.5	NL	1995
PESTICIDES/PCBs						
4,4'-DDD	mg/Kg	0.01	1100	1	1	0.1
4,4'-DDE	mg/Kg	0.01	1100	1	1	0.1
4,4'-DDT	mg/Kg	0.01	1100	1	1	0.1
Endosulfan II	mg/Kg	NL	0.78	0.03	NL	0.3
Endrin	mg/Kg	0.8	NL	4	0.8	8
alpha-Chlordane	mg/Kg	0.001	1.4	0.03	0.006	0.01

Prepared/Date: RTB 10/20/05
 Checked/Date: MJS 10/20/05

Notes:

- Sediment Screening Values according to Table 1, NYSDEC Department of Fish and Wildlife Technical Guidance for Screening Contaminated Sediments, 1999.
 Risk based values presented based upon Fresh (FW) or Fresh and Saltwater (FS) Criteria.
 Sediment Screening Values presented in this table calculated for sediment organic content of 1%, and should be adjusted according to site-specific values.
 mg/kg =milligrams per kilogram
 µg/g OC = micrograms per gram organic content

Table B.5: Sediment Sample Results

COMPOUND	SAMPLE ID:	SEDIMENT	SEVERE	DUP of SD001							
				SD001	SD008	SD002	SD003	SD004	SD005	SD006	SD007
	LAB ID:	SCREENING	EFFECT	3134101	3134108	3134104	3134109	3134105	3134106	3134110	3134107
	SOURCE:	VALUE	LEVEL	NYTEST	NYTEST	NYTEST	NYTEST	NYTEST	NYTEST	NYTEST	NYTEST
	SDG:	mg/kg		SHD7	SHD7	SHD7	SHD7	SHD7	SHD7	SHD7	SHD7
	MATRIX:	(see Note 1)		SEDIMENT	SEDIMENT	SEDIMENT	SEDIMENT	SEDIMENT	SEDIMENT	SEDIMENT	SEDIMENT
	SAMPLED:			5/22/97	5/22/97	5/22/97	5/22/97	5/22/97	5/22/97	5/22/97	5/22/97
	VALIDATED:			7/25/97	7/25/97	7/25/97	7/25/97	7/25/97	7/25/97	7/25/97	7/25/97
	UNITS:										
VOLATILES											
1,2-Dichloroethene (total)	mg/Kg	NL		-	-	-	0.009 J	-	-	-	-
Trichloroethene	mg/Kg	20		-	-	-	0.017	-	-	-	-
SEMIVOLATILES											
Acenaphthene	mg/Kg	1400		-	-	-	0.32 J	-	-	-	-
Anthracene	mg/Kg	1070		-	-	-	0.36 J	0.089 J	-	-	-
Benzo(a)anthracene	mg/Kg	13		-	-	-	0.93 J	0.35 J	-	-	-
Benzo(a)pyrene	mg/Kg	13		-	-	-	0.59 J	0.15 J	-	-	-
Benzo(b)fluoranthene	mg/Kg	13		-	-	-	0.62 J	0.32 J	-	-	-
Benzo(k)fluoranthene	mg/Kg	13		-	-	-	0.79 J	0.25 J	-	-	-
Carbazole	mg/Kg	NL		-	-	-	0.26 J	-	-	-	-
Chrysene	mg/Kg	13		-	-	-	0.96 J	0.39 J	-	-	-
Fluoranthene	mg/Kg	10200		-	-	-	2.2	0.75 J	-	-	-
Fluorene	mg/Kg	80		-	-	-	0.26 J	-	-	-	-
Naphthalene	mg/Kg	300		-	-	-	0.23 J	-	-	-	-
Phenanthrene	mg/Kg	1200		-	-	-	1.9	0.12 J	-	-	-
Pyrene	mg/Kg	9610		-	-	-	1.2 J	0.78 J	-	-	-
bis(2-Ethylhexyl)phthalate	mg/Kg	1995		0.2 J	0.2 J	0.13 J	4.9	2.2 J	0.75 J	0.1 J	0.53
PESTICIDES/PCBs											
4,4'-DDD	mg/Kg	0.1		-	-	-	0.012 JN	-	-	-	-
4,4'-DDE	mg/Kg	0.1		-	-	-	0.055	-	0.0057 J	-	-
4,4'-DDT	mg/Kg	0.1		-	-	-	0.2	0.0073 J	0.0048 JN	-	-
Endosulfan II	mg/Kg	0.3		-	-	-	0.0053 J	0.0044 JN	-	-	-
Endrin	mg/Kg	8		-	-	-	-	0.015 J	-	-	-
alpha-Chlordane	mg/Kg	0.01		-	-	-	0.0017 J	-	-	-	-
INORGANICS											
Aluminum	mg/Kg	NL	NL	10200 J	9770 J	15200 J	11100 J	14700 J	13200 J	843 J	13400 J
Antimony	mg/Kg	2	25	6.6 J	6.2 J	-	2.8 J	-	-	8.4 J	1.3 J
Arsenic	mg/Kg	6	33	3.9 J	3.6 J	4	7.3	7.3 J	5.5 J	-	6.1
Barium	mg/Kg	NL	NL	207 J	180 J	128 J	411 J	141 J	180 J	147 J	130 J
Beryllium	mg/Kg	NL	NL	0.42 J	0.4 J	0.54 J	0.42 J	0.57 J	0.53 J	-	0.51 J

Table B.5: Sediment Sample Results

COMPOUND	DUP of SD001										
	SAMPLE ID:	SEDIMENT	SEVERE	SD001	SD008	SD002	SD003	SD004	SD005	SD006	SD007
	LAB ID:	SCREENING	EFFECT	3134101	3134108	3134104	3134109	3134105	3134106	3134110	3134107
	SOURCE:	VALUE	LEVEL	NYTEST	NYTEST	NYTEST	NYTEST	NYTEST	NYTEST	NYTEST	NYTEST
	SDG:	mg/kg		SHD7	SHD7	SHD7	SHD7	SHD7	SHD7	SHD7	SHD7
	MATRIX:	(see Note 1)		SEDIMENT	SEDIMENT	SEDIMENT	SEDIMENT	SEDIMENT	SEDIMENT	SEDIMENT	SEDIMENT
	SAMPLED:			5/22/97	5/22/97	5/22/97	5/22/97	5/22/97	5/22/97	5/22/97	5/22/97
	VALIDATED:			7/25/97	7/25/97	7/25/97	7/25/97	7/25/97	7/25/97	7/25/97	7/25/97
UNITS:											
Cadmium	mg/Kg	0.6	9	-	-	0.08 J	1.4	1.1 J	0.6 J	8.3	0.13 J
Calcium	mg/Kg	NL	NL	6010 J	5390 J	2060 J	8150 J	5200 J	5660 J	267000 J	2750 J
Chromium	mg/Kg	26	110	15.4 J	16.4 J	18.6	23.8	33.2 J	19.2 J	97.7	19.8
Cobalt	mg/Kg	NL	NL	12.7 J	11.5 J	10.2	11.1	10.6 J	11.8 J	3.5 J	11.7
Copper	mg/Kg	16	110	22 J	19.4 J	13.6 J	60.5 J	26.9 J	19.8 J	37 J	15.9 J
Iron	mg/Kg	20,000	40000	167000 J	136000 J	44600 J	29700 J	26900 J	26100 J	148000 J	28300 J
Lead	mg/Kg	31	110	33 J	28.2 J	15.5 J	334 J	75.4 J	28.9 J	20.3 J	31.8 J
Magnesium	mg/Kg	NL	NL	3410 J	3160 J	3740 J	3760 J	4140 J	4030 J	16200 J	4080 J
Manganese	mg/Kg	460	1100	927 J	913 J	521 J	876 J	733 J	1970 J	1010 J	1290 J
Mercury	mg/Kg	0.15	1.3	0.08 J	0.08 J	0.05 J	0.08 J	0.11 J	0.06 J	-	0.07 J
Nickel	mg/Kg	16	50	33.9 J	30.9 J	35 J	31 J	34.3 J	33 J	91.5 J	27.7 J
Potassium	mg/Kg	NL	NL	957 J	1040 J	1210	1230	1230 J	1210 J	143 J	1080
Silver	mg/Kg	1	2.2	-	-	-	-	-	-	2.4 J	-
Sodium	mg/Kg	NL	NL	186 J	182 J	142 J	349 J	250 J	162 J	1280	123 J
Vanadium	mg/Kg	NL	NL	18.4 J	17.2 J	21.6	24.1	23.5 J	20.9 J	3.8 J	19.3
Zinc	mg/Kg	120	270	581 J	500 J	290 J	1240 J	403 J	271 J	170 J	172 J
Total Cyanide	mg/Kg	NL	NL	-	-	-	0.71	-	-	3.8	-
TCLP METALS											
Barium	mg/L	100					1.8			0.63	
Cadmium	mg/L	1					0.013			0.0081	
Lead	mg/L	5					0.25			-	

Notes:

1. Lowest Effect Level (Sediment Screening Value for inorganics) and Severe Effect Level as published for inorganics in Table 2 of NYSDEC Department of Fish and Wildlife Technical Guidance for Screening Contaminated Sediments, 1999. TCLP criteria values from STARS Memo #1, 1992. See Table 1.4 for information on how Sediment Screening Values for organic contaminants were derived.

Highlighted values greater than screening value

mg/kg =milligrams per kilogram

mg/L = milligrams per liter

N = tentatively identified compound

NL = not listed

J = Estimated value

- = compound not detected

Prepared/Date:RTB 10/20/05

Checked/Date: MJS 10/20 05

SOIL DATA TABLES

TABLE 1

TEST PIT ANALYTICAL DATA SUMMARY

SOUTH HILL DUMP SITE VALIDATED TEST PIT SOIL/FILL SAMPLE RESULTS DETECTED COMPOUND SUMMARY	DUPLICATE OF TP1201											TP1201	TP1211
	SAMPLE ID:	CLEAN-UP	TP0101	TP0301	TP0501	TP0701	TP0801	TP1001	TP1101	TP1102	TP1201	TP1201	TP1211
	DEPTH:	OBJECTIVE	5'	3'	4'	8'	2'	15'	12'	4'	17'	17'	17'
	LAB ID:	TAGM No.	3066701	3066702	3066703	3067401	3067402	3067403	3067404	3067405	3069501	3069504	3069504
	SOURCE:	HWR-94-4046*	NYTEST	NYTEST	NYTEST	NYTEST	NYTEST	NYTEST	NYTEST	NYTEST	NYTEST	NYTEST	NYTEST
	SDG:	& TCLP	SHD1	SHD1	SHD1	SHD1	SHD1	SHD1	SHD1	SHD1	SHD1	SHD1	SHD1
	MATRIX:	SOIL	SOIL	SOIL	SOIL	SOIL	SOIL	SOIL	SOIL	SOIL	SOIL	SOIL	SOIL
	SAMPLED:		2/26/97	2/27/97	2/27/97	2/28/97	2/28/97	2/28/97	2/28/97	2/28/97	3/03/97	3/03/97	3/03/97
	VALIDATED:		7/25/97	7/25/97	7/25/97	7/25/97	7/25/97	7/25/97	7/25/97	7/25/97	7/25/97	7/25/97	7/25/97
	UNITS:												
COMPOUND													
VOLATILES													
Acetone	mg/Kg	0.20	-	-	-	-	-	-	-	-	-	-	-
Benzene	mg/Kg	0.06	-	-	-	-	-	-	-	-	-	-	-
2-Butanone	mg/Kg	0.30	-	-	-	-	-	-	-	-	-	-	-
Chlorobenzene	mg/Kg	1.70	-	-	-	-	-	-	-	-	-	-	-
1,2-Dichloroethene (total)	mg/Kg	0.30	-	-	-	-	-	-	0.00	J	-	-	-
Ethylbenzene	mg/Kg	5.50	-	-	-	-	0.01	J	-	-	-	-	-
4-Methyl-2-Pentanone	mg/Kg	1.00	-	-	-	-	-	-	-	-	-	-	-
Methylene Chloride	mg/Kg	0.10	-	-	-	-	-	-	-	-	-	-	-
Tetrachloroethene	mg/Kg	1.40	-	-	-	0.00	J	-	-	-	-	-	0.00 J
Toluene	mg/Kg	1.50	-	-	-	-	-	-	-	-	-	-	-
Trichloroethene	mg/Kg	0.70	-	0.00	J	-	-	-	0.02	-	-	-	0.00 J
Vinyl Chloride	mg/Kg	0.20	-	-	-	-	-	-	-	-	-	-	-
Xylene (total)	mg/Kg	1.20	-	-	-	-	0.00	J	-	-	-	-	0.00 J
SEMI-VOLATILES													
Acenaphthene	mg/Kg	50.00	-	0.07	J	-	-	-	-	-	0.05	J	-
Acenaphthylene	mg/Kg	41.00	0.15	J	-	-	-	-	-	-	-	-	-
Anthracene	mg/Kg	50.00	0.20	J	0.23	J	-	-	-	-	0.15	J	-
Benzo(a)anthracene	mg/Kg	0.224/MDL	0.76	0.40	J	-	0.10	J	-	0.12	J	0.19	J
Benzo(a)pyrene	mg/Kg	0.061/MDL	0.78	0.32	J	-	-	-	-	0.11	J	0.16	J
Benzo(b)fluoranthene	mg/Kg	1.10	0.84	0.30	J	-	-	-	-	-	-	-	-
Benzo(g,h,i)perylene	mg/Kg	50.00	0.16	J	0.06	J	-	-	-	-	0.08	J	-
Benzo(k)fluoranthene	mg/Kg	1.10	0.70	0.30	J	-	-	-	-	-	-	-	-
Butylbenzylphthalate	mg/Kg	50.00	-	-	-	-	0.45	J	4.10	J	-	0.05	J
Carbazole	mg/Kg		0.10	J	0.12	J	-	-	-	-	0.07	J	-
4-Chloroaniline	mg/Kg	0.220/MDL	-	-	-	-	-	-	-	-	-	-	-
Chrysene	mg/Kg	0.40	0.81	0.36	J	-	0.30	J	-	0.22	J	0.22	J
Di-n-butylphthalate	mg/Kg	8.10	-	-	-	-	1.00	-	0.41	J	-	-	-
Di-n-octylphthalate	mg/Kg	50.00	-	-	-	-	-	-	-	0.27	J	-	-
Dibenzofuran	mg/Kg	6.20	-	-	-	-	-	-	-	-	-	-	-
1,4-Dichlorobenzene	mg/Kg	-	-	-	-	-	-	-	-	-	-	-	-
Diethylphthalate	mg/Kg	7.10	-	-	-	-	-	0.31	J	-	-	-	-
Dimethylphthalate	mg/Kg	2.00	-	-	-	-	-	-	-	-	-	-	-
2,6-Dinitrotoluene	mg/Kg	1.00	-	-	-	-	-	-	-	-	-	-	-
Fluoranthene	mg/Kg	50.00	2.20	1.20	-	0.05	J	0.90	0.10	J	0.49	J	0.72 J
Fluorene	mg/Kg	50.00	0.06	J	0.08	J	-	-	-	-	-	0.11	J
Hexachlorocyclopentadiene	mg/Kg	-	-	-	-	-	-	-	-	-	-	-	-
Indeno(1,2,3-cd)pyrene	mg/Kg	3.20	0.32	J	0.11	J	-	-	-	-	0.10	J	-
2-Methylnaphthalene	mg/Kg	36.40	-	-	-	-	0.66	J	-	0.08	J	-	-
4-Methylphenol	mg/Kg	0.90	-	-	-	-	-	-	-	0.14	J	-	-
N-Nitrosodiphenylamine	mg/Kg	-	-	-	-	-	-	-	-	-	-	-	-
Naphthalene	mg/Kg	13.00	-	-	-	-	0.32	J	-	-	-	-	-
Pentachlorophenol	mg/Kg	1.0/MDL	-	-	-	-	-	-	-	-	-	-	-
Phenanthrene	mg/Kg	50.00	0.95	0.79	-	0.05	J	5.30	0.09	J	0.05	J	0.69 J
Phenol	mg/Kg	0.03/MDL	-	-	-	-	-	-	-	0.45	J	-	0.05 J
Pyrene	mg/Kg	50.00	1.00	0.52	-	-	0.88	-	-	0.50	J	0.46	J
1,2,4-Trichlorobenzene	mg/Kg	-	-	-	-	-	-	-	-	0.05	J	-	-
bis(2-Ethylhexyl)phthalate	mg/Kg	50.00	3.40	5.20	0.26	J	0.29	J	2.80	1.30	J	3.60	2.40

SOUTH HILL DUMP SITE VALIDATED TEST PIT SOIL/FILL SAMPLE RESULTS DETECTED COMPOUND SUMMARY	DUP of TP1201											
	SAMPLE ID:	CLEAN-UP	TP0101	TP0301	TP0501	TP0701	TP0801	TP1001	TP1101	TP1102	TP1201	TP1211
	DEPTH:	OBJECTIVE	5'	3'	4'	8'	2'	15'	12'	4'	17'	17'
	LAB ID:	TAGM No.	3066701	3066702	3066703	3067401	3067402	3067403	3067404	3067405	3069501	3069504
	SOURCE:	HWR-94-4046* & TCLP	NYTEST	NYTEST	NYTEST	NYTEST	NYTEST	NYTEST	NYTEST	NYTEST	NYTEST	NYTEST
	SDG:		SHD1	SHD1	SHD1	SHD1	SHD1	SHD1	SHD1	SHD1	SHD1	SHD1
	MATRIX:		SOIL	SOIL	SOIL	SOIL	SOIL	SOIL	SOIL	SOIL	SOIL	SOIL
	SAMPLED:		2/26/97	2/27/97	2/27/97	2/28/97	2/28/97	2/28/97	2/28/97	2/28/97	3/03/97	3/03/97
	VALIDATED:		7/25/97	7/25/97	7/25/97	7/25/97	7/25/97	7/25/97	7/25/97	7/25/97	7/25/97	7/25/97
	UNITS:											
COMPOUND												
PESTICIDES/PCBs												
alpha-BHC	mg/Kg	0.11	-	-	-	-	-	-	-	-	-	-
alpha-Chlordane	mg/Kg	0.54	-	-	-	-	-	0.02 JN	-	0.00 JN	-	-
beta-BHC	mg/Kg	0.20	-	-	-	-	-	-	-	-	-	-
delta-BHC	mg/Kg	0.30	-	-	-	-	-	-	-	-	-	-
gamma-BHC (Lindane)	mg/Kg	0.06	-	-	-	-	-	-	-	-	-	-
gamma-Chlordane	mg/Kg	0.54	-	-	-	-	-	0.02 JN	0.00 JN	0.00 JN	-	-
Aldrin	mg/Kg	0.04	-	-	-	-	-	-	-	-	-	-
4,4'-DDD	mg/Kg	2.90	0.01	0.00 J	-	-	-	0.06 JN	-	0.03 J	-	0.01 JN
4,4'-DDE	mg/Kg	2.10	0.00 J	-	0.01 JN	0.00 J	0.00 J	0.03 JN	0.03 J	0.02	-	0.00 J
4,4'-DDT	mg/Kg	2.10	0.00 JN	0.00 JN	0.00 JN	-	0.00 JN	0.02 JN	0.03 JN	0.06 JN	-	0.01 JN
Dieldrin	mg/Kg	0.04	-	-	-	-	-	-	-	0.00 J	-	0.00 JN
Endosulfan I	mg/Kg	0.90	-	-	0.00 JN	-	-	-	0.00 JN	-	-	-
Endosulfan II	mg/Kg	0.90	-	-	0.07	-	0.00 J	0.01 JN	0.01 JN	0.01 JN	-	-
Endosulfan sulfate	mg/Kg	1.00	-	-	-	-	-	-	0.01 JN	-	-	-
Endrin	mg/Kg	0.10	-	-	-	-	-	0.01 JN	-	0.00 JN	-	-
Endrin aldehyde	mg/Kg	-	-	-	0.01 JN	-	-	-	-	0.02 J	0.01 JN	0.00 JN
Endrin ketone	mg/Kg	-	-	-	-	-	-	-	-	-	-	-
Heptachlor	mg/Kg	0.10	-	-	-	-	-	-	-	-	-	-
Heptachlor epoxide	mg/Kg	0.02	-	-	-	-	-	-	-	-	-	0.00 J
Methoxychlor	mg/Kg	-	0.03	-	0.03	0.02	0.01 JN	-	0.02 JN	-	-	0.01 J
Toxaphene	mg/Kg	-	-	-	-	-	-	-	-	-	-	-
Aroclor-1016	mg/Kg	01/10	-	-	-	-	-	-	-	-	-	-
Aroclor-1221	mg/Kg	01/10	-	-	-	-	-	-	-	-	-	-
Aroclor-1232	mg/Kg	01/10	-	-	-	-	-	-	-	-	-	-
Aroclor-1242	mg/Kg	01/10	-	-	-	-	0.10	-	-	-	-	-
Aroclor-1248	mg/Kg	01/10	-	-	-	-	-	-	-	-	-	-
Aroclor-1254	mg/Kg	01/10	-	-	-	0.08	0.12	0.77 J	0.85	-	0.04 JN	0.13 J
Aroclor-1260	mg/Kg	01/10	-	-	2.80	-	-	0.57 J	-	0.44 J	-	-
INORGANICS												
Aluminum	mg/Kg	SB(33,000)	13500.00	12600.00	12100.00	13600.00	11200.00	8530.00	11000.00	17200.00	32900.00	26100
Antimony	mg/Kg	SB	2.10 J	17.20	2.20 J	2.60 J	2.80 J	21.90	5.40 J	2.00 J	24.00 J	16.40 J
Arsenic	mg/Kg	7.5/SB(3-12)	9.20	18.90	5.80	8.00	6.50	40.70	7.80	5.00	26.50	31.50
Barium	mg/Kg	300/SB(15-600)	181.00	528.00	138.00	137.00	69.50	146.00	111.00	82.80	673.00 J	904.00 J
Beryllium	mg/Kg	0.16/SB(0-1.75)	0.70 J	0.42 J	0.45 J	0.54 J	0.58 J	0.26 J	0.41 J	0.69	0.23 J	0.27 J
Cadmium	mg/Kg	1/SB(0.01-1)	1.70	49.80	6.30	1.20	1.50	6.50	1.70	-	12.80	18.10
Calcium	mg/Kg	SB(13-35,000)	6520.00	15600.00	18700.00	9630.00	18300.00	23100.00	33400.00	1060.00	34600.00	55900.00
Chromium	mg/Kg	10/SB(1.5-40)	25.10	75.20	27.20	28.80	38.00	103.00	20.10	23.60	63.20	102.00
Cobalt	mg/Kg	30/SB(2.5-60)	9.90	16.70	11.90	12.10	14.00	34.20	10.90	14.30	15.50	17.20
Copper	mg/Kg	25/SB(1-50)	52.00	396.00	65.50	89.50	95.60	224.00	95.20	23.30	1250.00	1820.00
Iron	mg/Kg	000/SB(2,000-500,000)	28100.00	141000.00	28900.00	43200.00	41200.00	569000.00	93000.00	31800.00	107000.00 J	105000.00 J
Lead	mg/Kg	SB(14)	180.00	814.00	140.00	240.00	291.00	934.00	189.00	11.40	2910.00 J	1470.00 J
Magnesium	mg/Kg	SB(100-5,000)	3500.00	4830.00	4460.00	5310.00	9510.00	4190.00	3920.00	5450.00	5250.00	6150.00
Manganese	mg/Kg	SB(50-5,000)	790.00	945.00	654.00	672.00	888.00	3490.00	740.00	527.00	588.00	777.00
Mercury	mg/Kg	0.10	0.12 J	0.11 J	0.53	-	-	0.79	0.15 J	-	0.21	0.15
Nickel	mg/Kg	13/SB(0.5-25)	24.20	62.10	35.10	31.70	30.60	117.00	27.40	185.00	178.00 J	249.00 J
Potassium	mg/Kg	SB(8,500-43,000)	1900.00	1330.00	1280.00	1180.00	1070.00	1020.00 J	1180.00	2190.00	4240.00 J	4950.00 J
Selenium	mg/Kg	2/SB(0.1-3.9)	1.00	0.92	-	-	-	1.10 J	1.50	-	-	-
Silver	mg/Kg	SB	0.49 J	7.00	1.00 J	0.60 J	0.32 J	-	0.81 J	0.46 J	6.80	10.30
Sodium	mg/Kg	SB(6,000-8,000)	389.00 J	611.00	374.00 J	361.00 J	355.00 J	963.00 J	866.00	295.00 J	2270.00	2440.00
Thallium	mg/Kg	SB	-	-	-	-	-	-	-	-	-	-
Vanadium	mg/Kg	150/SB(1-300)	21.80	25.10	54.80	20.00	25.20	24.60	19.10	22.90	27.30	26.5
Zinc	mg/Kg	20/SB(9-50)	396.00	1610.00	446.00	281.00	216.00	2830.00	327.00	150.00	2380.00	2320.00
Total Cyanide	mg/Kg	-	-	-	-	-	-	-	-	-	-	-

SOUTH HILL DUMP SITE VALIDATED TEST PIT SOIL/FILL SAMPLE RESULTS DETECTED COMPOUND SUMMARY	DUP of TP1201										
	SAMPLE ID:	CLEAN-UP	TP0101	TP0301	TP0501	TP0701	TP0801	TP1001	TP1101	TP1102	TP1201
	DEPTH:	OBJECTIVE	5'	3'	4'	8'	2'	15'	12'	4'	17'
	LAB ID:	TAGM No.	3066701	3066702	3066703	3067401	3067402	3067403	3067404	3067405	3069501
	SOURCE:	HWR-94-4046*	NYTEST	NYTEST	NYTEST	NYTEST	NYTEST	NYTEST	NYTEST	NYTEST	NYTEST
	SDG:	& TCLP	SHD1	SHD1	SHD1	SHD1	SHD1	SHD1	SHD1	SHD1	SHD1
	MATRIX:		SOIL	SOIL	SOIL	SOIL	SOIL	SOIL	SOIL	SOIL	SOIL
	SAMPLED:		2/26/97	2/27/97	2/27/97	2/28/97	2/28/97	2/28/97	2/28/97	2/28/97	3/03/97
	VALIDATED:		7/25/97	7/25/97	7/25/97	7/25/97	7/25/97	7/25/97	7/25/97	7/25/97	7/25/97
	UNITS:										
COMPOUND											
TCLP VOLATILES											
Tetrachloroethene	mg/L	0.70							-		
Trichloroethene	mg/L	0.50							-		
TCLP SEMIVOLATILES											
3+4-Methylphenol	mg/L								-		
TCLP PESTICIDES											
NONE	mg/L								-		
TCLP HERBICIDES											
NONE	mg/L								-		
TCLP METALS											
Arsenic	mg/L	5.00							0.31	J	
Barium	mg/L	100.00							1.80		
Cadmium	mg/L	1.00							0.05	J	
Lead	mg/L	5.00							1.10		
Silver	mg/L	5.00							0.06	J	

* Numbers in parentheses represent average background concentrations
for Eastern US soils. Site Background (SB) information is not available.

SOUTH HILL DUMP SITE VALIDATED TEST PIT SOIL/FILL SAMPLE RESULTS DETECTED COMPOUND SUMMARY	DUP of TP2701														
	SAMPLE ID:	CLEAN-UP	TP1601	TP1801	TP1901	TP1902	TP2101	TP2701	TP2711	TP3001	TP3201				
	DEPTH:	OBJECTIVE	5'	8'	10'	10'	3'	10'	10'	4'	1'				
	LAB ID:	TAGM No.	3069505	3072001	3072002	3072003	3072006	3076001	3076004	3076005	3076006				
	SOURCE:	HWR-94-4046*	NYTEST	NYTEST	NYTEST	NYTEST	NYTEST	NYTEST	NYTEST	NYTEST	NYTEST				
	SDG:	& TCLP	SHD1	SHD2	SHD2	SHD2	SHD2	SHD2	SHD2	SHD2	SHD2				
	MATRIX:		SOIL	SOIL	SOIL	SOIL	SOIL	SOIL	SOIL	SOIL	SOIL				
SAMPLED:		3/04/97	3/05/97	3/05/97	3/05/97	3/06/97	3/10/97	3/10/97	3/11/97	3/11/97					
VALIDATED:		7/25/97	7/25/97	7/25/97	7/25/97	7/25/97	7/25/97	7/25/97	7/25/97	7/25/97					
UNITS:															
COMPOUND															
VOLATILES															
Acetone	mg/Kg	0.20	-	0.03	-	0.02	-	-	-	0.03	J	0.01	J		
Benzene	mg/Kg	0.06	-	-	-	-	-	-	-	0.00	J	-	-		
2-Butanone	mg/Kg	0.30	0.02	-	-	-	-	-	-	-	-	-	-		
Chlorobenzene	mg/Kg	1.70	-	0.01	J	-	-	-	-	-	-	-	-		
1,2-Dichloroethene (total)	mg/Kg	0.30	-	-	-	0.01	J	-	-	-	-	-	-		
Ethylbenzene	mg/Kg	5.50	0.28	J	0.07	0.00	J	0.01	J	-	0.09	J	0.00	J	
4-Methyl-2-Pentanone	mg/Kg	1.00	-	-	-	-	-	-	-	-	-	-	-		
Methylene Chloride	mg/Kg	0.10	-	0.00	J	0.00	J	0.00	J	0.01	J	0.02	J	0.01	J
Tetrachloroethene	mg/Kg	1.40	0.01	J	0.00	J	0.01	J	0.00	J	-	0.01	J	-	-
Toluene	mg/Kg	1.50	0.01	-	-	-	-	0.22	J	-	-	-	-	0.00	J
Trichloroethene	mg/Kg	0.70	-	-	-	0.00	J	0.04	-	0.01	J	0.01	J	-	-
Vinyl Chloride	mg/Kg	0.20	-	-	-	-	-	-	-	-	-	-	-	-	-
Xylene (total)	mg/Kg	1.20	0.21	0.27	-	0.02	0.03	-	-	-	0.08	J	0.01	J	-
SEMIVOLATILES															
Acenaphthene	mg/Kg	50.00	2.20	-	-	-	-	-	-	-	-	-	-	-	-
Acenaphthylene	mg/Kg	41.00	-	0.05	J	-	-	-	-	-	-	-	-	-	-
Anthracene	mg/Kg	50.00	0.72	-	-	-	-	-	-	-	-	-	-	-	-
Benzo(a)anthracene	mg/Kg	0.224/MDL	0.22	J	0.17	J	-	-	-	-	-	-	-	-	-
Benzo(a)pyrene	mg/Kg	0.061/MDL	0.17	J	0.21	J	-	-	-	-	-	-	-	-	-
Benzo(b)fluoranthene	mg/Kg	1.10	-	0.20	J	-	-	-	-	-	-	-	-	-	-
Benzo(g,h,i)perylene	mg/Kg	50.00	-	0.16	J	-	-	-	-	-	-	-	-	-	-
Benzo(k)fluoranthene	mg/Kg	1.10	-	0.21	J	-	-	-	-	-	-	-	-	-	-
Butylbenzylphthalate	mg/Kg	50.00	1.10	1.20	-	-	-	-	-	-	-	-	-	-	-
Carbazole	mg/Kg		-	-	-	-	-	-	-	-	-	-	-	-	-
4-Chloroaniline	mg/Kg	0.220/MDL	-	-	-	-	-	-	-	-	-	-	-	-	-
Chrysene	mg/Kg	0.40	0.31	J	0.31	J	-	-	-	-	0.27	J	-	-	-
Di-n-butylphthalate	mg/Kg	8.10	-	-	-	-	-	0.26	J	0.54	J	1.00	J	-	-
Di-n-octylphthalate	mg/Kg	50.00	0.22	J	-	-	-	-	-	-	-	-	-	-	-
Dibenzofuran	mg/Kg	6.20	1.60	-	-	-	-	-	-	-	-	-	-	-	-
1,4-Dichlorobenzene	mg/Kg		-	0.33	J	-	-	-	-	-	-	-	-	-	-
Diethylphthalate	mg/Kg	7.10	-	-	-	-	-	-	-	-	-	-	-	-	-
Dimethylphthalate	mg/Kg	2.00	-	0.10	J	-	-	-	-	-	0.20	J	-	-	-
2,6-Dinitrotoluene	mg/Kg	1.00	-	-	-	-	-	-	-	-	0.29	J	-	-	-
Fluoranthene	mg/Kg	50.00	0.67	-	-	-	-	0.18	J	-	1.50	J	-	-	-
Fluorene	mg/Kg	50.00	2.80	0.05	J	-	-	0.12	J	-	0.22	J	-	-	-
Hexachlorocyclopentadiene	mg/Kg		-	-	-	-	-	-	-	-	-	-	-	-	-
Indeno(1,2,3-cd)pyrene	mg/Kg	3.20	0.05	J	0.14	J	-	-	-	-	-	-	-	-	-
2-Methylnaphthalene	mg/Kg	36.40	34.00	0.30	J	-	-	0.07	J	-	1.20	J	-	-	-
4-Methylphenol	mg/Kg	0.90	0.68	-	-	-	-	-	-	-	0.21	J	0.04	J	-
N-Nitrosodiphenylamine	mg/Kg		-	-	-	-	-	-	-	-	0.72	J	-	-	-
Naphthalene	mg/Kg	13.00	7.00	0.40	J	-	-	0.16	J	-	1.10	J	-	-	-
Pentachlorophenol	mg/Kg	1.0/MDL	-	-	-	-	-	-	-	-	-	-	-	-	-
Phenanthrene	mg/Kg	50.00	6.90	-	-	-	-	0.34	J	-	1.00	J	-	-	-
Phenol	mg/Kg	0.03/MDL	-	1.40	-	-	-	-	-	-	-	-	-	-	-
Pyrene	mg/Kg	50.00	0.75	0.25	J	-	-	0.09	J	-	0.58	J	-	-	-
1,2,4-Trichlorobenzene	mg/Kg		-	-	-	-	-	-	-	-	0.14	J	-	-	-
bis(2-Ethylhexyl)phthalate	mg/Kg	50.00	4.00	J	28.00	J	-	-	-	-	23.00	J	-	-	-

DUP of TP2701											
SOUTH HILL DUMP SITE VALIDATED TEST PIT SOIL/FILL SAMPLE RESULTS DETECTED COMPOUND SUMMARY	SAMPLE ID: DEPTH: LAB ID: SOURCE: SDG: MATRIX: SAMPLED: VALIDATED: UNITS:	CLEAN-UP OBJECTIVE TAGM No. HWR-94-4046* & TCLP	TP1601 5' 3069505 NYTEST SHD1 SOIL 3/04/97 7/25/97	TP1801 8' 3072001 NYTEST SHD2 SOIL 3/05/97 7/25/97	TP1901 10' 3072002 NYTEST SHD2 SOIL 3/05/97 7/25/97	TP1902 10' 3072003 NYTEST SHD2 SOIL 3/05/97 7/25/97	TP2101 3' 3072006 NYTEST SHD2 SOIL 3/06/97 7/25/97	TP2701 10' 3076001 NYTEST SHD2 SOIL 3/10/97 7/25/97	TP2711 10' 3076004 NYTEST SHD2 SOIL 3/10/97 7/25/97	TP3001 4' 3076005 NYTEST SHD2 SOIL 3/11/97 7/25/97	TP3201 1' 3076006 NYTEST SHD2 SOIL 3/11/97 7/25/97
COMPOUND											
PESTICIDES/PCBs											
alpha-BHC	mg/Kg	0.11	-	R	-	-	-	-	-	-	-
alpha-Chlordane	mg/Kg	0.54	-	0.00 JN	-	-	-	-	-	0.01 JN	-
beta-BHC	mg/Kg	0.20	-	R	-	-	-	-	-	-	-
delta-BHC	mg/Kg	0.30	-	R	-	-	-	-	-	-	-
gamma-BHC (Lindane)	mg/Kg	0.06	-	R	-	-	-	-	-	-	-
gamma-Chlordane	mg/Kg	0.54	-	0.00 JN	-	-	-	-	-	0.01 JN	0.01 J
Aldrin	mg/Kg	0.04	-	R	-	-	-	-	-	-	-
4,4'-DDD	mg/Kg	2.90	0.01	0.07 J	-	0.00 JN	0.00 J	-	-	0.11 JN	0.00 JN
4,4'-DDE	mg/Kg	2.10	-	R	-	-	0.00 J	-	-	0.03 J	0.01 JN
4,4'-DDT	mg/Kg	2.10	0.00 JN	R	-	0.00 JN	-	0.00 JN	-	0.02 JN	-
Dieldrin	mg/Kg	0.04	0.00 JN	R	-	-	-	0.00	-	0.01 J	-
Endosulfan I	mg/Kg	0.90	-	R	-	-	-	-	-	-	0.00 JN
Endosulfan II	mg/Kg	0.90	-	R	-	-	-	-	-	-	-
Endosulfan sulfate	mg/Kg	1.00	-	R	-	-	-	-	-	0.01 J	0.01 JN
Endrin	mg/Kg	0.10	-	R	-	-	-	-	-	-	0.00 JN
Endrin aldehyde	mg/Kg	-	0.00 JN	0.00 JN	-	0.00 J	-	0.00 JN	-	-	-
Endrin ketone	mg/Kg	-	-	R	-	-	-	-	-	-	-
Heptachlor	mg/Kg	0.10	-	R	-	-	-	-	-	0.00 JN	0.01 JN
Heptachlor epoxide	mg/Kg	0.02	-	R	-	-	-	-	-	-	-
Methoxychlor	mg/Kg	-	-	R	-	-	-	-	-	-	-
Toxaphene	mg/Kg	-	-	R	-	-	-	-	-	-	-
Aroclor-1016	mg/Kg	01/10	-	R	-	-	-	-	-	0.71 J	-
Aroclor-1221	mg/Kg	01/10	-	R	-	-	-	-	-	-	-
Aroclor-1232	mg/Kg	01/10	-	R	-	-	-	-	-	-	-
Aroclor-1242	mg/Kg	01/10	0.35	R	-	-	-	-	-	-	-
Aroclor-1248	mg/Kg	01/10	-	R	-	-	-	-	-	-	4.00
Aroclor-1254	mg/Kg	01/10	0.09	0.05 J	-	0.05	-	0.04 J	0.03 J	0.59 J	-
Aroclor-1260	mg/Kg	01/10	-	R	-	-	0.04 J	-	-	0.67 J	-
INORGANICS											
Aluminum	mg/Kg	SB(33,000)	6610.00	14800.00	22000.00	17500.00	15800.00	12900.00	13000.00	6990 J	14600.00
Antimony	mg/Kg	SB	5.90 J	3.10 J	6.70 J	5.40 J	1.70 J	4.50 J	1.90 J	9.00 J	1.70 J
Arsenic	mg/Kg	7.5/SB(3-12)	4.80	14.20	16.20	11.70	7.70	8.50	7.20	18.20 J	5.80
Barium	mg/Kg	300/SB(15-600)	45.60 J	116.00	424.00	214.00	81.60	83.90	84.20	270.00 J	96.50
Beryllium	mg/Kg	0.16/SB(0-1.75)	0.10 J	0.39 J	0.42 J	0.32 J	0.35 J	0.31 J	0.30 J	-	0.37 J
Cadmium	mg/Kg	1/SB(0.01-1)	0.26 J	1.60	39.90	19.00	1.90	6.10	3.10	4.70 J	-
Calcium	mg/Kg	SB(13-35,000)	7280.00	8060.00	26900.00	14700.00	2010.00	17900.00 J	61900.00 J	23200.00 J	784.00
Chromium	mg/Kg	10/SB(1.5-40)	11.80	38.20	70.70	55.20	39.40	114.00 J	52.90 J	121.00 J	19.60
Cobalt	mg/Kg	30/SB(2.5-60)	6.00 J	12.00	16.30	19.90	14.20	12.70	9.10	33.40 J	11.70
Copper	mg/Kg	25/SB(1-50)	11.90	34.20	718.00	346.00	77.60	227.00 J	114.00 J	134.00 J	19.70
Iron	mg/Kg	000/SB(2,000-500,000)	17100.00 J	44800.00 J	112000.00 J	89200.00 J	37400.00 J	71800.00 J	42600.00 J	298000.00 J	26000.00 J
Lead	mg/Kg	SB(14)	117.00 J	135.00	1410.00	759.00	90.30	801.00 J	371.00 J	417.00 J	17.90
Magnesium	mg/Kg	SB(100-5,000)	3090.00	5000.00	9130.00	6410.00	4580.00	5930.00	8520.00	1650.00 J	4570.00
Manganese	mg/Kg	SB(50-5,000)	304.00	533.00	931.00	917.00	601.00	617.00	598.00	1850.00 J	336.00
Mercury	mg/Kg	0.10	-	0.16	0.07 J	0.18	0.07 J	0.11 J	-	0.24 J	-
Nickel	mg/Kg	13/SB(0.5-25)	15.30 J	31.80	176.00	114.00	54.80	63.60 J	35.90 J	218.00 J	29.10
Potassium	mg/Kg	SB(8,500-43,000)	519.00 J	1530.00	4850.00	2360.00	1780.00	2020.00	2330.00	1140.00 J	1200.00
Selenium	mg/Kg	2/SB(0.1-3.9)	-	-	-	-	-	-	-	-	-
Silver	mg/Kg	SB	13.60	0.37 J	5.40	193.00	2.30	0.98 J	0.52 J	-	0.29 J
Sodium	mg/Kg	SB(6,000-8,000)	608.00 J	315.00 J	1890.00	874.00	457.00 J	508.00 J	551.00 J	1690.00 J	208.00 J
Thallium	mg/Kg	SB	-	-	-	-	-	-	-	-	-
Vanadium	mg/Kg	150/SB(1-300)	10.80	23.90	33.40	24.20	22.90	23.80	22.60	19.00 J	19.20
Zinc	mg/Kg	20/SB(9-50)	109.00	368.00	3590.00	1580.00	252.00	683.00	488.00	4130.00 J	138.00
Total Cyanide	mg/Kg	-	-	-	0.73	-	-	0.80 J	-	-	-

DUP of TP2701											
SOUTH HILL DUMP SITE VALIDATED TEST PIT SOIL/FILL SAMPLE RESULTS DETECTED COMPOUND SUMMARY	SAMPLE ID:	CLEAN-UP	TP1601	TP1801	TP1901	TP1902	TP2101	TP2701	TP2711	TP3001	TP3201
	DEPTH:	OBJECTIVE	5'	8'	10'	10'	3'	10'	10'	4'	1'
	LAB ID:	TAGM No.	3069505	3072001	3072002	3072003	3072006	3076001	3076004	3076005	3076006
	SOURCE:	HWR-94-4046*	NYTEST	NYTEST	NYTEST	NYTEST	NYTEST	NYTEST	NYTEST	NYTEST	NYTEST
	SDG:	& TCLP	SHD1	SHD2	SHD2	SHD2	SHD2	SHD2	SHD2	SHD2	SHD2
	MATRIX:		SOIL	SOIL	SOIL	SOIL	SOIL	SOIL	SOIL	SOIL	SOIL
COMPOUND	SAMPLED:		3/04/97	3/05/97	3/05/97	3/05/97	3/06/97	3/10/97	3/10/97	3/11/97	3/11/97
	VALIDATED:		7/25/97	7/25/97	7/25/97	7/25/97	7/25/97	7/25/97	7/25/97	7/25/97	7/25/97
	UNITS:										
TCLP VOLATILES											
	Tetrachloroethene	mg/L	0.70								
	Trichloroethene	mg/L	0.50								
TCLP SEMIVOLATILES											
	3+4-Methylphenol	mg/L									
TCLP PESTICIDES											
	NONE	mg/L									
TCLP HERBICIDES											
	NONE	mg/L									
TCLP METALS											
	Arsenic	mg/L	5.00								
	Barium	mg/L	100.00								
	Cadmium	mg/L	1.00								
	Lead	mg/L	5.00								
	Silver	mg/L	5.00								

* Numbers in parentheses represent average background concentrations for Eastern US soils. Site Background (SB) information is not available.

SOUTH HILL DUMP SITE VALIDATED TEST PIT SOIL/FILL SAMPLE RESULTS DETECTED COMPOUND SUMMARY	DUP of TP3901									
	SAMPLE ID:	CLEAN-UP	TP3601	TP3602	TP3801	TP3901	TP3911	TP4001	TP4301	TP4601
	DEPTH:	OBJECTIVE	2'	3'	2'	1'	1'	4'	6'	2'
	LAB ID:	TAGM No.	3076801	3076802	3078701	3079701	3079704	3079705	3082302	3082303
	SOURCE:	HWR-94-4046*	NYTEST	NYTEST	NYTEST	NYTEST	NYTEST	NYTEST	NYTEST	NYTEST
	SDG:	& TCLP	SHD2	SHD2	SHD3	SHD3	SHD3	SHD3	SHD3	SHD3
	MATRIX:	SOIL	SOIL	SOIL	SOIL	SOIL	SOIL	SOIL	SOIL	SOIL
COMPOUND	SAMPLED:	3/12/97	3/12/97	3/13/97	3/17/97	3/17/97	3/17/97	3/17/97	3/18/97	3/19/97
	VALIDATED:	7/25/97	7/25/97	7/25/97	7/25/97	7/25/97	7/25/97	7/25/97	7/25/97	7/25/97
UNITS:										
VOLATILES										
Acetone	mg/Kg	0.20	-	-	0.01	J	-	0.00	J	0.02
Benzene	mg/Kg	0.06	-	-	-	-	-	-	-	-
2-Butanone	mg/Kg	0.30	-	-	-	-	-	-	-	0.00
Chlorobenzene	mg/Kg	1.70	-	-	-	-	-	-	-	J
1,2-Dichloroethene (total)	mg/Kg	0.30	-	-	-	-	-	0.13	-	-
Ethylbenzene	mg/Kg	5.50	-	-	-	-	-	0.01	J	-
4-Methyl-2-Pentanone	mg/Kg	1.00	-	-	-	-	-	-	-	-
Methylene Chloride	mg/Kg	0.10	0.01	J	0.01	J	-	-	-	-
Tetrachloroethene	mg/Kg	1.40	-	-	-	-	-	-	-	-
Toluene	mg/Kg	1.50	-	-	-	-	-	0.01	J	-
Trichloroethene	mg/Kg	0.70	-	-	0.00	J	0.02	J	0.03	-
Vinyl Chloride	mg/Kg	0.20	-	-	-	-	-	0.04	J	-
Xylene (total)	mg/Kg	1.20	-	-	-	-	-	0.00	J	-
SEMIVOLATILES										
Acenaphthene	mg/Kg	50.00	-	-	-	0.07	J	-	-	-
Acenaphthylene	mg/Kg	41.00	-	-	-	-	-	-	-	-
Anthracene	mg/Kg	50.00	-	-	-	0.09	J	0.05	J	-
Benzo(a)anthracene	mg/Kg	0.224/MDL	-	-	-	0.40	J	0.19	J	-
Benzo(a)pyrene	mg/Kg	0.061/MDL	-	-	-	0.30	J	0.16	J	-
Benzo(b)fluoranthene	mg/Kg	1.10	-	-	-	0.29	J	0.22	J	-
Benzo(g,h,i)perylene	mg/Kg	50.00	-	-	-	0.13	J	0.09	J	-
Benzo(k)fluoranthene	mg/Kg	1.10	-	-	-	0.29	J	0.14	J	-
Butylbenzylphthalate	mg/Kg	50.00	-	-	-	-	-	0.08	JN	-
Carbazole	mg/Kg	-	-	-	-	0.09	J	-	-	-
4-Chloroaniline	mg/Kg	0.220/MDL	-	-	-	-	R	R	R	R
Chrysene	mg/Kg	0.40	-	-	-	0.58	J	0.26	J	-
Di-n-butylphthalate	mg/Kg	8.10	-	-	-	-	-	0.18	J	-
Di-n-octylphthalate	mg/Kg	50.00	-	-	-	-	-	-	-	-
Dibenzofuran	mg/Kg	6.20	-	-	-	0.05	J	-	-	-
1,4-Dichlorobenzene	mg/Kg	-	-	-	-	-	-	-	-	-
Diethylphthalate	mg/Kg	7.10	-	-	-	-	-	-	-	-
Dimethylphthalate	mg/Kg	2.00	-	-	-	-	-	-	-	-
2,6-Dinitrotoluene	mg/Kg	1.00	-	-	-	-	-	-	-	-
Fluoranthene	mg/Kg	50.00	-	-	-	0.84	J	0.39	J	-
Fluorene	mg/Kg	50.00	-	-	-	0.06	J	-	-	-
Hexachlorocyclopentadiene	mg/Kg	-	-	-	-	-	-	-	-	-
Indeno(1,2,3-cd)pyrene	mg/Kg	3.20	-	-	-	0.15	J	0.09	J	-
2-Methylnaphthalene	mg/Kg	36.40	-	-	-	-	-	-	-	-
4-Methylphenol	mg/Kg	0.90	-	-	-	-	-	-	-	-
N-Nitrosodiphenylamine	mg/Kg	-	-	-	-	-	-	1.40	-	-
Naphthalene	mg/Kg	13.00	-	-	-	0.05	J	-	-	-
Pentachlorophenol	mg/Kg	1.0/MDL	-	-	-	-	-	-	-	-
Phenanthrene	mg/Kg	50.00	-	-	-	0.65	J	0.32	J	-
Phenol	mg/Kg	0.03/MDL	-	-	0.25	J	-	-	-	-
Pyrene	mg/Kg	50.00	-	-	-	0.75	J	0.31	J	-
1,2,4-Trichlorobenzene	mg/Kg	-	-	-	-	-	-	-	-	-
bis(2-Ethylhexyl)phthalate	mg/Kg	50.00	-	-	1.50	-	-	1.30	-	-

DUP of TP3901										
SOUTH HILL DUMP SITE VALIDATED TEST PIT SOIL/FILL SAMPLE RESULTS DETECTED COMPOUND SUMMARY	SAMPLE ID: DEPTH: LAB ID: SOURCE: SDG: MATRIX: SAMPLED: VALIDATED: UNITS:	CLEAN-UP OBJECTIVE TAGM No. HWR-94-4046* & TCLP	TP3601 2' 3076801 NYTEST SHD2 SOIL 3/12/97 7/25/97	TP3602 3' 3076802 NYTEST SHD2 SOIL 3/12/97 7/25/97	TP3801 2' 3078701 NYTEST SHD3 SOIL 3/13/97 7/25/97	TP3901 1' 3079701 NYTEST SHD3 SOIL 3/17/97 7/25/97	TP3911 1' 3079704 NYTEST SHD3 SOIL 3/17/97 7/25/97	TP4001 4' 3079705 NYTEST SHD3 SOIL 3/17/97 7/25/97	TP4301 6' 3082302 NYTEST SHD3 SOIL 3/18/97 7/25/97	TP4601 2' 3082303 NYTEST SHD3 SOIL 3/19/97 7/25/97
COMPOUND										
PESTICIDES/PCBs										
alpha-BHC	mg/Kg	0.11	-	-	-	-	-	-	-	-
alpha-Chlordane	mg/Kg	0.54	-	-	-	-	-	-	-	-
beta-BHC	mg/Kg	0.20	-	-	-	-	-	-	-	-
delta-BHC	mg/Kg	0.30	-	-	-	-	-	-	-	-
gamma-BHC (Lindane)	mg/Kg	0.06	-	-	-	-	-	-	-	-
gamma-Chlordane	mg/Kg	0.54	-	-	-	-	-	-	-	-
Aldrin	mg/Kg	0.04	-	-	-	-	-	-	-	-
4,4'-DDD	mg/Kg	2.90	-	-	-	-	-	-	-	-
4,4'-DDE	mg/Kg	2.10	-	-	-	0.00 JN	0.00 J	-	-	-
4,4'-DDT	mg/Kg	2.10	-	-	.0033 J	0.02 JN	0.02 J	0.01 J	-	-
Dieldrin	mg/Kg	0.04	-	-	-	-	-	-	-	-
Endosulfan I	mg/Kg	0.90	-	-	-	-	-	-	-	-
Endosulfan II	mg/Kg	0.90	-	-	-	-	-	-	-	-
Endosulfan sulfate	mg/Kg	1.00	-	-	-	-	-	-	-	-
Endrin	mg/Kg	0.10	-	-	-	-	-	-	-	-
Endrin aldehyde	mg/Kg	-	-	-	-	-	-	-	-	-
Endrin ketone	mg/Kg	-	-	-	-	0.00 J	-	-	-	-
Heptachlor	mg/Kg	0.10	-	-	-	-	-	0.00 J	-	-
Heptachlor epoxide	mg/Kg	0.02	-	-	-	-	-	-	-	-
Methoxychlor	mg/Kg	-	-	-	-	-	-	-	-	-
Toxaphene	mg/Kg	-	-	-	-	-	-	-	-	-
Aroclor-1016	mg/Kg	01/10	-	-	-	-	-	-	-	-
Aroclor-1221	mg/Kg	01/10	-	-	-	-	-	-	-	-
Aroclor-1232	mg/Kg	01/10	-	-	-	-	-	-	-	-
Aroclor-1242	mg/Kg	01/10	-	-	-	-	-	-	-	-
Aroclor-1248	mg/Kg	01/10	-	-	-	-	-	-	-	-
Aroclor-1254	mg/Kg	01/10	-	-	-	0.04	0.03 J	-	-	-
Aroclor-1260	mg/Kg	01/10	-	-	0.03 J	-	-	-	-	-
INORGANICS										
Aluminum	mg/Kg	SB(33,000)	15700.00	12800.00	9960.00	11500.00 J	395.00 J	10500.00	14500.00	16200.00
Antimony	mg/Kg	SB	2.10 J	2.00 J	1.70 J	1.80 J	21.90 J	2.60 J	2.00 J	2.50 J
Arsenic	mg/Kg	7.5/SB(3-12)	7.80	7.10	7.90 J	10.90 J	6.50	8.20	6.00	6.70
Barium	mg/Kg	300/SB(15-600)	77.70	83.30	155.00	298.00 J	12.70 J	109.00	117.00	131.00
Beryllium	mg/Kg	0.16/SB(0-1.75)	0.46 J	0.41 J	0.43 J	0.37 J	-	0.32 J	0.45 J	0.50 J
Cadmium	mg/Kg	1/SB(0.01-1)	-	-	-	1.80 J	-	0.39 J	-	-
Calcium	mg/Kg	SB(13-35,000)	688.00	735.00	1220.00	11500.00 J	3900.00 J	1250.00	924.00	1030.00
Chromium	mg/Kg	10/SB(1.5-40)	21.20	18.00	13.40 J	19.00 J	435.00 J	15.20 J	27.30 J	30.50 J
Cobalt	mg/Kg	30/SB(2.5-60)	13.00	10.30	8.70 J	9.80 J	3.90 J	9.60 J	12.60 J	14.00 J
Copper	mg/Kg	25/SB(1-50)	17.60	17.60	17.30 J	87.00 J	12.50 J	24.20 J	11.80 J	13.30 J
Iron	mg/Kg	000/SB(2,000-500,000)	85300.00 J	25800.00 J	22900.00	24900.00 J	6350.00 J	27900.00	26800.00	29900.00
Lead	mg/Kg	SB(14)	7.50	10.80	9.30	700.00 J	14.60 J	52.10	8.40	9.50
Magnesium	mg/Kg	SB(100-5,000)	5600.00	4090.00	3420.00	4070.00 J	461.00 J	3270.00	3910.00	4360.00
Manganese	mg/Kg	SB(50-5,000)	529.00	493.00	692	646.00 J	2610.00 J	477.00	1330.00 J	1480.00
Mercury	mg/Kg	0.10	-	-	-	0.20	0.18	-	-	-
Nickel	mg/Kg	13/SB(0.5-25)	30.10	23.70	22.50	25.90 J	194.00 J	36.40	24.60	27.30
Potassium	mg/Kg	SB(8,500-43,000)	1780.00	1790.00	1290.00	1190.00 J	535.00 J	1260.00	1320.00	1470.00
Selenium	mg/Kg	2/SB(0.1-3.9)	-	-	-	-	-	-	-	-
Silver	mg/Kg	SB	-	-	-	0.73 J	3.30 J	-	-	-
Sodium	mg/Kg	SB(6,000-8,000)	185.00 J	200.00 J	345.00 J	664.00 J	-	684.00 J	457.00 J	475.00 J
Thallium	mg/Kg	SB	-	-	0.72 J	0.84 J	-	-	2.10 J	1.40 J
Vanadium	mg/Kg	150/SB(1-300)	20.30	18.00	14.1	30.20 J	10.10 J	16.00	21.10	23.60
Zinc	mg/Kg	20/SB(9-50)	62.10	54.10	50.70	1060.00 J	28.10 J	1270.00	70.50	78.60
Total Cyanide	mg/Kg	-	-	-	-	3.01 J	0.84 J	1.34	-	-

DUP of TP3901										
SOUTH HILL DUMP SITE VALIDATED TEST PIT SOIL/FILL SAMPLE RESULTS DETECTED COMPOUND SUMMAR COMPOUND TCLP VOLATILES Tetrachloroethene Trichloroethene TCLP SEMIVOLATILES 3+4-Methylphenol TCLP PESTICIDES NONE TCLP HERBICIDES NONE TCLP METALS Arsenic Barium Cadmium Lead Silver	SAMPLE ID:	CLEAN-UP	TP3601	TP3602	TP3801	TP3901	TP3911	TP4001	TP4301	TP4601
	DEPTH:	OBJECTIVE	2'	3'	2'	1'	1'	4'	6'	2'
	LAB ID:	TAGM No.	3076801	3076802	3078701	3079701	3079704	3079705	3082302	3082303
	SOURCE:	HWR-94-4046*	NYTEST	NYTEST	NYTEST	NYTEST	NYTEST	NYTEST	NYTEST	NYTEST
	SDG:	& TCLP	SHD2	SHD2	SHD3	SHD3	SHD3	SHD3	SHD3	SHD3
	MATRIX:		SOIL	SOIL	SOIL	SOIL	SOIL	SOIL	SOIL	SOIL
	SAMPLED:		3/12/97	3/12/97	3/13/97	3/17/97	3/17/97	3/17/97	3/18/97	3/19/97
	VALIDATED:		7/25/97	7/25/97	7/25/97	7/25/97	7/25/97	7/25/97	7/25/97	7/25/97
	UNITS:									
	mg/L	0.70								
	mg/L	0.50								
	mg/L									
	mg/L									
	mg/L									
	mg/L									
	mg/L	5.00								
	mg/L	100.00								
	mg/L	1.00								
	mg/L	5.00								
	mg/L	5.00								

* Numbers in parentheses represent average background concentrations
for Eastern US soils. Site Background (SB) information is not available.

TABLE 4
SOIL BORING ANALYTICAL DATA SUMMARY

SOUTH HILL DUMP SITE VALIDATED SOIL BORING RESULTS DETECTED COMPOUND SUMMARY		DUP of MW3E					
COMPOUND	SAMPLE ID: DEPTH: LAB ID: SOURCE: SDG: MATRIX: SAMPLED: VALIDATED: UNITS:	CLEAN-UP OBJECTIVE TAGM No. HWR-94-4046	MW2N 20-28' 3091101 NYTEST SHD5 SOIL 3/28/97 7/25/97	MW3E 2-8' 3096801 NYTEST SHD6 SOIL 4/03/97 7/25/97	MW3D 2-8' 3096804 NYTEST SHD6 SOIL 4/03/97 7/25/97	MW4C 4-6' 3093901 NYTEST SHD5 SOIL 3/31/97 7/25/97	MW4J 16-20' 3093902 NYTEST SHD5 SOIL 3/31/97 7/25/97
VOLATILES							
1,2-Dichloroethene (total)	mg/Kg	0.3	-	0.002 J	0.002 J	-	-
Methylene Chloride	mg/Kg	0.1	-	-	-	0.007 J	0.008 J
Trichloroethene	mg/Kg	0.7	-	0.028 J	0.021 J	-	-
SEMIVOLATILES							
bis(2-Ethylhexyl)phthalate	mg/Kg	50	0.079 J	0.1 J	0.058 J	R	R
PESTICIDES/PCBs							
Methoxychlor	mg/Kg	-	-	-	-	-	-
INORGANICS							
Aluminum	mg/Kg	SB(33,000)	17900	12600 J	4880 J	14400	11800
Antimony	mg/Kg	SB	1.8 J	2 J	1.6 J	2 J	0.55 J
Arsenic	mg/Kg	7.5/SB(3-12)	10.6 J	7.8 J	1.9 J	9.6 J	6.6 J
Barium	mg/Kg	300/SB(15-600)	163 J	160 J	24.9 J	95.8 J	87 J
Beryllium	mg/Kg	0.16/SB(0-1.75)	0.73	0.47 J	0.38 J	0.57	0.46 J
Calcium	mg/Kg	SB(13-35,000)	5510 J	1590 J	1540 J	1490 J	22200 J
Chromium	mg/Kg	10/SB(1.5-40)	24.1 J	17.2 J	11.2 J	19.4 J	15.8 J
Cobalt	mg/Kg	30/SB(2.5-60)	16.8 J	10.8 J	4.3 J	13.1 J	10.8 J
Copper	mg/Kg	25/SB(1-50)	23.2	20 J	7.9 J	20.2	17.9
Iron	mg/Kg	2000/SB(2000-500,000)	40000 J	27200	19500	31100 J	25300 J
Lead	mg/Kg	SB(14)	16.6	17.3 J	4.1 J	10.8	9.4
Magnesium	mg/Kg	SB(100-5,000)	7000 J	4130 J	2040 J	5140 J	7650 J
Manganese	mg/Kg	SB(50-5,000)	584 J	616 J	97.3 J	586 J	504 J
Mercury	mg/Kg	0.1	-	-	0.05 J	-	0.06 J
Nickel	mg/Kg	13/SB(0.5-25)	37.6 J	25.4 J	7.9 J	31.3 J	25.5 J
Potassium	mg/Kg	SB(8,500-43,000)	2220	1720	1130	1470	1550
Sodium	mg/Kg	SB(6,000-8,000)	146 J	298 J	293 J	77.5 J	145 J
Thallium	mg/Kg	SB	-	-	-	0.77 J	-
Vanadium	mg/Kg	150/SB(1-300)	24 J	18.4 J	20.2 J	19.5 J	16.1 J
Zinc	mg/Kg	20/SB(9-50)	83.9 J	87.2 J	24.6 J	70 J	57.6 J
Total Cyanide	mg/Kg	-	-	-	-	2.23	-

SOUTH HILL DUMP SITE VALIDATED SOIL BORING RESULTS DETECTED COMPOUND SUMMARY		SAMPLE ID: DEPTH: LAB ID: SOURCE: SDG: MATRIX: SAMPLED: VALIDATED: UNITS:	CLEAN-UP OBJECTIVE TAGM No. HWR-94-4046	MW1B 2-4' 3090501 NYTEST SHD5 SOIL 3/26/97 7/25/97	MW1E 6-10' 3090502 NYTEST SHD5 SOIL 3/26/97 7/25/97	MW2B 2-4' 3090503 NYTEST SHD5 SOIL 3/27/97 7/25/97	MW2G 10-14' 3090504 NYTEST SHD5 SOIL 3/27/97 7/25/97
COMPOUND							
VOLATILES							
1,2-Dichloroethene (total)	mg/Kg	0.3	-	-	-	-	-
Methylene Chloride	mg/Kg	0.1	0.004 J	0.004 J	0.004 J	0.004 J	0.004 J
Trichloroethene	mg/Kg	0.7	-	-	-	-	-
SEMIVOLATILES							
bis(2-Ethylhexyl)phthalate	mg/Kg	50	0.23 J	0.077 J	-	-	-
PESTICIDES/PCBs							
Methoxychlor	mg/Kg	-	-	0.014 J	-	-	-
INORGANICS							
Aluminum	mg/Kg	SB(33,000)	17400	15000	15000	13100	
Antimony	mg/Kg	SB	1.7 J	1.5 J	1.7 J	0.98 J	
Arsenic	mg/Kg	7.5/SB(3-12)	8.9	6.9	8	7.9	
Barium	mg/Kg	300/SB(15-600)	46.6 J	133 J	59.6 J	99.2 J	
Beryllium	mg/Kg	0.16/SB(0-1.75)	0.65	0.55	0.56	0.55	
Calcium	mg/Kg	SB(13-35,000)	1000 J	1270 J	782 J	50300 J	
Chromium	mg/Kg	10/SB(1.5-40)	22.3 J	21.4 J	20.5 J	17.6 J	
Cobalt	mg/Kg	30/SB(2.5-60)	15.5 J	16 J	13.6 J	11.3 J	
Copper	mg/Kg	25/SB(1-50)	20	18.2	19	18.3	
Iron	mg/Kg	2000/SB(2000-500,000)	33900 J	33200 J	29400 J	29200 J	
Lead	mg/Kg	SB(14)	22.9	5.7	9.2	9.5	
Magnesium	mg/Kg	SB(100-5,000)	6020 J	6150 J	5490 J	9070 J	
Manganese	mg/Kg	SB(50-5,000)	836 J	1000 J	547 J	675 J	
Mercury	mg/Kg	0.1	-	-	-	-	
Nickel	mg/Kg	13/SB(0.5-25)	35.5 J	33.5 J	31.4 J	26.6 J	
Potassium	mg/Kg	SB(8,500-43,000)	1290	1250	1140	1970	
Sodium	mg/Kg	SB(6,000-8,000)	167 J	-	121 J	181 J	
Thallium	mg/Kg	SB	-	-	0.97 J	-	
Vanadium	mg/Kg	150/SB(1-300)	21.3 J	19.4 J	19.4 J	18.2 J	
Zinc	mg/Kg	20/SB(9-50)	73.5 J	65 J	68.1 J	57.7 J	
Total Cyanide	mg/Kg		-	-	-	-	

Table 1.1: Test Pit Investigation Summary

TEST PIT	PID READING (NOTE 1)	BOTTOM OF FILL (FT BGS)	DRUMS ENCOUNTERED	STAINS OBSERVED	OTHER	ADDITIONAL DRUMS SUSPECTED (Yes/No)	SAMPLES COLLECTED	DEPTH TO GROUNDWATER (FT)	SAMPLES FROM BENEATH WT (Yes/No)	SAMPLE RESULTS (see Note 2)
TP-1	0 ppm	7.5	Drum fragments	Black stained area approx. 15 feet from west edge of trench		No, native soil encountered	TP-01-01 from stained area 17 feet west of end of trench and 5 feet deep	NE	No	SVOCs, primarily PAHs above SCGs.
TP-2	--	17	No	No		No, native soil encountered	No	NE	No	NS
TP-3	29 ppm	8	Crushed w/ 1 intact	No		No, native soil encountered	TP-03-01 soil below excavated drum 20 feet from top of slope and 3 feet deep	NE	No	PAHs above SCGs.
TP-4	No elevated readings	11	Corroded drum, crushed and corroded carcasses, and open drum 15 feet from base of slope	No, burn zones only		No, native soil encountered	No	NE	No	NS
TP-5	--	unknown, slope unstable at 11 feet	No	No, burn zones only		Possibly - native soil not encountered	TP-05-01 from burn area 20 feet from west end of trench and 4 feet deep	NE	No	No concentrations above SCGs. Elevated aroclor 1260 concentration (2.8 mg/kg).
TP-6	--	5	No	No		No, native soil encountered	No	NE	No	NS
TP-7	0.5 ppm	15	No	No, burn zones only		No, native soil encountered	TP-07-01 from stained area 5 feet from south end of trench and 8 feet deep	NE	No	No concentrations above SCGs.
TP-8	--	13	No	No, burn zones only	Fuel oil odor	No, native soil encountered	TP-08-01 from ash with hydrocarbon odor 2 feet deep from east end of trench	NE	No	No concentrations above SCGs. Elevated phenanthrene concentration (5.3 mg/kg).
TP-9	--	11	No	No		No, native soil encountered	No	NE	No	NS
TP-10	--	unknown, slope unstable at 15 feet	No	No		Possibly - native soil not encountered	TP-10-01 near rubber caps 15 feet from south end of trench and 15 feet deep	NE	No	No concentrations above SCGs. Elevated butylbenzylphthalate concentration (4.1 mg/kg).
TP-11	1.0 ppm	unknown, slope unstable at 17 feet	Crushed drums and corroded drum fragments	Yes, near drum		Possibly - native soil not encountered	TP-11-01 stained area near crushed drum 20 feet from north end, 12 feet deep; TP-11-02 from gray-blue clay 3 feet from north end of trench and 4 feet deep	NE	No	SVOCs, including one PAH above SCGs.
TP-12	2.7 ppm	unknown, slope unstable at 17 feet	Crushed drums encountered	No, burn zones only	Slight sheen	Yes, drums near trench termination depth	TP-12-01(DUP TP-12-11) stained soil from center of trench 17 feet deep	NE	No	One PAH above SCGs.
TP-13	5.0 ppm	unknown, slope unstable at 16 feet	Crushed drum	No		Possibly - native soil not encountered	No	NE	No	NS
TP-14	0.8 ppm	21, bedrock at 21 feet	Flattened drum	No	Water at 14 feet	No, bedrock encountered	No	14	No	NS
TP-15	--	17	No	No		No, native soil encountered	No	NE	No	NS
TP-16	8 ppm	17, bedrock at 17 feet	Sheared drum with resin and fibers, crushed drum with orange-rust colored soil and glue odor	No	Water at 17 feet	No, bedrock encountered	TP-16-01 resin and fibers near crushed drum 5 feet from south end, 5 feet deep; TP-16-02 from crushed drum 12 feet from south end of trench, 8 feet deep	17	No	One PAH above SCGs. Concentration of 2-methylnaphthalene slightly below SCG value.
TP-17	--	15, bedrock at 17 feet	No	No	Water at 17 feet	No, bedrock encountered	No	17	No	NS

Table 1.1: Test Pit Investigation Summary

TEST PIT	PID READING (NOTE 1)	BOTTOM OF FILL (FT BGS)	DRUMS ENCOUNTERED	STAINS OBSERVED	OTHER	ADDITIONAL DRUMS SUSPECTED (Yes/No)	SAMPLES COLLECTED	DEPTH TO GROUNDWATER (FT)	SAMPLES FROM BENEATH WT (Yes/No)	SAMPLE RESULTS (see Note 2)
TP-18	26 ppm	18, bedrock at 19 feet	1 Crushed w/ soil staining	Yes, near drum	Water at 19 feet	No, bedrock encountered	TP-18-01 adjacent to flattened drum 8 feet deep and 24 feet from east end of trench	19	No	SVOCs, including one PAH above SCGs. Elevated bis(2-ethylhexyl)phthalate concentration.
TP-19	31 ppm	13, bedrock at 15 feet	Burned & crushed drum 30 feet, crushed drum 51 feet, & fragments 42 from east end	No, soil in burned area is rust colored		No, bedrock encountered	TP-19-01 near crushed drum 42 feet from east end, 10 feet deep; TP-19-02 near crushed drum 51 feet from east end, 10 feet deep.	NE	No	Low concentrations detected, primarily VOCs.
TP-20	124 ppm	15	Four crushed drums 48 feet from south end, two drums empty, one left undisturbed in bank, fourth contained dark gray-black fine shavings, all located approx 1 foot below grade; a fifth crushed drum 40 feet from south end, contains gray sandy material, slightly cemented, located 4 feet below grade	No, burn zone at southern end		Yes, drum left in-place	DS-20-01 from drum 40 feet from south end, 4 feet deep; DS-20-02 from drum in nest 48 feet from south end, 1 foot deep	NE	No	VOCs, PAHs, pesticides, and PCBs detected.
TP-21	10.8 ppm	unknown, trench terminated at 5 feet, no explanation	Crushed drum empty at north end, three crushed drums at south end, two left undisturbed, third intact with label "__NT "Wilmington Delaware". Third drum opened, contained approx 2 inches black oily substance	No		Yes - trench terminated at 5 feet	TP-21-01 soil below drum nest at south end of trench, 3 feet deep; TP-21-D1 from overpacked drum	NE	No	Low concentrations detected, primarily SVOCs. In drum, elevated concentrations of TCE, methylene chloride, phenanthrene, 2,4,5-trichlorophenol, and bis(2-ethylhexyl)phthalate.
TP-22	--	3, bedrock at 7 feet	No	No		No, bedrock encountered	No	NE	No	NS
TP-23	--	4, bedrock 7 feet	No	No		No, bedrock encountered	No	NE	No	NS
TP-24	30.2 ppm	13, bedrock at 14 feet	1 Corroded - overpacked	No		No, bedrock encountered	TP-24-01 resin from crushed drum at east end, 4 feet deep	NE	No	
TP-25	3 ppm	14, bedrock at 14 feet	1 Crushed, empty	No	Water at 14 feet	No, bedrock encountered	No	14	No	NS
TP-26	0 ppm	4, bedrock at 8 feet	No	No	2 to 3 foot diameter white-tan resin fragment	No, bedrock encountered	No	NE	No	NS
TP-27	--	14	No	No		No, native soil encountered	TP-27-01(DUP TP-27-11) burned fill from wall of slope 10 feet deep	NE	No	Low concentrations detected, primarily pests/PCBs
TP-28	--	5, bedrock at 8 feet	No	No		No, bedrock encountered	No	NE	No	NS
TP-29	--	9, bedrock at 10 feet	No	No		No, bedrock encountered	No	NE	No	NS
TP-30	0 ppm	4, bedrock at 7 feet	No	black residue on soil at 4 feet below grade	pungent odor at 4 feet below grade	No, bedrock encountered	TP-30-01 stained area from center of trench 4 feet deep	NE	No	No concentrations above SCGs. Elevated bis(2-Ethylhexyl)phthalate concentration.
TP-31	--	20	No	No		No, native soil encountered	No	NE	No	NS

Table 1.1: Test Pit Investigation Summary

TEST PIT	PID READING (NOTE 1)	BOTTOM OF FILL (FT BGS)	DRUMS ENCOUNTERED	STAINS OBSERVED	OTHER	ADDITIONAL DRUMS SUSPECTED (Yes/No)	SAMPLES COLLECTED	DEPTH TO GROUNDWATER (FT)	SAMPLES FROM BENEATH WT (Yes/No)	SAMPLE RESULTS (see Note 2)
TP-32	0 ppm	3	3 Crushed, empty at 15, 32, & 45 ft from east end	Gray green residue 1 foot deep at east end of trench		No, native soil encountered	TP-32-01 gray-green residue from east end of trench, 1 foot deep	NE	No	No concentrations above SCGs. Elevated Aroclor 1248 concentration (4 mg/kg).
TP-33	--	1 to 4	Several crushed, most empty, some contain yellow paint residue	No		No, native soil encountered	No	NE	No	NS
TP-34	--	no fill, bedrock at 8 feet	No	No	wet at 6 feet	No, native soil encountered	No	possibly 6	No	NS
TP-35	--	no fill, bedrock at 4 feet	No	No		No, native soil encountered	No	NE	No	NS
TP-36	96 ppm	varies 0 to 3	1 Crushed, empty	No		No, native soil encountered	TP-36-01 soil beneath crushed drum on east portion of trench, 2 feet deep; TP-36-02 from soil at west end of trench, 3 feet deep	NE	No	Only a low concentration of methylene chloride detected, both samples.
TP-37	--	varies 1 to 2	Multiple drums on ground at west and at east end	No		No, native soil encountered	No	NE	No	NS
TP-38	57 ppm, LEL 1% on drum contents	3	Mult. drums on surface	No	wet at 5 feet, fuel odor at 3 feet	No, native soil encountered	TP-38-01 soil from 2 feet deep; TP-38-D1 from overpacked drum	possibly 5	No	Phenol above SCGs in soil. In drum sample, phenol not detected, low concentrations of VOCs, and elevated xylene, 4-methyl-2-pentanone and bis(2-ethylhexyl)phthalate (60,000 mg/kg).
TP-39	--	2	Carcasses at and just below ground surface	No		No, native soil encountered	TP-39-01(DUPTP-39-11) soil from beneath empty drums, 1 foot deep	NE	No	Several PAHs above SCGs.
TP-40	0 ppm	5	Crushed drums & fragments	No, NAPL encountered entering trench from north		Possibly - NAPL reportedly encountered entering trench from the north	TP-40-01 soil below seep at north portion of trench, 4 feet deep; TP-40-W aqueous sample from seep at north end of trench; TP-40-SEEP from drainage into swale downstream of TP-40; additional aqueous samples collected from trench by Buck Labs for waste disposal characterization	4 to 5	Yes	No concentrations elevated or above SCGs in soil. Elevated benzene, 1,2-DCE, TCE, toluene, and vinyl chloride detected in aqueous samples.
TP-41	0 ppm	4	2 Leaking and 1 empty at 1 foot; contents maroon-colored solid mixed with metal typerwriter pieces	No	water at 7 feet	No, native soil encountered	TP-41-01 composite sample of 2 leaking drums; TP-41-D1 (DUP TP-41-DR1) from overpacked drum	7	No	Elevated 2,4,5-trichlorophenol.
TP-42	2.5 ppm	4	No	No		No, native soil encountered	No	NE	No	NS
TP-43	--	6 in southwest, 0 in northeast	No	No		No, native soil encountered	TP-43-01 gray till 6 feet deep	NE	No	No concentrations elevated or above SCGs in soil.
TP-44	--	0 to 1	No	No		No, native soil encountered	No	NE	No	NS

Table 1.1: Test Pit Investigation Summary

TEST PIT	PID READING (NOTE 1)	BOTTOM OF FILL (FT BGS)	DRUMS ENCOUNTERED	STAINS OBSERVED	OTHER	ADDITIONAL DRUMS SUSPECTED (Yes/No)	SAMPLES COLLECTED	DEPTH TO GROUNDWATER (FT)	SAMPLES FROM BENEATH WT (Yes/No)	SAMPLE RESULTS (see Note 2)
TP-45	0 ppm	unknown, no subsurface excavation	Eleven total drums encountered at surface, four drums with following contents; first half-full, oil-like contents, second one-thrid full, oil-like contents, third less than one-quarter full, oil-like contents, and fourth containing ash; remaining drums empty	No		Possibly - No subsurface excavation	TP-45-D1 from overpacked drum; TP-45-D2 from overpacked drum	NE	No	Several elevated SVOCs, acid test yielded elevated aroclor 1254.
TP-46	2 ppm	1.5 to 2	1 empty crushed drum	No		No, native soil encountered	TP-46-01 gray silt clay at north end of trench 2 feet deep	NE	No	Low concentrations of several VOCs.
TP-47	--	No fill	No	Possible reddish stain at surface		No, native soil encountered	No	NE	No	NS
TP-48	--	1	2 Drum lids	Occassionally red stained near surface	water at between 3 and 5 feet	No, native soil encountered	No	3 to 5	No	NS
TP-49	--	1.5	No	Black and red stained organics	water at 3.5 feet	Possibly - native soil not encountered	No	3.5	No	NS
TP-50	--	unknown, trench terminated at 5 feet, no explanation	No	No	water and oil encountered near surface, oil recovered with pads	Possibly - native soil not encountered, oil encountered	No	possibly less than 5	No	NS

Notes:
1. PID reading presented is the highest observed for that location.
2. Concentrations of inorganics exceed SCGs at all test pit locations.
Only organic analyte results are discussed.
-- = not indicated
NS = not sampled
NE = not encountered
ppm = parts per million
FT = feet
FT BGS = feet below ground surface
WT = water table
VOCs = volatile organic compounds
SVOCs = semi-volatile organic compounds
PAHs = polyaromatic hydrocarbons
pests = pesticides

Prepared/Date: RTB 10/20/05
Checked/Date: MJS 10/20/05

Table 1.2: Determination of Recommended Soil Cleanup Objectives for Organic Contaminants

COMPOUND	UNITS:	SOIL CLEANUP	USEPA HEALTH BASED		CRQL	RECOMMENDED
		OBJECTIVE TO	CARCIN-	SYSTEMIC	(see	SOIL CLEAN-UP
		PROTECT GW	OGENS	TOXICANTS	Note 2)	OBJECTIVE
		QUALITY				(see Note 3)
		(see Note 1)				
VOLATILES*						
Acetone	mg/Kg	0.11	N/A	8000	0.01	0.2
Benzene	mg/Kg	0.06	24	N/A	0.005	0.1
2-Butanone	mg/Kg	0.3	N/A	4000	0.01	0.3
Chlorobenzene	mg/Kg	1.7	N/A	2000	0.005	1.7
1,2-Dichloroethene (total)	mg/Kg	0.3	N/A	2000	0.005	0.3
Ethylbenzene	mg/Kg	5.5	N/A	8000	0.005	5.5
4-Methyl-2-Pentanone	mg/Kg	1	N/A	N/A	0.01	1
Methylene Chloride	mg/Kg	0.1	93	5000	0.005	0.1
Tetrachloroethene	mg/Kg	1.4	14	800	0.005	1.4
Toluene	mg/Kg	1.5	N/A	20000	0.005	1.5
Trichloroethene	mg/Kg	0.7	64	N/A	0.005	0.7
Vinyl Chloride	mg/Kg	0.12	N/A	N/A	0.01	0.2
Xylene (total)	mg/Kg	1.2	N/A	200000	N/A	1.2
SEMIVOLATILES*						
Acenaphthene	mg/Kg	90	N/A	5000	0.33	50
Acenaphthylene	mg/Kg	41	N/A	N/A	0.33	41
Anthracene	mg/Kg	700	N/A	20000	0.33	50
Benzo(a)anthracene	mg/Kg	3	0.224	N/A	0.33	0.224/MDL
Benzo(a)pyrene	mg/Kg	11	0.0609	N/A	0.33	0.061/MDL
Benzo(b)fluoranthene	mg/Kg	1.1	N/A	N/A	0.33	1.1
Benzo(g,h,i)perylene	mg/Kg	8000	N/A	N/A	0.33	50
Benzo(k)fluoranthene	mg/Kg	1.1	N/A	N/A	0.33	1.1
bis(2-Ethylhexyl)phthalate	mg/Kg	435	50	2000	0.33	50
Butylbenzylphthalate	mg/Kg	122	N/A	20000	0.33	50.00
Carbazole	mg/Kg	N/A	N/A	N/A	N/A	N/A
4-Chloroaniline	mg/Kg	0.22	200	300	0.33	0.220/MDL
Chrysene	mg/Kg	0.4	N/A	N/A	0.33	0.4
Di-n-butylphthalate	mg/Kg	8.1	N/A	8000	0.33	8.1
Di-n-octylphthalate	mg/Kg	120	N/A	2000	0.33	50
Dibenzofuran	mg/Kg	6.2	N/A	N/A	0.33	6.2
1,4-Dichlorobenzene	mg/Kg	N/A	N/A	N/A	N	N/A
Diethylphthalate	mg/Kg	7.1	N/A	60000	0.33	7.1
Dimethylphthalate	mg/Kg	2	N/A	80000	0.33	2
2,6-Dinitrotoluene	mg/Kg	1	1.03	N/A	0.33	1
Fluoranthene	mg/Kg	1900	N/A	3000	0.33	50
Fluorene	mg/Kg	350	N/A	3000	0.33	50
Hexachlorocyclopentadiene	mg/Kg	N/A	N/A	N/A	N/A	N/A
Indeno(1,2,3-cd)pyrene	mg/Kg	3.2	N/A	N/A	0.33	3.2
2-Methylnaphthalene	mg/Kg	36.4	N/A	N/A	0.33	36.4
4-Methylphenol	mg/Kg	0.9	N/A	4000	0.33	0.9
N-Nitrosodiphenylamine	mg/Kg	N/A	N/A	N/A	N/A	N/A
Naphthalene	mg/Kg	13	N/A	300	0.33	13
Pentachlorophenol	mg/Kg	1	N/A	2000	1.6	1.0/MDL

Table 1.2: Determination of Recommended Soil Cleanup Objectives for Organic Contaminants

COMPOUND	UNITS:	SOIL CLEANUP	USEPA HEALTH BASED		CRQL	RECOMMENDED
		OBJECTIVE TO PROTECT GW QUALITY (see Note 1)	CARCIN- OGENS	SYSTEMIC TOXICANTS	(see Note 2)	SOIL CLEAN-UP OBJECTIVE (see Note 3)
Phenanthrene	mg/Kg	220	N/A	N/A	0.33	50
Phenol	mg/Kg	0.03	N/A	50000	0.33	0.03/MDL
Pyrene	mg/Kg	665	N/A	2000	0.33	50
1,2,4-Trichlorobenzene	mg/Kg	N/A	N/A	N/A	N/A	N/A
bis(2-Ethylhexyl)phthalate	mg/Kg	435	50	2000	0.33	50
PESTICIDES/PCBs*						
alpha-BHC	mg/Kg	0.2	0.111	N/A	0.008	0.11
alpha-Chlordane***	mg/Kg	2	0.54	50	0.08	0.54
beta-BHC	mg/Kg	0.2	3.89	N/A	0.008	0.20
delta-BHC	mg/Kg	0.3	N/A	N/A	0.008	0.30
gamma-BHC (Lindane)	mg/Kg	0.06	5.4	20	0.008	0.06
gamma-Chlordane	mg/Kg	14	0.54	5	0.08	0.54
Aldrin	mg/Kg	9.6	0.041	2	0.008	0.041
4,4'-DDD	mg/Kg	7.7	2.9	N/A	0.016	2.9
4,4'-DDE	mg/Kg	4.4	2.1	N/A	0.016	2.1
4,4'-DDT	mg/Kg	2.5	2.1	40	0.016	2.1
Dieldrin	mg/Kg	0.1	0.044	4	0.016	0.044
Endosulfan I	mg/Kg	0.9	N/A	N/A	0.016	0.9
Endosulfan II	mg/Kg	0.9	N/A	N/A	0.016	0.9
Endosulfan sulfate	mg/Kg	1	N/A	N/A	0.016	1
Endrin	mg/Kg	0.1	N/A	20	0.008	0.10
Endrin aldehyde	mg/Kg	N/A	N/A	N/A	N/A	N/A
Endrin ketone	mg/Kg	N/A	N/A	N/A	N/A	N/A
Heptachlor	mg/Kg	0.1	0.16	40	0.008	0.1
Heptachlor epoxide	mg/Kg	0.002	0.077	0.8	0.008	0.02
Methoxychlor	mg/Kg	900	N/A	400	0.08	N/A
Toxaphene	mg/Kg	N/A	N/A	N/A	N/A	N/A
Aroclor-1016**	mg/Kg	10	1	N/A	0.16	1, 10
Aroclor-1221**	mg/Kg	10	1	N/A	0.161	1, 10
Aroclor-1232**	mg/Kg	10	1	N/A	0.162	1, 10
Aroclor-1242**	mg/Kg	10	1	N/A	0.163	1, 10
Aroclor-1248**	mg/Kg	10	1	N/A	0.164	1, 10
Aroclor-1254**	mg/Kg	10	1	N/A	0.165	1, 10
Aroclor-1260**	mg/Kg	10	1	N/A	0.166	1, 10
TCLP VOLATILES						
NONE	mg/L					
TCLP SEMIVOLATILES						
NONE	mg/L					
TCLP PESTICIDES						
NONE	mg/L					
TCLP HERBICIDES						
NONE	mg/L					

Prepared/Date: RTB 10/20/05

Checked/Date: MJS 10/20/05

Table 1.2: Determination of Recommended Soil Cleanup Objectives for Organic Contaminants

		SOIL CLEANUP	USEPA HEALTH BASED	CRQL	RECOMMENDED
COMPOUND	UNITS:	OBJECTIVE TO PROTECT GW QUALITY (see Note 1)	CARCIN- OGENS	SYSTEMIC TOXICANTS	(see Note 2) SOIL CLEAN-UP OBJECTIVE (see Note 3)
Notes:					
1. Soil cleanup objective to protect groundwater quality according to TAGM 4046, 1994. This value was calculated for 1% (5% for PCBs) soil organic carbon content, and should be adjusted according to site-specific values.					
2. Cleanup objective not to be less than CRQL.					
3. Cleanup objective lesser of value to protect groundwater and health based values, unless otherwise specified in TAGM 4046. TCLP criteria values from STARS Memo #1, 1992.					
*Per TAGM 4046, total VOCs less than 10 ppm, individual SVOCs less than 50 ppm, total SVOCs less than 500 ppm, total pesticides less than 10 ppm.					
**PCB criteria 1 mg/kg surface soil, 10 mg/kg subsurface soil. No surface soils presented; data compared to value of 10 mg/kg.					
TCLP Criteria from Spill Technology and Remediation Series (STARS) Memo #1 Petroleum-Contaminated Soil Guidance Policy.					
*** chlordane criteria value used					
CRQL = contract required quantitation limit					
MDL = Method detection limit					
mg/kg = milligrams per kilogram					
mg/L = milligrams per liter					
N/A = not available					

Table 1.3: Determination of Recommended Soil Cleanup Objectives for Inorganic Contaminants

COMPOUND	UNITS:	EASTERN US BACKGROUND (see Note 1)	CRDL (see Note 2)	SITE BACKGROUND (see Note 3)	RECOMMENDED SOIL CLEAN-UP OBJECTIVE (see Note 4)
INORGANICS					
Aluminum	mg/Kg	33,000	2	16200	SB
Antimony	mg/Kg	N/A	0.6	1.6	SB
Arsenic	mg/Kg	3-12**	0.1	7.9	7.5 or SB
Barium	mg/Kg	15-600	2	89.8	300 or SB
Beryllium	mg/Kg	0-1.75	0.05	0.6	0.16 (HEAST) or SB
Cadmium	mg/Kg	0.1-1	0.05	N/A	1 or SB
Calcium	mg/Kg	130-35000	50	1135	SB
Chromium	mg/Kg	1.5-40 **	0.1	21.85	10 or SB
Cobalt	mg/Kg	2.5-60 **	0.5	15.75	30 or SB
Copper	mg/Kg	1-50	0.25	19.1	25 or SB
Iron	mg/Kg	2000-550000	1	33550	2000 or SB
Lead	mg/Kg	****	0.03	14.3	SB
Magnesium	mg/Kg	100-5000	50	6085	SB
Manganese	mg/Kg	50-5000	0.15	918	SB
Mercury	mg/Kg	0.001-0.2	0.002	ND	0.1
Nickel	mg/Kg	0.5-25	0.4	34.5	13 or SB
Potassium	mg/Kg	8500-43000 **	50	1270	SB
Selenium	mg/Kg	0.1-3.9	0.05	N/A	2 or SB
Silver	mg/Kg	N/A	0.1	N/A	SB
Sodium	mg/Kg	6000-8000	50	167	SB
Thallium	mg/Kg	N/A	0.1	ND	SB
Vanadium	mg/Kg	1-300	0.5	20.35	150 or SB
Zinc	mg/Kg	9-50	0.2	69.25	20 or SB
Total Cyanide	mg/Kg	N/A	0.1	ND	***
TCLP METALS					
Arsenic	mg/L				5.00
Barium	mg/L				100.00
Cadmium	mg/L				1.00
Lead	mg/L				5.00
Silver	mg/L				5.00

Prepared/Date: RTB 10/20/05
 Checked/Date: MJS 10/20/05

Notes:

- Represents average background concentrations for Eastern US soils.
- ** values represent New York State background
- Recommended Soil Cleanup Objective not to be less than CRDL.
 - Site Background is average of results from samples MW-1B and MW-1E (refer to Table B.6)
 - Recommended Soil Cleanup Objectives from TAGM 4046, 1994. TCLP values from STARS Memo #1, 1992.
- Recommended Soil Cleanup Objective is the higher of the values listed.
- ***site-specific forms of cyanide should be evaluated in determining cleanup objective
- ****background levels for lead vary widely, from 4-61 mg/kg for rural areas, to 200-500 mg/kg for urban
- CRDL = contract required detection limit, which is approximately 10 times the CRDL for water.
- HEAST = USEPA HEAST database value
- MDL = Method Detection Limit
- mg/kg = milligrams per kilogram
- mg/L = milligrams per liter
- N/A = not available
- ND = not detected
- SB = site background

Table B.1: Test Pit Soil Sample Results

COMPOUND	SAMPLE ID: RECOMMENDED				
	UNITS:				
VOLATILES					
Acetone	mg/Kg	0.20	-	-	-
Benzene	mg/Kg	0.06	-	-	-
2-Butanone	mg/Kg	0.30	-	-	-
Chlorobenzene	mg/Kg	1.70	-	-	-
1,2-Dichloroethene (total)	mg/Kg	0.30	-	-	-
Ethylbenzene	mg/Kg	5.50	-	-	-
4-Methyl-2-Pentanone	mg/Kg	1.00	-	-	-
Methylene Chloride	mg/Kg	0.10	-	-	-
Tetrachloroethene	mg/Kg	1.40	-	-	-
Toluene	mg/Kg	1.50	-	-	-
Trichloroethene	mg/Kg	0.70	-	0.004 J	-
Vinyl Chloride	mg/Kg	0.20	-	-	-
Xylene (total)	mg/Kg	1.20	-	-	-
Total VOCs	mg/Kg	10.00	0.000	0.004	0.000
SEMIVOLATILES					
Acenaphthene	mg/Kg	50.00	-	0.07 J	-
Acenaphthylene	mg/Kg	41.00	0.15 J	-	-
Anthracene	mg/Kg	50.00	0.20 J	0.23 J	-
Benzo(a)anthracene	mg/Kg	0.224/MDL	0.76	0.40 J	-
Benzo(a)pyrene	mg/Kg	0.061/MDL	0.78	0.32 J	-
Benzo(b)fluoranthene	mg/Kg	1.10	0.84	0.30 J	-
Benzo(g,h,i)perylene	mg/Kg	50.00	0.16 J	0.06 J	-
Benzo(k)fluoranthene	mg/Kg	1.10	0.70	0.30 J	-
Butylbenzylphthalate	mg/Kg	50.00	-	-	-
Carbazole	mg/Kg	-	0.10 J	0.12 J	-
4-Chloroaniline	mg/Kg	0.220/MDL	-	-	-
Chrysene	mg/Kg	0.40	0.81	0.36 J	-
Di-n-butylphthalate	mg/Kg	8.10	-	-	-
Di-n-octylphthalate	mg/Kg	50.00	-	-	-
Dibenzofuran	mg/Kg	6.20	-	-	-
1,4-Dichlorobenzene	mg/Kg	-	-	-	-
Diethylphthalate	mg/Kg	7.10	-	-	-
Dimethylphthalate	mg/Kg	2.00	-	-	-
2,6-Dinitrotoluene	mg/Kg	1.00	-	-	-
Fluoranthene	mg/Kg	50.00	2.20	1.20	-
Fluorene	mg/Kg	50.00	0.06 J	0.08 J	-
Hexachlorocyclopentadiene	mg/Kg	-	-	-	-
Indeno(1,2,3-cd)pyrene	mg/Kg	3.20	0.32 J	0.11 J	-
2-Methylnaphthalene	mg/Kg	36.40	-	-	-
4-Methylphenol	mg/Kg	0.90	-	-	-
N-Nitrosodiphenylamine	mg/Kg	-	-	-	-
Naphthalene	mg/Kg	13.00	-	-	-

Table B.1: Test Pit Soil Sample Results

		SAMPLE ID: RECOMMENDED	TP0101	TP0301	TP0501
		DEPTH: SOIL CLEAN-UP	5'	3'	4'
		LAB ID: OBJECTIVE	3066701	3066702	3066703
		SOURCE: (see Note 1)	NYTEST	NYTEST	NYTEST
		SDG:	SHD1	SHD1	SHD1
		MATRIX:	SOIL	SOIL	SOIL
		SAMPLED:	2/26/97	2/27/97	2/27/97
		VALIDATED:	7/25/97	7/25/97	7/25/97
COMPOUND	UNITS:				
Pentachlorophenol	mg/Kg	1.0/MDL	-	-	-
Phenanthrene	mg/Kg	50.00	0.95	0.79	-
Phenol	mg/Kg	0.03/MDL	-	-	-
Pyrene	mg/Kg	50.00	1.00	0.52	-
1,2,4-Trichlorobenzene	mg/Kg	-	-	-	-
bis(2-Ethylhexyl)phthalate	mg/Kg	50.00	3.40	5.20	0.26 J
Total SVOCs	mg/Kg	500.00	12.43	10.06	0.26
PESTICIDES/PCBs					
alpha-BHC	mg/Kg	0.11	-	-	-
alpha-Chlordane	mg/Kg	0.54	-	-	-
beta-BHC	mg/Kg	0.20	-	-	-
delta-BHC	mg/Kg	0.30	-	-	-
gamma-BHC (Lindane)	mg/Kg	0.06	-	-	-
gamma-Chlordane	mg/Kg	0.54	-	-	-
Aldrin	mg/Kg	0.041	-	-	-
4,4'-DDD	mg/Kg	2.90	0.01	0.003 J	-
4,4'-DDE	mg/Kg	2.10	0.005 J	-	0.01 JN
4,4'-DDT	mg/Kg	2.10	0.003 JN	0.002 JN	0.003 JN
Dieldrin	mg/Kg	0.044	-	-	-
Endosulfan I	mg/Kg	0.90	-	-	0.002 JN
Endosulfan II	mg/Kg	0.90	-	-	0.07
Endosulfan sulfate	mg/Kg	1.00	-	-	-
Endrin	mg/Kg	0.10	-	-	-
Endrin aldehyde	mg/Kg	-	-	-	0.01 JN
Endrin ketone	mg/Kg	N/A	-	-	-
Heptachlor	mg/Kg	0.10	-	-	-
Heptachlor epoxide	mg/Kg	0.02	-	-	-
Methoxychlor	mg/Kg	N/A	0.03	-	0.03
Toxaphene	mg/Kg	-	-	-	-
Total Pesticides	mg/kg	10.00	0.05	0.00	0.12
Aroclor-1016	mg/Kg	1, 10	-	-	-
Aroclor-1221	mg/Kg	1, 10	-	-	-
Aroclor-1232	mg/Kg	1, 10	-	-	-
Aroclor-1242	mg/Kg	1, 10	-	-	-
Aroclor-1248	mg/Kg	1, 10	-	-	-
Aroclor-1254	mg/Kg	1, 10	-	-	-
Aroclor-1260	mg/Kg	1, 10	-	-	2.80
TCLP VOLATILES					
NONE	mg/L				
TCLP SEMIVOLATILES					
NONE	mg/L				
TCLP PESTICIDES					
NONE	mg/L				

Table B.1: Test Pit Soil Sample Results

SAMPLE ID: RECOMMENDED		TP0101	TP0301	TP0501
DEPTH: SOIL CLEAN-UP		5'	3'	4'
LAB ID: OBJECTIVE		3066701	3066702	3066703
SOURCE: (see Note 1)		NYTEST	NYTEST	NYTEST
SDG:		SHD1	SHD1	SHD1
MATRIX:		SOIL	SOIL	SOIL
SAMPLED:		2/26/97	2/27/97	2/27/97
VALIDATED:		7/25/97	7/25/97	7/25/97
COMPOUND	UNITS:			
TCLP HERBICIDES				
NONE	mg/L			
INORGANICS				
Aluminum	mg/Kg	16200	13500	12600
Antimony	mg/Kg	1.6	2.10 J	17.20
Arsenic	mg/Kg	7.9	9.20	18.90
Barium	mg/Kg	300	181.00	528.00
Beryllium	mg/Kg	0.6	0.70 J	0.42 J
Cadmium	mg/Kg	1	1.70	49.80
Calcium	mg/Kg	1135	6520	15600
Chromium	mg/Kg	21.85	25.10	75.20
Cobalt	mg/Kg	30	9.90	16.70
Copper	mg/Kg	25	52.00	396.00
Iron	mg/Kg	33550	28100	141000
Lead	mg/Kg	14.3	180.00	814.00
Magnesium	mg/Kg	6085	3500	4830
Manganese	mg/Kg	918	790.00	945.00
Mercury	mg/Kg	0.1	0.12 J	0.11 J
Nickel	mg/Kg	34.5	24.20	62.10
Potassium	mg/Kg	1270	1900.00	1330.00
Selenium	mg/Kg	2	1.00	0.92
Silver	mg/Kg	N/A	0.49 J	7.00
Sodium	mg/Kg	167	389.00 J	611.00
Thallium	mg/Kg	ND	-	-
Vanadium	mg/Kg	150	21.80	25.10
Zinc	mg/Kg	69.25	396.00	1610.00
Total Cyanide	mg/Kg	ND	-	-
TCLP METALS				
Arsenic	mg/L	5		
Barium	mg/L	100		
Cadmium	mg/L	1		
Lead	mg/L	5		
Silver	mg/L	5		

Notes:

1. See Tables 1.2 and 1.3 regarding how recommended cleanup objectives were derived.

Highlighted values exceed Recommended Soil Cleanup Objective

- = compound not detected

mg/L = milligrams per liter

J = Estimated value

N = tentatively identified compound

MDL = Method detection limit

R = Data Rejected

mg/kg = milligrams per kilogram

ND = not detected in background samples

Table B.1: Test Pit Soil Sample Results

COMPOUND	SAMPLE ID: RECOMMENDED		TP0701	TP0801	TP1001
	DEPTH:	SOIL CLEAN-UP	8'	2'	15'
	LAB ID:	OBJECTIVE	3067401	3067402	3067403
	SOURCE:	(see Note 1)	NYTEST	NYTEST	NYTEST
	SDG:		SHD1	SHD1	SHD1
	MATRIX:		SOIL	SOIL	SOIL
	SAMPLED:		2/28/97	2/28/97	2/28/97
	VALIDATED:		7/25/97	7/25/97	7/25/97
	UNITS:				
VOLATILES					
Acetone	mg/Kg	0.20	-	-	-
Benzene	mg/Kg	0.06	-	-	-
2-Butanone	mg/Kg	0.30	-	-	-
Chlorobenzene	mg/Kg	1.70	-	-	-
1,2-Dichloroethene (total)	mg/Kg	0.30	-	-	-
Ethylbenzene	mg/Kg	5.50	-	0.006 J	-
4-Methyl-2-Pentanone	mg/Kg	1.00	-	-	-
Methylene Chloride	mg/Kg	0.10	-	-	-
Tetrachloroethene	mg/Kg	1.40	0.004 J	-	-
Toluene	mg/Kg	1.50	-	-	-
Trichloroethene	mg/Kg	0.70	-	-	-
Vinyl Chloride	mg/Kg	0.20	-	-	-
Xylene (total)	mg/Kg	1.20	-	0.002 J	-
Total VOCs	mg/Kg	10.00	0.004	0.008	0.000
SEMIVOLATILES					
Acenaphthene	mg/Kg	50.00	-	-	-
Acenaphthylene	mg/Kg	41.00	-	-	-
Anthracene	mg/Kg	50.00	-	-	-
Benzo(a)anthracene	mg/Kg	0.224/MDL	-	0.10 J	-
Benzo(a)pyrene	mg/Kg	0.061/MDL	-	-	-
Benzo(b)fluoranthene	mg/Kg	1.10	-	-	-
Benzo(g,h,i)perylene	mg/Kg	50.00	-	-	-
Benzo(k)fluoranthene	mg/Kg	1.10	-	-	-
Butylbenzylphthalate	mg/Kg	50.00	-	0.45 J	4.10 J
Carbazole	mg/Kg	-	-	-	-
4-Chloroaniline	mg/Kg	0.220/MDL	-	-	-
Chrysene	mg/Kg	0.40	-	0.30 J	-
Di-n-butylphthalate	mg/Kg	8.10	-	1.00	0.41 J
Di-n-octylphthalate	mg/Kg	50.00	-	-	-
Dibenzofuran	mg/Kg	6.20	-	-	-
1,4-Dichlorobenzene	mg/Kg	-	-	-	-
Diethylphthalate	mg/Kg	7.10	-	-	0.31 J
Dimethylphthalate	mg/Kg	2.00	-	-	-
2,6-Dinitrotoluene	mg/Kg	1.00	-	-	-
Fluoranthene	mg/Kg	50.00	0.05 J	0.90	0.10 J
Fluorene	mg/Kg	50.00	-	-	-
Hexachlorocyclopentadiene	mg/Kg	-	-	-	-
Indeno(1,2,3-cd)pyrene	mg/Kg	3.20	-	-	-
2-Methylnaphthalene	mg/Kg	36.40	-	0.66 J	-
4-Methylphenol	mg/Kg	0.90	-	-	-
N-Nitrosodiphenylamine	mg/Kg	-	-	-	-
Naphthalene	mg/Kg	13.00	-	0.32 J	-

Table B.1: Test Pit Soil Sample Results

		SAMPLE ID: RECOMMENDED	TP0701	TP0801	TP1001
		DEPTH: SOIL CLEAN-UP	8'	2'	15'
		LAB ID: OBJECTIVE	3067401	3067402	3067403
		SOURCE: (see Note 1)	NYTEST	NYTEST	NYTEST
		SDG:	SHD1	SHD1	SHD1
		MATRIX:	SOIL	SOIL	SOIL
		SAMPLED:	2/28/97	2/28/97	2/28/97
		VALIDATED:	7/25/97	7/25/97	7/25/97
COMPOUND	UNITS:				
Pentachlorophenol	mg/Kg	1.0/MDL	-	-	-
Phenanthrene	mg/Kg	50.00	0.05 J	5.30	0.09 J
Phenol	mg/Kg	0.03/MDL	-	-	-
Pyrene	mg/Kg	50.00	-	0.88	-
1,2,4-Trichlorobenzene	mg/Kg	-	-	-	-
bis(2-Ethylhexyl)phthalate	mg/Kg	50.00	0.29 J	2.80	1.30 J
Total SVOCs	mg/Kg	500.00	0.38	12.71	6.31
PESTICIDES/PCBs					
alpha-BHC	mg/Kg	0.11	-	-	-
alpha-Chlordane	mg/Kg	0.54	-	-	0.02 JN
beta-BHC	mg/Kg	0.20	-	-	-
delta-BHC	mg/Kg	0.30	-	-	-
gamma-BHC (Lindane)	mg/Kg	0.06	-	-	-
gamma-Chlordane	mg/Kg	0.54	-	-	0.02 JN
Aldrin	mg/Kg	0.041	-	-	-
4,4'-DDD	mg/Kg	2.90	-	-	0.06 JN
4,4'-DDE	mg/Kg	2.10	0.00 J	0.004 J	0.03 JN
4,4'-DDT	mg/Kg	2.10	-	0.005 JN	0.02 JN
Dieldrin	mg/Kg	0.044	-	-	-
Endosulfan I	mg/Kg	0.90	-	-	-
Endosulfan II	mg/Kg	0.90	-	0.004 J	0.01 JN
Endosulfan sulfate	mg/Kg	1.00	-	-	-
Endrin	mg/Kg	0.10	-	-	0.01 JN
Endrin aldehyde	mg/Kg	-	-	-	-
Endrin ketone	mg/Kg	N/A	-	-	-
Heptachlor	mg/Kg	0.10	-	-	-
Heptachlor epoxide	mg/Kg	0.02	-	-	-
Methoxychlor	mg/Kg	N/A	0.02	0.01 JN	-
Toxaphene	mg/Kg	-	-	-	-
Total Pesticides	mg/kg	10.00	0.03	0.03	0.17
Aroclor-1016	mg/Kg	1, 10	-	-	-
Aroclor-1221	mg/Kg	1, 10	-	-	-
Aroclor-1232	mg/Kg	1, 10	-	-	-
Aroclor-1242	mg/Kg	1, 10	-	0.10	-
Aroclor-1248	mg/Kg	1, 10	-	-	-
Aroclor-1254	mg/Kg	1, 10	0.08	0.12	0.77 J
Aroclor-1260	mg/Kg	1, 10	-	-	0.57 J
TCLP VOLATILES					
NONE	mg/L				
TCLP SEMIVOLATILES					
NONE	mg/L				
TCLP PESTICIDES					
NONE	mg/L				

Table B.1: Test Pit Soil Sample Results

SAMPLE ID: RECOMMENDED		TP0701	TP0801	TP1001
DEPTH: SOIL CLEAN-UP		8'	2'	15'
LAB ID: OBJECTIVE		3067401	3067402	3067403
SOURCE: (see Note 1)		NYTEST	NYTEST	NYTEST
SDG:		SHD1	SHD1	SHD1
MATRIX:		SOIL	SOIL	SOIL
SAMPLED:		2/28/97	2/28/97	2/28/97
VALIDATED:		7/25/97	7/25/97	7/25/97
COMPOUND	UNITS:			
TCLP HERBICIDES				
NONE	mg/L			
INORGANICS				
Aluminum	mg/Kg	16200	13600	11200
Antimony	mg/Kg	1.6	2.60 J	2.80 J
Arsenic	mg/Kg	7.9	8.00	6.50
Barium	mg/Kg	300	137.00	69.50
Beryllium	mg/Kg	0.6	0.54 J	0.58 J
Cadmium	mg/Kg	1	1.20	1.50
Calcium	mg/Kg	1135	9630	18300
Chromium	mg/Kg	21.85	28.80	38.00
Cobalt	mg/Kg	30	12.10	14.00
Copper	mg/Kg	25	89.50	95.60
Iron	mg/Kg	33550	43200	41200
Lead	mg/Kg	14.3	240.00	291.00
Magnesium	mg/Kg	6085	5310	9510
Manganese	mg/Kg	918	672.00	888.00
Mercury	mg/Kg	0.1	-	-
Nickel	mg/Kg	34.5	31.70	30.60
Potassium	mg/Kg	1270	1180.00	1070.00
Selenium	mg/Kg	2	-	-
Silver	mg/Kg	N/A	0.60 J	0.32 J
Sodium	mg/Kg	167	361.00 J	355.00 J
Thallium	mg/Kg	ND	-	-
Vanadium	mg/Kg	150	20.00	25.20
Zinc	mg/Kg	69.25	281.00	216.00
Total Cyanide	mg/Kg	ND	-	-
TCLP METALS				
Arsenic	mg/L	5		
Barium	mg/L	100		
Cadmium	mg/L	1		
Lead	mg/L	5		
Silver	mg/L	5		

Notes:

1. See Tables 1.2 and 1.3 regarding how recommended cleanup objectives were derived.

Highlighted values exceed Recommended Soil Cleanup Ol

- = compound not detected mg/L = milligrams per

J = Estimated value N = tentatively identi

MDL = Method detection limit R = Data Rejected

mg/kg = milligrams per kilogram ND = not detected in

Table B.1: Test Pit Soil Sample Results

			SAMPLE ID: RECOMMENDED	TP1101	TP1102	TP1201
			DEPTH: SOIL CLEAN-UP	12'	4'	17'
			LAB ID: OBJECTIVE	3067404	3067405	3069501
			SOURCE: (see Note 1)	NYTEST	NYTEST	NYTEST
			SDG:	SHD1	SHD1	SHD1
			MATRIX:	SOIL	SOIL	SOIL
			SAMPLED:	2/28/97	2/28/97	3/03/97
			VALIDATED:	7/25/97	7/25/97	7/25/97
COMPOUND	UNITS:					
VOLATILES						
Acetone	mg/Kg	0.20		-	-	-
Benzene	mg/Kg	0.06		-	-	-
2-Butanone	mg/Kg	0.30		-	-	-
Chlorobenzene	mg/Kg	1.70		-	-	-
1,2-Dichloroethene (total)	mg/Kg	0.30		0.001 J	-	-
Ethylbenzene	mg/Kg	5.50		-	-	-
4-Methyl-2-Pentanone	mg/Kg	1.00		-	-	-
Methylene Chloride	mg/Kg	0.10		-	-	-
Tetrachloroethene	mg/Kg	1.40		-	-	-
Toluene	mg/Kg	1.50		-	-	-
Trichloroethene	mg/Kg	0.70		0.020	-	-
Vinyl Chloride	mg/Kg	0.20		-	-	-
Xylene (total)	mg/Kg	1.20		-	-	-
Total VOCs	mg/Kg	10.00		0.021	0.000	0.000
SEMIVOLATILES						
Acenaphthene	mg/Kg	50.00		-	-	0.05 J
Acenaphthylene	mg/Kg	41.00		-	-	-
Anthracene	mg/Kg	50.00		-	-	0.15 J
Benzo(a)anthracene	mg/Kg	0.224/MDL		0.12 J	-	0.19 J
Benzo(a)pyrene	mg/Kg	0.061/MDL		0.11 J	-	0.16 J
Benzo(b)fluoranthene	mg/Kg	1.10		-	-	-
Benzo(g,h,i)perylene	mg/Kg	50.00		-	-	0.08 J
Benzo(k)fluoranthene	mg/Kg	1.10		-	-	-
Butylbenzylphthalate	mg/Kg	50.00		-	-	0.05 J
Carbazole	mg/Kg	-		-	-	0.07 J
4-Chloroaniline	mg/Kg	0.220/MDL		-	-	-
Chrysene	mg/Kg	0.40		0.22 J	-	0.22 J
Di-n-butylphthalate	mg/Kg	8.10		-	-	-
Di-n-octylphthalate	mg/Kg	50.00		0.27 J	-	-
Dibenzofuran	mg/Kg	6.20		-	-	-
1,4-Dichlorobenzene	mg/Kg	-		-	-	-
Diethylphthalate	mg/Kg	7.10		-	-	-
Dimethylphthalate	mg/Kg	2.00		-	-	-
2,6-Dinitrotoluene	mg/Kg	1.00		-	-	-
Fluoranthene	mg/Kg	50.00		0.49 J	-	0.72 J
Fluorene	mg/Kg	50.00		-	-	0.11 J
Hexachlorocyclopentadiene	mg/Kg	-		-	-	-
Indeno(1,2,3-cd)pyrene	mg/Kg	3.20		-	-	0.10 J
2-Methylnaphthalene	mg/Kg	36.40		0.08 J	-	-
4-Methylphenol	mg/Kg	0.90		0.14 J	-	-
N-Nitrosodiphenylamine	mg/Kg	-		-	-	-
Naphthalene	mg/Kg	13.00		-	-	-

Table B.1: Test Pit Soil Sample Results

SAMPLE ID: RECOMMENDED			TP1101	TP1102	TP1201
DEPTH: SOIL CLEAN-UP			12'	4'	17'
LAB ID: OBJECTIVE			3067404	3067405	3069501
SOURCE: (see Note 1)			NYTEST	NYTEST	NYTEST
SDG:			SHD1	SHD1	SHD1
MATRIX:			SOIL	SOIL	SOIL
SAMPLED:			2/28/97	2/28/97	3/03/97
VALIDATED:			7/25/97	7/25/97	7/25/97
COMPOUND	UNITS:				
Pentachlorophenol	mg/Kg	1.0/MDL	-	-	-
Phenanthrene	mg/Kg	50.00	-	0.05 J	0.69 J
Phenol	mg/Kg	0.03/MDL	0.45 J	-	-
Pyrene	mg/Kg	50.00	0.50 J	-	0.46 J
1,2,4-Trichlorobenzene	mg/Kg	-	0.05 J	-	-
bis(2-Ethylhexyl)phthalate	mg/Kg	50.00	3.60	2.40	0.78 J
Total SVOCs	mg/Kg	500.00	6.03	2.45	3.83
PESTICIDES/PCBs					
alpha-BHC	mg/Kg	0.11	-	-	-
alpha-Chlordane	mg/Kg	0.54	-	0.001 JN	-
beta-BHC	mg/Kg	0.20	-	-	-
delta-BHC	mg/Kg	0.30	-	-	-
gamma-BHC (Lindane)	mg/Kg	0.06	-	-	-
gamma-Chlordane	mg/Kg	0.54	0.003 JN	0.003 JN	-
Aldrin	mg/Kg	0.041	-	-	-
4,4'-DDD	mg/Kg	2.90	-	0.03 J	-
4,4'-DDE	mg/Kg	2.10	0.03 J	0.02	-
4,4'-DDT	mg/Kg	2.10	0.03 JN	0.06 JN	-
Dieldrin	mg/Kg	0.044	-	0.00 J	-
Endosulfan I	mg/Kg	0.90	0.00 JN	-	-
Endosulfan II	mg/Kg	0.90	0.01 JN	0.01 JN	-
Endosulfan sulfate	mg/Kg	1.00	0.01 JN	-	-
Endrin	mg/Kg	0.10	-	0.003 JN	-
Endrin aldehyde	mg/Kg	-	-	0.02 J	0.01 JN
Endrin ketone	mg/Kg	N/A	-	-	-
Heptachlor	mg/Kg	0.10	-	-	-
Heptachlor epoxide	mg/Kg	0.02	-	-	-
Methoxychlor	mg/Kg	N/A	0.02 JN	-	-
Toxaphene	mg/Kg	-	-	-	-
Total Pesticides	mg/kg	10.00	0.11	0.15	0.01
Aroclor-1016	mg/Kg	1, 10	-	-	-
Aroclor-1221	mg/Kg	1, 10	-	-	-
Aroclor-1232	mg/Kg	1, 10	-	-	-
Aroclor-1242	mg/Kg	1, 10	-	-	-
Aroclor-1248	mg/Kg	1, 10	-	-	-
Aroclor-1254	mg/Kg	1, 10	0.85	-	0.04 JN
Aroclor-1260	mg/Kg	1, 10	-	0.44 J	-
TCLP VOLATILES					
NONE	mg/L		-		
TCLP SEMIVOLATILES					
NONE	mg/L		-		
TCLP PESTICIDES					
NONE	mg/L		-		

Table B.1: Test Pit Soil Sample Results

SAMPLE ID: RECOMMENDED		TP1101	TP1102	TP1201
DEPTH: SOIL CLEAN-UP		12'	4'	17'
LAB ID: OBJECTIVE		3067404	3067405	3069501
SOURCE: (see Note 1)		NYTEST	NYTEST	NYTEST
SDG:		SHD1	SHD1	SHD1
MATRIX:		SOIL	SOIL	SOIL
SAMPLED:		2/28/97	2/28/97	3/03/97
VALIDATED:		7/25/97	7/25/97	7/25/97
COMPOUND	UNITS:			
TCLP HERBICIDES				
NONE	mg/L	-		
INORGANICS				
Aluminum	mg/Kg	16200	11000	17200
Antimony	mg/Kg	1.6	5.40 J	2.00 J
Arsenic	mg/Kg	7.9	7.80	5.00
Barium	mg/Kg	300	111.00	82.80
Beryllium	mg/Kg	0.6	0.41 J	0.69
Cadmium	mg/Kg	1	1.70	-
Calcium	mg/Kg	1135	33400	1060
Chromium	mg/Kg	21.85	20.10	23.60
Cobalt	mg/Kg	30	10.90	14.30
Copper	mg/Kg	25	95.20	23.30
Iron	mg/Kg	33550	93000	31800
Lead	mg/Kg	14.3	189.00	11.40
Magnesium	mg/Kg	6085	3920	5450
Manganese	mg/Kg	918	740.00	527.00
Mercury	mg/Kg	0.1	0.15 J	-
Nickel	mg/Kg	34.5	27.40	185.00
Potassium	mg/Kg	1270	1180.00	2190.00
Selenium	mg/Kg	2	1.50	-
Silver	mg/Kg	N/A	0.81 J	0.46 J
Sodium	mg/Kg	167	866.00	295.00 J
Thallium	mg/Kg	ND	-	-
Vanadium	mg/Kg	150	19.10	22.90
Zinc	mg/Kg	69.25	327.00	150.00
Total Cyanide	mg/Kg	ND	-	-
TCLP METALS				
Arsenic	mg/L	5	0.31 J	
Barium	mg/L	100	1.80	
Cadmium	mg/L	1	0.05 J	
Lead	mg/L	5	1.10	
Silver	mg/L	5	0.06 J	

Notes:

1. See Tables 1.2 and 1.3 regarding how recommended cleanup objectives were derived.

Highlighted values exceed Recommended Soil Cleanup Ol

- = compound not detected mg/L = milligrams per

J = Estimated value N = tentatively identi

MDL = Method detection limit R = Data Rejected

mg/kg = milligrams per kilogram ND = not detected in

Table B.1: Test Pit Soil Sample Results

			DUP of TP1201		
	SAMPLE ID:	RECOMMENDED	TP1211	TP1601	TP1801
	DEPTH:	SOIL CLEAN-UP	17'	5'	8'
	LAB ID:	OBJECTIVE	3069504	3069505	3072001
	SOURCE:	(see Note 1)	NYTEST	NYTEST	NYTEST
	SDG:		SHD1	SHD1	SHD2
	MATRIX:		SOIL	SOIL	SOIL
	SAMPLED:		3/03/97	3/04/97	3/05/97
	VALIDATED:		7/25/97	7/25/97	7/25/97
COMPOUND	UNITS:				
VOLATILES					
Acetone	mg/Kg	0.20	-	-	0.032
Benzene	mg/Kg	0.06	-	-	-
2-Butanone	mg/Kg	0.30	-	0.023	-
Chlorobenzene	mg/Kg	1.70	-	-	0.012 J
1,2-Dichloroethene (total)	mg/Kg	0.30	-	-	-
Ethylbenzene	mg/Kg	5.50	-	0.28 J	0.071
4-Methyl-2-Pentanone	mg/Kg	1.00	-	-	-
Methylene Chloride	mg/Kg	0.10	-	-	0.003 J
Tetrachloroethene	mg/Kg	1.40	0.004 J	0.006 J	0.004 J
Toluene	mg/Kg	1.50	-	0.014	-
Trichloroethene	mg/Kg	0.70	0.002 J	-	-
Vinyl Chloride	mg/Kg	0.20	-	-	-
Xylene (total)	mg/Kg	1.20	0.001 J	0.21	0.270
Total VOCs	mg/Kg	10.00	0.007	0.53	0.392
SEMIVOLATILES					
Acenaphthene	mg/Kg	50.00	-	2.20	-
Acenaphthylene	mg/Kg	41.00	-	-	0.05 J
Anthracene	mg/Kg	50.00	-	0.72	-
Benzo(a)anthracene	mg/Kg	0.224/MDL	-	0.22 J	0.17 J
Benzo(a)pyrene	mg/Kg	0.061/MDL	-	0.17 J	0.21 J
Benzo(b)fluoranthene	mg/Kg	1.10	-	-	0.20 J
Benzo(g,h,i)perylene	mg/Kg	50.00	-	-	0.16 J
Benzo(k)fluoranthene	mg/Kg	1.10	-	-	0.21 J
Butylbenzylphthalate	mg/Kg	50.00	-	1.10	1.20
Carbazole	mg/Kg	-	-	-	-
4-Chloroaniline	mg/Kg	0.220/MDL	-	-	-
Chrysene	mg/Kg	0.40	-	0.31 J	0.31 J
Di-n-butylphthalate	mg/Kg	8.10	-	-	-
Di-n-octylphthalate	mg/Kg	50.00	-	0.22 J	-
Dibenzofuran	mg/Kg	6.20	-	1.60	-
1,4-Dichlorobenzene	mg/Kg	-	-	-	0.33 J
Diethylphthalate	mg/Kg	7.10	-	-	-
Dimethylphthalate	mg/Kg	2.00	-	-	0.10 J
2,6-Dinitrotoluene	mg/Kg	1.00	-	-	-
Fluoranthene	mg/Kg	50.00	0.07 J	0.67	-
Fluorene	mg/Kg	50.00	-	2.80	0.05 J
Hexachlorocyclopentadiene	mg/Kg	-	-	-	-
Indeno(1,2,3-cd)pyrene	mg/Kg	3.20	-	0.05 J	0.14 J
2-Methylnaphthalene	mg/Kg	36.40	-	34.00	0.30 J
4-Methylphenol	mg/Kg	0.90	-	0.68	-
N-Nitrosodiphenylamine	mg/Kg	-	-	-	-
Naphthalene	mg/Kg	13.00	-	7.00	0.40 J

Table B.1: Test Pit Soil Sample Results

			DUP of TP1201		
	SAMPLE ID:	RECOMMENDED	TP1211	TP1601	TP1801
	DEPTH:	SOIL CLEAN-UP	17'	5'	8'
	LAB ID:	OBJECTIVE	3069504	3069505	3072001
	SOURCE:	(see Note 1)	NYTEST	NYTEST	NYTEST
	SDG:		SHD1	SHD1	SHD2
	MATRIX:		SOIL	SOIL	SOIL
	SAMPLED:		3/03/97	3/04/97	3/05/97
	VALIDATED:		7/25/97	7/25/97	7/25/97
COMPOUND	UNITS:				
Pentachlorophenol	mg/Kg	1.0/MDL	-	-	-
Phenanthrene	mg/Kg	50.00	0.05 J	6.90	-
Phenol	mg/Kg	0.03/MDL	-	-	1.40
Pyrene	mg/Kg	50.00	0.05 J	0.75	0.25 J
1,2,4-Trichlorobenzene	mg/Kg	-	-	-	-
bis(2-Ethylhexyl)phthalate	mg/Kg	50.00	1.60 J	4.00 J	28.00 J
Total SVOCs	mg/Kg	500.00	1.78	63.39	33.49
PESTICIDES/PCBs					
alpha-BHC	mg/Kg	0.11	-	-	R
alpha-Chlordane	mg/Kg	0.54	-	-	0.002 JN
beta-BHC	mg/Kg	0.20	-	-	R
delta-BHC	mg/Kg	0.30	-	-	R
gamma-BHC (Lindane)	mg/Kg	0.06	-	-	R
gamma-Chlordane	mg/Kg	0.54	-	-	0.002 JN
Aldrin	mg/Kg	0.041	-	-	R
4,4'-DDD	mg/Kg	2.90	0.01 JN	0.01	0.07 J
4,4'-DDE	mg/Kg	2.10	0.004 J	-	R
4,4'-DDT	mg/Kg	2.10	0.01 JN	0.003 JN	R
Dieldrin	mg/Kg	0.044	0.003 JN	0.002 JN	R
Endosulfan I	mg/Kg	0.90	-	-	R
Endosulfan II	mg/Kg	0.90	-	-	R
Endosulfan sulfate	mg/Kg	1.00	-	-	R
Endrin	mg/Kg	0.10	-	-	R
Endrin aldehyde	mg/Kg	-	0.004 JN	0.004 JN	0.004 JN
Endrin ketone	mg/Kg	N/A	-	-	R
Heptachlor	mg/Kg	0.10	-	-	R
Heptachlor epoxide	mg/Kg	0.02	0.002 J	-	R
Methoxychlor	mg/Kg	N/A	0.01 J	-	R
Toxaphene	mg/Kg	-	-	-	R
Total Pesticides	mg/kg	10.00	0.04	0.02	0.08
Aroclor-1016	mg/Kg	1, 10	-	-	R
Aroclor-1221	mg/Kg	1, 10	-	-	R
Aroclor-1232	mg/Kg	1, 10	-	-	R
Aroclor-1242	mg/Kg	1, 10	-	0.35	R
Aroclor-1248	mg/Kg	1, 10	-	-	R
Aroclor-1254	mg/Kg	1, 10	0.13 J	0.09	0.05 J
Aroclor-1260	mg/Kg	1, 10	-	-	R
TCLP VOLATILES					
NONE	mg/L				
TCLP SEMIVOLATILES					
NONE	mg/L				
TCLP PESTICIDES					
NONE	mg/L				

Table B.1: Test Pit Soil Sample Results

			DUP of TP1201		
SAMPLE ID:	RECOMMENDED		TP1211	TP1601	TP1801
DEPTH:	SOIL CLEAN-UP		17'	5'	8'
LAB ID:	OBJECTIVE		3069504	3069505	3072001
SOURCE:	(see Note 1)		NYTEST	NYTEST	NYTEST
SDG:			SHD1	SHD1	SHD2
MATRIX:			SOIL	SOIL	SOIL
SAMPLED:			3/03/97	3/04/97	3/05/97
VALIDATED:			7/25/97	7/25/97	7/25/97
COMPOUND	UNITS:				
TCLP HERBICIDES					
NONE	mg/L				
INORGANICS					
Aluminum	mg/Kg	16200	26100	6610	14800
Antimony	mg/Kg	1.6	16.40 J	5.90 J	3.10 J
Arsenic	mg/Kg	7.9	31.50	4.80	14.20
Barium	mg/Kg	300	904.00 J	45.60 J	116.00
Beryllium	mg/Kg	0.6	0.27 J	0.10 J	0.39 J
Cadmium	mg/Kg	1	18.10	0.26 J	1.60
Calcium	mg/Kg	1135	55900	7280	8060
Chromium	mg/Kg	21.85	102.00	11.80	38.20
Cobalt	mg/Kg	30	17.20	6.00 J	12.00
Copper	mg/Kg	25	1820.00	11.90	34.20
Iron	mg/Kg	33550	105000 J	17100 J	44800 J
Lead	mg/Kg	14.3	1470.00 J	117.00 J	135.00
Magnesium	mg/Kg	6085	6150	3090	5000
Manganese	mg/Kg	918	777.00	304.00	533.00
Mercury	mg/Kg	0.1	0.15	-	0.16
Nickel	mg/Kg	34.5	249.00 J	15.30 J	31.80
Potassium	mg/Kg	1270	4950.00 J	519.00 J	1530.00
Selenium	mg/Kg	2	-	-	-
Silver	mg/Kg	N/A	10.30	13.60	0.37 J
Sodium	mg/Kg	167	2440.00	608.00 J	315.00 J
Thallium	mg/Kg	ND	-	-	-
Vanadium	mg/Kg	150	26.5	10.80	23.90
Zinc	mg/Kg	69.25	2320.00	109.00	368.00
Total Cyanide	mg/Kg	ND	-	-	-
TCLP METALS					
Arsenic	mg/L	5			
Barium	mg/L	100			
Cadmium	mg/L	1			
Lead	mg/L	5			
Silver	mg/L	5			

Notes:

1. See Tables 1.2 and 1.3 regarding how recommended cleanup objectives were derived.

Highlighted values exceed Recommended Soil Cleanup OL

- = compound not detected mg/L = milligrams per

J = Estimated value N = tentatively identified

MDL = Method detection limit R = Data Rejected

mg/kg = milligrams per kilogram ND = not detected in

Table B.1: Test Pit Soil Sample Results

	SAMPLE ID:	RECOMMENDED	TP1901	TP1902	TP2101
	DEPTH:	SOIL CLEAN-UP	10'	10'	3'
	LAB ID:	OBJECTIVE	3072002	3072003	3072006
	SOURCE:	(see Note 1)	NYTEST	NYTEST	NYTEST
	SDG:		SHD2	SHD2	SHD2
	MATRIX:		SOIL	SOIL	SOIL
	SAMPLED:		3/05/97	3/05/97	3/06/97
	VALIDATED:		7/25/97	7/25/97	7/25/97
COMPOUND	UNITS:				
VOLATILES					
Acetone	mg/Kg	0.20	-	0.020	-
Benzene	mg/Kg	0.06	-	-	-
2-Butanone	mg/Kg	0.30	-	-	-
Chlorobenzene	mg/Kg	1.70	-	-	-
1,2-Dichloroethene (total)	mg/Kg	0.30	-	0.006 J	-
Ethylbenzene	mg/Kg	5.50	0.004 J	0.011 J	-
4-Methyl-2-Pentanone	mg/Kg	1.00	-	-	-
Methylene Chloride	mg/Kg	0.10	0.004 J	0.003 J	-
Tetrachloroethene	mg/Kg	1.40	0.007 J	0.002 J	-
Toluene	mg/Kg	1.50	-	-	0.220 J
Trichloroethene	mg/Kg	0.70	0.002 J	0.040	-
Vinyl Chloride	mg/Kg	0.20	-	-	-
Xylene (total)	mg/Kg	1.20	0.020	0.031	-
Total VOCs	mg/Kg	10.00	0.037	0.113	0.220
SEMIVOLATILES					
Acenaphthene	mg/Kg	50.00	-	-	-
Acenaphthylene	mg/Kg	41.00	-	-	-
Anthracene	mg/Kg	50.00	-	-	-
Benzo(a)anthracene	mg/Kg	0.224/MDL	-	-	-
Benzo(a)pyrene	mg/Kg	0.061/MDL	-	-	-
Benzo(b)fluoranthene	mg/Kg	1.10	-	-	-
Benzo(g,h,i)perylene	mg/Kg	50.00	-	-	-
Benzo(k)fluoranthene	mg/Kg	1.10	-	-	-
Butylbenzylphthalate	mg/Kg	50.00	-	-	-
Carbazole	mg/Kg	-	-	-	-
4-Chloroaniline	mg/Kg	0.220/MDL	-	-	-
Chrysene	mg/Kg	0.40	-	-	-
Di-n-butylphthalate	mg/Kg	8.10	-	-	0.26 J
Di-n-octylphthalate	mg/Kg	50.00	-	-	-
Dibenzofuran	mg/Kg	6.20	-	-	-
1,4-Dichlorobenzene	mg/Kg	-	-	-	-
Diethylphthalate	mg/Kg	7.10	-	-	-
Dimethylphthalate	mg/Kg	2.00	-	-	-
2,6-Dinitrotoluene	mg/Kg	1.00	-	-	-
Fluoranthene	mg/Kg	50.00	-	-	0.18 J
Fluorene	mg/Kg	50.00	-	-	0.12 J
Hexachlorocyclopentadiene	mg/Kg	-	-	-	-
Indeno(1,2,3-cd)pyrene	mg/Kg	3.20	-	-	-
2-Methylnaphthalene	mg/Kg	36.40	-	-	0.07 J
4-Methylphenol	mg/Kg	0.90	-	-	-
N-Nitrosodiphenylamine	mg/Kg	-	-	-	-
Naphthalene	mg/Kg	13.00	-	-	0.16 J

Table B.1: Test Pit Soil Sample Results

		SAMPLE ID: RECOMMENDED	TP1901	TP1902	TP2101
		DEPTH: SOIL CLEAN-UP	10'	10'	3'
		LAB ID: OBJECTIVE	3072002	3072003	3072006
		SOURCE: (see Note 1)	NYTEST	NYTEST	NYTEST
		SDG:	SHD2	SHD2	SHD2
		MATRIX:	SOIL	SOIL	SOIL
		SAMPLED:	3/05/97	3/05/97	3/06/97
		VALIDATED:	7/25/97	7/25/97	7/25/97
COMPOUND	UNITS:				
Pentachlorophenol	mg/Kg	1.0/MDL	-	-	-
Phenanthrene	mg/Kg	50.00	-	-	0.34 J
Phenol	mg/Kg	0.03/MDL	-	-	-
Pyrene	mg/Kg	50.00	-	-	0.09 J
1,2,4-Trichlorobenzene	mg/Kg	-	-	-	-
bis(2-Ethylhexyl)phthalate	mg/Kg	50.00	-	-	-
Total SVOCs	mg/Kg	500.00	0.00	0.00	1.22
PESTICIDES/PCBs					
alpha-BHC	mg/Kg	0.11	-	-	-
alpha-Chlordane	mg/Kg	0.54	-	-	-
beta-BHC	mg/Kg	0.20	-	-	-
delta-BHC	mg/Kg	0.30	-	-	-
gamma-BHC (Lindane)	mg/Kg	0.06	-	-	-
gamma-Chlordane	mg/Kg	0.54	-	-	-
Aldrin	mg/Kg	0.041	-	-	-
4,4'-DDD	mg/Kg	2.90	-	0.005 JN	0.004 J
4,4'-DDE	mg/Kg	2.10	-	-	0.002 J
4,4'-DDT	mg/Kg	2.10	-	0.003 JN	-
Dieldrin	mg/Kg	0.044	-	-	-
Endosulfan I	mg/Kg	0.90	-	-	-
Endosulfan II	mg/Kg	0.90	-	-	-
Endosulfan sulfate	mg/Kg	1.00	-	-	-
Endrin	mg/Kg	0.10	-	-	-
Endrin aldehyde	mg/Kg	-	-	0.004 J	-
Endrin ketone	mg/Kg	N/A	-	-	-
Heptachlor	mg/Kg	0.10	-	-	-
Heptachlor epoxide	mg/Kg	0.02	-	-	-
Methoxychlor	mg/Kg	N/A	-	-	-
Toxaphene	mg/Kg	-	-	-	-
Total Pesticides	mg/kg	10.00	0.00	0.01	0.01
Aroclor-1016	mg/Kg	1, 10	-	-	-
Aroclor-1221	mg/Kg	1, 10	-	-	-
Aroclor-1232	mg/Kg	1, 10	-	-	-
Aroclor-1242	mg/Kg	1, 10	-	-	-
Aroclor-1248	mg/Kg	1, 10	-	-	-
Aroclor-1254	mg/Kg	1, 10	-	0.05	-
Aroclor-1260	mg/Kg	1, 10	-	-	0.04 J
TCLP VOLATILES					
NONE	mg/L				
TCLP SEMIVOLATILES					
NONE	mg/L				
TCLP PESTICIDES					
NONE	mg/L				

Table B.1: Test Pit Soil Sample Results

SAMPLE ID: RECOMMENDED		TP1901	TP1902	TP2101
DEPTH: SOIL CLEAN-UP		10'	10'	3'
LAB ID: OBJECTIVE		3072002	3072003	3072006
SOURCE: (see Note 1)		NYTEST	NYTEST	NYTEST
SDG:		SHD2	SHD2	SHD2
MATRIX:		SOIL	SOIL	SOIL
SAMPLED:		3/05/97	3/05/97	3/06/97
VALIDATED:		7/25/97	7/25/97	7/25/97
COMPOUND	UNITS:			
TCLP HERBICIDES				
NONE	mg/L			
INORGANICS				
Aluminum	mg/Kg	16200	22000	17500
Antimony	mg/Kg	1.6	6.70 J	5.40 J
Arsenic	mg/Kg	7.9	16.20	11.70
Barium	mg/Kg	300	424.00	214.00
Beryllium	mg/Kg	0.6	0.42 J	0.32 J
Cadmium	mg/Kg	1	39.90	19.00
Calcium	mg/Kg	1135	26900	14700
Chromium	mg/Kg	21.85	70.70	55.20
Cobalt	mg/Kg	30	16.30	19.90
Copper	mg/Kg	25	718.00	346.00
Iron	mg/Kg	33550	112000 J	89200 J
Lead	mg/Kg	14.3	1410.00	759.00
Magnesium	mg/Kg	6085	9130	6410
Manganese	mg/Kg	918	931.00	917.00
Mercury	mg/Kg	0.1	0.07 J	0.18
Nickel	mg/Kg	34.5	176.00	114.00
Potassium	mg/Kg	1270	4850.00	2360.00
Selenium	mg/Kg	2	-	-
Silver	mg/Kg	N/A	5.40	193.00
Sodium	mg/Kg	167	1890.00	874.00
Thallium	mg/Kg	ND	-	-
Vanadium	mg/Kg	150	33.40	24.20
Zinc	mg/Kg	69.25	3590.00	1580.00
Total Cyanide	mg/Kg	ND	0.73	-
TCLP METALS				
Arsenic	mg/L	5		
Barium	mg/L	100		
Cadmium	mg/L	1		
Lead	mg/L	5		
Silver	mg/L	5		

Notes:

1. See Tables 1.2 and 1.3 regarding how recommended cleanup objectives were derived.

Highlighted values exceed Recommended Soil Cleanup Ol

- = compound not detected mg/L = milligrams per

J = Estimated value N = tentatively identi

MDL = Method detection limit R = Data Rejected

mg/kg = milligrams per kilogram ND = not detected in

Table B.1: Test Pit Soil Sample Results

			DUP of TP2701		
	SAMPLE ID:	RECOMMENDED	TP2701	TP2711	TP3001
	DEPTH:	SOIL CLEAN-UP	10'	10'	4'
	LAB ID:	OBJECTIVE	3076001	3076004	3076005
	SOURCE:	(see Note 1)	NYTEST	NYTEST	NYTEST
	SDG:		SHD2	SHD2	SHD2
	MATRIX:		SOIL	SOIL	SOIL
	SAMPLED:		3/10/97	3/10/97	3/11/97
	VALIDATED:		7/25/97	7/25/97	7/25/97
COMPOUND	UNITS:				
VOLATILES					
Acetone	mg/Kg	0.20	-	-	0.028 J
Benzene	mg/Kg	0.06	-	-	0.004 J
2-Butanone	mg/Kg	0.30	-	-	-
Chlorobenzene	mg/Kg	1.70	-	-	-
1,2-Dichloroethene (total)	mg/Kg	0.30	-	-	-
Ethylbenzene	mg/Kg	5.50	-	-	0.090 J
4-Methyl-2-Pentanone	mg/Kg	1.00	-	-	-
Methylene Chloride	mg/Kg	0.10	0.013	0.012 J	0.023 J
Tetrachloroethene	mg/Kg	1.40	-	-	0.008 J
Toluene	mg/Kg	1.50	-	-	-
Trichloroethene	mg/Kg	0.70	0.009 J	0.009 J	-
Vinyl Chloride	mg/Kg	0.20	-	-	-
Xylene (total)	mg/Kg	1.20	-	-	0.079 J
Total VOCs	mg/Kg	10.00	0.022	0.021	0.232
SEMIVOLATILES					
Acenaphthene	mg/Kg	50.00	-	-	-
Acenaphthylene	mg/Kg	41.00	-	-	-
Anthracene	mg/Kg	50.00	-	-	-
Benzo(a)anthracene	mg/Kg	0.224/MDL	-	-	-
Benzo(a)pyrene	mg/Kg	0.061/MDL	-	-	-
Benzo(b)fluoranthene	mg/Kg	1.10	-	-	-
Benzo(g,h,i)perylene	mg/Kg	50.00	-	-	-
Benzo(k)fluoranthene	mg/Kg	1.10	-	-	-
Butylbenzylphthalate	mg/Kg	50.00	-	-	-
Carbazole	mg/Kg	-	-	-	-
4-Chloroaniline	mg/Kg	0.220/MDL	-	-	-
Chrysene	mg/Kg	0.40	-	-	0.27 J
Di-n-butylphthalate	mg/Kg	8.10	0.54 J	-	1.00 J
Di-n-octylphthalate	mg/Kg	50.00	-	-	-
Dibenzofuran	mg/Kg	6.20	-	-	-
1,4-Dichlorobenzene	mg/Kg	-	-	-	-
Diethylphthalate	mg/Kg	7.10	-	-	-
Dimethylphthalate	mg/Kg	2.00	-	-	0.20 J
2,6-Dinitrotoluene	mg/Kg	1.00	-	-	0.29 J
Fluoranthene	mg/Kg	50.00	-	-	1.50 J
Fluorene	mg/Kg	50.00	-	-	0.22 J
Hexachlorocyclopentadiene	mg/Kg	-	-	-	-
Indeno(1,2,3-cd)pyrene	mg/Kg	3.20	-	-	-
2-Methylnaphthalene	mg/Kg	36.40	-	-	1.20 J
4-Methylphenol	mg/Kg	0.90	-	-	0.21 J
N-Nitrosodiphenylamine	mg/Kg	-	-	-	0.72 J
Naphthalene	mg/Kg	13.00	-	-	1.10 J

Table B.1: Test Pit Soil Sample Results

			DUP of TP2701		
	SAMPLE ID:	RECOMMENDED	TP2701	TP2711	TP3001
	DEPTH:	SOIL CLEAN-UP	10'	10'	4'
	LAB ID:	OBJECTIVE	3076001	3076004	3076005
	SOURCE:	(see Note 1)	NYTEST	NYTEST	NYTEST
	SDG:		SHD2	SHD2	SHD2
	MATRIX:		SOIL	SOIL	SOIL
	SAMPLED:		3/10/97	3/10/97	3/11/97
	VALIDATED:		7/25/97	7/25/97	7/25/97
COMPOUND	UNITS:				
Pentachlorophenol	mg/Kg	1.0/MDL	-	-	-
Phenanthrene	mg/Kg	50.00	-	-	1.00 J
Phenol	mg/Kg	0.03/MDL	-	-	-
Pyrene	mg/Kg	50.00	-	-	0.58 J
1,2,4-Trichlorobenzene	mg/Kg	-	-	-	0.14 J
bis(2-Ethylhexyl)phthalate	mg/Kg	50.00	-	-	23.00 J
Total SVOCs	mg/Kg	500.00	0.54	0.00	31.43
PESTICIDES/PCBs					
alpha-BHC	mg/Kg	0.11	-	-	-
alpha-Chlordane	mg/Kg	0.54	-	-	0.01 JN
beta-BHC	mg/Kg	0.20	-	-	-
delta-BHC	mg/Kg	0.30	-	-	-
gamma-BHC (Lindane)	mg/Kg	0.06	-	-	-
gamma-Chlordane	mg/Kg	0.54	-	-	0.01 JN
Aldrin	mg/Kg	0.041	-	-	-
4,4'-DDD	mg/Kg	2.90	-	-	0.11 JN
4,4'-DDE	mg/Kg	2.10	-	-	0.03 J
4,4'-DDT	mg/Kg	2.10	0.003 JN	-	0.02 JN
Dieldrin	mg/Kg	0.044	0.004	-	0.01 J
Endosulfan I	mg/Kg	0.90	-	-	-
Endosulfan II	mg/Kg	0.90	-	-	-
Endosulfan sulfate	mg/Kg	1.00	-	-	0.01 J
Endrin	mg/Kg	0.10	-	-	-
Endrin aldehyde	mg/Kg	-	0.003 JN	-	-
Endrin ketone	mg/Kg	N/A	-	-	-
Heptachlor	mg/Kg	0.10	-	-	0.005 JN
Heptachlor epoxide	mg/Kg	0.02	-	-	-
Methoxychlor	mg/Kg	N/A	-	-	-
Toxaphene	mg/Kg	-	-	-	-
Total Pesticides	mg/kg	10.00	0.01	0.00	0.20
Aroclor-1016	mg/Kg	1, 10	-	-	0.71 J
Aroclor-1221	mg/Kg	1, 10	-	-	-
Aroclor-1232	mg/Kg	1, 10	-	-	-
Aroclor-1242	mg/Kg	1, 10	-	-	-
Aroclor-1248	mg/Kg	1, 10	-	-	-
Aroclor-1254	mg/Kg	1, 10	0.04 J	0.03 J	0.59 J
Aroclor-1260	mg/Kg	1, 10	-	-	0.67 J
TCLP VOLATILES					
NONE	mg/L				
TCLP SEMIVOLATILES					
NONE	mg/L				
TCLP PESTICIDES					
NONE	mg/L				

Table B.1: Test Pit Soil Sample Results

			DUP of TP2701		
SAMPLE ID:	RECOMMENDED	TP2701	TP2711	TP3001	
DEPTH:	SOIL CLEAN-UP	10'	10'	4'	
LAB ID:	OBJECTIVE	3076001	3076004	3076005	
SOURCE:	(see Note 1)	NYTEST	NYTEST	NYTEST	
SDG:		SHD2	SHD2	SHD2	
MATRIX:		SOIL	SOIL	SOIL	
SAMPLED:		3/10/97	3/10/97	3/11/97	
VALIDATED:		7/25/97	7/25/97	7/25/97	
COMPOUND	UNITS:				
TCLP HERBICIDES					
NONE	mg/L				
INORGANICS					
Aluminum	mg/Kg	16200	12900	13000	6990 J
Antimony	mg/Kg	1.6	4.50 J	1.90 J	9.00 J
Arsenic	mg/Kg	7.9	8.50	7.20	18.20 J
Barium	mg/Kg	300	83.90	84.20	270.00 J
Beryllium	mg/Kg	0.6	0.31 J	0.30 J	-
Cadmium	mg/Kg	1	6.10	3.10	4.70 J
Calcium	mg/Kg	1135	17900 J	61900 J	23200 J
Chromium	mg/Kg	21.85	114.00 J	52.90 J	121.00 J
Cobalt	mg/Kg	30	12.70	9.10	33.40 J
Copper	mg/Kg	25	227.00 J	114.00 J	134.00 J
Iron	mg/Kg	33550	71800 J	42600 J	298000 J
Lead	mg/Kg	14.3	801.00 J	371.00 J	417.00 J
Magnesium	mg/Kg	6085	5930	8520	1650 J
Manganese	mg/Kg	918	617.00	598.00	1850 J
Mercury	mg/Kg	0.1	0.11 J	-	0.24 J
Nickel	mg/Kg	34.5	63.60 J	35.90 J	218.00 J
Potassium	mg/Kg	1270	2020.00	2330.00	1140.00 J
Selenium	mg/Kg	2	-	-	-
Silver	mg/Kg	N/A	0.98 J	0.52 J	-
Sodium	mg/Kg	167	508.00 J	551.00 J	1690.00 J
Thallium	mg/Kg	ND	-	-	-
Vanadium	mg/Kg	150	23.80	22.60	19.00 J
Zinc	mg/Kg	69.25	683.00	488.00	4130.00 J
Total Cyanide	mg/Kg	ND	0.80 J	-	-
TCLP METALS					
Arsenic	mg/L	5			
Barium	mg/L	100			
Cadmium	mg/L	1			
Lead	mg/L	5			
Silver	mg/L	5			

Notes:

1. See Tables 1.2 and 1.3 regarding how recommended cleanup objectives were derived.

Highlighted values exceed Recommended Soil Cleanup O

- = compound not detected mg/L = milligrams pe

J = Estimated value N = tentatively identi

MDL = Method detection limit R = Data Rejected

mg/kg = milligrams per kilogram ND = not detected in

Table B.1: Test Pit Soil Sample Results

		SAMPLE ID: RECOMMENDED	TP3201	TP3601	TP3602
		DEPTH: SOIL CLEAN-UP	1'	2'	3'
		LAB ID: OBJECTIVE	3076006	3076801	3076802
		SOURCE: (see Note 1)	NYTEST	NYTEST	NYTEST
		SDG:	SHD2	SHD2	SHD2
		MATRIX:	SOIL	SOIL	SOIL
		SAMPLED:	3/11/97	3/12/97	3/12/97
		VALIDATED:	7/25/97	7/25/97	7/25/97
COMPOUND	UNITS:				
VOLATILES					
Acetone	mg/Kg	0.20	0.008 J	-	-
Benzene	mg/Kg	0.06	-	-	-
2-Butanone	mg/Kg	0.30	-	-	-
Chlorobenzene	mg/Kg	1.70	-	-	-
1,2-Dichloroethene (total)	mg/Kg	0.30	-	-	-
Ethylbenzene	mg/Kg	5.50	0.002 J	-	-
4-Methyl-2-Pentanone	mg/Kg	1.00	-	-	-
Methylene Chloride	mg/Kg	0.10	0.010 J	0.007 J	0.007 J
Tetrachloroethene	mg/Kg	1.40	-	-	-
Toluene	mg/Kg	1.50	0.001 J	-	-
Trichloroethene	mg/Kg	0.70	-	-	-
Vinyl Chloride	mg/Kg	0.20	-	-	-
Xylene (total)	mg/Kg	1.20	0.005 J	-	-
Total VOCs	mg/Kg	10.00	0.026	0.007	0.007
SEMIVOLATILES					
Acenaphthene	mg/Kg	50.00	-	-	-
Acenaphthylene	mg/Kg	41.00	-	-	-
Anthracene	mg/Kg	50.00	-	-	-
Benzo(a)anthracene	mg/Kg	0.224/MDL	-	-	-
Benzo(a)pyrene	mg/Kg	0.061/MDL	-	-	-
Benzo(b)fluoranthene	mg/Kg	1.10	-	-	-
Benzo(g,h,i)perylene	mg/Kg	50.00	-	-	-
Benzo(k)fluoranthene	mg/Kg	1.10	-	-	-
Butylbenzylphthalate	mg/Kg	50.00	-	-	-
Carbazole	mg/Kg	-	-	-	-
4-Chloroaniline	mg/Kg	0.220/MDL	-	-	-
Chrysene	mg/Kg	0.40	-	-	-
Di-n-butylphthalate	mg/Kg	8.10	-	-	-
Di-n-octylphthalate	mg/Kg	50.00	-	-	-
Dibenzofuran	mg/Kg	6.20	-	-	-
1,4-Dichlorobenzene	mg/Kg	-	-	-	-
Diethylphthalate	mg/Kg	7.10	-	-	-
Dimethylphthalate	mg/Kg	2.00	-	-	-
2,6-Dinitrotoluene	mg/Kg	1.00	-	-	-
Fluoranthene	mg/Kg	50.00	-	-	-
Fluorene	mg/Kg	50.00	-	-	-
Hexachlorocyclopentadiene	mg/Kg	-	-	-	-
Indeno(1,2,3-cd)pyrene	mg/Kg	3.20	-	-	-
2-Methylnaphthalene	mg/Kg	36.40	-	-	-
4-Methylphenol	mg/Kg	0.90	0.04 J	-	-
N-Nitrosodiphenylamine	mg/Kg	-	-	-	-
Naphthalene	mg/Kg	13.00	-	-	-

Table B.1: Test Pit Soil Sample Results

		SAMPLE ID: RECOMMENDED	TP3201	TP3601	TP3602
		DEPTH: SOIL CLEAN-UP	1'	2'	3'
		LAB ID: OBJECTIVE	3076006	3076801	3076802
		SOURCE: (see Note 1)	NYTEST	NYTEST	NYTEST
		SDG:	SHD2	SHD2	SHD2
		MATRIX:	SOIL	SOIL	SOIL
		SAMPLED:	3/11/97	3/12/97	3/12/97
		VALIDATED:	7/25/97	7/25/97	7/25/97
COMPOUND	UNITS:				
Pentachlorophenol	mg/Kg	1.0/MDL	-	-	-
Phenanthrene	mg/Kg	50.00	-	-	-
Phenol	mg/Kg	0.03/MDL	-	-	-
Pyrene	mg/Kg	50.00	-	-	-
1,2,4-Trichlorobenzene	mg/Kg	-	-	-	-
bis(2-Ethylhexyl)phthalate	mg/Kg	50.00	-	-	-
Total SVOCs	mg/Kg	500.00	0.04	0.00	0.00
PESTICIDES/PCBs					
alpha-BHC	mg/Kg	0.11	-	-	-
alpha-Chlordane	mg/Kg	0.54	-	-	-
beta-BHC	mg/Kg	0.20	-	-	-
delta-BHC	mg/Kg	0.30	-	-	-
gamma-BHC (Lindane)	mg/Kg	0.06	-	-	-
gamma-Chlordane	mg/Kg	0.54	0.01 J	-	-
Aldrin	mg/Kg	0.041	-	-	-
4,4'-DDD	mg/Kg	2.90	0.005 JN	-	-
4,4'-DDE	mg/Kg	2.10	0.01 JN	-	-
4,4'-DDT	mg/Kg	2.10	-	-	-
Dieldrin	mg/Kg	0.044	-	-	-
Endosulfan I	mg/Kg	0.90	0.003 JN	-	-
Endosulfan II	mg/Kg	0.90	-	-	-
Endosulfan sulfate	mg/Kg	1.00	0.01 JN	-	-
Endrin	mg/Kg	0.10	0.003 JN	-	-
Endrin aldehyde	mg/Kg	-	-	-	-
Endrin ketone	mg/Kg	N/A	-	-	-
Heptachlor	mg/Kg	0.10	0.01 JN	-	-
Heptachlor epoxide	mg/Kg	0.02	-	-	-
Methoxychlor	mg/Kg	N/A	-	-	-
Toxaphene	mg/Kg	-	-	-	-
Total Pesticides	mg/kg	10.00	0.06	0.00	0.00
Aroclor-1016	mg/Kg	1, 10	-	-	-
Aroclor-1221	mg/Kg	1, 10	-	-	-
Aroclor-1232	mg/Kg	1, 10	-	-	-
Aroclor-1242	mg/Kg	1, 10	-	-	-
Aroclor-1248	mg/Kg	1, 10	4.00	-	-
Aroclor-1254	mg/Kg	1, 10	-	-	-
Aroclor-1260	mg/Kg	1, 10	-	-	-
TCLP VOLATILES					
NONE	mg/L				
TCLP SEMIVOLATILES					
NONE	mg/L				
TCLP PESTICIDES					
NONE	mg/L				

Table B.1: Test Pit Soil Sample Results

SAMPLE ID: RECOMMENDED		TP3201	TP3601	TP3602
DEPTH: SOIL CLEAN-UP		1'	2'	3'
LAB ID: OBJECTIVE		3076006	3076801	3076802
SOURCE: (see Note 1)		NYTEST	NYTEST	NYTEST
SDG:		SHD2	SHD2	SHD2
MATRIX:		SOIL	SOIL	SOIL
SAMPLED:		3/11/97	3/12/97	3/12/97
VALIDATED:		7/25/97	7/25/97	7/25/97
COMPOUND	UNITS:			
TCLP HERBICIDES				
NONE	mg/L			
INORGANICS				
Aluminum	mg/Kg	16200	14600	15700
Antimony	mg/Kg	1.6	1.70 J	2.10 J
Arsenic	mg/Kg	7.9	5.80	7.80
Barium	mg/Kg	300	96.50	77.70
Beryllium	mg/Kg	0.6	0.37 J	0.46 J
Cadmium	mg/Kg	1	-	-
Calcium	mg/Kg	1135	784	688
Chromium	mg/Kg	21.85	19.60	21.20
Cobalt	mg/Kg	30	11.70	13.00
Copper	mg/Kg	25	19.70	17.60
Iron	mg/Kg	33550	26000 J	85300 J
Lead	mg/Kg	14.3	17.90	7.50
Magnesium	mg/Kg	6085	4570	5600
Manganese	mg/Kg	918	336.00	529.00
Mercury	mg/Kg	0.1	-	-
Nickel	mg/Kg	34.5	29.10	30.10
Potassium	mg/Kg	1270	1200.00	1780.00
Selenium	mg/Kg	2	-	-
Silver	mg/Kg	N/A	0.29 J	-
Sodium	mg/Kg	167	208.00 J	185.00 J
Thallium	mg/Kg	ND	-	-
Vanadium	mg/Kg	150	19.20	20.30
Zinc	mg/Kg	69.25	138.00	62.10
Total Cyanide	mg/Kg	ND	-	-
TCLP METALS				
Arsenic	mg/L	5		
Barium	mg/L	100		
Cadmium	mg/L	1		
Lead	mg/L	5		
Silver	mg/L	5		

Notes:

1. See Tables 1.2 and 1.3 regarding how recommended cleanup objectives were derived.

Highlighted values exceed Recommended Soil Cleanup Objectives

- = compound not detected mg/L = milligrams per liter

J = Estimated value N = tentatively identified

MDL = Method detection limit R = Data Rejected

mg/kg = milligrams per kilogram ND = not detected in

Table B.1: Test Pit Soil Sample Results

COMPOUND	DUP of TP3901				
	SAMPLE ID:	RECOMMENDED	TP3801	TP3901	TP3911
	DEPTH:	SOIL CLEAN-UP	2'	1'	1'
	LAB ID:	OBJECTIVE	3078701	3079701	3079704
	SOURCE:	(see Note 1)	NYTEST	NYTEST	NYTEST
	SDG:		SHD3	SHD3	SHD3
	MATRIX:		SOIL	SOIL	SOIL
	SAMPLED:		3/13/97	3/17/97	3/17/97
	VALIDATED:		7/25/97	7/25/97	7/25/97
COMPOUND	UNITS:				
VOLATILES					
Acetone	mg/Kg	0.20	0.005 J	-	0.003 J
Benzene	mg/Kg	0.06	-	-	-
2-Butanone	mg/Kg	0.30	-	-	-
Chlorobenzene	mg/Kg	1.70	-	-	-
1,2-Dichloroethene (total)	mg/Kg	0.30	-	-	-
Ethylbenzene	mg/Kg	5.50	-	-	-
4-Methyl-2-Pentanone	mg/Kg	1.00	-	-	-
Methylene Chloride	mg/Kg	0.10	-	-	-
Tetrachloroethene	mg/Kg	1.40	-	-	-
Toluene	mg/Kg	1.50	-	-	-
Trichloroethene	mg/Kg	0.70	0.002 J	0.017 J	0.006 J
Vinyl Chloride	mg/Kg	0.20	-	-	-
Xylene (total)	mg/Kg	1.20	-	-	-
Total VOCs	mg/Kg	10.00	0.007	0.017	0.009
SEMIVOLATILES					
Acenaphthene	mg/Kg	50.00	-	0.07 J	-
Acenaphthylene	mg/Kg	41.00	-	-	-
Anthracene	mg/Kg	50.00	-	0.09 J	0.05 J
Benzo(a)anthracene	mg/Kg	0.224/MDL	-	0.40 J	0.19 J
Benzo(a)pyrene	mg/Kg	0.061/MDL	-	0.30 J	0.16 J
Benzo(b)fluoranthene	mg/Kg	1.10	-	0.29 J	0.22 J
Benzo(g,h,i)perylene	mg/Kg	50.00	-	0.13 J	0.09 J
Benzo(k)fluoranthene	mg/Kg	1.10	-	0.29 J	0.14 J
Butylbenzylphthalate	mg/Kg	50.00	-	-	-
Carbazole	mg/Kg	-	-	0.09 J	-
4-Chloroaniline	mg/Kg	0.220/MDL	-	-	R
Chrysene	mg/Kg	0.40	-	0.58 J	0.26 J
Di-n-butylphthalate	mg/Kg	8.10	-	-	-
Di-n-octylphthalate	mg/Kg	50.00	-	-	-
Dibenzofuran	mg/Kg	6.20	-	0.05 J	-
1,4-Dichlorobenzene	mg/Kg	-	-	-	-
Diethylphthalate	mg/Kg	7.10	-	-	-
Dimethylphthalate	mg/Kg	2.00	-	-	-
2,6-Dinitrotoluene	mg/Kg	1.00	-	-	-
Fluoranthene	mg/Kg	50.00	-	0.84 J	0.39 J
Fluorene	mg/Kg	50.00	-	0.06 J	-
Hexachlorocyclopentadiene	mg/Kg	-	-	-	-
Indeno(1,2,3-cd)pyrene	mg/Kg	3.20	-	0.15 J	0.09 J
2-Methylnaphthalene	mg/Kg	36.40	-	-	-
4-Methylphenol	mg/Kg	0.90	-	-	-
N-Nitrosodiphenylamine	mg/Kg	-	-	-	-
Naphthalene	mg/Kg	13.00	-	0.05 J	-

Table B.1: Test Pit Soil Sample Results

			DUP of TP3901		
	SAMPLE ID:	RECOMMENDED	TP3801	TP3901	TP3911
	DEPTH:	SOIL CLEAN-UP	2'	1'	1'
	LAB ID:	OBJECTIVE	3078701	3079701	3079704
	SOURCE:	(see Note 1)	NYTEST	NYTEST	NYTEST
	SDG:		SHD3	SHD3	SHD3
	MATRIX:		SOIL	SOIL	SOIL
	SAMPLED:		3/13/97	3/17/97	3/17/97
	VALIDATED:		7/25/97	7/25/97	7/25/97
COMPOUND	UNITS:				
Pentachlorophenol	mg/Kg	1.0/MDL	-	-	-
Phenanthrene	mg/Kg	50.00	-	0.65 J	0.32 J
Phenol	mg/Kg	0.03/MDL	0.25 J	-	-
Pyrene	mg/Kg	50.00	-	0.75 J	0.31 J
1,2,4-Trichlorobenzene	mg/Kg	-	-	-	-
bis(2-Ethylhexyl)phthalate	mg/Kg	50.00	1.50	-	-
Total SVOCs	mg/Kg	500.00	1.75	4.78	2.22
PESTICIDES/PCBs					
alpha-BHC	mg/Kg	0.11	-	-	-
alpha-Chlordane	mg/Kg	0.54	-	-	-
beta-BHC	mg/Kg	0.20	-	-	-
delta-BHC	mg/Kg	0.30	-	-	-
gamma-BHC (Lindane)	mg/Kg	0.06	-	-	-
gamma-Chlordane	mg/Kg	0.54	-	-	-
Aldrin	mg/Kg	0.041	-	-	-
4,4'-DDD	mg/Kg	2.90	-	-	-
4,4'-DDE	mg/Kg	2.10	-	0.004 JN	0.003 J
4,4'-DDT	mg/Kg	2.10	.0033 J	0.02 JN	0.02 J
Dieldrin	mg/Kg	0.044	-	-	-
Endosulfan I	mg/Kg	0.90	-	-	-
Endosulfan II	mg/Kg	0.90	-	-	-
Endosulfan sulfate	mg/Kg	1.00	-	-	-
Endrin	mg/Kg	0.10	-	-	-
Endrin aldehyde	mg/Kg	-	-	-	-
Endrin ketone	mg/Kg	N/A	-	0.004 J	-
Heptachlor	mg/Kg	0.10	-	-	-
Heptachlor epoxide	mg/Kg	0.02	-	-	-
Methoxychlor	mg/Kg	N/A	-	-	-
Toxaphene	mg/Kg	-	-	-	-
Total Pesticides	mg/kg	10.00	0.00	0.03	0.02
Aroclor-1016	mg/Kg	1, 10	-	-	-
Aroclor-1221	mg/Kg	1, 10	-	-	-
Aroclor-1232	mg/Kg	1, 10	-	-	-
Aroclor-1242	mg/Kg	1, 10	-	-	-
Aroclor-1248	mg/Kg	1, 10	-	-	-
Aroclor-1254	mg/Kg	1, 10	-	0.04	0.03 J
Aroclor-1260	mg/Kg	1, 10	0.03 J	-	-
TCLP VOLATILES					
NONE	mg/L				
TCLP SEMIVOLATILES					
NONE	mg/L				
TCLP PESTICIDES					
NONE	mg/L				

Table B.1: Test Pit Soil Sample Results

			DUP of TP3901		
SAMPLE ID: RECOMMENDED		TP3801	TP3901	TP3911	
DEPTH: SOIL CLEAN-UP		2'	1'	1'	
LAB ID: OBJECTIVE		3078701	3079701	3079704	
SOURCE: (see Note 1)		NYTEST	NYTEST	NYTEST	
SDG:		SHD3	SHD3	SHD3	
MATRIX:		SOIL	SOIL	SOIL	
SAMPLED:		3/13/97	3/17/97	3/17/97	
VALIDATED:		7/25/97	7/25/97	7/25/97	
COMPOUND	UNITS:				
TCLP HERBICIDES					
NONE	mg/L				
INORGANICS					
Aluminum	mg/Kg	16200	9960	11500 J	395 J
Antimony	mg/Kg	1.6	1.70 J	1.80 J	21.90 J
Arsenic	mg/Kg	7.9	7.90 J	10.90 J	6.50
Barium	mg/Kg	300	155.00	298.00 J	12.70 J
Beryllium	mg/Kg	0.6	0.43 J	0.37 J	-
Cadmium	mg/Kg	1	-	1.80 J	-
Calcium	mg/Kg	1135	1220	11500 J	3900 J
Chromium	mg/Kg	21.85	13.40 J	19.00 J	435.00 J
Cobalt	mg/Kg	30	8.70 J	9.80 J	3.90 J
Copper	mg/Kg	25	17.30 J	87.00 J	12.50 J
Iron	mg/Kg	33550	22900	24900 J	6350 J
Lead	mg/Kg	14.3	9.30	700.00 J	14.60 J
Magnesium	mg/Kg	6085	3420	4070 J	461 J
Manganese	mg/Kg	918	692	646.00 J	2610 J
Mercury	mg/Kg	0.1	-	0.20	0.18
Nickel	mg/Kg	34.5	22.50	25.90 J	194.00 J
Potassium	mg/Kg	1270	1290.00	1190.00 J	535.00 J
Selenium	mg/Kg	2	-	-	-
Silver	mg/Kg	N/A	-	0.73 J	3.30 J
Sodium	mg/Kg	167	345.00 J	664.00 J	-
Thallium	mg/Kg	ND	0.72 J	0.84 J	-
Vanadium	mg/Kg	150	14.1	30.20 J	10.10 J
Zinc	mg/Kg	69.25	50.70	1060.00 J	28.10 J
Total Cyanide	mg/Kg	ND	-	3.01 J	0.84 J
TCLP METALS					
Arsenic	mg/L	5			
Barium	mg/L	100			
Cadmium	mg/L	1			
Lead	mg/L	5			
Silver	mg/L	5			

Notes:

1. See Tables 1.2 and 1.3 regarding how recommended cleanup objectives were derived.

Highlighted values exceed Recommended Soil Cleanup Ol

- = compound not detected mg/L = milligrams per

J = Estimated value N = tentatively identi

MDL = Method detection limit R = Data Rejected

mg/kg = milligrams per kilogram ND = not detected in

Table B.1: Test Pit Soil Sample Results

		SAMPLE ID: RECOMMENDED	TP4001	TP4301	TP4601
		DEPTH: SOIL CLEAN-UP	4'	6'	2'
		LAB ID: OBJECTIVE	3079705	3082302	3082303
		SOURCE: (see Note 1)	NYTEST	NYTEST	NYTEST
		SDG:	SHD3	SHD3	SHD3
		MATRIX:	SOIL	SOIL	SOIL
		SAMPLED:	3/17/97	3/18/97	3/19/97
		VALIDATED:	7/25/97	7/25/97	7/25/97
COMPOUND	UNITS:				
VOLATILES					
Acetone	mg/Kg	0.20	0.019	0.014	0.016
Benzene	mg/Kg	0.06	-	-	-
2-Butanone	mg/Kg	0.30	-	-	0.004 J
Chlorobenzene	mg/Kg	1.70	-	-	-
1,2-Dichloroethene (total)	mg/Kg	0.30	0.130	-	-
Ethylbenzene	mg/Kg	5.50	0.006 J	-	-
4-Methyl-2-Pentanone	mg/Kg	1.00	-	-	-
Methylene Chloride	mg/Kg	0.10	-	-	-
Tetrachloroethene	mg/Kg	1.40	-	-	-
Toluene	mg/Kg	1.50	0.006 J	-	-
Trichloroethene	mg/Kg	0.70	0.028	-	-
Vinyl Chloride	mg/Kg	0.20	0.041 J	-	-
Xylene (total)	mg/Kg	1.20	0.003 J	-	-
Total VOCs	mg/Kg	10.00	0.233	0.014	0.020
SEMIVOLATILES					
Acenaphthene	mg/Kg	50.00	-	-	-
Acenaphthylene	mg/Kg	41.00	-	-	-
Anthracene	mg/Kg	50.00	-	-	-
Benzo(a)anthracene	mg/Kg	0.224/MDL	-	-	-
Benzo(a)pyrene	mg/Kg	0.061/MDL	-	-	-
Benzo(b)fluoranthene	mg/Kg	1.10	-	-	-
Benzo(g,h,i)perylene	mg/Kg	50.00	-	-	-
Benzo(k)fluoranthene	mg/Kg	1.10	-	-	-
Butylbenzylphthalate	mg/Kg	50.00	0.08 JN	-	-
Carbazole	mg/Kg	-	-	-	-
4-Chloroaniline	mg/Kg	0.220/MDL	R	R	R
Chrysene	mg/Kg	0.40	0.12 J	-	-
Di-n-butylphthalate	mg/Kg	8.10	0.18 J	-	-
Di-n-octylphthalate	mg/Kg	50.00	-	-	-
Dibenzofuran	mg/Kg	6.20	-	-	-
1,4-Dichlorobenzene	mg/Kg	-	-	-	-
Diethylphthalate	mg/Kg	7.10	-	-	-
Dimethylphthalate	mg/Kg	2.00	-	-	-
2,6-Dinitrotoluene	mg/Kg	1.00	-	-	-
Fluoranthene	mg/Kg	50.00	0.15 J	-	-
Fluorene	mg/Kg	50.00	-	-	-
Hexachlorocyclopentadiene	mg/Kg	-	-	-	-
Indeno(1,2,3-cd)pyrene	mg/Kg	3.20	-	-	-
2-Methylnaphthalene	mg/Kg	36.40	-	-	-
4-Methylphenol	mg/Kg	0.90	-	-	-
N-Nitrosodiphenylamine	mg/Kg	-	1.40	-	-
Naphthalene	mg/Kg	13.00	-	-	-

Table B.1: Test Pit Soil Sample Results

		SAMPLE ID: RECOMMENDED	TP4001	TP4301	TP4601
		DEPTH: SOIL CLEAN-UP	4'	6'	2'
		LAB ID: OBJECTIVE	3079705	3082302	3082303
		SOURCE: (see Note 1)	NYTEST	NYTEST	NYTEST
		SDG:	SHD3	SHD3	SHD3
		MATRIX:	SOIL	SOIL	SOIL
		SAMPLED:	3/17/97	3/18/97	3/19/97
		VALIDATED:	7/25/97	7/25/97	7/25/97
COMPOUND	UNITS:				
Pentachlorophenol	mg/Kg	1.0/MDL	-	-	-
Phenanthrene	mg/Kg	50.00	0.54	-	-
Phenol	mg/Kg	0.03/MDL	-	-	-
Pyrene	mg/Kg	50.00	0.16 J	-	-
1,2,4-Trichlorobenzene	mg/Kg	-	-	-	-
bis(2-Ethylhexyl)phthalate	mg/Kg	50.00	1.30	-	-
Total SVOCs	mg/Kg	500.00	3.93	0.00	0.00
PESTICIDES/PCBs					
alpha-BHC	mg/Kg	0.11	-	-	-
alpha-Chlordane	mg/Kg	0.54	-	-	-
beta-BHC	mg/Kg	0.20	-	-	-
delta-BHC	mg/Kg	0.30	-	-	-
gamma-BHC (Lindane)	mg/Kg	0.06	-	-	-
gamma-Chlordane	mg/Kg	0.54	-	-	-
Aldrin	mg/Kg	0.041	-	-	-
4,4'-DDD	mg/Kg	2.90	-	-	-
4,4'-DDE	mg/Kg	2.10	-	-	-
4,4'-DDT	mg/Kg	2.10	0.01 J	-	-
Dieldrin	mg/Kg	0.044	-	-	-
Endosulfan I	mg/Kg	0.90	-	-	-
Endosulfan II	mg/Kg	0.90	-	-	-
Endosulfan sulfate	mg/Kg	1.00	-	-	-
Endrin	mg/Kg	0.10	-	-	-
Endrin aldehyde	mg/Kg	-	-	-	-
Endrin ketone	mg/Kg	N/A	-	-	-
Heptachlor	mg/Kg	0.10	0.001 J	-	-
Heptachlor epoxide	mg/Kg	0.02	-	-	-
Methoxychlor	mg/Kg	N/A	-	-	-
Toxaphene	mg/Kg	-	-	-	-
Total Pesticides	mg/kg	10.00	0.01	0.00	0.00
Aroclor-1016	mg/Kg	1, 10	-	-	-
Aroclor-1221	mg/Kg	1, 10	-	-	-
Aroclor-1232	mg/Kg	1, 10	-	-	-
Aroclor-1242	mg/Kg	1, 10	-	-	-
Aroclor-1248	mg/Kg	1, 10	-	-	-
Aroclor-1254	mg/Kg	1, 10	-	-	-
Aroclor-1260	mg/Kg	1, 10	-	-	-
TCLP VOLATILES					
NONE	mg/L				
TCLP SEMIVOLATILES					
NONE	mg/L				
TCLP PESTICIDES					
NONE	mg/L				

Table B.1: Test Pit Soil Sample Results

SAMPLE ID: RECOMMENDED		TP4001	TP4301	TP4601
DEPTH: SOIL CLEAN-UP		4'	6'	2'
LAB ID: OBJECTIVE		3079705	3082302	3082303
SOURCE: (see Note 1)		NYTEST	NYTEST	NYTEST
SDG:		SHD3	SHD3	SHD3
MATRIX:		SOIL	SOIL	SOIL
SAMPLED:		3/17/97	3/18/97	3/19/97
VALIDATED:		7/25/97	7/25/97	7/25/97
COMPOUND	UNITS:			
TCLP HERBICIDES				
NONE	mg/L			
INORGANICS				
Aluminum	mg/Kg	16200	10500	14500
Antimony	mg/Kg	1.6	2.60 J	2.00 J
Arsenic	mg/Kg	7.9	8.20	6.00
Barium	mg/Kg	300	109.00	117.00
Beryllium	mg/Kg	0.6	0.32 J	0.45 J
Cadmium	mg/Kg	1	0.39 J	-
Calcium	mg/Kg	1135	1250	924
Chromium	mg/Kg	21.85	15.20 J	27.30 J
Cobalt	mg/Kg	30	9.60 J	12.60 J
Copper	mg/Kg	25	24.20 J	11.80 J
Iron	mg/Kg	33550	27900	26800
Lead	mg/Kg	14.3	52.10	8.40
Magnesium	mg/Kg	6085	3270	3910
Manganese	mg/Kg	918	477.00	1330 J
Mercury	mg/Kg	0.1	-	-
Nickel	mg/Kg	34.5	36.40	24.60
Potassium	mg/Kg	1270	1260.00	1320.00
Selenium	mg/Kg	2	-	-
Silver	mg/Kg	N/A	-	-
Sodium	mg/Kg	167	684.00 J	457.00 J
Thallium	mg/Kg	ND	-	2.10 J
Vanadium	mg/Kg	150	16.00	21.10
Zinc	mg/Kg	69.25	1270.00	70.50
Total Cyanide	mg/Kg	ND	1.34	-
TCLP METALS				
Arsenic	mg/L	5		
Barium	mg/L	100		
Cadmium	mg/L	1		
Lead	mg/L	5		
Silver	mg/L	5		

Prepared/Date: RTB 10/20 05
Checked/Date: MJS 10/20 05

Notes:

1. See Tables 1.2 and 1.3 regarding how recommended cleanup objectives were derived.

Highlighted values exceed Recommended Soil Cleanup Ol

- = compound not detected mg/L = milligrams per

J = Estimated value N = tentatively identi

MDL = Method detection limit R = Data Rejected

mg/kg = milligrams per kilogram ND = not detected in

Table B.3: Drum Sample Results

	SAMPLE ID:	DS2001	DS2002	TP21D1	TP38D1
	LAB ID:	3072004	3072005	3129001	3083505
	SOURCE:	NYTEST	NYTEST	NYTEST	NYTEST
	SDG:	SHD2	SHD2	SHD4	SHD4
	MATRIX:	SOIL	SOIL	SOIL	SOIL
	SAMPLED:	3/05/97	3/05/97	3/20/97	3/20/97
	VALIDATED:	7/25/97	7/25/97	7/25/97	7/25/97
COMPOUND	UNITS:				
VOLATILES					
Acetone	mg/Kg	-	1.1 J	-	-
Benzene	mg/Kg	-	0.01 J	-	-
2-Butanone	mg/Kg	-	0.15 J	-	-
Carbon Disulfide	mg/Kg	-	0.002 J	-	-
Ethylbenzene	mg/Kg	-	0.06 J	0.36 J	1.9
4-Methyl-2-Pentanone	mg/Kg	-	-	-	5.8
Methylene Chloride	mg/Kg	-	0.007 J	8.2	0.65 J
Styrene	mg/Kg	-	-	0.29 J	-
Tetrachloroethene	mg/Kg	-	-	0.24 J	-
Toluene	mg/Kg	-	0.041 J	1.2	-
Trichloroethene	mg/Kg	-	-	5.8	-
Xylene (total)	mg/Kg	-	0.013 J	1.4	24
SEMIVOLATILES					
Benzo(a)pyrene	mg/Kg	0.1 J	-	-	-
Benzo(b)fluoranthene	mg/Kg	-	-	-	-
Benzo(g,h,i)perylene	mg/Kg	-	-	-	-
Benzo(k)fluoranthene	mg/Kg	-	-	-	-
Benzoic Acid	mg/Kg	-	-	-	21 J
Benzyl Alcohol	mg/Kg	-	-	-	-
Butylbenzylphthalate	mg/Kg	-	7.6	-	-
4-Chloroaniline	mg/Kg	-	-	R	-
Di-n-butylphthalate	mg/Kg	-	-	-	-
Di-n-octylphthalate	mg/Kg	0.18 J	-	-	-
Dibenz(a,h)anthracene	mg/Kg	-	-	-	-
2,4-Dimethylphenol	mg/Kg	-	-	-	3.3 J
Fluoranthene	mg/Kg	0.42 J	-	-	-
Indeno(1,2,3-cd)pyrene	mg/Kg	-	-	-	-
2-Methylnaphthalene	mg/Kg	0.25 J	1.9 J	-	-
4-Methylphenol	mg/Kg	-	0.31 J	-	-
Naphthalene	mg/Kg	-	0.5 J	-	-
4-Nitroaniline	mg/Kg	-	-	R	-
Phenanthrene	mg/Kg	3.5	-	100	-
Pyrene	mg/Kg	0.58 J	-	14 J	-
2,4,5-Trichlorophenol	mg/Kg	-	-	350	-
bis(2-Ethylhexyl)phthalate	mg/Kg	-	-	200	60000
PESTICIDES/PCBs					
alpha-BHC	mg/Kg	-	-	-	-
alpha-Chlordane	mg/Kg	-	0.011 J	-	-
beta-BHC	mg/Kg	-	-	-	-
delta-BHC	mg/Kg	-	-	-	-
gamma-BHC (Lindane)	mg/Kg	-	-	-	-
gamma-Chlordane	mg/Kg	-	0.007 JN	-	-
Aldrin	mg/Kg	-	-	-	-

Table B.3: Drum Sample Results

	SAMPLE ID:	DS2001	DS2002	TP21D1	TP38D1
	LAB ID:	3072004	3072005	3129001	3083505
	SOURCE:	NYTEST	NYTEST	NYTEST	NYTEST
	SDG:	SHD2	SHD2	SHD4	SHD4
	MATRIX:	SOIL	SOIL	SOIL	SOIL
	SAMPLED:	3/05/97	3/05/97	3/20/97	3/20/97
	VALIDATED:	7/25/97	7/25/97	7/25/97	7/25/97
COMPOUND	UNITS:				
4,4'-DDD	mg/Kg	-	-	-	-
4,4'-DDE	mg/Kg	-	0.019 J	-	-
4,4'-DDT	mg/Kg	0.0079 JN	-	-	-
Dieldrin	mg/Kg	-	-	-	-
Endosulfan I	mg/Kg	-	0.0026 JN	-	-
Endosulfan II	mg/Kg	0.0062 J	-	-	-
Endosulfan sulfate	mg/Kg	-	-	-	-
Endrin	mg/Kg	-	0.0072 JN	-	-
Endrin aldehyde	mg/Kg	-	0.063 JN	-	-
Endrin ketone	mg/Kg	-	-	-	-
Heptachlor	mg/Kg	-	-	-	-
Heptachlor epoxide	mg/Kg	-	0.0013 JN	-	-
Methoxychlor	mg/Kg	-	-	-	-
Toxaphene	mg/Kg	-	-	-	-
Aroclor-1016	mg/Kg	-	-	-	-
Aroclor-1221	mg/Kg	-	-	-	-
Aroclor-1232	mg/Kg	-	-	-	-
Aroclor-1242	mg/Kg	-	-	-	-
Aroclor-1248	mg/Kg	-	-	-	-
Aroclor-1254	mg/Kg	0.047 J	0.35 J	-	-
Aroclor-1260	mg/Kg	-	-	-	-
INORGANICS					
Aluminum	mg/Kg	2650	22600	1960	549
Antimony	mg/Kg	11.1 J	36.4 J	11.1 J	1.3 J
Arsenic	mg/Kg	26.7	47.8	0.76 J	-
Barium	mg/Kg	40.4	46.3	343	6.6 J
Beryllium	mg/Kg	-	-	-	0.05 J
Cadmium	mg/Kg	-	-	1.2	0.06 J
Calcium	mg/Kg	5240	688	3660	497 J
Chromium	mg/Kg	75.5	5560	6.2	5.9
Cobalt	mg/Kg	22.8	1210	1.1 J	1.2 J
Copper	mg/Kg	626	2260	84.4	19.6
Iron	mg/Kg	193000 J	622000 J	9510 J	14000 J
Lead	mg/Kg	1580	1340	116 J	11.2 J
Magnesium	mg/Kg	1000	201 J	304 J	350 J
Manganese	mg/Kg	2910	4170	76.8	54.5
Nickel	mg/Kg	109	908	5.3	4.2 J
Potassium	mg/Kg	307 J	734	248 J	509 J
Selenium	mg/Kg	-	-	0.95	0.61
Silver	mg/Kg	1.4	17.8	0.51 J	-
Sodium	mg/Kg	186 J	898	440 J	445 J
Thallium	mg/Kg	-	-	-	-
Vanadium	mg/Kg	11	430	1.9 J	0.75 J
Zinc	mg/Kg	303	448	826 J	987 J

Table B.3: Drum Sample Results

	SAMPLE ID:	DS2001	DS2002	TP21D1	TP38D1
	LAB ID:	3072004	3072005	3129001	3083505
	SOURCE:	NYTEST	NYTEST	NYTEST	NYTEST
	SDG:	SHD2	SHD2	SHD4	SHD4
	MATRIX:	SOIL	SOIL	SOIL	SOIL
	SAMPLED:	3/05/97	3/05/97	3/20/97	3/20/97
	VALIDATED:	7/25/97	7/25/97	7/25/97	7/25/97
COMPOUND	UNITS:				
Total Cyanide	mg/Kg	1.55	-	1.58	1.88
TCLP VOLATILES					
Benzene	mg/L			R	
2-Butanone	mg/L			0.03 J	
Carbon Tetrachloride	mg/L			R	
Chlorobenzene	mg/L			R	
Chloroform	mg/L			R	
1,2-Dichloroethane	mg/L			R	
1,1-Dichloroethene	mg/L			R	
Tetrachloroethene	mg/L			R	
Trichloroethene	mg/L			0.01 J	
Vinyl Chloride	mg/L			R	
TCLP SEMIVOLATILES					
1,4-Dichlorobenzene	mg/L			R	
2,4-Dinitrotoluene	mg/L			R	
Hexachlorobenzene	mg/L			R	
Hexachlorobutadiene	mg/L			R	
Hexachloroethane	mg/L			R	
2-Methylphenol	mg/L			R	
3+4-Methylphenol	mg/L			0.06 J	
Nitrobenzene	mg/L			R	
Pentachlorophenol	mg/L			R	
Pyridine	mg/L			R	
2,4,5-Trichlorophenol	mg/L			0.23 J	
2,4,6-Trichlorophenol	mg/L			0.25 J	
TCLP METALS					
Arsenic	mg/L			0.0721	
Cadmium	mg/L			-	
Lead	mg/L			-	
Mercury	mg/L			0.00013 J	
Selenium	mg/L			-	
Silver	mg/L			0.0182 J	

Notes:

- = compound not detected

J = Estimated value

mg/kg = milligrams per kilogram

mg/L = milligrams per liter

N = tentatively identified compound

R = Data rejected

Table B.3: Drum Sample Results

COMPOUND	SAMPLE ID:	TP4101	TP41D1	DUP of TP41D1	
				TP41DR1	TP45D1
	LAB ID:	3082301	3083501	3129003	3083507
	SOURCE:	NYTEST	NYTEST	NYTEST	NYTEST
	SDG:	SHD3	SHD4	SHD4	SHD4
	MATRIX:	SOIL	SOIL	SOIL	SOIL
	SAMPLED:	3/18/97	3/20/97	3/20/97	3/20/97
	VALIDATED:	7/25/97	7/25/97	7/25/97	7/25/97
	UNITS:				
VOLATILES					
Acetone	mg/Kg	0.011 J	-	-	-
Benzene	mg/Kg	-	-	-	-
2-Butanone	mg/Kg	-	-	0.006 J	-
Carbon Disulfide	mg/Kg	-	-	-	-
Ethylbenzene	mg/Kg	-	-	-	-
4-Methyl-2-Pentanone	mg/Kg	-	-	-	-
Methylene Chloride	mg/Kg	-	-	0.032 J	0.34 J
Styrene	mg/Kg	-	-	-	-
Tetrachloroethene	mg/Kg	-	-	-	-
Toluene	mg/Kg	-	-	0.003 J	-
Trichloroethene	mg/Kg	0.002 J	-	-	-
Xylene (total)	mg/Kg	-	-	-	-
SEMIVOLATILES					
Benzo(a)pyrene	mg/Kg	-	-	-	R
Benzo(b)fluoranthene	mg/Kg	-	-	-	R
Benzo(g,h,i)perylene	mg/Kg	-	-	-	R
Benzo(k)fluoranthene	mg/Kg	-	-	-	R
Benzoic Acid	mg/Kg	-	-	-	R
Benzyl Alcohol	mg/Kg	-	-	-	R
Butylbenzylphthalate	mg/Kg	-	-	-	-
4-Chloroaniline	mg/Kg	R	-	R	-
Di-n-butylphthalate	mg/Kg	-	-	-	6.2 J
Di-n-octylphthalate	mg/Kg	-	-	-	R
Dibenz(a,h)anthracene	mg/Kg	-	-	-	R
2,4-Dimethylphenol	mg/Kg	-	-	-	-
Fluoranthene	mg/Kg	-	-	-	-
Indeno(1,2,3-cd)pyrene	mg/Kg	-	-	-	R
2-Methylnaphthalene	mg/Kg	-	-	-	-
4-Methylphenol	mg/Kg	-	-	-	-
Naphthalene	mg/Kg	-	-	-	-
4-Nitroaniline	mg/Kg	-	-	R	-
Phenanthrene	mg/Kg	-	13 J	17 J	-
Pyrene	mg/Kg	-	-	-	-
2,4,5-Trichlorophenol	mg/Kg	-	46 J	47 J	-
bis(2-Ethylhexyl)phthalate	mg/Kg	-	13 J	20 J	24 J
PESTICIDES/PCBs					
alpha-BHC	mg/Kg	-	-	-	R
alpha-Chlordane	mg/Kg	-	-	-	R
beta-BHC	mg/Kg	-	-	-	R
delta-BHC	mg/Kg	-	-	-	R
gamma-BHC (Lindane)	mg/Kg	-	-	-	R
gamma-Chlordane	mg/Kg	-	-	-	R
Aldrin	mg/Kg	-	-	-	R

Table B.3: Drum Sample Results

	DUP of TP41D1				
	SAMPLE ID:	TP4101	TP41D1	TP41DR1	TP45D1
	LAB ID:	3082301	3083501	3129003	3083507
	SOURCE:	NYTEST	NYTEST	NYTEST	NYTEST
	SDG:	SHD3	SHD4	SHD4	SHD4
	MATRIX:	SOIL	SOIL	SOIL	SOIL
	SAMPLED:	3/18/97	3/20/97	3/20/97	3/20/97
	VALIDATED:	7/25/97	7/25/97	7/25/97	7/25/97
COMPOUND	UNITS:				
4,4'-DDD	mg/Kg	-	-	-	R
4,4'-DDE	mg/Kg	-	-	-	R
4,4'-DDT	mg/Kg	-	-	-	R
Dieldrin	mg/Kg	-	-	-	R
Endosulfan I	mg/Kg	-	-	-	R
Endosulfan II	mg/Kg	-	-	-	R
Endosulfan sulfate	mg/Kg	-	-	-	R
Endrin	mg/Kg	-	-	-	R
Endrin aldehyde	mg/Kg	-	-	-	R
Endrin ketone	mg/Kg	-	-	-	R
Heptachlor	mg/Kg	-	-	-	R
Heptachlor epoxide	mg/Kg	-	-	-	R
Methoxychlor	mg/Kg	-	-	-	R
Toxaphene	mg/Kg	-	-	-	R
Aroclor-1016	mg/Kg	-	-	-	R
Aroclor-1221	mg/Kg	-	-	-	R
Aroclor-1232	mg/Kg	-	-	-	R
Aroclor-1242	mg/Kg	-	-	-	R
Aroclor-1248	mg/Kg	-	-	-	R
Aroclor-1254	mg/Kg	-	-	-	R
Aroclor-1260	mg/Kg	-	-	-	R
INORGANICS					
Aluminum	mg/Kg	21800	-	-	43.6
Antimony	mg/Kg	2.7 J	18.6 J	23.9 J	-
Arsenic	mg/Kg	15.5	23.3 J	26.3 J	-
Barium	mg/Kg	114	10.2 J	11.1 J	47.4
Beryllium	mg/Kg	0.87	-	-	-
Cadmium	mg/Kg	-	26	12.2	0.52
Calcium	mg/Kg	1140	368 J	427 J	30.4 J
Chromium	mg/Kg	28 J	212	205	0.29 J
Cobalt	mg/Kg	16.9 J	15.9	16.1	-
Copper	mg/Kg	24 J	6090	5120	7.3
Iron	mg/Kg	326000	310000 J	302000 J	161 J
Lead	mg/Kg	15.2	292 J	321 J	5.8 J
Magnesium	mg/Kg	7830	1120	1290	-
Manganese	mg/Kg	310	2270	2300	1.6
Nickel	mg/Kg	51.4	240	160	0.27 J
Potassium	mg/Kg	2000	153 J	134 J	-
Selenium	mg/Kg	-	-	-	-
Silver	mg/Kg	-	2.3	1.9	-
Sodium	mg/Kg	522 J	631	493 J	-
Thallium	mg/Kg	-	-	-	0.75 J
Vanadium	mg/Kg	26	40.3	43.5	-
Zinc	mg/Kg	182	1680 J	1410 J	206 J

Table B.3: Drum Sample Results

COMPOUND	UNITS:	DUP of TP41D1			
		SAMPLE ID:	TP41D1	TP41DR1	TP45D1
Total Cyanide	mg/Kg	LAB ID: 3082301	3083501	3129003	3083507
TCLP VOLATILES		SOURCE: NYTEST	NYTEST	NYTEST	NYTEST
Benzene	mg/L	SDG: SHD3	SHD4	SHD4	SHD4
2-Butanone	mg/L	MATRIX: SOIL	SOIL	SOIL	SOIL
Carbon Tetrachloride	mg/L	SAMPLED: 3/18/97	3/20/97	3/20/97	3/20/97
Chlorobenzene	mg/L	VALIDATED: 7/25/97	7/25/97	7/25/97	7/25/97
Chloroform	mg/L				
1,2-Dichloroethane	mg/L				
1,1-Dichloroethene	mg/L				
Tetrachloroethene	mg/L				
Trichloroethene	mg/L				
Vinyl Chloride	mg/L				
TCLP SEMIVOLATILES					
1,4-Dichlorobenzene	mg/L				
2,4-Dinitrotoluene	mg/L				
Hexachlorobenzene	mg/L				
Hexachlorobutadiene	mg/L				
Hexachloroethane	mg/L				
2-Methylphenol	mg/L				
3+4-Methylphenol	mg/L				
Nitrobenzene	mg/L				
Pentachlorophenol	mg/L				
Pyridine	mg/L				
2,4,5-Trichlorophenol	mg/L				
2,4,6-Trichlorophenol	mg/L				
TCLP METALS					
Arsenic	mg/L		0.4	0.408	
Cadmium	mg/L		0.0521 J	0.0608 J	
Lead	mg/L		0.117	0.128	
Mercury	mg/L		0.0002 J	0.00007 J	
Selenium	mg/L		0.374	0.336	
Silver	mg/L		0.105 J	0.117 J	

Notes:

- = compound not detected

J = Estimated value

mg/kg = milligrams per kilogram

mg/L = milligrams per liter

N = tentatively identified compound

R = Data rejected

Table B.3: Drum Sample Results

	SAMPLE ID:	TP45D2	TP45D2 ACID
	LAB ID:	3083508	3083508
	SOURCE:	NYTEST	NYTEST
	SDG:	SHD4	SHD4
	MATRIX:	SOIL	SOIL
	SAMPLED:	3/20/97	3/20/97
	VALIDATED:	7/25/97	7/25/97
COMPOUND	UNITS:		
VOLATILES			
Acetone	mg/Kg	-	
Benzene	mg/Kg	-	
2-Butanone	mg/Kg	-	
Carbon Disulfide	mg/Kg	-	
Ethylbenzene	mg/Kg	0.15 J	
4-Methyl-2-Pentanone	mg/Kg	-	
Methylene Chloride	mg/Kg	0.33 J	
Styrene	mg/Kg	-	
Tetrachloroethene	mg/Kg	-	
Toluene	mg/Kg	0.82 J	
Trichloroethene	mg/Kg	-	
Xylene (total)	mg/Kg	2.8	
SEMIVOLATILES			
Benzo(a)pyrene	mg/Kg	-	
Benzo(b)fluoranthene	mg/Kg	-	
Benzo(g,h,i)perylene	mg/Kg	-	
Benzo(k)fluoranthene	mg/Kg	-	
Benzoic Acid	mg/Kg	-	
Benzyl Alcohol	mg/Kg	-	
Butylbenzylphthalate	mg/Kg	-	
4-Chloroaniline	mg/Kg	R	
Di-n-butylphthalate	mg/Kg	-	
Di-n-octylphthalate	mg/Kg	11 J	
Dibenz(a,h)anthracene	mg/Kg	-	
2,4-Dimethylphenol	mg/Kg	-	
Fluoranthene	mg/Kg	-	
Indeno(1,2,3-cd)pyrene	mg/Kg	-	
2-Methylnaphthalene	mg/Kg	-	
4-Methylphenol	mg/Kg	-	
Naphthalene	mg/Kg	35 J	
4-Nitroaniline	mg/Kg	R	
Phenanthrene	mg/Kg	15 J	
Pyrene	mg/Kg	-	
2,4,5-Trichlorophenol	mg/Kg	-	
bis(2-Ethylhexyl)phthalate	mg/Kg	-	
PESTICIDES/PCBs			
alpha-BHC	mg/Kg	-	
alpha-Chlordane	mg/Kg	-	
beta-BHC	mg/Kg	-	
delta-BHC	mg/Kg	-	
gamma-BHC (Lindane)	mg/Kg	-	
gamma-Chlordane	mg/Kg	-	
Aldrin	mg/Kg	-	

Table B.3: Drum Sample Results

	SAMPLE ID:	TP45D2	TP45D2 ACID
	LAB ID:	3083508	3083508
	SOURCE:	NYTEST	NYTEST
	SDG:	SHD4	SHD4
	MATRIX:	SOIL	SOIL
	SAMPLED:	3/20/97	3/20/97
	VALIDATED:	7/25/97	7/25/97
COMPOUND	UNITS:		
4,4'-DDD	mg/Kg	-	
4,4'-DDE	mg/Kg	-	
4,4'-DDT	mg/Kg	-	
Dieldrin	mg/Kg	-	
Endosulfan I	mg/Kg	-	
Endosulfan II	mg/Kg	-	
Endosulfan sulfate	mg/Kg	-	
Endrin	mg/Kg	-	
Endrin aldehyde	mg/Kg	-	
Endrin ketone	mg/Kg	-	
Heptachlor	mg/Kg	-	
Heptachlor epoxide	mg/Kg	-	
Methoxychlor	mg/Kg	-	
Toxaphene	mg/Kg	-	
Aroclor-1016	mg/Kg	-	-
Aroclor-1221	mg/Kg	-	-
Aroclor-1232	mg/Kg	-	-
Aroclor-1242	mg/Kg	-	-
Aroclor-1248	mg/Kg	-	-
Aroclor-1254	mg/Kg	-	7100
Aroclor-1260	mg/Kg	-	-
INORGANICS			
Aluminum	mg/Kg	2300	
Antimony	mg/Kg	1 J	
Arsenic	mg/Kg	0.89 J	
Barium	mg/Kg	74.3	
Beryllium	mg/Kg	-	
Cadmium	mg/Kg	58	
Calcium	mg/Kg	420 J	
Chromium	mg/Kg	11.5	
Cobalt	mg/Kg	0.53 J	
Copper	mg/Kg	249	
Iron	mg/Kg	16300 J	
Lead	mg/Kg	86.7 J	
Magnesium	mg/Kg	161 J	
Manganese	mg/Kg	317	
Nickel	mg/Kg	11.9	
Potassium	mg/Kg	249 J	
Selenium	mg/Kg	0.45 J	
Silver	mg/Kg	0.52 J	
Sodium	mg/Kg	733	
Thallium	mg/Kg	-	
Vanadium	mg/Kg	2.2 J	
Zinc	mg/Kg	181 J	

Table B.3: Drum Sample Results

	SAMPLE ID:	TP45D2	TP45D2 ACID
	LAB ID:	3083508	3083508
	SOURCE:	NYTEST	NYTEST
	SDG:	SHD4	SHD4
	MATRIX:	SOIL	SOIL
	SAMPLED:	3/20/97	3/20/97
	VALIDATED:	7/25/97	7/25/97
COMPOUND	UNITS:		
Total Cyanide	mg/Kg	-	
TCLP VOLATILES			
Benzene	mg/L		
2-Butanone	mg/L		
Carbon Tetrachloride	mg/L		
Chlorobenzene	mg/L		
Chloroform	mg/L		
1,2-Dichloroethane	mg/L		
1,1-Dichloroethene	mg/L		
Tetrachloroethene	mg/L		
Trichloroethene	mg/L		
Vinyl Chloride	mg/L		
TCLP SEMIVOLATILES			
1,4-Dichlorobenzene	mg/L		
2,4-Dinitrotoluene	mg/L		
Hexachlorobenzene	mg/L		
Hexachlorobutadiene	mg/L		
Hexachloroethane	mg/L		
2-Methylphenol	mg/L		
3+4-Methylphenol	mg/L		
Nitrobenzene	mg/L		
Pentachlorophenol	mg/L		
Pyridine	mg/L		
2,4,5-Trichlorophenol	mg/L		
2,4,6-Trichlorophenol	mg/L		
TCLP METALS			
Arsenic	mg/L	-	
Cadmium	mg/L	2.14 J	
Lead	mg/L	0.264	
Mercury	mg/L	-	
Selenium	mg/L	-	
Silver	mg/L	0.0095 J	

Notes:

- = compound not detected

J = Estimated value

mg/kg = milligrams per kilogram

mg/L = milligrams per liter

N = tentatively identified compound

R = Data rejected

Prepare/Date: RTB 10/20/05

Checked/Date: MJS 10/20/05

Table B.6: Soil Boring Sample Results

	SAMPLE ID:	RECOMMENDED	MW1B	MW1E	MW2B
	DEPTH:	SOIL CLEAN-UP	2-4'	6-10'	2-4'
	LAB ID:	OBJECTIVE	3090501	3090502	3090503
	SOURCE:	(see Note 1)	NYTEST	NYTEST	NYTEST
	SDG:		SHD5	SHD5	SHD5
	MATRIX:		SOIL	SOIL	SOIL
	SAMPLED:		3/26/97	3/26/97	3/27/97
	VALIDATED:		7/25/97	7/25/97	7/25/97
COMPOUND	UNITS:				
VOLATILES					
1,2-Dichloroethene (total)	mg/Kg	0.3	-	-	-
Methylene Chloride	mg/Kg	0.1	0.004 J	0.004 J	0.004 J
Trichloroethene	mg/Kg	0.7	-	-	-
Total VOCs*	mg/Kg	10	0.004	0.004	0.004
SEMIVOLATILES					
bis(2-Ethylhexyl)phthalate	mg/Kg	50	0.23 J	0.077 J	-
Total SVOCs*	mg/Kg	500	0.23	0.077	-
PESTICIDES/PCBs					
Methoxychlor	mg/Kg	10	-	0.014 J	-
Total Pesticides*	mg/Kg	10			
INORGANICS					
Aluminum	mg/Kg	16200	17400	15000	15000
Antimony	mg/Kg	1.6	1.7 J	1.5 J	1.7 J
Arsenic	mg/Kg	7.9	8.9	6.9	8
Barium	mg/Kg	300	46.6 J	133 J	59.6 J
Beryllium	mg/Kg	0.6	0.65	0.55	0.56
Calcium	mg/Kg	1135	1000 J	1270 J	782 J
Chromium	mg/Kg	21.85	22.3 J	21.4 J	20.5 J
Cobalt	mg/Kg	30	15.5 J	16 J	13.6 J
Copper	mg/Kg	25	20	18.2	19
Iron	mg/Kg	33550	33900 J	33200 J	29400 J
Lead	mg/Kg	14.3	22.9	5.7	9.2
Magnesium	mg/Kg	6085	6020 J	6150 J	5490 J
Manganese	mg/Kg	918	836 J	1000 J	547 J
Mercury	mg/Kg	0.1	-	-	-
Nickel	mg/Kg	34.5	35.5 J	33.5 J	31.4 J
Potassium	mg/Kg	1270	1290	1250	1140
Sodium	mg/Kg	167	167 J	-	121 J
Thallium	mg/Kg	ND	-	-	0.97 J
Vanadium	mg/Kg	150	21.3 J	19.4 J	19.4 J
Zinc	mg/Kg	69.25	73.5 J	65 J	68.1 J
Total Cyanide	mg/Kg	***	-	-	-

Notes:

1. See Tables 1.2 and 1.3 for information on how recommended cleanup objectives were derived.

Highlighted values exceed Recommended Soil Cleanup Objective

- = compound not detected

J = Estimated value

mg/kg = milligrams per kilogram

ND = not detected in background samples

R = Data Rejected

Table B.6: Soil Boring Sample Results

COMPOUND	SAMPLE ID:	RECOMMENDED	MW2G	MW2N	MW3E
	DEPTH:	SOIL CLEAN-UP	10-14'	20-28'	2-8'
	LAB ID:	OBJECTIVE	3090504	3091101	3096801
	SOURCE:	(see Note 1)	NYTEST	NYTEST	NYTEST
	SDG:		SHD5	SHD5	SHD6
	MATRIX:		SOIL	SOIL	SOIL
	SAMPLED:		3/27/97	3/28/97	4/03/97
	VALIDATED:		7/25/97	7/25/97	7/25/97
	UNITS:				
VOLATILES					
1,2-Dichloroethene (total)	mg/Kg	0.3	-	-	0.002 J
Methylene Chloride	mg/Kg	0.1	0.004 J	-	-
Trichloroethene	mg/Kg	0.7	-	-	0.028 J
Total VOCs*	mg/Kg	10	0.004	0	0.03
SEMIVOLATILES					
bis(2-Ethylhexyl)phthalate	mg/Kg	50	-	0.079 J	0.1 J
Total SVOCs*	mg/Kg	500	-	0.079	0.1
PESTICIDES/PCBs					
Methoxychlor	mg/Kg	10	-	-	-
Total Pesticides*	mg/Kg	10			
INORGANICS					
Aluminum	mg/Kg	16200	13100	17900	12600 J
Antimony	mg/Kg	1.6	0.98 J	1.8 J	2 J
Arsenic	mg/Kg	7.9	7.9	10.6 J	7.8 J
Barium	mg/Kg	300	99.2 J	163 J	160 J
Beryllium	mg/Kg	0.6	0.55	0.73	0.47 J
Calcium	mg/Kg	1135	50300 J	5510 J	1590 J
Chromium	mg/Kg	21.85	17.6 J	24.1 J	17.2 J
Cobalt	mg/Kg	30	11.3 J	16.8 J	10.8 J
Copper	mg/Kg	25	18.3	23.2	20 J
Iron	mg/Kg	33550	29200 J	40000 J	27200
Lead	mg/Kg	14.3	9.5	16.6	17.3 J
Magnesium	mg/Kg	6085	9070 J	7000 J	4130 J
Manganese	mg/Kg	918	675 J	584 J	616 J
Mercury	mg/Kg	0.1	-	-	-
Nickel	mg/Kg	34.5	26.6 J	37.6 J	25.4 J
Potassium	mg/Kg	1270	1970	2220	1720
Sodium	mg/Kg	167	181 J	146 J	298 J
Thallium	mg/Kg	ND	-	-	-
Vanadium	mg/Kg	150	18.2 J	24 J	18.4 J
Zinc	mg/Kg	69.25	57.7 J	83.9 J	87.2 J
Total Cyanide	mg/Kg	***	-	-	-

Notes:

1. See Tables 1.2 and 1.3 for information on how recommended cleanup objectives were derived.

Highlighted values exceed Recommended Soil Cleanup Objectives

- = compound not detected

J = Estimated value

mg/kg = milligrams per kilogram

ND = not detected in background samples

R = Data Rejected

Table B.6: Soil Boring Sample Results

COMPOUND	DUP of MW3E				
	SAMPLE ID:	RECOMMENDED	MW3D	MW4C	MW4J
VOLATILES	DEPTH:	SOIL CLEAN-UP	2-8'	4-6'	16-20'
	LAB ID:	OBJECTIVE	3096804	3093901	3093902
	SOURCE:	(see Note 1)	NYTEST	NYTEST	NYTEST
	SDG:		SHD6	SHD5	SHD5
	MATRIX:		SOIL	SOIL	SOIL
	SAMPLED:		4/03/97	3/31/97	3/31/97
	VALIDATED:		7/25/97	7/25/97	7/25/97
	UNITS:				
1,2-Dichloroethene (total)	mg/Kg	0.3	0.002 J	-	-
Methylene Chloride	mg/Kg	0.1	-	0.007 J	0.008 J
Trichloroethene	mg/Kg	0.7	0.021 J	-	-
Total VOCs*	mg/Kg	10	0.023	0.007	0.008
SEMIVOLATILES					
bis(2-Ethylhexyl)phthalate	mg/Kg	50	0.058 J	R	R
Total SVOCs*	mg/Kg	500	0.058	0	0
PESTICIDES/PCBs					
Methoxychlor	mg/Kg	10	-	-	-
Total Pesticides*	mg/Kg	10			
INORGANICS					
Aluminum	mg/Kg	16200	4880 J	14400	11800
Antimony	mg/Kg	1.6	1.6 J	2 J	0.55 J
Arsenic	mg/Kg	7.9	1.9 J	9.6 J	6.6 J
Barium	mg/Kg	300	24.9 J	95.8 J	87 J
Beryllium	mg/Kg	0.6	0.38 J	0.57	0.46 J
Calcium	mg/Kg	1135	1540 J	1490 J	22200 J
Chromium	mg/Kg	21.85	11.2 J	19.4 J	15.8 J
Cobalt	mg/Kg	30	4.3 J	13.1 J	10.8 J
Copper	mg/Kg	25	7.9 J	20.2	17.9
Iron	mg/Kg	33550	19500	31100 J	25300 J
Lead	mg/Kg	14.3	4.1 J	10.8	9.4
Magnesium	mg/Kg	6085	2040 J	5140 J	7650 J
Manganese	mg/Kg	918	97.3 J	586 J	504 J
Mercury	mg/Kg	0.1	0.05 J	-	0.06 J
Nickel	mg/Kg	34.5	7.9 J	31.3 J	25.5 J
Potassium	mg/Kg	1270	1130	1470	1550
Sodium	mg/Kg	167	293 J	77.5 J	145 J
Thallium	mg/Kg	ND	-	0.77 J	-
Vanadium	mg/Kg	150	20.2 J	19.5 J	16.1 J
Zinc	mg/Kg	69.25	24.6 J	70 J	57.6 J
Total Cyanide	mg/Kg	***	-	2.23	-

Notes:

1. See Tables 1.2 and 1.3 for information on how recommended cleanup objectives were derived.

Highlighted values exceed Recommended Soil Cleanup Objectives

- = compound not detected

J = Estimated value

mg/kg = milligrams per kilogram

ND = not detected in background samples

R = Data Rejected

Prepared/Date: RTB 10/20/05

Checked/Date: MJS 10/20/05

APPENDIX A

PHOTOGRAPHS

Appendix A contains photographs of the South Hill Dump Site from a site visit on April 28, 2005. This information is offered for consideration when planning the remedial work.



Photo 37 - View of drums in fenced area from below embankment



Photo 38 - View of farm field across South Hill Road



Photo 39 - View of drums in fenced area from South Hill Road



Photo 40 - View of additional drums in fenced area from South Hill Road



Photo 41 - View of flat area NE/E of fenced area



Photo 42 - View of flat area looking E from landfill road



Photo 43



Photo 44



Photo 45



Photo 46



Photo 47



Photo 48



Photo 49



Photo 50



Photo 51



Photo 52



Photo 53



Photo 54



Photo 55



Photo 56



Photo 57



Photo 58



Photo 59



Photo 60



Photo 61



Photo 62



Photo 63



Photo 64



Photo 65



Photo 66



Photo 67



Photo 68



Photo 69



Photo 70



Photo 71



Photo 72



Photo 73



Photo 74



Photo 75



Photo 76



Photo 77



Photo 78



Photo 79



Photo 80



Photo 81



Photo 82



Photo 83



Photo 84



Photo 85



Photo 86



Photo 87



Photo 88



Photo 89



Photo 90




PHOTO LOG: SOUTH HILL
DUMP

DATE: APRIL 28, 2005

○ LOCATION OF PHOTOGRAPHER
→ DIRECTION FACING
15 PICTURE NO., REFER
TO SKETCH AND
TABLE OF CONTENTS
FILE.

SOUTH HILL DUMP
CORTLANDVILLE, CORTLAND COUNTY, NEW YORK
SITE NO. 7-12-009

New York State Department of
Environmental Conservation




FILE: DRAWING: DRAIN FROM SPENCER F. THOMAS, JR. - US BASE MAP
BY: JEB

MONITORING WELLS AND
SAMPLE LOCATIONS

APPENDIX B

SITE SURVEY

Appendix B contains the site survey prepared by Popli Consulting Engineers and Surveyors at the South Hill Dump Site in January 2010. This information is offered for consideration when planning the remedial work.



SURVEY NOTES

1. MAPPING REFERENCED TO THE NORTH AMERICAN DATUM OF 1983 (CORS)
- NEW YORK STATE PLANE COORDINATE SYSTEM, CENTRAL ZONE.
2. ELEVATIONS SHOWN HEREON ARE REFERENCED TO THE NORTH
AMERICAN VERTICAL DATUM OF 1988.
3. MAPPING UNITS ARE SHOWN IN U.S. SURVEY FEET.
4. THE CONTOUR INTERVAL IS 1 FOOT.
5. TEST PIT, 'SW' AND 'SD' LOCATIONS ARE BASED ON MAPPING ENTITLED,
' TOPOGRAPHIC SURVEY SOUTH HILL DUMP SITE ', PREPARED BY
SPENCER F. THEW, P.E., L.S., DATED 7/7/97, & PROVIDED BY MACTEC.
6. THE SITE WAS SNOW COVERED AT THE TIME OF SURVEY.

BOUNDARY REFERENCES

1. DEED, FILED IN LIBER 287 AT PAGE 852.
2. DEED, FILED IN LIBER 1995 AT PAGE 2298.
3. DEED, FILED WITH INSTRUMENT NO. 1031548-001.
4. DEED, FILED WITH INSTRUMENT NO. 1018211-002.
5. MAP ENTITLED, ' LANDS OF CORTLAND COUNTY, SOUTH HILL ROAD &
MONROE ROAD ', PREPARED BY GARY BRUCE DAVISON, L.S., DATED
JULY 28, 1993.
6. MAP ENTITLED, ' LANDS OF DONALD W. MONROE + PATRICIA H/W ',
PREPARED BY W.M. MOTT ASSOCIATES, P.E., L.S., DATED APRIL 20,
1976.


DONALD F. JONES, JR. AND
DIANE M. ECCLESTON
(REPUTED OWNERS)

DONALD F. JONES, JR. AND
DIANE M. ECCLESTON
(REPUTED OWNERS)




GREG SCHMIDT AND
CAROLYN SCHMIDT
ALLEN S. CRAWFORD AND
ROBERTA J. CRAWFORD
(REPUTED OWNERS)

CERTIFICATION

WE, POPLI ARCHITECTURE + ENGINEERING & L.S.,
P.C., HEREBY CERTIFY TO THE NEW YORK STATE
DEPARTMENT OF ENVIRONMENTAL CONSERVATION
THAT THIS SURVEY AND MAP WAS PREPARED
UNDER THE DIRECTION OF A LICENSED LAND
SURVEYOR AND FROM THE NOTES OF AN
INSTRUMENT SURVEY COMPLETED DECEMBER 15,
2009 AND THE REFERENCES LISTED HEREON. THIS
SURVEY IS SUBJECT TO ANY EASEMENTS AND/OR
ENCUMBRANCES AN UP-TO-DATE ABSTRACT OF
TITLE MAY REVEAL, AS NONE WAS PROVIDED.



VICINITY MAP



LEGEND

- TP37 S TEST PIT
- SW/SD SAMPLE POINT
- MONITORING WELL
- EM FLAG (CHAIN OF FLAGS BOUND THE DEBRIS ON SITE)
- TREE LINE
- STORM DRAIN PIPE W/ INVERT ELEVATIONS

SURVEY BY:		PREPARED FOR:	
			
ARCHITECTURE ENGINEERING 555 Pentecost Drive Parsippany NJ 08859			
SURVEYOR JOB NUMBER:		3282.07	
SURVEY CREW:		J. PHILLIPS, W. STRATTON	
DRAWN BY:		J. PHILLIPS	
CHECKED BY:		M. VENTURO	
REVISIONS			

BOUNDARY & TOPOGRAPHIC MAP

FOR THE
NEW YORK STATE D.E.C.
FORMER SOUTH HILL DUMP SITE

Being part of Lot #100
Town of Cortlandville, County of Cortland, State of New York
DATE: JANUARY 20, 2010
SCALE: 1" = 50'
SHEET: 1 OF 1

APPENDIX C

INACTIVE HAZARDOUS WASTE DISPOSAL SITES DATABASE SITE SUMMARY

Appendix C contains a site summary for the South Hill Dump Site provided by the NYSDEC's Inactive Hazardous Waste Disposal Sites Database dated March 17, 2005. This information is offered for consideration when planning the remedial work.



Inactive Hazardous Waste Disposal Sites Database Search

More information:

[Environmental Remediation Databases](#)

[Glossary of Hazardous Waste Sites Database Terms](#)

More searches:

[New Inactive Hazardous Waste Disposal Sites Database Search](#)

[Other Links of Interest...](#)

Site Record

Administrative Information

Site Name: Rosen Site (a.k.a. Scrap King, Inc.)

Site Code: 712004

[Classification:](#) 02

EPA ID Number:

Location

DEC Region: 7

Address: Pendleton Street

City: Cortland **Zip:** 13045

County: Cortland

Latitude: 42:35:30 **Longitude:** 76:10:29

Site Type: DUMP

Estimated Size: 20 Acres

Site Owner(s)

Current Owner Name: PHILLIP ROSEN

Current Owner(s) Address: PENDLETON STREET
CORTLAND ,NY 13045

Site Owner(s)

Current Owner Name: Philip Rosen

Current Owner(s) Address: 107 Avon Court
Slidell ,LA 70461

Site Owner(s)

Current Owner Name: PHILLIP ROSEN

Current Owner(s) Address: 107 AVON COURT
SLIDELL ,LA 70461

Owner(s) during disposal: PHILLIP ROSEN

Operator during disposal: PHILLIP ROSEN

Stated Operator(s) Address: 129 PORT WATSON
CORTLAND ,NY 13045

Operator during disposal: Wickwire Brothers, Inc.

Stated Operator(s) Address: Pendleton Street
Cortland ,NY 13045

Operator during disposal: PHILLIP ROSEN

Stated Operator(s) Address: PENDLETON STREET
CORTLAND ,NY 13045

Operator during disposal: Phillip Rosen

Stated Operator(s) Address: 129 Port Watson
Cortland ,NY 13045

Hazardous Waste Disposal Period From: 1975 **To:** 1985

Site Description:

The Rosen site is a closed scrap yard where construction & demolition (C & D) waste and other items were dumped. Car crushing was one of the major operations here. Some of the wastes included old tires, drums (some marked as pesticides and paints), piles of metal shavings and other unknown industrial & municipal wastes. Prior to the Rosen's business, the property was operated by the Wickwire Brothers Company. They manufactured wire screens until 1970 when the factory burned to the ground. While they were in business, they dumped industrial waste on site. The site overlies an the aquifer that supplies drinking water for the City of Cortland. It is the sole source of drinking water for approximately 24,000 people. Inspections have noted that some waste has been pushed into a creek on the site. Some of the soil on the property was saturated with fouled fluids from the old car crushing operation, as well as leaking drums of 1,1,1-Trichloroethane (1,1,1-TCA). A Phase II Investigation was completed in May of 1987. Groundwater sampling

revealed contamination. The USEPA conducted a removal action at the end of the 1990 construction season in which all containerized wastes on site were removed & taken to an approved disposal site. The area was fenced to restrict access. The PRPs signed a Consent Order (CO) with the USEPA for a Remedial Investigation/Feasibility Study (RI/FS). The completed RI identified significant levels of chlorinated solvents, primarily 1,1,1-TCA, in on-site soils, groundwater and in the groundwater that is off-site and downgradient. PCBs, heavy metals and polynuclear aromatic hydrocarbons (PAHs) were also found in portions of the on-site soils. The source locations are uncertain. The final RI report was submitted in May of 1994. A Record of Decision (ROD) was signed in March of 1998. The ROD calls for a soil cap over the entire site, consolidation of the C&D waste and contaminated soils and materials into the "cooling pond" area, and placing a Part 360 cap over this area. The Remedial Design (RD) was completed in 2002. Construction is underway.

Confirmed Hazardous Waste Disposal Type and Quantity:

Type of Waste	Quantity of Waste
DRUMS (POSSIBLY CONTAINING PAINT AND OR PESTICIDES)	UNKNOWN
WASTE FLUIDS FROM THE CAR CRUSHING OPERATION	UNKNOWN
TRANS 1,1-DICHLOROETHANE	UNKNOWN
CIS 1,2-DICHLOROETHANE	UNKNOWN
1,1,1-TRICHLOROETHANE (TCA)	UNKNOWN
TETRACHLOROETHANE (PCE OR "PERC.")	UNKNOWN

Assessment of Environmental Problems:

Extensive sections of the property are covered with municipal waste. Some sections of soil are saturated with contaminated fluids from the car crushing operation.

Assessment of Health Problems:

Groundwater at the site is contaminated, but the area is served by public water so ingestion of contaminated

groundwater is not a concern. The site is fenced and secured so access is unlikely. Presently, there are no known exposures to site contaminants.

The information in this record also appears each year in the annual report, *Registry of Inactive Hazardous Waste Disposal Sites in New York State*. If you have questions regarding the information in this database, please contact the Department at (518) 402-9553 for further assistance.

Other Links of Interest

[Priority Classification](#) definitions of the site classification codes used in the inactive hazardous waste disposal records

[Information about the Inactive Hazardous Waste Disposal Site Program](#)

[Phone Numbers for Environmental Site Remediation](#)

APPENDIX D

SELECTED APPENDICES FROM REMEDIAL INVESTIGATION REPORT

Appendix D contains groundwater elevation data, vertical groundwater gradients, test pit logs, well installation boring logs, and well construction logs from the Final Remedial Investigation Report for the South Hill Dump Inactive Hazardous Waste Disposal Site by NYSDEC (July 2003). This information is offered for consideration when planning the remedial work.

GROUNDWATER ELEVATION DATA
SOUTH HILL DUMP SITE
CORTLANDVILLE TOWNSHIP, NEW YORK

WELL	GROUND SURFACE ELEVATION (feet)	REFERENCE ELEVATION (feet)	SCREEN/OPEN HOLE DEPTH		SCREEN/OPEN HOLE ELEVATION		DATE: 5/22/97		DATE: 6/11/97	
			TOP (feet)	BOTTOM (feet)	TOP (feet)	BOTTOM (feet)	DEPTH TO WATER (ft. below Ref.)	WATER ELEVATION (feet)	DEPTH TO WATER (ft. below Ref.)	WATER ELEVATION (feet)
MW-1S	1668.1	1670.95	5.0	15.0	1663.10	1653.10	10.26	1660.69	12.88	1658.07
MW-1B	1668.5	1671.35	25.0	35.0	1643.50	1633.50	22.22	1649.13	23.03	1648.32
MW-2S	1572.6	1575.45	5.0	10.0	1567.60	1562.60	12.02	1563.43	10.97	1564.48
MW-2D	1572.0	1575.00	14.0	24.0	1558.00	1548.00	16.18	1558.82	11.38	1563.62
MW-2B	1573.4	1574.85	31.5	41.5	1541.90	1531.90	10.06	1564.79	12.45	1562.40
MW-3S	1568.3	1571.15	5.0	10.0	1563.30	1558.30	4.04	1567.11	4.70	1566.45
MW-3B	1567.3	1570.20	16.0	26.0	1551.30	1541.30	4.24	1565.96	5.56	1564.64
MW-4S	1542.6	1545.40	6.0	16.0	1536.60	1526.60	5.48	1539.92	8.67	1536.73
MW-4B	1541.9	1545.45	36.0	46.6	1505.90	1495.30	27.09	1518.36	28.00	1517.45

**VERTICAL GRADIENTS
SOUTH HILL DUMP SITE
CORTLANDVILLE, NEW YORK**

WELL PAIR	UPPER WELL	LOWER WELL	DATE: 5/22/97			DATE: 6/11/97		
	TOP SCREEN ELEVATION (feet)	TOP SCREEN ELEVATION (feet)	UPPER WATER ELEVATION (feet)	LOWER WATER ELEVATION (feet)	VERTICAL* GRADIENT (feet/foot)	UPPER WATER ELEVATION (feet)	LOWER WATER ELEVATION (feet)	VERTICAL* GRADIENT (feet/foot)
MW-1S/1B	1663.1	1643.5	1660.69	1649.13	-0.672	1658.07	1648.32	-0.669
MW-2S/2D	1567.6	1558.0	1563.43	1558.82	-0.849	1564.48	1563.62	-0.133
MW-2S/2B	1567.6	1541.9	1563.43	1564.79	0.063	1564.48	1562.40	-0.092
MW-2D/2B	1558.0	1541.9	1558.82	1564.79	0.371	1563.62	1562.40	-0.076
MW-3S/3B	1563.3	1551.3	1567.11	1565.96	-0.096	1566.45	1564.64	-0.151
MW-4S/4B	1536.6	1505.9	1539.92	1518.36	-0.702	1536.73	1517.45	-0.628


* If the water level in the upper well was above the top of the upper well screen, then the vertical distance between water level measurements was calculated using the elevation of the top of the upper well screen. Otherwise, the upper water level elevation was used. Positive gradients indicate upward flow.

**PARSONS ENGINEERING SCIENCE, INC.
TEST PIT RECORD**

PROJECT NAME: NYSDEC - South Hill Dump
 PROJECT NUMBER: 729396.02000
 WEATHER: Sunny, 40s
 DATE/TIME START: February 26, 1997 / 1315
 DATE/TIME FINISH: February 26, 1997 / 1330
 CONTRACTOR: Marcor Environmental
 INSPECTOR: N.A. Smith

TEST PIT ID: TP-1

LOCATION: Upper level, north of Mound 1.



DEPTH (feet bgs)	FIELD IDENTIFICATION OF MATERIAL	COMMENTS
1	COVER SOIL - gray sand, some stone. 2 ft	Drum fragment PID: 0.0 ppm
2		
3	FILL - brown sand, metal cans, plastic, drum fragments.	
4		
5	FILL - as above with wood, concrete, burned cans, oil filter, washing machine. Encountered black stained area approx. 15 feet from west edge of trench. 7.5 ft	
6		
7		
8		
9	NATIVE SOIL - CLAY, some silt, trace fine gravel, brown-gray, soft, damp. 9 ft	
10	Trench terminated at 9 feet bgs.	
11		
12		
13		
14		
15		
16		
17		
18		
19		
20		
21		
22		

SUMMARY

Dimensions (LENGTH x WIDTH x DEPTH): 32 feet x 5 feet x 9 feet

Analytical samples collected: TP-01-01 - from stained area 17 feet from west end of trench and 5 feet deep.


Downwind air monitoring results: PID: 0.0 ppm LEL: NORMAL Cyanide Draeger: NON-DETECT

**PARSONS ENGINEERING SCIENCE, INC.
TEST PIT RECORD**

PROJECT NAME: NYSDEC - South Hill Dump
 PROJECT NUMBER: 729396.02000
 WEATHER: Sunny, 40s
 DATE/TIME START: February 26, 1997 / 1533
 DATE/TIME FINISH: February 26, 1997 / 1550
 CONTRACTOR: Marcor Environmental
 INSPECTOR: N.A. Smith

TEST PIT ID: TP-2

LOCATION: Upper level, across Mound 1.



DEPTH (feet bgs)	FIELD IDENTIFICATION OF MATERIAL	COMMENTS
1	C & D FILL - mounded brown silt and stone, some asphalt debris.	Excavating from top of mound.
2		
3		
4		
5		
6		
7		
8		
9		
10	FILL - Remnants of burned debris, metal scraps, glass bottles, and muffler.	At base of mound, level with surrounding grade.
11		
12		
13		
14		
15		
16		
17		
18	NATIVE SOIL - CLAY and SILT. Trench terminated at 17 feet bgs.	
19		
20		
21		
22		

SUMMARY

Dimensions (LENGTH x WIDTH x DEPTH): 25 feet x 10 feet x 17 feet

No analytical samples collected.


Downwind air monitoring results: PID: 0.0 ppm LEL: NORMAL Cyanide Draeger: NON-DETECT

**PARSONS ENGINEERING SCIENCE, INC.
TEST PIT RECORD**

PROJECT NAME: NYSDEC - South Hill Dump
 PROJECT NUMBER: 729396.02000
 WEATHER: Rain, 40s
 DATE/TIME START: February 27, 1997 / 0905
 DATE/TIME FINISH: February 27, 1997 / 1019
 CONTRACTOR: Marcor Environmental
 INSPECTOR: N.A. Smith

TEST PIT ID: TP-3

LOCATION: Upper level, northwest corner.



DEPTH (feet bgs)	FIELD IDENTIFICATION OF MATERIAL	COMMENTS
1	FILL (on slope) - brown silt, sand, stone, timbers, and carpet.	Drum ID: TP-3-D1 Drum opened 3/20/97. PID: 29 ppm LEL: 4% Contents: Approx. 1 inch of ice. Unable to collect sample.
2	FILL (on top of slope) - tires, concrete slabs, and white metal.	
3	Intact, rusted drum excavated from 20 feet east of top of slope and overpacked.	
4	FILL - metal piping and sheets, car bumper and axle, empty crushed corroded drum and several drum lids.	
5		
6		
7		
8	8 ft	
9	NATIVE SOIL - Brown CLAY and SILT align="right">9 ft	
10	Trench terminated at 9 feet bgs.	
11		
12		
13		
14		
15		
16		
17		
18		
19		
20		
21		
22		

SUMMARY

Dimensions (LENGTH x WIDTH x DEPTH): 25 feet x 13 feet x 9 feet

Analytical samples collected: TP-03-01 - soil below excavated drum 20 feet from top of slope and 3 feet deep.


Downwind air monitoring results: PID: 0.0 ppm LEL: NORMAL Cyanide Draeger: NON-DETECT

**PARSONS ENGINEERING SCIENCE, INC.
TEST PIT RECORD**

PROJECT NAME: NYSDEC - South Hill Dump
 PROJECT NUMBER: 729396.02000
 WEATHER: Breezy, 45 degrees
 DATE/TIME START: February 27, 1997 / 1100
 DATE/TIME FINISH: February 27, 1997 / 1141
 CONTRACTOR: Marcor Environmental
 INSPECTOR: N.A. Smith

TEST PIT ID: TP-4

LOCATION: Upper level, west slope.



DEPTH (feet bgs)	FIELD IDENTIFICATION OF MATERIAL	COMMENTS
1	COVER SOIL - gray sand, some stone and concrete slabs.	Three empty drums observed at base of slope. Fill on slope overlays cover. No elevated PID reading from corroded drum.
2	FILL (on slope) - brown silt, sand, stone, timbers, sofabad, water heater, metal bands and rod fragments, corroded drum containing small amount of soil .	
3	FILL - metal piping, straps, and sheets, scattered crushed corroded drum carcasses.	
4	Evidence of burn and cover layering on eastern portion of trench.	
5		
6		
7	Open drum 15 feet from base of slope containing trash (paper, fabric, some soil).	
8		
9		
10		
11	11 ft	
12	NATIVE SOIL - Brown CLAY and SILT Trench terminated at 11 feet bgs.	
13		
14		
15		
16		
17		
18		
19		
20		
21		
22		

SUMMARY

Dimensions (LENGTH x WIDTH x DEPTH): 37 feet x 14 feet x 11 feet

No analytical samples collected.

Downwind air monitoring results: PID: 0.0 ppm LEL: NORMAL Cyanide Draeger: NON-DETECT


**PARSONS ENGINEERING SCIENCE, INC.
TEST PIT RECORD**

PROJECT NAME: NYSDEC - South Hill Dump
 PROJECT NUMBER: 729396.02000
 WEATHER: Sunny, windy, 50s
 DATE/TIME START: February 27, 1997 / 1425
 DATE/TIME FINISH: February 27, 1997 / 1450
 CONTRACTOR: Marcor Environmental
 INSPECTOR: N.A. Smith

TEST PIT ID: TP-5

LOCATION: Upper level, western portion south of Mound 1.

Excavation began at top of slope to west.



DEPTH (feet bgs)	FIELD IDENTIFICATION OF MATERIAL	COMMENTS	
1	COVER SOIL - sand, silt, stone, and concrete slabs.		
2			
3			
4			
5	FILL - Layer of black burned debris.		4.0 ft
6	COVER SOIL - sand, silt, and stone.		4.5 ft
7	FILL - Burned debris including ash, metal scraps, glass bottles, and food wrappers.		5.5 ft
8			
9			
10			
11	Excavation stopped - slope unstable. Native soil not encountered.		11.0 ft
12	Trench terminated at 11 feet bgs.		
13			
14			
15			
16			
17			
18			
19			
20			
21			
22			

SUMMARY

Dimensions (LENGTH x WIDTH x DEPTH): 40 feet x 9 feet x 11 feet

Analytical samples collected: TP-05-01 - from burn area 20 feet from west end of trench and 4 feet deep.


Downwind air monitoring results: PID: 0.0 ppm LEL: NORMAL Cyanide Draeger: NON-DETECT

**PARSONS ENGINEERING SCIENCE, INC.
TEST PIT RECORD**

PROJECT NAME: NYSDEC - South Hill Dump
 PROJECT NUMBER: 729396.02000
 WEATHER: Sunny, windy, 50s
 DATE/TIME START: February 27, 1997 / 1605
 DATE/TIME FINISH: February 27, 1997 / 1620
 CONTRACTOR: Marcor Environmental
 INSPECTOR: N.A. Smith

TEST PIT ID: TP-6

LOCATION: Upper level, south of Mound 1.



DEPTH (feet bgs)	FIELD IDENTIFICATION OF MATERIAL	COMMENTS
1	COVER SOIL - sand, silt, stone, and concrete slabs. 1 ft	
2	FILL - Household debris including metal cans, glass bottles, rags, carpet, brick, lumber, wall tiles, and fiberglass insulation.	
3		
4		
5	5 ft	
6	NATIVE SOIL - Brown CLAY and SILT	
7		
8	8 ft	
9	Trench terminated at 8 feet bgs.	
10		
11		
12		
13		
14		
15		
16		
17		
18		
19		
20		
21		
22		

SUMMARY

Dimensions (LENGTH x WIDTH x DEPTH): 42 feet x 5 feet x 8 feet

No analytical samples collected.


Downwind air monitoring results: PID: 0.0 ppm LEL: NORMAL Cyanide Draeger: NON-DETECT

**PARSONS ENGINEERING SCIENCE, INC.
TEST PIT RECORD**

PROJECT NAME: NYSDEC - South Hill Dump
 PROJECT NUMBER: 729396.02000
 WEATHER: Partly sunny, 30s
 DATE/TIME START: February 28, 1997 / 0845
 DATE/TIME FINISH: February 28, 1997 / 0912
 CONTRACTOR: Marcor Environmental
 INSPECTOR: N.A. Smith

TEST PIT ID: TP-7

LOCATION: Upper level, along west edge of Mound 2.



DEPTH (feet bgs)	FIELD IDENTIFICATION OF MATERIAL	COMMENTS
1	COVER SOIL - sand, silt, and stone. FILL - Metal bands, cans, plastic bottles, and cut limbs.	Soil sample PID: 0.5 ppm
2		
3		
4		
5		
6		
7		
8		
9	Black stained burn area approx. 5 feet from south end of trench. 8 ft	
10	FILL - Household debris, scrap metal, brick, cinder block, plastic bags and sheeting. Depth of fill increases northward.	
11		
12		
13		
14		
15		
16	NATIVE SOIL - Brown CLAY and SILT 15 ft	
17	Trench terminated at approx. 16 feet bgs. Unable to measure due to caving of sidewalls.	
18		
19		
20		
21		
22		

SUMMARY

Dimensions (LENGTH x WIDTH x DEPTH): 34 feet x 9 feet x 16 feet

Analytical samples collected: TP-07-01 - from stained area 5 feet from south end of trench and 8 feet deep.


Downwind air monitoring results: PID: 0.0 ppm LEL: NORMAL Cyanide Draeger: NON-DETECT

**PARSONS ENGINEERING SCIENCE, INC.
TEST PIT RECORD**

PROJECT NAME: NYSDEC - South Hill Dump
 PROJECT NUMBER: 729396.02000
 WEATHER: Partly sunny, 40s
 DATE/TIME START: February 28, 1997 / 1015
 DATE/TIME FINISH: February 28, 1997 / 1040
 CONTRACTOR: Marcor Environmental
 INSPECTOR: N.A. Smith

TEST PIT ID: TP-8

LOCATION: Center of Upper level, east of Mound 2.



DEPTH (feet bgs)	FIELD IDENTIFICATION OF MATERIAL	COMMENTS
1	COVER SOIL - sand, silt, and stone.	Excavating from top of mound.
2		
3		
4		At base of mound, level with surrounding grade.
5		5 ft
6	FILL - Household debris, scrap metal, ash, rags, tires, plastic bags and sheeting. Drum lid approx. 25 feet from west edge of trench. Evidence of burn and cover layering on eastern portion of trench.	Increase in ash concentration to east.
7		Hydrocarbon (fuel oil) odor noted on excavated soils, but no elevated PID readings.
8		
9		
10		Newspaper dated September 4, 1969 found on excavated soil pile.
11		
12		
13		13 ft
14	NATIVE SOIL - Brown CLAY and SILT Trench terminated at 13 feet bgs.	
15		
16		
17		
18		
19		
20		
21		
22		

SUMMARY

Dimensions (LENGTH x WIDTH x DEPTH): 44 feet x 5 feet x 13 feet

Analytical samples collected: TP-08-01 - from ash with hydrocarbon odor 2 feet deep from east end of trench.

Downwind air monitoring results: PID: 0.0 ppm LEL: NORMAL Cyanide Draeger: NON-DETECT

**PARSONS ENGINEERING SCIENCE, INC.
TEST PIT RECORD**

PROJECT NAME:	NYSDEC - South Hill Dump	TEST PIT ID: TP-9												
PROJECT NUMBER:	729396.02000	LOCATION: Upper level, east of Mound 2, near slope to												
WEATHER	Partly sunny, 40s	Level 2.												
DATE/TIME START:	February 28, 1997 / 1130	<table border="1" style="margin: auto;"> <tr> <td style="width:30%;">WEST</td> <td style="width:40%;">CROSS SECTION VIEW</td> <td style="width:30%;">EAST</td> </tr> <tr> <td colspan="3" style="text-align: center;">COVER w/ LITTLE-SOME FILL</td> </tr> <tr> <td colspan="3" style="text-align: center;">FILL</td> </tr> <tr> <td colspan="3" style="text-align: center;">NATIVE SOIL</td> </tr> </table>	WEST	CROSS SECTION VIEW	EAST	COVER w/ LITTLE-SOME FILL			FILL			NATIVE SOIL		
WEST	CROSS SECTION VIEW		EAST											
COVER w/ LITTLE-SOME FILL														
FILL														
NATIVE SOIL														
DATE/TIME FINISH:	February 28, 1997 / 1145													
CONTRACTOR:	Marcor Environmental													
INSPECTOR:	N.A. Smith													

DEPTH (feet bgs)	FIELD IDENTIFICATION OF MATERIAL	COMMENTS
1	COVER SOIL - sand, silt, and stone, trash (bottle, cans). 4 ft	
2		
3		
4		
5	COVER SOIL and FILL - sand, silt, and stone, trash . Fill includes sheet metal, bagged household trash, bottles, and plastic containers. 7 ft	
6		
7		
8	FILL - concentrated layer of bagged household trash, bottles, and plastic contaners. 11 ft	
9		
10		
11		
12	NATIVE SOIL - Brown CLAY, some silt and fine-medium gravel (TILL). 15 ft	
13		
14		
15		
16	Trench terminated at 15 feet bgs.	
17		
18		
19		
20		
21		
22		

SUMMARY

Dimensions (LENGTH x WIDTH x DEPTH): 19 feet x 10 feet x 15 feet

No analytical samples collected.


Downwind air monitoring results: PID: 0.0 ppm LEL: NORMAL Cyanide Draeger: NON-DETECT

**PARSONS ENGINEERING SCIENCE, INC.
TEST PIT RECORD**

PROJECT NAME: NYSDEC - South Hill Dump
 PROJECT NUMBER: 729396.02000
 WEATHER: Sunny, 50s
 DATE/TIME START: February 28, 1997 / 1345
 DATE/TIME FINISH: February 28, 1997 / 1415
 CONTRACTOR: Marcor Environmental
 INSPECTOR: N.A. Smith

TEST PIT ID: TP-10

LOCATION: Upper level, on flat eastern portion.



DEPTH (feet bgs)	FIELD IDENTIFICATION OF MATERIAL	COMMENTS
1	COVER SOIL - sand, silt, stone, railroad ties, timbers, and piping.	
2	Culvert pipe section 20 feet from south end of trench.	
3		
4		
5		
6	6 ft	
7	FILL - concentrated layer of bagged household trash, bottles, cans, cloth, and cooking utensils.	Layer slopes north to south.
8	8 ft	
9	COVER SOIL and FILL - sand, silt, and stone with trash .	
10		
11		
12	12 ft	
13	FILL - concentrated layer of white plastic brackets used to hold molded parts. 13 ft	Layer slopes north to south. Similar pieces found in other test pits with typewriter keys attached.
14	COVER SOIL and FILL - sand, silt, and stone with little-some trash .	
15	Pile of small rubber caps approx. 15 feet from south end of trench. 15 ft	
16	Slope unstable - unable to continue. Trench terminated at 15 feet bgs. Native soil not encountered.	
17		
18		
19		
20		
21		
22		

SUMMARY


Dimensions (LENGTH x WIDTH x DEPTH): 36 feet x 13 feet x 15 feet

Analytical samples collected: TP-10-01 - near rubber caps 15 feet from south end of trench and 15 feet deep.

Downwind air monitoring results: PID: 0.0 ppm LEL: NORMAL Cyanide Draeger: NON-DETECT

**PARSONS ENGINEERING SCIENCE, INC.
TEST PIT RECORD**

PROJECT NAME:	NYSDEC - South Hill Dump	TEST PIT ID: TP-11
PROJECT NUMBER:	729396.02000	LOCATION: Upper level, on flat eastern portion.
WEATHER	Sunny, 50s	
DATE/TIME START:	February 28, 1997 / 1450	
DATE/TIME FINISH:	February 28, 1997 / 1520	
CONTRACTOR:	Marcor Environmental	
INSPECTOR:	N.A. Smith	



DEPTH (feet bgs)	FIELD IDENTIFICATION OF MATERIAL	COMMENTS
1	COVER SOIL - mounded sand, silt, and stone. 2 ft	Excavating from top of mound which was later moved in order to access Test Pit 19.
2		
3	COVER SOIL - gray-blue clay. 4 ft	At base of mound, level with surrounding grade. Clay PID: 0.8 ppm
4		
5	FILL - household debris, metal cans, and charred wood fragments. Crushed drum found 8 feet from north end of trench. Concentrated layer of white plastic brackets used to hold molded parts at start of trench. 6 ft	Crushed drum PID: 0.5 ppm Similar pieces found in other test pits with typewriter keys attached.
6		
7	FILL - gray clay mixed with C&D debris. Crushed drum found 20 feet from north end of trench. Corroded drum fragments found 5 feet from north end of trench. 17 ft	Crushed drum PID: 0.5 ppm Drum fragment PID: 1.0 ppm
8		
9		
10		
11		
12		
13		
14		
15		
16		
17		
18	Trench terminated at 17 feet bgs. Native soil not encountered.	
19		
20		
21		

SUMMARY

Dimensions (LENGTH x WIDTH x DEPTH): 34 feet x 5 feet x 17 feet


Analytical samples collected: TP-11-01 - stained area near crushed drum 20 feet from north end, 12 feet deep.

TP-11-02 - from gray-blue clay 3 feet from north end of trench and 4 feet deep.

Downwind air monitoring results: PID: 0.0 ppm LEL: NORMAL Cyanide Draeger: NON-DETECT

**PARSONS ENGINEERING SCIENCE, INC.
TEST PIT RECORD**

PROJECT NAME:	NYSDEC - South Hill Dump	TEST PIT ID: TP-12
PROJECT NUMBER:	729396.02000	LOCATION: Upper level, on flat eastern portion.
WEATHER:	Partly sunny, 30s	
DATE/TIME START:	March 3, 1997 / 1114	
DATE/TIME FINISH:	March 3, 1997 / 1415	
CONTRACTOR:	Marcor Environmental	
INSPECTOR:	N.A. Smith	




DEPTH (feet bgs)	FIELD IDENTIFICATION OF MATERIAL	COMMENTS
1	COVER SOIL - sand, silt, stone and tree stumps. 9 ft	
2		
3		
4		
5		
6		
7		
8		
9		
10	FILL - Household debris in plastic bags, carpet, metal cans, glass bottles, and lumber.	Water leaking from trash. Slight sheen
11	Fill on western portion of trench is burned and mostly ash.	
12	Two crushed drums containing a resinous substance found 12 feet from east end of trench.	Crushed drum PID: 1.0 ppm
13		
14	Large amount (multiple excavator buckets) of fishing line.	
15	Several small green plastic beads, typewriter ribbon, and plastic parts labelled "Smith-Corona" 15 feet from east end of trench.	Bucket scoop PID: 1.7 ppm
16	Burned, crushed drum found 16 feet from east end of trench.	Crushed drum PID: 2.7 ppm
17	Slope unstable - unable to continue excavation. 17 ft	
18	Trench terminated at 17 feet bgs. Native soil not encountered.	
19		
20		
21		
22		

SUMMARY	Dimensions (LENGTH x WIDTH x DEPTH): 32 feet x 11 feet x 17 feet
	Analytical samples collected: TP-12-01(DUP. ID:TP-12-11) - stained soil from center of trench 17 feet deep.
	Downwind air monitoring results: PID: 1.0 ppm LEL: NORMAL Cyanide Draeger: NON-DETECT

**PARSONS ENGINEERING SCIENCE, INC.
TEST PIT RECORD**

PROJECT NAME:	NYSDEC - South Hill Dump	TEST PIT ID: TP-13
PROJECT NUMBER:	729396.02000	LOCATION: Upper level, on flat eastern portion.
WEATHER	Partly sunny, 30s	
DATE/TIME START:	March 3, 1997 / 1542	
DATE/TIME FINISH:	March 3, 1997 / 1621	
CONTRACTOR:	Marcor Environmental	
INSPECTOR:	N.A. Smith	



DEPTH (feet bgs)	FIELD IDENTIFICATION OF MATERIAL	COMMENTS
1	COVER SOIL - sand, silt, stone and tree stumps. 4 ft	Increase in trash proportion to north. Crushed drum PID: 5.0 ppm

SUMMARY


Dimensions (LENGTH x WIDTH x DEPTH): 29 feet x 9 feet x 16 feet

No analytical samples collected.

Downwind air monitoring results: PID: 0.0 ppm LEL: NORMAL Cyanide Draeger: NON-DETECT

**PARSONS ENGINEERING SCIENCE, INC.
TEST PIT RECORD**

PROJECT NAME:	NYSDEC - South Hill Dump	TEST PIT ID: TP-14
PROJECT NUMBER:	729396.02000	LOCATION: Upper level, southeast edge of flat portion.
WEATHER	Light snow, 30s	
DATE/TIME START:	March 4, 1997 / 0830	
DATE/TIME FINISH:	March 4, 1997 / 0921	
CONTRACTOR:	Marcor Environmental	
INSPECTOR:	N.A. Smith	




DEPTH (feet bgs)	FIELD IDENTIFICATION OF MATERIAL	COMMENTS
1	COVER SOIL - silt, sand, stone with scattered stumps and cans.	
2		
3		
4	FILL - household debris in bags, charcoal lighter fluid can, tires, lumber.	Depth to start of fill increases to 4 ft on west side of trench.
5		
6		
7		
8		
9		
10		
11		
12		
13		
14	FILL - household debris in bags mixed in gray clay cover soil, stone, and concrete slabs.	Drum PID: 0.8 ppm
15		
16		
17		
18		
19		
20		
21		
22		
23	Flattened drum 20 feet from west end. Also plastic molds labelled "Smith Corona" with typewriter key shaped holes punched out.	Similar pieces found in other test pits with typewriter keys attached.
24		
25		
26		
27		
28		
29		
30		
31		
32		
33	Concentrated layer of angled white plastic brackets used to hold molded parts.	
34		
35		
36		
37		
38		
39		
40		
41		
42		
43	Water entering west end of trench.	
44		
45		
46		
47		
48		
49		
50		
51		
52		
53	BEDROCK	Trench terminated at 21 feet bgs.
54		
55		
56		
57		
58		
59		
60		
61		
62		

SUMMARY	Dimensions (LENGTH x WIDTH x DEPTH):	35 feet x 5 feet x 21 feet
	No analytical samples collected.	
	Downwind air monitoring results:	PID: 0.4 ppm LEL: NORMAL Cyanide Draeger: NON-DETECT

**PARSONS ENGINEERING SCIENCE, INC.
TEST PIT RECORD**

PROJECT NAME:	NYSDEC - South Hill Dump	TEST PIT ID: TP-15
PROJECT NUMBER:	729396.02000	LOCATION: Upper level, southeast corner of flat portion.
WEATHER	Sunny, 30s	
DATE/TIME START:	March 4, 1997 / 1000	
DATE/TIME FINISH:	March 4, 1997 / 1055	
CONTRACTOR:	Marcor Environmental	
INSPECTOR:	N.A. Smith	




DEPTH (feet bgs)	FIELD IDENTIFICATION OF MATERIAL	COMMENTS
1	COVER SOIL - silt, sand, stone with scattered stumps, plastic, and cans.	
2		
3		
	3 ft	
4	FILL - household debris in bags, bottles, paint cans, tires, lumber, carpet.	Depth to fill increases to east.
5		
6		
7		
8		
9		
10		
11		
	Concentrated layer of angled white plastic brackets used to hold molded parts and plastic molds with typewriter key shaped holes punched out.	Found on excavated soil pile: Newspaper dated February 2, 1972 and a deer carcass.
12		
13		
14		
15		
16		
17		
	17 ft	
18	NATIVE SOIL - Till	
	18 ft	
19	Trench terminated at 18 feet bgs.	
20		
21		

SUMMARY	Dimensions (LENGTH x WIDTH x DEPTH): 42 feet x 6 feet x 18 feet		
	No analytical samples collected.		
	Downwind air monitoring results:	PID: 0.0 ppm	LEL: NORMAL Cyanide Draeger: NON-DETECT

**PARSONS ENGINEERING SCIENCE, INC.
TEST PIT RECORD**

PROJECT NAME:	NYSDEC - South Hill Dump	TEST PIT ID: TP-16
PROJECT NUMBER:	729396.02000	LOCATION: Upper level, east edge of flat eastern portion.
WEATHER	Partly sunny, 30s	
DATE/TIME START:	March 3, 1997 / 1114	
DATE/TIME FINISH:	March 3, 1997 / 1415	
CONTRACTOR:	Marcor Environmental	
INSPECTOR:	N.A. Smith	



DEPTH (feet bgs)	FIELD IDENTIFICATION OF MATERIAL	COMMENTS
1	COVER SOIL - sand, silt, stone, brown.	
2		
3		
4		
5	FILL - wood, blue plastic sheeting, burned material.	Resin PID: 3 ppm Fiber PID: 8 ppm Drum ID: TP-16-D1 Drum PID: 7.2 ppm
6	SAND, tan, approx. 20 feet from south end.	
7	White-tan resin, and gray-green fibrous material mixed with cover soil near south end.	
8	Half of sheared drum containing similar resin and fibers found 5 feet from south end of trench.	
9	Crushed drum excavated 12 feet from south end and overpacked into 55-gallon drum. Drum contains orange-rust colored soil with glue-type odor.	
10		
11		
12		
13		
14		
15		
16		
17		
18	BEDROCK, water at interface. Trench terminated at 17 feet bgs.	
19		
20		
21		

SUMMARY

Dimensions (LENGTH x WIDTH x DEPTH): 36 feet x 5 feet x 17 feet

Analytical samples collected: TP-16-01 - resin and fibers near crushed drum 5 feet from south end, 5 feet deep.
TP-16-02 - from crushed drum 12 feet from south end of trench.

Downwind air monitoring results: PID: 0.0 ppm LEL: NORMAL Cyanide Draeger: NON-DETECT

**PARSONS ENGINEERING SCIENCE, INC.
TEST PIT RECORD**

PROJECT NAME: NYSDEC - South Hill Dump
 PROJECT NUMBER: 729396.02000
 WEATHER: Partly sunny, 40s
 DATE/TIME START: March 4, 1997 / 1515
 DATE/TIME FINISH: March 4, 1997 / 1600
 CONTRACTOR: Marcor Environmental
 INSPECTOR: N.A. Smith

TEST PIT ID: TP-17

LOCATION: Upper level, on flat eastern portion.

SOUTH	CROSS SECTION VIEW	NORTH
	COVER SOIL	
	HOUSEHOLD FILL	
	NATIVE SOIL	
	BEDROCK	

DEPTH (feet bgs)	FIELD IDENTIFICATION OF MATERIAL	COMMENTS	
1	COVER SOIL - sand, silt, and stone. 2 ft	Found on excavated soil pile: Newspaper dated November 29, 1971	
2			
3	FILL - white plastic brackets, brick, plywood. 3 ft		
4	FILL - household debris in bags, clothing, paper, cardboard, cans, tires, furniture, toys, diapers, food containers, auto and appliance parts.		
5			
6			
7			
8			
9			
10			
11			
12			
13			
14			
15			15 ft
16			NATIVE SOIL - till 16 ft
17	Trench terminated at 17 feet bgs. 17 ft		
18	BEDROCK - interface dips to 17 feet bgs on south end of trench. Water on top of rock.		
19			
20			
21			
21			

SUMMARY

Dimensions (LENGTH x WIDTH x DEPTH): 43 feet x 6 feet x 17 feet

No analytical samples collected.


Downwind air monitoring results: PID: 0.0 ppm LEL: NORMAL Cyanide Draeger: NON-DETECT

**PARSONS ENGINEERING SCIENCE, INC.
TEST PIT RECORD**

PROJECT NAME: NYSDEC - South Hill Dump
 PROJECT NUMBER: 729396.02000
 WEATHER: Partly sunny, 30s
 DATE/TIME START: March 5, 1997 / 0830
 DATE/TIME FINISH: March 5, 1997 / 0927
 CONTRACTOR: Marcor Environmental
 INSPECTOR: N.A. Smith

TEST PIT ID: TP-18

LOCATION: Upper level, on flat eastern portion.



DEPTH (feet bgs)	FIELD IDENTIFICATION OF MATERIAL	COMMENTS
1	COVER SOIL - sand, silt, and stumps.	
2	2 ft	
3	FILL - Household debris, cans, rags, clothing, plastic bags, and food containers.	
4	Fill is burned on western 7 feet of trench, high ash concentration.	Depth to fill increases to east to 4 feet bgs.
5		
6		Increase in ash concentration to east.
7	Layer of white, angled plastic brackets on eastern end.	
8	Household demolition materials in center portion of trench. Wallboard, linoleum, shingling, lumber, burlap bags.	
9	Flattened drum 24 feet from east end.	
10	Soil near drum: CLAY, some silt, brown-gray with little black staining.	Soil PID near drum: 26 ppm
11		
12		
13		
14		Newspaper dated November 2, 1971 and magazine dated April 1971 found on excavated soil pile.
15		
16		
17		
18	18 ft	
19	NATIVE SOIL - CLAY, little silt, trace pebbles, gray (TILL). align="right">19 ft	
20	BEDROCK, water at interface. Trench terminated at 19 feet bgs.	
21		
22		

SUMMARY

Dimensions (LENGTH x WIDTH x DEPTH): 42 feet x 6 feet x 19 feet

Analytical samples collected: TP-18-01 - adjacent to flattened drum 8 ft deep and 24 ft from east end of trench.


Downwind air monitoring results: PID: 0.0 ppm LEL: NORMAL Cyanide Draeger: NON-DETECT

**PARSONS ENGINEERING SCIENCE, INC.
TEST PIT RECORD**

PROJECT NAME: NYSDEC - South Hill Dump
 PROJECT NUMBER: 729396.02000
 WEATHER: Partly sunny, 40s
 DATE/TIME START: March 5, 1997 / 1035
 DATE/TIME FINISH: March 5, 1997 / 1130
 CONTRACTOR: Marcor Environmental
 INSPECTOR: N.A. Smith

TEST PIT ID: TP-19

LOCATION: Upper level, on flat eastern portion.



DEPTH (feet bgs)	FIELD IDENTIFICATION OF MATERIAL	COMMENTS
1	COVER SOIL - gray clay and stone. 1 ft	
2	FILL - bagged household trash, tires, lumber, chimney pipe, auto lights, and plastic angled brackets and typewriter keypad borders.	
3		
4	4 ft	
5	COVER SOIL & FILL - sand, silt, and stone, little trash in eastern half of trench. BURNED FILL - ash, metal fragments, sheet metal, water heater. Soil in burned area becomes rust colored 42 feet from east end of trench.	
6		
7	Burned, crushed drum 30 feet from east end, empty with greasy coating.	Drum PID: 4.4 ppm
8		
9		
10		
11	Crushed drum fragments 42 feet from east end in rusty soil. Crushed drum 51 feet from east end, has multiple holes.	Drum PID: 3.9 ppm Drum PID: 31 ppm
12		
13	13 ft	
14	NATIVE SOIL - Brown SILT.	
15	15 ft	
16	BEDROCK Trench terminated at 15 feet bgs.	
17		
18		
19		
20		
21		

SUMMARY

Dimensions (LENGTH x WIDTH x DEPTH): 59 feet x 6 feet x 15 feet

Analytical samples collected: TP-19-01 - near crushed drum 42 feet from east end, 10 feet deep.

TP-19-02 - near crushed drum 51 feet from east end, 10 feet deep.


Downwind air monitoring results: PID: 0.0 ppm LEL: NORMAL Cyanide Draeger: NON-DETECT

**PARSONS ENGINEERING SCIENCE, INC.
TEST PIT RECORD**

PROJECT NAME: NYSDEC - South Hill Dump
 PROJECT NUMBER: 729396.02000
 WEATHER: Partly sunny, 40s
 DATE/TIME START: March 5, 1997 / 1410
 DATE/TIME FINISH: March 5, 1997 / 1615
 CONTRACTOR: Marcor Environmental
 INSPECTOR: N.A. Smith

TEST PIT ID: TP-20

LOCATION: Upper level, north of Mound 2.



DEPTH (feet bgs)	FIELD IDENTIFICATION OF MATERIAL	COMMENTS
1	COVER SOIL - mounded sand, silt, and stone, brown.	Excavating from top of mound
2		
3		
4		
5		
6		
7	COVER SOIL - clay and stone, gray. 7 ft	At base of mound, level with surrounding grade.
8	FILL - Remnants of burned debris, metal scraps, concrete, plastic sheeting. Four crushed drums 48 feet from south end. Two drums empty, one left undisturbed in bank. Fourth drum contains dark gray-black fine shavings. Surrounding soil is rust-colored. Fill contains burned metal.	Drum PIDs: 23-124 ppm Drums are 1 foot below grade. 3 drums were excavated and overpacked.
9		
10		
11		
12		
13	Crushed drum 40 feet from south end, contains gray sandy material, slightly cemented.	Drum PID: 57 ppm Drum is 4 feet below grade. Drum was excavated and overpacked.
14		
15		
16	Trench terminated at 15 feet bgs. 15 ft NATIVE SOIL - Brown-gray-olive SAND and SILT.	
17		
18		
19		
20		
21		

SUMMARY

Dimensions (LENGTH x WIDTH x DEPTH): 50 feet x 6 feet x 15 feet


Analytical samples collected: DS-20-01 - from drum 40 feet from south end, 4 feet deep.

DS-20-02 - from drum in nest 48 feet from south end, 1 foot deep.

Downwind air monitoring results: PID: 0.0 ppm LEL: NORMAL Cyanide Draeger: NON-DETECT

**PARSONS ENGINEERING SCIENCE, INC.
TEST PIT RECORD**

PROJECT NAME:	NYSDEC - South Hill Dump	TEST PIT ID: TP-21
PROJECT NUMBER:	729396.02000	LOCATION: Upper level, between mounds.
WEATHER	Snow, windy, 30s	
DATE/TIME START:	March 6, 1997 / 0940	
DATE/TIME FINISH:	March 6, 1997 / 1045	
CONTRACTOR:	Marcor Environmental	
INSPECTOR:	N.A. Smith	



DEPTH (feet bgs)	FIELD IDENTIFICATION OF MATERIAL	COMMENTS
1	COVER SOIL - sand and stone, timbers and concrete, gray. Crushed drum found, empty, flattened at north end of trench.	
2	Three crushed drums at south end. Two drums left undisturbed.	Crushed drum PID: 0.0 ppm
3	Third drum is intact with partially legible label: " __NT" "Wilmington Delaware". 3 ft	3rd drum was excavated and overpacked.
4	FILL - Metal scraps, car parts, plastic sheeting.	Drum ID: TP-21-D1
5	5 ft	Drum opened 3/20/97. PID: 10.8 ppm
6	Trench terminated at 5 feet bgs.	LEL: 1%
7		Contents: Approx. 2 inches of black oily substance.
8		
9		
10		
11		
12		
13		
14		
15		
16		
17		
18		
19		
20		
21		


SUMMARY	Dimensions (LENGTH x WIDTH x DEPTH): 30 feet x 6-10 feet x 5 feet Samples collected: TP-21-D1 - soil below drum nest at south end of trench, 3 feet deep. TP-21-D1- from overpacked drum. Downwind air monitoring results: PID: 0.0 ppm LEL: NORMAL Cyanide Draeger: NON-DETECT
----------------	--

**PARSONS ENGINEERING SCIENCE, INC.
TEST PIT RECORD**

PROJECT NAME: NYSDEC - South Hill Dump
 PROJECT NUMBER: 729396.02000
 WEATHER: Snow, windy, 20s
 DATE/TIME START: March 7, 1997 / 0915
 DATE/TIME FINISH: March 7, 1997 / 0945
 CONTRACTOR: Marcor Environmental
 INSPECTOR: N.A. Smith

TEST PIT ID: TP-22

LOCATION: Upper level, along access road.



DEPTH (feet bgs)	FIELD IDENTIFICATION OF MATERIAL	COMMENTS
1	COVER SOIL - sand, silt, and stone, trace metal posts and plates, brown.	
2	Increase in metallic fill (cans and bands) in southern half of trench	
3		3 ft
4	NATIVE SOIL - CLAY, little silt, trace pebbles, gray (TILL).	
5		
6		
7		7 ft
8	BEDROCK	Trench terminated at 7 feet bgs.
9		
10		
11		
12		
13		
14		
15		
16		
17		
18		
19		
20		
21		

SUMMARY

Dimensions (LENGTH x WIDTH x DEPTH): 45 feet x 6 feet x 7 feet

No analytical samples collected.


Downwind air monitoring results: PID: 0.0 ppm LEL: NORMAL Cyanide Draeger: NON-DETECT

**PARSONS ENGINEERING SCIENCE, INC.
TEST PIT RECORD**

PROJECT NAME: NYSDEC - South Hill Dump
 PROJECT NUMBER: 729396.02000
 WEATHER: Snow, windy, 20s
 DATE/TIME START: March 7, 1997 / 1020
 DATE/TIME FINISH: March 7, 1997 / 1035
 CONTRACTOR: Marcor Environmental
 INSPECTOR: N.A. Smith

TEST PIT ID: TP-23

LOCATION: Upper level, on slope to entrance level.



DEPTH (feet bgs)	FIELD IDENTIFICATION OF MATERIAL	COMMENTS
1	SAND and GRAVEL, bank run, on slope.	
2		
3	FILL - sand, silt, and stone, metal cans and jars.	
4		
5	NATIVE SOIL - SILT and CLAY, gray to north, brown to south.	
6		
7		
8	BEDROCK Trench terminated at 7 feet bgs.	
9		
10		
11		
12		
13		
14		
15		
16		
17		
18		
19		
20		
21		

SUMMARY

Dimensions (LENGTH x WIDTH x DEPTH): 38 feet x 6 feet x 7 feet

No analytical samples collected.


Downwind air monitoring results: PID: 0.0 ppm LEL: NORMAL Cyanide Draeger: NON-DETECT

**PARSONS ENGINEERING SCIENCE, INC.
TEST PIT RECORD**

PROJECT NAME: NYSDEC - South Hill Dump
 PROJECT NUMBER: 729396.02000
 WEATHER: Partly sunny, 30s
 DATE/TIME START: March 7, 1997 / 1320
 DATE/TIME FINISH: March 7, 1997 / 1347
 CONTRACTOR: Marcor Environmental
 INSPECTOR: N.A. Smith

TEST PIT ID: TP-24

LOCATION: Second level, on eastern portion.



DEPTH (feet bgs)	FIELD IDENTIFICATION OF MATERIAL	COMMENTS
1	COVER SOIL & FILL - bagged household trash, bottles, cans.	
2	Household building debris (lumber, plastic sheeting, carpet) on west portion of trench.	
3	Typewriter keyboard overlays, white plastic strips, and several briefcase handles at east end of trench.	
4		
5	Flattened, corroded drum at east end of trench containing brown resin and soil.	Drum was overpacked
6	Fill is predominantly household trash, fabric, tires, white goods.	Drum ID: TP-24-D1
7		Drum PID: 30.2 ppm
8		
9		
10		
11	Hot water heater	
12		
13		
14	SILT and CLAY, gray. 13 ft	
15	BEDROCK, water at interface. Trench terminated at 14 feet bgs. 14 ft	
16		
17		
18		
19		
20		
21		

SUMMARY

Dimensions (LENGTH x WIDTH x DEPTH): 41 feet x 6 feet x 14 feet

Analytical samples collected: TP-24-01 - resin from crushed drum at east end, 4 feet deep.


Downwind air monitoring results: PID: 0.0 ppm LEL: NORMAL Cyanide Draeger: NON-DETECT

**PARSONS ENGINEERING SCIENCE, INC.
TEST PIT RECORD**

PROJECT NAME: NYSDEC - South Hill Dump
 PROJECT NUMBER: 729396.02000
 WEATHER: Partly sunny, 30s
 DATE/TIME START: March 7, 1997 / 1455
 DATE/TIME FINISH: March 7, 1997 / 1520
 CONTRACTOR: Marcor Environmental
 INSPECTOR: N.A. Smith

TEST PIT ID: TP-25

LOCATION: Slope between upper and second levels.



DEPTH (feet bgs)	FIELD IDENTIFICATION OF MATERIAL	COMMENTS
1	COVER SOIL - silt, stone, stumps.	
2		
3		
4		
5		
6	FILL - bagged trash, fabric, wheel housing, typewriter keyboard debris, and white plastic mold brackets.	Fill begins at mid-slope Drum PID: 3 ppm
7	Empty crushed drum at base of slope.	
8	Black netting on lower level.	
9		
10		
11		
12		
13		
14		
15	BEDROCK, water at interface. Trench terminated at 14 feet bgs.	
16		
17		
18		
19		
20		
21		

SUMMARY

Dimensions (LENGTH x WIDTH x DEPTH): 45 feet x 6 feet x 14 feet

No analytical samples collected.


Downwind air monitoring results: PID: 0.0 ppm LEL: NORMAL Cyanide Draeger: NON-DETECT

**PARSONS ENGINEERING SCIENCE, INC.
TEST PIT RECORD**

PROJECT NAME: NYSDEC - South Hill Dump
 PROJECT NUMBER: 729396.02000
 WEATHER: Sunny, 30s
 DATE/TIME START: March 10, 1997 / 1105
 DATE/TIME FINISH: March 10, 1997 / 1130
 CONTRACTOR: Marcor Environmental
 INSPECTOR: N.A. Smith

TEST PIT ID: TP-26

LOCATION: Second level, center portion.



DEPTH (feet bgs)	FIELD IDENTIFICATION OF MATERIAL	COMMENTS
1	FILL - blue tarp, tires, metal plating, keyboard housings, cable, stumps. White-tan resin fragment, 2-3 feet in diameter at west end of trench. East half of trench is bagged household waste, cover soil is black.	Resin PID: 0.0 ppm
2		
3	White plastic brackets and rubber caps near center of trench.	
4	4 ft	
5	NATIVE SOIL - silt and clay	
6		
7		
8	8 ft	
9	BEDROCK	Trench terminated at 8 feet bgs.
10		
11		
12		
13		
14		
15		
16		
17		
18		
19		
20		
21		

SUMMARY

Dimensions (LENGTH x WIDTH x DEPTH): 68 feet x 6 feet x 8 feet

No analytical samples collected.


Downwind air monitoring results: PID: 0.0 ppm LEL: NORMAL Cyanide Draeger: NON-DETECT

**PARSONS ENGINEERING SCIENCE, INC.
TEST PIT RECORD**

PROJECT NAME: NYSDEC - South Hill Dump
 PROJECT NUMBER: 729396.02000
 WEATHER: Sunny, 40s
 DATE/TIME START: March 10, 1997 / 1159
 DATE/TIME FINISH: March 10, 1997 / 1212
 CONTRACTOR: Marcor Environmental
 INSPECTOR: N.A. Smith

TEST PIT ID: TP-27

LOCATION: Slope between upper and second levels.



DEPTH (feet bgs)	FIELD IDENTIFICATION OF MATERIAL	COMMENTS
1	COVER SOIL - silt, stone, stumps, brown and gray layers. 8 ft	
2		
3		
4		
5		
6		
7		
8		
9	FILL - ash and burned cans, brackets, furnace parts, black to rust-colored. 14 ft	
10		
11		
12		
13		
14		
15	NATIVE SOIL - silt and clay 15 ft	
16	Trench terminated at 15 feet bgs.	
17		
18		
19		
20		
21		

SUMMARY

Dimensions (LENGTH x WIDTH x DEPTH): 25 feet x 9 feet x 15 feet

Analytical samples collected: TP-27-01(DUP. ID:TP-27-11) - burned fill from wall of slope 10 feet deep.

Downwind air monitoring results: PID: 0.0 ppm LEL: NORMAL Cyanide Draeger: NON-DETECT

**PARSONS ENGINEERING SCIENCE, INC.
TEST PIT RECORD**

PROJECT NAME: <u>NYSDEC - South Hill Dump</u>		TEST PIT ID: TP-28										
PROJECT NUMBER: <u>729396.02000</u>		LOCATION: <u>Second level, west of center portion.</u>										
WEATHER: <u>Sunny, 40s</u>												
DATE/TIME START: <u>March 10, 1997 / 1435</u>		<table border="1" style="width:100%; border-collapse: collapse;"> <tr> <td style="width:25%; text-align: center;">WEST</td> <td style="width:50%; text-align: center;">CROSS SECTION VIEW</td> <td style="width:25%; text-align: center;">EAST</td> </tr> <tr> <td colspan="3" style="height: 40px;"> APPLIANCES FILL TYPEWRITER KEYS NATIVE SOIL </td> </tr> <tr> <td colspan="3" style="text-align: center;">BEDROCK</td> </tr> </table>		WEST	CROSS SECTION VIEW	EAST	APPLIANCES FILL TYPEWRITER KEYS NATIVE SOIL			BEDROCK		
WEST	CROSS SECTION VIEW			EAST								
APPLIANCES FILL TYPEWRITER KEYS NATIVE SOIL												
BEDROCK												
DATE/TIME FINISH: <u>March 10, 1997 / 1455</u>												
CONTRACTOR: <u>Marcor Environmental</u>												
INSPECTOR: <u>N.A. Smith</u>												

DEPTH (feet bgs)	FIELD IDENTIFICATION OF MATERIAL	COMMENTS
1	FILL - household waste, clothing, bagged trash, tires, partially burned. White goods and auto parts on west end of trench. White plastic brackets with typewriter keys attached on east end of trench.	
2		
3		
4		
5		
6	NATIVE SOIL - silt and clay	
7		
8		
9	BEDROCK Trench terminated at 8 feet bgs.	
10		
11		
12		
13		
14		
15		
16		
17		
18		
19		
20		
21		

SUMMARY	Dimensions (LENGTH x WIDTH x DEPTH): <u>53 feet x 6 feet x 8 feet</u> No analytical samples collected. Downwind air monitoring results: PID: 0.0 ppm LEL: NORMAL Cyanide Draeger: NON-DETECT
----------------	---

**PARSONS ENGINEERING SCIENCE, INC.
TEST PIT RECORD**

PROJECT NAME: NYSDEC - South Hill Dump
 PROJECT NUMBER: 729396.02000
 WEATHER: Cloudy, 30s
 DATE/TIME START: March 11, 1997 / 0900
 DATE/TIME FINISH: March 11, 1997 / 0917
 CONTRACTOR: Marcor Environmental
 INSPECTOR: N.A. Smith

TEST PIT ID: TP-29

LOCATION: Second level, on southern extension.

WEST	CROSS SECTION VIEW	EAST

DEPTH (feet bgs)	FIELD IDENTIFICATION OF MATERIAL	COMMENTS
1	Fill - sand, silt, stone, stumps, metal scrap, bottles, fabric, bagged trash. Scattered white goods along length of trench. Layers of cover soil within fill.	Found on excavated soil pile: Newspaper dated June 14, 1971
2		
3	Typewriter key mold brackets at east end and west of center of trench.	
4		
5		
6		
7		
8		
9		
10	NATIVE SOIL - silt and clay, gray. 9 ft	
11	BEDROCK Trench terminated at 10 feet bgs. 10 ft	
12		
13		
14		
15		
16		
17		
18		
19		
20		
21		

SUMMARY

Dimensions (LENGTH x WIDTH x DEPTH): 48 feet x 5 feet x 10 feet

No analytical samples collected.

Downwind air monitoring results: PID: 0.0 ppm LEL: NORMAL Cyanide Draeger: NON-DETECT

**PARSONS ENGINEERING SCIENCE, INC.
TEST PIT RECORD**


PROJECT NAME: <u>NYSDEC - South Hill Dump</u>		TEST PIT ID: TP-30													
PROJECT NUMBER: <u>729396.02000</u>		LOCATION: <u>Second level, on southern extension.</u>													
WEATHER: <u>Sunny, 30s</u>															
DATE/TIME START: <u>March 11, 1997 / 1005</u>		<table border="1" style="width:100%; border-collapse: collapse;"> <tr> <td style="width:33%; text-align: center;">SOUTH</td> <td style="width:34%; text-align: center;">CROSS SECTION VIEW</td> <td style="width:33%; text-align: center;">NORTH</td> </tr> <tr> <td colspan="3" style="text-align: center;"> </td> </tr> <tr> <td colspan="3" style="text-align: center;"> METAL BANDS BLACK RESIDUE FILL </td> </tr> <tr> <td colspan="3" style="text-align: center;"> BEDROCK NATIVE SOIL </td> </tr> </table>		SOUTH	CROSS SECTION VIEW	NORTH				METAL BANDS BLACK RESIDUE FILL			BEDROCK NATIVE SOIL		
SOUTH	CROSS SECTION VIEW			NORTH											
METAL BANDS BLACK RESIDUE FILL															
BEDROCK NATIVE SOIL															
DATE/TIME FINISH: <u>March 11, 1997 / 1015</u>															
CONTRACTOR: <u>Marcor Environmental</u>															
INSPECTOR: <u>N.A. Smith</u>															

DEPTH (feet bgs)	FIELD IDENTIFICATION OF MATERIAL	COMMENTS
1	FILL - bagged household refuse, tires, metal scrap, jars.	Found on excavated soil pile: Newspaper dated June 14, 1971 Same date as that found in adjacent test pit no. 29
2	Metal banding piled 30 feet from north end of trench.	
3		
4	Black residue on soil, plastic bag, and cardboard stack, pungent odor. 4 ft	
5	NATIVE SOIL - gray silt and clay (till) and weathered bedrock.	Residue PID: 0.0 ppm
6		Fill extends to 6 feet to south
7	7 ft	
8	BEDROCK Trench terminated at 7 feet bgs.	
9		
10		
11		
12		
13		
14		
15		
16		
17		
18		
19		
20		
21		

SUMMARY	Dimensions (LENGTH x WIDTH x DEPTH): 45 feet x 6 feet x 7 feet Samples collected: TP-30-01 - stained area from center of trench 4 feet deep. Downwind air monitoring results: PID: 0.0 ppm LEL: NORMAL Cyanide Draeger: NON-DETECT
----------------	--

**PARSONS ENGINEERING SCIENCE, INC.
TEST PIT RECORD**


PROJECT NAME:	NYSDEC - South Hill Dump	TEST PIT ID: TP-31
PROJECT NUMBER:	729396.02000	LOCATION: Slope between upper and second levels.
WEATHER	Sunny, 30s	
DATE/TIME START:	March 11, 1997 / 1105	
DATE/TIME FINISH:	March 11, 1997 / 1120	
CONTRACTOR:	Marcor Environmental	
INSPECTOR:	N.A. Smith	

DEPTH (feet bgs)	FIELD IDENTIFICATION OF MATERIAL	COMMENTS
1	COVER SOIL - sand, silt, and stone, fill (plastic sheeting).	Trench was dug along steep slope. Depth of layering is estimated as instability of slope prevented access for detailed measurements.
2	2 ft	
3	FILL - ash and burned debris.	
4	3.5 ft	
5	COVER SOIL - sand, silt, and stone, trace fill.	CROSS SECTION VIEW SOUTH NORTH 
6	6 ft	
7	FILL - household debris.	
8	7.5 ft	
9	COVER SOIL - sand, silt, and stone, trace fill.	
10	10.5 ft	
11	FILL - car bumpers and large scrap metal debris.	
12	12 ft	
13	FILL - ash and burned debris.	
14		
15		
16		
17		
18		
19		
20	20 ft	
21	NATIVE SOIL - CLAY, little silt, trace pebbles, gray (TILL). 21 ft	
22	Trench terminated at 21 feet bgs.	

SUMMARY	Dimensions (LENGTH x WIDTH x DEPTH): 17 feet x 10 feet x 21 feet
	No analytical samples collected.
	Downwind air monitoring results: PID: 0.0 ppm LEL: NORMAL Cyanide Draeger: NON-DETECT

**PARSONS ENGINEERING SCIENCE, INC.
TEST PIT RECORD**

PROJECT NAME:	NYSDEC - South Hill Dump	TEST PIT ID: TP-32
PROJECT NUMBER:	729396.02000	LOCATION: Level 2, southwest portion.
WEATHER	Partly sunny, 30s	
DATE/TIME START:	March 11, 1997 / 1345	
DATE/TIME FINISH:	March 11, 1997 / 1423	
CONTRACTOR:	Marcor Environmental	
INSPECTOR:	N.A. Smith	



DEPTH (feet bgs)	FIELD IDENTIFICATION OF MATERIAL	COMMENTS
1	COVER SOIL & FILL - household refuse. Design plans labelled "Pall Trinity Corp." at east end of trench.	
2	Gray-green residue with putty-like consistency at east end of trench. 2 ft	
3	Large metal debris (water heaters, auto and farm machine parts, bedsprings) in western half of trench. Three empty crushed drums found at 15 ft, 32 ft, and 45 ft from east end. 3 ft	PID on each drum: 0.0 ppm
4	NATIVE SOIL - CLAY, little silt, trace pebbles, gray (TILL). 4 ft	
5	Trench terminated at 4 feet bgs.	
6		
7		
8		
9		
10		
11		
12		
13		
14		
15		
16		
17		
18		
19		
20		
21		

SUMMARY

Dimensions (LENGTH x WIDTH x DEPTH): 48 feet x 5 feet x 4 feet

Samples collected: TP-32-01 - gray-green residue from east end of trench, 1 foot deep.


Downwind air monitoring results: PID: 0.0 ppm LEL: NORMAL Cyanide Draeger: NON-DETECT

**PARSONS ENGINEERING SCIENCE, INC.
TEST PIT RECORD**

PROJECT NAME: NYSDEC - South Hill Dump
 PROJECT NUMBER: 729396.02000
 WEATHER: Mostly sunny, 30s
 DATE/TIME START: March 11, 1997 / 1505
 DATE/TIME FINISH: March 11, 1997 / 1600
 CONTRACTOR: Marcor Environmental
 INSPECTOR: N.A. Smith

TEST PIT ID: TP-33

LOCATION: Ridge along access road between Levels 2 and 3.



DEPTH (feet bgs)	FIELD IDENTIFICATION OF MATERIAL	COMMENTS
0	Metallic debris piled above grade, decreasing to south. 0 ft	Drums present on northern portion of trench only.
1	Several crushed drums near surface - most empty, some contain soil or yellow paint residue. 1 ft	
2	NATIVE SOIL - Silt and sand. 4 ft	
3		
4		
5		
6	NATIVE SOIL - CLAY, little silt, trace pebbles, gray (TILL). 6 ft	
7	Trench terminated at 6 feet bgs.	
8		
9		
10		
11		
12		
13		
14		
15		
16		
17		
18		
19		
20		

SUMMARY

Dimensions (LENGTH x WIDTH x DEPTH): 85 feet x 15 feet x 6 feet

No analytical samples collected.

Downwind air monitoring results: PID: 0.0 ppm LEL: NORMAL Cyanide Draeger: NON-DETECT

PARSONS ENGINEERING SCIENCE, INC.
TEST PIT RECORD

PROJECT NAME: NYSDEC - South Hill Dump

PROJECT NUMBER: 729396.02000

WEATHER Mostly sunny, 30s

DATE/TIME START: March 12, 1997 / 1047

DATE/TIME FINISH: March 12, 1997 / 1057

CONTRACTOR: Marcor Environmental

INSPECTOR: N.A. Smith

TEST PIT ID: TP-34

LOCATION: Base of slope between Levels 2 and 3.

WEST

CROSS SECTION VIEW

EAST

SILT, SAND, & STONE

BEDROCK

DEPTH (feet bgs)	FIELD IDENTIFICATION OF MATERIAL	COMMENTS
1	NATIVE SOIL - Silt, sand, and stone, brown-gray (TILL). Wet at 6 feet.	
2		
3		
4		
5		
6		
7		
8		
	8 ft	
9	BEDROCK	Trench terminated at 8 feet bgs.
10		
11		
12		
13		
14		
15		
16		
17		
18		
19		
20		
21		

SUMMARY

Dimensions (LENGTH x WIDTH x DEPTH): 42 feet x 5 feet x 8 feet

No analytical samples collected.


Downwind air monitoring results: PID: 0.0 ppm LEL: NORMAL Cyanide Draeger: NON-DETECT

PARSONS ENGINEERING SCIENCE, INC.
TEST PIT RECORD

PROJECT NAME: NYSDEC - South Hill Dump
 PROJECT NUMBER: 729396.02000
 WEATHER: Mostly sunny, 30s
 DATE/TIME START: March 12, 1997 / 1118
 DATE/TIME FINISH: March 12, 1997 / 1125
 CONTRACTOR: Marcor Environmental
 INSPECTOR: N.A. Smith

TEST PIT ID: TP-35

LOCATION: Base of slope between Levels 2 and 3.



DEPTH (feet bgs)	FIELD IDENTIFICATION OF MATERIAL	COMMENTS
1	TOPSOIL, brown-black. 1 ft	
2	NATIVE SOIL - Silt, sand, and stone, brown-gray (TILL). 4 ft	
3		
4		
5		
5	BEDROCK Trench terminated at 4 feet bgs.	
6		
7		
8		
9		
10		
11		
12		
13		
14		
15		
16		
17		
18		
19		
20		
21		

SUMMARY

Dimensions (LENGTH x WIDTH x DEPTH): 43 feet x 5 feet x 4 feet

No analytical samples collected.


Downwind air monitoring results: PID: 0.0 ppm LEL: NORMAL Cyanide Draeger: NON-DETECT

**PARSONS ENGINEERING SCIENCE, INC.
TEST PIT RECORD**

PROJECT NAME: NYSDEC - South Hill Dump
 PROJECT NUMBER: 729396.02000
 WEATHER: Sunny, 30s
 DATE/TIME START: March 12, 1997 / 1400
 DATE/TIME FINISH: March 12, 1997 / 1425
 CONTRACTOR: Marcor Environmental
 INSPECTOR: N.A. Smith

TEST PIT ID: TP-36

LOCATION: Level 3, west of center.



DEPTH (feet bgs)	FIELD IDENTIFICATION OF MATERIAL	COMMENTS	
+3	Mound on eastern portion of excavation.	Crushed drum PID: 40 ppm Soil below drum PID: 15 ppm	
+2	Bagged trash, bottles, cans, roofing materials, concrete slabs, machinery parts.		
+1	Crushed drum found, empty.		
0	Ground surface of surrounding grade. 0 ft		
1	NATIVE SOIL - Silt, sand, and stone, brown-gray (TILL). 4 ft		
2			
3			
4			
5	Trench terminated at 4 feet bgs.		Soil PID: 96 ppm at isolated portion on west side of trench
6			
7			
8			
9			
10			
11			
12			
13			
14			
15			
16			
17			

SUMMARY

Dimensions (LENGTH x WIDTH x DEPTH): 56 feet x 5-15 feet x 4 feet

Analytical samples collected: TP-36-01 - soil beneath crushed drum on east portion of trench, 2 feet deep.

TP-36-02 - from soil at west end of trench, 3 feet deep.


Downwind air monitoring results: PID: 0.0 ppm LEL: NORMAL Cyanide Draeger: NON-DETECT

**PARSONS ENGINEERING SCIENCE, INC.
TEST PIT RECORD**

PROJECT NAME: NYSDEC - South Hill Dump
 PROJECT NUMBER: 729396.02000
 WEATHER: Cloudy, 30s
 DATE/TIME START: March 12, 1997 / 1515
 DATE/TIME FINISH: March 12, 1997 / 1525
 CONTRACTOR: Marcor Environmental
 INSPECTOR: N.A. Smith

TEST PIT ID: TP-37

LOCATION: Level 3, between drum piles.



DEPTH (feet bgs)	FIELD IDENTIFICATION OF MATERIAL	COMMENTS
0	Fill on surface - metal bands and bedspring. 0 ft	
1	NATIVE SOIL - Silt and fine-medium sand, brown. 1 ft	
2	NATIVE SOIL - Silt, sand, and stone, brown-gray (TILL). 6 ft	
3		
4		
5		
6		
7		
8		
9		
10		
11		
12		
13		
14		
15		
16		
17		
18		
19		
20		

SUMMARY


Dimensions (LENGTH x WIDTH x DEPTH): 43 feet x 5 feet x 6 feet

No analytical samples collected.

Downwind air monitoring results: PID: 0.0 ppm LEL: NORMAL Cyanide Draeger: NON-DETECT

**PARSONS ENGINEERING SCIENCE, INC.
TEST PIT RECORD**

PROJECT NAME:	NYSDEC - South Hill Dump	TEST PIT ID: TP-38
PROJECT NUMBER:	729396.02000	LOCATION: Level 3, drum nest on west end of ridge.
WEATHER	Sunny, 40s	
DATE/TIME START:	March 13, 1997 / 1430	
DATE/TIME FINISH:	March 13, 1997 / 1515	
CONTRACTOR:	Marcor Environmental	
INSPECTOR:	E.A. Felter	



DEPTH (feet bgs)	FIELD IDENTIFICATION OF MATERIAL	COMMENTS
0	Several drums present on ground surface. Most are empty, one drum overpacked. 0 ft	
1	TOPSOIL - Dark gray-black silt, little fine-coarse sand, trace fine-coarse gravel, organic-rich, moist. 1 ft	Drum ID: TP-38-D1 Drum opened 3/20/97.
2	NATIVE SOIL - brown fine -coarse SAND and GRAVEL, little silt, iron-stained, dry. 2 ft	PID: 57 ppm LEL: 1%
3	NATIVE SOIL - gray-brown fine -coarse GRAVEL, little silt, clay, and sand, moist. Fuel odor present approx. 2 feet below grade, soil PID: 15 ppm. Wet at 5 feet.	Contents: Approx. 5 gallons of brown, tan, and black solidified resin.
4		
5		
6		
7		
8		
9		
10		
11	Trench terminated at 10 feet bgs.	
12		
13		
14		
15		
16		
17		
18		
19		
20		


SUMMARY	Dimensions (LENGTH x WIDTH x DEPTH): 18 feet x 13 feet x 10 feet Samples collected: TP-38-01 - soil from 2 feet deep. TP-38-D1- from overpacked drum. Downwind air monitoring results: PID: 0.0 ppm LEL: NORMAL Cyanide Draeger: NON-DETECT
----------------	--

**PARSONS ENGINEERING SCIENCE, INC.
TEST PIT RECORD**

PROJECT NAME: NYSDEC - South Hill Dump
 PROJECT NUMBER: 729396.02000
 WEATHER: Sunny, 40s
 DATE/TIME START: March 17, 1997 / 1035
 DATE/TIME FINISH: March 17, 1997 / 1055
 CONTRACTOR: Marcor Environmental
 INSPECTOR: N.A. Smith

TEST PIT ID: TP-39

LOCATION: Level 3, across ridge.



DEPTH (feet bgs)	FIELD IDENTIFICATION OF MATERIAL	COMMENTS
+3	FILL - Soil and metal debris consisting of: several drum carcasses, bedsprings, auto parts, and metal banding.	
+2		
+1		
0	Ground surface of surrounding grade.	0 ft
1	NATIVE SOIL - brown SILT, SAND, and STONE.	
2		
3		
4		
5		
6		
7		
8		
9		9 ft
10	Trench terminated at 12 feet bgs from top of ridge (9 feet below surrounding grade).	
11		
12		
13		
14		
15		
16		
17		

SUMMARY


Dimensions (LENGTH x WIDTH x DEPTH): 17 feet x 11 feet x 9-12 feet

Analytical samples collected: TP-39-01(DUP. ID:TP-39-11) - soil from beneath empty drums, 1 foot deep.

Downwind air monitoring results: PID: 0.0 ppm LEL: NORMAL Cyanide Draeger: NON-DETECT

**PARSONS ENGINEERING SCIENCE, INC.
TEST PIT RECORD**

PROJECT NAME:	NYSDEC - South Hill Dump	TEST PIT ID: TP-40
PROJECT NUMBER:	729396.02000	LOCATION: Level 3, ridge near drainage swale.
WEATHER	Partly sunny, 40s	
DATE/TIME START:	March 17, 1997 / 1315	
DATE/TIME FINISH:	March 17, 1997 / 1400	
CONTRACTOR:	Marcor Environmental	
INSPECTOR:	N.A. Smith	



DEPTH (feet bgs)	FIELD IDENTIFICATION OF MATERIAL	COMMENTS
1	FILL - Scrap metal, white goods, tires, sheet metal, several empty crushed drums and drum fragments.	All drums empty, PID: 0.0 ppm
2		
3		
4		
5		
6	Stacked tires, appear to have been burned.	
7	Water flowing into trench from north, contains NAPL. 5 ft	
8	NATIVE SOIL - brown fine-coarse SAND, some silt, little gravel, moist.	Excavation terminated when NAPL was encountered. NYSDEC Spill Response Unit contacted for guidance. Area fenced off and sorbent pads were applied. Samples of seep were collected by field team and by spill response contractor. Fluid in trench pumped into tanker truck for proper disposal.
9		
10		
11		
12		
13	Trench terminated at 10 feet bgs at south, 5 feet bgs at seep to north.	
14		
15		
16		
17		
18		
19		

Dimensions (LENGTH x WIDTH x DEPTH): 28 feet x 10 feet x 5-10 feet

Analytical samples collected: TP-40-01 - soil below seep at north portion of trench, 4 feet deep.

TP-40-W - aqueous sample from seep at north end of trench.


TP-40-SEEP - from drainage into swale downstream of TP-40.

Additional aqueous samples collected from trench by Buck Labs for waste disposal characterization.

Downwind air monitoring results: PID: 0.0 ppm LEL: NORMAL Cyanide Draeger: NON-DETECT

**PARSONS ENGINEERING SCIENCE, INC.
TEST PIT RECORD**

PROJECT NAME:	NYSDEC - South Hill Dump	TEST PIT ID: TP-41
PROJECT NUMBER:	729396.02000	LOCATION: Level 3, southeast portion of ridge.
WEATHER	Sunny, 40s	
DATE/TIME START:	March 18, 1997 / 0920	
DATE/TIME FINISH:	March 18, 1997 / 0930	
CONTRACTOR:	Marcor Environmental	
INSPECTOR:	N.A. Smith	



DEPTH (feet bgs)	FIELD IDENTIFICATION OF MATERIAL	COMMENTS
1	FILL - tires, metal bands, and brackets.	
2	Two leaking drums and one empty drum at 1 foot. Contents of leaking drums: moroon-colored solid and metal typewriter pieces.	
3		
4	4 ft	
5	NATIVE SOIL - brown SAND, SILT, AND STONE.	
6		
7	Water at 7 feet. 7 ft	
8	Trench terminated at 7 feet bgs.	
9		
10		
11		
12		
13		
14		
15		
16		
17		
18		
19		
20		
21		


SUMMARY	Dimensions (LENGTH x WIDTH x DEPTH): 28 feet x 11 feet x 7 feet Samples collected: TP-41-01 - composite sample of 2 leaking drums. TP-41-D1 (DUP. ID: TP-41-DR1) - from overpacked drum. Downwind air monitoring results: PID: 0.0 ppm LEL: NORMAL Cyanide Draeger: NON-DETECT
----------------	---

**PARSONS ENGINEERING SCIENCE, INC.
TEST PIT RECORD**

PROJECT NAME: NYSDEC - South Hill Dump
 PROJECT NUMBER: 729396.02000
 WEATHER: Sunny, 40s
 DATE/TIME START: March 18, 1997 / 1127
 DATE/TIME FINISH: March 18, 1997 / 1135
 CONTRACTOR: Marcor Environmental
 INSPECTOR: E.A. Felter

TEST PIT ID: TP-42

LOCATION: Slope between second and third levels.



DEPTH (feet bgs)	FIELD IDENTIFICATION OF MATERIAL	COMMENTS
1	FILL - household trash (mostly plastics), white plastic typewriter key molds, mixed with brown f.-c. sand and silt, dry.	PID reading: 2.5 ppm.
2		
3		
4		
5	Gray-green CLAY, some silt, little f.-c. sand, tr. f.-c. gravel, moist.	
6	Gray-brown COBBLES and SILT, little f.-c. sand and f.-c. gravel, dry to moist (TILL).	
7		
8		
9	Trench terminated at 4 feet bgs at southeast end, 8 feet bgs at northwest end.	
10		
11		
12		
13		
14		
15		
16		
17		
18		
19		
20		
21		




SUMMARY

Dimensions (LENGTH x WIDTH x DEPTH): 15 feet x 5 feet x 4-8 feet

No analytical samples collected.

Downwind air monitoring results: PID: 0.0 ppm LEL: NORMAL Cyanide Draeger: NON-DETECT

**PARSONS ENGINEERING SCIENCE, INC.
TEST PIT RECORD**


PROJECT NAME: <u>NYSDEC - South Hill Dump</u>		TEST PIT ID: TP-43										
PROJECT NUMBER: <u>729396.02000</u>		LOCATION: <u>Level 3, southeast corner.</u>										
WEATHER: <u>Sunny, 40s</u>												
DATE/TIME START: <u>March 18, 1997 / 1400</u>		<table border="1" style="width:100%; border-collapse: collapse;"> <tr> <td style="width:33%; text-align: center;">SOUTHWEST</td> <td style="width:34%; text-align: center;">CROSS SECTION VIEW</td> <td style="width:33%; text-align: center;">NORTHEAST</td> </tr> <tr> <td style="text-align: center;">FILL</td> <td align="center">  </td> <td style="text-align: center;">SAND, SILT, STONE</td> </tr> <tr> <td colspan="3" style="text-align: center;">GRAY TILL</td> </tr> </table>		SOUTHWEST	CROSS SECTION VIEW	NORTHEAST	FILL		SAND, SILT, STONE	GRAY TILL		
SOUTHWEST	CROSS SECTION VIEW			NORTHEAST								
FILL				SAND, SILT, STONE								
GRAY TILL												
DATE/TIME FINISH: <u>March 18, 1997 / 1410</u>												
CONTRACTOR: <u>Marcor Environmental</u>												
INSPECTOR: <u>N.A. Smith</u>												

DEPTH (feet bgs)	FIELD IDENTIFICATION OF MATERIAL	COMMENTS
1	FILL - household trash, food, cleaning containers, fabric, tires, typewriter key molds, newspaper dated October 11, 1971. Replaced by brown SAND, SILT, and STONE to northeast.	
2		
3		
4		
5		
6		
7	Gray SAND, SILT, and CLAY (TILL). Encountered at shallower depth at north-east end of trench. 6 ft	
8	Trench terminated at 7 feet bgs. 7 ft	
9		
10		
11		
12		
13		
14		
15		
16		
17		
18		
19		
20		
21		

SUMMARY	Dimensions (LENGTH x WIDTH x DEPTH): <u>33 feet x 5 feet x 7 feet</u>		
	Samples collected: <u>TP-43-01 - gray till, 6 feet deep.</u>		
	Downwind air monitoring results: PID: <u>0.0 ppm</u> LEL: <u>NORMAL</u> Cyanide Draeger: <u>NON-DETECT</u>		

**PARSONS ENGINEERING SCIENCE, INC.
TEST PIT RECORD**

PROJECT NAME:	NYSDEC - South Hill Dump	TEST PIT ID: TP-44
PROJECT NUMBER:	729396.02000	LOCATION: Level 3, near iron-stained seep.
WEATHER	Sunny, 40s	
DATE/TIME START:	March 18, 1997 / 1520	
DATE/TIME FINISH:	March 18, 1997 / 1528	
CONTRACTOR:	Marcor Environmental	
INSPECTOR:	N.A. Smith	



DEPTH (feet bgs)	FIELD IDENTIFICATION OF MATERIAL	COMMENTS
1	FILL - bagged household trash. Thin cover on southwest end of trench. 1 ft	
2	Brown SAND, SILT, and STONE. Replaced by gray CLAY near southwest end of trench.	
3		
4		
5		
6		
7		
8	Trench terminated at 7 feet bgs.	
9		
10		
11		
12		
13		
14		
15		
16		
17		
18		
19		
20		
21		

SUMMARY	Dimensions (LENGTH x WIDTH x DEPTH): 18 feet x 8 feet x 7 feet		
	No analytical samples collected.		
	Downwind air monitoring results:	PID: 0.0 ppm	LEL: NORMAL Cyanide Draeger: NON-DETECT

**PARSONS ENGINEERING SCIENCE, INC.
TEST PIT RECORD**


PROJECT NAME: <u>NYSDEC - South Hill Dump</u>		TEST PIT ID: <u>TP-45</u>	
PROJECT NUMBER: <u>729396.02000</u>		LOCATION: <u>Level 3, east end of ridge.</u>	
WEATHER: <u>Sunny, 20s</u>			
DATE/TIME START: <u>March 19, 1997 / 0910</u>	WEST CROSS SECTION VIEW EAST		
DATE/TIME FINISH: <u>March 19, 1997 / 0945</u>			
CONTRACTOR: <u>Marcor Environmental</u>			
INSPECTOR: <u>E.A. Felter</u>	NO SUBSURFACE EXCAVATION		

DEPTH (feet bgs)	FIELD IDENTIFICATION OF MATERIAL	COMMENTS
+3	Four drums with contents encountered at surface: D1: half-full, oil-like contents, PID reading: 0 ppm. D2: one-third-full, oil-like contents, PID reading: 0 ppm. D3: less than one-quarter-full, oil-like contents, PID reading: 0 ppm. D4: contains ash, PID reading: 0 ppm.	D1, D2, and D3 overpacked. D1 and D2 sampled 3/20/97. Due to insufficient quantity, D3 could not be sampled.
+2		
+1		
0		
0	Seven empty drums encountered at surface. Two rusted through. Mixed metal debris exposed at surface. 0 ft	
1	No subsurface excavation.	
2		
3		
4		
5		
6		
7		
8		
9		
10		
11		
12		
13		
14		
15		
16		
17		

SUMMARY	Dimensions (LENGTH x WIDTH x DEPTH): <u>17 feet x 10 feet x 0 feet (drums on surface)</u>		
	Samples collected: <u>TP-45-D1 - from overpacked drum.</u>		
	<u>TP-45-D2 - from overpacked drum.</u>		
	Downwind air monitoring results: PID: <u>0.0 ppm</u> LEL: <u>NORMAL</u> Cyanide Draeger: <u>NON-DETECT</u>		

**PARSONS ENGINEERING SCIENCE, INC.
TEST PIT RECORD**

PROJECT NAME:	NYSDEC - South Hill Dump	TEST PIT ID: TP-46
PROJECT NUMBER:	729396.02000	LOCATION: Level 3, north of ridge.
WEATHER	Sunny, 20s	
DATE/TIME START:	March 19, 1997 / 1022	
DATE/TIME FINISH:	March 19, 1997 / 1030	
CONTRACTOR:	Marcor Environmental	
INSPECTOR:	E.A. Felter	



DEPTH (feet bgs)	FIELD IDENTIFICATION OF MATERIAL	COMMENTS
1	FILL - Mixture of brown silt, sand, and gravel; roots and organic material; and trash: plastic, cans, tires, one empty crushed drum, and metal parts.	Drum PID reading: 2 ppm.
2	Gray silty CLAY, little f.-c.sand, tr. f. gravel, moist (absent on south end). 1.5 ft	
3	Brown f.-c. SAND, some silt, tr. f.-c. gravel, dry. 2 ft	
4	Trench terminated at 4 feet bgs. 4 ft	
5	Gray-brown SILT and COBBLES, little f.-c. sand, dry (TILL).	
6		
7		
8		
9		
10		
11		
12		
13		
14		
15		
16		
17		
18		
19		
20		
21		

SUMMARY

Dimensions (LENGTH x WIDTH x DEPTH): 35 feet x 4 feet x 4 feet

Samples collected: TP-46-01 - gray silty clay at north end of trench, 2 feet deep.

Downwind air monitoring results: PID: 0.0 ppm LEL: NORMAL Cyanide Draeger: NON-DETECT

**PARSONS ENGINEERING SCIENCE, INC.
TEST PIT RECORD**

PROJECT NAME:	NYSDEC - South Hill Dump	TEST PIT ID: TP-47
PROJECT NUMBER:	729396.02000	LOCATION: Level 3, east of ridge.
WEATHER	Sunny, 30s	
DATE/TIME START:	March 19, 1997 / 1053	
DATE/TIME FINISH:	March 19, 1997 / 1058	
CONTRACTOR:	Marcor Environmental	
INSPECTOR:	E.A. Felter	

DEPTH (feet bgs)	FIELD IDENTIFICATION OF MATERIAL	COMMENTS
1	Reddish (stain?) f.-m. SAND, some-little silt, tr. f. gravel, dry to moist. 1 ft	
2	Gray, f.-c. SAND and SILT, little f.-c. gravel, dry to moist.	
3		
4	Trench terminated at 4 feet bgs. 4 ft	
5	Gray-brown SILT and COBBLES, little f.-c. sand, dry to moist (TILL).	
6		
7		
8		
9		
10		
11		
12		
13		
14		
15		
16		
17		
18		
19		
20		
21		

SUMMARY	Dimensions (LENGTH x WIDTH x DEPTH): 29 feet x 4 feet x 4 feet No analytical samples collected. Downwind air monitoring results: PID: 0.0 ppm LEL: NORMAL Cyanide Draeger: NON-DETECT
----------------	---

**PARSONS ENGINEERING SCIENCE, INC.
TEST PIT RECORD**

PROJECT NAME: <u>NYSDEC - South Hill Dump</u>		TEST PIT ID: TP-48													
PROJECT NUMBER: <u>729396.02000</u>		LOCATION: <u>Level 3, north of ridge near TP-40.</u>													
WEATHER: <u>Sunny, 40s</u>															
DATE/TIME START: <u>March 19, 1997 / 1427</u>		<table border="1" style="width:100%; border-collapse: collapse;"> <tr> <td style="width:25%;">SOUTH</td> <td style="width:50%;">CROSS SECTION VIEW</td> <td style="width:25%;">NORTH</td> </tr> <tr> <td colspan="3" style="text-align:center;">FILL</td> </tr> <tr> <td colspan="3" style="height: 40px;"></td> </tr> <tr> <td style="text-align:center;">SAND</td> <td></td> <td style="text-align:center;">WET</td> </tr> </table>		SOUTH	CROSS SECTION VIEW	NORTH	FILL						SAND		WET
SOUTH	CROSS SECTION VIEW			NORTH											
FILL															
SAND		WET													
DATE/TIME FINISH: <u>March 19, 1997 / 1436</u>															
CONTRACTOR: <u>Marcor Environmental</u>															
INSPECTOR: <u>E.A. Felter</u>															

DEPTH (feet bgs)	FIELD IDENTIFICATION OF MATERIAL	COMMENTS
1	FILL - black to dark brown, occasionally red-stained, organic-rich topsoil (?), scattered trash, including two drum lids. 1 ft	
2	Brown f.-c. silty SAND, little f.-c. gravel, tr. cobbles, moist to wet. Water entered north end of trench between 3 to 5 feet.	
3		
4		
5		
6	Trench terminated at 5 feet bgs.	
7		
8		
9		
10		
11		
12		
13		
14		
15		
16		
17		
18		
19		
20		
21		

SUMMARY	Dimensions (LENGTH x WIDTH x DEPTH): <u>48 feet x 4 feet x 5 feet</u> No analytical samples collected. Downwind air monitoring results: PID: 0.0 ppm LEL: NORMAL Cyanide Draeger: NON-DETECT
----------------	---

**PARSONS ENGINEERING SCIENCE, INC.
TEST PIT RECORD**

PROJECT NAME: <u>NYSDEC - South Hill Dump</u>		TEST PIT ID: TP-49													
PROJECT NUMBER: <u>729396.02000</u>		LOCATION: <u>Level 3, north of ridge near TP-40.</u>													
WEATHER: <u>Sunny, 40s</u>															
DATE/TIME START: <u>March 19, 1997 / 1504</u>		<table border="1" style="width:100%; border-collapse: collapse;"> <tr> <td style="width:25%; text-align: center;">SOUTH</td> <td style="width:50%; text-align: center;">CROSS SECTION VIEW</td> <td style="width:25%; text-align: center;">NORTH</td> </tr> <tr> <td colspan="3" style="text-align: center;">FILL</td> </tr> <tr> <td style="text-align: center;"> </td> <td></td> <td style="text-align: center;"> </td> </tr> <tr> <td style="text-align: center;">TIRES</td> <td style="text-align: center;">SAND</td> <td style="text-align: center;">TIRES</td> </tr> </table>		SOUTH	CROSS SECTION VIEW	NORTH	FILL						TIRES	SAND	TIRES
SOUTH	CROSS SECTION VIEW			NORTH											
FILL															
TIRES	SAND	TIRES													
DATE/TIME FINISH: <u>March 19, 1997 / 1509</u>															
CONTRACTOR: <u>Marcor Environmental</u>															
INSPECTOR: <u>E.A. Felter</u>															

DEPTH (feet bgs)	FIELD IDENTIFICATION OF MATERIAL	COMMENTS
1	FILL - Black and red-stained organics and rusted metal debris.	
2	1.5 ft	
3	FILL - Mixture of brown-gray silty, f.-c. SAND, little f.-c. gravel, tr. cobbles; and tires.	
4	Water entered trench at 3.5 feet.	
5		
6	5.5 ft	
7	Trench terminated at 5.5 feet bgs.	
8		
9		
10		
11		
12		
13		
14		
15		
16		
17		
18		
19		
20		
21		

SUMMARY	Dimensions (LENGTH x WIDTH x DEPTH): <u>18 feet x 4 feet x 5.5 feet</u> No analytical samples collected. Downwind air monitoring results: PID: <u>0.0 ppm</u> LEL: <u>NORMAL</u> Cyanide Draeger: <u>NON-DETECT</u>
----------------	---

**PARSONS ENGINEERING SCIENCE, INC.
TEST PIT RECORD**

PROJECT NAME: NYSDEC - South Hill Dump
 PROJECT NUMBER: 729396.02000
 WEATHER: Sunny, 40s
 DATE/TIME START: March 19, 1997 / 1518
 DATE/TIME FINISH: March 19, 1997 / 1524
 CONTRACTOR: Marcor Environmental
 INSPECTOR: E.A. Felter

TEST PIT ID: TP-50

LOCATION: Level 3, ridge near TP-40.

WEST CROSS SECTION VIEW EAST

TIRES

TIRES

DEPTH (feet bgs)	FIELD IDENTIFICATION OF MATERIAL	COMMENTS
1	FILL - tires, some apparently burned. Water and oil entered trench.	Oil recovered with pads.
2		
3		
4		
5		
6	Trench terminated at 5 feet bgs.	
7		
8		
9		
10		
11		
12		
13		
14		
15		
16		
17		
18		
19		
20		
21		

5 ft


SUMMARY

Dimensions (LENGTH x WIDTH x DEPTH): 10 feet x 4 feet x 5 feet

No analytical samples collected.


Downwind air monitoring results: PID: 0.0 ppm LEL: NORMAL Cyanide Draeger: NON-DETECT

WELL BORING LOGS

PARSONS ENGINEERING SCIENCE, INC. DRILLING RECORD						Sheet <u>1</u> of <u>2</u>
Contractor: <u>SJB Services</u> Driller: <u>Dale Matthies</u> Inspector: <u>N. Smith / S. Dillman</u> Rig Type: <u>CME-550</u>						BORING/ WELL NO. MW-1B Location Description: <u>North of South Hill</u> <u>Road in tree cluster across road from site.</u> Upgradient well location.
GROUNDWATER OBSERVATIONS Water Level: _____ Date: _____ Time: _____ Meas. From: _____						Location Plan 
Weather: <u>Variable - 20 to 40 degrees, sun, wind, snow</u> Date/Time Start: <u>March 26, 1997 / 0810</u> Date/Time Finish: <u>April 10, 1997 / 1218</u>						
Sample Depth	Sample I.D.	SPT / RQD	% Rec.	PID (ppm)	FIELD IDENTIFICATION OF MATERIAL	COMMENTS
+2						
+1						
0		SS				
	A	1	25%	0.0	SILT, little clay, brown, dry.	
1		1				
		2				
2		3				
	B	4	50%	0.0	some siltstone fragments	
3		7				
		10				
4		23				
	C	5	40%	0.0	SILT, some siltstone fragments, brown-gray, dry.	
5		11				
		19				
6		40				
	D	20	35%	0.1	stiff	
7		50/0.5'				
		A				
8		A				
	E	15	70%	0.0	SILT, little clay and weathered shale, brown, wet.	
9		27				
		50/0.4'				
10		A				
	F	42	70%	0.0	CLAY and weathered SHALE, little silt, gray, wet.	
11		30				
		23				
12		50/0.4'				
	G	19	25%	0.0	damp	
13		50/0.3'				
		A				
14		A				
	H	19	50%	0.0	CLAY and weathered SHALE, gray, wet.	
15		14				
		17				
16		38				
	I	29	40%	0.0		
17		50/0.3'				
		A				
18		A				
	J	50/0.3'	0%	N/A	SHALE, gray, competent.	
SAMPLING METHOD SS = SPLIT SPOON A = AUGER CUTTINGS C = CORED						COMMENTS: Analytical samples collected from 2-4 feet and from 6-10 feet bgs. _____ _____ _____

PARSONS ENGINEERING SCIENCE, INC. DRILLING RECORD					Sheet <u>2</u> of <u>2</u>	
Contractor: SJB Services Driller: Dale Matthies Inspector: N. Smith / S. Dillman Rig Type: CME-550					BORING/ WELL NO. MW-1B Location Description: North of South Hill Road in tree cluster across road from site. Upgradient well location.	
PROJECT NAME: NYSDEC - South Hill Dump PROJECT NUMBE 729396.02000					Location Plan 	
GROUNDWATER OBSERVATIONS Water Level: _____ Date: _____ Time: _____ Meas. From: _____ Weather: Variable - 20 to 40 degrees, sun, wind, snow Date/Time Start: March 26, 1997 / 0810 Date/Time Finish: April 10, 1997 / 1218						
Sample Depth	Sample I.D.	SPT / RQD	% Rec.	PID (ppm)	FIELD IDENTIFICATION OF MATERIAL	COMMENTS
18		C			SHALE, gray, competent. Vertical fracture from 18.5 to 19.8 feet bgs. Drilling breaks at 18.9, 19.1, and 19.5 feet bgs.	MW-1B outer casing set to 20 feet bgs Details on Well Construction Log
	1-1	73	92%			
19		C				
		C				
20		C			SHALE, some weathered, gray. Core recovery mostly gravel-sized rubble with some 3-5" pieces.	MW-1B screen set 25 to 35 feet bgs Details on Well Construction Log
	1-2	LOW				
21		C				
		C				
22		C				
		C				
23		C				
		C				
24		C				
		C				
25		C				
		C				
26		C			SHALE, gray, calcareous, fossiliferous, some angular porosity. Crinoid layer from 26.5-27 feet bgs. Bedding-plane fractures at 27.4 and 28.4 feet bgs.	MW-1B screen set 25 to 35 feet bgs Details on Well Construction Log
	1-3	35	100%			
27		C				
		C				
28		C				
		C				
29		C				
		C				
30		C				
	1-4	49	100%			
31		C			SHALE, gray, few fossils. Vertical fracture at 31.6 feet bgs. Bedding-plane fractures at 30.9, 31.1, 31.3, 31.4, 32.8, 32.9, 33.1, and 34.0 feet bgs.	MW-1B screen set 25 to 35 feet bgs Details on Well Construction Log
		C				
32		C				
		C				
33		C				
		C				
34		C				
		C				
35		C				
36					Boring terminated at 35 feet bgs.	
37						
38						
SAMPLING METHOD SS = SPLIT SPOON A = AUGER CUTTINGS C = CORED					COMMENTS: Analytical samples collected from 2-4 feet and from 6-10 feet bgs.	

9/11/97


Contractor <u>SJB Services</u> Driller: <u>Dale Matthies</u> Inspector: <u>N. Smith / C. Torell</u> Rig Type: <u>CME-550</u>					PARSONS ENGINEERING SCIENCE, INC. DRILLING RECORD		BORING/ WELL NO. <u>Sheet 2 of 3</u> <u>MW-2S/B</u>
GROUNDWATER OBSERVATIONS					PROJECT NAME: <u>NYSDEC - South Hill Dump</u> PROJECT NUMBE <u>729396.02000</u>		Location Description <u>West of edge of fill Level 3, southwest of stacked resin drums.</u>
Water Level _____ Date _____ Time _____ Meas. From _____					Weather: <u>Variable - 30 to 60 degrees, sun, wind</u> Date/Time Start: <u>March 27, 1997 / 1302</u> Date/Time Finish: <u>April 7, 1997 / 1630</u>		Location Plan 
Sample Depth	Sample I.D.	SPT / RQD	% Rec.	PID (ppm)	FIELD IDENTIFICATION OF MATERIAL		COMMENTS
19	J	15	25%	69.4	CLAY, some shale fragments, brown, loose, wet.		
		19					
20		23					
	K	19	30%	150			
21		12			little-some shale fragments		
		29					
22		38					
	L	8	45%	54.7			
23		10			CLAY, some silt, little fine gravel and shale fragments, brown, soft, wet to 22.3 feet bgs.		
		12					
24		25					
	M	6	65%	32.2			
25		16			CLAY, some shale fragments, brown, wet.		26.5 feet
		17					
26		18					
	N	10	40%	104			
27		50/0.4'			SHALE fragments, gray, wet.		
		A					
28		A					
	O	50/0.2'	10%	105			
29		A			SHALE fragments, trace clay, partially weathered, gray, wet.		29.3 feet
		A					
30	2-1	78	100%				
		C					
31		C			SHALE, gray, trace fossils, competent. Several horizontal-angular drilling breaks. Horizontal iron-stained fractures at 30, 30.5, and 31 feet bgs.		
		C					
32	2-2	64	98%				
		C					
33		C			SHALE, gray. Several drilling breaks. Iron-stained fractures at 31.8-32.1, 32.2-32.5, and 36.2-36.4 feet bgs.		MW-2B casing set to 31.5 feet bgs Details on Well Construction Log
		C					
34		C					
		C					
35		C					
		C					
36		C					
		C					
37		C					
		C					
38		C					
		C					
39		C					
		C					

SAMPLING METHOD
 SS = SPLIT SPOON
 A = AUGER CUTTINGS
 C = CORED


COMMENTS:
Analytical samples collected from 2-4 feet, 10-14 feet, and 20-28 feet bgs.

Contractor <u>SJB Services</u> Driller: <u>Dale Matthies</u> Inspector: <u>N. Smith / C. Torell</u> Rig Type: <u>CME-550</u>						PARSONS ENGINEERING SCIENCE, INC. DRILLING RECORD						BORING/ WELL NO. <u>Sheet 3 of 3</u> <u>MW-2S/B</u> Location Description <u>West of edge of</u> <u>fill Level 3, southwest of stacked resin</u> <u>drums.</u>					
GROUNDWATER OBSERVATIONS						PROJECT NAME: <u>NYSDEC - South Hill Dump</u> PROJECT NUMBE <u>729396.02000</u>						Location Plan 					
Water Level Date Time Meas. From						Weather: <u>Variable - 30 to 60 degrees, sun, wind</u> Date/Time Start: <u>March 27, 1997 / 1302</u> Date/Time Finish: <u>April 7, 1997 / 1630</u>						COMMENTS MW-2B open from 31.5 to 41.5 feet bgs Details on Well Construction Log					
FIELD IDENTIFICATION OF MATERIAL						41.5 feet Boring terminated at 41.5 feet bgs.											
Sample Depth	Sample I.D.	SPT / RQD	% Rec.	PID (ppm)													
40	2-2	64	98%		SHALE, gray. Several drilling breaks.												
		C															
41		C															
		C															
42																	
43																	
44																	
45																	
46																	
47																	
48																	
49																	
50																	
51																	
52																	
53																	
54																	
55																	
56																	
57																	
58																	
59																	
60																	
SAMPLING METHOD SS = SPLIT SPOON A = AUGER CUTTINGS C = CORED					COMMENTS: <u>Analytical samples collected from 2-4 feet, 10-14 feet, and 20-28 feet bgs.</u>												

Contractor: SJB Services Driller: Dale Matthies Inspector: N. Smith / S. Dillman Rig Type: CME-550					PARSONS ENGINEERING SCIENCE, INC. DRILLING RECORD		BORING/ WELL NO. MW-3B Sheet 1 of 2
GROUNDWATER OBSERVATIONS					PROJECT NAME: NYSDEC - South Hill Dump PROJECT NUMBE 729396.02000		Location Description Along drainage stream east of metallic surficial fill area.
Water Level: Date: Time: Meas. From:					Weather: Variable - 30 to 50 degrees, sun, wind, snow Date/Time Start: April 3, 1997 / 0947 Date/Time Finish: April 9, 1997 / 1155		Location Plan 
Sample Depth	Sample I.D.	SPT / RQD	% Rec.	PID (ppm)	FIELD IDENTIFICATION OF MATERIAL		COMMENTS
+2							
+1							
0		SS			0 feet		
	A	1	30%	20.9	SILT, trace clay, roots, and shale, brown, soft, damp.		
1		3					
		7					
2		9					
	B	5	25%	21.9	SILT, brown, some clay, gray, trace fine gravel, damp.		
3		7					
		5					
4		20					
	C	15	50%	26.3	SILT, some clay, little fine-medium gravel, brown, wet.		
5		4					
		4					
6		4					
	D	1	38%	15.9			
7		2					
		3					
8		1					
	E	1	65%	22.7			
9		2					
		5			CLAY, some silt and rock fragments, brown, moist-wet.		
10		10			10.0 feet		
	F	50/0.3'	10%	23.7	SHALE fragments, dark gray, dry (sampling spoon is wet).		
11		A					
		A					
12		A					
		A					
13	G	50/0.1'	3%	22.1	CLAY and SHALE fragments, gray, wet.		
	3-1	86	86%	0.0	12.8 feet		
14		C			SHALE, gray, competent, scattered fossils, several drilling breaks.		
		C			Vertical fracture from 14.5 to 15.25 feet bgs (mechanical).		
15		C			Horizontal clay-filled and iron-stained fractures at 13.7, 14.2-14.4, and 14.8-15.0 feet bgs.		
		C					
16		C					
	3-2	94	100%		SHALE, gray, competent, some fossils.		
17		C			Vertical fracture from 21.0 to 21.4 feet bgs.		
		C			Horizontal iron-stained fractures at 19.0-19.1 and 25.5-26.1 feet bgs.		
18		C					
		C					
SAMPLING METHOD SS = SPLIT SPOON A = AUGER CUTTINGS C = CORED					COMMENTS: Analytical samples collected from 2-8 feet bgs.		

Contractor: SJB Services Driller: Dale Matthies Inspector: N. Smith / S. Dillman Rig Type: CME-550					PARSONS ENGINEERING SCIENCE, INC. DRILLING RECORD		BORING/ Sheet <u>2</u> of <u>2</u> WELL NO. MW-3B		
					PROJECT NAME: NYSDEC - South Hill Dump PROJECT NUMBE 729396.02000		Location Description Along drainage stream east of metallic surficial fill area.		
GROUNDWATER OBSERVATIONS					Weather: Variable - 30 to 50 degrees, sun, wind, snow Date/Time Start: April 3, 1997 / 0947 Date/Time Finish: April 9, 1997 / 1155		Location Plan 		
Water Level Date Time Meas. From									
Sample Depth	Sample I.D.	SPT / RQD	% Rec.	PID (ppm)	FIELD IDENTIFICATION OF MATERIAL				COMMENTS
19	3-2	94	100%		SHALE, gray, competent, some fossils. Vertical fracture from 21.0 to 21.4 feet bgs. Horizontal iron-stained fractures at 19.0-19.1 and 25.5-26.1 feet bgs.				MW-3B open from 16 to 26 feet bgs Details on Well Construction Log
20		C							
21		C							
22		C							
23		C							
24		C							
25		C							
26		C							
27									
28									
29					Boring terminated at 26.1 feet bgs.				
30									
31									
32									
33									
34									
35									
36									
37									
38									
39									
SAMPLING METHOD SS = SPLIT SPOON A = AUGER CUTTINGS C = CORED					COMMENTS: Analytical samples collected from 2-8 feet bgs.				

Contractor SJB Services Driller: Dale Matthies Inspector: N. Smith / C. Torell Rig Type: CME-550					PARSONS ENGINEERING SCIENCE, INC. DRILLING RECORD		BORING/ WELL NO. Sheet <u>1</u> of <u>3</u> MW-4B	
					PROJECT NAME: NYSDEC - South Hill Dump PROJECT NUMBE 729396.02000		Location Description At top of ravine, south of site.	
GROUNDWATER OBSERVATIONS					Weather: Variable - 20 to 40 degrees, sun, clouds, wind Date/Time Start: March 31, 1997 / 1325 Date/Time Finish: April 8, 1997 / 1510		Location Plan 	
Water Level Date Time Meas. From								
Sample Depth	Sample LD.	SPT / RQD	% Rec.	PID (ppm)	FIELD IDENTIFICATION OF MATERIAL			COMMENTS
+2								
+1								
0		SS			0 feet			MW-4S screen set 6 to 16 feet bgs Details on Well Construction Log
	A	2	40%	0.0	SILT, little clay, trace roots and rock fragments, brown, moist.			
1		2						
		3						
2		20						
	B	12	35%	0.0				
3		10						
		21						
4		36						
	C	6	50%	0.0				
5		5						
		14						
6		8						
	D	3	75%	0.0				
7		4						
		5						
8		4						
	E	6	45%	0.0				
9		8						
		9						
10		14						
	F	6	40%	0.0				trace shale, moist
11		10						
		16						
12		49						
	G	14	30%	0.0				SILT, some clay, little pebbles, brown, firm, moist, wet around pebbles.
13		19						
		18						
14		16						
	H	7	40%	0.0				
15		8						
		7						
16		25						
	I	31	25%	0.0				
17		17						
		26						
18		30						
	J	11	35%	0.0				
SAMPLING METHOD SS = SPLIT SPOON A = AUGER CUTTINGS C = CORED					COMMENTS: Analytical samples collected from 4-6 feet and 16-20 feet bgs.			

Contractor <u>SJB Services</u> Driller: <u>Dale Matthies</u> Inspector: <u>N. Smith / C. Torell</u> Rig Type: <u>CME-550</u>					PARSONS ENGINEERING SCIENCE, INC. DRILLING RECORD					BORING/ WELL NO. <u>Sheet 2 of 3</u> <u>MW-4B</u>		
					PROJECT NAME: <u>NYSDEC - South Hill Dump</u> PROJECT NUMBER: <u>729396.02000</u>					Location Description <u>At top of ravine,</u> <u>south of site.</u>		
GROUNDWATER OBSERVATIONS					Weather: <u>Variable - 20 to 40 degrees, sun, clouds, wind</u> Date/Time Start: <u>March 31, 1997 / 1325</u> Date/Time Finish: <u>April 8, 1997 / 1510</u>					Location Plan 		
Water Level					FIELD IDENTIFICATION OF MATERIAL						COMMENTS	
Date												
Time					SILT, some clay, little pebbles, brown, firm, moist, wet around pebbles.						20.2 feet	
Meas. From												
Sample Depth	Sample I.D.	SPT / RQD	% Rec.	PID (ppm)	SHALE fragments, little till, moist.						20.2 feet	
19		22										
		50/0.4'			SHALE fragments, dry.						33.2 feet	
20		A										
	K	50/0.4'	20%	0.0	SHALE fragments, fossiliferous, not competent, fragments <1/2" to 1-1/2" diameter.						33.2 feet	
21		A										
		A			CLAY layer 26-26.2 feet bgs.						33.2 feet	
22		A										
	L	50/0.3'	10%	0.0	SHALE fragments, gray, not competent, fragments approx. 2" diameter.						33.2 feet	
23		A										
		A			Angular fracture from at 27 feet bgs.						33.2 feet	
24		A										
		A			CLAY and GRAVEL layer, gray, 27.5-27.7 feet bgs.						33.2 feet	
25		C										
	4-1	0	67%		SAND, fine-medium, trace fine-medium gravel, gray, compact, wet.						33.2 feet	
26		C										
		C			CLAY, little shale fragments, gray, stiff, wet.						33.2 feet	
27	4-2	22	43%									
		C			CLAY and SHALE fragments, gray, wet.						33.2 feet	
28		C										
		C			SHALE, gray, competent, scattered fossils, several drilling breaks.						33.2 feet	
29		C										
		C			Angular fracture from 34 to 34.2 feet bgs.						33.2 feet	
30		SS										
	P	6	45%	0.0	Horizontal clay-filled fractures at 34.9-35.1 and 35.7 feet bgs.						33.2 feet	
31		46										
		50/0.4'			SHALE, gray, competent, some fossils.						33.2 feet	
32		A										
	Q	50/0.4'	10%	0.0	Fractures at 38.8, 39-39.3, 39.6 feet bgs.						33.2 feet	
33		A										
	4-3	88	97%	0.0	Details on Well Construction Log						33.2 feet	
34		C										
		C			Details on Well Construction Log						33.2 feet	
35		C										
		C			Details on Well Construction Log						33.2 feet	
36		C										
	4-4	53	96%		Details on Well Construction Log						33.2 feet	
37		C										
		C			Details on Well Construction Log						33.2 feet	
38		C										
		C			Details on Well Construction Log						33.2 feet	
39		C										
		C			Details on Well Construction Log						33.2 feet	
		C										

SAMPLING METHOD

SS = SPLIT SPOON

A = AUGER CUTTINGS

C = CORED

COMMENTS:

Analytical samples collected from 4-6 feet and 16-20 feet bgs.

8/11/97

WELL CONSTRUCTION DIAGRAMS

OVERBURDEN MONITORING WELL CONSTRUCTION LOG

WELL NO.: MW-1S
 PROJ. NO.: 729396.02000
 INSPECTORS: N.A. SMITH
 DATE START: MARCH 26, 1997
 AREA GEOLOGY DESCRIBED ON BORING LOG MW-1

FACILITY/SITE NAME: SOUTH HILL DUMP
 CLIENT: NYSDEC
 DRILLING CONTACTOR: SJB SERVICES, INC.
 DATE END: MARCH 27, 1997

Elevation: 1670.85 feet (rim below PVC)



Height:

Elevation: 1670.95 feet

Height:

GS Elevation: 1668.1 feet

Depth BGS



PROTECTIVE CASING

Material: STEEL
 Diameter: 4 INCHES
 Depth BGS: 2 FEET
 Water Tight Seal: YES
 Flushmount: NO
 Weep hole:

GUARD POSTS

Material: N/A
 No. & Size: N/A

SURFACE PAD

Composition: N/A
 Size: N/A

RISER PIPE

Material: PVC
 Schedule: SCH 40
 Joint Type: THREADED
 O-ring: RUBBER
 Diameter: 2 INCHES

GROUT

Amt cement: 47 POUNDS
 Amt bentonite: 5 POUNDS
 Amt water: 5 GALLONS
 Tremied: NO
 Interval BGS: 0-2 FEET

SEAL

Material: BENTONITE
 Type: CHIPS
 Amount Used: 50 POUNDS
 Interval BGS: 2-4 FEET

FILTER PACK

Material: SILICA SAND
 Brand Name: MORIE
 Amount Used: 275 POUNDS
 Grain Size Dist: #0
 Interval BGS: 4-15 FEET

SCREEN

Material: PVC
 Diameter: 2 INCHES
 Slot Size & Type: 0.01 INCHES
 Interval BGS: 5-15 FEET

SUMP


Interval BGS: N/A
 Bottom Cap: YES

BACKFILL PLUG

Material: N/A
 Setup/Hydration Time: N/A

BEDROCK MONITORING WELL CONSTRUCTION LOG

WELL NO.: MW-1B	FACILITY/SITE NAME: SOUTH HILL DUMP
PROJ. NO.: 729396.02000	CLIENT: NYSDEC
INSPECTORS N.A. SMITH / S.B. DILLMAN	DRILLING CONTACTOR: SJB SERVICES, INC.
DATE START: MARCH 26, 1997	DATE END: APRIL 10, 1997
AREA GEOLOGY DESCRIBED ON BORING LOG MW-1	



PROTECTIVE CASING	
Material:	STEEL
Diameter:	4 INCHES
Depth BGS:	20 FEET
Water Tight Seal:	YES
Flushmount:	NO
Weep hole:	
GUARD POSTS	
Material:	N/A
No. & Size:	N/A
SURFACE PAD	
Composition:	N/A
Size:	N/A
OUTER CASING	
Material:	STEEL
Diameter:	4 INCHES
RISER PIPE	
Material:	PVC
Schedule:	SCH 40
Joint Type:	THREADED
O-ring:	RUBBER
Diameter:	2 INCHES
GROUT	
Amt cement:	564 POUNDS
Amt bentonite:	25 POUNDS
Amt water:	60 GALLONS
Tremied:	YES
Interval BGS:	0-27 FEET
SEAL	
Material:	N/A
Type:	N/A
Amount Used:	N/A
Interval BGS:	N/A
FILTER PACK	
Material:	SILICA SAND
Brand Name:	MORIE
Amount Used:	150 POUNDS
Grain Size Dist.:	#0
Interval BGS:	19-35 FEET
SCREEN	
Material:	PVC
Diameter:	2 INCHES
Slot Size & Type:	0.01"
Interval BGS:	25-35 FEET
SUMP	
Interval BGS:	N/A
Bottom Cap:	YES
BACKFILL PLUG	
Material:	N/A
Setup/Hydration Time:	N/A

OVERBURDEN MONITORING WELL CONSTRUCTION LOG


WELL NO.: MW-2S
 PROJ. NO.: 729396.02000
 INSPECTORS: N.A. SMITH
 DATE START: MARCH 27, 1997
 AREA GEOLOGY DESCRIBED ON BORING LOG MW-2

FACILITY/SITE NAME: SOUTH HILL DUMP
 CLIENT: NYSDEC
 DRILLING CONTACTOR: SJB SERVICES. INC.
 DATE END: MARCH 27, 1997

Elevation: 1575.40 feet (rim below PVC)
 Height:

Elevation: 1575.45 feet
 Height:

GS Elevation: 1572.6 feet
 Depth BGS



PROTECTIVE CASING	
Material:	STEEL
Diameter:	4 INCHES
Depth BGS:	2 FEET
Water Tight Seal:	YES
Flushmount:	NO
Weep hole:	
GUARD POSTS	
Material:	N/A
No. & Size:	N/A
SURFACE PAD	
Composition:	N/A
Size:	N/A
RISER PIPE	
Material:	PVC
Schedule:	SCH 40
Joint Type:	THREADED
O-ring:	RUBBER
Diameter:	2 INCHES
GROUT	
Amt cement:	94 POUNDS
Amt bentonite:	8 POUNDS
Amt water:	10 GALLONS
Tremied:	NO
Interval BGS:	0-2 FEET
SEAL	
Material:	BENTONITE
Type:	CHIPS
Amount Used:	50 POUNDS
Interval BGS:	2-4 FEET
FILTER PACK	
Material:	SILICA SAND
Brand Name:	MORIE
Amount Used:	125 POUNDS
Grain Size Dist.:	#0
Interval BGS:	4-10 FEET
SCREEN	
Material:	PVC
Diameter:	2 INCHES
Slot Size & Type:	0.01 INCHES
Interval BGS:	5-10 FEET
SUMP	
Interval BGS:	N/A
Bottom Cap:	YES
BACKFILL PLUG	
Material:	N/A
Setup/Hydration Time:	N/A

OVERBURDEN MONITORING WELL CONSTRUCTION LOG



WELL NO.: MW-2D
 PROJ. NO.: 729396.02000
 INSPECTORS: N.A. SMITH / C.R. TORELL
 DATE START: MARCH 27, 1997
 AREA GEOLOGY DESCRIBED ON BORING LOG MW-2

FACILITY/SITE NAME: SOUTH HILL DUMP
 CLIENT: NYSDEC
 DRILLING CONTACTOR: SJB SERVICES, INC.
 DATE END: APRIL 7, 1997

Elevation: 1576.30 feet
 Height:

Elevation: 1575.00 feet
 Height:

GS Elevation: 1572.0 feet
 Depth BGS:



PROTECTIVE CASING

Material: STEEL
 Diameter: 4 INCHES
 Depth BGS: 2 FEET
 Water Tight Seal: YES
 Flushmount: NO
 Weep hole:

GUARD POSTS

Material: N/A
 No. & Size: N/A

SURFACE PAD

Composition: N/A
 Size: N/A

RISER PIPE

Material: PVC
 Schedule: SCH 40
 Joint Type: THREADED
 O-ring: RUBBER
 Diameter: 2 INCHES

GROUT

Amt cement: 282 POUNDS
 Amt bentonite: 25 POUNDS
 Amt water: 20 GALLONS
 Tremied: NO
 Interval BGS: 0-10 FEET

SEAL

Material: BENTONITE
 Type: CHIPS
 Amount Used: 37.5 POUNDS
 Interval BGS: 10-12 FEET

FILTER PACK

Material: SILICA SAND
 Brand Name: MORIE
 Amount Used: 300 POUNDS
 Grain Size Dist.: #0
 Interval BGS: 12-24 FEET

SCREEN

Material: PVC
 Diameter: 2 INCHES
 Slot Size & Type: 0.01 INCHES
 Interval BGS: 14-24 FEET

SUMP

Interval BGS: N/A
 Bottom Cap: YES

BACKFILL PLUG

Material: N/A
 Setup/Hydration Time: N/A


BEDROCK MONITORING WELL CONSTRUCTION LOG

WELL NO.: MW-2B
 PROJ. NO.: 729396.02000
 INSPECTORS: N.A. SMITH / C.R. TORELL
 DATE START: MARCH 27, 1997
 AREA GEOLOGY DESCRIBED ON BORING LOG MW-2

FACILITY/SITE NAME: SOUTH HILL DUMP
 CLIENT: NYSDEC
 DRILLING CONTACTOR: SJB SERVICES, INC.
 DATE END: APRIL 7, 1997

Elevation: 1574.85 feet
 Height:

GS Elevation: 1573.4 feet
 Depth BGS



PROTECTIVE CASING

Material: STEEL
 Diameter: 4 INCHES
 Depth BGS: 31.5 FEET
 Water Tight Seal: YES
 Flushmount: NO
 Weep hole:

GUARD POSTS

Material: N/A
 No. & Size: N/A

SURFACE PAD

Composition: N/A
 Size: N/A

OUTER CASING

Material: STEEL
 Diameter: 4 INCHES

RISER PIPE

Material: N/A - OPEN HOLE
 Schedule: N/A
 Joint Type: N/A
 O-ring: N/A
 Diameter: N/A

GROUT

Amt cement: 470 POUNDS
 Amt bentonite: 37.5 POUNDS
 Amt water: 25 GALLONS
 Tremied: YES
 Interval BGS: 0-31.5 FEET

SEAL

Material: N/A - OPEN HOLE
 Type: N/A
 Amount Used: N/A
 Interval BGS: N/A

FILTER PACK

Material: N/A - OPEN HOLE
 Brand Name: N/A
 Amount Used: N/A
 Grain Size Dist.: N/A
 Interval BGS: N/A

SCREEN

Material: N/A - OPEN HOLE
 Diameter: N/A
 Slot Size & Type: N/A
 Interval BGS: N/A

SUMP

Interval BGS: N/A - OPEN HOLE
 Bottom Cap: N/A

BACKFILL PLUG

Material: N/A
 Setup/Hydration Time: N/A

OVERBURDEN MONITORING WELL CONSTRUCTION LOG

WELL NO.: MW-3S
 PROJ. NO.: 729396.02000
 INSPECTORS: N.A. SMITH
 DATE START: APRIL 3, 1997
 AREA GEOLOGY DESCRIBED ON BORING LOG MW-3

FACILITY/SITE NAME: SOUTH HILL DUMP
 CLIENT: NYSDEC
 DRILLING CONTACTOR: SJB SERVICES, INC.
 DATE END: APRIL 4, 1997

Elevation: 1571.05 feet (rim below PVC)


Height:

Elevation: 1571.15 feet

Height:

GS Elevation: 1568.3 feet

Depth BGS



PROTECTIVE CASING

Material: STEEL
 Diameter: 4 INCHES
 Depth BGS: 2 FEET
 Water Tight Seal: YES
 Flushmount: NO
 Weep hole:

GUARD POSTS

Material: N/A
 No. & Size: N/A

SURFACE PAD

Composition: N/A
 Size: N/A

RISER PIPE

Material: PVC
 Schedule: SCH 40
 Joint Type: THREADED
 O-ring: RUBBER
 Diameter: 2 INCHES

GROUT

Amt cement: 94 POUNDS
 Amt bentonite: 8 POUNDS
 Amt water: 10 GALLONS
 Tremied: NO
 Interval BGS: 0-2 FEET

SEAL

Material: BENTONITE
 Type: CHIPS
 Amount Used: 37.5 POUNDS
 Interval BGS: 2-4 FEET

FILTER PACK

Material: SILICA SAND
 Brand Name: MORIE
 Amount Used: 225 POUNDS
 Grain Size Dist.: #0
 Interval BGS: 4-10 FEET

SCREEN

Material: PVC
 Diameter: 2 INCHES
 Slot Size & Type: 0.01 INCHES
 Interval BGS: 5-10 FEET

SUMP

Interval BGS: N/A
 Bottom Cap: YES

BACKFILL PLUG

Material: N/A
 Setup/Hydration Time: N/A


BEDROCK MONITORING WELL CONSTRUCTION LOG

WELL NO.: MW-3B
 PROJ. NO.: 729396.02000
 INSPECTORS: N.A. SMITH / S.B. DILLMAN
 DATE START: APRIL 3, 1997
 AREA GEOLOGY DESCRIBED ON BORING LOG MW-3

FACILITY/SITE NAME: SOUTH HILL DUMP
 CLIENT: NYSDEC
 DRILLING CONTACTOR: SJB SERVICES, INC.
 DATE END: APRIL 9, 1997

Elevation: 1570.20 feet
 Height:

GS Elevation: 1567.3 feet
 Depth BGS



PROTECTIVE CASING

Material: STEEL
 Diameter: 4 INCHES
 Depth BGS: 16 FEET
 Water Tight Seal: YES
 Flushmount: NO
 Weep hole:

GUARD POSTS

Material: N/A
 No. & Size: N/A

SURFACE PAD

Composition: N/A
 Size: N/A

OUTER CASING

Material: STEEL
 Diameter: 4 INCHES

RISER PIPE

Material: N/A - OPEN HOLE
 Schedule: N/A
 Joint Type: N/A
 O-ring: N/A
 Diameter: N/A

GROUT

Amt cement: 188 POUNDS
 Amt bentonite: 25 POUNDS
 Amt water: 15 GALLONS
 Tremied: YES
 Interval BGS: 0-16 FEET

SEAL

Material: N/A - OPEN HOLE
 Type: N/A
 Amount Used: N/A
 Interval BGS: N/A

FILTER PACK

Material: N/A - OPEN HOLE
 Brand Name: N/A
 Amount Used: N/A
 Grain Size Dist.: N/A
 Interval BGS: N/A

SCREEN

Material: N/A - OPEN HOLE
 Diameter: N/A
 Slot Size & Type: N/A
 Interval BGS: N/A

SUMP

Interval BGS: N/A - OPEN HOLE
 Bottom Cap: N/A

BACKFILL PLUG

Material: N/A
 Setup/Hydration Time: N/A

OVERBURDEN MONITORING WELL CONSTRUCTION LOG


WELL NO.: MW-4S
 PROJ. NO.: 729396.02000
 INSPECTORS: N.A. SMITH / C.R. TORELL
 DATE START: APRIL 8, 1997
 AREA GEOLOGY DESCRIBED ON BORING LOG MW-4

FACILITY/SITE NAME: SOUTH HILL DUMP
 CLIENT: NYSDEC
 DRILLING CONTACTOR: SJB SERVICES, INC.
 DATE END: APRIL 8, 1997

Elevation: 1545.45 feet
 Height:

Elevation: 1545.40 feet
 Height:

GS Elevation: 1542.6 feet
 Depth BGS



PROTECTIVE CASING

Material: STEEL
 Diameter: 4 INCHES
 Depth BGS: 2 FEET
 Water Tight Seal: YES
 Flushmount: NO
 Weep hole:

GUARD POSTS

Material: N/A
 No. & Size: N/A

SURFACE PAD

Composition: N/A
 Size: N/A

RISER PIPE

Material: PVC
 Schedule: SCH 40
 Joint Type: THREADED
 O-ring: RUBBER
 Diameter: 2 INCHES

GROUT

Amt cement: 94 POUNDS
 Amt bentonite: 10 POUNDS
 Amt water: 10 GALLONS
 Tremied: NO
 Interval BGS: 0-3 FEET

SEAL

Material: BENTONITE
 Type: CHIPS
 Amount Used: 50 POUNDS
 Interval BGS: 3-5 FEET

FILTER PACK

Material: SILICA SAND
 Brand Name: MORIE
 Amount Used: 350 POUNDS
 Grain Size Dist.: #0
 Interval BGS: 5-16 FEET

SCREEN

Material: PVC
 Diameter: 2 INCHES
 Slot Size & Type: 0.01 INCHES
 Interval BGS: 6-16 FEET

SUMP

Interval BGS: N/A
 Bottom Cap: YES

BACKFILL PLUG

Material: N/A
 Setup/Hydration Time: N/A

BEDROCK MONITORING WELL CONSTRUCTION LOG

WELL NO.: MW-4B
 PROJ. NO.: 729396.02000
 INSPECTORS: N.A. SMITH / C.R. TORELL
 DATE START: MARCH 31, 1997
 AREA GEOLOGY DESCRIBED ON BORING LOG MW-4

FACILITY/SITE NAME: SOUTH HILL DUMP
 CLIENT: NYSDEC
 DRILLING CONTACTOR: SJB SERVICES, INC.
 DATE END: APRIL 8, 1997

Elevation: 1545.45 feet
 Height:

GS Elevation: 1541.9 feet
 Depth BGS

33.2
FEET

TOP OF BEDROCK

36
FEET

46.6
FEET

BOREHOLE DIA.

3 INCHES

PROTECTIVE CASING

Material: STEEL
 Diameter: 4 INCHES
 Depth BGS: 36 FEET
 Water Tight Seal: YES
 Flushmount: NO
 Weep hole:

GUARD POSTS

Material: N/A
 No. & Size: N/A

SURFACE PAD

Composition: N/A
 Size: N/A

OUTER CASING

Material: STEEL
 Diameter: 4 INCHES

RISER PIPE

Material: N/A - OPEN HOLE
 Schedule: N/A
 Joint Type: N/A
 O-ring: N/A
 Diameter: N/A

GROUT

Amt cement: 376 POUNDS
 Amt bentonite: 42 POUNDS
 Amt water: 20 GALLONS
 Tremied: YES
 Interval BGS: 0-36 FEET

SEAL

Material: N/A - OPEN HOLE
 Type: N/A
 Amount Used: N/A
 Interval BGS: N/A

FILTER PACK

Material: N/A - OPEN HOLE
 Brand Name: N/A
 Amount Used: N/A
 Grain Size Dist.: N/A
 Interval BGS: N/A

SCREEN

Material: N/A - OPEN HOLE
 Diameter: N/A
 Slot Size & Type: N/A
 Interval BGS: N/A

SUMP

Interval BGS: N/A - OPEN HOLE
 Bottom Cap: N/A

BACKFILL PLUG

Material: N/A
 Setup/Hydration Time: N/A

WELL DEVELOPMENT DATA

Well Name: MW-15

Site Name: South Hill bump

Site No.: 712009

[illegible]

REMARKS:

Well Name: MW-1B

Site Name: South Hill Dump

Site No.: 712009

[illegible]

REMARKS:

Well Name: MW-2S

Site Name: South Hill Dump

Site No.: 712009

[illegible]

REMARKS:

Well Name: MW-2D

Site Name: South Hill Dump

Site No.: 712009

[illegible]

REMARKS:

WELL DEVELOPMENT OBSERVATIONS

Well Name: MW-2B

Site Name: South Hill Dump

Site No.: 712889

[illegible]

REMARKS:

Well Name: mw-35

Site Name: South Hill bump

Site No.: 712009

[illegible]

REMARKS:

WELL DEVELOPMENT OBSERVATIONS

Well Name: MW-3B

Site Name: South Hill Dump

Site No.: 712009

[illegible]

REMARKS:

Well Name: nw-48

Site Name: South Hill Dump

Site No.: 712409

[illegible]

Well Name:

mw-45

Site Name: South Hill Dump

Site No.: 212009

[illegible]

REMARKS: