
REMEDIAL ACTION NEW YORK STATE DEPARTMENT OF ENVIRONMENTAL CONSERVATION SOUTH HILL DUMP SITE, SITE NO. 712009 CORTLANDVILLE, NEW YORK

MARCH 2011 CONTRACT NO. D007992



DRAWING INDEX

INCLUDED THIS SUBMITTAL	SHEET NUMBER	DRAWING TITLE	DISCIPLINE NUMBER
•	1	COVER SHEET	G-001
•	2	LEGEND, ABBREVIATIONS, AND GENERAL NOTES	G-002
•	3	EXISTING CONDITIONS PLAN	C-101
•	4	EXCAVATION PLAN 1	C-102
•	5	EXCAVATION PLAN 2	C-103
•	6	SUBGRADE AND EROSION AND SEDIMENT CONTROL PLAN 1	C-104
•	7	SUBGRADE AND EROSION AND SEDIMENT CONTROL PLAN 2	C-105
•	8	FINAL CONDITIONS PLAN 1	C-106
•	9	FINAL CONDITIONS PLAN 2	C-107
•	10	EROSION AND SEDIMENT CONTROL NOTES	C-301
•	11	EROSION AND SEDIMENT CONTROL DETAILS	C-302
•	12	CIVIL DETAILS 1	C-303
•	13	CIVIL DETAILS 2	C-304
•	14	CIVIL DETAILS 3	C-305
•	15	GROUNDWATER MONITORING WELL DETAILS	C-306





FILE NAME: M:\Projects\nvsdec1\SOUTH HILL DUMP\RD-G-001.dwg PLOT DATE: Fri. 04 Mar 2011 PLOT TIME: 4:14 PM

GENERAL NOTES:

1 DRAWING INFORMATION

- SITE LOCATION, TOPOGRAPHY, AND BOUNDARY INFORMATION BASED ON A PLAN ENTITLED BOUNDARY & TOPOGRAPHIC MAP, PREPARED FOR THE NEW YORK STATE D.E.C., FORMER SOUTH HILL DUMP SITE, BEING PART OF LOT #100, TOWN OF CORTLANDVILLE, COUNTY OF CORTLAND, STATE OF NEW YORK, BY THE POPLI DESIGN GROUP, DATED JANUARY 20, 2010.
- TEST PIT TRENCH LOCATIONS, DESIGNATED AS "TP-X", ARE BASED ON A PLAN ENTITLED, "TOPOGRAPHIC SURVEY SOUTH HILL DUMP SITE", PREPARED BY SPENCER F. THEW, P.E., L.S., DATED
- C. TEST PIT TRENCH LOCATIONS DESIGNATED AS "TP 10-X", ARE BASED ON GPS LOCATIONS COLLECTED BY MACTEC ENGINEERING AND CONSULTING, PC IN NOVEMBER 2010.
- APPROXIMATE LOCATION OF BULKY WASTE AND DEBRIS STOCKPILES BASED ON FIELD OBSERVATIONS BY MACTEC ENGINEERING AND CONSULTING, PC DURING A SITE VISIT ON APRIL 28, 2005.
- APPROXIMATE LOCATION OF EXISTING SOLID WASTE BOUNDARY (LIMIT OF WASTE) IS BASED ON GEOPHYSICAL SURVEY INCLUDING HIGH RESOLUTION METAL DETECTION AND GROUND PENETRATING RADAR PERFORMED BY MACTEC ENGINEERING AND CONSULTING, P.C. IN THE FALL 2009.

2 SURVEY INFORMATION:

- MAPPING REFERENCED TO THE NORTH AMERICAN DATUM OF 1983 (CORS) NEW YORK STATE PLANE COORDINATE SYSTEM, CENTRAL ZONE,
- B. ELEVATIONS SHOWN HEREON ARE REFERENCED TO THE NORTH AMERICAN VERTICAL DATUM OF 1988.
- C. MAPPING UNITS ARE SHOWN IN U.S. SURVEY FEET.
- D. THE CONTOUR INTERVAL IS 1 FOOT.
- E. THE SITE WAS SNOW COVERED AT THE TIME OF SURVEY.
- F. SURVEY CONTROL POINTS ESTABLISHED BY THE POPLI DESIGN GROUP DURING THEIR FIELD SURVEY IN 2009/2010 ARE SHOWN IN THE SURVEY CONTROL POINT LOCATION DIAGRAMS, THIS SHEET.
- FOR BOUNDARY DEED REFERENCES AND NOTES, REFER TO THE PLAN ENTITLED BOUNDARY & TOPOGRAPHIC MAP, PREPARED FOR THE NEW YORK STATE D.E.C., FORMER SOUTH HILL DUMP SITE, BEING PART OF LOT #100, TOWN OF CORTLANDVILLE, COUNTY OF CORTLAND, STATE OF NEW YORK, BY THE POPLI DESIGN GROUP, DATED JANUARY 20, 2010.

3. EXISTING SOLID WASTE BOUNDARY (LIMIT OF WASTE):

- THE EXISTING SOLID WASTE BOUNDARY AS SHOWN ON DRAWING SHEET C-101 IS LOCATED BASED ON TEST PITTING AND GEOPHYSICAL SURVEY AND IS APPROXIMATE.
- THE DEPTH OF WASTE AT THE IDENTIFIED SOLID WASTE BOUNDARY IS UNKNOWN, HOWEVER, HAS BEEN ESTIMATED TO BE APPROXIMATELY 2.5 FEET.
- THE CONTRACTOR IS RESPONSIBLE FOR COORDINATING PERMISSIONS AND ACCESS AGREEMENTS TO PERMIT WORK INCLUDING, BUT NOT LIMITED TO, CLEARING, GRUBBING, EXCAVATING, GRADING, AND FILLING IN THE SOUTH HILL ROAD RIGHT-OF-WAY OWNED BY THE TOWN OF CORTLANDVILLE. THE NEW YORK STATE DEPARTMENT OF ENVIRONMENTAL CONSERVATION IS RESPONSIBLE FOR SECURING ANY OTHER ACCESS AGREEMENTS REQUIRED TO
- EAST AND WEST PROPERTY BOUNDARIES SHALL BE MARKED IN THE FIELD BY A NEW YORK STATE LICENSED SURVEYOR TO ENSURE DISTURBANCE OCCURS ONLY WITHIN THE TOWN OF CORTLANDVILLE PROPERTY WITH THE EXCEPTION OF THE NEGOTIATED PERMISSIONS/ACCESS AGREEMENTS.

WASTE CONSOLIDATION SHALL CONSIST OF:

- REMOVING AND RELOCATING ON-SITE SOLID WASTES AS DEFINED IN THE SPECIFICATIONS TO WITHIN THE NEW SOLID WASTE BOUNDARY
- REMOVING GRUBBINGS AND RELOCATION TO WITHIN THE IDENTIFIED AREA INSIDE THE NEW SOLID WASTE
- ONLY THOSE CLASSIFICATIONS OF WASTES AS DEFINED IN THE SPECIFICATIONS SHALL BE ALLOWED TO BE CONSOLIDATED ON-SITE.

7. GRADING PERFORMANCE CRITERIA:

SUBGRADE CONTOURS WITHIN THE NEW SOLID WASTE BOUNDARY SHOWN ON DRAWING SHEET C-104 AND C-105 REPRESENT THE REGRADED SURFACE OF THE LANDFILL ON WHICH THE COVER SYSTEM WILL BE INSTALLED. THE REGRADED SURFACE TAKES INTO ACCOUNT THE FILL QUANTITIES GENERATED FROM WASTE CONSOLIDATION, EXCESS EXCAVATED SOILS FROM OUTSIDE THE NEW SOLID WASTE BOUNDARY, AND GRUBBINGS DISPOSAL. HOWEVER, THE WASTE CONSOLIDATION VOLUME IS BASED ON AN ESTIMATED DEPTH OF WASTE AND MAY DIFFER FROM THE DESIGN ESTIMATES. THEREFORE, FLEXIBILITY IN THE ELEVATION OF SUBGRADE IS REQUIRED TO ACCOMMODATE DIFFERENCES DUE TO ACTUAL FIELD CONDITIONS. THE SUBGRADE DRAWING IS INTENDED TO SHOW GENERAL SLOPES AND DRAINAGE PATTERNS; IT DOES NOT MANDATE ELEVATIONS TO BE ACHIEVED. DEVAINOS FROM THE SUBGRADE ELEVATIONS ARE ALLOWED WITH ENGINEER APPROVAL, PROVIDED THE FOLLOWING GRADING CRITERIA ARE MET:

- MAXIMUM ALLOWABLE SUBGRADE SLOPE IS 3 FEET IN THE HORIZONTAL TO 1 FOOT IN THE VERTICAL (3:1) OR 33 PERCENT.
- MINIMUM ALLOWABLE SUBGRADE SLOPE IS 20 FEET IN THE HORIZIONTAL TO 1 FOOT IN THE VERTICAL (20:1)
- ON-SITE SOLID WASTE, COVER SOILS, GRUBBINGS, AND EXCESS SOILS SHALL BE PLACED, GRADED, AND COMPACTED IN LANDFILL FILL AREAS TO MEET THE MINIMUM AND MAXIMUM SLOPE CRITERIA.
- SUBRADE SHALL BE ESTABLISHED WITH THE MINIMAL AMOUNT OF IMPORTED SELECT BORROW POSSIBLE. IMPORTED SELECT BORROW SHALL BE USED ONLY WITH THE APPROVAL OF THE ENGINEER TO AUGMENT AVAILABLE ON-SITE MATERIALS.
- ON-SITE FILL MATERIALS SHALL BE INSTALLED IN A PLANNED SEQUENCE TO ACCOMMODATE THE TOTAL AVAILABLE QUANTITIES AND MINIMIZE THE REQUIRED QUANTITY OF IMPORTED SELECT BORROW. EACH LIFT OF MATERIAL PLACED SHALL MEET THE MINIMUM AND MAXIMUM SLOPE CRITERIA.
- GRADING ACTIVITIES SHALL BE PERFORMED IN A MANNER THAT MAINTAINS ALL SITE FEATURES IN CONFORMANCE WITH THE DESIGN, INCLUDING BUT NOT LIMITED TO SLOPES, SLOPE BENCHES, APRONS, SOLID WASTE BOUNDARY, ROADS, AND DRAINAGE CHANNELS/SWALES.

ABBREVIATIONS:

APPROX APPROXIMATELY ASF AUGMENTED SILTATION FENCE Œ CENTER LINE CONC CP CONTROL POINT (SURVEY) CPE CORRUGATED POLYETHYLENE MEDIAN STONE SIZE D50 DD DOWNDRAIN DIA Ε EASTING, EAST, END EAST DRAINAGE SWALE EDS ELEVATION ELEV FEET GV GAS VENT GW GROUNDWATER HDPE HIGH DENSITY POLYETHYLENE HR HOUR IDENTIFICATION, INSIDE DIAMETER INCHES INV INVFRT LINEAR FEET LOG LIMIT OF GRADING LOW LIMIT OF WORK MAG MAGNETIC MAX MAXIMUM MIN MINIMUM MM MILLIMETER мw MONITORING WELL NORTHING, NORTH ΝE NORTHEAST NO. NUMBER NTS NOT TO SCALE NW NYSDEC NEW YORK STATE DEPARTMENT OF ENVIRONMENTAL CONSERVATION, DEPARTMENT NYSDOT NEW YORK STATE DEPARTMENT OF TRANSPORTATION OD OUTSIDE DIAMETER 07 OUNCE PROPERTY LINE PSI POUNDS PER SQUARE INCH РΤ POINT PVC POLYVINYL CHLORIDE RC. RIPRAP CHANNEL SB SOIL BORING, SLOPE BENCH SCD STONE CHECK DAM SE SOUTHEAST SF SQUARE FEET OR SILTATION FENCE

LEGEND - EXISTING:

- PROPERTY LINE


TOPOGRAPHIC CONTOUR

EDGE OF PAVEMENT CHAINLINK FENCE BARBED-WIRE FENCE SW006/SD005 + SURFACE WATER/SEDIMENT LOCATION GROUNDWATER MONITORING WELL MW-1B-⊕ INTERPRETED SOLID WASTE BOUNDARY LIMIT OF SOLID WASTE IDENTIFIED BY TEST PITTING, INTERPRETED SOLID WASTE BOUNDARY .~~~. TREE LINE INV 1659.XX INVERT ELEVATIONS \$ POSSIBLE DRUMS REMAINING 8 KNOWN DRUMS REMAINING SURFACE MATERIALS OR CONDITIONS AS OBSERVED
DURING THE APRIL 28, 2005 DRUMS, METAL LEGEND - PROPOSED:

 SILTATION FENCE - AUGMENTED SILTATION FENCE - CHAIN LINK FENCE — — — LOW — LIMIT OF WORK - LOG - LIMIT OF GRADING - LOW-LOG - LIMIT OF WORK AND GRADING C ACCESS ROAD — — — — EDGE OF ACCESS ROAD ——— 1600 ——— TOPOGRAPHIC CONTOUR (MAJOR) ——— 1602 ——— TOPOGRAPHIC CONTOUR (MINOR) LIMIT OF CLEARING MW-1R-GROUNDWATER MONITORING WELL GAS VENT SCD COLLECTED SITE STORMWATER RUNOFF (CONSTRUCTION WATER) -—⊳ DIVERTED STORMWATER RUNON — — — un — UNDERDRAIN PIPE

DETAIL LETTER C-103 C-301 -

REFERENCE LEGEND:





State

York ent of Er

VERIFY SCALE BAR IS ONE INCH ON ORIGINAL DRAWING

03/04/20 DATE PROJ 3612-09-2133 DWG G-002 SHEET

SURVEY CONTROL POINT LOCATION DIAGRAMS:


SS

SW

TP

TYP

YR



SOURCE: ōBOUNDARY & TOPOGRAPHIC MAP, PREPARED FOR THE NEW YORK STATE D.E.C., FORMER SOUTH HILL DUMP SITE, BEING PART OF LOT #100, TOWN OF CORTLANDVILLE, COUNTY OF CORTLAND, STATE OF NEW YORK, BY THE POPLI DESIGN GROUP, DATED JANUARY 20, 2010.


STANDARD SPECIFICATIONS


SOUTHWEST


TEST PIT

TYPICAL

YFAR









NY STATE PLANE (NAD 83) HAY BALES (LOCATE AS REQUIRED, SEE NOTE 3) NOTES: INSTALL TEMPORARY PERIMETER DIKE/SWALE TO SEPARATE AND CONVEY STORMWATER IN THE FOLLOWING MANNER:


RUNON FROM THE SOUTH HILL ROAD CULVERT AND ASSOCIATED EXISTING DRAINAGE SWALES SHALL BE CONVEYED THROUGH AND BEYOND THE PROJECT SITE.

RUNOFF FROM THE SITE SHALL BE CONVEYED TO THE ON—SITE SEDIMENTATION BASIN.

RUNOFF AND RUNON SHALL REMAIN SEPARATE UP TO THE SEDIMENTATION BASIN OUTLET. SLOPE BENCH (TYP) PROVIDE TEMPORARY SWALE AND DIVERSION MEASURES TO DIRECT SITE STORMWATER RUNOFF TO THE SEDIMENTATION BASIN DURING CONSTRUCTION. ADJUST THESE MEASURES AS WORK PROGRESSES AND NEW WORK AREAS BECOME ACTIVE. PROVIDE HAY BALE BARRIERS OR SIMILAR SUPPLEMENTAL MEASURE TO CONTROL SEDIMENTATION ALONG THE PERIMETER OF THE NEW SOLID WASTE BOUNDARY DURING CONSTRUCTION. NEW SOLID WASTE BOUNDARY SEDIMENTATION BASIN SUBGRADE AND EROSION AND SEDIMENT CONTROL PLAN 1 MACTEC x 1557 VERIFY SCALE ROCK OUTLET PROTECTION (TYP) (TEMPORARY) -sedimentation/detention basin outlet structure BAR IS ONE INCH ON ORIGINAL DRAWING TEMPORARY PERIMETER DIKE/SWALE 03/04/201 NOTE: PROJ 3612-09-2133 SITE LOCATION, TOPOGRAPHY, AND BOUNDARY INFORMATION BASED ON A PLAN ENTITLED BOUNDARY & TOPOGRAPHIC MAP, PREPARED FOR THE NEW YORK STATE D.E.C., FORMER SOUTH HILL DUMP SITE, BEING PART OF LOT #100, TOWN OF CORTLANDVILLE, COUNTY OF CORTLAND, STATE OF NEW YORK, BY THE POPLI DESIGN GROUP, DATED JANUARY 20, 2010. DWG C-104 SCALE IN FEET







GENERAL EROSION AND SEDIMENT CONTROL NOTES:

- 1. ALL WORK IS TO BE DONE IN ACCORDANCE WITH THE NEW YORK STATE STANDARDS AND SPECIFICATIONS FOR EROSION AND SEDIMENT CONTROL (STATE STANDARDS) AND THE CONTRACT DOCUMENTS, SPECIFICALLY:

 - DRAWING C-103 ōSUBGRADE AND EROSION AND SEDIMENT CONTROL PLANō; DRAWING C-301 ōEROSION AND SEDIMENT CONTROL NOTESö; AND
 - DRAWING C-302 TEROSION AND SEDIMENT CONTROL DETAILS
- IF A DISCREPANCY EXISTS BETWEEN THE STATE STANDARDS AND THE CONTRACT DOCUMENTS, THE STATE STANDARDS
- . SOIL EROSION AND SEDIMENT CONTROL PRACTICES ARE TO BE INSTALLED PRIOR TO ANY MAJOR SOIL 2. ALL SOIL EROSION AND SEDIMENT CONTROL PRACTICES ARE TO BE INSTALLED FROM TO ARE TRADE. SOIL DISTURBANCE, OR IN THEIR PROPER SEQUENCE, AND MAINTAINED UNTIL PERMANENT PROTECTION IS ESTABLISHED.
- 3. EROSION AND SEDIMENTATION CONTROLS SHALL BE AUGMENTED OR SUPPLEMENTED IF THE INSTALLED MEASURES DO NOT PROVIDE ADEQUATE PROTECTION OF DOWNSTREAM RESOURCES AS DETERMINED BY THE ENGINEER OR
- ANY DISTURBED AREAS THAT WILL BE LEFT EXPOSED MORE THAN FOURTEEN (14) DAYS, AND NOT SUBJECT TO CONSTRUCTION TRAFFIC, WILL IMMEDIATELY RECEIVE A TEMPORARY SEEDING. IF THE SEASON PREVENTS THE ESTABLISHMENT OF TEMPORARY COVER, THE DISTURBED AREAS WILL BE MULCHED WITH HAY OR STRAW, OR EQUIVALENT MATERIAL, AT A RATE OF 2 TONS PER ACRE, ACCORDING TO STATE STANDARDS.
- 5. IMMEDIATELY FOLLOWING INITIAL DISTURBANCE OR ROUGH GRADING, ALL CRITICAL AREAS SUBJECT TO EROSION (I.E. STEEP SLOPES AND ROADWAY EMBANKMENTS) WILL RECEIVE TEMPORARY SEEDING IN COMBINATION WITH HAY OR STRAW MULCH OR A SUITABLE EQUIVALENT. AT A RATE OF 2 TONS PER ACRE. ACCORDING TO STATE STANDARDS.
- 6. ANY STEEP SLOPES (I.E. SLOPES GREATER THAN 3:1) WILL BE COMPLETELY GRADED AND STABILIZED DAILY, AS
- 7. THE STANDARD FOR STABILIZED CONSTRUCTION ENTRANCE REQUIRES THE INSTALLATION OF A PAD OF CLEAN CRUSHED STONE AT POINTS WHERE TRAFFIC WILL BE ACCESSING THE CONSTRUCTION SITE.
- 8. ALL SOIL WASHED, DROPPED, SPILLED, OR TRACKED OUTSIDE THE LIMIT OF WORK OR ONTO PUBLIC RIGHT-OF-WAYS SHALL BE REMOVED IMMEDIATELY.
- PERMANENT VEGETATION IS TO BE SEEDED OR SODDED ON ALL EXPOSED AREAS AS SOON AS POSSIBLE AFTER FINAL GRADING. IF SEEDING IS NOT PERFORMED WITHIN 48 HOURS OF COMPLETION OF FINAL GRADING, ADDITIONAL SURFACE SCARIFICATION SHALL BE COMPLETED PRIOR TO SEEDING.
- 10. AT THE TIME THAT SITE PREPARATION FOR PERMANENT VEGETATIVE STABILIZATION IS TO BE UNDERTAKEN, ANY SOIL THAT WILL NOT PROVIDE A SUITABLE ENVIRONMENT TO SUPPORT ADEQUATE VEGETATIVE GROWTH SHALL BE REMOVED OR TREATED IN SUCH A WAY THAT WILL PERMANENTLY ADJUST THE SOIL CONDITIONS AND RENDER IT SUITABLE TO SUSTAIN VEGETATIVE GROWTH. IF THE REMOVAL OR TREATMENT OF THE SOIL WILL NOT PROVIDE SUITABLE CONDITIONS, NON-VEGETATIVE MEANS OF PERMANENT STABILIZATION SHALL BE EMPLOYED.
- 11. UNFILTERED DEWATERING IS NOT PERMITTED. NECESSARY PRECAUTIONS MUST BE TAKEN DURING ALL DEWATERIN OPERATIONS TO MINIMIZE SEDIMENT TRANSFER. ANY DEWATERING METHODS USED MUST BE IN ACCORDANCE WITH THE STANDARD FOR DEWATERING.
- 12. SHOULD THE CONTROL OF DUST AT THE SITE BE NECESSARY, THE SITE WILL BE SPRINKLED WITH WATER UNTIL THE SURFACE IS WET. TEMPORARY VEGETATIVE COVER SHALL BE ESTABLISHED OR MULCH SHALL BE APPLIED PER THE STATE STANDARDS. CALCIUM CHLORIDE SHALL ONLY BE USED FOR DUST CONTROL DURING FREEZING CONDITIONS.
- 13. STOCKPILE AND STAGING LOCATIONS ESTABLISHED IN THE FIELD SHALL BE PLACED WITHIN THE LIMIT OF WORK WITH APPROPRIATE PROTECTIVE EROSION AND SEDIMENTATION CONTROLS.
- 14. ALL SOIL STOCKPILES ARE TO BE TEMPORARILY STABILIZED IN ACCORDANCE WITH GENERAL EROSION AND SEDIMENT CONTROL NOTE NO. 4.
- 15. CONDUIT OUTLET PROTECTION MUST BE INSTALLED AT ALL REQUIRED OUTFALLS PRIOR TO THE DRAINAGE SYSTEM BECOMING OPERATIONAL.
- 16. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY EROSION OR SEDIMENTATION THAT MAY OCCUR DOWNGRADIENT OF STORMWATER OUTFALLS/OUTLETS OR OFFSITE AS A RESULT OF CONSTRUCTION OF THE PROJECT.

SOIL EROSION AND SEDIMENT CONTROL INSPECTION AND MAINTENANCE:

- 1. STABILIZED CONSTRUCTION FNTRANCE
 - STABILIZED CONSTRUCTION ENTRANCES SHALL, AT A MINIMUM, BE INSPECTED WEEKLY AND WITHIN 24 HOURS AFTER EVERY PRECIPITATION EVENT THAT PRODUCES 0.5 INCHES OF RAIN OR MORE DURING A 24-HOUR
 - STABILIZED CONSTRUCTION ENTRANCES SHALL BE MAINTAINED IN A CONDITION THAT WILL PREVENT TRACKING OF SEDIMENT ONTO PAVED SURFACES. CHECK FOR DAMAGE/DETERIORATION/CLOGGING AND IMMEDIATELY REPAIR OR RECONSTRUCT AS NECESSARY.
 - C. THE PERFORMANCE OF STABILIZED CONSTRUCTION ENTRANCES SHALL BE MAINTAINED BY LENGTHENING, SCRAPING, OR TOP-DRESSING WITH ADDITIONAL AGGREGATE.
 - D. STABILIZED CONSTRUCTION ENTRANCES SHALL HAVE A 6-INCH MINIMUM THICKNESS.
 - INSPECT ADJACENT IMPERVIOUS SURFACES DAILY (MINIMUM). IMMEDIATELY REMOVE VISIBLE ACCUMULATED SEDIMENT DEPOSITED ON PAVED SURFACES VIA SWEEPING, VACUUMING, OR WASHING. WHEN WASHING IS REQUIRED, IT SHALL BE DONE ON AN AREA STABILIZED WITH AGGREGATE, WHICH DRAINS INTO AN APPROVED SEDIMENT TRAPPING DEVICE. PROPERLY DISPOSE OF SEDIMENT
- SEDIMENT BARRIERS

 - A.1. SILTATION FENCES SHALL, AT A MINIMUM, BE INSPECTED WEEKLY AND WITHIN 24 HOURS AFTER EVERY PRECIPITATION EVENT THAT PRODUCES 0.5 INCHES OF RAIN OR MORE DURING A 24- HOUR PERIOD.
 - A.2. REMOVE THE SEDIMENT DEPOSITS OR INSTALL A SECONDARY BARRIER UPSLOPE FROM THE EXISTING BARRIER WHEN SEDIMENT DEPOSITS REACH ONE HALF THE HEIGHT OF THE FENCE. PROPERLY DISPOSE OF SEDIMENT.
 - A.3. REPLACE OR REPAIR FENCES WITHIN 24 HOURS OF OBSERVED FAILURE (E.G., DAMAGE OR DECOMPOSITION; FENCE MOVED OUT OF POSITION; UNDERCUTTING, OVERTOPPING, OR FLOW CHANNELS AROUND THE END OF FENCES).
 - A.4. MAINTAIN SILTATION FENCES UNTIL THE CONTRIBUTING AREA IS STABILIZED

SOIL EROSION AND SEDIMENT CONTROL INSPECTION AND MAINTENANCE:

- - B.1. AUGMENTED SILTATION FENCES SHALL, AT A MINIMUM, BE INSPECTED WEEKLY AND WITHIN 24 HOURS AFTER EVERY PRECIPITATION EVENT THAT PRODUCES 0.5 INCHES OF RAIN OR MORE DURING A 24-
 - B.2. REMOVE THE SEDIMENT DEPOSITS OR INSTALL A SECONDARY BARRIER UPSLOPE FROM THE EXISTING BARRIER WHEN SEDIMENT DEPOSITS REACH ONE HALF THE HEIGHT OF THE FENCE. PROPERLY DISPOSE OF SEDIMENT.
 - B.3. REPLACE OR REPAIR FENCES WITHIN 24 HOURS OF OBSERVED FAILURE (E.G., DAMAGE OR DECOMPOSITION; FENCE MOVED OUT OF POSITION; UNDERCUTTING, OVERTOPPING, OR FLOW CHANNELS
 - B.4. RESHAPE, ADD ADDITIONAL MATERIAL, OR REPLACE FILTER BERM WHEN DISTURBED BY CONSTRUCTION ACTIVITIES OR SIGNIFICANT STORM EVENTS.
 - B.5. MAINTAIN AUGMENTED SILTATION FENCES UNTIL THE CONTRIBUTING AREA IS STABILIZED.

1. PERIMETER DIKE/SWALE

- PERIMETER DIKES/SWALES SHALL, AT A MINIMUM, BE INSPECTED WEEKLY AND WITHIN 24 HOURS AFTER EVERY PRECIPITATION EVENT THAT PRODUCES 0.5 INCHES OF RAIN OR MORE DURING A 24-HOUR PERIOD.
- ACCUMULATED SEDIMENT SHALL BE REMOVED WHEN IT REACHES ONE HALF THE HEIGHT OF THE PERIMETER DIKE/SWALE. PROPERLY DISPOSE OF SEDIMENT.
- REGRADE SWALE AND REPAIR DIKE AS REQUIRED TO CAPTURE CONSTRUCTION RUNOFF FROM THE LANDFILL AND CONVEY IT TO THE SEDIMENTATION BASIN.
- D. MAINTAIN PERIMETER DIKES/SWALES UNTIL THE AREA IS STABILIZED.
- 4. TEMPORARY SWALE
 - TEMPORARY SWALES SHALL, AT A MINIMUM, BE INSPECTED WEEKLY AND WITHIN 24 HOURS AFTER EVERY PRECIPITATION EVENT THAT PRODUCES 0.5 INCHES OF RAIN OR MORE DURING A 24-HOUR PERIOD.
 - ACCUMULATED SEDIMENT SHALL BE REMOVED WHEN IT REACHES ONE HALF THE HEIGHT OF THE TEMPORARY SWALE. PROPERLY DISPOSE OF SEDIMENT.
- MAINTAIN TEMPORARY SWALES UNTIL THE AREA IS STABILIZED.
- TEMPORARY CONVEYANCES SHOULD BE COMPLETELY REMOVED OR CONVERTED TO PERMANENT CONVEYANCES AS SOON AS THE SURROUNDING DRAINAGE AREA HAS BEEN STABILIZED OR AT THE COMPLETION OF

CHECK DAMS

- CHECK DAMS SHALL, AT A MINIMUM, BE INSPECTED WEEKLY AND WITHIN 24 HOURS AFTER EVERY PRECIPITATION EVENT THAT PRODUCES 0.5 INCHES OF RAIN OR MORE DURING A 24 HOUR PERIOD
- REPLACE OR REPAIR CHECK DAMS WITHIN 24 HOURS OF OBSERVED FAILURE (E.G., MOVED STONE, ERODED SOIL AROUND OR UNDER THE CHECK DAM, TRAPPED SEDIMENTS OVERTOPPING CHECK DAM)
- UNLESS INCORPORATED INTO A PERMANENT STORMWATER MANAGEMENT SYSTEM, CHECK DAMS SHALL BE REMOVED ONCE THE FINAL GRADING AND CHANNEL STABILIZATION IS APPLIED.
- SEDIMENT DEPOSITS SHALL BE REMOVED WHEN DEPOSITS REACH HALF THE HEIGHT OF THE CHECK DAM. REMOVAL OF SEDIMENT MAY REQUIRE REPLACEMENT OF STONE. PROPERLY DISPOSE OF SEDIMENT.

ROCK OUTLET PROTECTION

- ROCK OUTLET PROTECTION SHALL, AT A MINIMUM, BE INSPECTED WEEKLY AND WITHIN 24 HOURS AFTER EVERY PRECIPITATION EVENT THAT PRODUCES 0.5 INCHES OF RAIN OR MORE DURING A 24 HOUR PERIOD.
- REPAIR ROCK OUTLET PROTECTION WITHIN 24 HOURS IF DISLODGED STONES; ERODED SOIL AROUND OR UNDER THE RIPRAP OR UNDERLYING FABRIC; OR TREE GROWTH IS OBSERVED.

SEDIMENTATION BASIN

- SEDIMENTATION BASINS SHALL, AT A MINIMUM, BE INSPECTED WEEKLY AND WITHIN 24 HOURS AFTER EVERY PRECIPITATION EVENT THAT PRODUCES 0.5 INCHES OF RAIN OR MORE DURING A 24-HOUR PERIOD.
- REMOVE SEDIMENT DEPOSITS WHEN SEDIMENT ACCUMULATION REACHES ONE HALF OF THE WET STORAGE CAPACITY OF THE BASIN OR WHEN THE DEPTH OF THE AVAILABLE POOL IS REDUCED TO 18 INCHES, WHICHEVER IS ACHIEVED FIRST.
- C. IF THE OUTLET BECOMES CLOGGED, IT SHALL BE CLEANED TO RESTORE FLOW CAPACITY.
- DISPOSE OF SEDIMENT WITHIN THE NEW SOLID WASTE BOUNDARY OR OFF-SITE IN ACCORDANCE WITH LOCAL, STATE, AND FEDERAL REGULATIONS.

- AREAS RECEIVING TEMPORARY SEEDING AND MULCHING SHALL, AT A MINIMUM, BE INSPECTED WEEKLY AND WITHIN 24 HOURS AFTER EVERY PRECIPITATION EVENT THAT PRODUCES 0.5 INCHES OF RAIN OR MORE DURING
- WHERE SEED/MULCH HAS MOVED OR SOIL EROSION HAS OCCURRED, REPAIR THE AREA APPROPRIATELY AND RE-APPLY SEED AND/OR MULCH. APPLY NETTING, TACKIFIER, OR OTHER ANCHORING TECHNIQUES AS NECESSARY TO PREVENT FAILURE. ADDITIONAL TEMPORARY MEASURES MAY ALSO BE INSTALLED TO CONTROL STORMWATER RUNOFF AND SEDIMENT MOVEMENT.
- CONTINUE INSPECTION AND MAINTENANCE OF AREAS RECEIVING TEMPORARY SEEDING AND MULCHING UNTIL AT LEAST 90% OF THE SOIL SURFACE IS BE COVERED BY MATURE, ESTABLISHED VEGETATION CAPABLE OF CONTROLLING SOIL EROSION AND SURVIVING SEVERE WEATHER.

DUST CONTROL

- A. AREAS THAT HAVE DUST CONTROL PRACTICES SHALL, AT A MINIMUM, BE INSPECTED DAILY.
- REPEAT APPLICATION OF DUST CONTROL MEASURES WHEN FUGITIVE DUST BECOMES EVIDENT.

GENERAL CONSTRUCTION SEQUENCE:

- 1. INSTALL STABILIZED CONSTRUCTION ENTRANCE AND TEMPORARY FACILITIES AND CONTROLS
- 2. INSTALL PERIMETER EROSION AND SEDIMENT CONTROLS INCLUDING SILTATION FENCE, AUGMENTED SILTATION FENCE,
- 3. REMOVE STOCKPILED BULKY WASTES FOR OFF-SITE DISPOSAL
- 4. CLEAR AND GRUB ALL AREAS BETWEEN THE EXISTING AND NEW SOLID WASTE BOUNDARIES, BETWEEN THE OUTERMOST WASTE BOUNDARY AND THE LIMIT OF GRADING. AND WITHIN THE LIMITS OF THE DESIGNATED GRUBBING DISPOSAL AREAS. DISPOSE OF GRUBBINGS WITHIN THE NEW SOLID WASTE BOUNDARY IN THE DESIGNATED
- 5. REALIGN AND IMPROVE THE EXISTING EAST DRAINAGE SWALE ALONG THE EAST PROPERTY BOUNDARY TO CONVEY STORMWATER RUN-ON THROUGH AND BEYOND THE SITE. THIS ACTIVITY MAY COINCIDE WITH ITEM 6.
- 6. EXCAVATE ON-SITE WASTE OUTSIDE THE NEW SOLID WASTE BOUNDARY AND CONSOLIDATE WITHIN THE NEW SOLID
- 7. ABANDON EXISTING GROUNDWATER MONITORING WELLS.
- 8. INSTALL ADDITIONAL EROSION AND SEDIMENTATION CONTROLS AND MEASURES ADJACENT TO THE NEW SOLID WASTE
- GRADE LANDFILL TO THE REQUIRED SUBGRADE. CUT AND FILL WASTE, EXISTING COVER SOILS, WASTE SOILS, AND GRUBBING WITHIN THE NEW SOLID WASTE BOUNDARY, AS REQUIRED, TO ACHIEVE SUBGRADE. LANDFILL STORMWATER CONTROLS (SLOPE BENCHES AND DOWNDRAIN) WILL BE EXCAVATED AND SHAPED AS SUBGRADE IS
- 10. INSTALL LANDFILL COVER SYSTEM INCLUDING ASSOCIATED LANDFILL STORMWATER CONTROLS (SLOPE BENCHES AND DOWNDRAIN).
- 12. STABILIZE LANDFILL WITH SEED AND EROSION CONTROL MATTING, OR RIPRAP, AS REQUIRED.
- 13. INSTALL PERIMETER ACCESS ROAD WITH WATERBARS.
- 14. INSTALL PERIMETER STORMWATER CONTROLS INCLUDING RIRAP DRAINAGE CHANNELS, EAST DRAINAGE SWALE, AND
- 15. INSTALL FINAL GRADE OF ACCESS ROAD.
- 16. CLEAN SEDIMENT BASIN AND OUTLET STRUCTURE OF ACCUMULATED SEDIMENT: REPAIR AS REQUIRED: AND CONVERT
- 17. INSTALL NEW GROUNDWATER MONITORING WELLS.
- 19. REMOVE TEMPORARY EROSION AND SEDIMENT CONTROLS DOWNGRADIENT OF STABILIZED AREAS

New York State							
Department of Environmental Conservation							
DEMEDIAL ACTION							
SOLITH HILL DIMP SITE							
SOLITH HILL BOAD	0	0 03/04/11		ISSNE	ISSUED FOR BID		P
CORTI ANDVILLE NEW YORK	Š	NO. DATE		RE	REVISION		á
EC SITE NO 243000 CONTENCT NO DO02003	DSGN			DR	CHK	APVD	
EC SITE NO. / IZUUS, CONTRACT NO. DUU/ 882		J.P. McCRADY	RADY	M.R. STACEY	S.H. MITCHELL	M.J. STE	ST
AWMENG IS THE PROPERTY OF MACTEC, INCLUDING ALL PATENTED AND PATENDABLE REATURES, ANDOOR CONFIDENTIAL INFORMATION AND ITSUSE IS CONDITIONABLE TO THE WAY THE WAY SHOWN SHOWN TO AND	- PATEN	TED AND PA	TENTABLE	FEATURES, AND/OR CONF	IDENTIAL INFORMATION AND	O ITS USE IS CO	ION C

gineering ar 7050, 511 and, Maine (207) 775 SEDIMEN NOTES AND ROL ROSION /

MACTE VERIFY SCALE BAR IS ONE INCH ON ORIGINAL DRAWING

03/04/20 DATE PROJ 3612-09-2133 DWG C-30 HEET


- BOUNDARY INCLUDING TEMPORARY PERIMETER DIKE/SWALES, TEMPORARY SWALES, STONE CHECK DAMS, HAYBALES, A SEDIMENTATION BASIN WITH OUTLET STRUCTURE, AND TEMPORARY ROCK OUTLET PROTECTION.


- 18. INSTALL TOPSOIL, SEED, AND MULCH/EROSION CONTROL MATTING IN ALL AREAS WITHIN THE LIMIT OF GRADING. SEED AND MULCH ALL VEGETATED AREAS DISTURBED WITHIN THE LIMIT OF WORK.


21. MAINTAIN VEGETATED AREAS IN ACCORDANCE WITH SECTION VIII. ARTICLE 12.1 OF THE CONTRACT DOCUMENTS.


- 20. INSTALL PERMANENT SITE CONTROLS INCLUDING CHAIN LINK FENCE/GATE AND PERIMETER SIGNAGE.

II F NAME: M:\Projects\nvsdec1\SQUTH.HILL DUMP\RD-C-301.dwg PLOT.DATE: Mon. 07.Mar.2011 PLOT.TIME: 11:45.AN










CULVERT SCHEDULE									
CULVERT						OUTLET PROTECTION APRON			
ID	PIPE DIAMETER	INVERT IN	INVERT OUT	LENGTH	D50	APRON LENGTH (L)	START WIDTH (W1)	END WIDTH (W2)	DEPTH (D)
	INCHES	FEET	FEET	FEET	INCHES	FEET (MIN)	FEET (MIN)	FEET (MIN)	INCHES (MIN)
FINAL									
C-1	24	1565.0	1557.0	51	8	15	6	21	18
C-2	12	1551.0	1548.0	58	8	BLEND WITH EDS	3	BLEND WITH EDS	18
C-3	12	1578.0	1577.0	39	8	_	_	_	18
TEMPORARY									
C-2	12	1551.0	1548.0	58	8	20	3	15	18

NOTES:

- NONWOVEN GEOTEXTILE SHALL BE INSTALLED BENEATH THE RIPRAP AND AT ALL SOIL/RIPRAP INTERFACES. MINIMUM D50 OF 6 INCHES SINGLE CULVERT APRON START WIDTH = 3 x PIPE DIAMETER

- END WIDTH = START WIDTH + LENGTH RIPRAP DEPTH = 2.25 x D50
- CLEARING AND GRUBBING SHALL OCCUR AT ROCK OUTLET PROTECTION TO A MINIMUM DISTANCE OF 5' BEYOND THE APRON INSTALLATION.
- ALL DISTURBED AREAS BEYOND THE APRON INSTALLATION SHALL BE SEEDED AND MULCHED.




ROCK OUTLET PROTECTION

RIPRAP DRAINAGE CHANNEL (TYP) C-106 C-305 NTS


-18" D50=8" RIPRAP


THIS DETAIL APPLIES TO LOCATIONS OF THE RIPRAP DRAINAGE CHANNEL NOT DIRECTLY ADJACENT TO THE PERIMETER ACCESS ROAD, SEE DETAIL M, SHEET 304 FOR AREAS ADJACENT TO THE PERIMETER




NOTE:

- 1. PERFORATED AND SOLID HDPE PIPE TO BE SDR 17.
- 2. PROVIDE 6" MIN OF SAND AS FILTER BETWEEN BENTONITE AND CRUSHED STONE.







DESCRIPTION END, CORNER AND PULL POSTS FOR FABRIC HEIGHT: ROUND SQUARE 2.375"ø 2.0" 3.65#/FT. 3.60#/FT.

INTERMEDIATE POSTS FOR FABRIC HEIGHTS: ROUND 1.90" 2.72#/F1. H-SECTION 1.875"x 1.625"x 0.113" 2.70#/FT.

BRACE TUBES: 1.66"O.D. NOMIMAL, 1.806#/FT. GALVANIZED STEEL PIPE

STRETCHER BARS: LENGTH TO BE 1" LESS THAN FULL HEIGHT OF FABRIC.
ONE STRETCHER BAR FOR EACH GATE AND END POST.
TWO STRETCHER BARS FOR CORNERS AND BRACING.

TOP RAIL: 1.66"O.D. NOMIMAL, 1.806#/FT. GALVANIZED STEEL PIPE

TENSION WIRE: 7 GAUGE GALVANIZED

NOTES:

1. POST DIMENSIONS SHOWN ARE O.D. NOMINAL.

FOOTING DETAIL

LINE,GATE AND END POST BASE "A" 4'-0" FOR FENCE 8' HIGH

POSTS PER FO-3

6'-0" FOR ALL END, CORNER, PULL, AND GATE

SELECT

CONCRETE

2. 4-6 FENCE POSTS MAY REQUIRE INSTALLATION

CHAIN LINK FENCE C-107 C-305 NTS



VERIFY SCALE

BAR IS ONE INCH ON ORIGINAL DRAWING

PROJ 3612-09-2133

03/04/201

C-30

DATE

DWG

SHEET

GEOTEXTILE

