

New York State Department of Environmental Conservation
Division of Environmental Remediation
Bureau of Hazardous Site Control

ADDITIONS/CHANGES TO REGISTRY: SUMMARY OF APPROVALS

SITE NAME: SPEEDY'S CLEANERS

DEC I.D. NUMBER 828109

Current Classification 2A

Volunteer Yes _____ No _____
Sign (7) below

Activity:

☐

Add as
Class _____

☒

Reclassify
to 2

☐

Delist
Category _____

☐

Modify _____

Approvals:

1. Regional Hazardous Waste Engineer

Yes

☒

No

☐

3/20/03

2. BEEI of NYSDOH

Yes

☒

No

☐

3/11/03

3. DEE

Yes

☒

No

☐

2/20/03

4. WISCONSIN Remediation Action
Bureau Director [Class 2]

Yes

☒

No

☐

3/20/03

5. BHSC - Investigation Section

Yes

☒

No

☐

2/7/03

6. BHSC - O&M Section - [Class 4]

Yes

☐

No

☐

N/A

7. BPM - Brownfield & Voluntary Cleanup Section

Date _____

8. Site Control Section

Don J. F...

Date 4/16/03

9. Director

Robert J. M...

Date 4/22/03

Completion Checklist for Registry Sites

Completed By:
Initials

Date

OWNER NOTIFICATION LETTER?

☐

ADJACENT PROPERTY OWNER NOTIFICATION LETTER?

☐

ENB / LEGAL NOTICE SENT? (For Deletion Only)

☐

COMMENTS SUMMARIZED / PLACE IN REPOSITORY?

☐

FINAL NOTIFICATION SENT TO OWNER? (For Deletion Only)

☐



SITE INVESTIGATION INFORMATION

1. SITE NAME SPEEDY'S CLEANERS		2. SITE NUMBER 8-28-109	3. TOWN/CITY/VILLAGE PITTSFORD, NY	4. COUNTY MONROE COUNTY																																																																																
5. REGION 8	6. CLASSIFICATION CURRENT [2a] PROPOSED [2] MODIFICATION																																																																																			
7. LOCATION OF SITE (Attach U.S.G.S. Topographic Map showing site location) a. Quadrangle UGS 7.5 Minute Quad Pittsford b. Site Latitude 43° 06' 24" Site Longitude 77° 32' 33" c. Tax Map Number(s) 150.120-01-006 and 150.120-01-35.1 d. Site Street Address 3130 Monroe Avenue																																																																																				
8. BRIEFLY DESCRIBE THE SITE (Attach site map showing disposal/sampling locations) The site is located in a commercial area of the Town of Pittsford. The Site includes the Speedy's Cleaners property and the Rochester Gas and Electric Company (RG&E) property. The Speedy's Cleaners property is situated on 0.27 acres and consists of a small paved lot and a 4900 square foot building housing Speedy's Cleaners and Cliffords Wine and Liquor. The RG&E property consists of a level grassy area that drops off sharply to the north. Speedy's Cleaners operated as a dry cleaner from approximately 1966 until approximately 1993. Speedy's Cleaners is currently used as a drop-off and pick up-location only and no dry cleaning is conducted on the premises. Tetrachloroethene (PCE) has been detected in Site soils and groundwater. a. Area 0.38 acres b. Completed: <input type="checkbox"/> Env. Property Assessment <input checked="" type="checkbox"/> PSA <input type="checkbox"/> SI <input type="checkbox"/> ESI <input type="checkbox"/> IRM <input type="checkbox"/> RI/FS <input type="checkbox"/> Construction <input type="checkbox"/> O&M <input type="checkbox"/> Other.																																																																																				
9. HAZARDOUS WASTE DISPOSED (Include EPA Hazardous Waste Numbers) Tetrachloroethene (CAS # 127-18-4) EPA Waste # F002, D039 Trichloroethylene D040 (Breakdown product of tetrachloroethylene) Vinyl Chloride D043 (Breakdown product of tetrachloroethylene)																																																																																				
10. ANALYTICAL DATA AVAILABLE a. <input type="checkbox"/> Air <input checked="" type="checkbox"/> Groundwater <input type="checkbox"/> Surface Water <input type="checkbox"/> Sediment <input checked="" type="checkbox"/> Soil <input type="checkbox"/> Waste <input type="checkbox"/> Leachate <input type="checkbox"/> EPTox <input type="checkbox"/> TCLP b. Contravention of Standards or Guidance Values <table border="1" style="width:100%; border-collapse: collapse;"><thead><tr><th>Contaminant</th><th>Media</th><th>Concentration</th><th>NYS Groundwater Standard</th><th>Contaminant</th><th>Media</th><th>Concentration</th><th>NYSDEC Soil Cleanup Objective</th></tr></thead><tbody><tr><td>PCE</td><td>groundwater</td><td>5,900 ppb</td><td>5 ppb</td><td>PCE</td><td>soil</td><td>110,000 ppb</td><td>1,400 ppb</td></tr><tr><td>trichloroethene (TCE)</td><td>groundwater</td><td>580 ppb</td><td>5 ppb</td><td>TCE</td><td>soil</td><td>4,200 ppb</td><td>300 ppb</td></tr><tr><td>cis-1,2-dichloroethene (DCE)</td><td>groundwater</td><td>64,000 ppb</td><td>5 ppb</td><td></td><td></td><td></td><td></td></tr><tr><td>trans 1,2-DCE</td><td>groundwater</td><td>580 ppb</td><td>5 ppb</td><td></td><td></td><td></td><td></td></tr><tr><td>1,1-DCE</td><td>groundwater</td><td>80 ppb</td><td>5 ppb</td><td></td><td></td><td></td><td></td></tr><tr><td>vinyl chloride</td><td>groundwater</td><td>9,200 ppb</td><td>2 ppb</td><td></td><td></td><td></td><td></td></tr><tr><td>ethylbenzene</td><td>groundwater</td><td>250 ppb</td><td>5 ppb</td><td></td><td></td><td></td><td></td></tr><tr><td>xylene (total)</td><td>groundwater</td><td>310 ppb</td><td>5 ppb</td><td></td><td></td><td></td><td></td></tr><tr><td>chloromethane</td><td>groundwater</td><td>22 ppb</td><td>5 ppb</td><td></td><td></td><td></td><td></td></tr></tbody></table>					Contaminant	Media	Concentration	NYS Groundwater Standard	Contaminant	Media	Concentration	NYSDEC Soil Cleanup Objective	PCE	groundwater	5,900 ppb	5 ppb	PCE	soil	110,000 ppb	1,400 ppb	trichloroethene (TCE)	groundwater	580 ppb	5 ppb	TCE	soil	4,200 ppb	300 ppb	cis-1,2-dichloroethene (DCE)	groundwater	64,000 ppb	5 ppb					trans 1,2-DCE	groundwater	580 ppb	5 ppb					1,1-DCE	groundwater	80 ppb	5 ppb					vinyl chloride	groundwater	9,200 ppb	2 ppb					ethylbenzene	groundwater	250 ppb	5 ppb					xylene (total)	groundwater	310 ppb	5 ppb					chloromethane	groundwater	22 ppb	5 ppb				
Contaminant	Media	Concentration	NYS Groundwater Standard	Contaminant	Media	Concentration	NYSDEC Soil Cleanup Objective																																																																													
PCE	groundwater	5,900 ppb	5 ppb	PCE	soil	110,000 ppb	1,400 ppb																																																																													
trichloroethene (TCE)	groundwater	580 ppb	5 ppb	TCE	soil	4,200 ppb	300 ppb																																																																													
cis-1,2-dichloroethene (DCE)	groundwater	64,000 ppb	5 ppb																																																																																	
trans 1,2-DCE	groundwater	580 ppb	5 ppb																																																																																	
1,1-DCE	groundwater	80 ppb	5 ppb																																																																																	
vinyl chloride	groundwater	9,200 ppb	2 ppb																																																																																	
ethylbenzene	groundwater	250 ppb	5 ppb																																																																																	
xylene (total)	groundwater	310 ppb	5 ppb																																																																																	
chloromethane	groundwater	22 ppb	5 ppb																																																																																	
11. CONCLUSION Concentrations of contaminants detected in groundwater and soil samples collected at the Site exceed NYS Class GA groundwater standards and the NYSDEC Soil Cleanup Objectives. Concentrations of chlorinated solvents were detected in groundwater samples collected downgradient of the Site, at concentrations above the NYS Class GA groundwater standards. Contaminants originating from the Site soils are migrating off-site in groundwater. Tetrachloroethene, Trichloroethylene and Vinyl Chloride contaminant concentrations in groundwater exceed the maximum regulatory level for Toxicity Characteristic thus making the subsurface soils at the site hazardous waste. a. Institutional Controls (IC) Required? <input type="checkbox"/> Y <input checked="" type="checkbox"/> N b. If yes, identify _____ () N c. Are these ICs in place and verified? <input checked="" type="checkbox"/> NO																																																																																				
12. SITE IMPACT DATA a. Nearest Surface Water: Distance 100 ft. Direction northeast Class AA/B b. Groundwater: Depth 12 ft. Flow Direction northeast <input type="checkbox"/> Sole Source <input checked="" type="checkbox"/> Primary <input type="checkbox"/> Other High-Yield Aquifer c. Water Supply: Distance 3800 ft. Direction southeast Active <input type="checkbox"/> Yes <input type="checkbox"/> No d. Nearest Building: Distance on site ft. Direction on - site Use Business: dry cleaner pick up / liquor store e. Documented fish or wildlife mortality? <input type="checkbox"/> NO f. Impact on special status fish or wildlife resource? <input type="checkbox"/> NO g. Controlled Site Access? <input type="checkbox"/> NO h. Exposed hazardous waste? <input type="checkbox"/> NO i. If proposed Classification is 2, Priority? <input type="checkbox"/> 1 <input checked="" type="checkbox"/> 2 <input type="checkbox"/> 3 j. EPA ID# NYD981558315 HRS Score																																																																																				
13. SITE OWNER'S NAME Chris Williams / Rochester Gas & Electric		14. ADDRESS P.O. Box 499 Pittsford, NY 14618-Williams 89 East Avenue, Rochester, NY 14604- RG&E		15. TELEPHONE NUMBER (585) 586-3060																																																																																
16. PREPARER Signature Date 2/3/2003 A. Joseph White, Environmental Engineer II, DER, BHSC Name, Title, Organization		17. APPROVED Signature Date 4/22/03 Robert L. Marino Director BTS Name, Title, Organization																																																																																		



STATE OF NEW YORK DEPARTMENT OF HEALTH


Flanigan Square, 547 River Street, Troy, New York 12180-2216

Antonia C. Novello, M.D., M.P.H., Dr.P.H.
Commissioner

Dennis P. Whalen
Executive Deputy Commissioner

March 6, 2003

Mr. Dennis Farrar, Chief
Site Control Section
Bureau of Hazardous Site Control
Division of Environmental Remediation
NYS Dept. of Environmental Conservation
625 Broadway, 11th Floor
Albany, New York 12233-7015



Re: Classification Package
Speedy's Cleaners Site
Site #828109
Pittsford (T), Monroe County

Staff reviewed the Classification Package for the Speedy's Cleaners site, located in Pittsford, Monroe County. I understand that during an underground fuel oil tank removal in 1999, subsurface investigations detected volatile organic compounds in site soils, including tetrachloroethene (PCE) as high as 748 milligrams per kilogram. In September 2002, additional site investigation revealed substantial on- and off-site subsurface soil contamination of PCE and trichloroethene (TCE).

I also understand that recently collected groundwater data indicate significant levels of volatile organic compounds (including PCE, TCE, cis-1,2-dichloroethene and vinyl chloride) in both on- and off-site groundwater. Two active commercial facilities currently occupy the site and the potential exists for human exposure to elevated levels of site-related contaminants. With this information, I concur with the proposal to list this site on the NYS Registry of Inactive Hazardous Waste Disposal Sites as a class 2. The signed decision form is enclosed.

If you have any questions, please contact Mark VanValkenburg of my staff at (518) 402-7860.

Sincerely,

Gary A Litwin, Director
Bureau of Environmental Exposure Investigation

Enclosure

cc: G. A. Carlson, Ph.D.
Mr. M. VanValkenburg/Mr. J. Crua/file
Mr. J. Albert, MCHD
Mr. E. Belmore, DEC
Mr. B. Putzig, DEC Region 8

P:\Bureau\Sites\Region_8\MONROE\828109\classification.doc



Erin M. Crotty
Commissioner

MEMORANDUM

TO: Investigation Section & O&M
E. Belmore Remedial Bureau (Cl.2 only)
B. Putzig Regional Hazardous Waste Remediation Engineer
G. Rider, O&M Section (as needed)
A. Grant, DEE
G. Litwin, DOH, Bureau of Environmental Exposure Investigation

FROM: Dennis Farrar, Chief, Site Control Section, BHSC, DER

SUBJECT: Review of Classification Package for Site # 828109
Speedy's Cleaners

DATE: February 11, 2003

The attached new "Registry Site Investigation Information Form" with supporting documentation is attached for your review and approval.

If acceptable, sign at the bottom of the form (Box #17) and return within 30 calendar days.

If unacceptable, please return with an explanation of your position in a separate memo or letter.

An important part of your review should include modifying, if necessary, the statement in Block 11 (Conclusion) for Classification Decision of the Investigation Form so that it can be used in all appropriate notification documentation (i.e., ENB, owner and adjacent property owner notification letter, and newspaper legal notice.

Please keep the supporting documentation for your records.

Attachment(s)

**NEW YORK STATE DEPARTMENTS OF ENVIRONMENTAL CONSERVATION AND HEALTH
INACTIVE HAZARDOUS WASTE DISPOSAL SITE PRIORITY RANKING WORKSHEET**

SITE I.D. 8-28-109

SITE NAME SPEEDY'S CLEANERS

- ° **Priority I** - Sites for which remediation should supersede all other Class 2 sites. Priority I can be assigned if any one of the following questions can be answered affirmatively.

a) Has a public or private water supply which is currently in use been contaminated or threatened?.....	<input type="checkbox"/>	<input type="checkbox"/> (1) [If 1 or more boxes are checked, check this box]
b) Has human exposure to contaminants (or the potential for exposure) been identified which represents a significant health risk as determined by DOH?.....	<input type="checkbox"/>	
c) Has bioaccumulation of site contaminants in flora or fauna resulted in a health advisory?.....	<input type="checkbox"/>	
d) Are site contaminants present at levels that are acutely toxic to fish or wildlife or that have caused documented fish or more wildlife mortality?.....	<input type="checkbox"/>	
e) Is there a potentially responsible party or volunteer ready, willing and able to proceed with remediation?.....	<input type="checkbox"/>	

- ° **Priority II** - Important Sites. Priority II will be assigned if any of the following questions can be answered affirmatively.

a) Has a Class A or AA surface water body, a primary aquifer or other high yielding aquifer been contaminated or threatened without affecting an existing water supply which draws from it?.....	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/> (2) [If 1 or more boxes are checked, check this box]
b) Has bioaccumulation of site contaminants in flora or fauna resulted in actionable levels (but not a health advisory)?.....	<input type="checkbox"/>	
c) Are contaminants at levels chronically toxic to fish/wildlife?.....	<input type="checkbox"/>	
d) Have endangered, threatened or rare species, significant habitats, designated coastal zone or regulated wetlands been impacted by releases from the site?.....	<input type="checkbox"/>	

- ° **Priority III** - will be assigned unless one or more of the site prioritization criteria, specified above, apply to a site. After remedial needs for Priority I and II sites have been accommodated, remediation of sites under this category can be considered. If priority III, check box 3.

☐ (3)

Enter the number of the priority box checked 1, 2, or 3 here.....
This is the site's priority rank.

(4)

FACTORS

IJC Factor - If the site has been identified by the International Joint Commission (IJC) as a component in a remedial action plan, subtract (1) from the value in box 4 and enter the result in box 5.....

☐ (5)

Yes No

EDZ Factor - If the site is within a New York State designated Economic Development Zone (EDZ) should this fact cause the site priority to be raised?..

☐ ☒

Community Support Factor - If the site has been targeted for local government-supported development, should this fact cause the site priority to be raised?.....

Yes No
☐ ☐

If either "yes" box is checked, subtract 1 from the value in box 4 and enter the result into box 6. If "no" is checked, the value in box 6 equals box 4 (or box 5 if applicable). If both IJC and EDZ/Community Support factors apply, only 1 (not 2) will be subtracted from the value in box 4. The resultant value in box 6 will never be less than 1.....

(6)

Yes No

IRM NOTE: Should this site be considered a candidate for an Interim Remedial Measure (IRM) as defined by 6NYCRR Part 375-1.3n?.....

☐ ☒

If "yes", please explain why:

Preparer A. Joseph White, Environmental Engineer II, DER, BHSC

Date 2/3/2003

NEW YORK STATE DEPARTMENT OF ENVIRONMENTAL CONSERVATION
Division of Environmental Remediation

Inactive Hazardous Waste Disposal Report

Site Name: SPEEDY'S CLEANERS		Site Code: 8-28-109	
Class Code: 2	Region: 8	County: MONROE	EPA Id: NYD981558315
Address: 3130 Monroe Avenue		City: PITTSFORD	Zip: 14618
Latitude: 43 06' 24"	Longitude: 77 32' 33"		
Site Type: commercial area		Estimated Size: 0.38	Acres

Site Owner / Operator Information:	
Current Owner(s) Name: Chris Williams / Rochester Gas & Electric	NY
Current Owner(s) Address: P.O. Box 499, Pittsford, NY 14618	
Owner(s) during disposal: Charles Speedy, Demosthenes Speedy, D&L Realty	
Operator(s) during disposal:	
Stated Operator(s) Address:	
Hazardous Waste Disposal Period: From 1966 To 1993	

Site Description:

The site is located in a commercial area of the Town of Pittsford. The Site includes the Speedy's Cleaners property and the Rochester Gas and Electric Company (RG&E) property. The Speedy's Cleaners property is situated on 0.27 acres and consists of a small paved lot and a 4900 square foot building housing Speedy's Cleaners and Cliffords Wine and Liquor. The RG&E property consists of a level grassy area that drops off sharply to the north. Speedy's Cleaners operated as a dry cleaner from approximately 1966 until approximately 1993. Speedy's Cleaners is currently used as a drop-off and pick up-location only and no dry cleaning is conducted on the premises. Tetrachloroethene (PCE) has been detected in Site soils and groundwater.

Confirmed Hazardous Waste Disposal:

Tetrachloroethene
Trichloroethylene
Vinyl Chloride

Quantity:

5,900 ppb in groundwater
580 ppb in groundwater
9,200 ppb in groundwater

Analytical Data Available for: groundwater and soil	
Applicable Standards Exceeded in: groundwater	
Geotechnical Info lacustrine silts, sands & clays over glacial till	Depth to
Soil/Rock Type: Redrock- Vernon Shale	Groundwater: 12 ft.

Legal Action: Type: none	Status:
Remedial Action: PSA Investigation	Nature of action: Investigation

Assessment of Environmental Problems:

Concentrations of contaminants detected in groundwater and soil samples collected at the Site exceed NYS Class GA groundwater standards and the NYSDEC Soil Cleanup Objectives. Concentrations of chlorinated solvents were detected in groundwater samples collected downgradient of the Site, at concentrations above the NYS Class GA groundwater standards. Contaminants originating from the Site soils are migrating off-site in groundwater. Tetrachloroethene, Trichloroethylene and Vinyl Chloride contaminant concentrations in groundwater exceed the maximum regulatory level for Toxicity Characteristic thus making the subsurface soils at the site hazardous waste.

Assessment of Health Problems:

SECTION 4

4.2 SOIL AND GROUNDWATER ANALYTICAL RESULTS

Soil and groundwater analytical results are compared to appropriate standards or guidelines. Reported concentrations of individual analytes indicating contravention of standards or guidelines are summarized below, and noted on Tables 4-1 and 4-2. The tables were assembled after the on-site and off-site analytical laboratory data comparison was completed and present only contaminants detected above the project quantitative limits. The tables present both on-site and off-site analytical laboratory data.

A Data Usability Summary Report was completed in accordance with the NYSDEC's Guidance for the Development of Data Usability Summary Reports (NYSDEC, 1997). This report and complete analytical results are presented in Appendix G.

For purposes of analytical interpretation, some of the data was qualified with a J. Compounds were qualified J if the concentration listed was an estimated value, which was less than the specified minimum detection limit but greater than zero. Compounds qualified J were analyzed for and determined to be present in the sample, and the mass spectrum of the compound met the identification criteria of the method.

Analytical results were compared to the standards or guidelines described below.

Soil Samples. Analytical results were compared to the Recommended Soil Cleanup Objectives in the NYSDEC TAGM No. 94-4046 (NYSDEC, 1994).

Groundwater Samples. Analytical results were compared to: (1) the NYS Class GA Groundwater Quality Standards from 6 NYCRR Parts 700-706 (NYS, 1999b) or, for those VOCs having no Class GA standard, (2) the NYS Class GA Groundwater Quality Guidance Values from the Division of Water Technical and Operational Guidance Series 1.1.1 "Ambient Water Quality Standards and Guidance Values" (NYSDEC, 1998).

4.2.1 Data Comparability

This section presents a comparison between VOC analytical results from the on-site and off-site laboratories. A more detailed discussion of split-sample results is presented in Appendix G.

4.2.1.1 Soil Sample Comparability. Of the 11 soil samples collected for on-site VOC analysis, one split sample from BS-7 was sent to the off-site analytical laboratory for confirmatory analysis. The split sample results showed agreement for the absence of contamination at the project reporting limits.

Harding Lawson Associates

4.2.1.2 Groundwater Sample Comparability. Of the 13 samples collected for on-site VOC analysis, three split samples were sent to the off-site analytical laboratory for confirmatory analysis (from BW-1, BW-6, and BW-7). All samples showed good correlation with the detection of target compounds. The average relative percent difference of the detected analytes was 23 percent, indicating good quantitative agreement between the laboratories. Although high concentrations of target VOCs were detected in both the on-site and off-site analytical laboratory results, low concentrations of VOCs were detected in two of the off-site samples, but not in the corresponding on-site samples. These low concentration VOCs were detected at concentrations below the on-site analytical laboratory project quantitative limit. This is not considered significant, because high concentrations of target compounds were detected in the two off-site and on-site samples.

4.2.2 Soil Sample Results

A summary of target VOCs detected in soil samples is presented in Table 4-1. Table 4-1 presents hits only on-site and off-site analytical laboratory results.

PCE was detected in five samples from four borings (BS-4, BS-7, BS-8, and BS-9) at concentrations above the NYSDEC Soil Cleanup Objectives. Concentrations ranged from 4,200 $\mu\text{g/Kg}$ (BS-8) to 110,000 $\mu\text{g/Kg}$ (BS-9); the Soil Cleanup Objective for PCE is 1,400 $\mu\text{g/Kg}$. These borings are located north and east of the northern corner of the Site building. Relatively low concentrations of fuel related compounds were also detected in soil samples from two of the borings (BS-5 and BS-7).

To evaluate whether dense non-aqueous phase liquid (DNAPL) might be present in Site soil, linear partitioning calculations were performed with reasonable soil parameter estimates (Appendix H). Based on these calculations, DNAPL does not appear to be an important component of contaminant mass in the source area, considering the maximum reported concentration of 110,000 $\mu\text{g/Kg}$ in Site soil.

4.2.3 Groundwater Sample Results

A summary of target VOCs detected in groundwater samples is presented in Table 4-2 and on Figure 4-1. Table 4-2 presents hits only on-site and off-site analytical laboratory results.

PCE was detected in groundwater samples collected from eight of the 10 borings. Concentrations ranged from 3.9 $\mu\text{g/L}$ (BW-3) to 5900 $\mu\text{g/L}$ (BW-4). Concentrations in samples collected from seven of the borings (BW-4 through BW-10), exceeded the NYS Class GA groundwater standard of 5 $\mu\text{g/L}$ (Figure 4-1).

Concentrations of analytes other than PCE were detected at concentrations above the NYS Class GA groundwater standards in groundwater samples collected from seven of the ten borings. The highest concentrations detected for analytes other than PCE were detected in the sample from

SECTION 4

boring BW-9. Analytes detected in boring BW-9, and corresponding NYS Class GA Groundwater standards are listed below.

Location BW-9		
Parameter	Standard (µg/L)	Result (µg/L)
Tetrachloroethene	5	483
Trichloroethene	5	580
cis-1,2-Dichloroethene	5	64,000
trans-1,2-Dichloroethene	5	580
1,1-Dichloroethene	5	80
Vinyl chloride	2	9,200
Toluene	5	46
Ethylbenzene	5	250
m,p-Xylene	5	170
o-Xylene	5	140

Reported concentrations of analytes detected in groundwater samples collected west (PA-1), southwest (BW-2), and southeast (BW-1) of the Site building were less than the NYS Class GA groundwater standards. Vinyl chloride was the only analyte detected (2.4 µg/L) above the NYS Class GA groundwater standard (2 µg/L) in the sample collected from boring BW-3, located east of the Site building.

The highest concentrations of VOCs detected in shallow groundwater occur near the northern corner of the Site building. Contamination in groundwater appears to be migrating off the Site. Six of the analytes detected in the sample collected from boring BW-6, located on the Oak Hill Country Club property, exceeded the NYS Class GA groundwater standards. Results for this sample are listed below:

Location BW-6		
Parameter	Standard (µg/L)	Result (µg/L)
Tetrachloroethene	5	2400
Trichloroethene	5	350
cis-1,2-Dichloroethene	5	2700
trans-1,2-Dichloroethene	5	31
1,1-Dichloroethene	5	5
Vinyl chloride	2	1200

Considering the high concentrations of PCE degradation products (PCE ~~to~~ TCE ~~to~~ cis-1,2-dichloroethene [DCE] ~~to~~ vinyl chloride), it appears reductive de-chlorination of the PCE is actively occurring. The petroleum hydrocarbon plume from the fuel oil spill appears to have migrated into the chlorinated solvent plume. Anaerobic conditions resulting from degradation of hydrocarbons are most likely contributing to the reductive degradation, allowing breakdown of the chlorinated solvents. Because cis-1,2-DCE and vinyl chloride are less readily degraded

Harding Lawson Associates

under reducing conditions, net concentrations of these two compounds have apparently increased in the aquifer. As more oxygen becomes available in groundwater further downgradient of the Site, it is expected that these compounds would more rapidly degrade.


Due to the high turbidity of the groundwater samples, analytical results may include concentrations of solvents sorbed to the soil matrix, and may not give an absolute quantification of dissolved constituents.

4.3 SURFACE WATER AND SEDIMENT SAMPLE RESULTS

No VOCs were detected in the three surface water or sediment samples collected. Surface water results are presented in Table 4-2; sediment sample results are presented in Table 4-3.

4.4 POTENTIOMETRIC SURFACE MAP

Well and pond survey and depth to water measurements from September 26, 2002 were used to create a potentiometric surface map (Figure 4-2). Microwell survey and water elevation data are presented in Table 4-3. To preclude introduction of possibly false high water levels caused by heavy rains during the evening of September 26 and day of September 27, groundwater measurements collected on September 27, 2002 were not used for contouring groundwater data. Measured groundwater elevations on September 26 varied from a high of 433.24 feet above msl southwest of the Site buildings, to a low of 427.13 feet above msl at the golf course pond. Interpreted groundwater surface contours indicate that groundwater flows to the northeast. Because MW-7 was located adjacent to the public sewer lines, groundwater levels in MW-2 may be artificially high due to the presence of localized drainage in the gravel trenches of the utility lines.



SW/SD-1 ▲ SURFACE WATER AND SEDIMENT SAMPLE LOCATION


SOURCE: USGS TOPOGRAPHIC QUADRANGLE - PITTSFORD, NY





0 500 1000
Scale in feet

FIGURE 3-2
SURFACE WATER AND SEDIMENT SAMPLE LOCATIONS
PRELIMINARY SITE ASSESSMENT REPORT
SPEEDY'S CLEANERS SITE
PITTSFORD, NEW YORK

Harding Lawson Associates









APPENDIX A


SITE PHOTOGRAPHS
SPEEDY'S CLEANERS SITE
PITTSFORD, NEW YORK



Looking south from small pond on Oak Hill Country Club fairway #13 to Site




APPENDIX A
SITE PHOTOGRAPHS
SPEEDY'S CLEANERS SITE
PITTSFORD, NEW YORK



Looking northeast across Monroe Avenue towards Site

APPENDIX A
SITE PHOTOGRAPHS
SPEEDY'S CLEANERS SITE
PITTSFORD, NEW YORK



View looking southwest at Site

Approximate property line location