





Contract Drawings For 100% REMEDIAL DESIGN FOR FORMER AIR FORCE PLANT NO. 51

NYSDEC SITE NO. 828156

GREECE, MONROE COUNTY, NEW YORK

INDEX OF DRAWINGS


GENERAL

- G-1 COVER
- G-2 GENERAL NOTES AND LEGEND
- CONSTRUCTION DETAILS
- D-2 EROSION CONTROL DETAILS
- D-3 STORM SEWER RESTORATION DETAILS

SITE WORK

- C-1 SITE PLAN
- C-2A EXISTING CONDITIONS (CATCH BASIN CB-1 & OUTFALL AREA)
 C-2B EXISTING CONDITIONS (FORMER SEPTIC SYSTEM/LEACHFIELD AREA)
- C-3A EXCAVATION PLAN CATCH BASIN CB-1 & OUTFALL AREA
- C-3B EXCAVATION PLAN FORMER SEPTIC SYSTEM/LEACHFIELD AREA
- C-4 CROSS SECTION VIEWS
- C-5 STAGING PLAN
- C-6 DEWATERING AND WATER TREATMENT PROCESS FLOW DIAGRAM
- C-7 NEW STORM SEWER SYSTEM PLAN
- C-8 NEW STORM SEWER UTILITY PROFILE
- C-9 GRADING PLAN
- C-10 RESTORATION PLAN

APRIL 2016



PERMITS BEFORE BEGINNING WORK.

- APPLICABLE FEDERAL, STATE, AND LOCAL CODES AND REGULATIONS.

 2. THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING ALL NECESSARY
- 3. SITE IS LOCATED AT 4777 DEWEY AVENUE, TOWN OF GREECE, MONROE COUNTY, NY. THE SITE IS A 33.6 ACRE PROPERTY. THE SITE NUMBER IS 828156.
- 4. THE ENTIRE PARCEL IS CURRENTLY OWNED BY 4800 DEWEY. NYSDEC WILL BE RESPONSIBLE FOR OBTAINING ALL ACCESS AGREEMENTS NECESSARY TO COMPLETE THE WORK SHOWN ON THE DRAWINGS AND SPECIFICATIONS.
- 5. ALL SITE FEATURES SHALL BE FIELD VERIFIED BY CONTRACTOR PRIOR TO CONSTRUCTION.
- 6. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO HAVE A GEOPHYSICAL SURVEY COMPLETED TO LOCATE ALL EXISTING ABOVEGROUND AND UNDERGROUND UTILITIES AND STRUCTURES WHETHER SHOWN ON THIS PLAN OR NOT, AND TO PROTECT THEM FROM DAMAGE. INACTIVE OR ABANDONED UTILITIES SHALL BE CAPPED IN ACCORDANCE WITH LOCAL CODES. REMOVE INACTIVE SERVICES AS REQUIRED TO MAINTAIN OPERATION. FOR ASSISTANCE IN LOCATING UNDERGROUND UTILITIES CALL UFPO AT 1-800-962-7962 OR 811.
- 7. IN THE EVENT THE CONTRACTOR DAMAGES ANY EXISTING UTILITY SERVICE CAUSING SERVICE INTERRUPTION, THE CONTRACTOR SHALL IMMEDIATELY NOTIFY NYSDEC OR THE ENGINEER. ANY DAMAGE TO UTILITIES WILL BE REPAIRED/REPLACED AT THE CONTRACTOR'S OWN EXPENSE.
- 8. THE CONTRACTOR SHALL TAKE CARE WHEN WORKING IN THE VICINITY OF OVERHEAD POWER LINES.
- 9. PROVISIONS SHALL BE MADE TO MINIMIZE THE SPREAD OF DEBRIS, DIRT, AND DUST.
- 10. PROVISIONS SHALL BE TAKEN TO MINIMIZE NOISE. CONSTRUCTION ACTIVITIES ARE NOT PERMITTED BETWEEN THE HOURS OF 10PM TO 7AM.
- 11. THE CONTRACTOR IS RESPONSIBLE FOR ENSURING UNAUTHORIZED PERSONS DO NOT ENTER THE EXCLUSION ZONE. SNOW FENCE OR OTHER ACCEPTABLE MEANS SHALL BE PROVIDED AROUND THE HAZARDOUS WORK ZONE TO RESTRICT ACCESS. WARNING SIGNS SHALL BE POSTED AS REQUIRED BY SPECIFICATION SECTION 02073 SPEC 00003 SOIL EXCAVATION, DEMOLITION AND REMOVAL.
- 12. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE SECURITY OF THE SITE. ANY REPAIRS RESULTING FROM DAMAGE CAUSED BY TRESPASSERS SHALL BE AT THE EXPENSE OF THE CONTRACTOR. MINIMUM SECURITY MEASURES SHALL BE AS REQUIRED BY THE CONTRACT SPECIFICATIONS.
- 13. CONSTRUCTION WATER COLLECTED FROM DECONTAMINATING OR DEWATERING ACTIVITIES SHALL BE COLLECTED IN TEMPORARY STORAGE TANKS FOR TREATMENT OR DISPOSAL OFF SITE AS SPECIFIED IN THE CONTRACT SPECIFICATIONS. DEWATERING IS CURRENTLY NOT ANTICIPATED. HOWEVER, IT HAS BEEN INCLUDED AS A CONTINGENCY, AS NECESSARY.
- 14. ALL AREAS DISTURBED BY THE CONTRACTOR SHALL BE RESTORED TO THEIR ORIGINAL CONDITIONS OR AS OTHERWISE REQUIRED IN THE CONTRACT DOCUMENTS AND TO THE SATISFACTION OF THE ENGINEER.

SURVEY NOTES

- 1. SURVEY COMPLETED NOVEMBER 12, 2015 BY JEFF PHILLIPS, LS.
- 2. HORIZONTAL DATUM IS REFERENCED TO THE NORTH AMERICAN DATUM OF 1983 (2011) NEW YORK STATE PLANE COORDINATE SYSTEM, WEST ZONE.
- 3. VERTICAL DATUM IS REFERENCED TO THE NAVD88.
- 4. MAPPING UNITS ARE U.S. SURVEY FEET.
- 5. THE CONTOUR INTERVAL IS 1 FOOT.
- 6. UTILITIES SHOWN HEREON WERE PLOTTED FROM SURFACE FEATURES ONLY. UNDERGROUND UTILITIES MAY EXIST WHICH ARE NOT SHOWN HEREON.
- 7. PROPERTY LINES SHOWN HEREON ARE BASED UPON A DEED PLOT AND TAX MAP INFORMATION ONLY.

WASTE DISPOSAL NOTES:

- 1. THE CONTRACTOR MUST TAKE EVERY EFFORT TO REDUCE THE AMOUNT OF WASTE THAT IS GENERATED, TO REUSE MATERIALS WITH THE CONCURRENCE OF NYSDEC, AND TO SEGREGATE WASTE MATERIALS FOR WASTE DISPOSAL.
- 2. ALL WASTE MATERIALS MUST BE PROPERLY TRANSPORTED, STORED, HANDLED, AND CONTAINED TO PREVENT SPILLS, LEAKAGE, DISCHARGE OR RELEASE TO THE ENVIRONMENT. WASTE CONTAINERS MUST BE PROPERLY LABELED TO IDENTIFY CONTENTS.
- 3. CONTRACTORS MUST NOT DISCHARGE OR DISPOSE OF ANY WASTE INTO ANY STORM OR SANITARY SEWER DRAIN SYSTEM OR WATER BODY.
- 4. CONTRACTORS MUST DISPOSE OF ALL WASTE MATERIALS ACCORDING TO ALL LOCAL, STATE AND FEDERAL REGULATIONS.
- 5. NYSDEC SHALL APPROVE THE WASTE DISPOSAL FACILITY SELECTED BY THE CONTRACTOR. ALL WASTE MANIFESTS REQUIRED FOR THE PROJECT SHALL BE PREPARED AND SIGNED BY THE NYSDEC OR THEIR REPRESENTATIVE.

EXCAVATION NOTES:

- 1. EXCAVATION EQUIPMENT AND WORK SHALL COMPLY WITH ALL FEDERAL, STATE, AND LOCAL CODES AND REGULATIONS INCLUDING BUT NOT LIMITED TO OSHA 29 CFR 1926, SUBPARTS M, O, AND P.
- 2. THE CONTRACTOR SHALL PERFORM THE EXCAVATIONS AT THE MINIMUM DEPTHS SHOWN ON THE PLANS. THE EXCAVATION LIMITS SHOWN MAY BE ENLARGED BASED ON THE RESULTS OF THE CONFIRMATION SAMPLE RESULTS. ALL EXCAVATIONS BEYOND THE DEPTHS OR LIMITS SHOWN SHALL BE PREVIOUSLY APPROVED BY THE ENGINEER PRIOR TO COMMENCING. SIDEWALL END POINT SAMPLING SHALL BE AT DISCRETION OF ENGINEER. BOTTOM END POINT SAMPLING IN ACCORDANCE WITH DER—10.
- 3. ESTIMATED VOLUME OF SOIL TO BE REMOVED IS NOT NECESSARILY EQUAL TO THE ACTUAL VOLUME THAT WILL BE REMOVED. THE CONTRACTOR SHALL SLOPE AND/OR SHORE EXCAVATIONS TO PROTECT EXISTING STRUCTURES AND UTILITIES THAT ARE TO REMAIN.
- 4. THE USE OF TRENCH BOXES DOES NOT REQUIRE CONTRACTOR TO PROCURE A STRUCTURAL ENGINEER. REFER SPECIFICATION SECTION 02073 FOR EXCAVATIONS.
- 5. PROVIDE BARRICADES, COVERINGS, OR OTHER TYPES OF PROTECTION NECESSARY TO PREVENT DAMAGE TO EXISTING STRUCTURES AND UTILITIES TO REMAIN IN PLACE.
- 6. COORDINATES PROVIDED FOR STAKE OUT ARE BASED ON STATE PLANE DATUM AND ARE ESTIMATED TO THE NEAREST HUNDREDTH OF A FOOT
- 7. CONTRACTORS MUST PROVIDE LADDERS, STAIRWAYS, RAMPS, OR OTHER SAFE MEANS OF EGRESS IN ALL EXCAVATIONS THAT ARE FOUR FEET DEEP OR MORE SO THAT A WORKER DOES NOT NEED TO TRAVEL MORE THAN 25 FEET IN ANY DIRECTION BEFORE BEING ABLE TO EXIT THE EXCAVATION.
- 8. DIRT, DEBRIS, AND OTHER MATERIAL MUST BE EFFECTIVELY STORED AND RETAINED AT LEAST TWO FEET FROM THE EDGE OF EXCAVATIONS THAT PERSONNEL MAY BE REQUIRED TO ENTER.
- 9. EXISTING MONITORING WELLS WITHIN THE EXCAVATION LIMIT SHALL BE PULLED IN PLACE PER NYSDEC CP-43.
- 10. ALL EXISTING VEGETATION AND STRUCTURES WITHIN THE EXCAVATION LIMIT SHALL BE REMOVED UNLESS NOTED TO REMAIN. THE CONTRACTOR SHALL DISPOSE OF THESE MATERIALS IN ACCORDANCE WITH ALL LOCAL, STATE AND FEDERAL LAWS.

LAND GRADING NOTES

WHEN NOT IN USE.

- 1. PROVISIONS SHALL BE MADE TO SAFELY CONDUCT SURFACE RUNOFF AWAY FROM EXPOSED AREAS AND OPEN EXCAVATIONS. RUNOFF THAT COMES IN CONTACT WITH IMPACTED SOILS SHALL BE COLLECTED AND PROPERLY DISPOSE OFFSITE IN ACCORDANCE WITH ALL REGULATIONS.
- 2. ALL GRADED OR DISTURBED AREAS, INCLUDING SLOPES, SHALL BE PROPERLY PROTECTED DURING CLEARING AND CONSTRUCTION IN ACCORDANCE WITH THE EROSION AND SEDIMENT CONTROL PLAN UNTIL THEY ARE ADEQUATELY STABILIZED.
- 3. ALL EROSION AND SEDIMENT CONTROL PRACTICES AND MEASURES SHALL BE CONSTRUCTED, APPLIED, AND MAINTAINED IN ACCORDANCE WITH THE SEDIMENT CONTROL PLAN AND THE "NEW YORK STANDARDS AND SPECIFICATIONS FOR EROSION AND SEDIMENT CONTROL".
- 4. TOPSOIL REQUIRED FOR THE ESTABLISHMENT OF VEGETATION SHALL BE EROSION STOCKPILED IN AMOUNT NECESSARY TO COMPLETE FINISHED GRADING OF FOLLOWS: ALL EXPOSED AREAS.
- 5. AREAS THAT ARE TO BE TOPSOILED SHALL BE SCARIFIED TO A MINIMUM DEPTH OF FOUR INCHES PRIOR TO PLACEMENT OF TOPSOIL.
- 6. ALL FILL SHALL BE COMPACTED AS REQUIRED TO REDUCE EROSION, SLIPPAGE, SETTLEMENT, SUBSIDENCE, OR OTHER RELATED PROBLEMS. FILL INTENDED TO SUPPORT BUILDINGS, STRUCTURES, AND CONDUITS, ETC., SHALL BE COMPACTED IN ACCORDANCE WITH LOCAL REQUIREMENTS OR CODES.
- 7. ALL FILL SHALL BE PLACED AND COMPACTED IN LAYERS NOT TO EXCEED 2 FEET IN THICKNESS OR AS OTHERWISE SPECIFIED IN THE CONSTRUCTION SPECIFICATIONS.
- 8. FILL MATERIAL SHALL BE FREE OF FROZEN PARTICLES, BRUSH, ROOTS, SOD, OR OTHER FOREIGN OBJECTIONABLE MATERIALS THAT WOULD INTERFERE WITH, OR PREVENT, CONSTRUCTION OF SATISFACTORY FILLS.
- 9. FROZEN MATERIAL OR SOFT, MUCK OR HIGHLY COMPRESSIBLE MATERIALS SHALL NOT BE INCORPORATED INTO FILL SLOPES OR STRUCTURAL FILL.
- 10. FILL SHALL NOT BE PLACED ON SATURATED OR FROZEN SURFACES.
- 11. ALL BENCHES SHALL BE KEPT FREE OF SEDIMENT DURING ALL PHASES OF CONSTRUCTION.
- 12. SEEPS OR SPRINGS ENCOUNTERED DURING CONSTRUCTION SHALL BE HANDLED IN ACCORDANCE WITH THE CONTRACT SPECIFICATIONS.13. ALL GRADED AREAS SHALL BE PERMANENTLY STABILIZED IMMEDIATELY
- FOLLOWING FINISHED GRADING.

 14. STOCKPILES, BORROW AREAS, AND SPOIL AREAS SHALL BE PROTECTED AS REQUIRED BY THE CONTACT DOCUMENTS. STOCKPILES SHALL NOT BE

STORED WITHIN 50 FEET OF A WATER BODY OR IN ANY DRAINAGE PATHS.

ALL MATERIALS SHALL BE ENCIRCLED WITH SILT FENCE AND COVERED

EROSION AND SEDIMENT CONTROL NOTES

1. FULL EROSION AND SEDIMENT CONTROL MEASURES WILL BE INCORPORATED INTO THE PROJECT CONSTRUCTION. THESE PRACTICES WILL BE IN ACCORDANCE WITH THOSE SET FORTH IN THE NEW YORK STATE DEPARTMENT OF ENVIRONMENTAL CONSERVATION PUBLICATION ENTITLED "NEW YORK STATE STANDARDS AND SPECIFICATIONS FOR EROSION AND SEDIMENT CONTROL".

A. EROSION CONTROL MEASURES

THE FOLLOWING EROSION CONTROL MEASURES WILL BE INCORPORATED TO MINIMIZE EROSION POTENTIAL:

1. FILTER FABRIC SILT FENCE

SILT FENCE SHALL BE USED TO CONTROL EROSION FROM SHEET FLOW ON SLOPES NOT TO EXCEED TWO HORIZONTAL TO ONE VERTICAL. CONCENTRATED FLOW SHALL NOT BE DIRECTED TOWARD SILT FENCE AND SPACING SHALL VARY FROM 50' TO 200' DEPENDING ON SLOPE STEEPNESS.

O DEDMANIENT AND TEMPODADY CEEDING MINTURES

2. PERMANENT AND TEMPORARY SEEDING MIXTURES
PERMANENT EROSION CONTROL MEASURES INCLUDE INSTALLATION OF JUTE
MESH EROSION CONTROL SEED MATTING ON ALL SLOPES 2:1 OR GREATER.
PERMANENT AND TEMPORARY SEEDING, MULCH, FERTILIZER, SOIL AMENDMENTS,
AND SLOPE STABILIZATION WILL BE USED ON SEEDED AREAS. LAND THAT IS
STRIPPED OF VEGETATION WILL BE LEFT BARE FOR THE SHORTEST TIME
POSSIBLE. ANY AREA THAT WILL REMAIN CLEARED, BUT NOT UNDER
CONSTRUCTION FOR 24 DAYS OR LONGER, WILL BE STABILIZED WITH
TEMPORARY SEED AND MULCH WITHIN 14 DAYS OF LAST DISTURBANCE.

3. SLOPE STABILIZATION

ALL SLOPES SHALL BE STABILIZED TO MINIMIZE EROSION. SLOPES SHALL BE STABILIZED WITH TEMPORARY SEEDING MIXTURES AND STRAW MULCH. SLOPES IN EXCESS OF TWO HORIZONTAL TO ONE VERTICAL SHALL BE STABILIZED WITH JUTE NETTING AND HYDRO—SEED. EXISTING VEGETATION, WHICH IS NOT TO BE REMOVED, WILL ALSO ACT AS FILTER STRIPS TO PROTECT DOWN SLOPE AREAS. RUNOFF WILL BE DIVERTED FROM NEWLY GRADED AREAS TO PREVENT EROSION UNTIL A PERMANENT GROUND COVER HAS BEEN ESTABLISHED.

4. DUST CONTRO

MEASURES FOR DUST CONTROL DURING CONSTRUCTION SHALL BE IMPLEMENTED AS NEEDED (DAILY WATER SPRAYS WILL BE USED DURING DRY CONDITIONS). IN ADDITION TO WATER SPRAYS, TEMPORARY PLANTINGS WILL AID IN MINIMIZING DUST.

5. STABILIZED CONSTRUCTION ENTRANCE

TOWN, COUNTY AND STATE ROADWAYS WILL BE PROTECTED BY INSTALLATION OF CRUSHED STONE BLANKET FOR CLEANING CONSTRUCTION VEHICLE WHEELS. BLANKETS SHALL BE PLACED AT ANY INTERSECTION OF A CONSTRUCTION ROAD WITH A PAVED OR PUBLICLY OWNED ROAD. STABILIZED CONSTRUCTION ENTRANCES SHALL BE INSTALLED IN THE LOCATION AND BE OF SIZE AND TYPE SPECIFIED.

6 TREE PROTECTION

TREES TO BE PRESERVED WITHIN AREAS OF CONSTRUCTION SHALL BE PROTECTED. IN AREAS OF CONCENTRATED CONSTRUCTION ACTIVITY TEMPORARY FENCING WILL BE PLACED AROUND THE DRIP LINES. IN ALL OTHER AREAS, CONSTRUCTION WORKERS WILL BE DIRECTED TO AVOID THE STORING OF EQUIPMENT OR SOIL UNDER TREES TO BE PRESERVED, IN ORDER TO PREVENT SOIL COMPACTION.

7. INSPECTIO

THE GENERAL CONTRACTOR WILL CONDUCT WEEKLY INSPECTIONS OF THE EROSION CONTROL MEASURES.

B. EROSION CONTROL SEQUENCE

THE INSTALLATION OF EROSION CONTROL MEASURES SHOULD BEGIN WITH THE MOST DOWNSTREAM DEVICE, THEN WORKING UPSTREAM. WHEN INSTALLING EROSION CONTROL MEASURES, THE SEQUENCE SHOULD GENERALLY BE AS FOLLOWS:

1. PRIOR TO COMMENCING CONSTRUCTION ACTIVITIES, THE LIMITS OF CLEARING AND GRADING SHALL BE CLEARLY MARKED. PERIMETER SILT FENCE AND STABILIZED CONSTRUCTION ENTRANCES SHALL BE PUT IN PLACE.

2. ANY AREAS NOT REQUIRING FURTHER EARTHWORK SHALL BE FINE GRADED, TOP SOILED AND STABILIZED AS EARLY AS POSSIBLE.

C. MAINTENANCE OF EROSION CONTROL DEVICES

ALL EROSION CONTROL DEVICES WILL BE MONITORED, CLEANED, AND RESTORED THROUGHOUT CONSTRUCTION TO MAINTAIN THEIR EFFECTIVENESS.

1. SPECIFIC MAINTENANCE SHALL INCLUDE:

a. MAINTAINING SEEDED AREAS INCLUDING RESEEDING WEAK AREAS,
 RE-GRADING WASH OUTS AND FERTILIZING AS NEEDED.
 b. MAINTAINING MULCHED AREAS INCLUDING REPLACEMENT OF DISTURBED MULCHED AREAS.

c. ALL DEVICES SHALL BE INSPECTED ONCE PER WEEK AND REPAIRED AS NEEDED.
d. SEDIMENT SHALL BE REMOVED FROM BEHIND SILT FENCE WHEN BULGES

d. SEDIMENT SHALL BE REMOVED FROM BEHIND SILT FENCE WHEN BULGES START TO OCCUR AND FENCING RESET TO ORIGINAL CONDITION.

e. CONSTRUCTION EQUIPMENT SHALL NOT UNNECESSARILY CROSS DRAINAGE SWALES. CROSSING OF DRAINAGE CHANNELS SHALL BE BY MEANS OF BRIDGES, CULVERTS OR OTHER APPROVED METHODS.

f. CULVERTS SHALL BE MAINTAINED FREE OF SILT OR DEBRIS.

C. MAINTENANCE OF EROSION CONTROL DEVICES (CONTINUED)

g. TREE PROTECTION FENCING TO BE INSPECTED DAILY DURING GRADING AND FINISH GRADING OPERATIONS.

h. DAILY WATER SPRAYS WILL BE USED AS NEEDED OR AS DIRECTED BY THE ENGINEER. WATER SPRAYS WILL BE USED TO PREVENT POLLUTION FROM DUST UNTIL CONSTRUCTION IS COMPLETED AND SOIL COVER IS ESTABLISHED.

D. REMOVAL OF EROSION CONTROL DEVICES

NO EROSION CONTROL STRUCTURES SHALL BE REMOVED UNTIL ALL WORK UPSTREAM HAS BEEN COMPLETED, STABILIZED, AND APPROVED BY THE ENGINEER.

1. THE REMOVAL OF EROSION CONTROL DEVICES SHOULD GENERALLY BE AS FOLLOWS:

a. AFTER CONSTRUCTION, THE TEMPORARY EROSION CONTROL STRUCTURES ARE TO BE REMOVED IN REVERSE ORDER WITH THE MOST UPSTREAM STRUCTURE REMOVED FIRST AND THENCE PROCEEDING DOWNSTREAM.

b. ALL TREE PROTECTION FENCING SHALL BE REMOVED AFTER ADJACENT AREAS HAVE BEEN GRADED, TOP SOILED, SEEDED, AND VEGETATION HAS BEEN ESTABLISHED.

c. ANY WASHOUTS SHALL BE RE-TOPSOILED AND SEEDED.

SPECIFICATIONS FOR SEEDING, MULCHING, AND NETTING

STABILIZATION SHALL BE DONE ACCORDING TO THE APPROPRIATE STANDARDS AND SPECIFICATIONS FOR CRITICAL AREA SEEDING, MULCHING AND NETTING. (NEW YORK STATE STANDARDS AND SPECIFICATIONS FOR EROSION AND SEDIMENT CONTROL)

CONSTRUCTION SEQUENCE:

- 1. A PRE-CONSTRUCTION MEETING SHALL BE HELD AT THE SITE.
- MOBILIZE EQUIPMENT TO SITE.
 INSTALL EROSION CONTROL MEASURES SHOWN FOR THE ONSITE EXCAVATION AREA.
- 4. INSTALL TEMPORARY CONSTRUCTION FENCE AS SHOWN.
- 5. COMPLETE EXCAVATION AS SHOWN.
- 6. INSTALL TEMP ACCESS ROAD AS SHOWN.7. REMOVE SEPTIC TANK STRUCTURE, CATCH BASIN CB-1 STRUCTURE, AND ASSOCIATED PIPING UNTIL OUTFALL AS SHOWN.
- 8. INSTALL PIPE AND NEW CB-1 AS SHOWN.
- 9. RESTORE SITE AS SHOWN.

 10. PEMOVE EPOSION CONTROL MEASURES ONCE SITE HA
- 10. REMOVE EROSION CONTROL MEASURES ONCE SITE HAS ACHIEVED FINAL STABILIZATION.

ENVIRONMENTAL NOTES:

- THE CONTRACTOR SHALL REDUCE VEHICLE IDLING. ALL VEHICLES, BOTH ON AND OFF ROAD (INCLUDING CONSTRUCTION EQUIPMENT) SHALL BE SHUT OFF WHEN NOT IN USE FOR MORE THAN 5 MINUTES IN ACCORDANCE WITH 6NYCRR PART 217 MOTOR VEHICLE EMISSIONS, SUBPART 217—3 IDLING PROHIBITION FOR HEAVY DUTY VEHICLES.
- 2. CONTRACTORS MUST NOT SPILL, DISCHARGE, OR RELEASE ANY HAZARDOUS MATERIAL OR CHEMICAL UPON OR FROM THE SITE. A RELEASE IS DEFINED AS ANY UNPLANNED RELEASE, LEAKING, PUMPING, POURING, EMITTING, DUMPING, DISCHARGING, EMPTYING, OR DISPOSING OF A HAZARDOUS MATERIAL OR CHEMICAL (INCLUDING WASTEWATER OR CHEMICALLY TREATED WATER) FROM A PRIMARY CONTAINMENT.
- 3. CONTRACTOR EQUIPMENT MUST BE PROPERLY MAINTAINED AND IS SUBJECT TO INSPECTION BY THE ENGINEER. IF EQUIPMENT IS FOUND LEAKING, IT MUST IMMEDIATELY BE CONTAINED, STOPPED, AND REPAIRED. ALL ASSOCIATED COSTS INCLUDING CLEANUP WILL BE THE SOLE RESPONSIBILITY OF THE CONTRACTOR.
- 4. UNREPORTED SPILLS, DISCHARGES, AND RELEASES ARE A VIOLATION OF FEDERAL, STATE, AND LOCAL LAWS. IF A CHEMICAL OR UNKNOWN LIQUID IS SPILLED, DISCHARGED, OR RELEASED TO THE PROPERTY, THE CONTRACTOR MUST IMMEDIATELY NOTIFY THE ENGINEER.
- 5. WHEN A SPILL, DISCHARGE, OR RELEASE IS DIRECTLY ATTRIBUTABLE TO A CONTRACTOR, THEIR SUBCONTRACTOR OR SUPPLIER, THE CONTRACTOR MUST PROVIDE ANY ASSISTANCE REQUIRED TO IDENTIFY THE CAUSE OF THE RELEASE AND TO CLEAN UP THE RELEASE. HOWEVER CONTRACTORS MUST NOT BEGIN CLEAN UP UNTIL AUTHORIZED TO DO SO BY THE ENGINEER.
- 6. ANY CHEMICAL SPILL, DISCHARGE, OR RELEASE CAUSED BY THE CONTRACTOR MUST BE CLEANED TO NYSDEC'S SATISFACTION. ALL ASSOCIATED CLEANUP COSTS ARE THE RESPONSIBILITY OF THE RESPONSIBLE CONTRACTOR.

<u>LEGEND:</u>

MONITORING WELL

CATCH BASIN MANHOLE

SANITARY MANHOLE

-O- UTILITY POLE

SAMPLE LOCATION

---- MINOR CONTOUR

VEGETATION LINE

WETLAND LIMIT


WETLAND 100 FEET BUFFER LIMIT

SANITARY SEWER LINE
STORM DRAINAGE LINE

APPROXIMATE STORM
DRAINAGE LINE (NOT SURVEYED)

NEW YORK
STATE OF OPPORTUNITY
Department of Environmental Conservation








04/29/2016 DATE


WARNING: It is a violation of the New York State Education Law for any person unless acting under the direction of a licensed professional engineer, to alter any item on these plans in any way. If alterations to these plans are made, the alterations shall be made in accordance with 145—subsection 7209 of the New York State Education Law.

FORMER AIR FORCE PLANT NO.51 NYSDEC SITE NO. 828156 GREECE, MONROE COUNTY, NEW YORK GENERAL NOTES AND LEGEND

NOT TO SCALE



G-Z



LEGEND:


DEMOLISHED BUILDING

LIMIT OF DISTURBANCE

EXCAVATION LIMIT

NOTE: AERIAL BACKGROUND SOURCE: NYS GIS CLEARING HOUSE WEBSITE.









04/29/2016 DATE


WARNING: It is a violation of the New York State Education Law for any person unless acting under the direction of a licensed professional engineer, to alter any item on these plans in any way. If alterations to these plans are made, the alterations shall be made in accordance with 145—subsection 7209 of the New York State Education Law.


FORMER AIR FORCE PLANT NO.51 NYSDEC SITE NO. 828156 GREECE, MONROE COUNTY, NEW YORK


SITE PLAN























1 04/29/2016


ISSUE DATE


100% REMEDIAL DESIGN


DESCRIPTION


PROJECT NUMBER | 147 - 258214


FILENAME SCALE N.T.S.












CONSTRUCTION SPECIFICATIONS

- 1. ROAD WIDTH OF 14 FEET FOR ONE-WAY TRAFFIC OR 24 FEET MINIMUM FOR TWO-WAY TRAFFIC.
- 2. MAXIMUM SLOPE OF 10%. 3. CLEAR AND STRIP ROADBED AND PARKING AREAS OF ALL VEGETATION, ROOTS AND
- OTHER OBJECTIONABLE MATERIAL.

 4. LOCATE PARKING AREAS ON NATURALLY FLAT AREAS AS AVAILABLE. KEEP GRADES
- SUFFICIENT FOR DRAINAGE BUT NOT MORE THAN 2 TO 3 PERCENT.

 5. PROVIDE SURFACE DRAINAGE AND DIVERT EXCESS RUNOFF TO STABILIZED AREAS.
- 6. MAINTAIN CUT AND FILL SLOPES TO 2:1 OR FLATTER AND STABILIZED WITH VEGETATION AS SOON AS GRADING IS ACCOMPLISHED.
- 7. SPREAD SIX INCH LAYER OF SUB-BASE MATERIAL EVENLY OVER THE FULL WIDTH OF THE ROAD AND SMOOTH TO AVOID DEPRESSIONS.
- 8. PROVIDE APPROPRIATE SEDIMENT CONTROL MEASURES TO PREVENT OFFSITE SEDIMENTATION.





NOTES:


SIGN SHALL BE 4' HIGH BY 8' LONG AND SHALL BE CONSTRUCTED OF \$\frac{3}{4}\$ INCH PLYWOOD. THE EDGE SHALL BE FRAMED WITH A SNAP TRIM EDGE CAP CONSISTING OF AN ALUMINUM CHANNEL WITH A POLYVINYL COATING.

THE POST SHALL BE A 4 INCH BY 4 INCH PRESSURE TREATED POST OR SIMILARLY SUITABLE MATERIAL. THE POST SHALL BE EMBEDDED INTO THE GROUND A MINIMUM OF 30 INCHES. THE SIGN SHALL BE ERECTED SO THAT THE BOTTOM OF THE SIGN IS SIX FEET ABOVE THE GROUND SURFACE.


THE SIGNS BACKGROUND SHALL BE PAINTED WITH WHITE EXTERIOR OIL BASE SIGN ENAMEL. THE FIRST, SECOND, SIXTH, AND SEVENTH LINES WILL HAVE GREEN LETERS. THE NYS LOGO SHALL BE PAINTED AS SHOWN. ALL ADHESIVES SHALL BE SOLVENT RESISTANT.

TEMPORARY SIGN WILL REQUIRE A PERMIT FROM THE TOWN.











DECONTAMINATION PAD SECTION DETAIL


N.T.S.



NEW YORK
STATE OF OPPORTUNITY
Conservation

Department of Environmental Conservation






FORMER AIR FORCE PLANT NO.51 NYSDEC SITE NO. 828156 GREECE, MONROE COUNTY, NEW YORK

CONSTRUCTION DETAILS



SHEET

D—



SECTION VII CONSTRUCTION SPECIFICATIONS

1. WOVEN WIRE FENCE TO BE FASTENED SECURELY TO FENCE POSTS WITH WIRE TIES OR STAPLES. POSTS SHALL BE STEEL EITHER "T" OR "U" TYPE OR HARDWOOD.


2. FILTER CLOTH TO BE TO BE FASTENED SECURELY TO WOVEN WIRE FENCE WITH TIES SPACED EVERY 24" AT TOP AND MID SECTION. FENCE SHALL BE WOVEN WIRE, 12 1/2 GAUGE, 6" MAXIMUM MESH OPENING.

3. WHEN TWO SECTIONS OF FILTER CLOTH ADJOIN EACH OTHER THEY SHALL BE OVER— LAPPED BY SIX INCHES AND FOLDED. FILTER CLOTH SHALL BE EITHER MIRAFI 100X, STABILINKA T140N, OR APPROVED EQUIVALENT.


4. PREFABRICATED UNITS SHALL BE GEOFAB, ENVIROFENCE, OR APPROVED EQUIVALENT.

5. MAINTENANCE SHALL BE PERFORMED AS NEEDED AND MATERIAL REMOVED WHEN "BULGES" DEVELOP OR SIX INCHES OF SEDIMENT HAS COLLECTED IN THE SILT FENCE.

6. SILT FENCE SHALL BE INSPECTED AFTER RAINFALL EVENTS OF 0.5 INCHES OR GREATER.



SILT FENCE



CONSTRUCTION SPECIFICATIONS

1. STONE SIZE - USE 2" STONE, OR RECLAIMED OR RECYCLED CONCRETE

- EQUIVALENT.

 2. LENGTH NOT LESS THAN 50 FEET (EXCEPT ON A SINGLE RESIDENCE LOT WHERE
- A 30 FOOT MINIMUM LENGTH WOULD APPLY).
- 3. THICKNESS NOT LESS THAN SIX (6) INCHES.
- 4. WIDTH TWELVE (12) FOOT MINIMUM, BUT NOT LESS THAN THE FULL WIDTH AT POINTS WHERE INGRESS OR EGRESS OCCURS. TWENTY—FOUR (24) FOOT IF SINGLE
- 5. FILTER CLOTH WILL BE PLACED OVER THE ENTIRE AREA PRIOR TO PLACING OF
- STONE.


 6. SURFACE WATER ALL SURFACE WATER FLOWING OR DIVERTED TOWARD CON—
 STRUCTION ENTRANCES SHALL BE PIPED ACROSS THE ENTRANCE. IF PIPING IS
 IMPRACTICAL, A MOUNTABLE BERM WITH 5:1 SLOPES WILL BE PERMITTED.

 7. MAINTENANCE THE ENTRANCE SHALL BE MAINTAINED IN A CONDITION WHICH WILL
 PREVENT TRACKING OR FLOWING OF SEDIMENT ONTO PUBLIC RIGHTS—OF—WAY, ALL
- PREVENT TRACKING OR FLOWING OF SEDIMENT ONTO PUBLIC RIGHTS—OF—WAY, ALL SEDIMENT SPILLED, DROPPED, WASHED OR TRACTED ONTO PUBLIC RIGHTS—OF—WAY MUST BE REMOVED IMMEDIATELY.

 8. WHEN WASHING IS REQUIRED, IT SHALL BE DONE ON A AREA STABILIZED WITH
- STONE AND WHICH DRAINS INTO AN APPROVED SEDIMENT TRAPPING DEVICE.

 9. PERIODIC INSPECTION AND NEEDED MAINTENANCE SHALL BE PROVIDED AFTER EACH

STABILIZED CONSTRUCTION ENTRANCE
N.T.S.



CONSTRUCTION SPECIFICATIONS

PROJECT MANAGER M. MUSSO

PROJECT NUMBER 147 - 258214

1. BALES SHALL BE PLACED AT THE TOE OF A SLOPE OR ON THE CONTOUR AND IN A ROW WITH ENDS TIGHTLY ABUTTING THE ADJACENT BALES.


2. EACH BALE SHALL BE EMBEDDED IN THE SOIL A MINIMUM OF (4) INCHES, AND PLACED SO THE BINDINGS ARE HORIZONTAL.

3. BALES SHALL BE SECURELY ANCHORED IN PLACE BY EITHER TWO STAKES OR RE-BARS DRIVEN THROUGH THE BALE. THE FIRST STAKE IN EACH BALE SHALL BE DRIVEN TOWARD THE PREVIOUSLY LAID BALE AT AN ANGLE TO FORCE THE BALES TOGETHER. STAKES SHALL BE DRIVEN FLUSH WITH THE BALE.

4. INSPECTION SHALL BE FREQUENT AND REPAIR REPLACEMENT SHALL BE MADE PROMTLY AS NEFDED.

5. BALES SHALL BE REMOVED WHEN THEY HAVE SERVED THEIR USEFULLNESS SO AS NOT TO BLOCK OR IMPEDE STORM FLOW OR DRAINAGE.





- 1. CONTAMINATED SOIL STOCKPILES MUST BE PLACED ON A HDPE GEO-MEMBRANE LINER COVERED WITH A 4 INCH LAYER OF SAND AND GEO-TEXTILE FILTER FABRIC. THE HDPE LINER SHALL HAVE A MINIMUM THICKNESS AS SPECIFIED IN THE CONTRACT SPECIFICATIONS.
- 2. THE GEO-MEMBRANE SHALL BE PLACED SUCH THAT STOCKPILED SOIL DOES NOT COME INTO CONTACT WITH SURFACE WATER RUN-OFF.
- 3. A BERM OR SILT FENCE SHALL BE INSTALLED AROUND THE STOCKPILED SOIL TO PREVENT THE
- MIGRATION OF CONTAMINANTS.

 4. STOCKPILES SHALL BE COVERED WITH A 10 MIL SHEET OF GEO-MEMBRANE TO PREVENT RAIN OR
- SURFACE WATER FROM COMING INTO CONTACT WITH THE CONTAMINATED SOIL.
 5. THE COVER SHALL BE ANCHORED WITH SANDBAGS TO PREVENT IT FROM BEING BLOWN AWAY.


SOIL STOCKPILE DETAIL

N.T.S.

NEW YORK
STATE OF OPPORTUNITY
Conservation

Department of Environmental Conservation

1 04/29/2016 100% REMEDIAL DESIGN
ISSUE DATE DESCRIPTION



145—subsection 7209 of the New York State Education Law.

FORMER AIR FORCE PLANT NO.51 NYSDEC SITE NO. 828156 GREECE, MONROE COUNTY, NEW YORK **EROSION CONTROL DETAILS**



SHEET D-2

