

# **State Superfund Standby Contract**

## **Work Assignment**

### **Site Investigation Project**

#### **Contract Type: Cost Plus Fixed Fee**

**Site Name: North Franklin Street Site (No. 8-49-002)**

#### **I. Site Location and Description:**

##### **1.1 Location**

The North Franklin Street inactive hazardous waste disposal site is an approximately 0.3 acre parcel of land situated in the Village of Watkins Glen, Schuyler County. The site is located in an urban area approximately 400 feet south of Seneca Lake. Two (2) structures currently exist on site. The building referred to as the "Former Auto Museum" is a single-story metal building on a concrete slab. The second structure is referred to as the "Former Dry Cleaning Building." This is a two-story brick building that also includes two (2) unoccupied single-story brick sheds to the east and the "VFW Building attached to the south." The former dry cleaning building and former auto museum are vacant and scheduled for demolition during summer of 2006 under the Brownfield Cleanup Program.

The cleanup is necessary to address groundwater beneath the site that has been contaminated with dry cleaning chemicals known as volatile organic compounds (VOCs), primarily tetrachloroethene (perchloroethene or PCE).

##### **1.2 Operational/Disposal History**

Spent solvents resulting from the illegal disposal practices of the former dry cleaning operation has contaminated subsurface soil and groundwater at the site. The solvent was reportedly PCE. This VOC naturally degrades, with time, into several breakdown products including trichloroethene (TCE), 1,2-Dichloroethene (1,2 DCE), and vinyl chloride (VC).

##### **1.3 Remedial History**

In the fall of 1991, Norstar Bank hired Enasco, Inc., to conduct an environmental assessment at the site. This assessment, concluded in January 1992, indicated that the groundwater was contaminated with elevated levels of VOC (including tetrachloroethene, also known as PCE, TCE, 1,2-DCE, and VC), and low levels of polychlorinated biphenyls (PCBs) at concentrations above New York State Groundwater Standards. As a

result, in July 1992, the New York State Department of Environmental Conservation (NYSDEC) placed this site on the "Registry of Inactive Hazardous Waste Disposal Sites in New York State" with a classification of "2" (Site No. 849002). The area is serviced by a public water supply, and no homes in the immediate area are utilizing private water as their primary source of water, so chemical exposure through drinking water is not a concern.

In October 1992, all of the identified potentially responsible parties were given an opportunity to voluntarily finance the RI/FS. No agreement could be reached with any of them. Therefore, the NYSDEC contracted the services of URS Consultants, Inc., from Buffalo, New York to perform the RI/FS using State Superfund monies. Field work for the investigation was initiated in November 1992. The purpose of the RI was to define the nature and extent of any contamination resulting from previous disposal activities at the site. The RI was conducted in two (2) phases. The first phase was conducted between November 1992 and March 1993, and the second phase was conducted between March 1993 and April 1993.

#### **1.4 Selected Remedy**

On January 26, 1994, the NYSDEC signed a Record of Decision (ROD) which selected a remedy to clean up the site involving active soil vapor extraction (SVE) and groundwater extraction and treatment technologies. The State-funded remedial design was completed by the NYSDEC's Engineering Consultant, URS Consultants, Inc., (URS) in June 1995. Construction of the treatment systems was completed and operations began in the fall of 1996. Confirmatory soil samples collected during remediation indicated that SVE had effectively cleaned up the soil near the extraction wells, underneath the former auto museum, and to the rear of the former dry cleaning building. However, in the process of collecting the confirmatory samples, it was discovered that the contaminant concentrations in the immediate vicinity of the dry cleaning building were much higher and extended deeper into clay than previously thought. SVE did not clean up this area of highly contaminated soil despite subsequent modifications to and extended operation of the SVE System. Operation of the SVE System was suspended in March 1998 and operation of the groundwater treatment system was suspended at the end of April 1998, pending the results of further investigations. Additional investigations and a chemical oxidation pilot study were performed through 1999 into May 2000 on the remaining soil contamination. In November 2001, URS's final report on the additional investigations and the pilot study concluded that the chemical oxidation pilot study program significantly reduced the mass of chlorinated contaminants in on-site soils. Despite the reduction, however, localized areas with residual contaminant concentrations exceeding remedial action objectives for soils remain concentrated within the deeper clay, primarily at depths ranging from four (4) to six (6) feet below ground surface

In March 2003, the NYSDEC changed the remedy outlined within the 1994 ROD and issued an Explanation of Significant Differences (ESD) for the site. The purpose of the ESD was to describe how the residual contaminated soil and groundwater would be addressed. The change to the remedy included the placement of deed restrictions to prevent usage of groundwater and contact with residual soil contamination in addition to the installation of an active venting system within the former dry cleaner building to control the potential indoor migration of vapors.

The remedial design for the venting system was initiated in July 2003 and completed in December 2003 by the NYSDEC. The construction contract to perform the work was bid in January 2004 and awarded to a qualified Contractor, EQ-EWMI of New Jersey, in March 2004. Construction work was initiated on March 22, 2004 and completed four (4) days later on March 26, 2004. Site management of the venting system began in April 2004 by the NYSDEC, and continued until January 2006 when ownership of the parcel changed and the building was scheduled for demolition. During that time air samples from within the former dry cleaning building were collected and analyzed on a bimonthly basis to determine the efficiency of the venting system.

## **1.5 Current Status**

URS Corporation (URS) has completed a soil-gas investigation in the vicinity of the North Franklin Street site. The field work associated with this investigation consisted of the installation and sampling of 13 new soil-gas conduits. URS personnel supervised the installation of the soil-gas conduits between July 12, 2005 and July 13, 2005, and conducted the soil-gas conduit sampling on July 18, 2005. A total of 13 soil-gas conduits (SG-01 through SG-13) were installed. URS collected 13 one (1) hour soil gas samples plus two (2) field duplicate samples.

VOCs were detected at every soil-gas conduit location, with the highest concentration detected in the sample collected from SG-03 (benzene at 22,700 ug/m<sup>3</sup> and m, p-xylene at 6,430ug/m<sup>3</sup>). However, chlorinated VOCs were only detected in the samples collected from soil-gas conduits SG-01, SG-02, SG-04, SG-06, SG-07 and SG09 through SG-12, with the highest concentration detected in the sample collected from SG-02 (chloroform at 214.83 ug/m<sup>3</sup>). PCE was detected in samples collected from conduits SG-06, SG-07, SG-09, SG-10 and SG-12, at concentrations ranging from 3.26 ug/m<sup>3</sup> to 35.3 ug/m<sup>3</sup>. TCE was detected in the sample collected from conduit SG-09, at a concentration of 12.4 ug/m<sup>3</sup>.

## **II. Scope of Work**

The tasks and requirements of this work assignment are specified in URS's Investigation and Standby Contract, D004433. The work shall include, but not necessarily be limited to, the following activities:

1. Subsurface soil and groundwater investigation utilizing direct push technology to define nature and extent of BETX contamination in the site area near SG-03.

Included as part of this work are tasks associated with work plan development, surveying of boring locations and existing monitoring wells, and letter report preparation.

## **Task 1 Work Plans:**

### **Subtask 1.1 Work Plans:**

Within one (1) week of notification of the work assignment, the project cover letter is to be signed and returned by the URS Contract Manager acknowledging receipt of the proposed work assignment.

URS's Project Manager will have a telephone discussion with NYSDEC's Project Manager regarding the components of the work assignment and any required scope and schedule changes. A level of effort (LOE) estimate and the associated cost for completing all tasks and deliverables will be submitted for negotiation with URS's work plan.

For the issuance of the work assignment, URS shall prepare and submit six (6) copies of this proposed Work Plan for Remedial Site Management. The purpose of this work plan is to:

1. provide more detail of the scope of work, where necessary, to support URS's LOE estimates and assumptions in the project budget; and
2. present a work plan that includes a Statement of Work, which describes and explains the purpose of the major tasks and sub-tasks; a detailed schedule with milestones and deliverables; a staffing plan; a MBE/WBE and Equal Employment Opportunity (EEO) utilization plan; and a proposed list of subcontractors.

When an acceptable work plan is produced, a Notice to Proceed will be issued to complete the project. It is the goal of the Department to formally approve the Engineer's work plan within 90 days of issuing the work assignment.

## **Task 2: Geoprobe® Investigation of BETX Contaminated Soils and Groundwater**

The purpose of the investigation task is to provide professional engineering services for the proper delineation of BTEX contaminated soils and groundwater recently encountered during the ongoing soil vapor intrusion study at the North Franklin Street site.

### **Subtask 2.1: Geoprobe® Boring Installation**

URS will procure a drilling subcontract to advance 21 borings within a 25 foot square grid pattern around soil gas location SG-03, and advance 7 borings along the west side of Route 14 for a total of 28 borings. For costing purposes the Engineer shall assume boring installation will be completed in three (3), 10-hour days and will include 8 hours for travel, 8 hours of preparation time, and 16 hours

to complete boring logs. Permits will be the responsibility of the driller, the Engineer shall stake out boring locations and visit site with necessary utilities prior to commencement of field work.

A total of 33 soil and 33 groundwater samples, including QA/QC shall be analyzed. One (1) soil sample will be collected from each boring from interval exhibiting highest PID reading or from just above water table should no elevated PID readings be encountered. Groundwater samples shall also be collected from each boring location. Both soil and groundwater samples shall be collected and analyzed for STARS 8260 and STARS 8270 compounds. Standard turn around time (four (4) weeks) on all samples collected will be required. The Engineer shall assume two (2) drums of soil cuttings and one (1) drum of sampling liners/PPE will be generated and required to be properly characterized and disposed offsite.

A hard copy of the analytical results, including QA/QC results, and an ASP Category B reporting and deliverable package in CLP format, will be submitted by the qualified laboratory to the URS Project Manager within three (3) weeks after the analytical results become available. The analytical results will be reviewed and validated by URS, as an independent data validator.

URS will submit an evaluation letter report for each bi-annual sampling event summarizing the results and findings obtained during this subtask. The report will be delivered in approximately five (5) weeks after receipt of the analytical results.

#### Subtask 2.2: Surveying

Engineer shall survey 28 boring locations and 11 existing monitoring well locations for vertical and horizontal. Engineer shall assume field work will take two (2), eight (8) hour days with travel.

#### Subtask 2.3: Reporting

A letter report will be required, and will be written to summarize field activities and findings only. Eight (8) copies of final report shall be made by outside subcontractor. Engineer shall assign a Senior Geologist to write and revise report as necessary (24 hours). Engineer shall assign a Chemist to validate data and write DUSR (33 hours), assign GIS personnel to create maps/tables and manage data base (four (4) hours), and assign administrative support involved with typing report and DUSR (three (3) hours).

**III. Level of Effort and Cost Estimates (includes labor, overhead, direct costs, subcontracts, fixed fee):**

<b><u>Task No.</u></b>	<b><u>Major Task Description</u></b>	<b><u>LOE(hrs.)</u></b>	<b><u>Labor Cost</u></b>
1.1	Develop Detailed Work Plan	24	\$ 2,000.00
2.1	Geoprobe® Boring Installation	100	\$29,500.00
2.2	Surveying	40	\$2,700.00
2.3	Reporting	86	\$5,600.00
<b>Totals:</b>		<b>250</b>	<b>\$39,800.00</b>

**IV. Period of Performance**

Approximately 180 Calendar Days.

**V. Work Plan Development Authorization**

The Engineer is authorized to spend up to \$2,000 to perform Task 1.1.

**VI. URS's Site Tentative O&M Project Schedule**

<b><u>Work Assignment Element</u></b>	<b><u>No. of Calendar Days from WA Issuance</u></b>
Department issues W.A.	0
* Consultant submits WP, staffing plan, estimated budget, and M/WBE Utilization Plan	28
Notice to Proceed (Work Plan Approval)	42
* Investigation Field Work Initiated	72
Draft Letter Report Submitted	150
* Final Letter Report Submitted/WA Complete	180

\* Milestones for rating purpose

**VII: Project Budget**

The estimated total project budget is \$39,800.

**VIII: M/WBE Utilization Plan**

The Consultant will prepare a M/WBE Utilization Plan in compliance with the conditions of their standby contract with the Department.