

**2020**

**PERIODIC REVIEW REPORT**

**FOR**

**DOWCRAFT, SOUTH DOW STREET**

**NYSDEC SITE #907020**

**FALCONER, CHAUTAUQUA COUNTY, NEW YORK**

Prepared by:



**C&S ENGINEERS, INC.**

141 ELM STREET

BUFFALO, NEW YORK 14203

Prepared for:

**JAMESTOWN CONTAINER COMPANIES**

14 DEMING DRIVE

FALCONER, NEW YORK 14733

**NOVEMBER 2020**

---

**TABLE OF CONTENTS**

<b>EXECUTIVE SUMMARY</b>	<b>1</b>
<b>1 SITE OVERVIEW</b>	<b>2</b>
1.1 SITE DESCRIPTION	2
1.2 GEOLOGY AND HYDROGEOLOGY	2
1.3 NATURE AND EXTENT OF CONTAMINATION	2
1.4 SITE HISTORY	3
<b>2 MONITORING PLAN COMPLIANCE REPORT</b>	<b>4</b>
<b>3 REMEDY PERFORMANCE, EFFECTIVENESS AND PROTECTIVENESS</b>	<b>5</b>
<b>4 IC/EC PLAN COMPLIANCE REPORT</b>	<b>7</b>
4.1 IC/EC REQUIREMENTS AND COMPLIANCE	7
4.1.1 INSTITUTIONAL CONTROLS	7
4.1.2 ENGINEERING CONTROLS	7
4.2 IC/EC CERTIFICATION	9
<b>5 OPERATION AND MAINTENANCE PLAN COMPLIANCE</b>	<b>9</b>
5.1 GROUNDWATER MONITORING WELLS	9
5.2 SOIL VAPOR MITIGATION SYSTEMS	9
5.2.1 MONTHLY MONITORING	9
5.2.2 ANNUAL INSPECTION	10
<b>6 CONCLUSIONS AND RECOMMENDATIONS</b>	<b>10</b>

**FIGURES**

FIGURE 1	HISTORIC AND EXISTING SITE FEATURES
FIGURE 2	TRICHLOROETHYLENE CONCENTRATIONS
FIGURE 3	CIS-1,2-DICHLOROETHENE CONCENTRATIONS
FIGURE 4	VINYL CHLORIDE CONCENTRATIONS

**TABLES**

TABLE 1 .....JULY 2013 GROUNDWATER ANALYTICAL RESULTS

TABLE 2 .....PRE AND POST TREATMENT GROUNDWATER ANALYTICAL RESULTS

**APPENDICES**

APPENDIX A ..... LABORATORY ANALYTICAL RESULTS AND DUSR

APPENDIX B.....GROUNDWATER USE CERTIFICATION

APPENDIX C .....INSTITUTIONAL AND ENGINEERING CONTROLS CERTIFICATION FORM

APPENDIX D .....OPERATION, MAINTENANCE AND MONITORING WORK PLAN

APPENDIX E.....SSDS INSPECTION REPORTS

**ACRONYM LIST**

C&S	C&S ENGINEERS, INC.
JCC	JAMESTOWN CONTAINER COMPANIES
SITE	FORMER DOWCRAFT FACILITY
TCE	TRICHLOROETHYLENE
IRM	INTERIM REMEDIAL MEASURES
NYSDEC	NEW YORK STATE DEPARTMENT OF ENVIRONMENTAL CONSERVATION
ROD	RECORD OF DECISION
CRA	CONESTOGA-ROVERS & ASSOCIATES
RI	REMEDIAL INVESTIGATION
SCO	SOIL CLEANUP OBJECTIVES
SVOC	SEMI-VOLATILE ORGANIC COMPOUNDS
VOC	VOLATILE ORGANIC COMPOUNDS
SVI	SOIL VAPOR INTRUSION

## EXECUTIVE SUMMARY

C&S Engineers, Inc. (C&S) has prepared the 2019 Periodic Review Report for the former Dowcraft, South Dow Street Site (NYSDEC Site No. 907020) located at 65 South Dow Street in Falconer, New York. From 1939 to 1999, the Site manufactured steel partitions. As part of this manufacturing process, a vapor degreaser was used which included the use of chemicals such as trichloroethylene (TCE).

Previous environmental investigations have detected a TCE plume in the area of the former Dowcraft, South Dow Street Site. TCE contamination is located within two sand/gravel layers separated by a silt/clay lens. According to previous environmental reports, the area of former degreaser pit (area of groundwater monitoring wells PW-3 and PW-3R) is a likely source area for the TCE plume. The plume originates from the degreaser area and has affected groundwater in the upper and lower sand/gravel layers. The plume extends from the degreaser area to the north, under the JCC building and up to the area of the Chadakoin River. This is an area of approximately one acre. The rate of movement is approximately 2 to 3 feet per year to the north. Sampling in the River has not shown any impact to date.

The 2003 Record of Decision of the Site selected in-situ chemical dechlorination using potassium permanganate as the approved remedy. Nine in-situ treatment events occurred between May 2000 and July 2006. In 2014, C&S completed another treatment on the Site. Ten injection borings were advanced throughout the TCE plume and a potassium permanganate treatment fence was installed adjacent to the source area by PW-3R.

Post-treatment groundwater monitoring indicates that the latest treatment was successful in the dechlorination of TCE; however, the affect of the treatments seems to be lessening. Out of eleven monitoring wells, seven wells show a decrease in TCE and other chlorinated compounds, and two of these monitoring wells show a decrease of 80% or greater. Some wells show an increase of daughter compounds, this suggests that the dechlorination process is breaking TCE into its daughter compounds.

The Site is compliant with all institutional and engineering controls. The Institutional and Engineering Controls Certification form is provided in **Appendix C**.

## **1 SITE OVERVIEW**

### **1.1 Site Description**

The Dowcraft, South Dow Street Site is located at 65 South Dow Street in Falconer, New York and occupies approximately 2.2 acres of land situated immediately east of South Dow Street and approximately 100 feet south of the Chadakoin River (Site). The Jamestown Container manufacturing building is situated between the Site and the Chadakoin River.

### **1.2 Geology and Hydrogeology**

Site geology consists of fill material overlying two sand/gravel layers separated by a silt/clay lens. Fill material consists of a mixed matrix of sand, cinders, silt, gravel, brick, concrete, coal, slag and metal. The fill unit ranges in thickness from 2 to over 14 feet, with an average thickness of 8 feet.

Under the fill, the upper sand/gravel layer ranges from 10 to 20 feet in thickness. Underlying the upper sand/gravel layer is a silt/clay lens that ranges from 4 to 8 feet in thickness. The lower sand/gravel layer is 10 to 18 feet thick. Underlying the lower sand layer is a second silt/clay layer that starts approximately 43 feet below ground surface (BGS). This unit is estimated to be 60 feet in thickness according to regional geology.

The average depth to groundwater is 10 feet BGS within the upper sand/gravel layer. Groundwater flow within the upper sand/gravel layer is to the north-northeast at approximately 2.7 feet per year.

### **1.3 Nature and Extent of Contamination**

The chemicals of concern (COC) of the Site are trichloroethylene and its daughter compounds (cis-1,2-dichloroethene and vinyl chloride). According to previous environmental reports, the area of former degreaser pit (area of groundwater monitoring wells PW-3 and PW-3R) is a likely source area for the COC plume. The plume originates from the degreaser area and has affected groundwater in the upper and lower sand/gravel layers. The plume extends from the degreaser area to the north, under the JCC building and up to the area of the Chadakoin River. This is an area of approximately one acre. Sampling in the River has not shown any impact to date.

Total volatile organic compound (VOC) concentrations range between 4.2 to 3,446 ug/L. The volume of the COC plume extends from the degreaser pits to the southern façade of the JCC building (approximate area of 5,000 square feet), then vertically down to the base of the second sand/gravel layer (43 feet BGS); a total volume of approximately 8,333 cubic yards of groundwater and subsurface soil.

**Table 1** presents the 2013 baseline groundwater monitoring data. **Table 2** presents data for the pre-treatment and post-treatment groundwater monitoring events. Another groundwater monitoring event was conducted on June 2019. Sampling data will be submitted as a separate report to the NYSDEC.

#### **1.4 Site History**

The property was first developed in 1890 as a woolen mill until 1939 when it was converted into a factory which manufactured steel partitions used for offices. In 1986 the deed was transferred to the Dowcraft Corporation. Manufacturing activities continued until the facility closed in 1999. As part of this manufacturing process, a vapor degreaser was used which included the use of chemicals such as trichloroethylene (TCE). This work continued until 1999 when the facility was closed, a portion of the Site was demolished, and the property was sold to JCC.

**Figure 1** presents present and historic site features.

The Dowcraft, South Dow Street Site was the subject of environmental investigations in the early 1990s, at which time contaminated groundwater was discovered on site. An interim remedial measure (IRM) was subsequently put in place in 1994 which consisted of groundwater extraction and treatment. In 2000, the use of additional groundwater remediation technologies was approved by the NYSDEC which involved in-situ chemical oxidation of TCE through the injection of potassium permanganate into the overburden groundwater. In 2003, a Record of Decision (ROD) was approved that selected the following remedy:

- In-situ groundwater treatment through chemical oxidation, by injection of potassium permanganate dissolved in water through existing well points into the shallow overburden groundwater table;
- Overburden groundwater monitoring to verify the effectiveness of the treatment;
- Institutional controls to prevent the use of groundwater as a source of potable water; and
- Annual certification to NYSDEC to certify that institutional controls remain in place.

Conestoga-Rovers & Associates (CRA) conducted nine injection treatments between May 2000 and July 2006, totaling 21,500 pounds of potassium permanganate. These injection treatments were successful in oxidizing TCE in outer plume area; however, the concentrations of TCE in the source area remain high.

#### 2014 and 2015 In-situ Remedial Activities

In May 2013, C&S was asked to re-evaluate the environmental conditions of the Site. On July 2013, baseline groundwater monitoring was conducted to determine the changes, if any, in TCE concentrations since 2006. Based on the findings of this work, a Corrective Measures Work Plan was submitted to the NYSDEC on May 2, 2014. C&S proposed additional in-situ chemical oxidation (ISCO) injections and the installation of a potassium permanganate treatment fence. This work was conducted on December 1 through 9, 2014.

Ten borings were each injected with approximately 33 gallons ISCO solution containing approximately 400 pounds of ISCO material. As the solution was pumped into the subsurface, the drill rods were lifted at a rate designed to inject a consistent amount of materials between 5 and 30 feet below grade. A total of 4,024.12 pounds of potassium permanganate was injected into the TCE plume.

Within the lower sand/gravel layer, the area adjacent to PW-3R contains the highest concentrations of TCE. To address these concentrations, a treatment fence was installed to reduce source loading into downgradient groundwater zones. The treatment fence consisted of 1.5 foot long tubes of paraffin wax mixed with potassium permanganate installed in selected monitoring wells and in the subsurface. A 36-foot treatment fence was installed next to the northwest corner of the building. A total of ten borings to 40 feet below grade were drilled to facilitate the installation of the treatment fence. A potassium permanganate cylinder was dropped down the drill casing. Four feet of casing was removed allowing the bore hole to collapse and another cylinder was placed in series until a total of 5 cylinders were installed (a vertical treatment thickness of approximately 7.5 feet in each boring).

## **2 MONITORING PLAN COMPLIANCE REPORT**

The monitoring plan developed by C&S for the Site includes both chemical and hydraulic monitoring of groundwater before and after treatment semi-annually for two years (sampling frequency was changed in the 2018 Operation, Monitoring and Maintenance Plan). Baseline groundwater monitoring was performed on July 2, 2013 and the chemical data is provided in **Table 1**. The following monitoring wells are included in the groundwater monitoring plan:

ESI - 1	ESI - 11
ESI - 2	ESI - 12
ESI - 3	ESI -13R
ESI - 6	PW - 1
ESI - 7	PW - 3R
ESI - 10	

The groundwater monitoring activities included the collection of depth-to-water measurements at each monitoring well and the collection of groundwater samples

for laboratory analysis. Pre-treatment sampling was conducted on October 21, 22 and 29, 2014 and post-treatment sampling was conducted on:

April 21 and 22, 2015	1 <sup>st</sup> Post-treatment
November 2 and 3, 2015	2 <sup>nd</sup> Post-treatment
April 25 and 26, 2016	3 <sup>rd</sup> Post-treatment
October 20 and 21, 2016	4 <sup>th</sup> Post-treatment
June 7 and 8, 2017	5 <sup>th</sup> Post-treatment
May 7 and 8, 2018	6 <sup>th</sup> Post-treatment (1 <sup>st</sup> Annual Sample Event under new OM&M)
June 25 and 25, 2019	7 <sup>th</sup> Post-treatment (2 <sup>nd</sup> Annual Sample Event under new OM&M)
July 15 and 16, 2020	8 <sup>th</sup> Post-treatment (3 <sup>rd</sup> Annual Sample Event under new OM&M)

Groundwater sampling was conducted in accordance with the U.S. Environmental Protection Agency Low flow sample procedure.

### **3 REMEDY PERFORMANCE, EFFECTIVENESS AND PROTECTIVENESS**

Contaminant concentrations appeared to have decreased, although some increases were also observed. The table below presents a comparison of total VOC



concentrations from each monitoring well and the percent change from pre-treatment and post-treatment groundwater monitoring.

**CHANGE IN VOC CONCENTRATION 2014-2020**

<i>Monitoring Well</i>	<i>Total VOC Concentration (ug/L)</i>		<i>Percent Change</i>
	<i>Pre-Treatment October 2014</i>	<i>Post-Treatment July 2020</i>	
PW-1	16.9	35.29	+108.8%
PW-3R	2,609.3	2,335.6	-10.5%
ESI-1	8.9	7.73	-13.15%
ESI-2	816.08	2,638	+223.25%
ESI-3	4.8	5.47	+14%
ESI-6	575.22	29	-94.96%
ESI-7	208.39	45.44	-78.19%
ESI-10	352.11	15	-95.74%
ESI-11	157	14.41	-90.82%
ESI-12	221.48	7.86	-96.45%
ESI-13R	40	18.08	-54.8%

Out of eleven monitoring wells, six wells show significant decreases, over 40%, in TCE and other chlorinated compounds from the first initial sampling event in 2014. Only three wells showed an increase in total VOC concentrations from the previous sampling event in 2019. Wells inside the JCC building (ESI-10, ESI-11 and ESI-12) showed a continuation of non-detect for TCE. PW-3R shows a decrease in DCE and vinyl chloride from the June 2019 sample event. TCE did rise from non-detect to 75.2 ug/l in PW-3R.

ESI-2, ESI-3, and PW-1 showed rebounds of chlorinated compounds from the December 2014 treatment event. ESI-2 still contains elevated levels of TCE and daughter compounds. Elevated concentrations were observed in sampling events conducted from April 2015 through October 2016. The reason for this observation is not clear, although a possible explanation is the injections caused the migration of groundwater with higher concentrations towards certain monitoring wells, or the ISCO materials may have increased the mobilization of contaminants that may have adhered to soil particles. However, these monitoring wells have increased levels of daughter compounds of TCE, indicating that reductive de-chlorination of TCE is taking place as a result of the potassium permanganate treatment overall when compared to previous treatments, compared to the initially sampling event in 2014.

Historic concentrations of TCE and its daughter compounds from October 2005 to July 2020 are presented on **Figures 2, 3, and 4**. Laboratory analytical results and Data Usability Summary Report (DUSR) are provided in **Appendix A**.

## 4 IC/EC PLAN COMPLIANCE REPORT

### 4.1 IC/EC Requirements and Compliance

As stated in the 2003 ROD, the remedial goals selected for this Site are:

- Treat the source area of groundwater contamination by oxidation dechlorination of the contaminants in place;
- Prevent exposure of human receptors to contaminated groundwater in the sand and gravel unit under Site;
- Prevent or mitigate, to the maximum extent practicable, COC migration via groundwater so that releases from the underlying sand and gravel unit to the Chadakoin River do not exceed applicable standards, criteria and guidance.

#### 4.1.1 Institutional Controls

The institutional controls for this Site are:

- Groundwater Use Restriction
- Land Use Restriction
- Monitoring Plan
- Operation and Monitoring Plan

The Site has not changed owners and the land use of the Site has not change. A signed certification that groundwater is not utilized is provided by the property owner in **Appendix B**.

#### 4.1.2 Engineering Controls

As specified under the Engineering Control Provision, any future development on the Site will include provisions for soil gas controls, or an assessment demonstrating that such controls are not needed.

The soil vapor intrusion (SVI) work plan, submitted on February 20, 2015, targeted areas in the main JCC building and one smaller out building to determine if TCE and other chlorinated compounds in the groundwater have impacted the soil vapor and indoor air quality.

The main JCC building is a linear building that begins at South Dow Street and extends approximately 1,060 feet to the northeast. The main building consists of multiple interconnected buildings that have been added throughout its history. The main building consists of the following portions, starting from South Dow Street:

- Four-story brick building, 55 feet long by 100 feet wide;

- Two-story brick building 300, feet long by 50 feet wide;
- One-story brick building 380, feet long by 80 feet wide; and
- One-story steel building 325, feet long by 100 feet wide.

A second, one-story concrete block building (220 feet long by 50 feet wide), referred by JCC as Building #9, is south of the main building. Building #9 is used for manufacturing.

#### Building #9 SSD System

Two multi-suction point SSD systems were installed by Mitigation Tech using principles and equipment typically used for soil vapor intrusion mitigation in buildings in compliance with the NYSDOH document, "Guidance for Evaluation Soil Vapor Intrusion in the State of New York, October 2006."

The building was assessed by confirmatory sub-slab air communication testing at the job start to refine data obtained from the preliminary building assessment. The system, comprised of two fans, suction cavities, and other SSD system components, was constructed on March 21 through 27, 2017. Vacuum and air flow measurements were performed continuously during construction to ensure design integrity.

A detailed description of the SSDS components are provided in **Appendix D**.

#### Building #5 and #6 SSD System

Mitigation Tech installed five single suction point SSD systems using principles and equipment typically used for soil vapor intrusion mitigation in buildings in compliance with the NYSDOH document, "Guidance for Evaluation Soil Vapor Intrusion in the State of New York, October 2006."

The building was assessed by extensive sub-slab air communication testing at job start to refine data obtained from the preliminary building assessment. Due to a system of sub-slab structural arches and crisscrossing grade beams, sub-slab spaces were either inaccessible or difficult to access. In the case of Building 5, extensive backfilling has occurred such that the soil is present immediately below the floor in the central and northernmost portions of the foundation. The southernmost portion is an open crawlspace with a dirt floor. Mitigation Tech determined that active ventilation of the southernmost sub-slab compartment bounded by buildings 4 and 6A would constitute a zone of defense to intercept soil vapor migrating from the south which would also create some limited depressurization north of the first grade beam. In the case of Building 6, the sub-space is in essence a crawlspace so ventilation was determined the most appropriate strategy to divert vapors from the building interior.

A detailed description of the SSDS components are provided in **Appendix D**.

## **4.2 IC/EC Certification**

As required, the Site Management Periodic Review Report Notice – Institutional and Engineering Controls Certificate Form has been completed and a copy is provided in **Appendix C**.

## **5 OPERATION AND MAINTENANCE PLAN COMPLIANCE**

An updated Operation, Maintenance and Monitoring (OM&M) Work Plan was approved by the NYSDEC in March 2018. The updated Work Plan includes monitoring the natural attenuation of the groundwater contamination and periodic inspection of two soil vapor mitigation systems over five years. The Remedial Action Monitoring Program consists of monitoring Site groundwater on an annual basis and the performance of the SSDS on a monthly and annual basis.

**Appendix D** provides the approved OM&M Work Plan

### **5.1 Groundwater Monitoring Wells**

The following maintenance items were identified:

- No maintenance items were identified at this time.

### **5.2 Soil Vapor Mitigation Systems**

#### **5.2.1 Monthly Monitoring**

Monthly monitoring will be conducted as follows:

- Inspect fan vacuum indicator to verify that the value indicated by a mark on the gauge has not changed significantly from the position of the mark. The gauge is inspected by observing the level of colored fluid.
- Record the observed measurement for each fan vacuum indicator on form labeled “SSD System Vacuum Gauge Record”. Store all forms in the facility maintenance office.
- Inspect visible components of SSD system for degraded condition.

#### **5.2.2 Annual Inspection**

Annual inspection will be conducted as follows:

- Conduct a visual inspection of the complete system (e.g., vent fans, piping, warning devices, labeling).
- Inspect all components for condition and proper operation.

- Identify and repair any leaks in accordance with Sections 4.3.1(a) and 4.3.4(a) of the NYS DOH VI Guidance (i.e., with the systems running, use smoke sticks to check for leaks through concrete cracks, floor joints and at the suction points; any leaks will be resealed until smoke is no longer observed flowing through the opening).
- Inspect the exhaust or discharge point of each exhaust fan to verify that no air intakes have been located within 10 feet.
- Conduct pressure field extension testing to ensure that the system is maintaining a vacuum beneath the entire slab. Perform a differential pressure reading at least one vacuum test point.
- Interview appropriate building occupants seeking comments and observations regarding the operation of the system.
- Confirm that the circuit breakers controlling the circuits on which the soil vapor vent fans operate are labeled "Soil Vapor System."

#### 5.2.2.1 SSDS Inspection

On October 30, 2020, Mitigation Tech performed a complete inspection of all system components. Mitigation Tech certifies both systems are effectively maintaining sub-slab depressurization.

After Mitigation Tech's inspection a five gaps and openings on the northern façade of Building #5 and 6 were identified. These gaps and openings reduced the effectiveness of the SSDS in these buildings; however, the gauges still recorded negative pressure. In order to improve the SSDS effectiveness JCC blocked up all five gaps and openings on November 18, 2020.

Mitigation Tech's inspection reports are provided in **Appendix E**.

## **6 CONCLUSIONS AND RECOMMENDATIONS**

Based upon the remedial activities performed, the following conclusions have been formulated:

- All of the required work was completed and is reported herein.
- The remedial activities performed at the Site have prevented any adverse risk to human health and the environment.
- The groundwater flow configuration beneath the Site is stable and remains consistent with the historically identified trends. The groundwater flow is to the north and discharges into the Chadakoin River.

- Sampling suggests the effectiveness of potassium permanganate injections and cylinders may be waning at treating the groundwater contaminants in many well.
- The SVI systems comprised of a SSD system for Building 9 and a SSD system and CVS for Buildings 5 and 6 were properly installed and verified for effectiveness. The primary objective of implementing these systems was to mitigate potential intrusion of soil vapors.


In addition to the groundwater monitoring under the OM&M Plan and PRR, C&S investigated remedial options in order to reduce CVOC concentrations around PW-3R, ESI-2 and ESI-10. Various remedial methods were evaluated based on their logistic and financial feasibility. On March 20, 2020 the NYSDEC approved C&S's Work Plan to further investigate the Site prior to the next injection event.

Below is an anticipated schedule of milestones for the remediation of the Site.

<b><u>Anticipated Date</u></b>	<b><u>Milestone</u></b>
Early February 2020	Remedial Action Work Plan Submission
Late March 2020	Work Plan Approved
Early January 2021	Pre-treatment Investigation
Late April 2021	ERD/ISCR Treatment
Late July 2021	Post-treatment Groundwater Monitoring
Mid August 2021	Injection/Groundwater Monitoring Report Submission
Early September 2021	Discuss Injection/Groundwater Monitoring Report with DEC
Late November 20201	Periodic Review Report Submission
Late December 2021	Periodic Review Report Acceptance by DEC

# FIGURES


F:\Project\N30 - Jamestown Container\Environmental\CADD-GIS\Sheet Files\FIGURE 1 HISTORIC AND EXISTING SITE FEATURES.dwg



- LEGEND**
- MONITORING WELL
  - ⊠ SURFACE WATER SAMPLE LOCATION
  - BOREHOLE
  - ⊞ SURFACE SOIL SAMPLE LOCATION
  - ▲ PURGE WELL
  - △ DRYWELL


**NOTES**

1. Drawing from CRA "Final Supplemental Remedial Investigation Report/Focused Feasibility Study," Figure 5.1: Sample Locations, 2001.



C&S  
COMPANIES®

C&S Engineers, Inc.  
141 Elm Street,  
Buffalo, New York 14203  
Phone: 716-847-1630  
Fax: 716-847-1454  
www.cscos.com



FORMER DOWCRAFT FACILITY  
GROUNDWATER REMEDIATION

FALCONER, NEW YORK

REVISIONS		
MARK	DATE	DESCRIPTION



PROJECT NO:	N30.001.001
DATE:	JUNE 6, 2016
DRAWN BY:	C. MARTIN
DESIGNED BY:	C. MARTIN
CHECKED BY:	D. RIKER

NO ALTERATION PERMITTED HEREON EXCEPT AS PROVIDED UNDER SECTION 7209 SUBDIVISION 2 OF THE NEW YORK EDUCATION LAW

**HISTORIC AND  
EXISTING SITE  
FEATURES**

**FIGURE 1**







**FORMER DOWCRAFT FACILITY -  
 PERIODIC REVIEW REPORT  
 FALCONER, NEW YORK**

MARK	DATE	DESCRIPTION
REVISIONS		
PROJECT NO: N30.001.001		
DATE: NOVEMBER 18, 2020		
DRAWN BY: C. MARTIN		
DESIGNED BY: C. MARTIN		
CHECKED BY: D. RIKER		
NO ALTERATION PERMITTED HEREON EXCEPT AS PROVIDED UNDER SECTION 7209 SUBDIVISION 2 OF THE NEW YORK EDUCATION LAW		

**TRICHLOROETHYLENE  
 CONCENTRATIONS**

FIGURE 2




**FORMER DOWCRAFT FACILITY -  
 PERIODIC REVIEW REPORT  
 FALCONER, NEW YORK**

**LEGEND**  
 ◆ MONITORING WELL  
 □ HISTORIC BUILDINGS (DEMOLISHED)

**LABEL LEGEND**

PW-3R	SAMPLE ID
190,000	CONCENTRATION (ug/L) OCTOBER 2005
ND	CONCENTRATION (ug/L) NOVEMBER 2006
120,000	CONCENTRATION (ug/L) SEPTEMBER 2007
79,000	CONCENTRATION (ug/L) DECEMBER 2007
5,450	CONCENTRATION (ug/L) SEPTEMBER 2008
40,000	CONCENTRATION (ug/L) DECEMBER 2008
ND	CONCENTRATION (ug/L) JUNE 2009
23,000	CONCENTRATION (ug/L) DECEMBER 2009
27,000	CONCENTRATION (ug/L) OCTOBER 2010
97,000	CONCENTRATION (ug/L) JULY 2013
0.79	CONCENTRATION (ug/L) OCTOBER 2014
ND	CONCENTRATION (ug/L) APRIL 2015
ND	CONCENTRATION (ug/L) NOVEMBER 2015
17.2	CONCENTRATION (ug/L) APRIL 2016
84.4	CONCENTRATION (ug/L) OCTOBER 2016
229	CONCENTRATION (ug/L) JUNE 2017
2.1	CONCENTRATION (ug/L) MAY 2018
ND	CONCENTRATION (ug/L) JUNE 2019
809	CONCENTRATION (ug/L) JULY 2020





MARK	DATE	DESCRIPTION
REVISIONS		
PROJECT NO: N30.001.001		
DATE: NOVEMBER 18, 2020		
DRAWN BY: C. MARTIN		
DESIGNED BY: C. MARTIN		
CHECKED BY: D. RIKER		

NO ALTERATION PERMITTED HEREON EXCEPT AS PROVIDED UNDER SECTION 7209 SUBDIVISION 2 OF THE NEW YORK EDUCATION LAW

cis-1,2-DICHLOROETHENE  
 CONCENTRATIONS

FIGURE 3



**FORMER DOWCRAFT FACILITY -  
 PERIODIC REVIEW REPORT**  
**FALCONER, NEW YORK**

MARK	DATE	DESCRIPTION
REVISIONS		
PROJECT NO: N30.001.001		
DATE: NOVEMBER 18, 2020		
DRAWN BY: C. MARTIN		
DESIGNED BY: C. MARTIN		
CHECKED BY: D. RIKER		

NO ALTERATION PERMITTED HEREON EXCEPT AS PROVIDED UNDER SECTION 7209 SUBDIVISION 2 OF THE NEW YORK EDUCATION LAW

**VINYL CHLORIDE  
 CONCENTRATIONS**

**FIGURE 4**

# TABLES

**TABLE 1: JULY 2013 GROUNDWATER ANALYTICAL RESULTS - VOLATILE ORGANIC COMPOUNDS  
FORMER DOWCRAFT FACILITY**

Sample Location	NYSDEC Standards & Guidance Values	ESI - 1	ESI - 2	ESI - 3	ESI - 6	ESI - 7	ESI - 10	ESI - 11	ESI - 12	ESI - 13R	PW - 1	PW - 3R
		2-Jul-13	2-Jul-13	2-Jul-13	2-Jul-13	2-Jul-13	2-Jul-13	2-Jul-13	2-Jul-13	2-Jul-13	2-Jul-13	2-Jul-13
Sample Date	Matrix Units	Water	Water	Water	Water	Water	Water	Water	Water	Water	Water	Water
Matrix Units		ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L	ug/l	ug/l	ug/l
Contaminant												
Volatile Organic Compounds												
Acetone	50	<10.0	<10.0	<10.0		<10.0	<10.0	<10.0				13
Benzene	1	<0.70	<0.70	<0.70		<0.70	<0.70	<0.70				0.88 J
Carbon disulfide	N/S	<2.0	1.3	<2.0		<2.0	<2.0	<2.0				5.0
1,1-Dichloroethane	5	<2.0	<2.0	<2.0		<2.0	<2.0	<2.0				5.5
1,2-Dichloroethane	0.6	<2.0	<2.0	<2.0		<2.0	<2.0	<2.0				1.2
1,1-Dichloroethene	5	<2.0	2.8	<2.0	1.6	<2.0	0.34 J	<2.0				48
cis-1,2-Dichloroethene	5	1.1	1,900	<2.0	230	1.9	160	39	48	2.7	2.7	27,000 DL
trans-1,2-Dichloroethene	5	<2.0	13	<2.0	1.2	<2.0	1.6	<2.0				500 E
1,2-Dichloropropane	1	<2.0	<2.0	<2.0		<2.0	<2.0	<2.0				2.2
Ethylbenzene	5	<2.0	<2.0	<2.0		<2.0	<2.0	<2.0				0.77 J
Methylene Chloride	5	<5.0	<5.0	<5.0		<5.0	<5.0	<5.0				1.3
4-Methyl-2-pentanone	N/S	<5.0	<5.0	<5.0		<5.0	<5.0	<5.0				2.6 J
Tetrachloroethene	5	<2.0	0.55 J	<2.0	0.88 J	<2.0	<2.0	<2.0				18
1,1,2-Trichloroethane	1	<2.0	<2.0	<2.0		<2.0	<2.0	<2.0				2.8
Trichloroethene	5	8.2	98	6.3	230	21	18	4.2	92	8.9	11	97000 DL
Toluene	5	<2.0	<2.0	<2.0		<2.0	<2.0	<2.0				18
Vinyl chloride	2	<2.0	800	<2.0	73	<2.0	11	75				6300 DL
Xylene (total)	5	<2.0	<2.0	<2.0		<2.0	<2.0	<2.0				4.8
<b>Total VOCs</b>		<b>9.3</b>	<b>2815.65</b>	<b>6.3</b>	<b>536.68</b>	<b>22.9</b>	<b>190.94</b>	<b>118.2</b>	<b>140</b>	<b>11.6</b>	<b>13.7</b>	<b>130924</b>

Notes

- 1) Shaded areas indicate concentration exceeds NYSDEC T.O.G.S 1.1.1 Ambient Water Quality Standards
- 2) < = not detected - below Method Detection Limit.
- 3) J = The analyte was positively identified but, the number indicates an estimated value. Detected concentration is less than the contract required quantitation limit but is greater than zero.
- 4) N/S = No Standard

TABLE 2

**GROUNDWATER RESULTS  
FORMER DOWCRAFT FACILITY  
FALCONER, NEW YORK**



Location ID	NY-TOGs GA- WtrClass GuidValues	NY-TOGs GA- WtrClass StdValues	ESI-1 12/2/2014 Water ug/l	ESI-1 4/21/2015 Water ug/l	ESI-1 11/3/2015 Water mg/l	ESI-1 4/25/2016 Water ug/l	ESI-1 10/20/2016 Water mg/l	ESI-1 6/7/2017 Water ug/l	ESI-1 5/7/2018 Water mg/l	ESI-1 6/26/2019 Water ug/l	ESI-1 7/15/2020 Water mg/l	ESI-2 12/2/2014 Water ug/l	ESI-2 4/22/2015 Water ug/l	ESI-2 11/3/2015 Water mg/l	ESI-2 4/25/2016 Water ug/l	ESI-2 10/21/2016 Water mg/l				
<b>VOCs</b>																				
1,1,1-Trichloroethane		5	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND				
1,1-Dichloroethane		5	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND				
1,1-Dichloroethene		5	ND	ND	ND	ND	ND	ND	ND	ND	ND	1.1	ND	12.0	ND	ND				
1,2-Dichlorobenzene		3	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND				
1,2-Dichloroethane		0.6	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND				
1,4-Dichlorobenzene		3	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND				
Acetone	50		ND	ND	ND	ND	ND	ND	ND	2.2	J	ND	ND	ND	ND	ND				
Benzene		1	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND				
Bromoform	50		ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND				
Carbon tetrachloride		5	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND				
Chlorobenzene		5	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND				
Dibromochloromethane	50		ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND				
Chloroform		7	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND				
61		5	ND	4.4	ND	ND	ND	ND	ND	0.7	J	1.0	J	540.0	E	740.0	4400.0	E	5290.0	592.0
Ethylbenzene		5	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND				
Methylene Chloride		5	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	7.9	J	ND	ND	ND			
Tetrachloroethene		5	ND	ND	ND	ND	ND	ND	ND	ND	ND	0.48	J	ND	ND	ND				
Toluene		5	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND				
trans-1,2-Dichloroethene		5	ND	ND	ND	ND	ND	ND	ND	ND	ND	4.5	ND	19.0	ND	ND				
Trichloroethene		5	8.9	15.0	12.0	4.9	6.5	3.7	4.4	10.0	6.7	130.0	E	110.0	1100.0	E	1260.0	303.0		
Vinyl chloride		2	ND	ND	ND	ND	ND	ND	ND	ND	ND	130.0	E	130.0	320.0	289.0	ND			
Xylenes, Total			ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND				
<b>Total VOC</b>			<b>8.9</b>	<b>19.4</b>	<b>12.0</b>	<b>4.9</b>	<b>6.5</b>	<b>3.7</b>	<b>4.4</b>	<b>12.9</b>	<b>7.7</b>	<b>806.1</b>		<b>987.9</b>	<b>5851.0</b>	<b>6839.0</b>	<b>895.0</b>			

ND indicates analyte was not detected.  
 Blank space indicates analyte was not analyzed for in that sample.  
 ^ - ICV,CCV,ICB,CCB, ISA, ISB, CRI, CRA,  
 DLCK or MRL standard: Instrument related QC  
 is outside acceptance limits.  
 F1 - MS and/or MSD recovery exceeds control limits.  
 F2 - MS/MSD RPD exceeds control limits  
 J - Result is less than the RL but greater than or  
 equal to the MDL and the concentration is an  
 approximate value.

TABLE 2

**GROUNDWATER RESULTS  
FORMER DOWCRAFT FACILITY  
FALCONER, NEW YORK**



Location ID	NY-TOGs GA- WtrClass GuidValues	NY-TOGs GA- WtrClass StdValues	ESI-2 6/8/2017 Water ug/l	ESI-2 5/8/2018 Water mg/l	ESI-2 6/26/2019 Water ug/l	ESI-2 7/15/2020 Water mg/l	ESI-3 10/21/2014 Water ug/l	ESI-3 4/22/2015 Water ug/l	ESI-3 11/2/2015 Water mg/l	ESI-3 4/25/2016 Water ug/l	ESI-3 10/20/2016 Water mg/l	ESI-3 6/7/2017 Water ug/l	ESI-3 5/8/2018 Water mg/l	ESI-3 6/26/2019 Water ug/l	ESI-3 7/15/2020 Water mg/l	ESI-6 10/29/2014 Water ug/l		
<b>VOCs</b>																		
1,1,1-Trichloroethane		5	Well cap damaged. Sample not collected.	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND		
1,1-Dichloroethane		5		ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	
1,1-Dichloroethene		5		ND	3.7	J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	1.6	
1,2-Dichlorobenzene		3		ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	
1,2-Dichloroethane		0.6		ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	
1,4-Dichlorobenzene		3		ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	
Acetone	50			ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	3.4	J	ND	
Benzene		1		ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	
Bromoform	50			ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	
Carbon tetrachloride		5		ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	
Chlorobenzene		5		ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	
Dibromochloromethane	50			ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	
Chloroform		7		ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	
61		5		480.0	1400.0		1910.0	ND	ND	ND	ND	1.4	J	ND	ND	ND	210.0	E
Ethylbenzene		5		ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	
Methylene Chloride		5		ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	
Tetrachloroethene		5		ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	1.1	
Toluene		5		ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	
trans-1,2-Dichloroethene		5		27.0	18.0	J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	2.2	
Trichloroethene		5		450.0	690.0		708.0	4.8	2.5	4.8	1.06	J	7.0	ND	0.3	0.8	5.5	200.0
Vinyl chloride		2	ND	120.0		20.3	J	ND	ND	ND	ND	ND	ND	ND	ND	160.0	E	
Xylenes, Total			ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND		
<b>Total VOC</b>			<b>957.0</b>	<b>2231.7</b>		<b>2638.3</b>	<b>4.8</b>	<b>2.5</b>	<b>4.8</b>	<b>1.1</b>	<b>8.4</b>	<b>0.0</b>	<b>0.3</b>	<b>4.2</b>	<b>5.5</b>	<b>574.9</b>		

ND indicates analyte was not detected.  
 Blank space indicates analyte was not analyzed for in that sample.  
 ^ - ICV,CCV,ICB,CCB, ISA, ISB, CRI, CRA,  
 DLCK or MRL standard: Instrument related QC  
 is outside acceptance limits.  
 F1 - MS and/or MSD recovery exceeds control limits.  
 F2 - MS/MSD RPD exceeds control limits  
 J - Result is less than the RL but greater than or  
 equal to the MDL and the concentration is an  
 approximate value.

TABLE 2

**GROUNDWATER RESULTS  
FORMER DOWCRAFT FACILITY  
FALCONER, NEW YORK**



Location ID	NY-TOGs GA- WtrClass GuidValues	NY-TOGs GA- WtrClass StdValues	ESI-6 4/22/2015 Water ug/l	ESI-6 11/2/2015 Water mg/l	ESI-6 4/25/2016 Water ug/l	ESI-6 10/21/2016 Water mg/l	ESI-6 6/8/2017 Water ug/l	ESI-6 5/8/2018 Water mg/l	ESI-6 6/26/2019 Water ug/l	ESI-6 7/15/2020 Water mg/l	ESI-7 10/21/2014 Water ug/l	ESI-7 4/21/2015 Water ug/l	ESI-7 11/2/2015 Water mg/l	ESI-7 4/25/2016 Water ug/l	ESI-7 10/20/2016 Water mg/l	ESI-7 6/8/2017 Water ug/l		
<b>VOCs</b>																		
1,1,1-Trichloroethane		5	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND		
1,1-Dichloroethane		5	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND		
1,1-Dichloroethene		5	ND	3.9	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND		
1,2-Dichlorobenzene		3	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND		
1,2-Dichloroethane		0.6	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND		
1,4-Dichlorobenzene		3	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND		
Acetone	50		ND	ND	ND	ND	ND	2.4	J	7.7	15.8	ND	ND	ND	ND	6.89	J	10.1
Benzene		1	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	
Bromoform	50		ND	ND	ND	ND	ND	ND	1.2	J	13.2	ND	ND	ND	ND	ND	ND	
Carbon tetrachloride		5	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	
Chlorobenzene		5	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	
Dibromochloromethane	50		ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	
Chloroform		7	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	
61		5	1100.0	1000.0	322.0	626.0	181.0	5.3	80.0	ND	78.0	25.0	12.0	8.3	25.0	5.2		
Ethylbenzene		5	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	
Methylene Chloride		5	10.0	J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	
Tetrachloroethene		5	ND	5.8	ND	ND	ND	1.4	1.6	ND	0.39	J	ND	ND	ND	ND	ND	
Toluene		5	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	
trans-1,2-Dichloroethene		5	ND	4.0	ND	11.1	J	ND	ND	1.2	J	ND	ND	ND	ND	ND	ND	
Trichloroethene		5	810.0	1500.0	E	924.0	1060.0	431.0	40.0	200.0	ND	150.0	E	78.0	57.0	43.0	106.0	21.0
Vinyl chloride		2	100.0	68.0	21.7	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	
Xylenes, Total			ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	
<b>Total VOC</b>			<b>2020.0</b>	<b>2581.7</b>	<b>1267.7</b>	<b>1697.1</b>	<b>612.0</b>	<b>49.1</b>	<b>291.7</b>	<b>29.0</b>	<b>228.4</b>	<b>103.0</b>	<b>69.0</b>	<b>51.3</b>	<b>137.9</b>	<b>36.3</b>		

ND indicates analyte was not detected.  
 Blank space indicates analyte was not analyzed for in that sample.  
 ^ - ICV,CCV,ICB,CCB, ISA, ISB, CRI, CRA,  
 DLCK or MRL standard: Instrument related QC  
 is outside acceptance limits.  
 F1 - MS and/or MSD recovery exceeds control limits.  
 F2 - MS/MSD RPD exceeds control limits  
 J - Result is less than the RL but greater than or  
 equal to the MDL and the concentration is an  
 approximate value.



TABLE 2

GROUNDWATER RESULTS  
FORMER DOWCRAFT FACILITY  
FALCONER, NEW YORK



Location ID	NY-TOGs GA- WtrClass GuidValues	NY-TOGs GA- WtrClass StdValues	ESI-7 5/7/2018 Water mg/l	ESI-7 6/26/2019 Water ug/l	ESI-7 7/15/2020 Water mg/l	ESI-10 11/3/2015 Water ug/l	ESI-10 4/26/2016 Water mg/l	ESI-10 10/20/2016 Water ug/l	ESI-10 6/7/2017 Water ug/l	ESI-10 5/7/2018 Water mg/l	ESI-10 6/25/2019 Water ug/l	ESI-10 7/15/2020 Water mg/l	ESI-11 10/29/2014 Water ug/l	ESI-11 4/21/2015 Water ug/l	ESI-11 11/3/2015 Water mg/l	ESI-11 4/26/2016 Water ug/l
<b>VOCs</b>																
1,1,1-Trichloroethane		5	ND		ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,1-Dichloroethane		5	ND		ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,1-Dichloroethene		5	ND		ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,2-Dichlorobenzene		3	ND		ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,2-Dichloroethane		0.6	ND		ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,4-Dichlorobenzene		3	ND		ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Acetone	50		ND		15.8	5.9 J	7.1 J	7.2 J	ND	ND	9.6	15.0	ND	3.9 J	7.0	32.4
Benzene		1	ND		ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Bromoform	50		ND		13.2	ND	ND	ND	3.01	ND	ND	ND	ND	ND	ND	ND
Carbon tetrachloride		5	ND		ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Chlorobenzene		5	ND		ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Dibromochloromethane	50		ND		ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Chloroform		7	ND		ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
61		5	30.0		5.9	ND	ND	ND	ND	ND	61.0	ND	ND	ND	ND	ND
Ethylbenzene		5	ND		ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Methylene Chloride		5	ND		ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Tetrachloroethene		5	ND		ND	ND	ND	ND	ND	ND	0.22 J	ND	ND	ND	ND	ND
Toluene		5	ND		ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
trans-1,2-Dichloroethene		5	ND		ND	ND	ND	ND	ND	ND	0.8 J	ND	ND	ND	ND	ND
Trichloroethene		5	52.0		39.5	ND	ND	ND	ND	0.94	84.0	ND	ND	ND	ND	ND
Vinyl chloride		2	ND		ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Xylenes, Total			ND		ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
<b>Total VOC</b>			<b>82.0</b>		<b>74.4</b>	<b>5.9</b>	<b>7.1</b>	<b>7.2</b>	<b>3.0</b>	<b>0.9</b>	<b>155.6</b>	<b>15.0</b>	<b>0.0</b>	<b>3.9</b>	<b>7.0</b>	<b>32.4</b>

ESI-7 was paved over. Well ESI-4 was alternatively sampled for PFAS.

ND indicates analyte was not detected.  
 Blank space indicates analyte was not analyzed for in that sample.  
 ^ - ICV,CCV,ICB,CCB, ISA, ISB, CRI, CRA,  
 DLCK or MRL standard: Instrument related QC  
 is outside acceptance limits.  
 F1 - MS and/or MSD recovery exceeds control limits.  
 F2 - MS/MSD RPD exceeds control limits  
 J - Result is less than the RL but greater than or  
 equal to the MDL and the concentration is an  
 approximate value.

TABLE 2

**GROUNDWATER RESULTS  
FORMER DOWCRAFT FACILITY  
FALCONER, NEW YORK**



Location ID	NY-TOGs GA- WtrClass GuidValues	NY-TOGs GA- WtrClass StdValues	ESI-11 10/20/2016 Water mg/l	ESI-11 6/7/2017 Water ug/l	ESI-11 5/7/2018 Water mg/l	ESI-11 6/25/2019 Water ug/l	ESI-11 7/15/2020 Water mg/l	ESI-12 10/22/2014 Water ug/l	ESI-12 4/21/2015 Water ug/l	ESI-12 11/3/2015 Water mg/l	ESI-12 4/26/2016 Water ug/l	ESI-12 10/21/2016 Water mg/l	ESI-12 6/7/2017 Water ug/l	ESI-12 5/8/2018 Water mg/l	ESI-12 6/25/2019 Water ug/l	ESI-12 7/15/2020 Water mg/l
<b>VOCs</b>																
1,1,1-Trichloroethane		5	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,1-Dichloroethane		5	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,1-Dichloroethene		5	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,2-Dichlorobenzene		3	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,2-Dichloroethane		0.6	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,4-Dichlorobenzene		3	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Acetone	50		ND	ND	2.6 J	24.0	5.64 J	ND	ND	5.6 J	5.84 J	6.19 J	ND	3.0 J	19.0	ND
Benzene		1	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	1.19
Bromoform	50		ND	4.78	ND	2.4	8.77	ND	ND	ND	ND	ND	14.50	ND	2.8	6.67
Carbon tetrachloride		5	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Chlorobenzene		5	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Dibromochloromethane	50		ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Chloroform		7	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
61		5	ND	ND	ND	ND	ND	71.0	1.2	ND	ND	ND	ND	ND	ND	ND
Ethylbenzene		5	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Methylene Chloride		5	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Tetrachloroethene		5	ND	ND	ND	ND	ND	0.5 J	0.54 J	ND	ND	ND	ND	ND	ND	ND
Toluene		5	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
trans-1,2-Dichloroethene		5	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Trichloroethene		5	ND	ND	ND	ND	ND	140.0 E	10.0	ND	ND	ND	ND	ND	ND	ND
Vinyl chloride		2	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Xylenes, Total			ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
<b>Total VOC</b>			<b>0.0</b>	<b>4.8</b>	<b>2.6</b>	<b>26.4</b>	<b>14.4</b>	<b>211.5</b>	<b>11.7</b>	<b>5.6</b>	<b>5.8</b>	<b>6.2</b>	<b>14.5</b>	<b>3.0</b>	<b>21.8</b>	<b>7.9</b>

ND indicates analyte was not detected.  
 Blank space indicates analyte was not analyzed for in that sample.  
 ^ - ICV,CCV,ICB,CCB, ISA, ISB, CRI, CRA,  
 DLCK or MRL standard: Instrument related QC  
 is outside acceptance limits.  
 F1 - MS and/or MSD recovery exceeds control limits.  
 F2 - MS/MSD RPD exceeds control limits  
 J - Result is less than the RL but greater than or  
 equal to the MDL and the concentration is an  
 approximate value.

TABLE 2

**GROUNDWATER RESULTS  
FORMER DOWCRAFT FACILITY  
FALCONER, NEW YORK**



Location ID	NY-TOGs GA- WtrClass GuidValues	NY-TOGs GA- WtrClass StdValues	ESI-13R 10/21/2014 Water ug/l	ESI-13R 4/21/2015 Water ug/l	ESI-13R 11/2/2015 Water mg/l	ESI-13R 4/25/2016 Water ug/l	ESI-13R 10/20/2016 Water mg/l	ESI-13R 6/7/2017 Water ug/l	ESI-13R 5/8/2018 Water mg/l	ESI-13R 6/26/2019 Water ug/l	ESI-13R 7/15/2020 Water mg/l	PW-1 10/21/2014 Water ug/l	PW-1 4/21/2015 Water ug/l	PW-1 11/2/2015 Water mg/l	PW-1 4/25/2016 Water ug/l	PW-1 10/20/2016 Water mg/l		
<b>VOCs</b>																		
1,1,1-Trichloroethane		5	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND		
1,1-Dichloroethane		5	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND		
1,1-Dichloroethene		5	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND		
1,2-Dichlorobenzene		3	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND		
1,2-Dichloroethane		0.6	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND		
1,4-Dichlorobenzene		3	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND		
Acetone	50		ND	ND	ND	ND	ND	ND	ND	2.4	J	ND	ND	ND	ND	ND		
Benzene		1	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND		
Bromoform	50		ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND		
Carbon tetrachloride		5	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND		
Chlorobenzene		5	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND		
Dibromochloromethane	50		ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND		
Chloroform		7	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND		
61		5	18.0	18.0	8.3	7.5	9.4	ND	1.30	J	1.90	J	4.38	1.90	8.8	2.40	5.03	7.14
Ethylbenzene		5	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND		
Methylene Chloride		5	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND		
Tetrachloroethene		5	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND		
Toluene		5	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND		
trans-1,2-Dichloroethene		5	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND		
Trichloroethene		5	22.0	46.0	19.0	21.0	13.0	7.4	7.3	18.0	13.7	15.0	3.30	11.0	6.96	22.1		
Vinyl chloride		2	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND		
Xylenes, Total			ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND		
<b>Total VOC</b>			<b>40.0</b>	<b>64.0</b>	<b>27.3</b>	<b>28.5</b>	<b>22.4</b>	<b>7.4</b>	<b>8.6</b>	<b>22.3</b>	<b>18.1</b>	<b>16.9</b>	<b>12.1</b>	<b>13.4</b>	<b>12.0</b>	<b>29.2</b>		

ND indicates analyte was not detected.  
 Blank space indicates analyte was not analyzed for in that sample.  
 ^ - ICV,CCV,ICB,CCB, ISA, ISB, CRI, CRA,  
 DLCK or MRL standard: Instrument related QC  
 is outside acceptance limits.  
 F1 - MS and/or MSD recovery exceeds control limits.  
 F2 - MS/MSD RPD exceeds control limits  
 J - Result is less than the RL but greater than or  
 equal to the MDL and the concentration is an  
 approximate value.

TABLE 2

**GROUNDWATER RESULTS  
FORMER DOWCRAFT FACILITY  
FALCONER, NEW YORK**



Location ID	NY-TOGs GA- WtrClass GuidValues	NY-TOGs GA- WtrClass StdValues	PW-1 6/8/2017 Water ug/l	PW-1 5/8/2018 Water mg/l	PW-1 6/26/2019 Water ug/l	PW-1 7/15/2020 Water mg/l	PW-3R 10/29/2014 Water ug/l	PW-3R 4/22/2015 Water ug/l	PW-3R 11/3/2015 Water mg/l	PW-3R 4/26/2016 Water ug/l	PW-3R 10/21/2016 Water mg/l	PW-3R 6/8/2017 Water ug/l				
<b>VOCs</b>																
1,1,1-Trichloroethane		5	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND				
1,1-Dichloroethane		5	ND	ND	ND	ND	5.1	4.0	ND	ND	ND	ND				
1,1-Dichloroethene		5	ND	ND	ND	ND	1.6	ND	3.9	ND	ND	ND				
1,2-Dichlorobenzene		3	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND				
1,2-Dichloroethane		0.6	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND				
1,4-Dichlorobenzene		3	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND				
Acetone	50		8.09	J	ND	2.4	J	ND	12.0	16.0	ND	11.3	J	12.3	J	ND
Benzene		1	ND	ND	ND	ND	0.6	J	0.5	J	ND	ND	ND	ND	ND	
Bromoform	50		ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	
Carbon tetrachloride		5	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	
Chlorobenzene		5	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	
Dibromochloromethane	50		ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	
Chloroform		7	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	
61		5	3.88	ND	ND	7.89	21.0	1.6	140.0	242.0	1450.0	1990.0				
Ethylbenzene		5	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	
Methylene Chloride		5	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	
Tetrachloroethene		5	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	
Toluene		5	ND	ND	ND	ND	8.1	6.9	8.0	J	4.9	ND	ND	ND	ND	
trans-1,2-Dichloroethene		5	ND	ND	ND	ND	39.0	ND	ND	ND	ND	ND	ND	10.2	ND	
Trichloroethene		5	8.39	0.84	1.8	27.4	0.79	ND	ND	17.2	84.4	229.0				
Vinyl chloride		2	ND	ND	ND	ND	1800.0	E	120.0	E	790.0	F1	134.0	751.0	861.0	
Xylenes, Total			ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	
<b>Total VOC</b>			<b>20.4</b>	<b>0.8</b>	<b>4.2</b>	<b>35.3</b>	<b>1888.2</b>	<b>149.0</b>	<b>941.9</b>	<b>409.4</b>	<b>2297.7</b>	<b>3090.2</b>				

ND indicates analyte was not detected.  
 Blank space indicates analyte was not analyzed for in that sample.  
 ^ - ICV,CCV,ICB,CCB, ISA, ISB, CRI, CRA,  
 DLCK or MRL standard: Instrument related QC  
 is outside acceptance limits.  
 F1 - MS and/or MSD recovery exceeds control limits.  
 F2 - MS/MSD RPD exceeds control limits  
 J - Result is less than the RL but greater than or  
 equal to the MDL and the concentration is an  
 approximate value.

TABLE 2

**GROUNDWATER RESULTS  
FORMER DOWCRAFT FACILITY  
FALCONER, NEW YORK**



Location ID	NY-TOGs GA- WtrClass GuidValues	NY-TOGs GA- WtrClass StdValues	PW-3R 5/8/2018 Water mg/l	PW-3R 6/26/2019 Water ug/l	PW-3R 7/15/2020 Water mg/l
<b>VOCs</b>					
1,1,1-Trichloroethane		5	ND	ND	ND
1,1-Dichloroethane		5	ND	ND	ND
1,1-Dichloroethene		5	ND	ND	ND
1,2-Dichlorobenzene		3	ND	ND	ND
1,2-Dichloroethane		0.6	ND	ND	ND
1,4-Dichlorobenzene		3	ND	ND	ND
Acetone	50		9.0	19.0 J	ND
Benzene		1	ND	ND	ND
Bromoform	50		ND	1.2 J	13.2
Carbon tetrachloride		5	ND	ND	ND
Chlorobenzene		5	ND	ND	ND
Dibromochloromethane	50		ND	ND	ND
Chloroform		7	ND	ND	ND
61		5	70.0	1200.0	809.0
Ethylbenzene		5	ND	ND	ND
Methylene Chloride		5	ND	ND	ND
Tetrachloroethene		5	ND	ND	ND
Toluene		5	4.6	7.3 J	ND
trans-1,2-Dichloroethene		5	2.2	20.0 J	11.4 J
Trichloroethene		5	ND	ND	75.2
Vinyl chloride		2	110.0	2200.0 E	1440.0
Xylenes, Total			ND	ND	ND
<b>Total VOC</b>			<b>195.8</b>	<b>3447.5</b>	<b>2348.8</b>

ND indicates analyte was not detected.

Blank space indicates analyte was not analyzed for in that sample.

^ - ICV,CCV,ICB,CCB, ISA, ISB, CRI, CRA,  
DLCK or MRL standard: Instrument related QC  
is outside acceptance limits.

F1 - MS and/or MSD recovery exceeds control limits.

F2 - MS/MSD RPD exceeds control limits

J - Result is less than the RL but greater than or  
equal to the MDL and the concentration is an  
approximate value.

# APPENDICES

APPENDIX A  
LABORATORY ANALYTICAL RESULTS



Lab Project ID: 203467

Client: Alpha Analytical

Project Reference: L2030254, C&S Companies, Jamestown Container

Sample Identifier: 30254-01 ESI-3-071520

Lab Sample ID: 203467-01

Date Sampled: 7/15/2020

Matrix: Groundwater

Date Received: 7/28/2020

**Volatile Organics**

Analyte	Result	Units	Qualifier	Date Analyzed
1,1,1-Trichloroethane	< 2.00	ug/L		7/28/2020 17:32
1,1,2,2-Tetrachloroethane	< 2.00	ug/L		7/28/2020 17:32
1,1,2-Trichloroethane	< 2.00	ug/L		7/28/2020 17:32
1,1-Dichloroethane	< 2.00	ug/L		7/28/2020 17:32
1,1-Dichloroethene	< 2.00	ug/L		7/28/2020 17:32
1,2,3-Trichlorobenzene	< 5.00	ug/L		7/28/2020 17:32
1,2,4-Trichlorobenzene	< 5.00	ug/L		7/28/2020 17:32
1,2,4-Trimethylbenzene	< 2.00	ug/L		7/28/2020 17:32
1,2-Dibromo-3-Chloropropane	< 10.0	ug/L		7/28/2020 17:32
1,2-Dibromoethane	< 2.00	ug/L		7/28/2020 17:32
1,2-Dichlorobenzene	< 2.00	ug/L		7/28/2020 17:32
1,2-Dichloroethane	< 2.00	ug/L		7/28/2020 17:32
1,2-Dichloropropane	< 2.00	ug/L		7/28/2020 17:32
1,3,5-Trimethylbenzene	< 2.00	ug/L		7/28/2020 17:32
1,3-Dichlorobenzene	< 2.00	ug/L		7/28/2020 17:32
1,4-Dichlorobenzene	< 2.00	ug/L		7/28/2020 17:32
1,4-Dioxane	< 20.0	ug/L		7/28/2020 17:32
2-Butanone	< 10.0	ug/L		7/28/2020 17:32
2-Hexanone	< 5.00	ug/L		7/28/2020 17:32
4-Methyl-2-pentanone	< 5.00	ug/L		7/28/2020 17:32
Acetone	< 10.0	ug/L		7/28/2020 17:32
Benzene	< 1.00	ug/L		7/28/2020 17:32
Bromochloromethane	< 5.00	ug/L		7/28/2020 17:32

This report is part of a multipage document and should only be evaluated in its entirety. The Chain of Custody provides additional sample information, including compliance with the sample condition requirements upon receipt.

Report Prepared Monday, August 3, 2020





Lab Project ID: 203467

Client: Alpha Analytical

Project Reference: L2030254, C&S Companies, Jamestown Container

<b>Sample Identifier:</b>	30254-01 ESI-3-071520		
<b>Lab Sample ID:</b>	203467-01	<b>Date Sampled:</b>	7/15/2020
<b>Matrix:</b>	Groundwater	<b>Date Received:</b>	7/28/2020
Bromodichloromethane	< 2.00	ug/L	7/28/2020 17:32
Bromoform	< 5.00	ug/L	7/28/2020 17:32
Bromomethane	< 2.00	ug/L	7/28/2020 17:32
Carbon disulfide	< 2.00	ug/L	7/28/2020 17:32
Carbon Tetrachloride	< 2.00	ug/L	7/28/2020 17:32
Chlorobenzene	< 2.00	ug/L	7/28/2020 17:32
Chloroethane	< 2.00	ug/L	7/28/2020 17:32
Chloroform	< 2.00	ug/L	7/28/2020 17:32
Chloromethane	< 2.00	ug/L	7/28/2020 17:32
cis-1,2-Dichloroethene	< 2.00	ug/L	7/28/2020 17:32
cis-1,3-Dichloropropene	< 2.00	ug/L	7/28/2020 17:32
Cyclohexane	< 10.0	ug/L	7/28/2020 17:32
Dibromochloromethane	< 2.00	ug/L	7/28/2020 17:32
Dichlorodifluoromethane	< 2.00	ug/L	7/28/2020 17:32
Ethylbenzene	< 2.00	ug/L	7/28/2020 17:32
Freon 113	< 2.00	ug/L	7/28/2020 17:32
Isopropylbenzene	< 2.00	ug/L	7/28/2020 17:32
m,p-Xylene	< 2.00	ug/L	7/28/2020 17:32
Methyl acetate	< 2.00	ug/L	7/28/2020 17:32
Methyl tert-butyl Ether	< 2.00	ug/L	7/28/2020 17:32
Methylcyclohexane	< 2.00	ug/L	7/28/2020 17:32
Methylene chloride	< 5.00	ug/L	7/28/2020 17:32
Naphthalene	< 5.00	ug/L	7/28/2020 17:32
n-Butylbenzene	< 2.00	ug/L	7/28/2020 17:32
n-Propylbenzene	< 2.00	ug/L	7/28/2020 17:32

This report is part of a multipage document and should only be evaluated in its entirety. The Chain of Custody provides additional sample information, including compliance with the sample condition requirements upon receipt.

Report Prepared Monday, August 3, 2020



Lab Project ID: 203467

Client: Alpha Analytical

Project Reference: L2030254, C&S Companies, Jamestown Container

Sample Identifier: 30254-01 ESI-3-071520

Lab Sample ID: 203467-01

Date Sampled: 7/15/2020

Matrix: Groundwater

Date Received: 7/28/2020

o-Xylene	< 2.00	ug/L	7/28/2020	17:32
p-Isopropyltoluene	< 2.00	ug/L	7/28/2020	17:32
sec-Butylbenzene	< 2.00	ug/L	7/28/2020	17:32
Styrene	< 5.00	ug/L	7/28/2020	17:32
tert-Butylbenzene	< 2.00	ug/L	7/28/2020	17:32
Tetrachloroethene	< 2.00	ug/L	7/28/2020	17:32
Toluene	< 2.00	ug/L	7/28/2020	17:32
trans-1,2-Dichloroethene	< 2.00	ug/L	7/28/2020	17:32
trans-1,3-Dichloropropene	< 2.00	ug/L	7/28/2020	17:32
Trichloroethene	<b>5.47</b>	ug/L	7/28/2020	17:32
Trichlorofluoromethane	< 2.00	ug/L	7/28/2020	17:32
Vinyl chloride	< 2.00	ug/L	7/28/2020	17:32

Surrogate	Percent Recovery	Limits	Outliers	Date Analyzed
1,2-Dichloroethane-d4	<b>97.9</b>	80.8 - 132		7/28/2020 17:32
4-Bromofluorobenzene	<b>63.3</b>	56.6 - 130		7/28/2020 17:32
Pentafluorobenzene	<b>105</b>	87.4 - 113		7/28/2020 17:32
Toluene-D8	<b>86.2</b>	82.2 - 115		7/28/2020 17:32

Method Reference(s): EPA 8260C  
EPA 5030C

Data File: x72087.D

This report is part of a multipage document and should only be evaluated in its entirety. The Chain of Custody provides additional sample information, including compliance with the sample condition requirements upon receipt.

Report Prepared Monday, August 3, 2020



Lab Project ID: 203467

Client: Alpha Analytical

Project Reference: L2030254, C&S Companies, Jamestown Container

Sample Identifier: 30254-02 PW-1-071520

Lab Sample ID: 203467-02

Date Sampled: 7/15/2020

Matrix: Groundwater

Date Received: 7/28/2020

**Volatile Organics**

Analyte	Result	Units	Qualifier	Date Analyzed
1,1,1-Trichloroethane	< 2.00	ug/L		7/28/2020 21:38
1,1,2,2-Tetrachloroethane	< 2.00	ug/L		7/28/2020 21:38
1,1,2-Trichloroethane	< 2.00	ug/L		7/28/2020 21:38
1,1-Dichloroethane	< 2.00	ug/L		7/28/2020 21:38
1,1-Dichloroethene	< 2.00	ug/L		7/28/2020 21:38
1,2,3-Trichlorobenzene	< 5.00	ug/L		7/28/2020 21:38
1,2,4-Trichlorobenzene	< 5.00	ug/L		7/28/2020 21:38
1,2,4-Trimethylbenzene	< 2.00	ug/L		7/28/2020 21:38
1,2-Dibromo-3-Chloropropane	< 10.0	ug/L		7/28/2020 21:38
1,2-Dibromoethane	< 2.00	ug/L		7/28/2020 21:38
1,2-Dichlorobenzene	< 2.00	ug/L		7/28/2020 21:38
1,2-Dichloroethane	< 2.00	ug/L		7/28/2020 21:38
1,2-Dichloropropane	< 2.00	ug/L		7/28/2020 21:38
1,3,5-Trimethylbenzene	< 2.00	ug/L		7/28/2020 21:38
1,3-Dichlorobenzene	< 2.00	ug/L		7/28/2020 21:38
1,4-Dichlorobenzene	< 2.00	ug/L		7/28/2020 21:38
1,4-Dioxane	< 20.0	ug/L		7/28/2020 21:38
2-Butanone	< 10.0	ug/L		7/28/2020 21:38
2-Hexanone	< 5.00	ug/L		7/28/2020 21:38
4-Methyl-2-pentanone	< 5.00	ug/L		7/28/2020 21:38
Acetone	< 10.0	ug/L		7/28/2020 21:38
Benzene	< 1.00	ug/L		7/28/2020 21:38
Bromochloromethane	< 5.00	ug/L		7/28/2020 21:38

This report is part of a multipage document and should only be evaluated in its entirety. The Chain of Custody provides additional sample information, including compliance with the sample condition requirements upon receipt.

Report Prepared Monday, August 3, 2020



Lab Project ID: 203467

Client: Alpha Analytical

Project Reference: L2030254, C&S Companies, Jamestown Container

<b>Sample Identifier:</b>	30254-02 PW-1-071520		
<b>Lab Sample ID:</b>	203467-02	<b>Date Sampled:</b>	7/15/2020
<b>Matrix:</b>	Groundwater	<b>Date Received:</b>	7/28/2020
Bromodichloromethane	< 2.00	ug/L	7/28/2020 21:38
Bromoform	< 5.00	ug/L	7/28/2020 21:38
Bromomethane	< 2.00	ug/L	7/28/2020 21:38
Carbon disulfide	< 2.00	ug/L	7/28/2020 21:38
Carbon Tetrachloride	< 2.00	ug/L	7/28/2020 21:38
Chlorobenzene	< 2.00	ug/L	7/28/2020 21:38
Chloroethane	< 2.00	ug/L	7/28/2020 21:38
Chloroform	< 2.00	ug/L	7/28/2020 21:38
Chloromethane	< 2.00	ug/L	7/28/2020 21:38
cis-1,2-Dichloroethene	<b>7.89</b>	ug/L	7/28/2020 21:38
cis-1,3-Dichloropropene	< 2.00	ug/L	7/28/2020 21:38
Cyclohexane	< 10.0	ug/L	7/28/2020 21:38
Dibromochloromethane	< 2.00	ug/L	7/28/2020 21:38
Dichlorodifluoromethane	< 2.00	ug/L	7/28/2020 21:38
Ethylbenzene	< 2.00	ug/L	7/28/2020 21:38
Freon 113	< 2.00	ug/L	7/28/2020 21:38
Isopropylbenzene	< 2.00	ug/L	7/28/2020 21:38
m,p-Xylene	< 2.00	ug/L	7/28/2020 21:38
Methyl acetate	< 2.00	ug/L	7/28/2020 21:38
Methyl tert-butyl Ether	< 2.00	ug/L	7/28/2020 21:38
Methylcyclohexane	< 2.00	ug/L	7/28/2020 21:38
Methylene chloride	< 5.00	ug/L	7/28/2020 21:38
Naphthalene	< 5.00	ug/L	7/28/2020 21:38
n-Butylbenzene	< 2.00	ug/L	7/28/2020 21:38
n-Propylbenzene	< 2.00	ug/L	7/28/2020 21:38

This report is part of a multipage document and should only be evaluated in its entirety. The Chain of Custody provides additional sample information, including compliance with the sample condition requirements upon receipt.

Report Prepared Monday, August 3, 2020



Lab Project ID: 203467

**Client:** Alpha Analytical

**Project Reference:** L2030254, C&S Companies, Jamestown Container

**Sample Identifier:** 30254-02 PW-1-071520

**Lab Sample ID:** 203467-02

**Date Sampled:** 7/15/2020

**Matrix:** Groundwater

**Date Received:** 7/28/2020

o-Xylene	< 2.00	ug/L	7/28/2020	21:38
p-Isopropyltoluene	< 2.00	ug/L	7/28/2020	21:38
sec-Butylbenzene	< 2.00	ug/L	7/28/2020	21:38
Styrene	< 5.00	ug/L	7/28/2020	21:38
tert-Butylbenzene	< 2.00	ug/L	7/28/2020	21:38
Tetrachloroethene	< 2.00	ug/L	7/28/2020	21:38
Toluene	< 2.00	ug/L	7/28/2020	21:38
trans-1,2-Dichloroethene	< 2.00	ug/L	7/28/2020	21:38
trans-1,3-Dichloropropene	< 2.00	ug/L	7/28/2020	21:38
Trichloroethene	<b>27.4</b>	ug/L	7/28/2020	21:38
Trichlorofluoromethane	< 2.00	ug/L	7/28/2020	21:38
Vinyl chloride	< 2.00	ug/L	7/28/2020	21:38

<b>Surrogate</b>	<b>Percent Recovery</b>	<b>Limits</b>	<b>Outliers</b>	<b>Date Analyzed</b>
1,2-Dichloroethane-d4	<b>127</b>	80.8 - 132		7/28/2020 21:38
4-Bromofluorobenzene	<b>63.4</b>	56.6 - 130		7/28/2020 21:38
Pentafluorobenzene	<b>98.8</b>	87.4 - 113		7/28/2020 21:38
Toluene-D8	<b>79.0</b>	82.2 - 115	*	7/28/2020 21:38

**Method Reference(s):** EPA 8260C  
EPA 5030C

**Data File:** x72098.D

This report is part of a multipage document and should only be evaluated in its entirety. The Chain of Custody provides additional sample information, including compliance with the sample condition requirements upon receipt.

Report Prepared Monday, August 3, 2020



Lab Project ID: 203467

Client: Alpha Analytical

Project Reference: L2030254, C&S Companies, Jamestown Container

Sample Identifier: 30254-03 DUP-PW-1-071520

Lab Sample ID: 203467-03

Date Sampled: 7/15/2020

Matrix: Groundwater

Date Received: 7/28/2020

**Volatile Organics**

Analyte	Result	Units	Qualifier	Date Analyzed
1,1,1-Trichloroethane	< 2.00	ug/L		7/29/2020 14:36
1,1,2,2-Tetrachloroethane	< 2.00	ug/L		7/29/2020 14:36
1,1,2-Trichloroethane	< 2.00	ug/L		7/29/2020 14:36
1,1-Dichloroethane	< 2.00	ug/L		7/29/2020 14:36
1,1-Dichloroethene	< 2.00	ug/L		7/29/2020 14:36
1,2,3-Trichlorobenzene	< 5.00	ug/L		7/29/2020 14:36
1,2,4-Trichlorobenzene	< 5.00	ug/L		7/29/2020 14:36
1,2,4-Trimethylbenzene	< 2.00	ug/L		7/29/2020 14:36
1,2-Dibromo-3-Chloropropane	< 10.0	ug/L		7/29/2020 14:36
1,2-Dibromoethane	< 2.00	ug/L		7/29/2020 14:36
1,2-Dichlorobenzene	< 2.00	ug/L		7/29/2020 14:36
1,2-Dichloroethane	< 2.00	ug/L		7/29/2020 14:36
1,2-Dichloropropane	< 2.00	ug/L		7/29/2020 14:36
1,3,5-Trimethylbenzene	< 2.00	ug/L		7/29/2020 14:36
1,3-Dichlorobenzene	< 2.00	ug/L		7/29/2020 14:36
1,4-Dichlorobenzene	< 2.00	ug/L		7/29/2020 14:36
1,4-Dioxane	< 20.0	ug/L		7/29/2020 14:36
2-Butanone	< 10.0	ug/L		7/29/2020 14:36
2-Hexanone	< 5.00	ug/L		7/29/2020 14:36
4-Methyl-2-pentanone	< 5.00	ug/L		7/29/2020 14:36
Acetone	< 10.0	ug/L		7/29/2020 14:36
Benzene	< 1.00	ug/L		7/29/2020 14:36
Bromochloromethane	< 5.00	ug/L		7/29/2020 14:36

This report is part of a multipage document and should only be evaluated in its entirety. The Chain of Custody provides additional sample information, including compliance with the sample condition requirements upon receipt.

Report Prepared Monday, August 3, 2020



Lab Project ID: 203467

Client: Alpha Analytical

Project Reference: L2030254, C&S Companies, Jamestown Container

<b>Sample Identifier:</b>	30254-03 DUP-PW-1-071520		
<b>Lab Sample ID:</b>	203467-03	<b>Date Sampled:</b>	7/15/2020
<b>Matrix:</b>	Groundwater	<b>Date Received:</b>	7/28/2020
Bromodichloromethane	< 2.00	ug/L	7/29/2020 14:36
Bromoform	< 5.00	ug/L	7/29/2020 14:36
Bromomethane	< 2.00	ug/L	7/29/2020 14:36
Carbon disulfide	< 2.00	ug/L	7/29/2020 14:36
Carbon Tetrachloride	< 2.00	ug/L	7/29/2020 14:36
Chlorobenzene	< 2.00	ug/L	7/29/2020 14:36
Chloroethane	< 2.00	ug/L	7/29/2020 14:36
Chloroform	< 2.00	ug/L	7/29/2020 14:36
Chloromethane	< 2.00	ug/L	7/29/2020 14:36
cis-1,2-Dichloroethene	<b>8.57</b>	ug/L	7/29/2020 14:36
cis-1,3-Dichloropropene	< 2.00	ug/L	7/29/2020 14:36
Cyclohexane	< 10.0	ug/L	7/29/2020 14:36
Dibromochloromethane	< 2.00	ug/L	7/29/2020 14:36
Dichlorodifluoromethane	< 2.00	ug/L	7/29/2020 14:36
Ethylbenzene	< 2.00	ug/L	7/29/2020 14:36
Freon 113	< 2.00	ug/L	7/29/2020 14:36
Isopropylbenzene	< 2.00	ug/L	7/29/2020 14:36
m,p-Xylene	< 2.00	ug/L	7/29/2020 14:36
Methyl acetate	< 2.00	ug/L	7/29/2020 14:36
Methyl tert-butyl Ether	< 2.00	ug/L	7/29/2020 14:36
Methylcyclohexane	< 2.00	ug/L	7/29/2020 14:36
Methylene chloride	< 5.00	ug/L	7/29/2020 14:36
Naphthalene	< 5.00	ug/L	7/29/2020 14:36
n-Butylbenzene	< 2.00	ug/L	7/29/2020 14:36
n-Propylbenzene	< 2.00	ug/L	7/29/2020 14:36

This report is part of a multipage document and should only be evaluated in its entirety. The Chain of Custody provides additional sample information, including compliance with the sample condition requirements upon receipt.

Report Prepared Monday, August 3, 2020



Lab Project ID: 203467

Client: Alpha Analytical

Project Reference: L2030254, C&S Companies, Jamestown Container

Sample Identifier: 30254-03 DUP-PW-1-071520

Lab Sample ID: 203467-03

Date Sampled: 7/15/2020

Matrix: Groundwater

Date Received: 7/28/2020

o-Xylene	< 2.00	ug/L	7/29/2020	14:36
p-Isopropyltoluene	< 2.00	ug/L	7/29/2020	14:36
sec-Butylbenzene	< 2.00	ug/L	7/29/2020	14:36
Styrene	< 5.00	ug/L	7/29/2020	14:36
tert-Butylbenzene	< 2.00	ug/L	7/29/2020	14:36
Tetrachloroethene	< 2.00	ug/L	7/29/2020	14:36
Toluene	< 2.00	ug/L	7/29/2020	14:36
trans-1,2-Dichloroethene	< 2.00	ug/L	7/29/2020	14:36
trans-1,3-Dichloropropene	< 2.00	ug/L	7/29/2020	14:36
Trichloroethene	<b>30.2</b>	ug/L	7/29/2020	14:36
Trichlorofluoromethane	< 2.00	ug/L	7/29/2020	14:36
Vinyl chloride	< 2.00	ug/L	7/29/2020	14:36

Surrogate	Percent Recovery	Limits	Outliers	Date Analyzed
1,2-Dichloroethane-d4	<b>115</b>	80.8 - 132		7/29/2020 14:36
4-Bromofluorobenzene	<b>62.2</b>	56.6 - 130		7/29/2020 14:36
Pentafluorobenzene	<b>103</b>	87.4 - 113		7/29/2020 14:36
Toluene-D8	<b>82.9</b>	82.2 - 115		7/29/2020 14:36

Method Reference(s): EPA 8260C  
EPA 5030C

Data File: x72116.D

This report is part of a multipage document and should only be evaluated in its entirety. The Chain of Custody provides additional sample information, including compliance with the sample condition requirements upon receipt.

Report Prepared Monday, August 3, 2020





Lab Project ID: 203467

Client: Alpha Analytical

Project Reference: L2030254, C&S Companies, Jamestown Container

Sample Identifier: 30254-04 ESI-1-071520

Lab Sample ID: 203467-04

Date Sampled: 7/15/2020

Matrix: Groundwater

Date Received: 7/28/2020

**Volatile Organics**

Analyte	Result	Units	Qualifier	Date Analyzed
1,1,1-Trichloroethane	< 2.00	ug/L		7/28/2020 17:54
1,1,2,2-Tetrachloroethane	< 2.00	ug/L		7/28/2020 17:54
1,1,2-Trichloroethane	< 2.00	ug/L		7/28/2020 17:54
1,1-Dichloroethane	< 2.00	ug/L		7/28/2020 17:54
1,1-Dichloroethene	< 2.00	ug/L		7/28/2020 17:54
1,2,3-Trichlorobenzene	< 5.00	ug/L		7/28/2020 17:54
1,2,4-Trichlorobenzene	< 5.00	ug/L		7/28/2020 17:54
1,2,4-Trimethylbenzene	< 2.00	ug/L		7/28/2020 17:54
1,2-Dibromo-3-Chloropropane	< 10.0	ug/L		7/28/2020 17:54
1,2-Dibromoethane	< 2.00	ug/L		7/28/2020 17:54
1,2-Dichlorobenzene	< 2.00	ug/L		7/28/2020 17:54
1,2-Dichloroethane	< 2.00	ug/L		7/28/2020 17:54
1,2-Dichloropropane	< 2.00	ug/L		7/28/2020 17:54
1,3,5-Trimethylbenzene	< 2.00	ug/L		7/28/2020 17:54
1,3-Dichlorobenzene	< 2.00	ug/L		7/28/2020 17:54
1,4-Dichlorobenzene	< 2.00	ug/L		7/28/2020 17:54
1,4-Dioxane	< 20.0	ug/L		7/28/2020 17:54
2-Butanone	< 10.0	ug/L		7/28/2020 17:54
2-Hexanone	< 5.00	ug/L		7/28/2020 17:54
4-Methyl-2-pentanone	< 5.00	ug/L		7/28/2020 17:54
Acetone	< 10.0	ug/L		7/28/2020 17:54
Benzene	< 1.00	ug/L		7/28/2020 17:54
Bromochloromethane	< 5.00	ug/L		7/28/2020 17:54

This report is part of a multipage document and should only be evaluated in its entirety. The Chain of Custody provides additional sample information, including compliance with the sample condition requirements upon receipt.

Report Prepared Monday, August 3, 2020



Lab Project ID: 203467

Client: Alpha Analytical

Project Reference: L2030254, C&S Companies, Jamestown Container

<b>Sample Identifier:</b>	30254-04 ESI-1-071520		
<b>Lab Sample ID:</b>	203467-04	<b>Date Sampled:</b>	7/15/2020
<b>Matrix:</b>	Groundwater	<b>Date Received:</b>	7/28/2020
Bromodichloromethane	< 2.00	ug/L	7/28/2020 17:54
Bromoform	< 5.00	ug/L	7/28/2020 17:54
Bromomethane	< 2.00	ug/L	7/28/2020 17:54
Carbon disulfide	< 2.00	ug/L	7/28/2020 17:54
Carbon Tetrachloride	< 2.00	ug/L	7/28/2020 17:54
Chlorobenzene	< 2.00	ug/L	7/28/2020 17:54
Chloroethane	< 2.00	ug/L	7/28/2020 17:54
Chloroform	< 2.00	ug/L	7/28/2020 17:54
Chloromethane	< 2.00	ug/L	7/28/2020 17:54
cis-1,2-Dichloroethene	<b>1.01</b>	ug/L	J 7/28/2020 17:54
cis-1,3-Dichloropropene	< 2.00	ug/L	7/28/2020 17:54
Cyclohexane	< 10.0	ug/L	7/28/2020 17:54
Dibromochloromethane	< 2.00	ug/L	7/28/2020 17:54
Dichlorodifluoromethane	< 2.00	ug/L	7/28/2020 17:54
Ethylbenzene	< 2.00	ug/L	7/28/2020 17:54
Freon 113	< 2.00	ug/L	7/28/2020 17:54
Isopropylbenzene	< 2.00	ug/L	7/28/2020 17:54
m,p-Xylene	< 2.00	ug/L	7/28/2020 17:54
Methyl acetate	< 2.00	ug/L	7/28/2020 17:54
Methyl tert-butyl Ether	< 2.00	ug/L	7/28/2020 17:54
Methylcyclohexane	< 2.00	ug/L	7/28/2020 17:54
Methylene chloride	< 5.00	ug/L	7/28/2020 17:54
Naphthalene	< 5.00	ug/L	7/28/2020 17:54
n-Butylbenzene	< 2.00	ug/L	7/28/2020 17:54
n-Propylbenzene	< 2.00	ug/L	7/28/2020 17:54

This report is part of a multipage document and should only be evaluated in its entirety. The Chain of Custody provides additional sample information, including compliance with the sample condition requirements upon receipt.

Report Prepared Monday, August 3, 2020



Lab Project ID: 203467

Client: Alpha Analytical

Project Reference: L2030254, C&S Companies, Jamestown Container

Sample Identifier: 30254-04 ESI-1-071520

Lab Sample ID: 203467-04

Date Sampled: 7/15/2020

Matrix: Groundwater

Date Received: 7/28/2020

o-Xylene	< 2.00	ug/L	7/28/2020	17:54
p-Isopropyltoluene	< 2.00	ug/L	7/28/2020	17:54
sec-Butylbenzene	< 2.00	ug/L	7/28/2020	17:54
Styrene	< 5.00	ug/L	7/28/2020	17:54
tert-Butylbenzene	< 2.00	ug/L	7/28/2020	17:54
Tetrachloroethene	< 2.00	ug/L	7/28/2020	17:54
Toluene	< 2.00	ug/L	7/28/2020	17:54
trans-1,2-Dichloroethene	< 2.00	ug/L	7/28/2020	17:54
trans-1,3-Dichloropropene	< 2.00	ug/L	7/28/2020	17:54
Trichloroethene	<b>6.72</b>	ug/L	7/28/2020	17:54
Trichlorofluoromethane	< 2.00	ug/L	7/28/2020	17:54
Vinyl chloride	< 2.00	ug/L	7/28/2020	17:54

Surrogate	Percent Recovery	Limits	Outliers	Date Analyzed
1,2-Dichloroethane-d4	<b>103</b>	80.8 - 132		7/28/2020 17:54
4-Bromofluorobenzene	<b>62.6</b>	56.6 - 130		7/28/2020 17:54
Pentafluorobenzene	<b>105</b>	87.4 - 113		7/28/2020 17:54
Toluene-D8	<b>88.6</b>	82.2 - 115		7/28/2020 17:54

Method Reference(s): EPA 8260C  
EPA 5030C  
Data File: x72088.D

This report is part of a multipage document and should only be evaluated in its entirety. The Chain of Custody provides additional sample information, including compliance with the sample condition requirements upon receipt.

Report Prepared Monday, August 3, 2020



Lab Project ID: 203467

Client: Alpha Analytical

Project Reference: L2030254, C&S Companies, Jamestown Container

Sample Identifier: 30254-05 ESI-13R-071520

Lab Sample ID: 203467-05

Date Sampled: 7/15/2020

Matrix: Groundwater

Date Received: 7/28/2020

**Volatile Organics**

Analyte	Result	Units	Qualifier	Date Analyzed
1,1,1-Trichloroethane	< 2.00	ug/L		7/28/2020 18:17
1,1,2,2-Tetrachloroethane	< 2.00	ug/L		7/28/2020 18:17
1,1,2-Trichloroethane	< 2.00	ug/L		7/28/2020 18:17
1,1-Dichloroethane	< 2.00	ug/L		7/28/2020 18:17
1,1-Dichloroethene	< 2.00	ug/L		7/28/2020 18:17
1,2,3-Trichlorobenzene	< 5.00	ug/L		7/28/2020 18:17
1,2,4-Trichlorobenzene	< 5.00	ug/L		7/28/2020 18:17
1,2,4-Trimethylbenzene	< 2.00	ug/L		7/28/2020 18:17
1,2-Dibromo-3-Chloropropane	< 10.0	ug/L		7/28/2020 18:17
1,2-Dibromoethane	< 2.00	ug/L		7/28/2020 18:17
1,2-Dichlorobenzene	< 2.00	ug/L		7/28/2020 18:17
1,2-Dichloroethane	< 2.00	ug/L		7/28/2020 18:17
1,2-Dichloropropane	< 2.00	ug/L		7/28/2020 18:17
1,3,5-Trimethylbenzene	< 2.00	ug/L		7/28/2020 18:17
1,3-Dichlorobenzene	< 2.00	ug/L		7/28/2020 18:17
1,4-Dichlorobenzene	< 2.00	ug/L		7/28/2020 18:17
1,4-Dioxane	< 20.0	ug/L		7/28/2020 18:17
2-Butanone	< 10.0	ug/L		7/28/2020 18:17
2-Hexanone	< 5.00	ug/L		7/28/2020 18:17
4-Methyl-2-pentanone	< 5.00	ug/L		7/28/2020 18:17
Acetone	< 10.0	ug/L		7/28/2020 18:17
Benzene	< 1.00	ug/L		7/28/2020 18:17
Bromochloromethane	< 5.00	ug/L		7/28/2020 18:17

This report is part of a multipage document and should only be evaluated in its entirety. The Chain of Custody provides additional sample information, including compliance with the sample condition requirements upon receipt.

Report Prepared Monday, August 3, 2020



Lab Project ID: 203467

**Client:** Alpha Analytical

**Project Reference:** L2030254, C&S Companies, Jamestown Container

<b>Sample Identifier:</b>	30254-05 ESI-13R-071520		
<b>Lab Sample ID:</b>	203467-05	<b>Date Sampled:</b>	7/15/2020
<b>Matrix:</b>	Groundwater	<b>Date Received:</b>	7/28/2020
Bromodichloromethane	< 2.00	ug/L	7/28/2020 18:17
Bromoform	< 5.00	ug/L	7/28/2020 18:17
Bromomethane	< 2.00	ug/L	7/28/2020 18:17
Carbon disulfide	< 2.00	ug/L	7/28/2020 18:17
Carbon Tetrachloride	< 2.00	ug/L	7/28/2020 18:17
Chlorobenzene	< 2.00	ug/L	7/28/2020 18:17
Chloroethane	< 2.00	ug/L	7/28/2020 18:17
Chloroform	< 2.00	ug/L	7/28/2020 18:17
Chloromethane	< 2.00	ug/L	7/28/2020 18:17
cis-1,2-Dichloroethene	<b>4.38</b>	ug/L	7/28/2020 18:17
cis-1,3-Dichloropropene	< 2.00	ug/L	7/28/2020 18:17
Cyclohexane	< 10.0	ug/L	7/28/2020 18:17
Dibromochloromethane	< 2.00	ug/L	7/28/2020 18:17
Dichlorodifluoromethane	< 2.00	ug/L	7/28/2020 18:17
Ethylbenzene	< 2.00	ug/L	7/28/2020 18:17
Freon 113	< 2.00	ug/L	7/28/2020 18:17
Isopropylbenzene	< 2.00	ug/L	7/28/2020 18:17
m,p-Xylene	< 2.00	ug/L	7/28/2020 18:17
Methyl acetate	< 2.00	ug/L	7/28/2020 18:17
Methyl tert-butyl Ether	< 2.00	ug/L	7/28/2020 18:17
Methylcyclohexane	< 2.00	ug/L	7/28/2020 18:17
Methylene chloride	< 5.00	ug/L	7/28/2020 18:17
Naphthalene	< 5.00	ug/L	7/28/2020 18:17
n-Butylbenzene	< 2.00	ug/L	7/28/2020 18:17
n-Propylbenzene	< 2.00	ug/L	7/28/2020 18:17

This report is part of a multipage document and should only be evaluated in its entirety. The Chain of Custody provides additional sample information, including compliance with the sample condition requirements upon receipt.

Report Prepared Monday, August 3, 2020



Lab Project ID: 203467

Client: Alpha Analytical

Project Reference: L2030254, C&S Companies, Jamestown Container

Sample Identifier: 30254-05 ESI-13R-071520

Lab Sample ID: 203467-05

Date Sampled: 7/15/2020

Matrix: Groundwater

Date Received: 7/28/2020

o-Xylene	< 2.00	ug/L	7/28/2020	18:17
p-Isopropyltoluene	< 2.00	ug/L	7/28/2020	18:17
sec-Butylbenzene	< 2.00	ug/L	7/28/2020	18:17
Styrene	< 5.00	ug/L	7/28/2020	18:17
tert-Butylbenzene	< 2.00	ug/L	7/28/2020	18:17
Tetrachloroethene	< 2.00	ug/L	7/28/2020	18:17
Toluene	< 2.00	ug/L	7/28/2020	18:17
trans-1,2-Dichloroethene	< 2.00	ug/L	7/28/2020	18:17
trans-1,3-Dichloropropene	< 2.00	ug/L	7/28/2020	18:17
Trichloroethene	<b>13.7</b>	ug/L	7/28/2020	18:17
Trichlorofluoromethane	< 2.00	ug/L	7/28/2020	18:17
Vinyl chloride	< 2.00	ug/L	7/28/2020	18:17

Surrogate	Percent Recovery	Limits	Outliers	Date Analyzed
1,2-Dichloroethane-d4	<b>104</b>	80.8 - 132		7/28/2020 18:17
4-Bromofluorobenzene	<b>63.1</b>	56.6 - 130		7/28/2020 18:17
Pentafluorobenzene	<b>103</b>	87.4 - 113		7/28/2020 18:17
Toluene-D8	<b>84.5</b>	82.2 - 115		7/28/2020 18:17

Method Reference(s): EPA 8260C  
EPA 5030C

Data File: x72089.D

This report is part of a multipage document and should only be evaluated in its entirety. The Chain of Custody provides additional sample information, including compliance with the sample condition requirements upon receipt.

Report Prepared Monday, August 3, 2020



Lab Project ID: 203467

Client: Alpha Analytical

Project Reference: L2030254, C&S Companies, Jamestown Container

Sample Identifier: 30254-06 ESI-6-071520

Lab Sample ID: 203467-06

Date Sampled: 7/15/2020

Matrix: Groundwater

Date Received: 7/28/2020

**Volatile Organics**

<u>Analyte</u>	<u>Result</u>	<u>Units</u>	<u>Qualifier</u>	<u>Date Analyzed</u>
1,1,1-Trichloroethane	< 2.00	ug/L		7/28/2020 18:39
1,1,2,2-Tetrachloroethane	< 2.00	ug/L		7/28/2020 18:39
1,1,2-Trichloroethane	< 2.00	ug/L		7/28/2020 18:39
1,1-Dichloroethane	< 2.00	ug/L		7/28/2020 18:39
1,1-Dichloroethene	< 2.00	ug/L		7/28/2020 18:39
1,2,3-Trichlorobenzene	< 5.00	ug/L		7/28/2020 18:39
1,2,4-Trichlorobenzene	< 5.00	ug/L		7/28/2020 18:39
1,2,4-Trimethylbenzene	< 2.00	ug/L		7/28/2020 18:39
1,2-Dibromo-3-Chloropropane	< 10.0	ug/L		7/28/2020 18:39
1,2-Dibromoethane	< 2.00	ug/L		7/28/2020 18:39
1,2-Dichlorobenzene	< 2.00	ug/L		7/28/2020 18:39
1,2-Dichloroethane	< 2.00	ug/L		7/28/2020 18:39
1,2-Dichloropropane	< 2.00	ug/L		7/28/2020 18:39
1,3,5-Trimethylbenzene	< 2.00	ug/L		7/28/2020 18:39
1,3-Dichlorobenzene	< 2.00	ug/L		7/28/2020 18:39
1,4-Dichlorobenzene	< 2.00	ug/L		7/28/2020 18:39
1,4-Dioxane	< 20.0	ug/L		7/28/2020 18:39
2-Butanone	< 10.0	ug/L		7/28/2020 18:39
2-Hexanone	< 5.00	ug/L		7/28/2020 18:39
4-Methyl-2-pentanone	< 5.00	ug/L		7/28/2020 18:39
Acetone	<b>15.8</b>	ug/L		7/28/2020 18:39
Benzene	< 1.00	ug/L		7/28/2020 18:39
Bromochloromethane	< 5.00	ug/L		7/28/2020 18:39

This report is part of a multipage document and should only be evaluated in its entirety. The Chain of Custody provides additional sample information, including compliance with the sample condition requirements upon receipt.

Report Prepared Monday, August 3, 2020



Lab Project ID: 203467

Client: Alpha Analytical

Project Reference: L2030254, C&S Companies, Jamestown Container

Sample Identifier: 30254-06 ESI-6-071520

Lab Sample ID: 203467-06

Date Sampled: 7/15/2020

Matrix: Groundwater

Date Received: 7/28/2020

Bromodichloromethane	< 2.00	ug/L	7/28/2020 18:39
Bromoform	13.2	ug/L	7/28/2020 18:39
Bromomethane	< 2.00	ug/L	7/28/2020 18:39
Carbon disulfide	< 2.00	ug/L	7/28/2020 18:39
Carbon Tetrachloride	< 2.00	ug/L	7/28/2020 18:39
Chlorobenzene	< 2.00	ug/L	7/28/2020 18:39
Chloroethane	< 2.00	ug/L	7/28/2020 18:39
Chloroform	< 2.00	ug/L	7/28/2020 18:39
Chloromethane	< 2.00	ug/L	7/28/2020 18:39
cis-1,2-Dichloroethene	< 2.00	ug/L	7/28/2020 18:39
cis-1,3-Dichloropropene	< 2.00	ug/L	7/28/2020 18:39
Cyclohexane	< 10.0	ug/L	7/28/2020 18:39
Dibromochloromethane	< 2.00	ug/L	7/28/2020 18:39
Dichlorodifluoromethane	< 2.00	ug/L	7/28/2020 18:39
Ethylbenzene	< 2.00	ug/L	7/28/2020 18:39
Freon 113	< 2.00	ug/L	7/28/2020 18:39
Isopropylbenzene	< 2.00	ug/L	7/28/2020 18:39
m,p-Xylene	< 2.00	ug/L	7/28/2020 18:39
Methyl acetate	< 2.00	ug/L	7/28/2020 18:39
Methyl tert-butyl Ether	< 2.00	ug/L	7/28/2020 18:39
Methylcyclohexane	< 2.00	ug/L	7/28/2020 18:39
Methylene chloride	< 5.00	ug/L	7/28/2020 18:39
Naphthalene	< 5.00	ug/L	7/28/2020 18:39
n-Butylbenzene	< 2.00	ug/L	7/28/2020 18:39
n-Propylbenzene	< 2.00	ug/L	7/28/2020 18:39

This report is part of a multipage document and should only be evaluated in its entirety. The Chain of Custody provides additional sample information, including compliance with the sample condition requirements upon receipt.

Report Prepared Monday, August 3, 2020





Lab Project ID: 203467

Client: Alpha Analytical

Project Reference: L2030254, C&S Companies, Jamestown Container

Sample Identifier: 30254-06 ESI-6-071520

Lab Sample ID: 203467-06

Date Sampled: 7/15/2020

Matrix: Groundwater

Date Received: 7/28/2020

o-Xylene	< 2.00	ug/L	7/28/2020	18:39
p-Isopropyltoluene	< 2.00	ug/L	7/28/2020	18:39
sec-Butylbenzene	< 2.00	ug/L	7/28/2020	18:39
Styrene	< 5.00	ug/L	7/28/2020	18:39
tert-Butylbenzene	< 2.00	ug/L	7/28/2020	18:39
Tetrachloroethene	< 2.00	ug/L	7/28/2020	18:39
Toluene	< 2.00	ug/L	7/28/2020	18:39
trans-1,2-Dichloroethene	< 2.00	ug/L	7/28/2020	18:39
trans-1,3-Dichloropropene	< 2.00	ug/L	7/28/2020	18:39
Trichloroethene	< 2.00	ug/L	7/28/2020	18:39
Trichlorofluoromethane	< 2.00	ug/L	7/28/2020	18:39
Vinyl chloride	< 2.00	ug/L	7/28/2020	18:39

Surrogate	Percent Recovery	Limits	Outliers	Date Analyzed
1,2-Dichloroethane-d4	105	80.8 - 132		7/28/2020 18:39
4-Bromofluorobenzene	60.4	56.6 - 130		7/28/2020 18:39
Pentafluorobenzene	106	87.4 - 113		7/28/2020 18:39
Toluene-D8	83.9	82.2 - 115		7/28/2020 18:39

Method Reference(s): EPA 8260C  
EPA 5030C  
Data File: x72090.D

This report is part of a multipage document and should only be evaluated in its entirety. The Chain of Custody provides additional sample information, including compliance with the sample condition requirements upon receipt.

Report Prepared Monday, August 3, 2020



Lab Project ID: 203467

Client: Alpha Analytical

Project Reference: L2030254, C&S Companies, Jamestown Container

Sample Identifier: 30254-07 ESI-7-071520

Lab Sample ID: 203467-07

Date Sampled: 7/15/2020

Matrix: Groundwater

Date Received: 7/28/2020

**Volatile Organics**

Analyte	Result	Units	Qualifier	Date Analyzed
1,1,1-Trichloroethane	< 2.00	ug/L		7/28/2020 19:02
1,1,2,2-Tetrachloroethane	< 2.00	ug/L		7/28/2020 19:02
1,1,2-Trichloroethane	< 2.00	ug/L		7/28/2020 19:02
1,1-Dichloroethane	< 2.00	ug/L		7/28/2020 19:02
1,1-Dichloroethene	< 2.00	ug/L		7/28/2020 19:02
1,2,3-Trichlorobenzene	< 5.00	ug/L		7/28/2020 19:02
1,2,4-Trichlorobenzene	< 5.00	ug/L		7/28/2020 19:02
1,2,4-Trimethylbenzene	< 2.00	ug/L		7/28/2020 19:02
1,2-Dibromo-3-Chloropropane	< 10.0	ug/L		7/28/2020 19:02
1,2-Dibromoethane	< 2.00	ug/L		7/28/2020 19:02
1,2-Dichlorobenzene	< 2.00	ug/L		7/28/2020 19:02
1,2-Dichloroethane	< 2.00	ug/L		7/28/2020 19:02
1,2-Dichloropropane	< 2.00	ug/L		7/28/2020 19:02
1,3,5-Trimethylbenzene	< 2.00	ug/L		7/28/2020 19:02
1,3-Dichlorobenzene	< 2.00	ug/L		7/28/2020 19:02
1,4-Dichlorobenzene	< 2.00	ug/L		7/28/2020 19:02
1,4-Dioxane	< 20.0	ug/L		7/28/2020 19:02
2-Butanone	< 10.0	ug/L		7/28/2020 19:02
2-Hexanone	< 5.00	ug/L		7/28/2020 19:02
4-Methyl-2-pentanone	< 5.00	ug/L		7/28/2020 19:02
Acetone	< 10.0	ug/L		7/28/2020 19:02
Benzene	< 1.00	ug/L		7/28/2020 19:02
Bromochloromethane	< 5.00	ug/L		7/28/2020 19:02

This report is part of a multipage document and should only be evaluated in its entirety. The Chain of Custody provides additional sample information, including compliance with the sample condition requirements upon receipt.

Report Prepared Monday, August 3, 2020



Lab Project ID: 203467

**Client:** Alpha Analytical

**Project Reference:** L2030254, C&S Companies, Jamestown Container

<b>Sample Identifier:</b>	30254-07 ESI-7-071520		
<b>Lab Sample ID:</b>	203467-07	<b>Date Sampled:</b>	7/15/2020
<b>Matrix:</b>	Groundwater	<b>Date Received:</b>	7/28/2020
Bromodichloromethane	< 2.00	ug/L	7/28/2020 19:02
Bromoform	< 5.00	ug/L	7/28/2020 19:02
Bromomethane	< 2.00	ug/L	7/28/2020 19:02
Carbon disulfide	< 2.00	ug/L	7/28/2020 19:02
Carbon Tetrachloride	< 2.00	ug/L	7/28/2020 19:02
Chlorobenzene	< 2.00	ug/L	7/28/2020 19:02
Chloroethane	< 2.00	ug/L	7/28/2020 19:02
Chloroform	< 2.00	ug/L	7/28/2020 19:02
Chloromethane	< 2.00	ug/L	7/28/2020 19:02
cis-1,2-Dichloroethene	<b>5.94</b>	ug/L	7/28/2020 19:02
cis-1,3-Dichloropropene	< 2.00	ug/L	7/28/2020 19:02
Cyclohexane	< 10.0	ug/L	7/28/2020 19:02
Dibromochloromethane	< 2.00	ug/L	7/28/2020 19:02
Dichlorodifluoromethane	< 2.00	ug/L	7/28/2020 19:02
Ethylbenzene	< 2.00	ug/L	7/28/2020 19:02
Freon 113	< 2.00	ug/L	7/28/2020 19:02
Isopropylbenzene	< 2.00	ug/L	7/28/2020 19:02
m,p-Xylene	< 2.00	ug/L	7/28/2020 19:02
Methyl acetate	< 2.00	ug/L	7/28/2020 19:02
Methyl tert-butyl Ether	< 2.00	ug/L	7/28/2020 19:02
Methylcyclohexane	< 2.00	ug/L	7/28/2020 19:02
Methylene chloride	< 5.00	ug/L	7/28/2020 19:02
Naphthalene	< 5.00	ug/L	7/28/2020 19:02
n-Butylbenzene	< 2.00	ug/L	7/28/2020 19:02
n-Propylbenzene	< 2.00	ug/L	7/28/2020 19:02

This report is part of a multipage document and should only be evaluated in its entirety. The Chain of Custody provides additional sample information, including compliance with the sample condition requirements upon receipt.

Report Prepared Monday, August 3, 2020



Lab Project ID: 203467

**Client:** Alpha Analytical

**Project Reference:** L2030254, C&S Companies, Jamestown Container

**Sample Identifier:** 30254-07 ESI-7-071520

**Lab Sample ID:** 203467-07

**Date Sampled:** 7/15/2020

**Matrix:** Groundwater

**Date Received:** 7/28/2020

o-Xylene	< 2.00	ug/L	7/28/2020	19:02
p-Isopropyltoluene	< 2.00	ug/L	7/28/2020	19:02
sec-Butylbenzene	< 2.00	ug/L	7/28/2020	19:02
Styrene	< 5.00	ug/L	7/28/2020	19:02
tert-Butylbenzene	< 2.00	ug/L	7/28/2020	19:02
Tetrachloroethene	< 2.00	ug/L	7/28/2020	19:02
Toluene	< 2.00	ug/L	7/28/2020	19:02
trans-1,2-Dichloroethene	< 2.00	ug/L	7/28/2020	19:02
trans-1,3-Dichloropropene	< 2.00	ug/L	7/28/2020	19:02
Trichloroethene	<b>39.5</b>	ug/L	7/28/2020	19:02
Trichlorofluoromethane	< 2.00	ug/L	7/28/2020	19:02
Vinyl chloride	< 2.00	ug/L	7/28/2020	19:02

<b>Surrogate</b>	<b>Percent Recovery</b>	<b>Limits</b>	<b>Outliers</b>	<b>Date Analyzed</b>
1,2-Dichloroethane-d4	<b>113</b>	80.8 - 132		7/28/2020 19:02
4-Bromofluorobenzene	<b>60.6</b>	56.6 - 130		7/28/2020 19:02
Pentafluorobenzene	<b>102</b>	87.4 - 113		7/28/2020 19:02
Toluene-D8	<b>82.3</b>	82.2 - 115		7/28/2020 19:02

**Method Reference(s):** EPA 8260C  
EPA 5030C

**Data File:** x72091.D

This report is part of a multipage document and should only be evaluated in its entirety. The Chain of Custody provides additional sample information, including compliance with the sample condition requirements upon receipt.

Report Prepared Monday, August 3, 2020



Lab Project ID: 203467

Client: Alpha Analytical

Project Reference: L2030254, C&S Companies, Jamestown Container

Sample Identifier: 30254-08 PW-3R-071520

Lab Sample ID: 203467-08

Date Sampled: 7/15/2020

Matrix: Groundwater

Date Received: 7/28/2020

**Volatile Organics**

Analyte	Result	Units	Qualifier	Date Analyzed
1,1,1-Trichloroethane	< 20.0	ug/L		7/28/2020 19:24
1,1,2,2-Tetrachloroethane	< 20.0	ug/L		7/28/2020 19:24
1,1,2-Trichloroethane	< 20.0	ug/L		7/28/2020 19:24
1,1-Dichloroethane	< 20.0	ug/L		7/28/2020 19:24
1,1-Dichloroethene	< 20.0	ug/L		7/28/2020 19:24
1,2,3-Trichlorobenzene	< 50.0	ug/L		7/28/2020 19:24
1,2,4-Trichlorobenzene	< 50.0	ug/L		7/28/2020 19:24
1,2,4-Trimethylbenzene	< 20.0	ug/L		7/28/2020 19:24
1,2-Dibromo-3-Chloropropane	< 100	ug/L		7/28/2020 19:24
1,2-Dibromoethane	< 20.0	ug/L		7/28/2020 19:24
1,2-Dichlorobenzene	< 20.0	ug/L		7/28/2020 19:24
1,2-Dichloroethane	< 20.0	ug/L		7/28/2020 19:24
1,2-Dichloropropane	< 20.0	ug/L		7/28/2020 19:24
1,3,5-Trimethylbenzene	< 20.0	ug/L		7/28/2020 19:24
1,3-Dichlorobenzene	< 20.0	ug/L		7/28/2020 19:24
1,4-Dichlorobenzene	< 20.0	ug/L		7/28/2020 19:24
1,4-Dioxane	< 200	ug/L		7/28/2020 19:24
2-Butanone	< 100	ug/L		7/28/2020 19:24
2-Hexanone	< 50.0	ug/L		7/28/2020 19:24
4-Methyl-2-pentanone	< 50.0	ug/L		7/28/2020 19:24
Acetone	< 100	ug/L		7/28/2020 19:24
Benzene	< 10.0	ug/L		7/28/2020 19:24
Bromochloromethane	< 50.0	ug/L		7/28/2020 19:24

This report is part of a multipage document and should only be evaluated in its entirety. The Chain of Custody provides additional sample information, including compliance with the sample condition requirements upon receipt.

Report Prepared Monday, August 3, 2020



Lab Project ID: 203467

**Client:** Alpha Analytical

**Project Reference:** L2030254, C&S Companies, Jamestown Container

<b>Sample Identifier:</b>	30254-08 PW-3R-071520		
<b>Lab Sample ID:</b>	203467-08	<b>Date Sampled:</b>	7/15/2020
<b>Matrix:</b>	Groundwater	<b>Date Received:</b>	7/28/2020
Bromodichloromethane	< 20.0	ug/L	7/28/2020 19:24
Bromoform	< 50.0	ug/L	7/28/2020 19:24
Bromomethane	< 20.0	ug/L	7/28/2020 19:24
Carbon disulfide	< 20.0	ug/L	7/28/2020 19:24
Carbon Tetrachloride	< 20.0	ug/L	7/28/2020 19:24
Chlorobenzene	< 20.0	ug/L	7/28/2020 19:24
Chloroethane	< 20.0	ug/L	7/28/2020 19:24
Chloroform	< 20.0	ug/L	7/28/2020 19:24
Chloromethane	< 20.0	ug/L	7/28/2020 19:24
cis-1,2-Dichloroethene	<b>809</b>	ug/L	7/28/2020 19:24
cis-1,3-Dichloropropene	< 20.0	ug/L	7/28/2020 19:24
Cyclohexane	< 100	ug/L	7/28/2020 19:24
Dibromochloromethane	< 20.0	ug/L	7/28/2020 19:24
Dichlorodifluoromethane	< 20.0	ug/L	7/28/2020 19:24
Ethylbenzene	< 20.0	ug/L	7/28/2020 19:24
Freon 113	< 20.0	ug/L	7/28/2020 19:24
Isopropylbenzene	< 20.0	ug/L	7/28/2020 19:24
m,p-Xylene	< 20.0	ug/L	7/28/2020 19:24
Methyl acetate	< 20.0	ug/L	7/28/2020 19:24
Methyl tert-butyl Ether	< 20.0	ug/L	7/28/2020 19:24
Methylcyclohexane	< 20.0	ug/L	7/28/2020 19:24
Methylene chloride	< 50.0	ug/L	7/28/2020 19:24
Naphthalene	< 50.0	ug/L	7/28/2020 19:24
n-Butylbenzene	< 20.0	ug/L	7/28/2020 19:24
n-Propylbenzene	< 20.0	ug/L	7/28/2020 19:24

This report is part of a multipage document and should only be evaluated in its entirety. The Chain of Custody provides additional sample information, including compliance with the sample condition requirements upon receipt.

Report Prepared Monday, August 3, 2020



Lab Project ID: 203467

Client: Alpha Analytical

Project Reference: L2030254, C&S Companies, Jamestown Container

Sample Identifier: 30254-08 PW-3R-071520

Lab Sample ID: 203467-08

Date Sampled: 7/15/2020

Matrix: Groundwater

Date Received: 7/28/2020

o-Xylene	< 20.0	ug/L		7/28/2020 19:24
p-Isopropyltoluene	< 20.0	ug/L		7/28/2020 19:24
sec-Butylbenzene	< 20.0	ug/L		7/28/2020 19:24
Styrene	< 50.0	ug/L		7/28/2020 19:24
tert-Butylbenzene	< 20.0	ug/L		7/28/2020 19:24
Tetrachloroethene	< 20.0	ug/L		7/28/2020 19:24
Toluene	< 20.0	ug/L		7/28/2020 19:24
trans-1,2-Dichloroethene	11.4	ug/L	J	7/28/2020 19:24
trans-1,3-Dichloropropene	< 20.0	ug/L		7/28/2020 19:24
Trichloroethene	75.2	ug/L		7/28/2020 19:24
Trichlorofluoromethane	< 20.0	ug/L		7/28/2020 19:24
Vinyl chloride	1440	ug/L		7/28/2020 19:24

Surrogate	Percent Recovery	Limits	Outliers	Date Analyzed
1,2-Dichloroethane-d4	110	80.8 - 132		7/28/2020 19:24
4-Bromofluorobenzene	59.6	56.6 - 130		7/28/2020 19:24
Pentafluorobenzene	103	87.4 - 113		7/28/2020 19:24
Toluene-D8	79.6	82.2 - 115	*	7/28/2020 19:24

Method Reference(s): EPA 8260C  
EPA 5030C  
Data File: x72092.D

This report is part of a multipage document and should only be evaluated in its entirety. The Chain of Custody provides additional sample information, including compliance with the sample condition requirements upon receipt.

Report Prepared Monday, August 3, 2020



Lab Project ID: 203467

Client: Alpha Analytical

Project Reference: L2030254, C&S Companies, Jamestown Container

Sample Identifier: 30254-09 DUP-PW-3R-071520

Lab Sample ID: 203467-09

Date Sampled: 7/15/2020

Matrix: Groundwater

Date Received: 7/28/2020

**Volatile Organics**

Analyte	Result	Units	Qualifier	Date Analyzed
1,1,1-Trichloroethane	< 20.0	ug/L		7/29/2020 14:13
1,1,2,2-Tetrachloroethane	< 20.0	ug/L		7/29/2020 14:13
1,1,2-Trichloroethane	< 20.0	ug/L		7/29/2020 14:13
1,1-Dichloroethane	< 20.0	ug/L		7/29/2020 14:13
1,1-Dichloroethene	< 20.0	ug/L		7/29/2020 14:13
1,2,3-Trichlorobenzene	< 50.0	ug/L		7/29/2020 14:13
1,2,4-Trichlorobenzene	< 50.0	ug/L		7/29/2020 14:13
1,2,4-Trimethylbenzene	< 20.0	ug/L		7/29/2020 14:13
1,2-Dibromo-3-Chloropropane	< 100	ug/L		7/29/2020 14:13
1,2-Dibromoethane	< 20.0	ug/L		7/29/2020 14:13
1,2-Dichlorobenzene	< 20.0	ug/L		7/29/2020 14:13
1,2-Dichloroethane	< 20.0	ug/L		7/29/2020 14:13
1,2-Dichloropropane	< 20.0	ug/L		7/29/2020 14:13
1,3,5-Trimethylbenzene	< 20.0	ug/L		7/29/2020 14:13
1,3-Dichlorobenzene	< 20.0	ug/L		7/29/2020 14:13
1,4-Dichlorobenzene	< 20.0	ug/L		7/29/2020 14:13
1,4-Dioxane	< 200	ug/L		7/29/2020 14:13
2-Butanone	< 100	ug/L		7/29/2020 14:13
2-Hexanone	< 50.0	ug/L		7/29/2020 14:13
4-Methyl-2-pentanone	< 50.0	ug/L		7/29/2020 14:13
Acetone	< 100	ug/L		7/29/2020 14:13
Benzene	< 10.0	ug/L		7/29/2020 14:13
Bromochloromethane	< 50.0	ug/L		7/29/2020 14:13

This report is part of a multipage document and should only be evaluated in its entirety. The Chain of Custody provides additional sample information, including compliance with the sample condition requirements upon receipt.

Report Prepared Monday, August 3, 2020





Lab Project ID: 203467

Client: Alpha Analytical

Project Reference: L2030254, C&S Companies, Jamestown Container

<b>Sample Identifier:</b>	30254-09 DUP-PW-3R-071520		
<b>Lab Sample ID:</b>	203467-09	<b>Date Sampled:</b>	7/15/2020
<b>Matrix:</b>	Groundwater	<b>Date Received:</b>	7/28/2020
Bromodichloromethane	< 20.0	ug/L	7/29/2020 14:13
Bromoform	< 50.0	ug/L	7/29/2020 14:13
Bromomethane	< 20.0	ug/L	7/29/2020 14:13
Carbon disulfide	< 20.0	ug/L	7/29/2020 14:13
Carbon Tetrachloride	< 20.0	ug/L	7/29/2020 14:13
Chlorobenzene	< 20.0	ug/L	7/29/2020 14:13
Chloroethane	< 20.0	ug/L	7/29/2020 14:13
Chloroform	< 20.0	ug/L	7/29/2020 14:13
Chloromethane	< 20.0	ug/L	7/29/2020 14:13
cis-1,2-Dichloroethene	<b>1000</b>	ug/L	7/29/2020 14:13
cis-1,3-Dichloropropene	< 20.0	ug/L	7/29/2020 14:13
Cyclohexane	< 100	ug/L	7/29/2020 14:13
Dibromochloromethane	< 20.0	ug/L	7/29/2020 14:13
Dichlorodifluoromethane	< 20.0	ug/L	7/29/2020 14:13
Ethylbenzene	< 20.0	ug/L	7/29/2020 14:13
Freon 113	< 20.0	ug/L	7/29/2020 14:13
Isopropylbenzene	< 20.0	ug/L	7/29/2020 14:13
m,p-Xylene	< 20.0	ug/L	7/29/2020 14:13
Methyl acetate	< 20.0	ug/L	7/29/2020 14:13
Methyl tert-butyl Ether	< 20.0	ug/L	7/29/2020 14:13
Methylcyclohexane	< 20.0	ug/L	7/29/2020 14:13
Methylene chloride	< 50.0	ug/L	7/29/2020 14:13
Naphthalene	< 50.0	ug/L	7/29/2020 14:13
n-Butylbenzene	< 20.0	ug/L	7/29/2020 14:13
n-Propylbenzene	< 20.0	ug/L	7/29/2020 14:13

This report is part of a multipage document and should only be evaluated in its entirety. The Chain of Custody provides additional sample information, including compliance with the sample condition requirements upon receipt.

Report Prepared Monday, August 3, 2020



Lab Project ID: 203467

**Client:** Alpha Analytical

**Project Reference:** L2030254, C&S Companies, Jamestown Container

**Sample Identifier:** 30254-09 DUP-PW-3R-071520

**Lab Sample ID:** 203467-09

**Date Sampled:** 7/15/2020

**Matrix:** Groundwater

**Date Received:** 7/28/2020

o-Xylene	< 20.0	ug/L		7/29/2020 14:13
p-Isopropyltoluene	< 20.0	ug/L		7/29/2020 14:13
sec-Butylbenzene	< 20.0	ug/L		7/29/2020 14:13
Styrene	< 50.0	ug/L		7/29/2020 14:13
tert-Butylbenzene	< 20.0	ug/L		7/29/2020 14:13
Tetrachloroethene	< 20.0	ug/L		7/29/2020 14:13
Toluene	< 20.0	ug/L		7/29/2020 14:13
trans-1,2-Dichloroethene	<b>13.8</b>	ug/L	J	7/29/2020 14:13
trans-1,3-Dichloropropene	< 20.0	ug/L		7/29/2020 14:13
Trichloroethene	<b>92.9</b>	ug/L		7/29/2020 14:13
Trichlorofluoromethane	< 20.0	ug/L		7/29/2020 14:13
Vinyl chloride	<b>1720</b>	ug/L		7/29/2020 14:13

<b>Surrogate</b>	<b>Percent Recovery</b>	<b>Limits</b>	<b>Outliers</b>	<b>Date Analyzed</b>
1,2-Dichloroethane-d4	<b>104</b>	80.8 - 132		7/29/2020 14:13
4-Bromofluorobenzene	<b>61.9</b>	56.6 - 130		7/29/2020 14:13
Pentafluorobenzene	<b>103</b>	87.4 - 113		7/29/2020 14:13
Toluene-D8	<b>84.3</b>	82.2 - 115		7/29/2020 14:13

**Method Reference(s):** EPA 8260C  
EPA 5030C

**Data File:** x72115.D

This report is part of a multipage document and should only be evaluated in its entirety. The Chain of Custody provides additional sample information, including compliance with the sample condition requirements upon receipt.

Report Prepared Monday, August 3, 2020



Lab Project ID: 203467

Client: Alpha Analytical

Project Reference: L2030254, C&S Companies, Jamestown Container

Sample Identifier: 30254-10 ESI-2-071520

Lab Sample ID: 203467-10

Date Sampled: 7/15/2020

Matrix: Groundwater

Date Received: 7/28/2020

**Volatile Organics**

Analyte	Result	Units	Qualifier	Date Analyzed
1,1,1-Trichloroethane	< 40.0	ug/L		7/29/2020 13:50
1,1,2,2-Tetrachloroethane	< 40.0	ug/L		7/29/2020 13:50
1,1,2-Trichloroethane	< 40.0	ug/L		7/29/2020 13:50
1,1-Dichloroethane	< 40.0	ug/L		7/29/2020 13:50
1,1-Dichloroethene	< 40.0	ug/L		7/29/2020 13:50
1,2,3-Trichlorobenzene	< 100	ug/L		7/29/2020 13:50
1,2,4-Trichlorobenzene	< 100	ug/L		7/29/2020 13:50
1,2,4-Trimethylbenzene	< 40.0	ug/L		7/29/2020 13:50
1,2-Dibromo-3-Chloropropane	< 200	ug/L		7/29/2020 13:50
1,2-Dibromoethane	< 40.0	ug/L		7/29/2020 13:50
1,2-Dichlorobenzene	< 40.0	ug/L		7/29/2020 13:50
1,2-Dichloroethane	< 40.0	ug/L		7/29/2020 13:50
1,2-Dichloropropane	< 40.0	ug/L		7/29/2020 13:50
1,3,5-Trimethylbenzene	< 40.0	ug/L		7/29/2020 13:50
1,3-Dichlorobenzene	< 40.0	ug/L		7/29/2020 13:50
1,4-Dichlorobenzene	< 40.0	ug/L		7/29/2020 13:50
1,4-Dioxane	< 400	ug/L		7/29/2020 13:50
2-Butanone	< 200	ug/L		7/29/2020 13:50
2-Hexanone	< 100	ug/L		7/29/2020 13:50
4-Methyl-2-pentanone	< 100	ug/L		7/29/2020 13:50
Acetone	< 200	ug/L		7/29/2020 13:50
Benzene	< 20.0	ug/L		7/29/2020 13:50
Bromochloromethane	< 100	ug/L		7/29/2020 13:50

This report is part of a multipage document and should only be evaluated in its entirety. The Chain of Custody provides additional sample information, including compliance with the sample condition requirements upon receipt.

Report Prepared Monday, August 3, 2020



Lab Project ID: 203467

Client: Alpha Analytical

Project Reference: L2030254, C&S Companies, Jamestown Container

<b>Sample Identifier:</b>	30254-10 ESI-2-071520		
<b>Lab Sample ID:</b>	203467-10	<b>Date Sampled:</b>	7/15/2020
<b>Matrix:</b>	Groundwater	<b>Date Received:</b>	7/28/2020
Bromodichloromethane	< 40.0	ug/L	7/29/2020 13:50
Bromoform	< 100	ug/L	7/29/2020 13:50
Bromomethane	< 40.0	ug/L	7/29/2020 13:50
Carbon disulfide	< 40.0	ug/L	7/29/2020 13:50
Carbon Tetrachloride	< 40.0	ug/L	7/29/2020 13:50
Chlorobenzene	< 40.0	ug/L	7/29/2020 13:50
Chloroethane	< 40.0	ug/L	7/29/2020 13:50
Chloroform	< 40.0	ug/L	7/29/2020 13:50
Chloromethane	< 40.0	ug/L	7/29/2020 13:50
cis-1,2-Dichloroethene	<b>1910</b>	ug/L	7/29/2020 13:50
cis-1,3-Dichloropropene	< 40.0	ug/L	7/29/2020 13:50
Cyclohexane	< 200	ug/L	7/29/2020 13:50
Dibromochloromethane	< 40.0	ug/L	7/29/2020 13:50
Dichlorodifluoromethane	< 40.0	ug/L	7/29/2020 13:50
Ethylbenzene	< 40.0	ug/L	7/29/2020 13:50
Freon 113	< 40.0	ug/L	7/29/2020 13:50
Isopropylbenzene	< 40.0	ug/L	7/29/2020 13:50
m,p-Xylene	< 40.0	ug/L	7/29/2020 13:50
Methyl acetate	< 40.0	ug/L	7/29/2020 13:50
Methyl tert-butyl Ether	< 40.0	ug/L	7/29/2020 13:50
Methylcyclohexane	< 40.0	ug/L	7/29/2020 13:50
Methylene chloride	< 100	ug/L	7/29/2020 13:50
Naphthalene	< 100	ug/L	7/29/2020 13:50
n-Butylbenzene	< 40.0	ug/L	7/29/2020 13:50
n-Propylbenzene	< 40.0	ug/L	7/29/2020 13:50

This report is part of a multipage document and should only be evaluated in its entirety. The Chain of Custody provides additional sample information, including compliance with the sample condition requirements upon receipt.

Report Prepared Monday, August 3, 2020



Lab Project ID: 203467

Client: Alpha Analytical

Project Reference: L2030254, C&S Companies, Jamestown Container

Sample Identifier: 30254-10 ESI-2-071520

Lab Sample ID: 203467-10

Date Sampled: 7/15/2020

Matrix: Groundwater

Date Received: 7/28/2020

o-Xylene	< 40.0	ug/L		7/29/2020 13:50
p-Isopropyltoluene	< 40.0	ug/L		7/29/2020 13:50
sec-Butylbenzene	< 40.0	ug/L		7/29/2020 13:50
Styrene	< 100	ug/L		7/29/2020 13:50
tert-Butylbenzene	< 40.0	ug/L		7/29/2020 13:50
Tetrachloroethene	< 40.0	ug/L		7/29/2020 13:50
Toluene	< 40.0	ug/L		7/29/2020 13:50
trans-1,2-Dichloroethene	< 40.0	ug/L		7/29/2020 13:50
trans-1,3-Dichloropropene	< 40.0	ug/L		7/29/2020 13:50
Trichloroethene	<b>708</b>	ug/L		7/29/2020 13:50
Trichlorofluoromethane	< 40.0	ug/L		7/29/2020 13:50
Vinyl chloride	<b>20.3</b>	ug/L	J	7/29/2020 13:50

Surrogate	Percent Recovery	Limits	Outliers	Date Analyzed
1,2-Dichloroethane-d4	<b>99.6</b>	80.8 - 132		7/29/2020 13:50
4-Bromofluorobenzene	<b>65.4</b>	56.6 - 130		7/29/2020 13:50
Pentafluorobenzene	<b>107</b>	87.4 - 113		7/29/2020 13:50
Toluene-D8	<b>87.1</b>	82.2 - 115		7/29/2020 13:50

Method Reference(s): EPA 8260C  
EPA 5030C

Data File: x72114.D

This report is part of a multipage document and should only be evaluated in its entirety. The Chain of Custody provides additional sample information, including compliance with the sample condition requirements upon receipt.

Report Prepared Monday, August 3, 2020



Lab Project ID: 203467

Client: Alpha Analytical

Project Reference: L2030254, C&S Companies, Jamestown Container

Sample Identifier: 30254-11 ESI-10-071520

Lab Sample ID: 203467-11

Date Sampled: 7/15/2020

Matrix: Groundwater

Date Received: 7/28/2020

**Volatile Organics**

Analyte	Result	Units	Qualifier	Date Analyzed
1,1,1-Trichloroethane	< 2.00	ug/L		7/28/2020 20:31
1,1,2,2-Tetrachloroethane	< 2.00	ug/L		7/28/2020 20:31
1,1,2-Trichloroethane	< 2.00	ug/L		7/28/2020 20:31
1,1-Dichloroethane	< 2.00	ug/L		7/28/2020 20:31
1,1-Dichloroethene	< 2.00	ug/L		7/28/2020 20:31
1,2,3-Trichlorobenzene	< 5.00	ug/L		7/28/2020 20:31
1,2,4-Trichlorobenzene	< 5.00	ug/L		7/28/2020 20:31
1,2,4-Trimethylbenzene	< 2.00	ug/L		7/28/2020 20:31
1,2-Dibromo-3-Chloropropane	< 10.0	ug/L		7/28/2020 20:31
1,2-Dibromoethane	< 2.00	ug/L		7/28/2020 20:31
1,2-Dichlorobenzene	< 2.00	ug/L		7/28/2020 20:31
1,2-Dichloroethane	< 2.00	ug/L		7/28/2020 20:31
1,2-Dichloropropane	< 2.00	ug/L		7/28/2020 20:31
1,3,5-Trimethylbenzene	< 2.00	ug/L		7/28/2020 20:31
1,3-Dichlorobenzene	< 2.00	ug/L		7/28/2020 20:31
1,4-Dichlorobenzene	< 2.00	ug/L		7/28/2020 20:31
1,4-Dioxane	< 20.0	ug/L		7/28/2020 20:31
2-Butanone	< 10.0	ug/L		7/28/2020 20:31
2-Hexanone	< 5.00	ug/L		7/28/2020 20:31
4-Methyl-2-pentanone	< 5.00	ug/L		7/28/2020 20:31
Acetone	<b>15.0</b>	ug/L		7/28/2020 20:31
Benzene	< 1.00	ug/L		7/28/2020 20:31
Bromochloromethane	< 5.00	ug/L		7/28/2020 20:31

This report is part of a multipage document and should only be evaluated in its entirety. The Chain of Custody provides additional sample information, including compliance with the sample condition requirements upon receipt.

Report Prepared Monday, August 3, 2020



Lab Project ID: 203467

Client: Alpha Analytical

Project Reference: L2030254, C&S Companies, Jamestown Container

Sample Identifier: 30254-11 ESI-10-071520

Lab Sample ID: 203467-11

Date Sampled: 7/15/2020

Matrix: Groundwater

Date Received: 7/28/2020

Bromodichloromethane	< 2.00	ug/L	7/28/2020 20:31
Bromoform	< 5.00	ug/L	7/28/2020 20:31
Bromomethane	< 2.00	ug/L	7/28/2020 20:31
Carbon disulfide	< 2.00	ug/L	7/28/2020 20:31
Carbon Tetrachloride	< 2.00	ug/L	7/28/2020 20:31
Chlorobenzene	< 2.00	ug/L	7/28/2020 20:31
Chloroethane	< 2.00	ug/L	7/28/2020 20:31
Chloroform	< 2.00	ug/L	7/28/2020 20:31
Chloromethane	< 2.00	ug/L	7/28/2020 20:31
cis-1,2-Dichloroethene	< 2.00	ug/L	7/28/2020 20:31
cis-1,3-Dichloropropene	< 2.00	ug/L	7/28/2020 20:31
Cyclohexane	< 10.0	ug/L	7/28/2020 20:31
Dibromochloromethane	< 2.00	ug/L	7/28/2020 20:31
Dichlorodifluoromethane	< 2.00	ug/L	7/28/2020 20:31
Ethylbenzene	< 2.00	ug/L	7/28/2020 20:31
Freon 113	< 2.00	ug/L	7/28/2020 20:31
Isopropylbenzene	< 2.00	ug/L	7/28/2020 20:31
m,p-Xylene	< 2.00	ug/L	7/28/2020 20:31
Methyl acetate	< 2.00	ug/L	7/28/2020 20:31
Methyl tert-butyl Ether	< 2.00	ug/L	7/28/2020 20:31
Methylcyclohexane	< 2.00	ug/L	7/28/2020 20:31
Methylene chloride	< 5.00	ug/L	7/28/2020 20:31
Naphthalene	< 5.00	ug/L	7/28/2020 20:31
n-Butylbenzene	< 2.00	ug/L	7/28/2020 20:31
n-Propylbenzene	< 2.00	ug/L	7/28/2020 20:31

This report is part of a multipage document and should only be evaluated in its entirety. The Chain of Custody provides additional sample information, including compliance with the sample condition requirements upon receipt.

Report Prepared Monday, August 3, 2020



Lab Project ID: 203467

**Client:** Alpha Analytical

**Project Reference:** L2030254, C&S Companies, Jamestown Container

**Sample Identifier:** 30254-11 ESI-10-071520

**Lab Sample ID:** 203467-11

**Date Sampled:** 7/15/2020

**Matrix:** Groundwater

**Date Received:** 7/28/2020

o-Xylene	< 2.00	ug/L	7/28/2020	20:31
p-Isopropyltoluene	< 2.00	ug/L	7/28/2020	20:31
sec-Butylbenzene	< 2.00	ug/L	7/28/2020	20:31
Styrene	< 5.00	ug/L	7/28/2020	20:31
tert-Butylbenzene	< 2.00	ug/L	7/28/2020	20:31
Tetrachloroethene	< 2.00	ug/L	7/28/2020	20:31
Toluene	< 2.00	ug/L	7/28/2020	20:31
trans-1,2-Dichloroethene	< 2.00	ug/L	7/28/2020	20:31
trans-1,3-Dichloropropene	< 2.00	ug/L	7/28/2020	20:31
Trichloroethene	< 2.00	ug/L	7/28/2020	20:31
Trichlorofluoromethane	< 2.00	ug/L	7/28/2020	20:31
Vinyl chloride	< 2.00	ug/L	7/28/2020	20:31

<b>Surrogate</b>	<b>Percent Recovery</b>	<b>Limits</b>	<b>Outliers</b>	<b>Date Analyzed</b>
1,2-Dichloroethane-d4	<b>115</b>	80.8 - 132		7/28/2020 20:31
4-Bromofluorobenzene	<b>62.6</b>	56.6 - 130		7/28/2020 20:31
Pentafluorobenzene	<b>100</b>	87.4 - 113		7/28/2020 20:31
Toluene-D8	<b>82.0</b>	82.2 - 115	*	7/28/2020 20:31

**Method Reference(s):** EPA 8260C

EPA 5030C

**Data File:** x72095.D

This report is part of a multipage document and should only be evaluated in its entirety. The Chain of Custody provides additional sample information, including compliance with the sample condition requirements upon receipt.

Report Prepared Monday, August 3, 2020





Lab Project ID: 203467

Client: Alpha Analytical

Project Reference: L2030254, C&S Companies, Jamestown Container

Sample Identifier: 30254-12 ESI-11-071520

Lab Sample ID: 203467-12

Date Sampled: 7/15/2020

Matrix: Groundwater

Date Received: 7/28/2020

**Volatile Organics**

Analyte	Result	Units	Qualifier	Date Analyzed
1,1,1-Trichloroethane	< 2.00	ug/L		7/28/2020 20:53
1,1,2,2-Tetrachloroethane	< 2.00	ug/L		7/28/2020 20:53
1,1,2-Trichloroethane	< 2.00	ug/L		7/28/2020 20:53
1,1-Dichloroethane	< 2.00	ug/L		7/28/2020 20:53
1,1-Dichloroethene	< 2.00	ug/L		7/28/2020 20:53
1,2,3-Trichlorobenzene	< 5.00	ug/L		7/28/2020 20:53
1,2,4-Trichlorobenzene	< 5.00	ug/L		7/28/2020 20:53
1,2,4-Trimethylbenzene	< 2.00	ug/L		7/28/2020 20:53
1,2-Dibromo-3-Chloropropane	< 10.0	ug/L		7/28/2020 20:53
1,2-Dibromoethane	< 2.00	ug/L		7/28/2020 20:53
1,2-Dichlorobenzene	< 2.00	ug/L		7/28/2020 20:53
1,2-Dichloroethane	< 2.00	ug/L		7/28/2020 20:53
1,2-Dichloropropane	< 2.00	ug/L		7/28/2020 20:53
1,3,5-Trimethylbenzene	< 2.00	ug/L		7/28/2020 20:53
1,3-Dichlorobenzene	< 2.00	ug/L		7/28/2020 20:53
1,4-Dichlorobenzene	< 2.00	ug/L		7/28/2020 20:53
1,4-Dioxane	< 20.0	ug/L		7/28/2020 20:53
2-Butanone	< 10.0	ug/L		7/28/2020 20:53
2-Hexanone	< 5.00	ug/L		7/28/2020 20:53
4-Methyl-2-pentanone	< 5.00	ug/L		7/28/2020 20:53
Acetone	<b>5.64</b>	ug/L	J	7/28/2020 20:53
Benzene	< 1.00	ug/L		7/28/2020 20:53
Bromochloromethane	< 5.00	ug/L		7/28/2020 20:53

This report is part of a multipage document and should only be evaluated in its entirety. The Chain of Custody provides additional sample information, including compliance with the sample condition requirements upon receipt.

Report Prepared Monday, August 3, 2020



Lab Project ID: 203467

Client: Alpha Analytical

Project Reference: L2030254, C&S Companies, Jamestown Container

Sample Identifier: 30254-12 ESI-11-071520

Lab Sample ID: 203467-12

Date Sampled: 7/15/2020

Matrix: Groundwater

Date Received: 7/28/2020

Bromodichloromethane	< 2.00	ug/L	7/28/2020 20:53
Bromoform	8.77	ug/L	7/28/2020 20:53
Bromomethane	< 2.00	ug/L	7/28/2020 20:53
Carbon disulfide	< 2.00	ug/L	7/28/2020 20:53
Carbon Tetrachloride	< 2.00	ug/L	7/28/2020 20:53
Chlorobenzene	< 2.00	ug/L	7/28/2020 20:53
Chloroethane	< 2.00	ug/L	7/28/2020 20:53
Chloroform	< 2.00	ug/L	7/28/2020 20:53
Chloromethane	< 2.00	ug/L	7/28/2020 20:53
cis-1,2-Dichloroethene	< 2.00	ug/L	7/28/2020 20:53
cis-1,3-Dichloropropene	< 2.00	ug/L	7/28/2020 20:53
Cyclohexane	< 10.0	ug/L	7/28/2020 20:53
Dibromochloromethane	< 2.00	ug/L	7/28/2020 20:53
Dichlorodifluoromethane	< 2.00	ug/L	7/28/2020 20:53
Ethylbenzene	< 2.00	ug/L	7/28/2020 20:53
Freon 113	< 2.00	ug/L	7/28/2020 20:53
Isopropylbenzene	< 2.00	ug/L	7/28/2020 20:53
m,p-Xylene	< 2.00	ug/L	7/28/2020 20:53
Methyl acetate	< 2.00	ug/L	7/28/2020 20:53
Methyl tert-butyl Ether	< 2.00	ug/L	7/28/2020 20:53
Methylcyclohexane	< 2.00	ug/L	7/28/2020 20:53
Methylene chloride	< 5.00	ug/L	7/28/2020 20:53
Naphthalene	< 5.00	ug/L	7/28/2020 20:53
n-Butylbenzene	< 2.00	ug/L	7/28/2020 20:53
n-Propylbenzene	< 2.00	ug/L	7/28/2020 20:53

This report is part of a multipage document and should only be evaluated in its entirety. The Chain of Custody provides additional sample information, including compliance with the sample condition requirements upon receipt.

Report Prepared Monday, August 3, 2020



Lab Project ID: 203467

Client: Alpha Analytical

Project Reference: L2030254, C&S Companies, Jamestown Container

Sample Identifier: 30254-12 ESI-11-071520

Lab Sample ID: 203467-12

Date Sampled: 7/15/2020

Matrix: Groundwater

Date Received: 7/28/2020

o-Xylene	< 2.00	ug/L	7/28/2020	20:53
p-Isopropyltoluene	< 2.00	ug/L	7/28/2020	20:53
sec-Butylbenzene	< 2.00	ug/L	7/28/2020	20:53
Styrene	< 5.00	ug/L	7/28/2020	20:53
tert-Butylbenzene	< 2.00	ug/L	7/28/2020	20:53
Tetrachloroethene	< 2.00	ug/L	7/28/2020	20:53
Toluene	< 2.00	ug/L	7/28/2020	20:53
trans-1,2-Dichloroethene	< 2.00	ug/L	7/28/2020	20:53
trans-1,3-Dichloropropene	< 2.00	ug/L	7/28/2020	20:53
Trichloroethene	< 2.00	ug/L	7/28/2020	20:53
Trichlorofluoromethane	< 2.00	ug/L	7/28/2020	20:53
Vinyl chloride	< 2.00	ug/L	7/28/2020	20:53

Surrogate	Percent Recovery	Limits	Outliers	Date Analyzed
1,2-Dichloroethane-d4	121	80.8 - 132		7/28/2020 20:53
4-Bromofluorobenzene	66.8	56.6 - 130		7/28/2020 20:53
Pentafluorobenzene	104	87.4 - 113		7/28/2020 20:53
Toluene-D8	82.2	82.2 - 115		7/28/2020 20:53

Method Reference(s): EPA 8260C  
EPA 5030C

Data File: x72096.D

This report is part of a multipage document and should only be evaluated in its entirety. The Chain of Custody provides additional sample information, including compliance with the sample condition requirements upon receipt.

Report Prepared Monday, August 3, 2020



Lab Project ID: 203467

Client: Alpha Analytical

Project Reference: L2030254, C&S Companies, Jamestown Container

Sample Identifier: 30254-13 ESI-12-071520

Lab Sample ID: 203467-13

Date Sampled: 7/15/2020

Matrix: Groundwater

Date Received: 7/28/2020

**Volatile Organics**

Analyte	Result	Units	Qualifier	Date Analyzed
1,1,1-Trichloroethane	< 2.00	ug/L		7/28/2020 21:15
1,1,2,2-Tetrachloroethane	< 2.00	ug/L		7/28/2020 21:15
1,1,2-Trichloroethane	< 2.00	ug/L		7/28/2020 21:15
1,1-Dichloroethane	< 2.00	ug/L		7/28/2020 21:15
1,1-Dichloroethene	< 2.00	ug/L		7/28/2020 21:15
1,2,3-Trichlorobenzene	< 5.00	ug/L		7/28/2020 21:15
1,2,4-Trichlorobenzene	< 5.00	ug/L		7/28/2020 21:15
1,2,4-Trimethylbenzene	< 2.00	ug/L		7/28/2020 21:15
1,2-Dibromo-3-Chloropropane	< 10.0	ug/L		7/28/2020 21:15
1,2-Dibromoethane	< 2.00	ug/L		7/28/2020 21:15
1,2-Dichlorobenzene	< 2.00	ug/L		7/28/2020 21:15
1,2-Dichloroethane	< 2.00	ug/L		7/28/2020 21:15
1,2-Dichloropropane	< 2.00	ug/L		7/28/2020 21:15
1,3,5-Trimethylbenzene	< 2.00	ug/L		7/28/2020 21:15
1,3-Dichlorobenzene	< 2.00	ug/L		7/28/2020 21:15
1,4-Dichlorobenzene	< 2.00	ug/L		7/28/2020 21:15
1,4-Dioxane	< 20.0	ug/L		7/28/2020 21:15
2-Butanone	< 10.0	ug/L		7/28/2020 21:15
2-Hexanone	< 5.00	ug/L		7/28/2020 21:15
4-Methyl-2-pentanone	< 5.00	ug/L		7/28/2020 21:15
Acetone	< 10.0	ug/L		7/28/2020 21:15
Benzene	<b>1.19</b>	ug/L		7/28/2020 21:15
Bromochloromethane	< 5.00	ug/L		7/28/2020 21:15

This report is part of a multipage document and should only be evaluated in its entirety. The Chain of Custody provides additional sample information, including compliance with the sample condition requirements upon receipt.

Report Prepared Monday, August 3, 2020



Lab Project ID: 203467

Client: Alpha Analytical

Project Reference: L2030254, C&S Companies, Jamestown Container

Sample Identifier: 30254-13 ESI-12-071520

Lab Sample ID: 203467-13

Date Sampled: 7/15/2020

Matrix: Groundwater

Date Received: 7/28/2020

Bromodichloromethane	< 2.00	ug/L	7/28/2020 21:15
Bromoform	6.67	ug/L	7/28/2020 21:15
Bromomethane	< 2.00	ug/L	7/28/2020 21:15
Carbon disulfide	< 2.00	ug/L	7/28/2020 21:15
Carbon Tetrachloride	< 2.00	ug/L	7/28/2020 21:15
Chlorobenzene	< 2.00	ug/L	7/28/2020 21:15
Chloroethane	< 2.00	ug/L	7/28/2020 21:15
Chloroform	< 2.00	ug/L	7/28/2020 21:15
Chloromethane	< 2.00	ug/L	7/28/2020 21:15
cis-1,2-Dichloroethene	< 2.00	ug/L	7/28/2020 21:15
cis-1,3-Dichloropropene	< 2.00	ug/L	7/28/2020 21:15
Cyclohexane	< 10.0	ug/L	7/28/2020 21:15
Dibromochloromethane	< 2.00	ug/L	7/28/2020 21:15
Dichlorodifluoromethane	< 2.00	ug/L	7/28/2020 21:15
Ethylbenzene	< 2.00	ug/L	7/28/2020 21:15
Freon 113	< 2.00	ug/L	7/28/2020 21:15
Isopropylbenzene	< 2.00	ug/L	7/28/2020 21:15
m,p-Xylene	< 2.00	ug/L	7/28/2020 21:15
Methyl acetate	< 2.00	ug/L	7/28/2020 21:15
Methyl tert-butyl Ether	< 2.00	ug/L	7/28/2020 21:15
Methylcyclohexane	< 2.00	ug/L	7/28/2020 21:15
Methylene chloride	< 5.00	ug/L	7/28/2020 21:15
Naphthalene	< 5.00	ug/L	7/28/2020 21:15
n-Butylbenzene	< 2.00	ug/L	7/28/2020 21:15
n-Propylbenzene	< 2.00	ug/L	7/28/2020 21:15

This report is part of a multipage document and should only be evaluated in its entirety. The Chain of Custody provides additional sample information, including compliance with the sample condition requirements upon receipt.

Report Prepared Monday, August 3, 2020



Lab Project ID: 203467

**Client:** Alpha Analytical

**Project Reference:** L2030254, C&S Companies, Jamestown Container

**Sample Identifier:** 30254-13 ESI-12-071520

**Lab Sample ID:** 203467-13

**Date Sampled:** 7/15/2020

**Matrix:** Groundwater

**Date Received:** 7/28/2020

o-Xylene	< 2.00	ug/L	7/28/2020	21:15
p-Isopropyltoluene	< 2.00	ug/L	7/28/2020	21:15
sec-Butylbenzene	< 2.00	ug/L	7/28/2020	21:15
Styrene	< 5.00	ug/L	7/28/2020	21:15
tert-Butylbenzene	< 2.00	ug/L	7/28/2020	21:15
Tetrachloroethene	< 2.00	ug/L	7/28/2020	21:15
Toluene	< 2.00	ug/L	7/28/2020	21:15
trans-1,2-Dichloroethene	< 2.00	ug/L	7/28/2020	21:15
trans-1,3-Dichloropropene	< 2.00	ug/L	7/28/2020	21:15
Trichloroethene	< 2.00	ug/L	7/28/2020	21:15
Trichlorofluoromethane	< 2.00	ug/L	7/28/2020	21:15
Vinyl chloride	< 2.00	ug/L	7/28/2020	21:15

<b>Surrogate</b>	<b>Percent Recovery</b>	<b>Limits</b>	<b>Outliers</b>	<b>Date Analyzed</b>
1,2-Dichloroethane-d4	<b>121</b>	80.8 - 132		7/28/2020 21:15
4-Bromofluorobenzene	<b>64.0</b>	56.6 - 130		7/28/2020 21:15
Pentafluorobenzene	<b>104</b>	87.4 - 113		7/28/2020 21:15
Toluene-D8	<b>79.9</b>	82.2 - 115	*	7/28/2020 21:15

**Method Reference(s):** EPA 8260C  
EPA 5030C

**Data File:** x72097.D

This report is part of a multipage document and should only be evaluated in its entirety. The Chain of Custody provides additional sample information, including compliance with the sample condition requirements upon receipt.

Report Prepared Monday, August 3, 2020



Lab Project ID: 203467

Client: Alpha Analytical

Project Reference: L2030254, C&S Companies, Jamestown Container

Sample Identifier: 30254-14 Equipment Blank

Lab Sample ID: 203467-14

Date Sampled: 7/15/2020

Matrix: Groundwater

Date Received: 7/28/2020

**Volatile Organics**

Analyte	Result	Units	Qualifier	Date Analyzed
1,1,1-Trichloroethane	< 2.00	ug/L		7/28/2020 16:48
1,1,2,2-Tetrachloroethane	< 2.00	ug/L		7/28/2020 16:48
1,1,2-Trichloroethane	< 2.00	ug/L		7/28/2020 16:48
1,1-Dichloroethane	< 2.00	ug/L		7/28/2020 16:48
1,1-Dichloroethene	< 2.00	ug/L		7/28/2020 16:48
1,2,3-Trichlorobenzene	< 5.00	ug/L		7/28/2020 16:48
1,2,4-Trichlorobenzene	< 5.00	ug/L		7/28/2020 16:48
1,2,4-Trimethylbenzene	< 2.00	ug/L		7/28/2020 16:48
1,2-Dibromo-3-Chloropropane	< 10.0	ug/L		7/28/2020 16:48
1,2-Dibromoethane	< 2.00	ug/L		7/28/2020 16:48
1,2-Dichlorobenzene	< 2.00	ug/L		7/28/2020 16:48
1,2-Dichloroethane	< 2.00	ug/L		7/28/2020 16:48
1,2-Dichloropropane	< 2.00	ug/L		7/28/2020 16:48
1,3,5-Trimethylbenzene	< 2.00	ug/L		7/28/2020 16:48
1,3-Dichlorobenzene	< 2.00	ug/L		7/28/2020 16:48
1,4-Dichlorobenzene	< 2.00	ug/L		7/28/2020 16:48
1,4-Dioxane	< 20.0	ug/L		7/28/2020 16:48
2-Butanone	< 10.0	ug/L		7/28/2020 16:48
2-Hexanone	< 5.00	ug/L		7/28/2020 16:48
4-Methyl-2-pentanone	< 5.00	ug/L		7/28/2020 16:48
Acetone	< 10.0	ug/L		7/28/2020 16:48
Benzene	< 1.00	ug/L		7/28/2020 16:48
Bromochloromethane	< 5.00	ug/L		7/28/2020 16:48

This report is part of a multipage document and should only be evaluated in its entirety. The Chain of Custody provides additional sample information, including compliance with the sample condition requirements upon receipt.

Report Prepared Monday, August 3, 2020



Lab Project ID: 203467

Client: Alpha Analytical

Project Reference: L2030254, C&S Companies, Jamestown Container

<b>Sample Identifier:</b>	30254-14 Equipment Blank		
<b>Lab Sample ID:</b>	203467-14	<b>Date Sampled:</b>	7/15/2020
<b>Matrix:</b>	Groundwater	<b>Date Received:</b>	7/28/2020
Bromodichloromethane	< 2.00	ug/L	7/28/2020 16:48
Bromoform	< 5.00	ug/L	7/28/2020 16:48
Bromomethane	< 2.00	ug/L	7/28/2020 16:48
Carbon disulfide	< 2.00	ug/L	7/28/2020 16:48
Carbon Tetrachloride	< 2.00	ug/L	7/28/2020 16:48
Chlorobenzene	< 2.00	ug/L	7/28/2020 16:48
Chloroethane	< 2.00	ug/L	7/28/2020 16:48
Chloroform	< 2.00	ug/L	7/28/2020 16:48
Chloromethane	< 2.00	ug/L	7/28/2020 16:48
cis-1,2-Dichloroethene	< 2.00	ug/L	7/28/2020 16:48
cis-1,3-Dichloropropene	< 2.00	ug/L	7/28/2020 16:48
Cyclohexane	< 10.0	ug/L	7/28/2020 16:48
Dibromochloromethane	< 2.00	ug/L	7/28/2020 16:48
Dichlorodifluoromethane	< 2.00	ug/L	7/28/2020 16:48
Ethylbenzene	< 2.00	ug/L	7/28/2020 16:48
Freon 113	< 2.00	ug/L	7/28/2020 16:48
Isopropylbenzene	< 2.00	ug/L	7/28/2020 16:48
m,p-Xylene	< 2.00	ug/L	7/28/2020 16:48
Methyl acetate	< 2.00	ug/L	7/28/2020 16:48
Methyl tert-butyl Ether	< 2.00	ug/L	7/28/2020 16:48
Methylcyclohexane	< 2.00	ug/L	7/28/2020 16:48
Methylene chloride	< 5.00	ug/L	7/28/2020 16:48
Naphthalene	< 5.00	ug/L	7/28/2020 16:48
n-Butylbenzene	< 2.00	ug/L	7/28/2020 16:48
n-Propylbenzene	< 2.00	ug/L	7/28/2020 16:48

This report is part of a multipage document and should only be evaluated in its entirety. The Chain of Custody provides additional sample information, including compliance with the sample condition requirements upon receipt.

Report Prepared Monday, August 3, 2020





Lab Project ID: 203467

**Client:** Alpha Analytical

**Project Reference:** L2030254, C&S Companies, Jamestown Container

**Sample Identifier:** 30254-14 Equipment Blank

**Lab Sample ID:** 203467-14

**Date Sampled:** 7/15/2020

**Matrix:** Groundwater

**Date Received:** 7/28/2020

o-Xylene	< 2.00	ug/L	7/28/2020	16:48
p-Isopropyltoluene	< 2.00	ug/L	7/28/2020	16:48
sec-Butylbenzene	< 2.00	ug/L	7/28/2020	16:48
Styrene	< 5.00	ug/L	7/28/2020	16:48
tert-Butylbenzene	< 2.00	ug/L	7/28/2020	16:48
Tetrachloroethene	< 2.00	ug/L	7/28/2020	16:48
Toluene	< 2.00	ug/L	7/28/2020	16:48
trans-1,2-Dichloroethene	< 2.00	ug/L	7/28/2020	16:48
trans-1,3-Dichloropropene	< 2.00	ug/L	7/28/2020	16:48
Trichloroethene	< 2.00	ug/L	7/28/2020	16:48
Trichlorofluoromethane	< 2.00	ug/L	7/28/2020	16:48
Vinyl chloride	< 2.00	ug/L	7/28/2020	16:48

<b>Surrogate</b>	<b>Percent Recovery</b>	<b>Limits</b>	<b>Outliers</b>	<b>Date Analyzed</b>
1,2-Dichloroethane-d4	<b>89.3</b>	80.8 - 132		7/28/2020 16:48
4-Bromofluorobenzene	<b>68.4</b>	56.6 - 130		7/28/2020 16:48
Pentafluorobenzene	<b>107</b>	87.4 - 113		7/28/2020 16:48
Toluene-D8	<b>89.7</b>	82.2 - 115		7/28/2020 16:48

**Method Reference(s):** EPA 8260C  
EPA 5030C

**Data File:** x72085.D

This report is part of a multipage document and should only be evaluated in its entirety. The Chain of Custody provides additional sample information, including compliance with the sample condition requirements upon receipt.

Report Prepared Monday, August 3, 2020



Lab Project ID: 203467

Client: Alpha Analytical

Project Reference: L2030254, C&S Companies, Jamestown Container

Sample Identifier: 30254-15 Field Blank

Lab Sample ID: 203467-15

Date Sampled: 7/15/2020

Matrix: Groundwater

Date Received: 7/28/2020

**Volatile Organics**

Analyte	Result	Units	Qualifier	Date Analyzed
1,1,1-Trichloroethane	< 2.00	ug/L		7/28/2020 17:10
1,1,2,2-Tetrachloroethane	< 2.00	ug/L		7/28/2020 17:10
1,1,2-Trichloroethane	< 2.00	ug/L		7/28/2020 17:10
1,1-Dichloroethane	< 2.00	ug/L		7/28/2020 17:10
1,1-Dichloroethene	< 2.00	ug/L		7/28/2020 17:10
1,2,3-Trichlorobenzene	< 5.00	ug/L		7/28/2020 17:10
1,2,4-Trichlorobenzene	< 5.00	ug/L		7/28/2020 17:10
1,2,4-Trimethylbenzene	< 2.00	ug/L		7/28/2020 17:10
1,2-Dibromo-3-Chloropropane	< 10.0	ug/L		7/28/2020 17:10
1,2-Dibromoethane	< 2.00	ug/L		7/28/2020 17:10
1,2-Dichlorobenzene	< 2.00	ug/L		7/28/2020 17:10
1,2-Dichloroethane	< 2.00	ug/L		7/28/2020 17:10
1,2-Dichloropropane	< 2.00	ug/L		7/28/2020 17:10
1,3,5-Trimethylbenzene	< 2.00	ug/L		7/28/2020 17:10
1,3-Dichlorobenzene	< 2.00	ug/L		7/28/2020 17:10
1,4-Dichlorobenzene	< 2.00	ug/L		7/28/2020 17:10
1,4-Dioxane	< 20.0	ug/L		7/28/2020 17:10
2-Butanone	< 10.0	ug/L		7/28/2020 17:10
2-Hexanone	< 5.00	ug/L		7/28/2020 17:10
4-Methyl-2-pentanone	< 5.00	ug/L		7/28/2020 17:10
Acetone	< 10.0	ug/L		7/28/2020 17:10
Benzene	< 1.00	ug/L		7/28/2020 17:10
Bromochloromethane	< 5.00	ug/L		7/28/2020 17:10

This report is part of a multipage document and should only be evaluated in its entirety. The Chain of Custody provides additional sample information, including compliance with the sample condition requirements upon receipt.

Report Prepared Monday, August 3, 2020



Lab Project ID: 203467

Client: Alpha Analytical

Project Reference: L2030254, C&S Companies, Jamestown Container

<b>Sample Identifier:</b>	30254-15 Field Blank		
<b>Lab Sample ID:</b>	203467-15	<b>Date Sampled:</b>	7/15/2020
<b>Matrix:</b>	Groundwater	<b>Date Received:</b>	7/28/2020
Bromodichloromethane	< 2.00	ug/L	7/28/2020 17:10
Bromoform	< 5.00	ug/L	7/28/2020 17:10
Bromomethane	< 2.00	ug/L	7/28/2020 17:10
Carbon disulfide	< 2.00	ug/L	7/28/2020 17:10
Carbon Tetrachloride	< 2.00	ug/L	7/28/2020 17:10
Chlorobenzene	< 2.00	ug/L	7/28/2020 17:10
Chloroethane	< 2.00	ug/L	7/28/2020 17:10
Chloroform	< 2.00	ug/L	7/28/2020 17:10
Chloromethane	< 2.00	ug/L	7/28/2020 17:10
cis-1,2-Dichloroethene	< 2.00	ug/L	7/28/2020 17:10
cis-1,3-Dichloropropene	< 2.00	ug/L	7/28/2020 17:10
Cyclohexane	< 10.0	ug/L	7/28/2020 17:10
Dibromochloromethane	< 2.00	ug/L	7/28/2020 17:10
Dichlorodifluoromethane	< 2.00	ug/L	7/28/2020 17:10
Ethylbenzene	< 2.00	ug/L	7/28/2020 17:10
Freon 113	< 2.00	ug/L	7/28/2020 17:10
Isopropylbenzene	< 2.00	ug/L	7/28/2020 17:10
m,p-Xylene	< 2.00	ug/L	7/28/2020 17:10
Methyl acetate	< 2.00	ug/L	7/28/2020 17:10
Methyl tert-butyl Ether	< 2.00	ug/L	7/28/2020 17:10
Methylcyclohexane	< 2.00	ug/L	7/28/2020 17:10
Methylene chloride	< 5.00	ug/L	7/28/2020 17:10
Naphthalene	< 5.00	ug/L	7/28/2020 17:10
n-Butylbenzene	< 2.00	ug/L	7/28/2020 17:10
n-Propylbenzene	< 2.00	ug/L	7/28/2020 17:10

This report is part of a multipage document and should only be evaluated in its entirety. The Chain of Custody provides additional sample information, including compliance with the sample condition requirements upon receipt.

Report Prepared Monday, August 3, 2020



Lab Project ID: 203467

**Client:** Alpha Analytical

**Project Reference:** L2030254, C&S Companies, Jamestown Container

**Sample Identifier:** 30254-15 Field Blank

**Lab Sample ID:** 203467-15

**Date Sampled:** 7/15/2020

**Matrix:** Groundwater

**Date Received:** 7/28/2020

o-Xylene	< 2.00	ug/L	7/28/2020	17:10
p-Isopropyltoluene	< 2.00	ug/L	7/28/2020	17:10
sec-Butylbenzene	< 2.00	ug/L	7/28/2020	17:10
Styrene	< 5.00	ug/L	7/28/2020	17:10
tert-Butylbenzene	< 2.00	ug/L	7/28/2020	17:10
Tetrachloroethene	< 2.00	ug/L	7/28/2020	17:10
Toluene	< 2.00	ug/L	7/28/2020	17:10
trans-1,2-Dichloroethene	< 2.00	ug/L	7/28/2020	17:10
trans-1,3-Dichloropropene	< 2.00	ug/L	7/28/2020	17:10
Trichloroethene	< 2.00	ug/L	7/28/2020	17:10
Trichlorofluoromethane	< 2.00	ug/L	7/28/2020	17:10
Vinyl chloride	< 2.00	ug/L	7/28/2020	17:10

<b>Surrogate</b>	<b>Percent Recovery</b>	<b>Limits</b>	<b>Outliers</b>	<b>Date Analyzed</b>
1,2-Dichloroethane-d4	<b>92.7</b>	80.8 - 132		7/28/2020 17:10
4-Bromofluorobenzene	<b>66.1</b>	56.6 - 130		7/28/2020 17:10
Pentafluorobenzene	<b>110</b>	87.4 - 113		7/28/2020 17:10
Toluene-D8	<b>89.2</b>	82.2 - 115		7/28/2020 17:10

**Method Reference(s):** EPA 8260C  
EPA 5030C

**Data File:** x72086.D

This report is part of a multipage document and should only be evaluated in its entirety. The Chain of Custody provides additional sample information, including compliance with the sample condition requirements upon receipt.

Report Prepared Monday, August 3, 2020



## Analytical Report Appendix

The reported results relate only to the samples as they have been received by the laboratory.

Each page of this document is part of a multipage report. This document may not be reproduced except in its entirety, without the prior consent of Paradigm Environmental Services, Inc.

All soil/sludge samples have been reported on a dry weight basis, unless qualified "reported as received". Other solids are reported as received.

Low level Volatiles blank reports for soil/solid matrix are based on a nominal 5 gram weight. Sample results and reporting limits are based on actual weight, which may be more or less than 5 grams.

The Chain of Custody provides additional information, including compliance with sample condition requirements upon receipt. Sample condition requirements are defined under the 2003 NELAC Standard, sections 5.5.8.3.1 and 5.5.8.3.2.

NYSDOH ELAP does not certify for all parameters. Paradigm Environmental Services or the indicated subcontracted laboratory does hold certification for all analytes where certification is offered by ELAP unless otherwise specified. Aliquots separated for certain tests, such as TCLP, are indicated on the Chain of Custody and final reports with an "A" suffix.

Data qualifiers are used, when necessary, to provide additional information about the data. This information may be communicated as a flag or as text at the bottom of the report. Please refer to the following list of analyte-specific, frequently used data flags and their meaning:

*"<" = Analyzed for but not detected at or above the quantitation limit.*

*"E" = Result has been estimated, calibration limit exceeded.*

*"Z" = See case narrative.*

*"D" = Sample, Laboratory Control Sample, or Matrix Spike Duplicate results above Relative Percent Difference limit.*

*"M" = Matrix spike recoveries outside QC limits. Matrix bias indicated.*

*"B" = Method blank contained trace levels of analyte. Refer to included method blank report.*

*"J" = Result estimated between the quantitation limit and half the quantitation limit.*

*"L" = Laboratory Control Sample recovery outside accepted QC limits.*

*"P" = Concentration differs by more than 40% between the primary and secondary analytical columns.*

*"NC" = Not calculable. Applicable to RPD if sample or duplicate result is non-detect or estimated (see primary report for data flags). Applicable to MS if sample is greater or equal to ten times the spike added. Applicable to sample surrogates or MS if sample dilution is 10x or higher.*

*"\*" = Indicates any recoveries outside associated acceptance windows. Surrogate outliers in samples are presumed matrix effects. LCS demonstrates method compliance unless otherwise noted.*

*"(1)" = Indicates data from primary column used for QC calculation.*

*"A" = denotes a parameter for which ELAP does not offer approval as part of their laboratory certification program.*

*"F" = denotes a parameter for which Paradigm does not carry certification, the results for which should therefore only be used where ELAP certification is not required, such as personal exposure assessment.*

This report is part of a multipage document and should only be evaluated in its entirety. The Chain of Custody provides additional sample information, including compliance with the sample condition requirements upon receipt.

# GENERAL TERMS AND CONDITIONS

## LABORATORY SERVICES

These Terms and Conditions embody the whole agreement of the parties in the absence of a signed and executed contract between the Laboratory (LAB) and Client. They shall supersede all previous communications, representations, or agreements, either verbal or written, between the parties. The LAB specifically rejects all additional, inconsistent, or conflicting terms, whether printed or otherwise set forth in any purchase order or other communication from the Client to the LAB. The invalidity or unenforceability in whole or in part of any provision, term or condition hereof shall not affect in any way the validity or enforceability of the remainder of the Terms and Conditions. No waiver by LAB of any provision, term, or condition hereof or of any breach by or obligation of the Client hereunder shall constitute a waiver of such provision, term, or condition on any other occasion or a waiver of any other breach by or obligation of the Client. This agreement shall be administered and interpreted under the laws of the state which services are procured.

### **Warranty.**

Recognizing that the nature of many samples is unknown and that some may contain potentially hazardous components, LAB warrants only that it will perform testing services, obtain findings, and prepare reports in accordance with generally accepted analytical laboratory principles and practices at the time of performance of services. LAB makes no other warranty, express or implied.

### **Scope and Compensation.**

LAB agrees to perform the services described in the chain of custody to which these terms and conditions are attached. Unless the parties agree in writing to the contrary, the duties of LAB shall not be construed to exceed the services specifically described. LAB will use LAB default method for all tests unless specified otherwise on the Work Order.

Payment terms are net 30 days from the date of invoice. All overdue payments are subject to an interest charge of one and one-half percent (1-1/2%) per month or a portion thereof. Client shall also be responsible for costs of collection, including payment of reasonable attorney fees if such expense is incurred. The prices, unless stated, do not include any sale, use or other taxes. Such taxes will be added to invoice prices when required.

### **Prices.**

Compensation for services performed will be based on the current Lab Analytical Fee Schedule or on quotations agreed to in writing by the parties. Turnaround time based charges are determined from the time of resolution of all work order questions. Testimony, court appearances or data compilation for legal action will be charged separately. Evaluation and reporting of initial screening runs may incur additional fees.

### **Limitations of Liability.**

In the event of any error, omission, or other professional negligence, the sole and exclusive responsibility of LAB shall be to re-perform the deficient work at its own expense and LAB shall have no other liability whatsoever. All claims shall be deemed waived unless made in writing and received by LAB within ninety (90) days following completion of services.

LAB shall have no liability, obligation, or responsibility of any kind for losses, costs, expenses, or other damages (including but not limited to any special, direct, incidental or consequential damages) with respect to LAB's services or results.

All results provided by LAB are strictly for the use of its clients and LAB is in no way responsible for the use of such results by clients or third parties. All reports should be considered in their entirety, and LAB is not responsible for the separation, detachment, or other use of any portion of these reports. Client may not assign the lab report without the written consent of the LAB.

Client covenants and agrees, at its/his/her sole expense, to indemnify, protect, defend, and save harmless the LAB from and against any and all damages, losses, liabilities, obligations, penalties, claims, litigation, demands, defenses, judgments, suits, actions, proceedings, costs, disbursements and/or expenses (including, without limitation attorneys' and experts' fees and disbursements) of any kind whatsoever which may at any time be imposed upon, incurred by or asserted or awarded against client relating to, resulting from or arising out of (a) the breach of this agreement by this client, (b) the negligence of the client in handling, delivering or disclosing any hazardous substance, (c) the violation of the Client of any applicable law, (d) non-compliance by the Client with any environmental permit or (e) a material misrepresentation in disclosing the materials to be tested.

### **Hazard Disclosure.**

Client represents and warrants that any sample delivered to LAB will be preceded or accompanied by complete written disclosure of the presence of any hazardous substances known or suspected by Client. Client further warrants that any sample containing any hazardous substance that is to be delivered to LAB will be packaged, labeled, transported, and delivered properly and in accordance with applicable laws.

### **Sample Handling.**

Prior to LAB's acceptance of any sample (or after any revocation of acceptance), the entire risk of loss or of damage to such sample remains with Client. Samples are accepted when receipt is acknowledged on chain of custody documentation. In no event will LAB have any responsibility for the action or inaction of any carrier shipping or delivering any sample to or from LAB premises.

Client authorizes LAB to proceed with the analysis of samples as received by the laboratory, recognizing that any samples not in compliance with all current DOH-ELAP-NELAP requirements for containers, preservation or holding time will be noted as such on the final report.

Disposal of hazardous waste samples is the responsibility of the Client. If the Client does not wish such samples returned, LAB may add storage and disposal fees to the final invoice. Maximum storage time for samples is 30 days after completion of analysis unless modified by applicable state or federal laws. Client will be required to give the LAB written instructions concerning disposal of these samples.

LAB reserves the absolute right, exercisable at any time, to refuse to receive delivery of, refuse to accept, or revoke acceptance of any sample, which, in the sole judgment of LAB (a) is of unsuitable volume, (b) may be or become unsuitable for or may pose a risk in handling, transport, or processing for any health, safety, environmental or other reason whether or not due to the presence in the sample of any hazardous substance, and whether or not such presence has been disclosed to LAB by Client or (c) if the condition or sample date make the sample unsuitable for analysis.

### **Legal Responsibility.**

LAB is solely responsible for performance of this contract, and no affiliated company, director, officer, employee, or agent shall have any legal responsibility hereunder, whether in contract or tort including negligence.

### **Assignment.**

LAB may assign its performance obligations under this contract to other parties, as it deems necessary. LAB shall disclose to Client any assignee (subcontractor) by ELAP ID # on the submitted final report.

### **Force Majeure.**

LAB shall have no responsibility or liability to the Client for any failure or delay in performance by LAB, which results in whole or in part from any cause or circumstance beyond the reasonable control of LAB. Such causes and circumstances shall include, but not limited to, acts of God, acts or orders of any government authority, strikes or other labor disputes, natural disasters, accidents, wars, civil disturbances, difficulties or delays in transportation, mail or delivery services, inability to obtain sufficient services or supplies from LAB's usual suppliers, or any other cause beyond LAB's reasonable control.

### **Law.**

This contract shall be continued under the laws of the State of New York without regard to its conflicts of laws provision.

This report is part of a multipage document and should only be evaluated in its entirety. The Chain of Custody provides additional sample information, including compliance with the sample condition requirements upon receipt.



Westborough, MA 01581  
 8 Walkup Dr.  
 TEL: 508-898-9220  
 FAX: 508-898-9193

Mansfield, MA 02048  
 320 Forbes Blvd  
 TEL: 508-822-9300  
 FAX: 508-822-3288

**NEW YORK CHAIN OF CUSTODY**

Service Centers  
 Mahwah, NJ 07430: 35 Whitney Rd, Suite 5  
 Albany, NY 12205: 14 Walker Way  
 Tonawanda, NY 14150: 275 Cooper Ave, Suite 105

Date Rec'd in Lab 7/17/20

ALPHA Job # L2030254

203467 153

**Project Information**  
 Project Name: *STATISLOW QUANTITATIVE*  
 Project Location: *14 DERTING DRIVE*  
 Project # *N30001001*

**Deliverables**  
 ASP-A  
 EQUIS (1 File)  
 Other  
 ASP-B  
 EQUIS (4 File)

**Billing Information**  
 Same as Client Info  
 PO #

**Client Information**  
 Client: *CIS COMPANIES*  
 Address: *141 ELn ST*  
*Bucarus ny 14203*  
 Phone:  
 Fax:  
 Email: *Rbuckley@cis.com*

**Regulatory Requirement**  
 NY TOGS  
 AWC Standards  
 NY Restricted Use  
 NY Unrestricted Use  
 NYC Sewer Discharge  
 NY Part 375  
 NY CR-51  
 Other

**Disposal Site Information**  
 Please identify below location of applicable disposal facilities.  
 Disposal Facility:  
 NJ  
 NY  
 Other:

These samples have been previously analyzed by Alpha   
 Other project specific requirements/comments:  
 Please specify Metals or TAL.

**ANALYSIS**  
 8260 VOCs  
 TCL+  
 per email  
 of 7/28

**Sample Filtration**  
 Done  
 Lab to do  
 Preservation  
 Lab to do  
 (Please Specify below)

ALPHA Lab ID (Lab Use Only)	Sample ID	Collection		Sample Matrix	Sampler's Initials	Preservative	Container Type	Date/Time	Received By:	Date/Time	Sample Specific Comments
		Date	Time								
30254-01	ESI-3-071520	7/15/20	12:06	GW	RB						
01	01S - ESI3 - 071520	7/15/20	12:00	GW	RB						01
01	01S - ESI3 - 071520	7/15/20	12:00	GW	RB						01
02	PAI-1 - 071520	7/15/20	1:00	GW	RB						02
03	DUP - DU-1 - 071520	7/15/20	1:00	GW	RB						03
04	ESI-1 - 071520	7/15/20	1:20	GW	RB						04
05	ESI-1312 - 071520	7/15/20	1:45	GW	RB						05
05	NS - ESI1312 - 071520	7/15/20	1:45	GW	RB						05
05	NS - ESI1312 - 071520	7/15/20	1:45	GW	RB						05
05	ESI - 1312 - 071520	7/15/20	2:30	GW	RB						05

**Preservative Code:**  
 A = None  
 B = HCl  
 C = HNO3  
 D = H2SO4  
 E = NaOH  
 F = MeOH  
 G = NaHSO4  
 H = Na2S2O3  
 K/E = Zn AcNaOH  
 O = Other

**Container Code:**  
 P = Plastic  
 A = Amber Glass  
 V = Vial  
 G = Glass  
 B = Bacteria Cup  
 C = Cube  
 O = Other  
 D = BOD Bottle

Westboro: Certification No: MA935  
 Mansfield: Certification No: MA015

**Container Type**  
 V  
 B

**Received By:**  
 Date/Time: 7/16/20 16:00  
 Date/Time: 7/16/20 16:00

**Disposal Site Information**  
 Please print clearly, legibly and completely. Samples can not be logged in and turnaround time clock will not start until any ambiguities are resolved. BY EXECUTING THIS COC, THE CLIENT HAS READ AND AGREES TO BE BOUND BY ALPHAS TERMS & CONDITIONS. (See reverse side.)

Form No: 01-25 HC (rev. 30-Sept-2013)

Customer: SA1 VFA, Sample 5  
 delivered by Alpha, CR7158600



Westborough, MA 01581
8 Walkup Dr.
TEL: 508-898-9220
FAX: 508-898-9193

Mansfield, MA 02048
320 Forbes Blvd
TEL: 508-822-9300
FAX: 508-822-3288

NEW YORK
CHAIN OF
CUSTODY

Service Centers
Mansfield, NJ 07430- 35 Whitney Rd, Suite 5
Albany, NY 12205: 14 Walker Way
Tonawanda, NY 14150: 275 Cooper Ave, Suite 105

Page 2 of 2

Date Rec'd in Lab 7/17/20

ALPHA Job # 2030254

203467 2 of 3

Client Information

Client: WHEATON CIS
Address: 141 Elm St.
Beverly MA 02003
Phone:
Fax:
Email: Albrecht@Cis.com

Project Information

Project Name: JANESEWELL CONTRACTOR
Project Location: 14 DEWING DRIVE
Project # NB0 001 001
Project Manager: RICH SATTNER
ALPHAQuote #:
Turn-Around Time
Standard 
Rush (only if pre approved) 
Due Date:
# of Days:

Deliverables

ASP-A 
EQUIS (1 File) 
Other 
ASP-B 
EQUIS (4 File)

Regulatory Requirement

NY TOGS 
AWQ Standards 
NY CP-51 
NY Restricted Use 
NY Unrestricted Use 
NYC Sewer Discharge

Billing Information

Same as Client Info 
PO #

Disposal Site Information

Please identify below location of applicable disposal facilities.
Disposal Facility:
NJ 
NY 
Other:

These samples have been previously analyzed by Alpha

ANALYSIS

Please specify Metals or TAL.

8260 VOC
TEL + Perma
of 50

Table with columns: ALPHA Lab ID (Lab Use Only), Sample ID, Collection Date, Time, Sample Matrix, Sampler's Initials, Container Type, Preservative, Date/Time, Received By, Date/Time. Includes handwritten entries for sample IDs 07-09, 10-15 and collection details.

Form No: 01-25 HC (rev. 30-Sept-2013)

Westboro: Certification No: MA935
Mansfield: Certification No: MA015

Please print clearly, legibly and completely. Samples can not be logged in and turnaround time clock will not start until any ambiguities are resolved. BY EXECUTING THIS COC, THE CLIENT HAS READ AND AGREES TO BE BOUND BY ALPHAS TERMS & CONDITIONS. (See reverse side.)

Signature and date: 8/7/18/2020





### Chain of Custody Supplement

Client: Alpha Analytical Completed by: Glenn Pezzulo  
Lab Project ID: 203467 Date: 7/28/2020

#### Sample Condition Requirements

Per NELAC/ELAP 210/241/242/243/244

Condition	NELAC compliance with the sample condition requirements upon receipt		
	Yes	No	N/A
Container Type	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Comments	_____		
Transferred to method-compliant container	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
Headspace (<1 mL)	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Comments	_____		
Preservation	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Comments	_____		
Chlorine Absent (<0.10 ppm per test strip)	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
Comments	_____		
Holding Time	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Comments	_____		
Temperature	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Comments	<u>3°C iced</u>		
Compliant Sample Quantity/Type	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Comments	_____		

# **DATA USABILITY SUMMARY REPORT (DUSR)**

**Jamestown Container  
Jamestown, NY, 14701  
NYS DEC #: 907020**

**SDG: 203467**  
15 water samples

Prepared for:

**C&S Companies  
141 Elm Street, Suite 100  
Buffalo, NY 14203  
Attention: Cody Martin**

**November 2020**



*Environmental Data Usability 10028 Deer Park Dr. Dansville, NY 14437 585-991-9156*

---

## *Table of Contents*

	<u>Page No.</u>
REVIEWER'S NARRATIVE	
1.0 SUMMARY	1
2.0 INTRODUCTION	1
3.0 SAMPLE AND ANALYSIS SUMMARY	2
4.0 GUIDANCE DOCUMENTS AND DATA REVIEW CRITERIA	2
5.0 DATA VALIDATION QUALIFIERS	3
6.0 RESULTS OF THE DATA REVIEW	4
7.0 TOTAL USABLE DATA	4

---

<b>APPENDIX A</b>	Validated Analytical Results
<b>APPENDIX B</b>	Laboratory QC Documentation
<b>APPENDIX C</b>	Validator Qualifications

### *Tables*

Table 4-1	Data Validation Guidance Documents
Table 4-2	Quality Control Criteria for Validating Laboratory Analytical Data

### **Summaries of Validated Results**

Table 6-1	VOCs (8260)
-----------	-------------

**REVIEWER'S NARRATIVE**


**C & S Companies – SDG 203467 Jamestown Container**

The data associated with this Sample Delivery Group (SDGs), analyzed by Paradigm Environmental Rochester, NY have been reviewed in accordance with assessment criteria provided by the New York State Department of Environmental Conservation following the review procedures provided in the USEPA Functional Guidelines for evaluating organic and inorganic data.

All analytical results reported by the laboratory are considered valid and acceptable except results that have been qualified as rejected, "R". Results qualified as estimated "J", or as non-detects, "U", are considered usable for the purpose of evaluating water and/or soil quality. However, these qualifiers indicate that the accuracy and/or precision of the analytical result is questionable. A summary of all data that have been qualified and the reasons for qualification are provided in the following data usability summary report (DUSR).

Two facts should be noted by all data users. First, the "R" qualifier means that the associated value is unusable. In other words, due to significant quality control (QC) problems, the analysis is invalid and provides no information as to whether the analyte is present or not. Values qualified with an "R" should not appear on the final data tables because they cannot be relied upon, even as the last resort. Second, no analyte concentration, even if it has passed all QC tests, is guaranteed to be accurate. Strict QC serves to increase confidence in data, but any value potentially contains error.

Reviewer's Signature: \_\_\_\_\_

  
Michael K. Perry  
Chemist

Date: \_\_\_\_\_

11/20/20

## 1.0 SUMMARY

<b>SITE:</b>	Jamestown Container 14 Deming Drive Jamestown, NY 14701
<b>SAMPLING DATE:</b>	July 15, 2020
<b>SAMPLE TYPE:</b>	15 water samples
<b>LABORATORY:</b>	Paradigm Environmental Rochester, NY
<b>SDG No.:</b>	203467

## 2.0 INTRODUCTION

This data usability summary report (DUSR) was prepared in accordance with guidance provided by the New York State Department of Environmental Conservation (NYSDEC). The DUSR is based on a review and evaluation of the laboratory analytical data package. Specifically, the NYSDEC guidance recommends review and evaluation of the following elements of the data package:

- Completeness of the data package as defined under the requirements of the NYSDEC Analytical Services Protocols (ASP) Category B or the United States Environmental Protection Agency (USEPA) Contract Laboratory Program (CLP) deliverables,
- Compliance with established analyte holding times,
- Adherence to quality control (QC) limits and specifications for blanks, instrument tuning and calibration, surrogate recoveries, spike recoveries, laboratory duplicate analyses, and other QC criteria,
- Adherence to established analytical protocols,
- Conformance of data summary sheets with raw analytical data, and
- Use of correct data qualifiers.

Data deficiencies, analytical protocol deviations, and quality control problems identified using the review criteria above and their effect on the analytical results are discussed in this report.

### **3.0 SAMPLE AND ANALYSIS SUMMARY**

The data package consists of analytical results for fifteen water samples collected on July 15, 2020. These samples were analyzed for Volatile Organic Compounds (VOCs).

All laboratory analyses were performed by Paradigm Environmental, Rochester, NY and analyzed as SDG 203467. The analytical results were provided in NYSDEC ASP Category B format, which includes all raw analytical data and laboratory QC data.

### **4.0 GUIDANCE DOCUMENTS AND DATA REVIEW CRITERIA**

The guidance documents used for reviewing laboratory quality control (QC) data and assigning data qualifiers (flags) to analytical results are listed in Table 4-1. The QC limits established in the documents applicable to this data review were used to assess the quality of the analytical results. In some cases, however, QC limits established internally by the laboratory were taken into account to determine data quality.

The QC criteria considered for assessing the usability of the reported analytical results provided for each analyte type (i.e. VOCs, SVOCs, metals, etc.) are listed in Table 4-2. These criteria may vary with the analytical method utilized by the laboratory. These criteria comply with the guidance recommended in Section 2.0 above.

### **5.0 DATA VALIDATION QUALIFIERS**

The letter qualifiers (flags) used to define data usability are described briefly below. These letters are assigned by the data validator to analytical results having questionable accuracy and/or precision as determined by reviewing the laboratory QC data associated with the analytical results.

**TABLE 4-1****DATA VALIDATION GUIDANCE DOCUMENTS**

<b>Analyte Type</b>	<b>Validation Guidance</b>
VOCs	USEPA, 2008, Validating Volatile Organic Compounds By Gas Chromatography/Mass Spectrometry; SW-846 Method 8260B; SOP # HW-24, Rev. 2.  USEPA, 2008, Statement of Work for Organic Analysis of Low/Medium Concentration of Volatile Organic Compounds SQM01.2; SOP HW-33, Rev. 2.
SVOCs	USEPA, 2007, Statement of Work for Organic Analysis of Low/Medium Concentration of Semivolatile Organic Compounds SQM01.2; SOP HW-35, Rev. 1.
Pesticides/PCBs	USEPA, 2006, CLP Organics Data Review and Preliminary Review (CLP/SOW OLMO 4.3); SOP # HW-6, Rev. 14, Part C.
Metals	USEPA, 2006, Validation of Metals for the Contract Laboratory Program (CLP) based on SOW ILMO 5.3 (SOP Revision 13), SOP # HW-2, Rev. 13.
Gen Chemistry	NYSDEC, 2005, Analytical Services Protocols (ASP)
VOCs (Ambient air)	USEPA, 2006, Validating Air Samples, Volatile Organic Analysis of Ambient Air in Canister by Method TO-15; SOP # HW-31, Rev. 4.
Perfluoroalkyl Substances (PFASs)	USEPA, 2018, Data Review and Validation Guidelines for Perfluoroalkyl Substances (PFASs) Analyzed Using EPA Method 537

**TABLE 4-2**

**QUALITY CONTROL CRITERIA USED FOR VALIDATING  
LABORATORY ANALYTICAL DATA**

<b>VOCs</b>	<b>SVOCs</b>	<b>Pesticides/PCBs</b>	<b>Metals</b>	<b>Gen Chemistry</b>	<b>Method TO-15</b>
Completeness of Pkg Sample Preservation Holding Time System Monitoring Compounds Lab Control Sample Matrix Spikes Blanks Instrument Tuning Internal Standards Initial Calibration Continuing Calibration Lab Qualifiers Field Duplicate	Completeness of Pkg Sample Preservation Holding Time Surrogate Recoveries Lab Control Sample Matrix Spikes Blanks Instrument Tuning Internal Standards Initial Calibration Continuing Calibration Lab Qualifiers Field Duplicate	Completeness of Pkg Sample Preservation Holding Time Surrogate Recoveries Matrix Spikes Blanks Instrument Calibration & Verification Analyte ID Lab Qualifiers Field Duplicate	Completeness of Pkg Sample Preservation Holding Time Initial/Continuing Calibration CRDL Standards Blanks Interference Check Sample Spike Recoveries Lab Duplicate Lab Control Sample ICP Serial Dilutions Lab Qualifiers Field Duplicate	Completeness of Pkg Sample Preservation Holding Times Calibration Lab Control Samples Blanks Spike Recoveries Lab Duplicates	Completeness of Pkg Sample Preservation Holding Time Canister Certification Lab Control Sample Instrument Tuning Blanks Initial Calibration & System Performance Daily Calibration Field Duplicate

<b>PFASs</b>
Completeness of Pkg Sample Preservation Holding Time Instr Performance Check Initial Calibration Continuing Calibration Blanks Surrogates Lab Fortified Blank Matrix Spikes Internal Standards



The laboratory may also use various letters and symbols to flag analytical results generated when QC limits were exceeded. The meanings of these flags may differ from those used by the independent data validator. Those used by the laboratory are provided with the analytical results.

**NOTE:** The assignment of data qualifiers by the data reviewer (validator) to laboratory analytical results should not necessarily be interpreted by the data user as a measure of laboratory ability or proficiency. Rather, the qualifiers are intended to provide a measure of data accuracy and precision to the data user, which, for example, may provide a level of confidence in determining whether or not standards or cleanup objectives have been met.

- U** The analyte was analyzed for but was not detected at or above the sample quantitation limit.
- J** The analyte was positively identified; the associated numerical value is the *approximate* concentration of the analyte in the sample. (The magnitude of any  $\pm$  value associated with the result is not determined by data validation).
- UJ** The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is *approximate* and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
- R** The sample result is rejected (i.e., is unusable) due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence or absence of the analyte cannot be verified.
- N** The analysis indicates the presence of an analyte for which there is presumptive evidence to make a "tentative identification".
- JN** The analyte is considered to be "presumptively present." The associated numerical value represents its *approximate* concentration.

The validated analytical results are attached to this report. Validation qualifiers (flags) are indicated using red ink. Data sheets having qualified data are signed and dated by the data reviewer.

## **6.0 RESULTS OF THE DATA REVIEW**

The results of the data review are summarized in Table 6-1. The tables list the samples where QC criteria were found to exceed acceptable limits and the actions taken to qualify the associated analytical results.

## **7.0 TOTAL USABLE DATA**

For SDG 203467, fifteen samples were analyzed and results were reported for 915 analytes. Fifteen results were rejected, even though some results were flagged with a “J” as estimated, all other results (98 %) are considered usable. See the summary table for the analyses that have been qualified and the associated QC reasons.

**Table 6-1**      **VOCs**

<b>SAMPLES AFFECTED</b>	<b>ANALYTES</b>	<b>ACTION</b>	<b>QC VIOLATION</b>	<b>COMMENTS</b>
All samples	1,4-Dioxane	R	Initial calibration RRF < 0.005	Based on the new low responders rule from SOM2.1, the RRF < 0.005 is used
PW-1 PW-3R ESI-10 ESI-12	All analytes	UJ non-detects J detects	Surr rec for TD8 > QC limit	Results are estimated
All samples	1,2-DCB 1,3-DCB 1,4-DCB n-Butylbenzene DBCP	UJ non-detects J detects	CCV % D > 20 %	Results are estimated
All samples except: DUP-PW-1 DUP-PW-3R ESI-2	1,2,4-TCB 1,2,3-TCB	UJ non-detects J detects	CCV % D > 20 %	Results are estimated

## ACRONYMS

BSP	Blank Spike
CCAL	Continuing Calibration
CCB	Continuing Calibration Blank
CCV	Continuing Calibration Verification
CRDL	Contract Required Detection Limit
CRQL	Contract Required Quantitation Limit
%D	Percent Difference
ICAL	Initial Calibration
ICB	Initial Calibration Blank
IS	Internal Standard
LCS	Laboratory Control Sample
MS/MSD	Matrix Spike/Matrix Spike Duplicate
QA	Quality Assurance
QC	Quality Control
%R	Percent recovery
RPD	Relative Percent Difference
RRF	Relative Response Factor
%RSD	Percent Relative Standard Deviation
TAL	Target Analyte List (metals)
TCL	Target Compound List (organics)

*Appendix A*

---

*Validated  
Analytical  
Results*



## Analytical Report Cover Page

### *Alpha Analytical*

For Lab Project # 203467  
Issued Date: September 01, 2020  
This report contains a total of 250 pages.

The reported results relate only to the samples as they have been received by the laboratory.

Each page of this document is part of a multipage report. This document may not be reproduced except in its entirety, without the prior consent of Paradigm Environmental Services, Inc.

All soil/sludge samples have been reported on a dry weight basis, unless qualified "reported as received". Other solids are reported as received.

Low level Volatiles blank reports for soil/solid matrix are based on a nominal 5 gram weight. Sample results and reporting limits are based on actual weight, which may be more or less than 5 grams.

The Chain of Custody provides additional information, including compliance with sample condition requirements upon receipt. Sample condition requirements are defined under the 2003 NELAC Standard, sections 5.5.8.3.1 and 5.5.8.3.2.

NYSDOH ELAP does not certify for all parameters. Paradigm Environmental Services or the indicated subcontracted laboratory does hold certification for all analytes where certification is offered by ELAP unless otherwise specified. Aliquots separated for certain tests, such as TCLP, are indicated on the Chain of Custody and final reports with an "A" suffix.

Data qualifiers are used, when necessary, to provide additional information about the data. This information may be communicated as a flag or as text at the bottom of the report. Please refer to the appendix for a list of frequently used data flags and their meaning.

LAB PROJECT NARRATIVE: 203454  
PROJECT NAME: L20302254, C&S Companies, Jamestown Container  
SDG: 3454-01  
CLIENT: Alpha Analytical

Alpha Analytical delivered 11 groundwater samples to the Paradigm Laboratory on July 28, 2020. The samples were collected on July 15, 2020. Samples were accompanied by two field duplicates, an equipment blank, and a field blank. Samples were received under the conditions as noted on the Chain-of-Custody Supplement, at 3°C on ice. The samples were submitted with the Chains-of-Custody requesting the TCL+ list for VOCs. All analyses were performed using EPA SW-846 Methods and the associated holding times.

The items noted in this case narrative address compliance with the referenced methods, NYSDOH ELAP rules, and any project specific data quality requirements. These may be different from the usability criteria referenced in any “Functional Guidelines” or other data review standards used by data validators.

## **GENERAL NOTES**

### **ALL ANALYSES**

The initial and continuing calibration reports are only evaluated for compounds that are on the sample summary report.

Regarding results on QC summary forms versus included raw data, due to calculations made at the instrument where many significant figures may be used, there may be slight discrepancies between the summary report result and that recorded on the raw data. This does not affect data usability.

### **VOLATILES**

Regarding initial calibrations, it should be noted that the Quantitation Report concentrations supplied for the initial calibration reflect the calibration prior to updating. The response factors and areas are correct.

Regarding Quantitation Reports, it should be noted that the “#” symbol that appears on some of the Quantitation Reports is a software artifact and should be disregarded.

Compounds flagged with an “\*” on the summary table have been calibrated using a non-average Response Factor calibration curve. The supporting curves are located after the initial calibration table.

Holding times were met for all samples.

All surrogate recoveries for the samples and associated QC were within acceptance limits, except Toluene-d8 was out low in 30254-02 PW-1-071520, 30254-08 PW-3R-071520, 30254-11 ESI-10-071520, and 30254-13 ESI-12-071520. These outliers have been flagged with an “\*” on the surrogate recovery form and the sample results page. Matrix interference is suspected.

Site specific QC requested on 30254-01 ESI-3-071520 and 30254-05 ESI-13R-071520 and all compounds recovered within acceptance limits. The Laboratory Control Samples recovered within acceptance limits.

The Method Blanks were free from contamination within reportable ranges.

The instrument tunes passed all criteria and samples were within a 12-hour window.

The internal standards areas and retention times were within acceptance ranges for the samples and associated QC.

All data for the initial calibration was within acceptance limits for the reported analytes.

All continuing calibration data was within acceptance limits for the reported analytes, with the following exceptions: 1,3-Dichlorobenzene, 1,4-Dichlorobenzene, 1,2-Dichlorobenzene, n-Butylbenzene, 1,2-Dibromo-3-Chloropropane, 1,2,4-Trichlorobenzene, and 1,2,3-Trichlorobenzene were out high in the CCV analyzed on July 28, 2020. 1,3-Dichlorobenzene, 1,4-Dichlorobenzene, 1,2-Dichlorobenzene, n-Butylbenzene, and 1,2-Dibromo-3-Chloropropane were out high in the CCV analyzed on July 28, 2020. These outliers were deemed usable since the samples were non-detect for these compounds.

(signed) Steven DeVito  
Steven DeVito – Technical Director

(date) 9/1/2020



**BATCH LOG**

Lab Name: Paradigm Environmental Services  
 Lab Project #: 203467  
 Client Name: Alpha Analytical  
 Client Project Name: L2030254, C&S Companies, Jamestown Container  
 Client Project #: N/A  
 SDG No.: 3467-01

Protocol: SW846                      Report Due Date: 8/4/2020                      Batch Due Date: 8/27/2020

LAB SAMPLE NO.	MATRIX	CLIENT SAMPLE ID	REQUESTED ANALYSIS	DATE SAMPLED	DATE REC'D
203467-01	Groundwater	30254-01 ESI-3-071520	VOAs	7/15/2020	7/28/2020
203467-02	Groundwater	30254-02 PW-1-071520	VOAs	7/15/2020	7/28/2020
203467-03	Groundwater	30254-03 DUP-PW-1-071520	VOAs	7/15/2020	7/28/2020
203467-04	Groundwater	30254-04 ESI-1-071520	VOAs	7/15/2020	7/28/2020
203467-05	Groundwater	30254-05 ESI-13R-071520	VOAs	7/15/2020	7/28/2020
203467-06	Groundwater	30254-06 ESI-6-071520	VOAs	7/15/2020	7/28/2020
203467-07	Groundwater	30254-07 ESI-7-071520	VOAs	7/15/2020	7/28/2020
203467-08	Groundwater	30254-08 PW-3R-071520	VOAs	7/15/2020	7/28/2020
203467-09	Groundwater	30254-09 DUP-PW-3R-071520	VOAs	7/15/2020	7/28/2020
203467-10	Groundwater	30254-10 ESI-2-071520	VOAs	7/15/2020	7/28/2020
203467-11	Groundwater	30254-11 ESI-10-071520	VOAs	7/15/2020	7/28/2020
203467-12	Groundwater	30254-12 ESI-11-071520	VOAs	7/15/2020	7/28/2020
203467-13	Groundwater	30254-13 ESI-12-071520	VOAs	7/15/2020	7/28/2020
203467-14	Groundwater	30254-14 Equipment Blank	VOAs	7/15/2020	7/28/2020
203467-15	Groundwater	30254-15 Field Blank	VOAs	7/15/2020	7/28/2020



NEW YORK CHAIN OF CUSTODY

Westborough, MA 01581
8 Walkup Dr.
TEL: 508-898-9220
FAX: 508-898-9193

Mansfield, MA 02048
320 Forbes Blvd
TEL: 508-822-9300
FAX: 508-822-3288

Service Centers
Mahwah, NJ 07430: 35 Whitney Rd, Suite 5
Albany, NY 12205: 14 Walker Way
Tonawanda, NY 14150: 275 Cooper Ave, Suite 105

Date Rec'd in Lab 7/17/20

203467

10F3

ALPHA Job # L2030254

Project Information: Project Name: JAMES STONING CONTRACTING, Project Location: 14 DERRING DRIVE, Project # N30001001. Deliverables: ASP-B checked. Billing Information: Same as Client Info checked. Regulatory Requirement: NY TOGS and NY Part 375 checked. Disposal Site Information: NY checked.

Client Information: Client: CES COMPANIES, Address: 141 E LA ST, BURLINGTON MA 01807. Turn-Around Time: Standard checked. ANALYSIS: 8260 VOCs, TCL+ per contract ed 7/18.

Table with columns: ALPHA Lab ID, Sample ID, Collection Date/Time, Sample Matrix, Sampler's Initials, and Sample Specific Comments. Rows include samples 01, 02, 03, 04, 05, 06.

Preservative Code, Container Code, Westboro/Mansfield Certification No, Container Type, Preservative, Relinquished By, Date/Time, Received By, Date/Time.

Handwritten notes and signatures at the bottom of the page, including 'Rec'd Paradise Ave 7/29/20 103' and 'Custody Seal N/A, samples delivered by Alpha. GP 7/28/20'.



**NEW YORK CHAIN OF CUSTODY**

**Service Centers**  
 Mahwah, NJ 07430: 35 Whitney Rd, Suite 5  
 Albany, NY 12205: 14 Walker Way  
 Tonawanda, NY 14150: 275 Cooper Ave, Suite 105

Westborough, MA 01581  
 8 Walkup Dr.  
 TEL: 508-898-9220  
 FAX: 508-898-9193

Mansfield, MA 02048  
 320 Forbes Blvd  
 TEL: 508-822-9300  
 FAX: 508-822-3288

Page 2 of 2	Date Rec'd in Lab 7/17/20	ALPHA Job # 2030254
----------------	------------------------------	------------------------

<b>Client Information</b>	<b>Project Information</b>	<b>Deliverables</b>	<b>Billing Information</b>
Client: <i>Hineshaus CIS</i>	Project Name: <i>JAMES TOWN CONTAINER</i>	<input type="checkbox"/> ASP-A <input checked="" type="checkbox"/> ASP-B	<input checked="" type="checkbox"/> Same as Client Info
Address: <i>141 RLM ST. BURLINGAME NY 11203</i>	Project Location: <i>141 DEERING DRIVE</i>	<input checked="" type="checkbox"/> EQUIS (1 File) <input type="checkbox"/> EQUIS (4 File)	PO #
Phone:	Project # <i>N30 001 001</i>	<input type="checkbox"/> Other	

<b>Project Manager:</b> <i>RICH BALKERT</i>	<b>Regulatory Requirement</b>	<b>Disposal Site Information</b>
<b>ALPHAQuote #:</b>	<input checked="" type="checkbox"/> NY TOGS <input type="checkbox"/> NY Part 375	Please identify below location of applicable disposal facilities.
<b>Turn-Around Time</b>	<input type="checkbox"/> AWQ Standards <input type="checkbox"/> NY CP-51	Disposal Facility:
Standard <input checked="" type="checkbox"/> Due Date:	<input type="checkbox"/> NY Restricted Use <input type="checkbox"/> Other	<input type="checkbox"/> NJ <input checked="" type="checkbox"/> NY
Rush (only if pre approved) <input type="checkbox"/> # of Days:	<input type="checkbox"/> NY Unrestricted Use	<input type="checkbox"/> Other:
	<input type="checkbox"/> NYC Sewer Discharge	

These samples have been previously analyzed by Alpha

Other project specific requirements/comments:

Please specify Metals or TAL.

ALPHA Lab ID (Lab Use Only)	Sample ID	Collection		Sample Matrix	Sampler's Initials	ANALYSIS	Sample Filtration	Sample Specific Comments	Total Bottles	
		Date	Time							
30254-07	ESI-7-071520	7/15/20	3:00	GW	RB	8260 VOC TEC + perma col F 718	<input type="checkbox"/> Done <input type="checkbox"/> Lab to do	07	1	
08	PW-3R-071520	7/15/20	3:25	GW	RSB		<input type="checkbox"/> Lab to do	08	1	
09	DUP-PW-3R-071520	7/15/20	3:25	GW	RSB			09	1	
10	RSE-2-071520	7/15/20	3:25	GW	RSB			10	1	
11	ESI-10-071520	7/15/20	4:10	GW	RSB			11	1	
12	ESI-11-071520	7/15/20	4:30	GW	RSB			12	1	
13	RSE-12-071520	7/15/20	4:55	GW	RSB			13	1	
14	Equipment Blank	7/15/20	5:00	GW	RSB			14	2	
15	Field Blank	7/15/20	5:00	GW	RSB			15	2	
16	TRIT BLANK	7/15/20	2:00	GW	RSB					

Preservative Code: A = None, B = HCl, C = HNO3, D = H2SO4, E = NaOH, F = MeOH, G = NaHSO4, H = Na2S2O3, K/E = Zn Ac/NaOH, O = Other

Container Code: P = Plastic, A = Amber Glass, V = Vial, G = Glass, B = Bacteria Cup, C = Cube, O = Other, E = Encore, D = BOD Bottle

Westboro: Certification No: MA935  
 Mansfield: Certification No: MA015

Container Type:  V  
 Preservative:  D

Relinquished By:	Date/Time	Received By:	Date/Time
<i>[Signature]</i>	7/16/20 16:00	<i>[Signature]</i>	7/16/20 16:00
<i>[Signature]</i>	7/16/20 16:00	<i>[Signature]</i>	7/17/20 02:00
<i>[Signature]</i>	7/17/20 23:55	<i>[Signature]</i>	7/21/20 23:55
<i>[Signature]</i>	7/28/20 3:25	<i>[Signature]</i>	7/28/20 05:47
<i>[Signature]</i>	7/29/20 10:28	<i>[Signature]</i>	7/29/20 10:30

**VOLATILE ORGANICS**  
**SAMPLE DATA**



Lab Project ID: 203467

Client: Alpha Analytical

Project Reference: L2030254, C&S Companies, Jamestown Container

Sample Identifier: 30254-01 ESI-3-071520

Lab Sample ID: 203467-01

Date Sampled: 7/15/2020

Matrix: Groundwater

Date Received: 7/28/2020

**Volatile Organics**

Analyte	Result	Units	Qualifier	Date Analyzed
1,1,1-Trichloroethane	< 2.00	ug/L		7/28/2020 17:32
1,1,2,2-Tetrachloroethane	< 2.00	ug/L		7/28/2020 17:32
1,1,2-Trichloroethane	< 2.00	ug/L		7/28/2020 17:32
1,1-Dichloroethane	< 2.00	ug/L		7/28/2020 17:32
1,1-Dichloroethene	< 2.00	ug/L		7/28/2020 17:32
1,2,3-Trichlorobenzene	< 5.00 UJ	ug/L		7/28/2020 17:32
1,2,4-Trichlorobenzene	< 5.00 UJ	ug/L		7/28/2020 17:32
1,2,4-Trimethylbenzene	< 2.00	ug/L		7/28/2020 17:32
1,2-Dibromo-3-Chloropropane	< 10.0 UJ	ug/L		7/28/2020 17:32
1,2-Dibromoethane	< 2.00	ug/L		7/28/2020 17:32
1,2-Dichlorobenzene	< 2.00 UJ	ug/L		7/28/2020 17:32
1,2-Dichloroethane	< 2.00	ug/L		7/28/2020 17:32
1,2-Dichloropropane	< 2.00	ug/L		7/28/2020 17:32
1,3,5-Trimethylbenzene	< 2.00	ug/L		7/28/2020 17:32
1,3-Dichlorobenzene	< 2.00 UJ	ug/L		7/28/2020 17:32
1,4-Dichlorobenzene	< 2.00 UJ	ug/L		7/28/2020 17:32
1,4-Dioxane	<del>&lt; 20.0</del> R	ug/L		7/28/2020 17:32
2-Butanone	< 10.0	ug/L		7/28/2020 17:32
2-Hexanone	< 5.00	ug/L		7/28/2020 17:32
4-Methyl-2-pentanone	< 5.00	ug/L		7/28/2020 17:32
Acetone	< 10.0	ug/L		7/28/2020 17:32
Benzene	< 1.00	ug/L		7/28/2020 17:32
Bromochloromethane	< 5.00	ug/L		7/28/2020 17:32

This report is part of a multipage document and should only be evaluated in its entirety. The Chain of Custody provides additional sample information, including compliance with the sample condition requirements upon receipt.



Lab Project ID: 203467

**Client:** Alpha Analytical

**Project Reference:** L2030254, C&S Companies, Jamestown Container

**Sample Identifier:** 30254-01 ESI-3-071520

**Lab Sample ID:** 203467-01

**Date Sampled:** 7/15/2020

**Matrix:** Groundwater

**Date Received:** 7/28/2020

Bromodichloromethane	< 2.00	ug/L	7/28/2020 17:32
Bromoform	< 5.00	ug/L	7/28/2020 17:32
Bromomethane	< 2.00	ug/L	7/28/2020 17:32
Carbon disulfide	< 2.00	ug/L	7/28/2020 17:32
Carbon Tetrachloride	< 2.00	ug/L	7/28/2020 17:32
Chlorobenzene	< 2.00	ug/L	7/28/2020 17:32
Chloroethane	< 2.00	ug/L	7/28/2020 17:32
Chloroform	< 2.00	ug/L	7/28/2020 17:32
Chloromethane	< 2.00	ug/L	7/28/2020 17:32
cis-1,2-Dichloroethene	< 2.00	ug/L	7/28/2020 17:32
cis-1,3-Dichloropropene	< 2.00	ug/L	7/28/2020 17:32
Cyclohexane	< 10.0	ug/L	7/28/2020 17:32
Dibromochloromethane	< 2.00	ug/L	7/28/2020 17:32
Dichlorodifluoromethane	< 2.00	ug/L	7/28/2020 17:32
Ethylbenzene	< 2.00	ug/L	7/28/2020 17:32
Freon 113	< 2.00	ug/L	7/28/2020 17:32
Isopropylbenzene	< 2.00	ug/L	7/28/2020 17:32
m,p-Xylene	< 2.00	ug/L	7/28/2020 17:32
Methyl acetate	< 2.00	ug/L	7/28/2020 17:32
Methyl tert-butyl Ether	< 2.00	ug/L	7/28/2020 17:32
Methylcyclohexane	< 2.00	ug/L	7/28/2020 17:32
Methylene chloride	< 5.00	ug/L	7/28/2020 17:32
Naphthalene	< 5.00	ug/L	7/28/2020 17:32
n-Butylbenzene	< 2.00 UJ	ug/L	7/28/2020 17:32
n-Propylbenzene	< 2.00	ug/L	7/28/2020 17:32

This report is part of a multipage document and should only be evaluated in its entirety. The Chain of Custody provides additional sample information, including compliance with the sample condition requirements upon receipt.



Lab Project ID: 203467

**Client:** Alpha Analytical

**Project Reference:** L2030254, C&S Companies, Jamestown Container

**Sample Identifier:** 30254-01 ESI-3-071520

**Lab Sample ID:** 203467-01

**Date Sampled:** 7/15/2020

**Matrix:** Groundwater

**Date Received:** 7/28/2020

o-Xylene	< 2.00	ug/L	7/28/2020	17:32
p-Isopropyltoluene	< 2.00	ug/L	7/28/2020	17:32
sec-Butylbenzene	< 2.00	ug/L	7/28/2020	17:32
Styrene	< 5.00	ug/L	7/28/2020	17:32
tert-Butylbenzene	< 2.00	ug/L	7/28/2020	17:32
Tetrachloroethene	< 2.00	ug/L	7/28/2020	17:32
Toluene	< 2.00	ug/L	7/28/2020	17:32
trans-1,2-Dichloroethene	< 2.00	ug/L	7/28/2020	17:32
trans-1,3-Dichloropropene	< 2.00	ug/L	7/28/2020	17:32
Trichloroethene	<b>5.47</b>	ug/L	7/28/2020	17:32
Trichlorofluoromethane	< 2.00	ug/L	7/28/2020	17:32
Vinyl chloride	< 2.00	ug/L	7/28/2020	17:32

<b>Surrogate</b>	<b>Percent Recovery</b>	<b>Limits</b>	<b>Outliers</b>	<b>Date Analyzed</b>
1,2-Dichloroethane-d4	<b>97.9</b>	80.8 - 132		7/28/2020 17:32
4-Bromofluorobenzene	<b>63.3</b>	56.6 - 130		7/28/2020 17:32
Pentafluorobenzene	<b>105</b>	87.4 - 113		7/28/2020 17:32
Toluene-D8	<b>86.2</b>	82.2 - 115		7/28/2020 17:32

**Method Reference(s):** EPA 8260C  
EPA 5030C

**Data File:** x72087.D

This report is part of a multipage document and should only be evaluated in its entirety. The Chain of Custody provides additional sample information, including compliance with the sample condition requirements upon receipt.



Lab Project ID: 203467

Client: Alpha Analytical

Project Reference: L2030254, C&S Companies, Jamestown Container

Sample Identifier: 30254-02 PW-1-071520

Lab Sample ID: 203467-02

Date Sampled: 7/15/2020

Matrix: Groundwater

Date Received: 7/28/2020

**Volatile Organics**

Analyte	Result	Units	Qualifier	Date Analyzed
1,1,1-Trichloroethane	< 2.00 UJ	ug/L		7/28/2020 21:38
1,1,2,2-Tetrachloroethane	< 2.00	ug/L		7/28/2020 21:38
1,1,2-Trichloroethane	< 2.00	ug/L		7/28/2020 21:38
1,1-Dichloroethane	< 2.00	ug/L		7/28/2020 21:38
1,1-Dichloroethene	< 2.00	ug/L		7/28/2020 21:38
1,2,3-Trichlorobenzene	< 5.00	ug/L		7/28/2020 21:38
1,2,4-Trichlorobenzene	< 5.00	ug/L		7/28/2020 21:38
1,2,4-Trimethylbenzene	< 2.00	ug/L		7/28/2020 21:38
1,2-Dibromo-3-Chloropropane	< 10.0	ug/L		7/28/2020 21:38
1,2-Dibromoethane	< 2.00	ug/L		7/28/2020 21:38
1,2-Dichlorobenzene	< 2.00	ug/L		7/28/2020 21:38
1,2-Dichloroethane	< 2.00	ug/L		7/28/2020 21:38
1,2-Dichloropropane	< 2.00	ug/L		7/28/2020 21:38
1,3,5-Trimethylbenzene	< 2.00	ug/L		7/28/2020 21:38
1,3-Dichlorobenzene	< 2.00	ug/L		7/28/2020 21:38
1,4-Dichlorobenzene	< 2.00	ug/L		7/28/2020 21:38
1,4-Dioxane	<del>&lt; 20.0</del> R	ug/L		7/28/2020 21:38
2-Butanone	< 10.0 UJ	ug/L		7/28/2020 21:38
2-Hexanone	< 5.00	ug/L		7/28/2020 21:38
4-Methyl-2-pentanone	< 5.00	ug/L		7/28/2020 21:38
Acetone	< 10.0	ug/L		7/28/2020 21:38
Benzene	< 1.00	ug/L		7/28/2020 21:38
Bromochloromethane	< 5.00	ug/L		7/28/2020 21:38

This report is part of a multipage document and should only be evaluated in its entirety. The Chain of Custody provides additional sample information, including compliance with the sample condition requirements upon receipt.





**Client:** Alpha Analytical

**Project Reference:** L2030254, C&S Companies, Jamestown Container

**Sample Identifier:** 30254-02 PW-1-071520

**Lab Sample ID:** 203467-02

**Date Sampled:** 7/15/2020

**Matrix:** Groundwater

**Date Received:** 7/28/2020

Bromodichloromethane	< 2.00	UJ	ug/L	7/28/2020	21:38	
Bromoform	< 5.00		ug/L	7/28/2020	21:38	
Bromomethane	< 2.00		ug/L	7/28/2020	21:38	
Carbon disulfide	< 2.00		ug/L	7/28/2020	21:38	
Carbon Tetrachloride	< 2.00		ug/L	7/28/2020	21:38	
Chlorobenzene	< 2.00		ug/L	7/28/2020	21:38	
Chloroethane	< 2.00		ug/L	7/28/2020	21:38	
Chloroform	< 2.00		ug/L	7/28/2020	21:38	
Chloromethane	< 2.00		ug/L	7/28/2020	21:38	
cis-1,2-Dichloroethene	7.89		J	ug/L	7/28/2020	21:38
cis-1,3-Dichloropropene	< 2.00		UJ	ug/L	7/28/2020	21:38
Cyclohexane	< 10.0		ug/L	7/28/2020	21:38	
Dibromochloromethane	< 2.00		ug/L	7/28/2020	21:38	
Dichlorodifluoromethane	< 2.00		ug/L	7/28/2020	21:38	
Ethylbenzene	< 2.00		ug/L	7/28/2020	21:38	
Freon 113	< 2.00		ug/L	7/28/2020	21:38	
Isopropylbenzene	< 2.00		ug/L	7/28/2020	21:38	
m,p-Xylene	< 2.00		ug/L	7/28/2020	21:38	
Methyl acetate	< 2.00		ug/L	7/28/2020	21:38	
Methyl tert-butyl Ether	< 2.00	ug/L	7/28/2020	21:38		
Methylcyclohexane	< 2.00	ug/L	7/28/2020	21:38		
Methylene chloride	< 5.00	ug/L	7/28/2020	21:38		
Naphthalene	< 5.00	ug/L	7/28/2020	21:38		
n-Butylbenzene	< 2.00	ug/L	7/28/2020	21:38		
n-Propylbenzene	< 2.00	ug/L	7/28/2020	21:38		

This report is part of a multipage document and should only be evaluated in its entirety. The Chain of Custody provides additional sample information, including compliance with the sample condition requirements upon receipt.



Lab Project ID: 203467

**Client:** Alpha Analytical

**Project Reference:** L2030254, C&S Companies, Jamestown Container

**Sample Identifier:** 30254-02 PW-1-071520

**Lab Sample ID:** 203467-02

**Date Sampled:** 7/15/2020

**Matrix:** Groundwater

**Date Received:** 7/28/2020

o-Xylene	< 2.00	UJ	ug/L	7/28/2020	21:38
p-Isopropyltoluene	< 2.00		ug/L	7/28/2020	21:38
sec-Butylbenzene	< 2.00		ug/L	7/28/2020	21:38
Styrene	< 5.00		ug/L	7/28/2020	21:38
tert-Butylbenzene	< 2.00		ug/L	7/28/2020	21:38
Tetrachloroethene	< 2.00		ug/L	7/28/2020	21:38
Toluene	< 2.00		ug/L	7/28/2020	21:38
trans-1,2-Dichloroethene	< 2.00		ug/L	7/28/2020	21:38
trans-1,3-Dichloropropene	< 2.00		ug/L	7/28/2020	21:38
Trichloroethene	27.4	J	ug/L	7/28/2020	21:38
Trichlorofluoromethane	< 2.00	UJ	ug/L	7/28/2020	21:38
Vinyl chloride	< 2.00	UJ	ug/L	7/28/2020	21:38

Surrogate	Percent Recovery	Limits	Outliers	Date Analyzed
1,2-Dichloroethane-d4	127	80.8 - 132		7/28/2020 21:38
4-Bromofluorobenzene	63.4	56.6 - 130		7/28/2020 21:38
Pentafluorobenzene	98.8	87.4 - 113		7/28/2020 21:38
Toluene-D8	79.0	82.2 - 115	*	7/28/2020 21:38

**Method Reference(s):** EPA 8260C  
EPA 5030C  
**Data File:** x72098.D

MKP 11/20/2020

This report is part of a multipage document and should only be evaluated in its entirety. The Chain of Custody provides additional sample information, including compliance with the sample condition requirements upon receipt.



Lab Project ID: 203467

Client: Alpha Analytical

Project Reference: L2030254, C&S Companies, Jamestown Container

Sample Identifier: 30254-03 DUP-PW-1-071520

Lab Sample ID: 203467-03

Date Sampled: 7/15/2020

Matrix: Groundwater

Date Received: 7/28/2020

**Volatile Organics**

Analyte	Result	Units	Qualifier	Date Analyzed
1,1,1-Trichloroethane	< 2.00	ug/L		7/29/2020 14:36
1,1,2,2-Tetrachloroethane	< 2.00	ug/L		7/29/2020 14:36
1,1,2-Trichloroethane	< 2.00	ug/L		7/29/2020 14:36
1,1-Dichloroethane	< 2.00	ug/L		7/29/2020 14:36
1,1-Dichloroethene	< 2.00	ug/L		7/29/2020 14:36
1,2,3-Trichlorobenzene	< 5.00	ug/L		7/29/2020 14:36
1,2,4-Trichlorobenzene	< 5.00	ug/L		7/29/2020 14:36
1,2,4-Trimethylbenzene	< 2.00	ug/L		7/29/2020 14:36
1,2-Dibromo-3-Chloropropane	< 10.0 UJ	ug/L		7/29/2020 14:36
1,2-Dibromoethane	< 2.00	ug/L		7/29/2020 14:36
1,2-Dichlorobenzene	< 2.00 UJ	ug/L		7/29/2020 14:36
1,2-Dichloroethane	< 2.00	ug/L		7/29/2020 14:36
1,2-Dichloropropane	< 2.00	ug/L		7/29/2020 14:36
1,3,5-Trimethylbenzene	< 2.00	ug/L		7/29/2020 14:36
1,3-Dichlorobenzene	< 2.00 UJ	ug/L		7/29/2020 14:36
1,4-Dichlorobenzene	< 2.00 UJ	ug/L		7/29/2020 14:36
1,4-Dioxane	< <del>20.0</del> R	ug/L		7/29/2020 14:36
2-Butanone	< 10.0	ug/L		7/29/2020 14:36
2-Hexanone	< 5.00	ug/L		7/29/2020 14:36
4-Methyl-2-pentanone	< 5.00	ug/L		7/29/2020 14:36
Acetone	< 10.0	ug/L		7/29/2020 14:36
Benzene	< 1.00	ug/L		7/29/2020 14:36
Bromochloromethane	< 5.00	ug/L		7/29/2020 14:36

This report is part of a multipage document and should only be evaluated in its entirety. The Chain of Custody provides additional sample information, including compliance with the sample condition requirements upon receipt.



Lab Project ID: 203467

**Client:** Alpha Analytical

**Project Reference:** L2030254, C&S Companies, Jamestown Container

**Sample Identifier:** 30254-03 DUP-PW-1-071520

**Lab Sample ID:** 203467-03

**Date Sampled:** 7/15/2020

**Matrix:** Groundwater

**Date Received:** 7/28/2020

Bromodichloromethane	< 2.00	ug/L	7/29/2020 14:36
Bromoform	< 5.00	ug/L	7/29/2020 14:36
Bromomethane	< 2.00	ug/L	7/29/2020 14:36
Carbon disulfide	< 2.00	ug/L	7/29/2020 14:36
Carbon Tetrachloride	< 2.00	ug/L	7/29/2020 14:36
Chlorobenzene	< 2.00	ug/L	7/29/2020 14:36
Chloroethane	< 2.00	ug/L	7/29/2020 14:36
Chloroform	< 2.00	ug/L	7/29/2020 14:36
Chloromethane	< 2.00	ug/L	7/29/2020 14:36
cis-1,2-Dichloroethene	<b>8.57</b>	ug/L	7/29/2020 14:36
cis-1,3-Dichloropropene	< 2.00	ug/L	7/29/2020 14:36
Cyclohexane	< 10.0	ug/L	7/29/2020 14:36
Dibromochloromethane	< 2.00	ug/L	7/29/2020 14:36
Dichlorodifluoromethane	< 2.00	ug/L	7/29/2020 14:36
Ethylbenzene	< 2.00	ug/L	7/29/2020 14:36
Freon 113	< 2.00	ug/L	7/29/2020 14:36
Isopropylbenzene	< 2.00	ug/L	7/29/2020 14:36
m,p-Xylene	< 2.00	ug/L	7/29/2020 14:36
Methyl acetate	< 2.00	ug/L	7/29/2020 14:36
Methyl tert-butyl Ether	< 2.00	ug/L	7/29/2020 14:36
Methylcyclohexane	< 2.00	ug/L	7/29/2020 14:36
Methylene chloride	< 5.00	ug/L	7/29/2020 14:36
Naphthalene	< 5.00	ug/L	7/29/2020 14:36
n-Butylbenzene	< 2.00 UJ	ug/L	7/29/2020 14:36
n-Propylbenzene	< 2.00	ug/L	7/29/2020 14:36

This report is part of a multipage document and should only be evaluated in its entirety. The Chain of Custody provides additional sample information, including compliance with the sample condition requirements upon receipt.



Lab Project ID: 203467

Client: Alpha Analytical

Project Reference: L2030254, C&S Companies, Jamestown Container

Sample Identifier: 30254-03 DUP-PW-1-071520

Lab Sample ID: 203467-03

Date Sampled: 7/15/2020

Matrix: Groundwater

Date Received: 7/28/2020

o-Xylene	< 2.00	ug/L	7/29/2020	14:36
p-Isopropyltoluene	< 2.00	ug/L	7/29/2020	14:36
sec-Butylbenzene	< 2.00	ug/L	7/29/2020	14:36
Styrene	< 5.00	ug/L	7/29/2020	14:36
tert-Butylbenzene	< 2.00	ug/L	7/29/2020	14:36
Tetrachloroethene	< 2.00	ug/L	7/29/2020	14:36
Toluene	< 2.00	ug/L	7/29/2020	14:36
trans-1,2-Dichloroethene	< 2.00	ug/L	7/29/2020	14:36
trans-1,3-Dichloropropene	< 2.00	ug/L	7/29/2020	14:36
Trichloroethene	<b>30.2</b>	ug/L	7/29/2020	14:36
Trichlorofluoromethane	< 2.00	ug/L	7/29/2020	14:36
Vinyl chloride	< 2.00	ug/L	7/29/2020	14:36

Surrogate	Percent Recovery	Limits	Outliers	Date Analyzed
1,2-Dichloroethane-d4	<b>115</b>	80.8 - 132		7/29/2020 14:36
4-Bromofluorobenzene	<b>62.2</b>	56.6 - 130		7/29/2020 14:36
Pentafluorobenzene	<b>103</b>	87.4 - 113		7/29/2020 14:36
Toluene-D8	<b>82.9</b>	82.2 - 115		7/29/2020 14:36

Method Reference(s): EPA 8260C  
EPA 5030C  
Data File: x72116.D

This report is part of a multipage document and should only be evaluated in its entirety. The Chain of Custody provides additional sample information, including compliance with the sample condition requirements upon receipt.



Lab Project ID: 203467

Client: Alpha Analytical

Project Reference: L2030254, C&S Companies, Jamestown Container

Sample Identifier: 30254-04 ESI-1-071520

Lab Sample ID: 203467-04

Date Sampled: 7/15/2020

Matrix: Groundwater

Date Received: 7/28/2020

**Volatile Organics**

Analyte	Result	Units	Qualifier	Date Analyzed
1,1,1-Trichloroethane	< 2.00	ug/L		7/28/2020 17:54
1,1,2,2-Tetrachloroethane	< 2.00	ug/L		7/28/2020 17:54
1,1,2-Trichloroethane	< 2.00	ug/L		7/28/2020 17:54
1,1-Dichloroethane	< 2.00	ug/L		7/28/2020 17:54
1,1-Dichloroethene	< 2.00	ug/L		7/28/2020 17:54
1,2,3-Trichlorobenzene	< 5.00 UJ	ug/L		7/28/2020 17:54
1,2,4-Trichlorobenzene	< 5.00 UJ	ug/L		7/28/2020 17:54
1,2,4-Trimethylbenzene	< 2.00	ug/L		7/28/2020 17:54
1,2-Dibromo-3-Chloropropane	< 10.0 UJ	ug/L		7/28/2020 17:54
1,2-Dibromoethane	< 2.00	ug/L		7/28/2020 17:54
1,2-Dichlorobenzene	< 2.00 UJ	ug/L		7/28/2020 17:54
1,2-Dichloroethane	< 2.00	ug/L		7/28/2020 17:54
1,2-Dichloropropane	< 2.00	ug/L		7/28/2020 17:54
1,3,5-Trimethylbenzene	< 2.00	ug/L		7/28/2020 17:54
1,3-Dichlorobenzene	< 2.00 UJ	ug/L		7/28/2020 17:54
1,4-Dichlorobenzene	< 2.00 UJ	ug/L		7/28/2020 17:54
1,4-Dioxane	< <del>20.0</del> R	ug/L		7/28/2020 17:54
2-Butanone	< 10.0	ug/L		7/28/2020 17:54
2-Hexanone	< 5.00	ug/L		7/28/2020 17:54
4-Methyl-2-pentanone	< 5.00	ug/L		7/28/2020 17:54
Acetone	< 10.0	ug/L		7/28/2020 17:54
Benzene	< 1.00	ug/L		7/28/2020 17:54
Bromochloromethane	< 5.00	ug/L		7/28/2020 17:54

This report is part of a multipage document and should only be evaluated in its entirety. The Chain of Custody provides additional sample information, including compliance with the sample condition requirements upon receipt.



Lab Project ID: 203467

Client: Alpha Analytical

Project Reference: L2030254, C&S Companies, Jamestown Container

<b>Sample Identifier:</b>	30254-04 ESI-1-071520		
<b>Lab Sample ID:</b>	203467-04	<b>Date Sampled:</b>	7/15/2020
<b>Matrix:</b>	Groundwater	<b>Date Received:</b>	7/28/2020
Bromodichloromethane	< 2.00	ug/L	7/28/2020 17:54
Bromoform	< 5.00	ug/L	7/28/2020 17:54
Bromomethane	< 2.00	ug/L	7/28/2020 17:54
Carbon disulfide	< 2.00	ug/L	7/28/2020 17:54
Carbon Tetrachloride	< 2.00	ug/L	7/28/2020 17:54
Chlorobenzene	< 2.00	ug/L	7/28/2020 17:54
Chloroethane	< 2.00	ug/L	7/28/2020 17:54
Chloroform	< 2.00	ug/L	7/28/2020 17:54
Chloromethane	< 2.00	ug/L	7/28/2020 17:54
cis-1,2-Dichloroethene	<b>1.01</b>	ug/L	J 7/28/2020 17:54
cis-1,3-Dichloropropene	< 2.00	ug/L	7/28/2020 17:54
Cyclohexane	< 10.0	ug/L	7/28/2020 17:54
Dibromochloromethane	< 2.00	ug/L	7/28/2020 17:54
Dichlorodifluoromethane	< 2.00	ug/L	7/28/2020 17:54
Ethylbenzene	< 2.00	ug/L	7/28/2020 17:54
Freon 113	< 2.00	ug/L	7/28/2020 17:54
Isopropylbenzene	< 2.00	ug/L	7/28/2020 17:54
m,p-Xylene	< 2.00	ug/L	7/28/2020 17:54
Methyl acetate	< 2.00	ug/L	7/28/2020 17:54
Methyl tert-butyl Ether	< 2.00	ug/L	7/28/2020 17:54
Methylcyclohexane	< 2.00	ug/L	7/28/2020 17:54
Methylene chloride	< 5.00	ug/L	7/28/2020 17:54
Naphthalene	< 5.00	ug/L	7/28/2020 17:54
n-Butylbenzene	< 2.00 UJ	ug/L	7/28/2020 17:54
n-Propylbenzene	< 2.00	ug/L	7/28/2020 17:54

This report is part of a multipage document and should only be evaluated in its entirety. The Chain of Custody provides additional sample information, including compliance with the sample condition requirements upon receipt.



Lab Project ID: 203467

Client: Alpha Analytical

Project Reference: L2030254, C&S Companies, Jamestown Container

Sample Identifier: 30254-04 ESI-1-071520

Lab Sample ID: 203467-04

Date Sampled: 7/15/2020

Matrix: Groundwater

Date Received: 7/28/2020

o-Xylene	< 2.00	ug/L	7/28/2020	17:54
p-Isopropyltoluene	< 2.00	ug/L	7/28/2020	17:54
sec-Butylbenzene	< 2.00	ug/L	7/28/2020	17:54
Styrene	< 5.00	ug/L	7/28/2020	17:54
tert-Butylbenzene	< 2.00	ug/L	7/28/2020	17:54
Tetrachloroethene	< 2.00	ug/L	7/28/2020	17:54
Toluene	< 2.00	ug/L	7/28/2020	17:54
trans-1,2-Dichloroethene	< 2.00	ug/L	7/28/2020	17:54
trans-1,3-Dichloropropene	< 2.00	ug/L	7/28/2020	17:54
Trichloroethene	<b>6.72</b>	ug/L	7/28/2020	17:54
Trichlorofluoromethane	< 2.00	ug/L	7/28/2020	17:54
Vinyl chloride	< 2.00	ug/L	7/28/2020	17:54

Surrogate	Percent Recovery	Limits	Outliers	Date Analyzed
1,2-Dichloroethane-d4	<b>103</b>	80.8 - 132		7/28/2020 17:54
4-Bromofluorobenzene	<b>62.6</b>	56.6 - 130		7/28/2020 17:54
Pentafluorobenzene	<b>105</b>	87.4 - 113		7/28/2020 17:54
Toluene-D8	<b>88.6</b>	82.2 - 115		7/28/2020 17:54

Method Reference(s): EPA 8260C  
EPA 5030C  
Data File: x72088.D

This report is part of a multipage document and should only be evaluated in its entirety. The Chain of Custody provides additional sample information, including compliance with the sample condition requirements upon receipt.





Lab Project ID: 203467

Client: Alpha Analytical

Project Reference: L2030254, C&S Companies, Jamestown Container

Sample Identifier: 30254-05 ESI-13R-071520

Lab Sample ID: 203467-05

Date Sampled: 7/15/2020

Matrix: Groundwater

Date Received: 7/28/2020

**Volatile Organics**

Analyte	Result	Units	Qualifier	Date Analyzed
1,1,1-Trichloroethane	< 2.00	ug/L		7/28/2020 18:17
1,1,2,2-Tetrachloroethane	< 2.00	ug/L		7/28/2020 18:17
1,1,2-Trichloroethane	< 2.00	ug/L		7/28/2020 18:17
1,1-Dichloroethane	< 2.00	ug/L		7/28/2020 18:17
1,1-Dichloroethene	< 2.00	ug/L		7/28/2020 18:17
1,2,3-Trichlorobenzene	< 5.00 UJ	ug/L		7/28/2020 18:17
1,2,4-Trichlorobenzene	< 5.00 UJ	ug/L		7/28/2020 18:17
1,2,4-Trimethylbenzene	< 2.00	ug/L		7/28/2020 18:17
1,2-Dibromo-3-Chloropropane	< 10.0 UJ	ug/L		7/28/2020 18:17
1,2-Dibromoethane	< 2.00	ug/L		7/28/2020 18:17
1,2-Dichlorobenzene	< 2.00 UJ	ug/L		7/28/2020 18:17
1,2-Dichloroethane	< 2.00	ug/L		7/28/2020 18:17
1,2-Dichloropropane	< 2.00	ug/L		7/28/2020 18:17
1,3,5-Trimethylbenzene	< 2.00	ug/L		7/28/2020 18:17
1,3-Dichlorobenzene	< 2.00 UJ	ug/L		7/28/2020 18:17
1,4-Dichlorobenzene	< 2.00 UJ	ug/L		7/28/2020 18:17
1,4-Dioxane	<del>&lt; 20.0</del> R	ug/L		7/28/2020 18:17
2-Butanone	< 10.0	ug/L		7/28/2020 18:17
2-Hexanone	< 5.00	ug/L		7/28/2020 18:17
4-Methyl-2-pentanone	< 5.00	ug/L		7/28/2020 18:17
Acetone	< 10.0	ug/L		7/28/2020 18:17
Benzene	< 1.00	ug/L		7/28/2020 18:17
Bromochloromethane	< 5.00	ug/L		7/28/2020 18:17

This report is part of a multipage document and should only be evaluated in its entirety. The Chain of Custody provides additional sample information, including compliance with the sample condition requirements upon receipt.



Lab Project ID: 203467

Client: Alpha Analytical

Project Reference: L2030254, C&S Companies, Jamestown Container

<b>Sample Identifier:</b>	30254-05 ESI-13R-071520		
<b>Lab Sample ID:</b>	203467-05	<b>Date Sampled:</b>	7/15/2020
<b>Matrix:</b>	Groundwater	<b>Date Received:</b>	7/28/2020
Bromodichloromethane	< 2.00	ug/L	7/28/2020 18:17
Bromoform	< 5.00	ug/L	7/28/2020 18:17
Bromomethane	< 2.00	ug/L	7/28/2020 18:17
Carbon disulfide	< 2.00	ug/L	7/28/2020 18:17
Carbon Tetrachloride	< 2.00	ug/L	7/28/2020 18:17
Chlorobenzene	< 2.00	ug/L	7/28/2020 18:17
Chloroethane	< 2.00	ug/L	7/28/2020 18:17
Chloroform	< 2.00	ug/L	7/28/2020 18:17
Chloromethane	< 2.00	ug/L	7/28/2020 18:17
cis-1,2-Dichloroethene	<b>4.38</b>	ug/L	7/28/2020 18:17
cis-1,3-Dichloropropene	< 2.00	ug/L	7/28/2020 18:17
Cyclohexane	< 10.0	ug/L	7/28/2020 18:17
Dibromochloromethane	< 2.00	ug/L	7/28/2020 18:17
Dichlorodifluoromethane	< 2.00	ug/L	7/28/2020 18:17
Ethylbenzene	< 2.00	ug/L	7/28/2020 18:17
Freon 113	< 2.00	ug/L	7/28/2020 18:17
Isopropylbenzene	< 2.00	ug/L	7/28/2020 18:17
m,p-Xylene	< 2.00	ug/L	7/28/2020 18:17
Methyl acetate	< 2.00	ug/L	7/28/2020 18:17
Methyl tert-butyl Ether	< 2.00	ug/L	7/28/2020 18:17
Methylcyclohexane	< 2.00	ug/L	7/28/2020 18:17
Methylene chloride	< 5.00	ug/L	7/28/2020 18:17
Naphthalene	< 5.00	ug/L	7/28/2020 18:17
n-Butylbenzene	< 2.00 UJ	ug/L	7/28/2020 18:17
n-Propylbenzene	< 2.00	ug/L	7/28/2020 18:17

This report is part of a multipage document and should only be evaluated in its entirety. The Chain of Custody provides additional sample information, including compliance with the sample condition requirements upon receipt.



Lab Project ID: 203467

Client: Alpha Analytical

Project Reference: L2030254, C&S Companies, Jamestown Container

Sample Identifier: 30254-05 ESI-13R-071520

Lab Sample ID: 203467-05

Date Sampled: 7/15/2020

Matrix: Groundwater

Date Received: 7/28/2020

o-Xylene	< 2.00	ug/L	7/28/2020	18:17
p-Isopropyltoluene	< 2.00	ug/L	7/28/2020	18:17
sec-Butylbenzene	< 2.00	ug/L	7/28/2020	18:17
Styrene	< 5.00	ug/L	7/28/2020	18:17
tert-Butylbenzene	< 2.00	ug/L	7/28/2020	18:17
Tetrachloroethene	< 2.00	ug/L	7/28/2020	18:17
Toluene	< 2.00	ug/L	7/28/2020	18:17
trans-1,2-Dichloroethene	< 2.00	ug/L	7/28/2020	18:17
trans-1,3-Dichloropropene	< 2.00	ug/L	7/28/2020	18:17
Trichloroethene	<b>13.7</b>	ug/L	7/28/2020	18:17
Trichlorofluoromethane	< 2.00	ug/L	7/28/2020	18:17
Vinyl chloride	< 2.00	ug/L	7/28/2020	18:17

Surrogate	Percent Recovery	Limits	Outliers	Date Analyzed
1,2-Dichloroethane-d4	<b>104</b>	80.8 - 132		7/28/2020 18:17
4-Bromofluorobenzene	<b>63.1</b>	56.6 - 130		7/28/2020 18:17
Pentafluorobenzene	<b>103</b>	87.4 - 113		7/28/2020 18:17
Toluene-D8	<b>84.5</b>	82.2 - 115		7/28/2020 18:17

Method Reference(s): EPA 8260C  
EPA 5030C

Data File: x72089.D

This report is part of a multipage document and should only be evaluated in its entirety. The Chain of Custody provides additional sample information, including compliance with the sample condition requirements upon receipt.



Lab Project ID: 203467

Client: Alpha Analytical

Project Reference: L2030254, C&S Companies, Jamestown Container

Sample Identifier: 30254-06 ESI-6-071520

Lab Sample ID: 203467-06

Date Sampled: 7/15/2020

Matrix: Groundwater

Date Received: 7/28/2020

**Volatile Organics**

Analyte	Result	Units	Qualifier	Date Analyzed
1,1,1-Trichloroethane	< 2.00	ug/L		7/28/2020 18:39
1,1,2,2-Tetrachloroethane	< 2.00	ug/L		7/28/2020 18:39
1,1,2-Trichloroethane	< 2.00	ug/L		7/28/2020 18:39
1,1-Dichloroethane	< 2.00	ug/L		7/28/2020 18:39
1,1-Dichloroethene	< 2.00	ug/L		7/28/2020 18:39
1,2,3-Trichlorobenzene	< 5.00 UJ	ug/L		7/28/2020 18:39
1,2,4-Trichlorobenzene	< 5.00 UJ	ug/L		7/28/2020 18:39
1,2,4-Trimethylbenzene	< 2.00	ug/L		7/28/2020 18:39
1,2-Dibromo-3-Chloropropane	< 10.0 UJ	ug/L		7/28/2020 18:39
1,2-Dibromoethane	< 2.00	ug/L		7/28/2020 18:39
1,2-Dichlorobenzene	< 2.00 UJ	ug/L		7/28/2020 18:39
1,2-Dichloroethane	< 2.00	ug/L		7/28/2020 18:39
1,2-Dichloropropane	< 2.00	ug/L		7/28/2020 18:39
1,3,5-Trimethylbenzene	< 2.00	ug/L		7/28/2020 18:39
1,3-Dichlorobenzene	< 2.00 UJ	ug/L		7/28/2020 18:39
1,4-Dichlorobenzene	< 2.00 UJ	ug/L		7/28/2020 18:39
1,4-Dioxane	< <del>2.00</del> R	ug/L		7/28/2020 18:39
2-Butanone	< 10.0	ug/L		7/28/2020 18:39
2-Hexanone	< 5.00	ug/L		7/28/2020 18:39
4-Methyl-2-pentanone	< 5.00	ug/L		7/28/2020 18:39
Acetone	<b>15.8</b>	ug/L		7/28/2020 18:39
Benzene	< 1.00	ug/L		7/28/2020 18:39
Bromochloromethane	< 5.00	ug/L		7/28/2020 18:39

This report is part of a multipage document and should only be evaluated in its entirety. The Chain of Custody provides additional sample information, including compliance with the sample condition requirements upon receipt.



Lab Project ID: 203467

**Client:** Alpha Analytical

**Project Reference:** L2030254, C&S Companies, Jamestown Container

<b>Sample Identifier:</b>	30254-06 ESI-6-071520		
<b>Lab Sample ID:</b>	203467-06	<b>Date Sampled:</b>	7/15/2020
<b>Matrix:</b>	Groundwater	<b>Date Received:</b>	7/28/2020
Bromodichloromethane	< 2.00	ug/L	7/28/2020 18:39
Bromoform	<b>13.2</b>	ug/L	7/28/2020 18:39
Bromomethane	< 2.00	ug/L	7/28/2020 18:39
Carbon disulfide	< 2.00	ug/L	7/28/2020 18:39
Carbon Tetrachloride	< 2.00	ug/L	7/28/2020 18:39
Chlorobenzene	< 2.00	ug/L	7/28/2020 18:39
Chloroethane	< 2.00	ug/L	7/28/2020 18:39
Chloroform	< 2.00	ug/L	7/28/2020 18:39
Chloromethane	< 2.00	ug/L	7/28/2020 18:39
cis-1,2-Dichloroethene	< 2.00	ug/L	7/28/2020 18:39
cis-1,3-Dichloropropene	< 2.00	ug/L	7/28/2020 18:39
Cyclohexane	< 10.0	ug/L	7/28/2020 18:39
Dibromochloromethane	< 2.00	ug/L	7/28/2020 18:39
Dichlorodifluoromethane	< 2.00	ug/L	7/28/2020 18:39
Ethylbenzene	< 2.00	ug/L	7/28/2020 18:39
Freon 113	< 2.00	ug/L	7/28/2020 18:39
Isopropylbenzene	< 2.00	ug/L	7/28/2020 18:39
m,p-Xylene	< 2.00	ug/L	7/28/2020 18:39
Methyl acetate	< 2.00	ug/L	7/28/2020 18:39
Methyl tert-butyl Ether	< 2.00	ug/L	7/28/2020 18:39
Methylcyclohexane	< 2.00	ug/L	7/28/2020 18:39
Methylene chloride	< 5.00	ug/L	7/28/2020 18:39
Naphthalene	< 5.00	ug/L	7/28/2020 18:39
n-Butylbenzene	< 2.00 UJ	ug/L	7/28/2020 18:39
n-Propylbenzene	< 2.00	ug/L	7/28/2020 18:39

This report is part of a multipage document and should only be evaluated in its entirety. The Chain of Custody provides additional sample information, including compliance with the sample condition requirements upon receipt.



Lab Project ID: 203467

**Client:** Alpha Analytical

**Project Reference:** L2030254, C&S Companies, Jamestown Container

**Sample Identifier:** 30254-06 ESI-6-071520

**Lab Sample ID:** 203467-06

**Date Sampled:** 7/15/2020

**Matrix:** Groundwater

**Date Received:** 7/28/2020

o-Xylene	< 2.00	ug/L	7/28/2020	18:39
p-Isopropyltoluene	< 2.00	ug/L	7/28/2020	18:39
sec-Butylbenzene	< 2.00	ug/L	7/28/2020	18:39
Styrene	< 5.00	ug/L	7/28/2020	18:39
tert-Butylbenzene	< 2.00	ug/L	7/28/2020	18:39
Tetrachloroethene	< 2.00	ug/L	7/28/2020	18:39
Toluene	< 2.00	ug/L	7/28/2020	18:39
trans-1,2-Dichloroethene	< 2.00	ug/L	7/28/2020	18:39
trans-1,3-Dichloropropene	< 2.00	ug/L	7/28/2020	18:39
Trichloroethene	< 2.00	ug/L	7/28/2020	18:39
Trichlorofluoromethane	< 2.00	ug/L	7/28/2020	18:39
Vinyl chloride	< 2.00	ug/L	7/28/2020	18:39

<b>Surrogate</b>	<b>Percent Recovery</b>	<b>Limits</b>	<b>Outliers</b>	<b>Date Analyzed</b>
1,2-Dichloroethane-d4	<b>105</b>	80.8 - 132		7/28/2020 18:39
4-Bromofluorobenzene	<b>60.4</b>	56.6 - 130		7/28/2020 18:39
Pentafluorobenzene	<b>106</b>	87.4 - 113		7/28/2020 18:39
Toluene-D8	<b>83.9</b>	82.2 - 115		7/28/2020 18:39

**Method Reference(s):** EPA 8260C  
EPA 5030C

**Data File:** x72090.D

This report is part of a multipage document and should only be evaluated in its entirety. The Chain of Custody provides additional sample information, including compliance with the sample condition requirements upon receipt.



Lab Project ID: 203467

Client: Alpha Analytical

Project Reference: L2030254, C&S Companies, Jamestown Container

Sample Identifier: 30254-07 ESI-7-071520

Lab Sample ID: 203467-07

Date Sampled: 7/15/2020

Matrix: Groundwater

Date Received: 7/28/2020

**Volatile Organics**

Analyte	Result	Units	Qualifier	Date Analyzed
1,1,1-Trichloroethane	< 2.00	ug/L		7/28/2020 19:02
1,1,2,2-Tetrachloroethane	< 2.00	ug/L		7/28/2020 19:02
1,1,2-Trichloroethane	< 2.00	ug/L		7/28/2020 19:02
1,1-Dichloroethane	< 2.00	ug/L		7/28/2020 19:02
1,1-Dichloroethene	< 2.00	ug/L		7/28/2020 19:02
1,2,3-Trichlorobenzene	< 5.00 UJ	ug/L		7/28/2020 19:02
1,2,4-Trichlorobenzene	< 5.00 UJ	ug/L		7/28/2020 19:02
1,2,4-Trimethylbenzene	< 2.00	ug/L		7/28/2020 19:02
1,2-Dibromo-3-Chloropropane	< 10.0 UJ	ug/L		7/28/2020 19:02
1,2-Dibromoethane	< 2.00	ug/L		7/28/2020 19:02
1,2-Dichlorobenzene	< 2.00 UJ	ug/L		7/28/2020 19:02
1,2-Dichloroethane	< 2.00	ug/L		7/28/2020 19:02
1,2-Dichloropropane	< 2.00	ug/L		7/28/2020 19:02
1,3,5-Trimethylbenzene	< 2.00	ug/L		7/28/2020 19:02
1,3-Dichlorobenzene	< 2.00 UJ	ug/L		7/28/2020 19:02
1,4-Dichlorobenzene	< 2.00 UJ	ug/L		7/28/2020 19:02
1,4-Dioxane	<del>&lt; 2.00</del> R	ug/L		7/28/2020 19:02
2-Butanone	< 10.0	ug/L		7/28/2020 19:02
2-Hexanone	< 5.00	ug/L		7/28/2020 19:02
4-Methyl-2-pentanone	< 5.00	ug/L		7/28/2020 19:02
Acetone	< 10.0	ug/L		7/28/2020 19:02
Benzene	< 1.00	ug/L		7/28/2020 19:02
Bromochloromethane	< 5.00	ug/L		7/28/2020 19:02

This report is part of a multipage document and should only be evaluated in its entirety. The Chain of Custody provides additional sample information, including compliance with the sample condition requirements upon receipt.



Lab Project ID: 203467

Client: Alpha Analytical

Project Reference: L2030254, C&S Companies, Jamestown Container

<b>Sample Identifier:</b>	30254-07 ESI-7-071520		
<b>Lab Sample ID:</b>	203467-07	<b>Date Sampled:</b>	7/15/2020
<b>Matrix:</b>	Groundwater	<b>Date Received:</b>	7/28/2020
Bromodichloromethane	< 2.00	ug/L	7/28/2020 19:02
Bromoform	< 5.00	ug/L	7/28/2020 19:02
Bromomethane	< 2.00	ug/L	7/28/2020 19:02
Carbon disulfide	< 2.00	ug/L	7/28/2020 19:02
Carbon Tetrachloride	< 2.00	ug/L	7/28/2020 19:02
Chlorobenzene	< 2.00	ug/L	7/28/2020 19:02
Chloroethane	< 2.00	ug/L	7/28/2020 19:02
Chloroform	< 2.00	ug/L	7/28/2020 19:02
Chloromethane	< 2.00	ug/L	7/28/2020 19:02
cis-1,2-Dichloroethene	<b>5.94</b>	ug/L	7/28/2020 19:02
cis-1,3-Dichloropropene	< 2.00	ug/L	7/28/2020 19:02
Cyclohexane	< 10.0	ug/L	7/28/2020 19:02
Dibromochloromethane	< 2.00	ug/L	7/28/2020 19:02
Dichlorodifluoromethane	< 2.00	ug/L	7/28/2020 19:02
Ethylbenzene	< 2.00	ug/L	7/28/2020 19:02
Freon 113	< 2.00	ug/L	7/28/2020 19:02
Isopropylbenzene	< 2.00	ug/L	7/28/2020 19:02
m,p-Xylene	< 2.00	ug/L	7/28/2020 19:02
Methyl acetate	< 2.00	ug/L	7/28/2020 19:02
Methyl tert-butyl Ether	< 2.00	ug/L	7/28/2020 19:02
Methylcyclohexane	< 2.00	ug/L	7/28/2020 19:02
Methylene chloride	< 5.00	ug/L	7/28/2020 19:02
Naphthalene	< 5.00	ug/L	7/28/2020 19:02
n-Butylbenzene	< 2.00 UJ	ug/L	7/28/2020 19:02
n-Propylbenzene	< 2.00	ug/L	7/28/2020 19:02

This report is part of a multipage document and should only be evaluated in its entirety. The Chain of Custody provides additional sample information, including compliance with the sample condition requirements upon receipt.





Lab Project ID: 203467

**Client:** Alpha Analytical

**Project Reference:** L2030254, C&S Companies, Jamestown Container

**Sample Identifier:** 30254-07 ESI-7-071520

**Lab Sample ID:** 203467-07

**Date Sampled:** 7/15/2020

**Matrix:** Groundwater

**Date Received:** 7/28/2020

o-Xylene	< 2.00	ug/L	7/28/2020	19:02
p-Isopropyltoluene	< 2.00	ug/L	7/28/2020	19:02
sec-Butylbenzene	< 2.00	ug/L	7/28/2020	19:02
Styrene	< 5.00	ug/L	7/28/2020	19:02
tert-Butylbenzene	< 2.00	ug/L	7/28/2020	19:02
Tetrachloroethene	< 2.00	ug/L	7/28/2020	19:02
Toluene	< 2.00	ug/L	7/28/2020	19:02
trans-1,2-Dichloroethene	< 2.00	ug/L	7/28/2020	19:02
trans-1,3-Dichloropropene	< 2.00	ug/L	7/28/2020	19:02
Trichloroethene	<b>39.5</b>	ug/L	7/28/2020	19:02
Trichlorofluoromethane	< 2.00	ug/L	7/28/2020	19:02
Vinyl chloride	< 2.00	ug/L	7/28/2020	19:02

<b>Surrogate</b>	<b>Percent Recovery</b>	<b>Limits</b>	<b>Outliers</b>	<b>Date Analyzed</b>
1,2-Dichloroethane-d4	<b>113</b>	80.8 - 132		7/28/2020 19:02
4-Bromofluorobenzene	<b>60.6</b>	56.6 - 130		7/28/2020 19:02
Pentafluorobenzene	<b>102</b>	87.4 - 113		7/28/2020 19:02
Toluene-D8	<b>82.3</b>	82.2 - 115		7/28/2020 19:02

**Method Reference(s):** EPA 8260C  
EPA 5030C

**Data File:** x72091.D

This report is part of a multipage document and should only be evaluated in its entirety. The Chain of Custody provides additional sample information, including compliance with the sample condition requirements upon receipt.



Lab Project ID: 203467

Client: Alpha Analytical

Project Reference: L2030254, C&S Companies, Jamestown Container

Sample Identifier: 30254-08 PW-3R-071520

Lab Sample ID: 203467-08

Date Sampled: 7/15/2020

Matrix: Groundwater

Date Received: 7/28/2020

**Volatile Organics**

Analyte	Result	Units	Qualifier	Date Analyzed
1,1,1-Trichloroethane	< 20.0 UJ	ug/L		7/28/2020 19:24
1,1,2,2-Tetrachloroethane	< 20.0	ug/L		7/28/2020 19:24
1,1,2-Trichloroethane	< 20.0	ug/L		7/28/2020 19:24
1,1-Dichloroethane	< 20.0	ug/L		7/28/2020 19:24
1,1-Dichloroethene	< 20.0	ug/L		7/28/2020 19:24
1,2,3-Trichlorobenzene	< 50.0	ug/L		7/28/2020 19:24
1,2,4-Trichlorobenzene	< 50.0	ug/L		7/28/2020 19:24
1,2,4-Trimethylbenzene	< 20.0	ug/L		7/28/2020 19:24
1,2-Dibromo-3-Chloropropane	< 100	ug/L		7/28/2020 19:24
1,2-Dibromoethane	< 20.0	ug/L		7/28/2020 19:24
1,2-Dichlorobenzene	< 20.0	ug/L		7/28/2020 19:24
1,2-Dichloroethane	< 20.0	ug/L		7/28/2020 19:24
1,2-Dichloropropane	< 20.0	ug/L		7/28/2020 19:24
1,3,5-Trimethylbenzene	< 20.0	ug/L		7/28/2020 19:24
1,3-Dichlorobenzene	< 20.0	ug/L		7/28/2020 19:24
1,4-Dichlorobenzene	< 20.0	ug/L		7/28/2020 19:24
1,4-Dioxane	< 20.0 R	ug/L		7/28/2020 19:24
2-Butanone	< 100 UJ	ug/L		7/28/2020 19:24
2-Hexanone	< 50.0	ug/L		7/28/2020 19:24
4-Methyl-2-pentanone	< 50.0	ug/L		7/28/2020 19:24
Acetone	< 100	ug/L		7/28/2020 19:24
Benzene	< 10.0	ug/L		7/28/2020 19:24
Bromochloromethane	< 50.0	ug/L		7/28/2020 19:24

This report is part of a multipage document and should only be evaluated in its entirety. The Chain of Custody provides additional sample information, including compliance with the sample condition requirements upon receipt.



Lab Project ID: 203467

**Client:** Alpha Analytical

**Project Reference:** L2030254, C&S Companies, Jamestown Container

**Sample Identifier:** 30254-08 PW-3R-071520

**Lab Sample ID:** 203467-08

**Date Sampled:** 7/15/2020

**Matrix:** Groundwater

**Date Received:** 7/28/2020

Bromodichloromethane	< 20.0	UJ	ug/L	7/28/2020	19:24
Bromoform	< 50.0		ug/L	7/28/2020	19:24
Bromomethane	< 20.0		ug/L	7/28/2020	19:24
Carbon disulfide	< 20.0		ug/L	7/28/2020	19:24
Carbon Tetrachloride	< 20.0		ug/L	7/28/2020	19:24
Chlorobenzene	< 20.0		ug/L	7/28/2020	19:24
Chloroethane	< 20.0		ug/L	7/28/2020	19:24
Chloroform	< 20.0		ug/L	7/28/2020	19:24
Chloromethane	< 20.0		ug/L	7/28/2020	19:24
cis-1,2-Dichloroethene	<b>809</b>	J	ug/L	7/28/2020	19:24
cis-1,3-Dichloropropene	< 20.0	UJ	ug/L	7/28/2020	19:24
Cyclohexane	< 100		ug/L	7/28/2020	19:24
Dibromochloromethane	< 20.0		ug/L	7/28/2020	19:24
Dichlorodifluoromethane	< 20.0		ug/L	7/28/2020	19:24
Ethylbenzene	< 20.0		ug/L	7/28/2020	19:24
Freon 113	< 20.0		ug/L	7/28/2020	19:24
Isopropylbenzene	< 20.0		ug/L	7/28/2020	19:24
m,p-Xylene	< 20.0		ug/L	7/28/2020	19:24
Methyl acetate	< 20.0		ug/L	7/28/2020	19:24
Methyl tert-butyl Ether	< 20.0		ug/L	7/28/2020	19:24
Methylcyclohexane	< 20.0		ug/L	7/28/2020	19:24
Methylene chloride	< 50.0		ug/L	7/28/2020	19:24
Naphthalene	< 50.0		ug/L	7/28/2020	19:24
n-Butylbenzene	< 20.0		ug/L	7/28/2020	19:24
n-Propylbenzene	< 20.0		ug/L	7/28/2020	19:24

This report is part of a multipage document and should only be evaluated in its entirety. The Chain of Custody provides additional sample information, including compliance with the sample condition requirements upon receipt.



Lab Project ID: 203467

Client: Alpha Analytical

Project Reference: L2030254, C&S Companies, Jamestown Container

Sample Identifier: 30254-08 PW-3R-071520

Lab Sample ID: 203467-08

Date Sampled: 7/15/2020

Matrix: Groundwater

Date Received: 7/28/2020

o-Xylene	< 20.0	UJ	ug/L		7/28/2020	19:24
p-Isopropyltoluene	< 20.0		ug/L		7/28/2020	19:24
sec-Butylbenzene	< 20.0		ug/L		7/28/2020	19:24
Styrene	< 50.0		ug/L		7/28/2020	19:24
tert-Butylbenzene	< 20.0		ug/L		7/28/2020	19:24
Tetrachloroethene	< 20.0		ug/L		7/28/2020	19:24
Toluene	< 20.0		ug/L		7/28/2020	19:24
trans-1,2-Dichloroethene	11.4	J	ug/L	J	7/28/2020	19:24
trans-1,3-Dichloropropene	< 20.0	UJ	ug/L		7/28/2020	19:24
Trichloroethene	75.2	J	ug/L		7/28/2020	19:24
Trichlorofluoromethane	< 20.0	UJ	ug/L		7/28/2020	19:24
Vinyl chloride	1440	J	ug/L		7/28/2020	19:24

Surrogate	Percent Recovery	Limits	Outliers	Date Analyzed
1,2-Dichloroethane-d4	110	80.8 - 132		7/28/2020 19:24
4-Bromofluorobenzene	59.6	56.6 - 130		7/28/2020 19:24
Pentafluorobenzene	103	87.4 - 113		7/28/2020 19:24
Toluene-D8	79.6	82.2 - 115	*	7/28/2020 19:24

Method Reference(s): EPA 8260C  
EPA 5030C  
Data File: x72092.D

MKP 11/20/2020

This report is part of a multipage document and should only be evaluated in its entirety. The Chain of Custody provides additional sample information, including compliance with the sample condition requirements upon receipt.



Lab Project ID: 203467

Client: Alpha Analytical

Project Reference: L2030254, C&S Companies, Jamestown Container

Sample Identifier: 30254-09 DUP-PW-3R-071520

Lab Sample ID: 203467-09

Date Sampled: 7/15/2020

Matrix: Groundwater

Date Received: 7/28/2020

**Volatile Organics**

Analyte	Result	Units	Qualifier	Date Analyzed
1,1,1-Trichloroethane	< 20.0	ug/L		7/29/2020 14:13
1,1,2,2-Tetrachloroethane	< 20.0	ug/L		7/29/2020 14:13
1,1,2-Trichloroethane	< 20.0	ug/L		7/29/2020 14:13
1,1-Dichloroethane	< 20.0	ug/L		7/29/2020 14:13
1,1-Dichloroethene	< 20.0	ug/L		7/29/2020 14:13
1,2,3-Trichlorobenzene	< 50.0	ug/L		7/29/2020 14:13
1,2,4-Trichlorobenzene	< 50.0	ug/L		7/29/2020 14:13
1,2,4-Trimethylbenzene	< 20.0	ug/L		7/29/2020 14:13
1,2-Dibromo-3-Chloropropane	< 100 UJ	ug/L		7/29/2020 14:13
1,2-Dibromoethane	< 20.0	ug/L		7/29/2020 14:13
1,2-Dichlorobenzene	< 20.0 UJ	ug/L		7/29/2020 14:13
1,2-Dichloroethane	< 20.0	ug/L		7/29/2020 14:13
1,2-Dichloropropane	< 20.0	ug/L		7/29/2020 14:13
1,3,5-Trimethylbenzene	< 20.0	ug/L		7/29/2020 14:13
1,3-Dichlorobenzene	< 20.0 UJ	ug/L		7/29/2020 14:13
1,4-Dichlorobenzene	< 20.0 UJ	ug/L		7/29/2020 14:13
1,4-Dioxane	< <del>20.0</del> R	ug/L		7/29/2020 14:13
2-Butanone	< 100	ug/L		7/29/2020 14:13
2-Hexanone	< 50.0	ug/L		7/29/2020 14:13
4-Methyl-2-pentanone	< 50.0	ug/L		7/29/2020 14:13
Acetone	< 100	ug/L		7/29/2020 14:13
Benzene	< 10.0	ug/L		7/29/2020 14:13
Bromochloromethane	< 50.0	ug/L		7/29/2020 14:13

This report is part of a multipage document and should only be evaluated in its entirety. The Chain of Custody provides additional sample information, including compliance with the sample condition requirements upon receipt.



Lab Project ID: 203467

Client: Alpha Analytical

Project Reference: L2030254, C&S Companies, Jamestown Container

<b>Sample Identifier:</b>	30254-09 DUP-PW-3R-071520		
<b>Lab Sample ID:</b>	203467-09	<b>Date Sampled:</b>	7/15/2020
<b>Matrix:</b>	Groundwater	<b>Date Received:</b>	7/28/2020
Bromodichloromethane	< 20.0	ug/L	7/29/2020 14:13
Bromoform	< 50.0	ug/L	7/29/2020 14:13
Bromomethane	< 20.0	ug/L	7/29/2020 14:13
Carbon disulfide	< 20.0	ug/L	7/29/2020 14:13
Carbon Tetrachloride	< 20.0	ug/L	7/29/2020 14:13
Chlorobenzene	< 20.0	ug/L	7/29/2020 14:13
Chloroethane	< 20.0	ug/L	7/29/2020 14:13
Chloroform	< 20.0	ug/L	7/29/2020 14:13
Chloromethane	< 20.0	ug/L	7/29/2020 14:13
cis-1,2-Dichloroethene	<b>1000</b>	ug/L	7/29/2020 14:13
cis-1,3-Dichloropropene	< 20.0	ug/L	7/29/2020 14:13
Cyclohexane	< 100	ug/L	7/29/2020 14:13
Dibromochloromethane	< 20.0	ug/L	7/29/2020 14:13
Dichlorodifluoromethane	< 20.0	ug/L	7/29/2020 14:13
Ethylbenzene	< 20.0	ug/L	7/29/2020 14:13
Freon 113	< 20.0	ug/L	7/29/2020 14:13
Isopropylbenzene	< 20.0	ug/L	7/29/2020 14:13
m,p-Xylene	< 20.0	ug/L	7/29/2020 14:13
Methyl acetate	< 20.0	ug/L	7/29/2020 14:13
Methyl tert-butyl Ether	< 20.0	ug/L	7/29/2020 14:13
Methylcyclohexane	< 20.0	ug/L	7/29/2020 14:13
Methylene chloride	< 50.0	ug/L	7/29/2020 14:13
Naphthalene	< 50.0	ug/L	7/29/2020 14:13
n-Butylbenzene	< 20.0 UJ	ug/L	7/29/2020 14:13
n-Propylbenzene	< 20.0	ug/L	7/29/2020 14:13

This report is part of a multipage document and should only be evaluated in its entirety. The Chain of Custody provides additional sample information, including compliance with the sample condition requirements upon receipt.



Lab Project ID: 203467

**Client:** Alpha Analytical

**Project Reference:** L2030254, C&S Companies, Jamestown Container

**Sample Identifier:** 30254-09 DUP-PW-3R-071520

**Lab Sample ID:** 203467-09

**Date Sampled:** 7/15/2020

**Matrix:** Groundwater

**Date Received:** 7/28/2020

o-Xylene	< 20.0	ug/L		7/29/2020 14:13
p-Isopropyltoluene	< 20.0	ug/L		7/29/2020 14:13
sec-Butylbenzene	< 20.0	ug/L		7/29/2020 14:13
Styrene	< 50.0	ug/L		7/29/2020 14:13
tert-Butylbenzene	< 20.0	ug/L		7/29/2020 14:13
Tetrachloroethene	< 20.0	ug/L		7/29/2020 14:13
Toluene	< 20.0	ug/L		7/29/2020 14:13
trans-1,2-Dichloroethene	<b>13.8</b>	ug/L	J	7/29/2020 14:13
trans-1,3-Dichloropropene	< 20.0	ug/L		7/29/2020 14:13
Trichloroethene	<b>92.9</b>	ug/L		7/29/2020 14:13
Trichlorofluoromethane	< 20.0	ug/L		7/29/2020 14:13
Vinyl chloride	<b>1720</b>	ug/L		7/29/2020 14:13

<b>Surrogate</b>	<b>Percent Recovery</b>	<b>Limits</b>	<b>Outliers</b>	<b>Date Analyzed</b>
1,2-Dichloroethane-d4	<b>104</b>	80.8 - 132		7/29/2020 14:13
4-Bromofluorobenzene	<b>61.9</b>	56.6 - 130		7/29/2020 14:13
Pentafluorobenzene	<b>103</b>	87.4 - 113		7/29/2020 14:13
Toluene-D8	<b>84.3</b>	82.2 - 115		7/29/2020 14:13

**Method Reference(s):** EPA 8260C  
EPA 5030C

**Data File:** x72115.D

This report is part of a multipage document and should only be evaluated in its entirety. The Chain of Custody provides additional sample information, including compliance with the sample condition requirements upon receipt.



Lab Project ID: 203467

Client: Alpha Analytical

Project Reference: L2030254, C&S Companies, Jamestown Container

Sample Identifier: 30254-10 ESI-2-071520

Lab Sample ID: 203467-10

Date Sampled: 7/15/2020

Matrix: Groundwater

Date Received: 7/28/2020

**Volatile Organics**

Analyte	Result	Units	Qualifier	Date Analyzed
1,1,1-Trichloroethane	< 40.0	ug/L		7/29/2020 13:50
1,1,2,2-Tetrachloroethane	< 40.0	ug/L		7/29/2020 13:50
1,1,2-Trichloroethane	< 40.0	ug/L		7/29/2020 13:50
1,1-Dichloroethane	< 40.0	ug/L		7/29/2020 13:50
1,1-Dichloroethene	< 40.0	ug/L		7/29/2020 13:50
1,2,3-Trichlorobenzene	< 100	ug/L		7/29/2020 13:50
1,2,4-Trichlorobenzene	< 100	ug/L		7/29/2020 13:50
1,2,4-Trimethylbenzene	< 40.0	ug/L		7/29/2020 13:50
1,2-Dibromo-3-Chloropropane	< 200 UJ	ug/L		7/29/2020 13:50
1,2-Dibromoethane	< 40.0	ug/L		7/29/2020 13:50
1,2-Dichlorobenzene	< 40.0 UJ	ug/L		7/29/2020 13:50
1,2-Dichloroethane	< 40.0	ug/L		7/29/2020 13:50
1,2-Dichloropropane	< 40.0	ug/L		7/29/2020 13:50
1,3,5-Trimethylbenzene	< 40.0	ug/L		7/29/2020 13:50
1,3-Dichlorobenzene	< 40.0 UJ	ug/L		7/29/2020 13:50
1,4-Dichlorobenzene	< 40.0 UJ	ug/L		7/29/2020 13:50
1,4-Dioxane	<del>&lt; 40.0</del> R	ug/L		7/29/2020 13:50
2-Butanone	< 200	ug/L		7/29/2020 13:50
2-Hexanone	< 100	ug/L		7/29/2020 13:50
4-Methyl-2-pentanone	< 100	ug/L		7/29/2020 13:50
Acetone	< 200	ug/L		7/29/2020 13:50
Benzene	< 20.0	ug/L		7/29/2020 13:50
Bromochloromethane	< 100	ug/L		7/29/2020 13:50

This report is part of a multipage document and should only be evaluated in its entirety. The Chain of Custody provides additional sample information, including compliance with the sample condition requirements upon receipt.





Lab Project ID: 203467

Client: Alpha Analytical

Project Reference: L2030254, C&S Companies, Jamestown Container

<b>Sample Identifier:</b>	30254-10 ESI-2-071520		
<b>Lab Sample ID:</b>	203467-10	<b>Date Sampled:</b>	7/15/2020
<b>Matrix:</b>	Groundwater	<b>Date Received:</b>	7/28/2020
Bromodichloromethane	< 40.0	ug/L	7/29/2020 13:50
Bromoform	< 100	ug/L	7/29/2020 13:50
Bromomethane	< 40.0	ug/L	7/29/2020 13:50
Carbon disulfide	< 40.0	ug/L	7/29/2020 13:50
Carbon Tetrachloride	< 40.0	ug/L	7/29/2020 13:50
Chlorobenzene	< 40.0	ug/L	7/29/2020 13:50
Chloroethane	< 40.0	ug/L	7/29/2020 13:50
Chloroform	< 40.0	ug/L	7/29/2020 13:50
Chloromethane	< 40.0	ug/L	7/29/2020 13:50
cis-1,2-Dichloroethene	<b>1910</b>	ug/L	7/29/2020 13:50
cis-1,3-Dichloropropene	< 40.0	ug/L	7/29/2020 13:50
Cyclohexane	< 200	ug/L	7/29/2020 13:50
Dibromochloromethane	< 40.0	ug/L	7/29/2020 13:50
Dichlorodifluoromethane	< 40.0	ug/L	7/29/2020 13:50
Ethylbenzene	< 40.0	ug/L	7/29/2020 13:50
Freon 113	< 40.0	ug/L	7/29/2020 13:50
Isopropylbenzene	< 40.0	ug/L	7/29/2020 13:50
m,p-Xylene	< 40.0	ug/L	7/29/2020 13:50
Methyl acetate	< 40.0	ug/L	7/29/2020 13:50
Methyl tert-butyl Ether	< 40.0	ug/L	7/29/2020 13:50
Methylcyclohexane	< 40.0	ug/L	7/29/2020 13:50
Methylene chloride	< 100	ug/L	7/29/2020 13:50
Naphthalene	< 100	ug/L	7/29/2020 13:50
n-Butylbenzene	< 40.0 UJ	ug/L	7/29/2020 13:50
n-Propylbenzene	< 40.0	ug/L	7/29/2020 13:50

This report is part of a multipage document and should only be evaluated in its entirety. The Chain of Custody provides additional sample information, including compliance with the sample condition requirements upon receipt.



Lab Project ID: 203467

Client: Alpha Analytical

Project Reference: L2030254, C&S Companies, Jamestown Container

<b>Sample Identifier:</b>	30254-10 ESI-2-071520		
<b>Lab Sample ID:</b>	203467-10	<b>Date Sampled:</b>	7/15/2020
<b>Matrix:</b>	Groundwater	<b>Date Received:</b>	7/28/2020

o-Xylene	< 40.0	ug/L	7/29/2020	13:50
p-Isopropyltoluene	< 40.0	ug/L	7/29/2020	13:50
sec-Butylbenzene	< 40.0	ug/L	7/29/2020	13:50
Styrene	< 100	ug/L	7/29/2020	13:50
tert-Butylbenzene	< 40.0	ug/L	7/29/2020	13:50
Tetrachloroethene	< 40.0	ug/L	7/29/2020	13:50
Toluene	< 40.0	ug/L	7/29/2020	13:50
trans-1,2-Dichloroethene	< 40.0	ug/L	7/29/2020	13:50
trans-1,3-Dichloropropene	< 40.0	ug/L	7/29/2020	13:50
Trichloroethene	<b>708</b>	ug/L	7/29/2020	13:50
Trichlorofluoromethane	< 40.0	ug/L	7/29/2020	13:50
Vinyl chloride	<b>20.3</b>	ug/L	J	7/29/2020 13:50

<b>Surrogate</b>	<b>Percent Recovery</b>	<b>Limits</b>	<b>Outliers</b>	<b>Date Analyzed</b>
1,2-Dichloroethane-d4	<b>99.6</b>	80.8 - 132		7/29/2020 13:50
4-Bromofluorobenzene	<b>65.4</b>	56.6 - 130		7/29/2020 13:50
Pentafluorobenzene	<b>107</b>	87.4 - 113		7/29/2020 13:50
Toluene-D8	<b>87.1</b>	82.2 - 115		7/29/2020 13:50

**Method Reference(s):** EPA 8260C  
EPA 5030C  
**Data File:** x72114.D

This report is part of a multipage document and should only be evaluated in its entirety. The Chain of Custody provides additional sample information, including compliance with the sample condition requirements upon receipt.



Lab Project ID: 203467

Client: Alpha Analytical

Project Reference: L2030254, C&S Companies, Jamestown Container

Sample Identifier: 30254-11 ESI-10-071520

Lab Sample ID: 203467-11

Date Sampled: 7/15/2020

Matrix: Groundwater

Date Received: 7/28/2020

**Volatile Organics**

Analyte	Result	Units	Qualifier	Date Analyzed
1,1,1-Trichloroethane	< 2.00 UJ	ug/L		7/28/2020 20:31
1,1,2,2-Tetrachloroethane	< 2.00	ug/L		7/28/2020 20:31
1,1,2-Trichloroethane	< 2.00	ug/L		7/28/2020 20:31
1,1-Dichloroethane	< 2.00	ug/L		7/28/2020 20:31
1,1-Dichloroethene	< 2.00	ug/L		7/28/2020 20:31
1,2,3-Trichlorobenzene	< 5.00	ug/L		7/28/2020 20:31
1,2,4-Trichlorobenzene	< 5.00	ug/L		7/28/2020 20:31
1,2,4-Trimethylbenzene	< 2.00	ug/L		7/28/2020 20:31
1,2-Dibromo-3-Chloropropane	< 10.0	ug/L		7/28/2020 20:31
1,2-Dibromoethane	< 2.00	ug/L		7/28/2020 20:31
1,2-Dichlorobenzene	< 2.00	ug/L		7/28/2020 20:31
1,2-Dichloroethane	< 2.00	ug/L		7/28/2020 20:31
1,2-Dichloropropane	< 2.00	ug/L		7/28/2020 20:31
1,3,5-Trimethylbenzene	< 2.00	ug/L		7/28/2020 20:31
1,3-Dichlorobenzene	< 2.00	ug/L		7/28/2020 20:31
1,4-Dichlorobenzene	< 2.00	ug/L		7/28/2020 20:31
1,4-Dioxane	<del>&lt; 20.0</del> R	ug/L		7/28/2020 20:31
2-Butanone	< 10.0 UJ	ug/L		7/28/2020 20:31
2-Hexanone	< 5.00	ug/L		7/28/2020 20:31
4-Methyl-2-pentanone	< 5.00	ug/L		7/28/2020 20:31
Acetone	15.0 J	ug/L		7/28/2020 20:31
Benzene	< 1.00 UJ	ug/L		7/28/2020 20:31
Bromochloromethane	< 5.00 UJ	ug/L		7/28/2020 20:31

This report is part of a multipage document and should only be evaluated in its entirety. The Chain of Custody provides additional sample information, including compliance with the sample condition requirements upon receipt.



Lab Project ID: 203467

Client: Alpha Analytical

Project Reference: L2030254, C&S Companies, Jamestown Container

Sample Identifier: 30254-11 ESI-10-071520

Lab Sample ID: 203467-11

Date Sampled: 7/15/2020

Matrix: Groundwater

Date Received: 7/28/2020

Bromodichloromethane	< 2.00	UJ	ug/L	7/28/2020	20:31
Bromoform	< 5.00		ug/L	7/28/2020	20:31
Bromomethane	< 2.00		ug/L	7/28/2020	20:31
Carbon disulfide	< 2.00		ug/L	7/28/2020	20:31
Carbon Tetrachloride	< 2.00		ug/L	7/28/2020	20:31
Chlorobenzene	< 2.00		ug/L	7/28/2020	20:31
Chloroethane	< 2.00		ug/L	7/28/2020	20:31
Chloroform	< 2.00		ug/L	7/28/2020	20:31
Chloromethane	< 2.00		ug/L	7/28/2020	20:31
cis-1,2-Dichloroethene	< 2.00		ug/L	7/28/2020	20:31
cis-1,3-Dichloropropene	< 2.00		ug/L	7/28/2020	20:31
Cyclohexane	< 10.0		ug/L	7/28/2020	20:31
Dibromochloromethane	< 2.00		ug/L	7/28/2020	20:31
Dichlorodifluoromethane	< 2.00		ug/L	7/28/2020	20:31
Ethylbenzene	< 2.00		ug/L	7/28/2020	20:31
Freon 113	< 2.00		ug/L	7/28/2020	20:31
Isopropylbenzene	< 2.00		ug/L	7/28/2020	20:31
m,p-Xylene	< 2.00		ug/L	7/28/2020	20:31
Methyl acetate	< 2.00		ug/L	7/28/2020	20:31
Methyl tert-butyl Ether	< 2.00		ug/L	7/28/2020	20:31
Methylcyclohexane	< 2.00		ug/L	7/28/2020	20:31
Methylene chloride	< 5.00		ug/L	7/28/2020	20:31
Naphthalene	< 5.00		ug/L	7/28/2020	20:31
n-Butylbenzene	< 2.00		ug/L	7/28/2020	20:31
n-Propylbenzene	< 2.00		ug/L	7/28/2020	20:31

This report is part of a multipage document and should only be evaluated in its entirety. The Chain of Custody provides additional sample information, including compliance with the sample condition requirements upon receipt.



Lab Project ID: 203467

Client: Alpha Analytical

Project Reference: L2030254, C&S Companies, Jamestown Container

Sample Identifier: 30254-11 ESI-10-071520

Lab Sample ID: 203467-11

Date Sampled: 7/15/2020

Matrix: Groundwater

Date Received: 7/28/2020

o-Xylene	< 2.00	UU	ug/L	7/28/2020	20:31
p-Isopropyltoluene	< 2.00		ug/L	7/28/2020	20:31
sec-Butylbenzene	< 2.00		ug/L	7/28/2020	20:31
Styrene	< 5.00		ug/L	7/28/2020	20:31
tert-Butylbenzene	< 2.00		ug/L	7/28/2020	20:31
Tetrachloroethene	< 2.00		ug/L	7/28/2020	20:31
Toluene	< 2.00		ug/L	7/28/2020	20:31
trans-1,2-Dichloroethene	< 2.00		ug/L	7/28/2020	20:31
trans-1,3-Dichloropropene	< 2.00		ug/L	7/28/2020	20:31
Trichloroethene	< 2.00		ug/L	7/28/2020	20:31
Trichlorofluoromethane	< 2.00		ug/L	7/28/2020	20:31
Vinyl chloride	< 2.00		ug/L	7/28/2020	20:31

Surrogate	Percent Recovery	Limits	Outliers	Date Analyzed
1,2-Dichloroethane-d4	115	80.8 - 132		7/28/2020 20:31
4-Bromofluorobenzene	62.6	56.6 - 130		7/28/2020 20:31
Pentafluorobenzene	100	87.4 - 113		7/28/2020 20:31
Toluene-D8	82.0	82.2 - 115	*	7/28/2020 20:31

Method Reference(s): EPA 8260C  
EPA 5030C  
Data File: x72095.D

MKP 11/20/2020

This report is part of a multipage document and should only be evaluated in its entirety. The Chain of Custody provides additional sample information, including compliance with the sample condition requirements upon receipt.



Lab Project ID: 203467

Client: Alpha Analytical

Project Reference: L2030254, C&S Companies, Jamestown Container

Sample Identifier: 30254-12 ESI-11-071520

Lab Sample ID: 203467-12

Date Sampled: 7/15/2020

Matrix: Groundwater

Date Received: 7/28/2020

**Volatile Organics**

Analyte	Result	Units	Qualifier	Date Analyzed
1,1,1-Trichloroethane	< 2.00	ug/L		7/28/2020 20:53
1,1,2,2-Tetrachloroethane	< 2.00	ug/L		7/28/2020 20:53
1,1,2-Trichloroethane	< 2.00	ug/L		7/28/2020 20:53
1,1-Dichloroethane	< 2.00	ug/L		7/28/2020 20:53
1,1-Dichloroethene	< 2.00	ug/L		7/28/2020 20:53
1,2,3-Trichlorobenzene	< 5.00 UJ	ug/L		7/28/2020 20:53
1,2,4-Trichlorobenzene	< 5.00 UJ	ug/L		7/28/2020 20:53
1,2,4-Trimethylbenzene	< 2.00	ug/L		7/28/2020 20:53
1,2-Dibromo-3-Chloropropane	< 10.0 UJ	ug/L		7/28/2020 20:53
1,2-Dibromoethane	< 2.00	ug/L		7/28/2020 20:53
1,2-Dichlorobenzene	< 2.00 UJ	ug/L		7/28/2020 20:53
1,2-Dichloroethane	< 2.00	ug/L		7/28/2020 20:53
1,2-Dichloropropane	< 2.00	ug/L		7/28/2020 20:53
1,3,5-Trimethylbenzene	< 2.00	ug/L		7/28/2020 20:53
1,3-Dichlorobenzene	< 2.00 UJ	ug/L		7/28/2020 20:53
1,4-Dichlorobenzene	< 2.00 UJ	ug/L		7/28/2020 20:53
1,4-Dioxane	<del>&lt; 2.00</del> R	ug/L		7/28/2020 20:53
2-Butanone	< 10.0	ug/L		7/28/2020 20:53
2-Hexanone	< 5.00	ug/L		7/28/2020 20:53
4-Methyl-2-pentanone	< 5.00	ug/L		7/28/2020 20:53
Acetone	5.64	ug/L	J	7/28/2020 20:53
Benzene	< 1.00	ug/L		7/28/2020 20:53
Bromochloromethane	< 5.00	ug/L		7/28/2020 20:53

This report is part of a multipage document and should only be evaluated in its entirety. The Chain of Custody provides additional sample information, including compliance with the sample condition requirements upon receipt.



Lab Project ID: 203467

**Client:** Alpha Analytical

**Project Reference:** L2030254, C&S Companies, Jamestown Container

**Sample Identifier:** 30254-12 ESI-11-071520

**Lab Sample ID:** 203467-12

**Date Sampled:** 7/15/2020

**Matrix:** Groundwater

**Date Received:** 7/28/2020

Bromodichloromethane	< 2.00	ug/L	7/28/2020 20:53
Bromoform	<b>8.77</b>	ug/L	7/28/2020 20:53
Bromomethane	< 2.00	ug/L	7/28/2020 20:53
Carbon disulfide	< 2.00	ug/L	7/28/2020 20:53
Carbon Tetrachloride	< 2.00	ug/L	7/28/2020 20:53
Chlorobenzene	< 2.00	ug/L	7/28/2020 20:53
Chloroethane	< 2.00	ug/L	7/28/2020 20:53
Chloroform	< 2.00	ug/L	7/28/2020 20:53
Chloromethane	< 2.00	ug/L	7/28/2020 20:53
cis-1,2-Dichloroethene	< 2.00	ug/L	7/28/2020 20:53
cis-1,3-Dichloropropene	< 2.00	ug/L	7/28/2020 20:53
Cyclohexane	< 10.0	ug/L	7/28/2020 20:53
Dibromochloromethane	< 2.00	ug/L	7/28/2020 20:53
Dichlorodifluoromethane	< 2.00	ug/L	7/28/2020 20:53
Ethylbenzene	< 2.00	ug/L	7/28/2020 20:53
Freon 113	< 2.00	ug/L	7/28/2020 20:53
Isopropylbenzene	< 2.00	ug/L	7/28/2020 20:53
m,p-Xylene	< 2.00	ug/L	7/28/2020 20:53
Methyl acetate	< 2.00	ug/L	7/28/2020 20:53
Methyl tert-butyl Ether	< 2.00	ug/L	7/28/2020 20:53
Methylcyclohexane	< 2.00	ug/L	7/28/2020 20:53
Methylene chloride	< 5.00	ug/L	7/28/2020 20:53
Naphthalene	< 5.00	ug/L	7/28/2020 20:53
n-Butylbenzene	< 2.00 <b>UJ</b>	ug/L	7/28/2020 20:53
n-Propylbenzene	< 2.00	ug/L	7/28/2020 20:53

This report is part of a multipage document and should only be evaluated in its entirety. The Chain of Custody provides additional sample information, including compliance with the sample condition requirements upon receipt.



Lab Project ID: 203467

**Client:** Alpha Analytical

**Project Reference:** L2030254, C&S Companies, Jamestown Container

**Sample Identifier:** 30254-12 ESI-11-071520

**Lab Sample ID:** 203467-12

**Date Sampled:** 7/15/2020

**Matrix:** Groundwater

**Date Received:** 7/28/2020

o-Xylene	< 2.00	ug/L	7/28/2020	20:53
p-Isopropyltoluene	< 2.00	ug/L	7/28/2020	20:53
sec-Butylbenzene	< 2.00	ug/L	7/28/2020	20:53
Styrene	< 5.00	ug/L	7/28/2020	20:53
tert-Butylbenzene	< 2.00	ug/L	7/28/2020	20:53
Tetrachloroethene	< 2.00	ug/L	7/28/2020	20:53
Toluene	< 2.00	ug/L	7/28/2020	20:53
trans-1,2-Dichloroethene	< 2.00	ug/L	7/28/2020	20:53
trans-1,3-Dichloropropene	< 2.00	ug/L	7/28/2020	20:53
Trichloroethene	< 2.00	ug/L	7/28/2020	20:53
Trichlorofluoromethane	< 2.00	ug/L	7/28/2020	20:53
Vinyl chloride	< 2.00	ug/L	7/28/2020	20:53

<b>Surrogate</b>	<b>Percent Recovery</b>	<b>Limits</b>	<b>Outliers</b>	<b>Date Analyzed</b>
1,2-Dichloroethane-d4	<b>121</b>	80.8 - 132		7/28/2020 20:53
4-Bromofluorobenzene	<b>66.8</b>	56.6 - 130		7/28/2020 20:53
Pentafluorobenzene	<b>104</b>	87.4 - 113		7/28/2020 20:53
Toluene-D8	<b>82.2</b>	82.2 - 115		7/28/2020 20:53

**Method Reference(s):** EPA 8260C  
EPA 5030C

**Data File:** x72096.D

This report is part of a multipage document and should only be evaluated in its entirety. The Chain of Custody provides additional sample information, including compliance with the sample condition requirements upon receipt.





Lab Project ID: 203467

Client: Alpha Analytical

Project Reference: L2030254, C&S Companies, Jamestown Container

Sample Identifier: 30254-13 ESI-12-071520

Lab Sample ID: 203467-13

Date Sampled: 7/15/2020

Matrix: Groundwater

Date Received: 7/28/2020

**Volatile Organics**

Analyte	Result	Units	Qualifier	Date Analyzed
1,1,1-Trichloroethane	< 2.00 UJ	ug/L		7/28/2020 21:15
1,1,2,2-Tetrachloroethane	< 2.00	ug/L		7/28/2020 21:15
1,1,2-Trichloroethane	< 2.00	ug/L		7/28/2020 21:15
1,1-Dichloroethane	< 2.00	ug/L		7/28/2020 21:15
1,1-Dichloroethene	< 2.00	ug/L		7/28/2020 21:15
1,2,3-Trichlorobenzene	< 5.00	ug/L		7/28/2020 21:15
1,2,4-Trichlorobenzene	< 5.00	ug/L		7/28/2020 21:15
1,2,4-Trimethylbenzene	< 2.00	ug/L		7/28/2020 21:15
1,2-Dibromo-3-Chloropropane	< 10.0	ug/L		7/28/2020 21:15
1,2-Dibromoethane	< 2.00	ug/L		7/28/2020 21:15
1,2-Dichlorobenzene	< 2.00	ug/L		7/28/2020 21:15
1,2-Dichloroethane	< 2.00	ug/L		7/28/2020 21:15
1,2-Dichloropropane	< 2.00	ug/L		7/28/2020 21:15
1,3,5-Trimethylbenzene	< 2.00	ug/L		7/28/2020 21:15
1,3-Dichlorobenzene	< 2.00	ug/L		7/28/2020 21:15
1,4-Dichlorobenzene	< 2.00	ug/L		7/28/2020 21:15
1,4-Dioxane	<del>&lt; 20.0</del> R	ug/L		7/28/2020 21:15
2-Butanone	< 10.0 UJ	ug/L		7/28/2020 21:15
2-Hexanone	< 5.00	ug/L		7/28/2020 21:15
4-Methyl-2-pentanone	< 5.00	ug/L		7/28/2020 21:15
Acetone	< 10.0	ug/L		7/28/2020 21:15
Benzene	1.19 J	ug/L		7/28/2020 21:15
Bromochloromethane	< 5.00 UJ	ug/L		7/28/2020 21:15

This report is part of a multipage document and should only be evaluated in its entirety. The Chain of Custody provides additional sample information, including compliance with the sample condition requirements upon receipt.



Lab Project ID: 203467

**Client:** Alpha Analytical

**Project Reference:** L2030254, C&S Companies, Jamestown Container

**Sample Identifier:** 30254-13 ESI-12-071520

**Lab Sample ID:** 203467-13

**Date Sampled:** 7/15/2020

**Matrix:** Groundwater

**Date Received:** 7/28/2020

Bromodichloromethane	< 2.00	UJ	ug/L	7/28/2020	21:15
Bromoform	6.67	J	ug/L	7/28/2020	21:15
Bromomethane	< 2.00	UJ	ug/L	7/28/2020	21:15
Carbon disulfide	< 2.00		ug/L	7/28/2020	21:15
Carbon Tetrachloride	< 2.00		ug/L	7/28/2020	21:15
Chlorobenzene	< 2.00		ug/L	7/28/2020	21:15
Chloroethane	< 2.00		ug/L	7/28/2020	21:15
Chloroform	< 2.00		ug/L	7/28/2020	21:15
Chloromethane	< 2.00		ug/L	7/28/2020	21:15
cis-1,2-Dichloroethene	< 2.00		ug/L	7/28/2020	21:15
cis-1,3-Dichloropropene	< 2.00		ug/L	7/28/2020	21:15
Cyclohexane	< 10.0		ug/L	7/28/2020	21:15
Dibromochloromethane	< 2.00		ug/L	7/28/2020	21:15
Dichlorodifluoromethane	< 2.00		ug/L	7/28/2020	21:15
Ethylbenzene	< 2.00		ug/L	7/28/2020	21:15
Freon 113	< 2.00		ug/L	7/28/2020	21:15
Isopropylbenzene	< 2.00		ug/L	7/28/2020	21:15
m,p-Xylene	< 2.00		ug/L	7/28/2020	21:15
Methyl acetate	< 2.00		ug/L	7/28/2020	21:15
Methyl tert-butyl Ether	< 2.00		ug/L	7/28/2020	21:15
Methylcyclohexane	< 2.00		ug/L	7/28/2020	21:15
Methylene chloride	< 5.00		ug/L	7/28/2020	21:15
Naphthalene	< 5.00		ug/L	7/28/2020	21:15
n-Butylbenzene	< 2.00		ug/L	7/28/2020	21:15
n-Propylbenzene	< 2.00		ug/L	7/28/2020	21:15

This report is part of a multipage document and should only be evaluated in its entirety. The Chain of Custody provides additional sample information, including compliance with the sample condition requirements upon receipt.



Lab Project ID: 203467

Client: Alpha Analytical

Project Reference: L2030254, C&S Companies, Jamestown Container

Sample Identifier: 30254-13 ESI-12-071520

Lab Sample ID: 203467-13

Date Sampled: 7/15/2020

Matrix: Groundwater

Date Received: 7/28/2020

o-Xylene	< 2.00	UJ	ug/L	7/28/2020	21:15
p-Isopropyltoluene	< 2.00		ug/L	7/28/2020	21:15
sec-Butylbenzene	< 2.00		ug/L	7/28/2020	21:15
Styrene	< 5.00		ug/L	7/28/2020	21:15
tert-Butylbenzene	< 2.00		ug/L	7/28/2020	21:15
Tetrachloroethene	< 2.00		ug/L	7/28/2020	21:15
Toluene	< 2.00		ug/L	7/28/2020	21:15
trans-1,2-Dichloroethene	< 2.00		ug/L	7/28/2020	21:15
trans-1,3-Dichloropropene	< 2.00		ug/L	7/28/2020	21:15
Trichloroethene	< 2.00		ug/L	7/28/2020	21:15
Trichlorofluoromethane	< 2.00		ug/L	7/28/2020	21:15
Vinyl chloride	< 2.00		ug/L	7/28/2020	21:15

Surrogate	Percent Recovery	Limits	Outliers	Date Analyzed
1,2-Dichloroethane-d4	121	80.8 - 132		7/28/2020 21:15
4-Bromofluorobenzene	64.0	56.6 - 130		7/28/2020 21:15
Pentafluorobenzene	104	87.4 - 113		7/28/2020 21:15
Toluene-D8	79.9	82.2 - 115	*	7/28/2020 21:15

Method Reference(s): EPA 8260C  
EPA 5030C  
Data File: x72097.D

MKP 11/20/2020

This report is part of a multipage document and should only be evaluated in its entirety. The Chain of Custody provides additional sample information, including compliance with the sample condition requirements upon receipt.



Lab Project ID: 203467

Client: Alpha Analytical

Project Reference: L2030254, C&S Companies, Jamestown Container

Sample Identifier: 30254-14 Equipment Blank

Lab Sample ID: 203467-14

Date Sampled: 7/15/2020

Matrix: Groundwater

Date Received: 7/28/2020

**Volatile Organics**

Analyte	Result	Units	Qualifier	Date Analyzed
1,1,1-Trichloroethane	< 2.00	ug/L		7/28/2020 16:48
1,1,2,2-Tetrachloroethane	< 2.00	ug/L		7/28/2020 16:48
1,1,2-Trichloroethane	< 2.00	ug/L		7/28/2020 16:48
1,1-Dichloroethane	< 2.00	ug/L		7/28/2020 16:48
1,1-Dichloroethene	< 2.00	ug/L		7/28/2020 16:48
1,2,3-Trichlorobenzene	< 5.00 UJ	ug/L		7/28/2020 16:48
1,2,4-Trichlorobenzene	< 5.00 UJ	ug/L		7/28/2020 16:48
1,2,4-Trimethylbenzene	< 2.00	ug/L		7/28/2020 16:48
1,2-Dibromo-3-Chloropropane	< 10.0 UJ	ug/L		7/28/2020 16:48
1,2-Dibromoethane	< 2.00	ug/L		7/28/2020 16:48
1,2-Dichlorobenzene	< 2.00 UJ	ug/L		7/28/2020 16:48
1,2-Dichloroethane	< 2.00	ug/L		7/28/2020 16:48
1,2-Dichloropropane	< 2.00	ug/L		7/28/2020 16:48
1,3,5-Trimethylbenzene	< 2.00	ug/L		7/28/2020 16:48
1,3-Dichlorobenzene	< 2.00 UJ	ug/L		7/28/2020 16:48
1,4-Dichlorobenzene	< 2.00 UJ	ug/L		7/28/2020 16:48
1,4-Dioxane	< <del>20.0</del> R	ug/L		7/28/2020 16:48
2-Butanone	< 10.0	ug/L		7/28/2020 16:48
2-Hexanone	< 5.00	ug/L		7/28/2020 16:48
4-Methyl-2-pentanone	< 5.00	ug/L		7/28/2020 16:48
Acetone	< 10.0	ug/L		7/28/2020 16:48
Benzene	< 1.00	ug/L		7/28/2020 16:48
Bromochloromethane	< 5.00	ug/L		7/28/2020 16:48

This report is part of a multipage document and should only be evaluated in its entirety. The Chain of Custody provides additional sample information, including compliance with the sample condition requirements upon receipt.



Lab Project ID: 203467

**Client:** Alpha Analytical

**Project Reference:** L2030254, C&S Companies, Jamestown Container

<b>Sample Identifier:</b>	30254-14 Equipment Blank		
<b>Lab Sample ID:</b>	203467-14	<b>Date Sampled:</b>	7/15/2020
<b>Matrix:</b>	Groundwater	<b>Date Received:</b>	7/28/2020
Bromodichloromethane	< 2.00	ug/L	7/28/2020 16:48
Bromoform	< 5.00	ug/L	7/28/2020 16:48
Bromomethane	< 2.00	ug/L	7/28/2020 16:48
Carbon disulfide	< 2.00	ug/L	7/28/2020 16:48
Carbon Tetrachloride	< 2.00	ug/L	7/28/2020 16:48
Chlorobenzene	< 2.00	ug/L	7/28/2020 16:48
Chloroethane	< 2.00	ug/L	7/28/2020 16:48
Chloroform	< 2.00	ug/L	7/28/2020 16:48
Chloromethane	< 2.00	ug/L	7/28/2020 16:48
cis-1,2-Dichloroethene	< 2.00	ug/L	7/28/2020 16:48
cis-1,3-Dichloropropene	< 2.00	ug/L	7/28/2020 16:48
Cyclohexane	< 10.0	ug/L	7/28/2020 16:48
Dibromochloromethane	< 2.00	ug/L	7/28/2020 16:48
Dichlorodifluoromethane	< 2.00	ug/L	7/28/2020 16:48
Ethylbenzene	< 2.00	ug/L	7/28/2020 16:48
Freon 113	< 2.00	ug/L	7/28/2020 16:48
Isopropylbenzene	< 2.00	ug/L	7/28/2020 16:48
m,p-Xylene	< 2.00	ug/L	7/28/2020 16:48
Methyl acetate	< 2.00	ug/L	7/28/2020 16:48
Methyl tert-butyl Ether	< 2.00	ug/L	7/28/2020 16:48
Methylcyclohexane	< 2.00	ug/L	7/28/2020 16:48
Methylene chloride	< 5.00	ug/L	7/28/2020 16:48
Naphthalene	< 5.00	ug/L	7/28/2020 16:48
n-Butylbenzene	< 2.00 UJ	ug/L	7/28/2020 16:48
n-Propylbenzene	< 2.00	ug/L	7/28/2020 16:48

This report is part of a multipage document and should only be evaluated in its entirety. The Chain of Custody provides additional sample information, including compliance with the sample condition requirements upon receipt.



Lab Project ID: 203467

**Client:** Alpha Analytical

**Project Reference:** L2030254, C&S Companies, Jamestown Container

**Sample Identifier:** 30254-14 Equipment Blank

**Lab Sample ID:** 203467-14

**Date Sampled:** 7/15/2020

**Matrix:** Groundwater

**Date Received:** 7/28/2020

o-Xylene	< 2.00	ug/L	7/28/2020	16:48
p-Isopropyltoluene	< 2.00	ug/L	7/28/2020	16:48
sec-Butylbenzene	< 2.00	ug/L	7/28/2020	16:48
Styrene	< 5.00	ug/L	7/28/2020	16:48
tert-Butylbenzene	< 2.00	ug/L	7/28/2020	16:48
Tetrachloroethene	< 2.00	ug/L	7/28/2020	16:48
Toluene	< 2.00	ug/L	7/28/2020	16:48
trans-1,2-Dichloroethene	< 2.00	ug/L	7/28/2020	16:48
trans-1,3-Dichloropropene	< 2.00	ug/L	7/28/2020	16:48
Trichloroethene	< 2.00	ug/L	7/28/2020	16:48
Trichlorofluoromethane	< 2.00	ug/L	7/28/2020	16:48
Vinyl chloride	< 2.00	ug/L	7/28/2020	16:48

<b>Surrogate</b>	<b>Percent Recovery</b>	<b>Limits</b>	<b>Outliers</b>	<b>Date Analyzed</b>
1,2-Dichloroethane-d4	<b>89.3</b>	80.8 - 132		7/28/2020 16:48
4-Bromofluorobenzene	<b>68.4</b>	56.6 - 130		7/28/2020 16:48
Pentafluorobenzene	<b>107</b>	87.4 - 113		7/28/2020 16:48
Toluene-D8	<b>89.7</b>	82.2 - 115		7/28/2020 16:48

**Method Reference(s):** EPA 8260C  
EPA 5030C

**Data File:** x72085.D

This report is part of a multipage document and should only be evaluated in its entirety. The Chain of Custody provides additional sample information, including compliance with the sample condition requirements upon receipt.



Lab Project ID: 203467

Client: Alpha Analytical

Project Reference: L2030254, C&S Companies, Jamestown Container

Sample Identifier: 30254-15 Field Blank

Lab Sample ID: 203467-15

Date Sampled: 7/15/2020

Matrix: Groundwater

Date Received: 7/28/2020

**Volatile Organics**

Analyte	Result	Units	Qualifier	Date Analyzed
1,1,1-Trichloroethane	< 2.00	ug/L		7/28/2020 17:10
1,1,2,2-Tetrachloroethane	< 2.00	ug/L		7/28/2020 17:10
1,1,2-Trichloroethane	< 2.00	ug/L		7/28/2020 17:10
1,1-Dichloroethane	< 2.00	ug/L		7/28/2020 17:10
1,1-Dichloroethene	< 2.00	ug/L		7/28/2020 17:10
1,2,3-Trichlorobenzene	< 5.00 UJ	ug/L		7/28/2020 17:10
1,2,4-Trichlorobenzene	< 5.00 UJ	ug/L		7/28/2020 17:10
1,2,4-Trimethylbenzene	< 2.00	ug/L		7/28/2020 17:10
1,2-Dibromo-3-Chloropropane	< 10.0 UJ	ug/L		7/28/2020 17:10
1,2-Dibromoethane	< 2.00	ug/L		7/28/2020 17:10
1,2-Dichlorobenzene	< 2.00 UJ	ug/L		7/28/2020 17:10
1,2-Dichloroethane	< 2.00	ug/L		7/28/2020 17:10
1,2-Dichloropropane	< 2.00	ug/L		7/28/2020 17:10
1,3,5-Trimethylbenzene	< 2.00	ug/L		7/28/2020 17:10
1,3-Dichlorobenzene	< 2.00 UJ	ug/L		7/28/2020 17:10
1,4-Dichlorobenzene	< 2.00 UJ	ug/L		7/28/2020 17:10
1,4-Dioxane	< <del>20.0</del> R	ug/L		7/28/2020 17:10
2-Butanone	< 10.0	ug/L		7/28/2020 17:10
2-Hexanone	< 5.00	ug/L		7/28/2020 17:10
4-Methyl-2-pentanone	< 5.00	ug/L		7/28/2020 17:10
Acetone	< 10.0	ug/L		7/28/2020 17:10
Benzene	< 1.00	ug/L		7/28/2020 17:10
Bromochloromethane	< 5.00	ug/L		7/28/2020 17:10

This report is part of a multipage document and should only be evaluated in its entirety. The Chain of Custody provides additional sample information, including compliance with the sample condition requirements upon receipt.



Lab Project ID: 203467

**Client:** Alpha Analytical

**Project Reference:** L2030254, C&S Companies, Jamestown Container

<b>Sample Identifier:</b>	30254-15 Field Blank		
<b>Lab Sample ID:</b>	203467-15	<b>Date Sampled:</b>	7/15/2020
<b>Matrix:</b>	Groundwater	<b>Date Received:</b>	7/28/2020
Bromodichloromethane	< 2.00	ug/L	7/28/2020 17:10
Bromoform	< 5.00	ug/L	7/28/2020 17:10
Bromomethane	< 2.00	ug/L	7/28/2020 17:10
Carbon disulfide	< 2.00	ug/L	7/28/2020 17:10
Carbon Tetrachloride	< 2.00	ug/L	7/28/2020 17:10
Chlorobenzene	< 2.00	ug/L	7/28/2020 17:10
Chloroethane	< 2.00	ug/L	7/28/2020 17:10
Chloroform	< 2.00	ug/L	7/28/2020 17:10
Chloromethane	< 2.00	ug/L	7/28/2020 17:10
cis-1,2-Dichloroethene	< 2.00	ug/L	7/28/2020 17:10
cis-1,3-Dichloropropene	< 2.00	ug/L	7/28/2020 17:10
Cyclohexane	< 10.0	ug/L	7/28/2020 17:10
Dibromochloromethane	< 2.00	ug/L	7/28/2020 17:10
Dichlorodifluoromethane	< 2.00	ug/L	7/28/2020 17:10
Ethylbenzene	< 2.00	ug/L	7/28/2020 17:10
Freon 113	< 2.00	ug/L	7/28/2020 17:10
Isopropylbenzene	< 2.00	ug/L	7/28/2020 17:10
m,p-Xylene	< 2.00	ug/L	7/28/2020 17:10
Methyl acetate	< 2.00	ug/L	7/28/2020 17:10
Methyl tert-butyl Ether	< 2.00	ug/L	7/28/2020 17:10
Methylcyclohexane	< 2.00	ug/L	7/28/2020 17:10
Methylene chloride	< 5.00	ug/L	7/28/2020 17:10
Naphthalene	< 5.00	ug/L	7/28/2020 17:10
n-Butylbenzene	< 2.00 UJ	ug/L	7/28/2020 17:10
n-Propylbenzene	< 2.00	ug/L	7/28/2020 17:10

This report is part of a multipage document and should only be evaluated in its entirety. The Chain of Custody provides additional sample information, including compliance with the sample condition requirements upon receipt.





Lab Project ID: 203467

**Client:** Alpha Analytical

**Project Reference:** L2030254, C&S Companies, Jamestown Container

**Sample Identifier:** 30254-15 Field Blank

**Lab Sample ID:** 203467-15

**Date Sampled:** 7/15/2020

**Matrix:** Groundwater

**Date Received:** 7/28/2020

o-Xylene	< 2.00	ug/L	7/28/2020	17:10
p-Isopropyltoluene	< 2.00	ug/L	7/28/2020	17:10
sec-Butylbenzene	< 2.00	ug/L	7/28/2020	17:10
Styrene	< 5.00	ug/L	7/28/2020	17:10
tert-Butylbenzene	< 2.00	ug/L	7/28/2020	17:10
Tetrachloroethene	< 2.00	ug/L	7/28/2020	17:10
Toluene	< 2.00	ug/L	7/28/2020	17:10
trans-1,2-Dichloroethene	< 2.00	ug/L	7/28/2020	17:10
trans-1,3-Dichloropropene	< 2.00	ug/L	7/28/2020	17:10
Trichloroethene	< 2.00	ug/L	7/28/2020	17:10
Trichlorofluoromethane	< 2.00	ug/L	7/28/2020	17:10
Vinyl chloride	< 2.00	ug/L	7/28/2020	17:10

<b>Surrogate</b>	<b>Percent Recovery</b>	<b>Limits</b>	<b>Outliers</b>	<b>Date Analyzed</b>
1,2-Dichloroethane-d4	<b>92.7</b>	80.8 - 132		7/28/2020 17:10
4-Bromofluorobenzene	<b>66.1</b>	56.6 - 130		7/28/2020 17:10
Pentafluorobenzene	<b>110</b>	87.4 - 113		7/28/2020 17:10
Toluene-D8	<b>89.2</b>	82.2 - 115		7/28/2020 17:10

**Method Reference(s):** EPA 8260C  
EPA 5030C  
**Data File:** x72086.D

This report is part of a multipage document and should only be evaluated in its entirety. The Chain of Custody provides additional sample information, including compliance with the sample condition requirements upon receipt.

*Appendix B*

---

*Laboratory  
QC  
Documentation*

2  
VOLATILE SURROGATE RECOVERY

Lab Name: Paradigm Environmental Services  
 Lab Project #: 203467  
 Client Name: Alpha Analytical  
 Client Project Name: L2030254, C&S Companies, Jamestown Container  
 Client Project #: N/A  
 SDG No.: 3467-01

Matrix: Groundwater  
 QC Batch: voaw200728

Instrument ID: Instrument1  
 GC Column 1: DB-624 ID (mm): 0.20 Detector: MSD

LAB SAMPLE NO.	CLIENT SAMPLE ID	PFB %REC	12DCEd4 %REC	TD8 %REC	4BFB %REC	Total Out	
1	Blk 1	N/A	108	104	87.3	61.3	0
2	LCS 1	N/A	107	99.2	96.6	106	0
3	203467-01	30254-01 ESI-3-071520	105	97.9	86.2	63.3	0
4	203467-01MS	30254-01 ESI-3-071520	103	115	108	122	0
5	203467-01MSD	30254-01 ESI-3-071520	108	101	102	114	0
6	203467-02	30254-02 PW-1-071520	98.8	127	79.0 *	63.4	1
7	203467-04	30254-04 ESI-1-071520	105	103	88.6	62.6	0
8	203467-05	30254-05 ESI-13R-071520	103	104	84.5	63.1	0
9	203467-05MS	30254-05 ESI-13R-071520	108	99.7	104	112	0
10	203467-05MSD	30254-05 ESI-13R-071520	105	94.3	105	109	0
11	203467-06	30254-06 ESI-6-071520	106	105	83.9	60.4	0
12	203467-07	30254-07 ESI-7-071520	102	113	82.3	60.6	0
13	203467-08	30254-08 PW-3R-071520	103	110	79.6 *	59.6	1
14	203467-11	30254-11 ESI-10-071520	100	115	82.0 *	62.6	1
15	203467-12	30254-12 ESI-11-071520	104	121	82.2	66.8	0
16	203467-13	30254-13 ESI-12-071520	104	121	79.9 *	64.0	1
17	203467-14	30254-14 Equipment Blank	107	89.3	89.7	68.4	0
18	203467-15	30254-15 Field Blank	110	92.7	89.2	66.1	0
19							
20							
21							
22							
23							
24							
25							

QC LIMITS %

PFB = Pentafluorobenzene (87.4 - 113)  
 12DCEd4 = 1,2-Dichloroethane-d4 (80.8 - 132)  
 TD8 = Toluene-d8 (82.2 - 115)  
 4BFB = 4-Bromofluorobenzene (56.6 - 130)

\* Values outside of current required QC limits  
 D Surrogate diluted out

Response Factor Report Instrument #1

Method Path : C:\msdchem\1\METHODS\  
 Method File : 200720.M  
 Title : 8260/624 Analysis  
 Last Update : Mon Jul 20 13:51:34 2020  
 Response Via : Initial Calibration

7/20/2020 BB

Calibration Files

1 =x71886.D 2 =x71887.D 3 =x71888.D 4 =x71889.D 5 =x71890.D 6 =x71891.D 7 =x71892.D

Compound	1	2	3	4	5	6	7	Avg	%RSD
1) I Fluorobenzene	-----ISTD-----								
2) P Dichlorodifluo...	1.314	1.070	0.975	0.983	0.884	0.788	0.761	0.968	19.44
3) P Chloromethane	1.578	1.334	1.197	1.182	1.060	0.974	0.936	1.180	18.90
4) P Vinyl chloride	1.107	0.979	0.949	1.055	1.004	0.919	0.895	0.987	7.61
5) P Bromomethane	1.036	0.777	0.685	0.663	0.609	0.564	0.539	0.696	24.39 *
6) P Chloroethane	0.918	0.718	0.640	0.652	0.591	0.543	0.531	0.656	20.19 *
7) P Trichlorofluor...	1.711	1.510	1.320	1.327	1.184	1.060	1.015	1.304	18.95
8) Ethyl ether	0.288	0.271	0.294	0.326	0.318	0.313	0.310	0.303	6.34
9) P Freon 113	0.969	0.863	0.783	0.791	0.704	0.622	0.603	0.762	17.12
10) P 1,1-Dichloroet...	1.153	1.070	0.988	1.020	0.948	0.857	0.828	0.981	11.70
11) P Acetone	0.361	0.245	0.160	0.150	0.138	0.137	0.111	0.186	47.21 *
12) Isopropyl Alcohol							0.000		-1.00
13) P Carbon disulfide	2.000	1.746	1.700	1.849	1.732	1.581	1.532	1.734	9.10
14) P Methyl acetate	0.225	0.166	0.168	0.175	0.173	0.161	0.159	0.175	12.96
15) P Methylene chlo...	1.163	0.779	0.668	0.638	0.573	0.536	0.522	0.697	32.09 *
16) Acrylonitrile		0.098	0.104	0.106	0.098	0.093	0.092	0.098	5.84
17) tert-Butyl Alc...	0.017	0.013	0.012	0.012	0.012	0.012	0.013	0.013	14.92
18) P Methyl tert-bu...	0.742	0.659	0.692	0.751	0.724	0.731	0.738	0.719	4.56
19) P trans-1,2-Dich...	1.136	0.972	0.938	0.985	0.886	0.811	0.779	0.930	12.89
20) P 1,1-Dichloroet...	1.590	1.428	1.362	1.332	1.237	1.137	1.108	1.313	12.87
21) Vinyl acetate		0.439	0.445	0.534	0.563	0.577	0.602	0.527	13.13
22) 2,2-Dichloropr...	0.917	0.832	0.858	0.955	0.921	0.877	0.873	0.890	4.75
23) P 2-Butanone	0.045	0.045	0.043	0.047	0.044	0.043	0.043	0.044#	3.19
24) P cis-1,2-Dichlo...	0.769	0.711	0.730	0.781	0.758	0.719	0.700	0.738	4.21
25) Bromochloromet...	0.300	0.294	0.277	0.277	0.262	0.246	0.241	0.271	8.27
26) P Chloroform	1.420	1.355	1.293	1.286	1.175	1.098	1.050	1.240	10.99
27) S Pentafluoroben...	0.490	0.492	0.496	0.529	0.533	0.523	0.530	0.513	3.86
28) Tetrahydrofuran	0.042	0.041	0.038	0.048	0.050	0.055	0.057	0.047	15.58
29) P 1,1,1-Trichlor...	1.177	1.078	1.092	1.149	1.092	1.013	1.002	1.086	5.92
30) P Cyclohexane	1.157	1.081	1.213	1.460	1.492	1.256	1.340	1.285	11.89
31) S 1,2-Dichloroet...	0.262	0.252	0.238	0.231	0.212	0.198	0.196	0.227	11.42
32) P Carbon Tetrach...	0.945	0.941	0.941	1.017	0.971	0.893	0.875	0.940	5.01
33) P Benzene	2.752	2.737	2.843	2.941	2.743	2.510	2.387	2.702	7.06
34) P 1,2-Dichloroet...	0.759	0.718	0.686	0.680	0.614	0.583	0.561	0.657	11.11
35) P Trichloroethene	0.677	0.612	0.636	0.714	0.725	0.696	0.699	0.680	6.13
36) tert-Butyl Ace...							0.000		-1.00
37) P Methylcyclohexane	0.740	0.726	1.040	1.352	1.363	1.277	1.264	1.100	25.07 *
38) 1,4-Dioxane		0.003	0.004	0.003	0.003	0.004	0.004	0.004	9.44

Rf <0.005

\*curve is not avg. of response factors

Evaluate Continuing Calibration Report

Data File: C:\msdchem\1\DATA\200728\x72073.D  
 DataAcq Meth:8260RUN.M  
 Acq On : 28 Jul 2020 12:20 pm  
 Sample : 50ppb mega CC  
 Misc :  
 ALS Vial : 4 Sample Multiplier: 1

Operator: Bill Brew  
 Inst : Instrument #1

Quant Time: Jul 28 16:11:59 2020  
 Quant Method : C:\msdchem\1\METHODS\200720.M  
 Quant Title : 8260/624 Analysis  
 QLast Update : Tue Jul 28 11:26:04 2020  
 Response via : Initial Calibration  
 Integrator: RTE

Min. RRF : 0.000 Min. Rel. Area : 50% Max. R.T. Dev 0.50min  
 Max. RRF Dev : 20% Max. Rel. Area : 200%

	Compound	Amount	Calc.	%Dev	Area%	Dev(min)
48 P	4-Methyl-2-pentanone	50.000	46.342	7.3	86	0.01
49 S	Toluene-D8	30.000	31.417	-4.7	94	0.01
50 P	Toluene	50.000	59.324	-18.6	94	0.00
51 P	trans-1,3-Dichloropropene	50.000	44.777	10.4	87	0.00
52 P	1,1,2-Trichloroethane	50.000	50.538	-1.1	91	0.00
53	1,3-Dichloropropane	50.000	52.752	-5.5	89	0.00
54 P	Tetrachloroethene	50.000	55.535	-11.1	96	0.01
55 P	2-Hexanone	50.000	45.210	9.6	88	0.00
56 P	Dibromochloromethane	50.000	51.106	-2.2	89	0.00
57 P	1,2-Dibromoethane	50.000	50.533	-1.1	90	0.01
58 I	Chlorobenzene-d5	50.000	50.000	0.0	95	0.01
59 P	Chlorobenzene	50.000	53.955	-7.9	95	0.00
60	1,1,1,2-Tetrachloroethane	50.000	52.942	-5.9	93	0.00
61 P	Ethylbenzene	50.000	50.336	-0.7	94	0.00
62 P	m,p-Xylene	100.000	103.357	-3.4	96	0.00
63 P	o-Xylene	50.000	48.532	2.9	92	0.01
64 P	Styrene	50.000	49.997	0.0	94	0.00
65 P	Bromoform	50.000	44.425	11.2	88	0.00
66 P	Isopropylbenzene	50.000	48.590	2.8	94	0.00
67	1,2,3-Trichloropropane	50.000	48.643	2.7	87	0.00
68 S	4-Bromofluorobenzene	30.000	32.193	-7.3	93	0.00
69	Bromobenzene	50.000	56.726	-13.5	92	0.00
70 P	1,1,2,2-Tetrachloroethane	50.000	49.945	0.1	89	0.00
71	n-Propylbenzene	50.000	50.968	-1.9	94	0.00
72	2-Chlorotoluene	50.000	58.530	-17.1	95	0.00
73	4-Chlorotoluene	50.000	59.436	-18.9	97	0.00
74	1,3,5-Trimethylbenzene	50.000	50.655	-1.3	95	0.00
75	tert-Butylbenzene	50.000	49.783	0.4	95	0.00
76	1,2,4-Trimethylbenzene	50.000	50.182	-0.4	95	0.00
77	sec-Butylbenzene	50.000	49.716	0.6	94	0.00
78	p-Isopropyltoluene	50.000	50.331	-0.7	95	0.00
79 I	1,4-Dichlorobenzene-d4	50.000	50.000	0.0	64	0.00
80 P	1,3-Dichlorobenzene	50.000	76.147	-52.3#	95	0.00
81 P	1,4-Dichlorobenzene	50.000	73.017	-46.0#	97	0.00
82	n-Butylbenzene	50.000	72.307	-44.6#	95	0.00
83 P	1,2-Dichlorobenzene	50.000	79.451	-58.9#	96	0.00
84 UN	Tetraethyllead	-1.000	0.000	0.0	0	0.00
85 P	1,2-Dibromo-3-Chloropropane	50.000	67.839	-35.7#	91	0.00
86 P	1,2,4-Trichlorobenzene	50.000	60.472	-20.9#	92	0.00
87	1,2,3-Trichlorobenzene	50.000	61.704	-23.4#	91	0.00
88	Hexachlorobutadiene	50.000	67.536	-35.1#	95	0.00
89	Naphthalene	50.000	51.002	-2.0	82	0.00

ok if ND  
 ↓  
 ok if ND  
 ↓

(#) = Out of Range

SPCC's out = 0 CCC's out = 0

Evaluate Continuing Calibration Report

Data File: C:\msdchem\1\DATA\200729\x72107.D  
 DataAcq Meth:8260RUN.M  
 Acq On : 29 Jul 2020 11:15 am  
 Sample : 50ppb mega CC  
 Misc :  
 ALS Vial : 4 Sample Multiplier: 1

Operator: Bill Brew  
 Inst : Instrument #1

Quant Time: Jul 29 14:52:54 2020  
 Quant Method : C:\msdchem\1\METHODS\200720.M  
 Quant Title : 8260/624 Analysis  
 QLast Update : Tue Jul 28 14:50:59 2020  
 Response via : Initial Calibration  
 Integrator: RTE

Min. RRF : 0.000 Min. Rel. Area : 50% Max. R.T. Dev 0.50min  
 Max. RRF Dev : 20% Max. Rel. Area : 200%

Compound	Amount	Calc.	%Dev	Area%	Dev(min)
48 P 4-Methyl-2-pentanone	50.000	45.054	9.9	81	0.01
49 S Toluene-D8	30.000	31.182	-3.9	91	0.00
50 P Toluene	50.000	58.332	-16.7	89	0.00
51 P trans-1,3-Dichloropropene	50.000	42.505	15.0	80	0.00
52 P 1,1,2-Trichloroethane	50.000	50.579	-1.2	89	0.00
53 1,3-Dichloropropane	50.000	52.249	-4.5	85	0.00
54 P Tetrachloroethene	50.000	55.320	-10.6	93	0.01
55 P 2-Hexanone	50.000	44.930	10.1	85	0.00
56 P Dibromochloromethane	50.000	49.865	0.3	84	0.00
57 P 1,2-Dibromoethane	50.000	49.134	1.7	85	0.00
58 I Chlorobenzene-d5	50.000	50.000	0.0	90	0.01
59 P Chlorobenzene	50.000	53.020	-6.0	89	0.00
60 1,1,1,2-Tetrachloroethane	50.000	53.425	-6.8	89	0.00
61 P Ethylbenzene	50.000	49.840	0.3	89	0.00
62 P m,p-Xylene	100.000	102.055	-2.1	90	0.00
63 P o-Xylene	50.000	46.765	6.5	85	0.00
64 P Styrene	50.000	49.123	1.8	88	0.00
65 P Bromoform	50.000	44.478	11.0	84	0.00
66 P Isopropylbenzene	50.000	47.708	4.6	88	0.00
67 1,2,3-Trichloropropane	50.000	49.841	0.3	84	0.00
68 S 4-Bromofluorobenzene	30.000	32.002	-6.7	88	0.00
69 Bromobenzene	50.000	55.224	-10.4	86	0.00
70 P 1,1,2,2-Tetrachloroethane	50.000	49.473	1.1	84	0.00
71 n-Propylbenzene	50.000	50.277	-0.6	89	0.00
72 2-Chlorotoluene	50.000	57.043	-14.1	88	0.00
73 4-Chlorotoluene	50.000	58.192	-16.4	90	0.00
74 1,3,5-Trimethylbenzene	50.000	48.809	2.4	87	0.00
75 tert-Butylbenzene	50.000	47.921	4.2	87	0.00
76 1,2,4-Trimethylbenzene	50.000	48.511	3.0	88	0.00
77 sec-Butylbenzene	50.000	48.377	3.2	87	0.00
78 p-Isopropyltoluene	50.000	48.340	3.3	87	0.00
79 I 1,4-Dichlorobenzene-d4	50.000	50.000	0.0	62	0.00
80 P 1,3-Dichlorobenzene	50.000	73.147	-46.3#	87	0.00
81 P 1,4-Dichlorobenzene	50.000	70.118	-40.2#	89	0.00
82 n-Butylbenzene	50.000	68.091	-36.2#	86	0.00
83 P 1,2-Dichlorobenzene	50.000	76.426	-52.9#	88	0.00
84 UN Tetraethyllead	-1.000	0.000	0.0	0	0.00
85 P 1,2-Dibromo-3-Chloropropane	50.000	62.249	-24.5#	79	0.00
86 P 1,2,4-Trichlorobenzene	50.000	51.561	-3.1	73	0.00
87 1,2,3-Trichlorobenzene	50.000	51.775	-3.5	72	0.00
88 Hexachlorobutadiene	50.000	60.019	-20.0#	81	0.00
89 Naphthalene	50.000	41.390	17.2	62	0.00

Handwritten notes: "OK if ND" with arrows pointing to rows 80, 81, 82, 83, 85. "62" is circled in row 79. "-24.5#" is circled in row 85.

(#) = Out of Range

SPCC's out = 0 CCC's out = 0

## *Appendix C*

---

### *Validator Qualifications*

**KENNETH R. APPLIN**  
**Geochemist/Data Validator**

Ph.D., Geochemistry and Mineralogy, The Pennsylvania State University

M.S., Geochemistry and Mineralogy, The Pennsylvania State University

B.A., Geological Sciences, SUNY at Geneseo, NY

Dr. Applin has over 35 years of experience working with the geochemistry of natural waters. His prior experience includes working as an Assistant Professor of Geology at the University of Missouri-Columbia and as Chief Hydrogeologist and Geochemist with a leading engineering firm in Rochester, NY. In 1993, he established KR Applin and Associates, a small consulting business that focuses on the geochemistry of natural waters, especially as applied to problems involving the contamination of groundwater and surface water.

Dr. Applin is also an experienced analytical data validator and has provided data validation services since 1994 to a variety of clients performing brownfield cleanup projects, hazardous waste remediation, groundwater monitoring at solid waste facilities, and other projects requiring third-party data validation. Dr. Applin has several years of hands-on experience with the laboratory analysis of natural waters and has successfully completed the USEPA Region II certification courses for performing inorganic and organic analytical data validation.



**MICHAEL K. PERRY**  
**Chemist/Data Validator**

B.S. Chemistry, Georgia State University, Atlanta, GA

A.A.S., Chemical Technology, Alfred State College, Alfred, NY

Mr. Perry has over 30 years of experience in the analytical laboratory business. During his early career, he spent several years as a laboratory analyst performing the analysis of soil, water, and air samples for inorganic and organic chemical parameters. During his last 20 years in the environmental laboratory business, he managed and directed two major analytical laboratories in Rochester, NY. His management responsibilities included oversight of the daily operations of the lab, staff training and supervision, the selection, purchase, and maintenance of analytical instruments, the introduction of new laboratory methods, analytical quality assurance and quality control, data acquisition and management, and other business-related activities.

Mr. Perry has an extensive working knowledge of the methods and procedures used for sampling and analyzing both inorganic and organic analytes in soil, water, and air. He is an accomplished laboratory chemist and is familiar with the analytical methods and procedures established under the USEPA Contract Laboratory Protocols (CLP), the NYSDEC Analytical Services Protocols (ASP), and the NYSDOH Environmental Laboratory Approval Program (ELAP).

APPENDIX B  
GROUNDWATER USE CERTIFICATION

*Jamestown Container Realty Inc.  
14 Deming Drive  
Falconer, NY 14733*

September 24, 2020


Re: Site Name: Dowcraft, South Dow Street  
Site No: 907020  
Site Address: 65 South Dow Street, Falconer, NY 14733

To Whom It May Concern,

This confirms that the above referenced property is owned by Jamestown Container Realty Inc. As the property owner, Jamestown Container Realty Inc. hereby certifies that it is not using any ground water drawn from the property.

If you need anything further, please advise.

Sincerely,

A handwritten signature in cursive script that reads "Joseph R. Palmeri". The signature is written in dark ink and is positioned above the printed name and title.

Joseph R. Palmeri  
Vice President / COO

APPENDIX C

INSTITUTIONAL AND ENGINEERING CONTROLS CERTIFICATION FORM



Enclosure 2  
**NEW YORK STATE DEPARTMENT OF ENVIRONMENTAL CONSERVATION**  
**Site Management Periodic Review Report Notice**  
**Institutional and Engineering Controls Certification Form**



	Site Details	Box 1
<b>Site No.</b> 907020		
<b>Site Name</b> Dowcraft, South Dow Street		
Site Address: 65 South Dow Street      Zip Code: 14733		
City/Town: Falconer		
County: Chautauqua		
Site Acreage: 2.200		
Reporting Period: October 31, 2018 to October 31, 2019		
		YES    NO
1. Is the information above correct?		<input checked="" type="checkbox"/> <input type="checkbox"/>
If NO, include handwritten above or on a separate sheet.		
2. Has some or all of the site property been sold, subdivided, merged, or undergone a tax map amendment during this Reporting Period?		<input type="checkbox"/> <input checked="" type="checkbox"/>
3. Has there been any change of use at the site during this Reporting Period (see 6NYCRR 375-1.11(d))?		<input type="checkbox"/> <input checked="" type="checkbox"/>
4. Have any federal, state, and/or local permits (e.g., building, discharge) been issued for or at the property during this Reporting Period?		<input type="checkbox"/> <input checked="" type="checkbox"/>
<b>If you answered YES to questions 2 thru 4, include documentation or evidence that documentation has been previously submitted with this certification form.</b>		
5. Is the site currently undergoing development?		<input type="checkbox"/> <input checked="" type="checkbox"/>

	Box 2
	YES    NO
6. Is the current site use consistent with the use(s) listed below? Industrial	<input checked="" type="checkbox"/> <input type="checkbox"/>
7. Are all ICs/ECs in place and functioning as designed?	<input checked="" type="checkbox"/> <input type="checkbox"/>
<b>IF THE ANSWER TO EITHER QUESTION 6 OR 7 IS NO, sign and date below and DO NOT COMPLETE THE REST OF THIS FORM. Otherwise continue.</b>	
<b>A Corrective Measures Work Plan must be submitted along with this form to address these issues.</b>	
Signature of Owner, Remedial Party or Designated Representative	Date

SITE NO. 907020

Box 3

**Description of Institutional Controls**

Parcel

Owner

Institutional Control

104-12-2

Bruce Janowski, Jamestown Container Real

Ground Water Use Restriction  
Landuse Restriction  
Monitoring Plan  
O&M Plan

Box 4

**Description of Engineering Controls**

None Required

Not Applicable/No EC's

**Periodic Review Report (PRR) Certification Statements**

1. I certify by checking "YES" below that:

- a) the Periodic Review report and all attachments were prepared under the direction of, and reviewed by, the party making the certification;
- b) to the best of my knowledge and belief, the work and conclusions described in this certification are in accordance with the requirements of the site remedial program, and generally accepted engineering practices; and the information presented is accurate and complete.

YES      NO

2. If this site has an IC/EC Plan (or equivalent as required in the Decision Document), for each Institutional or Engineering control listed in Boxes 3 and/or 4, I certify by checking "YES" below that all of the following statements are true:

- (a) the Institutional Control and/or Engineering Control(s) employed at this site is unchanged since the date that the Control was put in-place, or was last approved by the Department;
- (b) nothing has occurred that would impair the ability of such Control, to protect public health and the environment;
- (c) access to the site will continue to be provided to the Department, to evaluate the remedy, including access to evaluate the continued maintenance of this Control;
- (d) nothing has occurred that would constitute a violation or failure to comply with the Site Management Plan for this Control; and
- (e) if a financial assurance mechanism is required by the oversight document for the site, the mechanism remains valid and sufficient for its intended purpose established in the document.

YES      NO

**IF THE ANSWER TO QUESTION 2 IS NO, sign and date below and  
DO NOT COMPLETE THE REST OF THIS FORM. Otherwise continue.**

**A Corrective Measures Work Plan must be submitted along with this form to address these issues.**

\_\_\_\_\_  
Signature of Owner, Remedial Party or Designated Representative

\_\_\_\_\_  
Date

IC CERTIFICATIONS

SITE NO. 907020

Box 6

**SITE OWNER OR DESIGNATED REPRESENTATIVE SIGNATURE**

I certify that all information and statements in Boxes 1, 2, and 3 are true. I understand that a false statement made herein is punishable as a Class "A" misdemeanor, pursuant to Section 210.45 of the Penal Law.

I Cody Martin at C&S Engineers Inc., 141 Elm St. Buffalo, NY  
print name print business address

am certifying as Designated Representative (Owner or Remedial Party)

for the Site named in the Site Details Section of this form.

Cody Martin  
Signature of Owner, Remedial Party, or Designated Representative  
Rendering Certification

11/27/19  
Date



APPENDIX D  
OPERATION, MAINTENANCE AND MONITORING WORK PLAN

# **OPERATION, MAINTENANCE AND MONITORING WORK PLAN**

**FOR**

**FORMER DOWCRAFT SITE  
FALCONER, NEW YORK**

*Prepared by:*



**C&S ENGINEERS, INC.**  
141 ELM STREET, SUITE 100  
BUFFALO, NEW YORK 14203

**MARCH 2018**

**TABLE OF CONTENTS**

<b><u>1</u></b>	<b><u>INTRODUCTION</u></b>	<b><u>4</u></b>
1.1	BACKGROUND AND SITE DESCRIPTION	4
<b><u>2</u></b>	<b><u>SUMMARY OF ENVIRONMENTAL CONDITIONS</u></b>	<b><u>5</u></b>
1.2	CONTAMINANTS OF CONCERN	5
1.3	GEOLOGY AND HYDROGEOLOGY	6
1.4	EXTENT OF CONTAMINATION	6
<b><u>3</u></b>	<b><u>OBJECTIVES, SCOPE AND RATIONALE</u></b>	<b><u>6</u></b>
3.1	GROUNDWATER CONTAMINATION	6
3.2	SOIL VAPOR CONTAMINATION	7
<b><u>4</u></b>	<b><u>REMEDIAL ACTION MONITORING AND REPORTING</u></b>	<b><u>8</u></b>
4.1	GROUNDWATER MONITORING PROGRAM	8
4.1.1	MONITORING WELL NETWORK	8
4.1.2	GROUNDWATER MONITORING	9
4.1.3	WELL INSPECTION AND MAINTENANCE	9
4.2	SUB-SLAB DEPRESSURIZATION SYSTEM COMPONENTS	9
4.2.1	BUILDING 9 SYSTEM	9
4.2.2	BUILDING 5 AND 6 SYSTEM	10
4.3	SUB-SLAB DEPRESSURIZATION SYSTEM OPERATION	11
4.4	SOIL VAPOR MONITORING PROGRAM	11
4.4.1	WEEKLY MONITORING	11
4.4.2	ANNUAL INSPECTION	12
4.5	CONTACT INFORMATION	12
4.6	SAMPLING METHODS, ANALYTICAL PROCEDURES AND DOCUMENTATION	13
4.6.1	SAMPLING METHODS	13
4.6.2	ANALYTICAL PROCEDURES	14
4.6.3	DOCUMENTATION	14
<b><u>5</u></b>	<b><u>HEALTH AND SAFETY</u></b>	<b><u>14</u></b>
<b><u>6</u></b>	<b><u>REPORTING</u></b>	<b><u>15</u></b>
<b><u>7</u></b>	<b><u>SCHEDULE</u></b>	<b><u>15</u></b>

**FIGURES**

FIGURE 1 ..... HISTORIC AND EXISTING SITE FEATURES  
FIGURE 2 ..... GROUNDWATER MONITORING

**APPENDICES**

APPENDIX A ..... SUB-SLAB DEPRESSURIZATION SYSTEM WORK PLAN  
APPENDIX B..... HEALTH AND SAFETY PLAN  
APPENDIX C..... SUB-SLAB DEPRESSURIZATION CONSTRUCTION COMPLETION REPORTS

**ACRONYM LIST**

OM&M Plan	OPERATION, MONITORING AND MAINTENANCE PLAN
JCC	JAMESTOWN CONTAINER COMPANY
TCE	TRICHLOROETHENE
IRM	INTERIM REMEDIAL MEASURE
ROD	RECORD OF DECISION
CRA	CONESTOGA-ROVERS & ASSOCIATES
COC	CONTAMINANTS OF CONCERN
DNAPL	DENSE NON-AQUEOUS PHASE LIQUID
BGS	BELOW GROUND SURFACE
NYSDOH	NEW YORK STATE DEPARTMENT OF HEALTH
SSDS	SUB-SLAB DEPRESSURIZATION SYSTEM
HASP	HEALTH AND SAFETY PLAN
MS/MSD	MATRIX SPIKE / MATRIX SPIKE DUPLICATE
U.S. EPA	UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

## **1 INTRODUCTION**

C&S Engineers, Inc. (C&S) has prepared this Operation, Maintenance and Monitoring (OM&M) Plan on behalf of Jamestown Container Companies (JCC) for the former Dowcraft facility (the Site).

### **1.1 Background and Site Description**

The Dowcraft Site is located at 65 South Dow Street in Falconer, New York and occupies approximately 2.2 acres of land situated immediately east of South Dow Street and approximately 100 feet south of the Chadakoin River. The Jamestown Container manufacturing building is situated between the Site and the Chadakoin River.

The property was first developed in 1890 as a woolen mill until 1939 when it was converted into a factory which manufactured steel partitions used for offices. As part of this manufacturing process, a vapor degreaser was used which included the use of chemicals such as trichloroethene (TCE). This work continued until 1999 when the facility was closed, a portion of the Site was demolished, and the property was sold to JCC.

**Figure 1** presents present and historic site features.

The Site was the subject of environmental investigations in the early 1990s, at which time contaminated groundwater was discovered on site. An interim remedial measure (IRM) was subsequently put in place in 1994 which consisted of groundwater extraction and treatment. In 2000, the use of additional groundwater remediation technologies was approved by the NYSDEC which involved in-situ chemical oxidation of TCE through the injection of potassium permanganate into the overburden groundwater. In 2003, a Record of Decision (ROD) was approved that selected the following remedy:

- J In-situ groundwater treatment through chemical oxidation, by injection of potassium permanganate dissolved in water, through existing well points into the shallow overburden groundwater table;
- J Overburden groundwater monitoring to verify the effectiveness of the treatment;
- J Institutional controls to prevent the use of groundwater as a source of potable water; and
- J Annual certification to NYSDEC to certify that institutional controls remain in place.

Conestoga-Rovers & Associates (CRA) conducted nine injection treatments between May 2000 and July 2006, totaling 21,500 pounds of potassium permanganate. Previous injection treatments were successful in oxidizing some TCE; however, the concentrations of TCE in the source area remain high.

Injections were conducted on December 1 through 9, 2014. Two methods were implemented in treating the contaminated groundwater. The first method included the injection of a solution of 4,024.12 pounds of potassium permanganate in ten borings. The second method included the placement of potassium permanganate cylinders as a treatment adjacent to PW-3R and installation of cylinders in monitoring wells inside the JCC building.

The fifth round of post-treatment sampling suggests that the potassium permanganate injections and cylinders appear to be effective in treating the groundwater contaminants in many wells.

## 2 SUMMARY OF ENVIRONMENTAL CONDITIONS


### 1.2 Contaminants of Concern

Chlorinated solvents, primarily, trichloroethene and its daughter compounds, were identified as the contaminants of concern (COC) for this Site. TCE is a man-made volatile organic compound used for degreasing metal and electronic parts. Remedial considerations for TCE include its low solubility value and heavy molecular weight. TCE is in a class of chemicals called dense non-aqueous phase liquids (DNAPL) that sink through the water column until they encounter an impermeable barrier.

Groundwater contaminant plumes with TCE can undergo a process of reductive dechlorination, during which chlorine atoms are stripped from TCE and daughter compounds are produced. The rate of dechlorination can vary based on:

- ) Amount of TCE in the subsurface;
- ) Amount of organic material; and
- ) Type and concentration of electron acceptors available in the system.

The process of TCE reductive dechlorination is shown below:



### **1.3 Geology and Hydrogeology**

Site geology consists of fill material overlying two sand/gravel layers separated by a silt/clay lens. Fill material consists of a mixed matrix of sand, cinders, silt, gravel, brick, concrete, coal, slag and metal. The fill unit ranges in thickness from 2 to over 14 feet with an average thickness of 8 feet.

The upper sand/gravel layer ranges from 10 to 20 feet in thickness. Underlying the upper sand/gravel layer is a silt/clay lens that ranges from 4 to 8 feet in thickness. The lower sand/gravel layer is 10 to 18 feet thick. Underlying the lower sand layer is a second silt/clay layer that starts approximately 43 feet below ground surface (BGS). This unit is estimated to be 60 feet in thickness according to regional geology.

The average depth to groundwater is 10 feet BGS within the upper sand/gravel layer. Groundwater flow within the upper sand/gravel layer is to the north-northeast at approximately 2.7 feet per year. Figure 2 shows the inferred groundwater flow direction in the upper sand/gravel layer. The silt/clay layer overlying the lower sand/gravel layer is acting as an aquitard for deeper groundwater and is creating a semi-confined aquifer.

### **1.4 Extent of Contamination**

According to previous environmental reports, the area of former degreaser pit (area of groundwater monitoring wells PW-3 and PW-3R) is a likely source area for the COC plume. The plume originates from the degreaser area and has affected groundwater in the upper and lower sand/gravel layers. The plume extends from the degreaser area to the north, under the JCC building and up to the area of the Chadakoin River. This is an area of approximately one acre. The rate of movement is approximately 2 to 3 feet per year to the north.

## **3 OBJECTIVES, SCOPE AND RATIONALE**

The objectives of the scope of work described in this Work Plan are to monitor the natural attenuation of the groundwater contamination and periodically inspect the operation of two soil vapor mitigation systems over five years.

### **3.1 Groundwater Contamination**

As stated in the 2003 ROD, the remedial goals selected for this Site are:

- J Treat the source area of groundwater contamination by oxidative de-chlorination of the contaminants in place;
- J Prevent exposure of human receptors to contaminated groundwater in the sand and gravel unit under Site;
- J Prevent or mitigate, to the maximum extent practicable, COC migration via groundwater so that releases from the underlying sand and gravel unit to the Chadakoin River do not exceed applicable standards, criteria and guidance;
- J Prevent or mitigate, to the maximum extent practicable, the migration of contaminated groundwater to off-site areas;
- J Restore on-Site groundwater in the sand and gravel unit to the maximum extent practicable which will not result in exceedances of applicable standards, criteria and guidance; and



J) Monitor the groundwater in a manner to verify the effectiveness of the remedial actions.

Two IRMs have been conducted at the Site. The first IRM involved the operation of a groundwater pump & treat system between 1994 and 1999. The second IRM consisted of CRA conducting nine injection treatments between May 2000 and July 2006, totaling 21,500 pounds of potassium permanganate and one injection of soy lactate have been completed and have dramatically reduced the concentrations of COCs in groundwater in the area of the former TCE degreaser pit. C&S conducted one injection in December 2014, totaling 4,024.12 pounds of potassium permanganate, and installed a potassium permanganate treatment fence. These efforts have further reduced COC concentrations.

C&S has reviewed the criteria outlined by the EPA on evaluating the potential for natural attenuation on sites contaminated with chlorinated solvents. Based on groundwater quality results from past groundwater monitoring events, C&S believes that natural attenuation via anaerobic biodegradation could effectively degrade the remaining COCs in the on-site groundwater.

C&S proposes the next remedial action for the Site consist of monitored natural attenuation for five years in addition to existing institutional controls to prohibit the use of impacted Site groundwater. The sections below outline the sampling plan, maintenance/monitoring protocols and reporting for the natural attenuation monitoring.

### **3.2 Soil Vapor Contamination**

On November 2, 2015, Centek Laboratories performed the SVI sampling with the assistance of JCC maintenance staff. A total of nine sub-slab samples and nine indoor air samples installed within two buildings. Sub-slab air samples indicate that TCE contaminated soil vapor has impacted the subsurface underneath both of the buildings. After review of the SVI study, the New York State Department of Health (NYSDOH) required the installation of a mitigation system address soil vapor concerns.

Two separate sub-slab depressurization systems (SSDS) were designed and recently installed to mitigate the migration or potential migration of subsurface vapors into the building interiors. As stated in the Sub-Slab Depressurization System Work Plan (provided in **Appendix A**) C&S proposes to monitor the SSDS for five years.

*April 2017, Jamestown Container Companies – 65 South DOW St., Falconer, NY 14733 Construction Completion Report for SSD System – Building 9, prepared by Mitigation Tech Vapor Intrusion Specialists.*

The building was assessed by confirmatory sub-slab air communication testing at the job start to refine data obtained from the preliminary building assessment. The system, comprised of two fans, suction cavities, and other SSD system components, was constructed on March 21 through 27, 2017. Vacuum and air flow measurements were performed continuously during construction to ensure design integrity.

As-built sketches of the system are provided in Appendix C.

*October 2017, Jamestown Container Companies – 65 South DOW St., Falconer, NY 14733 Construction Completion Report for SSD System – Building 5 & 6, prepared by Mitigation Tech Vapor Intrusion Specialists.*

This document presented a construction report, performance evaluation, O&M recommendations, and certification of effectiveness for the SSDS and Crawlspace Ventilation System (CVS) installed by Mitigation Tech. Following a Design/Build SSD construction plan that was modified based on continuing assessment performed during construction, five single suction point SSD systems were installed using principles and equipment typically used for soil vapor intrusion mitigation in buildings in compliance with the NYSDOH document, "Guidance for Evaluation Soil Vapor Intrusion in the State of New York, October 2006."

The building was assessed by extensive sub-slab air communication testing at job start to refine data obtained from the preliminary building assessment. Due to a system of sub-slab structural arches and crisscrossing grade beams, sub-slab spaces were either inaccessible or difficult to access. In the case of Building 5, extensive backfilling has occurred such that the soil is present immediately below the floor in the central and northernmost portions of the foundation. The southernmost portion is an open crawlspace with a dirt floor. Mitigation Tech determined that active ventilation of the southernmost sub-slab compartment bounded by buildings 4 and 6A would constitute a zone of defense to intercept soil vapor migrating from the south which would also create some limited depressurization north of the first grade beam. In the case of Building 6, the sub-space is in essence a crawlspace so ventilation was determined the most appropriate strategy to divert vapors from the building interior.

The system, comprised of five independent fan systems, suction cavities, and other SSD system components, was constructed on August 4 through 7, 2017. Vacuum and air flow measurements were performed continuously during construction to ensure design integrity.

As-built sketches of the system are provided in Appendix C.

## **4 REMEDIAL ACTION MONITORING AND REPORTING**

The Remedial Action Monitoring Program will consist of monitoring of Site groundwater on annual basis and the performance of the SSDS on a weekly/annual. The data collected will be used to evaluate the performance of the remedial action and to meet the monitoring requirements.

The following subsections present the details of the monitoring program including specific sample collection, sample analyses, and reporting tasks.

### **4.1 Groundwater Monitoring Program**

A groundwater monitoring program has been designed to provide the data necessary to demonstrate the effectiveness of natural attenuation

#### **4.1.1 Monitoring Well Network**

The Site contains a total of 23 monitoring wells installed in November 1990, November 1991, and April 1992. The monitoring wells below have been shown to be directly within the contaminant plume.

ESI - 1	ESI - 11
ESI - 2	ESI - 12
ESI - 3	ESI - 13R
ESI - 6	PW - 1
ESI - 7	PW - 3R

## ESI - 10

It should be noted that PW-2 has been previously sampled by other consultants; however, during groundwater monitoring conducted by C&S on July 2, 2013, PW-2 could not be developed and sampled because piping was located in the well that could not be removed. Monitoring well ESI - 6 is located within six feet of PW-2 and was developed and sampled as a substitute for PW-2.

### 4.1.2 Groundwater Monitoring

To characterize groundwater conditions at the Site, 11 existing monitoring wells will be sampled annually. The groundwater samples will be analyzed for Target Compound List (TCL) VOCs. The locations of the monitoring wells to be sampled are shown in **Figure 2**.

Groundwater sampling will be conducted using low-flow purging and sampling techniques. Before purging the well, water levels will be measured using an electric water level sounder capable of measuring to the 0.01-foot accuracy. Peristaltic or bladder pumps using manufacturer-specified tubing will be used for purging and sampling groundwater. Calibration, purging and sampling procedures will be performed as specified by the USEPA<sup>1</sup> for low-flow sampling. Decontamination will be conducted after each well is sampled to reduce the likelihood of cross contamination. Calibration times, purging volumes, water levels and field measurements will be recorded in a field log.

Purge fluids will be treated with activated carbon prior to being allowed to infiltrate the ground surface of the Site.

### 4.1.3 Well Inspection and Maintenance

All on-site wells will be inspected annually in conjunction with a groundwater monitoring event. Wells will be inspected for structural damage to the well cap seal, protective pad, and visible portion of the well casing. The presence and condition of J-plugs and locks also will be noted. In addition, the open depth of the well will be sounded. Deficiencies in or damages to the wells will be corrected or repaired as necessary.

The well inspection and maintenance program will continue until the remedial action (including monitoring) is complete. Once the project has been completed, all wells will be decommissioned following CP-43: Groundwater Monitoring Well Decommissioning Policy.

## **4.2 Sub-slab Depressurization System Components**

### 4.2.1 Building 9 System

- ) Two sidewall mounted fans connected by manifold piping to vapor extraction points.
- ) Suction Points: The suction points consists of a 5” core boring into the slab through which 1- 2 cubic feet of sub-slab material has been removed. Mechanically suspended 3” SCH 40 PVC pipe has been inserted into the boring and sealed with urethane sealant.

---

<sup>1</sup> U.S. EPA Region 1 Low Stress (low-flow) Purging and Sampling Procedure for the Collection of Groundwater Samples from Monitoring Wells, January 19, 2010.

- J Riser Piping: The riser piping consists of 3” SCH 40 PVC pipe that follows a route from the extraction point to a 4” trunk line, then to the exterior mounted vacuum fan. Weatherproof flashing or sealant has been applied to all penetrations.
- J Exhaust Fans: Exhaust fans has been field selected for specific performance properties. Models: 1) Festa Radon Technologies “Force” producing 4.5 wci at 55 CFM, at 300 watts; 2) RADONAWAY RP-265, producing 2.0 wci at 50 CFM, at 120 watts. Fans have an exterior disconnect switch. Fans are mounted with rubber Fernco couplings, for simplified replacement. No air intakes are present within 10’ of the exhaust points.
- J Instrumentation and Control: There is no centralized instrumentation or control for the SSDS. The fans can be switched either from the adjacent positioned disconnect or at the marked breakers #36 and #42 on the panel box centrally located on the east wall. The exhaust fan systems are equipped with a vacuum indicator mounted in a visible location on a riser pipe per the attached schematic. The indicator consists of an oil filled U-tube style manometer. The indicator can be inspected by observing the level of colored fluid. The indicator is designed primarily to give a simple visual check that vacuum is present in the riser pipe, specifically by observation that the fluid levels on each side of the indicator are not even. Indicator is marked at level observed on March 27, 2017.
- J Sealing measures: Polyurethane sealants have been applied to control joints, floor cracks and slab penetrations to enhance the barrier between sub-slab and ambient air and improve the efficiency of the SSD System. Smoke testing has been employed to guide sealing operations. Materials used include Sika Sikaflex 1c-SL self leveling sealant.

#### 4.2.2 Building 5 and 6 System

- J Five sidewall mounted fans connected to vapor extraction points.
- J Suction Points: The suction points consists of a 10” core boring into the slab directly to crawlspace voids. Mechanically suspended 8” SCH 40 PVC pipe has been inserted into the boring and sealed with urethane sealant.
- J Riser Piping: The riser piping consists of 8” SCH 40 PVC pipe that follows a route from the extraction point to the exterior mounted vacuum fan.
- J Exhaust Fans: Exhaust fans were field selected for specific performance properties. Model: RADONAWAY RP-380 producing 5.0 wci at 350 CFM, at 140 watts. Fans have an exterior disconnect switch. Fans are mounted with rubber Fernco couplings, for simplified replacement.
- J Instrumentation and Control: There is no centralized instrumentation or control for the SSDS. The fans can be switched either from the adjacent positioned disconnect or at the marked breakers on the panel box centrally located. The exhaust fan systems are equipped with a vacuum indicator mounted in a visible location near the riser pipe per the attached schematic. The indicator consists of a dial style manometer, Dwyer Model 5001 or oil filled U-tube. The indicator can be inspected by observing the position of the dial needle or oil level. The indicator is designed primarily to give a simple visual check that vacuum is present in the riser pipe. Indicator is marked at level observed on August 4, 2017.

- J Sealing measures: Polyurethane sealants have been applied to control joints, floor cracks and slab. Smoke testing has been employed to guide sealing operations. Materials used include Sika Sikaflex 1c-SL self leveling sealant.

### **4.3 Sub-slab Depressurization System Operation**

By design, other than the fans and electrical system, the SSDS has relatively few components that could fail and affect operation. The system fans are designed by the manufacturer for a long operational lifespan. At the end of this lifespan, the fan should be replaced, as necessary, with an equivalent or better performance unit. In the event of failure of the SSDS electrical components (breakers, switches, etc.), the component should be repaired or replaced by a licensed electrical contractor. Where necessary, the subcontractor that installed the system (Mitigation Tech) could be contacted to discuss the problem. In the event the subcontractor is not able to assist in fixing the problem, a licensed subcontractor should be contacted to correct the problem and return the SSDS to normal operation. Other SSDS contacts are provided in Section 4.5. A summary of the operation requirements provided in Mitigation Tech's Construction Completion Report is provided below.

- J The fans should be kept in continuous operation.
- J Reset: Fans restart automatically in event of power loss.
- J In the event of unusual fan noise, failure to start, physical damage, or repeated circuit breaker trip, turn fan off and call for service.
- J Regularly inspect system oil filled U-tube type manometers to verify that value, indicated by a mark on the gauge, has not changed significantly from the position of the mark. Gauge is inspected by observing the level of colored fluid.
- J Normal system operation requires unchanged structural conditions. Report any changes in structure, HVAC systems, slab conditions, etc., so that the change can be evaluated for impact on the SSD System.
- J Ensure that a periodic inspection is performed

### **4.4 Soil Vapor Monitoring Program**

#### **4.4.1 Weekly Monitoring**

Weekly monitoring will be conducted as follows:

- J Inspect fan vacuum indicator to verify that value, indicated by a mark on the gauge, has not changed significantly from the position of the mark. Gauge is inspected by observing the level of colored fluid.
- J Record the observed measurement for each fan vacuum indicator on form labeled "SSD System Vacuum Gauge Record". Store all forms in the facility maintenance office.
- J Inspect visible components of SSD system for degraded condition.

#### 4.4.2 Annual Inspection

Annual inspection will be conducted as follows:

- J Conduct a visual inspection of the complete system (e.g., vent fans, piping, warning devices, labeling).
- J Inspect all components for condition and proper operation.
- J Identify and repair any leaks in accordance with Sections 4.3.1(a) and 4.3.4(a) of the NYS DOH VI Guidance (i.e.; with the systems running, use smoke sticks to check for leaks through concrete cracks, floor joints and at the suction points; any leaks will be resealed until smoke is no longer observed flowing through the opening).
- J Inspect the exhaust or discharge point of each exhaust fan to verify that no air intakes have been located within 10 feet.
- J Conduct pressure field extension testing to ensure that the system is maintaining a vacuum beneath the entire slab. Perform a differential pressure reading at least one vacuum test point.
- J Interview appropriate building occupants seeking comments and observations regarding the operation of the system.
- J Confirm that the circuit breakers controlling the circuits on which the soil vapor vent fans operate are labeled "Soil Vapor System."

#### **4.5 Contact Information**

The following is a list of contacts for use regarding the SSDS operation, maintenance and monitoring:

##### **Environmental Consultant**

C&S Engineers, Inc.  
Cody Martin  
141 Elm Street  
Buffalo NY, 14203  
(716) 955-3021

##### **SSDS Installation Contractor**

Mitigation Tech  
Nicholas Mouganis  
55 Shumway Road  
Brockport, NY 14420  
(585) 637-7430

## **4.6 Sampling Methods, Analytical Procedures and Documentation**

### 4.6.1 Sampling Methods

Sampling procedures will be conducted in accordance with the NYSDEC *Sampling Guidelines and Protocols Manual*. Collection of representative samples will include the following procedures:

- ) Ensuring that the sample taken is representative of the material being sampled;
- ) Using proper sampling, handling and preservation techniques;
- ) Properly identifying the collected samples and documenting their collection in field records;
- ) Maintaining chain-of-custody; and
- ) Properly preserving samples after collection.

#### Water Sampling

Groundwater sampling will be conducted in accordance with USEPA guidance for low-flow purging and sampling, as described in **Section 4**.

Water samples will be collected in 40 ml vial and immediately placed on ice. The water will be analyzed for VOC on a standard turnaround time.

In addition to collecting VOC samples for laboratory analysis, groundwater chemistry will be continuously monitored during sample collection. Groundwater chemistry will be monitored for the following:

- ) pH;
- ) Turbidity;
- ) Oxidation Reduction Potential;
- ) Specific Conductance;
- ) Dissolved Oxygen; and
- ) Temperature

#### QA/QC Sampling

**Table 4-1** summarizes the sampling program described in the sections above. Additionally, Quality Assurance/Quality Control (QA/QC) samples will be collected, and the following describes the minimum number of groundwater QA/QC samples.

- ) Trip blank – 1 per shipment
- ) Blind Duplicate – 1 per monitoring event
- ) Matrix Spike/Matrix Spike Duplicate (MS/MSD) – 1 MS / 1 MSD per monitoring event

*Table 4-1: Summary of Estimated Sampling*

<i>Sample Type</i>	<i>Matrix</i>	<i>Estimated Samples (one sample event)</i>	<i>Estimated Samples (total – 5 years)</i>	<i>Purpose</i>
Groundwater	Water	11	55	Characterization
Duplicate Groundwater	Water	1	5	QA/QC (VOC Only)
MS/MSD –Aq.	Water	1/1	5/5	QA/QC (VOC Only)
<b>Total</b>		<b>14</b>	<b>70</b>	

#### 4.6.2 Analytical Procedures

##### Laboratory Analysis

Laboratory analysis will be conducted by a third-party laboratory that is accredited by the NYSDOH Environmental Laboratory Accreditation Program (ELAP). Laboratory analytical methods will include the most current NYSDEC Analytical Services Protocol (ASP).

Groundwater samples sent to a certified laboratory will be analyzed in accordance with EPA SW-846 methodology for Target Compound List for Volatile Organic Compounds (USEPA Method 8260) and Chloride (USEPA Method 9251).

#### 4.6.3 Documentation

##### Custody Procedures

As outlined in NYSDEC *Sampling Guidelines and Protocols*, a sample is in custody under the following conditions:

- ) It is in your actual possession;
- ) It is in your view after being in your physical possession;
- ) It was in your possession and then you locked or sealed it up to prevent tampering; or
- ) It is in a secure area.

The environmental professional will maintain all chain-of-custody documents that will be completed for all samples that will leave the Site to be tested in the laboratory.

## **5 HEALTH AND SAFETY**

A Health and Safety Plan (HASP) was prepared that details procedures for maintaining safe working conditions and minimizing the potential for exposure to hazardous material. The HASP is provided in **Appendix B**.



## **6 REPORTING**

Monitoring Reports will be submitted to NYSDEC annually. The Monitoring Reports will include:

- ) Analytical results and appropriate QA/QC data
- ) Hydraulic monitoring data
- ) An evaluation of the effectiveness of the Remedial Action
- ) Recommendations for program revisions, if appropriate

An Annual Periodic Review Report will also be submitted and will include:

- ) Monitoring Plan Compliance Report
- ) An evaluation of the performance, effectiveness and protectiveness of the Remedial Action
- ) Institutional and Engineering Controls Compliance Report
- ) Operation and Maintenance Compliance Report
- ) Recommendations for program revisions, if appropriate


## **7 SCHEDULE**

The schedule for Site work is as follows:

- ) Initiating Groundwater Sampling Event:
  - o Within 30 days of NYSDEC approval of this Work Plan.
- ) Groundwater Monitoring:
  - o Annually for five years.
  - o After five years, JCC, C&S and the NYSDEC will discuss the status of the OM&M Plan.
- ) Reporting:
  - o Periodic Review / Monitoring Report will be submitted annually starting 15 months after approval of the Work Plan.

# FIGURES

f:\Project\30 - Jamestown Container\environmental\CADD\GIS\Sheet Files\FIGURE 1 HISTORIC AND EXISTING SITE FEATURES.dwg




**LEGEND**


- MONITORING WELL
- ⊠ SURFACE WATER SAMPLE LOCATION
- BOREHOLE
- ⊞ SURFACE SOIL SAMPLE LOCATION
- ▲ PURGE WELL
- △ DRYWELL

**NOTES**

1. Drawing from CRA "Final Supplemental Remedial Investigation Report/Focused Feasibility Study," Figure 5.1: Sample Locations, 2001.



**C&S COMPANIES**  
 C&S Engineers, Inc.  
 141 Elm Street.  
 Buffalo, New York 14203  
 Phone: 716-847-1630  
 Fax: 716-847-1454  
 www.cscos.com



**FORMER DOWCRAFT FACILITY  
 GROUNDWATER REMEDIATION  
 FALCONER, NEW YORK**

MARK	DATE	DESCRIPTION

REVISIONS

MARK	DATE	DESCRIPTION


PROJECT NO: N30.001.001  
 DATE: MAY 28, 2015  
 DRAWN BY: C. MARTIN  
 DESIGNED BY: C. MARTIN  
 CHECKED BY: M. COLMERAUER

NO ALTERATION PERMITTED HEREON EXCEPT AS PROVIDED UNDER SECTION 7209 SUBDIVISION 2 OF THE NEW YORK EDUCATION LAW

**HISTORIC AND  
 EXISTING SITE  
 FEATURES**

**FIGURE 1**

f:\Project\30 - jamestown container\environmental\CADD-GIS\Sheet Files\FIGURE 2 GROUNDWATER MONITORING.dwg




**LEGEND**

- MONITORING WELL
- HISTORIC BUILDINGS (DEMOLISHED)
- MONITORING WELL TO BE SAMPLED

**NOTES**

1. Drawing from CRA "Final Supplemental Remedial Investigation Report/Focused Feasibility Study," Figure 5.1: Sample Locations, 2001.



C&S Engineers, Inc.  
 141 Elm Street  
 Buffalo, New York 14203  
 Phone: 716-847-1630  
 Fax: 716-847-1454  
 www.cscos.com

**FORMER DOWCRAFT FACILITY  
 GROUNDWATER REMEDIATION**

**FALCONER, NEW YORK**

MARK	DATE	DESCRIPTION
REVISIONS		
		PROJECT NO: N30.001.001
		DATE: MAY 28, 2015
		DRAWN BY: C. MARTIN
		DESIGNED BY: C. MARTIN
		CHECKED BY: M. COLMERAUER
NO ALTERATION PERMITTED HEREON EXCEPT AS PROVIDED UNDER SECTION 7209 SUBDIVISION 2 OF THE NEW YORK EDUCATION LAW		

**GROUNDWATER  
 MONITORING**

**FIGURE 2**

# APPENDICES

**APPENDIX A**  
**SUB-SLAB DEPRESSURIZATION SYSTEM WORK PLANS**



**C&S Companies**

141 Elm Street  
Suite 100  
Buffalo, NY 14203  
p: (716) 847-1630  
f: (716) 847-1454  
www.cscos.com

January 12, 2017

David Szymanski  
Department of Environmental Conservation  
Division of Environmental Remediation  
270 Michigan Avenue  
Buffalo, New York 14203

*Re: Soil Vapor Mitigation System Work Plan  
Former Dowcraft Facility, Falconer, New York*

Mr. Szymanski:

C&S Engineers (C&S) is providing New York State Department of Environmental Conservation (NYSDEC) a work plan for the installation of a sub-slab depressurization system by Mitigation Tech with C&S oversight at former Dowcraft Facility in Falconer, New York.

**I. PROJECT UNDERSTANDING**

The Former Dowcraft Site is located at 65 South Dow Street in Falconer, New York and occupies approximately 2.2 acres of land situated immediately east of South Dow Street and approximately 100 feet south of the Chadakoin River. The Jamestown Container Company currently owns the Dowcraft site. The JCC primary manufacturing building is situated on the northern portion of the Site, adjacent to the Chadakoin River and a smaller structure (Building 9) is located on the southern portion of the Site.

Based on the presence of the VOC plume proximal to or under the site building(s), the NYSDOH requested the performance of a Soil Vapor Intrusion (SVI) study to evaluate potential impacts to indoor air quality. On November 2, 2015, Centek Laboratories performed the SVI sampling with the assistance of JCC maintenance staff. A total of nine sub-slab samples (SS-1 to SS-9) and nine indoor air samples (IA-1 to IA-9) were installed within the main building and Building #9. Sub-slab air samples indicate that TCE contaminated soil vapor has impacted the subsurface underneath the main JCC Buildings #5, #6 and #9. After review of the SVI study, the New York State Department of Health (NYSDOH) requires the installation of a mitigation system address soil vapor concerns.

**II. SCOPE OF WORK**

This document presents a Work Plan that consists of the installation and operation of a sub-slab depressurization system (SSDS) that is designed to mitigate the migration or potential migration of sub surface vapors into the building interiors. The subject area is the foundation footprint of Buildings #5, #6 and #9 of Jamestown Container Companies – 65 South Dow St., Falconer, NY 14733. The SSDS is intended to protect the occupants of the subject area and is not intended to remove or diminish the source of the contamination. After start-up, demonstration of SSDS effectiveness will be confirmed and thereafter, a program of periodic maintenance and monitoring will be proposed.

### **III. OBJECTIVES**

This work plan was developed by Mitigation Tech in general accordance with the NYS DOH document, “Guidance for Evaluating Soil Vapor Intrusion in the State of New York, October 2006”. The performance objective of the SSDS is to create and maintain a minimum negative pressure differential of .002 inches of water column (wci) below certain concrete slabs which function as boundaries between subject area sub-slab space and occupied interior space. In the case of Building #9, this includes the entire building footprint. In the cases of Buildings #5 and #6, several complicating factors (see sec 3.2 below) are present and a specific area of vacuum influence is not defined as part of this proposal. Rather, reasonably scaled soil vapor intrusion mitigation systems are proposed that would furnish substantial depressurization and ventilation focused along the interior southern walls of #5 & #6. This would constitute a line of defense to intercept soil vapor migrating from the south. The exact northern boundary of the pressure extension field cannot be predicted prior to construction except by elaborate simulation, expensive enough as to suggest construction of a partial system as an alternative.

We therefore recommend a partial approach to function like a permanent pilot study, the effect of which could be ascertained by interim testing. If further post-construction mitigation is desired, additional measures at additional expense would further extend the pressure field. We would specify these measures exactly based on information obtained during the first phase. We have proposed this strategy because it provides a reasonable response to the degree of known contamination and may well be sufficient by itself. In the event testing shows that additional measures are required, such measures would be incremental to work already performed and therefore no work done under the first phase would be inappropriate or wasteful.

### **IV. WORK PLAN DESIGN AND SPECIFICATIONS**

Work descriptions are based on certain assumptions identified herein and are subject to modification based on further field observations and measurements before and during construction. In the interest of achieving efficiency of design, this Work Plan is presented on a “Design/Build” basis which allows for adjustment to quantity, type and placement of system components. Adjustments are informed by analysis of data continuously obtained during construction.

#### **A. Pre-design Communication Testing and Cost Factors**

The enclosed system configuration is informed by a general building assessment and sub-slab air communication testing performed August 19, 2016 deemed necessary to determine the most efficient system configuration. Included were interviews of key site personnel and document review, although no foundation plans were available. The test procedure included drilling into the concrete at likely suction cavity locations and applying a vacuum to simulate operation of an SSDS fan. Small diameter test holes were established to measure vacuum influence. The enclosed design is a result of weighing key elements (fan type, suction point location, pipe diameter, etc.) against the cost of different construction techniques and materials.

Also included was assessment of the confined space beneath buildings #5 and #6. There is a network of tunnel like structures supporting the floor, some backfilled and some with open voids. In some cases, the voids taper down to less than a foot. Standing water, large scale debris and other obstacles to work are present. The effect of these structures is to create a dense grid of grade beams that effectively restrict airflow due to compartmentalization. As a consequence, comprehensive depressurization would involve either a very dense network of suction cavities or trenching in the main floor of the building.

A further complicating factor is the continuous operation of Cyclone type rooftop vacuum systems. These systems collect scraps of cardboard generated during production and are always running during plant



operation. They create a vacuum in the building by generating air flow exhaust on the order of 5000 CFM. These systems introduce high rate of building air exchange and also potentially interfere with the operation of sub slab depressurization systems.

## **B. Scope of Work**

The Scope of Work is to furnish and install multi-point active sub-slab depressurization systems consisting of high performance exhaust blower and suction cavity network, combined with sealing of slab openings. The Scope of Work for Building #9 is based on the minimum construction necessary to achieve the design objective of creating a minimum .002 wci pressure differential at all areas of the sub-slab. The Scope of Work for Building #5 and #6 is to create sub-slab depressurization or ventilation in the southern section of the buildings. At conclusion, documentation will be provided showing the pressure field extension values. The system configuration is subject to change based on field observations made during construction.

### **Furnish and Install:**

#### **Building 9**

- J (1) OBAR GBR 76 or 89 high performance radial blower [or as indicated by field testing], roof mount or sidewall mount on south side, to provide sub-slab depressurization via 4" schedule 40 PVC trunk line to conduct soil vapor from riser pipes to exhaust fan roof exhaust, with penetration through main roof deck; with mounting frame and rubber connector fittings.
- J (6) Suction points, with risers surface mounted at alternating columns on south wall, 3" Schedule 40 PVC pipe; add suction cavities where necessary to achieve minimum performance objective.

#### **Building 5**

- J (1) OBAR GBR 76 or 89 high performance radial blower [or as indicated by field testing], roof mount or sidewall mount on south side, to provide sub-slab depressurization via 4" schedule 40 PVC trunk line to conduct soil vapor from riser pipes to exhaust fan roof exhaust, with penetration through main roof deck; with mounting frame and rubber connector fittings.
- J (8) Suction points, with risers surface mounted on south wall, 3" Schedule 40 PVC pipe.

#### **Building 6**

- J (1) OBAR GBR 76 or 89 high performance radial blower [or as indicated by field testing], roof mount or sidewall mount on south side, to provide sub-slab depressurization via 4" schedule 40 PVC trunk line to conduct soil vapor from riser pipes to exhaust fan roof exhaust, with penetration through main roof deck; with mounting frame and rubber connector fittings
- J (5) Suction points, with risers surface mounted on south wall or at office partitions, 3" Schedule 40 PVC pipe

#### **Common Elements**

- J Continuous building assessment and sub-slab vacuum measurement to optimize design
- J Pre-construction consultation to obtain approval for component placements
- J All interior pipe SCH 40 PVC with appropriate metal hangers, riser clamps, and additional accessories to properly attach components directly to structural members; sloped as required; routing to avoid interference with other building systems
- J Fire stop devices and other fire code compliance measures
- J Suction cavities to consist of approximately 1 cu. ft. excavated material in sub-slab, with urethane seal; access hole to suction cavity by 5" core drill or hand drill; trenching around footers where required, with concrete restoration

- J Proportioning valves for suction risers where required
- J All exhaust points minimum 10' from any air intakes
- J Exterior-interior penetrations shall have appropriate sealing systems
- J Mobilization and Demobilization per work shift, with daily temporary restorations and basic dust control measures
- J Exterior switch and Sealtight and/or MC conduit from fan housing to nearest electrical panel; extra cost if panel has insufficient capacity; final panel hookup by others at other's expense
- J Vacuum indicator, (1) oil filled U-tube manometer or dial type Magnehelic vacuum gauge; and audible low pressure alarm at location TBD
- J Urethane sealant at slab joints, accessible cracks and penetrations; backer where necessary
- J Horizontal pipe at highest practicable height, with metal bracketing, sloped as required, with valves or restrictor plates as required
- J Consult with occupant to minimize disruption to operations and provide access to work areas
- J Additional SSDS components necessary to achieve performance objective
- J At completion, perform backdraft testing, label components and provide system description and operating instructions
- J At completion, measure pressure differentials and document
- J Consult with client representatives to develop operation, maintenance and periodic inspection plan
- J Two-year warranty; labor, installed components and sub-slab depressurization to objective (or greater)

#### **C. Post Installation Pressure Field Extension Testing**

A digital micromanometer will be used to measure pressure differentials and values will be recorded on a floor plan. All test holes will be repaired with urethane caulk (MSDS available) applied over a closed cell backer rod. Smoke tubes will be used to identify floor cracks and other openings to the sub-slab that could "short circuit" the pressure field. Backdrafting testing will be performed.

#### **D. IRM Construction Completion Report**

At conclusion of construction, a Construction Completion Report (CCR) will be submitted. This report will include an as-built sketch or an overlay of client furnished building drawings, showing SSDS locations and components. The CCR will include measurements of created sub-slab to ambient air static pressure differentials, detailed descriptions of SSDS components, and post-installation sampling results.

An Operations, Maintenance, and Monitoring (OM&M) Plan will be submitted with the CCR. The OM&M Plan will be provided to the owner and occupants to facilitate their understanding of the system's operation, maintenance and monitoring.

#### **E. Maintenance and Monitoring**

Future maintenance and monitoring will be proposed to verify system effectiveness by inspection procedures and via differential pressure measurements. The monitoring will be performed annually until a less-frequent monitoring frequency is approved. In addition, non-routine maintenance may be conducted should it appear that the SSDS has reduced its effectiveness due to malfunction, renovation, or other unplanned circumstance.

### **V. SCHEDULE**

Installation of the soil vapor system can begin immediately once the NYSDOH approves the work plan. Installation will take 45 – 60 days to complete.

NYSDEC  
January 12, 2017  
Page 5

Should you have any questions regarding this work plan or the information contained herein, please feel free to contact me at (716) 847-1630.

Sincerely,

C&S ENGINEERS, INC.

A handwritten signature in blue ink, appearing to read "Cody A. Martin".

Cody Martin  
Environmental Scientist

A handwritten signature in blue ink, appearing to read "Daniel E. Riker".

Daniel E. Riker, P.G.  
Managing Geologist

Enclosed: Sub-slab Depressurization System Map

F:\PROJECT\N30 - JAMESTOWN CONTAINER\N30001001 - JAMESTOWN  
CONTAINER\CORRESPONDENCE\SOIL VAPOR MITIGATION SYSTEM WORK Plan.docx





**C&S Companies**

141 Elm Street  
Suite 100  
Buffalo, NY 14203  
p: (716) 847-1630  
f: (716) 847-1454  
www.cscos.com

April 6, 2017

David Szymanski  
Department of Environmental Conservation  
Division of Environmental Remediation  
270 Michigan Avenue  
Buffalo, New York 14203

*Re: Building 5 and 6 Revised Soil Vapor Mitigation System Work Plan  
Former Dowcraft Facility, Falconer, New York*

Mr. Szymanski:

C&S Engineers (C&S) and Mitigation Tech offer an alternative approach to mitigating soil vapor impacts on Buildings 5 and 6 at the Jamestown Container Company (JCC) facility in Falconer, New York. On February 8, 2017 the New York State Department of Environmental Conservation (NYSDEC) approving C&S's work plan for the installation of sub-slab depressurization systems (SSDS) in Buildings 5, 6 and 9. On March 24, 2017, the SSDS for Building 9 was installed according to the approved work plan.

Buildings 5 and 6 are a particular challenge for installing the approved SSDS due to multiple factors that were presented to the NYSDEC and the New York State Department of Health (NYSDOH) during their site visit on March 28, 2017. These factors include the following:

- ) The high rate of air exchange within the building from the continuous operation of the Cyclone rooftop vacuum systems;
- ) Confined spaces underneath the majority of the floor within the building that are either open or partially backfilled with large debris; and
- ) Network of tunnel-like structures or arches supporting the floor.

Due to these constraining factors associated with the construction and use of Buildings 5 and 6, the SSDS designs within these buildings have been continually re-evaluated by Mitigation Tech to achieve reasonable performance goals for mitigating soil vapor impacts.

As discussed on March 28<sup>th</sup>, C&S and Mitigation Tech propose to mitigate soil vapor beneath the sub-slab of Buildings 5 and 6 using targeted SSDS in areas not impeded by sub-slab obstacles and the installation of a crawl space ventilation system in areas with sub-slab obstacles. The size and location of the SSDS will be determined in the field through sub-slab air communication testing prior to installation. The crawl space ventilation system (CVS) consists of two high air flow blowers located on the perimeter of Building 6. A detailed description of this revised system, developed by Mitigation Tech, for Buildings 5 and 6 is attached to this letter.

We request that NYSDEC and NYSDOH review the attached revised work plan for Buildings 5 and 6. As requested by the NYSDOH for the previously approved work plan, indoor air analytical sampling will be conducted after the SSDS / CVS is operational. These samples will assess the systems' impact on indoor air quality. A total of 9 indoor air locations and one outdoor air location will be sampled to evaluate indoor air quality. Future indoor air monitoring events will use the same locations to collect samples during the operation of the SSDS / CVS.

NYSDEC  
April 6, 2017  
Page 2

Should you have any questions regarding this work plan or the information contained herein, please feel free to contact me at (716) 847-1630.

Sincerely,

C&S ENGINEERS, INC.



Cody Martin  
Environmental Scientist



Daniel E. Riker, P.G.  
Managing Geologist

Enclosed: Mitigation Tech Revised Work Plan

F:\PROJECT\N30 - JAMESTOWN CONTAINER\N30001001 - JAMESTOWN  
CONTAINER\CORRESPONDENCE\BUILDING 5 AND 6 REVISED Soil Vapor Mitigation Work  
Plan.docx

---

# mitigation tech *vapor intrusion specialists*

April 5, 2017

Mr. Cody Martin  
Project Manager  
C & S Companies  
141 Elm Street, Suite 100  
Buffalo, NY 14203  
Via email: *Cody Martin* <*cmartin@cscos.com*>

Re: Jamestown Container Companies – 65 South Dow St., Falconer, NY 14733  
Revised Work Plan

Dear Mr. Martin,

Based additional building investigation and on our recent meeting with representatives of NYS DEC, we submit the following revised work plan:

## **1.0 Introduction**

Soil vapor containing chlorinated volatile organic compounds has been detected at or near this site. This document presents a Work Plan that consists of the installation and operation of both a sub-slab depressurization system (SSDS) and a Crawlspace Ventilation System (CVS) that are designed to mitigate the migration or potential migration of sub surface vapors into the building interiors. The subject area is the foundation footprint of Buildings #5 and #6 of Jamestown Container Companies – 65 South Dow St., Falconer, NY 14733. The SSDS and CVS are intended to protect the occupants of the subject area and are not intended to remove or diminish the source of the contamination. After start-up, system effectiveness will be assessed and thereafter, a program of periodic maintenance and monitoring will be proposed. It is expected that oversight of construction, confirmation of effectiveness and post mitigation air sampling will be provided by *C & S Companies* under separate contract and at additional expense.

## **2.0 Objectives**

This work plan was developed in general accordance with the NYS DOH document, “Guidance for Evaluating Soil Vapor Intrusion in the State of New York, October 2006”. The performance objective of the SSDS is to create and maintain a minimum negative pressure differential of .002 inches of water column (wci) below the southernmost concrete slab sections of Building #5, which function as boundaries between subject area sub-slab space and occupied interior space. The performance objective of the CVS is to create continuous air exchange with outside air in the Building #6 crawlspace beneath the ground level concrete slab.

Both building #5 and #6 are characterized mostly by systems of sub-slab structural arches and grade beams crisscrossing in a north to south and east to west pattern.

In the case of Building #5, extensive backfilling has occurred over time, mostly via concrete patch, so that soil is present immediately below the surface. Four east to west grade beams define five compartments. A reasonably scaled soil vapor intrusion mitigation system is proposed that would furnish depressurization in the southernmost sub-slab compartment bounded by Buildings # 4 and #6.

April 5, 2017

Page 2

This would constitute a line of defense to intercept soil vapor migrating from the south. Some limited depressurization may be created north of the first grade beam. The exact northern boundary of the pressure extension field cannot be predicted prior to construction of the proposed system.

In the case of Building #6, several complicating factors (see sec 3.2 below) are present and the construction of an SSDS is judged to be impracticable. We judge that most of the sub-space of Building #6 is in essence a crawlspace and that ventilation is the most appropriate strategy to divert vapors from the building interior. A portion of Building #6 that includes the office area does not have a crawlspace, and SSDS is proposed for that area.

Therefore this proposal advocates a mixed and balanced soil vapor intrusion mitigation strategy, wherein measures most likely to yield good outcomes efficiently are applied first. If desired, additional measures at additional expense would further mitigate vapor intrusion. We would specify these measures exactly based on information obtained during the first phase. We have proposed this strategy because it provides a reasonable response to the degree of known contamination and may well be sufficient by itself. In the event testing shows that additional measures are required, such measures would be incremental to work already performed and therefore no work done under this proposed phase would be inappropriate or wasteful.

### **3.0 Work Plan Design and Specifications**

#### **3.1 Overview**

Work descriptions are based on certain assumptions identified herein and are subject to modification based on further field observations and measurements before and during construction. In the interest of achieving efficiency of design, this Work Plan is presented on a "Design/Build" basis which allows for adjustment to quantity, type and placement of system components. Adjustments are informed by analysis of data continuously obtained during construction.

#### **3.2 Pre-design Communication Testing**

The enclosed system configuration is informed by a general building assessment and sub-slab air communication testing performed August 19, 2016 and subsequently, deemed necessary to determine the most efficient system configuration. Included were interviews of key site personnel, document and historical photograph review, although no foundation plans were available. The test procedure (Building #5) included drilling into the concrete at likely suction cavity locations and applying a vacuum to simulate operation of an SSDS fan. Small diameter test holes were established to measure vacuum influence. The enclosed design is a result of weighing key elements (fan type, suction point location, pipe diameter, etc.) against the cost of different construction techniques and materials.

Also included was assessment of the confined space beneath a small portion of Building #5 and Building #6. There is a network of tunnel like structures supporting the floor, some partially backfilled and some with open voids. In some cases, the voids taper down to less than a foot. Standing water, silt, large scale debris and other obstacles to work are present. The floor of this space was observed to be difficult to access and in many cases degraded. As a consequence, depressurization of the sub-slab of the confined space is judged to be impracticable.

Another factor is the continuous operation of *Cyclone* type rooftop vacuum systems. These systems collect scraps of cardboard generated during production and are always running during plant operation. They create a vacuum in the building by generating air flow exhaust on the order of 5000 CFM. These systems introduce high rate of building air exchange and also potentially interfere with the operation of



sub-slab depressurization systems. Compensation for this effect includes establishment and maintenance of secure boundaries between ambient and sub-slab air.

### 3.3 Scope of Work

The Scope of Work is to furnish and install 1) a multi-point active sub-slab depressurization system in Building #5 and a crawl space ventilation system in Building #6. At conclusion, documentation will be provided showing the pressure field extension or air exchange values. The system configuration is subject to change based on field observations made during construction.

#### **Furnish and Install:**

- **Building 5 - east to west space defined by south perimeter wall and southernmost east to west interior footer**
- (1) OBAR GBR 76 or 89 high performance radial blower [or as indicated by field testing], roof mount or sidewall mount on south side, to provide sub-slab depressurization via 4" schedule 40 PVC trunk line to conduct soil vapor from riser pipes to exhaust fan roof exhaust; with mounting frame and rubber connector fittings
- (5-6) Suction points, with risers surface mounted on south wall, 3" Schedule 40 PVC pipe
- **Building 6 - (includes influence at Building #5 sump room)**
- (2) RADONAWAY RP-380 high air flow blowers [or as indicated by field testing], roof mount or sidewall mount, to provide sub-slab ventilation via 8" schedule 40 PVC; to conduct soil vapor from riser pipes to exhaust fan roof exhaust, with penetration through main roof deck; with rubber connector fittings
- Sub floor ducting
- Evaluate and repair as necessary, north side foundation vents and openings
- **Building 6 - (includes portion office area not over crawl space)**
- (1) RADONAWAY HS-5000 blower [or as indicated by field testing], roof mount or sidewall mount on south side, to provide sub-slab depressurization via 3" schedule 40 PVC trunk line to conduct soil vapor from riser pipes to exhaust fan roof exhaust; with mounting frame and rubber connector fittings
- (2-3) Suction points, with risers surface mounted on south wall, 3" Schedule 40 PVC pipe
- **Common Elements:**
- Continuous building assessment and sub-slab vacuum measurement to optimize design and meet stated objectives
- Pre-construction consultation to obtain approval for component placements
- All interior pipe SCH 40 PVC with appropriate metal hangers, riser clamps, and additional accessories to properly attach components directly to structural members; sloped as required; routing to avoid interference with other building systems
- Fire stop devices and other fire code compliance measures
- Suction cavities to consist of approximately 1 cu. ft. excavated material in sub-slab, with urethane seal; access hole to suction cavity by 5" core drill or hand drill; trenching around footers where required, with concrete restoration
- Proportioning valves for suction risers where required
- All exhaust points minimum 10' from any air intakes
- Exterior-interior penetrations shall have appropriate sealing systems
- Mobilization and Demobilization per work shift, with daily temporary restorations and basic dust control measures
- Exterior switch and *Sealtight* and/or MC conduit from fan housing to nearest electrical panel; extra cost if panel has insufficient capacity; final panel hookup by others at other's expense

April 5, 2017

Page 4

- Vacuum indicator, (1) per system
- Urethane sealant at slab joints, accessible cracks and penetrations; backer where necessary
- Horizontal pipe at highest practicable height , with metal bracketing, sloped as required, with valves or restrictor plates as required
- Consult with occupant to minimize disruption to operations and provide access to work areas
- At completion, perform backdraft testing, label components and provide system description and operating instructions
- At completion, measure and document pressure differentials and airflow volumes
- Consult with client representatives to develop operation, maintenance and periodic inspection plan
- Two year warranty; labor, installed components and sub-slab depressurization to objective (or greater)

### **3.4 Post Installation Pressure Field Extension Testing**

A digital micromanometer will be used to measure pressure differentials and values will be recorded on a floor plan. All test holes will be repaired with urethane caulk (MSDS available) applied over a closed cell backer rod. Smoke tubes will be used to identify floor cracks and other openings to the sub-slab that could “short circuit” the pressure field. Backdrafting testing will be performed.

### **3.5 General Work Plan Provisions**

- Daily tailgate meeting for safety review
- HAZWOPER trained personnel to perform drilling operations
- PID or Particulate monitoring not included
- Level 4 PPE for on-site personnel
- Procedures to follow site specific HASP

### **3.6 IRM Construction Completion Report**

At conclusion of construction, a Construction Completion Report (CCR) will be submitted. This report will include an as-built sketch or an overlay of client furnished building drawings, showing SSDS locations and components. The CCR will include measurements of created sub-slab to ambient air static pressure differentials, detailed descriptions of SSDS components, and post-installation sampling results.

An Operations, Maintenance, and Monitoring (OM&M) Plan will be submitted with the CCR. The OM&M Plan will be provided to the owner and occupants to facilitate their understanding of the system's operation, maintenance and monitoring. Future maintenance and monitoring will be proposed to verify system effectiveness by inspection procedures and measurements.

Thank you.

Nicholas E. Mouganis EPA listing # 15415-I; NEHA ID# 100722

---

**55 SHUMWAY ROAD, BROCKPORT, NEW YORK, 14420 \* OFFICE/FAX 585-637-7430**

**APPENDIX B**  
**HEALTH AND SAFETY PLAN**

# **Health and Safety Plan**

## **Former Dowcraft Site 65 South Dow Street Falconer, NY**

Site ID # 9-07-020

Prepared by



C&S Engineers, Inc.  
141 Elm Street, Suite 100  
Buffalo, New York 14203

August 2017

## TABLE OF CONTENTS

	<i>page</i>
Section 1 General Information .....	4
Section 2 - Health And Safety Personnel.....	5
2.0 Health and Safety Personnel Designations .....	5
2.1 Project Manager (PM).....	5
2.2 Health and Safety Manager.....	5
2.3 Health and Safety Officer (HSO).....	6
2.4 Emergency Coordinator .....	7
2.5 Site Workers.....	7
Section 3 - Pertinent Site Information .....	7
3.1 Site Location and General History.....	7
Section 5 - Training .....	8
5.1 Site-specific Training.....	8
5.2 Safety Briefings .....	9
Section 6 - Zones .....	9
6.1 Exclusion Zone .....	9
6.2 Contamination Reduction Zone .....	10
6.3 Remediation Zone .....	10
6.4 Support Zone.....	11
Section 7 - Personal Protective Equipment.....	11
7.1 General.....	11
7.2 Personal Protective Equipment – Site Specific.....	13
Section 8 - Monitoring Procedures .....	13
8.1 Monitoring During Site Operations .....	13
8.1.1 Drilling Operations (Monitoring Well Installation and Subsurface Borings) and Test Pit Excavations .....	13
8.1.2 Interim Remedial Measures .....	13
8.2 Action Levels .....	14
8.3 Personal Monitoring Procedures.....	14
Section 9 - Communications.....	14
Section 10 - Safety Considerations For Site Operations.....	14
10.1 General.....	14
10.2 Field Operations.....	15
10.2.1 Intrusive Operations.....	15
10.2.2 Excavations and Excavation Trenching.....	16
Section 11 - Decontamination Procedures .....	16
Section 12 Disposal Procedures .....	17
Section 13 - Emergency Response Procedures.....	17
13.1 Emergency Coordinator .....	17
13.2 Evacuation.....	18
13.3 Potential or Actual Fire or Explosion .....	18
13.4 Environmental Incident (spread or release of contamination).....	18
13.5 Personnel Injury.....	18
13.6 Personnel Exposure.....	19

***Health and Safety Plan***

---

13.7	Adverse Weather Conditions .....	19
13.8	Incident Investigation and Reporting .....	19
Section 14 -	Community Relations .....	19
14.1	Community Health and Safety Plan.....	19
14.1.1	Community Air Monitoring Plan.....	19
Section 15 -	Authorizations .....	19

**FIGURES**

- Figure 1 Site Location
- Figure 2 Site Aerial Photo

**ATTACHMENTS**

- Attachment A – Map and Directions to Hospital

**APPENDICES**

- Appendix A – Excavation/Trenching Guideline
- Appendix B – Guidance on Incident Investigation and Reporting



**SECTION 1 GENERAL INFORMATION**

The Health and Safety Plan (HASP) described in this document will address health and safety considerations for all those activities that personnel employed by C&S Engineers, Inc., may be engaged in during site investigation and remediation work at the Former Dowcraft Site located on 65 South Dow Street in Falconer, Chautauqua County, New York (Site). Figure 1 shows the approximate location of the Site. This HASP will be implemented by the Health and Safety Officer (HSO) during site work.

Compliance with this HASP is required of all C&S personnel who enter this Site. The content of the HASP may change or undergo revision based upon additional information made available to the health, safety, and training (H&S) committee, monitoring results or changes in the technical scope of work. Any changes proposed must be reviewed by the H&S committee.

**Responsibilities**

Project Manager.....	Daniel Riker Phone: (716) 847-1630 Cell: (716) 572-5312
Site Health and Safety Officer.....	Cody Martin Phone: (716) 847-1630 Cell: (716) 864-3752
Emergency Coordinator.....	Cody Martin Phone: (716) 847-1630 Cell: (716) 864-3752
Health and Safety Manager.....	Cody Martin Phone: (716) 847-1630 Cell: (716) 864-3752

**Emergency Phone Numbers**

Emergency Medical Service.....	911
<u>Police</u> : Buffalo Police Department (NYPD).....	911
<u>Hospital</u> : Buffalo General Hospital.....	(716) 859-5600
<u>Fire</u> : Buffalo Fire Department.....	911
National Response Center .....	(800) 424-8802

Poison Control Center .....	(800) 222-1222
Center for Disease Control .....	(800) 311-3435
NYSDEC Region 9 (Buffalo, New York) .....	(716) 851-7220
C&S Engineers .....	(716) 847-1630
Site Superintendent .....	TBD
Project Field Office Trailer .....	(716) 847-1630

## **SECTION 2 - HEALTH AND SAFETY PERSONNEL**

### **2.0 Health and Safety Personnel Designations**

The following information briefly describes the health and safety designations and general responsibilities for this Site.

#### **2.1 Project Manager (PM)**

The PM is responsible for the overall project including the implementation of the HASP. Specifically, this includes allocating adequate manpower, equipment, and time resources to conduct Site activities safely.

#### **2.2 Health and Safety Manager**

- ◆ Has the overall responsibility for coordinating and reporting all health and safety activities and the health and safety of Site Workers.
- ◆ Must have completed, at a minimum, the OSHA 30-Hour Construction Safety Training, and either the 24-Hour training course for the Occasional Hazardous Waste Site Worker or the 40-Hour training course for the Hazardous Waste Operations Worker that meets OSHA 29 CFR 1910.
- ◆ Must have completed the 8-Hour Site supervisor/manager’s course for supervisors and managers having responsibilities for hazardous waste Site operations and management.
- ◆ Directs and coordinates health and safety monitoring activities.
- ◆ Ensures that field teams utilize proper personal protective equipment (PPE).
- ◆ Conducts initial on-site specific training prior to Site Workers commencing work.



- ◆ Conducts and documents daily and periodic safety briefings.
- ◆ Ensures that field team members comply with this HASP.
- ◆ Immediately notifies the Construction Manager (CM) Project Manager and Superintendent of all accident/incidents.
- ◆ Determines upgrading or downgrading of PPE based on Site conditions and/or real time monitoring results.
- ◆ Ensures that monitoring instruments are calibrated daily or as the manufacturer's instructions determine.
- ◆ Reports to the CM Project Manager and Superintendent to provide summaries of field operations and progress.
- ◆ Submits and maintains all documentation required in this HASP and any other pertinent health and safety documentation.

### **2.3 Health and Safety Officer (HSO)**

- ◆ Must be designated to the Health and Safety Manager by each Subcontractor as a Competent Person having, at a minimum, the OSHA 30-Hour Construction Safety Training
- ◆ Must schedule and attend a Pre-Construction Safety Meeting with the Health and Safety Manager to discuss the Subcontractor Safety Requirements and must attend the Weekly Subcontractor Coordination Meeting.
- ◆ Responsible for ensuring that their lower tier contractors comply with project safety requirements.
- ◆ Must make frequent and regular inspections of their work areas and activities and ensure hazards that are under their control are corrected immediately and all other hazards are reported to the Construction Manager's Project Manager and Health and Safety Manager.

- ◆ Must report all work related injuries, regardless of severity, to the Construction Manager's Project Manager and the Health and Safety Manager within 24 hours after they occur.

## **2.4 Emergency Coordinator**

- ◆ The Emergency Coordinator or his on-site designee will, in coordination with Campus Square, LLC., implement the emergency response procedures whenever conditions at the Site warrant such action.
- ◆ The Emergency Coordinator or his on-site designee will be responsible for assuring the evacuation, emergency treatment, emergency transport of C&S personnel as necessary, and notification of emergency response units (refer to phone listing in the beginning of this HASP) and the appropriate management staff.

## **2.5 Site Workers**

- ◆ Report any unsafe or potentially hazardous conditions to the Health and Safety Manager.
- ◆ Maintain knowledge of the information, instructions, and emergency response actions contained in the HASP.
- ◆ Comply with rules, regulations, and procedures as set forth in this HASP, including any revisions that are instituted.
- ◆ Prevent unauthorized personnel from entering work Site.

# **SECTION 3 - PERTINENT SITE INFORMATION**

## **3.1 Site Location and General History**

The Dowcraft Site is located at 65 South Dow Street in Falconer, New York and occupies approximately 2.2 acres of land situated immediately east of South Dow Street and approximately 100 feet south of the Chadakoin River. The Jamestown Container manufacturing building is situated between the Site and the Chadakoin River.

The property was first developed in 1890 as a woolen mill until 1939 when it was converted into

a factory which manufactured steel partitions used for offices. As part of this manufacturing process, a vapor degreaser was used which included the use of chemicals such as trichloroethene (TCE). This work continued until 1999 when the facility was closed, a portion of the Site was demolished, and the property was sold to JCC. Figure 1 presents the Site's location.

*Site History and Suspect Recognized Environmental Conditions*

Chlorinated solvents, primarily, trichloroethene (TCE) and its daughter compounds, were identified as the contaminants of concern (COC) for this Site. TCE is a man-made volatile organic compound used for degreasing metal and electronic parts. Remedial considerations for TCE include its low solubility value and heavy molecular weight. TCE is in a class of chemicals called dense non-aqueous phase liquids (DNAPL) that sink through the water column until they encounter an impermeable barrier.

According to previous environmental reports, the area of former degreaser pit (area of groundwater monitoring wells PW-3 and PW-3R) is a likely source area for the COC plume. The plume originates from the degreaser area and has affected groundwater in the upper and lower sand/gravel layers. The plume extends from the degreaser area to the north, under the JCC building and up to the area of the Chadakoin River. This is an area of approximately one acre. The rate of movement is approximately 2 to 3 feet per year to the north.

Five out of the ten wells that were sampled contained groundwater that exceeded water quality standard for TCE (5 ug/L). Analytical results for TCE in these wells ranged from 7.37 ug/L to 431 ug/L. Other chlorinated compounds, including TCE daughter compounds (cis-1,2-dichloroethene, trans-1,2-dichloroethane and vinyl chloride) were detected in three of the ten wells. The highest concentration of cis-1,2-Dichloroethene was detected in PW-3R (1,990 ug/L). Vinyl chloride was detected in one well, PW-3R, at 861 ug/L.

## **SECTION 5 - TRAINING**

### **5.1 Site-specific Training**

Training will be provided that specifically addresses the activities, procedures, monitoring, and equipment for the Site operations prior to going on site. Training will include familiarization with Site and facility layout, known and potential hazards, and emergency services at the Site, and

details all provisions contained within this HASP. This training will also allow Site Workers to clarify anything they do not understand and to reinforce their responsibilities regarding safety and operations for their particular activity.

## **5.2 Safety Briefings**

C&S project personnel will be given briefings by the HSO on a daily or as needed basis to further assist Site Workers in conducting their activities safely. Pertinent information will be provided when new operations are to be conducted. Changes in work practices must be implemented due to new information made available, or if Site or environmental conditions change. Briefings will also be given to facilitate conformance with prescribed safety practices. When conformance with these practices is not occurring or if deficiencies are identified during safety audits, the project manager will be notified.

## **SECTION 6 - ZONES**

Four types of Site activity zones are identified for the Brownfield investigation activities, including the Exclusion Zone, Contamination Reduction Zone, Remediation Zone and the Support Zone. Prior to commencement of field work a further definition of where these zones will be set up will be established.

### **6.1 Exclusion Zone**

The area where the unexpected condition is discovered would be considered the Exclusion Zone (EZ). All excavation and handling of contaminated materials generated as a result of the discovery of an unexpected condition would take place within the EZ. This zone will be clearly delineated by hay bales, jersey barriers, and/or similar methods. Safety tape may be used as secondary delineation within the EZ. The zone delineation markings may be opened in areas for varying lengths of time to accommodate equipment operation or specific construction activities. The Site Safety Manager/Director may establish more than one EZ where different levels of protection may be employed or where different hazards exist. Site Workers will not be allowed in the EZ without:

- ◆ A buddy (co-worker);
- ◆ Appropriate PPE in accordance with OSHA regulations;

- ◆ Medical authorization; and
- ◆ Training certification in accordance with 29 CFR 1910.120.

## **6.2 Contamination Reduction Zone**

A Contamination Reduction Zone (CRZ) will be established between the EZ and the property limits. The CRZ contains the Contamination Reduction Corridor (CRC) and provides an area for decontamination of Site equipment. The CRZ will be used for general Site entry and egress, in addition to access for heavy equipment and emergency support services. Site Workers will not be allowed in the CRZ without:

- ◆ A buddy (co-worker);
- ◆ Appropriate PPE in accordance with OSHA regulations;
- ◆ Medical authorization; and
- ◆ Training certification in accordance with 29 CFR 1910.120.

In addition, the CRZ will include a Site Worker Cleaning Area that will include a field wash station for Site Workers, equipment, and PPE to allow Site Workers to wash their hands, arms, neck, and face after exiting areas of grossly contaminated soil or hazardous materials. All Site Workers will be required to pass through the Site Worker Cleaning Area and wash their hands and remove any loose fill and soils from their clothing and boots prior to exiting the CRZ.

## **6.3 Remediation Zone**

A Remediated Zone (RZ) will be established in portions of the Site where the remediation has been completed and only general construction work will be performed. Setup of the RZ will consist of implementing several measures designed to reduce the risk of workers' exposure and prevent non-trained workers from entering the non-remediated zone. Non-trained workers will work only in areas where the potential for exposure has been minimized by removal of all hazardous materials. The remediated zone will then be separated from the non-remediated zone by installing and maintaining temporary plywood or other construction fences along the boundary between the two zones. If potentially impacted material is uncovered in the RZ, all non-trained workers will

be removed and the Site Safety Manager/Director will assess the potential risks. If, at any other time, the risk of exposure increases while non-trained workers are present in the RZ, the non-trained workers will be removed. At all times, when non-trained workers are present in the RZ, air monitoring for the presence of VOCs will be conducted in the RZ, as well as at the fence line of the non-remediated zone.

#### **6.4 Support Zone**

The Support Zone (SZ) will be an uncontaminated area that will be the field support area for the Site operations. The SZ will contain the temporary project trailers and provide for field team communications and staging for emergency response. Appropriate sanitary facilities and safety equipment will be located in this zone. Potentially contaminated equipment or materials are not allowed in this zone. The only exception will be appropriately packaged/decontaminated and labeled samples. Meteorological conditions will be observed and noted from this zone, as well as those factors pertinent to heat and cold.

## **SECTION 7 - PERSONAL PROTECTIVE EQUIPMENT**

### **7.1 General**

The level of protection to be worn by field personnel will be defined and controlled by the HSO. Depending upon the type and levels of material present or anticipated at the site, varying degrees of protective equipment will be needed. If the possible hazards are unknown, a reasonable level of protection will be taken until sampling and monitoring results can ascertain potential risks. The levels of protection listed below are based on USEPA Guidelines. A list of the appropriate clothing for each level is also provided.

Level A protection must be worn when a reasonable determination has been made that the highest available level of respiratory, skin, eye, and mucous membrane protection is needed. It should be noted that while Level A provides maximum available protection, it does not protect against all possible hazards. Consideration of the heat stress that can arise from wearing Level A protection should also enter into the decision making process. Level A protection includes:

- ◆ Open circuit, pressure-demand self-contained breathing apparatus (SCBA)
- ◆ Totally encapsulated chemical resistant suit
- ◆ Gloves, inner (surgical type)

- ◆ Gloves, outer, chemical protective
- ◆ Boots, chemical protective

Level B protection must be used when the highest level of respiratory protection is needed, but hazardous material exposure to the few unprotected areas of the body (e.g., the back of the neck) is unlikely. Level B protection includes:

- ◆ Open circuit, pressure-demand SCBA or pressure airline with escape air bottle
- ◆ Chemical protective clothing: Overalls and long sleeved jacket; disposal chemical resistant coveralls; coveralls; one or two piece chemical splash suit with hood
- ◆ Gloves, inner (surgical type)
- ◆ Gloves, outer, chemical protective
- ◆ Boots, chemical protective

Level C must be used when the required level of respiratory protection is known, or reasonably assumed to be, not greater than the level of protection afforded by air purifying respirators; and hazardous materials exposure to the few unprotected areas of the body (e.g., the back of the neck) is unlikely. Level C protection includes:

- ◆ Full or half face air-purifying respirator
- ◆ Chemical protective clothing: Overalls and long-sleeve jacket; disposable chemical resistant coveralls; coveralls; one or two piece chemical splash suit
- ◆ Gloves, inner (surgical type)
- ◆ Gloves, outer, chemical protective
- ◆ Boots, chemical protective

Level D is the basic work uniform. It cannot be worn on any site where respiratory or skin hazards exist. Level D protection includes:

- ◆ Safety boots/shoes
- ◆ Safety glasses
- ◆ Hard hat with optional face shield

Note that the use of SCBA and airline equipment is contingent upon the user receiving special training in the proper use and maintenance of such equipment.

## **7.2 Personal Protective Equipment – Site Specific**

Level D with some modification will be required when working in the work zone on this Site. In addition to the basic work uniform specified by Level D protection, Nitrile gloves will be required when contact with soil or ground water is likely. Hearing protection will be worn when power equipment is used to perform subsurface investigation work. An upgrade to a higher level (Level C) of protection may occur if determined necessary by the HSO.

## **SECTION 8 - MONITORING PROCEDURES**

### **8.1 Monitoring During Site Operations**

All Site environmental monitoring should be accompanied by periodic meteorological monitoring of appropriate climatic conditions.

#### 8.1.1 Drilling Operations (Monitoring Well Installation and Subsurface Borings) and Test Pit Excavations

Monitoring will be performed by the HSO or drilling observer during the conduct of work. A photoionization detector (PID) equipped with a 10.0 eV lamp will be utilized to monitor for the presence of volatile organic vapors within the breathing zone, the borehole, and subsurface samples upon their retrieval. Drill cuttings and excavation spoils will also be monitored by use of the PID. The PID will be field checked for calibration accuracy three times per day (morning, lunch, and end of day). If subsurface conditions warrant, a combustible gas indicator (CGI) with oxygen alarm may also be used to monitor the borehole for the presence of combustible gases. Similar monitoring of fluids produced during well development will also be conducted.

#### 8.1.2 Interim Remedial Measures

If future Interim Remedial Measures (IRM) occurs, monitoring will be performed during excavation and sampling operations when C&S personnel are within the work zone. Although historical information previously obtained at the Site indicates low level of volatile organic vapors and compounds, a photoionization detector (PID) will be used during subsurface activities. If an IRM is performed, the remedial contractor will be required to employ dust control practices during work.



## **8.2 Action Levels**

If readings on the PID exceed 10 ppm for more than fifteen minutes consecutively, then personal protective equipment should be upgraded to Level C. The air purifying respirator used with Level C protective equipment must be equipped with organic vapor cartridges. If readings on the explosive gas meter are within a range of 10%-25% of the LEL then continuous monitoring will be implemented. Readings above 25% of the LEL indicate the potential for an explosive condition. Sources of ignition should be removed and the Site should be evacuated.

## **8.3 Personal Monitoring Procedures**

Personal monitoring shall be performed as a contingency measure in the event that VOC concentrations are consistently above the 10 ppm action level as detected by the PID. If the concentration of VOCs is above this action level, then amendments to the HASP must be made before work can continue at the Site.

# **SECTION 9 - COMMUNICATIONS**

A phone will be located on Site to be utilized by personnel conducting investigation and IRM efforts. Cell phones will be the primary means of communicating with emergency support services/facilities.

# **SECTION 10 - SAFETY CONSIDERATIONS FOR SITE OPERATIONS**

## **10.1 General**

Standard safe work practices that will be followed include:

- ◆ Do not climb over/under drums, or other obstacles.
- ◆ Do not enter the work zone alone.
- ◆ Practice contamination avoidance, on and off-site.
- ◆ Plan activities ahead of time, use caution when conducting concurrently running activities.
- ◆ No eating, drinking, chewing or smoking is permitted in work zones.
- ◆ Due to the unknown nature of waste placement at the Site, extreme caution should be practiced during excavation activities.
- ◆ Apply immediate first aid to any and all cuts, scratches, abrasions, etc.

- ◆ Be alert to your own physical condition. Watch your buddy for signs of fatigue, exposure, etc.
- ◆ A work/rest regimen will be initiated when ambient temperatures and protective clothing create a potential heat stress situation.
- ◆ No work will be conducted without adequate natural light or without appropriate supervision.
- ◆ Task safety briefings will be held prior to onset of task work.
- ◆ Ignition of flammable liquids within or through improvised heating devices (barrels, etc.) or space heaters is forbidden.
- ◆ Entry into areas of spaces where toxic or explosive concentrations of gases or dust may exist without proper equipment is prohibited.
- ◆ Any injury or unusual health effect must be reported to the Site health and safety officer.
- ◆ Prevent splashing or spilling of potentially contaminated materials.
- ◆ Use of contact lenses is prohibited while on site.
- ◆ Beards and other facial hair that would impair the effectiveness of respiratory protection are prohibited if respiratory protection is necessary.
- ◆ Field crew members should be familiar with the physical characteristics of investigations, including:
  - ◆ Wind direction in relation to potential sources
  - ◆ Accessibility to co-workers, equipment, and vehicles
  - ◆ Communication
  - ◆ Hot zones (areas of known or suspected contamination)
  - ◆ Site access
  - ◆ Nearest water sources
- ◆ The number of personnel and equipment in potentially contaminated areas should be minimized consistent with site operations.

## **10.2 Field Operations**

### 10.2.1 Intrusive Operations

The HSO or designee will be present on-site during all intrusive work, e.g., drilling operations, excavations, trenching, and will provide monitoring to oversee that appropriate levels of protection and safety procedures are utilized by C&S Engineers, Inc., personnel. The use of salamanders or other equipment with an open flame is prohibited and the use of protective clothing, especially hard hats and boots, will be required during drilling or other heavy equipment operations.

### 10.2.2 Excavations and Excavation Trenching

Guidance relating to safe work practices for C&S employees regarding excavations and excavating/trenching operation is presented in Appendix A of this HASP.

## **SECTION 11 - DECONTAMINATION PROCEDURES**

Decontamination involves physically removing contaminants and/or converting them chemically into innocuous substances. Only general guidance can be given on methods and techniques for decontamination. Decontamination procedures are designed to:

- ◆ Remove contaminant(s).
- ◆ Avoid spreading the contamination from the work zone.
- ◆ Avoid exposing unprotected personnel outside of the work zone to contaminants.

Contamination avoidance is the first and best method for preventing spread of contamination from a hazardous site. Each person involved in site operations must practice the basic methods of contamination avoidance listed below. Additional precautions may be required in the HASP.

- ◆ Know the limitations of all protective equipment being used.
- ◆ Do not enter a contaminated area unless it is necessary to carry out a specific objective.
- ◆ When in a contaminated area, avoid touching anything unnecessarily.
- ◆ Walk around pools of liquids, discolored areas, or any area that shows evidence of possible contamination.
- ◆ Walk upwind of contamination, if possible.
- ◆ Do not sit or lean against anything in a contaminated area. If you must kneel (e.g., to take samples), use a plastic ground sheet.
- ◆ If at all possible, do not set sampling equipment directly on contaminated areas. Place equipment on a protective cover such as a ground cloth.
- ◆ Use the proper tools necessary to safely conduct the work.

Specific methods that may reduce the chance of contamination are:

- ◆ Use of remote sampling techniques.
- ◆ Opening containers by non-manual means.
- ◆ Bagging monitoring instruments.

- ◆ Use of drum grapplers.
- ◆ Watering down dusty areas.

Equipment which will need to be decontaminated includes tools, monitoring equipment, and personal protective equipment. Items to be decontaminated will be brushed off, rinsed, and dropped into a plastic container supplied for that purpose. They will then be washed with a detergent solution and rinsed with clean water. Monitoring instruments may be wrapped in plastic bags prior to entering the field in order to reduce the potential for contamination. Instrumentation that is contaminated during field operations will be carefully wiped down. Heavy equipment, if utilized for operations where it may be contaminated, will have prescribed decontamination procedures to prevent contaminant materials from potentially leaving the Site. On-site contractors, such as drillers or backhoe operators, will be responsible for decontaminating all construction equipment prior to demobilization.

## **SECTION 12 DISPOSAL PROCEDURES**

All discarded materials, waste materials, or other objects shall be handled in such a way as to reduce or eliminate the potential for spreading contamination, creating a sanitary hazard, or causing litter to be left on-site. All potentially contaminated materials, e.g., clothing, gloves, etc., will be bagged or drummed as necessary and segregated for proper disposal. All contaminated waste materials shall be disposed of as required by the provisions included in the contract and consistent with regulatory provisions. All non-contaminated materials shall be collected and bagged for appropriate disposal. Investigation derived waste will be managed consistent with the work plan for this Site and DER-10 Technical Guidance for Site Investigation and Remediation dated May 2010.

## **SECTION 13 - EMERGENCY RESPONSE PROCEDURES**

As a result of the hazards at the Site, and the conditions under which operations are conducted, there is the possibility of emergency situations. This section establishes procedures for the implementation of an emergency plan.

### **13.1 Emergency Coordinator**

*Emergency Coordinator: ..... Cody Martin ..... Work Phone: (716) 847-1630*

The Emergency Coordinator or his on-site designee will, in concert with Campus Square LLC, implement the emergency response procedures whenever conditions at the Site warrant such action. The Emergency Coordinator or his on-site designee will be responsible for assuring the evacuation, emergency treatment, emergency transport of C&S personnel as necessary, and notification of emergency response units (refer to phone listing in the beginning of this HASP) and the appropriate management staff.

### **13.2 Evacuation**

In the event of an emergency situation, such as fire, explosion, significant release of toxic gases, etc., all personnel will evacuate and assemble in a designated assembly area. The Emergency Coordinator or his on-site designee will have authority to contact outside services as required. Under no circumstances will incoming personnel or visitors be allowed to proceed into the area once the emergency signal has been given. The Emergency Coordinator or his on-site designee must see that access for emergency equipment is provided and that all ignition sources have been shut down once the emergency situation is established. Once the safety of all personnel is established, the Fire Department and other emergency response groups will be notified by telephone of the emergency.

### **13.3 Potential or Actual Fire or Explosion**

Immediately evacuate the Site and notify local fire and police departments, and other appropriate emergency response groups, if LEL values are above 25% in the work zone or if an actual fire or explosion has taken place.

### **13.4 Environmental Incident (spread or release of contamination)**

Control or stop the spread of contamination if possible. Notify the Emergency Coordinator and the Project Manager. Other appropriate response groups will be notified as appropriate.

### **13.5 Personnel Injury**

Emergency first aid shall be applied on-site as necessary. Then, decontaminate (en route if necessary) and transport the individual to nearest medical facility if needed. The ambulance/rescue squad shall be contacted for transport as necessary in an emergency. The directions to the hospital are shown in Section 1 of this HASP and a map is shown in Attachment A.

### **13.6 Personnel Exposure**

- ◆ *Skin Contact:* Use copious amounts of soap and water. Wash/rinse affected area thoroughly, and then provide appropriate medical attention. Eyes should be thoroughly rinsed with water for at least 15 minutes.
- ◆ *Inhalation:* Move to fresh air and/or, if necessary, decontaminate and transport to emergency medical facility.
- ◆ *Ingestion:* Decontaminate and transport to emergency medical facility.
- ◆ *Puncture Wound/Laceration:* Decontaminate, if possible, and transport to emergency medical facility.

### **13.7 Adverse Weather Conditions**

In the event of adverse weather conditions, the HSO will determine if work can continue without sacrificing the health and safety of field workers.

### **13.8 Incident Investigation and Reporting**

In the event of an incident, procedures discussed in the Medical Emergency/Incident Response Protocol, presented in Appendix B of this HASP, shall be followed.

## **SECTION 14 - COMMUNITY RELATIONS**

### **14.1 Community Health and Safety Plan**

#### 14.1.1 Community Air Monitoring Plan

Efforts will be taken to complete field work in a manner which will minimize the creation of airborne dust or particulates. Under dry conditions, work areas may be wetted to control dust. During periods of extreme wind, intrusive field work may be halted until such time as the potential for creating airborne dust or particulate matter as a result of investigation activities is limited.

## **SECTION 15 - AUTHORIZATIONS**

Personnel authorized to enter the Site while operations are being conducted must be approved by the HSO. Authorization will involve completion of appropriate training courses, medical examination requirements, and review and sign-off of this HASP. No C&S personnel should enter



the work zone alone. Each site visitor should check in with the HSO or Project Manager prior to entering the work zones.

# **FIGURE 1**

## ***SITE LOCATION MAP***







C&S Engineers, Inc.  
 90 Broadway  
 Buffalo, New York 14203  
 Phone: 716-847-1630  
 Fax: 716-847-1454  
 www.cscos.com

3

JAMESTOWN CONTAINER CORP

FALCONER, NEW YORK

MARK	DATE	DESCRIPTION
REVISIONS		
PROJECT NO:		N30.001.001
DATE:		August 21, 2017
DRAWN BY:		C. Martin
DESIGNED BY:		C. Martin
CHECKED BY:		

NO ALTERATION PERMITTED HEREON EXCEPT AS PROVIDED UNDER SECTION 7209 SUBDIVISION 2 OF THE NEW YORK EDUCATION LAW

SITE  
LOCATION MAP


FIGURE 1

# **FIGURE 2**

***SITE AERIAL PHOTO***




Path: F:\Project\W30 - Jamestown Container\30001001 - Jamestown Container\Environmental\CADD-GIS\GIS\Projects\Untitled.mxd



Source: Esri, DigitalGlobe, GeoEye, Earthstar Geographics, CNES/Airbus DS, USDA, USGS, AEX, Getmapping, Aerogrid, IGN, IGP, swisstopo, and the GIS User Community, Esri, HERE, DeLorme, MapmyIndia, © OpenStreetMap contributors, and the GIS user community

Legend

- Existing Building
- Historic Buildings
- Groundwater Contours
- Rail Road



**C&S COMPANIES**  
 C&S Engineers, Inc.  
 90 Broadway  
 Buffalo, New York 14203  
 Phone: 716-847-1630  
 Fax: 716-847-1454  
 www.cscos.com

**3**

JAMESTOWN CONTAINER CORP

FALCONER, NEW YORK

MARK	DATE	DESCRIPTION
REVISIONS		
PROJECT NO:		N30.001.001
DATE:		August 21, 2017
DRAWN BY:		C. Martin
DESIGNED BY:		C. Martin
CHECKED BY:		
NO ALTERATION PERMITTED HEREON EXCEPT AS PROVIDED UNDER SECTION 7209 SUBDIVISION 2 OF THE NEW YORK EDUCATION LAW		

SITE  
LOCATION MAP

FIGURE 1

# **ATTACHMENT A**

***MAP TO HOSPITAL***





**A** 65 S Dow St, Falconer, NY 14733

**10 min, 3.0 mi**

**B** Upmc Chautauqua Wca Hospital, 51 Glasgow Ave, Jamestown, NY 14701


Light traffic (9 min without traffic)  
Via RT-394

Type your route notes here


**A** 65 S Dow St, Falconer, NY 14733

↑	1. Depart <b>S Dow St</b> toward W Everett St	0.2 mi
↶	2. Turn <b>left</b> onto <b>RT-394 / W Main St</b> Pass 7-Eleven in 1.1 mi	1.9 mi
↑↑	3. Keep <b>left</b> onto <b>E 2nd St</b> KFC on the corner	0.1 mi
↶	4. Turn <b>left</b> onto <b>Foote Ave</b>	0.2 mi
↷	5. Turn <b>right</b> onto <b>Harrison St</b>	0.3 mi
↑	6. Road name changes to <b>W Harrison St</b>	0.2 mi
↑↑	7. Keep <b>right</b> onto <b>Steele St</b>	72 ft
↶	8. Turn <b>left</b> onto <b>Glasgow Ave</b>	0.2 mi
	9. Arrive at <b>Glasgow Ave</b> on the left The last intersection is Steele St If you reach Culver St, you've gone too far	


**B** Upmc Chautauqua Wca Hospital



**A** 65 S Dow St, Falconer, NY 14733



**B** UPMC Chautauqua WCA Hospital, 51 Glasg...



These directions are subject to the Microsoft® Service Agreement and are for informational purposes only. No guarantee is made regarding their completeness or accuracy. Construction projects, traffic, or other events may cause actual conditions to differ from these results. Map and traffic data © 2017 HERE™.

# Appendix A

## *EXCAVATION/TRENCHING GUIDELINE*



**C&S ENGINEERS, INC. HEALTH & SAFETY GUIDELINE #14  
EXCAVATION/TRENCHING OPERATIONS**

**TABLE OF CONTENTS**

<b>1.0</b>	<b>PURPOSE</b> .....	<b>1</b>
<b>2.0</b>	<b>SCOPE</b> .....	<b>1</b>
<b>3.0</b>	<b>DEFINITION</b> .....	<b>1</b>
<b>4.0</b>	<b>RESPONSIBILITY</b> .....	<b>1</b>
<b>5.0</b>	<b>GUIDELINES</b> .....	<b>1</b>
5.1	Hazards Associated With Excavation/Trenching.....	1
5.2	Procedures Prior to Excavation .....	2
5.3	Procedures For Doing The Excavation .....	2
5.4	Entering the Excavation .....	3
<b>6.0</b>	<b>REFERENCES</b> .....	<b>3</b>
<b>7.0</b>	<b>ATTACHMENTS</b> .....	<b>3</b>



**C&S ENGINEERS, INC.**  
**EXCAVATION/TRENCHING OPERATIONS**

**1.0 PURPOSE**

To establish safe operating procedures for excavation/trenching operations at C&S work sites.

**2.0 SCOPE**

Applies to all C&S activity where excavation or trenching operations take place.

**3.0 DEFINITIONS**

**Excavation** — Any manmade cavity or depression in the earth's surface, including its sides, walls, or faces, formed by earth removal and producing unsupported earth conditions by reasons of the excavation.

**Trench** — A narrow excavation made below the surface of the ground. In general, the depth is greater than the width, but the width of a trench is not greater than 15 feet.

**4.0 RESPONSIBILITY EMPLOYEES**

**Employees** — All employees must understand and follow the procedures outlined in this guideline during all excavation and trenching operations.

**Health and Safety Coordinator/Officer (HSC/HSO)** - The HSC/HSO is responsible for ensuring that these procedures are implemented at each work site.

**5.0 GUIDELINES**

**5.1 Hazards Associated With Excavation/Trenching**

The principal hazards associated with excavation/trenching are:

- Suffocation, crushing, or other injury from falling material.
- Damage/failure of installed underground services and consequent hazards.
- Tripping, slipping, or falling.
- Possibility of explosive, flammable, toxic, or oxygen-deficient atmosphere in excavation.

## 5.2 Procedures Prior to Excavation

### 1. Underground Utilities

- Determine the presence and location of any underground chemical or utility pipes, electrical, telephone, or instrument wire or cables.
- If the local DigSafely NY is unable to locate private/domestic or plant utilities, then an independent utility locating service must be contacted and mobilized to the site.
- Identify the location of underground services by stakes, markers or paint.
- Arrange to de-energize or isolate underground services during excavation. If not possible, or if location is not definite, method of excavation shall be established to minimize hazards by such means as:
  - a) Use of hand tools in area of underground services.
  - b) Insulating personnel and equipment from possible electrical contact.
  - c) Use of tools or equipment that will reduce possibility of damage to underground services and hazard to worker.

2. Identify Excavation Area — Areas to be excavated shall be identified and segregated by means of barricades, ropes, and/or signs to prevent access of unauthorized personnel and equipment. Suitable means shall be provided to make barriers visible at all times.
3. Surface Water Provide means of diverting surface water from excavation.
4. Shoring/Bracing — Shoring or bracing that may be required for installed equipment adjacent to the excavation shall be designed by a competent person.
5. Structural Ramps — Structural ramps that are used solely by employees as a means of access to or egress from the excavation shall be designed by a competent person.

## 5.3 Procedures For Doing The Excavation

1. **Determine the need for shoring/sloping** — the type of soil will establish the need for shoring, slope of the excavation, support systems, and equipment to be used. The soil condition may change as the excavation proceeds. Appendices A, B, C, D, E, and F of the OSHA Excavation Regulation, 29 CFR 1926 Subpart P, are to be used in defining shoring and sloping requirements.
2. **Mobile equipment** — For safe use of mobile industrial equipment in or near the excavation, the load carrying capacity of soil shall be established and suitable protection against collapse of soil provided by the use of mats, barricades, restricting the location of equipment, or shoring.
3. Excavated material (spoil) shall be stored at least two (2) feet from the edge of the excavation.
4. All trench (vertical sides) excavations greater than five (5) feet deep shall be shored.

5. The excavation shall be inspected daily for changes in conditions, including the presence of ground water, change in soil condition, or effects of weather such as rain or freeze. A safe means of continuing the work shall be established based on changes in condition. Typically test trench excavations made as part of an environmental subsurface investigation are made and backfilled the same day.
6. Appropriate monitoring for gas, toxic, or flammable materials will be conducted to establish the need for respiratory equipment, ventilation, or other measures required to continue the excavation safely.
7. Adequate means of dewatering the excavation shall be provided by the contractor as required.
8. A signal person shall be provided to direct powered equipment if working in the excavation with other personnel.
9. A signal person shall be provided when backfilling excavations to direct powered equipment working in the excavation with other personnel.
10. Warning vests will be worn when employees are exposed to public vehicular traffic.
11. Employees shall stand away from vehicles being loaded or unloaded, and shall not be permitted underneath loads handled by lifting or dragging equipment.
12. Emergency rescue equipment, such as breathing apparatus, a safety harness and line, or a basket stretcher, shall be readily available if hazardous atmospheric conditions exist or may be expected to develop. The specifics will be determined by the HSC/HSM.
13. Walkways or bridges with standard guardrail shall be provided where employees or equipment are required or permitted to cross over excavations.

#### **5.4 Entering the Excavation**

No C&S Engineers, Inc., employee shall enter an excavation which fails to meet the requirements of Section 5.3 of this guideline.

#### **6.0 REFERENCES**

29 CFR 1926, Subpart P - Excavations

#### **7.0 ATTACHMENTS**

29 CFR 1926 Subpart P - Appendices A, B, F



[Regulations \(Standards - 29 CFR\) - Table of Contents](#)

---

● <b>Part Number:</b>	1926
● <b>Part Title:</b>	Safety and Health Regulations for Construction
● <b>Subpart:</b>	P
● <b>Subpart Title:</b>	Excavations
● <b>Standard Number:</b>	1926 Subpart P App A
● <b>Title:</b>	Soil Classification

---

(a) Scope and application - (1) Scope. This appendix describes a method of classifying soil and rock deposits based on site and environmental conditions, and on the structure and composition of the earth deposits. The appendix contains definitions, sets for requirements, and describes acceptable visual and manual tests for use in classifying soils.

(2) Application. This appendix applies when a sloping or benching system is designed in accordance with the requirements set for 1926.652(b)(2) as a method of protection for employees from cave-ins. This appendix also applies when timber shoring for excavations designed as a method of protection from cave-ins in accordance with appendix C to subpart P of part 1926, and when aluminum shoring is designed in accordance with appendix D. This Appendix also applies if other protective systems are designed and selected from data prepared in accordance with the requirements set forth in 1926.652(c), and the use of the data is predicated on the soil classification system set forth in this appendix.

(b) Definitions. The definitions and examples given below are based on, in whole or in part, the following; American Society for Testing and Materials (ASTM) Standards D653-85 and D2488; The Unified Soils Classification System; The U.S. Department of Agriculture (USDA) Textural Classification Scheme; and The National Bureau of Standards Report BSS-121.

"Cemented soil" means a soil in which the particles are held together by a chemical agent, such as calcium carbonate, such that a hand-size sample cannot be crushed into powder or individual soil particles by finger pressure.

"Cohesive soil" means clay (fine grained soil), or soil with a high clay content, which has cohesive strength. Cohesive soil does not crumble, can be excavated with vertical sideslopes, and is plastic when moist. Cohesive soil is hard to break up when dry, and exhibits significant cohesion when submerged. Cohesive soils include clayey silt, sandy clay, silty clay, clay and organic clay.

"Dry soil" means soil that does not exhibit visible signs of moisture content.

"Fissured" means a soil material that has a tendency to break along definite planes of fracture with little resistance, or a material that exhibits open cracks, such as tension cracks, in an exposed surface.

"Granular soil" means gravel, sand, or silt (coarse grained soil) with little or no clay content. Granular soil has no cohesive strength. Some moist granular soils exhibit apparent cohesion. Granular soil cannot be molded when moist and crumbles easily when dry.

"Layered system" means two or more distinctly different soil or rock types arranged in layers. Micaceous seams or weakened planes in rock or shale are considered layered.

"Moist soil" means a condition in which a soil looks and feels damp. Moist cohesive soil can easily be shaped into a ball and rolled into small diameter threads before crumbling. Moist granular soil that contains some cohesive material will exhibit signs of cohesion between particles.

"Plastic" means a property of a soil which allows the soil to be

deformed or molded without cracking, or appreciable volume change.

"Saturated soil" means a soil in which the voids are filled with water. Saturation does not require flow. Saturation, or near saturation, is necessary for the proper use of instruments such as a pocket penetrometer or shear vane.

"Soil classification system" means, for the purpose of this subpart, a method of categorizing soil and rock deposits in a hierarchy of Stable Rock, Type A, Type B, and Type C, in decreasing order of stability. The categories are determined based on an analysis of the properties and performance characteristics of the deposits and the characteristics of the deposits and the environmental conditions of exposure.

"Stable rock" means natural solid mineral matter that can be excavated with vertical sides and remain intact while exposed.

"Submerged soil" means soil which is underwater or is free seeping.

"Type A" means cohesive soils with an unconfined, compressive strength of 1.5 ton per square foot (tsf) (144 kPa) or greater. Examples of cohesive soils are: clay, silty clay, sandy clay, clay loam and, in some cases, silty clay loam and sandy clay loam. Cemented soils such as caliche and hardpan are also considered Type A. However, no soil is Type A if:

- (i) The soil is fissured; or
- (ii) The soil is subject to vibration from heavy traffic, pile driving, or similar effects; or
- (iii) The soil has been previously disturbed; or
- (iv) The soil is part of a sloped, layered system where the layers dip into the excavation on a slope of four horizontal to one vertical (4H:1V) or greater; or
- (v) The material is subject to other factors that would require it to be classified as a less stable material.

"Type B" means:

- (i) Cohesive soil with an unconfined compressive strength greater than 0.5 tsf (48 kPa) but less than 1.5 tsf (144 kPa); or
- (ii) Granular cohesionless soils including: angular gravel (similar to crushed rock), silt, silt loam, sandy loam and, in some cases, silty clay loam and sandy clay loam.
- (iii) Previously disturbed soils except those which would otherwise be classed as Type C soil.
- (iv) Soil that meets the unconfined compressive strength or cementation requirements for Type A, but is fissured or subject to vibration; or
- (v) Dry rock that is not stable; or
- (vi) Material that is part of a sloped, layered system where the layers dip into the excavation on a slope less steep than four horizontal to one vertical (4H:1V), but only if the material would otherwise be classified as Type B.

"Type C" means:

- (i) Cohesive soil with an unconfined compressive strength of 0.5 tsf (48 kPa) or less; or
- (ii) Granular soils including gravel, sand, and loamy sand; or
- (iii) Submerged soil or soil from which water is freely seeping; or
- (iv) Submerged rock that is not stable, or
- (v) Material in a sloped, layered system where the layers dip into the excavation on a slope of four horizontal to one vertical (4H:1V) or steeper.

"Unconfined compressive strength" means the load per unit area at which a soil will fail in compression. It can be determined by laboratory testing, or estimated in the field using a pocket penetrometer, by thumb penetration tests, and other methods.

"Wet soil" means soil that contains significantly more moisture than moist soil, but in such a range of values that cohesive material will slump or begin to flow when vibrated. Granular material that would exhibit cohesive properties when moist will lose those cohesive properties when wet.

(c) Requirements - (1) Classification of soil and rock deposits. Each soil and rock deposit shall be classified by a competent person as Type A, Type B, or Type C in accordance with the definitions set forth in paragraph (b) of this appendix.

(2) Basis of classification. The classification of the deposits shall be made based on the results of at least one visual and at least one laboratory analysis. Such analyses shall be conducted by a competent person using tests described in paragraph (d) below, or in other recognized methods of soil classification and testing such as those adopted by the American Society for Testing Materials, or the U.S. Department of Agriculture textural classification system.

(3) Visual and manual analyses. The visual and manual analyses, such as those noted as being acceptable in paragraph (d) of this appendix, shall be designed and conducted to provide sufficient quantitative and qualitative information as may be necessary to identify properties, factors, and conditions affecting the classification of the deposits.

(4) Layered systems. In a layered system, the system shall be classified in accordance with its weakest layer. However, each layer shall be classified individually where a more stable layer lies under a less stable layer.

(5) Reclassification. If, after classifying a deposit, the properties, factors, or conditions affecting its classification change in any way, the deposit shall be reclassified as necessary to reflect the changed circumstances.

(d) Acceptable visual and manual tests. - (1) Visual tests. Visual analysis is conducted to determine qualitative information regarding an excavation site in general, the soil adjacent to the excavation, the soil forming the sides of the open excavation, and the soil taken from excavated material.

(i) Observe samples of soil that are excavated and soil in the sides of the excavation. Estimate the range of particle sizes and the amounts of the particle sizes. Soil that is primarily composed of fine-grained material is cohesive material. Soil composed of coarse-grained sand or gravel is granular material.

(ii) Observe soil as it is excavated. Soil that remains in clumps when excavated is cohesive. Soil that breaks up easily and does not form clumps is granular.

(iii) Observe the side of the opened excavation and the surface area adjacent to the excavation. Crack-like openings such as tensile cracks could indicate fissured material. If chunks of soil spall off a vertical side, the soil could be fissured. Small spalls are evidence of moisture in the ground and are indications of potentially hazardous situations.

(iv) Observe the area adjacent to the excavation and the excavation itself for evidence of existing utility and other underground structures and to identify previously disturbed soil.

(v) Observe the opened side of the excavation to identify layered systems. Examine layered systems to identify if the layers slope away from the excavation. Estimate the degree of slope of the layers.

(vi) Observe the area adjacent to the excavation and the sides of the opened excavation for evidence of surface water, water seepage, or the location of the level of the water table.

(vii) Observe the area adjacent to the excavation and the area within the excavation for sources of vibration that may affect the excavation face.

(2) Manual tests. Manual analysis of soil samples is conducted to determine quantitative as well as qualitative properties of soil and to provide more information in order to classify soil properly.

(i) Plasticity. Mold a moist or wet sample of soil into a ball and attempt to roll it into threads as thin as 1/8-inch in diameter. Cohesive material can be successfully rolled into threads without crumbling. For example, if at least a two inch (50 mm) length of 1/8-inch diameter thread can be held on one end without tearing, the soil is cohesive.

(ii) Dry strength. If the soil is dry and crumbles on its own or with moderate pressure into individual grains or fine powder, it is granular (a combination of gravel, sand, or silt). If the soil is dry and falls into clumps which break up into smaller clumps, but the smaller clumps can only be broken up with difficulty, it may be clay in any combination with gravel, sand or silt. If the dry soil breaks into clumps which break up into small clumps and which can only be broken with difficulty, and there is no visual indication the soil is fissured, the soil is considered unfissured.

(iii) Thumb penetration. The thumb penetration test can be used to estimate the unconfined compressive strength of cohesive soil. This test is based on the thumb penetration test described in American Society for Testing and Materials (ASTM) Standard designation "Standard Recommended Practice for Description of Soils (Visual - Manual Procedure)." Type A soils with an unconfined compressive strength of 1.5 tsf can be readily indented by the thumb; however, they can be penetrated by the thumb only with very great effort. Type B soils with an unconfined compressive strength of 0.5 tsf can be easily penetrated several inches by the thumb, and can be molded by finger pressure. This test should be conducted on an undisturbed soil sample, such as a large clump of spoil, as soon as practical after excavation to keep to a minimum the effects of exposure to drying influences. If the excavation is later exposed to wetting influences (e.g., flooding), the classification of the soil must be changed accordingly.

(iv) Other strength tests. Estimates of unconfined compressive strength of soils can also be obtained by use of a pocket penetrometer using a hand-operated shearvane.

(v) Drying test. The basic purpose of the drying test is to differentiate between cohesive material with fissures, unfissured cohesive material, and granular material. The procedure for the drying test involves drying a sample of soil that is approximately one inch thick (2.54 cm) and six inches (15.24 cm) in diameter until it is thoroughly dry:

(A) If the sample develops cracks as it dries, significant fissures are indicated.

(B) Samples that dry without cracking are to be broken by hand. If considerable force is necessary to break a sample, the soil has a high cohesive material content. The soil can be classified as an unfissured cohesive material and the unconfined compressive strength determined.

(C) If a sample breaks easily by hand, it is either a fissured cohesive material or a granular material. To distinguish between the two, pulverize the dried clumps of the sample by hand or by stepping on them. If the clumps do not pulverize easily, the material is cohesive. If they pulverize easily into very small fragments, the material is granular.

---

◀ [Next Standard \(1926 Subpart P App B\)](#)

◀ [Regulations \(Standards - 29 CFR\) - Table of Contents](#)

---

[Freedom of Information Act](#) | [Privacy & Security Statement](#) | [Disclaimers](#) | [Customer Survey](#) | [Important Web Site Notices](#)

---

U.S. Department of Labor | Occupational Safety & Health Administration | 200 Constitution Ave., NW, Washington, DC 20355  
Telephone: 800-321-OSHA (6742) | TTY: 877-889-5627

[www.OSHA.gov](http://www.OSHA.gov)



[Regulations \(Standards - 29 CFR\) - Table of Contents](#)

---

● <b>Part Number:</b>	1926
● <b>Part Title:</b>	Safety and Health Regulations for Construction
● <b>Subpart:</b>	P
● <b>Subpart Title:</b>	Excavations
● <b>Standard Number:</b>	1926 Subpart P App B
● <b>Title:</b>	Sloping and Benching

---

(a) **Scope and application.** This appendix contains specifications for sloping and benching when used as methods of protecting working in excavations from cave-ins. The requirements of this appendix apply when the design of sloping and benching protective is to be performed in accordance with the requirements set forth in § 1926.652(b)(2).

(b) **Definitions.**

**Actual slope** means the slope to which an excavation face is excavated.

**Distress** means that the soil is in a condition where a cave-in is imminent or is likely to occur. Distress is evidenced by such phenomena as the development of fissures in the face of or adjacent to an open excavation; the subsidence of the edge of an excavation; the slumping of material from the face or the bulging or heaving of material from the bottom of an excavation; the spalling of material from the face of an excavation; and raveling, i.e., small amounts of material such as pebbles or little clumps of material suddenly separating from the excavation and trickling or rolling down into the excavation.

**Maximum allowable slope** means the steepest incline of an excavation face that is acceptable for the most favorable site conditions for protection against cave-ins, and is expressed as the ratio of horizontal distance to vertical rise (H:V).

**Short term exposure** means a period of time less than or equal to 24 hours that an excavation is open.

(c) **Requirements -- (1) Soil classification.** Soil and rock deposits shall be classified in accordance with appendix A to subpart I of 1926.

(2) **Maximum allowable slope.** The maximum allowable slope for a soil or rock deposit shall be determined from Table B-1 of this appendix.

(3) **Actual slope.** (i) The actual slope shall not be steeper than the maximum allowable slope.

(ii) The actual slope shall be less steep than the maximum allowable slope, when there are signs of distress. If that situation occurs, the actual slope shall be cut back to an actual slope which is at least 1/2 horizontal to one vertical (1/2H:1V) less steep than the maximum allowable slope.

(iii) When surcharge loads from stored material or equipment, operating equipment, or traffic are present, a competent person shall determine the degree to which the actual slope must be reduced below the maximum allowable slope, and shall assure that such reduction is achieved. Surcharge loads from adjacent structures shall be evaluated in accordance with § 1926.651(i).

(4) **Configurations.** Configurations of sloping and benching systems shall be in accordance with Figure B-1.



**TABLE B-1  
MAXIMUM ALLOWABLE SLOPES**

SOIL OR ROCK TYPE	MAXIMUM ALLOWABLE SLOPES (H:V)(1) FOR EXCAVATIONS LESS THAN 20 FEET DEEP(3)
STABLE ROCK	VERTICAL (90°)
TYPE A (2)	3/4:1 (53°)
TYPE B	1:1 (45°)
TYPE C	1 1/2:1 (34°)

Footnote(1) Numbers shown in parentheses next to maximum allowable slopes are angles expressed in degrees from the horizontal. Angle rounded off.

Footnote(2) A short-term maximum allowable slope of 1/2H:1V (63°) is allowed in excavations in Type A soil that are 12 feet (3.67 m) or less in depth. Short-term maximum allowable slopes for excavations greater than 12 feet (3.67 m) in depth shall be 3/4H:1V (53°).


Footnote(3) Sloping or benching for excavations greater than 20 feet deep shall be designed by a registered professional engineer.

**Figure B-1  
Slope Configurations**

(All slopes stated below are in the horizontal to vertical ratio)


**B-1.1 Excavations made in Type A soil.**

1. All simple slope excavation 20 feet or less in depth shall have a maximum allowable slope of 3/4:1.



SIMPLE SLOPE -- GENERAL


Exception: Simple slope excavations which are open 24 hours or less (short term) and which are 12 feet or less in depth shall have maximum allowable slope of 1/2:1.




SIMPLE SLOPE -- SHORT TERM

2. All benched excavations 20 feet or less in depth shall have a maximum allowable slope of 3/4 to 1 and maximum bench dimensions

follows:




SIMPLE BENCH




MULTIPLE BENCH

3. All excavations 8 feet or less in depth which have unsupported vertically sided lower portions shall have a maximum vertical side feet.




UNSUPPORTED VERTICALLY SIDED LOWER PORTION -- MAXIMUM 8 FEET IN DEPTH)

All excavations more than 8 feet but not more than 12 feet in depth with unsupported vertically sided lower portions shall have a allowable slope of 1:1 and a maximum vertical side of 3 1/2 feet.



UNSUPPORTED VERTICALLY SIDED LOWER PORTION -- MAXIMUM 12 FEET IN DEPTH)

All excavations 20 feet or less in depth which have vertically sided lower portions that are supported or shielded shall have a maximum allowable slope of 3/4:1. The support or shield system must extend at least 18 inches above the top of the vertical side.




SUPPORTED OR SHIELDED VERTICALLY SIDED LOWER PORTION

4. All other simple slope, compound slope, and vertically sided lower portion excavations shall be in accordance with the other options permitted under § 1926.652(b).


**B-1.2 Excavations Made in Type B Soil**

1. All simple slope excavations 20 feet or less in depth shall have a maximum allowable slope of 1:1.




SIMPLE SLOPE

2. All benched excavations 20 feet or less in depth shall have a maximum allowable slope of 1:1 and maximum bench dimensions




SINGLE BENCH



MULTIPLE BENCH

3. All excavations 20 feet or less in depth which have vertically sided lower portions shall be shielded or supported to a height at least 18 inches above the top of the vertical side. All such excavations shall have a maximum allowable slope of 1:1.




VERTICALLY SIDED LOWER PORTION

4. All other sloped excavations shall be in accordance with the other options permitted in § 1926.652(b).


### B-1.3 Excavations Made in Type C Soil

1. All simple slope excavations 20 feet or less in depth shall have a maximum allowable slope of 1½:1.



SIMPLE SLOPE

2. All excavations 20 feet or less in depth which have vertically sided lower portions shall be shielded or supported to a height at least 18 inches above the top of the vertical side. All such excavations shall have a maximum allowable slope of 1 1/2:1.









VERTICAL SIDED LOWER PORTION

3. All other sloped excavations shall be in accordance with the other options permitted in § 1926.652(b).

**B-1.4 Excavations Made in Layered Soils**

1. All excavations 20 feet or less in depth made in layered soils shall have a maximum allowable slope for each layer as set forth b





2. All other sloped excavations shall be in accordance with the other options permitted in § 1926.652(b).

---

◀ [Next Standard \(1926 Subpart P App C\)](#)

◀ [Regulations \(Standards - 29 CFR\) - Table of Contents](#)

[Freedom of Information Act](#) | [Privacy & Security Statement](#) | [Disclaimers](#) | [Customer Survey](#) | [Important Web Site Notices](#)

---

U.S. Department of Labor | Occupational Safety & Health Administration | 200 Constitution Ave., NW, Washington, DC  
Telephone: 800-321-OSHA (6742) | TTY: 877-889-5627

[www.OSHA.gov](http://www.OSHA.gov)



Regulations (Standards - 29 CFR) - Table of Contents

- **Part Number:** 1926
- **Part Title:** Safety and Health Regulations for Construction
- **Subpart:** P
- **Subpart Title:** Excavations
- **Standard Number:** 1926 Subpart P App F
- **Title:** Selection of Protective Systems

The following figures are a graphic summary of the requirements contained in subpart P for excavations 20 feet or less in depth. Protective systems for use in excavations more than 20 feet in depth must be designed by a registered professional engineer in accordance with 1926.652(b) and (c).






FIGURE 1 - PRELIMINARY DECISIONS




FIGURE 2 - SLOPING OPTIONS

Soil Classification is required when shoring or shielding is used. The excavation must comply with one of the following four options:

Option 1

Sec. 1926.652(c)(1) which requires Appendices A and C to be followed (e.g. timber shoring).

Option 2

Sec. 1926.652(c)(2) which requires manufacturers data to be followed (e.g. hydraulic shoring, trench jacks, air shores, shields).

Option 3

Sec. 1926.652(c)(3) which requires tabulated data (see definition) to be followed (e.g. any system as per the tabulated data).

Option 4

Sec. 1926.652(c)(4) which requires the excavation to be designed by a registered professional engineer (e.g. any designed system).

FIGURE 3 - SHORING AND SHIELDING OPTIONS

[◀ Next Standard \(1926 Subpart Q\)](#)

[◀ Regulations \(Standards - 29 CFR\) - Table of Contents](#)

[Freedom of Information Act](#) | [Privacy & Security Statement](#) | [Disclaimers](#) | [Customer Survey](#) | [Important Web Site Notices](#) |

U.S. Department of Labor | Occupational Safety & Health Administration | 200 Constitution Ave., NW, Washington, DC 20535  
Telephone: 800-321-OSHA (6742) | TTY: 877-889-5627

[www.OSHA.gov](http://www.OSHA.gov)

# **Appendix B**

***GUIDANCE ON INCIDENT INVESTIGATION***

***AND REPORTING***



3. Following the treatment and care of the injured employee, the emergency coordinator or his on-site designee and the project manager will initiate the completion of the first injury report. The Health & Safety Manager will assist.

### **Project Manager**

1. Upon notification of a personal injury or illness on the job site, will notify C & S Engineers, Inc, President and Corporate Legal and C&S Companies Health and Safety Manager.
2. Will report to the worksite to initiate the first injury report.
3. Will report to the treatment facility to check on the well being of the injured employee. The project manager will ensure that the treatment facility is aware that this is a workers compensation case.
4. Will assist the Health and Safety Manager in the analysis of the incident.

### **Health & Safety Manager**

1. Upon notification of the personal injury will determined if it is necessary to report to the treatment facility or the accident site, depending on the nature of the injuries and the circumstances of the accident.
2. Will report to the worksite to begin a root cause analysis investigation of the accident. The investigation may include interview of witnesses, field crew , and project manager, the photographing of the scene, reconstruction of the accident scene, using test instruments and taking measurements. The Health and Safety Manager may draw diagrams from the information learned.
3. The Health and Safety Manager will work with the owner/client as necessary to investigate the accident.
4. The Health & Safety manager will ensure that the site is safe to resume work.
5. The Health & Safety Manager shall initiate the New York State Compensation form requirements (C-2) and forward a copy of the C-2 to the C & S Engineers, Inc. controller for transmittal to the Compensation Carrier within 8 hrs of notification of the incident or by the end of the next business day.
6. The Health and Safety manager, upon completion of the investigation, will provide the Project Manager with a written investigative report (copy to the President)
7. The accident will be reviewed at the next Project Managers meeting with the intent to prevent further or similar events on other projects.
8. The Health & Safety Manager will assess the incident to determine OSHA record ability and make record if necessary on the OSHA 300 form, within five working days.

## **Incident Response**

### **1.0 PURPOSE**

To prevent the occurrence of accidents on C&S Engineers, Inc., work sites and to establish a procedure for investigation and reporting of incidents occurring in, or related to C&S work activities.

### **2.0 SCOPE**

Applies to all incidents related to C&S Engineers, Inc. work activities.

### **3.0 DEFINITIONS**

Accident - An undesired event resulting in personal injury and/or property damage, and/or equipment failure.

Fatality - An injury or illness resulting in death of the individual.

Incident - Any occurrence which results in, or could potentially result in, the need for medical care or property damage. Such incidents shall include lost time accidents or illness, medical treatment cases, unplanned exposure to toxic materials or any other significant occurrence resulting in property damage or in "near misses."

Incidence Rate - the number of injuries, illnesses, or lost workdays related to a common exposure base of 100 full-time workers. The rate is calculated as:

$$N/EH \times 200,000$$

N = number of injuries and illnesses or lost workday cases; EH = total hours worked by all associates during calendar year. 200,000 = base for 100 full-time equivalent workers (working 40 hours per week, 50 weeks per year).

Injury - An injury such as a cut, fracture, sprain, amputation, etc. which results from a work accident or from a single instantaneous event in the work environment.

Lost Workday Case - A lost workday case occurs when an injured or ill employee experiences days away from work beginning with the next scheduled work day. Lost workday cases do not occur unless the employee is effected beyond the day of injury or onset of illness.

Recordable Illness - An illness that results from the course of employment and must be entered on the OSHA 300 Log and Summary of Occupational Injuries and Illnesses. These illnesses require medical treatment and evaluation of work related injury. For example, dermatitis, bronchitis, irritation of eyes, nose, and throat can result from work and non-work related incidents.

Recordable Injury - An injury that results from the course of employment and must be entered on the OSHA 300 Log and Summary of Occupational Injuries and Illnesses. These injuries require medical treatment; may involve loss of consciousness; may result in restriction of work or motion or transfer to another job; or result in a fatality.

Near Miss - An incident which, if occurring at a different time or in a different personnel or equipment configuration, would have resulted in an incident.

#### **4.0 RESPONSIBILITIES**

Employees - It shall be the responsibility of all C&S Engineers, Inc. employees to report all incidents as soon as possible to the HSC, regardless of the severity.

Human Resources - has overall responsibility for maintaining accident/ incident reporting and investigations according to current regulations and recording injuries/ illness on the OSHA 300 log, and posting the OSHA 300 log.

Emergency Coordinator - It is the responsibility of the Emergency Coordinator to investigate and prepare an appropriate report of all accidents, illnesses, and incidents occurring on or related to C&S Engineers, Inc. work. The Emergency Coordinator shall complete Attachment A within 24 hours of the incident occurrence.

Health and Safety Manager (HSM) - It is the responsibility of the HSM to investigate and prepare an appropriate report of all lost time injuries and illnesses and significant incidents occurring on or related to C&S Companies. The HSM shall maintain the OSHA 300 form.

Project Managers (PM) - It shall be the PM's responsibility to promptly correct any deficiencies in personnel, training, actions, or any site or equipment deficiencies that were determined to cause or contribute to the incident investigated.

#### **5.0 GUIDELINES**

##### **5.1 Incident Investigation**

The Project Manager will immediately investigate the circumstances surrounding the incident and will make recommendations to prevent recurrence. The HSM shall be immediately notified by telephone if a serious accident/ incident occurs. The incident shall be evaluated to determine whether it is OSHA recordable. If the incident is determined to be OSHA 300 recordable, it shall be entered on the OSHA 300 form.

The Project Manager with assistance from the HSM must submit to the office an incident report form pertaining to any incident resulting in injury or property damage.

## **5.2 Incident Report**

The completed incident report must be completed by the Project Manager within 12 hours of the incident and distributed to the HSM, and Human Resources. This form shall be maintained by Human Resources for at least five years for all OSHA recordable cases. This form serves as an equivalent to the OSHA 101 form.

## **5.3 Incident Follow-up Report**

The Incident Follow-Up Report (Attachment B) shall be distributed with the Incident Report within one week of the incident. Delay in filing this report shall be explained in a brief memorandum.

## **5.4 Reporting of Fatalities or Multiple Hospitalization Accidents**

Fatalities or accidents resulting in the hospitalization of three or more employees must be reported to OSHA verbally or in writing within 8 hours. The report must contain 1) circumstances surrounding the accident(s), 2) the number of fatalities, and 3) the extent of any injuries.

## **5.5 OSHA 300A Summary Form**

Recordable cases must be entered on the log within six workdays of receipt of the information that a recordable case has occurred. The OSHA log must be kept updated to within 45 calendar days.

OSHA 300 forms must be updated during the 5 year retention period, if there is a change in the extent or outcome of an injury or illness which affects an entry on a log. If a change is necessary, the original entry should be lined out and a corrected entry made on that log. New entries should be made for previously unrecorded cases that are discovered or for cases that initially weren't recorded but were found to be recordable after the end of the year. Log totals should also be modified to reflect these changes.

### **5.5.1 Posting**

The log must be summarized at the end of the calendar year and the summary must be posted from February 1 through May 31.

## **5.6 OSHA 300A**

Facilities selected by the Bureau of Labor Statistics (BLS) to participate in surveys of occupational injuries and illnesses will receive the OSHA 300A. The data from the annual summary on the OSHA 300 log should be transferred to the OSHA 300A, other requested information provided and the form returned as instructed by the BLS.

## **5.7 Access to OSHA Records**

All OSHA records (accident reporting forms and OSHA 300 logs) should be available for inspection and copying by authorized Federal and State government officials.

Employees, former employees, and their representatives must be given access for inspection and copying to only the log, OSHA No. 300, for the establishment in which the employee currently works or formerly worked.

## **6.0 REFERENCES**

29 CFR Part 1904

## **7.0 ATTACHMENTS**

Attachment A - Incident Investigation Form

Attachment B - Incident Follow-Up Report

Attachment C - Establishing Recordability



**ATTACHMENT A**  
**INCIDENT INVESTIGATION FORM**

Accident investigation should include:

Location: \_\_\_\_\_

Time of Day: \_\_\_\_\_

Accident Type: \_\_\_\_\_

Victim: \_\_\_\_\_

Nature of Injury: \_\_\_\_\_

Released Injury: \_\_\_\_\_

Hazardous Material: \_\_\_\_\_

Unsafe Acts: \_\_\_\_\_

Unsafe Conditions: \_\_\_\_\_

Policies, Decisions: \_\_\_\_\_

\_\_\_\_\_

Personal Factors: \_\_\_\_\_

\_\_\_\_\_

Environmental Factors: \_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

**ATTACHMENT B**

Date \_\_\_\_\_

Foreman: \_\_\_\_\_

**INCIDENT FOLLOW-UP REPORT**

Date of Incident: \_\_\_\_\_

Site: \_\_\_\_\_

Brief description of incident: \_\_\_\_\_

\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

Outcome of incident: \_\_\_\_\_

\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

Physician's recommendations: \_\_\_\_\_

\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

Date the injured returned to work: \_\_\_\_\_

Project Manager Signature: \_\_\_\_\_

Date: \_\_\_\_\_

ATTACH ANY ADDITIONAL INFORMATION TO THIS FORM

## ATTACHMENT C

### ESTABLISHING RECORDABILITY

1. Deciding whether to record a case and how to classify the case.

Determine whether a fatality, injury or illness is recordable.

A fatality is recordable if:

- Results from employment

An injury is recordable if:

- Results from employment and
- It requires medical treatment beyond first aid or
- Results in restricted work activity or job transfer, or
- Results in lost work day or
- Results in loss of consciousness

An illness is recordable if:

- It results from employment

2. Definition of "Resulting from Employment"

Resulting from employment is when the injury or illness results from an event or exposure in the work environment. The work environment is primarily composed of: 1) The employer's premises, and 2) other locations where associates are engaged in work-related activities or are present as a condition of their employment.

The employer's premises include company rest rooms, hallways, cafeterias, sidewalks and parking lots. Injuries occurring in these places are generally considered work related.

The employer's premises EXCLUDES employer controlled ball fields, tennis courts, golf courses, parks, swimming pools, gyms, and other similar recreational facilities, used by associates on a voluntary basis for their own benefit, primarily during off work hours.

Ordinary and customary commute, is not generally considered work related.

Employees injured or taken ill while engaged in consuming food, as part of a normal break or activity is not considered work related. Employees injured or taken ill as the result of smoking, consuming illegal drugs, alcohol or applying make up are generally not considered work related. Employee injured by an authorized horseplay is generally not considered work related, however, an employee injured as a result of a fight or other workplace violence act, may be considered work related.

Associates who travel on company business are considered to be engaged in work related activities all the time they spend in the interest of the company. This includes travel to and from customer contacts, and entertaining or being entertained for purpose of promoting or discussing business. Incidents occurring during normal living activities (eating, sleeping, recreation) or if the associate deviates from a reasonably direct route of travel are not considered OSHA recordable.

3. Distinction between Medical Treatment and First Aid.

First aid is defined as any one-time treatment, and any follow up visit for the purpose of observation, of minor scratches, cuts, burns, splinters, etc., which do not ordinarily require medical care. Such one time treatment, and follow up visit for the purpose of observation, is considered first aid even though provided by a physician or registered professional personnel.

Medical Treatment (recordable)

- a) They must be treated only by a physician or licensed medical personnel.
- b) They impair bodily function (i.e. normal use of senses, limbs, etc.).
- c) They result in damage to physical structure of a non superficial nature (fractures).
- d) They involve complications requiring follow up medical treatment.



APPENDIX C  
SUB-SLAB DEPRESSURIZATION CONSTRUCTION COMPLETION  
REPORTS

---

# mitigation tech *vapor intrusion specialists*

April 8, 2017

Mr. Cody Martin  
Project Manager  
C & S Companies  
141 Elm Street, Suite 100  
Buffalo, NY 14203  
Via email: Cody Martin <cmartin@cscos.com>

Re: Jamestown Container Companies – 65 South Dow St., Falconer, NY 14733  
Construction Completion Report for SSD System - Building 9

## **CONSTRUCTION COMPLETION REPORT**

### **1. OVERVIEW**

This document presents a construction report, performance evaluation, O&M advice and certification of effectiveness for the Sub-Slab Depressurization system (SSDS) installed by *Mitigation Tech* at 65 South Dow St., Falconer, NY 14733, Building 9, as commissioned March 27, 2017.

Following an SSD construction plan (dated October 18, 2016) informed by a general building assessment performed August 19, 2016, two multi-suction point SSD Systems were installed using principles and equipment typically used for soil vapor intrusion mitigation in buildings. The primary objective of implementing this preemptive measure was to mitigate potential intrusion of soil vapors. This would be achieved by maintaining a negative pressure of at least .002 water column inches (wci) below the slab relative to the air pressure above the slab. All work is in compliance with the NYS DOH document, “Guidance for Evaluating Soil Vapor Intrusion in the State of New York, October 2006”.

### **2. BUILDING ASSESSMENT AND SYSTEM CONSTRUCTION**

Confirmatory sub-slab air communication testing was performed at job start March 21, 2017 to refine data obtained from the preliminary building assessment. Work continued with an analysis of appropriate locations for fans, suction cavities and other SSD system components. It was determined that two fan systems were more practicable than a single fan system. Both for physical protection and minimum impact on active use areas, riser pipes were surface mounted near columns or perimeter walls; horizontal pipe was installed as close to ceiling and established raceways as possible. Work was coordinated with client to minimize disturbance of work areas, relocate obstacles and control dust. Vacuum and air flow measurements were performed continuously during construction to ensure integrity of design. Various fans were evaluated in place and in combination to determine the most effective configuration. At commissioning, all components inspected for condition and proper operation. Premises left in clean condition.

Key on site personnel were Aaron Hurysz and Robert Beck, both highly experienced soil vapor intrusion technicians. Weather conditions were favorable. Daily tailgate meetings were held to review the daily work objectives and relevant aspects of the Health & Safety Plan. No accidents or incidents occurred during the construction.

### 3. SUB-SLAB DEPRESSURIZATION SYSTEM GENERAL DESCRIPTION

3.1. Introduction. The SSDS is maintaining sub-slab vacuum at all subject areas. The system consists of (2) sidewall mounted fans connected by manifold piping to vapor extraction points. The system was constructed using principles and equipment typically used for radon mitigation in buildings as detailed in the United States Environmental Protection Agency (EPA) EPA 402-K-03-007 (May 2006), and the final NYSDOH Guidance for Evaluating Soil Vapor Intrusion in the State of New York (October 2006). The SSDS was installed as a permanent, integral addition to the structure. The key components of the SSDS are described below and are shown on an as-built diagram labeled "Sub-Slab System Diagram."

3.2. Suction Points. The suction points consists of a 5" core boring into the slab through which 1- 2 cubic feet of sub-slab material has been removed. Mechanically suspended 3" SCH 40 PVC pipe has been inserted into the boring and sealed with urethane sealant.

3.3. Riser Piping. The riser piping consists of 3" SCH 40 PVC pipe that follows a route from the extraction point to a 4" trunk line, then to the exterior mounted vacuum fan. Weatherproof flashing or sealant has been applied to all penetrations. Vent pipes were installed at a pitch that ensures that any rainwater or condensation within the pipes drains downward into the ground beneath the slab. Piping is independently supported, and not supported from existing building mechanical systems. Piping is labeled at each level as "Sub-Slab Vent". Piping is connected using manufacturer's approved methods.

3.4. Exhaust Fans. Exhaust fans has been field selected for specific performance properties. Models: 1) Festa Radon Technologies "Force" producing 4.5 wci at 55 CFM, at 300 watts; 2) RADONAWAY RP-265, producing 2.0 wci at 50 CFM, at 120 watts. Fans have an exterior disconnect switch. Fans are mounted with rubber Fernco couplings, for simplified replacement. No air intakes are present within 10' of the exhaust points.

3.5. Instrumentation and Control. There is no centralized instrumentation or control for the SSDS. The fans can be switched either from the adjacent positioned disconnect or at the marked breakers #36 and #42 on the panel box centrally located on the east wall. The exhaust fan systems are equipped with a vacuum indicator mounted in a visible location on a riser pipe per the attached schematic. The indicator consists of an oil filled U-tube style manometer. The indicator can be inspected by observing the level of colored fluid. The indicator is designed primarily to give a simple visual check that vacuum is present in the riser pipe, specifically by observation that the fluid levels on each side of the indicator are not even. Indicator is marked at level observed on March 27, 2017.

3.6 Sealing measures. Polyurethane sealants have been applied to control joints, floor cracks and slab penetrations to enhance the barrier between sub-slab and ambient air and improve the efficiency of the SSD System. Smoke testing has been employed to guide sealing operations. Materials used include Sika Sikaflex 1c-SLself-leveling joint sealant and Sika I a Sealant.

3.7 Monitoring Points. Monitoring Points are indicated on the system diagram. These consist of 3/4" drill points through the slab into which a digital micromanometer probe can be inserted. They are semi-permanently closed with backer and urethane sealant. These were established to aid in original system design and confirmatory testing, and in some cases are difficult to access. The primary future use would be in recertification of system effectiveness.



3.8 System Configuration (see attached schematic for component locations)

**Basic Systems**

- West System - FESTA RADON TECHNOLOGIES “Force” centrifugal blower, roof level sidewall exhaust; w/ (3) dedicated suction points, main plant, per attached schematic
- East System - RADONAWAY RP-265 centrifugal blower roof level sidewall exhaust; w/ (2) dedicated suction points, main plant, per attached schematic

**Common Elements:**

- Comprehensive diagnostics to optimize component type and placement
- Suction points as follows: connection via 3” Schedule 40 PVC pipe, to cavity in sub-slab, with urethane seal; access hole to suction cavity by 5” core drill; suction cavity to consists of approximately 1 cu. ft. excavated material in sub-slab
- Proportioning valves for suction risers where required
- All exhaust points minimum 10’ from any air intakes
- Exterior switch and *Sealtight* and/or MC conduit from fan housing to building interior; connection to panel with EMT or MC conduit
- U-tube style vacuum indicator per system, on vertical pipe run
- Urethane sealant with closed cell backer at slab joints, accessible cracks and penetrations
- Horizontal pipe as high as practicable, with metal bracketing direct to structure, sloped as required, above drop ceiling where applicable
- (6) vacuum test points to verify pressure extension field
- At completion, perform backdraft testing, measure pressure differentials and document; label components and provide system description and operational instructions
- Consult with client to develop operation, maintenance and periodic inspection plan
- Two year warranty; labor, installed components and sub-slab depressurization to objective (or greater); warranty is transferable and assignable to future owners of the building.

3.9 PERFORMANCE EVALUATION

Measurement date – March 27, 2017 - In order to verify system effectiveness and as a performance evaluation, test points were established at various distances from the suction cavities suitable to verify that the sub-slab of the subject area was being depressurized at least to the objective. See schematic for point locations.

<u>TP #</u>	<u>Value (neg wci)</u>
1	.014
2	.023
3	.007
4	.014
5	.012
6	.014

East system vacuum gauge value --- 2.0 wci

West system vacuum gauge value --- 4.5 wci

**4. SUB-SLAB DEPRESSURIZATION SYSTEM OPERATION**

- 4.1. The fans should be kept in continuous operation. New York State Soil Vapor Intrusion Guidance (2006) specifies that operation, maintenance and monitoring of the SSD system should be included as part of site management.
- 4.2. Reset. Fans restart automatically in event of power loss.
- 4.3. In the event of unusual fan noise, failure to start, physical damage, or repeated circuit breaker trip, turn fan off and call for service. MITIGATION TECH – 800-637-9228
- 4.4. Regularly inspect system oil filled U-tube type manometers to verify that value, indicated by a mark on the gauge, has not changed significantly from the position of the mark. Gauge is inspected by observing the level of colored fluid.
- 4.5. Normal system operation requires unchanged structural conditions. Report any changes in structure, HVAC systems, slab conditions, etc., so that the change can be evaluated for impact on the SSD System. For service, call MITIGATION TECH at 800-637-9228
- 4.6. Ensure that a periodic inspection is performed

**5. SSD SYSTEM PERFORMANCE MONITORING RECOMMENDATIONS**

**5.1. Monthly Monitoring**

- 5.1.1. Inspect fan vacuum indicator to verify that value, indicated by a mark on the gauge, has not changed significantly from the position of the mark. Gauge is inspected by observing the level of colored fluid.
- 5.1.2. Record the observed measurement for each fan vacuum indicator on form labeled “SSD System Vacuum Gauge Record”. Store all forms in the facility maintenance office.
- 5.1.3. Inspect visible components of SSD system for degraded condition.
- 5.1.4. For reporting, call MITIGATION TECH at 800-637-9228

**5.2. Annual Inspection**

- 5.2.1. Conduct a visual inspection of the complete System (e.g., vent fans, piping, warning devices, labeling)
- 5.2.2. Inspect all components for condition and proper operation;
- 5.2.3. Identify and repair any leaks in accordance with Sections 4.3.1(a) and 4.3.4(a) of the NYS DOH VI Guidance (i.e.; with the systems running, use smoke sticks to check for leaks through concrete cracks, floor joints and at the suction points; any leaks will be resealed until smoke is no longer observed flowing through the opening).
- 5.2.4. Inspect the exhaust or discharge point of each exhaust fan to verify that no air intakes have been located within 10 feet
- 5.2.5. Conduct pressure field extension testing (to ensure that the system is maintaining a vacuum beneath the entire slab). Perform a differential pressure reading at least one vacuum test point.
- 5.2.6. Interview appropriate building occupants seeking comments and observations regarding the operation of the System

April 9, 2017

Page 5

5.2.7. Check to see that the circuit breakers controlling the circuits on which the soil vapor vent fans operate are labeled "Soil Vapor System"

### **5.3. Annual Certification of Effectiveness**

5.3.1. Upon completion of the tasks outlined in section 5.2 above, the installing contractor should submit a Certification of Effectiveness document, stating that the SSD system continues to perform to the purpose for which it was designed.

## **6. SUB-SLAB DEPRESSURIZATION SYSTEM MAINTENANCE**

### **6.1. Routine Maintenance**

6.1.1. Perform procedures as specified in sections 5.2 and 5.3

6.1.2. There are no routine component replacement procedures; Replace components upon findings of damage or failure

### **6.2. Non-Routine Maintenance**

6.2.1. Non-routine maintenance may also be appropriate during the operation of the mitigation system. Examples of such situations include the following:

6.2.2. It is determined through inspection or notification by others that the vacuum gauge indicates the mitigation system is not operating properly

6.2.3. the mitigation system becomes damaged

6.2.4. the building has undergone renovations that may reduce the effectiveness of the mitigation system.

### **Certification**

I hereby certify that the SSD Systems at this location are installed properly and are effective in achieving the above stated objective.

End of Report

Thank you

Nicholas E. Mouganis EPA listing # 15415-I; NEHA ID# 100722


---

**55 SHUMWAY ROAD, BROCKPORT, NEW YORK, 14420 \* OFFICE/FAX 585-637-7430**

**SUB-SLAB  
DEPRESSURIZATION  
SYSTEM**

Legend

- F = fan w/ exterior switch
- P = circuit breaker
- G = vacuum gauge
- = suction point
- X = test point
- = pipe run



**Building #9 - SSDD**

SUB-SLAB DEPRESSURIZATION SYSTEM DIAGRAM  
 Jamestown Container Companies - 65 South Dow St., Falconer, NY 14733  
 Installed by: Mitigation Tech, 55 Shunway Rd., Brockport, NY 14420  
 Date of Completion: March 27, 2017 Phone: 1-800-637-9228

October 12, 2017

Mr. Cody Martin  
Project Manager  
C & S Companies  
141 Elm Street, Suite 100  
Buffalo, NY 14203  
Via email: *Cody Martin* <[cmartin@cscos.com](mailto:cmartin@cscos.com)>

Re: Jamestown Container Companies – 65 South Dow St., Falconer, NY 14733  
Construction Completion Report for SSD System - Building 5 & 6

## **CONSTRUCTION COMPLETION REPORT**

### **1. OVERVIEW**

This document presents a construction report, performance evaluation, O&M advice and certification of effectiveness for the Sub-Slab Depressurization (SSDS) and Crawlspace Ventilation System (CVS) installed by *Mitigation Tech* at 65 South Dow St., Falconer, NY 14733, Buildings 5 & 6, as commissioned August 4, 2017.

Following a Design/Build SSD construction plan (dated April 4, 2017) and modified based on continuing assessments performed during construction, five single suction point SSD Systems were installed using principles and equipment typically used for soil vapor intrusion mitigation in buildings. The primary objective of implementing this preemptive measure was to mitigate potential intrusion of soil vapors. This would be achieved by maintaining a negative pressure of at least .002 water column inches (wci) below the slab relative to the air pressure above the slab, specifically in the sub-slab compartments in the southernmost sections of the buildings. All work is in compliance with the NYS DOH document, “Guidance for Evaluating Soil Vapor Intrusion in the State of New York, October 2006”.

### **2. BUILDING ASSESSMENT AND SYSTEM CONSTRUCTION**

Extensive sub-slab air communication testing and building assessment was performed at job start to refine data obtained from the preliminary building assessment. Both building #5 and #6 are characterized by systems of sub-slab structural arches and grade beams crisscrossing in a north to south and east to west pattern. The sub-slab spaces are either inaccessible or difficult to access.

In the case of Building #5, extensive backfilling has occurred over time, mostly via concrete patch, so that soil is present immediately below the surface in the central and northernmost portions of the foundation. The southernmost section is an open crawlspace with a dirt floor, wet in many sections. Four east to west grade beams define five compartments. We determined that active ventilation of southernmost sub-slab compartment bounded by Buildings #4 and #6A would constitute a zone of defense to intercept soil vapor migrating from the south. This would also

October 12, 2017

Page 2

create some limited depressurization north of the first grade beam. In the case of Building #6, the sub-space of is in essence a crawlspace and ventilation is the most appropriate strategy to divert vapors from the building interior.

It was determined that five independent fan systems were necessary and practicable for creating sufficient air flow and exchange. Work continued with an analysis of appropriate locations for fans, suction cavities and other SSD system components. Both for physical protection and minimum impact on active use areas, riser pipes were surface mounted on exterior walls. Work was coordinated with client to minimize disturbance of work areas, relocate obstacles and control dust. Vacuum and air flow measurements were performed continuously during construction to ensure integrity of design. Various fans were evaluated in place and in combination to determine the most effective configuration. At commissioning, all components inspected for condition and proper operation. Premises left in clean condition.

Key on site personnel were Aaron Hurysz and Robert Beck, both highly experienced soil vapor intrusion technicians. Weather conditions were favorable. Daily tailgate meetings were held to review the daily work objectives and relevant aspects of the Health & Safety Plan. No accidents or incidents occurred during the construction.

### 3. SUB-SLAB DEPRESSURIZATION SYSTEM GENERAL DESCRIPTION

3.1. Introduction. The SSDS/CVS is maintaining sub-slab vacuum at all subject areas. The system consists of (5) sidewall mounted fans connected to vapor extraction points. The system was constructed using principles and equipment typically used for radon mitigation in buildings as detailed in the United States Environmental Protection Agency (EPA) EPA 402-K-03-007 (May 2006), and the final NYSDOH Guidance for Evaluating Soil Vapor Intrusion in the State of New York (October 2006). The SSDS was installed as a permanent, integral addition to the structure. The key components of the SSDS are described below and are shown on an as-built diagram labeled "Sub-Slab System Diagram."

3.2. Suction Points. The suction points consists of a 10" core boring into the slab directly to crawlspace voids. Mechanically suspended 8" SCH 40 PVC pipe has been inserted into the boring and sealed with urethane sealant.

3.3. Riser Piping. The riser piping consists of 8" SCH 40 PVC pipe that follows a route from the extraction point to the exterior mounted vacuum fan. Weatherproof flashing or sealant has been applied to all penetrations. Vent pipes were installed at a pitch that ensures that any rainwater or condensation within the pipes drains downward into the ground beneath the slab. Piping is independently supported, and not supported from existing building mechanical systems. Piping is labeled at each level as "Sub-Slab Vent". Piping is connected using manufacturer's approved methods.

3.4. Exhaust Fans. Exhaust fans has been field selected for specific performance properties. Model: RADONAWAY RP-380 producing 5.0 wci at 350 CFM, at 140 watts. Fans have an exterior disconnect switch. Fans are mounted with rubber Fernco couplings, for simplified replacement.

3.5. Instrumentation and Control. There is no centralized instrumentation or control for the SSDS. The fans can be switched either from the adjacent positioned disconnect or at the marked breakers on the panel box centrally located. (Labeled "P" on schematic) The exhaust fan systems are equipped with a vacuum indicator mounted in a visible location near the riser pipe per the attached schematic. The indicator consists of a dial style manometer, Dwyer Model 5001 or oil filled U-tube. The indicator can be inspected by observing the position of the dial needle or oil level. (Labeled "G" on schematic) The indicator is designed primarily to give a simple visual check that vacuum is present in the riser pipe. Indicator is marked at level observed on August 4, 2017.

3.6 Sealing measures. Polyurethane sealants have been applied to control joints, floor cracks and slab penetrations to enhance the barrier between sub-slab and ambient air and improve the efficiency of the SSD System.

October 12, 2017

Page 3

Smoke testing has been employed to guide sealing operations. Materials used include Sika Sikaflex 1c-SLself-leveling joint sealant and Sika 1a Sealant.

3.7 Monitoring Points. Monitoring Points are indicated on the system diagram. These consist of  $\frac{3}{4}$ " drill points through the slab into which a digital micromanometer probe can be inserted. They are semi-permanently closed with backer and urethane sealant. These were established to aid in original system design and confirmatory testing, and in some cases are difficult to access. The primary future use would be in recertification of system effectiveness.

3.8 System Configuration (see attached schematic for component locations)

**Furnish and Install:**

- Building 5 - east to west space defined by south perimeter wall and southernmost east to west interior footer - (2) RADONAWAY RP-380 high air flow blowers, sidewall mount, to provide sub-slab ventilation via 8" schedule 40 PVC; to conduct soil vapor from riser pipes to exhaust fan roof exhaust, with rubber connector fittings
- Building 6 - (includes influence at Building #5 sump room) - (3) RADONAWAY RP-380 high air flow blowers, sidewall mount, to provide sub-slab ventilation via 8" schedule 40 PVC; to conduct soil vapor from riser pipes to exhaust fan roof exhaust, with rubber connector fittings
- Evaluate and repair as necessary, foundation vents and openings (some left open to allow for controlled through ventilation)
- Continuous building assessment and sub-slab vacuum measurement to optimize design
- Pre-construction consultation to obtain approval for component placements
- All interior pipe SCH 40 PVC with appropriate metal hangers, riser clamps, and additional accessories to properly attach components directly to structural members; sloped as required; routing to avoid interference with other building systems
- Exterior switch and *Sealtight* and/or MC conduit from fan housing to nearest electrical panel; extra cost if panel has insufficient capacity; final panel hookup by others at other's expense
- (5) Magnahelic Series 5001 vacuum indicators
- Urethane sealant at slab joints, accessible cracks and penetrations; backer where necessary
- At completion, perform backdraft testing, label components and provide system description and operating instructions
- At completion, confirm pressure differentials
- Consult with client representatives to develop operation, maintenance and periodic inspection plan
- Two year warranty; labor, installed components and sub-slab depressurization to objective (or greater)

3.9 PERFORMANCE EVALUATION

Measurement date – August 7, 2017 - In order to verify system effectiveness and as a performance evaluation, test points were established at various distances from the suction cavities suitable to verify that the sub-slab of the subject area was being depressurized at least to the objective. See schematic for point locations. (Labeled "TP" on schematic) Downward movement of test smoke was observed at each location and in addition, negative pressure values of -.004 or better were observed.

#### **4. SUB-SLAB DEPRESSURIZATION SYSTEM OPERATION**

- 4.1. The fans should be kept in continuous operation. New York State Soil Vapor Intrusion Guidance (2006) specifies that operation, maintenance and monitoring of the SSD system should be included as part of site management.
- 4.2. Reset. Fans restart automatically in event of power loss.
- 4.3. In the event of unusual fan noise, failure to start, physical damage, or repeated circuit breaker trip, turn fan off and call for service. MITIGATION TECH – 800-637-9228
- 4.4. Regularly inspect system dial manometers to verify that value, indicated by a mark on the gauge, has not changed significantly from the position of the mark.
- 4.5. Normal system operation requires unchanged structural conditions. Report any changes in structure, HVAC systems, slab conditions, etc., so that the change can be evaluated for impact on the SSD System. For service, call MITIGATION TECH at 800-637-9228
- 4.6. Ensure that a periodic inspection is performed

#### **5. SSD SYSTEM PERFORMANCE MONITORING RECOMMENDATIONS**

##### **5.1. Monthly Monitoring**

- 5.1.1. Inspect fan vacuum indicator to verify that value, indicated by a mark on the gauge, has not changed significantly from the position of the mark.
- 5.1.2. Record the observed measurement for each fan vacuum indicator on form labeled “SSD System Vacuum Gauge Record”. Store all forms in the facility maintenance office.
- 5.1.3. Inspect visible components of SSD system for degraded condition.
- 5.1.4. For reporting, call MITIGATION TECH at 800-637-9228

##### **5.2. Annual Inspection**

- 5.2.1. Conduct a visual inspection of the complete System (e.g., vent fans, piping, warning devices, labeling)
- 5.2.2. Inspect all components for condition and proper operation;
- 5.2.3. Identify and repair any leaks in accordance with Sections 4.3.1(a) and 4.3.4(a) of the NYS DOH VI Guidance (i.e.; with the systems running, use smoke sticks to check for leaks through concrete cracks, floor joints and at the suction points; any leaks will be resealed until smoke is no longer observed flowing through the opening).
- 5.2.4. Inspect the exhaust or discharge point of each exhaust fan to verify that no air intakes have been located within 10 feet
- 5.2.5. Conduct pressure field extension testing (to ensure that the system is maintaining a vacuum beneath the entire slab). Perform a differential pressure reading at least one vacuum test point.
- 5.2.6. Interview appropriate building occupants seeking comments and observations regarding the operation of the System



October 12, 2017

Page 5

5.2.7. Check to see that the circuit breakers controlling the circuits on which the soil vapor vent fans operate are labeled "Soil Vapor System"

### **5.3. Annual Certification of Effectiveness**

5.3.1. Upon completion of the tasks outlined in section 5.2 above, the installing contractor should submit a Certification of Effectiveness document, stating that the SSD system continues to perform to the purpose for which it was designed.

## **6. SUB-SLAB DEPRESSURIZATION SYSTEM MAINTENANCE**

### **6.1. Routine Maintenance**

6.1.1. Perform procedures as specified in sections 5.2 and 5.3

6.1.2. There are no routine component replacement procedures; Replace components upon findings of damage or failure

### **6.2. Non-Routine Maintenance**

6.2.1. Non-routine maintenance may also be appropriate during the operation of the mitigation system. Examples of such situations include the following:

6.2.2. It is determined through inspection or notification by others that the vacuum gauge indicates the mitigation system is not operating properly

6.2.3. the mitigation system becomes damaged

6.2.4. the building has undergone renovations that may reduce the effectiveness of the mitigation system.

### **Certification**

I hereby certify that the SSD Systems at this location are installed properly and are effective in achieving the above stated objective.

Thank you

Nicholas E. Mouganis EPA listing # 15415-I; NEHA ID# 100722


---

**55 SHUMWAY ROAD, BROCKPORT, NEW YORK, 14420 \* OFFICE/FAX 585-637-7430**

FAN/SUCTION POINT

G = GAUGE P = PANEL

TP = VACUUM TEST POINT



SUB-SLAB DEPRESSURIZATION/VENTILATION SYSTEM DIAGRAM  
Jamestown Container Companies - 65 South Dow St., Falconer, NY 14733  
Buildings #5 & #6

Installed by: Mitigation Tech, 55 Shumway Rd., Brockport, NY 14420  
Date of Completion: August 4, 2017

APPENDIX E  
SSDS INSPECTION REPORTS

## INSPECTION REPORT

November 24, 2020

Mr. Cody Martin  
Project Manager  
C & S Companies  
141 Elm Street, Suite 100  
Buffalo, NY 14203  
Via email: Cody Martin <cmartin@cscos.com>

Re: Jamestown Container Companies – Building 9, 65 South Dow St., Falconer, NY  
Inspection Report for Sub-slab Depressurization System

For work completed October 30, 2020

1. Conducted a visual inspection of the complete System (e.g., vent fan, piping, warning device, labeling on systems, etc.): **SATISFACTORY**
2. Conducted an inspection of all surfaces to which vacuum is applied: **SATISFACTORY**
3. Inspected all components for condition and proper operation: **SATISFACTORY**
4. Identify and repair any leaks: **NO LEAKS OBSERVED**
5. Inspect the exhaust or discharge point to verify that no air intakes have been located nearby:  
**NO AIR INTAKES WITHIN TEN FEET**
6. Conduct an airstream velocity measurement: **SATISFACTORY**
7. Conduct pressure field extension testing (to ensure that the system is maintaining a vacuum beneath the entire slab): **SATISFACTORY**
8. Interview an appropriate individual seeking comments and observations regarding the operation of the System: **SATISFACTORY**

Thank you

Nicholas E. Mouganis EPA listing # 15415-I; NEHA ID# 100722 \*\*\*mitigationtech.com

## INSPECTION REPORT

November 24, 2020

Mr. Cody Martin  
Project Manager  
C & S Companies  
141 Elm Street, Suite 100  
Buffalo, NY 14203  
*Via email: Cody Martin <cmartin@cscos.com>*

Re: Jamestown Container Companies – Buildings 5&6, 65 South Dow St., Falconer, NY  
Inspection Report for Sub-slab Ventilation System

**For work completed October 30, 2020**

1. Conducted a visual inspection of the complete System (e.g., vent fan, piping, warning device, labeling on systems, etc.): **SATISFACTORY**
2. Conducted an inspection of all surfaces to which vacuum is applied: **SATISFACTORY**
3. Inspected all components for condition and proper operation: **SATISFACTORY**
4. Identify and repair any leaks: **NO LEAKS OBSERVED**
5. Inspect the exhaust or discharge points to verify that no air intakes have been located nearby: **NO AIR INTAKES WITHIN TEN FEET**
6. Conduct an airstream velocity measurement: **SATISFACTORY**
7. Conduct pressure field extension testing (to ensure that the system is maintaining a vacuum beneath the slab sections per CCR dated 10.17.17): **PROVISIONAL SATISFACTORY**  
Test points showed a decline from previous measurements and in some cases a positive pressure differential, attributed to seasonal change of measurement timing and large unsealed openings on north side of foundation. Plant manager subsequently had openings sealed. Recommend subsequent testing during the heating season.
8. Interview an appropriate individual seeking comments and observations regarding the operation of the System: **SATISFACTORY**

Thank you

Nicholas E. Mouganis EPA listing # 15415-I; NEHA ID# 100722 \*\*\*mitigationtech.com