PERIODIC REVIEW REPORT 2012 PFOHL BROTHERS LANDFILL CHEEKTOWAGA, NY

Submitted to:

NEW YORK STATE DEPARTMENT OF ENVIRONMENTAL CONSERVATION 270 MICHIGAN AVENUE BUFFALO, NEW YORK 14203

Prepared by:

URS CORPORATION 77 GOODELL STREET BUFFALO, NEW YORK 14203

Prepared for:

TOWN OF CHEEKTOWAGA ENGINEERING DEPARTMENT 275 ALEXANDER AVE CHEEKTOWAGA, NEW YORK 14211

MAY 2013

TABLE OF CONTENTS

1.0	Introduction	1		
1.1	Background	1		
1.2	Effectiveness of Remedial Program	1		
1.3	Compliance	1		
1.4	Recommendations	2		
2.0	Site Overview	2		
2.1	Site Description	2		
2.2	Chronology	2		
3.0	Remedy Performance, Effectiveness and Protectiveness	2		
3.1	Groundwater Monitoring	3		
3.2	Surface Water/Sediment Sampling			
3.3	Effluent Monitoring	4		
3.4	Hydraulic Monitoring			
3.5	Wetlands Monitoring	4		
3.6	General Physical and Mechanical Maintenance			
4.0	IC/EC Plan Compliance	5		
4.1	Institutional Controls	5		
4.2	Engineering Controls	5		
5.0	Operation & Maintenance and Monitoring Plan Compliance	5		
6.0	Conclusions and Recommendations	6		

FIGURES

Figure 2-1 Site Plan

ATTACHMENTS

- Attachment A January 2012 June 2012 Semi Annual Report
- Attachment B July 2012 December 2012 Semi Annual Report
- Attachment C IC/EC Certification

1.0 INTRODUCTION

1.1 <u>Background</u>

This Pfohl Brothers Landfill Site (No. 915043) is a 130 acre landfill located on the north and south sides of Aero Drive in the Town of Cheektowaga, Erie County. The site is located in a commercial area just west of Transit Road. The landfill was operated between 1940 and 1969 receiving household and industrial wastes. The industrial waste materials included paints, waste solvents, thinners, pine tar pitch, cellulose, rubber, scrap metal and phenolic tars. A Remedial Investigation and Feasibility Study was completed in 1991. The data showed that on-site soils, groundwater, seeps, and sediments were contaminated with Volatile and Semi-Volatile Organic Compounds, and metals at various concentrations. The data did not show any significant off-site impact. A Record of Decision (ROD) was issued in 1992 requiring the landfill to be consolidated and closed. A second ROD was issued in 1994 which removed the northern portion of the site (located immediately south of Interstate 90) from the site description. The ROD also stated that there will be no action in regard to off-site groundwater. The final remedial design for the site was completed in 2000. The remedial construction consisted of waste consolidation; capping of landfills on either side of Aero Drive; providing leachate collection around these areas; restoring wetlands; and fencing the landfill. Work commenced in 2001 and was completed in 2002. The consolidated landfill was reduced to 94 acres. Deed restrictions have been filed by the Potentially Responsible Parties (PRPs). The Operation, Maintenance and Monitoring (OM&M) Plan was approved in March 2006 and is being implemented by the Town of Cheektowaga.

1.2 Effectiveness of Remedial Program

During 2012, the capping and remedial action remedy continued to successfully prevent exposure of buried waste to human health or environmental receptors. Effectiveness has been demonstrated through maintenance of the landfill cap, effective hydraulic control of groundwater beneath the cap, and regular semiannual groundwater sampling.

1.3 Compliance

The management of the site is in compliance with the OM&M Plan. Institutional controls in the form of deed restrictions remain in place.

1.4 <u>Recommendations</u>

No changes to the operation, maintenance, and monitoring of the site are recommended.

2.0 SITE OVERVIEW

2.1 <u>Site Description</u>

The boundaries of the site are shown on Figure 2-1. The site is located immediately southwest of the intersection of Interstate 90 and Transit Road in the Town of Cheektowaga. The site is bisected by the east/west Aero Drive. Each of the two portions of the landfill are covered with a cap comprising a gas venting layer, a low permeability synthetic membrane, and a barrier protection fill layer. Surrounding the entire site is a groundwater/leachate collection system consisting of a collection trench that drains into six wetwells. Leachate and groundwater collected in the wetwells is pumped via submersible pumps in the wetwells to a fifteen-inch sanitary sewer line on the south side of Aero Drive. This sanitary sewer, installed as part of the remedy, connects to the existing fifteen-inch sanitary sewer on Rein Road south of Aero Drive. The collected groundwater/leachate discharges to the sanitary sewer under a permit from the Buffalo Sewer Authority (BSA).

2.2 Chronology

The principal elements of the remedy were consolidation of waste materials, construction of a landfill cap and construction of a perimeter leachate collection system. Construction of the remedy was completed in 2002.

OM&M commenced in 2002 upon completion of construction. These efforts are performed in accordance with the OM&M plan issued as draft in 2002 and approved as final in 2006. Based upon the results of the first three years of surface water, sediment and monitoring results, the surface water/sediment sampling was discontinued in 2008, and the list of parameters evaluated during groundwater sampling was reduced in 2006 (limiting the list of VOC and SVOC parameters and metals) and 2007 (discontinuing dioxin and radionuclide analyses).

3.0 REMEDY PERFORMANCE, EFFECTIVENESS AND PROTECTIVENESS

The principal elements of the OM&M are:

Groundwater Monitoring

- Surface Water/Sediment Sampling
- Effluent Monitoring
- Hydraulic Monitoring
- Wetlands Monitoring
- General physical and mechanical maintenance.

The Town of Cheektowaga submits OM&M reports to NYSDEC twice per year reporting on the performance, effectiveness, and protectiveness of each of these elements. The two reports covering the calendar year of 2012 are attached to this Periodic Review Report. A summary of the findings of performance, effectiveness, and protectiveness for 2012 is presented in the sections below.

3.1 Groundwater Monitoring

As the OM&M contractor for the Town of Cheektowaga, URS Corporation (URS) has performed sixteen rounds of semi-annual groundwater sampling. The most recent sampling was conducted in May and November 2012. Results of this sampling continue to show no impacts to groundwater from the landfill. In brief, no VOCs were detected above Class GA water quality standards except vinyl chloride at location GW-30S in May 2012. This is the first time vinyl chloride has been detected in this well since O&M sampling began in 2004. No SVOCs were detected at concentrations above the Class GA water quality standards at any location during either sampling event.

Metals were detected at concentrations similar to previous sampling events and are attributable to naturally occurring or offsite (e.g. road salting operations) sources. The attached semi-annual reports present the data from this sampling in tables, graphs, and charts.

3.2 <u>Surface Water/Sediment Sampling</u>

Surface water and sediment sampling was discontinued in 2008 after three years of sampling showed that no site-related contaminants were present in these media. This sampling was eliminated in accordance with the approved OM&M plan and as approved by NYSDEC.

3.3 <u>Effluent Monitoring</u>

URS performed effluent monitoring on a quarterly basis during 2012. The results of the sampling are reported in the attached semiannual reports. The parameter values in the effluent have always been well below the discharge criteria for all quarterly sampling events conducted since the start of the OM&M.

3.4 Hydraulic Monitoring

URS performed hydraulic monitoring on a quarterly basis during 2012. Hydraulic monitoring is performed through measuring the water elevation in each of the six wetwells and in nine manholes associated with the perimeter collection system, and comparing each of these elevations with the groundwater elevations in paired monitoring wells adjacent to each wetwell or manhole. Hydraulic control is demonstrated by an inward hydraulic gradient from the monitoring wells to the collection system. The hydraulic gradient has been towards the groundwater collection system for every quarterly measurement taken during 2012.

3.5 <u>Wetlands Monitoring</u>

The monitoring of wetlands mitigation has not gone as originally planned in the OM&M manual. Initially, the wetlands species planted for mitigation faired poorly due to trampling from geese and deer. Fences were erected in 2004 to keep this wildlife out. Some wetland vegetation was also lost during landfill cap mowing in 2005 when the mowing contractor mowed a greater area than had been specified. The wetland vegetation species were replanted in 2005. However, in the time since construction ended in 2002, the *Phragmites sp.* vegetation that is quite abundant in this area has spread and established itself throughout the areas formerly disturbed during construction. *Phragmites sp.* does not provide robust food source for wildlife, but does act to stabilize soil in the interface zone between the landfill and the existing pond and wetland.

3.6 General Physical and Mechanical Maintenance

The Town of Cheektowaga performs the necessary general physical and mechanical maintenance as needed. Example maintenance items are routine maintenance and replacement of pumps and instrumentation used for groundwater/leachate collection, annual cap mowing, snow plowing, etc. A summary of the general maintenance activities performed during 2012 is provided in the attached semiannual reports.

4.0 IC/EC PLAN COMPLIANCE

There is no formal Institutional Control/Engineering Control (IC/EC) plan for this site. However, there are institutional and engineering controls in place and they are functioning as intended. These are discussed below.

4.1 Institutional Controls

Institutional controls (ICs) consist of restrictions on land use for the various parcels that comprise this site. The parcels subject and their restrictions are listed on the attached Site Management Periodic Review Report Notice Institutional and Engineering Controls Certification Form. The restrictions address building use, groundwater use, and land use. Compliance with these ICs is evaluated by observation to see if any infringing activities are occurring on these parcels. These ICs remain in effect, as certified in Attachment C.

4.2 Engineering Controls

Engineering controls (ECs) consist of the landfill cap, fencing and access control, collection of the groundwater/leachate, and vapor mitigation. Compliance with these ECs is evaluated at a minimum through inspection of these elements during each semiannual monitoring event. In most cases, inspection is more frequent. For example collection of the groundwater/leachate is monitored continuously by Town of Cheektowaga personnel and effluent compliance reports are submitted quarterly. These ECs remain in effect, as certified in Attachment C.


5.0 OPERATION & MAINTENANCE AND MONITORING PLAN COMPLIANCE

The components of the OM&M Plan are discussed above in Section 3.0. Summaries of OM&M activities performed during 2012 are provided in the attached semiannual reports. The OM&M activities show that the landfill and its groundwater/leachate collection system are operating as intended, and receive repairs and maintenance as needed in a timely fashion. Sampling of the groundwater in monitoring wells and the effluent generated by the groundwater/leachate collection system show that no landfill contamination is migrating to these media, and therefore the wastes remain effectively contained. No changes to the OM&M for this site are recommended.

6.0 CONCLUSIONS AND RECOMMENDATIONS

The remedy at the Pfohl Brothers Site Landfill is operating as designed and remains protective of human health and the environment. No changes to the OM&M for this site are recommended.

FIGURES





ATTACHMENTS

ATTACHMENT A

January 2012 – June 2012

Semi Annual Report

SEMI ANNUAL REPORT OPERATION AND MAINTENANCE JANUARY 2012 TO JUNE 2012 PFOHL BROTHERS LANDFILL CHEEKTOWAGA, NY

Submitted to:

NEW YORK STATE DEPARTMENT OF ENVIRONMENTAL CONSERVATION 270 MICHIGAN AVENUE BUFFALO, NEW YORK 14203

Prepared by:

URS CORPORATION 77 GOODELL STREET BUFFALO, NEW YORK 14203

Prepared for:

TOWN OF CHEEKTOWAGA ENGINEERING DEPARTMENT 275 ALEXANDER AVE CHEEKTOWAGA, NEW YORK 14211

> SEPTEMBER 2012



September 24, 2012

Mr. Jaspal Singh Walia, P.E. New York State Department of Environmental Conservation 270 Michigan Ave. Buffalo, NY 14203

Re: Semi-Annual Report Pfohl Brothers Landfill, Town of Cheektowaga, New York

Dear Mr. Walia:

Enclosed is one copy of the seventeenth Semi-Annual Report for the Pfohl Brothers Landfill in Cheektowaga, New York. A copy has also been sent to Ms. Pamela Tames, P.E. of the United States Environmental Protection Agency. Also enclosed is the Data Applicability Report for laboratory analyses associated with the Semi-Annual Report. PDF copies of the reports are also enclosed.

If you have any questions on this report, please feel free to contact me.

Sincerely,

URS CORPORATION

Jon Sundquist, Ph.D. Project Manager

Enclosures

cc: Pamela Tames, P.E. - USEPA (w/attachments) William Pugh, P.E. – Town of Cheektowaga (w/attachments) File 11172700 (C-1)

TABLE OF CONTENTS

Page No.

1.0	INTR	RODUCTION	1-1				
	1.1	Background	1-1				
	1.2	Operation and Maintenance Activities	1-1				
2.0	GEN	ERAL MAINTENANCE ACTIVITIES	2-1				
3.0	MON	MONITORING ACTIVITIES					
	3.1	Groundwater Hydraulic Monitoring	3-1				
	3.2	Groundwater Quality Monitoring	3-1				
	3.3	Groundwater Discharge Monitoring	3-4				
	3.4	Monitoring Well Inspections	3-5				
4.0	SUM	IMARY AND RECOMMENDATIONS	4-1				

TABLES

Table 3-1	Groundwater Sample Analytical Results
Table 3-2	Approved Revision Of Table 3.2 From The O&M Plan

FIGURES

- Figure 1-1 Site Location Map
- Figure 3-1 Monitoring Locations

APPENDICES

- Appendix A Example Daily Inspection Sheets
- Appendix B Monthly Flow Summaries (January 2012 June 2012)
- Appendix C Hydraulic Monitoring Tables
- Appendix D Groundwater Purge and Sample Collection Logs
- Appendix E Historical Analytical Results
- Appendix F BSA Permit No. 10-11-CH016
- Appendix G Discharge Report Summary Tables
- Appendix H Monitoring Well Inspection Logs

1.0 INTRODUCTION

1.1 <u>Background</u>

The Pfohl Brothers Landfill is located on Aero Drive in the Town of Cheektowaga, New York (Figure 1-1). The site is listed as site No. 9-15-043 on the New York State Department of Environmental Conservation's (NYSDEC's) Registry of Inactive Hazardous Waste Disposal Sites. A Consent Order between NYSDEC and potentially responsible parties (PRPs) for closure of the site was signed in 2001 and remedial construction commenced in 2001. The remedy included consolidation of waste material, capping of the waste disposal and consolidation areas, and encircling the landfill areas with a groundwater collection system to prevent off-site migration. The remedial action was completed in 2002.

Responsibility for implementing the remedy was divided between a "steering committee" of industrial PRPs and the Town of Cheektowaga. The steering committee responsibilities lay generally with the capital construction activities of the remedy including waste consolidation, cap and drainage system installation, etc. The Town of Cheektowaga, which was named as a PRP for disposal of municipal waste at the Pfohl Brothers Landfill when it was operating, is performing the operation and maintenance (O&M) activities at the landfill, pursuant to a settlement agreement between the Town and the steering committee.

1.2 **Operation and Maintenance Activities**

While construction of the remedy was substantially complete by late 2002, the final O&M manual was not approved by the NYSDEC until March 10, 2006. However, the Town of Cheektowaga and its consultant (URS Corporation – New York) assumed most of the operational responsibilities since 2002. This includes a variety of general maintenance activities as outlined in Section 2 and sampling and other monitoring activities outlined in Section 3.

Beginning in 2004, the Town and URS assumed all of the O&M activities described in the O&M plan. This report is the seventeenth semi-annual report as called for by Section 3.6 of the O&M plan.

2.0 GENERAL MAINTENANCE ACTIVITIES

Since completion of construction activities in 2002, personnel from the Town of Cheektowaga Engineering Department have performed general activities to ensure the physical operation of the landfill as intended by the design. The various O&M activities performed by the Town from January 2012 through June 2012 include the following actions.

- The amount of groundwater discharged through the collection system was recorded on a daily basis. The flow rate displayed by each wet well pump at the time of daily inspection and the total cumulative volume of flow was recorded for each wet well on daily inspection sheets. Examples of the daily inspection sheet are attached in Appendix A.
- Total cumulative effluent flow rates and volumes were summarized on a monthly basis starting in February 2003. The monthly totals for the period of January 2012 through June 2012, including graphs showing daily total discharge (gallons) as a function of calendar day, are presented in Appendix B.
- The wet well pumps were shutdown during wet weather flow conditions throughout the year to reduce hydraulic loading to the sewer. Such actions were only taken upon request of the Buffalo Sewer Authority during heavy storm events in order to reduce the hydraulic load on the BSA treatment system during such events. Shutdown events are recorded and included with the monthly flow data as previously requested by NYSDEC.
- Plowed snow to access the Control Building when necessary.
- Cleaned/replaced check valves as necessary at all wet wells.
- Replaced surge protector for WW4 (May 2012).
- Prepared bid specifications for mowing landfill cap and awarded new contract for calendar years 2012, 2013, and 2014.
- Wildlife trapper engaged as needed to control ground burrowing animals.

3.0 MONITORING ACTIVITIES

The Town of Cheektowaga retained URS Corporation to perform monitoring activities as outlined in Section 3.1 of the O&M plan. During the period of January 2004 through the present, URS performed groundwater hydraulic monitoring (Section 3.1.1.2 of the O&M plan) and effluent monitoring (Section 3.1.4 of the O&M plan) on a quarterly basis. URS also performed the seventeenth semi-annual groundwater quality monitoring event (Section 3.1.1.3 of the O&M plan). A summary of the monitoring activities is presented in the following subsections. Hydraulic and groundwater sampling locations are shown on Figure 3-1.

3.1 Groundwater Hydraulic Monitoring

Groundwater and surface water elevations were monitored on a quarterly basis at all locations listed in Table 3.1 of the O&M Plan. The hydraulic monitoring data tables showing groundwater elevations are presented in Appendix C. Table 1 of this appendix lists the measured elevations. Table 2 provides a comparison of the measured levels in the wells and corresponding manholes/wet wells.

The data presented in Appendix C indicate that groundwater levels outside the collection system were higher than the levels measured in the corresponding wet well or manhole for each measurement date. Therefore, these data demonstrate that the collection system is operating as designed.

3.2 Groundwater Quality Monitoring

The seventeenth semi-annual round of groundwater sampling was conducted between May 15, 2012 and May 17, 2012. All wells listed in Table 3.2 of the O&M plan were purged and sampled using dedicated/disposable equipment. Figure 3-1 shows the well locations. Low flow sampling techniques were used on most wells.

Passive diffusion bags (PDBs) were placed in three wells with low recharge rates (GW-4S, GW-7S, and GW-7D) on March 26, 2012. The PDBs were removed from the wells during the sampling event and their contents were analyzed for VOCs. Following removal of the PDBs the three wells were purged dry. These wells were sampled for the other required parameters after their water levels recovered.

Purge logs and sampling summary sheets are provided in Appendix D. Measurements of pH, specific conductivity, temperature, dissolved oxygen, oxidation reduction potential, and turbidity taken during purging are provided in Appendix D. The samples were packed with ice in coolers and transported under chain-of-custody (CoC) control to Test America Laboratories of Amherst, New York.

Groundwater samples were analyzed for the parameters listed in Table 3.2 of the O&M plan as revised in accordance with Table 3-6 in the Semi Annual Report dated September 2007 (January through June 2007) and as approved by the December 6, 2006 and November 29, 2007 correspondence from the NYSDEC authorizing a reduction in the parameters list (this table is included in this report as Table 3-2). Table 3-1 of this report presents the groundwater sample results compared with NYSDEC Ambient Water Quality Standards and Guidance Values and Groundwater Effluent Limitations Class GA water quality standards.

Results

Only one VOC (vinyl chloride at location GW-30S) was detected at a concentration that exceeded Class GA water quality standards. This is the first time vinyl chloride has been detected in this well since O&M sampling began in 2004. No SVOCs were detected at concentrations above the Class GA water quality standards at any location

Among the metals, iron, magnesium, manganese, and sodium routinely exceed Class GA standards in most site wells. Antimony, chromium, lead, and nickel were detected at concentrations exceeding Class GA standards in well GW-07D. Arsenic was detected at a concentration exceeding Class GA standards in well GW-29S.

Comparison to Historical Results

No significant changes in metals concentrations were observed when compared to previous sampling event analytical results. The concentration of iron, magnesium, manganese, and sodium in most site wells was similar to the concentrations found during previous sampling events.

The concentrations of chromium and nickel at GW-07D and GW-03S, and lead at GW-07D were within the historical range of concentrations observed for these compounds at these wells.

Sodium concentrations were generally higher in bedrock wells (GW-01D, GW-03D, GW-08D and GW-26D) and shallow wells adjacent to roads (GW-01S and GW-30S). The sodium concentration was also elevated in GW-08SR. The higher sodium concentrations in the bedrock wells may be attributed to the local bedrock composition and the elevated concentration in the shallow wells may be the result of seasonal road de-icing activities.

Trend Analysis

Appendix E, Figures E-1 through E-19 presents a trend analysis of groundwater parameters that routinely exceed Class GA groundwater standards. A review of the trend analysis indicated that no significant changes or trends in concentrations of any of the parameters exceeding groundwater standards have occurred over the seventeen semi-annual sampling events except as described below. Figure E-2 for GW-01S, indicates a consistent drop in sodium concentration over the seventeen sampling events. Figure E-4 indicates a slight upward trend for magnesium in GW-03S since monitoring began. Figure E-5 for GW-04D, indicates a slight increasing trend for magnesium. Figure E-7 for GW-07D shows an upward trend for chromium over the last seven events. Figure E-9 for GW-08D shows a decreasing trend for both iron and manganese since monitoring began. Figures E-10 and E-11 for GW-08SR and GW-26D, respectively, show an upward trend in sodium concentrations since monitoring began. Figures E-

12 and E-14 for GW-28S and GW-30S, respectively, indicate a decreasing trend for sodium since monitoring began.

Laboratory Report

The groundwater analytical data package was prepared by Test America in accordance with NYSDEC Category A deliverable requirements. It was reviewed for compliance with analytical method requirements and the following guidelines: USEPA *Contract Laboratory Program (CLP) National Functional Guidelines for Organic Data Review*, EPA-540-R-99-008, October 1999; USEPA *CLP National Functional Guidelines for Inorganic Data Review*, EPA-540-R-99-008, October 1999; USEPA *CLP National Functional Guidelines for Inorganic Data Review*, EPA-540-R-99-008, July 2002; and USEPA *Region II Data Validation SOP for SW-846 Method 8290, PCDDs and PCDFs by High Resolution Gas Chromatography/High-Resolution Mass Spectrometry (HRGC/HRMS*), SOP No. HW-19, Revision 1, October 1994. Qualifications applied to the data include "J/UJ" (estimated concentration/estimated quantitation limit), "J+" (estimated concentration with possible high bias), "J-" (estimated concentration with possible low bias), and "U" (not detected).

A Data Applicability Report (DAR) was prepared following the guidelines provided in NYSDEC Division of Environmental Remediation (DER-10) *Technical Guidance for Site Investigation and Remediation, Appendix 2B*, dated May 2010. The DAR dated June 2012 is submitted separately from this report.

3.3 Groundwater Discharge Monitoring

URS completed two quarterly sampling events (March 2012 and June 2012) of the groundwater collection system discharge since the previous semi-annual report. The sampling was performed in accordance with the requirements of Discharge Permit No. 10-11-CH016 between the Buffalo Sewer Authority and the Town of Cheektowaga. A copy of Permit No. 10-11-CH016 is included as Appendix F.

During the sampling events in March 2012 and June 2012, each regulated parameter was below the limits set by the permit. Copies of the data summary tables that were included with the monitoring reports are included as Appendix G.

3.4 Monitoring Well Inspections

During the May 2012 groundwater sampling event, a well inspection was performed. All wells appeared to be in good condition with the exception of previously existing damage to the risers on GW-07D, GW-01S, and GW-01D. The monitoring well inspection logs may be found in Appendix H.

4.0 SUMMARY AND RECOMMENDATIONS

General Maintenance: The Town will continue to maintain mechanical equipment at the landfill on an as-needed basis and operate the groundwater collection and discharge system as designed. The Town will also continue regular inspections, mow the cap once per year, and plow access to the control building during winter months as necessary.

Groundwater Hydraulic Monitoring: Hydraulic monitoring has been performed on a quarterly basis in conjunction with the discharge monitoring. Water level measurement data demonstrates that the hydraulic gradient is from outside the landfill towards the collection trench. Continued quarterly monitoring is recommended.

Groundwater Quality Monitoring: Groundwater sample results indicate that only low levels of organic compounds and metals are present. Similar concentrations of most parameters were found during previous sampling events. The eighteenth round of groundwater sampling will be conducted in November 2012. Low flow sampling techniques will be used. Passive diffusion bags will be used again for VOC analyses at the three wells (GW-4S, GW-7S, and GW-7D) that go dry even using low flow sampling techniques.

Groundwater Discharge Monitoring: Groundwater discharges remain within permit limits. Continued quarterly monitoring is recommended.

TABLES

Location ID			GW-01D	GW-01S	GW-03D	GW-03S	GW-04D
Sample ID	GW-1D	GW-1S	GW-3D	GW-3S	GW-4D		
Matrix	Groundwater	Groundwater	Groundwater	Groundwater	Groundwater		
Depth Interval (f	t)		-	-	-	-	-
Date Sampled			05/17/12	05/17/12	05/15/12	05/15/12	05/16/12
Parameter	Units	*					
Volatile Organic Compounds							
1,2-Dichloroethene (total)	UG/L	5					
Vinyl chloride	UG/L	2					
Semivolatile Organic Compounds							
1,3-Dichlorobenzene	UG/L	3			0.72 J		
1,4-Dichlorobenzene	UG/L	3			2.1 J		
Antimony	MG/L	0.003					
Arsenic	MG/L	0.025		0.0058 J			
Barium	MG/L	1	0.072	0.15	0.091	0.15	0.073
Cadmium	MG/L	0.005				0.00056 J	
Chromium	MG/L	0.05	0.026			0.029	0.0030 J
Copper	MG/L	0.2	0.0027 J	0.0018 J		0.0019 J	
Iron	MG/L	0.3	2.8	7.4	1.8	0.91	0.21
Lead	MG/L	0.025					
Magnesium	MG/L	35	35.2	11.2	17.2	81.1	70.1
Manganese	MG/L	0.3	0.021	0.75	0.55	0.25	0.016
Mercury	MG/L	7.00E-04					
Nickel	MG/L	0.1			0.0033 J	0.097	
Sodium	MG/L	20	92.6 J-	99.3 J-	214 J-	34.8 J-	77.4 J-
Zinc	MG/L	2	0.014	0.0027 J	0.0085 J	0.0094 J	0.023

*- NYSDEC TOGS (1.1.1), Ambient Water Quality Standards and Guidance Values and Groundwater Effluent Limitations. June 1998 (includes 4/2000 Addendum). Class GA. *- PCB Criteria based on sum of the aroclors.

Flags assigned during chemistry validation are shown.

Concentration Exceeds

J - The analyte was positively identified, the quantitation is an estimation.

Blank - not detected. - = No criteria.

Location ID	GW-04S	GW-07D	GW-07D	GW-07S	GW-07S		
Sample ID	GW-4S	GW-7D	GW-7D	GW-7S	GW-7S		
Matrix			Groundwater	Groundwater	Groundwater	Groundwater	Groundwater
Depth Interval (f	t)		-	-	-	-	-
Date Sampled	-		05/16/12	05/15/12	05/16/12	05/15/12	05/16/12
Parameter	Units	*					
Volatile Organic Compounds							
1,2-Dichloroethene (total)	UG/L	5			NA		NA
Vinyl chloride	UG/L	2			NA		NA
Semivolatile Organic Compounds							
1,3-Dichlorobenzene	UG/L	3		NA		NA	
1,4-Dichlorobenzene	UG/L	3		NA		NA	
Antimony	MG/L	0.003		NA	0.013 J	NA	
Arsenic	MG/L	0.025		NA		NA	
Barium	MG/L	1	0.12	NA	0.084	NA	0.26
Cadmium	MG/L	0.005		NA	0.0021	NA	0.0013
Chromium	MG/L	0.05	0.021	NA	0.45	NA	0.035
Copper	MG/L	0.2	0.0062 J	NA	0.050	NA	0.0017 J
Iron	MG/L	0.3	4.5	NA		NA	0.69
Lead	MG/L	0.025	0.0035 J	NA	0.18	NA	
Magnesium	MG/L	35	27.6	NA	31.7	NA	32.8
Manganese	MG/L	0.3	0.19	NA	0.13	NA	0.039
Mercury	MG/L	7.00E-04	0.00013 J	NA		NA	
Nickel	MG/L	0.1	0.011	NA	0.22	NA	0.023
Sodium	MG/L	20	29.5 J-	NA	81.8 J-	NA	55.9 J-
Zinc	MG/L	2	0.022	NA	0.080	NA	0.0070 J

*- NYSDEC TOGS (1.1.1), Ambient Water Quality Standards and Guidance Values and Groundwater Effluent Limitations. June 1998 (includes 4/2000 Addendum). Class GA. * - PCB Criteria based on sum of the aroclors.

Flags assigned during chemistry validation are shown.

Concentration Exceeds

J - The analyte was positively identified, the quantitation is an estimation.

Blank - not detected. - = No criteria.

Only Detected Results Reported.

Location ID	Location ID			GW-08D	GW-08SR	GW-26D	GW-28S
Sample ID	DUPLICATE	GW-8D	GW-8SR	GW-26D	GW-28S		
Matrix	Groundwater	Groundwater	Groundwater	Groundwater	Groundwater		
Depth Interval (f	t)		-	-	-	-	-
Date Sampled			05/15/12	05/15/12	05/15/12	05/16/12	05/16/12
Parameter	Units	*	Field Duplicate (1-1)				
Volatile Organic Compounds							
1,2-Dichloroethene (total)	UG/L	5				2.0	
Vinyl chloride	UG/L	2					
Semivolatile Organic Compounds							
1,3-Dichlorobenzene	UG/L	3					
1,4-Dichlorobenzene	UG/L	3					
Antimony	MG/L	0.003					
Arsenic	MG/L	0.025			0.011	0.0075 J	
Barium	MG/L	1	0.11	0.10	0.46	0.18	0.076
Cadmium	MG/L	0.005					
Chromium	MG/L	0.05	0.0014 J	0.0034 J	0.0020 J	0.0013 J	
Copper	MG/L	0.2	0.0037 J	0.0028 J			
Iron	MG/L	0.3	0.18	0.13	29.4	6.2	0.092
Lead	MG/L	0.025					
Magnesium	MG/L	35	16.9	16.7	47.3	21.5	29.1
Manganese	MG/L	0.3	0.14	0.14		0.81	0.88
Mercury	MG/L	7.00E-04					
Nickel	MG/L	0.1	0.0041 J	0.0040 J	0.0031 J	0.0021 J	0.0016 J
Sodium	MG/L	20	244 J-	243 J-	360 J-	419 J-	17.3 J-
Zinc	MG/L	2	0.025	0.015	0.0022 J		0.0055 J

*- NYSDEC TOGS (1.1.1), Ambient Water Quality Standards and Guidance Values and Groundwater Effluent Limitations. June 1998 (includes 4/2000 Addendum). Class GA. * - PCB Criteria based on sum of the aroclors.

Flags assigned during chemistry validation are shown.

Concentration Exceeds

J - The analyte was positively identified, the quantitation is an estimation.

Blank - not detected. - = No criteria.

Only Detected Results Reported.

Location ID			GW-29S	GW-30S	GW-31S	GW-32S	GW-33S
Sample ID	GW-29S	GW-30S	GW-31S	GW-32S	GW-33S		
Matrix	Groundwater	Groundwater	Groundwater	Groundwater	Groundwater		
Depth Interval (f	t)		-	-	-	-	-
Date Sampled			05/16/12	05/17/12	05/17/12	05/17/12	05/17/12
Parameter	Units	*					
Volatile Organic Compounds							
1,2-Dichloroethene (total)	UG/L	5					
Vinyl chloride	UG/L	2		5.3			
Semivolatile Organic Compounds							
1,3-Dichlorobenzene	UG/L	3					
1,4-Dichlorobenzene	UG/L	3					
Antimony	MG/L	0.003					
Arsenic	MG/L	0.025	0.029				
Barium	MG/L	1	0.20	0.18	0.059	0.057	0.017
Cadmium	MG/L	0.005					
Chromium	MG/L	0.05			0.0016 J	0.0013 J	
Copper	MG/L	0.2			0.0022 J	0.0019 J	
Iron	MG/L	0.3			0.42	0.044 J	0.080
Lead	MG/L	0.025					
Magnesium	MG/L	35		45.2	29.3	32.5	40.0
Manganese	MG/L	0.3	0.78		0.87	0.29	0.47
Mercury	MG/L	7.00E-04					
Nickel	MG/L	0.1		0.0025 J	0.0096 J		0.0025 J
Sodium	MG/L	20	11.4 J-	115 J-	4.8 J-	4.1 J-	4.6 J-
Zinc	MG/L	2			0.0067 J	0.0030 J	0.0043 J

*- NYSDEC TOGS (1.1.1), Ambient Water Quality Standards and Guidance Values and Groundwater Effluent Limitations. June 1998 (includes 4/2000 Addendum). Class GA. *- PCB Criteria based on sum of the aroclors.

Flags assigned during chemistry validation are shown.

Concentration Exceeds

J - The analyte was positively identified, the quantitation is an estimation.

Blank - not detected. - = No criteria.

Location ID	GW-34S	GW-35S		
Sample ID	GW-34S	GW-35S		
Matrix	Groundwater	Groundwater		
Depth Interval (f	-	-		
Date Sampled			05/16/12	05/16/12
Parameter	Units	*		
Volatile Organic Compounds				
1,2-Dichloroethene (total)	UG/L	5		
Vinyl chloride	UG/L	2		
Semivolatile Organic Compounds				
1,3-Dichlorobenzene	UG/L	3		
1,4-Dichlorobenzene	UG/L	3		
Antimony	MG/L	0.003		
Arsenic	MG/L	0.025		
Barium	MG/L	1	0.14	0.074
Cadmium	MG/L	0.005		
Chromium	MG/L	0.05	0.0035 J	0.0011 J
Copper	MG/L	0.2		
Iron	MG/L	0.3	0.37	0.084
Lead	MG/L	0.025		
Magnesium	MG/L	35	53.1	23.4
Manganese	MG/L	0.3	0.092	0.30
Mercury	MG/L	7.00E-04		
Nickel	MG/L	0.1	0.0075 J	0.0014 J
Sodium	MG/L	20	32.9 J-	2.7 J-
Zinc	MG/L	2	0.0022 J	0.0024 J

*- NYSDEC TOGS (1.1.1), Ambient Water Quality Standards and Guidance Values and Groundwater Effluent Limitations. June 1998 (includes 4/2000 Addendum). Class GA. *- PCB Criteria based on sum of the aroclors.

Flags assigned during chemistry validation are shown.

Concentration Exceeds

J - The analyte was positively identified, the quantitation is an estimation.

Blank - not detected. - = No criteria.

Only Detected Results Reported.

TABLE 3-2

APPROVED REVISION OF TABLE 3.2 FROM THE O&M PLAN

GROUNDWATER SAMPLING SUMMARY OPERATION AND MAINTENANCE PLAN PFOHL BROTHERS LANDFILL SITE, CHEEKTOWAGA, NEW YORK

LOCATIONS

GW-1D/1S GW- 3D/3S GW- 4D/4S GW- 7D/7S GW- 8D/8S(R) GW- 26D/35S GW- 28S GW- 29S GW- 30S GW- 31S GW- 31S GW- 32S GW- 33S GW- 34S

FREQUENCY

semi-annually for overburden and bedrock groundwater

PARAMETERS

Field	pH conductivity temperature turbidity
VOCs	Acetone Benzene 1,2-Dichloroethene (total) 1,1,2-Trichloroethane Vinyl chloride
SVOCs	Phenol 1,3-Dichlorobenzene 1,4-Dichlorobenzene

bis(2-Ethylhexyl)phthalate

TABLE 3-2 (continued)


APPROVED REVISION OF TABLE 3.2 FROM THE O&M PLAN


GROUNDWATER SAMPLING SUMMARY OPERATION AND MAINTENANCE PLAN PFOHL BROTHERS LANDFILL SITE, CHEEKTOWAGA, NEW YORK

PARAMETERS (cont'd)

Metals Antimony Arsenic Barium Cadmium Chromium Copper Iron Lead Magnesium Manganese Mercury Nickel Silver Sodium Zinc

FIGURES





APPENDIX A

EXAMPLE DAILY INSPECTION SHEETS

N:\11172700.0000\WORD\DRAFT\Semi Annual Report Jan-Jun12\Semi Annual Report Jan-Jun12.doc

Pfohl Brothers Landfill Site

rate $2 \cdot 14 - 12$ $2 \cdot 15$ Weather conditions $LT. 5 \wedge 0 \omega$ $B + U =$ Time $2 \cdot 15$ Read by: $B + U =$ Level of Water from bottom (ft.)Flow gallons / minuteFlow Totals gallonsPump Ru Hrs gallonsWW-3 5.8 o $443, 977$ 1776 WW-2 4.7 o -3558 $12 \cdot 1$ WW-1 4.0 o $1, 120, 371$ 17973 WW-3 6.0 65.8 $4, 383, 8 \circ 2$ 7176 WW-4 7.0 o $641, 349$ 5172 WW-5 7.1 o $2, 765, 976$ 8766 Flow Totalizer at Meter chamber $9, 948, 237$ Heat Trace Outside temp T = 30° Current A = 2.72 Set point SP = 40° Irge Suppressor events $414, 795$ Motor Control Center Vots $414, 795$ Motor Control Center Vots $414, 795$ Motor Control Center Wuts $414, 795$ Wuts </th <th></th>	
from bottom (ft.)gallons / minutegallonsHrsWW-3 5.8 \circ $(43, 977)$ 7776 WW-2 4.7 \circ -3558 121 WW-1 4.0 \circ $1, 120, 371$ 1793 WW-6 6.2 65.8 $4, 383, 8.62$ 71.96 WW-4 7.0 \circ $641, 347$ 5172 WW-5 7.1 \circ $2, 965, 976$ 8766 Flow Totalizer at Meter chamber $9, 948, 237$ Heat Trace $9, 948, 237$ Current $A = 2.72$ Set point $SP = 40^{\circ}$ Irge Suppressor events $414, 795$ Motor Control Center $Volts$ Which WW was running? $Amps$ 6 amps $10.20.30.40.50.66$ FilterChanged 0Comments and/or Current ConditionsChanged 0	1 30 PUGH
WW-2 4.7 o -3558 171 WW-1 4.0 o $1, 120, 371$ 1793 WW-6 6.0 65.8 $4, 383, 802$ 7196 WW-4 7.0 o $641, 349$ 5172 WW-5 7.1 o $2, 765, 976$ 8766 Flow Totalizer at Meter chamber $9, 948, 237$ Heat Trace 0 0 $2, 765, 976$ 8766 Current $A = 2.2$ Set point $SP = 40^{\circ}$ Irge Suppressor events $414, 795$ Motor Control Center $volts$ $wlitch WW was running?$ $Motor Control CentervoltsampsIn 20.30.40.50.61/2FilterChanged 0Comments and/or Current Conditions$	
WW-1 4.0 0 $1, 120, 371$ 1793 WW-6 6.0 65.8 $4.383, 8.02$ 7196 WW-6 7.0 0 $641, 349$ 5172 WW-5 7.1 0 $2, 765, 976$ 8763 Flow Totalizer at Meter chamber $9, 948, 237$ Heat Trace $9, 948, 237$ Current $A = 2.72$ Set point $SP = 40^{\circ}$ Irge Suppressor events $414, 795$ Motor Control CentervoltsWhich WW was running?Motor Control Centeramps 10203040506 FliterChanged 0 Comments and/or Current Conditions	
WW-6 6.0 65.8 $4.383, 8.02$ 7196 WW-4 7.0 0 $641, 349$ 5172 WW-5 7.1 0 $2,765,976$ 8766 Flow Totalizer at Meter chamber $9,948,231$ Heat Trace $9,948,231$ Gurrent $A = 7.72$ Set point $SP = 40^{\circ}$ Irge Suppressor events $414,795$ Motor Control Center Volts 480 Volts 480 volts Which WW was running? Amps 6 amps 10203040506 Filter Checked 0 Changed 0 Comments and/or Current Conditions Changed 0	
WW-4 7.0 0 $641, 349$ 5172 WW-5 7.1 0 $2, 765, 976$ 8766 Flow Totalizer at Meter chamber $9, 948, 237$ Heat Trace $9, 948, 237$ Outside temp T = 30° Set point SP = 40° Current A = 2.2 Set point SP = 40° Irge Suppressor events $414, 795$ Motor Control Center volts Which WW was running? Amps 6 amps 1020304050 Filter Changed 0 Changed 0 Comments and/or Current Conditions Comments and/or Current Conditions	
WW-57.102,965,9768766Flow Totalizer at Meter chamber $g, 948, 237$ Heat Trace Outside temp T = 30° Current A = 2.2 Set point SP = 40° Irge Suppressor events $4 4, 795$ Motor Control Center VoltsvoltsWhich WW was running?Ampsamps 10203040506 FilterChanged 0Comments and/or Current Conditions	
Flow Totalizer at Meter chamber $g, 948, 231$ Heat Trace Outside temp T = 30° Set point SP = 40° Irge Suppressor events $4 4, 795$ Motor Control Center Volts Which WW was running? Amps 4 amps 1020304050 Filter Checked I Changed I Comments and/or Current Conditions Changed I	
Heat Trace Outside temp T = 30° Current A = 2.2 Irge Suppressor events Motor Control Center Volts <u>480</u> volts Amps <u>6</u> amps <u>10203040506</u> Filter Checked Changed Change	3
Outside temp T = 30° Set point SP = 4.0 Irge Suppressor events $4 4, 795^{\circ}$ Motor Control Center volts Which WW was running? Amps amps 10 20 30 40 50 6 K Filter Checked 0 Changed 0 Comments and/or Current Conditions Changed 0	
Motor Control Center Volts 480 volts Which WW was running? Amps 6 amps 1 = 2 = 3 = 4 = 5 = 6 K Filter Checked I Changed I Comments and/or Current Conditions	
Volts 480 volts Which WW was running? Amps 6 amps 1 □ 2 □ 3 □ 4 □ 5 □ 6 € Filter Checked □ Changed □ Comments and/or Current Conditions	
Amps 6 amps 1 □ 2 □ 3 □ 4 □ 5 □ 6 k Filter Checked □ Changed □ Cha	
Comments and/or Current Conditions	
WWZ NEG ROW ALARM - CLEARED AN ALA REMOVED JOIN LOGSHEERS TO ENG. DEDT F	
REMOVED JOIN LOGSHEETS TO ENG. DEDT F	rms
	-ne
	and the second

Pfohl Brothers Landfill Site

Daily L	ogsheet		Town of Cheektowa	aga
)ate Time	4/23/12		Weather conditions Read by:	AT. SNOW OVERCAST 32° BILL PUGH
	Level of Water from bottom (ft.)	Flow gallons / minute	Flow Totals gallons	Pump Run Time Hrs.
WW-3	5.1	0	945,618	1936
WW-2	4.6	0	- 44917	121
WW-1	4.5	0	1,241,330	/881
WW-6	7.5	0	5,806,317	7585
WW-4	7.0	0	708,554	5215
WW-5	7.7	0	3,769,628	9077
Flow Tot	alizer at Meter chamber		12,658,293)
Heat Trac	Current A = 20	3 - -	Set point SP = 4-0	
irge Su	ppressor events	414,825		
Motor Co	ntrol Center Volts 480	volts	Which WW was running?	>
	Amps 5	amps	10 20 30 40 50 60	
Filter	Checked 🛛	Changed 🛛		
Comment	s and/or Current Condition			
	WW4 Fil	W JAVAU	N - WILL NOT	PESET
	REMOTE INHIB	sit onl		

				مر می از می اور
		a Marine a Marine and an ann ann ann ann ann ann ann ann		

Pfohl Brothers Landfill Site

Daily Log	gsheet		Town of Cheektowa	ga
vate Time	6/11/12 2:05		Weather conditions Read by:	SUNNY 82° B. PUGH
WW-3 WW-2 WW-1 WW-6 WW-4 WW-5 Flow Tota	Level of Water from bottom (ft.) 5.8 4.7 4.2 6.9 7.1 7.1 7.7 lizer at Meter chamber	Flow gallons / minute 0 0 0 0 0	Flow Totals gallons 1, 132, 294 -5117 1, 372, 639 6, 511, 214 708, 631 4, 359, 295 14, 268, 576	Pump Run Time Hrs. 2050 121 1973 7775 5215 9298
Heat Trace	Outside temp T = 82 Current A = 0		Set point SP = <i>A0</i>	
irge Sup	pressor events	414,841		
Motor Con	trol Center Volts 460 Amps 9	volts amps	Which WW was running? 1 0 2 0 3 0 4 0 5 0 6 0	
Filter	Checked 🛛	Changed 🛛		
Comments	and/or Current Condition	S		
	Lowbrets A	.C. p	78°	
ر میں پر اور اور اور اور اور اور اور اور اور او				

APPENDIX B

MONTHLY FLOW SUMMARIES JANUARY 2012 – JUNE 2012

The TOWN OF CHEEKTOWAGA



Jon W. Nichy Superintendent Joseph Glab Asst. Superintendent Main Pump Station 171 Central Blvd. Cheektowaga, NY 14225 Phone: 716-896-1777 Fax: 716-896-6437

February 2, 2012

Mr. William R. Pugh, P.E. Town Engineer Town of Cheektowaga

Re: Pfohl Bros. Flow Data

Dear Mr. Pugh,

Enclosed for your review, please find a copy of the January 2012 Direct Discharge Flow Data Report, prepared by Jon W. Nichy.

Should you have any other questions or comments regarding this submittal, please contact this office @ 896-1777.


Yours truly,

Jon W. Nichy Superintendent Main Pump Station

Direct Discharge Flow Data

v

12/12/201		7252183	98,563	7,239,005	
January-12	11:58pm 11:58pm unless otherwise stated	Totalizer Reading (Gallons)	Daily Total Discharge (Gallons)	Total Direct Discharge (Gallons)	Notes
1		7427863	175,680	7,414,685	ανα παι το πολογομικό με πολογολογοριστικό το σύμφατα που ματά το πολογοριστικό το πολογοριστικό το συγγαριστικό Το πολογοριστικό το πολογοριστικό το πολογοριστικό το πολογοριστικό που πολογοριστικό το πολογοριστικό πολογορισ
2		7561417	133,555	7,548,240	9.999999999999999999999999999999999999
3		7571957	10,540	7,558,780	
4	-	7587682	15,725	7,574,505	
5		7607660	19,979	7,594,484	
6		7739392	131,732	7,726,216	entralizzation de la construcción d
7		7781144	41,752	7,767,968	
8		7798132	16,989	7,784,957	
9		7827310	29,178	7,814,135	
10		7842173	14,863	7,828,998	
11		7922540	80,367	7,909,365	
12		7932976	10,437	7,919,802	0029inhibit 2239enable
13		8075700	142,724	8,062,526	
14		8185786	110,086	8,172,612	
15		8291515	105,729	8,278,341	
16		8307491	15,976	8,294,317	2240inhibit
17		8307491	0	8,294,317	
18		8410954	103,464	8,397,781	0956enable
19		8566451	155,497	8,553,278	
20		8582403	15,952	8,569,230	
21		8593706	11,303	8,580,533	
22		8675969	82,263	8,662,796	
23		8682737	6,768	8,669,564	0912inhibit
24		8682737	0	8,669,564	
25		8682737	0	8,669,564	
26		8682737	0	8,669,564	
27		8682737	0	8,669,564	
28		8773614	90,877	8,760,441	0709enable 1728inhibit
29		8872399	98,785	8,859,226	1129enable
30		9077645	205,246	9,064,472	
31		9272351	194,706	9,259,178	
		2,020,168	2,020,173	2,020,173	



đ

20

The TOWN OF CHEEKTOWAGA



Jon W. Nichy Superintendent Joseph Glab Asst. Superintendent Main Pump Station 171 Central Blvd. Cheektowaga, NY 14225 Phone: 716-896-1777 Fax: 716-896-6437

March 3, 2012

Mr. William R. Pugh, P.E. Town Engineer Town of Cheektowaga

Re: Pfohl Bros. Flow Data

Dear Mr. Pugh,

Enclosed for your review, please find a copy of the **February 2012** Direct Discharge Flow Data Report, prepared by Jon W. Nichy.

Should you have any other questions or comments regarding this submittal, please contact this office @ 896-1777.

Yours truly,


LAG

Jon W. Nichy Superintendent Main Pump Station

Direct Discharge Flow Data

ě

			<u> </u>		
12/12/20		9272351	194,706	9,259,178	
February-12	February-12		Daily Total Discharge (Gallons)	Total Direct Discharge (Gallons)	Notes
1		9413081	140,730	9,399,908	
2		9532459	119,378	9,519,286	
3		9560050	27,591	9,546,877	
4		9562667	2,617	9,549,494	₩₩₩₩₩₩₩₩₩₩₩₩₩₩₩₩₩₩₩₩₩₩₩₩₩₩₩₩₩₩₩₩₩₩₩₩₩
5		9627855	65,188	9,614,682	
6		9770733	142,878	9,757,560	
7		9781749	11,016	9,768,576	
8		9797838	16,089	9,784,665	
9		9810390	12,552	9,797,217	
10		9810390	0	9,797,217	
11		9813737	3,347	9,800,564	
12		9851201	37,464	9,838,028	
13		9872719	21,518	9,859,546	
14		9969076	96,357	9,955,903	
15		9984244	15,168	9,971,071	
16		9995554	11,310	9,982,381	
17		10067610	72,056	10,054,437	0002inhibit 0941enabl
18		10170918	103,308	10,157,745	
19		10272336	101,418	10,259,163	
20		10297634	25,298	10,284,461	
21		10311829	14,195	10,298,656	
22		1038671	71,842	10,370,498	0031inhibit 0821enabl
23		10444503	60,832	10,431,330	1435inhibit 2244enabl
24		10479793	35,290	10,466,620	0303inhibit
25		10579238	99,445	10,566,065	1004enable
26		10724031	144,793	10,710,858	
27	-	10798320	74,289	10,785,147	
28		10828783	30,463	10,815,610	
29	l	10833508	4,725	10,820,335	
30					
31		1,561,157	1,561,157	1,561,157	······





ų

\$

The TOWN OF CHEEKTOWAGA



Jon W. Nichy Superintendent Joseph Glab Asst. Superintendent Main Pump Station 171 Central Blvd. Cheektowaga, NY 14225 Phone: 716-896-1777 Fax: 716-896-6437

April 7, 2012

Mr. William R. Pugh, P.E. Town Engineer Town of Cheektowaga

Re: Pfohl Bros. Flow Data

Dear Mr. Pugh,

Enclosed for your review, please find a copy of the March 2012 Direct Discharge Flow Data Report, prepared by Jon W. Nichy.

Should you have any other questions or comments regarding this submittal, please contact this office @ 896-1777.


Yours truly. Jon W. Nichy/ Superintendent

Superintendent Main Pump Station

Direct Discharge Flow Data

		••••••••••••••••••••••••••••••••••••••		· · · · · · · · · · · · · · · · · · ·	
2/29/2		10833508	4,725	10,820,335	
March-12	11:58pm 11:58pm unless otherwise stated	Totalizer Reading (Gallons)	Daily Total Discharge (Gallons)	Total Direct Discharge (Gallons)	Notes
1		10913638	80,130	10,900,465	0006inhibit 0701enable
2		11014230	100,592	11,001,057	2221inhibit
3		11093755	79,525	11,080,582	0638enable
4		11130020	36,265	11,116,847	occenable
5		11142187	12,167	11,129,014	
6		11152039	9,852	11,138,866	
7		11166989	14,950	11,153,816	*********
8		11205728	38,739	11,192,555	1622inhibit
9		11205728	0	11,192,555	TOZZITERON
10		11205728	0	11,192,555	
11		11205728	0	11,192,555	
12		11205728	0	11,192,555	
13		11327332	121,604	11,314,159	0747enable
14		11522414	195,082	11,509,241	
15		11643018	120,604	11,629,845	······································
16		11643018	0	11,629,845	0300inhibit 0612enabl
17		11643018	0	11,629,845	
18		11674660	31,642	11,661,487	
19		11674660	0	11,661,487	
20		11752603	77,943	11,739,430	
21		11789308	36,705	11,776,135	*****
22		11829359	40,051	11,816,186	
23		11864094	34,735	11,850,921	
24		11873556	9,462	11,860,383	2322inhibit
25		11924957	51,401	11,911,784	0827enable
26		12025225	100,268	12,012,052	
27		12036117	10,892	12,022,944	
28		12036117	0	12,022,944	
29		12038563	2,446	12,025,390	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,
30		12073961	35,398	12,060,788	
31		12073961	0	12,060,788	·····
	-	1,240,453	1,240,453	1,240,453	······································

4



The TOWN OF CHEEKTOWAGA



Jon W. Nichy Superintendent Joseph Glab Asst. Superintendent Main Pump Station 171 Central Blvd. Cheektowaga, NY 14225 Phone: 716-896-1777 Fax: 716-896-6437

May 1, 2012

Mr. William R. Pugh, P.E. Town Engineer Town of Cheektowaga

Re: Pfohl Bros. Flow Data

Dear Mr. Pugh,

Enclosed for your review, please find a copy of the April 2012 Direct Discharge Flow Data Report, prepared by Jon W. Nichy.

Should you have any other questions or comments regarding this submittal, please contact this office @ 896-1777.

Yours truly,


Jon W. Nichy/

Superintendent Main Pump Station

Direct Discharge Flow Data

ß

				1	
3/31/2012		12073961	0	12,060,788	
April-12	11:58pm 11:58pm unless otherwise stated	Totalizer Reading (Gallons)	Daily Total Discharge (Gallons)	Total Direct Discharge (Gallons)	Notes
1	1	12073961	0	12,060,788	1329 inhibit
2		12073961	0	12,060,788	0050 enable
3		12164095	90,134	12,150,922	анан табимий и инистриција и транција и транц
4		12317739	153,644	12,304,566	
5		12340068	22,329	12,326,895	
6		12340068	0	12,326,895	
7		12340068	0	12,326,895	<u>, and an </u>
8		12377272	37,104	12,363,999	
9		12385929	8,657	12,372,656	
10		12385929	0	12,372,656	
11		12385929	0	12,372,656	
12		12392502	6,573	12,379,229	
13		12418627	26,125	12,405,354	
14		12510303	91,676	12,497,030	
15		12516719	6,416	12,503,446	
16		12516719	0	12,503,446	
17		12516719	0	12,503,446	
18		12517367	648	12,504,094	
19		12535667	18,300	12,522,394	
20		12576436	40,769	12,563,163	
21		12603435	26,999	12,590,162	2034 inhibit
22		12603435	0	12,590,162	
23		12637173	33,738	12,623,900	0443 enable 1609 inhib
24		12658293	21,120	12,645,020	
25		12781797	123,504	12,768,524	2002 enable
26		12964227	182,430	12,950,954	
27		13038163	73,936	13,024,890	
28		13038163	0	13,024,890	
29		13048061	9,898	13,034,788	
30		13084801	36,740	13,071,528	
	1				



April 2012

The TOWN OF CHEEKTOWAGA



Jon W. Nichy Superintendent Joseph Glab Asst. Superintendent Main Pump Station 171 Central Blvd. Cheektowaga, NY 14225 Phone: 716-896-1777 Fax: 716-896-6437

June 2, 2012

Mr. William R. Pugh, P.E. Town Engineer Town of Cheektowaga

Re: Pfohl Bros. Flow Data

Dear Mr. Pugh,

Enclosed for your review, please find a copy of the May 2012 Direct Discharge Flow Data Report, prepared by Jon W. Nichy.

Should you have any other questions or comments regarding this submittal, please contact this office @ 896-1777.


Yours truly,

Jon W. Nichy Superintendent Main Pump Station

Direct Discharge Flow Data

*

	1	······			
4/30/20		13084801	36,740	13,071,528	
May-12	Ime; 11:58pm unless otherwise stated		Daily Total Discharge (Gallons)	Total Direct Discharge (Gallons)	Notes
1		13147699	62,898	13,134,426	0816 inhibit 1224 enable
2		13282362	134,663	13,269,089	
3		13354530	72,168	13,341,257	
4		13354530	0	13,341,257	0007 inhibit 0728 enable
5		13354530	0	13,341,257	
6		13387455	32,925	13,374,182	<u> </u>
7		13410734	23,279	13,397,461	
8		13452088	41,354	13,438,815	
9		13558359	106,271	13,545,086	
10		13622494	64,135	13,609,221	
11		13635862	13,368	13,622,589	
12		13658141	22,279	13,644,868	
13		13684147	26,006	13,670,874	
14		13693387	9,240	13,680,114	
15		13711928	18,541	13,698,655	
16		13711928	0	13,698,655	
17		13711928	0	13,698,655	
18		13724184	12,256	13,710,911	<u></u>
19		13748296	24,112	13,735,023	
20		13782690	34,394	13,769,417	
21		13856110	73,420	13,842,837	
22		13895307	39,197	13,882,034	
23		13907079	11,772	13,893,806	
24		13908509	1,430	13,895,236	
25		13908509	0	13,895,236	
26		13927050	18,541	13,913,777	
27		13936158	9,108	13,922,885	
28		13951813	15,655	13,938,540	
29		13965191	13,378	13,951,918	
30		13975665	10,474	13,962,392	
31		13991552	15,887	13,978,279	
		906,751	906,751	906,751	





The TOWN OF CHEEKTOWAGA



Jon W. Nichy Superintendent Joseph Glab Asst. Superintendent **Main Pump Station**

171 Central Blvd. Cheektowaga, NY 14225 Phone: 716-896-1777 Fax: 716-896-6437

July 12, 2012

Mr. William R. Pugh, P.E. Town Engineer Town of Cheektowaga

Re: Pfohl Bros. Flow Data

Dear Mr. Pugh,

Enclosed for your review, please find a copy of the June 2012 Direct Discharge Flow Data Report, prepared by Jon W. Nichy.

Should you have any other questions or comments regarding this submittal, please contact this office @ 896-1777.


Yours truly,

Jon W. Nichy

Superintendent Main Pump Station

Direct Discharge Flow Data

5/31/2	017	13983857	15,887	13,978,279]
June-12	11:58pm unless otherwise stated	Totalizer Reading (Gallons)	Daily Total Discharge (Gallons)	Total Direct Discharge (Gallons)	Notes
1		13991552	7,695	13,985,974	1236 inhibit
2		14067530	75,978	14,061,952	0924 enable
3		14102023	34,493	14,096,445	0718 inhibit
4		14106959	4,936	14,101,381	2058 enable
5		14232237	125,278	14,226,659	
6		14232237	0	14,226,659	
7		14232237	0	14,226,659	
8		14268576	36,399	14,263,058	
9		14268576	0	14,263,058	
10		14268576	0	14,263,058	
11		14279922	11,346	14,274,404	annan an a
12		14296448	16,526		0037 inhibit 1820 enable
13		14307954	11,506	14,302,436	
14		14324877	16,923	14,319,359	
15		14387433	62,556	14,381,915	
16		14451442	64,009	14,445,924	
17		14453747	2,305	14,448,229	1326 inhibit
18		14472815	19,068	14,467,297	1332 enable
19		14484036	11,221	14,478,518	, ////////////////////////////////////
20		14513179	29,143	14,507,661	
21		14547759	34,580	14,542,241	MANGE - MERCAN MANANANA CARA ANA ANA ANA ANA ANA ANA ANA ANA ANA
22		14583170	35,411	14,577,652	
23		14592236	9,066	14,586,718	***************************************
24		14602028	9,792	14,596,510	
25		14607844	5,816	14,602,326	
26		14618712	10,868	14,613,194	••••••••••••••••••••••••••••••••••••••
27		14627006	8,294	14,621,488	
28		14639735	12,729	14,634,217	, , , , , , , , , , , , , , , , , , ,
29		14678481	38,746	14,672,963	
30		14727189	48,708	14,721,671	······································
31					
		743,332	743,392	743,392	



ď

₩.

APPENDIX C

HYDRAULIC MONITORING TABLES

N:\11172700.00000\WORD\DRAFT\Semi Annual Report Jan-Jun12\Semi Annual Report Jan-Jun12.doc

Location ID / Type	Northing	Easting	Ground Elevation (ft)	Casing Elevation (ft)	Meas.point (Riser)Elev.(ft)	Geol. Zone	Specific Gravity	Date / Time	Depth to Water (ft)	Water Elev. (ft)	Product Thick. (ft)	Corrected Water Elev. (ft)	Remark
GW-01D	1073088.634	1117968.213	694.41	NM	696.12	D	1						
MNW								3/26/2012 1124	2.75	693.37	0.00	693.37	
MNW								5/15/2012 0942	3.09	693.03	0.00	693.03	
MNW								6/20/2012 1413	3.85	692.27	0.00	692.27	
GW-01S	1073087.779	1117961.500	694.53	NM	696.19	S	1						
MNW								3/26/2012 1124	3.59	692.60	0.00	692.60	
MNW								5/15/2012 0942	4.24	691.95	0.00	691.95	
MNW								6/20/2012 1413	4.97	691.22	0.00	691.22	
GW-03D	1073819.106	1114602.426	692.35	NM	693.88	D	1						
MNW								3/26/2012 1009	2.11	691.77	0.00	691.77	
MNW								5/15/2012 0845	2.29	691.59	0.00	691.59	
MNW								6/20/2012 1311	2.57	691.31	0.00	691.31	
GW-03S	1073812.622	1114605.762	692.61	NM	693.80	S	1						
MNW								3/26/2012 1009	2.30	691.50	0.00	691.50	
MNW								5/15/2012 0845	2.73	691.07	0.00	691.07	
MNW								6/20/2012 1311	5.43	688.37	0.00	688.37	
GW-04D	1072289.432	1114685.625	690.89	NM	692.75	D	1						
MNW								3/26/2012 1132	13.08	679.67	0.00	679.67	
MNW								5/15/2012 0937	13.04	679.71	0.00	679.71	
MNW								6/20/2012 1419	13.58	679.17	0.00	679.17	
GW-04S	1072284.456	1114685.127	690.76	NM	692.72	S	1						
MNW								3/26/2012 1132	4.34	688.38	0.00	688.38	
MNW								5/15/2012 0937	4.66	688.06	0.00	688.06	
MNW								6/20/2012 1419	5.82	686.90	0.00	686.90	

NM - No Measurement

The value noted in the column labeled Specific Gravity is an assumed value for free product, if found.

Page 1 of 7

Type: MH

MNW

SG

Manhole Monitoring Point Monitoring Well Staff Gauge

Location ID / Type	Northing	Easting	Ground Elevation (ft)	Casing Elevation (ft)	Meas.point (Riser)Elev.(ft)	Geol. Zone	Specific Gravity	Date / Time	Depth to Water (ft)	Water Elev. (ft)	Product Thick. (ft)	Corrected Water Elev. (ft)	Remark
GW-07D	1071242.458	1117669.925	697.15	NM	699.94	D	1						
MNW								3/26/2012 1101	47.52	652.42	0.00	652.42	
MNW								5/15/2012 0947	44.25	655.69	0.00	655.69	
MNW								6/20/2012 1405	56.77	643.17	0.00	643.17	
GW-07S	1071238.157	1117666.265	697.47	NM	699.51	S	1						
MNW								3/26/2012 1101	4.90	694.61	0.00	694.61	
MNW								5/15/2012 0946	5.00	694.51	0.00	694.51	
MNW								6/20/2012 1405	5.88	693.63	0.00	693.63	
GW-08D	1073713.617	1116795.328	695.28	NM	697.79	D	1						
MNW								3/26/2012 1024	6.07	691.72	0.00	691.72	
MNW								5/15/2012 0856	6.27	691.52	0.00	691.52	
MNW								6/20/2012 1325	6.56	691.23	0.00	691.23	
GW-08SR	1073714.172	1116786.343	695.08	NM	697.50	S	1						
MNW								3/26/2012 1024	5.22	692.28	0.00	692.28	
MNW								5/15/2012 0857	5.34	692.16	0.00	692.16	
MNW								6/20/2012 1325	6.02	691.48	0.00	691.48	
GW-26D	1071698.573	1115997.470	696.01	NM	698.50	D	1						
MNW								3/26/2012 1051	6.94	691.56	0.00	691.56	
MNW								5/15/2012 0922	7.12	691.38	0.00	691.38	
MNW								6/20/2012 1355	7.41	691.09	0.00	691.09	
GW-28S	1073129.479	1117648.927	698.60	NM	700.95	S	1						
MNW								3/26/2012 1030	9.09	691.86	0.00	691.86	
MNW								5/15/2012 0903	9.27	691.68	0.00	691.68	
MNW								6/20/2012 1335	10.17	690.78	0.00	690.78	

NM - No Measurement

Filter = ([tblGWD].[LOGDATE]>=#3/26/2012#)

The value noted in the column labeled Specific Gravity is an assumed value for free product, if found.

Manhole Monitoring Point Monitoring Well Staff Gauge



MNW

SG

Location ID / Type	Northing	Easting	Ground Elevation (ft)	Casing Elevation (ft)	Meas.point (Riser)Elev.(ft)	Geol. Zone	Specific Gravity	Date / Time	Depth to Water (ft)	Water Elev. (ft)	Product Thick. (ft)	Corrected Water Elev. (ft)	Remark
GW-29S	1072552.638	1117761.993	697.50	NM	699.63	S	1						
MNW								3/26/2012 1038	8.29	691.34	0.00	691.34	
MNW								5/15/2012 0910	8.39	691.24	0.00	691.24	
MNW								6/20/2012 1342	9.72	689.91	0.00	689.91	
GW-30S	1072096.109	1117743.563	693.67	NM	696.58	S	1						
MNW								3/26/2012 1041	7.95	688.63	0.00	688.63	
MNW								5/15/2012 0912	8.05	688.53	0.00	688.53	
MNW								6/20/2012 1345	8.20	688.38	0.00	688.38	
GW-31S	1071786.280	1117191.441	695.84	NM	698.62	S	1						
MNW								3/26/2012 1044	2.86	695.76	0.00	695.76	
MNW								5/15/2012 0916	3.45	695.17	0.00	695.17	
MNW								6/20/2012 1348	5.77	692.85	0.00	692.85	
GW-32S	1071613.793	1116364.200	696.19	NM	698.37	S	1						
MNW								3/26/2012 1048	2.78	695.59	0.00	695.59	
MNW								5/15/2012 0919	3.81	694.56	0.00	694.56	
MNW								6/20/2012 1352	5.30	693.07	0.00	693.07	
GW-33S	1072165.625	1115561.866	695.94	NM	698.24	S	1						
MNW								3/26/2012 1055	3.94	694.30	0.00	694.30	
MNW								5/15/2012 0924	5.60	692.64	0.00	692.64	
MNW								6/20/2012 1359	7.03	691.21	0.00	691.21	
GW-34S	1072979.205	1114730.200	692.51	NM	694.77	S	1						
MNW								3/26/2012 1007	2.64	692.13	0.00	692.13	
MNW								5/15/2012 0838	3.05	691.72	0.00	691.72	
MNW								6/20/2012 1304	5.48	689.29	0.00	689.29	

NM - No Measurement

The value noted in the column labeled Specific Gravity is an assumed value for free product, if found.

Printe	d: 8/30/2012 4:28:03 PN
N:\11172700.00000\GIS\dB\Program\EDN	IS.mde/Groundwater Lev

Manhole Monitoring Point

Monitoring Well

Staff Gauge

Type:

MNW

MH

SG

Filter = ([tbIGWD].[LOGDATE]>=#3/26/2012#)

Location ID / Type	Northing	Easting	Ground Elevation (ft)	Casing Elevation (ft)	Meas.point (Riser)Elev.(ft)	Geol. Zone	Specific Gravity	Date / Time	Depth to Water (ft)	Water Elev. (ft)	Product Thick. (ft)	Corrected Water Elev. (ft)	Remark
GW-35S	1071701.925	1115985.585	696.19	NM	697.39	S	1						
MNW								3/26/2012 1052	3.41	693.98	0.00	693.98	
MNW								5/15/2012 0922	3.81	693.58	0.00	693.58	
MNW								6/20/2012 1355	5.55	691.84	0.00	691.84	
MH-01	1073806.665	1114810.501	698.62	NM	698.62	NA	1						
MH								3/26/2012 1008	10.35	688.27	0.00	688.27	
MH								5/15/2012 0842	10.23	688.39	0.00	688.39	
MH								6/20/2012 1308	10.10	688.52	0.00	688.52	
MH-03	1073736.789	1115259.334	699.40	NM	699.40	NA	1						
MH								3/26/2012 1018	11.13	688.27	0.00	688.27	
MH								5/15/2012 0849	11.07	688.33	0.00	688.33	
MH								6/20/2012 1315	11.02	688.38	0.00	688.38	
MH-07	1073838.229	1116243.757	696.82	NM	696.82	NA	1						
MH								3/26/2012 1020	9.33	687.49	0.00	687.49	
MH								5/15/2012 0853	9.29	687.53	0.00	687.53	
MH								6/20/2012 1319	9.20	687.62	0.00	687.62	
MH-10	1073540.729	1117381.524	703.01	NM	703.01	NA	1						
MH								3/26/2012 1028	14.46	688.55	0.00	688.55	
MH								5/15/2012 0900	14.50	688.51	0.00	688.51	
MH								6/20/2012 1332	14.45	688.56	0.00	688.56	
MH-15	1072531.567	1117761.125	699.02	NM	699.02	NA	1						
MH								3/26/2012 1037	14.98	684.04	0.00	684.04	
MH								5/15/2012 0910	14.90	684.12	0.00	684.12	
MH								6/20/2012 1341	14.94	684.08	0.00	684.08	

NM - No Measurement

The value noted in the column labeled Specific Gravity is an assumed value for free product, if found.

Staff Gauge

Filter = ([tblGWD].[LOGDATE]>=#3/26/2012#)

Type: MH MNW

SG

Manhole Monitoring Point Monitoring Well

Location I Type	D/	Northing	Easting	Ground Elevation (ft)	Casing Elevation (ft)	Meas.point (Riser)Elev.(ft)	Geol. Zone	Specific Gravity	Date / Time	Depth to Water (ft)	Water Elev. (ft)	Product Thick. (ft)	Corrected Water Elev. (ft)	Remark
MH-16	1	1072133.714	1117748.238	698.57	NM	698.57	NA	1						
	мн								3/26/2012 1041	14.55	684.02	0.00	684.02	
	MH								5/15/2012 0912	14.46	684.11	0.00	684.11	
	MH								6/20/2012 1344	14.50	684.07	0.00	684.07	
MH-17	1	1071813.137	1117180.019	702.16	NM	702.16	NA	1						
	мн								3/26/2012 1044	18.96	683.20	0.00	683.20	
	MH								5/15/2012 0916	18.11	684.05	0.00	684.05	
	MH								6/20/2012 1347	18.11	684.05	0.00	684.05	
MH-20	1	1071756.395	1115997.024	706.20	NM	706.20	NA	1						
	мн								3/26/2012 1049	19.73	686.47	0.00	686.47	
	ΜН								5/15/2012 0921	19.73	686.47	0.00	686.47	
	MH								6/20/2012 1354	19.71	686.49	0.00	686.49	
MH-22	1	1072158.023	1115589.309	698.05	NM	698.05	NA	1						
	мн								3/26/2012 1055	9.00	689.05	0.00	689.05	
	ΜΗ								5/15/2012 0923	9.04	689.01	0.00	689.01	
	MH								6/20/2012 1358	9.00	689.05	0.00	689.05	
MH-25	1	1072483.928	1114820.313	698.17	NM	698.17	NA	1						
	мн								3/26/2012 1005	10.04	688.13	0.00	688.13	
	ΜН								5/15/2012 0831	9.83	688.34	0.00	688.34	
	MH								6/20/2012 1301	9.72	688.45	0.00	688.45	
SG-01	1	1073882.887	1114813.101	NM	NM	690.00	NA	1						
	SG								3/26/2012 1014	-1.00	691.00	0.00	691.00	
	SG								5/15/2012 0844	-0.92	690.92	0.00	690.92	
	SG								6/20/2012 1308	Dry		0.00		Dry

NM - No Measurement

The value noted in the column labeled Specific Gravity is an assumed value for free product, if found.

Type: MH MNW

SG

Manhole Monitoring Point Monitoring Well

Staff Gauge

Location ID / Type	Northing	Easting	Ground Elevation (ft)	Casing Elevation (ft)	Meas.point (Riser)Elev.(ft)	Geol. Zone	Specific Gravity	Date / Time	Depth to Water (ft)	Water Elev. (ft)	Product Thick. (ft)	Corrected Water Elev. (ft)	Remark
SG-02	1073738.27	1116805.85	NM	NM	690.00	NA	1						
SG	à							3/26/2012 1024	-3.28	693.28	0.00	693.28	
SG	6							5/15/2012 0856	-3.10	693.10	0.00	693.10	
SG	ì							6/20/2012 1325	Dry		0.00		Dry
WW-01	1073676.903	1115710.476	NM	NM	684.02	NA	1						
MH	ł							3/26/2012 0930	-4.1	688.12	0.00	688.12	
MH	1							5/15/2012 0800	-4.1	688.12	0.00	688.12	
MH	ł							6/20/2012 1230	-4.2	688.22	0.00	688.22	
WW-02	1073684.724	1116792.311	NM	NM	684.18	NA	1						
MH	ł							3/26/2012 0930	-4.7	688.88	0.00	688.88	
MH	1							5/15/2012 0800	-4.6	688.78	0.00	688.78	
MH	ł							6/20/2012 1230	-4.7	688.88	0.00	688.88	
WW-03	1073140.339	1117618.499	NM	NM	683.80	NA	1						
MH	1							3/26/2012 0930	-5.0	688.80	0.00	688.80	
MH	1							5/15/2012 0800	-5.2	689.00	0.00	689.00	
MH	ł							6/20/2012 1230	-5.2	689.00	0.00	689.00	
WW-04	1072057.563	1117610.508	NM	NM	676.62	NA	1						
MH	ł							3/26/2012 0930	-6.9	683.52	0.00	683.52	
MH	1							5/15/2012 0800	-7.0	683.62	0.00	683.62	
MH	1							6/20/2012 1230	-7.0	683.62	0.00	683.62	
WW-05	1071661.368	1116370.876	NM	NM	676.14	NA	1						
MH	1							3/26/2012 0930	-6.7	682.84	0.00	682.84	
MH	1							5/15/2012 0800	-7.2	683.34	0.00	683.34	
MH	ł							6/20/2012 1230	-6.6	682.74	0.00	682.74	

NM - No Measurement

The value noted in the column labeled Specific Gravity is an assumed value for free product, if found.

Manhole Monitoring Point

Printed: 8/30/2012 4:28:03 PN N:\11172700.00000\GIS\dB\Program\EDMS.mde/Groundwater Lev

Filter = ([tblGWD].[LOGDATE]>=#3/26/2012#)

Type: MH MNW

SG

Monitoring Well Staff Gauge

I	Location ID / Type	Northing	Easting	Ground Elevation (ft)	Casing Elevation (ft)	Meas.point (Riser)Elev.(ft)		Specific Gravity		Depth to Water (ft)	Water Elev. (ft)	Product Thick. (ft)	Corrected Water Elev. (ft)	Remark
v	/W-06	1072988.420	1114811.518	NM	NM	681.89	NA	1						
	МН								3/26/2012 0930	-6.6	688.49	0.00	688.49	
	MH								5/15/2012 0800	-6.9	688.79	0.00	688.79	
	MH								6/20/2012 1230	-6.9	688.79	0.00	688.79	

NM - No Measurement

The value noted in the column labeled Specific Gravity is an assumed value for free product, if found.

 Type:

 MH
 Manhole Monitoring Point

 MNW
 Monitoring Well

 SG
 Staff Gauge

TABLE 2 PFOHL BROTHERS LANDFILL SITE **OVERBURDEN HYDRAULIC GRADIENT**

ſ	WELL PAIR:	WW-1	*	Level	WW-2	GW-8SR	Level	SG-02	Level
		Water Level	Water Level	Difference	Water Level	Water Level	Difference	Water Level	Difference
ſ	DATE	(ft amsl)	(ft amsl)	(ft)	(ft amsl)	(ft amsl)	(ft)	(ft amsl)	(ft)
	3/26/2012	688.12			688.88	692.28	3.40	693.28	4.40
ſ	5/15/2012	688.12			688.78	692.16	3.38	693.10	4.32
Γ	6/20/2012	688.22			688.88	691.48	2.60	DRY	NA
ſ	WELL PAIR:	WW-3	GW-28S	Level	WW-4	*	Level		
		Water Level	Water Level	Difference	Water Level	Water Level	Difference]	
ſ	DATE	(ft amsl)	(ft amsl)	(ft)	(ft amsl)	(ft amsl)	(ft)		
	3/26/2012	688.80	691.86	3.06	683.52				
	5/15/2012	689.00	691.68	2.68	683.62				
ſ	6/20/2012	689.00	690.78	1.78	683.62				
Г	WELL PAIR:	WW-5	GW-32S	Level	WW-6	GW-34S	Level		
		Water Level	Water Level	Difference	Water Level	Water Level	Difference]	
ſ	DATE	(ft amsl)	(ft amsl)	(ft)	(ft amsl)	(ft amsl)	(ft)		
ſ	3/26/2012	682.84	695.59	12.75	688.49	692.13	3.64		
ſ	5/15/2012	683.34	694.56	11.22	688.79	691.72	2.93		
ſ	6/20/2012	682.74	693.07	10.33	688.79	689.29	0.50		
								_	
ſ	WELL PAIR:	MH-1	SG-1	Level	MH-15	GW-29S	Level]	
		Water Level	Water Level	Difference	Water Level	Water Level	Difference		
	DATE	(ft amsl)	(ft amsl)	(ft)	(ft amsl)	(ft amsl)	(ft)]	
ſ	3/26/2012	688.27	691.00	2.73	684.04	691.34	7.30		
ſ	5/15/2012	688.39	690.92	2.53	684.12	691.24	7.12		
	6/20/2012	688.52	DRY	NA	684.08	689.91	5.83	l	
_								-	
Γ	WELL PAIR:	MH-16	GW-30S	Level	MH-17	GW-31S	Level		
		Water Level	Water Level	Difference	Water Level	Water Level	Difference		
	DATE	(ft amsl)	(ft amsl)	(ft)	(ft amsl)	(ft amsl)	(ft)]	
ſ	3/26/2012	684.02	688.63	4.61	683.20	695.76	12.56		
	5/15/2012	684.11	688.53	4.42	684.05	695.17	11.12		
	6/20/2012	684.07	688.38	4.31	684.05	692.85	8.80	J	
								-	
ſ	WELL PAIR:	MH-20	GW-35S	Level	MH-22	GW-33S	Level]	
		Water Level	Water Level	Difference	Water Level	Water Level	Difference		
ſ	DATE	(ft amsl)	(ft amsl)	(ft)	(ft amsl)	(ft amsl)	(ft)		
ſ	3/26/2012	686.47	693.98	7.51	689.05	694.30	5.25		
	5/15/2012	686.47	693.58	7.11	689.01	692.64	3.63		
ſ	6/20/2012	686.49	691.84	5.35	689.05	691.21	2.16		

Notes:

* = No corresponding monitoring well. NA = Not applicable

APPENDIX D

GROUNDWATER PURGE AND SAMPLE COLLECTION LOGS

LOW FLOW GROUNDWATER PURGING/SAMPLING LOG

Project:	11175616.00000			Site:	Pfohl E	Brothers	Well I.D.:	GW-1S
Date:	5/17/2012	Sampling	Personnel:	Rob Mu	ırphy, Tim If	kovich	_ Company: _	URS Corporation
Purging/ Sampling Device:		Geopump 2		_Tubing Type:	LDPE/	Silicone	Pump/Tubing Inlet Location:	Screen midpoint
Measuring Point:	Below Top of Riser	Initial Depth to Water:	4.41'	Depth to Well Bottom:	14.94'	Well Diameter:	2"	Screen Length:
Casing Type:	Stainles	ss Steel		Volume in 1 Well Casing (liters):	6.5	-	Estimated Purge Volume (liters):	9.5
Sample ID:		GW-1S		Sample Time:	12	::59	QA/QC:	None
•	er Information:		ged inwards,	could not remove	e stainless s	teel bailer fror	n within well, sar	mpled around it.
		Orange stain in v	water initially.					

PURGE PARAMETERS

ТІМЕ	рН	TEMP (°C)	COND. (mS/cm)	DISS. O ₂ (mg/l)	TURB. (NTU)	ORP (mV)	FLOW RATE (ml/min.)	DEPTH TO WATER (btor)
12:14	6.68	14.32	0.722	2.60	716	-7	225	4.41
12:19	6.69	12.41	0.783	0.00	342	-32	210	NM
12:24	6.73	12.35	0.653	0.29	773	-41	210	5.20
12:29	6.73	12.14	0.717	0.00	523	-34	210	5.40
12:34	6.66	11.98	0.792	0.00	237	-33	210	5.46
12:39	6.58	11.89	0.835	0.00	99.4	-35	210	5.52
12:44	6.59	11.84	0.841	0.00	65.0	-37	210	5.55
12:49	6.60	11.89	0.845	0.00	50.0	-39	210	5.55
12:54	6.62	11.89	0.846	0.00	50.8	-41	210	5.56
12:59	6.64	11.88	0.847	0.00	47.7	-43	210	5.57
Tolerance:	0.1		3%	10%	10%	+ or - 10		

Information: WATER VOLUMES--0.75 inch diameter well = 87 ml/ft; 1 inch diameter well = 154 ml/ft; 2 inch diameter well = 617 ml/ft; 4 inch diameter well = 2470 ml/ft ($vol_{cvl} = \pi r^2h$)

LOW FLOW GROUNDWATER PURGING/SAMPLING LOG

Project:	11175616.00000			Site:	Pfohl B	Brothers	Well I.D.:	GW-1D
Date:	5/17/2012	Sampling I	Personnel:	Rob Mu	ırphy, Tim Ifl	kovich	_ Company: _	URS Corporation
Purging/ Sampling Device:		Geopump 2		Tubing Type:	LDPE/	Silicone	Pump/Tubing Inlet Location:	Screen midpoint
Measuring Point:	Below Top of Riser	Initial Depth to Water:	3.23'	Depth to Well Bottom:	39.65'	Well Diameter:	4"	Screen Length:
Casing Type:	Stainles	s Steel		Volume in 1 Well Casing (liters):	90.0		Estimated Purge Volume (liters):	62.2
Sample ID:		GW-1D		Sample Time:	14	:43	QA/QC:	None
•	er Information:	VOCs, SVOCs, a Sulfur odor Dark Tint	Ind TAL Meta	als				

PURGE PARAMETERS

TIME	рН	TEMP (°C)	COND. (mS/cm)	DISS. O ₂ (mg/l)	TURB. (NTU)	ORP (mV)	FLOW RATE (ml/min.)	DEPTH TO WATER (btor)
13:18	6.89	17.07	0.932	2.31	>800	-50	440	3.23
13:23	7.02	13.27	0.998	0.00	41.8	-94	750	3.26
13:28	7.01	12.86	1.01	0.00	12.0	-102	750	3.27
13:33	7.04	12.76	1.01	0.00	14.0	-107	750	3.28
13:38	7.02	12.63	1.01	0.00	16.7	-109	750	3.28
13:43	7.00	12.64	1.01	0.00	15.1	-110	750	3.28
13:48	7.03	12.70	1.00	0.00	19.2	-113	750	3.28
13:53	7.07	12.73	1.00	0.00	24.3	-116	750	3.28
13:58	7.06	12.60	1.01	0.00	15.6	-121	750	3.28
14:03	7.04	12.58	1.01	0.00	13.3	-127	750	3.28
14:08	7.03	12.52	1.01	0.00	10.5	-133	750	3.28
14:13	7.05	12.81	0.997	0.00	8.2	-142	750	3.28
14:18	7.04	12.89	0.996	0.00	5.2	-150	750	3.28
14:23	7.04	12.84	0.996	0.00	5.2	-156	750	3.28
14:28	7.04	12.76	0.997	0.00	1.9	-161	750	3.28
14:33	7.04	12.66	1.00	0.00	1.8	-168	750	3.28
14:38	7.04	12.61	1.00	0.00	0.0	-173	750	3.28
14:43	7.04	12.82	0.996	0.00	0.0	-178	750	3.28
Tolerance:	0.1		3%	10%	10%	+ or - 10		

Information: WATER VOLUMES--0.75 inch diameter well = 87 ml/ft; 1 inch diameter well = 154 ml/ft; 2 inch diameter well = 617 ml/ft; 4 inch diameter well = 2470 ml/ft ($vol_{cvl} = \pi r^2h$)

LOW FLOW GROUNDWATER	R PURGING/SAMPLING LOG
----------------------	-------------------------------

Project:	11175616.00000			Site:	Pfohl B	Brothers	Well I.D.:	GW-3S
Date:	5/15/2012	Sampling F	Personnel:	Rob Mu	ırphy, Tim Ifl	kovich	_ Company: _	URS Corporation
Purging/ Sampling Device:		Geopump 2		Tubing Type:	LDPE/S	Silicone	Pump/Tubing Inlet Location:	Screen midpoint
Measuring Point:	Below Top of Riser	Initial Depth to Water:	3.20'	Depth to Well Bottom:	13.22'	Well Diameter:	2"	Screen Length:
Casing Type:	Stainles	s Steel		Volume in 1 Well Casing (liters):	6.2		Estimated Purge Volume (liters):	8.7
Sample ID:		GW-3S		Sample Time:	12	:44	QA/QC:	None
	e Parameters: er Information:	VOCs, SVOCs, ar	nd TAL Meta	als				

PURGE PARAMETERS

TIME	рН	TEMP (°C)	COND. (mS/cm)	DISS. O ₂ (mg/l)	TURB. (NTU)	ORP (mV)	FLOW RATE (ml/min.)	DEPTH TO WATER (btor)
11:57	7.42	17.11	1.020	1.97	45.1	89	275	3.20
12:04	7.15	18.41	0.985	1.35	25.1	82	250	5.28
12:09	6.93	18.54	0.969	0.12	14.1	77	185	5.61
12:14	6.83	18.72	0.957	0.00	9.4	81	185	6.18
12:19	6.77	19.07	0.960	0.07	9.7	84	145	6.44
12:24	6.74	19.51	0.947	0.09	11.9	87	145	6.70
12:29	6.71	20.00	0.933	0.16	10.4	89	145	6.95
12:34	6.69	20.34	0.926	0.16	9.5	90	145	7.07
12:39	6.68	20.76	0.911	0.11	8.8	92	145	7.25
12:44	6.67	21.02	0.905	0.11	9.3	93	145	7.39
Tolerance:	0.1	l I	3%	10%	10%	+ or - 10		

Information: WATER VOLUMES--0.75 inch diameter well = 87 ml/ft; 1 inch diameter well = 154 ml/ft; 2 inch diameter well = 617 ml/ft; 4 inch diameter well = 2470 ml/ft ($vol_{cvl} = \pi r^2h$)

LOW FLOW GROUNDWATER PURGING/SAMPLING LOG

Project:	11175616.00000			Site: Pfohl Brothers		Well I.D.:	GW-3D	
Date:	5/15/2012 Sampling Personnel:			Rob Murphy, Tim Ifkovich			Company:	URS Corporation
Purging/ Sampling Device:		Geopump 2		Tubing Type:	LDPE/	Silicone	Pump/Tubing Inlet Location:	Screen midpoint
Measuring Point:	Below Top of Riser	Initial Depth to Water:	2.27'	Depth to Well Bottom:	35.70'	Well Diameter:	4"	Screen Length:
Casing Type:	Stainles	s Steel		Volume in 1 Well Casing (liters):	82.6		Estimated Purge Volume (liters):	54.0
Sample ID:	GW-3D		Sample Time:	14:09		QA/QC:	MS/MSD	
Sample Parameters: VOCs, SVOCs, and TAL Metals Other Information:								

PURGE PARAMETERS

TIME	рН	TEMP (°C)	COND. (mS/cm)	DISS. O ₂ (mg/l)	TURB. (NTU)	ORP (mV)	FLOW RATE (ml/min.)	DEPTH TO WATER (btor)
13:09	6.17	15.70	1.43	0.00	66.9	40	900	2.27
13:14	6.43	13.89	1.49	0.00	9.6	2	900	2.27
13:19	6.46	13.52	1.50	0.00	10.2	-10	900	2.27
13:24	6.45	13.31	1.51	0.00	7.5	-13	900	2.27
13:29	6.44	13.17	1.51	0.00	4.7	-16	900	2.27
13:34	6.55	13.36	1.51	0.00	3.6	-24	900	2.27
13:39	6.54	13.13	1.51	0.00	3.7	-25	900	2.27
13:44	6.53	13.03	1.52	0.00	4.3	-26	900	2.27
13:49	6.54	13.67	1.50	0.00	5.2	-27	900	2.27
13:54	6.55	14.25	1.47	0.00	7.1	-29	900	2.27
13:59	6.55	13.74	1.49	0.00	3.2	-29	900	2.27
14:04	6.53	13.54	1.49	0.00	3.3	-29	900	2.27
14:09	6.51	13.36	1.50	0.00	1.3	-28	900	2.27
Tolerance:	0.1		3%	10%	10%	+ or - 10		

Information: WATER VOLUMES--0.75 inch diameter well = 87 ml/ft; 1 inch diameter well = 154 ml/ft; 2 inch diameter well = 617 ml/ft; 4 inch diameter well = 2470 ml/ft ($vol_{cvl} = \pi r^2h$)

Project:		11175616.00000		Site:	Pfohl E	Brothers	Well I.D.:	GW-4S	
Date:	5/16/2012	Sampling Perso	nnel:	Rob M	urphy, Tim Ifl	kovich	Company:	URS Corporation	
Purging/ Sampling Device:		Geopump 2		Tubing Type:	LDPE/3	Silicone	Pump/Tubing Inlet Location:	Screen midpoint	
Measuring Point:	Below Top of Riser		-	Depth to Well Bottom:	16.23'	Well Diameter:	2"	Screen Length:	
Casing Type:	Stainles	s Steel		Volume in 1 Well Casing (liters):	7.1		Estimated Purge Volume (liters):	17.0	
Sample ID:		GW-4S		Sample Time:		/OCs/ Cs & Metals	QA/QC:	None	
Sample Parameters: VOCs, SVOCs, and TAL Metals Other Information: Placed passive diffusion bag (PDB) in well 3/26/12, sampled VOCs from PDB at 9:00 on 5/16/12 Well historically goes dry at very low purge rates (<75ml/min). Bailed dry and sampled for SVOCs and Metals after recovery at 10:35.									

PURGE PARAMETERS

TIME	рН	TEMP (°C)	COND. (mS/cm)	DISS. O ₂ (mg/l)	TURB. (NTU)	ORP (mV)	FLOW RATE (ml/min.)	DEPTH TO WATER (btor)
9:06	7.49	15.15	0.456	5.75	23.5	113	Intial	4.72
9:08	7.71	13.06	0.456	3.77	167.0	113	2 Gal. Purged	-
9:11	7.65	12.59	0.477	3.38	>800	64	4.5 Gal. Purged	
Tolerance:	0.1		3%	10%	10%	+ or - 10		

Project:		11175616.00000		Site:	Pfohl E	Brothers	Well I.D.:	GW-4D
Date:	5/16/2012	Sampling	Personnel:	Rob Murphy, Tim Ifkovich			_ Company: _	URS Corporation
Purging/ Sampling Device:		Geopump 2		Tubing Type:	LDPE/	Silicone	Pump/Tubing Inlet Location:	Screen midpoint
Measuring Point:	Below Top of Riser	Initial Depth to Water:	12.91'	Depth to Well Bottom:	45.57'	Well Diameter:	4"	Screen Length:
Casing Type:	Stainles	s Steel		Volume in 1 Well Casing (liters):	80.7	-	Estimated Purge Volume (liters):	8.8
Sample ID:		GW-4D		Sample Time:	10):17	QA/QC:	None
•	e Parameters: er Information:	VOCs, SVOCs, a	and TAL Meta	als				

PURGE PARAMETERS

TIME	рН	TEMP (°C)	COND. (mS/cm)	DISS. O ₂ (mg/l)	TURB. (NTU)	ORP (mV)	FLOW RATE (ml/min.)	DEPTH TO WATER (btor)
9:22	7.06	16.39	1.20	0.42	9.2	-56	160	12.91
9:27	6.95	17.21	1.17	0.00	14.1	-86	160	13.27
9:32	6.91	17.77	1.16	0.00	15.2	-113	160	13.57
9:37	6.92	18.11	1.14	0.00	13.3	-136	160	13.70
9:42	6.92	18.40	1.14	0.00	10.7	-153	160	13.81
9:47	6.93	18.52	1.14	0.00	7.7	-168	160	13.98
9:52	6.93	18.13	1.13	0.00	7.4	-188	160	14.10
9:57	6.94	18.82	1.26	0.00	5.2	-210	160	14.23
10:02	6.94	19.05	1.27	0.00	1.6	-223	160	14.33
10:07	6.94	19.22	1.27	0.00	0.0	-229	160	14.39
10:12	6.95	19.93	1.27	0.00	0.0	-234	160	14.47
10:17	6.96	20.06	1.27	0.00	0.0	-238	160	14.55
Tolerance:	0.1		3%	10%	10%	+ or - 10		

WELL PURGING LOG

URS Corporation

		-									
SITE NAME:	Pfohl Brot	hers La	ndfill					WELL NO.:	G	W-7S	
PROJECT NO.:	11175616	6.00000									
STAFF:	Rob Murp	hy, Tim	lfkovich								
DATE(S):	5/15/12, 5	5/16/12									
1. TOTAL CASING	AND SCREI	EN LENG	TH (FT.)			=	35	.04	WELL ID. 1"	VOL. (GAL/FT) 0.040	
2. WATER LEVEL	BELOW TOP	P OF CAS	SING (FT.)			=	5.00		2"	0.17	
3. NUMBER OF FI	EET STANDI	NG WATE	ER (#1 - #2)		=	30	.04	3"	0.38	
4. VOLUME OF W	ATER/FOOT	OF CASI	NG (GAL.)			=	0.	17	4"	0.66	
5. VOLUME OF W	VOLUME OF WATER IN CASING (GAL.)(#3 x #4)							.1	5"	1.04	
6. VOLUME OF W	ATER TO RE	EMOVE (G	GAL.)(#5 x	3)		=			6"	1.50	
7. VOLUME OF W	7. VOLUME OF WATER ACTUALLY REMOVED (GAL.)							.5	8"	2.60	
								V=	=0.0408 x (CASING	DIAMETER [INCHES]	
					ACCUN	ULATED	VOLUME F	PURGED (GA	ALLONS)		
PARAMETERS		Initial	2.0	4.0	6.0	7.5					
рН		7.63	7.56	7.44	7.33	7.47					
SPEC. COND. (mS/	cm)	0.582	0.582	0.587	0.584	0.570					
DO (mg/l)		6.45	8.32	6.20	7.21	7.21					
TEMPERATURE (°C	C)	12.17	11.55	12.07	12.69	13.04					
TURBIDITY (NTU)		7.1	15.5	9.8	150	161					
ORP (millivolts)		26	42	60	78	79					
TIME		11:05	11:06	11:09	11:15	11:20					
COMMENTS: 5/16/2012	10:05 - Fill 11:05 - Beg 11:20 - We 15:40 - retu 15:45 - Col	gin handt II dry afte urn to we	bailing wel er removin II, depth to	l. ng 7.5 gall o water =	lons. 5.18 feet.	·	was instal	led on 3/26/	12		

WELL PURGING LOG

URS Corporation

	rothers La	ndfill					WELL NO	.:G	GW-7D	
	urphy, Tim	lfkovich								
	2, 5/16/12									
1. TOTAL CASING AND SCREEN LENGTH (FT.) = 60.45 WELL ID. VOL. (GAL/FT) 1. TOTAL CASING AND SCREEN LENGTH (FT.) = 60.45 1" 0.040										
2. WATER LEVEL BELOW	TOP OF CAS	ING (FT.)			=	44	.25	2"	0.17	
3. NUMBER OF FEET STA	NDING WATE	ER (#1 - #2	2)		=	16.20		3"	0.38	
4. VOLUME OF WATER/FC	OT OF CASI	NG (GAL.)			=	0.	66	4"	0.66	
5. VOLUME OF WATER IN	CASING (GA	L.)(#3 x #4	l)		=	10.7		5"	1.04	
6. VOLUME OF WATER TO	REMOVE (0	GAL.)(#5 x	3)		=			6"	1.50	
7. VOLUME OF WATER AC	TUALLY REI	MOVED (G	iAL.)		=	10).7	8"	2.60	
								V=0.0408 x (CASING	DIAMETER [INCHES]) ²	
		1		ACCUM	ULATED		PURGED (GALLONS)		
PARAMETERS	Init	2	4	6	8	10	10.7			
рН	8.95	8.23	7.85	7.60	7.74	7.35	7.42			

рп		0.90	0.23	7.00	7.60	1.74	7.35	7.42			
SPEC. COND. (mS/	cm)	0.717	0.656	0.671	0.718	0.754	0.806	0.794			
DO (mg/)		16.80	8.65	11.90	12.47	11.95	4.06	8.85			
TEMPERATURE (⁰ C	C)	15.65	14.40	13.94	13.83	13.91	13.77	14.16			
TURBIDITY (NTU)		5.0	18.3	23.5	27.8	30.2	29.5	61.9			
ORP (millivolts)		4	14	24	10	-2	-26	21			
TIME		10:18	10:24	10:29	10:35	10:44	10:50	10:59			
COMMENTS: 10:00 - Fill VOCs from passive diffusion bag (PDB), PDB was installed on 3/26/12 10:12 - Begin handbailing well. 10:59 - Well dry after removing 10.7 gallons 5/16/2012 15:48 - return to well, depth to water = 59.30 feet. 15:50 - Collect sample for SVOCs and Metals, only enough volume to fill 1 metals container and 1-1 liter Amber container.								iber			

LOW FLOW GROUNDWATER	R PURGING/SAMPLING LOG
----------------------	------------------------

Project:	1	11175616.00000		Site:	Pfohl E	Brothers	Well I.D.:	GW-8SR
Date:	5/15/2012	Sampling F	ersonnel:	Rob Murphy, Tim Ifkovich			_ Company: _	URS Corporation
Purging/ Sampling Device:		Geopump 2		Tubing Type:	LDPE/S	Silicone	Pump/Tubing Inlet Location:	Screen midpoint
Measuring Point:	Below Top of Riser	Initial Depth to Water:	5.33'	Depth to Well Bottom:	13.02'	Well Diameter:	2"	Screen Length:
Casing Type:	Stainles	s Steel		Volume in 1 Well Casing (liters):	4.7	-	Estimated Purge Volume (liters):	5.9
Sample ID:		GW-8SR		Sample Time:	16	:25	QA/QC:	None
	e Parameters: er Information:	VOCs, SVOCs, ar	nd TAL Meta	als				

TIME	рН	TEMP (°C)	COND. (mS/cm)	DISS. O ₂ (mg/l)	TURB. (NTU)	ORP (mV)	FLOW RATE (ml/min.)	DEPTH TO WATER (btor)
16:00	6.31	13.03	3.04	0.00	36.0	-6	315	5.33
16:05	6.16	13.12	3.05	0.00	35.3	-13	230	7.08
16:10	6.09	13.17	3.04	0.00	61.3	-17	230	7.55
16:15	6.07	13.43	3.04	0.00	65.8	-20	200	7.63
16:20	6.06	13.47	3.04	0.00	61.0	-22	200	7.70
16:25	6.06	13.44	3.04	0.00	59.0	-23	200	7.74
Tolerance:	0.1		3%	10%	10%	+ or - 10		

Project:		1175616.00000	Site:	Pfohl I	Brothers	Well I.D.:	GW-8D
Date:	5/15/2012	Sampling Personne	el: Rob M	urphy, Tim li	fkovich	_ Company:	URS Corporation
Purging/ Sampling Device:		Geopump 2	Tubing Type:	LDPE	/Silicone	Pump/Tubing Inlet Location:	Screen midpoint
Measuring Point:	Below Top of Riser	Initial Depth to Water: <u>6.26</u>	Depth to Well Bottom:	36.54'	Well Diameter:	4"	Screen Length:
Casing Type:	Stainles	s Steel	Volume in 1 Well Casing (liters):	74.8	-	Estimated Purge Volume (liters):	43.3
Sample ID:		GW-8D	Sample Time:	15	5:47	QA/QC:	Duplicate (ID=Duplicate)
•	e Parameters:	VOCs, SVOCs, and TAL Me	elais				

PURGE PARAMETERS

TIME	рН	TEMP (°C)	COND. (mS/cm)	DISS. O ₂ (mg/l)	TURB. (NTU)	ORP (mV)	FLOW RATE (ml/min.)	DEPTH TO WATER (btor)
14:52	6.73	13.61	2.64	1.57	>800	-53	860	6.26
14:57	6.63	12.46	2.71	0.00	12.2	-51	780	6.26
15:02	6.62	12.39	2.70	0.00	10.1	-52	780	6.26
15:07	6.58	12.40	2.67	0.00	5.4	-51	780	6.26
15:12	6.59	12.29	2.33	0.00	10.6	-45	780	6.26
15:17	6.64	12.22	1.86	0.00	4.5	-39	780	6.26
15:22	6.63	12.09	1.76	0.00	2.3	-21	780	6.26
15:27	6.61	12.19	1.75	0.00	2.3	-10	780	6.26
15:32	6.60	12.16	1.75	0.00	1.4	-2	780	6.26
15:37	6.58	12.17	1.75	0.00	1.7	4	780	6.26
15:42	6.58	12.20	1.75	0.00	1.3	7	780	6.26
15:47	6.58	12.18	1.74	0.00	1.3	11	780	6.26
Tolerance:	0.1	I	3%	10%	10%	+ or - 10		

Project:	11175616.00000			Site:	Pfohl Brothers		Well I.D.:	GW-26D		
Date:	5/16/2012 Sampling Personnel:			Rob Murphy, Tim Ifkovich			Company:	URS Corporation		
Purging/ Sampling Device:		Geopump 2		Tubing Type:	LDPE/	Silicone	Pump/Tubing Inlet Location:	Screen midpoint		
Measuring Point:	Below Top of Riser	Initial Depth to Water:	7.15'	Depth to Well Bottom:	40.70'	Well Diameter:	4"	Screen Length:		
Casing Type:	Stainles	s Steel		Volume in 1 Well Casing (liters):	82.9		Estimated Purge Volume (liters):	33.2		
Sample ID:		GW-26D		Sample Time:	13	:44	QA/QC:	None		
	Sample Parameters: VOCs, SVOCs, and TAL Metals Other Information: Occasional pulses of iron stained particulates in purge water.									

PURGE PARAMETERS

TIME	рН	TEMP (°C)	COND. (mS/cm)	DISS. O ₂ (mg/l)	TURB. (NTU)	ORP (mV)	FLOW RATE (ml/min.)	DEPTH TO WATER (btor)
13:04	5.91	12.89	2.70	2.28	35.4	3	830	7.15
13:09	6.11	12.67	2.72	0.00	5.7	-7	830	7.15
13:14	6.27	12.54	2.75	0.00	0.4	-18	830	7.15
13:19	6.34	12.56	2.76	0.00	1.9	-23	830	7.15
13:24	6.35	12.49	2.75	0.00	2.2	-26	830	7.15
13:29	6.36	12.46	2.76	0.00	1.2	-28	830	7.15
13:34	6.35	12.43	2.76	0.00	0.6	-29	830	7.15
13:39	6.33	12.44	2.76	0.00	0.0	-29	830	7.15
13:44	6.35	12.43	2.75	0.00	0.0	-30	830	7.15
Tolerance:	0.1		3%	10%	10%	+ or - 10		

LOW FLOW GROUNDWATER	R PURGING/SAMPLING LOG
----------------------	------------------------

Project:	11175616.00000			Site:	te: Pfohl Brothers		Well I.D.:	GW-28S		
Date:	5/16/2012	Sampling P	ersonnel:	Rob Murphy, Tim Ifkovich		_ Company: _	URS Corporation			
Purging/ Sampling Device:		Geopump 2		Tubing Type:	LDPE/S	Silicone	Pump/Tubing Inlet Location:	Screen midpoint		
Measuring Point:	Below Top of Riser	Initial Depth to Water:	9.32'	Depth to Well Bottom:	15.52'	Well Diameter:	2"	Screen Length:		
Casing Type:	Stainles	s Steel		Volume in 1 Well Casing (liters):	3.8		Estimated Purge Volume (liters):	9.8		
Sample ID:		GW-28S		Sample Time:	11	:53	QA/QC:	None		
	Sample Parameters: VOCs, SVOCs, and TAL Metals Other Information: Orange floc. in purge water									

TIME	рН	TEMP (°C)	COND. (mS/cm)	DISS. O ₂ (mg/l)	TURB. (NTU)	ORP (mV)	FLOW RATE (ml/min.)	DEPTH TO WATER (btor)
11:03	7.63	15.26	0.549	2.98	50.1	-43	255	9.32
11:08	7.16	12.36	0.560	0.00	34.8	-34	190	10.58
11:13	6.97	11.95	0.547	0.00	0.0	-27	190	10.82
11:18	6.90	11.85	0.544	0.00	0.1	-20	190	10.85
11:23	6.77	11.75	0.555	0.06	0.8	-7	190	10.92
11:28	6.67	11.65	0.570	0.00	0.0	0	190	10.98
11:33	6.55	11.52	0.584	0.00	0.0	6	190	10.99
11:38	6.48	11.46	0.591	0.00	0.0	10	190	11.00
11:43	6.39	11.41	0.593	0.00	0.0	14	190	11.01
11:48	6.34	11.33	0.597	0.00	0.0	16	190	11.01
11:53	6.37	11.30	0.600	0.00	0.0	17	190	11.00
Tolerance:	0.1		3%	10%	10%	+ or - 10		

Project:		11175616.00000			Pfohl B	Brothers	Well I.D.:	GW-29S			
Date:	5/16/2012 Sampling Personnel:			Rob Murphy, Tim Ifkovich			_ Company: _	URS Corporation			
Purging/ Sampling Device:		Geopump 2		Tubing Type:	LDPE/S	Silicone	Pump/Tubing Inlet Location:	Screen midpoint			
Measuring Point:	Below Top of Riser	Initial Depth to Water:	8.56'	Depth to Well Bottom:	20.04'	Well Diameter:	2"	Screen Length:			
Casing Type:	Stainles	s Steel		Volume in 1 Well Casing (liters):	7.1		Estimated Purge Volume (liters):	10.7			
Sample ID:		GW-29S		Sample Time:	15	:13	QA/QC:	None			
	Sample Parameters: VOCs, SVOCs, and TAL Metals Other Information: Orange iron particulates at start of purge										

PURGE PARAMETERS

TIME	рН	TEMP (°C)	COND. (mS/cm)	DISS. O ₂ (mg/l)	TURB. (NTU)	ORP (mV)	FLOW RATE (ml/min.)	DEPTH TO WATER (btor)
14:07	7.32	12.79	1.27	1.22	>800	-29	250	8.56
14:12	6.80	12.19	1.27	0.00	692	-32	155	1.32
14:17	6.59	12.17	1.24	0.00	524	-32	155	10.55
14:22	6.50	12.62	1.24	0.00	387	-30	155	10.63
14:27	6.50	12.67	1.24	0.00	239	-30	155	10.74
14:32	6.48	13.01	1.30	0.00	220	-32	155	10.82
14:37	6.45	13.19	1.33	0.00	197	-33	155	10.89
14:42	6.43	13.36	1.34	0.00	132	-35	155	10.92
14:47	6.42	13.51	1.34	0.00	112	-36	155	10.96
14:52	6.41	13.62	1.35	0.00	82.2	-37	155	11.00
14:57	6.41	13.70	1.35	0.00	64.5	-38	155	11.03
15:02	6.40	13.85	1.35	0.00	58.3	-39	155	11.07
15:07	6.40	14.10	1.35	0.00	47.4	-40	155	11.11
15:10	6.40	13.83	1.36	0.00	45.6	-40	155	11.13
15:13	6.38	13.47	1.37	0.00	45.8	-40	155	11.15
Tolerance:	0.1		3%	10%	10%	+ or - 10		

LOW FLOW GROUNDWATER	R PURGING/SAMPLING LOG
----------------------	------------------------

Project:	11175616.00000			Site: Pfohl Brothers		Well I.D.:	GW-30S				
Date:	5/17/2012	Sampling F	Personnel:	Rob Murphy, Tim Ifkovich		_ Company: _	URS Corporation				
Purging/ Sampling Device:		Geopump 2		Tubing Type:	LDPE/	Silicone	Pump/Tubing Inlet Location:	Screen midpoint			
Measuring Point:	Below Top of Riser	Initial Depth to Water:	8.12'	Depth to Well Bottom:	17.97'	Well Diameter:	2"	Screen Length:			
Casing Type:	Stainles	s Steel		Volume in 1 Well Casing (liters):	6.1	-	Estimated Purge Volume (liters):	31.5			
Sample ID:		GW-30S		Sample Time:	8	42	QA/QC:	None			
	Sample Parameters: VOCs, SVOCs, and TAL Metals Other Information:										

TIME	рН	TEMP (°C)	COND. (mS/cm)	DISS. O ₂ (mg/l)	TURB. (NTU)	ORP (mV)	FLOW RATE (ml/min.)	DEPTH TO WATER (btor)
8:07	6.05	10.99	3.08	4.00	322	-11	900	8.12
8:12	6.38	10.45	1.48	0.00	24.0	-30	900	8.27
8:17	6.30	10.37	1.46	0.00	12.0	-33	900	8.28
8:22	6.24	10.34	1.43	0.00	7.6	-34	900	8.28
8:27	6.20	10.33	1.42	0.00	5.7	-33	900	8.28
8:32	6.33	10.32	1.41	0.00	5.2	-43	900	8.28
8:37	6.35	10.32	1.39	0.00	4.1	-44	900	8.28
8:42	6.34	10.32	1.38	0.00	3.1	-44	900	8.28
Tolerance:	0.1		3%	10%	10%	+ or - 10		

LOW FLOW GROUNDWATER	R PURGING/SAMPLING LOG
----------------------	------------------------

Project:	11175616.00000			Site: Pfohl Brothers		Well I.D.:	GW-31S			
Date:	5/17/2012	Sampling F	Personnel:	Rob Mu	urphy, Tim Ifkovich		_ Company: _	URS Corporation		
Purging/ Sampling Device:		Geopump 2		Tubing Type:	LDPE/	'Silicone	Pump/Tubing Inlet Location:	Screen midpoint		
Measuring Point:	Below Top of Riser	Initial Depth to Water:	3.85'	Depth to Well Bottom:	9.57'	Well Diameter:	2"	Screen Length:		
Casing Type:	Stainles	s Steel		Volume in 1 Well Casing (liters):	3.5	-	Estimated Purge Volume (liters):	4.3		
Sample ID:		GW-31S		Sample Time:	9	:30	QA/QC:	None		
	Sample Parameters: VOCs, SVOCs, and TAL Metals Other Information:									

TIME	рН	TEMP (°C)	COND. (mS/cm)	DISS. O ₂ (mg/l)	TURB. (NTU)	ORP (mV)	FLOW RATE (ml/min.)	DEPTH TO WATER (btor)
9:00	6.82	12.34	0.680	5.73	8.8	-26	205	3.85
9:05	6.70	12.54	0.663	0.00	3.2	13	145	5.42
9:10	6.69	12.54	0.664	0.00	7.9	21	145	5.81
9:15	6.69	12.51	0.665	0.00	6.4	27	145	6.30
9:20	6.68	12.76	0.674	0.00	6.4	30	110	6.41
9:25	6.68	12.75	0.676	0.00	9.1	34	110	6.51
9:30	6.67	12.81	0.678	0.00	8.1	36	110	6.62
Tolerance:	0.1		3%	10%	10%	+ or - 10		

LOW FLOW GROUNDWATER	R PURGING/SAMPLING LOG
----------------------	------------------------

Project:	11175616.00000			Site:	Pfohl Brothers		Well I.D.:	GW-32S
Date:	5/17/2012 Sampling Personnel:		Rob Mu	Rob Murphy, Tim Ifkovich			URS Corporation	
Purging/ Sampling Device:		Geopump 2		Tubing Type:	LDPE/	'Silicone	Pump/Tubing Inlet Location:	Screen midpoint
Measuring Point:	Below Top of Initial Depth Riser to Water: 4.14'		Depth to Well Bottom:	9.93'	Well Diameter:	2"	Screen Length:	
Casing Type:	Stainles	s Steel		Volume in 1 Well Casing (liters):	3.6	-	Estimated Purge Volume (liters):	6.4
Sample ID:		GW-32S		Sample Time:	10):42	QA/QC:	None
	e Parameters: er Information:	VOCs, SVOCs, a	and TAL Meta	als				

TIME	рН	TEMP (°C)	COND. (mS/cm)	DISS. O ₂ (mg/l)	TURB. (NTU)	ORP (mV)	FLOW RATE (ml/min.)	DEPTH TO WATER (btor)
10:07	7.39	14.04	0.477	7.17	7.4	104	255	4.14
10:12	7.26	13.00	0.483	5.09	4.1	111	170	4.70
10:17	7.11	12.39	0.524	0.68	0.4	107	170	4.68
10:22	7.01	12.30	0.532	0.00	0.6	96	170	4.70
10:27	6.98	12.19	0.537	0.00	0.0	90	170	4.72
10:32	6.97	12.16	0.537	0.00	0.0	84	170	4.75
10:37	6.96	12.19	0.538	0.00	0.0	81	170	4.77
10:42	6.96	12.19	0.537	0.00	0.0	81	170	4.78
Tolerance:	0.1		3%	10%	10%	+ or - 10		

Project:	11175616.00000			Site:	Site: Pfohl Brothers		Well I.D.:	GW-33S
Date:	5/17/2012 Sampling Personnel:		Rob Murphy, Tim Ifkovich			_ Company: _	URS Corporation	
Purging/ Sampling Device:		Geopump 2		Tubing Type:	LDPE/	/Silicone	Pump/Tubing Inlet Location:	Screen midpoint
Measuring Point:	Below Top of Riser	Initial Depth to Water:	5.98'	Depth to Well Bottom:	8.21'	Well Diameter:	2"	Screen Length:
Casing Type:	Stainles	s Steel		Volume in 1 Well Casing (liters):	1.4	-	Estimated Purge Volume (liters):	4.9
Sample ID:		GW-33S		Sample Time:	11	1:41	QA/QC:	None
	e Parameters:	VOCs, SVOCs, a	Ind TAL Meta	als				

TIME	рН	TEMP (°C)	COND. (mS/cm)	DISS. O ₂ (mg/l)	TURB. (NTU)	ORP (mV)	FLOW RATE (ml/min.)	DEPTH TO WATER (btor)
11:06	6.92	16.86	0.721	0.63	0.0	137	140	5.98
11:11	6.74	16.86	0.640	0.00	0.0	126	140	6.53
11:16	6.73	17.00	0.628	0.00	0.0	112	140	6.75
11:21	6.70	16.90	0.632	0.00	0.0	105	140	6.90
11:26	6.68	16.81	0.639	0.00	0.0	99	140	7.05
11:31	6.66	16.63	0.651	0.00	0.0	93	140	7.20
11:36	6.65	16.60	0.656	0.00	0.0	89	140	7.35
11:41	6.64	16.57	0.669	0.00	0.0	89	140	7.50
Tolerance:	0.1		3%	10%	10%	+ or - 10		

Project:		11175616.00000			Site: Pfohl Brothers		Well I.D.:	GW-34S
Date:	5/16/2012 Sampling Personnel:		Rob Mu	Rob Murphy, Tim Ifkovich			URS Corporation	
Purging/ Sampling Device:		Geopump 2		_Tubing Type: _	LDPE/	Silicone	Pump/Tubing Inlet Location:	Screen midpoint
Measuring Point:	Below Top of Initial Depth Riser to Water: <u>3.11'</u>		Depth to Well Bottom:	10.01'	Well Diameter:	2"	Screen Length:	
Casing Type:	Stainles	s Steel		Volume in 1 Well Casing (liters):	4.3	-	Estimated Purge Volume (liters):	4.2
Sample ID:		GW-34S		Sample Time:	8:	:30	QA/QC:	None
•	e Parameters:	VOCs, SVOCs, a	nd TAL Meta	als				

PURGE PARAMETERS

TIME	рН	TEMP (°C)	COND. (mS/cm)	DISS. O ₂ (mg/l)	TURB. (NTU)	ORP (mV)	FLOW RATE (ml/min.)	DEPTH TO WATER (btor)
8:00	7.72	17.91	1.06	1.93	131	102	140	3.11
8:05	6.97	17.91	1.01	0.04	114	69	140	4.40
8:10	6.82	16.92	0.915	0.37	22.2	71	140	4.53
8:15	6.71	16.45	0.926	0.13	14.5	81	140	4.62
8:20	6.62	16.41	0.926	0.00	9.4	87	140	4.71
8:25	6.57	16.35	0.922	0.00	6.9	88	140	4.75
8:30	6.51	16.15	0.918	0.00	6.0	88	140	4.79
Tolerance:	0.1		3%	10%	10%	+ or - 10		

LOW FLOW GROUNDWATER	R PURGING/SAMPLING LOG
----------------------	------------------------

Project:	11175616.00000			Site:	e: Pfohl Brothers		Well I.D.:	GW-35S
Date:	5/16/2012 Sampling Personnel:		Rob Mu	Rob Murphy, Tim Ifkovich			URS Corporation	
Purging/ Sampling Device:		Geopump 2		Tubing Type:	LDPE/	Silicone	Pump/Tubing Inlet Location:	Screen midpoint
Measuring Point:	Below Top of Initial Depth Riser to Water: 3.94'		Depth to Well Bottom:	7.46'	Well Diameter:	2"	Screen Length:	
Casing Type:	Stainles	s Steel		Volume in 1 Well Casing (liters):	2.2	-	Estimated Purge Volume (liters):	5.5
Sample ID:		GW-35S		Sample Time:	12	2:50	QA/QC:	None
•	e Parameters: er Information:	VOCs, SVOCs, a	and TAL Meta	als				

TIME	рН	TEMP (°C)	COND. (mS/cm)	DISS. O ₂ (mg/l)	TURB. (NTU)	ORP (mV)	FLOW RATE (ml/min.)	DEPTH TO WATER (btor)
12:25	6.82	13.88	0.587	2.40	0.0	48	240	3.94
12:30	6.80	13.83	0.492	0.00	0.0	32	215	4.48
12:35	6.78	13.49	0.484	0.00	0.0	24	215	4.53
12:40	6.77	13.42	0.486	0.00	0.0	19	215	4.58
12:45	6.76	13.34	0.487	0.00	0.0	16	215	4.60
12:50	6.74	13.84	0.487	0.00	0.0	13	215	4.60
Tolerance:	0.1		3%	10%	10%	+ or - 10		

Project Name:	Pfohl Brothers	Project Number:	11175616.00000
Sampling Crew Members:	<u>R. Murphy, T. Ifkovich</u>	Supervisor:	<u>J. Sundquist</u>

Date of Sampling:

<u>May 15, 2012</u>

Sample I.D. Number	Well Number	Well Volume (liters)	Volume Purged (liters)	Sample Time	Sample Description	Analysis Required	Chain-of- Custody Number
GW-7D	GW-7D	40.5	PDB	10:00	Groundwater	VOCs	Not Applicable
GW-7S	GW-7S	19.3	PDB	10:05	Groundwater		Not Applicable
GW-3S	GW-3S	6.2	8.7	12:44	Groundwater	VOCs/SVOCs/ Metals	Not Applicable
GW-3D	GW-3D	82.6	54.0	14:09	Groundwater		Not Applicable
GW-3D-MS	GW-3D	82.6	54.0	14:09	Matrix Spike		Not Applicable
GW-3D-MSD	GW-3D	82.6	54.0	14:09	Matrix Spike Duplicate		Not Applicable
GW-8D	GW-8D	74.8	43.3	15:47	Groundwater		Not Applicable

Additional Comments:

GW-7D and GW-7S were sampled for VOCs using passive diffusion bags (PDBs).

GW-7D and GW-7S were then purged dry, remaining parameters collected May 16, 2012. All other wells were purged using low flow methods until parameter stabilization.

N:11172700.00000\WORD\DRAFT\Semi Annual Report Jan-Jun08\Field Forms 3_5 (May_12)\Form 5 (05_15_2012)

Project Name:	Pfohl Brothers	Project Number:	11175616.00000
Sampling Crew Members:	<u>R. Murphy, T. Ifkovich</u>	Supervisor:	<u>J. Sundquist</u>

Date of Sampling:

<u>May 15, 2012</u>

Sample I.D. Number	Well Number	Well Volume (liters)	Volume Purged (liters)	Sample Time	Sample Description	Analysis Required	Chain-of- Custody Number
DUPLICATE	GW-8D	74.8	43.3	15:47	Blind Duplicate	VOCs/SVOCs/ Metals	Not Applicable
GW-8SR	GW-8SR	4.7	5.9	16:25	Groundwater	motalo	Not Applicable
TB-051512					Trip Blank	VOCs	Not Applicable

Additional Comments:

All wells were purged using low flow methods until parameter stabilization.

Project Name:	Pfohl Brothers	Project Number:	11175616.00000
Sampling Crew Members:	<u>R. Murphy, T. Ifkovich</u>	Supervisor:	<u>J. Sundquist</u>
Date of Sampling:	May 16, 2012		

Chain-of-Well Sample I.D. Volume Purged Sample Analysis Well Volume Sample Time Custody (liters) Description Required Number Number (liters) Number VOCs/SVOCs/ Not Applicable Groundwater GW-34S **GW-34S** 4.3 4.2 8:30 Metals Not Applicable GW-4S GW-4S 7.1 17.0 9:00 & 10:35 Groundwater Not Applicable GW-4D GW-4D 80.7 8.8 10:17 Groundwater **GW-28S GW-28S** 3.8 9.8 11:53 Groundwater Not Applicable GW-35S **GW-35S** 2.2 5.5 12:50 Groundwater Not Applicable **GW-26D GW-26D** 82.9 33.2 13:44 Groundwater Not Applicable **GW-29S GW-29S** 7.1 10.7 15:13 Groundwater Not Applicable

Additional Comments:

GW-4S was sampled for VOCs using a passive diffusion bag and then purged dry/allowed to recharge for collection of other parameters

All other wells were purged using low flow methods until parameter stabilization.

Project Name:	Pfohl Brothers	Project Number:	11175616.00000
Sampling Crew Members:	<u>R. Murphy, T. Ifkovich</u>	Supervisor:	<u>J. Sundquist</u>

Date of Sampling:

<u>May 16, 2012</u>

Sample I.D. Number	Well Number	Well Volume (liters)	Volume Purged (liters)	Sample Time	Sample Description	Analysis Required	Chain-of- Custody Number
GW-7S	GW-7S	5.1	7.5	15:45	Groundwater	SVOCs/ Metals	Not Applicable
GW-7D	GW-7D	10.7	10.7	15:50	Groundwater	motalo	Not Applicable
TB-051612					Trip Blank	VOCs	Not Applicable

Additional Comments:

GW-7D and GW-7S were sampled for SVOCs and Metals after recharging overnight.

Project Name:	Pfohl Brothers	Project Number:	11175616.00000
Sampling Crew Members:	<u>R. Murphy, T. Ifkovich</u>	Supervisor:	<u>J. Sundquist</u>

Date of Sampling:

<u>May 17, 2012</u>

Sample I.D. Number	Well Number	Well Volume (liters)	Volume Purged (liters)	Sample Time	Sample Description	Analysis Required	Chain-of- Custody Number
GW-30S	GW-30S	6.1	31.5	8:42	Groundwater	VOCs/SVOCs/ Metals	Not Applicable
GW-31S	GW-31S	3.5	4.3	9:30	Groundwater		Not Applicable
GW-32S	GW-32S	3.6	6.4	10:42	Groundwater		Not Applicable
GW-33S	GW-33S	1.4	4.9	11:41	Groundwater		Not Applicable
GW-1S	GW-1S	6.5	9.5	12:59	Groundwater		Not Applicable
GW-1D	GW-1D	90.0	62.2	14:43	Groundwater		Not Applicable
TB-110311					Trip Blank	VOCs	Not Applicable

Additional Comments:

All wells were purged using low flow methods until parameter stabilization.

APPENDIX E

HISTORICAL ANALYTICAL RESULTS

FIGURE E-1 TRENDS OF PARAMETERS ROUTINELY EXCEEDING GROUNDWATER STANDARDS IN MONITORING WELL GW-1D




FIGURE E-2 TRENDS OF PARAMETERS ROUTINELY EXCEEDING GROUNDWATER STANDARDS IN MONITORING WELL GW-1S




FIGURE E-3 TRENDS OF PARAMETERS ROUTINELY EXCEEDING GROUNDWATER STANDARDS IN MONITORING WELL GW-3D




FIGURE E-4 TRENDS OF PARAMETERS ROUTINELY EXCEEDING GROUNDWATER STANDARDS IN MONITORING WELL GW-3S




FIGURE E-4 TRENDS OF PARAMETERS ROUTINELY EXCEEDING GROUNDWATER STANDARDS IN MONITORING WELL GW-3S




FIGURE E-5 TRENDS OF PARAMETERS ROUTINELY EXCEEDING GROUNDWATER STANDARDS IN MONITORING WELL GW-4D




FIGURE E-6 TRENDS OF PARAMETERS ROUTINELY EXCEEDING GROUNDWATER STANDARDS IN MONITORING WELL GW-4S




FIGURE E-7 TRENDS OF PARAMETERS ROUTINELY EXCEEDING GROUNDWATER STANDARDS IN MONITORING WELL GW-7D




FIGURE E-8 TRENDS OF PARAMETERS ROUTINELY EXCEEDING GROUNDWATER STANDARDS IN MONITORING WELL GW-7S




FIGURE E-9 TRENDS OF PARAMETERS ROUTINELY EXCEEDING GROUNDWATER STANDARDS IN MONITORING WELL GW-8D




FIGURE E-10 TRENDS OF PARAMETERS ROUTINELY EXCEEDING GROUNDWATER STANDARDS IN MONITORING WELL GW-8SR




FIGURE E-11 TRENDS OF PARAMETERS ROUTINELY EXCEEDING GROUNDWATER STANDARDS IN MONITORING WELL GW-26D




FIGURE E-12 TRENDS OF PARAMETERS ROUTINELY EXCEEDING GROUNDWATER STANDARDS IN MONITORING WELL GW-28S




FIGURE E-13 TRENDS OF PARAMETERS ROUTINELY EXCEEDING GROUNDWATER STANDARDS IN MONITORING WELL GW-29S




FIGURE E-13 TRENDS OF PARAMETERS ROUTINELY EXCEEDING GROUNDWATER STANDARDS IN MONITORING WELL GW-29S




FIGURE E-14 TRENDS OF PARAMETERS ROUTINELY EXCEEDING GROUNDWATER STANDARDS IN MONITORING WELL GW-30S




FIGURE E-15 TRENDS OF PARAMETERS ROUTINELY EXCEEDING GROUNDWATER STANDARDS IN MONITORING WELL GW-31S




FIGURE E-16 TRENDS OF PARAMETERS ROUTINELY EXCEEDING GROUNDWATER STANDARDS IN MONITORING WELL GW-32S




FIGURE E-17 TRENDS OF PARAMETERS ROUTINELY EXCEEDING GROUNDWATER STANDARDS IN MONITORING WELL GW-33S




FIGURE E-18 TRENDS OF PARAMETERS ROUTINELY EXCEEDING GROUNDWATER STANDARDS IN MONITORING WELL GW-34S





FIGURE E-19 TRENDS OF PARAMETERS ROUTINELY EXCEEDING GROUNDWATER STANDARDS IN MONITORING WELL GW-35S



APPENDIX F

BSA PERMIT NO. 10-11-CH016

AUTHORIZATION TO DISCHARGE UNDER THE BUFFALO POLLUTANT DISCHARGE ELIMINATION SYSTEM

PERMIT NO. 10-11-CH016 USEPA Category 40 CFR Part 403

In accordance with the provisions of the Federal Water Pollution Control Act, as amended, and the Sewer Regulations of the Buffalo Sewer Authority, authorization is hereby granted to:

THE TOWN OF CHEEKTOWAGA

to discharge wastewater from a facility located at:

PFOHL BROTHERS LANDFILL REMEDIATION SITE 1000 AERO DRIVE

CHEEKTOWAGA, NEW YORK 14225

The wastewater permitted herein shall be discharged to the Town of Cheektowaga sewer system, which is connected to the Buffalo Municipal Sewer System and Treatment facilities, and which wastewater will be treated at the Buffalo Sewer Authority's Treatment Plant.

Issuance of this permit is based upon a permit application filed on **November 3, 2005** analytical data. This permit is granted in accordance with discharge limitations, monitoring requirements and other conditions set forth in Parts I and II hereof.

Effective this 1st day of November, 2010

To Expire the 31st day of March, 2013

General Manager

Signed this 30th day of Leptember, 2010

PAGE 1 OF 6

Permit No. 10-11-CH016 Part I^{*} Page 2 of 6

PART I: SPECIFIC CONDITIONS

A. DISCHARGE LIMITATIONS & MONITORING REQUIREMENTS

During the period beginning the effective date of this Permit and lasting until the expiration date, discharge from the permitted facility outfall (see attached map) shall be limited and monitored **quarterly** by the permittee as specified below.

Gample		Discharge Limitations ⁽¹⁾	Samp	ling Requirements
Sample Point	Parameter	Daily Max	Period	Туре
001	pH Total Cadmium Total Chromium Total Copper	5.0 – 12.0 S.U. 1.17 lbs. 1.17 lbs. 3.74 lbs.	1 day 1 day 1 day 1 day	Composite ² Composite ² Composite ² Composite ²
	Total Lead Total Nickel Total Zinc Total Barium Total Suspended Solids ⁵	1.17 lbs. 3.27 lbs. 5.84 lbs. 2.34 lbs. 250 mg/l	1 day 1 day 1 day 1 day 1 day	Composite ² Composite ² Composite ² Composite ² Composite ²
	Total Flow	140,100 gallons ⁶	1 day	Discharge meter reading

Footnotes are explained on page 5.

Permit No. 10-11-CH016 Part I Page 3 of 6

PART I: SPECIFIC CONDITIONS

A. DISCHARGE LIMITATIONS & MONITORING REQUIREMENTS

During the period beginning the effective date of this Permit and lasting until the expiration date, discharge from the permitted facility outfall (see attached map) shall be limited and monitored **once** by the permittee as specified below.

Sample		Discharge Limitations ⁽¹⁾	Sampling	Requirements
Point	Parameter	Daily Max	Period	Type
001	Total Mercury	0.001 lbs.	1 day	Composite ²
	USEPA Test		4 1	Grab ³
	Method 608 ⁴	To be monitored	1 day	Grad
	USEPA Test		1 1	Grab ³
	Method 624 ⁴	To be monitored	1 day	Grad
	USEPA Test		1 1	Grab ³
	Method 625 ⁴	To be monitored	1 day	Ulau

Footnotes are explained on page 5.

PART I: SPECIFIC CONDITIONS

B. DISCHARGE MONITORING REPORTING REQUIREMENTS

During the period beginning the effective date of this permit and lasting until the expiration date, discharge monitoring results shall be summarized and reported **quarterly** by the permittee on the days specified below:


Sample Point 001	Parameter All except USEPA Test Methods 608, 624, 625 & T Mercury	Reporting Initial Report March 31, 2011	Requirements Subsequent Reports Every March 31 st , June 30 th , September 30 th and December 31 st
	USEPA Test Methods 608, 624 and 625 & T Mercury	March 31, 2011	

Permit No. 10-11-CH016 Part I Page 5 of 6

PART I: SPECIFIC CONDITIONS

C. SPECIAL REQUIREMENTS

- 1. Mass limits based on an average discharge of 140,100 gpd.
- 2. Composite samples may be time proportioned.
- 3. Four grab samples must be collected at equally spaced intervals throughout the sample day. The four (4) grab samples must be composited by a NYSDOH certified laboratory prior to analysis.
- 4. The permittee must report any compound whose concentration is equal to or greater than 0.01 mg/L. The permittee is not authorized to discharge any of the parameters evaluated by these test procedures which may cause or contribute to a violation of water quality standards or harm the sewerage system. Any parameter detected may, at the discretion of the BSA, be specifically limited and incorporated in this permit.
- 5. Surchargeable over 250 mg/L.
- 6. Flow is an action level only. If the permittee consistently exceeds this level, the BSA must be notified so that this permit can be modified.



TOWN OF CHEEKTOWAGA/BUFFALO POLLUTANT DISCHARGE ELIMINATION SYSTEM PERMIT

PART II GENERAL CONDITIONS

A. MONITORING AND REPORTING

1. Local Limits

Except as otherwise specified in this permit, the permit holder shall comply with all specific prohibitions, limits on pollutants or pollutant parameters set forth in the Buffalo Sewer Authority Sewer Use Regulations, as amended from time to time, and such prohibitions, limits and parameters shall be deemed pretreatment standards for purposes of the Clean Water Act

2. Definitions

Definitions of terms contained in this permit are as defined in the Town of Cheektowaga Local Law No. 2 and the Buffalo Sewer Authority Sewer Use Regulations.

3. Discharge Sampling Analysis

All Wastewater discharge samples and analyses and flow measurements shall be representative of the volume and character of the monitored discharge. Methods employed for flow measurements and sample collections and analyses shall conform to the Buffalo Sewer Authority "Sampling Measurement and Analytical Guidelines Sheet."

4. Recording of Results

For each measurement or sample taken pursuant to the requirements of the permit, the Permittee shall record the information as required in the "Sampling Measurement and Analytical Guidelines Sheet."

5. Additional Monitoring by Permittee

If the Permittee monitors any pollutants at the location(s) designated herein more frequently than required by this permit, using approved analytical methods as specified in 40 CFR Part 136 the results of such monitoring shall be included in the calculation and reporting of values required under Part I, B. Such increased frequency shall also be indicated.

6. Reporting

All reports prepared in accordance with this Permit shall be submitted to:

Mr. William Pugh, P.E. Town Engineer 275 Alexander Ave. Cheektowaga, New York, 14211

All self-monitoring reports shall be prepared in accordance with the BSA "Sampling Measurement and Analytical Guidelines Sheet." These reporting requirements shall not relieve the Permittee of any other reports, which may be required by the

N.Y.S.D.E.C. or the U.S.E.P.A.

B. PERMITTEE REQUIREMENTS

1. Change in Discharge

All discharges authorized herein shall be consistent with the terms and conditions of this permit and with the information contained in the TC/BPDES Permit Application on which basis this permit is granted. In the event of any facility expansions, production increases, process modifications or the installation, modification or repair of any pretreatment equipment which may result in new, different or increased discharges of pollutants, a new TC/BPDES Permit Application must be submitted prior to any change. Following receipt of an amended application, the BSA may modify this permit to specify and limit any pollutants not previously limited. In the event that the proposed change will be covered under an applicable Categorical Standard, a Baseline Monitoring Report must be submitted at least ninety (90) days prior to any discharge.

2. Records Retention

All records and information resulting from the monitoring activities required by this permit including all records of analyses performed, calibration and maintenance of instrumentation, and recordings from continuous monitoring instrumentation shall be retained at this facility for a minimum of three (3) years, or longer if requested by the General Manager and/or Town Engineer.

3. Notification of Slug, Accidental Discharge or Spill

In the event that a slug, accidental discharge or any spill occurs at the facility for which this permit is issued, it is the responsibility of the Permittee to immediately notify the B.S.A. Treatment Plant at 883-1820 of the quantity and character of such discharge. If requested by the B.S.A., within five (5) days following all such discharges, the Permittee shall submit a report describing the character and duration of the discharge, the cause of the discharge, and measures taken or that will be taken to prevent a recurrence of such discharge.

4. Noncompliance Notification

If, for any reason, the Permittee does not comply with or will be unable to comply with any discharge limitation specified in this permit, the Permittee or their assigns must verbally notify the Industrial Waste Section at 883-1820 within twenty-four (24) hours of becoming aware of the violation. The Permittee shall provide the Industrial Waste Section with the following information, in writing, within five (5) days of becoming aware of such condition:

- a. a description of the discharge and cause of noncompliance and;
- b. the period of noncompliance, including exact dates and times; or, if not corrected, the anticipated time the noncompliance is expected to continue, and steps being taken to reduce, eliminate and prevent recurrence of the noncomplying discharge.

5. Adverse Impact

The Permittee shall take all reasonable steps to minimize any adverse impact to the Buffalo and Town Sewerage System resulting from noncompliance with any discharge limitations specified in this permit, including such accelerated or additional monitoring as necessary to determine the nature and impact of the noncomplying discharge.

6. Waste Residuals

Solids, sludges, filter backwash or other pollutants removed in the course of treatment or control of wastewaters and/or the treatment of intake waters, shall be disposed of in a manner such as to prevent any pollutant from such materials from entering the Buffalo or Town Sewer System.

7. Power Failures

In order to maintain compliance with the discharge limitations and prohibitions of this permit, the Permittee shall provide an alternative power source sufficient to operate the wastewater control facilities; or, if such alternative power source is not provided the Permittee shall halt, reduce or otherwise control production and/or controlled discharges upon the loss of power to the wastewater control facilities.

8. Treatment Upsets

- a. Any industrial user which experiences an upset in operations that places it in a temporary state of noncompliance, which is not the result of operational error, improperly designed treatment facilities, inadequate treatment facilities, lack of preventive maintenance, or careless or improper operation, shall inform the Industrial Waste Section immediately upon becoming aware of the upset. Where such information is given verbally, a written report shall be filed by the user within five (5) days. The report shall contain:
 - (i) A description of the upset, its cause(s) and impact on the discharger's compliance status.
 - (ii) The duration of noncompliance, including exact dates and times of noncompliance, and if the noncompliance is continuing, the time by which compliance is reasonably expected to be restored
 - (iii) All steps taken or planned to reduce, eliminate, and prevent recurrence of such an upset.
- b. An industrial user which complies with the notification provisions of this Section in a timely manner shall have an affirmative defense to any enforcement action brought by the Industrial Waste Section/Town Engineer for any noncompliance of the limits in this permit, which arises out of violations attributable to and alleged to have occurred during the period of the documented and verified upset.

9. Treatment Bypasses

- a. A bypass of the treatment system is prohibited unless the following conditions are met:
 - (i) The bypass was unavoidable to prevent loss of life, personal injury, or severe property damage; or
 - (ii) There was no feasible alternative to the bypass, including the use of auxiliary treatment or retention of the wastewater; and
 - (iii) The industrial user properly notified the Industrial Waste Section as described in paragraph b. below.
- b. Industrial users must provide immediate notice to the Industrial Waste Section upon delivery of an unanticipated bypass. If necessary, the Industrial Waste Section may require the industrial user to submit a written report explaining the cause(s), nature, and duration of the bypass, and the steps being taken to prevent its recurrence.
- c. An industrial user may allow a bypass to occur which does not cause pretreatment standards or requirements to be violated, but only if it is for essential maintenance to ensure efficient operation of the treatment system. Industrial users anticipating a bypass must submit notice to the Industrial Waste Section at least ten (10) days in advance. The Industrial Waste Section may only approve the anticipated bypass if the circumstances satisfy those set forth in paragraph a. above.

C. PERMITTEE RESPONSIBILITIES

1. Permit Availability

The originally signed permit must be available upon request at all times for review at the address stated on the first page of this permit.

2. Inspections

The Permittee shall allow the representatives of the Buffalo Sewer Authority or Town of Cheektowaga upon the presentation of credentials and during normal working hours or at any other reasonable times, to have access to and copy any records required in this permit; and to sample any discharge of pollutants.

3. Transfer of Ownership or Control

In the event of any change in control or ownership of facilities for which this permit has been issued the permit shall become null and void. The succeeding owner shall submit a completed Town of Cheektowaga/ Buffalo Sewer Authority permit application prior to discharge to the sewer system.

D. PERMITTEE LIABILITIES

1. Permit Modification

After notice and opportunity for a hearing, this permit may be modified, suspended, or revoked in whole or in part during its term for cause including, but not limited to the following:

- a. Violation of any terms or conditions of this permit,
- b. Obtaining this permit by misrepresentation or failure to disclose fully all relevant facts,
- c. A change in any condition that requires either a temporary or permanent reduction or elimination of the authorized discharge.

2. Imminent Danger

In the event there exists an imminent danger to health or property, the permitter reserves the right to take immediate action to halt the permitted discharge to the sewerage works.

3. Civil and Criminal Liability

Nothing in this permit shall relieve the Permittee from any requirements, liabilities, or penalties under provisions of the Town of Cheektowaga Local Law No. 2, the "Sewer Regulations of the Buffalo Sewer Authority" or any Federal, State and/or local laws or regulations.

4. Penalties for Violations of Permit Conditions

The "Sewer Regulations of the Buffalo Sewer Authority" and Town of Cheektowaga Local Law No. 2, provide that any person who violates a B.P.D.E.S. permit condition is liable to the Authority and/or the Town for a civil penalty of up to \$10,000 per day for each violation. Any person who willfully or negligently violates permit conditions will be referred to the New York State Attorney General.

E. NATIONAL PRETREATMENT STANDARDS

If a pretreatment standard or prohibition (including any Schedule of Compliance specified in such pretreatment standard or prohibition) is established under Section 307 (b) of the Act for a pollutant which is present in the discharge and such standard or prohibition is more stringent than any limitation for such pollutant in this permit, this permit shall be revised or modified in accordance with such pretreatment standard or prohibition.

F. PLANT CLOSURE

In the event of plant closure, the Permittee is required to notify the Industrial Waste Section/Town Engineer in writing as soon as an anticipated closure date is determined, but in no case later than five (5) days of the actual closure.

G. CONFIDENTIALITY

Except for data determined to be confidential under Section 308 of the Act, all reports prepared in accordance with the terms of this permit shall be available for public inspection at the offices of the Buffalo Sewer Authority or Town Engineer of the Town of Cheektowaga. As required by the Act, effluent data shall not be considered confidential. Knowingly making any false statement on any such report may result in the imposition of criminal penalties as provided for in Section 309 of the Act.

H. SEVERABILITY

The provisions of this permit are severable, and if any provision of this permit, or the application of any provision of this permit to any circumstance, is held invalid, the application of such provision to other circumstances, and the remainder of this permit, shall not be affected thereby.

APPENDIX G

DISCHARGE REPORT SUMMARY TABLES

N:\11172700.0000\WORD\DRAFT\Semi Annual Report Jan-Jun12\Semi Annual Report Jan-Jun12.doc

SAMPLING FIELD SHEET



Client Name:						
	Pfohl Brothers	Landfill				
Address:	Aero Drive, Cheektowaga, NY					
Contact:	Bill Pugh, P.E.		Phone:	716-897-7288		
Installation:						
Sample Point:	SP-001					
Sample Locatio	n: Meter	Chamber - ball va	lve on 6" HDP	E forcemain		
Date:	03/26/12	Crew: R. Murp	hy, T. Ifkovich	, J. Brayer		
Weather:	35° F, Clear					
Sampling Devic	e: NA					
Time of Installa	tion: 09	:45т	ype of Sample:	Composite		
Sample Interva	: N	A s	ample Volume:	NA		
Date:	03/27/12		als), WW-06 (hy, T. lfkovich	4,140 gals), WW-03 (855,519 gals), 5,483,868 gals) & MH-25 (11,965,900 gals). , J. Brayer		
	03/27/12 36° F, Clear	Crew: R. Murp		5,483,868 gals) & MH-25 (11,965,900 gals).		
Date: Weather: Time of Collecti Field Measuren	03/27/12 <u>36° F, Clear</u> on: <u>09</u> nents:	_Crew: <u>R. Murp</u> :45	hy, T. Ifkovich	5,483,868 gals) & MH-25 (11,965,900 gals). , J. Brayer		
Date: Weather: Time of Collecti Field Measuren 09:4	03/27/12 36 ^o F, Clear on:09	_Crew: <u>R. Murp</u> :45 _ pH Calibra	bhy, T. Ifkovich	5,483,868 gals) & MH-25 (11,965,900 gals). , J. Brayer 7Buffer 44Buffer 1010		
Date: Weather: Time of Collecti Field Measuren 09:4	03/27/12 <u>36° F, Clear</u> on: <u>09</u> nents: 5/RJM	Crew: <u>R. Murp</u> :45 pH Calibra pH Measu	tion: Buffer 7-	5,483,868 gals) & MH-25 (11,965,900 gals). , J. Brayer 7Buffer 44Buffer 1010 7.6		
Date: Weather: Time of Collecti Field Measuren 09:4 (tim	03/27/12 36 ^o F, Clear on: 09 nents: 5/RJM e/initial)	_Crew: <u>R. Murp</u> :45 _ pH Calibra	tion: Buffer 7-	5,483,868 gals) & MH-25 (11,965,900 gals). , J. Brayer 7Buffer 44Buffer 1010		
Date: Weather: Time of Collecti Field Measuren 09:4 (tim	03/27/12 <u>36° F, Clear</u> on: <u>09</u> nents: <u>5/RJM</u> e/initial) EFF-032712	Crew: <u>R. Murp</u> :45 _ pH Calibra _ pH Measu Temperatu	tion: Buffer 7- rement:	5,483,868 gals) & MH-25 (11,965,900 gals). , J. Brayer 7Buffer 44Buffer 1010 7.6 9.3°C		
Date: Weather: Time of Collecti Field Measuren 09:4 (tim	03/27/12 <u>36° F, Clear</u> on: <u>09</u> nents: <u>5/RJM</u> e/initial) EFF-032712	Crew: <u>R. Murp</u> :45 pH Calibra pH Measu	tion: Buffer 7- rement:	5,483,868 gals) & MH-25 (11,965,900 gals). , J. Brayer 7Buffer 44Buffer 1010 7.6 9.3°C		
Date: Weather: Time of Collecti Field Measuren 09:4 (tim Identification: Physical Obser	03/27/12 <u>36° F, Clear</u> on: <u>09</u> nents: <u>5/RJM</u> e/initial) EFF-032712	Crew: <u>R. Murp</u> :45 pH Calibra pH Measu Temperatu	tion: Buffer 7- rement:	5,483,868 gals) & MH-25 (11,965,900 gals). , J. Brayer 7Buffer 44Buffer 1010 7.6 9.3°C		
Date: Weather: Time of Collecti Field Measuren (tim Identification: Physical Obser Laboratory: Comments:	03/27/12 <u>36° F, Clear</u> on: <u>09</u> nents: <u>5/RJM</u> e/initial) EFF-032712 vations: TestAmerica, Bi No wells were re	Crew: <u>R. Murp</u> :45 pH Calibra pH Measu Temperatu uffalo, NY unning at the time	tion: Buffer 7- rement:	5,483,868 gals) & MH-25 (11,965,900 gals). , J. Brayer 		
Date: Weather: Time of Collecti Field Measuren (tim Identification: Physical Obser Laboratory: Comments: PLC display	03/27/12 <u>36° F, Clear</u> on: <u>09</u> nents: <u>5/RJM</u> e/initial) <u>EFF-032712</u> vations: <u></u> <u>restAmerica, Br</u> <u>No wells were re</u> volumes: WW	Crew: <u>R. Murp</u> :45 pH Calibra pH Measu Temperatu uffalo, NY unning at the time -01 (1,241,323 ga	tion: Buffer 7- rement: ure: of sample coll	5,483,868 gals) & MH-25 (11,965,900 gals). , J. Brayer 		
Date: Weather: Time of Collecti Field Measuren 09:4 (tim Identification: Physical Obser Laboratory: Comments: PLC display WW-04 (70	03/27/12 <u>36° F, Clear</u> on: <u>09</u> nents: <u>5/RJM</u> e/initial) <u>EFF-032712</u> vations: <u>restAmerica, Br</u> <u>No wells were re</u> volumes: WW	Crew: <u>R. Murp</u> :45 pH Calibra pH Measu Temperatu uffalo, NY unning at the time -01 (1,241,323 ga V-05 (3,501,551 g	tion: Buffer 7- rement: ure: of sample coll	5,483,868 gals) & MH-25 (11,965,900 gals). , J. Brayer 		

TABLE 1

PFOHL BROTHERS LANDFILL - EFFLUENT MONITORING ANALYTICAL RESULTS, TOTAL FLOW, AND MASS LOADINGS MARCH 2012

Sample ID		EFF-032712						
Matrix	Effluent Water							
Date Sampled	3/27/2012							
Parameter	Result	Mass Loading	Discharge Limitation	Violations				
	(mg/L)	(lbs/day)	(lbs/day)	(Y/N)				
Total Barium	0.23	0.13	2.34	No				
Total Cadmuim	ND ⁽¹⁾	NA ⁽²⁾	1.17	No				
Total Chromium	0.0014	0.0008	1.17	No				
Total Copper	0.05	0.029	3.74	No				
Total Lead	ND	NA	1.17	No				
Total Nickel	0.0037	0.0022	3.27	No				
Total Zinc	0.13	0.076	5.84	No				
Total Suspended Solids	25.6	NA	250 ⁽³⁾	No				
рН ⁽⁴⁾	7.9	NA	5.0 - 12.0	No				
Total Flow ⁽⁵⁾		70,217	140,000	No				

Notes:

(1) ND = Not Detected

(2) NA = Not Applicable

(3) Discharge Limitation in units of mg/L

- (4) pH measurement and Discharge Limitation in Standard Units
- (5) Total Flow reported in gallons, sample was collected over a 24 hour period

Calculation:
$$\left(\frac{x \text{ mg}}{L}\right)\left(\frac{y \text{ gal}}{\text{day}}\right)\left(\frac{1 \text{ lb}}{453,600 \text{ mg}}\right)\left(\frac{3.785 \text{ L}}{\text{gal}}\right) = \frac{x \times y}{119,841} \frac{\text{lb}}{\text{day}}$$

SAMPLING FIELD SHEET



	Pfohl Brothers La	andfill			
Address:	Aero Drive, Cheektowaga, NY				
Contact:	Bill Pugh, P.E. Phone: 716-897-7288				
Installation:					
Sample Point:	SP-001				
Sample Locatio	n: Meter Ch	namber - ball valve on 6" HDP	PE forcemain		
Date:	<u>6/20/12</u> C	rew: R. Murphy, T. Urban,	S. Conway		
Weather:	90° F, Clear				
Sampling Devic	e: NA				
Time of Installa	tion: <u>12:5</u> 5	5 Type of Sample:	Composite		
Sample Interval	: <u>NA</u>	Sample Volume:	NA		
Date:		rew: <u>R. Murphy, T. Urban,</u>	(6,511,214 gals) & MH-25 (14,486,555 gals). S. Conway		
Date: Weather: Time of Collecti	<u>6/21/12</u> C 90 ^o F, Clear on: <u>12:55</u>	rew:R. Murphy, T. Urban,			
Date: Weather: Time of Collecti Field Measurem	<u>6/21/12</u> C 90 ^o F, Clear on: <u>12:55</u>	rew: <u>R. Murphy, T. Urban,</u>			
Date: Weather: Time of Collecti Field Measurem 12:5	6/21/12 C 90° F, Clear on: <u>12:55</u> nents:	rew: <u>R. Murphy, T. Urban,</u>	S. Conway		
Date: Weather: Time of Collecti Field Measurem 12:5	6/21/12 C 90° F, Clear on: <u>12:55</u> nents: 5/RJM	rew: <u>R. Murphy, T. Urban,</u> 5 pH Calibration: Buffer 7 pH Measurement:	S. Conway 7 Buffer 44 Buffer 1010 8.4		
Date: Weather: Time of Collecti Field Measurem 12:5	6/21/12 C 90° F, Clear on: <u>12:55</u> hents: <u>5/RJM</u> _{a/initial)}	rew: <u>R. Murphy, T. Urban,</u>	S. Conway 7Buffer 44Buffer 1010		
Date: Weather: Time of Collecti Field Measurem 12:5 (time Identification:	6/21/12 C 90° F, Clear on: <u>12:55</u> nents: 5/RJM e/initial)	rew: <u>R. Murphy, T. Urban,</u> 5 pH Calibration: Buffer 7 pH Measurement: Temperature:	S. Conway 7 Buffer 44 Buffer 1010 8.4 22.9°C		
Date: Weather: Time of Collecti Field Measurem 12:5 (time Identification:	6/21/12 C 90° F, Clear on: <u>12:55</u> nents: 5/RJM e/initial)	rew: <u>R. Murphy, T. Urban,</u> 5 pH Calibration: Buffer 7 pH Measurement:	S. Conway 7 Buffer 44 Buffer 1010 8.4 22.9°C		
Date:	6/21/12 C 90° F, Clear on: <u>12:55</u> nents: 5/RJM e/initial)	rew: <u>R. Murphy, T. Urban,</u> 5 pH Calibration: Buffer 7- pH Measurement: Temperature:	S. Conway 7 Buffer 44 Buffer 1010 8.4 22.9°C		
Date:	6/21/12 C 90° F, Clear C on: 12:55 hents: 5/RJM s/initial) EFF-062112 vations:	rew: <u>R. Murphy, T. Urban,</u> 5 pH Calibration: Buffer 7 pH Measurement: Temperature: alo, NY ning at the time of sample col	S. Conway 7 Buffer 44 Buffer 1010 8.4 22.9°C		
Date:	6/21/12 C 90° F, Clear C on: 12:55 hents: 5/RJM a/initial) C EFF-062112 C vations: C CestAmerica, Buff No wells were runi volumes: WW-0	rew: <u>R. Murphy, T. Urban,</u> 5 pH Calibration: Buffer 7 pH Measurement: Temperature: alo, NY ning at the time of sample col 1 (1,467,849 gals), WW-02 (-	S. Conway 7Buffer 44Buffer 1010 8.4 22.9°C		

TABLE 1

PFOHL BROTHERS LANDFILL - EFFLUENT MONITORING ANALYTICAL RESULTS, TOTAL FLOW, AND MASS LOADINGS JUNE 2012

Sample ID	EFF-062112							
Matrix	Effluent Water							
Date Sampled	6/21/2012							
Parameter	Result	Mass Loading	Discharge Limitation	Violations				
	(mg/L)	(lbs/day)	(lbs/day)	(Y/N)				
Total Barium	0.21	0.08	2.34	No				
Total Cadmuim	0.0005	0.0002	1.17	No				
Total Chromium	0.0019	0.0007	1.17	No				
Total Copper	0.0082	0.003	3.74	No				
Total Lead	0.003	0.0011	1.17	No				
Total Nickel	0.0052	0.0020	3.27	No				
Total Zinc	0.025	0.009	5.84	No				
Total Suspended Solids	29.2	NA	250 ⁽³⁾	No				
pH ⁽⁴⁾	8.37	NA	5.0 - 12.0	No				
Total Flow ⁽⁵⁾		45,215	140,000	No				

Notes:

(1) ND = Not Detected

(2) NA = Not Applicable

(3) Discharge Limitation in units of mg/L

- (4) pH measurement and Discharge Limitation in Standard Units
- (5) Total Flow reported in gallons, sample was collected over a 24 hour period

Calculation:
$$\left(\frac{x \text{ mg}}{L}\right)\left(\frac{y \text{ gal}}{\text{day}}\right)\left(\frac{1 \text{ lb}}{453,600 \text{ mg}}\right)\left(\frac{3.785 \text{ L}}{\text{gal}}\right) = \frac{x \times y}{119,841} \frac{\text{lb}}{\text{day}}$$

APPENDIX H

MONITORING WELL INSPECTION LOGS

WELL INSPECTION SUMMARY								
Proj	ect Name:			Pfohl Brothers Lar	ndfill	Project Number:	11175616.00000	
Insp	ection Crew Members	:		<u>R. Murphy, T. Ifko</u>	<u>vich</u>	Supervisor:	<u>J. Sundquist</u>	
Date	e(s) of Inspection:			<u>May 15, 2012</u>				
	Well I.D. Number	Lock	Surface Seal	Protective Casing	Riser	Water Level (ft. BTOC)	Well Depth (ft. BTOC)	Other Comments
	GW-1S	OK	ОК	ОК	Bulged	4.24	14.94	
	GW-1D	ОК	ОК	ОК	Bulged	3.09	39.65	
	GW-3S	ОК	ОК	ОК	ОК	2.73	13.22	
	GW-3D	ОК	ОК	ОК	ОК	2.29	35.70	
	GW-4S	ОК	ОК	ОК	ОК	4.66	16.23	
	GW-4D	ОК	ОК	ОК	ОК	13.04	45.57	
	GW-7S	OK	ОК	ОК	ОК	5.00	35.04	
	GW-7D	ОК	ОК	ОК	Damaged	44.25	60.45	

Additional Comments:

WELL INSPECTION SUMMARY

Project Name:

Pfohl Brothers Landfill

Project Number: <u>11175616.00000</u>

Inspection Crew Members:

R. Murphy, T. Ifkovich

Supervisor: <u>J. Sundquist</u>

Date(s) of Inspection:

<u>May 15, 2012</u>

Well I.D. Number	Lock	Surface Seal	Protective Casing	Riser	Water Level (ft. BTOC)	Well Depth (ft. BTOC)	Other Comments
GW-8SR	ОК	ОК	OK	ОК	5.34	13.02	
GW-8D	ОК	ОК	OK	ОК	6.27	36.54	
GW-26D	ОК	ОК	OK	ОК	7.12	40.70	
GW-28S	ОК	ОК	OK	ОК	9.27	15.52	
GW-29S	ОК	ОК	OK	ОК	8.39	20.04	
GW-30S	ОК	ОК	OK	ОК	8.05	17.97	
GW-31S	ОК	ОК	OK	ОК	3.45	9.57	
GW-32S	ОК	ОК	OK	ОК	3.81	9.93	

Additional Comments:

WELL INSPECTION SUMMARY **Project Name:** Pfohl Brothers Landfill Project Number: *11175616.00000* Inspection Crew Members: Supervisor: R. Murphy, T. Ifkovich J. Sundquist Date(s) of Inspection: <u>May 15, 2012</u> Water Level Well Depth Other Surface Protective Well I.D. Number Lock Riser (ft. BTOC) (ft. BTOC) Seal Casing **Comments** OK OK OK OK GW-33S 5.60 8.21 GW-34S OK OK OK OK 3.05 10.01 GW-35S OK OK OK OK 3.81 7.46 Additional Comments:

N:11172700.0000\WORD\DRAFT\Semi Annual Report Jan-Jun08\Field Forms 3_5 (May_12)\Form 3 (May_2012) (3)

ATTACHMENT B

July 2012 – December 2012

Semi Annual Report

SEMI ANNUAL REPORT OPERATION AND MAINTENANCE JULY 2012 TO DECEMBER 2012 PFOHL BROTHERS LANDFILL CHEEKTOWAGA, NY

Submitted to:

NEW YORK STATE DEPARTMENT OF ENVIRONMENTAL CONSERVATION 270 MICHIGAN AVENUE BUFFALO, NEW YORK 14203

Prepared by:

URS CORPORATION 77 GOODELL STREET BUFFALO, NEW YORK 14203

Prepared for:

TOWN OF CHEEKTOWAGA ENGINEERING DEPARTMENT 275 ALEXANDER AVE CHEEKTOWAGA, NEW YORK 14211

> MAY 2013



May 9, 2013

Mr. Jaspal Singh Walia, P.E. New York State Department of Environmental Conservation 270 Michigan Ave. Buffalo, NY 14203

Re: Semi-Annual Report Pfohl Brothers Landfill, Town of Cheektowaga, New York

Dear Mr. Walia:

Enclosed is one copy of the eighteen Semi-Annual Report for the Pfohl Brothers Landfill in Cheektowaga, New York. A copy has also been sent to Ms. Pamela Tames, P.E. of the United States Environmental Protection Agency. Also enclosed is the Data Applicability Report for laboratory analyses associated with the Semi-Annual Report. PDF copies of the reports are also enclosed.

If you have any questions on this report, please feel free to contact me.

Sincerely,

URS CORPORATION

Jon Sundquist, Ph.D. Project Manager

Enclosures

cc: Pamela Tames, P.E. - USEPA (w/attachments) William Pugh, P.E. – Town of Cheektowaga (w/attachments) File 11172700 (C-1)

TABLE OF CONTENTS

Page No.

1.0	INTR	RODUCTION	1-1
	1.1	Background	1-1
	1.2	Operation and Maintenance Activities	1-1
2.0	GEN	ERAL MAINTENANCE ACTIVITIES	2-1
3.0	MON	NITORING ACTIVITIES	3-1
	3.1	Groundwater Hydraulic Monitoring	
	3.2	Groundwater Quality Monitoring	
	3.3	Groundwater Discharge Monitoring	
	3.4	Monitoring Well Inspections	
4.0	SUM	IMARY AND RECOMMENDATIONS	4-1

TABLES

Table 3-1	Groundwater Sample Analytical Results
Table 3-2	Approved Revision Of Table 3.2 From The O&M Plan

FIGURES

- Figure 1-1 Site Location Map
- Figure 3-1 Monitoring Locations

APPENDICES

- Appendix A Example Daily Inspection Sheets
- Appendix B Monthly Flow Summaries (July 2012 December 2012)
- Appendix C Hydraulic Monitoring Tables
- Appendix D Groundwater Purge and Sample Collection Logs
- Appendix E Groundwater Trend Analysis
- Appendix F BSA Permit No. 10-11-CH016
- Appendix G Discharge Report Summary Tables
- Appendix H Monitoring Well Inspection Logs

1.0 INTRODUCTION

1.1 Background

The Pfohl Brothers Landfill is located on Aero Drive in the Town of Cheektowaga, New York (Figure 1-1). The site is listed as site No. 915043 on the New York State Department of Environmental Conservation's (NYSDEC's) Registry of Inactive Hazardous Waste Disposal Sites. A Consent Order between NYSDEC and potentially responsible parties (PRPs) for closure of the site was signed in 2001 and remedial construction commenced in 2001. The remedy included consolidation of waste material, capping of the waste disposal and consolidation areas, and encircling the landfill areas with a groundwater collection system to prevent off-site migration. The remedial action was completed in 2002.

Responsibility for implementing the remedy was divided between a "steering committee" of industrial PRPs and the Town of Cheektowaga. The steering committee responsibilities lay generally with the capital construction activities of the remedy including waste consolidation, cap and drainage system installation, etc. The Town of Cheektowaga, which was named as a PRP for disposal of municipal waste at the Pfohl Brothers Landfill when it was operating, is performing the operation and maintenance (O&M) activities at the landfill, pursuant to a settlement agreement between the Town and the steering committee.

1.2 **Operation and Maintenance Activities**

While construction of the remedy was substantially complete by late 2002, the final O&M manual was not approved by the NYSDEC until March 10, 2006. However, the Town of Cheektowaga and its consultant (URS Corporation – New York) assumed most of the operational responsibilities since 2002. This includes a variety of general maintenance activities as outlined in Section 2 and sampling and other monitoring activities outlined in Section 3.

Beginning in 2004, the Town and URS assumed all of the O&M activities described in the O&M plan. This report is the eighteenth semi-annual report as called for by Section 3.6 of the O&M plan.

2.0 **GENERAL MAINTENANCE ACTIVITIES**

Since completion of construction activities in 2002, personnel from the Town of Cheektowaga Engineering Department have performed general activities to ensure the physical operation of the landfill as intended by the design. The various O&M activities performed by the Town from July 2012 through December 2012 include the following actions.

- The amount of groundwater discharged through the collection system was recorded • on a daily basis. The flow rate displayed by each wet well pump at the time of daily inspection and the total cumulative volume of flow was recorded for each wet well on daily inspection sheets. Examples of the daily inspection sheet are attached in Appendix A.
- Total cumulative effluent flow rates and volumes were summarized on a monthly basis starting in February 2003. The monthly totals for the period of July 2012 through December 2012, including graphs showing daily total discharge (gallons) as a function of calendar day, are presented in Appendix B.
- The wet well pumps were shutdown during wet weather flow conditions throughout the year to reduce hydraulic loading to the sewer. Such actions were only taken upon request of the Buffalo Sewer Authority during heavy storm events in order to reduce the hydraulic load on the BSA treatment system during such events. Shutdown events are recorded and included with the monthly flow data as previously requested by NYSDEC.
- Plowed snow to access the Control Building when necessary.
- Cleaned/replaced check valves as necessary at all wet wells.
- Replaced surge suppressors and fuses as need for pump station instrumentation equipment.
- Performed annual mowing of the landfill cap and trimming which was completed on • September 18, 2012.

- Engaged contractor to apply Roundup herbicide to control vegetation growth through the stone access road. Applied herbicide on both Area B and C (i.e., along the perimeter access road around the landfill areas north and south of Aero Drive) following the annual mowing in September.
- Wildlife trapper engaged as needed to control ground burrowing animals. A total of 32 woodchucks were trapped from May through September 2012.
- Purchased a new A/C Unit (replacement) for the Control Building in October 2012 later installed in December 2012.
- Met with representatives of the Cornell Cooperative Extension of Erie County in August 2012 for assistance in identifying an invasive woody weed spreading throughout the perimeter access stone road. The perennial woody plant was identified as the Eastern Cottonwood which will be controlled in the future with herbicide and more frequent mowing.
- Replaced discharge hose at WW3 (December 2012).
- Met with the property owner south of Area C (i.e., the Landfill area south of Aero Drive) where perimeter fence damage was evident and re-established this section of fence line (October/November 2012) with the cooperation of the neighboring property owner.

3.0 MONITORING ACTIVITIES

The Town of Cheektowaga retained URS Corporation to perform monitoring activities as outlined in Section 3.1 of the O&M plan. During the period of January 2004 through the present, URS performed groundwater hydraulic monitoring (Section 3.1.1.2 of the O&M plan) and effluent monitoring (Section 3.1.4 of the O&M plan) on a quarterly basis. URS also performed the eighteenth semi-annual groundwater quality monitoring event (Section 3.1.1.3 of the O&M plan). A summary of the monitoring activities is presented in the following subsections. Hydraulic and groundwater sampling locations are shown on Figure 3-1.

3.1 Groundwater Hydraulic Monitoring

Groundwater and surface water elevations were monitored on a quarterly basis at all locations listed in Table 3.1 of the O&M Plan. The hydraulic monitoring data tables showing groundwater elevations are presented in Appendix C. Table 1 of this appendix lists the measured elevations. Table 2 provides a comparison of the measured levels in the wells and corresponding manholes/wet wells.

The data presented in Appendix C indicate that groundwater levels outside the collection system were higher than the levels measured in the corresponding wet well or manhole for each measurement date. Therefore, these data demonstrate that the collection system is operating as designed.

3.2 Groundwater Quality Monitoring

The eighteenth semi-annual round of groundwater sampling was conducted between November 6, 2012 and November 8, 2012. All wells listed in Table 3.2 of the O&M plan were purged and sampled using dedicated/disposable equipment. Figure 3-1 shows the well locations. Low flow sampling techniques were used at most monitoring well locations.

Passive diffusion bags (PDBs) were placed in three monitoring wells with low recharge rates (GW-4S, GW-7S, and GW-7D) on September 21, 2012. The PDBs were removed from the wells during the sampling event and their contents were analyzed for VOCs. Following removal of the PDBs the three wells were purged dry. These wells were sampled for the other required parameters after their water levels recovered.

Purge logs and sampling summary sheets are provided in Appendix D. Measurements of pH, specific conductivity, temperature, dissolved oxygen, oxidation reduction potential, and turbidity taken during purging are provided in Appendix D. The samples were packed with ice in coolers and transported under chain-of-custody (CoC) control to Test America Laboratories of Amherst, New York.

Table 3-1 of this report presents the groundwater sample results compared with NYSDEC Ambient Water Quality Standards and Guidance Values and Groundwater Effluent Limitations Class GA water quality standards. Groundwater samples were analyzed for the parameters listed in Table 3.2 of the O&M plan as revised in accordance with Table 3-6 in the Semi Annual Report dated September 2007 (January through June 2007) and as approved by the December 6, 2006 and November 29, 2007 correspondence from the NYSDEC authorizing a reduction in the parameters list (this table is included in this report as Table 3-2).

Results

No VOCs or SVOCs were detected at concentrations above the Class GA water quality standards at any location.

Among the metals, iron, magnesium, manganese, and sodium routinely exceed Class GA standards in most site wells. Chromium and lead were detected at concentrations exceeding Class GA standards in well GW-07D. It is noted that GW-07D is located upgradient of the site.

Comparison to Historical Results

No significant changes in metals concentrations were observed when compared to previous sampling event analytical results. The concentration of iron, magnesium, manganese, and sodium in most site wells was similar to the concentrations found during previous sampling events.

The concentrations of chromium and nickel at GW-07D and GW-03S, and lead at GW-07D were within the historical range of concentrations observed for these compounds at these wells.

Sodium concentrations were generally higher in bedrock wells (GW-01D, GW-03D, GW-08D and GW-26D) and shallow wells adjacent to roads (GW-01S and GW-30S). The sodium concentration was also elevated in GW-08SR. The higher sodium concentrations in the bedrock wells may be attributed to the local bedrock composition and the elevated concentration in the shallow wells may be the result of seasonal road de-icing activities.

Trend Analysis

A trend analysis of groundwater parameters that routinely exceed Class GA groundwater standards was performed and is presented in Figures E-1 through E-19 of Appendix E. A review of the trend analysis indicated that no significant changes or trends in concentrations of any of the parameters exceeding groundwater standards have occurred over the eighteen semi-annual sampling events except as described below. Figure E-2 for GW-01S, indicates a consistent drop in sodium concentration over the eighteen sampling events. Figure E-3 for GW-03D indicates a slight downward trend for manganese over the last eight sample events. Figure E-4 indicates a slight upward trend for magnesium in GW-03S since monitoring began. Figure E-5 for GW-04D, indicates a slight increasing trend for magnesium. Figure E-6 for GW-04S shows a slight upward trend for magnesium over the last 11 events. Figure E-7 for GW-07D shows an upward trend for chromium. Figure E-9 for GW-08D shows a decreasing trend for both iron and manganese since monitoring began. Figures E-10 and E-11 for GW-08SR and GW-26D, respectively, show an

upward trend in sodium concentrations since monitoring began. Figure E-10 for GW-08SR also indicates an upward trend for manganese. Figures E-12 and E-14 for GW-28S and GW-30S, respectively, indicate decreasing trends for magnesium and sodium since monitoring began. Figure E-16 shows there is a seasonal variation in sodium concentration in monitoring well GW-32S. Figures E-17 and E-18 for GW-33S and GW-34S indicate a seasonal fluctuation in manganese concentration.

Laboratory Report

The groundwater analytical data package was prepared by Test America in accordance with NYSDEC Category A deliverable requirements. It was reviewed for compliance with analytical method requirements and the following guidelines: USEPA *Contract Laboratory Program (CLP) National Functional Guidelines for Organic Data Review*, EPA-540-R-99-008, October 1999; USEPA *CLP National Functional Guidelines for Inorganic Data Review*, EPA-540-R-99-008, July 2002; and USEPA *Region II Data Validation SOP for SW-846 Method 8290, PCDDs and PCDFs by High Resolution Gas Chromatography/High-Resolution Mass Spectrometry (HRGC/HRMS)*, SOP No. HW-19, Revision 1, October 1994. Qualifications applied to the data include "J/UJ" (estimated concentration/estimated quantitation limit), "J+" (estimated concentration with possible high bias), "J-" (estimated concentration with possible low bias), and "U" (not detected).

A Data Applicability Report (DAR) was prepared following the guidelines provided in NYSDEC Division of Environmental Remediation (DER-10) *Technical Guidance for Site Investigation and Remediation, Appendix 2B,* dated May 2010. The DAR dated November 2012 is submitted separately from this report.

3.3 Groundwater Discharge Monitoring

URS completed two quarterly sampling events (September 2012 and December 2012) of the groundwater collection system discharge since the previous semi-annual report. The sampling was performed in accordance with the requirements of Discharge Permit No. 10-11CH016 between the Buffalo Sewer Authority and the Town of Cheektowaga. A copy of Permit No. 10-11-CH016 is included as Appendix F.

During the sampling events in September 2012 and December 2012, each regulated parameter was below the limits set by the permit. Copies of the data summary tables that were included with the monitoring reports are included as Appendix G.

3.4 Monitoring Well Inspections

During the November 2012 groundwater sampling event, a well inspection was performed. All wells appeared to be in good condition with the exception of previously existing damage to the risers on GW-07D, GW-01S, and GW-01D. The monitoring well inspection logs may be found in Appendix H.

4.0 SUMMARY AND RECOMMENDATIONS

General Maintenance: The Town will continue to maintain mechanical equipment at the landfill on an as-needed basis and operate the groundwater collection and discharge system as designed. The Town will also continue regular inspections, mow the cap once per year, and plow access to the control building during winter months as necessary.

Groundwater Hydraulic Monitoring: Hydraulic monitoring has been performed on a quarterly basis in conjunction with the discharge monitoring. Water level measurement data demonstrates that the hydraulic gradient is from outside the landfill towards the collection trench. Continued quarterly monitoring is recommended.

Groundwater Quality Monitoring: Groundwater sample results indicate that only low levels of organic compounds and metals are present. Similar concentrations of most parameters were found during previous sampling events. The nineteenth round of groundwater sampling will be conducted in May 2013. Low flow sampling techniques will be used. Passive diffusion bags will be used again for VOC analyses at the three wells (GW-4S, GW-7S, and GW-7D) that go dry even using low flow sampling techniques.

Groundwater Discharge Monitoring: Groundwater discharges remain within permit limits. Continued quarterly monitoring is recommended.

TABLES

Location ID			GW-01D	GW-01D	GW-01S	GW-03D	GW-04D
Sample ID			FD-110712	GW-1D	GW-1S	GW-3D	GW-4D
Matrix		Groundwater	Groundwater	Groundwater	Groundwater	Groundwater	
Depth Interval (fr	t)		-	-	-	-	-
Date Sampled			11/07/12	11/07/12	11/07/12	11/06/12	11/07/12
Parameter	Units	*	Field Duplicate (1-1)				
Volatile Organic Compounds							
1,2-Dichloroethene (total)	UG/L	5					
Semivolatile Organic Compounds							
1,3-Dichlorobenzene	UG/L	3				0.75 J	
1,4-Dichlorobenzene	UG/L	3				1.1 J	
bis(2-Ethylhexyl)phthalate	UG/L	5					
Arsenic	MG/L	0.025					
Barium	MG/L	1	0.071	0.071	0.15	0.095	0.068
Cadmium	MG/L	0.005					
Chromium	MG/L	0.05	0.016	0.021	0.0021 J		0.0020 J
Copper	MG/L	0.2				0.0016 J	
Iron	MG/L	0.3	0.20	0.23			0.036 J
Lead	MG/L	0.025					
Magnesium	MG/L	35	32.8	32.9	11.4	18.4	66.2
Manganese	MG/L	0.3	0.018	0.019	0.97	0.42	0.020
Mercury	MG/L	7.00E-04					
Nickel	MG/L	0.1	0.0054 J	0.0056 J		0.0032 J	
Sodium	MG/L	20	93.0	94.8	91.1		72.1
Zinc	MG/L	2	0.0040 J	0.0025 J	0.0027 J	0.0021 J	0.0023 J

*- NYSDEC TOGS (1.1.1), Ambient Water Quality Standards and Guidance Values and Groundwater Effluent Limitations. June 1998 (includes 4/2000 Addendum). Class GA. * - PCB Criteria based on sum of the aroclors.

Flags assigned during chemistry validation are shown.

Concentration Exceeds

J- - The analyte was positively identified, the quantitation is an estimation with possible low bias.

Location ID			GW-04S	GW-07D	GW-07S	GW-08D	GW-08SR
Sample ID			GW-4S	GW-7D	GW-7S	GW-8D	GW-8SR
Matrix		Groundwater	Groundwater	Groundwater	Groundwater	Groundwater	
Depth Interval (ff	t)		-	-	-	-	-
Date Sampled			11/07/12	11/07/12	11/07/12	11/06/12	11/06/12
Parameter	Units	*					
Volatile Organic Compounds							
1,2-Dichloroethene (total)	UG/L	5					
Semivolatile Organic Compounds							
1,3-Dichlorobenzene	UG/L	3					
1,4-Dichlorobenzene	UG/L	3					
bis(2-Ethylhexyl)phthalate	UG/L	5			2.6 J		
Arsenic	MG/L	0.025	0.0083 J				0.012
Barium	MG/L	1	0.25	0.067	0.34	0.078	0.46
Cadmium	MG/L	0.005		0.0014			
Chromium	MG/L	0.05	0.039	0.16	0.0046	0.014	0.0080
Copper	MG/L	0.2	0.035	0.021	0.0017 J	0.0042 J	0.0021 J
Iron	MG/L	0.3		8.7	0.68	0.25	22.8
Lead	MG/L	0.025	0.013	0.099			
Magnesium	MG/L	35	35.8	29.7	37.0	13.8	47.9
Manganese	MG/L	0.3	0.54	0.071	0.13	0.13	1.4
Mercury	MG/L	7.00E-04	0.00060				
Nickel	MG/L	0.1	0.032	0.085	0.014	0.0048 J	0.013
Sodium	MG/L	20	25.9	74.6	56.0		415
Zinc	MG/L	2	0.077	0.051	0.0071 J	0.0098 J	0.013

*- NYSDEC TOGS (1.1.1), Ambient Water Quality Standards and Guidance Values and Groundwater Effluent Limitations. June 1998 (includes 4/2000 Addendum). Class GA. * - PCB Criteria based on sum of the aroclors.

Flags assigned during chemistry validation are shown.

Concentration Exceeds

J- - The analyte was positively identified, the quantitation is an estimation with possible low bias.

Location ID			GW-26D	GW-28S	GW-29S	GW-30S	GW-31S	
Sample ID			GW-26D	GW-28S	GW-29S	GW-30S	GW-31S	
Matrix			Groundwater	Groundwater	Groundwater	Groundwater	Groundwater	
Depth Interval (ff	:)		-	-	-	-	-	
Date Sampled			11/08/12	11/07/12	11/08/12	11/08/12	11/08/12	
Parameter	Units	*						
Volatile Organic Compounds								
1,2-Dichloroethene (total)	UG/L	5	1.3 J					
Semivolatile Organic Compounds								
1,3-Dichlorobenzene	UG/L	3						
1,4-Dichlorobenzene	UG/L	3						
bis(2-Ethylhexyl)phthalate	UG/L	5						
Arsenic	MG/L	0.025			0.023			
Barium	MG/L	1	0.16	0.086	0.20	0.30	0.089	
Cadmium	MG/L	0.005			0.00050 J			
Chromium	MG/L	0.05	0.0012 J	0.0014 J			0.0020 J	
Copper	MG/L	0.2		0.0019 J			0.0025 J	
Iron	MG/L	0.3	5.9	0.11			0.42	
Lead	MG/L	0.025						
Magnesium	MG/L	35	20.8	27.2	90.8	37.3	35.4	
Manganese	MG/L	0.3	0.74	0.67	0.67		0.81	
Mercury	MG/L	7.00E-04						
Nickel	MG/L	0.1	0.0038 J	0.0036 J			0.017	
Sodium	MG/L	20	341	16.6	19.1	599	6.5	
Zinc	MG/L	2	0.0029 J	0.0041 J	0.0044 J	0.0038 J	0.011	

*- NYSDEC TOGS (1.1.1), Ambient Water Quality Standards and Guidance Values and Groundwater Effluent Limitations. June 1998 (includes 4/2000 Addendum). Class GA. * - PCB Criteria based on sum of the aroclors.

Flags assigned during chemistry validation are shown.

Concentration Exceeds

J- - The analyte was positively identified, the quantitation is an estimation with possible low bias.

Location ID	Location ID				GW-34S	GW-35S	
Sample ID			GW-32S	GW-33S	GW-34S	GW-35S	
Matrix	=			Groundwater	Groundwater	Groundwater	
Depth Interval (fr	t)		-	-	-	-	
Date Sampled			11/08/12	11/08/12	11/07/12	11/08/12	
Parameter	Units	*					
Volatile Organic Compounds							
1,2-Dichloroethene (total)	UG/L	5					
Semivolatile Organic Compounds							
1,3-Dichlorobenzene	UG/L	3					
1,4-Dichlorobenzene	UG/L	3					
bis(2-Ethylhexyl)phthalate	UG/L	5					
Arsenic		0.025					
	MG/L		0.005	0.040	0.000	0.40	
Barium	MG/L	1	0.065	0.048	0.099	0.13	
Cadmium	MG/L	0.005					
Chromium	MG/L	0.05		0.0042	0.011	0.0022 J	
Copper	MG/L	0.2			0.0053 J		
Iron	MG/L	0.3					
Lead	MG/L	0.025					
Magnesium	MG/L	35	36.6	91.5	29.8		
Manganese	MG/L	0.3	0.14	0.0082	0.026	0.035	
Mercury	MG/L	7.00E-04					
Nickel	MG/L	0.1	0.0024 J	0.0022 J	0.0075 J		
Sodium	MG/L	20	8.2	5.3	20.8	5.4	
Zinc	MG/L	2	0.0045 J	0.0056 J	0.0057 J	0.0045 J	

*- NYSDEC TOGS (1.1.1), Ambient Water Quality Standards and Guidance Values and Groundwater Effluent Limitations. June 1998 (includes 4/2000 Addendum). Class GA. *- PCB Criteria based on sum of the aroclors.

Flags assigned during chemistry validation are shown.

Concentration Exceeds

J- - The analyte was positively identified, the quantitation is an estimation with possible low bias.

TABLE 3-2

APPROVED REVISION OF TABLE 3.2 FROM THE O&M PLAN

GROUNDWATER SAMPLING SUMMARY OPERATION AND MAINTENANCE PLAN PFOHL BROTHERS LANDFILL SITE, CHEEKTOWAGA, NEW YORK

LOCATIONS

GW-1D/1S GW- 3D/3S GW- 4D/4S GW- 7D/7S GW- 8D/8S(R) GW- 26D/35S GW- 28S GW- 29S GW- 30S GW- 31S GW- 31S GW- 32S GW- 33S GW- 34S

FREQUENCY

semi-annually for overburden and bedrock groundwater

PARAMETERS

Field	pH conductivity temperature turbidity
VOCs	Acetone Benzene 1,2-Dichloroethene (total) 1,1,2-Trichloroethane Vinyl chloride
SVOCs	Phenol 1,3-Dichlorobenzene 1,4-Dichlorobenzene

bis(2-Ethylhexyl)phthalate

TABLE 3-2 (continued)


APPROVED REVISION OF TABLE 3.2 FROM THE O&M PLAN


GROUNDWATER SAMPLING SUMMARY OPERATION AND MAINTENANCE PLAN PFOHL BROTHERS LANDFILL SITE, CHEEKTOWAGA, NEW YORK

PARAMETERS (cont'd)

Metals Antimony Arsenic Barium Cadmium Chromium Copper Iron Lead Magnesium Manganese Mercury Nickel Silver Sodium Zinc

FIGURES





APPENDIX A

EXAMPLE DAILY INSPECTION SHEETS

 $\label{eq:constraint} $$ 02123k5515 ONEWORLDJOBS 11172700.0000 WORD DRAFT semi Annual Report Jul-Dec12 Semi Annual Semi Annu$

Pfohl Brothers Landfill Site

Daily Logsheet			Town of Cheektowaga			
)ate Time	8/17/12 10:05	-	Weather conditions Read by:	LT. RAINS OVERCAST 68 B. PUGH		
	Level of Water from bottom (ft.)	Flow gallons / minute	Flow Totals gallons	Pump Run Time Hrs.		
WW-3	4.9	0	110,257	2148		
WW-2	4.1	o	19,536	131		
WW-1	4.6	0	252,067	2150		
WW-6	7.3	0	0	2005		
WW-4	6.9	0	18122	5223		
WW-5	6.7	0	365,832	9511		
Flow Tota	alizer at Meter chamber		760,675			
	Outside temp T = 71 Current A = 0	-				
		<u> </u>				
	Current A =	<u>415,204</u> volts	Which WW was running	?		
	Current A = opressor events ntrol Center		Which WW was running 1 0 2 0 3 0 4 0 5 0 6 0	?		
	Current A = \odot opressor events ntrol Center Volts 48 °	volts		? 		
Motor Cor Filter	Current A = \odot opressor events ntrol Center Voits 4.8° Amps / \circ	volts _amps Changed 🛛		?		
Motor Cor Filter Comment	Current A = opressor events ntrol Center Volts 4.8 ° Amps / ° Checked s and/or Current Condition	volts amps Changed I	10 20 30 40 50 60	6		
Motor Cor Filter Comment	Current A = opressor events ntrol Center Volts 4.8 ° Amps / ° Checked s and/or Current Condition	volts amps Changed I	10 20 30 40 50 60	6		
Motor Cor Filter Comment	Current A = opressor events ntrol Center Volts 4.8 ° Amps / ° Checked s and/or Current Condition	volts amps Changed I	10 20 30 40 50 60	6		
Motor Cor Filter Comment	Current A = \odot opressor events ntrol Center Volts 48° Amps $/ \circ$ Checked \Box	volts amps Changed I	10 20 30 40 50 60	6		
Motor Cor Filter Comment	Current A = opressor events ntrol Center Volts 4.8 ° Amps / ° Checked s and/or Current Condition	volts amps Changed I	10 20 30 40 50 60	6		
Motor Cor Filter Comment	Current A = opressor events ntrol Center Volts 4.8 ° Amps / ° Checked s and/or Current Condition	volts amps Changed I	10 20 30 40 50 60	6		

Pfohl Brothers Landfill Site

£ +

Daily Lo	gsheet		Town of Cheektowaga		
vate Time	9-10-12 12:10		Weather conditions Read by:	BILL PUGH	
	Level of Water from bottom (ft.)	Flow gallons / minute	Flow Totals gallons	Pump Run Time Hrs.	
WW-3	4.7	40.8	153,465	2167	
WW-2	4.7	0	19,381	131	
WW-1	4.4	0	304,971	2170	
WW-6	7.1	0	107,207	7801	
WW-4	7.0	0	18,122	5223	
WW-5	6.9	0	550,214	9576	
Flow Tota	alizer at Meter chamber		1,148,161		
Heat Trace	e Outside temp T = 68 Current A = 0		Set point SP = 4.0		
irge Sup	pressor events	415,216			
Motor Con	ntrol Center Volts 480	volts	Which WW was running	?	
	Amps 6	amps	1 0 2 0 3 4 0 5 0 6 0		
Filter	Checked 🛛	Changed 🛛			
Comments	s and/or Current Condition	S			
R	ESET LEVEL 1	NVALID ALARA	1 WW-3		
R	ESET NEL.	FLOW AL	ARM WW-2		
	ESET LEVEL 1. ESET NEG. LLEARED AL	L ALARMS	•		
	MEET MOWIN	4 CONTRAC	CTOR AT SIN		
······································					

Pfohl Brothers Landfill Site

Daily Lo	ogsheet		Town of Cheektowaga		
)ate Time	11/27/12 2:05	-	Weather conditions Read by:	OVERCAST 38 BILL PUGH	
	Level of Water from bottom (ft.)	Flow gallons / minute	Flow Totals gallons	Pump Run Time Hrs.	
WW-3	6.0	40.1	299,784	2227	
WW-2	4.7	0	13,690	131	
WW-1	4:2	0	492,201	2250	
WW-6	7.1	0	1,509,564	8167	
WW-4	7.0	0	149,517	5297	
WW-5	7.2	0	1,422,870	9894	
Flow Tot	alizer at Meter chamber		3,889,093		
Heat Trac	Current $A = 1.9$		Set point SP = 40°		
Irge Su	ppressor events	415,229			
Motor Co	ntrol Center Volts 480	volts	Which WW was running	?	
	Amps 6	_amps	10 20 34 40 50 60	- -	
Filter	Checked 🛛	Changed 🛛			
Comment	ts and/or Current Condition	IS			
	RESET LEVEL 1 CLEARES AU	NVALID ALARM - ALARMS	WW3		

:					

APPENDIX B

MONTHLY FLOW SUMMARIES JULY 2012 – DECEMBER 2012

The TOWN OF CHEEKTOWAGA



Jon W. Nichy Superintendent Joseph Glab Asst. Superintendent Main Pump Station 171 Central Blvd. Cheektowaga, NY 14225 Phone: 716-896-1777 Fax: 716-896-6437

August 8, 2012

Mr. William R. Pugh, P.E. Town Engineer Town of Cheektowaga

Re: Pfohl Bros. Flow Data

Dear Mr. Pugh,

Enclosed for your review, please find a copy of the July 2012 Direct Discharge Flow Data Report, prepared by Jon W. Nichy.

On July 1, 2012 the Flow Totalizers were reset to zero.

Should you have any other questions or comments regarding this submittal, please contact this office @ 896-1777.

Yours truly. Ion W. Nichy


Superintendent Main Pump Station

Direct Discharge Flow Data

site Sta

			<u> </u>		•
6/30/2		14727189	48,708	14,721,671	
July-12	Time; 11:58pm unless otherwise stated	Totalizer Reading (Gallons)	Daily Total Discharge (Gallons)	Total Direct Discharge (Gallons)	Notes
1		2866	2,866	2,866	
2		30460	27,595	30,461	
3		33624	3,164	33,625	······
4		62306	28,683	62,308	
5		84501	22,195	84,503	
6		116614	32,113	116,616	
7		129583	12,969	129,585	
8		149098	19,515	149,100	
9		171892	22,794	171,894	
10		193620	21,728	193,622	
11		210427	16,807	210,429	
12		226621	16,194	226,623	
13		241956	15,335	241,958	
14		258061	16,105	258,063	
15		265267	7,205	265,268	
16		287501	22,234	287,502	
17		317482	29,981	317,483	
18		337349	19,867	337,350	
19		340692	3,343	340,693	
20		342767	2,075	342,768	
21		355692	12,924	355,692	
22		366493	10,801	366,493	
23		394242	27,749	394,242	0532inhibit 1013enabl
24		416959	22,717	416,959	
25		431245	14,286	431,245	
26		431807	562	431,807	0007inhibit
27		442789	10,981	442,788	1104enable
28		452271	9,482	452,270	
29		498154	45,883	498,153	
30		530348	32,194	530,347	
31		547797	17,448	547,795	
······		547,797	547,795	547,795	

:





The TOWN OF CHEEKTOWAGA



Jon W. Nichy Superintendent Joseph Glab Asst. Superintendent Main Pump Station 171 Central Blvd. Cheektowaga, NY 14225 Phone: 716-896-1777

Fax: 716-896-6437

September 4, 2012

Mr. William R. Pugh, P.E. Town Engineer Town of Cheektowaga

Re: Pfohl Bros. Flow Data

Dear Mr. Pugh,

Enclosed for your review, please find a copy of the August 2012 Direct Discharge Flow Data Report, prepared by Jon W. Nichy.


Should you have any other questions or comments regarding this submittal, please contact this office @ 896-1777.

Yours tr Kn W. Nichy

Superintendent Main Pump Station

Direct Discharge Flow Data

					-
7/31/20		547797	17,449	547,795	
August-12	11:58pm 11:58pm unless otherwise stated	Totalizer Reading (Gallons)	Daily Total Discharge (Gallons)	Total Direct Discharge (Gallons)	Notes
1		554012	6,215	554,010	
2		564363	10,351	564,361	
3		590989	26,627	590,988	
4		620088	29,099	620,087	······································
5		623893	3,805	623,892	1345 inhibit
6		642013	18,120	642,012	0017 enable
7		668078	26,065	668,077	
8		677487	9,409	677,486	
9		682533	5,047	682,533	
10		691464	8,931	691,464	
11		691464	0	691,464	
12		691464	0	691,464	******
13		708797	17,332	708,796	
14		716940	8,143	716,939	
15		751207	34,267	751,206	
16		760566	9,359	760,565	
17		761125	559	761,124	<u></u>
18		776204	15,079	776,203	
19		786081	9,877	786,080	******
20		787977	1,896	787,976	***************************************
21		802825	14,848	802,824	
22		902538	99, 7 13	902,537	
23		937981	35,443	937,980	
24		959241	21,260	959,240	
25		976528	17,288	976,528	
26		982251	5,723	982,251	
27		987138	4,887	987,138	
28		994034	6,896	994,034	······
29		1001410	7,376	1,001,410	······
30		1010496	9,085	1,010,495	
31		1015494	4,999	1,015,494	
	L	467,697	467,699	467,699	



August 2012

The TOWN OF CHEEKTOWAGA



Jon W. Nichy Superintendent Joseph Glab Asst. Superintendent Main Pump Station

171 Central Blvd. Cheektowaga, NY 14225 Phone: 716-896-1777 Fax: 716-896-6437

October 5, 2012

Mr. William R. Pugh, P.E. Town Engineer Town of Cheektowaga

Re: Pfohl Bros. Flow Data

Dear Mr. Pugh,


Enclosed for your review, please find a copy of the September 2012 Direct Discharge Flow Data Report, prepared by Jon W. Nichy.

Should you have any other questions or comments regarding this submittal, please contact this office @ 896-1777.

Yourstra Jon W. Nichy Superintendent Main Pump Station

Direct Discharge Flow Data

			<u> </u>		1
8/31/2012		1015494	4,999	1,015,494	
September-12	11:58pm 11:58pm unless otherwise stated	Totalizer Reading (Gallons)	Daily Total Discharge (Gallons)	Total Direct Discharge (Gallons)	Notes
1		1064380	48,886	1,064,380	
2		1087469	23,088	1,087,468	
3		1089455	1,986	1,089,454	
4		1094748	5,293	1,094,747	1552 inhibit
5		1104903	10,155	1,104,902	0012 enable
6		1108714	3,811	1,108,713	
7		1128317	19,603	1,128,316	2019 inhibit
8		1128317	0	1,128,316	
9		1147986	19,669	1,147,985	2320 enable
10		1157019	9,034	1,157,019	
11		1157137	118	1,157,137	
12		1157137	0	1,157,137	
13		1157137	0	1,157,137	
14		1175191	18,054	1,175,191	1715 inhibit
15		1210748	35,556	1,210,747	0851 enable
16		1218788	8,040	1,218,787	
17		1297931	79,144	1,297,931	
18		1347197	49,265	1,347,196	
19		1347197	0	1,347,196	
20		1347334	137	1,347,333	
21		1348170	836	1,348,169	
22		1350568	2,398	1,350,567	0232inhibit 1946enable
23		13857 2 6	35,158	1,385,725	····
24		1387542	1,815	1,387,540	
25		1401757	14,215	1,401,755	
26		1401757	0	1,401,755	
27		1401757	0	1,401,755	-
28		1401757	0	1,401,755	
29		1425256	23,499	1,425,254	
30		1439632	14,376	1,439,630	
31			101 101	1011120	
		424,138	424,136	424,136	



The TOWN OF **CHEEKTOWAGA**



Jon W. Nichy Superintendent Joseph Glab Asst. Superintendent **Main Pump Station** 171 Central Blvd.

Cheektowaga, NY 14225 Phone: 716-896-1777 Fax: 716-896-6437

µ0√. October 6, 2012

Mr. William R. Pugh, P.E. **Town Engineer** Town of Cheektowaga

> Re: Pfohl Bros. Flow Data

Dear Mr. Pugh,

OCT.

Enclosed for your review, please find a copy of the September 2012 Direct Discharge Flow Data Report, prepared by Jon W. Nichy.


Should you have any other questions or comments regarding this submittal, please contact this office @ 896-1777.

Yours truly,

in bill Jon W. Nichy Superintendent/ Main Pump Station

Direct Discharge Flow Data

		·····	<u> </u>		
9/30/2012		1439632	14,376	1,439,630	
October-12	11:58pm 11:58pm unless otherwise stated	Totalizer Reading (Gallons)	Daily Total Discharge (Gallons)	Total Direct Discharge (Gallons)	Notes
1		1439632	0	1,439,630	
2		1442225	2,593	1,442,223	
3		1541296	99,071	1,541,294	······································
4		1564945	23,649	1,564,943	
5		1614495	49,550	1,614,493	2237 inhibit
6		1614495	0	1,614,493	
7		1630313	16,118	1,630,611	0834 enable
8		1636594	5,981	1,636,592	
9		1668817	32,222	1,668,814	
10		1678578	9,762	1,678,576	
11		1687194	8,615	1,687,191	
12		1698766	11,573	1,698,764	
13		1703325	4,560	1,703,324	
14		1729527	26,201	1,729,525	0654 inhibit 1858 enabl
15		1839443	109, 9 16	1,839,441	
16		1854632	15,189	1,854,630	
17		1860946	6,314	1,860,944	<u></u>
18		1860946	0	1,860,944	2233 inhibit
19		1860946	0	1,860,944	2104 enable
20		1860946	о	1,860,944	1436 inhibit
21		1888678	27,732	1,888,676	1649 enable
22		2024364	135,687	2,024,363	
23		2024364	О	2,024,363	0337 inhibit 2354 enable
24		2114222	89,858	2,114,221	
25		2230913	116,691	2,230,912	
26		2318133	87,220	2,318,132	2306 inhibit
27		2318133	0	2,318,132	
28		2342295	24,162	2,342,294	1952 enable
29		2368708	26,414	2,368,708	0146 inhibit
30		2453947	85,239	2,453,947	1328 enable
31		2661526 1,221,894	207,579 1,221,896	2,661,526 1,221,896	2040 inhibit



allen ",

200

The TOWN OF CHEEKTOWAGA



Jon W. Nichy Superintendent Joseph Glab Asst. Superintendent Main Pump Station

171 Central Blvd. Cheektowaga, NY 14225 Phone: 716-896-1777 Fax: 716-896-6437

December 4, 2012

Mr. William R. Pugh, P.E. Town Engineer Town of Cheektowaga

Re: Pfohl Bros. Flow Data

Dear Mr. Pugh,

Enclosed for your review, please find a copy of the November 2012 Direct Discharge Flow Data Report, prepared by Jon W. Nichy.


Should you have any other questions or comments regarding this submittal, please contact this office @ 896-1777.

Yours truly,

Jon W. Nichy Superintendent Main Pump Station

Direct Discharge Flow Data

			<u> </u>		
10/31/2012		2661526	207,579	2,661,526	······································
November-12	Time; 11:58pm unless otherwise stated	Totalizer Reading (Gallons)	Daily Total Discharge (Gallons)	Total Direct Discharge (Gallons)	Notes
1		2796267	134,741	2,796,267	
2		2945069	148,802	2,945,069	
3		3134636	189,567	3,134,636	
4		3248809	114,173	3,248,809	
5		3249968	1,159	3,249,968	······································
6		3279541	29,573	3,279,541	
7		3279541	0	3,279,541	·
8		3348757	69,216	3,348,757	
9		3417333	68,577	3,417,334	
10		3417333	0	3,417,334	
11		3417333	0	3,417,334	
12		3456632	39,298	3,456,632	
13		3528726	72,094	3,528,726	
14		3587891	59,166	3,587,892	
15		3613122	25,230	3,613,122	
16		3613122	0	3,613,122	
17		3618309	5,188	3,618,310	
18		3657176	38,867	3,657,177	
19		3657176	0	3,657,177	
20		3696862	39,687	3,696,864	
21		3788616	91,754	3,788,618)
22		3795400	6,784	3,795,402	
23		3838941	43,541	3,838,943	
24		3841689	2,748	3,841,691	
25		3865081	23,392	3,865,083	3
26		3873895	8,814	3,873,897	7
27		3910722	36,828	3,910,725	5
28		3930472	19,750	3,930,47	5
29		3940514	10,043	3,940,510	3
30		3984300	43,786	3,984,304	4
31					
		1,322,774	1,322,778	1,322,77	5]



and: dite

· ~ 34

The TOWN OF CHEEKTOWAGA



Jon W. Nichy Superintendent Joseph Glab Asst. Superintendent Main Pump Station 171 Central Blvd. Cheektowaga, NY 14225 Phone: 716-896-1777 Fax: 716-896-6437

January 3, 2013

Mr. William R. Pugh, P.E. Town Engineer Town of Cheektowaga

Re: Pfohl Bros. Flow Data

Dear Mr. Pugh,

Enclosed for your review, please find a copy of the **December 2012** Direct Discharge Flow Data Report, prepared by Jon W. Nichy.


Should you have any other questions or comments regarding this submittal, please contact this office @ 896-1777.

Yours fr

Ion W. Nichy Superintendent Main Pump Station

Direct Discharge Flow Data

11/30/2012		3984300	43,786	3,984,304	
December-12	Time; 11:58pm unless otherwise stated	Totalizer Reading (Gallons)	Daily Total Discharge (Gallons)	Total Direct Discharge (Gallons)	Notes
1		4039201	54,901	4,039,205	
2		4039201	0	4,039,205	1354inhibit 2327enable
3		4082739	43,538	4,082,743	
4		4105052	22,314	4,105,057	1909inhibit 2354enable
5		4196864	91,812	4,196,869	
6		4318427	121,563	4,318,432	
7		4328486	10,059	4,328,491	
8		4387285	58,799	4,387,290	
9		4463823	76,538	4,463,828	2020inhibit
10		4463823	0	4,463,828	
11		4617894	154,072	4,617,900	0427enable
12		4747504	129,610	4,747,510	
13		4806235	58,731	4,806,241	
14		4816586	10,352	4,816,593	
15		4828850	12,264	4,828,857	· · · · · · · · · · · · · · · · · · ·
16		4842916	14,067	4,842,924	
17		4930853	87,937	4,930,861	2307ihibit
18		4933504	2,651	4,933,512	
19		5057737	124,234	5,057,746	0013enable
20		5177982	120,245	5,177,991	2328inhibit
21		5224525	46,543	5,224,534	0727enable 1716inhibi
22		5327964	103,440	5,327,974	0924enable
23		5427502	99,538	5,427,512	
24		5434296	6,794	5,434,306	
25		5442693	8,397	5,442,703	
26		5561147	118,454	5,561,157	
27		5586297	25,151	5,586,308	
28		5587023	726	5,587,034	· · · · · · · · · · · · · · · · · · ·
29		5587023	0	5,587,034	·····
30		5730493	143,471	5,730,505	
31		5760787	30,294	5,760,799	



NA 830

¢

: ; ;

APPENDIX C

HYDRAULIC MONITORING TABLES

Location ID / Type	Northing	Easting	Ground Elevation (ft)	Casing Elevation (ft)	Meas.point (Riser)Elev.(ft)	Geol. Zone	Specific Gravity	Date / Time	Depth to Water (ft)	Water Elev. (ft)	Product Thick. (ft)	Corrected Water Elev. (ft)	Remark
GW-01D	1073088.634	1117968.213	694.41	NM	696.12	D	1						
MNW								9/20/2012 1235	4.10	692.02	0.00	692.02	
MNW								11/6/2012 0915	2.81	693.31	0.00	693.31	
MNW								12/27/2012 1506	2.88	693.24	0.00	693.24	
GW-01S	1073087.779	1117961.500	694.53	NM	696.19	S	1						
MNW								9/20/2012 1234	4.91	691.28	0.00	691.28	
MNW								11/6/2012 0914	3.38	692.81	0.00	692.81	
MNW								12/27/2012 1505	3.57	692.62	0.00	692.62	
GW-03D	1073819.106	1114602.426	692.35	NM	693.88	D	1						
MNW								9/20/2012 1134	2.54	691.34	0.00	691.34	
MNW								11/6/2012 0812	2.08	691.80	0.00	691.80	
MNW								12/27/2012 1238	2.03	691.85	0.00	691.85	
GW-03S	1073812.622	1114605.762	692.61	NM	693.80	S	1						
MNW								9/20/2012 1133	DRY		0.00		
MNW								11/6/2012 0810	DRY		0.00		Dry @ 13.24'
MNW								12/27/2012 1238	5.05	688.75	0.00	688.75	
GW-04D	1072289.432	1114685.625	690.89	NM	692.75	D	1						
MNW								9/20/2012 1248	14.40	678.35	0.00	678.35	
MNW								11/6/2012 0909	13.64	679.11	0.00	679.11	
MNW								12/27/2012 1445	13.09	679.66	0.00	679.66	
GW-04S	1072284.456	1114685.127	690.76	NM	692.72	S	1						
MNW								9/20/2012 1247	10.15	682.57	0.00	682.57	
MNW								11/6/2012 0908	6.47	686.25	0.00	686.25	
MNW								12/27/2012 1444	4.57	688.15	0.00	688.15	

NM - No Measurement

The value noted in the column labeled Specific Gravity is an assumed value for free product, if found.

Type: MH

MNW

SG

Location ID / Type	Northing	Easting	Ground Elevation (ft)	Casing Elevation (ft)	Meas.point (Riser)Elev.(ft)	Geol. Zone	Specific Gravity	Date / Time	Depth to Water (ft)	Water Elev. (ft)	Product Thick. (ft)	Corrected Water Elev. (ft)	Remark
GW-07D	1071242.458	1117669.925	697.15	NM	699.94	D	1						
MNW								9/20/2012 1229	49.59	650.35	0.00	650.35	
MNW								11/6/2012 0923	46.42	653.52	0.00	653.52	
MNW								12/27/2012 1514	55.37	644.57	0.00	644.57	
GW-07S	1071238.157	1117666.265	697.47	NM	699.51	S	1						
MNW								9/20/2012 1230	8.32	691.19	0.00	691.19	
MNW								11/6/2012 0924	4.55	694.96	0.00	694.96	
MNW								12/27/2012 1513	4.80	694.71	0.00	694.71	
GW-08D	1073713.617	1116795.328	695.28	NM	697.79	D	1						
MNW								9/20/2012 1147	6.58	691.21	0.00	691.21	
MNW								11/6/2012 0827	6.05	691.74	0.00	691.74	
MNW								12/27/2012 1320	6.00	691.79	0.00	691.79	
GW-08SR	1073714.172	1116786.343	695.08	NM	697.50	S	1						
MNW								9/20/2012 1147	5.47	692.03	0.00	692.03	
MNW								11/6/2012 0827	5.46	692.04	0.00	692.04	
MNW								12/27/2012 1320	5.31	692.19	0.00	692.19	
GW-26D	1071698.573	1115997.470	696.01	NM	698.50	D	1						
MNW								9/20/2012 1218	7.41	691.09	0.00	691.09	
MNW								11/6/2012 0856	6.92	691.58	0.00	691.58	
MNW								12/27/2012 1415	6.88	691.62	0.00	691.62	
GW-28S	1073129.479	1117648.927	698.60	NM	700.95	S	1						
MNW								9/20/2012 1156	11.28	689.67	0.00	689.67	
MNW								11/6/2012 0835	8.55	692.40	0.00	692.40	
MNW								12/27/2012 1334	8.77	692.18	0.00	692.18	

NM - No Measurement

Filter = ([tblGWD].[LOGDATE]>=#9/20/2012#)

The value noted in the column labeled Specific Gravity is an assumed value for free product, if found.

Type: MH

MNW

SG



Location ID / Type	Northing	Easting	Ground Elevation (ft)	Casing Elevation (ft)	Meas.point (Riser)Elev.(ft)	Geol. Zone	Specific Gravity	Date / Time	Depth to Water (ft)	Water Elev. (ft)	Product Thick. (ft)	Corrected Water Elev. (ft)	Remark
GW-29S	1072552.638	1117761.993	697.50	NM	699.63	S	1						
MNW								9/20/2012 1205	10.53	689.10	0.00	689.10	
MNW								11/6/2012 0843	6.88	692.75	0.00	692.75	
MNW								12/27/2012 1350	7.49	692.14	0.00	692.14	
GW-30S	1072096.109	1117743.563	693.67	NM	696.58	S	1						
MNW								9/20/2012 1208	8.39	688.19	0.00	688.19	
MNW								11/6/2012 0846	8.00	688.58	0.00	688.58	
MNW								12/27/2012 1355	7.98	688.60	0.00	688.60	
GW-31S	1071786.280	1117191.441	695.84	NM	698.62	S	1						
MNW								9/20/2012 1212	8.23	690.39	0.00	690.39	
MNW								11/6/2012 0850	2.45	696.17	0.00	696.17	
MNW								12/27/2012 1400	2.58	696.04	0.00	696.04	
GW-32S	1071613.793	1116364.200	696.19	NM	698.37	S	1						
MNW								9/20/2012 1214	Dry		0.00		
MNW								11/6/2012 0853	2.58	695.79	0.00	695.79	
MNW								12/27/2012 1412	2.70	695.67	0.00	695.67	
GW-33S	1072165.625	1115561.866	695.94	NM	698.24	S	1						
MNW								9/20/2012 1223	Dry		0.00		
MNW								11/6/2012 0901	4.08	694.16	0.00	694.16	
MNW								12/27/2012 1428	3.97	694.27	0.00	694.27	
GW-34S	1072979.205	1114730.200	692.51	NM	694.77	S	1						
MNW								9/20/2012 1125	Dry		0.00		
MNW								11/6/2012 0802	3.35	691.42	0.00	691.42	
MNW								12/27/2012 1225	2.71	692.06	0.00	692.06	

NM - No Measurement

Filter = ([tblGWD].[LOGDATE]>=#9/20/2012#)

The value noted in the column labeled Specific Gravity is an assumed value for free product, if found.



MNW

SG

Location ID / Type	Northing	Easting	Ground Elevation (ft)	Casing Elevation (ft)	Meas.point (Riser)Elev.(ft)	Geol. Zone	Specific Gravity	Date / Time	Depth to Water (ft)	Water Elev. (ft)	Product Thick. (ft)	Corrected Water Elev. (ft)	Remark
GW-35S	1071701.925	1115985.585	696.19	NM	697.39	S	1						
MNW								9/20/2012 1219	Dry		0.00		
MNW								11/6/2012 0850	4.25	693.14	0.00	693.14	
MNW								12/27/2012 1415	3.17	694.22	0.00	694.22	
MH-01	1073806.665	1114810.501	698.62	NM	698.62	NA	1						
МН								9/20/2012 1130	10.54	688.08	0.00	688.08	
MH								11/6/2012 0806	10.23	688.39	0.00	688.39	
MH								12/27/2012 1229	11.01	687.61	0.00	687.61	
MH-03	1073736.789	1115259.334	699.40	NM	699.40	NA	1						
МН								9/20/2012 1140	11.25	688.15	0.00	688.15	
MH								11/6/2012 0822	11.11	688.29	0.00	688.29	
MH								12/27/2012 1452	11.26	688.14	0.00	688.14	
MH-07	1073838.229	1116243.757	696.82	NM	696.82	NA	1						
МН								9/20/2012 1142	9.47	687.35	0.00	687.35	
MH								11/6/2012 0819	9.32	687.50	0.00	687.50	
MH								12/27/2012 1307	9.46	687.36	0.00	687.36	
MH-10	1073540.729	1117381.524	703.01	NM	703.01	NA	1						
MH								9/20/2012 1154	14.51	688.50	0.00	688.50	
MH								11/6/2012 0831	14.49	688.52	0.00	688.52	
MH								12/27/2012 1328	14.48	688.53	0.00	688.53	
MH-15	1072531.567	1117761.125	699.02	NM	699.02	NA	1						
МН								9/20/2012 1205	15.02	684.00	0.00	684.00	
MH								11/6/2012 0842	14.97	684.05	0.00	684.05	
MH								12/27/2012 1350	14.91	684.11	0.00	684.11	

NM - No Measurement

The value noted in the column labeled Specific Gravity is an assumed value for free product, if found.



MNW

SG

Location ID Type	/ Northing	Easting	Ground Elevation (ft)	Casing Elevation (ft)	Meas.point (Riser)Elev.(ft)	Geol. Zone	Specific Gravity	Date / Time	Depth to Water (ft)	Water Elev. (ft)	Product Thick. (ft)	Corrected Water Elev. (ft)	Remark
MH-16	1072133.714	1117748.238	698.57	NM	698.57	NA	1						
N	н							9/20/2012 1208	14.53	684.04	0.00	684.04	
N	IH							11/6/2012 0846	14.51	684.06	0.00	684.06	
N	IH							12/27/2012 1355	14.51	684.06	0.00	684.06	
MH-17	1071813.137	1117180.019	702.16	NM	702.16	NA	1						
N	н							9/20/2012 1212	18.14	684.02	0.00	684.02	
N	н							11/6/2012 0849	18.16	684.00	0.00	684.00	
N	IH							12/27/2012 1400	18.15	684.01	0.00	684.01	
MH-20	1071756.395	1115997.024	706.20	NM	706.20	NA	1						
Ν	н							9/20/2012 1220	19.72	686.48	0.00	686.48	
N	IH							11/6/2012 0855	19.73	686.47	0.00	686.47	
N	IH							12/27/2012 1417	19.75	686.45	0.00	686.45	
MH-22	1072158.023	1115589.309	698.05	NM	698.05	NA	1						
Ν	н							9/20/2012 1224	8.99	689.06	0.00	689.06	
N	IH							11/6/2012 0900	9.01	689.04	0.00	689.04	
N	IH							12/27/2012 1427	9.02	689.03	0.00	689.03	
MH-25	1072483.928	1114820.313	698.17	NM	698.17	NA	1						
Ν	н							9/20/2012 1120	10.13	688.04	0.00	688.04	
N	IH							11/6/2012 0755	9.81	688.36	0.00	688.36	
N	IH							12/27/2012 1220	10.60	687.57	0.00	687.57	
SG-01	1073882.887	1114813.101	NM	NM	690.00	NA	1						
5	G							9/20/2012 1130	Dry		NP		
S	G							11/6/2012 0807	-1.20	691.20	0.00	691.20	
5	G							12/27/2012 1240	-1.23	691.23	0.00	691.23	

NM - No Measurement

The value noted in the column labeled Specific Gravity is an assumed value for free product, if found.

Type: MH MNW

SG

Location ID / Type	Northing	Easting	Ground Elevation (ft)	Casing Elevation (ft)	Meas.point (Riser)Elev.(ft)	Geol. Zone	Specific Gravity	Date / Time	Depth to Water (ft)	Water Elev. (ft)	Product Thick. (ft)	Corrected Water Elev. (ft)	Remark
SG-02	1073738.27	1116805.85	NM	NM	690.00	NA	1						
so	6							9/20/2012 1150	-2.90	692.90	0.00	692.90	
SO	6							11/6/2012 0820	-3.10	693.10	0.00	693.10	
SC	6							12/27/2012 1320	SNOW		0.00		Snow Covered/Frozen
WW-01	1073676.903	1115710.476	NM	NM	684.02	NA	1						
MF	4							9/20/2012 1050	-3.9	687.92	0.00	687.92	
MH	1							11/6/2012 0730	-4.1	688.12	0.00	688.12	
MH	4							12/27/2012 1130	-3.9	687.92	0.00	687.92	
WW-02	1073684.724	1116792.311	NM	NM	684.18	NA	1						
MH	4							9/20/2012 1050	-4.6	688.78	0.00	688.78	
MH	1							11/6/2012 0730	-4.6	688.78	0.00	688.78	
MH	4							12/27/2012 1130	-4.7	688.88	0.00	688.88	
WW-03	1073140.339	1117618.499	NM	NM	683.80	NA	1						
MH	4							9/20/2012 1050	-4.6	688.40	0.00	688.40	
MH	1							11/6/2012 0730	ERROR		0.00		Level Error
MH	1							12/27/2012 1130	-4.6	688.40	0.00	688.40	
WW-04	1072057.563	1117610.508	NM	NM	676.62	NA	1						
MH	4							9/20/2012 1020	-7.0	683.62	0.00	683.62	
MH	4							11/6/2012 0730	-6.9	683.52	0.00	683.52	
MH	1							12/27/2012 1130	-6.9	683.52	0.00	683.52	
WW-05	1071661.368	1116370.876	NM	NM	676.14	NA	1						
MH	4							9/20/2012 1050	-7.4	683.54	0.00	683.54	
MF	4							11/6/2012 0730	-5.6	681.74	0.00	681.74	
MH	4							12/27/2012 1130	-7.3	683.44	0.00	683.44	

NM - No Measurement

Filter = ([tblGWD].[LOGDATE]>=#9/20/2012#)

The value noted in the column labeled Specific Gravity is an assumed value for free product, if found.

Type: MH MNW

SG

	Location ID / Type	Northing	Easting	Ground Elevation (ft)	Casing Elevation (ft)	Meas.point (Riser)Elev.(ft)		Specific Gravity		Depth to Water (ft)	Water Elev. (ft)	Product Thick. (ft)	Corrected Water Elev. (ft)	Remark
v	/W-06	1072988.420	1114811.518	NM	NM	681.89	NA	1						
	MH								9/20/2012 1050	-6.5	688.39	0.00	688.39	
	MH								11/6/2012 0730	-7.0	688.89	0.00	688.89	
	MH								12/27/2012 1130	-6.2	688.09	0.00	688.09	

NM - No Measurement

The value noted in the column labeled Specific Gravity is an assumed value for free product, if found.

 Type:

 MH
 Manhole Monitoring Point

 MNW
 Monitoring Well

 SG
 Staff Gauge

Filter = ([tblGWD].[LOGDATE]>=#9/20/2012#)

Printed: 5/6/2013 2:31:11 PN N:\11172700.00000\GIS\dB\Program\EDMS.mde/Groundwater Lev

TABLE 2 PFOHL BROTHERS LANDFILL SITE OVERBURDEN HYDRAULIC GRADIENT

WELL PAIR:	WW-1	*	Level	WW-2	GW-8SR	Level	SG-02	Level
		Water Level	Difference		Water Level	Difference	Water Level	Difference
DATE	(ft amsl)	(ft amsl)	(ft)	(ft amsl)	(ft amsl)	(ft)	(ft amsl)	(ft)
9/20/2012	687.92			688.78	692.03	3.25	692.90	4.12
11/6/2012	688.12			688.78	692.04	3.26	693.10	4.32
12/27/2012	687.92			688.88	692.19	3.31	FROZEN	NA
							-	
WELL PAIR:	WW-3	GW-28S	Level	WW-4	*	Level		
	Water Level	Water Level	Difference	Water Level	Water Level	Difference	1	
DATE	(ft amsl)	(ft amsl)	(ft)	(ft amsl)	(ft amsl)	(ft)		
9/20/2012	688.40	689.67	1.27	683.62				
11/6/2012	ERROR	692.40	NA	683.52				
12/27/2012	688.40	692.18	3.78	683.52				
							-	
WELL PAIR:	WW-5	GW-32S	Level	WW-6	GW-34S	Level		
	Water Level	Water Level	Difference	Water Level	Water Level	Difference		
DATE	(ft amsl)	(ft amsl)	(ft)	(ft amsl)	(ft amsl)	(ft)		
9/20/2012	683.54	DRY	NA	688.39	DRY	NA		
11/6/2012	681.74	695.79	14.05	688.89	691.42	2.53		
12/27/2012	683.44	695.67	12.23	688.09	692.06	3.97		
							_	
WELL PAIR:	MH-1	SG-1	Level	MH-15	GW-29S	Level		
	Water Level	Water Level	Difference	Water Level	Water Level	Difference		
DATE	(ft amsl)	(ft amsl)	(ft)	(ft amsl)	(ft amsl)	(ft)		
9/20/2012	688.08	DRY	NA	684.00	689.10	5.10		
11/6/2012	688.39	691.20	2.81	684.05	692.75	8.70		
12/27/2012	687.61	691.23	3.62	684.11	692.14	8.03		
							_	
WELL PAIR:	MH-16	GW-30S	Level	MH-17	GW-31S	Level		
	Water Level	Water Level	Difference	Water Level	Water Level	Difference		
DATE	(ft amsl)	(ft amsl)	(ft)	(ft amsl)	(ft amsl)	(ft)		
9/20/2012	684.04	688.19	4.15	684.02	690.39	6.37	l	
11/6/2012	684.06	688.58	4.52	684.00	696.17	12.17		
12/27/2012	684.06	688.60	4.54	684.01	696.04	12.03		
							_	
WELL PAIR:	MH-20	GW-35S	Level	MH-22	GW-33S	Level		
	Water Level	Water Level	Difference	Water Level	Water Level	Difference		
DATE	(ft amsl)	(ft amsl)	(ft)	(ft amsl)	(ft amsl)	(ft)]	
9/20/2012	686.48	DRY	NA	689.06	DRY	NA		
11/6/2012	686.47	693.14	6.67	689.04	694.16	5.12	l	
12/27/2012	686.45	694.22	7.77	689.03	694.27	5.24		

Notes:

* = No corresponding monitoring well. NA = Not applicable

APPENDIX D

GROUNDWATER PURGE AND SAMPLE COLLECTION LOGS

Project:		11175616.00000		Site:	Pfohl B	lrothers	Well I.D.:	GW-1S	
Date:	11/7/2012	Sampling	Personnel:	Tim Ifkovi	ch, Kevin Mo	cGovern	Company:	URS Corporation	
Purging/ Sampling Device:		Geopump 2		_Tubing Type:	LDPE/S	Silicone	Pump/Tubing Inlet Location:	Screen midpoint	
Measuring Point:	Below Top of Riser	Initial Depth to Water:	3.40'	Depth to Well Bottom:	14.94'	Well Diameter:	2"	Screen Length:	
Casing Type:	Stainles	s Steel		Volume in 1 Well Casing (liters):	7.1		Estimated Purge Volume (liters):	9.0	
Sample Sample Sample ID: GW-1S Time: 12:47 QA/QC: None									
•	er Information:	VOCs, SVOCs, a Riser pipe is bulg Orange stain in v	ged inwards,	could not remove	e stainless s	teel bailer fror	m within well, sar	npled around it.	

PURGE PARAMETERS

TIME	рН	TEMP (°C)	COND. (mS/cm)	DISS. O ₂ (mg/l)	TURB. (NTU)	ORP (mV)	FLOW RATE (ml/min.)	DEPTH TO WATER (btor)
12:02	8.04	11.86	0.601	0.50	>800	-156	200	3.40
12:07	7.67	11.61	0.605	0.00	488	-150	200	4.15
12:12	7.59	11.88	0.601	0.00	490	-157	200	4.28
12:17	7.55	11.96	0.599	0.00	341	-157	200	4.32
12:22	7.52	12.06	0.598	0.00	213	-159	200	4.38
12:27	7.52	12.05	0.602	0.00	255	-152	200	4.40
12:32	7.50	12.16	0.605	0.00	180	-154	200	4.45
12:37	7.48	12.24	0.611	0.00	145	-153	200	4.47
12:42	7.49	12.10	0.616	0.00	140	-151	200	4.49
12:47	7.47	12.28	0.619	0.00	92.9	-150	200	4.50
Tolerance:	0.1		3%	10%	10%	+ or - 10		

Project:	11175616.00000			Site:	Pfohl I	Brothers	Well I.D.:	GW-1D
Date:	11/7/2012	Sampling	Personnel:	Tim Ifkovi	ich, Kevin N	lcGovern	Company:	URS Corporation
Purging/ Sampling Device:		Geopump 2		Tubing Type:	LDPE/	/Silicone	Pump/Tubing Inlet Location:	Screen midpoint
Measuring Point:	Below Top of Riser	Initial Depth to Water:	2.95'	Depth to Well Bottom:	39.65'	Well Diameter:	4"	Screen Length:
Casing Type:	Stainles	s Steel		Volume in 1 Well Casing (liters):	90.6	_	Estimated Purge Volume (liters):	49.7
Sample ID:		GW-1D		Sample Time:	11	1:47	QA/QC:	Duplicate (FD-110712)
	e Parameters: er Information:	VOCs, SVOCs, a Sulfur odor	and TAL Meta	als				

PURGE PARAMETERS

TIME	рН	TEMP (°C)	COND. (mS/cm)	DISS. O₂ (mg/l)	TURB. (NTU)	ORP (mV)	FLOW RATE (ml/min.)	DEPTH TO WATER (btor)
10:47	7.92	11.71	0.823	0.43	12.8	-69	690	2.95
10:52	7.72	11.86	0.816	0.00	3.1	-120	840	2.95
10:57	7.71	11.74	0.816	0.00	3.2	-135	840	2.95
11:02	7.71	12.02	0.816	0.00	1.2	-140	840	2.95
11:07	7.70	12.10	0.816	0.00	1.5	-153	840	2.95
11:12	7.69	12.15	0.815	0.00	0.7	-159	840	2.95
11:17	7.67	12.20	0.814	0.00	0.0	-168	840	2.95
11:22	7.66	12.21	0.813	0.00	0.0	-174	840	2.95
11:27	7.66	12.21	0.813	0.00	0.0	-182	840	2.95
11:32	7.66	12.22	0.813	0.00	0.0	-187	840	2.95
11:37	7.66	12.23	0.813	0.00	0.0	-191	840	2.95
11:42	7.66	12.22	0.812	0.00	0.0	-195	840	2.95
11:47	7.66	12.24	0.812	0.00	0.0	-199	840	2.95
Tolerance:	0.1		3%	10%	10%	+ or - 10		

Project:		11175616.00000)	Site:	Pfohl I	Brothers	Well I.D.:	GW-3S
Date:	11/6/2012	Sampling	Personnel:	Tim Ifkovi	ch, Kevin N	lcGovern	_ Company:_	URS Corporation
Purging/ Sampling Device:		Geopump 2		Tubing Type:	LDPE/	/Silicone	Pump/Tubing Inlet Location:	Screen midpoint
Measuring Point:	Below Top of Riser	Initial Depth to Water:	DRY	Depth to Well Bottom:	13.22'	Well Diameter:	2"	Screen Length:
Casing Type:	Stainles	ss Steel		Volume in 1 Well Casing (liters):		_	Estimated Purge Volume (liters):	
Sample ID:		GW-3S		Sample Time:	1	NA	QA/QC:	
	e Parameters: er Information:	W	ell was Dry					

PURGE PARAMETERS

TIME	рН	TEMP (°C)	COND. (mS/cm)	DISS. O ₂ (mg/l)	TURB. (NTU)	ORP (mV)	FLOW RATE (ml/min.)	DEPTH TO WATER (btor)
Tolerance:	0.1		3%	10%	10%	+ or - 10		

Project:	1	1175616.00000		Site:	Pfohl B	Brothers	Well I.D.:	GW-3D
Date:	11/6/2012	Sampling F	Personnel:	Tim lfkovi	ch, Kevin Mo	cGovern	Company:	URS Corporation
Purging/ Sampling Device:		Geopump 2		Tubing Type:	LDPE/S	Silicone	Pump/Tubing Inlet Location:	Screen midpoint
Measuring Point:	Below Top of Riser	Initial Depth to Water:	2.08'	Depth to Well Bottom:	35.70'	Well Diameter:	4"	Screen Length:
Casing Type:	Stainles	s Steel		Volume in 1 Well Casing (liters):	83.0	-	Estimated Purge Volume (liters):	54.6
Sample ID:		GW-3D		Sample Time:	13	:10	QA/QC:	MS/MSD
•	e Parameters: er Information:	VOCs, SVOCs, a	nd TAL Meta	als				

PURGE PARAMETERS

TIME	рН	TEMP (°C)	COND. (mS/cm)	DISS. O ₂ (mg/l)	TURB. (NTU)	ORP (mV)	FLOW RATE (ml/min.)	DEPTH TO WATER (btor)
12:10	7.65	11.52	1.17	0.00	7.7	-25	910	2.08
12:15	7.50	11.97	1.16	0.00	7.4	-95	910	2.08
12:20	7.44	12.10	1.16	0.00	0.1	-96	910	2.08
12:25	7.42	12.19	1.16	0.00	0.0	-96	910	2.08
12:30	7.41	12.26	1.16	0.00	0.0	-97	910	2.08
12:35	7.41	12.33	1.15	0.00	0.0	-97	910	2.08
12:40	7.41	12.35	1.15	0.00	0.0	-98	910	2.08
12:45	7.41	12.35	1.15	0.00	0.0	-98	910	2.08
12:50	7.40	12.35	1.15	0.00	0.0	-99	910	2.08
12:55	7.40	12.36	1.15	0.00	0.0	-99	910	2.08
13:00	7.40	12.35	1.15	0.00	0.0	-100	910	2.08
13:05	7.41	12.32	1.15	0.00	0.0	-101	910	2.08
13:10	7.40	12.32	1.15	0.00	0.0	-101	910	2.08
Tolerance:	0.1		3%	10%	10%	+ or - 10		

Project:		11175616.00000		Site:	Pfohl B	Brothers	Well I.D.:	GW-4S
Date:	11/7/2012	Sampling	Personnel:	Tim Ifkov	vich, Kevin Mo	cGovern	Company:	URS Corporation
Purging/ Sampling Device:		Geopump 2		Tubing Type:	LDPE/S	Silicone	Pump/Tubing Inlet Location:	Screen midpoint
Measuring Point:	Below Top of Riser	Initial Depth to Water:	6.47'	Depth to Well Bottom:	16.23'	Well Diameter:	2"	Screen Length:
Casing Type:	Stainles	s Steel		Volume in 1 Well Casing (liters):	6.0		Estimated Purge Volume (liters):	15.1
Sample ID:		GW-4S		Sample Time:		VOCs/ Cs & Metals	QA/QC:	None
•	er Information:	VOCs, SVOCs, a Placed passive o Well historically of Metals after reco	liffusion bag goes dry at ve	(PDB) in well 9/ ery low purge ra				

PURGE PARAMETERS

TIME	рН	TEMP (°C)	COND. (mS/cm)	DISS. O ₂ (mg/l)	TURB. (NTU)	ORP (mV)	FLOW RATE (ml/min.)	DEPTH TO WATER (btor)
13:27	6.67	12.33	0.500	10.70	2.2	11	Intial	6.47
13:29	8.11	12.49	0.360	3.11	64.8	-87	2 Gal. Purged	-
13:34	8.17	12.16	0.340	3.56	>1000	-139	4.0 Gal. Purged	
Tolerance:	0.1		3%	10%	10%	+ or - 10		

Project:	1	1175616.00000		Site:	Pfohl E	Brothers	Well I.D.:	GW-4D
Date:	11/7/2012	Sampling	Personnel:	Tim Ifkovi	ch, Kevin M	cGovern	Company:	URS Corporation
Purging/ Sampling Device:		Geopump 2		_Tubing Type:	LDPE/	Silicone	Pump/Tubing Inlet Location:	Screen midpoint
Measuring Point:	Below Top of Riser	Initial Depth to Water:	13.64'	Depth to Well Bottom:	45.57'	Well Diameter:	4"	Screen Length:
Casing Type:	Stainles	s Steel		Volume in 1 Well Casing (liters):	78.9	-	Estimated Purge Volume (liters):	8.4
Sample ID:		GW-4D		Sample Time:	14	l:40	QA/QC:	None
•	e Parameters:	VOCs, SVOCs, a	and TAL Meta	als				

PURGE PARAMETERS

TIME	рН	TEMP (°C)	COND. (mS/cm)	DISS. O ₂ (mg/l)	TURB. (NTU)	ORP (mV)	FLOW RATE (ml/min.)	DEPTH TO WATER (btor)
13:50	7.85	10.41	1.02	1.02	0.8	-111	200	13.64
13:55	7.73	10.46	1.02	0.00	0.0	-133	165	13.77
14:00	7.69	10.44	1.04	0.00	0.0	-154	165	13.95
14:05	7.67	10.32	1.05	0.00	0.0	-163	165	14.06
14:10	7.66	10.27	1.05	0.00	0.0	-174	165	14.16
14:15	7.66	10.16	1.05	0.00	0.0	-178	165	14.25
14:20	7.66	10.01	1.05	0.00	0.0	-182	165	14.31
14:25	7.66	9.94	1.06	0.00	0.0	-188	165	14.41
14:30	7.66	9.87	1.06	0.00	0.0	-190	165	14.46
14:35	7.65	9.82	1.06	0.00	0.0	-193	165	14.51
14:40	7.65	9.77	1.07	0.00	0.0	-196	165	14.55
Tolerance:	0.1		3%	10%	10%	+ or - 10		

WELL PURGING LOG

URS Corporation

									poratic
SITE NAME:	Pfohl Bro	thers Lar	ndfill				WELL	NO.: <u> </u>	W-7S
PROJECT NO.:	11175616	6.00000							
STAFF:	Tim Ifkov	ich, Kevi	n McGov	rern					
DATE(S):	11/6/12, <i>*</i>	11/7/12							
1. TOTAL CASIN	G AND SCRE	EN LENG	TH (FT.)			=	35.04	WELL ID. 1"	VOL. (GAL/FT) 0.040
2. WATER LEVE	L BELOW TO	P OF CAS	ING (FT.)			=	4.55	2"	0.17
3. NUMBER OF F	EET STAND	ING WATE	ER (#1 - #2)		=	30.49	3"	0.38
4. VOLUME OF V	VATER/FOOT	OF CASI	NG (GAL.)			=	0.17	4"	0.66
5. VOLUME OF V	VATER IN CA	SING (GA	L.)(#3 x #4)		=	5.1	5"	1.04
6. VOLUME OF V	VATER TO RI	EMOVE (G	GAL.)(#5 x 3	3)		=		6"	1.50
7. VOLUME OF V	VATER ACTU	IALLY REM	MOVED (G	AL.)		=	7.5	8"	2.60
		Initial	2.0	4.0			VOLUME PURGE	V=0.0408 x (CASING D (GALLONS)	
PARAMETERS		Initial 6.49	2.0 6.78	4.0 7.64	6.0 7.92	7.5 8.00			
SPEC. COND. (mS	i/cm)	0.333	0.474	0.458	0.456	0.443			
DO (mg/l)		3.53	10.73	11.65	11.31	1.52			
TEMPERATURE (⁰	C)	9.40	11.21	11.39	11.26	11.11			
TURBIDITY (NTU)		8.4	23.8	46.4	80.2	276			
ORP (millivolts)		107	169	139	124	35			
TIME		10:06	10:09	10:14	10:21	10:28			
COMMENTS: 11/7/2012	9:25 - Fill \ 10:04 - Be 10:27 - We return to v 10:15 - Co	gin handb ell dry afte vell, depth	ailing wel r removin to water	l. g 7.5 gall = 4.74 fe	ons. et.	8), PDB w	as installed on 9	/21/12	

WELL PURGING LOG

URS Corporation

SITE NAME:	Pfohl Bro	thers Lar	ndfill					WELL NO	.:	GV	W-7D	
PROJECT NO.:	11175616	6.00000										
STAFF:	Tim lfkovi	ich, Kevii	n McGov	rern								
DATE(S):	11/6/12, 1	11/7/12										
1. TOTAL CASING	G AND SCRE	EN LENG	TH (FT.)			=	60	.45	WE	ELL ID. 1"	VOL. (GAL 0.0	,
2. WATER LEVEL	BELOW TO	P OF CAS	ING (FT.)			=	46	.42		2"	0.	17
3. NUMBER OF F	EET STANDI	ING WATE	R (#1 - #2)		=	14	.03		3"	0.3	38
4. VOLUME OF W	ATER/FOOT	OF CASI	NG (GAL.)			=	0.	66		4"	0.	66
5. VOLUME OF W	ATER IN CA	SING (GA	L.)(#3 x #4)		=	9	.3		5"	1.0	04
6. VOLUME OF W	ATER TO RI	EMOVE (G	AL.)(#5 x 3	3)		=				6"	1.	50
7. VOLUME OF W	ATER ACTU	IALLY REM	IOVED (G	AL.)		=	10	0.0		8"	2.	60
									V=0.0408 x	(CASING D	DIAMETER [INC	CHES]) ²
					ACCUM	IULATED	VOLUME I	PURGED (GALLONS))		
PARAMETERS		Init	2	4	6	8	10					
рН		8.10	7.99	7.98	8.02	7.10	8.08					

PARAMETERS		Init	2	4	0	0	10				
рН		8.10	7.99	7.98	8.02	7.10	8.08				
SPEC. COND. (mS/c	cm)	0.540	0.542	0.569	0.606	0.615	0.620				
DO (mg/l)		11.31	11.16	4.70	2.91	2.18	1.99				
TEMPERATURE (⁰ C)	10.61	11.22	11.32	11.40	11.24	11.08				
TURBIDITY (NTU)		15.0	4.5	10.6	11.6	20.9	25.7				
ORP (millivolts)		36	-59	-101	-130	-153	-165				
TIME		10:59	11:03	11:11	11:19	11:27	11:31				
	9:35 - Fill \ 10:45 - Be 11:31 - We return to w 10:25 - Co	gin handb ell dry afte ell, depth	ailing wel r removin to water :	l. g 10 gallo = 59.26 fe	ons eet.				ainer and 1	I-1 liter An	nber

Project:	1	11175616.00000		Site:	Pfohl E	Brothers	Well I.D.:	GW-8SR
Date:	11/6/2012	Sampling	Personnel:	Tim Ifkovi	ch, Kevin M	cGovern	_ Company:_	URS Corporation
Purging/ Sampling Device:		Geopump 2		Tubing Type:	LDPE/	Silicone	Pump/Tubing Inlet Location:	Screen midpoint
Measuring Point:	Below Top of Riser	Initial Depth to Water:	5.46'	Depth to Well Bottom:	13.02'	Well Diameter:	2"	Screen Length:
Casing Type:	Stainles	s Steel		Volume in 1 Well Casing (liters):	4.7	-	Estimated Purge Volume (liters):	8.5
Sample ID:		GW-8SR		Sample Time:	14	l:24	QA/QC:	None
•	e Parameters:	VOCs, SVOCs, a	and TAL Meta	als				

PURGE PARAMETERS

TIME	рН	TEMP (°C)	COND. (mS/cm)	DISS. O ₂ (mg/l)	TURB. (NTU)	ORP (mV)	FLOW RATE (ml/min.)	DEPTH TO WATER (btor)
13:44	7.11	12.78	3.09	0.00	108.0	-75	370	5.46
13:49	6.99	12.72	2.99	0.00	160.0	-72	275	7.15
13:54	6.98	12.77	2.99	0.00	125.0	-62	135	6.95
13:59	6.97	12.55	3.04	0.00	95.1	-66	185	7.10
14:04	6.96	12.47	3.05	0.00	80.7	-66	185	7.23
14:09	6.95	12.59	3.07	0.00	61.3	-66	185	7.30
14:14	6.93	12.50	3.09	0.00	42.9	-67	185	7.35
14:19	6.92	12.48	3.10	0.00	31.8	-69	185	7.40
14:24	6.91	12.47	3.11	0.00	23.3	-71	185	7.40
Tolerance:	0.1		3%	10%	10%	+ or - 10		

Project:	1	11175616.00000		Site:	Pfohl E	Brothers	Well I.D.:	GW-8D
Date:	11/6/2012	Sampling	Personnel:	Tim Ifkovi	ch, Kevin M	cGovern	_ Company:_	URS Corporation
Purging/ Sampling Device:		Geopump 2		Tubing Type:	LDPE/	Silicone	Pump/Tubing Inlet Location:	Screen midpoint
Measuring Point:	Below Top of Riser	Initial Depth to Water:	6.05'	Depth to Well Bottom:	36.54'	Well Diameter:	4''	Screen Length:
Casing Type:	Stainles	s Steel		Volume in 1 Well Casing (liters):	75.3	-	Estimated Purge Volume (liters):	44.5
Sample ID:		GW-8D		Sample Time:	15	5:39	QA/QC:	None
•	e Parameters: er Information:	VOCs, SVOCs, a	and TAL Meta	als				

PURGE PARAMETERS

TIME	рН	TEMP (°C)	COND. (mS/cm)	DISS. O ₂ (mg/l)	TURB. (NTU)	ORP (mV)	FLOW RATE (ml/min.)	DEPTH TO WATER (btor)
14:44	7.44	12.58	2.14	0.00	7.4	-64	500	6.05
14:49	7.25	12.08	2.53	0.00	0.0	-50	840	6.05
14:54	7.26	12.18	2.52	0.00	0.0	-70	840	6.05
14:59	7.41	12.22	1.34	0.00	0.0	-108	840	6.05
15:04	7.53	12.27	0.902	0.00	0.0	-51	840	6.05
15:09	7.54	12.25	0.895	0.00	0.0	-34	840	6.05
15:14	7.54	12.25	0.893	0.00	0.0	-26	840	6.05
15:19	7.54	12.23	0.894	0.00	0.0	-23	840	6.05
15:24	7.54	12.23	0.891	0.00	0.0	-15	840	6.05
15:29	7.53	12.20	0.891	0.00	0.0	-9	840	6.05
15:34	7.53	12.17	0.891	0.00	0.0	-2	840	6.05
15:39	7.53	12.15	0.889	0.00	0.0	2	840	6.05
Tolerance:	0.1		3%	10%	10%	+ or - 10		

Project:		11175616.00000		Site:	Pfohl E	Brothers	Well I.D.:	GW-26D
Date:	11/8/2012	Sampling	Personnel:	Tim Ifkovich, Kevin McGovern			_ Company:_	URS Corporation
Purging/ Sampling Device:		Geopump 2		Tubing Type:	LDPE/	Silicone	Pump/Tubing Inlet Location:	Screen midpoint
Measuring Point:	Below Top of Riser	Initial Depth to Water:	7.04'	Depth to Well Bottom:	40.70'	Well Diameter:	4"	Screen Length:
Casing Type:	Stainles	s Steel		Volume in 1 Well Casing (liters):	83.1	-	Estimated Purge Volume (liters):	28.1
Sample ID:		GW-26D		Sample Time:	12	:22	QA/QC:	None
•	er Information:	VOCs, SVOCs, a			in purge wa	ter.		

PURGE PARAMETERS

TIME	рН	TEMP (°C)	COND. (mS/cm)	DISS. O ₂ (mg/l)	TURB. (NTU)	ORP (mV)	FLOW RATE (ml/min.)	DEPTH TO WATER (btor)
11:47	8.07	12.31	1.92	4.27	0.0	-50	700	7.04
11:52	7.38	12.39	2.23	0.00	0.0	-73	820	7.04
11:57	7.35	12.32	2.24	0.00	0.0	-76	820	7.04
12:02	7.33	12.28	2.23	0.00	0.0	-77	820	7.04
12:07	7.32	12.29	2.24	0.00	0.0	-78	820	7.04
12:12	7.32	12.36	2.25	0.00	0.0	-79	820	7.04
12:17	7.29	12.46	2.24	0.00	0.0	-79	820	7.04
12:22	7.30	12.49	2.24	0.00	0.0	-79	820	7.04
		- -						
Tolerance:	0.1		3%	10%	10%	+ or - 10		

Project:	1	11175616.00000		Site:	Pfohl E	Brothers	Well I.D.:	GW-28S
Date:	5/16/2012	Sampling	Personnel:	Tim Ifkovich, Kevin McGovern		_ Company:_	URS Corporation	
Purging/ Sampling Device:		Geopump 2		Tubing Type:	LDPE/	Silicone	Pump/Tubing Inlet Location:	Screen midpoint
Measuring Point:	Below Top of Riser	Initial Depth to Water:	8.64'	Depth to Well Bottom:	15.52'	Well Diameter:	2"	Screen Length:
Casing Type:	Stainles	s Steel		Volume in 1 Well Casing (liters):	4.2	-	Estimated Purge Volume (liters):	6.4
Sample ID:		GW-28S		Sample Time:	9:	45	QA/QC:	None
•	e Parameters:	VOCs, SVOCs, a	Ind TAL Meta	als				

PURGE PARAMETERS

TIME	рН	TEMP (°C)	COND. (mS/cm)	DISS. O ₂ (mg/l)	TURB. (NTU)	ORP (mV)	FLOW RATE (ml/min.)	DEPTH TO WATER (btor)
9:10	7.98	9.84	0.486	0.00	26.1	100	150	8.64
9:15	7.60	11.66	0.466	0.00	21.2	99	200	9.55
9:20	7.53	12.36	0.450	0.00	16.0	97	200	9.85
9:25	7.51	12.29	0.453	0.00	7.2	92	180	9.85
9:30	7.50	12.42	0.460	0.00	2.0	87	180	9.88
9:35	7.50	12.51	0.462	0.00	0.4	81	180	9.91
9:40	7.50	12.59	0.465	0.00	0.0	75	180	9.96
9:45	7.49	12.63	0.467	0.00	0.0	72	180	9.99
Tolerance:	0.1		3%	10%	10%	+ or - 10		

Project:		1175616.00000		Site:	Pfohl E	Brothers	Well I.D.:	GW-29S
Date:	11/8/2012	Sampling F	Personnel:	Tim Ifkovich, Kevin McGovern		_ Company:_	URS Corporation	
Purging/ Sampling Device:		Geopump 2		_Tubing Type:	LDPE/:	Silicone	Pump/Tubing Inlet Location:	Screen midpoint
Measuring Point:	Below Top of Riser	Initial Depth to Water:	7.49'	Depth to Well Bottom:	20.04'	Well Diameter:	2"	Screen Length:
Casing Type:	Stainles	s Steel		Volume in 1 Well Casing (liters):	7.7		Estimated Purge Volume (liters):	8.5
Sample ID:		GW-29S		Sample Time:	8:	53	QA/QC:	None
•	r Information:	VOCs, SVOCs, a Orange iron partic						

PURGE PARAMETERS

TIME	рН	TEMP (°C)	COND. (mS/cm)	DISS. O ₂ (mg/l)	TURB. (NTU)	ORP (mV)	FLOW RATE (ml/min.)	DEPTH TO WATER (btor)
7:58	7.08	12.61	0.924	0.00	453	-83	190	7.49
8:03	7.22	12.38	0.917	0.00	319	-97	150	8.98
8:08	7.25	11.88	0.907	0.00	204	-100	150	9.10
8:13	7.25	11.60	0.894	0.00	220	-97	150	9.15
8:18	7.25	11.54	0.886	0.00	177	-92	150	9.23
8:23	7.26	11.61	0.890	0.00	147	-90	150	9.39
8:28	7.26	11.86	0.893	0.00	129	-89	150	9.49
8:33	7.26	11.99	0.894	0.00	126	-89	150	9.54
8:38	7.26	12.01	0.900	0.00	86.7	-88	150	9.65
8:43	7.26	11.92	0.908	0.00	48.3	-87	150	9.71
8:48	7.26	11.90	0.913	0.00	41.6	-86	150	9.77
8:53	7.26	11.83	0.913	0.00	40.8	-85	150	9.82
Tolerance:	0.1		3%	10%	10%	+ or - 10		

Project:	1	11175616.00000		Site:	Pfohl E	Brothers	Well I.D.:	GW-30S
Date:	11/8/2012	Sampling	Personnel:	Tim Ifkovich, Kevin McGovern		cGovern	_ Company:_	URS Corporation
Purging/ Sampling Device:		Geopump 2		Tubing Type:	LDPE/	Silicone	Pump/Tubing Inlet Location:	Screen midpoint
Measuring Point:	Below Top of Riser	Initial Depth to Water:	8.06'	Depth to Well Bottom:	17.97'	Well Diameter:	2"	Screen Length:
Casing Type:	Stainles	s Steel		Volume in 1 Well Casing (liters):	6.1	-	Estimated Purge Volume (liters):	21.3
Sample ID:		GW-30S		Sample Time:	9:	:38	QA/QC:	None
	e Parameters: er Information:	VOCs, SVOCs, a	and TAL Meta	als				

PURGE PARAMETERS

TIME	рН	TEMP (°C)	COND. (mS/cm)	DISS. O ₂ (mg/l)	TURB. (NTU)	ORP (mV)	FLOW RATE (ml/min.)	DEPTH TO WATER (btor)
9:13	7.46	11.59	3.79	0.00	82	-84	850	8.06
9:18	7.25	13.71	3.83	0.00	13.1	-115	850	8.15
9:23	7.23	13.87	3.85	0.00	1.9	-122	850	8.17
9:28	7.24	13.82	3.85	0.00	0.0	-125	850	8.17
9:33	7.23	13.93	3.85	0.00	0.0	-127	850	8.17
9:38	7.23	13.93	3.84	0.00	0.0	-127	850	8.17
Tolerance:	0.1		3%	10%	10%	+ or - 10		

Project:	1	1175616.00000		Site:	Pfohl E	Brothers	Well I.D.:	GW-31S
Date:	11/8/2012	Sampling I	Personnel:	Tim Ifkovi	ch, Kevin M	cGovern	_ Company:_	URS Corporation
Purging/ Sampling Device:		Geopump 2		Tubing Type:	LDPE/	Silicone	Pump/Tubing Inlet Location:	Screen midpoint
Measuring Point:	Below Top of Riser	Initial Depth to Water:	2.63'	Depth to Well Bottom:	9.57'	Well Diameter:	2"	Screen Length:
Casing Type:	Stainles	s Steel		Volume in 1 Well Casing (liters):	4.3	-	Estimated Purge Volume (liters):	3.5
Sample ID:		GW-31S		Sample Time:	10):23	QA/QC:	None
•	e Parameters: er Information:	VOCs, SVOCs, a	nd TAL Meta	als				

PURGE PARAMETERS

TIME	рН	TEMP (°C)	COND. (mS/cm)	DISS. O ₂ (mg/l)	TURB. (NTU)	ORP (mV)	FLOW RATE (ml/min.)	DEPTH TO WATER (btor)
9:53	7.83	11.84	0.676	0.00	8.9	-5	120	2.63
9:58	7.61	11.97	0.670	0.00	10.9	15	120	3.57
10:03	7.56	11.91	0.665	0.00	8.7	25	120	3.97
10:08	7.53	11.87	0.647	0.00	14.3	39	110	4.29
10:13	7.52	11.93	0.646	0.00	13.7	42	110	4.50
10:18	7.52	12.00	0.644	0.00	14.7	43	110	4.68
10:23	7.51	12.12	0.642	0.00	13.3	41	110	4.85
Tolerance:	0.1		3%	10%	10%	+ or - 10		

Project:		1175616.00000		Site:	Pfohl I	Brothers	Well I.D.:	GW-32S
Date:	11/8/2012	Sampling	Personnel:	Tim Ifkovi	ch, Kevin M	lcGovern	_ Company:_	URS Corporation
Purging/ Sampling Device:		Geopump 2		Tubing Type:	LDPE/	'Silicone	Pump/Tubing Inlet Location:	Screen midpoint
Measuring Point:	Below Top of Riser	Initial Depth to Water:	2.85'	Depth to Well Bottom:	9.93'	Well Diameter:	2"	Screen Length:
Casing Type:	Stainles	s Steel		Volume in 1 Well Casing (liters):	4.4	-	Estimated Purge Volume (liters):	6.1
Sample ID:		GW-32S		Sample Time:	11	:23	QA/QC:	None
•	e Parameters: er Information:	VOCs, SVOCs, a	and TAL Meta	als				

PURGE PARAMETERS

TIME	рН	TEMP (°C)	COND. (mS/cm)	DISS. O ₂ (mg/l)	TURB. (NTU)	ORP (mV)	FLOW RATE (ml/min.)	DEPTH TO WATER (btor)
10:53	8.15	12.80	0.453	0.99	16.2	42	250	2.85
10:58	7.86	12.35	0.462	0.00	13.2	63	195	3.33
11:03	7.82	12.40	0.459	0.00	10.8	64	195	3.34
11:08	7.79	12.34	0.457	0.00	4.3	62	195	3.35
11:13	7.78	12.37	0.457	0.00	1.6	61	195	3.36
11:18	7.77	12.41	0.456	0.00	0.6	60	195	3.35
11:23	7.76	12.48	0.454	0.00	0.9	58	195	3.35
Tolerance:	0.1		3%	10%	10%	+ or - 10		

Project:	1	1175616.00000		Site:	Pfohl I	Brothers	Well I.D.:	GW-33S
Date:	11/8/2012	Sampling	Personnel:	Tim Ifkovi	ch, Kevin N	lcGovern	_ Company:_	URS Corporation
Purging/ Sampling Device:		Geopump 2		Tubing Type:	LDPE/	/Silicone	Pump/Tubing Inlet Location:	Screen midpoint
Measuring Point:	Below Top of Riser	Initial Depth to Water:	4.35'	Depth to Well Bottom:	8.21'	Well Diameter:	2"	Screen Length:
Casing Type:	Stainles	s Steel		Volume in 1 Well Casing (liters):	2.4	_	Estimated Purge Volume (liters):	4.9
Sample ID:		GW-33S		Sample Time:	14	4:10	QA/QC:	None
•	e Parameters: er Information:	VOCs, SVOCs, a	and TAL Meta	als				

PURGE PARAMETERS

TIME	рН	TEMP (°C)	COND. (mS/cm)	DISS. O ₂ (mg/l)	TURB. (NTU)	ORP (mV)	FLOW RATE (ml/min.)	DEPTH TO WATER (btor)
13:35	7.73	13.08	1.12	4.89	6.5	104	140	4.35
13:40	7.48	12.88	1.14	3.64	4.7	124	140	5.41
13:45	7.42	12.75	1.16	3.45	3.0	130	140	5.81
13:50	7.41	12.13	1.18	3.46	2.7	131	140	6.11
13:55	7.39	12.18	1.18	3.28	3.6	133	140	6.30
14:00	7.37	12.11	1.20	3.29	0.0	135	140	6.38
14:05	7.35	12.26	1.20	3.29	0.0	137	140	6.45
14:10	7.32	12.30	1.20	3.27	0.0	140	140	6.55
Tolerance:	0.1		3%	10%	10%	+ or - 10		

Project:	1	1175616.00000		Site:	Pfohl E	Brothers	Well I.D.:	GW-34S
Date:	11/7/2012	Sampling	Personnel:	Tim lfkovi	ch, Kevin M	cGovern	_ Company:_	URS Corporation
Purging/ Sampling Device:		Geopump 2		Tubing Type:	LDPE/	Silicone	Pump/Tubing Inlet Location:	Screen midpoint
Measuring Point:	Below Top of Riser	Initial Depth to Water:	3.59'	Depth to Well Bottom:	10.01'	Well Diameter:	2"	Screen Length:
Casing Type:	Stainles	s Steel		Volume in 1 Well Casing (liters):	4.0	-	Estimated Purge Volume (liters):	3.9
Sample ID:		GW-34S		Sample Time:	8:	32	QA/QC:	None
•	e Parameters: er Information:	VOCs, SVOCs, a	and TAL Meta	als				

PURGE PARAMETERS

TIME	рН	TEMP (°C)	COND. (mS/cm)	DISS. O ₂ (mg/l)	TURB. (NTU)	ORP (mV)	FLOW RATE (ml/min.)	DEPTH TO WATER (btor)
8:02	8.09	13.32	0.520	4.99	53.9	77	140	3.59
8:07	7.68	11.68	0.553	4.50	30.4	90	140	4.30
8:12	7.63	11.07	0.564	4.55	27.4	96	140	4.61
8:17	7.61	10.74	0.565	4.10	26.2	99	120	4.70
8:22	7.59	10.33	0.573	3.93	25.0	101	120	4.78
8:27	7.57	9.91	0.582	3.80	21.8	103	120	4.81
8:32	7.56	9.64	0.586	3.71	19.7	105	120	4.84
Tolerance:	0.1		3%	10%	10%	+ or - 10		

Project:	1	1175616.00000		Site:	Pfohl I	Brothers	Well I.D.:	GW-35S
Date:	11/8/2012	Sampling F	Personnel:	Tim Ifkovi	ch, Kevin M	lcGovern	_ Company:_	URS Corporation
Purging/ Sampling Device:		Geopump 2		Tubing Type:	LDPE/	'Silicone	Pump/Tubing Inlet Location:	Screen midpoint
Measuring Point:	Below Top of Riser	Initial Depth to Water:	4.26'	Depth to Well Bottom:	7.46'	Well Diameter:	2"	Screen Length:
Casing Type:	Stainles	s Steel		Volume in 1 Well Casing (liters):	2.0	-	Estimated Purge Volume (liters):	8.3
Sample ID:		GW-35S		Sample Time:	13	3:12	QA/QC:	None
	e Parameters: er Information:	VOCs, SVOCs, a	nd TAL Meta	als				

PURGE PARAMETERS

TIME	рН	TEMP (°C)	COND. (mS/cm)	DISS. O ₂ (mg/l)	TURB. (NTU)	ORP (mV)	FLOW RATE (ml/min.)	DEPTH TO WATER (btor)
12:32	7.61	13.04	0.641	3.98	15.6	-5	250	4.26
12:37	7.46	12.70	0.617	1.39	6.3	54	200	4.58
12:42	7.43	12.51	0.610	0.82	0.8	77	200	4.58
12:47	7.41	12.54	0.605	0.58	0.0	88	200	4.61
12:52	7.39	12.52	0.602	0.28	0.0	95	200	4.61
12:57	7.38	12.51	0.599	0.15	0.0	101	200	4.61
13:02	7.37	12.52	0.595	0.00	0.0	105	200	4.61
13:07	7.38	12.46	0.593	0.00	0.0	108	200	4.61
13:12	7.38	12.36	0.591	0.00	0.0	110	200	4.61
Tolerance:	0.1		3%	10%	10%	+ or - 10		

 Project Name:
 Pfohl Brothers
 Project Number:
 11175616.00000

 Sampling Crew Members:
 T. Ifkovich, K. McGovern
 Supervisor:
 J. Sundquist

Date of Sampling:

November 6, 2012

Sample I.D. Number	Well Number	Well Volume (liters)	Volume Purged (liters)	Sample Time	Sample Description	Analysis Required	Chain-of- Custody Number
GW-7S	GW-7S	19.3	PDB	9:25	Groundwater	VOCs	Not Applicable
GW-7D	GW-7D	35.2	PDB	9:35	Groundwater		Not Applicable
GW-3D	GW-3D	83.0	54.6	13:10	Groundwater	VOCs/SVOCs/ Metals	Not Applicable
GW-3D-MS	GW-3D	83.0	54.6	13:10	Matrix Spike		Not Applicable
GW-3D-MSD	GW-3D	83.0	54.6	13:10	Matrix Spike Duplicate		Not Applicable
GW-8SR	GW-8SR	4.7	8.5	14:24	Groundwater		Not Applicable
GW-8D	GW-8D	75.3	44.5	15:39	Groundwater		Not Applicable

Additional Comments:

GW-7D and GW-7S were sampled for VOCs using passive diffusion bags (PDBs).

GW-7D and GW-7S were then purged dry, remaining parameters collected November 7, 2012.

All other wells were purged using low flow methods until parameter stabilization.

Proj	ect Name:			Pfohl Brothers		Project Number:	11175616.00000	
Sam	pling Crew Mem	bers:		<u>T. Ifkovich, K. McG</u>	<u>iovern</u>	Supervisor:	<u>J. Sundquist</u>	
Date	e of Sampling:			<u>November 6, 2012</u>				
	Sample I.D.	Well	Well	Volume Purged		Sample	Analysis	Chain-of-

Sample I.D. Number	Well Number	Volume (liters)	Volume Purged (liters)	Sample Time	Sample Description	Analysis Required	Custody Number
TB-110612					Trip Blank	VOCs	Not Applicable

Additional Comments:

All wells were purged using low flow methods until parameter stabilization.

Project Name:	Pfohl Brothers	Project Number:	11175616.00000
Sampling Crew Members:	<u>T. Ifkovich, K. McGovern</u>	Supervisor:	<u>J. Sundquist</u>
Date of Sampling:	November 7, 2012		

<u>November 7, 2012</u>

Sample I.D. Number	Well Number	Well Volume (liters)	Volume Purged (liters)	Sample Time	Sample Description	Analysis Required	Chain-of- Custody Number
GW-34S	GW-34S	4.0	3.9	8:32	Groundwater	VOCs/SVOCs/ Metals	Not Applicable
GW-28S	GW-28S	4.2	6.4	9:45	Groundwater		Not Applicable
GW-7S	GW-7S	19.3	28.4	10:15	Groundwater	SVOCs/ Metals	Not Applicable
GW-7D	GW-7D	35.2	37.9	10:25	Groundwater		Not Applicable
GW-1D	GW-1D	90.6	49.7	11:47	Groundwater	VOCs/SVOCs/ Metals	Not Applicable
FD-110712	GW-1D	90.6	49.7	11:47	Duplicate		Not Applicable
GW-1S	GW-1S	7.1	9.0	12:47	Groundwater		Not Applicable

Additional Comments:

GW-7D and GW-7S were sampled for SVOCs and Metals after recharging overnight.

All other wells were purged using low flow methods until parameter stabilization.

Project Name:	Pfohl Brothers	Project Number:	11175616.00000
Sampling Crew Members:	T. Ifkovich, K. McGovern	Supervisor:	<u>J. Sundquist</u>

Date of Sampling:

<u>November 7, 2012</u>

Sample I.D. Number	Well Number	Well Volume (liters)	Volume Purged (liters)	Sample Time	Sample Description	Analysis Required	Chain-of- Custody Number
GW-4S	GW-4S	6.0	15.1	13:25 & 15:00	Groundwater	VOCs/SVOCs/ Metals	Not Applicable
GW-4D	GW-4D	78.9	8.4	14:40	Groundwater		Not Applicable
TB-110712					Trip Blank	VOCs	Not Applicable

Additional Comments:

GW-4S was sampled for VOCs using a passive diffusion bag and then purged dry/allowed to recharge for collection of other parameters. All other wells were purged using low flow methods until parameter stabilization.

GROUNDWATER SAMPLING - SAMPLE COLLECTION DATA SHEET

Project Name:	Pfohl Brothers	Project Number:	11175616.00000
Sampling Crew Members:	<u>T. Ifkovich, K. McGovern</u>	Supervisor:	<u>J. Sundquist</u>
Date of Sampling:	<u>November 8, 2012</u>		

Sample I.D. Number	Well Number	Well Volume (liters)	Volume Purged (liters)	Sample Time	Sample Description	Analysis Required	Chain-of- Custody Number
GW-29S	GW-29S	7.7	8.5	8:53	Groundwater	VOCs/SVOCs/ Metals	Not Applicable
GW-30S	GW-30S	6.1	21.3	9:38	Groundwater		Not Applicable
GW-31S	GW-31S	4.3	3.5	10:23	Groundwater		Not Applicable
GW-32S	GW-32S	4.4	6.1	11:23	Groundwater		Not Applicable
GW-26D	GW-26D	83.1	28.1	12:22	Groundwater		Not Applicable
GW-35S	GW-35S	2.0	8.3	13:12	Groundwater		Not Applicable
GW-33S	GW-33S	2.4	4.9	14:10	Groundwater		Not Applicable

Additional Comments:

All wells were purged using low flow methods until parameter stabilization.

In addition, trip blank TB-110812 was submitted for analysis of VOCs.

APPENDIX E

GROUNDWATER TREND ANALYSIS

 $\label{eq:constraint} $$ 02123k5515 ONEWORLDJOBS 11172700.0000 WORD DRAFT semi Annual Report Jul-Dec12 Semi Annual Semi Annual Report Jul-Dec12 Semi Annual Semi Annu$

FIGURE E-1 TRENDS OF PARAMETERS ROUTINELY EXCEEDING GROUNDWATER STANDARDS IN MONITORING WELL GW-1D




FIGURE E-2 TRENDS OF PARAMETERS ROUTINELY EXCEEDING GROUNDWATER STANDARDS IN MONITORING WELL GW-1S




FIGURE E-3 TRENDS OF PARAMETERS ROUTINELY EXCEEDING GROUNDWATER STANDARDS IN MONITORING WELL GW-3D




FIGURE E-4 TRENDS OF PARAMETERS ROUTINELY EXCEEDING GROUNDWATER STANDARDS IN MONITORING WELL GW-3S




FIGURE E-5 TRENDS OF PARAMETERS ROUTINELY EXCEEDING GROUNDWATER STANDARDS IN MONITORING WELL GW-4D




FIGURE E-6 TRENDS OF PARAMETERS ROUTINELY EXCEEDING GROUNDWATER STANDARDS IN MONITORING WELL GW-4S




FIGURE E-7 TRENDS OF PARAMETERS ROUTINELY EXCEEDING GROUNDWATER STANDARDS IN MONITORING WELL GW-7D




FIGURE E-8 TRENDS OF PARAMETERS ROUTINELY EXCEEDING GROUNDWATER STANDARDS IN MONITORING WELL GW-7S




FIGURE E-9 TRENDS OF PARAMETERS ROUTINELY EXCEEDING GROUNDWATER STANDARDS IN MONITORING WELL GW-8D




FIGURE E-10 TRENDS OF PARAMETERS ROUTINELY EXCEEDING GROUNDWATER STANDARDS IN MONITORING WELL GW-8SR




FIGURE E-11 TRENDS OF PARAMETERS ROUTINELY EXCEEDING GROUNDWATER STANDARDS IN MONITORING WELL GW-26D




FIGURE E-12 TRENDS OF PARAMETERS ROUTINELY EXCEEDING GROUNDWATER STANDARDS IN MONITORING WELL GW-28S




FIGURE E-13 TRENDS OF PARAMETERS ROUTINELY EXCEEDING GROUNDWATER STANDARDS IN MONITORING WELL GW-29S




FIGURE E-14 TRENDS OF PARAMETERS ROUTINELY EXCEEDING GROUNDWATER STANDARDS IN MONITORING WELL GW-30S




FIGURE E-15 TRENDS OF PARAMETERS ROUTINELY EXCEEDING GROUNDWATER STANDARDS IN MONITORING WELL GW-31S




FIGURE E-16 TRENDS OF PARAMETERS ROUTINELY EXCEEDING GROUNDWATER STANDARDS IN MONITORING WELL GW-32S




FIGURE E-17 TRENDS OF PARAMETERS ROUTINELY EXCEEDING GROUNDWATER STANDARDS IN MONITORING WELL GW-33S




FIGURE E-18 TRENDS OF PARAMETERS ROUTINELY EXCEEDING GROUNDWATER STANDARDS IN MONITORING WELL GW-34S





FIGURE E-19 TRENDS OF PARAMETERS ROUTINELY EXCEEDING GROUNDWATER STANDARDS IN MONITORING WELL GW-35S



APPENDIX F

BSA PERMIT NO. 10-11-CH016

AUTHORIZATION TO DISCHARGE UNDER THE BUFFALO POLLUTANT DISCHARGE ELIMINATION SYSTEM

PERMIT NO. 10-11-CH016 USEPA Category 40 CFR Part 403

In accordance with the provisions of the Federal Water Pollution Control Act, as amended, and the Sewer Regulations of the Buffalo Sewer Authority, authorization is hereby granted to:

THE TOWN OF CHEEKTOWAGA

to discharge wastewater from a facility located at:

PFOHL BROTHERS LANDFILL REMEDIATION SITE 1000 AERO DRIVE

CHEEKTOWAGA, NEW YORK 14225

The wastewater permitted herein shall be discharged to the Town of Cheektowaga sewer system, which is connected to the Buffalo Municipal Sewer System and Treatment facilities, and which wastewater will be treated at the Buffalo Sewer Authority's Treatment Plant.

Issuance of this permit is based upon a permit application filed on **November 3, 2005** analytical data. This permit is granted in accordance with discharge limitations, monitoring requirements and other conditions set forth in Parts I and II hereof.

Effective this 1st day of November, 2010

To Expire the 31st day of March, 2013

General Manager

Signed this 30th day of Leptember, 2010

PAGE 1 OF 6

Permit No. 10-11-CH016 Part I^{*} Page 2 of 6

PART I: SPECIFIC CONDITIONS

A. DISCHARGE LIMITATIONS & MONITORING REQUIREMENTS

During the period beginning the effective date of this Permit and lasting until the expiration date, discharge from the permitted facility outfall (see attached map) shall be limited and monitored **quarterly** by the permittee as specified below.

Gample		Discharge Limitations ⁽¹⁾	Samp	ling Requirements
Sample Point	Parameter	Daily Max	Period	Туре
001	pH Total Cadmium Total Chromium Total Copper	5.0 – 12.0 S.U. 1.17 lbs. 1.17 lbs. 3.74 lbs.	1 day 1 day 1 day 1 day	Composite ² Composite ² Composite ² Composite ²
	Total Lead Total Nickel Total Zinc Total Barium Total Suspended Solids ⁵	1.17 lbs. 3.27 lbs. 5.84 lbs. 2.34 lbs. 250 mg/l	1 day 1 day 1 day 1 day 1 day	Composite ² Composite ² Composite ² Composite ² Composite ²
	Total Flow	140,100 gallons ⁶	1 day	Discharge meter reading

Footnotes are explained on page 5.

Permit No. 10-11-CH016 Part I Page 3 of 6

PART I: SPECIFIC CONDITIONS

A. DISCHARGE LIMITATIONS & MONITORING REQUIREMENTS

During the period beginning the effective date of this Permit and lasting until the expiration date, discharge from the permitted facility outfall (see attached map) shall be limited and monitored **once** by the permittee as specified below.

Sample		Discharge Limitations ⁽¹⁾	Sampling	Requirements
Point	Parameter	Daily Max	Period	Type
001	Total Mercury	0.001 lbs.	1 day	Composite ²
	USEPA Test		1 1	Grab ³
	Method 608 ⁴	To be monitored	1 day	Grao
	USEPA Test		1 1	Grab ³
	Method 624 ⁴	To be monitored	1 day	Grad
	USEPA Test		1 1	Grab ³
	Method 625 ⁴	To be monitored	1 day	Grad

Footnotes are explained on page 5.

PART I: SPECIFIC CONDITIONS

B. DISCHARGE MONITORING REPORTING REQUIREMENTS

During the period beginning the effective date of this permit and lasting until the expiration date, discharge monitoring results shall be summarized and reported **quarterly** by the permittee on the days specified below:


Sample Point 001	Parameter All except USEPA Test Methods 608, 624, 625 & T Mercury	Reporting Initial Report March 31, 2011	Requirements Subsequent Reports Every March 31 st , June 30 th , September 30 th and December 31 st
	USEPA Test Methods 608, 624 and 625 & T Mercury	March 31, 2011	

Permit No. 10-11-CH016 Part I Page 5 of 6

PART I: SPECIFIC CONDITIONS

C. SPECIAL REQUIREMENTS

- 1. Mass limits based on an average discharge of 140,100 gpd.
- 2. Composite samples may be time proportioned.
- 3. Four grab samples must be collected at equally spaced intervals throughout the sample day. The four (4) grab samples must be composited by a NYSDOH certified laboratory prior to analysis.
- 4. The permittee must report any compound whose concentration is equal to or greater than 0.01 mg/L. The permittee is not authorized to discharge any of the parameters evaluated by these test procedures which may cause or contribute to a violation of water quality standards or harm the sewerage system. Any parameter detected may, at the discretion of the BSA, be specifically limited and incorporated in this permit.
- 5. Surchargeable over 250 mg/L.
- 6. Flow is an action level only. If the permittee consistently exceeds this level, the BSA must be notified so that this permit can be modified.



TOWN OF CHEEKTOWAGA/BUFFALO POLLUTANT DISCHARGE ELIMINATION SYSTEM PERMIT

PART II GENERAL CONDITIONS

A. MONITORING AND REPORTING

1. Local Limits

Except as otherwise specified in this permit, the permit holder shall comply with all specific prohibitions, limits on pollutants or pollutant parameters set forth in the Buffalo Sewer Authority Sewer Use Regulations, as amended from time to time, and such prohibitions, limits and parameters shall be deemed pretreatment standards for purposes of the Clean Water Act

2. Definitions

Definitions of terms contained in this permit are as defined in the Town of Cheektowaga Local Law No. 2 and the Buffalo Sewer Authority Sewer Use Regulations.

3. Discharge Sampling Analysis

All Wastewater discharge samples and analyses and flow measurements shall be representative of the volume and character of the monitored discharge. Methods employed for flow measurements and sample collections and analyses shall conform to the Buffalo Sewer Authority "Sampling Measurement and Analytical Guidelines Sheet."

4. Recording of Results

For each measurement or sample taken pursuant to the requirements of the permit, the Permittee shall record the information as required in the "Sampling Measurement and Analytical Guidelines Sheet."

5. Additional Monitoring by Permittee

If the Permittee monitors any pollutants at the location(s) designated herein more frequently than required by this permit, using approved analytical methods as specified in 40 CFR Part 136 the results of such monitoring shall be included in the calculation and reporting of values required under Part I, B. Such increased frequency shall also be indicated.

6. Reporting

All reports prepared in accordance with this Permit shall be submitted to:

Mr. William Pugh, P.E. Town Engineer 275 Alexander Ave. Cheektowaga, New York, 14211

All self-monitoring reports shall be prepared in accordance with the BSA "Sampling Measurement and Analytical Guidelines Sheet." These reporting requirements shall not relieve the Permittee of any other reports, which may be required by the

N.Y.S.D.E.C. or the U.S.E.P.A.

B. PERMITTEE REQUIREMENTS

1. Change in Discharge

All discharges authorized herein shall be consistent with the terms and conditions of this permit and with the information contained in the TC/BPDES Permit Application on which basis this permit is granted. In the event of any facility expansions, production increases, process modifications or the installation, modification or repair of any pretreatment equipment which may result in new, different or increased discharges of pollutants, a new TC/BPDES Permit Application must be submitted prior to any change. Following receipt of an amended application, the BSA may modify this permit to specify and limit any pollutants not previously limited. In the event that the proposed change will be covered under an applicable Categorical Standard, a Baseline Monitoring Report must be submitted at least ninety (90) days prior to any discharge.

2. Records Retention

All records and information resulting from the monitoring activities required by this permit including all records of analyses performed, calibration and maintenance of instrumentation, and recordings from continuous monitoring instrumentation shall be retained at this facility for a minimum of three (3) years, or longer if requested by the General Manager and/or Town Engineer.

3. Notification of Slug, Accidental Discharge or Spill

In the event that a slug, accidental discharge or any spill occurs at the facility for which this permit is issued, it is the responsibility of the Permittee to immediately notify the B.S.A. Treatment Plant at 883-1820 of the quantity and character of such discharge. If requested by the B.S.A., within five (5) days following all such discharges, the Permittee shall submit a report describing the character and duration of the discharge, the cause of the discharge, and measures taken or that will be taken to prevent a recurrence of such discharge.

4. Noncompliance Notification

If, for any reason, the Permittee does not comply with or will be unable to comply with any discharge limitation specified in this permit, the Permittee or their assigns must verbally notify the Industrial Waste Section at 883-1820 within twenty-four (24) hours of becoming aware of the violation. The Permittee shall provide the Industrial Waste Section with the following information, in writing, within five (5) days of becoming aware of such condition:

- a. a description of the discharge and cause of noncompliance and;
- b. the period of noncompliance, including exact dates and times; or, if not corrected, the anticipated time the noncompliance is expected to continue, and steps being taken to reduce, eliminate and prevent recurrence of the noncomplying discharge.

5. Adverse Impact

The Permittee shall take all reasonable steps to minimize any adverse impact to the Buffalo and Town Sewerage System resulting from noncompliance with any discharge limitations specified in this permit, including such accelerated or additional monitoring as necessary to determine the nature and impact of the noncomplying discharge.

6. Waste Residuals

Solids, sludges, filter backwash or other pollutants removed in the course of treatment or control of wastewaters and/or the treatment of intake waters, shall be disposed of in a manner such as to prevent any pollutant from such materials from entering the Buffalo or Town Sewer System.

7. Power Failures

In order to maintain compliance with the discharge limitations and prohibitions of this permit, the Permittee shall provide an alternative power source sufficient to operate the wastewater control facilities; or, if such alternative power source is not provided the Permittee shall halt, reduce or otherwise control production and/or controlled discharges upon the loss of power to the wastewater control facilities.

8. Treatment Upsets

- a. Any industrial user which experiences an upset in operations that places it in a temporary state of noncompliance, which is not the result of operational error, improperly designed treatment facilities, inadequate treatment facilities, lack of preventive maintenance, or careless or improper operation, shall inform the Industrial Waste Section immediately upon becoming aware of the upset. Where such information is given verbally, a written report shall be filed by the user within five (5) days. The report shall contain:
 - (i) A description of the upset, its cause(s) and impact on the discharger's compliance status.
 - (ii) The duration of noncompliance, including exact dates and times of noncompliance, and if the noncompliance is continuing, the time by which compliance is reasonably expected to be restored
 - (iii) All steps taken or planned to reduce, eliminate, and prevent recurrence of such an upset.
- b. An industrial user which complies with the notification provisions of this Section in a timely manner shall have an affirmative defense to any enforcement action brought by the Industrial Waste Section/Town Engineer for any noncompliance of the limits in this permit, which arises out of violations attributable to and alleged to have occurred during the period of the documented and verified upset.

9. Treatment Bypasses

- a. A bypass of the treatment system is prohibited unless the following conditions are met:
 - (i) The bypass was unavoidable to prevent loss of life, personal injury, or severe property damage; or
 - (ii) There was no feasible alternative to the bypass, including the use of auxiliary treatment or retention of the wastewater; and
 - (iii) The industrial user properly notified the Industrial Waste Section as described in paragraph b. below.
- b. Industrial users must provide immediate notice to the Industrial Waste Section upon delivery of an unanticipated bypass. If necessary, the Industrial Waste Section may require the industrial user to submit a written report explaining the cause(s), nature, and duration of the bypass, and the steps being taken to prevent its recurrence.
- c. An industrial user may allow a bypass to occur which does not cause pretreatment standards or requirements to be violated, but only if it is for essential maintenance to ensure efficient operation of the treatment system. Industrial users anticipating a bypass must submit notice to the Industrial Waste Section at least ten (10) days in advance. The Industrial Waste Section may only approve the anticipated bypass if the circumstances satisfy those set forth in paragraph a. above.

C. PERMITTEE RESPONSIBILITIES

1. Permit Availability

The originally signed permit must be available upon request at all times for review at the address stated on the first page of this permit.

2. Inspections

The Permittee shall allow the representatives of the Buffalo Sewer Authority or Town of Cheektowaga upon the presentation of credentials and during normal working hours or at any other reasonable times, to have access to and copy any records required in this permit; and to sample any discharge of pollutants.

3. Transfer of Ownership or Control

In the event of any change in control or ownership of facilities for which this permit has been issued the permit shall become null and void. The succeeding owner shall submit a completed Town of Cheektowaga/ Buffalo Sewer Authority permit application prior to discharge to the sewer system.

D. PERMITTEE LIABILITIES

1. Permit Modification

After notice and opportunity for a hearing, this permit may be modified, suspended, or revoked in whole or in part during its term for cause including, but not limited to the following:

- a. Violation of any terms or conditions of this permit,
- b. Obtaining this permit by misrepresentation or failure to disclose fully all relevant facts,
- c. A change in any condition that requires either a temporary or permanent reduction or elimination of the authorized discharge.

2. Imminent Danger

In the event there exists an imminent danger to health or property, the permitter reserves the right to take immediate action to halt the permitted discharge to the sewerage works.

3. Civil and Criminal Liability

Nothing in this permit shall relieve the Permittee from any requirements, liabilities, or penalties under provisions of the Town of Cheektowaga Local Law No. 2, the "Sewer Regulations of the Buffalo Sewer Authority" or any Federal, State and/or local laws or regulations.

4. Penalties for Violations of Permit Conditions

The "Sewer Regulations of the Buffalo Sewer Authority" and Town of Cheektowaga Local Law No. 2, provide that any person who violates a B.P.D.E.S. permit condition is liable to the Authority and/or the Town for a civil penalty of up to \$10,000 per day for each violation. Any person who willfully or negligently violates permit conditions will be referred to the New York State Attorney General.

E. NATIONAL PRETREATMENT STANDARDS

If a pretreatment standard or prohibition (including any Schedule of Compliance specified in such pretreatment standard or prohibition) is established under Section 307 (b) of the Act for a pollutant which is present in the discharge and such standard or prohibition is more stringent than any limitation for such pollutant in this permit, this permit shall be revised or modified in accordance with such pretreatment standard or prohibition.

F. PLANT CLOSURE

In the event of plant closure, the Permittee is required to notify the Industrial Waste Section/Town Engineer in writing as soon as an anticipated closure date is determined, but in no case later than five (5) days of the actual closure.

G. CONFIDENTIALITY

Except for data determined to be confidential under Section 308 of the Act, all reports prepared in accordance with the terms of this permit shall be available for public inspection at the offices of the Buffalo Sewer Authority or Town Engineer of the Town of Cheektowaga. As required by the Act, effluent data shall not be considered confidential. Knowingly making any false statement on any such report may result in the imposition of criminal penalties as provided for in Section 309 of the Act.

H. SEVERABILITY

The provisions of this permit are severable, and if any provision of this permit, or the application of any provision of this permit to any circumstance, is held invalid, the application of such provision to other circumstances, and the remainder of this permit, shall not be affected thereby.

APPENDIX G

DISCHARGE REPORT SUMMARY TABLES

 $\label{eq:constraint} $$ 02123k5515 ONEWORLDJOBS 11172700.0000 WORD DRAFT semi Annual Report Jul-Dec12 Semi Annual Semi Annual Report Jul-Dec12 Semi Annual Semi Annu$

SAMPLING FIELD SHEET



Client Name:	Pfohl Brothers Landfil				
Address:	Aero Drive, Cheektow	aga, NY			
Contact:	Bill Pugh, P.E.	F	Phone:	716-897-7288	
Installation:					
Sample Point:	SP-001				
Sample Location	: Meter Chamb	er - ball valve on 6	6" HDPE	forcemain	
Date:	9/20/12 Crew:	R. Murphy, T. If	fkovich,	S. Conway	
Weather:	65° F, Clear				
Sampling Device	: NA				
Time of Installation		Type of Sa	ample:	Composite	
		_		·	
Sample Interval:		_ Sample Vo	olume:	NA	
Comments and C				e of sample setup.	
		• /		<u>332 gals), WW-03 (18</u> ,586 gals) & MH-25 (1	
Date:	9/21/12 Crew:	R. Murphy, T. If	fkovich,	S. Conway	
M/oothow					
Weather:	66° F, Cloudy				
Time of Collectio	n: <u>11:15</u>	_			
Field Measureme	ents:				
12:55	5/RJM	pH Calibration: E	Buffer 7-	7 Buffer 4- 4	Buffer 10- 10
(time/	(initial)		-		
		pH Measurement:		7.1	
		Temperature:		20.7°C	
ldontifications.		_			
Identification:	EFF-092112				

_aboratory: <u>TestAmerica, Buffalo, NY</u>	
Comments: No wells were running at the time of sample of	collection.
PLC display volumes: WW-01 (304,971 gals), WW-02 (
WW-04 (18,122 gals), WW-05 (616,813 gals), WW-06 (2	210,586 gals) & MH-25 (1,348,170 gals).
Reviewed By:	Date:

N:\11172700.00000\Excel\Data and Calcs\Field Sampling Form (9-21-12)

TABLE 1

PFOHL BROTHERS LANDFILL - EFFLUENT MONITORING ANALYTICAL RESULTS, TOTAL FLOW, AND MASS LOADINGS SEPTEMBER 2012

Sample ID	EFF-092112						
Matrix	Effluent Water						
Date Sampled		ç	9/21/2012				
Parameter	Result	Mass Loading	Discharge Limitation	Violations			
	(mg/L)	(lbs/day)	(lbs/day)	(Y/N)			
Total Barium	0.45	0.004	2.34	No			
Total Cadmuim	ND ⁽¹⁾	NA ⁽²⁾	1.17	No			
Total Chromium	0.0014	0.00001	1.17	No			
Total Copper	0.0089	0.0001	3.74	No			
Total Lead	ND	NA	1.17	No			
Total Nickel	0.011	0.0001	3.27	No			
Total Zinc	0.032	0.0003	5.84	No			
Total Suspended Solids	55.2	NA	250 ⁽³⁾	No			
рН ⁽⁴⁾	7.07	NA	5.0 - 12.0	No			
Total Flow ⁽⁵⁾		973	140,000	No			

Notes:

(1) ND = Not Detected

(2) NA = Not Applicable

(3) Discharge Limitation in units of mg/L

- (4) pH measurement and Discharge Limitation in Standard Units
- (5) Total Flow reported in gallons, sample was collected over a 24 hour period

Calculation:
$$\left(\frac{x \text{ mg}}{L}\right)\left(\frac{y \text{ gal}}{\text{day}}\right)\left(\frac{1 \text{ lb}}{453,600 \text{ mg}}\right)\left(\frac{3.785 \text{ L}}{\text{gal}}\right) = \frac{x \times y}{119,841} \frac{\text{lb}}{\text{day}}$$

SAMPLING FIELD SHEET



Client Name: Pf	ohl Brothers Landfill						
Address: Ae	ero Drive, Cheektowa	iga, NY					
Contact: Bi	ll Pugh, P.E.	Pł	hone:	716-897-7288	8		
Installation:							
Sample Point: SF	P-001						
Sample Location:	Meter Chambe	r - ball valve on 6"	' HDPE	forcemain			
Date:	12/27/12 Crew:	R. Murphy, T. Ifk	kovich,	K. McGovern			
Weather: <u>30</u>	^o F, Snow						
Sampling Device:	NA						
Time of Installation	12:05	Type of Sa	mple:	Composite			
Sample Interval:	NA	Sample Vol	lume:	NA			
Comments and Ob	servations: <u>No well</u>	s were running at	the time	e of sample se	etup.		
	lumes: WW-01 (557 17 gals), WW-05 (1,7						
	<u></u>		1 00 (2)	1000,000 gale)			
Date:	9/28/12 Crew:	R. Murphy, T. Ifk	kovich,	K. McGovern			
Weather: 29	[°] F, Cloudy						
Time of Collection:	12:15						
Field Measurement	s:						
12:15/R		pH Calibration: Bu	uffer 7	7 Buffer 4	- 4	_Buffer 10-	10
(time/init	,	pH Measurement:	8	3.8			
		Temperature:	8	3.9°C			
Identification: EF	FF-122812					_	

TestAmerica, Buffalo, NY	
No wells were running at the time of sample collectior	۱.
9,517 gals), WW-05 (1,797,370 gals), WW-06 (2,589	,530 gals) & MH-25 (5,587,023 gals).
	Date:
ľ	No wells were running at the time of sample collection volumes: WW-01 (557,819 gals), WW-02 (12,826 g

N:\11172700.00000\Excel\Data and Calcs\Field Sampling Form (12-28-12)

TABLE 1

PFOHL BROTHERS LANDFILL - EFFLUENT MONITORING ANALYTICAL RESULTS, TOTAL FLOW, AND MASS LOADINGS DECEMBER 2012

Sample ID	EFF-122812							
Matrix		luent Water						
Date Sampled		12/28/2012						
Parameter	Result	Mass Loading	Discharge Limitation	Violations				
	(mg/L)	(lbs/day)	(lbs/day)	(Y/N)				
Total Barium	0.22	0.002	2.34	No				
Total Cadmuim	< ⁽¹⁾ 0.0005	< 0.000004	1.17	No				
Total Chromium	0.0011	0.00001	1.17	No				
Total Copper	0.024	0.0002	3.74	No				
Total Lead	< 0.003	< 0.00003	1.17	No				
Total Nickel	0.0052	0.00004	3.27	No				
Total Zinc	0.14	0.0012	5.84	No				
Total Suspended Solids	9.6	NA	250 ⁽³⁾	No				
рН ⁽⁴⁾	8.79	NA	5.0 - 12.0	No				
Total Flow ⁽⁵⁾		1,005	140,100	No				

Notes:

- (1) < = Compound not detected, method detection limit shown
- (2) NA = Not Applicable
- (3) Discharge Limitation in units of mg/L
- (4) pH measurement and Discharge Limitation in Standard Units
- (5) Total Flow reported in gallons, sample was collected over a 24 hour period

Calculation:
$$\left(\frac{x \text{ mg}}{L}\right)\left(\frac{y \text{ gal}}{\text{day}}\right)\left(\frac{1 \text{ lb}}{453,600 \text{ mg}}\right)\left(\frac{3.785 \text{ L}}{\text{gal}}\right) = \frac{x \times y}{119,841} \frac{\text{lb}}{\text{day}}$$

APPENDIX H

MONITORING WELL INSPECTION LOGS

WELL INSPECTION SUMMARY Project Name: Pfohl Brothers Landfill Project Number: *11175616.00000* Inspection Crew Members: T. Ifkovich, K. McGovern Supervisor: <u>J. Sundquist</u> Date(s) of Inspection: November 6, 2012 Surface Protective Water Level Well Depth Other Well I.D. Number Lock Riser (ft. BTOC) (ft. BTOC) Seal Casing **Comments** OK OK GW-1S OK Bulged 3.38 14.94 GW-1D OK OK OK Bulged 2.81 39.65 GW-3S OK OK OK OK DRY 13.22 GW-3D OK 35.70 OK OK OK 2.08 GW-4S OK OK 6.47 OK OK 16.23 GW-4D OK OK OK 13.64 45.57 OK OK OK OK 4.55 35.04 GW-7S OK GW-7D OK OK OK Damaged 46.42 60.45

Additional Comments:

WELL INSPECTION SUMMARY

Project Name:

Project Number: <u>11175616.00000</u>

Inspection Crew Members:

T. Ifkovich, K. McGovern

Pfohl Brothers Landfill

Supervisor: <u>J. Sundquist</u>

Date(s) of Inspection:

<u>November 6, 2012</u>

Well I.D. Number	Lock	Surface Seal	Protective Casing	Riser	Water Level (ft. BTOC)	Well Depth (ft. BTOC)	Other Comments
GW-8SR	ОК	ОК	ОК	ОК	5.46	13.02	
GW-8D	ОК	ОК	ОК	ОК	6.05	36.54	
GW-26D	ОК	ОК	ОК	ОК	6.92	40.70	
GW-28S	ОК	ОК	ОК	ОК	8.55	15.52	
GW-29S	ОК	ОК	ОК	ОК	6.88	20.04	
GW-30S	ОК	ОК	ОК	ОК	8.00	17.97	
GW-31S	ОК	ОК	ОК	ОК	2.45	9.57	
GW-32S	ОК	ОК	ОК	ОК	2.58	9.93	

Additional Comments:

WELL INSPECTION SUMMARY

Project Name:

Project Number: <u>11175616.00000</u>

Inspection Crew Members:

T. Ifkovich, K. McGovern

Pfohl Brothers Landfill

Supervisor: <u>J. Sundquist</u>

Date(s) of Inspection:

<u>November 6, 2012</u>

Well I.D. Number	Lock	Surface Seal	Protective Casing	Riser	Water Level (ft. BTOC)	Well Depth (ft. BTOC)	Other Comments
GW-33S	ОК	ОК	OK	ОК	4.08	8.21	
GW-34S	ОК	ОК	ОК	ОК	3.35	10.01	
GW-35S	ОК	ОК	ОК	ОК	4.25	7.46	

Additional Comments:

ATTACHMENT C

IC/EC CERTIFICATION



Enclosure 2 NEW YORK STATE DEPARTMENT OF ENVIRONMENTAL CONSERVATION Site Management Periodic Review Report Notice Institutional and Engineering Controls Certification Form



Si	te No.	Site Details	Box 1	
Si	te Name Pfo	ohl Brothers Landfill		
Cit Co	te Address: // ty/Town: Ch bunty:Erie te Acreage: !			
Re	eporting Peric	od: February 12, 2012 to February 12, 2013		
			YES	NO
1.	Is the inform	mation above correct?	×	
	If NO, inclu	ide handwritten above or on a separate sheet.		
2.		or all of the site property been sold, subdivided, merged, or unendment during this Reporting Period?	undergone a □	×
3.		been any change of use at the site during this Reporting Peri RR 375-1.11(d))?	od	×
4.		ederal, state, and/or local permits (e.g., building, discharge) e property during this Reporting Period?	been issued □	×
		wered YES to questions 2 thru 4, include documentation nentation has been previously submitted with this certifi		
5.	Is the site c	currently undergoing development?		×
		i	Box 2	
			YES	NO .
6.	Is the curren	nt site use consistent with the use(s) listed below?	×	
7.	Are all ICs/E	ECs in place and functioning as designed?	×	
,		E ANSWER TO EITHER QUESTION 6 OR 7 IS NO, sign and DO NOT COMPLETE THE REST OF THIS FORM. Otherwise		
A C	Corrective Me	easures Work Plan must be submitted along with this form	to address these issu	es.
Sig	nature of Owr	ner, Remedial Party or Designated Representative	Date	

Description of	Institutional Controls	
	Institutional Controls	
	<u>Owner</u>	Institutional Control
81.04-1-26	William A. Pfohl	Ground Water Use Restriction Soil Management Plan Landuse Restriction Building Use Restriction Surface Water Use Restriction
Office on 4/25/03 and ollowing Controls are A. Entire Site: i) Gro B. Capped Area: i) F	d included as Appendix P in the Rem e in place: undwater use prohibition, ii) Surface encing, ii) No Excavation, iii) Plantin	
llowed. Construction		
1.04-1-27	Paul Pfohl	
		Ground Water Use Restriction Landuse Restriction
accordance with th	e Declaration of Covenants and Res	Building Use Restriction
ffice on 4/25/03 and ollowing Controls are A. Entire Site: i) Grou B. Capped Area: i) F C. Cleared Portion w lowed. Construction	I included as Appendix P in the Rem a in place: undwater use prohibition, ii) Surface encing, ii) No Excavation, iii) Planting ithin the Perimeter Barrier System: i)	strictions filed with the Erie County Clerk's edial Action Construction Report, Vol. II, the water use prohibition. g trees/shrubs prohibited.) Only Commercial/Industrial Development is Ground Water Use Restriction
office on 4/25/03 and ollowing Controls are A. Entire Site: i) Grou B. Capped Area: i) F C. Cleared Portion w llowed. Construction	I included as Appendix P in the Rem a in place: undwater use prohibition, ii) Surface encing, ii) No Excavation, iii) Planting ithin the Perimeter Barrier System: i) restrictions.	strictions filed with the Erie County Clerk's edial Action Construction Report, Vol. II, the water use prohibition. g trees/shrubs prohibited.) Only Commercial/Industrial Development is
Office on 4/25/03 and ollowing Controls are A. Entire Site: i) Grou B. Capped Area: i) F C. Cleared Portion w llowed. Construction 1.04-1-28.1	I included as Appendix P in the Rem e in place: undwater use prohibition, ii) Surface encing, ii) No Excavation, iii) Planting ithin the Perimeter Barrier System: i) restrictions. Paul Pfohl e Declaration of Covenants and Res included as Appendix P in the Reme	strictions filed with the Erie County Clerk's edial Action Construction Report, Vol. II, the water use prohibition. g trees/shrubs prohibited.) Only Commercial/Industrial Development is Ground Water Use Restriction Landuse Restriction
office on 4/25/03 and billowing Controls are A. Entire Site: i) Grou B. Capped Area: i) F C. Cleared Portion w llowed. Construction 1.04-1-28.1 accordance with the ffice on 4/25/03 and llowing Controls are A. Entire Site: i) Grou B. Capped Area: i) Fe	I included as Appendix P in the Rem a in place: undwater use prohibition, ii) Surface encing, ii) No Excavation, iii) Planting ithin the Perimeter Barrier System: i) restrictions. Paul Pfohl Paul Pfohl included as Appendix P in the Reme in place: undwater use prohibition, ii) Surface v encing, ii) No Excavation, iii) Planting ithin the Perimeter Barrier System: i)	strictions filed with the Erie County Clerk's edial Action Construction Report, Vol. II, the water use prohibition. g trees/shrubs prohibited.) Only Commercial/Industrial Development is Ground Water Use Restriction Landuse Restriction Building Use Restriction Building Use Restriction

• •

Office on 4/25/03 and included as Appendix P in the Remedial Action Construction Report, Vol. II, the following Controls are in place: A. Entire Site: i) Groundwater use prohibition, ii) Surface water use prohibition. B. Capped Area: i) Fencing, ii) No Excavation, iii) Planting trees/shrubs prohibited. C. Cleared Portion within the Perimeter Barrier System: i) Only Commercial/Industrial Development is allowed. Construction restrictions. 81.04-2-11 Paul Pfohl Ground Water Use Restriction Landuse Restriction Building Use Restriction In accordance with the Declaration of Covenants and Restrictions filed with the Erie County Clerk's Office on 4/25/03 and included as Appendix P in the Remedial Action Construction Report, Vol. II, the following Controls are in place: A. Entire Site: i) Groundwater use prohibition, ii) Surface water use prohibition. B. Capped Area: i) Fencing, ii) No Excavation, iii) Planting trees/shrubs prohibited. C. Cleared Portion within the Perimeter Barrier System: i) Only Commercial/Industrial Development is allowed. Construction restrictions. 81.04-2-9.1 Paul Pfohl Ground Water Use Restriction Landuse Restriction Building Use Restriction In accordance with the Declaration of Covenants and Restrictions filed with the Erie County Clerk's Office on 4/25/03 and included as Appendix P in the Remedial Action Construction Report, Vol. II, the following Controls are in place: A. Entire Site: i) Groundwater use prohibition, ii) Surface water use prohibition. B. Capped Area: i) Fencing, ii) No Excavation, iii) Planting trees/shrubs prohibited. C. Cleared Portion within the Perimeter Barrier System: i) Only Commercial/Industrial Development is allowed. Construction restrictions. 82.03-4-10 Elizabeth L. McBride Ground Water Use Restriction Landuse Restriction Building Use Restriction In accordance with the Declaration of Covenants and Restrictions filed with the Erie County Clerk's Office on 4/25/03 and included as Appendix P in the Remedial Action Construction Report, Vol. II, the following Controls are in place: A. Entire Site: i) Groundwater use prohibition, ii) Surface water use prohibition. B. Capped Area: i) Fencing, ii) No Excavation, iii) Planting trees/shrubs prohibited. C. Cleared Portion within the Perimeter Barrier System: i) Only Commercial/Industrial Development is allowed. Construction restrictions. 82.03-4-11 Paul Pfohl Ground Water Use Restriction Landuse Restriction Building Use Restriction In accordance with the Declaration of Covenants and Restrictions filed with the Erie County Clerk's Office on 4/25/03 and included as Appendix P in the Remedial Action Construction Report, Vol. II, the

following Controls are in place:

A: Entire Site: i) Groundwater use prohibition, ii) Surface water use prohibition.

B. Capped Area: i) Fencing, ii) No Excavation, iii) Planting trees/shrubs prohibited.

C. Cleared Portion within the Perimeter Barrier System: i) Only Commercial/Industrial Development is allowed. Construction restrictions.

82.03-4-5

Paul Pfohl

Ground Water Use Restriction Landuse Restriction Building Use Restriction

In accordance with the Declaration of Covenants and Restrictions filed with the Erie County Clerk's Office on 4/25/03 and included as Appendix P in the Remedial Action Construction Report, Vol. II, the following Controls are in place:

A. Entire Site: i) Groundwater use prohibition, ii) Surface water use prohibition.

B. Capped Area: i) Fencing, ii) No Excavation, iii) Planting trees/shrubs prohibited.

C. Cleared Portion within the Perimeter Barrier System: i) Only Commercial/Industrial Development is allowed. Construction restrictions.

82.03-4-6 Paul Pfohl

Ground Water Use Restriction Landuse Restriction Building Use Restriction

In accordance with the Declaration of Covenants and Restrictions filed with the Erie County Clerk's Office on 4/25/03 and included as Appendix P in the Remedial Action Construction Report, Vol. II, the following Controls are in place:

A. Entire Site: i) Groundwater use prohibition, ii) Surface water use prohibition.

B. Capped Area: i) Fencing, ii) No Excavation, iii) Planting trees/shrubs prohibited.

C. Cleared Portion within the Perimeter Barrier System: i) Only Commercial/Industrial Development is allowed. Construction restrictions.

82.03-4-8 Paul Pfohl

Ground Water Use Restriction Landuse Restriction Building Use Restriction

In accordance with the Declaration of Covenants and Restrictions filed with the Erie County Clerk's Office on 4/25/03 and included as Appendix P in the Remedial Action Construction Report, Vol. II, the following Controls are in place:

A. Entire Site: i) Groundwater use prohibition, ii) Surface water use prohibition.

B. Capped Area: i) Fencing, ii) No Excavation, iii) Planting trees/shrubs prohibited.

C. Cleared Portion within the Perimeter Barrier System: i) Only Commercial/Industrial Development is allowed. Construction restrictions.

82.03-4-9.11

Aero Land, Inc. c/o Jerome Hirsh

Ground Water Use Restriction Landuse Restriction Building Use Restriction

In accordance with the Declaration of Covenants and Restrictions filed with the Erie County Clerk's Office on 4/25/03 and included as Appendix P in the Remedial Action Construction Report, Vol. II, the following Controls are in place:

A. Entire Site: i) Groundwater use prohibition, ii) Surface water use prohibition.

B. Capped Area: i) Fencing, ii) No Excavation, iii) Planting trees/shrubs prohibited.

C. Cleared Portion within the Perimeter Barrier System: i) Only Commercial/Industrial Development is allowed. Construction restrictions.

82.03-4-9.12

Stuart Jenkins

Ground Water Use Restriction Landuse Restriction Building Use Restriction

In accordance with the Declaration of Covenants and Restrictions filed with the Erie County Clerk's Office on 4/25/03 and included as Appendix P in the Remedial Action Construction Report, Vol. II, the following Controls are in place:

A. Entire Site: i) Groundwater use prohibition, ii) Surface water use prohibition.

B. Capped Area: i) Fencing, ii) No Excavation, iii) Planting trees/shrubs prohibited.

C. Cleared Portion within the Perimeter Barrier System: i) Only Commercial/Industrial Development is allowed. Construction restrictions.

82.03-4-9.2

Aero Land, Inc. c/o Jerome Hirsh

Ground Water Use Restriction Landuse Restriction Building Use Restriction

In accordance with the Declaration of Covenants and Restrictions filed with the Erie County Clerk's Office on 4/25/03 and included as Appendix P in the Remedial Action Construction Report, Vol. II, the following Controls are in place:

A. Entire Site: i) Groundwater use prohibition, ii) Surface water use prohibition.

B. Capped Area: i) Fencing, ii) No Excavation, iii) Planting trees/shrubs prohibited.

C. Cleared Portion within the Perimeter Barrier System: i) Only Commercial/Industrial Development is allowed. Construction restrictions.

Box 4

Description of Engineering Controls

Engineering Control

81.04-1-26

Parcel

Vapor Mitigation Fencing/Access Control Cover System Leachate Collection

81.04-1-27

Cover System Leachate Collection Fencing/Access Control Vapor Mitigation

For Declaration of Covenants and Restrictions, see Appendix P in the Remedial Action Construction Report, Vol. II

81.04-1-28.1

Vapor Mitigation Cover System Leachate Collection Fencing/Access Control

For Declaration of Covenants and Restrictions, see Appendix P in the Remedial Action Construction Report, Vol. II

81.04-2-10.1

Vapor Mitigation Cover System

Parcel	Engineering Control
	Leachate Collection Fencing/Access Control
Vol. II	trictions, see Appendix P in the Remedial Action Construction Report,
81.04-2-11	
	Vapor Mitigation Cover System
	Leachate Collection
	Fencing/Access Control
For Declaration of Covenants and Rest Vol. II	rictions, see Appendix P in the Remedial Action Construction Report,
81.04-2-9.1	
	Vapor Mitigation
	Cover System Leachate Collection
	Fencing/Access Control
For Declaration of Covenants and Rest	rictions, see Appendix P in the Remedial Action Construction Report,
Vol. II	
82.03-4-10	Vener Mitigation
	Vapor Mitigation Cover System
	Leachate Collection
	Fencing/Access Control
82.03-4-11	
	Vapor Mitigation
	Cover System Leachate Collection
	Fencing/Access Control
For Declaration of Covenants and Restr	ictions, see Appendix P in the Remedial Action Construction Report,
Vol. II	· · · · · · · · · · · · · · · · · · ·
82.03-4-5	
	Vapor Mitigation Cover System
	Leachate Collection
	Fencing/Access Control
For Declaration of Covenants and Restr	ictions, see Appendix P in the Remedial Action Construction Report,
82.03-4-6	Ven an Millingtion
	Vapor Mitigation Cover System
	Leachate Collection
	Fencing/Access Control
Vol. II	ictions, see Appendix P in the Remedial Action Construction Report,
82.03-4-8	Vener Mitigation
	Vapor Mitigation Cover System
	Leachate Collection Fencing/Access Control
For Declaration of Covenants and Restri	ctions, see Appendix P in the Remedial Action Construction Report,
Vol. II	cuerte, see Appendix F in the Remedial Action Construction Report,
82.03-4-9.11	Vapor Mitigation
	Cover System
	Leachate Collection
	Fencing/Access Control
Vol. II	ctions, see Appendix P in the Remedial Action Construction Report,
82.03-4-9.12	Vener Milizetian
	Vapor Mitigation

Parcel

Engineering Control Cover System Leachate Collection Fencing/Access Control

For Declaration of Covenants and Restrictions, see Appendix P in the Remedial Action Construction Report, Vol. II

82.03-4-9.2

Vapor Mitigation Cover System Leachate Collection Fencing/Access Control

For Declaration of Covenants and Restrictions, see Appendix P in the Remedial Action Construction Report, Vol. II

	Box 5
	Periodic Review Report (PRR) Certification Statements
١.	I certify by checking "YES" below that:
	a) the Periodic Review report and all attachments were prepared under the direction of, and reviewed by, the party making the certification;
	b) to the best of my knowledge and belief, the work and conclusions described in this certification are in accordance with the requirements of the site remedial program, and generally accepted engineering practices; and the information presented is accurate and compete.
	YES NO
	If this site has an IC/EC Plan (or equivalent as required in the Decision Document), for each Institutional or Engineering control listed in Boxes 3 and/or 4, I certify by checking "YES" below that all of the following statements are true:
	(a) the Institutional Control and/or Engineering Control(s) employed at this site is unchanged sinc the date that the Control was put in-place, or was last approved by the Department;
	(b) nothing has occurred that would impair the ability of such Control, to protect public health and the environment;
	(c) access to the site will continue to be provided to the Department, to evaluate the remedy, including access to evaluate the continued maintenance of this Control;
	(d) nothing has occurred that would constitute a violation or failure to comply with the Site Management Plan for this Control; and
	(e) if a financial assurance mechanism is required by the oversight document for the site, the mechanism remains valid and sufficient for its intended purpose established in the document.
	YES NO
	IF THE ANSWER TO QUESTION 2 IS NO, sign and date below and DO NOT COMPLETE THE REST OF THIS FORM. Otherwise continue.
A	Corrective Measures Work Plan must be submitted along with this form to address these issues.
	ignature of Owner, Remedial Party or Designated Representative Date

IC CERTIFICATIONS SITE NO. 915043	
	Box 6
O. & M. MANAGER SITE OWNER OR DESIGNATED REPRESENTATIVE SIGNATURE	
I certify that all information and statements in Boxes 1,2, and 3 are true. I understand that a statement made herein is punishable as a Class "A" misdemeanor, pursuant to Section 210.	45 of the
Penal Law. Town of CHEEKTOWAGA 275 ALEXANDER AVENUE Print name am certifying as <u>517E OFM</u> MANAGER (Owner or Rem	211
print name print business address	,
am certifying as SITE OF M MANAGER (Owner or Rem	nedia Party)
for the Site named in the Site Details Section of this form.	x
$\frac{W - n \cdot n}{\text{Signature of Owner, Remedial Party, or Designated Representative}} \qquad \frac{4 3 }{\text{Date}}$	3
Rendering Certification	

· 1

IC/EC CERTIFICATIONS Box 7 **Professional Engineer Signature** I certify that all information in Boxes 4 and 5 are true. I understand that a false statement made herein is punishable as a Class "A" misdemeanor, pursuant to Section 210.45 of the Penal Law. TOWN OF CHEEKTOWAGA 275 ALEXANDER AVENUE CHEEKTOWAGA N.Y. 14211 print business address print name (Owner or Remodial Party) SITE Of M PROVIDER/MANAGER am certifying as a Professional Engineer for the STATE OF NEW YORK ROFES Signature of Professional Engineer, for the Owner or Remedial Party, Rendering Certification Stamp Date (Required for PE) SITE of M PROVIDER/MANAGER