

The electronic version of this file/report should have the file name:

Type of document.Spill Number.Year-Month.File Year-Year or Report name.pdf

letter._____._____._____.File spillfile_____.pdf

report.hw915053 . 2001 - 12-01 . IRM MONITORINGpdf
AND MAINTENANCE REPORT

Project Site numbers will be proceeded by the following:

Municipal Brownfields - b

Superfund - hw

Spills - sp

ERP - e


VCP - v

BCP - c

non-releasable - put .nf.pdf

Example: letter.sp9875693.1998-01.Filespillfile.nf.pdf

915053



RECEIVED

DEC 31 2001

NYSDEC - REG. 9
FOIL
REL UNREL

**IRM MONITORING AND
MAINTENANCE REPORT
December 12, 2001 SAMPLE EVENT**

**STRIPPIT, INC.
AKRON, NEW YORK
NYSDEC SITE NUMBER 9-15-053**

Prepared by: Day Environmental, Inc.
40 Commercial Street
Rochester, New York 14614-1008

Prepared for: Strippit, Inc.
12975 Clarence Center Road
Akron, New York 14001

Date: December 2001

Project No.: 1863R-99

TABLE OF CONTENTS

1.0	INTRODUCTION	1
2.0	GROUNDWATER SAMPLING PROCEDURES	2
3.0	GROUNDWATER ELEVATIONS	3
4.0	ANALYTICAL LABORATORY RESULTS	4
5.0	SITE INSPECTION REPORT	5
6.0	DISCUSSION	6

Figures:

Figure 1	Locus Plan
Figure 2	Site Plan
Figure 3	Groundwater Contour Map

Appendices:

Appendix A	December 12, 2001 Sample Round: Paradigm Environmental Services, Inc. Report and Chain-of-Custody Documentation
Appendix B	Monitoring Well Sample Logs
Appendix C	Summary of Detected Parameters
Appendix D	Site Inspection Report

1.0 INTRODUCTION

Strippit, Inc., (Strippit) has implemented an Interim Remedial Measure (IRM) approved by the New York State Department of Environmental Conservation (NYSDEC) at a former disposal area (Site) located south of their facility at 12975 Clarence Center Road in Akron, New York (see Locus Plan, Figure 1). As outlined in the NYSDEC's March 1995 Record of Decision (ROD), post-closure monitoring and maintenance is required at the Site to evaluate the effectiveness of the IRM. Specific post-closure monitoring and maintenance requirements are outlined in a document prepared by Day Engineering, P.C. titled *Post-Closure Monitoring and Maintenance Plan; Interim Remedial Measure; Strippit, inc.; Akron, New York* dated February 1995. This plan was reviewed and approved by the NYSDEC prior to implementation.

In accordance with a May 1, 1996 letter by the NYSDEC, the testing program outlined in the February 1995 plan was modified to include testing for the following parameters:

- Indicator Parameters: pH, specific conductance, turbidity and temperature
- total and soluble barium, iron, magnesium and manganese
- TCL Volatile Organic Compounds (VOCs)
- total Phenols

In accordance with a June 24, 1998 letter by the NYSDEC, the frequency of groundwater sampling was reduced from quarterly to bi-annually.

This submittal presents the results of the bi-annual groundwater sampling and monitoring conducted on December 12, 2001.

2.0 GROUNDWATER SAMPLING PROCEDURES

Groundwater samples were collected in general accordance with the procedures outlined in the approved post-closure monitoring and maintenance plan. A site plan, showing the location of the monitoring wells is included as Figure 2. Groundwater sampling initially included the measurement of static water levels in each of the wells (designated GW-1 through GW-5) followed by the purging of the wells to remove approximately 3 well volumes (or until wells were dry). The wells were then ~~were~~ allowed to recover so that "fresh" water was retained for testing. Groundwater samples were collected for testing using a dedicated bailer, which is permanently stored above the water within each well casing.

A portion of the groundwater collected from each well was tested in the field for the following parameters using the equipment listed below.

- Specific conductance, temperature, pH, and turbidity: Horiba U-22 Multi-Parameter Water Quality Monitoring System.

In addition to the field testing, samples were also collected for analytical testing. These samples were placed in pre-cleaned sample containers provided by the analytical laboratory. The analytical laboratory also provided necessary preservatives, which were added to the containers before they were returned to the laboratory.

The containers for VOC testing were filled first. The remaining sample containers were filled by placing approximately equal amounts of sample from the bailer into each sample container until the container was filled. When the containers were filled they were placed in a plastic cooler containing ice and stored in a locked field vehicle until they were delivered to the analytical laboratory for testing. Chain-of-custody documentation was maintained throughout the sample collection process. Copies of the executed chain-of-custody forms for the December 12, 2001 sample round are included with the test results in Appendix A.

Executed copies of the monitoring well sample logs for the December 12, 2001 sample round are included in Appendix B. These logs summarize in-situ measurements, groundwater depths, purging information and other relative data.

3.0 GROUNDWATER ELEVATIONS

During the sample round, the depth to groundwater was measured from a monitoring point elevation established on the top of each well casing using an electronic tape water level indicator. The groundwater depths and elevations measured during the December 12, 2001 sample round are presented in the following table.

WELL	TOP OF CASING ELEVATION (ft.)	DEPTH TO WATER (ft.)	GROUNDWATER ELEVATION (ft.)
GW-1	754.32	43.19	711.13
GW-2	770.62	54.19	716.43
GW-3	742.59	36.54	706.05
GW-4	752.24	40.19	712.05
GW-5	771.26	54.59	716.67

A groundwater contour map developed based upon the groundwater elevations calculated using the measurements obtained during the December 12, 2001 sample round is included as Figure 3.

4.0 ANALYTICAL LABORATORY RESULTS

During the December 12, 2001 sample round, groundwater samples were collected from each of the five monitoring wells (i.e., GW-1 through GW-5). A duplicate sample, designated "DUPE", was collected from monitoring well GW-4. All samples were analyzed by Paradigm Environmental Services, Inc. (Paradigm) for the following parameters.

- TCL Volatile Organic Compounds via USEPA Method 8260
- total and soluble Barium, Iron, Magnesium and Manganese via USEPA Method 6010 and total Phenolics via ~~USEPA~~ Method 420.1.
USEPA

Paradigm filtered a portion of unpreserved sample from each test location using a 2-micron filter to create the "soluble" sample for testing. A copy of Paradigm's report for the samples collected on December 12, 2001 is included in Appendix A.

Field and analytical laboratory test parameters measured above applicable detection limits reported by the analytical laboratory are summarized in the tables presented in Appendix C.

5.0 SITE INSPECTION REPORT

A copy of the site inspection report completed during the December 12, 2001 sample round is included in Appendix D.

6.0 DISCUSSION

Groundwater level measurements made during the December 12, 2001 sample round indicate that groundwater flow is generally to the northwest (refer to Figure 3). This flow direction is similar to that determined during earlier sample rounds; however, groundwater elevations measured in the wells during the December 12, 2001 sample round range from about 0.8 to 2.3 feet lower than those measured during the previous monitoring event on October 12, 2001.


A review of the analytical laboratory test results for the detected parameters indicates that with the exceptions noted below the inorganic compounds detected were measured at concentrations below Class GA standards established in 6 NYCRR Part 700-705 for potable groundwater supplies. The concentration of total iron in samples from monitoring wells GW-2, GW-3, GW-4 and GW-5 exceeded these standards; however, none of the soluble iron concentrations exceeded the standards. The total manganese concentration of the sample from GW-4 also exceed the class GA standard, however, the soluble fraction was below the standards. In addition, the total and soluble magnesium concentration in the sample from GW-1 exceeded the 6 NYCRR Part 700-705 standards. VOCs were not detected in any of the samples tested above the laboratory detection limit reported by Paradigm (refer to Appendix A).

The pH values measured in the upgradient wells (GW-2 and GW-5) show evidence of elevated levels concentrations (i.e., they exceed 10.5 standard units, 11.18 and 10.93 respectively). While the pH values measured in the downgradient wells (GW-1, GW-3, and GW-4) do not exceed 10.5 standard units, there has been a recent historic apparent increase in pH concentration within the downgradient wells. As sufficient data becomes available, statistical analysis of the pH data should be completed to determine if the apparent increase is statistically significant. If the increase is found to be statistically significant and the trend of increasing pH continues additional study and remediation may be warranted.

During the December 12, 2001 sample round evidence of erosion and sloughing was observed along north face of the IRM closure area (i.e., approximately three feet above the base of the closure area). The remainder of the IRM is in relatively good condition with no apparent areas of erosion noted during the site visit. No repairs appear necessary at this time, but the area of sloughing should be re-evaluated in the spring 2002 and repaired as necessary. The monitoring wells and the gas well are in relatively good condition and no repairs to the wells or their surface seals are recommended at this time. Waste concrete rubble was observed within a drainage area on the western portion of the Site, this material should be removed to preclude blockage of the drainage way and future problems. An apparent oil sheen was observed on standing water near the north face of the IRM closure area. The source of this apparent sheen could not be determined at the time of the Site visit (i.e., discharge from the IRM closure area or the adjacent parking lot.)

The next scheduled monitoring event at the Site is on or about March 5, ²⁰⁰² ~~2001~~ (i.e., this event will include measurement of water levels measurement of pH and observing the condition of the IRM closure).

FIGURE 1
LOCUS PLAN



3-D TopoQuads Copyright © 1999 DeLorme Yarmouth, ME 04096 Source Data: USGS 550 ft Scale: 1:19,200 Detail: 14-0 Datum: NAD27

Drawing Produced From: 3-D TopoQuads, DeLorme Map Co., referencing USGS quad maps, Wolcottsville (NY) 1995; Akron (NY) 1995; Lancaster (NY) 1982; & Corfu (NY) 1984. Site Lat/Long: N43d-0.6' - W78d-30.25'

DATE
12/27/2001

DRAWN BY
Tww

SCALE
1" = 2000'

day

DAY ENVIRONMENTAL, INC.
ENVIRONMENTAL CONSULTANTS
ROCHESTER, NEW YORK 14614-1008

PROJECT TITLE
**STRIPPIT, INC.
AKRON, NEW YORK**


GROUNDWATER MONITORING

DRAWING TITLE
PROJECT LOCUS MAP

PROJECT NO.
1863R-99

FIGURE 1

FIGURE 2
SITE PLAN



NOTES:

1. This drawing produced from a drawing provided by Deborah A. Naybor, PLS, PC. entitled "Topographic Map Of Part Of Lot 5, TWP. 12, Range 5, Section 6, Town Of Newstead, County Of Erie, New York" dated 3/4/93 & revised 3/26/93.
2. No boundary survey was performed by Deborah A. Naybor, PLS, PC.

LEGEND:

GW-1 ♦ Groundwater Monitoring Well With Designation

DATE
12/27/2001

DRAWN BY
Tww

SCALE
1" = 100'

day

DAY ENVIRONMENTAL, INC.
ENVIRONMENTAL CONSULTANTS
ROCHESTER, NEW YORK 14614-1008

PROJECT TITLE
STRIPPIT, INC.
AKRON, NY

GROUNDWATER MONITORING


DRAWING TITLE

Site Location Map

PROJECT NO.
1863R-99

FIGURE 2

FIGURE 3
GROUNDWATER CONTOUR MAP



NOTES:

1. This drawing produced from a drawing provided by Deborah A. Naybor, PLS, PC. entitled "Topographic Map Of Part Of Lot 5, TWP. 12, Range 5, Section 6, Town Of Newstead, County Of Erie, New York" dated 3/4/93 & revised 3/26/93.
2. No boundary survey was performed by Deborah A. Naybor, PLS, PC.

LEGEND:

- GW-1** 711.13 Groundwater Monitoring Well With Groundwater Elevation Obtained On December 12, 2001
- Potentiometric Contour Line For 12-12-2001
- ↗ Apparent Direction Of Groundwater Flow

DATE
12/27/2001

DRAWN BY
Tww

SCALE
1" = 100'

day

DAY ENVIRONMENTAL, INC.
ENVIRONMENTAL CONSULTANTS
ROCHESTER, NEW YORK 14614-1008

PROJECT TITLE
STRIPPIT, INC.
AKRON, NY

GROUNDWATER MONITORING
DRAWING TITLE
Groundwater Potentiometric Contour Map
For 12/12/2001

PROJECT NO.
1863R-99

FIGURE 3

APPENDIX A

**PARADIGM ENVIRONMENTAL SERVICES, INC. ANALYTICAL SERVICES
REPORT & CHAIN-OF-CUSTODY DOCUMENTATION
December 12, 2001 SAMPLE ROUND**



PARADIGM

ENVIRONMENTAL SERVICES, INC.

179 Lake Avenue, Rochester, NY 14608 (716) 647-2530 FAX (716) 647-3311

Client: Day Environmental, Inc.

Lab Project No.: 01-3099

Client Job Site: Strippit

Lab Sample No.: 11250

Client Job No.: N/A

Sample Type: Water

Field Location: MW-3


Date Sampled: 12/12/2001

Date Received: 12/12/2001

Parameter	Date Analyzed	Method	Total Results (mg/L)	Soluble Results (mg/L)
Barium	12/18/2001	EPA 6010	0.060	0.053
Iron	12/18/2001	EPA 6010	0.943	<0.100
Magnesium	12/18/2001	EPA 6010	25.0	23.9
Manganese	12/18/2001	EPA 6010	0.082	0.063

ELAP ID No.: 10958

Comments: Soluble metals filtered to 0.45um in lab.

Approved By: 

Laboratory Director

File ID: 013099



PARADIGM

ENVIRONMENTAL SERVICES, INC.

179 Lake Avenue, Rochester, NY 14608 (716) 647-2530 FAX (716) 647-3311

Client: Day Environmental, Inc.

Lab Project No.: 01-3099

Client Job Site: Strippit

Lab Sample No.: 11251

Client Job No.: N/A

Sample Type: Water

Field Location: MW-1

Date Sampled: 12/12/2001

Date Received: 12/12/2001

Parameter	Date Analyzed	Method	Total Results (mg/L)	Soluble Results (mg/L)
Barium	12/18/2001	EPA 6010	0.023	<0.020
Iron	12/18/2001	EPA 6010	0.188	<0.100
Magnesium	12/18/2001	EPA 6010	39.1	37.1
Manganese	12/18/2001	EPA 6010	0.027	<0.010

ELAP ID No.: 10958

Comments: Soluble metals filtered to 0.45um in lab.

Approved By: _____

Laboratory Director

File ID: 013099



PARADIGM

ENVIRONMENTAL SERVICES, INC.

179 Lake Avenue, Rochester, NY 14608 (716) 647-2530 FAX (716) 647-3311

Client: Day Environmental, Inc.

Lab Project No.: 01-3099

Client Job Site: Strippit

Lab Sample No.: 11252

Client Job No.: N/A

Sample Type: Water

Field Location: MW-2

Date Sampled: 12/12/2001

Date Received: 12/12/2001

Parameter	Date Analyzed	Method	Total Results (mg/L)	Soluble Results (mg/L)
Barium	12/18/2001	EPA 6010	0.145	0.091
Iron	12/18/2001	EPA 6010	3.11	<0.100
Magnesium	12/18/2001	EPA 6010	2.93	<0.050
Manganese	12/18/2001	EPA 6010	0.064	<0.010

ELAP ID No.: 10958

Comments: Soluble metals filtered to 0.45um in lab.

Approved By: _____

Laboratory Director

File ID: 013099



PARADIGM

ENVIRONMENTAL SERVICES, INC.

179 Lake Avenue, Rochester, NY 14608 (716) 647-2530 FAX (716) 647-3311

Client: Day Environmental, Inc.

Lab Project No.: 01-3099

Lab Sample No.: 11253

Client Job Site: Strippit

Sample Type: Water

Client Job No.: N/A

Field Location: MW-5


Date Sampled: 12/12/2001

Date Received: 12/12/2001

Parameter	Date Analyzed	Method	Total Results (mg/L)	Soluble Results (mg/L)
Barium	12/18/2001	EPA 6010	0.082	0.033
Iron	12/18/2001	EPA 6010	7.97	<0.100
Magnesium	12/18/2001	EPA 6010	13.9	0.275
Manganese	12/18/2001	EPA 6010	0.198	<0.010

ELAP ID No.: 10958

Comments: Soluble metals filtered to 0.45um in lab.

Approved By: 

Laboratory Director

File ID: 013099



PARADIGM

ENVIRONMENTAL SERVICES, INC.

179 Lake Avenue, Rochester, NY 14608 (716) 647-2530 FAX (716) 647-3311

Client: Day Environmental, Inc.

Lab Project No.: 01-3099

Client Job Site: Strippit

Lab Sample No.: 11254

Client Job No.: N/A

Sample Type: Water

Field Location: MW-4

Date Sampled: 12/12/2001

Date Received: 12/12/2001

Parameter	Date Analyzed	Method	Total Results (mg/L)	Soluble Results (mg/L)
Barium	12/18/2001	EPA 6010	0.072	0.043
Iron	12/18/2001	EPA 6010	3.13	<0.100
Magnesium	12/18/2001	EPA 6010	17.2	9.860
Manganese	12/18/2001	EPA 6010	0.074	<0.010

ELAP ID No.: 10958

Comments: Soluble metals filtered to 0.45um in lab.

Approved By: _____

Laboratory Director

File ID: 013099



PARADIGM

ENVIRONMENTAL SERVICES, INC.

179 Lake Avenue, Rochester, NY 14608 (716) 847-2530 FAX (716) 847-3311

Client: Day Environmental, Inc.

Lab Project No.: 01-3099

Client Job Site: Strippit

Lab Sample No.: 11255

Client Job No.: N/A

Sample Type: Water

Field Location: Dupe

Date Sampled: 12/12/2001

Date Received: 12/12/2001

Parameter	Date Analyzed	Method	Total Results (mg/L)	Soluble Results (mg/L)
Barium	12/18/2001	EPA 6010	0.060	0.043
Iron	12/18/2001	EPA 6010	1.78	<0.100
Magnesium	12/18/2001	EPA 6010	14.9	11.2
Manganese	12/18/2001	EPA 6010	0.037	<0.010

ELAP ID No.: 10958

Comments: Soluble metals filtered to 0.45um in lab.

Approved By: _____

Laboratory Director

File ID: 013099

**PARADIGM
ENVIRONMENTAL
SERVICES, INC.**

179 Lake Avenue Rochester, New York 14608 716-647-2530 FAX 716-647-3311

Volatile Laboratory Analysis Report For Non-Potable Water

Client: Day Environmental

Client Job Site: Strippit

Lab Project No.: 01-3099

Lab Sample No.: 11250

Client Job No.: N/A

Sample Type: Water

Field Location: MW-3

Date Sampled: 12/12/01

Date Received: 12/12/01

Field ID No.: N/A

Date Analyzed: 12/13/01

VOLATILE HALOCARBONS	RESULTS (ug/L)	VOLATILE AROMATICS	RESULTS (ug/L)
Bromodichloromethane	ND< 2.0	Benzene	ND< 0.5
Bromomethane	ND< 2.0	Chlorobenzene	ND< 2.0
Bromoform	ND< 2.0	Ethylbenzene	ND< 2.0
Carbon tetrachloride	ND< 0.5	Toluene	ND< 0.5
Chloroethane	ND< 2.0	m,p - Xylene	ND< 1.0
Chloromethane	ND< 1.0	o - Xylene	ND< 0.5
2-Chloroethyl vinyl ether	ND< 2.0	Styrene	ND< 2.0
Chloroform	ND< 0.5		
Dibromochloromethane	ND< 2.0		
1,1-Dichloroethane	ND< 0.5		
1,2-Dichloroethane	ND< 2.0		
1,1-Dichloroethene	ND< 2.0		
trans-1,2-Dichloroethene	ND< 0.5		
1,2-Dichloropropane	ND< 2.0		
cis-1,3-Dichloropropene	ND< 2.0		
trans-1,3-Dichloropropene	ND< 2.0		
Methylene chloride	ND< 5.0		
1,1,2,2-Tetrachloroethane	ND< 2.0		
Tetrachloroethene	ND< 0.5		
1,1,1-Trichloroethane	ND< 0.5		
1,1,2-Trichloroethane	ND< 2.0		
Trichloroethene	ND< 0.5		
Vinyl Chloride	ND< 1.0		
		Ketones & Misc.	
		Acetone	ND< 5.0
		Vinyl acetate	ND< 5.0
		2-Butanone	ND< 5.0
		4-Methyl-2-pentanone	ND< 5.0
		2-Hexanone	ND< 5.0
		Carbon disulfide	ND< 1.0

Analytical Method: EPA 8260

ELAP ID No.: 10958

Comments: ND denotes Not Detected

Approved By

Laboratory Director

**PARADIGM
ENVIRONMENTAL
SERVICES, INC.**

179 Lake Avenue Rochester, New York 14608 716-647-2530 FAX 716-647-3311

Volatile Laboratory Analysis Report For Non-Potable Water

Client: Day Environmental

Client Job Site: Strippit

Lab Project No.: 01-3099

Lab Sample No.: 11251

Client Job No.: N/A

Sample Type: Water

Field Location: MW-1

Date Sampled: 12/12/01

Date Received: 12/12/01

Field ID No.: N/A

Date Analyzed: 12/13/01

VOLATILE HALOCARBONS	RESULTS (ug/L)	VOLATILE AROMATICS	RESULTS (ug/L)
Bromodichloromethane	ND< 2.0	Benzene	ND< 0.5
Bromomethane	ND< 2.0	Chlorobenzene	ND< 2.0
Bromoform	ND< 2.0	Ethylbenzene	ND< 2.0
Carbon tetrachloride	ND< 0.5	Toluene	ND< 0.5
Chloroethane	ND< 2.0	m,p - Xylene	ND< 1.0
Chloromethane	ND< 1.0	o - Xylene	ND< 0.5
2-Chloroethyl vinyl ether	ND< 2.0	Styrene	ND< 2.0
Chloroform	ND< 0.5		
Dibromochloromethane	ND< 2.0		
1,1-Dichloroethane	ND< 0.5		
1,2-Dichloroethane	ND< 2.0		
1,1-Dichloroethene	ND< 2.0		
trans-1,2-Dichloroethene	ND< 0.5		
1,2-Dichloropropane	ND< 2.0		
cis-1,3-Dichloropropene	ND< 2.0		
trans-1,3-Dichloropropene	ND< 2.0		
Methylene chloride	ND< 5.0		
1,1,2,2-Tetrachloroethane	ND< 2.0		
Tetrachloroethene	ND< 0.5		
1,1,1-Trichloroethane	ND< 0.5		
1,1,2-Trichloroethane	ND< 2.0		
Trichloroethene	ND< 0.5		
Vinyl Chloride	ND< 1.0		
		Ketones & Misc.	
		Acetone	ND< 5.0
		Vinyl acetate	ND< 5.0
		2-Butanone	ND< 5.0
		4-Methyl-2-pentanone	ND< 5.0
		2-Hexanone	ND< 5.0
		Carbon disulfide	ND< 1.0

Analytical Method: EPA 8260

ELAP ID No.: 10958

Comments: ND denotes Not Detected

Approved By

Laboratory Director

**PARADIGM
ENVIRONMENTAL
SERVICES, INC.**

179 Lake Avenue Rochester, New York 14608 716-647-2530 FAX 716-647-3311

Volatile Laboratory Analysis Report For Non-Potable Water

Client: Day Environmental
Client Job Site: Strippit

Lab Project No.: 01-3099
Lab Sample No.: 11252

Client Job No.: N/A

Sample Type: Water

Field Location: MW-2

Date Sampled: 12/12/01

Date Received: 12/12/01

Field ID No.: N/A

Date Analyzed: 12/14/01

VOLATILE HALOCARBONS	RESULTS (ug/L)	VOLATILE AROMATICS	RESULTS (ug/L)
Bromodichloromethane	ND< 2.0	Benzene	ND< 0.5
Bromomethane	ND< 2.0	Chlorobenzene	ND< 2.0
Bromoform	ND< 2.0	Ethylbenzene	ND< 2.0
Carbon tetrachloride	ND< 0.5	Toluene	ND< 0.5
Chloroethane	ND< 2.0	m,p - Xylene	ND< 1.0
Chloromethane	ND< 1.0	o - Xylene	ND< 0.5
2-Chloroethyl vinyl ether	ND< 2.0	Styrene	ND< 2.0
Chloroform	ND< 0.5		
Dibromochloromethane	ND< 2.0		
1,1-Dichloroethane	ND< 0.5		
1,2-Dichloroethane	ND< 2.0		
1,1-Dichloroethene	ND< 2.0		
trans-1,2-Dichloroethene	ND< 0.5		
1,2-Dichloropropane	ND< 2.0		
cis-1,3-Dichloropropene	ND< 2.0		
trans-1,3-Dichloropropene	ND< 2.0		
Methylene chloride	ND< 5.0		
1,1,2,2-Tetrachloroethane	ND< 2.0		
Tetrachloroethene	ND< 0.5		
1,1,1-Trichloroethane	ND< 0.5		
1,1,2-Trichloroethane	ND< 2.0		
Trichloroethene	ND< 0.5		
Vinyl Chloride	ND< 1.0		
		Ketones & Misc.	
		Acetone	ND< 5.0
		Vinyl acetate	ND< 5.0
		2-Butanone	ND< 5.0
		4-Methyl-2-pentanone	ND< 5.0
		2-Hexanone	ND< 5.0
		Carbon disulfide	ND< 1.0

Analytical Method: EPA 8260

ELAP ID No.: 10958

Comments: ND denotes Not Detected

Approved By

Laboratory Director

PARADIGM
ENVIRONMENTAL
SERVICES, INC.

179 Lake Avenue Rochester, New York 14608 716-647-2530 FAX 716-647-3311

Volatile Laboratory Analysis Report For Non-Potable Water

Client: Day Environmental

Client Job Site: Strippit

Lab Project No.: 01-3099

Lab Sample No.: 11253

Client Job No.: N/A

Sample Type: Water

Field Location: MW-5

Date Sampled: 12/12/01

Date Received: 12/12/01

Field ID No.: N/A

Date Analyzed: 12/14/01

VOLATILE HALOCARBONS	RESULTS (ug/L)	VOLATILE AROMATICS	RESULTS (ug/L)
Bromodichloromethane	ND< 2.0	Benzene	ND< 0.5
Bromomethane	ND< 2.0	Chlorobenzene	ND< 2.0
Bromoform	ND< 2.0	Ethylbenzene	ND< 2.0
Carbon tetrachloride	ND< 0.5	Toluene	ND< 0.5
Chloroethane	ND< 2.0	m,p - Xylene	ND< 1.0
Chloromethane	ND< 1.0	o - Xylene	ND< 0.5
2-Chloroethyl vinyl ether	ND< 2.0	Styrene	ND< 2.0
Chloroform	ND< 0.5		
Dibromochloromethane	ND< 2.0		
1,1-Dichloroethane	ND< 0.5		
1,2-Dichloroethane	ND< 2.0		
1,1-Dichloroethene	ND< 2.0		
trans-1,2-Dichloroethene	ND< 0.5		
1,2-Dichloropropane	ND< 2.0		
cis-1,3-Dichloropropene	ND< 2.0		
trans-1,3-Dichloropropene	ND< 2.0		
Methylene chloride	ND< 5.0		
1,1,2,2-Tetrachloroethane	ND< 2.0		
Tetrachloroethene	ND< 0.5		
1,1,1-Trichloroethane	ND< 0.5		
1,1,2-Trichloroethane	ND< 2.0		
Trichloroethene	ND< 0.5		
Vinyl Chloride	ND< 1.0		
		Ketones & Misc.	
		Acetone	ND< 5.0
		Vinyl acetate	ND< 5.0
		2-Butanone	ND< 5.0
		4-Methyl-2-pentanone	ND< 5.0
		2-Hexanone	ND< 5.0
		Carbon disulfide	ND< 1.0

Analytical Method: EPA 8260

ELAP ID No.: 10958

Comments: ND denotes Not Detected

Approved By

Laboratory Director

SERVICES, INC.

179 Lake Avenue Rochester, New York 14608 716-647-2530 FAX 716-647-3311

Volatile Laboratory Analysis Report For Non-Potable Water

Client: Day Environmental

Client Job Site: Strippit

Lab Project No.: 01-3099

Lab Sample No.: 11254

Client Job No.: N/A

Sample Type: Water

Field Location: MW-4

Date Sampled: 12/12/01

Date Received: 12/12/01

Field ID No.: N/A

Date Analyzed: 12/14/01

VOLATILE HALOCARBONS	RESULTS (ug/L)	VOLATILE AROMATICS	RESULTS (ug/L)
Bromodichloromethane	ND< 2.0	Benzene	ND< 0.5
Bromomethane	ND< 2.0	Chlorobenzene	ND< 2.0
Bromoform	ND< 2.0	Ethylbenzene	ND< 2.0
Carbon tetrachloride	ND< 0.5	Toluene	ND< 0.5
Chloroethane	ND< 2.0	m,p - Xylene	ND< 1.0
Chloromethane	ND< 1.0	o - Xylene	ND< 0.5
2-Chloroethyl vinyl ether	ND< 2.0	Styrene	ND< 2.0
Chloroform	ND< 0.5		
Dibromochloromethane	ND< 2.0		
1,1-Dichloroethane	ND< 0.5		
1,2-Dichloroethane	ND< 2.0		
1,1-Dichloroethene	ND< 2.0		
trans-1,2-Dichloroethene	ND< 0.5		
1,2-Dichloropropane	ND< 2.0		
cis-1,3-Dichloropropene	ND< 2.0		
trans-1,3-Dichloropropene	ND< 2.0		
Methylene chloride	ND< 5.0		
1,1,2,2-Tetrachloroethane	ND< 2.0		
Tetrachloroethene	ND< 0.5		
1,1,1-Trichloroethane	ND< 0.5		
1,1,2-Trichloroethane	ND< 2.0		
Trichloroethene	ND< 0.5		
Vinyl Chloride	ND< 1.0		
		Ketones & Misc.	
		Acetone	ND< 5.0
		Vinyl acetate	ND< 5.0
		2-Butanone	ND< 5.0
		4-Methyl-2-pentanone	ND< 5.0
		2-Hexanone	ND< 5.0
		Carbon disulfide	ND< 1.0

Analytical Method: EPA 8260

ELAP ID No.: 10958

Comments: ND denotes Not Detected

Approved By

Laboratory Director

PARADIGM
ENVIRONMENTAL
SERVICES, INC.

179 Lake Avenue Rochester, New York 14608 716-647-2530 FAX 716-647-3311

Volatile Laboratory Analysis Report For Non-Potable Water

Client: Day Environmental
Client Job Site: Strippit

Lab Project No.: 01-3099
Lab Sample No.: 11255

Client Job No.: N/A

Sample Type: Water

Field Location: Dupe

Date Sampled: 12/12/01

Date Received: 12/12/01

Field ID No.: N/A

Date Analyzed: 12/14/01

VOLATILE HALOCARBONS	RESULTS (ug/L)	VOLATILE AROMATICS	RESULTS (ug/L)
Bromodichloromethane	ND< 2.0	Benzene	ND< 0.5
Bromomethane	ND< 2.0	Chlorobenzene	ND< 2.0
Bromoform	ND< 2.0	Ethylbenzene	ND< 2.0
Carbon tetrachloride	ND< 0.5	Toluene	ND< 0.5
Chloroethane	ND< 2.0	m,p - Xylene	ND< 1.0
Chloromethane	ND< 1.0	o - Xylene	ND< 0.5
2-Chloroethyl vinyl ether	ND< 2.0	Styrene	ND< 2.0
Chloroform	ND< 0.5		
Dibromochloromethane	ND< 2.0		
1,1-Dichloroethane	ND< 0.5		
1,2-Dichloroethane	ND< 2.0		
1,1-Dichloroethene	ND< 2.0		
trans-1,2-Dichloroethene	ND< 0.5		
1,2-Dichloropropane	ND< 2.0		
cis-1,3-Dichloropropene	ND< 2.0		
trans-1,3-Dichloropropene	ND< 2.0		
Methylene chloride	ND< 5.0		
1,1,2,2-Tetrachloroethane	ND< 2.0		
Tetrachloroethene	ND< 0.5		
1,1,1-Trichloroethane	ND< 0.5		
1,1,2-Trichloroethane	ND< 2.0		
Trichloroethene	ND< 0.5		
Vinyl Chloride	ND< 1.0		
		Ketones & Misc.	
		Acetone	ND< 5.0
		Vinyl acetate	ND< 5.0
		2-Butanone	ND< 5.0
		4-Methyl-2-pentanone	ND< 5.0
		2-Hexanone	ND< 5.0
		Carbon disulfide	ND< 1.0

Analytical Method: EPA 8260

ELAP ID No.: 10958

Comments: ND denotes Not Detected

Approved By

Laboratory Director



PARADIGM

ENVIRONMENTAL SERVICES, INC.

179 Lake Avenue Rochester, New York 716-647-2530 FAX 716-647-3311

Client: Day Environmental, Inc.

Lab Project No.: 01-3099

Client Job Site: Strippit

Client Job No.: N/A

Sample Type: Water

Analytical Method: EPA 420.1

Date Sampled: 12/12/2001

Date Received: 12/12/2001

Date Analyzed: 12/18/2001

Lab Sample ID.	Sample Location/Field ID	Total Phenolics mg/l
11250	MW-3	ND<0.002
11251	MW-1	ND<0.002
11252	MW-2	ND<0.002
11253	MW-5	ND<0.002
11254	MW-4	ND<0.002
11255	Dupe	ND<0.002

ELAP ID No. 10709

Comments: ND denotes Non Detected.

Approved By: _____


Laboratory Director

PARADIGM ENVIRONMENTAL SERVICES, INC.

179 Lake Avenue
Rochester, NY 14608
(716) 647-2530 * (800) 724-1997
FAX: (716) 647-3311

CHAIN OF CUSTODY

REPORT TO:		INVOICE TO:		LAB PROJECT #:	CLIENT PROJECT #:
COMPANY:	DAY Environmental	COMPANY:		01-3099	
ADDRESS:	40 Commercial St.	ADDRESS:	same	TURNAROUND TIME: (WORKING DAYS)	
CITY:	Rochester	CITY:			
STATE:	NY	STATE:			
ZIP:	14614	ZIP:			
PHONE:	454-0210 x 108	PHONE:			
FAX:	454-0825	FAX:			
ATTN:	RAY Kemp	ATTN:			
PROJECT NAME/SITE NAME:	Stripper		☐ 1 ☐ 2 ☐ 3 ☒ 4 ☐ 5 ☐ OTHER		
COMMENTS:	Hold 2 40ml "ww-12"				

DATE	TIME	COMPOSITE	GRAB	SAMPLE LOCATION/FIELD ID	MATRIX	CONTAINER	ANALYST	REMARKS	PARADIGM LAB SAMPLE NUMBER
12/12/01	11:45			mw-3	H ₂ O	4	X X X X		11250
2	12:00			mw-1			X X X X		11251
3	12:12			mw-2			X X X X		11252
4	12:25			mw-5			X X X X		11253
5	12:45			mw-4			X X X X		11254
6				Dupe			X X X X		11255
7	12:55			ww-12	H ₂ O	2	Hold		11256
8									
9									
10									

LAB USE ONLY

SAMPLE CONDITION: Check box if acceptable or note deviation:	CONTAINER TYPE: ☒	PRESERVATIONS: ☒	HOLDING TIME: ☒	TEMPERATURE: ☐
--	---	--	---	---------------------------------------

Sampled By: <i>[Signature]</i>	Date/Time: 12/12/01	Relinquished By: <i>[Signature]</i>	Date/Time: 12/12/01 14:51	Total Cost:
Received By: <i>[Signature]</i>	Date/Time: 12/12/01 14:51	Received @ Lab By: <i>[Signature]</i>	Date/Time: 12/12/01 1530	P.I.F.

APPENDIX B

MONITORING WELL SAMPLE LOGS
December 12, 2001 SAMPLE ROUND

DAY ENVIRONMENTAL, INC.
MONITORING WELL SAMPLING LOG

Gw-1

SECTION 1

SITE LOCATION: Strippit, Akron, New York JOB# : 1863R-99
PROJECT NAME: Post Closure Long Term Monitoring DATE : 12/12/01
SAMPLE COLLECTOR(S): Kirk Hampton
WEATHER CONDITIONS: Partly Cloudy 45°

SECTION 2 - PURGE INFORMATION

DEPTH OF WELL [FT]: 58.44 (MEASURED FROM TOP OF CASING - T.O.C.)

STATIC WATER LEVEL (SWL) [FT]: 43.19 (MEASURED FROM T.O.C.)

DEPTH OF WATER COLUMN [FT]: 15.25 (DEPTH OF WELL - SWL)

CALCULATED VOL. OF H₂O PER WELL CASING [GAL]: 2.48

CALCULATIONS:

CASING DIA. (FT) WELL CONSTANT (GAL/FT)
2" (0.1667) 0.1632

CALCULATIONS

VOL. OF H₂O IN CASING = DEPTH OF WATER COLUMN
X WELL CONSTANT

CALCULATED PURGE VOLUME [GAL]: 7.46 (3 TIMES CASING VOLUME)

ACTUAL VOLUME PURGED [GAL]: ~3.0 (Dry)

PURGE METHOD: 3' Bailer PURGE START: 10:22 END: 10:30

SECTION 3 - SAMPLE IDENTIFICATION

SAMPLE ID #	TIME / DATE	SAMPLING METHOD	ANALYTICAL SCAN(S)	SAMPLE APPEARANCE
Gw-1	12/12/01 12:00	3' Bailer	8260 TCL, Tot./Sol.- Ba, Fe, Mg, Mn-. Tot Phenolics	Clear

SECTION 4 - SAMPLE DATA

SWL (FT)	TEMP (°C)	pH	CONDUCTIVITY mS/m	TURBIDITY (NTU)	VISUAL	PID/FID READING
48.53	10.3	8.76	0.11	NR	Clear	NC

DAY ENVIRONMENTAL, INC.
MONITORING WELL SAMPLING LOG

Gw-2

SECTION 1

SITE LOCATION: Strippit, Akron, New York JOB# : 1863R-99
PROJECT NAME: Post Closure Long Term Monitoring DATE : 12/12/01
SAMPLE COLLECTOR(S): Kirk Hampton
WEATHER CONDITIONS: Partly Cloudy 45°

SECTION 2 - PURGE INFORMATION

DEPTH OF WELL [FT]: 78.60 (MEASURED FROM TOP OF CASING - T.O.C.)

STATIC WATER LEVEL (SWL) [FT]: 54.17 (MEASURED FROM T.O.C.)

DEPTH OF WATER COLUMN [FT]: 24.43 (DEPTH OF WELL - SWL)

CALCULATED VOL. OF H₂O PER WELL CASING [GAL]: 3.98

CALCULATIONS:

CASING DIA. (FT) WELL CONSTANT (GAL/FT)
2" (0.1667) 0.1632

CALCULATIONS

VOL. OF H₂O IN CASING = DEPTH OF WATER COLUMN
X WELL CONSTANT

CALCULATED PURGE VOLUME [GAL]: 11.96 (3 TIMES CASING VOLUME)

ACTUAL VOLUME PURGED [GAL]: 5.0 (Dry)

PURGE METHOD: 3' Bailer PURGE START: 10:38 END: 10:51

SECTION 3 - SAMPLE IDENTIFICATION

SAMPLE ID #	TIME / DATE	SAMPLING METHOD	ANALYTICAL SCAN(S)	SAMPLE APPEARANCE
Gw-2	12/12/01 12:12	3' Bailer	8260 TCL, Tot./Sol.- Ba, Fe, Mg, Mn-. Tot Phenolics	Mostly Clear

SECTION 4 - SAMPLE DATA

SWL (FT)	TEMP (°C)	pH	CONDUCTIVITY mS/m	TURBIDITY (NTU)	VISUAL	PID/FID READING
68.66	9.9	11.18	0.073	560	Mostly Clear	NC

DAY ENVIRONMENTAL, INC.
MONITORING WELL SAMPLING LOG

Gw-3

SECTION 1

SITE LOCATION: Strippit, Akron, New York JOB# : 1863R-99
PROJECT NAME: Post Closure Long Term Monitoring DATE : 12/12/01
SAMPLE COLLECTOR(S): Kirk Hampton
WEATHER CONDITIONS: Partly Cloudy 45°

SECTION 2 - PURGE INFORMATION

DEPTH OF WELL [FT]: 50.00 (MEASURED FROM TOP OF CASING - T.O.C.)
STATIC WATER LEVEL (SWL) [FT]: 36.54 (MEASURED FROM T.O.C.)
DEPTH OF WATER COLUMN [FT]: 13.46 (DEPTH OF WELL - SWL)
CALCULATED VOL. OF H₂O PER WELL CASING [GAL]: 2.19

CALCULATIONS:

CASING DIA. (FT) WELL CONSTANT (GAL/FT)
2" (0.1667) 0.1632

CALCULATIONS

VOL. OF H₂O IN CASING = DEPTH OF WATER COLUMN
X WELL CONSTANT

CALCULATED PURGE VOLUME [GAL]: 6.59 (3 TIMES CASING VOLUME)
ACTUAL VOLUME PURGED [GAL]: ~5.0 (Dry)
PURGE METHOD: 3' Bailer PURGE START: 10:05 END: 10:14

SECTION 3 - SAMPLE IDENTIFICATION

SAMPLE ID #	TIME / DATE	SAMPLING METHOD	ANALYTICAL SCAN(S)	SAMPLE APPEARANCE
Gw-3	12/12/01 11:45	3' Bailer	8260 TCL, Tot./Sol.- Ba, Fe, Mg, Mn-. Tot Phenolics	Clear

SECTION 4 - SAMPLE DATA

SWL (FT)	TEMP (°C)	pH	CONDUCTIVITY mS/m	TURBIDITY (NTU)	VISUAL	PID/FID READING
36.00	10.6	6.45	0.75	51	Clear	NC

DAY ENVIRONMENTAL, INC.
MONITORING WELL SAMPLING LOG

Gw-4

SECTION 1

SITE LOCATION: Strippit, Akron, New York JOB# : 1863R-99
PROJECT NAME: Post Closure Long Term Monitoring DATE : 12/12/01
SAMPLE COLLECTOR(S): Kirk Hampton
WEATHER CONDITIONS: Partly Cloudy 45°

SECTION 2 - PURGE INFORMATION

DEPTH OF WELL [FT]: 52.40 (MEASURED FROM TOP OF CASING - T.O.C.)
STATIC WATER LEVEL (SWL) [FT]: 40.19 (MEASURED FROM T.O.C.)
DEPTH OF WATER COLUMN [FT]: 12.21 (DEPTH OF WELL - SWL)
CALCULATED VOL. OF H₂O PER WELL CASING [GAL]: 1.99

CALCULATIONS:

CASING DIA. (FT) 2" (0.1667) WELL CONSTANT (GAL/FT) 0.1632

CALCULATIONS

VOL. OF H₂O IN CASING = DEPTH OF WATER COLUMN
X WELL CONSTANT

CALCULATED PURGE VOLUME [GAL]: 5.97 (3 TIMES CASING VOLUME)
ACTUAL VOLUME PURGED [GAL]: ~5.0 (Dry)
PURGE METHOD: 3' Bailer PURGE START: 11:17 END: 11:26

SECTION 3 - SAMPLE IDENTIFICATION

SAMPLE ID #	TIME / DATE	SAMPLING METHOD	ANALYTICAL SCAN(S)	SAMPLE APPEARANCE
Gw-4	12/12/01 12:45	3' Bailer	8260 TCL, Tot./Sol.- Ba, Fe, Mg, Mn-. Tot Phenolics	Mostly Clear

SECTION 4 - SAMPLE DATA

SWL (FT)	TEMP (°C)	pH	CONDUCTIVITY mS/m	TURBIDITY (NTU)	VISUAL	PID/FID READING
42.65	11.0	9.68	0.079	270	Mostly Clear	NC

DAY ENVIRONMENTAL, INC.
MONITORING WELL SAMPLING LOG

Gw-5

SECTION 1

SITE LOCATION: Strippit, Akron, New York JOB# : 1863R-99
PROJECT NAME: Post Closure Long Term Monitoring DATE : 12/12/01
SAMPLE COLLECTOR(S): Kirk Hampton
WEATHER CONDITIONS: Partly Cloudy 45°

SECTION 2 - PURGE INFORMATION

DEPTH OF WELL [FT]: 74.30 (MEASURED FROM TOP OF CASING - T.O.C.)
STATIC WATER LEVEL (SWL) [FT]: 54.59 (MEASURED FROM T.O.C.)
DEPTH OF WATER COLUMN [FT]: 19.71 (DEPTH OF WELL - SWL)
CALCULATED VOL. OF H₂O PER WELL CASING [GAL]: 3.21

CALCULATIONS:

CASING DIA. (FT) 2" (0.1667) WELL CONSTANT (GAL/FT) 0.1632

CALCULATIONS

VOL. OF H₂O IN CASING = DEPTH OF WATER COLUMN
X WELL CONSTANT

CALCULATED PURGE VOLUME [GAL]: 9.65 (3 TIMES CASING VOLUME)
ACTUAL VOLUME PURGED [GAL]: ~5.0 (DRY)
PURGE METHOD: 3' Bailer PURGE START: 10:58 END: 11:11

SECTION 3 - SAMPLE IDENTIFICATION

SAMPLE ID #	TIME / DATE	SAMPLING METHOD	ANALYTICAL SCAN(S)	SAMPLE APPEARANCE
Gw-5	12/12/01 12:25	3' Bailer	8260 TCL, Tot./Sol.- Ba, Fe, Mg, Mn-. Tot Phenolics	Mostly Clear

SECTION 4 - SAMPLE DATA

SWL (FT)	TEMP (°C)	PH	CONDUCTIVITY mS/m	TURBIDITY (NTU)	VISUAL	PID/FID READING
66.98	9.9	10.93	0.069	360	Mostly Clear	NC

APPENDIX C
SUMMARY OF DETECTED PARAMETERS

STRIPPIT, INC
INTERIM REMEDIAL MEASURE
POSTCLOSURE MONITORING
SUMMARY OF DETECTED GROUNDWATER PARAMETERS
QUARTERLY SAMPLING: 4/95 TO 12/01:GW1

TEST PARAMETER	UNITS	SAMPLE ROUND																			
		4/11/95	7/12/95	10/16/95	1/22/96	5/8/96	8/6/96	10/29/96	2/6/97	6/9/97	9/15/97	12/16/97	3/13/98	6/11/98	12/14/98	6/23/99	12/15/99	6/22/00	1/11/01	7/3/01	12/12/01
pH	Standard	7.35	8.76	8.63	9.07	8.87	8.04	8.31	8.55	7.38	7.82	7.35	8.37	7.75	8.28	7.502	7.95	8.77	10.57	6.36	8.76
specific conductance	uMHOS/cm	1,400	1,170	751	889	1,297	862	1,179	870	1,660	1,292		1140	1128	877	764	866	968	666	1400	1100
turbidity	NTU	85.8	200	46.6		101.6	83.8	135.2										0		45	
barium, soluble	mg/L	0.058	0.059	0.06	0.12	0.054	0.03	0.04	0.033	0.027	0.02	0.024	0.027	0.028	0.022	0.02	0.02	0.027	0.021	0.023	0.020
barium, total	mg/L	0.079	0.123	0.07	0.13	0.054	0.04	0.0575	0.041	0.0624	0.033	0.035	0.023	0.032	0.0950	0.041	0.036	0.025	0.027	0.025	0.023
iron, soluble	mg/L	0.03	0.36	0.13	8.24	0.15	0.03	1.065	0.04	0.812	0.061	0.05	0.127	0.05	0.232	0.05	0.05	0.1	0.1	0.140	0.100
iron, total	mg/L	1.46	6.82	2.53	8.34	0.15	0.17	2.96	1	5.91	0.985	1.21	0.229	0.676	8.66	1.96	0.724	0.1	0.522	0.246	0.188
magnesium, soluble	mg/L	50.8	44.6	47.5	66.8	62.9	68.6	57.35	63	56	55.2	66.5	66.2	62.2	47.2	62.3	53.5	51	42.2	39.6	37.1
magnesium, total	mg/L	54	52	56.8	68.8	62.9	71.2	64.8	65.6	66.3	69.3	78	65.8	64.5	59.8	63.6	57.7	52.7	43.4	44.3	39.1
manganese, soluble	mg/L	0.005	0.026	0.01	0.23	0.039	0.021	0.04	0.015	0.0347	0.02	0.013	0.017	0.042	0.16	0.036	0.023	0.032	0.012	0.015	0.010
manganese, total	mg/L	0.038	0.171	0.08	0.24	0.039	0.024	0.085	0.041	0.158	0.03	0.049	0.019	0.069	0.255	0.084	0.049	0.033	0.03	0.041	0.027
total phenols	mg/L					0.005	0.005	0.005	0.005	0.005	0.002	0.002	0.005	0.03	0.029	0.002	0.002	0.004	0.002	0.002	0.002
dichlorodifluoromethane	ug/L	0.5	0.5	0.5	0.5	1.00	1.00	1.00	1.00												
chloromethane	ug/L	0.5	0.5	0.5	0.5	1.00	1.00	1.00	1.00	5.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
vinyl chloride	ug/L	0.5	0.5	0.5	0.5	1.00	1.00	1.00	1.00	5.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
acetone	ug/L	26.00	5.00	34.00	6.00	71.00	5.00	5.00	5.00	20.00	5.00	5.00	5.00	241.9	5.00	5.00	5.00	5.00	5.00	5.00	5.00
carbon disulfide	ug/L	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	10.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
trans1,2dichloroethene	ug/L	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	5.00	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50
1,1dichloroethane	ug/L	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	5.00	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50
chloroform	ug/L	0.5	0.5	1.5	0.5	0.5	1.00	0.5	0.5	5.00	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50
2butanone	ug/L	1.00	2.00	0.5	0.5	1.00	1.00	1.00	2.00	10.00	5.00	5.00	5.00	5.00	0.50	5.00	5.00	5.00	5.00	5.00	5.00
1,1,1trichloroethane	ug/L	0.5	0.5	0.9	0.5	0.5	0.5	0.5	0.5	5.0	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50
carbon tetrachloride	ug/L	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	5.0	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50
benzene	ug/L	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	5.0	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50
trichloroethene	ug/L	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	5.0	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50
toluene	ug/L	0.5	0.5	0.5	0.6	0.5	0.5	0.5	0.5	5.0	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50
tetrachloroethene	ug/L	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	5.0	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50
methylene chloride	ug/L	11.00	5.00	21.00	5.00	35.00	14.00	5.00	5.00	5.0	5.00	5.00	5.00	5.00	5.00	5.00	5.00	5.00	5.00	5.00	5.00
m,p-xylenes	ug/L	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	5.0	1.00	1.90	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
o-xylenes	ug/L	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	5.0	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50
phenol	ug/L	1.00	1.00	1.00	1.00																
groundwater elevation	feet	713.43	711.04	710.09	712.82	715.76	714.71	714.29	715.02	715.09	712.34	713.81	715.52	715.27	711.01	713.24	710.6	714.65	713.52	712.98	711.13

STRIPPIT, INC.
INTERIM REMEDIAL MEASURE
POSTCLOSURE MONITORING
SUMMARY OF DETECTED GROUNDWATER PARAMETERS
QUARTERLY SAMPLING: 4/95 TO 12/01: GW2

TEST PARAMETER	UNITS	SAMPLE ROUND																			
		4/11/95	7/12/95	10/16/95	1/22/96	5/8/96	8/6/96	10/29/96	2/6/97	6/9/97	9/15/97	12/16/97	3/13/98	6/11/98	12/14/98	6/23/99	12/15/99	6/22/00	1/11/01	7/3/01	12/12/01
pH	Standard	7.23	11.58	11.71	12.23	11.55	11.33	11.29	11.31	10.51	10.61	10.43	11.54	11.28	11.42	11.04	11.28	10.81	11.56	10.43	11.18
specific conductance	uMHOS/cm	1870	1170	695	771	1239	1050	827	244	770	904	864	80	799	676	761	592	493	564	1000	730
turbidity	NTU	200.00	16.50	11.90		11.60	6.91	3.92	74.00										80		560
barium, soluble	mg/L	0.199	0.200	0.180	0.150	0.116	0.129	0.171	0.115	0.102	0.091	0.045	0.094	0.094	0.088	0.140	0.118	0.111	0.129	0.130	0.091
barium, total	mg/L	0.210	0.211	0.210	0.180	0.118	0.130	0.139	0.127	0.108	0.110	0.099	0.091	0.118	0.107	0.146	0.172	0.122	0.176	0.159	0.145
iron, soluble	mg/L	0.030	0.150	0.007	0.430	0.090	0.030	0.100	0.340	0.100	0.050	0.050	0.050	0.050	0.050	0.050	0.050	0.180	0.143	0.148	0.100
iron, total	mg/L	0.250	0.490	1.440	1.260	0.090	0.180	0.260	0.410	0.100	0.319	9.350	0.194	0.247	0.431	1.230	2.230	1.270	2.360	0.566	3.11
magnesium, soluble	mg/L	0.050	0.140	0.230	1.010	0.470	0.950	0.910	0.089	0.500	0.500	4.100	0.038	0.099	0.214	0.131	0.109	0.251	0.050	0.050	0.050
magnesium, total	mg/L	1.030	0.360	0.910	1.360	0.470	2.510	2.800	0.342	0.500	0.500	23.300	0.222	0.393	0.404	1.140	1.860	1.580	1.660	0.342	2.93
manganese, soluble	mg/L	0.005	0.053	0.005	0.030	0.005	0.005	0.005	0.008	0.010	0.020	0.010	0.010	0.010	0.010	0.010	0.100	0.010	0.010	0.010	0.010
manganese, total	mg/L	0.006	0.150	0.020	0.040	0.005	0.005	0.030	0.009	0.010	0.020	0.224	0.010	0.010	0.010	0.025	0.040	0.040	0.042	0.010	0.064
total phenols	mg/L					0.005	0.020	0.008	0.005	0.005	0.020	0.002	0.005	0.008	0.008	0.002	0.002	0.002	0.002	0.002	0.002
dichlorodifluoromethane	ug/L	0.50	0.50	0.50	0.50	1.00	1.00	1.00	1.00												
chloromethane	ug/L	0.50	0.50	0.50	0.50	1.00	1.00	1.00	1.00	5.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
vinyl chloride	ug/L	0.50	0.50	0.50	0.50	1.00	1.00	1.00	1.00	5.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
acetone	ug/L	31.00	33.00	63.00	24.00	100.00	21.00	47.00	19.00	20.00	5.00	5.00	9.60	29.60	10.80	6.90	5.00	5.00	5.00	5.00	5.00
carbon disulfide	ug/L	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	10.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
trans 1,2dichloroethene	ug/L	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	5.00	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50
1,1dichloroethane	ug/L	0.60	0.50	0.70	0.50	0.50	0.50	0.70	0.60	5.00	0.50	0.50	0.50	0.50	0.50	1.00	1.00	1.00	1.00	1.00	0.50
chloroform	ug/L	0.50	0.50	2.00	0.60	0.50	0.80	0.50	0.50	5.00	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50
2butanone	ug/L	3.00	6.00	0.50	2.00	4.00	1.00	1.00	2.00	10.00	5.00	5.00	5.00	5.00	5.00	5.00	5.00	5.00	5.00	5.00	5.00
1,1,1trichloroethane	ug/L	0.50	0.70	0.60	0.50	0.50	0.60	0.50	0.50	5.00	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50
carbon tetrachloride	ug/L	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	5.00	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50
benzene	ug/L	0.50	0.50	0.50	0.50	0.50	0.60	0.50	0.50	5.00	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50
trichloroethene	ug/L	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	5.00	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50
toluene	ug/L	0.70	0.50	0.90	0.60	0.80	1.00	0.90	0.60	5.00	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50
tetrachloroethene	ug/L	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	5.00	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50
methylene chloride	ug/L	11.00	5.00	23.00	10.00	38.00	5.00	5.00	5.00	5.00	5.00	5.00	5.00	5.00	5.00	5.00	5.00	5.00	5.00	5.00	5.00
m,p-xylenes	ug/L	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	5.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
o-xylenes	ug/L	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	5.00	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50
phenol	ug/L	1.00	5.60	2.00	3.00																
groundwater elevation	feet	719.90	717.08	715.62	718.59	721.58	720.24	719.96	721.22	720.69	717.76	719.67	721.29	720.39	715.77	717.64	716.20	720.42	721.26	718.36	716.43

STRIPPIT, INC.
INTERIM REMEDIAL MEASURE
POST CLOSURE MONITORING
SUMMARY OF DETECTED GROUNDWATER PARAMETERS
QUARTERLY SAMPLING: 4/95 TO 12/01:GW3

TEST PARAMETER	UNITS	SAMPLE ROUND																			
		4/11/95	7/12/95	10/16/95	1/22/96	5/8/96	8/6/96	10/29/97	2/6/97	6/9/97	9/15/97	12/16/97	3/13/98	6/11/98	12/14/98	6/23/99	12/15/99	6/22/00	1/11/01	7/3/01	12/12/01
pH	Standard	6.82	8.01	8.01	8.42	8.42	7.85	7.53	7.63	7.73	7.03	7.43	8.25	6.93	9.20	9.90	7.15	7.75	9.73	6.32	6.45
Specific conductance	uMHOS/cm	2010	568	502	475	614	623	585	342	570	635	567	626	445	507	620	562	441	399	750	750
turbidity	NTU	26.00	26.80	191.00		70.70	5.12	150.30	47.40											140	51
barium, soluble	mg/L	0.056	0.032	0.070	0.850	0.075	0.065	0.073	0.066	0.058	0.057	0.055	0.055	0.057	0.028	0.064	0.052	0.064	0.055	0.056	0.053
barium, total	mg/L	0.065	0.173	0.165	0.090	0.078	0.086	0.078	0.083	0.072	0.076	0.087	0.063	0.069	0.071	0.078	0.084	0.064	0.087	0.068	0.060
iron, soluble	mg/L	0.030	0.100	0.095	3.020	2.030	0.050	1.740	0.120	0.114	0.050	0.050	0.050	0.050	0.005	0.005	0.050	0.100	0.100	0.100	0.100
iron, total	mg/L	1.560	6.710	13.550	4.090	4.230	1.300	2.000	2.370	2.255	3.800	4.650	1.720	1.380	1.810	1.960	3.150	0.250	4.790	1.690	0.943
magnesium, soluble	mg/L	27.700	29.350	29.650	31.950	30.650	27.900	28.450	29.700	26.900	25.400	29.500	27.200	24.550	16.600	28.250	25.800	25.800	25.200	24.800	23.9
magnesium, total	mg/L	28.300	68.700	72.550	32.450	30.950	32.700	16.650	32.900	30.350	35.800	39.350	28.700	27.550	24.600	32.150	31.600	26.300	31.600	26.800	25.0
manganese, soluble	mg/L	0.078	0.138	0.075	0.165	0.131	0.124	0.113	0.148	0.078	0.050	0.080	0.070	0.063	0.010	0.082	0.047	0.064	0.069	0.045	0.063
manganese, total	mg/L	0.120	0.456	0.660	0.210	0.142	0.141	0.128	0.148	0.001	0.120	0.195	0.097	0.011	0.079	0.128	0.111	0.067	0.170	0.082	0.082
total phenols	mg/L					0.005	0.140	0.005	0.005	0.005	0.002	0.002	0.050	0.050	0.001	0.002	0.002	0.002	0.002	0.002	0.002
dichlorodifluoromethane	ug/L	2.40	0.50	0.50	0.50	1.00	1.00	1.00	1.00												
chloromethane	ug/L	1.50	0.50	0.50	0.50	1.00	1.00	1.00	1.00	5.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
vinyl chloride	ug/L	2.30	0.50	0.50	0.50	1.00	1.00	1.00	1.00	5.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
acetone	ug/L	16.00	10.50	18.50	5.50	90.00	5.00	5.00	5.00	20.00	5.00	5.00	5.00	5.00	5.00	5.00	5.00	5.00	5.00	5.00	5.00
carbon disulfide	ug/L	1.80	0.50	0.50	0.50	0.50	3.00	0.50	0.50	10.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
trans1,2dichloroethene	ug/L	0.80	0.50	0.50	0.50	0.50	0.50	0.50	0.50	5.00	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50
1,1dichloroethane	ug/L	0.80	0.50	0.50	0.50	0.50	0.50	0.50	0.50	5.00	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50
chloroform	ug/L	0.70	1.50	1.50	0.50	0.95	3.00	0.50	0.50	5.00	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50
2butanone	ug/L	1.00	7.50	0.75	0.55	0.75	1.00	1.00	2.00	10.00	5.00	5.00	5.00	5.00	5.00	5.00	5.00	5.00	5.00	5.00	5.00
1,1,1trichloroethane	ug/L	1.80	0.50	0.50	0.50	0.50	0.50	0.50	0.50	5.00	0.50	0.50	0.50	0.56	0.50	0.50	0.50	0.50	0.50	0.50	0.50
carbon tetrachloride	ug/L	1.70	0.50	0.50	0.50	0.50	0.50	0.50	0.50	5.00	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50
benzene	ug/L	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	5.00	0.50	0.50	0.50	0.50	0.50	0.50	0.70	0.50	0.50	0.50	0.50
trichloroethene	ug/L	0.80	0.50	0.50	0.50	0.50	0.50	0.50	0.50	5.00	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50
toluene	ug/L	0.70	0.50	0.50	0.50	0.50	0.50	0.50	0.50	5.00	0.50	0.50	0.50	1.00	0.50	0.50	0.50	0.50	0.50	0.50	0.50
tetrachloroethene	ug/L	0.90	0.50	0.50	0.50	0.50	0.50	0.50	0.50	5.00	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50
methylene chloride	ug/L	6.30	5.00	15.50	5.50	37.50	10.00	5.00	5.00	5.00	5.00	5.00	5.00	5.00	5.00	5.00	5.00	5.00	5.00	5.00	5.00
m,p-xylenes	ug/L	1.00	2.00	1.00	1.00	1.00	1.00	1.00	1.00	5.00	1.00	12.80	1.00	3.35	1.00	1.00	1.00	1.00	1.00	1.00	1.00
o-xylenes	ug/L	0.50	7.50	0.50	0.50	0.50	0.50	0.50	0.50	5.00	0.50	3.60	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50
phenol	ug/L	1.00	1.00	1.00	1.00																
groundwater elevation	feet	709.53	707.19	705.56	708.26	711.25	710.47	709.65	710.29	710.16	708.13	709.14	711.01	710.47	706.24	707.94	706.14	710.24	709.00	708.68	706.05

STRIPPIT, INC.
INTERIM REMEDIAL MEASURE
POST CLOSURE MONITORING
SUMMARY OF DETECTED GROUNDWATER PARAMETERS
QUARTERLY SAMPLING: 4/95 TO 12/01:GW4

TEST PARAMETER	UNITS	SAMPLE ROUND																			
		4/11/95	7/12/95	10/16/95	1/22/96	5/8/96	8/6/96	10/29/96	2/6/97	6/9/97	9/15/97	12/16/97	3/13/98	6/11/98	12/14/98	6/23/99	12/15/99	6/22/00	1/11/01	7/3/01	12/12/01
pH	Standard	7.06	8.31	8.34	9.07	8.03	8.01	7.47	8.21	7.62	7.92	8.06	9.11	8.27	9.10	9.49	9.77	10.57	9.37	6.36	9.68
specific conductance	uMHOS/cm	1990	935	628	626	1118	1141	1094	743	1220	1237	989	985	918	745	997	806	784	595	110	790
turbidity	NTU	200	200	107		43	105	47	116											500	270
barium, soluble	mg/L	0.045	0.058	0.070	0.110	0.044	0.041	0.050	0.050	0.046	0.051	0.052	0.054	0.038	0.029	0.060	0.043	0.059	0.044	0.041/0.041	0.043/0.043
barium, total	mg/L	0.179	0.099	0.120	0.130	0.044	0.044	0.054	0.071	0.058	0.060	0.055	0.055	0.055	0.081	0.059	0.078	0.065	0.058	0.079/0.116	0.072/0.060
iron, soluble	mg/L	0.030	1.000	0.370	8.320	1.000	0.030	1.940	0.225	0.100	0.620	0.060	0.050	0.050	0.050	0.050	0.050	0.100	0.100	0.100/0.100	0.100/0.100
iron, total	mg/L	12.020	6.720	11.900	9.850	1.000	0.043	2.140	2.870	1.290	1.320	0.766	0.286	1.510	4.420	1.580	4.000	0.110	1.430	4.91/8.19	3.13/1.78
magnesium, soluble	mg/L	50.020	36.700	30.200	47.900	39.700	37.500	44.300	39.650	40.300	29.550	39.900	34.800	32.700	12.500	28.800	18.400	29.400	29.500	17.600/20.0	9.860/11.2
magnesium, total	mg/L	77.900	48.300	66.000	49.400	39.700	38.800	49.100	46.150	39.000	33.750	42.300	36.000	35.900	31.000	40.100	27.700	25.200	32.100	30.7/35.7	17.2/14.9
manganese, soluble	mg/L	0.005	0.029	0.150	0.200	0.022	0.065	0.062	0.031	0.011	0.020	0.010	0.010	0.014	0.030	0.010	0.010	0.010	0.010	0.010/0.010	0.010/0.010
manganese, total	mg/L	0.320	0.162	0.320	0.240	0.022	0.022	0.086	0.076	0.034		0.023	0.010	0.072	0.094	0.039	0.086	0.010	0.027	0.106/0.201	0.074/0.037
total phenols	mg/L					0.005	0.005	0.005	0.012	0.005	0.020	0.003	0.005	0.005	0.002	0.002	0.002	0.002	0.002	0.002/0.002	0.002/0.002
dichlorodifluoromethane	ug/L	0.50	0.50	0.50	0.50	1.00	1.00	1.00	1.00												
chloromethane	ug/L	0.50	0.50	0.50	0.50	1.00	1.00	1.00	1.00	5.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00/1.00	1.00/1.00
vinyl chloride	ug/L	0.50	0.50	0.50	0.50	1.00	1.00	1.00	1.00	5.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00/1.00	1.00/1.00
acetone	ug/L	12.00	5.00	29.00	14.00	38.00	5.00	5.00	5.00	20.00	5.00	7.70	0.50	16.40	5.00	5.00	5.00	5.00	5.00	5.00/5.00	5.00/5.00
carbon disulfide	ug/L	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	10.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00/1.00	1.00/1.00
trans1,2dichloroethene	ug/L	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	5.00	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50/0.50	0.50/0.50
1,1dichloroethane	ug/L	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	5.00	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50/0.50	0.50/0.50
chloroform	ug/L	0.50	1.60	1.00	0.80	0.50	0.55	0.50	0.50	5.00	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50/0.50	0.50/0.50
2butanone	ug/L	1.00	1.00	0.50	1.00	1.00	1.00	1.00	2.00	10.00	5.00	5.00	5.00	5.00	5.00	5.00	5.00	5.00	5.00	5.00/5.00	5.00/5.00
1,1,1trichloroethane	ug/L	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	5.00	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50/0.50	0.50/0.50
carbon tetrachloride	ug/L	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	5.00	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50/0.50	0.50/0.50
benzene	ug/L	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	5.00	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50/0.50	0.50/0.50
trichloroethene	ug/L	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	5.00	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50/0.50	0.50/0.50
toluene	ug/L	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	5.00	0.50	0.50	0.50	2.10	0.50	0.50	0.50	0.50	0.50	0.50/0.50	0.50/0.50
tetrachloroethene	ug/L	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	5.00	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50/0.50	0.50/0.50
methylene chloride	ug/L	2.60	5.00	18.00	10.00	36.00	6.00	5.00	5.00	5.00	5.00	5.00	5.00	5.00	5.00	5.00	5.00	5.00	5.00	5.00/5.00	5.00/5.00
m,p-xylenes	ug/L	1.00	2.00	1.00	1.00	1.00	1.00	1.00	1.00	5.00	1.00	8.60	1.00	5.90	1.00	1.00	1.00	1.00	1.00	1.00/1.00	1.00/1.00
o-xylenes	ug/L	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	5.00	0.50	2.30	0.50	1.60	0.50	0.50	0.50	0.50	0.50	0.50/0.50	0.50/0.50
phenol	ug/L	1.00	1.00	1.00	1.00																
groundwater elevation	feet	715.06	712.56	711.13	713.69	716.70	715.75	715.36	716.14	715.92	713.37	714.69	716.43	715.74	711.34	711.09	711.60	715.68	714.36	713.90	712.05

STRIPPIT, INC.
INTERIM REMEDIAL MEASURE
POST CLOSURE MONITORING
SUMMARY OF DETECTED GROUNDWATER PARAMETERS
QUARTERLY SAMPLING: 4/95 TO 12/01:GW5

TEST PARAMETER	UNITS	SAMPLE ROUND																			
		4/11/95	7/12/95	10/16/95	1/22/96	5/8/96	8/6/96	10/29/96	2/6/97	6/9/97	9/15/97	12/16/97	3/13/98	6/11/98	12/14/98	6/23/99	12/15/99	6/22/00	1/11/01	7/3/01	12/12/01
pH	Standard	6.99	10.88	10.97	11.54	10.93	10.87	10.39	10.90	10.35	10.14	10.76	11.32	10.84	11.31	10.51	11.18	12.27	9.58	9.76	10.93
specific conductance	uMHOS/cm	2090	735	506	641	831	816	737	286	820	903	665	820	590	567	770	663	634	648	810	690
turbidity	NTU	200	168	113		163	181	38	50											44	360
barium, soluble	mg/L	0.078	0.484	0.060	0.180	0.050	0.051	0.049	0.056	0.046	0.043	0.101	0.051	0.049	0.034	0.042	0.040	0.050	0.041	0.040	0.033
barium, total	mg/L	0.172	0.600	0.180	0.230	0.053	0.055	0.090	0.114	0.053	0.067	0.148	0.065	0.071	0.146	0.068	0.076	0.050	0.073	0.042	0.082
iron, soluble	mg/L	0.030	0.090	0.340	24.800	0.480	0.030	0.990	0.640	0.100	0.050	0.050	0.050	0.050	0.050	0.050	0.050	0.100	0.100	0.100	0.100
iron, total	mg/L	23.000	1.730	24.700	34.300	0.510	0.280	1.330	8.670	1.300	4.930	1.660	1.820	2.220	17.700	3.230	4.210	0.527	5.100	0.443	7.97
magnesium, soluble	mg/L	16.500	4.320	3.680	33.500	2.400	1.330	1.960	5.420	1.540	1.300	0.140	2.070	1.990	0.440	1.590	1.310	0.829	0.778	0.274	0.275
magnesium, total	mg/L	32.200	9.710	32.800	42.500	2.530	2.490	3.050	18.600	3.650	8.000	1.640	5.380	9.300	23.600	5.850	7.150	3.970	7.850	1.450	13.9
manganese, soluble	mg/L	0.005	0.005	0.010	0.570	0.011	0.005	0.014	0.016	0.010	0.002	0.010	0.010	0.010	0.010	0.010	0.010	0.010	0.010	0.010	0.010
manganese, total	mg/L	0.485	0.038	0.620	0.760	0.011	0.008	0.030	0.218	0.024	0.080	0.035	0.037	0.105	0.382	0.068	0.088	0.036	0.106	0.010	0.198
total phenols	mg/L					0.005	0.005	0.005	0.005	0.005	0.002	0.002	0.005	0.081	0.002	0.002	0.002	0.002		0.002	0.002
dichlorodifluoromethane	ug/L	0.50	0.50	0.50	0.50	1.00	1.00	1.00	1.00												
chloromethane	ug/L	0.50	0.50	0.50	0.50	1.00	1.00	1.00	1.00	5.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
vinyl chloride	ug/L	0.50	0.50	0.50	0.50	1.00	1.00	1.00	1.00	5.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
acetone	ug/L	33.00	29.00	43.00	8.00	57.00	7.00	9.00	5.00	20.00	5.00	18.80	5.00	19.70	5.00	8.00	5.00	5.00	5.00	5.00	5.00
carbon disulfide	ug/L	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	10.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
trans1,2dichloroethene	ug/L	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	5.00	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50
1,1dichloroethane	ug/L	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	5.00	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50
chloroform	ug/L	0.50	1.00	1.00	0.50	0.50	2.00	0.50	0.50	5.00	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50
2butanone	ug/L	1.00	1.00	1.00	0.50	1.00	1.00	1.00	2.00	10.00	5.00	5.00	5.00	5.00	5.00	5.00	5.00	5.00	5.00	5.00	5.00
1,1,1trichloroethane	ug/L	0.50	0.50	1.50	0.50	0.50	0.50	0.50	0.50	5.00	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50
carbon tetrachloride	ug/L	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	5.00	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50
benzene	ug/L	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	5.00	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50
trichloroethene	ug/L	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	5.00	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50
toluene	ug/L	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	5.00	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50
tetrachloroethene	ug/L	0.50	0.50	0.60	0.50	0.50	0.50	0.50	0.50	5.00	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50
methylene chloride	ug/L	2.40	5.00	24.00	12.00	23.00	10.00	5.00	5.00	5.00	5.00	5.00	5.00	5.00	5.00	5.00	5.00	5.00	5.00	5.00	5.00
m,p-xylenes	ug/L	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	5.00	1.00	1.00	1.00	6.90	1.00	1.00	1.00	1.00	1.00	1.00	1.00
o-xylenes	ug/L	0.50	0.50	0.50	0.50	0.50	0.50	0.50	0.50	5.00	0.50	0.50	0.50	2.40	0.50	0.50	0.50	0.50	0.50	0.50	0.50
phenol	ug/L	1.00	1.40	1.40	1.00																
groundwater elevation	feet	719.54	716.72	715.29	718.53	721.37	719.99	719.94	721.01	720.14	717.55	719.42	721.08	719.96	715.57	717.30	716.09	720.26	719.05	717.98	716.67

Results in bold print indicate that compound was "nondetect" at the concentration listed.
Results left blank indicate the compound was "not tested" during that sample round.

APPENDIX D

SITE INSPECTION REPORT
December 12, 2001 SAMPLE ROUND

LONG-TERM QUARTERLY MONITORING REPORT
INTERIM REMEDIAL MEASURE
STRIPPIT, INC.
AKRON, NEW YORK

Date of Inspection: December 12, 2001

Inspected By: J. Kirk Hampton

Summary of Observation:

General Condition of Cover: Cover is in good condition, with exception of small area of sloughing.

Evidence of Erosion, sloughing or other degradation: ☒ Yes ☐ No

Explain: Small area of sloughing (approximately 20 feet long by 1.5 high) along north face of IEM

Evidence of cracking: ☐ Yes ☒ No

Explain (include measurements and site sketch): _____

Evidence of water seepage: ☐ Yes ☒ No

Explain: _____

Evidence of Settlement: ☐ Yes ☒ No

Explain: _____

Condition of monitoring wells and gas wells: Wells are in good condition, some areas of surface rust present.

Condition of Vegetative Cover: Vegetative cover is in good condition, no overgrowth is present.

Condition of drainage ways (discuss amount of water/sediments present, vegetative growth unusual staining, blockage, etc.): Drainage ways are in good condition, possible area of concern is small amount of concrete waste along west drainage way that may cause future blockage.

Additional Comments:

Apparent oil sheen observed along Northface of IRM at
parking lot elevation. There were two areas of sheen approximately
20 feet apart.

Action Item(s) Required:

- Upgrade of well casings and concrete seals if needed
- Replacement of barriers in Gw-2, Gw-5 if warranted.
- Evaluation of apparent oil sheen and remediate as
necessary.

Action Item(s) completed since last inspection:

None

Signatures:

