

Consulting March 12, 2019

Engineers and Scientists

Brian Sadowski Project Manager New York State Department of Environmental Conservation 270 Michigan Avenue Buffalo, New York 14209-2915

#### Re: Site Management Periodic Review Report (PRR) and IC/EC Certification Submittal (2018) NFG - Iroquois Gas/Westwood Pharm Riparian Site: Site # 915141B Scajaquada Creek, Upstream of West Ave. Bridge – Buffalo, NY

Dear Mr. Sadowski:

On behalf of National Fuel Gas (NFG), GEI Consultants, Inc. P.C. (GEI) is submitting the attached Periodic Review Report and IC/EC Certification Submittal for the Iroquois Gas/Westwood Pharm Riparian Site on Scajaquada Creek via email transmittal. A hardcopy will follow via UPS.

If you have any questions please contact the undersigned or Ms. Katie Hoelscher of NFG at (716) 857-2236.

Sincerely yours, GEI CONSULTANTS, INC., P.C.

Rillyp

Richard H. Frappa, P.G. Senior Consultant

Kell An of

Kelly R. McIntosh, Ph.D., P.E. Senior Consultant

Enclosure

cc: S. Radon, NYSDEC (1 electronic copy - email)
K. Hoelscher (1 hardcopy - UPS,1 electronic copy - email)
T. Alexander (1 electronic copy - email)





Consulting Engineers and Scientists

## Site Management Periodic Review Report and IC/EC Certification (2018)

Iroquois Gas/Westwood Pharmaceutical Riparian Site No. 915141B Buffalo, New York

Submitted to: NYSDEC Region 9

#### Submitted by:

GEI Consultants, Inc., P.C. 90B John Muir Drive, Suite 104 Amherst, NY 14228

#### On behalf of:

National Fuel Gas Williamsville, New York 14221

March 2019 Project 1403480



MAR Kil.

Richard H. Frappa, P.G. Senior Consultant

Kelly R. McIntosh, P.E., Ph.D. Senior Consultant

# **Table of Contents**

1.	Exec	utive Summary	1
2.	Site	Overview	2
	2.1	Site Description	2
	2.2	Site Remedial Program Summary	2
	2.3	O&M Plan	3
3.	Rem	edy Performance Evaluation	4
	3.1	Scajaquada Creek Sediment Cap	4
	3.2	DNAPL Recovery Systems	4
		3.2.1 Southern DNAPL Recovery System	4
		3.2.2 Northern DNAPL Recovery System	6
4.	IC/EC	C Compliance	8
	4.1	IC/EC Requirements	8
	4.2	IC/EC Compliance	8
	4.3	IC/EC Certification	8
5.	Conc	clusions and Recommendations	9

Site Management Periodic Review Report and IC/EC Certification (2018) Iroquois Gas/Westwood Pharmaceutical Riparian Site No. 915141B Buffalo, New York March 2019

#### Figures

- 1 Site Location Map
- 2 Site Layout

#### Appendices

- A Scajaquada Creek Cap Inspection Photographs and Observations
- B DNAPL Recovery System Monitoring Logs
- C Institutional and Engineering Controls Certification Forms

# 1. Executive Summary

GEI Consultants, Inc., P.C. (GEI) was retained to conduct the Site Management Periodic Review Report (PRR) and IC/EC Certification submittal for the Iroquois Gas/Westwood Pharmaceutical Site located in Buffalo, New York. This PRR presents and evaluates the results of operation and maintenance (O&M) activities performed at the site over the past year and since the remedial action was completed in 2002. The O&M activities include visual inspections of the Scajaquada Creek sediment cap, the creek banks and site restoration elements, and maintenance checks on the northern and southern DNAPL recovery systems.

In conducting this periodic review, GEI determined the components of the O&M Plan dated February 8, 2005 (serves as the Site Management Plan or {SMP}) and amended frequencies of inspections as agreed to in NYSDEC correspondence dated December 2, 2009 were in compliance during this reporting period (February 15, 2018 through February 15, 2019):

- ICs/ECs have been in place and effective.
- Inspections were performed as required.

Based upon the inspections and compliance with the O&M Plan, the site remedy continues to meet the remedial objectives for the site.

Site Management Periodic Review Report and IC/EC Certification (2018) Iroquois Gas/Westwood Pharmaceutical Riparian Site No. 915141B Buffalo, New York March 2019

# 2. Site Overview

### 2.1 Site Description

The Scajaquada Creek Site is the riparian portion of the Iroquois Gas/Westwood Pharmaceutical (IG/WP) Site and is situated in a mixed industrial and residential area of Buffalo, New York. The site comprises approximately 2.5 acres along a 1,600-foot long reach of Scajaquada Creek. The Site location and Site layout are shown on Figure 1 and Figure 2, respectively. Manufactured gas plant (MGP) operations were conducted at a former Iroquois Gas facility situated upgradient of the Site on property at 100 Forest Avenue from the 1890s to the 1950s and gas storage continued until 1972. Investigations indicated that soil and groundwater were impacted with chemicals associated with gas manufacturing processes and that constituents were migrating into the creek. Remedial activities (i.e., sheet pile wall installation, sediment excavation, capping, and installation and operation of dense non-aqueous phase liquid (DNAPL) recovery systems) have been performed since 1999 to address these impacts.

### 2.2 Site Remedial Program Summary

In 1996, National Fuel constructed a sheet pile wall along the eastern bank of the creek, adjacent to the IG/WP property. The sheet pile wall was an initial component of the remedial action which separates the terrestrial remedial action (the responsibility of others) from the riparian remedial action. National Fuel conducted the riparian remedial action in two phases: 1. Sediment/soil removal and capping in Scajaquada Creek; and 2. DNAPL collection and removal from permeable soil below the creek sediment cap. The riparian remedial design was conducted in 1997/1998 and received approval in June 1998. Remedial excavation and capping began in July 1998 and completed in May 1999. Installation and startup of the southern DNAPL recovery system was completed in June 1999. Following completion of property access agreements, installation and startup of the northern DNAPL recovery system was completed in August 2002. In summary, the components of the selected remedy include:

- Installation of a sheet pile barrier wall beneath a 70-foot width of the creek, close to West Avenue.
- Installation of approximately 450 linear feet of a steel sheet pile barrier along the east bank of the creek (bordering property of former MGP operations).
- Excavation of the creek bottom and off-site disposal of 18,976 cubic yards of contaminated sediment and debris. The overall goal of excavation was to remove

sediments with concentrations of PAHs greater than 50 mg/kg within the site boundary, taking into account the physical limitations at the site.

- Capping of the creek bottom resulting in a horizontal barrier (cap) along the 1,600 foot reach of Scajaquada Creek. The cap consists of geosynthetic clay liner (GCL), angular sand, geotextile, and anchoring stone.
- Installation of two DNAPL recovery systems near the West Avenue Bridge and the Conrail railroad bridge.
- Implementation of an O&M Plan as an institutional control to verify and ensure the performance of the remedial systems.

Excluding O&M activities, no significant changes have been made to the remedy since remedy selection.

Details of the Remedial Action are presented in the Final Engineering Report (FER), prepared by ThermoRetec (August 2000) with a supplemental FER prepared by Retec (November 2001).

### 2.3 O&M Plan

O&M requirements for the Site are documented in the NYSDEC-approved O&M Plan dated February 8, 2005 (O&M Plan) and a modification of monitoring frequency as described in a correspondence prepared by AECOM dated July 9, 2009 and approved by the NYSDEC by letter dated December 2, 2009. These documents serve as the Site Management Plan (SMP) for the site. Components of the SMP for the Scajaquada Creek Site include:

- inspection of the Scajaquada Creek sediment cap;
- inspection of the DNAPL recovery systems;
- maintenance checks on the operation of the DNAPL recovery systems;
- maintenance and repair of engineering controls; and
- field observations and reporting.

Each of these elements was conducted between February 2018 and February 2019.

# 3. Remedy Performance Evaluation

The remedial performance is evaluated based on the following:

- 1. Periodic inspection of the Scajaquada Creek sediment cap.
- 2. Periodic inspection of the DNAPL recovery systems.

### 3.1 Scajaquada Creek Sediment Cap

The 2018 annual inspection of the Scajaquada Creek Sediment Cap was conducted by Mr. Richard Frappa, P.G. of GEI on May 8, 2018. Photographs of the inspection were discussed with and reviewed by Mr. Kelly McIntosh, P.E. of GEI. The annual visual inspection was performed to evaluate remedy effectiveness in protecting human health and the environment. The inspection also included the assessment of repairs made in 2015 (as shown on attached Figure 2 and in the photograph logs in Appendix A) to determine the continued protectiveness of repairs. Sheen was not observed on Scajaquada Creek surface water nor was NAPL seepage seen along the eastern shoreline. GEI 2018 inspection noted similar conditions to the prior year's observations and did not identify deficiencies in the capping system nor any incipient problems meriting corrective measures. GEI recommends periodic monitoring of partially exposed geotextile observed at Maintenance Area 5 (see Photo 8 in Appendix A). No specific supplemental maintenance activities are recommended in 2019 for the capping system at this site.

### 3.2 DNAPL Recovery Systems

The northern and southern DNAPL recovery systems were checked monthly by National Fuel staff between February 2018 and February 2019. GEI periodically supported monthly system checks and provided recommended improvements in system function focusing on maximizing DNAPL volume collection while minimizing water volume collection. System operations were augmented periodically to achieve this goal in 2018 and actions taken are summarized below for the Southern and Northern DNAPL recovery systems.

#### 3.2.1 Southern DNAPL Recovery System

The southern DNAPL recovery system was observed to function properly during the period of this report. Maintenance activities performed on the southern DNAPL recovery system during this period included: changing flexible tubing near the pump head in each vault, resetting timers to Daylight Savings Time, and pump run time adjustments as necessary.

DNAPL level measurements were recorded periodically from the collection tank of the southern DNAPL recovery system. Annual DNAPL monitoring was conducted during the monitoring period in April (April 26, 2018) and measurements were also collected on several other dates in 2018. During each monitoring event, depth to water and DNAPL, as well as calculated quantities were determined and are reported on the DNAPL recovery system monitoring log presented in Appendix B. Volumes were calculated by taking measurements in the tanks with a water level meter and also measuring the length of DNAPL staining on a weighted string lowered to the tank bottom. The increase in DNAPL volume recovered between February 15, 2018 and February 15, 2019 was approximately 69 gallons.

# Actions Taken to Monitor System Function and Improve DNAPL Recovery (in addition to monthly checks):

- February 15, 2018 Inspected system to assess overall DNAPL collection volume improvement and measured DNAPL collected in hanging pail inside tank. Pump malfunction was identified and corrected.
- March 1, 2018 Replaced peristaltic pump, pump controller, and pump head tubing.
- April 26, 2018 Inspected system to evaluate pump repairs performed in February and adjusted pump rate and schedule. Float shut-off switch was found to be faulty.
- May 1, 2018 Replaced the float shut-off switch in the NAPL collection vault. Adjusted flow rate and schedule of peristaltic pump.
- May 17, 2018 Vacuum extract tank contents and transport by Allied Environmental Services (AES) to an off-site licensed disposal facility (Covanta Environmental Solutions {CES}). Adjusted flow rate of peristaltic pump.
- July 12, 2018 Inspected system to assess overall DNAPL collection volume improvement.
- July 26, 2018 Cleaning of the interior of the concrete storage vault walls and floors using high pressure water and degreaser. Vacuum extract cleaning residuals and transport by AES to an off-site licensed disposal facility (CES).
- August 16, 2018 Inspected system to assess overall DNAPL collection volume improvement.
- September 20, 2018 Inspected system to assess overall DNAPL collection volume improvement. Adjusted flow rate and schedule of peristaltic pump.

- October 25, 2018 Inspected system to assess overall DNAPL collection volume improvement.
- January 16, 2019 Inspected system to assess overall DNAPL collection volume improvement.

The south vault DNAPL collection system continues to operate efficiently following the jetting and tubing improvements made in May 2017. Since operation startup in 1999, approximately 2,589 gallons of DNAPL have been collected by the south vault collection system.

#### 3.2.2 Northern DNAPL Recovery System

The northern DNAPL recovery system was observed to function properly during each inspection event in 2018. During the January 2019 inspection event, the peristaltic pump was found to be off and the electrical circuit breaker powering the pump was tripped to the off position. The circuit breaker was subsequently reset, and the pump was observed to function normally. Maintenance activities performed on the northern DNAPL recovery system during this period included: improving methods of obtaining DNAPL volume estimates, changing flexible tubing near the pump head as necessary, resetting timers to Daylight Savings Time, and pump run time adjustments.

DNAPL level measurements were recorded periodically from the collection tank of the northern DNAPL recovery system. Annual DNAPL monitoring was conducted during the monitoring period in April 2018 and measurements were also collected on several other dates. Depth to water and DNAPL, as well as calculated quantities, are reported on the DNAPL recovery system monitoring log presented in Appendix B. Volumes were calculated by taking measurements in the tanks with a water level meter and measuring the length of DNAPL staining on a weighted string lowered to the tank bottom. The increase in DNAPL volume recovered between February 15, 2018 and February 15, 2019 was approximately 11 gallons.

# Actions Taken to Monitor System Function and Improve DNAPL Recovery (in addition to monthly checks):

- April 26, 2018 Inspected system to assess overall DNAPL collection volume improvement.
- May 17, 2018 Replaced downhole extraction tubing, replaced pump head tubing, clean interior of NAPL vault (high pressure wash and vacuum), vacuum extract DNAPL collection tank contents and transport tank contents and cleaning residuals by AES to an off-site licensed disposal facility (CES).

- July 12, 2018 Inspected system to assess overall DNAPL collection volume improvement.
- July 26, 2018 Cleaning of the interior of the concrete storage vault walls and floors using high pressure water and degreaser. Vacuum extract cleaning residuals and transport by AES to an off-site licensed disposal facility (CES).
- August 16, 2018 Inspected system to assess overall DNAPL collection volume improvement.
- September 20, 2018 Inspected system to assess overall DNAPL collection volume improvement.
- October 25, 2018 Inspected system to assess overall DNAPL collection volume improvement.
- January 16, 2019 Inspected system to assess overall DNAPL collection volume improvement and reset malfunctioning peristaltic pump power supply.

NAPL recovery rates during the February 2018 to February 2019 period were generally consistent between assessment events. The pumping rate was lowered from previous monitoring periods to maximize DNAPL collection and minimize the amount of water pumped.

Since operation startup in 2001, approximately 566 gallons of DNAPL have been collected by the north vault system.

Site Management Periodic Review Report and IC/EC Certification (2018) Iroquois Gas/Westwood Pharmaceutical Riparian Site No. 915141B Buffalo, New York March 2019

# 4. IC/EC Compliance

### 4.1 IC/EC Requirements

ICs include the following;

- Implementation of Site O&M Plan.
- Monitoring and inspection to assess the performance and effectiveness of the remedy.

The Site is a New York State waterway and property use is limited to its function as a conveyance of surface water in the City of Buffalo.

ECs include the following;

- Sediment cap consisting of GCL overlain by sand, geotextile and anchoring stone.
- Collection of mobile DNAPL below the sediment cap.
- Maintenance of the sediment cap and operation and maintenance of the DNAPL collection systems.

#### 4.2 IC/EC Compliance

The NYSDEC-approved O&M Plan is in place. All required inspections were performed during this reporting period in accordance with the plan.


### 4.3 IC/EC Certification


The IC/EC Certification is included in Appendix C.

# 5. Conclusions and Recommendations


Each component of the O&M Plan dated February 8, 2005 and amended frequencies of inspections as agreed to in NYSDEC correspondence dated December 2, 2009, collectively regarded as the SMP, were in compliance during this reporting period (February 15, 2018 through February 15, 2019). The ICs/ECs have been in place and effective and inspections and maintenance were performed as required.

Based upon the inspections and compliance with the SMP, the site remedy continues to meet the remedial objectives for the site.





Scajaquada Creek Cap Inspection Photographs and Observations



Project :	Iroquois Gas/Westwood Pharmaceutical Riparian Site No. 915141B - 2018 Creek Cover	Date: 05/08/18	
	•		
	System Inspection		
Client :	National Fuel	Report No. PRR'18	
Photo by:	R. Frappa, P.G./ <b>Reviewed by:</b> K. McIntosh, P.E.	<b>Page:</b> 1 of 13	5
2		<b>GEI Proj. No.</b> 140348	80

Photo 1. View looking northeast of west bank of creek at 2015 Maintenance Area 1. Vegetation and rip rap remain in place.





Project :	Iroquois Gas/Westwood Pharmaceutical Riparian Site No. 915141B - 2018 Creek Cover	Date: 05/08/18	
Client :	System Inspection National Fuel	<b>Report</b> No. prr <sup>.</sup>	18
Photo by:	R. Frappa, P.G./ <b>Reviewed by:</b> K. McIntosh, P.E.	Page: GEI Proi. No.	2 of 13 1403480

Photo 2. View looking east of east bank of creek at 2015 Maintenance Area 2. Rip rap remains in place.





Project :	Iroquois Gas/Westwood Pharmaceutical	Date: 05/08/18	
	Riparian Site No. 915141B - 2018 Creek Cover		
	System Inspection		
Client :	National Fuel	Report No. PRR'18	
Photo by:	R. Frappa, P.G./ <b>Reviewed by:</b> K. McIntosh, P.E.	Page: 3 of 1	3
-		<b>GEI Proj. No.</b> 14034	180

Photo 3. Downslope view on east bank of 2015 Maintenance Area 2. Rip rap in good condition.





Droiset	Ironucia CooMostucad Dharmasoutical	Dete: 05/00/40
Project :	Iroquois Gas/Westwood Pharmaceutical	Date: 05/08/18
	Riparian Site No. 915141B - 2018 Creek Cover	
	System Inspection	
Client :	National Fuel	Report No. PRR'18
Photo by:	R. Frappa, P.G./ <b>Reviewed by:</b> K. McIntosh, P.E.	Page: 4 of 13
-		<b>GEI Proi</b> , <b>No</b> , 1403480

Photo 4. View looking east at east bank of BMS sheet pile near Maintenance Area 4. Sheet pile and rip rap in good condition.





Project :	Iroquois Gas/Westwood Pharmaceutical	Date: 05/08/18	
-	Riparian Site No. 915141B - 2018 Creek Cover		
	System Inspection		
Client :	National Fuel	Report No. PRR'1	8
Photo by:	R. Frappa, P.G./ <b>Reviewed by:</b> K. McIntosh, P.E.	Page:	5 of 13
-		GEI Proj. No.	1403480

Photo 5. Top down closeup view of Maintenance Area 4 and sheet pile. Rip rap in good condition.





Project :	Iroquois Gas/Westwood Pharmaceutical Riparian Site No. 915141B - 2018 Creek Cover	Date: 05/08/18	
Client :	System Inspection National Fuel	<b>Report</b> No. PRR <sup>*</sup>	18
Photo by:	R. Frappa, P.G./ <b>Reviewed by:</b> K. McIntosh, P.E.	Page: GEI Proi, No.	6 of 13 1403480

Photo 6. Southeast view of west bank at Maintenance Area 8, rip rap in good condition, no erosion on down slope of drain spout.





Project :	Iroquois Gas/Westwood Pharmaceutical Riparian Site No. 915141B - 2018 Creek Cover	Date: 05/08/18	
Client :	System Inspection National Fuel	Report No. PRR'18	
Photo by:	R. Frappa, P.G./ <b>Reviewed by:</b> K. McIntosh, P.E.	Page: 7 of 13 GEI Proj. No. 140348	

Photo 7. North view of Maintenance Area 5. No visible erosion. Rip rap and stone block in place.





Project :	Iroquois Gas/Westwood Pharmaceutical Riparian Site No. 915141B - 2018 Creek Cover	Date: 05/08/18	
	System Inspection		
Client :	National Fuel	Report No. PRR'	18
Photo by:	R. Frappa, P.G./ <b>Reviewed by:</b> K. McIntosh, P.E.	Page:	8 of 13
-		GEI Proj. No.	1403480

Photo 8. Closeup view east bank at Maintenance Area 5. Some geotextile visible but tightly bound by surrounding block and stone.





Project :	Iroquois Gas/Westwood Pharmaceutical Riparian Site No. 915141B - 2018 Creek Cover	Date: 05/08/18
Client :	System Inspection National Fuel	Report No. PRR'18
Photo by:	R. Frappa, P.G./ <b>Reviewed by:</b> K. McIntosh, P.E.	Page: 9 of 13 GEI Proj. No. 1403480

### Photo 9. Closeup view of Maintenance Area 6. Rip rap placement intact. No visible erosion.





Project :	Iroquois Gas/Westwood Pharmaceutical Riparian Site No. 915141B - 2018 Creek Cover System Inspection	Date: 05/08/18
Client : Photo by:	National Fuel R. Frappa, P.G./ <b>Reviewed by:</b> K. McIntosh, P.E.	Report No. PRR'18 Page: 10 of 13 GEI Proj. No. 1403480

Photo 10. North view of west bank toward Conrail Bridge. No visible erosion.





Project :	Iroquois Gas/Westwood Pharmaceutical Riparian Site No. 915141B - 2018 Creek Cover System Inspection	Date: 05/08/18
Client : Photo by:	National Fuel R. Frappa, P.G./ <b>Reviewed by:</b> K. McIntosh, P.E.	Report No. PRR'18 Page: 11 of 13 GEI Proj. No. 1403480


Photo 11. Closeup view of west bank at BMS outfall with gabion baskets. No visible erosion.





Project :	Iroquois Gas/Westwood Pharmaceutical Riparian Site No. 915141B - 2018 Creek Cover	Date: 05/08/18
Client :	System Inspection National Fuel	Report No. prr <sup>,</sup> 18
Photo by:	R. Frappa, P.G./ <b>Reviewed by:</b> K. McIntosh, P.E.	Page:12 of 13GEI Proj. No.1403480


Photo 12. West view of west bank south of Area 7. No visible erosion of creek bank.





Project :	Iroquois Gas/Westwood Pharmaceutical	Date: 05/08/18	
•	Riparian Site No. 915141B - 2018 Creek Cover		
	System Inspection		
Client :	National Fuel	Report No. PRR'18	
Photo by:	R. Frappa, P.G./ <b>Reviewed by:</b> K. McIntosh, P.E.	Page:	13 of 13
-		GEI Proi. No.	1403480

Photo 13. West view of west bank near South Vault showing rip rap surface water conveyance. No visible erosion above or at creek bank.





DNAPL Recovery System Monitoring Log

#### NORTHERN DNAPL RECOVERY SYSTEM

		Field Me	asurements	(by OWI	probe)	Calculatio	ons (total t	ank conten	ts) *	Calculatio	ons (this pe	eriod recovery)			
Date	Initials	Manhole rim to top of LNAPL (ft)	Manhole rim to top of Water (ft) (estimated)	Manhole rim to top of DNAPL (ft)	Manhole rim to bottom of Tank (ft)	LNAPL (gal)	Water (gal)	DNAPL (gal)	Total (gal)	Water Increase (gal)	NAPL Increase (gal)	% NAPL	NAPL (gpd)	Ave. Recovery in GPD	Operator's No
28-Nov-01	mrh/cd	8.89	8.89	8.89	8.89	0	0	0	0	0	0	0%	0.00	0.0	Develop well with hand operated diaphragm pump. Measurements are approximate.
7-Feb-02	hs/jc	8.62	8.62	8.85	8.89	0	71	12	83	71	12	15%	0.17	1.2	Pump well by hand.
8-Mar-02	hs/jc	8.61	8.61	8.85	8.89	0	74	12	86	3	0	0%	0.00	0.1	Pump well by hand.
10-Apr-02	mrh	8.59	8.59	8.84	8.89	0	77	15	93	3	3	50%	0.09	0.2	Pump well by hand.
7-May-02	hs/jc	8.51	8.51	8.83	8.89	0	99	19	117	22	3	12%	0.11	0.9	Hand pump not working well.
25-Jun-02	cd	8.51	8.51	8.83	8.89	0	99	19	117	0	0	0%	0.00	0.0	Hand pump not working. Discarded.
2-Aug-02	mrh/jc	8.51	8.51	8.83	8.89	0	99	19	117	0	0	0%	0.00	0.0	Begin peristaltic startup. Setting #6.5, 2hr 15 min per day
8-Oct-02	mrh/jc	7.43	7.44	8.55	8.89	3	343	105	451	244	90	27%	1.34	5.0	Additional system checks/adjustments made by J Clark on 8/15, 8/21, 8/27, 9/09, and
4-Feb-03	mrh/jc	7.36	7.37	8.52	8.89	3	355	114	472	12	9	43%	0.08	0.2	Numbers approximate. Surface of contents frozen. Turn on heat.
10-Apr-03	mrh/jc	7.28	7.29	8.50	8.89	3	374	120	497	19	6	25%	0.10	0.4	Pumping mostly water, changed timer to 30 min/week.
23-Jul-03	mrh	7.05	7.06	8.49	8.89	3	442	124	568	68	3	4%	0.03	0.7	Additional system checks/adjustments made by J Clark on 5/5, 5/20, 6/12, and 6/24.
23-Apr-04	mrh	6.90	6.91	8.42	8.89	3	466	145	614	25	22	47%	0.08	0.2	Additional system checks/adjustments made by NFG on 8/01, 8/06, 9/05, 9/08, 9/11,
24-Nov-04	jl, jc	6.66	6.67	8.41	8.89	3	537	148	689	71	3	4%	0.01	0.3	O/W interface probe not working accurately, depth of DNAPL is estimated.
19-Apr-05	mh,jc,jl,sh	6.45	6.46	8.39	8.89	3	596	154	753	59	6	10%	0.04	0.4	Additional system checks/adjustments made by J Clark on 11/24, 1/20/2005, 3/7, 3/1
26-Oct-05	mrh, jc	6.33	6.34	8.30	8.89	3	605	182	790	9	28	75%	0.15	0.2	New OWI probe, but readings inconsistent with previous readings. System checks by
22-Mar-06	mrh, jc	6.20	6.21	8.23	8.89	3	624	204	831	19	22	54%	0.15	0.3	Additional system checks by NFG 10/26/05, 12/14/05, 1/6/06, 2/24/06.
24-Oct-06	mrh, jc	5.20	5.21	7.89	8.89	3	828	309	1139	204	105	34%	0.49	1.4	Depth to NAPL reading is approximate. Additional system checks by NFG 5/11, 6/29
25-Apr-07	mrh, jc	4.90	4.91	7.80	8.89	3	892	337	1232	65	28	30%	0.15	0.5	Depth to NAPL reading is approximate. Additional system checks by NFG 10/31/200
30-Oct-07	dms, jc	4.68	4.69	7.70	8.89	3	929	367	1300	37	31	45%	0.16	0.4	Depth to NAPL reading is approximate. Tubing changed out.
13-May-08	dms, jc	3.46	3.47	7.65	8.89	3	1291	383	1677	361	15	4%	0.08	1.9	Depth of DNAPL is estimated. Additional system checks by NFG on 1/08/08, 3/20/08
25-Mar-09	jl, dz	8.75	8.76	8.88	8.89	3	37	3	43	34	9	20%	0.03	0.1	Data for depth to DNAPL changed to prevent table indicating a reduction in NAPL vol
8-Jun-09	jc				8.89										Covered exposed fabric on the bank and on the creek bed with angular stone.
10-Jul-09	tr, jc	8.46	8.47	8.88	8.89	3	127	3	133	90	0	0%	0.00	0.8	O/W interface probe is working accurately
23-Sep-09	jc				8.89										J Clark changed pum run time from 45 minutes to 30 minutes.
6-Oct-09	tr, jc	8.08	8.09	8.88	8.89	3	244	3	250	117	0	0%	0.00	1.3	A skim of LNAPL and DNAPL were present, the thickness (not measureable) is estim
14-Jan-10	jc				8.89										J. Clark repaired air vent hose.
24-Feb-10	jc				8.89										Repaired hose.
26-Mar-10	jc				8.89										Fabric visible on east side of creek.
21-Apr-10		8.00	8.01	8.88	8.89	3	269	3	275	25	0	0%	0.00	0.1	A skim of LNAPL and DNAPL were present, the thickness (not measureable) is estim
21-Aug-10					8.89										Changed tubing.
21-Oct-10					8.89										Reset time.
	jc				8.89										Additional checks made by J. Clark on 5/20, 6/24, 7/22, 9/16, 11/18, 12/17, and 1/27/
7-Apr-11	tr, jc	4.27	4.28	8.88	8.89	3	1420	3	1427	1152	0	0%	0.00	3.3	A skim of LNAPL and DNAPL were present, the thickness (not measureable) is estim
16-Jun-11	jc	8.89	8.89	8.89	8.89	0	0	0	0						Tank pumped out. NAPL and water transported to offsite treatment facility.
18-Apr-12	el, jc	8.85	8.85	8.83	8.89	0	-6	19	12	-6	19	150%	0.06	0.0	Measured water and NAPL levels. Corrected depth to top of DNAPL and depth to bol
29-Apr-13	tr, jc	2.87	2.87	8.83	8.89	0	1840	19	1859	1846	1	0%	0.00	4.9	Estimate approximately 1/2 inch DNAPL. Corrected depth to bottom of tank measure
23-May-13	jc					0	0	0	0						Tank pumped out. NAPL and water transported to offsite treatment facility.
23-Apr-14	el, jc	7.58	7.58	8.82	8.89	0	383	22	404	383	22	5%	0.06	1.2	Estimate approximately 3/4 inch DNAPL. Corrected depth to bottom of tank measure
21-May-15	kh	6.95	6.95	8.80	8.88	0	571	25	596	188	3	2%	0.01	0.5	Measurements by Op-Tech
20-Apr-16	kh,rw	6.55	6.55	8.77	8.88	0	685	34	719	114	9	7%	0.03	0.4	Measurements by Op-Tech
20-Apr-17	kh, rf	6.49	6.49	8.71	8.88	0	685	52	738	0	19	100%	0.05	0.1	Measurements by GEI weighted cotton string (stain height). Changed 62 ft of dischar
29-Jun-17	mc					0			86						NAPL collection tank emptied by Allied Env. Services,
29-Sep-17 26-Oct-17	mc mc	8.60 8.60	8.60 8.60	8.60 8.60	8.88 8.88	0	0	86	00	0	86 2	100	0.93		Measurements by GEI using weighted cotton string and measured stain height. Differ Measurements by GEI. Bucket hung in tank contains ~3.5 gallons, approximately 50
15-Feb-18	mc	8.60	8.60	8.60	8.88	0	0	86.46	86	4.5	0.25	0%	0.00	0.0	Measurements by GEI. Bucket hung in tank contains 4.5 gallons, approximately 50 Measurements by GEI. Bucket hung in tank contains 4.5 gallons of water and 0.25 g
26-Apr-18	mc	8.20	8.20	8.60	8.88	0	124	86.46	210	4.5	0.25	5%	0.00	1.2	Measurements by GEI. Bucket hung in tank contains 4.5 gailons of water and 0.25 g Measurements by GEI. Bucket hung in tank contains ~4.75 gallons of water and 0.25
12-Jul-18	mc				8.88		2.00	2.00	4.00	2.00	2.00	50%			No measurements by GEI. National Fuel personel states that 3-5 gallons of oil/water (505
16-Aug-18	mc				8.88		2.00	2.00	4.00	2.00	2.00	50%			No measurements by GEI. National Fuel personel states that 3-5 gallons of oil/water (50%
20-Sep-18	mc	8.76	8.76	8.76	8.88	0	2	2.00	4	1.5	2.00	43%			Measurements by GEI. Bucket hung in tank contains ~1.5 gallons of water and 2 gallo
25-Oct-18	mc						2	2.00	4	2.00	2.00	50%			No measurements by GEI. National Fuel personel states that 3-5 gallons of oil/water (50%) Measurements by GEI. Bucket hung in tank contains ~2.5 gallons of NAPL. Pump wa
16-Jan-19	mc	8.76	8.76	8.76	8.88	0	2	2.50	3	2.0	2.50	100%	0.02	0.8	the close of the inspection. Consider increasing pump speed.
								Cumulative	e gallons :	5252	566	I			

s Notes
ate.
and 9/12.
24.
(11, 9/17, 9/25, 10/30, 11/18.
3/11, 4/12, 4/18.
s by NFG 5/11, 6/24, 7/28, 8/25, 10/06.
6/29, 7/26, 9/07.
/2006, 11/16/2006, 3/02/2007.
)/08 and 5/08/08. Tank pumped out.
. volume. Actual measurement 8.87.
stimated to be 0.01 ft.
stimated to be 0.01 ft. Damage to armor stone observed by sheet pile wall.
/27/11. No adjustments made.
stimated to be 0.01 ft.
bottom of tank measurements.
surement.
surement.
charge tubing.
ifferentiation between water and NAPL difficult with this small of a quantity
v 50% of which is NAPL, 50% water. Change pump sched to DST.
25 gallons of DNAPL.
0.25 gallons of DNAPL.
(50%/50%) mixture present in bucket hung in tank.
50%/50%) mixture present in bucket hung in tank.
gallons of DNAPL. (NAPL storage tank pumped May 2018) 50%/50%) mixture present in bucket hung in tank.
p was not running during inspection, but breaker was reset and was running at

# Scajaquada Creek DNAPL Recovery System Monitoring Log

# SOUTHERN DNAPL RECOVERY SYSTEM

	Field Measurements (by OWI probe) Calculations (total tank contents) *					Calculatio	ns (this pe	eriod recov	ery)						
Date	Initials	Manhole rim to top of LNAPL(ft)	Manhole rim to top of Water (ft) (estimated)	Manhole rim to top of DNAPL (ft)	Manhole rim to bottom of Tank (ft)	LNAPL (gal)	Water (gal)	DNAPL (gal)	Total (gal)	Water Increase (gal)	NAPL Increase (gal)	% NAPL	NAPL (gpd)	Ave Recovery in GPD	Operator's Notes
24-Jun-99	mrh	9.05	9.05	9.05	9.05	0	0	0	0	0	0	0%		0	90% construction complete, begin initial testing
29-Jun-99	mrh/day	6.80	6.80	9.05	9.05	0	695	0	695	695	0	0%		139	Complete initial system test, PW2003 has silt damage
23-Jul-99	mrh/day	6.80	6.80	9.05	9.05	0	695	0	695	0	0	0%		0	Recommence shakedown with peristaltic pump
30-Jul-99	day	6.34	6.34	8.95	9.05	0	806	31	837	111	31	22%	4.41	20	Shakedown, flow adjustment
26-Aug-99	jhe	5.90	5.90	8.73	9.05	0	874	99	973	68	68	50%	2.52	5	Routine system check, slow drip from tank bung noted (0.5 gpd?)
16-Sep-99	mrh/bdc	5.79	5.80	8.75	9.05	3	911	93	1007	37	-3			2	Significant (2 gpd?) DNAPL loss through bung drip, PW2003 reinstalled
28-Sep-99	mrh/cc	3.30	3.32	8.61	9.05	6	1633	136	1775	723	46	6%	3.86	64	Tank emptied (was full, pump off), bung replaced,
28-Sep-99	mrh/cc	9.05	9.05	9.05	9.05	0	0	0	0	0	0	0%		0	vault cleaned, flow setting reduced to 4.5
3-Oct-99	mrh	8.75	8.75	9.03	9.05	0	86	6	93	86	6	7%	1.24	19	Measurements are visual estimates only, flow setting reduced to 3.5
11-Oct-99	СС	8.75	8.75	9.03	9.05	0	86	6	93	0	0	0%		0	No flow observed, flow setting increased to 5.0
29-Oct-99	СС	6.81	6.81	8.98	9.05	0	670	22	692	584	15	3%	0.86	33	Flow setting decreased to 4.0
2-Dec-99	mrh/day	6.09	6.10	8.77	9.05	3	824	86	914	154	68	31%	2.00	7	Flow setting increased to 4.7 (24 gpd), timer installed/set for 1pm to 2pm operation
16-Dec-99	сс														Pump running but no flow, Timer reset for 3 hr per day operation
9-Mar-00	mrh/day	6.09	6.10	8.89	9.05	3	861	49	914	37	-37			0	PW2000 running but no flow, Peristaltic installed (2 hr/day), DNAPL thickened over time
11-Apr-00	mrh/day	4.71	4.73	8.82	9.05	6	1263	71	1340	401	25	6%	0.75	13	New peristaltic purchased/installed. Flow setting #7 (for 2 hr/day).
1-May-00	mrh/dms	4.62	4.64	8.80	9.05	6	1284	77	1368	22	6	22%	0.31	1	No flow (tubing collapsed). Repaired.
4-May-00	day/jc	4.62	4.64	8.80	9.05	6	1284	77	1368	0	0	0%		0	No flow (tubing leak). Tank emptied. System turned off.
8-May-00	mrh/jtf	9.05	9.05	9.05	9.05	0	0	0	0	0	0	0%		0	Original tubing replaced with silicon. System restarted at flow setting #3 (for 2 hr/day).
8-Jun-00	mrh/day	8.55	8.56	8.98	9.05	3	130	22	154	130	25	16%	0.80	5	Backfill settled around vault. Total depth shallow; measurements estimated. Tubing adjusted.
10-Jul-00	mrh/dms	8.10	8.11	8.90	9.05	3	244	46	293	114	25	18%	0.77	4	Tubing was worn; adjusted.
25-Aug-00	day	7.30	7.31	8.80	9.05	3	460	77	540	216	31	12%	0.67	5	Tubing adjusted.
20-Oct-00	mrh	6.25	6.26	8.64	9.05	3	735	127	865	275	49	15%	0.88	6	Tubing worn; adjusted.
30-Nov-00	mrh	5.75	5.77	8.55	9.05	6	858	154	1019	124	31	20%	0.75	4	Tubing worn; adjusted. Flow rate setting reduced from 3.0 to 1.5; timer not changed.
18-Jan-01	mrh	5.75	5.77	8.55	9.05	6	858	154	1019	0	0			0	Pump starts rough and sounds bad. Pump removed and sent in for repairs.
7-Feb-01	mrh/hs	5.75	5.77	8.55	9.05	6	858	154	1019	0	0	0%		0	Temporary FloJet pump installed but insufficient NPSH due to low creek elevation.
30-Mar-01	mrh	5.75	5.77	8.55	9.05	6	858	154	1019	0	0	0%		0	Peristaltic (geopump) installed, full speed, 600 rpm, system OK. NAPL is hi viscocity/settled.
10-Apr-01	mrh	5.70	5.72	8.51	9.05	6	861	167	1034	3	12	80%	1.12	1.4	3/16" id tubing replaced with 3/8" id tubing. Float switch replaced (plus relay).
18-May-01	dms/jc	5.65	5.68	8.52	9.05	9	877	164	1050	15	0	0%	0.00	0.4	Tubing worn and soft; adjusted.
30-Aug-01	mrh/hs	5.53	5.55	8.39	9.05	6	877	204	1087	0	37	100%	0.36	0.4	NAPL appears to be accumulated in well. Timer set to 3 hrs/day. Original peristaltic re-installed.
3-Oct-01	hs/jc	5.46	5.48	8.35	9.05	6	886	216	1108	9	12	57%	0.36	0.6	NAPL may still be accumulated in well. Timer increased to 4 hrs/day.
6-Nov-01	hs/jc	5.30	5.32	8.27	9.05	6	911	241	1158	25	25	50%	0.73	1.5	Additional NAPL purged from well after readings taken. Timer decreased to 3 hrs/day.
Ĺ		1	I		1		1	1	1			1	I.	1	

# SOUTHERN DNAPL RECOVERY SYSTEM

		Field Me	asurements	(by OWI	probe)	Calculati	ons (total ta	ank content	s) *	Calculatio	ns (this pe	riod recove	ery)		
Date	Initials	Manhole rim to top of LNAPL (ft)	Manhole rim to top of Water (ft) (estimated)	Manhole rim to top of DNAPL (ft)	Manhole rim to bottom of Tank (ft)	LNAPL (gal)	Water (gal)	DNAPL (gal)	Total (gal)	Water Increase (gal)	NAPL Increase (gal)	% NAPL	NAPL (gpd)	Ave Recovery in GPD	Operator's Notes
7-Feb-02	hs/jc	3.89	3.91	8.22	9.05	6	1331	256	1593	420	15	4%	0.17	4.7	Adjusted peristaltic tubing.
8-Mar-02	hs/jc	3.81	3.83	8.17	9.05	6	1340	272	1618	9	15	62%	0.53	0.9	Adjusted peristaltic tubing.
10-Apr-02	mrh	3.43	3.45	7.88	9.05	6	1368	361	1735	28	90	76%	2.71	3.6	Adjusted tubing. Installed piston pump for one day test (then removed). Timer increased to 4 hrs.
7-May-02	hs/jc	3.15	3.17	7.82	9.05	6	1436	380	1822	68	19	21%	0.69	3.2	Tank full.
7-May-02		9.05	9.05	9.05	9.05	0	0	0	0						Tank pumped out.
25-Jun-02	cd	6.00	6.02	9.02	9.05	6	926	9	942	926	15	2%	0.32	19.2	Depth's estimated. Pump set at #4, 3 hrs/day
2-Aug-02	mrh/jc	3.15	3.17	9.00	9.05	6	1800	15	1822	874	6	1%	0.16	23.2	Tank full, mostly water.
6-Sep-02	jc	3.15	3.17	9.00	9.05	6	1800	15	1822	0	0	0%		0.0	Tank Emptied.
6-Sep-02		9.05	9.05	9.05	9.05	0	0	0	0	0	0				
8-Oct-02	mrh/jc	8.98	8.98	8.98	9.05	0	0	22	22	0	22	100%	0.68	0.7	Pump removed for repair
18-Nov-02	cd	8.98	8.98	8.98	9.05	0	0	22	22	0	0	0%		0.0	Pump reinstalled
4-Feb-03	mrh/jc	4.32	4.32	8.95	9.05	0	1430	31	1460	1430	9	1%	0.12	18.4	Tank again full of mostly water (timer was left on manual?). Tank emptied.
4-Feb-03		9.05	9.05	9.05	9.05	0	0	0	0						
12-Mar-03	jc	9.00	9.00	9.00	9.05	0	0	15	15	0	15	100%	0.43	0.4	Pump running fast, so removed for evaluation/repair.
10-Apr-03	mrh/jc	9.00	9.00	9.00	9.05	0	0	15	15	0	0	0%		0.0	Pump reinstalled: runs fast/variable with no load, runs OK with flow load. Timer set to 30 min/day, speed 8.
23-Jul-03	mrh/jc	8.78	8.78	8.78	9.05	0	0	83	83	0	68	100%	0.51	0.7	Additional system checks/adjustments made by J Clark on 5/5, 5/20, 6/12, and 6/24.
23-Apr-04	mrh	8.05	8.06	8.55	9.05	3	151	154	309	151	74	33%	0.27	0.8	Additional system checks/adjustments made by NFG on 8/01, 8/06, 9/05, 9/08, 9/11, 9/17, 9/25, 10/30, 11/18.
24-Nov-04	jl,jc	7.31	7.32	8.54	9.05	3	377	157	537	225	3	1%	0.01	1.1	O/W Interface probe not acting precisely, actual DNAPL volume probably greater.
19-Apr-05	mh,jc,jl,sh	n 7.19	7.20	8.43	9.05	3	380	191	574	3	34	92%	0.23	0.3	Additional system checks/adjustments made by J Clark on 11/24, 1/20/2005, 3/7, 3/11, 4/12, 4/18.
27-Oct-05	mrh, jc	6.96	6.97	8.20	9.05	3	380	262	645	0	71	100%	0.37	0.4	New OWI probe, but readings inconsistent with previous readings. System checks by NFG 5/11, 6/24, 7/28, 8/25, 10/06.
22-Mar-06	mrh, jc	6.78	6.79	8.02	9.05	3	380	318	701	0	56	100%	0.38	0.4	Additional system checks by NFG 10/26/05, 12/14/05, 1/6/06, 2/24/06.
24-Oct-06	mrh, jc	4.90	4.91	7.38	9.05	3	763	516	1281	383	198	34%	0.91	2.7	Depth to NAPL reading is approximate. Additional system checks by NFG 5/11, 6/29, 7/26, 9/07.
2-Mar-07	jc, cb	3.36	3.37	7.15	9.05	3	1167	587	1757	404	71	15%	0.55	3.7	Pump turned off 3/02/07 because tank near full. Readings taken 4/25/07. Depth to DNAPL reading is approximate.
23-Jun-07		9.05	9.05	9.05	9.05	0	0	0	0						Tank pumped out.
30-Oct-07	dms, jc	8.55	8.56	9.01	9.05	3	139	12	154	139	15	10%	0.06	1.2	Depth to DNAPL reading is approximate.
13-May-08	dms, jc														Data appears to be invalid.
25-Mar-09	jl, dz	7.90	7.91	8.90	9.05	3	306	46	355	167	34	17%	0.07	0.4	O/W interface probe is working accurately
10-Jul-09	tr, jc	7.73	7.74	8.71	9.05	3	300	105	408	300	108	27%	1.01	0.2	O/W interface probe is working accurately
6-Oct-09	tr, jc	7.23	7.24	9.04	9.05	3	556	3	562	556	6	1%	0.07	0.2	A skim of LNAPL and DNAPL were present, the thickness (not measureable) is estimated to be 0.01 ft.
21-Apr-10	tr, jc	6.30	6.31	8.40	9.05	3	645	201	849	645	188	23%	0.96	0.3	A skim of LNAPL was present, the thickness (not measureable) is estimated to be 0.01 ft.
7-Apr-11	tr, jc	5.40	5.40	8.05	9.05	0	818	309	1127	173	105	38%	0.30	0.8	A skim of LNAPL was present, the thickness (not measureable) is estimated to be 0.01 ft.
16-Jun-11	jc	9.05	9.05	9.05	9.05	0	0	0	0						Tank pumped out. Water and NAPL shipped offsite for disposal.
18-Apr-12	el	6.60	6.60	8.50	9.05	0	587	170	756	587	170	22%	0.55	2.5	Corrected depth to top of DNAPL and depth to bottom of tank measurements
29-Apr-13	tr, jc	6.12	6.12	8.50	9.05	0	735	170	905	148	0	0%	0	0.4	DNAPL measurement duplicated and accurate. Corrected depth to bottom of tank measurement.
23-May-13	jc					0	0	0	0						Tank pumped out. Water and NAPL shipped offsite for disposal.
23-Apr-14	el, jc	8.38	8.40	8.40	9.10	6	0	216	222	0	222	100%	0.66	0.7	Corrected depth to bottom of tank measurement.
21-May-15	kh	8.28	8.30	8.30	9.06	6	0	235	241	0	19	100%	0.05	0.0	Measurements by Op-Tech
20-Apr-16	kh	6.55	6.55	7.96	9.16	0	435	371	806	435	148	29%	0.20	0.39	Measurements by Op-Tech: weighted rope indicates 1.2 ft of DNAPL in tank. OWI probe did not sense DNAPL
20-Apr-17	kh, rf	6.55	6.55	7.73	9.06	0	364	411	775	435	188	29%	0.17	0.39	Measurements by GEI using weighted cotton string and measured stain height.
16-May-17	mc														Removed approximately 90 feet of collection tubing in the recovery with new 0.5 inch diameter PEX tubing. Pumped 4 gallons of water from well.
29-Jun-17	mc														High pressure jet cleaning (water lance) used to clean/improve hydraulic communication in well screen. NAPL collection tank emptied by Allied Env. Services, collection piping
28-Sep-17	mc	8.86	8.86	8.86	9.06	0	0	62	62	0	62	100%	0.12	2.39	Measurements by GEI using weighted cotton string and measured stain height. Differentiation between water and NAPL difficult with this small of a quantity
26-Oct-17	mc	8.86	8.86	8.86											No measurements by GEI. A hole is burned through tubing at pump head. Tubing is replaced, and pumping 100% tar when started back up. Change pump sched to DST.
15-Feb-18	mc	8.86	8.86	8.86	9.06	0	0	62	62	0	trace	100%	trace	0.00	Measurements by GEI using weighted cotton string and measured stain height. Pump malfunction and less than 1/4 gallon DNAPL collected. Pump repaired.
26-Apr-18	mc	5.40	5.40	8.86	9.06	0	1068	67	1130	1	4	100%	trace		Measurements by GEI using weighted cotton string and measured stain height. 5 gal. liquid in hung bucket, ~4 gal DNAPL. >1000 gal pumped since 3/1. Turn pump rate dow
12-Jul-18	mc				9.06			5.00		trace	5.00	100%			No measurements by GEI. National Fuel states approximately 5 gallons of DNAPL accumulated in bucket hung in tank with bucket overflowing into tank.
16-Aug-18	mc				9.06			5.00		trace	5.00	100%			No measurements by GEI. National Fuel states approximately 5 gallons of DNAPL accumulated in bucket hung in tank with bucket overflowing into tank.
20-Sep-18	mc	9.05	9.05	9.05	9.06	0	0	0	3	trace	trace	trace	trace		Measurements by GEI. No NAPL accumulated in bucket. Pump rate increased from "30" to "60". (NAPL Storage tank pumped May 2018)
25-Oct-18	mc				9.06	0	0	5		trace	5.0	trace			No measurements by GEI. National Fuel states approximately 5 gallons of DNAPL accumulated in bucket hung in tank with bucket overflowing into tank.
16-Jan-19	mc	8.88	8.88	8.88	9.06	0	0	56	56	0	50.6	100%	0.43	0.47	Measurements by GEI. 5gal of DNAPL in bucket hung in tank with bucket overflowing into tank. No adjustments to the system are recommended.
								Cumulative	gallons :	12,336	2,589				

Cumulative gallons : 12,336 2,589 Water NAPL

n piping and yoult flooring walls cloaned
n piping and vault flooring walls cleaned.
ST.
ate down by 50%. Will check and re-evaluate.

Institutional and Engineering Controls Certification Forms



Enclosure 2 NEW YORK STATE DEPARTMENT OF ENVIRONMENTAL CONSERVATION Site Management Periodic Review Report Notice Institutional and Engineering Controls Certification Form



1

Site	Site Details No. 915141B	Box 1						
Site	Name NFG - Iroquois Gas/Westwood Pharm. Riparian							
City Cou Site	Address: Scajaquada Creek, Upstream of West Ave. Bridge Zip Code: 14213 /Town: Buffalo inty: Erie Acreage: 2.5							
Rep	oorting Period: February 15, 2018 to February 15, 2019							
		YES	NO					
1.	Is the information above correct?	X						
	If NO, include handwritten above or on a separate sheet.							
2.	<ul> <li>Has some or all of the site property been sold, subdivided, merged, or undergone a tax map amendment during this Reporting Period?</li> </ul>							
3.	Has there been any change of use at the site during this Reporting Period (see 6NYCRR 375-1.11(d))? $\hfill \Box$							
4.	Have any federal, state, and/or local permits (e.g., building, discharge) been issued for or at the property during this Reporting Period? $\hfill \square$							
	If you answered YES to questions 2 thru 4, include documentation or evidence that documentation has been previously submitted with this certification form.							
5.	Is the site currently undergoing development?		X					
		Box 2						
		YES	NO					
6.	Is the current site use consistent with the use(s) listed below? Commercial and Industrial	X						
7.	Are all ICs/ECs in place and functioning as designed?	X						
	IF THE ANSWER TO EITHER QUESTION 6 OR 7 IS NO, sign and date below a DO NOT COMPLETE THE REST OF THIS FORM. Otherwise continue.	Ind						
A C	orrective Measures Work Plan must be submitted along with this form to address th	nese issi	ues.					
Sig	nature of Owner, Remedial Party or Designated Representative Date							

SITE NO. 91514	1B	Box 3
Descrip	tion of Institutional Controls	
Parcel	<u>Owner</u> No Owner	Institutional Control O&M Plan Monitoring Plan
completed betwee Scajaquada Creek foot reach of the c	n 1996 and 2002 and included: (1) insta x; (2) excavation of contaminated sedime	or this site. The remedial action at this site was allation of the sheet pile wall along the eastern bank of ent and debris; (3) construction of a cap along a 1,600 recovery systems. There is no SBL identification for
Descrip	tion of Engineering Controls	Box 4
Parcel	<u>Engineering C</u> Subsurface Ba Cover System	arriers
by sand, geotextile substrata of the cr	e and anchoring stone; and two DNAPL	ed cap that consists of a geosynthetic clay liner overlain recovery systems to extract DNAPL from the cap, creek banks and DNAPL recovery systems are

	Box 5
	Periodic Review Report (PRR) Certification Statements
۱.	I certify by checking "YES" below that:
	a) the Periodic Review report and all attachments were prepared under the direction of, and reviewed by, the party making the certification;
	b) to the best of my knowledge and belief, the work and conclusions described in this certification are in accordance with the requirements of the site remedial program, and generally accepted engineering practices; and the information presented is accurate and compete.
	YES NO
2.	If this site has an IC/EC Plan (or equivalent as required in the Decision Document), for each Institutional or Engineering control listed in Boxes 3 and/or 4, I certify by checking "YES" below that all of the following statements are true:
	(a) the Institutional Control and/or Engineering Control(s) employed at this site is unchanged since the date that the Control was put in-place, or was last approved by the Department;
	(b) nothing has occurred that would impair the ability of such Control, to protect public health and the environment;
	(c) access to the site will continue to be provided to the Department, to evaluate the remedy, including access to evaluate the continued maintenance of this Control;
	(d) nothing has occurred that would constitute a violation or failure to comply with the Site Management Plan for this Control; and
	(e) if a financial assurance mechanism is required by the oversight document for the site, the mechanism remains valid and sufficient for its intended purpose established in the document.
	YES NO
	$\mathbf{X}$ $\Box$
	IF THE ANSWER TO QUESTION 2 IS NO, sign and date below and DO NOT COMPLETE THE REST OF THIS FORM. Otherwise continue.
	A Corrective Measures Work Plan must be submitted along with this form to address these issues.
-	Signature of Owner, Remedial Party or Designated Representative Date

#### IC CERTIFICATIONS SITE NO. 915141B

Box 6

#### SITE OWNER OR DESIGNATED REPRESENTATIVE SIGNATURE

I certify that all information and statements in Boxes 1,2, and 3 are true. I understand that a false statement made herein is punishable as a Class "A" misdemeanor, pursuant to Section 210.45 of the Penal Law.

I JAY LESCH at	6363 Main ST. Williams Ville NY 14221 print business address
am certifying as <i>OWNER</i>	(Owner or Remedial Party)
for the Site named in the Site Details Section	3/12/19

#### IC/EC CERTIFICATIONS

#### **Professional Engineer Signature**

Box 7

I certify that all information in Boxes 4 and 5 are true. I understand that a false statement made herein is punishable as a Class "A" misdemeanor, pursuant to Section 210.45 of the Penal Law.

Kelly R Mc Intosh at 90 B John Muir Drive, Amherst, N print name print business address 14 14228 STATE (Owner of Remedial Party) am certifying as a Professional Engineer for the Nathana / LICENSED Ш ENGIN No. 6801 PROFESSIONAL Signature of Professional Engineer, for the Owner or Stamp Remedial Party, Rendering Certification (Required for PE)