# **PERIODIC REVEW REPORT**

For

300-320 SCAJ LLC 5102 Donnington Road Clarence, New York

Site

Saginaw – Buffalo Site Site Number 915152 320 Scajaquada Street Buffalo, New York

Dates Covered by Report May 4, 2022 to August 31, 2023

Prepared by:



10 Jones Avenue Rochester, New York 14608 585-313-9683

## **Table of Contents**

1.0	Summ	ary1		
	1.1 1.2 1.3	Site Summary		
	1.4	Recommendations		
2.0	Site O	verview5		
	2.1 2.2	Site Location		
3.0	Remed	ly Performance, Effectiveness, and Protectiveness		
4.0	IC/EC	Plan Compliance Report7		
	4.1 4.2	IC/EC Requirements and Compliance		
5.0	Monito	oring Plan Compliance Report7		
	5.1 5.2 5.3 5.4	Monitoring Plan Compliance Report7Monitoring Completed During Reporting Period8Monitoring Deficiencies8Conclusions and Recommendations for Changes8		
6.0	Operat	ion & Maintenance (O&M) Plan Compliance Report8		
7.0	Overall PRR Conclusions and Recommendations			

#### **Appendices**

Appendix A:	Annual Site Wide Inspection Forms and Photographs
Appendix B:	Annual Storm Sewer Sampling Summary
Appendix C:	Laboratory Reports
Appendix D:	Institutional Control/ Engineering Control (IC/EC) Certification
Appendix E:	Site Map
Appendix F:	Site Survey

# Section 1

NEU-VELLE LLC

# Summary

#### 1.0 Summary

NEU-VELLE LLC (NEU-VELLE) has prepared this Site Management (SM) Periodic Review Report (PRR) for the Saginaw-Buffalo Site (Site) located at 320 Scajacuada Street in the City of Buffalo, Erie County. The Site is defined as the former Parking Lot #4 associated with the former General Motors and American Axle & Manufacturing (AAM) facility that manufactured axles and drive-train components for cars and trucks. The Site covers an area of approximately 7.248 acres (SBL Parcel No. 101.24-1-3.1) and is included in the New York Registry of Inactive Hazardous Waste Sites (Site No. 915152). Site Institutional Controls (ICs) and Engineering Controls (ECs) were adhered to over the PRR reporting period and continue to be effective in maintaining the remedial objectives. No changes to the established SMP or recommended during the next PRR reporting period.

#### **1.1 Site Summary**

General Motors (GM) purchased several parcels in the mid-1960s and constructed Parking Lot #4 which is the current listed Site. In 1989 during a spill cleanup of industrial oil by GM, excavated soil was found to contain Polychlorinated Biphenyls (PCBs). The Site was sold to AAM in 1994 along with the main facility west of the railroad right of way. As part of this conveyance, a deed restriction was placed on the property limiting it for use for industrial purposes only. GM-Saginaw Division, the previous owner of the Site, entered into a Consent Order in 1995 and a Final Site Investigation Report and Engineering Evaluation Report of Alternatives was completed in 1997. A Record of Decision (ROD) was issued in March 1998 which required: 1) The further removal of PCB contaminated soil, water and oil; 2) Maintenance of the pavement to reduce infiltration and provided a barrier to lead contaminated soil; and 3) Long-term monitoring and maintenance. Remediation (the "removal of PCB contaminated soil, water and oil") of the Site was completed in 1998 and a long-term operation and maintenance (O&M) plan is in place. The property was sold to East Delavan Property, LLC in October 2008.

The paved portion of the Site is currently utilized periodically by the City of Buffalo for training school bus drivers. There remainder of the Site is vacant. The property was purchased by 300-320 SCAJ LLC on February 9, 2023. In addition, the monitoring wells were re-surveyed by the previous consultant in November 2022.

#### **1.2** Effectiveness of the Remedial Program

Remediation of the Site was completed between 1998 and 2000 and included:

- Dewatering of an approximately 1-acre area surrounding the former Wastewater Treatment Plant and on-site water treatment, confirmatory effluent sampling and analysis, and batch discharge to the Buffalo Sewer Authority (BSA) sanitary sewer system;
- Excavating fill/soil containing greater than the site cleanup goal of 10 parts per million (ppm) PCBs in the OU1 area, and confirmatory sampling;
- Transporting excavated materials off-site for treatment and disposal;
- Backfilling of the OU1 excavation with clay soil; and
- Paving the excavation area (OU1) and repaving of the OU2 area which was the remainder of the Parking Lot No. 4.

The remedial program was effective and long-term site monitoring requirements were established requiring:

- Pavement inspection and maintenance conducted on an annual basis to ensure that the integrity of the asphalt surface has been maintained;
- Visual inspection of storm sewer manhole covers and manhole risers for structural damage;
- Groundwater sampling of Site monitoring wells for PCBs, Total Lead, and Soluble Lead; and
- Storm sewer sampling from Manhole #2 for PCBs and Total Lead.

Groundwater sampling has been conducted on a biennial basis since 2008 and storm sewer sampling (Manhole #2) on an annual basis.

A requirement for the collection of groundwater samples for per and polyfluoroalkyl substances (PFAS) and 1,4-Dioxane at monitoring wells MW-204 (PFAS only), MW-211, and MW-202 were added to the biennial program in March 2021. The next biennial Groundwater sampling will be conducted in October 2023 and included in the subsequent PRR (2024).

Pavement inspection, storm sewer visual inspection, and storm sewer sampling is conducted on an annual basis.

#### **1.2.1** Progress During the Reporting Period

The cover system is intact and functioning as intended. NEU-VELLE conducted the annual inspection in August 2023 and completed the required inspection form (Appendix A). Photographs of the inspection are included in Appendix A. During this reporting period the property was purchased by 300-320 SCAJ LLC on February 9, 2023. In addition, the monitoring wells were re-surveyed by the previous consultant in November 2022.

Biennial groundwater sampling was completed in November 2021 (next sampling to be conducted in October 2023). A tabular summary of groundwater and storm sewer sampling results was provided in the previous PRR.

The annual storm sewer sampling from Manhole #2 was conducted in Augst 2023. Samples were collected for PCB and Total Lead analysis. A summary of the storm sewer results is provided in Appendix B. No sediment was observed within the manholes during the sampling event and therefore, no sediment samples were collected.

No groundwater use, change of use, or excavations occurred onsite during the reporting period.

The EQuIS formatted EDD from the August 2023 annual storm sewer sampling was submitted to the NYSDEC on September 25, 2023. The laboratory report is provided as Appendix C.

#### **1.2.2** Progress to Remedial Objectives for the Site

The Remedial Objectives (ROs) for the Site as established in the March 1998 Record of Decision (ROD) have been achieved and the Site has been in long-term monitoring since 2002. The ROs were as follows:

- To the extent practicable, reduce the potential for human contact with PCBs and lead impacted soils;
- Prevent or greatly reduce the potential for migration of contaminants via surface run-off and on-site drain lines;
- Prevent, to the extent practicable, migration of contaminants at the site to the Scajaquada Creek Drain; and
- To the extent practicable, provide for attainment of SCGs in groundwater.

#### 1.3 Compliance

There were no areas of potential non-compliance identified during the reporting period.

#### **1.4 Recommendations**

There are no recommended changes to the SMP at this time.

Section 2

NEU-VELLE LLC

**Site Overview** 

#### 2.0 Site Overview

#### 2.1 Site Location

The Site is located at 320 Scajacuada Street in the City of Buffalo, Erie County. The Site is defined as the former Parking Lot #4 associated with the former General Motors and American Axle & Manufacturing (AAM) facility that manufactured axles and drive-train components for cars and trucks. The Site covers an area of approximately 7.248 acres and is included in the New York Registry of Inactive Hazardous Waste Sites (Site No. 915152). Currently the site is used for bus driver training and consists of an asphalt parking area. In addition, the site houses a decommissioned wastewater treatment facility which is scheduled for demolition/removal.

#### 2.2 Chronology of the Remedial Program

GM and NYSDEC entered on Order on Consent (Index #B9-0410-92-09), effective February 2, 1995, pursuant to which GM performed an Interim Remedial Measure (IRM) at OU1 and conducted a Site Investigation and Engineering Evaluation of Alternatives in both OU1 and OU2. Based upon the Engineering Evaluation of Alternatives Report prepared by Wehran-New York, Inc. (ENCOR), NYSDEC prepared a Proposed Remedial Action Plan, which it submitted for public comment in February 1998.

NYSDEC selected a final remedial alternative for the Site in a ROD that was issued in March 1998. A Remedial Design (RD) Report was prepared by EMCON to implement the ROD-selected remedial alternatives at the Site. The RD Report was approved by the NYSDEC, and remedial activities were conducted between July 1998 and March 2000.

Section 3

NEU-VELLE LLC

# Remedy Performance, Effectiveness, and Protectiveness

#### 3.0 Remedy Performance, Effectiveness, and Protectiveness

The performance, effectiveness, and protectiveness of the remedy are verified through evaluating each of the primary remedial measures.

- The pavement and structural integrity of the sewer system remain in good condition at the Site based on a visual evaluation. The next annual inspection will be conducted in June 2024
- Groundwater samples in accordance with the O&M plan will be collected in October 2023. In addition to routine biennial sampling for PCBs, Total Lead, and Soluble Lead, MW-204 will also be sampled for PFAS and MW-211 and MW-202 will also be sampled for PFAS and 1,4-Dioxane.
- Sewer samples in accordance with the O&M plan will be collected in June 2024.

Section 4

NEU-VELLE LLC

# **IC/EC Plan Compliance Report**

#### 4.0 IC/EC Plan Compliance Report

#### 4.1 IC/EC Requirements and Compliance

A series of IC's have been developed and are being adhered to at the Site and include:

- Inspection and maintenance of Parking Lot #4.
- Groundwater and sewer monitoring in accordance with the April 2001 O&M
- Manual and subsequent modifications to the O&M Manual in January 2004 and September 2008.

#### 4.1.1 Controls

Engineering controls (ECs) developed for the Site consist of an asphalt pavement cover system.

#### 4.1.2 Status

The Site IC/ECs are all currently active and in force.

#### 4.1.3 Corrective Measures

There are no corrective measures proposed at this time.

#### 4.2 IC/EC Certification

The IC/EC certifications are provided in Enclosure A.

# Section 5

NEU-VELLE LLC

# **Monitoring Plan Compliance Report**

#### 5.0 Monitoring Plan Compliance Report

#### 5.1 Monitoring Plan Compliance Report

Routine Site Monitoring includes annual pavement inspection, annual visual inspection of sewer structure integrity, annual storm sewer sample collection, biennial groundwater sample collection, and periodic certification.

#### 5.2 Monitoring Completed During Reporting Period

NEU-VELLE conducted the annual inspection August 2023 and completed the required inspection form (Appendix A). The cover system remains in good condition.

Groundwater sampling for PCBs, Total Lead, and Soluble Lead was conducted in November 2021. Sampling for PFAS and 1,4-Dioxane was conducted at select monitoring wells.

Storm sewer sampling from Manhole #2 for PCBs and Total Lead was conducted in August 2023. A summary of the storm sewer results is provided in Table 2 of Appendix B.

Laboratory analytical results for samples collected during the reporting period are provided in Appendix C and the EDDs formatted for the NYSDEC Environmental Information Management System (EIMS) were submitted to the NYSDEC database on September 25, 2023.

There were no emergencies or unforeseen failures of established ECs that would require nonroutine inspections.

#### 5.3 Monitoring Deficiencies

No monitoring deficiencies were noted during the reporting period.

#### 5.4 Conclusions and Recommendations for Changes

There are no recommendations for changes at this time.

# Section 6

NEU-VELLE LLC

# **Operation & Maintenance (O&M) Plan Compliance Report**

#### 6.0 Operation & Maintenance (O&M) Plan Compliance Report

The Site remedy does not rely on any mechanical systems to protect public health and the environment; therefore, an O&M Plan Compliance Report is not applicable to this PRR.

# Section 7

NEU-VELLE LLC

# **Overall PRR Conclusions and Recommendations**

#### 7.0 Overall PRR Conclusions and Recommendations

Site IC/ECs remain in place and effective in maintaining the remedial objectives. No changes to the established SMP are recommended during the next PRR reporting period.

# **Appendix A**

NEU-VELLE LLC

# Annual Site Wide Inspection Forms and Photographs

#### ANNUAL INSPECTION FORM

Inspection Date: 8/23/23 Inspected By: Albert G. Lyons, Jr. (NEU-VELLE LLC)

#### PAVEMENT (Identify any damaged areas on site sketch)

1. 2. 3. 4. 5. 6.	<ul> <li>Cracked Areas</li> <li>Settled Areas</li> <li>Potholes</li> <li>Heaving</li> <li>Plow Damage</li> <li>Drainage</li> </ul>	Yes Yes Yes Yes Goodx	No <u>x</u> No <u>x</u> No <u>x</u> No <u>x</u> Poor	
7.	. Condition of Surface Sealing	Explain: Good <u>x</u> Explain: Surface is in good shape.	Poor No deep fissures in sealant. Photos colle	cted.
STORM SEWERS 1.	Condition of Manhole Risers	Good <u>x</u> Poo Explain:	r	
2.	Sediment in Main	None <u>x</u> omments: <u>No sediment visible in N</u>	Avg (1-4") 1H #1 or MH#2. Very low_flow.	Avg (>4")

#### MONITORING WELLS

	MW-1	MW-5	MW-201	MW-202	MW-203	MW-204	MW-205	MW-206	MW-208	MW-209	MW-210	MW-211
Is protective casing in good condition?	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
Is flush mount casing in good condition?	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
Are casing labeled?	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
Is concrete surface seal in good condition?	Yes	Yes	Yes	Yes	Yes	Yes	Yes	No	Yes	Yes	Yes	Yes
Is protected pad in good condition?	Yes	Yes	Yes	Yes	Yes	Yes	Yes	No	Yes	Yes	Yes	Yes
Are locks present?	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
Are lock in good condition?	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
Is riser in good condition?	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
Are J-plugs present?	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes

Annual Inspection	Photo Date: Project:		
2022-2023 PRR	August 2023	Saginaw – Buffalo Site	
		Site No. 915152	
Photo No. 1			
Direction Photo	-		
Taken:		and the second	
Looking North	and the second second		
		and the second se	
		and a second sec	
Description:			
Description.			
Typical, Pavement in		1 and the second	
good condition.			
0	and an and and		
	the last	and all and the second	
	1	The second se	
	and the second		
		CARLAN AN AN	
	and a spectra and		
	Them be at		
A second to an estimate	Dhate Date:		
Annual Inspection	Photo Date:	Project:	
Annual Inspection 2022-2023 PRR	Photo Date: August 2023	Project: Saginaw – Buffalo Site Site No. 915152	
Annual Inspection 2022-2023 PRR Photo No. 2	Photo Date: August 2023	<b>Project:</b> Saginaw – Buffalo Site Site No. 915152	
Annual Inspection 2022-2023 PRR Photo No. 2 Direction Photo	Photo Date: August 2023	<b>Project:</b> Saginaw – Buffalo Site Site No. 915152	
Annual Inspection 2022-2023 PRR Photo No. 2 Direction Photo Taken:	Photo Date: August 2023	Project: Saginaw – Buffalo Site Site No. 915152	
Annual Inspection 2022-2023 PRR Photo No. 2 Direction Photo Taken: Looking southwest.	Photo Date: August 2023	Project: Saginaw – Buffalo Site Site No. 915152	
Annual Inspection 2022-2023 PRR Photo No. 2 Direction Photo Taken: Looking southwest.	Photo Date: August 2023	Project: Saginaw – Buffalo Site Site No. 915152	
Annual Inspection 2022-2023 PRR Photo No. 2 Direction Photo Taken: Looking southwest.	Photo Date: August 2023	Project: Saginaw – Buffalo Site Site No. 915152	
Annual Inspection 2022-2023 PRR Photo No. 2 Direction Photo Taken: Looking southwest.	Photo Date: August 2023	Project: Saginaw – Buffalo Site Site No. 915152	
Annual Inspection 2022-2023 PRR Photo No. 2 Direction Photo Taken: Looking southwest.	Photo Date: August 2023	Project: Saginaw – Buffalo Site Site No. 915152	
Annual Inspection 2022-2023 PRR Photo No. 2 Direction Photo Taken: Looking southwest. Description:	Photo Date: August 2023	Project: Saginaw – Buffalo Site Site No. 915152	
Annual Inspection 2022-2023 PRR Photo No. 2 Direction Photo Taken: Looking southwest. Description:	Photo Date: August 2023	Project: Saginaw – Buffalo Site Site No. 915152	
Annual Inspection 2022-2023 PRR Photo No. 2 Direction Photo Taken: Looking southwest. Description: Typical. Pavement in	Photo Date: August 2023	Project: Saginaw – Buffalo Site Site No. 915152	
Annual Inspection 2022-2023 PRR Photo No. 2 Direction Photo Taken: Looking southwest. Description: Typical. Pavement in good condition.	Photo Date: August 2023	Project: Saginaw – Buffalo Site Site No. 915152	
Annual Inspection 2022-2023 PRR Photo No. 2 Direction Photo Taken: Looking southwest. Description: Typical. Pavement in good condition.	Photo Date: August 2023	Project: Saginaw – Buffalo Site Site No. 915152	
Annual Inspection 2022-2023 PRR Photo No. 2 Direction Photo Taken: Looking southwest. Description: Typical. Pavement in good condition.	Photo Date: August 2023	Project: Saginaw – Buffalo Site Site No. 915152	
Annual Inspection 2022-2023 PRR Photo No. 2 Direction Photo Taken: Looking southwest. Description: Typical. Pavement in good condition.	Photo Date: August 2023	Project: Saginaw – Buffalo Site Site No. 915152	
Annual Inspection 2022-2023 PRR Photo No. 2 Direction Photo Taken: Looking southwest. Description: Typical. Pavement in good condition.	Photo Date: August 2023	Project: Saginaw – Buffalo Site Site No. 915152	
Annual Inspection 2022-2023 PRR Photo No. 2 Direction Photo Taken: Looking southwest. Description: Typical. Pavement in good condition.	Photo Date: August 2023	Project: Saginaw – Buffalo Site Site No. 915152	
Annual Inspection 2022-2023 PRR Photo No. 2 Direction Photo Taken: Looking southwest. Description: Typical. Pavement in good condition.	Photo Date: August 2023	Project: Saginaw – Buffalo Site Site No. 915152	

#### Appendix A – Annual Inspection Photolog



#### **Appendix A – Annual Inspection Photolog**

Annual Inspection	Photo Date:	Project:
2022-2023 PRR	August 2023	Saginaw – Buffalo Site
		Site No. 915152
Photo No. 1		
Direction Photo	h	The second se
Taken:		
Looking west	~	Æ.
	the second	A Contraction of the second seco
Description:	C. All Photo	
Description.		NI N
Typical. Pavement in		
good condition.		
-		(The man have been a start of the start of t
		The second states the
	and the second second	
	and the	The second s
		the state of the s
		A State of the second sec
Annual Inspection	Photo Date:	Broject:
Annual Inspection	Photo Date:	Project: Saginaw – Buffalo Site
Annual Inspection 2022-2023 PRR	Photo Date: August 2023	Project: Saginaw – Buffalo Site Site No. 915152
Annual Inspection 2022-2023 PRR Photo No. 2	Photo Date: August 2023	<b>Project:</b> Saginaw – Buffalo Site Site No. 915152
Annual Inspection 2022-2023 PRR Photo No. 2 Direction Photo	Photo Date: August 2023	<b>Project:</b> Saginaw – Buffalo Site Site No. 915152
Annual Inspection 2022-2023 PRR Photo No. 2 Direction Photo Taken:	Photo Date: August 2023	Project: Saginaw – Buffalo Site Site No. 915152
Annual Inspection 2022-2023 PRR Photo No. 2 Direction Photo Taken: Looking south.	Photo Date: August 2023	Project: Saginaw – Buffalo Site Site No. 915152
Annual Inspection 2022-2023 PRR Photo No. 2 Direction Photo Taken: Looking south.	Photo Date: August 2023	Project: Saginaw – Buffalo Site Site No. 915152
Annual Inspection 2022-2023 PRR Photo No. 2 Direction Photo Taken: Looking south.	Photo Date: August 2023	Project: Saginaw – Buffalo Site Site No. 915152
Annual Inspection 2022-2023 PRR Photo No. 2 Direction Photo Taken: Looking south.	Photo Date: August 2023	Project: Saginaw – Buffalo Site Site No. 915152
Annual Inspection 2022-2023 PRR Photo No. 2 Direction Photo Taken: Looking south.	Photo Date: August 2023	Project: Saginaw – Buffalo Site Site No. 915152
Annual Inspection 2022-2023 PRR Photo No. 2 Direction Photo Taken: Looking south. Description:	Photo Date: August 2023	Project: Saginaw – Buffalo Site Site No. 915152
Annual Inspection 2022-2023 PRR Photo No. 2 Direction Photo Taken: Looking south. Description:	Photo Date: August 2023	Project: Saginaw – Buffalo Site Site No. 915152
Annual Inspection 2022-2023 PRR Photo No. 2 Direction Photo Taken: Looking south. Description: Typical. Pavement in good condition	Photo Date: August 2023	Project: Saginaw – Buffalo Site Site No. 915152
Annual Inspection 2022-2023 PRR Photo No. 2 Direction Photo Taken: Looking south. Description: Typical. Pavement in good condition.	Photo Date: August 2023	Project: Saginaw – Buffalo Site Site No. 915152
Annual Inspection 2022-2023 PRR Photo No. 2 Direction Photo Taken: Looking south. Description: Typical. Pavement in good condition.	Photo Date: August 2023	Project: Saginaw – Buffalo Site Site No. 915152
Annual Inspection 2022-2023 PRR Photo No. 2 Direction Photo Taken: Looking south. Description: Typical. Pavement in good condition.	Photo Date: August 2023	<image/>
Annual Inspection 2022-2023 PRR Photo No. 2 Direction Photo Taken: Looking south. Description: Typical. Pavement in good condition.	Photo Date: August 2023	<image/>
Annual Inspection 2022-2023 PRR Photo No. 2 Direction Photo Taken: Looking south. Description: Typical. Pavement in good condition.	Photo Date: August 2023	<image/>
Annual Inspection 2022-2023 PRR Photo No. 2 Direction Photo Taken: Looking south. Description: Typical. Pavement in good condition.	Photo Date: August 2023	<image/>
Annual Inspection 2022-2023 PRR Photo No. 2 Direction Photo Taken: Looking south. Description: Typical. Pavement in good condition.	Photo Date: August 2023	<image/>

#### Appendix A – Annual Inspection Photolog

**Appendix B** 

NEU-VELLE LLC

# **Annual Storm Sewer Sampling Summary**

#### Annual Storm Sewer Sampling Saginaw Site (Site #915152) August 2023

#### **SMP** Constituents

Sample Location:MH-2Sample Date:8/23/23

Constituent	Result
Metals (ug/L)	
Lead (Total)	39J
PCBs (ug/L)	
PCB - 1016	U<0.5
PCB - 1221	U<1.0
PCB - 1232	U<0.5
PCB - 1242	U<0.5
PCB - 1248	U<0.5
PCB - 1254	U<0.5
PCB - 1260	U<0.5

- U: Analyte not detected above reporting limit shown
- J: Estimated value

# Appendix C

NEU-VELLE LLC

# **Laboratory Report**



Al Lyons Neu-Velle LLC 10 Jones Avenue Rochester, NY 14608

#### Laboratory Results for: Saginaw-Buffalo

Dear Al,

Enclosed are the results of the sample(s) submitted to our laboratory August 18, 2023 For your reference, these analyses have been assigned our service request number **R2307578**.

All testing was performed according to our laboratory's quality assurance program and met the requirements of the TNI standards except as noted in the case narrative report. Any testing not included in the lab's accreditation is identified on a Non-Certified Analytes report. All results are intended to be considered in their entirety. ALS Environmental is not responsible for use of less than the complete report. Results apply only to the individual samples submitted to the lab for analysis, as listed in the report. The measurement uncertainty of the results included in this report is within that expected when using the prescribed method(s), and represented by Laboratory Control Sample control limits. Any events, such as QC failures or Holding Time exceedances, which may add to the uncertainty are explained in the report narrative or are flagged with qualifiers. The flags are explained in the Report Qualifiers and Definitions page of this report.

Please contact me if you have any questions. My extension is 7475. You may also contact me via email at Meghan.Pedro@alsglobal.com.

Respectfully submitted,

#### ALS Group USA, Corp. dba ALS Environmental

Mighan Redio

Meghan Pedro Project Manager



# Narrative Documents

ALS Environmental—Rochester Laboratory 1565 Jefferson Road, Building 300, Suite 360, Rochester, NY 14623 Phone (585) 288-5380 Fax (585) 288-8475 www.alsglobal.com



Client:Neu-Velle LLCProject:Saginaw-BuffaloSample Matrix:Water

Service Request: R2307578 Date Received: 08/18/2023

#### **CASE NARRATIVE**

All analyses were performed consistent with the quality assurance program of ALS Environmental. This report contains analytical results for samples for the Tier level IV requested by the client.

#### Sample Receipt:

One water sample was received for analysis at ALS Environmental on 08/18/2023. Any discrepancies upon initial sample inspection are annotated on the sample receipt and preservation form included within this report. The samples were stored at minimum in accordance with the analytical method requirements.

#### <u>Semivoa GC:</u>

Method 8082A, 08/28/2023: The upper control limit was exceeded for one or more analytes in the Continuing Calibration Verification (CCV). The field samples analyzed in this sequence did not contain the analyte(s) in question above the Method Reporting Limit (MRL). Since the exceedance equates to a potential high bias, the data quality was not significantly affected and no further corrective action was taken.

Method 8082A, 815673s: The control limits were exceeded for one or more surrogates due to matrix interferences. Due to the presence of non-target background components that prevented adequate resolution of the surrogate, accurate quantitation was not possible. No further corrective action was appropriate.

#### Metals:

Approved by

No significant anomalies were noted with this analysis.

Mighan Redio

Date

08/31/2023



# Sample Receipt Information

ALS Environmental—Rochester Laboratory 1565 Jefferson Road, Building 300, Suite 360, Rochester, NY 14623 Phone (585) 288-5380 Fax (585) 288-8475 www.alsglobal.com

Client:Neu-Velle LLCProject:Saginaw-Buffalo

#### SAMPLE CROSS-REFERENCE

<u>SAMPLE #</u>	CLIENT SAMPLE ID	DATE	TIME
R2307578-001	MH-2-081823	8/18/2023	0915

# Chain of Custody / Analytical Request Form

7. NaHSO4 5. Zn Acet. 3. H2SO4 Notes: 6. MeOH 4. NAOH 2. HNO3 8. Other Invoice To: 📢 Same as Report To) 0. None Metals: RCRA 8•PP 13•TAL 23•TCLP•Other (List) VOA/SVOA Report List: TCL • BTEX • TCLP • 1. HCI 5 CP-51/Stars •THM • Other: Page SR#: Company: ddress: Contact: Phone: # Od Email: 0727 JATOT X 70780 Metals, Dissolved - Field / In-Lab Filter **Report Requirements** Tier II/Cat A -Results/QC 1565 Jefferson Road, Building 300, Suite 360 • Rochester, NY 14623 • +1 585 288 5380 • alsglobal.com Received By: Metals, Total - Select Below Validation Report w/. Data X\_Tier IV/Cat B - Data 5 EDD: X Yes No EDD Type: EQ UIS 8121 • 1CLP - sebicides -C808) 2829 809  $\mathbf{\lambda}$ R2307578 Pesticides - 8081 • 608 • TCLP Relinquished By: GC/MS SVOA - 8270 • 625 • TCLP 92740121000 - 826000224022401216 **Turnaround Requirements** Standard (10 Business Days) Preservative sasm/sm Rush (Surcharges Apply) \*Please Check with your PM\* Number of Containers n \*Subject to Availability\* 2 2 2 Q - ₹ xinteM S Page 6 of 30 Received By: ALL SHADED AREAS MUST BE COMPLETED BY THE Date Required: 0915 Time NY, MA, PA, CT, Other: Project Name: Sagin a - Buthalo Project Number: **CLIENT / SAMPLER** 8/10/25 Date Relinquished By: Sample Collection Information: State Samples Collected (Circle or Write): Sampler's Signature: ß ALS Quote #: Email CC: Email CC: Received-By MH - 2 - 081823 JULY IN Sample ID: 14608 ai e ver-velle, con Relinquished By: 1045 AVE LVOAS rev-velle Report To: Special Instructions / Comments: 2 C L 585-513- 283 とく Date/Time **Y/11/23** Jones 2~077 Ì Veu-veile Redered Signature Printed Name Company Lab ID 2 (ALS) E E

© 2012 by ALS Group

Distribution: White - Lab Copy; Yellow - Return to Originator

	R2307578 5					
(ALS) Cooler Receipt and Preservation Check Form						
Project/Client Neu-VeleFolder Number						
Cooler received on 8 18/23 by: MU COURIER: ALS UPS FEDEX	VELOCITY CLIENT					
1 Were Custody seals on outside of cooler? Y (N) 5a Perchlorate samples have requir	red headspace? Y N (NA)					
2 Custody papers properly completed (ink, signed)? (Y) N 5b Did VOA vials, Alk, or Sulfide have sig* bubbles? Y N (NA)						
3 Did all bottles arrive in good condition (unbroken)? YN 6 Where did the bottles originate?	(ALS/ROC) CLIENT					
4 Circle: Wet Re, Dry Ice Gel packs present? Y N 7 Soil VOA received as: Bulk	Encore 5035set NA)					
8. Temperature Readings Date: 8/18/23 Time: 11:13 ID: IR#12 (R#11)	From: Temp Blank Sample Bottle					
Observed Temp (°C) 16.3						
Within 0-6°C?     Y (N)     Y N     Y N     Y N	Y N Y N					
IT <0°C, were samples frozen? Y N Y N Y N Y N Y N	Y N Y N					
If out of Temperature, note packing/ice condition: Ice melted Poorly Packed (descr	ribed below) Same Day Rule					
Chent Approval to Kur Samples: Standing Approval Chent aware at drop-off Chent	notified by:					
All samples held in storage location: 5035 samples placed in storage location: $k   002 by \\ by \\ by \\ by \\ con \\ by \\ con \\ at \\ con \\ con \\ at \\ con \\ co$	ours of sampling? Y N					
Cooler Breakdown/Preservation Check**: Date: 8-22-23 Time: 15:30 by: 12	DA					
10. Did all bottle labels and tags agree with custody papers?						
11. Were correct containers used for the tests indicated?						
12. Were 5035 vials acceptable (no extra labels, not leaking)? YES NO N/A						
14. Air Samples: Cassettes / Tubes Intact Y / N with MS Y / N Canisters Pressurized Tedlar	n® Bags Inflated					
pH Lot of test Reagent Preserved? Lot Received Exp Sample ID Vo	ol. Lot Added Final					
>12 Yes No Adjusted Adjusted	dded pH					
<2 $06(7)7$ HNO <sub>2</sub> $> 30(014)$ $1/25$						
$\leq 2$ $H_2SO_4$						
<4 NaHSO4						
5-9 For 608pest No=Notify for 3day	······					
Residual For CN, If +, contact PM to add						
Chlorine         Phenol, 625,         Na2S2O3 (625, 608,           (a)         (b)         (c)						
(-) 608pest, 522						
LIAUCCIALE	t to be tested before analysis.					
are checked (not just re	epresentatives).					

Bottle lot numbers: 06/9/3 - 165, 052023 - 2AES Explain all Discrepancies/ Other Comments:

.

HPROD BULK HTR FLDT SUB HGFB ALS LL3541

Labels secondary reviewed by: <u>RDA</u> PC Secondary Review:

\*significant air bubbles: VOA > 5-6 mm : WC >1 in. diameter

P:\INTRANET\QAQC\Forms Controlled\Cooler Receipt r20.doc

01/23/2023

#### Internal Chain of Custody Report

Client:Neu-Velle LLCProject:Saginaw-Buffalo

Service Request: R2307578

Bottle ID	Methods	Date	Time	Sample Location / User	<b>Disposed On</b>
R2307578-001.01					
	6010C				
		8/22/2023	1526	SMO / GESMERIAN	
		8/22/2023	1528	R-A01 / GESMERIAN	
		8/23/2023	1519	In Lab / CDISTEFANO	
		8/23/2023	1533	R-A01 / CDISTEFANO	
R2307578-001.02					
	8082A				
		8/22/2023	1526	SMO / GESMERIAN	
		8/22/2023	1529	R-002 / GESMERIAN	
		8/24/2023	0957	In Lab / EDEGRAY	
R2307578-001.03					
		8/22/2023	1528	SMO / GESMERIAN	
		8/22/2023	1529	R-002 / GESMERIAN	



# Miscellaneous Forms

ALS Environmental—Rochester Laboratory 1565 Jefferson Road, Building 300, Suite 360, Rochester, NY 14623 Phone (585) 288-5380 Fax (585) 288-8475 www.alsglobal.com

LS) Environmental

#### **REPORT QUALIFIERS AND DEFINITIONS**

- U Analyte was analyzed for but not detected. The sample quantitation limit has been corrected for dilution and for percent moisture, unless otherwise noted in the case narrative.
- J Estimated value due to either being a Tentatively Identified Compound (TIC) or that the concentration is between the MRL and the MDL. Concentrations are not verified within the linear range of the calibration. For DoD: concentration >40% difference between two GC columns (pesticides/Arclors).
- B Analyte was also detected in the associated method blank at a concentration that may have contributed to the sample result.
- E Inorganics- Concentration is estimated due to the serial dilution was outside control limits.
- E Organics- Concentration has exceeded the calibration range for that specific analysis.
- D Concentration is a result of a dilution, typically a secondary analysis of the sample due to exceeding the calibration range or that a surrogate has been diluted out of the sample and cannot be assessed.
- Indicates that a quality control parameter has exceeded laboratory limits. Under the "Notes" column of the Form I, this qualifier denotes analysis was performed out of Holding Time.
- H Analysis was performed out of hold time for tests that have an "immediate" hold time criteria.
- # Spike was diluted out.

- + Correlation coefficient for MSA is <0.995.
- N Inorganics- Matrix spike recovery was outside laboratory limits.
- N Organics- Presumptive evidence of a compound (reported as a TIC) based on the MS library search.
- S Concentration has been determined using Method of Standard Additions (MSA).
- W Post-Digestion Spike recovery is outside control limits and the sample absorbance is <50% of the spike absorbance.
- P Concentration >40% difference between the two GC columns.
- C Confirmed by GC/MS
- Q DoD reports: indicates a pesticide/Aroclor is not confirmed (≥100% Difference between two GC columns).
- X See Case Narrative for discussion.
- MRL Method Reporting Limit. Also known as:
- LOQ Limit of Quantitation (LOQ) The lowest concentration at which the method analyte may be reliably quantified under the method conditions.
- MDL Method Detection Limit. A statistical value derived from a study designed to provide the lowest concentration that will be detected 99% of the time. Values between the MDL and MRL are estimated (see J qualifier).
- LOD Limit of Detection. A value at or above the MDL which has been verified to be detectable.
- ND Non-Detect. Analyte was not detected at the concentration listed. Same as U qualifier.



# NELAP StatesFlorida ID # E87674New Hampshire ID # 2941New York ID # 10145Pennsylvania ID# 68-786Virginia #460167

# Non-NELAP StatesConnecticut ID #PH0556Delaware ApprovedMaine ID #NY01587North Carolina #36701North Carolina #676Rhode Island LAO00333

<sup>1</sup> Analyses were performed according to our laboratory's NELAP-approved quality assurance program and any applicable state or agency requirements. The test results meet requirements of the current NELAP/TNI standards or state or agency requirements, where applicable, except as noted in the case narrative. Since not all analyte/method/matrix combinations are offered for state/NELAC accreditation, this report may contain results which are not accredited. For a specific list of accredited analytes, contact the laboratory or go to <a href="https://www.alsglobal.com/locations/americas/north-america/usa/new-york/rochester-environmental">https://www.alsglobal.com/locations/americas/north-america/usa/new-york/rochester-environmental</a>

Rochester Lab ID # for State Accreditations<sup>1</sup>

# ALS Laboratory Group

#### Acronyms

ASTM	American Society for Testing and Materials
A2LA	American Association for Laboratory Accreditation
CARB	California Air Resources Board
CAS Number	Chemical Abstract Service registry Number
CFC	Chlorofluorocarbon
CFU	Colony-Forming Unit
DEC	Department of Environmental Conservation
DEQ	Department of Environmental Quality
DHS	Department of Health Services
DOE	Department of Ecology
DOH	Department of Health
EPA	U. S. Environmental Protection Agency
ELAP	Environmental Laboratory Accreditation Program
GC	Gas Chromatography
GC/MS	Gas Chromatography/Mass Spectrometry
LUFT	Leaking Underground Fuel Tank
М	Modified
MCL	Maximum Contaminant Level is the highest permissible concentration of a
	substance allowed in drinking water as established by the USEPA.
MDL	Method Detection Limit
MPN	Most Probable Number
MRL	Method Reporting Limit
NA	Not Applicable
NC	Not Calculated
NCASI	National Council of the Paper Industry for Air and Stream Improvement
ND	Not Detected
NIOSH	National Institute for Occupational Safety and Health
PQL	Practical Quantitation Limit
RCRA	Resource Conservation and Recovery Act
SIM	Selected Ion Monitoring
TPH	Total Petroleum Hydrocarbons
tr	Trace level is the concentration of an analyte that is less than the PQL but
	greater than or equal to the MDL.

Analyst Summary report

Client:Neu-Velle LLCProject:Saginaw-Buffalo/

Service Request: R2307578

Sample Name:MH-2-081823Lab Code:R2307578-001Sample Matrix:Water

**Date Collected:** 08/18/23 **Date Received:** 08/18/23

Analysis MethodExtracted/Digested ByAnalyzed By6010CCDISTEFANONMANSEN8082AJVANHEYNINGENAFELSER



The preparation methods associated with this report are found in these tables unless discussed in the case narrative.

#### Water/Liquid Matrix

#### Solid/Soil/Non-Aqueous Matrix

Analytical Method	Preparation Method
200.7	200.2
200.8	200.2
6010C	3005A/3010A
6020A	ILM05.3
9034 Sulfide Acid Soluble	9030B
SM 4500-CN-E Residual Cyanide	SM 4500-CN-G
SM 4500-CN-E WAD Cyanide	SM 4500-CN-I

Analytical Method	Preparation				
	Method				
6010C	3050B				
6020A	3050B				
6010C TCLP (1311)	3005A/3010A				
extract					
6010 SPLP (1312) extract	3005A/3010A				
7199	3060A				
300.0 Anions/ 350.1/	DI extraction				
353.2/ SM 2320B/ SM					
5210B/ 9056A Anions					
For analytical methods not listed,	the preparation				
method is the same as the analytic	al method				
reference.					



# Sample Results

ALS Environmental—Rochester Laboratory 1565 Jefferson Road, Building 300, Suite 360, Rochester, NY 14623 Phone (585) 288-5380 Fax (585) 288-8475 www.alsglobal.com



# Semivolatile Organic Compounds by GC

ALS Environmental—Rochester Laboratory 1565 Jefferson Road, Building 300, Suite 360, Rochester, NY 14623 Phone (585) 288-5380 Fax (585) 288-8475 www.alsglobal.com

Analytical Report **Client:** Neu-Velle LLC Service Request: R2307578 Date Collected: 08/18/23 09:15 **Project:** Saginaw-Buffalo Sample Matrix: Water Date Received: 08/18/23 10:45 Sample Name: MH-2-081823 Units: ug/L Lab Code: R2307578-001 Basis: NA

#### Polychlorinated Biphenyls (PCBs) by GC

Analysis Method:8082APrep Method:EPA 3510C

Analyte Name	Result	MRL	MDL	Dil.	Date Analyzed	Date Extracted	Q
Aroclor 1016	0.50 U	0.93	0.50	1	08/28/23 18:01	8/24/23	
Aroclor 1221	1.0 U	1.9	1.0	1	08/28/23 18:01	8/24/23	
Aroclor 1232	0.50 U	0.93	0.50	1	08/28/23 18:01	8/24/23	
Aroclor 1242	0.50 U	0.93	0.50	1	08/28/23 18:01	8/24/23	
Aroclor 1248	0.50 U	0.93	0.50	1	08/28/23 18:01	8/24/23	
Aroclor 1254	0.50 U	0.93	0.50	1	08/28/23 18:01	8/24/23	
Aroclor 1260	0.50 U	0.93	0.50	1	08/28/23 18:01	8/24/23	

Surrogate Name	% Rec	<b>Control Limits</b>	Date Analyzed	Q	
Decachlorobiphenyl	138 *	10 - 118	08/28/23 18:01	*	
Tetrachloro-m-xylene	52	10 - 103	08/28/23 18:01		



# Metals

ALS Environmental—Rochester Laboratory 1565 Jefferson Road, Building 300, Suite 360, Rochester, NY 14623 Phone (585) 288-5380 Fax (585) 288-8475 www.alsglobal.com



Form 1

# **Inorganic Analysis Data Sheet**

# Metals by ICP

Workorder **R2307578** 

Client
Neu-Velle LLC

Project Saginaw-Buffalo

08/30/2023

ALS Environmental–Rochester Laboratory

1565 Jefferson Road, Building 300, Suite 360, Rochester, NY 14623 Phone (585) 288-5380 Fax (585) 288-8475 www.alsglobal.com



Workorder

R2307578

# Form 1 - Inorganic Analysis Data Sheet

Client Neu-Velle LLC

Project Saginaw-Buffalo

#### Metals by ICP

R2307578-001					Collect	ted	Rece	ived	Matrix	1	
MH-2-081823					08/18/23	0915	08/18/2	3 1045	Water		
Analyte	Units	МС	Result	٥	DL	LOQ	DF	Analysis I	Date	Run <b>I</b> D	PrepBatch
Lead, Total	ug/L	Ρ	39	J	3	50	1	08/29/23	02:40	RPAES06_815477	425309

MC - Method Class CV - Cold Vapor/AA P - ICP/AES MS - ICP/MS



# Form 1 - Inorganic Analysis Data Sheet

Client Neu-Velle LLC

#### Metals by ICP

R2307578-MB Matrix											
Method Blank Water											
Analyte	Units	МС	Result	Q	DL	LOQ	DF	Analysis Date	Run <b>I</b> D	PrepBatch	
Lead, Total	ug/L	Р	3	U	3	50	1	08/29/23 01:21	RPAES06_815477	425309	

MC - Method Class CV - Cold Vapor/AA P - ICP/AES MS - ICP/MS





# QC Summary Forms

ALS Environmental—Rochester Laboratory 1565 Jefferson Road, Building 300, Suite 360, Rochester, NY 14623 Phone (585) 288-5380 Fax (585) 288-8475 www.alsglobal.com



# Semivolatile Organic Compounds by GC

ALS Environmental—Rochester Laboratory 1565 Jefferson Road, Building 300, Suite 360, Rochester, NY 14623 Phone (585) 288-5380 Fax (585) 288-8475 www.alsglobal.com

QA/QC Report

Service Request: R2307578

Client:Neu-Velle LLCProject:Saginaw-BuffaloSample Matrix:Water

#### SURROGATE RECOVERY SUMMARY

Polychlorinated Biphenyls (PCBs) by GC

Analysis Method:8082AExtraction Method:EPA 3510C

		Decachlorobiphenyl	Tetrachloro-m-xylene
Sample Name	Lab Code	10 - 118	10 - 103
MH-2-081823	R2307578-001	138 *	52
Method Blank	RQ2310819-01	43	60
Lab Control Sample	RQ2310819-04	34	59
Duplicate Lab Control Sample	RQ2310819-05	33	53

Analytical Report **Client:** Neu-Velle LLC Service Request: R2307578 **Project:** Saginaw-Buffalo Date Collected: NA Sample Matrix: Water Date Received: NA Sample Name: Method Blank Units: ug/L RQ2310819-01 Lab Code: Basis: NA

#### Polychlorinated Biphenyls (PCBs) by GC

Analysis Method:	8082A
Prep Method:	EPA 3510C

Analyte Name	Result	MRL	MDL	Dil.	Date Analyzed	<b>Date Extracted</b>	Q
Aroclor 1016	0.50 U	1.0	0.50	1	08/28/23 16:22	8/24/23	
Aroclor 1221	1.0 U	2.0	1.0	1	08/28/23 16:22	8/24/23	
Aroclor 1232	0.50 U	1.0	0.50	1	08/28/23 16:22	8/24/23	
Aroclor 1242	0.50 U	1.0	0.50	1	08/28/23 16:22	8/24/23	
Aroclor 1248	0.50 U	1.0	0.50	1	08/28/23 16:22	8/24/23	
Aroclor 1254	0.50 U	1.0	0.50	1	08/28/23 16:22	8/24/23	
Aroclor 1260	0.50 U	1.0	0.50	1	08/28/23 16:22	8/24/23	

Surrogate Name	% Rec	<b>Control Limits</b>	Date Analyzed	Q	
Decachlorobiphenyl	43	10 - 118	08/28/23 16:22		
Tetrachloro-m-xylene	60	10 - 103	08/28/23 16:22		

QA/QC Report

Client: Project: Sample Matrix: Neu-Velle LLC

Saginaw-Buffalo

Water

Service Request: R2307578 Date Analyzed: 08/28/23

Duplicate Lab Control Sample Summary Polychlorinated Biphenyls (PCBs) by GC

> Units:ug/L Basis:NA

			<b>Lab</b> R	<b>Control Sa</b> Q2310819-	mple 04	<b>Duplicate La</b> RQ23	b Control S 10819-05	Sample		
Analyte Name	Analytical Method	Result	Spike Amount	% Rec	Result	Spike Amount	% Rec	% Rec Limits	RPD	RPD Limit
Aroclor 1016	8082A	2.84	4.00	71	2.60	4.00	65	35-131	9	30
Aroclor 1260	8082A	2.70	4.00	68	2.47	4.00	62	37-141	9	30



# Metals

ALS Environmental—Rochester Laboratory 1565 Jefferson Road, Building 300, Suite 360, Rochester, NY 14623 Phone (585) 288-5380 Fax (585) 288-8475 www.alsglobal.com



Form 3

# Blanks

Workorder R2307578

Client
Neu-Velle LLC

Project Saginaw-Buffalo

08/30/2023

ALS Environmental–Rochester Laboratory

1565 Jefferson Road, Building 300, Suite 360, Rochester, NY 14623 Phone (585) 288-5380 Fax (585) 288-8475 www.alsglobal.com

# ALS

## Form 3 - Blanks

Client Neu-Velle LLC

Workorder **R2307578** 

Project Saginaw-Buffalo

RPAES06_815477		ŀ	СВ	с	СВ	С	СВ	MB-8154	77	C	СВ	C	СВ	
Units	Run Date		08/28/	23	08/29/	23	08/29/	08/29/23		23	08/29/23		08/29/2	23
ug/L	Run Time		18:58		01:02		01:18		01:21		01:54		02:3	31
Analyte	DL	LOQ	Result	Q	Result	Q	Result	Q	Result	Q	Result	Q	Result	Q
Lead	3	50	3	U	3	U	3	U	3	U	3	U	3	U

RPAES06_815477			С	СВ	с	СВ
Units		Run Date	08/29/	/23	08/29/	23
ug/L		Run Time	02	:49	03:	05
Analyte	DL	LOQ	Result	Q	Result	Q
Lead	3	50	3	U	3	U



Form 7

# Laboratory Control Sample

# Metals by ICP

Workorder **R2307578** 

Client
Neu-Velle LLC

Project Saginaw-Buffalo

08/30/2023

ALS Environmental–Rochester Laboratory

1565 Jefferson Road, Building 300, Suite 360, Rochester, NY 14623 Phone (585) 288-5380 Fax (585) 288-8475 www.alsglobal.com



# Form 7 - Laboratory Control Sample

Client Neu-Velle LLC

#### Metals by ICP

											• • • • •	•
RPAES06_815477				R23075	78-LCS		R230757	8-DLCS				
Spike Matrix Water			Run Date	08/29	9/23		08/29	9/23				
Result Units ug/L			Run Time	01:2	24		01::	27				
Prep Method	Prep Batch	Prep Date		NA	4		N/	4				
EPA 3005A/3010A	08/23/23	425309	Prep Amt	50 r	nL		50 r	nL				
Analyte		%Recovery Limits	Spike Added	LCS Result	%R	Q	LCSD Result	%R	Q	RPD Limit	RPD	٥
Lead, Total		80-120	500	502	100		502	100		20	0	

Q - %Recovery / RPD Flag \* - %Recovery / RPD Outside Limits %R - %Recovery DF - Dilution Factor Amt - Amount (weight or volume)

Workorder

#### R2307578

RunID RPAES06-815477

# **Appendix D**

NEU-VELLE LLC

# Institutional Control/ Engineering Control (IC/EC) Certification



#### Enclosure 2 NEW YORK STATE DEPARTMENT OF ENVIRONMENTAL CONSERVATION Site Management Periodic Review Report Notice Institutional and Engineering Controls Certification Form



Sit	e No. 915152	Box 1	
Sit	e Name Saginaw - Buffalo		
Site Cit Co Site	e Address: 320 Scajaquada St. Zip Code: 14215 y/Town: Buffalo unty:Erie e Acreage: 7.248		
Re	porting Period: May 04, 2022 to August 31, ZOZ3		
		YES	NO
1.	Is the information above correct?	X	
	If NO, include handwritten above or on a separate sheet.		
2.	Has some or all of the site property been sold, subdivided, merged, or undergone a tax map amendment during this Reporting Period?	X	
3.	Has there been any change of use at the site during this Reporting Period (see 6NYCRR 375-1.11(d))?	X	
4.	Have any federal, state, and/or local permits (e.g., building, discharge) been issued for or at the property during this Reporting Period?		×
	If you answered YES to questions 2 thru 4, include documentation or evidence that documentation has been previously submitted with this certification form.		
5.	Is the site currently undergoing development?		×
		Box 2	NO
6.	Is the current site use consistent with the use(s) listed below? Industrial	X	
7.	Are all ICs in place and functioning as designed?		
	IF THE ANSWER TO EITHER QUESTION 6 OR 7 IS NO, sign and date below a DO NOT COMPLETE THE REST OF THIS FORM. Otherwise continue.	Ind	
A	Corrective Measures Work Plan must be submitted along with this form to address th	nese iss	ues.
		<u></u>	
SIG	mature of Owner, Remedial Party or Designated Representative Date Date		

SITE NO. 915152		Box 3
Description of Institut	tional Controls	
<u>Parcel</u> 101.24-1-3.1	<u>Owner</u> East Delavan Property, LLC	Institutional Control
		Monitoring Plan O&M Plan
<ul> <li>i) Inspection and Maintenand</li> <li>ii) Groundwater and Sewer</li> <li>2001.</li> <li>iii) Modification to O&amp;M Free</li> <li>iv) Modification to O&amp;M Free</li> </ul>	ce of Parking Lot #4. Monitoring according to the Oper quency Dated January 4, 2004. quency Dated September 22, 20	ation and Maintenance Manual, dated April 2, 08.
		Box 4
Description of Engine	eering Controls	
Parcel 101.24-1-3.1	Engineering Contro	<u>l</u> .
Asphalt Parking Lot Cover.	Cover System	

<ul> <li>Periodic Review Report (PRR) Certification Statements</li> <li>I certify by checking "YES" below that: <ul> <li>a) the Periodic Review report and all attachments were prepared under the direction of, eviewed by, the party making the Engineering Control certification;</li> <li>b) to the best of my knowledge and belief, the work and conclusions described in this certare in accordance with the requirements of the site remedial program, and generally according practices; and the information presented is accurate and comptex.</li> <li>YES</li> </ul> </li> <li>for each Engineering control listed in Box 4, I certify by checking "YES" below that all of the following statements are true: <ul> <li>a) The Engineering Control(s) employed at this site is unchanged since the date that the Control was put in-place, or was last approved by the Department (b) nothing has occurred that would impair the ability of such Control, to protect public he be environment;</li> <li>c) access to the site will continue to be provided to the Department, to evaluate the emoty, including access to evaluate the continued maintenance of this Control;</li> <li>d) nothing has occurred that would constitute a violation or failure to comply with the site Management Plan for this Control; and</li> <li>d) if a financial assurance mechanism is required by the oversight document for the site mechanism remains valid and sufficient for its intended purpose established in the document for the source of the site will control; and</li> </ul> </li> </ul>	
<ul> <li>I certify by checking "YES" below that:</li> <li>a) the Periodic Review report and all attachments were prepared under the direction of, reviewed by, the party making the Engineering Control certification;</li> <li>b) to the best of my knowledge and belief, the work and conclusions described in this certar in accordance with the requirements of the site remedial program, and generally according in accordance with the requirements of the site remedial program, and generally according in accordance with the requirements of the site remedial program, and generally according in accordance with the requirements of the site remedial program, and generally according in accordance with the requirements of the site remedial program, and generally according interesting practices; and the information presented is accurate and comptet.</li> <li>WES</li> <li>For each Engineering control listed in Box 4, I certify by checking "YES" below that all of the following statements are true: <ul> <li>(a) The Engineering Control(s) employed at this site is unchanged since the date that the Control was put in-place, or was last approved by the Department (b) nothing has occurred that would impair the ability of such Control, to protect public here environment;</li> <li>(c) access to the site will continue to be provided to the Department, to evaluate the remedy, including access to evaluate the continued maintenance of this Control;</li> <li>(d) nothing has occurred that would constitute a violation or failure to comply with the site Management Plan for this Control; and</li> <li>(e) if a financial assurance mechanism is required by the oversight document for the site mechanism remains valid and sufficient for Its intended purpose established in the document for the site mechanism remains valid and sufficient for Its intended purpose established in the document for the site mechanism remains valid and sufficient for Its intended purpose established in the document for the site mechanism remains valid and sufficient for Its in</li></ul></li></ul>	
<ul> <li>a) the Periodic Review report and all attachments were prepared under the direction of, reviewed by, the party making the Engineering Control certification;</li> <li>b) to the best of my knowledge and belief, the work and conclusions described in this certare in accordance with the requirements of the site remedial program, and generally accesses are in accordance with the requirements of the site remedial program, and generally accesses are in accordance with the requirements of the site remedial program, and generally accesses are in accordance with the requirements of the site remedial program, and generally accesses are in accordance with the requirements of the site remedial program, and generally accesses are in accordance with the requirements of the site remedial program, and generally accesses are in accordance with the requirements of the site remedial program, and generally accesses are in accordance with the requirements of the site remedial program, and generally accesses are in accordance with the requirements of the site is accurate and compete. YES</li> <li>For each Engineering control listed in Box 4, I certify by checking "YES" below that all of the following statements are true: <ul> <li>(a) The Engineering Control(s) employed at this site is unchanged since the date that the Control was put in-place, or was last approved by the Department (b) nothing has occurred that would impair the ability of such Control, to protect public here environment;</li> <li>(c) access to the site will continue to be provided to the Department, to evaluate the remedy, including access to evaluate the continued maintenance of this Control;</li> <li>(d) nothing has occurred that would constitute a violation or failure to comply with the Site Management Plan for this Control; and</li> <li>(e) If a financial assurance mechanism is required by the oversight document for the site mechanism remains valid and sufficient for its intended purpose established in the document for the site mechanism remains valid and</li></ul></li></ul>	
<ul> <li>b) to the best of my knowledge and belief, the work and conclusions described in this centre in accordance with the requirements of the site remedial program, and generally accompleted in accordance with the requirements of the site remedial program, and generally accompleted in accordance with the requirements of the site remedial program, and generally accompleted in accordance with the requirements of the site remedial program, and generally accompleted in accordance with the requirements of the site remedial program, and generally accompleted in accordance with the requirements of the site remedial program, and generally accompleted in accordance with the information presented is accurate and complete.</li> <li>YES</li> <li>For each Engineering control listed in Box 4, I certify by checking "YES" below that all of the following statements are true: <ul> <li>(a) The Engineering Control(s) employed at this site is unchanged since the date that the Control was put in-place, or was last approved by the Department (b) nothing has occurred that would impair the ability of such Control, to protect public here the environment;</li> <li>(c) access to the site will continue to be provided to the Department, to evaluate the remedy, including access to evaluate the continued maintenance of this Control;</li> <li>(d) nothing has occurred that would constitute a violation or failure to comply with the Site Management Plan for this Control; and</li> <li>(e) if a financial assurance mechanism is required by the oversight document for the site mechanism remains valid and sufficient for its intended purpose established in the document of the source of the source of the source of the document for the site mechanism remains valid and sufficient for its intended purpose established in the document of the source o</li></ul></li></ul>	and
<ul> <li>For each Engineering control listed in Box 4, I certify by checking "YES" below that all of the following statements are true:</li> <li>(a) The Engineering Control(s) employed at this site is unchanged since the date that the Control was put in-place, or was last approved by the Department (b) nothing has occurred that would impair the ability of such Control, to protect public he the environment;</li> <li>(c) access to the site will continue to be provided to the Department, to evaluate the remedy, including access to evaluate the continued maintenance of this Control;</li> <li>(d) nothing has occurred that would constitute a violation or failure to comply with the Site Management Plan for this Control; and</li> <li>(e) if a financial assurance mechanism is required by the oversight document for the site mechanism remains valid and sufficient for its intended purpose established in the docum</li> </ul>	ertificat epted
<ul> <li>For each Engineering control listed in Box 4, I certify by checking "YES" below that all of the following statements are true:</li> <li>(a) The Engineering Control(s) employed at this site is unchanged since the date that the Control was put in-place, or was last approved by the Department</li> <li>(b) nothing has occurred that would impair the ability of such Control, to protect public he the environment;</li> <li>(c) access to the site will continue to be provided to the Department, to evaluate the remedy, including access to evaluate the continued maintenance of this Control;</li> <li>(d) nothing has occurred that would constitute a violation or failure to comply with the Site Management Plan for this Control; and</li> <li>(e) If a financial assurance mechanism is required by the oversight document for the site mechanism remains valid and sufficient for its intended purpose established in the document YES</li> </ul>	NO
<ul> <li>For each Engineering control listed in Box 4, I certify by checking "YES" below that all of the following statements are true:</li> <li>(a) The Engineering Control(s) employed at this site is unchanged since the date that the Control was put in-place, or was last approved by the Department (b) nothing has occurred that would impair the ability of such Control, to protect public he the environment;</li> <li>(c) access to the site will continue to be provided to the Department, to evaluate the remedy, including access to evaluate the continued maintenance of this Control;</li> <li>(d) nothing has occurred that would constitute a violation or failure to comply with the Site Management Plan for this Control; and</li> <li>(e) if a financial assurance mechanism is required by the oversight document for the site mechanism remains valid and sufficient for its intended purpose established in the document YES</li> </ul>	
<ul> <li>(a) The Engineering Control(s) employed at this site is unchanged since the date that the Control was put in-place, or was last approved by the Department</li> <li>(b) nothing has occurred that would impair the ability of such Control, to protect public he the environment;</li> <li>(c) access to the site will continue to be provided to the Department, to evaluate the remedy, including access to evaluate the continued maintenance of this Control;</li> <li>(d) nothing has occurred that would constitute a violation or failure to comply with the Site Management Plan for this Control; and</li> <li>(e) if a financial assurance mechanism is required by the oversight document for the site mechanism remains valid and sufficient for its intended purpose established in the docum</li> </ul>	
<ul> <li>(b) nothing has occurred that would impair the ability of such Control, to protect public he the environment;</li> <li>(c) access to the site will continue to be provided to the Department, to evaluate the remedy, including access to evaluate the continued maintenance of this Control;</li> <li>(d) nothing has occurred that would constitute a violation or failure to comply with the Site Management Plan for this Control; and</li> <li>(e) if a financial assurance mechanism is required by the oversight document for the site mechanism remains valid and sufficient for its intended purpose established in the docum</li> </ul>	t;
<ul> <li>(c) access to the site will continue to be provided to the Department, to evaluate the remedy, including access to evaluate the continued maintenance of this Control;</li> <li>(d) nothing has occurred that would constitute a violation or failure to comply with the Site Management Plan for this Control; and</li> <li>(e) if a financial assurance mechanism is required by the oversight document for the site mechanism remains valid and sufficient for its intended purpose established in the docum YES</li> </ul>	ealth a
<ul> <li>(d) nothing has occurred that would constitute a violation or failure to comply with the Site Management Plan for this Control; and</li> <li>(e) if a financial assurance mechanism is required by the oversight document for the site mechanism remains valid and sufficient for its intended purpose established in the docum</li> </ul>	
(e) if a financial assurance mechanism is required by the oversight document for the site mechanism remains valid and sufficient for its intended purpose established in the docun YES	
YES	e, the nent.
	NO
×	
IF THE ANSWER TO QUESTION 2 IS NO, sign and date below and DO NOT COMPLETE THE REST OF THIS FORM. Otherwise continue.	
A Corrective Measures Work Plan must be submitted along with this form to address these iss	ues.
Signature of Owner, Demodial Darty or Designated Dessessation	

	IC CERTIFICATIONS	
	SHE NO. 313132	Box 6
SITE OWNER OR I certify that all information and stat statement made herein is punishab	DESIGNATED REPRESENTATIV lements in Boxes 1,2, and 3 are true le as a Class "A" misdemeanor, put	E SIGNATURE e, I understand that a false rsuant to Sectlon 210.45 of the
Penal Law.	Neu-velle LLC 10 Jones Ave	
1 Albert G. Lyons, Jr	al Rochester, NY	14608
print name	print business ad	dress
am certifying as	Representative	(Owner or Remedial Party)
for the Sile named in the Sile Detail Mut D how Signature of Owner, Remédial Par Rendering Certification	lls Section of this form. y, or Designaled Representative	9/25/23 Date

· ·

- .

.

.

.

.

.

,

.

. 1

EC CERTIF	ICATIONS
	Box 7
Professional E	ngineer Signature
I certify that all information in Boxes 4 and 5 are true punishable as a Class "A" misdemeanor, pursuant t	e. I understand that a false statement made herein is o Section 210.45 of the Penal Law. אינט-יפוול נכך
1 Albert 6. Wons. dr at	Rochester, NY 14608
print name	print business address
am certifying as a Professional Engineer for the Multiply Jack Signature of Professional Engineer, for the Owner of Remedial Party, Rendering Certification	or Stamp (Required for PE)

,

,

. . . •

.

.

•

.

· .

.

-

# Appendix E

NEU-VELLE LLC

Site Map



Property Boundary —

Monitoring Well 🔴

Manhole 🧅

Appendix F

NEU-VELLE LLC

**Survey Map** 



eproduction or copying of this document may be a violation of copyright law unless permission of the author and / or copyright holder is obtaine

LATITUDE LONGITUDE DISTANCE (m) W 78 50 47.2734 22847.0

#### W 78 45 13.3570 27517.5 W 78 58 12.5941 36570.8 W 78 58 11.2659 36560.3

N01°00'00"E 1252.98' Deed & Measure Well MW 5 MW-205 🕒 Well Power Facilities License Agreement RE-250 between General Motors and Niagara Mohawk MW 211 🕒 Well MW 204 Je Well Transmission Tower MW 1 

