

S-5167 South Park Avenue Box 0513 Hamburg, New York 14075 (716) 649-6110 Fax (716) 649-8051

915167

# PHASE II ENVIRONMENTAL INVESTIGATION WATERFRONT REDEVELOPMENT PROJECT NYR35 PARCELS 17A, 23 & 24 BUFFALO, NEW YORK

#### Prepared For:

Buffalo Urban Renewal Agency 920 City Hall Buffalo, New York 14202-3376

Attention: Mr. Joseph V. Schollard

#### Prepared By:

Huntingdon - Empire Soils Investigations, Inc. S-5167 South Park Avenue Hamburg, New York 14075 (716)649-8110

> BTA-92-060 May 20, 1992



S-5167 South Park Avenue Box 9612 Hamburg, New York 14075 (7161649-8110 Fax: (7161649-8051

#### TABLE OF CONTENTS

I.	INT	RODUCTION -	1
	A.	Background	1
	В.	Scope of Services	2
II.	PHY	YSICAL SETTING	3
	A.	General	3
	B.	Site Characteristics	3
III.	SUE	SSURFACE EXPLORATIONS	4
	A.	General	-4
	B.	Modified Soil Gas Survey and Results	4
	<i>C</i> .	Test Pit Excavations	7
	D.	Test Borings	7 8
	<i>E</i> .	Soil Samples	9
	F.	Ground Water Monitoring Installations & Development	10
	G.	Ground Water Sampling	. 11
IV.	SUE	SSURFACE CONDITIONS	12
V.	ANA	ALYTICAL RESULTS	15
	A.	General .	15
	B.	Area of Tar-like Contamination	15
	<i>C</i> .	Area of Suspected Fuel Contamination	17
VI.	DIS	CUSSION	18
VII.	CON	NCLUSIONS AND RECOMMENDATIONS	19
<u>Appe</u>	<u>ndices</u>		
Apper	ndix A	- Drawings	
Apper	ndix B	- Limitations	
Apper	ndix C	- Test Pit Logs	
Apper	ndix D	- Subsurface Boring Logs	
Apper	ndix E	- Analytical Data Results	



S-5187 South Fark 7 Jende Box 0813 Handrung, New York 14075 716 849-8110 Fax: 1716 649-8051

#### PHASE II ENVIRONMENTAL INVESTIGATION WATERFRONT REDEVELOPMENT PROJECT NYR35 PARCELS 17A, 23 & 24 BUFFALO, NEW YORK

#### I. INTRODUCTION

#### A. -Background

Empire Soils Investigations, Inc. (Empire) was requested and authorized by Mr. Joseph V. Schollard, Commissioner of the City of Buffalo Urban Renewal Agency (BURA) to complete a Phase II Environmental Investigation for NYR35 Parcels 17A, 23 & 24 of the Waterfront Redevelopment Project in downtown Buffalo, New York. A site location map is presented as Drawing No. 1 in Appendix A.

Empire understands that BURA is planning to construct residential townhouse units on the subject property. Previous studies completed by Empire (report dated October 1989) and Buffalo Drilling Company, Inc. (report dated May 23, 1991) on the subject property indicated organic vapor readings and petroleum-type odors on subsurface soils and/or fill materials. Site history research indicated that a bus terminal had previously occupied a portion of the subject site, including the associated underground fuel tanks. Based on this information, the New York State Department of Environmental Conservation (NYSDEC) recommended a Phase II Environmental Investigation to better define the nature, extent and concentration of suspected contamination.

Empire's work was completed in accordance with a revised proposal to BURA dated November 14, 1991. It should be noted that tar-like contamination was observed in test pit excavations completed by Empire near the northwest portion of the site during the initial field work phase of the current project. Based on this observation, Empire recommended additional work at the subject site in a letter to BURA dated March 11, 1992 to further investigate the observed contamination. The additional work was also authorized by BURA. The results of the additional work, including additional test pit excavations and laboratory analytical testing, are included in this report.

#### B. Scope of Services

Empire completed the following scope of services to investigate the potential contamination discussed above:

- o Planned and coordinated a subsurface investigation program and analytical testing program for the site;
- o Completed a Modified Soil Gas Survey at the site;
- o Completed twenty-nine (29) exploratory Test Pit excavations at the site;
- o Advanced four (4) test borings and installed four (4) ground water monitoring wells at the site;
- o Monitored all test pit excavations and drilling and monitoring well installation activities in the field and collected soil samples for laboratory chemical analysis;
- o Scanned the excavated materials and recovered soil samples in the field with a photoionization detector (PID) for the presence of volatile organic compounds;
- o Prepared test boring logs and monitoring well installation diagrams;
- O Developed the four (4) monitoring wells and collected representative ground water samples from each well for laboratory chemical analysis;
- o Measured relative ground water elevations in each of the four (4) monitoring wells;
- o Subjected five (5) soil samples and four (4) ground water samples to laboratory chemical analysis; and
- o Summarized the collected data in this report.

The information presented in this report is subject to the limitations presented in Appendix B.

#### II. PHYSICAL SETTING

#### A. General

The subject site is located south of Carolina Street, between Fourth and Seventh Streets in downtown Buffalo, New York. The Waterfront School is located adjacent to the southwest portion of the property, and the Shoreline Apartments are located northeast of the site.

#### B. Site Characteristics

Site topography is generally flat, with a gentle slope downward toward the southwest. Based on the proximity of the subject property to Lake Erie (approximately 1/4-mile to the southwest), it is expected that the ground water flow direction is to the west/southwest, toward the lake.

The subject property is currently vacant and grass-covered except for a few trees.

A 48-inch diameter water line reportedly crosses the site in a northwest-southeast direction.

#### III. SUBSURFACE EXPLORATION

#### A. General

Empire's subsurface exploration tasks at the site included a modified soil gas survey, test pit excavations, test borings, monitoring well installation and development and ground water sampling. Each task is discussed later in this report.

The modified soil gas survey was completed in the general area of the site where petroleum-type vapors and relatively higher organic vapor measurements were detected in previous test pit excavations. Empire measured volatile organic vapors at twenty-five (25) soil gas probe locations.

Empire excavated fifteen (15) test pits on March 6, 1992 and fourteen (14) test pits on March 25, 1992, for a total of twenty-nine (29). The locations of the test pits excavated on March 6, 1992 were based on the results of Empire's modified soil gas survey. The locations of the test pits excavated on March 25, 1992 were selected to better define the lateral and vertical extent of apparent contamination observed in the test pits excavated on March 6, 1992.

Composite soil samples collected from two (2) of the test pits were subjected to laboratory chemical analysis.

Empire advanced four (4) test borings and installed four (4) ground water monitoring wells at the subject site on March 30 and 31, 1992. The test boring/monitoring well locations were selected based on the results of the test pit excavations. After installation, Empire developed the wells and collected ground water samples for laboratory chemical analysis. A composite soil sample from one of the test borings was also subjected to laboratory chemical analysis.

#### B. Modified Soil Gas Survey and Results

Empire completed a modified soil gas survey on March 4 and 5, 1992. A 50-feet x 50-feet grid was established across the soil gas survey area. One-half inch diameter PVC soil vent pipes were installed at each grid point. The pipes were installed to a depth of about two and one-half (2.5) to three and one-half (3.5) feet below ground

surface. Each of the pipes was capped and labeled. An initial soil vapor measurement was taken of the stagnant air in the pipe prior to purging. The pipe was then purged with a battery operated diaphram pump, to remove the stagnant air and several pipe volumes of air from within the pipe and to draw representative soil vapors into the pipe. The soil vapors were then collected into a sealed plastic bag and analyzed for volatile organic vapors using a photoionization detector (PID), manufactured by Hnu Systems, Inc. of Newton Highlands, Massachusetts. The PID used was a Hnu Model PI-101 with a 10.2 eV ultraviolet light source. The PID measurements were recorded in parts per million (ppm). The PID was calibrated prior to use each day in accordance with the manufacturers instructions. The soil gas measurement points are shown on Drawing No.—2 presented in Appendix A. The PID soil gas measurements are summarized in Table 1.

TABLE 1 SUMMARY OF SOIL GAS FIELD MEASUREMENTS (From March 4 & 5, 1992)									
DATE OF TEST	PROBE ID#	INITIAL PID (ppm)	PURGED PID (ppm)	COMMENTS					
Mar 4	A1	BG	BG						
-Mar 4	A3	BG	BG						
Mar 4	A5	BG	BG						
Mar 4	A7			No Probe (refusal)					
Mar 4	B <b>2</b>	BG	BG						
Mar 4	В4	BG	BG						
Mar 4	В6	BG	BG						
Mar 4	C1	2.0	BG	Petroleum odor on probe tool (wet)					
Mar 4	С3	BG	BG						
Mar 4	_C5	BG	BG						

#### TABLE 1 SUMMARY OF SOIL GAS FIELD MEASUREMENTS (From March 4 & 5, 1992)

DATE OF TEST	PROBE ID#	INITIAL PID (ppm <u>)</u>	PURGED PID (ppm)	COMMENTS
Mar 4	C7	BG	BG	
Mar 4	D2	BG	BG	
Mar 4	D4	BG	BG	
Mar 4	D6	BG	BG	
Mar 5	E1	BG	3.0	
Mar 5	E3	BG	0.4	
Mar 5	E5	BG	0.5	
Mar 5	E7	BG	BG	
Mar 5	F2	BG	BG	
Mar 5	F4	BG_	BG ·	
Mar 5	F6	BG	BG	
Mar 5	B1	0.8	0.4	
Mar 5	D1	BG	0.5	
Mar 5	F1	20.0	30.0	Petroleum odor and sheen on probe tool (wet)
Mar 5	- G1	BG ·	BG	
Mar 5	H1	BG	BG	
Mar 5	- G2			No Probe (refusal)

BG = Background or ambient air PID measurements

Empire used a John Deere 410C backhoe to excavate the test pits on March 6, 1992. Test pit locations were determined in the field by Empire based on the results of the soil gas survey. An Empire environmental geologist observed and logged each test pit, collected soil samples and scanned the test pits for volatile organic compounds using a PID. The PID used to measure total organic vapors was an Hnu PI 101 with a 11.7 eV ultraviolet light source. The PID was calibrated before field use. Refer to the test pit logs presented in Appendix C for PID results.

In two (2) of the fifteen (15) test pits excavated on March 6, 1992 soils were encountered which had a diesel fuel-type odor and/or PID readings above background (test pits TP-15 and TP-21). Also in a few test pits excavated near the western site boundary (tests pits TP-10, TP-11, TP-12, TP-13 and TP-18), a black, tar-like substance was encountered with a very strong tar-like odor. Soil samples were collected from test pits TP-10, TP-11 and TP-12 and were analyzed for reactivity, corrosivity, ignitability. The samples were placed in the appropriate precleaned containers and shipped to Huntington Analytical Services, Inc. (HAS) in Middleport, New York for testing. The analytical test results will be discussed later in this report.

An additional day of test pit exploration was completed on March 25, 1992 to better define the areal and vertical extent of the contamination of the diesel fuel-type odor and the black, tar-like substance. A total of fourteen (14) additional test pits were excavated on March 25, 1992. Eight (8) of the test pits were located in the area of the black, tar-like substance (test pits TP-1 through TP-8). The remaining seven (7) test pits (test pits TP-24 through TP-29) were located in the area of the diesel fuel-type odor. Test pit logs are presented in Appendix C.

#### D. Test Borings

Empire advanced four (4) test borings (MW-1 through MW-4) and installed a ground water monitoring well at each test boring location. The test borings and monitoring well installations were completed on March 30 and March 31, 1992.

The test borings were advanced to evaluate the general subsurface conditions at the site and the presence of potential contamination which may be present in the soil and ground water beneath the site. The test borings were located in the field by Empire based on the results of a soil gas survey and test pits which were completed by Empire at an earlier date. Test borings MW-1 and MW-2 were located in the area where black, tar-like contamination was encountered along the western site boundary in test pit excavations on March 6 and March 25, 1992. Test boring MW-3 was located near where diesel fuel-type contamination was also encountered in test pit excavations on March 6 and March 25, 1992. Test boring MW-4 was located upgradient from MW-1, MW-2 and MW-3 to establish background conditions at the subject site with regard to ground water quality. Test borings were generally advanced to refusal at depths of approximately 14 to 16 feet below ground surface to evaluate subsurface soil and ground water conditions. Refer to Drawing No. 2 in Appendix A for test boring locations.

Empire used a CME-55 rotary drill righto advance the test borings and install the monitoring wells. The test borings were advanced using 4-1/4 inch inside diameter (I.D.) hollow stem augers equipped with a center plug to prevent soil from entering the augers during drilling. Continuous soil samples were recovered by driving a 24-inch long by 2-inch outside diameter (O.D.) split-spoon sampler into the soil below the bottom of the augers. A 140-pound hammer free falling 30-inches (ASTM D-1586) was used to advance the sampler. The number of blows required to drive the split spoon for the second and third six-inch intervals is the Standard Penetration Test (SPT) N-value and is recorded on the appropriate space on the boring log. Representative soil samples were collected and stored in 8-ounce glass jars for future reference.

All equipment was decontaminated with a steam cleaner prior to drilling at each

of the four (4) test boring/monitoring well locations. Split-spoon samplers were decontaminated using a detergent wash and clean water rinse between samples.

Empire completed air quality monitoring for volatile organic vapors with a photoionization detector (PID) during the drilling and soil sampling procedures. PID measurements were made at the top of the hollow-stem augers and on recovered split-spoon soil samples. The PID used to measure volatile organic vapors was an Hnu PI 101 with a 11.7 eV ultraviolet light source. The PID was calibrated before field use. Ambient background PID measurements were made upwind of each borehole location prior to drilling to establish site conditions. The range of these background readings during the monitoring period (March 30 & 31, 1992) were 0.0 to 0.6 parts per million (ppm). All PID measurements are recorded on the boring logs presented in Appendix D.

Soil sampling was done continuously from ground surface to boring completion. An Empire environmental geologist monitored the drilling and soil sampling procedures and prepared boring logs based on visual observations of the recovered soil samples. The soil samples were generally described using ASTM D-2488 for identification of soils. Features such as relative density or consistency (obtained from the SPT), color, grain size, moisture, etc. were recorded on the boring logs.

#### E. Soil Samples

A composite soil sample was collected from test pit TP-11 excavated on March 6, 1992 and analyzed for reactivity, corrosivity and ignitability (i.e. hazardous waste characterization). A composite soil sample was collected from test pit TP-3 excavated on March 25, 1992 and analyzed for reactivity, corrosivity and ignitability as well as for volatile and semi-volatile compounds. A sample of the black, tar-like substance ("product") was also collected from test pit TP-3 and analyzed for volatile and semi-volatile compounds.

A composite soil sample was collected from test boring MW-3 for chemical laboratory analysis. The soil sample was analyzed for reactivity, corrosivity, ignitability, USEPA Target Compound List (TCLP Procedures) and PCBs. The soil sample was composited from split-spoon samples S-3, S-4 and S-5.

All samples were placed in the appropriate precleaned containers and shipped to HAS in Middleport, New York for testing. The analytical test results are discussed later in this report.

#### F. Ground Water Monitoring Well Installations and Development

Ground water monitoring wells were installed in each of the four (4) boreholes upon completion of drilling. The wells consisted of 2-inch I.D. schedule 40 PVC well screen and riser pipe. The slot size on the well screen was 0.010-inch (No. 10 slot). The annular space around the well screen was backfilled with No. 1 Morie sand from the bottom of the borehole to approximately 0.5-foot above the top of the well screen. A minimum 1.0-foot thick bentonite pellet seal was constructed above the sand pack. A protective steel casing with a locking cap was installed over the top of the well pipe, cemented in place and secured with a padlock. Monitoring well completion reports are presented in Appendix D.

The well screens for wells MW-1, MW-3 and MW-4 were installed to monitor ground water contained in the miscellaneous fills and the uppermost zone of the underlying native soils. The well screen for monitoring well MW-2 was installed to monitor only the ground water contained in the native soils. Since well MW-2 was located near MW-1, the vertical difference in screen placement between the two (2) wells was done to give an indication of downward migration of contaminants, if any.

Ground water samples were collected from monitoring wells MW-1, MW-2, MW-3 and MW-4 on April 2, 1992. The monitoring wells were developed prior to sampling using a peristaltic pump. MW-1 and MW-2 were developed by being taken to dryness three (3) times, MW-3 and MW-4 were developed by removing ten (10) well volumes

BTA-92-060 Page 10 5/92

and insuring stability of PH and Temperature. The wells were then allowed to recover to a sufficient volume before sampling.

#### G. Ground Water Sampling

Ground water samples were collected from each of the four (4) monitoring wells installed at the site. The ground water samples were analyzed for Total Petroleum Hydrocarbons (Test Method DOH 310-13), Target compound List (TCL) volatiles (USEPA Test Method 8020) and TCL semi-volatiles (USEPA Test Method 8270).

Ground water was sampled by carefully lowering a dedicated polyethylene bailer equipped with a bottom filling check valve into the well and allowing it to fill. The bailer was then slowly removed and the contents emptied into the appropriate precleaned containers. The samples were then placed in an ice cooler and delivered to HAS for testing. The analytical test results are discussed later in this report.

#### IV. SUBSURFACE CONDITIONS

Subsurface conditions at the subject site were evaluated on the basis of the twenty-nine (29) test pits excavated, the four (4) test borings advanced and the four (4) ground water monitoring wells installed by Empire. Test pit logs are presented in Appendix C and test boring logs and monitoring well installation diagrams are presented in Appendix D.

Miscellaneous, man-placed fill materials were encountered in the various subsurface explorations from ground surface to depths of approximately four (4) to eleven (11) feet. Fill depth generally increased from east to west across the study area. The miscellaneous fill materials consisted mainly of sand, gravel, silt, clayey silt, boulders, concrete fragments and bricks. The fill materials also occasionally contained wood, metal fragments, ash seams, pipe fragments, slag, asphaltic concrete fragments and glass. Wooden beams, apparent remnants of concrete building foundations and apparent remnants of concrete or asphaltic concrete pavement were also encountered in the subsurface at the subject site.

Native soils encountered beneath the miscellaneous fills at the site consisted mainly of light brown sandy silt with traces of gravel. Based on previous subsurface work by Empire in the vicinity of the subject site, we expect that the underlying bedrock is limestone belonging to the Onondaga formation. We also expect that drilling refusal achieved at test boring locations MW-1, MW-2, and MW-4 was due to encountering bedrock. We note that no bedrock core samples were obtained as part of this project.

Depth to ground water at the site ranged between approximately one and one-half (1.5) and four (4) feet below ground surface in the test pit excavations. Some areas of the site appeared to contain "pockets" of ground water perched in relatively more permeable zones of the miscellaneous fills.

Water levels measured in the four (4) monitoring wells on April 2 and May 13, 1992 are presented in Table 2. The water levels measured on both days indicate a ground water flow direction to the west toward Lake Erie, as expected.

TABLE 2 WATER LEVEL DATA							
Well No.	Date	Depth Below Measuring Point	Ground Water Elevation				
MW-1	4-2-92	4.96	88.92				
	5-13-92	5.56	88.32				
MW-2	4-2-92	3.24	88.84				
	5-13-92	3.71	88.37				
MW-3	4-2-92	3.18	91.45				
	5-13-92	5.01	89.62				
MW-4	4-2-92	3.98	91.64				
	5-13-92	5.52	90.10				

Note: Ground water elevations were referenced to a bench mark established by Empire on top of the valve nut on a fire hydrant located at the western border of the site in front of Shoreline Apartment No. 26. Assumed bench mark elevation = 100.00.

Empire observed evidence of contamination on materials excavated from many of the twenty-nine (29) test pits and soil samples recovered from three (3) of the four (4) test borings. The contamination evidence consisted of relatively high PID readings, odors or visual evidence such as soil discoloration or a petroleum-type sheen on soils or standing water. Based on these observations, it appears that there are two (2) primary areas of subsurface contamination at the site, as discussed in the following paragraphs.

The more significant area of contamination is in the vicinity of monitoring wells MW-1 and MW-2, near the northwestern portion of the property. In this area, a black, tar-like substance was encountered in the subsurface. PID measurements near the surface of the black material were typically about 100 to 300 ppm, and the material exhibited a strong, tar-like odor. Much of the soil in relatively close vertical proximity to the seam of black material was also black in color, exhibited relatively high PID readings and had a noticeable petroleum-type sheen on the surface. Ground water which collected in the test pits excavated in this area also had a noticeable surface sheen. It should be noted that the western extent of this subsurface contamination was not defined since test borings and/or test pit excavations were not completed on the adjacent property owned by the Waterfront School.

The second area of apparent subsurface contamination is in the vicinity of monitoring well MW-3, southeast of the area containing the tar-like substance. In this area, apparent contamination indicated by relatively higher PID readings exhibited an odor similar to diesel fuel or fuel oil. Based on field observations, the concentrations and lateral extent of the fuel-type contamination appeared to be significantly less than the black, tar-like contamination discussed above.

#### V. ANALYTICAL RESULTS

#### A. General

Empire collected a total of five (5) soil samples and four (4) ground water samples at the subject site and submitted the samples to the laboratory for chemical analysis. The analytical results are discussed in the following sections of this report.

#### B. Area of Tar-like Contamination

Empire collected four (4) composite soil samples from test pit excavations TP-3 and TP-11 and two (2) ground water samples from monitoring wells MW-1 and MW-2 in the area of the tar-like contamination. Two (2) of the soil samples were analyzed for corrosivity, reactivity and ignitability and a third soil sample was analyzed for volatile and semi-volatile compounds. The fourth soil sample was of the actual tar-like material (i.e. "product") and was analyzed for volatile and semi-volatile compounds. The two (2) ground water samples were analyzed for purgeable aromatic compounds, semi-volatile compounds and total petroleum hydrocarbons (method DOH 310.13). Analytical results for soil and ground water samples are presented in Appendix E.

Analysis of soil sample TP-3B indicated detectable concentrations of compounds typically associated with petroleum fuels and coal tar-based substances. These compounds included benzene, toluene, ethyl benzene and xylene (BTEX; volatile compounds), as well as anthracene, fluorene, naphthalene, phenanthrene and other similar compounds (semi-volatile compounds). Detected concentrations of BTEX compounds in sample TP-3B ranged between 970 and 11,000 micrograms per kilogram (ug/kg) or parts per billion (ppb). Concentrations of detected coal tar (semi-volatile) compounds ranged between 14,000 and 2,000,000 ppb (naphthalene concentration was 2,000,000 ppb). Some phenolic substances were also detected in sample TP-3B, but the concentration of each individual phenolic compound was not quantifiable.

Analysis of sample TP-3C (tar-like "product") indicated detectable concentrations of typical petroleum fuel compounds and coal tar compounds, as discussed above. Measured concentrations of these compounds in sample TP-3C were generally higher as

compared to measured concentrations of the same compounds in sample TP-3B. Concentrations of detected BTEX compounds in sample TP-3C ranged between 160,000 and 3,300,000 ppb (benzene concentration of 3,300,000 ppb). Concentrations of detected coal tar compounds in sample TP-3C ranged between 160,000 and 12,000,000 ppb (naphthalene concentration of 12,000,000 ppb). Detected concentrations of phenolic compounds in sample TP-3C ranged between 460,000 and 1,300,000 ppb (4-methyl phenol concentration of 1,300,000 ppb). Please refer to the laboratory analytical results presented in Appendix E for detected concentrations on a compound by compound basis.

Samples of the black, tar-like material ("product") from test pits TP-3 (sample TP-3A) and TP-11 (sample TP-C1) were analyzed for corrosivity, ignitability and reactivity (hazardous waste characterization). Results of the corrosivity and reactivity analyses for these two (2) samples indicated non-hazardous characteristics. Results of ignitability analysis indicated flash points of 123-degrees Fahrenheit for sample TP-3A and 111-degrees Fahrenheit for sample TP-C1, which were both below the hazardous flash point value of 160-degrees Fahrenheit, indicating a hazardous material.

For the ground water samples collected from monitoring wells MW-1 and MW-2, detectable concentrations of petroleum fuel compounds, coal tar compounds and phenolic compounds were measured. Concentrations of benzene, toluene and xylene detected in wells MW-1 and MW-2 ranged between 1,100 and 21,000 ppb (benzene concentration of 21,000 ppb in well MW-2). Concentrations of coal tar compounds detected in wells MW-1 and MW-2 ranged between 10 and 6,500 ppb (naphthalene concentration of 6,500 ppb in well MW-2). Concentrations of phenolic compounds detected in wells MW-1 and MW-2 ranged between 13,000 and 46,000 ppb (4-methyl phenol concentration of 46,000 ppb in well MW-2).

For the ground water sample collected from upgradient well MW-4, only ethyl benzene and total xylenes were detected at concentrations of 0.59 ppb and 1.4 ppb, respectively.

No concentrations of petroleum products in water (method DOH 310.13) were detected in ground water samples collected from wells MW-1, MW-2 or MW-4 above the method detection limits. However, the method detection limits were elevated for wells MW-1 and MW-2 due to the high levels of some semi-volatile compounds present in the water samples from these wells.

#### C. Area of Suspected Fuel Contamination

Empire collected one (1) composite soil sample from test boring MW-3 and one (1) ground water sample from monitoring well MW-3 for chemical laboratory analysis. The soil sample was analyzed for corrosivity, reactivity and ignitability (hazardous waste characterization) and the full Target Compound List (TCL) parameters using the Toxicity Characteristic Leachate Procedure (TCLP). The ground water sample was analyzed for purgeable aromatic compounds, semi-volatile compounds and total petroleum hydrocarbons (method DOH 310.13). Analytical results for the soil and ground water samples are presented in Appendix E.

Analysis of soil sample MW-3 indicated concentrations of barium at 0.54 milligrams per liter or parts per million (ppm), lead at 0.52 ppm and mercury at 0.0029 ppm. The measured concentrations of these three (3) metals were only slightly above the method detection limits. No concentrations of any other TCL parameters were detected above the method detection limits for soil sample MW-3.

Analysis of the ground water sample from monitoring well MW-3 indicated concentrations of benzene (86 ppb), acenapthene (17 ppb) and fluorene (12 ppb). No concentrations of other purgeable aromatic compounds, semi-volatile compounds or total petroleum hydrocarbons were detected above the method detection limits for the ground water sample from well MW-3.

#### VI. DISCUSSION

Additional site history research revealed that northern half of the subject property was occupied by a facility known as "Citizens Gas Works" in the early 1900's. In Empire's opinion, the tar-like substance, the large pipe fragments and wooden beams discovered in the subsurface at the site are probably remnants of this former gas manufacturing plant. The plant also occupied land to the west of the subject property, where a parking lot for the Waterfront School is presently located.

Laboratory chemical analysis of soil and ground water samples in the area of the black tar-like contamination indicated relatively high levels of BTEX and coal tar-type compounds. Based on the inferred ground water flow direction (i.e. generally east to west), it is likely that these contaminants are being transported off-site toward the adjacent Waterfront School parking lot and Lake Erie (approximately 1/4-mile to the southwest).

Site history research also indicated that a bus garage previously occupied a portion of the site. Leakage from underground fuel tanks associated with the former bus garage is the most probable source of the petroleum fuel-type contamination observed during Empire's subsurface work at the site. The lateral extent of the fuel-type contamination appears to be limited to the area around monitoring well MW-3.

Although petroleum fuel-type odors were noted in test pit excavations in the vicinity of well MW-3, laboratory analytical results for soil and ground water samples from this area did not generally indicate significant concentrations of fuel-type compounds. The concentrations of benzene, acenapthene and fluorene measured in the ground water sample from well MW-3 may indicate that the source of these contaminants is the black tar-like substance, rather than leakage from underground fuel storage tanks which previously existed at the site, since these compounds were detected at relatively high levels in sample TP-3C ("product" sample).

#### VII. CONCLUSIONS AND RECOMMENDATIONS

The conclusions and recommendations presented in the following paragraphs are subject to the limitations presented in Appendix B.

Based on the findings of the Phase II Environmental Investigation completed for the subject property, it is Empire's opinion that the present environmental condition of the site is unsuitable for residential development due to the potential health hazard during construction (workers) and long-term exposure (residents of proposed construction) to the relatively high concentrations of volatile and semi-volatile compounds detected in the soil and ground water near the northwestern portion of the property. The source of these contaminants is apparently a black tar-like substance in the shallow subsurface which probably resulted from a portion of the property being previously used as a gas manufacturing facility. It is likely that these contaminants are being transported off-site to the west via ground water flow in the subsurface.

Petroleum fuel-type odors were observed in test pit excavations in the vicinity of monitoring well MW-3. However, analysis of soil and ground water samples in this area did not indicate significant concentrations of compounds typically associated with petroleum fuels. The compounds that were detected in the ground water sample form well MW-3 are probably related to the black tar-like substance rather than previous leakage at the site.

The relatively minor concentrations of metals (barium, lead and mercury) detected in soil sample MW-3 do not represent a significant environmental liability, in Empire's opinion.

Empire expects that the NYSDEC will require remediation of the black tar-like material and the soils and ground water contaminated with this material. Options for soil remediation at the subject site include (1) excavation, hauling and off-site disposal at an appropriate disposal facility including backfilling with select material, (2) excavation, on-

site treatment with post-treatment replacement of remediated material on-site and (3) on-site bioremediation. Ground water remediation can be addressed with an on-site pump and treat system.

The lateral and vertical extent of soil and ground water contamination must be determined in order to prepare accurate remediation cost estimates. Empire therefore recommends additional subsurface explorations such as test pits, test borings and monitoring wells be completed on the adjacent Waterfront School property to define the northern and western limits of the soil and ground water contamination.

Detailed investigation into various remediation alternatives was beyond the scope of services for this Phase II Environmental Investigation. Relative costs for various remediation alternatives are dependent upon volume of material to be treated, existing contaminant concentrations and regulatory clean-up requirements. For soil remediation, excavation, hauling and off-site disposal is typically the most expensive option. Please note that Empire can provide consulting assistance with regard to remediation alternatives and can also provide project management services for remediation projects of this nature.

If you have any questions or if we can be of further assistance, please contact our office.

Respectfully Submitted,

EMPIRE SOILS INVESTIGATIONS, INC.

mud B- Olrans

. Steiner

David R. Steiner

Senior Environmental Geologist


Donald B. Abrams

Senior Environmental Geologist

drs



## APPENDIX A





## APPENDIX B

#### APPENDIX B LIMITATIONS

- 1. Empire Soils Investigations, Inc. (ESI) work was completed in accordance with generally accepted practices of other consultants undertaking similar studies, and ESI observed that degree of care and skill generally exercised by other consulting under similar circumstances and conditions. ESI's findings and conclusions must be considered not as scientific certainties but as probabilities based on our professional judgement concerning the significance of the limited data gathered during the course of the work.
- 2. The observations described in this report were made under conditions stated therein. The conclusions presented in the report were based solely upon the services described therein and not tasks and procedures beyond the scope of described services or the time and budgetary constraints imposed by the client.
- 3. ESI taped the boring locations from existing structures and measured the ground surface elevations at the borings and referenced them to a bench mark (100.00-feet) established on top of the valve nut on a fire hydrant located near the western border of the site in front of Shoreline Apartment No. 26.
- 4. The generalized soil and rock profile described in the text is intended to convey trends in subsurface conditions. The boundaries between strata are approximate and idealized and have been developed by interpretations of widely spaced explorations and samples; actual soil and rock transitions are probably more gradual. For specific information, refer to the boring logs.
- 5. Water level readings have been made in the explorations at times and under conditions stated in the boring logs. These data have been reviewed and interpretations have been made in the text of this report. However, it must be noted that fluctuations in the level of the groundwater may occur due to variations in rainfall, temperature, and other factors occurring from the time measurements were made.
- 6. Except as noted within the text of the report, no quantitative laboratory testing was performed as part of the site assessment. Where such analyses have been conducted by a laboratory, ESI has relied upon the data provided and has not conducted an independent evaluation of the reliability of these data.
- 7. This report has been prepared for the exclusive use of the Buffalo Urban Renewal Agency and its designated agents for the specific application to the subject property in accordance with generally accepted engineering practice. No other warranty, expressed or implied is made.



## APPENDIX C

TEST PIT FIELD LOG			
	ST PI	T NO. <u>TP</u>	-1
13.0)(15)(1/1/24)(16)(1)(1)(1)		BTA-92	
	TE_	3/25/	92
		_EV	
OPERATOR M. Gaudy TIM		TED 9:	
CAPACITY C.Y. REACH FT. TIM	TE COMP	BOULDER	43
DEPTH SOIL DESCRIPTION	EXCAV. EFFORT	COUNT	REMARK NO.
Black-brown FILL; contains sand, gravel, silt, brick, concrete, metal, boulders	E		BG
Fill heavily coated with sheen, petroleum-odor	M·		5-7
free standing water with oil and sheen at 2.6'	м		25-30
Concrete slab obstruction	М		25-30
Test Pit terminated at 3.9' due to water and obstruction.			
6'-			
7'-			
8'-			
- 9'			
10'			
11'-			
12'			
13'-			
14'-	-		
REMARKS: PID = Photoionization Detector Readings (ppm) Background (BG) PID = 0.2-0.6 ppm	•	,	
Sheen & brown scum on water in test pit, petroleum-odor			
TEST PIT PLAN LEGEND: PROPORTIONS LABBREVIA		EXCAVA	TION
BOULDER COUNT USED F-FINE		EFFO	RT
SIZE RANGE LETTER TRACE (TR) 0 - 10% C-COARSE CLASSIFICATION DESIGNATION	MEDILL	EASY -	
6"-18" A [ETTICE(ET.) 10 - 20 %   F/C-FINE TO		GROUNDY	
NORTH. 18"-36" B   SOME (SO.) 20-35% V-VERY   GR GRAY		TIME TO 2	

			TEST	PIT	FIELD	LOG	;				
E	RAT	TTC	5E		PROJEC					T NO. TP	
801	रें विश्वास	(a, (v)	कार्यंट		ION Phase					BTA-92	
				1	N BURA S		]	DA	ATE	3/25/	92
FNG	SINEER	D. Wa	artinger	EXCA\ CONTRACTOR	VATION EQU Empire So M. Gaudy	IPMENT ils				.EV	
WEATHE			cezv	OPERATOR						TED9:2	
WCATTI				CAPACITY	C.Y. R	EACH	FY.	T 11	YE COMP	LETED 9:4	
DEPTH			SOIL	DESC	RIPŢION	 			EXCAV. EFFORT	BOULDER COUNT QTY, CLASS	REMARK NO.
1'		bould	ers, wood		ns sand, gr oncrete wit				Е		BG
2'-	$\rightarrow$	pipe.							W		BG
3'				oved, wet w	ith heavy s	heen, pet	roleum-		М		5-7
4'		odor. Free		water with	sheen at 3	.21			<u></u>	_	5-7
5'							!				5-7
6'	X										5-7
<del></del> 7'		Test	Pit Termi	nated at 6	.0' due to	water.					
8'-											
9'							•				
10'-											
11'											
12'											
13'	}										
14'	<u> </u>										
REMAR					ctor Readin	gs (ppm)			•	_	
Heavy sl	heen wit	th pet:	ound (BG) roleum od	PID = 0.2- or on fill	·0.6 ppm being remov	wed from	a depth	of	2.8" t	6.0",	
1	ORTH.		BOULDER SIZE RANG CLASSIFICATI 6"-18" 18"-36" 36"AND LAR	COUNT  E LETTER ON DESIGNATIO A B	PROPOR USE TRACE (TR.) LITTLE (LI.) SOME (SO.)	0 - 10 % 10 - 20 %	F-FINE M-MEDI C-COAF F/M-FIN F/C-FIN V-VERY GRGRA	IUM RSE IE TO IE TO	) MEDIUM COARSE	EFFC EASY MODERAT DIFFICUL GROUNDY JELAPSED TIME TO	ORT E E M T D WATER
VOLUME	- =	_C.Y.	JJ AND CAN	JEN O	•		YEL - YE			READING -	=

Į

1

I

TEST PIT FIELD LC	G			
PROJECT DESCRIPTION Phase II ESA LOCATION BURA Site	F	ILE NO.	T NO. <u>TP</u> BTA-92	-060
EXCAVATION EQUIPMEN ENGINEER D. Wartinger contractor Empire Soils OPERATOR M. Gaudy WEATHER Sunny, Breezy MAKE MODEL CAPACITY C.Y. REACH		IME STAR	EV9: TED9: LETED <u>10:</u>	50
DEPTH SOIL DESCRIPTION		EXCAV. EFFORT	BOULDER COUNT OTY CLASS.	REMARK NO.
Brown-black FILL; contains sand, gravel, concrete with rebar, metal pipe	brick, wood	, E		BG
Black seam, tar-like material (coal tar o	odor),	Ď		150
free standing water with heavy sheen at Black viscious tar like material (running coal tar odor		D		1 <u>5</u> 0
-4'-		D	_	70 
Running water with heavy sheen	į.			
Sandy-Silt, tr. gravel (moist-wet), appears of tar-like material	ars to have	E		50
Wood piles appear to have been driven		E		50
Test Pit Terminated at 7.0'.				_
9'	•			_
-10'-				_
11'-				
12'-				
13'-				
<u> </u>				
REMARKS: PID = Photoionization Detector Readings (pp Background (BG) PID = 0.2-0.6 ppm Running water between Fill and natural material with heav from 1.5' to 7.0' plus.		ood Driv	, en piles	
TEST PIT PLAN LEGEND: PROPORTIONS	1	ZNCITAL	EXCAVE	
SIZE RANGE LETTER TRACE (TR.) 0 - 10  CLASSIFICATION DESIGNATION  6"-18" A   LITTLE (LI.) 10 - 20	% F/M-FINE	E TO MEDIUM TO COARSE	EASY	— E E — M T — D
NORTH.	GR GRAY %   BH BROW YEL YELL	н	TIME TO TREADING (HRS.)	₹ G.W.L

		TEST	PIT I	FIELD L	OG				
-B-4.		range		PROJECT		TE	ST PI	T NO	2 4
			DESCRIPTION	ON Phase II E	SA	FI	LE NO	BTA-92-	-060
				BURA Site		DA	TE	3/25/	92
			FYCAVO	TION FOLLIPME	NT	GR	OUND EL	.EV	
ENC	SINEER	. Wartinger (	CONTRACTOR	Empire Soils M. Gaudy				TED 10	
WEATH	R Sun	my, Breezy	AAKE	M. Gaudy  HODEL C.Y. REACH	FY.	TI	4E COMP	LETED 10:	55
DEPTH			DESCR				EXCAV.	BOULDER COUNT	REMARK
DEPIN		SUIL	DESCI	II JIION			EFFORT	QTY. CLASS.	NO.
-0-		rown FILL: con		gravel, silt,	boulders,		Е		BG
2'-				avy coal tar-od	lor		M		100
	ightharpoons	lack, moist	tar-like mat	cerial, heavy o	oal tar odo	r	М		300
							М		200
1	XX				!		М		
5'		unning water ree Standing		heen					
6'—	X								
 7'_	Т	est Pit Termi	nated at 6.	0					
<del>  8</del> '-								<u> </u>	
9'—					-				
10'									
11'-									
12'-									
<u> </u>				•					
-14'-	1							_	
REMAR		= Photoioniz kground (BG)		tor Readings (	ppm)		,	,	J
TEST	PIT PLA	N LEGEN	D:	PROPORTION			ATIONS		
1 1	77777	BOULDER		<u>USED</u>	F - FINE	IUM		EFFC	— E
1-1///			E LETTER ON DESIGNATION		SOOK F/M-FIR	NE TO	NEDIUN	MODERAT	
1 (	$\bigcirc$	6"-18"	A	LITTLE (LI.) 10 -	35% V-VER	Y	COARSE	GROUND	
1	RTH.	18"-36"  36"AND LAR	B GER C		50%   GR GR. 50%   BN BR			TIME TO	₹G.W.L.
VOLUME	: =C.	Y. 36 AND LAN	och C	·	YELY			(HRS.)	=

### TEST PIT FIELD LOG

EN	IP	IR	E
SOUSI	તોષ્ટ્રતાલ	14(O)/B	iýG

PROJECT
DESCRIPTION Phase II ESA
LOCATION BURA Site

TEST PIT NO. \_\_TP-5

FILE NO. \_\_BTA-92-060

DATE \_\_\_\_\_3/6/92

ENGINE	ER_	D.	Wartinger
VEATHER	Sur	ıny,	Breezv

EXCAVATION EQUIPMENT

CONTRACTOR Empire Soils

OPERATOR M. Gaudy

MAKE HODEL

CAPACITY C.Y. REACH FT

TIME STARTED 11:00
TIME COMPLETED 11:20

	CAPACITY C.I. REACH			,
DEPTH	SOIL DESCRIPTION	EXCAV. EFFORT	BOULDER COUNT	REMARK NO.
0'-	Brown-Black FILL; contains sand, gravel, boulder, concrete, brick, wood, glass	E		BG_
		м.		50
2'-	Heavy coal tar-odor	М		100
3'-	Free standing water with heavy sheen			-
4'-	Flat, appears to be wood obstruction	M		100
5'	X \ .	M		100
6.	Test Pit Terminated at 4.6' due to obstruction.			
6				
'7'				
8,—		<b></b>		
9'-				
10'				
-11'-				
-12'-		-		-
-13'-				-
-14'-				
- 14		1		

REMARKS: PID = Photoionization Detector Readings (ppm)

Background (BG) PID = 0.2-0.6 ppm

Appears to be flat wooden obstruction at bottom of test pit.

TEST PIT PLAN	LEGEND:	PROPORTIONS	ABBREVIATIONS	EXCAVATION
<del>   </del>	BOULDER COUNT	USED	F-FINE	EFFORT
	SIZE RANGE LETTER CLASSIFICATION DESIGNATION	TRACE (TR.) 0 - 10%	C-COARSE	EASY E MODERATE M
T	6"-18" A	LITTLE (LI.) 10 - 20 %	F/C-FINE TO COARSE	i pirricoci o i
NORTH.	18"-36" B	SOME (SO.) 20-35%	. A. AFKI	ELAPSED
VOLUME =C.Y.	36"AND LARGER C	AND 35-50%	BNBROWN YELYELLOW	READING -
	18"-36" B	SOME (SO.) 20-35%	V-VERY GRGRAY BNBROWN	ELAPSED TIME TO 27 GWI

### TEST PIT FIELD LOG

<b>EMPIRE</b>
SOMETIVESMEATIONSING

PROJECT DESCRIPTION Phase II ESA LOCATION BURA Site

TEST PIT NO. <u>TP-6</u>

FILE NO. <u>BTA-92-060</u>

DATE \_\_\_\_\_\_ 3/25/92

ENGINEER D. Wartinger	EXCAVATION EQUIPMENT CONTRACTOR Empire Soils	GROUND ELEV
	OPERATOR M. Gaudy	TIME STARTED11:25
WEATHER Sunny, Breezy	MAKE HODEL CAPACITY C.Y. REACH FT.	TIME COMPLETED 11:45
	CATACITY REACT	

	CAPACITY C.Y. REACH FT.			
DEPTH	SOIL DESCRIPTION	EXCAV. EFFORT	BOULDER COUNT QTY, CLASS	REMARK NO.
	Brown FILL; contains sand, silt, brick, concrete, pipe (1/2") boulder, wood, etc.	Е	-	BG
2'-	Becomes black, coal tar-odor	М		50
3'-	Since Since, conf car one?	М		70
4'	Running water with sheen	М		70
5'-	Sandy-Silt (moist-wet), contains tar-like seams	М		30
6'—	Free Standing Water with sheen	Е		
7'-		Е		
8'-	Test Pit terminated at 7.0' due to water.			
— 9' —	-		, <u>.</u>	
10'				
11'-				
12'-		-		
<u> </u>			_	
—14 <b>'</b> —				

REMARKS: PID = Photoionization Detector Readings (ppm)

Background (BG) PID = 0.2-0.6 ppm

TEST PIT PLAN	LEGEND: BOULDER COUNT	PROPORTIONS USED	ABBREVIATIONS	EXCAVATION EFFORT
NORTH.	SIZE RANGE LETTER CLASSIFICATION DESIGNATION 6"-18" A	LITTLE(LI.) 10 - 20 %   SOME (SO.) 20 - 35 %	V-VERY GRGRAY	GROUNDWATER ELAPSED TIME TO \$27 GW.L.
VOLUME =C.Y.	30 AND LANGER C		YEL - YELLOW	(HRS.)

### TEST PIT FIELD LOG

LOCATION \_\_\_\_

EMPIRE South Management	

**PROJECT** DESCRIPTION Phase II ESA BURA Site

TEST PIT NO. TP-7 FILE NO. \_\_BTA-92-060 DATE \_\_\_\_\_3/25/92

ENCINCED D. Wartinger	EXCAVATION EQUIPMENT CONTRACTOR Empire Soils	GROUND ELEV.
	OPERATORM. Gaudy	TIME STARTED 12:40
WEATHER Sunny, Breezy		TIME COMPLETED 1:05
	CAPACITY C.Y. REACH FT.	

	CAPACITY C.Y. REACH FT.	IME COMP	LEIED	.00
DEPTH	SOIL DESCRIPTION	EXCAV. EFFORT	BOULDER COUNT OTY CLASS	REMARK NO.
1'	Brown FILL; contains sand, silt, brick, concrete, boulders, metal, pipe	М		BG
2'-		M		50
3'-	Becomes black, tar-like material, coal tar odor Greenish-black running liquid, heavy sheen	М		<u>70</u>
4'-	Lt. brown sandy-silt, tr. gravel, contains black	M		30
5'-	seams of tar-like material	М		
6'-		М		
7'-	Test Pit terminated at 6.0'.	Е		
<u> </u> −8'−				
9'-				
10'-				
-11'-				
12'-				
13'-				
14'-				
14				

REMARKS: PID = Photoionization Detector Readings (ppm) Background (BG) PID = 0.2-0.6 ppm

	TEST PIT PLAN
1	Turn
ı	NORTH.
J	VOLUME =C.Y.

BOULDER COUNT SIZE RANGE LETTER TRACE (TR) 0 - 10% C - COARSE

LEGEND:

6.-18.

18"-36"

36 AND LARGER

CLASSIFICATION DESIGNATION!

В

1 SOME (SO.) 20-35% DHA 35-50% | BN.-BROWN

**PROPORTIONS** 

USED

IABBREVIATIONS F-FINE

M - MEDIUM F/M-FINE TO MEDIUM DIFFICULT - D LITTLE (LI.) 10 - 20% F/C-FINE TO COARSE V-VERY GR. GRAY

YEL. - YELLOW

EASY -MODERATE - M IGROUNDWATER TIME TO 2 G.W.L

(HRS.)

EXCAVATION

**EFFORT** 

		TEST	PIT F	FIELD	LOG					
	RATE	TOT	1	PROJEC			TE	EST PI	T NOT	P-8
San Sinus Welvions in C			DESCRIPTION Phase II ESA			FILE NOBTA-92-060				
	3.00-3.5		LOCATION_	BURA Si	te		DA	ATE	3/6/9	2
		D. Wartinger	EXCAVA	TION EQUI	PMENT		G R	OUND EL	_EV	
ENG	SINEER _	D. Wartinger	OPERATOR	M. Gaudy	.13				TED1:1	
WEATHE	:Rsu	nny, Breezy	CAPACITY	C.Y. RE	DEL	FT.	TII	YE COMP	LETED 1:3	5
DEPTH			DESCRI					EXCAV. EFFORT	BOULDER COUNT OTY, CLASS.	REMARK NO.
-0-			onsists of b			,		Е		BG
2'		Becomes blac	k, tar-like m	material,	heavy co	al tar-		M		30
1	$\langle \times \rangle$	odor						М		70
3 -		Water seepin	g in with sh	neen				М		30
5'		Sandy-Silt (	moist, wet),	tr. grave	l, black	seams		M		
6'-								М		
								М		
		Test Pit Ter	minated at 8.	.0'.				Е		
9'										
-10'-										-
1'										
12'										
13'										
_14'_										
REMAR		ID = Photoioniz ackground (BG)		-	s (ppm)			,	,	
		No Free Stan	ding Water no	oted						
TEST	PIT PL	AN LEGEN	D:	PROPORT	TIONS I	ABBRE	EVIA	ZNOITA	EXCAVA	TION
1 1-		BOULDER		USE	<u>_</u>	F-FINE			EFFO	
		SIZE RANG	E LETTER	TRACE (TR)	0 - 10%	M - MEDI   C - COAR	RSE		LEASY	<del></del> Е Е <b>- м</b>
T		6 - 18 -	ON DESIGNATION!	LITTLE(LI.)	10 - 20%	F/K-FIN F/C-FIN	IE TO	MEDIUM COARSE	GROUND	T D
NO	RTH.	18-36	8	SOME (SO.)		GR. GRA	¥Υ		IFL APSED	
VOLUME	=	C.Y. 36"AND LAR	GER C	AND .	35-50%	BN. BRO			TIME TO	<u>{/</u> G.W.L.  <u>=</u>

4 -										
		TES	F PIT	FIELD	LOC	3				
JE T	BAT	OTDT		PROJEC	CT ,		TE	ST PI	T NO. TP	-9
200	STATISTIC	awokawa	DESCRIPT	ION Phase	II ESA		FI	LE NO	BTA-92	-060
			LOCATION	U BURA S	ite		DA	ATE	3/6/9	2
CAL	CINCED	D.R. Steiner	EXCA	VATION EQU	IPMENT		GR	OUND EL	_EV	
			OPERATOR				TI	HE STAR	TED2:2	5 pm
WEATH	-R <u>F. C</u>	loudy, Breezy 30's	CAPACITY		EACH	FT.	TI	IE COMP	LETED 2:3	5 pm
DEPTH		SOIL	DESCR	RIPTION				EXCAV. EFFORT	BOULDER COUNT QTY. CLASS.	REMARK NO.
	XX	Brown FILL; o			arge amou	ınt of		М		BG_
2'	$\times$	Water at 2.6	•		er			М.		BG
ر ر	(X)									
3'								M		.BG.
<u>     4</u> '—		Test Pit Term	ninated at	3.2'.						
5'						<u> </u>			_	
6'-										
<del></del> 7'										
<del></del> 8'										
<del></del> 9'										
<u>    10'                                </u>		•								
11'										
<u></u> 12'										
13'										
<del></del> 14'										
REMAR	KS: PI	D = Photoioniz	ation Date	ctor Reading	75 (nnm)					
	Ва	eckground (BG) ight sheen on	PID = 0.2-6		23 (bbm)					
TEST	PIT PL	AN LEGEN	D:	PROPOR	TIONS	IABBRE	VIA	TIONS.	EXCAVA	TION
1 1-		BOULDER	COUNT	USE		F-FINE		1	EFFO	
7///		SIZE RANG	E LETTER ON DESIGNATIO	TRACE (TR.)	0 - 10%	M - MEDIL C - COAR	SE	l I	EASY -	— E
T		6"-18"	A DESIGNATIO	ונודדנב(נו.)	10 - 20%	F/M-FINE	E TO	COARCE	DIFFICULT	— D
иои	RTH.	1836	В	SOME (SO.)	20-35%	V-VERY		1.	GROUNDW ELAPSED	
VOLUME	=	C.Y. 36"AND LAR	GER C	1 AND	35-50%	BN BRO		w i	TIME TO 2 READING (HRS.)	/ G.W.L.

		TEST	PIT	FIELD	ĽOG	;					
	RAPTI	DE.	· · · · · · · · · · · · · · · · · · ·	PROJEC		•	TEST F	TONOT	P-10		
201	31/1/22/1/03/14(	निर्मावर्ग	DESCRIPTI	ON Phase	II ESA		FILE N	O. <u>BTA-92</u>	-060_		
			LOCATION				DATE_	3/6/9	2		
FNO	SINEER D.R.	Steiner	CONTRACTOR	ATION EQU Empire So	IPMENT		GROUND ELEV				
WEATHE	FR P. Cloudy	. Breezv						RTED $_{-11:0}$			
WEAT III	P. Cloudy	s	CAPACITY	C.Y. R	EACH	FY.	TIME CO	BOULDER	1.20 211		
DEPTH		SOIL	DESCR	IPTION			EXCA	V. COUNT	REMARK NO.		
	IA X 1		ILL; contai l pipe frag	-		ilt,	E		BG		
2'-	B1 2.	ack seam w 5-4.0', al	ith obvious so tar-like	sheen and		e odor	М -		BG		
3'-	Wa	ter trick	ling in at	4.5'			E		150-		
		·					E		200		
5'-						!	E		BG		
6,-							E		BG		
	Tes	st Pit Ter	minated at	6.0'.			-				
<b>├</b> ─-7'—									1 -1		
8'-											
9'—						•					
-10'-											
11'-		•									
-12'-											
13'-											
14'-								-			
REMAR	RKS: PID =		ation Detec		gs (ppm)			,			
	_		n, strong t		or	PID = 1	50-200	ppm			
TEST	PIT PLAN	LEGEN BOULDER	D:	PROPOR USE	TIONS	F-FINE		S EXCAVA	-		
T		SIZE RANG CLASSIFICATION	E LETTER ON DESIGNATION	TRACE (TR.)		F/C-FINE	SE E TO MEDIL		τ — ο		
МО	RTH.	18"-36"	8	SOME (SO.)	20-35%	V-VERY		IFI APSED			
VOLUME	=C.Y.	36"AND LAR	GER C	DHA	35-50%	BH BRO YEL YE		TIME TO	€/ G.W.L. =		

		TEST	PIT F	FIELD	LOG			-	
E		PIRE	DESCRIPTION .	BURA Si	I ESA _	·	FILE N	PIT NOT IOBTA-92 3/6/9	2-060
		D.R. Steiner loudy, Breezy 30's	EXCAVA CONTRACTOR OPERATOR CARE CAPACITY	TION EQUI Empire Soi M. Gaudy	ls	FT.	TIME ST	ELEV ARTED10:2 MPLETED1	
DEPTH			DESCR				EXCA EFFO	1 000	NO.
-0'- -1'- -2'-		Dark brown FI concrete frag boulders	nents, metal				E		BG
—3'— —4'—		Encountered p tar-like subs east and cont orientation. I at 3.0' with meter approx.	tance below inued to exc Encountered E-W orientat	pipe. Mov avate deep very large ion. Large	ed a few er. Pipe , steel <sub>l</sub> Pipe has	feet e has N- pipe s dia-	-S		200+
— 5'— — 6'—		from about 4.0 Water seems to on N & S side:	)-4.5°. PID be mixed w	0 = 200 + ppm with black	on black	k ooze.			
—7'— —8'—		Took Dit Town		0.1					
— 9 <b>'</b> —		Test Pit Term	nated at o.	0.		•			
10'									
— I2'—									
—13'—									
REMAR		ID = Photoioniz ackground (BG)		-	s (ppm)			,	
1 H	PIT PL	BOULDER SIZE RANG	COUNT  E LETTER ON DESIGNATION A B	PROPORTUSE  TRACE (TR.)  LITTLE (LI.)  SOME (SO.)  AND	0 - 10 % 10 - 20 %	F/C-FINI V-VERY GR GRA	UM SE E TO MEDI E TO COAR Y OWN	EASY —   EASY —   MODERAT	DRT  E = M I - D WATER

			TEST	PIT	FIELD	LOG				
	E	VIPI INDENDATION	RE		PROJECTON Phase I	I ESA	F	ILE NO	BTA-92-	-060
1				EYCAV	BURA SI	PMENT	l		3/6/9:	
		INEER D.R.	, Breezy	CONTRACTOR _ OPERATOR MAKE	Empire Soi M. Gaudy	1s		ME STAR	EV	5 am
ŀ			's	CAPACITY	C.Y. RE	ACH	<u> </u>		BOULDER	
	DEPTH		SOIL	DESCR	RIPTION			EXCAV. EFFORT	COUNT QTY, CLASS.	REMARK NO.
	ı'				s sand, gra		,	Е		BG
	2'	Con	tains blac	k seam with	obvious sh	een and ta	ar-like	M		BG .
	—3'—			', sandy co				М	· .	5-10
	— 4'—	Tes	t Pit Term	inated at 3	.5' due to	water.				
	5'	Wat	er stabili	zed at 2.0'			,			
	<del></del> 6'									
- [	— 7'—							<del></del>		
	—- 8 <b>'</b> —									
ł	— 9'—									
ŀ	—10'—									
	11'									
	— 12 <b>'</b> —									
	13'									
	<u></u> 14'−									-
	REMAR			zation Detec	ctor Reading	s (ppm)		•	,	
		backgr amination neen on water	ot as exte	nsive (odor	, vertical	extent, P	ID) as T	`P-10 ar	nd TP-11	
		PIT PLAN	LEGEN		PROPOR		ABBREV	RIONS	EXCAVA	
Į	11-	{ 77777}	BOULDER SIZE RANG		TRACE (TR.)	_ 1	F - FINE M - MEDIUM		EFFC	-
	T 1/1/		CLASSIFICATI	ON DESIGNATIO	LITTLE(LI.)		C - COARSE F/M - FINE T F/C - FINE T	O MEDIUN	I MODERAT	E — M T — D
	, (	) RTH.	18"-36"	В	SOME (SO.)	20-35%	V-VERY GRGRAY	O COMRSE	ELAPSED	
	VOLUME		36"AND LAR	GER C	OHA	35-50% [			TIME TO	<u>2∕</u> G.W.L.

	TEST PIT	FIELD LOG	ì			
EMPI		PROJECT . TION Phase II ESA BURA Site	FI	LE NO	T NO. <u>TP-</u> BTA-92-	-060
ENGINEER D.R. WEATHER P. Cloudy	EVCAL	VATION EQUIPMENT Empire Soils	GR TI	OUND EL	EV	40 pm
DEPTH	SOIL DESCR			EXCAV. EFFORT	BOULDER COUNT QTY, CLASS.	REMARK NO.
	wn FILL; contains san crete fragments, wood		icks,	M		
1 IX \(\triangle \)	er entering at 3.5'			м		
2' Mate	erial has petroleum-1 -like odor, PID = 3-9	type sheen at 4.0' 5 ppm		М		3-5
4'-				M		3-5
-5'- Test	t Pit Terminated at 4	4.5'	!	-		
6'-						
7'-						
8'-				-		
9'-			•			
10'-						
11'-	·					
12'-						
13'-						
14'-						
Backgr Odor l	Photoionization Deteround (BG) PID = 0.2- like Test Pit TP-11 e contamination (she	0.6 ppm		,	,	
TEST PIT PLAN  I PLAN  NORTH.  VOLUME =C.Y.	LEGEND:  BOULDER COUNT  SIZE RANGE LETTER CLASSIFICATION DESIGNATIO  6"-18" A  18"-36" B  36"AND LARGER C	USED  TRACE (TR) 0 - 10 %  LITTLE (LI.) 10 - 20 %  SOME (SO.) 20-35 %	ABBREVIA  F - FINE  M - MEDIUM  C - COARSE  F/M - FINE TO  F/C - FINE TO  V - VERY  GR GRAY  BN BROWN  YEL YELLO	MEDIUM COARSE	EFFO	RT - E - M - D VATER

·		TEST	PIT	FIELD	LOG	,				]
E.	RAPT	PF		PROJEC			TE	ST PI	T NOTP	-14
Son	Silvisidani	Onanc		ION Phase I			FIL	E NO	BTA-92	-060
				BURA Si			DA	TE	3/6/9	2
ENG	SINEER D.R	. Steiner	EXCAV CONTRACTOR	ATION EQUI Empire Soi M. Gaudy	PMENT				.EV	
	R P. Cloud	v. Breezv	HAKE	1/0	0.51				TED 12:5	
·	3			C.Y. RE		FY.			BOULDER	
DEPTH		SOIL	DESCF	SIPŢION			1	EXCAV. EFFORT	COUNT	REMARK NO.
0'-							-		OTY. CLASS.	
1*	A Bro	own-black F agments, la	ILL; conta:	ins sand, ci	nders, c	concrete	L	M		BG
				water stabi	lized at	1.7'.				
2'	X ) .				<del></del>		-	<u>M</u>	-	BG
~!	Tes	st Pit Term	inated at 2	2.01 due to	water.		Ì			
3					ĭ					
<u>     4'                               </u>							-	_		
_1						!	- {			
5'		•								
<del></del> 6'							-			
-7-										
<u> </u>							-			
- 1										
9'										
10'										
							}			
-12'										
<b>一13</b> '一							-			
—14 <b>'</b> —							-			
REMAR	KS: PID =	Photoioniz	ation Detec	tor Readings	s (ppm)					
	Backgr	cound (BG)	PID = 0.2-0	).6 ppm					,	
	Very	slight, spo	tty sheen	on water in	test pit	· _				
TEST 1	PIT PLAN	LEGEN	D:	PROPORT	10NS 1	ABBRE	VIAI	CIONS,	EXCAVA	TION
11-		BOULDER		USEC	<u> </u>	F - FINE M - MEDIU	· ·	1	EFFO	
_////		SIZE RANGE	E LETTER ON DESIGNATION			C - COARS	38	, EU	EASY	— ε — <b>м</b>
1 (	$\supset$	6"-18"	A	SOME (SO.)		F/C-FINE V-VERY	то с	OFFE	DIFFICULT GROUNDW	
	RTH.	18"-36" 36"AND LARG	B ER C	1	- 1	GR. GRAY		į	ELAPSED TIME TO 2	
VOLUME	= C.Y.	30 AND LANG			2 20 70 1	YEL YEL		, 1 	READING =	= 0.11.0.

			TEST	r PIT	-	HELD	LOG	3				·
	RAT	OTT	)E			PROJEC			TE	EST PI	T NOTF	2-15
हिं <u>न</u>		तः(५(०))	क्रांग्रेन			N Phase			F١	LE NO	BTA-92	-060
						BURA S			DA	ATE	3/6/9	2
FNC	SINEER	D.R.	Steiner	EXC	NR.	TION EQU Empire So	IPMENT				_EV	
1				OPERATOR		m. Gaudy	00EL				TED 1:10	
	1	30'		MAKE		C.Y. RE	EACH	FY.	711	ME COMP	BOULDER	20
DEPTH	}		SOIL	DESC	CRI	PTION				EXCAV. EFFORT	COUNT	REMARK NO.
o'	75 71				· · · · ·	<del>-</del>					OTY. CLASS.	
	XX					ains sand				М		BG
	large amount of brick, also contains clayey silt. Material has very apparent petroleum sheen at											H 199
<u> </u>	approximately 3.0' Water entering from 2-different levels, water sta-									<u>M</u>		BG
	KXJ					s obvious		cr sta		М		10-20
3'—	XX		-							<del> </del>	·	
4'—												
4-		Test	Pit Term:	inated at	3.5	<b>''.</b>		!				
5'	1		•									
C:												
	]					•						
<del> </del>						•				· <u>-</u>		
1 0!												
8	1											
<u> </u>												
		•										
10,-												-
11'-	] ]											
										ļ		
12'-	1										<u>-</u>	
  13'	]											
13												
14'—	}											
REMAR	7KS: P1	ID = P	hotoioniz	ation De	tect	or Reading	es (ppm)			·	L	
				PID = 0.			) - (FFm)				,	
	На	s die	sel fuel-	type odo	r							
TEST	PIT PL	INA	LEGEN	ID:		PROPOR	TIONS	ı ABBRE	VIA	TIONS.	EXCAVA	TION
1 1-			BOULDER		l l	USE		F-FINE		<u>-</u> [	EFFO	
			SIZE RANG	E LETTE	R I	TRACE (TR)	0 - 10%	M - MEDII	SE	1	EASY	— E
T (			6-18	A	11	LITTLE (LI.)		F/K-FIN F/C-FINI			GROUNDY	a —
NO	RTH.		18"-36"	В	l	SOME (SO.)		V-VERY		1	ELAPSED TIME TO 2	
VOLUME	=	C.Y.	36 AND LAR	GER C	1	AND .	35-50%	BNBRC	LLO	w	READING =	/_G.W.L.

		TEST F	PIT F	FIELD	LOG				
	EMPI	Loc	ATION_	PROJEC ON Phase BURA S	II ESA		FILE NO	T NO. <u>TP</u> BTA-92	-060
	ENGINEER D.R WEATHER P. Cloud	Steiner CONTR	ACTOR	Empire So M. Gaudy	ils	FY.	GROUND EL	EV1:4 PLETED 1:5	0 PM 0 PM
	DEPTH .	SOIL DE	SCRI	IPTION			EXCAV. EFFORT	BOULDER COUNT OTY, CLASS,	REMARK NO.
	, Coi	own and black F ncrete fragment ter at 1.7'	ILL; con	ntains san s, boulde	d, gravel	, ,	M	- :	BG
	-2'-								
	— 4'—	st Pit Terminat	ed at 2.	8	· · · · · · · · · · · · · · · · · · ·			-	
į	5'					!			
	— 6'—								
	— 7'— — 8'—								
	9'-					-	-		
-	10'								
	1 1'								
	— 12'— —13'—								-
	-14'-								
	REMARKS: PID = Backgr	Photoionization cound (BG) PID =			gs (ppm)		•	,	
	TEST PIT PLAN  LITTURE OF THE NORTH.	6-18- 18-36	ETTER 1 SIGNATION A 1 B 1	PROPOR  USE  TRACE (TR)  LITTLE (LI.)  SOME (SO.)  AND	O - 10 %   10 - 20 %   20 - 35 %	F - FINE M - MEDIU C - COARS F/M - FINE F/C - FINE V - VERY GR - GRAY	SE TO MEDIUM TO COARSE	EFFO EASY—	RT — E E — M — D VATER
	VOLUME =C.Y.	36 AND LARGER	c I		35-50% [	YEL. YEI		READING	= 0

[ -	TEST PIT FIELD LOG				
	PROJECT DESCRIPTION Phase II ESA LOCATION BURA Site	F	LE NO	T NO. <u>TP-</u> BTA-92	-060
	EXCAVATION EQUIPMENT  ENGINEER D.R. Steiner CONTRACTOR Empire Soils  OPERATOR M. Gaudy  WEATHER P. Cloudy, Breezy  30's CAPACITY C.Y. REACH		ME STAR	EV	20 pm
ſ	DEPTH SOIL DESCRIPTION		EXCAV. EFFORT	BOULDER COUNT OTY. CLASS.	REMARK NO.
1	Brown Soil FILL; contains clayey silt, sand, concrete fragments, large amount of bricks		E		BG
!	Bricks and large concrete fragments (old fou	ndations)	D.		BG
	Test Pit Terminated at 2.0'.				
	4'				
	5'	į			_
i 	6'-				
1.	├ <b>-</b> 7'-				
	8'-	-			
	9'-				
<u> </u>					
<u>'</u> _	12'-				
_	13'-				
_	14'-				
	REMARKS: PID = Photoionization Detector Readings (ppm) Background (BG) PID = 0.2-0.6 ppm No visible contamination	<u>.</u>	•	,	
_	LICED 1	ABBREVIA	SNCITA	EXCAVA	
	SIZE RANGE LETTER TRACE (TR.) 0 - 10%   CLASSIFICATION DESIGNATION   LITTLE (LI.) 10 - 20%	M - MEDIUM C - COARSE F/M - FINE TO F/C - FINE TO	MEDIUM COARSE	EASY	— E
-	NORTH. 18 36 B 1 AND 25 50% 1	V-VERY GRGRAY BNBROWN YEL-YELLO	1	ELAPSED TIME TO 22 READING	

#### TEST PIT FIELD LOG TEST PIT NO. TP-18 **PROJECT** DESCRIPTION Phase II ESA FILE NO. BTA-92-060 BURA Site DATE \_\_\_\_\_ 3/6/92 LOCATION \_ EXCAVATION EQUIPMENT ENGINEER D.R. Steiner GROUND ELEV. \_ CONTRACTOR \_ Empire Soils TIME STARTED \_\_ 2:00 pm M. Gaudy OPERATOR \_ WEATHER P. Cloudy, Breezy MAKE TIME COMPLETED 2:20 30's ' BOULDER SOIL DESCRIPTION EXCAV. REMARK DEPTH COUNT EFFORT NO. QTY. CLASS - O'-Dark brown FILL; contains sand, gravel, bricks, E BG boulders, cinders, clayey silt, wood Ε BG2'-Black clayey silt seam and lense has PID=3-5 ppm Seam at 3.5', lense at 2.0' Ε 3-5 3**'**· Top of Pipe at 3.0', Pipe diameter apprx. 16" Water entering at 2.0' Ε <del>-1</del>3-5 Concrete "wall" E. of pipe, Top approx. 2.2' deep Ε ΒG Ε ΒG 6' Test Pit Terminated at 6.0' 9'-·10**'**-11'-· 12'-13'--14'-REMARKS: PID = Photoionization Detector Readings (ppm) Background (BG) PID = 0.2-0.6 ppm Black material has tar odor, rest of soil/fill at BG. LEGEND: TEST PIT PLAN PROPORTIONS ABBREVIATIONS, EXCAVATION USED F-FINE **EFFORT** BOULDER COUNT M - MEDIUM TRACE (TR) 0 - 10% | C - COARSE LETTER EASY -SIZE RANGE MODERATE - M CLASSIFICATION DESIGNATION! F/M-FINE TO MEDIUM DIFFICULT - D | LITTLE(LI.) 10 - 20 % | F/C-FINE TO COARSE | GROUNDWATER 6"-18" А SOME (SO.) 20-35% 18-36 В NORTH. 1 GR. GRAY TIME TO SO G.W.L

36 AND LARGER

C.Y.

VOLUME =

35-50% | BH.-BROWN

YEL. TELLOW

READING -

(HRS.)

TEST PIT FIELD LOG				
PROJECT DESCRIPTION Phase II ESA LOCATION BURA Site	FI	LE NO.	NO. <u>TP-</u> BTA-92 3/6/9	-060
EXCAVATION EQUIPMENT  CONTRACTOR Empire Soils  OPERATOR M. Gaudy  WEATHER P. Cloudy, Breezy  30's CAPACITY C.Y. REACH FT.	TIL	LE STAR	EV	pm
DEPTH SOIL DESCRIPTION		EXCAV. EFFORT	BOULDER COUNT QTY. CLASS.	REMARK NO.
Dark brown FILL; contains sand, clayey silt, bricks, concrete fragments		_ E		BG
		м		BG
Light tan material with sandy silt consistency Water entering at 3.0' Ash?		E		BG
4'		E		BG
Dark grey clayey silt, little sand		E.		BG —
		E		BG
— 6'— — — — — — — — — — — — — — — — — —		E		BG
-8'-	,	Е		BG
Test Pit Terminated at 8.5'.			-	
-10'-				
— I I'—				
-12' <del>-</del>				
REMARKS: PID = Photoionization Detector Readings (ppm)  Background (BG) PID = 0.2-0.6 ppm  No visible petroleum contamination observed			,	
TEST PIT PLAN LEGEND:  BOULDER COUNT  SIZE RANGE LETTER TRACE (TR.) 0 - 10% C-COAR CLASSIFICATION DESIGNATION  6"-18"  A   LITTLE(LI.) 10 - 20% F/C-FINE	UM SE E TO E TO	MEDIUM,	EXCAVA  EFFO  EASY — MODERATE DIFFICULT GROUNDY	RT — E — M
NORTH. 18-36- B   SOME (SO.) 20-35%   V-VERY   GR GRA	Y	ĺ	ELAPSED TIME TO	
OLUME =C.Y. 36 AND LARGER C AND 35-50% BNBRO		w l	READING	Z G.W.L.

		TEST	r PIT I	FIELD	LOG	;				٠.
F.	RAPT	RE.		PROJEC	E.				T NO. TH	
Sor	इंग्लिब्ब्ला	oluan	DESCRIPTION			· ·			BTA-92	
			LOCATION				DA	ATE	3/6/9	2
ENG	SINEER D.R.	. Steiner	CONTRACTOR	ATION EQUI	IPMENI ils				EV	
1	R P. Cloudy 30		OPERATOR	M. Gaudy	DEL		TII	ME STAR ME COMP	TED <u>9:3</u> LETED <u>9:5</u>	50
	3(					F1.			BOULDER	1
DEPTH		SOIL	DESCR	IPTION		<u> </u>		EXCAV. EFFORT	COUNT	REMARK NO.
			contains sa al pipe frag		, clayey	silt,		E		BG
1'			P2P0 2106							
2'	1/ \/ \	-	oncrete pave					D		BG
		lack and g	ray fill, sa	ndy silt co	onsisten	cy, wood	Ι,	E	<u> </u>	₿G
	Wa	ter trick	ling into te	st pit at i	3.6'			E	-	BG
4'	W <sub>2</sub>	ater level	stabilized	at approx	<b>γς</b> 1	1	•	E		
5'		,	Stabilized	at approx.	2.0	·				BG
6'	XX							E		BG
	Te	est Pit Te	rminated at	6.01.						
7'-								·		
<u> </u>					-					
9'—						•				
10'									1	
<del>10</del>										
11'-										
12'										
13'										
<u> </u>										
REMAR			zation Detec		gs (ppm)			,	,	
	васка	cound (bG)	PID = 0.2-0	.o ppm						
TEST	PIT PLAN	LEGEN	ID:	PROPOR	TIONS	IABBRE	VIV	ZNOITA	EXCAVA	TION
1		BOULDER	COUNT	USE		F-FINE			EFFO	
		SIZE RANG	E LETTER ON DESIGNATION	TRACE (TR.)	0 - 10%	C - COAR	SE		EASY	E-#
1 (		618_	A	LITTLE (LI.)		F/M-FIN F/C-FIN	E TO	COARSE	I DIFFICULT	
[	RTH.	18"-36"	-	SOME (SO.)		V-VERY	۲		ELAPSED TIME TO	
VOLUME	=C.Y.	36 AND LAR	GER C		35-50%	YELYE			READING =	

		IESI	PIL	FIELD	LUC	3				
F	RAPT	PF		PROJEC			TE	ST PI	T NOT	P-21
<b>3</b> 000	डेग् <u>री</u> एड्रेस्ट्रिस	onario	DESCRIPT	ION Phase			FII	LE NO	BTA-92	-060_
			LOCATION				DA	TE	3/6/9	2
ENG	SINEERD.I	R. Steiner	CONTRACTOR	ATION EQU Empire Sc	JIPMENT				EV	
ł	R P. Cloud		OPERATOR	M. Gaudy					TED9:0	
		80's	MAKE	C.Y. R	EACH	FT.	11~	COMP	BOULDER	
DEPTH		SOIL	DESCF	RIPTION	1			EXCAV. EFFORT	COUNT	REMARK NO.
o'	X / Br	own, FILL;	contains sa	and, gravel	clavey	eilt	-		QTY. CLASS.	
1'	bo	ulders, bri	cks, pipe f	ragments (	moist)	5110,		E		BG
·	X 1	phaltic cón	oriete desseina					M		20
2'—	X X wo	od and soil	fill	ient			Ì			BG
3'								M	_	BG
3	Gr	ay, wet, sa	ndy fill ma	terial, has	s petrole	um odor,		77		
4'-	X PII	D = 5+ ppm ulder. Wat	on stockpil er running	e. Sheen a	also seen Sheen	on		E		5
٠, ١	in	test pit.	22 2428	III ac 5.5 .	. Sheen	oif water		E		
5 -	Te	st Pit term	inated at 5	.0'.						
6'							-			
_,,							-			
/ /					,			·		
<u></u> 8'—							-			
9'	-						Ì			
10'										
							1			
-11							1			
- 12'-										
13'-							-			
<u> </u>							}			
REMAR		Photoioniz round (BG)			gs (ppm)			•	,	
		ible petrol			odor				·	
TECT		T								
TEST I	PIT PLAN	LEGEN	-	PROPOR		ABBRE	VIA.	ISNCIT		
10///	77777	BOULDER SIZE RANGE		TRACE (TR.)	_	F-FINE	М	1	EFFOI	E
T			N DESIGNATION	ILITTLE(LI.)		C-COARS	TO	MEDIUM	MODERATE	— M
NOF	) RTH	1836_	8	SOME (SO.)		F/C-FINE V-VERY		1.	GROUNDW	
VOLUME		36"AND LARG		DHA		GR GRAY	<b>₩</b> N	i	TIME TO 2	<u>7</u> G.W.L.
		1				YEL YEL	LOV	<b>Y</b>	(HRS.)	-

  -	•	TEST P	IT FIE	LD LOG				
r	EMPI South Mandari		PROCRIPTION PROCRIPTION BI			FILE NO	T NO. <u>TP-</u> ). <u>BTA-92</u> 3/6/9	060
	ENGINEER D.R. WEATHER P. Cloudy	Steiner CONTRA	CTOR _ Empi	EQUIPMENT TE SOILS TOUCHUS TOU	FY	TIME STAF	LEV9; PLETED 10:	50
	DEPTH	SOIL DE		ION		EXCAV. EFFORT	COOKI	REMARK NO.
1	Bro bou	wn FILL; contain	ns sand, gra fragments,	vel, clayey si slag	llt,	E		BG
		haltic concrete				D		BG
	-3' ─ odo Gra	' - seam of hard r, has small gra y and black wet	evel in it			, М		BG BG-0.8
	3.5	2-4' ' Wood layer ' Top of brick -			!		_	BG-0.8
	-5'-4.4 -6'-	Water entering	g under bric	k layer		1		
	Tes	t Pit Terminated er stabilized at				<u></u>		
	— 8'—			•				
	— 9'—				•			
-	-10'-							
-	11'							
-	-13'-							
_	—14'—		•					
~	REMARKS: PID =  Backgr No strong petroleum (tar, cinders, etc.	cound (BG) PID = n-odor or visibl	0.2-0.6 ppm e contaminat	n	pes of	, petroleum	, compound	s
-	TEST PIT PLAN	LEGEND: BOULDER COUR	PRO I NT I ETTER ITRACE IGNATION A LITTL	DPORTIONS   USED     (TR) 0 - 10 %   (E(Li.) 10 - 20 %   (50.) 20 - 35 %	F - FINE M - MEDIL C - COAR F/M - FIN	SE E TO MEDIUM E TO COARSE	EFFO EASY— MODERATE OFFICULT GROUNDY IELAPSED	RT - E E - M T - D WATER
	VOLUME =C.Y.	36 AND LARGER	C AND	35-50%		ижи	TIME TO SERVING =	ZG.W.L.

	TEST	PIT	FIELD	LOG				
EMI	PIRE	1	PROJEC	I ESA_	F	TLE NO	T NO	-060
			BURA Si			ATE	3/6/92	
ENGINEER	D.R. Steiner	EXCAV. CONTRACTOR	ATION EQUI Empire Soi	lls			EV9	
WEATHER P. C	Cloudy, Breezy 30's	MAKE	MC	OEL		THE COMP	0	35
DEPTH O'		DESCR	IPŢION			EXCAV. EFFORT	BOULDER COUNT OTY, CLASS	REMARK NO.
	Brown FILL; of bricks, bould	contains sand lers, slag (	d, gravel, mostly brow	clayey s n clayey	ilt, silt)	E		BG
				-		E		BG
						Е		BG
3'	Water tricklin	ng into test	pit from n	orth side	e at 3.7'	D	-	BG
4'	Test Pit Term Refusal at 4.		o be concre	te	!			
5								
<u></u> — е' —								
7'-				,				
8'-								
9'-								
10'-								
11'-								
12'-								
13'-								
14'-								
	PID = Photoioni Background (BG)			gs (ppm)		•	,	
1	No visible evid	ence of petr	oleum conta	amination	<u> </u>			
TEST PIT P	LAN LEGEN	1 <u>D</u> :	PROPOR		ABBREV	ZNCITAL		
	BOULDER SIZE RANG		USE		F-FINE		EFFC	
1 + 1////	CLASSIFICAT	ION DESIGNATION	TRACE (TR)		C - COARSI F/M - FINE F/C - FINE	TO MEDIUM	MODERAT	E — M T — D
NORTH.	18"-36"	В	SOME (SO.)	20-35%	V-VERY GRGRAY		GROUNDY ELAPSED TIME TO TREADING	
VOLUME =	_C.Y.				YEL - YEL		(HRS.)	=

			1001	F11	FIELD L	.00				
1	7_1	RADTI	OF		PROJECT		TE	ST PIT	NO. TP-	-24
	3012	ने ग्रेग्रेट्स प्रदेशप	NS ME		ION Phase II E	SA			BTA-92	
					BURA Site		DA	TE_	3/25/9	92
	ENG	INEER D. W.	artinger	CONTRACTOR	VATION EQUIPM Empire Soils	ENT			EV	
		R Sunny,		OPERATOR	M. Gaudy				TED 1:4	
				CAPACITY	C.Y. REACH	FY.	11T	LE COMP	LETED 2:0	
	DEPTH		SOIL	DESC	RIPTION			EXCAV. EFFORT	COUNT OTY CLASS	REMARK NO.
	ı'				nd, silt, grave material, concre			E		BG
١								М		BG
	-2'-	Lt.	brown sand	i seam				М		BG
	—3'→ —4'—		-					М		BG
		´ X ) 6"¬⊂	lay tile p		naterial being n cunning water	removed		М		BG
		1100	Jeanuriig	water with	. Sheen			М		BG _
	6'	Grey	-brown sar	ndy silt, t	r. gravel (mois	st)		Е		BG
		Test	Pit termi	nated at 7	7.0'					
	<del></del> 8'									
	— 9'—									
	-10'								_	
	1 1'									
}	— 12 <b>'</b> —									
	13'-									
-	14'									-
	REMAR	KKS: PID =	——————— Phot <b>o</b> ioniz	ation Dete	ector Readings (			,		1
				PID = 0.2-	_					
	TEST	PIT PLAN	LEGEN	D:	PROPORTION	NS LABBRE	EVIA	ZNCITA	EXCAVA	TION
	1		BOULDER	COUNT	USED	F - FINE   H - MED		,	EFFO	RT
1	_\//		SIZE RANG CLASSIFICATION	E LETTER ON DESIGNATION	INC	10%   C - COAL	RSE	MEDIUM	MODERATI	
	1 (	$\supset$	618_	A	LITTLE(LI.) 10 -	20 % F/C-FIN	E TO	COADCE	GROUNDY	
		RTH.	18"-36"	B	SOME (SO.) 20-	35%   GR GR. 50%   BN BR	¥Υ		ELAPSED	7 G.W.L
Į	VOLUME	=C.Y.	36 AND LAR	GER C		YELY		· <b>Y</b>	READING ===	=

1	TEST	PIT	FIELD	LOC	3				
FRADI	DF		PROJEC	•		TE	ST PI	T NO. TP	-25
दिनार्द्वाती/क्राविश्य	-//-///-		ION Phase			FII	LE NO	BTA-92	-060_
			BURA S			DA	TE	3/25/	92
ENGINEERD	. Wartinger OF	EXCAV _ EXCAV	ATION EQU Empire So	IPMENT				EV	:05
WEATHER Sunny,	preezv				FY		KE STAR		:30
			C.Y. RI		F 1.			BOULDER	
DEPTH 0'			RIPTION				EXCAV. EFFORT	COUNT OTY. CLASS.	REMARK NO.
IX X   PIS	ack FILL; con ncrete, wood,				,		E		BG
_2							М ·		5-7
						į	М		5-7
Sea Sea	am of white m		, petroleum	n odor _			М	-	
1 1//	ty sandy cla	ay,tr. gra	vel, black	seams	į		М		
-6'- Fre	e standing w	ater with	sheen				М		
7'-//-							Е		
Tes	t Pit Termin	ated at 7	.0'.				E		
- 'e -					-				
-10'-									
11'-						ļ		_	
12'-									
13'-									
14'-									
	Photoionizat			gs (ppm)		1	•	,	
TECT DIT OF AT	LECEND		000000	510.110			<b></b>		
TEST PIT PLAN	LEGEND	<b>-</b>	PROPORT USE		ABBRE	VIA	ISNCII	EXCAVA EFFO	
	SIZE RANGE CLASSIFICATION	LETTER	TRACE (TR.)	0 - 10%	M-MEDIU C-COARS	SE	ا ا	EASY	— E
1 0	6"-18"	A B	SOME (SO.)		F/C-FINE	TO (	COARSE	DIFFICULT GROUNDW	
NORTH. VOLUME =C.Y.	36"AND LARGE		DHA J		I GR GRAY   BH BRO   YEL YEL	wи	i	ELAPSED TIME TO \\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\	7 G.W.L.

		1651	PH	FIELD	LUG					٠.
	PA AFT	ידרדי		PROJEC	T .		TE	ST PI	NO. TP	-26
	ATT		DESCRIPTI	ON Phase I					BTA-92	
E-011	31/1/2/3/10	======================================	1	BURA Si					3/25	
		D.Wartinger	FYCAV	ATION FOLL	PMENT	J			EV	
	SINEER _	D.war cinger	CONTRACTOR	M. Gaudy	.15		TII	HE STAR	TED2:3	5
WEATHE	R Sun		MAKE			FT.	TIF	4E COMP	LETED <u>2:4</u>	5
DEPTH			DESCR					EXCAV. EFFORT	BOULDER COUNT OTY, CLASS.	REMARK NO.
o'	X	Brown FILL; o	ontains san	d. gravel	brick c	oncrete				
1'	$\times \times$	glass	onearns san	d, graver,	brick, c	oncrete	,	E		BG
	$\times \times$							М		5-7
<u> </u>		Becomes black	, petrolum	odor				М		5-7
3'	$(\times)$	_								-
	$\times$							М		5-7
— 4 <b>'</b> —	$\times$	Running water	:							
<del></del> 5'		Free standing	torith	ahaan		!		M		
3	KX'	riee standing	, water with	Sileeli				E		
<b>→</b> 6'—	(+ +)	Grey-brown Sa	ndv-Silt t	r gravel	black se	2mc		Е.		
		0.20, 0.20, 0.20						E .		
,		Test Pit Term	inated at 7	.0'.	,					
<u> </u>										
- 0'-						-				
_ 9 _										
<u>10'-</u>										
	}							1		
	1									
— ı2'—										
<u> —</u> 13'—										
14'								<u> </u>		
REMAR	1	TD - Dhahai ani		ton Donline	· · · · · · · · · · · · · · · · · · ·	· ·	_			<u></u>
<b>REMAR</b>		ID = Photoioni: ackground (BG)			gs (ppm)			•	,	
TEST	PIT PL	AN LEGEN	ID:	PROPORT	TIONS	ABBRE	VII	ZTIONS	EXCAVA	TION
1 1		BOULDER	<del></del>	USE		F-FINE			EFFO	
-7///	7777	SIZE RANG	E LETTER	TRACE (TR)	0 - 10 %	M - MEDI			EASY -	ε ε
TVIII	11111	CLASSIFICATI	ON DESIGNATION A	LITTLE(LI.)		F/M-FIN	E TO	MEDIUM	01111000	<b>—</b> D
, (		18-36	В	SOME (SO.)		F/C-FIN		COARSE	GROUNDY	VATER
VOLUME	RTH.	C.Y. 36 AND LAR		1 AND		GR GRA   BN BRO	NW		TIME TO	ZG.W.L.
* OLUME		0.1.		•		YEL. YE	LLC	W	(HRS.)	=

		1651	PILI	FIELD LC	) (3			
B.	RADIT	) E		PROJECT .		TEST PI	T NO. TP-	-27
	annaniani		DESCRIPTION	ON Phase II ESA		FILE NO	BTA-92	-060
			LOCATION	BURA Site		DATE	3/25/	92
	D	Jartinger	EXCAVA	TION EQUIPMEN	IT	GROUND EL	.EV	
ENG	SINEER		CONTRACTOR OPERATOR	Empire Soils  M. Gaudy		TIME STAR	TED2:	: 47
WEATH	R Sunny,	Breezy	MAKE CAPACITY	C.Y. REACH	FT.	TIME COMP	LETED2:	55
DEPTH			DESCR			EXCAV. EFFORT	BOULDER COUNT QTY. CLASS.	REMARK NO.
0'-	Brown	FILL; co	ntains sand,	brick, gravel,	slag	D		BG
	Aspha	ılt, Slag				-D		BG
2'-	Conta	ins white	slag			М		BG
3'-		-				М	_	BG
4'—	Runni	ing water			!	М	_	BG
5'-	Free	standing v	water – no s	heen noted		М		BG
6'-	Grey	brown sand	ly silt, tr.	gravel		Е		BG
7'-	Toot	Dit Townia	nated at 7.0					
8'		ire leimi	lated at 7.0	•		-		
<u> </u>					-			
-10'-								
-11'-								
<u> </u>							1	
<u> </u>								<u> </u>
-14'-						-		
REMAR	RKS: PTD =	Photoionia	ation Detec	tor Readings (pp			J	1
			PID = 0.2-0		)		/	
TEST	PIT PLAN	LEGEN	D:	PROPORTIONS	IABBRE	VIATIONS	EXCAVA	TION
1-		BOULDER	COUNT	USED	F-FINE		EFFO	RT
		SIZE RANG	E LETTER ON DESIGNATION	TRACE (TR) 0 - 10		εE	EASY	
T (		6-18	A	LITTLE (LI.) 10 - 20	% F/C-FINE	TO MEDIUM TO COARSE	DIFFICULT  GROUNDY	
NO	RTH.	18"-36"	в	SOME (SO.) 20-35	I GR. GRAY		ELAPSED TIME TO	
VOLUME	=C.Y.	36 AND LAR	GER C	1 AND 35-50	%   BNBROV		READING =	Z_G.W.L.

			TĖST	PIT	FIELD	LOG					·
E			E	1	PROJECTION Phase  BURA S	II ESA		FII	LE NO.	NO. <u>TP-</u> BTA-92- 3/25/9	-060
ENG WEATHE	SINEER _ R _ Sunn	D. Wa	Process	EXCA CONTRACTOR OPERATOR	VATION EQU Empire So M. Gaudy	IPMENT ils	FY.	TIL	KE STAR	EV	00
DEPTH		·			RIPTION				EXCAV. EFFORT	BOULDER COUNT OTY, CLASS,	REMARK NO.
— 0'—			orown FIL rete, gla		s sand, sil	t, gravel,	brick	,	M		BG
<u> </u>		Becor	nes black	:					M ·	<u> </u>	BG
<u> </u>			_						M		BG
4'	XX	Runn	ing water	- no shee	n noted				M		BG
5'		Grev-	-brown Sa	ndv-silt.	tr. gravel		!		E		BG
c'				, 0121,	er graver				E		BG
<b>-</b> 7'		Test	Pit Term	inated at	6.01.						
<u> </u>										-	
9'											
<u> </u>											<u>-</u>
— I I'—	:		•								
— 12 <b>'</b> —											
—ı3'—											
<u> </u>							-				
REMAR				ation Dete PID = 0.2-	ector Readin -0.6 ppm	gs (ppm)			•	,	
1 H	PIT PL		LEGEN BOULDER SIZE RANG CLASSIFICATI 6"-18" 18"-36"	COUNT  E LETTER ON DESIGNATION A B		0 - 10 %   10 - 20 %   20 - 35 %   35 - 50 %	ABBRE F - FINE M - MEDI C - COAR F/M - FIN F/C - FIN V - VERY GR GRA BN BRO YEL YE	UM ISE E TO E TO	MEDIUM COARSE	EFFO EASY —	RT E - M r - D WATER

#### TEST PIT FIELD LOG TEST PIT NO. \_TP-29 PROJECT DESCRIPTION Phase II ESA FILE NO. BTA-92-060 BURA Site DATE \_\_\_\_\_3/25/92 LOCATION \_ EXCAVATION EQUIPMENT GROUND ELEV. \_ ENGINEER D. Wartinger Empire Soils M. Gaudy CONTRACTOR \_\_\_ 3:10 TIME STARTED \_ OPERATOR \_ TIME COMPLETED 3:25 Sunny, Breezy WEATHER \_ MAKE MODEL CAPACITY REACH BOULDER EXCAV. REMARK SOIL DESCRIPTION DEPTH COUNT **EFFORT** NO. QTY. CLASS - O'-D BGBrown FILL; contains sand, brick, gravel, slag D BGAsphalt, Slag - 2'-Contain's white slag М BG -3' М BG -4" M BG Running water - 5' Free standing water - no sheen noted М ΒG 6' Grey brown sandy silt, tr. gravel Ε ВG Test Pit Terminated at 7.0' 8. 10. -11'-- 12'--13'--14'-REMARKS: PID = Photoionization Detector Readings (ppm) Background (BG) PID = 0.2-0.6 ppm LEGEND: PIT PLAN PROPORTIONS ABBREVIATIONS. EXCAVATION USED F-FINE **EFFORT** BOULDER COUNT M - MEDIUM LETTER TRACE (TR) 0 - 10% SIZE RANGE EASY -C - COARSE CLASSIFICATION DESIGNATIONS MODERATE - M F/M-FINE TO MEDIUM DIFFICULT - D LITTLE(LI.) 10 - 20% F/C-FINE TO COARSE GROUNDWATER 6"-18" SOME (50.) 20-35% 18"-36" ELAPSED NORTH. GR. GRAY TIME TO SZ G.W.L 35-50% | BN.-BROWN

READING -

(HRS.)

YEL .- YELLOW

36"AND LARGER

VOLUME = C.Y.



# APPENDIX D

## GENERAL INFORMATION & KEY TO SUBSURFACE LOGS

The Subsurface Logs anached to this report present the observations and mechanical data collected by the driller at the site, supplemented by classification of the material removed from the borings as determined through visual identification by technicians in the laboratory. It is cautioned that the materials removed from the borings represent only a fraction of the total volume of the deposits at the site and may not necessarily be representative of the substrated conditions between adjacent borings or between the sampled intervals. The data presented on the Substrated Logs together with the recovered samples will provide a basis for evaluating the character of the significance relative to each other. Often analyses of standard boring data indicate the need for additional testing or sampling procedures to more accurately evaluate the substrated conditions. Any evaluation of the contents of this report and the recovered samples must be performed by Professionals. The information presented in the following defines some of the procedures and terms used on the Substrated Logs to describe the conditions encountered.

- 1. The figures in the Depth column defines the scale of the Subsurface Log.
- The sample column shows, graphically, the depth-range from which a sample was recovered. See Table 1 for a description of the symbols used to signify the various types of samples.
- 3. The Sample No. is used for identification on sample containers and/or Laboratory Test Reports.
- 4. Blows on Sampler shows the results of the "Penetration Test", recording the number of blows required to drive a split spoon sampler into the soil. The number of blows required for each six inches of penetration is recorded. The first 6 inches of penetration is considered to be a seating drive. The number of blows required for the second and third 6 inches of penetration is termed the penetration resistance, N. The outside diameter of the sampler, the hammer weight and the length of drop are noted at the bottom of the Subsurface Log.
- 5. PID Organic vapor measurements taken with a Photoionization Detector (PID). Measurements recorded in parts per million (ppm).
- 6. Symbol Material symbol which indicates the type of soil that was encountered during classification of the recovered soil at the approximate depth. The symbol indicated represents an approximate boundary between soil types and the transition may be gradual.
- All recovered soil samples are reviewed in the laboratory by an engineering technician, geologist, or geotechnical engineer, unless note otherwise. The visual descriptions are made on the basis of a combination of the driller's field descriptions and observations and the sample as received in the laboratory. The method of visual classification is based primarily on the United Soil Classification (ASTM D 2487-83) with regard to the particle size and plasticity. (See Table No. II) Additionally, the relative portion, by weight, of two or more soil types is Eurmister, ASTM Special Technical Publication 479, June 1970. (See Table III) The description of the relative soil density or consistency is based upon the penetration records as defined on Table No. IV. The description of the soil moisture is based upon the relative wetness of the soils as recovered and is described as dry, moist, wet and saturated. Water introduced in the boring either naturally or during drilling may have affected the moisture condition of the recovered sample. Special terms are used as required to describe materials in greater detail; several such terms are listed in Table V. When sampling gravelly oils with a standard two inch diameter split spoon, the true percentage of gravel is often not recovered due to the relatively small sampler diameter. The presence of boulders and large gravel is sometimes, but not necessarily detected by an evaluation of the casing and samplers blows or through the "action" of the drill rig as reponted by the driller.
- 8. The description of the rock shown is based on the recovered rock core and the driller's observations. The terms frequently used in the description are included in Table VI.
- The stratification lines represent the approximate boundary between soil types and the transition may be gradual. Solid stratification
  lines are based on the driller's field observations.
- 10. Miscellaneous observations and procedures noted by the driller are shown in this column, including water level observations. It is important to realize the reliability of the water level observations depends upon the soil type (water does not readily stabilize in a hole through fine grained soils), and that drill water used to advance the boring may have influenced the observations. The ground water level typically will fluctuate seasonally. One or more perched or trapped water levels may exist in the ground seasonally. All the available readings should be evaluated. If definite conclusions cannot be made, it is often prodent to examine the conditions more thoroughly through test pit excavations or water observations wells.
- 11. The length of core run is defined as the length of penetration of the core barrel. Core recovery is the length of core recovered divided by the core run. The RQD (Rock Quality Designation) is the total pieces of NX core exceeding 4 inches in length divided by the core run. The size core barrel used is also noted.

DATE BORING NO.: B-1 SUBSURFACE SOILS INVESTIGATIONS INC. STARTED: 5-7-91 SURF. ELEV .: \_ 100.0 ± LOG SHEET \_1 OF \_1 FINISHED: 5-7-91 PROJECT: SAMPLE SUBSURFACE LOG LOCATION: PROJECT NO: CLIENT: ELOWS ON PLE SOIL OR ROCK SAMPLER P.H NOTES CLASSIFICATION 4 | 6 | 6 | 10 | FILL WELL GRADED GRAVELS, GW 4) POORLY GRADED GRAVELS, GP Water encountered SILTY GRAVELS, GM at 4.8 feet. CLAYEY GRAVELS, GC 6 WELL GRADED SANDS, SW POORLY GRADED SANDS, SP SILTY SAND, SM CLAYEY SAND, SC INORG. SILT AND VERY F. SAND. CLAYEY SILT WITH LOW PLASTICITY, ML 20 INORG CLAYS, GRAVELLY CLAY, SANDY CLÁY, SILTY CLAY, LEAN CLAY, CL ORGANIC SILTS AND ORGANIC SILTY CLAYS OF LOW PLASTICITY, OL INORGANIC SILTS. MH 25 -INORGANIC CLAYS OF HIGH PLASTICITY, FAT CLAYS, CH ORGANIC CLAYS OF MED TO HIGH PLASTICITY, OH PEAT, Pt RUN: 32.0'-40.0' SHALE REC: 88% **RQD: 65%** SANDSTONE SILTSTONE LIMESTONE DRILLER: DRILL RIG: CME - 45 METHOD OF INVESTIGATION: ASTM D-1586 Using Hollow Stem Augers WEATHER: SUNDY, 70 F CLASSIFIED BY: By Geologist

DATE

STARTED: 3-30-92

FINISHED: \_3-30-92

## SUBSURFACE LOG-

BORING NO.: MW-1

SURF. ELEV .: 91.3 ±

SHEET 1 OF 1

BTA-92-060 PROJECT: BURA-Phase II Environmental LOCATION: Waterfront Redev. Project Buffalo, NY CLIENT: **BURA** 9 DEPTH-FT. **BLOWS ON** SYMBOL SOIL OR ROCK SAMPLE PID SAMPL SAMPLER NOTES CLASSIFICATION 112/18/ TOPSOIL PID = Photoionization 8 6 20 6 26 BG Detector readings Black FILL, contains, tr. gravel, tr. sand, tr. (ppm) silt, tr. slag, tr. concrete (moist, FILL) Contains Coal-tar odor Background (BG) 30 2 4 5 4 5 9 PID = 0.2 - 0.6 ppmContains viscous Tar-like material 5 4 3 4 7 20 Gray-brown Sandy SILT, tr. gravel, tr. 5 8 6 9 14 10 wood, black seams (moist, FILL) Contains occasional Tar seams and 13 7 20 20 4 9 orange seams Light brown Sandy SILT (wet, firm, ML) 6 14 14 14 28 3-5 Contains slight sheen 7 12 13 16 16 29 0.4 AUGER 8 50/ REF Boring Complete with Sample Spoon Installed 2" PVC refusal at 16.0' Monitoring Well 20

DRILLER: D. Beitz

DRILL RIG: CME-55

METHOD OF INVESTIGATION: ASTM D-1586 USING HOLLOW STEM'AUGERS

WEATHER: LT. SNOW, COLD

CLASSIFIED BY: D. Wartinger

MONITOR WELL COMPLETION REPORT :

•	WELL Nº MW-1 JOB Nº BTA-92-060
	PROJECT BURA-PHASE II
	Buffalo, NY
91.3	1. PROTECTIVE CASING 1.D. 4 HICHES.
	2 SURFACE SEAL TYPE Portland Cement
*OEPTH 2.5'	3. BORENOLE DIAMETER 8 INCHES.
	4_ RISER PIPE:
Y/A   Y/A	Schedule 40 PVC
\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\	b. LD. 2 INCHES
	a Longth 5 FEET
	d Joint Type Flush Threaded
\\\\\\\\ <del>\\\\\\\\\\\\\\\\\\\\\\\\\\\\\</del>	
·	5. BACKFILL:
*DEFTH 2.0-	Portland Cement
3.0	6. Installation Surface
Sermi 3.0	
	6. Tree of SELL Bentonite Pellets
	•
	I. SCREEN
	Schedule 40 PVC
	ALA 2 MORES
	c star size 0.010 moves
	d. Langth 8 FEET
12.0	
ФСЕТН 12.0	B. SCREEN FILTER TYPE No. 1 Morie Sand
	. Soleta Helen The Month Hollie Salid
*ocen 16.0'	
	9. BLOWFILL TIPE No. 1 Morie Sand
	S. DACAPILL HEE

\*Depth in feel below grode.



DATE

STARTED: 3-31-92

PROJECT:

CLIENT:

SOILS INVESTIGATIONS INC.

## **SUBSURFACE** LOG ·

BORING NO.: MW-2

SURF. ELEV .: 91.2 ±

SHEET 1 OF 1

FINISHED: 3-31-92

<u>BURA</u>

BTA-92-060 BURA-Phase II Environmental

LOCATION: Waterfront Redev. Project

Buffalo, NY

, OLIC				0117	_					<u>Sanato, Mi</u>	
DEPTH-FT.	SAMPLES	SAMPLE NO	0 6	SA	OWS MPL 12/ 18		N	PID	SYMBOL	SOIL OR ROCK CLASSIFICATION	NOTES
- 0		1	WR		1	1	2	6	$\bigotimes$	Brown Silty CLAY, tr. gravel, tr. sand, tr. brick (moist, FILL)	PID = Photoionization Detector readings (ppm)
-		2	2	1	1	1	2	25	$\bigotimes$	Contains a sheen (wet)	Background (BG PID=0.2-0.6ppm
- 5 -		3	3	2	3	9	5	20		Becomes black, contains Tar-like material with Coal Tar odor	
-		4	11	3	4	3	7	15	$\bigotimes$	Contains little wood	-
-		5	6	6	2	37	8	8		Contains Brick seam, visous black Tar	_
10		6	26	11	13	19	24	(8	$\bigotimes$	Contains wood (6")	
-		Α	JGE	R						Light brown Sandy SILT, tr. gravel, occasional black Tar inclusions (moist, ML)	Driller notes heavy sheen on water
- 15		7	20	45	43	50/ .05	98	1	- - - - - - - - - - - - - - - - - - -		coming from Borehole
- 15 - -											·
-										Boring Complete with Sample Spoon refusal at 16.5'	Installed 2" PVC Monitoring Well
- 20 -											
-											_
25 -							_		1		

DRILLER: D. Beitz\_\_\_\_\_

DRILL RIG: CME-55

METHOD OF INVESTIGATION: ASTM D-1586 USING HOLLOW STEM AUGERS

WEATHER: COLD, SUNNY

CLASSIFIED BY: D. Wartinger

MONITOR WELL COMPLETION REPORT :

4	PROJECT_BURA-PHASE II
	Buffalo, NY
εc. 91.2	. I. PROTECTIVE CASING I.D. 4 MCHES.
	z surface seal TYPE Portland Cement
	•
*OEPTH 2.5' 2007	3. BORENOLE DIAMETER 8" INCHES.
	4. RISER PIPE:
Y// \ \ / / F	a Type Schedule 40 PVC
V/ \ \ //_3	D. LO. 2 INCHES
	c Longith 14.2' FEET
\//\ \ \ \/\\ \ \ \ \ \ \ \ \ \ \ \ \ \	d Joint Type Flush Threaded
V/ \ \ \/\_3	
	5. BACKFILL:
*ocerH 11.0	o. Type Portland Cement
(6)	D. Austothetion Surface
*xern \( \frac{13.0}{2} \)	b. Milanian
	6. Type of SELL Bentonite Pellet
	6. Type of SELL BUILDING TETTE
	Z SCREEN Sahadula 40 DVC
	Schedule 40 PVC
	A LO 2 MONES
	c sky size 0.010 MCHES
	1. Longth (2.5) FEET
*осети 16.0	
	B. SCREEN FILTER TYPE No. 1 Morie Sand
•осети 16.5	
	9. EXECUTIVE No. 1 Morie Sand

WELL NR MIN-2

JOB Nº BTA-92-060

\*Depth in foot below grade.



DATE

STARTED: <u>3-31-92</u> FINISHED: 3-31-92

WEATHER: COLD, SUNNY

SOILS INVESTIGATIONS INC.

# SUBSURFACE ĻOG~

BORING NO.: MW-3

SURF. ELEV.: 92.2 ±

SHEET 1 OF 1

CLASSIFIED BY: D. Wartinger

	_				=					BTA-92-060	
PRO CLIE				URA URA		nase	II E	nviro	nme	ntal LOCATION: Waterfront Re Buffalo, NY	dev. Project
DEPTH-FT.	SAMPLES	SAMPLE NO		SA	OWS MPL		2	PID	SYMBOL	SOIL OR ROCK CLASSIFICATION	NOTES
- 0		1	3	40	22	11	62	.6		Brown Silty CLAY, tr. gravel, tr brick, tr. sand (moist, FILL)	PID = Photionization Detector readings (ppm)
-		2	3	1	2	1	3	1		Becomes black, contains tr. cinders. tr. slag, tr. wood	Background (BG) PID=0.2-0.6ppm
- 5 -		3	3	2	2	2	4	70		Contains seam White Sand (wet)	Driller notes free standing water
-      -		4	2	2	2	3	4	80		Contains black Tar-like material, Petroleum odor	inside Augers at approx. 6.0'
- -		5	3	6	5	8	11	2-5		Contains seam, of Green Sandy Silt	
- 10 - -		6	3	6	7	7	13	1		Light brown Sandy SILT, tr. gravel, occasional black inclusions (moist, firm,	
-			UGE							MC)	  - 
- 15 -		BG	13	22	15	21	37	7			
-										Boring Complete at 15.0'	Composite Soil Sample collected from Sample #S-3, S-4, and S-5 for Laboratory Chemical Analysis
20 - - -											Installed 2" PVC Monitoring Well
25 - DRILI			D. B		ATIO	N: 4	ASTI	M D-1	1586	DRILL RIG: CME-55 USING HOLOW STEM AUGERS	

# MONITOR WELL COMPLETION REPORT :

	WELL Nº NN-3 JOB Nº BTA-92-060
	PROJECT BURA-PHASE II
	Buffalo, NY
92.2'	.I. PROTECTIVE CASING I.D. 4 MICHES.
	z surface seal TYPE Portland Cement
*OEPTH 2.51	3. BORSNOLE DIAMETER 8 INCHES.
<b>%</b> // \ \ // <del>&amp;</del> ·	4. RISER PIPE:
<b>₹/</b> /  <b>                                  </b>	a. Type Schedule 40 PVC
	D. LD. 2 INCHES
	c Longith 5.8 FEET
	d sont Type Flush Threaded
	5. BACKFILL:
*OCETH 1.9 (6)	a Type Portland Cement
-ocrm 2.9	D. Autocorron Surface
<u> </u>	
	6. Tred SELL Bentonite Pellet
	T. SCREEN
	Schedule 40 PVC
	A LO. 2 MOVES
	c. star size 0.010 Maches
	1. Longth 10 FEET
13.9 (A)	•
	B. SCREEN FILTER TYPE No.1. Morie Sand
+ocen 15.0	
DEFINITION (9)	No 1 Maria Sand
	9. MOSFILL TIPE No.1 Morie Sand



\*Depth in last below grade.

DATE BORING NO.: MW-4 SUBSURFACE STARTED: 3-31-92 SOILS INVESTIGATIONS INC. SURF. ELEV.: 93.5 ± LOG FINISHED: 3-31-92 SHEET 1 OF 1 BTA-92-060 BURA-Phase II Environmental LOCATION: Waterfront Redev. Project PROJECT: Buffalo, NY CLIENT: **BURA** DEPTH-FT. BLOWS ON SYMBOL SOIL OR ROCK PIO SAMPLER NOTES CLASSIFICATION BG 🔀 Brown Silty CLAY, tr. brick, tr. slag, tr. PID = Photoionization sand, tr. gravel (moist, FILL) Detector readings (ppm) Contains tr. wood 6 14 BG Background (BG) 7 6 8 PID = 0.2-0.6ppm Becomes gray-black 8 9 7 16 BG 3 BG 7 5 6 5 11 Light Brown Sandy SILT, tr. roots (moist, 6 7 16 14 BG firm, ML) (wet) AUGER BG 10 26 10 100 36 УŚ Boring Complete with Sample Spoon Installed 2" PVC refusal at 14.8' Monitoring Well 20 DRILLER: D. Beitz DRILL RIG: CME-55 METHOD OF INVESTIGATION: ASTM D-1586 USING HOLLOW STEM AUGERS WEATHER: COLD, SUNNY CLASSIFIED BY: D. Wartinger

11



# APPENDIX E

## ENVIRONMENTAL ANALYTICAL REPORT

REPORT NUMBER 92-462

### PREPARED FOR:

EMPIRE SOILS INVESTIGATIONS, INC. S-5167 S. PARK AVENUE HAMBURG, NEW YORK 14075

RE: BTA-92-040-BURA

PREPARED BY:

HUNTINGDON ANALYTICAL SERVICES
DIVISION OF EMPIRE SOILS INVESTIGATIONS, INC.
P.O. BOX 250
MIDDLEPORT, NEW YORK 14105

MARCH 30, 1992

PAGE 1



## HUNTINGDON ANALYTICAL SERVICES ELAP #10833 ENVIRONMENTAL REPORT

REPORT NUMBER 92-462

### STATEMENT OF WORK PERFORMED

I HEREBY DECLARE THAT THE WORK WAS PERFORMED UNDER MY SUPERVISION ACCORDING TO THE PROCEDURES OUTLINED BY THE FOLLOWING REFERENCES AND THAT THIS REPORT PROVIDES A CORRECT AND FAITHFUL RECORD OF THE RESULTS OBTAINED.

- 40 CFR PART 136, "GUIDELINES ESTABLISHING TEST PROCEDURES FOR THE ANALYSIS OF POLLUTANTS UNDER THE CLEAN WATER ACT", OCTOBER 26, 1984 (FEDERAL REGISTER) U. S. ENVIRONMENTAL PROTECTION AGENCY.
- U.S. ENVIRONMENTAL PROTECTION AGENCY, "TEST METHODS OF EVALUATING SOLID WASTE PHYSICAL/CHEMICAL METHODS", OFFICE OF SOLID WASTE AND EMERGENCY RESPONSE, SW-846, 2ND EDITION AND 3RD EDITION.
- NEW YORK STATE DEPARTMENT OF HEALTH, ANALYTICAL TOXICOLOGY LABORATORY HANDBOOK, AUGUST 1982.

RICHARD J. RONAN, PH.D.

MARCH 30, 1992

LABORATORY DIRECTOR, ENVIRONMENTAL

REPORT CODE LEGEND:

<DL = Less than detection limit

ND = NOT DETECTED

NA = NOT APPLICABLE

INP = INFORMATION NOT PROVIDED

MB = METHOD BLANK



# -UNTINGUON ANALYTICAL SERVICES. INC. ENVIRONMENTAL

lnorganio wet Chemical Analyses

Sample Identification: TP-C1

HAS Sample #92-462-001

Date Sampleo: 3/6/92

				Metnod			
i	!	Date :		Detection	<u>:</u>	! }	) : :
1						i Limite	1 1 7747: 1 - 2: 1
i Analyte !	EPĀ Methad i	rrebareo:	Mnaiyzeu	Limit	Result	! Units	l QC in % i
		1			!	!	[!
,	i		. =	5 - 5			! <1***
I Hal	SW-846 9045	37207921	3/20/921	0.18	7.69	/ S. J.	! 95** /
i	:	1	i		)		ı
1	i	1	:	Initial :	1	1	i (
i	i	í		Temp.	!	1	i ı
ıFlasn Point (	SW-646 10101	(	5/20/92	58	111	ı of	! 101* +
i	i	;	i	i :	1	1	! i
1 i	:	!				í	i I
Reactivity	SW-846		i	1	1	i	i
i	Section 7.31	i	1	'	I	f	1
1		í	1		i	i	l i
:Total :	;	i		:	İ	img/kg as ∶	ı i
(Releasable Sulfide)	9030	3/27/92;	3/27/92	50	i <50	i H2S	i 96 <del>+</del> i
1	!		j		i	i	i i
Total		į		i	i	lmo/ko as	i
(Releasable Cvanide)	9010 -	3/27/921	3/27/92	50	i <50	I HON	1 106* 1
i yanzazi		1		i	1	1	i i
		1			i	1	

- \* A known standard of the analyte of interest was analyzed along with this sample with the percent recovery indicated above.
- ++ This indicates that a 95% confidence limit was achieved with an EPA Quality Control Check analyzed with this sample.
- \*\*\* This sample was analyzed in oublicate with the RPD indicated above.

Client None EST- HAMBURS	•	
	Cilent Contact DAVE STEINER	RAS QUOTE #
	Phone 649-8110	** · · · · · · · · · · · · · · · · · ·
Project No.:   Project/Site Name:   BUP A	H   m   Conteiner Size & Type	
Signature :	of sine of the state of the sta	Analysis Requested/
Sample   Sample   HAS	t con	
100) X X 100,00		CORROSIVITY REACTIVITY, IGHTABILITY
(200) X X X (200) 3-6 (200)		VOLATILES & SEMI- VOLATILE
		1
P-C1(5)3-6 11:45 × × 1 1003		VOLATILES & SEMI-VOLATILES
		- * DO MOT INCLUDE TAR @
		BOTTOM OF JAR FOR TP-CI(N)
		WE ARE INTERESTED IN CONTAMINA
		1 CONCENTRATIONS IN THE SOIL,
I porce Time: Received by:	Relinquished by:	Dote/ Time:   Received By:
Relinquished by:   Dete/ Time: Received by:	Relinquished by:	Dote/ Ilme: Received By:

### ENVIRONMENTAL ANALYTICAL REPORT

REPORT NUMBER 92-501

### PREPARED FOR:

EMPIRE SOILS INVESTIGATIONS, INC. S-5167 S. PARK AVENUE HAMBURG, NEW YORK 14075

RE: BTA-92-040, BURA

PREPARED BY:

HUNTINGDON ANALYTICAL SERVICES
DIVISION OF EMPIRE SOILS INVESTIGATIONS, INC.
P.O. BOX 250
MIDDLEPORT, NEW YORK 14105

APRIL 10, 1992

PAGE 1

HAS

#### HUNTINGDON ANALYTICAL SERVICES ELAP #10833 ENVIRONMENTAL REPORT

REPORT NUMBER 92-501

#### STATEMENT OF WORK PERFORMED

I HEREBY DECLARE THAT THE WORK WAS PERFORMED UNDER MY SUPERVISION ACCORDING TO THE PROCEDURES OUTLINED BY THE FOLLOWING REFERENCES AND THAT THIS REPORT PROVIDES A CORRECT AND FAITHFUL RECORD OF THE RESULTS OBTAINED.

- 40 CFR PART 136, "GUIDELINES ESTABLISHING TEST PROCEDURES FOR THE ANALYSIS OF POLLUTANTS UNDER THE CLEAN WATER ACT", OCTOBER 26, 1984 (FEDERAL REGISTER) U. S. ENVIRONMENTAL PROTECTION AGENCY.
- U.S. ENVIRONMENTAL PROTECTION AGENCY, "TEST METHODS OF EVALUATING SOLID WASTE - PHYSICAL/CHEMICAL METHODS", OFFICE OF SOLID WASTE AND EMERGENCY RESPONSE, SW-846, 2ND EDITION AND 3RD EDITION.
- NEW YORK STATE DEPARTMENT OF HEALTH, ANALYTICAL TOXICOLOGY LABORATORY HANDBOOK, AUGUST 1982.

Kichard J. Konan Jame 4-10-92

LABORATORY DIRECTOR, ENVIRONMENTAL

REPORT CODE LEGEND:

<DL = Less than detection limit

ND = NOT DETECTED

NA = NOT APPLICABLE

INP = INFORMATION NOT PROVIDED

MB = METHOD BLANK



Inorganic Wet Chemical Analyses

Sample Identification: TP-3A

HAS Sample #92-501-001

Date Samoled: 3/25/92

1		i	l Method	1	i	i
i	Date i	Date .	Detection	I	1	j
EPA Method i	Prepared	Analyzed	Limit	Result	1 Units	rQC in %
i			i	1	i	1
					1	·
. avuo avalue	7/54/00:	7/74/00		, , 4 28		i 95** i
- DW-040 7040;	3/31/72)	: 0/01/72:		. 6.00	1 2. 0.	; 7⊃⊼⊼ ;
i	i	1				. :
ı	i			i		;
ì	i			1	1	<b>;</b>
SW-846 1010	1	3/31/92	63	1 123	ı eF	! 3 <del>***</del> i
Í	i		İ	i	i	<b>!</b> i
i	i	!		1	į	1 :
SW-846 1	i		ı	İ	i	i i
Section 7.31	1			i	1	i i
i			1	1	1	
:	:			: !	lma/ka se	, I ,
0075	; - 7707700;			1 750		. <b>6</b> 78
7030 I	3/2//72)	3/2//92	50	1 750	1 H25	i 96* i
İ	i	•		}	1	<b>!</b> .
i	į	i		I		1 ;
9010 (	3/27/921	3/27/921	50	(50)	I HCN	<b>1</b> 106∗ i
i	i	·		i	1	i i
1	í			i	i	i i
	SW-846 9045; SW-846 9045; SW-846 1010; SW-846 Section 7.3; 9030	EPA Method   Prepared	Date   Date   Date     EPA Method   Prepared   Analyzed           SW-846   9045   3/31/92   3/31/92     SW-846	EPA Method   Prepared   Analyzed   Limit	Date   Date   Detection    EPA Method   Prepared   Analyzed   Limit   Result	EPA Methoo   Prepared   Analyzed   Limit   Result   Units

- $\star$  A known standard of the analyte of interest was analyzed along with this sample with the percent recovery indicated above.
- \*\* This indicates that a 95% confidence limit was achieved with an EPA Quality Control Check analyzed with this sample.
- \*\*\* This sample was analyzed in oublicate with the RPD indicated above.

METHOD 8240 VOLATILE ORGANICS

SAMPLE IDENTIFICATION :	TP-3B	TP-3C	METHOD BLANK	
HAS SAMPLE #92-501	<i>0</i> 02	ØØ3		
COMPOUND	RESULT ug/Kg	RESULT ug/Kg	RESULT ug/Kg	MDL ug/Kg
CHLOROMETHANE  BROMOMETHANE  VINYL CHLORIDE  CHLOROETHANE  METHYLENE CHLORIDE  ACETONE  TRICHLOROFLUOROMETHANE  CARBON DISULFIDE  1,1-DICHLOROETHENE  1,1-DICHLOROETHENE (TOTAL)  CHLOROFORM  1,2-DICHLOROETHANE  2-BUTANONE  1,1,1-TRICHLOROETHANE  CARBON TETRACHLORIDE  VINYL ACETATE  BROMODICHLOROMETHANE  1,2-DICHLOROPROPANE  1,2-DICHLOROETHANE  1,2-TRICHLOROETHANE  1,2-TRICHLOROETHANE  1,2-TRICHLOROETHANE  1,1,2-TRICHLOROPROPENE  1,1,2-TRICHLOROETHANE  1,1,2-TRICHLOROETHANE  1,1,2-TRICHLOROETHANE  1,1,2-TRICHLOROETHANE  1,1,2-TRICHLOROETHANE  1,1,2-TRICHLOROETHANE  1,1,2-TRICHLOROETHANE  1,1,2-TRICHLOROETHANE  1,1,2-TRICHLOROETHANE  CHLOROETHYLVINYL ETHER  BROMOFORM  4-METHYL-2-PENTANONE  2-HEXANONE  TETRACHLOROETHENE  1,1,2,2-TETRACHLOROETHANE  TOLUENE  CHLOROBENZENE  STYRENE  XYLENE (TOTAL)  1,3-DICHLOROBENZENE	<1,300 <1,300 <1,300 <1,300 <630 <1,300 <630 <630 <630 <630 <630 <630 <630 <	<130,020 <130,020 <130,020 <130,020 <130,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <63,020 <	<1,300 <1,300 <1,300 <1,300 <1,300 <630 <630 <630 <630 <630 <630 <630 <	<1,300 <1,300 <1,300 <1,300 <630 <1,300 <630 <630 <630 <630 <630 <630 <630 <
DATE SAMPLED: DATE RECEIVED: DATE ANALYZED:	<1,300 3-25-92 3-27-92 4-8-92	<13Ø,ØØØ 3-25-92 3-27-92 4-8-92	<1,300  4-8-92	<1,300

METHOD 8270 SEMI-VOLATILE ORGANICS

SAMPLE IDENTIFICATION:	TP-3B	TP-3C	METHOD BLANK	
HAS SAMPLE #92-501-	002	003		
BASE/NEUTRAL	RESULT	RESULT	RESULT	MDL
COMPOUNDS	ug/Kg	ug/Kg	ug/Kg	ug/Kg
ACENAPHTHENE	740,000	350,000	<330	<330
ACENAPHTHYLENE	29,000	2,900,000	<330	<330
ANTHRACENE	470,000	3,000,000	<330	<330
BENZO(a)ANTHRACENE	250,000	2,200,000	<330	<330
BENZO(b)FLUORANTHENE	140,000	1,200,000	<330	<330
BENZO(k)FLUORANTHENE	170,000	1,300,000	<330	<330
BENZO(a)PYRENE	190,000	1,700,000	<330	<330
BENZO(g,h,i)PERYLENE	57,000	680,000	<330	<330
BENZYL ALCOHOL	<17,000	<33,000	<330	<330
BIS(2-CHLOROETHOXY)METHANE	<17,000	<33,000	<330	<330
BIS(2-CHLOROETHYL)ETHER	<17,000	<33,000	<330	<330
BIS(2-CHLOROISOPROPYL)ETHER	<17,000	<33,000	<330	<330
BIS(2-ETHYLHEXYL)PHTHALATE	<17,000	<33,000	<330 .	<330
BUTYLBENZYL PHTHALATE	<17,000	<33,000	<330	<330
4-BROMOPHENYL-PHENYL ETHER	<17,000	<33,000	<330	<330
4-CHLOROANILINE	<17,000	<33,000	<330	<330
2-CHLORONAPHTHALENE	<17,000	<33,000	<330	<330
4-CHLOROPHENYL-PHENYL ETHER	<17,000	<33,000	<330	<330
CHRYSENE	190,000	2,100,000	<330	<330
DIBENZ(a,h)ANTHRACENE	14,000	160,000	<330	<330
DIBENZOFURAN	590,000	2,400,000	<330	<330
DI-N-BUTYLPHTHALATE	<17,000	<33,000	<330	<330
1,2-DICHLOROBENZENE	<17,000	<33,000	<330	<330
1,3-DICHLOROBENZENE	<17,000	<33,000	<330	<330
1,4-DICHLOROBENZENE	<17,000	<33,000	<330	<330
3,3-DICHLOROBENZIDINE	<33,000	<66,000	<660	<660
DIETHYL PHTHALATE	< 17,000	<33,000	<330	<330
DIMETHYL PHTHALATE	<17,000	<33,000	<330	<330
2,4-DINITROTOLUENE	<17,000	<33,000	<330	<330
2,6-DINITROTOLUENE	<17,000	<33,000	<330	<330
DI-N-OCTYL PHTHALATE	<17,000	<33,000	<330	<330
FLUORANTHENE	1,100,000	5,700,000	<330	<330
FLUORENE	680,000	2,600,000	<330	<330
HEXACHLOROBENZENE	<17,000	<33,000	<330	<330
HEXACHLOROBUTADIENE	<17,000	<33,000	<330	<330
HEXACHLOROCYCLOPENTADIENE	<17,000	<33,000	<330	<330
HEXACHLOROETHANE	<17,000	<33,000	<330	<330
INDENO(1,2,3-cd)PYRENE	52,000	700,000	<330	<330
	,	,		

#### PAGE 2 OF 2

# HUNTINGDON ANALYTICAL SERVICES ENVIRONMENTAL

METHOD 8270 SEMI-VOLATILE ORGANICS

SAMPLE IDENTIFICATION:	TP-3B	TP-3C	METHOD BLANK	
HAS SAMPLE #92-501-	002	003		
BASE/NEUTRAL	RESULT	RESULT	RESULT	MDL
COMPOUNDS	ug/Kg	ug/Kg	ug/Kg	ug/Kg
ISOPHORONE	<17,000	<33,000	<330	<330
2-METHYL NAPHTHALENE	660,000	3,800,000	<330	<330
NAPHTHALENE	2,000,000	12,000,000	<330	<330
2-NITROANILINE	<80,000	<160,000	<1,600	<1,600
3-NITROANILINE	<80,000	<160,000	< 1,600	<1,600
4-NITROANILINE	<80,000	<160,000	<1,600	< 1,600
NTTROBENZENE	<17,000	<33,000	<330	<330
N-NTTROSODIPHENYLAMINE	<33,000	<33,000 .	<330	<330
N-NTTROS-DI-N-PROPYLAMINE	<17,000	<33,000	<330	<330
PHENANTHRENE	1,500,000	6,400,000	<330	<330
PYRENE	750,000	3,600,000	<330	<330
1,2,4-TRICHLOROBENZENE	< 17,000	<33,000	<330	<330
ACID COMPOUNDS	RESULT	RESULT	RESULT	MDL
ACID COM CONDS	ug/Kg	ug/Kg		
	ug/kg	ug/kg	ug/Kg	ug/Kg
BENZOIC ACID	<80,000	<160,000	<1,600	<1,600
4-CHLORO-3-METHYLPHENOL	< 17,000	<33,000	<330	<330
2-CHLOROPHENOL	<17,000	<33,000	<330	<330
2,4-DICHLOROPHENOL	<17,000	<33,000	<330	<330
2,4-DIMETHYL PHENOL	<17,000	820,000	<330	<330
2,4-DINTTROPHENOL	<80,000	<160,000	<1,600	<1,600
4,6-DINITRO-2-METHYLPHENOL	<80,000	<160,000	<1,600	<1,600
2-METHYL PHENOL	<17,000	460,000	<330	<330
4-METHYL PHENOL	<17,000	1,300,000	<330	<330
2-NITROPHENOL	<17,000	<33,000	<330	<330
4-NTTROPHENOL	<80,000	<160,000	<1,600	< 1,600
PENTACHLOROPHENOL	<80,000	<160,000	<1,600	<1,600
PHENOL	<17,000	470,000	<330	<330
2,4,5-TRICHLOROPHENOL	<80,000	<160,000	< 1,600	<1,600
2,4,6-TRICHLOROPHENOL	< 17,000	<33,000	<330	<330
DATE OF UNITED	4.45.00	2.05.02		
DATE SAMPLED:	3-25-92	3-25-92		
DATE RECEIVED:	3-27-92	3-27-92		
DATE EXTRACTED:	3-30-92	3-30-92	3-30-92	
DATE ANALYZED:	3-31-92	3-31-92	3-30-92	

#### ENVIRONMENTAL ANALYTICAL REPORT

REPORT NUMBER 92-535

#### PREPARED FOR:

EMPIRE SOILS INVESTIGATIONS, INC. S-5167 S. PARK AVENUE HAMBURG, NEW YORK 14075

RE: BTA-92-060, BURA-PHASE II

#### PREPARED BY:

HUNTINGDON ANALYTICAL SERVICES
DIVISION OF EMPIRE SOILS INVESTIGATIONS, INC.
P.O. BOX 250
MIDDLEPORT, NEW YORK 14105

APRIL 29, 1992

PAGE 1



#### HUNTINGDON ANALYTICAL SERVICES ELAP #10833 ENVIRONMENTAL REPORT

REPORT NUMBER 92-535

#### STATEMENT OF WORK PERFORMED

I HEREBY DECLARE THAT THE WORK WAS PERFORMED UNDER MY SUPERVISION ACCORDING TO THE PROCEDURES OUTLINED BY THE FOLLOWING REFERENCES AND THAT THIS REPORT PROVIDES A CORRECT AND FAITHFUL RECORD OF THE RESULTS OBTAINED.

- 40 CFR PART 136, "GUIDELINES ESTABLISHING TEST PROCEDURES FOR THE ANALYSIS OF POLLUTANTS UNDER THE CLEAN WATER ACT", OCTOBER 26, 1984 (FEDERAL REGISTER) U. S. ENVIRONMENTAL PROTECTION AGENCY.
- U.S. ENVIRONMENTAL PROTECTION AGENCY, "TEST METHODS OF EVALUATING SOLID WASTE PHYSICAL/CHEMICAL METHODS", OFFICE OF SOLID WASTE AND EMERGENCY RESPONSE, SW-846, 2ND EDITION AND 3RD EDITION.
- NEW YORK STATE DEPARTMENT OF HEALTH, ANALYTICAL TOXICOLOGY LABORATORY HANDBOOK, AUGUST 1982.

RICHARD J. RONAN, PH.D.

APRIL 29, 1992

LABORATORY DIRECTOR, ENVIRONMENTAL

#### REPORT CODE LEGEND:

<DL = LESS THAN DETECTION LIMIT

ND = NOT DETECTED

NA = NOT APPLICABLE

INP = INFORMATION NOT PROVIDED

MB = METHOD BLANK



#### HUNTINGDON ANALYTICAL SERVICES. INC. Environmental

lnorganio wet Chemical Analyses

Sample Identification: MW-5

HAS Samole #92-535-001

Date Sampled: 3/31/92

				l Method			
: :	·	Date		Detection	i	j	i
1 Analyte (	EPA Method I					1 Units	QC in %
ا ـ ـ ـ ـ ـ ـ ـ ـ ـ ـ ـ ـ ـ ـ ـ ـ ـ ـ ـ				1	1		
1	i		i	i	(	1	i <1***
ioH i	5W-546 90451	4/6/92	1 4/6/92	0.10	1 7.30	! S. U.	95 <del>**</del>
	!		<b>i</b>	) 	i	i	i
!	!		<b>!</b> :	Initial   Temo.	:	1	
Flash Point :	SW-846 1010	A 74 790 -	i - 4747 <b>9</b> 2 -		, ( >160	, , of	101 <del>*</del>
irlasiriusiie i	i 040 1010	470772	1 7/0//2	, 65 i	1 2100	1 5	101
į	i i		I	I	1 / ~	1	16***
Total Cyanice i	SW-846 90101	4/8/92	4/8/92	1.0	i (2.3)	i mg/kg i	96∗
!	;	i	l ·	İ	1	í	i e
i	í		1	i	1	1	1
Reactivity 1	SW-846 1	1	!	!	I.	i i	İ
!	Section 7.3	1		1	1	! !	İ
7	!	•		1	1	1	
Total (	, acto :	1 14 7 100	l - 7.747.400.	i i 50	1 1 <50	img/kg as i	07.5
Releasable Sulfide!	7050 1	4/14/72!	4/14/92	חק י	: 750	1 H2S (	94*
Total ,	1	i			1	img/kg as i	
Releasable Cyanidel	9010 - I	4/14/921	4/14/92	. 50	i <50	I HCN I	104*
nereconsists symmetri	i	i			1	1	
1	i	,		i	i	i	

- \* A known standard of the analyte of interest was analyzed along with this sample with the percent recovery indicated above.
- \*\* This indicates that a 95% confidence limit was achieved with an EPA Quality Control Check analyzed with this sample.
- \*\*\* This sample was analyzed in ouplicate with the RPD indicated above.

#### HUNTINGDON ANALYTICAL SERVICES

#### METALS ANALYSIS-TCLP DATA SHEET

Sample ID: BTA-92-060 BURA--PHASE II MW-3 HAS Sample #92-0535-001

Date Sampled: 3/31/92

ANALYTE	EPA METHOD	EPA LIMITS	DATE ANALYZED	DETECTION LIMIT	RESULT mg/l	QC %REC	RPD
ARSENIC BARIUM CADMIUM CHROMIUM LEAD MERCURY SELENIUM SILVER	6010 6010 6010 6010 6010 7470 6010 6010	5.0 mg/l 100 mg/l 1.0 mg/l 5.0 mg/l 5.0 mg/l 0.2 mg/l 1.0 mg/l 5.0 mg/l	4/14/92 4/14/92 4/14/92 4/14/92 4/14/92 4/28/92 4/14/92 4/14/92	0.50 0.10 0.050 0.10 0.40 0.0002 0.60 0.10	<pre></pre>	*95 *95 *95 *95 *95 *95 *95	1.0

<sup>\*</sup>THIS INDICATES A 95% CONFIDENCE LIMIT ACHIEVED WITH AN EPA QUALITY CONTROL SOLUTION ANALYZED ALONG WITH YOUR SAMPLE.

#### HUNTINGDON ANALYTICAL SERVICES

#### METALS ANALYSIS-TCLP DATA SHEET

Sample ID: TCLP B# 1
HAS Sample #92-0535-B#1

Date Sampled: NA

	EPA	EPA	DATE	DETECTION	RESULT	
ANALYTE	METHOD	LIMITS	ANALYZED	LIMIT	mg/l	QC
ARSENIC	6010	5.0  mg/l	4/14/92	0.50	<dl< td=""><td><b>*</b>95</td></dl<>	<b>*</b> 95
BARIUM	6010	100  mg/l	4/14/92	0.10	<dl< td=""><td><b>*</b>95</td></dl<>	<b>*</b> 95
CADMIUM	6010	1.0  mg/l	4/14/92	0.050	<dl< td=""><td><b>*</b>95</td></dl<>	<b>*</b> 95
CHROMIUM	6010	5.0  mg/l	4/14/92	0.10	<dl< td=""><td><b>*</b>95</td></dl<>	<b>*</b> 95
LEAD	6010	5.0  mg/l	4/14/92	0.40	<dl< td=""><td><b>*</b>95</td></dl<>	<b>*</b> 95
MERCURY	7470	0.2  mg/l	4/28/92	0.0002	<dl< td=""><td><b>*</b>95</td></dl<>	<b>*</b> 95
SELENIUM	6010	1.0  mg/l	4/14/92	0.60	<dl< td=""><td><b>*</b>95</td></dl<>	<b>*</b> 95
SILVER	6010	5.0  mg/l	4/14/92	0.10	<dl< td=""><td><b>*</b>95</td></dl<>	<b>*</b> 95
CADMIUM CHROMIUM LEAD MERCURY SELENIUM	6010 6010 6010 7470 6010	1.0 mg/l 5.0 mg/l 5.0 mg/l 0.2 mg/l 1.0 mg/l	4/14/92 4/14/92 4/14/92 4/28/92 4/14/92	0.050 0.10 0.40 0.0002 0.60	<dl <dl <dl <dl< td=""><td>*95 *95 *95 *95 *95</td></dl<></dl </dl </dl 	*95 *95 *95 *95 *95

<sup>\*</sup>THIS INDICATES A 95% CONFIDENCE LIMIT ACHIEVED WITH AN EPA QUALITY CONTROL SOLUTION ANALYZED ALONG WITH YOUR SAMPLE.

METHOD 608
TARGET COMPOUND LIST
TCLP EXTRACT

SAMPLE IDENTIFICATION :	METHOD BLANK	MW-3
HAS SAMPLE #92-535-		001
DATE ANALYZED:	4-13-92	4-13-92
COMPOUND	RESULT ug/L	RESULT ug/L
ALDRIN	<0.25 <0.25 <0.25 <0.25 <2.5 <0.50	<0.25 <0.25 <0.25 <0.25 <0.25 <2.5 <0.50
4,4-DDE 4,4-DDT DIELDRIN ENDOSULFAN I ENDOSULFAN II ENDOSULFAN SULFATE	<0.50 <0.50 <0.50 <0.25 <0.50 <0.50	<0.50 <0.50 <0.50 <0.25 <0.50 <0.50
ENDRIN ENDRIN ALDEHYDE HEPTACHLOR HEPTACHLOR EPOXIDE TOXAPHENE	<0.50 <0.50 <0.25 <0.25 <5.0	<0.50 <0.50 <0.25 <0.25 <5.0
METHOXYCHLOR ENDRIN KETONE PCB-1016 PCB-1221 PCB-1232	<2.5 <0.50 <2.5 <2.5 <2.5	<2.5 <0.50 <2.5 <2.5 <2.5
PCB-1242	<2.5 <2.5	<2.5 <2.5 <5.0 <5.0

#### EPA METHOD 624 TCLP VOLATILE ORGANICS

SAMPLE IDENTIFICATION :	MW-3	METHOD BLANK	
HAS SAMPLE #92-535-	Ø01	·	
COMPOUND	RESULT ug/l	RESULT ug/l	MDL ug/l
	ug/1	WE/ I	u5/ ±
CHLOROMETHANE	<5Ø	<5Ø	<5Ø
BROMOMETHANE	<5Ø	<5Ø	<5Ø
VINYL CHLORIDE	<5Ø	<5Ø	<5Ø
CHLOROETHANE	<5Ø	<5Ø	<5Ø
METHYLENE CHLORIDE	29 *	31 *	<25
ACETONE	73 *	56Ø ∗	<5Ø
TRICHLOROFLUOROMETHANE	<5Ø	<5Ø	<5Ø
CARBON DISULFIDE	<25	<25	<25
1,1-DICHLOROETHENE	<25	<25	<25
1,1-DICHLOROETHANE	<25	<25	<25
1,2-DICHLOROETHENE (TOTAL) -	<25	<25	<25
CHLOROFORM	<25	<25	<25
1,2-DICHLOROETHANE	<25	<25	<25
2-BUTANONE	<5Ø	<5Ø	<5Ø
1,1,1-TRICHLOROETHANE	<25	<25	<25
CARBON TETRACHLORIDE	<25	<25	<25
VINYL ACETATE	<5Ø	<5Ø	<5Ø
BROMODICHLOROMETHANE	<25	<25	<25
1,2-DICHLOROPROPANE	<25	<25	<25
cis-1,3-DICHLOROPROPENE	<25	<25	<25
TRICHLOROETHENE	<25	<25	<25
DIBROMOCHLOROMETHANE	<25	<25	<25
1,1,2-TRICHLOROETHANE	<25	<25	<25
BENZENE	<25	<25	<25
trans-1,3-DICHLOROPROPENE	<25	<25	<25
2-CHLOROETHYLVINYL ETHER	<100	<100	<100
EROMOFORM	<25	<25	<25
4-METHYL-2-PENTANONE	<5Ø	<5Ø	<5Ø
2-HEXANONE	<5Ø	<5Ø	<5Ø
TETRACHLOROETHENE	<25	<25	<25
1,1,2,2-TETRACHLOROETHANE	<25	<25	<25
TOLUENE		<25	<25
CHLOROBENZENE		<25	<25
ETHYL BENZENE	<25	<25	<25
STYRENE		<25	<25
	<25	<25	<25
	<5Ø	<5Ø	<5Ø
	<5Ø	<5Ø	<5Ø
1,4-DICHLOROBENZENE	<5Ø	<5Ø	<5Ø
DATE SAMPLED:	3-31-92		
DATE RECEIVED:	4-1-92		
TCLP DATE:	4-7-92	4-7-92	
DATE ANALYZED:	4-9-92	4-9-92	
DULE MANDIEN.	7 0 02	1 3 02	

<sup>\*</sup> LABORATORY BACKGROUND

## TCLP EXTRACTION/METHOD 8270 SEMI-VOLATILE ORGANICS

SAMPLE IDENTIFICATION:	MW-3	METHOD BLANK	
HAS SAMPLE #92-535-	001		
BASE/NEUTRAL	RESULT	RESULT	MDL
COMPOUNDS	ug/L	ug/L	ug/L
ACENAPHTHENE	<50	<50	<50
ACENAPHTHYLENE	<50	<50	<50
ANTHRACENE	<50	<50	<50
BENZO(a)ANTHRACENE	<50	<50	<50
BENZO(b)FLUORANTHENE	<50	<50	<50
BENZO(k)FLUORANTHENE	<50	<50	<50
BENZO(a)PYRENE	<50	<50	<50
BENZO(g,h,i)PERYLENE	<50	<50	<50
BENZYL ALCOHOL	<50	<50	<50
BIS(2-CHLOROETHOXY)METHANE	<50	<50	<50
BIS(2-CHLOROETHYL)ETHER	<50	<50	<50
BIS(2-CHLOROISOPROPYL)ETHER	<50	<50	<50
BIS(2-ETHYLHEXYL)PHTHALATE	<50	<50	<50
BUTYLBENZYL PHTHALATE	<50	<50	<50
4-BROMOPHENYL-PHENYL ETHER	<50	<50	<50
4-CHLOROANILINE	<50	<50	<50
2-CHLORONAPHTHALENE	<50	<50 .	<50
4-CHLOROPHENYL-PHENYL ETHER	<50	<50	<50
CHRYSENE	<50	<50	<50
DIBENZ(a,h)ANTHRACENE	<50	<50	<50
DIBENZOFURAN	<50	<50	<50
DI-N-BUTYLPHTHALATE	<50	<50	<50
1,2-DICHLOROBENZENE	<50	<50	<50
1,3-DICHLOROBENZENE	<50	<50	<50
1,4-DICHLOROBENZENE	<50	<50	<50
3,3-DICHLOROBENZIDINE	< 100	< 100	<100
DIETHYL PHTHALATE	<50	<50	<50
DIMETHYL PHTHALATE	<50	<50	<50
2,4-DINITROTOLUENE	<50	<50	<50
2,6-DINTIROTOLUENE	<50	<50	<50
DI-N-OCTYL PHTHALATE	<50	<50	<50
FLUORANTHENE	<50	<50	<50
FLUORENE	<50	<50	<50
HEXACHLOROBENZENE	<50	<50	<50
HEXACHLOROBUTADIENE	<50	<50	<50
HEXACHLOROCYCLOPENTADIENE	<50	<50	<50
HEXACHLOROETHANE	<50	<50	
INDENO(1,2,3-cd)PYRENE	<50	<50 <50	<50
INDERO(1,2,3-cu)r I KENE	~50	< 30	<50

PAGE 2 OF 2

TCLP EXTRACTION/METHOD 8270 SEMI-VOLATILE ORGANICS

SAMPLE IDENTIFICATION:	MW-3	METHOD BLANK	
HAS SAMPLE #92-535-	001		
BASE/NEUTRAL	RESULT	RESULT	MDL
COMPOUNDS	ug/L	ug/L	ug/L
ISOPHORONE	<50	<50	<50
2-METHYL NAPHTHALENE	<50	<50	<50
NAPHTHALENE	<50	<50	<50
2-NITROANILINE	<250	<250	<250
3-NITROANILINE	<250	<250	<250
4-NITROANILINE	<250	<250	<250
NITROBENZENE	<50	<50	<50
N-NITROSODIPHENYLAMINE	<50	<50	<50
N-NITROS-DI-N-PROPYLAMINE	<50	<50	<50
PHENANTHRENE	<50	<50	<50
PYRENE	<50	<50	<50
1,2,4-TRICHLOROBENZENE	<50	<50	<50
ACID COMPOUNDS	RESULT	RESULT	MDL
	ug/i	ug/I	ug/i
BENZOIC ACID	<250	<250	<250
4-CHLORO-3-METHYLPHENOL	<50	<50	<50
2-CHLOROPHENOL	<50	<50	<50
2,4-DICHLOROPHENOL	<50	<50	<50
2,4-DIMETHYL PHENOL	<50	<50	<50
2,4-DINTTROPHENOL	<250	<250	<250
4,6-DINTTRO-2-METHYLPHENOL	<250	<250	<250
2-METHYL PHENOL	<50	<50	<50
4-METHYL PHENOL	<50	<50	<50
2-NTTROPHENOL	<50	<50	<50
4-NTTROPHENOL	<250	<250	<250
PENTACHLOROPHENOL	<250	<250	<250
PHENOL	<50	<50	<50
2,4,5-TRICHLOROPHENOL	<250	<250	<250
2,4,6-TRICHLOROPHENOL	<50	<50	<50
DATE SAMPLED:	3-31-92		
DATE RECEIVED:	4-1-92	*****	
TCLP DATE:	4-7-92	4-7-92	
DATE EXTRACTED:	4-9-92	4-9-92	
DATE ANALYZED:	4-9-92	4-9-92 4-9-92	
		4-7-72	

ellont Kont Forpire Soils	110	Contout DAVE STRINET	XAS Quete 6
	3 1 1 2 1 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2	(716)641-1110	1.0.
ATM-02100	Pro  ot / R  to Mone	sayl Last sanigines	
TARPLOTO (SIGNATUTO):	HAS ROLL TOWNS TO THE PARTY OF	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	Analyels Requested/
0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	A SAN CONTRACTOR NAME OF THE PARTY OF THE PA	479 52/479 6	
3/3//2/1215	<u> </u>	1 2	1950 ml - Reactivity, corresivity
			Ign, tability, TCL PCB'S
			(methed BUBO), FULL TCL
	/		CXCENT VOLATILES (TELD Principles
			1 `
			(TULD PLOCE
			XX ANAlyze ONIY ONE
		7 	125 ml SAMPLE
			/. 
Jedinquiened by:	3.31.821500 EST Cooler	Relingulated by	Jane Heart May 19 Ann
Laster M. March	U.S. 11REL ROCOIVED by:	Relinquished by:	PRIST ILES (ROSIVED BY:
		-//-	

#### ENVIRONMENTAL ANALYTICAL REPORT

REPORT NUMBER 92-558

#### PREPARED FOR:

EMPIRE SOILS INVESTIGATIONS, INC. S-5167 S. PARK AVENUE HAMBURG, NEW YORK 14075

RE: BTA-92-060, BURA - PHASE II

#### PREPARED BY:

HUNTINGDON ANALYTICAL SERVICES
DIVISION OF EMPIRE SOILS INVESTIGATIONS, INC.
P.O. BOX 250
MIDDLEPORT, NEW YORK 14105

APRIL 21, 1992

#### HUNTINGDON ANALYTICAL SERVICES ELAP #10833 ENVIRONMENTAL REPORT

REPORT NUMBER 92-558

#### STATEMENT OF WORK PERFORMED

I HEREBY DECLARE THAT THE WORK WAS PERFORMED UNDER MY SUPERVISION ACCORDING TO THE PROCEDURES OUTLINED BY THE FOLLOWING REFERENCES AND THAT THIS REPORT PROVIDES A CORRECT AND FAITHFUL RECORD OF THE RESULTS OBTAINED.

- 40 CFR PART 136, "GUIDELINES ESTABLISHING TEST PROCEDURES FOR THE ANALYSIS OF POLLUTANTS UNDER THE CLEAN WATER ACT", OCTOBER 26, 1984 (FEDERAL REGISTER) U. S. ENVIRONMENTAL PROTECTION AGENCY.
- U.S. ENVIRONMENTAL PROTECTION AGENCY, "TEST METHODS OF EVALUATING SOLID WASTE PHYSICAL/CHEMICAL METHODS", OFFICE OF SOLID WASTE AND EMERGENCY RESPONSE, SW-846, 2ND EDITION AND 3RD EDITION.
- NEW YORK STATE DEPARTMENT OF HEALTH, ANALYTICAL TOXICOLOGY LABORATORY HANDBOOK, AUGUST 1982.

RICHARD J. RONAN, PH.D.

' APRIL<sup>l</sup> 21, 1992

LABORATORY DIRECTOR, ENVIRONMENTAL

#### REPORT CODE LEGEND:

<DL = Less than detection limit

ND = NOT DETECTED

NA = NOT APPLICABLE

INP = Information not provided

MB = METHOD BLANK



METHOD DOH 310-13
PETROLEUM PRODUCTS IN WATER

SAMPLE IDENTIFICATION:	METHOD BLANK	HV-1	<b>₩-2</b>	MW-3	HW-4
HAS SAMPLE #92-558-		001	002	003	004
DATE ANALYZED:	4-10-92	4-10-92	4-10-92	4-10-92	4-10-92
COMPOUND	RESULT ug/L	RESULT * ug/L	RESUL <b>T *</b> ug/L	RESULT * ug/L	RESUL <b>T</b> ug/L
GASOLINE	ND	ND	ND	ND	ND
KEROSENE	<100	<5000	<50 <b>0</b> 0	<500	<100
FUEL OILS	<100	<5000	<5000	<1000	<100
LUBE OIL	ND	ND	ND	ND	ND

ND = NONE DETECTED

<sup>\*</sup> ELEVATED DETECTION LIMITS NECESSITATED BY HIGH LEVELS OF PAH'S. SEE 8270 ANALYSIS.

METHOD 602 PURGEABLE AROMATICS

SAMPLE IDENTIFICATION:	METHOD BLANK	MW-1	MW-2	MW-3	MW-4
HAS SAMPLE #92-558-	*****	001	002	003	004
COMPOUND	RESULT ug/l	RESULT ug/l	RESULT ug/l	RESULT ug/l	RESULT ug/l
BENZENE	< 0.50	16,000 -	21,000	86	< 0.50
TOLUENE	< 0.50	3,700	5,800	< 5.0	< 0.50
ETHYL BENZENE	< 0.50	<500	<500	< 5.0	0.59
TOTAL XYLENES	<1.0	1,100	1,100	< 10	1.4
CHLOROBENZENE	< 0.50	< 500	< 500	< 5.0	< 0.50
1,4-DICHLOROBENZENE	< 0.50	< 500	<500	<5.0	< 0.50
1,3-DICHLOROBENZENE	< 0.50	<500	< 500	<5.0	< 0.50
1,2-DICHLOROBENZENE	<1.0	<1,000	<1,000	<10	<1.0
DATE SAMPLED:		4-2-92	4-2-92	4-2-92	4-2-92
DATE RECEIVED:		4-6-92	4-6-92	4-6-92	4-6-92
DATE EXTRACTED:	4-11-92	4-11-92	4-11-92	4-11-92	4-10-92
DATE ANALYZED:	4-11-92	4-11-92	4-11-92	4-11-92	4-10-92

#### PAGE 1 OF 2

# HUNTINGDON ANALYTICAL SERVICES ENVIRONMENTAL

METHOD 8270 SEMI-VOLATILE ORGANICS

SAMPLE IDENTIFICATION:	MW-1	MW-2	MW-3	MW-4	METHOD BLANK	
HAS SAMPLE #92-558-	001	002	003	004		
BASE/NEUTRAL	RESULT	RESULT	RESULT	RESULT	RESULT	MDL
COMPOUNDS	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L
ACENAPHTHENE	73	41	17	< 10	<10	·< 10
ACENAPHTHYLENE	120	250	< 10	< 10	<10	< 10
ANTHRACENE	10	25	< 10	< 10	< 10	_<10
BENZO(a)ANTHRACENE	< 10	< 10	< 10	< 10	< 10	< 10
BENZO(b)FLUORANTHENE	< 10	< 10	< 10	<10	< 10	< 10
BENZO(k)FLUORANTHENE	< 10	< 10	< 10	<10	< 10	< 10
BENZO(a)PYRENE	< 10	< 10	< 10	< 10	< 10	< 10
BENZO(g,h,i)PERYLENE	< 10	< 10	< 10	<10	< 10	< 10
BENZYL ALCOHOL	<10	< 10	< 10	< 10	< 10	< 10
BIS(2-CHLOROETHOXY)METHANE	< 10	< 10	< 10	< 10	< 10	<10
BIS(2-CHLOROETHYL)ETHER	< 10	< 10	< 10	< 10	<10	< 10
BIS(2-CHLOROISOPROPYL)ETHER	< 10	<10	< 10	<10	< 10	<10
BIS(2-ETHYLHEXYL)PHTHALATE	< 10	< 10	< 10	< 10	<10	< 10
BUTYLBENZYL PHTHALATE	< 10	< 10	< 10	<10	<10	< 10
4-BROMOPHENYL-PHENYL ETHER	< 10	< 10	< 10	< 10	<10	< 10
4-CHLOROANILINE	< 10	< 10	< 10	< 10	< 10	< 10
2-CHLORONAPHTHALENE	<10	< 10	< 10	<10	< 10	< 10
4-CHLOROPHENYL-PHENYL ETHER	< 10	< 10	< 10	<10	< 10	< 10
CHRYSENE	< 10	< 10	< 10	< 10	< 10	< 10
DIBENZ(a,h)ANTHRACENE	<10	< 10	< 10	<10	< 10	<10
DIBENZOFURAN	47	82	< 10	<10	< 10	<10
DI-N-BUTYLPHTHALATE	< 10	< 10	< 10	< 10	< 10	< 10
1,2-DICHLOROBENZENE	<10	< 10	< 10	<10	< 10	< 10
1,3-DICHLOROBENZENE	< 10	< 10	< 10	< 10	< 10	<10
1,4-DICHLOROBENZENE	< 10	< 10	< 10	< 10	< 10	< 10
3,3-DICHLOROBENZIDINE	<20	< 20	< 20	<20	<20	<20
DIETHYL PHIHALATE	12	< 10	< 10	< 10	< 10	< 10
DIMETHYL PHIHALATE	<10	< 10	< 10	< 10	< 10	<10
2,4-DINITROTOLUENE	<10	< 10	< 10	< 10	<10	< 10
2,6-DINITROTOLUENE	< 10	< 10	<10	<10	< 10	< 10
DI-N-OCTYL PHTHALATE	< 10	< 10	< 10	<10	<10	< 10
FLUORANTHENE	< 10	15	< 10	< 10	< 10	< 10
FLUORENE	40	72	12	< 10	< 10	< 10
HEXACHLOROBENZENE	<10	< 10	< 10	<10	< 10	< 10
HEXACHLOROBUTADIENE	< 10	< 10	< 10	< 10	< 10	<10
HEXACHLOROCYCLOPENTADIENE	< 10	< 10	< 10	< 10	< 10	< 10
HEXACHLOROETHANE	< 10	< 10	< 10	< 10	< 10	< 10
INDENO(1,2,3-cd)PYRENE	< 10	< 10	< 10	< 10	< 10	< 10

#### PAGE 2 OF 2

# HUNTINGDON ANALYTICAL SERVICES ENVIRONMENTAL

METHOD 8270 SEMI-VOLATILE ORGANICS

SAMPLE IDENTIFICATION:	MW-1	MŴ-2	MW-3	MW-4	METHOD BLANK	
HAS SAMPLE #92-558-	001	002	003	004		
BASE/NEUTRAL	RESULT	RESULT	RESULT	RESULT	RESULT	MDL
COMPOUNDS	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L
ISOPHORONE	< 10	< 10	< 10	<10	< 10	< 10
2-METHYL NAPHTHALENE	530	.640	<10	< 10	< 10	< 10
NAPHTHALENE	5,200	6,500	< 10	<10	<10	< 10
2-NTTROANILINE	<50	<50	<50	<50	<50	<50
3-NITROANILINE	<50	<50	<50	<50	<50	<50
4-NITROANILINE	<50	<50	<50	<50	<50	<50
NITROBENZENE	< 10	< 10	<10	< 10	< 10	< 10
N-NTTROSODIPHENYLAMINE	< 10	< 10	< 10	< 10	< 10	< 10
N-NTTROS-DI-N-PROPYLAMINE	< 10	< 10	< 10	< 10	< 10	< 10
PHENANTHRENE	39	81	<10	<10	< 10	< 10
PYRENE	<10	<10	<10	<10	<10	< 10
1,2,4-TRICHLOROBENZENE	< 10	< 10	<10	<10	< 10	< 10
ACID COMPOUNDS	RESULT	RESULT	RESULT	RESULT	RESULT	MDL
	ug/I	ug/l	ug/I	ug/l	ug/l	ug/l
	-6.	-6.	-5.	~ <i>B</i> .	-5.	56.
BENZOIC ACID	<50	<50	<50	· <50	<50	<50
4-CHLORO-3-METHYLPHENOL	<10	< 10	< 10	< 10	< 10	< 10
2-CHLOROPHENOL	< 10	< 10	<10	<10	< 10	<10
2,4-DICHLOROPHENOL	< 10	< 10	< 10	<10	< 10	< 10
2,4-DIMETHYL PHENOL	→ 13,000	21,000	<10	< 10	< 10	< 10
2,4-DINITROPHENOL	<50	<50	<50	<50	<50	<50
4,6-DINITRO-2-METHYLPHENOL	<50	< 50	<50	<50	< 50	<50
2-METHYL PHENOL	~>13,000	20,000	< 10	< 10	< 10	< 10
4-METHYL PHENOL	->28,000	46,000	< 10	< 10	< 10	<10
2-NTTROPHENOL	< 10	<10	< 10	< 10	< 10	< 10
4-NTTROPHENOL	<50	<50	<50	<50	< 50	<50
PENTACHLOROPHENOL	<50	<50	<50	<50	<50	<50
PHENOL	→ 17,000	27,000	<10	<10	< 10	<10
2,4,5-TRICHLOROPHENOL	<50	<50	<50	<50	<50	<50
2,4,6-TRICHLOROPHENOL	<10	<10	< 10	<10	< 10	<10
2,4,0-11dc1fE0N011fEN0E	110	110	110	<10	<10	~10
D						
DATE SAMPLED:	4-2-92	4-2-92	4-2-92	4-2-92	*****	
DATE RECEIVED:	4-6-92	4-6-92	4-6-92	4-6-92	****	
DATE EXTRACTED:	4-8-92	4-8-92	4-8-92	4-8-92	4-8-92	
DATE ANALYZED:	4-9-92	4-9-92	4-9-92	4-9-92	4-8-92	

IXXIIXIVIX AVALTIIGAL IX	INVITABLE ANALYTICAL INVIGER - GRAIN-OF-SUNIONY REGOIN ALA ANALYTICAL REQUEST FORM	-1
CITION NOW STANKE STANKE	Client Centeet DAVE STEWAY	
LINE (HAMBURE)	8476 J. 100.1	1 1 1 1
STA-92060		1 1 5 3 6 5
liaplere (figneture)!	35.	/>
•	HAN THE STATE OF T	
1 - 7	2/2/ 1/1/1/1/1/1/1/1/1/1/1/1/1/1/1/1/1/1	10-135
00:h 2-mu	X mw. 2 002, Wy 1 = 2 2   726 semi-vocations 500 80	A 42705 A020.
155.6	1   2   2   0   9   0   5   2   2	
	17 17 17 17 12 12 1/1 1/200 1/20/1/2/1	
Itelinquiehed by:	PRIET ILREL ACCIONA BY: AND THE CONTROL BY: PRIET LIREL ACCOUNTS AND AND AND AND AND AND AND AND AND AND	- Sincolaries
if the whaten	Ileas   foce   ved by	
	4/7/62 Q:45	

!

1

# DEPARTMENT OF INSPECTIONS and COMMUNITY REVITALIZATION

#### OFFICE OF THE COMMISSIONER

WAT	ERFRONT REDEVELOPMENT PROJECT PARCELS 17A, 23 and
	24
	Dete March 15, 1993
to:	*SEE BELOW
	FOR YOUR ATTENTION
	FOR YOUR INFORMATION
	FOR YOUR FILES
	PLEASE ANSWER DIRECT STATING THAT YOU ARE ANSWERING FOR THIS OFFICE
	PLEASE SEND COPY OF REPLY TO THIS OFFICE
	PLEASE ADVISE ME
	PLEASE PREPARE REPLY FOR MY SIGNATURE
	PLEASE INVESTIGATE AND REPORT TO ME
	PLEASE INVESTIGATE AND REPORT TO COMPLAINANT
	FOR CENTRAL FILING
ks: ///.	Alle
HV.	SCHOLLARD, COMMISSIONER
n	
~	- Pill
	es Pitts oner Sam Iraci
	Anderhalt

CV