PERIODIC REVIEW REPORT (PRR) INACTIVE LANDFILL AREA SAINT GOBAIN ABRASIVES, INC.

St. Gobain Abrasives Division Site No. 932007 6600 Walmore Road Wheatfield NY 14304

FTA Report ET-13-703PRR

March 13, 2013

Prepared For:

Mr. Douglas M. Wright Saint Gobain Abrasives, Inc. P.O. Box 301 (6600 Walmore Road) Niagara Falls, NY 14304

Prepared By:

Frontier Technical Associates, Inc. 8675 Main Street Williamsville, NY 14221


This report was prepared at the request of and for the use of Saint Gobain Abrasives, Inc. management use only, and except for required regulatory compliance reporting, is not intended for any other purpose. This report updates previously submitted information and reflects no change in the data.

INTRODUCTION


In response to the requirements of NYSDEC (6 NYCRR 375-1.2), Saint Gobain Abrasives, Inc. has requested that Frontier Technical Associates, Inc. complete documentation of site activities and site characteristics of the former Carborundum Abrasives Inactive Landfill Site (932007). This site was capped in 1981 and since that time inspections and groundwater sampling and analysis for the landfill area located on the southwest corner of the property in Wheatfield, NY have been completed. Figure 1 is a sketch of the landfill area showing the location of the monitoring wells which were installed in 1981 and the location of the "A" storm sewer line (West Branch) (see NFTA security fence installed in 2004). Figure 1 A is an aerial photo of the area with the fence installed. Frontier Technical Associates, Inc. has completed much of the monitoring and site activities since that time, and has periodically submitted inspection and monitoring reports to the NYSDEC documenting these activities. FTA had prepared technical reports describing sampling and analytical results for 1991. The NYSDEC subsequently reduced monitoring parameters for 1992. For 1993, the NYSDEC deleted the requirement for analysis of unfiltered groundwater for metals, and for 1994, all metals requirements were deleted and turbidity was added for informational purposes. After the 1997 monitoring episode, SGC requested and received approval to monitor these wells every two years. FTA has been inspecting the wells quarterly and expects to continue to do so until the next regularly scheduled bi-annual sampling event in 2013.

Since 1982, the monitoring wells and adjacent catch basin were sampled for pH and total phenolics (4AAP). In the period 1982-1988, there were no detectable levels of phenolics in monitoring wells OW2-81 through OW5-81. However, in 1989, perhaps as the result of unusual spring and summer precipitation events, low levels of phenolics (4AAP) were detected in the monitoring wells and adjacent catch basins. Again in 1990, low levels of total phenolics were detected using the same method. This resulted in the NYSDEC's desire to obtain additional data for evaluation beginning in 1991. Based upon the 1991 results, Well OW1-81 was decommissioned because it had fallen into disrepair and was no longer functioning to monitor the *interior* of the landfill. The request was approved by the NYSDEC and implemented on September 27, 1991. The phenolic compound analytical methodology was also changed to the more accurate and specific EPA Method 8270. The former method (4AAP) is subject to interferences (colorimetric method) typically yielding false positive results. It was deemed inappropriate for monitoring at this site.

This report outlines the approach used to fulfill the NYSDEC requirements for 2012 in connection with the Site Management Periodic Review request. This report covers the period from January 1, 2012 to December 31, 2012.







Legend

Streets and Highways

- Interstate
- Primary State Road
- Secondary State Road
- County Road
- Local Road

Parcels

1Ft Color Aerials

- Red: Band_1
- Green: Band_2
- Blue: Band_3 2Ft Color Aerials
- Red: Band 1
- Green: Band_2
- Blue: Band_3

1:1,414



Enter Map Description

NIAGARA COUNTY, NEW YORK

DEPARTMENT OF REAL PROPERTY SERVICES

The most recent biannual sampling and monitoring effort took place in 2011 and included sampling of all four groundwater monitoring wells and one catch basin which drains the surface runoff and subsurface drainage from the landfill area. In accordance with the Site Sampling Plan, the samples collected were all analyzed for pH, specific conductance, temperature, turbidity and phenolic compounds by EPA Method 8270.


GEOLOGY AND HYDROGEOLOGY

The area in the immediate vicinity of the SGA, Inc. (formerly Carborundum Abrasives) plant is underlain by approximately 10-15 feet of clayey to sandy silt, glacial-lacustrine deposits and glacial till. These deposits thicken southward across the site toward the Niagara River. The hydraulic conductivity of these materials is relatively low, perhaps reaching the range of 10⁻⁵ to 10⁻⁸ cm/sec.

The bedrock underlying the site consists of approximately 160 feet of dolomite of the Lockport Formation. The upper zone of the Lockport Formation is generally highly weathered, medium gray dolomite with extensive vertical fractures. It is generally striated on the surface, has extensive partings which are argillaceous or gypsum-coated. Water produced from this upper zone in the Bergholtz area of Wheatfield is generally of very poor quality, with a characteristic odor. The water generally is not suitable for drinking but occasionally is used for watering livestock or agricultural purposes. The Town of Wheatfield has extended its water lines throughout the area and recent information indicates that there are few wells in use throughout the area. Those that were used occasionally along Walmore Rd to the south were closed as part of a groundwater remediation effort conducted by the former Bell Aerospace-Textron in the late 1980's and early 1990's. This groundwater withdrawal and treatment on-site continues to the present.

The upper portion of the dolomite sequence consists of 10 to 20 feet of bedrock consisting of thinly bedded dolomite which may produce well yields of 10-20 gpm. Hydraulic conductivities of 0.1 to 0.01 cm/sec may be encountered in this unit. For purposes of this current study, it is not thought that any of the wells penetrate significantly into the bedrock and were either drilled to refusal or into the uppermost few feet of the weathered bedrock. The bedrock surface is generally encountered at elevations between 560 feet to 570 feet MSL and is gently dipping to the south.

The wells monitored in this project were drilled to refusal as indicated in a report by Conestoga-Rovers Associates, who installed the wells in 1981 after placement of a clay cap by Secured Landfill Contractors, Inc. (SLC Contractors). Figure 2 illustrates a typical surficial geologic cross section in the landfill area.



FORMER USE OF THE LANDFILL

The former Carborundum Abrasives Company landfill site in Wheatfield was identified in a report by the Inter-Agency Task Force on Hazardous Wastes in the report entitled "Draft Report on Hazardous Waste Disposal in Erie and Niagara County, New York, March 1979." The site was used during the period 1968 to 1976 to dispose of plantgenerated wastes described in the Draft Report as follows:

"...partially solidified and solidified resins, floor sweepings, wastes (sic) fillers including calcium carbonate, clays and animal glue (est. 400 tons total) with free phenols (resins) (est. 800 to 1600 lbs total)."

The method used to dispose of the waste materials involved the excavation of a long, narrow trench. The dimensions of the trench were estimated to be 20 feet in width, 450 feet in length, and 12 feet in depth. As waste materials were deposited into the trench, a soil cover utilizing the excavated soil (glacial-lacustrine clays) was placed over the waste.


MONITORING WELLS

From January 20-22, 1981, Empire Soils Investigations, Inc. installed a total of five groundwater monitoring wells in the landfill area. Four were located at the perimeter of the site and the fifth well was installed through the center of the landfilled waste in order to identify landfill characteristics. This included waste types, depth of disposal, soil cover, and moisture conditions.

All four of the perimeter wells extended to the bedrock-overburden interface or penetrated them slightly. The monitoring well installed in the landfilled waste extended only to the bottom of the landfilled materials. This well was damaged over time and ceased to function properly and was subsequently removed in 1991 (see locations in Figure 1). The wells were constructed of two inch diameter black steel pipe attached to a two foot, Johnson SS well point. All joints were welded during installation. Each well has a protective outer casing with a lockable cap. A typical installation is shown in Figure 3.

STRATIGRAPHY

The landfill area had a typical overburden which included an upper mixed layer of silt and clay fill which supported a grass cover. Two of the wells were installed through the concrete pavement which was approximately six to eight inches in thickness. Beneath these materials was a medium to stiff silty clay material. Traces of vegetative matter could be observed and these materials appeared to be graded and compacted prior to installation of



the concrete pad which, from old photographs of the site, appeared to be either a taxiway or parking area for aircraft manufactured at Bell Aircraft Co. during WW II. Beneath the silty clay fill is a silty clay layer which in the area is reddish brown in color. Some mottling can be observed with gray clay. Beneath these layers is a reddish-brown silt to clayey silt till. The thickness of the materials overlying the bedrock at this site may reach 15 feet based upon other excavations. Most of the perimeter boreholes reached a maximum depth of approximately 17 feet. Bedrock slopes in the area are approximately 0.25 to 0.5 degrees to the south.

Materials encountered in the central borehole included wood, silt, sand, screen materials, paper and the backing cloth used for sandpaper manufacturing. Most of the materials contained in the landfill were general plant trash and off spec materials and damaged goods from the manufacturing process.

GROUNDWATER

The primary presence of groundwater at the landfill site and surrounding area is in a silty till material immediately overlying the bedrock. This layer ranges in thickness from absent at some site locations to approximately 8-12 inches in thickness at others. At the time of the initial investigation in 1981, perched groundwater was observed in the landfill monitoring well. Installation of a landfill cap with appropriate slopes coupled with the low permeability surrounding soils subsequent to the initial investigation in 1981, indicated that the landfill water itself was contained in the landfill. The source was precipitation infiltration. The terrain is relatively flat except for the capped landfill itself. To the west of the landfill, soils remain moist throughout most of the summer due to runoff from the airport runways and taxiways in the area and low permeability of the soils.

The initial piezometric surface observed differs little from 1981 to the present time. The direction of groundwater flow is from the southwest to northeast and has remained constant through the series of investigations carried on over the last 20 years of monitoring by Frontier Technical Associates, Inc. In addition, based up the analysis of the groundwater, the landfill cap has remained intact, and the quality of the groundwater has not been impaired. The landfill is functioning to contain the waste materials present. In addition, it would appear that the waste resins either were polymerized or became polymerized and thus very resistant to breakdown. No phenolic compounds are present in the catch basin draining the immediate area during recent sampling episodes in the last ten years.

SITE MONITORING AND ANALYICAL PLAN

Sampling Objectives

The results of analysis of samples collected and analyzed in accordance with the approval of the NYSDEC are being used to:

- 1. Assess the groundwater flow direction and chemistry.
- 2. Define the nature and extent of pollutant migration, if any.
- 3. Meet the NYSDEC requirements for data submission.

Sampling Personnel

Sampling personnel must be trained and experienced in the procedures used for data collection, sampling procedures and analytical methodology in the field. They must demonstrate their competence in accordance with NYDOH-ELAP certification program. Personnel must be specifically trained in the analytical procedure and pass demonstrations of capability in accordance with the NYSDOH-ELAP requirements and FTA SOPs implementing the Laboratory Procedures Manual.

The project manager is currently David M. Harty, P.E., BCEE. Mr. Harty has been involved with this site since 1981.

Sampling Locations

As indicated previously, Figure 1A and 1B illustrate the sample locations. Four wells are sampled together with one catch basin (MH-9 located on the "A" Storm Line). Table 1 presents the sample locations and USEPA or Standard Methods analytical methods used for samples from each location. All methods used conformed to the USEPA Methods of

Table 1. Sample Locations and Parameters Analyzed

Well Designation	Well Depth (ft)*	Analytical Parameters**
OW2-81	18.20	pH, Specific conductivity, Temperature, Turbidity, Phenols (8270)
OW3-81	19.66	pH, Specific conductivity, Temperature, Turbidity, Phenols (8270)
OW4-81	19.38	pH, Specific conductivity, Temperature, Turbidity, Phenols (8270)
OW5-81	18.23	pH, Specific conductivity, Temperature, Turbidity, Phenols (8270)
MH A-9		pH, Specific conductivity, Temperature, Turbidity, Phenols (8270)

^{*} Based upon measurement by FTA in 1998; rechecked in 2000 and 2003; measured from top of riser pipe.

Phenols = Phenol Compounds as measured by EPA Method 8270.

^{**} Field measurement of pH made within NYELAP guidelines (15 minutes); Turbidity measured using a nephelometer in the field.

Table 2
Summary of Parameters, Methods,
Preservation Methods and Holding Times

Parameter	EPA Method	Preservation	Holding Time
pН	SM18-21: 4500 H B	None	Analyze Immediately- 15 Minutes (Field)
Specific Conductance	120.1 (rev 1982)	4° C	6 Hours (or Field)
Temperature	SM 18:21 2550B		Immediately (Field)
Turbidity	180.1 (Rev 2.0)	4° C	Immediately (Field)
Phenol Compounds	8270	4° C	5 days to extract 28 days to analyze

pH, Specific Conductance, turbidity, and temperature were measured immediately in the field. Frontier Technical Associates, Inc. is a NYELAP-Certified Laboratory (10475).

Analysis for Water and Wastewater (40 CFR Part 136) or SW-846 (as revised). Table 2 is a summary of the parameters, methods used, preservation methods, and holding times required.

Sampling Equipment and Procedures

The procedures outlined here were developed to minimize contamination of water sampling equipment and analyses, minimize concentration changes prior to testing, and standardize procedures to minimize analytical differences.

The procedures below outline the purging, sampling, and preservation methods used during this sampling program in accordance with the approved sampling plan submitted and approved in 1991 and revised in 1999: This plan was revised in November 2012 per the NYS DEC.

- 1. Quarterly inspection of the well noting any unusual conditions.
- 2. The water level indicating device and the bottom foot or more of cable was triple rinsed with distilled water.
- 3. The depth to the water surface from the top of the riser pipe was measured and recorded on the Sample Collection Form. Depth to the bottom of each well was also measured.
- 4. The volume of water in each well is calculated. Each well is purged by removing three times this volume, or if the well yield is low, water is removed until the well is considered "dry" (within 1-2 inches of the bottom).
- 5. A peristaltic pump is used to purge these shallow wells. All tubing coming into contact with the well water consists of food-grade polyethylene tubing dedicated to the well. This dedicated tubing is intended to eliminate cross-contamination between the wells. The tubing was gradually lowered into the well as pumping continued. The volume required, volume obtained, water level before purging, and the start and stop times are to be recorded.
- 6. All purge water is to be placed in a container specifically used for that well and for measuring purge volume. If the well contained very little volume, this water was reserved for pH, specific conductance and turbidity determination. After a time has elapsed for sufficient recovery, sampling was completed. In one instance several days are occasionally necessary to obtain a sufficient volume for phenol compound analysis. Based upon results of the analyses performed over the past decade, the water, contains no parameters which might be incompatible with the treatment process or SGA's sanitary sewage permit, and is acceptable to the NCSD #1 and meets their criteria. The water is then disposed of in the sanitary sewer.
- 7. For the wells which generally recover slowly, the wells are sampled within 24 to 48 hours of purging. Sample size, containers and amount of sample obtained are contained in Table 3. In 2007 for example, it took nine days to recharge to an adequate volume for sampling from one well after checking it daily.
- 8. Groundwater samples are obtained by dedicated tubing. No equipment is to be used for more than one well location.

- 9. Usually, the first sample is taken for analysis of pH, temperature, specific conductance and turbidity. Probes are triple rinsed with distilled water after use. A standard reporting form with all field data is provided for each well and sample location (See Appendix).
- 10. Temperature, specific conductance, turbidity and pH were reported on the form along with the equipment used, weather conditions, field observations, and sampling times.
- 11. Sample container labels are affixed to the sample container and the samples placed in an insulated container where they were kept cool with ice if temperatures were above 4° C.
- 12. In a similar fashion, samples were obtained for phenolic compounds as required for each sample location (EPA 8270). Each sample label was completed including the date, time, location, analysis required, and sampler's initials.
- 13. All samples are packed in an insulated cooler with sufficient ice to maintain a temperature of 4° to 6° C during storage and transport to the laboratory.
- 14. Analyses are to be completed within the specified holding times. The laboratory is notified by the sampling team prior to sampling and upon shipping to assist in scheduling analyses to meet all specified holding times.

SAMPLE CUSTODY

Field sampling data and purging was documented on a Well Monitoring Field Form. The following information was included:

- 1. Site name (Saint Gobain Abrasives, Inc.), sample number, etc;
- 2. Date, time, and elapsed time from purge start to finish;
- 3. Information regarding the well groundwater level, purge volume required, and actual purge volume;
- 4. Field test results including pH, temperature, turbidity and specific conductance;
- 5. Sampling method used; the materials of construction of special equipment (in margin);
- 6. Type of sample and information which appears significant;
- 7. Field observations/sampling conditions (e.g. weather)
- 8. Appearance of sample such as color, sediment, oil on surface, obvious odor, etc.
- 9. Sampler's identity and signature.

In order to maintain integrity of the groundwater samples, strict chain-of-custody procedures are to be followed. From the time the sample was collected until the sample was in the custody of the analytical laboratory, the samples were:

- 1. In the sampler's possession;
- 2. In the sampler's view, after being in his/her possession;
- 3. In the sampler's possession and then locked in a designated, secure area to prevent tampering; or in a sample cooler sealed with a tamper proof chain-of-custody seal.

A written Chain-of-Custody Record of the transfer of samples is maintained with a copy in the Appendix of the Sampling and analytical report.

The Chain-of-Custody Record is transported with the sample container at the time the sample is collected. When transferring the possession of the samples, the person making the transfer signs and records the date and time on the record. The number of custodians in the chain of possession are as few as possible.

SAFETY

Personnel performing the sampling adhered to all safety requirements for contractors and/or visitors of the facility. Personnel performing the sampling wear suitable personal protective equipment.

ANALYTICAL LABORATORIES

The pH, temperature, turbidity and specific conductance are measured in the field by Frontier Technical Associates, Inc., NYELAP # 10475, Katherine A. Wager, Laboratory Director. FTA is a certified NYSDOH-ELAP laboratory. All field analyses for appropriate parameters under the NYELAP program are performed within prescribed holding times (15 minutes for pH for example, in the field.) The phenol compound analyses (EPA 8270) is performed by Columbia Analytical Services, Inc. (now part of ALS), NYELAP # 10145. Each laboratory is certified for the parameters for which data are provided.

FIELD SAMPLING PERSONNEL

All field sampling and field measurements were performed by personnel who are specifically trained in the analytical procedure and who pass demonstrations of capability in accordance with the NYSDOH-ELAP requirements and FTA SOPs implementing the Laboratory Procedures Manual.

RESULTS OF RECENT SAMPLING AND INSPECTIONS

Phenol Compounds

Table 3 is a summary of the analysis for phenol compounds for 2011 (Complete data are contained in Appendix II). EPA Method 8270 was used for analysis of these compounds. There were no detectable concentrations of phenol above minimum detection or quantitation limits in all samples analyzed including the duplicate sample obtained at Well OW4-81. Surrogate recovery data indicated acceptable recoveries of spiked compounds. The data are consistent with the data collected over the last 20 years, and there is no reason to believe with the low detection limits reported here, that phenol compounds are migrating from the landfill. Tables 4 and 5 summarize the 2012 field data collected and analyzed.

Table 3
Results for Phenol Compound (EPA Method 8270) Analysis at Saint Gobain Abrasives Inc.
(July 20, 2011)

Location	Concentration (mg/l) <u>All Phenol Compounds*</u>
OW2-81	ND
OW3-81	ND
OW4-81	ND
OW4-1(Dup)	ND
OW5-81	ND
MH A-9	ND
Method Blank	ND

ND = None of the 14 phenolic compounds detected by this method were present above laboratory quantitation levels for each sample (See Analytical Report).

MS/MSD Recovery: All acceptable

Table 4
Groundwater Elevations at
Saint Gobain Abrasives, Inc.
(July 23, 2012)

Date	Well No.	Top of Pipe Elevation	Depth to Water Surface	Groundwater Elevation
07/23/12	OW2-81	588.50	9.64	578.86
07/23/12	OW3-81	587.59	9.96	577.63
07/23/12	OW4-81	587.74	10.88	576.86
07/23/12	OW5-81	587.52	10.34	577.18

^{*} Groundwater level measurements obtained on July 19, 2011 by Ronald B. Blinston of Frontier Technical Associates, Inc. under the supervision of David M. Harty, PE, BCEE.

The groundwater elevation data presented above were obtained under my supervision and represent, to the best of my knowledge, accurate measurements for the date listed.

David M. Harty

PE, BCEE

Table 5
Field Monitoring Data
at Saint Gobain Abrasives Inc.
(July 23, 2012)

Well No.	pH (SU)	Specific Conductance (umhos/cm)	Turbidity (NTU)
OW2-81	10.92 (10.93)	2795	162
OW3-81	7.45	3660	243
OW4-81	11.50	2153	130
OW5-81	6.38	6105	361
MH A-9	7.09	830	4.10

Notes:

pH, specific conductance and turbidity analyses performed by Ronald B. Blinston immediately upon sampling. Duplicate analysis is in "()".

The recoveries of spiked surrogate compounds in the set of samples analyzed from the site were very similar. Duplicate analysis performed on OW4 indicated consistent results with the separate sample. Laboratory Control Sample (LCS) recoveries were also within QC limits and indicated agreement with surrogate recoveries. The monitoring wells appear to have a dark, biological particulate material. These waters when stored in the laboratory support rapid biological growth. The method blank also had no detectable phenol at MDLs or MRLs.

It should be noted that historically only "phenol" resins were used in the resins and materials disposed in the landfill. The other compounds, particularly chlorinated phenols, were not used and have never been detected.

Quality Assurance/Quality Control

As part of the QA/QC activities associated with the 2011 sampling episode, a field duplicate was obtained at Well OW4-81, surrogate recoveries were reported, and a method blank was analyzed for this batch. A matrix spike and matrix spike duplicate was also performed on Well OW4-81. Analysis for all these samples was by EPA Method 8270. pH, temperature, specific conductance and turbidity were run in quadruplicate and the average value of the measurements was reported. However, there was little to no little variation noted in the data.

Physical Appearance

New concrete pads installed in 1999 at Wells OW2-81 and OW3-81 by Frontier Technical Associates, Inc. has remained intact. The riser for Well OW4-81 was replaced and repaired in 2004 due to a vehicle collision. Some cracking may be present in the well pads but this does not impede their function. Quarterly inspections of the landfill area continue under the supervision of Saint Gobain Abrasives Co. and are conducted by Frontier Technical Associates, Inc. Copies of the quarterly inspection reports have been provided to Mr. Michael Hinton, P.E. and Brian Sadowski of the NYSDEC Region 9.

COMMENTS ON HISTORICAL DATA

Groundwater associated with the Lockport Dolomite is highly mineralized as evidenced by the specific conductance values measured at the wells which indicates the concentration of dissolved solids present. This has been consistent with previous data from this site and data available for wells in the immediate vicinity.

As a result of evaluation of the data recovered, the following is concluded:

- 1. Sampling of the four existing monitoring wells and catch basin in 2011 and quantification of the phenolic compounds again showed no detectable levels of any of the phenol compounds above detectable or quantitation limits.
- 2. Groundwater data indicate no migration of materials from the former landfill. This confirms after 28 years of monitoring that the containment and cap is effective.
- 3. Any future monitoring for phenols should continue to use EPA Method 8270.
- 4. There are no data developed within the past several years that would indicate any need to alter the current monitoring frequency (every two years).
- 5. pH measurements during this episode indicate elevated pH values at Well OW4-81. Repair and replacement of the riser for this well was completed during the Fall of 2004. It is believed that the bentonite-cement grout and water migrating along the casing contributed to the rise in pH at this location.
- 6. Well OW5-81 has the highest value of specific conductance and the presence of black particles has always been noted. There was no change otherwise.

OPERATIONS AND MAINTENANCE PLAN

This operation and maintenance plan was modified from the original plan developed in 1999 and taken from the following document with appropriate timely minor modifications:

"Operations and Maintenance Plan, Landfill Area St. Gobain Abrasives Company, Frontier Technical Associates, Inc. Report ET-99-703-02."

Originally five wells were installed in the landfill area, one in the landfill itself and four on the perimeter of the landfill. In 1991, one well was removed because it was no longer functioning properly and soil shifts between the cap materials and landfill materials themselves had occurred, most likely due to settling. The request was approved and implemented on September 27, 1991. The phenolics analytical methodology was changed from the 4AAP method to EPA Method 8270 to develop more specific and accurate data.

Site Inspection

The physical attributes of the site will be inspected annually This inspection may be conducted by Saint Gobain Abrasives personnel or Frontier Technical Associates, Inc. personnel. The inspections will be conducted in July.

For each monitoring point, the following items will be included: well locks, well casings, covers, concrete pads, bailers and ropes (if any), general conditions and tubing. If any of these items are missing, deteriorated or in disrepair, they will be replaced as or repaired as appropriate. This action will be undertaken immediately or prior to the next quarterly inspection as appropriate. A written inspection report (usually a form) will be prepared and completed and maintained on file at Saint Gobain Abrasives, Inc.

A monitoring point assessment form to be used for the annual inspection is attached in the Appendix. A copy of the completed forms will be forwarded to the NYSDEC Project Manager.

Physical Conditions and Grass Cutting

During the annual inspection, observations of the landfill cap will be made to assess whether any soil slumping is present, rodent burrows present, growth of any large rooted vegetation, etc. Brush and bushes will be trimmed and the area will be kept free of debris or trash which might blow onto the site.

Grass cutting will be performed as needed, however it is expected that it will be cut at least once annually after August 15th as a habitat objective.

Annual Inspection

Once each year, the wells will be purged and depths checked. If depth data indicates infilling of sand or sediment to a depth of 25% of the screen length, the wells will be developed in order to remove the sediment. Sampling and purging will be conducted in accordance with the following schedule:

1999	Purging, Sampling	2007	Purging, Sampling
2000	Purging	2008	Purging
2001	Purging, Sampling	2009	Purging, Sampling
2002	Purging	2010	Purging
2003	Purging, Sampling	2011	Purging, Sampling
2004	Purging	2012	Purging
2005	Purging, Sampling	2013	Purging, Sampling
2006	Purging	2014	Purging

During even years, field measurements are taken after completion of purging during the annual inspection. However, biannual sampling for phenols occurs only in odd years.

The annual inspection (even years) will include the following in addition to purging:

- 1. Analysis of well samples for field parameters, pH, turbidity, specific conductance and temperature.
- 2. The depth/elevation to the water surface. The total depth of each well will be checked against previous measurements. If infilling is noted, well development will be scheduled.
- 3. Each well will be purged to remove suspended sediment and biological growth, if present.
- 4. A peristaltic pump or bailer may be used to purge these shallow wells. All tubing or bailers are dedicated to ensure that no cross-contamination occurs.
- 5. In years ending with odd numbers, sampling will be conducted in accordance with the sampling and analytical plan and schedule above.

Safety

Personnel performing the sampling will adhere to all safety requirements for contractors and visitors to the SGC facility. In addition, since two of the wells are within the security fence erected by the NFTA and the USAF, appropriate arrangements with the NFTA Police and an escort is required to inspect and conduct operations at those well locations. Personnel performing the sampling or purging will wear suitable field boots, and protective gloves and safety glasses or goggles.

EVALUATION OF REMEDY PERFORMANCE, EFFECTIVENESS, AND PROTECTIVENESS

As can be seen from the information presented above and elsewhere in this document, the landfill cap is functioning as intended, the lacustrine clay surrounding the fill has prevented any escape of phenols and phenol-containing resins, and the polymerization of these materials, appears to have taken place. There has been no detection of phenol containing materials or alteration of the groundwater quality though out the last twelve year monitoring period (1999-2011). Therefore, no change in the current status of the landfill or the monitoring plan is appropriate.

IC/EC PLAN COMPLIANCE REPORT

The clay cap, periodic inspections and biannual sampling of the monitoring wells and catch basin have been proven effective in prevention of seepage of leachate from the landfill. In addition the site appears to be relatively dry from a groundwater standpoint. Recharge of three of the wells is generally slow. The site monitoring plan is appropriate for the type of site and little maintenance appears to be warranted provided inspections are conducted on a regularly scheduled basis.

The plans were updated in November 2012 per the NYS DEC.

OVERALL PRR CONCLUSIONS AND RECOMMENDATIONS

- 1. Site analytical plan is adequate for the site and the monitoring frequency is appropriate. No detection of phenol-containing groundwater has occurred in the last ten years.
- 2. Biannual sampling, annual well development and field sample analysis, including annual inspection provides an adequate level of protection for the facility and remedy.

- 3. The O & M plan, in conjunction with the quarterly inspections, have been adequate to detect any changes in the landfill cap or site conditions. Inspections have been reduced to annually beginning in 2013.
- 4. The changes in this facility have been minimal during the past thirty years, there is no reason to believe that this may change. At some point in the future, monitoring wells may have to be replaced, but at this point they are functioning properly and in good repair. Annual inspections will be sufficient to detect any needed repair needed.

APPENDIX

2012 Quarterly Reports

Sampling and Analytical Plan

Operations and Maintenance Plan

2011 Analytical Data Laboratory Report

Quarterly Inspection Reports Saint Gobain Abrasives, Inc. Site No. 932007

(Conducted January 24, 2012)

January 31, 2012

Prepared For:

Mr. Doug Wright
Saint Gobain Grains & Powders, Inc.
P.O. Box 301
Niagara Falls, NY 14304

and

Mr. Brian Sadowski/Mr. Michael Hinton NYS DEC 270 Michigan Ave. Buffalo, NY 14203

Prepared By:

Frontier Technical Associates, Inc. 9120 Main Street Clarence, NY 14031

The measurements and observations reported herein were obtained in accordance with professional standards. Any field laboratory results reported were obtained in compliance with the professional standards of the NYELAP and National Environmental Lab Accreditation Program. The results were prepared for management use and, with the exception of regulatory compliance reporting, are not intended for any other purpose.

Introduction

Attached are the quarterly inspection reports for the Saint Gobain Abrasives, Inc. landfill located at 6600 Walmore Road, Niagara Falls, NY 14304 (Site 932007; formerly Carborundum Abrasives Co.) This inactive landfill is inspected quarterly and annually (see comment on biannual sampling below). During the annual inspections, the wells are purged, samples are analyzed for pH, Temperature, and Specific Conductance and water elevation. The last annual inspection was conducted in 2011. During July 2011, a Bi-Annual sampling, testing and inspection was completed. During that inspection and sampling event, analysis of phenol concentrations by EPA Method 8270 was also completed. During July 2013, the biannual inspection and well sampling is expected to be repeated in accordance with the Site Analytical Plan.

Quarterly Reports

There is one quarterly event documented in the attachments to this report. This quarterly inspection occurred on January 24, 2012.

Annual Report

For 2011, we completed the annual inspection requirements along with the inspection biannual and sampling for 2011.

Bi-Annual Sampling Event

Every two years (odd), all wells at the landfill are also sampled for the presence of phenol compounds by EPA Method 8270. Although only "phenol" has been detected in the past since 1980, this method can detect other phenolic compounds as well. This last event last took place in 2011 in compliance with the SGA Approved Sampling and Analytical Plan and was reported separately. The next Bi-Annual sampling is expected to occur in July 2013.

Results

Review of all data and inspection reports indicates that the landfill characteristics and monitoring wells did not exhibit any changes over the monitoring period. In addition, visual observation of the site indicates that the grounds have been maintained since the last inspection and no damage to the wells is apparent except for OW-3 where the protective casing is crooked and the concrete pad is wobbly. Damage occurred to Well OW-4 in 2004 and the well riser was reinstalled properly. We have encountered elevated pH at this well in the past due to the use and leakage of grout at that location. Additional purging is conducted from time to time during quarterly inspections in an attempt to alleviate that condition.

Appendix

Quarterly Inspection Reports



Page \underline{I} of $\underline{\underline{4}}$

Monitoring Point: 0W-Z			Date: 1/24/12	
Inspector's Name (Print): んん	Bunss	0.0		
Well Locked:	Yes	No	NA	
Lock Functioning:	Yes	No	NA ·	
Bailer and Rope OK:	Yes	No	(NA)	
Tubing OK:	Yes	No	NA NA	
Protective Casing OK:	Yes	No	NA	
Concrete Pad in Good Condition:	Yes	No	NA	
Heaving of Well or Casing:	Yes	(No)	NA	
Well Sand in Purge Water:	Yes	No	(NA)	
Well Constricted:	Yes	(No)	NA NA	
Debris in Well:	Yes	No	NA	
Insects in Well:	Yes	No	NA	
Other Observations or Details on Cor	ditions Abov	e:		
Inspector's Signature:	-e-	32		



Page <u>2</u> of <u>4</u>

Monitoring Point: OW-3			Date: 1/24/12
Inspector's Name (Print):	BLINSTO	٨	
Well Locked:	Yes	No	NA
Lock Functioning:	Yes	No	NA
Bailer and Rope OK:	Yes	No	(NA)
Tubing OK:	Yes	No	NA
Protective Casing OK:	*(Yes)	No	NA
Concrete Pad in Good Condition:	Yes	No	NA
Heaving of Well or Casing:	Yes	No	NA
Well Sand in Purge Water:	Yes	No	(NA)
Well Constricted:	Yes	No	NA
Debris in Well:	Yes	No	NA
Insects in Well:	Yes	No	NA
Other Observations or Details on Col	nditions Abov	re:	
* CASING IS CROOKED			
Inspector's Signature:	-er	RUR	

Monitoring Point: 00-4			Date:	Page <u>3</u> of
Inspector's Name (Print): <u>Ron</u>	BLINST	6N		
Well Locked:	Yes	No	NA	
Lock Functioning:	Yes	No	NA	
Bailer and Rope OK:	Yes	No	(NA)	
Tubing OK:	Yes	No	NA	
Protective Casing OK:	(Yes)	No	NA	
Concrete Pad in Good Condition:	Yes	No	NA	
Heaving of Well or Casing:	Yes	No	NA	
Well Sand in Purge Water:	Yes	No	(NA)	
Well Constricted:	Yes	No	NA NA	
Debris in Well:	Yes	No	NA	
Insects in Well:	Yes	No	NA	
Other Observations or Details on C	onditions Abovo	e:		
				,

Inspector's Signature:



Page 4 of 4

Monitoring Point: 0W-5			Date: _ / /	24/12
Inspector's Name (Print):RoN	BUN	STON		
Well Locked:	(Yes)	No	NA	
Lock Functioning:	Ves	No	NA	
Bailer and Rope OK:	Yes	No	(NA)	
Tubing OK:	Yes	No	NA	
Protective Casing OK:	(Yes)	No	NA	
Concrete Pad in Good Condition:	Yes	No	NA	
Heaving of Well or Casing:	Yes	(No)	NA	
Well Sand in Purge Water:	Yes	No	(NA)	
Well Constricted:	Yes	(Ng)	NA NA	
Debris in Well:	Yes	1 60	NA	
Insects in Well:	Yes	(NG)	NA ·	
Other Observations or Details on Cor	aditions Abov	re:		
Inspector's Signature:	~ 1	EX.		

May 1, 2012 ET-703

Mr. Doug Wright Saint Gobain Abrasives Co. P.O. Box 301 Niagara Falls, NY 14304

Re: Inspection of Site 932007

Dear Mr. Wright:

In accordance with SGA requirements, we have completed the Second Quarter inspection of the monitoring wells located at the former landfill (Site 932007) in the southwest portion of the facility on the following date: April 24, 2012. This inspection was completed in fulfillment of NYSDEC requirements and the SGA Sampling and Analytical Plan and the requirements of SGA P.O. 4700003698.

The April 24, 2012 inspection was a quarterly inspection. Well OW-2 and OW-3 are accessible only through the NFTA-NFIA security escort because of the installation of a security fence (with no access) in 2004. These two wells were inspected with a security escort and are not accessible any other way. The inspection forms are attached for each well location.

In response to Mr. Michael Hinton's letter of August 22, 2002, we have also noted again that the riser on well OW-3 is not completely vertical. This condition has existed since the late 1980's with no obstruction in the well. The riser on OW-4 was replaced in late 2004 due to a vehicle accident. No obstructions or problems were encountered during our inspection. As of this inspection, all well casings were intact, and except for the riser for OW-3 being slightly out of vertical, everything appeared to be normal. The concrete pads for Well OW-2 & 3 showed some slight heaving as noted in the past.

Copies of the inspection reports should be maintained in a separate inspection file for review of the NYDEC project monitor. One copy of this letter (and attachments) has been transmitted on your behalf to Mr. Brian Sadowski and Mr. Michael Hinton, NYSDEC Region 9, Division of Solid Waste, 270 Michigan Ave, Buffalo, NY 14203.

Sincerely,

Kathy Wager

Vice President

Kathwagg

KAW: 12-197

cc w/attach: Ms. Sue Bartlett (SGA-Watervliet)

Quarterly Inspection Reports Saint Gobain Abrasives, Inc. Site No. 932007

(Conducted April 24, 2012)

May 1, 2012

Prepared For:

Mr. Doug Wright
Saint Gobain Grains & Powders, Inc.
P.O. Box 301
Niagara Falls, NY 14304

and

Mr. Brian Sadowski/Mr. Michael Hinton NYS DEC 270 Michigan Ave. Buffalo, NY 14203

Prepared By:

Frontier Technical Associates, Inc. 8675 Main Street Williamsville, NY 14221

The measurements and observations reported herein were obtained in accordance with professional standards. Any field laboratory results reported were obtained in compliance with the professional standards of the NYELAP and National Environmental Lab Accreditation Program. The results were prepared for management use and, with the exception of regulatory compliance reporting, are not intended for any other purpose.

Introduction

Attached are the quarterly inspection reports for the Saint Gobain Abrasives, Inc. landfill located at 6600 Walmore Road, Niagara Falls, NY 14304 (Site 932007; formerly Carborundum Abrasives Co.) This inactive landfill is inspected quarterly and annually (see comment on biannual sampling below). During the annual inspections, the wells are purged, samples are analyzed for pH, Temperature, and Specific Conductance and water elevation. The last annual inspection was conducted in 2011. During July 2011, a Bi-Annual sampling, testing and inspection was completed. During that inspection and sampling event, analysis of phenol concentrations by EPA Method 8270 was also completed. During July 2013, the biannual inspection and well sampling is expected to be repeated in accordance with the Site Analytical Plan.

Quarterly Reports

There is one quarterly event documented in the attachments to this report. This quarterly inspection occurred on April 24, 2012.

Annual Report

For 2011, we completed the annual inspection requirements along with the inspection biannual and sampling for 2011.

Bi-Annual Sampling Event

Every two years (odd), all wells at the landfill are also sampled for the presence of phenol compounds by EPA Method 8270. Although only "phenol" has been detected in the past since 1980, this method can detect other phenolic compounds as well. This last event last took place in 2011 in compliance with the SGA Approved Sampling and Analytical Plan and was reported separately. The next Bi-Annual sampling is expected to occur in July 2013.

Results

Review of all data and inspection reports indicates that the landfill characteristics and monitoring wells did not exhibit any changes over the monitoring period. In addition, visual observation of the site indicates that the grounds have been maintained since the last inspection and no damage to the wells is apparent except for OW-3 where the protective casing is crooked and the concrete pad is wobbly. Damage occurred to Well OW-4 in 2004 and the well riser was reinstalled properly. We have encountered elevated pH at this well in the past due to the use and leakage of grout at that location. Additional purging is conducted from time to time during quarterly inspections in an attempt to alleviate that condition.

Appendix

Quarterly Inspection Reports



Page \underline{I} of $\underline{\underline{4}}$

Monitoring Point: <u>\(\mathcal{O}\mathcal{W}^2\tau\) \(\tau\)</u>			Date: 4/24/12
Inspector's Name (Print): <u></u> たい	BLINSTON		
Well Locked:	Yes	No	NA
Lock Functioning:	Yes	No	NA
Bailer and Rope OK:	Yes	No	NA
Tubing OK:	Yes	No	NA
Protective Casing OK:	Yes	No	NA
Concrete Pad in Good Condition:	(Yes)	No	NA
Heaving of Well or Casing:	Yes	No	NA
Well Sand in Purge Water:	Yes	No	NÃ
Well Constricted:	Yes	(No)	NA
Debris in Well:	Yes	No	NA
Insects in Well:	Yes	No	NA
Other Observations or Details on Co	nditions Above:		
		, 5	
Inspector's Signature:	12		



Page <u>Z</u> of <u>4</u>

nspector's Name (Print): <u> </u>	SLINSTON		
Vell Locked:	Yes	No	NA
Lock Functioning:	Yes	No	NA
Bailer and Rope OK:	Yes	No	NA
Tubing OK:	(Yes)	No	NA
Protective Casing OK:	Yes	No	NA
Concrete Pad in Good Condition:	Yes	No	NA
leaving of Well or Casing:	Yes	(No)	NA
Vell Sand in Purge Water:	Yes	No	(NA')
Well Constricted:	Yes	No	NA
Debris in Well:	Yes	No	NA
nsects in Well:	Yes	No	NA
Other Observations or Details on Co	nditions Above		
X LASING IS CROOKED.			



Page 3 of 4

Monitoring Point: <u>のい・</u> 4			Date: 4/24/12
Inspector's Name (Print): <u>Ro</u> N	BLINSTON	<u> </u>	
Well Locked:	Yes	No	NA
Lock Functioning:	Yes	No	NA
Bailer and Rope OK:	Yes	No	NA
Tubing OK:	Yes	No	NA
Protective Casing OK:	Yes	No	NA
Concrete Pad in Good Condition:	Yes	No	NA
Heaving of Well or Casing:	Yes	(No	NA
Well Sand in Purge Water:	Yes	No	NA
Well Constricted:	Yes	No	NA
Debris in Well:	Yes	No	NA
Insects in Well:	Yes	No	NA
Other Observations or Details on Co	nditions Abov	e:	
Inspector's Signature:		ser	



Page $\frac{4}{9}$ of $\frac{4}{9}$

Monitoring Point: U()			Date: 4/24//2
Inspector's Name (Print):	BLINS	<u>ron</u>	
Well Locked:	Yes	No	NA
Lock Functioning:	Yes	No	NA
Bailer and Rope OK:	Yes	No	NÃ
Tubing OK:	Yes	No	NA
Protective Casing OK:	Yes	No	NA
Concrete Pad in Good Condition:	Yes	No	NA
Heaving of Well or Casing:	Yes	No	NA
Well Sand in Purge Water:	Yes	No	NA
Well Constricted:	Yes	No	NA
Debris in Well:	Yes	No	NA
Insects in Well:	Yes	No	NA
Other Observations or Details on Co	onditions Abov	/e:	
Inspector's Signature:		ser	

July 27, 2012 ET-703

Mr. Doug Wright Saint Gobain Abrasives Co. P.O. Box 301 Niagara Falls, NY 14304

Re: Inspection of Site 932007

Dear Mr. Wright:

In accordance with SGA requirements, we have completed the Third Quarter inspection of the monitoring wells located at the former landfill (Site 932007) in the southwest portion of the facility on the following date: July 23, 2012. This inspection was completed in fulfillment of NYSDEC requirements and the SGA Sampling and Analytical Plan and the requirements of SGA P.O. 4700003698.

The July 23, 2012 inspection was an annual inspection. Well OW-2 and OW-3 are accessible only through the NFTA-NFIA security escort because of the installation of a security fence (with no access) in 2004. These two wells were inspected with a security escort and are not accessible any other way. The inspection forms are attached for each well location.

In response to Mr. Michael Hinton's letter of August 22, 2002, we have also noted again that the riser on well OW-3 is not completely vertical. This condition has existed since the late 1980's with no obstruction in the well. The riser on OW-4 was replaced in late 2004 due to a vehicle accident. No obstructions or problems were encountered during our inspection. As of this inspection, all well casings were intact, and except for the riser for OW-3 being slightly out of vertical, everything appeared to be normal. The concrete pads for Well OW-2 & 3 showed some slight heaving as noted in the past.

Mr. Doug Wright July 27, 2012 Page 2

Copies of the inspection reports should be maintained in a separate inspection file for review of the NYDEC project monitor. One copy of this letter (and attachments) has been transmitted on your behalf to Mr. Brian Sadowski and Mr. Michael Hinton, NYSDEC Region 9, Division of Solid Waste, 270 Michigan Ave, Buffalo, NY 14203 via email at their request.

If you have any questions, please don't hesitate to contact us.

Sincerely,

Kathy Wager Vice President

KAW: 12-336

cc w/attach: Ms. Sue Bartlett (SGA-Watervliet)



Page 1 of 4

Yes Yes	No No	NA NA
		NA
Yes	NI.	
	No	(NA)
Yes	No	NA
Yes	(No)	NA
Yes	No	NA
itions Abov	ve:	
	Yes Yes Yes Yes Yes Yes Yes	Yes No



Page $\frac{2}{4}$ of $\frac{4}{4}$

Monitoring Point: OW-3			Date: 7/23/12
Inspector's Name (Print): _ Kon	BLINSTON		
Well Locked:	Yes	No	NA
Lock Functioning:	Yes	No	NA
Bailer and Rope OK:	Yes	No	(NA)
Tubing OK:	Yes	No	NA
Protective Casing OK:	* Yes	No	NA
Concrete Pad in Good Condition:	* Yes	No	NA
Heaving of Well or Casing:	Yes	No	NA
Well Sand in Purge Water:	Yes	No	NA
Well Constricted:	Yes	No	NA
Debris in Well:	Yes	No	NA
Insects in Well:	Yes	No	NA
Other Observations or Details on C	Conditions Abov	e:	
* CASING 18 CROOKED,	CONCRETE	PAD 15 W	OBBLY AND CHIPPED
Inspector's Signature:	er s		



Page <u>3</u> of <u>4</u>

Monitoring Point: OW-4			Date: 7/23/12	<u> </u>
Inspector's Name (Print): <u>犬の</u> い	BLIN550.	<u>J</u>		
Well Locked:	Yes	No	NA	
Lock Functioning:	Yes	No	NA	
Bailer and Rope OK:	Yes	No	NA	
Tubing OK:	Yes	No	NA	
Protective Casing OK:	Yes	No	NA	
Concrete Pad in Good Condition:	Yes	No	NA	
Heaving of Well or Casing:	Yes	No	NA	
Well Sand in Purge Water:	Yes	No	NA	
Well Constricted:	Yes	No	NA	
Debris in Well:	Yes	No	NA	
Insects in Well:	Yes	No	NA	
Other Observations or Details on Co	onditions Above	:		
			,	
Inspector's Signature:		BE		



Page 4 of 4

Monitoring Point: OW-5			Date: 7/2	3/12
Inspector's Name (Print): <u></u>	BLINSTON	<u>) </u>		
Well Locked:	Yes	No	NA	
Lock Functioning:	Yes	No	NA	
Bailer and Rope OK:	Yes	No	NA	
Tubing OK:	Yes	No	NA	
Protective Casing OK:	Yes	No	NA	
Concrete Pad in Good Condition:	Yes	No	NA	
Heaving of Well or Casing:	Yes	No	NA	
Well Sand in Purge Water:	Yes	No	NA	
Well Constricted:	Yes	No	NA	
Debris in Well:	Yes	No	NA	
Insects in Well:	Yes	No	NA	
Other Observations or Details on Co	onditions Abov	e:		
				<u></u>
Inspector's Signature:	-01	BCR		



FRONTIER TECHNICAL ASSOCIATES, INC. WELL MONITORING FIELD FORM

Site Location: Saint-Go	bain Abrasives Landf	ill	Job No: ET7()3		
Sample Point ID:O	W-2 Cor	nsultant: Frontie	er Technical Associa	ites, Inc.		
PURGE INFORMATION			od: Bailer, Peristaltic I	-		
Depth to Bottom of Well: 18.20 ft. 2" Well = 0.17 gals/ft.						
Depth to Water Surface	e: <u>9.64</u> ft.		-			
Depth of Water Column	n: <u>8,56</u> ft.					
Volume of Standing Wa	ater in Well: <u>/ / </u> gal	llons				
Start of Purge: Date: _7	1231 12 Time: 12:	59				
End of Purge: Date: _7						
Total Volume Purge:	<u>/.5 g</u> allons Well Pi	urged Dry?:Yes) No			
# of Volumes Purged _	•		_			
Recharge Rate: Rapid	, Slow Extremely SI	ow				
SAMPLING INFORMA	TION Sample M	ethod: <u>Bailer, P</u> e	eristaltic Pump Blado	ler Pump		
Sample Date: 7/23/12	Z_Sample Time:/_;	<u>07</u> Depth to W	/ater Surface <u>/4,8Z</u> f	t.		
Sample Appearance: _	TURBID				_	
Samples Preserved: Ye	es No Dissolved Met	tals Field Filtered	d: <u>Yes No</u>			
Sampling Personnel:	RON BLINSTON	<u>) </u>				
FIELD MEASUREMEN						
Meters Calibrated Yes						
ALL FIELD PA	LAMETICAS TAKE	N IN ACCOR	ANCE TO THE G	LOUND WATER	SAMP(IN	
PARAMETER	METER NUMBER	UNITS	MEASUREMENT	NOTES	PLAN	
рН	Hanna HI9023	STD. UNITS	10.92	(10.93)		
Spec. Conductance	Oakton Con6	μ MHOS/CM	2795			
Temperature	Uei 550	°F	58		ļ	
Turbidity	Hach 2100P	NTU	162			
Weather: SUNNY,	89%				_	
Notes: <u>PH 4:10</u>	4.05 7.0	2 10.03	24°c * CHi	ck only	_	
Weather: SUNNY, Notes: PH 9:10 SPICE. COND.	1000 STO REA	DING 1000 W	m Hoslem			

YPICC. COND. 1000 STO READING 1000 WHOS/CM
TURB. MIETIER - A 5.92 STO READING 5.96 NTU.



FRONTIER TECHNICAL ASSOCIATES, INC. WELL MONITORING FIELD FORM

Site Location: Saint-Gobain Abrasives Landfill	Job No: ET- <u>703</u>
Sample Point ID: <u>OW-3</u> Consultant	: Frontier Technical Associates, Inc.
PURGE INFORMATION Pur	ge Method: Bailer, Peristaltic Pump
Depth to Bottom of Well: <u>19.66</u> ft.	2" Well = 0.17 gals/ft.
Depth to Water Surface: <u>9,%</u> ft.	
Depth of Water Column: <u>9,70</u> ft.	
Volume of Standing Water in Well: 1.45 gallons	
Start of Purge: Date: 7/23/12 Time: 1: 31	
End of Purge: Date: <u>7/23/17</u> Time: <u>/ : 4</u>	_
Total Volume Purge: <u> /. 7 g</u> allons Well Purged [)ry?: <u>(Yes) No</u>
# of Volumes Purged/ Purging Personnel:_	RON BLINSTON
Recharge Rate: Rapid, Slow, Extremely Slow	
SAMPLING INFORMATION Sample Method:	Bailer, Peristaltic Pump Bladder Pump
Sample Date: <u>7/23/72</u> Sample Time: <u>/ : ᠳ</u> De	epth to Water Surface DRY ft.
Sample Appearance: <i>TURBID</i>	
Samples Preserved: Yes No Dissolved Metals Fie	d Filtered: <u>Yes No</u>
Sampling Personnel: <u>Kow Blinston</u>	
FIELD MEASUREMENTS	
Meters Calibrated Yes No	

PARAMETER	METER NUMBER	UNITS	MEASUREMENT	NOTES
рН	Hanna HI9023	STD. UNITS	7.45	
Spec. Conductance	Oakton Con6	μ M HOS/CM	3660	
Temperature	Uei 550	۰F	60	
Turbidity	Hach 2100P	NTU	243	

-	
Notes:	_
Neather:	



FRONTIER TECHNICAL ASSOCIATES, INC. WELL MONITORING FIELD FORM

Site Location: Saint-Gobain Abrasives Landfill	Job No: ET- <u>703</u>
Sample Point ID: <u>OW-4</u> Consulta	nt: Frontier Technical Associates, Inc.
PURGE INFORMATION Pu	urge Method: <u>Bailer, Peristaltic Pump</u>
Depth to Bottom of Well: <u>19.38</u> ft.	2" Well = 0.17 gals/ft.
Depth to Water Surface: <u>//) .88</u> ft.	
Depth of Water Column: <u>\$.50</u> ft.	
Volume of Standing Water in Well: 1.5 gallons	
Start of Purge: Date: 7/23/12 Time: 2:12	
End of Purge: Date: 7/23/12 Time: 2:16	-
Total Volume Purge: 1,5 gallons Well Purged	Dry? Yes No
# of Volumes Purged/ Purging Personne	: RON BLINSTON
Recharge Rate: Rapid, Slow, Extremely Slow	
	: Bailer Peristaltic Pump Bladder Pump
Sample Date: 7/23/12 Sample Time: 2:17	
Sample Appearance: SLIGHTLY TURBID	TO TURBID
Samples Preserved: Yes No Dissolved Metals F	ield Filtered: <u>Yeş_No</u>
Sampling Personnel: Row Stimston	
FIELD MEASUREMENTS	
Meters Calibrated Yes No	

PARAMETER	METER NUMBER	UNITS	MEASUREMENT	NOTES
рН	Hanna HI9023	STD. UNITS	11.50	
Spec. Conductance	Oakton Con6	μ MHOS/CM	2153	
Temperature	Uei 550	°F	64	
Turbidity	Hach 2100P	NTU	130	

Neather:			- 1
Notes:			
		Zall	Ret



FRONTIER TECHNICAL ASSOCIATES, INC. WELL MONITORING FIELD FORM

Site Location: Saint-Gobain Abrasives Landfill	Job No: ET- <u>703</u>
Sample Point ID: <u>OW-5</u> Consultar	nt: Frontier Technical Associates, Inc.
PURGE INFORMATION Pu	rge Method: Bailer, Peristaltic Pump
Depth to Bottom of Well: 18.23 ft.	2" Well = 0.17 gals/ft.
Depth to Water Surface: 10.34 ft.	
Depth of Water Column: 7.89 ft.	
Volume of Standing Water in Well: <u>ル</u> gallons	
Start of Purge: Date: 7/23/12 Time: 2:25	
End of Purge: Date: 7/23/12 Time: 2:28	
Total Volume Purge:/ gallons Well Purged	Dry?: Yes No
# of Volumes Purged/ Purging Personnel	RON BUNSTON
Recharge Rate: Rapid, Slow, Extremely Slow	
	Bailer Peristaltic Pump Bladder Pump
Sample Date: 7/23/12 Sample Time: 2:29 D	Pepth to Water Surface <u>DKY</u> ft.
Sample Appearance: TURBID BLA	cK
Samples Preserved: Yes No Dissolved Metals Fig.	eld Filtered: <u>Yes_No</u>
Sampling Personnel: RON BLINSTON	
FIELD MEASUREMENTS	
Meters Calibrated Yes No	

PARAMETER	METER NUMBER	UNITS	MEASUREMENT	NOTES
рН	Hanna HI9023	STD. UNITS	6.38	
Spec. Conductance	Oakton Con6	μ MHOS/CM	6105	
Temperature	Uei 550	°F	blo	
Turbidity	Hach 2100P	NTU	361	

Weather:	
Notes:	
	Fill Bett



Meters Calibrated Yes No

FRONTIER TECHNICAL ASSOCIATES, INC. WELL MONITORING FIELD FORM

Site Location: Saint-Gobain Abrasives Landfill		Job No: ET- 703		
Sample Point ID: <u>MH-9</u>	Consultant: <u>F</u>	rontier Technical Associates, Inc.		
SAMPLING INFORMATION	Sample Metho	od: Bailer Peristaltic Pump Bladder Pump		
Sample Date: 7/23/12 Sample	Time: <u>/2:00</u>	Depth to Water Surface ft.		
Sample Appearance:				
Samples Preserved: Yes No Dissolved Metals Field Filtered: Yes No				
Sampling Personnel:	BLINSTON			
·	.,,			
FIELD MEASUREMENTS				

PARAMETER	METER NUMBER	UNITS	MEASUREMENT	NOTES
pH	Hanna HI9023	STD. UNITS	7.08	
Spec. Conductance	Oakton Con6	μ MHOS/CM	830	
Temperature	Uei 550	°F	78	
Turbidity	Hach 2100P	NTU	4.10	

vveatner:	
Notes:	
	15 25-1

October 29, 2012 ET-703-39

Mr. Brian Sadowski/Mr. Michael Hinton NY Dept. Environmental Conservation Division of Environmental Remediation 270 Michigan Ave. Buffalo, NY 14203

Re: Inspection of Site No. 932007 (4th Qtr-2012)

Dear Mr. Sadowski/Mr. Michael Hinton:

Enclosed is the annual report for inspections conducted at the former St. Gobain Abrasives Landfill, 6600 Walmore Road, Wheatfield, NY. This submission covers the fourth quarter of 2012 in accordance with the SAP and Saint Gobain Abrasives order. The bi-annual phenol sampling was completed in July 2011 in accordance with the approved Site Analytical Plan.

Sincerely,

Kathy Wager Vice Presiden

KAW: 12-479

Enclosures

cc w/encl. Doug Wright, Sue Bartlett

October 29, 2012 ET-703

Mr. Doug Wright Saint Gobain Abrasives Co. P.O. Box 301 Niagara Falls, NY 14304

Re: Inspection of Site 932007

Dear Mr. Wright:

In accordance with SGA requirements, we have completed the Third Quarter inspection of the monitoring wells located at the former landfill (Site 932007) in the southwest portion of the facility on the following date: October 23, 2012. This inspection was completed in fulfillment of NYSDEC requirements and the SGA Sampling and Analytical Plan and the requirements of SGA P.O. 4700003698.

The October 23, 2012 inspection was a quarterly inspection. Well OW-2 and OW-3 are accessible only through the NFTA-NFIA security escort because of the installation of a security fence (with no access) in 2004. These two wells were inspected with a security escort and are not accessible any other way. The inspection forms are attached for each well location.

In response to Mr. Michael Hinton's letter of August 22, 2002, we have also noted again that the riser on well OW-3 is not completely vertical. This condition has existed since the late 1980's with no obstruction in the well. The riser on OW-4 was replaced in late 2004 due to a vehicle accident. No obstructions or problems were encountered during our inspection. As of this inspection, all well casings were intact, and except for the riser for OW-3 being slightly out of vertical, everything appeared to be normal. The concrete pads for Well OW-2 & 3 showed some slight heaving as noted in the past.



Page <u>1</u> of <u>4</u>

Inspector's Name (Print): <u>Lon</u>	BLINSTON			
Well Locked:	Yes	No	NA	
Lock Functioning:	Yes	No	NA	
Bailer and Rope OK:	Yes	No	NA	
Γubing OK:	Yes	No	NA	
Protective Casing OK:	Yes	No	NA	
Concrete Pad in Good Condition:	Yes	No	NA	
leaving of Well or Casing:	Yes	No	NA	
Well Sand in Purge Water:	Yes	No	NA	
Well Constricted:	Yes	No	NA	
Debris in Well:	Yes	No	NA	
nsects in Well:	Yes	No	NA	
Other Observations or Details on Co	nditions Above:			
and the state of t				



Page <u>2</u> of <u>4</u>

Monitoring Point: OW-3			Date: 10/23/12	_
Inspector's Name (Print): <u>Ro</u> N	BLINSTON	J		
Well Locked:	(Yes)	No	NA	
Lock Functioning:	Yes	No	NA	
Bailer and Rope OK:	Yes	No	(NA)	
Tubing OK:	Yes	No	NA	
Protective Casing OK:	* Yes	No	NA	
Concrete Pad in Good Condition:	Yes	No	NA	
Heaving of Well or Casing:	Yes	No	NA	
Well Sand in Purge Water:	Yes	No	(NA)	
Well Constricted:	Yes	No	NA	
Debris in Well:	Yes	(No)	NA	
Insects in Well:	Yes	No	NA	
Other Observations or Details on Co	nditions Abov	e:		
*CASING IS CROOKED.				
Inspector's Signature:		SEL		



Page 3 of 4

Monitoring Point: OW-4			Date: 10/23/12
Inspector's Name (Print):	BLINSTO	J	
Well Locked:	(Yes)	No	NA
Lock Functioning:	Yes	No	NA
Bailer and Rope OK:	Yes	No	NA
Tubing OK:	Yes	No	NA
Protective Casing OK:	Yes	No	NA
Concrete Pad in Good Condition:	Yes	No	NA
Heaving of Well or Casing:	Yes	No	NA
Well Sand in Purge Water:	Yes	No	NA
Well Constricted:	Yes	No	NA
Debris in Well:	Yes	No	NA
Insects in Well:	Yes	No	NA
Other Observations or Details on Co	nditions Abov	e:	
	,		
Inspector's Signature:	Be		



Page <u>4</u> of <u>4</u>

Monitoring Point: OW-5			Date: <u>/0/2</u>	3/12
Inspector's Name (Print): Ron	BLINSTO	<u>ال</u>		
Well Locked:	(Yes)	No	NA	
Lock Functioning:	Yes	No	NA	
Bailer and Rope OK:	Yes	No	(NA)	
Tubing OK:	(Yes)	No	NA	
Protective Casing OK:	Yes	No	NA	
Concrete Pad in Good Condition:	Yes	No	NA	
Heaving of Well or Casing:	Yes	No	NA	
Well Sand in Purge Water:	Yes	No	(NA)	
Well Constricted:	Yes	(No)	NA	
Debris in Well:	Yes	No	NA	
Insects in Well:	Yes	No	NA	
Other Observations or Details on Co	nditions Abov	e:		
Inspector's Signature:	e B	RI.		_

GROUNDWATER SAMPLING & ANALYSIS PLAN

LANDFILL AREA

St. Gobain Abrasives, Inc.

NYSDEC Site 932007

FTA Report ET-703-GWP2

November 19, 2012

Prepared For:

Mr. Douglas Wright St. Gobain Abrasives, Inc. 6600 Walmore Road P.O. Box 301 Niagara Falls, NY 14304

Prepared By:

Frontier Technical Associates, Inc. 8675 Main Street
Williamsville, NY 14221

The sample and analysis plan provided herein was developed for St. Gobain Abrasives Company management use only and, except for required regulatory compliance submission, is not intended for any other purpose.

Table of Contents

	Page
Introduction	2
Chronology	2
Geology and Hydrogeology	4
Sampling and Analytical Methods	4
Sampling Objectives	4
Sampling Locations	4
Sample Designation	5
Sampling Equipment and Procedures	6
Sample Custody	8
Operations and Maintenance	9
Safety	9
Analytical Laboratories	9
Field Sampling Personnel	9
Reporting	9
Appendix	11

Introduction

In response to the requirements of NYSDEC Region 9, St. Gobain Abrasives Inc. has been requested to supply this revised groundwater sampling and analysis plan for the landfill area located on the southwest corner of the property in Wheatfield, New York. Figure 1 is a sketch of the landfill area showing the location of the monitoring wells which were installed in 1981 and the location of the "A" storm sewer line (West Branch), Frontier Technical Associates, Inc. has prepared this plan for St. Gobain's submission to the NYSDEC. This revised plan is amended from the plan submitted and approved in 1999.

Previously, technical reports were prepared which described the results of the priority pollutant sampling and analysis in 1990 and 1991. This included sample splits and full QA/QC. As a result of the findings, the NYSDEC subsequently reduced monitoring parameters for 1992. For 1993, the NYDEC deleted the requirement for analysis of filtered and unfiltered groundwater samples for metals including zinc. In 1994, all metals requirements were deleted and turbidity was added for informational purposes. This report presents the current requirements for monitoring at the landfill and discusses maintenance activities which have been performed in connection with the wells since 1994. In addition, a new section on Operations and Maintenance of the monitoring wells has been added.

Chronology


Since 1982, the monitoring wells and adjacent catch basins were sampled for pH and total phenolics (4AAP). In the period 1982-1988 there were no detectable levels of phenolics (4AAP) in monitoring wells OW2-81 through OW5-81. However, in 1989, perhaps as the result of unusual spring and summer precipitation events, low levels of phenolics were detected in the monitoring wells and adjacent catch basins. Again in 1990, low levels of total phenolics were detected. This resulted in the NYSDEC's desire to obtain additional data for evaluation beginning in 1991 as discussed above. Based upon the 1991 results, Carborundum Abrasives requested the decommissioning of one well (OW1-81) which had fallen into disrepair and was no longer functioning. The request was approved and subsequently implemented on September 27, 1991. The phenolics analytical methodology was also changed to the more accurate and specific SW846 Method 8270 and approved by the NYSDEC.

On May 20, 1994, new locking caps were installed on Well OW2-81 and OW4-81 by Frontier Technical Associates, Inc. New concrete pads were also installed by FTA around Well OW2-81 and OW3-81 on June 26, 1997.

As the result of review of the well depths presented in the 1997 sampling report, Frontier Technical Associates, Inc. undertook the redevelopment of all four wells in the monitoring network. On October 16 and 22, 1998, each well was purged and flushed two times on each day. A well development report dated January 28, 1999 was prepared and forwarded to the NYSDEC (Mr. Michael Hinton) for review. As a result of the review, this revised and updated Sampling and Analysis Plan (SAP) has been prepared. This report outlines the approach used to fulfill the NYSDEC requirements f or updating and revising the SAP to reflect current practice and requested and approved changes to the previous plans.



Figure 1 SCG Landfill Locations



To the same of the

Legend

Streets and Highways

- -- Interstate
- Primary State Road
- Secondary State Road
- County Road
- Local Road

☐ Parcels

1Ft Color Aerials

- Red: Band_1
- ₩ Green: Band_2
- Blue. Band_3

 2Ft Color Aerials
- Red: Band 1
- Green: Band_2
- Blue: Band_3

1: 1,414



Notes

Enter Map Description

Niagara County and its officials and employees assume no responsibility or legal liability for the accuracy, completeness, reliability, smeliness, or usefulness of any information provided. Tax parcel data was prepared for tax purposes only and is not to be reproduced or used for surveying or conveyancing.

NIAGARA COUNTY, NEW YORK DEPARTMENT OF REAL PROPERTY SERVICES

Geology and Hydrogeology

The area in the immediate vicinity of the St. Gobain plant is underlain by approximately 10 to 15 feet of clayey to sandy silt, glacial-lacustrine deposits and till. These deposits thicken southward across the site toward the Niagara River. The hydraulic conductivity of these materials is relatively low perhaps reaching the range of 1×10^{-8} to 1×10^{-8} cm/sec.

The bedrock underlying the site consists of approximately 160 feet of dolomite of the Lockport Formation. The upper zone of the Lockport Formation is generally highly weathered, medium-gray dolomite with extensive vertical fractures. The dolomite has partings which are argillaceous or gypsum-coated. Water produced from this upper zone in the Bergholtz area of Wheatfield is generally of very poor quality, with a characteristic odor. The water generally is not suitable for drinking but is used for watering livestock or agricultural purposes. The Town of Wheatfield has extended its water lines throughout the area and recent information indicates that there are few wells in use throughout the area. On the adjacent property formerly operated by Textron Defense Systems, groundwater remediation is being conducted. The bottom of the St. Gobain landfill is up dip in the Lockport Dolomite. This appears to have had little effect on the St. Gobain landfill site as evidenced by historical groundwater elevation data.

The upper portion of the dolomite sequence consists of 10 to 20 feet of bedrock consisting of thinly bedded dolomite which may produce well yields of 10 to 20 gpm. Hydraulic conductivities of 0.1 to 0.01 cm/sec may be encountered in this unit. For purposes of this current plan, it is not thought that any of the wells penetrate significantly into the bedrock and were either drilled to refusal or into the uppermost few feet of the weathered bedrock. The bedrock surface is generally encountered at elevations between 560 feet to 570 feet MSL and gently dips to the south. The wells monitored in this project were drilled to refusal as indicated in a report by Conestoga-Rovers Associates, who installed the wells in 1981 after placement of a clay cap by Secured Landfill Contractors, Inc.

Sampling and Analytical Methods

Sampling Objectives

The results of samples collected and analyzed in accordance with the approval of the NYDEC are to be used to:

- 1. Assess the groundwater flow direction and chemistry.
- 2. Define the nature and extent of pollutant migration, if any.
- 3. Meet the NYDEC requirements for data submission.

Sampling Locations

Figure 1 illustrates the sample locations. Four wells are to be sampled together with one catch basin (A-9). Table 1 presents the sample locations and the analytical parameters for each location. All methods used conformed to the Standard Methods for Examination of Water/Wastewater, EPA Methods of Analysis for Water and Wastewater (40 CFR 136) or SW-846. Table 2 is a summary of the parameters, methods used, preservation methods, and holding times required for this site.

Sample Designation

All samples obtained at the St. Gobain site shall have sample numbers which are unique to the well or sampling location. For example, the numbering scheme below will be used:

OW-2	OW-5
OW-3	MH A-9
ΩW_{-4}	

Any trip blanks, field blanks, equipment blanks, matrix spikes, and matrix spike duplicates shall have identifying sample numbers which are unique. Any and all split samples made available for NYSDEC duplicate analysis will be marked and labeled as above.

Table 1 Sample Locations and Well Depths

Well Depth (feet)*
18.20
19.66
19.38
18.23

^{*} Based upon measurement by FTA in 1998 after well development; measured from top of riser pipe.

All samples are analyzed biannually for pH, specific conductivity, temperature, turbidity and phenol by Method 8270

^{**} Field measurement of pH made within NYELAP guidelines (15 min). Turbidity measured using a nephelometer in the field.

Table 2 Summary of Parameters, Methods, Preservation Methods and Holding Times

Analysis	Method	Preservation Method/ Sample Container	Holding Time*
рН	SM4500 HB	None/plastic or glass	Analyze immediately in the field
Specific Conductivity	EPA 120.1	None/plastic or glass	Analyze immediately in the field
Temperature	SM2550B	None/plastic or glass	Analyze immediately in the field
Turbidity	EPA 180.1	None/plastic or glass	Analyze immediately in the field
Phenol	SW846 8270	4°C; glass	7 days to extraction; 40 days for analysis

^{*} pH, specific conductivity, temperature, turbidity measured in the field. Frontier Technical Associates is a NYELAP-Certified Laboratory (10475).

Sampling Equipment and Procedures

The procedures outlined here were developed to minimize contamination of water sampling, minimize concentration change prior to testing, and standardize procedures to minimize analytical differences.

The following procedures outline the purging, sampling, and preservation methods used during this sampling program in accordance with the approved sampling plan submitted in 1991 and used to the present time:

- 1. Inspection of the well noting any unusual conditions.
- 2. The electronic water level meter probe will be triple rinsed with distilled water.
- 3. The depth to the water surface from the top of the riser pipe will be measured and recorded on the Well Monitoring Field Form. The total depth of each well is to be checked against previous measurements made by the sample team since the 1998 well redevelopment.
- 4. Calculate the volume of water in each well. Purge each well by removing three times the volume, or if the well yield is low, remove water until the well is "dry." (within 1-2 inches of bottom).

- 5. A low-flow peristaltic pump will be used to purge these shallow wells. All tubing coming into contact with the well water shall consist of food-grade polyethylene tubing dedicated to the well or catch basin. This dedicated tubing is stored in its respective well. The dedicated tubing is necessary to prevent cross-contamination between the wells. The tubing will be gradually lowered to the bottom of the well. The volume required, the volume purged, water level before purging, and the start and stop times will also be recorded on the Well Monitoring Field Form.
- 6. All purge water will be placed in a container specifically used for that purpose and for measuring purge volume. Based upon the results of the analyses previously conducted, the water contains no pollutants incompatible with the treatment process or St. Gobain's sanitary sewage permit, and has been acceptable to the NCSD and meets their criteria. The water will be disposed of in the sanitary sewer.
- 7. Because most of the wells recover slowly, the wells will be sampled within 24 hours of purging. Sample size, containers, and amount of sample obtained are listed in Table 3. If any delays are encountered, proper documentation must be provided.
- 8. Groundwater samples will be obtained by dedicated tubing. No equipment will be used for more than one well.
- 9. Usually, the first sample is taken for analysis of pH, specific conductance, temperature and turbidity. All field analysis equipment is triple rinsed with distilled water prior to and after use.
- 10. Temperature, specific conductance, turbidity and pH are reported on the Well Monitoring Field Form along with equipment used, weather conditions, field observations, and sampling times.
- 11. Sample container labels will be affixed to the sample container and the samples placed in an insulated container where they will be kept cool with ice.
- 12. In a similar fashion, samples will be obtained for phenolic compounds as required for each sample location. Each sample label will be completed including the date, time, location, analysis required, and sampler's initials.
- 13. All samples are to be packed in an insulated cooler with sufficient ice to ensure a temperature of 4°C during storage and transport to the laboratory.
- 14. If analyzed locally, all samples will be transported to the laboratory on the same day acquired. If a laboratory outside of the immediate area is chosen, the samples will be shipped by overnight service.
- 15. Analyses will be completed within the specified holding times (see above). The laboratory will be notified by the sampling team prior to sampling and upon shipping to assist in scheduling analyses to meet all specified holding times.

Table 3 Sample Containers and Required Sample Volume

Analysis	Container	Sample Volume
pH, Specific Conductance, Temperature	Plastic or glass	500 ml
Turbidity*	Glass vial	25 ml
Phenol	Glass	1000 ml

Well Monitoring Field Form will be used to record the following data/information:

- 1. Site name (St. Gobain), sample number, etc.
- 2. Date, time, and elapsed time from sample start to sample finish (if applicable);
- 3. Information regarding purging the well prior to sampling including initial groundwater level, purge volume required, and actual purge volume;
- 4. Field test results including pH, temperature, turbidity and specific conductance;
- 5. Sampling method used; the construction material of equipment;
- 6. Type of sample and information which appeared significant;
- 7. Field observations/sampling conditions (e.g., weather);
- 8. Appearance of sample, such as color, sediment, oil on surface, obvious odor, etc.;
- 9. Sampler's identity and signature.

Sample Custody

In order to maintain integrity of the groundwater samples, strict chain-of-custody procedures will be followed. From the time the sample is collected until the sample is in the custody of the analytical laboratory, the samples are required to be:

- 1. In the sampler's possession;
- 2. In the sampler's view, after being in his possession;
- 3. In the sampler's possession and then locked in a designated, secure area to prevent tampering; or
- 4. In a sample cooler sealed with a tamper-proof chain-of--custody seal.

A written Chain-of-Custody Record of the transfer of samples must be maintained. An example can be found in the Appendix of this report.

When transferring the possession of samples, the person making the transfer signs and records the date and time on the record. The number of custodians in the chain of possession should be as few as possible.

Landfill Operations and Maintenance

A landfill area operations and maintenance plan has been developed to address the requirements to inspect and maintain the landfill area proper as well as the monitoring wells. In connection with this plan, an inspection schedule, grass cutting requirements, and required items to be performed have been outlined in detail. A copy of the site O & M Plan is included as an Appendix to this SAP.

Safety

Personnel performing the sampling must adhere to all safety requirements for contractors and/or visitors to the St. Gobain facility. Personnel performing the sampling must wear suitable field boots and protective gloves and goggles or safety glasses. Since no detectable levels of priority or hazardous pollutants have been present in the past, additional safety clothing may be used but is not required.

Analytical Laboratories

The pH, temperature, turbidity and specific conductance are to be measured in the field by Frontier Technical Associates, NYELAP #10475. All other analyses must be performed by a NYELAP-certified laboratory. Each laboratory must be certified for the parameters for which data are provided. No other laboratory may perform any analyses related to the effort reported here without demonstrating that they have and maintain the required NYELAP certification for the required parameters.

Field Sampling Personnel

All field sampling and field measurements must be performed by qualified personnel. Personnel performing the work must be identified in the sampling report, and if requested, must present their certifications, licenses and/or professional qualifications for inspection by the St. Gobain Environmental Engineer.

Samples must be in the custody of the above personnel at all times or be sealed in a container with a tamper-proof seal attached. A summary of weather conditions during the sampling period must be recorded on field sampling forms.

Reporting

Daily field sampling reporting forms including all sample collection forms, inspection reports, purging data, weather conditions and chain-of-custody forms shall be maintained. Within approximately 15 business days of receipt of laboratory data, three copies of the sampling and analytical report shall be delivered to the St. Gobain Environmental Engineer. In turn, after review and approval, St. Gobain will transmit one copy to the NYSDEC Project Monitor (Mr.

Brian Sadowski and Mr. Michael Hinton). In the event of discovery of a significant concentration of phenol in the wells, a determination will be made as to the cause or source and a decision to resample only those wells, if necessary, will be made to reconfirm the analysis. This will be done in consultation with the St. Gobain and NYSDEC, as appropriate.

As a minimum, the following data shall be provided in any sampling report provided in accordance with this SAP:

- 1. Groundwater Elevations; these data shall be certified by a Professional Engineer.
- 2. Piezometric Surface Map of groundwater elevations and inferred groundwater flow direction.
- 3. A summary of pH, Turbidity, and Specific Conductance sampling and analytical results.
- 4. pH, Turbidity, Specific Conductance and Phenol concentration of water sampled from MH A-9 if there is any flow present (A-9 is frequently dry unless rainfall or snowmelt is occurring).
- 5. A summary of the phenol analytical results (8270) including all QA/QC data.
- 6. A discussion of the findings including any quality assurance/quality control data.
- 7. Results of the field duplicate and surrogate recovery, method blank and matrix spike and matrix spike duplicate, if analyzed, must be presented.
- 8. Conclusions and Recommendations for future action including any O & M required.
- 9. Appendix to include field data and notes, groundwater elevations, observations, well inspection reports, laboratory report(s), and chain-of-custody forms.

APPENDIX

- I. Well Monitoring Field Form
- II. Sample Well Inspection Report Form
- III. Operations and Maintenance Plan
- IV. Chain-of-Custody Form

APPENDIX

- I. Well Monitoring Field Form
- II. Sample Well Inspection Report Form
- III. Operations and Maintenance Plan
- IV. Chain-of-Custody Form



FRONTIER TECHNICAL ASSOCIATES, INC. WELL MONITORING FIELD FORM

Site Location: Saint-Gobain Abrasives Landfill Job No: ET- 703						
Sample Point ID:	Sample Point ID: Consultant: Frontier Technical Associates, Inc.					
PURGE INFORMATIO			od: <u>Bailer, Peristaltic F</u>			
Depth to Bottom of Well:ft. 2" Well = 0.17 gals/ft.						
Depth to Water Surface	e:ft.					
Depth of Water Column:ft.						
Volume of Standing Wa	ater in Well: ga	llons				
Start of Purge: Date:	<u>/ /</u> Time::_					
End of Purge: Date:	/ / Time::					
Total Volume Purge:	gallons Well Pu	irged Dry?: Yes	No			
# of Volumes PurgedPurging Personnel:						
Recharge Rate: Rapid, Slow, Extremely Slow						
SAMPLING INFORMATION Sample Method: <u>Bailer, Peristaltic Pump, Bladder Pump</u>						
Sample Date:/ _/ Sample Time:: Depth to Water Surface ft.						
Sample Appearance:						
Samples Preserved: Yes No						
Sampling Personnel:						
FIELD MEASUREMENTS						
Meters Calibrated Yes	No					
PARAMETER	METER NUMBER	UNITS	MEASUREMENT	NOTES		
рН	Hanna HI9023	STD. UNITS				
Spec. Conductance	Oakton Con6	μ MHOS/CM				
Temperature	Oakton Con6	С				
Turbidity	Hach 2100P	NTU				
Weather:						



Monitoring Point Assessment Form at Saint-Gobain Abrasives Landfill

				Page of
Monitoring Point:			Date:	
Inspector's Name (Print):				
Well Locked:	Yes	No	NA	
Lock Functioning:	Yes	No	NA	
Bailer and Rope OK:	Yes	No	NA	
Tubing OK:	Yes	No	NA	
Protective Casing OK:	Yes	No	NA	
Concrete Pad in Good Condition:	Yes	No	NA	
Heaving of Well or Casing:	Yes	No	NA	
Well Sand in Purge Water:	Yes	No	NA	
Well Constricted:	Yes	No	NA	
Debris in Well:	Yes	No	NA	
Insects in Well:	Yes	No	NA	
Other Observations or Details on Cor	iditions Abov	e:		
			····	

Inspector's Signature:



OPERATIONS AND MAINTENANCE PLAN

LANDFILL AREA

ST. GOBAIN ABRASIVES INC.

(Addendum to Sampling and Analytical Plan)

Report ET-703-02

November 19, 2012

Prepared for:

Mr. Douglas Wright St. Gobain Abrasives Inc. 6600 Walmore Road P.O. Box 301 Niagara Falls, NY 14304

Prepared by:

Frontier Technical Associates, Inc. 8675 Main Street
Williamsville, NY 14221

The O & M Plan contained herein is intended for the use of St. Gobain Abrasives Inc. for evaluation and implementation purposes and submission to regulatory authorities as required. The contents may not he released to other parties without the written permission of St. Gobain Abrasives Inc.

INTRODUCTION

In response to the requirements of NYSDEC Region 9, St. Gobain Abrasives Inc. has been monitoring groundwater and performing sampling and analysis for the landfill area located on the southwest corner of the property in Wheatfield, New York since 1981. Figure 1 is a map of the landfill area showing the location of the monitoring wells which were installed in 1981 and the location of the "A" storm sewer line (West Branch). Frontier Technical Associates, Inc. has been performing monitoring and inspection on behalf of St. Gobain Abrasives Inc. and has prepared this supplemental report for St. Gobain's submission to the NYSDEC. Previously, technical reports were prepared which described the results of the sampling and analysis for each year and a formal monitoring or sampling and analytical plan has been on file since 1991. The NYSDEC subsequently reduced monitoring parameters for 1992. For 1993, the NYSDEC deleted the requirement for analysis of unfiltered groundwater samples for metals, and for 1994, all metals requirements were deleted and turbidity was added for informational purposes. In 1998, the NYSDEC approved a modification of the monitoring frequency to once every two years.

Originally, five wells were installed in the landfill area--one in the landfill itself and four on the perimeter of the landfill. In 1991, one well (OW1-81), was decommissioned because it had fallen into disrepair because of ground movement in the landfill cap and was no longer functioning. The request was approved and subsequently implemented on September 27, 1991. The phenolics analytical methodology was also changed to the more accurate and specific SW 846 Method 8270.

This report outlines the approach used to fulfill the NYSDEC requirements for operations and maintenance as requested by way of Mr. Sadowski's letter dated October 30, 2012. The purpose of this report is to present the St. Gobain's Operations and Maintenance Plan for the monitoring wells and inspection of the landfill area. We are prepared to implement this plan immediately.

SITE INSPECTION

The physical attributes of the site will be inspected annually. This inspection may be conducted by St. Gobain Abrasives Inc. or Frontier Technical Associates, Inc. personnel. The inspection will be conducted in July.

For each monitoring point, the following items will be included: well locks, well casings, covers, concrete pads, bailers and ropes, general conditions and tubing. If any of these items has deteriorated or is in disrepair, they will be replaced or repaired as appropriate. This action will be undertaken as soon as practicable and prior to the next annual inspection. A written report will be prepared and maintained on file at St. Gobain Abrasives Inc.

A monitoring point assessment form to be used for the annual inspection is presented as Figure 2. A copy of this form will be retained for review during NYSDEC inspections.



Figure 1 SCG Landfill Locations



0



Monitoring Point Assessment Form at Saint-Gobain Abrasives Landfill

Page __ of ___

Monitoring Point:			Date:	
Inspector's Name (Print):				
Well Locked:	Yes	No	NA	
Lock Functioning:	Yes	No	NA	
Bailer and Rope OK:	Yes	No	NA	
Tubing OK:	Yes	No	NA	
Protective Casing OK:	Yes	No	NA	
Concrete Pad in Good Condition:	Yes	No	NA	
Heaving of Well or Casing:	Yes	No	NA	
Well Sand in Purge Water:	Yes	No	NA	
Well Constricted:	Yes	No	NA	
Debris in Well:	Yes	No	NA	
Insects in Well:	Yes	No	NA	
Other Observations or Details on Cor	nditions Abov	e:		

Inspector's Signature:

PHYSICAL CONDITION AND GRASS CUTTING

During the annual inspection, observations of the landfill cap will be made to assess whether any soil slumping is present, rodent burrows present, growth of any large rooted vegetation, etc. Brush and bushes will be trimmed and the area will be kept clear of debris or trash which might blow onto the site, etc.

The Department has and continues to encourage all Responsible Parties to cut the grass on their landfills once per year after August 15th. The reason for this is for habitat objectives.

ANNUAL INSPECTION

Once each year, the wells will be purged and depths checked. If depth data indicates infilling of sand or sediment to a depth of 25% of the screen length, the wells will be developed in order to remove the sediment. The wells were last developed in October 1998. Sampling and purging will be conducted in accordance with the following schedule:

Year	Activity
2011	Purging, Sampling
2012	Purging
2013	Purging, Sampling
2014	Purging
2015	Purging, Sampling
2016	Purging
2017	Purging, Sampling
2018	Purging
2019	Purging, Sampling
2020	Purging
2021	Purging, Sampling
2022	Purging

The annual inspection will include the following in addition to purging:

- 1. Inspection of the well noting any unusual conditions.
- 2. The depth to the water surface from the top of the riser pipe. The total depth of each well will be checked against previous measurements. If infilling is noted, well development will be scheduled.
- 3. Each well will be purged to remove suspended sediment and biological growth if present.
- 4. A peristaltic pump or bailer may be used to purge these shallow wells. All tubing or bailers are dedicated to ensure that no cross-contamination occurs.
- 5. In years ending with odd numbers, sampling will be conducted in accordance with the sampling and analytical plan and schedule above.

REPORTING

All observations and results made during the annual inspections(s) of the landfill and physical integrity/physical parameters of the monitoring points along with the bi-annual chemistry sampling shall be reported to the Department in one annual report (Periodic Review Report) as it pertains for that year.

SAFETY

Personnel performing the sampling will adhere to all safety requirements for contractors and/or visitors of the St. Gobain facility. Personnel performing the sampling or purging will wear suitable field boots and protective gloves and safety glasses or goggles.

	w
	•
	7
	-
	a
	=
	F
	Ξ
	_
	Ã
	u
	=
	Ž
	~
	-
	ш
	Ξ
_	
_	и
_	- i
	_
-	a
-	ч
•	$\overline{}$

CHAIN OF CUSTODY/LABORATORY ANALYSIS REQUEST FORM 3385

1565 Jefferson Road, Building 300, Suite 360 • Rochester, NY 14623 | +1 585 288 5380 +1 585 288 8475 (fax) PAGE

Ю

Project Name	ъ	Project Number				ANA	ANALYSIS REQUESTED (Include Method Number and Container Preservative)	(Include	Method Numb	er and Contain	er Preservat	ive)
Project Manager	R	Report CC		PRE	PRESERVATIVE							
Company/Address				SHE	/	/		<u></u>	\	\ \ \		Preservative Key 0. NONE 1. HCL
				3NIATN		_		in	<u> </u>	\	<u></u>	2. HNO3 4. NaO4 NaOH
				OF COI	970		_	Oled sine Oled sine Oled sine	\	\ \ \		5. Zn. Acetate 6. MeOH 7. NaHSO
Phone #	ш	Email		MBER	\$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$	04s	809°	SIO 'STI		<u></u>	<u></u>	8. Other
Sampler's Signature	o o	Sampler's Printed Name		IUM	100 100 100 100 100 100 100 100 100 100	105	1 08 08 V VI	(1) 18/7)	///			REMARKS/ ALTERNATE DESCRIPTION
CLIENT SAMPLE ID	FOR OFFICE USE ONLY LAB ID	EUSE SAMPLING	LING TIME	MATRIX								
SPECIAL INSTRUCTIONS/COMMENTS						TURNAROU	TURNAROUND REQUIREMENTS		REPORT REQUIREMENTS	HREMENTS	<u> </u>	INVOICE INFORMATION
Metals						RUSH (SL	RUSH (SURCHARGES APPLY)		I. Results Only			
						— 1 day —	_2 day3 day		II. Results + QC Summaries	mmaries D as required)	# Od	
						— 4 day —	5 day		ייים אינים אינים אינים אינים		BILL TO:	
						RECUESTED REPORT DATE	PORT DATE		III. Hesults + CC and Calibration Summaries	id Calibration	:	
									. IV. Data Validation f	IV. Data Validation Report with Raw Data	eg.	
See QAPP												
STATE WHERE SAMPLES WERE COLLECTED	OLLECTED								Edata	Yes No		
RELINQUISHED BY	2	RECEIVED BY	REL	RELINQUISHED BY		REC	RECEIVED BY		RELINQUISHED BY	HED BY		RECEIVED BY
Signature	Signature		Signature		Sign	Signature		Signature	nre		Signature	
Printed Name	Printed Name		Printed Name		Print	Printed Name		Printec	Printed Name		Printed Name	
Firm	Firm		Firm		Firm			Firm			Firm	
Date/Time	Date/Time		Date/Time		Date	Date/Time		Date/Time	ime		Date/Time	



Kathy Wager< kathy.wager@frontiertechnical.com>

REPORT.HW932007.1999-11.GWSAMPLINGPLAN-LANDFILL.pdf - Adobe Acrobat Standard

4 messages

Brian Sadowski < bpsadows@gw.dec.state.ny.us>

Tue, Oct 30, 2012 at 11:16 AM

To: George.o.Davis@saint-gobain.com

Cc: Kathy.Wager@frontiertechnical.com, Michael Hinton <mjhinton@gw.dec.state.ny.us>

Dear Mr. Davis,

The above subject Plan (attached) for your site needs to be updated as it was written on November 17, 1999. At the minimum the following changes shall be made which are under the O&M Plan Landfill Area (addendum to the Sampling Plan).

Site Inspection

"The physical attributes of the site will be inspected quarterly." Change quarterly to annually. This includes the monitoring points.

Physical Condition and Grass Cutting

"During the quarterly inspection....." Change quarterly to annually.

"Grass cutting will be performed as needed, however it is expected that it will be cut at least three times during the growing season (expected in May, July and September) or more frequently if inspection indicates it is necessary".

The Department has and continues to encourage all Responsible Parties to cut their landfills once per year after August 15th. The reason for this is for habitat objectives.

Annual Inspection

"Once each year, the wells will be purged and depths checked. If depth data indicates infilling of sand or sediment to a depth of 25% of the screen length, the wells will be developed in order to remove sediment. The wells were last developed in October 1998. Sampling and purging will be conducted in accordance with the following schedule":

The last year of this schedule was 2010. Continue the schedule in year(s) and relative activity for that year.

All observations and results during the annual inspection(s) of the landfill and physical integrity and physical parameters of the monitoring points along with bi-annual chemistry sampling shall be reported to the Department in one annual report (Periodic Review Report) as it pertains for that year.

As mentioned earlier, these changes are the minimum. Please have your consultant thoroughly review the "Plan(s)" and make changes as needed. Once the changes are made, submit the updated Groundwater Sampling & Analysis Plan, Landfill Area with the O&M Plan to the Department for review.

Should you have questions, please contact me at 716-851-7220 or email at bpsadows@gw.dec.state.ny.us

Regards,

Brian Sadowski



GROUNDWATER SAMPLING AND ANALYSIS

LANDFILL AREA

SAINT GOBAIN ABRASIVES, INC.

FTA Report ET-703-711

August 5, 2011

Prepared For:

Mr. Doug Wright
Saint Gobain Abrasives, Inc.
P.O. Box 301
(6600 Walmore Road)
Niagara Falls, NY 14304

Prepared By:

Frontier Technical Associates, Inc. 9120 Main Street Clarence, NY 14031

The test results reported herein were obtained in accordance with the professional standards of the NYELAP certification program. The report was prepared for the use of Saint Gobain Abrasives, Inc. management use only, and except for required regulatory compliance reporting, are not intended for any other purpose.

INTRODUCTION

In response to the requirements of NYSDEC Region 9, Saint Gobain Abrasives. Inc. has completed groundwater sampling and analysis for the landfill area located on the southwest corner of the property in Wheatfield, NY. Figure 1A is a sketch of the landfill area showing the location of the monitoring wells which were installed in 1981 and the location of the "A" storm sewer line (West Branch) (see fence installed in 2004). Figure 1 B is an aerial photo of the area with the fence installed. Frontier Technical Associates, Inc. completed the monitoring and field analysis and prepared this report for SGA's submission to the NYSDEC. Previously, FTA had prepared technical reports which described the results of the sampling and analysis for 1991. The NYSDEC subsequently reduced monitoring parameters for 1992. For 1993, the NYSDEC deleted the requirement for analysis of unfiltered groundwater for metals, and for 1994, all metals requirements were deleted and turbidity was added for informational purposes. After the 1997 monitoring episode, SGC requested and received approval to monitor these wells every two years (1999-2009 were subsequently submitted). This report presents the results for the monitoring episode conducted for 2011. FTA has been inspecting the wells quarterly and expects to continue to do so until the next regularly scheduled bi-annual sampling event in 2013.

Since 1982, the monitoring wells and adjacent catch basin were sampled for pH and total phenolics (4AAP). In the period 1982-1988 there were no detectable levels of phenolics in monitoring wells OW2-81 through OW5-81. However, in 1989, perhaps as the result of unusual spring and summer precipitation events, low levels of phenolics were detected in the monitoring wells and adjacent catch basins. Again in 1990, low levels of total phenolics were detected. This resulted in the NYSDEC's desire to obtain additional data for evaluation beginning in 1991. Based upon the 1991 results, Well OW1-81 was decommissioned because it had fallen into disrepair and was no longer functioning to monitor the interior of the landfill. The request was approved by the NYSDEC and implemented on September 27, 1991. The phenolic compound analytical methodology was also changed to the more accurate and specific EPA Method 8270.

This report outlines the approach used to fulfill the NYSDEC requirements for 2011. The effort included sampling of four groundwater monitoring wells and one catch basin. The samples collected were all analyzed for pH, specific conductance, temperature, turbidity and phenolic compounds by EPA Method 8270.







Figure 1B. SCG Landfill Locations



0.0 0 0.02 0.0 Miles

Niagara County and its officials and employees assume no responsibility or legal liability for the accuracy, completeness, reliability, timeliness, or usefulness of any information provided. Tax parcel data was prepared for tax purposes only and is not to be reproduced or used for surveying or conveyancing.

NIAGARA COUNTY, NEW YORK DEPARTMENT OF REAL PROPERTY SERVICES



Legend

Streets and Highways

- Interstat
- Primary State Road
- Secondary State Road
- County Road
- Local Road

Parcels

1Ft Color Aerials

- Red: Band_1
- Green: Band_2
- Blue: Band_3

2Ft Color Aerials


- Red: Band_1
- Green: Band_2
- Blue: Band_3

1: 1,414

0

Notes

Enter Map Description



RESULTS OF GROUNDWATER ANALYSIS

Groundwater Elevations


Groundwater elevations were measured at the arrival at each well and recorded. These data were initially used to determine the required purge volume since the well depths are known. The data are summarized in Table 4 and Figure 3. The data obtained here support the previous observations that, historically, the movement of groundwater is generally from the southwest to the northeast in the landfill vicinity. Typically, well OW2-81 exhibits the highest groundwater elevations from year-to-year compared to the other wells while OW4-81 generally exhibits the lowest elevation. Thus, groundwater generally is moving from southwest to northeast. For this monitoring period, the movement is generally southwest to east-northeast (Figure 3).

pH, Turbidity and Specific Conductance

Analysis for pH and specific conductance were completed within 15 minutes of sampling in the field. Turbidity analyses were completed within EPA-prescribed holding times. The field data sheets documenting the analyses are included in the Appendix. Table 5 summarizes all pH, turbidity, and specific conductance data obtained on the sample date. Field sheets with the measurements are presented in Appendix I. Turbidity values were measured directly or, if necessitated by high values, were performed using dilutions. The pH measurements were within the typical range expected and previously encountered for waters in this area. The specific conductance values for the wells were similar to past data and to other wells drilled to refusal or to the upper few feet of bedrock in this area. These waters are often highly mineralized. The catch basin also yielded values which were characteristic of rain water accumulation.

Phenol Compounds

Table 6 is a summary of the analysis for phenol compounds (Complete data are contained in Appendix II). EPA Method 8270 was used for analysis of these compounds. There were no detectable concentrations of phenol, the primary parameter analyzed, above minimum detection or quantitation limits in all samples analyzed including the duplicate sample obtained at Well OW4-81. Surrogate recovery data indicated acceptable recoveries of spiked compounds.



Field analysis was completed within 15 minutes of sampling. Because of slow recharge for some of the wells, they were purged on July 19, 2011. Field data included pH, temperature, specific conductance and turbidity. These data, as well as well purging reports and groundwater elevation data, are also included this report.

GEOLOGY AND HYDROGEOLOGY

The area in the immediate vicinity of the SGA, Inc. plant is underlain by approximately 10-15 feet of clayey to sandy silt, glacial-lacustrine deposits and till. These deposits thicken southward across the site toward the Niagara River. The hydraulic conductivity of these materials is relatively low, perhaps reaching the range of 10⁻⁵ to 10⁻⁸ cm/sec.

The bedrock underlying the site consists of approximately 160 feet of dolomite of the Lockport Formation. The upper zone of the Lockport Formation is generally highly weathered, medium gray dolomite with extensive vertical fractures. It is generally striated on the surface, has extensive partings which are argillaceous or gypsum-coated. Water produced from this upper zone in the Bergholtz area of Wheatfield is generally of very poor quality, with a characteristic odor. The water generally is not suitable for drinking but occasionally is used for watering livestock or agricultural purposes. The Town of Wheatfield has extended its water lines throughout the area and recent information indicates that there are few wells in use throughout the area.

The upper portion of the dolomite sequence consists of 10 to 20 feet of bedrock consisting of thinly bedded dolomite which may produce well yields of 10-20 gpm. Hydraulic conductivities of 0.1 to 0.01 cm/sec may be encountered in this unit. For purposes of this current study, it is not thought that any of the wells penetrate significantly into the bedrock and were either drilled to refusal or into the uppermost few feet of the weathered bedrock. The bedrock surface is generally encountered at elevations between 560 feet to 570 feet MSL and is gently dipping to the south.

The wells monitored in this project were drilled to refusal as indicated in a report by Conestoga-Rovers Associates, who installed the wells in 1981 after placement of a clay cap by Secured Landfill Contractors, Inc. (SLC Contractors). Figure 2 illustrates a typical surficial geologic cross section in the landfill area.

SAMPLING OBJECTIVES

The results of analysis of samples collected and analyzed in accordance with the approval of the NYSDEC are to be used to:

- 1. Assess the groundwater flow direction and chemistry.
- 2. Define the nature and extent of pollutant migration, if any.
- 3. Meet the NYSDEC requirements for data submission.

SAMPLING LOCATIONS

As indicated previously, Figure 1A and 1B illustrate the sample locations. Four wells were sampled together with one catch basin (MH-9 located on the "A" Storm Line). Table 1 presents the sample locations and USEPA analytical methods used for samples from each location. All methods used conformed to the USEPA Methods of Analysis for Water and Wastewater (40 CFR Part 136) or SW-846 (as revised). Table 2 is a summary of the parameters, methods used, preservation methods, and holding times required.

SAMPLING EQUIPMENT AND PROCEDURES

The procedures outlined here were developed to minimize contamination of water sampling equipment and analyses, minimize concentration changes prior to testing, and standardize procedures to minimize analytical differences.

The procedures below outline the purging, sampling, and preservation methods used during this sampling program in accordance with the approved sampling plan submitted and approved in 1991 and revised in 1999:

- 1. Inspection of the well noting any unusual conditions (this is also performed quarterly).
- 2. The water level indicating device and the bottom foot or more of cable was triple rinsed with distilled water.
- 3. The depth to the water surface from the top of the riser pipe was measured and recorded on the Sample Collection Form. Depth to the bottom of each well was also measured.

Table 1. Sample Locations and Parameters Analyzed.

Well Designation	Well Depth (ft)*	Analytical Parameters**
OW2-81	18.20	pH, SC, Phenols (625) Temp., Turbidity
OW3-81	19.66	pH, SC, Phenols (625) Temp., Turbidity
OW4-81	19.38	pH, SC, Phenols (625) Temp., Turbidity
OW5-81	18.23	pH, SC, Phenols (625) Temp., Turbidity
MH A-9		pH, SC, Phenols (625) Temp., Turbidity

^{*} Based upon measurement by FTA in 1998; rechecked in 2000 and 2003; measured from top of riser pipe.

SC = Specific Conductance Phenols = Phenol Compounds as measured by EPA Method 8270/625. Temp. = Temperature

^{**} Field measurement of pH made within NYELAP guidelines (15 minutes); Turbidity measured using a nephelometer in the field.

Table 2. Summary of Parameters, Methods, Preservation Methods and Holding Times.

Parameter	EPA Method	Preservation	Holding Time
pH*	SM 4500 H B	4°C	15 Minutes (Field)
Specific Conductance	e 120.1	4°C	6 Hours (Field)
Temperature*	SM2550B		Immediately (Field)
Turbidity	180.1	4°C	48 Hours
Phenol Compounds	8270	4°C	5 days to extract 21 days to analyze

^{*} pH, Specific Conductance, and temperature were measured immediately in the field. Temperature measurements were used with cell constant correction to correct specific conductance measurements to 25°C. Frontier Technical Associates, Inc. is a NYELAP-Certified Laboratory (10475).

- 4. The volume of water in each well was calculated. Each well was purged by removing three times this volume, or if the well yield was low, water was removed until the well was "dry" (within 1-2 inches of the bottom).
- 5. A peristaltic pump was used to purge these shallow wells. All tubing coming into contact with the well water consisted of food-grade polyethylene tubing dedicated to the well. This dedicated tubing is intended to eliminate cross-contamination between the wells. The tubing was gradually lowered into the well as pumping continued. The volume required, volume obtained, water level before purging, and the start and stop times were also recorded.
- 6. All purge water was placed in a container specifically used for that well and for measuring purge volume. If the well contained very little volume, this water was reserved for pH, specific conductance and turbidity determination. After a time had elapsed for sufficient recovery, sampling was completed. Based upon results of the analyses performed over the past decade, the water contains no parameters which might be incompatible with the treatment process or SGA's sanitary sewage permit, and is acceptable to the NCSD #1 and meets their criteria. The water was then disposed of in the sanitary sewer.
- 7. Because the wells recover slowly, the wells are generally sampled within 24 to 48 hours of purging. Sample size, containers and amount of sample obtained are contained in Table 3. In 2007, it took nine days to recharge to an adequate volume for sampling.
- 8. Groundwater samples were obtained by dedicated tubing. No equipment was used for more than one well location.
- 9. Usually, the first sample was taken for analysis of pH, temperature, specific conductance and turbidity. Probes were triple rinsed with distilled water after use. The temperature measurement was used to correct specific conductance to 25°C together with a determination of cell constant compared to a reference standard. A standard reporting form with all field data is provided for each well and sample location (See Appendix).
- 10. Temperature, specific conductance, turbidity and pH were reported on the form along with the equipment used, weather conditions, field observations, and sampling times.

Table 3. Sample Containers and Required Sample Volume.

Parameter	Sample Volume	No. of Containers
pH, Specific Conductance	1,000 ml	1
Phenols	1,000 ml	1
Turbidity*	25 ml	1

^{*} Subsample of pH and Specific Conductance sample.

- 11. Sample container labels were affixed to the sample container and the samples placed in an insulated container where they were kept cool with ice if temperatures were above 4°C.
- 12. In a similar fashion, samples were obtained for phenolic compounds as required for each sample location. Each sample label was completed including the date, time, location, analysis required, and sampler's initials.
- 13. All samples were packed in an insulated cooler with sufficient ice to ensure a temperature of 4°C during storage and transport to the laboratory.
- 15. Analyses were completed within the specified holding times. The laboratory was notified by the sampling team prior to sampling and upon shipping to assist in scheduling analyses to meet all specified holding times.

SAMPLE CUSTODY

Field sampling data and purging was documented on a Well Monitoring Field Form. The following information was included:

- 1. Site name (Saint Gobain Abrasives, Inc.), sample number, etc;
- 2. Date, time, and elapsed time from purge start to finish;
- 3. Information regarding the well groundwater level, purge volume required, and actual purge volume;
- 4. Field test results including pH, temperature, turbidity and specific conductance;
- 5. Sampling method used; the materials of construction of special equipment (in margin);
- 6. Type of sample and information which appears significant;
- 7. Field observations/sampling conditions (e.g. weather)
- 8. Appearance of sample such as color, sediment, oil on surface, obvious odor, etc.
- 9. Sampler's identity and signature.

In order to maintain integrity of the groundwater samples, strict chain-of-custody procedures were followed. From the time the sample was collected until the sample was in the custody of the analytical laboratory, the samples were:

- 1. In the sampler's possession;
- 2. In the sampler's view, after being in his possession;
- 3. In the sampler's possession and then locked in a designated, secure area to prevent tampering; or in a sample cooler sealed with a tamper proof chain-of-custody seal.

A written Chain-of-Custody Record of the transfer of samples was maintained with a copy in the Appendix to this report.

The Chain-of-Custody Record was transported with the sample container at the time the sample was collected. When transferring the possession of the samples, the person making the transfer signed and recorded the date and time on the record. The number of custodians in the chain of possession were as few as possible.

SAFETY

Personnel performing the sampling adhered to all safety requirements for contractors and/or visitors of the facility. Personnel performing the sampling wore suitable personal protective equipment.

ANALYTICAL LABORATORIES

The pH, temperature, turbidity and specific conductance were measured in the field by Ronald B. Blinston of Frontier Technical Associates, Inc., NYELAP # 10475, Kathy Wager, Laboratory Director. The phenol compound analyses (EPA 8270) were performed by Columbia Analytical Services, Inc., NYELAP # 10145. Each laboratory was certified for the parameters for which data were provided.

FIELD SAMPLING PERSONNEL

All field sampling and field measurements were performed by the following:

Ronald B. Blinston

Table 4. Groundwater Elevations at Saint Gobain Abrasives, Inc. (July 19, 2011).

Date	Well No.	Top of Pipe Elevation	Depth to Water Surface	Groundwater Elevation
07/19/11	OW2-81	588.50	8.52	579.98
07/19/11	OW3-81	587.59	7.43	580.16
07/19/11	OW4-81	587.74	10.62	577.12
07/19/11	OW5-81	587.52	9.57	577.95

The groundwater elevation data presented above were obtained under my supervision and represent, to the best of my knowledge, accurate measurements for the date listed.

David M. Harty PE, BCEE

Table 5. Field Monitoring Data at Saint Gobain Abrasives Inc. (July 20, 2011).

Well No.	pH (SU)	Spec. Conductance (umho/cm)	Turbidity (NTU)
OW2-81	7.84	3852	157
OW3-81	6.92	3160	1064
OW4-81	11.2	2360	47.0
OW5-81	6.13	5632	over range
MH A-9	8.10	622	2.11

Notes:

- 1. pH, specific conductance and turbidity analyses performed by Ronald B. Blinston immediately upon sampling.
- () = pH, Specific Conductance, and Turbidity represent an average of four readings each..

Laboratory Director

NYELAP # 10475

Table 6. Results for Phenol Compound Analysis at SGA, Inc. (EPA Method 8270).

	Concentration (mg/l)
Location	All Phenol Compounds*
OW2-81	ND
OW3-81	ND
OW4-81	ND
OW4-81(Dupl)	ND
OW5-81	ND
MH A-9	ND
Method Blank	ND

ND = None of the 14 phenolic compounds detected by this method were present above laboratory quantitation levels for each sample (See Analytical Report).

MS/MSD Recovery: All acceptable and nearly identical. (See Analytical Rept. Pg. 11)

Method Blank: ND for all compounds (See Analytical Report Pg. 10).

MRL = Minimum Reporting Level MDL = Minimum Detection Level

Note: Values detected above the MDL but below the MRL are reported as "J" concentrations. There were no phenol compounds detected in this range.

The data are consistent with the data collected over the last 21+ years, and there is no reason to believe with the low detection limits reported here, that phenol compounds are migrating from the landfill.

The recoveries of spiked surrogate compounds in the set of samples analyzed from the site were very similar. Duplicate analysis performed on OW4-81 indicated consistant results with the separate sample. Blank spike recoveries were also within QC limits and indicated agreement with surrogate recoveries. The monitoring wells appear to have a dark, biological particulate material. These waters when stored in the laboratory support rapid biological growth. The method blank also had no detectable phenol.

Based upon analysis of phenol compounds and use of the previous method (4AAP), it is believed that EPA Method 8270, which is not subject to the same interferences of the former method, accurately reflects the concentrations of the phenolic compounds of concern. It should be noted that historically only "phenol" resins were used in the resins and materials disposed in the landfill. The other compounds, particularly chlorinated phenols, were not used and have never been detected. Other substances present in groundwater including biological materials may produce false positive detections by the 4AAP test as seen in previous analysis by both methods at this site. Colorimetric methods such as the 4AAP method are subject to many interferences, and thus are not recommended nor used for monitoring at this site.

Quality Assurance/Quality Control

As part of the QA/QC activities associated with the 2011 sampling episode, a field duplicate was obtained at Well OW4-81, surrogate recoveries were reported, and a method blank was analyzed for this batch. A matrix spike and matrix spike duplicate was performed on laboratory control sample water. Analysis for all these samples was by EPA Method 8270. pH, Temperature, specific conductance and turbidity were run in quadruplicate and the average value of the measurements was reported. However, there was little to no little variation noted in the data.

Appendix II, Analytical Data, presents the results of the analyses performed by the laboratory including the field duplicate, surrogate recoveries, method blank, etc. Duplicate samples were taken at Well OW4-81 with identical results.

SUMMARY

The well and catch basin samples obtained during this sampling program did not exhibit levels above the quantitation limits of any of the phenol compounds as measured by EPA Method 8270 (see Appendix—Lab Report).

The four wells surrounding the former landfill did not contain detectable levels of phenol or any of the phenol compounds analyzed. Method blank, matrix spike and matrix spike duplicate results were within EPA acceptance criteria. The results are identical to monitoring data for 1997, 1999, 2001, 2003, 2005, 2007 and 2009. MH 9 also did not exhibit detectable levels of phenol compounds. Based upon these data, together with the last six monitoring episodes covering eleven years, we conclude that the containment of the landfilled phenolic materials in the low permeability, silty-clay subsoil must be effective. The cap appears to be functioning as designed and shows no evidence of settling or dessication cracking. There is no significant vegetation present with long tap roots. Continued grass cutting has kept vegetation under control.

New concrete pads installed ten years ago (1999) at Wells OW2-81 and OW3-81 by Frontier Technical Associates, Inc. have remained intact. The riser for Well OW4-81 was replaced and repaired in 2004 due to a vehicle collision. Some cracking may be present in the well pads. Quarterly inspections of the landfill area continue under the supervision of Saint Gobain Abrasives Co. and are conducted by Frontier Technical Associates, Inc. Copies of the quarterly inspection reports have been provided to Mr. Michael Hinton, P.E., of the NYSDEC.

Groundwater associated with the Lockport Dolomite is highly mineralized as evidenced by the specific conductance values measured which indicates the concentration of dissolved solids present. This is consistent with previous data from this site and data available for wells in the immediate vicinity.

As a result of evaluation of the data recovered, the following is concluded:

1. Sampling of the four existing monitoring wells in 2011 and quantification of the phenolic compounds again showed no detectable levels of any of the compounds above detectable or quantitation limits.

- 2. Groundwater data indicate no migration of materials from the former landfill. This confirms after 28 years of monitoring that the containment and cap is effective.
- 3. Any future monitoring for phenols should continue to use EPA Method 625/8270.
- 4. There are no data developed within the past several years that would indicate a need to alter the current monitoring frequency (every two years).
- 5. pH measurements during this episode indicate elevated pH values at Well OW4-81. Repair and replacement of the riser for this well was completed during the Fall of 2004. It is believed that the bentonite-cement grout and water migrating along the casing contributed to the rise in pH at this location.

APPENDIX

Groundwater Elevation Summary

Well Purging Reports, Field Forms and Notes

Laboratory Report and Chain of Custody Forms



FRONTIER TECHNICAL ASSOCIATES, INC. WELL MONITORING FIELD FORM

Site Location: SG ABRASIUS LANDFILL Job No: ET- 703
Sample Point ID: <u>6W-2-8</u> Consultant: <u>Frontier Technical Associates, Inc.</u>
PURGE INFORMATION Purge Method: Bailer, Peristaltic Pump
Depth to Bottom of Well: 18.20 ft. 2" Well = 0.17 gals/ft.
Depth to Water Surface: 8.52 ft. 4" well = 0.66 gals/ft.
Depth of Water Column: 9.68 ft.
Volume of Standing Water in Well: كُفُرُكُمْ gallons
Start of Purge: Date: 7/8/1/ Time: 12:20
End of Purge: Date: 7/9/ Time: 12:85
Total Volume Purge:gallons Well Purged Dry?:(Yes) No
of Volumes PurgedPurging Personnel:
Recharge Rate: Rapid Slow Extremely Slow
SAMPLING INFORMATION Sample Method: Bailer, Peristaltic Pump Bladder Pump
Sample Date: 7120 11 Sample Time: 12:11 Depth to Water Surface 1865 ft.
Sample Appearance:
Samples Preserved Yes No Dissolved Metals Field Filtered: Yes No
Sampling Personnel:
FIELD MEASUREMENTS
Meters Calibrated Yes No

PARAMETER	METER NUMBER	UNITS	MEASUREMENT	NOTES
рН	Oakton 300	STD. UNITS	7.89 ,7.85 7.81	7,79
Spec. Conductance	Hach 44600-00	× <i>LOOO</i> μMHOS/CM	3,84 385,3.84	3.86
Temperature	Hach 44600-00	С	21.6, 21.4, 21-2.	a1.2
Turbidity	Hach 2100P	NTU	44to 161, 157	157,153
REDOX	Oakton ORPTestr	mV	-78-67-41	56

Weather	
Notes:	



FRONTIER TECHNICAL ASSOCIATES, INC. WELL MONITORING FIELD FORM

.5.4.4
Site Location: S.G. ABRASIVES LANDFILL Job No: ET-703
Sample Point ID:Consultant: Frontier Technical Associates, Inc.
PURGE INFORMATION Purge Method: Bailer Peristaltic Pump
Depth to Bottom of Well: 19.66 ft. 2" Well = 0.17 gals/ft.
Depth to Water Surface:
Depth of Water Column: <u>12.23</u> ft.
Volume of Standing Water in Well: 🔼 🚺 gallons
Start of Purge: Date: 7/1/1/ Time: 12:33
End of Purge: Date: 7/19/1/ Time: /2:38
Total Volume Purge: 1,9 gallons Well Purged Dry?(Yes)No
of Volumes PurgedPurging Personnel:
Recharge Rate: Rapid, Slow, Extremely Slow
SAMPLING INFORMATION Sample Method: Bailer, Peristaltic Pump Bladder Pump
Sample Date: 7 129 11 Sample Time: 12 : 21 Depth to Water Surface 569 ft.
Sample Appearance: TORBID
Samples Preserved Yes No Dissolved Metals Field Filtered: Yes No
Sampling Personnel: RON GLINGTON
FIELD MEASUREMENTS
Meters Calibrated Yes No

PARAMETER	METER NUMBER	UNITS	MEASUREMENT	NOTES
рН	Oakton 300	STD. UNITS	7.02.694	6,90,6,84
Spec. Conductance	Hach 44600-00	× (Οοδ) μ MHOS/CM	3.14,3.16,	3,17, 317
Temperature	Hach 44600-00	С	19, 19, 19,	19
Turbidity	Hach 2100P	NTU	289, 283.	261,231
REDOX	Oakton ORPTestr	mV	-39,-34,-32	-31

Weather:	
Notes:	



8

FRONTIER TECHNICAL ASSOCIATES, INC. WELL MONITORING FIELD FORM

	Site Location: SG ABRASINES I	AND FILL JOB NO: ET- 703
	Sample Point ID:	Consultant: Frontier Technical Associates, Inc.
	PURGE INFORMATION	Purge Method: Bailer, Peristaltic Pump
	Depth to Bottom of Well: 19.38 ft.	2" Well = 0.17 gals/ft.
	Depth to Water Surface: 10.62 ft.	4" well = 0.66 gals/ft.
	Depth of Water Column: 8.76 ft.	
	Volume of Standing Water in Well:	5_ gallons
	Start of Purge: Date: 711911 Time:	11:10
	End of Purge: Date: 7/19/11 Time	: <u>II:20</u>
	Total Volume Purge: 1.4 gallons \	
79	# of Volumes PurgedPurgin	g Personnel: RON BLINSTON
	Recharge Rate: Rapid, Slow Extrem	nely Slow
		nple Method: Bailer Peristaltic Pump, Bladder Pump
		e: 11:30 Depth to Water Surface 1692ft.
	Sample Appearance: 5L(G)	HTLY TURBID
	Samples Preserved Yes No Dissolve	ed Metals Field Filtered: <u>Yes No</u>
	Sampling Personnel: KON !	SLINSTON_
	FIELD MEASUREMENTS	
	Meters Calibrated Yes No	

PARAMETER	METER NUMBER	UNITS	MEASUREMENT	NOTES	
рН	Oakton 300	STD. UNITS	11.24, 11.24	11.24, 1	1,21
Spec. Conductance	Hach 44600-00	Χ <i>(Θύφ</i> μ MHOS/CM	2.35, 2.36,	2.36,2.	37
Temperature	Hach 44600-00	С	20, 19, 19, 19		•
Turbidity	Hach 2100P	NTU	47.5, 47.5.	45.8 44	Ġ
REDOX	Oakton ORPTestr	mV	-10, -8, 6	-4	

Weather:					
Notes:	DUP-				



FRONTIER TECHNICAL ASSOCIATES, INC. WELL MONITORING FIELD FORM

	IN CUL
Site Location: SG ABRASIVES L	Job No: ET- 703
Sample Point ID: <u>Sw-5-81</u>	Consultant: Frontier Technical Associates, Inc.
PURGE INFORMATION	Purge Method: Bailer, Reristaltic Pump
Depth to Bottom of Well: 18.23ft.	2" Well = 0.17 gals/ft.
Depth to Water Surface: 9,57 ft.	4" well = 0.66 gals/ft.
Depth of Water Column: <u>\$.46</u> ft.	
Volume of Standing Water in Well: 🚣	<u>5</u> gallons
Start of Purge: Date: 71/91/	s: <u> N : 29 </u>
End of Purge: Date: 7/9/11 Time	e: <u>// :34</u>
Total Volume Purge: gallons	Well Purged Dry? Yes No
	ng Personnel: RON BLUSTON
Recharge Rate: Rapid, Slow, Extrer	nely Slow
	mple Method: Bailer, Peristaltic Pump Bladder Pump
Sample Date: 7 PO 11 Sample Tim	e: <u>/0: 55</u> Depth to Water Surface <u>DRY</u> ft.
Sample Appearance:	BLACK
Samples Preserved: Yes No Dissolv	ved Metals Field Filtered: <u>Yes No</u>
Sampling Personnel: Row Brings	ō√
FIELD MEASUREMENTS	
Meters Calibrated Yes No	

PARAMETER	METER NUMBER	UNITS	MEASUREMENT	NOTES	
рН	Oakton 300	STD. UNITS	6-13/6.13	(6.13)	6.13
Spec. Conductance	Hach 44600-00	χ(Ος ε) μ MHOS/CM	5.64 (5.63	5.62,5	-64
Temperature	Hach 44600-00	С	220022	22,22	
Turbidity	Hach 2100P	NTU	OR, OR,	OR, OR	
REDOX	Oakton ORPTestr	mV	-7, -9,	p,-19	

Weather	SUNNY,	80 -F	
Notes:			



FRONTIER TECHNICAL ASSOCIATES, INC. WELL MONITORING FIELD FORM

Site Location: SG ABRASING LANDICU Job No: ET	
Sample Point ID: MH-A-9 Consultant: Frontier Technical Associates, Inc.	
PURGE INFORMATION Purge Method: Bailer, Peristaltic Pump	
Depth to Bottom of Well:ft. 2" Well = 0.17 gals/ft.	
Depth to Water Surface:ft. 4" well = 0.66 gals/ft.	
Depth of Water Column:ft.	
Volume of Standing Water in Well: gallons	
Start of Purge: Date:/Time::	
End of Purge: Date:/ Time:	
Total Volume Purge: gallons Well Purged Dry?: Yes No	
# of Volumes PurgedPurging Personnel:	
Recharge Rate: Rapid, Slow, Extremely Slow	
SAMPLING INFORMATION Sample Method: Bailer Peristaltic Pump Bladder Pump	
Sample Date: 7/2011 Sample Time: 11:10 Depth to Water Surfaceft.	
Sample Appearance:CLEAR	
Samples Preserved Yes No Dissolved Metals, Field Filtered: Yes No	
Sampling Personnel: Row BLINSTON	
FIELD MEASUREMENTS	
Meters Calibrated Yes No	

PARAMETER	METER NUMBER	UNITS	MEASUREMENT	NOTES
рН	Oakton 300	STD. UNITS	8.10, 8.11, 8	.11, 8.09
Spec. Conductance	Hach 44600-00	χ/οσυ μ MHOS/CM	0.63,0.62,	0.62,062
Temperature	Hach 44600-00	С	26,26,26	0.61 26
Turbidity	Hach 2100P	NTU	2,20,2.10,	1
REDOX	Oakton ORPTestr	mV	-77, -62, -47	, -38

Weather:	
Notes:	



July 29, 2011

Service Request No: R1104088

Ms. Kathy Wager Frontier Technical Associates 9120 Main Street Clarence, NY 14031

Laboratory Results for: Plant C Landfill/ET-703

Dear Ms. Wager:

Enclosed are the results of the sample(s) submitted to our laboratory on July 21, 2011. For your reference, these analyses have been assigned our service request number R1104088.

All analyses were performed according to our laboratory's quality assurance program. The test results meet requirements of the NELAP standards except as noted in the case narrative report. All results are intended to be considered in their entirety, and Columbia Analytical Services, Inc. (CAS) is not responsible for use of less than the complete report. Results apply only to the items submitted to the laboratory for analysis and individual items (samples) analyzed, as listed in the report. The measurement uncertainty of the results included in this report is within that expected when using the prescribed method(s) for analysis of these samples, and represented by Laboratory Control Sample control limits. Any events, such as QC failures, which may add to the uncertainty are explained in the report narrative.

Please contact me if you have any questions. My extension is 7473. You may also contact me via email at DPatton@caslab.com.

Respectfully submitted,

Columbia Analytical Services, Inc.

Hatten. Deb Patton

Project Manager

Page 1 of _ 14

CASE NARRATIVE

This report contains analytical results for the following samples: Service Request Number: R1104088

Lab ID	Client ID
R1104088-001	OW-2
R1104088-002	OW-3
R1104088-003	OW-4
R1104088-004	OW-5
R1104088-005	DUP
R1104088-006	MH-A-9

All samples were received in good condition unless otherwise noted on the cooler receipt and preservation check form located at the end of this report.

All samples were preserved in accordance with approved analytical methods.

All samples have been analyzed by the approved methods cited on the analytical results pages.

All holding times and associated QC were within limits.

No analytical or QC problems were encountered.

All sampling activities performed by CAS personnel have been in accordance with "CAS Field Procedures and Measurements Manual" or by client specifications.



REPORT QUALIFIERS

- U Analyte was analyzed for but not detected. The sample quantitation limit has been corrected for dilution and for percent moisture, unless otherwise noted in the case narrative.
- Estimated value due to either being a Tentatively Identified Compound (TIC) or that the concentration is between the MRL and the MDL. Concentrations are not verified within the linear range of the calibration. For DoD: concentration >40% difference between two GC columns (pesticides/Arclors).
- B Analyte was also detected in the associated method blank at a concentration that may have contributed to the sample result.
- E Inorganics- Concentration is estimated due to the serial dilution was outside control limits.
- E Organics- Concentration has exceeded the calibration range for that specific analysis.
- D Concentration is a result of a dilution, typically a secondary analysis of the sample due to exceeding the calibration range or that a surrogate has been diluted out of the sample and cannot be assessed.
- * Indicates that a quality control parameter has exceeded laboratory limits. Under the "Notes" column of the Form I, this qualifier denotes analysis was performed out of Holding Time.
- H Analysis was performed out of hold time for tests that have an "immediate" hold time criteria.
- # Spike was diluted out.
- + Correlation coefficient for MSA is <0.995.
- N Inorganics- Matrix spike recovery was outside laboratory limits.
- N Organics- Presumptive evidence of a compound (reported as a TIC) based on the MS library search.
- S Concentration has been determined using Method of Standard Additions (MSA).
- W Post-Digestion Spike recovery is outside control limits and the sample absorbance is <50% of the spike absorbance.
- P Concentration >40% (25% for CLP) difference between the two GC columns.
- C Confirmed by GC/MS
- Q DoD reports: indicates a pesticide/Aroclor is not confirmed (≥100% Difference between two GC columns).
- X See Case Narrative for discussion.



CAS/Rochester Lab ID # for State Certifications1

NELAP Accredited Connecticut ID # PH0556 Delaware Accredited DoD ELAP #65817 Florida ID # E87674 Illinois ID #200047 Maine ID #NY0032 Nebraska Accredited Nevada ID # NY-00032 New Jersey ID # NY004 New York ID # 10145 New Hampshire ID # 294100 A/B Pennsylvania ID# 68-786 Rhode Island ID # 158

Analyses were performed according to our laboratory's NELAP-approved quality assurance program and any applicable state requirements. The test results meet requirements of the current NELAP standards or state requirements, where applicable, except as noted in the laboratory case narrative provided. For a specific list of accredited analytes, refer to the certifications section at www.caslab.com.

Analytical Report

Client:

Frontier Technical Associates

Project:

Plant C Landfill/ET-703

Sample Matrix:

Water

OW-2

Sample Name: Lab Code:

R1104088-001

Service Request: R1104088 Date Collected: 7/20/11 1211

Date Received: 7/21/11

Units: µg/L Basis: NA

Semivolatile Organic Compounds by GC/MS

Analytical Method: 8270D Prep Method:

EPA 3510C

Analysis Lot: 255089 Extraction Lot: 138283

			Dilution	Date	Date	Extraction	Analysis	
Analyte Name	Result Q	MRL	Factor	Extracted	Analyzed	Lot	Lot	Note
2,4,5-Trichlorophenol	ND U	9.4	1	7/25/11	7/27/11 13:22	138283	255089	
2,4,6-Trichlorophenol	ND U	9.4	I	7/25/11	7/27/11 13:23	2 138283	255089	
2,4-Dichlorophenol	ND U	9.4	1	7/25/11	7/27/11 13:22	2 138283	255089	
2,4-Dimethylphenol	ND U	9.4	I	7/25/11	7/27/11 13:22	138283	255089	
2,4-Dinitrophenol	ND U	47	1	7/25/11	7/27/11 13:22	2 138283	255089	
2-Chlorophenol	ND U	9.4	1	7/25/11	7/27/11 13:2:	2 138283	255089	
2-Methylphenol	ND U	9.4	1	7/25/11	7/27/11 13:22	2 138283	255089	
2-Nitrophenol	ND U	9.4	1	7/25/11	7/27/11 13:2:	2 138283	255089	
3- and 4-Methylphenol Coelution	ND U	9.4	1	7/25/11	7/27/11 13:2:	2 138283	255089	
4,6-Dinitro-2-methylphenol	ND U	47	1	7/25/11	7/27/11 13:2:	2 138283	255089	
4-Chloro-3-methylphenol	ND U	9.4	1	7/25/11	7/27/11 13:2:	2 138283	255089	
4-Nitrophenol	ND U	47	1	7/25/11	7/27/11 13:2:	2 138283	255089	
Pentachlorophenol (PCP)	ND U	47	1	7/25/11	7/27/11 13:2:	2 138283	255089	
Phenol	ND U	9.4	1	7/25/11	7/27/11 13:2:	2 138283	255089	

		Control	Date		
Surrogate Name	%Rec	Limits	Analyzed	Q	
2,4,6-Tribromophenol	84	28-157	7/27/11 13:22		
2-Fluorophenol	44	10-105	7/27/11 13:22		
Phenol-d6	33	10-107	7/27/11 13:22		***************************************

Analytical Report

Client:

Frontier Technical Associates

Project:

Plant C Landfill/ET-703

Sample Matrix:

Water

Sample Name:

Lab Code:

OW-3

R1104088-002

Service Request: R1104088 Date Collected: 7/20/11 1221 Date Received: 7/21/11

> Units: µg/L Basis: NA

Semivolatile Organic Compounds by GC/MS

Analysis Lot: 255089

Analytical Method: 8270D Extraction Lot: 138283 Prep Method: **EPA 3510C**

Analyte Name	Result	Q	MRL	Dilution Factor	Date Extracted	Date Analyzed	Extraction Lot	Analysis Lot	Note
2,4,5-Trichlorophenol	ND	U	9.4	1	7/25/11	7/27/11 14:02	138283	255089	
2,4,6-Trichlorophenol	ND	U	9.4	1	7/25/11	7/27/11 14:02	2 138283	255089	
2,4-Dichlorophenol	ND	U	9.4	1	7/25/11	7/27/11 14:02	2 138283	255089	
2,4-Dimethylphenol	ND	U	9.4	1	7/25/11	7/27/11 14:02	2 138283	255089	
2,4-Dinitrophenol	ND	U	47	1	7/25/11	7/27/11 14:03	2 138283	255089	
2-Chlorophenol	ND		9.4	1	7/25/11	7/27/11 14:02	2 138283	255089	**************
2-Methylphenol	ND	U	9.4	1	7/25/11	7/27/11 14:02	2 138283	255089	
2-Nitrophenol	ND		9.4	1	7/25/11	7/27/11 14:02	2 138283	255089	
3- and 4-Methylphenol Coelution	ND	_	9.4	1	7/25/11	7/27/11 14:03	2 138283	255089	
4,6-Dinitro-2-methylphenol	ND	U	47	1	7/25/11	7/27/11 14:0	2 138283	255089	
4-Chloro-3-methylphenol	ND		9,4	1	7/25/11	7/27/11 14:03	2 138283	255089	
4-Nitrophenol	ND	_	47	1	7/25/11	7/27/11 14:0	2 138283	255089	
Pentachlorophenol (PCP)	ND	ΙΙ	47	1	7/25/11	7/27/11 14:0	2 138283	255089	
Phenol	ND		9.4	ĩ	7/25/11	7/27/11 14:0	2 138283	255089	

Surrogate Name	%Rec	Control Limits	Date Analyzed	Q
2,4,6-Tribromophenol	81	28-157	7/27/11 14:02	
2-Fluorophenol	39	10-105	7/27/11 14:02	
Phenol-d6	25	10-107	7/27/11 14:02	

Analytical Report

Client:

Frontier Technical Associates

Project:

Plant C Landfill/ET-703

Sample Matrix:

Water

Sample Name: Lab Code:

OW-5 R1104088-004

Service Request: R1104088 Date Collected: 7/20/11 1055

Date Received: 7/21/11

Units: µg/L Basis: NA

Semivolatile Organic Compounds by GC/MS

Analytical Method: 8270D Prep Method:

EPA 3510C

Analysis Lot: 255089 Extraction Lot: 138283

Analyte Name	Result Q	MRL	Dilution Factor	Date Extracted	Date Analyzed	Extraction Lot	Analysis Lot	Note
2,4,5-Trichlorophenol	ND U	9.4	1	7/25/11	7/27/11 16:42	138283	255089	
2,4,6-Trichlorophenol	ND U	9.4	1	7/25/11	7/27/11 16:42	2 138283	255089	
2,4-Dichlorophenol	ND U	9.4	1	7/25/11	7/27/11 16:42	2 138283	255089	
2,4-Dimethylphenol	ND U	9.4	1	7/25/11	7/27/11 16:42	2 138283	255089	
2,4-Dinitrophenol	ND U	47	1	7/25/11	7/27/11 16:42	2 138283	255089	
2-Chlorophenol	ND U	9.4	1	7/25/11	7/27/11 16:42	138283	255089	
2-Methylphenol	ND U	9.4	1	7/25/11	7/27/11 16:42	2 138283	255089	
2-Nitrophenol	ND U	9.4	1	7/25/11	7/27/11 16:42	2 138283	255089	
3- and 4-Methylphenol Coelution	ND U	9.4	1	7/25/11	7/27/11 16:42	138283	255089	
4,6-Dinitro-2-methylphenol	ND U	47	1	7/25/11	7/27/11 16:42	2 138283	255089	
4-Chloro-3-methylphenol	ND U	9.4	I	7/25/11	7/27/11 16:42	2 138283	255089	
4-Nitrophenol	ND U	47	I	7/25/11	7/27/11 16:42	2 138283	255089	
Pentachlorophenol (PCP)	ND U	47	1	7/25/11	7/27/11 16:42	2 138283	255089	
Phenol	ND U	9.4	1	7/25/11	7/27/11 16:42	2 138283	255089	

Surrogate Name	%Rec	Control Limits	Date Analyzed	Q
2,4,6-Tribromophenol	81	28-157	7/27/11 16:42	
2-Fluorophenol	43	10-105	7/27/11 16:42	
Phenol-d6	28	10-107	7/27/11 16:42	

Analytical Report

Client:

Frontier Technical Associates

Project:

Plant C Landfill/ET-703

Sample Matrix:

Water

Sample Name: Lab Code:

MH-A-9 R1104088-006

Service Request: R1104088 Date Collected: 7/20/11 1110

Date Received: 7/21/11

Units: µg/L Basis: NA

Semivolatile Organic Compounds by GC/MS

Analytical Method: 8270D Prep Method:

EPA 3510C

Analysis Lot: 255089 Extraction Lot: 138283

				Dilution	Date	Date	Extraction	Analysis	
Analyte Name	Result	Q	MRL	Factor	Extracted	Analyzed	Lot	Lot	Note
2,4,5-Trichlorophenol	ND	U	9,4	1	7/25/11	7/27/11 18:01	138283	255089	
2,4,6-Trichlorophenol	ND	U	9.4	1	7/25/11	7/27/11 18:01	138283	255089	
2,4-Dichlorophenol	ND	U	9.4	I	7/25/11	7/27/11 18:01	138283	255089	
2,4-Dimethylphenol	ND	U	9.4	I	7/25/11	7/27/11 18:01	138283	255089	
2,4-Dinitrophenol	ND	U	47	1	7/25/11	7/27/11 18:01	138283	255089	
2-Chlorophenol	ND	U	9.4	1	7/25/11	7/27/11 18:01	138283	255089	
2-Methylphenol	ND	U	9,4	1	7/25/11	7/27/11 18:01	138283	255089	
2-Nitrophenol	ND	U	9.4	1	7/25/11	7/27/11 18:01	138283	255089	
3- and 4-Methylphenol Coelution	ND	U	9.4	1	7/25/11	7/27/11 18:01	138283	255089	
4,6-Dinitro-2-methylphenol	ND	U	47	1	7/25/11	7/27/11 18:0	138283	255089	
4-Chloro-3-methylphenol	ND	U	9.4	1	7/25/11	7/27/11 18:01	138283	255089	
4-Nitrophenol	ND	U	47	1	7/25/11	7/27/11 18:0	138283	255089	
Pentachlorophenol (PCP)	ND	U	47	1	7/25/11	7/27/11 18:0	138283	255089	
Phenol	ND	U	9.4	1	7/25/11	7/27/11 18:0	138283	255089	

Surrogate Name	%Rec	Control Limits	Date Analyzed	Q
2,4,6-Tribromophenol	74	28-157	7/27/11 18:01	
2-Fluorophenol	38	10-105	7/27/11 18:01	
Phenol-d6	24	10-107	7/27/11 18:01	

Analytical Report

Client:

Frontier Technical Associates

Project:

Plant C Landfill/ET-703

Sample Matrix:

Water

Sample Name: Lab Code:

Method Blank RQ1107035-01 Service Request: R1104088

Date Collected: NA Date Received: NA

> Units: µg/L Basis: NA

Semivolatile Organic Compounds by GC/MS

Analytical Method: 8270D Prep Method:

EPA 3510C

Analysis Lot: 254991 Extraction Lot: 138283

			Dilution	Date	Date	Extraction	Analysis	
Analyte Name	Result Q	MRL	Factor	Extracted	Analyzed	Lot	Lot	Note
2,4,5-Trichlorophenol	ND U	10	1	7/25/11	7/26/11 18:22	2 138283	254991	
2,4,6-Trichlorophenol	ND U	10	1	7/25/11	7/26/11 18:22	138283	254991	
2,4-Dichlorophenol	ND U	10	1	7/25/11	7/26/11 18:22	2 138283	254991	
2,4-Dimethylphenol	ND U	10	1	7/25/11	7/26/11 18:22	2 138283	254991	
2,4-Dinitrophenol	ND U	50	1	7/25/11	7/26/11 18:22	2 138283	254991	
2-Chlorophenol	ND U	10	1	7/25/11	7/26/11 18:22	2 138283	254991	
2-Methylphenol	ND U	10	1	7/25/11	7/26/11 18:22	2 138283	254991	
2-Nitrophenol	ND U	10	1	7/25/11	7/26/11 18:22	2 138283	254991	
3- and 4-Methylphenol Coelution	ND U	10	1	7/25/11	7/26/11 18:22	2 138283	254991	
4,6-Dinitro-2-methylphenol	ND U	50	1	7/25/11	7/26/11 18:22	2 138283	254991	
4-Chloro-3-methylphenol	ND U	10	1	7/25/11	7/26/11 18:22	2 138283	254991	
4-Nitrophenol	ND U	50	1	7/25/11	7/26/11 18:22	2 138283	254991	
Pentachlorophenol (PCP)	ND U	50	1	7/25/11	7/26/11 18:22	2 138283	254991	
Phenol	ND U	10	1	7/25/11	7/26/11 18:22	2 138283	254991	

Surrogate Name	%Rec	Control Limits	Date Analyzed Q	
2,4,6-Tribromophenol	89	28-157	7/26/11 18:22	
2-Fluorophenol	47	10-105	7/26/11 18:22	
Phenol-d6	29	10-107	7/26/11 18:22	

QA/QC Report

Client:

Frontier Technical Associates

Project:

Plant C Landfill/ET-703

Sample Matrix:

Water

Service Request: R1104088

Date Collected: 7/20/11 Date Received: 7/21/11 Date Analyzed: 7/27/11

Matrix Spike Summary Semivolatile Organic Compounds by GC/MS

Sample Name:

OW-4

Lab Code:

R1104088-003

Units: µg/L

Basis: NA

Analytical Method: 8270D

Prep Method:

EPA 3510C

	Sample		OW-4MS Aatrix Spike Q1107035-0 Spike		Duplic	OW-4DMS ate Matrix Q1107035-0 Spike		% Rec		RPD
Analyte Name	Result	Result	Amount	% Rec	Result	Amount	% Rec	Limits	RPD	Limit
2,4,5-Trichlorophenol	ND	76.7	94.3	81	84.7	94.3	90	62 - 117	10	30
2,4,6-Trichlorophenol	ND	76.6	94.3	81	85.2	94.3	90	62 - 115	11	30
2,4-Dichlorophenol	ND	72.8	94.3	77	78.1	94.3	83	62 - 109	7	30
2,4-Dimethylphenol	ND	67.6	94.3	72	74.6	94.3	79	36 - 106	10	30
2,4-Dinitrophenol	ND	58.9	94.3	62	74.1	94.3	79	55 - 153	23	30
2-Chlorophenol	ND	66.9	94.3	71	69.3	94.3	73	37 - 112	4	30
2-Methylphenol	ND	64.1	94.3	68	67.1	94.3	71	51 - 95	5	30
2-Nitrophenol	ND	73.9	94.3	78	79.9	94.3	85	60 - 113	8	30
3- and 4-Methylphenol Coelution	ND	120	189	64	126	189	67	49 - 89	5	30
4,6-Dinitro-2-methylphenol	ND	71.3	94.3	76	84.1	94.3	89	60 - 135	16	30
4-Chloro-3-methylphenol	ND	77.3	94.3	82	83.7	94.3	89	22 - 136	8	30
4-Nitrophenol	ND	32.9	94.3	35	39.9	94.3	42	23 - 67	19	30
Pentachlorophenol (PCP)	ND	70.7	94.3	75	86.8	94.3	92	64 - 147	20	30
Phenol	ND	31.9	94.3	34	33.0	94.3	35	20 - 52	3	30

Results flagged with an asterisk (*) indicate values outside control criteria.

Results flagged with a pound (#) indicate the control criteria is not applicable.

Percent recoveries and relative percent differences (RPD) are determined by the software using values in the calculation which have not been rounded

00011

QA/QC Report

Client:

Frontier Technical Associates

Project:

Plant C Landfill/ET-703

Sample Matrix:

Water

Service Request: R1104088

Date Analyzed: 7/26/11

Lab Control Sample Summary Semivolatile Organic Compounds by GC/MS

Analytical Method: Prep Method:

8270D

EPA 3510C

Units: μg/L Basis: NA

Extraction Lot: 138283

		Lab Control Sample RQ1107035-02			Duplicate Lab Control Sample RQ1107035-03					
Analyte Name	Result	Spike Amount	% Rec	Result	Spike Amount	% Rec	% Rec Limits	RPD	RPD Limit	
2,4,5-Trichlorophenol	97.0	100	97	100	100	100	62 - 117	3	30	
2.4.6-Trichlorophenol	97.9	100	98	99.0	100	99	62 - 115	1	30	
2,4-Dichlorophenol	91.4	100	91	90.4	100	90	62 - 109	1	30	
2,4-Dimethylphenol	89.5	100	90	86,9	100	87	28 - 100	3	30	
2,4-Dinitrophenol	92.5	100	93	94.6	100	95	40 - 156	2	30	
2-Chlorophenol	83.5	100	83	82,4	100	82	42 - 112	1	30	
2-Methylphenol	77.8	100	78	78.9	100	79	51 - 95	1	30	
2-Nitrophenol	93,5	100	93	93.5	100	94	60 - 113	<1	30	
3- and 4-Methylphenol Coelution	150	200	75	150	200	75	49 - 89	<1	30	
4,6-Dinitro-2-methylphenol	99.3	100	99	98.3	100	98	65 - 141	1	30	
4-Chloro-3-methylphenol	97.9	100	98	96.7	100	97	42 - 124	1	30	
4-Nitrophenol	43.0	100	43	44.6	100	45	10 - 126	4	30	
Pentachlorophenol (PCP)	102	100	102	103	100	103	56 - 146	<1	30	
Phenol	39.8	100	40	40.1	100	40	10 - 113	<1	30	

Results flagged with an asterisk (*) indicate values outside control criteria.

Percent recoveries and relative percent differences (RPD) are determined by the software using values in the calculation which have not been rounded.

X	Columbia Analytical	
四	Analytical	Services*

CHAIN OF CUSTODY/LABORATORY ANALYSIS REQUEST FORM

VI.	SR#		•	
	CAS Contact	DES	PATT	DN

Project Name	e 230, nochester, NY 140	00 1 000	.200.000	0 1 000.	1	222 1	303.	200.0	4/5 (iax)	PA	GE _	<u> </u>		<u> </u>					
PLANT-CLANDFILL ET-703							ANALYSIS REQUESTED (Include Method Number and Container Preservative)													
Project Manager, KATHY WAGER Report CC							TIVE	:							8					
Company Address FRONTIER TECH		1 /	7		-/	/ /	/	/ /	/	/_/	-	} 	/ /		Preservative Key O. NONE					
PRONTIER TECHNICAL ASSOCIATES, INC.							//				' /:	/_/	_/	_/.^	$\langle \rangle \rangle$) /		$\cdot /$		1. HCL 2. HNO ₃ 3. H ₂ SO ₄ 4. NãOH
CLARENCE NY	NUMBER OF CONTAINERS	/	10 C S C C C C C C C C C C C C C C C C C		/ <u>.</u>	/ a		1.0	PER PER							/ / 5. Zn. Acetate 1				
Phone (116) 6321 - 229		/ /:		* 50 0	21/60	S 20/			Somments L	5	9 /		/		/ /	6. MeOH 7. NaHSO ₄ 8. Othefr				
Sampler's Signature		CANS VOL		79 X			0000	981	\$ 50 E	š i /			• /			foc				
				15		METALS.	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1		y /		/ /				/					
CLIENT SAMPLE ID	LAB ID	7/20/11	TIME 12:51	MATRIX	-	100	/ 90/	00	0.0	12.0	 ₹	1 2 5		7	/		<u> </u>	/ 	_	REMARKS/ ALTERNATE DESCRIPTION
101-3		1/20/11	12:21	GW	1									-						
012-4			11:30		3		-+			-		~~~~~	\Diamond	'	-				·	,
0W-5			10:55		1				_											
DUP		1. 1	,,,,,,,,		1								$\overline{\mathbf{x}}$							
MH-A-9		Y	11:10	Å	1								X							
	· · · · · · · · · · · · · · · · · · ·				<u> </u>															
``																·				
						\vdash					,									
SPECIAL INSTRUCTIONS/COMMENTS					TURNAROUND REQUIREMENTS					TS	REPORT REQUIREMENTS						INVOICE INFORMATION			
Metals (ALL PITENOI		RUSH (SURCHARGES APPLY)						1. Results Only						INVOICE INPORMATION						
		24 hr48 hr5 day					iay	II. Results + QC Summaries (LCS, DUP, MS/MSD as required)						PO#						
PHENOIS B		STANDARD REQUESTED FAX DATE						III. Results + QC and Calibration						BILL TO:						
BATCH QAQC							REQUESTED FAX DATE						· Summaries						-	QQ012
	REQUESTED REPORT DATE						IV. Data Validation Report with Raw Data						\vdash	4548						
See QAPP						V. Specialized Forms / Custom Report						 4 A								
SAMPLE RECEIPT: CONDITION/COOL RELINQUISHED BY	LS: Y N					Edala Yes R1														
RELINQUISHED BY RECEIVED BY RELINQUISHED I							BY RECEIVED BY				RELINQUISHED BY Plant C						Landhii			
Signature	Signature Ward									1 12 2 (6)		10 11 12 12 13 14 15 15 15 15 15 15 15 15 15								
Printed Name SLINGTON	Printed Name				Printed Name						Printed Name									
Daigning 21 - 1/ 12 45 Day 1 12 45 Day 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1							Firm 7/21/11 / 1485 Date/Time				Firm						Firm			
Distribution: White - Return to Originator; Yellow	55		vais/ i iiiii	-					Date/Ti	пе					Date/T	ime				

Cooler Receipt And Preservation Check Form

Projec	t/Client_F	TA.			F	older Numbe	r RI	-4088	<u></u> •				
Coole	r received (on_7	12/1	(by: Dlu	_com	RIER: Ca s	UPS	FEDEX	VELOC	TITY CLIENT			
1. 2. 3. 4. 5. 6. 7.	Were cus Did all bo Did VOA Were Coe Where did	tody ottles vials or Ic i the	pape arriv s, Al e pa bottl	s on outside of coors properly filled ye in good conditickalinity, or Sulfid cks present? les originate?	out (ink on (unb e have s	oken)?	ir bubble	YES YES S? YES CAS/RC	NO NO NO NO NO SC, CLI	OVAT ENT			
	Is the tem	perat	ure v	within 0° - 6° C?:	¥	ණ ර ජ	S	Yes	Yes	Yes			
	If No, Explain Below No No No No												
	Date/Time Temperatures Taken: 7/2/11/1502												
	Thermome	eter I	D: I	R GUN#3 / IRC	JUN#4	Reading F	rom: T	emp Blank	/ Samo	te Bottle			
If out of PC Sec	of Temper: ondary Rev	ature /iew:	, no	te packing/ice co	ndition —	, Client App	oroval to	Run Samp	oles:				
	Breakdowr				Tim		35	bv:	AD				
2. 3. 4.	Did all bot Were corre Air Sample	tle lai ct co es: (bels ntair Cass	s complete (A.e. a) and tags agree wi ners used for the t ettes / Tubes Intac	th custo ests indi	dy papers?	·	YES YES Tedlar®	NO NO NO Bags Inf	lated N/A			
Explain	any discre	panci	ies: _										
pH	Reagent	YES	NO	Lot Received	Exp	Sample ID	Vol. Added	Lot Added	Final pH	Yes = All			
≥12	NaOH								,,,,,	samples OK			
≤2	HNO ₃									No =			
<u>\$2</u>	H ₂ SO ₄									Samples were			
Residual Chlorine -)	For TCN and Phenol			If present, contact add ascorbic acid						preserved at lab as listed			
	Na ₂ S ₂ O ₃	~	-			*Not to be te		PM OK to					
Zn Aceta tested and recorded by VOAs or GenChem on a separate worksheet									Chem	Adjust:			
	HCI	*	*			on a separate	WOLKSHE	JE					
ottle lot i		50	911	-15, 090 blo)- IJ					-			

Secondary Review: