

Fall 2021 Annual Groundwater Monitoring Report, Former Carborundum Company, Hyde Park Facility Town of Niagara, Niagara County, NY NYSDEC Site No. 932036

Submitted to:

New York State Department of Environmental Conservation
Division of Hazardous Waste Remediation
270 Michigan Avenue
Buffalo, NY 14203

On behalf of:

Elm Holdings Inc.

Fall 2021 Annual Groundwater Monitoring Report, Former Carborundum Company, Hyde Park Facility Town of Niagara, Niagara County, NY NYSDEC Site No. 932036

Submitted to:

New York State Department of Environmental Conservation
Division of Hazardous Waste Remediation
270 Michigan Avenue
Buffalo, NY 14203

On behalf of:

Elm Holdings Inc.



Prepared By Emily Au, P.G.



Reviewed By Mark T. Becker, P.G.

Contents

1.0 Introduction.....	1-1
2.0 Site Remedial Summary.....	2-1
3.0 Groundwater Monitoring Program Summary.....	3-1
3.1 Groundwater Elevation Measurements	3-1
3.2 Groundwater Sampling.....	3-1
3.3 Data Validation	3-2
4.0 Groundwater Monitoring Program Summary.....	4-1
4.1 Groundwater Elevations and Flow Directions	4-1
4.2 Data Summary.....	4-1
4.2.1 Long-term Bioremediation Results	4-2
4.2.2 CVOC Results	4-2
4.2.3 Attenuation Monitoring Results	4-6
5.0 Conclusions and Recommendations	5-1
6.0 References	6-1

List of Tables

Table 1	Summary of Groundwater Sampling (Fall 2021)
Table 2	Water Level Measurements (Fall 2021)
Table 3	Groundwater Sampling Field Parameter Results (Fall 2021)
Table 4	Summary of Analytical Specifications (Fall 2021)
Table 5	Sample Matrix (Fall 2021)
Table 6	Monitoring Well Groundwater Analytical Result Summary (Fall 2021)

List of Figures

Figure 1	Project Location Plan
Figure 2	Site Plan
Figure 3	Groundwater Contours, Overburden Wells (December 3, 2021)
Figure 4	Groundwater Contours, Bedrock Wells (December 3, 2021)
Figure 5	VOC Concentrations in Overburden Groundwater (2000 - 2021)
Figure 6	VOC Concentrations in Bedrock Groundwater (2000 - 2021)
Figure 7	Long-term Trends of Chlorinated Ethenes in Source Area Overburden and Bedrock Wells
Figure 8	Long-term Trends of Chlorinated Ethenes in Downgradient Overburden and Bedrock Wells

List of Appendices

Appendix A	Groundwater Sampling Logs
Appendix B	Data Usability Summary Report
Appendix C	Monitoring Well Analytical Data Summary, 2007 to 2021
Appendix D	Long-Term Trend Graphs of Chlorinated Ethenes in Monitoring Wells, 2000-2021

1.0 Introduction

This Fall 2021 Annual Groundwater Monitoring Report summarizes the groundwater monitoring activities completed at the Former Carborundum Company, Hyde Park Facility (Site) in the Town of Niagara, New York (see Figure 1 – Project Location Plan). This report provides the results from the recent Fall 2021 annual monitoring event conducted from December 3 through December 8, 2021, with a comparison to previous results. The annual groundwater monitoring is conducted on an alternating spring (even years)/fall (odd years) schedule and includes the collection of groundwater samples for the analysis of chlorinated volatile organic compounds (CVOCs) and natural attenuation parameters.

This work was completed in accordance with the groundwater monitoring work plan (DE&S 2000) for Operable Unit 2 (OU2), approved by the New York State Department of Environmental Conservation (NYSDEC), correspondence from NYSDEC dated September 28, 2005 (NYSDEC 2005), April 8, 2014 (NYSDEC 2014) and October 6, 2018 (NYSDEC 2018), and letters to NYSDEC dated August 20, 2013 (Parsons 2013) and April 3, 2014 (Parsons 2014).

The scope of the Fall 2021 annual groundwater monitoring program included:

- Collection of water level measurements from overburden and bedrock monitoring wells, injection wells, and performance monitoring wells;
- Purging of select overburden and bedrock monitoring wells and collection of field measurements of pH, temperature, specific conductivity, oxidation/reduction potential (ORP), dissolved oxygen (DO), and turbidity;
- Collection of groundwater samples from select overburden and bedrock monitoring wells for specific CVOC analyses; and,
- Collection of groundwater samples from select overburden and bedrock monitoring wells for analysis of natural attenuation parameters to aid in remedial action optimization (RAO) evaluations.

Figure 2 – Site Plan presents monitoring well locations, injection well locations, performance monitoring well locations, and site features.

2.0 Site Remedial Summary

The following section briefly summarizes the remedial work completed at the Site. Primary tasks included excavation and off-site disposal of impacted soil in 1999 and 2002, emulsified vegetable oil substrate injections in 2008, 2009, 2011 and 2013, and associated performance groundwater monitoring events. Terra Systems, Inc. (TSI) SRS®-SD was used for all overburden injections, SRS®-FR was used for all bedrock injections, and TSI-DC® bioaugmentation culture was used for microorganism bioaugmentation. Additional detail regarding Site background and remedial summaries are presented in event-specific performance reports and Five-Year Review Reports.

The following is a timeline of key remedial actions and associated groundwater monitoring:

Task	Start & Completion Date
1999 On-Site Soil (OU1) Interim Remedial Action	
Borehole Investigation and Test-Pit Pre-characterization of Soils	September 1998 – April 1999
Excavation of contaminated onsite soils and verification sampling.	May – August 1999
2000 Off-Site Soil (OU3) Interim Remedial Action	
OU3 Investigation -Extent of Contamination	August 2001
Excavation of contaminated offsite soils, and some remaining onsite soils and verification sampling.	December 2002
Initial Groundwater Monitoring Program (OU2)	
Post-Excavation Groundwater Sampling.	Year 1: October 1999; October 2000; Year 2: May 2001; November 2001; Year 3: May 2002; October 2002; Year 4: May 2003; November 2003; Year 5: May 2004; October 2004; Fall 2005: November 2005 Spring 2006: May 2006

Task	Start & Completion Date
	Fall 2007: October/November 2007 Spring 2008: April 2008
2008 Injection Event	
Baseline Performance Monitoring	August 2008
Overburden Substrate Injection (INJ-1 and INJ-2)	September 4 – 5, 2008
Overburden Bioaugmentation (INJ-1 and INJ-2)	October 21 – 22, 2008
Performance Groundwater Monitoring	October 2008, December 2008, January 2009, March 2009
2009 Injection Event	
Baseline Groundwater Monitoring	October 2009
Bedrock Substrate Injections (INJ-3 and INJ-4)	November 11 – 12, 2009
Overburden Substrate Injections (INJ-1 and INJ-2)	November 17 – 18, 2009
Overburden and Bedrock Bioaugmentation (INJ-1 through INJ-4)	December 17 – 22, 2009
Performance Groundwater Monitoring	December 2009, February 2010, March-April 2010, May 2010, November 2010
2011 Injection Event	
Overburden Injection Well Installation (INJ-5U, INJ-5L, INJ-6U, INJ-6L, INJ-7, INJ-8, INJ-9, INJ-10)	October 6 – 20, 2011
Baseline Sampling	October 20 – November 7, 2011
Overburden Substrate Injections and Bioaugmentation (INJ-1, INJ-2, INJ-5U, INJ-5L, INJ-6U, INJ-6L, INJ-7, INJ-8, INJ-9, INJ-10)	November 11 – December 13, 2011
3-month Performance Sampling	March 12 – 15, 2012
6-month Performance Sampling	June 11 – 18, 2012

Task	Start & Completion Date
12-month Performance Sampling	November 26 – 30, 2012
2013 Injection Event	
Overburden and Bedrock Substrate Injections and Bioaugmentation (INJ-1, INJ-2, INJ-3, INJ-4, MW-16B, MW-18B, INJ-9, INJ-10)	September 9 – October 1, 2013
Tracer Dye Injections (MW-16B, MW-18B)	September 19 – 24, 2013
Tracer Dye Sampling	September 20, 2013 – January 17, 2014
3-month Performance Sampling	January 13 – 20, 2014
6-month Performance Sampling	March 30 – April 3, 2014
12-month Performance Sampling	October 8 – 14, 2014
Annual Groundwater Monitoring Events (OU2)	
Groundwater Sampling (Alternating Spring/Fall)	November 16 – 20, 2015; April 19 – 22, 2016; September 11–14, 2017; April 23 – 26, 2018; June 14, 2018; December 3 – 5, 2019; March 18 – 20, 2020; December 6 – 8, 2021

3.0 Groundwater Monitoring Program Summary

The Fall 2021 annual groundwater monitoring program included water level measurements, groundwater sampling at 17 well locations, and submission of groundwater samples for analysis of CVOs and natural attenuation parameters. Quality assurance/quality control (QA/QC) samples, including one field duplicate, one matrix spike/matrix spike duplicate sample, and three trip blanks were also collected and submitted for analysis. Table 1 presents a summary of groundwater sample locations and associated QA/QC samples.

3.1 Groundwater Elevation Measurements

Water levels were measured on December 3, 2021 in the monitoring wells, injection wells, and performance monitoring wells relative to the top of the inner well casing using an electronic water level tape accurate to 0.01 foot (ft). The depth to water was measured in each well from a surveyed point on the casing. The water levels were then converted to elevations presented as feet above mean sea level (ft AMSL, NAVD 88 datum). The groundwater elevations were used to construct groundwater elevation contour maps in both the overburden and bedrock zones. Table 2 provides a summary of the groundwater level measurements and calculated groundwater elevations. Figure 3 presents overburden groundwater potentiometric surface contours and Figure 4 presents bedrock groundwater potentiometric contours. Section 4.1 presents a discussion of groundwater elevations and flow directions.

3.2 Groundwater Sampling

The locations of the 17 monitoring wells sampled are shown in Figure 2. Wells were sampled following the methodology outlined in the groundwater monitoring work plan and approved revisions per subsequent correspondence with NYSDEC. A list of wells, dates sampled, sample IDs, and purge volumes is provided in Table 1. A copy of the groundwater sampling logs is provided in Appendix A.

During purging, groundwater was monitored for temperature, specific conductivity, pH, DO, ORP, and turbidity. An aliquot of the groundwater sample was tested in the field for alkalinity, carbon dioxide, ferrous iron, and hydrogen sulfide using Hach™ test kits. Table 3 presents a summary of the groundwater sampling field parameter results.

The 17 monitoring wells were purged following low-flow procedures with dedicated tubing and a peristaltic pump. MW-12A was found to be destroyed during the Fall 2019 sampling event and therefore was not sampled. All samples for chemical analyses were hand-delivered to Eurofins TestAmerica Laboratories, Inc., (ETAL) in Amherst, New York under secure chain-of-custody (COC). ETAL Amherst transferred the samples to ETAL, Canton, Ohio which performed the analyses. Both ETAL locations are New York State Department of Health Environmental Laboratory Approval Program certified laboratories.

Table 4 provides a summary of sample collection and analysis specifications for each analysis type including sample containers, preservation methods, analytical methods, and other quality control information.

Table 5 presents a summary of scheduled analyses for each well sampled. Samples from each well were analyzed for select CVOCs, including tetrachloroethene (PCE), trichloroethene (TCE), cis-1,2-dichloroethene (DCE), trans-1,2-DCE, 1,1-DCE, 1,1-dichloroethane (DCA), 1,1,1-trichloroethane (TCA), vinyl chloride (VC), and chloroethane. In addition, samples from 13 wells consisting six overburden and bedrock well pairs and one bedrock well (MW-12B) were analyzed for natural attenuation evaluation parameters, consisting of:

- dissolved iron;
- methane, ethane, and ethene;
- total chloride, sulfate, and sulfide; and,
- total organic carbon (TOC), biological oxygen demand (BOD), chemical oxygen demand (COD), nitrate, and nitrite.

The six well pairs chosen for these additional analyses are located within, upgradient, downgradient, and side gradient of the source area, and consist of MW-5A and -5B, MW-7A and -7B, MW-10A and -10B, MW-16A and -16B, MW-17A and -17B, and MW-18A and -18B. A seventh well pair, MW-12A and MW-12B, has historically also been sampled; but, in Fall 2019 MW-12A was found destroyed and only MW-12B could be sampled in Fall 2019, Spring 2020, and Fall 2021.

Purge water and decontamination water were contained and staged in a secure area onsite in a 300-gallon holding tank for later characterization and proper disposal.

3.3 Data Validation

Analytical results for samples collected December 6 through December 8, 2021 were reviewed by AECOM for usability with respect to the following requirements:

- Work Plan and associated correspondence;
- NYSDEC Analytical Services Protocol (ASP); and,
- USEPA Region II Standard Operating Procedures (SOPs).

The data submitted by the laboratory have been reviewed and validated. The analytical data were found to be acceptable in terms of deliverable completeness, accuracy, precision, representativeness, completeness and comparability. Data validation was performed in accordance with the most current editions of the USEPA Region II SOPs and NYSDEC ASP for organic and inorganic data review.

Analytical holding times, laboratory control sample recoveries, laboratory method blanks, matrix spike/matrix spike duplicate (MS/MSD) precision and accuracy for designated spiked project samples, and surrogate recoveries associated with project samples, were considered acceptable with the following exceptions:

Sample MW-12B was analyzed several times for CVOCs due to instrument failures. Due to the presence of headspace in the vial (due to the multiple analyses) the results may be biased low. Samples MW-18A and TB-120721 were received at the lab with headspace in the vial. The detected results in all these samples have been qualified 'J-' and the non-detect results qualified 'UJ'.

The percent recoveries of the nitrate-nitrite MS/MSD performed on samples MW-10A and MW-10B were below the lower QC limit. The nitrate-nitrite results in these samples have been qualified 'J' or 'UJ'.

Several samples for CVOC analysis were diluted due to foaming and the presence of high concentrations of target compounds. All of these samples had detections for one or more of the target compounds. The reporting limits for the non-detect compounds are elevated due to the dilutions utilized.

All sample analyses were found to be compliant with the method criteria, except where previously noted. Those results qualified 'UJ' (estimated quantitation limit), 'J' (estimated result), or 'J-' (estimated, biased low) during the data review are considered conditionally usable. All other sample results are usable as reported.

A copy of the data usability summary report (DUSR) for groundwater samples is included in Appendix B.

4.0 Groundwater Monitoring Program Summary

4.1 Groundwater Elevations and Flow Directions

A summary of groundwater elevation monitoring data for the Fall 2021 annual event is provided in Table 2, including New York State Plane Coordinate System location coordinates, top of casing elevation, depth to water and calculated groundwater elevations for the monitoring wells, injection wells, and performance monitoring wells.

Figure 3 presents an overburden groundwater contour map based on the December 3, 2021 water level data. Overburden groundwater was measured at elevations between 594.73 ft AMSL (MW-3A) in the northeast portion of the Site to 585.84 ft AMSL (MW-14A) in the southwest corner of the Site. In general, groundwater flow is from northeast to southwest. Overall, overburden groundwater in the central portion of the site exhibited little change in gradient. Gradients and flow directions were more defined in both the northeast and southwest corners of the site.

Figure 4 presents a bedrock groundwater potentiometric surface contour map based on the December 3, 2021 water level data. Bedrock groundwater elevations ranged from 589.64 ft AMSL (MW-4B) on the northwest side of the Site to 587.80 ft AMSL (MW-11B) in the southwest corner of the Site. In the northeast corner of the site, MW-8 with groundwater elevation at 589.59 ft AMSL and MW-19B with groundwater elevation at 589.60 ft AMSL were almost as high as the maximum elevation at MW-4B. The general bedrock groundwater flow direction is southwesterly towards Hyde Park Boulevard and Rhode Island Avenue, consistent with historical observations of groundwater flow. Overall, the gradient is shallow. MW-15 was not measured on December 3, 2021 due to health and safety concerns (traffic and road access in Hyde Park Boulevard); MW-15 was last measured during its most recent 5-year sampling event on June 14, 2018 at 587.31 ft AMSL, consistent with the southwesterly gradient observed on December 3, 2021.

Downward vertical gradients were observed more commonly in overburden/bedrock well pairs in the north, east and central portions of the Site; upward vertical gradients were observed more commonly in well pairs in the south/southwest portion of the Site.

4.2 Data Summary

Groundwater samples collected during the Fall 2021 annual groundwater monitoring program were submitted to the analytical laboratory for select CVOC analysis and other parameters as discussed in Section 3.2 and as summarized on Tables 4 and 5. Field measurements for the sampling program are provided in Table 3. A summary of the Fall 2021 analytical laboratory data is provided in Table 6. Figure 5 presents select CVOC concentrations in overburden groundwater for 2000 and 2009 through 2021 and Figure 6 presents select CVOC concentrations in bedrock groundwater for the same period. Analytical data results from monitoring well samples for the period October 2007 through December 2021 are included in Appendix C.

Comments are noted below for wells where concentrations or trends varied from recent and historical monitoring data.

4.2.1 Long-term Bioremediation Results

Figure 7 and Figure 8 illustrate the long-term time-series plots for total CVOCs at source area and downgradient wells, respectively. In Figure 7 and Figure 8, the overburden and bedrock wells are presented on separate plots for clarity. These plots indicate the improvement in groundwater conditions that has occurred as the result of enhanced bioremediation activities.

In overburden source area wells, MW-7A displayed a CVOC concentration decrease of two orders of magnitude as a result of the enhanced bioremediation injections, but concentrations have increased somewhat since 2016. CVOC concentrations in well MW-16A have fluctuated over time, while concentrations in MW-17A have decreased steadily. Bedrock source area wells, including MW-7B, MW-16B and MW-17B, have generally shown concentration decreases following the enhanced bioremediation injections (Figure 7).

Bioremediation injections from 2008 to 2013 were also intended to decrease total CVOCs in downgradient wells over time. Downgradient wells MW-12B, MW-14B, and MW-15 exhibited slowly decreasing levels of total CVOC concentrations prior to injections, followed by significant decreases of approximately two orders of magnitude relative to pre-2008 total CVOC concentrations. MW-12B has shown some rebounding in total CVOCs in the last few sampling events driven mainly by 1,2-DCE, and VC. MW-13B total CVOC concentrations continue to slowly decrease. (Figure 8).

4.2.2 CVOC Results

Groundwater samples from 17 monitoring wells (6 overburden and 11 bedrock) were collected and analyzed for CVOCs. Overall, concentrations of CVOCs at most of the sample locations have decreased or remained stable since 2000. Over the past few sampling events, there are select locations that have shown a slight increase from post-injection low results for TCE degradation products DCE and/or VC (MW-5B, MW-7A, MW-10B, MW-12B, and MW-16A). The overall total CVOC reductions are due to both natural attenuation and enhanced biodegradation that included four rounds of vegetable oil substrate injections in 2008, 2009, 2011, and 2013.

Appendix D presents graphs of long-term trends for overburden and bedrock wells in the current sampling program. The time-series plots typically show gradual decreasing trends in TCE and DCE, and in some cases, stable trends, followed by significant decreases in concentrations following injection events. Most of these plots show stable VC concentrations prior to the injections, followed by significant decreases after the injections, and a slight increase of DCE degradation product VC in the most recent rounds of sampling in the wells mentioned above.

4.2.2.1 Overburden Results

Figure 5 shows a summary of the overburden well CVOC analytical results from the Fall 2021 annual sampling program, the data from the most recent thirteen previous annual sampling programs, and data from 2000 as a reference point. The results for the six overburden groundwater samples were generally consistent with previous rounds of monitoring and long-term trends. Key observations are listed below.

Overburden Source Area Wells:

The concentration of TCE at MW-7A in Fall 2021 was slightly above groundwater standards¹ and was the first detection of TCE at this location since 2009. However, the concentration is low compared with pre-injection concentrations. Concentrations of DCE and VC at MW-7A were above groundwater standards (Appendices C & D) and also higher than have been detected since the injections, continuing moderate increases of these constituents in the last few years. MW-7A is in an area that exhibited the highest CVOC concentrations in shallow groundwater prior to the first injection and is within the area that was targeted during the emulsified vegetable oil substrate injections in 2008, 2009, 2011 and 2013. MW-7A will continue to be monitored as a part of the annual sampling program.

MW-16A was targeted in the November 2011 injection event to address VC concentrations, but only a negligible amount of substrate was injected due to low permeability of the soils. Concentrations of TCE and DCA have been below groundwater standards since 2007. DCE has been below 10 micrograms per liter (µg/L) since 2012 and remained so in the Fall 2021 results. The VC concentration was lower than the previous year (Spring 2020) when VC was detected at a historical high (Appendices C & D). VC is a degradation product of TCE via DCE. MW-16A will continue to be monitored as a part of the annual sampling program.

MW-17A is an overburden well in the area of targeted bedrock injections in 2009 and 2013. TCE, DCE, VC, and DCA concentrations were consistent with recent historical data. Since 2009, TCE has been reduced to non-detect, DCE (48 µg/L) has steadily decreased to less than one-quarter the 2000 concentration (230 µg/L), while VC (110 µg/L) has increased as compared to its pre-injection concentration (18 µg/L) and has been more stable recently. MW-17A will continue to be monitored as a part of the annual sampling program.

Overburden Downgradient Wells:

MW-5A, located south of the east end of the former facility building, showed sporadic increases and decreases in DCE and VC before and after substrate injections in 2009, 2011, and 2013 (Figure 9). This trend continued in Fall 2021 where concentrations of DCE, VC, and DCA decreased from Spring 2020 but remained within the mid-range of the historical average (Appendices C & D). There appears to be a direct relationship between degradation product concentrations and water level fluctuations in MW-5A. Furthermore, there is a consistent upward hydraulic gradient between the bedrock and overburden zones at this location. MW-5A will continue to be monitored as a part of the annual sampling program.

MW-10A, located central to and south of the former facility building, showed DCE and VC concentrations similar to the previous few sampling events (Appendices C & D). TCE increased slightly to an estimated 13 µg/L, above the groundwater standard (5 µg/L). DCA has been non-detect since 2016. Groundwater elevation measurements indicate an upward hydraulic gradient between MW-10A and MW-10B (from bedrock to overburden), consistent with past results. MW-10A will continue to be monitored as a part of the annual sampling program.

¹ NYSDEC Technical & Operational Guidance Series (1.1.1), Ambient Water Quality Standards and Guidance Values and Groundwater Effluent Limitations and revisions

MW-12A, located west of the former facility building along Hyde Park Boulevard, was found destroyed during the Fall 2019 sampling event and no sample was collected in Fall 2019, Spring 2020, or Fall 2021. Recent historical data are presented on Figure 5 and in Appendices C & D.

MW-18A, located east of the former facility building, showed DCA below groundwater standards consistent with recent events. TCE (23 µg/L) and DCE (43 µg/L) were at similar concentrations as compared to 2010 through 2020 concentrations (Figure 5 and Appendices C & D). MW-18A will continue to be monitored as a part of the annual sampling program.

4.2.2.2 Bedrock Results

Figure 6 shows a summary of the bedrock well CVOC analytical results from the Fall 2021 annual sampling program, data from the most recent thirteen previous annual sampling events, and data from 2000 as a reference point. Key observations are listed below.

Bedrock Source Area Wells:

Significant reductions in DCE and VC concentrations have been observed in MW-6 relative to 2000 concentrations, which were measured prior to bioremediation injections in the area of MW-7A in 2008. Since 2009, DCE has steadily decreased (85 µg/L in 2009 to 13 µg/L in 2021) and is stable compared to the last several sampling events, while VC (98 µg/L in 2021) was at the upper end but within the observed range at this location and again, similar to the previous sampling event. The reduction of DCE to the current result with a generally stable VC concentration indicates natural attenuation is continuing to occur, although the rate of reduction of VC is less than that of DCE. TCE and DCA have consistently been non-detect or detected at an estimated concentration below the groundwater standard since 2000. MW-6 will continue to be monitored as a part of the annual sampling program to monitor progress of attenuation of DCE and VC.

Significant reductions in DCE and VC concentrations have been observed in MW-7B relative to 2000 concentrations, which were measured prior to bioremediation injections in the area of MW-7A in 2008. TCE, and DCA concentrations have been below groundwater standard since 2012. The DCE concentration (1.5 µg/L) was also below standard this round. The VC concentration (18 µg/L) was within the historic range and the same as Spring 2020. MW-7B will continue to be monitored as a part of the annual sampling program to monitor progress of attenuation of VC.

TCE, DCE, and VC concentrations increased at MW-16B in early 2012 and 2013 after injections were performed at overburden injection wells (INJ-6L, INJ-7 and INJ-8) in the vicinity of MW-16A in October 2011. TCE concentrations decreased in 2013 and have remained below groundwater standard since that time. DCE and VC concentrations remained elevated through 2015 and then sharply decreased in 2016, with DCE below groundwater standard and VC only slightly above groundwater standard since 2016. The Fall 2021 results is also only slightly above the VC groundwater standard (Figure 6 and Appendices C & D). MW-16B will continue to be monitored as a part of the annual sampling program to monitor progress of attenuation of VC.

The TCE concentration in MW-17B has been non-detect for more than 10 years except for an estimated value in 2017 (0.68 µg/L). DCE increased to above standard in Fall 2021 (31 µg/L) (Figure 6). The VC concentration decreased over the course of the bioremediation injections from 69 µg/L in 2000 to 0.88 µg/L in April 2016 but increased to 20 µg/L in Fall 2021. MW-17B is located within the area of the bedrock bioremediation injections performed in November 2009 and September 2013 and was the

location of the highest CVOs in bedrock prior to bioremediation activities. MW-17B will continue to be monitored as part of the annual sampling program to monitor progress of attenuation of VC.

MW-19B is located east of the main facility in the area remediated as part of Operable Unit 1. Concentrations of TCE and DCA have been below groundwater standards from 2012 through 2021. Concentrations of DCE and VC showed a decrease relative to Spring 2020 and have been relatively stable for the last 5 years. Based on its location and history of low, stable concentrations, MW-19B will be evaluated regarding continued inclusion in the annual sampling program.

Bedrock Downgradient Wells:

At MW-5B, TCE has consistently been non-detect or detected at an estimated concentration near the reporting limit since 2000, indicating this area is not a source area for TCE. Total concentrations of DCE and VC have remained relatively constant since 2009, with a slightly decreasing trend of DCE accompanied by an increasing trend of VC, indicating ongoing reductive dechlorination (Appendices C & D). In Fall 2021 DCE increased slightly to 40 µg/L and VC increased as well to 140 µg/L. MW-5B will continue to be monitored as a part of the annual sampling program.

At MW-10B, TCE has consistently been non-detect since 2009, indicating this area is not a source area for TCE. In addition, DCA has consistently been non-detect or detected at a concentration near the reporting limit and below groundwater standard since 2000. DCE and VC concentrations have remained relatively constant since 2009 (Appendices C & D). VC increased in Fall 2021 to 370 µg/L, one of the highest results recorded. MW-10B will continue to be monitored as a part of the annual sampling program.

At downgradient location MW-12B, TCE has consistently been non-detect or detected at an estimated concentration near the reporting limit since 2000, indicating this area is not a source area for TCE. In addition, DCA has consistently been non-detect or detected at a concentration near the reporting limit and below groundwater standard since 2000. Significant reductions in DCE and VC concentrations have been observed in MW-12B relative to concentrations measured prior to bioremediation injections in the vicinity of MW-17B in 2009. Concentrations of DCE and VC increased following injections in the vicinity of MW-17B in 2013 and have remained relatively stable since (Appendices C & D). MW-12B will continue to be monitored as a part of the annual sampling program to monitor attenuation of DCE and VC.

TCE, DCE, and VC concentrations in downgradient well MW-13B have steadily decreased since prior to the bioremediation injections (Figure 8 and Appendices C & D). Including Fall 2021 data, DCE concentrations have been fluctuating slightly above the groundwater standard since the injections. In Fall 2021 the DCE concentration of 3.7 µg/L was below the standard (5 µg/L). The VC concentration remains slightly above groundwater standard for Fall 2021 (6.4 µg/L), but below pre-injection levels. MW-13B will continue to be monitored as part of the annual sampling program.

Significant reductions in TCE, DCE, and VC concentrations have also been observed in downgradient well MW-14B relative to concentrations measured prior to bioremediation injections (Figure 8 and Appendices C & D). Including Fall 2021 data, TCE, DCE, and DCA concentrations have been below groundwater standards since 2011. VC concentrations had been below groundwater standards since August 2013, except for a September 2017 VC concentration of 2.9 µg/L; the VC concentration in Fall 2021 (1.9 µg/L) was slightly below groundwater standard. It is recommended that MW-14B continue to be monitored as part of the annual sampling program to monitor for perimeter concentrations of constituents of concern.

MW-15 is currently sampled every five years. The well was last sampled on June 14, 2018. Consistent with prior results, TCE and DCA concentrations were below groundwater standard. DCE and VC concentrations increased above groundwater standards (5.2 µg/L for DCE and 16 µg/L for VC), similar to May 2010 concentrations.

At MW-18B, TCE and DCA have consistently been non-detect at the reporting limit since 2009. DCE and VC concentrations have fluctuated since 2009, with historical lows occurring in October 2014 following enhanced bioremediation injections at MW-18B in September 2013. DCE and VC showed increases in April 2016 and September 2017, followed by decreases through Spring 2020. In Fall 2021 both increased slightly but are still within the range of the past 5 years (47 µg/L DCE and 80 µg/L VC) (Appendices C & D). MW-18B will continue to be monitored as a part of the annual sampling program to monitor progress of attenuation of DCE and VC.

4.2.3 Attenuation Monitoring Results

As part of the ongoing groundwater sampling program, natural attenuation parameters have been sampled during each monitoring event (see Table 5 and Appendix C). The results for Fall 2021 were generally consistent with previous monitoring events, with the following exceptions:

- TOC concentrations decreased in several wells from 2016 through 2021. These decreases are in areas targeted during the 2013 injections and represent continued depletion of the injected carbon substrate. TOC decreases over this period are observed in overburden wells including MW-7A, and MW-16A, and bedrock wells MW-7B, MW-16B, MW-18B with all values similar to last year's results. TOC concentrations in these wells have decreased to the point where they are near pre-injection concentrations.
- Decreases in BOD and COD levels were observed in wells (MW-4A, MW-7A, MW-16A, MW-17A, MW-7B, MW-16B, MW-17B, and MW-18B) following injections. Similar to TOC, this may represent continued depletion of the 2013 injectate. In Fall 2021, MW-10B, MW-12B, MW-16A, MW-17A, and MW-18A saw moderate increases to COD.
- From 2016 through 2021, chloride concentrations decreased in overburden wells MW-7A, MW-10A, MW-17A, MW-18A, and bedrock well MW-17B. Since chloride is produced during reductive dichlorination of CVOs, this may indicate that anaerobic biodegradation processes are ongoing, but may be slowing to pre-injection rates in the areas targeted during the 2013 injections. Chloride in these and other wells have remained fairly stable over the last few sampling rounds. The presence of chloride in several other wells suggests biodegradation is ongoing.
- Ethene is the final degradation product of TCE, providing solid evidence of substantial biodegradation. From 2014 to 2015, increases in ethene concentrations at wells MW-10B, MW-16A, and MW-16B were noted. Ethene concentrations for MW-10B, MW-16A, and MW-16B in 2016 through 2021 are noted to be lower in each location as compared to 2015 levels; although, MW-16A increased in 2020 to 270 µg/L, it decreased in 2021 to 77 µg/L and coincides with a decrease in VC when compared to the 2020 result. Several wells had ethene concentrations that were either stable or fluctuated somewhat following the injections. The presence of ethene is an indication that biodegradation through VC is continuing.
- Elevated methane concentrations (>20 mg/L) were noted in several wells following the site injections, indicating an environment conducive to anaerobic biodegradation. As of 2021, only MW-17B is above 20 mg/L. MW-7A, MW-16B, MW-17A, and MW-18B all are currently less

than 20 mg/L but still elevated since the injections. MW-18A methane concentrations increased two orders of magnitude in 2021 for the first time since the injections.

Overall, the environmental conditions and Site-wide long-term changes in concentrations indicate that the enhanced biodegradation program has been effective and natural attenuation is an ongoing, active process.

5.0 Conclusions and Recommendations

The following conclusions and recommendations were developed following the Fall 2021 groundwater monitoring event:

Conclusions:

CVOC concentrations have steadily declined in the overburden and bedrock groundwater over the past 21 years, with more recent substantial declines related to the 2008, 2009, 2011, and 2013 bioremediation injections.

MW-7A, located in the area of the vegetable oil substrate injections conducted in September 2008, November 2009, November 2011, and September 2013, continued to show decreased levels of CVOCs compared to pre-injection levels, with some increases in degradation products 1,2-DCE, and VC this round. VC is also gradually increasing or stable in other wells (i.e., MW-6, MW 10A/B, MW-16A, MW-17A). Fluctuations in concentrations of CVOC degradation products at MW-5A appear to have a direct relationship with water level fluctuations and are consistent with historical concentrations following substrate injections. Overall, overburden groundwater CVOC concentrations in 2021 were generally consistent with the previous sampling program results.

Bedrock groundwater CVOC concentrations generally showed declines in response to the previous substrate injections. Notably, CVOC concentrations decreased substantially in several downgradient bedrock monitoring wells since 2009. TCE was non-detect in all bedrock wells sampled. This trend will continue to be monitored.

Groundwater samples for natural attenuation monitoring have been collected since October 2000 and continue to indicate that natural attenuation processes are active. The results for Fall 2021 were generally consistent with recent monitoring events.

Natural anaerobic biodegradation of TCE, which was occurring at the Site prior to 2008, was substantially enhanced by the bioremediation injection program conducted over multiple years. The enhanced bioremediation injections effectively contributed to the observed decreasing concentration trends, and ongoing natural attenuation processes continue to improve groundwater quality at the Site.

Recommendations:

The annual groundwater monitoring program should be continued, although it is recommended that well MW-19B be eliminated from the monitoring program as CVOC concentrations there have remained low and stable for several years. Based on its location and contaminant history, the data obtained from MW-19B indicates remedial actions in the area of the well have created an improved and stable CVOC environment and does not benefit the monitoring program. . At present, CVOCs within the source area and downgradient of that area have decreased as a result of remedial measures including emulsified vegetable oil substrate injections in 2008, 2009, 2011 and 2013. Terra Systems, Inc. (TSI) SRS®-SD was used for all overburden injections, SRS®-FR was used for all bedrock injections, and TSI-DC® bioaugmentation culture was used for microorganism bioaugmentation. The substrate and bioaugmentation injections have been successful in decreasing levels of chlorinated VOCs in both

overburden and bedrock groundwater in the injection areas. Due largely to flow in bedrock fractures, the CVOC decreases have also been observed downgradient of the injection areas and in offsite wells, and to date, offsite CVOC concentrations have not rebounded. The remedial goal stated in the OU-2 Record of Decision is to "Reduce, to the extent practicable, off-site migration of groundwater that does not attain NYSDEC Class GA Ambient Water Quality Criteria." Since off-site VOC concentrations have been reduced to below or near the NYSDEC Class GA Ambient Water Quality Standards, this goal has been attained. If, in the future, downgradient and/or offsite VOC levels increase to pre-injection levels, the need will re-evaluate the need for additional injections will be re-evaluated. A Site Management Plan (SMP) for the Hyde Park Site is in preparation. The SMP may include proposals for alterations to the existing monitoring program.

6.0 References

- AECOM, 2021a. Five-Year Review Report (2016 to 2020), Former Carborundum Company, Hyde Park Facility, Town of Niagara, Niagara County, NY, NYSDEC Site No. 932036. March 2021.
- AECOM, 2021b. Site Management Periodic Review Report and IC/EC Certification for period July 31, 2018 to July 31, 2021, Former Carborundum Company, Hyde Park Facility, Town of Niagara, Niagara County, NY, NYSDEC Site No. 932036. August 2021.
- DE&S, 2000. Groundwater Monitoring Work Plan for the Former Carborundum Company – Electric Products Division, Hyde Park Facility, Town of Niagara, Niagara County, New York, Site No. 932036, Final Document. Duke Engineering & Services, January 2000.
- NYSDEC, 1998. Division of Water Technical Guidance Series (1.1.1). Ambient Water Quality Standards and Guidance Values and Groundwater Effluent Limitations. New York State Department of Environmental Conservation. June 1998.
- NYSDEC, 2005. Letter to Mr. William Barber (BP) from Michael Hinton (NYSDEC) re: Carborundum Global Site No. 932036, Town of Niagara, Niagara County, New York. Summary Report for the Fifth Year of the Groundwater Monitoring Program. NYSDEC, September 28, 2005.
- NYSDEC, 2000. Record of Decision, Carborundum Global Site, Town of Niagara, Niagara County, Site Number 9-32-036, Operable Units One and Two. October 2000
- NYSDEC, 2014. Letter to Mr. William Barber (BP) from Michael Hinton (NYSDEC) re: Carborundum Global Site No. 932036, Town of Niagara, Niagara County, New York. Proposed Revision to Annual Sampling MW-15. NYSDEC, April 8, 2014.
- NYSDEC, 2018. Letter to Mr. Randy Coil (BP) from Brian Sadowski (NYSDEC) Site Management (SM) Periodic Review Report (PRR) Response Letter Carborundum Company, Global, Niagara, Niagara County, Site No.: 932036. NYSDEC, October 16, 2018. Parsons, 2013. Letter to NYSDEC regarding modifications to the Fall 2013 monitoring event. August 20, 2013.
- Parsons, 2014. Letter to NYSDEC regarding Proposed Revision to Annual Sampling- MW-15. April 3, 2014.

Tables

Table 1
Summary of Groundwater Sampling
Fall 2021 Monitoring Event
Former Carborundum Company, Hyde Park Facility
Niagara, New York

Well ID	Date Sampled	Sample ID	Volume Purged (gallons)
MW-5A	6-Dec-21	MW-5A	4.5
MW-5B	6-Dec-21	MW-5B	5.0
MW-6	8-Dec-21	MW-6	4.5
MW-7A	8-Dec-21	MW-7A	4.5
MW-7B	8-Dec-21	MW-7B	5.0
MW-10A	6-Dec-21	MW-10A	4.0
MW-10B	6-Dec-21	MW-10B	7.5
MW-12A ⁽²⁾	NA	NA	NA
MW-12B	7-Dec-21	MW-12B	10.0
MW-13B	6-Dec-21	MW-13B	4.0
MW-14B	7-Dec-21	MW-14B	4.5
MW-15 ⁽¹⁾	NA	NA	NA
MW-16A	7-Dec-21	MW-16A	2.5
MW-16B	7-Dec-21	MW-16B	4.5
MW-17A	8-Dec-21	MW-17A	5.0
MW-17B	8-Dec-21	MW-17B	8.0
MW-18A	7-Dec-21	MW-18A	4.0
MW-18B	7-Dec-21	MW-18B	4.5
MW-19B	7-Dec-21	MW-19B	7.5

Note:

(1) MW-15 is to be sampled every 5 years in accordance with NYSDEC approval on April 8, 2014, and is to be sampled next in 2023.

(2) During the Fall 2019 sampling event, it was discovered that well MW-12A well has been destroyed.

(3) Duplicate_120621 is a field duplicate of MW-5B.

MS - Matrix Spike

MSD - Matrix Spike Duplicate

NA - Not Applicable (see Notes 1 & 2)

Table 2
Water Level Measurements
Fall 2021 Monitoring Event
Former Carborundum Company, Hyde Park Facility
Niagara, New York

Well ID	Elevation Top of Casing	Easting	Northing	12/3/2021	
				Depth to Water	Groundwater Elevation
PMW-1	596.62	1028372.30	1136886.30	7.25	589.37
PMW-2	595.98	1028371.76	1136875.49	6.19	589.79
PMW-3	596.59	1028379.73	1136882.30	6.46	590.13
PMW-4	597.05	1028384.66	1136909.84	7.41	589.64
PMW-5	592.65	1028308.62	1136764.72	3.61	589.04
PMW-6	592.44	1028310.46	1136747.77	4.12	588.32
PMW-7	592.93	1028325.51	1136758.05	4.49	588.44
PMW-8	593.11	1028352.65	1136824.51	4.41	588.70
PMW-9	592.45	1028282.58	1136689.24	3.80	588.65
INJ-1	596.66	1028382.45	1136887.25	6.84	589.82
INJ-2	595.89	1028374.60	1136890.69	6.75	589.14
INJ-3	592.87	1028313.28	1136774.48	4.21	588.66
INJ-4	593.26	1028332.65	1136771.29	4.39	588.87
INJ-5U	596.08	1028365.66	1136878.92	7.16	588.92
INJ-5L	596.00	1028365.66	1136878.92	5.64	590.36
INJ-6U	596.96	1028376.98	1136868.99	5.78	591.18
INJ-6L	595.97	1028376.98	1136868.99	6.95	589.02
INJ-7	592.76	1028409.44	1136837.46	2.43	590.33
INJ-8	592.98	1028418.16	1136832.59	3.78	589.20
INJ-9	591.62	1028023.50	1136898.15	3.29	588.33
INJ-10	591.49	1028032.17	1136890.90	1.41	590.08
MW-1A	597.56	1028606.44	1136554.99	7.89	589.67
MW-1B	597.64	1028611.01	1136554.66	8.09	589.55
MW-2A	595.73	1028335.27	1136881.61	5.21	590.52
MW-2B	595.80	1028337.09	1136888.34	7.03	588.77
MW-3A	599.94	1028627.22	1136895.86	5.21	594.73
MW-3B	599.70	1028624.57	1136899.80	10.38	589.32
MW-4A	591.60	1028027.77	1136890.77	3.19	588.41
MW-4B	591.49	1028023.72	1136890.65	1.85	589.64
MW-5A	597.91	1028256.93	1136567.66	9.69	588.22
MW-5B	597.79	1028256.86	1136562.36	9.25	588.54
MW-6	595.51	1028293.24	1136889.98	6.84	588.67
MW-7A	596.59	1028379.67	1136889.32	6.56	590.03
MW-7B	596.66	1028377.01	1136884.33	7.49	589.17
MW-8	599.63	1028584.29	1136897.91	10.04	589.59
MW-10A	596.87	1028134.19	1136571.96	8.82	588.05
MW-10B	596.71	1028129.79	1136571.87	8.19	588.52
MW-11A	595.48	1027992.43	1136576.28	8.07	587.41
MW-11B	595.57	1027996.44	1136575.71	7.77	587.80

Table 2
Water Level Measurements
Fall 2021 Monitoring Event
Former Carborundum Company, Hyde Park Facility
Niagara, New York

Well ID	Elevation Top of Casing	Easting	Northing	12/3/2021	
				Depth to Water	Groundwater Elevation
MW-12A ¹	590.79	1027887.31	1136654.88	NA	NA
MW-12B	590.89	1027886.62	1136658.22	2.31	588.58
MW-13A	595.18	1028202.92	1136517.75	7.09	588.09
MW-13B	594.73	1028199.59	1136517.64	6.62	588.11
MW-14A	592.97	1027954.11	1136524.76	7.13	585.84
MW-14B	592.85	1027951.17	1136524.55	4.49	588.36
MW-15 ²	591.44	1027851.99	1136475.97	NA	NA
MW-16A	591.64	1028415.02	1136829.41	2.59	589.05
MW-16B	592.38	1028414.66	1136826.44	2.78	589.60
MW-17A	593.13	1028319.92	1136765.00	2.99	590.14
MW-17B	592.92	1028319.47	1136763.41	4.21	588.71
MW-18A	593.78	1028377.39	1136661.13	4.71	589.07
MW-18B	593.43	1028375.07	1136659.79	4.77	588.66
MW-19A	594.95	1028610.90	1136747.48	5.09	589.86
MW-19B	594.65	1028611.64	1136749.89	5.05	589.60

Note:

NA - Not Available.

1. Well MW-12A discovered destroyed during Fall 2019 sampling event.
2. MW-15 is to be sampled every 5 years in accordance with NYSDEC approval on April 8, 2014 and is to be sampled next in 2023. A water level will be obtained at that time.

Table 3
Groundwater Sampling Field Parameter Results
Fall 2021 Sampling Event
Former Carborundum Company, Hyde Park Facility
Niagara, New York

Monitoring Well ID	Sample Date	Temperature (deg C)	Specific Conductivity (mS/cm)	Dissolved Oxygen ⁺ (mg/L)	pH (standard units)	ORP (mV)	Turbidity (NTU)	Alkalinity (mg/L)	Carbon Dioxide (mg/L)	Ferrous Iron (mg/L)	Hydrogen Sulfide (mg/L)
MW-5A	12/6/2021	14.4	0.751	1.20	7.49	124.0	10.00	160	25	0.02	0.0
MW-5B	12/6/2021	12.9	1.080	0.58	7.71	-66.4	52.23	360	35	0.20	5.0
MW-6	12/8/2021	12.0	1.615	0.74	7.09	-221.2	2.80	300	25	0.01	0.5
MW-7A	12/8/2021	12.5	1.178	0.71	6.85	-216.8	23.91	625	55	1.25	0.7
MW-7B	12/8/2021	11.8	1.627	0.73	7.07	-206.8	2.14	340	25	0.00	1.0
MW-10A	12/6/2021	13.7	1.351	0.72	7.63	-75.3	7.25	320	40	1.32	0.0
MW-10B	12/6/2021	12.7	1.311	0.68	7.42	-129.5	1.28	360	50	0.36	0.3
MW-12A	Well Destroyed										
MW-12B	12/7/2021	11.9	1.546	0.69	7.11	-139.2	1.94	180	15	0.01	0.0
MW-13B	12/6/2021	9.8	1.736	7.55	7.28	136.9	63.12	160	20	0.13	0.0
MW-14B	12/7/2021	12.6	1.557	0.70	7.15	-214.8	9.86	300	35	0.04	1.0
MW-16A	12/7/2021	12.4	2.645	3.43	6.96	97.2	8.47	460	50	0.00	0.0
MW-16B	12/7/2021	12.1	1.318	0.65	7.10	-261.4	0.84	380	35	0.15	0.3
MW-17A	12/8/2021	13.9	0.804	0.25	7.60	-120.8	10.93	420	20	0.56	0.0
MW-17B	12/8/2021	13.0	1.536	0.17	6.55	-309.8	99.94	485	45	0.69	>5.0
MW-18A	12/7/2021	12.6	0.962	0.25	7.22	-71.4	22.52	360	40	1.44	0.0
MW-18B	12/7/2021	12.4	0.918	0.29	6.85	-298.4	9.64	380	45	0.27	5.0
MW-19B	12/7/2021	11.8	1.445	0.24	7.12	-288.9	14.88	340	25	0.10	2.0

Notes:

- Not Measured

+ Elevated dissolved oxygen readings in some cases conflict with negative oxidation/reduction potential readings.

mS/cm - milliSiemen per centimeter

mg/L - milligram per liter

mV - millivolt

NTU - nephelometric turbidity unit

ORP - oxidation-reduction potential

Table 4
Summary of Analytical Specifications
Fall 2021 Monitoring Event
Former Carborundum Company, Hyde Park Facility
Niagara, New York

Sample Type	Container Type	Sample Volume	Preservation Method	Max. Holding Time	Analytical Method
Constituents of Concern					
Select VOCs	40 mL glass vial with septum top	3x40 mL	Hydrochloric acid, Cool 4°C	14 days	SW846 Method 8260C
Natural Attenuation Parameters					
Methane, Ethene, Ethane, Propane ¹	40 mL glass vial with septum top	3x40 mL	Hydrochloric acid, Cool 4°C	14 days	USEPA RSK175
TOC	40 mL glass vial with septum top	2x40 mL	Sulfuric acid, Cool 4°C	28 days	USEPA 5310C
BOD	1000 mL plastic	1000 mL	None, Cool 4°C	48 hours	USEPA 5120B
COD	250 mL plastic	250 mL	Sulfuric Acid, Cool 4°C	28 days	USEPA 410.4
Dissolved Iron	500 mL plastic	500 mL	Nitric Acid, Cool 4°C	6 months	USEPA 6010C
Chloride, Sulfate; Nitrate, Nitrite	500 mL plastic	500 mL	None, Cool 4°C	28 days; 48 hours	USEPA 300.0 USEPA 353.2
Sulfide	500 mL plastic	500 mL	Sodium hydroxide and zinc acetate, Cool 4°C	7 days	Standard Method (SM) 4500-S2

Notes:

1. The laboratory did not run propane in Fall 2021.

VOC - volatile organic compound

TOC - total organic carbon

BOD - biological oxygen demand

COD - chemical oxygen demand

mL - milliliter

Table 5
Sample Matrix
Fall 2021 Monitoring Event
Former Carborundum Company, Hyde Park Facility
Niagara, New York

Location	Unit	VOCs ^{A/} (SW8260C)	Methane, Ethene, Ethene (RSKSOP- 175mod) ^{(2) B/}	Chloride, Sulfate (300.0)	Total Organic Carbon (5310C)	BOD (5120B), COD (410.4)	Dissolved Iron (6010C)	Nitrate (353.2), Nitrite (353.2)	Sulfide (SM 4500-S2)	Well Head Analysis ^{C/}	Field Analyses (Hach kits) ^{D/}
Existing Site Investigation Monitoring Wells											
MW-5A	overburden	1	1	1	1	1	1	1	1	1	1
MW-5B	bedrock	1	1	1	1	1	1	1	1	1	1
MW-6	bedrock	1								1	1
MW-7A	overburden	1	1	1	1	1	1	1	1	1	1
MW-7B	bedrock	1	1	1	1	1	1	1	1	1	1
MW-10A	overburden	1	1	1	1	1	1	1	1	1	1
MW-10B	bedrock	1	1	1	1	1	1	1	1	1	1
MW-12A	overburden	Well Destroyed									
MW-12B	bedrock	1	1	1	1	1	1	1	1	1	1
MW-13B	bedrock	1								1	1
MW-14B	bedrock	1								1	1
MW-15 ⁽¹⁾	bedrock										
MW-16A	overburden	1	1	1	1	1	1	1	1	1	1
MW-16B	bedrock	1	1	1	1	1	1	1	1	1	1
MW-17A	overburden	1	1	1	1	1	1	1	1	1	1
MW-17B	bedrock	1	1	1	1	1	1	1	1	1	1
MW-18A	overburden	1	1	1	1	1	1	1	1	1	1
MW-18B	bedrock	1	1	1	1	1	1	1	1	1	1
MW-19B	bedrock	1								1	1

QA/QC

Matrix spike/matrix spike duplicate pairs and field duplicates were collected at a rate of 5%.

Name field duplicates blind, using FD followed by the date followed by the matrix and a numerical identifier in sequence for each duplicate sample collected for that day (e.g., FD-GW-060322).

Notes:

(1) MW-15 to be sampled every 5 years as approved by DEC in April 2014. Next sample event is in 2023.

Sampling for MW-15 requires permit from the Department of Transportation (DOT), Niagara County Residency (716) 438-2396.

(2) The sample set has historically included propane; however, the laboratory did not run propane in Fall 2021.

^{A/} VOCs (volatile organic compounds): tetrachloroethene, trichloroethene, cis-1,2-dichloroethene, trans-1,2- dichloroethene, 1,1-dichloroethene, 1,1-dichloroethane, 1-1-1-trichloroethane, vinyl chloride, and chloroethane.

^{B/} Analytical method for dissolved gases will be a laboratory-specific standard operating procedure (RSK-175).

^{C/} Well head analyses include dissolved oxygen, oxidation-reduction potential, pH, temperature, electrical conductivity, turbidity and visual appearance.

^{D/} Field analyses include alkalinity, carbon dioxide, hydrogen sulfide, and ferrous iron.

BOD - biological oxygen demand

COD - chemical oxygen demand

Table 6
Monitoring Well Groundwater Analytical Result Summary - Fall 2021
Former Carborundum Company, Hyde Park Facility
Niagara, New York

Parameter	Criteria ⁽¹⁾	MW- 5A	MW- 5B	MW- 6	MW- 7A	MW- 7B	MW-10A	MW-10B	MW-12B	MW-13B
Volatiles Organic Compounds										
PCE (µg/L)	5	1.0 U	2.0 U	2.0 U	4.0 U	1.0 U	25 U	10 U	1.0 UJ	2.0 U
TCE (µg/L)	5	1.0 U	2.0 U	2.0 U	7.3	1.0 U	13 J	10 U	1.0 UJ	2.0 U
Cis-1,2-DCE (µg/L)	5	52	40	13	150	1.5	650	220	73 J-	3.7
Trans-1,2-DCE (µg/L)	5	1.0 U	2.0 U	2.0 U	4.0 U	1.0 U	25 U	10 U	1.0 UJ	2.0 U
1,1-DCE (µg/L)	5	1.0 U	2.0 U	2.0 U	4.0 U	1.0 U	25 U	10 U	1.0 UJ	2.0 U
Vinyl Chloride (µg/L)	2	62	140	98	150	18	180	370	49 DJ-	6.4
1,1,1-Trichloroethane (µg/L)	5	1.0 U	2.0 U	2.0 U	4.0 U	1.0 U	25 U	10 U	1.0 UJ	2.0 U
1,1-Dichloroethane (µg/L)	5	1	2.0 U	2.0 U	90	1.0 U	25 U	10 U	0.4 J-	2.0 U
Chloroethane (µg/L)	5	0.60 J	2.0 U	2.0 U	16	1.0 U	25 U	10 U	1.0 UJ	2.0 U
Dissolved Metals										
Dissolved Iron (mg/L)	--	0.05 U	0.24	NA	1.5	0.05 U	1.4	0.33	0.048 J	NA
Dissolved Gases										
Ethane (µg/L)	--	7.2 J	7.5 U	NA	170 U	7.5 U	7.5 U	170 U	7.5 U	NA
Ethene (µg/L)	--	7.1	2.4 J	NA	150 U	7.0 U	14	150 U	4.1 J	NA
Methane (µg/L)	--	470	300	NA	13000	160	880	1900	330	NA
Miscellaneous Parameters										
BOD (mg/L)	--	2.0 U	2.0 U	NA	7.9	2.0 U	2.0 U	2.0 U	2.0 U	NA
COD (mg/L)	--	17	35	NA	36	10 U	26	40	100	NA
TOC (mg/L)	--	1.5	4.5	NA	14	4.6	2	4.6	6.3	NA
Chloride (mg/L)	250	76	120	NA	14	240	220	140	77	NA
Sulfate (mg/L)	250	87	230	NA	89	200	150	220	72	NA
Sulfide (mg/L)	0.05	1.0 U	1.0 U	NA	0.8 J	0.8 J	1.0 U	1.0 U	1.0 U	NA
Nitrate (mg/L)	10	0.47	0.25 U	NA	0.25 U	0.25 U	0.25 U	0.25 U	0.24	NA
Nitrite (mg/L)	1	0.10 U	0.25 U	NA	0.25 U	0.25 U	0.25 U	0.25 U	0.050 U	NA
Nitrate-Nitrite (mg/L)		0.050 U	0.050 U	NA	0.050 U	0.050 U	0.050 UJ	0.25 J	0.23	NA

See Page 2 of 2 for notes.

Table 6
Monitoring Well Groundwater Analytical Result Summary - Fall 2021
Former Carborundum Company, Hyde Park Facility
Niagara, New York

Parameter	Criteria ⁽¹⁾	MW-14B	MW-16A	MW-16B	MW-17A	MW-17B	MW-18A	MW-18B	MW-19B	MW-5B (Duplicate)
Volatile Organic Compounds										
PCE (µg/L)	5	1.0 U	5.0 U	1.0 U	4.0 U	4.0 U	1.0 UJ	2.0 U	1.0 U	2.0 U
TCE (µg/L)	5	1.0 U	5.0 U	1.0 U	4.0 U	4.0 U	23 J-	2.0 U	1.0 U	2.0 U
Cis-1,2-DCE (µg/L)	5	1.0 U	8.2	2.1	48	31	43 J-	47	1.8	39
Trans-1,2-DCE (µg/L)	5	1.0 U	5.0 U	1.0 U	4.0 U	4.0 U	1.0 UJ	2.0 U	1.0 U	2.0 U
1,1-DCE (µg/L)	5	1.0 U	5.0 U	1.0 U	4.0 U	4.0 U	0.49 J-	2.0 U	1.0 U	2.0 U
Vinyl Chloride (µg/L)	2	1.9	260	6.5	110	20	2.3 J-	80	1.5	130
1,1,1-Trichloroethane (µg/L)	5	1.0 U	5.0 U	1.0 U	4.0 U	4.0 U	1.0 UJ	2.0 U	1.0 U	2.0 U
1,1-Dichloroethane (µg/L)	5	1.0 U	5.0 U	1.0 U	13	7.3	3.3 J-	2.0 U	1.0 U	2.0 U
Chloroethane (µg/L)	5	1.0 U	5.0 U	1.0 U	4.0 U	2.9 J	1.0 UJ	2.0 U	1.0 U	2.0 U
Dissolved Metals										
Dissolved Iron (mg/L)	--	NA	0.024 J	0.54	0.69	0.94	1.4	0.32	NA	0.22
Dissolved Gases										
Ethane (µg/L)	--	NA	7.5 U	170 U	9.4	170 U	7.5 U	170 U	NA	7.5 U
Ethene (µg/L)	--	NA	77	150 U	14	150 U	7.0 U	150 U	NA	2.4 J
Methane (µg/L)	--	NA	160	8000	12000	26000	4000	13000	NA	300
Miscellaneous Parameters										
BOD (mg/L)	--	NA	2.0 U	6.4	6.0 U	16	2.0 U	14	NA	2.0 U
COD (mg/L)	--	NA	52	16	52	13	45	39	NA	33
TOC (mg/L)	--	NA	11	7.2	4.1	12	2.2	6	NA	4.6
Chloride (mg/L)	250	NA	190	130	32	130	53	98	NA	120
Sulfate (mg/L)	250	NA	930	230	55	90	120	190	NA	230
Sulfide (mg/L)	0.05	NA	1.0 U	4.8	1.0 U	5.6	1.0 U	8	NA	1.0 U
Nitrate (mg/L)	10	NA	0.42	0.050 U	0.25 U	0.25 U	0.050 U	0.050 U	NA	0.25 U
Nitrite (mg/L) ²	1	NA	0.050 U	0.050 U	0.25 U	0.25 U	0.050 U	0.050 U	NA	0.25 U
Nitrate-Nitrite (mg/L)		NA	0.22	0.050 U	0.050 U	0.034 J	0.050 U	0.029 J	NA	0.050 U

Notes:

(1) NYSDEC TOGS (1.1.1), Ambient Water Quality Standards and Guidance Values and Groundwater Effluent Limitations, April 2000, Glass GA.

(2) Bold concentrations exceed criteria.

J = The reported concentration is an estimated value.

J- = The reported concentration is an estimated value biased low.

D = Result reported from a secondary dilution analysis.

U = Not detected above the reporting limit.

UJ = Not detected. The reporting limit is an estimated value.

NA = Not Analyzed

µg/L - micrograms per liter

mg/L - milligrams per liter

PCE - tetrachlorethene

TCE - trichloroethene


DCE - dichloroethene

BOD - biological oxygen demand

COD - chemical oxygen demand

TOC - total organic carbon

Figures



Source: USGS The National Map Service;
1:24,000-scale USGS Topographic Map,
Lewiston, 2019
Niagara Falls, 2019

2,000 0 2,000 Feet

New York



AECOM


FORMER CARBORUNDUM COMPANY
TOWN OF NIAGARA, NEW YORK
SITE LOCATION

FIGURE 1


J:\Projects\60481767_BP\PMISC\GIS\Hyde Park Maps\SITE PLAN.mxd 10/26/2017



J:\Projects\60481767_BP\PM\GIS\Hyde Park\Maps\2021\GROUNDWATER CONTOURS - OVERBURDEN.mxd 12/7/2021



J:\Projects\60481767_BPI\PMISC\GIS\Hyde Park\Maps\2021\GROUNDWATER CONTOURS - BEDROCK.mxd 12/7/2021



J:\Projects\60481767_BPIDO\MISC\GIS\Hyde Park\Maps\2021\GROUNDWATER VOC - BEDROCK.mxd 2/7/2022



MW-7B	2000	Oct-09	May-10	Oct-11	Jun-12	Aug-13	Apr-14	Nov-15	Apr-16	Sep-17	Apr-17	Dec-19	Mar-20	Dec-21
TCE	5 U	1 U	1 U	1 U	1 U	1 U	0.5 U	0.5 U	0.5 U	0.33 U	0.33 U	0.10 U	0.10 U	0.46 U
DCE	84	7.3	4.5 J	6	1.6 J	1.2 J	0.5 U	1.2	0.82 J	2.2	2.2	1.3	5.4	1.5
VC	39	24	31	25	9.2	75	5.5	6.1	10	18	17	10	18	18
DCA	5 U	1 U	1 U	1 U	1 U	1 U	0.5 U	0.5 U	0.5 U	0.25 U	0.25 U	0.17 U	0.38 U	

MW-3B	2000	Oct-09	May-10	Oct-11	Jun-12	Aug-13	Apr-14	Nov-15	Apr-16	Sep-17	Apr-18	Dec-19	Mar-20	Dec-21
TCE	5 U	5 U	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS
DCE	4.8 J	1.5	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS
VC	2.3	2.9	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS
DCA	5	5 U	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS

MW-6	2000	Oct-09	May-10	Oct-11	Jun-12	Aug-13	Apr-14	Nov-15	Apr-16	Sep-17	Apr-18	Dec-19	Mar-20	Dec-21
TCE	5 U	5 U	1 U	1 U	1 U	1 U	0.5 U	0.5 U	0.5 U	1.7 U	0.33 U	0.10 U	0.10 U	0.92 U
DCE	560	85	39	33	30	24	18	20	18	16	12	10	11	13
VC	91	69	48	57	47	42	39	57	59	79	48	78	72	98
DCA	0.28 J	5 U	1 U	1 U	1 U	1 U	0.5 U	0.5 U	0.5 U	1.3 U	0.25 U	0.17 U	0.17 U	0.76 U

MW-4B	2000	Oct-09	May-10	Oct-11	Jun-12	Aug-13	Apr-14	Nov-15	Apr-16	Sep-17	Apr-18	Dec-19	Mar-20	Dec-21
TCE	3.2 J	5 U	1 U	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS
DCE	39	9.7	2.8	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS
VC	35	9.5	12	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS
DCA	3.2 J	5 U	1 U	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS

MW-2B	2000	Oct-09	May-10	Oct-11	Jun-12	Aug-13	Apr-14	Nov-15	Apr-16	Sep-17	Apr-18	Dec-19	Mar-20	Dec-21
TCE	0.44 J	5 U	1 U	1 U	1 U	1 U	0.5 U	0.5 U	0.5 U	0.33 U	0.33 U	NS	NS	NS
DCE	260	9.1	3.7 J	1.8 J	2.7 J	2.3 J	1	0.87 J	0.95 J	0.77 J	1.3	NS	NS	NS
VC	92	16	7.6 J	2.6 J	8.6	4 J	2.2	3.4	2.2	1.8	2.6	NS	NS	NS
DCA	5 UJ	5 U	1 U	1 U	1 U	1 U	0.92 J	0.65 J	0.96 J	0.50 J	0.25 U	NS	NS	NS

MW-17B	2000	Oct-09	May-10	Oct-11	Jun-12	Aug-13	Apr-14	Nov-15	Apr-16	Sep-17	Apr-18	Dec-19	Mar-20	Dec-21
TCE	22	3.1 J	1 U	1 U	1 U	1 U	0.5 U	0.5 U	0.5 U	0.33 U	0.33 U	0.10 U	0.10 U	1.7 U
DCE	1000	280	8.5	19	20	35	1.3	0.5 U	0.5 U	10	4.9	11	1.4	31
VC	69	69	9.6	27	18	40	2.1	0.8 J	0.88 J	12	7.9	14	2.6	20
DCA	5.4	26	45	48	43	38	8.2	1.5	1.7	6.3 J	4.5	4.3	4.5	7.3

MW-8	2000	Oct-09	May-10	Oct-11	Jun-12	Aug-13	Apr-14	Nov-15	Apr-16	Sep-17	Apr-18	Dec-19	Mar-20	Dec-21
TCE	5 U	5 U	1 U	1 U	1 U	1 U	0.5 U	0.5 U	0.5 U	0.33 U	0.33 U	NS	NS	NS
DCE	5.55	2.1	2.3	1.9 J	1.6 J	1.7 J	1.6	1.7	1.9	1.7	1.9	NS	NS	NS
VC	1.9 J	2.6	2.2	2.1 J	1.1 J	1.8 J	1.5	1.9	1.8	1.4	1.6	NS	NS	NS
DCA	5 U	5 U	1 U	1 U	1 U	0.5 U	0.5 U	0.5 U	0.25 U	0.25 U	NS	NS	NS	NS

MW-16B	2000	Oct-09	May-10	Oct-11	Jun-12	Aug-13	Apr-14	Nov-15	Apr-16	Sep-17	Apr-18	Dec-19	Mar-20	Dec-21
TCE	0.97 J	5 U	1 U	1 U	74	2.2 J	2.5 U	4.8	0.5 U	0.33 U	0.33 U	0.10 U	0.10 U	0.46 U
DCE	130	511.8	81	27	4700	600	2300	1100	0.5 U	0.30 U	0.63 J	1	0.60 J	2.1
VC	35	130	48	43	600	610	2000	780	4.3	2.6	4.6	6.7	2.9	6.5
DCA	5 U	5 U	1 U	1 U	4 J	1 J	3.4 J	6.6	2	0.39 J	0.25 U	0.17 U	0.17 U	0.38 U

MW-19B	2000	Oct-09	May-10	Oct-11	Jun-12	Aug-13	Apr-14	Nov-15	Apr-16	Sep-17	Apr-18	Dec-19	Mar-20	Dec-21
TCE	2.4 J	5 U	1 U	1 U	1 U	1 U	0.5 U	0.5 U	0.5 U	0.33 U	0.33 U	0.10 U	0.10 U	0.46 U
DCE	41	68	2.1	8.7	2.3 J	2.1 J	2.9	1.8	1.1	1.6	24	1.4	11	1.8
VC	6.3	7.2	2.1 J	3.3 J	1.6 J	1.2 J	0.65 J	1	1.1	1.5	5.0	1.2	2.3	1.5
DCA	5 U	5 U	1 U	1 U	1 U	1 U	0.5 U	0.5 U	0.5 U	0.25 UJ	0.25 U	0.17 U	0.17 U	0.38 U

MW-12B	2000	Oct-09	May-10	Oct-11	Jun-12	Aug-13	Apr-14	Nov-15	Apr-16	Sep-17	Apr-18	Dec-19	Mar-20	Dec-21
TCE	5 U	5 U	1 U	1 U	1 U	1 U	0.5 U	0.5 U	0.5 U	0.66 U	0.83 U	0.25 U	0.20 U	0.46 UJ
DCE	210	2.6	11	0.98 J	5.6	43	57	13	73	52	62	65	51	73 J-
VC	77	2 U	1 U	1 U	10	73	75	9.1	59	110	73	94	85	49 DJ-
DCA	2.3 J	5 U	1 U	1 U	1 U	1 U	0.5 U	0.5 U	0.5 U	0.66 J	0.63 U	0.43 U	0.41 J	0.40 J-

MW-18B	2000	Oct-09	May-10	Oct-11	Jun-12	Aug-13	Apr-14	Nov-15	Apr-16	Sep-17	Apr-18	Dec-19	Mar-20	Dec-21
TCE	7.7	5 U	1 U	1 U	1 U	1 U	0.5 U	0.5 U	0.5 U	0.5 U	6.6 U	0.83 U	0.20 U	0.20 U
DCE	690	62	69	150	110	120	43	35	90	380	69	56	32	47
VC	90	220	190	220	140	190	71	40	120	210	92	70	51	80
DCA	5 U	5 U	1 U	1 U	1 U	1 U	0.5 U	0.5 U	0.5 U	5.0 UJ	0.63 U	0.34 U	0.34 U	0.76 U

MW-11B	2000	Oct-09	May-10	Oct-11	Jun-12	Aug-13	Apr-14	Nov-15	Apr-16	Sep-17	Apr-18	Dec-19	Mar-20	Dec-21
TCE	5 U	1 U	1 U	1 U	1 U	1 U	0.5 U	0.5 U	0.5 U	0.33 U	0.33 U	NS	NS	NS
DCE	590	56	1.9 J	2.2 J	1 U	0.8 U	0.5 U	0.56 J	0.54 J	1.1	0.65 J	NS	NS	NS
VC	81	48	7.4	4.6 J	6.1	1.4 J	1.2	1.7	9.7	6.5	1.9	NS	NS	NS
DCA	3.5 J	U	1.3 J	1.8 J	1.4 J	1.9 J	2	1	1.7	0.95 J	1.9	NS	NS	NS

MW-10B	2000	Oct-09	May-10	Oct-11	Jun-12	Aug-13	Apr-14	Nov-15	Apr-16	Sep-17	Apr-18	Dec-19	Mar-20	Dec-21
TCE	68	1 U	1 U	2 U	1 U	1 U	0.5 U	0.5 U	0.5 U	3.3 U	2.6 U	2.0 U	0.50 U	4.6 U
DCE	1800	370	220	960	280	230	190	190	220	360	210	420	210	220
VC	95	150	83	180	110	120	22	190	6.1	270	12	180	23	370
DCA	1.2 J	1 U	1 U	2 U	1 U	1 U	0.5 U	0.9 J	0.59 J	2.5 UJ	2.0 U	3.4 U	0.85 U	3.8 U


MW-5B	2000	Oct-09	May-10	Oct-11	Jun-12	Aug-13	Apr-14	Nov-15	Apr-16	Sep-17	Apr-18	Dec-19	Mar-20	Dec-21
TCE	2.6 J	5 U	1.1 J	1 U	1 U	1 U	0.97 J	0.58 J	0.5 U	1.7 U	0.33 U	0.20 U	0.20 U	0.92 U
DCE	420	39	36	48	33	32	19	34	32	36	32	26	40	
VC	45	37	39	63	34	44	33	63	71	91	78	90	68	140
DCA	1.1 J	5 U	1 U	1 U	1 U	1 U	0.5 U	0.5 U	0.5 U	1.3 U	0.30 J	0.34 U	0.34 U	0.76 U

MW-14B	2000	Oct-09	May-10	Oct-11	Jun-12	Aug-13	Apr-14	Nov-15	Apr-16	Sep-17	Apr-18	Dec-19	Mar-20	Dec-21
TCE	5 U	5 U	1 U	1 U	1 U	1 U	0.5 U	0.5 U	0.5 U	0.33 U	0.33 U	0.10 U	0.10 U	0.46 U
DCE	300	64	16	4.1 J	1.5 J	0.8 U	0.67 J	0.95 J	0.94 J	0.92 J	0.72 J	0.37 J	1.0 U	0.81 U
VC	110	86	33	5.4	1.5 J	1.2	1.5	1.2	2.9	1.3	0.7 J	1.0	1.9	
DCA	0.61 J	5 U	1 U	1 U	1 U	1 U	0.5 U	0.53 J	0.5 U	0.43 J	0.34 J	0.19 J	0.24 J	0.38 U

MW-1B	2000	Oct-09	May-10	Oct-11	Jun-12	Aug-13	Apr-14	Nov-15	Apr-16	Sep-17	Apr-18	Dec-19	Mar-20	Dec-21
TCE	5 U	1 U	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS
DCE	4.7 J	0.8	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS
VC	3.8	1.7	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS
DCA	1.5 J	1 U	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS



MW-15	2000	Oct-09	May-10	Oct-11	Jun-12	Aug-13	Apr-14	Nov-15	Apr-16	Sep-17	Apr-18	Dec-19	Mar-20	Dec-21
TCE	5 U	5 U	1 U	1 U	1 U	1 U	NS	NS	NS	NS	0.10 UJ	NS	NS	NS
DCE	400	57.1	5.9	32	0.8 U	0.8 U	NS	NS	NS	NS	5.2	NS	NS	NS
VC	120	82	17	52	1.8 J	2 J	NS	NS	NS	NS	16	NS	NS	NS
DCA	0.95 J	2	1.3 J	1.4 J	1.2 J	1 U	NS	NS	NS	NS	1.1	NS	NS	NS

MW-13B	2000	Oct-09	May-10	Oct-11	Jun-12	Aug-13	Apr-14	Nov-15	Apr-16	Sep-17	Apr-18	Dec-19	Mar-20	Dec-21
TCE	12	5 U	1 U	1 U	1 U	1 U	0.5 U	0.5 U	0.5 U	0.33 U	0.33 U	0.19 J	0.10 U	0.92 U
DCE	310	88	46	17	27	8.6	19	18	9.9	22	7.8	16	1.6	3.7
VC	40	68	47	24	57	48	15	21	12	38	9.7	21	2.0	6.4
DCA	0.91 J	5 U	1 U	1 U	1 U	1 U	0.5 U	0.5 U	0.5 U	0.25 UJ	0.25 U	0.17 J	0.17 U	0.76 U



Note:
Total CVOC Concentration is the sum of TCE, cis-1,2-DCE, VC, and DCA concentrations.

FIGURE 7
FORMER CARBORUNDUM COMPANY
LONG TERM TRENDS OF TOTAL CHLORINATED ETHENES IN SOURCE AREA OVERBURDEN AND BEDROCK WELLS
AECOM
1 John James Audubon Parkway, Amherst, NY 14228



Note:
Total CVOC Concentration is the sum of TCE, cis-1,2-DCE, VC, and DCA concentrations.

FIGURE 8
FORMER CARBORUNDUM COMPANY
LONG TERM TRENDS OF TOTAL CHLORINATED ETHENES IN DOWNGRAIDENT OVERBURDEN AND BEDROCK WELLS
AECOM
1 John James Audubon Parkway, Amherst, NY 14228

Appendix A

Groundwater Sampling Logs

Low Flow Sampling Record											
Site Name: IP-BP Hyde Park			Well ID: MW-5A				Well Diameter: 2"				
Samplers: E. Au M.A. Kropovitch			Water Volume Calculation 1 inch= 0.041 6 inch= 1.4 1.5 inch= 0.092 8 inch= 2.5 2 inch= 0.163 10 inch= 4 4 inch= 0.64 = (Total Depth of Well - Depth to Water) × Casing volume per foot				Acceptance Criteria: Temp 3% pH ± 0.1 unit Sp. Cond. 3% ORP ± 10mV DO 10% Turbidity <50 NTU Drawdown <0.3'				
Weather: 45F, Rain											
Purging Data:						feet below top of PVC					
Method: Low Flow		Date: 12/06/21		Time: 0925 (hhmm)		Initial Depth to Water 9.28			Depth to Bottom 21.5		
Time hhmm	DTW (ft)	Pump Rate (ml/min)	Volume (gal.)	Temp (C°)	Sp. Cond (ms/cm)	DO (mg/L)	pH	ORP (mV)	Turb (NTU)	Comments:	
0925	9.84	250	0.0	14.3	0.691	3.85	8.10	114.0	117.20		
0930	9.93	250	0.3	14.4	0.681	3.12	7.85	63.3	13.90	Turb. has bubbles; clear	
0935	10.02	250	0.7	14.5	0.688	2.89	7.79	70.3	12.56		
0940	9.97	250	1.0	14.4	0.698	2.72	7.75	74.6	15.83		
0945	10.00	250	1.3	14.3	0.710	2.37	7.68	86.7	25.81		
0950	9.98	250	1.7	14.3	0.716	2.12	7.65	99.0	39.26		
0955	9.98	250	2.0	14.4	0.726	1.77	7.60	110.2	18.02		
1000	9.99	250	2.3	14.4	0.737	1.50	7.55	116.4	19.35		
1005	10.00	250	2.6	14.3	0.741	1.39	7.53	119.6	10.52		
1010	10.00	250	3.0	14.4	0.751	1.20	7.49	124.0	10.00		
Sample Collection Method:		Date: 12/06/21		Time: 1010		Total Volume of Water Purged: 4.5 gallons					
Hach Test Kits			Sample Set								
Alkalinity (mg/L)		160		Parameter		Bottle		Pres.		Method	
Carbon Dioxide (mg/L)		25		VOCs		3-40 mL glass vial		HCL		EPA 8260C	
Ferrous Iron (mg/L)		0.02		Dissolved Iron		1-250 mL plastic (field filtered)		HNO3		6010C	
Hydrogen Sulfide (mg/L)		0.0		TOC		2-40mL glass vial		H2SO4		5310C	
1 Well Volume		2.0		M.E.E.P.		3-40 mL glass vial		HCL		RSK-175 mod	
YSI Pro DDS - Turbidity reading high at times, tapping the flow through cell clears bubbles from around the probe. Setting flow through cell on an angle gave more consistent readings.				Nitrate/Nitrite/Chloride/Sulfate		1-500mL plastic		unpreserved		300, 353.2 300.0_28D	
				BOD		1-1000 mL plastic		unpreserved		5210B	
				COD		1-250 mL plastic		H2SO4		410.4	
				Sulfide		1-500mL plastic		NaOH/Zn Acetate		4500-S2-F	

Low Flow Sampling Record											
Site Name: IP-BP Hyde Park			Well ID: MW-5B				Well Diameter: 2"			Acceptance Criteria: Temp 3% pH ± 0.1 unit Sp. Cond. 3% ORP ± 10mV DO 10% Turbidity <50 NTU Drawdown <0.3'	
Samplers:			Water Volume Calculation								
E. Au			1 inch= 0.041 6 inch= 1.4								
M.A. Kropovitch			1.5 inch= 0.092 8 inch= 2.5								
Weather: 45F, Rain			2 inch= 0.163 10 inch= 4								
			4 inch= 0.64								
			= (Total Depth of Well - Depth to Water) × Casing volume per foot								
Purging Data:						feet below top of PVC					
Method: Low Flow		Date: 12/06/21		Time: 1048 (hhmm)		Initial Depth to Water 8.87			Depth to Bottom 39.5		
Time	DTW	Pump Rate	Volume	Temp	Sp. Cond	DO	pH	ORP	Turb	Comments:	
hhmm	(ft)	(ml/min)	(gal.)	(C°)	(ms/cm)	(mg/L)		(mV)	(NTU)		
1050	8.87	250	0.0	13.6	3.701	7.05	12.44	71.6	76.44		
1055	8.41	250	0.3	13.4	3.115	5.63	12.58	12.5	160.25		
1100	8.41	250	0.7	13.4	1.572	3.04	12.03	-7.1	242.80		
1105	8.41	250	1.0	13.4	1.094	1.51	9.71	20.9	90.1		
1110	8.41	250	1.3	13.3	1.081	1.23	9.10	34.5	58.4		
1115	8.41	250	1.7	13.3	1.010	0.98	8.76	38.1	59.5		
1120	8.41	250	2.0	13.4	1.087	0.93	8.96	20.4	58.8		
1125	8.41	250	2.3	13.2	1.100	0.81	8.55	9.1	54.2		
1130	8.41	250	2.6	13.0	1.095	0.78	8.49	-43.7	56.78		
1135	8.41	250	3.0	13.0	1.088	0.84	8.42	-36.0	57.76		
1140	8.41	250	3.3	13.0	1.090	0.72	8.12	-74.5	58.91		
1145	8.41	250	3.6	12.9	1.080	0.58	7.71	-66.4	52.23		
Sample Collection Method:		Date: 12/06/21		Time: 1145		Total Volume of Water Purged: 5 gallons					
Peristaltic Pump											
Hach Test Kits				Sample Set							
Alkalinity (mg/L)		360		Parameter		Bottle		Pres.		Method	
Carbon Dioxide (mg/L)		35		VOCs		3-40 mL glass vial		HCL		EPA 8260C	
Ferrous Iron (mg/L)		0.20		Dissolved Iron		1-250 mL plastic (field filtered)		HNO3		6010C	
Hydrogen Sulfide (mg/L)		0.0		TOC		2-40mL glass vial		H2SO4		5310C	
1 Well Volume		5.0		M.E.E.P.		3-40 mL glass vial		HCL		RSK-175 mod	
Duplicate 120621 collected. Time listed as 11:20.				Nitrate/Nitrite/Chloride/Sulfate		1-500mL plastic		unpreserved		300, 353.2 300.0_28D	
				BOD		1-1000 mL plastic		unpreserved		5210B	
				COD		1-250 mL plastic		H2SO4		410.4	
				Sulfide		1-500mL plastic		NaOH/Zn Acetate		4500-S2-F	

Low Flow Sampling Record											
Site Name: IP-BP Hyde Park			Well ID: MW-6				Well Diameter: 2"				
Samplers:			Water Volume Calculation				Acceptance Criteria:				
S. Connelly			1 inch= 0.041 6 inch= 1.4				Temp 3%				
			1.5 inch= 0.092 8 inch= 2.5				pH ± 0.1 unit				
			2 inch= 0.163 10 inch= 4				Sp. Cond. 3%				
			4 inch= 0.64				ORP ± 10mV				
Weather: 30F, Cloudy			= (Total Depth of Well - Depth to Water) × Casing volume per foot				DO 10%				
							Turbidity <50 NTU				
							Drawdown <0.3'				
Purging Data:						feet below top of PVC					
Method: Low Flow		Date: 12/08/21		Time: 1214		Initial Depth to Water			Depth to Bottom		
						6.44			43.00		
Time	DTW	Pump Rate	Volume	Temp	Sp. Cond	DO	pH	ORP	Turb	Comments:	
hhmm	(ft)	(ml/min)	(gal.)	(C°)	(ms/cm)	(mg/L)		(mV)	(NTU)		
1217	6.51	350	0.0	11.8	1.582	1.52	7.12	-176.3	80.87		
1222	6.51	350	0.5	11.9	1.610	1.00	7.09	-200.6	5.86		
1227	6.51	350	0.9	11.9	1.611	0.85	7.08	-209.3	2.31		
1232	6.51	350	1.4	11.9	1.611	0.80	7.08	-215.1	3.14		
1237	6.51	350	1.8	11.9	1.611	0.78	7.08	-217.7	4.24		
1242	6.51	350	2.3	11.8	1.612	0.76	7.09	-219.3	6.53		
1247	6.51	350	2.8	12.0	1.613	0.75	7.09	-220.5	4.18		
1252	6.51	350	3.2	12.0	1.614	0.75	7.09	-221.6	2.67		
1257	6.51	350	3.7	12.0	1.615	0.74	7.09	-221.2	2.80		
Sample Collection Method:		Date: 12/08/21		Time: 1257		Total Volume of Water Purged:					
Peristaltic Pump						4.5 gallons					
Hach Test Kits				Sample Set							
Alkalinity (mg/L)		300		Parameter		Bottle		Pres.		Method	
Carbon Dioxide (mg/L)		25		VOCs		3-40 mL glass vial		HCL		EPA 8260C	
Ferrous Iron (mg/L)		0.01		Dissolved Iron		1-250 mL plastic (field filtered)		HNO3		6010C	
Hydrogen Sulfide (mg/L)		0.5		TOC		2-40mL glass vial		H2SO4		5310C	
1 Well Volume		6.0		M.E.E.P.		3-40 mL glass vial		HCL		RSK-175 mod	
VOCs only				Nitrate/Nitrite/Chloride/Sulfate		1-500mL plastic		unpreserved		300, 353.2 300.0_28D	
				BOD		1-1000 mL plastic		unpreserved		5210B	
				COD		1-250 mL plastic		H2SO4		410.4	
				Sulfide		1-500mL plastic		NaOH/Zn Acetate		4500-S2-F	

Low Flow Sampling Record											
Site Name: IP-BP Hyde Park			Well ID: MW-7A				Well Diameter: 2"		Acceptance Criteria: Temp 3% pH ± 0.1 unit Sp. Cond. 3% ORP ± 10mV DO 10% Turbidity <50 NTU Drawdown <0.3'		
Samplers: S. Connelly			Water Volume Calculation 1 inch= 0.041 6 inch= 1.4 1.5 inch= 0.092 8 inch= 2.5 2 inch= 0.163 10 inch= 4 4 inch= 0.64 = (Total Depth of Well - Depth to Water) × Casing volume per foot								
Weather: 25F, Cloudy											
Purging Data:						feet below top of PVC					
Method: Low Flow		Date: 12/08/21		Time: 1045		Initial Depth to Water: 6.32		Depth to Bottom: 21.85			
Time hhmm	DTW (ft)	Pump Rate (ml/min)	Volume (gal.)	Temp (C°)	Sp. Cond (ms/cm)	DO (mg/L)	pH	ORP (mV)	Turb (NTU)	Comments:	
1046	8.29	350	0.0	11.2	1.186	4.00	7.10	-193.2	287.19		
1051	9.16	350	0.5	12.7	1.193	0.84	7.03	-235.4	50.35		
1056	10.04	350	0.9	12.7	1.179	0.77	7.10	-224.6	47.62		
1101	11.25	350	1.4	12.8	1.177	0.73	7.04	-223.6	49.08		
1106	12.00	350	1.8	12.7	1.180	0.73	7.01	-230.3	47.26		
1111	12.46	300	2.2	12.8	1.202	0.71	6.96	-234.9	45.33		
1116	12.95	300	2.6	12.7	1.203	0.71	6.96	-234.5	45.06		
1121	12.98	300	3.0	12.4	1.202	0.74	6.94	-230.6	37.98		
1126	13.01	300	3.4	12.6	1.206	0.72	6.90	-227.6	33.96		
1131	13.02	300	3.8	12.4	1.206	0.73	6.86	-223.4	31.25		
1136	13.04	300	4.2	12.5	1.186	0.71	6.86	-219.8	25.32		
1141	13.05	300	4.6	12.5	1.178	0.71	6.85	-216.8	23.91		
Sample Collection Method: Peristaltic Pump		Date: 12/08/21		Time: 1141		Total Volume of Water Purged: 4.5 gallons					
Hach Test Kits				Sample Set							
Alkalinity (mg/L)		625		Parameter		Bottle		Pres.		Method	
Carbon Dioxide (mg/L)		55		VOCs		3-40 mL glass vial		HCL		EPA 8260C	
Ferrous Iron (mg/L)		1.25		Dissolved Iron		1-250 mL plastic (field filtered)		HNO3		6010C	
Hydrogen Sulfide (mg/L)		0.7		TOC		2-40mL glass vial		H2SO4		5310C	
1 Well Volume		2.5		M.E.E.P.		3-40 mL glass vial		HCL		RSK-175 mod	
				Nitrate/Nitrite/Chloride/Sulfate		1-500mL plastic		unpreserved		300, 353.2 300.0_28D	
				BOD		1-1000 mL plastic		unpreserved		5210B	
				COD		1-250 mL plastic		H2SO4		410.4	
				Sulfide		1-500mL plastic		NaOH/Zn Acetate		4500-S2-F	

Low Flow Sampling Record										
Site Name: IP-BP Hyde Park			Well ID: MW-7B				Well Diameter: 2"			
Samplers: S. Connelly			Water Volume Calculation 1 inch= 0.041 6 inch= 1.4 1.5 inch= 0.092 8 inch= 2.5 2 inch= 0.163 10 inch= 4 4 inch= 0.64 = (Total Depth of Well - Depth to Water) × Casing volume per foot				Acceptance Criteria: Temp 3% pH ± 0.1 unit Sp. Cond. 3% ORP ± 10mV DO 10% Turbidity <50 NTU Drawdown <0.3'			
Weather: 25F, Cloudy										
Purging Data:						feet below top of PVC				
Method: Low Flow		Date: 12/08/21		Time: 0943 (hhmm)		Initial Depth to Water 6.97		Depth to Bottom 43.43		
Time hhmm	DTW (ft)	Pump Rate (ml/min)	Volume (gal.)	Temp (C°)	Sp. Cond (ms/cm)	DO (mg/L)	pH	ORP (mV)	Turb (NTU)	Comments:
0944	7.22	350	0.0	11.8	1.664	1.22	7.04	-157.3	11.1	
0949	7.29	400	0.5	11.7	1.661	0.97	7.06	-157.8	4.7	
0954	7.29	400	1.1	11.7	1.656	386.00	7.07	-162.8	4.11	
0959	7.29	400	1.6	11.7	1.650	0.81	7.07	-171.2	3.76	
1004	7.29	400	2.1	11.8	1.643	0.78	7.07	-177.8	3.84	
1009	7.29	400	2.6	11.7	1.640	0.76	7.07	-185.9	4.19	
1014	7.29	400	3.2	11.8	1.635	0.75	7.07	-194.1	3.21	
1019	7.29	400	3.7	11.7	1.631	0.74	7.07	-200.9	2.14	
1024	7.29	400	4.2	11.8	1.629	0.73	7.07	-204.3	2.37	
1029	7.29	400	4.8	11.8	1.627	0.73	7.07	-206.8	2.14	
Sample Collection Method: Peristaltic Pump		Date: 12/08/21		Time: 1029		Total Volume of Water Purged: 5 Gallons				
Hach Test Kits			Sample Set							
Alkalinity (mg/L)		340		Parameter		Bottle		Pres.		Method
Carbon Dioxide (mg/L)		25		VOCs		3-40 mL glass vial		HCL		EPA 8260C
Ferrous Iron (mg/L)		0.00		Dissolved Iron		1-250 mL plastic (field filtered)		HNO3		6010C
Hydrogen Sulfide (mg/L)		1.0		TOC		2-40mL glass vial		H2SO4		5310C
1 Well Volume		5.9		M.E.E.P.		3-40 mL glass vial		HCL		RSK-175 mod
				Nitrate/Nitrite/Chloride/Sulfate		1-500mL plastic		unpreserved		300, 353.2 300.0_28D
				BOD		1-1000 mL plastic		unpreserved		5210B
				COD		1-250 mL plastic		H2SO4		410.4
				Sulfide		1-500mL plastic		NaOH/Zn Acetate		4500-S2-F

Low Flow Sampling Record											
Site Name: IP-BP Hyde Park			Well ID: MW-10A				Well Diameter: 2"				
Samplers: S. Connelly			Water Volume Calculation 1 inch= 0.041 6 inch= 1.4 1.5 inch= 0.092 8 inch= 2.5 2 inch= 0.163 10 inch= 4 4 inch= 0.64 = (Total Depth of Well - Depth to Water) × Casing volume per foot				Acceptance Criteria: Temp 3% pH ± 0.1 unit Sp. Cond. 3% ORP ± 10mV DO 10% Turbidity <50 NTU Drawdown <0.3'				
Weather: 52F, Rain											
Purging Data:						feet below top of PVC					
Method: Low Flow		Date: 12/06/21		Time: 1003 (hhmm)		Initial Depth to Water: 8.43			Depth to Bottom: 20.82		
Time hhmm	DTW (ft)	Pump Rate (ml/min)	Volume (gal.)	Temp (C°)	Sp. Cond (ms/cm)	DO (mg/L)	pH	ORP (mV)	Turb (NTU)	Comments:	
1005	8.63	300	0.0	14.1	1.250	2.57	7.75	-45.4	15.62		
1010	8.63	300	0.4	14.1	1.274	1.12	7.69	-72.7	13.59		
1015	8.63	300	0.8	14.0	1.299	0.87	7.66	-67.4	7.04		
1020	8.63	300	1.2	14.0	1.322	0.80	7.65	-68.6	4.95		
1025	8.63	300	1.6	13.9	1.335	0.76	7.65	-70.6	3.81		
1030	8.63	300	2.0	13.9	1.344	0.73	7.65	-73.0	4.12		
1035	8.63	300	2.4	14.0	1.346	0.72	7.64	-73.8	4.64		
1040	8.63	300	2.8	14.0	1.349	0.71	7.64	-74.8	4.16		
1045	8.63	300	3.2	13.9	1.349	0.71	7.64	-75.6	8.65		
1050	8.63	300	3.6	13.8	1.351	0.72	7.64	-75.8	8.77		
1055	8.63	300	4.0	13.7	1.351	0.72	7.63	-75.3	7.25		
Sample Collection Method: Peristaltic Pump		Date: 12/06/21		Time: 1055		Total Volume of Water Purged: 4 gallons					
Hach Test Kits				Sample Set							
Alkalinity (mg/L)		320		Parameter		Bottle		Pres.		Method	
Carbon Dioxide (mg/L)		40		VOCs		3-40 mL glass vial		HCL		EPA 8260C	
Ferrous Iron (mg/L)		1.32		Dissolved Iron		1-250 mL plastic (field filtered)		HNO3		6010C	
Hydrogen Sulfide (mg/L)		0.0		TOC		2-40mL glass vial		H2SO4		5310C	
1 Well Volume		2.0		M.E.E.P.		3-40 mL glass vial		HCL		RSK-175 mod	
				Nitrate/Nitrite/Chloride/Sulfate		1-500mL plastic		unpreserved		300, 353.2 300.0_28D	
				BOD		1-1000 mL plastic		unpreserved		5210B	
				COD		1-250 mL plastic		H2SO4		410.4	
				Sulfide		1-500mL plastic		NaOH/Zn Acetate		4500-S2-F	

Low Flow Sampling Record											
Site Name: IP-BP Hyde Park			Well ID: MW-10B				Well Diameter: 4"		Acceptance Criteria: Temp 3% pH ± 0.1 unit Sp. Cond. 3% ORP ± 10mV DO 10% Turbidity <50 NTU Drawdown <0.3'		
Samplers: S. Connelly			Water Volume Calculation 1 inch= 0.041 6 inch= 1.4 1.5 inch= 0.092 8 inch= 2.5 2 inch= 0.163 10 inch= 4 4 inch= 0.64 = (Total Depth of Well - Depth to Water) × Casing volume per foot								
Weather: 52F, Rain											
Purging Data:						feet below top of PVC					
Method: Low Flow		Date: 12/06/21		Time: 0930 (hhmm)		Initial Depth to Water 7.78			Depth to Bottom 38.8		
Time hhmm	DTW (ft)	Pump Rate (ml/min)	Volume (gal.)	Temp (C°)	Sp. Cond (ms/cm)	DO (mg/L)	pH	ORP (mV)	Turb (NTU)	Comments:	
1125	7.79	350	0.0	13.7	1.344	0.88	7.39	-63.2	1.73		
1130	7.79	350	0.5	13.7	1.345	0.84	7.39	-64.4	1.67		
1135	7.79	350	0.9	13.5	1.345	0.74	7.40	-73.4	1.78		
1140	7.80	350	1.4	13.4	1.345	0.70	7.41	-85.6	1.93		
1145	7.80	350	1.8	13.3	1.343	0.69	7.41	-90.3	2.49		
1150	7.80	350	2.3	13.2	1.339	0.69	7.41	-96.8	3.25		
1155	7.80	300	2.7	13.3	1.342	0.69	7.41	-97.3	3.29		
1200	7.80	200	3.0	13.2	1.340	0.68	7.42	-102.0	5.08		
1205	7.80	200	3.2	13.1	1.340	0.68	7.42	-106.9	6.13		
1210	7.80	200	3.5	13.2	1.339	0.67	7.42	-112.1	3.02		
1215	7.80	200	3.8	13.1	1.342	0.68	7.42	-115.0	1.59		
1220	7.80	200	4.0	13.0	1.338	0.68	7.42	-117.7	1.84		
1225	7.80	200	4.3	12.9	1.338	0.68	7.42	-120.5	2.24		
1230	7.80	200	4.6	13.4	1.336	0.66	7.42	-122.5	2.75		
1235	7.80	200	4.8	13.3	1.339	0.64	7.42	-125.8	2.89		
Sample Collection Method: Peristaltic Pump		Date: 12/06/21		Time: 13:30		Total Volume of Water Purged: 7.5 Gallons					
Hach Test Kits				Sample Set							
Alkalinity (mg/L)		360		Parameter		Bottle		Pres.		Method	
Carbon Dioxide (mg/L)		50		VOCs		3-40 mL glass vial		HCL		EPA 8260C	
Ferrous Iron (mg/L)		0.36		Dissolved Iron		1-250 mL plastic (field filtered)		HNO3		6010C	
Hydrogen Sulfide (mg/L)		0.3		TOC		2-40mL glass vial		H2SO4		5310C	
1 Well Volume		7.37		M.E.E.P.		3-40 mL glass vial		HCL		RSK-175 mod	
MS/MSD collected at this location. Battery slowly died during pumping.				Nitrate/Nitrite/Chloride/Sulfate		1-500mL plastic		unpreserved		300, 353.2 300.0_28D	
				BOD		1-1000 mL plastic		unpreserved		5210B	
				COD		1-250 mL plastic		H2SO4		410.4	
				Sulfide		1-500mL plastic		NaOH/Zn Acetate		4500-S2-F	

Low Flow Sampling Record											
Site Name: IP-BP Hyde Park				Well ID: MW-10B				Well Diameter: 4"		Acceptance Criteria: Temp 3% pH ± 0.1 unit Sp. Cond. 3% ORP ± 10mV DO 10% Turbidity <50 NTU Drawdown <0.3'	
Samplers: S. Connelly				Water Volume Calculation 1 inch= 0.041 6 inch= 1.4 1.5 inch= 0.092 8 inch= 2.5 2 inch= 0.163 10 inch= 4 4 inch= 0.64 = (Total Depth of Well - Depth to Water) × Casing volume per foot							
Weather: 52F, Rain											
Purging Data:								feet below top of PVC			
Method: Low Flow		Date: 12/06/21		Time: 0930 (hhmm)		Initial Depth to Water: 7.78		Depth to Bottom: 38.8			
Time hhmm	DTW (ft)	Pump Rate (ml/min)	Volume (gal.)	Temp (C°)	Sp. Cond (ms/cm)	DO (mg/L)	pH	ORP (mV)	Turb (NTU)	Comments:	
1240	7.80	200	5.1	13.3	1.337	0.65	7.42	-126.7	2.07		
1245	7.80	200	5.3	13.2	1.336	0.64	7.43	-127.3	2.55		
1250	7.80	200	5.6	13.2	1.336	0.64	7.43	-129.5	3.68		
1255	7.80	200	5.9	13.2	1.335	0.64	7.43	-130.5	3.12		
1300	7.80	200	6.1	13.1	1.329	0.65	7.42	-130.2	2.02		
1305	7.80	200	6.4	13.0	1.326	0.66	7.43	-130.0	1.98		
1310	7.80	200	6.6	12.9	1.319	0.67	7.42	-129.3	2.13		
1315	7.80	200	6.9	12.8	1.317	0.67	7.42	-129.5	1.91		
1320	7.80	200	7.2	12.8	1.315	0.68	7.42	-129.4	1.54		
1325	7.80	200	7.4	12.8	1.312	0.69	7.42	-129.3	1.20		
1330	7.80	200	7.7	12.7	1.311	0.68	7.42	-129.5	1.28		
Sample Collection Method: Peristaltic Pump		Date: 12/06/21		Time: 13:30		Total Volume of Water Purged: 7.5 Gallons					
Hach Test Kits				Sample Set							
Alkalinity (mg/L)		360		Parameter		Bottle		Pres.		Method	
Carbon Dioxide (mg/L)		50		VOCS		3-40 mL glass vial		HCL		EPA 8260C	
Ferrous Iron (mg/L)		0.36		Dissolved Iron		1-250 mL plastic (field filtered)		HNO3		6010C	
Hydrogen Sulfide (mg/L)		0.3		TOC		2-40mL glass vial		H2SO4		5310C	
1 Well Volume		7.37		M.E.E.P.		3-40 mL glass vial		HCL		RSK-175 mod	
MS/MSD collected at this location.				Nitrate/Nitrite/Chloride/Sulfate		1-500mL plastic		unpreserved		300, 353.2 300.0_28D	
				BOD		1-1000 mL plastic		unpreserved		5210B	
				COD		1-250 mL plastic		H2SO4		410.4	
				Sulfide		1-500mL plastic		NaOH/Zn Acetate		4500-S2-F	

Low Flow Sampling Record											
Site Name: IP-BP Hyde Park			Well ID: MW-12B				Well Diameter: 4"		Acceptance Criteria: Temp 3% pH ± 0.1 unit Sp. Cond. 3% ORP ± 10mV DO 10% Turbidity <50 NTU Drawdown <0.3'		
Samplers: S. Connelly			Water Volume Calculation 1 inch= 0.041 6 inch= 1.4 1.5 inch= 0.092 8 inch= 2.5 2 inch= 0.163 10 inch= 4 4 inch= 0.64 = (Total Depth of Well - Depth to Water) × Casing volume per foot								
Weather: 28F, Partly Cloudy											
Purging Data:						feet below top of PVC					
Method: Low Flow		Date: 12/07/21		Time: 0820 (hhmm)		Initial Depth to Water: 2.05		Depth to Bottom: 30.40			
Time hhmm	DTW (ft)	Pump Rate (ml/min)	Volume (gal.)	Temp (C°)	Sp. Cond (ms/cm)	DO (mg/L)	pH	ORP (mV)	Turb (NTU)	Comments:	
0932	2.05	400	0.0	11.0	0.484	7.58	7.17	-38.8	6.56		
0937	2.05	400	0.5	11.8	0.355	6.60	7.18	-142.2	5.76		
0942	2.05	400	1.1	11.9	0.354	6.54	7.19	-155.5	5.33		
0947	2.05	400	1.6	11.9	0.357	6.28	7.18	-163.1	3.99		
0952	2.05	400	2.1	11.9	0.380	5.23	7.14	-168.8	3.6		
0957	2.05	400	2.6	11.9	0.394	4.90	7.12	-169.5	3.48		
1002	2.05	400	3.2	11.9	0.562	3.91	7.12	-154.9	2.98		
1007	2.05	400	3.7	11.9	0.891	2.44	7.12	-148.7	2.31		
1012	2.05	400	4.2	11.9	1.221	1.89	7.11	-140.6	2.06		
1017	2.05	400	4.8	11.9	1.532	0.93	7.10	-134.5	1.87		
1022	2.05	400	5.3	11.9	1.539	0.74	7.10	-132.0	1.85		
1027	2.05	400	5.8	12.0	1.543	0.72	7.10	-133.4	2.36		
1032	2.05	400	6.3	11.9	1.544	0.71	7.11	-136.2	2.41		
1037	2.05	400	6.9	11.9	1.545	0.69	7.11	-138.3	2.11		
1042	2.05	400	7.4	11.9	1.546	0.69	7.11	-139.2	1.94		
Sample Collection Method: Peristaltic Pump		Date: 12/07/21		Time: 1042		Total Volume of Water Purged: 10 gallons					
Hach Test Kits				Sample Set							
Alkalinity (mg/L)		180		Parameter		Bottle		Pres.		Method	
Carbon Dioxide (mg/L)		15		VOCs		3-40 mL glass vial		HCL		EPA 8260C	
Ferrous Iron (mg/L)		0.01		Dissolved Iron		1-250 mL plastic (field filtered)		HNO3		6010C	
Hydrogen Sulfide (mg/L)		0.0		TOC		2-40mL glass vial		H2SO4		5310C	
1 Well Volume		18.1		M.E.E.P.		3-40 mL glass vial		HCL		RSK-175 mod	
				Nitrate/Nitrite/Chloride/Sulfate		1-500mL plastic		unpreserved		300, 353.2 300.0_28D	
				BOD		1-1000 mL plastic		unpreserved		5210B	
				COD		1-250 mL plastic		H2SO4		410.4	
				Sulfide		1-500mL plastic		NaOH/Zn Acetate		4500-S2-F	

Low Flow Sampling Record											
Site Name: IP-BP Hyde Park			Well ID: MW-13B				Well Diameter: 2"				
Samplers:			Water Volume Calculation				Acceptance Criteria:				
E. Au			1 inch= 0.041 6 inch= 1.4				Temp 3%				
M.A. Kropovitch			1.5 inch= 0.092 8 inch= 2.5				pH ± 0.1 unit				
Weather:			2 inch= 0.163 10 inch= 4				Sp. Cond. 3%				
45F, Showers			4 inch= 0.64				ORP ± 10mV				
			= (Total Depth of Well - Depth to Water) × Casing volume per foot				DO 10%				
							Turbidity <50 NTU				
							Drawdown <0.3'				
Purging Data:						feet below top of PVC					
Method: Low Flow		Date: 12/06/21		Time: 1245 (hhmm)		Initial Depth to Water			Depth to Bottom		
						6.14			36.55		
Time	DTW	Pump Rate	Volume	Temp	Sp. Cond	DO	pH	ORP	Turb	Comments:	
hhmm	(ft)	(ml/min)	(gal.)	(C°)	(ms/cm)	(mg/L)		(mV)	(NTU)		
1245	6.14	300	0.0	11.5	1.289	10.17	7.95	46.9	207.44		
1250	6.64	300	0.4	11.6	1.713	10.21	7.80	68.5	204.36		
1255	6.53	300	0.8	11.6	1.751	9.98	7.70	83.7	184.58		
1300	6.52	200	1.1	11.5	1.778	9.41	7.56	102.8	108.3	losing battery power	
1305	6.41	200	1.3	11.2	1.779	9.26	7.53	107.4	95.36		
1310	6.38	200	1.6	11.2	1.770	8.94	7.48	114.3	85.62		
1315	6.53	200	1.8	11.6	1.750	8.94	7.43	118.3	84.19		
1320	6.54	300	2.2	11.6	1.772	8.86	7.41	123.3	74.96	turned up pump	
1325	6.51	300	2.6	11.6	1.769	8.52	7.39	126.2	60.70		
1330	6.51	300	3.0	11.3	1.761	7.92	7.36	130.1	58.98	changed battery	
1335	6.32	300	3.4	10.4	1.762	7.73	7.33	132.8	64.45		
1340	6.27	300	3.8	9.9	1.740	7.50	7.30	136.0	60.73		
1345	6.33	300	4.2	9.8	1.736	7.55	7.28	136.9	63.12		
Sample Collection Method:		Date: 12/06/21		Time: 1345		Total Volume of Water Purged:					
Peristaltic Pump						4 Gallons					
Hach Test Kits				Sample Set							
Alkalinity (mg/L)		160		Parameter		Bottle		Pres.		Method	
Carbon Dioxide (mg/L)		20		VOCs		3-40 mL glass vial		HCL		EPA 8260C	
Ferrous Iron (mg/L)		0.13		Dissolved Iron		1-250 mL plastic (field filtered)		HNO3		6010C	
Hydrogen Sulfide (mg/L)		0.0		TOC		2-40mL glass vial		H2SO4		5310C	
1 Well Volume		5.0		M.E.E.P.		3-40 mL glass vial		HCL		RSK-175 mod	
VOCs only.				Nitrate/Nitrite/Chloride/Sulfate		1-500mL plastic		unpreserved		300, 353.2 300.0_28D	
				BOD		1-1000 mL plastic		unpreserved		5210B	
				COD		1-250 mL plastic		H2SO4		410.4	
				Sulfide		1-500mL plastic		NaOH/Zn Acetate		4500-S2-F	

Low Flow Sampling Record													
Site Name: IP-BP Hyde Park			Well ID: MW-14B				Well Diameter: 2"						
Samplers: S. Connelly			Water Volume Calculation 1 inch= 0.041 6 inch= 1.4 1.5 inch= 0.092 8 inch= 2.5 2 inch= 0.163 10 inch= 4 4 inch= 0.64 = (Total Depth of Well - Depth to Water) × Casing volume per foot				Acceptance Criteria: Temp 3% pH ± 0.1 unit Sp. Cond. 3% ORP ± 10mV DO 10% Turbidity <50 NTU Drawdown <0.3'						
Weather: 28F, Cloudy													
Purging Data:						feet below top of PVC							
Method: Low Flow		Date: 12/07/21		Time: 1117 (hhmm)		Initial Depth to Water 4.18			Depth to Bottom 31.10				
Time hhmm	DTW (ft)	Pump Rate (ml/min)	Volume (gal.)	Temp (C°)	Sp. Cond (ms/cm)	DO (mg/L)	pH	ORP (mV)	Turb (NTU)	Comments:			
1118	5.36	300	0.0	11.2	1.958	4.84	7.08	-119.3	45.84				
1123	5.59	300	0.4	12.2	1.885	1.01	7.10	-173.0	72.52				
1128	5.59	301	0.8	12.6	1.777	0.83	7.15	-184.5	68.11				
1133	5.59	302	1.2	12.4	1.688	0.78	7.16	-191.5	67.83				
1138	5.59	303	1.6	12.6	1.636	0.76	7.17	-196.2	51.26				
1143	5.59	304	2.0	12.6	1.605	0.75	7.16	-200.1	33.17				
1148	5.59	305	2.4	12.6	1.580	0.73	7.16	-206.2	20.13				
1153	5.59	306	2.8	12.6	1.577	0.73	7.16	-200.4	14.45				
1158	5.59	307	3.2	12.6	1.564	0.71	7.15	-211.7	13.62				
1203	5.59	300	3.6	12.6	1.557	0.70	7.15	-214.8	9.86				
Sample Collection Method:		Date: 12/07/21		Time: 1203		Total Volume of Water Purged: 4.5 Gallons							
Hach Test Kits				Sample Set									
Alkalinity (mg/L)		300		Parameter		Bottle		Pres.		Method			
Carbon Dioxide (mg/L)		35		VOCs		☒		3-40 mL glass vial		HCL			
Ferrous Iron (mg/L)		0.04		Dissolved Iron		☐		1-250 mL plastic (field filtered)		HNO3			
Hydrogen Sulfide (mg/L)		1.0		TOC		☐		2-40mL glass vial		H2SO4			
1 Well Volume		4.4		M.E.E.P.		☐		3-40 mL glass vial		HCL			
VOCs only				Nitrate/Nitrite/ Chloride/Sulfate		☐		1-500mL plastic		unpreserved			
				BOD		☐		1-1000 mL plastic		unpreserved		300, 353.2 300.0_28D	
				COD		☐		1-250 mL plastic		H2SO4		5210B	
				Sulfide		☐		1-500mL plastic		NaOH/Zn Acetate		410.4 4500-S2-F	

Low Flow Sampling Record										
Site Name: IP-BP Hyde Park			Well ID: MW-16A				Well Diameter: 2"		Acceptance Criteria: Temp 3% pH ± 0.1 unit Sp. Cond. 3% ORP ± 10mV DO 10% Turbidity <50 NTU Drawdown <0.3'	
Samplers:			Water Volume Calculation							
S. Connelly			1 inch= 0.041 6 inch= 1.4 1.5 inch= 0.092 8 inch= 2.5 2 inch= 0.163 10 inch= 4 4 inch= 0.64							
Weather: 30F, Mostly Cloudy			= (Total Depth of Well - Depth to Water) × Casing volume per foot							
Purging Data:							feet below top of PVC			
Method: Low Flow		Date: 12/07/21		Time: 1306 (hhmm)		Initial Depth to Water: 2.71		Depth to Bottom: 19.25		
Time hhmm	DTW (ft)	Pump Rate (ml/min)	Volume (gal.)	Temp (C°)	Sp. Cond (ms/cm)	DO (mg/L)	pH	ORP (mV)	Turb (NTU)	Comments:
1307	3.58	200	0.0	11.8	2.790	2.97	6.87	-34.6	2.74	
1312	4.79	200	0.3	12.3	2.870	1.12	6.87	-66.6	2.95	
1317	6.65	200	0.5	12.4	2.860	0.95	6.87	-56.8	6.28	
1322	7.93	200	0.8	12.4	2.773	1.61	6.92	-28.1	7.19	
1327	9.37	200	1.1	12.3	2.654	3.18	6.97	43.1	7.39	
1332	11.42	200	1.3	12.3	2.646	3.43	6.97	78.9	7.63	
1337	12.18	200	1.6	12.3	2.648	3.41	6.98	85.3	8.02	
1342	13.55	200	1.8	12.4	2.647	3.42	6.96	91.6	8.25	
1347	14.84	200	2.1	12.4	2.645	3.43	6.96	97.2	8.47	
1352	14.94	200	2.4							
Sample Collection Method: Peristaltic Pump		Date: 12/07/21		Time: 1352		Total Volume of Water Purged: 2.5 Gallons				
Hach Test Kits				Sample Set						
Alkalinity (mg/L)		460		Parameter		Bottle		Pres.		Method
Carbon Dioxide (mg/L)		50		VOCs		3-40 mL glass vial		HCL		EPA 8260C
Ferrous Iron (mg/L)		0.00		Dissolved Iron		1-250 mL plastic (field filtered)		HNO3		6010C
Hydrogen Sulfide (mg/L)		0.0		TOC		2-40mL glass vial		H2SO4		5310C
1 Well Volume		2.8		M.E.E.P.		3-40 mL glass vial		HCL		RSK-175 mod
Water in flushmount. All stable except drawdown, grab sampled.				Nitrate/Nitrite/Chloride/Sulfate		1-500mL plastic		unpreserved		300, 353.2 300.0_28D
				BOD		1-1000 mL plastic		unpreserved		5210B
				COD		1-250 mL plastic		H2SO4		410.4
				Sulfide		1-500mL plastic		NaOH/Zn Acetate		4500-S2-F

Low Flow Sampling Record											
Site Name: IP-BP Hyde Park				Well ID: MW-16B				Well Diameter: 2"		Acceptance Criteria: Temp 3% pH ± 0.1 unit Sp. Cond. 3% ORP ± 10mV DO 10% Turbidity <50 NTU Drawdown <0.3'	
Samplers: S. Connelly				Water Volume Calculation 1 inch= 0.041 6 inch= 1.4 1.5 inch= 0.092 8 inch= 2.5 2 inch= 0.163 10 inch= 4 4 inch= 0.64 = (Total Depth of Well - Depth to Water) × Casing volume per foot							
Weather: 30F, Cloudy											
Purging Data:								feet below top of PVC			
Method: Low Flow		Date: 12/07/21		Time: 1417 (hhmm)		Initial Depth to Water: 2.74		Depth to Bottom: 39.12			
Time hhmm	DTW (ft)	Pump Rate (ml/min)	Volume (gal.)	Temp (C°)	Sp. Cond (ms/cm)	DO (mg/L)	pH	ORP (mV)	Turb (NTU)	Comments:	
1418	2.95	400	0.0	11.2	1.221	4.71	7.24	-84.7	4.46		
1423	3.01	400	0.5	12.1	1.104	0.78	7.15	-201.6	2.64		
1428	3.12	400	1.1	12.1	1.125	0.77	7.14	-212.7	2.90		
1433	3.12	400	1.6	12.1	1.173	0.75	7.13	-225.4	2.90		
1438	3.12	400	2.1	12.1	1.218	0.72	7.12	-236.4	1.54		
1443	3.12	400	2.6	12.0	1.261	0.71	7.11	-246.6	1.87		
1448	3.12	400	3.2	12.1	1.299	0.69	7.11	-255.2	1.01		
1453	3.12	400	3.7	12.1	1.315	0.66	7.10	-260.7	0.96		
1458	3.12	400	4.2	12.1	1.318	0.65	7.10	-261.4	0.84		
Sample Collection Method: Peristaltic Pump		Date: 12/07/21		Time: 1458		Total Volume of Water Purged: 4.5 Gallons					
Hach Test Kits				Sample Set							
Alkalinity (mg/L)		380		Parameter		Bottle		Pres.		Method	
Carbon Dioxide (mg/L)		35		VOCs		3-40 mL glass vial		HCL		EPA 8260C	
Ferrous Iron (mg/L)		0.15		Dissolved Iron		1-250 mL plastic (field filtered)		HNO3		6010C	
Hydrogen Sulfide (mg/L)		0.3		TOC		2-40mL glass vial		H2SO4		5310C	
1 Well Volume		5.9		M.E.E.P.		3-40 mL glass vial		HCL		RSK-175 mod	
				Nitrate/Nitrite/Chloride/Sulfate		1-500mL plastic		unpreserved		300, 353.2 300.0_28D	
				BOD		1-1000 mL plastic		unpreserved		5210B	
				COD		1-250 mL plastic		H2SO4		410.4	
				Sulfide		1-500mL plastic		NaOH/Zn Acetate		4500-S2-F	

Low Flow Sampling Record											
Site Name: IP-BP Hyde Park			Well ID: MW-17A				Well Diameter: 2"		Acceptance Criteria: Temp 3% pH ± 0.1 unit Sp. Cond. 3% ORP ± 10mV DO 10% Turbidity <50 NTU Drawdown <0.3'		
Samplers:			Water Volume Calculation								
E. Au			1 inch= 0.041 6 inch= 1.4								
M.A. Kropovitch			1.5 inch= 0.092 8 inch= 2.5								
Weather: 29F, Cloudy			2 inch= 0.163 10 inch= 4								
			4 inch= 0.64								
			= (Total Depth of Well - Depth to Water) × Casing volume per foot								
Purging Data:						feet below top of PVC					
Method: Low Flow		Date: 12/08/21		Time: 0930 (hhmm)		Initial Depth to Water 3.11		Depth to Bottom 16.15			
Time	DTW	Pump Rate	Volume	Temp	Sp. Cond	DO	pH	ORP	Turb	Comments:	
hhmm	(ft)	(ml/min)	(gal.)	(C°)	(ms/cm)	(mg/L)		(mV)	(NTU)		
0935	3.55	300	0.0	13.2	0.929	0.63	8.23	-131.0	21.74		
0940	3.65	300	0.4	13.3	0.950	0.45	7.96	-127.8	34.18		
0945	3.77	300	0.8	13.6	0.795	0.34	7.69	-114.7	34.01		
0950	3.86	300	1.2	13.5	0.796	0.30	7.64	-114.5	34.98		
0955	3.91	300	1.6	13.8	0.799	0.29	7.62	-114.8	25.69		
1000	3.96	300	2.0	13.8	0.799	0.27	7.62	-116.6	20.05		
1005	3.98	300	2.4	13.8	0.801	0.26	7.61	-117.2	14.46		
1010	4.02	300	2.8	14.0	0.804	0.26	7.60	-117.9	17.49		
1015	4.04	300	3.2	13.9	0.805	0.25	7.60	-119.0	12.15		
1020	4.07	300	3.6	14.1	0.805	0.25	7.60	-120.4	11.75		
1025	4.10	300	4.0	13.9	0.804	0.25	7.60	-120.8	10.93		
Sample Collection Method: Peristaltic Pump		Date: 12/08/21		Time: 1025		Total Volume of Water Purged: 5 Gallons					
Hach Test Kits				Sample Set							
Alkalinity (mg/L)		420		Parameter		Bottle		Pres.		Method	
Carbon Dioxide (mg/L)		20		VOCs		3-40 mL glass vial		HCL		EPA 8260C	
Ferrous Iron (mg/L)		0.56		Dissolved Iron		1-250 mL plastic (field filtered)		HNO3		6010C	
Hydrogen Sulfide (mg/L)		0.0		TOC		2-40mL glass vial		H2SO4		5310C	
1 Well Volume		2.1		M.E.E.P.		3-40 mL glass vial		HCL		RSK-175 mod	
				Nitrate/Nitrite/Chloride/Sulfate		1-500mL plastic		unpreserved		300, 353.2 300.0_28D	
				BOD		1-1000 mL plastic		unpreserved		5210B	
				COD		1-250 mL plastic		H2SO4		410.4	
				Sulfide		1-500mL plastic		NaOH/Zn Acetate		4500-S2-F	

Low Flow Sampling Record											
Site Name: IP-BP Hyde Park			Well ID: MW-17B				Well Diameter: 2"			Acceptance Criteria: Temp 3% pH ± 0.1 unit Sp. Cond. 3% ORP ± 10mV DO 10% Turbidity <50 NTU Drawdown <0.3'	
Samplers:			Water Volume Calculation								
E. Au			1 inch= 0.041 6 inch= 1.4								
M.A. Kropovitch			1.5 inch= 0.092 8 inch= 2.5								
Weather: 30F, Cloudy			2 inch= 0.163 10 inch= 4								
			4 inch= 0.64								
			= (Total Depth of Well - Depth to Water) × Casing volume per foot								
Purging Data:						feet below top of PVC					
Method: Low Flow		Date: 12/08/21		Time: 1103 (hhmm)		Initial Depth to Water: 2.50			Depth to Bottom: 30.92		
Time hhmm	DTW (ft)	Pump Rate (ml/min)	Volume (gal.)	Temp (C°)	Sp. Cond (ms/cm)	DO (mg/L)	pH	ORP (mV)	Turb (NTU)	Comments:	
1110	3.50	275	0.0	12.3	1.261	0.30	6.28	-219.5	221.30		
1115	4.12	275	0.4	12.5	1.269	0.24	6.41	-263.1	222.60		
1120	4.08	275	0.7	12.7	1.637	0.22	6.45	-280.5	172.18		
1125	4.03	275	1.1	12.9	1.607	0.20	6.47	-286.8	124.76		
1130	4.01	275	1.5	12.9	1.592	0.19	6.49	-291.2	102.94		
1135	4.01	275	1.8	13.0	1.578	0.18	6.51	-293.9	86.54	Bubbles in tubing.	
1140	4.01	275	2.2	13.0	1.568	0.18	6.51	-295.6	77.92		
1145	4.01	275	2.5	13.1	1.562	0.18	6.52	-297.6	80.01		
1150	4.01	275	2.9	13.0	1.556	0.18	6.53	-299.6	75.21		
1155	4.01	275	3.3	13.1	1.547	0.17	6.54	-301.5	76.09		
1200	4.01	275	3.6	13.0	1.547	0.17	6.54	-302.6	78.50		
1205	4.01	275	4.0	13.0	1.551	0.17	6.54	-302.4	77.5		
1210	4.01	275	4.4	13.1	1.547	0.17	6.54	-303.2	80.78		
1215	4.01	275	4.7	12.9	1.550	0.17	6.55	-304.6	76.7		
1220	4.01	275	5.1	13.1	1.546	0.17	6.54	-303.3	80.32		
Sample Collection Method: Peristaltic Pump		Date: 12/08/21		Time: 1245		Total Volume of Water Purged: 8 gallons					
Hach Test Kits				Sample Set							
Alkalinity (mg/L)		485		Parameter		Bottle		Pres.		Method	
Carbon Dioxide (mg/L)		45		VOCS		3-40 mL glass vial		HCL		EPA 8260C	
Ferrous Iron (mg/L)		0.69		Dissolved Iron		1-250 mL plastic (field filtered)		HNO3		6010C	
Hydrogen Sulfide (mg/L)		>5.0		TOC		2-40mL glass vial		H2SO4		5310C	
1 Well Volume		4.5		M.E.E.P.		3-40 mL glass vial		HCL		RSK-175 mod	
H2S odor. Well off gassing after start of pumping. Gas pushed water up and out of the well for > 1min. Before dying down. Made water turbid. Effervescence during sampling.				Nitrate/Nitrite/ Chloride/Sulfate		1-500mL plastic		unpreserved		300, 353.2 300.0_28D	
				BOD		1-1000 mL plastic		unpreserved		5210B	
				COD		1-250 mL plastic		H2SO4		410.4	
				Sulfide		1-500mL plastic		NaOH/Zn Acetate		4500-S2-F	

Low Flow Sampling Record											
Site Name: IP-BP Hyde Park			Well ID: MW-18A				Well Diameter: 2"		Acceptance Criteria: Temp 3% pH ± 0.1 unit Sp. Cond. 3% ORP ± 10mV DO 10% Turbidity <50 NTU Drawdown <0.3'		
Samplers:			Water Volume Calculation								
E. Au			1 inch= 0.041 6 inch= 1.4								
M.A. Kropovitch			1.5 inch= 0.092 8 inch= 2.5								
Weather: 30F, Breezy, Partly Cloudy			2 inch= 0.163 10 inch= 4								
			4 inch= 0.64								
			= (Total Depth of Well - Depth to Water) × Casing volume per foot								
Purging Data:						feet below top of PVC					
Method: Low Flow		Date: 12/07/21		Time: 0920 (hhmm)		Initial Depth to Water 4.23		Depth to Bottom 17.76			
Time	DTW	Pump Rate	Volume	Temp	Sp. Cond	DO	pH	ORP	Turb	Comments:	
hhmm	(ft)	(ml/min)	(gal.)	(C°)	(ms/cm)	(mg/L)		(mV)	(NTU)		
0925	4.41	250	0.0	10.7	0.969	1.33	7.66	-36.9	11.16		
0930	4.79	250	0.3	12.2	0.976	0.45	7.32	-44.1	8.83		
0935	5.10	250	0.7	12.8	0.930	0.35	7.26	-57.2	8.85		
0940	5.34	250	1.0	12.4	0.976	0.31	7.23	-61.4	9.68		
0945	5.45	250	1.3	12.2	0.976	0.29	7.22	-62.3	11.22		
0950	5.57	250	1.7	12.2	0.973	0.29	7.21	-64.3	12.68		
0955	5.60	250	2.0	12.7	0.972	0.27	7.20	-66.5	19.05		
1000	5.64	250	2.3	13.1	0.970	0.27	7.21	-69.5	12.65		
1005	5.67	250	2.6	12.8	0.968	0.26	7.23	-71.1	15.03		
1010	5.75	250	3.0	13.1	0.964	0.26	7.22	-71.9	19.49		
1015	5.76	250	3.3	12.6	0.962	0.25	7.22	-71.4	22.52		
Sample Collection Method:		Date: 12/07/21		Time: 1015		Total Volume of Water Purged: 4 Gallons					
Peristaltic Pump											
Hach Test Kits				Sample Set							
Alkalinity (mg/L)		360		Parameter		Bottle		Pres.		Method	
Carbon Dioxide (mg/L)		40		VOCs		3-40 mL glass vial		HCL		EPA 8260C	
Ferrous Iron (mg/L)		1.44		Dissolved Iron		1-250 mL plastic (field filtered)		HNO3		6010C	
Hydrogen Sulfide (mg/L)		0.0		TOC		2-40mL glass vial		H2SO4		5310C	
1 Well Volume		2.2		M.E.E.P.		3-40 mL glass vial		HCL		RSK-175 mod	
				Nitrate/Nitrite/Chloride/Sulfate		1-500mL plastic		unpreserved		300, 353.2 300.0_28D	
				BOD		1-1000 mL plastic		unpreserved		5210B	
				COD		1-250 mL plastic		H2SO4		410.4	
				Sulfide		1-500mL plastic		NaOH/Zn Acetate		4500-S2-F	

Low Flow Sampling Record										
Site Name: IP-BP Hyde Park			Well ID: MW-18B				Well Diameter: 2"			
Samplers: E. Au M.A. Kropovitch			Water Volume Calculation 1 inch= 0.041 6 inch= 1.4 1.5 inch= 0.092 8 inch= 2.5 2 inch= 0.163 10 inch= 4 4 inch= 0.64 = (Total Depth of Well - Depth to Water) × Casing volume per foot				Acceptance Criteria: Temp 3% pH ± 0.1 unit Sp. Cond. 3% ORP ± 10mV DO 10% Turbidity <50 NTU Drawdown <0.3'			
Weather: 30F, Cloudy										
Purging Data:							feet below top of PVC			
Method: Low Flow		Date: 12/07/21		Time: 1048 (hhmm)		Initial Depth to Water: 4.49		Depth to Bottom: 37.73		
Time hhmm	DTW (ft)	Pump Rate (ml/min)	Volume (gal.)	Temp (C°)	Sp. Cond (ms/cm)	DO (mg/L)	pH	ORP (mV)	Turb (NTU)	Comments:
1050	4.49	250	0.0	11.2	0.399	3.27	7.30	-105.6	9.63	
1055	4.69	250	0.3	12.1	0.640	1.99	7.18	-197.2	7.75	
1100	5.25	250	0.7	12.2	0.642	1.82	7.09	-215.2	8.56	
1105	4.74	250	1.0	12.3	0.753	1.16	6.98	-237.0	5.99	
1110	4.75	250	1.3	12.3	0.811	0.81	6.94	-253.0	11.42	
1115	4.72	250	1.7	12.3	0.820	0.65	6.89	-265.0	18.79	
1120	4.75	250	2.0	12.5	0.390	0.57	6.87	-272.1	12.15	
1125	4.75	250	2.3	12.3	0.850	0.50	6.87	-279.2	8.02	
1130	4.75	250	2.6	12.3	0.865	0.45	6.86	-281.9	4.92	
1135	4.75	250	3.0	12.5	0.882	0.39	6.86	-286.9	5.11	
1140	4.75	250	3.3	12.3	0.891	0.35	6.87	-292.2	5.64	
1145	4.75	250	3.6	12.3	0.901	0.32	6.86	-294.1	8.87	
1150	4.75	250	4.0	12.4	0.918	0.29	6.85	-298.4	9.64	
Sample Collection Method: Peristaltic Pump		Date: 12/07/21		Time: 1150		Total Volume of Water Purged: 4.5 gallons				
Hach Test Kits				Sample Set						
Alkalinity (mg/L)		380		Parameter		Bottle		Pres.		Method
Carbon Dioxide (mg/L)		45		VOCs		3-40 mL glass vial		HCL		EPA 8260C
Ferrous Iron (mg/L)		0.27		Dissolved Iron		1-250 mL plastic (field filtered)		HNO3		6010C
Hydrogen Sulfide (mg/L)		5.0		TOC		2-40mL glass vial		H2SO4		5310C
1 Well Volume		5.4		M.E.E.P.		3-40 mL glass vial		HCL		RSK-175 mod
				Nitrate/Nitrite/Chloride/Sulfate		1-500mL plastic		unpreserved		300, 353.2 300.0_28D
				BOD		1-1000 mL plastic		unpreserved		5210B
				COD		1-250 mL plastic		H2SO4		410.4
				Sulfide		1-500mL plastic		NaOH/Zn Acetate		4500-S2-F

Low Flow Sampling Record										
Site Name: IP-BP Hyde Park			Well ID: MW-19B				Well Diameter: 2"		Acceptance Criteria: Temp 3% pH ± 0.1 unit Sp. Cond. 3% ORP ± 10mV DO 10% Turbidity <50 NTU Drawdown <0.3'	
Samplers:			Water Volume Calculation							
E. Au			1 inch= 0.041 6 inch= 1.4							
M.A. Kropovitch			1.5 inch= 0.092 8 inch= 2.5							
Weather: 30F, Cloudy			2 inch= 0.163 10 inch= 4							
			4 inch= 0.64							
			= (Total Depth of Well - Depth to Water) × Casing volume per foot							
Purging Data:						feet below top of PVC				
Method: Low Flow		Date: 12/07/21		Time: 1323 (hhmm)		Initial Depth to Water: 4.63		Depth to Bottom: 37.65		
Time (hhmm)	DTW (ft)	Pump Rate (ml/min)	Volume (gal.)	Temp (C°)	Sp. Cond (ms/cm)	DO (mg/L)	pH	ORP (mV)	Turb (NTU)	Comments:
1325	4.84	350	0.0	11.5	0.622	1.16	7.74	-174.4	6.85	
1330	4.85	350	0.5	12.4	0.855	0.57	7.48	-182.1	6.14	
1335	4.81	350	0.9	12.4	1.100	0.40	7.31	-192.0	9.26	
1340	4.85	350	1.4	12.1	1.108	0.36	7.29	-201.6	7.31	
1345	4.80	350	1.8	12.2	1.117	0.33	7.26	-232.7	10.39	
1350	4.80	350	2.3	12.1	1.252	0.30	7.29	-261.3	19.42	
1355	4.79	350	2.8	12.2	1.254	0.30	7.21	-262.1	20.16	
1400	4.84	350	3.2	11.8	1.291	0.29	7.20	-270.6	25.83	
1405	4.80	350	3.7	12.3	1.326	0.27	7.18	-276.5	17.37	
1410	4.85	350	4.2	12.1	1.357	0.27	7.16	-280.7	18.63	
1415	4.88	350	4.6	12.1	1.385	0.26	7.16	-283.9	12.35	
1420	4.81	350	5.1	12.1	1.405	0.25	7.14	-286.0	13.19	
1425	4.89	350	5.5	11.9	1.427	0.25	7.13	-287.5	17.8	
1430	4.82	350	6.0	12.0	1.435	0.24	7.12	-288.4	14.29	
1435	4.81	350	6.5	11.8	1.445	0.24	7.12	-288.9	14.88	
Sample Collection Method: Peristaltic Pump		Date: 12/07/21		Time: 1435		Total Volume of Water Purged: 7.5 gallons				
Hach Test Kits				Sample Set						
Alkalinity (mg/L)		340		Parameter		Bottle		Pres.		Method
Carbon Dioxide (mg/L)		25		VOCs		3-40 mL glass vial		HCL		EPA 8260C
Ferrous Iron (mg/L)		0.1		Dissolved Iron		1-250 mL plastic (field filtered)		HNO3		6010C
Hydrogen Sulfide (mg/L)		2.0		TOC		2-40mL glass vial		H2SO4		5310C
1 Well Volume		5.4		M.E.E.P.		3-40 mL glass vial		HCL		RSK-175 mod
VOCs only.				Nitrate/Nitrite/Chloride/Sulfate		1-500mL plastic		unpreserved		300, 353.2 300.0_28D
				BOD		1-1000 mL plastic		unpreserved		5210B
				COD		1-250 mL plastic		H2SO4		410.4
				Sulfide		1-500mL plastic		NaOH/Zn Acetate		4500-S2-F

Appendix B

Data Usability Summary Report

DATA USABILITY SUMMARY REPORT

**FORMER CARBORUNDUM COMPANY
HYDE PARK FACILITY
TOWN OF NIAGARA, NIAGARA COUNTY, NY
SITE ID 932036**

Analyses Performed by:

**EUROFINS TESTAMERICA
AMHERST, NEW YORK**

Prepared by:

**AECOM
ONE JOHN JAMES AUDUBON PARKWAY, SUITE 210
AMHERST, NY 14228**

JANUARY 2022

TABLE OF CONTENTS

	<u>Page No.</u>
I. INTRODUCTION	1
II. ANALYTICAL METHODOLOGIES AND DATA VALIDATION PROCEDURES	1
III. DATA DELIVERABLE COMPLETENESS	2
IV. SAMPLE RECEIPT/PRESERVATION/HOLDING TIMES.....	2
V. NON-CONFORMANCES.....	3
VI. SAMPLE RESULTS AND REPORTING	3
VII. SUMMARY	3

TABLES (Following Text)

Table 1	Validated Groundwater Sample Analytical Results
Table 2	Validated Field QC Sample Analytical Results

ATTACHMENTS

Attachment A	Support Documentation
--------------	-----------------------

I. INTRODUCTION

This Data Usability Summary Report (DUSR) has been prepared following the guidelines provided in New York State Department of Environmental Conservation (NYSDEC) Division of Environmental Remediation *DER-10, Technical Guidance for Site Investigation and Remediation, Appendix 2B - Guidance for Data Deliverables and the Development of Data Usability Summary Reports*, May 2010. Discussed in this DUSR are the analytical data for seventeen (17) groundwater samples, one (1) field duplicate, one (1) matrix spike/matrix spike duplicate (MS/MSD pair), and three (3) trip blanks collected on December 6-8, 2021.

The samples were collected at the former Carborundum Company, Hyde Park Facility site (Site ID Number 932036), located in the Town of Niagara, Niagara County, NY and sent to Eurofins TestAmerica (TA) for analysis. TA is a New York State Department of Health (NYSDOH) Environmental Laboratory Approval Program (ELAP) certified laboratory.

II. ANALYTICAL METHODOLOGIES AND DATA VALIDATION PROCEDURES

The groundwater samples were analyzed for the following parameters (not all samples were analyzed for all parameters/analytes):

<u>Parameter</u>	<u>Method Number</u>
Select Chlorinated Volatile Organic Compounds (CVOCs)*	SW8260C
Dissolved Gases (methane, ethane, and ethene)	RSK SOP-175
Dissolved Iron	6010C
Anions (Chloride, Nitrate, Nitrite, and Sulfate)	EPA 300.0
Nitrate-Nitrite	EPA 353.2
Biochemical Oxygen Demand (BOD ₅)	SM 5210B
Chemical Oxygen Demand	EPA 410.4
Sulfide	SM 4500-S2E
Total Organic Carbon	SM 5310C

Notes:

* 1,1,1-Trichloroethane, 1,1-dichloroethane, 1,1-dichloroethene, cis-1,2-dichloroethene, trans-1,2-dichloroethene, chloroethane, tetrachloroethene, trichloroethene, and vinyl chloride.

A limited data validation was performed on the samples in accordance with the guidelines in the following USEPA Region II documents:

- *Validating Volatile Organic Compounds by Gas Chromatography/Mass Spectrometry SW-846 Method 8260B & 8260C*, SOP HW-24, Revision 4, October 2014;
- *ICP-AES Data Validation*, SOP HW-3a, Rev. 1, September 2016; and
- *Mercury and Cyanide Data Validation*, SOP HW-3c, Rev. 1, September 2016.

The limited data review included a review of: completeness of all required deliverables; holding times; QC results [blanks, instrument tunes, calibration standards, MS/MSD recoveries, duplicate precision, and laboratory control sample (LCS) recoveries] to determine if the data are within the protocol-required QC limits and specifications; a determination that all samples were analyzed using established and agreed upon analytical protocols; an evaluation of the raw data to confirm the results provided in the data summary sheets; and a review of laboratory data qualifiers.

Qualifications applied to the data during the limited data validation include ‘UJ’ (estimated quantitation limit), ‘J’ (estimated result), and ‘J-’ (estimated result, biased low). Definitions of USEPA data qualifiers are presented at the end of this text. The validated analytical results are presented on Table 1 and Table 2. Documentation supporting the qualification of data is presented in Attachment A. Only analytical deviations affecting data usability are discussed in this report.

III. DATA DELIVERABLE COMPLETENESS

Full deliverable data packages (i.e., NYSDEC ASP Category B or equivalent) were provided by the laboratory (where applicable) and included all reporting forms and raw data necessary to fully evaluate and verify the reported analytical results.

IV. SAMPLE RECEIPT/PRESERVATION/HOLDING TIMES

All samples were received by the laboratory intact, properly preserved, and under proper chain-of-custody (COC). All samples were analyzed within the required holding times (HT) with the following exceptions.

Sample MW-12B was analyzed several times for VOAs due to instrument failures. Due to the presence of headspace in the vial (due to the multiple analyses) the results may be biased low. Samples MW-18A and TB-120721 were received at the lab with headspace in the vial. The detected results in all these samples have been qualified ‘J-’ and the non-detect results qualified ‘UJ’.

V. NON-CONFORMANCES

Matrix Spike/Matrix Spike Duplicate

The percent recoveries of the nitrate-nitrite MS/MSD performed on samples MW-10A and MW-10B were below the lower QC limit. The nitrate-nitrite results in these samples have been qualified 'J' or 'UJ'.

Support documentation is presented in Attachment A.

VI. SAMPLE RESULTS AND REPORTING

A field duplicate was collected at location MW-5B, the FD exhibited good field and analytical precision.

All sample results were reported in accordance with method requirements and were adjusted for sample volume (where applicable). Results reported below the QL, but greater than the MDL, are qualified 'J' by the laboratory. Those results being reported from a secondary dilution have been qualified 'D'.

Several samples for VOA analysis were diluted due to foaming and the presence of high concentrations of target compounds. All of these samples had detections for one or more of the target compounds. The reporting limits for the non-detect compounds are elevated due to the dilutions utilized.

Sample MW-12B was analyzed several times for VOAs due to instrument failures. Due to the presence of headspace in the vial the results may be biased low. Samples MW-18A and TB-120721 were received at the lab with headspace in the vial. The detected results in all these samples have been qualified 'J-' and the non-detect results qualified 'UJ'.

VII. SUMMARY

All sample analyses were found to be compliant with the method criteria, except where previously noted. Those results qualified 'UJ' (estimated QL), 'J' (estimated result), or 'J-' (estimated, biased low) during the data review are considered conditionally usable. All other sample results are usable as reported. AECOM does not recommend the re-collection of any samples at this time.

Prepared By: Ann Marie Kropovitch, Chemist  Date: 1/8/22

Reviewed By: George E. Kisluk, Senior Chemist  Date: 1/17/22

DEFINITIONS OF USEPA REGION II/ DATA QUALIFIERS

- U** – The analyte was analyzed for, but was not detected above the reported sample quantitation limit.
- J** – The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.
- J-** – The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample, but biased low.
- UJ** – The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.
- R** – The sample results are rejected due to serious deficiencies in the ability to analyze the sample and meet quality control criteria. The presence or absence of the analyte cannot be verified.
- D** – The sample results are reported from a secondary dilution.

TABLE 1
VALIDATED GROUNDWATER SAMPLE ANALYTICAL RESULTS
HYDE PARK FACILITY

Location ID		MW- 5A	MW- 5B	MW- 5B	MW- 6	MW- 7A
Sample ID		MW- 5A	Duplicate - 120621	MW- 5B	MW- 6	MW- 7A
Matrix		Groundwater	Groundwater	Groundwater	Groundwater	Groundwater
Depth Interval (ft)		-	-	-	-	-
Date Sampled		12/06/21	12/06/21	12/06/21	12/08/21	12/08/21
Parameter	Units		Field Duplicate (1-1)			
Volatile Organic Compounds						
1,1,1-Trichloroethane	UG/L	1.0 U	2.0 U	2.0 U	2.0 U	4.0 U
1,1-Dichloroethane	UG/L	1.0	2.0 U	2.0 U	2.0 U	90
1,1-Dichloroethene	UG/L	1.0 U	2.0 U	2.0 U	2.0 U	4.0 U
1,2-Dichloroethene (cis)	UG/L	52	39	40	13	150
1,2-Dichloroethene (trans)	UG/L	1.0 U	2.0 U	2.0 U	2.0 U	4.0 U
Chloroethane	UG/L	0.60 J	2.0 U	2.0 U	2.0 U	16
Tetrachloroethene	UG/L	1.0 U	2.0 U	2.0 U	2.0 U	4.0 U
Trichloroethene	UG/L	1.0 U	2.0 U	2.0 U	2.0 U	7.3
Vinyl chloride	UG/L	62	130	140	98	150
Dissolved Gases						
Ethane	UG/L	7.2 J	7.5 U	7.5 U	NA	170 U
Ethene	UG/L	7.1	2.4 J	2.4 J	NA	150 U
Methane	UG/L	470	300	300	NA	13,000
Dissolved Metals						
Iron, Dissolved	MG/L	0.05 U	0.22	0.24	NA	1.5
Miscellaneous Parameters						
Biochemical Oxygen Demand (BOD)	MG/L	2.0 U	2.0 U	2.0 U	NA	7.9
Chemical Oxygen Demand (COD)	MG/L	17	33	35	NA	36
Chloride	MG/L	76	120	120	NA	14
Nitrate-Nitrite	MG/L	0.050 U	0.050 U	0.050 U	NA	0.050 U
Nitrate-Nitrogen	MG/L	0.47	0.25 U	0.25 U	NA	0.25 U
Nitrite-Nitrogen	MG/L	0.10 U	0.25 U	0.25 U	NA	0.25 U
Sulfate (as SO4)	MG/L	87	230	230	NA	89
Sulfide	MG/L	1.0 U	1.0 U	1.0 U	NA	0.80 J
Total Organic Carbon (TOC)	MG/L	1.5	4.6	4.5	NA	14

Flags assigned during chemistry validation are shown.

Made By _AMK_ 01/8/2022; Checked By GEK 1/17/2022

Detection Limits shown are PQL

TABLE 1
VALIDATED GROUNDWATER SAMPLE ANALYTICAL RESULTS
HYDE PARK FACILITY

Location ID		MW- 7B	MW-10A	MW-10B	MW-12B	MW-13B
Sample ID		MW- 7B	MW-10A	MW-10B	MW-12B	MW-13B
Matrix		Groundwater	Groundwater	Groundwater	Groundwater	Groundwater
Depth Interval (ft)		-	-	-	-	-
Date Sampled		12/08/21	12/06/21	12/06/21	12/07/21	12/06/21
Parameter	Units					
Volatile Organic Compounds						
1,1,1-Trichloroethane	UG/L	1.0 U	25 U	10 U	1.0 UJ	2.0 U
1,1-Dichloroethane	UG/L	1.0 U	25 U	10 U	0.40 J-	2.0 U
1,1-Dichloroethene	UG/L	1.0 U	25 U	10 U	1.0 UJ	2.0 U
1,2-Dichloroethene (cis)	UG/L	1.5	650	220	73 J-	3.7
1,2-Dichloroethene (trans)	UG/L	1.0 U	25 U	10 U	1.0 UJ	2.0 U
Chloroethane	UG/L	1.0 U	25 U	10 U	1.0 UJ	2.0 U
Tetrachloroethene	UG/L	1.0 U	25 U	10 U	1.0 UJ	2.0 U
Trichloroethene	UG/L	1.0 U	13 J	10 U	1.0 UJ	2.0 U
Vinyl chloride	UG/L	18	180	370	49 DJ-	6.4
Dissolved Gases						
Ethane	UG/L	7.5 U	7.5 U	170 U	7.5 U	NA
Ethene	UG/L	7.0 U	14	150 U	4.1 J	NA
Methane	UG/L	160	880	1,900	330	NA
Dissolved Metals						
Iron, Dissolved	MG/L	0.05 U	1.4	0.33	0.048 J	NA
Miscellaneous Parameters						
Biochemical Oxygen Demand (BOD)	MG/L	2.0 U	2.0 U	2.0 U	2.0 U	NA
Chemical Oxygen Demand (COD)	MG/L	10 U	26	40	100	NA
Chloride	MG/L	240	220	140	77	NA
Nitrate-Nitrite	MG/L	0.050 U	0.050 UJ	0.25 J	0.23	NA
Nitrate-Nitrogen	MG/L	0.25 U	0.25 U	0.25 U	0.24	NA
Nitrite-Nitrogen	MG/L	0.25 U	0.25 U	0.25 U	0.050 U	NA
Sulfate (as SO4)	MG/L	200	150	220	72	NA
Sulfide	MG/L	0.80 J	1.0 U	1.0 U	1.0 U	NA
Total Organic Carbon (TOC)	MG/L	4.6	2.0	4.6	6.3	NA

Flags assigned during chemistry validation are shown.

Made By _AMK_ 01/8/2022; Checked By GEK 1/17/2022

Detection Limits shown are PQL

TABLE 1
VALIDATED GROUNDWATER SAMPLE ANALYTICAL RESULTS
HYDE PARK FACILITY

Location ID		MW-14B	MW-16A	MW-16B	MW-17A	MW-17B
Sample ID		MW-14B	MW-16A	MW-16B	MW-17A	MW-17B
Matrix		Groundwater	Groundwater	Groundwater	Groundwater	Groundwater
Depth Interval (ft)		-	-	-	-	-
Date Sampled		12/07/21	12/07/21	12/07/21	12/08/21	12/08/21
Parameter	Units					
Volatile Organic Compounds						
1,1,1-Trichloroethane	UG/L	1.0 U	5.0 U	1.0 U	4.0 U	4.0 U
1,1-Dichloroethane	UG/L	1.0 U	5.0 U	1.0 U	13	7.3
1,1-Dichloroethene	UG/L	1.0 U	5.0 U	1.0 U	4.0 U	4.0 U
1,2-Dichloroethene (cis)	UG/L	1.0 U	8.2	2.1	48	31
1,2-Dichloroethene (trans)	UG/L	1.0 U	5.0 U	1.0 U	4.0 U	4.0 U
Chloroethane	UG/L	1.0 U	5.0 U	1.0 U	4.0 U	2.9 J
Tetrachloroethene	UG/L	1.0 U	5.0 U	1.0 U	4.0 U	4.0 U
Trichloroethene	UG/L	1.0 U	5.0 U	1.0 U	4.0 U	4.0 U
Vinyl chloride	UG/L	1.9	260	6.5	110	20
Dissolved Gases						
Ethane	UG/L	NA	7.5 U	170 U	9.4	170 U
Ethene	UG/L	NA	77	150 U	14	150 U
Methane	UG/L	NA	160	8,000	12,000	26,000
Dissolved Metals						
Iron, Dissolved	MG/L	NA	0.024 J	0.54	0.69	0.94
Miscellaneous Parameters						
Biochemical Oxygen Demand (BOD)	MG/L	NA	2.0 U	6.4	6.0 U	16
Chemical Oxygen Demand (COD)	MG/L	NA	52	16	52	13
Chloride	MG/L	NA	190	130	32	130
Nitrate-Nitrite	MG/L	NA	0.22	0.050 U	0.050 U	0.034 J
Nitrate-Nitrogen	MG/L	NA	0.42	0.050 U	0.25 U	0.25 U
Nitrite-Nitrogen	MG/L	NA	0.050 U	0.050 U	0.25 U	0.25 U
Sulfate (as SO ₄)	MG/L	NA	930	230	55	90
Sulfide	MG/L	NA	1.0 U	4.8	1.0 U	5.6
Total Organic Carbon (TOC)	MG/L	NA	11	7.2	4.1	12

Flags assigned during chemistry validation are shown.

Made By _AMK_ 01/8/2022; Checked By GEK 1/17/2022

Detection Limits shown are PQL

TABLE 1
VALIDATED GROUNDWATER SAMPLE ANALYTICAL RESULTS
HYDE PARK FACILITY

Location ID		MW-18A	MW-18B	MW-19B
Sample ID		MW-18A	MW-18B	MW-19B
Matrix		Groundwater	Groundwater	Groundwater
Depth Interval (ft)		-	-	-
Date Sampled		12/07/21	12/07/21	12/07/21
Parameter	Units			
Volatile Organic Compounds				
1,1,1-Trichloroethane	UG/L	1.0 UJ	2.0 U	1.0 U
1,1-Dichloroethane	UG/L	3.3 J-	2.0 U	1.0 U
1,1-Dichloroethene	UG/L	0.49 J-	2.0 U	1.0 U
1,2-Dichloroethene (cis)	UG/L	43 J-	47	1.8
1,2-Dichloroethene (trans)	UG/L	1.0 UJ	2.0 U	1.0 U
Chloroethane	UG/L	1.0 UJ	2.0 U	1.0 U
Tetrachloroethene	UG/L	1.0 UJ	2.0 U	1.0 U
Trichloroethene	UG/L	23 J-	2.0 U	1.0 U
Vinyl chloride	UG/L	2.3 J-	80	1.5
Dissolved Gases				
Ethane	UG/L	7.5 U	170 U	NA
Ethene	UG/L	7.0 U	150 U	NA
Methane	UG/L	4,000	13,000	NA
Dissolved Metals				
Iron, Dissolved	MG/L	1.4	0.32	NA
Miscellaneous Parameters				
Biochemical Oxygen Demand (BOD)	MG/L	2.0 U	14	NA
Chemical Oxygen Demand (COD)	MG/L	45	39	NA
Chloride	MG/L	53	98	NA
Nitrate-Nitrite	MG/L	0.050 U	0.029 J	NA
Nitrate-Nitrogen	MG/L	0.050 U	0.050 U	NA
Nitrite-Nitrogen	MG/L	0.050 U	0.050 U	NA
Sulfate (as SO4)	MG/L	120	190	NA
Sulfide	MG/L	1.0 U	8.0	NA
Total Organic Carbon (TOC)	MG/L	2.2	6.0	NA

Flags assigned during chemistry validation are shown.

Made By _AMK_ 01/8/2022; Checked By GEK 1/17/2022

Detection Limits shown are PQL

TABLE 2
VALIDATED FIELDQC SAMPLE ANALYTICAL RESULTS
HYDE PARK FACILITY

Location ID		FIELDQC	FIELDQC	FIELDQC
Sample ID		TB-120621	TB_120721	TB - 120821
Matrix		Water Quality	Water Quality	Water Quality
Depth Interval (ft)		-	-	-
Date Sampled		12/06/21	12/07/21	12/08/21
Parameter	Units	Trip Blank (1-1)	Trip Blank (1-1)	Trip Blank (1-1)
Volatile Organic Compounds				
1,1,1-Trichloroethane	UG/L	1.0 U	1.0 UJ	1.0 U
1,1-Dichloroethane	UG/L	1.0 U	1.0 UJ	1.0 U
1,1-Dichloroethene	UG/L	1.0 U	1.0 UJ	1.0 U
1,2-Dichloroethene (cis)	UG/L	1.0 U	1.0 UJ	1.0 U
1,2-Dichloroethene (trans)	UG/L	1.0 U	1.0 UJ	1.0 U
Chloroethane	UG/L	1.0 U	1.0 UJ	1.0 U
Tetrachloroethene	UG/L	1.0 U	1.0 UJ	1.0 U
Trichloroethene	UG/L	1.0 U	1.0 UJ	1.0 U
Vinyl chloride	UG/L	1.0 U	1.0 UJ	1.0 U

Flags assigned during chemistry validation are shown.

Made By: AMK 1/8/22

Checked By GEK1/17/22

Detection Limits shown are PQL

ATTACHMENT A
SUPPORT DOCUMENTATION

Laboratory Management Program LaMP Chain of Custody Record

BP/ARC Project Name: BP IPO Req Due Date (mm/dd/yy): Page ____ of ____
 BP/ARC Facility No: BP Hyde Park Lab Work Order Number: Rush TAT: Yes ____ No X

Lab Name:	Test America (Canton, OH)	BP/ARC Facility Address:	3425 Hyde Park Blvd	Consultant/Contractor:	AECOM
Lab Address:	4101 Shuffel Street NW, North Canton, OH 44720	City, State, ZIP Code:	Niagara, NY 14305	Consultant/Contractor Project No:	60481767.105.21.03H
Lab PM:	Lab Contact: Opal Johnson	Lead Regulatory Agency:	NYSDEC	Address:	1 John James Audubon Pkwy Ste 210, Amherst, NY 14228
Lab Phone:	330-497-9396 / 330-497-0772	California Global ID No.:		Consultant/Contractor PM:	James Kaczor
Lab Shipping Acct:		Entos Proposal No:		Phone:	716-923-1300

Lab Bottle Order No: Provision ____ OOC-BU ____ OOC-RM ____
 Other Info: Activity: Email EDD To: James.Kaczor@aecom.com BP/ARC Contractor X
 Invoice To: BP/ARC Contractor X

BP/ARC EBM: BP/ARC EBM: BP/ARC EBM:
 EBM Phone: EBM Phone: EBM Phone:
 EBM Email: EBM Email: EBM Email:

Lab No.	Sample Description	Date	Time	Requested Analyses																			Full Data Package
				Soil / Solid	Water / Liquid	Air / Vapor	Total Number of Containers	Unpreserved	HNO3	HCl	NaOH/Zn-acetate	H3PO4	8260C - VOCs	SM-4500 _S2_ F - Sulfide	410.4 - COD	RSK 175 - Dissolved Ga	5310 C - TOC	5210-BOD	300, 353.2, nitrate-nitrite	300.0_28D chloride, sulf	6010C - Dissolved Iron (field filtered)		
	MW-5A	12-6-21	1010		X		13	2	1	6	1		3	1	1	3	2	1	1	1			
	MW-5B	12-6-21	1145		X		13	2	1	6	1		3	1	1	3	2	1	1	1			
	MW-10A	12-6-21	1055		X		13	2	1	6	1		3	1	1	3	2	1	1	1			
	MW-10B	12-6-21	1330		X		39	6	3	18	3		9	3	3	9	6	3	3	3	m3/msd		
	Duplicate-120621	12-6-21	1120		X		13	2	1	6	1		3	1	1	3	2	1	1	1			
	MW-13B	12-6-21	1345		X		3			3													
	TB-120621	12-6-21	---		X		2			2													

Sampler's Name: E. Av. A. Krasovitch, S. Connolly
 Sampler's Company: AECOM
 Shipment Method: Dropoff at TA Buffalo, NY Ship Date:
 Shipment Tracking No: 412 3.0 #1

Special Instructions: PO #97842 Line 17: TA Buffalo run all samples due to TA Canton office move in Dec 2021.
 THIS LINE - LAB USE ONLY: Custody Seals in Place: Yes / No Temp Blank: Yes / No Cooler Temp on Receipt: ____ °F/C Trip Blank: Yes / No MS/MSD Sample Submitted: Yes / No

Case Narrative

Client: AECOM
Project/Site: BP Hyde Park

Job ID: 480-193105-1

Job ID: 480-193105-1

Laboratory: Eurofins Buffalo

Narrative

Job Narrative 480-193105-1

Comments

No additional comments.

Revision

The report being provided is a revision of the original report sent on 12/20/2021. The report (revision 1) is being revised due to: The need to add nitrite.

Receipt

The samples were received on 12/6/2021 3:45 PM. Unless otherwise noted below, the samples arrived in good condition, and where required, properly preserved and on ice. The temperatures of the 2 coolers at receipt time were 3.8° C and 4.2° C.

GC/MS VOA

Method 8260C: The following volatiles sample was diluted due to foaming at the time of purging during the original sample analysis: MW-13B (480-193105-6). Elevated reporting limits (RLs) are provided.

Method 8260C: The following samples were diluted to bring the concentration of target analytes within the calibration range: MW-5B (480-193105-2), MW-10A (480-193105-3), MW-10B (480-193105-4), MW-10B (480-193105-4[MS]), MW-10B (480-193105-4[MSD]) and Duplicate - 120621 (480-193105-5). Elevated reporting limits (RLs) are provided.

No additional analytical or quality issues were noted, other than those described above or in the Definitions/Glossary page.

HPLC/IC

Method 300.0: The following samples were diluted to bring the concentration of target analytes within the calibration range: MW-5B (480-193105-2), MW-10A (480-193105-3), MW-10B (480-193105-4) and Duplicate - 120621 (480-193105-5). Elevated reporting limits (RLs) are provided.

Method 300.0: The following sample was diluted due to the nature of the sample matrix: MW-5A (480-193105-1). Elevated reporting limits (RLs) are provided.

No additional analytical or quality issues were noted, other than those described above or in the Definitions/Glossary page.

GC VOA

Method RSK-175: The following samples were diluted to bring the concentration of target analytes within the calibration range: MW-5A (480-193105-1), MW-10A (480-193105-3), MW-10B (480-193105-4), MW-10B (480-193105-4[MS]) and MW-10B (480-193105-4[MSD]). Elevated reporting limits (RLs) are provided.

No additional analytical or quality issues were noted, other than those described above or in the Definitions/Glossary page.

Metals

No analytical or quality issues were noted, other than those described in the Definitions/Glossary page.

General Chemistry

No analytical or quality issues were noted, other than those described in the Definitions/Glossary page.

QC Sample Results

Client: AECOM
Project/Site: BP Hyde Park

Job ID: 480-193105-1

Method: 300.0 - Anions, Ion Chromatography (Continued)

Lab Sample ID: 480-193105-4 MSD

Matrix: Water

Analysis Batch: 607890

Client Sample ID: MW-10B

Prep Type: Total/NA

Analyte	Sample Result	Sample Qualifier	Spike Added	MSD Result	MSD Qualifier	Unit	D	%Rec	%Rec. Limits	RPD	RPD Limit
Nitrate as N	ND		25.0	24.9		mg/L		100	80 - 120	0	15

Method: 353.2 - Nitrogen, Nitrate-Nitrite

Lab Sample ID: MB 480-608486/4

Matrix: Water

Analysis Batch: 608486

Client Sample ID: Method Blank

Prep Type: Total/NA

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Nitrate Nitrite as N	ND		0.050	0.020	mg/L			12/11/21 12:07	1

Lab Sample ID: LCS 480-608486/5

Matrix: Water

Analysis Batch: 608486

Client Sample ID: Lab Control Sample

Prep Type: Total/NA

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec. Limits
Nitrate Nitrite as N	1.50	1.47		mg/L		98	90 - 110

Lab Sample ID: 480-193105-3 MS

Matrix: Water

Analysis Batch: 608486

Client Sample ID: MW-10A

Prep Type: Total/NA

Analyte	Sample Result	Sample Qualifier	Spike Added	MS Result	MS Qualifier	Unit	D	%Rec	%Rec. Limits
Nitrate Nitrite as N	ND	F1	1.00	0.866	F1	mg/L		87	90 - 110

Lab Sample ID: 480-193105-4 MS

Matrix: Water

Analysis Batch: 608486

Client Sample ID: MW-10B

Prep Type: Total/NA

Analyte	Sample Result	Sample Qualifier	Spike Added	MS Result	MS Qualifier	Unit	D	%Rec	%Rec. Limits
Nitrate Nitrite as N	0.25	F1	1.00	1.05	F1	mg/L		80	90 - 110

Lab Sample ID: 480-193105-4 MSD

Matrix: Water

Analysis Batch: 608486

Client Sample ID: MW-10B

Prep Type: Total/NA

Analyte	Sample Result	Sample Qualifier	Spike Added	MSD Result	MSD Qualifier	Unit	D	%Rec	%Rec. Limits	RPD	RPD Limit
Nitrate Nitrite as N	0.25	F1	1.00	0.907	F1	mg/L		66	90 - 110	15	20

Lab Sample ID: 480-193105-3 DU

Matrix: Water

Analysis Batch: 608486

Client Sample ID: MW-10A

Prep Type: Total/NA

Analyte	Sample Result	Sample Qualifier	DU Result	DU Qualifier	Unit	D	RPD	RPD Limit
Nitrate Nitrite as N	ND	F1	ND		mg/L		NC	20

Laboratory Management Program LaMP Chain of Custody Record

Page of

Rush TAT: Yes No X

BP/ARC Project Name: BP IPO
 BP/ARC Facility No: BP Hyde Park
 Req Due Date (mm/dd/yy):
 Lab Work Order Number:

Lab Name:	Test America (Canton, OH)		BP/ARC Facility Address:	3425 Hyde Park Blvd		Consultant/Contractor:	AECOM	
Lab Address:	4101 Shuffel Street NW, North Canton, OH 44720		City, State, ZIP Code:	Niagara, NY 14305		Consultant/Contractor Project No:	60481767.105.21.03H	
Lab PM:	Lab Contact: Opal Johnson		Lead Regulatory Agency:	NYSDEC		Address:	1 John James Audubon Pkwy Ste 210, Amherst, NY 14228	
Lab Phone:	330-497-9396 / 330-497-0772		California Global ID No.:			Consultant/Contractor PM:	James Kaczor	
Lab Shipping Acct:			Enfos Proposal No:			Phone:	716-923-1300	
Lab Bottle Order No:			Accounting Mode:	OOC-BU		Email EDD To:	James.Kaczor@aecom.com	
Other Info:			Provision	OOC-PM		Invoice To:	BP/ARC Contractor <u>X</u>	

Lab No.	Sample Description	Date	Time	Matrix		No. Containers / Preservative										Requested Analyses						Report Type & QC Level	
				Soil / Solid	Water / Liquid	Air / Vapor	Total Number of Containers	Unpreserved	HNO3	HCl	NaOH/Zn-acetate	H3PO4	8260C - VOCs	SM-4500 - S2 F-Sulfide	4104 - COD	RSK 175 - Dissolved Gases	5310 C - TOC	5210-BOD	300, 353, 2, nitrate-nitrite	300.0, 28D chloride, sulfate	6010C - Dissolved Iron (field filtered)	Standard	Full Data Package
1976	MW - 12B	12-7-21	1042		X		13	2	1	6	1		3	1	1	3	2	1	1	1	1		
1978	MW - 18A	12-7-21	1015		X		13	2	1	6	1		3	1	1	3	2	1	1	1	1		
	MW - 18B	12-7-21	1150		X		13	2	1	6	1		3	1	1	3	2	1	1	1	1		
	MW - 14B	12-7-21	1203				3			3													
	MW - 16A	12-7-21	1352		X		13	2	1	6	1		3	1	1	3	2	1	1	1	1		
	MW - 16B	12-7-21	1458		X		13	2	1	6	1		3	1	1	3	2	1	1	1	1		
	MW - 19B	12-7-21	1435		X		3			3													
	TB - 120721	12-7-21	-		X		3			2													

Sampler's Name:	Emily A ✓		Relinquished By / Affiliation	<i>Emily A</i>		Date	12/7/21	Time	16:05
Sampler's Company:	AECOM								
Shipment Method:	Dropoff at TA Buffalo, NY		Ship Date:						
Shipment Tracking No:									
Special Instructions:	PO #97842 Line 17: TA Buffalo run all samples due to TA Canton office move in Dec 2021.								
THIS LINE - LAB USE ONLY:		Custody Seals in Place: Yes / No	Temp Blank: Yes / No	Cooler Temp on Receipt: °F/C	Trip Blank: Yes / No	MS/MSD Sample Submitted: Yes / No	BP/ARC LaMP COC Rev. 6 01/01/2009		



480-193153 Chain of Custody

12/7/21 16:05

12/8/21 16:05

36 #1

12/8/21 16:05

36 #1

12/8/21 16:05

36 #1

12/8/21 16:05

36 #1

12/8/21 16:05

Case Narrative

Client: AECOM
Project/Site: BP Hyde Park

Job ID: 480-193153-1

Job ID: 480-193153-1

Laboratory: Eurofins Buffalo

Narrative

Job Narrative 480-193153-1

Comments

No additional comments.

Revision

The report being provided is a revision of the original report sent on 12/20/2021. The report (revision 1) is being revised due to: The need to add nitrite.

Receipt

The samples were received on 12/8/2021 8:00 AM. Unless otherwise noted below, the samples arrived in good condition, and where required, properly preserved and on ice. The temperature of the cooler at receipt was 3.5° C.

GC/MS VOA

Method 8260C: Surrogate recovery for the following sample was outside the upper control limit: TB_120721 (480-193153-8). This sample did not contain any target analytes; therefore, re-extraction and/or re-analysis was not performed.

Method 8260C: The following samples were diluted to bring the concentration of target analytes within the calibration range: MW-12B (480-193153-1), MW-18B (480-193153-3) and MW-16A (480-193153-5). Elevated reporting limits (RLs) are provided.

Method 8260C: Sample MW-12B (480-193153-1) was analyzed several times, due to instrumentation failures. Due to the headspace present in the vial the "DL" analysis may be biased low on recovery for the target analytes.

Method 8260C: The method requirement for no headspace was not met. The following volatile samples were analyzed with headspace in the sample container(s): MW-12B (480-193153-1), MW-18A (480-193153-2), and TB_120721 (480-193153-8).

No additional analytical or quality issues were noted, other than those described above or in the Definitions/Glossary page.

HPLC/IC

Method 300.0: The following samples were diluted to bring the concentration of target analytes within the calibration range: MW-16A (480-193153-5) and MW-16B (480-193153-6). Elevated reporting limits (RLs) are provided.

No additional analytical or quality issues were noted, other than those described above or in the Definitions/Glossary page.

GC VOA

Method RSK-175: The following samples were diluted to bring the concentration of target analytes within the calibration range: MW-12B (480-193153-1), MW-18A (480-193153-2), MW-18B (480-193153-3), and MW-16B (480-193153-6). Elevated reporting limits (RLs) are provided.

No additional analytical or quality issues were noted, other than those described above or in the Definitions/Glossary page.

Metals

No analytical or quality issues were noted, other than those described in the Definitions/Glossary page.

General Chemistry

Method SM 5310C: The matrix spikes for this batch were spiked at 50% normal spike amounts by the SOP. As recoveries were within acceptable margins for the spiked amount, the data has been reported. MW-12B (480-193153-1)

No additional analytical or quality issues were noted, other than those described above or in the Definitions/Glossary page.

Page of

Req Due Date (mm/dd/yy):

Rush TAT: Yes No X

Lab Work Order Number:

BP/ARC LaMP COC Rev. 6 01/01/2009

2.4, 2.9 #1

Case Narrative

Client: AECOM
Project/Site: BP Hyde Park

Job ID: 480-193204-1

Job ID: 480-193204-1

Laboratory: Eurofins Buffalo

Narrative

Job Narrative 480-193204-1

Comments

No additional comments.

Revision

The report being provided is a revision of the original report sent on 12/20/2021. The report (revision 1) is being revised due to: The need to add nitrite.

Receipt

The samples were received on 12/8/2021 2:20 PM. Unless otherwise noted below, the samples arrived in good condition, and where required, properly preserved and on ice. The temperatures of the 2 coolers at receipt time were 2.4° C and 2.9° C.

GC/MS VOA

Method 8260C: The following samples were diluted to bring the concentration of target analytes within the calibration range: MW - 7A (480-193204-1), MW - 17A (480-193204-3) and MW-6 (480-193204-5). Elevated reporting limits (RLs) are provided.

Method 8260C: The following volatiles sample was diluted due to foaming at the time of purging during the original sample analysis: MW - 17B (480-193204-4). Elevated reporting limits (RLs) are provided.

Method 8260C: The laboratory control sample (LCS) for analytical batch 480-608338 recovered outside control limits for the following analytes: Tetrachloroethene. These analytes were biased high in the LCS and were not detected in the associated samples; therefore, the data have been reported. The associated samples are: MW - 7A (480-193204-1), MW - 7B (480-193204-2), MW - 17A (480-193204-3), MW - 17B (480-193204-4), MW-6 (480-193204-5) and TB - 120821 (480-193204-6).

No additional analytical or quality issues were noted, other than those described above or in the Definitions/Glossary page.

HPLC/IC

Method 300.0: The following samples were diluted to bring the concentration of target analytes within the calibration range: MW - 7B (480-193204-2) and MW - 17B (480-193204-4). Elevated reporting limits (RLs) are provided.

Method 300.0: The following samples were diluted due to the nature of the sample matrix: MW - 7A (480-193204-1) and MW - 17A (480-193204-3). Elevated reporting limits (RLs) are provided.

No additional analytical or quality issues were noted, other than those described above or in the Definitions/Glossary page.

GC VOA

Method RSK-175: The following samples were diluted to bring the concentration of target analytes within the calibration range: MW - 7A (480-193204-1) and MW - 17B (480-193204-4). Elevated reporting limits (RLs) are provided.

Method RSK-175: The following samples were diluted to bring the concentration of target analytes within the calibration range: MW - 7A (480-193204-1), MW - 17A (480-193204-3) and MW - 17B (480-193204-4). Elevated reporting limits (RLs) are provided.

No additional analytical or quality issues were noted, other than those described above or in the Definitions/Glossary page.

Metals

No analytical or quality issues were noted, other than those described in the Definitions/Glossary page.

General Chemistry

No analytical or quality issues were noted, other than those described in the Definitions/Glossary page.

Appendix C

Monitoring Well Analytical Data Summary, 2007 to 2021

MONITORING WELL GROUNDWATER ANALYTICAL RESULT SUMMARY
HYDE PARK FACILITY
NIAGARA, NEW YORK

Well ID: MW- 1A

Date	PCE (µg/L)	TCE (µg/L)	Cis-1,2- DCE (µg/L)	Trans-1,2- DCE (µg/L)	1,1-DCE (µg/L)	Vinyl Chloride (µg/L)	Ethane (µg/L)	Ethene (µg/L)	Methane (µg/L)	1,1,1- Trichloroe thane (µg/L)	1,1- Dichloroe thane (µg/L)	Chloro ethane (µg/L)	Dissolved Iron (mg/L)	BOD (mg/L)	COD (mg/L)	TOC (mg/L)	Chloride (mg/L)	Sulfate (mg/L)	Sulfide (mg/L)	Nitrate (mg/L)	Nitrite (mg/L)
10/31/2007	5 U	5 U	5 U	5 U	5 U	2 U				5 U	5 U	5 U									
4/23/2008	5 U	5 U	5 U	5 U	5 U	2 U	1 U	1 U	2.6	5 U	5 U	5 U		2 U	6.02	1.53	112	109	1 U	0.05 U	0.05 U
10/27/2009	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	30	5 U	5 U	5 U		1.7 U	16.5 J	2	140 J	141	0.16 U	0 R	0.05 U

J Indicates an estimated value.
U Analyte was not detected above the reporting limit.
UJ The analyte was not detected. The reporting limit is an approximate value.
J- Indicates estimated value, biased low.
J+ Indicates estimated value, biased high.
D Result reported from a secondary dilution analysis.
R The sample results are rejected.

MONITORING WELL GROUNDWATER ANALYTICAL RESULT SUMMARY
HYDE PARK FACILITY
NIAGARA, NEW YORK

Well ID: MW- 1B

Date	PCE (µg/L)	TCE (µg/L)	Cis-1,2- DCE (µg/L)	Trans-1,2- DCE (µg/L)	1,1-DCE (µg/L)	Vinyl Chloride (µg/L)	Ethane (µg/L)	Ethene (µg/L)	Methane (µg/L)	1,1,1- Trichloroe thane (µg/L)	1,1- Dichloroe thane (µg/L)	Chloro ethane (µg/L)	Dissolved Iron (mg/L)	BOD (mg/L)	COD (mg/L)	TOC (mg/L)	Chloride (mg/L)	Sulfate (mg/L)	Sulfide (mg/L)	Nitrate (mg/L)	Nitrite (mg/L)
10/30/2007	5 U	5 U	11	5 U	5 U	16	0.36 J	0.97 J	160	5 U	5 U	5 U		2 U	5 UJ	4.23	97.6	301	1 U		
4/23/2008	5 U	5 U	1.2 J	5 U	5 U	1.9 J	1 U	1 U	64	5 U	0.71 J	5 U		2 U	13	4.06	70	181	1 U	0.05 U	0.05 U
10/27/2009	5 U	5 U	1.3 J	5 U	5 U	1.7 J	5 U	5 U	59	5 U	5 U	5 U		1.6 U	32.5 J	4.5	71.8 J	218	0.16 U	0 R	0.05 U

J Indicates an estimated value.
U Analyte was not detected above the reporting limit.
UJ The analyte was not detected. The reporting limit is an approximate value.
J- Indicates estimated value, biased low.
J+ Indicates estimated value, biased high.
D Result reported from a secondary dilution analysis.
R The sample results are rejected.

MONITORING WELL GROUNDWATER ANALYTICAL RESULT SUMMARY
HYDE PARK FACILITY
NIAGARA, NEW YORK

Well ID: MW- 2A

Date	PCE (µg/L)	TCE (µg/L)	Cis-1,2- DCE (µg/L)	Trans-1,2- DCE (µg/L)	1,1-DCE (µg/L)	Vinyl Chloride (µg/L)	Ethane (µg/L)	Ethene (µg/L)	Methane (µg/L)	1,1,1- Trichloroe thane (µg/L)	1,1- Dichloroe thane (µg/L)	Chloro ethane (µg/L)	Dissolved Iron (mg/L)	BOD (mg/L)	COD (mg/L)	TOC (mg/L)	Chloride (mg/L)	Sulfate (mg/L)	Sulfide (mg/L)	Nitrate (mg/L)	Nitrite (mg/L)
11/1/2007	5 U	0.91 J	9.8	5 U	5 U	1.9 J				5 U	7.1	4.9 J									
4/28/2008	5 U	5 U	0.38 J	5 U	2.4 J	2 U				2 J	14	1.2 J									
10/28/2009	5 U	5 U	5 U	5 U	6	1.3 J				7.6	26	1.2 J									
5/11/2010	5 U	5 U	5 U	5 U	4.3 J	1.2 J	5 U	5 U	30	4.9 J	18	1.7 J									

J Indicates an estimated value.
U Analyte was not detected above the reporting limit.
UJ The analyte was not detected. The reporting limit is an approximate value.
J- Indicates estimated value, biased low.
J+ Indicates estimated value, biased high.
D Result reported from a secondary dilution analysis.
R The sample results are rejected.

MONITORING WELL GROUNDWATER ANALYTICAL RESULT SUMMARY
HYDE PARK FACILITY
NIAGARA, NEW YORK

Well ID: MW- 2B

Date	PCE (µg/L)	TCE (µg/L)	Cis-1,2- DCE (µg/L)	Trans-1,2- DCE (µg/L)	1,1-DCE (µg/L)	Vinyl Chloride (µg/L)	Ethane (µg/L)	Ethene (µg/L)	Methane (µg/L)	1,1,1- Trichloroe thane (µg/L)	1,1- Dichloroe thane (µg/L)	Chloro ethane (µg/L)	Dissolved Iron (mg/L)	BOD (mg/L)	COD (mg/L)	TOC (mg/L)	Chloride (mg/L)	Sulfate (mg/L)	Sulfide (mg/L)	Nitrate (mg/L)	Nitrite (mg/L)
11/1/2007	5 U	5 U	48	5 U	5 U	59				5 U	5 U	5 U									
4/28/2008	5 U	5 U	41	5 U	5 U	62				5 U	5 U	5 U									
10/28/2009	5 U	5 U	9.1	5 U	5 U	16				5 U	5 U	5 U									
5/11/2010	5 U	5 U	3.7 J	5 U	5 U	7.6	1.9 J	55	2300	5 U	5 U	5 U									
10/20/2011	5 U	5 U	1.8 J	5 U	5 U	2.6 J				5 U	5 U	5 U									
6/13/2012	5 U	5 U	2.7 J	5 U	5 U	8.6				5 U	5 U	5 U									
8/30/2013	5 U	5 U	2.3 J	5 U	5 U	4 J				5 U	5 U	5 U									
4/3/2014	1 U	1 U	1	0.72 J	1 U	2.2				1 UJ	0.92 J	1 U									
11/20/2015	1 U	1 U	0.87 J	0.56 J	1 U	3.4				1 U	0.65 J	1 U									
4/19/2016	1.0 U	1.0 U	0.95 J	1.0 U	1.0 U	2.2				1.0 U	0.96 J	1.0 U									
9/12/2017	1.0 U	1.0 U	0.77 J	1.0 U	1.0 U	1.8				1.0 U	0.5 J	1.0 U									
4/25/2018	1.0 U	1.0 U	1.3	1.0 U	1.0 U	2.6				1.0 U	1.0 U	1.0 U									

J Indicates an estimated value.
U Analyte was not detected above the reporting limit.
UJ The analyte was not detected. The reporting limit is an approximate value.
J- Indicates estimated value, biased low.
J+ Indicates estimated value, biased high.
D Result reported from a secondary dilution analysis.
R The sample results are rejected.

MONITORING WELL GROUNDWATER ANALYTICAL RESULT SUMMARY
HYDE PARK FACILITY
NIAGARA, NEW YORK

Well ID: MW- 3A

Date	PCE (µg/L)	TCE (µg/L)	Cis-1,2- DCE (µg/L)	Trans-1,2- DCE (µg/L)	1,1-DCE (µg/L)	Vinyl Chloride (µg/L)	Ethane (µg/L)	Ethene (µg/L)	Methane (µg/L)	1,1,1- Trichloroe thane (µg/L)	1,1- Dichloroe thane (µg/L)	Chloro ethane (µg/L)	Dissolved Iron (mg/L)	BOD (mg/L)	COD (mg/L)	TOC (mg/L)	Chloride (mg/L)	Sulfate (mg/L)	Sulfide (mg/L)	Nitrate (mg/L)	Nitrite (mg/L)
10/31/2007	5 U	5 U	0.9 J	5 U	5 U	2 U	0.54 J	1 U	6	5 U	5 U	5 U		2 U	19 J	3.21	16.4	319	3.64		
4/24/2008	5 U	0.21 J	0.71 J	5 U	5 U	2 U	1 U	1 U	12	5 U	5 U	5 U		2 U	6.92	2.89	0.2 U	292	1 U	0.05 U	0.05 U
8/12/2008	5 U	5 U	0.89 J	5 U	5 U	5 U	5 U	5 U	25	5 U	5 U					2.6	17.6	318			
10/6/2008	5 U	1.9 J	11	5 U	5 U	5 U	5 U	5 U	19 J	5 U	5 U	5 U				2.3	19.4 J	347			
12/8/2008	5 U	1.4 J	5 U	5 U	5 U	5 U	5 U	5 U	7.7 J	5 U	5 U	5 U				4.9	23.3	444			
1/26/2009	5 U	5 U	1 J	5 U	5 U	5 U	5 U	5 U	7.3 J	5 U	5 U	5 U									
3/16/2009	5 U	5 U	0.99 J	5 U	5 U	5 U	5 U	5 U	5 J	5 U	5 U	5 U				3.7	27.3	334			
10/27/2009	5 U	5 U	5 U	5 U	5 U	5 U	5 U	5 U	14 J	5 U	5 U	5 U		1.9 U	25.6 J	2.2	15.9 J	250	0.16 U	0 R	0.05 U

J Indicates an estimated value.
U Analyte was not detected above the reporting limit.
UJ The analyte was not detected. The reporting limit is an approximate value.
J- Indicates estimated value, biased low.
J+ Indicates estimated value, biased high.
D Result reported from a secondary dilution analysis.
R The sample results are rejected.

MONITORING WELL GROUNDWATER ANALYTICAL RESULT SUMMARY
HYDE PARK FACILITY
NIAGARA, NEW YORK

Well ID: MW- 3B

Date	PCE (µg/L)	TCE (µg/L)	Cis-1,2- DCE (µg/L)	Trans-1,2- DCE (µg/L)	1,1-DCE (µg/L)	Vinyl Chloride (µg/L)	Ethane (µg/L)	Ethene (µg/L)	Methane (µg/L)	1,1,1- Trichloroe thane (µg/L)	1,1- Dichloroe thane (µg/L)	Chloro ethane (µg/L)	Dissolved Iron (mg/L)	BOD (mg/L)	COD (mg/L)	TOC (mg/L)	Chloride (mg/L)	Sulfate (mg/L)	Sulfide (mg/L)	Nitrate (mg/L)	Nitrite (mg/L)
10/31/2007	5 U	5 U	1.9 J	5 U	5 U	2.2	1 U	1 U	220	5 U	5 U	5 U		2 U	5 UJ	3.19	134	395	1 U		
4/25/2008	5 U	5 U	2.1 J	5 U	5 U	2.2	0.6 J	1 U	180	5 U	5 U	5 U		4.17	14.1	3.64	132	333	1 U	0.05 U	0.05 U
10/27/2009	5 U	5 U	1.5 J	5 U	5 U	2.9 J	5 U	5 U	170	5 U	5 U	5 U		2.2 U	16.5 J	3.8	121 J	254	0.9	0 R	0.05 U

J Indicates an estimated value.
U Analyte was not detected above the reporting limit.
UJ The analyte was not detected. The reporting limit is an approximate value.
J- Indicates estimated value, biased low.
J+ Indicates estimated value, biased high.
D Result reported from a secondary dilution analysis.
R The sample results are rejected.

MONITORING WELL GROUNDWATER ANALYTICAL RESULT SUMMARY
HYDE PARK FACILITY
NIAGARA, NEW YORK

Well ID: MW- 4A

Date	PCE (µg/L)	TCE (µg/L)	Cis-1,2- DCE (µg/L)	Trans-1,2- DCE (µg/L)	1,1-DCE (µg/L)	Vinyl Chloride (µg/L)	Ethane (µg/L)	Ethene (µg/L)	Methane (µg/L)	1,1,1- Trichloroe thane (µg/L)	1,1- Dichloroe thane (µg/L)	Chloro ethane (µg/L)	Dissolved Iron (mg/L)	BOD (mg/L)	COD (mg/L)	TOC (mg/L)	Chloride (mg/L)	Sulfate (mg/L)	Sulfide (mg/L)	Nitrate (mg/L)	Nitrite (mg/L)
10/31/2007	5 U	34	200	3.2 J	1.8 J	56	0.55 J	5.6	130	5 U	12	5 U		2 U	5 UJ	1.87	106	242	1 U		
4/29/2008	5 U	34	200	3.1 J	1.6 J	53	0.55 J	5.6	130	5 U	15	5 U		2 U	6.62	1.52	117	231	1 U	0.05 U	0.05 U
11/3/2009	5 U	130	110	5.7	2.5 J	41	5 U	4.6 J	83	5 U	17	5 U		2.6 U	50 U	1.7 J	97.1	244	0.16 U	0.1 U	0.05 U
5/14/2010	5 U	94	250	4.9 J	2.6 J	45	5 U	5.7	110	5 U	21	5 U		2.1 U	50 U	1.8	109	249	0.16 U	0.1 U	0.05 U
10/25/2011	5 U	160	150	8.1	3.8 J	73	5 U	12	170	5 U	18	5 U	0.0146 J	3.1 U	50 U	2.1	95.9 J	263 J	0.16 U	0.1 U	0.05 U
3/14/2012																					
3/15/2012	50 UJ	65 J	97 J	9.5 J	50 UJ	14 J	5.7	20	1200	50 UJ	18 J	50 UJ	0.0523 J			999	160	46.3			
6/12/2012	5 U	7.5	140	2.9 J	0.81 J	20	5 U	3.9 J	3700	5 U	5.4	7.8	3.22		1350	434	89.8	5 U		0.1 U	0.05 U
6/13/2012																			0.34		
6/25/2012														796							
11/29/2012	5 U	5.5	120	4.2 J	0.92 J	39	5 U	48	7900	5 U	3.6 J	21	4.85			397	37.8	5 U			
9/3/2013	5 U	4.2 J	31	3.5 J	5 U	11	1.4 J	60 J	11000	5 U	1.3 J	17		551 J	1040 J	251	82.9	1.6 J	0.074 J	0.1 UJ	0.05 U
1/22/2014	5 U	1.1 J	7.5	2.4 J	5 U	7.2	5 U	65	22000	5 U	5 U	12	39.4			362	87.3	5 U	0.16 U		
4/3/2014	1 U	1.2	3.7	2.1	1 U	4.1	4.2 J	47	25000	1 U	1 U	12	36.2	342	640	205	99	5 U	0.17	0.1 UJ	0.018 J
10/14/2014	1 U	0.57 J	5.3	2.2	1 U	5.8	3.5 J	56	19000 J	1 UJ	1.1	9.1	57.6			159	83.8	2.5 J	0.16 U		
11/18/2015	1 U	1.2	1.3	1 U	1 U	1.1	5.2	18	17000	1 U	1	3	14.5	70.6	443	36.6	123	5.6	0.085 J	0.1 U	0.05 U
4/21/2016	1.0 U	3.4	2.8	1.0 U	1.0 U	1.1	4.3 J	8.6	26000 D	1.0 U	1.4	3	9.67	34.3	181	20.4	179	7.6	0.069 J	0.10 U	0.050 U
9/11/2017	1.0 U	1.3	0.68 J	1.0 U	1.0 UJ	2.6	3.9	5.5	5400 D	1.0 U	1.4	2.7	11	27	48	17	26	2.1 J	1.0 U	0.25 U	0.050 UJ
4/23/2018	1.0 U	0.44 J	1.1	0.51 J	1.0 U	0.96 J	10 U	10 U	21000	1.0 U	1.8	2.5	14	7.6	23	7.2	110	3.7 J	1.0 U	0.25 U	0.050 UJ

J Indicates an estimated value.
U Analyte was not detected above the reporting limit.
UJ The analyte was not detected. The reporting limit is an approximate value.
J- Indicates estimated value, biased low.
J+ Indicates estimated value, biased high.
D Result reported from a secondary dilution analysis.
R The sample results are rejected.

MONITORING WELL GROUNDWATER ANALYTICAL RESULT SUMMARY
HYDE PARK FACILITY
NIAGARA, NEW YORK

Well ID: MW- 4B

Date	PCE (µg/L)	TCE (µg/L)	Cis-1,2- DCE (µg/L)	Trans-1,2- DCE (µg/L)	1,1-DCE (µg/L)	Vinyl Chloride (µg/L)	Ethane (µg/L)	Ethene (µg/L)	Methane (µg/L)	1,1,1- Trichloroe thane (µg/L)	1,1- Dichloroe thane (µg/L)	Chloro ethane (µg/L)	Dissolved Iron (mg/L)	BOD (mg/L)	COD (mg/L)	TOC (mg/L)	Chloride (mg/L)	Sulfate (mg/L)	Sulfide (mg/L)	Nitrate (mg/L)	Nitrite (mg/L)
10/31/2007	5 U	5 U	23	5 U	5 U	11	0.39 J	0.39 J	200	5 U	1.4 J	5 U		2 U	5.52 J	3.15	152	316	2.59		
4/29/2008	5 U	5 U	12	5 U	5 U	13	0.43 J	0.66 J	260	5 U	5 U	5 U		2 U	8.98	3.29	152	247	1 U	0.05 U	0.05 U
11/3/2009	5 U	5 U	9.7	5 U	5 U	9.5	5 U	5 U	140	5 U	5 U	5 U		3 U	25.6 J	2.9 J	190	267	0.16 J	0.1 U	0.05 U
5/14/2010	5 U	5 U	2.8 J	5 U	5 U	12	5 U	5 U	160	5 U	5 U	5 U		2.7 U	13.3 J	3.4	165	305	0.16 U	0.1 U	0.05 U
1/16/2014	5 U	5 U	11	5 U	5 U	15	5 U	2.8 J	150	5 U	1.1 J	5 U	0.459			3.9	142	298 J+	0.16 U		

J Indicates an estimated value.
U Analyte was not detected above the reporting limit.
UJ The analyte was not detected. The reporting limit is an approximate value.
J- Indicates estimated value, biased low.
J+ Indicates estimated value, biased high.
D Result reported from a secondary dilution analysis.
R The sample results are rejected.

MONITORING WELL GROUNDWATER ANALYTICAL RESULT SUMMARY
HYDE PARK FACILITY
NIAGARA, NEW YORK

Well ID: MW- 5A

Date	PCE (µg/L)	TCE (µg/L)	Cis-1,2- DCE (µg/L)	Trans-1,2- DCE (µg/L)	1,1-DCE (µg/L)	Vinyl Chloride (µg/L)	Ethane (µg/L)	Ethene (µg/L)	Methane (µg/L)	1,1,1- Trichloroe thane (µg/L)	1,1- Dichloroe thane (µg/L)	Chloro ethane (µg/L)	Dissolved Iron (mg/L)	BOD (mg/L)	COD (mg/L)	TOC (mg/L)	Chloride (mg/L)	Sulfate (mg/L)	Sulfide (mg/L)	Nitrate (mg/L)	Nitrite (mg/L)
10/29/2007															5 UJ						
10/30/2007	5 U	0.59 J	2.6 J	5 U	5 U	2 U	1 U	1 U	0.74 J	5 U	5 U	5 U		2 U		1.14	569	172	1 U		
4/22/2008	5 U	0.47 J	37	0.35 J	5 U	16	2	4.7	22	5 U	5 U	5 U		2 U	12.2	1.44	542	164	1 U	0.613	0.05 U
10/29/2009	5 U	5 U	5.9	5 U	5 U	1.8 J	5 U	5 U	5.5 J	5 U	5 U	5 U		1.7 U	23.3 J	1.1	263	148 J	0.16 U	0.85	0.05 U
5/13/2010	5 U	5 U	110	0.97 J	5 U	84	1.8 J	45	100	5 U	5 U	5 U		1.6 U	15.6 J	1.3	188	126	0.16 U	0.7	0.05 U
10/21/2011	5 U	5 U	5.7	5 U	5 U	3.3 J	5 U	1.5 J	9.6 J	5 U	5 U	5 U	0.0265 J	3.1 U	50 U	1.5	204	164	0.16 U	0.75	0.05 U
6/12/2012	5 U	5 U	88	1 J	5 U	82	2.8 J	34	130	5 U	5 U	1 J	0.2 U	3.2 U	50 U	0.98 J	120	116	0.16 U	0.57	0.05 U
8/28/2013	5 U	5 U	110	1.4 J	5 U	190	9.5	100	460	5 U	1.3 J	5 U		4.3 U	50 U	1.2	106 J	91.7	0.16 U	0.35	0.05 U
4/2/2014	1 U	1 U	240	2.3	1 U	300	16	110	1100	1 UJ	3.3	2.1	0.4 U	4.1 U	50 U	2.3	128 J-	63.3 J+	0.16 U	0.13	0.05 U
11/17/2015	1 U	1 U	150	1.6	1 U	140	5.4	39	2000	1 U	1.4	1.5	0.4 U		50 U	1 U	102	102	0.16 U	0.61	0.05 U
11/20/2015														6 U							
4/19/2016	1.0 U	1.0 U	340 D	5.4	1.0 U	340 D	12	87	7500	1.0 U	4.2	1.0 U	0.400 U	7.3	24.4 J	1.2	151	70.2	0.10 U	0.56	0.050 U
9/13/2017	2.0 U	2.0 U	61	0.74 J	2.0 U	68	2.1	9.8	460	2.0 U	0.88 J	2.0 U	0.100 U	2.0 U	12	0.76 J	69	99	1.0 U	0.25 U	0.050 U
4/24/2018	13 U	13 U	250	13 U	13 U	310	18	69	4200	13 U	3.3 J	13 U	0.200 U	4	4.2 J	1.5	120	60	1.0 U	0.13 J	0.050 UJ
12/3/2019	1.0 U	0.47 J	9.5	1.0 U	1.0 U	11	2.1	3.7	140	1.0 U	1.0 U	1.0 U	0.20 U	2.0 U	4.1 J	0.68 J	89	97	1.0 U	0.59	
3/18/2020	5.0 U	0.52 J	130	1.2 J	5.0 U	180	38	47	2600	5.0 U	2.5 J	5.0 U	0.2 U	1.3 J	12	1.2	130	67	1.0 U	0.098 J	0.10 U
12/6/2021	1.0 U	1.0 U	52	1.0 U	1.0 U	62	7.2 J	7.1	470	1.0 U	1	0.6 J	0.05 U	2.0 U	17	1.5	76	87	1.0 U	0.47	0.10 U

J Indicates an estimated value.
U Analyte was not detected above the reporting limit.
UJ The analyte was not detected. The reporting limit is an approximate value.
J- Indicates estimated value, biased low.
J+ Indicates estimated value, biased high.
D Result reported from a secondary dilution analysis.
R The sample results are rejected.

MONITORING WELL GROUNDWATER ANALYTICAL RESULT SUMMARY
HYDE PARK FACILITY
NIAGARA, NEW YORK

Well ID: MW- 5B

Date	PCE (µg/L)	TCE (µg/L)	Cis-1,2- DCE (µg/L)	Trans-1,2- DCE (µg/L)	1,1-DCE (µg/L)	Vinyl Chloride (µg/L)	Ethane (µg/L)	Ethene (µg/L)	Methane (µg/L)	1,1,1- Trichloroe thane (µg/L)	1,1- Dichloroe thane (µg/L)	Chloro ethane (µg/L)	Dissolved Iron (mg/L)	BOD (mg/L)	COD (mg/L)	TOC (mg/L)	Chloride (mg/L)	Sulfate (mg/L)	Sulfide (mg/L)	Nitrate (mg/L)	Nitrite (mg/L)
10/29/2007	5 U	0.76 J	61	0.66 J	5 U	49	1 U	0.6 J	86	5 U	0.38 J	5 U		2 U	5 UJ	4.26	83.2	230	1 U		
4/22/2008	5 U	0.51 J	58	0.5 J	5 U	57	0.37 J	0.76 J	80	5 U	5 U	5 U		2 U	9.57	4.49	81	223	1.94	0.05 U	0.05 U
10/29/2009	5 U	5 U	39	5 U	5 U	37	5 U	5 U	50	5 U	5 U	5 U		1.7 U	14.2 J	4.9	112	229 J	0.16 U	0.1 U	0.05 U
5/13/2010	5 U	1.1 J	36	5 U	5 U	39	5 U	5 U	63	5 U	5 U	5 U		1.2 U	15.6 J	4.7	98.5	234	0.16 U	0.1 U	0.05 U
11/9/2010	5 U	5 U	43	5 U	5 U	45	5 U	1.1 J	81	5 U	5 U	5 U				4.1	111	254			
10/21/2011	5 U	5 U	48	5 U	5 U	63	5 U	5 U	72	5 U	5 U	5 U	0.0196 J	2.5 U	17.9 J	4.9	130	358	0.16 U	0.1 U	0.05 U
6/13/2012	5 U	5 U	33	5 U	5 U	34	5 U	5 U	50	5 U	5 U	5 U	0.2 U	3.7 U	33.3 J	3.4	187	255	0.16 U	0.1 U	0.05 U
11/30/2012	5 U	5 U	39	5 U	5 U	44	5 U	5 U	66	5 U	5 U	5 U				3	166	267			
8/28/2013	5 U	5 U	32	5 U	5 U	44	5 U	5 U	41	5 U	5 U	5 U		2.8 U	15.6 J	4.5	119 J	299	0.16 U	0.1 U	0.05 U
4/3/2014	1 U	1	16	1 U	1 U	29	5 U	5 U	63	1 UJ	1 U	1 U	0.379 J	4.4 U	50 U	5.3	100	240	0.16 U	0.1 UJ	0.05 U
11/17/2015	1 U	0.58 J	34	1 U	1 U	65	5 U	2.3 J	120	1 U	1 U	1 U	0.502	5.1 U	17.5 J	3.1	117	251	0.16 U	0.1 U	0.05 U
4/19/2016	1.0 U	1.0 U	32	1.0 U	1.0 U	71	5.0 U	1.6 J	86	1.0 U	1.0 U	1.0 U	0.332 J	3.3 U	24.4 J	3	166	259	0.10 U	0.10 U	0.050 U
9/13/2017	5.0 U	5.0 U	36	5.0 U	5.0 U	91	0.50 U	2.2	110	5.0 U	5.0 U	5.0 U	0.54	2.0 U	17	3.4	110	240	1.0 U	0.50 U	0.050 U
4/24/2018	1.0 U	1.0 U	32	1.0 U	1.0 U	78	1.0 U	3.3	160	1.0 U	0.3 J	1.0 U	0.4	2.0 U	8.3 J	3.6	110	240	1.0 U	0.25 UJ	0.050 UJ
12/3/2019	2.0 U	2.0 U	32	2.0 U	2.0 U	90	0.66 J	4.8	270	2.0 U	2.0 U	2.0 U	0.41	2.0 U	9.4 J	3.3	110	240	1.1	0.25 U	
3/18/2020	2.0 U	2.0 U	26	2.0 U	2.0 U	68	1.0 U	2.9	160	2.0 U	2.0 U	2.0 U	0.37	2.0 U	10	3.2	140	220	1.0 U	0.50 U	0.10 U
12/6/2021	2.0 U	2.0 U	40	2.0 U	2.0 U	140	7.5 U	2.4 J	300	2.0 U	2.0 U	2.0 U	0.24	2.0 U	35	4.5	120	230	1.0 U	0.25 U	0.25 U

J Indicates an estimated value.
U Analyte was not detected above the reporting limit.
UJ The analyte was not detected. The reporting limit is an approximate value.
J- Indicates estimated value, biased low.
J+ Indicates estimated value, biased high.
D Result reported from a secondary dilution analysis.
R The sample results are rejected.

MONITORING WELL GROUNDWATER ANALYTICAL RESULT SUMMARY
HYDE PARK FACILITY
NIAGARA, NEW YORK

Well ID: MW- 6

Date	PCE (µg/L)	TCE (µg/L)	Cis-1,2- DCE (µg/L)	Trans-1,2- DCE (µg/L)	1,1-DCE (µg/L)	Vinyl Chloride (µg/L)	Ethane (µg/L)	Ethene (µg/L)	Methane (µg/L)	1,1,1- Trichloroe thane (µg/L)	1,1- Dichloroe thane (µg/L)	Chloro ethane (µg/L)	Dissolved Iron (mg/L)	BOD (mg/L)	COD (mg/L)	TOC (mg/L)	Chloride (mg/L)	Sulfate (mg/L)	Sulfide (mg/L)	Nitrate (mg/L)	Nitrite (mg/L)
11/1/2007	5 U	5 U	130	0.52 J	5 U	82				5 U	5 U	5 U									
4/29/2008	5 U	5 U	150	0.39 J	5 U	100				5 U	5 U	5 U									
10/30/2009	5 U	5 U	85	5 U	5 U	69				5 U	5 U	5 U									
5/12/2010	5 U	5 U	39	5 U	5 U	48	5 U	23	310	5 U	5 U	5 U		3.6 U	22.4 J	3.9	140 J	217	3.4	0.1 U	0.05 U
10/20/2011	5 U	5 U	33	5 U	5 U	57				5 U	5 U	5 U									
6/13/2012	5 U	5 U	30	5 U	5 U	47				5 U	5 U	5 U									
8/30/2013	5 U	5 U	24	5 U	5 U	42				5 U	5 U	5 U									
4/3/2014	1 U	1 U	18	1 U	1 U	39				1 U	1 U	1 U									
11/20/2015	1 U	1 U	20	1 U	1 U	57				1 U	1 U	1 U									
4/21/2016	1.0 U	1.0 U	18	1.0 U	1.0 U	59				1.0 U	1.0 U	1.0 U									
9/12/2017	5.0 U	5.0 U	16	5.0 U	5.0 U	79				5.0 U	5.0 U	5.0 U									
4/26/2018	1.0 U	1.0 U	12	1.0 U	1.0 U	48				1.0 U	1.0 U	1.0 U									
12/4/2019	1.0 U	1.0 U	10	1.0 U	1.0 U	78				1.0 U	1.0 U	1.0 U									
3/19/2020	1.0 U	1.0 U	11	1.0 U	1.0 U	72				1.0 U	1.0 U	1.0 U									
12/8/2021	2.0 U	2.0 U	13	2.0 U	2.0 U	98				2.0 U	2.0 U	2.0 U									

J Indicates an estimated value.
U Analyte was not detected above the reporting limit.
UJ The analyte was not detected. The reporting limit is an approximate value.
J- Indicates estimated value, biased low.
J+ Indicates estimated value, biased high.
D Result reported from a secondary dilution analysis.
R The sample results are rejected.

MONITORING WELL GROUNDWATER ANALYTICAL RESULT SUMMARY
HYDE PARK FACILITY
NIAGARA, NEW YORK

Well ID: MW- 7A

Date	PCE (µg/L)	TCE (µg/L)	Cis-1,2- DCE (µg/L)	Trans-1,2- DCE (µg/L)	1,1-DCE (µg/L)	Vinyl Chloride (µg/L)	Ethane (µg/L)	Ethene (µg/L)	Methane (µg/L)	1,1,1- Trichloroe thane (µg/L)	1,1- Dichloroe thane (µg/L)	Chloro ethane (µg/L)	Dissolved Iron (mg/L)	BOD (mg/L)	COD (mg/L)	TOC (mg/L)	Chloride (mg/L)	Sulfate (mg/L)	Sulfide (mg/L)	Nitrate (mg/L)	Nitrite (mg/L)
11/1/2007	25 U	36	580	25 U	9 J	60	0.95 J	8.5	10	25 U	80	25 U		2 U	7.97 J	2.74	21	250	1 U		
4/28/2008	5 U	210	1700	6.1 J	24	130	0.44 J	5.3	8.6	1.3 J	220	5 U		2 U	5.42	2.23	17.3	210	1 U	0.05 U	0.24
8/13/2008	13 U	270	1800	5.9 J	34	130	5 U	7.2	21	4.1 J	280					3.2	22.3	282			
10/8/2008	5 U	58	1800	3.5 J	25	210	5 U	12	21 J	5 U	250	5 U				143	21.3 J	60.4			
12/9/2008	10 U	4.3 J	1100	1.7 J	9.6 J	180	5 U	27	24	10 U	150	10 U				25.1	24.1	295			
1/27/2009	5 U	3.2 J	840	2.4 J	7.6	390	5 U	51	110	5 U	230	5 U									
3/17/2009	5 U	2.9 J	620	1.5 J	3.6 J	250	5 U	69	210	5 U	140	5 U				8.8	25	253			
10/15/2009	5 U	2.7 J	120	5 U	5 U	240	5 U	110	760	5 U	56	5 U				4.7	21.1	228			
10/30/2009	5 U	1.8 J	210	5 U	5 U	150	5 U	51	260	5 U	49	5 U		4.2 U	23.3 J	3.2	21.8	233 J	2.2	0.1 U	0.05 U
11/18/2009																1150					
12/14/2009	5 U	5 U	140	5 U	5 U	100	5.1	100	1900	5 U	47	5 U				207	23.3 J	56.2 J			
2/9/2010	5 U	5 U	77	5 U	5 U	84	1.1 J	92	1200	5 U	48	5 U				40.1 J	24.1	87.6			
4/1/2010	5 U	5 U	22	5 U	5 U	49				5 UJ	39	5 U									
5/6/2010	5 U	5 U	65	5 U	5 U	50	5 U	5 U	15 U	5 U	33	5 U				95.5	20.9 J	52.2 J			
11/10/2010	5 U	5 U	44	5 U	5 U	18	43 J	65 J	16000	5 U	15	23				261	26.7	31.8			
10/27/2011	5 U	5 U	20	5 U	5 U	19	57	25	20000	5 U	22	13	0.115 J			25.1	28.7	57.1			
3/14/2012	25 U	25 U	11 J	25 U	25 U	25 U	20	8	6700	25 U	18 J	15 J	4.09			1380	34.3	5			
6/14/2012	5 U	1.2 J	3.8 J	5 U	5 U	5 U	5.8	3.3 J	6300	5 U	9.1	22	3.6			573	24.3	5 U			
11/28/2012	5 U	5 U	2.7 J	5 U	5 U	1.3 J	10	1.1 J	16000	5 U	13	16	0.691			204	26.2	5.7			
8/30/2013	5 U	5 U	3.9 J	5 U	5 U	2.2 J	11	3.5 J	13000	5 U	15	7.8		277 J	576	151	26	8.7	0.16 J	0.1 U	0.05 U
1/15/2014	5 U	5 U	4 J	5 U	5 U	1.8 J	8.4	2.7 J	17000	5 U	16	13	39.4			1340	50.4 J+	5 U	0.34		
4/2/2014	1 U	1 U	3	1 U	1 U	1	6.3	1.2 J	20000	1 U	12	16	22.9	589	1250	453	25.5	2.3 J	0.067 J	0.1 U	0.05 U
10/9/2014	1 U	1 U	0.92 J	1 U	1 U	0.94 J	4.7 J	5 U	16000	1 U	8.1	11	14.1			132	27.9	4 J	0.11 J		
11/19/2015	1 U	1 U	1.5	1 U	1 U	3.1	2.8 J	1.1 J	5900	1 U	11	4.8	7.85	99.3	293 J-	84.3	24.6	20.2	0.22	0.1 U	0.05 U
4/20/2016	1.0 U	1.0 U	1.9	1.0 U	1.0 U	3.7	4 J	1.3 J	16000 D	1.0 U	12	4.2	2.18	62	217	50.1	27.4	5.1	0.5	0.10 U	0.050 U
9/12/2017	2.0 U	2.0 U	26	2.0 U	2.0 U	33	2.9	4.1	3400 D	2.0 U	61 J	19	1.7	61	170	52	25	93	1.0 U	0.25 U	0.050 UJ
4/25/2018	5.0 U	5.0 U	46	5.0 U	5.0 U	42	61	63	14000	5.0 U	140	23	0.55	9.2 J	97	32	25	56	1.1	0.25 U	0.027 J
12/4/2019	2.5 U	2.5 U	21 J	2.5 U	2.5 U	35 J	95	25	13000 D	2.5 U	69	44	1.5	14 J-	42	17	12	70	1.0 U	0.25 U	
3/19/2020	2.0 U	2.0 U	50	2.0 U	2.0 U	45	80	20	16000 D	2.0 U	59	23	0.91		36	12	8	82	2.1	0.50 UJ	0.10 UJ
12/8/2021	4.0 U	7.3	150	4.0 U	4.0 U	150	170 U	150 U	13000	4.0 U	90	16	1.5	7.9	36	14	14	89	0.8 J	0.25 U	0.25 U

J Indicates an estimated value.
U Analyte was not detected above the reporting limit.
UJ The analyte was not detected. The reporting limit is an approximate value.
J- Indicates estimated value, biased low.
J+ Indicates estimated value, biased high.
D Result reported from a secondary dilution analysis.
R The sample results are rejected.

MONITORING WELL GROUNDWATER ANALYTICAL RESULT SUMMARY
HYDE PARK FACILITY
NIAGARA, NEW YORK

Well ID: MW- 7B

Date	PCE (µg/L)	TCE (µg/L)	Cis-1,2- DCE (µg/L)	Trans-1,2- DCE (µg/L)	1,1-DCE (µg/L)	Vinyl Chloride (µg/L)	Ethane (µg/L)	Ethene (µg/L)	Methane (µg/L)	1,1,1- Trichloroe thane (µg/L)	1,1- Dichloroe thane (µg/L)	Chloro ethane (µg/L)	Dissolved Iron (mg/L)	BOD (mg/L)	COD (mg/L)	TOC (mg/L)	Chloride (mg/L)	Sulfate (mg/L)	Sulfide (mg/L)	Nitrate (mg/L)	Nitrite (mg/L)
11/1/2007	5 U	5 U	11	5 U	5 U	31	0.31 J	1.9	220	5 U	5 U	5 U		2 U	6.58 J	3.41	157	298	1 U		
4/28/2008	5 U	5 U	10	5 U	5 U	45	0.44 J	2.8	230	5 U	5 U	5 U		2 U	11.6	3.45	130	278	1 U	0.05 U	0.05 U
10/7/2008	5 UJ	5 UJ	19 J	5 UJ	5 UJ	29 J	5 U	3.1 J	220 J	5 UJ	5 UJ	5 UJ				5	164 J	271			
12/9/2008	5 U	5 U	21	5 U	5 U	33	5 U	4.1 J	250	5 U	5 U	5 U				9	153	384			
1/27/2009	5 U	5 U	13	5 U	5 U	29	5 U	3.3 J	220	5 U	5 U	5 U									
3/17/2009	5 U	5 U	20	5 U	5 U	30	5 U	2.1 J	150	5 U	5 U	5 U				5.3	179	296			
10/15/2009	5 U	5 U	7.1	5 U	5 U	39	5 U	3.3 J	340	5 U	5 U	5 U				6.4	146	250			
10/30/2009	5 U	5 U	7.3	5 U	5 U	24				5 U	5 U	5 U									
12/14/2009	5 U	5 U	7.7	5 U	5 U	24	5 U	3.6 J	260	5 U	5 U	5 U				26.8	171 J	220 J			
2/9/2010	5 U	5 U	3.2 J	5 U	5 U	21	5 U	6.1	650	5 U	5 U	5 U				13.9 J	157	248			
3/31/2010	5 U	5 U	3.8 J	5 U	5 U	29				5 U	5 U	5 U									
5/6/2010	5 U	5 U	4.5 J	5 U	5 U	31	5 U	5 U	15 U	5 U	5 U	5 U				60.6	130 J	244 J			
11/11/2010	5 U	5 U	6.7	5 U	5 U	24	5 U	4.2 J	1200	5 U	5 U	5 U				17.5	168	239			
10/26/2011	5 U	5 U	6	5 U	5 U	25	5 U	3.6 J	3400	5 U	5 U	5 U	0.0747 J			8.4	168	218 J			
3/15/2012	50 U	50 U	50 U	50 U	50 U	11 J	5 U	9.3	4500	50 U	50 U	50 U	0.0443 J			68.1	153	122			
6/14/2012	5 U	5 U	1.6 J	5 U	5 U	9.2	5 U	7.9	2400	5 U	5 U	5 U	0.2 U			19.3	150	143			
11/27/2012	5 U	5 U	1.5 J	5 U	5 U	9.5	5 U	11	3300	5 U	5 U	5 U	0.2 U			8.7	173	178			
9/3/2013	5 U	5 U	1.2 J	5 U	5 U	7.5	5 U	11	6400	5 U	5 U	5 U		17.4	95 J	11.5	146 J	139	10.3	0.1 UJ	0.05 U
1/13/2014	5 U	5 U	5 U	5 U	5 U	2 J	5 U	9.4	18000	5 U	5 U	5 U	0.4 U			70.1	145	61.7	47.9		
4/2/2014	1 U	1 U	1 U	1 U	1 U	5.5	5 U	11	19000	1 U	1 U	1 U	0.4 U	366	772	132	136	117	33.3	1 U	0.026 J
10/10/2014	1 U	1 U	1.5	1 U	1 U	8	5 U	7	13000	1 U	1 U	1 U	0.4 U			22.2	164	129	22.6		
11/23/2015	1 U	1 U	1.2	1 U	1 U	6.1	5 U	4.3 J	11000	1 U	1 U	1 U	0.4 U	22.2	97.8	10.8	189	146	20.4	0.1 U	0.05 U
4/20/2016	1.0 U	1.0 U	0.82 J	1.0 U	1.0 U	10	5.0 U	5.6	5000 D	1.0 U	1.0 U	1.0 U	0.400 U	27.1	142	6.9	172	162	16.5	0.10 U	0.050 U
9/12/2017	1.0 U	1.0 U	2.2	1.0 U	1.0 U	18	0.50 U	1.9	370	1.0 U	1.0 U	1.0 U	0.100 U	9.6	41	4.8	170	180	1.1	0.25 U	0.050 UJ
4/25/2018	1.0 U	1.0 U	2.2	1.0 U	1.0 U	17	1.0 U	6.4	240	1.0 U	1.0 U	1.0 U	0.200 U	2	29	4.7	140	260	1.0 U	0.25 U	0.050 U
12/3/2019	1.0 U	1.0 U	1.3	1.0 U	1.0 U	10	0.58 J	3.3	290	1.0 U	1.0 U	1.0 U	0.20 U	2.0 U	12	3.3	180	190	7.1	0.25 U	
3/19/2020	1.0 U	1.0 U	5.4	1.0 U	1.0 U	18	1.0 U	6.4	230	1.0 U	1.0 U	1.0 U	0.2 U		11	3.2	130	260	1.7	0.50 UJ	0.10 UJ
12/8/2021	1.0 U	1.0 U	1.5	1.0 U	1.0 U	18	7.5 U	7.0 U	160	1.0 U	1.0 U	1.0 U	0.05 U	2.0 U	10 U	4.6	240	200	0.8 J	0.25 U	0.25 U

J Indicates an estimated value.
U Analyte was not detected above the reporting limit.
UJ The analyte was not detected. The reporting limit is an approximate value.
J- Indicates estimated value, biased low.
J+ Indicates estimated value, biased high.
D Result reported from a secondary dilution analysis.
R The sample results are rejected.

MONITORING WELL GROUNDWATER ANALYTICAL RESULT SUMMARY
HYDE PARK FACILITY
NIAGARA, NEW YORK

Well ID: MW- 8

Date	PCE (µg/L)	TCE (µg/L)	Cis-1,2- DCE (µg/L)	Trans-1,2- DCE (µg/L)	1,1-DCE (µg/L)	Vinyl Chloride (µg/L)	Ethane (µg/L)	Ethene (µg/L)	Methane (µg/L)	1,1,1- Trichloroe thane (µg/L)	1,1- Dichloroe thane (µg/L)	Chloro ethane (µg/L)	Dissolved Iron (mg/L)	BOD (mg/L)	COD (mg/L)	TOC (mg/L)	Chloride (mg/L)	Sulfate (mg/L)	Sulfide (mg/L)	Nitrate (mg/L)	Nitrite (mg/L)
10/31/2007	5 U	5 U	2.2 J	5 U	5 U	1.8 J				5 U	5 U	5 U									
4/25/2008	5 U	5 U	2.5 J	5 U	5 U	2.6				5 U	5 U	5 U									
11/2/2009	5 U	5 U	2.1 J	5 U	5 U	2.6 J				5 U	5 U	5 U									
5/12/2010	5 U	5 U	2.3 J	5 U	5 U	2.2 J	5 U	5 U	140	5 U	5 U	5 U									
10/24/2011	5 U	5 U	1.9 J	5 U	5 U	2.1 J				5 U	5 U	5 U									
6/12/2012	5 U	5 U	1.6 J	5 U	5 U	1.1 J				5 U	5 U	5 U									
8/30/2013	5 U	5 U	1.7 J	5 U	5 U	1.8 J				5 U	5 U	5 U									
4/3/2014	1 U	1 U	1.6	1 U	1 U	1.5				1 U	1 U	1 U									
11/23/2015	1 U	1 U	1.7	1 U	1 U	1.9				1 U	1 U	1 U									
4/22/2016	1.0 U	1.0 U	1.9	1.0 U	1.0 U	1.8				1.0 U	1.0 U	1.0 U									
9/13/2017	1.0 U	1.0 U	1.7	1.0 U	1.0 U	1.4				1.0 U	1.0 U	1.0 U									
4/23/2018	1.0 U	1.0 U	1.9	1.0 U	1.0 U	1.6				1.0 U	1.0 U	1.0 U									

J Indicates an estimated value.
U Analyte was not detected above the reporting limit.
UJ The analyte was not detected. The reporting limit is an approximate value.
J- Indicates estimated value, biased low.
J+ Indicates estimated value, biased high.
D Result reported from a secondary dilution analysis.
R The sample results are rejected.

MONITORING WELL GROUNDWATER ANALYTICAL RESULT SUMMARY
HYDE PARK FACILITY
NIAGARA, NEW YORK

Well ID: MW-10A

Date	PCE (µg/L)	TCE (µg/L)	Cis-1,2- DCE (µg/L)	Trans-1,2- DCE (µg/L)	1,1-DCE (µg/L)	Vinyl Chloride (µg/L)	Ethane (µg/L)	Ethene (µg/L)	Methane (µg/L)	1,1,1- Trichloroe thane (µg/L)	1,1- Dichloroe thane (µg/L)	Chloro ethane (µg/L)	Dissolved Iron (mg/L)	BOD (mg/L)	COD (mg/L)	TOC (mg/L)	Chloride (mg/L)	Sulfate (mg/L)	Sulfide (mg/L)	Nitrate (mg/L)	Nitrite (mg/L)
10/29/2007	5 U	5 U	300	12	0.68 J	67	0.52 J	4.6	19	5 U	4.5 J	5 U		2 U	8.32 J	1.93	815	332	1 U		
4/22/2008	5 U	5 U	390	10	1.6 J	97	4.4	11	60	5 U	5.8	5 U		2 U	10.1	2.99	884	294	1 U	0.05 U	0.05 U
10/29/2009	5 U	5 U	400	9.4	1.5 J	140	5 U	10	38	5 U	6.4	5 U		1.8 U	46.2 J	1.6	903	279 J	0.16 U	0.1 U	0.05 U
5/11/2010	5 U	5 U	390	7.6	1.3 J	140	5 U	17	71	5 U	5.7	5 U		1.7 U	38.4 J	1.5	784	250	0.16 U	0.1 U	0.05 U
10/25/2011	5 U	5 U	630	11	1.2 J	250	5 U	29	66	5 U	7.7	5 U	0.0808 J	2.8 U	27 J	1.9	770 J	254 J	0.16 U	0.1 U	0.05 U
6/13/2012	5 U	5 U	620	13	1 J	170	1.5 J	43	120	5 U	7	5 U	0.2 U	3.2 U	31 J	0.98 J	621	264	0.16 U	0.1 U	0.05 U
8/29/2013	5 U	5 U	570	9.9	5 U	130	5 U	28	130	5 U	5.6	5 U		2.9 UJ	27 J	1.8	481	193	0.16 U	0.1 U	0.05 U
4/2/2014	1 U	1 U	560	8	0.6 J	95	5 U	24	170	1 UJ	4.4	1 U	0.719	3.9 U	17.2 J	2	438 J-	228 J+	0.16 U	0.1 U	0.05 U
11/18/2015	1 U	1 U	710	9.1	0.52 J	130	5 U	17	220	1 U	5.3	1 U	1.81	2.9 U	22.1 J	0.87 J	434	170	0.16 U	0.1 U	0.05 U
4/19/2016	1.0 U	0.57 J	960 D	12	0.71 J	83	5.0 U	6.4	88	1.0 U	5.4	1.0 U	0.831	3.4 U	33.6 J	0.9 J	523	216	0.10 U	0.10 U	0.050 U
9/13/2017	20 U	20 U	590	6.8 J	20 U	130	0.38 J	11	400	20 U	20 UJ	20 U	1.4	2.0 U	13	1.1	310	170	1.0 U	0.50 U	0.050 U
4/25/2018	20 U	20 U	540	20 U	20 U	94	1.0 U	12	640	20 U	20 U	20 U	1.2	2.0 U	10	1.4	260	160	1.0 U	0.25 U	0.050 U
12/4/2019	25 U	5 J	500	25 U	25 U	130	2.4	36	2000	25 U	25 U	25 U	1.1	2.0 UJ	4.2 J	1.4	200	150	1.0 U	0.25 U	
3/18/2020	20 U	7.6 J	570	4.4 J	20 U	130	2.7	34	2400	20 U	20 U	20 U	0.88	2.0 U	8.3 J	1.4	190	120	1.0 U	0.50 U	0.10 U
12/6/2021	25 U	13 J	650	25 U	25 U	180	7.5 U	14	880	25 U	25 U	25 U	1.4	2.0 U	26	2	220	150	1.0 U	0.25 U	0.25 U

J Indicates an estimated value.
U Analyte was not detected above the reporting limit.
UJ The analyte was not detected. The reporting limit is an approximate value.
J- Indicates estimated value, biased low.
J+ Indicates estimated value, biased high.
D Result reported from a secondary dilution analysis.
R The sample results are rejected.

MONITORING WELL GROUNDWATER ANALYTICAL RESULT SUMMARY
HYDE PARK FACILITY
NIAGARA, NEW YORK

Well ID: MW-10B

Date	PCE (µg/L)	TCE (µg/L)	Cis-1,2- DCE (µg/L)	Trans-1,2- DCE (µg/L)	1,1-DCE (µg/L)	Vinyl Chloride (µg/L)	Ethane (µg/L)	Ethene (µg/L)	Methane (µg/L)	1,1,1- Trichloroe thane (µg/L)	1,1- Dichloroe thane (µg/L)	Chloro ethane (µg/L)	Dissolved Iron (mg/L)	BOD (mg/L)	COD (mg/L)	TOC (mg/L)	Chloride (mg/L)	Sulfate (mg/L)	Sulfide (mg/L)	Nitrate (mg/L)	Nitrite (mg/L)
10/29/2007	5 U	0.7 J	220	1.9 J	0.38 J	130	0.43 J	1.5	100	5 U	0.69 J	5 U		2 U	5 UJ	3.81	226	236	1 U		
4/22/2008	5 U	0.46 J	180	1.3 J	5 U	76	0.48 J	1 J	96	5 U	0.54 J	5 U		2 U	12.7	4.22	87.4	198	1 U	0.05 U	0.05 U
4/23/2008																					
10/16/2009	5 U	5 U	420	3.1 J	5 U	120	5 U	2.7 J	110	5 U	5 U	5 U				3.8	121	239			
10/29/2009	5 U	5 U	370	3.8 J	5 U	150	5 U	2.2 J	94	5 U	5 U	5 U		2.1 U	16.5 J	4.6	107	245 J	0.16 U	0.1 U	0.05 U
12/16/2009	5 U	5 U	750	9	5 U	260	5 U	12	110	5 U	5 U	5 U				4.2	123 J	268 J			
2/10/2010	5 U	5 U	300	4 J	5 U	120	5 U	3.7 J	92	5 U	5 U	5 U				4.2 J	87.5	253			
3/30/2010	5 U	5 U	270	3.1 J	5 U	90				5 U	5 U	5 U									
5/6/2010	5 U	5 U	220	2 J	5 U	83	5 U	5 U	15 U	5 U	5 U	5 U		3.5 U	50 U	4.9	89.5 J	244 J	0.071 J	0.1 U	0.05 U
11/9/2010	5 U	5 U	1100	13	1.9 J	200	1.8 J	13	130	5 U	5 U	5 U				3.2	272	225			
10/26/2011	10 U	10 U	960	11	1.8 J	180	2.7 J	24	300	10 U	10 U	10 U	0.0459 J	3.5 U	13.4 J	3.4	189	259 J	0.16 U	0.1 U	0.05 U
3/12/2012	5 U	5 U	260	3 J	5 U	49	5 U	1.2 J	53	5 U	5 U	5 U	0.2 U			3.8	104	245			
6/14/2012	5 U	5 U	280	1.7 J	5 U	110	5 U	5.7	120	5 U	5 U	5 U	0.2 U	3.3 U	12.9 J	3.8	141	261	0.16 U	0.1 U	0.05 U
11/27/2012	5 U	5 U	630	5.8	5 U	130	5 U	11	160	5 U	5 U	5 U	0.2 U			3	194	265			
8/29/2013	5 U	5 U	230	1.5 J	5 U	120	5 U	9.2	220	5 U	5 U	5 U		3.1 UJ	24.7 J	2	156	246	0.16 U	0.1 U	0.05 U
1/17/2014	5 U	5 U	150	5 U	5 U	27	5 U	2 J	38	5 U	5 U	5 U	0.0884 J			7.9	128	250	0.16 U		
4/2/2014	1 U	1 U	190	0.7 J	1 U	22	5 U	2.3 J	38	1 U	1 U	1 U	0.076 J	3.2 U	50 U	4.8	133	256	0.16 U	0.1 U	0.05 U
10/14/2014	1 U	1 U	160	1 U	1 U	89	1.1 J	210	1100	1 UJ	1 U	1 U	0.05 J			5	137	215	1.3		
11/16/2015	1 U	1 U	190	0.68 J	1 U	190	2.1 J	190	2900	1 U	0.9 J	1 U	0.4 U	6 U	17.5 J	3	145	207	0.71	0.1 U	0.05 U
4/19/2016	1.0 U	1.0 U	220	1.1	1.0 U	6.1	5.0 U	5.0 U	9.1	1.0 U	1.0 U	1.0 U	0.400 U	3.6 U	26.7 J	2.9	160	272	0.10 U	0.087 J	0.050 U
9/13/2017	10 U	10 U	360	10 U	10 U	270	4.5	130	3900	10 U	10 UJ	10 U	0.24	2.0 U	17	3.2	150	230	1.0 U	0.50 U	0.050 U
4/25/2018	8.0 U	8.0 U	210	8.0 U	8.0 U	12	1.0 U	1.0 U	25	8.0 U	8.0 U	8.0 U	0.14 J	2.4 UJ	10 U	3.6	130	240	1.0 U	0.25 U	0.050 U
12/4/2019	20 U	20 U	420	4 J	20 U	180	1.8	27	1500	20 U	20 U	20 U	0.68	2.0 U	10 U	3	220	260	1.0 U	0.25 U	
3/18/2020	5.0 U	5.0 U	210	5.0 U	5.0 U	23	1.0 U	1.9	78	5.0 U	5.0 U	5.0 U	0.086 J	2.0 U	12	3.2	140	230	1.0 U	0.50 U	0.10 U
12/6/2021	10 U	10 U	220	10 U	10 U	370	170 U	150 U	1900	10 U	10 U	10 U	0.33	2.0 U	40	4.6	140	220	1.0 U	0.25 U	0.25 U

J Indicates an estimated value.
U Analyte was not detected above the reporting limit.
UJ The analyte was not detected. The reporting limit is an approximate value.
J- Indicates estimated value, biased low.
J+ Indicates estimated value, biased high.
D Result reported from a secondary dilution analysis.
R The sample results are rejected.

MONITORING WELL GROUNDWATER ANALYTICAL RESULT SUMMARY
HYDE PARK FACILITY
NIAGARA, NEW YORK

Well ID: MW-11A

Date	PCE (µg/L)	TCE (µg/L)	Cis-1,2- DCE (µg/L)	Trans-1,2- DCE (µg/L)	1,1-DCE (µg/L)	Vinyl Chloride (µg/L)	Ethane (µg/L)	Ethene (µg/L)	Methane (µg/L)	1,1,1- Trichloroe thane (µg/L)	1,1- Dichloroe thane (µg/L)	Chloro ethane (µg/L)	Dissolved Iron (mg/L)	BOD (mg/L)	COD (mg/L)	TOC (mg/L)	Chloride (mg/L)	Sulfate (mg/L)	Sulfide (mg/L)	Nitrate (mg/L)	Nitrite (mg/L)
10/29/2007	5 U	5 U	5 U	5 U	5 U	2 U				5 U	5 U	5 U									
4/22/2008	5 U	5 U	5 U	5 U	5 U	0.7 J				5 U	5 U	5 U									
10/30/2009	5 U	5 U	5 U	5 U	5 U	5 U				5 U	5 U	5 U									
5/11/2010	5 U	5 U	5 U	5 U	5 U	3.2 J	5 U	5 U	51	5 U	5 U	5 U									

J Indicates an estimated value.
U Analyte was not detected above the reporting limit.
UJ The analyte was not detected. The reporting limit is an approximate value.
J- Indicates estimated value, biased low.
J+ Indicates estimated value, biased high.
D Result reported from a secondary dilution analysis.
R The sample results are rejected.

MONITORING WELL GROUNDWATER ANALYTICAL RESULT SUMMARY
HYDE PARK FACILITY
NIAGARA, NEW YORK

Well ID: MW-11B

Date	PCE (µg/L)	TCE (µg/L)	Cis-1,2- DCE (µg/L)	Trans-1,2- DCE (µg/L)	1,1-DCE (µg/L)	Vinyl Chloride (µg/L)	Ethane (µg/L)	Ethene (µg/L)	Methane (µg/L)	1,1,1- Trichloroe thane (µg/L)	1,1- Dichloroe thane (µg/L)	Chloro ethane (µg/L)	Dissolved Iron (mg/L)	BOD (mg/L)	COD (mg/L)	TOC (mg/L)	Chloride (mg/L)	Sulfate (mg/L)	Sulfide (mg/L)	Nitrate (mg/L)	Nitrite (mg/L)
10/29/2007	5 U	5 U	140	1 J	5 U	80				5 U	0.39 J	5 U									
4/22/2008	5 U	5 U	100	0.77 J	5 U	64				5 U	5 U	5 U									
3/18/2009																3.8					
10/16/2009	5 U	5 U	64	5 U	5 U	73	5 U	14	170	5 U	5 U	5 U					172	221			
10/30/2009	5 U	5 U	56	5 U	5 U	48	5 U	15	150	5 U	5 U	5 U		1.8 U	21 J	3.4	165	207 J	0.3	0.1 U	0.05 U
12/16/2009	5 U	5 U	5.3	5 U	5 U	17	5 U	81	190	5 U	5 U	5 U				7.4	148 J	221 J			
2/10/2010	5 U	5 U	2.3 J	5 U	5 U	11	5 U	130	760	5 U	5 U	5 U				11.7 J	146	50.2			
3/30/2010	5 U	5 U	2.1 J	5 U	5 U	7.1				5 U	5 U	5 U									
5/6/2010	5 U	5 U	1.9 J	5 U	5 U	7.4	5 U	5 U	15 U	5 U	1.3 J	5 U		64.7 J	132	14.1	114 J	101 J	48.3	0.1 U	0.05 U
11/9/2010	5 U	5 U	1.4 J	5 U	5 U	4.3 J	5 U	57	1100	5 U	1.2 J	5 U				3.9	125	208			
10/26/2011	5 U	5 U	2.2 J	5 U	5 U	4.6 J	5 U	90	1500	5 U	1.8 J	5 U	0.0859 J	8.9	31.5 J	3.8	157	245 J	8.5	0.043 J	0.05 U
3/12/2012	5 U	5 U	1.4 J	5 U	5 U	6.7	1.3 J	72	5200	5 U	1.5 J	5 U	0.0711 J			9.5	117	118			
6/14/2012	5 U	5 U	1.8 J	5 U	5 U	6.1	2.6 J	110	7400	5 U	1.4 J	5 U	0.2 U	32	76.5	4.3	121	135	44.4	0.1 U	0.05 U
11/27/2012	5 U	5 U	0.83 J	5 U	5 U	2.5 J	3.9 J	130	6800	5 U	1.4 J	5 U	0.2 U			3.9	143	164			
8/29/2013	5 U	5 U	5 U	5 U	5 U	1.4 J				5 U	1.9 J	5 U									
1/14/2014	5 U	5 U	5 U	1.1 J	5 U	1.2 J	4 J	260	10000	5 U	2.5 J	5 U	0.4 U			8	141	120	23.8		
4/2/2014	1 U	1 U	1 U	0.92 J	1 U	1.2	3.5 J	280	8300	1 U	2	1 U	0.4 U			5.2	141	158	27.8		
10/14/2014	1 U	1 U	1 U	0.66 J	1 U	2.5	1.4 J	86	4200	1 UJ	1.2	1 U	0.4 U			5.3	143	160	11.1		
11/17/2015	1 U	1 U	0.56 J	0.57 J	1 U	1.7				1 U	1	1 U									
4/22/2016	1.0 U	1.0 U	0.54 J	0.76 J	1.0 U	9.7				1.0 U	1.7	1.0 U									
9/14/2017	1.0 U	1.0 U	1.1	1.0 U	1.0 U	6.5				1.0 U	0.95 J	1.0 U									
4/24/2018	1.0 U	1.0 U	0.65 J	0.74 J	1.0 U	1.9				1.0 U	1.9	1.0 U									

J Indicates an estimated value.
U Analyte was not detected above the reporting limit.
UJ The analyte was not detected. The reporting limit is an approximate value.
J- Indicates estimated value, biased low.
J+ Indicates estimated value, biased high.
D Result reported from a secondary dilution analysis.
R The sample results are rejected.

MONITORING WELL GROUNDWATER ANALYTICAL RESULT SUMMARY
HYDE PARK FACILITY
NIAGARA, NEW YORK

Well ID: MW-12A

Date	PCE (µg/L)	TCE (µg/L)	Cis-1,2- DCE (µg/L)	Trans-1,2- DCE (µg/L)	1,1-DCE (µg/L)	Vinyl Chloride (µg/L)	Ethane (µg/L)	Ethene (µg/L)	Methane (µg/L)	1,1,1- Trichloroe thane (µg/L)	1,1- Dichloroe thane (µg/L)	Chloro ethane (µg/L)	Dissolved Iron (mg/L)	BOD (mg/L)	COD (mg/L)	TOC (mg/L)	Chloride (mg/L)	Sulfate (mg/L)	Sulfide (mg/L)	Nitrate (mg/L)	Nitrite (mg/L)
10/29/2007	5 U	5 U	150	1.3 J	0.49 J	39				5 U	3.2 J	5 U									
4/22/2008	5 U	5 U	130	1 J	0.32 J	23				5 U	2 J	5 U									
11/2/2009	5 U	5 U	64	5 U	5 U	38				5 U	2.7 J	5 U									
5/11/2010	5 U	5 U	16	5 U	5 U	16	5 U	14	140	5 U	1.6 J	5 U									
10/20/2011	5 U	5 U	19	5 U	5 U	16				5 U	1.8 J	5 U									
6/13/2012	5 U	5 U	19	5 U	5 U	13				5 U	1.8 J	5 U									
8/29/2013	5 U	5 U	22	5 U	5 U	14	5.6	7.2	210	5 U	1.9 J	5 U		4.4 U	311	5.5	80.7	204	0.16 U	0.1 U	0.05 U
4/3/2014	1 U	1 U	8.9	1 U	1 U	6.8	5 U	2.4 J	140	1 U	0.89 J	1 U	0.962	4.7 U	15 J	5.6	69	179	0.16 U	0.14 J-	0.05 U
11/17/2015	1 U	1 U	1.6	1 U	1 U	9.6	5 U	5 U	140	1 U	0.7 J	1 U	2.27	3.8 U	26.7 J	7.7	63.6	119	0.079 J	0.1 U	0.05 U
4/22/2016	1.0 U	1.0 U	9.5	1.0 U	1.0 U	8.8	5.0 U	1.8 J	170	1.0 U	1.1	1.0 U	0.847	3.4 UJ	19.8 J	3.4	96	192	0.10 U	0.10 U	0.050 U
9/14/2017	1.0 U	1.0 U	21	0.34 J	1.0 U	13	0.31 J	2.7	210	1.0 U	1.6	1.0 U	1.5	2.0 U	49	4.2	330	650	1.0 U	1.0 U	0.050 U
4/24/2018	1.0 U	1.0 U	16	1.0 U	1.0 U	9.2	1.0 U	2	200	1.0 U	0.91 J	1.0 U	0.6	2.0 U	11	3.9	82	190	1.0 U	0.25 UJ	0.050 UJ

J Indicates an estimated value.
U Analyte was not detected above the reporting limit.
UJ The analyte was not detected. The reporting limit is an approximate value.
J- Indicates estimated value, biased low.
J+ Indicates estimated value, biased high.
D Result reported from a secondary dilution analysis.
R The sample results are rejected.

MONITORING WELL GROUNDWATER ANALYTICAL RESULT SUMMARY
HYDE PARK FACILITY
NIAGARA, NEW YORK

Well ID: MW-12B

Date	PCE (µg/L)	TCE (µg/L)	Cis-1,2- DCE (µg/L)	Trans-1,2- DCE (µg/L)	1,1-DCE (µg/L)	Vinyl Chloride (µg/L)	Ethane (µg/L)	Ethene (µg/L)	Methane (µg/L)	1,1,1- Trichloroe thane (µg/L)	1,1- Dichloroe thane (µg/L)	Chloro ethane (µg/L)	Dissolved Iron (mg/L)	BOD (mg/L)	COD (mg/L)	TOC (mg/L)	Chloride (mg/L)	Sulfate (mg/L)	Sulfide (mg/L)	Nitrate (mg/L)	Nitrite (mg/L)
10/29/2007	5 U	5 U	110	1 J	5 U	76				5 U	1.8 J	5 U									
4/21/2008	5 U	5 U	140	1.6 J	0.31 J	70				5 U	1.6 J	5 U									
11/2/2009	5 U	5 U	2.6 J	5 U	5 U	5 U				5 U	5 U	5 U									
5/11/2010	5 U	5 U	11	5 U	5 U	5 U	5 U	5 U	15 U	5 U	5 U	5 U									
11/9/2010	5 U	5 U	59	5 U	5 U	71	1.2 J	3.3 J	120	5 U	5 U	5 U				3.2	149	312			
10/20/2011	5 U	5 U	0.98 J	5 U	5 U	5 U				5 U	5 U	5 U									
6/13/2012	5 U	5 U	5.6	5 U	5 U	10				5 U	5 U	5 U									
8/29/2013	5 U	5 U	45	5 U	5 U	73	5 U	15	160	5 U	5 U	5 U		4.2 U	17.9 J	4.1	143	230	0.093 J	0.1 U	0.05 U
4/3/2014	1 U	1 U	57	1 U	1 U	75	5 U	9.7	190	1 U	1 U	1 U	0.4 U	4.1 U	50 U	5.4	149	201	0.16 U	0.1 UJ	0.05 U
11/16/2015	1 U	1 U	13	1 U	1 U	9.1	5 U	5 U	25	1 U	1 U	1 U	0.111 J	4.7 U	22.1 J	9.2	148	244	0.16 U	0.2 J+	0.039 J
4/22/2016	1.0 U	1.0 U	73	1.0 U	1.0 U	59	5.0 U	2.6 J	200	1.0 U	1.0 U	1.0 U	0.0618 J	3.5 UJ	19.8 J	3	177	204	0.10 U	0.10 U	0.050 U
9/14/2017	2.0 U	2.0 U	52	2.0 U	2.0 U	110	0.45 J	3.9	140	2.0 U	0.66 J	2.0 U	0.032 J	2.0 U	17	2.7	280	530	1.0 U	0.50 U	0.050 U
4/25/2018	2.5 U	2.5 U	62	2.5 U	2.5 U	73	1.0 U	4.4	340	2.5 U	2.5 U	2.5 U	0.027 J	2.0 U	12	3.5	150	190	1.0 U	0.25 U	0.050 U
12/5/2019	2.5 U	2.5 U	65	2.5 U	2.5 U	94	0.89 J	5.3	210	2.5 U	2.5 U	2.5 U	0.20 U	2.0 U	10 U	2.8	150	240	1.0 U	0.25 U	
3/19/2020	2.0 U	2.0 U	51	2.0 U	2.0 U	85	1.0 U	5.9	410	2.0 U	0.41 J	2.0 U	0.2 U		7.3 J	3.1	150	220	0.67 J	0.50 UJ	0.10 UJ
12/7/2021	1.0 UJ	1.0 UJ	73 J-	1.0 UJ	1.0 UJ	49 DJ-	7.5 U	4.1 J	330	1.0 UJ	0.4 J-	1.0 UJ	0.048 J	2.0 U	100	6.3	77	72	1.0 U	0.24	0.050 U

J Indicates an estimated value.
U Analyte was not detected above the reporting limit.
UJ The analyte was not detected. The reporting limit is an approximate value.
J- Indicates estimated value, biased low.
J+ Indicates estimated value, biased high.
D Result reported from a secondary dilution analysis.
R The sample results are rejected.

MONITORING WELL GROUNDWATER ANALYTICAL RESULT SUMMARY
HYDE PARK FACILITY
NIAGARA, NEW YORK

Well ID: MW-13A

Date	PCE (µg/L)	TCE (µg/L)	Cis-1,2- DCE (µg/L)	Trans-1,2- DCE (µg/L)	1,1-DCE (µg/L)	Vinyl Chloride (µg/L)	Ethane (µg/L)	Ethene (µg/L)	Methane (µg/L)	1,1,1- Trichloroe thane (µg/L)	1,1- Dichloroe thane (µg/L)	Chloro ethane (µg/L)	Dissolved Iron (mg/L)	BOD (mg/L)	COD (mg/L)	TOC (mg/L)	Chloride (mg/L)	Sulfate (mg/L)	Sulfide (mg/L)	Nitrate (mg/L)	Nitrite (mg/L)
10/30/2007	5 U	5 U	5 U	5 U	5 U	2 U				5 U	5 U	5 U									
4/29/2008																					
10/29/2009	5 U	5 U	5 U	5 U	5 U	5 U				5 U	5 U	5 U									

J Indicates an estimated value.
U Analyte was not detected above the reporting limit.
UJ The analyte was not detected. The reporting limit is an approximate value.
J- Indicates estimated value, biased low.
J+ Indicates estimated value, biased high.
D Result reported from a secondary dilution analysis.
R The sample results are rejected.

MONITORING WELL GROUNDWATER ANALYTICAL RESULT SUMMARY
HYDE PARK FACILITY
NIAGARA, NEW YORK

Well ID: MW-13B

Date	PCE (µg/L)	TCE (µg/L)	Cis-1,2- DCE (µg/L)	Trans-1,2- DCE (µg/L)	1,1-DCE (µg/L)	Vinyl Chloride (µg/L)	Ethane (µg/L)	Ethene (µg/L)	Methane (µg/L)	1,1,1- Trichloroe thane (µg/L)	1,1- Dichloroe thane (µg/L)	Chloro ethane (µg/L)	Dissolved Iron (mg/L)	BOD (mg/L)	COD (mg/L)	TOC (mg/L)	Chloride (mg/L)	Sulfate (mg/L)	Sulfide (mg/L)	Nitrate (mg/L)	Nitrite (mg/L)
10/30/2007	5 U	0.78 J	82	1.1 J	5 U	59				5 U	0.61 J	5 U									
4/24/2008	5 U	0.65 J	65	0.51 J	5 U	56				5 U	0.48 J	5 U									
10/29/2009	5 U	5 U	88	5 U	5 U	68				5 U	5 U	5 U									
5/13/2010	5 U	5 U	46	5 U	5 U	47	5 U	1 J	65	5 U	5 U	5 U									
10/21/2011	5 U	5 U	17	5 U	5 U	24				5 U	5 U	5 U									
6/13/2012	5 U	5 U	27	5 U	5 U	57				5 U	5 U	5 U									
8/30/2013	5 U	5 U	8.6	5 U	5 U	48				5 U	5 U	5 U									
4/3/2014	1 U	1 U	19	1 U	1 U	15				1 UJ	1 U	1 U									
11/17/2015	1 U	1 U	18	1 U	1 U	21				1 U	1 U	1 U									
4/21/2016	1.0 U	1.0 U	9.9	1.0 U	1.0 U	12				1.0 U	1.0 U	1.0 U									
9/13/2017	1.0 U	1.0 U	22	1.0 U	1.0 U	38				1.0 U	1.0 UJ	1.0 U									
4/24/2018	1.0 U	1.0 U	7.8	1.0 U	1.0 U	9.7				1.0 U	1.0 U	1.0 U									
12/3/2019	1.0 U	0.19 J	16	1.0 U	1.0 U	21				1.0 U	0.17 J	1.0 U									
3/19/2020	1.0 U	1.0 U	1.6	1.0 U	1.0 U	2				1.0 U	1.0 U	1.0 U									
12/6/2021	2.0 U	2.0 U	3.7	2.0 U	2.0 U	6.4				2.0 U	2.0 U	2.0 U									

J Indicates an estimated value.
U Analyte was not detected above the reporting limit.
UJ The analyte was not detected. The reporting limit is an approximate value.
J- Indicates estimated value, biased low.
J+ Indicates estimated value, biased high.
D Result reported from a secondary dilution analysis.
R The sample results are rejected.

MONITORING WELL GROUNDWATER ANALYTICAL RESULT SUMMARY
HYDE PARK FACILITY
NIAGARA, NEW YORK

Well ID: MW-14A

Date	PCE (µg/L)	TCE (µg/L)	Cis-1,2- DCE (µg/L)	Trans-1,2- DCE (µg/L)	1,1-DCE (µg/L)	Vinyl Chloride (µg/L)	Ethane (µg/L)	Ethene (µg/L)	Methane (µg/L)	1,1,1- Trichloroe thane (µg/L)	1,1- Dichloroe thane (µg/L)	Chloro ethane (µg/L)	Dissolved Iron (mg/L)	BOD (mg/L)	COD (mg/L)	TOC (mg/L)	Chloride (mg/L)	Sulfate (mg/L)	Sulfide (mg/L)	Nitrate (mg/L)	Nitrite (mg/L)
10/30/2007	5 U	5 U	1.6 J	5 U	5 U	2.4				5 U	5 U	5 U									
4/24/2008	5 U	5 U	1.5 J	5 U	5 U	1.6 J	0.64 J	1 U	15	5 U	5 U	5 U		2 U	18.8	5.38	68	118	1 U	0.05 U	0.05 U
10/29/2009	5 U	5 U	1.4 J	5 U	5 U	2.7 J	5 U	5 U	17	5 U	5 U	5 U		1.4 U	21 J	4.2	63.9	150 J	0.16 U	0.28	0.05 U

J Indicates an estimated value.
U Analyte was not detected above the reporting limit.
UJ The analyte was not detected. The reporting limit is an approximate value.
J- Indicates estimated value, biased low.
J+ Indicates estimated value, biased high.
D Result reported from a secondary dilution analysis.
R The sample results are rejected.

MONITORING WELL GROUNDWATER ANALYTICAL RESULT SUMMARY
HYDE PARK FACILITY
NIAGARA, NEW YORK

Well ID: MW-14B

Date	PCE (µg/L)	TCE (µg/L)	Cis-1,2- DCE (µg/L)	Trans-1,2- DCE (µg/L)	1,1-DCE (µg/L)	Vinyl Chloride (µg/L)	Ethane (µg/L)	Ethene (µg/L)	Methane (µg/L)	1,1,1- Trichloroe thane (µg/L)	1,1- Dichloroe thane (µg/L)	Chloro ethane (µg/L)	Dissolved Iron (mg/L)	BOD (mg/L)	COD (mg/L)	TOC (mg/L)	Chloride (mg/L)	Sulfate (mg/L)	Sulfide (mg/L)	Nitrate (mg/L)	Nitrite (mg/L)
10/30/2007	5 U	5 U	56	0.42 J	5 U	49	2 U	2 U	110	5 U	0.6 J	5 U		2 U	6.58 J	4.07	119	263	1 U		
4/24/2008	5 U	5 U	120	0.81 J	5 U	90	1 U	1.5 J	170	5 U	0.41 J	5 U		2 U	10.1	2.95	136	222	1 U	0.05 U	0.05 U
10/29/2009	5 U	5 U	64	5 U	5 U	86	5 U	2.2 J	130	5 U	5 U	5 U		2.1 U	23.3 J	3.5	133	310 J	0.5	0.1 U	0.05 U
5/13/2010	5 U	5 U	16	5 U	5 U	33	100 U	170	3400	5 U	5 U	5 U		53.6	137	14.6	143	103	46.9	0.1 U	0.05 U
10/24/2011	5 U	5 U	4.1 J	5 U	5 U	5.4	5 U	66	690	5 U	5 U	5 U	0.0264 J	5.2 U	36 J	7	260	274	3	0.1 U	0.05 U
6/13/2012	5 U	5 U	1.5 J	5 U	5 U	5.4	2.2 J	91	9100	5 U	5 U	5 U	0.027 J	33	117	10.2	241	126	48.2	0.1 U	0.05 U
8/29/2013	5 U	5 U	5 U	5 U	5 U	1.5 J				5 U	5 U	5 U									
4/3/2014	1 U	1 U	0.67 J	1 U	1 U	1.2				1 UJ	1 U	1 U									
11/18/2015	1 U	1 U	0.95 J	1 U	1 U	1.5				1 U	0.53 J	1 U									
4/21/2016	1.0 U	1.0 U	0.94 J	1.0 U	1.0 U	1.2				1.0 U	1.0 U	1.0 U									
9/14/2017	1.0 U	1.0 U	0.92 J	1.0 U	1.0 U	2.9				1.0 U	0.43 J	1.0 U									
4/24/2018	1.0 U	1.0 U	0.72 J	1.0 U	1.0 U	1.3				1.0 U	0.34 J	1.0 U									
12/5/2019	1.0 U	1.0 U	0.37 J	1.0 U	1.0 U	0.7 J				1.0 U	0.19 J	1.0 U									
3/18/2020	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1				1.0 U	0.24 J	1.0 U									
12/7/2021	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.9				1.0 U	1.0 U	1.0 U									

J Indicates an estimated value.
U Analyte was not detected above the reporting limit.
UJ The analyte was not detected. The reporting limit is an approximate value.
J- Indicates estimated value, biased low.
J+ Indicates estimated value, biased high.
D Result reported from a secondary dilution analysis.
R The sample results are rejected.

MONITORING WELL GROUNDWATER ANALYTICAL RESULT SUMMARY
HYDE PARK FACILITY
NIAGARA, NEW YORK

Well ID: MW-15

Date	PCE (µg/L)	TCE (µg/L)	Cis-1,2- DCE (µg/L)	Trans-1,2- DCE (µg/L)	1,1-DCE (µg/L)	Vinyl Chloride (µg/L)	Ethane (µg/L)	Ethene (µg/L)	Methane (µg/L)	1,1,1- Trichloroe thane (µg/L)	1,1- Dichloroe thane (µg/L)	Chloro ethane (µg/L)	Dissolved Iron (mg/L)	BOD (mg/L)	COD (mg/L)	TOC (mg/L)	Chloride (mg/L)	Sulfate (mg/L)	Sulfide (mg/L)	Nitrate (mg/L)	Nitrite (mg/L)
10/30/2007	5 U	5 U	170	1.7 J	5 U	86				5 U	0.66 J	5 U									
4/23/2008	5 U	5 U	190	1.5 J	5 U	93				5 U	0.58 J	0.38 J									
11/3/2009	5 U	5 U	56	1.1 J	5 U	82				5 U	2 J	5 U									
5/12/2010	5 U	5 U	5.9	5 U	5 U	17	1.1 J	140	1300	5 U	1.3 J	5 U									
10/21/2011	5 U	5 U	32	1.3 J	5 U	52				5 U	1.4 J	5 U									
6/14/2012	5 U	5 U	5 U	5 U	5 U	1.8 J				5 U	1.2 J	5 U									
8/29/2013	5 U	5 U	5 U	5 U	5 U	2 J				5 U	5 U	5 U									
6/14/2018	1.0 U	1.0 UJ	5.2	0.62 J	1.0 U	16				1.0 U	1.1	1.0 U									

J Indicates an estimated value.
U Analyte was not detected above the reporting limit.
UJ The analyte was not detected. The reporting limit is an approximate value.
J- Indicates estimated value, biased low.
J+ Indicates estimated value, biased high.
D Result reported from a secondary dilution analysis.
R The sample results are rejected.

MONITORING WELL GROUNDWATER ANALYTICAL RESULT SUMMARY
HYDE PARK FACILITY
NIAGARA, NEW YORK

Well ID: MW-16A

Date	PCE (µg/L)	TCE (µg/L)	Cis-1,2- DCE (µg/L)	Trans-1,2- DCE (µg/L)	1,1-DCE (µg/L)	Vinyl Chloride (µg/L)	Ethane (µg/L)	Ethene (µg/L)	Methane (µg/L)	1,1,1- Trichloroe thane (µg/L)	1,1- Dichloroe thane (µg/L)	Chloro ethane (µg/L)	Dissolved Iron (mg/L)	BOD (mg/L)	COD (mg/L)	TOC (mg/L)	Chloride (mg/L)	Sulfate (mg/L)	Sulfide (mg/L)	Nitrate (mg/L)	Nitrite (mg/L)
10/31/2007	5 U	0.39 J	12	5 U	5 U	160	0.87 J	15	18	5 U	5 U	5 U		2 U	23.2 J	6.93	278	981	1.2		
4/25/2008	5 U	0.39 J	9	5 U	5 U	53	1 U	0.62 J	4.5	5 U	5 U	5 U		2 U	20.4	6.5	209	1020	1 U	0.05 U	0.05 U
10/27/2009	5 U	5 U	8.2	5 U	5 U	75	5 U	4.7 J	11 J	5 U	5 U	5 U		1.7 U	41.6 J	7.2	247 J	1060	0.16 U	0 R	0.05 U
5/11/2010	5 U	5 U	10	5 U	5 U	180	5 U	20	20	5 U	5 U	5 U		2 U	40.7 J	7	260	1040	0.16 U	0.1 U	0.05 U
10/27/2011	5 U	5 U	11	5 U	5 U	340	5 U	44	33	5 U	5 U	5 U	0.0424 J		31.5 J	6.9	266	1130	0.16 U	0.1 U	0.05 UJ
3/14/2012																					
3/15/2012	5 U	5 U	7.2	5 U	5 U	12	5 U	1.3 J	15 U	5 U	5 U	5 U	0.044 J			8.1	245	1110			
6/14/2012	5 U	5 U	8.4	5 U	5 U	110	5 U	11	8.7 J	5 U	5 U	5 U	0.2 U	5.4	26.5 J	9.5	237	1100			
11/29/2012	5 U	5 U	10	5 U	5 U	330	1.2 J	79	40	5 U	5 U	5 U	0.2 U			7.7	255	1100			
8/29/2013	5 U	5 U	8.5	5 U	5 U	300	1.1 J	72	29	5 U	5 U	5 U		3.8 U	31.5 J	8.2	252	1080	0.16 U	0.1 U	0.05 U
1/15/2014	5 U	5 U	9	5 U	5 U	78	5 U	6.4	5 U	5 U	5 U	5 U	0.4 U			9.5	190 J+	812 J+	0.16 U		
4/2/2014	1 U	1 U	5.9	1 U	1 U	140	5 U	20	5 U	1 U	1 U	1 U	0.4 U	4.4 U	24.1 J	7.3	214	898	0.16 U	0.1 U	0.14
10/14/2014	1 U	1 U	8.6	1 U	1 U	350	5 U	52	9.5	1 UJ	1 U	1 U	0.491			9.1	221	958	0.16 U		
11/20/2015	1 U	1 U	9.1	1 U	1 U	250	1.2 J	95	49	1 U	1 U	1 U	0.4 U	5.2 U	33.6 J	6.5	290	1080	0.16 U	0.1 U	0.05 U
4/20/2016	1.0 U	1.0 U	6.5	1.0 U	1.0 U	18	5.0 U	1.1 J	5.0 U	1.0 U	1.0 U	1.0 U	0.400 U	2.9 U	33.6 J	6.2	907	1140	0.10 U	0.14	0.050 U
9/12/2017	10 U	10 U	7.3 J	10 U	10 U	190	0.47 J	33	28	10 U	10 U	10 U	0.100 U	2.0 U	28	6.4	250	1000	1.0 U	0.50 U	0.050 UJ
4/26/2018	1.0 U	1.0 U	1.4	1.0 U	1.0 U	33	1.0 U	13	12	1.0 U	1.0 U	1.0 U	0.026 J	2.0 U	17 J	5.8	48	190	1.0 U	0.21 J	0.050 U
12/3/2019	4.0 U	0.6 J	3.6 J	4.0 U	4.0 U	120	1	49	77	4.0 U	4.0 U	4.0 U	0.20 U	2.0 U	18	6.1	170	810	1.0 U	0.50 U	
3/20/2020	13 U	13 U	8.7 J	13 U	13 U	560	3.1	270	290	13 U	13 U	13 U	0.43	2.0 U	17	6.7	210	1000	1.0 U	1.0 U	0.10 U
12/7/2021	5.0 U	5.0 U	8.2	5.0 U	5.0 U	260	7.5 U	77	160	5.0 U	5.0 U	5.0 U	0.024 J	2.0 U	52	11	190	930	1.0 U	0.42	0.050 U

J Indicates an estimated value.
U Analyte was not detected above the reporting limit.
UJ The analyte was not detected. The reporting limit is an approximate value.
J- Indicates estimated value, biased low.
J+ Indicates estimated value, biased high.
D Result reported from a secondary dilution analysis.
R The sample results are rejected.

MONITORING WELL GROUNDWATER ANALYTICAL RESULT SUMMARY
HYDE PARK FACILITY
NIAGARA, NEW YORK

Well ID: MW-16B

Date	PCE (µg/L)	TCE (µg/L)	Cis-1,2- DCE (µg/L)	Trans-1,2- DCE (µg/L)	1,1-DCE (µg/L)	Vinyl Chloride (µg/L)	Ethane (µg/L)	Ethene (µg/L)	Methane (µg/L)	1,1,1- Trichloroe thane (µg/L)	1,1- Dichloroe thane (µg/L)	Chloro ethane (µg/L)	Dissolved Iron (mg/L)	BOD (mg/L)	COD (mg/L)	TOC (mg/L)	Chloride (mg/L)	Sulfate (mg/L)	Sulfide (mg/L)	Nitrate (mg/L)	Nitrite (mg/L)
10/31/2007	5 U	5 U	210	0.88 J	5 U	63	1 U	3.7	190	5 U	5 U	5 U		2 U	5 UJ	3.7	114	269			
11/29/2007																			1 U		
4/25/2008	5 U	0.25 J	280	1.4 J	0.33 J	86	0.7 J	3.1	220	5 U	0.22 J	5 U		2 U	10.1	3.81	106	264	1.1	0.05 U	0.05 U
10/27/2009	5 U	5 U	510	1.8 J	5 U	130	5 U	3.2 J	150	5 U	5 U	5 U		1.8 U	18.8 J	3.7	120 J	286	0.22	0 R	0.05 U
5/11/2010	5 U	5 U	81	5 U	5 U	48	5 U	2.3 J	150	5 U	5 U	5 U		2.1 U	15.6 J	3.8	105	247	0.3	0.1 U	0.05 U
11/8/2010	5 U	5 U	320	1.4 J	5 U	110	5 U	5 U	120	5 U	5 U	5 U				3.7	114	264			
10/25/2011	5 U	5 U	27	5 U	5 U	43	5 U	3.8 J	140	5 U	5 U	5 U	0.2 U	2.6 U	50 U	3.5	134 J	303 J	0.38	0.1 U	0.05 U
3/15/2012	50 U	45 J	9000	36 J	23 J	830	3.1 J	73	2400	50 U	50 U	50 U	0.0585 J			17.5	78.4	96.6			
6/13/2012	10 U	74	4700	19	15	600	2.5 J	74	2600	10 U	4 J	2.6 J	0.2 U	24.6	65.1	4.1	81.5	165	33.1	0.1 U	0.05 U
11/27/2012	50 U	430	6800	24 J	29 J	820	5.6	190	3600	50 U	50 U	50 U	0.0908 J			3.5	82.8	191			
8/28/2013	5 U	2.2 J	600	5.2	2.4 J	610	5 U	75	670	5 U	1 J	5 U		5.1 U	15.6 J	3.8	90.1 J	219	1.1	0.1 U	0.05 U
1/14/2014	25 U	25 U	8800	53	17 J	5500	15	1500	18000	25 U	15 J	25 U	0.214 J			194	44.8	5 U	50.9		
4/3/2014	5 U	5 U	2300	16	5.5	2000	11	700	16000	5 U	3.4 J	5 U	0.0956 J	140	253	69.2	26.9	17.7	38.3	0.1 UJ	0.05 U
10/13/2014	1 U	1 U	17	8.8	1 U	22	13	610	21000	1 U	2.9	1 U	0.372 J			211	43.3	21.6	17.2		
11/20/2015	1 U	4.8	1100	22	2.2	780	40	920	24000	1 U	6.6	1 U	0.4 U	105	215	47.3	70.6	4.2	36.5	0.1 U	0.05 UJ
4/20/2016	1.0 U	1.0 U	1.0 U	6.8	1.0 U	4.3	17	300	31000 D	1.0 U	2	1.0 U	0.400 U	62.4	201	26.5	73.8	8.2	50.5	0.10 U	0.050 U
9/12/2017	1.0 U	1.0 U	1.0 U	0.44 J	1.0 U	2.6	15	34	8200 D	1.0 U	0.39 J	1.0 U	0.100 U	39	99	6.8	120	120	29	0.25 U	0.050 UJ
4/26/2018	1.0 U	1.0 U	0.63 J	1.0 U	1.0 U	4.6	1.0 U	2.8	9900 D	1.0 U	1.0 U	1.0 U	0.200 U	13	49	5.7	120	230	6.9	0.25 U	0.050 U
12/3/2019	1.0 U	1.0 U	1	1.0 U	1.0 U	6.7	4.2	17	9300 D	1.0 U	1.0 U	1.0 U	0.20 U	14	25	4	110	220	9.5	0.25 U	
3/20/2020	1.0 U	1.0 U	0.6 J	1.0 U	1.0 U	2.9	1.5	1.1	14000 D	1.0 U	1.0 U	1.0 U	0.048 J	17	32	3.4	120	250	13	0.50 U	0.10 U
12/7/2021	1.0 U	1.0 U	2.1	1.0 U	1.0 U	6.5	170 U	150 U	8000	1.0 U	1.0 U	1.0 U	0.54	6.4	16	7.2	130	230	4.8	0.050 U	0.050 U

J Indicates an estimated value.
U Analyte was not detected above the reporting limit.
UJ The analyte was not detected. The reporting limit is an approximate value.
J- Indicates estimated value, biased low.
J+ Indicates estimated value, biased high.
D Result reported from a secondary dilution analysis.
R The sample results are rejected.

MONITORING WELL GROUNDWATER ANALYTICAL RESULT SUMMARY
HYDE PARK FACILITY
NIAGARA, NEW YORK

Well ID: MW-17A

Date	PCE (µg/L)	TCE (µg/L)	Cis-1,2-	Trans-1,2-	1,1-DCE (µg/L)	Vinyl	Ethane (µg/L)	Ethene (µg/L)	Methane (µg/L)	1,1,1-	1,1-	Chloro ethane (µg/L)	Dissolved Iron (mg/L)	BOD (mg/L)	COD (mg/L)	TOC (mg/L)	Chloride (mg/L)	Sulfate (mg/L)	Sulfide (mg/L)	Nitrate (mg/L)	Nitrite (mg/L)
			DCE (µg/L)	DCE (µg/L)		Chloride (µg/L)				Trichloroe thane (µg/L)	Dichloroe thane (µg/L)										
11/1/2007	5 U	38	160	1.9 J	10	12	1 U	0.42 J	60	5 U	19	5 U		2 U	11.4 J	2.51	1400	134	1 U		
4/28/2008	5 U	29	200	1.5 J	9.1	28	1 U	1.5	77	5 U	20	5 U		2 U	11	2.2	1120	153	1 U	0.05 U	0.05 U
8/12/2008	5 U	40	190	2.5 J	11	24	5 U	1.5 J	120	5 U	21					2.4	1250	168			
10/7/2008	5 U	43	200	3.5 J	13	23	5 U	1.3 J	120 J	5 U	23	5 U				2.2	1270 J	165			
12/10/2008	5 U	39	210	2.2 J	12	27	5 U	1.1 J	65	5 U	25	5 U				2.2	1070	161			
1/26/2009	5 U	32	210	2.1 J	11	29	5 U	1.4 J	88	5 U	23	5 U									
3/16/2009	5 U	29	210	2.5 J	12	28	5 U	1.4 J	78	5 U	20	5 U				2.3	1220	170			
10/20/2009	5 U	24	200	2.2 J	14	24	5 U	5 U	120	5 U	29	5 U				3.1	1080 J	198 J			
10/28/2009	5 U	22	180	1.6 J	14	25	5 U	5 U	97	5 U	30	5 U		1.9 U	59.9 J	2.9	1130 J	192	0.16 U	0 R	0.05 U
12/11/2009	5 U	11	200	1.4 J	13	29	5 U	5 U	100	5 U	28	5 U				3.1	1060 J	217 J			
2/9/2010	5 U	14	210	1.3 J	11	34	5 U	5 U	110	5 U	24	5 U				3.7 J	962	194			
3/30/2010	5 U	11	180	1.7 J	10	24				5 U	20	5 U									
5/6/2010	5 U	15	210	1.4 J	11	27	5 U	5 U	15 U	5 U	20	5 U		3.6 U	29.3 J	2.9	729 J	196 J	0.16 U	0.1 U	0.05 U
11/11/2010	5 U	16	200	1.9 J	13	28	1.5 J	8.5	2100	5 U	27	5 U				3.1	661	195			
10/24/2011	5 U	11	160	1.2 J	12	30	11	3.2 J	4900	5 U	26	5 U	0.2 U	5.1	33.8 J	3.9	1010	189	0.16 U	0.1 U	0.05 U
6/12/2012	5 U	5.3	140	1.2 J	8.1	25	12	3.1 J	8500	5 U	21	5 U	0.2 U	5.9	28.8 J	4.4	484	172	0.16 U	0.1 U	0.05 U
8/28/2013	5 U	3.1 J	180	5 U	6.3	45	11	8.8	12000	5 U	22	5 U		9.8	27 J	3.8	318 J	151	0.16 U	0.1 U	0.05 U
4/3/2014	1 U	0.62 J	150	1 U	3.6	49	14	17	18000	1 UJ	16	1 U	2.14	8.5	49.3 J	5.1	277	145	0.16 U	0.1 UJ	0.05 U
11/18/2015	1 U	1 U	160	1 U	1 U	86	12	11	15000	1 U	18	1 U	1.45	7.3	15.2 J	3	167	114	0.16 U	0.1 U	0.05 U
4/20/2016	1.0 U	1.0 U	110	1.0 U	1.0 U	89	7.4	11	15000 D	1.0 U	15	1.0 U	0.955	7.8	26.7 J	3.2	161	131	0.10 U	0.10 U	0.050 U
9/12/2017	5.0 U	5.0 U	120	5.0 U	5.0 U	120	5.5	8.4	3700 D	5.0 U	17	5.0 U	0.92	3.4	17	3	82	97	1.0 U	0.25 U	0.050 UJ
4/25/2018	5.0 U	5.0 U	59	5.0 U	5.0 U	91	10 U	10 U	13000	5.0 U	11	5.0 U	1	4.8 J	19	3.7	92	100	1.0 U	0.25 U	0.050 U
12/5/2019	2.0 U	2.0 U	50	2.0 U	2.0 U	83	11	17	9400 D	2.0 U	13	2.0 U	0.55	4.2	10 U	2.8	57	67	1.0 U	0.25 U	
3/19/2020	2.0 U	2.0 U	38	2.0 U	2.0 U	78	17	21	17000 D	2.0 U	12	2.0 U	0.7		7.6 J	2.7	53	70	1.0 U	0.50 UJ	0.10 UJ
12/8/2021	4.0 U	4.0 U	48	4.0 U	4.0 U	110	9.4	14	12000	4.0 U	13	4.0 U	0.69	6.0 U	52	4.1	32	55	1.0 U	0.25 U	0.25 U

J Indicates an estimated value.
U Analyte was not detected above the reporting limit.
UJ The analyte was not detected. The reporting limit is an approximate value.
J- Indicates estimated value, biased low.
J+ Indicates estimated value, biased high.
D Result reported from a secondary dilution analysis.
R The sample results are rejected.

MONITORING WELL GROUNDWATER ANALYTICAL RESULT SUMMARY
HYDE PARK FACILITY
NIAGARA, NEW YORK

Well ID: MW-17B

Date	PCE (µg/L)	TCE (µg/L)	Cis-1,2- DCE (µg/L)	Trans-1,2- DCE (µg/L)	1,1-DCE (µg/L)	Vinyl Chloride (µg/L)	Ethane (µg/L)	Ethene (µg/L)	Methane (µg/L)	1,1,1- Trichloroe thane (µg/L)	1,1- Dichloroe thane (µg/L)	Chloro ethane (µg/L)	Dissolved Iron (mg/L)	BOD (mg/L)	COD (mg/L)	TOC (mg/L)	Chloride (mg/L)	Sulfate (mg/L)	Sulfide (mg/L)	Nitrate (mg/L)	Nitrite (mg/L)
11/1/2007	5 U	4 J	440	3.4 J	3.4 J	64	0.66 J	2.8	180	5 U	9.3	5 U		2 U	9.7 J	3.31	431	209	1 U		
4/28/2008	5 U	4.6 J	630	8.5	5.5	82	0.53 J	4	160	5 U	17	5 U		2 U	10.4	3.06	475	211	1 U	0.05 U	0.05 U
10/8/2008	5 U	3.3 J	600	5.9	4.4 J	120	5 U	6.6	170 J	5 U	22	5 U				55.7	561 J	169			
12/10/2008	5 U	2.6 J	260	3.1 J	2.9 J	170	5 U	33	120	5 U	28	5 U				3	802	180			
1/26/2009	5 U	2.1 J	280	4.2 J	3.1 J	210	5 U	61	130	5 U	24	5 U									
3/17/2009	5 U	1.6 J	270	3.6 J	3.2 J	180	5 U	71	180	5 U	22	5 U				3.5	631	275			
10/20/2009	5 U	4.2 J	280 J	2.4 J	4.5 J	73	3 J	22	120	5 U	29	5 U				3	768 J	204 J			
10/28/2009	5 U	3.1 J	280	2.2 J	3.1 J	69	2 J	14	89	5 U	26	5 U		2.2 U	53.1 J	3.1	720 J	195	0.1 J	0 R	0.05 U
12/11/2009	5 U	2.2 J	170	2.4 J	5 U	160	2.4 J	130	300	5 U	8.4	5 U				264	171 J	18.3 J			
2/9/2010	5 U	1.2 J	31	1.8 J	5 U	52	4.2 J	190	4400	5 U	31	5 U				122 J	727	32.2			
3/30/2010	5 U	5 U	5.9	1.7 J	5 U	10				5 U	37	5 U									
5/6/2010	5 U	5 U	8.5	1.4 J	5 U	9.6	5 U	5 U	15 U	5 U	45	5 U		157 J	219	12.7	883 J	49.7 J	14.3	0.1 U	0.05 U
11/10/2010	5 U	5 U	8.1	0.86 J	5 U	8.8	16	110	4200	5 U	40	5 U				4.5	981	118			
10/26/2011	5 U	5 U	19	0.82 J	5 U	27	70	81	15000	5 U	48	1.4 J	0.102 J	5.7	45.1 J	3.2	966	154 J	4.5	0.1 U	0.05 U
3/13/2012	5 U	5 U	14	1.1 J	5 U	15	44	83	18000	5 U	46	1.3 J	0.0442 J			10.9	682	118			
6/12/2012	5 U	5 U	20	0.82 J	5 U	18	45	72	23000	5 U	43	1.5 J	0.19 J	9.6	49.2 J	3.8	739	116	11.6	0.1 U	0.05 U
11/27/2012	5 U	5 U	28 J	5 U	5 U	31	41	79	19000	5 U	35 J	5 U	0.172 J			3.2	669	130			
8/28/2013	5 U	5 U	35	5 U	5 U	40	29	56	19000	5 U	38	5 U		12.7	40.6 J	3.6	521 J	138	1.2	0.1 U	0.05 U
1/15/2014	5 U	5 U	1.8 J	1.5 J	5 U	2.9 J	7.2	52	19000	5 U	7.9	11	54.8			454	351 J+	5 U	6.3		
4/1/2014	1 U	1 U	1.3	0.73 J	1 U	2.1	13	34	20000	1 U	8.2	7.4	16.6	139	228	55.1	288	6.9	8.2 J-	0.1 U	0.016 J
10/14/2014	1 U	1 U	0.52 J	0.71 J	1 U	1.1	8.3	17	16000	1 UJ	3.3	8.2	15.5			38.4	386	5 U	4.1		
11/18/2015	1 U	1 U	1 U	1 U	1 U	0.8 J	8.5	8.9	14000	1 U	1.5	7.9	13.4	17.6	102	18.8	374	2.5 J	1.4	0.1 U	0.05 U
4/21/2016	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	0.88 J	8	7	18000 D	1.0 U	1.7	6.7	17.3	20.4	103	25	327	7.2	1	0.10 U	0.050 U
9/12/2017	1.0 U	0.68 J	10	0.45 J	1.0 U	12	3.5	4.6	6800	1.0 U	6.3 J	7.6	5.3	6.2	78	17	210	47	0.73 J	0.50 U	0.050 UJ
4/25/2018	1.0 U	1.0 U	4.9	0.39 J	1.0 U	7.9	19	27	22000	1.0 U	4.5	3.7	4.7	6.8	89	20	170	45	2.1	0.25 U	0.039 J
12/5/2019	1.0 U	1.0 U	11	0.28 J	1.0 U	14	24	17	27000 D	1.0 U	4.3	6.6	3.1	9.7 J-	19	5.9	140	67	2.3	0.25 U	
3/19/2020	1.0 U	1.0 U	1.4	1.0 U	1.0 U	2.6	23	6.5	33000 D	1.0 U	4.5	8.9	4.1		21	5.4	110	39	2.9	0.50 UJ	0.10 UJ
12/8/2021	4.0 U	4.0 U	31	4.0 U	4.0 U	20	170 U	150 U	26000	4.0 U	7.3	2.9 J	0.94	16	13	12	130	90	5.6	0.25 U	0.25 U

J Indicates an estimated value.
U Analyte was not detected above the reporting limit.
UJ The analyte was not detected. The reporting limit is an approximate value.
J- Indicates estimated value, biased low.
J+ Indicates estimated value, biased high.
D Result reported from a secondary dilution analysis.
R The sample results are rejected.

MONITORING WELL GROUNDWATER ANALYTICAL RESULT SUMMARY
HYDE PARK FACILITY
NIAGARA, NEW YORK

Well ID: MW-18A

Date	PCE (µg/L)	TCE (µg/L)	Cis-1,2- DCE (µg/L)	Trans-1,2- DCE (µg/L)	1,1-DCE (µg/L)	Vinyl Chloride (µg/L)	Ethane (µg/L)	Ethene (µg/L)	Methane (µg/L)	1,1,1- Trichloroe thane (µg/L)	1,1- Dichloroe thane (µg/L)	Chloro ethane (µg/L)	Dissolved Iron (mg/L)	BOD (mg/L)	COD (mg/L)	TOC (mg/L)	Chloride (mg/L)	Sulfate (mg/L)	Sulfide (mg/L)	Nitrate (mg/L)	Nitrite (mg/L)
11/1/2007	5 U	22	25	0.46 J	0.58 J	6.7	0.38 J	1 U	17	5 U	4.1 J	5 U		2 U	5 UJ	1.79	74.2	125	1 U		
4/28/2008	5 U	25	31	0.44 J	0.8 J	2.1 J	1 U	1 U	16	5 U	3.8 J	5 U		2 U	5 U	1.56	79.6	133	1 U	0.05 U	0.05 U
10/27/2009	5 U	25	43	5 U	0.93 J	7	5 U	5 U	23	5 U	4.7 J	5 U		1.4 U	14.2 J	1.5	90.2 J	130	0.16 U	0 R	0.05 U
5/12/2010	5 U	25	51	5 U	1.1 J	2.6 J	5 U	5 U	13 J	5 U	4.2 J	5 U		1.6 U	50 U	2.1	104 J	132	0.16 U	0.1 U	0.05 U
10/24/2011	5 U	23	42	5 U	0.9 J	8.4	5 U	5 U	19	5 U	4.7 J	5 U	0.0478 J	2.1 U	50 U	1.8	293	156	0.16 U	0.1 U	0.05 U
6/12/2012	5 U	21	56	0.94 J	1.1 J	2.4 J	5 U	5 U	11 J	5 U	4.2 J	5 U	0.2 U	3.1 U	50 U	1	108	129	0.16 U	0.1 U	0.05 U
8/27/2013	5 U	25	58	0.87 J	0.98 J	3.4 J	5 U	5 U	10	5 UJ	4.9 J	5 U		6.2	50 U	2.1	118	138	0.16 U	0.1 U	0.05 U
4/2/2014	1 U	27	43	0.76 J	0.9 J	0.86 J	5 U	5 U	3.4 J	1 UJ	3.6	1 U	0.89	3.3 U	50 U	2.4	106 J-	124 J+	0.16 U	0.1 U	0.05 U
11/18/2015	1 U	38	51	0.73 J	1.1	2.3	5 U	5 U	11 J	1 U	4.5	1 U	1.5	2.8 U	50 U	1.2	113	118	0.16 U	0.1 U	0.05 U
4/20/2016	1.0 U	37	51	0.83 J	0.99 J	0.62 J	5.0 U	5.0 U	5.2	1.0 U	4.3	1.0 U	0.463	4.2 U	19.8 J	1.4	233	144	0.10 U	0.10 U	0.050 U
9/13/2017	2.0 U	29	58	0.8 J	1 J	1.8 J	0.50 U	0.50 U	5.3	2.0 U	5	2.0 U	1.2	2.0 U	12	1.3	86	120	1.0 U	0.25 U	0.050 U
4/26/2018	1.0 U	36	42	0.61 J	0.88 J	1.1	1.0 U	1.0 U	13	1.0 U	3.7	1.0 U	0.99	2.0 U	12	1.5	81	130	1.0 U	0.25 U	0.050 U
12/4/2019	2.0 U	32	43	0.66 J	0.93 J	0.97 J	0.36 J	1.0 U	9.2	2.0 U	3.6	2.0 U	0.9	2.0 U	10 U	1.3	67	130	1.0 U	0.25 U	
3/19/2020	2.0 U	34	46	0.81 J	0.87 J	1.1 J	1.0 U	1.0 U	17	2.0 U	3.7	2.0 U	0.99		4.1 J	1.3	65	130	1.0 U	0.50 UJ	0.10 UJ
12/7/2021	1.0 UJ	23 J-	43 J-	1.0 UJ	0.49 J-	2.3 J-	7.5 U	7.0 U	4000	1.0 UJ	3.3 J-	1.0 UJ	1.4	2.0 U	45	2.2	53	120	1.0 U	0.050 U	0.050 U

J Indicates an estimated value.
U Analyte was not detected above the reporting limit.
UJ The analyte was not detected. The reporting limit is an approximate value.
J- Indicates estimated value, biased low.
J+ Indicates estimated value, biased high.
D Result reported from a secondary dilution analysis.
R The sample results are rejected.

MONITORING WELL GROUNDWATER ANALYTICAL RESULT SUMMARY
HYDE PARK FACILITY
NIAGARA, NEW YORK

Well ID: MW-18B

Date	PCE (µg/L)	TCE (µg/L)	Cis-1,2- DCE (µg/L)	Trans-1,2- DCE (µg/L)	1,1-DCE (µg/L)	Vinyl Chloride (µg/L)	Ethane (µg/L)	Ethene (µg/L)	Methane (µg/L)	1,1,1- Trichloroe thane (µg/L)	1,1- Dichloroe thane (µg/L)	Chloro ethane (µg/L)	Dissolved Iron (mg/L)	BOD (mg/L)	COD (mg/L)	TOC (mg/L)	Chloride (mg/L)	Sulfate (mg/L)	Sulfide (mg/L)	Nitrate (mg/L)	Nitrite (mg/L)
11/1/2007	5 U	5 U	160	0.9 J	5 U	140		2.1	120	5 U	5 U	5 U		2 U	5 UJ	4.09	80.9	261			
11/29/2007																			1 U		
4/28/2008	5 U	5 U	120	0.73 J	5 U	180	0.74 J	2.4	150	5 U	5 U	5 U		2 U	9.86	3.74	88.1	270	1 U	0.05 U	0.05 U
10/27/2009	5 U	5 U	62	5 U	5 U	220	5 U	2.3 J	120	5 U	5 U	5 U		1.7 U	23.3 J	4.1	93.8 J	296	0.16 U	0 R	0.05 U
5/12/2010	5 U	5 U	69	5 U	5 U	190	5 U	2.4 J	130	5 U	5 U	5 U									
10/25/2011	5 U	5 U	150	0.9 J	5 U	220	5 U	4 J	120	5 U	5 U	5 U	0.0657 J	2.4 U	50 U	3.9	114 J	305 J	0.16 U	0.1 U	0.05 U
3/14/2012	5 U	5 U	59	5 U	5 U	170	5 U	2.3 J	96	5 U	5 U	5 U	0.0423 J			3.5	102	281			
6/12/2012	5 U	5 U	110	5 U	5 U	140	5 U	3.6 J	110	5 U	5 U	5 U	0.2 U	3.5 U	50 U	4	102	268	0.16 U	0.1 U	0.05 U
11/28/2012	5 U	5 U	89	5 U	5 U	180	5 U	5.2	150	5 U	5 U	5 U	0.2 U			4.2	106	284			
8/15/2013	0.96 J	5 U	120	5 U	5 U	190				5 U	5 U	5 U							0.16 U		
8/27/2013	5 U	5 U	110	5 U	5 U	190	5 U	5.3	170	5 UJ	5 U	5 U		2.8 U	17.9 J	4.9	106	284	0.16 U	0.1 U	0.05 U
1/17/2014	5 U	5 U	28	5 U	5 U	56	3.2 J	41	5000	5 U	5 U	5 U	5.97			941	91.1	55.1	17.3		
1/21/2014																					
4/2/2014	1 U	1 U	43	1 U	1 U	71	3.8 J	33	13000	1 UJ	1 U	1 U	2.91	889 J	1340	427	79.3 J-	86.1 J+	7.7	0.1 U	0.05 U
10/13/2014	1 U	1 U	1.1	1 U	1 U	4.6	4 J	11	18000	1 U	1 U	1 U	8.37			166	34.9	3.8 J	2.8		
11/18/2015	1 U	1 U	35	1 U	1 U	40	3.5 J	15	18000	1 U	1 U	1 U	2.54	35.7	167	41.5	62.2	70.9	1.5	0.1 U	0.05 U
4/21/2016	1.0 U	1.0 U	90	1.0 U	1.0 U	120	2.8 J	16	19000 D	1.0 U	1.0 U	1.0 U	0.893	22.1	88.7	21.7	122	189	4.8	0.10 U	0.050 U
9/13/2017	20 U	20 U	380	20 U	20 U	210	6.8	38	5000 D	20 U	20 UJ	20 U	0.52	23	99	11	110	140	7.3	0.50 U	0.050 U
4/26/2018	2.5 U	2.5 U	69	2.5 U	2.5 U	92	2	12	17000 D	2.5 U	2.5 U	2.5 U	0.41	17	71	12	97	130	10	0.25 U	0.050 U
12/4/2019	2.0 U	2.0 U	56	2.0 U	2.0 U	70	2.3	9.9	24000 D	2.0 U	2.0 U	2.0 U	0.35	35 J-	49	8.8	96	130	13	0.25 U	
3/19/2020	2.0 U	2.0 U	32	2.0 U	2.0 U	51	2.5	29	24000 D	2.0 U	2.0 U	2.0 U	0.23		53	7.2	100	170	16	0.50 UJ	0.10 UJ
12/7/2021	2.0 U	2.0 U	47	2.0 U	2.0 U	80	170 U	150 U	13000	2.0 U	2.0 U	2.0 U	0.32	14	39	6	98	190	8	0.050 U	0.050 U

J Indicates an estimated value.
U Analyte was not detected above the reporting limit.
UJ The analyte was not detected. The reporting limit is an approximate value.
J- Indicates estimated value, biased low.
J+ Indicates estimated value, biased high.
D Result reported from a secondary dilution analysis.
R The sample results are rejected.

MONITORING WELL GROUNDWATER ANALYTICAL RESULT SUMMARY
HYDE PARK FACILITY
NIAGARA, NEW YORK

Well ID: MW-19A

Date	PCE (µg/L)	TCE (µg/L)	Cis-1,2- DCE (µg/L)	Trans-1,2- DCE (µg/L)	1,1-DCE (µg/L)	Vinyl Chloride (µg/L)	Ethane (µg/L)	Ethene (µg/L)	Methane (µg/L)	1,1,1- Trichloroe thane (µg/L)	1,1- Dichloroe thane (µg/L)	Chloro ethane (µg/L)	Dissolved Iron (mg/L)	BOD (mg/L)	COD (mg/L)	TOC (mg/L)	Chloride (mg/L)	Sulfate (mg/L)	Sulfide (mg/L)	Nitrate (mg/L)	Nitrite (mg/L)
10/31/2007	5 U	5 U	4.2 J	5 U	5 U	4				5 U	5 U	5 U									
4/24/2008	5 U	5 U	3.2 J	5 U	5 U	1.2 J				5 U	5 U	5 U									
11/2/2009	5 U	5 U	3.7 J	5 U	5 U	2.8 J				5 U	5 U	5 U									

J Indicates an estimated value.
U Analyte was not detected above the reporting limit.
UJ The analyte was not detected. The reporting limit is an approximate value.
J- Indicates estimated value, biased low.
J+ Indicates estimated value, biased high.
D Result reported from a secondary dilution analysis.
R The sample results are rejected.

MONITORING WELL GROUNDWATER ANALYTICAL RESULT SUMMARY
HYDE PARK FACILITY
NIAGARA, NEW YORK

Well ID: MW-19B


Date	PCE (µg/L)	TCE (µg/L)	Cis-1,2- DCE (µg/L)	Trans-1,2- DCE (µg/L)	1,1-DCE (µg/L)	Vinyl Chloride (µg/L)	Ethane (µg/L)	Ethene (µg/L)	Methane (µg/L)	1,1,1- Trichloroe thane (µg/L)	1,1- Dichloroe thane (µg/L)	Chloro ethane (µg/L)	Dissolved Iron (mg/L)	BOD (mg/L)	COD (mg/L)	TOC (mg/L)	Chloride (mg/L)	Sulfate (mg/L)	Sulfide (mg/L)	Nitrate (mg/L)	Nitrite (mg/L)
10/31/2007	5 U	5 U	12	5 U	5 U	3.4				5 U	5 U	5 U									
4/24/2008	5 U	5 U	24	5 U	5 U	5.8				5 U	5 U	5 U									
11/2/2009	5 U	5 U	68	5 U	5 U	7.2				5 U	5 U	5 U									
5/12/2010	5 U	5 U	2.1 J	5 U	5 U	2.1 J	5 U	5 U	160	5 U	5 U	5 U									
10/20/2011	5 U	5 U	8.7	5 U	5 U	3.3 J				5 U	5 U	5 U									
6/12/2012	5 U	5 U	2.3 J	5 U	5 U	1.6 J				5 U	5 U	5 U									
8/28/2013	5 U	5 U	2.1 J	5 U	5 U	1.2 J				5 U	5 U	5 U									
4/2/2014	1 U	1 U	2.9	1 U	1 U	0.65 J				1 U	1 U	1 U									
11/17/2015	1 U	1 U	1.8	1 U	1 U	1				1 U	1 U	1 U									
4/19/2016	1.0 U	1.0 U	1.1	1.0 U	1.0 U	1.1				1.0 U	1.0 U	1.0 U									
9/13/2017	1.0 U	1.0 U	1.6	1.0 U	1.0 U	1.5				1.0 U	1.0 UJ	1.0 U									
4/23/2018	1.0 U	1.0 U	24	1.0 U	1.0 U	5				1.0 U	1.0 U	1.0 U									
12/4/2019	1.0 U	1.0 U	1.4	1.0 U	1.0 U	1.2				1.0 U	1.0 U	1.0 U									
3/20/2020	1.0 U	1.0 U	11	1.0 U	1.0 U	2.3				1.0 U	1.0 U	1.0 U									
12/7/2021	1.0 U	1.0 U	1.8	1.0 U	1.0 U	1.5				1.0 U	1.0 U	1.0 U									

J Indicates an estimated value.
U Analyte was not detected above the reporting limit.
UJ The analyte was not detected. The reporting limit is an approximate value.
J- Indicates estimated value, biased low.
J+ Indicates estimated value, biased high.
D Result reported from a secondary dilution analysis.
R The sample results are rejected.


Appendix D

Long-Term Trend Graphs of Chlorinated Ethenes in Monitoring Wells, 2000-2021

CONCENTRATIONS OF CHLOROETHENES MW-5A



CONCENTRATIONS OF CHLOROETHENES MW-5B



- ◆ TCE
- DCE
- ▲ VC
- × DCA
- ✱ OB Injection (Fall 08)
- OB & BR Injection (Fall 09)
- ✱ OB Injection (Fall 11)
- OB+ BR Injection (Fall 13)


FORMER CARBORUNDUM COMPANY

LONG TERM TRENDS OF CHLORINATED
ETHENES IN WELLS MW-5A AND MW-5B

AECOM

1 John James Audubon Parkway, Amherst, NY 14228

CONCENTRATIONS OF CHLOROETHENES MW-6



- ◆ TCE
- DCE
- ▲- VC
- × DCA
- ✱ OB Injection (Fall 08)
- OB & BR Injection (Fall 09)
- ✱ OB Injection (Fall 11)
- OB+ BR Injection (Fall 13)


FORMER CARBORUNDUM COMPANY

LONG TERM TRENDS OF CHLORINATED
ETHENES IN WELLS MW-6


AECOM

1 John James Audubon Parkway, Amherst, NY 14228

CONCENTRATIONS OF CHLOROETHENES MW-7A



CONCENTRATIONS OF CHLOROETHENES MW-7B



- ◆ TCE
- DCE
- ▲ VC
- × DCA
- ⋈ OB Injection (Fall 08)
- OB & BR Injection (Fall 09)
- ⋈ OB Injection (Fall 11)
- OB+ BR Injection (Fall 13)


FORMER CARBORUNDUM COMPANY

LONG TERM TRENDS OF CHLORINATED
ETHENES IN WELLS MW-7A AND MW-7B


AECOM

1 John James Audubon Parkway, Amherst, NY 14228

CONCENTRATIONS OF CHLOROETHENES MW-10A



CONCENTRATIONS OF CHLOROETHENES MW-10B



- ◆ TCE
- DCE
- ▲ VC
- × DCA
- OB Injection (Fall 08)
- OB & BR Injection (Fall 09)
- OB Injection (Fall 11)
- OB+ BR Injection (Fall 13)


FORMER CARBORUNDUM COMPANY

LONG TERM TRENDS OF CHLORINATED
ETHENES IN WELLS MW-10A AND MW-10B


AECOM

1 John James Audubon Parkway, Amherst, NY 14228

CONCENTRATIONS OF CHLOROETHENES MW-12A



CONCENTRATIONS OF CHLOROETHENES MW-12B



- ◆ TCE
- DCE
- - - VC
- × DCA
- ✱ OB Injection (Fall 08)
- OB & BR Injection (Fall 09)
- ✱ OB Injection (Fall 11)
- OB+ BR Injection (Fall 13)


FORMER CARBORUNDUM COMPANY

LONG TERM TRENDS OF CHLORINATED
ETHENES IN WELLS MW-12A AND MW-12B


AECOM

1 John James Audubon Parkway, Amherst, NY 14228

CONCENTRATIONS OF CHLOROETHENES MW-13B



CONCENTRATIONS OF CHLOROETHENES MW-14B



- ◆ TCE
- DCE
- ▲ VC
- × DCA
- ✱ OB Injection (Fall 08)
- OB & BR Injection (Fall 09)
- ✱ OB Injection (Fall 11)
- OB+ BR Injection (Fall 13)


FORMER CARBORUNDUM COMPANY

LONG TERM TRENDS OF CHLORINATED
ETHENES IN WELLS MW-13B AND MW-14B

AECOM

1 John James Audubon Parkway, Amherst, NY 14228

CONCENTRATIONS OF CHLOROETHENES MW-15



- ◆ TCE
- DCE
- ▲ VC
- × DCA
- ✱ OB Injection (Fall 08)
- ✱ OB & BR Injection (Fall 09)
- ✱ OB Injection (Fall 11)
- ✱ OB+ BR Injection (Fall 13)


FORMER CARBORUNDUM COMPANY

LONG TERM TRENDS OF CHLORINATED
ETHENES IN WELLS MW-15


AECOM

1 John James Audubon Parkway, Amherst, NY 14228

CONCENTRATIONS OF CHLOROETHENES MW-16A



CONCENTRATIONS OF CHLOROETHENES MW-16B



- ◆ TCE
- DCE
- ▲ VC
- × DCA
- ✱ OB Injection (Fall 08)
- OB & BR Injection (Fall 09)
- ✱ OB Injection (Fall 11)
- OB+ BR Injection (Fall 13)


FORMER CARBORUNDUM COMPANY

LONG TERM TRENDS OF CHLORINATED
ETHENES IN WELLS MW-16A AND MW-16B


AECOM

1 John James Audubon Parkway, Amherst, NY 14228

CONCENTRATIONS OF CHLOROETHENES MW-17A



CONCENTRATIONS OF CHLOROETHENES MW-17B



- ◆ TCE
- DCE
- - - VC
- × DCA
- OB Injection (Fall 08)
- OB & BR Injection (Fall 09)
- OB Injection (Fall 11)
- OB+ BR Injection (Fall 13)


FORMER CARBORUNDUM COMPANY

LONG TERM TRENDS OF CHLORINATED
ETHENES IN WELLS MW-17A AND MW-17B


AECOM

1 John James Audubon Parkway, Amherst, NY 14228

CONCENTRATIONS OF CHLOROETHENES MW-18A



CONCENTRATIONS OF CHLOROETHENES MW-18B



- ◆ TCE
- DCE
- ▲ VC
- × DCA
- * OB Injection (Fall 08)
- OB & BR Injection (Fall 09)
- + OB Injection (Fall 11)
- OB+ BR Injection (Fall 13)


FORMER CARBORUNDUM COMPANY

LONG TERM TRENDS OF CHLORINATED
ETHENES IN WELLS MW-18A AND MW-18B

AECOM

1 John James Audubon Parkway, Amherst, NY 14228

CONCENTRATIONS OF CHLOROETHENES MW-19B



- ◆ TCE
- DCE
- ▲ VC
- × DCA
- ✱ OB Injection (Fall 08)
- OB & BR Injection (Fall 09)
- ✱ OB Injection (Fall 11)
- OB+ BR Injection (Fall 13)

FORMER CARBORUNDUM COMPANY

LONG TERM TRENDS OF CHLORINATED
ETHENES IN WELLS MW-19B

AECOM

1 John James Audubon Parkway, Amherst, NY 14228