

The electronic version of this file/report should have the file name:

Type of document . Site Number . Year-Month . File Year-Year or Report name . pdf

letter. \_\_\_\_\_ . \_\_\_\_\_ - \_\_\_\_\_.CorrespondenceFile\_\_\_\_\_.pdf

example: letter . Site Number . Year-Month . CorrespondanceFileYear-Year . pdf

report. hw932048B . 1990 - 01 . "Phase I Bldg 82" .pdf

example: report . Site Number . Year-Month . ReportName . pdf

if a non-foitable site: add ".nf.pdf" at end of file name

Project Site numbers will be proceeded by the following:

Municipal Brownfields - B

Superfund - HW

Spills - SP

ERP - E

VCP - V

BCP - C

# **ENGINEERING INVESTIGATIONS AT INACTIVE HAZARDOUS WASTE SITES**

## **PHASE I INVESTIGATION**

**CARBORUNDUM BUILDING 82, SITE NUMBER 932048B  
CITY OF NIAGARA FALLS, NIAGARA COUNTY**

**January 1990**



**Prepared for:  
New York State Department  
of Environmental Conservation**

**50 Wolf Road, Albany, New York 12233  
Thomas C. Jorling, Commissioner**

**Division of Hazardous Waste Remediation  
Michael J. O'Toole, Jr., P.E., Director**


**Prepared by:  
Ecology and Environment Engineering, P.C.**

# **ENGINEERING INVESTIGATIONS AT INACTIVE HAZARDOUS WASTE SITES**

## **PHASE I INVESTIGATION**

**CARBORUNDUM BUILDING 82, SITE NUMBER 932048B  
CITY OF NIAGARA FALLS, NIAGARA COUNTY**

**January 1990**



**Prepared for:**

**New York State Department  
of Environmental Conservation**

**50 Wolf Road, Albany, New York 12233**

**Thomas C. Jorling, Commissioner**

**Division of Hazardous Waste Remediation**

**Michael J. O'Toole, Jr., P.E., Director**

**Prepared by:**



**ecology and environment  
engineering, p.c.**

**BUFFALO CORPORATE CENTER**

**368 PLEASANTVIEW DRIVE, LANCASTER, NEW YORK 14086, TEL. 716/684-8060**

## TABLE OF CONTENTS

<u>Section</u>	<u>Page</u>
1 EXECUTIVE SUMMARY .....	1-1
1.1 SITE BACKGROUND .....	1-1
1.2 PHASE I EFFORTS .....	1-1
1.3 ASSESSMENT .....	1-1
1.4 HAZARD RANKING SYSTEM SCORE .....	1-4
2 PURPOSE .....	2-1
3 SCOPE OF WORK .....	3-1
4 SITE ASSESSMENT .....	4-1
4.1 SITE HISTORY .....	4-1
4.2 SITE TOPOGRAPHY .....	4-2
4.3 SITE HYDROLOGY .....	4-2
4.3.1 Regional Geology and Hydrology .....	4-2
4.3.2 Site Hydrogeology .....	4-3
4.3.3 Hydraulic Connections .....	4-4
4.4 SITE CONTAMINATION .....	4-4
5 PRELIMINARY APPLICATION OF THE HRS .....	5-1
5.1 NARRATIVE SUMMARY .....	5-1
5.2 LOCATION .....	5-2
5.3 HRS WORKSHEETS .....	5-3
5.4 HRS DOCUMENTATION RECORDS .....	5-10
5.5 EPA FORM 2070-13 .....	5-101

## Table of Contents (Cont.)

<u>Section</u>		<u>Page</u>
6	ASSESSMENT OF DATA ADEQUACY AND RECOMMENDATIONS .....	6-1
7	REFERENCES .....	7-1
<u>Appendix</u>		
A	PHOTOGRAPHIC RECORD .....	A-1
B	UPDATED INACTIVE HAZARDOUS WASTE DISPOSAL AREA REGISTRY FORM .....	B-1
C	PHOTOCOPIED REFERENCES .....	C-1

## LIST OF ILLUSTRATIONS

<u>Figure</u>		<u>Page</u>
1-1	Location Map .....	1-2
1-2	Site Map - Carborundum Building 82 .....	1-3
5-1	Location Map .....	5-2

## LIST OF TABLES

<u>Table</u>		<u>Page</u>
3-1	Sources Contacted for the NYSDEC Phase I Investigation at Carborundum Building 82 .....	3-3



## 1. EXECUTIVE SUMMARY

### 1.1 SITE BACKGROUND

The Carborundum Building 82 site, now owned by Electro Minerals (U.S.), Inc., is approximately 40 acres in area. The site is located adjacent to the Robert Moses Parkway near the Niagara River in the City of Niagara Falls, Niagara County (see Figures 1-1 and 1-2). A portion of this facility was used by Carborundum for temporary storage of sand, fly ash, fire brick, dust collector fines, kiln furniture, wood, carborundum, grinding wheels, aluminum-silica shot, fiber, and metal scrap. It is unknown if any hazardous waste was stored or disposed in this area.

### 1.2 PHASE I EFFORTS

The site was visited on June 24, 1987, by Ecology and Environment, Inc., (E & E) personnel to conduct a physical inspection of the site in support of this investigation. Prior to the inspection, available state, federal, and municipal files were reviewed, and individuals having knowledge of the site were contacted. The site inspection consisted of a walk-over survey around the perimeter and an interview with the plant Environmental Health and Safety Manager.

### 1.3 ASSESSMENT

In general, the site was free of stored waste. No landfill activity was noted and the former storage area was graded with crushed stone. All formerly stored waste appeared to be removed.






Figure 1-1 LOCATION MAP




Figure 1-2 SITE MAP - CARBORUNDUM BUILDING 82

There is little site specific hydrogeologic information available for the Carborundum Building 82 site. There are no known wells on site, and no sampling has been conducted in the former disposal area. E & E personnel used an HNu photoionizer while inspecting the site in 1987; they obtained no readings above background levels. Further site investigation would need to be performed to determine if contaminants are present, including soil and groundwater sampling and analysis.

#### 1.4 HAZARD RANKING SYSTEM SCORE

A preliminary application of the Hazard Ranking System (HRS) has been made to quantify the risk associated with this site. As the Phase I investigation is limited in scope, not all the information needed to fully evaluate the site is available. An HRS score was completed on the basis of the available data. Absence of necessary data may result in an unrealistically low HRS score.

Under the HRS, three numerical scores are computed to express the site's relative risk or damage to the population and the environment. The three scores are:

- o  $S_M$  reflects the potential for harm to humans or the environment from migration of a hazardous substance away from the facility by routes involving groundwater, surface water, or air. It is a composite of separate scores for each of the three routes ( $S_{GW}$  = groundwater route score,  $S_{SW}$  = surface water route score, and  $S_A$  = air route score).
- o  $S_{FE}$  reflects the potential for harm from substances that can explode or cause fires.
- o  $S_{DC}$  reflects the potential for harm from direct contact with hazardous substances at the facility (i.e., no migration need be involved).

The preliminary HRS score was:

$S_M = 0$                     ( $S_{GW} = 0$ ;  $S_{SW} = 0$ ;  $S_A = 0$ )  
 $S_{FE} = \text{not scored}$   
 $S_{DC} = 0$



## 2. PURPOSE

This Phase I investigation was conducted under contract to the New York State Department of Environmental Conservation (NYSDEC) Superfund Program. The purpose of this investigation was to provide a preliminary evaluation of the potential environmental or public health hazards associated with past disposal activities at the Carborundum Building 82 disposal site. This initial investigation consisted of a detailed file review of available information and a site inspection. This evaluation includes both a narrative description and preliminary HRS score. The investigation at this site focused on the portion of the site where miscellaneous wastes were reportedly stored during the 1970s and perhaps earlier. Based on this initial evaluation, a Phase II investigation is proposed to better assess the potential hazards posed by the industrial wastes disposed of on the site.



### 3. SCOPE OF WORK

The Phase I effort involved:

- The review of all available information from state, municipal, and private files;
- Interviews with individuals knowledgeable of the site; and
- A physical inspection of the site.

State files reviewed were maintained by the NYSDEC Region 9 in Buffalo, New York. County files reviewed were maintained by Niagara County Department of Health. Private files reviewed were maintained by Electro Minerals (U.S.), Inc., at their Buffalo Avenue, Niagara Falls, New York facility.

Mr. Ahmed Tayyebi at the NYSDEC Region 9 office in Buffalo, New York was contacted concerning information contained in the state file on this site. He referred E & E personnel to Mr. Michael Hopkins of Niagara County Health Department for information. Messrs. Peter Beuchi and Martin Doster from the Region 9 office of NYSDEC were also contacted, and they provided information regarding groundwater wells and soil borings in the vicinity of this site.

Mr. Michael Hopkins, Niagara County Health Department, was contacted in person on May 1, 1987 to discuss information maintained in the county files. Mr. Hopkins informed E & E personnel that the

county had no direct involvement with the site since it was on industrial property away from drinking water or residential areas.

Ms. Patricia K. Haynes of Electro Minerals (U.S.), Inc., was contacted in person on June 24, 1987 to furnish background information and to accompany E & E personnel on a site inspection. She furnished E & E personnel with a site map, as well as background information on site history and ongoing processes at the site. Records of soil borings by Thomsen Associates from 1984 were also made available.

A site inspection was conducted by E & E personnel on June 24, 1987. No samples were collected by E & E although monitoring of air quality was performed using a HNu photoionizing organic vapor detector. Photographs were taken and are included in Appendix A. A physical inspection of the site and review of pertinent USGS 7.5-minute topographic maps were completed. A summary of agencies contacted, along with contact persons and addresses, is presented in Table 3-1.



Table 3-1

SOURCES CONTACTED FOR THE NYSDEC PHASE I  
INVESTIGATION AT CARBORUNDUM BUILDING 82

- 
- o New York State Department of Environmental Conservation,  
Region 9  
600 Delaware Avenue, Buffalo, New York 14202  
Telephone Number: (716) 847-4585
    - Division of Solid Hazardous Waste  
Contact: Lawrence Clare, Ahmed Tayyebi, Peter Beuchi, and  
Martin Doster  
Date Contacted: May 8, 1987  
Information: Groundwater use; analytical results.
    - Division of Regulatory Affairs  
Contact: Paul Elsmann  
Date Contacted: May 8, 1987, and June 2, 1987  
Information: Permits; wetlands information.
    - Division of Environmental Enforcement  
Contact: Joann Gould  
Date Contacted: May 6, 1987  
Information: Enforcement actions.
    - Division of Water  
Contact: Rebecca Anderson  
Date Contacted: June 2, 1987  
Information: Floodplain locations.
    - Bureau of Wildlife  
Contact: James R. Snider  
Date Contacted: June 2, 1987  
Information: Critical habitat locations.
  - o New York State Department of Health  
Corning Tower  
The Governor Nelson A. Rockefeller  
Empire State Plaza  
Albany, New York 12237  
Telephone Number: (518) 458-6310  
Contact: Lani Rafferty  
Date Contacted: April 5, 6, 1989  
Information: File search for site history, correspondence,  
background information.
  - o New York State Department of Health  
Regional Toxic Program Office  
584 Delaware Avenue  
Buffalo, New York 14202  
Contact: Linda Rusin and Cameron O'Connor  
Telephone Number: (716) 847-4365  
Dates Contacted: May 5 and June 4, 1987; and April 13, 1989  
Information: Contact with NYSDOH on May 5, 1987, indicated  
that files were being transferred from Albany to Buffalo, the  
files were not accessible. Further correspondence in June  
1987 indicates that the office was newly established and file  
information was extremely limited; therefore, the county  
health departments were visited in lieu of NYSDOH. NYSDOH  
files were searched April 13, 1989.
-

Table 3-1 (Cont.)

- 
- o Niagara County Health Department  
10th and East Falls Street, Niagara Falls, New York, 14302  
Telephone Number: (716) 284-3128  
Contact: Michael Hopkins  
Dates Contacted: May 1, 1987, and May 5, 1987  
Information: Groundwater usage.
  - o Electro Minerals (U.S.), Inc.  
Buffalo Avenue, Niagara Falls, New York 14302  
Telephone Number: (716) 278-2563  
Contact: Patricia K. Haynes  
Date Contacted: June 24, 1987  
Information: Site history; site maps; background information.
-



## 4. SITE ASSESSMENT

### 4.1 SITE HISTORY

The Carborundum Building 82 waste storage area was used for the storage of sand, fly ash, fire brick, dust collector fines, kiln furniture, wood, grinding wheels, and other industrial scrap before transport to a proper disposal facility. This area is no longer used to store waste, and waste was transported from the site and disposed of by Modern Disposal Services, Inc. in 1985. The site has been graded and covered with crushed stone. Visual inspection revealed some evidence of firebrick and sand in the former storage area. No samples were taken from this area.

Electro Minerals (U.S.), Inc. was formerly owned by Carborundum Corporation, which, in turn, was owned by Standard Oil (SOHIO). Prior to being owned by SOHIO, Carborundum was owned by Kennecott Copper. Electro Minerals (U.S.), Inc., a subsidiary of Washington Mills Abrasives, manufactures abrasive grains from silicon carbide, premium aluminum oxide, graphite, and boric acid. Processes include crushing, sorting, bagging, and arc furnace processing. Waste streams generated include toluene, acetone, methanol, and sulfuric acid used in grain rinsing. Spent lubricating oils, greases and degreasing agents are either recycled by Safety-Kleen, a subcontractor, or removed by SCA (presently Chemical Waste Management) a few times each year. The sulfuric acid process was not in operation at the time of the inspection.

## 4.2 SITE TOPOGRAPHY

This site is located on the Ontario Plain approximately 1.75 miles east of the American Falls in the City of Niagara Falls, New York. The Falls represents the greatest topographic relief in the area, dropping approximately 210 feet from the Upper Niagara River to the Lower Gorge. The site is south of the Niagara Escarpment in an area of low relief which slopes toward the Niagara River located approximately 600 feet south of the site. Site elevation is approximately 570 feet above sea level. The site is not located in a floodplain and the nearest wetland is approximately 4.75 miles to the east. This site is located in the highly industrialized area in the southern portion of the City of Niagara Falls. This area contains several chemical industries.

## 4.3 SITE HYDROLOGY

### 4.3.1 Regional Geology and Hydrology

The geology of the Niagara Falls area is well understood because of its simplicity and because of the excellent exposures of bedrock along the Niagara River gorge and the Niagara escarpment.

The overburden in the Niagara Falls area is relatively thin. Three types of unconsolidated deposits are present. The lowermost is glacial till and regolith, an unsorted mixture of boulders, clay, and sand deposited by glaciers, which directly overlies the bedrock. This is covered by clays, silts, and fine sands of lacustrine origin. These are the surface soils throughout most of the region. In isolated spots, sand and gravel deposits are found above the lacustrine soils. These were deposited by glacial melt streams and by wave action of the larger ancestors of the Great Lakes.

The bedrock in the Niagara Falls area consists of nearly flat-lying sedimentary rocks, including dolomite, shale, limestone, and sandstone units. The several beds of bedrock slope southward approximately 30 feet per mile.

The entire region south of the Niagara escarpment, and extending almost to Erie County, is directly underlain by the Lockport Dolomite. The Clinton and Albion groups underlie the Lockport but crop out only along the escarpment and in the gorge of the Niagara River.

These units are underlain by the Queenston shale. This unit is the uppermost bedrock unit under the plain north of the escarpment.

Groundwater in the Niagara Falls area occurs in both the unconsolidated deposits and in the bedrock. The bedrock, specifically the Lockport Dolostone, is, however, the principal source of groundwater in the Lockport area. Three types of bedrock openings contain groundwater: bedding joints, vertical joints, and solution cavities.

The bedding joints, which transmit most of the water in the Lockport, are fractures along prominent bedding planes which have been widened up to 1/8 inch by solution of the rocks. These joints extend several miles thus constituting effective water conduits.

The vertical joints are generally too short and sparse to account for significant groundwater storage and transmission, except in the top 10 to 25 feet of bedrock. Solution cavities, formed when gypsum is dissolved, are also not important components of the aquifer. Although they increase the storage capacity of the aquifer, they are isolated and do not contribute to groundwater transmission.

Two distinct sets of groundwater conditions exist in the Lockport Dolostone. The first is the upper 10 to 25 feet of the bedrock, which is highly fractured resulting in moderate permeabilities. In some areas in the region, a confining layer of clay above this zone can produce artesian groundwater conditions. The second class of groundwater conditions is found deeper in the bedrock, where at least seven different permeable zones have been identified. These zones are surrounded by impermeable bedrock, and it is not likely that they are hydraulically connected (Johnston 1964).

#### 4.3.2 Site Hydrogeology

There are no groundwater wells on site, although some specific information on hydrogeology is available. Soil borings from 1984 (Thomsen Associates 1984) indicate the Lockport Dolostone is at a depth of 10 to 24 feet below ground level. Free standing water was encountered between 7 and 12 feet in several of the soil borings. Surface material consists of crushed stone, sand, slag, carbon, and cinder fill. Silts and clays underlie the fill material and overlie a fractured rock zone before competent bedrock is reached. Groundwater is most commonly encountered just above this fractured rock zone.

The silts and clays may impede downward flow of groundwater, but there is insufficient data to adequately assess hydraulic gradients and flow patterns at this site.

Groundwater flow is expected to be northeast toward an industrial pumping well located at the Olin Chemical plant, less than 0.5 mile away. This well is utilized to provide a source of water for a cooling process at a nearby chemical plant. However, some groundwater flow would also be expected to be south toward the Niagara River.

To determine more accurately the site hydrogeology, extensive subsurface investigations would have to be conducted, including installation of monitoring wells. This would provide more precise knowledge of groundwater gradients and flow patterns, and help to identify potential waste migration pathways.

For purposes of HRS scoring, the Lockport Dolostone is considered the aquifer of concern. This aquifer is expected to be encountered from 10 to 24 feet below land surface, and to be approximately 80 to 150 feet thick. A regolith zone is expected to be encountered before competent bedrock.

#### 4.3.3 Hydraulic Connections

The Lockport can be divided into two zones on the basis of water-transmitting properties. The upper 10 to 25 feet of rock is a moderately permeable zone that contains relatively abundant bedding planes and vertical joints enlarged by dissolution of dolomite and abundant solution cavities left by dissolution of gypsum. These zones are more than likely hydraulically connected. The remainder of the formation contains low to moderately permeable bedding planes of which as many as seven may be major water-bearing zones that are surrounded by fine-grained crystalline dolomite. These zones are probably not hydraulically connected.

#### 4.4 SITE CONTAMINATION

It has not been determined if hazardous waste has been disposed or stored at this site. It is known that hazardous materials were used for various processes at the facility, and that wastes were stored on site. The storage area was not lined, and any contaminants

that may have been present could have migrated to the groundwater and eventually into the Niagara River. No sampling for hazardous wastes is known to have taken place in the former waste storage area. Air monitoring with a photo ionization detector was performed by E & E while on site, and no readings above background were noted.

In November 1984, Earth Dimensions, Inc., collected split-spoon soil samples from five locations along Adams Avenue on the Electro Minerals (U.S.) property prior to the installation of the Adams Avenue storm sewer. Analysis of several of these samples indicated the presence of detectable levels of volatile organics, phenols, and total mercury (Advanced Environmental Systems, Inc. 1984). These results, although not attributable directly to the former storage area, show the potential for the presence of hazardous waste at the site. Soil analyses and a map showing sample location are presented in Appendix C to this report.







## 5. PRELIMINARY APPLICATION OF THE HAZARD RANKING SYSTEM

### 5.1 NARRATIVE SUMMARY

The Carborundum Building 82, now owned by Electro Minerals (U.S.), Inc., is located on an approximately 40-acre site in the City of Niagara Falls, Niagara County, New York (see Figure 5-1). A portion of this property was at one time used to temporarily store sand, fly ash, fire brick, dust collector fines, kiln furniture, wood, grinding wheels, fiber, aluminum-silica shot, and metal scrap prior to proper disposal. The property was used in this fashion for an unknown period of time ending in 1979. The waste was removed in 1985 and properly disposed, and the site was graded over with fill.


It has not been determined if hazardous wastes were stored at this site; however, the potential exists, since toluene, acetone, methanol, motor fuels, and lubricating oils are used on site.

The site is located on the Ontario plain, south of the Niagara escarpment, in an area of low relief which slopes toward the Niagara River. The Niagara River is located approximately 600 feet south of the site. The site elevation is approximately 570 feet above sea level.

The site is located in a highly industrialized area in the southern portion of the City of Niagara Falls. This area contains several chemical industries.

The aquifer of concern is the Lockport dolomite which is expected to be encountered from 10 to 24 feet below land surface and is approximately 80 to 150 feet thick.





SOURCE: U.S.G.S. 7.5 Minute Series (Topographic) Quadrangle, Niagara Falls, N.Y.-Ont., 1980.

Figure 5-1 LOCATION MAP



FIGURE 1

HRS COVER SHEET

Facility Name: Electro Minerals (U.S.), Inc., formerly Carborundum Building 82

Location: Buffalo Avenue, Niagara Falls, New York

EPA Region: II

Person(s) In Charge of Facility: Patricia A. Haynes

Name of Reviewer: Dennis Sutton

Date: 7/15/87

General Description of the Facility:

(For example: landfill, surface impoundment, pile, container; types of hazardous substances; location of the facility; contamination route of major concern; types of information needed for rating; agency action; etc.)

This property was formerly owned by Carborundum Corp., Kennecott Copper, and Standard Oil Co., and a portion of the site was used for disposal of sand, fly ash, fire brick, dust collector fines, kiln furniture, wood, carborundum wheels, aluminum-silica shot, fiber and metal scrap. This was placed directly on the ground surface and has since been removed.

The site has been leveled and filled. No wells are known on site and the Niagara River is approximately 600 feet to the south. Due to the proximity of the Niagara River, contamination routes of concern include both surface and groundwater.

Scores:  $S_M = 0$  ( $S_{gw} = 0$   $S_{sw} = 0$   $S_a = 0$  )

$S_{FE} = \text{Not scored}$

$S_{DC} = 0$

Ground Water Route Work Sheet						
Rating Factor	Assigned Value (Circle One)	Multi- plier	Score	Max. Score	Ref. (Section)	
<b>1</b> Observed Release	(0) 45	1	0	45	3.1	
If observed release is given a score of 45, proceed to line <b>4</b> . If observed release is given a score of 0, proceed to line <b>2</b> .						
<b>2</b> Route Characteristics					3.2	
Depth to Aquifer of Concern	0 1 2 (3)	2	6	6		
Net Precipitation	0 (1) 2 3	1	1	3		
Permeability of the Unsaturated Zone	0 (1) 2 3	1	1	3		
Physical State	0 1 (2) 3	1	2	3		
Total Route Characteristics Score			10	15		
<b>3</b> Containment	0 1 2 (3)	1	3	3	3.3	
<b>4</b> Waste Characteristics					3.4	
Toxicity/Persistence	(0) 3 6 9 12 15 18	1	0	18		
Hazardous Waste Quantity	(0) 1 2 3 4 5 6 7 8	1	0	8		
Total Waste Characteristics Score			0	26		
<b>5</b> Targets					3.5	
Ground Water Use	0 (1) 2 3	3	3	9		
Distance to Nearest Well/Population Served	(0) 4 6 8 10 12 16 18 20 24 30 32 35 40	1	0	40		
Total Targets Score			3	49		
<b>6</b> If line <b>1</b> is 45, multiply <b>1</b> x <b>4</b> x <b>5</b> If line <b>1</b> is 0, multiply <b>2</b> x <b>3</b> x <b>4</b> x <b>5</b>			0	57,330		
<b>7</b> Divide line <b>6</b> by 57,330 and multiply by 100			S <sub>gw</sub> = 0			

**FIGURE 2**  
**GROUND WATER ROUTE WORK SHEET**



Surface Water Route Work Sheet						
Rating Factor	Assigned Value (Circle One)	Multi-plier	Score	Max. Score	Ref. (Section)	
<b>[1] Observed Release</b>	(0) 45	1	0	45	4.1	
If observed release is given a value of 45, proceed to line <b>[4]</b> . If observed release is given a value of 0, proceed to line <b>[2]</b> .						
<b>[2] Route Characteristics</b>					4.2	
Facility Slope and Intervening Terrain	(0) 1 2 3	1	1	3		
1-yr. 24-hr. Rainfall	0 1 (2) 3	1	2	3		
Distance to Nearest Surface Water	0 1 2 (3)	2	6	6		
Physical State	0 1 (2) 3	1	2	3		
<b>Total Route Characteristics Score</b>			11	15		
<b>[3] Containment</b>	0 1 2 (3)	1	3	3	4.3	
<b>[4] Waste Characteristics</b>					4.4	
Toxicity/Persistence	(0) 3 6 9 12 15 18	1	0	18		
Hazardous Waste Quantity	(0) 1 2 3 4 5 6 7 8	1	0	8		
<b>Total Waste Characteristics Score</b>			0	26		
<b>[5] Targets</b>					4.5	
Surface Water Use	0 1 (2) 3	3	6	9		
Distance to a Sensitive Environment	(0) 1 2 3	2	0	6		
Population Served/Distance to Water Intake Downstream	(0) 4 6 8 10 12 16 18 20 24 30 32 35 40	1	0	40		
<b>Total Targets Score</b>			6	55		
<b>[6]</b> If line <b>[1]</b> is 45, multiply <b>[1]</b> x <b>[4]</b> x <b>[5]</b> If line <b>[1]</b> is 0, multiply <b>[2]</b> x <b>[3]</b> x <b>[4]</b> x <b>[5]</b>			0	64,350		
<b>[7] Divide line [6] by 64,350 and multiply by 100</b>			<b>S<sub>sw</sub> = 0</b>			

**FIGURE 7**  
**SURFACE WATER ROUTE WORK SHEET**

Air Route Work Sheet						
Rating Factor	Assigned Value (Circle One)	Multi-plier	Score	Max. Score	Ref. (Section)	
<b>[1]</b> Observed Release	<b>(0)</b> 45	1	0	45	5.1	
Date and Location:						
Sampling Protocol:						
If line <b>[1]</b> is 0, the $S_a = 0$ . Enter on line <b>[5]</b> . If line <b>[1]</b> is 45, then proceed to line <b>[2]</b> .						
<b>[2]</b> Waste Characteristics					5.2	
Reactivity and Incompatibility	0 1 2 3	1		3		
Toxicity	0 1 2 3	3		9		
Hazardous Waste Quantity	0 1 2 3 4 5 6 7 8	1		8		
Total Waste Characteristics Score				20		
<b>[3]</b> Targets					5.3	
Population Within 4-Mile Radius	0 9 12 15 18 21 24 27 30	1		30		
Distance to Sensitive Environment	0 1 2 3	2		6		
Land Use	0 1 2 3	1		3		
Total Targets Score				39		
<b>[4]</b> Multiply <b>[1]</b> x <b>[2]</b> x <b>[3]</b>				35,100		
<b>[5]</b> Divide line <b>[4]</b> by 35,100 and multiply by 100			$S_a = 0$			

**FIGURE 9**  
**AIR ROUTE WORK SHEET**

	<b>s</b>	<b>s<sup>2</sup></b>
<b>Groundwater Route Score (S<sub>gw</sub>)</b>	0	0
<b>Surface Water Route Score (S<sub>sw</sub>)</b>	0	0
<b>Air Route Score (S<sub>a</sub>)</b>	0	0
$s_{gw}^2 + s_{sw}^2 + s_a^2$		0
$\sqrt{s_{gw}^2 + s_{sw}^2 + s_a^2}$		0
$\sqrt{s_{gw}^2 + s_{sw}^2 + s_a^2} / 1.73 = S_M =$		0

**FIGURE 10**  
**WORKSHEET FOR COMPUTING S<sub>M</sub>**

Fire and Explosion Work Sheet						
Rating Factor	Assigned Value (Circle One)	Multi-plier	Score	Max. Score	Ref. (Section)	
<b>1</b> Containment	1                      3	1		3	7.1	
<b>2</b> Waste Characteristics					7.2	
Direct Evidence	0                      3	1		3		
Ignitability	0 1 2 3	1		3		
Reactivity	0 1 2 3	1		3		
Incompatibility	0 1 2 3	1		3		
Hazardous Waste Quantity	0 1 2 3 4 5 6 7 8	1		8		
Total Waste Characteristics Score				20		
<b>3</b> Targets					7.3	
Distance to Nearest Population	0 1 2 3 4 5	1		5		
Distance to Nearest Building	0 1 2 3	1		3		
Distance to Sensitive Environment	0 1 2 3	1		3		
Land Use	0 1 2 3	1		3		
Population Within 2-Mile Radius	0 1 2 3 4 5	1		5		
Buildings Within 2-Mile Radius	0 1 2 3 4 5	1		5		
Total Targets Score				24		
<b>4</b> Multiply <b>1</b> x <b>2</b> x <b>3</b>				1,440		
<b>5</b> Divide line <b>4</b> by 1,440 and multiply by 100			SFE = Not Scored			

**FIGURE 11  
FIRE AND EXPLOSION WORK SHEET**

Direct Contact Work Sheet						
Rating Factor	Assigned Value (Circle One)	Multi- plier	Score	Max. Score	Ref. (Section)	
<b>1</b> Observed Incident	<b>0</b> 45	1	0	45	8.1	
If line <b>1</b> is 45, proceed to line <b>4</b> If line <b>1</b> is 0, proceed to line <b>2</b>						
<b>2</b> Accessibility	<b>0</b> 1 2 3	1	0	3	8.2	
<b>3</b> Containment	<b>0</b> 15	1	0	15	8.3	
<b>4</b> Waste Characteristics Toxicity	<b>0</b> 1 2 3	5	0	15	8.4	
<b>5</b> Targets					8.5	
Population Within a 1-Mile Radius	0 1 2 3 4 <b>5</b>	4	20	20		
Distance to a Critical Habitat	<b>0</b> 1 2 3.	4	0	12		
Total Targets Score			20	32		
<b>6</b> If line <b>1</b> is 45, multiply <b>1</b> x <b>4</b> x <b>5</b> If line <b>1</b> is 0, multiply <b>2</b> x <b>3</b> x <b>4</b> x <b>5</b>			0	21,600		
<b>7</b> Divide line <b>6</b> by 21,600 and multiply by 100			SDC = 0			

**FIGURE 12**  
**DIRECT CONTACT WORK SHEET**



---

---

DOCUMENTATION RECORDS  
FOR  
HAZARD RANKING SYSTEM

---

---

Instructions: As briefly as possible summarize the information you used to assign the score for each factor (e.g., "Waste quantity = 4,230 drums plus 800 cubic yards of sludges"). The source of information should be provided for each entry and should be a bibliographic-type reference. Include the location of the document.

Facility Name: Electro Minerals (U.S.), formerly Carborundum Building 82

Location: Buffalo Avenue, Niagara Falls, New York

Date Scored: 7/14/87

Person Scoring: D. Sutton

Primary Source(s) of Information (e.g., EPA region, state, FIT, etc.):

New York State Department of Environmental Conservation, Region 9, Buffalo, New York

Factors Not Scored Due to Insufficient Information:

Fire and explosion score was not computed as this site has not been declared a fire hazard by a fire marshal.  
Ref. No. 10

Comments or Qualifications:

It has not been determined if hazardous wastes were ever disposed or stored on site. Waste characteristics and waste quantity, if any, are unknown. Site was scored on the basis of available information.

---

---

GROUNDWATER ROUTE

---

---

1. OBSERVED RELEASE

Contaminants detected (3 maximum):

None observed

Rationale for attributing the contaminants to the facility:

NA

\* \* \*

2. ROUTE CHARACTERISTICS

Depth to Aquifer of Concern

Name/description of aquifer(s) of concern:

Lockport Dolostone: massive- to thin-bedded dolostone with fracture zones and solution cavities  
Ref. No. 3

Depth(s) from the ground surface to the highest seasonal level of the saturated zone [water table(s)] of the aquifer of concern:

Approximately 9 feet  
Ref. No. 9

Depth from the ground surface to the lowest point of waste disposal/storage:

Unknown

Net Precipitation

Mean annual or seasonal precipitation (list months for seasonal):

31 in/yr.  
Ref. No. 1

Mean annual lake or seasonal evaporation (list months for seasonal):

27 in/yr  
Ref. No. 1

Net precipitation (subtract the above figures):

4 in/yr  
Ref. No. 1



---

Permeability of Unsaturated Zone

Soil type in unsaturated zone:

Silty clay, silty clay loam  
Ref. No. 4

Permeability associated with soil type:

$10^{-5}$  -  $10^{-7}$  cm/sec  
Ref. No. 1

Physical State

Physical state of substances at time of disposal (or at present time for generated gases):

Solid, unconsolidated and fine material (sand, dust collector fines)  
Ref. Nos. 6, 7, 1

\* \* \*

3. CONTAINMENT

Containment

Method(s) of waste or leachate containment evaluated:

None noted - waste material placed on land surface  
Ref. Nos. 6, 7

Method with highest score:

Piles  
No liner, piles uncovered  
Ref. No. 1

4. WASTE CHARACTERISTICS

Toxicity and Persistence

Compound(s) evaluated:

None evaluated

Compound with highest score:

Unknown

Hazardous Waste Quantity

Total quantity of hazardous substances at the facility, excluding those with a containment score of 0 (give a reasonable estimate even if quantity is above maximum):

Unknown

Basis of estimating and/or computing waste quantity:

NA

recycled paper

ecology and environment

---

5. TARGETS

Groundwater Use

Use(s) of aquifer(s) of concern within a 3-mile radius of the facility:

Industrial - non-contact cooling water  
Ref. Nos. 11, 5

Distance to Nearest Well

Location of nearest well drawing from aquifer of concern or occupied building not served by a public water supply:

Located on Olin Chemical Plant property less than 1/2 mile away  
Ref. Nos. 11, 5

Distance to above well or building:

4/10 mile  
Ref. Nos. 11, 2, 5

Population Served by Groundwater Wells Within a 3-Mile Radius

Identified water-supply well(s) drawing from aquifer(s) of concern within a 3-mile radius and populations served by each:

NA

Computation of land area irrigated by supply well(s) drawing from aquifer(s) of concern within a 3-mile radius, and conversion to population (1.5 people per acre):

NA

Total population served by groundwater within a 3-mile radius:

NA

---

---

---

S U R F A C E   W A T E R   R O U T E

---

---

1. OBSERVED RELEASE

Contaminants detected in surface water at the facility or downhill from it (5 maximum):

None observed

Rationale for attributing the contaminants to the facility:

NA

\* \* \*

2. ROUTE CHARACTERISTICS

Facility Slope and Intervening Terrain

Average slope of facility in percent:

0.1%  
Ref. No. 2

Name/description of nearest downslope surface water:

Niagara River  
Ref. No. 2

Average slope of terrain between facility and above-cited surface water body in percent:

0.1%  
Ref. No. 2

Is the facility located either totally or partially in surface water?

No  
Ref. No. 2

Is the facility completely surrounded by areas of higher elevation?

No  
Ref. No. 2

1-Year 24-Hour Rainfall in inches

2.5  
Ref. No. 1

Distance to Nearest Downslope Surface Water

600 feet  
Ref. No. 2

Physical State of Waste

Solid, unconsolidated and fine material (sand, dust collector fines)  
Ref. Nos. 6, 7

\* \* \*

3. CONTAINMENT

Containment

Method(s) of waste or leachate containment evaluated:

None evaluated

Method with highest score:

Piles

No liner, piles uncovered

Ref. Nos. 6, 7, 1

4. WASTE CHARACTERISTICS

Toxicity and Persistence

Compound(s) evaluated:

None evaluated

Compound with highest score:

NA

Hazardous Waste Quantity

Total quantity of hazardous substances at the facility, excluding those with a containment score of 0 (give a reasonable estimate even if quantity is above maximum):

No known hazardous waste on site

Basis of estimating and/or computing waste quantity:

NA

\* \* \*

5. TARGETS

Surface Water Use

Use(s) of surface water within 3 miles downstream of the hazardous substance:

Commercial or industrial and recreational

Ref. Nos. 11, 2, 13

Is there tidal influence?

No  
Ref. No. 2

Distance to a Sensitive Environment

Distance to 5-acre (minimum) coastal wetland, if 2 miles or less:

NA  
Ref. No. 2

Distance to 5-acre (minimum) fresh-water wetland, if 1 mile or less:

NA  
Ref. Nos. 2, 12

Distance to critical habitat of an endangered species or national wildlife refuge, if 1 mile or less:

NA  
Ref. Nos. 2, 13

Population Served by Surface Water

Location(s) of water-supply intake(s) within 3 miles (free-flowing bodies) or 1 mile (static water bodies) downstream of the hazardous substance and population served by each intake:

NA  
Ref. Nos. 10, 2

Computation of land area irrigated by above-cited intake(s) and conversion to population (1.5 people per acre):

NA

Total population served:

0  
Ref. No. 10

Name/description of nearest of above water bodies:

NA

Distance to above-cited intakes, measured in stream miles:

NA

---

---

A I R   R O U T E

---

---

1. OBSERVED RELEASE

Contaminants detected:

None observed

Date and location of detection of contaminants:

NA

Methods used to detect the contaminants:

NA

Rationale for attributing the contaminants to the site:

NA

\* \* \*

2. WASTE CHARACTERISTICS

Reactivity and Incompatibility

Most reactive compound:

NA

Most incompatible pair of compounds:

NA

Toxicity

Most toxic compound:

NA

Hazardous Waste Quantity

Total quantity of hazardous waste:

NA

Basis of estimating and/or computing waste quantity:

NA

\* \* \*

### 3. TARGETS

#### Population Within 4-Mile Radius

Circle radius used, give population, and indicate how determined:

0 to 4 ml \ 0 to 1 ml 0 to 1/2 ml 0 to 1/4 ml

18,758  
Ref. No. 8

#### Distance to a Sensitive Environment

Distance to 5-acre (minimum) coastal wetland, if 2 miles or less:

NA  
Ref. No. 2

Distance to 5-acre (minimum) fresh-water wetland, if 1 mile or less:

NA  
Ref. Nos. 2, 12

Distance to critical habitat of an endangered species, if 1 mile or less: \

NA

#### Land Use

Distance to commercial/industrial area, if 1 mile or less:

100 feet  
Ref. Nos. 2, 7

Distance to national or state park, forest, or wildlife reserve, if 2 miles or less:

1-1/8 miles  
Ref. No. 2

Distance to residential area, if 2 miles or less:

2,500 feet  
Ref. No. 2

Distance to agricultural land in production within past 5 years, if 1 mile or less:

NA  
Ref. No. 2

Distance to prime agricultural land in production within past 5 years, if 2 miles or less:

NA  
Ref. No. 2

Is a historic or landmark site (National Register of Historic Places and National Natural Landmarks) within the view of the site?

No  
Ref. Nos. 2, 7

---

F I R E   A N D   E X P L O S I O N

---

1. CONTAINMENT

Hazardous substances present:

Unknown

Type of containment, if applicable

Unknown

\* \* \*

2. WASTE CHARACTERISTICS

Direct Evidence

Type of instrument and measurements:

NA

Ignitability

Compound used:

NA

Reactivity

Most reactive compound:

NA

Incompatibility

Most incompatible pair of compounds:

NA

Hazardous Waste Quantity

Total quantity of hazardous substances at the facility:

Unknown

Basis of estimating and/or computing waste quantity:

NA

\* \* \*



### 3. TARGETS

#### Distance to Nearest Population

100 feet  
Ref. No. 2

#### Distance to Nearest Building

100 feet  
Ref. No. 2

#### Distance to a Sensitive Environment

##### Distance to wetlands:

NA  
Ref. Nos. 2, 12

##### Distance to critical habitat:

NA  
Ref. No. 13

#### Land Use

##### Distance to commercial/industrial area, if 1 mile or less:

100 feet  
Ref. No. 2

##### Distance to national or state park, forest, or wildlife reserve, if 2 miles or less:

1-1/8 mile  
Ref. No. 2

##### Distance to residential area, if 2 miles or less:

2,500 feet  
Ref. No. 2

##### Distance to agricultural land in production within past 5 years, if 1 mile or less:

NA  
Ref. No. 2

##### Distance to prime agricultural land in production within past 5 years, if 2 miles or less:

NA  
Ref. No. 2

##### Is a historic or landmark site (National Register of Historic Places and National Natural Landmarks) within the view of the site?

No  
Ref. No. 2

#### Population Within 2-Mile Radius

39,797  
Ref. No. 8

#### Buildings Within 2-Mile Radius

17,710  
Ref. No. 8

---

DIRECT CONTACT

---

1. OBSERVED INCIDENT

Date, location, and pertinent details of incident:

None observed

\* \* \*

2. ACCESSIBILITY

Describe type of barrier(s):

Site is fenced  
Plant facility guarded  
Ref. Nos. 6, 7

\* \* \*

3. CONTAINMENT

Type of containment, if applicable:

No containment - waste placed on land surface  
Ref. No. 6, 7

\* \* \*

4. WASTE CHARACTERISTICS

Toxicity

Compounds evaluated:

None evaluated

Compound with highest score:

NA

\* \* \*

5. TARGETS

Population within one-mile radius

18,758  
Ref. No. 8

Distance to critical habitat (of endangered species)

NA

## REFERENCES

If the entire reference is not available for public review in the EPA regional files on this site, indicate where the reference may be found:

Reference Number	Description of the Reference
1	Barrett, K.W., S.S. Chang, S.A. Hans, A.M. Platt, 1982, <u>Uncontrolled Hazardous Waste Site Ranking System; A Users Manual</u> . Document location: Ecology and Environment, Inc., Buffalo, New York.
2	USGS 7.5 Minute Topographical Map, 1980, Niagara Falls, N.Y. quadrangle. Document location: Ecology and Environment, Inc., Buffalo, New York.
3	Johnson, Richard H., 1964, <u>Groundwater in the Niagara Falls Area, New York</u> , State of New York Conservation Department, Water Resource Commission, Bulletin GW-53. Document location: Ecology and Environment, Inc., Buffalo, New York.
4	Higgins, B.A., P.S. Puglia, R.P. Leonard, T.D. Yoakun, W.A. Wirtz, 1972, <u>Soil Survey of Niagara County, New York</u> , USDA Soil Conservation Service. Document location: Ecology and Environment, Inc., Buffalo, New York.
5	Koszaka, E.J., J.E. Paschal, Jr., T.S. Miller, P.B. Duron, 1985, <u>Preliminary Evaluation of Chemical Migration to Groundwater and the Niagara River from Selected Waste-Disposal Sites</u> ; EPA Bulletin. Document location: Ecology and Environment, Inc., Buffalo, New York.
6	Patricia K. Haynes, Manager, Environmental Health and Safety, Electro Minerals (U.S.), June 1987; personal communication. Document location: Ecology and Environment, Inc., Buffalo, New York.
7	Ecology and Environment, Inc., June 12, 1987, site inspection log book and photo log. Document location: Ecology and Environment, Inc., Buffalo, New York.
8	Graphical Exposure Modeling System, June 1987, Environmental Protection Agency, Office of Pesticides and Toxic Substances, Federal Plaza, New York, New York. Information location: Ecology and Environment, Inc., Buffalo, New York.
9	Miller, T.S., W.M. Kappel, 1987, <u>The Effect of Niagara Power Project on Groundwater Flow in the Upper Part of the Lockport Dolomite, Niagara Falls Area, New York</u> ; USGS Survey Report 86-4130. Document location: Ecology and Environment, Inc., Buffalo, New York.
10	Hopkins, Michael, June 1987, Niagara County Health Department, Niagara Falls, New York, personal communication. Document location: Ecology and Environment, Inc., Buffalo, New York.
11	Beuchl, Peter, July 1987, New York State Department of Environmental Conservation, Region 9, Buffalo, New York, personal communication. Document location: Ecology and Environment, Inc., Buffalo, New York.
12	New York State Wetlands Maps, New York State Department of Environmental Conservation. Document location: Region 9, Buffalo, New York.
13	Snider, James, June 1987, Wildlife Biologist, New York State Department of Environmental Conservation, Region 9, Buffalo, New York; personal communication. Document location: Ecology and Environment, Inc., Buffalo, New York.
14	<u>New York Atlas of Community Water System Sources</u> , 1982, New York Department of Health, Division of Environmental Protection, Bureau of Public Water Supply Protection. Document location: Ecology and Environment, Buffalo, New York.
15	Murtagh, William, 1976, <u>The National Register of Historic Places</u> , U.S. Department of the Interior, National Park Service, Washington, D.C. Document location: Ecology and Environment, Inc., Buffalo, New York.

REFERENCE NO. 1

# Uncontrolled Hazardous Waste Site Ranking System

## A Users Manual

Kris W. Barrett  
S. Steven Chang  
Stuart A. Haus  
Andrew M. Platt

August 1982

MTR-82W111

SPONSOR:  
U.S. Environmental Protection Agency  
CONTRACT NO.:  
68-01-6278



The MITRE Corporation  
Metrek Division  
1820 Dolley Madison Boulevard  
McLean, Virginia 22102

5-24

REFERENCE NO. 2

To convert feet to meters  
multiply by .3048

To convert meters to feet  
multiply by 3.2808



1980

5-26

recycled paper

ecology and environment

REFERENCE NO. 3



# GROUND WATER IN THE NIAGARA FALLS AREA, NEW YORK

With Emphasis on the  
Water-Bearing Characteristics of the Bedrock

BY  
RICHARD H. JOHNSTON  
GEOLOGIST  
U.S. GEOLOGICAL SURVEY

RECEIVED

SEP 5 1985

ECOLOGY & ENVIRONMENT

STATE OF NEW YORK  
CONSERVATION DEPARTMENT  
WATER RESOURCES COMMISSION



BULLETIN GW-53  
1964

because studies made on the Lockport may contribute to a better understanding of the occurrence of ground water in bedrock generally. The Queenston Shale and Clinton and Albion Groups are poor aquifers in comparison to the Lockport Dolomite, and less is known of their water-bearing characteristics.

## LOCKPORT DOLOMITE

### Character and extent

The Lockport Dolomite is the uppermost bedrock formation in about one-third of the Niagara Falls area. Its outcrop area extends from the Niagara escarpment on the north to the southern boundary of the area covered by this report except in two small areas that may be underlain by the Salina Group. (See plate 3.) One of these areas is in the vicinity of the hamlet of Nashville and the other is in the extreme southeast corner. Because of a lack of rock outcrops in these areas the position of the contact between the Lockport and the Salina cannot be accurately determined. However, the Salina Group is not discussed as a separate water-bearing unit in this report because at most only a few feet of it occurs in the area. Continuous exposures of the Lockport are found along the gorge of the Niagara River and along the Niagara escarpment. The formation is about 150 feet thick in the southern part of the area but has been eroded to a thickness of only about 20 feet along the escarpment (pl. 2). The excellent exposures at Niagara Falls (fig. 5), where the Lockport forms the lip of the Falls, are shown in many geology textbooks as a classic example of flat-lying sedimentary rocks. Throughout most of the remainder of the area, which is relatively flat, the Lockport is concealed by a thin cover of glacial deposits.

As its name implies, the Lockport Dolomite consists mainly of dolomite; however, the formation also includes thin beds of limestone and shaly dolomite near the base. The Lockport consists of five lithologic types which, from top to bottom, are:

- (a) brownish-gray, coarse- to medium-grained dolomite, locally saccharoidal with thin intervals of curved bedding (algal structures).
- (b) gray to dark-gray, fine-grained dolomite, containing abundant carbonaceous partings.
- (c) tannish-gray, fine-grained dolomite.
- (d) light-gray, coarse-grained limestone containing abundant crinoid fragments (Gasport Limestone Member).
- (e) light-gray shaly dolomite, laminated in part (DeCew Limestone Member of Williams, 1919).

Fisher (1960) divides the Lockport Dolomite into six units based on fossils as well as rock types. An excellent discussion of the stratigraphy of the

Lockport, including measured sections in the Niagara Falls area, is given in the recent thesis by Zenger <sup>1/</sup>.

The detailed breakdowns by Fisher and Zenger, although helpful for geologic mapping and correlating the Lockport with rocks of similar age elsewhere, are not necessary in descriptions of the water-bearing properties of the formation. For this purpose the Lockport is subdivided as follows (figure 5 and table 1): (1) upper and middle parts of the Lockport, and (2) lower part of the Lockport, including the Gasport Limestone Member and DeCew Limestone Member of Williams (1919).

Most of the beds in the Lockport are described as either "thick" (1 foot to 3 feet) or "thin" (1 inch to 1 foot). However, massive beds up to eight feet thick and very thin beds (1/4 to 1 inch) occur within the formation. The bedding is generally straight, but curved bedding occurs in some places in the upper part of the formation. The curved bedding is caused by dome-shaped algal structures called "stromatolites" (Zenger, p. 140). These reefs (bioherms), which occur as lens-like masses up to 50 feet across and 10 to 20 feet thick, contain no bedding.

Gypsum (calcium sulfate) is common in the Lockport, occurring chiefly as small irregularly shaped masses (commonly 1/2 to 5 inches in diameter) and as selenite. Sulfide minerals, particularly sphalerite (zinc sulfide), galena (lead sulfide), and pyrite (iron sulfide) occur as particles disseminated throughout the formation.

#### Water-bearing openings

Types.--Ground-water occurs in the Lockport Dolomite in three types of openings: (1) bedding joints which constitute at least seven important water-bearing zones, (2) vertical joints, and (3) small cavities from which gypsum has been dissolved. Of these, the bedding joints are the most important and transmit nearly all the water moving through the formation. The three types of openings were observed in the dewatered excavations for the conduits of the Niagara Power Project. (See the description of the power project in the Introduction and the location of the conduits in figure 3.) The rock faces along the four-mile length of the conduits provided an unequalled opportunity to study water-bearing openings in the entire stratigraphic thickness of the Lockport and to observe the lateral extent of these openings for a few thousand feet. At the time the observations were made (July - August 1960), approximately one-third of the length of the conduits was available for inspection by the writer.

---

<sup>1/</sup> Zenger, D. H., 1962, Stratigraphy of the Lockport Formation (Silurian) in New York State: Unpublished doctoral thesis, Cornell University.

The bedding joints, which transmit most of the water in the Lockport, are fractures along prominent bedding planes which have been widened very slightly by solution of the rock. These planar openings persist laterally for distances of at least 3 to 4 miles. The separation along individual bedding joints is small (less than 1/8 inch). However, their continuity makes them effective "conduits" for movement of ground water. The large water-transmitting capacity of the bedding joints was shown by the fact that they supplied nearly all the ground-water seepage entering the conduit excavations. The almost continuous lines of seepage from bedding joints was strikingly apparent in the conduits. Figure 7 shows seepage from two bedding joints.

The bedding joints transmitting ground water comprise at least seven distinct water-bearing zones within the Lockport. These water-bearing zones could be traced laterally for distances of 1 to 4 miles. Figure 8 shows the stratigraphic position and part of the lateral extent of the seven zones. The water-bearing zones have been numbered from 1 to 7 from bottom to top. The three sections shown in figure 8 were surveyed by transit and then correlated on the following basis: (1) lithologic similarities, (2) laterally tracing seepage from individual water-bearing zones, and (3) in the case of section A, the distance above the Rochester Shale as shown by core holes. The correlation of water-bearing zone 6 between sections A and B has been changed slightly from an earlier published version (Johnston, 1962, fig. 110.2).

A water-bearing zone may consist of a single open bedding joint (for example zone 4, section C, fig. 8) or it may consist of an interval of rock measuring up to one foot in thickness containing several open bedding joints (zone 7, section A, fig. 8). Where the water-bearing zone consists of several joints, the open joint transmitting most of the water at one locality may "pinch out" laterally and be replaced by another open joint within the same zone elsewhere. For example, at section B (fig. 8) most seepage from water-bearing zone 6 came from a joint at the top of a thin-bedded interval; however, at section A all seepage came from a joint at the bottom of the interval. The opening along one bedding joint thus becomes closed while a parallel opening along an adjacent bedding joint becomes open.

The water-bearing zones occur most commonly within intervals of the Lockport containing thin beds from 1/4 to about 4 inches thick which are directly overlain by thick or massive beds. The thin beds generally contain open vertical joints, and at the intersection of such vertical joints with open bedding joints ground-water seepage is greatest. At a few such points water was observed to squirt from the openings into the conduit excavations in much the same manner as it would from a broken water pipe. It seems likely that open joints occur most commonly in thin-bedded intervals because the greater structural rigidity of the overlying thick or massive beds permits the joints to remain open.

Water-bearing zones occur less commonly within thick-bedded intervals. In such cases all seepage occurs from one distinct bedding joint rather than from several joints. Seepage from zone 4 at section C (fig. 8) came from one prominent bedding joint within an interval of beds averaging one foot in thickness. This bedding joint is open about 1/16 to 1/8 inch locally and appears to transmit as much ground water as any water-bearing zone in the Lockport.



Figure 7.--Seepage from bedding joints in the Lockport Dolomite.  
View is of east wall of conduit number 1,  
looking south from Porter Rd. bridge.  
(Photograph by the Power Authority  
of the State of New York.)

Vertical joints, excluding those mentioned above which are associated with open bedding joints in thin-bedded intervals, are not important water-bearing openings in the Lockport, except within the top few feet of rock. Two prominent sets of vertical joints exist in the Niagara Falls area; one set oriented N. 65° E. and the other N. 30° W. These joints are fractures in the rock which must be widened by solution before they can become effective water-bearing openings. Such widening is apparent in outcrops of the Lockport. For example, open vertical joints are particularly

prominent in the rock cliffs of the Niagara River Gorge and the Niagara escarpment. The width of these joints in many areas exceeds several inches. However, in fresh exposures of the Lockport, such as the conduit excavations, vertical joints are tight and often not apparent to the eye except in the upper few feet of the rock.

Cavities formed by solution of gypsum occur in the Lockport Dolomite. These cavities range in size from 1/16 inch or less to 5 inches but are generally less than one inch in size. The cavities are formed by the dissolving of gypsum by percolating ground water, and there is a complete range in the development of cavities from voids containing no gypsum to pin-point openings in gypsum nodules. The cavities are most abundant in the top 10 to 15 feet of rock but they also occur along water-bearing zones in the lower part of the rock (for example, water-bearing zone 3, section C, fig. 8). In the upper part of the rock, the abundance of cavities locally gives a vuggy appearance to the dolomite.


The cavities in the Lockport resulting from solution of gypsum increase the ability of the Lockport to store water (porosity) but probably have little effect on the water-transmitting ability of the formation. This is because the water-transmitting ability (or permeability) is dependent upon the size of the continuous openings rather than the size of isolated openings. Thus, the relatively thin but continuous bedding joints determine the permeability of the Lockport rather than the larger but isolated cavities resulting from solution of gypsum.

The character and interrelationships of the three types of water-bearing openings described above result in two distinct sets of ground-water conditions in the Lockport Dolomite: (1) a moderately permeable zone at the top of rock, generally 10 to 15 feet thick, characterized by both vertical and bedding joints that have been widened by solution and by gypsum cavities, and (2) the remainder of the formation consisting of seven permeable zones (composed of bedding joints) surrounded by essentially impermeable rock.

Areal extent.--Relatively little is known about the areal extent of the seven water-bearing zones in the Lockport Dolomite, except as observed in the conduits (fig. 8). Many of the individual bedding joints tend to "pinch out" laterally, and be replaced by adjacent joints in the same zone. Such "pinching out" of joints transmitting water was observed in the conduits. Observations in the conduits and data from wells suggest that a few of the zones may persist for tens of miles. The water-bearing zones of greatest areal extent are those which occur at distinct lithologic breaks in the formation. Zone 1, occurring at the base of the Lockport (fig. 8), is frequently reported to be a water-bearing zone by drillers throughout the area. Zone 2, which occurs at the contact between coarse-grained limestone (Gasport Member) and shaly dolomite (DeCew Limestone Member of Williams, 1919) is the source of most of the springs along the Niagara escarpment. Other water-bearing zones, not located at contacts between distinct lithologic units, probably tend to pinch out within a few miles. In summary, at any point in the area, a number of water-bearing zones parallel to bedding exist in the Lockport. All such zones, however, are not necessarily equivalent to the seven water-bearing zones observed in the conduit excavations at Niagara Falls.

REFERENCE NO. 4

# SOIL SURVEY OF Niagara County, New York




**NIAGARA COUNTY SOIL & WATER  
CONSERVATION DISTRICT  
FARM HOME CENTER 4437 LAKE AVE.  
LOCKPORT, NEW YORK 14094**



United States Department of Agriculture  
Soil Conservation Service  
In cooperation with  
Cornell University Agricultural Experiment Station

Issued October 1972





## SOIL ASSOCIATIONS

### AREAS DOMINATED BY SOILS FORMED IN GLACIAL TILL

- 1 Appleton-Hilton-Sun association: Deep, moderately well drained to very poorly drained soils having a medium-textured subsoil
- 2 Hilton-Ovid-Ontario association: Deep, well-drained to somewhat poorly drained soils having a medium-textured or moderately fine textured subsoil
- 3 Lockport-Ovid association: Moderately deep and deep, somewhat poorly drained soils having a fine textured or moderately fine textured subsoil

### AREAS DOMINATED BY SOILS FORMED IN GRAVELLY GLACIAL OUTWASH OR IN BEACH AND BAR DEPOSITS

- 4 Howard-Arkport-Phelps association: Deep, somewhat excessively drained to moderately well drained soils having a medium-textured to moderately coarse textured subsoil, over gravel and sand
- 5 Otisville-Altmar-Fredon-Stafford association: Deep, excessively drained to poorly drained soils having a dominantly medium-textured to coarse-textured subsoil, over gravel and sand

### AREAS DOMINATED BY SOILS FORMED IN LAKE-LAID SANDS

- 6 Minoa-Galen-Elnora association: Deep, somewhat poorly drained and moderately well drained soils having a medium-textured, moderately coarse textured, or coarse textured subsoil, over fine and very fine sand
- 7 Claverack-Cosad-Elnora association: Deep, moderately well drained and somewhat poorly drained soils having a coarse-textured subsoil, over clay or fine sand

### AREAS DOMINATED BY SOILS FORMED IN LAKE-LAID SILTS AND VERY FINE SANDS

- 8 Niagara-Collamer association: Deep, somewhat poorly drained and moderately well drained soils having a medium-textured to moderately fine textured subsoil
- 9 Canandaigua-Raynham-Rhinebeck association: Deep, somewhat poorly drained to very poorly drained soils having a dominantly medium-textured to fine-textured subsoil


### AREAS DOMINATED BY SOILS FORMED IN LAKE-LAID CLAYS AND SILTS

- 10 Rhinebeck-Ovid-Madalin association: Deep, somewhat poorly drained to very poorly drained soils having a fine textured or moderately fine textured subsoil that is dominantly brown or olive in color
- 11 Odessa-Lakemont-Ovid association: Deep, somewhat poorly drained to very poorly drained soils having a fine textured or moderately fine textured subsoil that is dominantly reddish in color

CA

ONTARIO

5-37



recycled paper

in the northwestern part of the county near the village of Youngstown. Three smaller areas also occur.

This association makes up about 15 percent of the county. About 32 percent of this is Rhinebeck soils, 10 percent is Ovid soils, and 9 percent is Madalin soils. The remaining 49 percent consists of minor soils.

The Rhinebeck soils are deep and are somewhat poorly drained. These soils typically have a silt loam surface layer, a silty clay or silty clay loam subsoil, and underlying material of varved silt and clay. They occupy the broad areas within the association and are slightly dissected by erosion in a few places, especially in areas that border Lake Ontario.

The Ovid soils occupy the slightly elevated areas where there has been some reworking of the fine-textured lake deposits and the glacial till or glacial beach deposits. The Ovid soils are deep and somewhat poorly drained. They typically have a silt loam surface layer and a silty clay loam subsoil and are underlain by loamy glacial till. Some coarse fragments are generally in and below the surface layer.

The Madalin soils occupy the more nearly level, more depressional areas within the broad, level lake plain. They are deep and poorly drained to very poorly drained. Madalin soils typically have a dark silt loam surface layer that is high in organic-matter content, a silty clay subsoil, and underlying material of varved silt and clay.

The minor soils are mainly of the Collamer, Hudson, and Niagara series. These soils are intermingled with the major soils in this association. The Collamer and Hudson soils occupy knolls or higher elevations and are intermingled with the Ovid soils. The Niagara soils are mainly nearly level.

This association has a medium value for farming. Much of it is idle or is cropland that is not used intensively. A fairly small acreage that is close to Lake Ontario is used intensively for fruit. The area near Youngstown is in community development, mostly for rural homes. The acreage in grapes is increasing, especially near the Model City area in the town of Lewiston.

Natural drainage is the principal concern in town and country planning and in farm development. The flatness of the area is the biggest factor to consider in planning artificial drainage. The soils in most of the association can be drained readily by installing adequate surface ditches. Tile lines help in draining some of the wet, coarser textured inclusions. The major need is group drainage projects that provide suitable outlets.

If drainage is adequate, this association has a good potential for apples, grapes, pears, and other fruit. Peaches and cherries normally are not suited. Some vegetables can be grown intensively, but maintaining soil tilth is difficult. Grain and hay crops are suited if drainage is adequate. The need for lime is generally small.

Natural drainage and slow permeability are the two most limiting factors for community development.

Sanitary sewers and adequate surface drainage are needed. In many places the soils are unstable because they formed in deep lake deposits.

About 85 percent of the acreage is in open land. The forested areas consist mostly of scattered farm woodlots. Some of the idle land is reverting to ash, soft maple, and other native hardwoods. Open-land wildlife is plentiful in many areas. Pheasants and rabbits are the most commonly hunted wildlife species, and there is a potential for wetland wildlife. Recreation in this association consists mostly of hunting, fishing, camping, and golfing. Scenic areas are confined mostly to the part of the association that borders the Niagara River and Lake Ontario.

#### 11. Odessa-Lakemont-Ovid association

Deep, somewhat poorly drained to very poorly drained soils having a fine textured or moderately fine textured subsoil that is dominantly reddish in color

This is the largest soil association in Niagara County. It consists of level or nearly level soils on lake plains south of the limestone escarpment (fig. 5). There are two large areas that are dotted with small knolls and ridges of till. The largest area is west of the Barge Canal, and the other area is in the same topographical position as the larger area but is east of the Barge Canal.

This association makes up about 21 percent of the county. About 24 percent of this is Odessa soils, 14 percent is Lakemont soils, and 11 percent is Ovid soils. The remaining 51 percent consists of minor soils.

The Odessa soils are deep and somewhat poorly drained. They typically have a silty clay loam surface layer, a silty clay subsoil, and clay and silt underlying material. These soils are level and occupy the broad areas between the poorly drained, depressional areas and the slightly elevated till ridges.

The Lakemont soils are level to slightly depressional and are generally adjacent to the better drained Odessa soils. Lakemont soils typically have a silty clay loam surface layer, a silty clay subsoil, and underlying material of clay and silt. They have a darker surface layer than the Odessa soils and show more indications of wetness.

The Ovid soils are nearly level to gently undulating and are on till landscapes at slightly higher elevations above the lake plain. They are deep and somewhat poorly drained. Ovid soils typically have a silt loam surface layer, a silty clay loam subsoil, and underlying material of loamy glacial till.

The minor soils are mainly of the Churchville, Cayuga, Cazenovia, Fonda, and Hilton series. Also included are some areas of shallow muck. In many places the moderately well drained Hilton and Cazenovia soils occupy the higher parts of the knolls and




Figure 5.--Typical cross section of the Odessa-Lakemont-Ovid association.

till ridges that are scattered throughout the association. Around the fringes of these areas, where lacustrine clays overlap the till, are the somewhat poorly drained Churchville soils and the moderately well drained Cayuga soils. The very poorly drained Fonda soils and the shallow muck occupy some of the deeper depressions in the lake plain.

This association has a fairly low value for farming. Much of it is idle or cropland that is not intensively used. Communities are being rapidly developed in the western part of the association near Niagara Falls and in areas south of Lockport. The Conservation Needs Inventory for 1958 indicated that 58 percent of this association is cropland, 6 percent is pasture, 4 percent is forest, 14 percent is urban or built-up areas, and 18 percent is open land (6).


Natural drainage is the main concern in town and county planning and in agricultural development. The flatness of the area and the generally fine texture of the soils are the main factors to consider before installing artificial drainage. The biggest need is for group drainage projects that provide suitable outlets.

If adequately drained, the soils in this association have a good potential for grain and for dairy cattle and other livestock. The texture of the soils is generally too fine for most vegetable crops. If the soils are cultivated intensively, they are difficult to till because they crust, clod, and compact. Most fruit crops are damaged by frost in this association. The need for lime is small.

REFERENCE NO. 5



# Preliminary Evaluation Of Chemical Migration To Groundwater and The Niagara River from Selected Waste- Disposal Sites



8. CARBORUNDUM, BUILDING 82 (Literature review)

NYSDEC 932048-b

General information and chemical-migration potential.--Building 82 is at Carborundum's Buffalo Avenue Plant in Niagara Falls. The area south of Building 82 is used as a transfer point for general waste products, which include silicon dust and fibers. The waste is sent away for disposal. No geologic, hydrologic, or chemical information is available. The potential for contaminant migration is indeterminable.

9. CARBORUNDUM--ABRASIVE DIVISION (Literature review)

NYSDEC 932007

General information and chemical-migration potential.--The Carborundum-Abrasive Division site, in the town of Wheatfield, was an open dump used during 1968-76 to dispose of 800 to 1,600 pounds of phenols and 400 tons of solidified resins, floor sweepings, and waste fillers, including calcium carbonate, clays, and animal glue. This site has been remediated through the installation of a clay cap, which was joined to the silty clay around the site. The potential for contaminant migration is indeterminable.

Geologic information.--The site consists of clay and silty fill underlain by a silty lacustrine clay, which is in turn underlain by a discontinuous layer of till. These units overlie bedrock of Lockport Dolomite. A geologic cross section is shown in figure C-4.




Figure C-4. Geologic cross section of formations underlying Carborundum-Abrasive Division, site 9, Wheatfield.  
(Modified from Conestoga-Rovers and Assoc., 1981.)

REFERENCE NO. 6



# ELECTRO MINERALS (U.S.), INC.

---

Subsidiary of  
Washington Mills Abrasive Co.

P.O. Box 423  
Niagara Falls, NY 14302

---

July 8, 1987

Mr. D. Sutton  
Ecology & Environment  
195 Sugg Road  
P.O. Box D  
Buffalo, NY 14225

Dear Mr. Sutton:

I have made corrections to the attachment. I also included information on soil borings done in 1984 in the area behind B82. If you have any questions, please call me at (716)278-2563.

Yours truly,

ELECTRO MINERALS (U.S.), INC.



P.K. Haynes  
Manager  
Environmental, Health & Safety

PKH:amb

Attachment

cc: R.R. Campbell N/A  
G.J. Bush N/A

Former Waste Material That Prompted Action by the New York State Department of Environmental Conservation (NYSDEC):

- o Metal and wood scrap and miscellaneous waste were stored behind Building 82
- o All these wastes were removed in 1985 by Modern Disposal

Permits:

- o EPA waste generator #: NYD001367481
- o SPDES Permit: NYD001367 (for cooling water)
- o Several air permits
- o ~~Sanitary sewer permit (for neutralized sulfuric acid)~~

X Previous Sampling:

- o 4 core samples taken during sewer installation on site along Adams Ave.
- o NYSDEC has analytical results for these samples
- o One sample had slightly elevated mercury

Storage Tanks:

- o Gasoline (underground), 8000 gallons for plant vehicles
- o Diesel fuel (underground), 4000 gallons for plant vehicles
- o Fuel oil (above ground), 20000 gallons, not currently used, has been cleaned by Elmwood Tank and Piping Corp.

Previous Enforcement Actions:

- o Response to Engineered Materials Division Machine Shop
- o Engineered materials is not part of Electro Minerals (U.S.) Inc.
- o Machine shop formerly disposed of used cutting oils on ground
- o Soil has been removed and site remediated

The above statements, with any qualifications or corrections added, are true to the best of my knowledge.

Signature

Date

ATTACHMENT 1

Name of Company:

Electro Minerals (U.S.) Inc.

Subsidiary of:

Washington Mills Abrasives  
20 North Main Street  
North Grafton, MA

Owner of Parent Company:

Peter Williams

Previous Owners:

- o Formerly owned by Carborundum
- o Carborundum owned by Standard Oil (SOHIO)
- o Carborundum formerly owned by Kennecott Copper

Field of Business:

Manufacture of abrasive grains ~~and grinding materials~~  
Current Plant Operations (partial list):

- o Crushing
- o Sorting
- o Bagging
- o Arc Furnace Processing

Current Products and Comments:

- o Silicon Carbide
  - requires crushing and sorting processes
- o Premium Aluminum Oxide *REFINED*
  - Manufactured from *BROWN* aluminum oxide in an arc furnace  
crushing and sorting processes follow production
- o Boron Carbide
  - Raw materials graphite and boric acid are fused  
in an arc furnace

*BROWN Aluminum  
OXIDE  
- processes;  
Crush, size,  
SORT, bag*

Waste Streams

- o Grain-rinsing solvents (toluene, acetone, methanol)
- o Used lubricating oils, *GREASES, DEGRASING AGENTS*

Waste Treatments:

- o Some solvents recycled by a contractor named Safety-Clean *KLEIN*
- o Other wastes are removed by SCA when 6-8 drums accumulate  
(this occurs a few times per year)

REFERENCE NO. 7

recycled paper

5-418

© 1987 J. L. Darling Corporation



# MEMO

NOTEBOOK NO. 391

Electronics

Garage, 100-1000, 382

June 24, 1987

a product of  
**J. L. DARLING CORPORATION**  
TACOMA, WASHINGTON 98421 U.S.A.

ecology and environment

recycled paper

Electromineral

Weather Sunny and very hot (40's) no wind

Arrive at Plant 9.00 AM, June 24, 1987

Conduct interview with Patricia Hogg.

155) See notes following site inspection  
rent

Commence visual site inspection at 9.55

Photo 1 → Silicon Carbide pile at Weir  
at Bdy 83  
Recycled eventually

Photo 2 → Alum. Oxide from settling  
pond.  
Settling pond for non-contact  
cooling water (does get some solids)  
Have SPDES permit.

Photo 3 → Mixed product pile

Settling pond ← Photo 4  
removes solids before it reaches turbine.  
Controlled by SPDES.

10:10: Viewed area behind Bldg 82.

Nothing above ground seen.

Some slag seen on ground.

Otherwise sandy, gravelly soil.

Some areas appeared dark.

Photo-5 → former disposal area.

Disposal items removed in 25 by  
Molten Disposal.

Elmwood tank clear #2 fuel oil tank  
in Building 82.

Lot of unused equipment in Building 82.

Photo 6 → H<sub>2</sub>SO<sub>4</sub> tank.

Is neutralized with NaOH,

has sanitary sewer.

Have Sanitary permit.

Photo 7 → acid neutralizing tank.

Discharges monitored in 3 spots.

Joe R. Lytle 6/24/87

Interview with Patricia Hynes

Manager Environmental Health & Safety

Name of Company:

Electrominerals (US) Incorporated

Subsidiary of Washington Mills Abrasives

Formerly owned by Carborundum

Carborundum bought by Kennecott Copper

then "Standard Oil (Indiana)"

then bought by Washington Mills Abrasives

Parent Co. Washington Mills Abrasives

20 North Main Street

North Canton, Ohio

President & CEO: Peter Williams

Joe R. Lytle 6/24/87

for Ldgt 6/24/87

Business:

Manufacture Grinding Materials  
Abrasive Grains

Current operations: Crushing  
Sorting  
Bagging

Are Furnace Processing

Products: Premium Aluminum Oxide  
(from refined aluminum) (use are)  
Graphite & Boric acid →  
Boron Carbide (Fusing process)  
Silicon Carbide

Current Waste: Spent Solvents for grain rinsing  
(Hexane, acetone, methanol)  
Used lubricating oil.

Disposed through SCA -- When  
6-8 drums accumulate, pay call SCA.

Safety - Clean does recycle solvents

for Ldgt

6/24/87

for Ldgt 6/24/87

Previous waste.

No buried on site.

→ Used to have junkyard behind Building 82  
All removed in 1983 by Modern Disposal  
Wastes were metal & wood scrap/mix. wastes.  
Since 1980, followed RCRA regulations for  
cell material

Permits:

EPA Waste generator # NYD001367481

SPDES Permit NYD001367

Numerous air Permits

Sanitary Sewer Permit

Sampling: 4 routine samples during installation  
of S/S sewer on site. DEC has  
received. One sample high in mercury -

for Ldgt 6/24/87



Tanks:

Jon budget 6/24/87

Gasoline (UST) 8000 gal } for plant  
Diesel (UST) 4000 gal } vehicle  
Fuel oil (HGST) 20000 gal

L7 applied & cleared

Jon budget 8/24/87

# INTERVIEW ACKNOWLEDGEMENT FORM

SITE NAME: Carborundum Bldg. 82 I.D. NUMBER: 932048B  
PERSON Barry H. Christensen DATE: 4/17/89  
CONTACTED: Manager Environmental Services PHONE NUMBER: (716) 286-3000  
AFFILIATION: Occidental Chemical Corporation CONTACT  
ADDRESS: Occidental Chemical Center PERSON(S):  
360 Rainbow Blvd., Niagara Falls, NY 14302  
TYPE OF CONTACT: Telephone

## INTERVIEW SUMMARY

Mr. Christensen stated that the two aboveground tanks shown in the photograph from the E & E logbook were underground storage tanks that had been exhumed and were pending removal. Since the time of the photograph, the tanks have been removed.


A copy of the photograph was sent along with this acknowledgement form.

Mr. Christensen also provided the full name, address and phone number for Diversified Manufacturing, Inc.

## ACKNOWLEDGEMENT

I have read the above transcript and I agree that it is an accurate summary of the information verbally conveyed to Ecology and Environment, Inc. interviewer(s) (as revised below, if necessary).

Revisions (please write in any corrections needed to above transcript)

  
Signature:

Date:

4/21/89


ecology and environment, Inc.  
PHOTOGRAPHIC RECORD

Client: New York State DEC

E & E Job No.: ND2031

Camera: Make Anso 35 mm

SN: \_\_\_\_\_



Photographer: D. Sutton


Date/Time: 6/12/87 10:13

Lens: Type: \_\_\_\_\_

SN: \_\_\_\_\_

Frame No.: 1

Comments\*: parking area,  
aboveground tanks located  
near the east side of the  
maintenance building



Photographer: D. Sutton

Date/Time: 6/12/87 10:17

Lens: Type: \_\_\_\_\_

SN: \_\_\_\_\_

Frame No.: 2

Comments\*: Modern Disposal  
dumpster for disposal of  
scrap pallets, paper, pipe,  
and steel

\*Comments to include location

339023

REFERENCE NO. 8

DRAFT

GRAPHICAL EXPOSURE MODELING SYSTEM

(GEMS)

USER'S GUIDE

VOLUME 1. CORE MANUAL

Prepared for:

U.S. ENVIRONMENTAL PROTECTION AGENCY  
OFFICE OF PESTICIDES AND TOXIC SUBSTANCES  
EXPOSURE EVALUATION DIVISION  
Task No. 3-2  
Contract No. 68023970  
Project Officer: Russell Kinerson  
Task Manager: Loren Hall

Prepared by:

GENERAL SCIENCES CORPORATION  
6100 Chevy Chase Drive, Suite 200  
Laurel, Maryland 20707

Submitted: February, 1987

## 1. INTRODUCTION

The Graphical Exposure Modeling System (GEMS) is an interactive computer system developed by General Sciences Corporation under the auspices of the Modeling Section in the Exposure Evaluation Division (EED), Office of Toxic Substances (OTS) of the Environmental Protection Agency (EPA). It provides a simple interface to environmental modeling, physiochemical property estimation, statistical analysis, and graphic display capabilities, with data manipulation which supports all of these functions. An overview of the basic GEMS components is shown in Figure 1-1. The system is installed on the OTS VAX 11/780 computer in Research Triangle Park, North Carolina, and is accessible through dial-up lines.

GEMS is being developed to support integrated exposure analyses at OTS. Its purpose is to provide environmental researchers and analysts with a set of sophisticated tools to perform exposure assessments of toxic substances without requiring them to become familiar with most aspects of computer science or programming.

GEMS is designed under a unique concept which integrates the computerized tools of graphics, mapping, statistics, file management, and special functions such as modeling and physiochemical property estimation, under a user-oriented and simple-to-learn interface. GEMS prompts the user or provides a menu for each action to be performed. The following features provide users with great flexibility during the GEMS execution:

- o **HELP commands** - When you are using the GEMS system, you may not always have a user's manual readily available and/or you may need to see the format and type of a command or an answer before you enter it. Various HELP commands are available in GEMS which provide such information.
- o **Recovering from errors** - If you enter a command or a response incorrectly, the system issues an error message and reprompts you for the correct information.
- o **Built-in defaults for model execution** - GEMS is designed to guide inexperienced users through the execution of selected models. Default responses are usually available when you cannot specify a choice or supply an input to a prompt during model execution.
- o **Data management of modeling results** - Data generated from execution of the SESOIL, ISC, SWIP, or AT123D models may be stored automatically in GEMS. These data may be accessed or analyzed via GEMS' file management, graphics, and statistics operations.

The purpose of this document is to describe GEMS from the user's point of view. It is intended as a comprehensive guide to the use of GEMS for personnel who have no specialized knowledge of computer programming. However, a working knowledge of environmental modeling is necessary for complete and accurate use of the system.




FIGURE 1-1. Components of the Graphical Exposure Modeling System (GEMS)

Since the last draft of the GEMS User's Guide, completed in June, 1984, the GEMS system has gone through a number of modifications and enhancements. It is no longer feasible to hold all sections in one single volume. This revised user's guide is designed in a modular fashion of six separate volumes described briefly below. In addition, GEMS has been adapted to function on an IBM PC/XT or AT. This prototype called POGEMS has many of the same capabilities of the mainframe GEMS. These include environmental modeling procedures such as ENPART and AT123D as well as property estimation procedures such as CLOGP and AUTOCHEM. The prototype POGEMS works in large part through interface with the OTS VAX 11/780 on which GEMS resides, a user's guide for POGEMS will be available in the near future.

#### Volume 1: Core-Manual

This volume is a reference manual and introduction for first-time users. In addition to Section 1 - Introduction, a functional description of GEMS is presented in Section 2, a detailed guide to the use of the system is presented in Section 3, and summaries of the VAX operating environment and system and frequently used utilities are presented in Section 4. Two sample runs are given in the attachment to provide users with information in order to interact with the GEMS system, to generate a dataset, and subsequently, produce a map from the dataset.

#### Volume 2: Modeling

This volume consists of all GSC prepared user's manuals to GEMS models, grouped according to media. User's manuals are available for the following models: SESOIL, AT123D, SWIP, ENPART, TOX-SCREEN, INPUFF, and ISC/GAMS. A user's manual for EXAMS II model will be available later this year. Refer to Section 2.2 for further information.

#### Volume 3: Graphics and Geodata Handling

This volume contains two GEMS operations, Graphics and Geodata Handling. The Graphics operation contains a variety of graphics procedures which may be used to display results from modeling runs or from datasets. The Geodata Handling operation contains procedures that perform geographic data manipulation and generate maps of U.S. states or counties. Refer to Section 2.3 for further information.

#### Volume 4: Data Manipulation

This volume contains descriptions of GEMS system-installed datasets and two GEMS operations - File Management, and Utilities. Refer to Section 2.4 for further information.



## Volume 5: Estimation


This volume consists of user's manuals for SFILES, FAP, CLOGP, and AUTOCHEM. These estimation programs may be used to provide estimated physiochemical properties for model input or for other environmental fate analyses. Refer to Section 2.5 for further information.

## Volume 6: Statistics

This volume contains information on the GEMS Statistics operation which includes the Descriptive Statistics procedure and procedures to produce simple or multiple regression and contingency tables. Refer to Section 2.6 for further information.

REFERENCE NO. 9

# Effect of Niagara Power Project on Ground-Water Flow in the Upper Part of the Lockport Dolomite, Niagara Falls Area, New York



U.S. GEOLOGICAL SURVEY  
Water-Resources Investigations  
Report 86-4130

Prepared in cooperation with the  
U.S. ENVIRONMENTAL PROTECTION AGENCY  
NEW YORK STATE DEPARTMENT OF  
ENVIRONMENTAL CONSERVATION



of studies by the New York State Department of Environmental Conservation, private consultants, and by the U.S. Geological Survey to describe groundwater conditions at many waste-disposal sites in the Niagara Falls area.

### Acknowledgments

The New York Power Authority provided construction details of the power-project facilities, water-level data from the forebay canal and pumped-storage reservoir, and assistance in measuring water levels in NYPA wells in the vicinity of the pumped-storage reservoir. The New York State Department of Environmental Conservation coordinated the water-level measurements at industrial sites. Several industries, including Occidental Petroleum and E.I. Dupont De Nemours and Company, provided water-level data. The City of Niagara Falls provided construction details on many sewer and building projects and assisted in obtaining permits and permission to drill observation wells within the city.

## GEOHYDROLOGY OF THE LOCKPORT DOLOMITE

### Stratigraphy and Lithology

Unconsolidated glacial deposits of till and lacustrine silt and clay, generally 5 to 15 ft thick but ranging to 48 ft thick, overlie the 80- to 158-ft-thick Lockport Dolomite of Middle Silurian age within the Niagara Falls area (Tesmer, 1981). The thickest unconsolidated deposits (up to 48 ft) are in a shallow buried valley in the western part of the city (pl. 1B).


Underlying the Lockport Dolomite is a 27-ft-thick sequence of Middle Silurian shale, limestone, and dolomite in the lower part of the Clinton Group, which is underlain by a 113-ft-thick sequence of Lower Silurian sandstone and shale that is in turn underlain by 1,200-ft-thick Upper Ordovician shale. These rocks are exposed only in the Niagara River gorge and are shown in the stratigraphic column in figure 2. The strata are gently folded and dip slightly to the south-southwest at about 30 ft/mi (Fisher and Brett, 1981).

The Lockport Dolomite is a fine to coarse crystalline, thin to massive bedded dolomite, limestone, and shaly dolomite, with vugs containing gypsum (calcium sulfate) and calcite (calcium carbonate). Other minor minerals disseminated throughout the formation are sphalerite (zinc sulfide), pyrite (iron sulfide), and galena (lead sulfide) (Tesmer, 1981).

### Hydraulic Conductivity

The Lockport can be divided into two zones on the basis of water-transmitting properties. The upper 10 to 25 ft of rock is a moderately permeable zone that contains relatively abundant bedding planes and vertical joints enlarged by dissolution of dolomite and abundant solution cavities left by dissolution of gypsum; the remainder of the formation contains low to moderately permeable bedding planes of which as many as seven may be major water-bearing zones that are surrounded by fine-grained crystalline dolomite.

of low permeability. Hydraulic-conductivity values obtained from model simulations and limited aquifer-test data (Maslia and Johnston, 1982) range from 5 to 15 ft/d in the upper part and from 1 to 2 ft/d in the lower part. Well yields commonly range from 10 to 100 gal/min.



System and series	Group	Formation	Thickness (feet)	Description
Silurian	Middle	Lockport Dolomite	158	Dark-gray to brown, massive to thin-bedded dolomite locally containing algal reefs and small, irregularly shaped masses of gypsum. Near the base are light-gray coarse-grained limestone (Gasport Limestone Member, dark-gray shaley dolomite)
		Rochester Shale	60	Dark-gray calcareous shale weathering light-gray to olive.
	Clinton	Irondequoit Limestone	12	Light-gray to pinkish-white coarse-grained limestone.
		Reynales Limestone	10	White to yellowish-gray shaly limestone and dolomite.
		Neahga Shale	5	Greenish-gray soft fissile shale.
		Thorold Sandstone	8	Greenish-gray shaly sandstone.
	Lower	Grimsby Sandstone	45	Reddish-brown to greenish-gray cross-bedded sandstone interbedded with red to greenish-gray shale.
		Power Glen Shale	40	Gray to greenish-gray shale interbedded with light-gray sandstone.
		Whirlpool Sandstone	20	White, quartzitic sandstone
Ordovician	Upper	Queenston Shale	1,200	Brick-red sandy to argillaceous shale.

Figure 2.--Stratigraphy of the Niagara Falls area.  
(Modified from Fisher, 1959.)

## Ground Water

### *Occurrence*

The Lockport Dolomite is the principal source of ground water in the Niagara Falls area. Although the effective primary porosity is negligible, significant ground-water movement occurs through secondary openings such as bedding joints (planes), vertical joints (fractures), and solution cavities, described below. The upper 25 ft of the Lockport has a greater potential for movement of ground water (and contaminants) than the deeper parts because it has more interconnected vertical and horizontal joints that have been widened by solutioning, which allows direct entry of contaminants from surface sources.

Bedding planes.--The bedding planes, which transmit most of the water in the Lockport (Johnston, 1964), are relatively continuous fracture planes parallel to the natural layering of the rock. These openings were caused by crustal movements and the expansion of the rock during removal of weight by erosion of overlying rock units and by retreat of the glaciers. Johnston (1964) identified seven water-bearing zones, which consist either of a single open-bedding plane or an interval of rock layers containing several open planes. The top 10 to 25 ft of rock may contain one or two significant bedding planes; these are probably connected by vertical joints, which are abundant in the upper part of the formation.

The lower part of the Lockport Dolomite contains fewer water-bearing bedding planes that are interconnected by vertical joints. These deeper water-bearing zones are underlain and overlain by essentially impermeable rock. Each water-bearing bedding plane can be considered a separate and distinct artesian aquifer (Johnston, 1964). The hydraulic head within each water-bearing zone is lower than that in the zone above it; this indicates a downward component of ground-water flow.

Vertical joints.--Vertical joints in the Lockport Dolomite are not significant water-bearing openings except (1) in the upper 10 to 25 ft of rock, (2) within about 200 ft of the Niagara River Gorge, and (3) in the vicinity of the buried conduits. Physical and chemical weathering have increased the number, continuity, and size of vertical fractures in the upper part of the Lockport. The major joints, oriented N 70°E to N 80°E, are generally straight, spaced 10 to 80 ft apart, and penetrate 10 to 25 ft (American Falls International Board, 1974). Intersecting the major joint set are less extensive high-angle joints that are confined to particular beds. Vertical joints become narrower, less numerous, and less connected with depth.

In addition to the major regional fractures, extensive tension-release fractures were formed near the gorge wall by the erosion and removal of the supporting rock mass in the gorge; openings up to 0.3 ft wide have been observed (American Falls International Board, 1974). Less developed tension-release joints and blasting-originated joints are common along the twin conduits. These fractures probably extend less than 100 ft from the trench walls.

Solution cavities.--Solution cavities are formed by the dissolution of gypsum pockets and stringers by percolating ground water. These cavities

range in diameter from 1/16 in to 5 in; they are most abundant in the upper 10 to 15 ft of rock but occur also along water-bearing bedding zones throughout the Lockport. The solution cavities become less continuous with depth and therefore have little effect on the water-transmitting ability of the lower parts of the formation.

### Recharge

Most of the recharge to the Lockport Dolomite results from infiltration of rainfall and snowmelt through the soil to the water table. Precipitation in the Niagara Falls area averages 30 in/yr and is fairly evenly distributed throughout the year (Dethier, 1966). Snow usually accumulates from mid-December to mid-March, during which time several thaws may reduce or entirely melt the snow pack. Seven 14-month hydrographs of U.S. Geological Survey wells installed in the upper part of the Lockport (fig. 3) and a 10-year hydrograph of a long-term observation well, NI-69 (fig. 4) indicate that most recharge occurs from late fall through winter (November to April), when evapotranspiration is low. Generally, water levels fluctuate less than 6 ft annually.




Figure 3.--Hydrographs of wells 84-1 through 84-7 in and near the City of Niagara Falls.




Figure 4.--Hydrograph of well Ni-69 in northern part of the city of Niagara Falls.

The rate and amount of recharge to a formation from precipitation depends on the permeability of the overlying lacustrine fine sand, silt, clay, and till, which in the Niagara Falls area is relatively low, with hydraulic conductivity ranging from 0.0014 to 0.27 ft/d. The average annual recharge from precipitation is estimated to be 5 to 6 in/yr (LaSala, 1967) but is probably greater in several small areas where the Lockport, whose hydraulic conductivity ranges from 5 to 15 ft/d, crops out at land surface.

#### *Movement and Discharge*

Before construction of Niagara Power project and Falls Street tunnel.-- Little information is available on ground-water levels in the Niagara Falls area before 1960; therefore, interpretation of ground-water movement in the upper part of the Lockport Dolomite before that time is based largely on fundamental assumptions governing ground-water flow. These assumptions are that (1) ground-water divides coincide with topographic highs; thus the major divides in the region were at the Niagara Escarpment, north of the study area (fig. 1), and in the central part of the City of Niagara Falls (pl. 1A); (2) regional flow of ground water followed the south-southwestward slope of the land surface and the southwestward dip of major bedding planes, (3) local ground-water movement followed the configuration of the buried bedrock surface; and (4) ground water in the central and southern parts of the city discharged to the upper Niagara River, while water in the western part discharged to the lower Niagara River in the gorge. The general inferred directions of ground-water movement in the upper part of the Lockport Dolomite before any major construction or industrial pumping is shown in figure 5.

Effect of Falls Street tunnel.--In the early 1900's, the Falls Street tunnel was excavated through the upper part of the Lockport Dolomite from 56th Street to the Niagara gorge (fig. 6). This 3.5-mi-long unlined tunnel trends



east-west and slopes 20 ft/mi beneath the southern part of the city approximately 0.65 mi north of the upper Niagara River (fig. 1). Runoff and ground water that drained into the tunnel flowed west with sewage to a treatment plant in the Niagara River gorge below the Falls.

The bottom of the Falls Street tunnel slopes westward from 549 ft above sea level at 56th Street to 533 ft at 27th Street (fig. 6), which places the tunnel at or above the altitude of the lowest part of the Niagara River channel in this reach. Thus, in the reach from 56th Street to 27th Street, water from the Niagara River (surface altitude about 560 ft) probably moves through the upper part of the Lockport northward toward the tunnel through the relatively permeable upper 15 to 20 ft of the Lockport. A shallow bedrock valley in this area (pl. 1B) may be a major zone of infiltration to the tunnel because the depth of weathering would be deepest under this channel. Ground water north and south of the tunnel probably drains into the tunnel also, but the size of the area affected by the tunnel is unknown.

The Falls Street tunnel from 24th Street west to the Niagara gorge is 25 ft or more below the relatively permeable upper zone of the Lockport. Thus, the tunnel in this area is overlain by less fractured, less permeable beds that limit downward flow. A study of ground-water infiltration into the tunnel (Camp, Dresser and McKee, 1982) found only minimal seepage to the Falls Street tunnel between 24th Street and the gorge. Although the amount of water that drained into the tunnel before construction of the conduits is unknown, the Falls Street tunnel east of 27th Street probably altered ground-water movement by creating a local ground-water low as water drained into the tunnel from the upper 25 ft of bedrock and possibly from the Niagara River.

During the 1930's and 1940's, several companies drilled and pumped water from an industrialized area within 2,000 ft of the Niagara River near Gill Creek (fig. 1); yields from these wells were as high as 1,800 gal/min. Johnston 1964) and Woodward-Clyde Consultants (1983) reported that most of the pumped water was induced recharge from the Niagara River that moves predominantly through the upper part of the Lockport Dolomite. The induced recharge from the Niagara River by industrial pumping and possibly some infiltration to the Falls Street tunnel are the only known changes in natural ground-water flow patterns in this part of the city before the construction of the Niagara Power Project.

## HYDROLOGIC EFFECTS OF NIAGARA POWER PROJECT

The Niagara Power Project, constructed by New York Power Authority during 1958-62, has an electrical production capacity of 1,950,000 kw. Part of the flow of the upper Niagara River 2.5 mi above the Falls is diverted 4 mi north through the twin buried conduits to the L-shaped forebay canal, which is between the Robert Moses powerplant and the Lewiston powerplant (fig. 1). The conduits can divert 50,000 to 75,000 ft<sup>3</sup>/s of water, which is at least 25 percent of the river's flow.

Table 1.--Flow of Niagara River over Horseshoe and American Falls.<sup>1</sup>

Season	Dates	Hours	Minimum flow over falls (ft <sup>3</sup> /s)
Tourist season	Apr. 1 to Sept. 15	Day: 8:00 am to 10:00 pm	100,000
		Night: 10:00 pm to 8:00 am	50,000
	Sept. 1 to Oct. 31	Day: 8:00 am to 8:00 pm	100,000
		Night: 8:00 pm to 8:00 am	50,000
Non-tourist season	Nov. 1 to Mar. 30	12:00 am to 12:00 am	50,000

<sup>1</sup> The diverted water (average total flow of river, 204,000 ft<sup>3</sup>/s, minus flow over falls) is divided between Canada and United States.




Figure 8.

Typical Lewiston Reservoir water levels during a weekly pumped-storage/release cycle.

### Ground-Water Flow and Water Levels

Construction of the twin buried conduits, the forebay canal, and the pumped-storage reservoir has modified hydrologic conditions within the Niagara Falls area. The daily and seasonal regulation of water levels in the reservoir and forebay canal have changed the natural flow patterns and water levels in the upper part of the Lockport Dolomite. To determine the effect of the power project on ground-water movement, water levels in the upper part of the Lockport Dolomite were measured at 104 wells on October 23-24, 1984 and on March 26-27, 1985 (values are given in table 2, at end of report). The difference between water levels in October and those in March were relatively small (generally within 3 to 5 ft); therefore, only the water levels measured in March were used to construct a potentiometric-surface map (pl. 1A), which includes arrows showing the directions of ground-water flow.

### Effect of Twin Buried Conduits

The twin buried conduits were constructed in two separate parallel bed-rock trenches approximately 4 mi long. Each trench is 52 ft wide and penetrates 100 to 160 ft into the Lockport Dolomite; at the north end they

penetrate the Lockport and upper part of the underlying Rochester Shale (fig. 9). The top of the conduits averages more than 40 ft below land surface. General construction details for the conduits are shown in figure 10.

Along the conduits are two dewatering stations--one at the intersection of the Falls Street tunnel at Royal Avenue, the other just south of the forebay canal (fig. 1). Each pumping station has direct access to water in both conduits and to water in the drain system that surrounds the conduits, which is in hydraulic contact with the surrounding bedrock. The pumping stations were designed to drain water from the bedrock surrounding each conduit through the drain system to reduce hydrostatic pressure, which could collapse the conduits should they need to be dewatered.

The drain system surrounding the conduits consists of formed, vertical 6-in-diameter drains placed every 10 ft along both sides of each conduit (fig. 11A), and two semicircular (2-ft radius) floor drains beneath the full length of the conduits at the bottom of each trench. The wall and floor drains are connected to continuous concrete-formed side drains in the lower corners of each bedrock trench (fig. 11A). All drains were formed into the concrete-conduit structure and are open to the bedrock walls and floor of conduit trenches but are not open directly to the river or forebay canal.

The only locations where water in the drain system can mix with water inside the conduits is at the two pumping stations. Each station has three sumps (fig. 11B)--a central sump connected to the conduit drain system that surrounds both conduits, and the two outer sumps, each of which is connected to the adjacent conduit. Both pumping stations have a pair of balancing weirs; one is near the Falls Street tunnel and operates at an altitude of 560 ft; the other is at the conduit outlet on the forebay canal and operates at an altitude of 550 ft. When the water level in the drain system exceeds the altitude of the balancing weir, water from the drains flows through the weir to the outer sumps and into the conduits, which discharge into the forebay canal.

Ground-water discharge into the backfill.--Backfill on top of the conduits was found to be relatively permeable where the Falls Street tunnel and conduits intersect (Koszalka and others, 1985, p. 56); however, no description of the backfill materials elsewhere along the conduits could be found. To determine whether the backfill is permeable elsewhere and forms a major pathway for ground-water movement, four wells were drilled during this study, three over the east conduit (wells 84-9, 84-10, and 84-11) and one over the west conduit (84-8, fig. 1). Drill cuttings indicated that the backfill consists of 2 to 5 ft of topsoil overlying 30 to 75 ft of shotrock (cobble- to boulder-size clasts of Lockport Dolomite that was blasted and removed during trench excavation), which overlies 5 to 15 ft of sandy, clayey silt fill of low permeability that overlies the conduits. The shotrock is permeable but unsaturated; only the lower part of the sandy, clayey silt was saturated. Water-level recorders installed on two wells in the sandy clayey silt (84-9 and 84-11, location shown in fig. 1) indicated that the water levels took several months to recover to a static level after the wells were pumped dry (fig. 12), which indicates that the sandy, clayey silt backfill has very low permeability and therefore transmits little ground water. Well 84-9 did not respond to fluctuations of water levels in the forebay canal, and water levels in well 84-11 fluctuated only when water levels in the forebay rose to altitudes greater


than 560 ft, which occurred at the end of January and beginning of February 1985, when NYPA raised the water level in the forebay canal to clear a large accumulation of pack ice from the conduit intakes along the upper Niagara River. When this occurred, the water level in well 84-11 rose 10 ft to an altitude of 556.11 ft, then began a slow, steady decline (fig. 12). Water-level altitudes greater than 560 ft at well 84-11 would have caused the lower zone of the permeable shotrock fill to become saturated. Water probably entered the well relatively rapidly by leakage down the side of the casing, which could explain the rapid rise of the water level in the well; normally this should not have occurred because the well was installed in relatively impermeable sediment. Well 84-11 does not respond to water-level fluctuations in the bedrock or forebay canal below this altitude.

The relatively impermeable, sandy, clayey silt in the saturated part of the backfill prevents significant ground-water movement in the backfill. An exception may be at the intersection of the Falls Street tunnel and the conduits, where more permeable backfill was found. The method of backfilling there may have been different from that used elsewhere along the conduits because the conduits dip where they pass under the Falls Street sewer (fig. 9).

Ground-water discharge into drains surrounding the conduits.--The drain system that surrounds the conduits has lowered ground-water levels near the conduit trenches, which causes ground water in the Lockport Dolomite to flow toward the conduits (pl. 1A). Ground water within 0.5 mi of the conduits that previously flowed southward now flows toward the conduits and discharges into the drain system. To determine the direction of flow in the drains, water levels were measured in the central chamber in the pumping stations and in several NYPA open-hole wells installed in the bedrock 5 to 10 ft from the vertical wall drains. Because the drain system is in direct hydraulic contact

Figure 12.

*Average daily water-level fluctuations in the forebay canal and recovery of water levels in wells 84-9 and 84-11 (installed in backfill atop conduits) after evacuation of water from the casing, November 1984 through July 1986.*



with ground water in the Lockport Dolomite, the hydraulic heads measured in the NYPA wells are the same or nearly the same as water levels in the drains that surround the conduits (fig. 10). Water levels in wells adjacent to the conduits indicate that, most of the time, water from the vicinity of the fore-bay canal that enters the drains flows southward to where the Falls Street tunnel crosses the conduits (pl. 1A), whereas water from the upper Niagara River that enters the drains flows northward to the tunnel. The drain system acts as the path of least resistance to ground-water flow in and near the conduit trenches.

The major discharge point for water in the conduit drains is the Falls Street tunnel where it crosses the conduits (fig. 9). The method of construction at the conduit/tunnel intersection probably created this discharge zone. During construction of the conduit trenches, a 400-ft section of the Falls Street tunnel was rebuilt with precast concrete pipe sections, and the conduit trenches were then excavated beneath the Falls Street pipeline. After backfill was placed over the conduits and around the Falls Street tunnel pipe section, ground-water levels in the backfill fluctuated at or above the top of the rebuilt section of the Falls Street tunnel (fig. 13). Apparently the seals between the concrete pipe sections failed, and water from the drains began to leak into the Falls Street tunnel.

In 1982, the Falls Street tunnel was inspected for ground-water infiltration, and a large amount of inflow, estimated at approximately 6 Mgal/d, was found to leak into the Falls Street tunnel through joints in the concrete pipe where the tunnel passes over the conduits (Camp, Dresser and McKee, 1982). Most of this leakage is probably water from the conduit drain system, which drains ground water from 0.5 mi on both sides of the 4-mi-long trenches. The Lockport Dolomite is too impermeable to supply the quantity of water that




Figure 13.

Vertical section of intersection of twin buried conduits and the reconstructed Falls Street tunnel. (Location is shown in fig. 1.)

leaks into the tunnel. Estimation of how much water enters the Falls Street tunnel from either the north (powerplant) or south (river) side of the tunnel was beyond the scope of this project, however.

### *Effect of Forebay Canal*

The forebay canal is an L-shaped excavation that penetrates the Lockport Dolomite and upper part of the Rochester Shale at the north end (outlet) of the twin conduits (fig. 1). It is 4,000 ft long, 500 ft wide, and 110 ft deep. The walls and floor are unlined. Water that enters the forebay canal from the conduits is routed to the Robert Moses powerplant, and some is pumped up to the Lewiston Reservoir, depending on the daily power-demand schedule.

The daily range of water-level fluctuations in the canal is dependent on the seasonal diversion schedule, the demand for power generation, and the flow of the Niagara River. During the summer and early fall, when the flow in the Niagara River is generally lower, daily fluctuations in the canal are greatest, as much as 25 ft. The water level in the forebay canal is increased by the release of water from the Lewiston Reservoir, which supplements the flow entering from the conduits. This combined flow into the forebay canal increases the hydraulic head in the canal to drive the Robert Moses powerplant turbines more efficiently. During high-flow periods (generally during spring) or when allowable diversions from the Niagara River are higher (table 1), daily water-level fluctuations in the forebay are less, usually ranging from 5 to 10 ft even during peak power-demand periods (fig. 7).

Ground-water discharge into the forebay canal.--The walls and floor of the forebay canal consist of bedrock. Observations of ground-water seepage from bedding planes in the forebay canal walls to the forebay canal (Lockport Dolomite) and higher water levels in nearby wells than in the forebay (pl. 1A and table 2) indicate that ground water generally discharges into the forebay canal. Little, if any, water enters the forebay canal from the underlying Rochester Shale, which has low permeability.

Effects of water-level fluctuations in the forebay canal.--The daily water-level fluctuations in the forebay canal, which can range to as much as 25 ft (fig. 7), cause instantaneous water-level fluctuations in wells along the conduits to as least 3.4 mi south of the forebay canal. The water-level fluctuations in the forebay canal also cause hydraulic-pressure changes in the drain system that surrounds the conduits. Instantaneous head responses in wells adjacent to the twin conduits to water-level fluctuations in the forebay canal suggest a direct hydraulic connection between the forebay canal and the drains. Water probably moves from the canal to the drains through gently southward dipping water-bearing bedding planes that are exposed in the walls of the forebay canal and is intercepted by the drain system that surrounds the conduits.

Water levels were recorded at four NYPA observation wells adjacent to the conduits at various distances south of the forebay canal; well OW-167 is at the outlet of the conduits, and wells OW-162, OW-152, and OW-139 are 0.8, 2.2,

REFERENCE NO. 10



NIAGARA COUNTY

HEALTH DEPARTMENT  
HUMAN RESOURCES BUILDING  
MAIN POST OFFICE BOX 428  
10th AND EAST FALLS STREET  
NIAGARA FALLS, NEW YORK 14302

October 8, 1987


Mr. Dennis Sutton  
Ecology & Environment, Inc.  
195 Sugg Road  
P.O. Box D  
Buffalo, New York 14225

Dear Dennis:

Attached are the signed interview forms you request.  
Please note that I added several comments as footnotes for  
clarification.

Contact me with any questions at 284-3126.

Sincerely,

  
Michael Hopkins  
Assistant Public  
Health Engineer

MH:lj

Attach.



Footnotes:

- 1) The Erie Barge Canal is intermittent in the Lockport area. This section is dewatered during the winter months.
- 2) The drinking water supply is over 10 miles away.
- 3) We believe that 4 families use groundwater for drinking at Wiltner and Pennsylvania Avenue. These homes may be connected to public water in the future. A line is now available for hook up.
- 4) It is noted that the wells referred to in #3 are separated from the Frontier Bronze site by the PASNY Conduits which should be a total sink and barrier to groundwater flow.
- 5) The irrigation well referred to is used only casually and occasionally to water fruit trees.
- 6) We are unaware of a fire official certifying any site in Niagara County to be a fire or explosion hazard. We do not feel that any of the sites listed constitutes a fire threat.
- 7) I assume that the location drawings provided are only approximate site locations. Most overestimate the site area.



# ecology and environment, inc.

195 SUGG ROAD, P.O. BOX D, BUFFALO, NEW YORK 14225, TEL. 716-632-4491, TELEX 91-9183

International Specialists in the Environment

October 2, 1987

Mr. Michael Hopkins  
Niagara County Department  
of Health  
10th and East Falls Street  
Niagara Falls, New York 14302

Dear Mr. Hopkins:

On several occasions during the course of the Phase 1 investigations, E & E has contacted the Niagara County Department of Health to obtain information in regard to various characteristics of the sites under investigation. The DEC requires that all information contained in Phase 1 reports be fully documented. We ask you to review the information your department has provided, as presented in this letter, and sign this document to acknowledge that you have provided this information and that it (with any corrections or qualifications) is correct to the best of your knowledge.

## Ross Steel

- 1) No hazardous waste is expected to be on site.
- 2) Groundwater is not used for irrigation within a 3-mile radius of the site.
- 3) Surface water within 3 miles of this site is used for commercial, industrial, and recreational purposes.
- 4) The drinking water intakes are upstream of site.

## Dussault Foundry

- 1) There is no use of groundwater within 3 miles of site.
- 2) The surface water within 3 miles downstream of site is used for recreation (Erie Canal). \* 1

## Town of Lockport Landfill

- 1) There is no use of groundwater within 3 miles of site.
- 2) The Erie Canal (surface water) is used for recreation near this site. \* 1
- 3) The drinking water intakes are located in the Niagara River located upstream of this site. \* 2

Mr. Michael Hopkins  
October 2, 1987  
Page Two

SKW Landfill

- 1) The drinking water surface intakes are located upstream of this site.
- 2) Groundwater is used within a 3 mile radius of this site for \* 3 drinking water.
- 3) The surface water downstream (Niagara River) is used for recreation (Maid of Mist, fishing).

Diamond Shamrock

- 1) There is no groundwater used within a 3 mile radius of this site.

Roblin Street

- 1) There is no use of groundwater within a 3 mile radius of this site, drinking or irrigation.

Electro Minerals U. S. (formerly Carborundum Bldg. 82)

- 1) The water supply intakes are located upstream of this site.

Frontier Bronze

- 1) There is no suspected hazardous waste disposal present at this site.
- 2) Groundwater for drinking purposes is used by a neighborhood approximately 2.5 miles to the NW, at the intersection of Pennsylvania and Witmer Road. Two families, roughly 8 people, use groundwater for drinking purposes. \* 5

Walmore Road

- 1) The well on site is used for irrigation.
- 2) Approximately 1 acre of area is irrigated by this groundwater well.
- 3) There is no use of surface water 3 miles downstream of this site. \* 5

New York Power Authority Road Site

- 1) Hazardous waste is not suspected to be disposed of on site.
- 2) There is no land irrigated with groundwater within 3 miles of site.

I would also like you to confirm the fact that no fire official has declared any of the following sites a fire or explosion hazard: \* 6

- o SKW Alloys Landfill - Witmer Road, Town of Niagara.
- o Dussault Foundry - Washburn Street, Lockport.
- o Frontier Bronze - New Road, City of Niagara Falls.
- o Stauffer Chemical, North Love Canal - Town of Lewiston.

Mr. Michael Hopkins  
October 2, 1987  
Page Three

- o Electro Minerals, U.S., Inc., (formerly Carobrundum Bldg. #82), Buffalo Avenue, City of Niagara Falls.
- o Ross Steel Co. - Pine Avenue, Niagara Falls (now the site of the New York Power Authority water intake conduit right-of-way).
- o Roblin Steel Company - Oliver Street, North Tonawanda.
- o LaSalle Expressway - specifically near Love Canal.
- o Diamond Shamrock, now Occidental Petroleum Corp., Ohio Street, Lockport, New York.
- o Town of Lockport Landfill - East Canal Street, Lockport, New York.
- o Power Authority Road Site - New Road, Lewiston, New York (across from Hyde Park Landfill).
- o 64 Street South (owned by Russo Chevrolet) - 64th and Niagara Falls Blvd., Niagara Falls.
- o Walmore Road, 6373 Walmore Road, Town of Wheatfield, New York.

I certify that I provided the above information to Ecology and Environment, Inc., and It is correct to the best of my knowledge.

*Subject to fact notes & comments provided*

Signature

Date

Please find maps enclosed to assist you in locating these sites. If you have any questions regarding the above, please contact me at 633-9881.

Thank you very much for your time and assistance in our ongoing investigations.

Sincerely,

*Dennis Sutton*  
Dennis Sutton

oio

REFERENCE NO. 11

New York State Department of Environmental Conservation  
600 Delaware Avenue, Buffalo, N.Y. 14202-1073



Thomas C. Jorlin  
Commissioner

July 30, 1987

Mr. Dennis Sutton  
Ecology & Environment, Inc.  
195 Sugg Road  
Buffalo, New York 14226

Dear Mr. Sutton:

Referencing your letter of July 22, the attachments furnish information relative to the location, construction, and operation of the process cooling water well installation located on the Olin Buffalo Ave. Plantsite. Sources are as follows:

- Attachment 1      Engineering Report  
                         Olin Corporation  
                         Niagara Falls, N.Y.  
                         April 15, 1983
- Attachment 2      Draft Remedial Action Program  
                         Dupont Niagara Plant  
                         Niagara Falls, N.Y.  
                         June 27, 1986
- Attachment 3      Olin Transmittal letter  
                         Re: SPDES Report for June 1987

Note that pumping rate has been reduced from approximately 3500 gpm to 670 gpm due to product line changes and engineered modifications made to Olin's cooling load.

No draw down information is available.

Sincerely,

Peter J. Buechi, P.E.  
Regional Engineer for  
Solid and Hazardous Waste

Attach.

C. Water Supply and Receiving Water1. Water Supply

The Niagara Falls plant operates with three (3) sources of water supply. Since the primary use of water is for cooling and the heat load and temperature of the Niagara River water vary with the seasons, there is a seasonal variation in consumption figures:

<u>Source</u>	<u>Flow (mgd)</u>	
	<u>Winter</u>	<u>Summer</u>
Niagara River	2.02-2.95 2.48 avg.	2.88-4.90 3.89 avg.
Well Water	2.88-3.74 3.31 avg.	3.74-5.18 4.46 avg.
City Water (City of Niagara Falls)	0.43	0.43

2. Water Quality Requirements

Among the several uses of raw water at the Niagara Falls plant (e.g., boiler feed water, product, cooling, etc.), cooling is by far the major usage of river and well water.

As noted previously, the plant can use in excess of 8 million gallons of water per day in the summer months. Ninety percent of this is for cooling purposes, mainly in "once-through" systems. In once-through systems, the initial temperature is of considerable importance. Generally, the lower the initial temperature of such a water, the more desirable it is as cooling water. Of similar importance is the consistency of temperature and the Olin process wells produce a supply at 53-55°F, summer and winter. The real value of the wells lies in the combination of low temperature and high volume.

Wells in an area about a half mile wide adjacent to the Niagara River above the falls have substantially higher yields than wells elsewhere in the area. The higher yields in this area are caused by two conditions: (1) the Lockport Dolomite is thickest in the area, and (2) more importantly, conditions are favorable for the infiltration of water from the Niagara River. The greatest thickness of the Lockport provides the maximum number of water-bearing zones to supply water to the wells. The Niagara River provides an unlimited source of recharge to the water-bearing zones.

### 3. Description of Production Wells

The Mathieson Chemical Company originally had one well at the Plant 1 site. The well was 18 inches in diameter, 125 feet deep, and was originally drilled in 1937. In a search for additional water in 1947, two additional wells were drilled approximately 50 feet west of the original No. 1 well. Also at this time, an 8 inch diameter test well was drilled between the two new wells (Number 2 and 3). Wells 2 and 3 (the wells in use at present) are 24 inches in diameter and 125 feet deep. In approximately this time period (1947), Olin discontinued use of the No. 1 well and later sold the property where the well was located to E. I. DuPont de Nemours Company. Plant records indicate that DuPont also had several wells on their property ranging in diameter from 6 to 24 inches in diameter and all approximately 125 feet deep. Field investigations carried out in 1948 concluded that "all the accessible DuPont and Mathieson operating and observation wells are cross connected either directly or indirectly" in the aquifer. Reports at the time also noted the consistent recording of crevices and broken limestone at the 45-50 foot level. This was a major water bearing layer.

Repair and remedial work was performed on Olin wells 2 and 3 in late 1978. This included plugging the 8 inch test well with concrete to a depth of 38 feet and relining the two production wells with new steel casings. The casings were 16 inches in diameter and were grouted in place from the 38 foot level to the surface. Any contamination reaching the wells must be entering from below the 38 foot level.

wells nos. 1, 2 and 3 are all 125 feet as per above.



Evidence that a substantial part of the water pumped is supplied by induced infiltration from the Niagara River is indicated by the high yields, which exceed 2000 gpm at some wells, and the chemical character of the water. The chemical composition of the water in well 304-901-6 (Olin) (which has been pumped at 2100 gpm) is more similar to Niagara River water than "typical" groundwater in the Lockport.<sup>2</sup>

The Niagara River water is returned via "clear water" sewers to the river after use. Important considerations with this supply are screening of debris, prevention of growth of aquatic organisms, fouling of conduits and heat exchangers. The major problem is lack of consistency in temperature. River water can actually be too cold in the winter months. Treatments for prevention of slime and scale must be inexpensive on a once-through system and substances cannot be added which would prove deleterious to its further uses or be in contravention of water quality or discharge standards.

In short, cooling waters should have appropriate initial temperatures and should not deposit scale, be corrosive, or encourage the growth of slimes. Among the constituents of natural water that may prove detrimental to its use for cooling purposes are hardness, suspended solids, dissolved gases, acids, and oil and slime-forming organisms. One of the most definitive lists of quality requirements for cooling waters gives the following recommended limiting concentrations:


Turbidity	50 mg/l
Hardness	50 mg/l
Iron	0.5 mg/l
Manganese	0.5 mg/l
Iron and manganese	0.5 mg/l

The Olin process wells provide a source of supply which is slightly harder than desired but in all other respects, is an ideal cooling water supply. No raw water treatment has been required for control (chemical addition or filtration) and the temperature is a uniform 53-55°F.

---

<sup>2</sup> Johnston, Groundwater in the Niagara Falls Area, New York, NYS Conservation Department, Bulletin GS-53, (1964) p. 30.

5-85



**LEGEND:**

- ⊗ OLIN PRODUCTION WELL
- NEW YORK STATE DEPARTMENT OF ENVIRONMENTAL CONSERVATION MONITORING WELL

NYSDEC MONITORING WELL LOCATION PLAN  
 NIAGARA PLANT  
 E. I. DUPONT DE NEMOURS & CO.

**WOODWARD-CLYDE CONSULTANTS**

CONSULTING ENGINEERS GEOLOGISTS AND ENVIRONMENTAL SCIENTISTS

DESIGNED BY: T.P.

SCALE IN FEET

DATE: 6/4/88

CHECKED: DWB

0 300

JOB: 83C2238-B



NIAGARA FALLS PLANT, P.O. BOX 748, NIAGARA FALLS, NY 14302

July 24, 1987

Mr. Colby Tucker  
Chief, Source Surveillance Section  
Bureau of Wastewater Facility Operation  
Division of Water - Room 320  
50 Wolf Road  
Albany, NY 12233-3506

Dear Mr. Tucker:


Re: Olin Corporation  
Niagara Falls Plant  
Permit No. NYD001635

The following comments concern Olin's Niagara Falls facility SPDES discharge monitoring report for June 1-30, 1987 reporting period:

1. All monitoring data are reported on preprinted 3320-1 forms as supplied by NYSDEC.
2. It should be noted that extra mercury sampling was conducted as an aid in better controlling our mercury discharge.
3. Credit is taken for the contribution of background total suspended solids found in the incoming river supply as sampled at Olin's river water pump house No. 16. All other reported values are gross with respect to our Niagara River intake as per revised SPDES Permit Conditions effective 6/1/87.
4. Volatile organics concentrations in samples collected from outfalls 004, 005, and the river water supply during June 10-11 are included as attachment A. Attachment B lists GC/MS detection limits for volatile organic compounds in effluent samples. Mass discharges for chloroform and trans-1,2-dichloroethylene are included in Attachment A.
5. The total average well water flow for 30 operating days during June is estimated to be 0.961 MGD based upon orifice meter integrator readings. The south well operated during the entire month of June.

Very truly yours,

OLIN CORPORATION

  
M. L. Norsworthy  
Plant Manager

AFK/MLN/dmh

Attachments

5-86

REFERENCE NO. 12

# Freshwater Wetlands Classification Sheet

December 5, 1984

Niagara County  
Map 13 of 18  
Niagara Falls Quadrangle

## Wetlands Identification

Code

Municipality

Classification

There are no wetlands in Niagara County on the Niagara Falls Quadrangle.

# NIAGARA FALLS QUADRANGLE ONTARIO-NEW YORK 7.5 MINUTE SERIES PLANIMETRIC SE/4 NIAGARA FALLS 15' QUADRANGLE


RANSOMVILLE

79°00'

43°07'30"

380 000 FEET

2'30"



REFERENCE NO. 13

## CONTACT REPORT

AGENCY : New York State Department of Environmental Conservation,  
Region 9

ADDRESS : 600 Delaware Ave., Buffalo, NY 14202

PHONE : (716)847-4550

PERSON  
CONTACTED : James Snider, Senior Wildlife Biologist

TO : Jon Sundquist

DATE : June 2, 1987

SUBJECT : Critical Wildlife habitats near potential hazardous  
waste sites in Niagara County


In preparation of Phase 1 reports on potential hazardous waste sites in New York for the NYSDEC, information about nearby critical wildlife habitats is necessary. The following information is provided by Mr. James Snider of the Bureau of Wildlife, NYSDEC Region 9.


Except for the seasonal appearance of migratory birds, including, possibly the bald eagle, there are no critical habitats of endangered species within 2 miles of the suspected waste sites listed below:

- SKW Alloys  
Witmer Road at Maryland Ave.  
Niagara Falls, NY
- Dussault Foundries  
2 Washburn Street  
Lockport, NY
- North Love Canal  
Near Cleghorn Drive  
Lewiston, NY
- Carborundum Building 82  
Buffalo Ave.  
Niagara Falls, NY
- Ross Steel Company  
4237 Pine Ave.  
Niagara Falls, NY
- Frontier Bronze  
4870 Packard Rd.  
Niagara Falls, NY
- Roblin Steel  
101 East Ave.  
N. Tonawanda, NY



- LaSalle Expressway  
Niagara Falls, NY
- Diamond Shamrock  
Ohio Ave.  
Lockport, NY
- Town of Lockport Landfill  
Canal Road  
Lockport, NY
- Power Authority Road  
Lewiston, NY
- 64th Street South  
Chevy Place  
Niagara Falls, NY
- Walmore Road  
Walmore Rd., 0.5 miles south of Lockport Road  
Wheatfield, NY

  
\_\_\_\_\_  
Signature

  
\_\_\_\_\_  
Date

REFERENCE NO. 14



# **New York State Atlas of Community Water System Sources 1982**

NEW YORK STATE DEPARTMENT OF HEALTH  
DIVISION OF ENVIRONMENTAL PROTECTION  
BUREAU OF PUBLIC WATER SUPPLY PROTECTION

## ERIE COUNTY


ID NO	COMMUNITY WATER SYSTEM	POPULATION	SOURCE
Municipal Community			
	Akron Village (See No 1 Wyoming Co. Page 10).	3640	
1	Alden Village.	3460.	Wells
2	Angola Village.	8500.	Lake Erie
3	Buffalo City Division of Water.	357870.	Lake Erie
4	Coffee Water Company.	210.	Wells
5	Collins Water District #3.	704.	Wells
6	Collins Water Districts #1 and #2.	1384.	Wells
7	Erie County Water Authority (Sturgeon Point Intake).	375000.	Lake Erie
8	Erie County Water Authority (Van DeWater Intake).	NA.	Niagara River - East Branch
9	Grand Island Water District #2.	9390.	Niagara River
10	Holland Water District.	1670.	Wells
11	Lawtons Water Company.	138.	Wells
12	Lockport City (Niagara Co).		Niagara River - East Branch
13	Niagara County Water District (Niagara Co).		Niagara River - West Branch
14	Niagara Falls City (Niagara Co).		Niagara River - West Branch
15	North Collins Village.	1500.	Wells
16	North Tonawanda City (Niagara Co).		Niagara River - West Branch
17	Orchard Park Village.	3671.	Pipe Creek Reservoir
18	Springville Village.	4169.	Wells
19	Tonawanda City.	18538.	Niagara River - East Branch
20	Tonawanda Water District #1.	91269.	Niagara River
21	Wanakah Water Company.	10750.	Lake Erie

### Non-Municipal Community

22	Aurora Mobile Park.	125.	Wells
23	Bush Gardens Mobile Home Park.	270.	Wells
24	Circle B Trailer Court.	50.	Wells
25	Circle Court Mobile Park.	125.	Wells
26	Creekside Mobile Home Park.	120.	Wells
27	Donnelly's Mobile Home Court.	99.	Wells
28	Cowanda State Hospital.	NA.	Clear Lake
29	Hillside Estates.	160.	Wells
30	Hunters Creek Mobile Home Park.	150.	Wells
31	Knox Apartments.	NA.	Wells
32	Maple Grove Trailer Court.	72.	Wells
33	Millgrove Mobile Park.	100.	Wells
34	Perkins Trailer Park.	75.	Wells
35	Quarry Hill Estates.	400.	Wells
36	Springville Mobile Park.	114.	Wells
37	Springwood Mobile Village.	132.	Wells
38	Taylor's Grove Trailer Park.	39.	Wells
39	Valley View Mobile Court.	42.	Wells
40	Villager Apartments.	NA.	Wells

## NIAGARA COUNTY

ID NO	COMMUNITY WATER SYSTEM	POPULATION	SOURCE
Municipal Community			
	Lockport City (See No 12, Erie Co).	25000	
1	Middleport Village.	2000.	Wells (Springs)
	Niagara County Water District (See No 13, Erie Co).	48	
2	Niagara Falls City (See also No 14 Erie Co).	77384.	Niagara River - East Branch
	North Tonawanda City (See No 16 Erie Co).	36000	
Non-Municipal Community			
3	Country Estates Mobile Village.	28.	Wells



Source: Erie County Department of Planning and Economic Development, 1982.

5-96

SCALE 1:250,000

5 MILES

NORTH

ecology and environment

REFERENCE NO. 15

# The National Register of Historic Places

1976

Irene Lewishon to carry forward their work in drama and dance with local children. *Multiple public/private: NHL.*

#### NIAGARA COUNTY

Lewiston. **FRONTIER HOUSE**, 460 Center St., 1824-1826. Stone, 3 1/2 stories, rectangular; gabled roof with stepped gables, paired chimneys, and balustrade; off-center and center entrances, full-width front porch with hipped roof, regular fenestration, oval windows in gables; N kitchen wings. Federal elements. Built as a tavern for Joshua Fairbanks and Benjamin and Samuel Barton, local prominent businessmen. *Private.*

Lewiston. **LEWISTON MOUND**, Lewiston State Park, Hopewellian affinities (c. 160). Oval burial mound. Partially investigated. *County.*

Lewiston vicinity. **LEWISTON PORTAGE LANDING SITE**, Prehistoric-19th C.. Gently sloping ravine leading from river remains of path used by travelers to avoid Niagara Falls. Archeological explorations yielded artifacts from Indian to British occupation, indicating this was a heavily used access point to a vital overland route. *State.*

Lockport. **LOWERTOWN HISTORIC DISTRICT**, Roughly bounded by Erie Canal and New York Central RR., 19th-20th C.. Primarily residential district, with some religious and commercial buildings and warehouses; facing the canal are 2 1/2-story brick and stone residences with Greek Revival and Italianate elements built in the 1830's; off the canal are 1-2-story frame structures with additions and modern siding built mid-19th C. and some stone structures: notable are the Gothic Revival former Christ Episcopal Church (1854) and the Italianate Vine Street School (1864). Systematic development of the village began after canal opened; district was Lockport's social, commercial, and industrial center, 1830's-1860's. *Multiple public/private: HABS.*

Lockport. **MOORE, BENJAMIN C., MILL (LOCKPORT CITY HALL; HOLLY WATER WORKS)**, Pine St. on the Erie Canal, 1864. Coursed rubble, 2 1/2 stories over basement on sloping site, trapezoidal shape, hipped roof sections with cross gables, interior chimney; front center entrance with transom and pediment on pilasters, triple round arched windows in gables, rock-faced stone lintels and sills, ashlar quoins; interior altered; rear 2-story addition 1893. Built as a flour mill, converted c. 1885 to a water pumping plant; adapted as city hall 1893; one of few survivors of 25 industrial buildings once clustered along this section of Erie Canal. *Municipal.*

Niagara Falls. **DEVEAUX SCHOOL COMPLEX**, 2900 Lewiston Rd., 1855-1888. Educational complex; contains 3 connected structures-Van Rensselaer Hall (1855-1857), Patterson Hall (1866), and Munro Hall (1888); and outbuildings-barn, shed, and gymnasium.

Gothic Revival elements. Founded by Judge Samuel DeVeaux as an Episcopal school for poor and orphaned boys; later became a prominent preparatory school; closed, 1971. *Private.*

Niagara Falls. **NIAGARA FALLS PUBLIC LIBRARY**, 1022 Main St., 1902-1904, E. E. Joralemon, architect. Stone, yellow brick; 1 story, rectangular with semielliptical rear bow, flat roof with parapet, slightly projecting center entrance bay with pedimented double doorway, pedimented windows, string courses; fine interior detail intact. Neo-Classical Revival elements. One of many public libraries endowed by Andrew Carnegie. *Public.*

Niagara Falls. **NIAGARA RESERVATION**, 1885. Includes the falls, Goat Island and other islets, paths, and an observation tower. In establishing a reservation of over 400 acres, New York became the first state to use eminent domain powers to acquire land for aesthetic purposes. *State: NHL.*

Niagara Falls. **SHREDDED WHEAT OFFICE BUILDING**, 430 Buffalo Ave., 1900. Steel frame, brick; 5 stories, rectangular, flat roof, center entrance, 5 paired window bays, segmental arched basement windows, wide parapet; interior featured 4th-floor auditorium and 5th-floor cafeteria; doubled glazed windows. Commercial style. Administrative office building of original Shredded Wheat factory complex, developed by Henry D. Perky. *Private.*

Niagara Falls. **U.S. CUSTOMHOUSE**, 2245 Whirlpool St., 1863. Stone, 2 1/2 stories, square, hipped roof, arched window and door openings on W facade; built into railroad embankment, S side opens onto railroad tracks; renovated, 1928. Continues to serve as customs office for trains from Canada. *Private: HABS.*

Niagara Falls. **WHITNEY MANSION**, 335 Buffalo Ave., 1849-1851. Limestone, 2 1/2 stories, L-shaped, intersecting gabled roof sections; original section has off-center entrance with full-width Ionic portico; 19th C. side addition has front bay window and gabled dormer with 3 round arched windows. Greek Revival. Built according to 1830's design by Solon Whitney, son of Gen. Parkhurst Whitney, village founder and prominent hotel and tavern owner. *Private.*

Youngstown vicinity. **OLD FORT NIAGARA**, N of Youngstown on NY 18, 1678. Complex of stone buildings bounded by stone walls, earthworks, and a moat; restored. Original fort built in 1678; altered 1725-1726 and 1750-1759. Held alternately by French, British, and Americans in struggle for control of continent; strategically located in commanding the Great Lakes from Lake Erie to Ontario and in covering approaches to western NY. *State: NHL.*

#### ONEIDA COUNTY

Boonville. **ERWIN LIBRARY AND PRATT HOUSE**, 104 and 106 Schuyler St., 1890, C. L. Vivian (Erwin Library); 1875, J. B. Lathrop (Pratt House). Erwin Library: limestone, 1 story, gabled and hipped roofs; square tower with pyramidal roof contains recessed arched entrance. Romanesque. Pratt House: brick, 3 stories, mansard roof with dormers and central tower crowned with iron cresting and spire, ornate bracketed cornices and metal lintels; original interior wall coverings, fixtures, and woodwork. Second Empire. *Private.*

Boonville. **FIVE LOCK COMBINE AND LOCKS 37 AND 38, BLACK RIVER CANAL (BOONVILLE GORGE PARK)**, NY 46, 19th-20th C.. Section of the abandoned Black River Canal (built mid-19th C.) running through rugged terrain of Boonville Gorge; contains locks 37 and 38 and a 5-lock combine (locks 39-43); canal was 42' deep; locks, 90' by 15', which accommodate 70-ton boats, were built 1895-early 1900's. Canal built to connect Black River Valley to Erie Canal provided water supply for Erie Canal, allowed expansion of valley's lumbering industry, and fostered growth of towns. *State/county: HAER.*

Clinton. **HAMILTON COLLEGE CHAPEL**, Hamilton College campus, 1827, Philip Hooker, architect. Coursed rubble, 3 stories, rectangular, low pitched roof, interior chimney, modillion cornice, front and rear parapet; front slightly projecting 4-story clock tower with 3-stage frame belfry-2 stories, each with columns and entablature, surmounted by octagonal cupola; front center double-door entrance with round arched window above, flanked by tall round arched windows, blind decorative frame panels; limestone ashlar quoins, lintels, and sills; side elevations with 3 tiers of windows; apse added 1897; interior altered. Federal. Multipurpose classroom and chapel building designed by Philip Hooker; unusual 3-story interior plan attributed to John H. Lathrop, a trustee. *Private.*

Clinton. **ROOT, ELIHU, HOUSE**, 101 College Hill Rd., 1817. Frame, clapboarding; 2 stories, irregular shape, gabled roof, interior chimneys, pedimented arched portico, off-center entrance with semielliptical fanlight and side lights, 2-story pilasters dividing bays in flush-sided main facade, pedimented rear porch; side additions; restored, 1900's. Federal. Home of Elihu Root, U.S. Secretary of War largely credited with conceptual foundation for 20th C. development of American Army, Secretary of State, U.S. senator, and winner of 1912 Nobel Peace Prize. *Private; not accessible to the public: NHL.*

Rome. **ARSENAL HOUSE**, 514 W. Dominick St., c. 1813-1814. Brick, 2 1/2 stories, rectangular, gabled roof, pairs of bridged interior end chimneys above single gable steps, central pedimented gable with elliptical window, 2 vertical elliptical windows in gabled ends between chimneys, stone sills and lintels; later front porch with large modillion blocks, chamfered



Irene Lewishon to carry forward their work in drama and dance with local children. *Multiple public/private: NHL.*

#### NIAGARA COUNTY

Lewiston. **FRONTIER HOUSE**, 460 Center St., 1824-1826. Stone, 3 1/2 stories, rectangular; gabled roof with stepped gables, paired chimneys, and balustrade; off-center and center entrances, full-width front porch with hipped roof, regular fenestration, oval windows in gables; N kitchen wings. Federal elements. Built as a tavern for Joshua Fairbanks and Benjamin and Samuel Barton, local prominent businessmen. *Private.*

Lewiston. **LEWISTON MOUND**, Lewiston State Park, Hopewellian affinities (c. 160). Oval burial mound. Partially investigated. *County.*

Lewiston vicinity. **LEWISTON PORTAGE LANDING SITE**, Prehistoric-19th C. Gently sloping ravine leading from river remains of path used by travelers to avoid Niagara Falls. Archeological explorations yielded artifacts from Indian to British occupation, indicating this was a heavily used access point to a vital overland route. *State.*

Lockport. **LOWERTOWN HISTORIC DISTRICT**, Roughly bounded by Erie Canal and New York Central RR., 19th-20th C. Primarily residential district, with some religious and commercial buildings and warehouses; facing the canal are 2 1/2-story brick and stone residences with Greek Revival and Italianate elements built in the 1830's; off the canal are 1-2-story frame structures with additions and modern siding built mid-19th C. and some stone structures; notable are the Gothic Revival former Christ Episcopal Church (1854) and the Italianate Vine Street School (1864). Systematic development of the village began after canal opened; district was Lockport's social, commercial, and industrial center, 1830's-1860's. *Multiple public/private: HABS.*

Lockport. **MOORE, BENJAMIN C., MILL (LOCKPORT CITY HALL; HOLLY WATER WORKS)**, Pine St. on the Erie Canal, 1864. Coursed rubble, 2 1/2 stories over basement on sloping site, trapezoidal shape, hipped roof sections with cross gables, interior chimney; front center entrance with transom and pediment on pilasters, triple round arched windows in gables, rock-faced stone lintels and sills, ashlar quoins; interior altered; rear 2-story addition 1893. Built as a flour mill, converted c. 1885 to a water pumping plant; adapted as city hall 1893; one of few survivors of 25 industrial buildings once clustered along this section of Erie Canal. *Municipal.*

Niagara Falls. **DEVEAUX SCHOOL COMPLEX**, 2900 Lewiston Rd., 1855-1888. Educational complex; contains 3 connected structures-Van Rensselaer Hall (1855-1857), Patterson Hall (1866), and Munro Hall (1888); and outbuildings-barn, shed, and gymnasium.

Gothic Revival elements. Founded by Judge Samuel DeVeaux as an Episcopal school for poor and orphaned boys; later became a prominent preparatory school; closed, 1971. *Private.*

Niagara Falls. **NIAGARA FALLS PUBLIC LIBRARY**, 1022 Main St., 1902-1904, E. E. Joralemon, architect. Stone, yellow brick; 1 story, rectangular with semielliptical rear bow, flat roof with parapet, slightly projecting center entrance bay with pedimented double doorway, pedimented windows, string courses; fine interior detail intact. Neo-Classical Revival elements. One of many public libraries endowed by Andrew Carnegie. *Public.*

Niagara Falls. **NIAGARA RESERVATION**, 1885. Includes the falls, Goat Island and other islets, paths, and an observation tower. In establishing a reservation of over 400 acres, New York became the first state to use eminent domain powers to acquire land for aesthetic purposes. *State: NHL.*

Niagara Falls. **SHREDDED WHEAT OFFICE BUILDING**, 430 Buffalo Ave., 1900. Steel frame, brick; 5 stories, rectangular, flat roof, center entrance, 5 paired window bays, segmental arched basement windows, wide parapet; interior featured 4th-floor auditorium and 5th-floor cafeteria; doubled glazed windows. Commercial style. Administrative office building of original Shredded Wheat factory complex, developed by Henry D. Perky. *Private.*

Niagara Falls. **U.S. CUSTOMHOUSE**, 2245 Whirlpool St., 1863. Stone, 2 1/2 stories, square, hipped roof, arched window and door openings on W facade; built into railroad embankment, S side opens onto railroad tracks; renovated, 1928. Continues to serve as customs office for trains from Canada. *Private: HABS.*

Niagara Falls. **WHITNEY MANSION**, 335 Buffalo Ave., 1849-1851. Limestone, 2 1/2 stories, L-shaped, intersecting gabled roof sections; original section has off-center entrance with full-width Ionic portico; 19th C. side addition has front bay window and gabled dormer with 3 round arched windows. Greek Revival. Built according to 1830's design by Solon Whitney, son of Gen. Parkhurst Whitney, village founder and prominent hotel and tavern owner. *Private.*

Youngstown vicinity. **OLD FORT NIAGARA**, N of Youngstown on NY 18, 1678. Complex of stone buildings bounded by stone walls, earthworks, and a moat; restored. Original fort built in 1678; altered 1725-1726 and 1750-1759. Held alternately by French, British, and Americans in struggle for control of continent; strategically located in commanding the Great Lakes from Lake Erie to Ontario and in covering approaches to western NY. *State: NHL.*

#### ONEIDA COUNTY

Boonville. **ERWIN LIBRARY AND PRATT HOUSE**, 104 and 106 Schuyler St., 1890, C. L. Vivian (Erwin Library); 1875, J. B. Lathrop (Pratt House). Erwin Library: limestone, 1 story, gabled and hipped roofs; square tower with pyramidal roof contains recessed arched entrance. Romanesque. Pratt House: brick, 3 stories, mansard roof with dormers and central tower crowned with iron cresting and spire, ornate bracketed cornices and metal lintels; original interior wall coverings, fixtures, and woodwork. Second Empire. *Private.*

Boonville. **FIVE LOCK COMBINE AND LOCKS 37 AND 38, BLACK RIVER CANAL (BOONVILLE GORGE PARK)**, NY 46, 19th-20th C. Section of the abandoned Black River Canal (built mid-19th C.) running through rugged terrain of Boonville Gorge; contains locks 37 and 38 and a 5-lock combine (locks 39-43); canal was 42' deep; locks, 90' by 15', which accommodate 70-ton boats, were built 1895-early 1900's. Canal built to connect Black River Valley to Erie Canal provided water supply for Erie Canal, allowed expansion of valley's lumbering industry, and fostered growth of towns. *State/county: HAER.*

Clinton. **HAMILTON COLLEGE CHAPEL**, Hamilton College campus, 1827, Philip Hooker, architect. Coursed rubble, 3 stories, rectangular, low pitched roof, interior chimney, modillion cornice, front and rear parapet; front slightly projecting 4-story clock tower with 3-stage frame belfry-2 stories, each with columns and entablature, surmounted by octagonal cupola; front center double-door entrance with round arched window above, flanked by tall round arched windows, blind decorative frame panels; limestone ashlar quoins, lintels, and sills; side elevations with 3 tiers of windows; apse added 1897; interior altered. Federal. Multipurpose classroom and chapel building designed by Philip Hooker; unusual 3-story interior plan attributed to John H. Lathrop, a trustee. *Private.*

Clinton. **ROOT, ELIHU, HOUSE**, 101 College Hill Rd., 1817. Frame, clapboarding; 2 stories, irregular shape, gabled roof, interior chimneys, pedimented arched portico, off-center entrance with semielliptical fanlight and side lights, 2-story pilasters dividing bays in flush-sided main facade, pedimented rear porch; side additions; restored, 1900's. Federal. Home of Elihu Root, U.S. Secretary of War largely credited with conceptual foundation for 20th C. development of American Army. Secretary of State, U.S. senator, and winner of 1912 Nobel Peace Prize. *Private; not accessible to the public: NHL.*

Rome. **ARSENAL HOUSE**, 514 W. Dominick St., c. 1813-1814. Brick, 2 1/2 stories, rectangular, gabled roof, pairs of bridged interior end chimneys above single gable steps, central pedimented gable with elliptical window, 2 vertical elliptical windows in gabled ends between chimneys, stone sills and lintels; later front porch with large modillion blocks, chamfered



EPA

POTENTIAL HAZARDOUS WASTE SITE  
SITE INSPECTION REPORT

## I. IDENTIFICATION

01 State  
NY02 Site Number  
932048B

## PART 1 - SITE LOCATION AND INSPECTION INFORMATION

## II. SITE NAME AND LOCATION

01 Site Name (Legal, common, or descriptive name of site)  
Carborundum Building 8202 Street, Route No., or Specific Location Identifier  
Buffalo Avenue

03 City

Niagara Falls

04 State

NY

05 Zip  
Code

14302

06 County

Niagara

07 County  
Code08 Cong.  
Dist.

09 Coordinates

Latitude

43° 05' 02"

Longitude

079° 02' 14"

10 Type of Ownership (Check one)

☒ A. Private☐ B. Federal☐ C. State☐ D. County☐ E. Municipal☐ F. Other☐ G. Unknown

## III. INSPECTION INFORMATION

01 Date of Inspection

6 / 24 / 87  
Month Day Year

02 Site Status

☒ Active☐ Inactive

03 Years of Operation

Beginning Year Ending Year  
1979☐ Unknown

04 Agency Performing Inspection (Check all that apply)

☐ A. EPA☐ B. EPA Contractor

(Name of Firm)

☐ C. Municipal☐ D. Municipal Contractor

(Name of Firm)

☐ E. State ☒ F. State Contractor

(Name of Firm)

☐ G. Other

(Specify)

05 Chief Inspector

Dennis Sutton

06 Title

Geologist

07 Organization

Ecology &amp; Environment

08 Telephone No.

(716) 684-8060

09 Other Inspectors

Jon Sundquist

10 Title

Chemical Engineer

11 Organization

Ecology &amp; Environment

12 Telephone No.

(716) 684-8060

13 Site Representatives Interviewed

Patricia K. Haynes

14 Title  
Health & Safety  
Manager

15 Address

Buffalo Ave., N.F., N.Y.

16 Telephone No.

(716) 278-2563

17 Access Gained By (Check one)

☒ Permission☐ Warrant

18 Time of Inspection

0930

19 Weather Conditions

Sunny and warm (80's F), winds 0-5 mph

## IV. INFORMATION AVAILABLE FROM

01 Contact

Walter E. Demick

02 Of (Agency/Organization)

NYSDEC

03 Telephone No.

(518) 457-9538

04 Person Responsible for Site Inspection Form

M. Farrell

05 Agency

06 Organization

E &amp; E

07 Telephone No.

(716) 684-8060

08 Date

7 / 10 / 87  
Month Day Year

## 1. IDENTIFICATION

02 Site Number  
9320488

## II. WASTE STATES, QUANTITIES, AND CHARACTERISTICS

03 Waste Characteristics (Check all that apply)

<input type="checkbox"/> A. Toxic	<input type="checkbox"/> H. Ignitable
<input type="checkbox"/> B. Corrosive	<input type="checkbox"/> I. Highly volatile
<input type="checkbox"/> C. Radioactive	<input type="checkbox"/> J. Explosive
<input type="checkbox"/> D. Persistent	<input type="checkbox"/> K. Reactive
<input type="checkbox"/> E. Soluble	<input type="checkbox"/> L. Incompatible
<input type="checkbox"/> F. Infectious	<input type="checkbox"/> M. Not applicable
<input type="checkbox"/> G. Flammable	

Category	Substance Name	01 Gross Amount	02 Unit of Measure	03 Comments
SLU	Sludge			Temporary storage area for sand, fly
OLW	Oily waste			ash, fire brick, dust collector fines,
SOL	Solvents			kiln furniture, wood, grinding wheels,
PSD	Pesticides			aluminum-silica shot, fiber and metal
OCC	Other organic chemicals			scrap. No waste has been landfilled.
IOC	Inorganic chemicals			The area is not now in use, and it is
ACD	Acids			not known if hazardous materials were
BAS	Bases			stored onsite.
MES	Heavy Metals	Unknown		

[illegible]

Category	01 Feedstock Name	02 CAS Number	Category	01 Feedstock Name	02 CAS Number
FDS			FDS		
FDS			FDS		
FDS			FDS		
FDS			FDS		

New York State DEC files, Region 9, Buffalo, New York  
Ecology and Environment Site Inspection, June 1987

POTENTIAL HAZARDOUS WASTE SITE  
SITE INSPECTION REPORT

PART 3 - DESCRIPTION OF HAZARDOUS CONDITIONS AND INCIDENTS

I. IDENTIFICATION

01 State  
NY

02 Site Number  
932048B

II. HAZARDOUS CONDITIONS AND INCIDENTS

01 ☐ A. Groundwater Contamination 02 ☐ Observed (Date \_\_\_\_\_) [X] Potential ☐ Alleged  
03 Population Potentially Affected Unknown 04 Narrative Description:

There is potential for contamination - site is not lined, it is not known if hazardous waste was stored on site.

01 ☐ B. Surface Water Contamination 02 ☐ Observed (Date \_\_\_\_\_) [X] Potential ☐ Alleged  
03 Population Potentially Affected Unknown 04 Narrative Description:

Potential for surface water is present, site is approximately 600 feet from the Niagara River.

01 ☐ C. Contamination of Air 02 ☐ Observed (Date \_\_\_\_\_) [X] Potential ☐ Alleged  
03 Population Potentially Affected Unknown 04 Narrative Description:

01 ☐ D. Fire/Explosive Conditions 02 ☐ Observed (Date \_\_\_\_\_) [X] Potential ☐ Alleged  
03 Population Potentially Affected Unknown 04 Narrative Description:

Waste no longer present in storage area.

01 ☐ E. Direct Contact 02 ☐ Observed (Date \_\_\_\_\_) ☐ Potential ☐ Alleged  
03 Population Potentially Affected Unknown 04 Narrative Description:

Potential for direct contact is low - waste is removed and site is graded over with fill.

01 ☐ F. Contamination of Soil 02 ☐ Observed (Date \_\_\_\_\_) [X] Potential ☐ Alleged  
03 Area Potentially Affected Unknown 04 Narrative Description:  
(Acres)

Potential for soil contamination is higher - waste was placed directly on ground surface.

01 ☐ G. Drinking Water Contamination 02 ☐ Observed (Date \_\_\_\_\_) ☐ Potential ☐ Alleged  
03 Population Potentially Affected Unknown 04 Narrative Description:

Potential is low - water intake for Niagara Falls is located upstream in the Niagara River.

01 ☐ H. Worker Exposure/Injury 02 ☐ Observed (Date \_\_\_\_\_) [X] Potential ☐ Alleged  
03 Workers Potentially Affected Unknown 04 Narrative Description:

Potential for worker exposure is low - waste has been removed and site graded over with fill.

01 ☐ I. Population Exposure/Injury 02 ☐ Observed (Date \_\_\_\_\_) ☐ Potential ☐ Alleged  
03 Population Potentially Affected Unknown 04 Narrative Description:

Potential is low - waste has been removed and site graded over with fill.

01349

POTENTIAL HAZARDOUS WASTE SITE  
SITE INSPECTION REPORT

PART 3 - DESCRIPTION OF HAZARDOUS CONDITIONS AND INCIDENTS

I. IDENTIFICATION

01 State  
NY

02 Site Number  
932048B

II. HAZARDOUS CONDITIONS AND INCIDENTS (Cont.)

01 [X] J. Damage to Flora 02 [ ] Observed (Date 6/87) [ ] Potential [X] Alleged  
04 Narrative Description:

All flora in former waste storage area has been destroyed.

01 [X] K. Damage to Fauna 02 [ ] Observed (Date           ) [X] Potential [ ] Alleged  
04 Narrative Description:

Potential for damage to fauna is low - area is fenced, there is no vegetation, and waste has been removed.

01 [X] L. Contamination of Food Chain 02 [ ] Observed (Date           ) [X] Potential [ ] Alleged  
04 Narrative Description:

Potential is low - no agriculture in area - population is advised not to eat fish or drink untreated water downstream from site.

01 [X] M. Unstable Containment of Wastes 02 [ ] Observed (Date           ) [X] Potential [ ] Alleged  
(Spills/Runoff/Standing liquids, Leaking drums)

03 Population Potentially Affected            04 Narrative Description:

Potential is low - waste has been removed and site is covered with fill.

01 [X] N. Damage to Offsite Property 02 [ ] Observed (Date           ) [X] Potential [ ] Alleged  
04 Narrative Description:

Potential is low - waste is removed from site.

01 [ ] O. Contamination of Sewers, Storm Drains, WWTPs 02 [ ] Observed (Date           ) [ ] Potential [ ] Alleged  
04 Narrative Description:

Unknown - potential appears to be low - waste has been removed from site.

01 [ ] P. Illegal/Unauthorized Dumping 02 [ ] Observed (Date           ) [ ] Potential [ ] Alleged  
04 Narrative Description:

No potential - site is fenced, grounds are guarded.

05 Description of Any Other Known, Potential, or Alleged Hazards

III. TOTAL POPULATION POTENTIALLY AFFECTED           Unknown          

IV. COMMENTS

It has not been determined if any hazardous wastes had been disposed or stored on site. Further investigation will be needed to assess site conditions.

V. SOURCES OF INFORMATION (Cite specific references, e.g., state files, sample analysis, reports)

New York State DEC Region 9 files, Buffalo, New York  
Electro Minerals (U.S.), Inc. files, Niagara Falls, New York

# POTENTIAL HAZARDOUS WASTE SITE SITE INSPECTION REPORT

## PART 4 - PERMIT AND DESCRIPTIVE INFORMATION

### I. IDENTIFICATION

01 State  
NY

02 Site Number  
932048B

### II. PERMIT INFORMATION

01 Type of Permit Issued (Check all that apply)	02 Permit Number	03 Date Issued	04 Expiration Date	05 Comments
<input type="checkbox"/> A. NPDES				
<input type="checkbox"/> B. UIC				
<input type="checkbox"/> C. AIR				
<input type="checkbox"/> D. RCRA				
<input type="checkbox"/> E. RCRA Interim Status				
<input type="checkbox"/> F. SPCC Plan				
<input type="checkbox"/> G. State (Specify)				
<input type="checkbox"/> H. Local (Specify)				
<input checked="" type="checkbox"/> I. Other (Specify)	SPDES NY D001367481			For cooling water discharge
<input type="checkbox"/> J. None				

### III. SITE DESCRIPTION

01 Storage Disposal (Check all that apply)	02 Amount	03 Unit of Measure	04 Treatment (Check all that apply)	05 Other
<input type="checkbox"/> A. Surface Impoundment			<input type="checkbox"/> A. Incineration	<input checked="" type="checkbox"/> A. Buildings On Site
<input type="checkbox"/> B. Piles			<input type="checkbox"/> B. Underground Injection	
<input type="checkbox"/> C. Drums, Above Ground			<input type="checkbox"/> C. Chemical/Physical	
<input type="checkbox"/> D. Tank, Above Ground			<input type="checkbox"/> D. Biological	
<input type="checkbox"/> E. Tank, Below Ground			<input type="checkbox"/> E. Waste Oil Processing	
<input type="checkbox"/> F. Landfill			<input checked="" type="checkbox"/> F. Solvent Recovery	06 Area of Site
<input type="checkbox"/> G. Landfarm			<input checked="" type="checkbox"/> G. Other Recycling Recovery	
<input checked="" type="checkbox"/> H. Open Dump	Unknown		<input type="checkbox"/> H. Other (Specify)	40 Acres
<input type="checkbox"/> I. Other (Specify)				

### 07 Comments

It is unknown if hazardous waste was ever stored on site.

### IV. CONTAINMENT

01 Containment of Wastes (Check one)			
<input type="checkbox"/> A. Adequate, Secure	<input type="checkbox"/> B. Moderate	<input checked="" type="checkbox"/> C. Inadequate, Poor	<input type="checkbox"/> D. Insecure, Unsound, Dangerous
02 Description of Drums, Diking, Liners, Barriers, etc.			
No liners in use.			

### V. ACCESSIBILITY

01 Waste Easily Accessible: <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No
02 Comments:
Site is fenced and guarded, waste has been removed.

### VI. SOURCES OF INFORMATION (Cite specific references, e.g., state files, sample analysis, reports)

New York State files, Region 9, Buffalo, New York  
Ecology & Environment Site Inspection Log Book, Buffalo, New York

ecology and environment  
5-105





# POTENTIAL HAZARDOUS WASTE SITE SITE INSPECTION REPORT

## PART 5 - WATER, DEMOGRAPHIC, AND ENVIRONMENTAL DATA

### 1. IDENTIFICATION

01 State NY	02 Site Number 932048B
----------------	---------------------------

### VI. ENVIRONMENTAL INFORMATION

#### 01 Permeability of Unsaturated Zone (Check one)

☐ A.  $10^{-6}$  -  $10^{-8}$  cm/sec   ☒ B.  $10^{-4}$  -  $10^{-6}$  cm/sec   ☐ C.  $10^{-4}$  -  $10^{-3}$  cm/sec   ☐ D. Greater Than  $10^{-3}$  cm/sec

#### 02 Permeability of Bedrock (Check one)

☐ A. Impermeable (Less than  $10^{-6}$  cm/sec)   ☐ B. Relatively Impermeable ( $10^{-4}$  -  $10^{-6}$  cm/sec)   ☒ C. Relatively Permeable ( $10^{-2}$  -  $10^{-4}$  cm/sec)   ☐ D. Very Permeable (Greater than  $10^{-2}$  cm/sec)

#### 03 Depth to Bedrock

9 (ft)

#### 04 Depth of Contaminated Soil Zone

Unknown (ft)

#### 05 Soil pH

5.6 - 7.6

#### 06 Net Precipitation

4 (in)

#### 07 One Year 24-Hour Rainfall

2.5 (in)

#### 08 Slope Site Slope

0.1 %

#### Direction of Site Slope

SW

#### Terrain Average Slope

0.1 %

#### 09 Flood Potential

Site is in NA Year Floodplain

☐ 10

☐ Site is on Barrier Island, Coastal High Hazard Area, Riverine Floodway

#### 11 Distance to Wetlands (5 acre minimum)

ESTUARINE

OTHER

A. NA (mi)

B. 3.5 (mi)

#### 12 Distance to Critical Habitat (of Endangered Species)

NA (mi)

Endangered Species: NA

#### 13 Land Use in Vicinity

Distance to:

COMMERCIAL/INDUSTRIAL

RESIDENTIAL AREAS, NATIONAL/STATE  
PARKS, FORESTS, OR WILDLIFE RESERVES

PRIME AG LAND

AGRICULTURAL LANDS

AG LAND

A. 0 (mi)

B. 1,500 feet (mi)

C. 1.5 (mi)

D. 1.5 (mi)

#### 14 Description of Site in Relation to Surrounding Topography

This site is located 1-3/4 miles east of the American Falls in the City of Niagara Falls, New York; Niagara Co. It is 600 feet north of the Niagara River in a highly industrialized southern section of the city. This area is characterized by numerous chemical plant facilities. Residential areas are located approximately 1,500 feet to the north of the site.

### VII. SOURCES OF INFORMATION (Cite specific references, e.g., state files, sample analysis, reports)

USGS 7-1/2 minute topographic map, Niagara Falls quadrangle  
Graphical Exposure Modeling System, USEPA, Federal Plaza, New York, New York  
Groundwater in the Niagara Falls Area, New York - Johnston, 1964  
Uncontrolled Hazardous Waste Site Ron King System; A Users Manual  
Soil Survey of Niagara County, New York, 1972, USDA Soil Conservation Service

D1649

POTENTIAL HAZARDOUS WASTE SITE  
SITE INSPECTION REPORT

I. IDENTIFICATION

01 State  
NY

02 Site Number  
932048B

PART 6 - SAMPLE AND FIELD INFORMATION

II. SAMPLES TAKEN

Sample Type	01 Number of Samples Taken	02 Samples Sent to	03 Estimated Date Results Availab
Groundwater			
Surface Water			
Waste			
Air			
Runoff			
Spill			
Soil			
Vegetation			
Other			

III. FIELD MEASUREMENTS TAKEN

01 Type	02 Comments
HnU Air Monitoring	No readings above background noted

IV. PHOTOGRAPHS AND MAPS

01 Type	<input checked="" type="checkbox"/> Ground <input type="checkbox"/> Aerial	02 In Custody of <u>Michael Hanchak, Ecology &amp; Environment, Inc.</u> (Name of organization or Individual)
03 Maps	04 Location of Maps	
<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	<u>Electro Minerals (U.S.), Inc.</u>	

V. OTHER FIELD DATA COLLECTED (Provide narrative description of sampling activities)

VI. SOURCES OF INFORMATION (Cite specific references, e.g., state files, sample analysis, reports)

New York State DEC files, Region 9, Buffalo, New York  
USEPA files, Region II, Federal Plaza, New York, New York

D164

POTENTIAL HAZARDOUS WASTE SITE  
SITE INSPECTION REPORT

PART 7 - OWNER INFORMATION

I. IDENTIFICATION

01 State  
NY

02 Site Number  
932048B

II. CURRENT OWNER(S)

PARENT COMPANY (If applicable)

01 Name  
Electro Minerals (U.S.), Inc.

02 D+B Number

08 Name  
Washington Mills Abrasives

09 D+B Number

03 Street Address (P.O. Box, RFD #, etc.)  
Buffalo Avenue

04 SIC Code

10 Street Address (P.O. Box, RFD #, etc.)  
20 North Main Street

11 SIC Code

05 City  
Niagara Falls

06 State  
NY

07 Zip Code  
14302

12 City  
North Grafton

13 State  
MA

14 Zip Code

01 Name

02 D+B Number

08 Name

09 D+B Number

03 Street Address (P.O. Box, RFD #, etc.)

04 SIC Code

10 Street Address (P.O. Box, RFD #, etc.)

11 SIC Code

05 City

06 State

07 Zip Code

12 City

13 State

14 Zip Code

01 Name

02 D+B Number

08 Name

09 D+B Number

03 Street Address (P.O. Box, RFD #, etc.)

04 SIC Code

10 Street Address (P.O. Box, RFD #, etc.)

11 SIC Code

05 City

06 State

07 Zip Code

12 City

13 State

14 Zip Code

01 Name

02 D+B Number

08 Name

09 D+B Number

03 Street Address (P.O. Box, RFD #, etc.)

04 SIC Code

10 Street Address (P.O. Box, RFD #, etc.)

11 SIC Code

05 City

06 State

07 Zip Code

12 City

13 State

14 Zip Code

III. PREVIOUS OWNER(S) (List most recent first)

IV. REALTY OWNER(S) (If applicable, list most recent first)

01 Name  
Carborundum Corp.

02 D+B Number

01 Name

02 D+B Number

03 Street Address (P.O. Box, RFD #, etc.)  
Buffalo Avenue

04 SIC Code

03 Street Address (P.O. Box, RFD #, etc.)

04 SIC Code

05 City  
Niagara Falls

06 State  
NY

07 Zip Code  
14302

05 City

06 State

07 Zip Code

01 Name

02 D+B Number

01 Name

02 D+B Number

03 Street Address (P.O. Box, RFD #, etc.)

04 SIC Code

03 Street Address (P.O. Box, RFD #, etc.)

04 SIC Code

05 City

06 State

07 Zip Code

05 City

06 State

07 Zip Code

01 Name

02 D+B Number

01 Name

02 D+B Number

03 Street Address (P.O. Box, RFD #, etc.)

04 SIC Code

03 Street Address (P.O. Box, RFD #, etc.)

04 SIC Code

05 City

06 State

07 Zip Code

05 City

06 State

07 Zip Code

V. SOURCES OF INFORMATION (Cite specific references, e.g., state files, sample analysis, reports)

Electro Minerals (U.S.), Inc., Niagara Falls, New York

ecology and environment

POTENTIAL HAZARDOUS WASTE SITE  
SITE INSPECTION REPORT

I. IDENTIFICATION

01 State  
NY

02 Site Number  
932048B

PART 8 - OPERATOR INFORMATION

II. CURRENT OPERATOR (Provide if different from owner)					OPERATOR'S PARENT COMPANY (if applicable)				
01 Name Electro Minerals (U.S.), Inc.		02 D+B Number		10 Name Washington Mills Abrasives		11 D+B Number			
03 Street Address (P.O. Box, RFD #, etc.) Buffalo Avenue		04 SIC Code		12 Street Address (P.O. Box, RFD #, etc.) 20 North Main Street		13 SIC Code			
05 City Niagara Falls		06 State NY	07 Zip Code 14302		14 City North Grafton		15 State MA	16 Zip Code	
08 Years of Operation 2		09 Name of Owner							
III. PREVIOUS OPERATOR(s) (List most recent first; provide only if different from owner)					PREVIOUS OPERATORS' PARENT COMPANIES (if applicable)				
01 Name Carborundum Corp.		02 D+B Number		10 Name Standard Oil of Ohio		11 D+B Number			
03 Street Address (P.O. Box, RFD #, etc.) Buffalo Avenue		04 SIC Code		12 Street Address (P.O. Box, RFD #, etc.)		13 SIC Code			
05 City Niagara Falls		06 State NY	07 Zip Code		14 City Cleveland		15 State OH	16 Zip Code	
08 Years of Operation		09 Name of Owner During This Period							
01 Name		02 D+B Number		10 Name		11 D+B Number			
03 Street Address (P.O. Box, RFD #, etc.)		04 SIC Code		12 Street Address (P.O. Box, RFD #, etc.)		13 SIC Code			
05 City		06 State	07 Zip Code		14 City		15 State	16 Zip Code	
08 Years of Operation		09 Name of Owner During This Period							
01 Name		02 D+B Number		10 Name		11 D+B Number			
03 Street Address (P.O. Box, RFD #, etc.)		04 SIC Code		12 Street Address (P.O. Box, RFD #, etc.)		13 SIC Code			
05 City		06 State	07 Zip Code		14 City		15 State	16 Zip Code	
08 Years of Operation		09 Name of Owner During This Period							
IV. SOURCES OF INFORMATION (Cite specific references, e.g., state files, sample analysis, reports)									
Electro Minerals (U.S.), Inc. files, Niagara Falls, New York									

# POTENTIAL HAZARDOUS WASTE SITE SITE INSPECTION REPORT

## PART 9 - GENERATOR/TRANSPORTER INFORMATION

### I. IDENTIFICATION

01 State  
NY

02 Site Number  
932048B

### II. ON-SITE GENERATOR

01 Name Electro Minerals (U.S.), Inc.	02 D+B Number	
03 Street Address (P.O. Box, RFD #, etc.) Buffalo Avenue	04 SIC Code	
05 City Niagara Falls	06 State NY	07 Zip Code 14302

### III. OFF-SITE GENERATOR(S)

01 Name	02 D+B Number	01 Name	02 D+B Number
03 Street Address (P.O. Box, RFD #, etc.)	04 SIC Code	03 Street Address (P.O. Box, RFD #, etc.)	04 SIC Code
05 City	06 State	07 Zip Code	

01 Name	02 D+B Number	01 Name	02 D+B Number
03 Street Address (P.O. Box, RFD #, etc.)	04 SIC Code	03 Street Address (P.O. Box, RFD #, etc.)	04 SIC Code
05 City	06 State	07 Zip Code	

### IV. TRANSPORTER(S)

01 Name Modern Disposal Services, Inc.	02 D+B Number	01 Name	02 D+B Number
03 Street Address (P.O. Box, RFD #, etc.) Model City Road	04 SIC Code	03 Street Address (P.O. Box, RFD #, etc.)	04 SIC Code
05 City Lewiston	06 State NY	07 Zip Code 14092	

01 Name	02 D+B Number	01 Name	02 D+B Number
03 Street Address (P.O. Box, RFD #, etc.)	04 SIC Code	03 Street Address (P.O. Box, RFD #, etc.)	04 SIC Code
05 City	06 State	07 Zip Code	

### V. SOURCES OF INFORMATION (Cite specific references, e.g., state files, sample analysis, reports)

Electro Minerals (U.S.), Inc. files, Niagara Falls, New York

POTENTIAL HAZARDOUS WASTE SITE  
SITE INSPECTION REPORT

I. IDENTIFICATION

01 State  
NY

02 Site Number  
932048B

PART 10 - PAST RESPONSE ACTIVITIES

II. PAST RESPONSE ACTIVITIES

01 <input type="checkbox"/> A. Water Supply Closed 04 Description:	02 Date _____	03 Agency _____
01 <input type="checkbox"/> B. Temporary Water Supply Provided 04 Description:	02 Date _____	03 Agency _____
01 <input type="checkbox"/> C. Permanent Water Supply Provided 04 Description:	02 Date _____	03 Agency _____
01 <input type="checkbox"/> D. Spilled Material Removed 04 Description:	02 Date <u>unknown</u>	03 Agency _____
01 <input type="checkbox"/> E. Contaminated Soil Removed 04 Description:	02 Date <u>unknown</u>	03 Agency _____
01 <input type="checkbox"/> F. Waste Repackaged 04 Description:	02 Date _____	03 Agency _____
01 <input checked="" type="checkbox"/> G. Waste Disposed Elsewhere 04 Description: Waste storage area cleaned up and transported by Modern Disposal.	02 Date <u>1985</u>	03 Agency _____
01 <input type="checkbox"/> H. On Site Burial 04 Description:	02 Date _____	03 Agency _____
01 <input type="checkbox"/> I. In Situ Chemical Treatment 04 Description:	02 Date _____	03 Agency _____
01 <input type="checkbox"/> J. In Situ Biological Treatment 04 Description:	02 Date _____	03 Agency _____
01 <input type="checkbox"/> K. In Situ Physical Treatment 04 Description:	02 Date _____	03 Agency _____
01 <input type="checkbox"/> L. Encapsulation 04 Description:	02 Date _____	03 Agency _____
01 <input type="checkbox"/> M. Emergency Waste Treatment 04 Description:	02 Date _____	03 Agency _____
01 <input type="checkbox"/> N. Cutoff Walls 04 Description:	02 Date _____	03 Agency _____
01 <input type="checkbox"/> O. Emergency Diking/Surface Water Diversion 04 Description:	02 Date _____	03 Agency _____
01 <input type="checkbox"/> P. Cutoff Trenches/Sump 04 Description:	02 Date _____	03 Agency _____
01 <input type="checkbox"/> Q. Subsurface Cutoff Wall 04 Description:	02 Date _____	03 Agency _____

POTENTIAL HAZARDOUS WASTE SITE  
SITE INSPECTION REPORT

PART 10 - PAST RESPONSE ACTIVITIES

I. IDENTIFICATION

01 State  
NY

02 Site Number  
932048B

II. PAST RESPONSE ACTIVITIES (Cont.)

01 ☐ R. Barrier Walls Constructed  
04 Description:

02 Date \_\_\_\_\_

03 Agency \_\_\_\_\_

01 ☐ S. Capping/Covering  
04 Description:

02 Date \_\_\_\_\_

03 Agency \_\_\_\_\_

01 ☐ T. Bulk Tankage Repaired  
04 Description:

02 Date \_\_\_\_\_

03 Agency \_\_\_\_\_

01 ☐ U. Grout Curtain Constructed  
04 Description:

02 Date \_\_\_\_\_

03 Agency \_\_\_\_\_

01 ☐ V. Bottom Sealed  
04 Description:

02 Date \_\_\_\_\_

03 Agency \_\_\_\_\_

01 ☐ W. Gas Control  
04 Description:

02 Date \_\_\_\_\_

03 Agency \_\_\_\_\_

01 ☐ X. Fire Control  
04 Description:

02 Date \_\_\_\_\_

03 Agency \_\_\_\_\_

01 ☐ Y. Leachate Treatment  
04 Description:

02 Date \_\_\_\_\_

03 Agency \_\_\_\_\_

01 ☐ Z. Area Evacuated  
04 Description:

02 Date \_\_\_\_\_

03 Agency \_\_\_\_\_

01 ☒ 1. Access to Site Restricted  
04 Description:  
Site is fenced and grounds guarded

02 Date 1987

03 Agency \_\_\_\_\_

01 ☐ 2. Population Relocated  
04 Description:

02 Date \_\_\_\_\_

03 Agency \_\_\_\_\_

01 ☐ 3. Other Remedial Activities  
04 Description:

02 Date \_\_\_\_\_

03 Agency \_\_\_\_\_

III. SOURCES OF INFORMATION (Cite specific references, e.g., state files, sample analysis, reports)

Ecology and Environment site inspection, 6/87

POTENTIAL HAZARDOUS WASTE SITE  
SITE INSPECTION REPORT

PART 11 - ENFORCEMENT INFORMATION

I. IDENTIFICATION

01 State  
NY

02 Site Number  
932048B

II. ENFORCEMENT INFORMATION

01 Past Regulatory/Enforcement Action ☐ Yes ☒ No

02 Description of Federal, State, Local Regulatory/Enforcement Action

III. SOURCES OF INFORMATION (Cite specific references, e.g., state files, sample analysis, reports)

D16





## 6. ASSESSMENT OF DATA ADEQUACY AND RECOMMENDATIONS

After assessing the information gathered for this site and applying it to an HRS worksheet, it was determined that the existing information is not adequate to accurately score the site, and that further investigations are necessary to determine a proper HRS score.

Since no sampling of any kind from the disposal area is known to have taken place, E & E recommends a screening program consisting of several soil samples collected at a depth of 2 feet from the disposal area and analyzed for priority pollutants and hazardous waste characteristics of ignitability, reactivity, corrosivity, and EP Toxicity. These data can be used to compute a more accurate HRS score.



## 7. REFERENCES

Johnston, R.H. (1964), Groundwater in the Niagara Falls Area, New York, State of New York Conservation Department, Water Resources Commission, Bulletin GW-53.

Higgins, B.A., P.S. Puglia, R.P. Leonard, T.D. Yoakum, W.A. Witz (1972), Soil Survey of Niagara County, New York, USDA Soil Conservation Service.

Advanced Environmental Systems, Inc., Investigation Prior to the Installation of the Adams Avenue Storm Sewer Analysis of Soil Samples Collected December 7, 1984, report prepared for SOHIO Electrominerals Company, December 7, 1984.

Thomsen Associates, Proposed SIC Facility, SOHIO Electro Minerals Company, Niagara Falls, New York, August 13, 1984.



APPENDIX A  
PHOTOGRAPHIC RECORD

ecology and environment, Inc.  
PHOTOGRAPHIC RECORD

Client: NYSDEC

E & E Job No.: ND2031

Camera: Make ANSCO

SN: \_\_\_\_\_



Photographer: J. Sundquist

Date/Time: 6/24/87 09:55

Lens: Type: \_\_\_\_\_

SN: \_\_\_\_\_

Frame No.: 1

Comments\*: Silicon carbide  
pile at west end of Building  
83, for eventual recycling.  
Electro Minerals (U.S.) Inc.



Photographer: J. Sundquist

Date/Time: 6/24/87 10:00

Lens: Type: \_\_\_\_\_

SN: \_\_\_\_\_

Frame No.: 2

Comments\*: Aluminum oxide  
from settling ponds on west  
side of Building 86.

\*Comments to include location

D1649

ecology and environment, Inc.  
PHOTOGRAPHIC RECORD

Client: NYSDEC

E & E Job No.: ND2031

Camera: Make ANSCO

SN: \_\_\_\_\_



Photographer: J. Sundquist

Date/Time: 6/24/87 10:05

Lens: Type: \_\_\_\_\_

SN: \_\_\_\_\_

Frame No.: 3

Comments\*: Mixed pile of


aluminum oxide and silica

carbide near west end of

Buildings 86 and 84. Note

rainwater runoff. West of

Building 82.



Photographer: J. Sundquist

Date/Time: 6/24/87 10:10

Lens: Type: \_\_\_\_\_

SN: \_\_\_\_\_

Frame No.: 4

Comments\*: Settling pond

which removes solids from

non-contact cooling water

before discharge to Niagara

River.

\*Comments to include location

D1649



ecology and environment, Inc.  
PHOTOGRAPHIC RECORD

Client: NYSDEC

E & E Job No.: ND2031

Camera: Make ANSCO

SN: \_\_\_\_\_



Photographer: J. Sundquist


Date/Time: 6/24/87 10:15

Lens: Type: \_\_\_\_\_

SN: \_\_\_\_\_

Frame No.: 5

Comments\*: Former waste storage area looking east toward Building 86. Trash has been removed, area is covered with fill.



Photographer: J. Sundquist

Date/Time: 6/24/87 10:20

Lens: Type: \_\_\_\_\_

SN: \_\_\_\_\_

Frame No.: 6

Comments\*: Photo showing H<sub>2</sub>SO<sub>4</sub> acid tank not in use at this time. Grain processing plant is in background. North of eastern end of Building 82.

\*Comments to include location

D1649


ecology and environment, Inc.  
P H O T O G R A P H I C   R E C O R D

Client: NYSDEC

E & E Job No.: ND2031

Camera: Make ANSCO

SN: \_\_\_\_\_



Photographer: J. Sundquist

Date/Time: 6/24/87 10:25

Lens: Type: \_\_\_\_\_

SN: \_\_\_\_\_

Frame No.: 7

Comments\*: Acid neutraliz-  
ing tank near grain process-  
ing plant, not in use at this  
time.

Photographer: \_\_\_\_\_

Date/Time: \_\_\_\_\_

Lens: Type: \_\_\_\_\_

SN: \_\_\_\_\_

Frame No.: \_\_\_\_\_

Comments\*: \_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

\*Comments to include location

01649

APPENDIX B

UPDATED INACTIVE HAZARDOUS WASTE  
DISPOSAL AREA REGISTRY FORM

NEW YORK STATE DEPARTMENT OF ENVIRONMENTAL CONSERVATION  
DIVISION OF SOLID AND HAZARDOUS WASTE  
INACTIVE HAZARDOUS WASTE  
DISPOSAL SITE REPORT

Priority Code: 2a Site Code: 932048B

Name of Site: Carborundum Building 82 Region: 9

Street Address: Buffalo Avenue

Town/City: Niagara Falls County: Niagara

Name of Current Owner of Site: Electro Minerals (U.S.), Inc.

Address of Current Owner of Site: Buffalo Avenue, Niagara Falls

Type of Site: ☒ Open Dump ☐ Structure ☐ Lagoon  
☒ Landfill ☐ Treatment Pond

Estimated Size: 7 acre(s)

Site Description:

Temporary storage area for sand, fly ash, fire brick, dust collector fines, kiln furniture, wood, carborundum wheels, aluminum-silica shot, and fibre prior to disposal at an approved offsite facility.

Hazardous Waste Disposed: ☐ Confirmed ☒ Suspected

Type and Quantity of Hazardous Wastes Disposed:

Type	Quantity (Pounds, Drums, Tons, Gallons)
Unknown	

Time Period Site was Used for Hazardous Waste Disposal:

Unknown, 19     To                     , 1979

Owner(s) During Period of Use: Carborundum Corp. (SOHIO)

Site Operator During Period of Use: Carborundum Corp.

Address of Site Operator: Buffalo Avenue, Niagara Falls

Analytical Data Available: ☐ Air ☐ Surface Water ☐ Groundwater  
☐ Soil ☐ Sediment ☒ None

Contravention of Standards: ☐ Groundwater ☐ Drinking Water  
☐ Surface Water ☐ Air

Soil Type: Silts, clays

Depth to Groundwater Table: Approx. 10 feet

Legal Action: Type: none ☐ State ☐ Federal

Status: ☐ In Progress ☐ Completed

Remedial Action: ☐ Proposed ☐ Under Design  
☐ In Progress ☐ Completed

Nature of Action: Stored wastes were removed to approved landfill in 1975.

Assessment of Environmental Problems:

Unknown

Assessment of Health Problems:

Unknown

Person(s) Completing This Form:

NEW YORK STATE DEPARTMENT OF  
ENVIRONMENTAL CONSERVATION

NEW YORK STATE DEPARTMENT OF HEALTH

Name:                                     

Name:                                     

Title:                                     

Title:                                     

Name:                                     

Name:                                     

Title:                                     

Title:                                     

Date:                                     

Date:

APPENDIX C

PHOTOCOPIED REFERENCES

INVESTIGATION PRIOR TO THE INSTALLATION  
OF THE ADAMS AVENUE STORM SEWER  
ANALYSIS OF SOIL SAMPLES COLLECTED  
DECEMBER 7, 1984

Report Prepared For  
SOHIO ELECTRO MINERALS COMPANY

By  
ADVANCED ENVIRONMENTAL SYSTEMS, INC.

Prepared by:

Susan M. Cerquetti  
Susan M. Cerquetti  
GC Division

David P. Mix  
David P. Mix  
Metals Division

Kathleen A. Martin  
Kathleen A. Martin  
Wet Chemistry Division

W. Joseph McDougall, for  
Leonard Borzynski  
Technical Evaluation

December 7, 1984  
AES Job ANY

### SCOPE OF WORK

~~Six~~ (6) soil samples were analyzed for parameters required by the New York State Department of Environmental Conservation, Region 9.

### COLLECTION OF SAMPLES

On Friday, November 23, 1984, Earth Dimension, Inc. collected split spoon soil samples from five locations along Adams Avenue. Mr. Donald Owens, Soil Scientist, delivered the samples directly to the AES Laboratory.



# ANALYTICAL METHODOLOGY REFERENCE LIST

Analyses were performed in accordance with some of the methods in the references listed below and as specified in the Laboratory Report.

1. EPA 600/D-80-021, "Guidelines Establishing Test Procedures for the Analysis of Pollutants; Proposed Regulations", Federal Register 44(233), December 3, 1979.
2. EPA 600/D-80-022, "Guidelines Establishing Test Procedures for the Analysis of Pollutants; Proposed Regulations, Correction", Federal Register 44(244), December 18, 1979.
3. EPA 600/4-79-020, "Methods for Chemical Analysis of Water and Wastes", (1983)
4. EPA 600/4-79-057, "Methods for Organic Chemical Analysis of Municipal and Industrial Wastewater", (1982)
5. EPA-SW-846, "Test Methods for Evaluating Solid Waste, Physical/Chemical Methods", second edition (1982)
6. "Standard Methods for the Examination of Water and Wastewater", 15th Edition, (1980)
7. New York State Institute of Toxicology Analytical Handbook, October 1982
8. NIOSH Manual of Analytical Methods, second edition 1977
9. "The Analysis of Polychlorinated Biphenyls in Transformer Fluid and Waste Oil", EPA Environmental Monitoring and Support Laboratory, draft, June 24, 1980
10. "Interim Methods for the Sampling and Analysis of Priority Pollutants in Sediments and Fish Tissue", EPA 600/4-81-055, January 7, 1983.

ADVANCED ENVIRONMENTAL SYSTEMS, INC.  
LABORATORY REPORT

=====

TYPE OF ANALYSIS: VOLATILE ORGANICS/THO SCAN  
UNITS OF MEASURE: MILLIGRAMS/KILOGRAM, OR PPM \*\*  
CLIENT:SOHIO A.E.S. JOB CODE (ANY)

-----

ANALYSIS	METHOD	REF	SAMPLE IDENTIFICATION				
			A0 BH #1 11/23/84	A1 BH #2 11/23/84	A2 BH #3 11/23/84	A3 BH #4 11/23/84	A4 BH #5 11/23/84
VINYL CHLORIDE	5030	5	<0.06	<0.06	<0.06	<0.06	<0.06
METHYLENE CHLORIDE	5030	5	<0.02	<0.02	<0.02	<0.02	<0.02
1,1 - DICHLOROETHYLENE	5030	5	<0.04	<0.04	<0.04	<0.04	<0.04
TRANS-1,2-DICHLOROETHYLENE	5030	5	<0.04	<0.04	<0.04	<0.04	<0.04
CHLOROFORM	5030	5	<0.04	<0.04	0.05	<0.04	<0.04
1,1,1-TRICHLOROETHANE	5030	5	<0.04	<0.04	<0.04	<0.04	<0.04
CARBON TETRACHLORIDE	5030	5	<0.10	<0.10	0.51	0.18	<0.10
BROMODICHLOROMETHANE	5030	5	<0.06	<0.06	<0.06	<0.06	<0.06
TRANS-1,3-DICHLOROPROPENE	5030	5	<0.04	<0.04	<0.04	<0.04	<0.04
TRICHLOROETHYLENE	5030	5	<0.03	0.18	<0.03	<0.03	<0.03
CIS-1,3-DICHLOROPROPENE	5030	5	<0.05	<0.05	<0.05	<0.05	<0.05
1,1,2-TRICHLOROETHANE	5030	5	<0.05	<0.05	<0.05	<0.05	<0.05
DIBROMOCHLOROMETHANE	5030	5	<0.08	<0.08	<0.08	<0.08	<0.08
BROMOFORM	5030	5	<0.26	<0.26	<0.26	<0.26	<0.26
TETRACHLOROETHYLENE	5030	5	<0.03	0.11	0.04	<0.03	<0.03
1,2,2-TETRACHLOROETHANE	5030	5	<0.10	<0.10	<0.10	<0.10	<0.10
DICHLOROBENZENES (ISOMERS)	5030	5	<0.07	<0.07	<0.07	<0.07	<0.07
THO SCAN	*	7	<0.22	<0.22	<0.23	<0.25	<0.20

\*SAMPLE WAS EXTRACTED ACCORDING TO "MODIFIED NIELSON-KRYGER STEAM DISTILLATION" AND ANALYZED ACCORDING TO "TOTAL CHLORINATED HYDROCARBONS"

\*\* Reported on dry weight basis

ADVANCED ENVIRONMENTAL SYSTEMS, INC.  
LABORATORY REPORT

=====

TYPE OF ANALYSIS: VOLATILE ORGANICS/THO SCAN  
UNITS OF MEASURE: MILLIGRAMS/KILOGRAM, OR PPM  
CLIENT: SOHIO A.E.S. JOB CODE (ANY)

-----

ANALYSIS	METHOD	REF	SAMPLE IDENTIFICATION
----------	--------	-----	-----------------------

A5  
FIELD DUP. 11/23/84

VINYL CHLORIDE	5030	5	<0.06
METHYLENE CHLORIDE	5030	5	<0.02
1,1 - DICHLOROETHYLENE	5030	5	<0.04
TRANS-1,2-DICHLOROETHYLENE	5030	5	<0.04
CHLOROFORM	5030	5	0.08
1,1,1-TRICHLOROETHANE	5030	5	<0.04
CARBON TETRACHLORIDE	5030	5	0.11
BROMODICHLOROMETHANE	5030	5	<0.06
TRANS-1,3-DICHLOROPROPENE	5030	5	<0.04
TRICHLOROETHYLENE	5030	5	<0.03
CIS-1,3-DICHLOROPROPENE	5030	5	<0.05
1,1,2-TRICHLOROETHANE	5030	5	<0.05
DIBROMOCHLOROMETHANE	5030	5	<0.08
BROMOFORM	5030	5	<0.26
TETRACHLOROETHYLENE	5030	5	0.04
1,1,2,2-TETRACHLOROETHANE	5030	5	<0.10
DICHLOROBENZENES (ISOMERS)	5030	5	<0.07
THO SCAN	*	7	<0.23

ADVANCED ENVIRONMENTAL SYSTEMS, INC.  
LABORATORY REPORT

=====

TYPE OF ANALYSIS: RESULTS - WET CHEMISTRY  
UNITS OF MEASURE: MILLIGRAMS/LITER, ORPPM  
CLIENT: SOHIO A.E.S. JOB CODE (ANY)

-----

ANALYSIS	METHOD	REF	SAMPLE IDENTIFICATION				
			A0 BH #1 11/23/84	A1 BH #2 11/23/84	A2 BH #3 11/23/84	A3 BH #4 11/23/84	A4 BH #5 11/23/84
PHENOLS	420.1	3	2.6	0.98	< 0.01	< 0.01	1.0
PERCENT SOLIDS*	160.3	3	87.1	91.7	91.5	87.4	91.4

\* REPORTED ON A DRY  
WEIGHT BASIS

ADVANCED ENVIRONMENTAL SYSTEMS, INC.  
LABORATORY REPORT

=====

TYPE OF ANALYSIS: RESULTS - WET CHEMISTRY  
UNITS OF MEASURE: MILLIGRAMS/LITER, OR PPM  
CLIENT:SOHIO                      A.E.S. JOB CODE (ANY)

-----

ANALYSIS

METHOD    REF

SAMPLE IDENTIFICATION

-----

A5  
FIELD DUP.  
11/23/84

-----

PHENOLS	420.1	3	< 0.01
PERCENT SOLIDS*	160.3	3	86.8

\* REPORTED ON A DRY  
WEIGHT BASIS

ADVANCED ENVIRONMENTAL SYSTEMS, INC.  
LABORATORY REPORT

=====

TYPE OF ANALYSIS: RESULTS - METALS  
UNITS OF MEASURE: MILLIGRAMS/KILOGRAM, DRY WT.  
CLIENT: SOHIO                      A.E.S. JOB CODE (ANY)

-----

ANALYSIS

METHOD    REF

SAMPLE IDENTIFICATION

-----

A0	A1	A2	A3	A4
BH #1	BH #2	BH #3	BH #4	BH #5
11/23/84	11/23/84	11/23/84	11/23/84	11/23/84

-----

TOTAL MERCURY (IN TRIPLE)      7471      5

ALIQUT #1	<u>1.4</u>	<0.5	<u>1.5</u>	<0.5	<0.5
ALIQUT #2	1.0	<0.5	1.9	<0.5	<0.5
ALIQUT #3	1.4	<0.5	1.7	<0.5	<0.5
AVERAGE	1.3	<0.5	1.7	<0.5	<0.5

ADVANCED ENVIRONMENTAL SYSTEMS, INC.  
LABORATORY REPORT

=====

TYPE OF ANALYSIS: RESULTS - METALS  
UNITS OF MEASURE: MILLIGRAMS/KILOGRAM, DRY WT.  
CLIENT: SOHIO                      A.E.S. JOB CODE (ANY)

-----

ANALYSIS

METHOD    REF

SAMPLE IDENTIFICATION

-----

A5  
FIELD DUP.  
11/23/84

-----

TOTAL MERCURY (IN TRIPLE)	7471	5	
ALIQUOT #1			<0.5
ALIQUOT #2			<0.5
ALIQUOT #3			<0.5

ADVANCED ENVIRONMENTAL SYSTEMS, INC.  
LABORATORY REPORT

=====

TYPE OF ANALYSIS:VOLATILE ORGANICS/THO SCAN  
UNITS OF MEASURE:MILLIGRAMS/KILOGRAM, PPM  
CLIENT: SOHIO A.E.S. JOB CODE (ANY)

-----

ANALYSIS	SAMPLE	ORIGINAL CONC.	DUPL. CONC.	AVERAGE CONC.	RANGE	REL. % DIFF.	*
VINYL CHLORIDE	A0	<0.06	<0.06	NA**	NA	NA	NA
METHYLENE CHLORIDE	A0	<0.02	<0.02	NA	NA	NA	NA
1,1-DICHLOROETHYLENE	A0	<0.04	<0.04	NA	NA	NA	NA
TRANS-1,2-DICHLOROETHYLENE	A0	<0.04	<0.04	NA	NA	NA	NA
CHLOROFORM	A0	<0.04	<0.04	NA	NA	NA	NA
1,1,1-TRICHLOROETHANE	A0	<0.10	<0.10	NA	NA	NA	NA
CARBON TETRACHLORIDE	A0	<0.06	<0.06	NA	NA	NA	NA
BROMODICHLOROMETHANE	A0	<0.04	<0.04	NA	NA	NA	NA
TRANS-1,3-DICHLOROPROPENE	A0	<0.03	<0.03	NA	NA	NA	NA
TRICHLOROETHYLENE	A0	<0.05	<0.05	NA	NA	NA	NA
CIS-1,3-DICHLOROPROPENE	A0	<0.05	<0.05	NA	NA	NA	NA
1,1,2-TRICHLOROETHANE	A0	<0.08	<0.08	NA	NA	NA	NA
DIBROMOCHLOROMETHANE	A0	<0.26	<0.26	NA	NA	NA	NA
BROMOFORM	A0	<0.03	<0.03	NA	NA	NA	NA
TETRACHLOROETHYLENE	A0	<0.10	<0.10	NA	NA	NA	NA
1,1,2,2-TETRACHLOROETHANE	A0	<0.07	<0.07	NA	NA	NA	NA
CHLOROBENZENES (ALL ISOMERS)	A0	<0.22	<0.22	NA	NA	NA	NA
THO SCAN							

\* RELATIVE % DIFFERENCE  
RANGE/AVERAGE X 100  
\*\*NA - NOT APPLICABLE



ADVANCED ENVIRONMENTAL SYSTEMS, INC.  
LABORATORY REPORT

=====

TYPE OF ANALYSIS:VOLATILE ORGANICS/THO SCAN  
UNITS OF MEASURE:MICROGRAMS/LITER, PPB  
CLIENT: SOHIO A.E.S. JOB CODE (ANY)

-----

ANALYSIS	TYPE	ORIGINAL CONC.	ADDED CONC.	EXPECTED CONC.	REPORTED CONC.	PERCENT RECOVERY	95% CONFIDENCE INTERVAL
L DANE	R. SPK	997	NONE	997	837	84.0	285-168
VINYI. CHLORIDE	A0	<3.10	18.39	18.39	15.67	85.2	9.8-25.
1,1-DICHLOROETHYLENE	A0	<1.80	13.81	13.81	12.72	92.1	11.2-18.
CHLOROFORM	A0	<1.82	13.83	13.83	16.36	118.3	11.3-18.
TRICHLORETHYLENE	A0	<1.37	12.52	12.52	12.28	98.1	9.3-14.
TETRACHLOROETHYLENE	A0	<1.66	11.80	11.80	13.15	111.4	8.0-14.

ADVANCED ENVIRONMENTAL SYSTEMS, INC.  
LABORATORY REPORT

=====

TYPE OF ANALYSIS: TEST CONTROLS - WET CHEMISTRY  
UNITS OF MEASURE: MILLIGRAMS/KILOGRAM, OR PPM  
CLIENT: SOHIO A.E.S. JOB CODE (ANY)

-----

ANALYSIS	TYPE	ORIGINAL CONC.	ADDED CONC.	EXPECTED CONC.	REPORTED CONC.	PERCENT RECOVERY	95% CONFIDENCE INTERVAL
PHENOLS	A2-SPK	<0.01	50	50	45.3	90.6	NOT APPLICABLE

recycled paper

C-13

ecology and environment

ADVANCED ENVIRONMENTAL SYSTEMS, INC.  
LABORATORY REPORT

=====

TYPE OF ANALYSIS: TEST CONTROLS - METALS  
UNITS OF MEASURE: MICROGRAMS/LITER, OR PPB  
CLIENT: SOHIO A.E.S. JOB CODE (ANY)

-----

ANALYSIS	TYPE	ORIGINAL CONC.	ADDED CONC.	EXPECTED CONC.	REPORTED CONC.	PERCENT RECOVERY	95% CONFIDENCE INTERVAL
MERCURY	EPA	8.7	NONE	8.7	9.8	112.6	5.9-11.1
MERCURY	A0-SPK	2.7	10.0	12.7	14.1	111.0	NONE
MERCURY	A1-SPK	<1.0	10.0	10.0	11.4	114.0	NONE
MERCURY	A2-SPK	3.3	10.0	13.3	14.1	106.0	NONE
MERCURY	A3-SPK	<1.0	10.0	10.0	10.2	102.0	NONE
MERCURY	A4-SPK	<1.0	10.0	10.0	9.2	92.0	NONE
MERCURY	A5-SPK	<1.0	10.0	10.0	9.6	96.0	NONE

NOTE: CONCENTRATIONS ARE  
REPORTED IN PPB, AS PRE-  
SENT IN LIQUID DIGESTED  
SAMPLES DURING ANALYSIS

ADVANCED ENVIRONMENTAL SYSTEMS, INC.  
LABORATORY REPORT

=====


TYPE OF ANALYSIS: DUPLICATE-WET CHEMISTRY  
UNITS OF MEASURE: MILLIGRAMS/KILOGRAM, OR PPM  
CLIENT: SOHIO                      A.E.S. JOB CODE (ANY)

-----

ANALYSIS	SAMPLE	ORIGINAL CONC.	DUPL. CONC.	AVERAGE CONC.	RANGE	REL. % * DIFF.
PHENOLS	A2	<0.01	<0.01	NA	NA	NA

\* RELATIVE % DIFFERENCE  
RANGE/AVERAGE X 100





## LEGEND

B-1 BORING DESIGNATION  
 (EL. ) SURFACE ELEVATION

BM BENCHMARK

## NOTES:

- 1.) BENCHMARK IS NORTH BONNET PUT OF HYDRANT NEAR FENCE LINE SOUTH OF PROPOSED FURNACE BUILDING/ ASSUMED ELEV. OF 100.0 FEET.
- 2.) PROFILE OF SECTION A-A IS SHOWN ON DRAWING N-3 AND THE PROFILE OF SECTION B-B IS SHOWN ON DRAWING N-4.

**EMPIRE**  
SOIL INVESTIGATIONS INC.

SUBSURFACE  
INVESTIGATION PLAN

PROPOSED SIC FACILITY  
 SOHIO ELECTRO MINERALS COMPANY  
 NIAGARA FALLS, NEW YORK


DR. BY: AJK / DLP	SCALE: 1" = 80'	PROJ. NO. 57A-84-44
CK'D BY: JLR	DATE: 3-8-84	DRWG. NO. 1

# SUBSURFACE PROFILE LEGEND

STANDARD PENETRATION  
RESISTANCE ("N" VALUE)

B-1  
EL. 98.9  
(OFFSET - 9' N.)

BORING NUMBER, GROUND SURFACE  
ELEVATION AND OFFSET DISTANCE



## UNIFIED CLASSIFICATION SYMBOLS

- SP - POORLY GRADED SANDS, GRAVELLY SANDS.
- SM - SILTY SANDS, POORLY GRADED SAND-SILT MIXTURES.
- ML - INORGANIC SILTS AND VERY FINE SAND, SILTY OR CLAYEY FINE SANDS, CLAYEY SILTS OF LOW PLASTICITY.
- CL - INORGANIC CLAYS OF LOW TO MEDIUM PLASTICITY, GRAVELLY CLAYS, SANDY CLAYS, SILTY CLAYS.

## NOTE:

SUBSURFACE PROFILES ARE SHOWN ON DRAWINGS N<sup>o</sup> 3 AND 4.

**THOMSEN ASSOCIATES**

CONSULTING GEOTECHNICAL  
ENGINEERS & GEOLOGISTS

Groton • Buffalo • Rochester • Syracuse • Albany  
New York • Woodbridge • Harrisburg • Washington


PROPOSED SIC FACILITY  
SOHIO ELECTRO MINERALS COMPANY  
NIAGARA FALLS, NEW YORK

DR. BY: DLP | SCALE: 1/10 SCALE | PROJ. NO. BTA-84-44  
CK'D. BY: J.D. | DATE: 8-13-84 | DRWG. NO. 2

100	95	90	85	80	75	70	65	60	55	50	45	40	35	30	25	20	15	10	5	0
-----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	---	---

ELEVATION (FEET)

WEST END OF  
PROPOSED ELEVATION



100	95	90	85	80	75	70	65	60	55	50	45	40	35	30	25	20	15	10	5	0
-----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	---	---

C-19 ecology and environment

NOTES:

- A LEGEND OF TERMS AND SYMBOLS USED TO PREPARE THIS PROFILE IS PRESENTED ON DRAWING NO. 2.
- THE LOCATION OF PROFILE B-B IS SHOWN ON DRAWING NO. 1.


**THOMSEN ASSOCIATES**

CONSULTING GEOTECHNICAL ENGINEERS & GEOLOGISTS  
Gorton • Buffalo • Rochester • Syracuse • Albany  
New York • Woodbridge • Harrisburg • Washington

PROPOSED SIC FACILITY  
SOHIO ELECTRO MINERALS COMPANY  
NIAGARA FALLS, NEW YORK

DR BY: DLP  
SCALE: AS NOTED  
PROJ. NO. STA-84-44  
CKD BY: JD  
DATE: 8-15-84  
DRWG. NO. 4





SEC  
SCALE: 1" = 10' HORIZ.  
1" = 10' VERT.

NOTES:

1. LEGEND OF TERMS AND SYMBOLS USED TO PREPARE THIS PROFILE IS PRESENTED ON DRAWING N# 2.
2. THE LOCATION OF PROFILE A-A IS SHOWN ON DRAWING N# 1.

<b>THOMSEN ASSOCIATES</b>		CONSULTING GEOTECHNICAL ENGINEERS & GEOLOGISTS	
Gretton • Buffalo • Rochester • Syracuse • Albany		New York • Woodbridge • Harrisburg • Washington	
PROPOSED SIC FACILITY SOHIO ELECTRO MINERALS COMPANY NIAGARA FALLS, NEW YORK			
DR. BY: DLP	SCALE: AS NOTED	PROJ. NO. STA-84-44	
CK'D BY: J.D.	DATE: 8-13-84	DRWG. NO. 3	

