| The electronic version o | of this | file/report | should | have | the file | name: |
|--------------------------|---------|-------------|--------|------|----------|-------|
|--------------------------|---------|-------------|--------|------|----------|-------|

| Type of document . Site ? | Number . Year-M | Nonth File Year-Year or Report | name . pdf |
|--|--------------------|--|------------|
| letter | (| CorrespondenceFile | pdf |
| example: <i>letter . Site Nun</i> | ıber . Year-Mon | th CorrespondanceFileYear-Ye | ar . pdf |
| report. Hw 932053 | · 1993 - 04 | . Spec Soil Vapor Extrac Pilot Studies | pdf |
| example: report . Site Nu | mber . Year-Moi | nth . ReportName . pdf | |
| if a non-foilable site: ada | l ".nf.pdf" at end | d of file name | |

Project Site numbers will be proceeded by the following:

Municipal Brownfields - B Superfund - HW Spills - SP ERP - E VCP - V BCP - C

VOLUME I OF II

SPECIFICATION FOR SOIL VAPOR EXTRACTION PILOT STUDIES

AT

Stauffer Management Company
Niagara Falls Site
Lewiston, NY

RECEIVED

APR 1 2 1993

ENVIRONMENTAL CONSERVATION
REGION 9

Zeneca Inc.
Hanby Building, 2nd Floor
Wilmington, DE 19897

DATE: April 1, 1993

STAUFFER MANAGEMENT COMPANY NIAGARA FALLS, LEWISTON, NY PILOT TESTING

OF SOIL VAPOR EXTRACTION

TABLE OF CONTENTS

| Volume | I * * * * * * * * * * * * * * * * * * * | CONTENTS |
|----------------|---|----------|
| <u>Section</u> | n I General Conditions | Pages |
| I.A | General Scope of Work | 3 |
| I.B | Terms and Condition for Environmental Scientific, Engineering, and Consulting Services (10/10/92) | 2 |
| I.C | Waiver of Liens | 1 |
| I.D | Equal Employment Opportunity (Am 9530 Rev. 3/78 |) 2 |
| I.E | Alcoholic Beverage & Substance Abuse Policy (9870 SMC) | 1 |
| I.F | Safety Procedures for Contractors (9299 SMC) | 8 |
| | | |
| <u>Section</u> | n II Details Of Work | ٠ |
| II.A | SVE Pilot Study Work Plan | 26 |
| II.B | Tables and Logs | 52 |
| Volume | II | |
| Section | n III Appendices | |
| A. | Health And Safety Plan | 22 |
| В. | Sampling Plan | 19 |
| c. | Quality Assurance Project Plan | 41 |
| D. | M.S.D.S. | 32 |

SECTION I

GENERAL CONDITIONS

Niagara Falls Site Lewiston, NY


SECTION I.A

GENERAL SCOPE OF WORK

SPECIFICATION FOR **PILOT TESTING**FOR SOIL VAPOR EXTRACTION (SVE) SYSTEM

SECTION I.A GENERAL SCOPE OF WORK

- 1.0 Provide a Health and Safety Plan for the work.
- 2.0 Install a soil vapor extraction pilot system in four areas, A and T-4 on the Stauffer plant site and B and C on New York Power Authority property as shown on Figure E1.
- 3.0 Provide mobile equipment and manpower to perform the pilot studies including all temporary power, water, trailers, etc.
- 4.0 Provide air and soil sampling as called out in the detail specifications.
- 5.0 Provide all raw data collected from the field or laboratory in an orderly tabular form prior to preparing the final report. Final report shall give all data necessary for the final design of the soil vacuum extraction system along with a capital cost estimate for purchase and installation.
- 6.0 Provide waste handling for soil and water residuals.
- 7.0 All areas disturbed by the field pilot studies shall be returned to their original condition except for leaving the wells in place.



SECTION I.B

TERMS AND CONDITIONS FOR ENVIRONMENTAL, SCIENTIFIC, ENGINEERING, AND CONSULTING. SERVICES (10/10/92)

TERMS AND CONDITIONS FOR ENVIRONMENTAL. SCIENTIFIC, ENGINEERING, AND CONSULTING SERVICES

| Terms and Conditions agreed to this date | | | | between ST. | | | | | | | | |
|--|---------------|--------|---------------|-------------|----------|---------|---------|------------|----------|------------|-------|----|
| | , hereinafter | called | "Consultant," | and attache | ed to ar | nd made | part of | Contract N | a. and/o | r Purchase | Order | No |
| | | | | | | | | | | | | |

- 1. Contractual Relationship
 - 1.1. Consultant agrees to provide consulting engineering and professional services and other related services (the "Services") for various projects upon written requests pursuant to purchase orders (the "Purchase Orders") to be issued by Company, or its designee, in accordance with the terms and conditions set forth herein and the scope presented in Consultant's proposal dated (the "Proposal"), unless otherwise specified in writing.
 - 1.2. Consultant represents that it is fully experienced and properly qualified and licensed as necessary to perform the Work provided in the identified documents relevant to the Work (Contract Documents)
 - 1.3. Consultant represents that it knows of no obligations to any third party which will in any way limit or restrict its ability to perform Services for Company.
 - 1.4. Any other contractual agreements that Consultant has with Company shall remain in full force and effect unless specifically modified otherwise in writing between the parties.
- 2. Conduct of Work
 - 2.1 Consultant shall perform professional and other related services (heremafter referred to as the "Work") as set forth in the Contract Documents.
 - 2.2. Consultant and its subcontractors, employees, agents and invitees shall observe and comply with any and all laws, ordinances, rules and regulations of any and all governmental authorities bearing on the Work and the conduct of the Work, including, but not limited to, the Occupational Safety & Health Act of 1970, as amended, and the Fair Labor Standards Act of 1938, as amended, and Executive Order 11246, as amended (including Equal Opportunity and Nondiscrimination provisions thereof).
 - 2.3. Consultant and its subcontractors, their employees, agents and invitees shall observe and comply with any and all rules, regulations and accident prevention programs promulgated by Company for the safe, orderly and efficient conduct of the Work at Company's job site, including Company's policies covering alcoholic beverage and substance abuse and equal employment opportunity.
 - 2.4. Company may, from time to time, make changes in the Work and the provisions of these Terms and Conditions shall apply to all such changes.
 - 2.5. Consultant agrees to make all of its emptoyees available to Company on reasonable advance notice from Company. The Services shall be provided at any of Company's plant sites, or at such other locations or facilities, as may be designated by Company or agreed upon between the parties hereto.
 - 2.6. In the event the Work called for in the Contract Document necessitates the sealing of drawings or other documents by a dufy licensed engineer, then Consultant and/or a sufficient number of individual engineers employed by Consultant on the Work shall be licensed as necessary to seal drawings and documents at no additional cost to Company.
 - 2.7. Neither party shall be in breach of contract of leable to the other for damages from delays caused by any event beyond its reasonable ability to controt, including, but not limited to. Acts of God, fire, flood, accident, strike or other labor trouble, war, and acts of government. The foregoing shall not, however, be considered a waiver of either party's obligations under this Agreement and the party affected by such event shall promptly fulfill its obligations under this contract after the cessation of such event.
 - 2.8. Services which Consultant shall undertake for Company hereunder shall be in the capacity of an independent contractor and not as an employee or agent of Company.
- 3. Title to the Work
 - 3.1. Altreports, plans and specifications or other written data and information supplied to Consultant by Company or prepared by Consultant for Company as part of the Work shall remain or become the property of the Company. Consultant shall not use themor permit them to be used for other work and shall furnish them, along with all copies, to Company upon completion of the Work, or within thirty (30) days after the written request of Company therefore.
- 4. Patents/Trade Secrets
 - 4.1. All materials prepared by Consultant for Company, including any components thereof, unless specifically excepted below, shall be regarded as works made for hire by Consultant for Company. All such materials shall become the absolute property of Company upon payment by Company to Consultant. All such materials may be used by Company or any affiliated company without adottional compensation to Consultant, in the event any materials prepared by Consultant do not qualify as works made for hire under copyright laws, Consultant agrees to assign all inghts and interests to such materials, including copyrights, to Company. Consultant shall place a proper copyright notice on all materials produced under this Agreement. As defined by the copyright laws, Company shall be deemed to be the author of the copyrights, together with all rights of renewal, worldwide, of all materials developed pursuant to this Agreement.
 - 4.2. Consultant agrees to assign to Company its Interest in all discoveries and inventions conceived or reduced to practice by Consultant's employees alone or jointly with others, during the term of this Agreement, which inventions are either (i) derived from trade secrets or other information of a confidential nature transmitted to Consultant by Company during the term of this Agreement, or (ii) derived from tasks assigned by Company pursuant to this Agreement. Consultant agrees to disclose promptly and fully all discoveries and inventions belonging to Company under this Agreement and to fully assist Company at its expense, to obtain patents thereon in any and all countries. Company shall have the right to apply for patent protection on any of these discoveries and inventions and to prosecute applications for patents through attorneys and agents of its own choosing.
 - 4.3. Consultant further agrees that it shall be conclusively presumed that any patent applications within this Agreement related to Company's commercial, developmental or experimental products or Company's trade secrets or confidential information, which may be filed within one year after termination or expiration of the term of this Agreement by Consultant or any of its employees, shall belong to Company, and Consultant further agrees to assign (or obtain the assignment of) the same to Company, as having been conceived or reduced to practice during the term of this Agreement and to fully assist Company, at its expense, to obtain patents thereon in any and all countries.
 - 4.4. Consultant agrees that it shall only assign employees to perform consulting services for Company pursuant to this Agreement who have agreed to assign to Company all inventions which are the subject of this paragraph 4, and who have acknowledged this Agreement in writing.
 - 4.5. Consultant agrees not to include in its designs, plans, or specifications furnished as part of the Work any methods, processes, equipment or inventions which are covered or claimed by any patent or pending patent application or, which to its knowledge, constitute confidential information or trade secrets and Consultant further agrees to indemnify, defend and save Company (including officers, directors, employees, and agents of Company) harmless from and against all claims, royalties, damages, liabilities, costs and expenses of whatever kind or nature (including, but not limited to, attorneys' fees in any manner resulting from, or claimed to result from, any such inclusion).
 - 4.6. The provisions of Article 4.1. shall not apply to designs, plans, or specifications furnished by Company or to any method, process, equipment or invention designated by Company for inclusion in the Work.
- 5. Confidential Information
 - 5.1. Consultant shall treat as confidential all information relating to Company's processes, products, compositions, machinery, apparatus or trade secrets or relating to Company's premises or Company's operations or the general business affairs of Company or other information which Consultant may observe or which may be disclosed to it by Company in connection with the Services hareunder, as well as all information developed by Consultant hereunder.
 - Consultant shall not divulge said information to others, including, but not limited to, affiliates of Consultant, for any reason or at any time, except with the prior written consent of Consultant shall not in any way or at any time use said information except as required for the proper performance of the Work. Consultant agrees to restrict access to all information disclosed by Company or developed by Consultant hereunder within Consultant's organization to only such limited group of authorized employees who (i) require such information inconnection with Consultant's activities as comemplated by this Agreement and (ii) have agreed with Consultant to maintain the confidential nature of such information. Excluded from the provisions of this Article shall be such portions of the information as:
 - (a) were known to Consultant without restriction of confidentiality prior to their disclosure by Company or observation by Consultant, as demonstrated by competent documentary evidence in Consultant's possession;
 - (b) properly become available to Consultant, under conditions which do not restrict further disclosure, from a third party source who shall not have obtained such information either directly or indirectly from Company or its affiliates; or
 - (c) are at the time of disclosure in the public domain or, after disclosure, come into public domain without fault on the part of Consultant or its employees.
 - 5.2. No information relating to the Work shall be released by Consultant for publication, advertising, or any other purpose without the prior written approval of Company.
 - 5.3. Consultant shall return to Company all documentation which embodies or reflects any of the information described in Anticle 5. 1, above (including all copies thereof) within 30 days after completion of the Work, or 30 days after the date of Company's written request therefore, except as expressly authorized by Company, Consultant shall not copy any documents furnished to Consultant hereunder.
- 6. Employees and Subcontractors
 - 6.1. Consultant shall not subcontract any portion of the Work without prior written approval of Company. No such approval shall relieve Consultant from any of its obligations pursuant to this Agreement and Consultant shall continue to be primarily responsible to Company for all portions of the Work whether or not subcontracted by it.
 - 6.2. Consultant shall bind, in a manner acceptable to Company, its employees and subcontractors, if any, to all of the provisions of Articles 2, 3, 4, 5, 7, 11, and 13 hereunder.

7 Indemnification

7.1. Consultant agrees to indemnify, defend, and save Company (including officers, directors, employees, and agents of Company) harmless from and against any and all losses, damages, expenses (including attorney's fees), claims, suits, and liabilities based upon damage to, or destruction of, any property or injury (including death) to any person arising out of or attributable to the performance or to the independent of the Work or to the errors, omissions, or negligent acts by Consultant hereunder (including, but not limited to, Consultant's employees, subcontractors or agents), except for such injuries or damages which are caused solely by the negligence of Company.

8. Insurance

- 8.1. Prior to commencement of the Work, Consultant shall furnish Company insurance certificate(s) evidencing that it maintains the following coverages:
 - (a) Worker's Compensation, with minimum statutory limits; Employer's Liability, with minimum limits of \$500,000 each injury/occupational disease.
 - (b) Comprehensive General Liability: Products/Completed Operations, Contractual and Independent Contractors with minimum limits of \$2,000,000 each occurrence, combined single limit, Personal Injury and Property Damage.
 - (c) Comprehensive Automobile Liability, with minimum limits of \$1,000,000 combined single limit, each occurrence, Personal trijury and Property Damage.
 - (d) Engineer's Professional Liability ("Errors and Omissions"), with minimum limits of \$2,000,000 each occurrence/\$2,000,000 aggregate.
 - (e) Engineer's Poliution Liability Insurance with minimum limits of \$2,000,000 each occurrence/\$2,000,000 aggregate.
- 8.2. The Certricate of Comprehensive Liability Insurance shall cite and insure (specifically, or by noting existence of "Blanket Contractual" provisions included on policy) the indemnification provision set forth in Article 7.1. above:
- 8.3. Company shall be named as additional insured on Consultant's Comprehensive General Liability and Comprehensive Automobile Liability insurance policies.
- 8.4. The Certification of Consultant's Professional Elability Insurance shall one and insure (specifically, or by noting existence of "Blanket Contractual" provisions included on policy) the indemnification provision set forth in Article 7.1, above. This coverage shall be continued for a period of not less than three years from the date of completion of Consultant's services hereunder.
- 6.5. All insurance Certificate(s) shall specify the date(s) when such assurance expires and shall provide further that Company shall be given not less than ten days' written notice before cancellation of or any material change in such insurance. A Renewal Certificate(s) must be furnished to Company not less than ten days prior to the expiration date of any policies noted therein.
- 8.6. Said insurance coverage shall be written by companies satisfactory to Company.
- 6.7. The failure to comply, or the full compliance, with all of the insurance previsions herein shall in no way act to relieve Consultant from its obligation of indemnification to Company provided in Article 7.1.

9. Taxes

- 9.1. Consultant and its subcontractors shall show any applicable sales and/or use taxes separately on all invoices submitted for payment.
- 9.2. All taxes, whether local, state or federal, imposed upon this Agreement or any sums paid hereunder shall be the responsibility of Consultant,

10 Payments

- 10.1. For the Services to be performed hereunder, Company agrees to remourse Consultant in accordance with the rates and discounts set forth in the Proposal
- 10.2 Company further agrees to reimburse Consultant for all ordinary and reasonable travel and other expenses incurred upon its behalf when authorized by Company. Such expenses shall be confirmed by appropriate receipts.
- \$40.3. Expenses properly chargeable to the Services shall include: Travel and Living Expenses when away from their home office on business connected directly with the project, duplicating and reproduction costs, commercial communications in excess of \$1.00 per item, including Long Distance Telephone. Telecopy, Postage and Shipping Costs, Computer and Record Processing Time and Software. Professional and Technical Subcontractors, identifiable Drafting and Stenographic Supplies, Expendable Materials, and other items purchased specifically for the project.
- 10.4. Invoices will be submitted on a monthly basis in such detail as prescribed by Company payable within forty-five (45) days thereof ("Payment Date").
- 10.5. The amounts payable to Consultant pursuant to this Article 10 shall be the sole and exclusive amounts payable to Consultant for the performance of Services hereunder
- 10.6 Payments may be withheld on account of (i) defective work not remedied, (ii) claims filed, (iii) failure of Consultant to make payment properly to any subcontractor or for labor, materials or equipment, (iv) damage to another contractor, (v) unsatisfactory prosecution of the Work by Consultant, or (vi) charges deemed inappropriate by Company.
- 10.7. Proposals for solloring or quoting work are at the sole expense of Consultant for which there will be no reimbursement by Company.
- 10.8. If the Work includes preparation and submittal of narrative reports to Company, Company will reimburse Consultant only for completion to the satisfaction of Company of two draft submittals and one final copy. Work in this regard by Consultant, required to satisfy Company, is at the discretion of Company. Report work by Consultant which is judged by Company to require more than two draft submittals and a final report, shall be at the expense of Consultant and Consultant shall be subject to backcharging by Company for Company's time and expenses to satisfy Company report requirements, such backcharges being at Company's prevailing rate at the time.

11. Records

11.1. Consultant shall without further compensation maintain accurate records of all reimbursable costs, and such records shall be open to inspection and audit by Company within normal business hours during the term of its Agreement and for a period of three years after its conclusion or termination.

12, Term

- 12.1 The initial term of this Agreement shall be for a period of one year commencing as of the date hereof. At the conclusion of such initial term, this Agreement shall automatically renew for an additional one-year term, unless terminated by Company oursuant to Article 15 herein or Consultant gives prior written notice of its intention not to renew at least one hundred twenty (120) days prior to the conclusion of the then current term.
- Nonwaiver of Default
 - 13.1. Any failure by Company at any time, or from time to time, to enforce any of the terms and conditions of this Agreement shall not constitute a waiver of such terms and conditions in any way, or the right of Company at any time to avail itself of such remedies as it may have for any breach of such terms and conditions.
- 14. Assignment
 - 14.1. Consultant shall not assign any of its rights, duties or obligations under this Agreement, except upon the prior written consent of Company, and any attempted assignment by Consultant shall be null, void, and without effect.
- 15. Termination or Suspension of the Work
 - 15.1. Company reserves the right to terminate this Agreement for any reason with or without cause at any time during the term of this Agreement by giving notice to Consultant.
 - 15.2. Company reserves the right to temporarily suspend all or any part of the Work at any time with or without cause. In such event, Consultant shall be reimbursed, without markup for profit and overhead, only for such extra out-of-pocket expenses that Consultant actually incurs as a result of such suspension.
 - 15.3. Company shall have the right to immediately terminate this Agreement for breach in the event Consultant does not correct any default within 10 days after notice thereof by Company.
 - 15.4. Termination or expiration of this Agreement for any reason shall not relieve Consultant of the obligations imposed upon Consultant by the provisions of this Agreement.
 - 15.5. In the event Company elects to terminate this Agreement pursuant to Article 12, Article 13, Article 15, or Article 16 hereof, Company shall be liable to Consultant only for any costs incurred and fees for services actually and properly rendered by Consultant prior to the date written notification of termination is received. Company shall retain all rights of ownership as set forth in this Agreement.
 - 15.6. Consultant shall not delay, defer or suspend work or any portions thereof for any reason, including contractual and payment disputes, without the specific written direction and authorization of Company.
- Completeness/Severability
 - 16.1. This Agreement, the Proposal and the Purchase Orders reflect the entire understanding of Consultant and Company with respect to the Services to be performed hereunder, provided, however, that the terms and conditions comained on the reverse side of the Purchase Orders shall be of no force and effect. Terms and conditions proposed by Consultant shall be without force or effect unless expressly agreed to by Company and made part of this Agreement. Any modification of the terms of this Agreement, the Proposal or any of the Purchase Orders shall be ineffective unless in writing and signed by both parties.
 - 16.2. In the event that any provisions of this Agreement shall at any time contravene in whole or in part any applicable federal or state law, ruling or regulation, then such provision shall remain in effect only to the extent permitted under law and the remaining provisions thereof shall remain in full force and effect.
- 17. Governing Law
 - 17.1 This Agreement shall be governed by and construed in accordance with the laws of the State of Delaware.

SECTION I.C

WAIVER OF LIENS

WAIVER OF LIENS

| Stau | ffer Contract No |
|--------|--|
| Date | , 19 |
| KNO | W ALL MEN BY THESE PRESENTS: |
| | for and in consideration of the payment of the sum of (dollars) (\$) by Stauffer Management Company (uffer") the undersigned: |
| 1. | Does hereby waive and relinquish any and all claims or rights or lien it may have against any land, buildings, or structures on account of any labor, services, materials, equipment or supplies furnished in connection with the above referenced contract; |
| 2. | Does hereby agree to defend, indemnify and save Stauffer harmless from all liens, claims or demands for labor, services, materials, equipment or supplies furnished in connection with the above referenced contract by the undersigned, its subcontractors, suppliers, employees or agents (including, but not limited to, the payment to Stauffer upon demand of all costs and expenses (including attorneys' fees) incurred by Stauffer in the defense, release or settlement of any such lien, claim or demand). |
| exec | ITNESS WHEREOF, the undersigned has caused this WAIVER OF LIEN to be uted by its duly authorized representative on this |
| | |
| By: | |
| Title: | |

wolstf

SECTION I.D

EQUAL EMPLOYMENT OPPORTUNITY (AM 9530 Rev. 3/78)

A EQUAL EMPLOYMENT OPPORTUNITY CLAUSE applicable to contracts or orders in excess of \$19,000

- The supplier will not discriminate against any employee or applicant for employment because of race, color, religion, sex, age, or national origin. The supplier will take affirmative action to ensure that applicants are employee, and that employees are treated during the applications are employed, and that employees are treated during thoughout without regard to their race, color, religion, sex, age, or national origin. Such action shall include, but not be limited to the following, employment, upgrading, demotion, or transfer, recruitment or recruitment advertising; tayoff or termination, rates of pay or other forms of compensation, the selection for training, including apprenticeship. The supplier agrees to post in conspicuous places, available to employees and applicants for employment, notices setting from the provisions of this nondescrimination clause.
- The supplier will, in all solicitations or advertisements for employees piaced by or on behalf
 of the supplier, state that all qualified applicants with receive consideration for employment
 without regard to race, color, religion, sax, age, or national origin.
- 5. The supplier will send to each labor union or representative of workers with which it has a collective bargaining agreement or other contract or understanding, a notice, advising the labor union or workers representative of the supplier's commitments under Section 202 of Executive Order 11245, as amended, and shall post copies of the notice in conspicuous piaces available to employees and applicants for employment.
- The supplier will comply with all provisions of Executive Order 11246, as amended, and of the rules, regulations, and relevant orders of the Secretary of Labor.
- 5 The supplier certifies that it has filled with the appropriate federal agency all reports due under the applicable filling requirements, including a complete and accurate report on Standard Form 100 (EED-1) or will file such reports within 30 days after the signing of this agreement or the award of any purchase order, as the case may be, and will continue to file such reports as required.
- 6 In the event of the supplier's noncompliance with the nondiscrimination clauses of this contract or with any of said rules regulations or orders, this contract may be canceled, terminated, or suspended in whole or in pain and the supplier may be declared lineligible for further government contracts in accordance with procedures authorized in Executive Order, 11246, as amended, and such other sanctions may be imposed and remedies invoked as provided in Executive Order; 11246, as amended, or by rule, regulations, or proof of the Secretary of Labor on equal employment opportunity or as otherwise provided by law.
- 7. The supplier will include the provisions of paragraphs 1 through 7 in every subcontract of purchase order unless exempted by rules regulations, or orders of the Secretary of Labor Issued pursuant to Section 204 of Executive Order 11246, as amended, so that such provisions will be binding upon each subcontractor or vendor. The supplief will take such action with respect to any subcontract or purchase order as the contracting agency may direct as a means of enforcing such provisions including sanctions for noncompliance. Provided, however, that in the event the supplier becomes involved in, or is threatened with, illigition with a subcontractor or vendor as a result of such direction by the contracting agency, the supplier may request the United States to enter into such talgation to protect the interest of the United States.
- 8. The supplier certifies that for orders in excess of \$50,000 or it supplier has 50 or more employees. It has developed and has on file a current written affirmative action compane program for each of its establishments in accordance with the regulations of the Secretary of Labor promulgated under Executive Order 11246, as amended, or will develop such programs within 120 days after the signing of this agreement. The supplier will also require subcontractions who are not otherwise exempt to establish written affirmative action compliance programs in accordance with Executive Order 11246, as amended.

CERTIFICATION OF NONSEGREGATED FACILITIES applicable to contracts or orders in excess of \$19,000

Supplier certifies that hiddes not and will not maintain or provide for its employees any segregated facilities at any of its establishments, and that it does not and will not permit its employees to perform their services at any location, under its control, where segregated facilities are maintained. The phrase "segregated facilities" includes facilities which are in fact segregated on a basis of race, color, creed or national origin, because of explicit directive or by habit, local custom or otherwise. Supplier agrees that it will obtain identical certifications from proposed subcontractors prior to the award of subcontracts exceeding \$10,000 which are not exampt from the provisions of the Equal Employment Opportunity Clause.

C. MINORITY BUSINESS ENTERPRISE

- Utilization of Minority Business Enterprises applicable to contracts or proess in excess of \$5,000
 - it is the policy of the government that minority business enterprises shall have the maximum practicable opportunity to participate in the performance of government contracts.
 - b. The supplier agrees to use its best efforts to carry out this policy in the award of its sub-contracts to the fullest extent consistent with the efficient performance of the contract. As used in the contract: the term "Minority Business Enterprise" means at business, at least 50 percent of which is owned by minority group members or, in the case of publicity owned businesses at least 51 percent of the stock of which is owned by minority group members. For the purposes of this definition, minority group members are helpings of this definition, minority group members are helpings. Spanish-Speaking American persons, American—Orientais, American—Indians. American—Eskimos, and American—Aleuts, Suppliers may rety on written representations by subcontractors regarding their status as minority business anterprises in lieu of an independent investigation.
- Minority Business Enterprises Subcontracting Programs applicable to contracts or proefs in excess of \$500,000
 - Supplier agrees to establish and conduct a program which will enable minority business enterprises (as defined in the clause entitled "Lititization of Minority Business En-

terprises") to be considered fairly as subcontractors and suppliers under this contract. In this connection the supplier shall:

- Designate e italison officer who will administer the supplier's minority business enterprises program.
- ii. Provide adequate and timely consideration of the potentialities of known minority business enterprises in all "make-or-buy" decisions.
- iii. Assure that known minority business enterprises will have an equitable opportunity to compete for subcontracts, particularly by arranging solicitation; time for see preparation of bids, quantities, specifications and delivery schedules so as to secilitate the participation of minority business enterprises.
- W. Maintain records showing (1) procedures which have been adopted to comply with the policies set forth in this clause, including the establishment of a source list of minority business enterprises, (2) awards to minority business enterprises on the source list, and (3) specific efforts to identify and award contracts to minority business enterprises.
- enclude the Utilization of Minority Business Enterprises Clause in subcontracts
 which offer substantial minority business enterprises subcontracting opportunities.
- vf. Cooperate with the contracting officer in any studies and surveys of the supplier's minority business enterprises procedures and practices that the contracting officer may from time to time conduct.
- vii. Submit periodic reports of subcontracting to known minority business enterprises with respect to the records referred to in Subparagraph iv. above in such form and manner and at such time (not more often than quarterly) as the contracting officer may prescribe.
- b The supplier further agrees to insert, in any subcontract hereunder which may exceed \$500,000, provisions which shall conform substantially to the language of this clause, including this Paragraph b, and to notify the contracting officer of the names of such subcontractors.

D. EMPLOYMENT OF VETERANS -

applicable to contracts or orders in excess of \$19,000

- 5. Subject to the definitions contained in 41 CFR 50-250.2 the supplier to provide special amphasis to the amployment openings which exist at the time of the execution of it inscential all suitable employment openings which exist at the time of the execution of this contract and those which occur during the performance of this contract, including those not generated by this contract and including those occurring stan establishment of the supplier other than the one wherein the contract is being performed but excluding those of independent operated corporated affiliates, shall be offered for issting at an appropriate local office of the State employment service system wherein the opening occurs and to provide such reports to each local office regarding employment openings and hinss as may be required. Provided that if the contract is for less than \$10,000 or if it is with a State or local government, the reports set forth in Paragraphs 3 and 4 of this clause are not required.
- 2. Listing of employment openings with the employment service system pursuant to this clause shall be made at least concurrently with the use of any other recruitment service effort and shall involve the normal obligations which attach to the placing of a bons fide job order, including the acceptance of referrals of veterans and nonveterans. The listing of employment openings does not require the hiring of any particular job applicant or from any particular group of job applicants, and nothing herein is intended to relieve the supplier from any requirements in any Executive Orders of regulations regarding nondiscrimination in employment.
- 3. The reports required by Paragraph 1 of this clause shall include, but not be limited to, periodic reports which shall be filed at least quarterly with the appropriate local office or, when the supplier has more than one establishment in a State, with the central office of that State employment service. Such reports shall indicate for each establishment (1) the number of trid Moduals who were hired during the reporting period. (2) the number of those hired who were disabled vererans, and (3) the number who were nondisabled vererans afthe Vine number who were nondisabled vererans afthe Vine number who were nondisabled vererans afthe Vine number of the supplier shall submit a report within 30 days after the end of each reporting period wherein any performance is made on this contract. The supplier shall maintain copies of the reports submitted until the expiration of 1 year after that payment under the contract, during which time they shall be made available, upon request for examination by any authorized representative of the contracting officer or of the Secretary of Labor.
- 4. Whenever the supplier becomes contractually bound to the listing provisions of this clause, it shall advise the employment service system to each State wherein it has establishments of the name and location of each such establishment in the State. As long as the supplieris contractually bound to these provisions and has not advised the State system, there is no need to advise the State system of subsequent contracts. The supplier may advise the State system when it is no longer bound by this contract clause.
- This clause does not apply to the listing of employment openings which secur and are filed outside of the 50 States, the District of Columbia, Puerto Rico, Guerri, and the Virgin Islands.
- 8. This clause does not apply to openings which the supplier proposes to fill from within its own organization or to fill pursuant to a customany and traditional employer—union hising arrangement. This exclusion does not apply to a particular opening once an employer decides to consider applicants outside of its own organization or employer—union arrangement for that opening.
- if the supplier does not have a current written affirmative action program pursuant to this
 section at each of its establishments having 50 or more employees, the undersigned supplier agrees to develop and maintain such programs in accordance with 41 CFR 60-250 at
 each establishment within 120 days after the receipt of any contract or purchase order in
 the amount of \$50,000 or more.

- E. AFFIRMATIVE ACTION FOR HANDICAPPED WORKERS applicable to contracts or orders in the amount of \$2,500 or more
 - 1. The supplier will not discriminate against any employee or applicant for employment because of physical or mental handicap in regard to any position for which the employee or applicant for employment is qualified. The supplier agrees to take affirmative action to employ, advance in employment and otherwise treat qualified handicapped includings without discrimination based upon their physical or mental handicap in all employment practices such as the following employment, upgracing, demotion or transfer, recruitment or recruitment adventising, layoff or termination, rates of pay or other forms of compensation, and selection for training including apprenticeship.
 - 2. The supplier agrees that, if it has established an internal review procedure and a handicapped individual files a complaint with the supplier under that procedure that it is not complying with the requirements of the Act, it will (1) investigate the complaint and taxe appropriate action consistent with the requirements of 20 CFR 741.27, and (2) maintain on file for three years the record regarding the complaint and the actions taken.
 - 3. The supplier agrees that, if a handicapped individual files a complaint with the Department of Labor that it has not compiled with the requirements of the Act, (1) it will cooperate with the Department in its investigation of the complaint, and (2) it will provide all pertinent information regarding its employment practices with respect to handicapped includiduals.
 - The supplier agrees to compty with the rules and regulations of the Secretary of Labor in 20 CFR Ch VI, Part 741.

| FIRM PONTO AND ALBUM | |
|----------------------|--|
| FIRM/COMPANY NAME | |
| | |
| | |

SIGNATURE OF AUTHORIZED REPRESENTATIVE

- In the event of the supplier's noncompliance with the requirements of this clause, the supplier may be declared in default and sanctions may be imposed in accordance with 20 CFR. Ch VI. Part 741
- 5. This clause shall be included in all subcontracts of \$2,500 or more
- 7. The supplier agrees to permit the examination by appropriate contracting agency officials or the Assistant Secretary for Employment Standards or the designee, of perfinent books, documents, papers, and records concerning its employment and advancement of handicapped individuals.
- 8. The supplier agrees to post in conspicuous places, available to employees and applicants for employment, notices in a form to be prescribed by the Assistant Secretary for Employment Standards, provided by the contracting officer stating supplier's obligation under the law to take affirmative action to employ and advance in employment qualified transicapped employees and applicants for employment and the rights and remedies available.
- 9. The supplier will notify each labor union or representative of workers with which it has a collective bargaining agreement or other contract understanding that the supplier is bound by the terms of Section 503 of the Rehabilitation Act and is committed to take affirmative action to employ and advance in employment physicatry and mentally handicapped includuss.
- 10. If the supplier does not have a current written affirmative action program pursuant to this section at each of its establishments having 50 or more employees, the supplier agrees to develop and maintain such programs in accordance with 41 CFR 60-741 at each establishment within 120 days after the receipt of any contract or purchase order in the amount of \$50,000 or more.

| | | |
|------------------------------|---|------|
| DATE | - | |
| | | |
| | | |
| PRINT OR TYPE NAME AND TITLE | | |

SECTION I.E

ALCOHOLIC BEVERAGE & SUBSTANCE ABUSE POLICY (9870 SMC)

ALCOHOLIC BEVERAGE AND SUBSTANCE ABUSE POLICY

Contractor/Vendor shall disseminate to its employees, agents and subcontractors the following text of the Stauffer Management Company (referred to as "SMC") Substance Abuse Policy as follows and require such persons and their employees to abide by the terms of such policy:

The SMC is vitally concerned with the safety and well-being of the employees of its contractors. Therefore, it is important for you to be aware of the SMC's policy regarding alcoholic beverages and controlled substances:

The use, possession, sale, transfer, or purchase of alcoholic beverages and controlled substances on the work site is prohibited.

"The work site" means any property or facility under the control of the SMC wherever located, including land, buildings, structures, installations, cars and trucks.

"Controlled substances" means any drug or other ingestible, inhalable, or injectable substance the use, sale or possession of which is prohibited or restricted by law except drugs prescribed for the user by a licensed physician.

"Use" means ingesting, inhaling, or injecting alcoholic beverages or controlled substances either during the time an individual is present on the work site or within such time prior to entering upon or returning to that his or her coordination, visual perception, or reaction time is, or is likely to be, affected by such beverage or substance.

Entry onto the work site constitutes consent to inspection of the individual's person and his or her personal effects upon entering or while remaining present on the work site. Any individual who is found in violation of this Substance Abuse Policy or who refuses to permit inspection is subject to be removed and barred from the work site at the discretion of the SMC.

| AGREED TO: | |
|------------|--------------|
| | Company Name |
| BY: | |
| TITLE: | |
| DATE: | |
| P.O.#: | |

9870SMC

SECTION I.F

SAFETY PROCEDURES FOR CONTRACTORS (9299 SMC)

SAFETY PROCEDURES FOR CONTRACTORS

I. POLICY

It is the policy of Stauffer Management Company ("SMC") to provide the safest possible work environment at the site. The SMC expends much time and effort to eliminate hazards and reduce accidents. Contractors must recognize this policy and extend it to all Contractor Personnel by establishing a sound safety program and complying with applicable standards and regulations. In addition, prior to the commencement of any work on SMC property, Contractors shall be responsible for (i) notifying all Contractor Personnel of the rules listed here, (ii) having all Contractor Personnel abide by these rules and (iii) exercising good judgement to avoid accidents and hazards. The Construction Manager will act as liaison between the Contractors and the SMC, and any questions that arise can be answered through him.

IT IS UNDERSTOOD THAT THE CONSTRUCTION MANAGER'S OPINION, ACT OR APPROVAL IN NO WAY RELIEVES CONTRACTORS OF THEIR RESPONSIBILITIES UNDER THESE SAFETY RULES AND SHALL NOT RESULT IN THE SMC ASSUMING ANY LIABILITY EITHER JOINTLY OR SEVERALLY FOR CONTRACTORS' FAILURE TO MEET THEIR RESPONSIBILITIES HEREUNDER.

II. <u>DEFINITIONS</u>

"Contractor Personnel" shall mean the Contractor, Subcontractors, and the employees and agents of the Contractor and Subcontractors.

"Construction Manager" shall mean the SMC representative who has responsible charge for the construction, activity or project.

"Safety Supervisor" shall mean the competent person designated by the Contractor to be responsible for safety.

III. <u>INTRODUCTION</u>

A. In addition to the rules set forth below, Contractors shall fully comply and insure that all Contractor Personnel comply with all applicable standards of the Occupational Safety and Health Act of 1970, as amended ("OSHA") and all safety codes, laws or ordinances established by any public authority.

B. Contractor shall supply the SMC Construction Manager with a copy of any variances issued by OSHA to Contractor or any of his Subcontractors.

IV. CONTRACTOR'S SAFETY PROGRAM

- A. Contractor shall designate a Safety Supervisor and, in writing, inform the Construction Manager of the Safety Supervisor's name and where he may be contacted in case of emergency.
- B. The Safety Supervisor shall meet with the Construction Manager or the SMC Safety Representative prior to the commencement of any work to review and discuss safety, fire, medical and other emergency procedures. Contractors shall ensure all Contractor Personnel are instructed as to the appropriate action to take in case of fire, medical and other emergencies.
- C. The Safety Supervisor shall plan, supervise, and report to the Construction Manager on a program for training and instructing of all Contractors' and Subcontractors' personnel in safe practices.
- D. The Safety Supervisor shall insure that weekly formal safety inspections of the site are conducted. He shall report the results of the Safety Inspection in writing to SMC Construction Manager.
- E. The Safety Supervisor shall insure that a weekly meeting with all Superintendents and Foremen (including Subcontractors') with the following agenda is conducted.
 - 1. Review of safety inspection
 - 2. Review of accident cases and "near misses"
 - 3. Remedial actions to correct deficiencies as a result of safety inspections or accident investigations
 - 4. Work activities for coming week which require special safety precautions
 - 5. Training programs
 - 6. Miscellaneous

Additional, unscheduled safety meetings shall be held as needed.

- F. Contractor and Subcontractor shall conduct short "tool box" meetings daily with their crews concerning job specific conditions.
- G. The Contractor shall maintain the OSHA 200 Log, the log of occupational injuries and illness.

H. Contractor shall comply with the OSHA Hazard Communication Standard. Contractor shall inform the SMC of all hazardous materials brought onto the construction site and shall provide the Construction Manager with a copy of the applicable Material Safety Data Sheets as requested.

V. <u>NEW EMPLOYEES</u>

- A. The Safety Supervisor shall insure that all new employees, immediately after they are placed on the payroll, are instructed in the following:
 - 1. The SMC Basic Safety Rules and Site Safety Rules.
 - 2. Proper use of personal protective equipment required for the project.
 - 3. Location of all the potentially hazardous areas and materials at the site.
 - 4. Location of first aid and emergency equipment.
 - 5. Procedure for reporting injuries or unsafe conditions/acts.
 - 6. Emergency alarm system.
 - 7. Safe work permits and areas/jobs where they will be required.
 - 8. Smoking areas.
 - 9. Washing and eating areas.
 - 10. The Drug and Alcohol Abuse Policy.
 - 11. Evacuation Plan.
 - 12. Use, if required, of a respirator for normal, emergency, or evacuation purposes.

VI. OWNER'S INVOLVEMENT

A. The Construction Manager shall be responsible for the following:

Stauffer Management Company

- 1. Monitoring the Contractor's compliance to the safety program and the SMC Safety Procedures for Contractors.
- 2. Reporting and follow up on safety inspections.
- 3. Attending weekly meetings.
- 4. Calling special meetings if needed.
- 5. Informing Contractor of designated safe work areas/jobs and issuing safe work permits for these areas/jobs.

B. OSHA Inspections and Citations

1. Contractor shall inform SMC's Construction Manager of all OSHA inspection's and send him copies of OSHA's inspection report.

C. Accidents

1. Contractor shall send the SMC Construction Manager a copy of all accident reports concerning Contractor's and Subcontractor's personnel (OSHA Form 200, Workmen's Compensation, and similar reports, if applicable), and an accident investigation report detailing the cause of the accident and the corrective action taken to prevent a recurrence.

D. SMC Inspections .

- 1. The SMC will conduct safety inspections.
- 2. The SMC insurance carrier may conduct periodic inspections.

E. Drug and Alcohol Abuse Policy.

1. The transportation, possession, sale, distribution or use of alcohol or drugs while on the property of the SMC is prohibited. Contractors shall disseminate to its agents, employees and Subcontractors the text of the Drug and Alcohol Abuse Policy as stated and require such persons and their employees to abide by the terms of such policy.

BASIC SAFETY RULES

1. SITE SAFETY RULES

When working within the confines of the site, all workers shall become thoroughly familiar with and abide by the site's safety rules.

2. EMERGENCY ALARMS

Workers <u>must</u> become familiar with the meaning of the emergency alarm and/or siren system on the site. The Safety Supervisor will instruct the workers to their meaning and the appropriate action that must be taken in case of an emergency.

3. EMERGENCY EQUIPMENT

Every employee must know the location of all safety showers, eye wash stations, and respiratory equipment when working on the site.

4. FIRE PROTECTION

Every employee shall become familiar with the location of all fire fighting equipment. Employees shall see that the proper fire fighting equipment is readily available, in case of emergency, as the job dictates.

5. HAZARDOUS AREAS

The Safety Supervisor will instruct the workers to the location of all potentially hazardous substances, materials, and atmospheres at the jobsite. Check with him daily. Become aware of wind direction by observing the direction of flags and stack plumes.

6. SAFETY HAZARDS

Any and all unsafe acts or conditions observed by employees shall be reported to their immediate supervisor promptly. Any close-calls shall also be reported.

7. FIRST AID

Employee shall have all injuries treated immediately, by the first aid station regardless of severity.

8. ACCIDENTS

All accidents shall be reported immediately to the injured man's supervisor. The accident shall be investigated immediately, the cause determined, and where possible, the remedy applied.

9. SAFETY HATS

Approved protective helmets shall be worn at all times within the site area. No exceptions.

10. FOOT PROTECTION

Approved foot protection shall be used as required by the job.

11. RESPIRATORY PROTECTION

If respirators have been issued, they <u>must</u> be carried on the employee <u>at all times</u>.

12. EYE PROTECTION

Approved safety glasses with side shields or goggles shall be worn at all times by all employees and all visitors. Conventional frame glasses with safety lenses glasses may be worn when protected by approved safety goggles.

13. CLOTHING

Full length sleeves are recommended on all jobs.

14. CONDUCT

Practical jokes, fighting or horseplay will not be tolerated at the construction site.

15. PARKING

Park in designated areas only. Do not take your personal vehicle into the construction site. Observe all traffic signs, especially, speed limits.

16. DRUG AND ALCOHOL ABUSE POLICY

The possession, use, sale or distribution of substances of abuse or drug paraphernalia by employees while on duty or while off duty and on company property is prohibited. The possession, use, sale or distribution of alcoholic beverages is similarly prohibited. Furthermore, no employee shall report to work while in an impaired condition; such impairment may be due to substance abuse as well as substances prescribed by a licensed practitioner.

17. FIREARMS

Possession of firearms, or other weapons, at the jobsite is prohibited.

18. **SMOKING**

Smoking is permitted in designated areas only.

19. COMPRESSED AIR

Compressed air shall not be used to clean clothing or people. Horseplay by blowing air at another person is prohibited.

20. MOBILE EQUIPMENT

Employees shall not ride on trucks, or any construction equipment unless they have express permission, and then, only when seats with seat belts are provided.

21. HOISTING EQUIPMENT

Employees shall not ride any load being raised nor shall they stand under same.

I HAVE READ THE ABOVE AND AGREE TO ABIDE THEM. I FULLY UNDERSTAND THAT

FAILURE TO COMPLY WILL RESULT IN TERMINATION.

| | SIGNED: | |
|-----|---------|--|
| | | |
| 100 | DATE: | |

9299smc

SECTION II

DETAILS OF WORK

SECTION II.A

SVE PILOT STUDY WORK PLAN

TABLE OF CONTENTS

| | | <u>Page</u> |
|-------|---|-------------|
| E.1.0 | INTRODUCTION | E-1 |
| E.2.0 | | E-2 |
| | E.2.1 DESCRIPTION OF SOIL VAPOR EXTRACTION | Б. 0 |
| | AS A REMEDIAL TECHNOLOGY | E-2 |
| | E.2.1.1 General | E-2 |
| | E.2.1.2 Site-Specific Application | £-4 |
| | E.2.2 TEST OBJECTIVES OF THE SOIL VAPOR | r - |
| | EXTRACTION PILOT STUDY | £-5 |
| | E.2.3 SOIL VAPOR EXTRACTION PILOT | г |
| | STUDY DESIGN AND SCOPE OF WORK | E-D |
| | E.2.3.1 Site Location for Performing | |
| | Pilot-Scale SVE Treatability Study | |
| | E.2.3.2 Proposed Layout of SVE Test System | E-/ |
| | E.2.3.3 Operating and Maintenance Procedures | E 12 |
| | for Pilot-Scale Soil Vacuum Extraction System | E-13 |
| | E.2.4 SOIL VAPOR EXTRACTION SYSTEM | E 15 |
| | EQUIPMENT AND MATERIALS | E-13 |
| E30 | SAMPLING AND ANALYSIS FOR | • |
| E.J.0 | SOIL VAPOR EXTRACTION PILOT STUDIES | E-18 |
| | SOLE VIII ON LATIOUS VILOUIS III. | |
| E.4.0 | DATA MANAGEMENT | E-20 |
| 2.1.0 | | |
| E.5.0 | DATA ANALYSIS AND INTERPRETATION FOR THE | |
| | SOIL VAPOR EXTRACTION PILOT STUDIES | E-21 |
| | E.5.1 GENERAL | |
| | E.5.2 SOIL VAPOR EXTRACTION DATA ANALYSIS | • |
| | AND INTERPRETATION | E-21 |
| | • | |
| E.6.0 | HEALTH AND SAFETY | E-23 |
| | | |
| E.7.0 | RESIDUALS MANAGEMENT | E-24 |
| | | |
| E.8.0 | REPORTING | E-25 |


LIST OF FIGURES

| | | Following Page |
|------------|---|----------------|
| FIGURE E.1 | AREAS REQUIRING REMEDIATION | E-1 |
| FIGURE E.2 | LAYOUT OF BOREHOLES AND SVE PILOT SYSTEM | E-8 |
| FIGURE E.3 | SOIL VAPOR EXTRACTION WELL | E-9 |
| FIGURE E.4 | VACUUM MONITORING PROBE CLUSTER | E-10 |
| FIGURE E.5 | SOIL VAPOR EXTRACTION PROCESS SCHEMATIC | E-12 |
| TABLE E.1 | LIST OF TABLES SAMPLING AND ANALYSIS SUMMARY SOIL VAPOR EXTRACTION STUDY | E-18 |
| | <u>LIST OF PLANS</u> | |
| PLAN E.1 | ADDITIONAL DATA COLLECTION BOREHOLE LOCATIONS | |

E.1.0 INTRODUCTION

Presented herein are the procedures and protocols that will be implemented to conduct the Soil Vapor Extraction (SVE) Pilot Study during the design data collection phase of the Remedial Design for the Site. Procedures and protocols outlined in the SVE Work Plan will be performed in conjunction with those presented in the Health and Safety Plan (Appendix A), Sampling Plan (Appendix B) and the QAPP (Appendix C).

The SVE Pilot Study will involve the installation of one extraction well and four vapor/pressure monitoring probe cluster wells in each of the four areas of the Site identified as requiring remediation. These areas (Areas A, B, C and T-4) are shown on Figure E.1.



E.2.0 SOIL VAPOR EXTRACTION (SVE) PILOT STUDY

E.2.1 DESCRIPTION OF SOIL VAPOR EXTRACTION AS A REMEDIAL TECHNOLOGY

E.2.1.1 General

Soil vapor extraction (SVE) is a technique used to remove volatile organic compounds from the vadose or unsaturated soil zone by establishment of a pressure gradient using vapor extraction wells installed in the contaminant zone. The extraction wells can be used alone or in conjunction with air injection wells that either passively take in atmospheric air or actively use forced air injection. Advective and diffusive transport mechanisms move volatile compounds in the vapor phase from the soil to the screened extraction wells. The contaminants in the vapor phase which are drawn out of the extraction well can then be treated as required.

The feasibility of the SVE process is dependent on Site-specific conditions. Contaminant mass removal is largely a function of VOC strippability and soil air permeability. The strippability of a particular VOC is a function of its vapor pressure and phase distribution coefficients. The process is best suited for use on VOCs in permeable, well drained soils with low organic carbon content. Factors such as stratigraphy and soil heterogeneities influence the flow of air as well as the location and concentration of contaminants. These factors will have a pronounced effect on the design of the SVE system.

After the area to be treated has been defined, the extraction wells can be strategically installed such that airflow within the contaminated soil zone is maximized. The vapor extraction wells usually consist of screened pipe placed in a permeable packing. The top few feet of the well is grouted to prevent short circuited airflow from the surface. Vacuum pumps or blowers induce negative pressure in the extraction wells and induce subsurface airflow to the wells.

As the air travels through the soil, it passes through a series of pores providing the least resistance. Air that passes through pores containing contaminated vapor will remove the contaminants from the soil. As this process continues, a concentration gradient will develop and VOCs will move via gas diffusion from lower permeability soils to higher permeability soils.

The airflow draws contaminated vapors and entrained water (if present due to moisture conditions or high water table conditions) from the extraction wells to a vapor-liquid separator. In this unit, the liquid is separated and contained for treatment and vapor is advanced to a vapor treatment unit. Monitoring probes can be installed to measure the soil vapor concentrations and sampling ports can be installed in the system at many stages after extraction from the well.

The vapors are typically treated using carbon adsorption, thermal destruction, or condensation. Carbon adsorption is the most

common method and can be used to accommodate a wide range of VOC concentrations and airflow rates. Thermal destruction is also effective for a wide range of compounds. Condensation by refrigeration can be used to separate VOCs from the air. This method is most effective for high concentrations of vapors but becomes less effective as the cleanup progresses and vapor concentrations drop. When properly operated, SVE systems have demonstrated their ability for safe, continuous operation with minimal attention. Equipment used in the process can be either mobile or field constructed. Once the equipment has been mobilized and wells and probes installed, full-scale operations can usually be underway in a matter of weeks.

E.2.1.2 Site-Specific Application

Soil vapor extraction systems will be installed in four areas of the Stauffer Plant Site (Areas A, B, C and T-4) as shown on Figure E.1. The SVE systems will remove VOCs from the unsaturated overburden soil zone which is generally less than twenty feet thick at the plant Site and landfill areas. The air permeability of the overburden Site soil is expected to be relatively low, and therefore careful attention to the design and spacing of the well is required.

E.2.2 TEST OBJECTIVES OF THE SOIL VAPOR EXTRACTION PILOT STUDY

The objectives of the SVE pilot study are to determine the Site-specific air flow rates, soil air permeability, air flow distribution profiles, extraction well radius of influence, equilibrium soil vapor concentrations and contaminant removal rates. This information will be used to gauge the effectiveness of soil vapor extraction technology and to complete the final design of the full-scale system.

E.2.3 SOIL VAPOR EXTRACTION PILOT STUDY DESIGN AND SCOPE OF WORK

The SVE pilot study will consist of a one short duration standard test in each of the four areas (A, B, C and T-4). Each test will be conducted using one 15-foot deep 4-inch diameter PVC extraction well and four vapor/pressure monitoring probe cluster wells. Mobile equipment will be delivered to the Site for conducting the pilot-scale treatability study. The mobile equipment will include: vacuum pump; moisture separator; one vapor phase carbon canister; and associated piping, valves, gauges, instruments and ancillary equipment.

SVE pilot tests will be conducted and monitored for a period of two to four weeks. Monitoring will include measuring: extraction well air flow and vacuum readings; vacuum readings at the four vacuum

monitoring probe cluster wells; inlet and outlet air temperatures; FID readings of the exhaust vapor and soil gas; and barometer readings. In addition, four air samples will be collected and analyzed for VOCs using the methods described in the Sampling Plan presented in Appendix B. Spent carbon from the treatment of SVE system vapor discharge will be staged on Site pending final characterization and disposal.

Soil samples will be collected via soil borings in Areas A, B, C and T4 prior to each pilot test. It is estimated that 36 samples (plus QA/QC) in total will be taken from the four areas. These samples will be analyzed for the SSPL VOCs. The methods for collecting the samples from the soil borings are discussed in the Sampling Plan (Appendix B).

E.2.3.1 Site Location for Performing Pilot-Scale SVE Treatability Study

SVE pilot tests will be conducted in Areas A, B, C and T-4 of the Site. In Area A the test will be conducted in the northwest corner of the area, in the approximate center of the area delineated by boreholes BH5, BH6, BH8 and BH9. In Area B the test will be conducted near borehole BH31. In Area C the test will be conducted near borehole BH30. In Area T-4 the test will be conducted in the center of the area.

E.2.3.2 Proposed Layout of SVE Test System

a) Soil Boring Investigation

Two phases of drilling, soil sampling and analysis will be conducted in Areas A, B, C and T-4 of the Site as part of the SVE pilot study.

The purpose of the first phase drilling and sampling program is to collect soil samples for chemical analysis to establish baseline VOC concentrations in the soil. During the first phase, samples will also be collected to further delineate the limits of the soil remediation areas and quantify the chemical mass in these areas. This program is described in detail in Section E.3.0.

The purpose of the second phase drilling and sampling program is to replicate (to the extent possible) the first phase sampling in the immediate area of the SVE pilot test to obtain and compare analytical results of soil samples collected after the SVE test has been completed. Comparison of these data will be used to estimate the effectiveness of the SVE test in removing VOCs in a limited time frame and evaluate the overall feasibility of vapor extraction as a viable remedial technology for accomplishing and attaining target cleanup levels for soil.


Initially, each of the four pilot study areas will receive five boreholes. One for the SVE test well and four for the monitoring probe clusters.

The locations of each borehole within a pilot test area are shown on Figure E.2. During installation, continuous soil sampling will be conducted at two-foot intervals and each sample will be screened using a PID or FID to measure organic vapors. Organic vapors will be measured from each split spoon sample and from the headspace of containerized samples. The borings will extend to the groundwater table or bedrock; whichever is encountered first. Three soils samples will be collected from each of the SVE test well boreholes, one from each third of the borehole depth (e.g. 0 - 5 feet, 5 - 10 feet and 10 - 15 feet) for a total of 12 samples. One sample will also be collected from each SVE well borehole and submitted for bulk density and grain size analysis. One soil sample will also be collected from each of the monitoring probe cluster boreholes in each pilot test area (16 samples). These samples will be collected from the interval with the highest organic vapor reading. All samples will be analyzed for SSPL and VOC parameters.

After completion of the SVE pilot test in each area, an additional two boreholes will be installed in each test area; one immediately adjacent to the SVE test well and the other immediately adjacent to the monitoring probe cluster 15 feet from the SVE test well. Both borings will be within five feet of the original borings. One sample will be collected from each borehole from the depth exhibiting the highest organic vapor reading as observed in the corresponding pre-test boreholes (8 samples). All samples will be analyzed for SSPL VOC parameters.

LEGEND

- PROPOSED SOIL BORING/SOIL VAPOR EXTRACTION WELL
- A PROPOSED VACUUM MONITORING PROBE CLUSTER
- PROPOSED SOIL BORING (POST SVE TESTING)
 (AREAS A,B,C AND T-4)



NOTE:

- 1) THE SVE WELLS WILL BE PLACED NEAR BORING BH5(AREA A), BH31 (AREA B), BH30 (AREA C) AND THE CENTER OF AREA T-4.
- 2) THE NUMBERS REPRESENT THE DISTANCE IN FEET FROM THE SVE WELL
- 3) THE CONFIGURATION OF THE VACUUM MONITORING PROBE CLUSTERS MAY VARY

figure E.2

TYPICAL LAYOUT OF BOREHOLES AND SVE PILOT SYSTEM RD DATA COLLECTION PROGRAM Stauffer Management Co.

CRA


In total, 36 soil samples will be collected and analyzed during the pilot test program.

The layout of the boreholes, SVE well and vacuum monitoring probe clusters is shown on Figure E.2.

b) Vapor Extraction Well Installations

A 4-inch diameter vapor extraction well will be installed within the pilot study area to a depth of approximately 20 feet below ground surface (BGS), to bedrock or to the groundwater table; whichever is first encountered. A nominal 10-inch diameter borehole will be required to properly construct and install the well. The vapor extraction well will consist of 4-inch diameter flush joint threaded Schedule 40 PVC casing and factory slotted well screen (see Figure E.3). The well screen will be approximately 10 feet in length and consist of 0.02-inch (20 slot) factory slotted openings.

After the well is installed, a filter pack consisting of a uniformly sized clean coarse sand will be placed around the screen. A filter collar of 60 mesh silica sand will extend one foot above the well screen. A bentonite seal, at least one foot thick, will be placed above the well screen on top of the filter pack. The remainder of the annulus will be backfilled to ground surface with a cement/bentonite grout mixture.




SOIL VAPOR EXTRACTION WELL RD DATA COLLECTION PROGRAM Stauffer Management Co.

CRA

A 4-inch NPT coupling will be attached to the top of the well casing. A surface-mounted protective well cover will be placed around the top of the well head. The protective cover shall be positioned to provide a nominal 1-inch clearance between the top of the well casing and the bottom of the bolt-down coverplate of the surface-mounted protective well cover. The protective well cover will be set in concrete to form a watertight seal around the well head. A cement apron will be placed around and shaped to slope away from the protective casing to allow for drainage away from the well.

c) Vacuum Monitoring Probe Cluster Wells Installation

Four vacuum monitoring probe cluster (VMPC) wells will be installed to measure the vertical and horizontal distribution of air flow within the overburden soils during the SVE pilot study. The VMPC wells will be installed at radial distances of approximately 8, 15, 25, and 40 feet away from the extraction well. Each well cluster will be comprised of two to three individual vacuum monitoring probes depending upon the depth of overburden. These probes would be vertically spaced at approximately 5-foot depth intervals. Each probe will consist of a 1-foot section of 1-inch diameter Schedule 40 PVC slotted pipe (see Figure E.4). The top of each section of one-inch pipe will be properly fitted with a reducer coupling, a nominal 1/4-inch NPT threaded nipple, clamps, and an adequate length of Teflon tubing to extend from the top of the screen to the ground surface.



4980 (1) DEC 23/92 REV.0 (D-05)

The vacuum monitoring probes will be installed at the specified depths discussed above. These depths are based on the assumption that the bedrock or groundwater is encountered at 20 feet BGS. The actual depth intervals for the VMPC wells will be determined in the field in accordance with field conditions. A nominal 10-inch diameter borehole will be drilled for construction of each VMPC well. The deepest probe will be placed in the borehole from 16 feet to 19 feet below ground surface, or immediately above the groundwater surface. A filter pack consisting of a uniformly sized coarse sand will be placed around each VMPC screen and to at least one foot above and below the probe screen. A hydrated bentonite seal at least 1 foot thick will be placed above the sand pack. The intermediate probe will be installed by the same procedure at the 9-foot to 14-foot interval (BGS) within the borehole and the shallow probe will be installed within the 3-foot to 8-foot interval. Each Teflon tube extending to the surface from the respective monitoring screen interval will be labelled to clearly identify the depth of the probe. The top of each tube will be equipped with a stainless steel fitting compatible with a 1/4-inch NPT threaded nipple. A 1/4-inch NPT nipple and vacuum gauge transducer will be attached to these fittings to monitor vacuum response during the pilot study. These fittings will be sealed with plugs when not in use. The remaining annular space for each VMPC well borehole will be backfilled to ground surface using a cement/bentonite grout.


A surface-mounted protective well cover will be placed around the top of the VMPC well head. The protective well cover will be set in

concrete to form a watertight seal around the well head. A cement apron will be placed around and shaped to slope away from the protective casing to allow for drainage away from the well.

d) Mobile Soil Vapor Extraction Pilot Equipment

Mobile soil vapor extraction pilot equipment capable of generating a suitable range of air flow rates will be provided for the duration of the pilot study. A flow rate per well of 15 scfm at 60 inches of water vacuum has been calculated for the Site using equations derived for radial compressible flow to a vertical well. The assumed air flow permeability is 1 (Darcy) based on currently available boring log information. The flow rate calculations and equipment sizing will be revised, if necessary, based on information obtained during soil boring activities conducted as part of this pilot study and based on the variable flow rate testing conducted at the start of the test period.

This mobile unit will be equipped with a vacuum pump; moisture separator; one vapor carbon canister and piping (suction or discharge side), valves, gauges, instruments (i.e. barometer), and ancillary equipment, as needed. Based on air flow rates of up to 100 scfm, single phase 240 volt (and 40 amp) power will be required in the area where the mobile trailer is located. Water vapor collected in the moisture separator will be returned to the ground surface at the area of the SVE well after the pilot tests are completed. Spent carbon from the treatment of off-gas will be staged on Site. Figure E.5 illustrates a



4980 (1) AUG 20/92 REV.0 (C-03)

conceptual layout of the proposed SVE pilot unit. The actual design and construction will be in accordance with field conditions.

E.2.3.3 Operating and Maintenance Procedures for Pilot-Scale Soil Vacuum Extraction System

It is assumed that each SVE pilot study will be operated for a period of two to four weeks. This period was determined based on the presumption that steady state conditions for airflow through the overburden soils are reached within a few days time. Initially, the unit will be operated for short durations at various flowrates for purposes of selecting the appropriate flowrate for the remainder of the test. The test will be operated at the selected flowrate during the remainder of the first phase of the test. During the second phase of the pilot tests, the air flow rate will be lowered or stepped down, approximately 25 to 50 percent, and the change in vacuum distribution and VOC removal rate will be monitored. The systems will be operated at the lower flow rate for the remainder of the tests.

The vacuum response at each of the monitoring probes, the extraction well air flow rate and applied vacuum, the air temperature, relative vapor hydrocarbon concentrations (flame ionization detector (FID)) and barometric pressure will be monitored during the test period. These parameters will be measured in accordance with the following schedule:

- at 15-minute intervals for the first eight hours after initial startup of the system;
- daily (at 24-hour intervals) for the next four days following initial startup;
- weekly (at 7-day intervals) beginning one week after initial startup (if required); and
- at 1-hour intervals for the first eight hours after lowering the air flow rate.

Air samples will be collected from the soil vapor blower discharge line. The line will be tapped and a manually operated gas cock will be threaded into the line. A vacuum pump will be used to divert air flow from the line to the sampling equipment. The gas cock of the sample pump will then be connected to the sample portal of the field FID (OVA) for direct VOC measurement in the field.

Air samples will also be collected for laboratory analysis for VOCs in accordance with Method TO-14. Method TO-14 was used for the well gas sampling program, as described in Section 2.5, in November 1992. The results from this sampling will be used to determine the applicability of this method for sampling during SVE pilot testing. A total of 20 air samples (five from each of the four tests) will be collected for laboratory analysis in accordance with the following schedule:

- at initial startup of the SVE system;
- eight hours after initial startup of the SVE system;
- after an estimated equivalent of one pore volume of air has been extracted from the pilot zone (estimated 24 hours);

- prior to adjusting air flow rate or shutting down a test run;
- an additional sample eight hours after lowering the air flow rate.

E.2.4 SOIL VAPOR EXTRACTION SYSTEM EQUIPMENT AND MATERIALS

The SVE system to be used for performing the pilot study tests consists of an integrated arrangement of portable equipment. The main features of the system include:

- explosion proof vapor extraction blower to maintain constant flow during
 pilot tests;
- continuous data logging of eight pressure points with the ability to download data to a PC and calculate log slopes for permeability calculations;
- 30-gallon moisture separator with high level shutdown switch; and
- 55-gallon carbon canisters for treatment of off-gas.

A description of each of these components of the SVE system is provided as follows:

a) <u>Vapor Extraction Blower</u>

An explosion proof blower mounted in a frame, similar to a portable generator, with built-in flowmeter.

b) <u>Control Box</u>

This unit will connect to an electrical power supply and distribute the power to the required equipment and also provides intrinsically safe supply to a high-level switch on separator.

c) <u>Moisture Separator</u>

A 30-gallon drum with intrinsically safe high-level float switch with tap for inlet pressure transmitter.

d) Vapor Treatment Carbon Canister

Upon review of soil data from the supplemental soil sampling program the sizing and number of carbon canisters will be determined.

e) <u>Data Logger</u>

A data logger will be provided, as required, to collect time/pressure data. A typical data logger is the Lakewood four to eight point data logger. This specific logger is IBM compatible, and data can be graphed and slopes calculated to provide accurate Darcy data.

f) Pressure Transmitters

Pressure transmitters will be connected to the data logger and to some of the pressure monitoring probes to provide pressure data measurements at predetermined time intervals. A typical pressure transmitter is the Dwyer 604 Model, with appropriate pressure ranges. The pressure transmitters will be calibrated in accordance with manufacturer's specifications.

g) Hoses, Piping, Fittings, Gauges and Wires

PVC Schedule 40 piping and fittings, lightweight, flexible vacuum hose with quick-connect fittings, tubing and supplies, and connection cords, pressure gauges and flowmeters of the appropriate ranges, other accessories, as needed.

E.3.0 SAMPLING AND ANALYSIS FOR SOIL VAPOR EXTRACTION PILOT STUDIES

Table E.1 contains a sampling and analysis summary for the soil vapor extraction pilot study including the pre-SVE test boring program which is described below.

Prior to conducting the SVE pilot test, additional data will be collected to further delineate the limits of the soil remediation areas and to quantify the chemical mass in these areas. The program involves the installation of 15 perimeter boreholes to refine the limits of Areas A (9 boreholes), B (3 boreholes), and T-4 (3 boreholes). Based on the review of existing data, additional boreholes are not required for Area C. Three interior boreholes will be installed within Area A to assist in the quantification of the chemical mass in this area. The boreholes installed for the SVE pilot test wells will also be used to assist in the quantification of chemical mass in each of the areas. The locations of the boreholes are shown on Plan E.1.

All boreholes will extend to the groundwater table or bedrock; whichever is encountered first. Soil samples will be collected in 2-foot intervals continuously to the final borehole depth. Each sample will be field screened using a PID or FID to measure organic vapors. A portion of each sample will also be placed in a glass jar and headspace readings will be obtained using a PID or FID.

Revised March 17, 1993

TABLE E.1

SAMPLING AND ANALYSIS SUMMARY SOIL VAPOR EXTRACTION STUDY

| Sample Type | Location | Matrix | Number of Samples(1) | Analyses | Method |
|----------------------|---------------------|--------|----------------------|-------------------------|-----------------|
| Additional Data | Perimeter Boreholes | soil | 15 | SSPL VOC | SW846-8240 |
| Collection Boreholes | Interior Boreholes | soil | 9 | SSPL VOC | SW846-8240 |
| Pre-Test Boreholes | Central Borehole | soil | 12 | SSPL VOC | SW846-8240 |
| | Outer Boreholes | soil | 16 | SSPL VOC | SW846-8240 |
| • | | soil | 4 | Bulk Density | Weight & Volume |
| | | soil | 4 | Grain Size Distribution | ASTM D422 |
| Post-Test Boreholes | Central Borehole | soil | 4 | SSPL VOC | SW846-8240 |
| | Outer Borehole | soil | 4 | SSPL VOC | SW846-8240 |
| SVE Off-Gas | SVE Unit | gas | 20 | SSPL VOC | TO-14 |

- (1) Total of four pilot tests.
- (2) QA/QC samples for both the soil and gas matrices will be collected in accordance with the QAPP (Appendix C).

Three soil samples for chemical analyses will be collected from each of the interior boreholes used for quantification of chemical mass. The samples will be analyzed for SSPL VOCs. One sample will be selected from each third of the borehole depth (e.g. 0-5 ft, 5-10 ft, 10-15 ft). All soil samples will be collected using the protocols presented in Appendix B (Sampling Plan).

Based on the results of the organic vapor screening from samples for each perimeter borehole, a decision will be made as to whether an additional borehole is required to further define the soil remediation areas. If the organic vapor readings are relatively low in the original boring, another boring may be drilled closer to the center of the soil remediation area. If the organic vapor readings are relatively high in the original boring, another boring will be drilled further outside the soil remediation area. This process will be repeated until the soil remediation areas are sufficiently defined. One soil sample will be submitted from the first perimeter borehole at each location exhibiting relatively low organic vapor readings (total of 15 samples). The actual sample interval will be the interval exhibiting the highest potential for chemical presence based upon organic vapor screening.

At the on-set of this program, soil samples from the first three (3) of the perimeter soil borings and the first interior soil boring will be analyzed using a rapid (24 hour) turnaround. The organic vapor screening level for the remainder of the perimeter boreholes will be based upon a review of the data for the boreholes installed during the Site Investigation and also on data obtained from the rapid turnaround samples.

Sample collection, packaging and shipping, as well as methods of analysis for the pilot SVE study will be performed in conformance with the Sampling Plan (Appendix B) and QAPP (Appendix C).

E.4.0 DATA MANAGEMENT

Data management refers to the procedures for recording observations and raw data in the field or laboratory, including the use of bound notebooks, data collection sheets, and photographs. Data management for the performance of the SVE pilot study will conform with the guidelines outlined in the QAPP (Appendix C).

E.5.0 DATA ANALYSIS AND INTERPRETATION FOR THE SOIL VAPOR EXTRACTION PILOT STUDIES

E.5.1 GENERAL

Raw data collected from the SVE pilot testing will be reviewed (tabulation and validation) and analyzed and presented (tabular or graphical) in conformance with guidelines outlined in the QAPP (Appendix C). The assessment of the soil vapor extraction data will take into account the duration of each test to simulate the actual duration required for operation of a full-scale system.

E.5.2 SOIL VAPOR EXTRACTION DATA ANALYSIS AND INTERPRETATION

SVE pilot data will provide input to, and support for, numerical simulation exercises. In these numerical simulations, energy equations for vapor flow in porous media and mass transfer equations are used to size and locate extraction wells and to size mechanical equipment, including vapor treatment, for full-scale project implementation.

Equations governing flow in porous media state that induced vacuum varies logarithmically with distance from the extraction well and linearly with amount of vacuum applied. The mobile soil vapor extraction system data logger will collect pressure data over time from

various points in the system. Pressure distribution data will be plotted as a function of time on a logarithmic scale. The calculated slope of the data equals the soil permeability to vapor flow.

Raw FID and laboratory analytical data for VOCs will be presented in tabular form. Vapor readings taken at the start of the testing are representative of equilibrium vapor concentrations in the soil matrix, while readings taken after one pore volume of vapor has been removed are indicative of the longer term expected removal rates. Vapor concentrations and mass removal rates can be plotted as a function of time to establish a trend over the short duration tests. In addition, the reduction in vapor concentration over time as a function of air volume per unit mass of contamination can be plotted and compared with theoretical calculations for VOC removal based on gas laws. Interpretation of mass removal rate data as a function of varying air flow rates will allow for an assessment of the degree to which gas diffusion transport mechanisms influence full-scale design criteria and remediation time frame.

Raw soil VOC data, collected from laboratory analyses of selected soil samples taken during drilling operations, will be presented.

E.6.0 HEALTH AND SAFETY

Work related to the SVE pilot testing will be performed in accordance with the RD Health and Safety Plan (Appendix A).

E.7.0 RESIDUALS MANAGEMENT

Residuals resulting or potentially resulting from the performance of the SVE tests include drill cuttings, spent carbon and water collected in the moisture separator. All wastes will be managed in accordance with the protocols presented in Section 6.0 of the RD Work Plan. The spent carbon will be staged on Site for future disposal.

6.0 WASTE HANDLING

The following sections present the waste handling procedures that will be implemented during the design data collection phase of the remedial design, construction/implementation of the remedial systems and operation of the remedial systems.

6.1 DESIGN DATA COLLECTION PHASE

6.1.1 Soils

Soils generated by the installation of wells and boreholes will be placed back into the borehole to the extent possible. Excess soils will be placed in 55-gallon drums, characterized and disposed of off Site at an appropriate disposal facility.

6.1.2 Groundwater

6.1.2.1 Well Development and Purge Waters

Well development and purge waters will be contained in 55-gallon drums or hazmat tankers, characterized and treated either on Site or at an appropriate off-Site treatment facility.

E.8.0 REPORTING

Results of the SVE testing will be reported in the form of a technical memorandum. In addition to presenting an evaluation of effectiveness of the technology based on pilot study results, this technical memorandum will also include information regarding the general feasibility of the technology.

SECTION II.B

TABLES AND LOGS

TABLE OF CONTENTS

| Table 1 | In Situ Hydraulic Conductivity Estimates | 1 Page |
|---------|--|----------|
| Table 2 | Summary of Groundwater Elevations | 2 Pages |
| Table 3 | Summary of On Site SSPL VOC Analytical Results | 4 Reges |
| Table 4 | Soil Analytical Results VOC Compounds | 2 Pages |
| Table 5 | Soil Analytical Results BNA Compounds | 3 Pages |
| Table 6 | Summary of Organic Compounds Detected - Soil | 1 Page |
| Fig. 10 | Boring Logs | 39 Pages |

TABLE 1
IN SITU HYDRAULIC CONDUCTIVITY ESTIMATES

| Well Designation | Monitored Interval Hy | draulic Conductivity |
|------------------|--------------------------|-------------------------------------|
| OW5-89 | Lockport/Rochester | 1.8×10^{-5} cm/sec |
| OW7-89 | Overburden | $3.6 \times 10^{-5} \text{cm/sec}$ |
| OW1-89 | Rochester | 3.9×10^{-8} cm/s |
| OW3-89 | Rochester | 1.9×10^{-5} cm/s |
| OW4-89 | Irondequoit/Reynales | $2.0 \times 10^{-7} \text{ cm/s}$ |

TABLE 2
SUMMARY OF GROUNDWATER ELEVATIONS (1989-1990)

| | Measuring Point | Bottom of . Well | Ele | | | |
|--------------|-------------------------|-------------------------|--------------------|--------------------|--------------------|-------------------------|
| WELL NO. | Elevation (ft. AMSL) | Elevation (ft. AMSL) | 11/28/89 | 4/2/90 | 4/17/90 | 4/27/90 |
| B- 01 | 578.88 | 449.5 | • | • | 477.706 | 472.80 |
| B -02 | 569.84 | 460.9 | • | • | • | 53 0. 2 0 |
| GPG-51 | <i>57</i> 9.19 | 294.7 | • | - | DRY | DRY |
| IR-3 | 586.61 | 2 95.7 | • | - | - | 46 0.96 |
| IR-49 | 587.22 | 428.5 | • . | • | - | 458.41 |
| IR-51 | 578.9 9 | 434.9 | • | | - | 463.44 |
| LR-2 | 594.53 | 505. 5 | 554.60 | 55 9.17 | 560. 18 | 559 .79 |
| LR-48 | 586.85 | 510.4 | 552.53 | 557.8 6 | 5 57.90 | 557. 71 |
| LR-49 | 588.01 | 508 .6 | 554.55 | 558.8 7 | 560 .01 | 559 .38 |
| LR-50 | 589.46 | 512.9 | 558.24 | 561.22 | 562. 51 | 561.68 |
| LR-51 | 579.15 | 512.4 | 551.78 | 555.8 5 | 556.64 | 556.4 1 |
| OW1-89 | 614.07 | 472.4 | • | 491.26* | 501.65* | 507.79 |
| OW2-89 | 614.60 | 424.3 | • | •• | •• | ** |
| OW3-89 | 591.80 | 461.7 | - | 536.18 | 533.45 | 535 .12 |
| OW4-89 | 592.26 | 423.7 | • | 439.14 | 442.46 | 443.84 |
| OW5-89 | 609.25 | 5 05. 4 | • | 55 8.50 | 558.31 | 559 .09 |
| OW6-89 | 587.87 | 328.4 | - | 329.6 0 | 329.82 | 329.94 |
| OW7-89 | 600.24 | 584.3 | • | 594 .08 | 594.12 | 594.42 |
| OW8-91 | 575.55 | 5 6 4.4 | • | - | - | - |
| OW9-91 | 574. 9 0 | 560.4 | • | - | . - | - |
| OW10-91 | 573.69 | 559.8 | • | - | - | - |
| R-49 | 587.53 | 467.4 | - | - | • | 5 26.86 |
| R-51 | 578.78 | 456.4 | • | - | - | z 518.11 |
| W-1 | 618.49 | 587 .1 | 591.76 | 59 2.86 | 5 93.54 | 593.08 |
| W-2A | 617.33 | 505.2 | 599.07 | 605.5 0 | 6 06.38 | 606 .19 |
| W-2B | 617.33 | 564.4 | 593.80 | 597 .92 | 598.2 8 | 598.9 0 |
| W-2C | 617.19 | 602 .3 | 602.73 | 611.2 5 | 611.99 | 611.88 |
| W-3A | 619.54 | 557.4 | DRY | DRY | DRY | DRY |
| W-3C | . 619.11 | 57 7 | 59 2.77 | 596 .72 | 596 .86 | 597 .97 |
| W-3D | 619.48 | 599.8 | 603.87 | 6 01.46 | 601.51 | 602 .01 |
| W-4 | 619.78 | 596 .8 | 598.21 | 598.21 | 598. 35 | 598 .78 |
| W-5A | 619.81 | 582.7 | 591.78 | 594 .51 | 594 .61 | 595 .83 |
| Y. 5B | 619.75 | 592.9 | DRY | 595.5 3 | 595 .85 | 5 96.38 |
| W-5C | 619.82 | <i>598.7</i> | 603.05 | 602.99 | 603.3 0 | 602 .98 |
| W-6 | 619.93 | 600.6 | 603.66 | 602.94 | 603 .36 | 603.11 |
| W-7A | 618.59 | 582.4 | 586.27 | 587.39 | 587 .73 | 587 .73 |
| W-7B | 618.83 | 554.4 | 557.17 | 558.66 | 558.78 | 559 .84 |
| W-7C | 618.86 | 597.4 | 606.28 | 601.61 | 601.70 | 605.2 0 |
| W-8A | 617.97 | 590 .0 | 593 .76 | DRY | DRY | DRY |
| W-9A | 616.97 | 560.4 | 563.4 0 | 563.42 | 563. 55 | 563.4 1 |

TABLE 2 SUMMARY OF GROUNDWATER FLEVATIONS (1989-1990)

| | Measuring Point | Bottom of Well | Elevation (ft. AMSL) | | | | | | |
|---------------|-------------------------|-------------------------|----------------------|-------------------------|-----------------|----------------|--|--|--|
| WELL NO. | Elevation (ft. AMSL) | Elevation (ft. AMSL) | 11/28/89 | 4/2/90 | 4/17/9 0 | 4/27/90 | | | |
| W-9B | 617.06 | 578. 3 | 584.30 | 584.69 | 584.79 | 584 .88 | | | |
| W-9C | 617.27 | 587.9 | 589.82 | DRY | DRY | DRY | | | |
| W-11 | 614.42 | 580.2 | 584.53 | 58 3.76 | 584. 00 | 583.7 8 | | | |
| W-12 | 616.59 | 58 1.9 | 589.38 | 59 2.07 | 592 .09 | 593 .07 | | | |
| W-13 | 613.58 | 590 .0 | 596.27 | 59 9.27 | 601.20 | 600.44 | | | |
| W-14 | 614.85 | 585. 9 | 590.30 | 592.4 6 | 594.4 5 | 588 .63 | | | |
| W-15A | 612.89 | 554.0 | 561.74 | 56 2. 4 6 | 5 63.09 | 562 .93 | | | |
| W-15B | 613.22 | 576.3 | 583.19 | 583.0 6 | 583.57 | 583. 08 | | | |
| W-15C | 612.99 | 591.6 | 595.23 | 59 5.26 | 595.21 | 595. 21 | | | |
| W-16 | 601.57 | 5 69.6 | 578.60 | 577.91 | 578.09 | 577 .78 | | | |
| W-17 | 602.36 | 573.4 | 585.62 | 587.23 | 587:31 | 587. 54 | | | |
| W-18A | 602.53 | 573.2 | 587.19 | 587.02 | 587.18 | 587.24 | | | |
| W-19 A | 597.41 | 556 | 558.54 | 558 .58 | 558 .63 | 558.64 | | | |
| W-19B | 596.57 | 510.3 | 552.81 | 559.08 | 558.22 | 558. 98 | | | |
| W-19D | 595.49 | 5 6 7.7 | 575.25 | 578.14 | 583.24 | 582 .62 | | | |
| W-20 | 593.75 | 564.9 | 576.88 | 576.3 8 | 577. 58 | 577. 09 | | | |
| W-22A | 592.24 | 567.8 | 568.42 | 57 0.19 | 570.96 | 570. 51 | | | |
| W-23A | 594.70 | 533.6 | 556.04 | 57 0.83 | 561.7 5 | 56 1.36 | | | |
| W-23B | 594.67 | 550.8 | 556.2 0 | 56 0.87 | 561.82 | 561.44 | | | |
| W-23C | 594.89 | 571.8 | 575.48 | 578.4 0 | 578.4 9 | 578.4 7 | | | |
| W-29A | 617.52 | 558.8 | 560.33 | 56 0.88 | 561 .10 | 560 .75 | | | |
| W-29B | 617.09 | 521.6 | 548.52 | 557.54 | 558.94 | 556. 53 | | | |
| W-34 | 616.86 | 471.3 | • | - | - | 524.56 | | | |
| W-48E | 587,70 | 545.8 | 553.34 | 558.4 3 | 558.88 | 558 .52 | | | |

- not measured
- ** non-operational

 * water level may not be at static level due to slow post-development recovery

| Location: | В | H1 | BH2 | BH3 | BH4 | B H5 | . B | Н6 | BH7 |
|----------------------|-------|---------------|-------|---------|---------------|-------------|---------|----------|----------|
| Depth: | 4'-6' | 10' - 12' | 4'-6' | 2' - 4' | 1'-3' | 2' - 4' | 2' - 4' | 8' - 10' | 8' - 10' |
| Parameter (ppb) | | | | | | | | | |
| Carbon Disulfide | <5 | < 5 | <5 | <5 | <5 | <620 | <620 | <620 | <5 |
| Carbon Tetrachloride | <5 | <5 | <5 | <5 | < 5 | 280] | 7,000 | 360J | <5 |
| Chloroform | <5 | < 5 | <5 | <5 | < 5 | 460J | 2,100 | <620 | <5 |
| Methylene Chloride | <5 | <5 | <5 | <5 | < 5 | <620 | <620 | <620 | <5 |
| Trichloroethene | <5 | <5 | <5 | <5 | < 5 | 5,800 | <620 | <620 | <5 |
| Benzene | <5 | <5 | <5 | <5 | <5 | <620 | <620 | <620 | <5 |
| Toluene | <5 | <5 | <5 | <5 | <5 | <620 | <620 | <620 | <5 |
| Tetrachloroethene | <5 | <5 | <5 | <5 | <5 | 7,100 | <620 | 1,200 | <5 |

⁽¹⁾ SSPL - Site Specific Parameter List.

J - Detected, but below quantitation limit, quantitation suspect.
B - Compound detected in method blank associated with this sample.

S - Estimated due to outlying surrogate recoveries.

| Location: | В | Н8 | В | Н9 | _BH10 | BH11 | BH12 | BH13 | BH14 | BH15 |
|----------------------|---------|-------------|----------|-----------|-----------------|---------------|---------------|-------------|---------|-------------|
| Depth: | 6' - 8' | 12' - 12.8' | 8' - 10' | 14' - 15' | 6'-8' | 4'-6' | 8' - 9.2' | 5.5' - 7.0' | 7' - 9' | 2.5' - 4.5' |
| Parameter (ppb) | | | | | | | | | | |
| Carbon Disulfide | <1,200 | <1,200 | <1200 | <50 | < 5 | < 5 | < 5 | <5 | <5/<5 | <5 |
| Carbon Tetrachloride | 37,000 | 32,000 | 23,000 | 1,200 | <5 | <5 | <5 | <5 | <5/<5 | <5 |
| Chloroform | 500] | 2,000 | 3,000 | 330 | <5 | <5 | < 5 | <5 | <5/<5 | <5 |
| Methylene Chloride | <1,200 | <1,200 | <1,200 | <180B | < 5 | <5 | <5 | <5 | <5/<5 | <5 |
| Trichloroethene | <1,200 | <1,200 | 2000 | 170 | <5 | < 5 | <5 | <5 | <5/<5 | <5 |
| Benzene | <1,200 | <1,200 | <1,200 | · 24J | · < 5 | <5 | <5 | <5 | <5/<5 | <5 |
| Toluene | <1,200 | <1,200 | <1,200 | <50 | <5 | <5 | <5 | <5 | <5/<5 | <5 |
| Tetrachloroethene | <1,200 | <1,200 | <1,200 | 60 | <5 | <5 | 4) | <5 | <5/<5 | <5 |

⁽¹⁾ SSPL - Site Specific Parameter List.J - Detected, but below quantitation limit, quantitation suspect.

| Location: | BH16 | BH17 | BH18 | BH19 | ВІ | ł2 0 | BH21 | BH23 _ | В | H24 |
|----------------------|---------------|---------|-----------|-----------|---------------|-------------|---------------|---------|---------|----------------|
| Depth: | 4'-6' | 5' - 7' | 7' - 8.6' | 4' - 5.7' | 5' - 7' | 7' - 7.3' | 4'-6' | 4' - 6' | 4' - 6' |) 6'-8' |
| Parameter (ppb) | | | | • | | | | | | |
| Carbon Disulfide | <5 | <5 | <5/<5 | <5 | <5 | 7 | <5 | <5 | <5 | <5 |
| Carbon Tetrachloride | <5 | <5 | <5/<5 | <5 | 100 | 52 | <5 | <5 | <5 | <5 |
| Chloroform | <5 | <5 | <5/<5 | <5 | 19 | . 9 | <5 | <5 | <5 | <5 |
| Methylene Chloride | <5 | <5 | <5/<5 | <5 | < 5 | <5 | < 5 | <5 | <5 | <5 |
| Trichloroethene | <5 | <5 | <5/<5 | <5 | <5 | <5 | <5 | <5 | · <5 | <5 |
| Benzene | < 5 | <5 | <5/<5 | <5 | <5 | <5 | <5 | <5 | <5 | <5 |
| Toluene | <5 | <5 | <5/<5 | <5 | <5 | <5 | <5 | <5 | <5 | <5 |
| Tetrachloroethene | <5 | <5· | <5/<5 | <5 | 17 | 20 | <5 | 3] | <5 | <5 |

⁽¹⁾ SSPL - Site Specific Parameter List.

J - Detected, but below quantitation limit, quantitation suspect.

TABLE 3

| Location: | BH25 | BH26 | Bl | BH27A | |
|----------------------|---------------|-------|---------|-----------|----------|
| Depth: | 1.7' - 2.4' | 6'-8' | 0' - 2' | 4' - 5.2' | 8' - 10' |
| Parameter (ppb) | | | | | |
| Carbon Disulfide | <5 | <5 | <630 | <610 | <5/<5 |
| Carbon Tetrachloride | <5 | <5 | <630 | <610 | <5/<5 |
| Chloroform | < 5 | <5 | <630 | <610 | <5/<5 |
| Methylene Chloride | <5 | <5 | <630 | <610 | <5/<5 |
| Trichloroethene | < 5 | <5 | <630 | <610 | <5/<5 |
| Benzene | <5 | <5 | <630 | <610 | <5/<5 |
| Toluene | <5 | <5 | 930 | <610 | <5/<5 |
| Tetrachloroethene | <5 | <5 | 550J | 13,000 | <5/<5 |

Notes:

(1) SSPL - Site Specific Parameter List.

J-Detected, but below quantitation limit, quantitation suspect.

SOIL ANALYTICAL RESULTS TCL (1) VOLATILE ORGANIC COMPOUNDS - ppb

| | D.143 | BH22 | BH28A | BH29 | BH30 | BH31 | Rinsate Blank | Drill Water |
|----------------------------|-------------------------|-----------------------|---------------|---------------|------------|----------------|------------------|----------------|
| Borehole Location: | BH13 4' - 5-5' | 3.5' - 5' | 5' - 7' | 3.5' - 5' | 10' - 12' | 4' - 6' | | rew . |
| Depth: | 4' - 5-5' 2365-PS-19 | 3.5 - 5 2365-PS-36 | 2365-SS-49 | 2365-SS-54 | 2365-SS-61 | BH31-2365-88/ | BH32R | DW-2365-SS-057 |
| Sample Designation: | 2303-13-19 | 2303-F3-30 | 2303-33-43 | 2,00,-35-34 | 2505 55 01 | BH34-2365-88 | | |
| Sample Date: | 8/31/89 | 9/6/89 | 9/11/89 | 9/11/89 | 11/15/89 | 12/11/89 | 12/11/89 | 11/13/89 |
| Compound (ppb) | | | | | | | | |
| Acetone | 110 | 70 | <50 | 50 | <40,000 | <4,000/18,000 | 73 | <50 |
| Benzene | < 5 | <5 | <5 | <5 | <4,000 | <500/<1,000 | >6 | <6 |
| Bromodichloromethane | <5 | <5 | <5 | <5 | <4,000 | <500/<1,000 | >6 | 4] |
| Bromoform | <5 | <5 | <5 | < 5 | <4,000 | <500/<1,000 | >6 | <5 |
| Bromomethane | <10 | <10 | <10 | <10 | <8,000 | <1,000/<5,000 | >30 | <10 |
| 2-Butanone | <50 | <50 | <50 | <50 | <40,000 | <1,000/<10,000 | . <60 | <50 |
| Carbon Disulfide | <5 | < 5 | <5 | <5 | <4,000J | 12,000]/34,000 | <6 | <5 |
| Carbon Tetrachloroide | చ | <5 | <5 | <5 | <4,000 | 3,000]/3,000 | <6 | 45 |
| Chlorobenzene | చ | < 5 | <5 | <5 | <4,000j | <500/<1,000 | <6 | <5 |
| Chloroethane | <10 | <10 | <10 | <10 | <8,000 | <1,000/<5,000 | <30 | <10 |
| Chloroform | <5 | < 5 | < 5 | <5 | <4,000J | <500J/2,000 | <6 | 10 |
| Chloromethane | <10 | <10 | <10 | <10 | <8,000 | <1,000/<5,000 | <30 | <10 |
| Dibromochloromethane | <5 | <5 | <5 | <5 | <4,000 | <500/<1,000 | <6 | 45 |
| 1,1-Dichloroethane | <5 | <5 | <5 | ⋖5 | <4,000 | <500/<1,000 | 8 | <5 |
| 1,2-Dichloroethane | <5 | <5 | <5 | <5 | <4,000 | <500/<1,000 | <6 | <5 |
| 1,1-Dichloroethene | <5 | <5 | <5 | <5 | <4,000 | <500/<1,000 | <6 | <5 |
| 1,2-Dichloroethene (Total) | <5 | <5 | <5 | <5 ⋅ | <4,000 | <500/<1,000 | <6 | <5 |
| 1,2-Dichloropropane | <5 | <5 | <5 | <5 | <4,000 | <500/<1,000 | <6 | <5 |
| cis-1,3-Dichloropropene | <5 | <5 | <5 | <5 | <4,000 | <500/<1,000 | <6 | <5 |
| trans-1,3-Dichloropropene | 45 | <5 | <5 | <5 | <4,000 | <500/<1,000 | <6 | <5 |

Notes:

(1) TCL - Target Compound List.

J - Detected, but below quantitation limit, quantitation suspect.

SOIL ANALYTICAL RESULTS TCL (1) VOLATILE ORGANIC COMPOUNDS - ppb

TABLE 4

| Borehole Location: Depth: Sample Designation: Sample Date: | BH13 4' - 5-5' 2365-PS-19 8/31/89 | BH22 3.5' - 5' 2365-PS-36 9/6/89 | BH28A 5' - 7' 2365-SS-49 9/11/89 | BH29 3.5' - 5' 2365-55-54 9/11/89 | BH30 104' - 12' 2365-SS- 6 1 11/15/89 | BH31 4' - 6' BH31-2365-88/ BH34-2365-88 12/11/89 | Rinsate Blank BH32R 12/11/89 | Drill Water DW-2365-SS-057 11/13/89 |
|--|--|---|---|--|---|--|---|--|
| Compound (ppb) | | | | | | | | |
| Ethylbenzen e | ර | < 5 | <5 | خ خ | 3,000] | <500/<1,000 | <6 | <5 |
| 2-hexanone | <50 | < 50 | <50 | <50 | <40,000 | <1,000/<10,000 | <60 | <50 |
| Methylene Chloride | < 5 | < 5 | < 5 | 45 | 10000 | <500/<1,000 | <6 | <5 |
| 4-Methyl-2-Pentanone | <50 | <50 | <50 | <50 | <40,000 | <1,000/<10,000 | <60 | <50 |
| Styrene | <5 | <5 | <5 | S | <4,000 | <500/<1,000 | <6 | <5 |
| 1,1,2,2-Tetrachloroethane | 11 | ح. | <5 | 4 | <4,000 | <500/<1,000 | <6 | <5 |
| Tetrachloroethene | <5 | <5 | 4] | <5 | 130000 | <500/<1,000 | <6 | <5 |
| Toluene | <5 | 4 5 | <5 | ර | <4,000 | <500/<1,000 | <6 | < 5 |
| 1,1,1-Trichloroethane | ح5 | <5 | <5 | ර | <4,000 | <500/<1,000 | <6 | <5 |
| 1,1,2-Trichloroethane | చ | ح5 | <5 | حة. | <4,000 | <500/<1,000 | <6 | <5 |
| Trichloroethene | 45 | <5 | 2J | 4 | 4000 | <500/<1,000 | 7 | <5 |
| Vinyl Acetate | <50 | <50 | <50 | <50 | <40,000 | <1,000/<10,000 | <60 | <50 |
| Vinyl Chloride | <10 | <10 | <10 | <10 | <8,000 | <1,000/<5,000 | <30 | <10 |
| Total Xylenes | ⋖5 | <5 | <5 | ර | 19000 | <500/<1,000 | <6 | < 5 |

⁽¹⁾ TCL - Target Compound List.

J - Detected, but below quantitation limit, quantitation suspect.

SOIL ANALYTICAL RESULTS TCL (1) BASE/NEUTRAL/ACID EXTRACTABLE COMPOUNDS - ppb

| | | | | | | | Rinsate | Drill |
|------------------------------|------------|------------|------------------|-----------------|------------|----------------|----------|----------------------|
| Borehole Location: | BH13 | BH22 | BH 28A | B H29 | BH30 | BH31 | Blank | Water |
| Depth: | 4' - 5-5' | 3.5' - 5' | 5*÷ 7* | 3.5' - 5' | 10' - 12' | 4' - 6' | | ' |
| Sample Designation: | 2365-PS-20 | 2365-PS-36 | 2365-SS-50 | 2365-SS-55 | 2365-SS-61 | BH31-2365-88/ | BH32R | DW-2365-SS-057 |
| , , | | | | | | BH34-2365-88 | | |
| Sample Date: | 8/31/89 | 9/6/89 | 9/11/89 | 9/11/8 9 | 11/15/89 | 12/11/89 | 12/11/89 | 11/13/8 9 |
| Compound (ppb) | | | | | • | | | |
| Acenaphthene | <660 | <660 | <660 | <660 | <8,300 | <6,700/<660 | <10 | <10 |
| Acenaphthylene | <660 | <660 | <660 | <660 | <8,300 | <6,700/<660 | <10 | <10 |
| Anthracene | <660 | <660 | <660 | <660 | <8,300 | <6,700/<660 | <10 | <10 |
| Benzoic Acid | <1,300 | <3,300 | <3,300 | <3,300 | <42,000 | <34,000/<3,300 | <50 | <50 |
| Benzo(a) Anthracene | <660 | <660 | <660 | <660 | <8,300 | <6,700/<660 | <10 | <10 |
| Benzo(b)Fluoranthene | <660 | <660 | 300] | <660 | <8,300 | <6,700/<660 | <10 | <10 |
| Benzo(k)Fluoranthene | <660 | <660 | 300) | <660 | <8,300 | <6,700/<660 | <10 | <10 |
| Benzo(g,h,i)Perylene | <660 | <660 | <660 | <660 | <8,300 | <6,700/<660 | <10 | <10 |
| Benzo(a)Pyrene | <660 | <660 | <660 | <660 | <8,300 | <6,700/<660 | <10 | <10 |
| BenzylAlcohol | <1,300 | <1,300 | <1,300 | <1,300 | <8,300 | <6,700/<660 | <10 | <10 |
| Bis(2-Chloroethoxy)Methane | <660 | <660 | <660 | <660 | <8,300 | <6,700/<660 | <10 | <10 |
| Bis(2-Chloroethyl)Ether | <660 | <660 | <660 | <660 | <8,300 | <6,700/<660 | <10 | <10 |
| Bis(2-Chloroiosopropyl)Ether | <660 | <660 | <660 | <660 | <8,300 | 900]/900 | <10 | <10 |
| Bis(2-Ethylhexyl)Phthalate | <660 | 400} | 700] | 1400 | <8,300 | <6,700/<660 | <10 | <10 |
| 4-Bromophenyl Phenyl Ether | <660 | <660 | <660 | <660 | <8,300 | <6,700/<660 | <10 | <10 |
| Butyl Benzyl Phthalate | <660 | <660 | <660 | <660 | <8,300 | <6,700/<660 | <10 | <10 |
| 4-Chloroaniline | <1,300 | <1,300 | <1,300 | <1,300 | <8,300 | <6,700/<660 | <10 | 2] |
| 2-Chloronaphthalene | <660 | <660 | <660 | <660 | <8,3(X) | <6,700/<660 | <10 | <10 |
| 4-Chlorophenyl Phenyl Ether | <660 | <660 | <660 | <660 | <8,300 | <6,700/<660 | <10 | <10 |
| 4-Chloro-3-Methylphenol | <1,300 | <660 | <6 60 | <660 | <8,3(X) | <6,700/<660 | <10 | <10 |
| 2-Chlorophenol | <660 | <660 | <660 | <660 | <8,300 | <6,700/<660 | <10 | <10 |
| Chrysene | <660 | <660 | 400) | <660 | <8,300 | <6,700/<660 | <10 | <10 |
| Dibenzo(a,h)Anthracene | <660 | <660 | <660 | <660 | <8,300 | <6,700/<660 | <10 | <10 |
| Dibenzofuran | <660 | <660 | 300) | <660 | <8,300 | <6,700/<660 | <10 | <10 |

⁽¹⁾ TCL - Target Compound List.

J - Detected, but below quantitation limit; quantitation suspect.

B - Compound detected in method blank associated with this sample.

SOIL ANALYTICAL RESULTS TCL (1) BASE/NEUTRAL/ACID EXTRACTABLE COMPOUNDS - ppb

| Borehole Location: | BH13 | BH22 | BH28A | BH29 | B11.30 | BH31 | Rinsate Blank | Drill Water |
|----------------------------|-------------------|--------------------------|----------------|--------------------|------------|-------------------------------|------------------|----------------|
| Depth: | 4' - 5 -5' | 3.5' - 5 ' | 5' - 7' | 3.5' - 5' · | 10' - 12' | 4' - 6' | | •• |
| Sample Designation: | 2365-PS-20 | 2365-PS-36 | 2365-55-50 | 2365-55-55 | 2365-SS-61 | BH31-2365-88/ BH34-2365-88 | BH32R | DW-2365-SS-057 |
| Sample Date: | 8/31/89 | 9/6/89 | 9/11/89 | 9/11/89 | 11/15/89 | 12/11/89 | 12/11/89 | 11/13/89 |
| Compound (ppb) | | | | | | | | |
| Di-n-Butyl Phthalate | / <660 | <660 | 200] | 200JB | <8,300 | <6,700/3,500B | <10 | 3) |
| 1,2-Dichlorobenzene | <660 | <660 | <660 | <660 | <8,300 | <6,700/< 66 0 | <10 | <10 |
| 1,3-Dichlorobenzene | <660 | <660 | <660 | <660 | <8,300 | <6,700/<660 | <10 | <10 |
| 1,4-Dichlorobenzene | <660 | <660 | <660 | <660 | <8,300 | <6,700/<660 | <10 | <10 |
| 3,3'-Dichlorobenzidine | <1,300 | <1,300 | <1,300 | <1,300 | <42,000 | <34,000/<3,300 | <50 | <50 |
| 2,4-Dichlorophenol | <660 | <660 | <660 | <660 | <8,300 | <6,700/<660 | <10 | <10 |
| Diethyl Phthalate | <660 | 200] B | <660 | 100 JB | <8,300 | <6,700/<660 | 6) | <10 |
| 2,4-Dimethylphenol | <660 | <3,300 | <660 | <660 | <8,300 | <6,700/<660 | <10 | <10 |
| Dimethyl Phthalate | <660 | <660 | <660 | <660 | <8,300 | <6,700/<660 | <10 | <10 |
| 2,4-Dinitrophenol | <3,300 | <3,300 | <3,300 | <3,300 | <42,000 | <34,000/<3,300 | <50 | <10 |
| 2,4-Dinitrotoluene | <660 | <660 | <660 | <660 | <8,300 | <6,700/ <i><</i> 660 | <10 | <10 |
| 2,6-Dinitrotoluene | <660 | <660 | <660 | <660 | <8,300 | <6,700/<660 | <10 | <10 |
| Di-n-Octyl Phthalate | <660 | <660 | <660 | <660 | <8,300 | <6,700/<660 | <10 | <10 |
| Fluoranthene | <660 | <660 | 300J | <660 | <8,300 | <6,700/<660 | <10 | <10 |
| Fluorene | <660 | <660 | <660 | <660 | <8,300 | <6,700/<660 | <10 | <10 |
| Hexachlorobenzene | <660 | <660 | < 660 | <660 | <8,300 | <6,700/600} | <10 | <10 |
| Hexachlorobutadiene | <660 | <660 | <660 | <660 | 1,000J | <6,700/<660 | <10 | <10 |
| Hexachlorocylopentadiene | <660 | <660 | < 66 0 | <660 | <8,300 | <6,700/<660 | <10 | <10 |
| Hexachloroethane | <660 | <660 | <660 | <660 | 16,000 | <6,700/<660 | <10 | <10 |
| Indeno(1,2,3-cd)Pyrene | <660 | <660 | <660 | <660 | <8,300 | <6,700/<660 | <10 | <10 |
| Isophorone | <660 | <660 | <660 | <660 | <8,300 | <6,700/<660 | <10 | <10 |
| 2-Methyl-4,6-Dinitrophenol | <3,300 | <3,300 | <3,300 | <3,300 | <42,000 | <34,000/<3,300 | <50 | <50 |
| 2-Methylphenol | <660 | <660 | <660 | <660 | <8,300 | <6,700/<660 | <10 | <10 |
| 4-Methylphenol | <660 | <660 | <660 | <660 | <8,300 | <6,700/<660 | <10 | <10 |

⁽¹⁾ TCL - Target Compound List.

J - Detected, but below quantitation limit; quantitation suspect.

B - Compound detected in method blank associated with this sample.

SOIL ANALYTICAL RESULTS TCL (1) BASE/NEUTRAL/ACID EXTRACTABLE COMPOUNDS - ppb

| Borehole Location: | BH13 | BH22 | B H28A | BH2 9 | BH30 | BH31 | Rinsate Blank | Drill Water |
|---------------------------|------------|------------|---------------|--------------|------------|-------------------------------|------------------|----------------|
| Depth: | 4' - 5-5' | 3.5' - 5' | 5' - 7' | 3.5' - 5' | 10' - 12' | 4' - 6' | -,- | |
| Sample Designation: | 2365-PS-20 | 2365-PS-36 | 2365-SS-50 | 2365-SS-55 | 2365-SS-61 | BH31-2365-88/ BH34-2365-88 | BH32R | DW-236S-SS-057 |
| Sample Date: | 8/31/89 | 9/6/89 | 9/11/89 | 9/11/89 | 11/15/89 | 12/11/89 | 12/11/89 | 11/13/89 |
| Compound (ppb) | • | | | | | | | |
| 2-Methylnaphthalene | <660 | <660 | 1,000} | <660 | <8,300 | <6,700/300] | <10 | <10 |
| Naphthalene | <660 | <660 | 1,000} | <660 | 800J | <6,700/200] | <10 | <10 |
| Nitrobenzene | <660 | <660 | <660 | <660 | <8,300 | <6 <i>,7</i> 00/<660 | <10 | <10 |
| 2-Nitrophenol | <660 | <660 | <660 | <660 | <8,300 | <6,700/<660 | <10 | <10 |
| 4-Nitrophenol | <3,300 | <3;300 | <3,300 | <3,300 | <42,000 | <34,300/<3,300 | <50 | <50 |
| 2-Nitroaniline | <3,300 | <3,300 | <3,300 | <3,300 | <42,000 | <34,300/<3,300 | <50 | <50 |
| 3-Nitroaniline | <3,300 | <3,300 | <3,300 | <3,300 | <42,000 | <34,300/<3,300 | <50 | <50 |
| 4-Nitroaniline | <3,300 | <3,300 | <3,300 | <3,300 | <42,000 | <34,300/<3,300 | < 50 | <50 |
| N-Nitrosodiphenylamine | <660 | <660 | <660 | <660 | <8,300 | <6,700/<660 | <10 | <10 |
| N-Nitrosodi-n-Propylamine | <660 | <660 | <660 | <660 | <8,300 | <6,700/<660 | <10 | <10 |
| Pentachlorophenol | <3,300 | <3,300 | <3,300 | <3,300 | <42,000 | <34,300/<3,300 | <50 | <50 |
| Phenanthrene | <660 | <660 | 700] | <660 | <8,300 | <6,700/100] | <10 | <10 |
| Phenol | <660 | <660 | <660 | <660 | <8,300 | <6,700/1,300 | <10 | <10 |
| Pyrene | <660 | <660 | 400J | <660 | <8,300 | <6,700/<660 | <10 | <10 |
| 1,2,4-Trichlorobenzene | <660 | <660 | <660 | <660 | <8,300 | <6,700/<660 | <10 | <10 |
| 2,4,5-Trichlorophenol | 100] | 100} | 100] | 100] | <42,000 | <6,700/<660 | <10 | <50 |
| 2,4,6-Trichlorophenol | <660 | <660 | <660 | <660 | <8,300 | <6,700/<660 | <10 | <10 |

⁽¹⁾ TCL - Target Compound List.

J - Detected, but below quantitation limit; quantitation suspect.

B - Compound detected in method blank associated with this sample.

TABLE 6
SUMMARY OF ORGANIC COMPOUNDS
DETECTED IN SOIL SAMPLES

| Parameter | No. Detections/ No. Samples | Maximum Concentration (ppm) |
|------------------------------|--------------------------------|-----------------------------|
| VOCs | | \ |
| Acetone | 5 /6 | 18 |
| Carbon Disulfide | 6/54 | 34 |
| Carbon Tetrachloride | 13/54 | 37 |
| Chloroform | 13/54 | 3 |
| Methylene Chloride | 2/54 | 10 |
| Trichloroethene | 7/5 8 | 5.8 |
| Benzene | 3/5 2 | 0.0024] |
| Toluene | 3/52 | 0.93 |
| Tetrachloroethene | 18/58 | 130 |
| BNAs | | |
| Diethyl phthalate | 2/6 | 0.2 JB |
| 2,4,5-Trichlorophenol | 4/6 | 0.1J |
| Bis(2 ethyl hexyl) phthalate | 3/6 | 1.4 |
| Benzo(b)fluoranthene | 1/6 | 0.3] |
| Benzo(k)fluroanthene | 1/6 | 0.3] |
| Chrysene | 1/6 | 0.4] |
| Dibenzofuran | 1/6 | 0.3] |
| Di-n-butyl phthalate | 2/6 | 0.2] |
| Fluoranthene | 1/6 | 0.3 J |
| 2-Methylnaphthalene | 1/6 | 1) |
| Naphthalene | 1/6 | 1j |
| Phenanthrene | 1/6 | 0.7] |
| Pyrene | 1/6 | 0.4J |
| Hexachloroethane | 1/6 | 16 |
| Hexachlorob ut adiene | 1/6 | 1J |
| Phenol | 1/6 | 1.3 |

HOLE DESIGNATION: BH-1

PROJECT NO.: 2365

PROJECT NAME: STAUFFER

DATE COMPLETED: AUGUST 24, 1989

(L-1)

CLIENT:

DRILLING METHOD: 3 1/4" ID HSA

LOCATION:

CHEMIACL ANALYSIS

ICI AMERICAS

N1146032.8 E379074.5

CRA SUPERVISOR: P. SMITH

| GROUND SURFACE Augers advanced to 2.0 ft. BGS thru asphalt and concrete SiLT, some clay, trace fine sand, trace brick and title, firm, brown gray moist, (ML)-Fill. SiLT, some clay and fine sand, stiff, brown gray and light brown mattled, wet, (ML)-NATIVE No recovery 7.5 SiLT, trace fine sand, stiff, red brown, wet. (ML) Coarse to fine SAND, some silt and clay, trace fine sand, medium dense, red brown, maist, (SM)-TILL Some, except wet 9.6 ft. BGS; borehole collapsed to 9.9 ft. BGS with augers pulled. 2. At completion, borehole was grouted to 9.9 ft. BGS with augers pulled. 2. At completion, borehole was grouted to ground surface. 3. 255 and 555 were collected for chemical analysis. | MPLE |
|--|----------------|
| Augers advanced to 2.0 ft. BGS thru asphalt and concrete 2.5 SILT, some clay, trace fine sand, trace brick and tile, firm, brown gray, moist, (ML)-FILL 5.0 SILT, some clay and fine sand, stiff, brown gray and light brown motitied, wet, (ML)-NATIVD No recovery 7.5 SILT, trace fine sand, stiff, red brown, wet, (ML)-NATIVD No recovery 7.5 SILT, trace fine sand, stiff, red brown, wet, (ML)-NATIVD No recovery 7.5 SILT, trace fine sand, stiff, red brown, maist, Same, except wet 10.0 Fine sand, medium dense, red brown, maist, Same, except wet 12.5 END OF HOLE © 12.8 FT. BGS NOTES: 1. At completion, water level was 9.6 ft. BGS, barehole collapsed to 9.9 ft. BGS with augers pulled. 2. At completion, barehole was grouted to 9.9 ft. BGS with augers pulled. 2. At completion, barehole was grouted to 9.9 ft. BGS with augers pulled. 2. At completion, barehole was grouted to 9.9 ft. BGS with augers pulled. 2. At completion, barehole was grouted to 9.9 ft. BGS with augers pulled. 2. At completion, barehole was grouted to 9.9 ft. BGS with augers pulled. 2. At completion, barehole was grouted to 9.9 ft. BGS with augers pulled. 2. At completion, barehole was grouted to 9.9 ft. BGS with augers pulled. 2. At completion, barehole was grouted to 9.9 ft. BGS with augers pulled. 2. At completion, barehole was grouted to 9.9 ft. BGS with augers pulled. 2. At completion, barehole was grouted to 9.9 ft. BGS with augers pulled. 2. At completion, barehole was grouted to 9.9 ft. BGS with augers pulled. 2. At completion, barehole was grouted to 9.9 ft. BGS with augers pulled. 2. At completion, barehole was grouted to 9.9 ft. BGS with augers pulled. 2. At completion, barehole was grouted to 9.9 ft. BGS with augers pulled. 2. At completion, barehole was grouted to 9.9 ft. BGS with augers pulled. | DS EP CL |
| and concrete 2.5 SILT, some clay, trace fine sand, trace brick and tile, firm, brown gray, moist, (ML)-FILL 5.0 SILT, some clay and fine sand, stiff, brown gray and light brown mattled, wet, (ML)-NATIVE No recovery 7.5 SILT, trace fine sand, stiff, red brown, wet, (ML)-Silt, trace fine sand, medium dense, red brown, maist, Sac. 6 576.6 Silt, trace fine sand, stiff, red brown, wet, (ML)-Silt, sand, medium dense, red brown, maist, Sac. 6 576.6 Silt, trace fine sand, stiff, red brown, wet, (ML)-Silt, sand, medium dense, red brown, maist, Sac. 6 576.6 Silt, trace fine sand, stiff, red brown, wet, (ML)-Silt, sand, medium dense, red brown, maist, Sac. 6 576.6 Silt, trace fine sand, stiff, red brown, wet, (ML)-Silt, sand, | |
| SILT, some clay, trace fine sand, trace brick and tile, firm, brown gray, moist, (ML)-FILL SILT, some clay and fine sand, stiff, brown gray and light brown mattled, wet, (ML)-NATIVE No recovery 7.5 SILT, trace fine sand, stiff, red brown, wet, (ML)-NATIVE No recovery 580.6 SILT, trace fine sand, stiff, red brown, wet, (ML)-NATIVE Sane, except wet 10.2 END OF HOLE © 12.8 FT. BGS NOTES: 1. At completion, water level was 9.6 ft. BGS; borehole collapsed to 9.9 ft. BGS with augers pulled. 2. At competion, borehole was grouted to ground surface. 3. 2SS and 5SS were collected for chemical analysis. | \prod |
| 5.0 gray and light brown mattled, wet, (ML)-NATIVE No recovery 7.5 Sil.T. trace fine sand, stiff, red brown, wet. (ML) Sand fine sand, medium dense, red brown, maist. Sand fine sand, medium dense, red brown, wet. Sand fine sand, medium dense, r | 7 |
| 7.5 SiLT, trace fine sand, stiff, red brown, wet, (ML) Coarse to fine SAND, some silt and clay, trace fine sand, medium dense, red brown, maist, Same, except wet END OF HOLE © 12.8 FT. BGS NOTES: 1. At completion, water level was 9.6 ft. BGS; barehole collapsed to 9.9 ft. BGS with augers pulled. 2. At completion, barehole was grouted to ground surface. 3. 2SS and SSS were collected for chemical analysis. | |
| SILT. trace fine sand, stiff, red brown, wet, (ML) Coarse to fine SAND, some sift and clay, trace fine sand, medium dense, red brown, maist, (SM)—TILL Same, except wet END OF HOLE © 12.8 FT. BGS NOTES: 1. At completion, water level was 9.6 ft. BGS; borehole collapsed to 9.9 ft. BGS with augers pulled. At completion, borehole was grouted to ground surface. 3. 25S and 5SS were collected for chemical analysis. | |
| Coarse to fine SAND, some silt and clay, trace fine sand, medium dense, red brown, maist, SM)—TILL Same, except wet 12.5 END OF HOLE © 12.8 FT. BGS NOTES: 1. At completion, water level was 9.6 ft. BGS, borehole collapsed to 9.9 ft. BGS with augers pulled. 2. At completion, borehole was grouted to ground surface. 3. 255 and 555 were collected for chemical analysis. 20.0 22.5 25.0 27.5 | 7 |
| Same, except wet 576.6 END OF HOLE © 12.8 FT. BGS NOTES: 1. At completion, water level was 9.6 ft. BGS; borehole collapsed to 9.9 ft. BGS with augers pulled. 2. At completion, borehole was grouted to ground surface. 3. 2SS and 5SS were collected for chemical analysis. 20.0 22.5 25.0 27.5 | |
| END OF HOLE © 12.8 FT. BGS NOTES: 1. At completion, water level was 9.6 ft. BGS; barehole collapsed to 9.9 ft. BGS with augers pulled 2. At completion, barehole was grouted to ground surface. 3. 2SS and SSS were collected for chemical analysis. 20.0 22.5 25.0 27.5 | , K |
| 9.6 ft. BGS; barehole collapsed to 9.9 ft. BGS with augers pulled. 2. At completion, borehole was grouted to ground surface. 3. 255 and 555 were collected for chemical analysis. 20.0 22.5 25.0 27.5 | ' |
| 17.5 3. 255 and 555 were collected for chemical analysis. 20.0 22.5 25.0 27.5 | |
| 22.5 25.0 27.5 | |
| 25.0 | |
| 27.5 | |
| | |
| | |
| 30.0 | |
|) | |
| 32.5 | |
| FIGURE 10 | |

WATER FOUND

HOLE DESIGNATION: BH-2

PROJECT NO.: 2365

PROJECT NAME: STAUFFER

DATE COMPLETED: AUGUST 24, 1989

CLIENT:

DRILLING METHOD: 3 1/4" ID HSA

(L-2)

LOCATION:

ICI AMERICAS

N1146103.4 E379225.6

CRA SUPERVISOR: P. SMITH

| | STRATIGRAPHIC DESCRIPTION & REMARKS | ELEVATION | MONITOR | <u> </u> | SAM | PLE | |
|-------------|---|------------------|--------------|----------|--------|-----|--------|
| BGS | GROUND SURFACE | 11 AMSL 390.6 | INSTALLATION | BRCZ | ST ATE | 0#C | |
| | Coarse to fine SAND, some fine gravel, trace silt, trace slog, firm, dark gray, dry, (SP)-Fill. | | openal E | 155 | X | | \mid |
| 2.5 | SILT, some fine sand and day, very stiff, light red brown mottled, dry, (ML)—NATIVE | 588.6 | | 255 | X | | |
| 5.0 | Same, except dry to maist | 58 6.6 | | 355 | X | | |
| 7.5 | SILT, trace clay, hard, red brown, moist, (ML) | 584.6 | | 45\$ | X | | |
| <i>'</i> .5 | SILT, some coarse to fine sand, trace fine gravel, medium dense, red brown, maist, (SC)-TILL | 58 2.6 | | 555 | | | |
| 10.0 | Same, except without fine gravel | 580.6 | | 655 | X | | |
| 12.5 | END OF HOLE @ 12.0 FT. BGS | <i>578.6</i> | | | | | |
| 15.0 | NOTES: 1. Borehole dry at completion. 2. At completion, borehole was grouted to ground surface. 3. 3SS was collected for chemical analysis. | | • | | | | |
| 17.5 | | | | | | | |
| 20.0 | | | | | | | |
| 22.5 | | | | | | | |
| 25.0 | | | | | | | |
| 27.5 | | | | | | | |
| 30.0 | | | | | | | |
| 70 5 | | | | | | | |
| 32.5 | FIG | URE 10 | | | | | |

NOTES:

MEASURING POINT ELEVATIONS MAY CHANGE: REFER TO CURRENT ELEVATION TABLE

CHEMICAL ANALYSIS

WATER FOUND

STATIC WATER LEVEL

Y

(L-1)

PROJECT NAME: STAUFFER

HOLE DESIGNATION: BH-1

PROJECT NO.: 2365

DATE COMPLETED: AUGUST 24, 1989

CLIENT:

ICI AMERICAS

DRILLING METHOD: 3 1/4" ID HSA

LOCATION:

N1146032.8 E379074.5

CRA SUPERMSOR: P. SMITH

| DEPTH | STRATIGRAPHIC DESCRIPTION & REMARKS | ELEVATION | | | SAM | | |
|--------|---|----------------|--------------|--------------|-------------|-------------|---------|
| IL BGS | | ft AMSL | INSTALLATION | BREZ | Ş I A | Omd r on |) V (§ |
| | GROUND SURFACE | 58 6.6 | | Į Ę | Ė | † | Ď |
| | Augers advanced to 2.0 ft. BGS thru asphalt and concrete | | BOREHOLE | | | | |
| - 2.5 | SILT, some clay, trace fine sand, trace brick and tile, firm, brown gray, moist, (ML)—FILL: | 584.6 | - ENLOW | 15\$ | X | | 5 |
| - 5.0 | SILT, some clay and fine sand, stiff, brown gray and light brown mattled, wet, (ML)—NATIVE | | 201 | 255 | X | | 13 |
| | No recovery | <i>580.6</i> | | 355 | | | 45 |
| 7.5 | SILT, trace fine sand, stiff, red brown, wet. | 578.6 578.1 | | 45\$ | | | 12 |
| - 10.0 | Coarse to fine SAND, some silt and clay, trace fine sand, medium dense, red brown, maist, | | | | \bigcirc | | |
| - 12.5 | (SM)- TILL Same, except wet | 576.6 | | 55 \$ | | | 122 |
| 75.0 | END OF HOLE • 12.8 FT. BGS | 573.8 | ACC. M. C. | | | | 4 |
| - 15.0 | NOTES: 1. At completion, water level was 9.6 ft. BGS; borehole collapsed to 9.9 ft. BGS with augers pulled. 2. At completion, borehole was grouted to ground surface. | | | | | | |
| 17.5 | 3. 25S and 5SS were collected for chemical analysis. | | | | | | · [|
| - 20.0 | · | | | | | | l |
| - 22.5 | | | | | | | 1 |
| | | | | | | | ı |
| - 25.0 | | | | | | | |
| - 27.5 | · | | | | | | |
| | · | | | 1 | | | |
| - 30.0 | | | | | | | |
| - 32.5 | | | | | | | |
| | FIGURE | 10 | | | | | |

CHEMIACL ANALYSIS

WATER FOUND

HOLE DESIGNATION: BH-2

PROJECT NO.: 2365

PROJECT NAME: STAUFFER

DATE COMPLETED: AUGUST 24, 1989

(L-2)

CLIENT:

ICI AMERICAS

DRILLING METHOD: 3 1/4" ID HSA

LOCATION: N1146103.4 E379225.6

CRA SUPERVISOR: P. SMITH

| 200 | STRATIGRAPHIC DESCRIPTION & REMARKS | ELEVATION | MONITOR INSTALLATION | | SAM | PLE Ne | |
|------|--|---------------|-------------------------|----------|------------|-----------|-----|
| BGS | GROUND SURFACE | ft AMSL 590.6 | RSTALLATION | ORC 2 | ATE | C L | |
| | Coarse to fine SAND, some fine gravel, trace | 330.0 | 257976NA | <u> </u> | E | Ť | L E |
| | silt, trace slag, firm, dark gray, dry, (SP)-FILL | 588.6 | OREHOLE . | 15\$ | X | | 1 |
| 2.5 | SILT, some fine sand and day, very stiff, light red brown mottled, dry, (ML)—NATIVE Some, except dry to moist | 58 6.6 | CHENTY EN CONTE | 255 | X | | 3 |
| 5.0 | Sume, except dry to maist | | Si di | 355 | X | | 4 |
| | SILT, trace clay, hard, red brown, moist, (ML) | 584.6 | | 455 | | | 11 |
| 7.5 | SILT come course to fine and trees fine | 582.6 | | 555 | \Diamond | | 2 |
| 10.0 | grovel, medium dense, red brown, moist, (SC)— TILL Same, except without fine gravel | 580.6 | | 1 | () | | |
| 12.5 | END OF HOLE @ 12.0 FT. BGS | 578.6 | | 655 | X | | 11 |
| 12.5 | NOTES: 1. Borehole dry at completion. 2. At completion, borehole was | | | | | | |
| 15.0 | grouted to ground surface. 3. 3SS was collected for chemical analysis. | | | | | | |
| 17.5 | | | | | | | |
| 20.0 | | | | | | | |
| 22.5 | | | | | | | |
| 25.0 | | | | | | | |
| | | | • | | | | |
| 27.5 | | | | | | | |
| 30.0 | | | | | | | |
| 705 | | | | | | | |
| 32.5 | FIG | URE 10 | | | | | |

CHEMICAL ANALYSIS WATER FOUND

HOLE DESIGNATION: BH-3

PROJECT NAME: STAUFFER

PROJECT NO.: 2365

DATE COMPLETED: AUGUST 25, 1989

CLIENT:

ICI AMERICAS

DRILLING METHOD: 3 1/4" ID HSA

(L-3)

LOCATION:

N1146220.6 E379243.7

CRA SUPERVISOR: P. SMITH

| LOCA | ON. N1140220.0 E3/3243./ | • | | | | |
|--------|---|----------------|-------------------------|-------------|-------------|------------|
| | STRATIGRAPHIC DESCRIPTION & REMARKS | ELEVATION | MONITOR INSTALLATION | | SAMPL | |
| ft BCS | | ft AMSL | INSTALLATION | BECZ | STA | S N P V |
| | GROUND SURFACE | 592.3 | | BLR | ۲ ٤ | LUE |
| | SILT, some coarse to fine sand and gravel, trace roots, trace slag, medium dense, brown | | -45 | 15\$ | \bigvee | 14 |
| 2.5 | and gray, dry. (SM)-Fill. Sil.T. some fine sand and day, very stiff. | 590.3 589.8 | BONEHOLE | | Θ | |
| | \brown, dry, (ML) Sil.T. some clay, trace fine sand, very stiff, | 588.3 | SENENT/E | 255 | \triangle | 18 |
| 5.0 | Sit I some fine sand and clay, very stiff. | 333.3 | | 3S S | X | 22 |
| | red brown and gray mottled, dry, (ML) Same, except moist | 586.3 | | 455 | \forall | 41 |
| 7.5 | | 584.1 | | 433 | | |
| | SILT, some fine sand, trace clay, very stiff, red brown, moist to wet, (ML)-NATIVE | | | 5S S | X | 26 |
| 10.0 | Same, except some clay | 582.3 | | 65 5 | \bigvee | 14 |
| 12.5 | · | 579.6 | | 655 | Θ | ١., |
| | SILT, some coarse to fine sand, trace day and fine gravel, medium dense, red brown, | .578.8 | | 022 | Θ | 18 |
| 15.0 | \moist. (SM)-TILL END OF HOLE ● 13.5 FT. BGS | | | | | |
| | NOTES: 1. Borehole dry at completion. 2. At completion, borehole was | | | | | |
| 17.5 | grouted to ground surface. 3. 255 was collected for chemical analysis. | | | | | |
| 20.0 | | | | | | |
| | · | | | | | |
| 22.5 | | | | | | |
| | | | | | | |
| 25.0 | | | · | | | |
| 27.5 | | | | | | |
| | | | | | | |
| 30.0 | | | | | | |
| | · | • | | | | |
| 32.5 | FIG | I JRE 10 | | | | |
| | 7100 | | | | | |
| NOT | ES: MEASURING POINT ELEVATIONS MAY CHAN | GE; REFER | TO CURRENT ELEVATION | TABLE | | |
| | CHEMICAL ANALYSIS WATER FO | DUND 🔽 | STATIC WATER LEVEL | • | | |

(L-4)

PROJECT NAME: STAUFFER

HOLE DESIGNATION: BH-4

DRILLING METHOD: 3 1/4" ID HSA

PROJECT NO.:

2365

DATE COMPLETED: AUGUST 25, 1989

CLIENT: LOCATION: ICI AMERICAS

N1146310.9 E379266.4

CRA SUPERVISOR: P. SMITH

| H143 | STRATIGRAPHIC DESCRIPTION & REMARKS | ELEVATION | MON | NITOR | | SAM | PLE | |
|---------------|---|---------------|--|---------|------|-------------|----------|-----|
| L BGS | | ft AMSL | INSTA | LLATION | NC X | \$ | DS EP | N. |
| | GROUND SURFACE | 5 91.8 | | | 1 BE | A T E | CL | ŗ |
| _ | Augers advanced to 1.0 ft. through asphalt and stone | 590.8 | | | | | | |
| 2.5 | CLAY, some silt, stiff, red brown, dry to moist, (CL)-NATIVE | | | OREHOLE | ISS | X | | 14 |
| | SILT, some clay, very stiff, light red brown mottled, dry, (CL) | 588.8 | | CEMENT/ | 255 | ∇ | | 20 |
| 5.0 | SILT, some fine sand, trace clay, hard, red | 586.8 | | | | (\cdot) | | |
| | brown, moist to wet, (ML) Same, except very stiff | 584.8 | | | 355 | \triangle | | 32 |
| 7.5 | | | | | 455 | X | | 19 |
| 1 0 .0 | | 581.8 | | | 555 | ∇ | | 20 |
| | SiLT, some coarse to fine sand and ciay, medium dense, red brown, maist, (SM)—TILL Same, except trace coarse to fine gravet | 58 0.8 | | | 625 | Θ | | 114 |
| 12.5 | END OF HOLE 6 12.3 FT. BGS | 579.5 | - A. | | | | | 9 |
| 15.0 | NOTES: 1. At completion, borehole was grouted to ground surface. 2. ISS was collected for chemical analysis. | | | | | | | |
| 17.5 | | | | | | | | |
| 20.0 | • | | • | | | | | |
| 22.5 | | | | | | | | |
| 25.0 | | | | | | | | |
| 27.5 | | | | | | | | |
| 3 0.0 | | | | | | | | |

NOTES:

32.5

MEASURING POINT ELEVATIONS MAY CHANGE; REFER TO CURRENT ELEVATION TABLE

FIGURE 10

CHEMICAL ANALYSIS

WATER FOUND

(L-5)

PROJECT NAME: STAUFFER

HOLE DESIGNATION: BH-5

PROJECT NO.: 2365

DATE COMPLETED: AUGUST 28, 1989

CLIENT:

ICI AMERICAS

DRILLING METHOD: 3 1/4" ID HSA

LOCATION:

N1146216.6 E379450.5

CRA SUPERMSOR: P. SMITH

| | STRATIGRAPHIC DESCRIPTION & REMARKS | ELEVATION | MONITOR | | SAM | |
|--------------|---|--------------|--|----------------------|-----|------|
| BCS | | ft AMSL | INSTALLATION | Z | I S | DS (|
| | GROUND SURFACE | 594.7 | | E . | E | 7 |
| | Coarse to fine SAND, some sitt, trace wood, slog, coment, medium dense, groy brown, dry, (SM)—FILL | | BOREHOLE | 155 | X | 1 |
| 2.5 | SLAG, some silt and sand, trace brick, medium dense, red brown to black, moist, (SM) | 592.7 | | 255 | X | 2 |
| 5.0 | SILT, some clay, trace slag, trace white crystalline material, stiff, dark gray brown moist, (ML) | <i>590.7</i> | STATE OF THE STATE | 325 | X | 1 |
| 7.5 | SILT, some clay, trace coarse sand and fine gravel, medium dense, red brown mottled, maist, (SC)—NATIVE | 588.7 | | 45\$ | X | 1 |
| 10.0 | SILT, some coarse to fine sand and gravel, | 584.7 | | 55\$ | X | 1 |
| | trace clay, medium dense, red brown, maist to dry, (SM) Same, except very dense | 582.7 | | 6S S | X | 2 |
| 12.5 | Fine SAND, some silt, trace day, very dense. | 581.4 | | 75\$ | X | 5 |
| 15.0 | gray brown, moist to wet, (SW) No recovery | <i>580.7</i> | | 8 S \$ | | 60 |
| | END OF HOLE @ 14.4 FT. BGS | 580.3 | A CONTRACTOR OF THE PARTY OF TH | | | |
| 17.5 20.0 | NOTES: 1. Borehole dry at completion. 2. At completion, borehole was grouted to ground surface. 3. 2SS was collected for chemical analysis. | | | | | |
| | | | | | | |
| 22.5 | | | | | | |
| 25.0 | | | | | | |
| 27.5 | , | | | | | |
| • | | · | | | | |
| 30.0 | | | • | | | |
| 32.5 | FIGU | RE 10 | | | | |

CHEMICAL ANALYSIS



STATIC WATER LEVEL

¥

PROJECT NAME: STAUFFER

HOLE DESIGNATION: BH-6

PROJECT NO.: 2365

DATE COMPLETED: AUGUST 28, 1989

(L-6)

CLIENT:

ICI AMERICAS

DRILLING METHOD: 3 1/4" ID HSA

LOCATION: N1146075.4 £379458.6

CRA SUPERVISOR: P. SMITH

| | TRATIGRAPHIC DESCRIPTION & REMARKS ELEVATION MONITOR | | - | SAM | PLE | Ι. | |
|--------------|---|---------------|--------------|------|-------------|----|---|
| BCS | | ft AMSL | INSTALLATION | BECZ | 1 3 | Ę, | |
| | GROUND SURFACE | 5 95.2 | · | Bulg | Ť E | 1 | |
| - | Coarse to fine SAND, some silt, trace coarse to fine gravel, brick, vegetation, dense, brown and gray, dry to moist, (SM)—Fill. | 593.2 | - Lorenale | 155 | X | | |
| 2.5 | Fine SAND, some black tar substance, medium dense, brown to black, moist, (SM) | 591.2 | THE NOTATE | 255 | X | | |
| 5.0 | WOOD, some coarse to fine sand, extremely dense, brown grey, moist | 589.2 | | 355 | \times | | þ |
| 7.5 | SILT, some coarse to fine sand, trace clay and fine gravel, dense, gray red brown, moist, (SM)—NATIVE, TILL Same, except medium dense | 587.2 | | 455 | \boxtimes | | |
| 10.0 | No recovery | <i>585.2</i> | | 55\$ | X | | 1 |
| 12.5 | END OF HOLE @ 11.7 FT. BGS | 583.5 | | 62\$ | \angle | | |
| 15.0 | NOTES: 1. Borehole dry at completion. 2. At completion, borehole was grouted to ground surface. 3. 255 collected for chemical analysis. | | | | | | |
| 17.5 | · | | | | | | |
| 20.0 | | | · | | | | |
| 22.5 | | | | | | | |
| 25 .0 | | | · | | | | |
| 27.5 | | | | | | | |
| 30.0 | | | | | | | |
| 3 2.5 | FIGU | RE 10 | | | | | |

NOTES:

MEASURING POINT ELEVATIONS MAY CHANGE: REFER TO CURRENT ELEVATION TABLE

CHEMICAL ANALYSIS



WATER FOUND STATIC WATER LEVEL

HOLE DESIGNATION: BH-7

PROJECT NAME: STAUFFER

HOLL BLUGON ON DI

PROJECT NO.: 2365

ICI AMERICAS

DRILLING METHOD: 3 1/4" ID HSA

CLIENT: LOCATION:

N1145950.9 E379406.3

CRA SUPERVISOR: P. SMITH

DATE COMPLETED: AUGUST 28, 1989

(L-7)

| DEPTH | STRATIGRAPHIC DESCRIPTION & REMARKS | ELEVATION | | | SAM | PLE | |
|-------------|---|---------------|--------------|-------------|------------|-----|--------------|
| ft BGS | | ft AMSL | INSTALLATION | N. | S | PS | Ŋ. |
| | GROUND SURFACE | 59 5.6 | | M Design | Ť | C L | ∢ LUE |
| | SILT, some fine gravel, very dense, light brown, dry (GM)-FILL | | | iss | V | | 50 |
| - 2.5 | No recovery | 593.6 | TO-CO-CLE | 25\$ | | | 50/1 |
| 5 .0 | SILT, some fine sand, trace clay, trace root structures, very stiff, mottled red brown an | 591.6 | SNI NATE | 35 5 | X | | 21 |
| 7.5 | light gray, dry, (ML)—NATIVE Same, without root structures, hard, red brown | 589.6 | | 45\$ | | | 95/1 |
| - 7.5 | SILT, trace coarse sand, very dense, | 587.6 | | | | | |
| - 10.0 | red brown, moist, (SM)—TILL SILT, some coarse to fine gravel, trace clay, very dense, red brown, moist, (GM) | 586.3 | | 55S 6SS | \Diamond | | 53 |
| | END OF HOLE • 11.3 FT. BGS | 584.3 | | 023 | | | 111/ |
| - 12.5 | NOTES: 1. Borehole dry at completion. 2. At completion, borehole was grouted to ground surface. 3. 5SS collected for chemical | | | | | | |
| - 15.0 | analysis. 4. Stratigraphy from 0.0 to 4.0 ft. BGS taken from initial borehole | | | | | | |
| - 17.5 | 3 ft. south. Borehole moved due to obstruction. | | | | | | |
| - 20.0 | | | | | | | |
| | | | | | | | |
| - 22.5 | | | | | | | |
| - 25.0 | | | · | | | | |
| | | | | | | | |
| - 27.5 | | | | | | | |
| - 30.0 | | | | | | | |
| - 32.5 | | | | | | | |
| | FIGUR | RE 10 | | | | | |
| NOTE | S. MEASURING POINT FLEVATIONS MAY CHANG | | 70.000 | | | | _ |

NOTES:

MEASURING POINT ELEVATIONS MAY CHANGE; REFER TO CURRENT ELEVATION TABLE

CHEMICAL ANALYSIS





HOLE DESIGNATION: BH-8

PROJECT NO.: - 2365

PROJECT NAME: STAUFFER

DATE COMPLETED: AUGUST 28, 1989

(L-8)

CLIENT: ICI AMERICAS

DRILLING METHOD: 3 1/4" ID HSA

LOCATION: N1146106.0 E379598.6

CHEMICAL ANALYSIS

CRA SUPERVISOR: P. SMITH

| H | STRATIGRAPHIC DESCRIPTION & REMARKS | ELEVATION | MONITOR INSTALLATION | - | SAM | PLE | |
|------|---|----------------|-------------------------|---------------|-------------|-----|--------------|
| 3GS | | ft AMSL | INSTALLATION | Ž | Ī | 20 | ' |
| | GROUND SURFACE | 597. 3 | | B | Ē | T | |
| | GRAVEL, some brick and cinders, very dense, gray red and black, dry. (GP)—FiLL | | ойнаг | 15\$ | X | | ; |
| .5 | SILT, some fine sand, trace clay, dense, brown, dry to moist, (ML)—NATIVE | <i>595.3</i> | | 255 | V | | |
| | Same, except brown to red brown | 5933 | EN ON THE | • | (\cdot) | | İ |
| .0 | Some, except extremely dense with slight chemical odor | 591.3 | | 355 | () | | |
| .5 | Same, except ve ry dense | 589.3 | | 455 | \triangle | | 9 |
| | SILT, some fine sand with interbedded clayey | 588.3 | | 5S S | X | | : |
| 0.0 | silt, trace fine gravel, very dense, red brawn, moist to wet, (ML)—TILL Same, with some coarse to fine sand Same, except extremely dense, wet | 587.3 585.3 | | 655 755 | X | | - - |
| 2.5 | END OF HOLE @ 12.8 FT. BGS | 583.3 | | | | | |
| 5.0 | NOTES: 1. Borehole dry at completion. 2. At completion, borehole was grouted to ground surface. 3. 455 and 755 collected for chemical analysis. | · | | | | , | |
| 7.5 | | | | | | | |
| | | | | | | | |
| 20.0 | | | | | | | |
| | | | | | | | |
| 22.5 | | | | | | | ļ |
| 25.0 | | | · | | | | |
| | | | | | | | |
| 27.5 | | | | | | | |
| | | | | | 1 | | |
| 30.0 | | | | | | | |
| | | | | | | | |
| 32.5 | 9 7.01 | ' ' RE 10 | | | | | |
| | FIGU | KE 10 | | | | | |

WATER FOUND STATIC WATER LEVEL ST

PROJECT NAME: STAUFFER

HOLE DESIGNATION: BH-9

PROJECT NO.: 2365

DATE COMPLETED: AUGUST 29, 1989

(L-8)

CUENT:

ICI AMERICAS

DRILLING METHOD: 3 1/4" ID HSA

LOCATION:

N1146215.9 E379617.2

CRA SUPERVISOR: P. SMITH

| | STRATIGRAPHIC DESCRIPTION & REMARKS | ELEVATION | MONITOR INSTALLATION | N | SAM | | יעל ו |
|--------------|--|-------------------------|-------------------------|------|------------|---------------|----------|
| BCS | GROUND SURFACE | ft AMSL | RSTREETING | | Ā | 03.0 4-1-1 | שבר > כצ |
| | Coarse to fine gravel, some coarse to fine sand and silt, trace slag, dense, gray to brown, dry, (GM)—FILL | 595.4 | - MONEHOLE | 155 | X | | 46 |
| 2.5 | FIBER, some coarse to fine sand, medium dense white and brown, dry | | - gylova | 255 | X | | 16 |
| 5.0 | SILT, some clay, trace fine sand, hard, mottled red brown and gray, maist, (CL) | † 1 | a a a | 355 | X | | 69 |
| ٠ | Same, with slight chemical odor | 591.4 | | 455 | \Diamond | | 34 |
| 7.5 | | | | | () | | |
| 10.0 | SILT, some fine sand, interbedded with clayey | 587.4 | | 555 | | | 3. |
| | silt, very stiff, red brown, moist, (ML) Coarse to fine SAND, medium dense, red | 585.9 585.7 585.4 | | 65\$ | X | | 2 |
| 12.5 | brown wet, (GW) Coarse to fine SAND, some clay and siit, medium dense, red brown, moist to wet. (SC)— TILL | | | 755 | X | | 6 |
| 15.0 | SILT, some coarse to fine gravel, trace coarse to fine sand and day, very dense, gray brown. moist to wet, (GM) | 582.4 | A. S. C. | 855 | \times | | 14 |
| | END OF HOLE • 15 FT. BGS | 1 1 | | | | | |
| 17.5 20.0 | NOTES: 1. At completion, a 2.0° ID observation well was installed to 13.0 (t. BGS. 2. Stratigraphy from 6.0 to 8.0 ft. BGS taken from adjacent borehole. 3. 555 and 855 collected for chemical | | | | | | |
| 22.5 | analysis. 4. At completion, water level was 9.4 ft. BGS. | | | | | | |
| 25.0 | | | | | , | | |
| 27.5 | | | | | | | |
| 30.0 | | | | , , | | | |
| į | | | | | | | |
| 32.5 | FIGUE |) PF 10 | | | | | |

NOTES:

MEASURING POINT ELEVATIONS MAY CHANGE; REFER TO CURRENT ELEVATION TABLE

CHEMICAL ANALYSIS

WATER FOUND

(L-10)

PROJECT NAME: STAUFFER

HOLE DESIGNATION: BH-10

PROJECT NO.: 2365

DATE COMPLETED: AUGUST 30, 1989

CLIENT:

ICI AMERICAS

CHEMICAL ANALYSIS

DRILLING METHOD: 3 1/4" ID HSA

LOCATION:

N1146315.2 E379619.8

CRA SUPERVISOR: P. SMITH

STATIC WATER LEVEL

| DEPTH | = | ELEVATION | MONITOR | | SAMI | PLE. | |
|--------|---|-------------------------|--------------|------------------------------|-------------|------|------------|
| ft BGS | | ft AMSL | INSTALLATION | ũ | 1 | EP I | 7 |
| | GROUND SURFACE | 597.4 | | Bala | Ē | + | 10. |
| - | Coarse to fine GRAVEL, trace coarse to fine sond, extremely dense, gray, dry, (GW)—FILL | 596.4 | - Contract | 155 | X | | 160 |
| 2.5 | SILT, some fine sand, extremely dense, red brown, dry, (ML)~NATIVE No recovery | <i>595.4</i> | SOLACI. | 25\$ | \forall | | 82 |
| | Same, except dense, maist | 593.4 | SNI OVIE | | () | | 02 |
| 5.0 | | 591.4 | | 35\$ | \triangle | | 38 |
| 7.5 | SILT, coarse to fine sand, trace clay, extremely dense, red brown, moist, (SM)—TILL Same, except some coarse to fine gravel, | 589.4 | | 455 | X | | 136 |
| | dense | | | 55\$ | V | | 42 |
| 10.0 | Same; except very dense, maist to wet | 587.4 | | 6S S | \forall | | 6 6 |
| 12.5 | | 584.9 | | | () | | |
| | SitT, some clay, trace coarse sand, red brown, maist | 584.4 583.7 583.4 | | 75 \$ 85 \$ | \triangle | | 78 |
| . 15.0 | ISILT, some coarse to fine sand, trace day, fred brown, moist | 582.6 | | 623 | | | 50/ 4 |
| 17.5 | SiLT, some coarse to fine sand, trace coarse to fine gravel and clay, gray brown, moist to wet | | | | | | |
| | END OF HOLE @ 14.8 FT. BGS | | | | | | |
| 20.0 | NOTES: 1. Borehole dry at completion. 2. At completion, borehole was grouted to ground surface. 3. 4SS collected for chemical analysis. | · | | | | | |
| 22.5 | | | | | | | |
| 25.0 | | | : | | | | |
| 27.5 | | | | | | | |
| 27.5 | | | | | | | |
| 30.0 | | | · | | | | |
| 32.5 | FIGU | RE 10 | | | | | |

WATER FOUND

(L-11)

PROJECT NAME: STAUFFER

PROJECT NO .:

2365

CLIENT:

ICI AMERICAS

LOCATION:

N1146312.2 E379832.1

HOLE DESIGNATION: BH-11

DATE COMPLETED: AUGUST 31, 1989

DRILLING METHOD: 3 1/4" ID HSA

CRA SUPERVISOR: P. SMITH

| BCS | STRATIGRAPHIC DESCRIPTION & REMARKS | ELEVATION It AMSL | MONITOR INSTALLATION | N | SAM | | N |
|------|---|----------------------|-------------------------|------|----------|------------|------|
| 000 | GROUND SURFACE | 6 01.7 | | 7 | Ā | DSP L-T | icr. |
| | Augers advanced through asphalt and cement to 2.0 ft. BGS | | 6.5' BORD | IGLE | | | |
| 2.5 | SILT, some clay, trace fine sand, hard, brown mottled, dry to moist, (ML)—FILL | 599.7 | | 15\$ | X | | 3 |
| 5.0 | SILT, some fine sand, trace clay with inter- bedded fine sand, very dense, red brown, dry to moist, (SM)-NATIVE | 597.7 | E NI ONTE | 25\$ | X | | 6. |
| 7.5 | SILT and CLAY, some coarse to fine sand, | 594.7 | | 355 | | | 6. |
| | trace fine gravel, very dense, red brown, moist, (SC)—TILL SILT, some coarse to fine sand, trace coarse | 593.7 | | 455 | X | | 13 |
| 10.0 | to fine gravel with interbedded clayey silt, extremely dense, red brown, maist, (SM) Same, except dry to maist without clayey | 591.7 591.4 | | 555 | <u> </u> | | 100 |
| 12.5 | Silt lenses END OF HOLE ● 10.3 FT. BGS | † † | | | | | |
| 15.0 | NOTES: 1. Barehole dry at completion. 2. At completion, barehole was grouted to ground surface. 3. 3SS collected for chemical analysis. | | | | | | |
| 17.5 | | | | | | | |
| 20.0 | | | | | | | |
| 22.5 | | | | | | | |
| | · | | | | | | |
| 25.0 | | | | | | | |
| 27.5 | | | | | | | |
| 30.0 | | | · | | | | |
| 32.5 | FIGUI | RE 10 | | | | | |

CHEMICAL ANALYSIS

WATER FOUND

HOLE DESIGNATION: BH-12

DRILLING METHOD: 3 1/4" ID HSA

PROJECT NAME: STAUFFER

PROJECT NO.: 2365

DATE COMPLETED: AUGUST 31, 1989

(L-12)

CLIENT:

ICI AMERICAS

CRA SUPERVISOR: P. SMITH

LOCATION: N1146197.6 E379818.9

| IGRAPHIC DESCRIPTION & REMARKS | ELEVATION | MONITOR INSTALLATION | | SAM | ** | _ |
|--|--------------|--|------|-----------|---|-----|
| GROUND SURFACE | ft AMSL | INSTALLATION | | 4> | 1 PE | |
| | au z | | Į į | Ē | Ť | L |
| SAND, some silt and fine gravel, medium e, gray, dry, (SM)—FILL | 538.5 | OREHOLE | 15\$ | X | | |
| some clay and fine sand, very stiff, red and gray mottled, dry, (CL)—NATIVE | 598.2 | | 255 | \bigvee | | |
| n and gray mottled, dry, (CL)—NATIVE c, except dry to moist | 596.2 | EN INVITE | | | | |
| | 594.2 | | 35\$ | X | | |
| some coarse to fine sand, trace coarse ne gravel, extremely dense, red brown, | 394.2 | | 45\$ | × | | h (|
| t to wet. (SM)—TILL some coarse to fine gravel and sand, | 592.2 | | 555 | × | | h (|
| mely dense, red brown, moist, (GM) | 590.2 | | | | | |
| OF HOLE © 10.0 FT. BGS S: 1. Borehole dry at completion. | | | | | | |
| At completion, borehole was grouted to ground surface. 5SS collected for chemical analysis. Augers advanced to refusal | | | | | | |
| | | | | | | |
| | | | | | | İ |
| | | ı | · | | | |
| | | · | i | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| |] | | | | | |
| FIGU | RE 10 | | | | | |
| ME | | FIGURE 10 ASURING POINT ELEVATIONS MAY CHANGE: REFER | | | FIGURE 10 ASURING POINT ELEVATIONS MAY CHANGE: REFER TO CURRENT ELEVATION TABLE | |

CHÉMICAL ANALYSIS

WATER FOUND

(L-13)

PROJECT NAME: STAUFFER

PROJECT NO.: 2365

CLIENT:

ICI AMERICAS

CHEMICAL ANALYSIS

LOCATION:

N1146078.7 E379822.9

HOLE DESIGNATION: BH-13

DATE COMPLETED: AUGUST 31, 1989

DRILLING METHOD: 3 1/4" ID HSA

CRA SUPERVISOR: P. SMITH

| DEPTH It BGS | STRATIGRAPHIC DESCRIPTION & REMARKS | ELEVATION | | | SAM | PLE | |
|-----------------|--|-------------------------|----------------------|----------------------|-------|----------|----|
| IT BGS | GROUND SURFACE | ft AMSL | INSTALLATION | BECZ | S- 4+ | Cr Eb | 7 |
| - | Coarse to fine SAND, some brick, very dense. | 330.0 | 70.7 | F | E / | 7 | E |
| | gray and red, dry, (SM)-FILL | 598.6 | - SOMEHOLE | 155 | X | | 77 |
| 2.5 | Coarse to fine SAND, some silt, trace coarse to fine gravel and brick, dense, gray, moist (SM) | | - CEMENT/ | 2S S | X | | 39 |
| - 5.0 | SILT, some coarse to fine sand and clay, dark gray and brown, maist, (SC) | 596.6 595.1 | GROUT CAROUT | 355 | X | • | 14 |
| | Same, except extremely dense with strong chemical odor | 594.6 594.7 593.6 | | 45\$ | X | | 93 |
| 7.5 | Fine SAND, some silt, extremely dense, brown, NATIVE SILT, some clay, hard, brown, strong chemical | 593.6 | | 5S S | V | | 20 |
| | odor SILT, some coarse to fine sand, trace day and | 591,6 | | | () | | |
| 10.0 | fine gravel, medium dense, red brown, moist, strong chemical odor, (SM)—TILL Same, except very dense | 591.6 590.6 589.6 | | 6 5 \$ | X | | 70 |
| 12.5 | Coorse to fine GRAVEL, some fractured bedrock, gray, moist, (GP) END OF HOLE © 11.0 FT. BGS | | | | | | |
| - 15.0 | NOTES: 1. Borehole dry at completion. 2. At completion, borehole was grouted to ground surface. 3. 355 and 455 were callected with a | | | | | | |
| - 17.5 | 3" split spoon for chemical analysis. | | | | | | |
| 20.0 | | | | | | | |
| | | | | | | | |
| - 22.5 | | | | | | | |
| 25.0 | | | | | | ł | |
| - 27.5 | | | | | | | |
| 27.5 | | ŀ | | | | | ı |
| - 30.0 | | | | i | | | |
| . | | | | | | | |
| 32.5 | FIGUR | E 10 | | | | | |
| NOTE | S: MEASURING POINT ELEVATIONS MAY CHANG | E; REFER 1 | TO CURRENT ELEVATION | TABLE | | | |

WATER FOUND

(L-14)

PROJECT NAME: STAUFFER

HOLE DESIGNATION: BH-14

PROJECT NO.:

2365

DATE COMPLETED: AUGUST 31, 1989

CLIENT:

ICI AMERICAS

DRILLING METHOD: 3 1/4" ID HSA

LOCATION:

N1146291.9 E380044.8

CRA SUPERVISOR: P. SMITH

| | EPTH | | ELEVATION | MONITOR | | SAM | PLE | |
|----|-------------|--|---------------|-------------------|-------------|-------------------|----------|------|
| 11 | BCS | | ft AMSL | INSTALLATION | Z J | 1 | CT EV | Ŋ. |
| | | GROUND SURFACE | 6 05.2 | | E A | Ē | 1 | Ĺ |
| | | | 604.2 | | | | | |
| | 2.5 | SILT, some fine sand, stiff, brown, dry to moist, (ML)—NATIVE | | BORCHOLE | 15\$ | X | | 14 |
| | | Same, except hard | 602.2 | GW NV | 255 | X | • | 54 |
| - | 5.0 | | | | 355 | $\langle \rangle$ | | 37 |
| - | 7.5 | Some, except trace day and fine growel, (CL) | 598.2 | | 45\$ | | | 80/ |
| | | | 505 7 | | | $\langle \rangle$ | | 11 |
| - | 10.0 | Fine SAND, some coarse to fine grovel, trace silt and clay, extremely dense, red brown, moist, (SW)—TILL | 595.7 | | 5S S | X | | 150 |
| - | 12.5 | | | | 655 | \times | | 100, |
| | | END OF HOLE @ 13.5 FT. BGS | · 591.7 | | | İ | | |
| | 15.0 | NOTES: 1. Borehole dry at completion. 2. At completion, borehole was grouted to ground surface. | | | | | | |
| - | 17.5 | 3. 4SS collected for chemical analysis. | | | | | | |
| | 20.0 | | | | | | | |
| | 70 F | | | | | | | |
| | 22.5 | | | | | | | |
| | 25.0 | | | | , | | | , |
| | 27.5 | | | | | | | |
| | 21.3 | <u>-</u> | | · | ' | | | |
| _ | 30.0 | | | | | | | |
| | 32.5 | | .] | | | i | | |
| | | FIGU | RE 10 | | , | | | |
| | NOT | ES: MEASURING POINT ELEVATIONS MAY CHANG | F PFFFD | TO CHERENT PLEASE | 74515 | | | |

CHEMICAL ANALYSIS

WATER FOUND

(L-15)

PROJECT NAME: STAUFFER

HOLE DESIGNATION: BH-15

PROJECT NO.: 2365

DATE COMPLETED: SEPTEMBER 1, 1989

CLIENT:

ICI AMERICAS

DRILLING METHOD: 3 1/4" ID HSA

LOCATION:

N1146225.4 E380004.6

CRA SUPERVISOR: P. SMITH

| EPTH | STRATIGRAPHIC DESCRIPTION & REMARKS | ELEVATION | MONITOR | | SAN | PLE | |
|-------|---|----------------|---|--------------|-------------------|-----|----|
| L BCS | | ft AMSL | INSTALLATION | | Ť | C C | |
| | GROUND SURFACE | 6 02.0 | | B wa: | A E | 1 | i |
| | Augers advanced from 0.0 to 2.5 ft. BGS through brick, gravel and rubble | | тонамо | | | | |
| 2.5 | CINDERS, some coarse to fine sand and wood, dense, black, moist, (SM)—Fill. | 599.5 598.2 | ENENV _E | 155 | \bigvee | | 3 |
| 5.0 | SILT, soem fine sand and clay, very stiff, red brown, moist, (ML)—NATIVE Same, except hard, mottled, moist to wet | 597.5 | Shout The Control of the Control of | 25\$ | $\langle \rangle$ | | |
| 7.5 | Medium to fine SAND, some silt and day, trace gravel, extremely dense, red brown, moist to wet, (SM)—Till. | 595.5 594.1 | | 355 | × | | 10 |
| | END OF HOLE • 7.9 FT. BGS | | | | | | |
| 10.0 | NOTES: 1. At completion, barehole was grouted to ground surface. 2. ISS collected for chemical analysis. 3. Borehole dry at completion. | | | | | | |
| 12.5 | | | · | | | | |
| | | | | | | | |
| 15.0 | | | | | | | |
| 17.5 | | | | i | | | |
| | | | | | | | |
| 20.0 | | | | | | | |
| | | | | | | | |
| 22.5 | | | | | | | |
| 25.0 | | | | | | | |
| 23.0 | | | | | | | |
| 27.5 | | | | | | | |
| | | | | | | | |
| 30.0 | | | | | | | |
| | | | | | | | |
| 32.5 | FIGU | RE 10 | | | | | |
| | · | | | | | | |

CHEMICAL ANALYSIS





PROJECT NAME: STAUFFER

HOLE DESIGNATION: BH-16

PROJECT NO.: 2365

DATE COMPLETED: SEPTEMBER 1, 1989

CLIENT:

ICI AMERICAS

DRILLING METHOD: 3 1/4" ID HSA

(L-16)

LOCATION:

N1146076.7 E380058.9

CHEMICAL ANALYSIS

CRA SUPERMSOR: P. SMITH

STATIC WATER LEVEL

Y

| DEPTH | STRATIGRAPHIC DESCRIPTION & REMARKS | ELEVATION | MONITOR | SA | MPLE |
|-------|--|------------------------|----------------------|--------------|---------|
| # BGS | STRATIGIAN FILE DESCRIPTION TO TEMPERATE | ft AMSL | INSTALLATION | H S | DE D. |
| · | GROUND SURFACE | \$ 01.8 | | M A T E | IČL I A |
| | SILT, some fine sand, trace ash and siag, hard, brown mottled, dry, (ML)—FILL | 1 | - Lockat | 155 | 30 |
| 2.5 | Coarse to fine GRAVEL, some glass and porcelain, hard, light gray, dry, (ML) SILT, some fine sand, trace black dessication, | 600.3 39 9.8 | | 255 | 38 |
| - 5.0 | cracks and vegetation, hard, light gray and red brown mattled, dry, (ML) | 597.8 | AND WE | 35\$ | 33 |
| 3.0 | SILT, some clay, trace clay and vegetation with interbedded fine sand, hard, red brown, (CL)-NATIVE | <i>596.3</i> | | 1 K | |
| 7.5 | Medium to fine SAND, some silt and day and fine gravel with interbedded silty day, very dense, red brown, moist, (SC)— ILL | | | 45 \$ | 79 |
| | END OF HOLE . 8.8 FT. BGS | 593.0 | | 1 1 | 1 |
| 10.0 | NOTES: 1. Borehole dry at completion. 2. At completion, borehole was grouted to ground surface. | | | | |
| 12.5 | 3. 3SS collected for chemical analysis. | | | | |
| 15.0 | | | · | | |
| | | | | | |
| 17.5 | | | | | |
| 20.0 | | | | | |
| 22.5 | | | | | |
| 22.5 | | | | | |
| 25.0 | | | | | |
| 27.5 | | | | | |
| | | | | | |
| 30.0 | | | | | |
| 32.5 | FIGU | RE 10 | | | |
| | | <u> </u> | | | |
| NOT | ES: MEASURING POINT ELEVATIONS MAY CHAN | GE; REFER | TO CURRENT ELEVATION | TABLE | |

WATER FOUND

(L-17)

PROJECT NAME: STAUFFER

PROJECT NO.: 2365

CLIENT:

ICI AMERICAS

LOCATION:

N1146300.6 E380195.7

HOLE DESIGNATION: BH-17

DATE COMPLETED: SEPTEMBER 5, 1989

DRILLING METHOD: 3 1/4" ID HSA

CRA SUPERVISOR: P. SMITH

STATIC WATER LEVEL

| | STRATIGRAPHIC DESCRIPTION & REMARKS | ELEVATION | MONITOR | | SAM | | |
|--------------|---|-----------|--------------|------|-------|------|-------------|
| BGS | | ft AMSL | INSTALLATION | OKCZ | Ş | OF C | 1 |
| | GROUND SURFACE | 607.1 | | DER | A T E | 1 | |
| 2.5 | Augers advanced to 3.0 ft. BGS, through asphalt, stone and slag | | - Polichort | | | | |
| 2.5 | SiLT, some fine sand, trace clay and fine gravel, medium dense, red brown to brown | 604.1 | GNIN/E | 155 | X | | ; |
| 5.0 | mottled, dry to moist, (SM)—NATIVE, TILL Same, with interbedded silty fine sand | 602.1 | | 25\$ | | | |
| 7.5 | Medium to fine SAND, some silt, trace coarse to fine gravel and clay, extremely dense, | 600.1 | | 355 | | | 5 |
| 10.0 | red brown, moist. (SM) END OF HOLE • 8.7 FT. BGS | 598.4 | | | | | ' |
| 10.0 | NOTES: 1. Borehole dry at completion. 2. At completion, borehole was grouted to ground surface. 3. 2SS collected for chemical analysis. | | | | | | |
| 12.5 | 3. 255 collected for chemical shalysis. | | | | | | |
| 15.0 | | | | | | | |
| 17.5 | | | | | | | |
| 20.0 | | | | | | | |
| 5 0.5 | · . | | | | | | |
| 22.5 | · | | | | | | |
| 25.0 | , | | | | | | |
| 27.5 | | | | | | | |
| 30.0 | | | | | | | |
| ••• | | | · | | | | |
| 32.5 | FIGU | RE 10 | | | | | |

WATER FOUND

CHEMICAL ANALYSIS

PROJECT NAME: STAUFFER

HOLE DESIGNATION: BH-18

PROJECT NO .:

2365

DATE COMPLETED: SEPTEMBER 5: 1989

CLIENT:

ICI AMERICAS

DRILLING METHOD: 3 1/4" ID HSA

(L-18)

LOCATION:

N1146301.5 E380359.6

CRA SUPERVISOR: P. SMITH

MONITOR SAMPLE FLEVATION DEPTH STRATIGRAPHIC DESCRIPTION & REMARKS INSTALLATION ft AMSL ft BGS ĀTE 608.9 GROUND SURFACE Augers advanced to 1.0 ft. BGS, through 607.9 asphalt and gravel SOSEHOLE CLAY, some silt and sand, very stiff, light brown to gray mottled, dry to moist, (CL)-155 17 2.5 605.9 FILL SILT, some sond and clay, trace vegetation, 255 25 very stiff, light to dark gray mottled, rust stained, dry, (ML) 603.9 5.0 Same, except hard 602.9 355 50 Fine SAND, some silt, very dense, light brown, dry, (SM)-NATIVE 601.9 7.5 455 Fine SAND, some silt and clay, trace vegetation, trace fine gravel, very stiff, ligh 16 600.2 to dark brown, dry. (ML) END OF HOLE @ 8.7 FT. BGS 10.0 NOTES: 1. Borehole dry at completion. 2. At completion, borehole was grouted to ground surface.
3. 455 collected for chemical analysis. 12.5 15.0 17.5 20.0 22.5 25.0 27.5 30.0

NOTES:

32.5

MEASURING POINT ELEVATIONS MAY CHANGE; REFER TO CURRENT ELEVATION TABLE

FIGURE 10

CHEMICAL ANALYSIS

WATER FOUND

STATIC WATER LEVEL

X

(L-18)

PROJECT NAME: STAUFFER

HOLE DESIGNATION: BH-19

PROJECT NO.: 2365

DATE COMPLETED: SEPTEMBER 5. 1989

CLIENT:

ICI AMERICAS

DRILLING METHOD: 3 1/4" ID HSA

LOCATION: N1146325.3 E380588.2

CRA SUPERVISOR: P. SMITH

| EPTH | STRATIGRAPHIC DESCRIPTION & REMARKS | ELEVATION | MONITOR | | SAMPLE | |
|-------|---|----------------|--|-------------|------------------|-----|
| t BCS | | ft AMSL | INSTALLATION | BECZ | S DSP CL T | , Y |
| | GROUND SURFACE | <i>611.0</i> | and the second s | Đ.L.R | Ė | Į į |
| | Fine SAND, some silt, trace fine gravel and vegetation, light brown to brown, dry, (SM)-NATIVE | 6094 | - BOSEHOLE | 155 | X | 18 |
| 2.5 | SILT, some clay and fine sand, brown, dry. (ML) SILT, some clay, trace vegetation, dry. | 609.4 609.0 | | 2S S | Δ | 51 |
| | brown and light gray motited, dry, (ML) Fine SAND, some silt, trace fine gravel, red brown, dry, (SM)—Till | 607.6 | BUN'TE | | () | |
| 5.0 | | 604 7 | | 355 | | 84 |
| 7.5 | Same, except moist END OF HOLE © 6.7 FT. BGS | 604.3 604.3 | | | | |
| , | NOTES: 1. Borehole dry at completion. 2. At completion, borehole was grouted to ground surface. 3. 3SS collected for chemical | | | | | |
| 10.0 | grouted to ground surface. 3. 3SS collected for chemical analysis. | | | | | |
| 12.5 | | | | | | |
| 15.0 | | | | | | |
| | | | | | | |
| 17.5 | | | | | | |
| | | | | | | ļ |
| 20,0 | | | · | | | |
| 22.5 | | | | | | |
| | | | | | | |
| 25.0 | | | | | | |
| 27.5 | | | | | | |
| _, | | | | | | |
| 30.0 | | | | | | |
| | | | | | | |
| 32.5 | 4 | RE 10 | | | | |
| | | | | | | |

CHEMICAL ANALYSIS





(L-20)

PROJECT NAME: STAUFFER

PROJECT NO.: 2365

CLIENT:

ICI AMERICAS

LOCATION:

N1146083.1 E380184.6

HOLE DESIGNATION: BH-20

DATE COMPLETED: SEPTEMBER 6, 1989

DRILLING METHOD: 3 1/4" ID HSA

CRA SUPERVISOR: P. SMITH

| | STRATIGRAPHIC DESCRIPTION & REMARKS | ELEVATION | . MONITOR INSTALLATION | | SAMF | | |
|--------|---|----------------|------------------------|-------|------|------|----------|
| IL BCS | | ft AMSL | M3 IALLA IIUN | - Z | | DS T | 'n. |
| | GROUND SURFACE | 605.9 | | 10-10 | Ť | + | Ĺ |
| | Augers advanced to 1.5 ft. BGS, through coment obstruction | | | | | | - |
| 2.5 | Coarse to fine GRAVEL, some sitt and sand, medium dense, brown and gray, dry to moist, (GM)—FitLL | 604.4 | CONTROL OF | 15\$ | X | 1 | 12 |
| | No recovery | 602.4 | EN NA | 255 | | | 4 |
| 5.0 | Same, except gray, moist | 600.9 | | | K | - 1 | |
| | Gray SAND and GRAVEL, dry | 59 9.9 | | 355 | XI | 1 | 15 |
| 7,5 | Coarse to fine SAND, some sitt, trace clay, red brown, dry to moist, (SM)—NATIVE, TILL END OF HOLE © 7.3 FT. BGS | 598.7 598.6 | | 455 | | 10 | 00/ 4 |
| 10.0 | NOTES: 1. Borehole dry at completion. 2. At completion, borehole was grouted to ground surface. 3. 3SS and 4SS collected for chemical | | | | | | |
| 12.5 | analysis. | | | | | | |
| 15.0 | | | | | | | |
| 17.5 | | | | | | | |
| 20.0 | | | | | | | |
| 22.5 | · | | | | | | |
| 25.0 | | | , | | | | |
| 27.5 | | | | | | | |
| 30.0 | | | | | | | |
| 32.5 | FIGUR | E 10 | | | | | |
| NOT | ES: MEASURING POINT ELEVATIONS MAY CHANG | GE; REFER | TO CURRENT ELEVATION | TABLE | | | _ |

CHEMICAL ANALYSIS

WATER FOUND

(L-21)

PROJECT NAME: STAUFFER

HOLE DESIGNATION: BH-21

PROJECT NO.: 2365

DATE COMPLETED: SEPTEMBER 5. 1989

CLIENT:

ICI AMERICAS

CHEMICAL ANALYSIS

DRILLING METHOD: 3 1/4" 10 HSA

STATIC WATER LEVEL

LOCATION:

N1146075.6 E380363.5

CRA SUPERMSOR: P. SMITH

| | STRATIGRAPHIC DESCRIPTION & REMARKS | ELEVATION | MONITOR | | SAM | PLE | |
|---------------|---|------------|----------------------|---------|-----------|----------|----------|
| ft BGS | | ft AMSL | INSTALLATION | ž U | \$ | 05 EP | , M |
| | GROUND SURFACE | 610.3 | | M Bluck | A T | CL | 4 |
| | SILT, some medium to fine sand, trace veg- etation, loose, brown, dry. (SM)-FILL | 609.3 | - 15 EHOLE | 15\$ | X | | 8 |
| 2.5 | Coorse to fine SAND, some fine gravel, loose, gray, dry, (SP) No recovery | 608.3 | | 25\$ | | | 16 |
| 5.0 | Medium to fine SAND, some silt and day, red brown, dry. (SC)-NATIVE, Titl | 606.3 | ENIOVIE | 35\$ | X | | 19 |
| 7.5 | Same, except trace fine gravel, maist | 604.3 | | 45\$ | X | | 116 |
| 7.5 | | · | | 55\$ | \bowtie | | 100/ |
| 10.0 | END OF HOLE @ 10.2 FT. BGS | 600.1 | | | | | |
| 12.5 | NOTES: 1. Borehole dry at completion. 2. At completion, borehole was grouted to ground surface. 3. 3SS collected for chemical analysis. | | · · · | | | | |
| 15.0 | | | | | | | |
| 17.5 | | | | | | | |
| 20.0 | | | | | | | |
| 22.5 | | | | | | | |
| 25.0 | | | | | | | |
| 27.5 | | | | | | | |
| - 30.0 | | | | | | | |
| 32.5 | FIGU | ЛRE 10 | | | | | |
| - 32.5 NOT | | <u> </u> | TO CURRENT ELEVATION | TABLE | | | |

WATER FOUND

HOLE DESIGNATION: BH-24

PROJECT NAME: STAUFFER PROJECT NO.: 2365

DATE COMPLETED: SEPTEMBER 7, 1989

(L-24)

CLIENT:

ICI AMERICAS

DRILLING METHOD: 3 1/4" ID HSA

LOCATION:

N1145861.2 E380338.7

CRA SUPERVISOR: S. SURPRENANT

| DEPTH | STRATIGRAPHIC DESCRIPTION & REMARKS | DEVATION | MONITOR | | SAMP | LE |
|--------|---|---------------|--|-------------|----------|-------|
| ft BCS | | ft AMSL | INSTALLATION | | P | EP N. |
| | GROUND SURFACE | 6 10.0 | | BLIC | ŤE | C |
| | Coarse to fine GRAVEL, some sitt, trace brick and slag, medium dense, gray brown, dry. (GM)—FILL | 608.0 | - CONEHOLE | 15\$ | X | 11 |
| 2.5 | SILT, some clay, stiff, gray brown, dry. (ML)-NATIVE | | CONTRACT | 25 5 | X | 15 |
| a* a | Some, except very stiff, red brown, dry to moist | 60 6.0 | THE NAME OF THE PARTY OF THE PA | 755 | H | 30 |
| 5.0 | Some, except trace day | 604.0 | | 355 | Θ | 30 |
| 7.5 | Fine SAND, some sitt, trace clay and fine gravel, medium dense, red brown, dry to mois | 603.0 | | 455 | A | 31 |
| - 10.0 | | 600.2 | | 555 | X | 33 |
| 10.0 | END OF HOLE © 9.8 FT. BGS NOTES: 1. At completion, barehole was | | | | . | |
| 12.5 | grouted to ground surface. 2. 3SS and 4SS collected for chemical analysis. 3. Borehole dry at completion. | | | | | |
| - 15.0 | 3. Borenole dry at completion. | | | | | - |
| 13.0 | | | | | | |
| - 17.5 | · | | | | | |
| | : | | | | | |
| - 20.0 | | | | | | |
| - 22.5 | · | | · | | | |
| | | | | | | |
| - 25.0 | | | | | | |
| 27.5 | | | | | | |
| | | | | | | |
| - 30.0 | | | | | | |
| - 32.5 | | | | | | |
| 92.0 | 1 | RE 10 | | | | |
| | · · · · · · · · · · · · · · · · · · · | | | <u> </u> | 1_1 | |

NOTES:

MEASURING POINT ELEVATIONS MAY CHANGE; REFER TO CURRENT ELEVATION TABLE

CHEMICAL ANALYSIS

WATER FOUND

(L-26)

PROJECT NAME: STAUFFER

HOLE DESIGNATION: BH-26

PROJECT NO.: 2365

DATE COMPLETED: SEPTEMBER 5, 1989

CLIENT: ICI AMERICAS

DRILLING METHOD: 3 1/4" ID HSA

LOCATION:

N1145874.9 E380176.7

CRA SUPERVISOR: P. SMITH

| GROUND SURFACE BRICK, some coarse to fine sand and gravel, trace cinders, dense, dark gray and arange, dry, (GM)—FILL No recovery | 604.2 | INSTALLATION BOREHOLE WHITE ACUT THE NAME OF THE N | 155 255 | | SP. |
|---|--|--|--|--|---|
| trace cinders, dense, dark gray and arange, dry, (GM)—FILL No recovery | | | | X | |
| No recovery | | | 255 | X | |
| | | EN TONTE | f | | 1 ' |
| SILT same fine sand and riov hard brown | 1 | | | H | Ī |
| SILL SOME TIME SANG AND MAY BOTH DENWA | 602.2 | | 355 | \square | |
| SILT, some fine sand and day, hard, brown, dry to maist, (ML)—NATIVE No recovery | 600.2 | | 455 | X | |
| END OF HOLE & 8.6 FT. BGS | 599.6 | | 333 | | h (|
| NOTES: 1. At completion, borehole was grouted to ground surface. 2. 4SS collected for chemical analysis. | | I | | | |
| 3. Borehole dry at completion. | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| Figu | RE 10 | | | | |
| | END OF HOLE © 8.6 FT. BGS NOTES: 1. At completion, borehole was grouted to ground surface. 2. 4SS collected for chemical analysis. 3. Borehole dry at completion. | END OF HOLE © 8.6 FT. BGS NOTES: 1. At completion, borehole was grouted to ground surface. 2. 4SS collected for chemical analysis. 3. Borehole dry at completion. FIGURE 10 | END OF HOLE © 8.6 FT. BGS NOTES: 1. At completion, borehole was grouted to ground surface. 2. 45S collected for chemical analysis. 3. Borehole dry at completion. | END OF HOLE © 8.6 FT. BGS NOTES: 1. At completion, borehole was grouted to ground surface. 2. 4SS collected for chemical analysis. 3. Borehole dry at completion. | END OF HOLE © 8.6 FT. BGS NOTES: 1. At completion, borehole was grouted to ground surface. 2. 4SS collected for chemical analysis. 3. Borehole dry at completion. FIGURE 10 |

CHEMICAL ANALYSIS

WATER FOUND

STATIC WATER LEVEL

Y

(L-27)

PROJECT NAME: STAUFFER

HOLE DESIGNATION: BH-27A

PROJECT NO.: 2365

DATE COMPLETED: SEPTEMBER 8, 1989

CLIENT:

ICI AMERICAS

DRILLING METHOD: 3 1/4" ID HSA

LOCATION:

N1145866.1 E380031.8

CRA SUPERVISOR: S. SURPRENANT

| | STRATIGRAPHIC DESCRIPTION & REMARKS | ELEVATION | MONITOR | | SAM | | |
|-------|--|----------------|--|-------------|-------------------------|-------------|------|
| BCS | | ft AMSL | INSTALLATION | MUKCZ | Ş | ביר ספיר |) cz |
| | GROUND SURFACE | 60 6.2 | | B E R | Ē | | ١ |
| | Augered to 4.0 ft BGS | | | | | | |
| | (refer to BH-27 for stratigraphy in upper 4 ft of column) | | OSEHOLE | | | | |
| 2.5 | • | | | | | | |
| | | 602.2 | S NEW YEAR | | | | ŀ |
| 5.0 | SILT, some coarse to fine sand and clay, trace cinders, loose, red brown, maist, (SM)—fill | | GROUT - | 155 | \bigvee | | ١, |
| | (| | | | \triangle | | ` |
| | | | | 255 | \bigvee | | : |
| 7.5 | Fine SAND, some silt, trace fine gravel, very | 598.4 | | | $\langle L \rangle$ | | |
| | loose, red brown, moist, (SM) | 597.4 | | 355 | łΧ | | ۱, |
| 10.0 | SILT, trace glass and cinders, soft, black, moist, (ML) | 596.4 596.2 | | | $\langle \cdot \rangle$ | | İ |
| | Fine SAND, some silt, trace fine grovet, | 594.2 | | 455 | IX | | 2 |
| 2.5 | loose, red brown, maist, (SM)—NATVE. Same, with trace clay and coarse gravei. | 594.1 | RECORD TO THE RESERVE | 555 | \leftarrow | | 101 |
| 2.0 | medium dense No recovery | | • | | | | |
| | END OF HOLE # 12.1 FT. BGS | 1 | | | | | |
| 5.0 | NOTES: 1. At completion, barehole was grouted to ground surface. | | | | | | |
| | 2 355 collected for | | | | | | |
| 17.5 | chemical analysis. 3. BH-27A is a continuation | | | | ŀ | | |
| | of BH-27. | | | | ļ | | |
| 20.0 | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| 22.5. | | | | | | | |
| | | | | 1 | | | |
| 25.0 | | | | | | | |
| | | | | | | | |
| 77 5 | | | | | | | |
| 27.5 | | | | | | | |
| | | | | | | | |
| 30.0 | | İ | • | | | | |
| | | | | | | | |
| 32.5 | | · . | | | | | |
| | FIGU | RE 10 | | | | | |
| - 1 | | | | | | | |

NOTES:

MEASURING POINT ELEVATIONS MAY CHANGE: REFER TO CURRENT ELEVATION TABLE

CHEMICAL ANALYSIS

WATER FOUND

(L-28)

PROCECT NAME: STAUFFER

HOLE DESIGNATION: BH-28

PROJECT NO.: 2365

DATE COMPLETED: SEPTEMBER 8, 1989

CLIENT:

ICI AMERICAS

DRILLING METHOD: 3 1/4" ID HSA

LOCATION:

N1145758.6 E380127.1

CRA SUPERMSOR: P. SMITH

| DEPTH IL BGS | STRATIGRAPHIC DESCRIPTION & REMARKS | ELEVATION | | I . | SAN | D 2 | |
|-----------------|--|-----------|--------------|----------------------------|--------------|------|------------|
| | ······································ | ft AMSL | INSTALLATION | N | 337 | DS | , M. |
| | GROUND SURFACE | 605.9 | | 3 M B M C | ATE | CL T | JC - > C |
| 2.5 | Coarse to fine GRAVEL, some sond, sing and brick, dense, gray to black, dry, (GM)—FILL Same, except medium dense | 6019 | Воленац | 15\$ | X | | 43 |
| 2.5 | Same, except extremely dense, moist | 602.4 | - SALLANDE | 25 5 35 5 | X | | 27 50/4 |
| 3.0 | Same, except loose, maist to wet | 600.9 | 2 001 | | | | · |
| | Same, with some metal slag | 599.4 | | 4SS 5SS | \bigotimes | | 5 |
| 7.5 | Same, without metal slag, wet | 597.9 | | 65\$ | | | 7 50/4 |
| - 10.0 | END OF HOLE • 9.4 FT. BGS | 596.5 | | | | | |
| | NOTES: 1. At completion, borehole was grouted to ground surface. 2. No samples collected for chemical | | | | | | |
| 12.5 | analysis. 3. Borehole dry at completion. | | | | | | |
| - 15.0 | | | | | | | |
| 17.5 | | | | | | | |
| - 20.0 | | | | | | | |
| - 22.5 | | | | | | | |
| 25.0 | - | | | | | | |
| - 27.5 | | | | | | | |
| - 30.0 | | | | | | | |
| | | | | | · | | |
| - 32.5 | FIGU | RE 10 | | | | | |

MEASURING POINT ELEVATIONS MAY CHANGE; REFER TO CURRENT ELEVATION TABLE TES: WATER FOUND X STATIC WATER LEVEL X THEMICAL ANALYSIS

PROJECT NAME: STAUFFER

HOLE DESIGNATION: BH-2BA

PROJECT NO.: 2365

DATE COMPLETED: SEPTEMBER 11, 1989

(L-29)

CLIENT:

ICI AMERICAS

DRILLING METHOD: 3 1/4" ID HSA

LOCATION:

N1145758.6 E380098.6

CRA SUPERVISOR:

P. SMITH

| DEPTH | STRATIGRAPHIC DESCRIPTION & REMARKS | ELEVATION | MONITOR | | SAM | | |
|----------------|---|----------------|--------------|--------------|-----|------------|----------|
| ft BCS | | ft AMSL | INSTALLATION | N U | Ş | C C F b | N. |
| | GROUND SURFACE | 6 05.9 | | P L | Ā | | Ü |
| | SILT, trace clay, slag and coarse to fine gravel, very stiff, brown, dry to moist, (ML)+FiLL | | - Concinct | 15\$ | X | | 19 |
| 2.5 | Same, with some clay, stiff | 602.4 | END VIE | 2S\$ 3S\$ | X | | 23 13 |
| - 5.0 | | 600.1 | | | K | ļ. | |
| - 7.5 | SILT, some medium to fine sand and clay. trace fine gravel, loose, brown, moist to wet, (SM)—TILL Same, except very dense | 598.9 | | 4S\$ 5S\$ | | | 5 59 |
| | No recovery | 596.9 596.6 | | 655 | | | 50/0 |
| 10.0 | END OF HOLE • 9.3 FT. BGS NOTES: 1. At completion, barehole was | 330.0 | | | | | |
| 12.5 | grouted to ground surface. 2. 4SS collected for chemical analysis. 3. Borehole dry at completion. | | | | | | |
| | | | | | | | |
| 15.0 | | | | | | | |
| 17.5 | | | | | | | |
| - 20.0 | | | | | | | |
| 22.5 | | | | | | | |
| - 25.0 | | | | | | | |
| 23.0 | | | | | | | |
| - 27.5 | | | | | | | |
| - 3 0.0 | | | | | | | |
| | | | | | | | |
| - 32.5 | FIGU | RE 10 | | | | | |

NOTES:

MEASURING POINT ELEVATIONS MAY CHANGE; REFER TO CURRENT ELEVATION TABLE

CHEMICAL ANALYSIS

WATER FOUND

(L-30)

PROJECT NAME: STAUFFER

HOLE DESIGNATION: BH-29

PROJECT NO.: 2365

DATE COMPLETED: SEPTEMBER 11, 1989

CLIENT:

ICI AMERICAS

DRILLING METHOD: 3 1/4" ID HSA

LOCATION:

N1145758.6 E379812.4

CRA SUPERMSOR: P. SMITH

| | STRATIGRAPHIC DESCRIPTION & REMARKS | ELEVATION | MONITOR | | SAM | | |
|------|--|----------------|--------------|------|-------------|----|----|
| BGS | | fft ABAGS | INSTALLATION | 4 3 | Ş | DS | 1 |
| | GROUND SURFACE | 602.9 | | | Ē | C. | |
| | Coarse to fine SAND, some silt, trace coarse to fine gravel, trace brick and siag, extremely, dense, gray and brown, dry. (SM)—Fill. | 600.9 | BOXEHOLE | 15\$ | X | | 7 |
| 2.5 | SILT, some clay—like compound, trace clay, hard, gray to black, moist | , | CEWENT/ | 255 | X | | 3 |
| 5.0 | CLAY, some silt, trace fine sand, very stiff, mottled brown and gray, moist, (CL)—NATIVE SILT, some clay and fine sand, very stiff, | 599.1 597.9 | | 355 | \boxtimes | • | 2 |
| | red brown, moist, (ML) | 595.9 | | 455 | X | | 3 |
| 7.5 | Fine SAND, some silt, trace clay and fine gravel, extremely dense, red brown, moist, (SM)—TILL | 3933 | | 555 | \bowtie | | 10 |
| 10.0 | Same, with trace coarse to fine gravel | 593.4 | | 65\$ | \nearrow | | 7 |
| | Same, except dense | 591.4 | | | | | |
| 12.5 | | 589.3 | | 75\$ | X | _ | 4 |
| 15.0 | END OF HOLE © 13.6 FT. BGS NOTES: 1. At completion, borehole was grouted to ground surface. 2. 3SS collected for chemical analysis | | | | | | |
| 17.5 | and split with State DEC. 3. 3SS and 4S\$ sampled with 3—inch split spoon. 4. Barehole dry at completion. | | | | | | |
| 20.0 | | | | | | | |
| 22.5 | · | | | | | | |
| 22.5 | | | | | | | |
| 25.0 | | | , | | | | |
| 27.5 | | | | | | | |
| | | | | | | | |
| 30.0 | | | | | | | |
| 32.5 | | 1 | | | : | | |
| | FIGU | RE 10 | | | | | |

NOTES:

MEASURING POINT ELEVATIONS MAY CHANGE; REFER TO CURRENT ELEVATION TABLE

CHEMICAL ANALYSIS



PROJECT NAME: STAUFFER

HOLE DESIGNATION: BH-30

PROJECT NO.: 2365

DATE COMPLETED: NOVEMBER 15, 1989

(L-31)

CLIENT:

ICI AMERICAS

DRILLING METHOD: 4 1/4" ID HSA

CRA SUPERVISOR: S. SURPRENANT

| | STRATIGRAPHIC DESCRIPTION & REMARKS | ELEVATION | MONITOR | | SAM | | |
|--------------|---|-----------|--------------|----------------------|-----------------------|----------|----|
| BCS | | ft AMSL | INSTALLATION | N C | S T A T E | Cr Eb | 1 |
| | GROUND SURFACE | 620.0 | | | E | + | |
| | SILT, some coarse to fine gravel, trace fine sand, very loose, red brown, moist, (GM)—FIL | 618.0 | - LOS HOLE | 155 | X | | |
| 2.5 | Fine SAND, trace coarse to fine gravel, silt and clay, medium dense, red brown, moist, (SP) | 616.0 | THE REST | 25\$ | X | | 1 |
| 5.0 | Some, except dense, dry | 375.5 | 801 | 355 | X | | 4 |
| | Same, with trace slag, medium dense | 614.0 | | 455 | \Diamond | | , |
| 7.5 | SILT and fine SAND, some slag, trace coarse | 612.0 | | | | | |
| 10.0 | to fine grave!, loose, black and brown, moist, (SM) | 610.0 | | 5 S \$ | X | | |
| , 0.0 | Fine SAND, some slag and coarse to fine gravel, trace silt, clay and cloth, medium dense, mattled black and brown, dry to maist | 5,5.5 | | 655 | X | | 1 |
| 12.5 | (\$P) Same, without slag and cloth, loose, yellow | 608.0 | | 755 | X | | ! |
| 15.0 | Fine SAND, trace coarse to fine gravel, very loose, gray, moist, (SP) | 606.0 | | 855 | X | | : |
| | Fine SAND, some silt, trace coorse to fine gravel, loose, red brown, wet, (SM) | 604.0 | | 955 | | | ۱, |
| 17.5 | CLAY and SILT, soft, brown, dry to moist moist (CL)-NATIVE | 601.5 | | | \vdash | | |
| 20.0 | END OF HOLE © 18.5 FT. BGS NOTES: 1. 6SS collected for chemical analysis. 2. At completion, borehole was grouted to ground surface. | | | | | | |
| 22.5 | 3. Borehole dry at completion. | | | | | | |
| 25.0 | | | | | | | |
| | | | | | | | |
| 27.5 | · | | | | | | |
| 3 0.0 | | | | | | | |
| 32.5 | · | | | | | | |
| د.عد | | URE 10 | | 1 | 1 | | |

NOTES:

MEASURING POINT ELEVATIONS MAY CHANGE: REFER TO CURRENT ELEVATION TABLE

CHEMICAL ANALYSIS

WATER FOUND

PROJECT NAME: STAUFFER

HOLE DESIGNATION: BH-31

PROJECT NO.: 2365

DATE COMPLETED: DECEMBER 11, 1989

DRILLING METHOD: 3 1/4" ID HSA

(L-38)

CLIENT:

ICI AMERICAS

| LOCATI | ON: N1145929.2 E381268.1 | | CRA SUPERVISOR: | P. VOLI | PE | | |
|--------|---|------------------|-----------------|--------------|--------------|-----|------------|
| | STRATIGRAPHIC DESCRIPTION & REMARKS | ELEVATION | | | SAM | | |
| ft BGS | GROUND SURFACE | ft AMSL 621.5 | INSTALLATION | A DE MICE | A T E | DEC | 10 P & & & |
| - 2.5 | SILT, some sand and gravei, loose, red brown dry, (ML)—FILL Same, except dry to moist | | - Kone Hall | 15\$ | X | | 7 |
| 5.0 | Some, except some slag, medium dense, moist to wet | | THE NAME | 25\$ 35\$ | \bigotimes | | 7 |
| 7.5 | Fine SAND, some silt, clay and gravel, trace slag, medium dense, red brown, dry to moist, (SM) | 615.5 | | 45\$ | | | 13 |
| 10.0 | Fine SAND, some gravel and slag, loose, black and yellow, dry, (SP) | 613.5 | | 55\$ | X | | 9 |
| 12.5 | CLAY and SiLT, some sand, trace gravel, stiff, red brown, dry to moist, (ML)—NATIVE | | | 65\$ | X | | 8 |
| - 15.0 | END OF HOLE © 14 FT. BGS NOTES: 1. Borehole dry at completion. | 607.5 | | 75 \$ | X | | 9 |
| 17.5 | NOTES: 1. Borehole dry at completion. 2. At completion, borehole was grouted to ground surface. 3. 3SS collected for chemical analysis. | | | | | | |
| 20.0 | | , | | | | | |
| - 22.5 | | | | | | | |
| - 25.0 | · | | | | | | |
| 27.5 | | - | | | | | |
| - 30.0 | | | | | | | |
| - 32.5 | FIGU | 1 RE 10 | | | | | |
| | FIGUI | RE 10 | | | | | |

NOTES:

MEASURING POINT ELEVATIONS MAY CHANGE; REFER TO CURRENT ELEVATION TABLE

CHEMICAL ANALYSIS

WATER FOUND T STATIC WATER LEVEL T

(L-39)

PROJECT NAME: STAUFFER

HOLE DESIGNATION: BH-32

PROJECT NO.: 2365

DATE COMPLETED: DECEMBER 11, 1989

CLIENT:

ICI AMERICAS

DRILLING METHOD: 3 1/4" ID HSA

LOCATION:

N1146012.1 E381372.7

CRA SUPERVISOR: P. VOLPE

| | STRATIGRAPHIC DESCRIPTION & REMARKS | ELEVATION | | | SAM | PLE. | |
|--------------|---|-----------|--------------|------|-------------|----------|-----|
| BGS | | ft AMSL | INSTALLATION | -ŭ | | ĽÞ ĽÞ | Å. |
| | GROUND SURFACE | 623.6 | | BLAR | Ē | Cr | E L |
| - | SILT, some gravel and fine sand, loose, red brown, dry to moist, (ML)—FiLL | 621.6 | - Love Hale | 155 | X | | 5 |
| 2.5 | Fine SAND, some silt and sigg, medium dense, black and red brown, dry to moist, (SM) | 619.6 | G MENT/ | 255 | \boxtimes | | 7 |
| 5.0 | CLAY and SILT, some fine sand, red brown, very stiff, maist, (ML) | 617.6 | Gloù1 | 355 | X | | 5 |
| 7.5 | CLAY, some silt, red brown, very stiff, moist, (CL)-NATIVE | 617.6 | | 455 | \boxtimes | | 11 |
| 10.0 | END OF HOLE @ 10 FT. BGS | 613.6 | | 555 | X | | 28 |
| 12.5 | NOTES: 1. Borehole dry at completion. 2. At completion, borehole was grouted to ground surface. 3. 455 collected for chemical | | | | | | |
| ,12.5 | 455 collected for chemical analysis. | | | | | | |
| 15.0 | | | | | | | |
| 17.5 | | | | | | | |
| 20.0 | | | | | | | |
| 22.5 | | | | | | | |
| 25.0 | | | | | | | |
| | | | | | | | |
| 27.5 | | | · | | | | ! |
| 30.0 | | | | | | | |
| 32.5 | 77.01 | | | | | | |
| 32.5 | FIGU | RE 10 | | | | | |

NOTES:

MEASURING POINT ELEVATIONS MAY CHANGE; REFER TO CURRENT ELEVATION TABLE

GRAIN SIZE ANALYSIS

WATER FOUND ____

(L-53)

PROJECT NAME: STAUFFER

PROJECT NO.: 2365

CLIENT:

ICI AMERICAS

CHEMICAL ANALYSIS

LOCATION: SMALL LANDFILL, NORTH

HOLE DESIGNATION: BH-34

DATE COMPLETED: MARCH 5, 1991

DRILLING METHOD: 2 1/4" ID HSA

CRA SUPERVISOR: A. KISIEL

| STRATIGRAPHIC DESCRIPTION & REMARKS | ELEVATION | MONITOR | | SAM | PLE | _ |
|---|--|---|---|--|--|--|
| | | INSTALLATION | (M | Ş | N A | 1 |
| GROUND SURFACE | <i>620.2</i> | | E R | E | Ŭ E | ļ |
| ML+SILT(FILL), trace clay, trace sand and fine gravel, soft, red brown, maist | | | 155 | M | 2 | : |
| CL/ML-SILT and CLAY, trace fine gravel, firm, red brown, moist | 618.2 | | 255 | X | 5 | |
| | 615.7 | ति हैं स्टिंग | | \bigvee | | |
| medium dense, black brown, moist Some, except becomes coarse to fine, trace | | BOREHOLE | | $\langle \rangle$ | | |
| loose, dry Some, with trace sulphur, medium dense, brown, moist | | CEMENT/ | | Å | | |
| Same, except fine, trace medium to coarse subrounded grove! black moist | 500.5 | CROUT | 5\$\$ | Å | 13 | |
| SW-SAND, fine, trace medium to coarse subrounded grovel, black, moist | 009.3 | | 6SS | X | 5 | |
| Some, except medicin dense, act | | | 755 | X | 15 | ľ |
| GM-GRAVEL, some silt and fine sand, red brown, moist | 605.3 | | | 17 XI | 17 >100 | |
| NOTES: 1. At completion borehole was grauted to ground surface. | B03.9 | | | | | |
| from 7SS and 8SS. | | | | | | |
| · | | | | | | |
| • . | | · | | | | |
| | | | | | | |
| • | | | | | | |
| | | | | | | |
| | | | | | | |
| | JRE 10 | | | | . | |
| | GROUND SURFACE ML+SHT(FILL), trace clay, trace sand and fine gravel, soft, red brown, maist CL/ML-SILT and CLAY, trace fine gravel, firm, red brown, moist Wood (4.0 ft. BGS) SW/GW-SAND and GRAVEL, fine, trace brick, medium dense, black brown, moist Some, except becomes coarse to fine, trace wood, fiber, cloth, flyash, slag, cinder, loose, dry Some, with trace sulphur, medium dense, brown, moist Same, except fine, trace medium to coarse subrounded gravel, black, moist SW-SAND, fine, trace medium to coarse subrounded gravel, black, moist SW-SAND, fine, trace medium to coarse subrounded gravel, black, moist Some, except medium dense, wet GM-GRAVEL, some silt and fine sand, red brown, moist END OF HOLE © 16.3 FT. BGS NOTES: 1. At completion borehole was grauted to ground surface. 2. Samples for chemical analysis callected | GROUND SURFACE GROUND SURFACE ML-SILT(FILL), trace clay, trace sand and fine gravel, soft, red brown, maist CL/ML-SILT and CLAY, trace fine gravel, firm, red brown, moist Wood (4.0 ft. BGS) SW/GW-SAND and GRAVEL, fine, trace brick, medium dense, black brown, maist Same, except becomes coarse to fine, trace wood, fiber, cloth, flyash, stag, cinder, loose, dry Same, with trace sulphur, medium dense, brown, maist Same, except fine, trace medium to coarse subrounded gravel, black, maist SW-SAND, fine, trace medium to coarse subrounded gravel, black, maist Same, except medium dense, wet GM-GRAVEL, some silt and fine sand, red brown, maist END OF HOLE © 16.3 FT. BGS NOTES: 1. At completion borehole was grauted to ground surface. 2. Samples for chemical analysis callected | GROUND SURFACE ML-SILT (FILL), trace clay, trace sand and fine grovel, soft, red brown, maist CL/ML-SILT and CLAY, trace fine gravel, firm, red brown, moist Wood (4.0 ft. BGS) SW/GW-SAND and GRAVEL, fine, trace brick, medium dense, black brown, maist Same, except becomes coarse to fine, trace wood, fiber, cloth, flyash, slag, cinder, loose, dry Same, with trace sulphur, medium dense, brown, moist Same, except fine, trace medium to coarse subrounded gravel, black, moist SW-SAND, fine, trace medium to coarse subrounded gravel, black, moist Some, except medium dense, wet GM-GRAVEL, some silt and fine sand, red brown, moist END OF HOLE 16.3 FT. BGS NOTES: 1. At completion borehole was grauted to ground surface. 2. Somples for chemical analysis callected | GROUND SURFACE ML-SILT(FILL), trace clay, trace sand and fine grovel, soft, red brown, maist CL/ML-SILT and CLAY, trace fine gravel, firm, red brown, moist Wood (4.0 ft. BGS) SW/GW-SAND and GRAVEL, fine, trace brick, medium dense, black brown, moist Same, except becomes coarse to fine, trace wood, fiber, cloth, flyash, slag, cinder, loose, dry Same, with trace sulphur, medium dense, brown, moist Seme, except fine, trace medium to coarse subrounded gravel, black, moist SW-SAND, fine, trace medium to coarse subrounded gravel, black, moist SW-SAND, fine, trace medium to coarse subrounded gravel, black, moist Some, except medium dense, wet GW-GRAVEL, some silt and fine sand, red brown, moist END OF HOLE 6 16.3 FT. BGS NOTES: At completion borehole was grauted to ground surface. 2. Samples for chemical analysis callected | GROUND SURFACE ML-SILT(FILL), trace clay, trace sand and fine grovel, soft, red brown, maist CL/ML-SILT and CLAY, trace fine gravel, firm, red brown, moist Wood (4.0 ft. BGS) SW/GW-SAND and GRAVEL, fine, trace brick, medium dense, black brown, maist Some, except becomes coarse to fine, trace wood, fiber, cloth, flyash, slag, cinder, loose, dry Same, with trace sulphur, medium dense, brown, moist Some, except fine, trace medium to coarse subrounded gravel, black, moist SW-SAND, fine, trace medium to coarse subrounded gravel, black, moist Some, except medium dense, wet GM-GRAVEL, some silt and fine sand, red brown, maist END OF HOLE 16.3 FT. BGS NOTES: 1. At completion borehole was grauted to ground surface. 2. Somples for chemical analysis callected | GROUND SURFACE ML-SILT(FILL), trace clay, trace sand and fine gravel, soft, red brown, maist CL/ML-SILT and CLAY, trace fine gravel, firm, red brown, moist Wood (4.0 ft. BGS) SW/GW-SAND and GRAVEL, fine, trace brick, medium dense, black brown, moist Some, except becomes coarse to fine, trace wood, fiber, cloth, flyosh, stag, cinder, loose, dry Same, with trace sulphur, medium dense, brown, moist Same, except fine, trace medium to coarse subrounded gravel, black, moist Same, except medium dense, wet GM-GRAVEL, some silt and fine sand, red brown, moist END OF HOLE © 16.3 FT. BGS NOTES: 1. At completion borehole was grauted to ground surface. 2. Somples for chemical analysis callected |

WATER FOUND STATIC WATER LEVEL TO

PROJECT NAME: STAUFFER

HOLE DESIGNATION: BH-35

PROJECT NO.: 2365

DATE COMPLETED: MARCH 6, 1991

(L-54)

CLIENT:

ICI AMERICAS

DRILLING METHOD: 2 1/4" ID HSA

LOCATION: SMALL LANDFILL, SOUTHWEST

CRA SUPERVISOR: A. KISIEL

| | STRATIGRAPHIC DESCRIPTION & REMARKS | ELEVATION | MONITOR | | AMP | LE | |
|--------------|--|-----------|-------------------------------|--------------|-------------|-----|-----------|
| BGS | | ft AMSL | INSTALLATION | MOKCZ | 7 | N A | |
| | GROUND SURFACE | 616.7 | | E R | Ē | שכי | PP |
| | ML—SiLT(FiLL), some clay, trace fine gravel, trace roots, firm, red brown, moist | | | 1 S S | X | 5 | 0 |
| 5 | Same, except becoming stiff, no roots | 1 1 | | 255 | \bigvee | 10 | ١, |
| | Same, except becomes firm | 1 | | | \triangle | | |
| 0 | Same, except trace brick, dense | | 4°8 BOREHOLE | 355 | X | 5 | |
| | ML-SILT(NATIVE), laminated, trace fine sand, | 609.7 | | 455 | \bigvee | 16 | |
| 5 | red brown, moist Some, except no sand | | CEMENT/ BENTONITE CROUT | | Θ | | |
| .0 | SW-SAND(TILL), fine, little fine to coorse | 606.7 | | 555 | | 36 | ' |
| | subrounded and subangular gravel, trace silt, dense, red brown, moist | | | 6SS | X | 41 | |
| .5 | Becomes extremely dense | | | 755 | \bigvee | 90 | 0 |
| _ | SM/ML-SAND and SILT, fine, little fine to | 602.7 | | 855 | | 00 | 0 |
| .0 | coarse gravel, extremely dense, red brown, maist END OF HOLE © 15.2 FT. BGS | 601.5 | | | | | |
| .5 | NOTES: 1. Auger refusal at 15.2 ft. BGS. | | | | | | ļ |
| | At completion borehole was grouted to ground surface. Samples for chemical analysis collected. | | · | | | | |
| .0 | from 4SS (6.0 to 7.0 ft. BGS only) and BSS. | | | | | | |
| | | | | | | | |
| :.5 | | | | | | | |
| 5.0 | | | | | | | |
| | | | | | | | |
| ². 5 | | | | | | | |
| | • | | | | | | |
| 0.0 | | | | | | | |
| 2.5 | | | | | | | |
| ل . ع | FIGU | TRE 10 | • | | | | |

CHEMICAL ANALYSIS



(L-\$5)

PROJECT NAME: STAUFFER

HOLE DESIGNATION: BH-36

PROJECT NO .:

2365

DATE COMPLETED: MARCH 6, 1991

CLIENT:

ICI AMERICAS

DRILLING METHOD: 2 1/4" ID HSA

LOCATION:

LARGE LANDFILL, SOUTH

CRA SUPERVISOR: A. KISIEL

| _ | STRATIGRAPHIC DESCRIPTION & REMARKS | ELEVATION | #SL INSTALLATION 1 | | | |
|--------------|--|-----------|-----------------------|--------------|-------------|----------|
| t BGS | | ft AMSL | INSTALLATION | - 0 . | | 5 # |
| | GROUND SURFACE | 6231 | | BELR | Î | . |
| | SM/ML-SAND and SILT, fine, trace fine gravel, loose, red brown, moist | | | 155 | X · | |
| 2.5 | | | | 255 | \bigvee | ; |
| _ | Becomes medium dense | 618.3 | | ,,,, | М. | |
| 5.0 | SW/GW-SAND and GRAVEL, trace stag, clay, wood, glass, cardboard, brick, black brown and yellow, moist | 0.0.5 | BOREHOLE | | () | 2 6 |
| 7.5 | Becomes dense | 615.1 | BENTONITE | 455 | \bigvee 3 | 2 8 |
| | SC-SAND, fine to coarse, some clay, stag, coal, brick, loose, red brown and black, dry to moist | 1 | | 555 | X | 5 0. |
| 10.0 | GM-GRAVEL, some silt and sond, very loose, aray, black, moist, trace to little orange | 613.1 | | 655 | | 3 0. |
| 12.5 | crystaline material and white translucent materia SM/ML-SAND and SILT, little clay, trace fine to medium subrounded gravel, trace slag, loose, black and olive gray, moist to wet No recovery | | | | 1 /\ | - 1 |
| 15.0 | END OF HOLE C 14.5 FT. BGS NOTES: | 608.6 | | 833 | | |
| 17.5 | Auger refusal at 14.5 ft. BGS. At completion borehole was growted to ground surface. Samples for chemical analysis collected from 4SS and 7SS. | | | | | |
| 20.0 | · | | | | | |
| 22.5 | | | | | | |
| 25.0 | | | | | | |
| 27.5 | | | | | | |
| ¥1.5 | | | | | | |
| 3 0.0 | | | | | | |
| 32.5 | | | | | | |
| | FIGU | RE 10 | • | | | |

NOTES:

MEASURING POINT ELEVATIONS MAY CHANGE; REFER TO CURRENT ELEVATION TABLE

CHEMICAL ANALYSIS







(L-96)

PROJECT NAME: STAUFFER

PROJECT NO.: 2365

CLIENT:

ICI AMERICAS

CHEMICAL ANALYSIS

LOCATION: LARGE LANDFILL, SOUTH CENTRAL

HOLE DESIGNATION: BH-37

DATE COMPLETED: MARCH 6, 1991

DRILLING METHOD: 2 1/4" ID HSA

CRA SUPERVISOR: A. KISIEL

| - 2.5 - 5.0 - 7.5 - 10.0 - 12.5 - 15.0 | STRATIGRAPHIC DESCRIPTION & REMARKS | ELEVATION | MONITOR | | | | MPLE | | | |
|---|---|-----------------|---------------------------------------|----------|-----------|-------------|------|--|--|--|
| BGS | GROUND SURFACE | ft AMSL 620.4 | INSTALLATION | 18 M C X | Ā | N A L | | | | |
| | | 620.4 | | E R | Ε | Ū E | ŀ | | | |
| | ML—SILT(FILL), some clay, trace fine to coarse gravel, roots, soft, red brown, moist to wet | | | 155 | X | 3 | 6 | | | |
| 5 | ML—SIL T, some fine sand, trace slag, toase, red br o wn, moist | | | 255 | X | 8 | | | | |
| | Some, except trace fine sand and gravel | 1 | | | (| | | | | |
|) | Becomes medium dense | , | BOREHOLE | 355 | Å | 7 | l | | | |
| 5 | | | | 455 | X | 17 | ۱, | | | |
| | ML—SILT, trace clay, trace slag and wood, very stiff, red brown, gray, moist | | CEMENT/ BENTONITE GROUT | 555 | \bigvee | 27 | | | | |
| .0 | CL/ML-CLAY and SILT(NATIVE), laminated, red | 610.7 | | | \Box | _ | | | | |
| | brówn, gray, dry to mòist Becom es hard | 608.4 | | 655 | X | 38 | ľ | | | |
| .5 | SW-SAND(TILL), fine, some fine to coarse subrounded and subangular gravel, extremely dense, red brown, dry to moist | | | 755 | M | 134 | ŀ | | | |
| ٥. | Becomes very dense | | | 855 | \bigvee | 64 | Į, | | | |
| | | | · · · · · · · · · · · · · · · · · · · | | \square | | ١ | | | |
| .5 | END OF HOLE © 17.1 FT. BGS NOTES: | 603.3 | | | | | | | | |
| | Auger refusal at 17.1 ft. BGS. At completion borehole was growted | <u> </u> | | | | | | | | |
| 0.0 | to ground surface. 3. Samples for chemical analysis collected from 4SS and 8SS. | | | | | | | | | |
| .5 | | | | | | | | | | |
| | | | | | | | | | | |
| 5.0 | | | | | | | | | | |
| 7.5 | | | • | | | | | | | |
| | | | | | | | | | | |
| 0.0 | | | | | | | | | | |
| | | | | | | | | | | |
| 2.5 | | 1 | , | 1 | | | | | | |
| | FIGU | RE 10 | • | | | | | | | |

WATER FOUND X STATIC WATER LEVEL X

(L-52)

PROJECT NAME: STAUFFER

HOLE DESIGNATION: BH-33

PROJECT NO.:

2365

DATE COMPLETED: MARCH 5, 1991

CLIENT:

ICI AMERICAS

DRILLING METHOD: 2 1/4" ID HSA

CRA SUPERVISOR: A. KISIEL

| LOCATION: | SMALL | LANDEUL | SOUTHEAST |
|------------|-------|------------|--------------|
| LUCA HUIT. | | FVIADL IFF | 300 1112 731 |

| | STRATIGRAPHIC DESCRIPTION & REMARKS | ELEVATION | MONITOR | | SAM | PLE | _ |
|-------------------|---|----------------|--------------------|--------------|--------------|------|----|
| BGS | | ft AMSL | INSTALLATION | ↓ 0 . | Ì | N. | |
| | GROUND SURFACE | 621.4 | | 2018 | Ē | (1) | ļ, |
| | ML-SILT(FILL), some fine sand, trace gravet and clay, loose, red brown, moist | | | 155 | X | 5 | |
| 2.5 | ML/CL-SILT and CLAY, some fine gravet, firm, red brown, moist | 619.4 | | 255 | X | 8 | , |
| 5.0 | Some, except stiff | | | 355 | \bigvee | 13 | |
| 5.0 | Same, except very stiff | | BOREHOLE | 333 | \triangle | 1.3 | ľ |
| 7.5 | | 613.4 | CEMENT/ | 455 | X | 26 | |
| | SW-SAND, very loose, block, moist | 873.4 | BENTONITE GROUT | 555 | \bigvee | <1 | |
| 10.0 | GW-GRAVEL, coarse to fine, some coarse to fine sand, very loose, gray, moist | 611.4 | | 655 | \bigvee | 2 | |
| 12.5 | Same, except some wood, some fine to medium gravel, extremely dense, brown, maist | | | 1 | \bigotimes | >100 | |
| 15.0 | Same, except medium to fine rounded to subrounded gravel, little fine sand and sitt, gray, brown, wet | | | 855 | X | >100 | , |
| 10.0 | END OF HOLE 4 15.4 FT. BGS NOTES: | 606.0 | tent. | | | Ì | İ |
| 17.5 | At completion borehole was grouted to ground surface. Samples for chemical onalysis collected from 5SS and 8SS. | | | | | · | |
| 20.0 | · | | | | | | |
| 22.5 | | | | | | | |
| 25.0 | | | | | | | |
| | | | | | | | |
| 27.5 [°] | | | | | | | |
| 3 0.0 | | | | | | | |
| | | | | | | | |
| 32.5 | FIGU | TRE 10 | | | | | |
| | | - - | | | [] | ł | |

NOTES:

MEASURING POINT ELEVATIONS MAY CHANGE; REFER TO CURRENT ELEVATION TABLE

CHEMICAL ANALYSIS



WATER FOUND ____

(L-57)

PROJECT NAME: STAUFFER

HOLE DESIGNATION: BH-38

PROJECT NO .:

2365

DATE COMPLETED: MARCH 7, 1991

CLIENT:

ICI AMERICAS

DRILLING METHOD: 2 1/4" ID HSA

LOCATION:

LARGE LANDFILL, NORTH CENTRAL

CRA SUPERVISOR: A. KISIEL

| STRATIGRAPHIC DESCRIPTION & REMARKS | ELEVATION | MONITOR | | SAM | PLE | τ- |
|---|--|---|---|--|---|--|
| GROUND SURFACE | 624.5 | INSTALL NIGHT | | A T | | İ |
| ML/CL-SILT and CLAY(FILL), trace fine sand, | 1 | | P. | | Ē | 1 |
| | | | 155 | X | 5 | |
| grovel, stiff | | | 255 | \bigvee | 9 | |
| Same, except trace slag | | | | (\cdot) | | ١ |
| · | 6185 | | 355 | X | 8 | ١ |
| SW-SAND, trace fine to coarse gravel, trace silt, loose, red brown, moist | 7 878.3 | BOREHOLE | 455 | X | 7 | İ |
| Same, except black, no silt | 6.5 | | 555 | \bigvee | g. | |
| ML-SILT, little clay, yellow brown, maist Becomes red brown | 1 1 | BENTONITE GROUT | | \triangle | | |
| SW-SAND(TILL), some fine grovel, red brown, dry to moist | 814.0 | | 6\$8 | X | 20 | |
| No recovery | | | 755 | | 20 | |
| SW-SAND, some gravel, some silty clay | 610.5 | | 855 | X | 58 | |
| Some, except trace fine gravel, extremely dense | | | 000 | () | 100 | |
| No recovery | ene i | | 333 | \triangle | 7100 | 1 |
| NOTES: | 300.7 | . — | | | | l |
| At completion borehole was grouted to ground surface. | | | | | | |
| 3. Samples for chemical analysis collected from 255 and 85\$. | | • | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | ı | |
| FIG | URE 10 | | | | | |
| | ML/CL-SILT and CLAY(FILL), trace fine sand, trace roots, firm, red brown, moist Same, except some fine sand, trace fine gravel, stiff Same, except trace slag SW-SAND, trace fine to coarse gravel, trace silt, loose, red brown, moist Same, except black, no silt ML-SILT, little clay, yellow brown, moist Becomes red brown SW-SAND(TILL), same fine gravel, red brown, dry to moist No recovery SW-SAND, some gravel, some silty clay layers, very dense, red brown, dry to moist Same, except trace fine gravel, extremely dense No recovery END OF HOLE & 18 4 FT. BGS NOTES: 1. Auger refusal at 18.4 ft. BGS. 2. At completion barehole was grouted to ground surface. 3. Samples for chemical analysis collected from 2SS and 8SS. | GROUND SURFACE ML/CL-SILT and CLAY(FILL), trace fine sand, trace roots, firm, red brown, moist Same, except some fine sand, trace fine gravel, stiff Same, except trace slag SW-SAND, trace fine to coorse gravel, trace silt, loose, red brown, moist Same, except black, no silt ML-SILT, little clay, yellow brown, maist Becomes red brown SW-SAND(TilL), some fine gravel, red brown, dry to maist No recovery SW-SAND, some gravel, some silty clay loyers, very dense, red brown, dry to moist Same, except trace fine gravel, extremely dense No recovery END OF HOLE 6 18 4 FT. BGS NOTES: 1. Auger refusol at 18.4 ft. BGS. 2. At completion barehale was grouted to ground surface. 3. Samples for chemical analysis collected | GROUND SURFACE ML/CL-SILT and CLAY(FILL), trace fine sand, trace roots, firm, red brown, moist Same, except some fine sand, trace fine gravel, stiff Same, except trace slag SW-SAND, trace fine to coorse gravel, trace sit, loose, red brown, moist Same, except black, no silt ML-SILT, little clay, yellow brown, moist Becomes red brown SW-SAND(TILL), some fine gravel, red brown, dry to moist No, recovery SW-SAND, some gravel, some silty clay layers, very dense, red brown, dry to moist Same, except trace fine gravel, extremely dense No recovery END OF HOLE © 18.4 FT. BGS NOTES: 1. Auger refusol at 18.4 ft, BGS. 2. At completion borehole was grouted to ground surface. 3. Samples for chemical analysis collected from 2SS and 8SS. | GROUND SURFACE ML/CL-SILT and CLAY(Filt), trace fine sand, trace roots, firm, red brown, moist Same, except some fine sand, trace fine gravel, stiff Same, except trace slag SW-SAND, trace fine to coarse gravel, trace sit, loose, red brown, moist ML-SILT, little clay, yellow brown, moist Becomes red brown SW-SAND(TILL), some fine gravel, red brown, dry to moist No, recovery SW-SAND(TILL), some gravel, some sitly clay loyers, very dense, red brown, dry to moist Same, except trace fine gravel, extremely dense. No recovery END OF HOLE 6 18 4 FT. BGS NOTES: 1. Auger refusal at 18.4 ft. BGS. 2. At completion barehole was grauted to gravel sorted. Samples for chemical analysis collected from 2SS and 8SS. | GROUND SURFACE ML/CL-SiLT and CLAY(Filt), trace fine sand, trace roots, firm, red brown, moist Same, except some fine sand, trace fine gravel, stiff Same, except some fine to coorse gravel, trace sit, loose, red brown, moist Same, except black, no silt ML-SiLT, little clay, yellow brown, moist Becomes red brown SW-SAND(TLL), some fine gravel, red brown, dry to moist No, recovery SW-SAND, some gravel, some sitty clay layers, very dense, red brown, dry to moist Same, except trace fine gravel, extremely dense No recovery No recovery No gravel trace fine gravel, extremely dense 1.50 Auger refusol at 18.4 ft. BGS. 2. At completion borehole was grouted to ground surface. 3. Samples for chemical analysis collected from 2SS and 8SS. | GROUND SURFACE ML/CL-SiLT and CLAY(FilL), trace fine sond, trace roots, firm, red brown, moist Same, except some fine sand, trace fine gravel, stiff Same, except trace slag SW-SAND, trace fine to coorse gravel, trace sit, loose, red brown, moist Same, except black, no sitt MI-SiLT, little clay, yellow brown, moist Becomes red brown SW-SAND(FILL), some fine gravel, red brown, dry to moist No, recovery SW-SAND, some gravel, some sity clay loyers, very dense, red brown, dry to moist Same, except trace fine gravel, extremely dense No recovery No recovery END OF HOLE © 18.4 FT. BGS NOTES: 1. Auger refusal of 18.4 ft. BGS. 2. At completion barehole was grauted to ground surface. 3. Samples for chemical analysis collected from 255 and 855. |

CHEMICAL ANALYSIS



HOLE DESIGNATION: BH-39

PROJECT NO.: 2365

PROJECT NAME: STAUFFER

DATE COMPLETED: MARCH 7, 1991

(L-58)

CLIENT:

ICI AMERICAS

DRILLING METHOD: 2 1/4" ID HSA

LOCATION;

LARGE LANDFILL, NORTHEAST

CRA SUPERVISOR: A. KISIEL

| | STRATIGRAPHIC DESCRIPTION & REMARKS | ELEVATION | MONITOR | | SAN | PLE | T |
|-----|--|---------------|----------------------------|-------------|-------------------|--------|---|
| BCS | GROUND SURFACE | 1t AMSL 623.5 | INSTALLATION | Z 3 M B L Q | 5 | r » cž | |
| | | 025.5 | \$ | Ę. | Ε | E | ļ |
| | ML—SILT(FILL), some clay and fine sand, trace fine gravel, very soft, red brown, moist | | | 188 | X | 2 | |
| 5 | Same, with trace wood, stiff | | | 255 | \bigvee | 14 | |
| | Same, except no wood, very soft | | 7 (9) (1) (2) (3) | | () | , , | |
| 0 | | 617.5 | BOREHOLE | 355 | X | 2 | - |
| 5 | SM-SAND, some coarse to fine gravel, some silt, trace clay, loose, red brown, moist to wet | 817.3 | | 455 | \bigvee | 12 | |
| | ML—SILT, dense, brown, red brown and gray Same, with some clay, maist | 615.5 | CEMENT/ BENTONITE GROUT | 555 | $\langle \rangle$ | 32 | |
| .0 | Becomes hard | | | 6\$\$ | () | 40 | |
| .5 | | 611.4 | ☑ 📉 | | () | | |
| | SM-SAND(TILL), medium to coarse, some fine | 610.2 | | 755 | Δ | 33 | |
| .0 | to coorse subrounded to subangular gravel, red brown, moist to wet Becomes extremely dense | 607.8 | | 855 | X | >100 | |
| .5 | END OF HOLE © 15.7 FT. BGS NOTES: 1. Auger refusal at 15.7 ft. BGS. 2. At completion borehole was grauted | | | | | | |
| 0.0 | to ground surface. 3. Samples for chemical analysis collected from 3SS and 8SS. | | | | | | |
| | | | | | | | |
| 2.5 | | | | | | | l |
| 5.0 | | | | | | | |
| | | | | | | | |
| .5 | | | | | | | |
| | | | | | | | |
| 0.0 | | | | | | | |
| .5 | • | 1 1 | | | | | |
| | FIGU | RE 10 | • | | | | |

GRAIN SIZE ANALYSIS



WATER FOUND X STATIC WATER LEVEL X



APRI 2 1993

ENVIRONNINA PERTURNATION