



PERIODIC REVIEW REPORT 2020

SOLVENT CHEMICAL SITE NIAGARA FALLS, NEW YORK SITE # 9-32-096

Prepared for:

Solvent Chemical Site
3163 Buffalo Avenue
Niagara Falls, New York

Prepared by:

TRC Environmental Corporation
Wannalancit Mills
650 Suffolk Street
Lowell, Massachusetts

TABLE OF CONTENTS

1.0	INTRODUCTION	1-1
1.1	Site Summary	1-1
1.2	Effectiveness of Remedial Program	1-1
1.3	Compliance	1-1
1.4	Recommendations	1-1
2.0	SITE OVERVIEW	2-1
2.1	Nature and Extent of Contamination Prior to Site Remediation	2-1
2.2	Chronology of Remedial Program	2-1
2.3	Site Components	2-1
3.0	EVALUATION OF REMEDY PERFORMANCE, EFFECTIVENESS AND PROTECTIVENESS	3-1
3.1	Performance	3-1
3.2	Effectiveness	3-1
3.3	Protectiveness	3-1
4.0	IC/EC COMPLIANCE	4-1
4.1	Institutional Controls (ICs)	4-1
4.2	Engineering Controls (ECs)	4-1
5.0	MONITORING PLAN COMPLIANCE REPORT	5-1
5.1	Site Cover Performance	5-1
5.1.1	Grassed and Vegetated Areas	5-1
5.1.2	Paved Area and Gravel Roadway	5-2
5.2	Overburden Ground Water Control and Collection System	5-2
5.3	Bedrock Ground Water Control System	5-2
5.4	Summary of Ground Water Quality Monitoring Program	5-2
5.4.1	1st Semi-Annual 2020	5-2
5.4.2	2 nd Semi-Annual 2020	5-2
5.4.3	Sample Results	5-3
5.4.4	Monitoring for NAPL	5-3
5.5	Pre-treatment System Discharge	5-3
6.0	OPERATION, MAINTENANCE & MONITORING (O, M & M) PLAN COMPLIANCE REPORT	6-1
6.1	Components of O, M & M Plan	6-1
6.2	Summary of O&M Completed During Reporting Period	6-2
6.3	Pretreatment System	6-3
6.4	Site Cover	6-3
7.0	OVERALL PRR CONCLUSIONS AND RECOMMENDATIONS	7-1
7.1	Compliance with Site Management Plans	7-1
7.2	Performance and Effectiveness of the Remedy	7-1
7.3	Future PRR and other Submittals	7-1

TABLES

Table 5.1	Components of Performance Monitoring Plan
Table 5.2	Solvent Chemical Site Analytical Results – First Semi-Annual 2020
Table 5.3	Solvent Chemical Site Analytical Results – Second Semi-Annual 2020
Table 6.1	Ground Water Elevations – First Semi-Annual 2020
Table 6.2	Ground Water Elevations – Second Semi-Annual 2020

FIGURES

Figure 1	Site Location Map
Figure 2	Ground Water Extraction System Layout
Figure 3	Overburden Water Levels Solvent Site - March 17, 2020
Figure 4	Overburden Water Levels Solvent Site – September 15 & 16, 2020
Figure 5	March Ground Water Contours – Solvent Site
Figure 6	September Ground Water Contours – Solvent Site
Figure 7	March Ground Water Contours – Hot Spot Site
Figure 8	September Ground Water Contours – Hot Spot Site
Figure 9	August 2004 – September 2020 A Zone Total Contaminants of Concern – Solvent Site
Figure 10	August 2004 – September 2020 B-Zone Total Contaminants of Concern – Solvent Site
Figure 11	August 2004 – September 2020 C, CD and F-Zones Total Contaminants of Concern – Solvent Site
Figure 12	August 2004 – September 2020 A and B-Zones Total Contaminants of Concern – Hot Spot Site

1.0 INTRODUCTION

This Periodic Review Report (PRR) documents activities conducted during the year 2020 at the Solvent Chemical Site (Site), located at 3163 Buffalo Avenue, Niagara Falls, New York (refer to Figure 1).

1.1 Site Summary

Remedial activities for the Site have addressed contamination associated with three areas: 1) the Solvent Chemical Property; 2) the Olin Hot Spot; and 3) the 18-inch Storm Sewer. The operation and maintenance phase of the remediation of the Site commenced on July 1, 2004. The primary Contaminants of Concern (CoCs) are benzene, chlorobenzene, 1,2,4-trichlorobenzene, 1,2-dichlorobenzene, 1,3-dichlorobenzene and 1,4-dichlorobenzene and are present in on-site soils and ground water.

The Solvent Chemical Property is a former chemical manufacturing facility, which included numerous buildings as well as above and underground tanks. All structures associated with the chemical manufacturing facility have been razed. The Olin Hot Spot is situated west of the Solvent Chemical Property and east of Gill Creek. CoCs have been found in overburden (A-zone) and upper bedrock (B-zone) ground water. The former 18-inch diameter concrete storm drain originated from the Solvent Property and extended west across DuPont Drive, an electrical substation and an Olin parking lot and eventually discharged to Gill Creek. As part of the remediation of the Site, this storm drain was addressed by removal/abandonment in place. This portion of the remediation requires no further Operation and Maintenance (O&M) activities.

1.2 Effectiveness of Remedial Program

The Site's cover system continues to provide containment of the contaminated soils onsite and was inspected during 2020. The overburden collection system provides an inward gradient on the Solvent Property as demonstrated over the current review period. The operating flow rates continue to achieve capture of the B-zone consistent with the baseline hydraulic conditions included as Appendix A of the Performance Monitoring Plan (PMP) and approved by the New York State Department of Environmental Conservation (NYSDEC). The Pre-Treatment system effluent data obtained over 2020 shows that permit-required contaminant loading limits continue to be achieved.

1.3 Compliance

There were no occurrences of non-compliance during this review period. NYSDEC was notified during periods of prolonged system downtime.

1.4 Recommendations

The components of the Solvent Chemical Site remediation continue to operate as designed. Given the consistent hydraulic capture of contaminants, Solvent does not propose to modify pumping rates at this time. Routine maintenance requirements will be continually reassessed and modified as necessary.

2.0 SITE OVERVIEW

A Site location map is provided as Figure 1.

2.1 Nature and Extent of Contamination Prior to Site Remediation

Remedial activities for the Solvent Chemical Site have addressed contamination associated with three areas: 1) the Solvent Chemical Property; 2) the Olin Hot Spot; and 3) the 18-inch Storm Sewer.

The Solvent Site is a former chemical manufacturing facility which included numerous buildings as well as above and below ground tanks. All structures associated with the chemical manufacturing facility have since been razed. The facility was constructed in the early 1940s for manufacturing of an aniline/urea-based chemical known as “Impregnite” during World War II and the Korean War. The Solvent Chemical Corporation manufactured chlorinated benzenes and zinc chlorides at the Site during the 1970s. Later in the Site’s history, drummed chemicals and wastes were stored onsite. The ground water remedial system onsite consists of a ground water interception trench in the overburden (A-zone) and recovery wells in the uppermost bedrock (B-zone).

The Hot Spot is situated west of the Solvent Site and east of Gill Creek. Contaminants of concern have been found in overburden (A-zone) and upper bedrock (B-zone) ground water in the vicinity of monitoring wells OBA-15A and OBA-3A. The ground water remedial system consists of a ground water interception trench in the overburden (A-zone) and recovery wells in the uppermost bedrock (B-zone).

The former 18-inch diameter concrete storm drain originated from the Solvent site property and extended west across DuPont Drive, an electrical substation and an Olin parking lot and eventually discharged to Gill Creek. As part of the remediation of the Solvent Site, this storm drain was addressed by removal/abandonment in place. This portion of the remediation requires no further O&M activities.

2.2 Chronology of Remedial Program

The Remedial Action selected by the NYSDEC, and subsequently implemented at the Solvent Site and Hot Spot is presented in the ROD, dated December 1996. Construction of the remedy was substantially completed in 2001 and documented in the Final Engineering Report submitted to the NYSDEC in April 2003. The monitoring of the remedy conforms to the requirements set forth in the approved PMP submitted to NYSDEC in June 2004 and the approved O&M Plan submitted to NYSDEC in April 2003. The requirements outlined in the PMP fulfill Solvent Chemical’s obligations as defined by the “Consent Decree between the State of New York and Solvent Chemical Company, Inc., 83 CIV 1401 (C), (Administrative Consent Order)”, Site Number 9-32-096. The operation and maintenance phase of the remediation of the Solvent Chemical Site commenced on July 1, 2004.

2.3 Site Components

The Site remediation components being addressed under the Site Management phase of the Remedial Program include: (1) a series of ground water extraction wells which provide hydraulic control of overburden and shallow bedrock ground water; (2) a pre-treatment system which

removes most of the contaminant loading prior to discharge of extracted ground water to the Niagara Falls POTW; and (3) a site cover which prevents direct exposure to contaminated soils which remain in place.

Ground water is extracted from five overburden (A-zone) and seven shallow bedrock (B-zone) recovery wells. A site plan identifying well locations is provided as Figure 2. All recovery wells are located on the Solvent Chemical Property except for two wells (PW-3B and PW-4B), which extract groundwater from both the A-zone and B-zone and are located on the "Olin Hot Spot" portion of the Site. Ground water extracted from the recovery wells is pumped to an on-site building for pre-treatment. Pre-treatment operations include oil/water separation (PW-5B through PW-8B) and air stripping. Prior to October 2005, water from the A-zone wells was also routed through the oil/water separator. This was discontinued upon approval from NYSDEC in a letter dated October 18, 2005. Pre-treated effluent is discharged to the Niagara Falls municipal sewer system. Solvent laden air from the air stripper is treated by carbon adsorption. Once treated by adsorption, the air is recycled to the air stripper in a closed loop. Consequently, there is no atmospheric discharge. Carbon beds are regenerated by steam at selected time intervals (currently twice per week). During the steam regeneration process, steam combined with vapor phase solvent is purged from the carbon beds, condensed into liquid and separated into water and waste solvent. Waste solvent accumulates in a tank on-site and is periodically removed for disposal as a hazardous waste. The water is recirculated back to the air stripper.

3.0 EVALUATION OF REMEDY PERFORMANCE, EFFECTIVENESS AND PROTECTIVENESS

3.1 Performance

Figures 3 and 4 present overburden water levels for the Solvent Chemical Property and document that the piezometric elevations of all the observation wells in the central portions of the Site are higher than the piezometric elevations encountered in the trench observation wells, indicating an overburden flow path towards the ground water extraction trench. Figures 5 through 8 present ground water contours for B-zone wells on the Solvent Chemical Site and Olin Hot Spot properties. The contours show that ground water extraction system pumping rates are achieving hydraulic capture. Figures 9 through 12 present graphical depictions of CoC concentrations versus time for the wells currently sampled. Additional discussions regarding these figures, where appropriate, are provided in the applicable sections of this report.

3.2 Effectiveness

Based on the figures presented, the extraction system is effectively maintaining hydraulic control in accordance with Appendix A of the PMP.

The Site's cover system is intact, based on inspections, effectively preventing direct exposure.

3.3 Protectiveness

The extraction system is preventing further migration. The Site's cover system continues to provide containment and protection from exposure.

4.0 IC/EC COMPLIANCE

4.1 Institutional Controls (ICs)

The Site has land use restrictions in place. A certification acknowledging that the controls are current is provided in the Institutional and Engineering Controls Certification Form.

4.2 Engineering Controls (ECs)

The following Engineering Controls (ECs) are in place and actively maintained: a cover system, access control (perimeter fence) and ground water containment.

Performance of the cover system and perimeter fencing is monitored quarterly through visual inspections. The ground water containment system is actively monitored and maintained as described in Section 6 of this report. All engineering controls are functioning as designed, are effective and are protective. No changes are recommended at this time.

5.0 MONITORING PLAN COMPLIANCE REPORT

The components of the Performance Monitoring Plan are presented in Table 5.1 below.

Table 5.1: Components of Performance Monitoring Plan Solvent Chemical Site Niagara Falls, NY		
Remedy Component	Performance Standard	Required Performance Monitoring Activity
Soil – Clean Soil Cover	Contain contaminated soils.	Inspect clean soil cover and pavement for erosion and/or other damage.
Overburden Ground Water – Control and Collection System	Control contaminated overburden groundwater.	Measure overburden ground water levels within and outside of ground water extraction trench to document inward hydraulic gradient.
Shallow Bedrock Ground Water – Control System	Control contaminated bedrock groundwater at the Solvent Site property and the Hot Spot.	Measure ground water levels within the B-zone with subsequent development of plots of the potentiometric surface to document hydraulic containment of contaminated ground water associated with the Solvent Site.
Ground Water – Quality Monitoring Program	Monitor and document offsite contaminant loadings within bedrock zones of concern.	Collection and analysis of B-zone and deeper ground water samples.
Treatment and Disposal of Extracted Ground Water	Comply with permit requirements.	Conduct effluent monitoring as required in discharge permit.

5.1 Site Cover Performance

Ground cover at the Site varies and includes a grassed area in the northern portion of the Site, a heavily vegetated area in the southern portion of the Site, a paved area along with a gravel access road, and an on-site treatment building.

5.1.1 Grassed and Vegetated Areas

Grass is still well established along the site's northern side, adjacent to Buffalo Avenue to just south of the treatment building. The vegetative growth covering the rest of the site is also still well established and there were no areas where growth was absent. Mowing is performed as described in the approved O&M plan.

On March 21 and September 17 2020 visual inspections of the cover soil for areas of potential significant erosion were conducted. No evidence of areas experiencing significant erosion of the grassy and vegetated areas was noted during these inspections.

5.1.2 Paved Area and Gravel Roadway

Overall the paved area and gravel roadway are still intact without any major cracks or areas of erosion. The gravel roadway is intact although noted as becoming overgrown with vegetation.

5.2 Overburden Ground Water Control and Collection System

Water level measurements were collected both within and outside of the ground water extraction trench. Figures 3 and 4 provide ground water piezometric surface elevations for the overburden observation wells on the Solvent site. As shown on these figures, the piezometric elevations of all the observation wells in the central portions of the Site are higher than the piezometric elevations encountered in the trench observation wells indicating an overburden flow path towards the ground water extraction trench.

5.3 Bedrock Ground Water Control System

Figures 5 through 8 present semi-annual water level contours for both the Solvent Site and Hotspot for 2020. The figures indicate that the B-zone pumping wells are achieving capture consistent with the baseline hydraulic conditions approved by NYSDEC, included as Appendix A of the PMP, with the exception of the occasions listed in Section 6.2 below.

5.4 Summary of Ground Water Quality Monitoring Program

Bi-annual ground water sampling events occurred during March and September of 2020. A brief summary of each event is described in Sections 5.4.1 and 5.4.2 below. A more detailed description of each sampling event can be found in the 1st Semi-Annual and the 2nd Semi-Annual for 2020 Operation, Maintenance and Monitoring (OM&M) reports, respectively. Ground water sampling is conducted using passive diffusion bags (PDBs) as described in revised PMP, dated June 2004, and accepted by NYSDEC in a letter dated July 1, 2004.

5.4.1 1st Semi-Annual 2020

The 1st Semi-Annual sampling event included 39 samples (including three duplicate samples) collected from PDBs that had been deployed in thirty-four monitoring/observation wells (nine A-zone wells, twenty B-zone wells, three C-zone, and two CD-zone) during September 2018. Three PDBs were installed in the F-zone wells on March 6, 2020, two weeks prior to sample collection on March 17, 18, 24, and 25, 2020. A sample was not collected at OW-18B or MW-6C; OW-18B was obstructed and no PDB was present in MW-6C.

The PDBs were retrieved on March 17 through 25, 2019 and samples for volatile organic compound analysis were collected and transported under chain of custody documentation to Test America and analyzed by Method 8260B.

5.4.2 2nd Semi-Annual 2020

The 2nd Semi-Annual 2020 sampling event included 38 samples (including three duplicate samples) collected from PDBs that had been deployed in thirty-four monitoring/observation wells (nine A-zone wells, twenty B-zone wells, three C-zone, and two CD-zone) during March 2020. PDBs were installed in three F-zone wells (MW-1F, MW-5F and MW-6F) on August 27, 2020, at least two weeks prior to sample collection on September 15 through 17, 2020. OW-18B was not sampled because of an obstruction in the well riser, OW-22A's water level was below the PDB,

and MW-6C was not sampled because it is bailed regularly for DNAPL. Samples collected for volatile organic compound analysis were transported under chain of custody documentation to Test America and analyzed by Method 8260B.

Ground water sampling is conducted semi-annually as described in the SMP and the next round of ground water quality monitoring is scheduled for March 2021 as part of 1st Semi-Annual 2021 OM&M activities.

5.4.3 Sample Results

Tables 5.2 and 5.3 present the analytical results for the March and September 2020 ground water sampling events, respectively. Figures presenting ground water contaminant results for each monitoring/observation well were presented in the 1st Semi-Annual and the 2nd Semi-Annual for 2020 OM&M reports. Figures 9 through 12 present graphical depictions of total CoC concentrations versus time for the observation/monitoring wells currently sampled at the Solvent and Hot Spot Sites.

5.4.4 Monitoring for NAPL

During the March and September 2020 ground water sampling events, after the PDB was removed and sampled, an oil/water interface probe was used to check for the presence of Non-Aqueous Phase Liquid (NAPL) at each of the wells. The presence or absence of NAPL was also evaluated at the wells that were not sampled.

During the March 2020 ground water sampling event, well OW-11B, OW-13B, MW-6C, OW-11A, MW-2B, and PW-1B had evidence of product. OW-11B had DNAPL on the PDB and was weighted from absorbing product. No product thickness could be determined. No additional groundwater monitoring wells had evidence of NAPL on the tip of the interface probe.

During the September 2019 ground water sampling event, NAPL was detected on the OW-11B PDB, which was weighted from absorbing product. However, no measurable thickness was measured. The probe had some evidence of product at OW-13B, MW-2B, and PW-1B, but there was not enough product to measure. There was 0.1 feet of product measured at OW-11A. There was 0.11 feet of product measured at MW-6C. The probe had some evidence of a tar-like non-NAPL product for wells PZ-01, PZ-02, PZ-03, and PZ-04. No additional groundwater monitoring wells had evidence of NAPL on the tip of the interface probe.

5.5 Pre-treatment System Discharge

The Site's pre-treatment system discharge concentrations during 2020 were below the limits required by the City of Niagara Falls, Significant Industrial User Discharge Permit Number 55.

6.0 OPERATION, MAINTENANCE & MONITORING (O, M & M) PLAN COMPLIANCE REPORT

6.1 Components of O, M & M Plan

O, M & M Reports are submitted to NYSDEC semi-annually. The reports include the results of all-environmental monitoring, findings of all site inspections, and details of the system maintenance activities performed at the Site during each semi-annual period. The maintenance schedule for the Site's pre-treatment system is presented in Table 9 of the OM&M Plan. NYSDEC is notified of any unscheduled maintenance that requires the system to be shut down for a period of more than three consecutive days or when down five or more total days within a 30-day period. The notification includes a plan and schedule for restoring system operations. A system shutdown occurs annually for approximately one to two weeks to deal with standard maintenance. The activities performed during the intermittent shutdown for this performance review occurred over the period of September 28, 2020 through October 9, 2020. NYSDEC was notified prior to system shutdown.

Waste containing site related chemicals are properly stored on site prior to transport to an off-site facility for disposal in accordance with all applicable Federal and State of New York regulations. Disposal waste manifest documentation has been provided in previous reports, as applicable. Transport or disposal of remedial waste was conducted during 2020.

Previous product removal and disposal was conducted as follows:

- On August 4, 2020, approximately 325 gallons of product was removed from the onsite above ground storage tank (AST) and transported to Chemtron Corporation of Avon, Ohio.
- On June 27, 2018, approximately 240 gallons of product was removed from the onsite AST and transported to Chemtron Corporation of Avon, Ohio.
- March 9, 2016, six super sacks containing spent carbon from the regenerable carbon unit were transported by Nortru LLC to the Petro-Chem Processing Group facility in Detroit, Michigan
- November 9, 2016, approximately 350 gallons of product was removed from the onsite AST and transported to Chemtron Corporation of Avon, Ohio.
- On January 9, 2015, approximately 272 gallons of product was removed from the onsite AST and transported to Chemtron Corporation of Avon, Ohio. Disposal documentation is provided in Appendix C of the 1st Quarter 2015 OM&M Report.
- On July 9, 2013, approximately 300 gallons of product was removed from the onsite AST for transport and disposal at an approved facility. Disposal documentation was provided in Appendix C of the 3rd Quarter 2013 OM&M Report.
- On September 4, 2012, 107 gallons of product was removed from the onsite AST for transport to an approved disposal facility. Documentation of the transport and disposal was included in Appendix C of the 3rd Quarter, 2012 OM&M Report.

- On August 2, 2011 approximately 150 gallons of product was transported by the Environmental Service Group, Inc. to Chemtron Corporation in Avon, Ohio. Documentation of this transport and disposal was included in Appendix C of the 3rd Quarter 2011 OM&M Report.
- During the 1st Quarter 2010, 488 gallons of recovered product was removed from the onsite AST for transport to an approved disposal facility on January 13, 2010. Documentation of the transport and disposal was included in Appendix C of the 1st Quarter, 2010 OM&M Report.
- On December 17, 2009, eleven drums of contaminated debris (pump parts, PPE) were transported to the Michigan Disposal Waste Treatment Plant in Belleville, MI. Documentation of the transport and disposal was included in Appendix C of the 4th Quarter 2009 OM&M Report.
- On September 26, 2007, eleven drums of carbon from the regenerable carbon unit were transported to Wayne Disposal, Inc. Site 2 Landfill located in Belleville, MI.
- On January 20, 2006 approximately 500 gallons of liquid waste were removed from the onsite AST and transported to Chemtron Corporation. Documentation of this transport and disposal activity was included in the 1st Quarter 2006 OM&M Report dated July 10, 2006.
- In July 2004, 90 gallons of product were transported by Frank's Vacuum Truck Service of Niagara Falls, New York to Chemtron Corporation of Avon, Ohio. Documentation of this transport and disposal activity was included in the 3rd Quarter 2004 OM&M Report dated November 17, 2004.

6.2 Summary of O&M Completed During Reporting Period

Routine operation and maintenance activities include regular site visits by Camtech Plumbing and Mechanical of Niagara Falls, New York (Camtech). Non-scheduled equipment repairs are made as soon as practicable as they occur. Major scheduled maintenance activities require a system shutdown and is scheduled annually. Non-scheduled maintenance (repairs) performed during 2019 are summarized as follows:

Date	Maintenance Action Taken
1/1/2020	Cleaned steam pump
1/3/2020	Pulled and cleaned pump for PW-4B
3/6/2020	Cleaned pump for PW-6B.
3/27/2020	Pulled and cleaned pump for PW-8B.
3/31/20	Repaired fridge and cleaned well PW-8B pump.
4/2/20	Cleaned flow meters.
4/7/20	Cleaned pump in well PW-2B.
5/27/20	Cleaned pump in well PW-6B.
5/28/20	Cleaned pump in well PW-2B.
5/29/20	Cleaned pump in well PW-5B.
7/10/20	Electrical work on pump in well PW-6B.
7/15/20	Boiler repair.

Date	Maintenance Action Taken
8/3/20	Cleaned level switch for well PW-5B.
8/4/20	Cleaned condenser motor.
8/7/20	Tested chiller and steam cycle.
8/18/20	Fixed panel and monitor. Level switches cleaned.
9/10/20	Cleaned pump in well PW-7B.
10/1/20	Replaced needles valves for steam pump.
10/2/20	Cleaned screens in PW-2B.
10/9/20	Repair of heater.
11/17/20	Cleaned pump in well PW-4B.
11/18/20	Cleaned pump in well PW-3A and installed new level switch.
11/27/20	Level switches cleaned, reset 301, and primed 401.
12/21/20	Cleaned and repaired pump in well PW-4A.
12/24/20	Cleaned level switches on air stripper.
12/28/20	Replaced and cleaned pump in well PW-5B.
12/29/20	Maintained pumps in wells PW-3A and PW-4A.

6.3 Pretreatment System

During 2020, the system treated approximately 15.9 million gallons of ground water. Tables of daily ground water pumping volumes and average flow rates for January through December 2020 are provided in the semi-annual reports. Solvent Chemical's Self-Monitoring Reports, which are submitted to the Niagara Falls' POTW on a semi-annual basis. The system is performing as designed and no violations were noted.

Ground water levels were measured on March 17 and September 15 to 17, 2020. Ground water depths and the corresponding ground water elevations (referenced to Benchmark J20, Niagara Falls City Datum) for the 1st Semi-Annual and the 2nd Semi-Annual Reports for 2020 are provided in Tables 6.1 and 6.2 respectively. As hydraulic control in accordance with the SMP is shown, the ground water extraction system is performing as designed.

6.4 Site Cover

The ground cover at the Site is inspected, areas of significant erosion, if any, are reported and repaired immediately. To date, the vegetation on-site is well established and erosion is minimal. Vegetated areas are mowed to prevent the establishment of any deep rooting plants. Paved areas are also inspected and any cracks or holes are patched as needed.

7.0 OVERALL PRR CONCLUSIONS AND RECOMMENDATIONS

7.1 Compliance with Site Management Plans

The requirements outlined in the SMP were met over this performance review period.

7.2 Performance and Effectiveness of the Remedy

The components of the Solvent Chemical Site remediation continue to operate as designed. Based on the consistent hydraulic capture of contaminants, this EC continues to perform properly and remains effective. Therefore, Solvent does not propose to modify recovery well pumping rates at this time. Pre-treatment system effluent data shows that permit-required contaminant loading limits continue to be achieved. The cover system and site access control remains intact with minor maintenance and continue to prevent exposure to contaminated soil. These ECs also are continuing to perform properly and remain effective.

ICs remain in effect for the Solvent Chemical property.

Based on a review of the information generated from the operation, maintenance and monitoring performed for the Solvent Chemical Site, the remedy continues to be protective of public health and the environment and is compliant with the applicable decision document.

7.3 Future PRR and other Submittals

PRRs for this Site will be submitted annually.

TABLES

TABLE 5.2 - GROUND WATER ANALYTICAL RESULTS
FIRST SEMI-ANNUAL 2020
SOLVENT CHEMICAL, 3163 BUFFALO AVENUE, NIAGARA FALLS, NY

Location	Date Sampled	Contaminants of Concern						Remaining Detected Analytes											
		Benzene	Chlorobenzene	1,2,4-Trichlorobenzene	1,2-Dichlorobenzene	1,3-Dichlorobenzene	1,4-Dichlorobenzene	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane	1,2,4-Trimethylbenzene	1,2-Dibromo-3-chloropropane	1,2-Dibromoethane
	Effluent Limit*	1	5	5	3	3	3	N/A	5	5	1	5	5	N/A	5	0.04	5	0.04	0.0006
A Zone																			
MW-02A	03/25/2020	140 J	5,400	160 J	1,700	380	1,900	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U
MW-05A	03/17/2020	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U
OW-09A	03/17/2020	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U
OW-12A	03/24/2020	84 J	2,200	440	6,500	1,700	5,400	< 130 U	< 130 U	< 130 U	< 130 U	< 130 U	< 130 U	< 130 U	< 130 U	< 130 U	< 130 U	< 130 U	< 130 U
OW-15A	03/18/2020	< 10 U	70	190	470	100	250	< 10 U	< 10 U	< 10 U	< 10 U	< 10 U	< 10 U	< 10 U	< 10 U	< 10 U	< 10 U	< 10 U	< 10 U
OW-16A	03/17/2020	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U
OW-18A	03/18/2020	270	5,800	130 J	5,500	1,200	9,300 F1	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U
OW-22A	03/24/2020	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U
OW-29A	03/25/2020	< 200 U	5,500	1,300	11,000	2,500	6,600	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	410	< 200 U	< 200 U	< 200 U	< 200 U
B Zone																			
MW-01B	03/24/2020	< 100 U	6,000	< 100 U	340	400	2,000	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U
MW-04B	03/18/2020	< 200 U	190 J	250	720	320	580	< 200 U	< 200 U	510	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U
MW-06B	03/25/2020	330	2,600	160	3,500	990	2,500	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U
OW-05B	03/18/2020	< 200 U	190 J	91 J	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	290	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U
DUP OW-05B	03/18/2020	52 J	170	89 J	100	100	130	< 100 U	< 100 U	280	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U
OW-06B	03/18/2020	73	510	770	490	280	550	< 50 U	< 50 U	70	< 50 U	< 50 U	< 50 U	< 50 U	30 J	< 50 U	< 50 U	< 50 U	< 50 U
OW-07B	03/18/2020	< 1.0 U	6.0	< 1.0 U	< 1.0 U	1.6	1.3	< 1.0 U	< 1.0 U	13	0.57 J	1.6	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U
OW-08B	03/18/2020	< 2.0 U	< 2.0 U	< 2.0 U	< 2.0 U	< 2.0 U	< 2.0 U	< 2.0 U	< 2.0 U	< 2.0 U	1.3 J	1.3 J	< 2.0 U	< 2.0 U	< 2.0 U	< 2.0 U	< 2.0 U	< 2.0 U	< 2.0 U
OW-10B	03/25/2020	370 J	7,500	1,200	10,000	2,100	7,900	< 500 U	< 500 U	< 500 U	< 500 U	< 500 U	< 500 U	< 500 U	< 500 U	< 500 U	< 500 U	< 500 U	< 500 U
OW-11B	03/25/2020	7,100	12,000	2,700	25,000	6,200	20,000	< 400 U	< 400 U	< 400 U	< 400 U	< 400 U	< 400 U	< 400 U	1,000	< 400 U	< 400 U	< 400 U	< 400 U
DUP OW-11B	03/25/2020	6,900	12,000	2,900	25,000	6,200	20,000	< 500 U	< 500 U	< 500 U	< 500 U	< 500 U	< 500 U	< 500 U	1,100	< 500 U	< 500 U	< 500 U	< 500 U
OW-12B	03/18/2020	40	1,100	3.0	310	320.0	670	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	2.0	< 1.0 U	< 1.0 U	0.47 J	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U
OW-13B	03/17/2020	1,300	8,100	5,900	6,400	1,500	5,200	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	400	< 200 U	< 200 U	< 200 U	< 200 U
DUP OW-13B	03/18/2020	1,400	8,100	5,600	6,600	1,600	5,500	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	370	< 200 U	< 200 U	< 200 U	< 200 U
OW-14B	03/24/2020	< 100 U	1,700	720	4,000	1,800	6,100	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	180	< 100 U	< 100 U	< 100 U	< 100 U
OW-15B	03/24/2020	10 J	67	< 25 U	< 25 U	29	35	< 25 U	< 25 U	34	< 25 U	< 25 U	< 25 U	< 25 U	< 25 U	< 25 U	< 25 U	< 25 U	< 25 U
OW-18B	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS
OW-22B	03/24/2020	< 20 U	< 20 U	< 20 U	< 20 U	< 20 U	< 20 U	< 20 U	< 20 U	180	< 20 U	< 20 U	< 20 U	< 20 U	< 20 U	< 20 U	< 20 U	< 20 U	< 20 U
OW-26B	03/17/2020	< 2.0 U	< 2.0 U	< 2.0 U	< 2.0 U	< 2.0 U	< 2.0 U	< 2.0 U	< 2.0 U	< 2.0 U	< 2.0 U	1.2 J	< 2.0 U	< 2.0 U	< 2.0 U	< 2.0 U	< 2.0 U	< 2.0 U	< 2.0 U
OW-27B	03/17/2020	290	2,000	160	1,000	430	1,300	< 50 U	< 50 U	< 50 U	< 50 U	< 50 U	< 50 U	< 50 U	27 J	< 50 U	< 50 U	< 50 U	< 50 U
OW-28B	03/18/2020	< 50 U	54	68	49 J	39 J	62	< 50 U	< 50 U	240	< 50 U	< 50 U	< 50 U	< 50 U	< 50 U	< 50 U	< 50 U	< 50 U	< 50 U
OW-29B	03/18/2020	830	4,600	2,000	3,500	1,000	3,000	< 200 U	< 200 U	250	< 200 U	< 200 U	< 200 U	< 200 U	190 J	< 200 U	< 200 U	< 200 U	< 200 U
OW-30B	03/17/2020	0.80 J	2.4	< 1.0 U	2.2	2.8	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	4.1	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U

TABLE 5.2 - GROUND WATER ANALYTICAL RESULTS
FIRST SEMI-ANNUAL 2020
SOLVENT CHEMICAL, 3163 BUFFALO AVENUE, NIAGARA FALLS, NY

Location	Date Sampled	Contaminants of Concern						Remaining Detected Analytes											
		Benzene	Chlorobenzene	1,2,4-Trichlorobenzene	1,2-Dichlorobenzene	1,3-Dichlorobenzene	1,4-Dichlorobenzene	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane	1,2,4-Trimethylbenzene	1,2-Dibromo-3-chloropropane	1,2-Dibromoethane
C Zone																			
MW-01C	03/25/2020	< 50 U	< 50 U	< 50 U	< 50 U	< 50 U	< 50 U	< 50 U	< 50 U	< 50 U	< 50 U	< 50 U	< 50 U	< 50 U	< 50 U	< 50 U	< 50 U	< 50 U	< 50 U
MW-04C	03/18/2020	3,000	3,900	500	1,600	< 400 U	1,100	< 400 U	< 400 U	290 J	< 400 U	< 400 U	< 400 U	< 400 U	< 400 U	< 400 U	< 400 U	< 400 U	< 400 U
MW-05C	03/17/2020	35	1,200	< 20 U	480	650	1,200	< 20 U	< 20 U	< 20 U	< 20 U	< 20 U	< 20 U	< 20 U	< 20 U	< 20 U	< 20 U	< 20 U	< 20 U
MW-06C	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS
CD Zone																			
MW-01CD	03/25/2020	5,500	50,000	< 800 U	14,000	1,900	9,800	< 800 U	< 800 U	< 800 U	< 800 U	< 800 U	< 800 U	< 800 U	< 800 U	< 800 U	< 800 U	< 800 U	< 800 U
MW-05CD	03/17/2020	38	< 10 U	< 10 U	< 10 U	< 10 U	< 10 U	< 10 U	< 10 U	< 10 U	< 10 U	< 10 U	< 10 U	< 10 U	< 10 U	< 10 U	< 10 U	< 10 U	< 10 U
F Zone																			
MW-01F	03/24/2020	< 50 U	< 50 U	< 50 U	< 50 U	< 50 U	< 50 U	< 50 U	< 50 U	< 50 U	< 50 U	< 50 U	< 50 U	< 50 U	< 50 U	< 50 U	< 50 U	< 50 U	< 50 U
MW-05F	03/24/2020	160	1,000	44 J	1,700	160	710	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U
MW-06F	03/24/2020	< 20 U	< 20 U	< 20 U	< 20 U	< 20 U	< 20 U	< 20 U	< 20 U	< 20 U	< 20 U	< 20 U	< 20 U	< 20 U	< 20 U	< 20 U	< 20 U	< 20 U	< 20 U

Note:

All units in ug/l.

QUALIFIERS

GC/MS VOA

J: Estimated value.

J-: Estimated value; bias low.

N/A : Not available.

NS: Not Sampled

F1: MS and/or MSD Recovery is outside acceptance limits.

R: Rejected data point.

UJ: Estimated non-detect.

U: Non-detect.

* - NYSDEC Groundwater effluent limitations for discharges to Class GA waters, 2019.

N/A - No criteria available.

Values in **bold** indicate the analyte was detected.

Values shown in bold and shaded type exceed the listed criteria.

TABLE 5.2 - GROUND WATER ANALYTICAL RESULTS
FIRST SEMI-ANNUAL 2020
SOLVENT CHEMICAL, 3163 BUFFALO AVENUE, NIAGARA FALLS, NY

Location	Date Sampled	Remaining Detected Analytes (Continued)																		
		1,2-Dichloroethane	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichloropropane	2,2-Dichloropropane	2-Butanone (MEK)	2-Chloroethyl vinyl ether	2-Hexanone	4-Methyl-2-pentanone	Acetone	Bromobenzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon tetrachloride	Chloroethane	Chloroform
	Effluent Limit*	0.6	1	5	N/A	N/A	50	N/A	50	N/A	50	5	5	50	50	5	120	5	5	7
A Zone																				
MW-02A	03/25/2020	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 2,000 U	< 1,000 U	< 1,000 U	< 1,000 U	< 2,000 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U
MW-05A	03/17/2020	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 10 U	< 5.0 U	< 5.0 U	< 5.0 U	< 10 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U
OW-09A	03/17/2020	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 1,000 U	< 500 U	< 500 U	< 500 U	< 1,000 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U
OW-12A	03/24/2020	< 130 U	< 130 U	< 130 U	< 130 U	< 130 U	< 1,300 U	< 630 U	< 630 U	< 630 U	< 1,300 U	< 130 U	< 130 U	< 130 U	< 130 U	< 130 U	< 130 U	< 130 U	< 130 U	< 130 U
OW-15A	03/18/2020	< 10 U	< 10 U	< 10 U	< 10 U	< 10 U	< 100 U	< 50 U	< 50 U	< 50 U	< 100 U	< 10 U	< 10 U	< 10 U	< 10 U	< 10 U	< 10 U	< 10 U	< 10 U	< 10 U
OW-16A	03/17/2020	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 10 U	< 5.0 U	< 5.0 U	< 5.0 U	< 10 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U
OW-18A	03/18/2020	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 2,000 U	< 1,000 U	< 1,000 U	< 1,000 U	< 2,000 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U
OW-22A	03/24/2020	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 10 U	< 5.0 U	< 5.0 U	< 5.0 U	< 10 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U
OW-29A	03/25/2020	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 2,000 U	< 1,000 U	< 1,000 U	< 1,000 U	< 2,000 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U
B Zone																				
MW-01B	03/24/2020	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 1,000 U	< 500 U	< 500 U	< 500 U	< 1,000 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U
MW-04B	03/18/2020	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 2,000 U	< 1,000 U	< 1,000 U	< 1,000 U	< 2,000 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	280
MW-06B	03/25/2020	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 1,000 U	< 500 U	< 500 U	< 500 U	< 1,000 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U
OW-05B	03/18/2020	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 2,000 U	< 1,000 U	< 1,000 U	< 1,000 U	< 2,000 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U
DUP OW-05B	03/18/2020	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 1,000 U	< 500 U	< 500 U	< 500 U	< 1,000 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U
OW-06B	03/18/2020	< 50 U	< 50 U	< 50 U	< 50 U	< 50 U	< 500 U	< 250 U	< 250 U	< 250 U	< 500 U	< 50 U	< 50 U	< 50 U	< 50 U	< 50 U	< 50 U	< 50 U	< 50 U	< 50 U
OW-07B	03/18/2020	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 10 U	< 5.0 U	< 5.0 U	< 5.0 U	< 10 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	1.8
OW-08B	03/18/2020	< 2.0 U	< 2.0 U	< 2.0 U	< 2.0 U	< 2.0 U	< 20 U	< 10 U	< 10 U	< 10 U	26	< 2.0 U	< 2.0 U	< 2.0 U	< 2.0 U	< 2.0 U	< 2.0 U	< 2.0 U	< 2.0 U	< 2.0 U
OW-10B	03/25/2020	< 500 U	< 500 U	< 500 U	< 500 U	< 500 U	< 5,000 U	< 2,500 U	< 2,500 U	< 2,500 U	< 5,000 U	< 500 U	< 500 U	< 500 U	< 500 U	< 500 U	< 500 U	< 500 U	< 500 U	< 500 U
OW-11B	03/25/2020	< 400 U	< 400 U	< 400 U	< 400 U	< 400 U	< 4,000 U	< 2,000 U	< 2,000 U	< 2,000 U	< 4,000 U	< 400 U	< 400 U	< 400 U	< 400 U	< 400 U	< 400 U	< 400 U	< 400 U	< 400 U
DUP OW-11B	03/25/2020	< 500 U	< 500 U	< 500 U	< 500 U	< 500 U	< 5,000 U	< 2,500 U	< 2,500 U	< 2,500 U	< 5,000 U	< 500 U	< 500 U	< 500 U	< 500 U	< 500 U	< 500 U	< 500 U	< 500 U	< 500 U
OW-12B	03/18/2020	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 10 U	< 5.0 U	< 5.0 U	< 5.0 U	< 10 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U
OW-13B	03/17/2020	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 2,000 U	< 1,000 U	< 1,000 U	< 1,000 U	< 2,000 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U
DUP OW-13B	03/18/2020	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 2,000 U	< 1,000 U	< 1,000 U	< 1,000 U	< 2,000 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U
OW-14B	03/24/2020	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 1,000 U	< 500 U	< 500 U	< 500 U	< 1,000 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U
OW-15B	03/24/2020	< 25 U	< 25 U	< 25 U	< 25 U	< 25 U	< 250 U	< 130 U	< 130 U	< 130 U	< 250 U	< 25 U	< 25 U	< 25 U	< 25 U	< 25 U	< 25 U	< 25 U	< 25 U	< 25 U
OW-18B	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS
OW-22B	03/24/2020	< 20 U	< 20 U	< 20 U	< 20 U	< 20 U	< 200 U	< 100 U	< 100 U	< 100 U	< 200 U	< 20 U	< 20 U	< 20 U	< 20 U	< 20 U	< 20 U	< 20 U	< 20 U	54
OW-26B	03/17/2020	< 2.0 U	< 2.0 U	< 2.0 U	< 2.0 U	< 2.0 U	< 20 U	< 10 U	< 10 U	< 10 U	< 20 U	< 2.0 U	< 2.0 U	< 2.0 U	< 2.0 U	< 2.0 U	< 2.0 U	< 2.0 U	< 2.0 U	< 2.0 U
OW-27B	03/17/2020	< 50 U	< 50 U	< 50 U	< 50 U	< 50 U	< 500 U	< 250 U	< 250 U	< 250 U	< 500 U	< 50 U	< 50 U	< 50 U	< 50 U	< 50 U	< 50 U	< 50 U	< 50 U	< 50 U
OW-28B	03/18/2020	< 50 U	< 50 U	< 50 U	< 50 U	< 50 U	< 500 U	< 250 U	< 250 U	< 250 U	< 500 U	< 50 U	< 50 U	< 50 U	< 50 U	< 50 U	< 50 U	< 50 U	< 50 U	63
OW-29B	03/18/2020	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 2,000 U	< 1,000 U	< 1,000 U	< 1,000 U	< 2,000 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U
OW-30B	03/17/2020	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 10 U	< 5.0 U	< 5.0 U	< 5.0 U	< 10 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U

TABLE 5.2 - GROUND WATER ANALYTICAL RESULTS
FIRST SEMI-ANNUAL 2020
SOLVENT CHEMICAL, 3163 BUFFALO AVENUE, NIAGARA FALLS, NY

Location	Date Sampled	Remaining Detected Analytes (Continued)																		
		1,2-Dichloroethane	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichloropropane	2,2-Dichloropropane	2-Butanone (MEK)	2-Chloroethyl vinyl ether	2-Hexanone	4-Methyl-2-pentanone	Acetone	Bromobenzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon tetrachloride	Chloroethane	Chloroform
C Zone																				
MW-01C	03/25/2020	< 50 U	< 50 U	< 50 U	< 50 U	< 50 U	< 500 U	< 250 U	< 250 U	< 250 U	< 500 U	< 50 U	< 50 U	< 50 U	< 50 U	< 50 U	< 50 U	< 50 U	< 50 U	< 50 U
MW-04C	03/18/2020	< 400 U	< 400 U	< 400 U	< 400 U	< 400 U	< 4,000 U	< 2,000 U	< 2,000 U	< 2,000 U	< 4,000 U	< 400 U	< 400 U	< 400 U	< 400 U	< 400 U	< 400 U	< 400 U	< 400 U	< 400 U
MW-05C	03/17/2020	< 20 U	< 20 U	< 20 U	< 20 U	< 20 U	< 200 U	< 100 U	< 100 U	< 100 U	< 200 U	< 20 U	< 20 U	< 20 U	< 20 U	< 20 U	< 20 U	< 20 U	< 20 U	< 20 U
MW-06C	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS
CD Zone																				
MW-01CD	03/25/2020	< 800 U	< 800 U	< 800 U	< 800 U	< 800 U	< 8,000 U	< 4,000 U	< 4,000 U	< 4,000 U	< 8,000 U	< 800 U	< 800 U	< 800 U	< 800 U	< 800 U	< 800 U	< 800 U	< 800 U	< 800 U
MW-05CD	03/17/2020	< 10 U	< 10 U	< 10 U	< 10 U	< 10 U	< 100 U	< 50 UJ	< 50 U	< 50 U	< 100 U	< 10 U	< 10 U	< 10 U	< 10 U	< 10 UJ	< 10 U	< 10 U	< 10 UJ	< 10 U
F Zone																				
MW-01F	03/24/2020	< 50 U	< 50 U	< 50 U	< 50 U	< 50 U	< 500 U	< 250 U	< 250 U	< 250 U	< 500 U	< 50 U	< 50 U	< 50 U	< 50 U	< 50 U	< 50 U	< 50 U	< 50 U	< 50 U
MW-05F	03/24/2020	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 1,000 U	< 500 U	< 500 U	< 500 U	< 1,000 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U
MW-06F	03/24/2020	< 20 U	< 20 U	< 20 U	< 20 U	< 20 U	< 200 U	< 100 U	< 100 U	< 100 U	< 200 U	< 20 U	< 20 U	< 20 U	< 20 U	< 20 U	< 20 U	< 20 U	< 20 U	< 20 U

Note:
All units in ug/l.
QUALIFIERS
GC/MS VOA
J: Estimated value.
J-: Estimated value; bias low.
N/A : Not available.
NS: Not Sampled
F1: MS and/or MSD Recovery is outside acceptance limits.
R: Rejected data point.
UJ: Estimated non-detect.
U: Non-detect.
* - NYSDEC Groundwater effluent limitations for discharges to Class GA waters, 2019.
N/A - No criteria available.
Values in **bold** indicate the analyte was detected.
Values shown in bold and shaded type exceed the listed criteria.

TABLE 5.2 - GROUND WATER ANALYTICAL RESULTS
FIRST SEMI-ANNUAL 2020
SOLVENT CHEMICAL, 3163 BUFFALO AVENUE, NIAGARA FALLS, NY

Location	Date Sampled	Remaining Detected Analytes (Continued)																		
		Chloromethane	cis-1,2-Dichloroethene	cis-1,3-Dichloropropene	Dibromochloromethane	Dichlorodifluoromethane	Ethylbenzene	Hexachlorobutadiene	Isopropylbenzene	m,p-Xylene	Methyl tert-butyl ether	Methylene chloride	n-Butylbenzene	n-Propylbenzene	Naphthalene	2-Chlorotoluene	o-Xylene	4-Chlorotoluene	4-Isopropyltoluene	sec-Butylbenzene
	Effluent Limit*	5	5	0.4	50	5	5	0.5	5	5	10	5	5	5	10	5	5	5	5	5
A Zone																				
MW-02A	03/25/2020	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 400 U	< 200 U	< 400 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U
MW-05A	03/17/2020	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 2.0 U	< 1.0 U	< 2.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U
OW-09A	03/17/2020	< 100 U	350	< 100 U	< 100 U	< 100 U	< 100 U	< 200 U	< 100 U	< 200 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U
OW-12A	03/24/2020	< 130 U	< 130 U	< 130 U	< 130 U	< 130 U	< 130 U	< 250 U	< 130 U	< 250 U	< 130 U	< 130 U	< 130 U	< 130 U	< 130 U	< 130 U	< 130 U	< 130 U	< 130 U	< 130 U
OW-15A	03/18/2020	< 10 U	< 10 U	< 10 U	< 10 U	< 10 U	< 10 U	< 20 U	< 10 U	< 20 U	< 10 U	< 10 U	< 10 U	< 10 U	< 10 U	< 10 U	< 10 U	< 10 U	< 10 U	< 10 U
OW-16A	03/17/2020	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 2.0 U	< 1.0 U	< 2.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U
OW-18A	03/18/2020	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 400 U	< 200 U	< 400 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U
OW-22A	03/24/2020	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 2.0 U	< 1.0 U	< 2.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U
OW-29A	03/25/2020	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 400 U	< 200 U	< 400 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U
B Zone																				
MW-01B	03/24/2020	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 200 U	< 100 U	< 200 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U
MW-04B	03/18/2020	< 200 U	1,800	< 200 U	< 200 U	< 200 U	< 200 U	< 400 U	< 200 U	< 400 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U
MW-06B	03/25/2020	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 200 U	< 100 U	< 200 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U
OW-05B	03/18/2020	< 200 U	1,500	< 200 U	< 200 U	< 200 U	< 200 U	< 400 U	< 200 U	< 400 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U
DUP OW-05B	03/18/2020	< 100 U	1,300	< 100 U	< 100 U	< 100 U	< 100 U	< 200 U	< 100 U	< 200 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U
OW-06B	03/18/2020	< 50 U	3,000	< 50 U	< 50 U	< 50 U	< 50 U	< 100 U	< 50 U	< 100 U	< 50 U	< 50 U	< 50 U	< 50 U	< 50 U	< 50 U	< 50 U	< 50 U	< 50 U	< 50 U
OW-07B	03/18/2020	< 1.0 U	84	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 2.0 U	< 1.0 U	< 2.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U
OW-08B	03/18/2020	< 2.0 U	50	< 2.0 U	< 2.0 U	< 2.0 U	< 2.0 U	< 4.0 U	< 2.0 U	< 4.0 U	< 2.0 U	< 2.0 U	< 2.0 U	< 2.0 U	< 2.0 U	< 2.0 U	< 2.0 U	< 2.0 U	< 2.0 U	< 2.0 U
OW-10B	03/25/2020	< 500 U	< 500 U	< 500 U	< 500 U	< 500 U	< 500 U	< 1,000 U	< 500 U	< 1,000 U	< 500 U	< 500 U	< 500 U	< 500 U	< 500 U	< 500 U	< 500 U	< 500 U	< 500 U	< 500 U
OW-11B	03/25/2020	< 400 U	< 400 U	< 400 U	< 400 U	< 400 U	< 400 U	< 800 U	< 400 U	< 800 U	< 400 U	< 400 U	< 400 U	< 400 U	< 400 U	< 400 U	< 400 U	< 400 U	< 400 U	< 400 U
DUP OW-11B	03/25/2020	< 500 U	< 500 U	< 500 U	< 500 U	< 500 U	< 500 U	< 1,000 U	< 500 U	< 1,000 U	< 500 U	< 500 U	< 500 U	< 500 U	< 500 U	< 500 U	< 500 U	< 500 U	< 500 U	< 500 U
OW-12B	03/18/2020	< 1.0 U	53	< 1.0 U	< 1.0 U	< 1.0 U	0.82 J	< 2.0 U	< 1.0 U	< 2.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U
OW-13B	03/17/2020	< 200 U	7,700	< 200 U	< 200 U	< 200 U	< 200 U	< 400 U	< 200 U	< 400 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U
DUP OW-13B	03/18/2020	< 200 U	7,900	< 200 U	< 200 U	< 200 U	< 200 U	< 400 U	< 200 U	< 400 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U
OW-14B	03/24/2020	< 100 U	140	< 100 U	< 100 U	< 100 U	< 100 U	< 200 U	< 100 U	< 200 U	< 100 U	59 J	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U
OW-15B	03/24/2020	< 25 U	510	< 25 U	< 25 U	< 25 U	< 25 U	< 50 U	< 25 U	< 50 U	< 25 U	< 25 U	< 25 U	< 25 U	< 25 U	< 25 U	< 25 U	< 25 U	< 25 U	< 25 U
OW-18B	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS
OW-22B	03/24/2020	< 20 U	660	< 20 U	< 20 U	< 20 U	< 20 U	< 40 U	< 20 U	< 40 U	< 20 U	16 J	< 20 U	< 20 U	< 20 U	< 20 U	< 20 U	< 20 U	< 20 U	< 20 U
OW-26B	03/17/2020	< 2.0 U	6	< 2.0 U	< 2.0 U	< 2.0 U	< 2.0 U	< 4.0 U	< 2.0 U	< 4.0 U	< 2.0 U	< 2.0 U	< 2.0 U	< 2.0 U	< 2.0 U	< 2.0 U	< 2.0 U	< 2.0 U	< 2.0 U	< 2.0 U
OW-27B	03/17/2020	< 50 U	1,300	< 50 U	< 50 U	< 50 U	< 50 U	< 100 U	< 50 U	< 100 U	< 50 U	< 50 U	< 50 U	< 50 U	< 50 U	< 50 U	< 50 U	< 50 U	< 50 U	< 50 U
OW-28B	03/18/2020	< 50 U	1,900	< 50 U	< 50 U	< 50 U	< 50 U	< 100 U	< 50 U	< 100 U	< 50 U	< 50 U	< 50 U	< 50 U	< 50 U	< 50 U	< 50 U	< 50 U	< 50 U	< 50 U
OW-29B	03/18/2020	< 200 U	9,700	< 200 U	< 200 U	< 200 U	< 200 U	< 400 U	< 200 U	< 400 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U
OW-30B	03/17/2020	< 1.0 U	13.0	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 2.0 U	< 1.0 U	< 2.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U

TABLE 5.2 - GROUND WATER ANALYTICAL RESULTS
FIRST SEMI-ANNUAL 2020
SOLVENT CHEMICAL, 3163 BUFFALO AVENUE, NIAGARA FALLS, NY

Location	Date Sampled	Remaining Detected Analytes (Continued)																		
		Chloromethane	cis-1,2-Dichloroethene	cis-1,3-Dichloropropene	Dibromochloromethane	Dichlorodifluoromethane	Ethylbenzene	Hexachlorobutadiene	Isopropylbenzene	m,p-Xylene	Methyl tert-butyl ether	Methylene chloride	n-Butylbenzene	n-Propylbenzene	Naphthalene	2-Chlorotoluene	o-Xylene	4-Chlorotoluene	4-Isopropyltoluene	sec-Butylbenzene
C Zone																				
MW-01C	03/25/2020	< 50 U	2,800	< 50 U	< 50 U	< 50 U	< 50 U	< 100 U	< 50 U	< 100 U	< 50 U	< 50 U	< 50 U	< 50 U	< 50 U	< 50 U	< 50 U	< 50 U	< 50 U	< 50 U
MW-04C	03/18/2020	< 400 U	19,000	< 400 U	< 400 U	< 400 U	< 400 U	< 800 U	< 400 U	< 800 U	< 400 U	< 400 U	< 400 U	< 400 U	< 400 U	< 400 U	< 400 U	< 400 U	< 400 U	< 400 U
MW-05C	03/17/2020	< 20 U	< 20 U	< 20 U	< 20 U	< 20 U	< 20 U	< 40 U	< 20 U	< 40 U	< 20 U	< 20 U	< 20 U	< 20 U	< 20 U	< 20 U	< 20 U	< 20 U	< 20 U	< 20 U
MW-06C	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS
CD Zone																				
MW-01CD	03/25/2020	< 800 U	8,700	< 800 U	< 800 U	< 800 U	< 800 U	< 1,600 U	< 800 U	< 1,600 U	< 800 U	< 800 U	< 800 U	< 800 U	< 800 U	< 800 U	< 800 U	< 800 U	< 800 U	< 800 U
MW-05CD	03/17/2020	< 10 U	550	< 10 U	< 10 U	< 10 U	< 10 U	< 20 U	< 10 U	< 20 U	< 10 U	< 10 U	< 10 U	< 10 U	< 10 U	< 10 U	< 10 U	< 10 U	< 10 U	< 10 U
F Zone																				
MW-01F	03/24/2020	< 50 U	< 50 U	< 50 U	< 50 U	< 50 U	< 50 U	< 100 U	< 50 U	< 100 U	< 50 U	< 50 U	< 50 U	< 50 U	< 50 U	< 50 U	< 50 U	< 50 U	< 50 U	< 50 U
MW-05F	03/24/2020	< 100 U	530	< 100 U	< 100 U	< 100 U	< 100 U	< 200 U	< 100 U	< 200 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U
MW-06F	03/24/2020	< 20 U	1,100	< 20 U	< 20 U	< 20 U	< 20 U	< 40 U	< 20 U	< 40 U	< 20 U	25	< 20 U	< 20 U	< 20 U	< 20 U	< 20 U	< 20 U	< 20 U	< 20 U

Note:
All units in ug/l.
QUALIFIERS
GC/MS VOA
J: Estimated value.
J-: Estimated value; bias low.
N/A : Not available.
NS: Not Sampled
F1: MS and/or MSD Recovery is outside acceptance limits.
R: Rejected data point.
UJ: Estimated non-detect.
U: Non-detect.
* - NYSDEC Groundwater effluent limitations for discharges to Class GA waters, 2019.
N/A - No criteria available.
Values in **bold** indicate the analyte was detected.
Values shown in bold and shaded type exceed the listed criteria.

TABLE 5.2 - GROUND WATER ANALYTICAL RESULTS
FIRST SEMI-ANNUAL 2020
SOLVENT CHEMICAL, 3163 BUFFALO AVENUE, NIAGARA FALLS, NY

Location	Date Sampled	Remaining Detected Analytes (Continued)									
		Styrene	tert-Butylbenzene	Tetrachloroethene	Toluene	trans-1,2-Dichloroethene	trans-1,3-Dichloropropene	Trichloroethene	Trichlorofluoromethane	Vinyl acetate	Vinyl chloride
	Effluent Limit*	5	5	5	5	5	0.4	5	5	N/A	2
A Zone											
MW-02A	03/25/2020	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 1,000 U	< 200 U
MW-05A	03/17/2020	< 1.0 U	< 1.0 U	8.9	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 5.0 U	< 1.0 U
OW-09A	03/17/2020	< 100 U	< 100 U	7,800	< 100 U	< 100 U	< 100 U	280	< 100 U	< 500 U	< 100 U
OW-12A	03/24/2020	< 130 U	< 130 U	< 130 U	< 130 U	< 130 U	< 130 U	< 130 U	< 130 U	< 630 U	< 130 U
OW-15A	03/18/2020	< 10 U	< 10 U	< 10 U	< 10 U	< 10 U	< 10 U	< 10 U	< 10 U	< 50 U	< 10 U
OW-16A	03/17/2020	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 5.0 U	< 1.0 U
OW-18A	03/18/2020	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 1,000 U	< 200 U
OW-22A	03/24/2020	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 5.0 U	< 1.0 U
OW-29A	03/25/2020	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 200 U	< 1,000 U	< 200 U
B Zone											
MW-01B	03/24/2020	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 500 U	< 100 U
MW-04B	03/18/2020	< 200 U	< 200 U	1,800	< 200 U	< 200 U	< 200 U	6,000	< 200 U	< 1,000 U	< 200 U
MW-06B	03/25/2020	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 500 U	< 100 U
OW-05B	03/18/2020	< 200 U	< 200 U	2,000	< 200 U	< 200 U	< 200 U	4,700	< 200 U	< 1,000 U	< 200 U
DUP OW-05B	03/18/2020	< 100 U	< 100 U	1,800	< 100 U	< 100 U	< 100 U	4,100	< 100 U	< 500 U	110
OW-06B	03/18/2020	< 50 U	< 50 U	570	< 50 U	77	< 50 U	1,000	< 50 U	< 250 U	420
OW-07B	03/18/2020	< 1.0 U	< 1.0 U	37	< 1.0 U	11	< 1.0 U	96	< 1.0 U	< 5.0 U	< 1.0 U
OW-08B	03/18/2020	< 2.0 U	< 2.0 U	< 2.0 U	< 2.0 U	< 2.0 U	< 2.0 U	60	< 2.0 U	< 10 U	< 2.0 U
OW-10B	03/25/2020	< 500 U	< 500 U	< 500 U	< 500 U	< 500 U	< 500 U	< 500 U	< 500 U	< 2,500 U	< 500 U
OW-11B	03/25/2020	< 400 U	< 400 U	< 400 U	< 400 U	< 400 U	< 400 U	< 400 U	< 400 U	< 2,000 U	< 400 U
DUP OW-11B	03/25/2020	< 500 U	< 500 U	< 500 U	< 500 U	< 500 U	< 500 U	< 500 U	< 500 U	< 2,500 U	< 500 U
OW-12B	03/18/2020	< 1.0 U	< 1.0 U	2.1	< 1.0 U	4.3	< 1.0 U	2.6	< 1.0 U	< 5.0 U	14
OW-13B	03/17/2020	< 200 U	< 200 U	590	< 200 U	220	< 200 U	280	< 200 U	< 1,000 U	2,200
DUP OW-13B	03/18/2020	< 200 U	< 200 U	550	< 200 U	210	< 200 U	250	< 200 U	< 1,000 U	1,900
OW-14B	03/24/2020	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 100 U	< 500 U	< 100 U
OW-15B	03/24/2020	< 25 U	< 25 U	290	< 25 U	< 25 U	< 25 U	310	< 25 U	< 130 U	< 25 U
OW-18B	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS
OW-22B	03/24/2020	< 20 U	< 20 U	840 F1	< 20 U	< 20 U	< 20 U	1,900 F1	< 20 U	< 100 U	< 20 U
OW-26B	03/17/2020	< 2.0 U	< 2.0 U	110	< 2.0 U	< 2.0 U	< 2.0 U	8.3	< 2.0 U	< 10 U	< 2.0 U
OW-27B	03/17/2020	< 50 U	< 50 U	180	< 50 U	52	< 50 U	98	< 50 U	< 250 U	410
OW-28B	03/18/2020	< 50 U	< 50 U	1,300	< 50 U	47 J	< 50 U	2,700	< 50 U	< 250 U	55
OW-29B	03/18/2020	< 200 U	< 200 U	1,800	< 200 U	250	< 200 U	2,300	< 200 U	< 1,000 U	2,000
OW-30B	03/17/2020	< 1.0 U	< 1.0 U	26	< 1.0 U	3.6	< 1.0 U	33	< 1.0 U	< 5.0 U	0.96 J

TABLE 5.2 - GROUND WATER ANALYTICAL RESULTS
FIRST SEMI-ANNUAL 2020
SOLVENT CHEMICAL, 3163 BUFFALO AVENUE, NIAGARA FALLS, NY

Location	Date Sampled	Remaining Detected Analytes (Continued)									
		Styrene	tert-Butylbenzene	Tetrachloroethene	Toluene	trans-1,2-Dichloroethene	trans-1,3-Dichloropropene	Trichloroethene	Trichlorofluoromethane	Vinyl acetate	Vinyl chloride
C Zone											
MW-01C	03/25/2020	< 50 U	< 50 U	< 50 U	< 50 U	130	< 50 U	< 50 U	< 50 U	< 250 U	320
MW-04C	03/18/2020	< 400 U	< 400 U	3,600	< 400 U	< 400 U	< 400 U	3,800	< 400 U	< 2,000 U	1,200
MW-05C	03/17/2020	< 20 U	< 20 U	< 20 U	< 20 U	< 20 U	< 20 U	< 20 U	< 20 U	< 100 U	< 20 U
MW-06C	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS
CD Zone											
MW-01CD	03/25/2020	< 800 U	< 800 U	< 800 U	< 800 U	< 800 U	< 800 U	< 800 U	< 800 U	< 4,000 U	1,500
MW-05CD	03/17/2020	< 10 U	< 10 U	< 10 U	< 10 U	45	< 10 U	< 10 U	< 10 U	< 50 U	290
F Zone											
MW-01F	03/24/2020	< 50 U	< 50 U	< 50 U	< 50 U	< 50 U	< 50 U	< 50 U	< 50 U	< 250 U	2,300
MW-05F	03/24/2020	< 100 U	< 100 U	< 100 U	< 100 U	97 J	< 100 U	< 100 U	< 100 U	< 500 U	4,700
MW-06F	03/24/2020	< 20 U	< 20 U	< 20 U	< 20 U	39	< 20 U	< 20 U	< 20 U	< 100 U	1,500

Note:
All units in ug/l.
QUALIFIERS
GC/MS VOA
J: Estimated value.
J-: Estimated value; bias low.
N/A : Not available.
NS: Not Sampled
F1: MS and/or MSD Recovery is outside acceptance limits.
R: Rejected data point.
UJ: Estimated non-detect.
U: Non-detect.
* - NYSDEC Groundwater effluent limitations for discharges to Class GA waters, 2019.
N/A - No criteria available.
Values in **bold** indicate the analyte was detected.
Values shown in bold and shaded type exceed the listed criteria.

TABLE 5.3 - GROUND WATER ANALYTICAL RESULTS
SECOND SEMI-ANNUAL 2020
SOLVENT CHEMICAL, 3163 BUFFALO AVENUE, NIAGARA FALLS, NY

Location	Date Sampled	Contaminants of Concern						Remaining Detected Analytes															
		Benzene	Chlorobenzene	1,2,4-Trichlorobenzene	1,2-Dichlorobenzene	1,3-Dichlorobenzene	1,4-Dichlorobenzene	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane	1,2,4-Trimethylbenzene	1,2-Dibromo-3-chloropropane	1,2-Dibromoethane	1,2-Dichloroethane	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichloropropane
	Effluent Limit*	1	5	5	3	3	3	N/A	5	5	1	5	5	N/A	5	0.04	5	0.04	0.0006	0.6	1	5	N/A
A Zone																							
MW-02A	09/17/2020	39	960	27	530	330	720	20 U	20 U	20 U	20 U	20 U	20 U	20 U	13 J	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U
MW-05A	09/15/2020	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U
OW-09A	09/15/2020	50 U	50 U	50 U	610	50 U	50 U	50 U	50 U	50 U	50 U	50 U	50 U	50 U	50 U	50 U	50 U	50 U	50 U	50 U	50 U	50 U	50 U
OW-12A	09/17/2020	92 J	4,300	110 J	3,100	400	1,700	200 U	200 U	200 U	200 U	200 U	200 U	200 U	200 U	200 U	200 U	200 U	200 U	200 U	200 U	200 U	200 U
OW-15A	09/15/2020	20 U	320	56	740	250	440	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U
OW-16A	09/15/2020	1.0 U	1.0 U	1.0 U	20	1.0 U	3.4	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U
OW-18A	09/17/2020	550	11,000	130 J	8,400	1,500	13,000	200 U	200 U	200 U	200 U	200 U	200 U	200 U	200 U	200 U	200 U	200 U	200 U	200 U	200 U	200 U	200 U
OW-22A	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS
OW-29A	09/17/2020	200 U	5,400	640	7,000	1,500	4,000	200 U	200 U	200 U	200 U	200 U	200 U	200 U	190 J	200 U	200 U	200 U	200 U	200 U	200 U	200 U	200 U
B Zone																							
MW-01B	09/15/2020	730	51,000	560	4,500	3,000	15,000	200 U	200 U	200 U	200 U	200 U	200 U	200 U	110 J	200 U	200 U	200 U	200 U	200 U	200 U	200 U	200 U
MW-04B	09/15/2020	40 U	40 U	35 J	40 U	40 U	40 U	40 U	40 U	180	40 U	40 U	40 U	40 U	21 J	40 U	40 U	40 U	40 U	40 U	40 U	40 U	40 U
MW-06B	09/17/2020	790	6,700	160	5,600	2,100	4,900	80 U	80 U	80 U	80 U	80 U	80 U	80 U	37 J	80 U	80 U	80 U	80 U	80 U	80 U	80 U	80 U
OW-05B	09/16/2020	36 J	160	160 J	100	110	130 J	40 U	40 U	120	40 U	40 U	40 U	40 U	57	40 U	40 U	40 U	40 U	40 U	40 U	40 U	40 U
DUP OW-05B	09/16/2020	39 J	190	220	130	140	180	40 U	40 U	140	40 U	40 U	40 U	40 U	86	40 U	40 U	40 U	40 U	40 U	40 U	40 U	40 U
OW-06B	09/16/2020	110	730	1,600	930	380	790	20 U	20 U	110	20 U	20 U	18 J	20 U	48	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U
OW-07B	09/16/2020	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	32	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U
OW-08B	09/16/2020	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.7	1.0	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U
OW-10B	09/17/2020	3,300	27,000	1,500	11,000	3,200	13,000	500 U	500 U	500 U	500 U	500 U	500 U	500 U	340 J	500 U	500 U	500 U	500 U	500 U	500 U	500 U	500 U
OW-11B	09/17/2020	5,100	11,000	2,000	18,000	5,600	16,000	400 U	400 U	400 U	400 U	400 U	400 U	400 U	800	400 U	400 U	400 U	400 U	400 U	400 U	400 U	400 U
DUP OW-11B	09/17/2020	4,400	9,800	2,100	18,000	5,700	16,000	500 U	500 U	500 U	500 U	500 U	500 U	500 U	820	500 U	500 U	500 U	500 U	500 U	500 U	500 U	500 U
OW-12B	09/15/2020	7.3	160	5.0 U	86	91	180	5.0 U	5.0 U	5.0 U	5.0 U	2.0 J	5.0 U	5.0 U	5.0 U	5.0 U	5.0 U	5.0 U	5.0 U	5.0 U	5.0 U	5.0 U	5.0 U
OW-13B	09/15/2020	510	4,700	5,500	6,500	1,500	5,100	80 U	80 U	510	80 U	80 U	80 U	80 U	410	80 U	80 U	80 U	80 U	80 U	80 U	80 U	80 U
DUP OW-13B	09/15/2020	480	4,600	5,600	6,500	1,400	5,000	80 U	80 U	490	28 J	80 U	44 J	80 U	400	80 U	80 U	80 U	80 U	80 U	80 U	80 U	80 U
OW-14B	09/16/2020	100 U	1,700	850	4,500	1,700	6,300	100 U	100 U	100 U	100 U	100 U	100 U	100 U	230	100 U	100 U	100 U	100 U	100 U	100 U	100 U	100 U
OW-15B	09/16/2020	2.0 U	2.0 U	1.0 J	2.0 U	2.0 U	1.7 J	2.0 U	2.0 U	52	1.5 J	2.0 U	2.0 U	2.0 U	0.97 J	2.0 U	2.0 U	2.0 U	2.0 U	2.0 U	2.0 U	2.0 U	2.0 U
OW-18B	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS
OW-22B	09/16/2020	20 U	20 U	11 J	20 U	20 U	20 U	20 U	20 U	57	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U
OW-26B	09/15/2020	20	120	5.0 U	9.3	13	16	5.0 U	5.0 U	5.0 U	5.0 U	5.0 U	5.0 U	5.0 U	5.0 U	5.0 U	5.0 U	5.0 U	5.0 U	5.0 U	5.0 U	5.0 U	5.0 U
OW-27B	09/15/2020	140	480	59	280	260	330	50 U	50 U	220	50 U	50 U	26 J	50 U	50 U	50 U	50 U	50 U	50 U	50 U	50 U	50 U	50 U
OW-28B	09/15/2020	10 U	41	29	28	25	44	10 U	10 U	75	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U
OW-29B	09/15/2020	260	790	2,000	1,100	540	990	40 U	64	1,600	40 U	40 U	60	40 U	390	40 U	40 U	40 U	40 U	40 U	40 U	40 U	40 U
OW-30B	09/15/2020	200	1,600	1.0 U	92	110	230	1.0 U	1.0 U	1.0 U	1.0 U	5.4	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U
C Zone																							
MW-01C	09/15/2020	450	50 U	50 U	50 U	50 U	50 U	50 U	50 U	50 U	50 U	50 U	50 U	50 U	50 U	50 U	50 U	50 U	50 U	50 U	50 U	50 U	50 U
MW-04C	09/15/2020	3,300	4,900	400 U	770	400 U	480	400 U	400 U	400 U	400 U	400 U	400 U	400 U	400 U	400 U	400 U	400 U	400 U	400 U	400 U	400 U	400 U
MW-05C	09/15/2020	38	500	20 U	68	63	150	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U
MW-06C	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS
CD Zone																							
MW-01CD	09/15/2020	4,700	44,000	800 U	12,000	1,500	8,100	800 U	800 U	800 U	800 U	800 U	800 U	800 U	800 U	800 U	800 U	800 U	800 U	800 U	800 U	800 U	800 U
MW-05CD	09/15/2020	33	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U

TABLE 5.3 - GROUND WATER ANALYTICAL RESULTS
SECOND SEMI-ANNUAL 2020
SOLVENT CHEMICAL, 3163 BUFFALO AVENUE, NIAGARA FALLS, NY

Location	Date Sampled	Contaminants of Concern						Remaining Detected Analytes															
		Benzene	Chlorobenzene	1,2,4-Trichlorobenzene	1,2-Dichlorobenzene	1,3-Dichlorobenzene	1,4-Dichlorobenzene	1,1,1,2-Tetrachloroethane	1,1,1-Trichloroethane	1,1,2,2-Tetrachloroethane	1,1,2-Trichloroethane	1,1-Dichloroethane	1,1-Dichloroethene	1,1-Dichloropropene	1,2,3-Trichlorobenzene	1,2,3-Trichloropropane	1,2,4-Trimethylbenzene	1,2-Dibromo-3-chloropropane	1,2-Dibromoethane	1,2-Dichloroethane	1,2-Dichloropropane	1,3,5-Trimethylbenzene	1,3-Dichloropropane
F Zone																							
MW-01F	09/15/2020	50 U	50 U	50 U	50 U	50 U	50 U	50 U	50 U	50 U	50 U	50 U	50 U	50 U	50 U	50 U	50 U	50 U	50 U	50 U	50 U	50 U	50 U
MW-05F	09/15/2020	100 U	190	100 U	220	100 U	100	100 U	100 U	100 U	100 U	100 U	100 U	100 U	100 U	100 U	100 U	100 U	100 U	100 U	100 U	100 U	100 U
MW-06F	09/17/2020	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	6.3 J	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U

Note:
All units in ug/l.
QUALIFIERS
GC/MS VOA
B: Analyte detected in associated method blank.
J: Estimated value.
J-: Estimated value; bias low.
N/A : Not available.
NS: Not Sampled
R: Rejected data point.
U: Non-detect.
* - NYSDEC Groundwater effluent limitations for discharges to Class GA waters, 2019.
Values in **bold** indicate the analyte was detected.
Values shown in bold and shaded type exceed the listed criteria.

TABLE 5.3 - GROUND WATER ANALYTICAL RESULTS
SECOND SEMI-ANNUAL 2020
SOLVENT CHEMICAL, 3163 BUFFALO AVENUE, NIAGARA FALLS, NY

Location	Date Sampled	Remaining Detected Analytes (Continued)																						
		2,2-Dichloropropane	2-Butanone (MEK)	2-Chloroethyl vinyl ether	2-Hexanone	4-Methyl-2-pentanone	Acetone	Bromobenzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon tetrachloride	Chloroethane	Chloroform	Chloromethane	cis-1,2-Dichloroethene	cis-1,3-Dichloropropene	Dibromochloromethane	Dichlorodifluoromethane	Ethylbenzene	Hexachlorobutadiene	Isopropylbenzene
	Effluent Limit*	N/A	50	N/A	50	N/A	50	5	5	50	50	5	120	5	5	7	5	5	0.4	50	5	5	0.5	5
A Zone																								
MW-02A	09/17/2020	20 U	200 U	100 U	100 U	100 U	200 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	40 U	20 U
MW-05A	09/15/2020	1.0 U	10 U	5.0 U	5.0 U	5.0 U	10 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	2.0 U	1.0 U
OW-09A	09/15/2020	50 U	500 U	250 U	250 U	250 U	500 U	50 U	50 U	50 U	50 U	50 U	50 U	50 U	50 U	50 U	50 U	730	50 U	50 U	50 U	50 U	100 U	50 U
OW-12A	09/17/2020	200 U	2,000 U	1,000 U	1,000 U	1,000 U	2,000 U	200 U	200 U	200 U	200 U	200 U	200 U	200 U	200 U	200 U	200 U	200 U	200 U	200 U	200 U	200 U	400 U	200 U
OW-15A	09/15/2020	20 U	200 U	100 U	100 U	100 U	200 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	40 U	20 U
OW-16A	09/15/2020	1.0 U	10 U	5.0 U	5.0 U	5.0 U	10 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	2.0 U	1.0 U
OW-18A	09/17/2020	200 U	2,000 U	1,000 U	1,000 U	1,000 U	2,000 U	200 U	200 U	200 U	200 U	200 U	200 U	200 U	200 U	200 U	200 U	200 U	200 U	200 U	200 U	200 U	400 U	200 U
OW-22A	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS
OW-29A	09/17/2020	200 U	2,000 U	1,000 U	1,000 U	1,000 U	2,000 U	200 U	200 U	200 U	200 U	200 U	200 U	200 U	200 U	200 U	200 U	200 U	200 U	200 U	200 U	200 U	400 U	200 U
B Zone																								
MW-01B	09/15/2020	200 U	2,000 U	1,000 U	1,000 U	1,000 U	2,000 U	200 U	200 U	200 U	200 U	200 U	200 U	200 U	200 U	200 U	200 U	200 U	200 U	200 U	200 U	200 U	400 U	200 U
MW-04B	09/15/2020	40 U	400 U	200 U	200 U	200 U	400 U	40 U	40 U	40 U	40 U	40 U	40 U	40 U	40 U	40 U	40 U	970	40 U	40 U	40 U	40 U	80 U	40 U
MW-06B	09/17/2020	80 U	800 U	400 U	400 U	400 U	800 U	80 U	80 U	80 U	80 U	80 U	80 U	80 U	80 U	80 U	80 U	97	80 U	80 U	80 U	80 U	160 U	80 U
OW-05B	09/16/2020	40 U	400 U	R	200 U	200 U	400 U	40 U	40 U	40 U	40 U	40 U	40 U	40 U	40 U	40 U	40 U	1,200	40 U	40 U	40 U	40 U	80 U	40 U
DUP OW-05B	09/16/2020	40 U	400 U	200 U	200 U	200 U	400 U	40 U	40 U	40 U	40 U	40 U	40 U	40 U	40 U	40 U	40 U	1,400	40 U	40 U	40 U	40 U	80 U	40 U
OW-06B	09/16/2020	20 U	200 U	100 U	100 U	100 U	200 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	3,400	20 U	20 U	20 U	20 U	40 U	20 U
OW-07B	09/16/2020	10 U	100 U	50 U	50 U	50 U	100 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	220	10 U	10 U	10 U	10 U	20 U	10 U
OW-08B	09/16/2020	1.0 U	10 U	5.0 U	5.0 U	5.0 U	10 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	24	1.0 U	1.0 U	1.0 U	1.0 U	2.0 U	1.0 U
OW-10B	09/17/2020	500 U	5,000 U	R	2,500 U	2,500 U	5,000 U	500 U	500 U	500 U	500 U	500 U	500 U	500 U	500 U	500 U	500 U	500 U	500 U	500 U	500 U	500 U	1,000 U	500 U
OW-11B	09/17/2020	400 U	4,000 U	2,000 U	2,000 U	2,000 U	4,000 U	400 U	400 U	400 U	400 U	400 U	400 U	400 U	400 U	400 U	400 U	400 U	400 U	400 U	400 U	400 U	800 U	400 U
DUP OW-11B	09/17/2020	500 U	5,000 U	2,500 U	2,500 U	2,500 U	5,000 U	500 U	500 U	500 U	500 U	500 U	500 U	500 U	500 U	500 U	500 U	500 U	500 U	500 U	500 U	500 U	1,000 U	500 U
OW-12B	09/15/2020	5.0 U	50 U	25 U	25 U	25 U	50 U	5.0 U	5.0 U	5.0 U	5.0 U	5.0 U	5.0 U	5.0 U	5.0 U	5.0 U	5.0 U	49	5.0 U	5.0 U	5.0 U	5.0 U	10 U	5.0 U
OW-13B	09/15/2020	80 U	800 U	400 U	400 U	400 U	800 U	80 U	80 U	80 U	80 U	80 U	80 U	80 U	80 U	80 U	80 U	63 J	80 U	80 U	80 U	80 U	160 U	80 U
DUP OW-13B	09/15/2020	80 U	800 U	400 U	400 U	400 U	800 U	80 U	80 U	80 U	80 U	80 U	80 U	80 U	80 U	80 U	80 U	57 J	80 U	80 U	80 U	80 U	160 U	80 U
OW-14B	09/16/2020	100 U	1,000 U	500 U	500 U	500 U	1,000 U	100 U	100 U	100 U	100 U	100 U	100 U	100 U	100 U	100 U	100 U	100 U	100 U	100 U	100 U	100 U	200 U	100 U
OW-15B	09/16/2020	2.0 U	20 U	10 U	10 U	10 U	20 U	2.0 U	2.0 U	2.0 U	2.0 U	2.0 U	2.0 U	2.0 U	2.0 U	2.0 U	2.0 U	9.6	2.0 U	2.0 U	2.0 U	2.0 U	4.0 U	2.0 U
OW-18B	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS
OW-22B	09/16/2020	20 U	200 U	R	100 U	100 U	200 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	12 J	20 U	20 U	20 U	20 U	40 U	20 U
OW-26B	09/15/2020	5.0 U	50 U	25 U	25 U	25 U	50 U	5.0 U	5.0 U	5.0 U	5.0 U	5.0 U	5.0 U	5.0 U	5.0 U	5.0 U	5.0 U	4.9 J	5.0 U	5.0 U	5.0 U	5.0 U	10 U	5.0 U
OW-27B	09/15/2020	50 U	500 U	250 U	250 U	250 U	500 U	50 U	50 U	50 U	50 U	50 U	50 U	50 U	50 U	50 U	50 U	27 J	50 U	50 U	50 U	50 U	100 U	50 U
OW-28B	09/15/2020	10 U	100 U	50 U	50 U	50 U	100 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	33	10 U	10 U	10 U	10 U	20 U	10 U
OW-29B	09/15/2020	40 U	400 U	200 U	200 U	200 U	400 U	40 U	40 U	40 U	40 U	40 U	40 U	40 U	40 U	40 U	40 U	430	40 U	40 U	40 U	40 U	80 U	40 U
OW-30B	09/15/2020	1.0 U	10 U	5.0 U	5.0 U	5.0 U	10 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	16	1.0 U	1.0 U	1.0 U	1.6	2.0 U	1.0 U
C Zone																								
MW-01C	09/15/2020	50 U	500 U	250 U	250 U	250 U	500 U	50 U	50 U	50 U	50 U	50 U	50 U	50 U	50 U	50 U	50 U	2,500	50 U	50 U	50 U	50 U	100 U	50 U
MW-04C	09/15/2020	400 U	4,000 U	R	2,000 U	2,000 U	4,000 U	400 U	400 U	400 U	400 U	400 U	400 U	400 U	400 U	400 U	400 U	24,000 J-	400 U	400 U	400 U	400 U	800 U	400 U
MW-05C	09/15/2020	20 U	200 U	100 U	100 U	100 U	200 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	40 U	20 U
MW-06C	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS
CD Zone																								
MW-01CD	09/15/2020	800 U	8000 U	4,000 U	4,000 U	4,000 U	8000 U	800 U	800 U	800 U	800 U	800 U	800 U	800 U	800 U	800 U	800 U	7,500	800 U	800 U	800 U	800 U	1600 U	800 U
MW-05CD	09/15/2020	10 U	100 U	50 U	50 U	50 U	100 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	590	10 U	10 U	10 U	10 U	20 U	10 U

TABLE 5.3 - GROUND WATER ANALYTICAL RESULTS
SECOND SEMI-ANNUAL 2020
SOLVENT CHEMICAL, 3163 BUFFALO AVENUE, NIAGARA FALLS, NY

Location	Date Sampled	Remaining Detected Analytes (Continued)																						
		2,2-Dichloropropane	2-Butanone (MEK)	2-Chloroethyl vinyl ether	2-Hexanone	4-Methyl-2-pentanone	Acetone	Bromobenzene	Bromochloromethane	Bromodichloromethane	Bromoform	Bromomethane	Carbon disulfide	Carbon tetrachloride	Chloroethane	Chloroform	Chloromethane	cis-1,2-Dichloroethene	cis-1,3-Dichloropropene	Dibromochloromethane	Dichlorodifluoromethane	Ethylbenzene	Hexachlorobutadiene	Isopropylbenzene
F Zone																								
MW-01F	09/15/2020	50 U	500 U	250 U	250 U	250 U	500 U	50 U	50 U	50 U	50 U	50 U	50 U	50 U	50 U	50 U	50 U	50 U	50 U	50 U	50 U	50 U	100 U	50 U
MW-05F	09/15/2020	100 U	1,000 U	500 U	500 U	500 U	1,000 U	100 U	100 U	100 U	100 U	100 U	100 U	100 U	100 U	100 U	100 U	110	100 U	100 U	100 U	100 U	200 U	100 U
MW-06F	09/17/2020	20 U	200 U	100 U	100 U	100 U	150 J	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	1,000	20 U	20 U	20 U	20 U	40 U	20 U

Note:
All units in ug/l.
QUALIFIERS
GC/MS VOA
B: Analyte detected in associated method blank.
J: Estimated value.
J-: Estimated value; bias low.
N/A : Not available.
NS: Not Sampled
R: Rejected data point.
U: Non-detect.
* - NYSDEC Groundwater effluent limitations for discharges to Class GA waters, 2019.
Values in **bold** indicate the analyte was detected.
Values shown in bold and shaded type exceed the listed criteria.

TABLE 5.3 - GROUND WATER ANALYTICAL RESULTS
SECOND SEMI-ANNUAL 2020
SOLVENT CHEMICAL, 3163 BUFFALO AVENUE, NIAGARA FALLS, NY

Location	Date Sampled	Remaining Detected Analytes (Continued)																				
		m,p-Xylene	Methyl tert-butyl ether	Methylene chloride	n-Butylbenzene	n-Propylbenzene	Naphthalene	2-Chlorotoluene	o-Xylene	4-Chlorotoluene	4-Isopropyltoluene	sec-Butylbenzene	Styrene	tert-Butylbenzene	Tetrachloroethene	Toluene	trans-1,2-Dichloroethene	trans-1,3-Dichloropropene	Trichloroethene	Trichlorofluoromethane	Vinyl acetate	Vinyl chloride
	Effluent Limit*	5	10	5	5	5	10	5	5	5	5	5	5	5	5	5	5	0.4	5	5	N/A	2
A Zone																						
MW-02A	09/17/2020	40 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	9.5 J	20 U	20 U	20 U	20 U	20 U	100 U	20 U
MW-05A	09/15/2020	2.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	21	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	5.0 U	1.0 U
OW-09A	09/15/2020	100 U	50 U	50 U	50 U	50 U	50 U	50 U	50 U	50 U	50 U	50 U	50 U	50 U	4,400	50 U	50 U	50 U	380	50 U	250 U	50 U
OW-12A	09/17/2020	400 U	200 U	200 U	200 U	200 U	200 U	200 U	200 U	200 U	200 U	200 U	200 U	200 U	200 U	200 U	200 U	200 U	200 U	200 U	1,000 U	200 U
OW-15A	09/15/2020	40 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	100 U	20 U
OW-16A	09/15/2020	2.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	5.0 U	1.0 U
OW-18A	09/17/2020	400 U	200 U	200 U	200 U	200 U	200 U	200 U	200 U	200 U	200 U	200 U	200 U	200 U	200 U	200 U	200 U	200 U	200 U	200 U	1,000 U	200 U
OW-22A	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS
OW-29A	09/17/2020	400 U	200 U	200 U	200 U	200 U	200 U	200 U	200 U	200 U	200 U	200 U	200 U	200 U	200 U	200 U	200 U	200 U	200 U	200 U	1,000 U	200 U
B Zone																						
MW-01B	09/15/2020	400 U	200 U	150 BJ	200 U	200 U	200 U	200 U	200 U	200 U	200 U	200 U	200 U	200 U	200 U	200 U	200 U	200 U	200 U	200 U	1,000 U	200 U
MW-04B	09/15/2020	80 U	40 U	40 U	40 U	40 U	40 U	40 U	40 U	40 U	40 U	40 U	40 U	40 U	980	40 U	40 U	40 U	2,200	40 U	200 U	40 U
MW-06B	09/17/2020	160 U	80 U	80 U	80 U	80 U	80 U	80 U	80 U	80 U	80 U	80 U	80 U	80 U	80 U	80 U	80 U	80 U	80 U	80 U	400 U	80 U
OW-05B	09/16/2020	80 U	40 U	20 J	40 U	40 U	40 U	40 U	40 U	40 U	40 U	40 U	40 U	40 U	1,700	40 U	44	40 U	2,100	40 U	200 U	160
DUP OW-05B	09/16/2020	80 U	40 U	40 U	40 U	40 U	40 U	40 U	40 U	40 U	40 U	40 U	40 U	40 U	2,100	40 U	49	40 U	2,500	40 U	200 U	180
OW-06B	09/16/2020	40 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	780	20 U	120	20 U	1,800	20 U	100 U	580
OW-07B	09/16/2020	20 U	10 U	5.2 J	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	28	10 U	17	10 U	150	10 U	50 U	10 U
OW-08B	09/16/2020	2.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	0.38 J	1.0 U	1.0 U	1.0 U	30	1.0 U	5.0 U	2.8
OW-10B	09/17/2020	1,000 U	500 U	500 U	500 U	500 U	500 U	500 U	500 U	500 U	500 U	500 U	500 U	500 U	500 U	500 U	500 U	500 U	500 U	500 U	2,500 U	500 U
OW-11B	09/17/2020	800 U	400 U	400 U	400 U	400 U	400 U	400 U	400 U	400 U	400 U	400 U	400 U	400 U	400 U	400 U	400 U	400 U	400 U	400 U	2,000 U	400 U
DUP OW-11B	09/17/2020	1,000 U	500 U	500 U	500 U	500 U	500 U	500 U	500 U	500 U	500 U	500 U	500 U	500 U	500 U	500 U	500 U	500 U	500 U	500 U	2,500 U	500 U
OW-12B	09/15/2020	10 U	5.0 U	2.7 J	5.0 U	5.0 U	5.0 U	5.0 U	5.0 U	5.0 U	5.0 U	5.0 U	5.0 U	5.0 U	5.0 U	5.0 U	6.1	5.0 U	5.0 U	5.0 U	25 U	17
OW-13B	09/15/2020	160 U	80 U	80 U	80 U	80 U	80 U	80 U	80 U	80 U	80 U	80 U	80 U	80 U	1,500	80 U	260	80 U	5,200	80 U	400 U	1,200
DUP OW-13B	09/15/2020	160 U	80 U	80 U	80 U	80 U	80 U	80 U	80 U	80 U	80 U	80 U	80 U	80 U	1,500	80 U	210	80 U	4,700	80 U	400 U	1,100
OW-14B	09/16/2020	200 U	100 U	78 BJ	100 U	100 U	100 U	100 U	100 U	100 U	100 U	100 U	100 U	100 U	100 U	100 U	100 U	100 U	100 U	100 U	500 U	100 U
OW-15B	09/16/2020	4.0 U	2.0 U	1.3 J	2.0 U	2.0 U	2.0 U	2.0 U	2.0 U	2.0 U	2.0 U	2.0 U	2.0 U	2.0 U	54	2.0 U	2.3	2.0 U	87	2.0 U	10 U	2.0
OW-18B	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS
OW-22B	09/16/2020	40 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	270 J-	20 U	20 U	20 U	280 J-	20 U	100 U	20 U
OW-26B	09/15/2020	10 U	5.0 U	5.0 U	5.0 U	5.0 U	5.0 U	5.0 U	5.0 U	5.0 U	5.0 U	5.0 U	5.0 U	5.0 U	18	5.0 U	5.0 U	5.0 U	5.0 U	5.0 U	25 U	4.8 J
OW-27B	09/15/2020	100 U	50 U	50 U	50 U	50 U	50 U	50 U	50 U	50 U	50 U	50 U	50 U	50 U	520	50 U	190	50 U	2200	50 U	250 U	240
OW-28B	09/15/2020	20 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	370	10 U	22	10 U	640	10 U	50 U	78
OW-29B	09/15/2020	80 U	40 U	40 U	40 U	40 U	40 U	40 U	40 U	40 U	40 U	40 U	40 U	40 U	5,800	40 U	190	40 U	15,000	40 U	200 U	730
OW-30B	09/15/2020	2.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U	22	0.86 J	5.3	1.0 U	8.4	1.0 U	5.0 U	30
C Zone																						
MW-01C	09/15/2020	100 U	50 U	36 BJ	50 U	50 U	50 U	50 U	50 U	50 U	50 U	50 U	50 U	50 U	50 U	50 U	140	50 U	50 U	50 U	250 U	560
MW-04C	09/15/2020	800 U	400 U	400 U	400 U	400 U	400 U	400 U	400 U	400 U	400 U	400 U	400 U	400 U	400 U	400 U	400 U	400 U	680	400 U	2,000 U	2,100
MW-05C	09/15/2020	40 U	20 U	13 J	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	100 U	20 U
MW-06C	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS
CD Zone																						
MW-01CD	09/15/2020	1600 U	800 U	350 J	800 U	800 U	800 U	800 U	800 U	800 U	800 U	800 U	800 U	800 U	800 U	800 U	800 U	800 U	800 U	800 U	4,000 U	2,100
MW-05CD	09/15/2020	20 U	10 U	5.2 J	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	10 U	44	10 U	10 U	10 U	50 U	370

TABLE 5.3 - GROUND WATER ANALYTICAL RESULTS
SECOND SEMI-ANNUAL 2020
SOLVENT CHEMICAL, 3163 BUFFALO AVENUE, NIAGARA FALLS, NY

Location	Date Sampled	Remaining Detected Analytes (Continued)																				
		m,p-Xylene	Methyl tert-butyl ether	Methylene chloride	n-Butylbenzene	n-Propylbenzene	Naphthalene	2-Chlorotoluene	o-Xylene	4-Chlorotoluene	4-Isopropyltoluene	sec-Butylbenzene	Styrene	tert-Butylbenzene	Tetrachloroethene	Toluene	trans-1,2-Dichloroethene	trans-1,3-Dichloropropene	Trichloroethene	Trichlorofluoromethane	Vinyl acetate	Vinyl chloride
F Zone																						
MW-01F	09/15/2020	100 U	50 U	36 BJ	50 U	50 U	50 U	50 U	50 U	50 U	50 U	50 U	50 U	50 U	50 U	50 U	50 U	50 U	50 U	50 U	250 U	2,200
MW-05F	09/15/2020	200 U	100 U	100 U	100 U	100 U	100 U	100 U	100 U	100 U	100 U	100 U	100 U	100 U	100 U	100 U	100 U	100 U	100 U	100 U	500 U	2,200
MW-06F	09/17/2020	40 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	20 U	40	20 U	20 U	20 U	100 U	1,800

Note:
All units in ug/l.
QUALIFIERS
GC/MS VOA
B: Analyte detected in associated method blank.
J: Estimated value.
J-: Estimated value; bias low.
N/A : Not available.
NS: Not Sampled
R: Rejected data point.
U: Non-detect.
* - NYSDEC Groundwater effluent limitations for discharges to Class GA waters, 2019.
Values in **bold** indicate the analyte was detected.
Values shown in bold and shaded type exceed the listed criteria.

TABLE 6.1 - GROUNDWATER ELEVATIONS
 SOLVENT CHEMICAL, 3163 BUFFALO AVENUE, NIAGARA FALLS, NEW YORK
 1ST QUARTER 2020

	Reference	3/17/2020	
Monitoring	Elevation	DTW	Elevation
Well No.	(ft.)	(ft)	(ft.)
A - Zone:			
MW-1A	572.45	7.80	564.65
MW-2A	572.16	6.73	565.43
MW-5A	570.56	8.52	562.04
MW-6A	573.28	7.40	565.88
OW-1A	570.46	5.75	564.71
OW-5A	573.05	12.09	560.96
OW-6A	572.10	9.70	562.40
OW-7A	574.00	9.52	564.48
OW-8A	572.82	9.58	563.24
OW-9A	574.13	11.93	562.20
OW-10A	568.29	DRY	DRY
OW-11A	575.26	10.62	564.64
OW-12A	575.41	10.76	564.65
OW-13A	574.95	9.49	565.46
OW-14A	575.21	9.73	565.48
OW-15A	569.19	5.79	563.40
OW-16A	572.05	6.74	565.31
OW-17A	567.85	7.10	560.75
OW-18A	575.87	9.50	566.37
OW-19A	572.89	7.26	565.63
OW-20A	572.62	11.96	560.66
OW-21A	569.33	5.71	563.62
OW-22A	570.68	6.60	564.08
OW-26A	570.63	10.32	560.31
OW-27A	570.34	7.93	562.41
OW-29A	573.14	7.63	565.51
TW-1A	569.19	7.48	561.71
TW-2A	569.72	5.14	564.58
TW-3A	571.16	6.50	564.66
TW-4A	569.82	NM	-
TW-5A	569.33	NM	-
B-Zone:			
MW-1B	572.44	8.27	564.17
MW-2B	572.46	12.97	559.49
MW-4B ⁽¹⁾	573.50	18.14	555.36
MW-5B	571.48	DRY	DRY
MW-6B	573.40	16.82	556.58
OW-1B	570.95	14.00	556.95
OW-2B	573.98	19.88	554.10
OW-3B	572.64	16.27	556.37
OW-4B	570.55	13.67	556.88
OW-5B	568.31	11.88	556.43
OW-6B ⁽⁴⁾	573.10	20.35	552.75
OW-7B ⁽⁴⁾	572.73	26.67	546.06
OW-8B ⁽⁴⁾	572.53	23.02	549.51
OW-10B	572.62	15.89	556.73
OW-11B	571.93	15.00	556.93
OW-12B	571.85	23.67	548.18
OW-13B	571.68	18.05	553.63
OW-14B ⁽¹⁾	570.87	14.23	556.64
OW-15B ⁽¹⁾	569.78	12.95	556.83
OW-18B ⁽²⁾	576.05	NM	-
OW-22B ⁽¹⁾	570.90	14.30	556.60
OW-23B ⁽¹⁾	569.67	13.10	556.57
OW-24B ⁽¹⁾	570.36	13.70	556.66

TABLE 6.1 - GROUNDWATER ELEVATIONS
SOLVENT CHEMICAL, 3163 BUFFALO AVENUE, NIAGARA FALLS, NEW YORK
1ST QUARTER 2020

Monitoring Well No.	Reference	3/17/2020	
	Elevation (ft.)	DTW (ft)	Elevation (ft.)
OW-25B ⁽¹⁾	570.9	14.1	556.80
OW-26B	571.64	22.82	548.82
OW-27B	569.81	17.18	552.63
OW-28B	568.76	13.71	555.05
OW-29B	568.16	13.55	554.61
OW-30B	568.10	19.52	548.58
OW-31B ⁽¹⁾	570.14	13.27	556.87
OW-32B ⁽¹⁾	569.99	13.16	556.83
OW-33B ⁽¹⁾	569.55	12.82	556.73
PW-1B	572.34	14.26	558.08
PW-2B	571.60	19.19	552.41
PW-3B ⁽¹⁾	571.21	21.75	549.46
PW-4B ⁽¹⁾	569.72	14.50	555.22
PW-5B	572.74	19.38	553.36
PW-6B	573.95	25.60	548.35
PW-7B	571.15	16.80	554.35
PW-8B	572.36	23.35	549.01
C-Zone:			
MW-1C	572.53	16.71	555.82
MW-4C	571.42	28.27	543.15
MW-5C	572.75	24.96	547.79
MW-6C ⁽³⁾	573.60	NM	-
CD-Zone:			
MW-1CD	572.78	17.10	555.68
MW-5CD	570.50	26.20	544.30
MW-6CD ⁽²⁾	573.45	NM	-
F-Zone:			
MW-1F	572.40	16.02	556.38
MW-5F	572.78	19.10	553.68
MW-6F	573.52	19.96	553.56
Piezometers:			
PZ-01	572.46	6.97	565.49
PZ-02	572.14	6.69	565.45
PZ-03	571.95	6.53	565.42
PZ-04	572.03	6.60	565.43

Notes:

- 1) Monitoring wells within the Hot Spot were measured on 3/24/20.
- 2) OW-18B and MW-6CD were not measured due to an obstruction in the well.
- 3) MW-6C is bailed monthly.
- 4) Monitoring wells measured on 3/18/20.

TABLE 6.2 - GROUNDWATER ELEVATIONS
 SOLVENT CHEMICAL, 3163 BUFFALO AVENUE, NIAGARA FALLS, NEW YORK
 3RD QUARTER 2020

Monitoring Well No.	Reference	9/15/2020 and 9/16/2020	
	Elevation (ft.)	DTW (ft)	Elevation (ft.)
A - Zone:			
MW-1A	572.45	DRY	DRY
MW-2A	572.16	12.69	559.47
MW-5A	570.56	10.85	559.71
MW-6A	573.28	11.29	561.99
OW-1A	570.46	8.07	562.39
OW-5A	573.05	DRY	DRY
OW-6A	572.10	10.98	561.12
OW-7A	574.00	DRY	DRY
OW-8A	572.82	10.91	561.91
OW-9A	574.13	13.04	561.09
OW-10A	568.29	DRY	DRY
OW-11A	575.26	13.14	562.12
OW-12A	575.41	12.40	563.01
OW-13A	574.95	14.63	560.32
OW-14A	575.21	13.75	561.46
OW-15A	569.19	8.78	560.41
OW-16A	572.05	10.32	561.73
OW-17A	567.85	DRY	DRY
OW-18A	575.87	12.21	563.66
OW-19A	572.89	9.88	563.01
OW-20A	572.62	DRY	DRY
OW-21A	569.33	DRY	DRY
OW-22A	570.68	DRY	DRY
OW-26A	570.63	DRY	DRY
OW-27A	570.34	9.46	560.88
OW-29A	573.14	7.71	565.43
TW-1A	569.19	8.81	560.38
TW-2A	569.72	8.74	560.98
TW-3A	571.16	9.17	561.99
TW-4A	569.82	10.51	559.31
TW-5A	569.33	7.77	561.56
B-Zone:			
MW-1B	572.44	10.18	562.26
MW-2B	572.46	14.51	557.95
MW-4B ⁽¹⁾	573.50	17.66	555.84
MW-5B	571.48	DRY	DRY
MW-6B	573.40	18.13	555.27
OW-1B	570.95	13.98	556.97
OW-2B	573.98	18.46	555.52
OW-3B	572.64	15.95	556.69
OW-4B	570.55	13.51	557.04
OW-5B	568.31	11.55	556.76
OW-6B	573.10	20.48	552.62
OW-7B	572.73	26.47	546.26
OW-8B	572.53	25.57	546.96
OW-10B	572.62	15.38	557.24
OW-11B	571.93	15.00	556.93
OW-12B	571.85	24.00	547.85
OW-13B	571.68	18.04	553.64
OW-14B ⁽¹⁾	570.87	14.03	556.84
OW-15B ⁽¹⁾	569.78	12.75	557.03
OW-18B ⁽²⁾	576.05	NM	-
OW-22B ⁽¹⁾	570.90	14.03	556.87
OW-23B ⁽¹⁾	569.67	12.89	556.78
OW-24B ⁽¹⁾	570.36	13.52	556.84

TABLE 6.2 - GROUNDWATER ELEVATIONS
SOLVENT CHEMICAL, 3163 BUFFALO AVENUE, NIAGARA FALLS, NEW YORK
3RD QUARTER 2020


Monitoring Well No.	Reference Elevation (ft.)	9/15/2020 and 9/16/2020	
		DTW (ft)	Elevation (ft.)
OW-25B ⁽¹⁾	570.9	13.93	556.97
OW-26B	571.64	23.46	548.18
OW-27B	569.81	16.96	552.85
OW-28B	568.76	13.12	555.64
OW-29B	568.16	13.28	554.88
OW-30B	568.10	20.01	548.09
OW-31B ⁽¹⁾	570.14	13.01	557.13
OW-32B ⁽¹⁾	569.99	12.99	557.00
OW-33B ⁽¹⁾	569.55	12.56	556.99
PW-1B	572.34	14.87	557.47
PW-2B	571.60	18.50	553.10
PW-3B ⁽¹⁾	571.21	17.40	553.81
PW-4B ⁽¹⁾	569.72	15.41	554.31
PW-5B	572.74	19.53	553.21
PW-6B	573.95	25.73	548.22
PW-7B	571.15	16.90	554.25
PW-8B	572.36	25.25	547.11
C-Zone:			
MW-1C	572.53	16.06	556.47
MW-4C	571.42	28.10	543.32
MW-5C	572.75	25.29	547.46
MW-6C ⁽³⁾	573.60	26.11	547.49
CD-Zone:			
MW-1CD	572.78	16.20	556.58
MW-5CD	570.50	25.06	545.44
MW-6CD	573.45	19.65	553.80
F-Zone:			
MW-1F	572.40	14.05	558.35
MW-5F	572.78	17.05	555.73
MW-6F	573.52	16.87	556.65
Piezometers:			
PZ-01	572.46	DRY	DRY
PZ-02	572.14	DRY	DRY
PZ-03	571.95	11.15	560.80
PZ-04	572.03	DRY	DRY

Notes:

- 1) Monitoring wells within the Hot Spot were measured on 9/16/20.
- 2) OW-18B was not measured due to an obstruction in the well.
- 3) MW-6C is bailed monthly.

FIGURES

6.5x11 - USER: nra00000 - ATTACHED: 01/07/2020 - 1:19PM - LAYOUT: FIG 2 SOLVENT GW CONTOURS
DRAWING NAME: J:\Projects\21397 - Solvent Chemical Quarterly, Semi-Annual and Annual Reports\Periodic Review Report 2020\Figures\DWG\Fig 1 Site Location Map.dwg --- PLOT DATE: January 07, 2020 - 1:19PM --- LAYOUT: FIG 2 SOLVENT GW CONTOURS



QUADRANGLE
LOCATION

Base Map: USGS National Map

PROJECT:

**SOLVENT CHEMICAL
NIAGARA FALLS, NEW YORK**

TITLE:

**SITE LOCATION
MAP**

DRAWN BY: MAN

PROJ NO.: 105146

CHECKED BY: NS

APPROVED BY: MP

DATE: JANUARY 2020

FIGURE 1




650 Suffolk Street
Suite 200
Lowell, MA 01854
Phone: 978.970.5600

FILE NO.:



FIGURE 1

2024 - USER: BROWN - ATTACHED: REF: BASE SOLVENT2 - ATTACHED: IMAGES
DRAWING NAME: K:\Stephen Brown\CAD Solvent 2019\Fig2_GW_extraction.dwg -- PLOT DATE: March 28, 2019 - 3:28PM -- LAYOUT: Layout1



PROJECT: SOLVENT CHEMICAL NIAGARA FALLS, NEW YORK			
TITLE: GROUND WATER EXTRACTION SYSTEM LAYOUT			
DRAWN BY: MANJUL	PROJ. NO.: 105146	FIGURE 2	
CHECKED BY: SB			
APPROVED BY: MP			
DATE: MARCH 2019			
		650 Suffolk Street Suite 200 Lowell, MA 01854 Phone: 978.970.5600	
FILE NO:		Fig2_GW_extraction.dwg	



2204 - USER: C:\p06 - ATTACHED XREFS: - ATTACHED IMAGES
DRAWING NAME: J:\Projects\27397 - Solvent Chemical\Quarterly, Semi-Annual and Annual Reports\2020 Semi-Annual\1\Figures\CAD\Fig 1_AZONE_WATERLEVELS 2020 1st.dwg --- PLOT DATE: May 07, 2020 - 10:33AM --- LAYOUT: FIG 1



PROJECT:		SOLVENT CHEMICAL NIAGARA FALLS, NEW YORK	
TITLE:		OVERBURDEN WATER LEVELS SOLVENT SITE MARCH 17, 2020	
DRAWN BY:	CL	PROJ. NO.:	105146
CHECKED BY:	EG	FIGURE 3	
APPROVED BY:	MP		
DATE:	APRIL 2020		
FILE NO.:		Fig 1_AZONE_WATERLEVELS 2020 1st.dwg	


650 Suffolk Street
Suite 200
Lowell, MA 01854
Phone: 978.970.5600

22/24 -- USER: Nshreya -- ATTACHED REFS: -- ATTACHED IMAGES:
DRAWING NAME: \\JLOWELL-VFP\Environmental\Projects\27397 - Solvent Chemical\Quarterly, Semi-Annual and Annual Reports\2020 Semi-Annual 2\Figures\CAD\Fig 1_AZONE_WATERLEVELS 2020 2nd.dwg -- PLOT DATE: October 09, 2020 - 1:50PM -- LAYOUT: FIG 1




PROJECT: SOLVENT CHEMICAL NIAGARA FALLS, NEW YORK	
TITLE: OVERBURDEN WATER LEVELS SOLVENT SITE SEPTEMBER 15 & 16, 2020	
DRAWN BY: NS	PROJ. NO.: 105146
CHECKED BY: MP	FIGURE 4
APPROVED BY: MP	
DATE: SEPTEMBER 2020	
650 Suffolk Street Suite 200 Lowell, MA 01854 Phone: 978.970.5600	
FILE NO:	Fig 1_AZONE_WATERLEVELS 2020 2nd.dwg

FILE: H:\Projects\27397 - Solvent Chemical\Quarterly, Semi-Annual and Annual Reports\2020 Semi-Annual and Annual Reports\CAD\2020_H1_FIG 2&3.dwg



PROJECT:	
SOLVENT CHEMICAL NIAGARA FALLS, NEW YORK	
TITLE:	
MARCH GROUNDWATER CONTOURS SOLVENT SITE MARCH 17, 2020	
DRAWN BY:	MAN
PROJ NO.:	105146
CHECKED BY:	SB
APPROVED BY:	MP
DATE:	APRIL 2020
FIGURE 5	
	
650 Suffolk Street Suite 200 Lowell, MA 01854 Phone: 978.970.5600	
FILE NO.:	2019 H1 FIG 2&3.dwg



LEGEND:


556 GROUNDWATER ELEVATION CONTOUR

→ GROUNDWATER FLOW DIRECTION


-X- CHAIN LINK FENCE


PW,OW,MW SOLVENT PUMPING OR MONITORING WELL




NOTE: OW-1B OMITTED DUE TO ANOMALOUS DATA.













PROJECT:		SOLVENT CHEMICAL NIAGRA FALLS, NEW YORK	
TITLE:		SEPTEMBER GROUNDWATER CONTOURS SOLVENT SITE SEPTEMBER 15, 16, & 17, 2020	
DRAWN BY:	NGS	PROJ NO.:	105146
CHECKED BY:	MP	FIGURE 6	
APPROVED BY:	MP		
DATE:	SEPTEMBER 2020		
		650 Suffolk Street Suite 200 Lowell, MA 01854 Phone: 978.970.5600	
FILE NO.:		2020_H1_FIG 283.dwg	









NOTES

- CHARTS DEPICT THE TOTAL CONCENTRATION OF CONTAMINANTS OF CONCERN, PER THE DECEMBER 1996 ROD, AT EACH LOCATION VERSUS TIME.
- BASE MAP WAS PREPARED BY NIAGARA BOUNDARY DATED 8/30/01.

LEGEND


- MH G-2 ○ SITE STORM SEWER MANHOLE
MH ○ CITY UTILITY MANHOLE
OW-3A ○ OBSERVATION WELL
MW-4A ● MONITORING WELL
PW-3B ● PRODUCTION WELL/
TRENCH WELL
PZ-01 ● PIEZOMETER
■ CATCH BASIN
▨ A-ZONE INTERCEPTOR TRENCH
- x - FENCE
H GATE

0' 20' 40' 80'
SCALE: 1"=40'

PROJECT: SOLVENT CHEMICAL NIAGARA FALLS, NEW YORK	
TITLE: AUGUST 2004 - SEPTEMBER 2020 C, CD, AND F - ZONES TOTAL CONTAMINANTS OF CONCERN - SOLVENT SITE	
DRAWN BY: NS	PROJ. NO.: 105146
CHECKED BY: JH	FIGURE 11
APPROVED BY: MP	
DATE: FEBRUARY 2021	



650 Suffolk Street
Suite 200
Lowell, MA 01854
Phone: 978.970.5600




NOTES

1. CHARTS DEPICT THE TOTAL CONCENTRATION OF CONTAMINANTS OF CONCERN, PER THE DECEMBER 1996 ROD, AT EACH LOCATION VERSUS TIME.

2. BASE MAP WAS PREPARED BY NIAGARA BOUNDARY DATED 8/30/01.

- LEGEND
- OW-3A ○ OBSERVATION WELL
 - MW-4A ● MONITORING WELL
 - PW-3B ● PRODUCTION WELL/TRENCH WELL
 - OW-14B ● OLIN CHEMICAL MONITORING WELL
 - x — FENCE
 - H — GATE



PROJECT: SOLVENT CHEMICAL NIAGARA FALLS, NEW YORK	
TITLE: AUGUST 2004 - SEPTEMBER 2020 A AND B - ZONES TOTAL CONTAMINANTS OF CONCERN - HOT SPOT SITE	
DRAWN BY: NS	PROJ. NO.: 105146
CHECKED BY: JH	FIGURE 12
APPROVED BY: MP	
DATE: FEBRUARY 2021	
650 Suffolk Street Suite 200 Lowell, MA 01854 Phone: 978.970.5600	
FILE NO:	FIG 12 - Solvent HOTSPOT TRENDS 2020.dwg