

121 West 27th Street, 702 New York, NY 10001 (646) 606-2332

June 4, 2021

New York State Department of Environmental Conservation Division of Environmental Remediation, Remedial Bureau B 625 Broadway, 11th Floor Albany, NY 12233-7016

Attn: Steve Walsh, Environmental Engineer

Re: Remedial Schedule and Sub-Slab Depressurization System (SSDS) Modification BCP Site ID #C224267 3901-3913 8th Avenue – Brooklyn, NY

On behalf of Noris Realty Corp. (the Participant), Tenen Environmental, LLC (Tenen) is providing an updated remedial schedule and proposed modification to the sub-slab depressurization system (SSDS).

The existing tenant has been engaged to produce personal protective equipment (PPE) required for the COVID-19 response efforts of state and local governments. After consultation with the tenant, the Participant has confirmed that the entire 3901 8th Avenue building is required for the production of PPE.

Therefore, the Participant is proposing to install an SSDS (as modified in the attached drawings and described below) to depressurize the plenum beneath the entire building slab in June 2021 and to implement the tank removal / remedial excavation in May 2022. This strategy will mitigate the potential for vapor intrusion until full access to the site is returned to the Participant.

The SSDS has been modified to extend the pit and riser approach approved in the Interim Remedial Measures Work Plan (IRM Work Plan), as shown on attached Drawings X-100 through X-102. As currently conceived, the SSDS will depressurize the area of the proposed remedial excavation until the subject area is available for excavation. All requirements of Section 6.1, Sub-slab Depressurization System, of the IRM Work Plan will be implemented under the revised layout.

Drawing X-100 shows the sub-grade components of the SSDS, including two new pits on the western portion of the site, closer to 8th Avenue. Drawing X-101 shows the SSDS layout within the building including detailing how the risers from the pits are connected prior to being extended to the roof in two locations. Lastly, Drawing X-102 shows the revised roof layout with two fans.

When the remedial excavation is completed in May 2022, the western portion of the SSDS will be removed and re-installed according to the layout detailed in the IRM Work Plan.

This approach will allow for the continued safe operations of the Tenant during the production of PPE as well as for the remediation to begin at the site.

Sincerely Tenen Environmental LLC

Matthew Carroll, PE



121 West 27th Street, 702 New York, NY 10001 (646) 606-2332


Bradley Lubin / Noris Realty Corp. Scott Furman / Sive, Paget & Riesel, P.C. cc:


Attachments

- X-100 SSDS Below Grade LayoutX-101 SSDS First Floor LayoutX-102 SSDS Roof Layout



Base Mapping: NYC Department of City Planning, Information Technology Division AKRF, 3901 8th Ave., Soil Sample Concentrations Above UUSCOs and/or CP-51 SCOs





Base Mapping:

NYC Department of City Planning, Information Technology Division AKRF, 3901 8th Ave., Soil Sample Concentrations Above UUSCOs and/or CP-51 SCOs




Legend

-

• • •	Suction Pit Riser to Roof Riser from Suction Pit Pressure Monitoring Point Alarm	Drawn By LM	Checked By MC	Date April 2021	Scale As Noted
····	Alarm Cast Iron Pipe Connecting Suction Pits	-	iyout		
0	Project Site Boundary Feet 15 30 60	Drawing Title	SOUS FIRST FIOOF LAYOU	Drawing No	101-Y

Drawing Title	Drawn By LM	TENEN	Site
SSUS FIRST FIGOR LAYOUT	Checked By MC		3901 8th Avenue
Drawing No	^{Date} April 2021	121 West 27th Street	Block 916, Lot 5
101-2	^{Scale} As Noted	New York, NY 10001 O: (646) 606-2332 F: (646) 606-2379	



Base Mapping:

NYC Department of City Planning, Information Technology Division AKRF, 3901 8th Ave., Soil Sample Concentrations Above UUSCOs and/or CP-51 SCOs

