



# Interim Remedial Measures Work Plan Addendum

---

12 Franklin Street  
Brooklyn, New York 11222

July 24, 2024

Prepared for:

**Franklin Point LLC**  
**Franklin Point Holding LLC**  
175 Great Neck Road, Suite #407  
Great Neck, New York 11021

Prepared by:

**Roux Environmental Engineering  
and Geology, D.P.C.**  
209 Shafter Street  
Islandia, New York 11749

## Table of Contents

1. Introduction .....	1
1.1 Certification .....	2
2. IRMWP Addendum Scope of Work.....	3
2.1 Mobilization and Site Preparation for IRM Addendum Scope of Work.....	3
2.2 Implementation of SVE Monitoring Point Installation and Monitoring .....	3
2.3 Monthly Recovery of LNAPL from Monitoring Well MW14 .....	3
2.4 Slab Restoration .....	4
2.5 Elevator Pit Installation and Cellar Backfilling .....	4
2.6 Waste Disposal .....	5
2.7 Documentation .....	5
3. Reporting .....	6
3.1 Reporting During Site Activities .....	6
3.2 Construction Completion Report (CCR) .....	6
4. IRMWP Addendum Implementation Schedule .....	7

## Drawings

1. Sub-Slab Depressurization and Soil Vapor Extraction System Plan and Details

## Figures

1. Monitoring Well Location Map

## Appendices *(Provided on CD in Bound Copy)*

- A. Health and Safety Plan (HASP)
- B. Sub-Slab Depressurization System / Soil Vapor Extraction System Operations and Maintenance Forms
- C. Structural Drawings for Proposed Elevator Pit Construction and Backfilled Cellar
- D. GPC PREPRUFE® 300R Membrane and Drago® Wrap Data Sheets

# 1. Introduction

Roux Environmental Engineering and Geology, D.P.C. (Roux) has prepared this Interim Remedial Measures (IRM) Work Plan (IRMWP) Addendum on behalf of Franklin Point LLC / Franklin Point Holding LLC (referred to herein as the “Volunteer”) for the property located at 12 Franklin Street (Tax Block 2614, Lot 3) in the Greenpoint section of the Borough of Brooklyn in the City and State of New York (Site). The Site location map is provided as Figure 1. This IRMWP Addendum will be implemented in accordance with the New York State Department of Environmental Conservation (NYSDEC) Brownfield Cleanup Program (BCP), and the Brownfield Cleanup Agreement (BCA) dated March 28, 2019, and the associated BCA Amendment No. 1 dated September 21, 2023, which added the Volunteer to the BCA. The Volunteer has purchased the Site, and a second BCA Amendment was executed on January 8, 2024, to reflect this change of ownership. This IRMWP Addendum supplements the NYSDEC-approved IRMWP dated January 25, 2024.

As part of the interim use for the Site prior to redevelopment, the existing structures will be renovated for a commercial/industrial mixed-use (manufacturing/retail/office). While residential reuse possibilities may be contemplated in the future, they are not under consideration at this time. Any such consideration would be in tandem with future building demolition and additional remediation efforts. The building is currently unoccupied, and an interior build-out will occur prior to tenant occupancy.

As part of the initial IRMWP scope of work, which was approved by NYSDEC in a letter dated February 8, 2024, to allow for commercial/industrial tenant use of the building, an extensive sub-slab depressurization system (SSDS) was recently installed and is operating as designed.

This IRMWP Addendum is being proposed to meet the following objectives:

- 1) Upgrade the newly installed SSDS with additional monitoring points to demonstrate that the system is also operating as a soil vapor extraction system (SVES);
- 2) Passively recover light non-aqueous phase liquid (LNAPL) from monitoring well MW14;
- 3) Restore the slab to improve the efficacy of the SSDS; and
- 4) Install the elevator pit and backfill the cellar.

This IRMWP Addendum has been prepared in accordance with NYSDEC procedures set forth in the guidance document titled DER-10 Technical Guidance for Site Investigation and Remediation, dated May 2010 (DER-10), and the New York State Department of Health (NYSDOH) Vapor Guidance, dated October 2006 and updated February 2024 (NYSDOH Guidance), and complies with all applicable Federal, State and local laws, regulations and requirements. Additionally, all interior invasive work will be completed in accordance with the health and safety plan (HASP) provided as Appendix A. A Community Air Monitoring Plan (CAMP) is not required because all work will be performed inside the vacant building.

## 1.1 Certification

I, David Kaiser, P.E., certify that I am currently a registered professional engineer in the State of New York as defined in 6 NYCRR Part 375 and that this IRMWP Addendum was prepared in accordance with all applicable statutes and regulations and in substantial conformance with the DER-10.

I certify that all information and statements in this certification are true. I understand that a false statement made herein is punishable as a Class "A" misdemeanor, pursuant to Section 210.45 of the Penal Law.



David Kaiser, P.E.

July 24, 2024

NYS Professional Engineer # 097317

Date

Signature

It is a violation of Article 130 of New York State Education Law for any person to alter this document in any way without the express written verification of adoption by any New York State licensed engineer in accordance with Section 7209(2), Article 145, New York State Education Law.

## 2. IRMWP Addendum Scope of Work

The scope of work for the IRMWP Addendum consists of the following tasks:

1. Mobilization and Site Preparation for IRM Addendum Scope of Work;
2. Implementation of SVE Monitoring Point Installation and Monitoring;
3. Monthly Recovery of LNAPL from Monitoring Well MW14;
4. Slab Restoration;
5. Elevator Pit Installation and Cellar Backfilling;
6. Waste Disposal (assumed to be minimal); and
7. Documentation.

### 2.1 Mobilization and Site Preparation for IRM Addendum Scope of Work

A seven-day notice will be provided prior to conducting a project kick-off call or meeting involving NYSDEC, the Volunteer, Roux, and the selected Contractor, if requested by NYSDEC. This meeting will precede the initiation of any ground-intrusive activities related to the IRM described in this IRMWP. The Contractor will be responsible for supplying the necessary labor (HAZWOPER Certified in accordance with OSHA 1910.120) and materials to execute the scope of work for the IRM. Additionally, all required permits, insurance, bonds, and licenses necessary for the completion of the work will be obtained, and associated fees will be paid. Mobilization and Site preparation activities will involve mobilization of equipment to the work area, conducting a geophysical survey to identify underground obstructions and utilities, and establishing work area delineation zones.

### 2.2 Implementation of SVE Monitoring Point Installation and Monitoring

Five SVES monitoring points (SVE-1 through SVE-5) will be installed to allow for the monitoring of the vertical influence exerted by the SSDS/SVES around each extraction point. These monitoring points will be installed to a depth approximately six inches above the observed groundwater table, adhering to the specification shown in Drawing 1. All work will be performed in conformance with the Soil/Materials Management Plan provided in the IRMWP.

Following the monitoring point installation, the SSDS/SVES will be restarted and balanced to maximize the depth of influence and contaminant extraction rate while preventing the ingress of groundwater into the SSDS/SVES. The points will be monitored for vacuum/pressure using the Sub-Slab Depressurization System/Soil Vapor Extraction System Operations and Maintenance Form provided as Appendix B.

### 2.3 Monthly Recovery of LNAPL from Monitoring Well MW14

During the removal of the UST at former lot 8 (8 Meserole Avenue), LNAPL was observed on top of the groundwater within the excavation along with odorous and stained soils. Petroleum impacts were observed throughout the UST grave. In response, Roux prepared a Supplemental Remedial Investigation Work Plan (SRIWP) Addendum to delineate the observed LNAPL. This SRIWP Addendum was approved by NYSDEC, and the investigation work was performed on May 1 and 2, 2024. Three monitoring wells were installed around the former UST grave to monitor for LNAPL (Figure 1). On May 10, 2024, Roux gauged the three monitoring wells around the former tank grave, and one of the monitoring wells, MW14, had a minor accumulation of measurable LNAPL (0.1 feet of LNAPL). Since LNAPL was detected, monitoring well MW14

was not sampled. However, groundwater from the other two monitoring wells, MW12 and MW13, was sampled as no measurable LNAPL was detected in those wells.

As part of this scope, manual LNAPL recovery will occur on a monthly basis within monitoring well MW14 at the Site. The manual recovery will be performed using absorbent “socks” and/or bailers. During each monthly gauging and manual recovery event, the three wells around the UST grave will be gauged to measure LNAPL thickness and depth to water. The absorbent “sock” will be changed out in MW14 during each monthly event. Spent absorbent “socks” and used bailers will be stored in properly labeled, 55-gallon steel drums to await subsequent off-site disposal.

## **2.4 Slab Restoration**

Following the installation of the SSDS/SVE system components, the areas of the slab that were removed for the removal of the USTs will be repaired to match the surrounding conditions. Additionally, the remaining slab within the buildings will be inspected for potential weaknesses, such as cracks, joints, and penetrations. Any accessible weaknesses that could affect sub-slab depressurization will be sealed with caulk or equivalent material. Larger penetrations will be filled with concrete to match the surrounding conditions. Openings or cracks at the floor-wall joint will be sealed with caulk. For openings or channels wider than 0.50 inches, a foam backer rod or comparable filler material will be inserted before applying the caulk.

## **2.5 Elevator Pit Installation and Cellar Backfilling**

As part of the building's rehabilitation, an elevator pit will be constructed to accommodate a machine room-less elevator. The excavation for the pit will extend about 5 feet below the existing slab, requiring the excavation of approximately 12 cubic yards of soil for offsite disposal. The excavated soil will be staged on protective sheeting and covered with additional protective sheeting at the end of each day or upon completion of excavation activities if the work is completed in less than one day. All handling of soil, groundwater, and other materials will be performed in accordance with the Soil/Materials Management Plan included in the NYSDEC-approved IRM Work Plan, dated January 25, 2024. No import of backfill is anticipated for the elevator pit construction.

The structural drawings for the elevator pit construction are provided in Appendix C. A GCP PREPRUFE® 300R pre-applied 46 mil waterproofing membrane will be applied around the exterior of the elevator pit according to the manufacturer's specifications, serving as both waterproofing and a vapor barrier. The product data sheet is provided as Appendix D. A 12-inch-thick concrete slab will be poured to form the bottom and the walls of the elevator pit.

Additionally, the cellar will be backfilled as part of the construction according to the drawings in Appendix C. Once backfilled, a Drago Wrap 20 mil vapor barrier membrane will be placed over the backfilled material and sealed to the existing cellar walls according to the manufacturer's specifications. The product data sheet is provided in Appendix D. A 5-inch-thick concrete slab will be poured over the vapor barrier once it is installed.

After these renovations are complete, the SSDS/SVE monitoring points will be monitored for vacuum/pressure using the Sub-Slab Depressurization System/Soil Vapor Extraction System Operations and Maintenance Form provided as Appendix B to demonstrate that the SSDS is still providing a sufficient vacuum under the slabs.

## **2.6 Waste Disposal**

All wastes generated during the installation of the SVE monitoring points, LNAPL recovery, cellar backfilling, and elevator pit installation will be handled, transported and disposed of in a manner consistent with Federal, State and local laws and regulations.

## **2.7 Documentation**

Detailed information regarding the IRMWP Addendum scope of work described herein (e.g., as-built drawings for SVE monitoring point installation and slab restoration, waste disposal documentation, photographs, etc.) will be included in the CCR.

## 3. Reporting

### 3.1 Reporting During Site Activities

Daily reports to NYSDEC and NYSDOH will be submitted during the days when IRMWP Addendum activities take place. Daily reports will include an update of progress made during the reporting period; locations of work and quantities of material imported and exported from the Site; a summary of any and all complaints with relevant details (names, phone numbers); and an explanation of notable Site conditions, etc. If any issues arise, NYSDOH and NYSDEC will be notified within 24 hours.

Monthly reports will be submitted to NYSDEC and NYSDOH Project Managers by the 10<sup>th</sup> of the month following the end of the month of the reporting period and will include:

- Activities relative to the Site during the previous reporting period and those anticipated for the next reporting period, including a quantitative presentation of work performed (i.e., tons of material exported and imported, etc.);
- Description of approved activity modifications, including changes of work scope and/or schedule;
- Sampling results received following internal data review and validation, as applicable; and
- An update of the remedial schedule including the percentage of project completion, unresolved delays encountered or anticipated that may affect the future schedule, and efforts made to mitigate such delays.

### 3.2 Construction Completion Report (CCR)

Detailed information regarding the IRMWP activities (e.g., general description of the construction activities, as-built of the SSDS/SVES with the new SVE monitoring points, waste disposal documentation, sample analysis results, vapor barrier documentation, photographs, etc.) will be included in the CCR.



## 4. IRMWP Addendum Implementation Schedule

This IRMWP Addendum scope of work is anticipated to begin in June through August 2024. It is anticipated that the actual on-Site duration of major remedial construction tasks will be completed as follows (time frames are not necessarily consecutive):


- SVE Monitoring Point Installation and Start-Up Monitoring ..... two days
- Monthly Recovery of LNAPL in Monitoring Well MW14 ..... ongoing on a monthly basis
- Slab Preparation ..... August through October 2024
- Elevator Pit Installation and Cellar Backfilling ..... August through October 2024
- Transportation and Off-Site Disposal ..... one day
- Submittal of CCR After Completion of IRMWP Addendum Scope of Work ..... December 2024

**Interim Remedial Measures Work Plan Addendum**  
***12 Franklin Street, Brooklyn, New York 11222***

---

**DRAWINGS**


1. Sub-Slab Depressurization and Soil Vapor Extraction System Plan and Details




**SUB-SLAB DEPRESSURIZATION SYSTEM/SOIL VAPOR EXTRACTION SYSTEM PLAN**  
SCALE: 1" = 20'

**SUB-SLAB DEPRESSURIZATION SYSTEM/SOIL VAPOR EXTRACTION SYSTEM NOTES**


- CONTRACTOR SHALL COORDINATE INSTALLATION OF SUB-SLAB DEPRESSURIZATION SYSTEM/SOIL VAPOR EXTRACTION SYSTEM (SSDS/SVES) WITH THE FOUNDATION, PLUMBING, MECHANICAL AND ELECTRICAL CONTRACTORS.
- CONTRACTOR SHALL COORDINATE WITH PLUMBING, MECHANICAL, CIVIL AND ELECTRICAL CONTRACTORS FOR ALL UTILITY CROSSINGS.
- CONTRACTOR SHALL FIELD VERIFY THE DESIGN INVERT ELEVATIONS (BOTTOM OF PIPING) FOR PENETRATIONS. THE CONTRACTOR SHALL ALSO FIELD VERIFY THE HORIZONTAL OFFSETS FOR THE LOCATIONS OF THE VERTICAL RISERS.
- ALL SSDS/SVES PIPING SHALL BE SLOPED TOWARDS THE PERFORATED PIPE SUCTION PITS TO PREVENT ANY POTENTIAL MOISTURE BUILD UP AND BLOCKAGES.
- ALL ABOVE GRADE SSDS/SVES PIPING (ALONG WITH FITTINGS AND APPURTENANCES) SHALL CONSIST OF GALVANIZED STEEL, CAST-IRON, OR DUCTILE IRON PIPE AND INSTALLED IN ACCORDANCE WITH THE NYC PLUMBING CODE CHAPTERS 7 AND 9 FOR VENT PIPE.
- PVC PIPE SHALL BE JOINED TOGETHER USING EITHER SOLVENTS, SLIP-JOINTS SECURED WITH SELF-TAPPING SCREWS OR THREADED CONNECTIONS.
- ALL PENETRATIONS THROUGH THE FLOOR SHALL BE SEALED USING A SILICONE BASED WATERPROOF SEALANT OR EQUIVALENT.
- EACH SSDS/SVES PIT SECTION (TENANT A, B/C, D AND E) SHALL BE INSTALLED WITH A RADONAWAY HS5500 IN-LINE FAN (QTY - 4), EACH SSDS/SVES PIT RISER PIPE SHALL BE INSTALLED WITH A VALVE AND RADONAWAY RSA1 VACUUM INDICATOR ALARM (QTY - 12).
- THE SURFACES TO BE LINED WITH GEOTEXTILE SHALL BE FREE OF ALL ROCKS, STONES, SHARP OBJECTS OR CONSTRUCTION DEBRIS OF ANY KIND.
- INSTALL GEOTEXTILE NONWOVEN FABRIC DIRECTLY ON FILL. MATERIAL OVERLAPS SHALL BE A MINIMUM OF 12" AND THE OVERLAPPED SEAMS WILL BE SEALED WITH TAPE.
- NON-WOVEN GEOTEXTILE SHALL MEET OR EXCEED FOLLOWING PROPERTY VALUES:
  - MINIMUM MASS PER UNIT AREA OF 10 OZ/YD<sup>2</sup> AS PER ASTM D 5261
  - MINIMUM GRAB STRENGTH OF 250 LBS AS PER ASTM D 4632
  - MINIMUM PUNCTURE STRENGTH OF 700 LBS AS PER ASTM D 6241
  - MINIMUM ULTRAVIOLET RESISTANCE @ 500 HOURS OF 70% AS PER ASTM D 4355




**PLAN VIEW**




**PROFILE VIEW A-A'**




**4 RISER DETAIL**  
SCALE: N.T.S.



**1 SSDS MONITORING POINT DETAIL**  
SCALE: N.T.S.




**2 SVES MONITORING POINT DETAIL**  
SCALE: N.T.S.



**3 SSDS/SVES SUCTION PIT DETAIL**  
SCALE: N.T.S.

V:\CAD\PROJECTS\4170\0001101\01-REV 2.DWG DWASER

NO.	DATE	REVISION DESCRIPTION	INT.
2	4/23/24	REVISE SSDS/SVES PIT LOCATIONS AND MONITORING POINTS	D.E.K.
1	1/19/24	REVISE SSDS PIT LOCATIONS, PIPING AND IN-LINE FANS	D.E.K.



UNAUTHORIZED ALTERATION OR ADDITION TO THIS DOCUMENT IS A VIOLATION OF STATE LAW.  
THESE DOCUMENTS (OR COPIES OF ANY THEREOF) PREPARED BY OR BEARING THE SEAL OF THE ENGINEER, SHALL NOT BE REUSED FOR ANY EXTENSIONS OF THE PROJECT OR ANY OTHER PROJECT WITHOUT THE WRITTEN CONSENT OF THE ENGINEER.

PROJ. ENGINEER: D.E.K.	DRAWN BY: D.E.K.
DESIGNED BY: D.E.K.	CHECKED BY: R.H.
DRAWING SCALE: AS SHOWN	PLOT SCALE: 1:1
DRAWING DATE: 5/16/2024	PRINT TYPE: COLOR
OFFICE: NY	PAPER SIZE: ARCH D
PROJECT NO.: 4170.0001Y000	
DRAWING FILE: 4170.0001Y101.01-REV 2.DWG	

**ROUX**  
Roux Environmental  
Engineering and Geology, D.P.C.  
209 SHAFTER STREET ISLANDIA NEW YORK 11749  
(631) 232-2600

PROJECT NAME:  
**12 FRANKLIN STREET  
BROOKLYN, NEW YORK 11222**  
PROJECT FOR:  
**FRANKLIN POINT LLC**

TITLE:  
**SUB-SLAB DEPRESSURIZATION  
AND SOIL VAPOR EXTRACTION  
SYSTEM PLAN AND DETAILS**

DRAWING NO.  
**1**  
DRAWING  
1 OF 1


**Interim Remedial Measures Work Plan Addendum**  
***12 Franklin Street, Brooklyn, New York 11222***

---

**FIGURES**



1. Monitoring Well Location Map

V:\CAD\PROJECTS\4170Y0001Y1154170.0001Y115.03.DWG GMILTON



**LEGEND**

- SITE BOUNDARY
- + MONITORING WELL LOCATION



Title:			
<b>MONITORING WELL LOCATION MAP</b>			
12 FRANKLIN STREET BROOKLYN, NEW YORK 11222			
Prepared for:			
<b>FRANKLIN POINT HOLDING LLC</b>			
<b>ROUX</b>	Compiled by: R.H.	Date: 5/15/2024	FIGURE <b>1</b>
	Prepared by: G.M.	Scale: AS SHOWN	
	Project Mgr: R.H.	Project: 4170.0001Y000	
	File: 4170.0001Y115.03.DWG		

**Interim Remedial Measures Work Plan Addendum**  
**12 Franklin Street, Brooklyn, New York 11222**

---

**APPENDICES**

- A. Health and Safety Plan (HASP)
- B. Sub-Slab Depressurization System / Soil Vapor Extraction System Operations and Maintenance Forms
- C. Structural Drawings for Elevator Pit Construction and Backfilled Cellar
- D. GPC PREPRUFE® 300R Membranes and Drago® Wrap Data Sheets

**Interim Remedial Measures Work Plan Addendum**  
***12 Franklin Street, Brooklyn, New York 11222***

---

**APPENDIX A**

Health and Safety Plan (HASP)



# Site-specific Health and Safety Plan

---

12 Franklin Street  
Brooklyn, New York 11222

January 25, 2024

Prepared for:

**Franklin Point LLC**  
**Franklin Point Holding LLC**  
175 Great Neck Road, Suite #407  
Great Neck, New York 11021

Prepared by:

**Roux Environmental Engineering  
and Geology, D.P.C.**  
209 Shafter Street  
Islandia, New York 11749



# Table of Contents

Site-Specific Emergency Information .....	1
Emergency Phone Numbers .....	1
1. Introduction .....	3
1.1 Roles and Responsibilities .....	3
2. Background .....	6
2.1 Site Description .....	6
2.2 Site History .....	6
2.3 Known and Potential Releases of Hazardous Substances at the Site .....	6
3. Scope of Work .....	7
4. Site Control .....	8
4.1 Site Map .....	8
4.2 Site Access .....	8
4.3 Buddy System .....	8
4.4 Site Communications .....	8
4.5 Site Work Zones .....	9
5. Job Hazard Evaluation .....	11
5.1 Hazard Communication and Overall Site Information Program .....	11
6. Emergency Response Plan .....	13
6.1 Emergency Response .....	13
6.2 Emergency Alerting and Evacuation .....	13
6.3 Emergency Medical Treatment and First Aid .....	13
6.4 Adverse Weather Conditions .....	14
6.5 Electrical Storm Guidelines .....	15
7. Safety Procedures .....	16
7.1 Training .....	16
7.2 Site-Specific Safety Briefings for Visitors .....	16
7.3 HASP Information and Site-Specific Briefings for Workers .....	16
7.4 Medical Surveillance .....	16
7.4.1 Site Medical Surveillance Program .....	17
7.4.2 Medical Recordkeeping Procedures .....	17
7.4.3 Program Review .....	17
7.5 Personnel Protection .....	18
7.5.1 Hearing Conservation .....	18
7.6 Monitoring .....	19
7.6.1 Action Levels for Air Monitoring .....	19
7.6.2 Air Monitoring Equipment and Calibration .....	21
7.7 Tailgate Safety Meetings .....	21
7.8 Spill Containment .....	22
7.8.1 Initial Spill Notification and Response .....	22
7.8.2 Spill Evaluation and Response .....	22

## Table of Contents (Continued)

7.9 Decontamination.....	22
7.9.1 Decontamination Procedures for Personnel and PPE.....	22
7.9.2 Decontamination Procedures for Equipment.....	23
7.9.3 Monitoring the Effectiveness of Decontamination Procedures.....	23
7.10 Confined Space Entry.....	24
7.11 Client and Site-Specific.....	24
7.12 Unusual or Significant Risks.....	24
7.13 Activity-Specific.....	25
7.13.1 Electrical and Other Utility Assessment and Accommodations.....	25
7.13.2 Subsurface Work.....	25
7.13.2.1 Excavations and Trenching.....	25
7.13.3 Heavy Equipment.....	26
7.14 Heat Stress.....	26
7.14.1 Heat Stress.....	27
7.14.2 Heat Exhaustion.....	27
7.14.3 Heat Stroke.....	27
7.15 Cold Stress.....	28
8. Field Team Review.....	29
9. Approvals.....	30

## Table

1. Toxicological Properties of Hazardous Substances Present at the Site

## Figures

1. Site Location Map
2. Site Plan with Emergency Muster Area
3. Routes to Urgent Care and Hospital

## Appendices

- A. Job Safety Analysis (JSA) Forms
- B. Safety Data Sheets SDSs for Chemicals Used
- C. Personal Protective Equipment (PPE) Management Program
- D. Subsurface Utility Clearance Management Program
- E. Heavy Equipment Exclusion Zone Policy

# Site-Specific Emergency Information

## Emergency Phone Numbers

Most emergency services can be obtained by calling **911**. Where 911 service is not available, use the telephone numbers provided in the below table. The following is a master emergency phone list for use by the project management personnel. A more condensed version of the emergency numbers listed below will be posted throughout project work areas. Emergencies encountered on the site will be responded to by a combination of off-site emergency services and site personnel.

Emergency Contact Information			
Site Personnel			
Title	Contact	Telephone	
Project Manager (PM)	Rachel Henke	(631) 630-2334	
Project Principal (PP)	Robert Kovacs	(631) 630-2320	
Site Supervisor (SS)	TBD		
Site Health and Site Safety Officer (SHSO)	TBD		
Office Health and Safety Manager (OHSM)	Nevin Pahlad	631-630-2426	
Corporate Health and Safety Manager (CHSM)	Brian Hobbs	(631) 630-2419	
Client Emergency Contact	TBD		
Outside Assistance			
Agency	Contact	Telephone	Address/Location
Ambulance/emergency medical services (EMS)	FDNY EMS Station 35	(718) 384-7039 / 911	332 Metropolitan Avenue Brooklyn, NY 11211
Police	94 <sup>th</sup> Precinct	(718) 383-3879 / 911	100 Meserole Avenue Brooklyn, NY 11222
Fire	New York City Fire Department	(718) 965 8229 / 911	75 Richardson Street Brooklyn, NY 11211
Site Address	12 Franklin Street, Brooklyn, NY 11222		

### Route to NYU Medical Center:

403 E 34<sup>th</sup> Street, New York, NY

- Head north on Franklin Street toward Meserole Avenue
- Turn right onto Cayler Street
- Continue on McGuinness Boulevard over Pulaski Bridge
- Take Queens Midtown tunnel to E 35<sup>th</sup> Street in Manhattan
- Take the exit toward downtown from I-495W
- Drive to E 34<sup>th</sup> Street

**Route to CityMD Greenpoint Urgent Care:**

795 Manhattan Ave, Brooklyn, New York

- Head north on Franklin Street toward Meserole Avenue
- Turn right onto Cayler Street
- Turn right onto Manhattan Avenue

# 1. Introduction

This Site-specific Health and Safety Plan (HASP) has been prepared by Roux Environmental Engineering and Geology, D.P.C. (Roux) for use during the implementation of the Interim Remedial Measure Work Plan (IRMWP) and the Supplemental Remedial Investigation Work Plan (SRIWP) at the 12 Franklin Street site (“the Site”), located at 12 Franklin Street, Brooklyn, NY 11222 (see **Figure 1**). These activities fall within the scope of operations covered by the Occupational Safety and Health Administration (OSHA) standards promulgated at 29 CFR 1910.120 and 29 CFR 1926.65, both commonly referred to as the Hazardous Waste Operations and Emergency Response (HAZWOPER) Standard. In accordance with the HAZWOPER Standard, this Site-specific HASP was prepared to address the safety and health hazards associated with the oversight being performed at the Site by Roux and to provide requirements and procedures for the protection of Roux employees, subcontractor personnel, government oversight personnel, Site personnel, and the general public. It also addresses client- and Site-specific requirements for health and safety.

Implementation of this HASP is the joint responsibility of the Project Manager (PM), the Site Health and Safety Officer (SHSO), and all field staff, with assistance from the Project Principal (PP), Office Health and Safety Manager (OHSM), and Corporate Health and Safety Manager (CHSM). The PM for this project is Rachel Henke. The Site Supervisor (SS) and Site Health and Safety Officer (SHSO) will be determined with the onset of field work.

This HASP will be introduced to, reviewed, and signed off on by all Roux personnel through a formal training session prior to commencing work. A copy of the HASP will be kept at the Site at all times. The Roux SHSO or PM will be responsible for posting any changes, amendments, memos, etc. to the HASP. Any revisions to this HASP will be signed by appropriate personnel, which can include Roux’s PP, CHSM, and SS. Any changes will be announced to all workers at the next safety meeting.

## 1.1 Roles and Responsibilities

Overall Roles and Responsibilities (R&Rs) of Roux personnel are provided in Roux’s Policies and Procedures Manual. Only those R&Rs specific to HASP requirements are listed below.

### Project Manager (PM)

The PM has responsibility and authority to direct all work operations. The PM coordinates safety and health functions with the Site Health and Safety Officer (SHSO), has the authority to oversee and monitor the performance of the SHSO, and bears ultimate responsibility for the proper implementation of this HASP. The specific duties of the PM are:

- preparing and coordinating the Site work plan;
- providing Site supervisor(s) with work assignments and overseeing their performance; Coordinating safety and health efforts with the SHSO;
- ensuring effective emergency response through coordination with the Emergency Response Coordinator (ERC); and
- serving as primary Site liaison with public agencies and officials and Site contractors.

### **Site Health and Safety Officer (SHSO)**

The SHSO has full responsibility and authority to develop and implement this HASP and to verify compliance. The SHSO reports to the Project Manager. The SHSO is on Site or readily accessible to the Site during all work operations and has the authority to halt Site work if unsafe conditions are detected. The specific responsibilities of the SHSO include:

- managing the safety and health functions on this Site;
- serving as the Site's point of contact for safety and health matters;
- ensuring Site monitoring, worker training, and effective selection and use of PPE;
- assessing Site conditions for unsafe acts and conditions and providing corrective action;
- assisting the preparation and review of this HASP;
- maintaining effective safety and health records as described in this HASP; and
- coordinating with the Site Supervisor(s) and others as necessary for safety and health efforts.

### **Site Supervisor**

The Site Supervisor is responsible for field operations and reports to the Project Manager (PM). The Site Supervisor ensures the implementation of the HASP requirements and procedures in the field. The specific responsibilities of the Site Supervisor include:

- executing the work plan and schedule as detailed by the PM;
- coordination with the SHSO on safety and health; and
- ensuring Site work compliance with the requirements of this HASP.

### **Employees**

All Roux employees are responsible for reading and following all provisions of the Corporate Health and Safety Manual, including this HASP. Employees report to the SS at the project Site. Each employee is also responsible for the following:

- wearing all appropriate PPE as outlined within this HASP;
- attending all safety meetings;
- inspecting tools and equipment prior to use, and taking any defective tools or equipment out of service;
- appropriately documenting field events as they occur within a logbook or equivalent;
- properly operating machinery and/or equipment only if trained to do so;
- stopping work operations if unsafe conditions exist;
- identifying and mitigating hazards when observed;
- reporting all incidents and near misses to the Roux SHSO and SS immediately; and
- knowing where emergency equipment is located (e.g. first aid kit, fire extinguisher).

### **Subcontractors and Visitors**

Subcontractors and visitors are responsible for complying with the same health and safety requirements. It is the responsibility of all to make sure subcontractors and visitors comply and uphold the HASP. Subcontractors and visitors have the following additional responsibilities:

- designating a qualified safety representative for the project that can make the necessary changes in work practices, as necessary;
- attending all safety meetings while participating in Roux Site work activities;
- reporting all incidents and near misses to Roux SHSO and SS immediately;
- conducting initial and periodic equipment inspections in accordance with manufacturer and regulatory guidelines; and
- providing copies of all Safety Data Sheets (SDS) to Roux SHSO for materials brought to the Site.

## 2. Background

Relevant background information is provided below, including a general description of the Site; a brief review of the Site's history with respect to hazardous material use, handling, and/or storage; and a review of known and potential releases of hazardous substances at the Site.

### 2.1 Site Description

The Site is located on the east side of Franklin Street, between Meserole Avenue to the north and N 15<sup>th</sup> Street to the south, in the borough of Brooklyn, New York. The borough of Brooklyn is situated in the southeast portion of New York City. The vicinity of the Subject Property consists of commercial, industrial, warehouses and factories. The ground surfaces in the vicinity of the Site consist of asphalt and concrete. The Site is located in an urban setting, so it is important that all personnel on site are aware of hazards that may arise in a densely populated setting, such as traffic hazards.

The properties situated adjacent to the Site include the unidentified one-story warehouses/industrial facilities to the north, an adjoining unmarked warehouse/industrial facility to the south, a smoke fish processing facility to the east, and a one story warehouse and undeveloped land, beyond which is the Bushwick inlet to the west.

### 2.2 Site History

According to available sources, the Site was developed as the current one-story building by 1951. The Site was occupied by multiple commercial entities including Ace Cellophane & Polyethylene Corp, Polycraft, Synerjol Co, Hardchrome Electro Processing Corp, ACME Finishing Co Inc, and Linaire Corp from 1960 to 2017. Soil quality was generally impacted with SVOCs characterized as PAHs and metals with some detections for pesticides and VOCs. Minor detections of chlorinated solvents were detected in soil suggesting a source may be present. Groundwater was generally impacted with both petroleum related and chlorinated VOCs, SVOCs and metals at concentrations exceeding NYSDEC standards as well as 1,4-dioxane (max 17,200 µg/L) and total PFAS with a maximum concentration of 847 µg/L. Soil vapor was also significantly impacted with chlorinated solvents, with concentrations of total VOCs ranging up to a total of 780,000 µg/m<sup>3</sup>. These potential constituents should be considered when performing activities on site.

### 2.3 Known and Potential Releases of Hazardous Substances at the Site

The Site was identified to be associated with open NYSDEC SPILLS case #1806488 which occurred on September 17, 2018 which showed petroleum related VOCs and SVOCs in the soil and groundwater. The final memo indicated that the spill case would be remediated during the BCP remedial construction phase, and this spill case is still open.



### **3. Scope of Work**

In general, the scope of work includes the following tasks:

- Mobilizing to the Site and Site preparation.
- Installing the SSDS components.
- Starting the SSDS and confirming its performance.
- Test pitting to confirm the presence of suspected underground storage tanks (USTs).
- Removing suspected USTs and excavating contaminated soil as needed.
- Collecting endpoint samples around the removed USTs.
- Collecting soil samples for emerging contaminant sampling.
- Investigation of groundwater elevations.
- Managing waste, which is assumed to be minimal.

## 4. Site Control

This Site control program is designed to reduce the spread of hazardous substances from contaminated areas to clean areas, to identify and isolate contaminated areas of the Site, to facilitate emergency evacuation and medical care, to prevent unauthorized entry to the Site, and to deter vandalism and theft.

### 4.1 Site Map

A map of this Site, showing Site boundaries, designated work zones, and points of entry and exit is provided in **Figure 2**.

### 4.2 Site Access

Access to the Site is restricted to reduce the potential for exposure to its safety and health hazards. During hours of Site operation, Site entry and exit is authorized only at the points identified in **Figure 2**. Entry and exit at these points is controlled by the following: closed front door, construction warning signs. When the Site is not operating, access to the Site is controlled by the following: Locked door, security camera, and alarm system.

### 4.3 Buddy System

This section is not applicable for all components of the SOW described in Section 3.0. Some Site inspections and oversight activities are completed by a single Roux employee. However, when completing these tasks, the single Roux employee is accompanied either by Roux subcontractors or the Site caretaker/other representatives from Franklin Point LLC / Franklin Point Holding LLC. Any time Roux is on-site, Franklin Point LLC / Franklin Point Holding is made aware and communications with Franklin Point LLC / Franklin Point Holding LLC and the Roux PM is maintained via cellular phone.

While working in the Exclusion Zone, Site workers use the buddy system. The buddy system means that personnel work in pairs and stay in close visual contact to be able to observe one another and summon rapid assistance in case of an emergency. The responsibilities of workers using the buddy system include:

- Remaining in close visual contact with partner;
- Providing partner with assistance as needed or requested;
- Observing partner for signs of heat stress or other difficulties;
- Periodically checking the integrity of partner's PPE; and
- Notifying the Site manager or other Site personnel if emergency assistance is needed.

### 4.4 Site Communications

The following communication equipment is used to support on-site communication: cell phones and hand signals.

As applicable, hand signals will be used according to the following:

### Hand Signals

SIGNAL	MEANING
Hand gripping throat	Out of air, can't breathe
Grip partner's wrist	Leave area immediately
Hands on top of head	Need assistance
Thumbs up	I'm alright, okay
Thumbs down	No, negative

A current list of emergency contact numbers is presented on Page 1 of this HASP.

## 4.5 Site Work Zones

The SOW does not require the implementation of work zones; however, should the need arise, this section provides details for the proper execution of work zones at this Site.

This Site is divided into three (3) major zones, described below. These zones are characterized by the presence or absence of biological, chemical, or physical hazards and the activities performed within them. Zone boundaries are clearly marked at all times and the flow of personnel among the zones is controlled. The Site is monitored for changing conditions that may warrant adjustment of zone boundaries. Zone boundaries are adjusted as necessary to protect personnel and clean areas. Whenever boundaries are adjusted, zone markings are also changed and workers are immediately notified of the change.

### Exclusion Zone

The area where contamination exists is the Exclusion Zone (EZ). All areas where excavation and handling of contaminated materials take place are considered the EZ. This zone will be delineated by orange high visibility fencing. Safety tape may be used as a secondary delineation within the EZ. The zone delineation markings may be opened in areas for varying lengths of time to accommodate equipment operation or specific construction activities. The SHSO may establish more than one EZ where different levels of protection may be employed or where different hazards exist. Personnel are not allowed in the EZ without:

- A buddy (co-worker)
- Required minimum level PPE
- Medical Authorization
- Training certification
- Requirement to be in the zone

### **Contamination Reduction Zone**

A Contamination Reduction Zone (CRZ) is established between the exclusion zone and the support zone. The CRZ contains the Contamination Reduction Corridor (CRC) and provides an area for decontamination of personnel and equipment. The CRZ will be used for general Site entry and egress in addition to access for heavy equipment and emergency support services. Personnel are not allowed in the CRZ without:

- A buddy (co-worker)
- Appropriate PPE
- Medical authorization
- Training certification
- Requirement to be in the zone

### **Support Zone**

The Support Zone (SZ) is an uncontaminated area that will be the field support area for the Site operations. The SZ will provide for field team communications and staging for emergency response. Appropriate sanitary facilities and safety equipment will be located in this zone. Potentially contaminated personnel or materials are not allowed in this zone. The only exception will be appropriately packaged/decontaminated and labeled samples.

## 5. Job Hazard Evaluation

Roux's work at the Site is expected to entail a variety of physical, chemical, and biological hazards, all of which must be sufficiently managed to allow the work to be performed safely. Some of the hazards are Site-specific, i.e., they are associated with the nature, physical characteristics, and/or routine operation of the Site itself, while others are activity-specific, i.e., they are associated with (or arise from) the particular activity being performed. The various hazards can be grouped into the following categories:

**Caught/Crushed** – the potential to become caught in, under, between, or by an object or parts of an object, such as equipment with parts that open and close or move up and down (“pinch points”) or equipment that rotates, and the accompanying potential to have body parts cut, mangled, or crushed thereby.

**Contact** – the potential to be struck by or against moving or stationary objects that can cause physical injury, such as heavy machinery, overhead piping, moving vehicles, falling objects, and equipment (including tools and hand-held equipment) or infrastructure with the ability to cut or impale.

**Energy Sources** – the potential for bodily harm associated with energy sources, most notably electricity, but also including latent energy sources such as compressed air and equipment under tension (which when released could cause injurious contact or a fall).

**Ergonomics** – the potential for musculoskeletal injury associated with lifting/carrying, pushing/pulling, bending, reaching, and other physical activity attributable to poor body position/mechanics, repetitive motion, and/or vibration.

**Exposure** – the potential for injury/illness due to physical, chemical, or biological exposures in the work environment, including but not limited to temperature extremes, solar radiation, and noise (physical), chemical splashes and hazardous atmospheres (chemical), and animal/insect bites and poisonous plants (biological).

**Falls** – the potential to slip or trip and thus fall or drop a load, resulting in bodily injury to oneself or others.

The foregoing is intended to provide Roux employees with a general awareness of the hazards involved with Site work. A more detailed review of the potential hazards associated with each specific activity planned for the Site (or ongoing activity, as the case may be) is provided in the activity-specific Job Safety Analysis (JSA) forms in **Appendix A**. As can be seen in the JSA forms, the hazards are identified by category per the above, and specific measures designed to mitigate/manage those hazards are also identified. In preparing the JSA forms, all categories of hazards were considered, and all anticipated potential hazards were identified to the extent possible based on the experience of the personnel preparing and reviewing the JSA forms. However, there is always the possibility for an unanticipated hazard to arise, potentially as condition change over the course of the workday. Roux personnel must maintain a continual awareness of potential hazards in the work zone, regardless of whether the hazard is identified in the JSA form. Particular attention should be paid to hazards associated with exposure to hazardous substances (see Table 1 for a listing of the hazardous substances most likely to be encountered in environmental media at the Site) and to Site personnel being located “in the line of fire” with respect to moving equipment, pinch points, and latent energy, e.g., being located or having body parts located within the swing radius of an excavator, between two sections of pipe being connected, below a piece of suspended equipment, or adjacent to a compressed air line.

### 5.1 Hazard Communication and Overall Site Information Program

The information in the JSAs and safety data sheets is made available to all employees and subcontractors who could be affected by it prior to the time they begin their work activities. Modifications to JSAs are communicated during routine pre-work briefings.

The information in the JSAs and Safety Data Sheets (SDSs) is made available to all employees and subcontractors who could be affected by an exposure to the hazards covered in them prior to the time they begin their work activities. Modifications to JSAs are communicated during routine pre-work briefings, and periodically updated as needed in the HASP. SDSs will be maintained by the SHSO/SS for new chemicals brought on-site as needed. Copies of SDSs can be found in **Appendix B**.

## 6. Emergency Response Plan

This emergency response plan details actions to be taken in the event of Site emergencies. The PM and SHSO is responsible for the implementation of emergency response procedures onsite. The SHSO/PM provides specific direction for emergency action based upon information available regarding the incident and response capabilities and initiates emergency procedures and notification of appropriate authorities. In the event of an emergency, Site personnel are evacuated and do not participate in emergency response activities, response is facilitated through external emergency services.

### 6.1 Emergency Response

The SHSO, after investigating the incident and relevant information, shall determine the level of response required for containment, rescue and medical care. Limited on-site emergency response activities could occur therefore the SHSO is responsible for notifying external emergency response agencies. The SHSO provides relevant information to the responding organizations, including but not limited to the hazards associated with the emergency incident, potential containment problems, and missing Site personnel.

### 6.2 Emergency Alerting and Evacuation

If evacuation notice is given, Site workers leave the worksite, if possible, by way of the nearest exit. Appropriate primary and alternate evacuation routes and assembly areas have been identified and are shown on the Site Plan with Emergency Muster Area **Figure 2**. The routes and assembly area will be determined by conditions at the time of the evacuation based on wind direction, the location of the hazard source, and other factors as determined by SHSO/PM.

Personnel exiting the Site gather at a designated assembly point. To determine that everyone has successfully exited the Site, personnel will be accounted for at the assembly Site. If any worker cannot be accounted for, notification is given to so that appropriate action can be initiated. Subcontractors on this Site have coordinated their emergency response plans to ensure that these plans are compatible and potential emergencies are recognized, alarm systems are clearly understood, and evacuation routes are accessible to all personnel relying upon them.

### 6.3 Emergency Medical Treatment and First Aid


In the event of a work-related injury or illness, employees are required to follow the procedures outlined below. All work-place injury and illness situations require Roux's Project and Corporate Management Team to be notified when an injury/illness incident occurs, and communication with the contracted Occupational Health Care Management Provider, AllOne Health (AOH), is initiated. The Injury/Illness Notification Flowchart is provided below and within Roux's Incident Investigation and Reporting program included within Roux's Corporate Health and Safety Manual.

If on-site personnel require any medical treatment, the following steps will be taken:

- a. Notify Roux's Project and Corporate Management Team for any work-related injury and/or illness occurrence, and communicate with the contracted Occupational Health Care Management Provider, AOH, immediately following the notifications provided above.
- b. Based on discussions with the Project Team, Corporate Management and the AOH evaluation, if medical attention beyond onsite First Aid is warranted, transport the injured / ill person (IP) to the Urgent Care Center, or notify the Fire Department or Ambulance Emergency service and request an

ambulance or transport the victim to the hospital, and continue communications with Corporate Management Team. An Urgent Care/Hospital Route map with location to NYU Medical Center is included as **Figure 3**.

- c. Decontaminate to the extent possible prior to administration of first aid or movement to medical or emergency facilities.
- d. First aid medical support will be provided by onsite personnel trained and certified in First Aid, Cardio Pulmonary Resuscitation (CPR), Automatic External Defibrillation (AED), and Blood-Borne Pathogens (BBP) Awareness, until relieved by emergency medical services (EMS).
- e. The SHSO and Project Manager will perform a Loss Investigation (LI) and the Project Team will complete the final Loss Report. If a Roux employee is involved in a vehicular incident, the employee must also complete the Acord Automobile Loss Notice.



## 6.4 Adverse Weather Conditions

In the event of adverse weather conditions, the SHSO or project principal will determine if work can continue without sacrificing the health and safety of all field workers. Some of the items to be considered prior to determining if work should continue are:

- Potential for heat stress and heat-related injuries.
- Potential for cold stress and cold-related injuries.
- Treacherous weather-related conditions.



- Limited visibility.
- Electrical storm potential.

Site activities will be limited to daylight hours and acceptable weather conditions. Inclement working conditions include heavy rain, fog, high winds, and lightning. Observe daily weather reports and evacuate if necessary in case of inclement weather conditions.

## **6.5 Electrical Storm Guidelines**

In the event that lightning and/or thunder are observed while working onsite, all onsite activities shall stop and personnel shall seek proper shelter (e.g., substantial building, enclosed vehicle, etc.). Work shall not resume until the threat of lightning has subsided and no lightning or thunder has been observed for 30 minutes. If the possibility of lightning is forecast for the day, advise the onsite personnel on the risks and proper procedure at the pre-work safety briefing. Continuously monitor for changing weather conditions and allow enough time to properly stop work if lightning is forecast.

## 7. Safety Procedures

This section of the HASP presents the specific safety procedures to be implemented during Roux's activities at the Site in order to protect the health and safety of various on-site personnel. Minimum OSHA-mandated procedures are presented first, followed by client- and Site-specific procedures. Lastly, activity-specific procedures are discussed. These Site and activity-specific procedures supplement the general safety procedures included in Roux's Corporate Health and Safety Manual, which also must be followed in their entirety.

### 7.1 Training

At a minimum, Site personnel who will perform work in areas where there exists the potential for toxic exposure will be health and safety-trained prior to performing work onsite per OSHA 29 CFR 1910.120(e) and 29 CFR 1926.65(e). More specifically, all Roux, subcontractor, and other personnel engaged in sampling and remedial activities at the Site and who are exposed or potentially exposed to hazardous substances, health hazards, or safety hazards must have received at a minimum the 40 hour initial HAZWOPER training consistent with the requirements of 29CFR 1910.120(e)(3)(i) training and a minimum of 3 days' actual field experience under the direct supervision of a trained experienced supervisor, plus 8 hours of refresher training on an annual basis. Depending on tasks performed, less training may be permitted. Evidence of such training must be maintained at the Site at all times. Furthermore, all onsite management and supervisory personnel directly responsible for or who supervise the employees engaged in Site remedial operations, must have received an additional 8 hours of specialized training at the time of job assignment on topics including, but not limited to, the employer's safety and health program and the associated employee training program, personal protective equipment program, spill containment program, and health hazard monitoring procedure and techniques, plus 8 hours of refresher training on an annual basis.

Roux personnel training records are maintained in a corporate database with records available upon request from either the OHSM/SHSO/CHSM or Human Resources Department.

### 7.2 Site-Specific Safety Briefings for Visitors

A site-specific briefing is provided to all site visitors who enter this site beyond the site entry point. For visitors, the site-specific briefing provides information about site hazards, the site lay-out including work zones and places of refuge, the emergency alarm system and emergency evacuation procedures, and other pertinent safety and health requirements as appropriate.

### 7.3 HASP Information and Site-Specific Briefings for Workers

Site personnel review this HASP and are provided a site-specific tailgate briefing prior to the commencement of work to ensure that employees are familiar with this HASP and the information and requirements it contains as well as relevant JSAs. Additional briefings are provided as necessary to notify employees of any changes to this HASP as a result of information gathered during ongoing site characterization and analysis. Conditions for which we schedule additional briefings include but are not limited to: changes in site conditions, changes in the work schedule/plan, newly discovered hazards, and incidents occurring during site work.

### 7.4 Medical Surveillance

The medical surveillance section of the Health and Safety Plan describes how worker health status is monitored at this site. Medical surveillance is used when there is the potential for worker exposure to

hazardous substance at levels above OSHA permissible exposure limits or other published limits. The purpose of a medical surveillance program is to medically monitor worker health to ensure that personnel are not adversely affected by site hazards. The provisions for medical surveillance at this site are based on the site characterization and job hazard analysis found in Section 4 of this HASP and are consistent with OSHA requirements in 29 CFR 1910.120(f) as applicable.

#### **7.4.1 Site Medical Surveillance Program**

Medical surveillance requirements are based on a worker's potential for exposure as determined by the site characterization and job hazard analysis documented in Section 4 and JSAs within **Appendix A** of this HASP and in compliance with the requirements of 29 CFR 1910.120(f)(2). Based on site information and use of direct reading instruments, limited use of respirators (less than 30 days per year), and the absence of an employee-staffed HAZMAT team, a limited medical surveillance program is required and implemented at this site. The medical surveillance program provides that:

1. Workers assigned to tasks requiring the use of respirators receive medical examinations in accordance with 29 CFR 1910.134(e) to ensure they are physically capable to perform the work and use the equipment, and
2. If a worker is injured, becomes ill, or develops signs or symptoms of possible over-exposure to hazardous substance or health hazards, medical examinations are provided to that worker as soon as possible after the occurrence and as required by the attending physician.
3. These medical examinations and procedures are performed by or under the supervision of a licensed physician and are provided to workers free of cost, without loss of pay, and at a reasonable time and place. In addition, the need to implement a more comprehensive medical surveillance program will be re-evaluated after any apparent over-exposure.

#### **7.4.2 Medical Recordkeeping Procedures**

Medical recordkeeping procedures are consistent with the requirements of 29 CFR 1910.1020 and are described in the company's overall safety and health program. A copy of that program is available at our Islandia, NY office.

The following items are maintained in worker medical records:

- Respirator fit test and selection
- Physician's medical opinion of fitness for duty (pre-placement, periodic, termination)
- Physician's medical opinion of fitness for respirator protection (pre-placement, periodic)
- Exposure monitoring results

#### **7.4.3 Program Review**

The medical program is reviewed to ensure its effectiveness. The Corporate Health and Safety Manager in coordination with the Human Resources Director is responsible for this review. At minimum, this review consists of:

- Review of accident and injury records and medical records to determine whether the causes of accidents and illness were promptly investigated and whether corrective measures were taken wherever possible;
- Evaluation of the appropriateness of required medical tests based on site exposures; and
- Review of emergency treatment procedures and emergency contacts list to ensure they were site-specific, effective, and current.

## 7.5 Personnel Protection

Site safety and health hazards are eliminated or reduced to the greatest extent possible through engineering controls and work practices. Where hazards are still present, a combination of engineering controls, work practices and PPE are used to protect employees. Appropriate personal protective equipment (PPE) shall be worn by Site personnel when there is a potential exposure to chemical hazards or physical hazards (e.g., falling objects, flying particles, sharp edges, electricity and noise), as determined by the SHSO. The level of personal protection, type and kind of equipment selected will depend on the hazardous conditions and in some cases cost, availability, compatibility with other equipment, and performance. An accurate assessment of all these factors will be made before work can be safely executed.

Roux maintains a comprehensive written PPE program that addresses proper PPE selection, use, maintenance, storage, fit and inspection. Roux's PPE program can be found within **Appendix C**. PPE to be used at the Site will meet the appropriate American National Standards Institute (ANSI) standards and the following OSHA (General/Construction Industry) standards for minimum PPE requirements.

The minimum level of PPE for entry onto the Site is Level D. The following equipment shall be worn:

- Work uniform (long pants, sleeved shirt)
- Hard hat
- Steel or composite toe work boots
- Safety Glasses (must comply with one of the following ANSI/ISEA Z87.1-2010, ANSI Z87.1-2003, ANSI Z87.1-2003)
- Boot Covers (as needed)
- Hearing Protection (as needed)
- High visibility clothing (shirt/vest)
- Hand Protection (e.g., minimum cut resistance meeting ANSI 105-2000 Level 2)

Note that jewelry shall be removed or appropriately secured to prevent it from becoming caught in rotating equipment or unexpectedly snagged on a fixed object. (e.g., wrist watches bracelets, rings, chains and necklaces, open earrings). Do not wear loose clothing and all shoulder length hair should be tied back.

Site specific PPE ensembles and materials are identified within task specific JSAs located within **Appendix A**, and any upgrades or downgrades of the level of protection (i.e., not specified in the JSA) must be approved by the PP and immediately communicated to all Roux personnel and subcontractors as applicable. PPE is used in accordance with manufacturer's recommendations.

### 7.5.1 Hearing Conservation

Hearing protection is made available when noise exposures equal or exceed an 8-hour time-weighted average sound level of 85 dBA. Hearing protection is required when the 8-hour time weighted average sound level  $\geq$  90 dBA. Where noise exposure meets or exceeds this level, noise is listed as a physical hazard in the JSA for the tasks/operation, and hearing protection is included as one of the control measures (PPE).

## 7.6 Monitoring

An air monitoring program is important to the safety of on- and off-Site personnel, and the surrounding area. A preliminary survey, to establish background conditions in the immediate sampling area, may be made prior to the initiation of Site work including, but not limited to, monitoring wind direction (e.g. wind socks) and approximate temperature during all invasive Site activities. This survey will be conducted with the appropriate pre-calibrated air monitoring instrument(s), as warranted by the field activity. Once this survey has been complete, any changes in the type of PPE will be determined and relayed to those working on-Site.

Work zone air monitoring will be performed to verify that the proper level of PPE is used, and to determine if increased protection or work stoppage is required. The following equipment shall be used to monitor conditions:

- A Photoionization Detector (PID) with a lamp energy of 10.6 eV will be used to provide direct readings of organic vapor concentrations during intrusive activities to determine that personnel protection is adequate. Concentrations shall be recorded during intrusive activities with the potential to encounter contaminant vapors.
- Colorimetric detection tubes shall be used based on PID action levels, to qualitatively identify possible contaminants as applicable.
- A pre-calibrated multi-gas meter with combustible Lower Explosive Limit (LEL), oxygen (O<sub>2</sub>), carbon monoxide (CO), and hydrogen sulfide (H<sub>2</sub>S) sensors shall be used to monitor the potential for oxygen-deficient atmospheres, explosive concentrations of organic vapors, and toxic gases during intrusive operations. Monitoring will be performed according to the action levels for oxygen and combustible gases provided in this section. The calibration for this device will be performed using a known gas composition calibration mixture.

Personal exposure monitoring utilizing activated charcoal tubes may be considered based on whether or not the area sample results are at or above half of the PEL. The decision to perform the monitoring will be made by, and under the control of, the CHSM.

Below are monitoring action levels for Site-specific chemicals of concern. In the event that PID readings above the thresholds identified below are sustained for 5 minutes in the breathing zone, worker protection will require upgrading following notification to the OHSM and applicable parties (e.g., client, board of health, regulators, etc.).

### 7.6.1 Action Levels for Air Monitoring

PPE can remain at Level D if breathing zone VOC concentrations are less than 5 ppm and benzene is non-detect. Personnel are required to evacuate the Site when breathing zone VOC readings exceed 25 ppm.

The following tables include summaries of the air monitoring, work practices, and action levels for the expected contaminants. The action levels to initiate testing with colorimetric tubes for airborne volatiles is 1 ppm (PID reading) and is based on the Permissible Exposure Limit (PEL) for benzene (1 ppm). The colorimetric tubes are used to confirm the presence or absence of specific constituents, and they do not provide a measured concentration.

Air Monitoring Summary and Action Levels Organic Vapors	
PID Reading in Breathing Zone (ppm) <sup>1</sup>	Action
0-1 ppm above background <sup>2</sup>	Continue monitoring
1-5 ppm sustained 60 seconds	Continue monitoring, if applicable initiate additional collection of benzene using colorimetric tubes.
<5 ppm and no presence of benzene	Continue Monitoring, ventilate space
≥ 5 ppm - ≤ 25 ppm and no presence of benzene	Ventilate space until PID reads < 5 ppm. If < 25 ppm cannot be achieved, upgrade to Level C <sup>3</sup> .
≥ 25 ppm	Ventilate space and evacuate area.

<sup>1</sup> Based on relative response/sensitivity of PID to benzene.

<sup>2</sup> Background concentrations should be established at the beginning of each work day. It may be necessary to re-establish background concentrations and ambient conditions vary through the day.

<sup>3</sup> Measured air concentrations of known organic vapors will be reduced by the respirator to one half of the PEL or lower, and the individual and combined compound concentrations shall be within the service limit of the respirator cartridge.

Air Monitoring Summary and Action Levels Oxygen	
O <sub>2</sub> Reading in Breathing Zone (%) <sup>1</sup>	Action
20.9% O <sub>2</sub>	Oxygen level normal
< 19.5% O <sub>2</sub>	Oxygen deficient Interrupt task/Evacuate area
>23.5% O <sub>2</sub>	Oxygen enriched Interrupt task/Evacuate area

1. Action levels based on USEPA Standard Operating Safety Guides; Table 5-1, Atmospheric Hazard Action Guidelines may be further restricted based on the CHSM's professional judgment and experience.

Air Monitoring Summary and Action Levels Carbon Monoxide	
CO Reading in Breathing Zone (ppm) <sup>1</sup>	Action
<25 ppm	Inspect exhaust system for leaks or other sources of CO. Monitor initially and every 15 minutes during use of CO-generating equipment
25-50 ppm	Ventilate area. Monitor continuously and record measurements. Contact PM.
>50 ppm	Cease Field Operations. Ventilate area.

1. Based upon the American Conference of Governmental Industrial Hygienists (ACGIH) Threshold Limit Value (TLV) of 25 ppm as an 8-hour time weighted average (TWA) and OSHA's Permissible Exposure Limit (PEL) of 50 ppm as an 8-hour TWA concentration.

Air Monitoring Summary and Action Levels Combustible Gases	
Lower Explosive Limit (LEL) Reading	Action
< 4% LEL (<2,000 ppm)	Site activities will continue with normal monitoring
4% – 20% LEL (2,000 – 10,000 ppm)	Stop work until levels dissipate to <4% LEL
> 20% LEL (>10,000 ppm)	Potential explosion hazard. Halt all site activities, research source of release, aerate work area, suppress source

Air Monitoring Summary and Action Levels Hydrogen Sulfide	
Hydrogen Sulfide (H <sub>2</sub> S) Reading	Action
<10 ppm	Site activities will continue with normal monitoring
>10 ppm	Stop work until levels dissipate to <10 ppm; use mechanical ventilation if possible
Cannot use air purifying respirators for H <sub>2</sub> S because of olfactory fatigue	

### 7.6.2 Air Monitoring Equipment and Calibration

A PID calibrated to an appropriate calibration mixture will be used to detect organic vapors in and around the work areas. Monitoring will be conducted in and around all work areas and at the workers breathing zone before activities commence to establish a background level, then at 15-minute intervals throughout the day. All equipment will be calibrated according to the manufacturer's recommendation. A calibration log will be maintained and will include the name of the person who performed the calibration, the date and time calibrated, and the instrument reading at the time of calibration. A manual bellows pump or equivalent with colorimetric tubes for formaldehyde will be utilized to determine the course of action related to upgrading or downgrading the level of respiratory protection, as applicable.

If air monitoring data indicate safe levels of potentially harmful constituents at consistent intervals (5-minute intervals), then monitoring can be conducted less frequently (every 30 minutes). This determination will be made by the onsite SHSO. Monitoring data, including background readings and calibration records, will be documented. Work to be performed on-Site will conform to Roux Associates' Standard Operating Procedures (SOPs). Conformance with these guidelines as well as the guidelines described in this HASP will aid in mitigating the physical and chemical hazards mentioned throughout this HASP.

### 7.7 Tailgate Safety Meetings

A designated Site worker will provide daily safety briefings (e.g., tailgate meetings) including, but not limited to, the following scenarios:

- When new operations are to be conducted;

- Whenever changes in work practices must be implemented; and
- When new conditions are identified and/or information becomes available.

Daily safety briefings shall be recorded on the Roux Daily Tailgate Health and Safety Meeting Log/Daily Site Safety Checklist, and all completed forms will become a part of the project file.

## **7.8 Spill Containment**

Spill containment equipment and procedures should, at a minimum, meet the requirements of the facility's Spill Prevention, Control and Countermeasure Plan, if applicable. Otherwise, spill containment equipment and procedures must be considered depending on the task including, but not limited to, chemical/product transfer points and handling.

### **7.8.1 Initial Spill Notification and Response**

Any worker who discovers a hazardous substance spill will immediately notify the Project Manager. The worker will, to his/her best ability, report the hazardous substance involved, the location of the spill, the estimated quantity of material spilled, the direction/flow of the spill material, related fire/explosion incidents, and any associated injuries without compromising their own safety.

### **7.8.2 Spill Evaluation and Response**

The Project Manager is responsible for evaluating spills and determining the appropriate response. When this evaluation is being made, the spill area will be isolated and demarcated to the extent possible. If necessary, to protect nearby community members, notification of the appropriate authorities is made by the PM as appropriate. On-site response is limited to small spills (e.g., <10 gallons), large spills require external emergency responders who will be contacted by the SHSO.

## **7.9 Decontamination**

The decontamination section of the HASP describes how personnel and equipment are decontaminated when they leave the Exclusion Zone. This section also describes how residual waste from decontamination processes is disposed. The site decontamination procedures are designed to achieve an orderly, controlled removal or neutralization of contaminants that may accumulate on personnel or equipment. These procedures minimize worker contact with contaminants and protect against the transfer of contaminants to clean areas of the site and off-site. They also extend the useful life of PPE by reducing the amount of time that contaminants contact and can permeate PPE surfaces. Decontamination is facilitated within the contamination reduction zone at this site.

### **7.9.1 Decontamination Procedures for Personnel and PPE**

The following are general decontamination procedures established and implemented at this site.

1. Decontamination is required for all workers exiting a contaminated area. Personnel may re-enter the Support Zone only after undergoing the decontamination procedures described below in the next section.
2. Protective clothing is decontaminated, cleaned, laundered, maintained and/or replaced as needed to ensure its effectiveness.
3. PPE used at this site that requires maintenance or parts replacement is decontaminated prior to repairs or



4. PPE used at this site is decontaminated or prepared for disposal on the premises. Personnel who handle contaminated equipment have been trained in the proper means to do so to avoid hazardous exposure.
5. This site uses an off-site laundry for decontamination of PPE. The site has informed that facility of the hazards associated with contaminated PPE from this site.
6. The site requires and trains workers that if their permeable clothing is splashed or becomes wetted with a hazardous substance, they will immediately exit the work zone, perform applicable decontamination procedures, shower, and change into uncontaminated clothing.
7. Procedures for disposal of decontamination waste meet applicable local, State, and Federal regulations.

### **7.9.2 Decontamination Procedures for Equipment**

All tools, equipment, and machinery from the Exclusion Zone or CRZ are decontaminated in the CRZ prior to removal to the Support Zone. Equipment decontamination procedures are designed to minimize the potential for hazardous skin or inhalation exposure and to avoid cross-contamination and chemical incompatibilities.

General Equipment Decontamination Procedures:

1. Decontamination is required for all equipment exiting a contaminated area. Equipment may re-enter the Support Zone only after undergoing the equipment decontamination procedures.
2. Vehicles that travel regularly between the contaminated and clean areas of the site are carefully decontaminated each time they exit the Exclusion Zone and the effectiveness of that decontamination is monitored to reduce the likelihood that contamination will be spread to other parts of the site.
3. Particular attention is given to decontaminating tires, scoops, and other parts of heavy equipment that are directly exposed to contaminants and contaminated soil.

The following items may be used to decontaminate equipment:

- Fresh water rinse;
- Non-phosphorus detergent wash;
- Distilled water rinse;
- Acetone rinse;
- Distilled water rinse; and
- A steam cleaner or pressure washer (heavy equipment only).

### **7.9.3 Monitoring the Effectiveness of Decontamination Procedures**

Visual examination and sampling are used to evaluate the effectiveness of decontamination procedures. Visual examination is used to ensure that procedures are implemented as described and that they appear to control the spread of contaminants under changing site conditions. Visual examination is also used to inspect for signs of residual contamination or for contaminant permeation of PPE.

Personnel who work in contaminated areas of the site, either the Contamination Reduction Zone (CRZ) or the Exclusion Zone, are trained in the principles and practices of decontamination described in this section of the HASP and in related SOPs. If site procedures are changed as a result of inspection and monitoring, all affected employees are notified of these changes.

## 7.10 Confined Space Entry

Confined space entry is not in the scope of work for Roux employees during the activities of this project, however the guidelines for such activities are outlined below, should the need arise.

The following is a list of the safety requirements for confined space entry at the Site:

- **ROUX PERSONNEL ARE NOT AUTHORIZED TO ENTER AN OSHA PERMIT REQUIRED CONFINED SPACE;**
- Currently the scope of work **DOES NOT** require personnel to enter permitted confined space for this project; and
- Any changes to the field activities that may necessitate confined space entry will be reported to the Project Principal and OHSM.

Confined space is defined as any space, depression, or enclosure that:

- Has limited opening for entry and egress;
- Is large enough for an employee to enter and perform assigned work; and
- Is not intended for continuous occupancy.

A permit required confined space is one that meets the definition of a confined space and has one or more of the following characteristics:

- May contain or produce life-threatening atmospheres due to oxygen deficiency the presence of toxic, flammable, or corrosive contaminants;
- Contains a material that has the potential for engulfment;
- Has an internal configuration that may cause an entrant to be trapped or asphyxiated by inwardly converging walls or by a floor that slopes downward and tapers to a smaller cross-section; and
- Contains any other serious safety or health hazards.

Although Roux personnel will not perform confined space entry, it is expected that subcontractors performing cleaning and mitigation and/or remedial measures activities may be required to enter structures that are considered to be a permit required confined space. Permitting of the confined space as well as hazard mitigation for entry will be completed by the subcontractor in accordance with 1910.146.

## 7.11 Client and Site-Specific

In addition to the OSHA-specific procedures discussed above, there may be client and site-specific safety procedures that must be adhered to during the performance of remedial activities at the Site.

## 7.12 Unusual or Significant Risks

Field activities that appear to have unusual or significant risks that cannot be adequately managed with existing risk tools such as LPS, HASPs, traffic safety plans, work permits, design and O&M practices, equipment HAZOPS or other safety tools must be referred to the CHSM to help with the assessment and management of the associated potential safety risks. Examples include the use of explosives for demolition, use of firearms to control wildlife, rappelling, demolition over water, etc.

## 7.13 Activity-Specific

In addition to the general hazards discussed above, there are activity-specific hazards associated with each work activity planned for the Site. An activity-specific JSA has been completed for each of the activities planned for the Site. JSAs are provided in **Appendix A**. In the event that new work activities or tasks are planned, JSAs will be developed and implemented prior to performing the new activities. In the absence of a JSA, the personnel performing work must prepare a field JSA and receive clearance from a designated competent safety official prior to performing any task with significant risk. In emergency situations where time is critical SPSAs will be utilized to identify the task, associated hazards and mitigative actions to take. For lower risk activities (as deemed by the discretion of a Competent Person) where a JSA is determined to not be needed, the individual(s) conducting the activities must perform SPSAs prior to and during the work.

### 7.13.1 Electrical and Other Utility Assessment and Accommodations

Roux shall perform a site walk to identify any potential overhead electrical or utility lines. All applicable guidelines will be followed in the vicinity of overhead power and utility lines (see Section 7.13.3 below).

Roux has also reviewed all available Site maps showing buried utility lines to identify potential hazards, which revealed that no underground hazards are known to exist in the vicinity of the areas of the Site pertinent to this HASP.

### 7.13.2 Subsurface Work

Subsurface work activities will require adherence to Roux's Corporate Subsurface Utility Clearance Management program found within **Appendix D**.

#### 7.13.2.1 Excavations and Trenching

All trenching and excavation work activities contracted by Roux shall comply with 29 CFR 1926.651-652 Subpart P. Additionally, for trenches greater than 4 feet deep, where employees will enter, the trench needs to have a stairway or ladder or other safe means of egress. Where employees will enter trenches greater than 5 feet deep, the trench must have some type of protective system or sloped appropriately to prevent cave-ins.

The SHSO will be present on-Site during all Roux contracted excavation and backfill operations and will supplement health and safety monitoring conducted by Subcontractor air quality screening to ensure that appropriate levels of protection and safety procedures are utilized. The proximity of chemical, water, sewer, and electrical lines will be identified by Roux and/or their subcontractor before any subsurface activity or sampling is attempted.

The following safe work practices will be implemented during this task.

- The proximity of chemical, water, sewer, and electrical lines will be identified by a facility representative prior to beginning any subsurface activity.
- While earthmoving, stay out of the excavator's delineated heavy equipment exclusion zone and away from the excavation sides, where there is potential for cave in (within excavations that are 6 feet or more in depth, a delineated perimeter 6 feet away from the excavated edge is required).

### Maximum Allowable Slopes

Soil or Rock Type	Maximum Allowable Slopes (H:V) <sup>1</sup> for Excavations Less Than 20 Feet Deep <sup>3</sup>
Stable Rock	Vertical (90°)
Type A <sup>2</sup>	<sup>3</sup> / <sub>4</sub> : 1 (53°)
Type B	1 : 1 (45°)
Type C	1 1/2 : 1 (34°)

OSHA (29 CFR 1926.652, Subpart P, Appendices A and B)

Notes:

- <sup>1</sup> Numbers shown in parentheses next to maximum allowable slopes are angles expressed in degrees from the horizontal. Angles have been rounded off.
- <sup>2</sup> A short-term maximum allowable slope of 1/2H : 1V (63°) is allowed in excavations in Type A soil that are 12 feet (3.67 meters) or less in depth. Short-term maximum allowable slopes for excavations greater than 12 feet (3.67 meters) in depth shall be <sup>3</sup>/<sub>4</sub>H : 1V (53°).
- <sup>3</sup> Sloping or benching for excavations greater than 20 feet deep shall be designed and stamped by a registered professional engineer.

Proper stockpiling (i.e., 2 feet minimum distance from the excavation edge), containment, transport, storage, and disposal practices will be utilized and is dependent upon the potential type and amount of waste generated during operations. The location of safety equipment and evacuation procedures will be established prior to initiation of operations according to this HASP.

### 7.13.3 Heavy Equipment

Use of heavy equipment at the Site will require adherence to Roux's Corporate Heavy Equipment Exclusion Zone Management Program found within **Appendix E**. Additionally, operation of the drill rig/other heavy equipment will maintain clearances from overhead power lines in accordance with OSHA 29 CFR1926.1408 Table A Minimum Clearance Distances provided below.

#### Minimum Required Clearances for Energized Overhead Power Lines

Nominal System Voltage of Power Line (K V)	Minimum Required Clearance (feet)
0-50	10
51-100	12
101-200	15
201-300	20
301-500	25
501-750	35
751-1000	45

1 kilovolt (KV) = 1,000 volts

### 7.14 Heat Stress

The National Oceanic and Atmospheric Administration records average minimum/maximum temperatures of [25/87] degrees Fahrenheit during the year in Brooklyn, New York.

### 7.14.1 Heat Stress

Heat stress is a significant potential hazard and can be associated with heavy physical activity and/or the use of personal protective equipment in hot weather environments. Heat cramps are brought on by prolonged exposure to heat. As an individual sweats, water and salts are lost by the body resulting in painful muscle cramps. The signs and symptoms of heat stress are as follows:

- Severe muscle cramps, usually in the legs and abdomen;
- Exhaustion, often to the point of collapse; and
- Dizziness or periods of faintness.

First aid treatment includes, but is not limited to, shade, rest, and fluid replacement. Typically, the individual should recover within one-half hour while being monitored constantly. If the individual has not improved substantially within 30 minutes and the body temperature has not decreased, the individual should be transported to a hospital for medical attention.

### 7.14.2 Heat Exhaustion

Heat exhaustion may occur in a healthy individual who has been exposed to excessive heat while working or exercising. The circulatory system of the individual fails as blood collects near the skin to rid the body of excess heat through transference. The signs and symptoms of heat exhaustion are as follows:

- Rapid and shallow breathing;
- Weak pulse;
- Cold and clammy skin with heavy perspiration;
- Skin appears pale;
- Fatigue and weakness;
- Dizziness; and
- Elevated body temperature.

First aid treatment includes, but is not limited to, cooling the victim, elevating the feet, and replacing fluids.

If the individual is not substantially improved within 30 minutes and the body temperature has not decreased, the individual should be transported to the hospital for medical attention.

### 7.14.3 Heat Stroke

Heat stroke occurs when an individual is exposed to excessive heat and stops sweating. This condition is classified as a MEDICAL EMERGENCY requiring immediate cooling of the victim and transport to a medical facility. The signs and symptoms of heat stroke are as follows:

- Dry, hot red skin;
- Body temperature approaching or above 105 degrees F;
- Confusion, altered mental state, slurred speech;
- Seizures;
- Large (dilated) pupils; and
- Loss of consciousness – the individual may go into a coma.

First aid treatment requires immediate cooling and transportation to a medical facility. Heat stress is a significant hazard if any type of protective equipment (semi-permeable or impermeable) that prevents evaporative cooling is worn in hot weather environments.

## 7.15 Cold Stress

Cold stress is a danger at low temperatures and when the wind-chill factor is low. Prevention of cold-related illnesses is a function of whole-body protection. Adequate insulating clothing must be used when the air temperature is below 60°F. A work/rest regimen will be initiated when ambient temperatures and protective clothing cause a stressful situation. In addition, reduced work periods followed by rest in a warm area may be necessary in extreme conditions. The signs and symptoms of cold stress include the following:

- Severe shivering;
- Abnormal behavior;
- Slowing;
- Weakness;
- Stumbling or repeated falling;
- Inability to walk;
- Collapse; and/or
- Unconsciousness.

First aid requires removing the victim from the cold environment and seeking medical attention immediately. Also, prevent further body heat loss by covering the victim lightly with blankets. Do not cover the victim's face. If the victim is still conscious, administer hot drinks and encourage activity such as walking, wrapped in a blanket.



## 9. Approvals

By their signature, the undersigned certify that this HASP is approved and will be utilized at the Franklin Point LLC / Franklin Point Holding LLC.

---

TBD – Site Health and Safety Officer

---

Date

---

Nevin Pahlad - Office Health and Safety Manager

---

Date

---

Rachel Henke – Senior Project Manager

---

Date

---

Robert Kovacs – Project Principal

---

Date



**Site-Specific Health and Safety Plan**  
**12 Franklin Street, Brooklyn, New York 11222**

---

**TABLES**

1. Toxicological Properties of Hazardous Substances Present at the Site

**Table 1. Toxicological, Physical, and Chemical Properties of Compounds Potentially Present at the Site.**

Compound	CAS #	ACGIH TLV	NIOSH REL	OSHA PEL	IDLH	Routes of Exposure	Toxic Properties	Target Organs	Physical/Chemical Properties
<b>ORGANOCHLORINE PESTICIDES (OCP)</b>									
DDT	50-29-3	TWA 1 mg/m3	TWA 0.5 mg/m3	TWA 1 mg/m3	500 mg/m3	Inhalation, ingestion, skin and/or eye contact	Irritation eyes, skin; paresthesia tongue, lips, face; tremor; anxiety, dizziness, confusion, malaise (vague feeling of discomfort), headache, lassitude (weakness, exhaustion); convulsions; paresis hands; vomiting; [potential occupational carcinogen]	Eyes, skin, central nervous system, kidneys, liver, peripheral nervous system	White, odorless and tasteless, very stable, water-insoluble, synthetic BP: 260°F Fl.Pt. = 162-171°F LEL: NA UEL: NA
Aldrin	309-00-2	TWA 0.1 mg/m3	TWA 0.25 mg/m3	TWA 0.25 mg/m3	25 mg/m3	Inhalation, ingestion, skin and/or eye contact	headache, dizziness; nausea, vomiting, malaise (vague feeling of discomfort); myoclonic jerks of limbs; clonic, tonic convulsions; coma; hematuria (blood in the urine), azotemia; [potential occupational carcinogen]	Developemntal, Endocrine, Liver, Immune System, Nervous System,	Colorless to dark-brown crystalline solid with a mild chemical odor. BP: 293°F Fl.Pt. = 150°F LEL: NA UEL: NA
Lindane (gamma-BHC)	58-89-9	TWA 0.5 mg/m3	TWA 0.5 mg/m3	TWA 0.5 mg/m3	50 mg/m3	Inhalation, ingestion, skin and/or eye contact	irritation eyes, skin, nose, throat; headache; nausea; clonic convulsions; resp difficulty; cyanosis; aplastic anemia; muscle spasm; In Animals: liver, kidney damage	Eyes, skin, respiratory system, central nervous system, blood, liver, kidneys	White to yellow, crystalline powder with a slight, musty odor. BP: 614°F Fl.Pt. = 150°F LEL: NA UEL: NA
Dieldrin	860-57-1 □	TWA 0.1 mg/m3	TWA 0.25 mg/m3	TWA 0.25 mg/m3	25 mg/m3	Inhalation, ingestion, skin and/or eye contact	headache, dizziness; nausea, vomiting, malaise (vague feeling of discomfort), sweating; myoclonic limb jerks; clonic, tonic convulsions; coma; ; In Animals: liver, kidney damage [potential occupational carcinogen]	Developemntal, Endocrine, Liver, Immune System, Nervous System,	Colorless to light-tan crystals with a mild, chemical odor. BP: NA (Decomposes) Fl.Pt. = NA LEL: NA UEL: NA
<b>VOLATILE ORGANIC COMPOUNDS (VOCs)</b>									
1,1,1-Trichloroethane	71-55-6	TWA 350 ppm STEL 450 ppm	C 350 ppm (1900 mg/m <sup>3</sup> ) [15-minute]	TWA 350 ppm (1900 mg/m <sup>3</sup> )	700 ppm	Inhalation, ingestion, skin and/or eye contact	Irritation eyes, skin; headache, lassitude (weakness, exhaustion), central nervous system depression, poor equilibrium; dermatitis; cardiac arrhythmias; liver damage	Eyes, skin, central nervous system, cardiovascular system, liver	Colorless liquid with a mild, chloroform-like odor. BP: 165°F Fl.Pt. = NA LEL: 7.5% UEL: 12.5% Combustible Liquid, but burns with difficulty
1,1,2,2-Tetrachloroethane	79-34-5	TWA 1 ppm [skin]	Ca TWA 1 ppm (7 mg/m <sup>3</sup> ) [skin]	TWA 5 ppm (35 mg/m <sup>3</sup> ) [skin]	Ca [100 ppm]	Inhalation, skin absorption, ingestion, skin and/or eye contact	Nausea, vomiting, abdominal pain; tremor fingers; jaundice, hepatitis, liver tenderness; dermatitis; leukocytosis (increased blood leukocytes); kidney damage; [potential occupational carcinogen]	Skin, liver, kidneys, central nervous system, gastrointestinal tract	Colorless to pale-yellow liquid with a pungent, chloroform-like odor BP: 296°F Fl.Pt. = NA LEL: NA UEL: NA Noncombustible Liquid
1,1,2-Trichloro-1,2,2-trifluoroethane	76-13-1	TWA 1000 ppm STEL 1250 ppm	TWA 1000 ppm (7600 mg/m <sup>3</sup> ) ST 1250 ppm (9500 mg/m <sup>3</sup> )	TWA 1000 ppm (7600 mg/m <sup>3</sup> )	2000 ppm	Inhalation, ingestion, skin and/or eye contact	Irritation skin, throat, drowsiness, dermatitis; central nervous system depression; In Animals: cardiac arrhythmias, narcosis	Skin, heart, central nervous system, cardiovascular system	Colorless to water-white liquid with an odor like carbon tetrachloride at high concentrations. [Note: A gas above 118°F.] BP: 118°F Fl.Pt. = NA LEL: NA UEL: NA
1,1,2-Trichloroethane	79-00-5	TWA 10 ppm [skin]	Ca TWA 10 ppm (45 mg/m <sup>3</sup> ) [skin]	TWA 10 ppm (45 mg/m <sup>3</sup> ) [skin]	Ca [100 ppm]	Inhalation, skin absorption, ingestion, skin and/or eye contact	Irritation eyes, nose; central nervous system depression; liver, kidney damage; dermatitis; [potential occupational carcinogen]	Eyes, respiratory system, central nervous system, liver, kidneys	Colorless liquid with a sweet, chloroform-like odor BP: 237°F Fl.Pt. = NA LEL: 6% UEL: 15.5% Combustible Liquid, forms dense soot
1,1-Dichloroethane	75-34-3	TWA 100 ppm	TWA 100 ppm (400 mg/m <sup>3</sup> )	TWA 100 ppm (400 mg/m <sup>3</sup> )	3,000 ppm	Inhalation, ingestion, skin and/or eye contact	Irritation skin; central nervous system depression; liver, kidney, lung damage	Skin, liver, kidneys, lungs, central nervous system	Colorless, oily liquid with a chloroform-like odor. BP: 135°F Fl.Pt. = 2°F LEL: 5.4% UEL: 11.4% Class IB Flammable Liquid Fl.P. below 73°F and BP at or above 100°F.
1,1-Dichloroethene	75-35-4	TWA 5 ppm	Ca	None	Ca	Inhalation, skin absorption, ingestion, skin and/or eye contact	Irritation eyes, skin, throat; dizziness, headache, nausea, dyspnea (breathing difficulty); liver, kidney disturbance; pneumonitis; [potential occupational carcinogen]	Eyes, skin, respiratory system, central nervous system, liver, kidneys	Colorless liquid or gas (above 89°F) with a mild, sweet, chloroform-like odor BP: 89°F Fl.Pt. = -2°F LEL: 6.5% UEL: 15.5% Class IA Flammable Liquid: Fl.P. below 73°F and BP below 100°F

**Table 1. Toxicological, Physical, and Chemical Properties of Compounds Potentially Present at the Site.**

Compound	CAS #	ACGIH TLV	NIOSH REL	OSHA PEL	IDLH	Routes of Exposure	Toxic Properties	Target Organs	Physical/Chemical Properties
1,2,3-Trichlorobenzene	87-61-6	Cameo Chemicals Source <a href="https://cameochemicals.noaa.gov/chemical/10051">https://cameochemicals.noaa.gov/chemical/10051</a>	NA	NA	NA	Inhalation, skin absorption, ingestion, skin and/or eye contact	Inhalation may cause irritation of respiratory tract. Irritating to the eyes. May redden skin on contact. Ingestion may cause liver damage.	Skin, eyes, respiratory tract, liver	A white solid with a sharp chlorobenzene odor. Insoluble in water and denser than water. Hence sinks in water Fl.Pt. = 234.9°F
1,2,4-Trichlorobenzene	120-82-1	C 5 ppm	C 5 ppm (40 mg/m3)	None	N.D.	Inhalation, skin absorption, ingestion, skin and/or eye contact	irritation eyes, skin, mucous membrane; In Animals: liver, kidney damage; possible teratogenic effects	Eyes, skin, respiratory system, liver, reproductive system	Colorless liquid or crystalline solid (below 63°F) with an aromatic odor BP: 416°F Fl.Pt. = 222°F LEL (302°F): 2.5% UEL (302°F): 6.6% Class IIIB Combustible Liquid: Fl.P. at or above 200°F. Combustible Solid
1,2-Dibromo-3-chloropropane	96-12-8	NA	Ca	TWA 0.001 ppm	Ca	Inhalation, skin absorption, ingestion, skin and/or eye contact	Irritation eyes, skin, nose, throat; drowsiness; nausea, vomiting; pulmonary edema; liver, kidney injury; sterility; [potential occupational carcinogen]	Eyes, skin, respiratory system, central nervous system, liver, kidneys, spleen, reproductive system, digestive system	Dense yellow or amber liquid with a pungent odor at high concentrations. [pesticide] [Note: A solid below 43°F.] BP: 384°F Fl.Pt. = (oc) 170°F LEL: NA UEL: NA Class IIIA Combustible Liquid: Fl.P. at or above 140°F and below 200°F.
1,2-Dibromoethane	106-93-4	None listed Skin	Ca TWA 0.045 ppm C 0.13 ppm [15-minute]	TWA 20 ppm C 30 ppm 50 ppm [5-minute maximum peak]	Ca [100 ppm]	Inhalation, skin absorption, ingestion, skin and/or eye contact	Irritation eyes, skin, respiratory system; dermatitis with vesiculation; liver, heart, spleen, kidney damage; reproductive effects; [potential occupational carcinogen]	Eyes, skin, respiratory system, liver, kidneys, reproductive system	Colorless liquid or solid (below 50°F) with a sweet odor. [fumigant] BP: 268°F Fl.Pt. = 50°F LEL: NA UEL: NA Noncombustible Liquid
1,2-Dichlorobenzene	95-50-1	TWA 25 ppm STEL 50 ppm	C 50 ppm (300 mg/m3)	C 50 ppm (300 mg/m3)	200 ppm	Inhalation, skin absorption, ingestion, skin and/or eye contact	Irritation eyes, nose; liver, kidney damage; skin blisters	Eyes, skin, respiratory system, liver, kidneys	Colorless to pale-yellow liquid with a pleasant, aromatic odor. [herbicide] BP: 357°F Fl.Pt. = 1°F LEL: 2.2% UEL: 9.2% Class IIIA Combustible Liquid: Fl.P. at or above 140°F and below 200°F.
1,2-Dichloroethane	107-06-2	TWA 10 ppm	Ca TWA 1 ppm (4 mg/m3) ST 2 ppm (8 mg/m3)	TWA 50 ppm C 100 ppm 200 ppm [5-minute maximum peak in any 3 hours]	Ca [50 ppm]	Inhalation, ingestion, skin absorption, skin and/or eye contact	Irritation eyes, corneal opacity; central nervous system depression; nausea, vomiting; dermatitis; liver, kidney, cardiovascular system damage; [potential occupational carcinogen]	Eyes, skin, kidneys, liver, central nervous system, cardiovascular system	Colorless liquid with a pleasant, chloroform-like odor. [Note: Decomposes slowly, becomes acidic & darkens in color.] BP: 182°F Fl.Pt. = 56°F LEL: 6.2% UEL: 16% Class IB Flammable Liquid Fl.P. below 73°F and BP at or above 100°F.
1,2-Dichloropropane	78-87-5	TWA 10 ppm Dermal Sensitizer (DSEN)	Ca	TWA 75 ppm (350 mg/m3)	Ca [400 ppm]	Inhalation, skin absorption, ingestion, skin and/or eye contact	Irritation eyes, skin, respiratory system; drowsiness, dizziness; liver, kidney damage; In Animals: central nervous system depression; [potential occupational carcinogen]	Eyes, skin, respiratory system, liver, kidneys, central nervous system	Colorless liquid with a chloroform-like odor. [pesticide] BP: 206°F Fl.Pt. = 60°F LEL: 3.4% UEL: 14.5% Class IB Flammable Liquid: Fl.P. below 73°F and BP at or above 100°F.
1,3-Dichlorobenzene	541-73-1	<a href="https://cameochemicals.noaa.gov/chemical/8514">https://cameochemicals.noaa.gov/chemical/8514</a>				Inhalation, skin absorption, ingestion, skin and/or eye contact	INHALATION: Causes headache, drowsiness, unsteadiness. Irritating to mucous membranes. EYES: Severe irritation. SKIN: Severe irritation. INGESTION: Irritation of gastric mucosa, nausea, vomiting, diarrhea, abdominal cramps and cyanosis.		Colorless liquid. Sinks in water. BP: 343°F Fl.Pt. = 146°F LEL: 2.02% UEL: 9.2%
1,4-Dichlorobenzene	106-46-7	TWA 10 ppm	Ca	TWA 75 ppm (450 mg/m3)	Ca [150 ppm]	Inhalation, skin absorption, ingestion, skin and/or eye contact	Eye irritation, swelling periorbital (situated around the eye); profuse rhinitis; headache, anorexia, nausea, vomiting; weight loss, jaundice, cirrhosis; In Animals: liver, kidney injury; [potential occupational carcinogen]	Liver, respiratory system, eyes, kidneys, skin	Colorless or white crystalline solid with a mothball-like odor. [insecticide] BP: 345°F Fl.Pt. = 150°F LEL: 2.5% UEL: NA Combustible Solid, but may take some effort to ignite.
1,4-Dioxane	123-91-1	TWA 20 ppm [skin]	Ca C 1 ppm (3.6 mg/m3) [30-minute]	TWA 100 ppm (360 mg/m3) [skin]	Ca [500 ppm]	Inhalation, skin absorption, ingestion, skin and/or eye contact	irritation eyes, skin, nose, throat; drowsiness, headache; nausea, vomiting; liver damage; kidney failure; [potential occupational carcinogen]	Eyes, skin, respiratory system, liver, kidneys	Colorless liquid or solid (below 53°F) with a mild, ether-like odor. BP: 214°F Fl.Pt. = 55°F LEL: 2.0% UEL: 22% Class IB Flammable Liquid: Fl.P. below 73°F and BP at or above 100°F
2-Butanone	78-93-3	TWA 200 ppm STEL 300 ppm	TWA 200 ppm (590 mg/m3) ST 300 ppm (885 mg/m3)	TWA 200 ppm (590 mg/m3)	3000 ppm	inhalation, ingestion, skin and/or eye contact	irritation eyes, skin, nose; headache; dizziness; vomiting; dermatitis	Eyes, skin, respiratory system, central nervous system	Colorless liquid with a moderately sharp, fragrant, mint- or acetone-like odor BP: 175°F Fl.Pt. = 16°F LEL (200°F): 1.4% UEL (200°F): 11.4% Class IB Flammable Liquid: Fl.P. below 73°F and BP at or above 100°F

**Table 1. Toxicological, Physical, and Chemical Properties of Compounds Potentially Present at the Site.**

Compound	CAS #	ACGIH TLV	NIOSH REL	OSHA PEL	IDLH	Routes of Exposure	Toxic Properties	Target Organs	Physical/Chemical Properties
2-Hexanone	591-78-6	TWA 5 ppm STEL 10 ppm [skin]	TWA 1 ppm (4 mg/m <sup>3</sup> )	TWA 100 ppm (410 mg/m <sup>3</sup> )	1600 ppm	Inhalation, skin absorption, ingestion, skin and/or eye contact	Irritation eyes, nose; peripheral neuropathy: lassitude (weakness, exhaustion), paresthesia; dermatitis; headache, drowsiness	Eyes, skin, respiratory system, central nervous system, peripheral nervous system	Colorless liquid with an acetone-like odor BP: 262°F Fl.Pt. = 77°F LEL: NA UEL: 8.0% Class IC Flammable Liquid: Fl.P. at or above 73°F and below 100°F
4-Methyl-2-pentanone	108-10-1	TWA 20 ppm STEL 75 ppm	TWA 50 ppm (205 mg/m <sup>3</sup> ) ST 75 ppm (300 mg/m <sup>3</sup> )	TWA 100 ppm (410 mg/m <sup>3</sup> )	500 ppm	Inhalation, ingestion, skin and/or eye contact	Irritation eyes, skin, mucous membrane; headache, narcosis, coma; dermatitis; In Animals: liver, kidney damage	Eyes, skin, respiratory system, central nervous system, liver, kidneys	Colorless liquid with a pleasant odor BP: 242°F Fl.Pt. = 64°F LEL (200°F): 1.2% UEL (200°F): 8.0% Class IB Flammable Liquid: Fl.P. below 73°F and BP at or above 100°F
Acetone	67-64-1	TWA 250 ppm STEL 500 ppm	TWA 250 ppm (590 mg/m <sup>3</sup> )	TWA 1000 ppm (2400 mg/m <sup>3</sup> )	2500 ppm [10% LEL]	Inhalation, ingestion, skin and/or eye contact	Irritation eyes, nose, throat; headache, dizziness, central nervous system depression; dermatitis	Eyes, skin, respiratory system, central nervous system	Colorless liquid with a fragrant, mint-like odor BP: 133°F Fl.Pt. = 0°F LEL: 12.8% UEL: 2.5% Class IB Flammable liquid: Fl.P. below 73°F and BP at or above 100°F.
Benzene	71-43-2	TWA 0.5 ppm STEL 2.5 ppm	Ca TWA 0.1 ppm ST 1 ppm	TWA 1 ppm ST 5 ppm	Ca [500 ppm]	Inhalation, skin absorption, ingestion, skin and/or eye contact	Irritation eyes, skin, nose, respiratory system; dizziness; headache, nausea, staggered gait; anorexia, lassitude (weakness, exhaustion); dermatitis; bone marrow depression; [potential occupational carcinogen]	Eyes, skin, respiratory system, blood, central nervous system, bone marrow	Colorless to light yellow liquid with an aromatic odor [Note: Solid below 42 °F] BP: 176°F Fl.Pt. = 12°F LEL: 1.2% UEL: 7.8% Class IB Flammable liquid. Fl.P. below 73°F and BP at or above 100°F.
Bromochloromethane	74-97-5	TWA 200 ppm	TWA 200 ppm (1050 mg/m <sup>3</sup> )	TWA 200 ppm (1050 mg/m <sup>3</sup> )	2000 ppm	Inhalation, ingestion, skin and/or eye contact	Irritation eyes, skin, throat; confusion, dizziness, central nervous system depression; pulmonary edema	Eyes, skin, respiratory system, liver, kidneys, central nervous system	Colorless to pale-yellow liquid with a chloroform-like odor. [Note: May be used as a fire extinguishing agent.] BP: 155°F Fl.Pt. = NA LEL: NA UEL: NA Noncombustible Liquid
Bromodichloromethane	75-27-4	<a href="https://cameochemicals.noaa.gov/chemical/16064">https://cameochemicals.noaa.gov/chemical/16064</a>				Inhalation, ingestion, skin and/or eye contact	Symptoms of exposure to this compound may include irritation of the skin, eyes, mucous membranes and respiratory tract. It may also cause narcosis. Other symptoms may include nausea, dizziness and headache.	Liver and kidney damage. Central nervous system effects may also occur.	Clear colorless liquid BP: 189°F Fl.Pt. = NA LEL: NA UEL: NA
Bromoform	75-25-2	TWA 0.5 ppm	TWA 0.5 ppm (5 mg/m <sup>3</sup> ) [skin]	TWA 0.5 ppm (5 mg/m <sup>3</sup> ) [skin]	850 ppm	Inhalation, skin absorption, ingestion, skin and/or eye contact	Irritation eyes, skin, respiratory system; central nervous system depression; liver, kidney damage	Eyes, skin, respiratory system, central nervous system, liver, kidneys	Colorless to yellow liquid with a chloroform-like odor. [Note: A solid below 47°F.] BP: 301°F Fl.Pt. = NA LEL: NA UEL: NA Noncombustible Liquid
Bromomethane	74-83-9	TWA 1 ppm [skin]	Ca	C 20 ppm (80 mg/m <sup>3</sup> ) [skin]	Ca [250 ppm]	Inhalation, skin absorption (liquid), skin and/or eye contact (liquid)	Irritation eyes, skin, respiratory system; muscle weak, incoordination, visual disturbance, dizziness; nausea, vomiting, headache; malaise (vague feeling of discomfort); hand tremor; convulsions; dyspnea (breathing difficulty); skin vesiculation; liquid: frostbite; [potential occupational carcinogen]	Eyes, skin, respiratory system, central nervous system	Colorless gas with a chloroform-like odor at high concentrations. [Note: A liquid below 38°F. Shipped as a liquefied compressed gas.] BP: 38°F Fl.Pt. = NA (Gas) LEL: 10% UEL: 16.0% Flammable Gas, but only in presence of a high energy ignition source.
Carbon disulfide	75-15-0	TWA 1 ppm [skin]	TWA 1 ppm (3 mg/m <sup>3</sup> ) ST 10 ppm (30 mg/m <sup>3</sup> ) [skin]	TWA 20 ppm C 30 ppm 100 ppm (30-minute maximum peak)	500 ppm	Inhalation, skin absorption, ingestion, skin and/or eye contact	Dizziness, headache, poor sleep, lassitude (weakness, exhaustion), anxiety, anorexia, weight loss; psychosis; polyneuropathy; Parkinson-like syndrome; ocular changes; coronary heart disease; gastritis; kidney, liver injury; eye, skin burns; dermatitis; reproductive effects	Central nervous system, peripheral nervous system, cardiovascular system, eyes, kidneys, liver, skin, reproductive system	Colorless to faint-yellow liquid with a sweet ether-like odor. [Note: Reagent grades are foul smelling.] BP: 116°F Fl.Pt. = -22°F LEL: 1.3% UEL: 50.0% Class IB Flammable Liquid: Fl.P. below 73°F and BP at or above 100°F.
Carbon tetrachloride	56-23-5	TWA 5 ppm STEL 10 ppm [skin]	Ca ST 2 ppm (12.6 mg/m <sup>3</sup> ) [60-minute]	TWA 10 ppm C 25 ppm 200 ppm (5-minute maximum peak in any 4 hours)	Ca [200 ppm]	Inhalation, skin absorption, ingestion, skin and/or eye contact	Irritation eyes, skin; central nervous system depression; nausea, vomiting; liver, kidney injury; drowsiness, dizziness, incoordination; [potential occupational carcinogen]	Central nervous system, eyes, lungs, liver, kidneys, skin	Colorless liquid with a characteristic ether-like odor BP: 170°F Fl.Pt. = NA LEL: NA UEL: NA Noncombustible Liquid
Chlorobenzene	108-90-7	TWA 10 ppm	NA	TWA 75 ppm (350 mg/m <sup>3</sup> )	1000 ppm	Inhalation, ingestion, skin and/or eye contact	Irritation eyes, skin, nose; drowsiness, incoordination; central nervous system depression; In Animals: liver, lung, kidney injury	Eyes, skin, respiratory system, central nervous system, liver	Colorless liquid with an almond-like odor BP: 270°F Fl.Pt. = 82°F LEL: 1.3% UEL: 9.6% Class IC Flammable Liquid: Fl.P. at or above 73°F and below 100°F.

**Table 1. Toxicological, Physical, and Chemical Properties of Compounds Potentially Present at the Site.**

Compound	CAS #	ACGIH TLV	NIOSH REL	OSHA PEL	IDLH	Routes of Exposure	Toxic Properties	Target Organs	Physical/Chemical Properties
Chloroethane	75-00-3	TWA 100 ppm [skin]	Handle with caution in the workplace	TWA 1000 ppm (2600 mg/m <sup>3</sup> )	3800 ppm [10%LEL]	Inhalation, skin absorption (liquid), ingestion (liquid), skin and/or eye contact	Incoordination, inebriation; abdominal cramps; cardiac arrhythmias, cardiac arrest; liver, kidney damage	Liver, kidneys, respiratory system, cardiovascular system, central nervous system	Colorless gas or liquid (below 54°F) with a pungent, ether-like odor. [Note: Shipped as a liquefied compressed gas.] BP: 54°F Fl.Pt. = NA (gas), -58°F (liquid) LEL: 3.8% UEL: 15.4% Flammable Gas
Chloroform	67-66-3	TWA 10 ppm	Ca ST 2 ppm (9.78 mg/m <sup>3</sup> ) [60-minute]	C 50 ppm (240 mg/m <sup>3</sup> )	Ca [500 ppm]	Inhalation, skin absorption, ingestion, skin and/or eye contact	Irritation eyes, skin; dizziness, mental dullness, nausea, confusion; headache, lassitude (weakness, exhaustion); anesthesia; enlarged liver; [potential occupational carcinogen]	Liver, kidneys, heart, eyes, skin, central nervous system	Colorless liquid with a pleasant odor BP: 143°F Fl.Pt. = -82°F LEL: NA UEL: NA Noncombustible Liquid
Chloromethane	74-87-3	TWA 50 ppm STEL 100 ppm	Ca	TWA 100 ppm C 200 ppm 300 ppm (5-minute maximum peak in any 3 hours)	Ca [2000 ppm]	Inhalation, skin and/or eye contact (liquid)	Dizziness, nausea, vomiting; visual disturbance, stagger, slurred speech, convulsions, coma; liver, kidney damage; liquid: frostbite; reproductive, teratogenic effects; [potential occupational carcinogen]	Central nervous system, liver, kidneys, reproductive system	Colorless gas with a faint, sweet odor which is not noticeable at dangerous concentrations. [Note: Shipped as a liquefied compressed gas.] BP: -12°F Fl.Pt. = NA (Gas) LEL: 8.1% UEL: 17.4% Flammable Gas
cis-1,2-Dichloroethene	156-59-2	TWA 200 ppm (All isomers)	TWA 200 ppm (790 mg/m <sup>3</sup> )	TWA 200 ppm (790 mg/m <sup>3</sup> )	1000 ppm	Inhalation, ingestion, skin and/or eye contact	Irritation eyes, respiratory system; central nervous system depression	Eyes, respiratory system, central nervous system	Colorless liquid (usually a mixture of the cis & trans isomers) with a slightly acrid, chloroform-like odor. BP: 118-140°F Fl.Pt. = 36-39°F LEL: 5.6% UEL: 12.8% Class IB Flammable Liquid: Fl.P. below 73°F and BP at or above 100°F
cis-1,3-Dichloropropene	10061-01-5	<a href="https://cameochemicals.noaa.gov/chemical/20168">https://cameochemicals.noaa.gov/chemical/20168</a>				Inhalation, ingestion, skin and/or eye contact	Symptoms of exposure to this compound may include local irritation of the eyes skin and respiratory tract; dermatitis, gasping, coughing, substernal pain, extreme respiratory distress, lacrimation, central nervous system depression, skin irritation, acute gastrointestinal distress with pulmonary congestion and edema. It also may cause injury to the liver, kidneys and heart.	Skin, eyes, mucous membranes, liver, kidney, heart	Colorless to amber liquid with a sweetish odor. BP: 219.7°F Fl.Pt. = NA LEL: NA UEL: NA
Cyclohexane	110-82-7	TWA 100 ppm	TWA 300 ppm (1050 mg/m <sup>3</sup> )	TWA 300 ppm (1050 mg/m <sup>3</sup> )	1300 ppm [10%LEL]	Inhalation, ingestion, skin and/or eye contact	Irritation eyes, skin, respiratory system; drowsiness; dermatitis; narcosis, coma	Eyes, skin, respiratory system, central nervous system	Colorless liquid with a sweet, chloroform-like odor. [Note: A solid below 44°F.] BP: 177°F Fl.Pt. = 0°F LEL: 1.3% UEL: 8.0% Class IB Flammable Liquid: Fl.P. below 73°F and BP at or above 100°F.
Dibromochloromethane	124-48-1	<a href="https://cameochemicals.noaa.gov/chemical/16183">https://cameochemicals.noaa.gov/chemical/16183</a>				Inhalation, ingestion, skin and/or eye contact	Symptoms of exposure to this compound may include irritation of the skin, eyes, mucous membranes and upper respiratory tract. It may also cause fatigue. Other symptoms may include central nervous system effects, lung and cornea irritation and liver and kidney damage. Prolonged exposure can cause nausea, dizziness, headache and narcosis.	Skin, eyes, mucous membranes, upper respiratory tract	Clear colorless to yellow-orange liquid BP: 246-248°F Fl.Pt. = Greater than 200°F LEL: NA UEL: NA
Dichlorodifluoromethane	75-71-8	TWA 1000 ppm	TWA 1000 ppm (4950 mg/m <sup>3</sup> )	TWA 1000 ppm (4950 mg/m <sup>3</sup> )	15,000 ppm	Inhalation, skin and/or eye contact (liquid)	Dizziness, tremor, asphyxia, unconsciousness, cardiac arrhythmias, cardiac arrest; liquid: frostbite	Cardiovascular system, peripheral nervous system	Colorless gas with an ether-like odor at extremely high concentrations. [Note: Shipped as a liquefied compressed gas.] BP: -22°F Fl.Pt. = NA LEL: NA UEL: NA Nonflammable Gas
Ethyl benzene	100-41-4	TWA 20 ppm	TWA 100 ppm (435 mg/m <sup>3</sup> ) ST 125 ppm (545 mg/m <sup>3</sup> )	TWA 100 ppm (435 mg/m <sup>3</sup> )	800 ppm [10%LEL]	Inhalation, ingestion, skin and/or eye contact	Irritation eyes, skin, mucous membrane; headache; dermatitis; narcosis, coma	Eyes, skin, respiratory system, central nervous system	Colorless liquid with an aromatic odor. BP: 277°F Fl.Pt. = 55°F LEL: 0.8% UEL: 6.7% Class IB Flammable Liquid below 73°F and BP at or above 100°F
Isopropyl benzene	98-82-8	TWA 5 ppm	TWA 50 ppm (245 mg/m <sup>3</sup> ) [skin]	TWA 50 ppm (245 mg/m <sup>3</sup> ) [skin]	900 ppm [10%LEL]	Inhalation, skin absorption, ingestion, skin and/or eye contact	Irritation eyes, skin, mucous membrane; dermatitis; headache, narcosis, coma	Eyes, skin, respiratory system, central nervous system	Colorless liquid with a sharp, penetrating, aromatic odor BP: 306°F Fl.Pt. = 96°F LEL: 0.9% UEL: 6.5% Class IC Flammable Liquid: Fl.P. at or above 73°F and below 100°F
Methyl Acetate	79-20-9	TWA 200 ppm STEL 250 ppm	TWA 200 ppm (610 mg/m <sup>3</sup> ) ST 250 ppm (760 mg/m <sup>3</sup> )	TWA 200 ppm (610 mg/m <sup>3</sup> )	3100 ppm [10%LEL]	Inhalation, ingestion, skin and/or eye contact	Irritation eyes, skin, nose, throat; headache, drowsiness; optic nerve atrophy; chest tightness; In Animals: narcosis	Eyes, skin, respiratory system, central nervous system	Colorless liquid with a fragrant, fruity odor BP: 135°F Fl.Pt. = 14°F LEL: 3.1% UEL: 16% Class IB Flammable Liquid: Fl.P. below 73°F and BP at or above 100°F.

**Table 1. Toxicological, Physical, and Chemical Properties of Compounds Potentially Present at the Site.**

Compound	CAS #	ACGIH TLV	NIOSH REL	OSHA PEL	IDLH	Routes of Exposure	Toxic Properties	Target Organs	Physical/Chemical Properties
Methylcyclohexane	108-87-2	TWA 400 ppm	TWA 400 ppm (1600 mg/m3)	TWA 500 ppm (2000 mg/m3)	1200 ppm [LEL]	Inhalation, ingestion, skin and/or eye contact	Irritation eyes, skin, nose, throat; dizziness, drowsiness; In Animals: narcosis	Eyes, skin, respiratory system, central nervous system	Colorless liquid with a faint, benzene-like odor BP: 214°F Fl.Pt. = 25°F LEL: 1.2% UEL: 6.7% Class IB Flammable Liquid: Fl.P. below 73°F and BP at or above 100°F.
Methylene chloride	75-09-2	TWA 50 ppm [skin] STEL 100 ppm	Ca	[1910.1052] TWA 25 ppm ST 125 ppm	Ca [2300 ppm]	Inhalation, skin absorption, ingestion, skin and/or eye contact	Irritation eyes, skin; lassitude (weakness, exhaustion), drowsiness, dizziness; numb, tingle limbs; nausea; [potential occupational carcinogen]	Eyes, skin, cardiovascular system, central nervous system	Colorless liquid with a chloroform-like odor. [Note: A gas above 104°F.] BP: 104°F Fl.Pt. = NA LEL: 13% UEL: 23% Combustible Liquid
Methyl-t-butyl ether	1634-04-4	TWA 50 ppm	NA	NA	NA	Inhalation, skin absorption, ingestion, skin and/or eye contact	May cause dizziness or suffocation. Contact may irritate or burn eyes or skin. May be harmful if swallowed.	Eyes, skin	A colorless liquid with a distinctive anesthetic like odor. BP: 131°F Fl.Pt. = -14°F LEL: NA UEL: NA
o-Xylene	95-47-6	TWA 20 ppm (All isomers)	TWA 100 ppm (435 mg/m3) ST 150 ppm (655 mg/m3)	TWA 100 ppm (435 mg/m3)	900 ppm	Inhalation, skin absorption, ingestion, skin and/or eye contact	Irritation eyes, skin, nose, throat; dizziness, excitement, drowsiness, incoordination, staggering gait; corneal vacuolization; anorexia, nausea, vomiting, abdominal pain; dermatitis	Eyes, skin, respiratory system, central nervous system, gastrointestinal tract, blood, liver, kidneys	Colorless liquid with an aromatic odor BP: 292°F Fl.Pt. = 90°F LEL: 0.9% UEL: 6.7% Class IC Flammable Liquid: Fl.P. at or above 73°F and below 100°F
Styrene	100-42-5	TWA 10 ppm STEL 20 ppm OTO (ototoxicant)	TWA 50 ppm (215 mg/m3) ST 100 ppm (425 mg/m3)	TWA 100 ppm C 200 ppm 600 ppm (5-minute maximum peak in any 3 hours)	700 ppm	Inhalation, skin absorption, ingestion, skin and/or eye contact	Irritation eyes, nose, respiratory system; headache, lassitude (weakness, exhaustion), dizziness, confusion, malaise (vague feeling of discomfort), drowsiness, unsteady gait; narcosis; defatting dermatitis; possible liver injury; reproductive effects	Eyes, skin, respiratory system, central nervous system, liver, reproductive system	Colorless to yellow, oily liquid with a sweet, floral odor BP: 293°F Fl.Pt. = 88°F LEL: 0.9% UEL: 6.8% Class IC Flammable Liquid: Fl.P. at or above 73°F and below 100°F
Tetrachloroethene	127-18-4	TWA 25 ppm STEL 100 ppm	Ca Minimize workplace exposure concentrations	TWA 100 ppm C 200 ppm (for 5 minutes in any 3-hour period), with a maximum peak of 300 ppm	Ca [150 ppm]	Inhalation, skin absorption, ingestion, skin and/or eye contact	Irritation eyes, skin, nose, throat, respiratory system; nausea; flush face, neck; dizziness, incoordination; headache, drowsiness; skin erythema (skin redness); liver damage; [potential occupational carcinogen]	Eyes, skin, respiratory system, liver, kidneys, central nervous system	Colorless liquid with a mild, chloroform-like odor BP: 250°F Fl.Pt. = NA LEL: NA UEL: NA Noncombustible Liquid, but decomposes in a fire to hydrogen chloride and phosgene
Sodium Hydroxide	1310-73-2	Ceiling 2 mg/m <sup>3</sup>	C 2 mg/m <sup>3</sup>	TWA 2 mg/m <sup>3</sup>	10 mg/m <sup>3</sup>	Inhalation, ingestion, skin and/or eye contact	Irritation eyes, skin, mucous membrane; pneumonitis; eye, skin burns; temporary loss of hair	Eyes, skin, respiratory system	Colorless to white, odorless solid (flakes, beads, granular form). BP: 2534°F Fl.Pt. = NA LEL: NA UEL: NA Noncombustible Solid, but when in contact with water may generate sufficient heat to ignite combustible materials.
Sulfuric Acid	7664-93-9	TWA 0.2 mg/m <sup>3</sup> (as thoracic particulate mass)	TWA 1 mg/m <sup>3</sup>	TWA 1 mg/m <sup>3</sup>	15 mg/m <sup>3</sup>	Inhalation, ingestion, skin and/or eye contact	Irritation eyes, skin, nose, throat; pulmonary edema, bronchitis; emphysema; conjunctivitis; stomatis; dental erosion; eye, skin burns; dermatitis	Eyes, skin, respiratory system, teeth	Colorless to dark-brown, oily, odorless liquid. [Note: Pure compound is a solid below 51°F. Often used in an aqueous solution.] BP = 554°F Fl.Pt. = NA LEL = NA UEL = NA Noncombustible Liquid, but capable of igniting finely divided combustible materials.
trans-1,2-Dichloroethene	156-60-5	200 ppm (All isomers)	TWA 200 ppm (790 mg/m3)	TWA 200 ppm (790 mg/m3)	1000 ppm	Inhalation, ingestion, skin and/or eye contact	Irritation eyes, respiratory system; central nervous system depression	Eyes, respiratory system, central nervous system	Colorless liquid (usually a mixture of the cis & trans isomers) with a slightly acrid, chloroform-like odor. BP: 118-140°F Fl.P: 36-39°F LEL: 5.6% UEL: 12.8% Class IB Flammable Liquid Fl.P. below 73°F and BP at or above 100°F.
trans-1,3-Dichloropropene	10061-02-6	<a href="https://cameochemicals.noaa.gov/chemical/18110">https://cameochemicals.noaa.gov/chemical/18110</a>				Inhalation, ingestion, skin and/or eye contact	Symptoms of exposure to this compound may include local irritation of the eyes skin and respiratory tract, dermatitis, gasping, coughing, substernal pain, extreme respiratory distress, lacrimation, central nervous system depression, acute gastrointestinal distress with pulmonary congestion and edema. It may also cause injury to the liver, kidneys and heart	Skin, eyes, mucous membranes, liver, kidney, heart	A clear colorless liquid with chloroform odor BP: 234°F Fl.P: NA LEL: NA UEL: NA

**Table 1. Toxicological, Physical, and Chemical Properties of Compounds Potentially Present at the Site.**

Compound	CAS #	ACGIH TLV	NIOSH REL	OSHA PEL	IDLH	Routes of Exposure	Toxic Properties	Target Organs	Physical/Chemical Properties
Toluene	108-88-3	TWA 20 ppm (ototoxicant)	TWA 100 ppm (375 mg/m <sup>3</sup> ) ST 150 ppm (560 mg/m <sup>3</sup> )	TWA 200 ppm C 300 ppm 500 ppm (10-minute maximum peak)	500 ppm	Inhalation, skin absorption, ingestion, skin and/or eye contact	Irritation eyes, nose; lassitude (weakness, exhaustion), confusion, euphoria, dizziness, headache; dilated pupils, lacrimation (discharge of tears); anxiety, muscle fatigue, insomnia; paresthesia; dermatitis; liver, kidney damage	Eyes, skin, respiratory system, central nervous system, liver, kidneys	Colorless liquid with a sweet, pungent, benzene-like odor. BP: 232°F Fl.P: 40°F LEL: 1.1% UEL: 7.1% Class IB Flammable Liquid Fl.P. below 73°F and BP at or above 100°F.
Trichloroethene (TCE)	79-01-6	TWA 10 ppm STEL 25 ppm	Ca	TWA 100 ppm C 200 ppm 300 ppm (5-minute maximum peak in any 2 hours)	Ca [1000 ppm]	Inhalation, skin absorption, ingestion, skin and/or eye contact	Irritation eyes, skin; headache, visual disturbance, lassitude (weakness, exhaustion), dizziness, tremor, drowsiness, nausea, vomiting; dermatitis; cardiac arrhythmias, paresthesia; liver injury; [potential occupational carcinogen]	Eyes, skin, respiratory system, heart, liver, kidneys, central nervous system	Colorless liquid (unless dyed blue) with a chloroform-like odor. BP: 189°F Fl.Pt. = NA LEL(77°F): 8.0% UEL(77°F): 10.5% Combustible Liquid, but burns with difficulty.
Trichlorofluoromethane	75-69-4	STEL C 1000 ppm	C 1000 ppm (5600 mg/m <sup>3</sup> )	TWA 1000 ppm (5600 mg/m <sup>3</sup> )	2000 ppm	Inhalation, ingestion, skin and/or eye contact	Incoordination, tremor; dermatitis; cardiac arrhythmias, cardiac arrest; asphyxia; liquid: frostbite	Skin, respiratory system, cardiovascular system	Colorless to water-white, nearly odorless liquid or gas (above 75°F) BP: 75°F Fl.P: NA LEL: NA UEL: NA Noncombustible Liquid Nonflammable Gas
Vinyl Chloride (chloroethylene)	75-01-4	TWA 1 ppm	Ca	TWA 1 ppm C 5 ppm [15-minute]	Ca (ND)	Inhalation, skin and/or eye contact (liquid)	Lassitude (weakness, exhaustion); abdominal pain, gastrointestinal bleeding; enlarged liver; pallor or cyanosis of extremities; liquid: frostbite; [potential occupational carcinogen]	Liver, central nervous system, blood, respiratory system, lymphatic system	Colorless gas or liquid (below 7°F) with a pleasant odor at high concentrations. [Note: Shipped as a liquefied compressed gas.] BP: 7°F Fl.Pt. = NA (Gas) LEL: 3.6% UEL: 33.0% Flammable Gas
Xylene (m, o & p isomers)	108-38-3, 95-47-6, 106-42-3	TWA 20 ppm	NA	NA	NA	Inhalation, skin absorption, ingestion, skin and/or eye contact	Irritation eyes, skin, nose, throat; dizziness, excitement, drowsiness, incoordination, staggering gait; corneal vacuolization; anorexia, nausea, vomiting, abdominal pain; dermatitis	Eyes, skin, respiratory system, central nervous system, gastrointestinal tract, blood, liver, kidneys	Colorless liquid with an aromatic odor BP: 282°F, 292°F, 281°F Fl. Pt. 82°F, 90°F, 81°F LEL: 1.1%, 0.9%, 1.1% UEL: 7.0%, 6.7%, 7.0% Class IC Flammable Liquid at or above 73°F and below 100°F.
Zinc Oxide (dust)	7440-66-6	TWA 2 mg/m <sup>3</sup> (respirable) STEL 10 mg/m <sup>3</sup> (respirable)	TWA 5 mg/m <sup>3</sup> C 15 mg/m <sup>3</sup>	TWA 15 mg/m <sup>3</sup> (total dust) TWA 5 mg/m <sup>3</sup> (resp dust) TWA 5 mg/m <sup>3</sup> (fume)	500 mg/m <sup>3</sup>	Inhalation	Metal fume fever: chills, muscle ache, nausea, fever, dry throat, cough; lassitude (weakness, exhaustion); metallic taste; headache; blurred vision; low back pain; vomiting; malaise (vague feeling of discomfort); chest tightness; dyspnea (breathing difficulty), rales, decreased pulmonary function	Respiratory system	White, odorless solid. BP: NA Fl.Pt. = NA LEL: NA UEL: NA Noncombustible Solid
<b>SEMI-VOLATILE ORGANIC COMPOUNDS (SVOCs)</b>									
2-Chloronaphthalene	91-58-7	<a href="https://cameochemicals.noaa.gov/chemical/16185">https://cameochemicals.noaa.gov/chemical/16185</a>				Inhalation, ingestion, skin and/or eye contact	Chloracne, cysts, headache, fatigue, vertigo, anorexia and jaundice		Monoclinic plates or off-white crystalline powder BP: NA Fl.Pt. = NA LEL: NA UEL: NA
2-Methylnaphthalene	91-57-6	TWA 0.5 ppm TLV-SL 3 mg/100 cm <sup>2</sup> [skin]	<a href="https://cameochemicals.noaa.gov/chemical/20668">https://cameochemicals.noaa.gov/chemical/20668</a>			Inhalation, ingestion, skin and/or eye contact	Headaches, nausea, vomiting, diarrhea, anemia, jaundice, euphoria, dermatitis, visual disturbances, convulsions and comatose	Skin, eyes, mucous membranes and upper respiratory tract	White crystalline solid Combustible solid BP: 466-468 ° F Fl.Pt. = 208 ° F LEL: NA UEL: NA
Acenaphthene	83-32-9	<a href="https://cameochemicals.noaa.gov/chemical/10358">https://cameochemicals.noaa.gov/chemical/10358</a>				Inhalation, ingestion, skin and/or eye contact	Irritation of the skin, eyes, mucous membranes and upper respiratory tract, vomiting	Skin, eyes, mucous membranes and upper respiratory tract	White needles BP: 534 ° F Fl.Pt. = NA LEL: 0.6% UEL: NA
Acenaphthylene	208-96-8	<a href="https://cameochemicals.noaa.gov/chemical/16157">https://cameochemicals.noaa.gov/chemical/16157</a>				Inhalation, ingestion, skin and/or eye contact			Colorless crystalline solid BP: 509 to 527 ° F at 760 mm Hg Fl.Pt. = NA LEL: NA UEL: NA
Anthracene (as coal tar pitch volatiles)	120-12-7	TWA 0.2 mg/m <sup>3</sup> (as Benzene solubles)	Ca TWA 0.1 mg/m <sup>3</sup> (cyclohexane-extractable fraction)	TWA 0.2 mg/m <sup>3</sup> (benzene-soluble fraction) [1910.1002]	Ca [80 mg/m <sup>3</sup> ]	Inhalation, skin and/or eye contact	Dermatitis, bronchitis, [potential occupational carcinogen]	Respiratory system, skin, bladder, kidneys	Black or dark-brown amorphous residue BP: NA Fl.Pt. = NA LEL: NA UEL: NA Combustible Solids
Benzo[a]anthracene	56-55-3	<a href="https://cameochemicals.noaa.gov/chemical/16171">https://cameochemicals.noaa.gov/chemical/16171</a>				Inhalation, ingestion, skin and/or eye contact			Colorless leaflets or plates or coarse gold powder with a greenish-yellow fluorescence. May reasonably be expected to be a carcinogen. BP: 815° F at 760 mm Hg Fl.Pt. = NA LEL: NA UEL: NA

**Table 1. Toxicological, Physical, and Chemical Properties of Compounds Potentially Present at the Site.**

Compound	CAS #	ACGIH TLV	NIOSH REL	OSHA PEL	IDLH	Routes of Exposure	Toxic Properties	Target Organs	Physical/Chemical Properties
Benzo[a]pyrene (as coal tar pitch volatiles)	50-32-8	TWA 0.2 mg/m3 (as Benzene solubles)	Ca TWA 0.1 mg/m3 (cyclohexane-extractable fraction)	TWA 0.2 mg/m3 (benzene-soluble fraction) [1910.1002]	Ca [80 mg/m3]	Inhalation, skin and/or eye contact	Dermatitis, bronchitis, [potential occupational carcinogen]	Respiratory system, skin, bladder, kidneys	Black or dark-brown amorphous residue BP: NA Fl.Pt. = NA LEL: NA UEL: NA Combustible Solids
Benzo[b]fluoranthene	205-99-2	None listed	<a href="https://cameochemicals.noaa.gov/chemical/16172">https://cameochemicals.noaa.gov/chemical/16172</a>			Inhalation, injection, skin and/or eye contact			Needles or yellow fluffy powder BP: NA Fl.Pt. = NA LEL: NA UEL: NA
Benzo[g,h,i]perylene	191-24-2	<a href="https://cameochemicals.noaa.gov/chemical/16174">https://cameochemicals.noaa.gov/chemical/16174</a>				Inhalation, injection, skin and/or eye contact	Inhalation of material may be harmful. Contact may cause burns to skin and eyes. Inhalation of Asbestos dust may have a damaging effect on the lungs. Fire may produce irritating, corrosive and/or toxic gases. Some liquids produce vapors that may cause dizziness or suffocation. Runoff from fire control may cause pollution.	Lungs, skin, eyes	Colorless to white crystalline solid. Water insoluble. BP: NA Fl.Pt. = NA LEL: NA UEL: NA
Benzo[k]fluoranthene	207-08-9	<a href="https://cameochemicals.noaa.gov/chemical/16173">https://cameochemicals.noaa.gov/chemical/16173</a>				Inhalation, injection, skin and/or eye contact	When heated to decomposition this compound emits acrid smoke and irritating fumes.		Pale yellow needles or yellow crystalline solid BP: 896° F Fl.Pt. = NA LEL: NA UEL: NA
Chrysene (as coal tar pitch volatiles)	218-01-9	TWA 0.2 mg/m3 (as Benzene solubles)	Ca TWA 0.1 mg/m3 (cyclohexane-extractable fraction)	TWA 0.2 mg/m3 (benzene-soluble fraction) [1910.1002]	Ca [80 mg/m3]	Inhalation, skin and/or eye contact	Dermatitis, bronchitis, [potential occupational carcinogen]	Respiratory system, skin, bladder, kidneys	Black or dark-brown amorphous residue BP: NA Fl.Pt. = NA LEL: NA UEL: NA Combustible Solids
Dibenzo(a,h)anthracene	53-70-3	<a href="https://cameochemicals.noaa.gov/chemical/16192">https://cameochemicals.noaa.gov/chemical/16192</a>				Inhalation, injection, skin and/or eye contact	Symptoms of exposure to this compound may include irritation. This compound is harmful if swallowed or inhaled. It may cause irritation. When heated to decomposition it emits acrid smoke, irritating fumes and toxic fumes of carbon monoxide and carbon dioxide.	Lungs	White crystals or pale yellow solid. Sublimes BP: 975° F Fl.Pt. = NA LEL: NA UEL: NA
Fluoranthene	206-44-0	<a href="https://cameochemicals.noaa.gov/chemical/16213">https://cameochemicals.noaa.gov/chemical/16213</a>				Inhalation, injection, skin and/or eye contact	When heated to decomposition this compound emits acrid smoke and fumes.		Light yellow fine crystals BP: 482° F Fl.Pt. = NA LEL: NA UEL: NA
Fluorene	86-73-7	<a href="https://cameochemicals.noaa.gov/chemical/16214">https://cameochemicals.noaa.gov/chemical/16214</a>				Inhalation, injection, skin and/or eye contact			White leaflets. Sublimes easily under a vacuum. Fluorescent when impure. BP: 563° F Fl.Pt. = NA LEL: NA UEL: NA
Indeno[1,2,3-cd]pyrene	193-39-5	<a href="https://cameochemicals.noaa.gov/chemical/16218">https://cameochemicals.noaa.gov/chemical/16218</a>				Inhalation, injection, skin and/or eye contact			Yellow crystals BP: 997° F Fl.Pt. = NA LEL: NA UEL: NA
Naphthalene	91-20-3	TWA 10 ppm [skin]	TWA 10 ppm (50 mg/m3) ST 15 ppm (75 mg/m3)	TWA 10 ppm (50 mg/m3)	250 ppm	Inhalation, skin absorption, ingestion, skin and/or eye contact	Irritation eyes; headache, confusion, excitement, malaise (vague feeling of discomfort); nausea, vomiting, abdominal pain; irritation bladder; profuse sweating; jaundice; hematuria (blood in the urine), renal shutdown; dermatitis, optical neuritis, corneal damage	Eyes, skin, blood, liver, kidneys, central nervous system	Colorless to brown solid with an odor of mothballs. [Note: Shipped as a molten solid.] BP: 424°F Fl.Pt.: 174°F LEL: 0.9% UEL: 5.9% Combustible Solid, but will take some effort to ignite
Phenanthrene	85-01-8	<a href="https://cameochemicals.noaa.gov/chemical/16236">https://cameochemicals.noaa.gov/chemical/16236</a>				Inhalation, injection, skin and/or eye contact	Symptoms following exposure to this compound may include skin sensitization, dermatitis, bronchitis, cough, dyspnea, respiratory neoplasm, kidney neoplasm, skin irritation, and respiratory irritation.	Skin, respiratory tract	Colorless monoclinic crystals with a faint aromatic odor. Solutions exhibit a blue fluorescence. BP: 642° F Fl.Pt. = 340° F LEL: NA UEL: NA
Pyrene (see coal tar pitch volatiles)	129-00-0	TWA 0.2 mg/m3 (as Benzene solubles)	Ca TWA 0.1 mg/m3 (cyclohexane-extractable fraction)	TWA 0.2 mg/m3 (benzene-soluble fraction) [1910.1002]	Ca [80 mg/m3]	Inhalation, skin and/or eye contact	Dermatitis, bronchitis, [potential occupational carcinogen]	Respiratory system, skin, bladder, kidneys	Black or dark-brown amorphous residue BP: NA Fl.Pt. = NA LEL: NA UEL: NA Combustible Solids
<b>METALS</b>									
Aluminum	7429-90-5	TWA 1 mg/m3	TWA 10 mg/m <sup>3</sup> (total) TWA 5 mg/m <sup>3</sup> (resp)	TWA 15 mg/m <sup>3</sup> (total) TWA 5 mg/m <sup>3</sup> (resp)	N.D.	Inhalation, skin and/or eye contact	Irritation eyes, skin, respiratory system	Eyes, skin, respiratory system	Silvery-white, malleable, ductile, odorless metal BP: 4221°F Fl.Pt. = NA LEL: NA UEL: NA Combustible Solid, finely divided dust is easily ignited; may cause explosions.



**Table 1. Toxicological, Physical, and Chemical Properties of Compounds Potentially Present at the Site.**

Compound	CAS #	ACGIH TLV	NIOSH REL	OSHA PEL	IDLH	Routes of Exposure	Toxic Properties	Target Organs	Physical/Chemical Properties
Antimony	7440-36-0	TWA 0.5 mg/m <sup>3</sup> (as Sb)	TWA 0.5 mg/m <sup>3</sup> [*Note: The REL also applies to other antimony compounds (as Sb).]	TWA 0.5 mg/m <sup>3</sup> [*Note: The PEL also applies to other antimony compounds (as Sb).]	50 mg/m <sup>3</sup> (as Sb)	Inhalation, ingestion, skin and/or eye contact	Irritation eyes, skin, nose, throat, mouth; cough; dizziness; headache; nausea, vomiting, diarrhea; stomach cramps; insomnia; anorexia; unable to smell properly	Eyes, skin, respiratory system, cardiovascular system	Silver-white, lustrous, hard, brittle solid; scale-like crystals; or a dark-gray, lustrous powder BP: 2975°F Fl.Pt. = NA LEL: NA UEL: NA Noncombustible Solid in bulk form, but a moderate explosion hazard in the form of dust when exposed to flame.
Arsenic	7440-38-2	TWA 0.01 mg/m <sup>3</sup>	Ca C 0.002 mg/m <sup>3</sup> [15-minute]	[1910.1018] TWA 0.010 mg/m <sup>3</sup>	Ca [5 mg/m <sup>3</sup> (as As)]	Inhalation, skin absorption, skin and/or eye contact, ingestion	Ulceration of nasal septum, dermatitis, gastrointestinal disturbances, peripheral neuropathy, resp irritation, hyperpigmentation of skin, [potential occupational carcinogen]	Liver, kidneys, skin, lungs, lymphatic system	Metal: Silver-gray or tin-white, brittle, odorless solid BP: Sublimes Fl.Pt. = NA LEL: NA UEL: NA Metal: Noncombustible Solid in bulk form, but a slight explosion hazard in the form of dust when exposed to flame
Barium	7440-39-3	TWA 0.5 mg/m <sup>3</sup>	0.5 mg Ba/m <sup>3</sup> TWA	0.5 mg Ba/m <sup>3</sup> TWA	50 mg Ba/m <sup>3</sup>	Inhalation, ingestion, skin and/or eye contact	Inhalation or contact with vapors, substance or decomposition products may cause severe injury or death. Contact may cause burns to skin, eyes, and mucous membranes. May be toxic by ingestion, inhalation and skin absorption. Used to make other chemicals.	Lungs, skin, eyes, and mucous membrane	A silver to white metallic solid BP: 1337°F Fl.Pt. = NA LEL: NA UEL: NA
Beryllium	7440-41-7	TWA 0.00005 mg/m <sup>3</sup>	Ca C 0.0005 mg/m <sup>3</sup>	TWA 0.002 mg/m <sup>3</sup> C 0.005 mg/m <sup>3</sup> 0.025 mg/m <sup>3</sup> [30-minute maximum peak]	Ca [4 mg/m <sup>3</sup> (as Be)]	Inhalation, skin and/or eye contact	Berylliosis (chronic exposure): anorexia, weight loss, lassitude (weakness, exhaustion), chest pain, cough, clubbing of fingers, cyanosis, pulmonary insufficiency; irritation eyes; dermatitis; [potential occupational carcinogen]	Eyes, skin, respiratory system	Hard, brittle, gray-white solid BP: 4532°F Fl.Pt. = NA LEL: NA UEL: NA Noncombustible Solid in bulk form, but a slight explosion hazard in the form of a powder or dust.
Cadmium	7440-43-9	TWA 0.01 mg/m <sup>3</sup> total dust TWA 0.002 mg/m <sup>3</sup> (as Cd) respirable fraction	Ca	TWA 0.005 mg/m <sup>3</sup>	Ca [9 mg/m <sup>3</sup> (as Cd)]	Inhalation, ingestion	Pulmonary edema, dyspnea (breathing difficulty), cough, chest tightness, substernal (occurring beneath the sternum) pain; headache; chills, muscle aches; nausea, vomiting, diarrhea; anosmia (loss of the sense of smell), emphysema, proteinuria, mild anemia; [potential occupational carcinogen]	Respiratory system, kidneys, prostate, blood	Silver-white/blue tinged lustrous, odorless solid. BP: 1409°F Fl.Pt. = NA LEL: NA UEL: NA Noncombustible - will burn in powder form
Calcium	7440-70-2	<a href="https://cameochemicals.noaa.gov/chemical/309">https://cameochemicals.noaa.gov/chemical/309</a>				Inhalation, ingestion, skin and/or eye contact	Contact with eyes or skin produces caustic burns.	Eyes, skin	A silvery, soft metal that turns grayish white on exposure to air. BP: 2714°F Fl.Pt. = NA LEL: NA UEL: NA
Chromium	7440-47-3	TWA 0.5 mg/m <sup>3</sup> (metal) TWA 0.003 mg/m <sup>3</sup> (water-soluble Cr III compounds) TWA 0.0002 mg/m <sup>3</sup> (water-soluble Cr VI compounds) STEL 0.0005 mg/m <sup>3</sup> (water-soluble Cr VI compounds)	TWA 0.5 mg/m <sup>3</sup>	TWA 1 mg/m <sup>3</sup>	250 mg/m <sup>3</sup> (as Cr)	Inhalation, ingestion, skin and/or eye contact	Irritation eyes, skin; lung fibrosis (histologic)	Eyes, skin, respiratory system	Blue-white to steel-gray, lustrous, brittle, hard, odorless solid. BP: 4788°F Fl.Pt. = NA LEL: NA UEL: NA Noncombustible - will burn in dust form if heated in a flame
Cobalt	7440-48-4	TWA 0.02 mg/m <sup>3</sup> [DSEN] [RSEN]	TWA 0.05 mg/m <sup>3</sup>	TWA 0.1 mg/m <sup>3</sup>	20 mg/m <sup>3</sup> (as Co)	Inhalation, ingestion, skin and/or eye contact	Cough, dyspnea (breathing difficulty), wheezing, decreased pulmonary function; weight loss; dermatitis; diffuse nodular fibrosis; resp hypersensitivity, asthma	Skin, respiratory system	Odorless, silver-gray to black solid BP: 5612°F Fl.Pt. = NA LEL: NA UEL: NA Noncombustible Solid in bulk form, but finely divided dust will burn at high temperatures.
Copper	7440-50-8	TWA 0.2 mg/m <sup>3</sup> (fume) TWA 1 mg/m <sup>3</sup> (dusts and mists)	TWA 1 mg/m <sup>3</sup>	TWA 1 mg/m <sup>3</sup>	100 mg/m <sup>3</sup> (as Cu)	Inhalation, ingestion, skin and/or eye contact	Irritation eyes, nose, pharynx; nasal septum perforation; metallic taste; dermatitis; In Animals: lung, liver, kidney damage; anemia	Eyes, skin, respiratory system, liver, kidneys (increased risk with Wilson's disease)	Reddish, lustrous, malleable, odorless solid. BP: 4703°F Fl.Pt. = NA LEL: NA UEL: NA Noncombustible - powdered form may ignite
Iron (as iron oxide)	7439-89-6	TWA 5 mg/m <sup>3</sup> (respirable particulate mass)	TWA 1 mg/m <sup>3</sup>	NA	NA	Inhalation, ingestion, skin and/or eye contact	Irritation eyes, skin, mucous membrane; abdominal pain, diarrhea, vomiting; possible liver damage	Eyes, skin, respiratory system, liver, gastrointestinal tract	Appearance and odor vary depending upon the specific soluble iron salt. BP: NA Fl.Pt. = NA LEL: NA UEL: NA Noncombustible Solids
Lead	7439-92-1	TWA 0.05 mg/m <sup>3</sup>	TWA (8-hour) 0.050 mg/m <sup>3</sup>	[1910.1025] TWA 0.050 mg/m <sup>3</sup>	100 mg/m <sup>3</sup> (as Pb)	Inhalation, ingestion, skin and/or eye contact	Lassitude (weakness, exhaustion), insomnia; facial pallor; anorexia, weight loss, malnutrition; constipation, abdominal pain, colic; anemia; gingival lead line; tremor; paralysis wrist, ankles; encephalopathy; kidney disease; irritation eyes; hypertension	Eyes, gastrointestinal tract, central nervous system, kidneys, blood, gingival tissue	A heavy, ductile, soft, gray solid BP: 3164°F Fl.Pt. = NA LEL: NA UEL: NA Noncombustible Solid in bulk form

**Table 1. Toxicological, Physical, and Chemical Properties of Compounds Potentially Present at the Site.**

Compound	CAS #	ACGIH TLV	NIOSH REL	OSHA PEL	IDLH	Routes of Exposure	Toxic Properties	Target Organs	Physical/Chemical Properties
Magnesium	7439-95-4	<a href="https://cameochemicals.noaa.gov/chemical/6949">https://cameochemicals.noaa.gov/chemical/6949</a>				Eye and/or skin contact	Dust irritates eyes in same way as any foreign material. Penetration of skin by fragments of metal is likely to produce local irritation, blisters, and ulcers which may become infected.	Eyes	A light silvery metal BP: 1202°F Fl.Pt. = NA LEL: NA UEL: NA
Manganese	7439-96-5	TWA 0.02 mg/m <sup>3</sup> [R] TWA 0.1 mg/m <sup>3</sup> [I]	TWA 1 mg/m <sup>3</sup> ST 3 mg/m <sup>3</sup>	C 5 mg/m <sup>3</sup>	500 mg/m <sup>3</sup> (as Mn)	Inhalation, ingestion	Manganism; asthenia, insomnia, mental confusion; metal fume fever: dry throat, cough, chest tightness, dyspnea (breathing difficulty), rales, flu-like fever; low-back pain; vomiting; malaise (vague feeling of discomfort); lassitude (weakness, exhaustion); kidney damage	respiratory system, central nervous system, blood, kidneys	A lustrous, brittle, silvery solid BP: 3564°F Fl.Pt. = NA LEL: NA UEL: NA Metal: Combustible Solid
Mercury	7439-97-6	TWA 0.1 mg/m <sup>3</sup> , as Hg Aryl compounds TWA 0.025 mg/m <sup>3</sup> as Hg, inorganic forms including metallic mercury	Hg Vapor: TWA 0.05 mg/m <sup>3</sup> [skin] Other: C 0.1 mg/m <sup>3</sup> [skin]	TWA 0.1 mg/m <sup>3</sup>	10 mg/m <sup>3</sup> (as Hg)	Inhalation, skin absorption, ingestion, skin and/or eye contact	Irritation eyes, skin; cough, chest pain, dyspnea (breathing difficulty), bronchitis, pneumonitis; tremor, insomnia, irritability, indecision, headache, lassitude (weakness, exhaustion); stomatitis, salivation; gastrointestinal disturbance, anorexia, weight loss; proteinuria	Eyes, skin, respiratory system, central nervous system, kidneys	Metal: Silver-white, heavy, odorless liquid. [Note: "Other" Hg compounds include all inorganic & aryl Hg compounds except (organo) alkyls.] BP: 674°F Fl.Pt. = NA LEL: NA UEL: NA Metal: Noncombustible Liquid
Nickel	7440-02-0	TWA 1.5 mg/m <sup>3</sup> [elemental] TWA 0.1 mg/m <sup>3</sup> [soluble inorganic compound] TWA 0.2 mg/m <sup>3</sup> [insoluble inorganic compound] TWA 0.1 mg/m <sup>3</sup> [Nickel subsulfide]	Ca TWA 0.015 mg/m <sup>3</sup>	TWA 1 mg/m <sup>3</sup>	Ca [10 mg/m <sup>3</sup> (as Ni)]	Inhalation, ingestion, skin and/or eye contact	Sensitization dermatitis, allergic asthma, pneumonitis; [potential occupational carcinogen]	Nasal cavities, lungs, skin	Lustrous, silvery, odorless solid. BP: 5139°F Fl.Pt. = NA LEL: NA UEL: NA Combustible Solid; nickel sponge catalyst may ignite spontaneously in air.
Potassium	97/7440	<a href="https://cameochemicals.noaa.gov/chemical/4289">https://cameochemicals.noaa.gov/chemical/4289</a>				Eye and/or skin contact	Will burn skin and eyes	Skin, eyes	Potassium is a soft silvery metal though normally grayish white due to oxidation BP: 1425°F Fl.Pt. = NA LEL: NA UEL: NA
Selenium	7782-49-2	TWA 0.2 mg/m <sup>3</sup>	TWA 0.2 mg/m <sup>3</sup>	TWA 0.2 mg/m <sup>3</sup>	1 mg/m <sup>3</sup> (as Se)	Inhalation, ingestion, skin and/or eye contact	Irritation eyes, skin, nose, throat; visual disturbance; headache; chills, fever; dyspnea (breathing difficulty), bronchitis; metallic taste, garlic breath, gastrointestinal disturbance; dermatitis; eye, skin burns; In Animals: anemia; liver necrosis, cirrhosis; kidney, spleen damage	Eyes, skin, respiratory system, liver, kidneys, blood, spleen	Amorphous or crystalline, red to gray solid. [Note: Occurs as an impurity in most sulfide ores.] BP: 1265°F Fl.Pt. = NA LEL: NA UEL: NA Combustible Solid
Silver	7440-22-4	TWA 0.1 mg/m <sup>3</sup> [Metal, dust, and fume] TWA 0.01 mg/m <sup>3</sup> [Soluble compounds, as Ag]	TWA 0.01 mg/m <sup>3</sup>	TWA 0.01 mg/m <sup>3</sup>	10 mg/m <sup>3</sup> (as Ag)	Inhalation, ingestion, skin and/or eye contact	Blue-gray eyes, nasal septum, throat, skin; irritation, ulceration skin; gastrointestinal disturbance	Nasal septum, skin, eyes	Metal: White, lustrous solid BP: 3632°F Fl.Pt. = NA LEL: NA UEL: NA Metal: Noncombustible Solid, but flammable in form of dust or powder
Sodium	7440-23-5	<a href="https://cameochemicals.noaa.gov/chemical/7794">https://cameochemicals.noaa.gov/chemical/7794</a>				Skin contact	Severe burns caused by burning metal or by caustic soda formed by reaction with moisture on skin	Skin	A silvery soft metal that becomes grayish white upon exposure to air BP: 1621°F Fl.Pt. = NA LEL: NA UEL: NA
Thallium	7440-28-0	0.02 mg/m <sup>3</sup> inhaleable particulate matter	TWA 0.1 mg/m <sup>3</sup> [skin]	TWA 0.1 mg/m <sup>3</sup> [skin]	15 mg/m <sup>3</sup> (as Tl)	Inhalation, skin absorption, ingestion, skin and/or eye contact	Nausea, diarrhea, abdominal pain, vomiting; ptosis, strabismus; peri neuritis, tremor; retrosternal (occurring behind the sternum) tightness, chest pain, pulmonary edema; convulsions, chorea, psychosis; liver, kidney damage; alopecia; paresthesia legs	Eyes, respiratory system, central nervous system, liver, kidneys, gastrointestinal tract, body hair	Appearance and odor vary depending upon the specific soluble thallium compound BP: NA Fl.Pt. = NA LEL: NA UEL: NA
Vanadium	7440-62-2	<a href="https://cameochemicals.noaa.gov/chemical/16147">https://cameochemicals.noaa.gov/chemical/16147</a>				Inhalation, skin absorption, ingestion, skin and/or eye contact	Highly toxic, may be fatal if inhaled, swallowed or absorbed through skin. Avoid any skin contact. Effects of contact or inhalation may be delayed. Fire may produce irritating, corrosive and/or toxic gases. Runoff from fire control or dilution water may be corrosive and/or toxic and cause pollution	Skin	Silvery-whitish powder BP: NA Fl.Pt. = NA LEL: NA UEL: NA
Zinc	7440-66-6	<a href="https://cameochemicals.noaa.gov/chemical/4814">https://cameochemicals.noaa.gov/chemical/4814</a>				Inhalation, skin absorption, ingestion, skin and/or eye contact	Inhalation or contact with vapors, substance or decomposition products may cause severe injury or death. May produce corrosive solutions on contact with water. Fire will produce irritating, corrosive and/or toxic gases. Runoff from fire control may cause pollution	Lungs	A grayish powder BP: NA Fl.Pt. = NA LEL: NA UEL: NA
<b>PCBs</b>									
PCBs (total)	11097-69-1, 53469-21-9	TWA 0.5 mg/m <sup>3</sup> [skin] TWA 1 mg/m <sup>3</sup> [skin]	Ca TWA 0.001 mg/m <sup>3</sup> Ca TWA 0.001 mg/m <sup>3</sup>	TWA 0.5 mg/m <sup>3</sup> [skin] TWA 1 mg/m <sup>3</sup> [skin]	Ca [5 mg/m <sup>3</sup> ] Ca [5 mg/m <sup>3</sup> ]	Inhalation, skin absorption, ingestion, skin and/or eye contact	Irritation eyes, chloracne; liver damage; reproductive effects; [potential occupational carcinogen]	Skin, eyes, liver, reproductive system	Colorless to pale-yellow, viscous liquid or solid (below 50°F) with a mild, hydrocarbon odor BP: 689-734°F, 617-691°F Fl.Pt. = NA, NA LEL: NA UEL: NA Nonflammable Liquid, but exposure in a fire results in the formation of a black soot containing PCBs, polychlorinated dibenzofurans, and chlorinated dibenzo-p-dioxins.

**Table 1. Toxicological, Physical, and Chemical Properties of Compounds Potentially Present at the Site.**

Compound	CAS #	ACGIH TLV	NIOSH REL	OSHA PEL	IDLH	Routes of Exposure	Toxic Properties	Target Organs	Physical/Chemical Properties
<b>Petroleum Hydrocarbons</b>									
Gasoline	86290-81-5	TWA 300 ppm STEL 500 ppm	Ca	None	Ca [N.D.]	Inhalation, skin absorption, ingestion, skin and/or eye contact	Irritation eyes, skin, mucous membrane; dermatitis; headache, lassitude (weakness, exhaustion), blurred vision, dizziness, slurred speech, confusion, convulsions; chemical pneumonitis (aspiration liquid); possible liver, kidney damage; [potential occupational carcinogen]	Eyes, skin, respiratory system, central nervous system, liver, kidneys	Clear liquid with a characteristic odor BP: 102°F Fl.Pt. = -45°F LEL: 1.4% UEL: 7.6%

**References**  
Centers for Disease Control and Prevention, 2018. *NIOSH Pocket Guide to Chemical Hazards*. The National Institute for Occupational Safety and Health.  
American Conference of Governmental Industrial Hygienists (ACGIH), 2017. *2017 TLVs® and BEIs®*. Cincinnati, OH.  
National Oceanic and Atmospheric Administration (NOAA) and Environmental Protection Agency (EPA), 2019. *CAMEO Chemicals Database*. <https://cameochemicals.noaa.gov/>  
U.S. Department of Labor, 1990. *OSHA Regulated Hazardous Substances*. Industrial Exposure and Control Technologies Government Institutes, Inc.  
Sax, N. Van Nostrand and Reinhold Company, 1987. *Hawley's Condensed Chemical Dictionary, 11th Edition*.  
Proctor, N.H., J.P. Hughes and M.L. Fischman, 1989. *Chemical Hazards of the Workplace*. Van Nostrand Reinhold. New York.  
Sax, N.I. and R.J. Lewis, 1989. *Dangerous Properties of Industrial Materials, 7th Edition*. Van Nostrand Reinhold. New York.

- Abbreviations:**  
ACGIH – American Conference of Governmental Industrial Hygienists.  
BP – boiling point at 1 atmosphere, °F  
C – Ceiling, is a concentration that should not be exceeded during and part of the working exposure.  
Ca – Carcinogenic.  
CAS# - Chemical Abstracts Service registry number which is unique for each chemical.  
DSEN - Dermal Sensitization  
Fl Pt. – Flash point  
IDLH - Immediately Dangerous to Life and Health concentrations represent the maximum concentration from which, in the event of respirator failure, one could escape within 30 minutes without a respirator and without experiencing any escape-impairing or irreversible health effects.  
LEL – Lower explosive (flammable) limit in air, % by volume (at room temperature)  
mg/m<sup>3</sup> – Milligrams of substance per cubic meter of air  
NIOSH - National Institute for Occupational Safety and Health.  
OSHA – Occupational Safety and Health Administration  
OTO - Ototoxicant  
PEL - OSHA Permissible Exposure Limit (usually) a time weighted average concentration that must not be exceeded during any 8 hour work shift of a 40 hr work week.  
ppm – parts per million  
REL – NIOSH Recommended Limit indicated a time weighted average concentration that must not be exceeded during any 10 hour work shift of a 40 hr work week  
RSEN - Respiratory Sensitization  
SG - Specific Gravity  
STEL – ACGIH Short-term exposure limit (ST)  
TLV - ACGIH Threshold Limit Values (usually 8 hour time weighted average concentrations).  
TWA – 8-hour, time-weighted average  
UEL – Upper explosive (flammable) limit in air, % by volume (at room temperature)  
VP - Vapor Pressure

**Site-Specific Health and Safety Plan**  
**12 Franklin Street, Brooklyn, New York 11222**

---

**FIGURES**

1. Site Location Map
2. Site Plan with Emergency Muster Area
3. Routes to Urgent Care and Hospital



QUADRANGLE LOCATION



SOURCE:  
USGS, 2013, Brooklyn, NY  
7.5 Minute Topographic Quadrangle



Title:

**SITE LOCATION MAP**

12 FRANKLIN STREET  
BROOKLYN, NEW YORK 11222

Prepared for:

FRANKLIN POINT LLC






Compiled by: J.R.	Date: 15MAY23
Prepared by: G.M.	Scale: AS SHOWN
Project Mgr: J.R.	Project: 4170.0001Y000
File: 4170.0001Y102.01.DWG	


FIGURE

**1**



**LEGEND**

	SITE ENTRANCES AND EXITS
	MUSTER AREA
	SITE BOUNDARY




Title:

## SITE PLAN WITH MUSTER AREA


12 FRANKLIN STREET  
BROOKLYN, NEW YORK 11222

Prepared for:

FRANKLINE POINT LLC

	Compiled by: J.R.	Date: 15MAY23	FIGURE <b>2</b>
	Prepared by: G.M.	Scale: AS SHOWN	
	Project Mgr: J.R.	Project: 4170.0001Y000	
	File: 4170.0001Y102.01.DWG		

V:\CAD\PROJECTS\4170\0001Y102\4170.0001Y102.01.DWG



**Directions to CityMD Greenpoint Urgent Care**

1. Head north on Franklin Street toward Meserole Avenue.
2. Turn right onto Meserole Avenue.
3. Turn Left onto Manhattan Avenue. CityMD is on the left at 795 Manhattan Avenue.

**Directions to NYU Medical Center**

1. Head north on Franklin Street toward Meserole Avenue.
2. Turn right onto Cayer Street.
3. Turn left onto McGuinness Boulevard
4. Keep left to continue on Pulaski Bridge.
5. Slight right toward 49th Avenue. Turn right onto 49th Avenue
6. Turn right onto 11th Place. Turn right onto 50th Avenue.
7. Turn left onto the I-495 West ramp.
8. Keep left, follow signs for I-495 West and merge onto onto I-495 West. Continue onto Queens Midtown Tunnel.
9. Continue onto I-495 W/Queens Midtown Tunnel.
10. Take the 35th Street exit on the left toward Downtown/34th Street/2nd Avenue. Turn left onto E 35th Street.
11. Turn right at the first cross street onto 2nd Avenue.
12. Turn left at the first cross street onto E 34th Street. NYU Medical Center in on the left at 403 E 34th Street.



<p>Title:</p> <h2 style="text-align: center;">ROUTES TO URGENT CARE AND HOSPITAL</h2> <p style="text-align: center;">12 FRANKLIN STREET BROOKLYN, NEW YORK 11222</p>		
<p>Prepared for:</p> <p style="text-align: center;">FRANKLIN POINT LLC</p>		
<p>Compiled by: J.R.</p> <p>Prepared by: G.M.</p> <p>Project Mgr: J.R.</p> <p>File: 4170.0001Y102.01.DWG</p>	<p>Date: 15MAY23</p> <p>Scale: AS SHOWN</p> <p>Project: 4170.0001Y000</p>	<p>FIGURE</p> <h1 style="font-size: 2em;">3</h1>

**Site-Specific Health and Safety Plan**  
**12 Franklin Street, Brooklyn, New York 11222**

---

**APPENDICES**

- A. Job Safety Analysis (JSA) Forms
- B. Safety Data Sheets (SDSs) for Chemicals Used
- C. Personal Protective Equipment (PPE) Management Program
- D. Subsurface Utility Clearance Management Program
- E. Heavy Equipment Exclusion Zone Policy



**Site-Specific Health and Safety Plan**  
**12 Franklin Street, Brooklyn, New York 11222**

---

**APPENDIX A**

Job Safety Analysis (JSA) Forms

<b>JOB SAFETY ANALYSIS</b>		<b>Cntrl. No.</b>	DATE:	<input checked="" type="checkbox"/> NEW <input type="checkbox"/> REVISED	PAGE 1 of 2
JSA TYPE CATEGORY <b>GENERIC</b>		WORK TYPE	WORK ACTIVITY (Description)		
DEVELOPMENT TEAM	POSITION / TITLE		REVIEWED BY:	POSITION / TITLE	
<b>REQUIRED AND / OR RECOMMENDED PERSONAL PROTECTIVE EQUIPMENT</b>					
<input type="checkbox"/> LIFE VEST	<input type="checkbox"/> GOGGLES	<input type="checkbox"/> AIR PURIFYING RESPIRATOR	<input type="checkbox"/> GLOVES:		
<input type="checkbox"/> HARD HAT	<input type="checkbox"/> FACE SHIELD	<input type="checkbox"/> SUPPLIED RESPIRATOR	<input type="checkbox"/> OTHER		
<input type="checkbox"/> LIFELINE / BODY HARNESS	<input type="checkbox"/> HEARING PROTECTION	<input type="checkbox"/> PPE CLOTHING:			
<input type="checkbox"/> SAFETY GLASSES	<input type="checkbox"/> SAFETY SHOES				
<b>REQUIRED AND / OR RECOMMENDED EQUIPMENT</b>					
Required Equipment:					
<b>Commitment to LPS</b> – All personnel onsite will actively participate in SPSA performance by verbalizing SPSAs throughout the day.					
<b>EXCLUSION ZONE: A _ foot exclusion zone will be maintained around (indicate equipment).</b>					
<b>Assess 1JOB STEPS</b>	<b>Analyze 2POTENTIAL HAZARDS</b>		<b>Act 3CRITICAL ACTIONS</b>		
1. [INSERT JOB STEP]	1a. CONTACT: [INSERT HAZARD]	1a.			
	1b. CAUGHT: [INSERT HAZARD]	1b.			
	1c. FALL: [INSERT HAZARD]	1c.			
	1d. EXPOSURE: [INSERT HAZARD]	1d.			
	1e. EXERTION: [INSERT HAZARD]	1e.			
	1f. ENERGY SOURCE: [INSERT HAZARD]	1f.			
2. [INSERT JOB STEP]	2a. CONTACT: [INSERT HAZARD]	2a.			
	2b. CAUGHT: [INSERT HAZARD]	2b.			

<sup>1</sup> Each Job or Operation consists of a set of tasks / steps. Be sure to list all the steps needed to perform job.

<sup>2</sup> A hazard is a potential danger. Break hazards into five types: Contact - victim is struck by or strikes an object; Caught - victim is caught on, caught in or caught between objects; Fall - victim falls to ground or lower level (includes slips and trips); Exertion - excessive strain or stress / ergonomics / lifting techniques; Exposure - inhalation/skin hazards.

<sup>3</sup> Using the first two columns as a guide, decide what actions or procedures are necessary to eliminate or minimize the risk. List the recommended safe operating procedures. Say exactly what needs to be done - such as "use two persons to lift." Avoid general statements such as, "be careful."

	<p><b>2c. FALL:</b> [INSERT HAZARD]</p> <p><b>2d. EXPOSURE:</b> [INSERT HAZARD]</p> <p><b>2e. EXERTION:</b> [INSERT HAZARD]</p> <p><b>2f. ENERGY SOURCE:</b> [INSERT HAZARD]</p>	<p>2c.</p> <p>2d.</p> <p>2e.</p> <p>2f.</p>
--	--	---

<sup>1</sup> Each Job or Operation consists of a set of tasks / steps. Be sure to list all the steps needed to perform job.

<sup>2</sup> A hazard is a potential danger. Break hazards into five types: Contact - victim is struck by or strikes an object;

Caught - victim is caught on, caught in or caught between objects; Fall - victim falls to ground or lower level (includes slips and trips); Exertion - excessive strain or stress / ergonomics / lifting techniques; Exposure - inhalation/skin hazards.

<sup>3</sup> Using the first two columns as a guide, decide what actions or procedures are necessary to eliminate or minimize the risk. List the recommended safe operating procedures. Say exactly what needs to be done - such as "use two persons to lift". Avoid general statements such as, "be careful".

JOB SAFETY ANALYSIS		Cntrl. No. GEN-011	DATE: 1/18/2015	<input type="checkbox"/> NEW <input checked="" type="checkbox"/> REVISED	PAGE 1 of 2
JSA TYPE CATEGORY <b>GENERIC</b>		WORK TYPE <b>Site Recon</b>	WORK ACTIVITY (Description) <b>Site Walk and Inspection</b>		
DEVELOPMENT TEAM		POSITION / TITLE	REVIEWED BY:		POSITION / TITLE
Anthony Giannetti		Staff Geologist	Daniel Abberton		SHSM
			Mike Ritorto		Project Hydrogeologist
			Joe Gentile		CHSM
<b>REQUIRED AND / OR RECOMMENDED PERSONAL PROTECTIVE EQUIPMENT</b>					
<input type="checkbox"/> LIFE VEST <input checked="" type="checkbox"/> HARD HAT <input type="checkbox"/> LIFELINE / BODY HARNESS <input checked="" type="checkbox"/> SAFETY GLASSES		<input type="checkbox"/> GOGGLES <input type="checkbox"/> FACE SHIELD <input checked="" type="checkbox"/> HEARING PROTECTION: ear plugs as necessary <input checked="" type="checkbox"/> SAFETY SHOES: <u>Steel or composite toed</u>	<input type="checkbox"/> AIR PURIFYING RESPIRATOR <input type="checkbox"/> SUPPLIED RESPIRATOR <input checked="" type="checkbox"/> PPE CLOTHING: <u>High-visibility vest or high-vis outerwear, sleeved shirt</u>	<input checked="" type="checkbox"/> GLOVES: <u>Leather/cut-resistant/chemical resistant</u> <input checked="" type="checkbox"/> OTHER: tyvek and rubber boots as necessary, dust mask as necessary	
<b>REQUIRED AND / OR RECOMMENDED EQUIPMENT</b>					
Required Equipment: Site map and/or guide familiar with Site, operating cell phone or walkie-talkie if Site allows.					
<b>Commitment to LPS</b> – All personnel onsite will actively participate in SPSA performance by verbalizing SPSAs throughout the day.					
<b>EXCLUSION ZONE (EZ): A minimum 10' exclusion zone will be maintained around equipment.</b>					
Assess <sup>1</sup> JOB STEPS	Analyze <sup>2</sup> POTENTIAL HAZARDS	Act <sup>3</sup> CRITICAL ACTIONS			
1. Check in with Site manager.	1a. <b>CONTACT/EXPOSURE/FALL:</b> Lack of communication could result in H&S incident.	1a. Inform Site personnel of work scope, timeline and location(s). 1a. Inquire about hazards and other activities taking place at the Site. 1a. Discuss emergency evacuation procedures and muster points with Site manager..			
2. Traversing the Site and setting up at work locations.	2a. <b>CONTACT:</b> Property damage and personal injury caused by obstructions/vehicles or unauthorized personnel at remote Sites.  2b. <b>FALL:</b> Uneven terrain and weather conditions. Overgrown shrubs and vines. Equipment in the work zone.  2c. <b>OVEREXERTION:</b> Muscle strain while carrying equipment.  2d. <b>EXPOSURE:</b> Biological hazards - ticks, bees/wasps, poison ivy, insects, etc. (Ticks are most active any time the temperature is above freezing, typically from March to November.)	2a. Maintain speed limit of 5 mph on-site. 2a. All equipment must be stowed and secured prior to moving. Use wheel chocks on all construction vehicles when not in motion. 2a. Drive on established roadways. 2a. Yield to all pedestrians. 2a. Do not back up vehicle without spotter where visibility is limited; use pull-through spots or back into parking spots; use an audible signal (horn/back-up alarm) when backing up vehicles. 2a. Wear high visibility clothing/safety vest. If working at remote Site, add orange accessories during hunting season.  2b. Inspect walking path for uneven terrain, weather-related hazards (i.e., ice, puddles, snow, etc.), and obstructions prior to mobilizing equipment. 2b. Use established pathways and walk on stable, secure ground. 2b. Communicate traversing hazards with others  2c. When carrying equipment to/from work area, use proper lifting techniques; keep back straight, lift with legs, keep load close to body, never reach with a load. Ensure that loads are balanced to reduce the potential for muscle strain. Use mechanical assistance or make multiple trips to carry equipment. 2c. Two people or a mechanical lifting device are required when lifting objects over 50 lbs or when the shape makes the object difficult to lift.  2d. Inspect area to avoid contact with biological hazards. 2d. Ticks: <ul style="list-style-type: none"> <li>• Treat outer clothing including pants, shirts, socks, boots and hats the evening before use with Permethrin (allowing at least two hours before use).</li> <li>• Apply DEET to exposed skin before travelling to the Site and reapply after two hours.</li> <li>• Check for ticks during and after work.</li> </ul> 2d. Bees: Use bee spray to remove nests. Protect exposed skin with insect repellent. 2d. Poison Ivy: <ul style="list-style-type: none"> <li>• Identify areas of poison ivy and spray with weed killer. Don Tyvek and rubber boots while traversing poison ivy areas.</li> <li>• If skin comes in contact with poison ivy, wash skin thoroughly with soap and water.</li> </ul>			

<sup>1</sup> Each Job or Operation consists of a set of tasks / steps. Be sure to list all the steps needed to perform job.

<sup>2</sup> A hazard is a potential danger. Break hazards into five types: Contact - victim is struck by or strikes an object; Caught - victim is caught on, caught in or caught between objects; Fall - victim falls to ground or lower level (includes slips and trips); Exertion - excessive strain or stress / ergonomics / lifting techniques; Exposure - inhalation/skin hazards; Energy Source – electricity, pressure, compression/tension.

<sup>3</sup> Using the first two columns as a guide, decide what actions or procedures are necessary to eliminate or minimize the risk. List the recommended safe operating procedures. Say exactly what needs to be done - such as "use two persons to lift." Avoid general statements such as, "be careful."

	<p><b>2e. EXPOSURE:</b> Heat Stress &amp; Cold Stress. Personal injury from working in inclement weather conditions.</p>	<p>2e. Wear sunscreen with SPF 15 or greater on exposed skin whenever 30 minutes or more of sun exposure is expected.</p> <p>2e. Watch for heat stress symptoms (muscle cramping, exhaustion, dizziness, rapid and shallow breathing). Take breaks as needed.</p> <p>2e. Watch for cold stress symptoms (severe shivering, slowing of body movement, weakness, stumbling or inability to walk, collapse). Take breaks as needed.</p> <p>2e. Wear appropriate rain gear as needed.</p> <p>2e. Take frequent breaks if tired, wet, or cold/hot. Drink water.</p> <p>2e. If lightning is observed, wait 30 minutes after last thunder boom/lightning bolt in a sheltered location (car acceptable) before starting work again.</p>
<p>3. Define and secure the work area.</p>	<p><b>3a. CONTACT:</b> Personal injury or property damage from other vehicles on-site.</p>	<p>3a. Face traffic, maintain eye contact with oncoming vehicles, and establish a safe exit route.</p> <p>3a. Look both ways in high traffic areas.</p> <p>3a. Position vehicle to protect against oncoming traffic.</p> <p>3a. Use 42" traffic cone and caution tape to delineate work area. Use a spotter in high traffic areas.</p> <p>3a. Wear high visibility clothing/safety vest.</p>
<p>4. Walking near heavy equipment and machinery.</p>	<p><b>4a. CONTACT:</b> Personal injury from Site and roadway traffic. Personal injury from flying debris.</p> <p><b>4b. OVEREXERTION:</b> Personal injury from lifting/moving/rotating equipment.</p> <p><b>4c. EXPOSURE:</b> Hearing damage from excavation activities. Inhalation/exposure to hazardous vapors and or dust.</p> <p><b>4d. EXPOSURE:</b> Working in a remote area.</p>	<p>4a. See 3a.</p> <p>4a. Place traffic cones to re-direct traffic flow around work area and to alert others as to activity taking place. Evaluate possible need for police detail and request as needed.</p> <p>4a. Maintain a minimum exclusion zone of 10 feet from all equipment. Task specific JSAs should be referenced to determine the actual exclusion zone for the piece of equipment being used.</p> <p>4a. Keep body parts out of the line of fire of pinch points.</p> <p>4a. Routinely inspect work area and be aware of location of all Site personnel. Make eye contact with spotter, if provided, or operator prior to entering the work area.</p> <p>4a. Wear safety glasses at all times.</p> <p>4b. See 2c.</p> <p>4c. Monitor air quality with multi-gas meter and dust meter, if necessary. Use water to suppress dust, if necessary. Wear dust mask, if necessary.</p> <p>4c. Wear hearing protection if &gt;85 dBA.</p> <p>4c. Always wear leather gloves when handling any tools or equipment. Wear cut-resistant gloves (Kevlar or similar) when handling sharp objects, glassware or cutting tools.</p> <p>4d. Use the "buddy system" whenever possible. If working alone, contact PM upon arrival/departure, as well as during work activities prior to commencing work.</p> <p>4d. Always carry a communication (i.e., cell phone, walkie-talkie) or directional (i.e., map, compass, etc.) device when traversing remote areas.</p>
<p>5. Working in adverse weather conditions.</p>	<p><b>5a. EXPOSURE:</b> Heat Stress &amp; Cold Stress. Personal injury from working in inclement weather conditions.</p>	<p>5a. Watch for heat stress symptoms (muscle cramping, exhaustion, dizziness, rapid and shallow breathing). Take breaks as needed.</p> <p>5a. Watch for cold stress symptoms (severe shivering, slowing of body movement, weakness, stumbling or inability to walk, collapse). Take breaks as needed.</p> <p>5a. Wear appropriate rain gear as needed.</p> <p>5a. Take frequent breaks if tired, wet, or cold/hot. Drink water.</p> <p>5a. If lightning is observed, wait 30 minutes after last thunder boom/lightning bolt in a sheltered location (car acceptable) before starting work again.</p>
<p>6. Departing Site.</p>	<p><b>6a. EXPOSURE:</b> Exposure to unnecessary hazards should personnel believe Roux is on-Site during an emergency and conduct a search.</p>	<p>6a. Sign out or notify Site personnel of your departure.</p>

<sup>1</sup> Each Job or Operation consists of a set of tasks / steps. Be sure to list all the steps needed to perform job.

<sup>2</sup> A hazard is a potential danger. Break hazards into five types: Contact - victim is struck by or strikes an object; Caught - victim is caught on, caught in or caught between objects; Fall - victim falls to ground or lower level (includes slips and trips); Exertion - excessive strain or stress / ergonomics / lifting techniques; Exposure - inhalation/skin hazards; Energy Source – electricity, pressure, compression/tension.

<sup>3</sup> Using the first two columns as a guide, decide what actions or procedures are necessary to eliminate or minimize the risk. List the recommended safe operating procedures. Say exactly what needs to be done - such as "use two persons to lift". Avoid general statements such as, "be careful".

<b>JOB SAFETY ANALYSIS</b>		Ctrl. No.	DATE 1/23/2015	<input type="checkbox"/> NEW <input checked="" type="checkbox"/> REVISED	PAGE 1 of 2
JSA TYPE CATEGORY: <b>Generic</b>		WORK TYPE: <b>Drilling</b>	WORK ACTIVITY (Description): <b>Hollow Stem Auger Soil Borings /Well Installation</b>		
<b>DEVELOPMENT TEAM</b>		<b>POSITION / TITLE</b>	<b>REVIEWED BY:</b>	<b>POSITION / TITLE</b>	
Gina Vanderlin		Project Scientist	Joseph Gentile	CSHM	
<b>REQUIRED AND / OR RECOMMENDED PERSONAL PROTECTIVE EQUIPMENT</b>					
<input type="checkbox"/> LIFE VEST <input checked="" type="checkbox"/> HARD HAT <input type="checkbox"/> LIFELINE / BODY HARNESS <input checked="" type="checkbox"/> SAFETY GLASSES	<input type="checkbox"/> GOGGLES <input type="checkbox"/> FACE SHIELD <input checked="" type="checkbox"/> HEARING PROTECTION: (as needed) <input checked="" type="checkbox"/> SAFETY SHOES <u>steel or composite toe</u>	<input type="checkbox"/> AIR PURIFYING RESPIRATOR <input type="checkbox"/> SUPPLIED RESPIRATOR <input checked="" type="checkbox"/> PPE CLOTHING: <u>fluorescent sleeved shirt or sleeved shirt and reflective safety vest.</u>	<input checked="" type="checkbox"/> GLOVES: <u>Leather, Nitrile and cut resistant</u> <input checked="" type="checkbox"/> OTHER: <u>Insect Repellant, sunscreen (as needed)</u>		
<b>REQUIRED AND / OR RECOMMENDED EQUIPMENT</b>					
Truck-Mounted Drilling Rig or Track Rig, Saw, Hand Tools, Photoionization Detector, Multi-Gas Meter (or equivalent), Interface Probe, 20 lb. Fire Extinguisher, 42" Cones & Flags, "Work Area" Signs					
<b>COMMITMENT TO LPS - All personnel onsite will actively participate in SPSA performance by verbalizing SPSAs throughout the day.</b>					
<b>EXCLUSION ZONE POLICY – All non-essential personnel shall maintain a 10 foot exclusion zone while drill rig is engaged</b>					
<b>"SHOW ME YOUR HANDS"</b>					
<b>Driller and helper should show that hands are clear from controls and moving parts</b>					
<b>Assess 1<sup>1</sup>JOB STEPS</b>	<b>Analyze 2<sup>2</sup>POTENTIAL HAZARDS</b>	<b>Act 3<sup>3</sup>CRITICAL ACTIONS</b>			
1. Mobilization of drilling rig	1a. <b>CONTACT:</b> Equipment or property damage.  1b. <b>FALL:</b> Slip/trip/fall hazards.	1a. The drill rig's tower/derrick will be lowered and secured prior to mobilization. 1a. A spotter should be utilized while moving or backing the drill rig. If personnel move into the path of the drilling rig, the drilling rig will be stopped until the path is again clear. 1a. Set-up the work area / position equipment in a manner that eliminates or reduces the need for backing of trucks and trailers. 1a. When backing up truck rig with an attached trailer use a second spotter if there is tight clearance simultaneously on multiple sides of the equipment or if turning angles limit driver visibility. 1a. Inspect the driving path for uneven terrain. Level or avoid if needed.  1b. Inspect walking path for uneven terrain, weather-related hazards (i.e., ice, puddles, snow, etc.), and obstructions prior to mobilizing equipment. 1b. Do not climb over stored materials/equipment; walk around. Practice good housekeeping. 1b. Use established pathways and walk on stable, secure ground. 1b. Use three points of contact when mounting or dismounting the rig.			
2. Raising tower/derrick of drilling rig	2a. <b>CONTACT:</b> Overhead hazards.  2b. <b>CONTACT:</b> Pinch points when raising the rig; crushing hazard with stability of rig during set-up	2a. Prior to raising the tower/derrick, area above the drilling rig will be inspected for overhead hazards (wires, tree limbs, piping, or other structures) that may be contacted by the rig's tower or drilling rods. 2a. The tower/derrick must not be raised beneath overhead power lines unless approved by both the ExxonMobil and Roux PMs. 2a. Maintain at a minimum 10' from overhead structures. 2a. Do not move the rig while the tower/derrick is raised.  2b. Inspect the equipment prior to use and avoid placing hands near pinch points. 2b. Lower out riggers on rig to ensure stability prior to raising rig tower derrick. 2b. Inspect the set-up location for uneven terrain. Level or avoid area if needed.			
3. Advancement of augers for soil borings and well material installation.	3a. <b>CONTACT:</b> Flying / spraying debris.  3b. <b>EXPOSURE:</b> Noise and dust.	3a. Wear minimum level D PPE 3a. Be aware of and avoid potential lines of fire.  3b. Wet borehole area with sprayer to minimize dust. Stand upwind and keep body positioned away from rig. 3b. Wear hearing protection while drill rig is operating/or the noise levels exceed 85dBA.			

<sup>1</sup> Each Job or Operation consists of a set of tasks / steps. Be sure to list all the steps needed to perform job.

<sup>2</sup> A hazard is a potential danger. Break hazards into six types: Contact - victim is struck by or strikes an object; Caught - victim is caught on, caught in or caught between objects; Fall - victim falls to ground or lower level (includes slips and trips); Exertion - excessive strain or stress / ergonomics / lifting techniques; Exposure - inhalation/skin hazards; Energy Source – electricity, pressure, compression/tension.

<sup>3</sup> Using the first two columns as a guide, decide what actions or procedures are necessary to eliminate or minimize the risk. List the recommended safe operating procedures. Say exactly what needs to be done - such as "use two persons to lift". Avoid general statements such as, "be careful".

Assess <sup>1</sup> JOB STEPS	Analyze <sup>2</sup> POTENTIAL HAZARDS	Act <sup>3</sup> CRITICAL ACTIONS
4. Advancement of augers for soil borings, and well material installation (Continued).	<p>4c. <b>CAUGHT:</b> Limb/extremity pinching, abrasion, and crushing.</p> <p>4d. <b>CONTACT:</b> Equipment imbalance during advancement of drill equipment.</p> <p>4e. <b>EXPOSURE:</b> Inhalation of contamination/vapors.</p> <p>4f. <b>FALL:</b> Slip/trip/fall hazards.</p> <p>4g. <b>EXERTION:</b> Installing well casings and lifting augers.</p> <p>4h. <b>CONTACT:</b> Using hand tools to install well casings and materials</p>	<p>4c. Always wear leather gloves when making connections and using hand tools; wear cut-resistant (i.e., Kevlar) gloves when handling cutting tools.</p> <p>4c. Test all emergency shutdown devices prior to drilling.</p> <p>4c. Inspect drill head for worn surface or missing teeth; replace if damaged or blunt.</p> <p>4c. Inspect augers; do not use if auger flight if damaged or bent.</p> <p>4c. Ensure all jewelry is removed, loose clothing is secured, and PPE is secured close to the body.</p> <p>4c. All non-essential personnel should stay away from the immediate work area; position body out of the line-of-fire of equipment particularly when installing auger flights.</p> <p>4c. Drillers and helpers will understand and use the "Show Me Your Hands" Policy.</p> <p>4c. Spinning augers should have an <b>exclusion zone of 20 feet</b> when in operation.</p> <p>4d. Drillers will advance the borehole with caution to avoid causing the rig to become imbalanced and/or tip.</p> <p>4d. The blocking and leveling devices used to secure the rig will be inspected by drillers and Roux personnel regularly to see if shifting has occurred.</p> <p>4e. Air monitoring using a calibrated photoionization detector (PID) will be used to periodically monitor the breathing zone of the work area.</p> <p>4e. The Action Level for breathing zone air is five parts per million (sustained) as detected by the PID.</p> <p>4e. If a reading of &gt;5ppm is recorded, the Roux field personnel must temporarily cease work, instruct all Site personnel to step away from the area of elevated readings and inform the Roux PM of the condition. The Roux PM will then recommend additional appropriate precautions in accordance with the site specific health and safety plan.</p> <p>4f. See 1b.</p> <p>4f. Remove soil cuttings to avoid a tripping hazard from developing near augers.</p> <p>4g. Keep back straight and bend at the knees.</p> <p>4g. Utilize team lifting for objects over 50lbs.</p> <p>4g. Use mechanical lifting device for odd shaped objects.</p> <p>4h. Wear cut resistant and leather gloves.</p> <p>4h. Secure materials on a level surface before cutting</p> <p>4h. Place hands out of the line of fire</p> <p>4h. Inspect all tools prior to use and remove damaged tools from service</p>
5. Cleaning the auger flights	5a. <b>CONTACT:</b> Cuts/scrapes or puncture wound from contacting rotating auger.	<p>5a. Follow "No Hands" Procedure and make sure auger is out of gear before contacting auger with hands or tool.</p> <p>5b. When using a cleaning tool, pull across your body with handle away from body; do not push toward the auger.</p> <p>5b. Do not clean more than ¼ turn around the auger at a time.</p> <p>5b. Wear cut resistant and leather gloves.</p> <p>5b. Always use two hands when operating cleaning tool.</p> <p>5b. Inspect any tool before use and remove from service if handle or metal are cracked/fatigued.</p> <p>5b. Stand out of the line of fire.</p>
6. Decontaminate equipment.	<p>6a. <b>EXPOSURE/CONTACT:</b> To contamination (e.g., contaminated groundwater, vapors).</p> <p>6b. <b>EXPOSURE:</b> To chemicals in cleaning solution (including ammonia)</p>	<p>6a. Wear chemical-resistant disposable gloves and safety glasses.</p> <p>6a. Contain decontamination water so that it does not spill.</p> <p>6a. Use an absorbent pad to clean spills, if necessary.</p> <p>6b. See 5a.</p>

<sup>1</sup> Each Job or Operation consists of a set of tasks / steps. Be sure to list all the steps needed to perform job.

<sup>2</sup> A hazard is a potential danger. Break hazards into six types: Contact - victim is struck by or strikes an object; Caught - victim is caught on, caught in or caught between objects; Fall - victim falls to ground or lower level (includes slips and trips); Exertion - excessive strain or stress / ergonomics / lifting techniques; Exposure - inhalation/skin hazards; Energy Source – electricity, pressure, compression/tension.

<sup>3</sup> Using the first two columns as a guide, decide what actions or procedures are necessary to eliminate or minimize the risk. List the recommended safe operating procedures. Say exactly what needs to be done - such as "use two persons to lift". Avoid general statements such as, "be careful".

<b>JOB SAFETY ANALYSIS</b> Cntrl#: GEN-015		DATE 1/27/15	<input type="checkbox"/> NEW <input checked="" type="checkbox"/> REVISED	PAGE 1 of 2
JSA TYPE CATEGORY: <b>GENERIC</b>		WORK TYPE: <b>Drilling</b>	WORK ACTIVITY (Description): <b>Monitoring and Recovery Well Development</b>	
<b>DEVELOPMENT TEAM</b>	<b>POSITION / TITLE</b>	<b>REVIEWED BY:</b>	<b>POSITION / TITLE</b>	
Amy Hoffman	Staff Geologist	Mike Ritorto	Senior Hydrogeologist	
Ron Lombino	Staff Geologist	Daniel Abberton		
<b>REQUIRED AND / OR RECOMMENDED PERSONAL PROTECTIVE EQUIPMENT</b>				
<input type="checkbox"/> LIFE VEST <input checked="" type="checkbox"/> HARD HAT <input type="checkbox"/> LIFELINE / BODY HARNESS <input checked="" type="checkbox"/> SAFETY GLASSES	<input type="checkbox"/> GOGGLES <input type="checkbox"/> FACE SHIELD <input checked="" type="checkbox"/> HEARING PROTECTION (as needed) <input checked="" type="checkbox"/> SAFETY SHOES: <u>Composite-toe or steel toe boots</u>	<input type="checkbox"/> AIR PURIFYING RESPIRATOR <input type="checkbox"/> SUPPLIED RESPIRATOR <input checked="" type="checkbox"/> PPE CLOTHING: <u>Fluorescent reflective vest or high visibility clothing</u>	<input checked="" type="checkbox"/> GLOVES: <u>Leather, Nitrile and cut resistant</u> <input checked="" type="checkbox"/> OTHER: <u>Insect repellent, sunscreen (as needed)</u>	
<b>REQUIRED AND / OR RECOMMENDED EQUIPMENT</b>				
Required Equipment as needed: Truck Rig or support truck, Trailer, 42 inch Safety cones and flags, Caution Tape, Interface Probe, Power Source, Submercible Pump, Surge Block/Plunger, 20 lb. Fire Extinguisher, Holding Tanks and/or Buckets, Tools as needed: Socket and Pipe Wrench, Screw Driver, Pry Bar, Ratchet, Vault Key.				
<b>COMMITMENT TO LPS</b> - All personnel onsite will actively participate in SPSA performance by verbalizing SPSAs throughout the day.				
<b>Maintain a 20 Foot Exclusion Zone During Development Activities</b>				
<b>"SHOW ME YOUR HANDS"</b>				
<b>Driller and helper should show that hands are clear from controls and moving parts</b>				
<b>Assess 1JOB STEPS</b>	<b>Analyze 2POTENTIAL HAZARDS</b>	<b>Act 3CRITICAL ACTIONS</b>		
1. Mobilization / Demobilization (Review Mobilization and Demobilization JSA)	1a. <b>CONTACT:</b> Equipment/property damage.  1b. <b>FALL:</b> Slip/trip/fall hazards.	1a. The truck rig's tower/derrick will be lowered and secured prior to mobilization. 1a. Set-up the work area / position equipment in a manner that eliminates or reduces the need for backing of trucks and trailers. 1a. All non-essential personnel should <b>maintain an exclusion zone of 20 feet.</b> 1a. Beep horn twice before backing up. 1a. When backing up with an attached trailer use a spotter if there is tight clearance simultaneously on multiple sides of the equipment or if turning angles limit driver visibility. Stay away from the line-of-fire. 1a. Inspect the driving path for uneven terrain. Level or avoid if needed.  1b Inspect walking path for uneven terrain, weather-related hazards (i.e., ice, puddles, snow, etc.), and obstructions prior to mobilizing equipment. 1b. Do not climb over stored materials/equipment; walk around. Store equipment at lowest potential energy.		
2. Open/close well.	2a. <b>OVEREXERTION:</b> Muscle strain (some wells have large vault covers).  2b. <b>CAUGHT:</b> Pinch points associated with removing/replacing manholes and working with hand tools.  2c. <b>EXPOSURE:</b> Potentially hazardous vapors.  2d. <b>CONTACT:</b> Traffic.	2a. Keep back straight, lift with legs, keep load close to body, and never reach with a load. Ensure that loads are balanced to reduce the potential for muscle strain. Two people are required when lifting objects over 50 lbs or when the shape makes the object difficult to lift.  2b. Wear leather gloves when working with well vault/cover and hand tools. Do not put fingers under well vault/cover. 2b. Use ratchet and pry bar for well cover and inspect before use.  2c. No open flames/heat sources. 2c. Allow well to vent after opening it and before starting development activities to minimize exposure to vapors. Air monitoring must be performed prior to set up and during the well development activities. Work on upwind side of well.  2d. Wear required PPE including high visibility clothing or reflective vest. 2d. Delineate work area with 42" safety cones and/or other barriers. Position vehicle to protect against oncoming traffic. 2d. Face traffic, maintain eye contact with oncoming vehicles, and establish a safe exit route.		

<sup>1</sup> Each Job or Operation consists of a set of tasks / steps. Be sure to list all the steps needed to perform job.

<sup>2</sup> A hazard is a potential danger. Break hazards into five types: Contact - victim is struck by or strikes an object; Caught - victim is caught on, caught in or caught between objects; Fall - victim falls to ground or lower level (includes slips and trips); Exertion - excessive strain or stress / ergonomics / lifting techniques; Exposure - inhalation/skin hazards; Energy Source - Electricity, Pressure, compression, tension, torque.

<sup>3</sup> Using the first two columns as a guide, decide what actions or procedures are necessary to eliminate or minimize the risk. List the recommended safe operating procedures. Say exactly what needs to be done - such as "use two persons to lift". Avoid general statements such as, "be careful".



Assess 1JOB STEPS	Analyze 2POTENTIAL HAZARDS	Act 3CRITICAL ACTIONS
3. Develop well (mechanical surging).	<p>3a. <b>CAUGHT:</b> Cut hazards and finger pinch points.</p> <p>3b. <b>CONTACT/EXPOSURE:</b> Contamination (e.g., SPH, contaminated groundwater, vapors).</p> <p>3c. <b>OVEREXERTION:</b> Muscle strain from lifting equipment.</p> <p>3d. <b>CONTACT:</b> Injury while handling wench line/cable, or with active surging equipment</p>	<p>3a See 2b. 3a. Use required PPE including leather/cut-resistant gloves when handling development equipment. Identify finger/hand pinch points. Keep hands away from active surge equipment. 3a. All non-essential personnel should <b>maintain an exclusion zone of 20 feet.</b></p> <p>3b. See 2c. 3b. Wear Nitrile gloves and safety glasses. Insert and remove surge block/plunger and line/cable slowly to avoid splashing at the surface. 3b. Use an absorbent pad to clean any spills.</p> <p>3c. See 2a. 3c. Use mechanical device to insert and remove surge block/plunger if greater than 50lb.</p> <p>3d. If using a drill rig, inspect all wench lines/cables for any kinks or if frayed prior to use. Replace any damaged lines/cables. Review <b>Drill Rig checklist prior to development activities.</b></p> <p>3d. See 3a.</p>
4. Purging well (pumping water to holding tanks/drums/buckets).	<p>4a. <b>CAUGHT:</b> Pinch points associated with connecting hose to tank. Pinch points associated with handling pump and hoses.</p> <p>4b. <b>FALL:</b> Using side mounted ladder when attaching hose to tank.  Slip, trip, fall from lines/hoses</p> <p>4c. <b>CONTACT:</b> Contamination (e.g., SPH, contaminated groundwater).</p> <p>4d. <b>EXERTION:</b> Muscle strain from lifting/carrying equipment.</p> <p>4e. <b>FALL:</b> Spilled purge water.</p>	<p>4a. See 3a. 4a. Ensure that fingers are not placed near coupling when attaching and securing hose(s). Do not place fingers under pump/hoses. Wear leather or cut-resistant gloves when handling pump/hose(s). 4a. Keep hands clear from any line of fire.</p> <p>4b. Inspect ladder steps to make sure steps are not bent/damaged and free of debris/fluid. 4b. Use three points of contact at all times when using ladder. 4b. Utilize anti-whip cords on all compressed hoses. Keep hoses and lines coiled and organized out of designated walking paths around the work zone.</p> <p>4c. Secure water hose. 4c. Do not overfill tanks, and purge/transfer liquids in such a manner that they do not splash. (See 3b). 4c. Dispose of used materials/PPE in the designated impacted PPE container.</p> <p>4d. See 2a.</p> <p>4e. Clean up any spills using absorbent pads or spill kits.</p>
5. Decontaminate equipment	<p>5a. <b>CONTACT/EXPOSURE:</b> Contamination (e.g., SPH, contaminated groundwater, vapors).</p> <p>5b. <b>EXPOSURE/CONTACT:</b> Chemicals in cleaning solution</p>	<p>5a. See 3b.</p> <p>5b. Decontaminate equipment in well-ventilated area. Wear nitrile gloves to avoid skin contact with cleaning solutions.</p>

<sup>1</sup> Each Job or Operation consists of a set of tasks / steps. Be sure to list all the steps needed to perform job.

<sup>2</sup> A hazard is a potential danger. Break hazards into five types: Contact - victim is struck by or strikes an object; Caught - victim is caught on, caught in or caught between objects; Fall - victim falls to ground or lower level (includes slips and trips); Exertion - excessive strain or stress / ergonomics / lifting techniques; Exposure - inhalation/skin hazards; Energy Source – Electricity, Pressure, compression, tension, torque.

<sup>3</sup> Using the first two columns as a guide, decide what actions or procedures are necessary to eliminate or minimize the risk. List the recommended safe operating procedures. Say exactly what needs to be done - such as "use two persons to lift". Avoid general statements such as, "be careful".

<b>JOB SAFETY ANALYSIS</b> Ctrl. No. GEN-005		DATE 2/4/2015	<input type="checkbox"/> NEW <input checked="" type="checkbox"/> REVISED	PAGE 1 of 2
JSA TYPE CATEGORY <b>Generic</b>	WORK TYPE: <b>Gauging and Sampling</b>	WORK ACTIVITY (Description): <b>Gauging and Sampling</b>		
<b>DEVELOPMENT TEAM</b>	<b>POSITION / TITLE</b>	<b>REVIEWED BY:</b>	<b>POSITION / TITLE</b>	
Gina Masciello	Project Scientist	Joe Gentile	Corp H&S Mgr	
Louis Goldstein	Staff Engineer	Michael Ritorto	Project Hydrogeologist	
		Louis Goldstein (as part of annual review)	Staff Engineer	
<b>REQUIRED AND / OR RECOMMENDED PERSONAL PROTECTIVE EQUIPMENT</b>				
<input checked="" type="checkbox"/> LIFE VEST <input checked="" type="checkbox"/> HARD HAT <input type="checkbox"/> LIFELINE / BODY HARNESS <input checked="" type="checkbox"/> SAFETY GLASSES	<input type="checkbox"/> GOGGLES <input type="checkbox"/> FACE SHIELD <input type="checkbox"/> HEARING PROTECTION <input checked="" type="checkbox"/> SAFETY SHOES: <u>Composite-toe or steel toe boots</u>	<input type="checkbox"/> AIR PURIFYING RESPIRATOR <input type="checkbox"/> SUPPLIED RESPIRATOR <input checked="" type="checkbox"/> PPE CLOTHING: <u>Fluorescent reflective vest or high visibility clothing</u>	<input checked="" type="checkbox"/> GLOVES: <u>Leather, Nitrile and cut resistant</u> <input checked="" type="checkbox"/> OTHER: <u>Knee pads, Insect Repellant, sunscreen (as needed)</u>	
<b>REQUIRED AND / OR RECOMMENDED EQUIPMENT</b>				
42-inch Safety Cones, Caution Tape, Interface Probe and/or Water Level Meter, 20-lb., Type ABC Fire Extinguisher, Buckets. Tools as needed: Socket Wrench, Screw Driver, Crow Bar, Mallet, and Wire Brush.				
<b>Commitment to LPS – All personnel onsite will actively participate in SPSA performance by verbalizing SPSAs throughout the day.</b>				
<b>Assess 1JOB STEPS</b>	<b>Analyze 2POTENTIAL HAZARDS</b>	<b>Act 3CRITICAL ACTIONS</b>		
1. Mobilization to monitoring well(s).	1a. <b>FALL:</b> Personal injury from slip/trip/fall due to uneven terrain and/or obstructions.  1b. <b>CONTACT:</b> With traffic/third parties.  1c. <b>EXPOSURE:</b> To biological hazards.	1a. Inspect pathway and plan for most suitable designated pathway prior to mobilization. 1a. Use established pathways, walk and/or drive on stable, secure ground and avoid steep hills or uneven terrain. 1a. If working near open water with an unguarded edge, wear life vest.  1b. Identify potential traffic sources and delineate work area with 42-inch traffic safety cones. Position vehicle to protect against oncoming traffic. Use caution tape to provide a more visible delineation of the work area if necessary. 1b. Wear appropriate PPE including high visibility clothing or reflective vest. 1b. Face traffic, maintain eye contact with oncoming vehicles, and establish a safe exit route.  1c. Inspect work area for bees and insects. 1c. Use insect/tick repellent as necessary.		
2. Open/close well.	2a. <b>ERGONOMICS:</b> Muscle strain.  2b. <b>CAUGHT:</b> Pinch/crush points associated with removing/replacing manholes and working with hand tools.  2c. <b>CAUGHT:</b> Pinch points associated with placing J-plug back onto PVC pipe.  2d. <b>EXPOSURE:</b> To potential hazardous vapors.	2a. Use proper lifting techniques; keep back straight, lift with legs and bend knees when reaching to open/close well.  2b. Wear leather gloves or cut resistant gloves when working with well cover and hand tools. 2b. Use proper tools (ratchet and pry bar for well cover) and inspect before use. 2b. Do not put fingers under well cover.  2c. See 2b. 2c. Keep fingers out of line-of-fire when securing cap  2d. No open flames/heat sources. 2d. To minimize exposure to vapors allow well to vent after opening it and before sampling activities begin. 2d. Stand up-wind, if possible, to avoid vapors.		
3. Gauge well.	3a. <b>CONTACT:</b> With contamination (e.g. contaminated groundwater).  3b. <b>CONTACT:</b> With traffic.	3a. Wear chemical-resistant disposable gloves (over cut-resistant gloves) and safety glasses when gauging well. 3a. Insert and remove probe slowly to avoid splashing. 3a. Use an absorbent pad to clean probe.  3b. See 1b.		

<sup>1</sup> Each Job or Operation consists of a set of tasks / steps. Be sure to list all the steps needed to perform job.

<sup>2</sup> A hazard is a potential danger. Break hazards into five types: Contact - victim is struck by or strikes an object; Caught - victim is caught on, caught in or caught between objects; Fall - victim falls to ground or lower level (includes slips and trips); Exertion - excessive strain or stress / ergonomics / lifting techniques; Exposure - inhalation/skin hazards; Energy Source - electricity, pressure, compression/tension.

<sup>3</sup> Using the first two columns as a guide, decide what actions or procedures are necessary to eliminate or minimize the risk. List the recommended safe operating procedures. Say exactly what needs to be done - such as "use two persons to lift". Avoid general statements such as, "be careful".

Assess <sup>1</sup> JOB STEPS	Analyze <sup>2</sup> POTENTIAL HAZARDS	Act <sup>3</sup> CRITICAL ACTIONS
4. Purge and sample well.	4a. <b>EXPOSURE/CONTACT:</b> To contamination (e.g., SPH, contaminated groundwater, vapors) and/or sample preservatives.	4a. Open and fill sample jars slowly to avoid splashing and contact with preservatives. 4a. Wear cut-resistant gloves and chemical-resistant disposable gloves when sampling. 4a. Fill sample containers over purge container to avoid spilling water onto the ground. 4a. Use an absorbent pad to clean spills. 4a. When using a bailer to purge a well, pull the bailer slowly from the well to avoid splash hazards. 4a. When sampling or purging the water using a bailer, pour out water slowly to reduce the potential for splash hazards with groundwater. 4a. When using a tubing valve always remove the valve slowly after sample collection to release any pressure and avoid pressurized splash hazards 4a. When collecting a groundwater sample always point sampling apparatus (tubing, bailer, etc.) away from face and body.
4. Purge and sample well (Continued).	4b. <b>CONTACT:</b> Personal injury from cuts, abrasions, or punctures by glassware or sharp objects.  4c. <b>ERGONOMICS:</b> Muscle strain while carrying equipment.  4d. <b>CONTACT:</b> With traffic.  4e. <b>CONTACT:</b> Pinch points with groundwater pump components (i.e. wheel, line, clamps)  4f. <b>ERGONOMICS:</b> Muscle strain from repetitive motion of bailing and sampling a well	4b. To avoid spills or breakage, place sample ware on even surface. 4b. Do not over tighten caps on glass sample ware. 4b. Wear chemical-resistant nitrile disposable gloves over cut-resistant (i.e. Kevlar) gloves when sampling and handling glassware (i.e., VOA vials) or when using cutting tools.  4c. Use proper lifting techniques when handling/moving equipment; bend knees and keep back straight. 4c. Use mechanical assistance or team lifting techniques when equipment is 50 lbs. or heavier. 4c. Make multiple trips to carry equipment.  4d. See 1b.  4e. Wear leather gloves when working with groundwater pumps 4e. Never place hands on or near pinch points such as the wheel, clamps or other moving parts during pump operations 4e. Use correct the correct mechanisms, such as a pump reel, to lower pump into well 4e. Never attempt to manually stop any moving part of equipment including hose reels and/or tubing.  4f. See 4c. 4f. Include a stretch break when repetitive motions are part of the task.
5. Management of purge water.	5a. <b>EXPOSURE/CONTACT:</b> To contamination (e.g., SPH, contaminated groundwater, vapors).  5b. <b>ERGONOMICS:</b> Muscle strain from lifting/carrying and moving containers.	5a. Do not overfill container and pour liquids slowly so that they do not splash. 5a. Properly dispose of used materials/PPE in appropriate container in designated storage area.  5b. Use proper lifting techniques when lifting / carrying or moving container(s) (see 4c.). 5b. Do not overfill container(s).
6. Decontaminate equipment.	6a. <b>EXPOSURE/CONTACT:</b> To contamination (e.g., SPH, contaminated groundwater, vapors).  6b. <b>CAUGHT:</b> Pinch points associated with handling hand tools	6a. Work on the upwind side, where possible, of decon area. 6a. Wear chemical-resistant disposable gloves and safety glasses. 6a. Use an absorbent pad to clean spills.  6b. See 2b. 6b. Inspect hand tools for sharp edges before decontaminating

<sup>1</sup> Each Job or Operation consists of a set of tasks / steps. Be sure to list all the steps needed to perform job.

<sup>2</sup> A hazard is a potential danger. Break hazards into five types: Contact - victim is struck by or strikes an object; Caught - victim is caught on, caught in or caught between objects; Fall - victim falls to ground or lower level (includes slips and trips); Exertion - excessive strain or stress / ergonomics / lifting techniques; Exposure - inhalation/skin hazards; Energy Source - electricity, pressure, compression/tension..

<sup>3</sup> Using the first two columns as a guide, decide what actions or procedures are necessary to eliminate or minimize the risk. List the recommended safe operating procedures. Say exactly what needs to be done - such as "use two persons to lift". Avoid general statements such as, "be careful".

<b>JOB SAFETY ANALYSIS</b>		<b>Ctrl. No. GEN-006</b>	DATE 9/15/2015	<input type="checkbox"/> NEW <input checked="" type="checkbox"/> REVISED	PAGE 1 of 2
JSA TYPE CATEGORY <b>Generic</b>		WORK TYPE <b>Surveying</b>	WORK ACTIVITY (Description) <b>Elevation Surveying</b>		
DEVELOPMENT TEAM		POSITION / TITLE	REVIEWED BY:	POSITION / TITLE	
Mark M Emmons		Project Engineer	Daniel Abberton	Health and Safety Officer	
Bjorn Wespestad		Senior Engineer	Michael Ritorto	Project Hydrogeologist	
<b>REQUIRED AND / OR RECOMMENDED PERSONAL PROTECTIVE EQUIPMENT</b>					
<input type="checkbox"/> LIFE VEST <input checked="" type="checkbox"/> HARD HAT <input type="checkbox"/> LIFELINE / BODY HARNESS <input checked="" type="checkbox"/> SAFETY GLASSES	<input type="checkbox"/> GOGGLES <input type="checkbox"/> FACE SHIELD <input type="checkbox"/> HEARING PROTECTION <input checked="" type="checkbox"/> SAFETY SHOES: <u>Steel-toe boots</u>	<input type="checkbox"/> AIR PURIFYING RESPIRATOR <input type="checkbox"/> SUPPLIED RESPIRATOR <input checked="" type="checkbox"/> PPE CLOTHING: <u>Fluorescent reflective vest or high visibility clothing</u>	<input checked="" type="checkbox"/> GLOVES: <u>Cut-resistant or leather</u> <input checked="" type="checkbox"/> OTHER: <u>Long sleeve Shirt</u>		
<b>REQUIRED AND / OR RECOMMENDED EQUIPMENT</b>					
Surveying equipment (i.e., leveling rod/measuring ruler, tripod and scope).					
<b>COMMITMENT TO LPS - All personnel onsite will actively participate in SPSA performance by verbalizing SPSAs throughout the day.</b>					
<b>Assess 1JOB STEPS</b>	<b>Analyze 2POTENTIAL HAZARDS</b>	<b>Act 3CRITICAL ACTIONS</b>			
1. Check in with Site manager/ property owner.	1a. <b>CONTACT/EXPOSURE/FALL:</b> Lack of communication could result in H&S incident.	1a. Inform Site personnel of work scope, timeline and location(s). 1a. Inquire about other activities taking place at the Site. 1a. If applicable, obtain General Work permit for the day.			
2. Locate surveying position for instrument and rod and set-up work area	2a. <b>FALL:</b> Slip/trip hazards.  2b. <b>CONTACT:</b> Traffic (surveying locations could potentially be located in parking areas and sidewalks).  2c. <b>OVEREXERTION:</b> Hazard due to carrying, lifting, and bending while transporting equipment.  2d. <b>CAUGHT/CONTACT:</b> Pinch Points / sharp edges associated with setting up the tripod.	2a. Inspect area for uneven terrain, weather-related hazards (i.e., ice, puddles, snow, etc.), and obstructions prior to setting up at the survey location. Keep eyes engaged with walking surface while in movement. Remember "Walking is Working" 2a. Conduct housekeeping and maintain clear paths to walk in and remove debris as required.  2b. Be aware of oncoming traffic. Utilize a flagman / spotter for locations in streets or high-traffic areas. 2b. Place 42 inch cones around the work area, and delineate work zone with caution tape ,snow fencing or safety bars, if necessary. 2b. Wear appropriate PPE including long sleeve high visibility clothing and or reflective safety vest. 2b. Face traffic, maintain eye contact with oncoming vehicles, and establish a safe exit route.  2c. Use proper body positioning and lifting techniques; keep back straight, lift with legs, keep load close to body, and never reach with a load. 2c. Avoid carrying too much equipment at one time and team-lift equipment that is more than 50 lb.  2d. Wear cut resistant gloves when handling the tripod and keep fingers away from pinch points located near moving parts of the tripod. Don't carry tripod by the pointed ends.			
3. Open / close manhole cover to well that is being surveyed (if necessary).	3a. <b>OVEREXERTION:</b> Muscle strain  3b. <b>CAUGHT:</b> Pinch points associated with removing / replacing manholes and working with hand tools.  3c. <b>EXPOSURE:</b> To potentially hazardous vapors.  To biological hazards.  3d. <b>CONTACT:</b> With traffic.	3a. See 1c. Bend knees when reaching to open well. Use manhole lifting hook or pry bar to avoid bending. 3b. Wear leather gloves or cut resistant gloves when working with well cover and hand tools. 3b. Use proper tools (ratchet and crowbar or pry bar for well cover) and inspect before use. 3b. Do not put fingers under well cover.  3c. No open flames/heat sources. 3c. To minimize exposure to vapors allow well to vent after opening it and before survey activities begin. 3c. Work on the upwind side of manhole/well. 3c. Use caution while opening up lids to inspect work area for bees and insects inside of covers. 3c. Use insect/tick repellent as necessary.  3d. See 2b.			

<sup>1</sup> Each Job or Operation consists of a set of tasks / steps. Be sure to list all the steps needed to perform job.

<sup>2</sup> A hazard is a potential danger. Break hazards into five types: Contact - victim is struck by or strikes an object; Caught - victim is caught on, caught in or caught between objects; Fall - victim falls to ground or lower level (includes slips and trips); Exertion - excessive strain or stress / ergonomics / lifting techniques; Exposure - inhalation/skin hazards; Energy Source - electricity, pressure, compression/tension.

<sup>3</sup> Using the first two columns as a guide, decide what actions or procedures are necessary to eliminate or minimize the risk. List the recommended safe operating procedures. Say exactly what needs to be done - such as "use two persons to lift". Avoid general statements such as, "be careful".

Assess <sup>1</sup> JOB STEPS	Analyze <sup>2</sup> POTENTIAL HAZARDS	Act <sup>3</sup> CRITICAL ACTIONS
4. Perform survey.	4a. <b>FALL:</b> Slip/trip hazards  4b. <b>CONTACT:</b> Traffic (surveying locations could be potentially located in parking areas and sidewalks)	4a. See 2a.  4b. See 2b. 4b. Personnel using the scope will be devoting most of their attention to the surveying activity and shall be aware of vehicular and pedestrian traffic. Personnel holding the measuring stick should be extra vigilant of survey personnel and communicate any potential hazards to the instrument person via handheld radio or similar means. Ensure reflective safety vest is worn.
5. Break down work area.	5a. <b>CONTACT:</b> Traffic (surveying locations can potentially be located in parking areas and sidewalks).  5b. <b>EXERTION:</b> Hazard due to carrying, lifting, and bending while transporting equipment	5a. See 2b.  5b. See 2c.

<sup>1</sup> Each Job or Operation consists of a set of tasks / steps. Be sure to list all the steps needed to perform job.

<sup>2</sup> A hazard is a potential danger. Break hazards into five types: Contact - victim is struck by or strikes an object; Caught - victim is caught on, caught in or caught between objects; Fall - victim falls to ground or lower level (includes slips and trips); Exertion - excessive strain or stress / ergonomics / lifting techniques; Exposure - inhalation/skin hazards; Energy Source – electricity, pressure, compression/tension.

<sup>3</sup> Using the first two columns as a guide, decide what actions or procedures are necessary to eliminate or minimize the risk. List the recommended safe operating procedures. Say exactly what needs to be done - such as "use two persons to lift". Avoid general statements such as, "be careful".

<b>JOB SAFETY ANALYSIS</b> Ctrl. No. GEN-006		DATE 1/4/2018	<input type="checkbox"/> NEW <input checked="" type="checkbox"/> REVISED	PAGE 1 of 2
JSA TYPE CATEGORY: <b>Generic</b>		WORK TYPE: <b>Drilling</b>	WORK ACTIVITY (Description): <b>Direct Push Soil Borings / Well Installation</b>	
<b>DEVELOPMENT TEAM</b>		<b>POSITION / TITLE</b>	<b>REVIEWED BY:</b>	<b>POSITION / TITLE</b>
Timothy Zei		Project Hydrogeologist	Raymond Olson	Staff Assistant Geologist
			Christine Pietrzyk	Office Health & Safety Manager
			Brian Hobbs	Senior Health & Safety Manager
			Joe Gentile	Corporate Health & Safety Manager
<b>REQUIRED AND / OR RECOMMENDED PERSONAL PROTECTIVE EQUIPMENT</b>				
<input type="checkbox"/> LIFE VEST <input checked="" type="checkbox"/> HARD HAT <input type="checkbox"/> LIFELINE / BODY HARNESS <input checked="" type="checkbox"/> SAFETY GLASSES	<input type="checkbox"/> GOGGLES <input type="checkbox"/> FACE SHIELD <input checked="" type="checkbox"/> HEARING PROTECTION: (as needed) <input checked="" type="checkbox"/> SAFETY SHOES: Composite-toe or steel toe boots	<input type="checkbox"/> AIR PURIFYING RESPIRATOR <input type="checkbox"/> SUPPLIED RESPIRATOR <input checked="" type="checkbox"/> PPE CLOTHING: <u>Fluorescent reflective vest or high visibility clothing, Long Sleeve Shirt</u>	<input checked="" type="checkbox"/> GLOVES: <u>Leather, Nitrile and cut resistant</u> <input checked="" type="checkbox"/> OTHER: <u>Insect Repellent, sunscreen (as needed)</u>	
<b>REQUIRED AND / OR RECOMMENDED EQUIPMENT</b>				
Geoprobe or Truck-Mounted Direct Push Drill Rig, Hand Tools, Photoionization Detector, Multi-Gas Meter (or equivalent), Macrocore liners, Liner Opening Tool, 20 lb. Type ABC Fire Extinguisher, 42" Cones & Flags, "Work Area" Signs, Water				
<b>COMMITMENT TO SAFETY-</b> All personnel onsite will actively participate in hazard recognition and mitigation throughout the day by verbalizing SPSAs				
<b>EXCLUSION ZONE (EZ) – All non-essential personnel will maintain a distance of 10 feet from drilling equipment while equipment is moving/engaged</b>				
<b>"SHOW ME YOUR HANDS"</b>				
<b>Driller and helper should show that hands are clear from controls and moving parts</b>				
<b>Assess JOB STEPS</b>	<b>Analyze POTENTIAL HAZARDS</b>	<b>Act CRITICAL ACTIONS</b>		
1. Mobilization of drilling rig (ensure the Subsurface Clearance Protocol and Drill Rig Checklist are completed)	1a. <b>CONTACT:</b> Equipment/property damage.  1b. <b>FALL:</b> Slip/trip/fall hazards.  1c. <b>CONTACT:</b> Crushing from roll-over.	1a. The drill rig's tower/derrick will be lowered and secured prior to mobilization. 1a. A spotter should be utilized while moving the drill rig. If personnel move into the path of the drill rig, the drill rig will be stopped until the path is again clear. Use a spotter for all required backing operations. 1a. Set-up the work area and position equipment in a manner that eliminates or reduces the need for backing of support trucks and trailers. 1a. When backing up truck rig with an attached trailer use a second spotter if there is tight clearance simultaneously on multiple sides of the equipment or if turning angles limit driver visibility. 1a. Inspect the driving path for uneven terrain. Level or avoid if needed. 1a. Drill rig should have a minimum <b>exclusion zone of 10 feet</b> for non-essential personnel (i.e., driller helper, geologist) when the rig is moving/ in operation.  1b. Inspect walking path for uneven terrain, weather-related hazards (i.e., ice, puddles, snow, etc.), and obstructions prior to mobilizing equipment. 1b. Do not climb over stored materials/equipment; walk around. Practice good housekeeping. 1b. Use established pathways and walk on stable, secure ground. 1c. Geoprobe should cross all hills/obstructions head on with the mast down to reduce risk of roll-over.		
2. Raising tower/derrick of drill rig	2a. <b>CONTACT:</b> Overhead hazards.  2b. <b>CONTACT:</b> Pinch Points/Amputation Points when raising the rig and instability of rig	2a. Prior to raising the tower/derrick, the area above the drilling rig will be inspected for wires, tree limbs, piping, or other structures, that could come in contact with the rig's tower and/or drilling rods or tools. 2a. Maintain a safe distance of 10' from overhead structures.  2b. Inspect the equipment prior to use and avoid pinch/amputation points. 2b. Lower outriggers to ensure stability prior to raising rig tower/derrick. 2b. If the rig needs to be mounted, be sure to use three points of contact.		
3. Advancement of drilling equipment and well installation	3a. <b>CONTACT:</b> Flying debris  3b. <b>EXPOSURE:</b> Noise and dust.	3a. Be aware of and avoid potential lines of fire and wear required PPE such as eye, ear, and hand protection.  3b. Wet borehole area with sprayer to minimize dust. 3b. Stand upwind and keep body away from rig. 3b. Dust mask should be worn if conditions warrant. 3b. Wear hearing protection when the drill rig is in operation.		

<sup>1</sup> Each Job or Operation consists of a set of tasks / steps. Be sure to list all the steps needed to perform job.

<sup>2</sup> A hazard is a potential danger. Break hazards into five types: Contact - victim is struck by or strikes an object; Caught - victim is caught on, caught in or caught between objects; Fall - victim falls to ground or lower level (includes slips and trips); Exertion - excessive strain or stress / ergonomics / lifting techniques; Exposure - inhalation/skin hazards; Energy Source – electricity, pressure, compression/tension.

<sup>3</sup> Using the first two columns as a guide, decide what actions or procedures are necessary to eliminate or minimize the risk. List the recommended safe operating procedures. Say exactly what needs to be done - such as "use two persons to lift". Avoid general statements such as, "be careful".

Assess 1JOB STEPS	Analyze 2POTENTIAL HAZARDS	Act 3CRITICAL ACTIONS
3. Advancement of drilling equipment and well installation (Continued)	<p><b>3a. CONTACT:</b> Flying debris</p> <p><b>3b. EXPOSURE:</b> Noise and dust.</p> <p><b>3c. FALL:</b> Slip/trip/fall hazards.</p> <p><b>3d. CAUGHT:</b> Limb/extremity pinching; abrasion/crushing.</p> <p><b>3e. CONTACT:</b> Equipment imbalance during advancement of drill equipment.</p> <p><b>3f. EXPOSURE:</b> Inhalation of contamination/vapors.</p> <p><b>3g. EXERTION:</b> Potential for muscle strain/injury while lifting and installing well casings, lifting sand bags, and/or lifting rods.</p>	<p>3c. Contain drill cuttings and drilling water to prevent fall hazards from developing in work area.</p> <p>3c. See 1b.</p> <p>3d. Ensure all Emergency Safety Stop buttons function properly.</p> <p>3d. Always wear leather gloves when making connections and using hand tools; wear cut-resistant (i.e., Kevlar) gloves when handling cutting tools.</p> <p>3d. Inspect the equipment prior to use for potential pinch/amputation points. Keep hands away from pinch/amputation points and use of tools is preferable compared to fingers and hands.</p> <p>3d. Inspect drill head for worn surface or missing teeth; replace if damaged or blunt.</p> <p>3d. Ensure all jewelry is removed, loose clothing is secured, and PPE is secured close to the body.</p> <p>3d. All non-essential personnel should stay away from the immediate work area; position body out of the line-of-fire of equipment.</p> <p>3d. Drillers and helpers will understand and use the "Show Me Your Hands" Policy.</p> <p>3d. Spinning rods/casing have an <b>exclusion zone of 10 feet</b> while in operation.</p> <p>3e. Drillers will advance the borehole with caution to avoid causing the rig to become imbalanced and/or tip.</p> <p>3e. The blocking and leveling devices used to secure the rig will be inspected by drillers and Roux personnel regularly to see if shifting has occurred.</p> <p>3e. In addition, personnel and equipment that are non-essential to the advancement of the borehole will be positioned away from the rig at a distance that is at least as far as the boom is high (<b>minimum exclusion zone of 10 feet</b>).</p> <p>3f. Monitor ambient air for dangerous conditions using a calibrated photoionization detector (PID) to periodically monitor the breathing zone of the work area.</p> <p>3f. If a reading of &gt;5ppm is recorded, the Roux field personnel must temporarily cease work, instruct all Site personnel to step away from the area of elevated readings and inform the Roux PM of the condition. The Roux PM will then recommend additional precautions in accordance with the site specific health and safety plan.</p> <p>3f. Use a multi-gas meter to monitor ambient air for dangerous conditions (i.e. unsafe levels of carbon monoxide when drilling indoors or the presence of explosive vapors).</p> <p>3g. Keep back straight and bend at the knees.</p> <p>3g. Utilize team lifting for objects over 50lbs.</p> <p>3g. Use mechanical lifting device for odd shaped objects.</p>
4. Remove sample liner.	<p><b>4a. EXERTION:</b> Potential for muscle strain/injury while removing liner from probe rod.</p> <p><b>4b. CONTACT:</b> Pinch points and cuts</p> <p><b>4c. EXPOSURE:</b> Inhalation and/or dermal contact with contaminants.</p>	<p>4a. Utilize team lifting for objects over 50lbs.</p> <p>4a. Use hydraulic liner extruder if available.</p> <p>4b. Place liner on sturdy surface when opening.</p> <p>4b. Don cut-resistant gloves and use appropriate liner cutter when opening liners.</p> <p>4b. Always cut away from the body.</p> <p>4c. Wear chemical-resistant disposable gloves when handling liners.</p> <p>4c. See 3e.</p>
5. Decontaminate equipment.	<p><b>5a. EXPOSURE/CONTACT:</b> To contamination (e.g., Separate Phase Hydrocarbons (SPH), contaminated groundwater, vapors).</p> <p><b>5b. EXPOSURE:</b> To chemicals in cleaning solution including ammonia.</p>	<p>5a. Wear chemical-resistant disposable gloves and safety glasses.</p> <p>5a. Contain decontamination water so that it does not spill.</p> <p>5a. Use an absorbent pad to clean spills, if necessary.</p> <p>5a. Spray equipment from side angle, not straight on, to avoid backsplash.</p> <p>5a. See 3b.</p> <p>5b. See 4a. Review SDS to ensure appropriate precautions are taken and understood.</p>

<sup>1</sup> Each Job or Operation consists of a set of tasks / steps. Be sure to list all the steps needed to perform job.

<sup>2</sup> A hazard is a potential danger. Break hazards into five types: Contact - victim is struck by or strikes an object; Caught - victim is caught on, caught in or caught between objects; Fall - victim falls to ground or lower level (includes slips and trips); Exertion - excessive strain or stress / ergonomics / lifting techniques; Exposure - inhalation/skin hazards; Energy Source - electricity, pressure, compression/tension.

<sup>3</sup> Using the first two columns as a guide, decide what actions or procedures are necessary to eliminate or minimize the risk. List the recommended safe operating procedures. Say exactly what needs to be done - such as "use two persons to lift". Avoid general statements such as, "be careful".

<b>JOB SAFETY ANALYSIS</b>		<b>Ctrl. No. GEN-009</b>	DATE: 1/4/2018	<input type="checkbox"/> NEW <input checked="" type="checkbox"/> REVISED	PAGE 1 of 1
JSA TYPE CATEGORY <b>Generic</b>		WORK TYPE <b>O&amp;M</b>	WORK ACTIVITY (Description) <b>Movement of 55-Gallon Drums/Drum Handling with Mobile Carrier</b>		
<b>DEVELOPMENT TEAM</b>		<b>POSITION / TITLE</b>		<b>REVIEWED BY:</b>	
Michael Sami		Technician		Brian Hobbs	
				Joe Gentile	
				Senior Health & Safety Manager	
				Corporate Health & Safety Manager	
<b>REQUIRED AND / OR RECOMMENDED PERSONAL PROTECTIVE EQUIPMENT</b>					
<input type="checkbox"/> LIFE VEST <input checked="" type="checkbox"/> HARD HAT <input type="checkbox"/> LIFELINE / BODY HARNESS <input checked="" type="checkbox"/> SAFETY GLASSES		<input type="checkbox"/> GOGGLES <input type="checkbox"/> FACE SHIELD <input type="checkbox"/> HEARING PROTECTION <input checked="" type="checkbox"/> SAFETY SHOES: <u>Steel or composite toe</u>		<input type="checkbox"/> AIR PURIFYING RESPIRATOR <input type="checkbox"/> SUPPLIED RESPIRATOR <input checked="" type="checkbox"/> PPE CLOTHING: <u>Fluorescent long sleeve shirt or long sleeve shirt and reflective safety vest.</u>	
				<input checked="" type="checkbox"/> GLOVES: <u>Cut-resistant gloves</u> <input type="checkbox"/> OTHER:	
<b>REQUIRED AND / OR RECOMMENDED EQUIPMENT</b>					
Mobile Drum Carrier, safety cones, and caution tape					
<b>COMMITMENT TO SAFETY</b> - All personnel onsite will actively participate in hazard recognition and mitigation throughout the day by verbalizing SPSAs					
<b>EXCLUSION ZONE (EZ): A 10-foot exclusion zone will be maintained around heavy equipment (i.e. forklift).</b>					
<b>Assess 1JOB STEPS</b>		<b>Analyze 2POTENTIAL HAZARDS</b>		<b>Act 3CRITICAL ACTIONS</b>	
1. Preparing for and Inspection of Drum		<b>1a. FALL:</b> Tripping/falling due to uneven surface. Loose debris/garbage in work area.  <b>1b. CONTACT/EXPOSURE:</b> Drums could potentially be damaged or contain hazardous material. Mobile drum carrier could potentially be in poor working condition causing malfunctioning during operation.  <b>1c. EXERTION/CAUGHT:</b> Potential pinching/exertion hazards while securing ring/tightening bolts		1a. Clear area of loose garbage and debris. Inspect 55-gal drums for proper condition, labeling, check drum ring and bolts for tightness, inspect mobile drum carrier.  1a. Do a Test Lift to get a general sense of the weight of the drum.  1a. Inspect and use established pathways to avoid uneven terrain, weather-related hazards (i.e., debris, puddles, ice, etc.), and other obstructions.  1a. Secure work area and coordinate and communicate the planned work activities with other personnel working in the area.  1a. Delineate work area with 42" safety cones.  1b. Prior to inspecting drums don cut-resistant gloves. If drum is not properly labeled, do not open and cease all drum transport activities. Immediately contact project manager and inform him/her of drum situation.  1b. Do not continue drum transport activities until further actions are determined by the project manager.  1b. If the drum is properly labeled, but leaking, improperly sealed or in poor condition, place drum in an over-pack drum.  1b. Inspect mobile drum carrier to ensure its overall integrity. Look for rust marks or potential weak points where the drum carrier could malfunction. Inspect the wheels to ensure that they easily turn and nothing is impeding their movement.  1c. Keep back straight and knees slightly bent while securing drum ring/tightening bolt. Wear cut-resistant gloves.	
2. Position drum clamp tightly in between drum ribs, securing drum clamp to drum with chain		2a. <b>CAUGHT:</b> Pinching fingers between drum clamp and handle/chain.		2a. Attach drum clamp with chain and tighten until snug. Do not place hands between drum clamp and drum as the chain is tightened; wear cut resistant gloves. Keep face away from drum when handling in case of escaping vapors.	

<sup>1</sup> Each Job or Operation consists of a set of tasks / steps. Be sure to list all the steps needed to perform job.  
<sup>2</sup> A hazard is a potential danger. Break hazards into six types: Contact - victim is struck by or strikes an object; Caught - victim is caught on, caught in or caught between objects; Fall - victim falls to ground or lower level (includes slips and trips); Exertion - excessive strain or stress / ergonomics / lifting techniques; Exposure - inhalation/skin hazards; Energy source - electricity, pressure, compression/tension.  
<sup>3</sup> Using the first two columns as a guide, decide what actions or procedures are necessary to eliminate or minimize the risk. List the recommended safe operating procedures. Say exactly what needs to be done - such as "use two persons to lift." Avoid general statements such as, "be careful."



Assess <sup>1</sup> JOB STEPS	Analyze <sup>2</sup> POTENTIAL HAZARDS	Act <sup>3</sup> CRITICAL ACTIONS
<p><b>3.</b> Disengage safety latches on handle, pull handle down until drum is lifted off ground and safety latches are reengaged; slightly suspending drum off the ground</p>	<p><b>3a. EXERTION/ CONTACT:</b> Potential muscle strain associated with lifting/engaging drum/handle. Drum could shift/slip downward and crush toes.</p> <p><b>3b. CAUGHT:</b> Fingers could be pinched while engaging/disengaging safety latches on handle</p>	<p>3a. Ascertain whether the drum is overweight; if it is, then two people are needed to lower handle while drum is secured with clamp so that safety latches can be engaged. Keep body out of the line of fire of the handle (do not position head above handle) as it is being pushed down. Do not allow feet/toes to be positioned under the drum as it is being lifted; wear steel/composite toe boots.</p> <p>3b. Wear cut-resistant gloves while disengaging/reengaging safety latches.</p> <p>3b. Avoid placing hands in pinch points.</p>
<p><b>4.</b> Transport drums to designated location and disengage drum clamp (repeat Step 3 in reverse order)</p>	<p><b>4a. FALL:</b> Tripping/ falling due to obstructions and uneven terrain. Potential for drum to fall during transport.</p>	<p>4a. Ensure transport path is free of potential obstructions that may cause the drum/carrier to become unstable. Position drum clamp between the ribs on the drum to prevent possible slipping.</p>

<sup>1</sup> Each Job or Operation consists of a set of tasks / steps. Be sure to list all the steps needed to perform job.

<sup>2</sup> A hazard is a potential danger. Break hazards into six types: Contact - victim is struck by or strikes an object; Caught - victim is caught on, caught in or caught between objects; Fall - victim falls to ground or lower level (includes slips and trips); Exertion - excessive strain or stress / ergonomics / lifting techniques; Exposure - inhalation/skin hazards; Energy source – electricity, pressure, compression/tension.

<sup>3</sup> Using the first two columns as a guide, decide what actions or procedures are necessary to eliminate or minimize the risk. List the recommended safe operating procedures. Say exactly what needs to be done - such as "use two persons to lift." Avoid general statements such as, "be careful."

<b>JOB SAFETY ANALYSIS</b>		<b>Cntrl. No. GEN-009</b>	DATE: 2/11/2015	<input type="checkbox"/> NEW <input checked="" type="checkbox"/> REVISED	PAGE 1 of 2
<b>JSA TYPE CATEGORY</b> <b>GENERIC</b>		<b>WORK TYPE</b> <b>Hand Tools</b>	<b>WORK ACTIVITY (Description)</b> <b>Pre-Clearing activities, including Air Knifing and Soil Vacuuming</b>		
<b>DEVELOPMENT TEAM</b>	<b>POSITION / TITLE</b>	<b>REVIEWED BY:</b>		<b>POSITION / TITLE</b>	
Alyssa Lau	Staff Engineer	Daniel Abberton		SHSM	
		Mike Ritorto		Senior Hydrogeologist	
		Laura Jensen		Staff Hydrogeologist	
<b>REQUIRED AND / OR RECOMMENDED PERSONAL PROTECTIVE EQUIPMENT</b>					
<input type="checkbox"/> LIFE VEST <input checked="" type="checkbox"/> HARD HAT <input type="checkbox"/> LIFELINE / BODY HARNESS <input checked="" type="checkbox"/> SAFETY GLASSES	<input type="checkbox"/> GOGGLES <input checked="" type="checkbox"/> FACE SHIELD (while air knifing) <input checked="" type="checkbox"/> HEARING PROTECTION (as needed) <input checked="" type="checkbox"/> SAFETY SHOES: <u>Steel or composite toed</u>	<input type="checkbox"/> AIR PURIFYING RESPIRATOR <input type="checkbox"/> SUPPLIED RESPIRATOR <input checked="" type="checkbox"/> PPE CLOTHING: <u>Fluorescent reflective vest or high visibility clothing</u>	<input checked="" type="checkbox"/> GLOVES: <u>Nitrile and cut resistant</u> <input checked="" type="checkbox"/> OTHER: <u>Dust mask (as needed)</u>		
<b>REQUIRED AND / OR RECOMMENDED EQUIPMENT</b>					
Required Equipment: Air Knife, Vactor Truck (Vac Truck), Compressor, Hand Tools, Circular Saw, Dust Mask, Photoionization Detector, Multi-Gas Meter, Traffic Cones, Rigid Barrier, Caution Tape, 20 lb. Fire Extinguisher, "Work Area" and/or "Exclusion Zone" Signs					
<b>Commitment to LPS</b> – All personnel onsite will actively participate in SPSA performance by verbalizing SPSAs throughout the day.					
<b>EXCLUSION ZONE: A 10 foot exclusion zone will be maintained around air knife and/or soil vacuum operations.</b>					
<b>Assess</b> <b>1<sup>1</sup> JOB STEPS</b>	<b>Analyze</b> <b>2<sup>2</sup>POTENTIAL HAZARDS</b>	<b>Act</b> <b>3<sup>3</sup>CRITICAL ACTIONS</b>			
1. Verify pre-clearance protocol.	1a. <b>CONTACT:</b> Underground utility damage; property damage; personal injury.  See Site Walk Inspection JSA for potential hazards.	1a. Confirm that local utility companies were contacted prior to drilling. 1a. Walk the Site to evaluate utility markings and review maps ( <b>See Site Walk Inspection JSA for critical actions</b> ). 1a. Review pre-clearing checklist form and sub-surface clearance form. Pre-clearing protocol indicates that clearance must be conducted to a minimum of 5 vertical feet below ground surface or 8 vertical feet below ground surface in the critical zone using hand tools.			
2. Mobilize/demobilize and establish work area.	2a. <b>See Mobilization / Demobilization JSA for potential hazards.</b>	2a. <b>See Mobilization / Demobilization JSA for critical actions.</b>			
3. Pre-clear with air knife, water lance, and soil vacuum, and/or clearance with hand tools	3a. <b>CONTACT:</b> Flying debris striking face or body  3b. <b>EXPOSURE/ENERGY SOURCE:</b> Inhalation/exposure to hazardous vapors; inhalation/exposure to dust; electrocution.  3c. <b>CONTACT:</b> Damage to unknown/known utility with air knife.  3d. <b>ERGONOMICS</b> Poor body positioning when handling equipment and materials.	3a. <b>Maintain 10 foot exclusion zone.</b> Only (air knife/vac truck) operator and designated helper shall remain within exclusion zone while air knife/vac truck is active. Use the required PPE, including (at a minimum), cut resistant gloves, safety glasses with side shields, and long sleeved shirt. 3a. Wear a face shield to protect face from flying debris when using air knife. 3a. Aim air knife tip away from self and others, so to avoid line-of-fire hazards. 3a. Use anti-whip devices on compressor hoses. 3b. Monitor breathing zone with a calibrated PID and multi-gas meter. If vapors sustain levels > 5 ppm, the Roux field personnel must temporarily cease work, instruct all Site personnel to step away from the area of elevated readings and inform the Roux Project Manager of the condition. The Roux Project Manager will then recommend additional precautions. 3b. Wear dust masks as needed 3b. Ensure no open flames/heat sources are present within the work area. 3b. No open flames/heat sources. 3b. Ensure vac truck is properly grounded prior to use. 3b. Do not use metal dig bar; use fiberglass or equivalent. 3c. Avoid contacting utilities directly with the high pressure air stream and using the air knife tip as a physical digging tool. 3c. Keep the air knife tip constantly moving to reduce direct pressure on a potential utility. 3c. increase the distance between air knife tip and soil/utility. 3c. Continually remove soil slurry from hole with vacuum, which may have an abrasive effect on utility casings. 3d. Use proper body positioning and lifting techniques that minimizes muscle strain; keep back straight, lift with legs, keep load close to body, and never reach with a load.			

<sup>1</sup> Each Job or Operation consists of a set of tasks / steps. Be sure to list all the steps needed to perform job.

<sup>2</sup> A hazard is a potential danger. Break hazards into five types: Contact - victim is struck by or strikes an object; Caught - victim is caught on, caught in or caught between objects; Fall - victim falls to ground or lower level (includes slips and trips); Exertion - excessive strain or stress / ergonomics / lifting techniques; Exposure - inhalation/skin hazards; Energy Source – electricity, pressure, compression/tension.

<sup>3</sup> Using the first two columns as a guide, decide what actions or procedures are necessary to eliminate or minimize the risk. List the recommended safe operating procedures. Say exactly what needs to be done - such as "use two persons to lift." Avoid general statements such as, "be careful."

Assess <sup>1</sup> JOB STEPS	Analyze <sup>2</sup> POTENTIAL HAZARDS	Act <sup>3</sup> CRITICAL ACTIONS
3. Pre-clearing with air knife and soil vacuum, and/or clearance with hand tools (continued)	<p>3d. <b>ERGONOMICS:</b> (continued) Poor body positioning when handling equipment and materials.</p> <p>3e. <b>FALL:</b> Tripping/falling due to uneven terrain, weather conditions, and materials/equipment stored at the Site.</p> <p>3f. <b>CAUGHT:</b> Pinch points or amputation points associated with the equipment and vacuum hose.</p> <p>3g. <b>EXPOSURE:</b> Noise from vac truck and/or air compressor.</p>	<p>3d. Ensure that loads are balanced to reduce the potential for muscle strain.</p> <p>3d. Two people or a mechanical lifting aid are required when lifting objects over 50 lb. or when the shape makes the object difficult to lift.</p> <p>3e. Inspect walking path for uneven terrain, weather-related hazards (e.g., ice, puddles, snow, etc.), and obstructions prior to mobilizing equipment.</p> <p>3e. Walk around any stored materials/equipment; do not climb over. Practice good housekeeping.</p> <p>3e. Use established pathways and walk on stable, secure ground.</p> <p>3e. Equipment and tools will be stored at the lowest point of potential energy and out of the walkway and immediate work area (i.e., tools should not be propped against walls or nearby equipment or vehicles).</p> <p>3e. Equipment and tools that are not anticipated to be used will be returned to a storage area that is out of the immediate work area.</p> <p>3e. Ensure power cords/hoses are grouped when used within the work area. Mark out cords/hoses that cross pathways with traffic cones.</p> <p>3e. Ensure all Site personnel and equipment stay a minimum of 2 feet from an open hole. Mark out open holes with traffic cones/caution tape, etc.</p> <p>3e. Pre-cleared location will be finished flush to grade as to prevent a slip/trip hazard.</p> <p>3f. Always wear cut-resistant gloves when making connections and using hand tools.</p> <p>3f. Inspect the equipment prior to use for potential pinch points.</p> <p>3f. Test all emergency shutdown devices prior to using equipment.</p> <p>3f. Ensure all jewelry is removed, loose clothing is secured, and PPE is secured close to the body.</p> <p>3f. <b>All non-essential personnel shall maintain a 10 foot exclusion zone;</b> position body out of the line-of-fire.</p> <p>3f. <b>Drillers and helpers will understand and use the “Show Me Your Hands Policy”.</b></p> <p>3g. Wear hearing protection when vac truck and air compressor are in operation. Otherwise, if sound levels exceed 85 dB, don hearing protection.</p>
4. Move drum to staging area using drum cart.	<p>4a. <b>EXPOSURE/CONTACT:</b> Contamination (e.g., Separate Phase Hydrocarbons (SPH), contaminated groundwater, soil).</p> <p>4b. <b>ERGONOMICS:</b> Muscle strain while maneuvering drums with drum cart/lift gate.</p> <p>4c. <b>CAUGHT:</b> Pinch points or amputation points associated with handling drum lid.</p>	<p>4a. Wear chemically resistant gloves (i.e., Nitrile; worn in addition to cut resistant gloves).</p> <p>4a. Do not overfill drums. Ensure that the drum lids are attached securely.</p> <p>4a. Stage all drums in the designated storage area (per Roux Project Manager) and ensure they are labeled.</p> <p>4b. See 3d. Do not overfill drums. Use lift gate on back of truck to load and unload drums or drum cart to transport drums.</p> <p>4c. Ensure that fingers are not placed under the lid of the drum. Wear cut-resistant gloves. Use 15/16” ratchet while sealing drum lid.</p>
5. Decontaminate equipment and tools.	<p>5a. <b>EXPOSURE/CONTACT:</b> To contamination (e.g., Separate Phase Hydrocarbons (SPH), contaminated groundwater, vapors).</p> <p>5b. <b>EXPOSURE:</b> To chemicals in cleaning solution.</p>	<p>5a. See 4a.</p> <p>5a. Contain decontamination water (closed lid) so that it does not spill.</p> <p>5a. Use an absorbent pad to clean spills, if necessary.</p> <p>5a. Store all impacted materials/PPE in a designated storage container (per Roux Project Manager) and ensure the container is labeled.</p> <p>5b. See 4a.</p>

<sup>1</sup> Each Job or Operation consists of a set of tasks / steps. Be sure to list all the steps needed to perform job.

<sup>2</sup> A hazard is a potential danger. Break hazards into five types: Contact - victim is struck by or strikes an object;

Caught - victim is caught on, caught in or caught between objects; Fall - victim falls to ground or lower level (includes slips and trips); Exertion - excessive strain or stress / ergonomics / lifting techniques; Exposure - inhalation/skin hazards; Energy Source – electricity, pressure, compression/tension.

<sup>3</sup> Using the first two columns as a guide, decide what actions or procedures are necessary to eliminate or minimize the risk. List the recommended safe operating procedures. Say exactly what needs to be done - such as "use two persons to lift". Avoid general statements such as, "be careful".

<b>JOB SAFETY ANALYSIS</b>		<b>Ctrl. No. GEN-015</b>	DATE: 1/4/2018	<input type="checkbox"/> NEW <input checked="" type="checkbox"/> REVISED	PAGE 1 of 2
JSA TYPE CATEGORY <b>GENERIC</b>		WORK TYPE <b>Site Recon</b>	WORK ACTIVITY (Description) <b>Mobilization/Demobilization</b>		
<b>DEVELOPMENT TEAM</b>		<b>POSITION / TITLE</b>	<b>REVIEWED BY:</b>	<b>POSITION / TITLE</b>	
Rebecca Lowy		Staff Assistant Geologist	Brian Hobbs	Senior Health & Safety Manager	
Tally Sodre		OHSM	Joe Gentile	Corporate Health & Safety Manager	
<b>REQUIRED AND / OR RECOMMENDED PERSONAL PROTECTIVE EQUIPMENT</b>					
<input type="checkbox"/> LIFE VEST <input checked="" type="checkbox"/> HARD HAT <input type="checkbox"/> LIFELINE / BODY HARNESS <input checked="" type="checkbox"/> SAFETY GLASSES		<input type="checkbox"/> GOGGLES <input type="checkbox"/> FACE SHIELD <input checked="" type="checkbox"/> HEARING PROTECTION (as needed) <input checked="" type="checkbox"/> SAFETY SHOES: <u>Steel Toe or composite toe</u>	<input type="checkbox"/> AIR PURIFYING RESPIRATOR <input type="checkbox"/> SUPPLIED RESPIRATOR <input checked="" type="checkbox"/> PPE CLOTHING: <u>Fluorescent reflective vest of high-visibility clothing; long sleeve shirt; long pants</u>	<input checked="" type="checkbox"/> GLOVES: <u>Leather, nitrile, and cut resistant (as needed)</u> <input type="checkbox"/> OTHER	
<b>REQUIRED AND / OR RECOMMENDED EQUIPMENT</b>					
Required Equipment: None					
<b>COMMITMENT TO SAFETY-</b> All personnel onsite will actively participate in hazard recognition and mitigation throughout the day by verbalizing SPSAs					
<b>EXCLUSION ZONE (EZ): A 10-foot exclusion zone will be maintained around equipment in use..</b>					
<b>Assess 1JOB STEPS</b>	<b>Analyze 2POTENTIAL HAZARDS</b>	<b>Act 3CRITICAL ACTIONS</b>			
1. Mobilize/demobilize and establish work area	<b>1a. FALL:</b> Slip/trips/falls from obstructions, uneven terrain, weather conditions, heavy loads, and/or poor housekeeping.  <b>1b. CONTACT:</b> Personal injury and/or property damage caused by being struck by Site traffic or equipment used in Site activities.	1a. Use 3 points-of-contact/ensure secure footing when entering and exiting vehicle. 1a. Inspect walking path for uneven terrain, steep hills, obstructions, and/or weather-related hazards (i.e., ice, snow, and puddles) prior to mobilizing equipment. Use established pathways. Walk on stable/secure ground. 1a. Do not climb over stored materials/equipment; walk around. Practice good housekeeping; organize and store equipment neatly in one area at its lowest potential energy. 1a. Wear boots with adequate treads. 1a. Delineate unsafe areas with 42" cones, caution tape and/or flagging.  1b. Observe and maintain the posted speed limits. 1b. When first arriving onsite, park vehicles in designated parking space and/or out of the way locations. Use parking brake on all vehicles and tire chocks on work trucks and trailers. 1b. Check in with Site Manager/Supervisor to ensure coordination with other Site activities and to discuss any special hazards. Ensure that short-service employees (SSE) are identified. 1b. Identify potential traffic sources. 1b. Wear PPE including high visibility clothing or reflective vest. 1b. Use a spotter while moving work vehicles; plan ahead to avoid backing whenever possible. 1b. Maintain a minimum 10' exclusion zone when vehicles are in motion. When backing up truck rig with an attached trailer use a second spotter if there is tight clearance simultaneously on multiple sides of the equipment or if turning angles limit driver-to-spotter visibility. 1b. Delineate work area with 42" cones, flags, caution tape, and/or other barriers. 1b. Position "Work Area" signs at Site entrances, if possible, or at either side of work area.			

<sup>1</sup> Each Job or Operation consists of a set of tasks / steps. Be sure to list all the steps needed to perform job.

<sup>2</sup> A hazard is a potential danger. Break hazards into five types: Contact - victim is struck by or strikes an object; Caught - victim is caught on, caught in or caught between objects; Fall - victim falls to ground or lower level (includes slips and trips); Exertion - excessive strain or stress / ergonomics / lifting techniques; Exposure - inhalation/skin hazards; Energy Source - electricity, pressure, compression/tension.

<sup>3</sup> Using the first two columns as a guide, decide what actions or procedures are necessary to eliminate or minimize the risk. List the recommended safe operating procedures. Say exactly what needs to be done - such as "use two persons to lift." Avoid general statements such as, "be careful."

Assess <sup>1</sup> JOB STEPS	Analyze <sup>2</sup> POTENTIAL HAZARDS	Act <sup>3</sup> CRITICAL ACTIONS
	<p><b>1c. CAUGHT:</b> Personal injury from pinch points and being in line-of-fire of vehicle and/or equipment.</p> <p><b>1d. OVEREXERTION:</b> Muscle strains while lifting/carrying equipment.</p> <p><b>1e. EXPOSURE:</b> Personal injury from exposure to biological and environmental hazards.</p> <p><b>1f. EXPOSURE:</b> Weather related injuries.</p> <p><b>1g. EXPOSURE:</b> Personal injury from noise hazards.</p>	<p>1b. Position largest vehicle to protect against oncoming traffic.</p> <p>1b. Face traffic, maintain eye contact with oncoming vehicles, use a spotter, and establish a safe exit route.</p> <p>1b. Observe potential overhead and ground surface features that may interfere with moving equipment. Clear the path of physical hazards prior to initiating mobilization.</p> <p>1c. Make sure driver has engaged parking brake and placed wheel chocks in a position to prevent movement. Be sure that vehicle is parked in front/down gradient (positioned to best block oncoming traffic) of work area.</p> <p>1c. Wear leather gloves when handling any tools or equipment. Wear cut-resistant gloves (Kevlar or similar) when handling sharp objects/cutting tools/glass.</p> <p>1c. Keep body parts away from line-of-fire of equipment.</p> <p>1c. Always carry tools by the handles and/or designated carrier. Ensure sharp-edged tools are sheathed/secure.</p> <p>1c. Remove any loose jewelry. Avoid wearing loose clothing and/or ensure loose clothing is secure.</p> <p>1c. Secure all items on the equipment, tighten up any items or features that have potential to shift or break during mobilization.</p> <p>1d. Use body positioning and lifting techniques that avoid muscle strain; keep back straight, lift with legs, turn with whole body, keep load close to body, and never reach with a load.</p> <p>1d. Ensure that loads are balanced. Use assistance (mechanical or additional person) to carry equipment that is either unwieldy or over 50 lbs.</p> <p>1e. Inspect area to avoid contact with biological hazards (i.e. poisonous plants, stinging insects, ticks, etc.).</p> <p>1e. Wear long sleeved clothes treated with Permethrin, apply insect repellent containing DEET to exposed skin, and inspect clothes and skin for ticks during and after work.</p> <p>1e. Apply sunscreen (SPF 15+) if exposure to sun for 30 minutes or more is expected.</p> <p>1f. Watch for heat stress symptoms (muscle cramping, exhaustion, dizziness, nausea, rapid and shallow breathing). Take breaks in cool places and hydrate as needed.</p> <p>1f. Watch for cold stress symptoms (severe shivering, slowing of body movement, weakness, stumbling or inability to walk, collapse). Take breaks in warm areas as needed.</p> <p>1f. Wear clothing appropriate for weather and temperature conditions (e.g., rain jackets, snow pants, multiple layers).</p> <p>1f. If lightning is observed, wait 30 minutes in a sheltered location (car is acceptable) before resuming work.</p> <p>1g. Wear hearing protection if sound levels exceed 85 dBA (if you must raise your voice for normal conversation).</p>

<sup>1</sup> Each Job or Operation consists of a set of tasks / steps. Be sure to list all the steps needed to perform job.

<sup>2</sup> A hazard is a potential danger. Break hazards into five types: Contact - victim is struck by or strikes an object; Caught - victim is caught on, caught in or caught between objects; Fall - victim falls to ground or lower level (includes slips and trips); Exertion - excessive strain or stress / ergonomics / lifting techniques; Exposure - inhalation/skin hazards; Energy Source – electricity, pressure, compression/tension.

<sup>3</sup> Using the first two columns as a guide, decide what actions or procedures are necessary to eliminate or minimize the risk. List the recommended safe operating procedures. Say exactly what needs to be done - such as "use two persons to lift". Avoid general statements such as, "be careful".

JOB SAFETY ANALYSIS		Ctrl. No. GEN-020	DATE: 1/4/2018	<input type="checkbox"/> NEW <input checked="" type="checkbox"/> REVISED	PAGE 1 of 2
JSA TYPE CATEGORY: <b>GENERIC</b>	WORK TYPE: <b>Gauging &amp; Sampling</b>	WORK ACTIVITY (Description): <b>Soil Sampling</b>			
<b>DEVELOPMENT TEAM</b>	<b>POSITION / TITLE</b>	<b>REVIEWED BY:</b>		<b>POSITION / TITLE</b>	
MaryBeth Lyons	Project Scientist	Brian Hobbs		Senior Health & Safety Manager	
		Joe Gentile		Corporate Health and Safety Manager	
REQUIRED AND / OR RECOMMENDED PERSONAL PROTECTIVE EQUIPMENT					
<input type="checkbox"/> LIFE VEST <input checked="" type="checkbox"/> HARD HAT <input type="checkbox"/> LIFELINE / BODY HARNESS <input checked="" type="checkbox"/> SAFETY GLASSES <input checked="" type="checkbox"/> FLAME RESISTANT CLOTHING (as needed)	<input type="checkbox"/> GOGGLES <input type="checkbox"/> FACE SHIELD: <input checked="" type="checkbox"/> HEARING PROTECTION: (as needed) <input checked="" type="checkbox"/> SAFETY SHOES: Composite-toe or steel toe boots	<input type="checkbox"/> AIR PURIFYING RESPIRATOR <input type="checkbox"/> SUPPLIED RESPIRATOR <input checked="" type="checkbox"/> PPE CLOTHING: Fluorescent reflective vest or high visibility clothing	<input checked="" type="checkbox"/> GLOVES: Leather, Nitrile and cut resistant <input checked="" type="checkbox"/> OTHER: Insect repellent, sunscreen (as needed)		
REQUIRED AND / OR RECOMMENDED EQUIPMENT					
Recommended Equipment: 42" traffic cones, caution tape, trowel					
<b>COMMITMENT TO SAFETY</b> - All personnel onsite will actively participate in hazard recognition and mitigation throughout the day by verbalizing SPSAs.					
<b>EXCLUSION ZONE (EZ): A 10-foot exclusion zone will be maintained around moving equipment, if present.</b>					
Assess <b>1JOB STEPS</b>	Analyze <b>2POTENTIAL HAZARDS</b>	Act <b>3CRITICAL ACTIONS</b>			
1. Secure location	<p><b>1a. CONTACT:</b> Personnel and vehicular traffic may enter the work area.</p> <p><b>1b. FALL:</b> Tripping/falling due to uneven terrain or entry/exit from excavations.</p> <p><b>1c. EXPOSURE:</b> Exposure to sun and excessive heat, possibly causing sunburn, heat exhaustion or heat stroke.  Exposure to cold temperatures possibly causing cold stress.  Skin burn as a result of fire, if applicable.  Exposure to explosive vapors due to tank farm operations.  Exposure to airborne dust due to high wind speeds.  Biological hazards - ticks, bees/wasps, poison ivy, thorns, insects, etc.</p>	<p>1a. If in an area with foot or vehicle traffic, delineate the work area with 42" traffic cones and/or caution tape to prevent exposure to traffic and inform others of work activity.</p> <p>1a. Wear reflective vest and/or high visibility clothing.</p> <p>1a. Face the direction of any vehicular traffic. Position vehicle to protect worker from traffic.</p> <p>1a. Communicate work activity with adjacent work areas.</p> <p>1b. Inspect pathways and work area for uneven terrain, weather-related hazards (i.e., ice, puddles, snow, etc.), and obstructions.</p> <p>1b. Use established pathways and walk on stable, secure ground.</p> <p>1b. Stage equipment and tools in a convenient, stable, and orderly manner. Store equipment at lowest potential energy.</p> <p>1b. Roux employees should stay 5 feet from in-progress excavations and trenches. Should entry to an excavation be required (when stabilization is complete), ladders must be employed for steep embankments, excavations, pits, and trenches.</p> <p>1c. Wear sunscreen with an SPF 15 or greater whenever 30 minutes or more of exposure is expected.</p> <p>1c. Use a tent to shade the work area from direct sunlight particularly when warm temperatures are expected.</p> <p>1c. Be aware of the location of all Site personnel.</p> <p>1c. Watch for heat stress symptoms (muscle cramping, exhaustion, dizziness, rapid and shallow breathing).</p> <p>1c. Watch for cold stress symptoms (severe shivering, slowing of body movement, weakness, stumbling or inability to walk, collapse).</p> <p>1c. Take breaks for rest and water as necessary. Move to an area that is well shaded or a climate controlled area (i.e., car, site trailer, etc.).</p> <p>1c. No open flames/heat sources.</p> <p>1c. Flame retardant clothing must be worn when specified by Site policy.</p> <p>1c. Cell phones should be disabled when specified by Site policy.</p> <p>1c. Pre-treat field clothing with Permethrin prior to site visit to kill ticks and insects.</p> <p>1c. Wear long sleeved shirts and tuck in (or tape) pant legs into socks or boots to prevent ticks from reaching skin.</p> <p>1c. Spray insect repellent containing DEET on exposed skin when working in overgrown areas of the Site.</p> <p>1c. Inspect area to avoid contact with biological hazards.</p> <p>1c. Wear cut-resistant gloves when handling branches, shrubs, etc. that may lie within the walking path.</p> <p>1c. Wear spoggles if the average wind speeds are above 15 mph.</p> <p>1c. Personnel shall examine themselves and co-worker's outer clothing for ticks periodically when onsite.</p> <p>1c. If skin comes in contact with poison ivy, wash skin thoroughly with soap and water. If rash persists after washing, immediately notify your supervisor, the OM and OHSM for possible consultation with a physician at an approved Occupational Health Clinic.</p>			

<sup>1</sup> Each Job or Operation consists of a set of tasks / steps. Be sure to list all the steps needed to perform job.

<sup>2</sup> A hazard is a potential danger. Break hazards into five types: Contact - victim is struck by or strikes an object; Caught - victim is caught on, caught in or caught between objects; Fall - victim falls to ground or lower level (includes slips and trips); Exertion - excessive strain or stress / ergonomics / lifting techniques; Exposure - inhalation/skin hazards; Energy Source - electricity, pressure, compression/tension.

<sup>3</sup> Using the first two columns as a guide, decide what actions or procedures are necessary to eliminate or minimize the risk. List the recommended safe operating procedures. Say exactly what needs to be done - such as "use two persons to lift". Avoid general statements such as, "be careful".

Assess <sup>1</sup> JOB STEPS	Analyze <sup>2</sup> POTENTIAL HAZARDS	Act <sup>3</sup> CRITICAL ACTIONS
2. Collect Soil Sample	<p><b>2a. CONTACT:</b> Personal injury from pinch points, cuts, and abrasions from sampling equipment tools, and material within soil sample. Personal injury from contact with moving equipment while sampling. Personal injury from contact with glass sample jars.</p> <p><b>2b. EXPOSURE:</b> Exposure to contamination (impacted soil) and/or lab preservatives.</p> <p><b>2c. EXERTION:</b> Exertion due to repetitive motion and ergonomics.</p>	<p>2a. Wear cut-resistant (i.e., Kevlar) gloves under chemical-resistant (nitrile) disposable gloves when handling soil samples and sampling jars. 2a. Where possible, use trowel or equivalent tool to avoid contact with soil. 2a. If sampling from bucket of heavy equipment, ensure all equipment is off and operator utilizes the "show me your hands" policy. 2a. See 1a.</p> <p>2b. Wear chemical-resistant (nitrile) disposable gloves over cut resistant gloves to protect hands when handling samples; use containment material or plastic sheeting to protect surrounding areas. 2b. Wear safety glasses to protect eyes from dust or air-borne contaminants that may result from disturbing the soil. 2b. Where possible, remain upgradient from sample location if collecting soil sample from stockpile, drill rig, etc. to avoid breathing contaminant vapors, if they are present. 2b. When collecting soil sample from hand auger, put large zip lock bag over entire auger to prevent spillage of soil on to the ground. 2b. Open sample jars slowly and fill carefully to avoid contact with preservatives.</p> <p>2c. Utilize a table or raised surface for soil sampling if multiple soil samples are going to be taken to minimize repetitive bending motion.</p>
3. Decontaminate equipment	<p><b>3a. EXPOSURE/CONTACT:</b> Contamination (e.g., Separate Phase Hydrocarbons (SPH), contaminated vapors and/or soil).</p> <p><b>3b. EXPOSURE:</b> Chemicals in cleaning solution including ammonia.</p>	<p>3a. Wear chemical-resistant (nitrile) disposable gloves and safety glasses. 3a. Use an absorbent pad to clean spills. 3a. Properly dispose of used materials/PPE in provided drums in designated drum storage area. 3a. Remain upwind of sample and avoid breathing contaminant vapors, if they are present.</p> <p>3b. Wear chemical-resistant (nitrile) disposable gloves and safety glasses. 3b. Work on the upwind side of decontamination area. 3b. Use an absorbent pad to clean spills. 3b. Properly dispose of used materials/PPE in provided drums in designated drum storage area. Ensure that all drums are properly labeled and secured.</p>

<sup>1</sup> Each Job or Operation consists of a set of tasks / steps. Be sure to list all the steps needed to perform job.

<sup>2</sup> A hazard is a potential danger. Break hazards into five types: Contact - victim is struck by or strikes an object; Caught - victim is caught on, caught in or caught between objects; Fall - victim falls to ground or lower level (includes slips and trips); Exertion - excessive strain or stress / ergonomics / lifting techniques; Exposure - inhalation/skin hazards; Energy Source – electricity, pressure, compression/tension.

<sup>3</sup> Using the first two columns as a guide, decide what actions or procedures are necessary to eliminate or minimize the risk. List the recommended safe operating procedures. Say exactly what needs to be done - such as "use two persons to lift". Avoid general statements such as, "be careful".

<b>JOB SAFETY ANALYSIS</b> Ctrl. No. GEN-021		DATE: 1/4/2018	<input type="checkbox"/> NEW <input checked="" type="checkbox"/> REVISED	PAGE 1 of 2
JSA TYPE CATEGORY: <b>GENERIC</b>	WORK TYPE <b>Gauging and Sampling</b>	WORK ACTIVITY (Description) <b>Soil Vapor Sampling (Permanent Monitoring Points)</b>		
<b>DEVELOPMENT TEAM</b>	<b>POSITION / TITLE</b>	<b>REVIEWED BY:</b>	<b>POSITION / TITLE</b>	
Jeff Wills	Project Hydrogeologist	Brian Hobbs	Senior Health & Safety Manager	
Julie Moriarity	Project Scientist	Joe Gentile	Corporate Health and Safety Manager	
<b>REQUIRED AND / OR RECOMMENDED PERSONAL PROTECTIVE EQUIPMENT</b>				
<input type="checkbox"/> LIFE VEST <input checked="" type="checkbox"/> HARD HAT <input type="checkbox"/> LIFELINE / BODY HARNESS <input checked="" type="checkbox"/> SAFETY GLASSES	<input type="checkbox"/> GOGGLES <input type="checkbox"/> FACE SHIELD <input type="checkbox"/> HEARING PROTECTION <input checked="" type="checkbox"/> SAFETY SHOES: <u>Steel-toe boots</u>	<input type="checkbox"/> AIR PURIFYING RESPIRATOR <input type="checkbox"/> SUPPLIED RESPIRATOR <input checked="" type="checkbox"/> PPE CLOTHING: <u>Fluorescent reflective vest or high visibility clothing</u>	<input checked="" type="checkbox"/> GLOVES: <u>Cut-resistant &amp; Nitriles</u> <input checked="" type="checkbox"/> OTHER: <u>Bug Spray, Sun Screen, Knee Pads or kneeling pad</u>	
<b>REQUIRED AND / OR RECOMMENDED EQUIPMENT</b>				
9/16" Socket and Wrench, Non-Toxic Clay, Teflon-Lined Tubing, Masterflex Tubing, Air Pump with Low Flow, Dry Cal, Enclosure (Bucket with 2 holes), Helium Gas Canister, Summa Canisters and Flow Controllers, MultiRae Photo Ionization Detector (PID), Helium Detector, Tubing Cutter, 42-inch Safety Cones, Caution Tape or Retractable Cone Bars				
<b>COMMITMENT TO SAFETY-</b> All personnel onsite will actively participate in hazard recognition and mitigation throughout the day by verbalizing SPSAs.				
<b>EXCLUSION ZONE (EZ): A 5-foot exclusion zone will be maintained for non-essential personnel.</b>				

<sup>1</sup> Each Job or Operation consists of a set of tasks / steps. Be sure to list all the steps needed to perform job.

<sup>2</sup> A hazard is a potential danger. Break hazards into five types: Contact - victim is struck by or strikes an object; Caught - victim is caught on, caught in or caught between objects; Fall - victim falls to ground or lower level (includes slips and trips); Exertion - excessive strain or stress / ergonomics / lifting techniques; Exposure - inhalation/skin hazards; Energy Source - Electricity, pressure, tension/compression, torque.

<sup>3</sup> Using the first two columns as a guide, decide what actions or procedures are necessary to eliminate or minimize the risk. List the recommended safe operating procedures. Say exactly what needs to be done - such as "use two persons to lift". Avoid general statements such as, "be careful".



Assess <sup>1</sup> JOB STEPS	Analyze <sup>2</sup> POTENTIAL HAZARDS	Act <sup>3</sup> CRITICAL ACTIONS
<p>1. Define and secure work area.</p>	<p><b>1a. FALL:</b> Potential tripping hazards.</p> <p><b>1b. CONTACT:</b> Potential contact with moving vehicles or pedestrians.</p> <p><b>1c. EXERTION:</b> Muscle strain while lifting and carrying equipment.</p>	<p>1a. Ensure work area is secure and inform others (third party) of work activity.</p> <p>1a. Remove tripping hazards and inspect walking path for uneven terrain, weather-related hazards (i.e., ice, puddles, snow, etc.), and obstructions prior to mobilizing equipment.</p> <p>1b. If working alongside roads, look both ways before entering roadways, face traffic, and utilize work vehicle to protect employees.</p> <p>1b. Delineate work area (including vehicles) with traffic safety cones and caution tape or retractable cone bars.</p> <p>1b. Maintain a 5-foot exclusion zone.</p> <p>1b. Wear high visibility clothing or reflective safety vest.</p> <p>1c. When carrying equipment to/from work area, keep back straight, lift with legs, keep load close to body, never reach with a load. Ensure that loads are balanced. Use mechanical assistance/make multiple trips to carry equipment.</p>

<sup>1</sup> Each Job or Operation consists of a set of tasks / steps. Be sure to list all the steps needed to perform job.

<sup>2</sup> A hazard is a potential danger. Break hazards into five types: Contact - victim is struck by or strikes an object;

Caught - victim is caught on, caught in or caught between objects; Fall - victim falls to ground or lower level (includes slips and trips); Exertion - excessive strain or stress / ergonomics / lifting techniques; Exposure - inhalation/skin hazards; Energy Source – Electricity, pressure, tension/compression, torque.

<sup>3</sup> Using the first two columns as a guide, decide what actions or procedures are necessary to eliminate or minimize the risk. List the recommended safe operating procedures. Say exactly what needs to be done - such as "use two persons to lift". Avoid general statements such as, "be careful".

Assess 1JOB STEPS	Analyze 2POTENTIAL HAZARDS	Act 3CRITICAL ACTIONS
2. Remove well cover / close well cover.	<p><b>2a. CONTACT/CAUGHT:</b> Pinch points and scrapes associated with hand tools and well covers.</p> <p><b>2b. FALL:</b> Potential tripping hazards associated with installing bolts.</p> <p><b>2c. EXERTION:</b> Physical exertion to remove bolts that were over torqued or stripped.</p>	<p>2a. Keep hands away from pinch points.</p> <p>2a. Use hand tools with extensions to remove and replace well covers.</p> <p>2a. Wear cut-resistant gloves.</p> <p>2a. Use knee pads or kneeling pad when repetitive kneeling on rough ground is anticipated.</p> <p>2b. Place security bolts in secure location so not to create tripping hazards. Replace security bolts so that they fit flush with monitoring well covers.</p> <p>2c. Replace any security bolts that show signs of stripping. Do not over tighten.</p> <p>2c. Use body positioning and bending techniques that minimize muscle strain; keep back straight, bend at the knees.</p> <p>2c. See 2a.</p>
3. Screen vapor point with PID.	<p><b>3a. FALL:</b> Potential tripping hazards associated with equipment.</p> <p><b>3b. EXPOSURE:</b> Inhalation of soil vapor</p>	<p>3a. Place equipment in one area close to the sampling location.</p> <p>3b. Identify area where equipment is to be stored within the work area (away from main walking path).</p> <p>3a. Don't leave equipment on the ground. Return equipment to storage area between uses.</p> <p>3b. Replace brass caps immediately upon completion to avoid soil vapors migrating to the surface through sample tubing.</p> <p>3b. Stand upwind of sample point during screening activities.</p>
4. Remove / replace brass caps at the end of the sam`ple tubing.	<p><b>4a. CONTACT:</b> Pinch points associated with hand tools and brass caps.</p> <p><b>4b. EXPOSURE:</b> Potential pathway for vapors to migrate to land surface.</p>	<p>4a. Use wrench to remove and replace brass caps.</p> <p>4a. Wear cut-resistant gloves to protect against pinch points and scrapes.</p> <p>4b. See 3b.</p> <p>4b. Stand up wind of sample point location.</p>
5. Set up soil vapor sampling equipment and calibration of meters.	<p><b>5a. FALL:</b> Potential tripping hazards associated with equipment and tubing.5b.</p> <p><b>5b. CONTACT:</b> Pinch points associated with handling equipment.</p> <p><b>5c. EXPOSURE:</b> Inhalation of calibration gas and helium.</p>	<p>5a. See 3a.</p> <p>5a. Keep tubing slack to a minimum and locate the summa canister as close to the sampling location as possible.</p> <p>5a. Avoid stepping over equipment and tubing.</p> <p>5b. Do not place fingers/hands under sampling equipment.</p> <p>5b. Make multiple trips when unloading equipment in work area.</p> <p>5b. Wear cut-resistant gloves to protect against pinch points while handling sampling equipment.</p> <p>5c. Review SDS for each type of calibration gas used before calibrating.</p> <p>5c. Calibrate meters in a well-ventilated area and keep air flow regulator away from face.</p> <p>5c. Close valve on canisters after use to avoid inhalation of excess helium or calibration gas.</p> <p>5c. Stand up wind of bucket during helium tracer gas test.</p>

<sup>1</sup> Each Job or Operation consists of a set of tasks / steps. Be sure to list all the steps needed to perform job.

<sup>2</sup> A hazard is a potential danger. Break hazards into five types: Contact - victim is struck by or strikes an object; Caught - victim is caught on, caught in or caught between objects; Fall - victim falls to ground or lower level (includes slips and trips); Exertion - excessive strain or stress / ergonomics / lifting techniques; Exposure - inhalation/skin hazards; Energy Source – Electricity, pressure, tension/compression, torque.

<sup>3</sup> Using the first two columns as a guide, decide what actions or procedures are necessary to eliminate or minimize the risk. List the recommended safe operating procedures. Say exactly what needs to be done - such as "use two persons to lift". Avoid general statements such as, "be careful".

Assess <sup>1</sup> JOB STEPS	Analyze <sup>2</sup> POTENTIAL HAZARDS	Act <sup>3</sup> CRITICAL ACTIONS
6. Cleaning Work Area.	<p><b>6a. FALL:</b> Potential tripping hazards associated with equipment and tubing.</p> <p><b>6b. CONTACT:</b> Storing and transport of equipment in car.</p>	<p>6a. See 3a. 6a. See 3b.</p> <p>6b. Ensure that equipment is placed securely in the vehicle. Do not stack equipment on top of each other. Secure equipment so that it will not slide while being transported.</p> <p>6b. Wear cut-resistant gloves while handling/loading equipment.</p>

<sup>1</sup> Each Job or Operation consists of a set of tasks / steps. Be sure to list all the steps needed to perform job.

<sup>2</sup> A hazard is a potential danger. Break hazards into five types: Contact - victim is struck by or strikes an object;

Caught - victim is caught on, caught in or caught between objects; Fall - victim falls to ground or lower level (includes slips and trips); Exertion - excessive strain or stress / ergonomics / lifting techniques; Exposure - inhalation/skin hazards; Energy Source – Electricity, pressure, tension/compression, torque.

<sup>3</sup> Using the first two columns as a guide, decide what actions or procedures are necessary to eliminate or minimize the risk. List the recommended safe operating procedures. Say exactly what needs to be done - such as "use two persons to lift". Avoid general statements such as, "be careful".

**Site-Specific Health and Safety Plan**  
**12 Franklin Street, Brooklyn, New York 11222**

---

**APPENDIX B**

Safety Data Sheets (SDSs) for Chemicals Used

**Safety Data Sheet**

according to 1907/2006/EC (REACH), 1272/2008/EC (CLP), 29CFR1910/1200 and GHS Rev. 3

**Effective date:** 12.08.2015**Revision :** 12.10.2015**Trade Name:** Alconox**1 Identification of the substance/mixture and of the supplier****1.1 Product identifier****Trade Name:** Alconox**Synonyms:****Product number:** Alconox**1.2 Application of the substance / the mixture :** Cleaning material/Detergent**1.3 Details of the supplier of the Safety Data Sheet**

<b>Manufacturer</b>	<b>Supplier</b>
Alconox, Inc. 30 Glenn Street White Plains, NY 10603 1-914-948-4040	Not Applicable

**Emergency telephone number:****ChemTel Inc**

North America: 1-800-255-3924

International: 01-813-248-0585

**2 Hazards identification****2.1 Classification of the substance or mixture:**

In compliance with EC regulation No. 1272/2008, 29CFR1910/1200 and GHS Rev. 3 and amendments.

**Hazard-determining components of labeling:**

Tetrasodium Pyrophosphate  
Sodium tripolyphosphate  
Sodium Alkylbenzene Sulfonate

**2.2 Label elements:**

Skin irritation, category 2.  
Eye irritation, category 2A.

**Hazard pictograms:****Signal word:** Warning**Hazard statements:**

H315 Causes skin irritation.  
H319 Causes serious eye irritation.

**Precautionary statements:**

P264 Wash skin thoroughly after handling.  
P280 Wear protective gloves/protective clothing/eye protection/face protection.  
P302+P352 If on skin: Wash with soap and water.  
P305+P351+P338 If in eyes: Rinse cautiously with water for several minutes. Remove contact lenses if present and easy to do. Continue rinsing.  
P321 Specific treatment (see supplemental first aid instructions on this label).  
P332+P313 If skin irritation occurs: Get medical advice/attention.  
P362 Take off contaminated clothing and wash before reuse.  
P501 Dispose of contents and container as instructed in Section 13.

**Safety Data Sheet**

according to 1907/2006/EC (REACH), 1272/2008/EC (CLP), 29CFR1910/1200 and GHS Rev. 3

**Effective date:** 12.08.2015**Revision :** 12.10.2015**Trade Name:** Alconox**Additional information:** None.**Hazard description****Hazards Not Otherwise Classified (HNOC):** None**Information concerning particular hazards for humans and environment:**

The product has to be labelled due to the calculation procedure of the "General Classification guideline for preparations of the EU" in the latest valid version.

**Classification system:**

The classification is according to EC regulation No. 1272/2008, 29CFR1910/1200 and GHS Rev. 3 and amendments, and extended by company and literature data. The classification is in accordance with the latest editions of international substances lists, and is supplemented by information from technical literature and by information provided by the company.

**3 Composition/information on ingredients****3.1 Chemical characterization :** None**3.2 Description :** None**3.3 Hazardous components (percentages by weight)**

Identification	Chemical Name	Classification	Wt. %
<b>CAS number:</b> 7758-29-4	Sodium tripolyphosphate	Skin Irrit. 2 ; H315 Eye Irrit. 2; H319	12-28
<b>CAS number:</b> 68081-81-2	Sodium Alkylbenzene Sulfonate	Acute Tox. 4; H303 Skin Irrit. 2 ; H315 Eye Irrit. 2; H319	8-22
<b>CAS number:</b> 7722-88-5	Tetrasodium Pyrophosphate	Skin Irrit. 2 ; H315 Eye Irrit. 2; H319	2-16

**3.4 Additional Information :** None.**4 First aid measures****4.1 Description of first aid measures****General information:** None.**After inhalation:**

Maintain an unobstructed airway.

Loosen clothing as necessary and position individual in a comfortable position.

**After skin contact:**

Wash affected area with soap and water.

Seek medical attention if symptoms develop or persist.

**After eye contact:**

Rinse/flush exposed eye(s) gently using water for 15-20 minutes.

Remove contact lens(es) if able to do so during rinsing.

Seek medical attention if irritation persists or if concerned.

**After swallowing:**

Rinse mouth thoroughly.

Seek medical attention if irritation, discomfort, or vomiting persists.

## Safety Data Sheet

according to 1907/2006/EC (REACH), 1272/2008/EC (CLP), 29CFR1910/1200 and GHS Rev. 3

**Effective date:** 12.08.2015

**Revision :** 12.10.2015

<b>Trade Name:</b> Alconox
----------------------------

### 4.2 Most important symptoms and effects, both acute and delayed

None

### 4.3 Indication of any immediate medical attention and special treatment needed:

No additional information.

<b>5 Firefighting measures</b>
--------------------------------

#### 5.1 Extinguishing media

##### Suitable extinguishing agents:

Use appropriate fire suppression agents for adjacent combustible materials or sources of ignition.

**For safety reasons unsuitable extinguishing agents :** None

#### 5.2 Special hazards arising from the substance or mixture :

Thermal decomposition can lead to release of irritating gases and vapors.

#### 5.3 Advice for firefighters

##### Protective equipment:

Wear protective eye wear, gloves and clothing.  
Refer to Section 8.

#### 5.4 Additional information :

Avoid inhaling gases, fumes, dust, mist, vapor and aerosols.  
Avoid contact with skin, eyes and clothing.

<b>6 Accidental release measures</b>
--------------------------------------

#### 6.1 Personal precautions, protective equipment and emergency procedures :

Ensure adequate ventilation.  
Ensure air handling systems are operational.

#### 6.2 Environmental precautions :

Should not be released into the environment.  
Prevent from reaching drains, sewer or waterway.

#### 6.3 Methods and material for containment and cleaning up :

Wear protective eye wear, gloves and clothing.

#### 6.4 Reference to other sections : None

<b>7 Handling and storage</b>
-------------------------------

#### 7.1 Precautions for safe handling :

Avoid breathing mist or vapor.  
Do not eat, drink, smoke or use personal products when handling chemical substances.

#### 7.2 Conditions for safe storage, including any incompatibilities :

Store in a cool, well-ventilated area.

#### 7.3 Specific end use(s):

No additional information.

## Safety Data Sheet

according to 1907/2006/EC (REACH), 1272/2008/EC (CLP), 29CFR1910/1200 and GHS Rev. 3

**Effective date:** 12.08.2015

**Revision :** 12.10.2015

**Trade Name:** Alconox

### 8 Exposure controls/personal protection



#### 8.1 Control parameters :

7722-88-5, Tetrasodium Pyrophosphate, OSHA TWA 5 mg/m3.

#### 8.2 Exposure controls

##### Appropriate engineering controls:

Emergency eye wash fountains and safety showers should be available in the immediate vicinity of use or handling.

##### Respiratory protection:

Not needed under normal conditions.

##### Protection of skin:

Select glove material impermeable and resistant to the substance.

##### Eye protection:

Safety goggles or glasses, or appropriate eye protection.

##### General hygienic measures:

Wash hands before breaks and at the end of work.

Avoid contact with skin, eyes and clothing.

### 9 Physical and chemical properties

<b>Appearance (physical state, color):</b>	White and cream colored flakes - powder	<b>Explosion limit lower: Explosion limit upper:</b>	Not determined or not available. Not determined or not available.
<b>Odor:</b>	Not determined or not available.	<b>Vapor pressure at 20°C:</b>	Not determined or not available.
<b>Odor threshold:</b>	Not determined or not available.	<b>Vapor density:</b>	Not determined or not available.
<b>pH-value:</b>	9.5 (aqueous solution)	<b>Relative density:</b>	Not determined or not available.
<b>Melting/Freezing point:</b>	Not determined or not available.	<b>Solubilities:</b>	Not determined or not available.
<b>Boiling point/Boiling range:</b>	Not determined or not available.	<b>Partition coefficient (n-octanol/water):</b>	Not determined or not available.
<b>Flash point (closed cup):</b>	Not determined or not available.	<b>Auto/Self-ignition temperature:</b>	Not determined or not available.
<b>Evaporation rate:</b>	Not determined or not available.	<b>Decomposition temperature:</b>	Not determined or not available.



**Safety Data Sheet**

according to 1907/2006/EC (REACH), 1272/2008/EC (CLP), 29CFR1910/1200 and GHS Rev. 3

**Effective date:** 12.08.2015**Revision :** 12.10.2015**Trade Name:** Alconox

<b>Flammability (solid, gaseous):</b>	Not determined or not available.	<b>Viscosity:</b>	a. Kinematic: Not determined or not available. b. Dynamic: Not determined or not available.
<b>Density at 20°C:</b>	Not determined or not available.		

**10 Stability and reactivity****10.1 Reactivity :** None**10.2 Chemical stability :** None**10.3 Possibility hazardous reactions :** None**10.4 Conditions to avoid :** None**10.5 Incompatible materials :** None**10.6 Hazardous decomposition products :** None**11 Toxicological information****11.1 Information on toxicological effects :****Acute Toxicity:****Oral:**

: LD50 &gt; 5000 mg/kg oral rat - Product .

**Chronic Toxicity:** No additional information.**Skin corrosion/irritation:**

Sodium Alkylbenzene Sulfonate: Causes skin irritation. .

**Serious eye damage/irritation:**

Sodium Alkylbenzene Sulfonate: Causes serious eye irritation .

Tetrasodium Pyrophosphate: Rabbit - Risk of serious damage to eyes .

**Respiratory or skin sensitization:** No additional information.**Carcinogenicity:** No additional information.**IARC (International Agency for Research on Cancer):** None of the ingredients are listed.**NTP (National Toxicology Program):** None of the ingredients are listed.**Germ cell mutagenicity:** No additional information.**Reproductive toxicity:** No additional information.**STOT-single and repeated exposure:** No additional information.**Additional toxicological information:** No additional information.**12 Ecological information**

**Safety Data Sheet**

according to 1907/2006/EC (REACH), 1272/2008/EC (CLP), 29CFR1910/1200 and GHS Rev. 3

**Effective date:** 12.08.2015**Revision :** 12.10.2015**Trade Name:** Alconox**12.1 Toxicity:**

Sodium Alkylbenzene Sulfonate: Fish, LC50 1.67 mg/l, 96 hours.

Sodium Alkylbenzene Sulfonate: Aquatic invertebrates, EC50 Daphnia 2.4 mg/l, 48 hours.

Sodium Alkylbenzene Sulfonate: Aquatic Plants, EC50 Algae 29 mg/l, 96 hours.

Tetrasodium Pyrophosphate: Fish, LC50 - other fish - 1,380 mg/l - 96 h.

Tetrasodium Pyrophosphate: Aquatic invertebrates, EC50 - Daphnia magna (Water flea) - 391 mg/l - 48 h.

**12.2 Persistence and degradability:** No additional information.**12.3 Bioaccumulative potential:** No additional information.**12.4 Mobility in soil:** No additional information.**General notes:** No additional information.**12.5 Results of PBT and vPvB assessment:****PBT:** No additional information.**vPvB:** No additional information.**12.6 Other adverse effects:** No additional information.**13 Disposal considerations****13.1 Waste treatment methods (consult local, regional and national authorities for proper disposal)****Relevant Information:**

It is the responsibility of the waste generator to properly characterize all waste materials according to applicable regulatory entities. (US 40CFR262.11).

**14 Transport information**

<b>14.1 UN Number:</b> ADR, ADN, DOT, IMDG, IATA	None														
<b>14.2 UN Proper shipping name:</b> ADR, ADN, DOT, IMDG, IATA	None														
<b>14.3 Transport hazard classes:</b> ADR, ADN, DOT, IMDG, IATA	<table> <tr> <td><b>Class:</b></td> <td>None</td> </tr> <tr> <td><b>Label:</b></td> <td>None</td> </tr> <tr> <td><b>LTD. QTY:</b></td> <td>None</td> </tr> </table>	<b>Class:</b>	None	<b>Label:</b>	None	<b>LTD. QTY:</b>	None								
<b>Class:</b>	None														
<b>Label:</b>	None														
<b>LTD. QTY:</b>	None														
<table> <tr> <td><b>US DOT Limited Quantity Exception:</b></td> <td>None</td> </tr> <tr> <td><b>Bulk:</b></td> <td><b>Non Bulk:</b></td> </tr> <tr> <td><b>RQ (if applicable):</b> None</td> <td><b>RQ (if applicable):</b> None</td> </tr> <tr> <td><b>Proper shipping Name:</b> None</td> <td><b>Proper shipping Name:</b> None</td> </tr> <tr> <td><b>Hazard Class:</b> None</td> <td><b>Hazard Class:</b> None</td> </tr> <tr> <td><b>Packing Group:</b> None</td> <td><b>Packing Group:</b> None</td> </tr> <tr> <td><b>Marine Pollutant (if applicable):</b> No additional information.</td> <td><b>Marine Pollutant (if applicable):</b> No additional information.</td> </tr> </table>		<b>US DOT Limited Quantity Exception:</b>	None	<b>Bulk:</b>	<b>Non Bulk:</b>	<b>RQ (if applicable):</b> None	<b>RQ (if applicable):</b> None	<b>Proper shipping Name:</b> None	<b>Proper shipping Name:</b> None	<b>Hazard Class:</b> None	<b>Hazard Class:</b> None	<b>Packing Group:</b> None	<b>Packing Group:</b> None	<b>Marine Pollutant (if applicable):</b> No additional information.	<b>Marine Pollutant (if applicable):</b> No additional information.
<b>US DOT Limited Quantity Exception:</b>	None														
<b>Bulk:</b>	<b>Non Bulk:</b>														
<b>RQ (if applicable):</b> None	<b>RQ (if applicable):</b> None														
<b>Proper shipping Name:</b> None	<b>Proper shipping Name:</b> None														
<b>Hazard Class:</b> None	<b>Hazard Class:</b> None														
<b>Packing Group:</b> None	<b>Packing Group:</b> None														
<b>Marine Pollutant (if applicable):</b> No additional information.	<b>Marine Pollutant (if applicable):</b> No additional information.														

**Safety Data Sheet**

according to 1907/2006/EC (REACH), 1272/2008/EC (CLP), 29CFR1910/1200 and GHS Rev. 3

Effective date: 12.08.2015

Revision : 12.10.2015

<b>Trade Name:</b> Alconox	
<b>Comments:</b> None	<b>Comments:</b> None
<b>14.4 Packing group:</b> ADR, ADN, DOT, IMDG, IATA	None
<b>14.5 Environmental hazards :</b>	None
<b>14.6 Special precautions for user:</b> <b>Danger code (Kemler):</b> <b>EMS number:</b> <b>Segregation groups:</b>	None None None None
<b>14.7 Transport in bulk according to Annex II of MARPOL73/78 and the IBC Code:</b> Not applicable.	
<b>14.8 Transport/Additional information:</b>  <b>Transport category:</b> <b>Tunnel restriction code:</b> <b>UN "Model Regulation":</b>	
	None None None

**15 Regulatory information****15.1 Safety, health and environmental regulations/legislation specific for the substance or mixture.****North American**

<b>SARA</b> <b>Section 313 (specific toxic chemical listings):</b> None of the ingredients are listed. <b>Section 302 (extremely hazardous substances):</b> None of the ingredients are listed.
<b>CERCLA (Comprehensive Environmental Response, Clean up and Liability Act) Reportable</b> <b>Spill Quantity:</b> None of the ingredients are listed.
<b>TSCA (Toxic Substances Control Act):</b> <b>Inventory:</b> All ingredients are listed. <b>Rules and Orders:</b> Not applicable.
<b>Proposition 65 (California):</b>  <b>Chemicals known to cause cancer:</b> None of the ingredients are listed. <b>Chemicals known to cause reproductive toxicity for females:</b> None of the ingredients are listed. <b>Chemicals known to cause reproductive toxicity for males:</b> None of the ingredients are listed. <b>Chemicals known to cause developmental toxicity:</b> None of the ingredients are listed.
<b>Canadian</b> <b>Canadian Domestic Substances List (DSL):</b> All ingredients are listed.

**EU****REACH Article 57 (SVHC):** None of the ingredients are listed.

**Safety Data Sheet**

according to 1907/2006/EC (REACH), 1272/2008/EC (CLP), 29CFR1910/1200 and GHS Rev. 3

**Effective date:** 12.08.2015**Revision :** 12.10.2015**Trade Name:** Alconox**Germany MAK:** Not classified.**Asia Pacific****Australia****Australian Inventory of Chemical Substances (AICS):** All ingredients are listed.**China****Inventory of Existing Chemical Substances in China (IECSC):** All ingredients are listed.**Japan****Inventory of Existing and New Chemical Substances (ENCS):** All ingredients are listed.**Korea****Existing Chemicals List (ECL):** All ingredients are listed.**New Zealand****New Zealand Inventory of Chemicals (NZOIC):** All ingredients are listed.**Philippines****Philippine Inventory of Chemicals and Chemical Substances (PICCS):** All ingredients are listed.**Taiwan****Taiwan Chemical Substance Inventory (TSCI):** All ingredients are listed.**16 Other information****Abbreviations and Acronyms:** None**Summary of Phrases****Hazard statements:**

H315 Causes skin irritation.

H319 Causes serious eye irritation.

**Precautionary statements:**

P264 Wash skin thoroughly after handling.

P280 Wear protective gloves/protective clothing/eye protection/face protection.

P302+P352 If on skin: Wash with soap and water.

P305+P351+P338 If in eyes: Rinse cautiously with water for several minutes. Remove contact lenses if present and easy to do. Continue rinsing.

P321 Specific treatment (see supplemental first aid instructions on this label).

P332+P313 If skin irritation occurs: Get medical advice/attention.

P362 Take off contaminated clothing and wash before reuse.

P501 Dispose of contents and container as instructed in Section 13.

**Manufacturer Statement:**

The information provided in this Safety Data Sheet is correct to the best of our knowledge, information and belief at the date of its publication. The information given is designed only as guidance for safe handling, use, processing, storage, transportation, disposal and release and is not to be considered a warranty or quality specification. The information relates only to the specific material designated and may not be valid for such material used in combination with any other materials or in any process, unless specified in the text.

**NFPA:** 1-0-0

**Safety Data Sheet**


according to 1907/2006/EC (REACH), 1272/2008/EC (CLP), 29CFR1910/1200 and GHS Rev. 3

**Effective date:** 12.08.2015

**Revision :** 12.10.2015

**Trade Name:** Alconox

**HMIS:** 1-0-0



Health	3
Fire	0
Reactivity	1
Personal Protection	

## Material Safety Data Sheet

### Hydrochloric acid MSDS

#### Section 1: Chemical Product and Company Identification

**Product Name:** Hydrochloric acid

**Catalog Codes:** SLH1462, SLH3154

**CAS#:** Mixture.

**RTECS:** MW4025000

**TSCA:** TSCA 8(b) inventory: Hydrochloric acid

**CI#:** Not applicable.

**Synonym:** Hydrochloric Acid; Muriatic Acid

**Chemical Name:** Not applicable.

**Chemical Formula:** Not applicable.

**Contact Information:**

**Sciencelab.com, Inc.**

14025 Smith Rd.

Houston, Texas 77396

US Sales: **1-800-901-7247**

International Sales: **1-281-441-4400**

Order Online: [ScienceLab.com](http://ScienceLab.com)

**CHEMTREC (24HR Emergency Telephone), call:**

1-800-424-9300

**International CHEMTREC, call:** 1-703-527-3887

**For non-emergency assistance, call:** 1-281-441-4400

#### Section 2: Composition and Information on Ingredients

**Composition:**

Name	CAS #	% by Weight
Hydrogen chloride	7647-01-0	20-38
Water	7732-18-5	62-80

**Toxicological Data on Ingredients:** Hydrogen chloride: GAS (LC50): Acute: 4701 ppm 0.5 hours [Rat].

#### Section 3: Hazards Identification

**Potential Acute Health Effects:**

Very hazardous in case of skin contact (corrosive, irritant, permeator), of eye contact (irritant, corrosive), of ingestion, . Slightly hazardous in case of inhalation (lung sensitizer). Non-corrosive for lungs. Liquid or spray mist may produce tissue damage particularly on mucous membranes of eyes, mouth and respiratory tract. Skin contact may produce burns. Inhalation of the spray mist may produce severe irritation of respiratory tract, characterized by coughing, choking, or shortness of breath. Severe over-exposure can result in death. Inflammation of the eye is characterized by redness, watering, and itching. Skin inflammation is characterized by itching, scaling, reddening, or, occasionally, blistering.

**Potential Chronic Health Effects:**

Slightly hazardous in case of skin contact (sensitizer). **CARCINOGENIC EFFECTS:** Classified 3 (Not classifiable for human.) by IARC [Hydrochloric acid]. **MUTAGENIC EFFECTS:** Not available. **TERATOGENIC EFFECTS:** Not available. **DEVELOPMENTAL TOXICITY:** Not available. The substance may be toxic to kidneys, liver, mucous membranes, upper respiratory tract, skin, eyes, Circulatory System, teeth. Repeated or prolonged exposure to the substance can produce target

organs damage. Repeated or prolonged contact with spray mist may produce chronic eye irritation and severe skin irritation. Repeated or prolonged exposure to spray mist may produce respiratory tract irritation leading to frequent attacks of bronchial infection. Repeated exposure to a highly toxic material may produce general deterioration of health by an accumulation in one or many human organs.

#### Section 4: First Aid Measures

**Eye Contact:**

Check for and remove any contact lenses. In case of contact, immediately flush eyes with plenty of water for at least 15 minutes. Cold water may be used. Get medical attention immediately.

**Skin Contact:**

In case of contact, immediately flush skin with plenty of water for at least 15 minutes while removing contaminated clothing and shoes. Cover the irritated skin with an emollient. Cold water may be used. Wash clothing before reuse. Thoroughly clean shoes before reuse. Get medical attention immediately.

**Serious Skin Contact:**

Wash with a disinfectant soap and cover the contaminated skin with an anti-bacterial cream. Seek immediate medical attention.

**Inhalation:**

If inhaled, remove to fresh air. If not breathing, give artificial respiration. If breathing is difficult, give oxygen. Get medical attention immediately.

**Serious Inhalation:**

Evacuate the victim to a safe area as soon as possible. Loosen tight clothing such as a collar, tie, belt or waistband. If breathing is difficult, administer oxygen. If the victim is not breathing, perform mouth-to-mouth resuscitation. **WARNING:** It may be hazardous to the person providing aid to give mouth-to-mouth resuscitation when the inhaled material is toxic, infectious or corrosive. Seek immediate medical attention.

**Ingestion:**

If swallowed, do not induce vomiting unless directed to do so by medical personnel. Never give anything by mouth to an unconscious person. Loosen tight clothing such as a collar, tie, belt or waistband. Get medical attention immediately.

**Serious Ingestion:** Not available.

#### Section 5: Fire and Explosion Data

**Flammability of the Product:** Non-flammable.

**Auto-Ignition Temperature:** Not applicable.

**Flash Points:** Not applicable.

**Flammable Limits:** Not applicable.

**Products of Combustion:** Not available.

**Fire Hazards in Presence of Various Substances:** of metals

**Explosion Hazards in Presence of Various Substances:** Non-explosive in presence of open flames and sparks, of shocks.

**Fire Fighting Media and Instructions:** Not applicable.

**Special Remarks on Fire Hazards:**

Non combustible. Calcium carbide reacts with hydrogen chloride gas with incandescence. Uranium phosphide reacts with hydrochloric acid to release spontaneously flammable phosphine. Rubidium acetylene carbides burns with slightly warm hydrochloric acid. Lithium silicide in contact with hydrogen chloride becomes incandescent. When dilute hydrochloric acid is used, gas spontaneously flammable in air is evolved. Magnesium boride treated with concentrated hydrochloric acid produces spontaneously flammable gas. Cesium acetylene carbide burns hydrogen chloride gas. Cesium carbide ignites in contact with hydrochloric acid unless acid is dilute. Reacts with most metals to produce flammable Hydrogen gas.

**Special Remarks on Explosion Hazards:**

Hydrogen chloride in contact with the following can cause an explosion, ignition on contact, or other violent/vigorous reaction: Acetic anhydride AgClO + CCl4 Alcohols + hydrogen cyanide, Aluminum Aluminum-titanium alloys (with HCl vapor), 2-Amino ethanol, Ammonium hydroxide, Calcium carbide Ca3P2 Chlorine + dinitroanilines (evolves gas), Chlorosulfonic acid Cesium carbide Cesium acetylene carbide, 1,1-Difluoroethylene Ethylene diamine Ethylene imine, Fluorine, HClO4 Hexalithium disilicide H2SO4 Metal acetylides or carbides, Magnesium boride, Mercuric sulfate, Oleum, Potassium permanganate, beta-Propiolactone Propylene oxide Rubidium carbide, Rubidium, acetylene carbide Sodium (with aqueous HCl), Sodium hydroxide Sodium tetraselenium, Sulfonic acid, Tetraselenium tetranitride, U3P4 , Vinyl acetate. Silver perchlorate with carbon tetrachloride in the presence of hydrochloric acid produces trichloromethyl perchlorate which detonates at 40 deg. C.

## Section 6: Accidental Release Measures

### Small Spill:

Dilute with water and mop up, or absorb with an inert dry material and place in an appropriate waste disposal container. If necessary: Neutralize the residue with a dilute solution of sodium carbonate.

### Large Spill:

Corrosive liquid. Poisonous liquid. Stop leak if without risk. Absorb with DRY earth, sand or other non-combustible material. Do not get water inside container. Do not touch spilled material. Use water spray curtain to divert vapor drift. Use water spray to reduce vapors. Prevent entry into sewers, basements or confined areas; dike if needed. Call for assistance on disposal. Neutralize the residue with a dilute solution of sodium carbonate. Be careful that the product is not present at a concentration level above TLV. Check TLV on the MSDS and with local authorities.

## Section 7: Handling and Storage

### Precautions:

Keep locked up.. Keep container dry. Do not ingest. Do not breathe gas/fumes/ vapor/spray. Never add water to this product. In case of insufficient ventilation, wear suitable respiratory equipment. If ingested, seek medical advice immediately and show the container or the label. Avoid contact with skin and eyes. Keep away from incompatibles such as oxidizing agents, organic materials, metals, alkalis, moisture. May corrode metallic surfaces. Store in a metallic or coated fiberboard drum using a strong polyethylene inner package.

**Storage:** Keep container tightly closed. Keep container in a cool, well-ventilated area.

## Section 8: Exposure Controls/Personal Protection

### Engineering Controls:

Provide exhaust ventilation or other engineering controls to keep the airborne concentrations of vapors below their respective threshold limit value. Ensure that eyewash stations and safety showers are proximal to the work-station location.

### Personal Protection:

Face shield. Full suit. Vapor respirator. Be sure to use an approved/certified respirator or equivalent. Gloves. Boots.

### Personal Protection in Case of a Large Spill:

Splash goggles. Full suit. Vapor respirator. Boots. Gloves. A self contained breathing apparatus should be used to avoid inhalation of the product. Suggested protective clothing might not be sufficient; consult a specialist BEFORE handling this product.

### Exposure Limits:

CEIL: 5 (ppm) from OSHA (PEL) [United States] CEIL: 7 (mg/m3) from OSHA (PEL) [United States] CEIL: 5 from NIOSH CEIL: 7 (mg/m3) from NIOSH TWA: 1 STEL: 5 (ppm) [United Kingdom (UK)] TWA: 2 STEL: 8 (mg/m3) [United Kingdom (UK)] Consult local authorities for acceptable exposure limits.

## Section 9: Physical and Chemical Properties

**Physical state and appearance:** Liquid.



**Odor:** Pungent. Irritating (Strong.)

**Taste:** Not available.

**Molecular Weight:** Not applicable.

**Color:** Colorless to light yellow.

**pH (1% soln/water):** Acidic.

**Boiling Point:**

108.58 C @ 760 mm Hg (for 20.22% HCl in water) 83 C @ 760 mm Hg (for 31% HCl in water) 50.5 C (for 37% HCl in water)

**Melting Point:**

-62.25°C (-80°F) (20.69% HCl in water) -46.2 C (31.24% HCl in water) -25.4 C (39.17% HCl in water)

**Critical Temperature:** Not available.

**Specific Gravity:**

1.1- 1.19 (Water = 1) 1.10 (20%and 22% HCl solutions) 1.12 (24% HCl solution) 1.15 (29.57% HCl solution) 1.16 (32% HCl solution) 1.19 (37% and 38%HCl solutions)

**Vapor Pressure:** 16 kPa (@ 20°C) average

**Vapor Density:** 1.267 (Air = 1)

**Volatility:** Not available.

**Odor Threshold:** 0.25 to 10 ppm

**Water/Oil Dist. Coeff.:** Not available.

**Ionicity (in Water):** Not available.

**Dispersion Properties:** See solubility in water, diethyl ether.

**Solubility:** Soluble in cold water, hot water, diethyl ether.

## Section 10: Stability and Reactivity Data

**Stability:** The product is stable.

**Instability Temperature:** Not available.

**Conditions of Instability:** Incompatible materials, water

**Incompatibility with various substances:**

Highly reactive with metals. Reactive with oxidizing agents, organic materials, alkalis, water.

**Corrosivity:**

Extremely corrosive in presence of aluminum, of copper, of stainless steel(304), of stainless steel(316). Non-corrosive in presence of glass.

**Special Remarks on Reactivity:**

Reacts with water especially when water is added to the product. Absorption of gaseous hydrogen chloride on mercuric sulfate becomes violent @ 125 deg. C. Sodium reacts very violently with gaseous hydrogen chloride. Calcium phosphide and hydrochloric acid undergo very energetic reaction. It reacts with oxidizers releasing chlorine gas. Incompatible with, alkali metals, carbides, borides, metal oxides, vinyl acetate, acetylides, sulphides, phosphides, cyanides, carbonates. Reacts with most metals to produce flammable Hydrogen gas. Reacts violently (moderate reaction with heat of evolution) with water especially when water is added to the product. Isolate hydrogen chloride from heat, direct sunlight, alkalis (reacts vigorously), organic materials, and oxidizers (especially nitric acid and chlorates), amines, metals, copper and alloys (e.g. brass), hydroxides, zinc (galvanized materials), lithium silicide (incandescence), sulfuric acid(increase in temperature and pressure) Hydrogen chloride gas is emitted when this product is in contact with sulfuric acid. Adsorption of Hydrochloric Acid onto silicon dioxide results in exothermic reaction. Hydrogen chloride causes aldehydes and epoxides to violently polymerize. Hydrogen chloride or Hydrochloric Acid in contact with the following can cause explosion or ignition on contact or

**Special Remarks on Corrosivity:**

Highly corrosive. Incompatible with copper and copper alloys. It attacks nearly all metals (mercury, gold, platinum, tantalum, silver, and certain alloys are exceptions). It is one of the most corrosive of the nonoxidizing acids in contact with copper alloys. No corrosivity data on zinc, steel. Severe Corrosive effect on brass and bronze

**Polymerization:** Will not occur.

## Section 11: Toxicological Information

**Routes of Entry:** Absorbed through skin. Dermal contact. Eye contact. Inhalation.

**Toxicity to Animals:**

Acute oral toxicity (LD50): 900 mg/kg [Rabbit]. Acute toxicity of the vapor (LC50): 1108 ppm, 1 hours [Mouse]. Acute toxicity of the vapor (LC50): 3124 ppm, 1 hours [Rat].

**Chronic Effects on Humans:**

CARCINOGENIC EFFECTS: Classified 3 (Not classifiable for human.) by IARC [Hydrochloric acid]. May cause damage to the following organs: kidneys, liver, mucous membranes, upper respiratory tract, skin, eyes, Circulatory System, teeth.

**Other Toxic Effects on Humans:**

Very hazardous in case of skin contact (corrosive, irritant, permeator), of ingestion, . Hazardous in case of eye contact (corrosive), of inhalation (lung corrosive).

**Special Remarks on Toxicity to Animals:**

Lowest Published Lethal Doses (LDL/LCL) LDL [Man] -Route: Oral; 2857 ug/kg LCL [Human] - Route: Inhalation; Dose: 1300 ppm/30M LCL [Rabbit] - Route: Inhalation; Dose: 4413 ppm/30M

**Special Remarks on Chronic Effects on Humans:**

May cause adverse reproductive effects (fetotoxicity). May affect genetic material.

**Special Remarks on other Toxic Effects on Humans:**

Acute Potential Health Effects: Skin: Corrosive. Causes severe skin irritation and burns. Eyes: Corrosive. Causes severe eye irritation/conjunctivitis, burns, corneal necrosis. Inhalation: May be fatal if inhaled. Material is extremely destructive to tissue of the mucous membranes and upper respiratory tract. Inhalation of hydrochloric acid fumes produces nose, throat, and laryngeal burning, and irritation, pain and inflammation, coughing, sneezing, choking sensation, hoarseness, laryngeal spasms, upper respiratory tract edema, chest pains, as well as headache, and palpitations. Inhalation of high concentrations can result in corrosive burns, necrosis of bronchial epithelium, constriction of the larynx and bronchi, nasospetal perforation, glottal closure, occur, particularly if exposure is prolonged. May affect the liver. Ingestion: May be fatal if swallowed. Causes irritation and burning, ulceration, or perforation of the gastrointestinal tract and resultant peritonitis, gastric hemorrhage and infection. Can also cause nausea, vomiting (with "coffee ground" emesis), diarrhea, thirst, difficulty swallowing, salivation, chills, fever, uneasiness, shock, strictures and stenosis (esophageal, gastric, pyloric). May affect behavior (excitement), the cardiovascular system (weak rapid pulse, tachycardia), respiration (shallow respiration), and urinary system (kidneys- renal failure, nephritis). Acute exposure via inhalation or ingestion can also cause erosion of tooth enamel. Chronic Potential Health Effects: dyspnea, bronchitis. Chemical pneumonitis and pulmonary edema can also

## Section 12: Ecological Information

**Ecotoxicity:** Not available.

**BOD5 and COD:** Not available.

**Products of Biodegradation:**

Possibly hazardous short term degradation products are not likely. However, long term degradation products may arise.

**Toxicity of the Products of Biodegradation:** The products of degradation are less toxic than the product itself.

**Special Remarks on the Products of Biodegradation:** Not available.

## Section 13: Disposal Considerations

**Waste Disposal:**

Waste must be disposed of in accordance with federal, state and local environmental control regulations.

## Section 14: Transport Information

**DOT Classification:** Class 8: Corrosive material

**Identification:** : Hydrochloric acid, solution UNNA: 1789 PG: II

**Special Provisions for Transport:** Not available.

## Section 15: Other Regulatory Information

### Federal and State Regulations:

Connecticut hazardous material survey.: Hydrochloric acid Illinois toxic substances disclosure to employee act: Hydrochloric acid Illinois chemical safety act: Hydrochloric acid New York release reporting list: Hydrochloric acid Rhode Island RTK hazardous substances: Hydrochloric acid Pennsylvania RTK: Hydrochloric acid Minnesota: Hydrochloric acid Massachusetts RTK: Hydrochloric acid Massachusetts spill list: Hydrochloric acid New Jersey: Hydrochloric acid New Jersey spill list: Hydrochloric acid Louisiana RTK reporting list: Hydrochloric acid Louisiana spill reporting: Hydrochloric acid California Director's List of Hazardous Substances: Hydrochloric acid TSCA 8(b) inventory: Hydrochloric acid TSCA 4(a) proposed test rules: Hydrochloric acid SARA 302/304/311/312 extremely hazardous substances: Hydrochloric acid SARA 313 toxic chemical notification and release reporting: Hydrochloric acid CERCLA: Hazardous substances.: Hydrochloric acid: 5000 lbs. (2268 kg)

### Other Regulations:

OSHA: Hazardous by definition of Hazard Communication Standard (29 CFR 1910.1200). EINECS: This product is on the European Inventory of Existing Commercial Chemical Substances.

### Other Classifications:

#### WHMIS (Canada):

CLASS D-2A: Material causing other toxic effects (VERY TOXIC). CLASS E: Corrosive liquid.

#### DSCL (EEC):

R34- Causes burns. R37- Irritating to respiratory system. S26- In case of contact with eyes, rinse immediately with plenty of water and seek medical advice. S45- In case of accident or if you feel unwell, seek medical advice immediately (show the label where possible).

#### HMIS (U.S.A.):

**Health Hazard:** 3

**Fire Hazard:** 0

**Reactivity:** 1

**Personal Protection:**

#### National Fire Protection Association (U.S.A.):

**Health:** 3

**Flammability:** 0

**Reactivity:** 1

**Specific hazard:**

#### Protective Equipment:

Gloves. Full suit. Vapor respirator. Be sure to use an approved/certified respirator or equivalent. Wear appropriate respirator when ventilation is inadequate. Face shield.

## Section 16: Other Information

**References:**

-Hawley, G.G.. The Condensed Chemical Dictionary, 11e ed., New York N.Y., Van Nostrand Reinold, 1987. -SAX, N.I. Dangerous Properties of Industrial Materials. Toronto, Van Nostrand Reinold, 6e ed. 1984. -The Sigma-Aldrich Library of Chemical Safety Data, Edition II. -Guide de la loi et du règlement sur le transport des marchandises dangereuses au Canada. Centre de conformité international Ltée. 1986.

**Other Special Considerations:** Not available.

**Created:** 10/09/2005 05:45 PM


**Last Updated:** 05/21/2013 12:00 PM

*The information above is believed to be accurate and represents the best information currently available to us. However, we make no warranty of merchantability or any other warranty, express or implied, with respect to such information, and we assume no liability resulting from its use. Users should make their own investigations to determine the suitability of the information for their particular purposes. In no event shall ScienceLab.com be liable for any claims, losses, or damages of any third party or for lost profits or any special, indirect, incidental, consequential or exemplary damages, howsoever arising, even if ScienceLab.com has been advised of the possibility of such damages.*



# MATERIAL SAFETY DATA SHEET

Prepared to U.S. OSHA, CMA, ANSI and Canadian WHMIS Standards



## PART I *What is the material and what do I need to know in an emergency?*

### 1. PRODUCT IDENTIFICATION

CHEMICAL NAME; CLASS: **ISOBUTYLENE - C<sub>4</sub>H<sub>8</sub>**  
 Document Number: Isobutylene

PRODUCT USE: For general analytical/synthetic chemical uses.

SUPPLIER/MANUFACTURER'S NAME: MESA Specialty Gases & Equipment  
ADDRESS: 3619 Pendleton Avenue, Suite C  
 Santa Ana, CA 92704

BUSINESS PHONE: 1-714-434-7102  
EMERGENCY PHONE: INFOTRAC: 1-800-535-5053

DATE OF PREPARATION: May 10, 1999

### 2. COMPOSITION and INFORMATION ON INGREDIENTS

CHEMICAL NAME	CAS #	mole %	EXPOSURE LIMITS IN AIR					
			ACGIH		OSHA		IDLH ppm	OTHER
			TLV ppm	STEL ppm	PEL ppm	STEL ppm		
Isobutylene	115-11-7	> 99.0%	There are no specific exposure limits for Isobutylene. Isobutylene is a simple asphyxiant (SA). Oxygen levels should be maintained above 19.5%.					
Maximum Impurities		< 1.0%	None of the trace impurities in this mixture contribute significantly to the hazards associated with the product. All hazard information pertinent to this product has been provided in this Material Safety Data Sheet, per the requirements of the OSHA Hazard Communication Standard (29 CFR 1910.1200) and State equivalent standards.					

NE = Not Established

C = Ceiling Limit

See Section 16 for Definitions of Terms Used

NOTE: All WHMIS required information is included. It is located in appropriate sections based on the ANSI Z400.1-1993 format.

### 3. HAZARD IDENTIFICATION

**EMERGENCY OVERVIEW:** Isobutylene is a colorless, liquefied, flammable gas with an unpleasant odor similar to burning coal. The liquefied gas rapidly turns into a gas at standard atmospheric temperatures and pressures. Isobutylene is an asphyxiant and presents a significant health hazard by displacing the oxygen in the atmosphere. Rapid evaporation of liquid from the cylinder may cause frostbite. Both the liquid and gas pose a serious fire hazard when accidentally released. The gas is heavier than air and may travel to a source of ignition and flash back to a leak or open container. Flame or high temperature impinging on a localized area of a cylinder of Isobutylene can cause the cylinder to rupture without activating the cylinder's relief devices. Provide adequate fire protection during emergency response situations.

**SYMPTOMS OF OVEREXPOSURE BY ROUTE OF EXPOSURE:**

The most significant route of overexposure for this gas is by inhalation. The following paragraphs describe symptoms of exposure by route of exposure.

**INHALATION:** High concentrations of this gas can cause an oxygen-deficient environment. Individuals breathing such an atmosphere may experience symptoms which include headaches, ringing in ears, dizziness, drowsiness, unconsciousness, nausea, vomiting, and depression of all the senses. Under some circumstances of overexposure, death may occur. Isobutylene also has some degree of anesthetic action and can be mildly irritating to the mucous membranes. The effects associated with various levels of oxygen are as follows:

**CONCENTRATION**

12-16% Oxygen:

10-14% Oxygen:

6-10% Oxygen:

Below 6%:

**SYMPTOMS OF EXPOSURE**

Breathing and pulse rate increased, muscular coordination slightly disturbed.

Emotional upset, abnormal fatigue, disturbed respiration.

Nausea and vomiting, collapse or loss of consciousness.

Convulsive movements, possible respiratory collapse, and death.



**OTHER POTENTIAL HEALTH EFFECTS:** Contact with liquid or rapidly expanding gases (which are released under high pressure) may cause frostbite. Symptoms of frostbite include change in skin color to white or grayish-yellow. The pain after such contact can quickly subside.

**HEALTH EFFECTS OR RISKS FROM EXPOSURE:** An Explanation in **Lay Terms**. Overexposure to Isobutylene may cause the following health effects:

**ACUTE:** The most significant hazard associated with this gas is inhalation of oxygen-deficient atmospheres. Symptoms of oxygen deficiency include respiratory difficulty, headache, dizziness, and nausea. At high concentrations, unconsciousness or death may occur. Contact with liquefied gas or rapidly expanding gases may cause frostbite.

**CHRONIC:** There are currently no known adverse health effects associated with chronic exposure to Isobutylene.

**TARGET ORGANS:** Respiratory system.

HAZARDOUS MATERIAL INFORMATION SYSTEM			
HEALTH		(BLUE)	1
FLAMMABILITY		(RED)	4
REACTIVITY		(YELLOW)	0
PROTECTIVE EQUIPMENT			B
EYES	RESPIRATORY	HANDS	BODY
	See Section 8		See Section 8
For routine industrial applications			

**See Section 16 for Definition of Ratings**

## PART II *What should I do if a hazardous situation occurs?*

### 4. FIRST-AID MEASURES

**RESCUERS SHOULD NOT ATTEMPT TO RETRIEVE VICTIMS OF EXPOSURE TO ISOBUTYLENE WITHOUT ADEQUATE PERSONAL PROTECTIVE EQUIPMENT.** At a minimum, Self-Contained Breathing Apparatus and Fire-Retardant Personal Protective equipment should be worn. Adequate fire protection must be provided during rescue situations.

#### 4. FIRST-AID MEASURES (Continued)

Remove victim(s) to fresh air as quickly as possible. Trained personnel should administer supplemental oxygen and/or cardio-pulmonary resuscitation, if necessary. Only trained personnel should administer supplemental oxygen.

In case of frostbite, place the frostbitten part in warm water. DO NOT USE HOT WATER. If warm water is not available, or is impractical to use, wrap the affected parts gently in blankets. Alternatively, if the fingers or hands are frostbitten, place the affected area in the armpit. Encourage victim to gently exercise the affected part while being warmed. Seek immediate medical attention.

Victim(s) must be taken for medical attention. Rescuers should be taken for medical attention, if necessary. Take copy of label and MSDS to physician or other health professional with victim(s).

#### 5. FIRE-FIGHTING MEASURES

FLASH POINT (Closed Cup): -10°C (< 14°F)

AUTOIGNITION TEMPERATURE: 465°C (869°F)

FLAMMABLE LIMITS (in air by volume, %):

Lower (LEL): 1.8%

Upper (UEL): 9.6%

FIRE EXTINGUISHING MATERIALS: Extinguish Isobutylene fires by shutting off the source of the gas. Use water spray or a foam agent to cool fire-exposed containers, structures, and equipment.


UNUSUAL FIRE AND EXPLOSION HAZARDS: When involved in a fire, this material may ignite and produce toxic gases, including carbon monoxide and carbon dioxide.

**DANGER!** Fires impinging (direct flame) on the outside surface of unprotected pressure storage vessels of Isobutylene can be very dangerous. Direct flame exposure on the cylinder wall can cause an explosion either by BLEVE (Boiling Liquid Expanding Vapor Explosion), or by exothermic decomposition. This is a catastrophic failure of the vessel releasing the contents into a massive fireball and explosion. The resulting fire and explosion can result in severe equipment damage and personnel injury or death over a large area around the vessel. For massive fires in large areas, use unmanned hose holder or monitor nozzles; if this is not possible, withdraw from area and allow fire to burn.

Explosion Sensitivity to Mechanical Impact: Not sensitive.

Explosion Sensitivity to Static Discharge: Static discharge may cause Isobutylene to ignite explosively if released.

SPECIAL FIRE-FIGHTING PROCEDURES: Structural firefighters must wear Self-Contained Breathing Apparatus and full protective equipment. The best fire-fighting technique may be simply to let the burning gas escape from the pressurized cylinder, tank car, or pipeline. Stop the leak before extinguishing fire. If the fire is extinguished before the leak is sealed, the leaking gas could explosively re-ignite without warning and cause extensive damage, injury, or fatality. In this case, increase ventilation (in enclosed areas) to prevent flammable or explosive mixture formation. Structural firefighters must wear Self-Contained Breathing Apparatus and full protective equipment. Because of the potential for a BLEVE, evacuation of non-emergency personnel is essential. If water is not available for cooling or protection of vessel exposures, evacuate the area. Refer to the North American Emergency Response Guidebook for additional information. Other information for pre-planning can be found in the American Petroleum Institute Publications 2510 and 2510A.



See Section 16 for Definition of Ratings

#### 6. ACCIDENTAL RELEASE MEASURES

SPILL AND LEAK RESPONSE: Uncontrolled releases should be responded to by trained personnel using pre-planned procedures. Proper protective equipment should be used. In case of a release, clear the affected area, protect people, and respond with trained personnel. Adequate fire protection must be provided. Minimum Personal Protective Equipment should be **Level B: fire-retardant protective clothing, gloves resistant to tears, and Self-Contained Breathing Apparatus.**

Use only non-sparking tools and equipment. Locate and seal the source of the leaking gas. Protect personnel attempting the shut off with water spray. Allow the gas to dissipate. Monitor the surrounding area for combustible gas levels and oxygen. Combustible gas concentration must be below 10% of the LEL (LEL = 1.8%) prior to entry. The atmosphere must have at least 19.5 percent oxygen before personnel can be allowed in the area without Self-Contained Breathing Apparatus. Attempt to close the main source valve prior to entering the area. If this does not stop the release (or if it is not possible to reach the valve), allow the gas to release in place or remove it to a safe area and allow the gas to be released there.

**THIS IS AN EXTREMELY FLAMMABLE GAS.** Protection of all personnel and the area must be maintained.

---

## **PART III** *How can I prevent hazardous situations from occurring?*

---

### **7. HANDLING and STORAGE**

**WORK PRACTICES AND HYGIENE PRACTICES:** As with all chemicals, avoid getting Isobutylene IN YOU. Do not eat or drink while handling chemicals. Be aware of any signs of dizziness or fatigue; exposures to fatal concentrations of Isobutylene could occur without any significant warning symptoms.

**STORAGE AND HANDLING PRACTICES:** Cylinders should be stored in dry, well-ventilated areas away from sources of heat. Compressed gases can present significant safety hazards. Store containers away from heavily trafficked areas and emergency exits. Post "No Smoking or Open Flames" signs in storage or use areas.

**SPECIAL PRECAUTIONS FOR HANDLING GAS CYLINDERS:** Protect cylinders against physical damage. Store in cool, dry, well-ventilated area, away from sources of heat, ignition and direct sunlight. Do not allow area where cylinders are stored to exceed 52°C (125°F). Isolate from oxidizers such as oxygen, chlorine, or fluorine. Use a check valve or trap in the discharge line to prevent hazardous backflow. Post "No Smoking or Open Flame" signs in storage and use areas. Cylinders should be stored upright and be firmly secured to prevent falling or being knocked over. Cylinders can be stored in the open, but in such cases, should be protected against extremes of weather and from the dampness of the ground to prevent rusting. Never tamper with pressure relief devices in valves and cylinders. Electrical equipment should be non-sparking or explosion proof. The following rules are applicable to situations in which cylinders are being used:

**Before Use:** Move cylinders with a suitable hand truck. Do not drag, slide, or roll cylinders. Do not drop cylinders or permit them to strike each other. Secure cylinders firmly. Leave the valve protection cap, if provided, in place until cylinder is ready for use.

**During Use:** Use designated CGA fittings and other support equipment. Do not use adapters. Do not heat cylinder by any means to increase the discharge rate of the product from the cylinder. Use check valve or trap in discharge line to prevent hazardous backflow into the cylinder. Do not use oils or grease on gas-handling fittings or equipment.

**After Use:** Close main cylinder valve. Replace valve protection cap, if provided. Mark empty cylinders "EMPTY".

**NOTE:** Use only DOT or ASME code containers. Earth-ground and bond all lines and equipment associated with Isobutylene. Close valve after each use and when empty. Cylinders must not be recharged except by or with the consent of owner. For additional information refer to the Compressed Gas Association Pamphlet P-1, *Safe Handling of Compressed Gases in Containers*. Additionally, refer to CGA Bulletin SB-2 "Oxygen Deficient Atmospheres".

**PROTECTIVE PRACTICES DURING MAINTENANCE OF CONTAMINATED EQUIPMENT:** Follow practices indicated in Section 6 (Accidental Release Measures). Make certain that application equipment is locked and tagged-out safely. Purge gas handling equipment with inert gas (e.g., nitrogen) before attempting repairs.

---

### **8. EXPOSURE CONTROLS - PERSONAL PROTECTION**

**VENTILATION AND ENGINEERING CONTROLS:** Use with adequate ventilation. Local exhaust ventilation is preferred, because it prevents Isobutylene dispersion into the work place by eliminating it at its source. If appropriate, install automatic monitoring equipment to detect the presence of potentially explosive air-gas mixtures and level of oxygen.

**RESPIRATORY PROTECTION:** Maintain oxygen levels above 19.5% in the workplace. Maintain level of gas below the level listed in Section 2 (Composition and Information on Ingredients). Use supplied air respiratory protection if oxygen levels are below 19.5% or during emergency response to a release of Isobutylene. If respiratory protection is required, follow the requirements of the Federal OSHA Respiratory Protection Standard (29 CFR 1910.134) or equivalent State standards.

**EYE PROTECTION:** Splash goggles or safety glasses, for protection from rapidly expanding gases and splashes of liquid Isobutylene.

**HAND PROTECTION:** Wear gloves resistant to tears when handling cylinders of Isobutylene. Use low-temperature protective gloves (e.g., Kevlar) when working with containers of liquid Isobutylene.

**BODY PROTECTION:** Use body protection appropriate for task. Transfer of large quantities under pressure may require protective equipment appropriate to protect employees from splashes of liquefied product, as well as fire retardant items.



---

## 9. PHYSICAL and CHEMICAL PROPERTIES

VAPOR DENSITY @ 21.1°C (70°F): 2.396 kg/m<sup>3</sup> (0.1496 lb/ft<sup>3</sup>)    pH: Not applicable.  
SPECIFIC GRAVITY (air = 1): 1.997    FREEZING POINT: -140°C (-220.6°F)  
SOLUBILITY IN WATER: Insoluble.    BOILING POINT @ 1 atm: -6.9°C (19.6°F)  
EVAPORATION RATE (nBuAc = 1): Not applicable.    EXPANSION RATIO: Not applicable  
ODOR THRESHOLD: Not established.    VAPOR PRESSURE (psia): 39  
COEFFICIENT WATER/OIL DISTRIBUTION: Not applicable.    SPECIFIC VOLUME (ft<sup>3</sup>/lb): 6.7

APPEARANCE AND COLOR: Colorless gas with the unpleasant odor of burning coal. The liquid is also colorless and has the same unpleasant odor of burning coal.

HOW TO DETECT THIS SUBSTANCE (warning properties): There are no distinct warning properties. In terms of leak detection, fittings and joints can be painted with a soap solution to detect leaks, which will be indicated by a bubble formation.

---

## 10. STABILITY and REACTIVITY

STABILITY: Stable.

DECOMPOSITION PRODUCTS: When ignited in the presence of oxygen, this gas will burn to produce carbon monoxide and carbon dioxide.

MATERIALS WITH WHICH SUBSTANCE IS INCOMPATIBLE: Strong oxidizers (e.g., chlorine, bromine pentafluoride, oxygen, oxygen difluoride, and nitrogen trifluoride).

HAZARDOUS POLYMERIZATION: Will not occur.

CONDITIONS TO AVOID: Contact with incompatible materials and exposure to heat, sparks, and other sources of ignition. Cylinders exposed to high temperatures or direct flame can rupture or burst.

---

## PART IV *Is there any other useful information about this material?*

---

## 11. TOXICOLOGICAL INFORMATION

TOXICITY DATA: The following information is for pure Isobutylene.

ISOBUTYLENE:

LC<sub>50</sub> (rat, inhalation) = 620 g/m<sup>3</sup>/4 hours

LC<sub>50</sub> (mouse, inhalation) = 415 g/m<sup>3</sup>/2 hours

SUSPECTED CANCER AGENT: Isobutylene is not found on the following lists: FEDERAL OSHA Z LIST, NTP, IARC, CAL/OSHA, and therefore is neither considered to be nor suspected to be a cancer-causing agent by these agencies.

IRRITANCY OF PRODUCT: Isobutylene may be mildly irritating to the mucous membranes. In addition, contact with rapidly expanding gases can cause frostbite to exposed tissue.

SENSITIZATION TO THE PRODUCT: Isobutylene is not known to cause sensitization in humans.

REPRODUCTIVE TOXICITY INFORMATION: Listed below is information concerning the effects of Isobutylene on the human reproductive system.

Mutagenicity: No mutagenic effects have been described for Isobutylene.

Embryotoxicity: No embryotoxic effects have been described for Isobutylene.

Teratogenicity: No teratogenic effects have been described for Isobutylene.

Reproductive Toxicity: No reproductive toxicity effects have been described for Isobutylene.

*A mutagen is a chemical which causes permanent changes to genetic material (DNA) such that the changes will propagate through generational lines. An embryotoxin is a chemical which causes damage to a developing embryo (i.e., within the first eight weeks of pregnancy in humans), but the damage does not propagate across generational lines. A teratogen is a chemical which causes damage to a developing fetus, but the damage does not propagate across generational lines. A reproductive toxin is any substance which interferes in any way with the reproductive process.*

MEDICAL CONDITIONS AGGRAVATED BY EXPOSURE: Acute or chronic respiratory conditions may be aggravated by overexposure to Isobutylene.

---

## 11. TOXICOLOGICAL INFORMATION (Continued)

RECOMMENDATIONS TO PHYSICIANS: Administer oxygen, if necessary. Treat symptoms and eliminate exposure.

BIOLOGICAL EXPOSURE INDICES (BEIs): Currently, Biological Exposure Indices (BEIs) are not applicable for Isobutylene.

---

## 12. ECOLOGICAL INFORMATION

ENVIRONMENTAL STABILITY: This gas will be dissipated rapidly in well-ventilated areas.

EFFECT OF MATERIAL ON PLANTS or ANIMALS: Any adverse effect on animals would be related to oxygen-deficient environments. No adverse effect is anticipated to occur to plant life, except for frost produced in the presence of rapidly expanding gases. See Section 11, Toxicological Information, for additional information on effects on animals.

EFFECT OF CHEMICAL ON AQUATIC LIFE: No evidence is currently available on the effects of Isobutylene on aquatic life.

---

## 13. DISPOSAL CONSIDERATIONS

PREPARING WASTES FOR DISPOSAL: Waste disposal must be in accordance with appropriate Federal, State, and local regulations. Return cylinders with any residual product to MESA Specialty Gases & Equipment. Do not dispose of locally.

---

## 14. TRANSPORTATION INFORMATION

THIS MATERIAL IS HAZARDOUS AS DEFINED BY 49 CFR 172.101 BY THE U.S. DEPARTMENT OF TRANSPORTATION.

**For Isobutylene Gas:**

<u>PROPER SHIPPING NAME:</u>	Isobutylene
<u>HAZARD CLASS NUMBER and DESCRIPTION:</u>	2.1 (Flammable Gas)
<u>UN IDENTIFICATION NUMBER:</u>	UN 1055
<u>PACKING GROUP:</u>	Not Applicable
<u>DOT LABEL(S) REQUIRED:</u>	Flammable Gas
<u>NORTH AMERICAN EMERGENCY RESPONSE GUIDEBOOK NUMBER (1996):</u>	115

**Alternate Description:**

<u>PROPER SHIPPING NAME:</u>	Petroleum gases, liquefied
<u>HAZARD CLASS NUMBER and DESCRIPTION:</u>	2.1 (Flammable Gas)
<u>UN IDENTIFICATION NUMBER:</u>	UN 1075
<u>PACKING GROUP:</u>	Not Applicable
<u>DOT LABEL(S) REQUIRED:</u>	Flammable Gas
<u>NORTH AMERICAN EMERGENCY RESPONSE GUIDEBOOK NUMBER (1996):</u>	115

MARINE POLLUTANT: Isobutylene is not classified by the DOT as a Marine Pollutant (as defined by 49 CFR 172.101, Appendix B).

TRANSPORT CANADA TRANSPORTATION OF DANGEROUS GOODS REGULATIONS: THIS MATERIAL IS CONSIDERED AS DANGEROUS GOODS. Use the above information for the preparation of Canadian Shipments.

---

## 15. REGULATORY INFORMATION

U.S. SARA REPORTING REQUIREMENTS: Isobutylene is not subject to the reporting requirements of Sections 302, 304, and 313 of Title III of the Superfund Amendments and Reauthorization Act.

U.S. SARA THRESHOLD PLANNING QUANTITY: Not applicable.

U.S. CERCLA REPORTABLE QUANTITY (RQ): Not applicable.

CANADIAN DSL/NDL INVENTORY STATUS: Isobutylene is on the DSL Inventory.

U.S. TSCA INVENTORY STATUS: Isobutylene is listed on the TSCA Inventory.

---

## 15. REGULATORY INFORMATION (Continued)

**OTHER U.S. FEDERAL REGULATIONS:** Isobutylene is subject to the reporting requirements of Section 112(r) of the Clean Air Act. The Threshold Quantity for this gas is 10,000 lb. Depending on specific operations involving the use of Isobutylene, the regulations of the Process Safety Management of Highly Hazardous Chemicals may be applicable (29 CFR 1910.119). Under this regulation Isobutylene is not listed in Appendix A; however, any process that involves a flammable gas on-site, in one location, in quantities of 10,000 lb (4,553 kg) or greater is covered under this regulation unless it is used as a fuel.

**U.S. STATE REGULATORY INFORMATION:** Isobutylene is covered under specific State regulations, as denoted below:

Alaska - Designated Toxic and Hazardous Substances: Liquefied Petroleum Gas.

California - Permissible Exposure Limits for Chemical Contaminants: Liquefied Petroleum Gas.

Florida - Substance List: Isobutylene.

Illinois - Toxic Substance List: No.

Kansas - Section 302/313 List: No.

Massachusetts - Substance List: Isobutylene.

Michigan - Critical Materials Register: No.

Minnesota - List of Hazardous Substances: Liquefied Petroleum Gas.

Missouri - Employer Information/Toxic Substance List: No.

New Jersey - Right to Know Hazardous Substance List: Isobutylene.

North Dakota - List of Hazardous Chemicals, Reportable Quantities: No.

Pennsylvania - Hazardous Substance List: Isobutylene.

Rhode Island - Hazardous Substance List: Liquefied Petroleum Gas.

Texas - Hazardous Substance List: Liquefied Petroleum Gas.

West Virginia - Hazardous Substance List: Liquefied Petroleum Gas.

Wisconsin - Toxic and Hazardous Substances: Liquefied Petroleum Gas.

**CALIFORNIA SAFE DRINKING WATER AND TOXIC ENFORCEMENT ACT (PROPOSITION 65):** Isobutylene is not on the California Proposition 65 lists.

### LABELING:

#### **DANGER:**

FLAMMABLE LIQUID AND GAS UNDER PRESSURE.  
CAN FORM EXPLOSIVE MIXTURES WITH AIR.  
MAY CAUSE FROSTBITE.

Keep away from heat, flames, and sparks.  
Store and use with adequate ventilation.  
Cylinder temperature should not exceed 52°C (125°F).  
Do not get liquid in eyes, on skin, or clothing.  
Close valve after each use and when empty.  
Use in accordance with the Material Safety Data Sheet.

#### **FIRST AID:**

**IF INHALED,** remove to fresh air. If not breathing, give artificial respiration. If breathing is difficult, give oxygen. Call a physician.


**IN CASE OF FROSTBITE,** obtain immediate medical attention.

**DO NOT REMOVE THIS PRODUCT LABEL.**

### CANADIAN WHMIS SYMBOLS:

**Class A:** Compressed Gas

**Class B1:** Flammable Gas



## 16. OTHER INFORMATION

The information contained herein is based on data considered accurate. However, no warranty is expressed or implied regarding the accuracy of these data or the results to be obtained from the use thereof. MESA Specialty Gases & Equipment assumes no responsibility for injury to the vendee or third persons proximately caused by the material if reasonable safety procedures are not adhered to as stipulated in the data sheet. Additionally, MESA Specialty Gases & Equipment assumes no responsibility for injury to vendee or third persons proximately caused by abnormal use of the material even if reasonable safety procedures are followed. Furthermore, vendee assumes the risk in his use of the material.

### DEFINITIONS OF TERMS

A large number of abbreviations and acronyms appear on a MSDS. Some of these which are commonly used include the following:

**CAS #:** This is the Chemical Abstract Service Number which uniquely identifies each constituent. It is used for computer-related searching.

#### EXPOSURE LIMITS IN AIR:

**ACGIH** - American Conference of Governmental Industrial Hygienists, a professional association which establishes exposure limits. **TLV** - Threshold Limit Value - an airborne concentration of a substance which represents conditions under which it is generally believed that nearly all workers may be repeatedly exposed without adverse effect. The duration must be considered, including the 8-hour Time Weighted Average (TWA), the 15-minute Short Term Exposure Limit, and the instantaneous Ceiling Level (C). Skin absorption effects must also be considered.

**OSHA** - U.S. Occupational Safety and Health Administration. **PEL** - Permissible Exposure Limit - This exposure value means exactly the same as a TLV, except that it is enforceable by OSHA. The OSHA Permissible Exposure Limits are based in the 1989 PELs and the June, 1993 Air Contaminants Rule (Federal Register: 58: 35338-35351 and 58: 40191). Both the current PELs and the vacated PELs are indicated. The phrase, "Vacated 1989 PEL," is placed next to the PEL which was vacated by Court Order.

**IDLH** - Immediately Dangerous to Life and Health - This level represents a concentration from which one can escape within 30-minutes without suffering escape-preventing or permanent injury. The **DFG** - MAK is the Republic of Germany's Maximum Exposure Level, similar to the U.S. PEL. **NIOSH** is the National Institute of Occupational Safety and Health, which is the research arm of the U.S. Occupational Safety and Health Administration (**OSHA**). NIOSH issues exposure guidelines called Recommended Exposure Levels (RELs). When no exposure guidelines are established, an entry of NE is made for reference.

#### HAZARD RATINGS:

**HAZARDOUS MATERIALS IDENTIFICATION SYSTEM:** Health Hazard: 0 (minimal acute or chronic exposure hazard); 1 (slight acute or chronic exposure hazard); 2 (moderate acute or significant chronic exposure hazard); 3 (severe acute exposure hazard; onetime overexposure can result in permanent injury and may be fatal); 4 (extreme acute exposure hazard; onetime overexposure can be fatal). Flammability Hazard: 0 (minimal hazard); 1 (materials that require substantial pre-heating before burning); 2 (combustible liquid or solids; liquids with a flash point of 38-93°C [100-200°F]); 3 (Class IB and IC flammable liquids with flash points below 38°C [100°F]); 4 (Class IA flammable liquids with flash points below 23°C [73°F] and boiling points below 38°C [100°F]). Reactivity Hazard: 0 (normally stable); 1 (material that can become unstable at elevated temperatures or which can react slightly with water); 2 (materials that are unstable but do not detonate or which can react violently with water); 3 (materials that can detonate when initiated or which can react explosively with water); 4 (materials that can detonate at normal temperatures or pressures).

**NATIONAL FIRE PROTECTION ASSOCIATION:** Health Hazard: 0 (material that on exposure under fire conditions would offer no hazard beyond that of ordinary combustible materials); 1 (materials that on exposure under fire conditions could cause irritation or minor residual injury); 2 (materials that on intense or continued exposure under fire conditions could cause temporary incapacitation or possible residual injury); 3 (materials that can on short exposure could cause serious temporary or residual injury); 4 (materials that under very short exposure causes death or major residual injury).

**NATIONAL FIRE PROTECTION ASSOCIATION (Continued):** Flammability Hazard and Reactivity Hazard: Refer to definitions for "Hazardous Materials Identification System".

#### FLAMMABILITY LIMITS IN AIR:

Much of the information related to fire and explosion is derived from the National Fire Protection Association (NFPA). Flash Point - Minimum temperature at which a liquid gives off sufficient vapors to form an ignitable mixture with air. Autoignition Temperature: The minimum temperature required to initiate combustion in air with no other source of ignition. LEL - the lowest percent of vapor in air, by volume, that will explode or ignite in the presence of an ignition source. UEL - the highest percent of vapor in air, by volume, that will explode or ignite in the presence of an ignition source.

#### TOXICOLOGICAL INFORMATION:

Possible health hazards as derived from human data, animal studies, or from the results of studies with similar compounds are presented. Definitions of some terms used in this section are: **LD<sub>50</sub>** - Lethal Dose (solids & liquids) which kills 50% of the exposed animals; **LC<sub>50</sub>** - Lethal Concentration (gases) which kills 50% of the exposed animals; **ppm** concentration expressed in parts of material per million parts of air or water; **mg/m<sup>3</sup>** concentration expressed in weight of substance per volume of air; **mg/kg** quantity of material, by weight, administered to a test subject, based on their body weight in kg. Data from several sources are used to evaluate the cancer-causing potential of the material. The sources are: **IARC** - the International Agency for Research on Cancer; **NTP** - the National Toxicology Program, **RTECS** - the Registry of Toxic Effects of Chemical Substances, **OSHA** and **CAL/OSHA**. **IARC** and **NTP** rate chemicals on a scale of decreasing potential to cause human cancer with rankings from 1 to 4. Subrankings (2A, 2B, etc.) are also used. Other measures of toxicity include **TDLo**, the lowest dose to cause a symptom and **TCLo** the lowest concentration to cause a symptom; **TD<sub>0</sub>**, **LDLo**, and **LDo**, or **TC**, **TC<sub>0</sub>**, **LCLo**, and **LCo**, the lowest dose (or concentration) to cause lethal or toxic effects. **BEI** - Biological Exposure Indices, represent the levels of determinants which are most likely to be observed in specimens collected from a healthy worker who has been exposed to chemicals to the same extent as a worker with inhalation exposure to the TLV. Ecological Information: **EC** is the effect concentration in water.

#### REGULATORY INFORMATION:

This section explains the impact of various laws and regulations on the material. **EPA** is the U.S. Environmental Protection Agency. **WHMIS** is the Canadian Workplace Hazardous Materials Information System. **DOT** and **TC** are the U.S. Department of Transportation and the Transport Canada, respectively. Superfund Amendments and Reauthorization Act (**SARA**); the Canadian Domestic/Non-Domestic Substances List (**DSL/NDL**); the U.S. Toxic Substance Control Act (**TSCA**); Marine Pollutant status according to the **DOT**; the Comprehensive Environmental Response, Compensation, and Liability Act (**CERCLA** or **Superfund**); and various state regulations.

# MATERIAL SAFETY DATA SHEET

Prepared to U.S. OSHA, CMA, ANSI and Canadian WHMIS Standards

## 1. PRODUCT IDENTIFICATION

**CHEMICAL NAME; CLASS: NON-FLAMMABLE GAS MIXTURE**

Containing One or More of the Following Components in a Nitrogen Balance Gas:

Oxygen, 0.0015-23.5%; Propane, 0-1.1%; n-Pentane, 0-0.75%; n-Hexane; 0-0.48%;

Carbon Monoxide, 0.0005-1.0%; Hydrogen Sulfide, 0.001-0.025%

NOTE: MIXTURES COMPRISED OF AN AIR BALANCE GAS CONTAIN BETWEEN 19.5-23.5% OXYGEN.

**SYNONYMS:** Not Applicable

**CHEMICAL FAMILY NAME:** Not Applicable

**FORMULA:** Not Applicable

**Document Number:** 50016 (Replaces ISC MSDS No.1810-2187, 1810-2343, 1810-3366, 1810-3937 1810-7219, 1810-7599, 1810-6179)

**Note:** The Material Safety Data Sheet is for this gas mixture supplied in cylinders with 33 cubic feet (935 liters) or less gas capacity (DOT - 39 cylinders). This MSDS has been developed for various gas mixtures with the composition of components within the ranges listed in Section 2 (Composition and Information on Ingredients). Refer to the product label for information on the actual composition of the product.

<b>PRODUCT USE:</b>	Calibration of Monitoring and Research Equipment
<b>SUPPLIER/MANUFACTURER'S NAME:</b>	CALGAZ
<b>ADDRESS:</b>	821 Chesapeake Drive Cambridge, MD 21613
<b>EMERGENCY PHONE:</b>	CHEMTREC: 1-800-424-9300
<b>BUSINESS PHONE:</b>	1-410-228-6400
	General MSDS Information 1-713/868-0440
	Fax on Demand: 1-800/231-1366

## 2. COMPOSITION and INFORMATION ON INGREDIENTS

CHEMICAL NAME	CAS #	mole %	EXPOSURE LIMITS IN AIR					
			ACGIHTLV		OSHA		IDLH	OTHER
			TWA ppm	STEL ppm	TWA ppm	STEL ppm		
Oxygen	7782-44-7	0.0015 - 23.5%	There are no specific exposure limits for Oxygen. Oxygen levels should be maintained above 19.5%.					
Propane	74-98-6	0 - 1.1%	2500	NE	1000	NE	2100	NIOSH REL: 1000 DFG MAK: 1000 ppm
n-Pentane	109-66-0	0 - 0.75%	600	750	1000 600 (Vacated 1989 PEL)	750 (Vacated 1989 PEL)	1500	NIOSH REL: TWA = 120 STEL = 610 (ceiling) 15 minutes DFG MAKs: TWA = 1000 PEAK = 2•MAK, 60 min., momentary value
n-Hexane	110-54-3	0 - 0.48%	50	NE	500 50 (Vacated 1989 PEL)	NE	1100	NIOSH REL: 50 DFG MAK: 50
Hydrogen Sulfide	7783-06-4	0.001-0.025 %	10 NIC = 5	15 NIC = 5	10 (Vacated 1989 PEL)	20 (ceiling), 50 (10 min. peak, once per shift) 15 (Vacated 1989 PEL)	100	NIOSH REL: STEL = 10 (ceiling), 10 minutes DFG MAKs: TWA = 10 PEAK = 2•MAK, 10 min., momentary value
Carbon Monoxide	630-08-0	0.0005 - 1.0%	25	NE	50 35 (Vacated 1989 PEL)	200 (ceiling) (Vacated 1989 PEL)	1200	NIOSH RELs: TWA = 35 STEL = 200 ceiling DFG MAKs: TWA = 30 PEAK = 2•MAK, 15 min., average value, 1 hr interval DFG MAK Pregnancy Risk Classification: B
Nitrogen	7727-37-9	Balance	There are no specific exposure limits for Nitrogen. Nitrogen is a simple asphyxiant (SA). Oxygen levels should be maintained above 19.5%.					

NE = Not Established.

NIC = Notice of Intended Change

See Section 16 for Definitions of Terms Used.

NOTE: ALL WHMIS required information is included in appropriate sections based on the ANSI Z400.1-1998 format. This gas mixture has been classified in accordance with the hazard criteria of the CPR and the MSDS contains all the information required by the CPR.

### 3. HAZARD IDENTIFICATION

**EMERGENCY OVERVIEW:** This gas mixture is a colorless gas which has a rotten-egg odor (due to the presence of Hydrogen Sulfide). The odor cannot be relied on as an adequate warning of the presence of this gas mixture, because olfactory fatigue occurs after over-exposure to Hydrogen Sulfide. Hydrogen Sulfide and Carbon Monoxide (another component of this gas mixture) are toxic to humans in relatively low concentrations. Over-exposure to this gas mixture can cause skin or eye irritation, nausea, dizziness, headaches, collapse, unconsciousness, coma, and death. The Propane, n-Pentane, and n-Hexane components can cause anesthetic or peripheral neuropathy effects. Additionally, releases of this gas mixture may produce oxygen-deficient atmospheres (especially in small confined spaces or other poorly-ventilated environments); individuals in such atmospheres may be asphyxiated.

**SYMPTOMS OF OVER-EXPOSURE BY ROUTE OF EXPOSURE:** The most significant route of over-exposure for this gas mixture is by inhalation.

**INHALATION:** Due to the small size of an individual cylinder of this gas mixture, no unusual health effects from over-exposure to the product are anticipated under routine circumstances of use. A significant health hazard associated with this gas mixture is the potential of inhalation of Hydrogen Sulfide, a component of this gas mixture. Such over-exposures may occur if this gas mixture is used in a confined space or other poorly-ventilated area. Over-exposures to Hydrogen Sulfide can cause dizziness, headache, and nausea. Exposure to this component can result in respiratory arrest, coma, or unconsciousness. Continuous inhalation of low concentrations of Hydrogen Sulfide may cause olfactory fatigue, so that the odor is no longer an effective warning of the presence of this gas. A summary of exposure concentrations and observed effects are as follows

**CONCENTRATION OF HYDROGEN SULFIDE**

**OBSERVED EFFECT**

0.3-30 ppm	Odor is obvious and unpleasant.
50 ppm	Eye irritation. Dryness and irritation of nose, throat.
Slightly higher than 50 ppm	Irritation of the respiratory system.
100-150 ppm	Temporary loss of smell.
200-250 ppm	Headache, vomiting, nausea. Prolonged exposure may lead to lung damage. Exposures of 4-8 hours can be fatal.
300-500	Swifter onset of symptoms. Death occurs in 1-4 hours.
500 ppm	Headache, excitement, staggering, and stomach ache after brief exposure. Death occurs within 0.5 - 1 hour of exposure.
> 600 ppm	Rapid onset of unconsciousness, coma, death.
> 1000 ppm	Immediate respiratory arrest.

NOTE:

This gas mixture contains a maximum of 250 ppm Hydrogen Sulfide. The higher concentration values here are presented to delineate the complete health effects which have been observed for humans after exposure to Hydrogen Sulfide.

Inhalation over-exposures to atmospheres containing more than the Threshold Limit Value of Carbon Monoxide (25 ppm), another component of this gas mixture, can result in serious health consequences. Carbon Monoxide is classified as a chemical asphyxiant, producing a toxic action by combining with the hemoglobin of the blood and replacing the available oxygen. Through this replacement, the body is deprived of the required oxygen, and asphyxiation occurs.

Since the affinity of Carbon Monoxide for hemoglobin is about 200-300 times that of oxygen, only a small amount of Carbon Monoxide will cause a toxic reaction to occur. Carbon Monoxide exposures in excess of 50 ppm will produce symptoms of poisoning if breathed for a sufficiently long time. If this gas mixture is released in a small, poorly ventilated area (i.e. an enclosed or confined space), symptoms which may develop include the following:

**CONCENTRATION OF CARBON MONOXIDE**

**OBSERVED EFFECT**

All exposure levels: ..	Over-exposure to Carbon Monoxide can be indicated by the lips and fingernails turning bright red.
200 ppm: .....	Slight symptoms (i.e. headache) after several hours of exposure.
400 ppm:	Headache and discomfort experienced within 2-3 hours of exposure.
1,000 -2000 ppm:	Within 30 minutes, slight palpitations of the heart occurs. Within 1.5 hours, there is a tendency to stagger.
200-2500 ppm:	Within 2 hours, there is mental confusion, headaches, and nausea. Unconsciousness within 30 minutes.
> 2500 ppm:	Potential for collapse and death before warning symptoms.

Another hazard associated with this gas mixture is the potential for anesthetic and peripheral neuropathy effects after inhalation over-exposures to the Propane, n-Pentane and n-Hexane components of this gas mixture. Specific human over-exposure data are available for n-Pentane and n-Hexane, as follows:

**CONCENTRATION OF n-PENTANE**

**OBSERVED EFFECT**

Brief (10 minute) up to 5,000 ppm:	No symptoms.
Higher than 5,000 ppm:	Exhilaration, dizziness and headache can occur.
Long term:	Can cause chronic neurological disorder causing damage to the nerves in the hands and feet (peripheral neuropathy)

**CONCENTRATION OF n-HEXANE**

**OBSERVED EFFECT**

Brief (10 minute) at 1,500 ppm:	Irritation of the respiratory tract, nausea and headache.
5000 ppm:	Dizziness and drowsiness can occur.
Long term at 500 ppm:	Can affect the nerves in the arms and legs. Effects include numbing or tingling sensations in the fingers and toes, tiredness, muscle weakness, cramps and spasms in the leg, difficulty in holding objects or walking, abdominal pains, loss of appetite, weight loss. More serious exposures can cause damage to the nerves in the hands and feet (peripheral neuropathy).

Eyes and Vision:

Abnormal color perception and pigment changes in the eyes have been reported among industrial workers exposed to 423-1280 ppm for 5 years or more.

Blood Cells:

Mild forms of anemia have also been associated with exposure to hexane. These are of temporary nature.

Additionally, if mixtures of this gas mixture contain less than 19.5% Oxygen and are released in a small, poorly ventilated area (i.e. an enclosed or confined space), an oxygen-deficient environment may occur. Individuals breathing such an atmosphere may experience symptoms which include headaches, ringing in ears, dizziness, drowsiness, unconsciousness, nausea, vomiting, and depression of all the senses. Under some circumstances of over-exposure, death may occur. The following effects associated with various levels of oxygen are as follows:

**CONCENTRATION OF OXYGEN**

**OBSERVED EFFECT**

12-16% Oxygen:	Breathing and pulse rate increased, muscular coordination slightly disturbed.
10-14% Oxygen:	Emotional upset, abnormal fatigue, disturbed respiration.
6-10% Oxygen:	Nausea, vomiting, collapse, or loss of consciousness.
Below 6%:	Convulsive movements, possible respiratory collapse, and death.

**SKIN and EYE CONTACT:** The Hydrogen Sulfide component of this gas mixture may be irritating to the skin. Inflammation and irritation of the eyes can occur at very low airborne concentration of Hydrogen Sulfide (less than 10 ppm). Exposure over several hours may result in "gas eyes" or "sore eyes" with symptoms of scratchiness, irritation, tearing and burning. Above 50 ppm of Hydrogen Sulfide, there is an intense tearing, blurring of vision, and pain when looking at light. Over-exposed individuals may see rings around bright lights. Most symptoms disappear when exposure ceases. However, in serious cases, the eye can be permanently damaged.

**HEALTH EFFECTS OR RISKS FROM EXPOSURE: An Explanation in Lay Terms.** Over-exposure to this gas mixture may cause the following health effects:

**ACUTE:** Due to the small size of the individual cylinder of this gas mixture, no unusual health effects from exposure to the product are anticipated under routine circumstances of use. However, the Hydrogen Sulfide and Carbon Monoxide components of this gas mixture are toxic to humans. Over-exposure to this gas mixture can cause nausea, dizziness, headaches, collapse, unconsciousness, coma, and death. Due to the presence of Hydrogen Sulfide, over-exposures to this gas mixture can also irritate the skin and eyes; severe eye contamination can result in blindness. Inhalation over-exposures to Propane, n-Pentane, and n-Hexane can cause anesthetic effects and motor neuropathy (i.e. pain and tingling in feet and hands).

HAZARDOUS MATERIAL IDENTIFICATION SYSTEM		
<b>HEALTH HAZARD</b>	(BLUE)	3
<b>FLAMMABILITY HAZARD</b>	(RED)	0
<b>PHYSICAL HAZARD</b>	(YELLOW)	0
PROTECTIVE EQUIPMENT		
EYES	RESPIRATORY	HANDS
BODY		
See Section 8		
For Routine Industrial Use and Handling Applications		

### 3. HAZARD IDENTIFICATION (Continued)

**CHRONIC:** Abnormal color perception and pigment changes in the eyes have been reported among persons exposed to 420 -1300 ppm of n-Hexane for five years. Additionally, long-term exposure to low levels of n-Hexane or n-Pentane can affect the nerves in the arms and legs. Effects include numbing or tingling sensation, tiredness, cramps, spasms in legs, difficulty holding objects or walking, loss of appetite and weight loss. Pentane isomers, such as n-Pentane, and Propane can cause sensitization of the heart to epinephrine. Refer to Section 11 (Toxicology Information) for additional information on the components of this gas mixture.

**TARGET ORGANS:** ACUTE: Respiratory system, blood system, central nervous system, cardiovascular system. CHRONIC: Reproductive system, cardiovascular system.

### 4. FIRST-AID MEASURES

**RESCUERS SHOULD NOT ATTEMPT TO RETRIEVE VICTIMS OF EXPOSURE TO THIS GAS MIXTURE WITHOUT ADEQUATE PERSONAL PROTECTIVE EQUIPMENT. At a minimum, Self-Contained Breathing Apparatus must be worn.**

No unusual health effects are anticipated after exposure to this gas mixture, due to the small cylinder size. If any adverse symptom develops after over-exposure to this gas mixture, remove victim(s) to fresh air as quickly as possible. Only trained personnel should administer supplemental oxygen and/or cardio-pulmonary resuscitation if necessary.

Victim(s) who experience any adverse effect after over-exposure to this gas mixture must be taken for medical attention. Rescuers should be taken for medical attention if necessary. Take a copy of the label and the MSDS to physician or other health professional with victim(s).

**SKIN EXPOSURE:** If irritation of the skin develops after exposure to this gas mixture, immediately begin decontamination with running water. Minimum flushing is for 15 minutes. Remove exposed or contaminated clothing, taking care not to contaminate eyes. Victim must seek immediate medical attention.

**EYE EXPOSURE:** If irritation of the eye develops after exposure to this gas mixture, open victim's eyes while under gentle running water. Use sufficient force to open eyelids. Have victim "roll" eyes. Minimum flushing is for 15 minutes. Seek medical assistance immediately, preferably an ophthalmologist.

**MEDICAL CONDITIONS AGGRAVATED BY EXPOSURE:** Pre-existing respiratory conditions may be aggravated by over-exposure to this gas mixture. Carbon Monoxide, a component of this gas mixture, can aggravate some diseases of the cardiovascular system, such as coronary artery disease and angina pectoris. Because of the presence of Hydrogen Sulfide, n-Hexane or n-Pentane in this gas mixture, central nervous system conditions, eye disorders, or skin problems may be aggravated by over-exposure to this gas mixture.

**RECOMMENDATIONS TO PHYSICIANS:** Treat symptoms and eliminate over-exposure. Hyperbaric oxygen is the most efficient antidote to Carbon Monoxide poisoning, the optimum range being 2-2.5 atm. A special mask, or, preferably, a compression chamber to utilize oxygen at these pressures is required. Avoid administering stimulant drugs. Be observant for initial signs of pulmonary edema in the event of severe inhalation over-exposures.

### 5. FIRE-FIGHTING MEASURES

**FLASH POINT:** Not applicable.

**AUTOIGNITION TEMPERATURE:** Not applicable.

**FLAMMABLE LIMITS (in air by volume, %):**

Lower (LEL): Not applicable.

Upper (UEL): Not applicable.


**FIRE EXTINGUISHING MATERIALS:** Non-flammable gas mixture. Use extinguishing media appropriate for surrounding fire.

**UNUSUAL FIRE AND EXPLOSION HAZARDS:** This gas mixture contains toxic gases, Hydrogen Sulfide and Carbon Monoxide, and presents an extreme health hazard to firefighters. This gas mixture is not flammable; however, containers, when involved in fire, may rupture or burst in the heat of the fire.

Explosion Sensitivity to Mechanical Impact: Not Sensitive.

Explosion Sensitivity to Static Discharge: Not Sensitive.

**SPECIAL FIRE-FIGHTING PROCEDURES:** Structural firefighters must wear Self-Contained Breathing Apparatus and full protective equipment.



### 6. ACCIDENTAL RELEASE MEASURES

**LEAK RESPONSE:** Due to the small size and content of the cylinder, an accidental release of this gas mixture presents significantly less risk of over-exposure to Hydrogen Sulfide and Carbon Monoxide, the toxic components of this gas mixture, and other safety hazards related to the remaining components of this gas mixture, than a similar release from a larger cylinder. However, as with any chemical release, extreme caution must be used during emergency response procedures. In the event of a release in which the atmosphere is unknown, and in which other chemicals are potentially involved, evacuate immediate area. Such releases should be responded to by trained personnel using pre-planned procedures. Proper protective equipment should be used. In case of a leak, clear the affected area, protect people, and respond with trained personnel.

For emergency disposal, secure the cylinder and slowly discharge the gas to the atmosphere in a well-ventilated area or outdoors. Allow the gas mixture to dissipate. If necessary, monitor the surrounding area (and the original area of the release) for Hydrogen Sulfide, Carbon Monoxide, and Oxygen. Hydrogen Sulfide and Carbon Monoxide level must be below exposure level listed in Section 2 (Composition and Information on Ingredients) and Oxygen levels must be above 19.5% before non-emergency personnel are allowed to re-enter area.

If leaking incidentally from the cylinder, contact your supplier.

### 7. HANDLING and USE

**WORK PRACTICES AND HYGIENE PRACTICES:** Be aware of any signs of dizziness or fatigue; exposures to fatal concentrations of this gas mixture could occur without any significant warning symptoms, due to olfactory fatigue or oxygen deficiency. Do not attempt to repair, adjust, or in any other way modify cylinders containing a gas mixture with Hydrogen Sulfide or Carbon Monoxide. If there is a malfunction or another type of operational problem, contact nearest distributor immediately. Eye wash stations/safety showers should be near areas where this gas mixture is used or stored. All work operations should be monitored in such a way that emergency personnel can be immediately contacted in the event of a release. All work practices should minimize releases of Hydrogen Sulfide and Carbon Monoxide-containing gas mixtures.

**STORAGE AND HANDLING PRACTICES:** Cylinders should be firmly secured to prevent falling or being knocked-over. Cylinders must be protected from the environment, and preferably kept at room temperature (approximately 21°C, 70°F). Cylinders should be stored in dry, well-ventilated areas, away from sources of heat, ignition, and direct sunlight. Protect cylinders against physical damage.

Full and empty cylinders should be segregated. Use a first-in, first-out inventory system to prevent full containers from being stored for long periods of time. These cylinders are not refillable. **WARNING! Do not refill DOT 39 cylinders. To do so may cause personal injury or property damage.**

**SPECIAL PRECAUTIONS FOR HANDLING GAS CYLINDERS: WARNING!** Compressed gases can present significant safety hazards. During cylinder use, use equipment designed for these specific cylinders. Ensure all lines and equipment are rated for proper service pressure.

**PROTECTIVE PRACTICES DURING MAINTENANCE OF CONTAMINATED EQUIPMENT:** Follow practices indicated in Section 6 (Accidental Release Measures). Make certain that application equipment is locked and tagged-out safely. Always use product in areas where adequate ventilation is provided.

### 8. EXPOSURE CONTROLS - PERSONAL PROTECTION

**VENTILATION AND ENGINEERING CONTROLS:** No special ventilation systems or engineering controls are needed under normal circumstances of use. As with all chemicals, use this gas mixture in well-ventilated areas. If this gas mixture is used in a poorly-ventilated area, install automatic monitoring equipment to detect the levels of Oxygen, Hydrogen Sulfide, and Carbon Monoxide.

**RESPIRATORY PROTECTION:** No special respiratory protection is required under normal circumstances of use. Use supplied air respiratory protection if Carbon Monoxide levels exceed the exposure levels given in Section 2 (Composition and Information on Ingredients) or if oxygen levels are below 19.5%, or if either level is unknown during emergency response to a release of this gas mixture. If respiratory protection is required for emergency response to this gas mixture, follow the requirements of the Federal OSHA Respiratory Protection Standard (29 CFR 1910.134) or equivalent State standards. The following NIOSH respiratory protection recommendations for Hydrogen Sulfide and Carbon Monoxide are provided for further information.

## 8. EXPOSURE CONTROLS - PERSONAL PROTECTION (Continued)

### NIOSH/OSHA RECOMMENDATIONS FOR HYDROGEN SULFIDE CONCENTRATIONS IN AIR:

Up to 100 ppm: Powered air-purifying respirator with cartridge(s) to protect against hydrogen sulfide; or gas mask with canister to protect against hydrogen sulfide; or SAR; or full-facepiece SCBA.

Emergency or Planned Entry into Unknown Concentration or IDLH Conditions: Positive pressure, full-facepiece SCBA; or positive pressure, full-facepiece SAR with an auxiliary positive pressure SCBA.

Escape: Gas mask with canister to protect against hydrogen sulfide; or escape-type SCBA

NOTE: The IDLH concentration for Hydrogen Sulfide is 100 ppm.

### NIOSH/OSHA RECOMMENDATIONS FOR CARBON MONOXIDE CONCENTRATIONS IN AIR:

Up to 350 ppm Supplied Air Respirator (SAR)

Up to 875 ppm Supplied Air Respirator (SAR) operated in a continuous flow mode.

Up to 1200 ppm Gas mask with canister to protect against carbon monoxide; or full-facepiece SCBA; or full-facepiece Supplied Air Respirator (SAR).

Emergency or Planned Entry into Unknown Concentration or IDLH Conditions: Positive pressure, full-facepiece SCBA; or positive pressure, full-facepiece Supplied Air Respirator (SAR) with an auxiliary positive pressure SCBA.

Escape: Gas mask with canister to protect against carbon monoxide; or escape-type SCBA.

NOTE: End of Service Life Indicator (ESLI) required for gas masks.

**EYE PROTECTION:** Safety glasses. If necessary, refer to U.S. OSHA 29 CFR 1910.133 or appropriate Canadian Standards.

**HAND PROTECTION:** No special protection is needed under normal circumstances of use. If necessary, refer to U.S. OSHA 29 CFR 1910.138 or appropriate Standards of Canada.

**BODY PROTECTION:** No special protection is needed under normal circumstances of use. If a hazard of injury to the feet exists due to falling objects, rolling objects, where objects may pierce the soles of the feet or where employee's feet may be exposed to electrical hazards, use foot protection, as described in U.S. OSHA 29 CFR 1910.136.

## 9. PHYSICAL and CHEMICAL PROPERTIES

The following information is for Nitrogen, the main component of this gas mixture.

**GAS DENSITY @ 32°F (0°C) and 1 atm:** 0.072 lbs/ft<sup>3</sup> (1.153 kg/m<sup>3</sup>)

**FREEZING/MELTING POINT @ 10 psig:** -210°C (-345.8°F)

**SPECIFIC GRAVITY (air = 1) @ 70°F (21.1°C):** 0.906

**SOLUBILITY IN WATER vol/vol @ 32°F (0°C) and 1 atm:** 0.023

**EVAPORATION RATE (nBuAc = 1):** Not applicable.

**ODOR THRESHOLD:** Not applicable.

**VAPOR PRESSURE @ 70°F (21.1°C) psig:** Not applicable.

**COEFFICIENT WATER/OIL DISTRIBUTION:** Not applicable.

**BOILING POINT:** -195.8°C (-320.4°F)

**pH:** Not applicable.

**MOLECULAR WEIGHT:** 28.01

**EXPANSION RATIO:** Not applicable.

**SPECIFIC VOLUME (ft<sup>3</sup>/lb):** 13.8

The following information is for the gas mixture.

**APPEARANCE AND COLOR:** This gas mixture is a colorless gas which has an rotten egg-like odor, due to the presence of Hydrogen Sulfide.

**HOW TO DETECT THIS SUBSTANCE (warning properties):** Continuous inhalation of low concentrations of Hydrogen Sulfide (a component of this gas mixture) may cause olfactory fatigue, so that there are no distinct warning properties. In terms of leak detection, fittings and joints can be painted with a soap solution to detect leaks, which will be indicated by a bubble formation. Wet lead acetate paper can be used for leak detection. The paper turns black in the presence of Hydrogen Sulfide. Cadmium chloride solutions can also be used. Cadmium solutions will turn yellow upon contact with Hydrogen Sulfide.

## 10. STABILITY and REACTIVITY

**STABILITY:** Normally stable in gaseous state.

**DECOMPOSITION PRODUCTS:** The thermal decomposition products of Propane, n-Hexane, and n-Pentane include carbon oxides. The decomposition products of Hydrogen Sulfide include water and sulfur oxides. The other components of this gas mixture do not decompose, per se, but can react with other compounds in the heat of a fire.

**MATERIALS WITH WHICH SUBSTANCE IS INCOMPATIBLE:** Titanium will burn in Nitrogen (the main component of this gas mixture). Lithium reacts slowly with Nitrogen at ambient temperatures. Components of this gas mixture (Hydrogen Sulfide, Propane, n-Pentane, n-Hexane) are also incompatible with strong oxidizers (i.e. chlorine, bromine pentafluoride, oxygen, oxygen difluoride, and nitrogen trifluoride). Carbon Monoxide is mildly corrosive to nickel and iron (especially at high temperatures and pressures). Hydrogen Sulfide is corrosive to most metals, because it reacts with these substances to form metal sulfides.

**HAZARDOUS POLYMERIZATION:** Will not occur.

**CONDITIONS TO AVOID:** Contact with incompatible materials. Cylinders exposed to high temperatures or direct flame can rupture or burst.

## 11. TOXICOLOGICAL INFORMATION

**TOXICITY DATA:** The following toxicology data are available for the components of this gas mixture:

**NITROGEN:** There are no specific toxicology data for Nitrogen. Nitrogen is a simple asphyxiant, which acts to displace oxygen in the

### n-PENTANE:

LD<sub>50</sub> (intravenous, mouse) = 446 mg/kg.

LC<sub>50</sub> (inhalation, rat) = 364 g/m<sup>3</sup>/4 hours

LCLo (inhalation, mouse) = 325 g/m<sup>3</sup>/2 hours

### n-HEXANE:

Eye, rabbit = 10 mg/ mild

TCLo (inhalation, rat) = 10,000 ppm/7 hr.

TCLo (inhalation, rat) = 5000 ppm/20 hours; teratogenic effects

LD50 (oral, rat) = 28710 mg/kg

LDLo (intraperitoneal, rat) = 9100 mg/kg

LCLo (inhalation, mouse) = 120,000 mg/kg

LD50 (rat, oral) = 28,710 mg/kg

ACUTE INHALATION (mouse): 30,000 ppm, narcosis within 30 to 60 minutes; 35,000-40,000 ppm, convulsions and death.

DERMAL (rabbit): 2 to 5 ml/kg for 4 hours resulted in restlessness and discoordination.; death occurred at 5 ml/kg.

### HYDROGEN SULFIDE:

LCLo (inhalation, human) = 600 ppm/30 minutes

LDLo (inhalation, man) = 5.7 mg/kg; central nervous system, pulmonary effects

**SUSPECTED CANCER AGENT:** The components of this gas mixture are not found on the following lists: FEDERAL OSHA Z LIST, NTP, CAL/OSHA, and IARC; therefore, they are not considered to be, nor suspected to be, cancer-causing agents by these agencies.

**IRRITANCY OF PRODUCT:** The Hydrogen Sulfide component of this gas mixture, is irritating to the eyes, and may be irritating to the skin.

**SENSITIZATION OF PRODUCT:** The components of this gas mixture are not known to be skin or respiratory sensitizers. Pentane isomers (i.e. n-Pentane) and Propane can cause cardiac sensitization to epinephrine.

**REPRODUCTIVE TOXICITY INFORMATION:** Listed below is information concerning the effects of this gas mixture on the human reproductive system.

**Mutagenicity:** No mutagenicity effects have been described for the components of this gas mixture.

**Embryotoxicity:** This gas mixture contains components that may cause embryotoxic effects in humans; however, due to the small total amount of the components, embryotoxic effects are not expected to occur.

**Teratogenicity:** This gas mixture is not expected to cause teratogenic effects in humans due to the small cylinder size and small total amount of all components. The Carbon Monoxide component of this gas mixture which exists up to 1%, can cause teratogenic effects in humans. Severe

### n-HEXANE (continued):

CHRONIC INHALATION (rat): 400-600 ppm, 5 days/week, peripheral neuropathy in 45 days; 850 ppm for 143 days, loss of weight and degeneration of the sciatic nerve. (mouse): 250 ppm, peripheral neuropathy within 7 months; no effects at 100 ppm.

### PROPANE:

**Long-Term Inhalation:** No toxicity or abnormalities were observed when monkeys were exposed to approximately 750 ppm for 90 days. Similar results were obtained when monkeys were exposed to an aerosol spray containing 65% propane and isobutane.

### CARBON MONOXIDE:

TCLo (inhalation, mouse) = 65 ppm/24 hours (7-18 preg): rep. effects

TCLo (inhalation, mouse) = 8 pph/1 hour (female 8D post): ter. effects

### HYDROGEN SULFIDE (continued):

LCLo (inhalation, human) = 800 ppm/5 minutes

LC<sub>50</sub> (inhalation, rat) = 444 ppm

### CARBON MONOXIDE (continued):

TCLo (inhalation, human) = 600 mg/m<sup>3</sup>/10 minutes

LCLo (inhalation, man) = 4000 ppm/30 minutes

TCLo (inhalation, man) = 650 ppm/45 minutes: central nervous system and blood system effects.

LCLo (inhalation, human) = 5000 ppm/5 minutes

LCLo (inhalation, dog) = 4000 ppm/46 minutes

LCLo (inhalation, rabbit) = 4000 ppm

LC<sub>50</sub> (inhalation, rat) = 1811 ppm/4 hours

LC<sub>50</sub> (inhalation, guinea pig) = 2450 ppm/4 hours

LC<sub>50</sub> (inhalation, guinea pig) = 5718 ppm/4 hours

LCLo (inhalation, mammal) = 5000 ppm/5 minutes

LD<sub>50</sub> (inhalation, wild bird) = 1334 ppm

### HYDROGEN SULFIDE (continued):

LC<sub>50</sub> (inhalation, mouse) = 673 ppm/1 hour

LCLo (inhalation, mammal) = 800 ppm/5 minutes



## 11. TOXICOLOGICAL INFORMATION (continued)

exposure to Carbon Monoxide during pregnancy has caused adverse effects and the death of the fetus. In general, maternal symptoms are an indicator of the potential risk to the fetus since Carbon Monoxide is toxic to the mother before it is toxic to the fetus.

**Reproductive Toxicity:** The components of this gas mixture are not expected to cause adverse reproductive effects in humans.

A **mutagen** is a chemical which causes permanent changes to genetic material (DNA) such that the changes will propagate through generation lines. An **embryotoxin** is a chemical which causes damage to a developing embryo (i.e. within the first eight weeks of pregnancy in humans), but the damage does not propagate across generational lines. A **teratogen** is a chemical which causes damage to a developing fetus, but the damage does not propagate across generational lines. A **reproductive toxin** is any substance which interferes in any way with the reproductive process.

**BIOLOGICAL EXPOSURE INDICES (BEIs):** Biological Exposure Indices (BEIs) have been determined for the components of this gas mixture, as follows:

CHEMICAL DETERMINANT	SAMPLING TIME	BEI
CARBON MONOXIDE • Carboxyhemoglobin in blood • Carbon monoxide in end-exhaled air	• End of shift • End of shift	• 3.5% of hemoglobin • 20 ppm
n-HEXANE • 2,5-Hexanedione in urine • n-Hexane in end-exhaled air	• End of shift	• 5 mg/g creatinine

## 12. ECOLOGICAL INFORMATION

**ENVIRONMENTAL STABILITY:** The gas will be dissipated rapidly in well-ventilated areas. The following environmental data are applicable to the components of this gas mixture.

**OXYGEN:** Water Solubility = 1 volume Oxygen/32 volumes water at 20°C. Log  $K_{ow}$  = -0.65

**PROPANE:** Log  $K_{ow}$  = 2.38. Water Solubility = 62.4 ppm, 25°C. Propane is readily degraded by soil bacteria.

**PENTANE:** Log  $K_{ow}$  = 3.39. Water Solubility = 38.5 mg/L. LOG BCF (n-pentane) = calculated, 1.90 and 2.35, respectively. Photolysis, hydrolysis, and bioconcentration are not anticipated to be important fate processes. Biodegradation and soil adsorption are anticipated to be more important processes for this compound.

**n-HEXANE:** Log  $K_{ow}$  = 3.90-4.11. Water Solubility = 9.5 mg/L. Estimated Bioconcentration Factor = 2.24 and 2.89. Bioconcentration in aquatic organisms is low. Hexane is volatile. Rapid volatilization from water and soil is anticipated for this compound. Hexane will float in slick on surface of the water

**HYDROGEN SULFIDE:** Water Solubility = 1 g/242 mL at 20°C.

**CARBON MONOXIDE:** Water solubility = 3.3 ml/100 cc at 0 °C, 2.3 ml at 20°C.

**NITROGEN:** Water Solubility = 2.4 volumes Nitrogen/100 volumes water at 0°C; 1.6 volumes Nitrogen/100 volumes water at 20°C.

**EFFECT OF MATERIAL ON PLANTS or ANIMALS:** No evidence is currently available on this gas mixture's effects on plant and animal life. The Hydrogen Sulfide and Carbon Monoxide components of this gas mixture, can be deadly to exposed animal life, producing symptoms similar to those experienced by humans. This gas mixture may also be harmful to plant life.

**EFFECT OF CHEMICAL ON AQUATIC LIFE:** No evidence is currently available on the effects of this gas effects on aquatic life. The presence of more than a trace of Carbon Monoxide is a hazard to fish. The following aquatic toxicity data are available for the Hydrogen Sulfide component of this gas mixture.

TLm (Asellussp) = 0.111 mg/L/96 hour

TLm (Lepomis macrochirus, bluegill sunfish) = 0.0448 mg/L/96 hour at 21-22 °C

TLm (Cranfongonyx sp) = 1.07 mg/L/96 hour

TLm (Pimephales promelas, fathead minnow) = 0.0071-0.55 mg/L/96 hour

TLm (Gammarrus) = 0.84 mg/L/96 hour

LC<sub>50</sub> (fly inhalation) = 380 mg/m<sup>3</sup>/960 minutes

LC<sub>50</sub> (fly inhalation) = 1500 mg/m<sup>3</sup>/7 minutes

TLm (Salvelinus fontinalis, brook trout) = 0.0216-0.038 mg/L/96 hour at 8-12.5 °C

TLm (Lepomis macrochirus, bluegill sunfish) = 0.0478 mg/L/96 hour

## 13. DISPOSAL CONSIDERATIONS

**PREPARING WASTES FOR DISPOSAL:** Waste disposal must be in accordance with appropriate Federal, State, and local regulations. Cylinders with undesired residual product may be safely vented outdoors with the proper regulator. For further information, refer to Section 16 (Other Information).

## 14. TRANSPORTATION INFORMATION

**THIS GAS MIXTURE IS HAZARDOUS AS DEFINED BY 49 CFR 172.101 BY THE U.S. DEPARTMENT OF TRANSPORTATION.**

**PROPER SHIPPING NAME:** Compressed gases, n.o.s. (\*Oxygen, Nitrogen)\* or the gas component with the next highest concentration next to Nitrogen.

**HAZARD CLASS NUMBER and DESCRIPTION:** 2.2 (Non-Flammable Gas)

**UN IDENTIFICATION NUMBER:** UN 1956

**PACKING GROUP:** Not Applicable

**DOT LABEL(S) REQUIRED:** Class 2.2 (Non-Flammable Gas)

**NORTH AMERICAN EMERGENCY RESPONSE GUIDEBOOK NUMBER (2000):** 126

**MARINE POLLUTANT:** The components of this gas mixture are not classified by the DOT as Marine Pollutants (as defined by 49 CFR 172.101, Appendix B).

**SPECIAL SHIPPING INFORMATION:** Cylinders should be transported in a secure position, in a well-ventilated vehicle. The transportation of compressed gas cylinders in automobiles or in closed-body vehicles can present serious safety hazards. If transporting these cylinders in vehicles, ensure these cylinders are not exposed to extremely high temperatures (as may occur in an enclosed vehicle on a hot day). Additionally, the vehicle should be well-ventilated during transportation.

**Note:** DOT 39 Cylinders ship in a strong outer carton (overpack). Pertinent shipping information goes on the outside of the overpack. DOT 39 Cylinders do not have transportation information on the cylinder itself.

**TRANSPORT CANADA TRANSPORTATION OF DANGEROUS GOODS REGULATIONS:** This gas is considered as Dangerous Goods, per regulations of Transport Canada.

**PROPER SHIPPING NAME:** Compressed gases, n.o.s. (\*Oxygen, Nitrogen)\* or the gas component with the next highest concentration next to Nitrogen.

**HAZARD CLASS NUMBER and DESCRIPTION:** 2.2 (Non-Flammable Gas)

**UN IDENTIFICATION NUMBER:** UN 1956

**PACKING GROUP:** Not Applicable

**HAZARD LABEL:** Class 2.2 (Non-Flammable Gas)

**SPECIAL PROVISIONS:** None

**EXPLOSIVE LIMIT AND LIMITED QUANTITY INDEX:** 0.12

**ERAP INDEX:** None

**PASSENGER CARRYING SHIP INDEX:** None

**PASSENGER CARRYING ROAD VEHICLE OR PASSENGER CARRYING RAILWAY VEHICLE INDEX:** 75

**NORTH AMERICAN EMERGENCY RESPONSE GUIDEBOOK NUMBER (2000):** 126

**NOTE:** Shipment of compressed gas cylinders via Public Passenger Road Vehicle is a violation of Canadian law (Transport Canada Transportation of Dangerous Goods Act, 1992).

## 15. REGULATORY INFORMATION

**ADDITIONAL U.S. REGULATIONS:**

**U.S. SARA REPORTING REQUIREMENTS:** This gas is not subject to the reporting requirements of Sections 302, 304 and 313 of Title III of the Superfund Amendments and Reauthorization Act., as follows:

COMPONENT	SARA 302 (40 CFR 355, Appendix A)	SARA 304 (40 CFR Table 302.4)	SARA 313 (40 CFR 372.65)
n-Hexane	NO	YES	YES
Hydrogen Sulfide	YES	YES	YES

## 15. REGULATORY INFORMATION (Continued)

**U.S. SARA THRESHOLD PLANNING QUANTITY:** Section 302 EHS TPQ = Hydrogen Sulfide = 500 lbs (227 kg);

**U.S. TSCA INVENTORY STATUS:** The components of this gas mixture are listed on the TSCA Inventory.

**U.S. CERCLA REPORTABLE QUANTITY (RQ):** Hexane = 5000 lb (2270 kg); Hydrogen Sulfide = 100 lbs (45.4 lb)

**OTHER U.S. FEDERAL REGULATIONS:**

- Hydrogen Sulfide, Carbon Monoxide, Propane, n-Pentane and n-Hexane are subject to the reporting requirements of CFR 29 1910.1000.
- Hydrogen Sulfide, Propane and n-Pentane are subject to the reporting requirements of Section 112(r) of the Clean Air Act. The Threshold Quantity for each of these gases is 10,000 pounds and so this mixture will not be affected by the regulation.
- Depending on specific operations involving the use of this gas mixture, the regulations of the Process Safety Management of Highly Hazardous Chemicals may be applicable (29 CFR 1910.119). Hydrogen Sulfide is listed in Appendix A of this regulation. The Threshold Quantity for Hydrogen Sulfide under this regulation is 1500 lbs.
- This gas mixture does not contain any Class I or Class II ozone depleting chemicals (40 CFR part 82).
- Nitrogen, Oxygen and n-Hexane are not listed Regulated Substances, per 40 CFR, Part 68, of the Risk Management for Chemical Releases. Hydrogen Sulfide is listed under this regulation in Table 1 as a Regulated Substance (Toxic Substance), in quantities of 10,000 lbs (4,553 kg) or greater. Carbon Monoxide, Propane and n-Pentane are listed under this regulation in Table 3, as Regulated Substances (Flammable), in quantities of 10,000 lbs (4,553 kg) or greater, and so this mixture will not be affected by the regulation.

**U.S. STATE REGULATORY INFORMATION:** The components of this gas mixture are covered under the following specific State regulations:

**Alaska - Designated Toxic and Hazardous Substances:** Carbon Monoxide, Propane, n-Pentane, n-Hexane, Hydrogen Sulfide.

**California - Permissible Exposure Limits for Chemical Contaminants:** Carbon Monoxide, Nitrogen, Propane, n-Pentane, n-Hexane, Hydrogen Sulfide.

**Florida - Substance List:** Oxygen, Carbon Monoxide, n-Pentane, n-Hexane, Hydrogen Sulfide.

**Illinois - Toxic Substance List:** Carbon Monoxide, Propane, n-Pentane, n-Hexane, Hydrogen Sulfide.

**Kansas - Section 302/313 List:** No.

**Massachusetts - Substance List:** Oxygen, Carbon Monoxide, Propane, n-Pentane, n-Hexane, Hydrogen Sulfide.

**Michigan - Critical Materials Register:** No.

**Minnesota - List of Hazardous Substances:** Carbon Monoxide, Propane, n-Pentane, n-Hexane, Hydrogen Sulfide.

**Missouri - Employer Information/Toxic Substance List t:** n-Pentane, n-Hexane, Propane, Hydrogen Sulfide.

**New Jersey - Right to Know Hazardous Substance List:** Oxygen, Carbon Monoxide, Nitrogen, Propane, n-Pentane, n-Hexane.

**North Dakota - List of Hazardous Chemicals, Reportable Quantities:** Hydrogen Sulfide.

**Pennsylvania - Hazardous Substance List:** Oxygen, Carbon Monoxide, Nitrogen, Propane, n-Pentane, n-Hexane, Hydrogen Sulfide.

**Rhode Island - Hazardous Substance List:** Oxygen, Carbon Monoxide, Nitrogen, Propane, n-Pentane, n-Hexane, Hydrogen Sulfide.

**Texas - Hazardous Substance List:** n-Pentane, n-Hexane, Propane, Hydrogen Sulfide.

**West Virginia - Hazardous Substance List:** n-Pentane, n-Hexane, Propane, Hydrogen Sulfide.

**Wisconsin - Toxic and Hazardous Substances:** n-Pentane, n-Hexane, Propane, Hydrogen Sulfide

**CALIFORNIA SAFE DRINKING WATER AND TOXIC ENFORCEMENT ACT (PROPOSITION 65):** The Carbon Monoxide component of this gas mixture is on the California Proposition 65 lists as a chemical known to the State of California to cause birth defects or other reproductive harm.

**ADDITIONAL CANADIAN REGULATIONS:**

**CANADIAN DSL/NDL INVENTORY STATUS:** The components of this gas mixture are on the Canadian DSL Inventory.

**CANADIAN ENVIRONMENTAL PROTECTION ACT (CEPA) PRIORITIES SUBSTANCES LISTS:** The components of this gas mixture are not on the CEPA Priorities Substances List.

**CANADIAN WHMIS CLASSIFICATION:** This gas mixture is categorized as a Controlled Product, Hazard Classes A and D2A, as per the Controlled Product Regulations.

## 16. OTHER INFORMATION

### INFORMATION ABOUT DOT-39 NRC (Non-Refillable Cylinder) PRODUCTS

DOT 39 cylinders ship as hazardous materials when full. Once the cylinders are relieved of pressure (empty) they are not considered hazardous material or waste. Residual gas in this type of cylinder is not an issue because toxic gas mixtures are prohibited. Calibration gas mixtures typically packaged in these cylinders are Nonflammable n.o.s., UN 1956. A small percentage of calibration gases packaged in DOT 39 cylinders are flammable or oxidizing gas mixtures.

For disposal of used DOT-39 cylinders, it is acceptable to place them in a landfill if local laws permit. Their disposal is no different than that employed with other DOT containers such as spray paint cans, household aerosols, or disposable cylinders of propane (for camping, torch etc.). When feasible, we recommended recycling for scrap metal content. CALGAZ will do this for any customer that wishes to return cylinders to us prepaid. All that is required is a phone call to make arrangements so we may anticipate arrival. Scrapping cylinders involves some preparation before the metal dealer may accept them. We perform this operation as a service to valued customers who want to participate.

**MIXTURES:** When two or more gases or liquefied gases are mixed, their hazardous properties may combine to create additional, unexpected hazards. Obtain and evaluate the safety information for each component before you produce the mixture. Consult an Industrial Hygienist or other trained person when you make your safety evaluation of the end product. Remember, gases and liquids have properties which can cause serious injury or death.

Further information about the handling of compressed gases can be found in the following pamphlets published by: Compressed Gas Association Inc. (CGA), 1725 Jefferson Davis Highway, Suite 1004, Arlington, VA 22202-4102. Telephone: (703) 412-0900.

P-1 "Safe Handling of Compressed Gases in Containers"  
AV-1 "Safe Handling and Storage of Compressed Gases"  
"Handbook of Compressed Gases"

**PREPARED BY:** CHEMICAL SAFETY ASSOCIATES, Inc.  
PO Box 3519, La Mesa, CA 91944-3519  
619/670-0609

Fax on Demand: 1-800/231-1366



This Material Safety Data Sheet is offered pursuant to OSHA's Hazard Communication Standard, 29 CFR, 1910.1200. Other government regulations must be reviewed for applicability to this gas mixture. To the best of CALGAZ knowledge, the information contained herein is reliable and accurate as of this date; however, accuracy, suitability or completeness are not guaranteed and no warranties of any type, either express or implied, are provided. The information contained herein relates only to this specific product. If this gas mixture is combined with other materials, all component properties must be considered. Data may be changed from time to time. Be sure to consult the latest edition.

## SAFETY DATA SHEET

Version 4.20  
Revision Date 11/07/2017  
Print Date 10/06/2018

---

**1. PRODUCT AND COMPANY IDENTIFICATION****1.1 Product identifiers**

Product name : Trizma® base

Product Number : T1503

Brand : Sigma

CAS-No. : 77-86-1

**1.2 Relevant identified uses of the substance or mixture and uses advised against**

Identified uses : Laboratory chemicals, Synthesis of substances

**1.3 Details of the supplier of the safety data sheet**

Company : Sigma-Aldrich  
3050 Spruce Street  
SAINT LOUIS MO 63103  
USA

Telephone : +1 800-325-5832

Fax : +1 800-325-5052

**1.4 Emergency telephone number**

Emergency Phone # : +1-703-527-3887 (CHEMTREC)

---

**2. HAZARDS IDENTIFICATION****2.1 Classification of the substance or mixture**

Not a hazardous substance or mixture.

**2.2 GHS Label elements, including precautionary statements**

Not a hazardous substance or mixture.

**2.3 Hazards not otherwise classified (HNOC) or not covered by GHS**

This substance is not considered to be persistent, bioaccumulating and toxic (PBT).

---

**3. COMPOSITION/INFORMATION ON INGREDIENTS****3.1 Substances**

Synonyms : 2-Amino-2-(hydroxymethyl)-1,3-propanediol  
THAM  
Trometamol  
Tris base  
Tris(hydroxymethyl)aminomethane

Formula : C<sub>4</sub>H<sub>11</sub>NO<sub>3</sub>

Molecular weight : 121.14 g/mol

CAS-No. : 77-86-1

EC-No. : 201-064-4

Registration number : 01-2119957659-16-XXXX

No components need to be disclosed according to the applicable regulations.

---

## 4. FIRST AID MEASURES

### 4.1 Description of first aid measures

#### **If inhaled**

If breathed in, move person into fresh air. If not breathing, give artificial respiration.

#### **In case of skin contact**

Wash off with soap and plenty of water.

#### **In case of eye contact**

Flush eyes with water as a precaution.

#### **If swallowed**

Never give anything by mouth to an unconscious person. Rinse mouth with water.

### 4.2 Most important symptoms and effects, both acute and delayed

The most important known symptoms and effects are described in the labelling (see section 2.2) and/or in section 11

### 4.3 Indication of any immediate medical attention and special treatment needed

No data available

---

## 5. FIREFIGHTING MEASURES

### 5.1 Extinguishing media

#### **Suitable extinguishing media**

Use water spray, alcohol-resistant foam, dry chemical or carbon dioxide.

### 5.2 Special hazards arising from the substance or mixture

No data available

### 5.3 Advice for firefighters

Wear self-contained breathing apparatus for firefighting if necessary.

### 5.4 Further information

No data available

---

## 6. ACCIDENTAL RELEASE MEASURES

### 6.1 Personal precautions, protective equipment and emergency procedures

Avoid dust formation. Avoid breathing vapours, mist or gas.

For personal protection see section 8.

### 6.2 Environmental precautions

No special environmental precautions required.

### 6.3 Methods and materials for containment and cleaning up

Sweep up and shovel. Keep in suitable, closed containers for disposal.

### 6.4 Reference to other sections

For disposal see section 13.

---

## 7. HANDLING AND STORAGE

### 7.1 Precautions for safe handling

Further processing of solid materials may result in the formation of combustible dusts. The potential for combustible dust formation should be taken into consideration before additional processing occurs.

Provide appropriate exhaust ventilation at places where dust is formed.

For precautions see section 2.2.

### 7.2 Conditions for safe storage, including any incompatibilities

Keep container tightly closed in a dry and well-ventilated place.

Hygroscopic. Store under inert gas.

Storage class (TRGS 510): 13: Non Combustible Solids

### 7.3 Specific end use(s)

Apart from the uses mentioned in section 1.2 no other specific uses are stipulated

---

## 8. EXPOSURE CONTROLS/PERSONAL PROTECTION

### 8.1 Control parameters

#### Components with workplace control parameters

Contains no substances with occupational exposure limit values.

### 8.2 Exposure controls

#### Appropriate engineering controls

General industrial hygiene practice.

#### Personal protective equipment

##### Eye/face protection

Use equipment for eye protection tested and approved under appropriate government standards such as NIOSH (US) or EN 166(EU).

##### Skin protection

Handle with gloves. Gloves must be inspected prior to use. Use proper glove removal technique (without touching glove's outer surface) to avoid skin contact with this product. Dispose of contaminated gloves after use in accordance with applicable laws and good laboratory practices. Wash and dry hands.

##### Full contact

Material: Nitrile rubber

Minimum layer thickness: 0.11 mm

Break through time: 480 min

Material tested: Dermatril® (KCL 740 / Aldrich Z677272, Size M)

##### Splash contact

Material: Nitrile rubber

Minimum layer thickness: 0.11 mm

Break through time: 480 min

Material tested: Dermatril® (KCL 740 / Aldrich Z677272, Size M)

data source: KCL GmbH, D-36124 Eichenzell, phone +49 (0)6659 87300, e-mail sales@kcl.de, test method: EN374

If used in solution, or mixed with other substances, and under conditions which differ from EN 374, contact the supplier of the CE approved gloves. This recommendation is advisory only and must be evaluated by an industrial hygienist and safety officer familiar with the specific situation of anticipated use by our customers. It should not be construed as offering an approval for any specific use scenario.

##### Body Protection

Choose body protection in relation to its type, to the concentration and amount of dangerous substances, and to the specific work-place., The type of protective equipment must be selected according to the concentration and amount of the dangerous substance at the specific workplace.

##### Respiratory protection

Respiratory protection is not required. Where protection from nuisance levels of dusts are desired, use type N95 (US) or type P1 (EN 143) dust masks. Use respirators and components tested and approved under appropriate government standards such as NIOSH (US) or CEN (EU).

##### Control of environmental exposure

No special environmental precautions required.

---

## 9. PHYSICAL AND CHEMICAL PROPERTIES

### 9.1 Information on basic physical and chemical properties

- |                    |  |
|--------------------|--|
| a) Appearance      | Form: crystalline<br>Colour: colourlesswhite |
| b) Odour           | No data available                            |
| c) Odour Threshold | No data available                            |
| d) pH              | 10.5 - 12                                    |

e) Melting point/freezing point	Melting point/range: 168 °C (334 °F)
f) Initial boiling point and boiling range	288 °C (550 °F) at 1,013 hPa (760 mmHg) - Decomposes below the boiling point.
g) Flash point	No data available
h) Evaporation rate	No data available
i) Flammability (solid, gas)	Does not sustain combustion.
j) Upper/lower flammability or explosive limits	No data available
k) Vapour pressure	No data available
l) Vapour density	No data available
m) Relative density	No data available
n) Water solubility	678 g/l at 20 °C (68 °F)
o) Partition coefficient: n-octanol/water	log Pow: -2.31 at 20 °C (68 °F)
p) Auto-ignition temperature	The substance or mixture is not classified as self heating.
q) Decomposition temperature	No data available
r) Viscosity	Not applicable
s) Explosive properties	Not explosive
t) Oxidizing properties	The substance or mixture is not classified as oxidizing.

## 9.2 Other safety information

Bulk density	800 kg/m <sup>3</sup>
Dissociation constant	8.22 at 25 °C (77 °F)

---

## 10. STABILITY AND REACTIVITY

### 10.1 Reactivity

No data available

### 10.2 Chemical stability

Stable under recommended storage conditions.

### 10.3 Possibility of hazardous reactions

No data available

### 10.4 Conditions to avoid

hygroscopic

### 10.5 Incompatible materials

Strong oxidizing agents

### 10.6 Hazardous decomposition products

Hazardous decomposition products formed under fire conditions. - Carbon oxides, Nitrogen oxides (NO<sub>x</sub>)

Other decomposition products - No data available

In the event of fire: see section 5

---

## 11. TOXICOLOGICAL INFORMATION

### 11.1 Information on toxicological effects

#### Acute toxicity

LD<sub>50</sub> Oral - Rat - > 5,000 mg/kg  
(OECD Test Guideline 425)

Inhalation: No data available

LD50 Dermal - Rat - > 5,000 mg/kg  
(OECD Test Guideline 402)

No data available

**Skin corrosion/irritation**

Skin - Rabbit

Result: No skin irritation  
(OECD Test Guideline 404)

**Serious eye damage/eye irritation**

Eyes - Rabbit

Result: No eye irritation  
(OECD Test Guideline 405)

**Respiratory or skin sensitisation**

Buehler Test - Guinea pig

Does not cause skin sensitisation.  
(OECD Test Guideline 406)

**Germ cell mutagenicity**

Result: Not mutagenic in Ames Test

in vitro assay

Result: negative

In vitro tests did not show mutagenic effects

Result: In vivo tests did not show any chromosomal changes.

**Carcinogenicity**

IARC: No component of this product present at levels greater than or equal to 0.1% is identified as probable, possible or confirmed human carcinogen by IARC.

NTP: No component of this product present at levels greater than or equal to 0.1% is identified as a known or anticipated carcinogen by NTP.

OSHA: No component of this product present at levels greater than or equal to 0.1% is identified as a carcinogen or potential carcinogen by OSHA.

**Reproductive toxicity**

No data available

No data available

**Specific target organ toxicity - single exposure**

No data available

**Specific target organ toxicity - repeated exposure**

No data available

**Aspiration hazard**

No data available

**Additional Information**

Repeated dose toxicity      Rat - Oral - Subacute toxicity - NOAEL : 1,000 mg/kg

RTECS: TY2900000

To the best of our knowledge, the chemical, physical, and toxicological properties have not been thoroughly investigated.

---

**12. ECOLOGICAL INFORMATION**

**12.1 Toxicity**

Toxicity to daphnia and other aquatic      EC50 - Daphnia (water flea) - > 980 mg/l - 48 h

invertebrates

Toxicity to algae EC50 - Algae - 397 mg/l - 72 h

NOEC - Algae - 100 mg/l - 72 h

## 12.2 Persistence and degradability

Biodegradability Result: - Readily biodegradable.  
(OECD Test Guideline 301F)

## 12.3 Bioaccumulative potential

No bioaccumulation is to be expected (log Pow <= 4).

## 12.4 Mobility in soil

No data available

## 12.5 Results of PBT and vPvB assessment

This substance is not considered to be persistent, bioaccumulating and toxic (PBT).

## 12.6 Other adverse effects

No data available

---

## 13. DISPOSAL CONSIDERATIONS

### 13.1 Waste treatment methods

#### Product

Offer surplus and non-recyclable solutions to a licensed disposal company.

#### Contaminated packaging

Dispose of as unused product.

---

## 14. TRANSPORT INFORMATION

### DOT (US)

Not dangerous goods

### IMDG

Not dangerous goods

### IATA

Not dangerous goods

---

## 15. REGULATORY INFORMATION

### SARA 302 Components

No chemicals in this material are subject to the reporting requirements of SARA Title III, Section 302.

### SARA 313 Components

This material does not contain any chemical components with known CAS numbers that exceed the threshold (De Minimis) reporting levels established by SARA Title III, Section 313.

### SARA 311/312 Hazards

No SARA Hazards

### Massachusetts Right To Know Components

No components are subject to the Massachusetts Right to Know Act.

### Pennsylvania Right To Know Components

Tris (hydroxymethyl) aminomethane

CAS-No.  
77-86-1

Revision Date

Tris (hydroxymethyl) aminomethane

CAS-No.  
77-86-1

Revision Date

### New Jersey Right To Know Components

CAS-No.

Revision Date



**California Prop. 65 Components**

This product does not contain any chemicals known to State of California to cause cancer, birth defects, or any other reproductive harm.

---

**16. OTHER INFORMATION**

**HMIS Rating**

Health hazard: 0  
Chronic Health Hazard:  
Flammability: 0  
Physical Hazard 0

**NFPA Rating**

Health hazard: 0  
Fire Hazard: 0  
Reactivity Hazard: 0

**Further information**

Copyright 2016 Sigma-Aldrich Co. LLC. License granted to make unlimited paper copies for internal use only. The above information is believed to be correct but does not purport to be all inclusive and shall be used only as a guide. The information in this document is based on the present state of our knowledge and is applicable to the product with regard to appropriate safety precautions. It does not represent any guarantee of the properties of the product. Sigma-Aldrich Corporation and its Affiliates shall not be held liable for any damage resulting from handling or from contact with the above product. See [www.sigma-aldrich.com](http://www.sigma-aldrich.com) and/or the reverse side of invoice or packing slip for additional terms and conditions of sale.

**Preparation Information**

Sigma-Aldrich Corporation  
Product Safety – Americas Region  
1-800-521-8956

Version: 4.20

Revision Date: 11/07/2017

Print Date: 10/06/2018

Personal Protective Equipment (PPE) Management Program

## PERSONAL PROTECTIVE EQUIPMENT MANAGEMENT PROGRAM

**CORPORATE HEALTH AND SAFETY MANAGER** : **Brian Hobbs, CIH, CSP**  
**EFFECTIVE DATE** : **01/19**  
**REVISION NUMBER** : **4**

**TABLE OF CONTENTS**

1. PURPOSE.....	1
2. SCOPE AND APPLICABILITY.....	1
3. PROCEDURES.....	1
3.1 Introduction.....	1
3.2 Types of PPE.....	1
3.3 Protective Clothing Selection Criteria.....	2
3.3.1 Chemicals Present.....	2
3.3.2 Concentration of the Chemical(s).....	2
3.3.3 Physical State.....	3
3.3.4 Length of Exposure.....	3
3.3.5 Abrasion.....	3
3.3.6 Dexterity.....	3
3.3.7 Ability to Decontaminate.....	3
3.3.8 Climactic Conditions.....	3
3.3.9 Work Load.....	4
3.4 Types of Protective Materials.....	4
3.5 Protection Levels.....	4
3.5.1 Level A Protection.....	4
3.5.2 Level B Protection.....	5
3.5.3 Level C Protection.....	6
3.5.4 Level D Protection.....	6
3.5.5 Level E Protection.....	6
3.5.6 Additional Considerations.....	7

## **1. PURPOSE**

Roux Associates, Inc. and its affiliated companies, Roux Environmental Engineering and Geology, D.P.C, and Remedial Engineering (collectively, "Roux") has instituted the following program to establish guidelines for the selection of personal protective equipment (PPE) for use by Roux personnel performing field activities in hazardous environments. PPE is not meant to be a substitute for engineering, work practice, and/or administrative controls, but PPE should be used in conjunction with these controls to protect the employees in the work place. Clothing, body coverings, and other accessories designed to prevent worker exposure to workplace hazards are all types of PPE. To ensure adequate PPE employee-owned PPE is evaluated on a case-by-case basis to insure its adequacy, maintenance and sanitation.

## **2. SCOPE AND APPLICABILITY**

These guidelines apply to all PPE selection decisions to be made in implementing the Roux program. The foundations for this program are the numerous Occupational Health and Safety Administration (OSHA) standards related to PPE cited in 29 CFR 1910 Subpart I, 29 CFR 1926 Subpart E, and the hazardous environment work employee protection requirements under the OSHA Hazardous Waste Operations and Emergency Response (HAZWOPER) standard at 29 CFR 1910.120 and 1926.65. To ensure hazard assessments are documented the levels of protection, types of protection and tasks requiring protection are covered in site-specific Health and Safety Plans (HASPs) and Job Safety Analyses (JSAs).

## **3. PROCEDURES**

Due to the varied nature of site activities and the different potential hazards associated with different sites, several aspects must be considered when selecting PPE. The following text describes PPE selection logic and provides guidelines and requirements for the appropriate selection and use of PPE.

### **3.1 Introduction**

To harm the body, chemicals must first gain entrance. The intact skin and the respiratory tract are usually the first body tissues attacked by chemical contaminants. These tissues provide barriers to some chemicals but in many cases, are damaged themselves or are highly permeable by certain chemical compounds. Personal protective equipment therefore is used to minimize or eliminate chemical compounds coming into contact with these first barrier tissues.

The proper selection of equipment is important in preventing exposures. The PM making the selection will have to take several factors into consideration. The level of protection, type and kind of equipment selected depends on the hazardous conditions and in some cases cost, availability, compatibility with other equipment, and performance. An accurate assessment of all these factors must be made before work can be safely carried out.

### **3.2 Types of PPE**

The type and selection of PPE must meet certain general criteria and requirements as required under OSHA 29 CFR 1910.132 and 1926.95. In addition to these general requirements, specific requirements and specifications exist for some types of PPE that form the basis of the protective clothing scheme. Following is a list of the common types of specific PPE and the specific requirements for the PPE type, where applicable:

1. Hard Hats - Regulated by 29 CFR 1910.135 and 1926.100; and, specified in ANSI Z89.1.

2. Face Shields and Safety Glasses - Regulated by 29 CFR 1910.133 and 1926.102; and, specified in ANSI Z87.1.
3. Respiratory Protection - Regulated by 29 CFR 1910.134 and 1926.103.
4. Hand Protection - Not specifically regulated.
5. Foot Protection - Regulated by 29 CFR 1910.136 and 1926.96; and, specified in ANSI Z41.1.
6. Protective Clothing (e.g., fully encapsulated suits, aprons) - Not specifically regulated.

### **3.3 Protective Clothing Selection Criteria**

#### **3.3.1 Chemicals Present**

The most important factor in selecting PPE is the determination of what chemicals the employee may be exposed to. On field investigations, the number of chemicals may range from a few to several hundred. The exact chemicals or group of chemicals present at the site (certain groups tend to require similar protection) can be determined by collecting and analyzing samples of the air, soil, water, or other site media. When data are lacking, research into the materials used or stored at the site can be used to infer chemicals possibly on the site.

Once the known or suspected chemicals have been identified, and taking into consideration the type of work to be performed, the most appropriate clothing shall be selected.

Protective garments are made of several different substances for protection against specific chemicals. There is no universal protective material. All will decompose, be permeated by, or otherwise fail to protect under given circumstances. Fortunately, most manufacturers make guides to the use of their products (i.e., Dupont's Tyvek™ Permeation Guide). These guides are usually for gloves and coveralls and typically provide information regarding chemical degradation rates (failure of the material to maintain structural integrity when in contact with the chemical), and may provide information on the permeation rate (whether or not the material allows the chemical to pass through). When permeation tables are available, they shall be used in conjunction with degradation tables to determine the most appropriate protective material.

During most site work, chemicals are usually in mixed combinations and the protective materials are not in continuous contact with pure chemicals for long periods of time; therefore, the selected material may be adequate for the particular chemical and type of work being performed, yet not the "best" protecting material for all site chemicals and activities. Selection shall depend upon the most hazardous chemicals based on their hazards and concentrations. Sometimes layering, using several different layers of protective materials, affords the best protection.

#### **3.3.2 Concentration of the Chemical(s)**

One of the major criteria for selecting protective material is the concentration of the chemical(s) in air, liquid, and/or solid state. Airborne and liquid chemical concentrations should be compared to the OSHA standards and/or American Conference of Governmental Industrial Hygienists (ACGIH) and National Institute for Occupational Safety and Health (NIOSH) guidelines to determine the level of skin or other absorptive surface (e.g., eyes) protection needed. While these standards are not designed specifically for skin exposed directly to the liquid, they may provide skin designations indicative of chemicals known to have significant skin or dermal absorption effects. For example, airborne levels of PCB on-site may be

low because it is not very volatile, so the inhalation hazard may be minimal; however, PCB-containing liquid coming in direct contact with the skin may cause overexposure. Thus, PCB has been assigned a skin designation in both the OSHA and ACGIH exposure limit tables.

### **3.3.3 Physical State**

The characteristics of a chemical may range from nontoxic to extremely toxic depending on its physical state. Inorganic lead in soil would not be considered toxic to site personnel, unless it became airborne, since it is generally not absorbed through the intact skin. Organic lead in a liquid could be readily absorbed. Soil is frequently contaminated with hazardous materials. Concentrations will vary from a few parts per million to nearly one hundred percent. The degree of hazard is dependent on the type of soil and concentration of the chemical. Generally speaking, "dry" soils do not cause a hazard to site personnel if they take minimal precautions such as wearing some type of lightweight gloves.

### **3.3.4 Length of Exposure**

The length of time a material is exposed to a chemical increases the probability of breakthrough. Determinations of actual breakthrough times for short-term exposures indicate that several different materials can be used which would be considered inadequate under long-term exposures. It should be kept in mind that during testing, a pure (100% composition) liquid is usually placed in direct contact with the material producing a worst-case situation.

### **3.3.5 Abrasion**

When selecting protective clothing, the job the employee is engaged in must be taken into consideration. Persons moving drums or performing other manual tasks may require added protection for their hands, lower chest and thighs. The use of leather gloves and a heavy apron over the other normal protective clothing will help prevent damage to the normal PPE and thus reduce worker exposures.

### **3.3.6 Dexterity**

Although protection from skin and inhalation hazards is the primary concern when selecting PPE, the ability to perform the assigned task must be maintained. For example, personnel cannot be expected to perform work that requires fine dexterity if they must wear a thick glove. Therefore, the PPE selection process must consider the task being performed and provide PPE alternatives or techniques that allow dexterity to be maintained while still protecting the worker (e.g., wearing tight latex gloves over more bulky hand protection to increase dexterity).

### **3.3.7 Ability to Decontaminate**

If disposable clothing cannot be used, the ability to decontaminate the materials selected must be taken into consideration. Once a chemical contacts the material, it must be cleaned before it can be reused. If the chemical has completely permeated the material, it is unlikely that the clothing can be adequately decontaminated and the material should be discarded.

### **3.3.8 Climactic Conditions**

The human body works best with few restraints from clothing. Protective clothing adds a burden by adding weight and restricting movement as well as preventing the natural cooling process. In severe situations, a modified work program must be used.

Some materials act differently when they are very hot and very cold. For example, PVC becomes almost brittle in very cold temperatures. If there are any questions about the stability of the protective materials under different conditions, the manufacturer should be contacted.

### **3.3.9 Work Load**

Like climactic conditions, the type of work activity may affect work duration and the ability of personnel to perform certain tasks. Similarly, the amount of protective materials a person wears will affect their ability to perform certain tasks. For example, a person in a total encapsulating suit, even at 72 °F, cannot work for more than a short period of time without requiring a break.

The work schedule should be adjusted to maintain the health of the employees. Special consideration should be given to the selection of clothing that both protects and adds the least burden when personnel are required to perform strenuous tasks. Excessive bodily stress frequently represents the most significant hazard encountered during field work.

## **3.4 Types of Protective Materials**

1. Cellulose or Paper
2. Natural and Synthetic Fibers
  - a. Tyvek™
  - b. Nomex™
3. Elastomers
  - a. Polyethylene
  - b. Saran
  - c. Polyvinyl Chloride (PVC)
  - d. Neoprene
  - e. Butyl Rubber
  - f. Viton

## **3.5 Protection Levels**

### **3.5.1 Level A Protection**

Level A protection (a fully encapsulated suit) is used when skin hazards exist or when there is no known data that positively rule out skin and other absorption hazards. Since Level A protection is extremely physiologically and psychologically stressful, the decision to use this protection must be carefully considered. At no time will Level A work be performed without the consent of the OM. The following conditions suggest a need for Level A protection:

- confined facilities where probability of skin contact is high;
- sites containing known skin hazards;
- sites with no established history to rule out skin and other absorption hazards;
- atmosphere immediately dangerous to life and health (IDLH) through the skin absorption route;
- site exhibiting signs of acute mammalian toxicity (e.g., dead animals, illnesses associated with past entry into site by humans);



- sites at which sealed drums of unknown materials must be opened;
- total atmospheric readings on the Photoionization Detector (PID), Flame Ionization Detector (FID), and similar instruments indicate 500 to 1,000 ppm of unidentified substances; and
- extremely hazardous substances (e.g., cyanide compounds, concentrated pesticides, Department of Transportation Poison "A" materials, suspected carcinogens and infectious substances) are known or suspected to be present and skin contact is possible.

The following items constitute Level A protection:

- open circuit, pressure-demand self-contained breathing apparatus (SCBA);
- totally encapsulated suit;
- gloves, inner (surgical type);
- gloves, outer;
- chemical protective;
- boots, chemical protective, steel toe and shank;
- radiation detector (if applicable); and
- communications.

### **3.5.2 Level B Protection**

Level B protection is utilized when the highest level of respiratory protection is needed but hazardous material exposure to the few unprotected areas of the body is unlikely.

The following conditions suggest a need for Level B protection:

- the type and atmospheric concentration of toxic substances have been identified and they require the highest level of respiratory protection;
- IDLH atmospheres where the substance or concentration in the air does not present a severe skin hazard;
- the type and concentrations of toxic substances do not meet the selection criteria permitting the use of air purifying respirators; and
- it is highly unlikely that the work being done will generate high concentrations of vapors, gases or particulates, or splashes of materials that will affect the skin of personnel.

Personal protective equipment for Level B includes:

- open circuit, pressure-demand SCBA;
- chemical protective clothing:
- overalls and long-sleeve jacket; or
- coveralls;
- gloves, inner (surgical type); gloves, outer, chemical protective;
- boots, chemical protective, steel toe and shank; and
- communications optional.

### **3.5.3 Level C Protection**

Level C protection is utilized when both skin and respiratory hazards are well defined and the criteria for the use of negative pressure respirators have been fulfilled (i.e., known contaminants and contaminant concentrations, acceptable oxygen levels, approved filter/cartridge available, known cartridge service life, etc.). Level C protection may require carrying an emergency escape respirator during certain initial entry and site reconnaissance situations, or when applicable thereafter.

Personal protective equipment for Level C typically includes:

- full facepiece air-purifying respirator;
- emergency escape respirator (optional);
- chemical protective clothing:
  - overalls and long-sleeved jacket; or
  - coveralls;
- gloves, inner (surgical type);
- gloves, outer, chemical protective; and
- boots, chemical protective, steel toe and shank.

### **3.5.4 Level D Protection**

Level D is the basic work uniform. Personal protective equipment for Level D includes:

- coveralls;
- safety boots/shoes;
- eye protection;
- hand protection;
- reflective traffic safety vest (mandatory for traffic areas or railyard);
- hard hat (with face shield is optional); and
- emergency escape respirator is optional.

### **3.5.5 Level E Protection**

Level E protection is used when radioactivity above 10 mr/hr is detected at the site. Personal protective equipment for Level E includes:

- coveralls;
- air purifying respirator;
- time limits on exposure;
- appropriate dermal protection for the type of radiation present; and
- radiation dosage monitoring.

### 3.5.6 Additional Considerations

Field work will contain a variety of situations due to chemicals in various concentrations and combinations. These situations may be partially ameliorated by following the work practices listed below:

1. Some sort of foot protection is needed on a site. If the ground to be worked on is contaminated with liquid and it is necessary to walk in the chemicals, some sort of protective "booties" can be worn over the boots. This cuts down on decontamination requirements. They are designed with soles to help prevent them from slipping around. If non-liquids are to be encountered, a Tyvek™ bootie could be used. If the ground contains any sharp objects, the advantage of booties is questionable. Boots should be worn with either cotton or wool socks to help absorb the perspiration.
2. If the site situation requires the use of hard hats, chin straps should be used if a person will be stooping over where his/her hat may fall off. Respirator straps should not be placed over the hard hats. This will affect the fit of the respirator.

Some types of protective materials conduct heat and cold readily. In cold conditions, natural material clothing should be worn under the protective clothing. Protective clothing should be removed prior to allowing a person "to get warm". Applying heat, such as a space heater, to the outside of the protective clothing may drive the contaminants through. In hot weather, under clothing will absorb sweat. It is recommended that workers use all cotton undergarments.

3. Body protection should be worn and taped to prevent anything from running into the top of the boot. Gloves should be worn and taped to prevent substances from entering the top of the glove. Duct tape is preferred, but masking tape can be used. When aprons are used, they should be taped across the back for added protection. However, this should be done in such a way that the person has mobility.
4. Atmospheric conditions such as precipitation, temperature, wind direction, wind velocity, and pressure determine the behavior of contaminants in air or the potential for volatile material getting into the air. These parameters should be considered in determining the need for and the level of protection.
5. A program must be established for periodic monitoring of the air during site operations. Without an air monitoring program, any changes would go undetected and might jeopardize response personnel. Monitoring can be done with various types of air pumps and filtering devices followed by analysis of the filtration media; personnel dosimeters; and periodic walk-throughs by personnel carrying real-time survey instruments.
6. For operations in the exclusion zone, different levels of protection may be selected, and various types of chemical-resistant clothing may be worn. This selection should be based on the job function, reason for being in the area, and the potential for skin contact with, or inhalation of, the chemicals present.
7. Escape masks must be readily available when levels of respiratory protection do not include a SCBA and the possibility of an IDLH atmosphere exists. Their use can be made on a case-by-case basis. Escape masks could be strategically located at the site in areas that have higher possibilities of vapors, gases or particulates.

**Site-Specific Health and Safety Plan**  
**12 Franklin Street, Brooklyn, New York 11222**

---

**APPENDIX D**

Subsurface Utility Clearance Management Program

**SUBSURFACE UTILITY CLEARANCE MANAGEMENT PROGRAM**

**CORPORATE HEALTH AND SAFETY MANAGER** : **Brian Hobbs, CIH, CSP**  
**EFFECTIVE DATE** : **01/19**  
**REVISION NUMBER** : **2**

**TABLE OF CONTENTS**

1. PURPOSE..... 1

2. SCOPE AND APPLICABILITY..... 1

3. PROCEDURES..... 1

    3.1 Before Intrusive Activities ..... 1

    3.2 During Intrusive Activities ..... 2

    3.3 Stop Work Authority..... 3

**APPENDICES**

- Appendix A – Definitions
- Appendix B – Example of Completed One Call
- Appendix C – Roux Subsurface Utility Clearance Checklist
- Appendix D – Utility Verification/Site Walkthrough Record

## 1. PURPOSE

Roux Associates, Inc. and its affiliated companies, Roux Environmental Engineering and Geology, D.P.C., and Remedial Engineering (collectively, “Roux”) has instituted the following program for completing proper utility mark-outs and for conducting subsurface clearance activities. This establishes a method to ensure, to the greatest extent possible, that utilities have been identified and contact and/or damage to underground utilities and other subsurface structures will be avoided.

## 2. SCOPE AND APPLICABILITY

The Subsurface Utility Clearance Management Program applies to all Roux employees, its contractors and subcontractors. Employees are expected to follow this program for all intrusive work involving Roux or other personnel (e.g., contractors/subcontractors) working for Roux unless the client’s requirements are more stringent. Deviation from the program regardless of the specific work activity or work location must be pre-approved based on client’s site knowledge, site experience and client’s willingness for the use of this program. Any and all exceptions shall be documented and pre-approved by the Project Principal and the Office Manager.

## 3. PROCEDURES

### 3.1 Before Intrusive Activities

During the project kick-off meeting for intrusive activities the PM will review the Roux Subsurface Utility Clearance Checklist and Utility Verification (Appendix C) / Site Walkthrough Record (Appendix D) and the below bullet points with the project field team:

(Please note that these are intended as general reminders only and should not be solely relied upon.)

- Ensure the Mark-out / Stake-out Request Information Sheet (or one-call report) is complete and accurate for the site including address and cross streets and review for missing utilities. (Note: utility mark-out organizations do not have contracts with all utilities and it is often necessary to contact certain utilities separately such as the local water and sewer authorities).
- Have written confirmation prior to mobilizing to the site that the firm or Roux personnel performing the intrusive activity has correctly completed the mark-out notification process including requesting mark-outs, waiting for mark-outs to be applied to ground surfaces at the site, and receiving written confirmation of findings (via fax or email) from utility operators for all known or suspected utilities in the proposed area of intrusive activity, and provided utility owner written confirmation to Roux personnel for review and project files documentation.
- Do not begin any intrusive activity until all utilities mark-out has been completed (i.e., did all utilities mark-out the site?) and any unresolved mark-out issues are finalized. Perform a site walk to review the existing utilities and determine if said utilities have been located by the utility locators.

(Note: The Tolerance Zone is defined as two feet plus half of the diameter or half of the greatest dimension (for elliptical sewers, duct banks and other non-cylindrical utilities) of a utility and two feet from the outside edge of any subsurface structure.)

- Install Pre-Clearance exploratory test holes (e.g., hand-dug test holes or other soft digging techniques) for the first 5-ft below land surface (BLS) at each location prior to conducting mechanized intrusive activities. The size of the pre-clearance exploratory test hole should be at a minimum twice the diameter of any downhole tool or boring device. (Note: Pre-Clearance exploratory test holes should be defined in the SOW/proposal provided to the client to prevent project delays and to allow adequate time for PM and PP to evaluate alternative approaches for the project. Alternative approaches will need to be pre-approved by the OM.

- For excavations, all utilities need to be marked and then exposed by hand following the protocols in this program. Pre-clearing for excavations may be performed by the “moat” technique (i.e., soft digging around the perimeter). In these cases, dig in small lifts (<12” for first 5 feet) using a dedicated spotter.) For Tolerance Zone work, unless otherwise agreed upon with the Utility Operator, work within the tolerance zone requires verification by means of hand-dug test holes performed to expose the utility. Once structures have been verified a minimum clearance of two feet must be maintained between the utility and any powered equipment.
- In addition, the following activities should be conducted:
  - Review the work scope to be performed with the site owner/tenant to determine if it may impact any utilities;
  - Attempt to procure any utility maps or historic drawings of subsurface conditions of the site;
  - **Determine the need for utility owner companies to be contacted or to have their representatives on site;**
  - Where mark-outs terminate at the property boundary, consider the use of private utility locating / GPR / geophysical-type services which may be helpful in locating utilities. Use of private utility locating firms, however, does not eliminate the legal requirement for the Excavator firm to submit a request for Public Utility Mark-outs. Also, the information provided by the service may be inaccurate and unable to locate subsurface utilities and structures in urban areas, landfills, urban fill areas and below reinforced slabs, etc. They should not be relied upon as the only means of performing utility clearance;
  - Documented description of the dig site which is included in the projects Health and Safety Plan (HASP) and one call report will be maintained in the field and distributed amongst Roux personnel its contractors and subcontractors; and
  - Documentation of the actual placement of mark outs in the field shall be collected using dated pictures, videos and/or sketches with distance from markings to fixed objects. All documentation shall be maintained within the project file.

### **3.2 During Intrusive Activities**

The PM, field team lead or personnel performing oversight is to:

- Ensure the mark-out remains valid. (In certain states there are limits regarding the duration of time after the mark-out was applied to the ground surface work can be started or interrupted.) Additionally, the mark-outs must be maintained, documented, and in many cases refreshed periodically to be considered valid, this will be accomplished through calls to the one call center.
- Ensure intrusive activities are only performed within the safe boundaries of the mark-out as detailed in the One-Call Report.
- Halt all work if intrusive activities have resulted in discovery of an unmarked utility. Roux personnel shall notify the facility owner/operator and the one call center. All incidents such as this will be reported as per Roux Incident Investigation and Reporting Management Program.
- Halt all work if intrusive activities must take place outside of the safe boundaries of a mark-out and only proceed after new mark-outs are performed.
- Halt the intrusive activities and immediately consult with the PP if an unmarked utility is encountered.
- Completing any subsurface utility clearance incident reports that are necessary.



- If a utility cannot be found as marked Roux personnel shall notify the facility owner/operator directly or through the one call center. Following notification, the excavation may continue, unless otherwise specified in state law.
- Contractors/subcontractors must contact the one-call center to refresh the ticket when the excavation continues past the life of the ticket. Ticket life shall be dictated by state law however at a maximum ticket life shall not exceed 20 working days.

### **3.3 Stop Work Authority**

Each Roux employee has Stop Work Authority which he or she will execute upon determination of any imminent safety hazard, emergency situation, or other potentially dangerous situation, such as hazardous weather conditions. This Stop Work Authority includes subsurface clearance issues such as the adequacy of a mark-out or identification during intrusive operations of an unexpected underground utility. Authorization to proceed with work will be issued by the PM/PP after such action is reviewed and resolved. The PM will initiate and execute all management notifications and contact with emergency facilities and personnel when this action is appropriate.

**Appendix A - Definitions**

<b><i>Intrusive Work Activities</i></b>	All activities such as digging or scraping the surface, including but not limited to, excavation, test pitting or trenching, soil vapor sampling or the installation of soil borings, soil vapor monitoring points and wells, or monitoring wells, and drilling within the basement slab of a recently demolished building.
<b><i>Mark-out / Stake Out</i></b>	The process of contracting with a competent and qualified company to confirm the presence or absence of underground utilities and structures. This process will clearly mark-out and delineate utilities that are identified so that intrusive work activities can be performed without causing disturbance or damage to the subsurface utilities and structures. After utility mark-outs are completed the soft digging will be completed prior to intrusive work.
<b><i>Tolerance Zone</i></b>	Defined as two feet on either side of the designated centerline of an identified utility, plus half of the diameter or half of the greatest dimension (for elliptical sewers, duct backs and other non-cylindrical utilities) of that utility and two feet from the outside edge of any subsurface structure.
<b><i>Structure</i></b>	For the purpose of this program a structure is defined as any underground feature that may a present potential source(s) of energy such as, but not limited to, utility vaults, bunkers, piping, electrical boxes, wires, conduits, culverts, utility lines, underground tanks and ducts.
<b><i>Soft Digging</i></b>	The safest way to remove material from unknown obstructions or services is by using tools such as a vactor or air knife, non-mechanical tools, or hand tools. The methods are clean and non-evasive and used for uncovering and exposing buried services, excavating and for providing a quick method of soil removal from sensitive areas.
<b><i>Verification</i></b>	Exploratory test-hole dug with hand tools within the Tolerance Zone to expose and verify the location, type, size, direction-of-run and depth of a utility or subsurface structure. Vacuum excavation (soft dig) methods can further facilitate exposure of a subsurface utility and accurately provide its location and identification prior to intrusive work approaching the Tolerance Zone.



**Appendix C - Roux Subsurface Utility Clearance Checklist**

**Roux Subsurface Utility Clearance Checklist**

**Date of Revision –  
12/3/14**

**Work site set-up and work execution**

ACTIVITY	Yes	No	N/A	COMMENTS INCLUDING JUSTIFICATION IF RESPONSE IS NO OR NOT APPLICABLE
Daily site safety meeting conducted, SPSAs performed, JSAs reviewed, appropriate work permits obtained.				
HASP is available and reviewed by site workers / visitors.				
Subsurface Utility Clearance Procedure has been reviewed with all site workers.				
Work area secured; traffic control established as needed. Emergency shut-off switch located. Fire extinguishers / other safety equipment available as needed.				
Utility mark-outs (public / private) clear and visible. Provide Excavator's Stake-Out Reference Number / Request Date / Time.				
Tolerance zone work identified.				
Work execution plan reviewed and adhered to (ground disturbance methods, clearance depths, any special utility protection requirements, or any other execution requirements; especially for Tolerance Zone work).				
Verbal endorsement received from Roux PM for any required field deviations to work execution plan.				

**Key reminders for execution:**

The Subsurface Utility Clearance Protocol should be referenced to determine all requirements while executing subsurface work. The bullet points below are intended as general reminders only and should not be solely relied upon.

- Tolerance zone is defined as two feet plus half of the diameter or half of the greatest dimension (for elliptical sewers, duct banks and other non-cylindrical utilities) of a utility and two feet from the outside of any subsurface structure.
- Install Pre-Clearance exploratory test holes (e.g., hand-dug test holes or vacuum excavation) must be performed for the first five feet below land surface (BLS) at each location prior to conducting mechanized intrusive activities. The size of the pre-clearance exploratory test hole should be at a minimum twice the diameter of any downhole tool or boring device. (Note: Pre-clearance exploratory test holes should be defined in the SOW/proposal provided to the client to prevent project delays and to allow adequate time for PM and PP to evaluate alternative approaches for the project. Alternate approaches will need to be pre-approved by the OM.
- For excavations, all utilities need to be marked and then exposed by hand following the protocols in this program. Pre-clearing for excavations may be performed by the "moat" technique (i.e., soft

digging around the perimeter). In these cases, dig in small lifts (<12" for first five feet) using a dedicated spotter.) For Tolerance Zone work, unless otherwise agreed upon with the Utility Operator, work within the tolerance zone requires verification by means of hand-dug test holes to expose the utility. Once structures have been verified a minimum clearance of two feet must be maintained between the utility and any powered equipment.



**Appendix D - Utility Verification/Site Walkthrough Record**

**Employee Name:** \_\_\_\_\_


**Date:** \_\_\_\_\_

**Instructions:** For each utility suspected at the job site, indicate location on the job site, approximate burial depth, and means of detecting the utility. Leave blank if that utility is not believed to be present.

Utility	Description of Utility Location Identified Onsite	Approx. Depth (bls)	Method / Instrumentation used to determine Utility Location	Utility Owner Response (Date/Time)	Mark Out Indicates (Clear / Conflict)
Electrical Lines					
Gas Lines					
Pipelines					
Steam Lines					
Water Lines					
Sanitary and Stormwater Sewer lines					
Pressured Air-Lines					
Tank Vent Lines					
Fiber Optic Lines					
Underground Storage Tanks					
Phone Lines/ Other					

\* bls - below land surface


Site Sketch Showing Utilities:



*Color Code*

ELECTRIC
Gas-oil Steam
Communications CATV
WATER
Reclaimed Water
SEWER
Temp. Survey Markings
Proposed Excavation

Other Comments / Findings:



Completed by: \_\_\_\_\_

Signature: \_\_\_\_\_ Date: \_\_\_\_\_

Heavy Equipment Exclusion Zone Policy



**HEAVY EQUIPMENT EXCLUSION ZONE  
MANAGEMENT PROGRAM**

**CORPORATE HEALTH AND SAFETY MANAGER : Brian Hobbs, CIH, CSP**  
**EFFECTIVE DATE : 01/2019**  
**REVISION NUMBER : 1**

**TABLE OF CONTENTS**

1. PURPOSE..... 2

2. SCOPE AND APPLICABILITY..... 2

3. PROCEDURES..... 2

    3.1 Exceptions..... 3

4. TRAINING..... 3

## 1. PURPOSE

The purpose of the Exclusion Zone Management Program is to establish the minimum clearance distance that must be maintained between workers and heavy equipment while equipment is in operation (i.e., engaged or moving). The intent is to have no personnel or equipment entering the Exclusion Zone while the equipment is in operation or moving to ensure that Roux and Subcontractor employees are not unnecessarily exposed to the hazards of the equipment.

## 2. SCOPE AND APPLICABILITY

This Management Program applies to all Roux Associates, Inc. and its affiliated companies, Roux Environmental Engineering and Geology, D.P.C, and Remedial Engineering (collectively, "Roux") employees and their subcontractors who are performing field work and are potentially exposed to heavy equipment. For the purpose of this program, heavy equipment includes, but is not necessarily limited to: excavation equipment, drill rigs, vacuum trucks, forklifts, lull telehandlers, man lifts, bobcats, delivery trucks, etc.

## 3. PROCEDURES

As specified in the following sections of this Program, an Exclusion Zones must be established and maintained during activities involving the movement/operation of heavy equipment. The Exclusion Zone requirements apply to all personnel on the site but are primarily focused on those personnel who are required to be working in the vicinity of the equipment. The exclusion zone is in effect when heavy equipment is moving or engaged (ex. movement of an arm or bucket of an excavator, rotation of an auger, lifting of a load with a forklift, raising/lowering of a man lift, etc.).

1. The Exclusion Zone must meet the following minimum requirements:

- A minimum distance of 10 feet from all heavy equipment and loads being moved by the equipment;
- Greater than the swing/reach radius of any moving part on the heavy equipment (i.e., for large equipment this may mean an exclusion zone distance larger than 20 feet);
- Greater than the tip-over distance of the heavy equipment; and
- Greater than the radius of blind spots.

The size of the Exclusion Zone will need to be determined on a task-specific basis considering the size of the heavy equipment in use and the task being performed. Prior to all heavy equipment operations, the Exclusion Zone(s) distance must be specifically identified in the Job Safety Analysis (JSA).

2. The spotter (or another individual) should be assigned responsibility for enforcing the Exclusion Zone. The spotter should be positioned immediately outside of the Exclusion Zone within a clear line of sight of the equipment operator. The spotter must signal the operator to stop work if anyone or anything has the potential to enter or compromise the Exclusion Zone. The operator should stop work if the spotter is not within his/her line of sight. If multiple pieces of equipment are being used, each piece of equipment must have its own Exclusion Zone and spotter. For large excavation and demolition projects the spotter should be in constant radio contact (not cell phone) with the machine driver.
3. If an individual must enter the Exclusion Zone, the designated Spotter must signal the Equipment Operator to stop the equipment. Once the equipment is no longer moving (ex. movement of an arm of an excavator is STOPPED, lifting of a load with a forklift STOPPED, raising/lowering of a man lift is

STOPPED, etc.), the operator must DISENGAGE THE CONTROLS and STOP and SIGNAL BY “SHOWING HIS HANDS”. This signal will indicate that it is safe for the personnel to enter the limits of the Exclusion Zone to perform the required activity. The equipment must remain completely stopped/disengaged until all personnel have exited the limits of the Exclusion Zone and the designated Spotter has signaled by “SHOWING HIS HANDS” to the Equipment Operator that it is safe to resume operations.

4. When entering the limits of the Exclusion Zone, personnel must at a minimum:
  - Establish eye contact with the operator and approach the heavy equipment in a manner that is in direct line of sight to the Equipment Operator;
  - Never walk under any suspended loads or raised booms/arms of the heavy equipment; and
  - Identify a travel path that is free of Slip/Trip/Fall hazards.
5. The Exclusion Zone should be delineated using cones with orange snow fence or solid poles between the cones, barrels, tape or other measures. For work in rights-of-way rigid barriers, such as Jersey barriers or temporary chain link fence should be used. For certain types of wide-spread or moving/mobile equipment operations, such delineation may not be practicable around pieces of equipment or individual work areas. In such instances, it is expected that the entire operation will be within a larger secure work area or that additional means will be utilized to ensure security of the work zone.

All subcontractors who provide heavy equipment operations to field projects must implement a program that meets or exceeds the expectations described above as well as any additional requirements that may be required on a client or site-specific basis.

### **3.1 Exceptions**

It is recognized that certain heavy equipment activities may require personnel to work within the limits of the Exclusion Zone as specified in this program. Such activities may include certain excavation clearance tasks, drill crew activities or construction tasks. However, any such activity must be pre-planned with emphasis on limiting the amount and potential exposure of any activity required within the zone. The critical safety steps to mitigate the hazards associated with working within the Exclusion Zone must be defined in the JSA and potentially other project-specific plans (i.e., critical lift plans, etc.), and approved by the Roux Project Principal and client representative, if required, prior to implementation.

## **4. TRAINING**

Many Roux projects have different requirements that are client-specific or site-specific in nature. It is the responsibility of the Project Principal (or Project Manager if delegated this responsibility by the Project Principal) to ensure that the workers assigned to his/her projects are provided orientation and training with respect to these client and/or site-specific requirements.

**Interim Remedial Measures Work Plan Addendum**  
***12 Franklin Street, Brooklyn, New York 11222***

---

**APPENDIX B**

Sub-Slab Depressurization System / Soil Vapor Extraction System  
Operations and Maintenance Forms

## SUB-SLAB DEPRESSURIZATION SYSTEM OPERATIONS AND MAINTENANCE FORM

Site Name: <u>12 Franklin Street</u> Street Address: <u>12 Franklin Street</u> Location: <u>Brooklyn, NY</u> System: <u>Active SSD/SVE System</u> Fans: _____ Fan Range: _____	Inspection Date: _____  Inspection Personnel: _____ _____
---	--

INSPECTION ITEM DESCRIPTION	Yes	No	Comments/ Actions Taken (list actions taken if "No" is checked)
Is the system operating normally?	—	—	_____
Are any warning lights on? (Please list those that are on)	—	—	_____
If there is an alarm condition, was it fixed and the system restarted?	—	—	_____
Are the fan enclosures in good condition?	—	—	_____
Are the valves (at fans and aboveground piping) in good condition?	—	—	_____
Are aboveground piping free of cracks, leaks, and support issues?	—	—	_____
Are vacuum/pressure gauges operating properly?	—	—	_____
Are interior piping free of cracks, leaks, and support issues?	—	—	_____

List maintenance activities that were performed or \_\_\_\_\_  
 other comments about the system: \_\_\_\_\_

Influent	Vacuum (in. w.c.)	Comments

Effluent	Pressure (in. w.c.)	Comments

**PERFORM THE FOLLOWING ONLY IF A VACUUM READING AT THE MONITORING POINTS IS LESS THAN 0.004 IN. W.C.**

INSPECTION ITEM DESCRIPTION	Yes	No	Comments/ Actions Taken (list actions taken if "No" is checked)
Are interior vacuum gauges operating properly?	—	—	_____

Monitoring Point*	Vacuum (in. w.c.)	Comments
MP-1		
MP-2		
MP-3		
MP-4		
MP-5		
MP-6		
MP-7		
SVE-1		
SVE-2		
SVE-3		
SVE-4		
SVE-5		

in. w.c. - inches of water


\* Refer to Drawing 1 for locations of SSDS/SVE Monitoring Points and Suction Points

**Interim Remedial Measures Work Plan Addendum**  
***12 Franklin Street, Brooklyn, New York 11222***

---

**APPENDIX C**

Structural Drawings for Elevator Pit Construction and Backfilled Cellar



PER SOIL REPORT, GROUNDWATER WAS FOUND AT -3' BELOW EXISTING CURB. PROVIDE 3" RAT SLAB BELOW MAT SLAB, AND USE WATERPROOFING MEMBRANE (RECOMMENDED PREPRUFE 300R OR EQUIVALENT) ALONG HORIZONTAL AND VERTICAL SURFACES OF ELEVATOR PIT.

9 NORTH 15TH STREET ADJACENT 1-STORY BUILDING BROOKLYN, NY 11222

**LEGEND:**

- EXIST. STRUCTURAL WALL
- EXIST. STRUCTURAL WALL BELOW/FOOTING
- PROPERTY LINE
- EXIST. STEEL BEAM
- EXIST. SLAB OPENING
- EXIST. WOOD JOIST
- EXIST. COLUMN UP/DOWN
- NEW STEEL BEAM
- NEW HSS POST ABOVE/BELOW
- NEW FOOTING
- BEAM POCKET IN EXIST. WALL
- NEW 8" CMU WALL
- NEW LIGHT GAUGE FRAMING
- NEW 1 1/2" 20 GAUGE ROOF DECK

**1 FOUNDATION PLAN**

SCALE: 1/8"=1'-0"

**NOTES:**

1. ALL FOOTINGS AND WALLS ARE ASSUMED AND ARE TO BE INVESTIGATED FURTHER. FOOTINGS ARE TO BE VERIFIED IN FIELD.
2. NEW FOUNDATION SIZES TO BE CONFIRMED UPON RECEIPT OF GEOTECHNICAL REPORT.
3. BOTTOM OF ALL NEW FOOTINGS SHOULD BE BETWEEN 5-8 FEET BELOW GRADE, TO REACH ADEQUATE SOIL WITH 1500PSF ALLOWABLE BEARING PER GEOTECH REPORT.
4. GROUNDWATER WAS FOUND AT 3' BELOW GRADE. GC TO PREPARE DEWATERING PLAN AT FOUNDATION PHASE.

DATE	REVISION
03/22/2024	ISSUE FOR REVIEW

KEY PLAN:  
  
PROJECT LOCATION:  
**12 FRANKLIN STREET  
BROOKLYN, 11222**

SEAL & SIGNATURE:

DRAWING TITLE:

**PRELIMINARY  
FOUNDATION PLAN**

NYC DOB NOW JOB NO.: XXXXXXXXXXXX-1

PROJECT NO: 24005

DATE: 02/27/2024

DRAWN BY: AA

REVIEWED BY: AA

DRAWING NO.


**FO-100.00**

SHEET NUMBER: 01 OF 08

BSCAN:







**1 ROOF FRAMING PLAN**

SCALE: 1/8"=1'-0"

**NOTES:**

- SEE REPAIR DRAWINGS FOR ADDITIONAL INFORMATION.
- SEE ROOF DECK DRAWINGS PREPARED BY FORMAT ARCHITECTURE FOR EXTENTS OF PROPOSED TERRACES
- LAYOUTS/REINFORCEMENTS MAY MODIFIED PENDING ADDITIONAL SITE STUDIES/INVESTIGATIONS

**LEGEND:**

- EXIST. STRUCTURAL WALL
- EXIST. STRUCTURAL WALL BELOW/FOOTING
- PROPERTY LINE
- EXIST. STEEL BEAM
- EXIST. SLAB OPENING
- EXIST. WOOD JOIST
- EXIST. COLUMN UP/DOWN
- NEW STEEL BEAM
- NEW HSS POST ABOVE/BELOW
- NEW FOOTING
- BEAM POCKET IN EXIST. WALL
- NEW 8" CMU WALL
- NEW LIGHT GAUGE FRAMING
- NEW 1 1/2" 20 GAUGE ROOF DECK

DATE	REVISION
03/22/2024	ISSUE FOR REVIEW

**KEY PLAN:**

**PROJECT LOCATION:**

**12 FRANKLIN STREET  
 BROOKLYN, 11222**

**SEAL & SIGNATURE:**

**DRAWING TITLE:**

**PRELIMINARY ROOF  
 TERRACE PLAN**

NYC DOB NOW JOB NO.: XXXXXXXXXXXX-1

PROJECT NO: 24005

DATE: 02/27/2024

DRAWN BY: AA


REVIEWED BY: AA

DRAWING NO.

**S-100.00**

SHEET NUMBER: 02 OF 08

BSCAN:



TAKE DOWN EXIST. PARAPET WALL IN THIS LOCATION AND INSTALL NEW CMU DIRECTLY IN BEARING WALL BELOW.

NEW 1000S162-54 @16" O.C.  
 NEW 3" PLYWOOD SUBFLOOR TO MATCH EXISTING

NEW ELEVATOR BULKHEAD FRAMED USING 600S162-54 @16" O.C.  
 SEE ARCH FOR ELEVATOR BULKHEAD ELEVATIONS

NEW BEAM BEARING POCKET, BOTH SIDES

INSTALL CAP PLATE PL12"x6"x1/2". WELD TO TOP OF NEW COLUMN AND BOLT TO UNDERSIDE OF EXIST. HIGH BEAM W/ (4) 3/8" BOLTS.

9 NORTH 15TH STREET  
 ADJACENT 1-STORY BUILDING  
 BROOKLYN, NY 11222

**LEGEND:**

- EXIST. STRUCTURAL WALL
- EXIST. STRUCTURAL WALL BELOW/FOOTING
- PROPERTY LINE
- EXIST. STEEL BEAM
- EXIST. SLAB OPENING
- EXIST. WOOD JOIST
- EXIST. COLUMN UP/DOWN
- NEW STEEL BEAM
- NEW HSS POST ABOVE/BELOW
- NEW FOOTING
- BEAM POCKET IN EXIST. WALL
- NEW 8" CMU WALL
- NEW LIGHT GAUGE FRAMING
- NEW 1 1/2" 20 GAUGE ROOF DECK

**1 HIGH ROOF FRAMING PLAN**

SCALE: 1/8"=1'-0"  
 NOTES:

DATE	REVISION
03/22/2024	ISSUE FOR REVIEW

KEY PLAN:

PROJECT LOCATION:  
**12 FRANKLIN STREET  
 BROOKLYN, 11222**

SEAL & SIGNATURE:




DRAWING TITLE:  
**PRELIMINARY  
 BULKHEAD FRAMING  
 PLAN**

NYC DOB NOW JOB NO.: XXXXXXXXXXXX-1  
 PROJECT NO.: 24005  
 DATE: 02/27/2024  
 DRAWN BY: AA  
 REVIEWED BY: AA

DRAWING NO.  
**S-101.00**

SHEET NUMBER: **03 OF 08**

BSCAN:



**LEGEND**

DOOR / WINDOW TO BE REMOVED, NO CHANGE TO OPENING  
 PORTION TO BE DEMOLISHED  
 PORTION TO BE INFILLED USING 12" BRICK TO MATCH EXISTING  
 \* REFER TO DM-200 DEMOLITION ELEVATIONS AND A-200 BUILDING ELEVATIONS FOR PRECISE BOUNDARY LOCATIONS.

DATE	REVISION
03/22/2024	ISSUE FOR REVIEW

KEY PLAN:


PROJECT LOCATION:  
**12 FRANKLIN STREET  
 BROOKLYN, 11222**

SEAL & SIGNATURE:

DRAWING TITLE:  
**STRUCTURAL  
 ELEVATIONS  
 NORTH + EAST**


NYC DOB NOW JOB NO.: XXXXXXXXXXXX-1  
 PROJECT NO.: 24005  
 DATE: 02/27/2024  
 DRAWN BY: AA  
 REVIEWED BY: AA  
 DRAWING NO.

S-200.00  
 SHEET NUMBER: 04 OF 08  
 BSCAN:



**2 SOUTH-WEST ELEVATION FACADE (ALONG NORTH 15TH ST.)**

SCALE: 1/4"=1'-0"



**1 NORTH-WEST ELEVATION FACADE (ALONG FRANKLIN ST.)**

SCALE: 1/4"=1'-0"

**LEGEND**

DATE	REVISION
03/22/2024	ISSUE FOR REVIEW

KEY PLAN:

PROJECT LOCATION:  
**12 FRANKLIN STREET  
 BROOKLYN, 11222**

SEAL & SIGNATURE:


DRAWING TITLE:  
**STRUCTURAL  
 ELEVATIONS  
 SOUTH + WEST**

NYC DOB NOW JOB NO.: XXXXXXXXXXXX-H  
 PROJECT NO: 24005  
 DATE: 02/27/2024  
 DRAWN BY: AA  
 REVIEWED BY: AA  
 DRAWING NO.


**S-201.00**

SHEET NUMBER: 05 OF 08


BSCAN:




**1 TYP. BEAM TO COLUMN FLANGE SHEAR CONN.**  
SCALE: 3/4"=1'-0"




**2 TYP. BEAM TO COLUMN WEB SHEAR CONN.**  
SCALE: 3/4"=1'-0"



**3 TYPICAL BEAM TO GIRDER CONN.**  
SCALE: 3/4"=1'-0"




**4 ALTERNATE BEAM TO COLUMN MOMENT CONNECTION AT COLUMN FLANGE**  
SCALE: 3/4"=1'-0"




**5 TYP. BEAM POCKET IN EX. MASONRY WALL**  
SCALE: 3/4"=1'-0"


LINTEL SCHEDULE					
NOTE	LOCATION	MATERIAL SECTION (BxH)	SPAN	REINFORCING	REMARKS
L1	CMU WALL	8" CMU BOND BEAM	< 4'	2#5 TOP 2#5 BOTTOM	8" BEARING EACH END




**7A TYPICAL ANGLE LINTEL SECTION**  
SCALE: 3/4"=1'-0"




**7B TYPICAL WF BEAM LINTEL SECTION**  
SCALE: 3/4"=1'-0"




**10 TYP. ADDITIONAL REINFORCING IN CMU STRUCTURAL WALLS**  
SCALE: N.T.S.  
NOTE: FOR TYPICAL JOINT REINFORCING SEE SPECS.




**6 TYPICAL 8" CMU LINTEL SECTION (L1)**  
SCALE: N.T.S.




**7C ALTERNATE DOUBLE CHANNEL LINTEL**  
SCALE: N.T.S.



**11 TYPICAL SHEAR WALL REINFORCEMENT DETAIL- PLAN VIEW**  
SCALE: N.T.S.  
NOTE: FOR EXP. JOINT, SHEAR WALL AND BEARING WALL LOCATION SEE PLAN.



**8 TYP. JOIST SISTER DETAIL**  
SCALE: 3/4"=1'-0"



**9 WOOD JOIST HANGER**  
SCALE: 1"=1'-0"

ELEVATOR SHAFT WALLS								
FLOOR	REINF.	THICKNESS	GROUT SPACING	VERT. REINFORCING	ADDITIONAL VERTICAL REINFORCING AT BOTH ENDS OF WALL	HORIZ. REINFORCING	REMARKS	BLOCK STRENGTH
BULKHEAD ROOF	8	SOLID		#5 AT 16" o/c	1#5	2#3 AT 16" o/c	F'M=2500psi	3750psi
ROOF	8	SOLID		#5 AT 16" o/c	1#5	2#3 AT 16" o/c	F'M=2500psi	3750psi
1ST FLOOR	8	SOLID		#5 AT 16" o/c	1#5	2#3 AT 16" o/c	F'M=2500psi	3750psi

NOTES:  
1. MIN. REINFORCING OF SHEAR WALL SHALL BE #4@32" O.C. (U.O.N.)  
2. TYPICAL HORIZONTAL REINFORCING SHALL BE 2#3 BARS @ 16" O.C. (U.O.N.)  
3. DOWELS UP FROM WALL OR FOUNDATION BELOW SHALL MATCH REBARS SHOWN ON SCHEDULE ABOVE.  
4. SEE CMU SHEAR WALL KEY PLANS ON THIS SHEET FOR SHEAR WALL LOCATIONS.  
5. TYPICAL REBAR PLACEMENT IS ONE REBAR PER FULLY GROUTED CELL.  
6. ALL REINFORCEMENT (HORIZ. AND VERT.) SHALL BE CONTINUOUS FOR THE FULL WALL LENGTH.


DATE	REVISION
03/22/2024	ISSUE FOR REVIEW

PROJECT LOCATION:  
**12 FRANKLIN STREET  
BROOKLYN, 11222**


DRAWING TITLE:  
**TYP. STRUCTURAL  
STEEL + MASONRY  
DETAILS**

NYC DOB NOW JOB NO.: XXXXXXXXXXXX-1  
PROJECT NO.: 24005  
DATE: 02/27/2024  
DRAWN BY: AA  
REVIEWED BY: AA  
DRAWING NO.


SHEET NUMBER: **06 OF 08**  
SCAN:




**1 SECTION @ ELEVATOR PIT**  
 SCALE: 1/2"=1'-0"




**2 TYP. CELLAR SLAB DETAIL**  
 SCALE: 1/2"=1'-0"




**3 TYP. SLAB CONST. JOINT**  
 SCALE: 1/2"=1'-0"



**4 TYP. SLAB CONTROL JOINT**  
 SCALE: 1/2"=1'-0"



**5 TYPICAL SUMP-PIT**  
 SCALE: 3/4"=1'-0"



**6 TYP. COLUMN FOOTING SECTION**  
 SCALE: 3/4"=1'-0"

DATE	REVISION
03/22/2024	ISSUE FOR REVIEW


KEY PLAN:  
 PROJECT LOCATION:  
**12 FRANKLIN STREET  
 BROOKLYN, 11222**

SEAL & SIGNATURE:  
 DRAWING TITLE:  
**FOUNDATION DETAILS**

NYC DOB NOW JOB NO.: XXXXXXXXXXXX-1  
 PROJECT NO: 24005  
 DATE: 02/27/2024  
 DRAWN BY: AA  
 REVIEWED BY: AA  
 DRAWING NO.  
**S-211.00**  
 SHEET NUMBER: 07 OF 08

BSCAN:  
 [ ]





① BACKFILLED CELLAR PLAN  
1/4" = 1'-0"


ARCHITECT  
**FORMAT**  
 ARCHITECTURE OFFICE, PLLC  
 55 Washington Street, Suite 312D  
 Brooklyn, NY 11201

PROJECT  
**12 FRANKLIN STREET**  
 12 FRANKLIN STREET  
 BROOKLYN, NY 11222


DRAWING  
**SK-01A**  
 BACKFILLED CELLAR SLAB PLAN  
 ISSUE / REVISIONS \_\_\_\_\_

DETAILS





② VAPOR BARRIER DETAIL #2  
1 1/2" = 1'-0"









① VAPOR BARRIER DETAIL #1  
1 1/2" = 1'-0"

ARCHITECT  
**FORMAT**  
ARCHITECTURE OFFICE, PLLC  
55 Washington Street, Suite 312D  
Brooklyn, NY 11201

PROJECT  
**12 FRANKLIN STREET**  
12 FRANKLIN STREET  
BROOKLYN, NY 11222

DRAWING  
**SK-01B**  
TYPICAL SLAB VAPOR BARRIER DETAILS  
ISSUE / REVISIONS \_\_\_\_\_

DETAILS



△	DATE	REVISION
	03/22/2024	ISSUE FOR REVIEW

KEY PLAN:

PROJECT LOCATION:  
**12 FRANKLIN STREET  
 BROOKLYN, 11222**

SEAL & SIGNATURE:

DRAWING TITLE:

**FOUNDATION DETAILS**

NYC DOB NOW JOB NO.: XXXXXXXXXXXX-1

PROJECT NO: 24005

DATE: 02/27/2024

DRAWN BY: AA

REVIEWED BY: AA

DRAWING NO.

**S-211.00**

SHEET NUMBER: 07 OF 08

BSCAN:



**Interim Remedial Measures Work Plan Addendum**  
***12 Franklin Street, Brooklyn, New York 11222***

---

**APPENDIX D**


GCP PREPRUFE 300R® Membranes and Drago® Wrap Data Sheets

# PREPRUFE® 300R & 160R Membranes Data Sheet (US Version)

Pre-applied waterproofing membranes that bond integrally to poured concrete for use below slabs or behind basement walls on confined sites

## Product Description

GCP Applied Technologies ("GCP") PREPRUFE® 300R & 160R membranes are proprietary composite sheets comprised of a thick HDPE film, pressure sensitive adhesive and weather resistant protective coating. Designed with Advanced Bond Technology™, PREPRUFE® 300R & 160R membranes form a proprietary, integral bond to poured concrete, designed to prevent lateral migration of water while providing a robust barrier to water, moisture and gas penetration.



Drawings are for illustration purposes only.  
Please refer to [gcpat.com](http://gcpat.com) for specific application details.

## Product Advantages

- Forms a continuous adhesive bond to concrete poured against it specifically designed to prevent water migration
- Continuous bond to poured concrete means PREPRUFE® 300R & 160R membranes are unaffected by ground settlement
- Can be placed directly over properly prepared compacted soil
- Does not activate prematurely during construction
- Fully adhered watertight laps and detailing
- Provides a barrier to water, moisture and gas - physically isolates the structure from the surrounding ground
- BBA Certified for all basement grades (BS 8102:2009)
- Impermeable- Perm rating less than 0.1 Perms
- Solar reflective - reduced temperature gain during construction

- Simple and quick to install – requires no priming on surfaces properly prepared following GCP surface preparation requirements
- Can be applied to permanent formwork - maximizes use of confined sites
- Allows for foot traffic immediately after application
- Ready for immediate placing of reinforcing steel
- Inherently waterproof--does not require water activation
- Waterproofing is not reliant on confining pressures or hydration
- Installed membrane is not affected by exposure to water during construction
- Waterproofing performance unaffected by wet/dry cycling
- Chemical resistance – protects structure from salt and sulfate attack, effective in most types of soils and waters

## System Components:

### Membrane

- PREPRUFE® 300R membrane- heavy-duty 46 mil grade can be used in horizontal applications below slabs and on rafts (i.e. mud slabs) and can be applied to vertical (blind side) substrates.
- PREPRUFE® 300R membrane is designed to accept the placing of heavy reinforcement using conventional concrete spacers
- PREPRUFE® 160R membrane 32 mil grade for blindside, zero property line applications against soil retention systems.
- PREPRUFE® 160R membrane is for vertical use only.

### Ancillary Components (the most current Data Sheets for all system components are available on [gcpat.com](http://gcpat.com))

- PREPRUFE® Tape LT – Low temperature tape for covering cut edges, roll ends, penetrations and detailing in cold weather
- PREPRUFE® Tape HC – High temperature tape for covering cut edges, roll ends, penetrations at elevated temperatures
- PREPRUFE® CJ Tape LT – Low temperature joint tape for construction joints and detailing in cold weather conditions
- PREPRUFE® CJ Tape HC – High temperature joint tape for construction joints and detailing at elevated temperatures
- BITUTHENE® Liquid Membrane - for sealing around penetrations, etc.
- ADCOR® - waterstop for joints in concrete walls and floors
- PREPRUFE® Tieback Covers - preformed cover for soil retention wall tieback heads
- PREPRUFE® 300LT and 160LT membranes are an equal alternate for application at low temperatures. See [GCPAT.com](http://GCPAT.com)

## Limitations of Use

- Approved uses only include those uses specifically detailed in this Product Data Sheet and other current Product Data Sheets that can be found at [gcpat.com](http://gcpat.com)
- PREPRUFE® 300R & 160R membranes are not intended for any other use. Contact GCP Technical Services where any other use is anticipated or intended.
- PREPRUFE® 300R membranes are designed for in-service temperatures below 120°F (49°C)
- PREPRUFE® 160R membrane is not for use in horizontal applications
- PREPRUFE® 300R & 160R membranes should not be used with conventional twin-sided formwork. (See PREPRUFE® Technical Letter #13 Forming Systems For Use with PREPRUFE® Membranes)
- **Special Note:** When this information is printed from the [gcpat.com](http://gcpat.com) global website, a footer appearing on this document will restrict its applicability to the United States. Note that the information and references in this document are hereby expanded and apply to North, Central and South America.

## Safety and Handling

Users must read and understand the product label and Safety Data Sheets (SDS's) for each system component before use. All users must acquaint themselves with this information prior to working with the material. Carefully read detailed precaution statements on the product labels and SDS's before use. The most current SDS's can be obtained from the GCP web site at [gcpat.com](http://gcpat.com) or by contacting GCP toll free at 1-866-333-3SBM (3726).

## Storage

- Observe 1 year shelf life and use on a first in first out basis
- Store in dry conditions at 40°F (4.5°C)-90°F (32°C)
- Store off ground under tarps or otherwise protected from rain and ground moisture
- See PREPRUFE® Technical Letter #30 Shelf Life/Storage and Handling of GCP Waterproofing

## Installation

### Technical Support, Details and Technical Letters

The most up to date detail drawings and technical letters are available at [gcpat.com](http://gcpat.com). For complete application instructions, please refer to the current GCP Applied Technologies Contractor Handbook and Literature on ([www.gcpat.com](http://www.gcpat.com)). Documents in hardcopy as well as information found on websites other than [www.gcpat.com](http://www.gcpat.com) may be out of date or in error. Before using this product it is important that information be confirmed by accessing [www.gcpat.com](http://www.gcpat.com) and reviewing the most recent product information, including without limitation Product Data Sheets and Contractor Manuals, Technical Bulletins, Detail Drawings and detailing recommendations. Please review all materials prior to installation of PREPRUFE® 300R & 160R membranes.

Support is also available by full-time technically trained GCP Applied Technologies field sales representatives and technical service personnel, backed by a central research and development technical services staff. For technical assistance with detailing and problem solving please call toll-free at (866) 333-3SBM (3726).

## Temperature Requirements

- PREPRUFE® membranes can be applied at temperatures of 25 °F (-4 °C) or above. When installing PREPRUFE® products in cold or marginal weather conditions <55 °F (<13 °C) the use of PREPRUFE® Tape LT is required at all laps and detailing. All surfaces to receive PREPRUFE® Tape LT must be clean and dry.
- As an alternate, where temperatures are between between 25 °F (-4 °C) and 60 °F (15.5 °C) PREPRUFE® Low Temperature (LT) Membrane is can be used without taping of laps. Refer to PREPRUFE® LT Membrane data sheet and Technical Letter #16 PREPRUFE® Waterproofing membranes: Cold Weather installation for more information.

## Substrate Preparation

All surfaces - It is essential to create a sound and solid substrate to eliminate movement during the concrete pour. Substrates must be regular and smooth with no gaps or voids greater than 0.5 in. (12 mm). Grout around all penetrations such as utility conduits, etc. for stability.

Horizontal - The substrate must be free of loose aggregate and sharp protrusions. Avoid curved or rounded substrates. When installing over earth or crushed stone, ensure substrate is well compacted to avoid displacement of substrate due to traffic or concrete pour. The surface does not need to be dry, but standing water must be removed.

Vertical - Use concrete, plywood, insulation or other approved facing to sheet piling to provide support to the membrane. Board systems such as timber lagging must be close butted to provide support and not more than 0.5" (12mm) out of alignment.

## Membrane Application

PREPRUFE® 300R & 160R membranes are supplied in rolls 4 ft. (1.2m) wide, with a selvedge on one side to provide self-adhered laps for continuity between rolls. The rolls of PREPRUFE® Membrane and PREPRUFE® Tape are manufactured with a disposable plastic release liner which must be removed before placing reinforcement and concrete. NOTE that the release liner must also be removed before application of any required tapes and at all surfaces where a bond between layers is to be formed.

Horizontal substrates -

PREPRUFE® 300R membrane can be applied horizontally to smooth prepared concrete or well rolled and compacted earth or crushed stone substrate. Place the PREPRUFE® 300R membrane HDPE film side to the substrate with the clear plastic release liner facing towards the concrete pour. End laps should be staggered to avoid a buildup of layers. Leave plastic release liner in position until overlap procedure is completed. When completed remove release liner. When installing over carton forms, contact your local GCP representative.

Accurately position succeeding sheets to overlap the previous sheet 3 in. (75 mm) along the marked selvedge. Ensure the underside of the succeeding sheet is clean, dry and free from contamination before attempting to overlap. Peel back the plastic release liner from between the overlaps allowing the two overlapped layers to bond together. Ensure a continuous bond is achieved without creases and roll firmly with a heavy roller. Completely remove the plastic liner to expose the white protective coating. Any initial tack will quickly disappear. Notes:

- PREPRUFE® 300R membrane can be returned up the inside face of slab formwork. To attain a fully bonded system and to allow a tie in with BITUTHENE® self-adhered membrane or PROCOR® fluid-applied membrane to all vertical structural surfaces after removal of formwork.
- Rebar Chairs: See PREPRUFE® Technical Letter #15 Rebar Chairs on PREPRUFE® Membranes.

#### Vertical substrates –

PREPRUFE® 300R & 160R membranes can be applied vertically to permanent formwork or adjoining structures. Concrete should then be cast directly against the adhesive side of the membrane. The membrane may be installed in any convenient length. The clear plastic release liner must be facing towards the concrete pour. Membrane must be shingle overlapped a minimum of 3" (75mm) All laps over cut edges must be taped using PREPRUFE® Tape.

Vertically placed sheets can be held in place using fasteners appropriate to the substrate. Fastening can also be made through the selvedge overlap area using a small and low profile head fastener so that the membrane lays flat and allows firmly rolled overlaps. Fasteners should be placed in the selvedge approximately 0.5" (12.5mm) from the edge of the membrane. The adhesive selvedge of successive membrane sheets must completely cover any fasteners by a minimum of 1 in. (25mm). After rolling immediately remove the plastic release liner. When placing successive sheets insure the underside of each succeeding sheet is clean, dry and free from contamination before attempting to overlap. After placement roll the membrane firmly to ensure a watertight seal.

Note that PREPRUFE® 300R & 160R membranes are not recommended for use with conventional twin-sided formwork. (See PREPRUFE® Technical Letter #13 Forming Systems For Use with PREPRUFE® Membranes)

#### Roll ends and cut edges –

Overlap all roll ends and cut edges by a minimum 3 in. (75 mm) and ensure the area is clean and free from contamination, wiping with a damp cloth if necessary. Allow the membrane to dry and apply PREPRUFE® Tape LT (or HC in hot climates) centered over the lap edges and roll firmly. Immediately remove plastic release liner from the tape.



## Membrane Repair

Inspect the membrane before installation of reinforcement steel, formwork and final placement of concrete. The membrane can be easily cleaned by power washing if required. Repair damage by wiping the area with a damp cloth to ensure the area is clean and free from dust, and other contaminants and allow the membrane to dry. Repair small punctures and slices (0.5 in. (12 mm) or less by applying PREPRUFE® Tape centered over the damaged area. Repair punctures and holes larger than 0.5 in. (12mm) by applying a patch of PREPRUFE® membrane. Extend the patch 6 in. (150 mm) beyond the damaged area. Seal all edges of the patch with PREPRUFE® Tape. Where exposed selvage has lost adhesion or laps have not been sealed, ensure the area is clean and dry and cover with fresh PREPRUFE® Tape. Any areas of damaged adhesive should be covered with PREPRUFE® Tape. All PREPRUFE® Tape must be rolled firmly and the tinted release liner removed.

Slices or relief cuts can be butted or overlapped and repaired by applying PREPRUFE® Tape centered over the edge of the overlap or center of the butt joint. Where it is not possible to create a butt joint or overlap, repair with fresh membrane and PREPRUFE® Tape as detailed above.

## Pouring of Concrete

Ensure the plastic release liner is removed from all areas of PREPRUFE® 300R & 160R Membrane and Tape.

Under most climatic conditions concrete should be poured within 56 days of membrane installation. Where ambient temperatures will exceed 38°C (100°F) for more than a total of 7 days, concrete should be placed within 42 days of installation of the membrane. Concrete must be placed and compacted carefully to avoid damage to the Membrane. Never use a sharp object to consolidate the concrete.

## Removal of Formwork

A minimum concrete compressive strength of 3000 psi (20 N/mm<sup>2</sup>) is recommended prior to stripping formwork supporting PREPRUFE® membranes. Premature stripping may result in displacement of the membrane and/or spalling of the concrete. (see PREPRUFE® Technical Letter #17 Removal of Formwork Placed against PREPRUFE® membranes)

After removal of the formwork and prior to backfilling, all exposed PREPRUFE® Membrane must be protected from damage with an approved protective course.

## Supply

DIMENSIONS (NOMINAL)	PREPRUFE® 300R MEMBRANE	PREPRUFE® 160R MEMBRANE
Roll size	4 ft x 98 ft (1.2 m x 30 m)	4 ft x 115 ft (1.2 m x 35 m)
Roll weight	108 lbs (50 kg)	92 lbs (42 kg)
Minimum side and end laps	3 in. (75 mm)	3 in. (75 mm)

## Physical Properties

PROPERTY	TYPICAL VALUE 300R	TYPICAL VALUE 160R	TEST METHOD
Color	white	white	
Thickness	0.046 in. (1.2 mm)	0.032 in. (0.8 mm)	ASTM D3767
Lateral Water Migration Resistance	Pass at 231 ft (71 m) of hydrostatic head pressure	Pass at 231 ft (71 m) of hydrostatic head pressure	ASTM D5385 <sup>1</sup>
Low Temperature Flexibility	Unaffected at -20°F (-29°C)	Unaffected at -20°F (-29°C)	ASTM D1970
Resistance to Hydrostatic Head	231 ft (71 m)	231 ft (71 m)	ASTM D5385 <sup>2</sup>
Elongation	400%	400%	ASTM D412 <sup>3</sup>
Tensile Strength, Film	4000 psi (27.6 MPa)	4000 psi (27.6 MPa)	ASTM D412
Crack Cycling at -9.4°F (-23°C), 100 cycles	Unaffected, Pass	Unaffected, Pass	ASTM C836 <sup>6</sup>
Puncture Resistance	200 lbs (890 N)	100 lbs (445 N)	ASTM E154
Peel Adhesion to Concrete	5 lbs/in. (880 N/m)	5 lbs/in. (880 N/m)	ASTM D903 <sup>4</sup>
Lap Peel Adhesion	5 lbs/in. (880 N/m)	5 lbs/in. (880 N/m)	ASTM D1876 <sup>5</sup>
Permeance to Water Vapor Transmission (HDPE side exposed)	<0.1 perms (5.74 ng/(Pa x s x m <sup>2</sup> ))	<0.1 perms (5.74 ng/(Pa x s x m <sup>2</sup> ))	ASTM E96, method B
Water Absorption	0.5%	0.5%	ASTM D570

### Footnotes:

1. Lateral water migration resistance is tested by casting concrete against membrane with a hole and subjecting the membrane to hydrostatic head pressure with water. The test measures the resistance of lateral water migration between the concrete and the membrane.
2. Hydrostatic head tests of PREPRUFE Membranes are performed by casting concrete against the membrane with a lap. Before the concrete cures, a 0.125 in. (3 mm) spacer is inserted perpendicular to the membrane to create a gap. The cured block (cured min. 7 days) is placed in a chamber where water is introduced to the membrane surface up to the head indicated.
3. Elongation of membrane is run at a rate of 2 in. (50 mm) per minute.
4. Concrete is cast against the protective coating surface of the membrane and allowed to properly cure (7 days minimum). Peel adhesion of membrane to concrete is measured at a rate of 2 in. (50 mm) per minute at room temperature.
5. The test is conducted 15 minutes after the lap is formed and run at a rate of 2 in. (50 mm) per minute.
6. Test conducted at -9.4°F (-23°C)

[gcpat.com](http://gcpat.com) | North America customer service: 1 (866) 333-3SBM (1 (866) 333-3726

We hope the information here will be helpful. It is based on data and knowledge considered to be true and accurate, and is offered for consideration, investigation and verification by the user, but we do not warrant the results to be obtained. Please read all statements, recommendations, and suggestions in conjunction with our conditions of sale, which apply to all goods supplied by us. No statement, recommendation, or suggestion is intended for any use that would infringe any patent, copyright, or other third party right.

ADCOR, PREPRUFE, PROCOR, and BITUTHENE are trademarks, which may be registered in the United States and/or other countries, of GCP Applied Technologies Inc. This trademark list has been compiled using available published information as of the publication date and may not accurately reflect current trademark ownership or status.

© Copyright 2018 GCP Applied Technologies Inc. All rights reserved.

GCP Applied Technologies Inc., 62 Whittemore Avenue, Cambridge, MA 02140 USA.

In Canada, 294 Clements Road, West, Ajax, Ontario, Canada L1S 3C6.

Printed materials intended for use in the United States only.

This document is only current as of the last updated date stated below and is valid only for use in the United States. It is important that you always refer to the currently available information at the URL below to provide the most current product information at the time of use. Additional literature such as Contractor Manuals, Technical Bulletins, Detail Drawings and detailing recommendations and other relevant documents are also available on [www.gcpat.com](http://www.gcpat.com). Information found on other websites must not be relied upon, as they may not be up-to-date or applicable to the conditions in your location and we do not accept any responsibility for their content. If there are any conflicts or if you need more information, please contact GCP Customer Service.

Last Updated: 2020-01-08

[gcpat.com/solutions/products/preprufe-membrane-pre-applied-waterproofing-solutions/preprufe-300r-160r-0](http://gcpat.com/solutions/products/preprufe-membrane-pre-applied-waterproofing-solutions/preprufe-300r-160r-0)



# DRAGO® MASTIC

A STEGO INDUSTRIES, LLC INNOVATION | VAPOR RETARDERS 07 26 00, 03 30 00 | VERSION: MAY 28, 2024

## 1. PRODUCT NAME

**DRAGO MASTIC**

## 2. MANUFACTURER

Stego Industries, LLC  
 216 Avenida Fabricante, Suite 101  
 San Clemente, CA 92672  
 Sales, Technical Assistance  
 Ph: (877) 464-7834  
 contact@stegoindustries.com  
**stegoindustries.com**



## 3. PRODUCT DESCRIPTION

**USES:** Drago Mastic is designed to be used as a vapor intrusion membrane in conjunction with Drago® Wrap. Drago Mastic can be used for sealing utility or pipe penetrations, and terminating edges against existing adjacent concrete or other foundation constructions.

**COMPOSITION:** Drago Mastic is a medium viscosity, water-based, polymer-modified anionic bituminous/asphalt emulsion.

**SIZE:** Drago Mastic comes in a 5-gallon pail.

## 4. TECHNICAL DATA

**TABLE 1: PHYSICAL PROPERTIES OF DRAGO MASTIC**

PROPERTY	TEST	RESULTS
Permeance Rating	ASTM E96	0.08 perms
Tensile Strength	ASTM D412	87 psi
Elongation	ASTM D412	1800%
Adhesion to Concrete	ASTM C836	Exceeds
Shore Hardness	ASTM C836	75
Crack Bridging	ASTM C836	Exceeds
Low Temp Flexibility	ASTM C836	No Cracking
Chemical Resistance (TCE, PCE, Toluene, Xylene)	ASTM D471/D543	No significant negative change to mass or volume.

Note: perm unit = grains/(ft<sup>2</sup>\*hr\*in-Hg)

# DRAGO MASTIC

A STEGO INDUSTRIES, LLC INNOVATION | VAPOR RETARDERS 07 26 00, 03 30 00 | VERSION: MAY 28, 2024

## 5. INSTALLATION

### PREPARATION:

- A test application simulating the project environment should always be done prior to final usage of Drago Mastic.
- All surfaces should be dry and free of loose materials, oils and other contaminants. The surfaces should be cleaned in the same fashion as the test surface in order to ensure proper results.
- Store above 40°F, and apply above 40°F and below 130°F.

### PENETRATIONS:

To repair penetrations in Drago Wrap, cut Drago Wrap just big enough to fit over and around the penetration so as to minimize void space. Liberally apply Drago Mastic around the penetration to keep the integrity of the membrane intact. Drago Mastic can be applied from pails by brush, roller, or trowel.

**NOTES:** 1) If needed to minimize void space around penetrations, utilize a detail patch of Drago Wrap to fit over the penetration and seal the patch/boot with DragoSeal™ Tape prior to applying Drago Mastic. 2) Solvent-based products should not be applied over this product. 3) Clean all tools with kerosene and/or oil-based cleaners.

For additional information, please refer to Drago's complete installation instructions.

## 6. AVAILABILITY & COST

Drago Mastic is available through our network of building supply distributors. For current cost information, contact your local Drago distributor or Stego® Sales Representative.

## 7. WARRANTY

Stego believes to the best of its knowledge, that specifications and recommendations herein are accurate and reliable. However, since site conditions are not within its control, Stego does not guarantee results from the use of the information provided herein. Stego does offer a limited warranty on Drago Wrap. Please see [stegoindustries.com/legal](https://stegoindustries.com/legal)

## 8. MAINTENANCE

None required.

## 9. TECHNICAL SERVICES

Technical advice, custom CAD drawings, and additional information can be obtained by contacting Stego or by visiting the website.

**Email:** [contact@stegoindustries.com](mailto:contact@stegoindustries.com)

**Contact Number:** (877) 464-7834

**Website:** [stegoindustries.com](https://stegoindustries.com)

## 10. FILING SYSTEMS: [stegoindustries.com](https://stegoindustries.com)





# DRAGO® SEALANT

A STEGO INDUSTRIES, LLC INNOVATION | VAPOR RETARDERS 07 26 00, 03 30 00 | VERSION: MAY 28, 2024

## 1. PRODUCT NAME

**DRAGO SEALANT**

## 2. MANUFACTURER

Stego Industries, LLC  
 216 Avenida Fabricante, Suite 101  
 San Clemente, CA 92672  
 Sales, Technical Assistance  
 Ph: (877) 464-7834  
 contact@stegoindustries.com  
 stegoindustries.com



## 3. PRODUCT DESCRIPTION

**USES:** Drago Sealant is designed to be used as a vapor intrusion membrane in conjunction with Drago® Wrap. Drago Sealant can be used as an alternate to detail patches for penetrations in Drago Wrap.

**COMPOSITION:** Drago Sealant is a two-component, 100% solids, semi-rigid epoxy sealant.

**SIZE:** Drago Sealant comes in a 4-gallon kit size: Two 1-gallon cans of Part A (Resin) and two 1-gallon cans of Part B (Hardener).

**COVERAGE:** 96ft² @ 60-mils per kit (4 gallons of product).

## 4. TECHNICAL DATA

**TABLE 4.1: PHYSICAL PROPERTIES OF DRAGO SEALANT**

PROPERTY	TEST	RESULTS
Mix Ratio (A:B by volume)		1:1
Mixed Viscosity		4,000 - 7,000 cp
Gel Time (100 g)		50-60 mins
Pot Life (full unit)		30-45 mins
Tack Free Time		5-6 hours
Shore A Hardness	ASTM D2240	80-90
Tensile Strength	ASTM D638	800 psi
Tensile Elongation %	ASTM D638	95-105%
Water Vapor Permeance	ASTM F1249	0.015 perms @ 60-mils
Chemical Resistance (TCE, PCE, Toluene, Xylene)	ASTM D471/D543	No significant change to mass or volume.

Note: perm unit = grains/(ft²\*hr\*in-Hg)

## 5. INSTALLATION

### PREPARATION:

- A test application simulating the project environment should always be done prior to final usage of Drago Sealant.
- All surfaces should be dry and free of loose materials, oils, and other contaminants. The surfaces should be cleaned in the same fashion as the test surface in order to ensure proper application.
- Drago Sealant can be applied to virtually any shape or contour by brush, paint roller, trowel or squeegee at various spread rates. The recommended installation temperature ranges from 50°F to 140°F. Optimum ambient temperature is between 50-90°F during application. Note: Cure times are affected by ambient and surface temperatures. Temperatures of 40°F and lower can slow cure times. Temperatures of 90°F and higher will speed up cured times and reduce working time.

Continued...

Note – legal notice on page 2.

# DRAGO SEALANT

A STEGO INDUSTRIES, LLC INNOVATION | VAPOR RETARDERS 07 26 00, 03 30 00 | VERSION: MAY 28, 2024

## PREPARATION: *Continued...*

- Drago Sealant comes in a 4-gallon kit size. It consists of two 1-gallon cans of Part A (Resin) and two 1-gallon cans of Part B (Hardener). Mix the following with a drill and mixing paddle (Note: If using a drill mixer, use a low speed [not to exceed 300 rpm] to prevent air entrapment):
  - Premix Part A and Part B separately. Combine 1 part by volume of Part A to 1 part by volume of Part B and mix thoroughly. Do not thin. Scrape the side and bottom of the mixing container to assure uniform and complete mixing. Mix for 2-3 minutes. Do not aerate mix.

## PENETRATIONS:

- To repair penetrations in Drago Wrap, cut a hole in Drago Wrap such that the membrane fits over and around the base of the pipes as closely as possible, ensuring that it is flush with the base of the penetrations.
- Install Drago® Sealant Form continuously around the entire perimeter of the group of penetrations and at least 1 inch beyond the terminating edge of Drago Wrap.
- Pour Drago Sealant inside of Drago Sealant Form to create a seal around the penetrations.
- If the void space between Drago Wrap and the penetrations is not minimized and/or the base course allows for too much drainage of the sealant, a second coat of Drago Sealant may need to be poured after the first application has cured.

Review Drago Wrap's complete installation instructions prior to installation.

## 6. AVAILABILITY & COST

Drago Sealant is available through our network of building supply distributors. For current cost information, contact your local Drago distributor or Stego® Sales Representative.

## 7. WARRANTY

Stego believes to the best of its knowledge, that specifications and recommendations herein are accurate and reliable. However, since site conditions are not within its control, Stego does not guarantee results from the use of the information provided herein. Stego does offer a limited warranty on Drago Wrap. Please see [stegoindustries.com/legal](https://stegoindustries.com/legal)

## 8. MAINTENANCE

Store locked up in a dry and temperate area.

## 9. TECHNICAL SERVICES

Technical advice, custom CAD drawings, and additional information can be obtained by contacting Stego or by visiting the website.

**Email:** [contact@stegoindustries.com](mailto:contact@stegoindustries.com)  
**Contact Number:** (877) 464-7834  
**Website:** [stegoindustries.com](https://stegoindustries.com)

## 10. FILING SYSTEMS: [stegoindustries.com](https://stegoindustries.com)





# DRAGO® SEALANT FORM


A STEGO INDUSTRIES, LLC INNOVATION | VAPOR RETARDERS 07 26 00, 03 30 00 | VERSION: MAY 28, 2024

## 1. PRODUCT NAME

**DRAGO SEALANT FORM**

## 2. MANUFACTURER

Stego Industries, LLC  
 216 Avenida Fabricante, Suite 101  
 San Clemente, CA 92672  
 Sales, Technical Assistance  
 Ph: (877) 464-7834  
 contact@stegoindustries.com  
**stegoindustries.com**



## 3. PRODUCT DESCRIPTION

**USES:** Drago Sealant Form is used in conjunction with Drago® Sealant to help create an efficient and effective seal around pipe penetrations in Drago® Wrap.

**COMPOSITION:** Drago Sealant Form is a low-density, cross-linked, closed-cell polyethylene foam with an acrylic, pressure-sensitive adhesive.

**SIZE:** Drago Sealant Form is 1/2" x 1/2" x 24". Drago Sealant Form comes in 200 pieces per case (10 boxes of 20 pieces).

## 4. TECHNICAL DATA

**TABLE 4.1: PHYSICAL PROPERTIES OF DRAGO SEALANT FORM**

PROPERTY	RESULTS
Dimensions	1/2" x 1/2" x 24"
Color	White
Weight	0.11 oz (3.1 grams)

## 5. INSTALLATION

**PENETRATIONS:** Make sure the area of adhesion is free of dust, debris, moisture, and frost to allow maximum adhesion. When ready to apply to Drago Wrap, remove the release liner and press Drago Sealant Form firmly against Drago Wrap to secure. Install Drago Sealant Form continuously around the entire perimeter of the penetration(s) and at least 1 inch beyond the terminating edge of Drago Wrap. Install Drago Sealant Form between 40°F and 110°F. Pour Drago Sealant inside of Drago Sealant Form to create a seal around the penetration(s).

Review Drago Wrap’s complete installation instructions prior to installation.

## 6. AVAILABILITY & COST

Drago Sealant Form is available nationally through our network of building supply distributors. For current cost information, contact your local Drago distributor or Stego® Sales Representative.



# DRAGO® SEALANT FORM

A STEGO INDUSTRIES, LLC INNOVATION | VAPOR RETARDERS 07 26 00, 03 30 00 | VERSION: MAY 28, 2024

## 7. WARRANTY

Stego believes to the best of its knowledge, that specifications and recommendations herein are accurate and reliable. However, since site conditions are not within its control, Stego does not guarantee results from the use of the information provided herein. Stego does offer a limited warranty on Drago Wrap. Please see [stegoindustries.com/legal](https://stegoindustries.com/legal)

## 8. MAINTENANCE

Store Drago Sealant Form in a dry and temperate area.

## 9. TECHNICAL SERVICES

Technical advice, custom CAD drawings, and additional information can be obtained by contacting Stego or by visiting the website.

**Email:** [contact@stegoindustries.com](mailto:contact@stegoindustries.com)

**Contact Number:** (877) 464-7834

**Website:** [stegoindustries.com](https://stegoindustries.com)

## 10. FILING SYSTEMS: [stegoindustries.com](https://stegoindustries.com)





# DRAGOSEAL® TAPE

A STEGO INDUSTRIES, LLC INNOVATION | VAPOR RETARDERS 07 26 00, 03 30 00 | VERSION: MAY 28, 2024

## 1. PRODUCT NAME

**DRAGOSEAL TAPE**

## 2. MANUFACTURER

Stego Industries, LLC  
 216 Avenida Fabricante, Suite 101  
 San Clemente, CA 92672  
 Sales, Technical Assistance  
 Ph: (877) 464-7834  
 contact@stegoindustries.com  
 stegoindustries.com



## 3. PRODUCT DESCRIPTION

**USES:** DragoSeal Tape is a low permeance, solvent resistant tape designed for protective sealing, seaming, splicing, and patching applications. It is engineered to adhere to a variety of surfaces and is ideal for sealing Drago® Wrap seams.

**COMPOSITION:** DragoSeal Tape is a multi-layered plastic extrusion that combines uniquely designed materials with only high grade, prime, virgin resins, and a solvent resistant blend of synthetic rubber and resins.

**SIZE:** DragoSeal Tape is 4" x 50'. DragoSeal Tape ships 6 rolls in a case.

## 4. TECHNICAL DATA

**TABLE 4.1: PHYSICAL PROPERTIES OF DRAGOSEAL TAPE**

PROPERTY	TEST	RESULTS
Dimensions		4" x 50'
Total Thickness		26 mil
Color		Grey
Material		Engineered film and synthetic rubber blend
Permeance	ASTM F1249	<0.02 perms (26 mil)
Adhesion to Steel	ASTM D1000	12.5 lbf/in width
Chemical Resistance (TCE, PCE, Toluene, Xylene)	ASTM D471 / D543	No significant change to mass or volume
Installation Temperature		40°F / 110°F
In Service Temperature Range		-20°F / 140°F
VOC Content		No VOCs, 100% solids

Note: perm unit = grains/(ft<sup>2</sup>\*hr\*in-Hg)

## DRAGOSEAL TAPE

A STEGO INDUSTRIES, LLC INNOVATION | VAPOR RETARDERS 07 26 00, 03 30 00 | VERSION: MAY 28, 2024

### 5. INSTALLATION

Cut DragoSeal Tape with a utility knife or scissors before removing the release liner for easier cutting. DragoSeal Tape should be installed between 40°F and 110°F. In temperatures below 40°F, take extra care to remove moisture or frost from the area of adhesion. Ensure that the entirety of all seams are taped with applied pressure to allow for maximum and continuous adhesion.

**SEAMS:** Overlap Drago Wrap a minimum of 12 inches and seal with DragoSeal Tape. Make sure the area of adhesion is free from dust, moisture and frost to allow for maximum adhesion.

**PIPE PENETRATION SEALING:**

- Install Drago Wrap around pipe by slitting/cutting material.
- If void space is minimal, seal around the base of the pipe using either DragoSeal Tape, Drago® Sealant and Drago® Sealant Form, or Drago® Mastic.

**DETAIL PATCH FOR PIPE PENETRATION SEALING:**

- Cut a piece of Drago Wrap that creates a 6 inch overlap around all edges of the void space at the base of the pipe.
- Cut an "X" slightly smaller than the size of the pipe diameter in the center of the detail patch.
- Slide detail patch over pipe, secure tightly.
- Tape down all sides of detail patch using DragoSeal Tape.
- Seal around the base of the pipe using either DragoSeal Tape, Drago Sealant and Drago Sealant Form, or Drago Mastic.

Review Drago Wrap's complete installation instructions prior to installation.

### 6. AVAILABILITY & COST

DragoSeal Tape is available through our network of building supply distributors. For current cost information, contact your local Drago distributor or Stego® Sales Representative.

### 7. WARRANTY

Stego believes to the best of its knowledge, that specifications and recommendations herein are accurate and reliable. However, since site conditions are not within its control, Stego does not guarantee results from the use of the information provided herein. Stego does offer a limited warranty on Drago Wrap. Please see [stegoindustries.com/legal](https://stegoindustries.com/legal)

### 8. MAINTENANCE

Store DragoSeal Tape in a dry and temperate area.

### 9. TECHNICAL SERVICES

Technical advice, custom CAD drawings, and additional information can be obtained by contacting Stego or by visiting the website.

**Email:** [contact@stegoindustries.com](mailto:contact@stegoindustries.com)

**Contact Number:** (877) 464-7834

**Website:** [stegoindustries.com](https://stegoindustries.com)

### 10. FILING SYSTEMS: [stegoindustries.com](https://stegoindustries.com)





# DRAGOTACK® TAPE

A STEGO INDUSTRIES, LLC INNOVATION | VAPOR RETARDERS 07 26 00, 03 30 00 | VERSION: MAY 28, 2024

## 1. PRODUCT NAME

**DRAGOTACK TAPE**

## 2. MANUFACTURER

Stego Industries, LLC  
 216 Avenida Fabricante, Suite 101  
 San Clemente, CA 92672  
 Sales, Technical Assistance  
 Ph: (877) 464-7834  
 contact@stegoindustries.com  
**stegoindustries.com**



## 3. PRODUCT DESCRIPTION

**USES:** Dragotack Tape is a solvent-resistant, double-sided adhesive strip used to bond and seal Drago® Wrap to concrete, masonry, wood, metal, and other surfaces. Dragotack Tape is a flexible and moldable material to allow for a variety of applications and installations.

**COMPOSITION:** Dragotack Tape is made from a solvent-resistant blend of synthetic rubber and resins.

**SIZE:** Dragotack Tape is 2" x 50'. Dragotack Tape ships 12 rolls in a case.

## 4. TECHNICAL DATA

**TABLE 4.1: PHYSICAL PROPERTIES OF DRAGOTACK TAPE**

PROPERTY	TEST	RESULTS
Dimensions		2" x 50'
Total Thickness		30 mil
Color		Grey
Material		Synthetic rubber blend
Permeance	ASTM F1249	0.03 perms (30 mil)
Adhesion to Steel	ASTM D1000	12.5 lbs/in width
Chemical Resistance (TCE, PCE, Toluene, Xylene)	ASTM D471 / D543	No significant change to mass or volume.
Installation Temperature		40°F / 110°
In Service Temperature Range		-20°F / +140°F
VOC Content		No VOCs, 100% solids

Note: perm unit = grains/(ft<sup>2</sup>\*hr\*in-Hg)

# DRAGOTACK TAPE

A STEGO INDUSTRIES, LLC INNOVATION | VAPOR RETARDERS 07 26 00, 03 30 00 | VERSION: MAY 28, 2024

## 5. INSTALLATION

**TO WALLS AND FOOTINGS:** Make sure the area of adhesion is free of dust, dirt, debris, moisture, and frost to allow maximum adhesion. Remove release liner on one side and stick to desired surface. When ready to apply Drago Wrap, remove the exposed release liner and press Drago Wrap firmly against DragoTack Tape to secure.

Cut DragoTack Tape using a utility knife or scissors. Cut DragoTack Tape before removing the release liner for easier cutting. Install DragoTack Tape between 40°F and 110°F.

Review Drago Wrap's complete installation instructions prior to installation.

## 6. AVAILABILITY & COST

DragoTack Tape is available nationally through our network of building supply distributors. For current cost information, contact your local Drago distributor or Stego® Sales Representative.

## 7. WARRANTY

Stego believes to the best of its knowledge, that specifications and recommendations herein are accurate and reliable. However, since site conditions are not within its control, Stego does not guarantee results from the use of the information provided herein. Stego does offer a limited warranty on Drago Wrap. Please see [stegoindustries.com/legal](https://stegoindustries.com/legal)

## 8. MAINTENANCE

Store DragoTack Tape in a dry and temperate area.

## 9. TECHNICAL SERVICES

Technical advice, custom CAD drawings, and additional information can be obtained by contacting Stego or by visiting the website.

**Email:** [contact@stegoindustries.com](mailto:contact@stegoindustries.com)

**Contact Number:** (877) 464-7834

**Website:** [stegoindustries.com](https://stegoindustries.com)

## 10. FILING SYSTEMS: [stegoindustries.com](https://stegoindustries.com)

