12074 FLATLANDS AVENUE P/O LOT 1 SITE
35 INSPIRATION LANE
F/K/A 12074 FLATLANDS AVENUE
KINGS COUNTY
BROOKLYN, NEW YORK

SITE MANAGEMENT PLAN

NYSDEC Site Number: C224353

Prepared for:

Innovative Urban Living, LLC
IUV Phase 1B Owner, LLC
IUV Phase 1B LIHTC Owner, LLC
IUV Phase 1B Housing Development Fund Corporation
c/o Gotham Organization
111 Fifth Avenue, 9th Floor
New York, New York 10016

Prepared by:

Langan Engineering, Environmental, Surveying,
Landscape Architecture and Geology, D.P.C.
300 Kimball Drive, Floor 4
Parsippany, New Jersey 07054
973-560-4900

Revisions to Final Approved Site Management Plan:

Revision No.	Date Submitted	Summary of Revision	NYSDEC Approval Date

JULY 2026

LANGAN

CERTIFICATION STATEMENT

I, Ronald D. Boyer, certify that I am currently a NYS registered professional engineer and that this Site Management Plan was prepared in accordance with all applicable statutes and regulations and in substantial conformance with the DER Technical Guidance for Site Investigation and Remediation (DER-10) and Green Remediation (DER-31).

Ronald D. Boyer RONALD D. BOYER, PE

7/31/2026 DATE

\\Langan.com\data\PAR\data8\100688801\Project Data_Discipline\Environmental\Reports\100688803 - Phase 1B\2026-07 - SMP\12074 Flatlands Avenue SMP (FINAL REVISED 2026-07-31)_text.docx

TABLE OF CONTENTS

12074 FLATLAND AVENUE P/O LOT 1 SITE
KINGS COUNTY
BROOKLYN, NEW YORK

SITE MANAGEMENT PLAN

Section	Description	Page
ES	EXECUTIVE SUMMARY	8
1.0	Introduction	10
1.1	General	10
1.2	Revisions and Alterations	12
1.3	Notifications	12
2.0	SUMMARY OF PREVIOUS INVESTIGATIONS AND REMEDIAL ACTIONS	14
2.1	Site Location and Description	14
2.2.1	Land Use	15
2.2.2	Geology	16
2.2.3	Hydrogeology	16
2.3	Investigation and Remedial History	16
2.4	Remedial Action Objectives	24
	Groundwater	24
	Soil	24
	Soil Vapor	24
2.5	Remaining Contamination	24
2.5.1	Soil	24
2.5.2	Groundwater	25
2.5.3	Soil Vapor	27
3.0	INSTITUTIONAL AND ENGINEERING CONTROL PLAN	28
3.1	General	28
3.2	Institutional Controls	29
3.3	Engineering Controls	30
3.3.1	Monitoring Wells	30
4.0	Monitoring and sampling plan	31
4.1	General	31
4.2	Site – wide Inspection	32
4.3	Post-Remediation Groundwater Monitoring and Sampling	33

4.3.1 Monitoring Well Installation 34
4.3.2 Groundwater Sampling 34
4.3.3 Monitoring and Sampling Protocol 36
4.4 Soil Vapor Intrusion Evaluation 36
5.0 OPERATION AND MAINTENANCE PLAN 37
5.1 General 37
6.0 PERIODIC ASSESSMENTS/EVALUATIONS 37
6.1 Climate Change Vulnerability Assessment 37
6.2 Green Remediation Evaluation 38
6.2.1 Environmental Footprint Analysis 39
6.2.2 Green Remediation Principles and Best Management Practices 39
6.2.3 Timing of Green Remediation Evaluations 42
6.2.4 Frequency of System Checks, Sampling and Other Periodic Activities 42
6.2.5 Metrics and Reporting 42
6.3 Remedial System Optimization 43
7.0 REPORTING REQUIREMENTS 44
7.1 Site Management Reports 44
7.2 Periodic Review Report 46
7.2.1 Certification of Institutional and Engineering Controls 48
7.3 Corrective Measures Work Plan 50
7.4 Remedial System Optimization Report 50
8.0 REFERENCES 51

List of Tables

Table 1A	Soil Cleanup Objectives
Table 1B	Groundwater Cleanup Objectives
Table 2	Documentation Endpoint Soil Sample Analytical Results
Table 3	Remedial Investigation Groundwater Analytical Results
Table 4A	Soil Vapor Analytical Results
Table 4B	Methane Monitoring Results
Table 5	Proposed Monitoring Well Construction Summary

List of Figures

Figure 1	Site Location Map
Figure 2	Site Plan
Figure 3	Remedial Excavation Extents – Subsurface Profiles A-A' & B-B'
Figure 4	Documentation Sample Analytical Results
Figure 5	Remedial Investigation Groundwater Analytical Results and Potentiometric Surface Map
Figure 6	Soil Vapor Analytical Results
Figure 7	Proposed Monitoring Well Location Map
Figure 8	Truck Route Map

List of Appendices

Appendix A – Environmental Easement
Appendix B – List of Site Contacts
Appendix C – Soil Boring and Monitoring Well Construction Logs
Appendix D – Excavation Work Plan
Appendix E - Quality Assurance Project Plan
Appendix F – Green and Sustainable Remediation Footprint Analysis and Climate Screening Checklist
Appendix G – Health and Safety Plan
Appendix H – Generic NYSDEC Community Air Monitoring Plan
Appendix I – Site Management Forms
Appendix J – Remedial System Optimization Report Outline

List of Acronyms

AS	Air Sparging
ASP	Analytical Services Protocol
BCA	Brownfield Cleanup Agreement
BCP	Brownfield Cleanup Program
BMP	Best Management Practice
CERCLA	Comprehensive Environmental Response, Compensation and Liability Act
CAMP	Community Air Monitoring Plan
C/D	Construction and Demolition
CFR	Code of Federal Regulation
CLP	Contract Laboratory Program
COC	Certificate of Completion
CO2	Carbon Dioxide
CP	Commissioner Policy
DER	Division of Environmental Remediation
DUSR	Data Usability Summary Report
EC	Engineering Control
ECL	Environmental Conservation Law
ELAP	Environmental Laboratory Approval Program
ERP	Environmental Restoration Program
EWP	Excavation Work Plan
GHG	Greenhouse Gas
GWE&T	Groundwater Extraction and Treatment
HASP	Health and Safety Plan
IC	Institutional Control
NYSDEC	New York State Department of Environmental Conservation
NYSDOH	New York State Department of Health
NYCRR	New York Codes, Rules and Regulations
O&M	Operation and Maintenance
OM&M	Operation, Maintenance and Monitoring
OSHA	Occupational Safety and Health Administration
OU	Operable Unit
P.E. or PE	Professional Engineer
PFAS	Per- and Polyfluoroalkyl Substances
PID	Photoionization Detector
PRP	Potentially Responsible Party
PRR	Periodic Review Report
QA/QC	Quality Assurance/Quality Control
QAPP	Quality Assurance Project Plan
QEP	Qualified Environmental Professional
RAO	Remedial Action Objective
RAWP	Remedial Action Work Plan
RCRA	Resource Conservation and Recovery Act

RI/FS	Remedial Investigation/Feasibility Study
ROD	Record of Decision
RP	Remedial Party
RSO	Remedial System Optimization
SAC	State Assistance Contract
SCG	Standards, Criteria and Guidelines
SCO	Soil Cleanup Objective
SMP	Site Management Plan
SOP	Standard Operating Procedures
SOW	Statement of Work
SPDES	State Pollutant Discharge Elimination System
SSD	Sub-slab Depressurization
SVE	Soil Vapor Extraction
SVI	Soil Vapor Intrusion
TAL	Target Analyte List
TCL	Target Compound List
TCLP	Toxicity Characteristic Leachate Procedure
USEPA	United States Environmental Protection Agency
UST	Underground Storage Tank
VCA	Voluntary Cleanup Agreement
VCP	Voluntary Cleanup Program

ES EXECUTIVE SUMMARY

The following provides a brief summary of the controls implemented for the Site, as well as the inspections, monitoring, maintenance and reporting activities required by this Site Management Plan:

Site Identification: 12074 Flatlands Avenue p/o Lot 1 Site
NYSDEC BCP Site No. C224353
35 Inspiration Lane
F/K/A 12074 Flatlands Avenue
Brooklyn, New York

Institutional Controls:	1. The property may be used for Restricted Residential as described in 6 NYCCR Part 375-1.8(g)(2)(ii), Commercial as described in 6 NYCCR Part 375-1.8(g)(2)(iii) and Industrial as described in 6 NYCRR Part 375-1.8(g)(2)(iv);
	2. All ECs must be operated and maintained as specified in this SMP;
	3. All ECs must be inspected at a frequency and in a manner defined in the SMP;
	4. The use of groundwater underlying the property is prohibited without necessary water quality treatment as determined by the NYSDOH or the New York City Department of Health to render it safe for use as drinking water or for industrial purposes, and the user must first notify and obtain written approval to do so from the Department;
	5. Groundwater and other environmental or public health monitoring must be performed as defined in this SMP;
	6. Data and information pertinent to site management must be reported at the frequency and in a manner as defined in this SMP;
	7. All future activities that will disturb remaining contaminated material must be conducted in accordance with this SMP;
	8. Monitoring to assess the performance and effectiveness of the remedy must be performed as defined in this SMP;
	9. Operation, maintenance, monitoring, inspection, and reporting of any mechanical or physical component of the remedy shall be performed as defined in this SMP;

Institutional Controls:	10. Access to the site must be provided to agents, employees or other representatives of the State of New York with reasonable prior notice to the property owner to assure compliance with the restrictions identified by the Environmental Easement;
	11. The potential for vapor intrusion must be evaluated for any new buildings developed in the area within the IC boundaries, and any potential impacts that are identified must be monitored or mitigated if present in exceedance of the NYSDOH Soil Vapor Intrusion Matrix monitoring and/or mitigation threshold values;
	12. Vegetable gardens and farming on the site are prohibited;
	13. An evaluation shall be performed to determine the need for further investigation and remediation should large scale redevelopment occur, if any of the existing structures are demolished, or if the subsurface is otherwise made accessible;
	14. All ECs must be inspected at a frequency and in a manner defined in the SMP.
Engineering Controls:	1. Monitoring Wells

Inspections:	Frequency
1. Site Wide Inspection	Annually
Monitoring:	
1. Post-Remediation Groundwater Monitoring	Biannually, re-evaluated after year 1
2. Soil Vapor Intrusion Evaluation for New Buildings	Upon a change in use of the property that will result in occupancy of a previously unoccupied building or initial occupancy of a new building.
Maintenance:	
1. Monitoring Wells	As needed
Reporting:	
1. Performance Monitoring Groundwater Analytical Data	Annually, with the PRR
2. Site-Wide Observations	Annually
3. Certification / Periodic Review Report	Annually

Further descriptions of the above requirements are provided in detail in the latter sections of this Site Management Plan.

1.0 INTRODUCTION

1.1 General

This Site Management Plan (SMP) is a required element of the remedial program for the approximately 2.084-acre 12074 Flatlands Avenue p/o Lot 1 Site located in Brooklyn, New York (hereinafter referred to as the "Site"). The Site location is presented on Figure 1. The Site is currently in the New York State (NYS) Brownfield Cleanup Program (BCP), Site No. C224353, which is administered by New York State Department of Environmental Conservation (NYSDEC or Department).

Innovative Urban Living, LLC entered into a Brownfield Cleanup Agreement (BCA) on 25 May 2022 with the NYSDEC to remediate the Site. A summary of the BCA amendments is presented below.

- An initial BCA amendment was executed on 26 October 2023 to add additional Requestor - IUV Phase 1B Owner, LLC (as the beneficial owner).
- A second BCA Amendment executed on 30 January 2025 to add IUV Phase 1B LIHTC Owner LLC as a new second prospective beneficial owner and IUV Phase 1B Housing Development Fund Corporation as a nominal title owner were added as another party. This second BCA amendment also identified the official revised Site address as 35 Inspiration Lane (formerly known as [F/K/A] 12074 Flatlands Avenue).
- A third BCA Amendment was submitted May 15, 2025, which stated on March 21, 2025, two ownership transfers occurred for the BCP site. First, Christian Cultural Center, Inc. transferred ownership to Urban Living Alternatives, LLC ("Urban Living") and then Urban Living transferred ownership to IUV Phase 1B Housing Development Fund Corporation ("IUV 1B HDFC"), as the nominee for both IUV Phase 1B Owner, LLC ("IUV 1B Owner") and IUV Phase 1B LIHTC Owner, LLC ("IUV 1B LIHTC"). IUV 1B HDFC is the nominal title owner, and IUV 1B Owner and IUV 1B LIHTC are both beneficial owners. IUV 1B LIHTC, and IUV 1B HDFC are all parties to the Brownfield Cleanup Agreement.

A figure showing the boundaries of this Site is provided in Figure 2. The boundaries of the Site are more fully described in the metes and bounds site description that is part of the Environmental Easement provided in Appendix A.

After completion of the remedial work between 24 March 2025 and 20 January 2026, some contamination was left at this site, which is hereafter referred to as "remaining

contamination". Institutional and Engineering Controls (ICs and ECs) have been incorporated into the site remedy to control exposure to remaining contamination to ensure protection of public health and the environment. An Environmental Easement granted to the NYSDEC and recorded with the Kings County Clerk requires compliance with this SMP and all ECs and ICs placed on the site. The environmental easement for the Site was executed by the Department on 17 September 2025 and recorded with the NYC Office of the City Register on 26 September 2025. The City Register File number for the filing is 2025000264211.

This SMP was prepared to manage remaining contamination at the Site, which is located between 15 and 22 feet bgs beneath the base of the redevelopment excavations, until the Environmental Easement is extinguished in accordance with ECL Article 71, Title 36. This plan has been approved by the NYSDEC, and compliance with this plan is required by the grantor of the Environmental Easement and the grantor's successors and assigns. This SMP may only be revised with the approval of the NYSDEC.

It is important to note that:

- This SMP details the site-specific implementation procedures that are required by the Environmental Easement. Failure to properly implement the SMP is a violation of the Environmental Easement, which is grounds for revocation of the Certificate of Completion (COC); and
- Failure to comply with this SMP is also a violation of Environmental Conservation Law, 6 NYCRR Part 375 and the [BCA (Index #C224353-05-22; BCP Site No. C224353) for the site, and thereby subject to applicable penalties.

All reports associated with the site can be viewed by contacting the NYSDEC or its successor agency managing environmental issues in New York State. A list of contacts for persons involved with the site is provided in Appendix B of this SMP.

This SMP was prepared by Langan Engineering, Environmental, Surveying, Landscape Architecture and Geology, D.P.C. (Langan), on behalf of the Volunteer, in accordance with the requirements of the NYSDEC's DER-10 ("Technical Guidance for Site Investigation and Remediation"), dated 3 May 2010, and the guidelines provided by the NYSDEC. This SMP addresses the means for implementing the ICs and/or ECs that are required by the Environmental Easement for the site.

1.2 Revisions and Alterations

Revisions and alterations to this plan will be proposed in writing to the NYSDEC's project manager. The NYSDEC can also make changes to the SMP or request revisions from the remedial party. Revisions will be necessary upon, but not limited to, the following occurring: a change in media monitoring requirements, post-remedial removal of contaminated soil, or other significant change to the Site conditions. All approved alterations must conform with Article 145 Section 7209 of the Education Law regarding the application of professional seals and alterations. For example, any changes to as-built drawings must be stamped by a New York State Professional Engineer. In accordance with the Environmental Easement for the site, the NYSDEC project manager will provide a notice of any approved changes to the SMP and append these notices to the SMP that is retained in its files.

1.3 Notifications

Notifications will be submitted by the property owner to the NYSDEC, as needed, in accordance with this SMP and NYSDEC's DER – 10 for the following reasons:

1. 60-day advance notice of any proposed changes in Site use that are required under the terms of the BCA, 6 NYCRR Part 375, and/or Environmental Conservation Law.

2. 7-day advance notice of any field activity associated with the remedial program.

3. 15-day advance notice of any proposed ground-intrusive activity pursuant to the Excavation Work Plan. If the ground-intrusive activity qualifies as a change of use as defined in 6 NYCRR Part 375, the above mentioned 60-day advance notice is also required.

4. Notice within 48 hours of any damage or defect to the foundation, structures or EC that reduces or has the potential to reduce the effectiveness of an EC, and likewise, any action to be taken to mitigate the damage or defect.

5. Notice within 48 hours of any non-routine maintenance activities.

6. Verbal notice by noon of the following day of any emergency, such as a fire; flood; or earthquake that reduces or has the potential to reduce the effectiveness of ECs in place at the site, with written confirmation within 7 days that includes a summary of actions taken, or to be taken, and the potential impact to the environment and the public.

7. Follow-up status reports on actions taken to respond to any emergency event requiring ongoing responsive action submitted to the NYSDEC within 45 days describing and documenting actions taken to restore the effectiveness of the ECs.

Any change in the ownership of the site or the responsibility for implementing this SMP will include the following notifications:

8. At least 60 days prior to the change, the NYSDEC will be notified in writing of the proposed change. This will include a certification that the prospective purchaser/Remedial Party has been provided with a copy of the BCA, and all approved work plans and reports, including this SMP.

9. Within 15 days after the transfer of all or part of the site, the new owner's name, contact representative, and contact information will be confirmed in writing to the NYSDEC.

The table below includes contact information for the above notifications. The information on this table will be updated as necessary to provide accurate contact information. A full listing of site-related contact information is provided in Appendix B.

Name*	**Contact Information**	**Required Notification***
Rafi Alam NYSDEC Project Manager	Telephone: (518) 402-8606 Email: Rafi.Alam@dec.ny.gov	All Notifications
Lisa Gorton NYSDEC Project Manager's Supervisor	Telephone: (518) 402-9574 Email: Lisa.Gorton@dec.ny.gov	All Notifications
Jim Sullivan NYSDOH Project Manager	Telephone: (518) 402-5584 Email: beei@health.ny.gov	Notifications 4, 6, and 7

* Note: Notifications are subject to change and will be updated as necessary.

** Note: Numbers in this column reference the numbered bullets in the notification list in this section.

2.0 SUMMARY OF PREVIOUS INVESTIGATIONS AND REMEDIAL ACTIONS

2.1 Site Location and Description

The Site is located in Brooklyn, Kings County, New York and is identified as Block 4434 and Lot 1 on the Kings County Tax Map. The Site is an approximately 90,780-square-foot (approximately 2.084-acre) area and is bounded by Flatlands Avenue followed by an automobile dismantling company and used automobile parts business, medical offices, and the Oasis Hotel to the north, a twelve-story multi-family residential apartment building to the south, a twelve-story multi-family residential apartment building and Block 4434 Lot 10 (BCP Site No. C224290) to the east, and Block 4434 Lot 100, which is being used as a construction logistics zone for the Site, followed by the Christian Cultural Center (CCC) building and the surrounding asphalt-paved parking lot to the west. The boundaries of the site are more fully described in Appendix A – Environmental Easement. A Site Plan is included as Figure 2. The nominee title owner of the Site at the time of issuance of this SMP is:

IUV Phase 1B Housing Development Fund Corporation
c/o Christian Cultural Center
12020 Flatlands Avenue
Brooklyn, NY 11207

The beneficial owners are:

IUV Phase 1B Owner, LLC &
IUV Phase 1B LIHTC Owner, LLC
c/o Gotham Organization, Inc.
111 Fifth Avenue, 9th Floor
New York, NY 10003

The operators of the Site at the time of issuance of this SMP are:

Innovative Urban Living, LLC
IUV Phase 1B Owner, LLC
IUV Phase 1B LIHTC Owner, LLC
111 Fifth Avenue, 9th Floor
New York, NY 10003

2.2.1 Land Use

After remediation and upon completion of construction, the development will consist of two mixed-use commercial/residential buildings in the northern and southern portion of the Site with a single cellar level with an approximate area of 72,269 square feet across the majority of the Site footprint. A publicly accessible private roadway will be constructed at street level within the western and central portions of the Site. The proposed end-use of the development is consistent with existing zoning regulations.

The following is a summary of adjacent property usage:

Direction	Adjacent Properties			Surrounding Properties
	Block No.	Lot No.	Description	
North	4411 4410	24 & 34 29	Flatlands Avenue followed by an automobile dismantling company and used automobile parts business, medical offices, and the Oasis Hotel	Flatlands Avenue followed by industrial / manufacturing and commercial buildings
East	4430	10 & 60	BCP Site No. C224290 (12096 Flatlands Avenue) and a twelve-story multi-family residential building	Pennsylvania Avenue followed by a vacant landscaped lot and the northern courtyard of a twenty-story residential building (part of the Starrett City Complex)
South	4431	70	A twelve-story multi-family residential building	Residential building complexes
West	4434	100	Vacant Lot used as a construction logistics zone for the Site	CCC building, commercial buildings, Fresh Creek Nature Preserve

2.2.2 Geology

According to the Boundary and Topographic Survey prepared by Control Point Associates Inc. signed 14 October 2021, pre-construction elevations around the Site sloped downward from south (elevation [el] 24.45 feet) to north (el 12.5 feet). All elevations are in North American Vertical Datum of 1988 (NAVD88).

The subsurface strata at the Site consisted of fill generally comprised of brown, gray, or black fine to coarse sand with varying proportions of fine to coarse gravel, silt, clay, ash, and miscellaneous debris including brick, concrete, asphalt, wood, slag, and glass, to depths ranging from approximately 8.5 to at least 26 feet below ground surface (bgs). A discontinuous ash layer was also encountered at depths ranging from 10 to 25 feet below existing grade throughout the Site footprint.

Based on subsurface observations made during environmental and geotechnical investigations completed by Langan between 2018 and 2023, fill is underlain by a native brown to dark brown or dark grey sand unit with varying proportions of gravel, silt and clay that extended to the termination depths of all borings, which ranged from 20 to 77 feet below grade.

A geologic cross section is shown in Figure 3. Site specific boring logs are provided in Appendix C.

2.2.3 Hydrogeology

Groundwater was encountered between el 2.01 to el 3.5 feet NAVD88 (between 10.48 and 19.73 feet below ground surface) during the 2023 RI. Based on area topography, observed water level measurements, and the proximity of the Site to Fresh Creek, groundwater flow is to the south toward Fresh Creek and Jamaica Bay. Groundwater contours are shown on Figure 5.

2.3 Investigation and Remedial History

The following environmental assessment and investigation reports have been prepared for the Site:

- *Fresh Creek Estates, Technical Memorandum to the Draft Environmental Impact Statement (DEIS)*, prepared by AKRF, Inc., dated June 1991;
- *Subsurface Investigation and Report*, prepared by Soil Engineering Services, Inc. (SESI), dated March 1994;

- *Phase I Environmental Site Assessment (ESA)*, prepared by Soil Mechanics Environmental Services (SMES), dated July 1997; and,
- *Phase I ESA for Flatlands Ave. & Pennsylvania Ave.*, prepared by Soil Mechanics Environmental Services (SMES), dated April 2003.

In addition, Langan prepared the following environmental reports for the Site:

- *Phase II Environmental (EI) Investigation Report* dated 30 May 2018;
- *Phase I ESA* dated 24 August 2018;
- *Remedial Investigation Work Plan* dated 20 October 2022;
- *Phase I ESA* dated 5 December 2022;
- 60-Day Advance Notice of Site Change of Use to temporary bus parking use, prepared by Knauf Shaw LLP, dated 21 June 2023;
- *Remedial Investigation Report* dated 1 December 2023;
- *Remedial Action Work Plan* dated 1 May 2024;
- *Phase I ESA* dated 18 September 2024; and,
- *Final Engineering Report* dated 22 May 2026.

Summaries of environmental findings of these reports are provided below.

Fresh Creek Estates, Technical Memorandum to the Draft Environmental Impact Statement (DEIS) (AKRF 1991)

According to the Technical Memorandum, AKRF, Inc. (AKRF) prepared a comprehensive environmental assessment of the proposed Fresh Creek Estates site, which included the Site and a number of surrounding properties. The Technical Memorandum identified that the Site was originally marshlands and was landfilled during the early 1900's using ash and residue from a city solid waste incinerator. Potential subsurface impacts due to historical site use and historic filling operations were investigated within the current extents of the Site by completion of an electromagnetic survey, advancement of test pits and a soil boring, and collection of soil samples. Based on the sample location plan provided, two test pits and one soil boring were installed on the central portion of former Block 4434, Lot 1, which includes the current extents of the Site.

The Technical Memorandum concluded that the Site is underlain by unconsolidated fill containing varying amounts of sand, gravel, clay, bricks, organic material, concrete, glass, and asphalt. Soil sample analytical results revealed TPH in soil at concentrations ranging from 91 parts-per-million (ppm) to 25,900 ppm over the entire proposed Fresh Creek

Estates development site, which included parcels other than the Site. However, laboratory analytical packages and summary tables were not provided for review; as such, subsurface soil and groundwater impacts identified during the 1991 environmental investigation could not be directly correlated to the Site.

The AKRF Technical Memorandum was reviewed by Soil Mechanics Environmental Services (SEMS) and a summary of the AKRF Technical Memorandum investigation and findings was included in the SEMS April 2003 Phase I ESA, as discussed below. According to the 2003 Phase I ESA, a soil vapor survey was completed by AKRF within the extents of the former gasoline station adjacent to the Site. Results of the soil vapor survey did not indicate elevated VOCs with the exception of methane, which was presumed to be associated from organic material in historic fill and/or underlying marsh deposits.

Subsurface Investigation and Report (SESI 1994)

SESI completed a subsurface investigation that included installation of eight soil borings to depths that ranged from 26- to 51.5-feet below existing grade at the entire CCC property for the purposes of evaluating geotechnical conditions and providing recommendations for foundation design and general Site development. The report documented that the Site is underlain by a layer of miscellaneous fill of unspecified thickness followed by native medium-dense medium to fine grained sand. As the report provided was not complete and a geotechnical boring location plan was not provided for review, subsurface conditions could not be correlated to the Site.

Phase I Environmental Site Assessment (SMES 1997)

SMES prepared a Phase I ESA on behalf of Legacy General Contracting Corp. for the intent of constructing an approximately 100,000-square foot two-story building, which presumably became the current CCC building. Based on the descriptions of the subject property in this report, and adjacent properties in the SMES Phase I ESA report, it appears that this Phase I ESA was not completed for the Site.

Phase I Environmental Site Assessment for Flatlands Ave. & Pennsylvania Ave. (SMES 2003)

The April 2003 SMES Phase I ESA was completed for the entire CCC property, including the current extents of the Site.

The Phase I ESA did not specifically identify RECs, but recommended completion and adherence to a Health and Safety Plan (HASP) and installation of a soil capping system and noted that a methane mitigation system may be required as part of any future building construction. SMES also recommended that future activities on the subject property be conducted under the oversight of the New York City Department of Environmental Protection (NYCDEP) or NYSDEC, and that all underground storage tanks (USTs) encountered during redevelopment be removed in accordance with all applicable laws. The report also identified that proper removal of all miscellaneous waste that was observed on the subject property including an abandoned crane, rubber tires, and demolition debris, and completion of a groundwater investigation to evaluate for potential impacts from hydraulically upgradient properties of concern, would be required.

Phase II Environmental Investigation Report (Langan 2018)

Langan conducted a Phase II EI for the Site in 2018 for the Volunteer. Results of the investigation were summarized in the 30 May 2018 Phase II Environmental Investigation Report, which was submitted to NYSDEC in the BCP Application. The validated analytical results of this investigation are also provided in Tables 3 through 5 and summarized on Figures 5A, 5B, 6, and 7 of the RIR.

The investigation included excavation of two test pits, installation of five soil borings, two permanent groundwater monitoring wells, and collection of soil and groundwater samples for laboratory analysis. Temporary soil vapor/methane monitoring points were installed adjacent to two soil borings and methane concentrations were monitored over a 5-minute period at each location. Evidence of petroleum impacts (i.e., elevated PID readings, odor, or staining) were not observed in any of the soil borings or test pits completed. Fill material was observed within all soil borings and test pits.

Soil analytical results revealed SVOCs were detected in the eastern portion of the site in surficial and in the deep soil samples collected from the fill material at concentrations exceeding the Unrestricted Use SCOs and Restricted-Residential RUSCOs. Pesticides and polychlorinated biphenyls (PCBs) were detected at concentrations exceeding the Unrestricted Use SCOs in surficial and deep samples collected from fill material. Metals were detected at concentrations exceeding the Restricted-Residential RUSCOs at all five soil boring locations. Exceedances of the Restricted-Residential RUSCOs for metals were detected in surficial soil in one boring locations, and the remaining exceedances were detected in deeper samples between 8 and 18 feet below grade.

Groundwater analytical results revealed the VOC methyl tert-butl ethyl and the SVOC 3&4 methylphenol were detected in exceedance of the Standards and Guidance Values for Class GA water (SGVs) in LMW-4. The PCB Aroclor 1254 and total PCBs were detected in exceedance of the NYSDEC SGVs in LMW-6. Metals including total and dissolved iron, total lead, total and dissolved manganese, total and dissolved selenium, and total and dissolved sodium were detected in exceedance of the SGVs in both LMW-4 and LMW-6. No pesticides were detected in exceedance of the SGVs.

Two temporary methane monitoring points were installed and methane concentrations were monitored using a Honeywell MultiRae meter over a period of 5 minutes. No measurable methane concentrations were detected over the 5-minute period at the temporary point installed at the Site or at any of the other seven temporary points installed across the entire CCC site footprint.

Based on the results of the May 2018 Phase II EI, two Areas of Concern (AOCs) related to historical Site operations were identified: former on-Site automobile junkyard (AOC-1) and the presence of contaminated fill material of an unknown origin and incinerator ash throughout the Site that filled the prior on-Site marshland (AOC-2), which are discussed in detail in the RAWP.

Phase I Environmental Assessment Report (Langan 2018)

Langan conducted a Phase I ESA for the Site dated 24 August 2018 on behalf of the Volunteer for the Site. The following RECs were identified in Langan's 2018 Phase I ESA:

- REC-1: Former On-Site Automobile Junkyard
- REC-2: Presence of Historic Fill

Automobile wrecking operations were identified at the Site from 1967 through 1980. Based on the review of the reports discussed above, the area was reportedly filled with ash and waste from the city solid waste incinerator. Subsurface observations made during environmental and geotechnical investigations completed by Langan in 2018 included the presence of fill material up to at least 25 feet below grade.

The Phase I ESA also identified business environmental risks (BERs) including the potential presence of undocumented USTs as a result of historical Site operations and potential impacts from current and historical operations conducted at adjacent and nearby properties involving automobile junkyards/dismantling facilities, automobile repair shops, and gasoline filling stations.

BCP Application and BCA (2022)

The Volunteer submitted a BCP Application to NYSDEC for the Site on 2 March 2022. The BCA was executed on 25 May 2022.

Remedial Investigation Work Plan (Langan 2022)

A Remedial Investigation Work Plan dated 20 October 2022 was prepared by Langan for the Volunteer. NYSDEC and NYSDOH provided a RIWP comment letter dated 9 August 2022. These comments were subsequently addressed in the revised RIWP dated 10 October 2022 prepared by Langan and approved by the NYSDEC on 23 October 2022.

The scope of work for the RI presented in the RIWP consisted of:

- A geophysical survey throughout accessible areas of the Site;
- Advancement of fifteen soil borings and collection of 48 soil samples (including three duplicate samples);
- Installation of eleven permanent monitoring wells and collection of fourteen groundwater samples (including one duplicate sample);
- Survey and gauging of monitoring wells to evaluate groundwater elevation and flow directions; and,
- Installation of thirteen soil vapor points and collection of fourteen soil vapor samples (including one duplicate sample) and two ambient air samples.

Remedial Investigation Report (Langan 2023)

A Remedial Investigation Report dated 1 December 2023 was prepared by Langan for the Volunteer to document the investigation completed in accordance with the RIWP.

The 2023 RI revealed that the Site is underlain by a layer of fill to depths ranging from approximately 8.5 to at least 26 feet bgs. An ash layer was also identified within the contaminated fill. The fill layer is underlain by a sand unit with varying proportion of gravel, silt, and clay. Depth to groundwater ranges from about 10.48 and 19.73 (corresponding to between el 2.01 and el 3.5 NAVD88) feet below ground surface. Based on the groundwater elevations recorded during the 2023 RI, groundwater flows to the south.

Soil samples were collected between 0 and 22 feet bgs and analytical results were indicative of contaminated fill present on Site. Exceedances of the Track 1 Unrestricted Use Soil Cleanup Objectives (SCOs), the Protection of Groundwater SCOs, and the Restricted-Residential RUSCOs for analytes associated with contaminated fill, including PAHs, pesticides, PCBs, and metals, were detected within contaminated fill layer.

Groundwater sample analytical results did not identify the presence of pesticides or herbicides at concentrations above the screening and guidance values (SGVs) in samples collected during the 2023 RI. The VOC naphthalene was detected in exceedance of the NYSDEC SGVs within two monitoring wells and impacts may be attributed to historical releases associated with former Site operations as an automobile junkyard. SVOCs were detected in exceedance of the NYSDEC SGVs and were attributed to sediment entrainment of fill material of unknown origin in the sample and are not indicative of any discrete releases to the subsurface. 1,4-Dioxane was detected in exceedance of the NYSDEC SGVs and was attributed to historical automobile junkyard operations. Total and dissolved metals were detected in exceedance of NYSDEC SGVs, although the detections of barium and selenium in groundwater is attributed to a combination of sediment entrainment in the sample and the quality of fill in contact with groundwater at that location and were not considered to be an ongoing source of groundwater contamination. Other metals detected in exceedance of NYSDEC SGVs were identified throughout the Site footprint and are attributed to a combination of sediment entrainment in the sample and naturally occurring background concentrations. PCBs were detected in exceedance of the NYSDEC SGVs in one groundwater sample and was attributed to sediment entrainment in the sample. PFOS and PFOA was detected above the guidance screening level of 10 ng/L in all groundwater samples collected throughout the Site footprint.

Three chlorinated VOCs (cis-1,2-dichloroethylene, tetrachlorethylene [PCE], and vinyl chloride) were detected in exceedance of the NYSDOH Soil Vapor Intrusion Matrix monitoring and/or mitigation threshold values across the Site footprint. Soil vapor sample analytical results also revealed low concentrations of petroleum-related VOCs including BTEX, 1,2,4-trimethylbenzene, and 1,3,5-trimethylbenzene throughout the Site footprint.

60-Day Advance Notice of Site Change of Use (Knauf Shaw LLP 2023)

A 60-Day Advanced Notification of Site Change of Use Form was submitted to the NYSDEC on 21 June 2023. The Site Change of Use submission indicated that the Site is temporarily being used for bus parking on a month-to-month lease. The buses were vacated from the Site prior to the start of the remediation.

Remedial Action Work Plan (Langan 2024)

A Remedial Action Work Plan (RAWP), dated 1 May 2024, was prepared by Langan on behalf of the Volunteer. The RAWP summarized the nature and extent of contamination as determined from data gathered during the RI and to select a remedy that is consistent with the procedures defined in DER-10 and complies with applicable standards, criteria,

and guidance, as well as with applicable federal, state and local laws, regulations and requirements. A Track 1 Unrestricted Use Remedy was selected for the remediation of the Site. A Track 2 Restricted Residential remedy was evaluated as a remedial alternative if a Track 1 remedy could not be achieved.

The Remedial Action Work Plan was approved by NYSDEC in a letter dated 2 May 2024.

Phase I Environmental Site Assessment (Langan 2024).

Langan conducted a Phase I ESA on behalf of the Volunteer dated 18 September 2024 for the Site. The following RECs were identified in Langan's 2024 Phase I ESA:

- REC-1: Former On-Site Automobile Junkyard
- REC-2: Presence of Historic Fill

The Phase I ESA also identified BERs including the potential presence of undocumented USTs as a result of historical Site operations and potential impacts from current and historical operations conducted at adjacent and nearby properties involving automobile junkyards/dismantling facilities, automobile repair shops, and gasoline filling stations.

Final Engineering Report (Langan 2026)

A Final Engineering Report (FER), dated May 2026, was prepared by Langan on behalf of the Volunteer. The FER documents the remedial actions implemented in accordance with the NYSDEC-approved Remedial Action Work Plan (RAWP) for Track 2 Restricted-Residential Use.

Site-wide remedial excavation was performed to 15 feet bgs for the removal of material exceeding the Unrestricted Use SCOs, Protection of Groundwater SCOs, and Restricted-Residential Use RUSCOs across the Site footprint and to 27.5 feet bgs for the removal of eight hazardous lead areas identified during the waste characterization investigation. Additional excavation for foundation construction was performed to between 15 and 22 feet bgs. Deeper localized excavation from 22 to about 27.5 feet bgs occurred for deeper construction foundation elements.

Documentation endpoint soil samples indicate that remaining contamination at the development depth consists of SVOCs, PCBs, and metals exceeding the Unrestricted Use SCOs, Protection of Groundwater SCOs, and/or Restricted-Residential Use RUSCOs.

2.4 Remedial Action Objectives

The Remedial Action Objectives (RAOs) for the Site as listed in the Decision Document dated May 2024 are as follows:

Groundwater

RAOs for Public Health Protection

- Prevent ingestion of groundwater with contaminant levels exceeding drinking water standards.
- Prevent contact with, or inhalation of, volatiles from contaminated groundwater.

RAOs for Environmental Protection

- Restore ground water aquifer to pre-disposal/pre-release conditions, to the extent practicable.
- Remove the source of ground or surface water contamination.

Soil

RAOs for Public Health Protection

- Prevent ingestion/direct contact with contaminated soil.
- Prevent inhalation of or exposure from contaminants volatilizing from contaminants in soil.

RAOs for Environmental Protection

- Prevent migration of contaminants that would result in groundwater or surface water contamination.

Soil Vapor

RAOs for Public Health Protection

- Mitigate impacts to public health resulting from existing, or the potential for, soil vapor intrusion into buildings at a site.

2.5 Remaining Contamination

2.5.1 Soil

A Track 2 Restricted-Residential Use remedy was achieved for the Site. Remaining impacts in soil were documented in endpoint samples collected from beneath the remedial excavations and are located beneath the base of the remedial excavations between 15 and 22 feet bgs.

The 99 documentation samples, in addition to six duplicate samples, were taken throughout the Site extents upon reaching the final development or remedial excavation depths. Laboratory analytical results identified that the remaining contamination below 15 feet bgs consists of SVOCs, PCBs, and metals above the Restricted-Residential RUSCOs. The Part 375 Restricted-Residential SCOs are summarized in Table 1A. Table 2 and Figure 4 summarize the results of all soil samples collected that exceed the Unrestricted Use SCOs, Protection of Groundwater SCOs, and/or the Restricted-Residential RUSCOs at the Site after completion of the remedial action.

The following table summarizes the laboratory analytical results of the remaining contamination:

Analyte	Minimum Detected Concentration above RRSCOs (mg/kg)		Maximum Detected Concentration above RRSCOs (mg/kg)	
SVOCs				
Benzo(a)anthracene	1.45	PE100_20	13.4	PE101_20
Benzo(a)pyrene	1.07	PE66_19.5	10.9	PE101_20
Benzo(b)fluoranthene	1.45	PE51_19.5	9.11	PE101_20
Benzo(g,h,i)perylene	6.16	PE101_20	6.16	PE101_20
Chrysene	4.99	PE55_20	13.8	PE101_20
Dibenzo(a,h)anthracene	0.378	PE51_19.5	2.64	PE101_20
Indeno(1,2,3-cd)pyrene	1.52	PE55_20	5.84	PE101_20
Phenanthrene	6.05	PE90_20	38	PE101_20
PCBs				
Total PCBs	1.04	PE12_15	3.48	PE92_20
Metals				
Arsenic	16.9	PE55_20	29.8	PE90_20
Barium	413	PE38_20	813	PE45_19.5
Cadmium	2.69	PE63_20.5	10.6	PE70_20
Copper	300	PE67_20	391	PE53_20
Cyanide	13.7	PE45_19.5	13.7	PE45_19.5
Lead	401	PE55_20	2,430	PE52_20
Mercury	0.305	PE86_20	34	PE95_19.5

2.5.2 Groundwater

Groundwater samples collected during the 2023 RI revealed the VOC naphthalene was detected above the SGVs in groundwater samples from LMW-15 and LMW-19 on the

northern and eastern sides of the Site, respectively. The VOC tert-butyl methyl ether was detected in the groundwater sample from LMW-4 during the 2018 Phase II EI; however, it was not detected above the SGVs during the 2023 RI. These impacts may be attributed to historical releases associated with former Site operations as an automobile junkyard.

Six SVOCs (1,4-dioxane, benzo(a)anthracene, benzo(a)pyrene, benzo(b)fluoranthene, chrysene, indeno(1,2,3-cd)pyrene, and naphthalene) were detected above the SGV in in four groundwater samples from LMW-15 and LMW-21 through LMW-23. The elevated concentrations of SVOCs detected in groundwater are attributed to sediment entrainment of fill material of unknown origin in the sample and are not indicative of any discrete releases to the subsurface. PAHs in soil are not considered to be an ongoing source of groundwater contamination. 1,4-Dioxane was identified in groundwater in exceedance of the SGVs, but was not detected in soil in exceedance of the Protection of Groundwater SCOs. 1,4-Dioxane in groundwater may be attributed to historical automobile junkyard operations.

Total metals including lead, barium, iron, magnesium, manganese, selenium, and/or sodium were detected in groundwater in exceedance of the SGVs in all monitoring wells. Dissolved lead was not detected above the SGVs and, as such, the detection of total lead is attributed to sediment entrainment in the sample. Elevated concentrations of barium in soil are present throughout the Site footprint; however, total and dissolved barium were detected above the SGV in only one well, LMW-17, during the 2023 RI. An elevated concentration of selenium was detected in only one soil sample and total and dissolved selenium were detected above the SGV in only one well, LMW-4, during the Phase II EI. The detections of barium and selenium in groundwater is attributed to a combination of sediment entrainment in the sample and the quality of fill in contact with groundwater at that location. Based on the isolated detection of total and dissolved barium and selenium in groundwater, barium and selenium concentrations in soil are not considered to be an ongoing source of groundwater contamination. Other metals detected in exceedance of NYSDEC SGVs (total and/or dissolved iron, magnesium, manganese, and sodium) were identified throughout the Site footprint and are attributed to a combination of sediment entrainment in the sample and naturally occurring background concentrations.

PCBs were detected in exceedance of the SGVs in one groundwater sample (LMW-6) during the 2018 Phase II EI. Although PCBs were detected in soil across the Site footprint, only one sample contained concentrations exceeding the Protection of Groundwater SCOs; as such, the PCBs detected in groundwater are attributed to sediment entrainment in the sample.

Groundwater sample analytical results did not identify the presence of pesticides and herbicides at concentrations above the SGVs in any samples for which it was analyzed. Groundwater analytical results are summarized in Table 3 and on Figure 5. Groundwater and Site use restrictions to prevent exposure to remaining groundwater contamination are included in the Environmental Easement.

Dewatering to facilitate implementation of the soil remediation and to remove contaminated groundwater was conducted under a NYCDEP-approved Groundwater Discharge permit and a NYSDEC-approved Long Island Well permit when the excavation area extended beyond the groundwater table. The dewatering system, including 43 dewatering wells and five groundwater monitoring wells, was installed between 21 May and 15 August 2025. The system was activated on 9 June 2025. The groundwater was removed via submersible pumps installed within dewatering wells, treated for suspended solids through one 18,000-gallon settling tank or through the newly constructed detention system for the new development, and then discharged to the NYC sewer system where the water was treated and returned to the freshwater system. A total of approximately 105,826,013 gallons of contaminated groundwater were extracted and subsequently treated and discharged to the NYC sewer system during the remedial action. The results of the daily gauging and the quarterly groundwater monitoring events were provided in Appendix Q of the FER.

2.5.3 Soil Vapor

Soil vapor samples collected during the 2023 RI contained chlorinated VOCs cis-1,2-dichloroethylene (7.69 micrograms per cubic meter [µg/m^3] – 12.2 µg/m^3), PCE (177 µg/m^3 – 340 µg/m^3), and vinyl chloride (6.26 µg/m^3 – 68 µg/m^3) at concentrations that are above the monitoring and/or mitigation threshold according to NYSDOH Soil Vapor Intrusion Guidance Matrix A, B and C. As CVOCs were not detected at concentrations exceeding NYSDEC threshold values in soil or groundwater at the Site, the presence of elevated concentrations of these compounds is attributed to an unknown source.

The 2023 RI soil vapor analytical results have also been compared to the February 2024 updates to the NYSDOH soil vapor/indoor air decision matrices. Soil vapor samples collected during the 2023 RI contained petroleum-related VOCs 2,2,4-trimethylpentane (68.7 µg/m^3 – 3,000 µg/m^3), benzene (275 µg/m^3), cyclohexane (75 µg/m^3 – 19,700 µg/m^3), ethylbenzene (72.1 µg/m^3 – 162 µg/m^3), n-heptane (200 µg/m^3 – 13,200 µg/m^3), n-hexane (212 µg/m^3 – 45,800 µg/m^3), o-xylene (95.1 µg/m^3 – 155 µg/m^3), and toluene (358 µg/m^3) at concentrations above the monitoring and/or mitigation threshold according to NYSDOH Soil Vapor Intrusion Guidance Matrix D, E, and F. Petroleum-related VOCs were not

detected at concentrations exceeding NYSDEC threshold values in soil or groundwater at the site, but concentrations in soil vapor may be attributable to releases associated with historical Site operations or an unknown source.

The building cellar was constructed within the groundwater elevation range measured during the RI (generally between el -2 and el 3.5 NAVD88). Additionally, the cellar of the building is operated as a parking garage with continuous high volume air exchange in conformance with NYC Building Code.

Soil vapor analytical results are summarized in Table 4 and on Figure 6. The soil vapor intrusion evaluation will be completed as discussed in Section 4.4.

3.0 INSTITUTIONAL AND ENGINEERING CONTROL PLAN

3.1 General

Since remaining contamination exists at the site, Institutional Controls (ICs) and Engineering Controls (ECs) are required to protect human health and the environment. This IC/EC Plan describes the procedures for the implementation and management of all IC/ECs at the site. The IC/EC Plan is one component of the SMP and is subject to revision by the NYSDEC project manager.

This plan provides:

- A description of all IC/ECs on the Site;
- The basic implementation and intended role of each IC/EC;
- A description of the key components of the ICs set forth in the Environmental Easement;
- A description of the controls to be evaluated during each required inspection and periodic review;
- A description of plans and procedures to be followed for implementation of IC/ECs, such as the implementation of the Excavation Work Plan (EWP) (as provided in Appendix D) for the proper handling of remaining contamination that may be disturbed during maintenance or redevelopment work on the site; and,

- Any other provisions necessary to identify or establish methods for implementing the IC/ECs required by the site remedy, as determined by the NYSDEC project manager.

3.2 Institutional Controls

A series of ICs is required by the Decision Document to: (1) implement, maintain and monitor Engineering Control systems; (2) prevent future exposure to remaining contamination; and, (3) limit the use and development of the site to Restricted-Residential, Commercial, or Industrial uses only. Adherence to these ICs on the site is required by the Environmental Easement and will be implemented under this SMP. ICs identified in the Environmental Easement may not be discontinued without an amendment to or extinguishment of the Environmental Easement. The IC boundaries are shown on Figure 2. These ICs are:

- The Controlled property may be used for: Restricted Residential as described in 6 NYCC Part 375-1.8(g)(2)(ii), Commercial as described in 6 NYCC Part 375-1.8(g)(2)(iii) and Industrial as described in 6 NYCRR Part 375-1.8(g)(2)(iv);
- All ECs must be operated and maintained as specified in this SMP;
- All ECs must be inspected at a frequency and in a manner defined in the SMP;
- The use of groundwater underlying the property is prohibited without necessary water quality treatment as determined by the NYSDOH or the New York City Department of Health to render it safe for use as drinking water or for industrial purposes, and the user must first notify and obtain written approval to do so from the Department;
- Groundwater and other environmental or public health monitoring must be performed as defined in this SMP;
- Data and information pertinent to site management must be reported at the frequency and in a manner as defined in this SMP;
- All future activities that will disturb remaining contaminated material must be conducted in accordance with this SMP;
- Monitoring to assess the performance and effectiveness of the remedy must be performed as defined in this SMP;

- Operation, maintenance, monitoring, inspection, and reporting of any mechanical or physical component of the remedy shall be performed as defined in this SMP;

- Access to the site must be provided to agents, employees or other representatives of the State of New York with reasonable prior notice to the property owner to assure compliance with the restrictions identified by the Environmental Easement;

- The potential for vapor intrusion must be evaluated for any new buildings developed in the area within the IC boundaries noted on Figure 2, and any potential impacts that are identified must be monitored or mitigated if present in exceedance of the NYSDOH Soil Vapor Intrusion Matrix monitoring and/or mitigation threshold values;

- Vegetable gardens and farming on the site are prohibited; and,
- The potential for vapor intrusion must be evaluated for any buildings developed in the area within the IC boundaries, and appropriate actions to address exposures must be implemented if present in exceedance of the NYSDOH Soil Vapor Intrusion Matrix monitoring and/or mitigation threshold values.

3.3 Engineering Controls

3.3.1 Monitoring Wells

Groundwater monitoring to assess the effectiveness of the remedy, which consists of source removal of contaminated soil and groundwater extraction via the dewatering system, will be completed to monitor for the presence of naphthalene.

Groundwater monitoring includes six permanent monitoring wells LMW-26 through LMW-29, B5_LMW-06, and B5-LMW-09, which will be installed as outlined in Section 4.3.1. The permanent monitoring wells will be installed along the northern, southern (downgradient), and eastern perimeter of the Site and the western and eastern exterior of the Site to assess for the remediation of historical naphthalene impacts detected during the Remedial Investigation in former monitoring wells LMW-15 and LMW-19. Specifically, B5_LMW-06 and B5_LMW-09 will be installed inside the boundary of and as part of the Remedial Investigation for BCP Site No. C224452, which is located adjacent to the west, and LMW-26 will be installed within the footprint of BCP Site No. C224290, which is located to the east. These three offsite wells will remain accessible for the post-

remediation monitoring required for this Site. Two rounds of performance monitoring groundwater sampling will be conducted to evaluate whether the remedy has met the remedial objectives of returning groundwater to pre-release/asymptotic conditions to the extent practicable. A description of the proposed monitoring wells is provided in Section 4.3.

A drawing of the proposed monitoring wells included in the groundwater monitoring well network is included as Figure 7.

Groundwater monitoring activities subsequent to source removal will continue, as determined by the NYSDEC project manager in consultation with NYSDOH project manager, until residual groundwater concentrations are found to be consistently below ambient water quality standards presented in Table 1B, the site SCGs, or have become asymptotic at an acceptable level over an extended period. If monitoring data indicates that monitoring may no longer be required, a proposal to discontinue the monitoring will be submitted by the remedial party. Monitoring will continue until permission to discontinue is granted in writing by the NYSDEC project manager. If groundwater contaminant levels become asymptotic at a level that is not acceptable to the NYSDEC, additional source removal, treatment and/or control measures will be evaluated.

4.0 MONITORING AND SAMPLING PLAN

4.1 General

This Monitoring and Sampling Plan describes the measures for evaluating the overall performance and effectiveness of the remedy. This Monitoring and Sampling Plan may only be revised with the approval of the NYSDEC project manager. Details regarding the sampling procedures, data quality usability objectives, analytical methods, etc. for all samples collected as part of site management for the site are included in the Quality Assurance Project Plan provided in Appendix E.

This Monitoring and Sampling Plan describes the methods to be used for:

- Sampling and analysis of all appropriate media (e.g., groundwater);
- Assessing compliance with applicable NYSDEC standards, criteria and guidance (SCGs), particularly groundwater standards ; and,
- Evaluating site information periodically to confirm that the remedy continues to be effective in protecting public health and the environment.

To adequately address these issues, this Monitoring and Sampling Plan provides information on:

- Sampling locations, protocol and frequency;
- Information on all designed monitoring systems;
- Analytical sampling program requirements;
- Inspection and maintenance requirements for monitoring wells;
- Monitoring well decommissioning procedures; and,
- Annual inspection and periodic certification.

Reporting requirements are provided in Section 7.0 of this SMP.

4.2 Site-wide Inspection

Site-wide inspections will be performed at a minimum of once per year. These periodic inspections must be conducted when the ground surface is visible (i.e. no snow cover). Site-wide inspections will be performed by a qualified environmental professional as defined in 6 NYCRR Part 375, or a qualified person who directly reports to a QEP. Modification to the frequency or duration of the inspections will require approval from the NYSDEC project manager. Site-wide inspections will also be performed after all severe weather conditions that may affect ECs or the remaining contamination at the Site. During these inspections, an inspection form will be completed as provided in Appendix I – Site Management Forms. The form will compile sufficient information to assess the following:

- Compliance with all ICs, including Site usage;
- An evaluation of the condition and continued effectiveness of ECs;
- General site conditions at the time of the inspection;
- The site management activities being conducted including, where appropriate, confirmation sampling and a health and safety inspection; and,
- Confirm that site records are up to date.

Inspections of all remedial components installed at the site will be conducted. A comprehensive Site-wide inspection will be conducted and documented according to the SMP schedule, regardless of the frequency of the Periodic Review Report. The inspections will determine and document the following:

- Whether ECs continue to perform as designed;
- If these controls continue to be protective of human health and the environment;
- Compliance with requirements of this SMP and the Environmental Easement;
- Achievement of remedial performance criteria; and,
- If site records are complete and up to date.

Reporting requirements are outlined in Section 7.0 of this plan.

Inspections will also be performed in the event of an emergency. If an emergency, such as a natural disaster or an unforeseen failure of any of the ECs occurs that reduces or has the potential to reduce the effectiveness of ECs in place at the site, verbal notice to the NYSDEC project manager must be given by noon of the following day. In addition, an inspection of the site will be conducted within 5 days of the event to verify the effectiveness of the IC/ECs implemented at the site by a qualified environmental professional, as defined in 6 NYCCR Part 375. Written confirmation must be provided to the NYSDEC project manager within 7 days of the event that includes a summary of actions taken, or to be taken, and the potential impact to the environment and the public. The remedial party will submit follow-up status reports to the NYSDEC within 45 days of the event on actions taken to respond to any emergency event requiring ongoing responsive action, describing and documenting actions taken to restore the effectiveness of the ECs.

4.3 Post-Remediation Groundwater Monitoring and Sampling

Groundwater samples shall be collected from the monitoring wells biannually. Sampling locations, required analytical parameters, and schedule are provided in the table below. Modification to the frequency or sampling requirements will require approval from the NYSDEC project manager.

Monitoring Well	Monitoring Parameter	Monitoring Schedule
LMW-26	TCL VOCs Naphthalene	Biannually (twice per year) starting in 2026 To be re-evaluated after year 1
LMW-27		
LMW-28		
LMW-29		
B5_LMW-06		
B5-LMW-09		

Detailed sample collection and analytical procedures and protocols are provided in Appendix E – Quality Assurance Project Plan.

4.3.1 Monitoring Well Installation

The proposed monitoring wells (LMW-26 through LMW-29, B5_LMW-06, and B5_LMW-09) will be constructed using 2-inch-diameter PVC riser pipe attached to 10-foot long, schedule-40, 0.010-inch slotted, 2-inch-diameter PVC screen. The monitoring wells will be installed so that the well screen straddles the observed water table. The 2-inch well annulus around the screen will be backfilled with clean sand to about 2 feet above the top of the screen. A minimum 2-foot bentonite seal will be installed above the sand, and the borehole annulus will be backfilled with non-impacted soil cuttings and/or clean sand. The wells will be finished with a flush-mounted metal manhole cover set in concrete. Following installation, the newly installed monitoring wells will be developed by surging the newly installed sand pack with a surge block, a weighted bailer, or surge pumping techniques across the well screen to agitate and remove fine particles. The surge block, bailer, or submersible pump will be surged across the submerged well screen in 2- to 3-foot increments for approximately 2 minutes per increment. After surging, the well will be purged via pumping until the water becomes clear. The well will then be allowed to sit for a minimum of one week before sampling. All drilling derived waste (i.e., soil and purged groundwater) collected during the well installation will be containerized in 55-gallon drums and properly disposed of off-Site.

Construction details for the proposed monitoring wells are presented in Table 5.

4.3.2 Groundwater Sampling

Groundwater monitoring will be performed biannually (twice per year) to assess the performance of the remedy. Modification to the frequency or sampling requirements will require approval from the NYSDEC project manager.

Groundwater monitoring includes six permanent monitoring wells LMW-26 through LMW-29, B5_LMW-06, and B5-LMW-09. The permanent monitoring wells will be installed along the northern, southern (downgradient), and eastern perimeter of the Site and the western and eastern exterior of the Site to assess for the remediation of historical naphthalene impacts detected during the Remedial Investigation in former monitoring wells LMW-15 and LMW-19. Specifically, B5_LMW-06 and B5_LMW-09 will be installed inside the boundary of and as part of the Remedial Investigation for BCP Site No. C224452, which is located adjacent to the west, and LMW-26 will be installed within the footprint of BCP Site No. C224290, which is located to the east. These three offsite wells will remain accessible for the post-remediation monitoring required for this Site.

The remedial party will measure depth to the water table for each monitoring well in the network before sampling. Groundwater samples will be collected by a QEP as defined in 6 NYCRR Part 375 or a qualified person who directly reports to a QEP via USEPA low-flow sampling methods. Samples will be analyzed for VOCs and naphthalene. Groundwater quality parameters (pH, temperature, ORP, DO, turbidity, and conductivity) will be collected during each groundwater monitoring event. Purged groundwater collected during the sampling event will be containerized in 55-gallon drums and properly disposed of off-Site. Groundwater samples will be collected in laboratory-supplied containers and will be sealed, labeled, and placed into a cooler containing ice (to maintain a temperature of approximately 4 degrees Celsius) for delivery to a NYSDOH ELAP-certified analytical laboratory. Detailed sample collection and analytical procedures, QA/QC procedures, and protocols are described in the QAPP provided as Appendix E.

If biofouling or silt accumulation occurs in the on-site and/or off-site monitoring wells, the wells will be physically agitated/surged and redeveloped. Additionally, monitoring wells will be properly decommissioned and replaced if an event renders the wells unusable. Repairs and/or replacement of wells in the monitoring well network will be performed based on assessments of structural integrity and overall performance.

The NYSDEC project manager will be notified prior to any repair or decommissioning of any monitoring well for the purpose of replacement, and the repair or decommissioning and replacement process will be documented in the subsequent Periodic Review Report. Well decommissioning without replacement will be done only with the prior approval of the NYSDEC project manager. Well abandonment will be performed in accordance with NYSDEC's guidance entitled "CP-43: Groundwater Monitoring Well Decommissioning Procedures." Monitoring wells that are decommissioned because they have been

rendered unusable will be replaced in kind in the nearest available location, unless otherwise approved by the NYSDEC project manager.
The frequency of groundwater sampling will be re-evaluated following review of results obtained from the first year of sampling. The sampling frequency may only be modified with the approval of the NYSDEC project manager. This SMP will be modified to reflect changes in sampling plans approved by the NYSDEC project manager.

Deliverables for the groundwater monitoring program are specified in Section 7.0 – Reporting Requirements.

4.3.3 Monitoring and Sampling Protocol

All sampling activities will be recorded in a field book and associated sampling log as provided in Appendix I – Site Management Forms. Other observations (e.g., groundwater monitoring well integrity) will be noted on the sampling log. The sampling log will serve as the inspection form for the monitoring network.

4.4 Soil Vapor Intrusion Evaluation

Thirteen soil vapor samples were collected during the 2023 RI. CVOCs, including cis-1,2-dichloroethylene, PCE, and/or vinyl chloride, were detected in all soil vapor samples across the Site footprint at concentrations which would be above the monitoring and/or mitigation threshold according to NYSDOH Soil Vapor Intrusion Guidance Matrix A, B, and C in samples collected from across the Site footprint. The highest concentration of cumulative CVOCs was detected at a concentration of 404.96 µg/m3 at LSV-15. As CVOCs were not detected at concentrations exceeding NYSDEC threshold values in soil or groundwater at the site, the presence of elevated concentrations of these compounds is attributed to an unknown source.

Petroleum-related VOCs were also identified across the Site footprint, including 2,2,4-trimethylpentane, benzene, cyclohexane, ethylbenzene, n-heptane, n-hexane, o-xylene, and toluene, were detected in all soil vapor samples across the Site footprint at concentrations which would be above the monitoring and/or mitigation threshold according to NYSDOH Soil Vapor Intrusion Guidance Matrix D, E, and F. The highest concentration of cumulative BTEX was detected at a concentration of 1,124 µg/m3 at LSV 14. LSV-14 is located in close proximity to LMW-19 at which naphthalene was detected in groundwater above the SGVs during the 2023 RI and LMW-4 at which methyl tert butyl ether was detected in groundwater above the SGVs during the 2018 Phase II EI; however, no other evidence of petroleum impacts were observed in soil or groundwater in this area

of the Site and no petroleum-related VOCs were detected at concentrations exceeding NYSDEC SCOs in soil samples collected from nearby soil borings. Concentrations of petroleum-related VOCs in soil vapor may be attributable to historical releases associated with former Site operations.

As chlorinated and petroleum-related VOCs were not detected at concentrations exceeding NYSDEC threshold values in soil or groundwater at the site, the presence of elevated concentrations of these compounds is attributed to an unknown source.

A soil vapor intrusion evaluation must be performed upon a change in use of the property that will result in occupancy of a previously unoccupied building or initial occupancy of a new building. The breadth of the evaluation will be determined based upon discussion with the NYSDEC and NYSDOH project managers. Based upon these discussions and agency requirements, a work plan may need to be developed that requires that sampling be performed. Upon completion of the evaluation, if an action is required, any actions taken or to be taken must be reflected in an updated SMP.

5.0 OPERATION AND MAINTENANCE PLAN

5.1 General

The site remedy does not rely on any mechanical systems, such as groundwater treatment systems, sub-slab depressurization systems or air sparge/soil vapor extraction systems to protect public health and the environment. Therefore, the operation and maintenance of such components is not included in this SMP.

6.0 PERIODIC ASSESSMENTS/EVALUATIONS

6.1 Climate Change Vulnerability Assessment

Increases in both the severity and frequency of storms/weather events, an increase in sea level elevations along with accompanying flooding impacts, shifting precipitation patterns and wide temperature fluctuation, resulting from global climactic change and instability, have the potential to significantly impact the performance, effectiveness and protectiveness of a given site and associated remedial systems. Vulnerability assessments provide information so that the site and associated remedial systems are prepared for the impacts of the increasing frequency and intensity of severe storms/weather events and associated flooding.

This section provides a current vulnerability assessment that evaluates the vulnerability of the site and/or engineering controls to severe storms/weather events and associated flooding. This section also identifies vulnerability assessment updates that will be conducted for the site in Periodic Review Reports.

As stated in Section 3.3, Site-wide inspections will be performed after severe weather events. According to the National Flood Insurance Rate map for the City of New York published by the FEMA (Community Panel No. 3604970219F, effective date September 5, 2007), the Site is located in Zone X, which is designated for areas determined to be outside the 0.2% annual chance of flood and in an area of minimal flood hazard. Based on the National Hurricane Center Storm Surge Risk Maps dated 2021, a storm surge is likely to impact the Site for a Category 3 or higher storm. The NYC Risk Landscape: Guide to Hazardous Mitigation cites the National Hurricane Center data point that Category 3 storms only impact New York City every 74 years.

Site erosion is not expected during severe weather or precipitation events because remaining impacts in soil is covered with a concrete slab. The Site would not be susceptible to a spill or contaminant release because source material has been removed.

A Climate Screening Checklist was completed for the Site as part of this SMP. The Climate Screening indicated that no further action is necessary. The Climate Screening Checklist is included in Appendix F.

6.2 Green Remediation Evaluation

NYSDEC's DER-31 Green Remediation requires that green remediation concepts and techniques be considered during all stages of the remedial program including site management, with the goal of improving the sustainability of the cleanup and summarizing the net environmental benefit of any implemented green technology. This section provides an environmental footprint analysis of the remedy, as implemented at the time of this SMP. This section of the SMP also provides a summary of green remediation evaluations to be completed for the site during site management and reported in Periodic Review Reports (PRRs).

6.2.1 Environmental Footprint Analysis

An environmental footprint analysis was completed using SiteWise™ (available in the SURF library) which is a NYSDEC accepted environmental footprint analysis calculator. The following components of this SMP were entered in the SiteWise™ model:

- Annual Inspections
- Biannual groundwater monitoring

The annual inspection would include up to ten years estimating the mileage to and from the Site for the annual inspections and biannual groundwater monitoring. The analysis also includes the installation of six monitoring wells for the implementation of biannual groundwater monitoring.

Using the above identified information, the SiteWise™ model estimated the following emissions and total energy usage for up to 10 years of annual inspections and biannual groundwater monitoring:

Remedial Alternatives	**10 Years of Annual Inspections and Biannual Groundwater Monitoring**
Greenhouse Gas (GHG) Emissions (metric ton)	153
Total energy Used (MMBTU)	5,600
Total NOx Emissions (metric ton)	0.67
Total SOx Emissions (metric ton)	0.5
Total PM10 Emissions (metric ton)	0.057

Details regarding the inputs and outputs of the SiteWise™ model are provided in Appendix F.

6.2.2 Green Remediation Principles and Best Management Practices

The SMP will be implemented to provide the details necessary for the construction, operation, optimization, maintenance, and/or monitoring of the remedial program. Green remediation principles and techniques will be implemented to the extent feasible in the

Site management of the remedy as per DER-31. The major green remediation components are as follows:

- Considering the environmental impacts of treatment technologies and remedy stewardship over the long term
- Reducing direct and indirect greenhouse gases and other emissions
- Increasing energy efficiency and minimizing use of non-renewable energy
- Conserving and efficiently managing resources and materials
- Reducing waste, increasing recycling and increasing reuse of materials that would otherwise be considered a waste
- Fostering green and healthy communities and working landscapes which balance ecological, economic and social goals
- Integrating the remedy with the end use where possible and encouraging green and sustainable re-development
- Additionally, to incorporate the GSR principles and techniques to the extent feasible in the future development at this Site, any future on-Site buildings shall be constructed, at a minimum, to meet the 2020 Energy Conservation Construction Code of New York (or most recent edition) to improve energy efficiency as an element of construction.

The SMP will include the implementation of several Best Management Practices (BMPs) related to these green remediation components, including but not limited to the following:

- Waste Generation
- Electrical Use
- Emissions
- Water Usage
- Land and/or Ecosystem

Waste Generation

Waste generation considers the management of waste associated with SMP activities and any waste reduction projects including, but not limited to, material reuse and recycling. Waste generation is not anticipated for routine SMP activities (annual Site-wide inspections). Waste generation may be required during non-routine SMP activities

(implementation of the Excavation Work Plan [EWP]). Several waste streams may be generated during implementation of non-routine SMP activities (e.g., soil, polyethylene sheets used for stockpile coverage and separating types of contamination, nitrile gloves for endpoint sampling, disposable sample ware, acetate liners from drilling operations, decontamination materials). When possible, an effort will made to minimize consumption/generation of such materials. If possible, decontamination and reuse of applicable materials will be considered. Electronic methods of data collection (e.g., tablets) will also be used to reduce paper consumption when possible. Additionally, designated collection points for waste streams will be encouraged to be separated into single use items such as metal, plastics, and glass containers; compostable materials; paper and cardboard; and other items that may be recycled locally.

Electrical Energy Use

Energy usage considers the electricity usage needed for SMP activities. Energy usage is not anticipated for routine SMP activities (annual Site-wide inspections) but may be required during non-routine SMP activities (implementation of the EWP). Energy will be required for charging equipment (e.g., PIDs, air monitoring equipment). Battery-powered equipment will be turned off when not in use to limit charging activities.

Emissions

Emissions tracking considers fuel usage for transportation of personnel to and from the Site for routine SMP activities. However, during non-routine SMP activities (implementation of the EWP), emissions tracking will consider fuel usage for transportation of personnel to and from the site, trucks used for export of contaminated material or import of backfill material, equipment and laboratory sample couriers, and drilling/construction equipment. To reduce fuel usage, trucks and heavy machinery operators will be encouraged to reduce idling time and shut down vehicles or equipment when not in use. The contractor will also be encouraged to perform routine, on-time maintenance such as oil changes to improve fuel efficiency. When possible and pending availability, personnel will be considered based on their proximity to the Site and will be encouraged to take public transport.

Water Usage

Water usage considers sources of water for tasks such as decontamination, irrigation, etc. Water usage is not anticipated for routine SMP activities (annual Site-wide inspections). Water usage may be required during non-routine SMP activities (implementation of the EWP). The public water supply will be used when water is

required for decontamination activities or dust suppression during any soil disturbance as part of this SMP. Water will only be consumed when necessary, and consumption will be in accordance with local regulations.

Land and/or Ecosystems

Land and/or ecosystems consider any disturbances and restoration of land and/or ecosystems as part of the implementation/operation of the remedy. The Site is currently an active construction site excavated to the cellar level. The final redevelopment of the Site will consist of two mixed-use commercial/residential towers in the central and eastern portion of the Site with a single cellar level across the majority of the Site footprint. A publicly accessible private roadway will be constructed at street level on the western portion of the Site. During implementation of the SMP, the Site cover will be restored following any excavation and will require minimal to no maintenance.

6.2.3 Timing of Green Remediation Evaluations

For major remedial system components, green remediation evaluations and corresponding modifications will be undertaken as part of a formal Remedial System Optimization (RSO), or at any time that the NYSDEC project manager feels appropriate, (e.g. during significant maintenance events or in conjunction with storm recovery activities).

Modifications resulting from green remediation evaluations will be routinely implemented and scheduled to occur during planned/routine operation and maintenance activities after approval from the DER project manager. Reporting of these modifications will be presented in the PRR.

6.2.4 Frequency of System Checks, Sampling and Other Periodic Activities

Transportation to and from the Site, use of consumables in relation to visiting the Site in order to collect samples, and shipping samples to a laboratory for analyses have direct and/or inherent energy costs. The schedule and/or means of these periodic activities have been prepared so that these tasks can be accomplished in a manner that does not impact remedy protectiveness but reduces expenditure of energy or resources.

6.2.5 Metrics and Reporting

As discussed in Section 7.0 and as shown in Appendix I – Site Management Forms, information on energy usage, solid waste generation, transportation and shipping, water usage and land use and ecosystems will be recorded to facilitate and document

consistent implementation of green remediation during site management and to identify corresponding benefits. A set of metrics has been developed and will be evaluated over time to ensure that green remediation actions are achieving the desired results.

Personnel mileage to and from the site for SMP activities will be tracked based on the number of Langan personnel field days.

6.3 Remedial System Optimization

A Remedial System Optimization (RSO) study will be conducted any time that the NYSDEC project manager or the remedial party requests in writing that an in-depth evaluation of the remedy is needed. An RSO may be appropriate if any of the following occur:

- The remedial actions have not met or are not expected to meet RAOs in the time frame estimated in the Decision Document;
- The management and operation of the remedial system is exceeding the estimated costs;
- The remedial system is not performing as expected or as designed;
- Previously unidentified source material may be suspected;
- Plume shift has potentially occurred;
- Site conditions change due to development, change of use, change in groundwater use, etc.;
- There is an anticipated transfer of the site management to another remedial party or agency; and
- A new and applicable remedial technology becomes available.

An RSO will provide a critique of a site's conceptual model, give a summary of past performance, document current cleanup practices, summarize progress made toward the site's cleanup goals, gather additional performance or media specific data and information and provide recommendations for improvements to enhance the ability of the present system to reach RAOs or to provide a basis for changing the remedial strategy.

The RSO study will focus on overall site cleanup strategy, process optimization and management with the intent of identifying impediments to cleanup and improvements to site operations to increase efficiency, cost effectiveness and remedial time frames. Green remediation technology and principals are to be considered when performing the RSO.

7.0 REPORTING REQUIREMENTS

7.1 Site Management Reports

All site management inspection, maintenance and monitoring events will be recorded on the appropriate site management forms provided in Appendix I. These forms are subject to NYSDEC revision. All site management inspection, maintenance, and monitoring events will be conducted by a qualified environmental professional as defined in 6 NYCRR Part 375 or a qualified person who directly reports to a QEP.

All applicable inspection forms and other records, including media sampling data, generated for the site during the reporting period will be provided in electronic format to the NYSDEC in accordance with the requirements of the following table:

Task/Report	**Reporting Frequency***
Performance Monitoring Groundwater Analytical Data	Annually with the PRR
Periodic Review Report	16 months after COC, annually thereafter, or as otherwise determined by the NYSDEC

* The frequency of events will be conducted as specified until otherwise approved by the NYSDEC project manager.

All interim monitoring/inspections reports will include, at a minimum:

- Date of event or reporting period;
- Name, company, and position of person(s) conducting monitoring/inspection activities;
- Description of the activities performed;

- Where appropriate, color photographs or sketches showing the approximate location of any problems or incidents noted (included either on the checklist/form or on an attached sheet);
- Type of samples collected (e.g., sub-slab vapor, indoor air, outdoor air);
- Copies of all field forms completed (e.g., well sampling logs, chain-of-custody documentation);
- Sampling results in comparison to appropriate standards/criteria;
- A figure illustrating sample type and sampling locations;
- Copies of all laboratory data sheets and the required laboratory data deliverables required for all points sampled (to be submitted electronically in the NYSDEC-identified format);
- Any observations, conclusions, or recommendations; and,
- A determination as to whether contaminant conditions have changed since the last reporting event.

Routine maintenance event reporting forms will include, at a minimum:

- Date of event;
- Name, company, and position of person(s) conducting maintenance activities;
- Description of maintenance activities performed;
- Any modifications to the system;
- Where appropriate, color photographs or sketches showing the approximate location of any problems or incidents noted (included either on the checklist/form or on an attached sheet); and
- Other documentation such as copies of invoices for maintenance work, receipts for replacement equipment, etc., (attached to the checklist/form).

Non-routine maintenance event reporting forms will include, at a minimum:

- Date of event;
- Name, company, and position of person(s) conducting non-routine maintenance/repair activities;
- Description of non-routine activities performed;
- Where appropriate, color photographs or sketches showing the approximate location of any problems or incidents (included either on the form or on an attached sheet); and .
- Other documentation such as copies of invoices for repair work, receipts for replacement equipment, etc. (attached to the checklist/form).

Data will be reported in digital format as determined by the NYSDEC. Currently, data is to be supplied electronically and submitted to the NYSDEC EQuIS™ database in accordance with the requirements found at this link http://www.dec.ny.gov/chemical/62440.html.

7.2 Periodic Review Report

A Periodic Review Report (PRR) will be submitted to the NYSDEC project manager beginning sixteen (16) months after the Certificate of Completion is issued. After submittal of the initial Periodic Review Report, the next PRR shall be submitted every fifth year to the NYSDEC project manager or at another frequency as may be required by the NYSDEC project manager. In the event that the site is subdivided into separate parcels with different ownership, a single Periodic Review Report will be prepared that addresses the site described in Appendix A - Environmental Easement. The report will be prepared in accordance with NYSDEC's DER-10 and submitted within 30 days of the end of each certification period. Media sampling results will also be incorporated into the Periodic Review Report. The report will include:

- Identification, assessment and certification of all ECs/ICs required by the remedy for the site.
- Results of the required annual site inspections, fire inspections and severe condition inspections, if applicable.
- Description of any change of use, import of materials, or excavation that occurred during the certifying period.

- All applicable Site management forms and other records generated for the site during the reporting period in the NYSDEC-approved electronic format, if not previously submitted.

- Identification of any wastes generated during the reporting period, along with waste characterization data, manifests, and disposal documentation.

- A summary of any data and/or information generated during the reporting period, with comments and conclusions.

- Data summary tables and graphical representations of contaminants of concern by media (groundwater), which include a listing of all compounds analyzed, along with the applicable standards, with all exceedances highlighted. These tables and figures will include a presentation of past data as part of an evaluation of contaminant concentration trends, including but not limited to:

  - Trend monitoring graphs that present groundwater contaminant levels from before the start of the remedy implementation to the most current sampling data;

  - Trend monitoring graphs depicting system influent analytical data on a per event and cumulative basis;

  - O&M data summary tables;

  - A current plume map for sites with remaining groundwater contamination; and

  - A groundwater elevation contour map for each gauging event.

- Results of all analyses, copies of all laboratory data sheets, and the required laboratory data deliverables for all samples collected during the reporting period will be submitted in digital format as determined by the NYSDEC. Currently, data is supplied electronically and submitted to the NYSDEC EQuIS™ database in accordance with the requirements found at this link: http://www.dec.ny.gov/chemical/62440.html.

- A Site evaluation, which includes the following:

  - The compliance of the remedy with the requirements of the site-specific Remedial Action Work Plan (RAWP) and Decision Document;

- The operation and the effectiveness of all treatment units, etc., including identification of any needed repairs or modifications;
- Any new conclusions or observations regarding site contamination based on inspections or data generated by the Monitoring and Sampling Plan for the media being monitored;
- Recommendations regarding any necessary changes to the remedy and/or Monitoring and Sampling Plan;
- An update to the climate change vulnerability assessment if site or external conditions have changed since the previous assessment, and recommendations to address vulnerabilities.
- A summary of the Green Remediation evaluation, including a quantitative and qualitative overview of a site's environmental impacts and recommendations to improve the remedy's environmental footprint. The PRR will include the completed Summary of Green Remediation Metrics form provided in Appendix F.
- An evaluation of trends in contaminant levels in the affected media to determine if the remedy continues to be effective in achieving remedial goals as specified by the RAWP and Decision Document; and
- The overall performance and effectiveness of the remedy.

7.2.1 Certification of Institutional and Engineering Controls

Following the last inspection of the reporting period, a qualified environmental professional as defined in 6 NYCRR Part 375 will prepare, and include in the Periodic Review Report, the following certification as per the requirements of NYSDEC DER-10:

"*For each institutional or engineering control identified for the site, I certify that all of the following statements are true:*

- *The inspection of the site to confirm the effectiveness of the institutional and engineering controls required by the remedial program was performed under my direction;*

- *The institutional control and/or engineering control employed at this site is unchanged from the date the control was put in place, or last approved by the Department;*
- *Nothing has occurred that would impair the ability of the control to protect the public health and environment;*
- *Nothing has occurred that would constitute a violation or failure to comply with any site management plan for this control;*
- *Access to the site will continue to be provided to the Department to evaluate the remedy, including access to evaluate the continued maintenance of this control;*
- *If a financial assurance mechanism is required under the oversight document for the site, the mechanism remains valid and sufficient for the intended purpose under the document;*
- *Use of the site is compliant with the environmental easement;*
- *The engineering control systems are performing as designed and are effective;*
- *To the best of my knowledge and belief, the work and conclusions described in this certification are in accordance with the requirements of the site remedial program and generally accepted engineering practices;*
- *The information presented in this report is accurate and complete; and,*
- *No new information has come to my attention, including groundwater monitoring data from wells located at the site boundary, if any, to indicate that the assumptions made in the qualitative exposure assessment of off-site contamination are no longer valid.*

I certify that all information and statements in this certification form are true. I understand that a false statement made herein is punishable as a Class "A" misdemeanor, pursuant to Section 210.45 of the Penal Law. I, Amanda Forsburg, of Langan Engineering, Environmental, Surveying, Landscape Architecture and Geology, D.P.C., am certifying as Remedial Party's Designated Site Representative].

For BCP projects, every five years the following certification will be added:

- *The assumptions made in the qualitative exposure assessment remain valid.*

The signed certification will be included in the Periodic Review Report, if such report is required for the period. Otherwise, the Certification will be submitted as a stand-alone document.

The Periodic Review Report will be submitted, in electronic format, to the NYSDEC project manager and the NYSDOH project manager. The Periodic Review Report may also need to be submitted in hard-copy format if requested by the NYSDEC project manager.

7.3 Corrective Measures Work Plan

If any component of the remedy is found to have failed, or if the periodic certification cannot be provided due to the failure of an institutional or engineering control or failure to conduct site management activities, a Corrective Measures Work Plan will be submitted to the NYSDEC project manager for approval. This plan will explain the failure and provide the details and schedule for performing work necessary to correct the failure. Unless an emergency condition exists, no work will be performed pursuant to the Corrective Measures Work Plan until it has been approved by the NYSDEC project manager.

7.4 Remedial System Optimization Report

If an RSO is to be performed (see Section 6.3), upon completion of an RSO, an RSO report must be submitted to the NYSDEC project manager for approval. A general outline for the RSO report is provided in Appendix J. The RSO report will document the research/ investigation and data gathering that was conducted, evaluate the results and facts obtained, present a revised conceptual site model and present recommendations. RSO recommendations are to be implemented upon approval from the NYSDEC. Additional work plans, design documents, HASPs etc., may still be required to implement the recommendations, based upon the actions that need to be taken. A final engineering report and update to the SMP may also be required.

The RSO report will be submitted, in electronic format, to the NYSDEC project manager and the NYSDOH project manager.

8.0 REFERENCES

1. 6 NYCRR Part 375, Environmental Remediation Programs. December 14, 2006.
2. NYSDEC DER-10 – "Technical Guidance for Site Investigation and Remediation".
3. NYSDEC, 1998. Ambient Water Quality Standards and Guidance Values and Groundwater Effluent Limitations Division of Water Technical and Operational Guidance Series (TOGS) 1.1.1. June 1998 (April 2000 addendum).
4. AKRF, Inc., Fresh Creek Estates, Technical Memorandum to the Draft Environmental Impact Statement (DEIS), dated June 1991.
5. Soil Engineering Services, Inc., Subsurface Investigation and Report, dated March 1994.
6. Soil Mechanics Environmental Services, Phase I Environmental Site Assessment, dated April 2003.
7. Soil Mechanics Environmental Services, Phase I Environmental Site Assessment for Flatlands Ave. & Pennsylvania Ave., dated April 2003.
8. Langan Engineering, Environmental, Surveying, Landscape Architecture and Geology, D.P.C., Phase I Environmental Site Assessment, dated 24 August 2018.
9. Langan Engineering, Environmental, Surveying, Landscape Architecture and Geology, D.P.C., Limited Phase II Environmental Investigation Report, dated 30 May 2018.
10. Langan Engineering, Environmental, Surveying, Landscape Architecture and Geology, D.P.C., Remedial Investigation Work Plan, dated 20 October 2022.
11. Langan Engineering, Environmental, Surveying, Landscape Architecture and Geology, D.P.C., Phase I Environmental Site Assessment, dated 5 December 2022.
12. Knauf Shaw LLP, 60-Day Advance Notice of Site Change of Use
13. Langan Engineering, Environmental, Surveying, Landscape Architecture and Geology, D.P.C., Remedial Investigation Report, dated 1 December 2023
14. Langan Engineering, Environmental, Surveying, Landscape Architecture and Geology, D.P.C., Remedial Action Work Plan, dated 1 May 2024.
15. Langan Engineering, Environmental, Surveying, Landscape Architecture and Geology, D.P.C., Phase I Environmental Site Assessment, dated 18 September 2024.
16. Langan Engineering, Environmental, Surveying, Landscape Architecture and Geology, D.P.C., Final Engineering Report, dated 22 May 2026.

TABLES

Table 1A
Site Management Plan
Soil Cleanup Objectives

12074 Flatlands Avenue p/o Lot 1 Site
Brooklyn, New York
NYSDEC BCP Site No.: C224353
Langan Project No.: 100688803

Analyte	CAS Number	Track 1 NYSDEC Part 375 Unrestricted Use SCOs	Track 2 NYSDEC Part 375 Restricted Use Restricted-Residential SCOs
Volatile Organic Compounds (mg/kg)			
1,1,1-Trichloroethane	71-55-6	0.68	100
1,1-Dichloroethane	75-34-3	0.27	47
1,1-Dichloroethene	75-35-4	0.24	0.98
1,2,4-Trimethylbenzene	95-63-6	5.9	100
1,2-Dichlorobenzene	95-50-1	1.1	100
1,2-Dichloroethane	107-06-2	0.02	5.8
1,3,5-Trimethylbenzene (Mesitylene)	108-67-8	3.1	100
1,3-Dichlorobenzene	541-73-1	2.6	38
1,4-Dichlorobenzene	106-46-7	1.8	24
1,4-Dioxane (P-Dioxane)	123-91-1	0.1	5.7
Acetone	67-64-1	0.03	100
Benzene	71-43-2	0.06	3.7
Carbon Tetrachloride	56-23-5	0.76	7.1
Chlorobenzene	108-90-7	4.5	100
Chloroform	67-66-3	0.37	24
Cis-1,2-Dichloroethene	156-59-2	0.19	41
Ethylbenzene	100-41-4	1	76
Methyl Ethyl Ketone (2-Butanone)	78-93-3	0.1	100
Methylene Chloride	75-09-2	0.05	81
n-Butylbenzene	104-51-8	18	100
n-Propylbenzene	103-65-1	5	100
Sec-Butylbenzene	135-98-8	25	100
T-Butylbenzene	98-06-6	11	100
Tert-Butyl Methyl Ether	1634-04-4	0.1	100
Tetrachloroethene (PCE)	127-18-4	1.3	18
Toluene	108-88-3	0.7	100
Total Xylenes	1330-20-7	0.26	100
Trans-1,2-Dichloroethene	156-60-5	0.19	100
Trichloroethene (TCE)	79-01-6	0.47	6.4
Vinyl Chloride	75-01-4	0.03	0.48
Semivolatile Organic Compounds (mg/kg)			
1,2-Dichlorobenzene	95-50-1	1.1	100
1,3-Dichlorobenzene	541-73-1	2.6	38
1,4-Dichlorobenzene	106-46-7	1.8	24
1,4-Dioxane (P-Dioxane)	123-91-1	0.1	5.7
2-Methylphenol (o-Cresol)	95-48-7	0.33	100
3 & 4 Methylphenol (m&p Cresol)	65794-96-9	0.33	100
Acenaphthene	83-32-9	20	100
Acenaphthylene	208-96-8	100	100
Aniline (Phenylamine, Aminobenzene)	62-53-3	0.04	8.1
Anthracene	120-12-7	100	100
Benzo(a)anthracene	56-55-3	1	1.4
Benzo(a)pyrene	50-32-8	1	1
Benzo(b)fluoranthene	205-99-2	1	1.4
Benzo(g,h,i)Perylene	191-24-2	0.64	4.9
Benzo(k)fluoranthene	207-08-9	0.8	4.9
Chrysene	218-01-9	1	4.9
Dibenz(a,h)anthracene	53-70-3	0.33	0.33
Dibenzofuran	132-64-9	2.1	18
Fluoranthene	206-44-0	85	100
Fluorene	86-73-7	30	100
Hexachlorobenzene	118-74-1	0.33	0.33
Indeno(1,2,3-cd)pyrene	193-39-5	0.5	1.4
Naphthalene	91-20-3	12	100
Nitrobenzene	98-95-3	0.08	1.8
Pentachlorophenol	87-86-5	0.8	1.3
Phenanthrene	85-01-8	1.1	4.9
Phenol	108-95-2	0.33	100
Pyrene	129-00-0	64	100

Table 1A
Site Management Plan
Soil Cleanup Objectives

12074 Flatlands Avenue p/o Lot 1 Site
Brooklyn, New York
NYSDEC BCP Site No.: C224353
Langan Project No.: 100688803

Analyte	CAS Number	Track 1 NYSDEC Part 375 Unrestricted Use SCOs	Track 2 NYSDEC Part 375 Restricted Use Restricted-Residential SCOs
Pesticides (mg/kg)			
4,4'-DDD	72-54-8	0.0033	5
4,4'-DDE	72-55-9	0.0033	3.4
4,4'-DDT	50-29-3	0.0033	3.8
Aldrin	309-00-2	0.0048	0.044
Alpha BHC (Alpha Hexachlorocyclohexane)	319-84-6	0.02	0.18
Alpha Chlordane	5103-71-9	0.014	0.65
Alpha Endosulfan	959-98-8	4.3	35
Beta Bhc (Beta Hexachlorocyclohexane)	319-85-7	0.021	0.18
Beta Endosulfan	33213-65-9	4.3	35
Delta Bhc (Delta Hexachlorocyclohexane)	319-86-8	0.04	100
Dieldrin	60-57-1	0.005	0.075
Endosulfan Sulfate	1031-07-8	4.3	35
Endrin	72-20-8	0.014	5.3
Gamma Bhc (Lindane)	58-89-9	0.025	0.21
Heptachlor	76-44-8	0.013	0.53
Herbicides (mg/kg)			
Silvex (2,4,5-Tp)	93-72-1	3.8	100
Polychlorinated Biphenyls (mg/kg)			
Total PCBs	1336-36-3	0.1	1
Inorganics (mg/kg)			
Arsenic	7440-38-2	13	16
Barium	7440-39-3	410	410
Beryllium	7440-41-7	4.4	43
Cadmium	7440-43-9	2.5	2.5
Chromium, Hexavalent	18540-29-9	1	1
Chromium, Trivalent	16065-83-1	30	110
Copper	7440-50-8	50	280
Total Cyanide	~	2.3	13
Lead	7439-92-1	63	400
Manganese	7439-96-5	1,600	2,000
Mercury	7439-97-6	0.18	0.3
Nickel	7440-02-0	30	320
Selenium	7782-49-2	3.9	110
Silver	7440-22-4	2	110
Zinc	7440-66-6	109	6,600

Notes:
1. Soil cleanup objectives taken from New York State Department of Environmental Conservation (NYSDEC) Title 6 of the Official Compilation of New York Codes, Rules, and Regulations (NYCRR) Part 375 Unrestricted Use and Restricted Use Restricted-Residential Soil Cleanup Objectives (SCOs).
2. Criterion comparisons for 3- & 4-methylphenol (m&p cresol) are provided for reference. Promulgated SCOs are for 3-methylphenol (m-cresol) and
3. ~ = Regulatory limit for this analyte does not exist
4. mg/kg = milligrams per kilogram

Table 1B
Site Management Plan
Groundwater Cleanup Objectives

12074 Flatlands Avenue p/o Lot 1 Site
Brooklyn, New York
NYSDEC BCP Site No.: C224353
Langan Project No.: 100688803

Analyte	CAS Number	NYSDEC SGVs
Volatile Organic Compounds (ug/l)		
1,1,1-Trichloroethane	71-55-6	5
1,1-Dichloroethane	75-34-3	5
1,1-Dichloroethene	75-35-4	5
1,2,4-Trimethylbenzene	95-63-6	5
1,2-Dichlorobenzene	95-50-1	3
1,2-Dichloroethane	107-06-2	0.6
1,3,5-Trimethylbenzene (Mesitylene)	108-67-8	5
1,3-Dichlorobenzene	541-73-1	3
1,4-Dichlorobenzene	106-46-7	3
1,4-Dioxane (P-Dioxane)	123-91-1	0.35
Acetone	67-64-1	50
Benzene	71-43-2	1
Carbon Tetrachloride	56-23-5	5
Chlorobenzene	108-90-7	5
Chloroform	67-66-3	7
Cis-1,2-Dichloroethene	156-59-2	5
Ethylbenzene	100-41-4	5
Hexachlorobenzene	118-74-1	0.5
Methyl Ethyl Ketone (2-Butanone)	78-93-3	50
Methylene Chloride	75-09-2	5
Naphthalene	91-20-3	10
n-Butylbenzene	104-51-8	5
n-Propylbenzene	103-65-1	5
Sec-Butylbenzene	135-98-8	5
T-Butylbenzene	98-06-6	5
Tert-Butyl Methyl Ether	1634-04-4	10
Tetrachloroethene (PCE)	127-18-4	5
Toluene	108-88-3	5
Total Xylenes	1330-20-7	5
Trans-1,2-Dichloroethene	156-60-5	5
Trichloroethene (TCE)	79-01-6	5
Vinyl Chloride	75-01-4	2
Semivolatile Organic Compounds (ug/l)		
Naphthalene	91-20-3	10

Table 2
Site Management Plan
Soil Sample Analytical Results

12074 Flatlands Avenue p/o Lot 1 Site
Brooklyn, New York
BCP Site No. C224353
Langan Project No.: 100688803

Analyte	CAS Number	NYSDEC Part 375 Unrestricted Use SCOs	NYSDEC Part 375 Protection of Groundwater SCOs	NYSDEC Part 375 Restricted Use Restricted-Residential SCOs	Location	PE01	PE03	PE04	PE04	PE05	PE06	PE07	PE08	PE09	PE10	PE11	PE12	PE13	PE14	PE15	PE16	PE17
					Sample Name	PE01_8	PE03_15.5	PE04_15	DUP_07212025	PE05_15	PE06_15	PE07_15	PE08_15	PE09_15	PE10_15	PE11_16.5	PE12_15	PE13_15	PE14_15	PE15_23.5	PE16_15	PE17_15
					Sample Date	06/16/2025	08/15/2025	07/21/2025	07/21/2025	07/21/2025	07/21/2025	07/21/2025	07/14/2025	06/19/2025	06/19/2025	08/13/2025	07/28/2025	07/21/2025	07/21/2025	07/21/2025	07/14/2025	06/19/2025
					Sample Elevation	8	15.5	15	15	15	15	15	15	15	15	16.5	15	15	15	23.5	15	15
					Unit	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result
Volatile Organic Compounds																						
1,1,1,2-Tetrachloroethane	630-20-6	NS	NS	NS	mg/kg	<0.0058 U	<0.0028 U	<0.0092 UJ	<0.007 UJ	<0.0093 UJ	<0.0092 UJ	<0.0089 U	<0.0052 U	<0.0048 U	<0.005 U	<0.0033 U	<0.0061 U	<0.0078 UJ	<0.0081 UJ	<0.0074 UJ	<0.0057 U	<0.0063 U
1,1,1-Trichloroethane	71-55-6	0.68	0.68	100	mg/kg	<0.0058 U	<0.0028 U	<0.0092 U	<0.007 U	<0.0093 U	<0.0092 U	<0.0089 U	<0.0052 U	<0.0048 U	<0.005 U	<0.0033 U	<0.0061 U	<0.0078 U	<0.0081 U	<0.0074 U	<0.0057 U	<0.0063 U
1,1,2,2-Tetrachloroethane	79-34-5	NS	NS	NS	mg/kg	<0.0058 U	<0.0028 U	<0.0092 U	<0.007 U	<0.0093 U	<0.0092 U	<0.0089 U	<0.0052 U	<0.0048 U	<0.005 U	<0.0033 U	<0.0061 U	<0.0078 U	<0.0081 U	<0.0074 U	<0.0057 U	<0.0063 U
1,1,2-Trichloro-1,2,2-Trifluoroethane	76-13-1	NS	NS	NS	mg/kg	<0.0058 U	<0.0028 U	<0.0092 U	<0.007 U	<0.0093 U	<0.0092 U	<0.0089 U	<0.0052 U	<0.0048 U	<0.005 U	<0.0033 U	<0.0061 U	<0.0078 U	<0.0081 U	<0.0074 U	<0.0057 U	<0.0063 U
1,1,2-Trichloroethane	79-00-5	NS	NS	NS	mg/kg	<0.0058 U	<0.0028 U	<0.0092 U	<0.007 U	<0.0093 U	<0.0092 U	<0.0089 U	<0.0052 U	<0.0048 U	<0.005 U	<0.0033 U	<0.0061 U	<0.0078 U	<0.0081 U	<0.0074 U	<0.0057 U	<0.0063 U
1,1-Dichloroethane	75-34-3	0.27	0.27	47	mg/kg	<0.0058 U	<0.0028 UJ	<0.0092 U	<0.007 U	<0.0093 U	<0.0092 U	<0.0089 U	<0.0052 U	<0.0048 U	<0.005 U	<0.0033 U	<0.0061 U	<0.0078 U	<0.0081 U	<0.0074 U	<0.0057 U	<0.0063 U
1,1-Dichloroethene	75-35-4	0.24	0.33	0.98	mg/kg	<0.0058 U	<0.0028 U	<0.0092 U	<0.007 U	<0.0093 U	<0.0092 U	<0.0089 U	<0.0052 U	<0.0048 U	<0.005 U	<0.0033 U	<0.0061 U	<0.0078 U	<0.0081 U	<0.0074 U	<0.0057 U	<0.0063 U
1,1-Dichloropropene	563-58-6	NS	NS	NS	mg/kg	<0.0058 U	<0.0028 U	<0.0092 U	<0.007 U	<0.0093 U	<0.0092 U	<0.0089 U	<0.0052 U	<0.0048 U	<0.005 U	<0.0033 U	<0.0061 U	<0.0078 U	<0.0081 U	<0.0074 U	<0.0057 U	<0.0063 U
1,2,3-Trichlorobenzene	87-61-6	NS	NS	NS	mg/kg	<0.0058 U	<0.0028 U	<0.0092 U	<0.007 U	<0.0093 U	<0.0092 U	<0.0089 U	<0.0052 U	<0.0048 U	<0.005 U	<0.0033 U	<0.0061 U	<0.0078 U	<0.0081 U	<0.0074 U	<0.0057 U	<0.0063 U
1,2,3-Trichloropropane	96-18-4	NS	NS	NS	mg/kg	<0.0058 U	<0.0028 U	<0.0092 U	<0.007 U	<0.0093 U	<0.0092 U	<0.0089 U	<0.0052 U	<0.0048 U	<0.005 U	<0.0033 U	<0.0061 U	<0.0078 U	<0.0081 U	<0.0074 U	<0.0057 U	<0.0063 U
1,2,4-Trichlorobenzene	120-82-1	NS	NS	NS	mg/kg	<0.0058 U	<0.0028 U	<0.0092 U	<0.007 U	<0.0093 U	<0.0092 U	<0.0089 U	<0.0052 U	<0.0048 U	<0.005 U	<0.0033 U	<0.0061 U	<0.0078 U	<0.0081 U	<0.0074 U	<0.0057 U	<0.0063 U
1,2,4-Trimethylbenzene	95-63-6	5.9	5.9	100	mg/kg	<0.0058 U	<0.0028 U	<0.0092 U	<0.007 U	<0.0093 U	<0.0092 U	<0.0089 U	<0.0052 U	<0.0048 U	<0.005 U	<0.0033 U	<0.0061 U	<0.0078 U	<0.0081 U	<0.0074 U	<0.0057 U	<0.0063 U
1,2-Dibromo-3-Chloropropane	96-12-8	NS	NS	NS	mg/kg	<0.0058 U	<0.0028 U	<0.0092 U	<0.007 U	<0.0093 U	<0.0092 U	<0.0089 U	<0.0052 U	<0.0048 U	<0.005 U	<0.0033 U	<0.0061 U	<0.0078 U	<0.0081 U	<0.0074 U	<0.0057 U	<0.0063 U
1,2-Dibromoethane (Ethylene Dibromide)	106-93-4	NS	NS	NS	mg/kg	<0.0058 U	<0.0028 U	<0.0092 U	<0.007 U	<0.0093 U	<0.0092 U	<0.0089 U	<0.0052 U	<0.0048 U	<0.005 U	<0.0033 U	<0.0061 U	<0.0078 U	<0.0081 U	<0.0074 U	<0.0057 U	<0.0063 U
1,2-Dichlorobenzene	95-50-1	1.1	1.1	100	mg/kg	<0.0058 U	<0.0028 U	<0.0092 U	<0.007 U	<0.0093 U	<0.0092 U	<0.0089 U	<0.0052 U	<0.0048 U	<0.005 U	<0.0033 U	<0.0061 U	<0.0078 U	<0.0081 U	<0.0074 U	<0.0057 U	<0.0063 U
1,2-Dichloroethane	107-06-2	0.02	0.02	5.8	mg/kg	<0.0058 U	<0.0028 U	<0.0092 U	<0.007 U	<0.0093 U	<0.0092 U	<0.0089 U	<0.0052 U	<0.0048 U	<0.005 U	<0.0033 U	<0.0061 U	<0.0078 U	<0.0081 U	<0.0074 U	<0.0057 U	<0.0063 U
1,2-Dichloropropane	78-87-5	NS	NS	NS	mg/kg	<0.0058 U	<0.0028 U	<0.0092 U	<0.007 U	<0.0093 U	<0.0092 U	<0.0089 U	<0.0052 U	<0.0048 U	<0.005 U	<0.0033 U	<0.0061 U	<0.0078 U	<0.0081 U	<0.0074 U	<0.0057 U	<0.0063 U
1,3,5-Trimethylbenzene (Mesitylene)	108-67-8	3.1	3.1	100	mg/kg	<0.0058 U	<0.0028 U	<0.0092 U	<0.007 U	<0.0093 U	<0.0092 U	<0.0089 U	<0.0052 U	<0.0048 U	<0.005 U	<0.0033 U	<0.0061 U	<0.0078 U	<0.0081 U	<0.0074 U	<0.0057 U	<0.0063 U
1,3-Dichlorobenzene	541-73-1	2.6	2.6	38	mg/kg	<0.0058 U	<0.0028 U	<0.0092 U	<0.007 U	<0.0093 U	<0.0092 U	<0.0089 U	<0.0052 U	<0.0048 U	<0.005 U	<0.0033 U	<0.0061 U	<0.0078 U	<0.0081 U	<0.0074 U	<0.0057 U	<0.0063 U
1,3-Dichloropropane	142-28-9	NS	NS	NS	mg/kg	<0.0058 U	<0.0028 U	<0.0092 U	<0.007 U	<0.0093 U	<0.0092 U	<0.0089 U	<0.0052 U	<0.0048 U	<0.005 U	<0.0033 U	<0.0061 U	<0.0078 U	<0.0081 U	<0.0074 U	<0.0057 U	<0.0063 U
1,4-Dichlorobenzene	106-46-7	1.8	1.8	24	mg/kg	<0.0058 U	<0.0028 U	<0.0092 U	<0.007 U	<0.0093 U	<0.0092 U	<0.0089 U	<0.0052 U	<0.0048 U	<0.005 U	<0.0033 U	<0.0061 U	<0.0078 U	<0.0081 U	<0.0074 U	<0.0057 U	<0.0063 U
1,4-Dioxane (P-Dioxane)	123-91-1	0.1	0.1	5.7	mg/kg	<0.12 U	NA	NA	NA	NA	NA	NA	<0.1 U	<0.097 U	<0.1 U	NA	NA	NA	NA	NA	<0.11 U	<0.13 U
2,2-Dichloropropane	594-20-7	NS	NS	NS	mg/kg	<0.0058 U	<0.0028 U	<0.0092 U	<0.007 U	<0.0093 U	<0.0092 U	<0.0089 U	<0.0052 U	<0.0048 UJ	<0.005 UJ	<0.0033 U	<0.0061 U	<0.0078 U	<0.0081 U	<0.0074 U	<0.0057 U	<0.0063 UJ
2-Chlorotoluene	95-49-8	NS	NS	NS	mg/kg	<0.0058 U	<0.0028 U	<0.0092 U	<0.007 U	<0.0093 U	<0.0092 U	<0.0089 U	<0.0052 U	<0.0048 U	<0.005 U	<0.0033 U	<0.0061 U	<0.0078 U	<0.0081 U	<0.0074 U	<0.0057 U	<0.0063 U
2-Hexanone (MBK)	591-78-6	NS	NS	NS	mg/kg	<0.0058 U	<0.0028 U	<0.0092 U	<0.007 U	<0.0093 U	<0.0092 U	<0.0089 U	<0.0052 U	<0.0048 U	<0.005 U	<0.0033 U	<0.0061 U	<0.0078 U	<0.0081 U	<0.0074 U	<0.0057 U	<0.0063 U
4-Chlorotoluene	106-43-4	NS	NS	NS	mg/kg	<0.0058 U	<0.0028 U	<0.0092 U	<0.007 U	<0.0093 U	<0.0092 U	<0.0089 U	<0.0052 U	<0.0048 U	<0.005 U	<0.0033 U	<0.0061 U	<0.0078 U	<0.0081 U	<0.0074 U	<0.0057 U	<0.0063 U
Acetone	67-64-1	**0.03**	0.03	100	mg/kg	<0.012 U	0.03	**0.13**	**0.055**	**0.063**	**0.046**	**0.057**	0.026	**0.033**	0.025	<0.0067 U	0.026	**0.067**	**0.078**	**0.045**	0.025	0.029
Acrolein	107-02-8	NS	NS	NS	mg/kg	<0.012 U	<0.0056 U	<0.018 U	<0.014 U	<0.019 U	<0.018 U	<0.018 U	<0.01 U	<0.0097 U	<0.01 U	<0.0067 U	<0.012 U	<0.016 U	<0.016 U	<0.015 U	<0.011 U	<0.013 U
Acrylonitrile	107-13-1	NS	NS	NS	mg/kg	<0.0058 U	<0.0028 UJ	<0.0092 U	<0.007 U	<0.0093 U	<0.0092 U	<0.0089 U	<0.0052 U	<0.0048 U	<0.005 U	<0.0033 U	<0.0061 U	<0.0078 U	<0.0081 U	<0.0074 U	<0.0057 U	<0.0063 U
Benzene	71-43-2	0.06	0.06	3.7	mg/kg	<0.0058 U	<0.0028 U	<0.0092 U	<0.007 U	<0.0093 U	<0.0092 U	<0.0089 U	<0.0052 U	<0.0048 U	<0.005 U	<0.0033 U	<0.0061 U	<0.0078 U	<0.0081 U	<0.0074 U	<0.0057 U	<0.0063 U
Bromobenzene	108-86-1	NS	NS	NS	mg/kg	<0.0058 U	<0.0028 U	<0.0092 U	<0.007 U	<0.0093 U	<0.0092 U	<0.0089 U	<0.0052 U	<0.0048 U	<0.005 U	<0.0033 U	<0.0061 U	<0.0078 U	<0.0081 U	<0.0074 U	<0.0057 U	<0.0063 U
Bromochloromethane	74-97-5	NS	NS	NS	mg/kg	<0.0058 U	<0.0028 U	<0.0092 U	<0.007 U	<0.0093 U	<0.0092 U	<0.0089 U	<0.0052 U	<0.0048 U	<0.005 U	<0.0033 U	<0.0061 U	<0.0078 U	<0.0081 U	<0.0074 U	<0.0057 U	<0.0063 U
Bromodichloromethane	75-27-4	NS	NS	NS	mg/kg	<0.0058 U	<0.0028 U	<0.0092 U	<0.007 U	<0.0093 U	<0.0092 U	<0.0089 U	<0.0052 U	<0.0048 U	<0.005 U	<0.0033 U	<0.0061 U	<0.0078 U	<0.0081 U	<0.0074 U	<0.0057 U	<0.0063 U
Bromoform	75-25-2	NS	NS	NS	mg/kg	<0.0058 U	<0.0028 U	<0.0092 U	<0.007 U	<0.0093 U	<0.0092 UJ	<0.0089 U	<0.0052 U	<0.0048 U	<0.005 U	<0.0033 U	<0.0061 U	<0.0078 U	<0.0081 UJ	<0.0074 UJ	<0.0057 U	<0.0063 U
Bromomethane	74-83-9	NS	NS	NS	mg/kg	<0.0058 U	<0.0028 U	<0.0092 U	<0.007 U	<0.0093 U	<0.0092 U	<0.0089 U	<0.0052 U	<0.0048 U	<0.005 U	<0.0033 U	<0.0061 U	<0.0078 U	<0.0081 U	<0.0074 U	<0.0057 U	<0.0063 U
Carbon Disulfide	75-15-0	NS	NS	NS	mg/kg	<0.0058 U	<0.0028 U	0.009 J	0.0045 J	<0.0093 U	0.0048 J	<0.0089 U	0.0052 J	<0.0048 U	<0.005 U	<0.0033 U	<0.0061 U	<0.0078 U	<0.0081 U	<0.0074 U	<0.0057 U	<0.0063 U
Carbon Tetrachloride	56-23-5	0.76	0.76	7.1	mg/kg	<0.0058 U	<0.0028 U	<0.0092 U	<0.007 U	<0.0093 U	<0.0092 U	<0.0089 U	<0.0052 U	<0.0048 U	<0.005 U	<0.0033 U	<0.0061 U	<0.0078 U	<0.0081 U	<0.0074 U	<0.0057 U	<0.0063 U
Chlorobenzene	108-90-7	4.5	4.5	100	mg/kg	<0.0058 U	<0.0028 U	<0.0092 U	<0.007 U	<0.0093 U	<0.0092 U	<0.0089 U	<0.0052 U	<0.0048 U	<0.005 U	<0.0033 U	<0.0061 U	<0.0078 U	<0.0081 U	<0.0074 U	<0.0057 U	<0.0063 U
Chloroethane	75-00-3	NS	NS	NS	mg/kg	<0.0058 U	<0.0028 U	<0.0092 U	<0.007 U	<0.0093 U	<0.0092 U	<0.0089 U	<0.0052 U	<0.0048 U	<0.005 U	<0.0033 U	<0.0061 U	<0.0078 U	<0.0081 U	<0.0074 U	<0.0057 U	<0.0063 U
Chloroform	67-66-3	0.37	0.37	24	mg/kg	<0.0058 U	<0.0028 U	<0.0092 U	<0.007 U	<0.0093 U	<0.0092 UJ	<0.0089 U	<0.0052 U	<0.0048 U	<0.005 U	<0.0033 U	<0.0061 U	<0.0078 U	<0.0081 UJ	<0.0074 UJ	<0.0057 U	<0.0063 U
Chloromethane	74-87-3	NS	NS	NS	mg/kg	<0.0058 U	<0.0028 U	<0.0092 U	<0.007 U	<0.0093 U	<0.0092 U	<0.0089 U	<0.0052 U	<0.0048 U	<0.005 U	<0.0033 U	<0.0061 U	<0.0078 U	<0.0081 U	<0.0074 U	<0.0057 U	<0.0063 U
Cis-1,2-Dichloroethene	156-59-2	0.19	0.19	41	mg/kg	<0.0058 U	<0.0028 U	<0.0092 U	<0.007 U	<0.0093 U	<0.0092 U	<0.0089 U	<0.0052 U	<0.0048 UJ	<0.005 UJ	<0.0033 U	<0.0061 U	<0.0078 U	<0.0081 U	<0.0074 U	<0.0057 U	<0.0063 UJ
Cis-1,3-Dichloropropene	10061-01-5	NS	NS	NS	mg/kg	<0.0058 U	<0.0028 U	<0.0092 U	<0.007 U	<0.0093 U	<0.0092 U	<0.0089 U	<0.0052 U	<0.0048 U	<0.005 U	<0.0033 U	<0.0061 U	<0.0078 U	<0.0081 U	<0.0074 U	<0.0057 U	<0.0063 U
Cyclohexane	110-82-7	NS	NS	NS	mg/kg	<0.0058 U	<0.0028 U	<0.0092 U	<0.007 U	<0.0093 U	<0.0092 U	<0.0089 U	<0.0052 U	<0.0048 U	<0.005 U	<0.0033 U	<0.0061 U	<0.0078 U	<0.0081 U	<0.0074 U	<0.0057 U	<0.0063 U
Cymene	99-87-6	NS	NS	NS	mg/kg	<0.0058 U	<0.0028 U	<0.0092 U	<0.007 U	<0.0093 U	<0.0092 U	<0.0089 U	<0.0052 U	<0.0048 U	<0.005 U	<0.0033 U	<0.0061 U	<0.0078 U	<0.0081 U	<0.0074 U	<0.0057 U	<0.0063 U
Dibromochloromethane	124-48-1	NS	NS	NS	mg/kg	<0.0058 U	<0.0028 U	<0.0092 U	<0.007 U	<0.0093 U	<0.0092 U	<0.0089 U	<0.0052 U	<0.0048 U	<0.005 U	<0.0033 U	<0.0061 U	<0.0078 U	<0.0081 U	<0.0074 U	<0.0057 U	<0.0063 U
Dibromomethane	74-95-3	NS	NS	NS	mg/kg	<0.0058 U	<0.0028 U	<0.0092 U	<0.007 U	<0.0093 U	<0.0092 U	<0.0089 U	<0.0052 U	<0.0048 U	<0.005 U	<0.0033 U	<0.0061 U	<0.0078 U	<0.0081 U	<0.0074 U	<0.0057 U	<0.0063 U
Dichlorodifluoromethane	75-71-8	NS	NS	NS	mg/kg	<0.0058 UJ	<0.0028 UJ	<0.0092 U	<0.007 U	<0.0093 U	<0.0092 U	<0.0089 U	<0.0052 U	<0.0048 U	<0.005 U	<0.0033 U	<0.0061 U	<0.0078 U	<0.0081 U	<0.0074 U	<0.0057 U	<0.0063 U
Ethylbenzene	100-41-4	1	1	76	mg/kg	<0.0058 U	<0.0028 U	<0.0092 U	<0.007 U	<0.0093 U	<0.0092 U	<0.0089 U	<0.0052 U	<0.0048 U	<0.005 U	<0.0033 U	<0.0061 U	<0.0078 U	<0.0081 U	<0.0074 U	<0.0057 U	<0.0063 U
Hexachlorobutadiene	87-68-3	NS	NS	NS	mg/kg	<0.0058 U	<0.0028 U	<0.0092 UJ	<0.007 UJ	<0.0093 UJ	<0.0092 UJ	<0.0089 U	<0.0052 U	<0.0048 U	<0.005 U	<0.0033 U	<0.0061 U	<0.0078 UJ	<0.0081 UJ	<0.0074 UJ	<0.0057 U	<0.0063 U
Isopropylbenzene (Cumene)	98-82-8	NS	NS	NS	mg/kg	<0.0058 U	<0.0028 U	<0.0092 U	<0.007 U	<0.0093 U	<0.0092 U	<0.0089 U	<0.0052 U	<0.0048 U	<0.005 U	<0.0033 U	<0.0061 U	<0.0078 U	<0.0081 U	<0.0074 U	<0.0057 U	<0.0063 U
M,P-Xylene	179601-23-1	NS	NS	NS	mg/kg	<0.012 U	<0.0056 U	<0.018 U	<0.014 U	<0.019 U	<0.018 U	<0.018 U	<0.01 U	<0.0097 U	<0.01 U	<0.0067 U	<0.012 U	<0.016 U	<0.016 U	<0.015 U	<0.011 U	<0.013 U
Methyl Acetate	79-20-9	NS	NS	NS	mg/kg	<0.0058 U	<0.0028 U	<0.0092 U	<0.007 U	<0.0093 U	<0.0092 U	<0.0089 U	<0.0052 UJ	<0.0048 U	<0.005 U	<0.0033 U	0.006 J	<0.0078 U	<0.0081 U	<0.0074 U	<0.0057 UJ	<0.0063 U
Methyl Ethyl Ketone (2-Butanone)	78-93-3	0.1	0.1	100	mg/kg	<0.0058 U	<0.0028 UJ	0.036	0.014	0.012	0.011	0.007 J	<0.0052 U	<0.0048 U	<0.005 U	<0.0033 U	<0.0061 U	0.02	0.015	0.015	<0.0057 U	<0.0063 U
Methyl Isobutyl Ketone (4-Methyl-2-Pentanone)	108-10-1	NS	NS	NS	mg/kg	<0.0058 U	<0.0028 U	<0.0092 U	<0.007 U	<0.0093 U	<0.0092 U	<0.0089 U	<0.0052 U	<0.0048 U	<0.005 U	<0.0033 U	<0.0061 U	<0.0078 U	<0.0081 U	<0.0074 U	<0.0057 U	<0.0063 U
Methylcyclohexane	108-87-2	NS	NS	NS	mg/kg	<0.0058 U	<0.0028 U	<0.0092 U	<0.007 U	<0.0093 U	<0.0092 U	<0.0089 U	<0.0052 U	<0.0048 U	<0.005 U	<0.0033 U	<0.0061 U	<0.0078 U	0.014	<0.0074 U	<0.0057 U	<0.0063 U
Methylene Chloride	75-09-2	0.05	0.05	81	mg/kg	<0.012 U	<0.0056 U	<0.018 U	<0.014 U	<0.019 U	<0.018 U	<0.018 U	<0.01 U	<0.0097 U	<0.01 U	<0.012 U	<0.012 U	<0.016 U	<0.016 U	<0.015 U	<0.011 U	<0.013 U
n-Butylbenzene	104-51-8	18	18	100	mg/kg	<0.0058 U	<0.0028 UJ	<0.0092 U	<0.007 U	<0.0093 U	<0.0092 U	<0.0089 U	<0.0052 U	<0.0048 U	<0.005 U	<0.0033 U	<0.0061 U	<0.0078 U	<0.0081 U	<0.0074 U	<0.0057 U	<0.0063 U
n-Propylbenzene	103-65-1	5	5	100	mg/kg	<0.0058 U	<0.0028 U	<0.0092 U	<0.007 U	<0.0093 U	<0.0092 U	<0.0089 U	<0.0052 U	<0.0048 U	<0.005 U	<0.0033 U	<0.0061 U	<0.0078 U	<0.0081 U	<0.0074 U	<0.0057 U	<0.0063 U
o-Xylene (1,2-Dimethylbenzene)	95-47-6	NS	NS	NS	mg/kg	<0.0058 U	<0.0028 U	<0.0092 U	<0.007 U	<0.0093 U	<0.0092 U	<0.0089 U	<0.0052 U	<0.0048 U	<0.005 U	<0.0033 U	<0.0061 U	<0.0078 U	<0.0081 U	<0.0074 U	<0.0057 U	<0.0063 U
Sec-Butylbenzene	135-98-8	25	25	100	mg/kg	<0.0058 U	<0.0028 U	<0.0092 U	<0.007 U	<0.0093 U	<0.0092 U	<0.0089 U	<0.0052 U	<0.0048 U	<0.005 U	<0.0033 U	<0.0061 U	<0.0078 U	<0.0081 U	<0.0074 U	<0.0057 U	<0.0063 U
Styrene	100-42-5	NS	NS	NS	mg/kg	<0.0058 U	<0.0028 U	<0.0092 U	<0.007 U	<0.0093 U	<0.0092 U	<0.0089 U	<0.0052 U	<0.0048 U	<0.005 U	<0.0033 U	<0.0061 U	<0.0078 U	<0.0081 U	<0.0074 U	<0.0057 U	<0.0063 U
T-Butylbenzene	98-06-6	11	11	100	mg/kg	<0.0058 U	<0.0028 U	<0.0092 U	<0.007 U	<0.0093 U	<0.0092 U	<0.0089 U	<0.0052 U	<0.0048 UJ	<0.005 UJ	<0.0033 U	<0.0061 UJ	<0.0078 U	<0.0081 U	<0.0074 U	<0.0057 U	<0.0063 UJ
Tert-Butyl Alcohol	75-65-0	NS	NS	NS	mg/kg	<0.029 U	<0.014 U	<0.046 U	<0.035 U	<0.047 U	<0.046 U	<0.044 U	<0.026 U	<0.024 U	<0.025 U	<0.017 U	<0.031 U	<0.039 U	<0.04 U	<0.037 U	<0.029 U	<0.032 U
Tert-Butyl Methyl Ether (MTBE)	1634-04-4	0.1	0.1	100	mg/kg	<0.0058 U	<0.0028 U	<0.0092 U	<0.007 U	<0.0093 U	<0.0092 U	<0.0089 U	<0.0052 U	<0.0048 U	<0.005 U	<0.0033 U	<0.0061 U	<0.0078 U	<0.0081 U	<0.0074 U	<0.0057 U	<0.0063 U
Tetrachloroethene (PCE)	127-18-4	1.3	1.3	18	mg/kg	<0.0058 U	<0.0028 U	<0.0092 U	<0.007 U	<0.0093 U	<0.0092 UJ	<0.0089 U	<0.0052 U	<0.0048 U	<0.005 U	<0.0033 U	<0.0061 U	<0.0078 U	<0.0081 UJ	<0.0074 UJ	<0.0057 U	<0.0063 U
Toluene	108-88-3	0.7	0.7	100	mg/kg	<0.0058 U	<0.0028 U	<0.0092 U	<0.007 U	<0.0093 U	<0.0092 U	<0.0089 U	<0.0052 U	<0.0048 U	<0.005 U	<0.0033 U	<0.0061 U	<0.0078 U	<0.0081 U	<0.0074 U	<0.0057 U	<0.0063 U
Total Xylenes	1330-20-7	0.26	1.2	100	mg/kg	<0.017 U	<0.0085 U	<0.028 U	<0.021 U	<0.028 U	<0.028 U	<0.027 U	<0.016 U	<0.015 U	<0.015 U	<0.01 U	<0.018 U	<0.023 U	<0.024 U	<0.022 U	<0.017 U	<0.019 U
Trans-1,2-Dichloroethene	156-60-5	0.19	0.19	100	mg/kg	<0.0058 U	<0.0028 U	<0.0092 U	<0.007 U	<0.0093 U	<0.0092 U	<0.0089 U	<0.0052 U	<0.0048 U	<0.005 U	<0.0033 U	<0.0061 U	<0.0078 U	<0.0081 U	<0.0074 U	<0.0057 U	<0.0063 U
Trans-1,3-Dichloropropene	10061-02-6	NS	NS	NS	mg/kg	<0.0058 U	<0.0028 U	<0.0092 U	<0.007 U	<0.0093 U	<0.0092 U	<0.0089 U	<0.0052 U	<0.0048 U	<0.005 U	<0.0033 U	<0.0061 U	<0.0078 U	<0.0081 U	<0.0074 U	<0.0057 U	<0.0063 U
Trans-1,4-Dichloro-2-Butene	110-57-6	NS	NS	NS	mg/kg	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
Trichloroethene (TCE)	79-01-6	0.47	0.47	6.4	mg/kg	<0.0058 U	<0.0028 U	<0.0092 U	<0.007 U	<0.0093 U	<0.0092 U	<0.0089 U	<0.0052 U	<0.0048 U	<0.005 U	<0.0033 U	<0.0061 U	<0.0078 U	<0.0081 U	<0.0074 U	<0.0057 U	<0.0063 U
Trichlorofluoromethane	75-69-4	NS	NS	NS	mg/kg	<0.0058 U	<0.0028 U	<0.0092 U	<0.007 U	<0.0093 U	<0.0092 U	<0.0089 U	<0.0052 U	<0.0048 U	<0.005 U	<0.0033 U	<0.0061 U	<0.0078 U	<0.0081 U	<0.0074 U	<0.0057 U	<0.0063 U
Vinyl Chloride	75-01-4	0.03	0.03	0.48	mg/kg	<0.0058 U	<0.0028 UJ	<0.0092 U	<0.007 U	<0.0093 U	<0.0092 U	<0.0089 U	<0.0052 U	<0.0048 U	<0.005 U	<0.0033 U	<0.0061 U	<0.0078 U	<0.0081 U	<0.0074 U	<0.0057 U	<0.0063 U

Table 2
Site Management Plan
Soil Sample Analytical Results

12074 Flatlands Avenue p/o Lot 1 Site
Brooklyn, New York
BCP Site No. C224353
Langan Project No.: 100688803

Analyte	CAS Number	NYSDEC Part 375 Unrestricted Use SCOs	NYSDEC Part 375 Protection of Groundwater SCOs	NYSDEC Part 375 Restricted Use Restricted-Residential SCOs	Location	PE01	PE03	PE04	PE04	PE05	PE06	PE07	PE08	PE09	PE10	PE11	PE12	PE13	PE14	PE15	PE16	PE17
					Sample Name	PE01_8	PE03_15.5	PE04_15	DUP_07212025	PE05_15	PE06_15	PE07_15	PE08_15	PE09_15	PE10_15	PE11_16.5	PE12_15	PE13_15	PE14_15	PE15_23.5	PE16_15	PE17_15
					Sample Date	06/16/2025	08/15/2025	07/21/2025	07/21/2025	07/21/2025	07/21/2025	07/21/2025	07/14/2025	06/19/2025	06/19/2025	08/13/2025	07/28/2025	07/21/2025	07/21/2025	07/21/2025	07/14/2025	06/19/2025
					Sample Elevation	8	15.5	15	15	15	15	15	15	15	15	16.5	15	15	15	23.5	15	15
					Unit	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result
Semi-Volatile Organic Compounds																						
1,2,4,5-Tetrachlorobenzene	95-94-3	NS	NS	NS	mg/kg	<0.187 U	<0.178 U	<0.264 U	<0.224 U	<0.248 U	<0.319 U	<0.227 U	<0.197 U	<0.194 U	<0.189 U	<0.176 U	<0.175 UJ	<0.267 U	<0.221 U	<0.235 U	<0.187 U	<0.181 U
1,2,4-Trichlorobenzene	120-82-1	NS	NS	NS	mg/kg	<0.0938 U	<0.0889 U	<0.132 U	<0.112 U	<0.124 U	<0.16 U	<0.114 U	<0.0988 U	<0.0971 U	<0.0946 U	<0.088 U	<0.0878 UJ	<0.133 U	<0.111 U	<0.118 U	<0.0934 U	<0.0905 U
1,2-Dichlorobenzene	95-50-1	1.1	1.1	100	mg/kg	<0.0938 U	<0.0889 U	<0.132 U	<0.112 U	<0.124 U	<0.16 U	<0.114 U	<0.0988 U	<0.0971 U	<0.0946 U	<0.088 U	<0.0878 UJ	<0.133 U	<0.111 U	<0.118 U	<0.0934 U	<0.0905 U
1,2-Diphenylhydrazine	122-66-7	NS	NS	NS	mg/kg	<0.0938 U	<0.0889 U	<0.132 U	<0.112 U	<0.124 U	<0.16 U	<0.114 U	<0.0988 U	<0.0971 U	<0.0946 U	<0.088 U	<0.0878 UJ	<0.133 U	<0.111 U	<0.118 U	<0.0934 U	<0.0905 U
1,3-Dichlorobenzene	541-73-1	2.6	2.6	38	mg/kg	<0.0938 U	<0.0889 U	<0.132 U	<0.112 U	<0.124 U	<0.16 U	<0.114 U	<0.0988 U	<0.0971 U	<0.0946 U	<0.088 U	<0.0878 UJ	<0.133 U	<0.111 U	<0.118 U	<0.0934 U	<0.0905 U
1,4-Dichlorobenzene	106-46-7	1.8	1.8	24	mg/kg	<0.0938 U	<0.0889 U	<0.132 U	<0.112 U	<0.124 U	<0.16 U	<0.114 U	<0.0988 U	<0.0971 U	<0.0946 U	<0.088 U	<0.0878 UJ	<0.133 U	<0.111 U	<0.118 U	<0.0934 U	<0.0905 U
1,4-Dioxane (P-Dioxane)	123-91-1	0.1	0.1	5.7	mg/kg	<0.0189 U	<0.0198 U	<0.0189 U	<0.0192 U	<0.0196 U	<0.0198 U	<0.0192 U	<0.0192 U	<0.0198 U	<0.0198 U	<0.0194 U	<0.0198 U	<0.0198 U	<0.0198 U	<0.0192 U	<0.0192 U	<0.0198 U
2,3,4,6-Tetrachlorophenol	58-90-2	NS	NS	NS	mg/kg	<0.187 U	<0.178 U	<0.264 U	<0.224 U	<0.248 U	<0.319 U	<0.227 U	<0.197 U	<0.194 U	<0.189 UJ	<0.176 U	<0.175 UJ	<0.267 U	<0.221 U	<0.235 U	<0.187 U	<0.181 U
2,4,5-Trichlorophenol	95-95-4	NS	NS	NS	mg/kg	<0.0938 U	<0.0889 U	<0.132 U	<0.112 U	<0.124 U	<0.16 U	<0.114 U	<0.0988 U	<0.0971 U	<0.0946 UJ	<0.088 U	<0.0878 UJ	<0.133 U	<0.111 U	<0.118 U	<0.0934 U	<0.0905 U
2,4,6-Trichlorophenol	88-06-2	NS	NS	NS	mg/kg	<0.0938 U	<0.0889 U	<0.132 U	<0.112 U	<0.124 U	<0.16 U	<0.114 U	<0.0988 U	<0.0971 U	<0.0946 UJ	<0.088 U	<0.0878 UJ	<0.133 U	<0.111 U	<0.118 U	<0.0934 U	<0.0905 U
2,4-Dichlorophenol	120-83-2	NS	NS	NS	mg/kg	<0.0938 U	<0.0889 U	<0.132 U	<0.112 U	<0.124 U	<0.16 U	<0.114 U	<0.0988 U	<0.0971 U	<0.0946 UJ	<0.088 U	<0.0878 UJ	<0.133 U	<0.111 U	<0.118 U	<0.0934 U	<0.0905 U
2,4-Dimethylphenol	105-67-9	NS	NS	NS	mg/kg	<0.0938 U	<0.0889 U	<0.132 U	<0.112 U	<0.124 U	<0.16 U	<0.114 U	<0.0988 U	<0.0971 U	<0.0946 UJ	<0.088 U	<0.0878 UJ	<0.133 U	<0.111 U	<0.118 U	<0.0934 U	<0.0905 U
2,4-Dinitrophenol	51-28-5	NS	NS	NS	mg/kg	<0.187 U	<0.178 UJ	<0.264 U	<0.224 U	<0.248 U	<0.319 U	<0.227 U	<0.197 U	<0.194 U	<0.189 UJ	<0.176 U	<0.175 UJ	<0.267 U	<0.221 U	<0.235 U	<0.187 U	<0.181 U
2,4-Dinitrotoluene	121-14-2	NS	NS	NS	mg/kg	<0.0938 U	<0.0889 U	<0.132 U	<0.112 U	<0.124 U	<0.16 U	<0.114 U	<0.0988 U	<0.0971 U	<0.0946 U	<0.088 U	<0.0878 UJ	<0.133 U	<0.111 U	<0.118 U	<0.0934 U	<0.0905 U
2,6-Dinitrotoluene	606-20-2	NS	NS	NS	mg/kg	<0.0938 U	<0.0889 U	<0.132 U	<0.112 U	<0.124 U	<0.16 U	<0.114 U	<0.0988 U	<0.0971 U	<0.0946 U	<0.088 U	<0.0878 UJ	<0.133 U	<0.111 U	<0.118 U	<0.0934 U	<0.0905 U
2-Chloronaphthalene	91-58-7	NS	NS	NS	mg/kg	<0.0938 U	<0.0889 U	<0.132 U	<0.112 U	<0.124 U	<0.16 U	<0.114 U	<0.0988 U	<0.0971 U	<0.0946 U	<0.088 U	<0.0878 UJ	<0.133 U	<0.111 U	<0.118 U	<0.0934 U	<0.0905 U
2-Chlorophenol	95-57-8	NS	NS	NS	mg/kg	<0.0938 U	<0.0889 U	<0.132 U	<0.112 U	<0.124 U	<0.16 U	<0.114 U	<0.0988 U	<0.0971 U	<0.0946 UJ	<0.088 U	<0.0878 UJ	<0.133 U	<0.111 U	<0.118 U	<0.0934 U	<0.0905 U
2-Methylnaphthalene	91-57-6	NS	NS	NS	mg/kg	0.0517 JD	<0.0889 U	<0.132 U	<0.112 U	<0.124 U	<0.16 U	<0.114 U	<0.0988 U	<0.0971 U	0.569 D	<0.088 U	<0.0878 UJ	<0.133 U	<0.111 U	<0.118 U	<0.0934 U	<0.0905 U
2-Methylphenol (o-Cresol)	95-48-7	0.33	0.33	100	mg/kg	<0.0938 U	<0.0889 U	<0.132 U	<0.112 U	<0.124 U	<0.16 U	<0.114 U	<0.0988 U	<0.0971 U	<0.0946 UJ	<0.088 U	<0.0878 UJ	<0.133 U	<0.111 U	<0.118 U	<0.0934 U	<0.0905 U
2-Nitroaniline	88-74-4	NS	NS	NS	mg/kg	<0.187 U	<0.178 U	<0.264 U	<0.224 U	<0.248 U	<0.319 U	<0.227 U	<0.197 U	<0.194 U	<0.189 U	<0.176 U	<0.175 UJ	<0.267 U	<0.221 U	<0.235 U	<0.187 U	<0.181 U
2-Nitrophenol	88-75-5	NS	NS	NS	mg/kg	<0.0938 U	<0.0889 U	<0.132 U	<0.112 U	<0.124 U	<0.16 U	<0.114 U	<0.0988 U	<0.0971 U	<0.0946 UJ	<0.088 U	<0.0878 UJ	<0.133 U	<0.111 U	<0.118 U	<0.0934 U	<0.0905 U
3 & 4 Methylphenol (m&p Cresol)	65794-96-9	**0.33**	0.33	100	mg/kg	<0.0938 U	<0.0889 U	<0.132 U	<0.112 U	<0.124 U	<0.16 U	<0.114 U	<0.0988 U	<0.0971 U	<0.0946 UJ	<0.088 U	<0.0878 UJ	<0.133 U	<0.111 U	<0.118 U	<0.0934 U	<0.0905 U
3,3'-Dichlorobenzidine	91-94-1	NS	NS	NS	mg/kg	<0.0938 U	<0.0889 U	<0.132 U	<0.112 U	<0.124 U	<0.16 U	<0.114 U	<0.0988 U	<0.0971 U	<0.0946 U	<0.088 U	<0.0878 UJ	<0.133 U	<0.111 U	<0.118 U	<0.0934 U	<0.0905 U
3-Nitroaniline	99-09-2	NS	NS	NS	mg/kg	<0.187 U	<0.178 U	<0.264 U	<0.224 U	<0.248 U	<0.319 U	<0.227 U	<0.197 U	<0.194 U	<0.189 U	<0.176 U	<0.175 UJ	<0.267 U	<0.221 U	<0.235 U	<0.187 U	<0.181 U
4,6-Dinitro-2-Methylphenol	534-52-1	NS	NS	NS	mg/kg	<0.187 U	<0.178 UJ	<0.264 U	<0.224 U	<0.248 U	<0.319 U	<0.227 U	<0.197 U	<0.194 U	<0.189 UJ	<0.176 U	<0.175 UJ	<0.267 U	<0.221 U	<0.235 U	<0.187 U	<0.181 U
4-Bromophenyl Phenyl Ether	101-55-3	NS	NS	NS	mg/kg	<0.0938 U	<0.0889 U	<0.132 U	<0.112 U	<0.124 U	<0.16 U	<0.114 U	<0.0988 U	<0.0971 U	<0.0946 U	<0.088 U	<0.0878 UJ	<0.133 U	<0.111 U	<0.118 U	<0.0934 U	<0.0905 U
4-Chloro-3-Methylphenol	59-50-7	NS	NS	NS	mg/kg	<0.0938 U	<0.0889 U	<0.132 U	<0.112 U	<0.124 U	<0.16 U	<0.114 U	<0.0988 U	<0.0971 U	<0.0946 UJ	<0.088 U	<0.0878 UJ	<0.133 U	<0.111 U	<0.118 U	<0.0934 U	<0.0905 U
4-Chloroaniline	106-47-8	NS	NS	NS	mg/kg	<0.0938 U	<0.0889 U	<0.132 U	<0.112 U	<0.124 U	<0.16 U	<0.114 U	<0.0988 U	<0.0971 U	<0.0946 U	<0.088 U	<0.0878 UJ	<0.133 U	<0.111 U	<0.118 U	<0.0934 U	<0.0905 U
4-Chlorophenyl Phenyl Ether	7005-72-3	NS	NS	NS	mg/kg	<0.0938 U	<0.0889 U	<0.132 U	<0.112 U	<0.124 U	<0.16 U	<0.114 U	<0.0988 U	<0.0971 U	<0.0946 U	<0.088 U	<0.0878 UJ	<0.133 U	<0.111 U	<0.118 U	<0.0934 U	<0.0905 U
4-Nitroaniline	100-01-6	NS	NS	NS	mg/kg	<0.187 U	<0.178 U	<0.264 U	<0.224 U	<0.248 U	<0.319 U	<0.227 U	<0.197 U	<0.194 U	<0.189 U	<0.176 U	<0.175 UJ	<0.267 U	<0.221 U	<0.235 U	<0.187 U	<0.181 U
4-Nitrophenol	100-02-7	NS	NS	NS	mg/kg	<0.187 U	<0.178 U	<0.264 U	<0.224 U	<0.248 U	<0.319 U	<0.227 U	<0.197 U	<0.194 U	<0.189 UJ	<0.176 U	<0.175 UJ	<0.267 U	<0.221 U	<0.235 U	<0.187 U	<0.181 U
Acenaphthene	83-32-9	20	98	100	mg/kg	0.0525 JD	<0.0889 U	<0.132 U	<0.112 U	<0.124 U	<0.16 U	<0.114 U	<0.0988 U	<0.0971 U	<0.0946 U	<0.088 U	<0.0878 UJ	<0.133 U	<0.111 U	<0.118 U	<0.0934 U	<0.0905 U
Acenaphthylene	208-96-8	100	365	100	mg/kg	<0.0938 U	<0.0889 U	<0.132 U	<0.112 U	<0.124 U	<0.16 U	<0.114 U	<0.0988 U	<0.0971 U	<0.0946 U	<0.088 U	<0.0878 UJ	<0.133 U	<0.111 U	<0.118 U	<0.0934 U	<0.0905 U
Acetophenone	98-86-2	NS	NS	NS	mg/kg	<0.0938 U	<0.0889 U	<0.132 U	<0.112 U	<0.124 U	<0.16 U	<0.114 U	<0.0988 U	<0.0971 U	<0.0946 U	<0.088 U	<0.0878 UJ	<0.133 U	<0.111 U	<0.118 U	<0.0934 U	<0.0905 U
Aniline (Phenylamine, Aminobenzene)	62-53-3	0.04	0.04	8.1	mg/kg	<0.375 U	<0.356 U	<0.529 U	<0.449 U	<0.498 U	<0.639 U	<0.455 U	<0.396 U	<0.389 U	<0.379 U	<0.353 U	<0.352 UJ	<0.534 U	<0.443 U	<0.471 U	<0.374 U	<0.363 U
Anthracene	120-12-7	100	1000	100	mg/kg	0.112 D	<0.0889 U	<0.132 U	<0.112 U	<0.124 U	<0.16 U	<0.114 U	<0.0988 U	<0.0971 U	<0.0946 U	<0.088 U	0.059 J	<0.133 U	<0.111 U	<0.118 U	<0.0934 U	<0.0905 U
Atrazine	1912-24-9	NS	NS	NS	mg/kg	<0.0938 U	<0.0889 U	<0.132 U	<0.112 U	<0.124 U	<0.16 U	<0.114 U	<0.0988 U	<0.0971 U	<0.0946 U	<0.088 U	<0.0878 UJ	<0.133 U	<0.111 U	<0.118 U	<0.0934 U	<0.0905 U
Benzaldehyde	100-52-7	NS	NS	NS	mg/kg	<0.0938 U	<0.0889 U	<0.132 U	<0.112 U	<0.124 U	<0.16 U	<0.114 U	<0.0988 U	<0.0971 U	<0.0946 U	<0.088 U	<0.0878 UJ	<0.133 U	<0.111 U	<0.118 U	<0.0934 U	<0.0905 U
Benzidine	92-87-5	NS	NS	NS	mg/kg	<0.375 U	<0.356 U	<0.529 U	<0.449 U	<0.498 U	<0.639 U	<0.455 U	<0.396 U	<0.389 U	<0.379 U	<0.353 U	<0.352 UJ	<0.534 U	<0.443 U	<0.471 U	<0.374 U	<0.363 U
Benzo(a)anthracene	56-55-3	**1**	1	1.4	mg/kg	0.254 D	<0.0889 U	<0.132 U	<0.112 U	<0.124 U	<0.16 U	<0.114 U	<0.0988 U	<0.0971 U	<0.0946 U	<0.088 U	0.17 J	<0.133 U	0.0867 JD	<0.118 U	<0.0934 U	<0.0905 U
Benzo(a)pyrene	50-32-8	**1**	22	1	mg/kg	0.241 D	<0.0889 U	<0.132 U	<0.112 U	<0.124 U	<0.16 U	<0.114 U	<0.0988 U	<0.0971 U	<0.0946 U	<0.088 U	<0.0878 UJ	<0.133 U	<0.111 U	<0.118 U	<0.0934 U	<0.0905 U
Benzo(b)fluoranthene	205-99-2	**1**	2.1	1.4	mg/kg	0.244 D	<0.0889 U	<0.132 U	<0.112 U	<0.124 U	<0.16 U	<0.114 U	<0.0988 U	<0.0971 U	<0.0946 U	<0.088 U	<0.0878 UJ	<0.133 U	<0.111 U	<0.118 U	<0.0934 U	<0.0905 U
Benzo(g,h,i)Perylene	191-24-2	**0.64**	1000	4.9	mg/kg	0.142 D	<0.0889 U	<0.132 U	<0.112 U	<0.124 U	<0.16 U	<0.114 U	<0.0988 U	<0.0971 U	<0.0946 U	<0.088 U	0.0681 J	<0.133 U	<0.111 U	<0.118 U	<0.0934 U	<0.0905 U
Benzo(k)fluoranthene	207-08-9	**0.8**	2	4.9	mg/kg	0.0884 JD	<0.0889 U	<0.132 U	<0.112 U	<0.124 U	<0.16 U	<0.114 U	<0.0988 U	<0.0971 U	<0.0946 U	<0.088 U	<0.0878 UJ	<0.133 U	<0.111 U	<0.118 U	<0.0934 U	<0.0905 U
Benzoic Acid	65-85-0	NS	NS	NS	mg/kg	<0.0938 U	<0.0889 U	<0.132 U	<0.112 U	<0.124 U	<0.16 U	<0.114 U	<0.0988 U	<0.0971 U	<0.0946 U	<0.088 U	<0.0878 UJ	<0.133 U	<0.111 U	<0.118 U	<0.0934 U	<0.0905 U
Benzyl Alcohol	100-51-6	NS	NS	NS	mg/kg	<0.0938 U	<0.0889 U	<0.132 U	<0.112 U	<0.124 U	<0.16 U	<0.114 U	<0.0988 U	<0.0971 U	<0.0946 UJ	<0.088 U	<0.0878 UJ	<0.133 U	<0.111 U	<0.118 U	<0.0934 U	<0.0905 U
Benzyl Butyl Phthalate	85-68-7	NS	NS	NS	mg/kg	<0.0938 U	<0.0889 U	<0.132 U	<0.112 U	<0.124 U	<0.16 U	<0.114 U	<0.0988 U	<0.0971 U	<0.0946 U	<0.088 U	<0.0878 UJ	<0.133 U	<0.111 U	<0.118 U	<0.0934 U	<0.0905 U
Biphenyl (Diphenyl)	92-52-4	NS	NS	NS	mg/kg	<0.0938 U	<0.0889 U	<0.132 U	<0.112 U	<0.124 U	<0.16 U	<0.114 U	<0.0988 U	<0.0971 U	<0.0946 U	<0.088 U	<0.0878 UJ	<0.133 U	<0.111 U	<0.118 U	<0.0934 U	<0.0905 U
Bis(2-chloroethoxy) methane	111-91-1	NS	NS	NS	mg/kg	<0.0938 U	<0.0889 U	<0.132 U	<0.112 U	<0.124 U	<0.16 U	<0.114 U	<0.0988 U	<0.0971 U	<0.0946 U	<0.088 U	<0.0878 UJ	<0.133 U	<0.111 U	<0.118 U	<0.0934 U	<0.0905 U
Bis(2-chloroethyl) ether (2-chloroethyl ether)	111-44-4	NS	NS	NS	mg/kg	<0.0938 U	<0.0889 U	<0.132 U	<0.112 U	<0.124 U	<0.16 U	<0.114 U	<0.0988 U	<0.0971 U	<0.0946 U	<0.088 U	<0.0878 UJ	<0.133 U	<0.111 U	<0.118 U	<0.0934 U	<0.0905 U
Bis(2-chloroisopropyl) ether	108-60-1	NS	NS	NS	mg/kg	<0.0938 U	<0.0889 U	<0.132 U	<0.112 U	<0.124 U	<0.16 U	<0.114 U	<0.0988 U	<0.0971 U	<0.0946 U	<0.088 U	<0.0878 UJ	<0.133 U	<0.111 U	<0.118 U	<0.0934 U	<0.0905 U
Bis(2-ethylhexyl) phthalate	117-81-7	NS	NS	NS	mg/kg	<0.0938 U	<0.0889 U	<0.132 U	<0.112 U	0.202 D	0.745 D	<0.114 U	<0.0988 U	<0.0971 U	<0.0946 U	<0.088 U	0.46 J	<0.133 U	0.355 D	<0.118 U	<0.0934 U	<0.0905 U
Caprolactam	105-60-2	NS	NS	NS	mg/kg	<0.187 U	<0.178 U	<0.264 U	<0.224 U	<0.248 U	<0.319 U	<0.227 U	<0.197 U	<0.194 U	<0.189 U	<0.176 U	<0.175 UJ	<0.267 U	<0.221 U	<0.235 U	<0.187 U	<0.181 U
Carbazole	86-74-8	NS	NS	NS	mg/kg	<0.0938 U	<0.0889 U	<0.132 U	<0.112 U	<0.124 U	<0.16 U	<0.114 U	<0.0988 U	<0.0971 U	<0.0946 U	<0.088 U	<0.0878 UJ	<0.133 U	<0.111 U	<0.118 U	<0.0934 U	<0.0905 U
Chrysene	218-01-9	**1**	1	4.9	mg/kg	0.251 D	<0.0889 U	<0.132 U	<0.112 U	<0.124 U	<0.16 U	<0.114 U	<0.0988 U	<0.0971 U	<0.0946 U	<0.088 U	0.307 J	<0.133 U	0.0982 JD	<0.118 U	<0.0934 U	<0.0905 U
Dibenz(a,h)anthracene	53-70-3	**0.33**	1000	0.33	mg/kg	<0.0938 U	<0.0889 U	<0.132 U	<0.112 U	<0.124 U	<0.16 U	<0.114 U	<0.0988 U	<0.0971 U	<0.0946 U	<0.088 U	<0.0878 UJ	<0.133 U	<0.111 U	<0.118 U	<0.0934 U	<0.0905 U
Dibenzofuran	132-64-9	**2.1**	110	18	mg/kg	<0.0938 U	<0.0889 U	<0.132 U	<0.112 U	<0.124 U	<0.16 U	<0.114 U	<0.0988 U	<0.0971 U	<0.0946 U	<0.088 U	<0.0878 UJ	<0.133 U	<0.111 U	<0.118 U	<0.0934 U	<0.0905 U
Dibutyl phthalate	84-74-2	NS	NS	NS	mg/kg	<0.0938 U	<0.0889 U	<0.132 U	<0.112 U	<0.124 U	<0.16 U	<0.114 U	<0.0988 U	<0.0971 U	<0.0946 U	<0.088 U	<0.0878 UJ	<0.133 U	<0.111 U	<0.118 U	<0.0934 U	<0.0905 U
Diethyl phthalate	84-66-2	NS	NS	NS	mg/kg	<0.0938 U	<0.0889 U	<0.132 U	<0.112 U	<0.124 U	<0.16 U	<0.114 U	<0.0988 U	<0.0971 U	<0.0946 U	<0.088 U	<0.0878 UJ	<0.133 U	<0.111 U	<0.118 U	<0.0934 U	<0.0905 U
Dimethyl phthalate	131-11-3	NS	NS	NS	mg/kg	<0.0938 U	<0.0889 U	<0.132 U	<0.112 U	<0.124 U	<0.16 U	<0.114 U	<0.0988 U	<0.0971 U	<0.0946 U	<0.088 U	<0.0878 UJ	<0.133 U	<0.111 U	<0.118 U	<0.0934 U	<0.0905 U
Dioctyl phthalate	117-84-0	NS	NS	NS	mg/kg	<0.0938 U	<0.0889 U	<0.132 U	<0.112 U	<0.124 U	<0.16 U	<0.114 U	<0.0988 U	<0.0971 U	0.0575 JD	<0.088 U	<0.0878 UJ	<0.133 U	<0.111 U	<0.118 U	<0.0934 U	<0.0905 U
Fluoranthene	206-44-0	85	1000	100	mg/kg	0.438 D	<0.0889 U	<0.132 U	<0.112 U	<0.124 U	<0.16 U	<0.114 U	<0.0988 U	<0.0971 U	<0.0946 U	<0.088 U	0.211 J	<0.133 U	0.119 D	<0.118 U	<0.0934 U	<0.0905 U
Fluorene	86-73-7	30	386	100	mg/kg	0.0772 JD	<0.0889 U	<0.132 U	<0.112 U	<0.124 U	<0.16 U	<0.114 U	<0.0988 U	<0.0971 U	<0.0946 U	<0.088 U	<0.0878 UJ	<0.133 U	<0.111 U	<0.118 U	<0.0934 U	<0.0905 U
Hexachlorobenzene	118-74-1	0.33	3.2	0.33	mg/kg	<0.0938 U	<0.0889 U	<0.132 U	<0.112 U	<0.124 U	<0.16 U	<0.114 U	<0.0988 U	<0.0971 U	<0.0946 U	<0.088 U	<0.0878 UJ	<0.133 U	<0.111 U	<0.118 U	<0.0934 U	<0.0905 U
Hexachlorobutadiene	87-68-3	NS	NS	NS	mg/kg	<0.0938 U	<0.0889 U	<0.132 U	<0.112 U	<0.124 U	<0.16 U	<0.114 U	<0.0988 U	<0.0971 U	<0.0946 U	<0.088 U	<0.0878 UJ	<0.133 U	<0.111 U	<0.118 U	<0.0934 U	<0.0905 U
Hexachlorocyclopentadiene	77-47-4	NS	NS	NS	mg/kg	<0.0938 U	<0.0889 UJ	<0.132 U	<0.112 U	<0.124 U	<0.16 U	<0.114 U	<0.0988 UJ	<0.0971 UJ	<0.0946 UJ	<0.088 UJ	<0.0878 UJ	<0.133 U	<0.111 U	<0.118 U	<0.0934 UJ	<0.0905 UJ
Hexachloroethane	67-72-1	NS	NS	NS	mg/kg	<0.0938 U	<0.0889 U	<0.132 U	<0.112 U	<0.124 U	<0.16 U	<0.114 U	<0.0988 U	<0.0971 U	<0.0946 U	<0.088 U	<0.0878 UJ	<0.133 U	<0.111 U	<0.118 U	<0.0934 U	<0.0905 U
Indeno(1,2,3-cd)pyrene	193-39-5	**0.5**	6.6	1.4	mg/kg	0.14 D	<0.0889 U	<0.132 U	<0.112 U	<0.124 U	<0.16 U	<0.114 U	<0.0988 U	<0.0971 U	<0.0946 U	<0.088 U	<0.0878 UJ	<0.133 U	<0.111 U	<0.118 U	<0.0934 U	<0.0905 U
Isophorone	78-59-1	NS	NS	NS	mg/kg	<0.0938 U	<0.0889 U	<0.132 U	<0.112 U	<0.124 U	<0.16 U	<0.114 U	<0.0988 U	<0.0971 U	<0.0946 U	<0.088 U	<0.0878 UJ	<0.133 U	<0.111 U	<0.118 U	<0.0934 U	<0.0905 U
Naphthalene	91-20-3	12	12	100	mg/kg	<0.0938 U	<0.0889 U	<0.132 U	<0.112 U	<0.124 U	<0.16 U	<0.114 U	<0.0988 U	<0.0971 U	0.157 D	<0.088 U	<0.0878 UJ	<0.133 U	0.0628 JD	<0.118 U	<0.0934 U	<0.0905 U
Nitrobenzene	98-95-3	0.08	0.08	1.8	mg/kg	<0.0938 U	<0.0889 U	<0.132 U	<0.112 U	<0.124 U	<0.16 U	<0.114 U	<0.0988 U	<0.0971 U	<0.0946 U	<0.088 U	<0.0878 UJ	<0.133 U	<0.111 U	<0.118 U	<0.0934 U	<0.0905 U
n-Nitrosodimethylamine	62-75-9	NS	NS	NS	mg/kg	<0.0938 U	<0.0889 U	<0.132 U	<0.112 U	<0.124 U	<0.16 U	<0.114 U	<0.0988 U	<0.0971 U	<0.0946 U	<0.088 U	<0.0878 UJ	<0.133 U	<0.111 U	<0.118 U	<0.0934 U	<0.0905 U
n-Nitrosodi-N-Propylamine	621-64-7	NS	NS	NS	mg/kg	<0.0938 U	<0.0889 U	<0.132 U	<0.112 U	<0.124 U	<0.16 U	<0.114 U	<0.0988 U	<0.0971 U	<0.0946 U	<0.088 U	<0.0878 UJ	<0.133 U	<0.111 U	<0.118 U	<0.0934 U	<0.0905 U
n-Nitrosodiphenylamine	86-30-6	NS	NS	NS	mg/kg	<0.0938 U	<0.0889 U	<0.132 U	<0.112 U	<0.124 U	<0.16 U	<0.114 U	<0.0988 U	<0.0971 U	<0.0946 U	<0.088 U	<0.0878 UJ	<0.133 U	<0.111 U	<0.118 U	<0.0934 U	<0.0905 U
Pentachlorophenol	87-86-5	0.8	0.8	1.3	mg/kg	<0.0938 U	<0.0889 U	<0.132 U	<0.112 U	<0.124 U	<0.16 U	<0.114 U	<0.0988 U	<0.0971 U	<0.0946 UJ	<0.088 U	<0.0878 UJ	<0.133 U	<0.111 U	<0.118 U	<0.0934 U	<0.0905 U
Phenanthrene	85-01-8	**1.1**	1000	4.9	mg/kg	0.444 D	<0.0889 U	<0.132 U	<0.112 U	<0.124 U	<0.16 U	<0.114 U	<0.0988 U	<0.0971 U	<0.0946 U	<0.088 U	0.118 J	<0.133 U	0.061 JD	<0.118 U	<0.0934 U	<0.0905 U
Phenol	108-95-2	0.33	0.33	100	mg/kg	<0.0938 U	<0.0889 U	<0.132 U	<0.112 U	<0.124 U	<0.16 U	<0.114 U	<0.0988 U	<0.0971 U	<0.0946 UJ	<0.088 U	<0.0878 UJ	<0.133 U	<0.111 U	<0.118 U	<0.0934 U	<0.0905 U
Pyrene	129-00-0	64	1000	100	mg/kg	0.6 D	<0.0889 U	<0.132 U	<0.112 U	<0.124 U	<0.16 U	<0.114 U	<0.0988 U	<0.0971 U	<0.0946 U	<0.088 U	0.503 J	<0.133 U	0.17 D	<0.118 U	<0.0934 U	<0.0905 U
Pyridine	110-86-1	NS	NS	NS	mg/kg	<0.375 U	<0.356 U	<0.529 U	<0.449 U	<0.498 U	<0.639 U	<0.455 U	<0.396 U	<0.389 U	<0.379 U	<0.353 U	<0.352 UJ	<0.534 U	<0.443 U	<0.471 U	<0.374 U	<0.363 U

Table 2
Site Management Plan
Soil Sample Analytical Results

12074 Flatlands Avenue p/o Lot 1 Site
Brooklyn, New York
BCP Site No. C224353
Langan Project No.: 100688803

Analyte	CAS Number	NYSDEC Part 375 Unrestricted Use SCOs	NYSDEC Part 375 Protection of Groundwater SCOs	NYSDEC Part 375 Restricted Use Restricted-Residential SCOs	Location	PE01	PE03	PE04	PE04	PE05	PE06	PE07	PE08	PE09	PE10	PE11	PE12	PE13	PE14	PE15	PE16	PE17
					Sample Name	PE01_8	PE03_15.5	PE04_15	DUP_07212025	PE05_15	PE06_15	PE07_15	PE08_15	PE09_15	PE10_15	PE11_16.5	PE12_15	PE13_15	PE14_15	PE15_23.5	PE16_15	PE17_15
					Sample Date	06/16/2025	08/15/2025	07/21/2025	07/21/2025	07/21/2025	07/21/2025	07/21/2025	07/14/2025	06/19/2025	06/19/2025	08/13/2025	07/28/2025	07/21/2025	07/21/2025	07/21/2025	07/14/2025	06/19/2025
					Sample Elevation	8	15.5	15	15	15	15	15	15	15	15	16.5	15	15	15	23.5	15	15
					Unit	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result
Pesticides																						
4,4'-DDD	72-54-8	**0.0033**	14	5	mg/kg	<0.00186 U	<0.00172 U	<0.00261 UP	<0.00222 UP	<0.00246 UP	<0.00316 UP	<0.00225 UP	<0.00193 UP	<0.00192 U	<0.00187 U	<0.00176 U	<0.00175 UJ	<0.00264 UP	<0.00223 UJ	<0.00233 UP	<0.00182 UP	<0.00176 U
4,4'-DDE	72-55-9	**0.0033**	9.3	3.4	mg/kg	<0.00186 U	<0.00172 U	<0.00261 UP	<0.00222 UP	<0.00246 UP	<0.00316 UP	<0.00225 UP	<0.00193 UP	<0.00192 U	<0.00187 U	<0.00176 U	<0.00175 UJ	<0.00264 UP	<0.00223 UJ	<0.00233 UP	<0.00182 UP	<0.00176 U
4,4'-DDT	50-29-3	**0.0033**	135	3.8	mg/kg	<0.00186 U	<0.00172 U	<0.00261 UP	<0.00222 UP	<0.00246 UP	<0.00316 UP	<0.00225 UP	<0.00193 UP	<0.00192 U	<0.00187 U	<0.00176 U	<0.00175 UJ	<0.00264 UP	<0.00223 UJ	<0.00233 UP	<0.00182 UP	<0.00176 U
Aldrin	309-00-2	0.0048	0.19	0.044	mg/kg	<0.00186 U	<0.00172 U	<0.00261 UP	<0.00222 UP	<0.00246 UP	<0.00316 UP	<0.00225 UP	<0.00193 UP	<0.00192 U	<0.00187 U	<0.00176 U	<0.00175 UJ	<0.00264 UP	<0.00223 UJ	<0.00233 UP	<0.00182 UP	<0.00176 U
Alpha BHC (Alpha Hexachlorocyclohexane)	319-84-6	0.02	0.02	0.18	mg/kg	<0.00186 U	<0.00172 U	<0.00261 UP	<0.00222 UP	<0.00246 UP	<0.00316 UP	<0.00225 UP	<0.00193 UP	<0.00192 U	<0.00187 U	<0.00176 U	<0.00175 UJ	<0.00264 UP	<0.00223 UJ	<0.00233 UP	<0.00182 UP	<0.00176 U
Alpha Chlordane	5103-71-9	**0.014**	4.5	0.65	mg/kg	<0.00186 U	<0.00172 U	<0.00261 UP	<0.00222 UP	<0.00246 UP	<0.00316 UP	<0.00225 UP	<0.00193 UP	<0.00192 U	<0.00187 U	<0.00176 U	<0.00175 UJ	<0.00264 UP	<0.00223 UJ	<0.00233 UP	<0.00182 UP	<0.00176 U
Alpha Endosulfan	959-98-8	4.3	65	35	mg/kg	<0.00186 U	<0.00172 U	<0.00261 UP	<0.00222 UP	<0.00246 UP	<0.00316 UP	<0.00225 UP	<0.00193 UP	<0.00192 U	<0.00187 U	<0.00176 U	<0.00175 UJ	<0.00264 UP	<0.00223 UJ	<0.00233 UP	<0.00182 UP	<0.00176 U
Beta Bhc (Beta Hexachlorocyclohexane)	319-85-7	0.021	0.09	0.18	mg/kg	<0.00186 U	<0.00172 U	<0.00261 UP	<0.00222 UP	<0.00246 UP	<0.00316 UP	<0.00225 UP	<0.00193 UP	<0.00192 U	<0.00187 U	<0.00176 U	<0.00175 UJ	<0.00264 UP	<0.00223 UJ	<0.00233 UP	<0.00182 UP	<0.00176 U
Beta Endosulfan	33213-65-9	4.3	44	35	mg/kg	<0.00186 U	<0.00172 U	<0.00261 UP	<0.00222 UP	<0.00246 UP	<0.00316 UP	<0.00225 UP	<0.00193 UP	<0.00192 U	<0.00187 U	<0.00176 U	<0.00175 UJ	<0.00264 UP	<0.00223 UJ	<0.00233 UP	<0.00182 UP	<0.00176 U
Delta Bhc (Delta Hexachlorocyclohexane)	319-86-8	0.04	0.1	100	mg/kg	<0.00186 U	<0.00172 U	<0.00261 UP	<0.00222 UP	<0.00246 UP	<0.00316 UP	<0.00225 UP	<0.00193 UP	<0.00192 U	<0.00187 U	<0.00176 U	<0.00175 UJ	<0.00264 UP	<0.00223 UJ	<0.00233 UP	<0.00182 UP	<0.00176 U
Dieldrin	60-57-1	**0.005**	0.1	0.075	mg/kg	<0.00186 U	<0.00172 U	<0.00261 UP	<0.00222 UP	<0.00246 UP	<0.00316 UP	<0.00225 UP	<0.00193 UP	<0.00192 U	<0.00187 U	<0.00176 U	<0.00175 UJ	<0.00264 UP	<0.00223 UJ	<0.00233 UP	<0.00182 UP	<0.00176 U
Endosulfan Sulfate	1031-07-8	4.3	47	35	mg/kg	<0.00186 U	<0.00172 U	<0.00261 UP	<0.00222 UP	<0.00246 UP	<0.00316 UP	<0.00225 UP	<0.00193 UP	<0.00192 U	<0.00187 U	<0.00176 U	<0.00175 UJ	<0.00264 UP	<0.00223 UJ	<0.00233 UP	<0.00182 UP	<0.00176 U
Endrin	72-20-8	0.014	0.06	5.3	mg/kg	<0.00186 U	<0.00172 U	<0.00261 UP	<0.00222 UP	<0.00246 UP	<0.00316 UP	<0.00225 UP	<0.00193 UP	<0.00192 U	<0.00187 U	<0.00176 U	<0.00175 UJ	<0.00264 UP	<0.00223 UJ	<0.00233 UP	<0.00182 UP	<0.00176 U
Endrin Aldehyde	7421-93-4	NS	NS	NS	mg/kg	<0.00186 U	<0.00172 U	<0.00261 UP	<0.00222 UP	<0.00246 UP	<0.00316 UP	<0.00225 UP	<0.00193 UP	<0.00192 U	<0.00187 U	<0.00176 U	<0.00175 UJ	<0.00264 UP	<0.00223 UJ	<0.00233 UP	<0.00182 UP	<0.00176 U
Endrin Ketone	53494-70-5	NS	NS	NS	mg/kg	<0.00186 U	<0.00172 U	<0.00261 UP	<0.00222 UP	<0.00246 UP	<0.00316 UP	<0.00225 UP	<0.00193 UP	<0.00192 U	<0.00187 U	<0.00176 U	<0.00175 UJ	<0.00264 UP	<0.00223 UJ	<0.00233 UP	<0.00182 UP	<0.00176 U
Gamma Bhc (Lindane)	58-89-9	0.025	0.05	0.21	mg/kg	<0.00186 U	<0.00172 U	<0.00261 UP	<0.00222 UP	<0.00246 UP	<0.00316 UP	<0.00225 UP	<0.00193 UP	<0.00192 U	<0.00187 U	<0.00176 U	<0.00175 UJ	<0.00264 UP	<0.00223 UJ	<0.00233 UP	<0.00182 UP	<0.00176 U
Gamma-Chlordane	5566-34-7	NS	NS	NS	mg/kg	<0.00186 U	<0.00172 U	<0.00261 UP	<0.00222 UP	<0.00246 UP	<0.00316 UP	<0.00225 UP	<0.00193 UP	<0.00192 U	<0.00187 U	<0.00176 U	<0.00175 UJ	<0.00264 UP	<0.00223 UJ	<0.00233 UP	<0.00182 UP	<0.00176 U
Heptachlor	76-44-8	0.013	0.38	0.53	mg/kg	<0.00186 U	<0.00172 U	<0.00261 UP	<0.00222 UP	<0.00246 UP	<0.00316 UP	<0.00225 UP	<0.00193 UP	<0.00192 U	<0.00187 U	<0.00176 U	<0.00175 UJ	<0.00264 UP	<0.00223 UJ	<0.00233 UP	<0.00182 UP	<0.00176 U
Heptachlor Epoxide	1024-57-3	NS	NS	NS	mg/kg	<0.00186 U	<0.00172 U	<0.00261 UP	<0.00222 UP	<0.00246 UP	<0.00316 UP	<0.00225 UP	<0.00193 UP	<0.00192 U	<0.00187 U	<0.00176 U	<0.00175 UJ	<0.00264 UP	<0.00223 UJ	<0.00233 UP	<0.00182 UP	<0.00176 U
Methoxychlor	72-43-5	NS	NS	NS	mg/kg	<0.00186 U	<0.00172 U	<0.00261 UP	<0.00222 UP	<0.00246 UP	<0.00316 UP	<0.00225 UP	<0.00193 UP	<0.00192 U	<0.00187 U	<0.00176 U	<0.00175 UJ	<0.00264 UP	<0.00223 UJ	<0.00233 UP	<0.00182 UP	<0.00176 U
Toxaphene	8001-35-2	NS	NS	NS	mg/kg	<0.186 U	<0.172 U	<0.261 UP	<0.222 UP	<0.246 UP	<0.316 UP	<0.225 UP	<0.193 UP	<0.192 U	<0.187 U	<0.176 U	<0.175 UJ	<0.264 UP	<0.223 UJ	<0.233 UP	<0.182 UP	<0.176 U
Herbicides																						
2,4,5-T (Trichlorophenoxyacetic Acid)	93-76-5	NS	NS	NS	mg/kg	<0.0222 U	<0.0213 U	<0.0318 UP	<0.0269 UP	<0.0297 UP	<0.0383 UP	<0.0271 UP	<0.0234 UP	<0.0233 U	<0.0228 U	<0.0213 U	<0.0214 UP	<0.0319 UP	<0.0269 UP	<0.028 UP	<0.0223 UP	<0.0217 U
2,4-D (Dichlorophenoxyacetic Acid)	94-75-7	NS	NS	NS	mg/kg	<0.0222 U	<0.0213 U	<0.0318 UP	<0.0269 UP	<0.0297 UP	<0.0383 UP	<0.0271 UP	<0.0234 UP	<0.0233 U	<0.0228 U	<0.0213 U	<0.0214 UP	<0.0319 UP	<0.0269 UP	<0.028 UP	<0.0223 UP	<0.0217 U
2,4-Dichlorophenoxybutyric acid	94-82-6	NS	NS	NS	mg/kg	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
Dalapon	75-99-0	NS	NS	NS	mg/kg	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
Dicamba	1918-00-9	NS	NS	NS	mg/kg	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
Silvex (2,4,5-Tp)	93-72-1	3.8	3.8	100	mg/kg	<0.0222 U	<0.0213 U	<0.0318 UP	<0.0269 UP	<0.0297 UP	<0.0383 UP	<0.0271 UP	<0.0234 UP	<0.0233 U	<0.0228 U	<0.0213 U	<0.0214 UP	<0.0319 UP	<0.0269 UP	<0.028 UP	<0.0223 UP	<0.0217 U
Polychlorinated Biphenyl																						
PCB-1016 (Aroclor 1016)	12674-11-2	NS	NS	NS	mg/kg	<0.0188 U	<0.0174 U	<0.0265 UP	<0.0221 UP	<0.0246 UP	<0.0318 UP	<0.0225 UP	<0.0195 UP	<0.0193 U	<0.0188 U	<0.0178 U	<0.0177 UP	<0.0267 UP	<0.0222 UP	<0.0234 UP	<0.0184 UP	<0.0177 U
PCB-1221 (Aroclor 1221)	11104-28-2	NS	NS	NS	mg/kg	<0.0188 U	<0.0174 U	<0.0265 UP	<0.0221 UP	<0.0246 UP	<0.0318 UP	<0.0225 UP	<0.0195 UP	<0.0193 U	<0.0188 U	<0.0178 U	<0.0177 UP	<0.0267 UP	<0.0222 UP	<0.0234 UP	<0.0184 UP	<0.0177 U
PCB-1232 (Aroclor 1232)	11141-16-5	NS	NS	NS	mg/kg	<0.0188 U	<0.0174 U	<0.0265 UP	<0.0221 UP	<0.0246 UP	<0.0318 UP	<0.0225 UP	<0.0195 UP	<0.0193 U	<0.0188 U	<0.0178 U	<0.0177 UP	<0.0267 UP	<0.0222 UP	<0.0234 UP	<0.0184 UP	<0.0177 U
PCB-1242 (Aroclor 1242)	53469-21-9	NS	NS	NS	mg/kg	<0.0188 U	<0.0174 U	<0.0265 UP	<0.0221 UP	<0.0246 UP	<0.0318 UP	<0.0225 UP	<0.0195 UP	<0.0193 U	<0.0188 U	<0.0178 U	<0.0177 UP	<0.0267 UP	<0.0222 UP	<0.0234 UP	<0.0184 UP	<0.0177 U
PCB-1248 (Aroclor 1248)	12672-29-6	NS	NS	NS	mg/kg	<0.0188 U	<0.0174 U	<0.0265 UP	<0.0221 UP	<0.0246 UP	<0.0318 UP	<0.0225 UP	<0.0195 UP	<0.0193 U	<0.0188 U	<0.0178 U	<0.0177 UP	<0.0267 UP	<0.0222 UP	<0.0234 UP	<0.0184 UP	<0.0177 U
PCB-1254 (Aroclor 1254)	11097-69-1	NS	NS	NS	mg/kg	<0.0188 U	<0.0174 U	<0.0265 UP	<0.0221 UP	<0.0246 UP	<0.0318 UP	<0.0225 UP	<0.0195 UP	<0.0193 U	<0.0188 U	<0.0178 U	0.482	<0.0267 UP	<0.0222 UP	<0.0234 UP	<0.0184 UP	<0.0177 U
PCB-1260 (Aroclor 1260)	11096-82-5	NS	NS	NS	mg/kg	<0.0188 U	<0.0174 U	<0.0265 UP	<0.0221 UP	<0.0246 UP	<0.0318 UP	<0.0225 UP	<0.0195 UP	<0.0193 U	<0.0188 U	0.0299	<0.0177 UP	<0.0267 UP	0.151 P	<0.0234 UP	<0.0184 UP	<0.0177 U
PCB-1262 (Aroclor 1262)	37324-23-5	NS	NS	NS	mg/kg	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	0.562 J	NA	NA	NA	NA	NA
PCB-1268 (Aroclor 1268)	11100-14-4	NS	NS	NS	mg/kg	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
Total PCBs	1336-36-3	**0.1**	3.2	1	mg/kg	<0.0188 U	<0.0174 U	<0.0265 UP	<0.0221 UP	<0.0246 UP	<0.0318 UP	<0.0225 UP	<0.0195 UP	<0.0193 U	<0.0188 U	0.0299	**1.04 J**	<0.0267 UP	**0.151 P**	<0.0234 UP	<0.0184 UP	<0.0177 U
Metals																						
Aluminum	7429-90-5	NS	NS	NS	mg/kg	6,580	4,370	3,580	5,330	5,440	5,340	5,120	10,900	4,740	4,590	4,740	4,570	5,340	6,160	5,150	7,650	4,860
Antimony	7440-36-0	NS	NS	NS	mg/kg	<2.37 U	<2.23 UJ	58.6 J	13.2 J	<3.13 U	<4 U	<2.85 UJ	<2.48 U	<2.43 U	<2.39 U	<2.23 UJ	<2.25 U	<3.37 U	<2.82 U	<2.95 U	<2.34 U	<2.27 U
Arsenic	7440-38-2	**13**	16	16	mg/kg	4.6	<1.34 U	**38.5**	10	7.76	10.1	10.9	<1.49 U	1.59	<1.43 U	1.52	2.23	**13.6**	10.1	10.8	1.83	<1.36 U
Barium	7440-39-3	**410**	820	410	mg/kg	42.3	13.6	226 J	341	369	**718**	357	11	17.4	11.2	16.2	114	180	**618**	256	6.96	11.5
Beryllium	7440-41-7	4.4	47	43	mg/kg	0.171	0.134	0.248	0.516	0.468	0.6	0.415	0.145	0.116	0.124	0.11 J	0.149	0.691	0.512	0.552	0.149	0.128
Cadmium	7440-43-9	**2.5**	7.5	2.5	mg/kg	<0.284 U	<0.267 U	**2.95 J**	0.697	1.14	0.8	0.98	<0.297 U	0.428	<0.286 U	<0.267 U	0.306	<0.404 U	1.31	1.33	<0.281 U	<0.272 U
Calcium	7440-70-2	NS	NS	NS	mg/kg	1,620	1,080	10,100	19,000 J	6,080	2,950	5,130 J	508	801	444	1,270	3,580	13,200	12,800	2,680	511	618
Chromium, Hexavalent	18540-29-9	1	19	1	mg/kg	<0.568 U	<0.535 U	<0.804 U	<0.674 U	<0.751 U	<0.96 U	<0.684 UJ	<0.594 U	<0.584 UJ	<0.573 U	<0.535 UJ	<0.541 U	<0.808 U	<0.677 U	<0.707 U	<0.562 U	<0.545 U
Chromium, Total	7440-47-3	NS	NS	NS	mg/kg	11.4	9.22	40.9 J	10.9	19.8	18.9	12.9	16.9	8.84	8.23	8.72	10.6	9.27	18.9	32.8	14.1	8.12
Chromium, Trivalent	16065-83-1	**30**	19	110	mg/kg	11.4	9.22	**40.9**	10.9	19.8	18.9	12.9	16.9	8.84	8.23	8.15	10.6	9.27	18.9	**32.8**	14.1	8.12
Cobalt	7440-48-4	NS	NS	NS	mg/kg	3.95	4.78	19.2	4.64	4.94	7.89	5.01	3.64	3.75	4.24	4.75	4.31	10.6	6.01	6.85	4.66	3.43
Copper	7440-50-8	**50**	1720	280	mg/kg	25.6	8.88 J	**169**	**60**	**72.7**	**77.6**	**60.3**	8.13	13.4	12.7	9.19	19.2	25.3	**86.6**	**68.9**	8.98	7.63
Cyanide	57-12-5	**2.3**	40	13	mg/kg	<0.568 U	<0.535 U	<0.804 U	**2.37 J**	<0.751 U	<0.96 U	0.72 J	<0.594 U	<0.584 U	<0.573 U	<0.535 U	<0.541 U	<0.808 U	<0.677 U	<0.707 U	<0.562 U	<0.545 U
Iron	7439-89-6	NS	NS	NS	mg/kg	10,000	9,650	533,000 D	25,400	17,300	13,300	20,300	8,950	8,260	8,270	10,300	12,300	19,800	13,300	14,600	8,250	6,850
Lead	7439-92-1	**63**	450	400	mg/kg	51.4	3.19 J	**154 J**	**162 J**	**792**	**747**	**316 J**	4.7	21.3	2.77	8.71 J	**90.4**	**89.6**	**381**	**2,370**	3.42	2.04
Magnesium	7439-95-4	NS	NS	NS	mg/kg	1,470	1,730	687	731	620	571	547	1,770	2,080	2,250	2,000	2,070	395	972	545	1,710	1,860
Manganese	7439-96-5	**1600**	2000	2000	mg/kg	122	136	**1,720**	207	109	117	161	54.6	144	357	290	219	247	106	144	48.6	103
Mercury	7439-97-6	**0.18**	0.73	0.3	mg/kg	0.0986	<0.0321 U	0.17	0.0838	**5.3**	**0.235**	0.104	<0.0357 U	<0.0351 U	<0.0344 U	<0.0321 U	0.0444	0.178	**0.183**	**20.8 D**	<0.0337 U	<0.0327 U
Nickel	7440-02-0	**30**	130	320	mg/kg	11.8	14.1	**41.6 J**	11.8	14.4	18.4	18.7	12.6	15.5	20.4	16.5	12.4	19.9	14.6	15.9	14.9	12.8
Potassium	7440-09-7	NS	NS	NS	mg/kg	557 B	488	457	481	466	525	451	590	452	424	546	571	416	582	647	473	559
Selenium	7782-49-2	**3.9**	4	110	mg/kg	<2.37 U	<2.23 U	<3.35 U	<2.81 U	<3.13 U	<4 U	<2.85 U	<2.48 U	<2.43 U	<2.39 U	<2.23 U	<2.25 U	<3.37 U	<2.82 U	<2.95 U	<2.34 U	<2.27 U
Silver	7440-22-4	**2**	8.3	110	mg/kg	<0.477 U	<0.449 U	<0.676 U	0.742	0.763	1.5	<0.574 U	<0.499 U	<0.491 U	<0.481 U	<0.449 U	<0.454 U	<0.679 U	<0.568 U	<0.594 U	<0.472 U	<0.458 U
Sodium	7440-23-5	NS	NS	NS	mg/kg	105	71.7	1,080	863 J	270	303	273 J	76.4	91.2	69.3	97.3	98.1 J	311	373	393	65.8	76.4
Thallium	7440-28-0	NS	NS	NS	mg/kg	<1.9 U	<1.79 U	<2.69 U	<2.25 U	<2.51 U	<3.21 U	<2.28 U	<1.98 U	<1.95 U	<1.91 U	<1.79 U	<1.81 U	<2.7 U	<2.26 U	<2.36 U	<1.88 U	<1.82 U
Vanadium	7440-62-2	NS	NS	NS	mg/kg	16.1	12.5	8.5 J	17.9	26.4	25.2	21.8	20.4	14.2	10.6	14.2	13.4	30.5	21.4	21.6	17.1	10.4
Zinc	7440-66-6	**109**	2480	6600	mg/kg	73.5	47.3	**119 J**	**237**	**374**	**221**	**365**	14	29.2	19.3	29	**147**	**3,070**	**375**	**191**	13.1	12

Table 2
Site Management Plan
Soil Sample Analytical Results

12074 Flatlands Avenue p/o Lot 1 Site
Brooklyn, New York
BCP Site No. C224353
Langan Project No.: 100688803

Analyte	CAS Number	NYSDEC Part 375 Unrestricted Use SCOs	NYSDEC Part 375 Protection of Groundwater SCOs	NYSDEC Part 375 Restricted Use Restricted-Residential SCOs	Location	PE01	PE03	PE04	PE04	PE05	PE06	PE07	PE08	PE09	PE10	PE11	PE12	PE13	PE14	PE15	PE16	PE17
					Sample Name	PE01_8	PE03_15.5	PE04_15	DUP_07212025	PE05_15	PE06_15	PE07_15	PE08_15	PE09_15	PE10_15	PE11_16.5	PE12_15	PE13_15	PE14_15	PE15_23.5	PE16_15	PE17_15
					Sample Date	06/16/2025	08/15/2025	07/21/2025	07/21/2025	07/21/2025	07/21/2025	07/21/2025	07/14/2025	06/19/2025	06/19/2025	08/13/2025	07/28/2025	07/21/2025	07/21/2025	07/21/2025	07/14/2025	06/19/2025
					Sample Elevation	8	15.5	15	15	15	15	15	15	15	15	16.5	15	15	15	23.5	15	15
					Unit	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result
Per- and Polyfluoroalkyl Substances																						
11-Chloroeicosafluoro-3-Oxaundecane-1-Sulfonic Acid (11Cl-PF3OUdS)	763051-92-9	NS	NS	NS	mg/kg	<0.000852 U	<0.000807 UJ	<0.0012 U	<0.00102 UJ	<0.00113 UJ	<0.00145 UJ	<0.00103 UJ	<0.000895 UJ	<0.00088 U	<0.000863 U	<0.000806 U	<0.000814 U	<0.00121 UJ	<0.00102 UJ	<0.00107 UJ	<0.000845 UJ	<0.00082 U
1H,1H,2H,2H-Perfluorodecane Sulfonic Acid (8:2 FTS)	39108-34-4	NS	NS	NS	mg/kg	<0.000865 U	<0.00082 UJ	<0.00122 U	<0.00103 U	<0.00115 U	<0.00147 U	<0.00105 U	<0.000909 U	<0.000894 U	<0.000876 U	<0.000818 U	<0.000827 U	<0.00123 U	<0.00104 U	<0.00109 U	<0.000858 U	<0.000833 U
1H,1H,2H,2H-Perfluorohexane Sulfonic Acid (4:2 FTS)	757124-72-4	NS	NS	NS	mg/kg	<0.000845 U	<0.0008 UJ	<0.00119 U	<0.00101 U	<0.00113 U	<0.00144 U	<0.00102 U	<0.000888 U	<0.000873 U	<0.000856 U	<0.000799 U	<0.000808 U	<0.0012 U	<0.00102 U	<0.00106 U	<0.000838 U	<0.000814 U
1H,1H,2H,2H-Perfluorooctane Sulfonic Acid (6:2 FTS)	27619-97-2	NS	NS	NS	mg/kg	<0.000856 U	<0.000811 UJ	<0.00121 U	<0.00102 U	<0.00114 U	<0.00146 U	<0.00104 U	<0.0009 U	<0.000884 U	<0.000867 U	<0.00081 U	<0.000818 U	<0.00122 U	<0.00103 U	<0.00108 U	<0.000849 U	<0.000825 U
2H,2H,3H,3H-Perfluorooctanoic Acid (5:3 FTCA)	914637-49-3	NS	NS	NS	mg/kg	<0.00563 U	<0.00534 UJ	<0.00797 U	<0.00672 U	<0.00751 U	<0.0096 U	<0.00681 U	<0.00592 U	<0.00582 U	<0.00571 U	<0.00533 U	0.00113 J	<0.00803 U	<0.00677 U	<0.00707 U	<0.00559 U	<0.00542 U
3-Perfluoroheptyl Propanoic Acid (7:3 FTCA)	812-70-4	NS	NS	NS	mg/kg	<0.00563 U	<0.00534 UJ	<0.00797 U	<0.00672 U	<0.00751 U	<0.0096 U	<0.00681 U	<0.00592 U	<0.00582 U	<0.00571 U	<0.00533 U	0.00124 J	<0.00803 U	<0.00677 U	<0.00707 U	<0.00559 U	<0.00542 U
3-Perfluoropropyl Propanoic Acid (3:3 FTCA)	356-02-5	NS	NS	NS	mg/kg	<0.00113 U	<0.00107 UJ	<0.00159 U	<0.00134 U	<0.0015 U	<0.00192 U	<0.00136 U	<0.00118 U	<0.00116 UJ	<0.00114 UJ	<0.00107 U	<0.00108 U	<0.00161 U	<0.00135 U	<0.00141 U	<0.00112 U	<0.00108 UJ
4,8-Dioxa-3H-perfluorononanoic Acid (ADONA)	919005-14-4	NS	NS	NS	mg/kg	<0.000852 U	<0.000807 UJ	<0.0012 U	<0.00102 U	<0.00113 U	<0.00145 U	<0.00103 U	<0.000895 U	<0.00088 U	<0.000863 U	<0.000806 U	<0.000814 U	<0.00121 U	<0.00102 U	<0.00107 U	<0.000845 U	<0.00082 U
9-Chlorohexadecafluoro-3-Oxanonane-1-Sulfonic Acid (9Cl-PF3ONS)	756426-58-1	NS	NS	NS	mg/kg	<0.000843 U	<0.000798 UJ	<0.00119 UJ	<0.001 UJ	<0.00112 UJ	<0.00144 UJ	<0.00102 UJ	<0.000885 UJ	<0.00087 U	<0.000854 U	<0.000797 U	<0.000805 U	<0.0012 UJ	<0.00101 UJ	<0.00106 UJ	<0.000836 UJ	<0.000812 U
Hexafluoropropylene Oxide Dimer Acid (HFPO-DA)	13252-13-6	NS	NS	NS	mg/kg	<0.000901 U	<0.000854 UJ	<0.00127 UJ	<0.00107 UJ	<0.0012 UJ	<0.00154 UJ	<0.00109 UJ	<0.000947 UJ	<0.000931 U	<0.000913 U	<0.000852 U	<0.000861 U	<0.00129 UJ	<0.00108 UJ	<0.00113 UJ	<0.000894 UJ	<0.000868 U
N-ethyl Perfluorooctanesulfonamide (NEtFOSA)	4151-50-2	NS	NS	NS	mg/kg	<0.000225 U	<0.000213 UJ	<0.000319 U	<0.000269 U	<0.0003 U	<0.000384 U	<0.000272 U	<0.000237 U	<0.000233 U	<0.000228 U	<0.000213 U	<0.000215 U	<0.000321 U	<0.000271 U	<0.000283 U	<0.000223 U	<0.000217 U
N-ethyl Perfluorooctanesulfonamidoacetic Acid (NEtFOSAA)	2991-50-6	NS	NS	NS	mg/kg	<0.000225 U	<0.000534 UJ	<0.000319 U	<0.000269 U	<0.0003 U	<0.000384 U	<0.000272 U	<0.000237 UJ	<0.000233 U	<0.000228 U	<0.000213 U	<0.000215 U	<0.000321 U	<0.000271 U	<0.000283 U	<0.000223 UJ	<0.000217 U
N-ethyl Perfluorooctanesulfonamidoethanol (NEtFOSE)	1691-99-2	NS	NS	NS	mg/kg	<0.00225 U	<0.00213 UJ	<0.00319 U	<0.00269 U	<0.003 U	<0.00384 U	<0.00272 U	<0.00237 U	<0.00233 U	<0.00228 U	<0.00213 U	<0.00215 U	<0.00321 U	<0.00271 U	<0.00283 U	<0.00223 U	<0.00217 U
N-methyl Perfluorooctanesulfonamide (NMeFOSA)	31506-32-8	NS	NS	NS	mg/kg	<0.000225 U	<0.000213 UJ	<0.000319 U	<0.000269 U	<0.0003 U	<0.000384 U	<0.000272 U	<0.000237 UJ	<0.000233 U	<0.000228 U	<0.000213 U	<0.000215 U	<0.000321 U	<0.000271 U	<0.000283 U	<0.000223 UJ	<0.000217 U
N-methyl Perfluorooctanesulfonamidoacetic Acid (NMeFOSAA)	2355-31-9	NS	NS	NS	mg/kg	<0.000225 U	<0.000213 UJ	<0.000319 U	<0.000269 U	<0.0003 U	<0.000384 U	<0.000272 U	<0.000237 U	<0.000233 U	<0.000228 U	<0.000213 U	<0.000215 U	<0.000321 U	<0.000271 U	<0.000283 U	<0.000223 U	<0.000217 U
N-methyl Perfluorooctanesulfonamidoethanol (NMeFOSE)	24448-09-7	NS	NS	NS	mg/kg	<0.00225 U	<0.00213 UJ	<0.00319 U	<0.00269 U	<0.003 U	<0.00384 U	<0.00272 U	<0.00237 U	<0.00233 U	<0.00228 U	<0.00213 U	<0.00215 U	<0.00321 U	<0.00271 U	<0.00283 U	<0.00223 U	<0.00217 U
Nonafluoro-3,6-dioxaheptanoic Acid (NFDHA)	151772-58-6	NS	NS	NS	mg/kg	<0.000451 U	<0.000427 UJ	<0.000637 U	<0.000537 U	<0.0006 U	<0.000768 U	<0.000545 U	<0.000473 UJ	<0.000465 U	<0.000456 U	<0.000426 UJ	<0.000431 U	<0.000643 U	<0.000541 U	<0.000566 U	<0.000447 UJ	<0.000434 U
Perfluoro(2-ethoxyethane)sulfonic Acid (PFEESA)	113507-82-7	NS	NS	NS	mg/kg	<0.000401 U	<0.00038 UJ	<0.000567 U	<0.000478 U	<0.000534 U	<0.000683 U	<0.000485 U	<0.000421 U	<0.000414 U	<0.000406 U	<0.000379 U	<0.000383 U	<0.000572 U	<0.000482 U	<0.000504 U	<0.000398 U	<0.000386 U
Perfluoro-3-methoxypropanoic Acid (PFMPA)	377-73-1	NS	NS	NS	mg/kg	<0.000451 UJ	<0.000427 UJ	<0.000637 U	<0.000537 U	<0.0006 U	<0.000768 U	<0.000545 U	<0.000473 U	<0.000465 UJ	<0.000456 UJ	<0.000426 U	<0.000431 U	<0.000643 U	<0.000541 U	<0.000566 U	<0.000447 U	<0.000434 UJ
Perfluoro-4-methoxybutanoic Acid (PFMBA)	863090-89-5	NS	NS	NS	mg/kg	<0.000451 U	<0.000427 UJ	<0.000637 U	<0.000537 U	<0.0006 U	<0.000768 U	<0.000545 U	<0.000473 U	<0.000465 UJ	<0.000456 UJ	<0.000426 U	<0.000431 U	<0.000643 U	<0.000541 U	<0.000566 U	<0.000447 U	<0.000434 UJ
Perfluorobutanesulfonic Acid (PFBS)	375-73-5	NS	NS	NS	mg/kg	<0.000199 U	<0.000189 UJ	<0.000282 U	<0.000238 U	<0.000266 U	<0.00034 U	<0.000241 U	<0.00021 U	<0.000206 U	<0.000202 U	<0.000189 U	0.000102 J	<0.000284 U	<0.00024 U	<0.00025 U	<0.000198 U	<0.000192 U
Perfluorobutanoic Acid (PFBA)	375-22-4	NS	NS	NS	mg/kg	<0.000901 U	<0.000854 UJ	<0.00127 UJ	<0.00107 UJ	<0.0012 UJ	<0.00154 UJ	<0.00109 UJ	<0.000947 U	<0.000931 U	<0.000913 U	<0.000852 U	<0.000861 U	<0.00129 UJ	<0.00108 UJ	<0.00113 UJ	<0.000894 U	<0.000868 U
Perfluorodecanesulfonic Acid (PFDS)	335-77-3	NS	NS	NS	mg/kg	<0.000217 U	<0.000206 UJ	<0.000307 U	<0.000259 U	<0.00029 U	<0.00037 U	<0.000263 U	<0.000228 U	<0.000225 U	<0.00022 U	<0.000206 U	<0.000208 U	<0.00031 U	<0.000261 U	<0.000273 U	<0.000216 U	<0.000209 U
Perfluorodecanoic Acid (PFDA)	335-76-2	NS	NS	NS	mg/kg	<0.000225 U	<0.000213 UJ	<0.000319 U	<0.000269 U	<0.0003 U	<0.000384 U	<0.000272 U	<0.000237 U	<0.000233 U	<0.000228 U	<0.000213 U	<0.000215 U	<0.000321 U	<0.000271 U	<0.000283 U	<0.000223 U	<0.000217 U
Perfluorododecanesulfonic Acid (PFDoS)	79780-39-5	NS	NS	NS	mg/kg	<0.000219 U	<0.000207 UJ	<0.000309 U	<0.000261 U	<0.000291 U	<0.000372 U	<0.000264 U	<0.00023 U	<0.000226 U	<0.000221 U	<0.000207 U	<0.000209 U	<0.000312 U	<0.000263 U	<0.000274 U	<0.000217 U	<0.00021 U
Perfluorododecanoic Acid (PFDoA)	307-55-1	NS	NS	NS	mg/kg	<0.000225 U	<0.000213 UJ	<0.000319 U	<0.000269 U	<0.0003 U	<0.000384 U	<0.000272 U	<0.000237 U	<0.000233 U	<0.000228 U	<0.000213 U	<0.000215 U	<0.000321 U	<0.000271 U	<0.000283 U	<0.000223 U	<0.000217 U
Perfluoroheptanesulfonic Acid (PFHpS)	375-92-8	NS	NS	NS	mg/kg	<0.000225 U	<0.000213 UJ	<0.000319 U	<0.000269 U	<0.0003 U	<0.000384 U	<0.000272 U	<0.000237 UJ	<0.000233 U	<0.000228 U	<0.000213 U	<0.000215 U	<0.000321 U	<0.000271 U	<0.000283 U	<0.000223 UJ	<0.000217 U
Perfluoroheptanoic Acid (PFHpA)	375-85-9	NS	NS	NS	mg/kg	<0.000225 U	<0.000213 UJ	<0.000319 U	<0.000269 U	<0.0003 U	<0.000384 U	<0.000272 U	<0.000237 U	<0.000233 U	<0.000228 U	<0.000213 U	<0.000215 U	<0.000321 U	<0.000271 U	<0.000283 U	<0.000223 U	<0.000217 U
Perfluorohexanesulfonic Acid (PFHxS)	355-46-4	NS	NS	NS	mg/kg	<0.000206 U	<0.000195 UJ	<0.000292 U	<0.000246 U	<0.000275 U	<0.000351 U	<0.000249 U	<0.000217 U	<0.000213 U	<0.000209 U	<0.000195 U	<0.000197 U	<0.000294 U	<0.000248 U	<0.000259 U	<0.000204 U	<0.000199 U
Perfluorohexanoic Acid (PFHxA)	307-24-4	NS	NS	NS	mg/kg	<0.000225 U	<0.000213 UJ	<0.000319 U	<0.000269 U	<0.0003 U	<0.000384 U	<0.000272 U	<0.000237 U	<0.000233 U	<0.000228 U	<0.000213 U	<0.000215 U	<0.000321 U	<0.000271 U	<0.000283 U	<0.000223 U	<0.000217 U
Perfluorononanesulfonic Acid (PFNS)	68259-12-1	NS	NS	NS	mg/kg	<0.000216 U	<0.000205 UJ	<0.000306 UJ	<0.000258 UJ	<0.000288 UJ	<0.000369 UJ	<0.000261 UJ	<0.000227 U	<0.000223 U	<0.000219 U	<0.000205 U	<0.000207 U	<0.000308 UJ	<0.00026 UJ	<0.000272 UJ	<0.000215 U	<0.000208 U
Perfluorononanoic Acid (PFNA)	375-95-1	NS	NS	NS	mg/kg	<0.000225 U	<0.000213 UJ	<0.000319 U	<0.000269 U	<0.0003 U	<0.000384 U	<0.000272 U	<0.000237 UJ	<0.000233 U	<0.000228 U	<0.000213 U	<0.000215 U	<0.000321 U	<0.000271 U	<0.000283 U	<0.000223 UJ	<0.000217 U
Perfluorooctanesulfonamide (PFOSA)	754-91-6	NS	NS	NS	mg/kg	<0.000225 U	<0.000213 UJ	<0.000319 U	<0.000269 U	<0.0003 U	<0.000384 U	<0.000272 U	<0.000237 U	<0.000233 U	<0.000228 U	<0.000213 U	0.0000365 J	<0.000321 U	<0.000271 U	<0.000283 U	<0.000223 U	<0.000217 U
Perfluorooctanesulfonic Acid (PFOS)	1763-23-1	**0.00088**	0.001	0.044	mg/kg	0.0002 J	0.000169 J	0.000705	0.000681	0.000416	<0.000357 U	0.000241 J	<0.00022 U	<0.000216 U	<0.000212 U	<0.000198 U	<0.0002 U	0.000227 J	<0.000252 U	<0.000263 U	<0.000208 U	<0.000202 U
Perfluorooctanoic Acid (PFOA)	335-67-1	**0.00066**	0.0008	0.033	mg/kg	<0.000225 U	<0.000213 UJ	0.000182 J	<0.000269 U	0.000312	<0.000384 U	0.000161 J	<0.000237 U	<0.000233 U	<0.000228 U	<0.000213 U	0.000104 J	<0.000321 U	0.000139 J	0.000105 J	<0.000223 U	<0.000217 U
Perfluoropentanesulfonic Acid (PFPeS)	2706-91-4	NS	NS	NS	mg/kg	<0.000212 U	<0.000201 UJ	<0.000299 U	<0.000253 U	<0.000282 U	<0.000361 U	<0.000256 U	<0.000223 U	<0.000219 U	<0.000215 U	<0.0002 U	<0.000202 U	<0.000302 U	<0.000254 U	<0.000266 U	<0.00021 U	<0.000204 U
Perfluoropentanoic Acid (PFPeA)	2706-90-3	NS	NS	NS	mg/kg	<0.000451 U	<0.000427 UJ	<0.000637 U	<0.000537 U	<0.0006 U	<0.000768 U	<0.000545 U	<0.000473 U	<0.000465 U	<0.000456 U	<0.000426 U	<0.000431 U	<0.000643 U	<0.000541 U	<0.000566 U	<0.000447 U	<0.000434 U
Perfluorotetradecanoic Acid (PFTeDA)	376-06-7	NS	NS	NS	mg/kg	<0.000225 U	<0.000213 UJ	<0.000319 U	<0.000269 U	<0.0003 U	<0.000384 U	<0.000272 U	<0.000237 U	<0.000233 U	<0.000228 U	<0.000213 U	<0.000215 U	<0.000321 U	<0.000271 U	<0.000283 U	<0.000223 U	<0.000217 U
Perfluorotridecanoic Acid (PFTrDA)	72629-94-8	NS	NS	NS	mg/kg	<0.000225 U	<0.000213 UJ	<0.000319 U	<0.000269 U	<0.0003 U	<0.000384 U	<0.000272 U	<0.000237 U	<0.000233 U	<0.000228 U	<0.000213 U	<0.000215 U	<0.000321 U	<0.000271 U	<0.000283 U	<0.000223 U	<0.000217 U
Perfluoroundecanoic Acid (PFUnA)	2058-94-8	NS	NS	NS	mg/kg	<0.000225 U	<0.000213 UJ	<0.000319 U	<0.000269 U	<0.0003 U	<0.000384 U	<0.000272 U	<0.000237 U	<0.000233 U	<0.000228 U	<0.000213 U	<0.000215 U	<0.000321 U	<0.000271 U	<0.000283 U	<0.000223 U	<0.000217 U
General Chemistry																						
Solids, Percent	SOLID	NS	NS	NS	Percent	88.1	93.5	62.2	74.1	66.6	52.1	73.1	84.2	85.6	87.3	93.5	92.5	61.9	73.9	70.7	89	91.8

Table 2
Site Management Plan
Soil Sample Analytical Results

12074 Flatlands Avenue p/o Lot 1 Site
Brooklyn, New York
BCP Site No. C224353
Langan Project No.: 100688803

Analyte	CAS Number	NYSDEC Part 375 Unrestricted Use SCOs	NYSDEC Part 375 Protection of Groundwater SCOs	NYSDEC Part 375 Restricted Use Restricted-Residential SCOs	Location	PE18	PE19	PE20	PE20	PE21	PE22	PE23	PE24	PE25	PE26	PE27	PE28	PE29	PE30	PE31	PE32	PE33
					Sample Name	PE18_15	PE19_15.5	PE20_15.5	DUP_07282025	PE21_16	PE22_16.5	PE23_16.5	PE24_16.5	PE25_15	PE26_15	PE27_17	PE28_17	PE29_18	PE30_18	PE31_18.5	PE32_20	PE33_20
					Sample Date	06/19/2025	08/08/2025	07/28/2025	07/28/2025	07/22/2025	07/22/2025	07/22/2025	07/14/2025	06/19/2025	06/19/2025	08/11/2025	07/28/2025	07/24/2025	07/24/2025	07/24/2025	07/22/2025	06/19/2025
					Sample Elevation	15	15.5	15.5	15.5	16	16.5	16.5	16.5	15	15	17	17	18	18	18.5	20	20
					Unit	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result
Volatile Organic Compounds																						
1,1,1,2-Tetrachloroethane	630-20-6	NS	NS	NS	mg/kg	<0.0058 U	<0.0072 U	<0.0076 U	<0.0081 U	<0.0073 UJ	<0.009 UJ	<0.0079 UJ	<0.0079 U	<0.0049 U	<0.0053 U	<0.006 U	<0.0078 U	<0.01 U	<0.0084 U	<0.0085 U	<0.007 UJ	<0.0051 U
1,1,1-Trichloroethane	71-55-6	0.68	0.68	100	mg/kg	<0.0058 U	<0.0072 U	<0.0076 U	<0.0081 U	<0.0073 U	<0.009 U	<0.0079 U	<0.0079 U	<0.0049 U	<0.0053 U	<0.006 U	<0.0078 U	<0.01 U	<0.0084 U	<0.0085 U	<0.007 U	<0.0051 U
1,1,2,2-Tetrachloroethane	79-34-5	NS	NS	NS	mg/kg	<0.0058 U	<0.0072 U	<0.0076 U	<0.0081 U	<0.0073 U	<0.009 U	<0.0079 U	<0.0079 U	<0.0049 U	<0.0053 U	<0.006 U	<0.0078 U	<0.01 U	<0.0084 U	<0.0085 U	<0.007 U	<0.0051 U
1,1,2-Trichloro-1,2,2-Trifluoroethane	76-13-1	NS	NS	NS	mg/kg	<0.0058 U	<0.0072 U	<0.0076 U	<0.0081 U	<0.0073 U	<0.009 U	<0.0079 U	<0.0079 U	<0.0049 U	<0.0053 U	<0.006 U	<0.0078 U	<0.01 U	<0.0084 U	<0.0085 U	<0.007 U	<0.0051 U
1,1,2-Trichloroethane	79-00-5	NS	NS	NS	mg/kg	<0.0058 U	<0.0072 U	<0.0076 U	<0.0081 U	<0.0073 U	<0.009 U	<0.0079 U	<0.0079 U	<0.0049 U	<0.0053 U	<0.006 U	<0.0078 U	<0.01 U	<0.0084 U	<0.0085 U	<0.007 U	<0.0051 U
1,1-Dichloroethane	75-34-3	0.27	0.27	47	mg/kg	<0.0058 U	<0.0072 U	<0.0076 U	<0.0081 U	<0.0073 U	<0.009 U	<0.0079 U	<0.0079 U	<0.0049 U	<0.0053 U	<0.006 U	<0.0078 U	<0.01 U	<0.0084 U	<0.0085 U	<0.007 U	<0.0051 U
1,1-Dichloroethene	75-35-4	0.24	0.33	0.98	mg/kg	<0.0058 U	<0.0072 U	<0.0076 U	<0.0081 U	<0.0073 U	<0.009 U	<0.0079 U	<0.0079 U	<0.0049 U	<0.0053 U	<0.006 U	<0.0078 U	<0.01 U	<0.0084 U	<0.0085 U	<0.007 U	<0.0051 U
1,1-Dichloropropene	563-58-6	NS	NS	NS	mg/kg	<0.0058 U	<0.0072 U	<0.0076 U	<0.0081 U	<0.0073 U	<0.009 U	<0.0079 U	<0.0079 U	<0.0049 U	<0.0053 U	<0.006 U	<0.0078 U	<0.01 U	<0.0084 U	<0.0085 U	<0.007 U	<0.0051 U
1,2,3-Trichlorobenzene	87-61-6	NS	NS	NS	mg/kg	<0.0058 U	<0.0072 U	<0.0076 U	<0.0081 U	<0.0073 U	<0.009 U	<0.0079 U	<0.0079 U	<0.0049 U	<0.0053 U	<0.006 U	<0.0078 U	<0.01 U	<0.0084 U	<0.0085 U	<0.007 U	<0.0051 U
1,2,3-Trichloropropane	96-18-4	NS	NS	NS	mg/kg	<0.0058 U	<0.0072 U	<0.0076 U	<0.0081 U	<0.0073 U	<0.009 U	<0.0079 U	<0.0079 U	<0.0049 U	<0.0053 U	<0.006 U	<0.0078 U	<0.01 U	<0.0084 U	<0.0085 U	<0.007 U	<0.0051 U
1,2,4-Trichlorobenzene	120-82-1	NS	NS	NS	mg/kg	<0.0058 U	<0.0072 U	<0.0076 U	<0.0081 U	<0.0073 U	<0.009 U	<0.0079 U	<0.0079 U	<0.0049 U	<0.0053 U	<0.006 U	<0.0078 U	<0.01 U	<0.0084 U	<0.0085 U	<0.007 U	<0.0051 U
1,2,4-Trimethylbenzene	95-63-6	5.9	5.9	100	mg/kg	<0.0058 U	<0.0072 U	<0.0076 U	<0.0081 U	<0.0073 U	<0.009 U	<0.0079 U	<0.0079 U	<0.0049 U	<0.0053 U	<0.006 U	<0.0078 U	<0.01 U	<0.0084 U	<0.0085 U	<0.007 U	<0.0051 U
1,2-Dibromo-3-Chloropropane	96-12-8	NS	NS	NS	mg/kg	<0.0058 U	<0.0072 U	<0.0076 U	<0.0081 U	<0.0073 U	<0.009 U	<0.0079 U	<0.0079 U	<0.0049 U	<0.0053 U	<0.006 U	<0.0078 U	<0.01 U	<0.0084 U	<0.0085 U	<0.007 U	<0.0051 U
1,2-Dibromoethane (Ethylene Dibromide)	106-93-4	NS	NS	NS	mg/kg	<0.0058 U	<0.0072 U	<0.0076 U	<0.0081 U	<0.0073 U	<0.009 U	<0.0079 U	<0.0079 U	<0.0049 U	<0.0053 U	<0.006 U	<0.0078 U	<0.01 U	<0.0084 U	<0.0085 U	<0.007 U	<0.0051 U
1,2-Dichlorobenzene	95-50-1	1.1	1.1	100	mg/kg	<0.0058 U	<0.0072 U	<0.0076 U	<0.0081 U	<0.0073 U	<0.009 U	<0.0079 U	<0.0079 U	<0.0049 U	<0.0053 U	<0.006 U	<0.0078 U	<0.01 U	<0.0084 U	<0.0085 U	<0.007 U	<0.0051 U
1,2-Dichloroethane	107-06-2	0.02	0.02	5.8	mg/kg	<0.0058 U	<0.0072 U	<0.0076 U	<0.0081 U	<0.0073 U	<0.009 U	<0.0079 U	<0.0079 U	<0.0049 U	<0.0053 U	<0.006 U	<0.0078 U	<0.01 U	<0.0084 U	<0.0085 U	<0.007 U	<0.0051 U
1,2-Dichloropropane	78-87-5	NS	NS	NS	mg/kg	<0.0058 U	<0.0072 U	<0.0076 U	<0.0081 U	<0.0073 U	<0.009 U	<0.0079 U	<0.0079 U	<0.0049 U	<0.0053 U	<0.006 U	<0.0078 U	<0.01 U	<0.0084 U	<0.0085 U	<0.007 U	<0.0051 U
1,3,5-Trimethylbenzene (Mesitylene)	108-67-8	3.1	3.1	100	mg/kg	<0.0058 U	<0.0072 U	<0.0076 U	<0.0081 U	<0.0073 U	<0.009 U	<0.0079 U	<0.0079 U	<0.0049 U	<0.0053 U	<0.006 U	<0.0078 U	<0.01 U	<0.0084 U	<0.0085 U	<0.007 U	<0.0051 U
1,3-Dichlorobenzene	541-73-1	2.6	2.6	38	mg/kg	<0.0058 U	<0.0072 U	<0.0076 U	<0.0081 U	<0.0073 U	<0.009 U	<0.0079 U	<0.0079 U	<0.0049 U	<0.0053 U	<0.006 U	<0.0078 U	<0.01 U	<0.0084 U	<0.0085 U	<0.007 U	<0.0051 U
1,3-Dichloropropane	142-28-9	NS	NS	NS	mg/kg	<0.0058 U	<0.0072 U	<0.0076 UJ	<0.0081 UJ	<0.0073 U	<0.009 U	<0.0079 U	<0.0079 U	<0.0049 U	<0.0053 U	<0.006 U	<0.0078 UJ	<0.01 U	<0.0084 U	<0.0085 U	<0.007 U	<0.0051 U
1,4-Dichlorobenzene	106-46-7	1.8	1.8	24	mg/kg	<0.0058 U	<0.0072 U	<0.0076 U	<0.0081 U	<0.0073 U	<0.009 U	<0.0079 U	<0.0079 U	<0.0049 U	<0.0053 U	<0.006 U	<0.0078 U	<0.01 U	<0.0084 U	<0.0085 U	<0.007 U	<0.0051 U
1,4-Dioxane (P-Dioxane)	123-91-1	0.1	0.1	5.7	mg/kg	<0.12 U	NA	NA	NA	NA	NA	NA	<0.16 U	<0.098 U	<0.11 U	NA	NA	NA	NA	NA	NA	<0.1 U
2,2-Dichloropropane	594-20-7	NS	NS	NS	mg/kg	<0.0058 UJ	<0.0072 U	<0.0076 U	<0.0081 U	<0.0073 U	<0.009 U	<0.0079 U	<0.0079 U	<0.0049 UJ	<0.0053 U	<0.006 U	<0.0078 U	<0.01 U	<0.0084 U	<0.0085 U	<0.007 U	<0.0051 U
2-Chlorotoluene	95-49-8	NS	NS	NS	mg/kg	<0.0058 U	<0.0072 U	<0.0076 U	<0.0081 U	<0.0073 U	<0.009 U	<0.0079 U	<0.0079 U	<0.0049 U	<0.0053 U	<0.006 U	<0.0078 U	<0.01 U	<0.0084 U	<0.0085 U	<0.007 U	<0.0051 U
2-Hexanone (MBK)	591-78-6	NS	NS	NS	mg/kg	<0.0058 U	<0.0072 U	<0.0076 U	<0.0081 U	<0.0073 U	<0.009 U	<0.0079 U	<0.0079 U	<0.0049 U	<0.0053 U	<0.006 U	<0.0078 U	<0.01 U	<0.0084 U	<0.0085 U	<0.007 U	<0.0051 U
4-Chlorotoluene	106-43-4	NS	NS	NS	mg/kg	<0.0058 U	<0.0072 U	<0.0076 U	<0.0081 U	<0.0073 U	<0.009 U	<0.0079 U	<0.0079 U	<0.0049 U	<0.0053 U	<0.006 U	<0.0078 U	<0.01 U	<0.0084 U	<0.0085 U	<0.007 U	<0.0051 U
Acetone	67-64-1	**0.03**	0.03	100	mg/kg	**0.031**	**0.061**	**0.066**	**0.047**	**0.096**	**0.13**	**0.17 J**	**0.11**	<0.0098 U	<0.011 U	<0.012 U	**0.062**	**0.092 J**	**0.06**	**0.052**	**0.045**	0.03
Acrolein	107-02-8	NS	NS	NS	mg/kg	<0.012 U	<0.014 U	<0.015 U	<0.016 U	<0.015 U	<0.018 U	<0.016 U	<0.016 U	<0.0098 U	<0.011 U	<0.012 U	<0.016 U	<0.02 U	<0.017 U	<0.017 U	<0.014 U	<0.01 U
Acrylonitrile	107-13-1	NS	NS	NS	mg/kg	<0.0058 U	<0.0072 U	<0.0076 U	<0.0081 U	<0.0073 U	<0.009 U	<0.0079 U	<0.0079 U	<0.0049 U	<0.0053 U	<0.006 U	<0.0078 U	<0.01 U	<0.0084 U	<0.0085 U	<0.007 U	<0.0051 U
Benzene	71-43-2	0.06	0.06	3.7	mg/kg	<0.0058 U	<0.0072 U	<0.0076 U	<0.0081 U	<0.0073 U	<0.009 U	<0.0079 U	<0.0079 U	<0.0049 U	<0.0053 U	<0.006 U	<0.0078 U	<0.01 U	<0.0084 U	<0.0085 U	<0.007 U	<0.0051 U
Bromobenzene	108-86-1	NS	NS	NS	mg/kg	<0.0058 U	<0.0072 U	<0.0076 U	<0.0081 U	<0.0073 U	<0.009 U	<0.0079 U	<0.0079 U	<0.0049 U	<0.0053 U	<0.006 U	<0.0078 U	<0.01 U	<0.0084 U	<0.0085 U	<0.007 U	<0.0051 U
Bromochloromethane	74-97-5	NS	NS	NS	mg/kg	<0.0058 U	<0.0072 U	<0.0076 U	<0.0081 U	<0.0073 U	<0.009 U	<0.0079 U	<0.0079 U	<0.0049 U	<0.0053 U	<0.006 U	<0.0078 U	<0.01 U	<0.0084 U	<0.0085 U	<0.007 U	<0.0051 U
Bromodichloromethane	75-27-4	NS	NS	NS	mg/kg	<0.0058 U	<0.0072 U	<0.0076 U	<0.0081 U	<0.0073 U	<0.009 U	<0.0079 U	<0.0079 U	<0.0049 U	<0.0053 U	<0.006 U	<0.0078 U	<0.01 U	<0.0084 U	<0.0085 U	<0.007 U	<0.0051 U
Bromoform	75-25-2	NS	NS	NS	mg/kg	<0.0058 U	<0.0072 U	<0.0076 U	<0.0081 U	<0.0073 UJ	<0.009 UJ	<0.0079 UJ	<0.0079 U	<0.0049 U	<0.0053 U	<0.006 U	<0.0078 U	<0.01 U	<0.0084 U	<0.0085 U	<0.007 UJ	<0.0051 U
Bromomethane	74-83-9	NS	NS	NS	mg/kg	<0.0058 U	<0.0072 U	<0.0076 U	<0.0081 U	<0.0073 U	<0.009 U	<0.0079 U	<0.0079 U	<0.0049 U	<0.0053 U	<0.006 U	<0.0078 U	<0.01 U	<0.0084 U	<0.0085 U	<0.007 U	<0.0051 U
Carbon Disulfide	75-15-0	NS	NS	NS	mg/kg	<0.0058 U	<0.0072 U	<0.0076 U	0.0045 J	<0.0073 U	<0.009 U	0.012 J	<0.0079 U	<0.0049 U	<0.0053 U	<0.006 U	<0.0078 U	0.012 J	<0.0084 U	<0.0085 U	0.0088	<0.0051 U
Carbon Tetrachloride	56-23-5	0.76	0.76	7.1	mg/kg	<0.0058 U	<0.0072 U	<0.0076 U	<0.0081 U	<0.0073 U	<0.009 U	<0.0079 U	<0.0079 U	<0.0049 U	<0.0053 U	<0.006 U	<0.0078 U	<0.01 U	<0.0084 U	<0.0085 U	<0.007 U	<0.0051 U
Chlorobenzene	108-90-7	4.5	4.5	100	mg/kg	<0.0058 U	<0.0072 U	<0.0076 U	<0.0081 U	<0.0073 U	<0.009 U	<0.0079 U	<0.0079 U	<0.0049 U	<0.0053 U	<0.006 U	<0.0078 U	<0.01 U	<0.0084 U	<0.0085 U	<0.007 U	<0.0051 U
Chloroethane	75-00-3	NS	NS	NS	mg/kg	<0.0058 U	<0.0072 U	<0.0076 U	<0.0081 U	<0.0073 U	<0.009 U	<0.0079 U	<0.0079 U	<0.0049 U	<0.0053 U	<0.006 U	<0.0078 U	<0.01 U	<0.0084 U	<0.0085 U	<0.007 U	<0.0051 U
Chloroform	67-66-3	0.37	0.37	24	mg/kg	<0.0058 U	<0.0072 U	<0.0076 U	<0.0081 U	<0.0073 UJ	<0.009 UJ	<0.0079 UJ	<0.0079 U	<0.0049 U	<0.0053 U	<0.006 U	<0.0078 U	<0.01 U	<0.0084 U	<0.0085 U	<0.007 UJ	<0.0051 U
Chloromethane	74-87-3	NS	NS	NS	mg/kg	<0.0058 U	<0.0072 U	<0.0076 U	<0.0081 U	<0.0073 U	<0.009 U	<0.0079 U	<0.0079 U	<0.0049 U	<0.0053 U	<0.006 U	<0.0078 U	<0.01 U	<0.0084 U	<0.0085 U	<0.007 U	<0.0051 U
Cis-1,2-Dichloroethene	156-59-2	0.19	0.19	41	mg/kg	<0.0058 UJ	<0.0072 U	<0.0076 U	<0.0081 U	<0.0073 U	<0.009 U	<0.0079 U	<0.0079 U	<0.0049 UJ	<0.0053 U	<0.006 U	<0.0078 U	<0.01 U	<0.0084 U	<0.0085 U	<0.007 U	<0.0051 U
Cis-1,3-Dichloropropene	10061-01-5	NS	NS	NS	mg/kg	<0.0058 U	<0.0072 U	<0.0076 U	<0.0081 U	<0.0073 U	<0.009 U	<0.0079 U	<0.0079 U	<0.0049 U	<0.0053 U	<0.006 U	<0.0078 U	<0.01 U	<0.0084 U	<0.0085 U	<0.007 U	<0.0051 U
Cyclohexane	110-82-7	NS	NS	NS	mg/kg	<0.0058 U	<0.0072 U	<0.0076 U	<0.0081 U	<0.0073 U	<0.009 U	<0.0079 U	<0.0079 U	<0.0049 U	<0.0053 U	<0.006 U	<0.0078 U	<0.01 U	<0.0084 U	<0.0085 U	<0.007 U	<0.0051 U
Cymene	99-87-6	NS	NS	NS	mg/kg	<0.0058 U	<0.0072 U	<0.0076 U	<0.0081 U	<0.0073 U	<0.009 U	<0.0079 U	<0.0079 U	<0.0049 U	<0.0053 U	<0.006 U	<0.0078 U	<0.01 U	<0.0084 U	<0.0085 U	<0.007 U	<0.0051 U
Dibromochloromethane	124-48-1	NS	NS	NS	mg/kg	<0.0058 U	<0.0072 U	<0.0076 U	<0.0081 U	<0.0073 U	<0.009 U	<0.0079 U	<0.0079 U	<0.0049 U	<0.0053 U	<0.006 U	<0.0078 U	<0.01 U	<0.0084 U	<0.0085 U	<0.007 U	<0.0051 U
Dibromomethane	74-95-3	NS	NS	NS	mg/kg	<0.0058 U	<0.0072 U	<0.0076 UJ	<0.0081 UJ	<0.0073 U	<0.009 U	<0.0079 U	<0.0079 U	<0.0049 U	<0.0053 U	<0.006 U	<0.0078 UJ	<0.01 U	<0.0084 U	<0.0085 U	<0.007 U	<0.0051 U
Dichlorodifluoromethane	75-71-8	NS	NS	NS	mg/kg	<0.0058 U	<0.0072 U	<0.0076 U	<0.0081 U	<0.0073 U	<0.009 U	<0.0079 U	<0.0079 U	<0.0049 U	<0.0053 UJ	<0.006 U	<0.0078 U	<0.01 U	<0.0084 U	<0.0085 U	<0.007 U	<0.0051 UJ
Ethylbenzene	100-41-4	1	1	76	mg/kg	<0.0058 U	<0.0072 U	<0.0076 U	<0.0081 U	<0.0073 U	<0.009 U	<0.0079 U	<0.0079 U	<0.0049 U	<0.0053 U	<0.006 U	<0.0078 U	<0.01 U	<0.0084 U	<0.0085 U	<0.007 U	<0.0051 U
Hexachlorobutadiene	87-68-3	NS	NS	NS	mg/kg	<0.0058 U	<0.0072 U	<0.0076 U	<0.0081 U	<0.0073 UJ	<0.009 UJ	<0.0079 UJ	<0.0079 U	<0.0049 U	<0.0053 U	<0.006 U	<0.0078 U	<0.01 U	<0.0084 U	<0.0085 U	<0.007 UJ	<0.0051 U
Isopropylbenzene (Cumene)	98-82-8	NS	NS	NS	mg/kg	<0.0058 U	<0.0072 U	<0.0076 U	<0.0081 U	<0.0073 U	<0.009 U	<0.0079 U	<0.0079 U	<0.0049 U	<0.0053 U	<0.006 U	<0.0078 U	<0.01 U	<0.0084 U	<0.0085 U	<0.007 U	<0.0051 U
M,P-Xylene	179601-23-1	NS	NS	NS	mg/kg	<0.012 U	<0.014 U	<0.015 U	<0.016 U	<0.015 U	<0.018 U	<0.016 U	<0.016 U	<0.0098 U	<0.011 U	<0.012 U	<0.016 U	<0.02 U	<0.017 U	<0.017 U	<0.014 U	<0.01 U
Methyl Acetate	79-20-9	NS	NS	NS	mg/kg	<0.0058 U	<0.0072 U	<0.0076 U	<0.0081 U	<0.0073 U	<0.009 U	<0.0079 U	<0.0079 UJ	<0.0049 U	<0.0053 U	<0.006 U	<0.0078 UJ	<0.01 U	<0.0084 U	<0.0085 U	<0.007 U	<0.0051 U
Methyl Ethyl Ketone (2-Butanone)	78-93-3	0.1	0.1	100	mg/kg	<0.0058 U	0.012	0.0054 J	0.0051 J	0.017	0.012	0.041 J	0.07	<0.0049 U	<0.0053 U	<0.006 U	0.018	0.0095 J	0.0044 J	0.0057 J	0.014	0.0032 J
Methyl Isobutyl Ketone (4-Methyl-2-Pentanone)	108-10-1	NS	NS	NS	mg/kg	<0.0058 U	<0.0072 U	<0.0076 U	<0.0081 U	<0.0073 U	<0.009 U	<0.0079 U	<0.0079 U	<0.0049 U	<0.0053 U	<0.006 U	<0.0078 U	<0.01 U	<0.0084 U	<0.0085 U	<0.007 U	<0.0051 U
Methylcyclohexane	108-87-2	NS	NS	NS	mg/kg	<0.0058 U	<0.0072 U	<0.0076 U	<0.0081 U	0.0045 J	<0.009 U	<0.0079 U	<0.0079 U	<0.0049 U	<0.0053 U	0.0099	0.013	0.0058 J	<0.0084 U	<0.0085 U	<0.007 U	<0.0051 U
Methylene Chloride	75-09-2	0.05	0.05	81	mg/kg	<0.012 U	<0.014 U	<0.015 U	<0.016 U	<0.015 U	<0.018 U	<0.016 U	<0.016 U	<0.0098 U	<0.011 U	<0.012 U	<0.016 U	<0.02 U	<0.017 U	<0.017 U	<0.014 U	<0.01 U
n-Butylbenzene	104-51-8	18	18	100	mg/kg	<0.0058 U	<0.0072 U	<0.0076 U	<0.0081 U	<0.0073 U	<0.009 U	<0.0079 U	<0.0079 U	<0.0049 U	<0.0053 U	<0.006 U	<0.0078 U	<0.01 U	<0.0084 U	<0.0085 U	<0.007 U	<0.0051 U
n-Propylbenzene	103-65-1	5	5	100	mg/kg	<0.0058 U	<0.0072 U	<0.0076 U	<0.0081 U	<0.0073 U	<0.009 U	<0.0079 U	<0.0079 U	<0.0049 U	<0.0053 U	<0.006 U	<0.0078 U	<0.01 U	<0.0084 U	<0.0085 U	<0.007 U	<0.0051 U
o-Xylene (1,2-Dimethylbenzene)	95-47-6	NS	NS	NS	mg/kg	<0.0058 U	<0.0072 U	<0.0076 U	<0.0081 U	<0.0073 U	<0.009 U	<0.0079 U	<0.0079 U	<0.0049 U	<0.0053 U	<0.006 U	<0.0078 U	<0.01 U	<0.0084 U	<0.0085 U	<0.007 U	<0.0051 U
Sec-Butylbenzene	135-98-8	25	25	100	mg/kg	<0.0058 U	<0.0072 U	<0.0076 U	<0.0081 U	<0.0073 U	<0.009 U	<0.0079 U	<0.0079 U	<0.0049 U	<0.0053 U	<0.006 U	<0.0078 U	<0.01 U	<0.0084 U	<0.0085 U	<0.007 U	<0.0051 U
Styrene	100-42-5	NS	NS	NS	mg/kg	<0.0058 U	<0.0072 U	<0.0076 U	<0.0081 U	<0.0073 U	<0.009 U	<0.0079 U	<0.0079 U	<0.0049 U	<0.0053 U	<0.006 U	<0.0078 U	<0.01 U	<0.0084 U	<0.0085 U	<0.007 U	<0.0051 U
T-Butylbenzene	98-06-6	11	11	100	mg/kg	<0.0058 UJ	<0.0072 U	<0.0076 UJ	<0.0081 UJ	<0.0073 U	<0.009 U	<0.0079 U	<0.0079 U	<0.0049 UJ	<0.0053 U	<0.006 U	<0.0078 U	<0.01 U	<0.0084 U	<0.0085 U	<0.007 U	<0.0051 U
Tert-Butyl Alcohol	75-65-0	NS	NS	NS	mg/kg	<0.029 U	<0.036 U	<0.038 U	<0.041 U	<0.036 U	<0.045 U	<0.04 U	<0.039 U	<0.025 U	<0.027 U	<0.03 U	<0.039 U	<0.05 U	<0.042 U	<0.042 U	<0.035 U	<0.025 U
Tert-Butyl Methyl Ether (MTBE)	1634-04-4	0.1	0.1	100	mg/kg	<0.0058 U	<0.0072 U	<0.0076 U	<0.0081 U	<0.0073 U	<0.009 U	<0.0079 U	<0.0079 U	<0.0049 U	<0.0053 U	<0.006 U	<0.0078 U	<0.01 U	<0.0084 U	<0.0085 U	<0.007 U	<0.0051 U
Tetrachloroethene (PCE)	127-18-4	1.3	1.3	18	mg/kg	<0.0058 U	<0.0072 U	<0.0076 U	<0.0081 U	<0.0073 UJ	<0.009 UJ	<0.0079 UJ	<0.0079 U	<0.0049 U	<0.0053 U	<0.006 U	<0.0078 U	<0.01 U	<0.0084 U	<0.0085 U	<0.007 UJ	<0.0051 U
Toluene	108-88-3	0.7	0.7	100	mg/kg	<0.0058 U	<0.0072 U	<0.0076 U	<0.0081 U	<0.0073 U	<0.009 U	<0.0079 U	<0.0079 U	<0.0049 U	<0.0053 U	<0.006 U	<0.0078 U	<0.01 U	<0.0084 U	<0.0085 U	<0.007 U	<0.0051 U
Total Xylenes	1330-20-7	0.26	1.2	100	mg/kg	<0.017 U	<0.022 U	<0.023 U	<0.024 U	<0.022 U	<0.027 U	<0.024 U	<0.024 U	<0.015 U	<0.016 U	<0.018 U	<0.023 U	<0.03 U	<0.025 U	<0.025 U	<0.021 U	<0.015 U
Trans-1,2-Dichloroethene	156-60-5	0.19	0.19	100	mg/kg	<0.0058 U	<0.0072 U	<0.0076 U	<0.0081 U	<0.0073 U	<0.009 U	<0.0079 U	<0.0079 U	<0.0049 U	<0.0053 U	<0.006 U	<0.0078 U	<0.01 U	<0.0084 U	<0.0085 U	<0.007 U	<0.0051 U
Trans-1,3-Dichloropropene	10061-02-6	NS	NS	NS	mg/kg	<0.0058 U	<0.0072 U	<0.0076 U	<0.0081 U	<0.0073 U	<0.009 U	<0.0079 U	<0.0079 U	<0.0049 U	<0.0053 U	<0.006 U	<0.0078 U	<0.01 U	<0.0084 U	<0.0085 U	<0.007 U	<0.0051 U
Trans-1,4-Dichloro-2-Butene	110-57-6	NS	NS	NS	mg/kg	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
Trichloroethene (TCE)	79-01-6	0.47	0.47	6.4	mg/kg	<0.0058 U	<0.0072 U	<0.0076 U	<0.0081 U	<0.0073 U	<0.009 U	<0.0079 U	<0.0079 U	<0.0049 U	<0.0053 U	<0.006 U	<0.0078 U	<0.01 U	<0.0084 U	<0.0085 U	<0.007 U	<0.0051 U
Trichlorofluoromethane	75-69-4	NS	NS	NS	mg/kg	<0.0058 U	<0.0072 U	<0.0076 U	<0.0081 U	<0.0073 U	<0.009 U	<0.0079 U	<0.0079 U	<0.0049 U	<0.0053 U	<0.006 U	<0.0078 U	<0.01 U	<0.0084 U	<0.0085 U	<0.007 U	<0.0051 U
Vinyl Chloride	75-01-4	0.03	0.03	0.48	mg/kg	<0.0058 U	<0.0072 U	<0.0076 U	<0.0081 U	<0.0073 U	<0.009 U	<0.0079 U	<0.0079 U	<0.0049 U	<0.0053 U	<0.006 U	<0.0078 U	<0.01 U	<0.0084 U	<0.0085 U	<0.007 U	<0.0051 U

Table 2
Site Management Plan
Soil Sample Analytical Results

12074 Flatlands Avenue p/o Lot 1 Site
Brooklyn, New York
BCP Site No. C224353
Langan Project No.: 100688803

Analyte	CAS Number	NYSDEC Part 375 Unrestricted Use SCOs	NYSDEC Part 375 Protection of Groundwater SCOs	NYSDEC Part 375 Restricted Use Restricted-Residential SCOs	Location	PE18	PE19	PE20	PE20	PE21	PE22	PE23	PE24	PE25	PE26	PE27	PE28	PE29	PE30	PE31	PE32	PE33
					Sample Name	PE18_15	PE19_15.5	PE20_15.5	DUP_07282025	PE21_16	PE22_16.5	PE23_16.5	PE24_16.5	PE25_15	PE26_15	PE27_17	PE28_17	PE29_18	PE30_18	PE31_18.5	PE32_20	PE33_20
					Sample Date	06/19/2025	08/08/2025	07/28/2025	07/28/2025	07/22/2025	07/22/2025	07/22/2025	07/14/2025	06/19/2025	06/19/2025	08/11/2025	07/28/2025	07/24/2025	07/24/2025	07/24/2025	07/22/2025	06/19/2025
					Sample Elevation	15	15.5	15.5	15.5	16	16.5	16.5	16.5	15	15	17	17	18	18	18.5	20	20
					Unit	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result
Semi-Volatile Organic Compounds																						
1,2,4,5-Tetrachlorobenzene	95-94-3	NS	NS	NS	mg/kg	<0.177 U	<0.204 U	<0.208 U	<0.217 U	<0.24 U	<0.243 U	<0.214 U	<0.256 U	<0.178 U	<0.184 U	<0.191 UJ	<0.556 U	<0.226 U	<0.227 U	<0.228 U	<0.222 U	<0.189 U
1,2,4-Trichlorobenzene	120-82-1	NS	NS	NS	mg/kg	<0.0885 U	<0.102 U	<0.104 U	<0.109 U	<0.12 U	<0.122 U	<0.107 U	<0.128 U	<0.089 U	<0.092 U	<0.0957 UJ	<0.278 U	<0.113 U	<0.114 U	<0.114 U	<0.111 U	<0.0945 U
1,2-Dichlorobenzene	95-50-1	1.1	1.1	100	mg/kg	<0.0885 U	<0.102 U	<0.104 U	<0.109 U	<0.12 U	<0.122 U	<0.107 U	<0.128 U	<0.089 U	<0.092 U	<0.0957 UJ	<0.278 U	<0.113 U	<0.114 U	<0.114 U	<0.111 U	<0.0945 U
1,2-Diphenylhydrazine	122-66-7	NS	NS	NS	mg/kg	<0.0885 U	<0.102 U	<0.104 U	<0.109 U	<0.12 U	<0.122 U	<0.107 U	<0.128 U	<0.089 U	<0.092 U	<0.0957 UJ	<0.278 U	<0.113 U	<0.114 U	<0.114 U	<0.111 U	<0.0945 U
1,3-Dichlorobenzene	541-73-1	2.6	2.6	38	mg/kg	<0.0885 U	<0.102 U	<0.104 U	<0.109 U	<0.12 U	<0.122 U	<0.107 U	<0.128 U	<0.089 U	<0.092 U	<0.0957 UJ	<0.278 U	<0.113 U	<0.114 U	<0.114 U	<0.111 U	<0.0945 U
1,4-Dichlorobenzene	106-46-7	1.8	1.8	24	mg/kg	<0.0885 U	<0.102 U	<0.104 U	<0.109 U	<0.12 U	<0.122 U	<0.107 U	<0.128 U	<0.089 U	<0.092 U	<0.0957 UJ	<0.278 U	<0.113 U	<0.114 U	<0.114 U	<0.111 U	<0.0945 U
1,4-Dioxane (P-Dioxane)	123-91-1	0.1	0.1	5.7	mg/kg	<0.0194 U	<0.0198 U	<0.0198 U	<0.0187 U	<0.0196 U	<0.0196 U	<0.0196 U	<0.0192 U	<0.0185 U	<0.0185 U	<0.0198 U	<0.0198 U	<0.0194 U	<0.0194 U	<0.0194 U	<0.0196 U	<0.0185 U
2,3,4,6-Tetrachlorophenol	58-90-2	NS	NS	NS	mg/kg	<0.177 U	<0.204 U	<0.208 U	<0.217 U	<0.24 U	<0.243 U	<0.214 U	<0.256 U	<0.178 U	<0.184 U	<0.191 UJ	<0.556 U	<0.226 U	<0.227 U	<0.228 U	<0.222 U	<0.189 U
2,4,5-Trichlorophenol	95-95-4	NS	NS	NS	mg/kg	<0.0885 U	<0.102 U	<0.104 U	<0.109 U	<0.12 U	<0.122 U	<0.107 U	<0.128 U	<0.089 U	<0.092 U	<0.0957 UJ	<0.278 U	<0.113 U	<0.114 U	<0.114 U	<0.111 U	<0.0945 U
2,4,6-Trichlorophenol	88-06-2	NS	NS	NS	mg/kg	<0.0885 U	<0.102 U	<0.104 U	<0.109 U	<0.12 U	<0.122 U	<0.107 U	<0.128 U	<0.089 U	<0.092 U	<0.0957 UJ	<0.278 U	<0.113 U	<0.114 U	<0.114 U	<0.111 U	<0.0945 U
2,4-Dichlorophenol	120-83-2	NS	NS	NS	mg/kg	<0.0885 U	<0.102 U	<0.104 U	<0.109 U	<0.12 U	<0.122 U	<0.107 U	<0.128 U	<0.089 U	<0.092 U	<0.0957 UJ	<0.278 U	<0.113 U	<0.114 U	<0.114 U	<0.111 U	<0.0945 U
2,4-Dimethylphenol	105-67-9	NS	NS	NS	mg/kg	<0.0885 U	<0.102 U	<0.104 U	<0.109 U	<0.12 U	<0.122 U	<0.107 U	<0.128 U	<0.089 U	<0.092 U	<0.0957 UJ	<0.278 U	<0.113 U	<0.114 U	<0.114 U	<0.111 U	<0.0945 U
2,4-Dinitrophenol	51-28-5	NS	NS	NS	mg/kg	<0.177 U	<0.204 U	<0.208 U	<0.217 U	<0.24 U	<0.243 U	<0.214 U	<0.256 U	<0.178 U	<0.184 U	<0.191 UJ	<0.556 U	<0.226 U	<0.227 U	<0.228 U	<0.222 U	<0.189 U
2,4-Dinitrotoluene	121-14-2	NS	NS	NS	mg/kg	<0.0885 U	<0.102 U	<0.104 U	<0.109 U	<0.12 U	<0.122 U	<0.107 U	<0.128 U	<0.089 U	<0.092 U	<0.0957 UJ	<0.278 U	<0.113 U	<0.114 U	<0.114 U	<0.111 U	<0.0945 U
2,6-Dinitrotoluene	606-20-2	NS	NS	NS	mg/kg	<0.0885 U	<0.102 U	<0.104 U	<0.109 U	<0.12 U	<0.122 U	<0.107 U	<0.128 U	<0.089 U	<0.092 U	<0.0957 UJ	<0.278 U	<0.113 U	<0.114 U	<0.114 U	<0.111 U	<0.0945 U
2-Chloronaphthalene	91-58-7	NS	NS	NS	mg/kg	<0.0885 U	<0.102 U	<0.104 U	<0.109 U	<0.12 U	<0.122 U	<0.107 U	<0.128 U	<0.089 U	<0.092 U	<0.0957 UJ	<0.278 U	<0.113 U	<0.114 U	<0.114 U	<0.111 U	<0.0945 U
2-Chlorophenol	95-57-8	NS	NS	NS	mg/kg	<0.0885 U	<0.102 U	<0.104 U	<0.109 U	<0.12 U	<0.122 U	<0.107 U	<0.128 U	<0.089 U	<0.092 U	<0.0957 UJ	<0.278 U	<0.113 U	<0.114 U	<0.114 U	<0.111 U	<0.0945 U
2-Methylnaphthalene	91-57-6	NS	NS	NS	mg/kg	<0.0885 U	<0.102 U	<0.104 U	<0.109 U	<0.12 U	<0.122 U	<0.107 U	<0.128 U	0.272 D	<0.092 U	0.0987 J	<0.278 U	<0.113 U	<0.114 U	<0.114 U	<0.111 U	<0.0945 U
2-Methylphenol (o-Cresol)	95-48-7	0.33	0.33	100	mg/kg	<0.0885 U	<0.102 U	<0.104 U	<0.109 U	<0.12 U	<0.122 U	<0.107 U	<0.128 U	<0.089 U	<0.092 U	<0.0957 UJ	<0.278 U	<0.113 U	<0.114 U	<0.114 U	<0.111 U	<0.0945 U
2-Nitroaniline	88-74-4	NS	NS	NS	mg/kg	<0.177 U	<0.204 U	<0.208 U	<0.217 U	<0.24 U	<0.243 U	<0.214 U	<0.256 U	<0.178 U	<0.184 U	<0.191 UJ	<0.556 U	<0.226 U	<0.227 U	<0.228 U	<0.222 U	<0.189 U
2-Nitrophenol	88-75-5	NS	NS	NS	mg/kg	<0.0885 U	<0.102 U	<0.104 U	<0.109 U	<0.12 U	<0.122 U	<0.107 U	<0.128 U	<0.089 U	<0.092 U	<0.0957 UJ	<0.278 U	<0.113 U	<0.114 U	<0.114 U	<0.111 U	<0.0945 U
3 & 4 Methylphenol (m&p Cresol)	65794-96-9	**0.33**	0.33	100	mg/kg	<0.0885 U	<0.102 U	<0.104 U	<0.109 U	<0.12 U	<0.122 U	<0.107 U	<0.128 U	<0.089 U	<0.092 U	<0.0957 UJ	<0.278 U	<0.113 U	<0.114 U	<0.114 U	<0.111 U	<0.0945 U
3,3'-Dichlorobenzidine	91-94-1	NS	NS	NS	mg/kg	<0.0885 U	<0.102 U	<0.104 U	<0.109 U	<0.12 U	<0.122 U	<0.107 U	<0.128 U	<0.089 U	<0.092 U	<0.0957 UJ	<0.278 U	<0.113 U	<0.114 U	<0.114 U	<0.111 U	<0.0945 U
3-Nitroaniline	99-09-2	NS	NS	NS	mg/kg	<0.177 U	<0.204 U	<0.208 U	<0.217 U	<0.24 U	<0.243 U	<0.214 U	<0.256 U	<0.178 U	<0.184 U	<0.191 UJ	<0.556 U	<0.226 U	<0.227 U	<0.228 U	<0.222 U	<0.189 U
4,6-Dinitro-2-Methylphenol	534-52-1	NS	NS	NS	mg/kg	<0.177 U	<0.204 U	<0.208 U	<0.217 U	<0.24 U	<0.243 U	<0.214 U	<0.256 U	<0.178 U	<0.184 U	<0.191 UJ	<0.556 U	<0.226 U	<0.227 U	<0.228 U	<0.222 U	<0.189 U
4-Bromophenyl Phenyl Ether	101-55-3	NS	NS	NS	mg/kg	<0.0885 U	<0.102 U	<0.104 U	<0.109 U	<0.12 U	<0.122 U	<0.107 U	<0.128 U	<0.089 U	<0.092 U	<0.0957 UJ	<0.278 U	<0.113 U	<0.114 U	<0.114 U	<0.111 U	<0.0945 U
4-Chloro-3-Methylphenol	59-50-7	NS	NS	NS	mg/kg	<0.0885 U	<0.102 U	<0.104 U	<0.109 U	<0.12 U	<0.122 U	<0.107 U	<0.128 U	<0.089 U	<0.092 U	<0.0957 UJ	<0.278 U	<0.113 U	<0.114 U	<0.114 U	<0.111 U	<0.0945 U
4-Chloroaniline	106-47-8	NS	NS	NS	mg/kg	<0.0885 U	<0.102 U	<0.104 U	<0.109 U	<0.12 U	<0.122 U	<0.107 U	<0.128 U	<0.089 U	<0.092 U	<0.0957 UJ	<0.278 U	<0.113 U	<0.114 U	<0.114 U	<0.111 U	<0.0945 U
4-Chlorophenyl Phenyl Ether	7005-72-3	NS	NS	NS	mg/kg	<0.0885 U	<0.102 U	<0.104 U	<0.109 U	<0.12 U	<0.122 U	<0.107 U	<0.128 U	<0.089 U	<0.092 U	<0.0957 UJ	<0.278 U	<0.113 U	<0.114 U	<0.114 U	<0.111 U	<0.0945 U
4-Nitroaniline	100-01-6	NS	NS	NS	mg/kg	<0.177 U	<0.204 U	<0.208 U	<0.217 U	<0.24 U	<0.243 U	<0.214 U	<0.256 U	<0.178 U	<0.184 U	<0.191 UJ	<0.556 U	<0.226 U	<0.227 U	<0.228 U	<0.222 U	<0.189 U
4-Nitrophenol	100-02-7	NS	NS	NS	mg/kg	<0.177 U	<0.204 U	<0.208 U	<0.217 U	<0.24 U	<0.243 U	<0.214 U	<0.256 U	<0.178 U	<0.184 U	<0.191 UJ	<0.556 U	<0.226 U	<0.227 U	<0.228 U	<0.222 U	<0.189 U
Acenaphthene	83-32-9	20	98	100	mg/kg	<0.0885 U	<0.102 U	<0.104 U	<0.109 U	<0.12 U	<0.122 U	<0.107 U	<0.128 U	0.148 D	<0.092 U	<0.0957 UJ	0.351 D	<0.113 U	<0.114 U	<0.114 U	<0.111 U	<0.0945 U
Acenaphthylene	208-96-8	100	365	100	mg/kg	<0.0885 U	<0.102 U	<0.104 U	<0.109 U	<0.12 U	<0.122 U	<0.107 U	<0.128 U	<0.089 U	<0.092 U	<0.0957 UJ	<0.278 U	<0.113 U	<0.114 U	<0.114 U	<0.111 U	<0.0945 U
Acetophenone	98-86-2	NS	NS	NS	mg/kg	<0.0885 U	<0.102 U	<0.104 U	<0.109 U	<0.12 U	<0.122 U	<0.107 U	<0.128 U	<0.089 U	<0.092 U	<0.0957 UJ	<0.278 U	<0.113 U	<0.114 U	<0.114 U	<0.111 U	<0.0945 U
Aniline (Phenylamine, Aminobenzene)	62-53-3	0.04	0.04	8.1	mg/kg	<0.355 U	<0.409 U	<0.416 U	<0.435 U	<0.481 U	<0.488 U	<0.429 U	<0.513 U	<0.357 U	<0.369 U	<0.383 UJ	<1.11 U	<0.453 U	<0.455 U	<0.457 U	<0.445 U	<0.379 U
Anthracene	120-12-7	100	1000	100	mg/kg	<0.0885 U	<0.102 U	<0.104 U	<0.109 U	<0.12 U	<0.122 U	<0.107 U	<0.128 U	0.464 D	<0.092 U	0.0841 J	0.171 JD	<0.113 U	<0.114 U	<0.114 U	<0.111 U	<0.0945 U
Atrazine	1912-24-9	NS	NS	NS	mg/kg	<0.0885 U	<0.102 U	<0.104 U	<0.109 U	<0.12 U	<0.122 U	<0.107 U	<0.128 U	<0.089 U	<0.092 U	<0.0957 UJ	<0.278 U	<0.113 U	<0.114 U	<0.114 U	<0.111 U	<0.0945 U
Benzaldehyde	100-52-7	NS	NS	NS	mg/kg	<0.0885 U	<0.102 U	<0.104 UJ	<0.109 UJ	<0.12 U	<0.122 U	<0.107 U	<0.128 U	<0.089 U	<0.092 U	<0.0957 UJ	<0.278 UJ	<0.113 U	<0.114 U	<0.114 U	<0.111 U	<0.0945 U
Benzidine	92-87-5	NS	NS	NS	mg/kg	<0.355 U	<0.409 U	<0.416 U	<0.435 U	<0.481 U	<0.488 U	<0.429 U	<0.513 U	<0.357 U	<0.369 U	<0.383 UJ	<1.11 U	<0.453 U	<0.455 U	<0.457 U	<0.445 U	<0.379 U
Benzo(a)anthracene	56-55-3	**1**	1	1.4	mg/kg	<0.0885 U	0.108 D	<0.104 U	<0.109 U	<0.12 U	<0.122 U	<0.107 U	0.0972 JD	0.551 D	<0.092 U	0.324 J	<0.278 U	<0.113 U	<0.114 U	<0.114 U	0.0905 JD	<0.0945 U
Benzo(a)pyrene	50-32-8	**1**	22	1	mg/kg	<0.0885 U	0.11 D	<0.104 U	<0.109 U	<0.12 U	<0.122 U	<0.107 U	0.0952 JD	0.327 D	<0.092 U	0.251 J	<0.278 U	<0.113 U	<0.114 U	<0.114 U	0.0941 JD	<0.0945 U
Benzo(b)fluoranthene	205-99-2	**1**	2.1	1.4	mg/kg	<0.0885 U	0.0817 JD	<0.104 U	<0.109 U	<0.12 U	<0.122 U	<0.107 U	0.123 JD	0.249 D	<0.092 U	0.548 J	<0.278 U	<0.113 U	<0.114 U	<0.114 U	0.12 D	<0.0945 U
Benzo(g,h,i)Perylene	191-24-2	**0.64**	1000	4.9	mg/kg	<0.0885 U	0.0727 JD	<0.104 U	<0.109 U	<0.12 U	<0.122 U	<0.107 U	<0.128 U	0.159 D	<0.092 U	0.187 J	<0.278 U	<0.113 U	<0.114 U	<0.114 U	0.0728 JD	<0.0945 U
Benzo(k)fluoranthene	207-08-9	**0.8**	2	4.9	mg/kg	<0.0885 U	0.0841 JD	<0.104 U	<0.109 U	<0.12 U	<0.122 U	<0.107 U	<0.128 U	0.163 D	<0.092 U	<0.0957 UJ	<0.278 U	<0.113 U	<0.114 U	<0.114 U	<0.111 U	<0.0945 U
Benzoic Acid	65-85-0	NS	NS	NS	mg/kg	<0.0885 U	<0.102 U	<0.104 U	<0.109 U	<0.12 U	<0.122 U	<0.107 U	<0.128 U	<0.089 U	<0.092 U	<0.0957 UJ	<0.278 U	<0.113 U	<0.114 U	<0.114 U	<0.111 U	<0.0945 U
Benzyl Alcohol	100-51-6	NS	NS	NS	mg/kg	<0.0885 U	<0.102 U	<0.104 U	<0.109 U	<0.12 U	<0.122 U	<0.107 U	<0.128 U	<0.089 U	<0.092 U	<0.0957 UJ	<0.278 U	<0.113 U	<0.114 U	<0.114 U	<0.111 U	<0.0945 U
Benzyl Butyl Phthalate	85-68-7	NS	NS	NS	mg/kg	<0.0885 U	<0.102 U	<0.104 U	<0.109 U	<0.12 U	<0.122 U	<0.107 U	<0.128 U	<0.089 U	<0.092 U	<0.0957 UJ	<0.278 U	<0.113 U	<0.114 U	<0.114 U	<0.111 U	<0.0945 U
Biphenyl (Diphenyl)	92-52-4	NS	NS	NS	mg/kg	<0.0885 U	<0.102 U	<0.104 U	<0.109 U	<0.12 U	<0.122 U	<0.107 U	<0.128 U	<0.089 U	<0.092 U	<0.0957 UJ	<0.278 U	<0.113 U	<0.114 U	<0.114 U	<0.111 U	<0.0945 U
Bis(2-chloroethoxy) methane	111-91-1	NS	NS	NS	mg/kg	<0.0885 U	<0.102 U	<0.104 U	<0.109 U	<0.12 U	<0.122 U	<0.107 U	<0.128 U	<0.089 U	<0.092 U	<0.0957 UJ	<0.278 U	<0.113 U	<0.114 U	<0.114 U	<0.111 U	<0.0945 U
Bis(2-chloroethyl) ether (2-chloroethyl ether)	111-44-4	NS	NS	NS	mg/kg	<0.0885 U	<0.102 U	<0.104 U	<0.109 U	<0.12 U	<0.122 U	<0.107 U	<0.128 U	<0.089 U	<0.092 U	<0.0957 UJ	<0.278 U	<0.113 U	<0.114 U	<0.114 U	<0.111 U	<0.0945 U
Bis(2-chloroisopropyl) ether	108-60-1	NS	NS	NS	mg/kg	<0.0885 U	<0.102 U	<0.104 U	<0.109 U	<0.12 U	<0.122 U	<0.107 U	<0.128 U	<0.089 U	<0.092 U	<0.0957 UJ	<0.278 U	<0.113 U	<0.114 U	<0.114 U	<0.111 U	<0.0945 U
Bis(2-ethylhexyl) phthalate	117-81-7	NS	NS	NS	mg/kg	<0.0885 U	0.102 D	<0.104 U	<0.109 U	0.177 D	0.0633 JD	0.153 D	<0.128 U	<0.089 U	<0.092 U	0.256 J	<0.278 U	0.252 D	<0.114 U	<0.114 U	2.13 D	<0.0945 U
Caprolactam	105-60-2	NS	NS	NS	mg/kg	<0.177 U	<0.204 U	<0.208 U	<0.217 U	<0.24 U	<0.243 U	<0.214 U	<0.256 U	<0.178 U	<0.184 U	<0.191 UJ	<0.556 U	<0.226 U	<0.227 U	<0.228 U	<0.222 U	<0.189 U
Carbazole	86-74-8	NS	NS	NS	mg/kg	<0.0885 U	<0.102 U	<0.104 U	<0.109 U	<0.12 U	<0.122 U	<0.107 U	<0.128 U	<0.089 U	<0.092 U	<0.0957 UJ	<0.278 U	<0.113 U	<0.114 U	<0.114 U	<0.111 U	<0.0945 U
Chrysene	218-01-9	**1**	1	4.9	mg/kg	<0.0885 U	0.0939 JD	<0.104 U	<0.109 U	<0.12 U	<0.122 U	<0.107 U	0.0891 JD	0.49 D	<0.092 U	0.375 J	<0.278 U	<0.113 U	<0.114 U	<0.114 U	0.115 D	<0.0945 U
Dibenz(a,h)anthracene	53-70-3	**0.33**	1000	0.33	mg/kg	<0.0885 U	<0.102 U	<0.104 U	<0.109 U	<0.12 U	<0.122 U	<0.107 U	<0.128 U	<0.089 U	<0.092 U	<0.0957 UJ	<0.278 U	<0.113 U	<0.114 U	<0.114 U	<0.111 U	<0.0945 U
Dibenzofuran	132-64-9	**2.1**	110	18	mg/kg	<0.0885 U	<0.102 U	<0.104 U	<0.109 U	<0.12 U	<0.122 U	<0.107 U	<0.128 U	0.094 D	<0.092 U	<0.0957 UJ	<0.278 U	<0.113 U	<0.114 U	<0.114 U	<0.111 U	<0.0945 U
Dibutyl phthalate	84-74-2	NS	NS	NS	mg/kg	<0.0885 U	<0.102 U	<0.104 U	<0.109 U	<0.12 U	<0.122 U	<0.107 U	<0.128 U	<0.089 U	<0.092 U	<0.0957 UJ	<0.278 U	<0.113 U	<0.114 U	<0.114 U	<0.111 U	<0.0945 U
Diethyl phthalate	84-66-2	NS	NS	NS	mg/kg	<0.0885 U	<0.102 U	<0.104 U	<0.109 U	<0.12 U	<0.122 U	<0.107 U	<0.128 U	<0.089 U	<0.092 U	<0.0957 UJ	<0.278 U	<0.113 U	<0.114 U	<0.114 U	<0.111 U	<0.0945 U
Dimethyl phthalate	131-11-3	NS	NS	NS	mg/kg	<0.0885 U	<0.102 U	<0.104 U	<0.109 U	<0.12 U	<0.122 U	<0.107 U	<0.128 U	<0.089 U	<0.092 U	<0.0957 UJ	<0.278 U	<0.113 U	<0.114 U	<0.114 U	<0.111 U	<0.0945 U
Dioctyl phthalate	117-84-0	NS	NS	NS	mg/kg	<0.0885 U	<0.102 U	<0.104 U	<0.109 U	<0.12 U	<0.122 U	<0.107 U	<0.128 U	<0.089 U	<0.092 U	<0.0957 UJ	<0.278 U	<0.113 U	<0.114 U	<0.114 U	<0.111 U	<0.0945 U
Fluoranthene	206-44-0	85	1000	100	mg/kg	<0.0885 U	0.167 D	<0.104 U	<0.109 U	0.0846 JD	<0.122 U	<0.107 U	0.186 D	0.876 D	<0.092 U	0.493 J	<0.278 U	0.066 JD	<0.114 U	<0.114 U	0.158 D	<0.0945 U
Fluorene	86-73-7	30	386	100	mg/kg	<0.0885 U	<0.102 U	<0.104 U	<0.109 U	<0.12 U	<0.122 U	<0.107 U	<0.128 U	0.399 D	<0.092 U	<0.0957 UJ	0.447 D	<0.113 U	<0.114 U	<0.114 U	<0.111 U	<0.0945 U
Hexachlorobenzene	118-74-1	0.33	3.2	0.33	mg/kg	<0.0885 U	<0.102 U	<0.104 U	<0.109 U	<0.12 U	<0.122 U	<0.107 U	<0.128 U	<0.089 U	<0.092 U	<0.0957 UJ	<0.278 U	<0.113 U	<0.114 U	<0.114 U	<0.111 U	<0.0945 U
Hexachlorobutadiene	87-68-3	NS	NS	NS	mg/kg	<0.0885 U	<0.102 U	<0.104 U	<0.109 U	<0.12 U	<0.122 U	<0.107 U	<0.128 U	<0.089 U	<0.092 U	<0.0957 UJ	<0.278 U	<0.113 U	<0.114 U	<0.114 U	<0.111 U	<0.0945 U
Hexachlorocyclopentadiene	77-47-4	NS	NS	NS	mg/kg	<0.0885 UJ	<0.102 UJ	<0.104 U	<0.109 U	<0.12 U	<0.122 U	<0.107 U	<0.128 UJ	<0.089 UJ	<0.092 UJ	<0.0957 UJ	<0.278 U	<0.113 U	<0.114 U	<0.114 U	<0.111 U	<0.0945 UJ
Hexachloroethane	67-72-1	NS	NS	NS	mg/kg	<0.0885 U	<0.102 U	<0.104 U	<0.109 U	<0.12 U	<0.122 U	<0.107 U	<0.128 U	<0.089 U	<0.092 U	<0.0957 UJ	<0.278 U	<0.113 U	<0.114 U	<0.114 U	<0.111 U	<0.0945 U
Indeno(1,2,3-cd)pyrene	193-39-5	**0.5**	6.6	1.4	mg/kg	<0.0885 U	0.0678 JD	<0.104 U	<0.109 U	<0.12 U	<0.122 U	<0.107 U	<0.128 U	<0.089 U	<0.092 U	0.185 J	<0.278 U	<0.113 U	<0.114 U	<0.114 U	0.0577 JD	<0.0945 U
Isophorone	78-59-1	NS	NS	NS	mg/kg	<0.0885 U	<0.102 U	<0.104 U	<0.109 U	<0.12 U	<0.122 U	<0.107 U	<0.128 U	<0.089 U	<0.092 U	<0.0957 UJ	<0.278 U	<0.113 U	<0.114 U	<0.114 U	<0.111 U	<0.0945 U
Naphthalene	91-20-3	12	12	100	mg/kg	<0.0885 U	<0.102 U	<0.104 U	<0.109 U	<0.12 U	<0.122 U	<0.107 U	<0.128 U	0.0797 JD	<0.092 U	0.0818 J	<0.278 U	<0.113 U	<0.114 U	<0.114 U	0.0595 JD	<0.0945 U
Nitrobenzene	98-95-3	0.08	0.08	1.8	mg/kg	<0.0885 U	<0.102 U	<0.104 U	<0.109 U	<0.12 U	<0.122 U	<0.107 U	<0.128 U	<0.089 U	<0.092 U	<0.0957 UJ	<0.278 U	<0.113 U	<0.114 U	<0.114 U	<0.111 U	<0.0945 U
n-Nitrosodimethylamine	62-75-9	NS	NS	NS	mg/kg	<0.0885 U	<0.102 U	<0.104 U	<0.109 U	<0.12 U	<0.122 U	<0.107 U	<0.128 U	<0.089 U	<0.092 U	<0.0957 UJ	<0.278 U	<0.113 U	<0.114 U	<0.114 U	<0.111 U	<0.0945 U
n-Nitrosodi-N-Propylamine	621-64-7	NS	NS	NS	mg/kg	<0.0885 U	<0.102 U	<0.104 U	<0.109 U	<0.12 U	<0.122 U	<0.107 U	<0.128 U	<0.089 U	<0.092 U	<0.0957 UJ	<0.278 U	<0.113 U	<0.114 U	<0.114 U	<0.111 U	<0.0945 U
n-Nitrosodiphenylamine	86-30-6	NS	NS	NS	mg/kg	<0.0885 U	<0.102 U	<0.104 U	<0.109 U	<0.12 U	<0.122 U	<0.107 U	<0.128 U	<0.089 U	<0.092 U	<0.0957 UJ	<0.278 U	<0.113 U	<0.114 U	<0.114 U	<0.111 U	<0.0945 U
Pentachlorophenol	87-86-5	0.8	0.8	1.3	mg/kg	<0.0885 U	<0.102 U	<0.104 U	<0.109 U	<0.12 U	<0.122 U	<0.107 U	<0.128 U	<0.089 U	<0.092 U	<0.0957 UJ	<0.278 U	<0.113 U	<0.114 U	<0.114 U	<0.111 U	<0.0945 U
Phenanthrene	85-01-8	**1.1**	1000	4.9	mg/kg	<0.0885 U	0.105 D	<0.104 U	<0.109 U	<0.12 U	<0.122 U	<0.107 U	0.113 JD	**2.02 D**	<0.092 U	0.278 J	**1.13 D**	0.0642 JD	<0.114 U	<0.114 U	0.0737 JD	<0.0945 U
Phenol	108-95-2	0.33	0.33	100	mg/kg	<0.0885 U	<0.102 U	<0.104 U	<0.109 U	<0.12 U	<0.122 U	<0.107 U	<0.128 U	<0.089 U	<0.092 U	<0.0957 UJ	<0.278 U	<0.113 U	<0.114 U	<0.114 U	<0.111 U	<0.0945 U
Pyrene	129-00-0	64	1000	100	mg/kg	<0.0885 U	0.185 D	<0.104 U	<0.109 U	0.0721 JD	<0.122 U	<0.107 U	0.127 JD	1.38 D	<0.092 U	0.702 J	0.498 D	0.0588 JD	<0.114 U	<0.114 U	0.144 D	<0.0945 U
Pyridine	110-86-1	NS	NS	NS	mg/kg	<0.355 U	<0.409 U	<0.416 U	<0.435 U	<0.481 U	<0.488 U	<0.429 U	<0.513 U	<0.357 U	<0.369 U	<0.383 UJ	<1.11 U	<0.453 U	<0.455 U	<0.457 U	<0.445 U	<0.379 U

Table 2
Site Management Plan
Soil Sample Analytical Results

12074 Flatlands Avenue p/o Lot 1 Site
Brooklyn, New York
BCP Site No. C224353
Langan Project No.: 100688803

Analyte	CAS Number	NYSDEC Part 375 Unrestricted Use SCOs	NYSDEC Part 375 Protection of Groundwater SCOs	NYSDEC Part 375 Restricted Use Restricted-Residential SCOs	Location	PE18	PE19	PE20	PE20	PE21	PE22	PE23	PE24	PE25	PE26	PE27	PE28	PE29	PE30	PE31	PE32	PE33
					Sample Name	PE18_15	PE19_15.5	PE20_15.5	DUP_07282025	PE21_16	PE22_16.5	PE23_16.5	PE24_16.5	PE25_15	PE26_15	PE27_17	PE28_17	PE29_18	PE30_18	PE31_18.5	PE32_20	PE33_20
					Sample Date	06/19/2025	08/08/2025	07/28/2025	07/28/2025	07/22/2025	07/22/2025	07/22/2025	07/14/2025	06/19/2025	06/19/2025	08/11/2025	07/28/2025	07/24/2025	07/24/2025	07/24/2025	07/22/2025	06/19/2025
					Sample Elevation	15	15.5	15.5	15.5	16	16.5	16.5	16.5	15	15	17	17	18	18	18.5	20	20
					Unit	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result
Pesticides																						
4,4'-DDD	72-54-8	**0.0033**	14	5	mg/kg	<0.00179 U	<0.00203 UP	<0.00207 UP	<0.00213 UP	<0.00235 UP	<0.00239 UP	<0.00209 UP	<0.00251 UP	<0.00178 U	<0.00181 U	**0.0202 DP**	**0.00335 J**	<0.00221 UP	<0.00223 UP	<0.00223 UP	<0.00215 UP	<0.00188 U
4,4'-DDE	72-55-9	**0.0033**	9.3	3.4	mg/kg	<0.00179 U	<0.00203 UP	<0.00207 UP	<0.00213 UP	<0.00235 UP	<0.00239 UP	<0.00209 UP	<0.00251 UP	<0.00178 U	<0.00181 U	<0.00191 U	**0.00658 J**	<0.00221 UP	<0.00223 UP	<0.00223 UP	<0.00215 UP	<0.00188 U
4,4'-DDT	50-29-3	**0.0033**	135	3.8	mg/kg	<0.00179 U	<0.00203 UP	<0.00207 UP	<0.00213 UP	<0.00235 UP	<0.00239 UP	<0.00209 UP	<0.00251 UP	<0.00178 U	<0.00181 U	<0.00191 UP	<0.00217 UJ	<0.00221 UP	<0.00223 UP	<0.00223 UP	<0.00215 UP	<0.00188 U
Aldrin	309-00-2	0.0048	0.19	0.044	mg/kg	<0.00179 U	<0.00203 UP	<0.00207 UP	<0.00213 UP	<0.00235 UP	<0.00239 UP	<0.00209 UP	<0.00251 UP	<0.00178 U	<0.00181 U	<0.00191 UP	<0.00217 UJ	<0.00221 UP	<0.00223 UP	<0.00223 UP	<0.00215 UP	<0.00188 U
Alpha BHC (Alpha Hexachlorocyclohexane)	319-84-6	0.02	0.02	0.18	mg/kg	<0.00179 U	<0.00203 UP	<0.00207 UP	<0.00213 UP	<0.00235 UP	<0.00239 UP	<0.00209 UP	<0.00251 UP	<0.00178 U	<0.00181 U	<0.00191 UP	<0.00217 UJ	<0.00221 UP	<0.00223 UP	<0.00223 UP	<0.00215 UP	<0.00188 U
Alpha Chlordane	5103-71-9	**0.014**	4.5	0.65	mg/kg	<0.00179 U	<0.00203 UP	<0.00207 UP	<0.00213 UP	<0.00235 UP	<0.00239 UP	<0.00209 UP	<0.00251 UP	<0.00178 U	<0.00181 U	<0.00191 UP	<0.00217 UJ	<0.00221 UP	<0.00223 UP	<0.00223 UP	<0.00215 UP	<0.00188 U
Alpha Endosulfan	959-98-8	4.3	65	35	mg/kg	<0.00179 U	<0.00203 UP	<0.00207 UP	<0.00213 UP	<0.00235 UP	<0.00239 UP	<0.00209 UP	<0.00251 UP	<0.00178 U	<0.00181 U	<0.00191 UP	<0.00217 UJ	<0.00221 UP	<0.00223 UP	<0.00223 UP	<0.00215 UP	<0.00188 U
Beta Bhc (Beta Hexachlorocyclohexane)	319-85-7	0.021	0.09	0.18	mg/kg	<0.00179 U	<0.00203 UP	<0.00207 UP	<0.00213 UP	<0.00235 UP	<0.00239 UP	<0.00209 UP	<0.00251 UP	<0.00178 U	<0.00181 U	<0.00191 UP	<0.00217 UJ	<0.00221 UP	<0.00223 UP	<0.00223 UP	<0.00215 UP	<0.00188 U
Beta Endosulfan	33213-65-9	4.3	44	35	mg/kg	<0.00179 U	<0.00203 UP	<0.00207 UP	<0.00213 UP	<0.00235 UP	<0.00239 UP	<0.00209 UP	<0.00251 UP	<0.00178 U	<0.00181 U	<0.00191 UP	<0.00217 UJ	<0.00221 UP	<0.00223 UP	<0.00223 UP	<0.00215 UP	<0.00188 U
Delta Bhc (Delta Hexachlorocyclohexane)	319-86-8	0.04	0.1	100	mg/kg	<0.00179 U	<0.00203 UP	<0.00207 UP	<0.00213 UP	<0.00235 UP	<0.00239 UP	<0.00209 UP	<0.00251 UP	<0.00178 U	<0.00181 U	<0.00191 UP	<0.00217 UJ	<0.00221 UP	<0.00223 UP	<0.00223 UP	<0.00215 UP	<0.00188 U
Dieldrin	60-57-1	**0.005**	0.1	0.075	mg/kg	<0.00179 U	<0.00203 UP	<0.00207 UP	<0.00213 UP	<0.00235 UP	<0.00239 UP	<0.00209 UP	<0.00251 UP	<0.00178 U	<0.00181 U	<0.00191 UP	<0.00217 UJ	<0.00221 UP	<0.00223 UP	<0.00223 UP	<0.00215 UP	<0.00188 U
Endosulfan Sulfate	1031-07-8	4.3	47	35	mg/kg	<0.00179 U	<0.00203 UP	<0.00207 UP	<0.00213 UP	<0.00235 UP	<0.00239 UP	<0.00209 UP	<0.00251 UP	<0.00178 U	<0.00181 U	<0.00191 UP	<0.00217 UJ	<0.00221 UP	<0.00223 UP	<0.00223 UP	<0.00215 UP	<0.00188 U
Endrin	72-20-8	0.014	0.06	5.3	mg/kg	<0.00179 U	<0.00203 UP	<0.00207 UP	<0.00213 UP	<0.00235 UP	<0.00239 UP	<0.00209 UP	<0.00251 UP	<0.00178 U	<0.00181 U	<0.00191 UP	<0.00217 UJ	<0.00221 UP	<0.00223 UP	<0.00223 UP	<0.00215 UP	<0.00188 U
Endrin Aldehyde	7421-93-4	NS	NS	NS	mg/kg	<0.00179 U	<0.00203 UP	<0.00207 UP	<0.00213 UP	<0.00235 UP	<0.00239 UP	<0.00209 UP	<0.00251 UP	<0.00178 U	<0.00181 U	<0.00191 UP	<0.00217 UJ	<0.00221 UP	<0.00223 UP	<0.00223 UP	<0.00215 UP	<0.00188 U
Endrin Ketone	53494-70-5	NS	NS	NS	mg/kg	<0.00179 U	<0.00203 UP	<0.00207 UP	<0.00213 UP	<0.00235 UP	<0.00239 UP	<0.00209 UP	<0.00251 UP	<0.00178 U	<0.00181 U	<0.00191 UP	<0.00217 UJ	<0.00221 UP	<0.00223 UP	<0.00223 UP	<0.00215 UP	<0.00188 U
Gamma Bhc (Lindane)	58-89-9	0.025	0.05	0.21	mg/kg	<0.00179 U	<0.00203 UP	<0.00207 UP	<0.00213 UP	<0.00235 UP	<0.00239 UP	<0.00209 UP	<0.00251 UP	<0.00178 U	<0.00181 U	<0.00191 UP	<0.00217 UJ	<0.00221 UP	<0.00223 UP	<0.00223 UP	<0.00215 UP	<0.00188 U
Gamma-Chlordane	5566-34-7	NS	NS	NS	mg/kg	<0.00179 U	<0.00203 UP	<0.00207 UP	<0.00213 UP	<0.00235 UP	<0.00239 UP	<0.00209 UP	<0.00251 UP	<0.00178 U	<0.00181 U	<0.00191 UP	<0.00217 UJ	<0.00221 UP	<0.00223 UP	<0.00223 UP	<0.00215 UP	<0.00188 U
Heptachlor	76-44-8	0.013	0.38	0.53	mg/kg	<0.00179 U	<0.00203 UP	<0.00207 UP	<0.00213 UP	<0.00235 UP	<0.00239 UP	<0.00209 UP	<0.00251 UP	<0.00178 U	<0.00181 U	<0.00191 UP	<0.00217 UJ	<0.00221 UP	<0.00223 UP	<0.00223 UP	<0.00215 UP	<0.00188 U
Heptachlor Epoxide	1024-57-3	NS	NS	NS	mg/kg	<0.00179 U	<0.00203 UP	<0.00207 UP	<0.00213 UP	<0.00235 UP	<0.00239 UP	<0.00209 UP	<0.00251 UP	<0.00178 U	<0.00181 U	<0.00191 UP	<0.00217 UJ	<0.00221 UP	<0.00223 UP	<0.00223 UP	<0.00215 UP	<0.00188 U
Methoxychlor	72-43-5	NS	NS	NS	mg/kg	<0.00179 U	<0.00203 UP	<0.00207 UP	<0.00213 UP	<0.00235 UP	<0.00239 UP	<0.00209 UP	<0.00251 UP	<0.00178 U	<0.00181 U	<0.00191 UP	<0.00217 UJ	<0.00221 UP	<0.00223 UP	<0.00223 UP	<0.00215 UP	<0.00188 U
Toxaphene	8001-35-2	NS	NS	NS	mg/kg	<0.179 U	<0.203 UP	<0.207 UP	<0.213 UP	<0.235 UP	<0.239 UP	<0.209 UP	<0.251 UP	<0.178 U	<0.181 U	<0.191 UP	<0.217 UJ	<0.221 UP	<0.223 UP	<0.223 UP	<0.215 UP	<0.188 U
Herbicides																						
2,4,5-T (Trichlorophenoxyacetic Acid)	93-76-5	NS	NS	NS	mg/kg	<0.0215 U	<0.0246 UP	<0.025 UP	<0.026 UP	<0.0288 UP	<0.0292 UP	<0.0257 UP	<0.0302 UP	<0.0215 U	<0.0222 U	<0.0232 UP	<0.0264 UP	<0.0264 UP	<0.0267 UP	<0.0267 UP	<0.0266 UP	<0.0228 U
2,4-D (Dichlorophenoxyacetic Acid)	94-75-7	NS	NS	NS	mg/kg	<0.0215 U	<0.0246 UP	<0.025 UP	<0.026 UP	<0.0288 UP	<0.0292 UP	<0.0257 UP	<0.0302 UP	<0.0215 U	<0.0222 U	<0.0232 UP	<0.0264 UP	<0.0264 UP	<0.0267 UP	<0.0267 UP	<0.0266 UP	<0.0228 U
2,4-Dichlorophenoxybutyric acid	94-82-6	NS	NS	NS	mg/kg	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
Dalapon	75-99-0	NS	NS	NS	mg/kg	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
Dicamba	1918-00-9	NS	NS	NS	mg/kg	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
Silvex (2,4,5-Tp)	93-72-1	3.8	3.8	100	mg/kg	<0.0215 U	<0.0246 UP	<0.025 UP	<0.026 UP	<0.0288 UP	<0.0292 UP	<0.0257 UP	<0.0302 UP	<0.0215 U	<0.0222 U	<0.0232 UP	<0.0264 UP	<0.0264 UP	<0.0267 UP	<0.0267 UP	<0.0266 UP	<0.0228 U
Polychlorinated Biphenyl																						
PCB-1016 (Aroclor 1016)	12674-11-2	NS	NS	NS	mg/kg	<0.018 U	<0.0205 UP	<0.0209 UP	<0.0215 UP	<0.0237 UP	<0.0242 UP	<0.0211 UP	<0.0377 UP	<0.018 U	<0.0183 U	<0.0193 UP	<0.0219 UP	<0.0223 UP	<0.0225 UP	<0.0225 UP	<0.0217 UP	<0.0189 U
PCB-1221 (Aroclor 1221)	11104-28-2	NS	NS	NS	mg/kg	<0.018 U	<0.0205 UP	<0.0209 UP	<0.0215 UP	<0.0237 UP	<0.0242 UP	<0.0211 UP	<0.0377 UP	<0.018 U	<0.0183 U	<0.0193 UP	<0.0219 UP	<0.0223 UP	<0.0225 UP	<0.0225 UP	<0.0217 UP	<0.0189 U
PCB-1232 (Aroclor 1232)	11141-16-5	NS	NS	NS	mg/kg	<0.018 U	<0.0205 UP	<0.0209 UP	<0.0215 UP	<0.0237 UP	<0.0242 UP	<0.0211 UP	<0.0377 UP	<0.018 U	<0.0183 U	<0.0193 UP	<0.0219 UP	<0.0223 UP	<0.0225 UP	<0.0225 UP	<0.0217 UP	<0.0189 U
PCB-1242 (Aroclor 1242)	53469-21-9	NS	NS	NS	mg/kg	<0.018 U	<0.0205 UP	<0.0209 UP	<0.0215 UP	<0.0237 UP	<0.0242 UP	<0.0211 UP	<0.0377 UP	<0.018 U	<0.0183 U	0.182 J	<0.0219 UP	<0.0223 UP	<0.0225 UP	<0.0225 UP	<0.0217 UP	<0.0189 U
PCB-1248 (Aroclor 1248)	12672-29-6	NS	NS	NS	mg/kg	<0.018 U	<0.0205 UP	<0.0209 UP	<0.0215 UP	<0.0237 UP	<0.0242 UP	<0.0211 UP	<0.0377 UP	<0.018 U	<0.0183 U	<0.0193 UP	<0.0219 UP	<0.0223 UP	<0.0225 UP	<0.0225 UP	<0.0217 UP	<0.0189 U
PCB-1254 (Aroclor 1254)	11097-69-1	NS	NS	NS	mg/kg	<0.018 U	<0.0205 UP	<0.0209 UP	0.0552 J	0.0278 P	<0.0242 UP	<0.0211 UP	<0.0377 UP	<0.018 U	<0.0183 U	<0.0193 UP	0.344	<0.0223 UP	<0.0225 UP	<0.0225 UP	<0.0217 UP	<0.0189 U
PCB-1260 (Aroclor 1260)	11096-82-5	NS	NS	NS	mg/kg	<0.018 U	<0.0205 UP	<0.0209 UP	<0.0215 UP	<0.0237 UP	<0.0242 UP	<0.0211 UP	0.968 P	<0.018 U	<0.0183 U	0.31 J	<0.0219 UP	<0.0223 UP	<0.0225 UP	<0.0225 UP	<0.0217 UP	<0.0189 U
PCB-1262 (Aroclor 1262)	37324-23-5	NS	NS	NS	mg/kg	NA	NA	0.0211 J	0.083 J	NA	NA	NA	NA	NA	NA	NA	0.331 J	NA	NA	NA	NA	NA
PCB-1268 (Aroclor 1268)	11100-14-4	NS	NS	NS	mg/kg	NA	0.0302 P	NA	NA	NA	NA	NA	NA	NA	NA	0.156 J	NA	NA	NA	NA	NA	NA
Total PCBs	1336-36-3	**0.1**	3.2	1	mg/kg	<0.018 U	0.0302 P	0.0211 J	**0.138 J**	0.0278 P	<0.0242 UP	<0.0211 UP	**0.968 P**	<0.018 U	<0.0183 U	**0.648 J**	**0.674 J**	<0.0223 UP	<0.0225 UP	<0.0225 UP	<0.0217 UP	<0.0189 U
Metals																						
Aluminum	7429-90-5	NS	NS	NS	mg/kg	5,090	5,370	6,010 J	3,260 J	5,500	4,510	4,050	5,400	6,840	5,750	6,340	5,580 B	5,030	7,520	4,210	5,150 J	5,250
Antimony	7440-36-0	NS	NS	NS	mg/kg	<2.26 U	<2.58 U	<2.64 U	<2.72 U	<3.01 U	<3.05 U	<2.69 U	<3.21 U	<2.28 U	<2.32 U	<2.45 U	<2.79 U	<2.84 UJ	<2.86 U	<2.86 U	<2.78 UJ	<2.42 U
Arsenic	7440-38-2	**13**	16	16	mg/kg	1.4	8.25	5.19	4.82	10.5	**43.7**	**83.5**	8.59	2.42	1.59	11.3	8.48	8.8	8.04	10.5	**15.9**	<1.45 U
Barium	7440-39-3	**410**	820	410	mg/kg	12	155	407	273	**506**	321	382	**772**	21.7	14.4	**490**	287	**540 J**	212	290	**427 J**	16.1
Beryllium	7440-41-7	4.4	47	43	mg/kg	0.142	0.484	0.396	0.423	0.572	0.426	0.392	0.451	0.15	0.143	0.243	0.48	0.571	0.6	0.417	0.42	0.161
Cadmium	7440-43-9	**2.5**	7.5	2.5	mg/kg	<0.272 U	0.639	1 J	1.82 J	1.34	**3.41**	1.71	1.09	<0.273 U	<0.279 U	**4.85**	0.502	1.16 J	0.721	**2.51**	0.957	<0.29 U
Calcium	7440-70-2	NS	NS	NS	mg/kg	672	4,390	4,220 J	2,340 J	6,580	2,900	6,030	7,340	955	884	7,870	3,290 B	5,300	2,700	4,520	7,550	649
Chromium, Hexavalent	18540-29-9	1	19	1	mg/kg	<0.543 U	<0.619 UJ	<0.634 U	<0.653 U	<0.723 U	<0.733 U	<0.645 U	<0.77 U	<0.546 U	<0.557 U	<0.589 U	<0.669 UJ	<0.681 U	<0.686 U	<0.687 U	<0.668 U	<0.58 U
Chromium, Total	7440-47-3	NS	NS	NS	mg/kg	8.13	12.2	24.3	17.4	25.1	46.4	24.8	15.1	11.1	9.43	26.6	23.1	24.9 J	13.9	10.6	136 J	8.57
Chromium, Trivalent	16065-83-1	**30**	19	110	mg/kg	8.13	12.2	24.3	17.4	25.1	**46.4**	24.8	15.1	11.1	9.43	26.6	23.1	24.9	13.9	10.6	**136**	8.57
Cobalt	7440-48-4	NS	NS	NS	mg/kg	3.86	5.17	5.96	4.64	6.82	6.84	11.2	5.93	4.12	3.95	6.86	6.33	6.18	7.92	24.9	6.69 J	3.73
Copper	7440-50-8	**50**	1720	280	mg/kg	9.66	**70.3**	**53.7**	45.8	**281**	**81.3**	**11,900 D**	**81**	13	11.2	**146**	**81.5**	**106 J**	43.1	**129**	**112 J**	9.44
Cyanide	57-12-5	**2.3**	40	13	mg/kg	<0.543 U	<0.619 U	<0.634 U	<0.653 U	1.03	<0.733 U	<0.645 U	<0.77 U	<0.546 U	<0.557 U	<0.589 U	<0.669 U	0.894	<0.686 U	<0.687 U	<0.668 U	<0.58 U
Iron	7439-89-6	NS	NS	NS	mg/kg	8,660	14,700	6,230	7,200	19,600	9,940	49,300	11,500	9,440	8,400	24,900	13,200	30,400 J	9,980	52,800	34,400	9,750
Lead	7439-92-1	**63**	450	400	mg/kg	2.44	**290**	**363**	**317**	**653**	**284**	**559**	**606**	15.2	10.4	**586**	**349**	**421**	**163**	**236**	**505 J**	3.21
Magnesium	7439-95-4	NS	NS	NS	mg/kg	1,990	1,020	352 J	187 J	683	331	1,050	699	1,770	2,140	2,240	1,190 B	464	744	346	655	2,380
Manganese	7439-96-5	**1600**	2000	2000	mg/kg	160	157	62.4	43.9	141	66.7	272	96.6	174	193	215	138	163 J	110	168	197	211
Mercury	7439-97-6	**0.18**	0.73	0.3	mg/kg	<0.0326 U	0.089	0.129	0.0938	**0.639**	0.175	0.116	**0.523**	0.125	<0.0334 U	**0.372**	**1.23**	0.123	**0.289**	0.131	0.112	<0.0348 U
Nickel	7440-02-0	**30**	130	320	mg/kg	14.5	14.4	12.5	8.92	21.4	15.6	19.3	16.3	14.2	14.6	28.8	16	18	18	**116**	22.4 J	15.2
Potassium	7440-09-7	NS	NS	NS	mg/kg	520	430	546 J	322 J	553	426	424	625	520	516	633	587 B	490 B	703 B	528 B	573 J	606
Selenium	7782-49-2	**3.9**	4	110	mg/kg	<2.26 U	<2.58 U	<2.64 U	<2.72 U	<3.01 U	**8.94**	<2.69 U	<3.21 U	<2.28 U	<2.32 U	<2.45 U	<2.79 U	<2.84 U	<2.86 U	<2.86 U	<2.78 U	<2.42 U
Silver	7440-22-4	**2**	8.3	110	mg/kg	<0.456 U	<0.52 U	1.4	1.01	<0.607 U	0.745	**5.18**	0.68	<0.459 U	<0.468 U	0.795	1.25	0.851	0.801	1.68	**6.52 J**	<0.487 U
Sodium	7440-23-5	NS	NS	NS	mg/kg	64.9	189	381 J	224 J	338 J	259 J	<215 U	273	82.3	86.4	273	239	316	310	259	348 J	89.2
Thallium	7440-28-0	NS	NS	NS	mg/kg	<1.81 U	<2.07 U	<2.12 U	<2.18 U	<2.42 U	<2.45 U	<2.15 U	<2.57 U	<1.82 U	<1.86 U	<1.97 U	<2.24 U	<2.27 U	<2.29 U	<2.29 U	<2.23 U	<1.94 U
Vanadium	7440-62-2	NS	NS	NS	mg/kg	13.1	22	14.1	9.62	21.5	30.2	18.5	26.4	17.3	12.5	27	20.7	19.9	24.2	26	21.2	13.7
Zinc	7440-66-6	**109**	2480	6600	mg/kg	18	**177**	**329**	**291**	**535**	**241**	**716**	**488**	30	21.4	**1,200**	**192**	**371**	**115**	**414**	**306**	14

Table 2
Site Management Plan
Soil Sample Analytical Results

12074 Flatlands Avenue p/o Lot 1 Site
Brooklyn, New York
BCP Site No. C224353
Langan Project No.: 100688803

Analyte	CAS Number	NYSDEC Part 375 Unrestricted Use SCOs	NYSDEC Part 375 Protection of Groundwater SCOs	NYSDEC Part 375 Restricted Use Restricted-Residential SCOs	Location	PE18	PE19	PE20	PE20	PE21	PE22	PE23	PE24	PE25	PE26	PE27	PE28	PE29	PE30	PE31	PE32	PE33
					Sample Name	PE18_15	PE19_15.5	PE20_15.5	DUP_07282025	PE21_16	PE22_16.5	PE23_16.5	PE24_16.5	PE25_15	PE26_15	PE27_17	PE28_17	PE29_18	PE30_18	PE31_18.5	PE32_20	PE33_20
					Sample Date	06/19/2025	08/08/2025	07/28/2025	07/28/2025	07/22/2025	07/22/2025	07/22/2025	07/14/2025	06/19/2025	06/19/2025	08/11/2025	07/28/2025	07/24/2025	07/24/2025	07/24/2025	07/22/2025	06/19/2025
					Sample Elevation	15	15.5	15.5	15.5	16	16.5	16.5	16.5	15	15	17	17	18	18	18.5	20	20
					Unit	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result
Per- and Polyfluoroalkyl Substances																						
11-Chloroeicosafluoro-3-Oxaundecane-1-Sulfonic Acid (11Cl-PF3OUdS)	763051-92-9	NS	NS	NS	mg/kg	<0.000816 U	<0.000935 U	<0.000958 U	<0.000987 U	<0.00217 U	<0.00111 U	<0.000971 U	<0.00116 UJ	<0.000826 U	<0.000841 U	<0.000889 U	<0.00101 U	<0.00103 UJ	<0.00104 UJ	<0.00104 U	<0.001 U	<0.000877 U
1H,1H,2H,2H-Perfluorodecane Sulfonic Acid (8:2 FTS)	39108-34-4	NS	NS	NS	mg/kg	<0.000829 U	<0.00095 U	<0.000974 U	<0.001 U	<0.00221 U	<0.00112 U	<0.000987 U	<0.00117 U	<0.000839 U	<0.000854 U	<0.000903 U	<0.00102 U	<0.00104 UJ	<0.00105 UJ	<0.00105 UJ	<0.00102 U	<0.000891 U
1H,1H,2H,2H-Perfluorohexane Sulfonic Acid (4:2 FTS)	757124-72-4	NS	NS	NS	mg/kg	<0.00081 U	<0.000928 U	<0.000951 U	<0.00098 U	<0.00216 U	<0.0011 U	<0.000964 U	<0.00115 U	<0.000819 U	<0.000834 U	<0.000882 U	<0.000998 U	<0.00102 UJ	<0.00103 UJ	<0.00103 UJ	<0.000996 U	<0.00087 U
1H,1H,2H,2H-Perfluorooctane Sulfonic Acid (6:2 FTS)	27619-97-2	NS	NS	NS	mg/kg	<0.000821 U	<0.00094 U	<0.000963 U	<0.000993 U	<0.00219 U	<0.00111 U	<0.000977 U	<0.00116 U	<0.00083 U	<0.000845 U	<0.000893 U	<0.00101 U	<0.00103 UJ	<0.00104 UJ	<0.00104 UJ	<0.00101 U	<0.000882 U
2H,2H,3H,3H-Perfluorooctanoic Acid (5:3 FTCA)	914637-49-3	NS	NS	NS	mg/kg	<0.0054 U	<0.00619 U	0.00136 J	0.00141 J	<0.0144 U	<0.00731 U	<0.00643 U	<0.00764 U	<0.00546 U	<0.00556 U	<0.00588 U	0.0014 J	0.00108 J	<0.00686 U	<0.00687 U	<0.00664 U	<0.0058 U
3-Perfluoroheptyl Propanoic Acid (7:3 FTCA)	812-70-4	NS	NS	NS	mg/kg	<0.0054 U	<0.00619 U	0.00148 J	0.00152 J	<0.0144 U	<0.00731 U	<0.00643 U	<0.00764 U	<0.00546 U	<0.00556 U	<0.00588 U	0.00154 J	<0.00679 U	<0.00686 U	<0.00687 U	<0.00664 U	<0.0058 U
3-Perfluoropropyl Propanoic Acid (3:3 FTCA)	356-02-5	NS	NS	NS	mg/kg	<0.00108 UJ	<0.00124 U	<0.00127 U	<0.00131 U	<0.00288 U	<0.00146 U	<0.00129 U	<0.00153 U	<0.00109 UJ	<0.00111 UJ	<0.00118 U	<0.00133 U	<0.00136 U	<0.00137 U	<0.00137 U	<0.00133 U	<0.00116 UJ
4,8-Dioxa-3H-perfluorononanoic Acid (ADONA)	919005-14-4	NS	NS	NS	mg/kg	<0.000816 U	<0.000935 U	<0.000958 U	<0.000987 U	<0.00217 U	<0.00111 U	<0.000971 U	<0.00116 U	<0.000826 U	<0.000841 U	<0.000889 U	<0.00101 U	<0.00103 UJ	<0.00104 UJ	<0.00104 U	<0.001 U	<0.000877 U
9-Chlorohexadecafluoro-3-Oxanonane-1-Sulfonic Acid (9Cl-PF3ONS)	756426-58-1	NS	NS	NS	mg/kg	<0.000808 U	<0.000925 UJ	<0.000948 U	<0.000977 U	<0.00215 U	<0.00109 UJ	<0.000961 UJ	<0.00114 UJ	<0.000817 U	<0.000832 U	<0.000879 UJ	<0.000995 U	<0.00102 UJ	<0.00103 UJ	<0.00103 UJ	<0.000993 UJ	<0.000868 U
Hexafluoropropylene Oxide Dimer Acid (HFPO-DA)	13252-13-6	NS	NS	NS	mg/kg	<0.000864 U	<0.00099 U	<0.00101 U	<0.00104 U	<0.0023 UJ	<0.00117 U	<0.00103 U	<0.00122 UJ	<0.000874 U	<0.00089 U	<0.00094 U	<0.00106 U	<0.00109 UJ	<0.0011 UJ	<0.0011 UJ	<0.00106 U	<0.000928 U
N-ethyl Perfluorooctanesulfonamide (NEtFOSA)	4151-50-2	NS	NS	NS	mg/kg	<0.000216 U	<0.000247 U	<0.000254 U	<0.000261 U	<0.000575 U	<0.000293 U	<0.000257 U	<0.000306 U	<0.000219 U	<0.000222 U	<0.000235 U	<0.000266 U	<0.000272 U	<0.000275 U	<0.000275 U	<0.000266 U	<0.000232 U
N-ethyl Perfluorooctanesulfonamidoacetic Acid (NEtFOSAA)	2991-50-6	NS	NS	NS	mg/kg	<0.000216 U	<0.000247 U	<0.000254 U	<0.000261 U	<0.000575 U	<0.000293 U	<0.000257 U	<0.000306 UJ	<0.000219 U	<0.000222 U	<0.000235 U	<0.000266 U	<0.000272 U	<0.000275 UJ	<0.000275 U	<0.000266 U	<0.000232 U
N-ethyl Perfluorooctanesulfonamidoethanol (NEtFOSE)	1691-99-2	NS	NS	NS	mg/kg	<0.00216 U	<0.00247 U	<0.00254 U	<0.00261 U	<0.00575 U	<0.00293 U	<0.00257 U	<0.00306 U	<0.00219 U	<0.00222 U	<0.00235 U	<0.00266 U	0.000647 J	<0.00275 U	<0.00275 U	<0.00266 U	<0.00232 U
N-methyl Perfluorooctanesulfonamide (NMeFOSA)	31506-32-8	NS	NS	NS	mg/kg	<0.000216 U	<0.000247 U	<0.000254 U	<0.000261 U	<0.000575 U	<0.000293 U	<0.000257 U	<0.000306 UJ	<0.000219 U	<0.000222 U	<0.000235 U	<0.000266 U	<0.000272 U	<0.000275 U	<0.000275 U	<0.000266 U	<0.000232 U
N-methyl Perfluorooctanesulfonamidoacetic Acid (NMeFOSAA)	2355-31-9	NS	NS	NS	mg/kg	<0.000216 U	<0.000247 U	<0.000254 U	<0.000261 U	<0.000575 U	<0.000293 U	<0.000257 U	<0.000306 U	<0.000219 U	<0.000222 U	<0.000235 U	<0.000266 U	<0.000272 U	<0.000275 U	<0.000275 U	<0.000266 U	<0.000232 U
N-methyl Perfluorooctanesulfonamidoethanol (NMeFOSE)	24448-09-7	NS	NS	NS	mg/kg	<0.00216 U	<0.00247 U	<0.00254 U	<0.00261 U	<0.00575 U	<0.00293 U	<0.00257 U	<0.00306 U	<0.00219 U	<0.00222 U	<0.00235 U	<0.00266 U	<0.00272 U	<0.00275 U	<0.00275 U	<0.00266 U	<0.00232 U
Nonafluoro-3,6-dioxaheptanoic Acid (NFDHA)	151772-58-6	NS	NS	NS	mg/kg	<0.000432 U	<0.000495 U	<0.000507 U	<0.000522 U	<0.00115 U	<0.000585 U	<0.000514 U	<0.000611 UJ	<0.000437 U	<0.000445 U	<0.00047 U	<0.000532 U	<0.000544 U	<0.000549 U	<0.000549 U	<0.000531 U	<0.000464 U
Perfluoro(2-ethoxyethane)sulfonic Acid (PFEESA)	113507-82-7	NS	NS	NS	mg/kg	<0.000384 U	<0.00044 U	<0.000451 U	<0.000465 U	<0.00102 U	<0.000521 U	<0.000457 U	<0.000544 U	<0.000389 U	<0.000396 U	<0.000419 UJ	<0.000474 U	0.000162 J	0.000166 J	<0.000489 U	<0.000473 U	<0.000413 U
Perfluoro-3-methoxypropanoic Acid (PFMPA)	377-73-1	NS	NS	NS	mg/kg	<0.000432 UJ	<0.000495 U	<0.000507 U	<0.000522 U	<0.00115 U	<0.000585 U	<0.000514 U	<0.000611 U	<0.000437 UJ	<0.000445 UJ	<0.00047 U	<0.000532 U	0.0000692 J	0.0000707 J	0.0000761 J	<0.000531 U	<0.000464 UJ
Perfluoro-4-methoxybutanoic Acid (PFMBA)	863090-89-5	NS	NS	NS	mg/kg	<0.000432 UJ	<0.000495 U	<0.000507 U	<0.000522 U	<0.00115 U	<0.000585 U	<0.000514 U	<0.000611 U	<0.000437 UJ	<0.000445 UJ	<0.00047 U	<0.000532 U	0.000176 J	0.000175 J	<0.000549 U	<0.000531 U	<0.000464 UJ
Perfluorobutanesulfonic Acid (PFBS)	375-73-5	NS	NS	NS	mg/kg	<0.000191 U	<0.000219 U	<0.000224 U	<0.000231 U	<0.000509 U	<0.000259 U	<0.000227 U	<0.000271 U	<0.000193 U	<0.000197 U	<0.000208 U	<0.000236 U	<0.000241 U	<0.000243 U	<0.000243 U	<0.000235 U	<0.000205 U
Perfluorobutanoic Acid (PFBA)	375-22-4	NS	NS	NS	mg/kg	<0.000864 U	<0.00099 U	0.000676 J	0.000617 J	<0.0023 UJ	<0.00117 U	<0.00103 U	<0.00122 U	<0.000874 U	<0.00089 U	0.00557	<0.00106 U	<0.00109 U	<0.0011 U	<0.0011 U	<0.00106 U	<0.000928 U
Perfluorodecanesulfonic Acid (PFDS)	335-77-3	NS	NS	NS	mg/kg	<0.000208 U	<0.000239 U	<0.000245 U	<0.000252 U	<0.000555 U	<0.000282 U	<0.000248 U	<0.000295 U	<0.000211 U	<0.000215 U	<0.000227 U	<0.000257 U	<0.000262 U	<0.000265 U	<0.000265 U	<0.000256 U	<0.000224 U
Perfluorodecanoic Acid (PFDA)	335-76-2	NS	NS	NS	mg/kg	<0.000216 U	<0.000247 U	<0.000254 U	<0.000261 U	<0.000575 U	<0.000293 U	<0.000257 U	<0.000306 U	<0.000219 U	<0.000222 U	<0.000235 U	<0.000266 U	<0.000272 U	<0.000275 U	<0.000275 U	<0.000266 U	<0.000232 U
Perfluorododecanesulfonic Acid (PFDoS)	79780-39-5	NS	NS	NS	mg/kg	<0.000209 U	<0.00024 U	<0.000246 U	<0.000253 U	<0.000558 U	<0.000284 U	<0.000249 U	<0.000296 U	<0.000212 U	<0.000216 U	<0.000228 U	<0.000258 U	<0.000264 U	<0.000266 U	<0.000266 U	<0.000258 U	<0.000225 U
Perfluorododecanoic Acid (PFDoA)	307-55-1	NS	NS	NS	mg/kg	<0.000216 U	<0.000247 U	<0.000254 U	<0.000261 U	<0.000575 U	<0.000293 U	<0.000257 U	<0.000306 U	<0.000219 U	<0.000222 U	<0.000235 U	<0.000266 U	<0.000272 U	<0.000275 U	<0.000275 U	<0.000266 U	<0.000232 U
Perfluoroheptanesulfonic Acid (PFHpS)	375-92-8	NS	NS	NS	mg/kg	<0.000216 U	<0.000247 U	<0.000254 U	<0.000261 U	<0.000575 U	<0.000293 U	<0.000257 U	<0.000306 UJ	<0.000219 U	<0.000222 U	<0.000235 U	<0.000266 U	<0.000272 U	<0.000275 U	<0.000275 U	<0.000266 U	<0.000232 U
Perfluoroheptanoic Acid (PFHpA)	375-85-9	NS	NS	NS	mg/kg	<0.000216 U	<0.000247 U	<0.000254 U	<0.000261 U	<0.000575 U	<0.000293 U	<0.000257 U	<0.000306 U	<0.000219 U	<0.000222 U	<0.000235 U	<0.000266 U	<0.000272 U	<0.000275 UJ	<0.000275 U	<0.000266 U	<0.000232 U
Perfluorohexanesulfonic Acid (PFHxS)	355-46-4	NS	NS	NS	mg/kg	<0.000198 U	<0.000226 U	0.000581	0.000324	<0.000526 U	<0.000268 U	<0.000235 U	0.00105	<0.0002 U	<0.000204 U	<0.000215 U	0.00014 J	0.00033	<0.000251 U	<0.000251 U	0.000367	<0.000212 U
Perfluorohexanoic Acid (PFHxA)	307-24-4	NS	NS	NS	mg/kg	<0.000216 U	<0.000247 U	0.0000704 J	<0.000261 U	<0.000575 U	<0.000293 U	<0.000257 U	<0.000306 U	<0.000219 U	<0.000222 U	0.0000763 J	<0.000266 U	<0.000272 U	<0.000275 U	0.0000691 J	<0.000266 U	<0.000232 U
Perfluorononanesulfonic Acid (PFNS)	68259-12-1	NS	NS	NS	mg/kg	<0.000207 U	<0.000238 U	<0.000243 U	<0.000251 U	<0.000552 U	<0.000281 U	<0.000247 U	<0.000293 U	<0.00021 U	<0.000214 U	<0.000226 U	<0.000255 U	<0.000261 U	<0.000264 U	<0.000264 U	<0.000255 U	<0.000223 U
Perfluorononanoic Acid (PFNA)	375-95-1	NS	NS	NS	mg/kg	<0.000216 U	<0.000247 U	<0.000254 U	<0.000261 U	<0.000575 U	<0.000293 U	<0.000257 U	<0.000306 UJ	<0.000219 U	<0.000222 U	<0.000235 U	<0.000266 U	<0.000272 U	<0.000275 U	<0.000275 U	<0.000266 U	<0.000232 U
Perfluorooctanesulfonamide (PFOSA)	754-91-6	NS	NS	NS	mg/kg	<0.000216 U	<0.000247 U	0.0000435 J	0.0000486 J	<0.000575 U	<0.000293 U	<0.000257 U	<0.000306 U	<0.000219 U	<0.000222 U	0.0000466 J	0.0000433 J	<0.000272 U	<0.000275 U	<0.000275 U	<0.000266 UJ	<0.000232 U
Perfluorooctanesulfonic Acid (PFOS)	1763-23-1	**0.00088**	0.001	0.044	mg/kg	<0.000201 U	<0.00023 U	<0.000236 U	<0.000243 U	<0.000535 U	<0.000272 U	<0.000239 U	<0.000284 U	<0.000203 U	<0.000207 U	<0.000219 U	0.0000981 J	0.000148 J	0.000125 J	0.000208 J	<0.000216 U	
Perfluorooctanoic Acid (PFOA)	335-67-1	**0.00066**	0.0008	0.033	mg/kg	<0.000216 U	0.000142 J	0.000208 J	0.000175 J	0.000645 D	0.000119 J	0.000206 J	<0.000306 U	<0.000219 U	<0.000222 U	0.000197 J	0.000151 J	0.000161 J	0.000106 J	0.000195 J	0.000275	<0.000232 U
Perfluoropentanesulfonic Acid (PFPeS)	2706-91-4	NS	NS	NS	mg/kg	<0.000203 U	<0.000233 U	0.0000968 J	<0.000246 U	<0.000541 U	<0.000275 U	<0.000242 U	<0.000287 U	<0.000205 U	<0.000209 U	<0.000221 U	<0.00025 U	<0.000255 U	<0.000258 U	0.000109 J	<0.00025 U	<0.000218 U
Perfluoropentanoic Acid (PFPeA)	2706-90-3	NS	NS	NS	mg/kg	<0.000432 U	<0.000495 U	<0.000507 U	<0.000522 U	<0.00115 U	<0.000585 U	<0.000514 U	<0.000611 U	<0.000437 U	<0.000445 U	<0.00047 U	<0.000532 U	<0.000544 U	<0.000549 U	<0.000549 U	<0.000531 U	<0.000464 U
Perfluorotetradecanoic Acid (PFTeDA)	376-06-7	NS	NS	NS	mg/kg	<0.000216 U	<0.000247 U	<0.000254 U	<0.000261 U	<0.000575 U	<0.000293 U	<0.000257 U	<0.000306 U	<0.000219 U	<0.000222 U	<0.000235 U	<0.000266 U	<0.000272 U	<0.000275 U	<0.000275 U	<0.000266 U	<0.000232 U
Perfluorotridecanoic Acid (PFTrDA)	72629-94-8	NS	NS	NS	mg/kg	<0.000216 U	<0.000247 U	<0.000254 U	<0.000261 U	<0.000575 U	<0.000293 U	<0.000257 U	<0.000306 U	<0.000219 U	<0.000222 U	<0.000235 U	<0.000266 U	<0.000272 U	<0.000275 U	<0.000275 U	<0.000266 U	<0.000232 U
Perfluoroundecanoic Acid (PFUnA)	2058-94-8	NS	NS	NS	mg/kg	<0.000216 U	<0.000247 U	<0.000254 U	<0.000261 U	<0.000575 U	<0.000293 U	<0.000257 U	<0.000306 U	<0.000219 U	<0.000222 U	<0.000235 U	<0.000266 U	<0.000272 U	<0.000275 U	<0.000275 U	<0.000266 U	<0.000232 U
General Chemistry																						
Solids, Percent	SOLID	NS	NS	NS	Percent	92.1	80.8	78.9	76.6	69.1	68.2	77.5	64.9	91.5	89.7	84.9	74.7	73.4	72.9	72.8	74.9	86.2

Table 2
Site Management Plan
Soil Sample Analytical Results

12074 Flatlands Avenue p/o Lot 1 Site
Brooklyn, New York
BCP Site No. C224353
Langan Project No.: 100688803

Analyte	CAS Number	NYSDEC Part 375 Unrestricted Use SCOs	NYSDEC Part 375 Protection of Groundwater SCOs	NYSDEC Part 375 Restricted Use Restricted-Residential SCOs	Location	PE34	PE35	PE36	PE37	PE38	PE39	PE40	PE41	PE42	PE43	PE44	PE45	PE45	PE46	PE47	PE48	PE50
					Sample Name	PE34_20	PE35_18.5	PE36_18.5	PE37_19	PE38_20	PE39_18.5	PE40_18.5	PE41_20	PE42_20	PE43_19	PE44_19.5	PE45_19.5	DUP_08262025	PE46_19.5	PE47_19.5	PE48_19	PE50_19.5
					Sample Date	06/19/2025	08/11/2025	07/29/2025	07/24/2025	08/11/2025	07/24/2025	07/23/2025	06/19/2025	06/19/2025	09/02/2025	08/28/2025	08/26/2025	08/26/2025	08/26/2025	08/27/2025	08/27/2025	09/17/2025
					Sample Elevation	20	18.5	18.5	19	20	18.5	18.5	20	20	19	19.5	19.5	19.5	19.5	19.5	19	19.5
					Unit	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result
Volatile Organic Compounds																						
1,1,1,2-Tetrachloroethane	630-20-6	NS	NS	NS	mg/kg	<0.0054 U	<0.0083 U	<0.0075 U	<0.009 U	<0.0079 U	<0.0076 U	<0.0054 UJ	<0.0054 U	<0.0053 U	<0.0076 U	<0.0053 U	<0.011 U	<0.0095 U	<0.01 U	<0.008 U	<0.0089 U	NA
1,1,1-Trichloroethane	71-55-6	0.68	0.68	100	mg/kg	<0.0054 U	<0.0083 U	<0.0075 U	<0.009 U	<0.0079 U	<0.0076 U	<0.0054 U	<0.0054 U	<0.0053 U	<0.0076 U	<0.0053 U	<0.011 U	<0.0095 U	<0.01 U	<0.008 U	<0.0089 U	<0.0051 U
1,1,2,2-Tetrachloroethane	79-34-5	NS	NS	NS	mg/kg	<0.0054 U	<0.0083 U	<0.0075 U	<0.009 U	<0.0079 U	<0.0076 U	<0.0054 U	<0.0054 U	<0.0053 U	<0.0076 U	<0.0053 U	<0.011 U	<0.0095 U	<0.01 U	<0.008 U	<0.0089 U	<0.0051 U
1,1,2-Trichloro-1,2,2-Trifluoroethane	76-13-1	NS	NS	NS	mg/kg	<0.0054 U	<0.0083 U	<0.0075 U	<0.009 U	<0.0079 U	<0.0076 U	<0.0054 U	<0.0054 U	<0.0053 U	<0.0076 U	<0.0053 U	<0.011 U	<0.0095 U	<0.01 U	<0.008 U	<0.0089 U	<0.0051 U
1,1,2-Trichloroethane	79-00-5	NS	NS	NS	mg/kg	<0.0054 U	<0.0083 U	<0.0075 U	<0.009 U	<0.0079 U	<0.0076 U	<0.0054 U	<0.0054 U	<0.0053 U	<0.0076 U	<0.0053 U	0.016	<0.0095 U	<0.01 U	<0.008 U	<0.0089 U	<0.0051 U
1,1-Dichloroethane	75-34-3	0.27	0.27	47	mg/kg	<0.0054 U	<0.0083 U	<0.0075 U	<0.009 U	<0.0079 U	<0.0076 U	<0.0054 U	<0.0054 U	<0.0053 U	<0.0076 U	<0.0053 U	<0.011 U	<0.0095 U	<0.01 U	<0.008 UJ	<0.0089 UJ	<0.0051 U
1,1-Dichloroethene	75-35-4	0.24	0.33	0.98	mg/kg	<0.0054 U	<0.0083 U	<0.0075 U	<0.009 U	<0.0079 U	<0.0076 U	<0.0054 U	<0.0054 U	<0.0053 U	<0.0076 U	<0.0053 U	<0.011 U	<0.0095 U	<0.01 U	<0.008 U	<0.0089 U	<0.0051 U
1,1-Dichloropropene	563-58-6	NS	NS	NS	mg/kg	<0.0054 U	<0.0083 U	<0.0075 U	<0.009 U	<0.0079 U	<0.0076 U	<0.0054 U	<0.0054 U	<0.0053 U	<0.0076 U	<0.0053 U	<0.011 U	<0.0095 U	<0.01 U	<0.008 U	<0.0089 U	NA
1,2,3-Trichlorobenzene	87-61-6	NS	NS	NS	mg/kg	<0.0054 U	<0.0083 U	<0.0075 U	<0.009 U	<0.0079 U	<0.0076 U	<0.0054 U	<0.0054 U	<0.0053 U	<0.0076 U	<0.0053 U	<0.011 U	<0.0095 U	<0.01 U	<0.008 U	<0.0089 U	<0.0051 U
1,2,3-Trichloropropane	96-18-4	NS	NS	NS	mg/kg	<0.0054 U	<0.0083 U	<0.0075 U	<0.009 U	<0.0079 U	<0.0076 U	<0.0054 U	<0.0054 U	<0.0053 U	<0.0076 U	<0.0053 U	<0.011 U	<0.0095 U	<0.01 U	<0.008 U	<0.0089 U	NA
1,2,4-Trichlorobenzene	120-82-1	NS	NS	NS	mg/kg	<0.0054 U	<0.0083 U	<0.0075 U	<0.009 U	<0.0079 U	<0.0076 U	<0.0054 U	<0.0054 U	<0.0053 U	<0.0076 U	<0.0053 U	<0.011 U	<0.0095 U	<0.01 U	<0.008 U	<0.0089 U	<0.0051 U
1,2,4-Trimethylbenzene	95-63-6	5.9	5.9	100	mg/kg	<0.0054 U	<0.0083 U	<0.0075 U	<0.009 U	<0.0079 U	<0.0076 U	<0.0054 U	<0.0054 U	<0.0053 U	<0.0076 U	<0.0053 U	<0.011 U	<0.0095 U	<0.01 U	<0.008 U	<0.0089 U	<0.0051 U
1,2-Dibromo-3-Chloropropane	96-12-8	NS	NS	NS	mg/kg	<0.0054 U	<0.0083 U	<0.0075 U	<0.009 U	<0.0079 U	<0.0076 U	<0.0054 U	<0.0054 U	<0.0053 U	<0.0076 U	<0.0053 U	<0.011 U	<0.0095 U	<0.01 U	<0.008 U	<0.0089 U	<0.0051 U
1,2-Dibromoethane (Ethylene Dibromide)	106-93-4	NS	NS	NS	mg/kg	<0.0054 U	<0.0083 U	<0.0075 U	<0.009 U	<0.0079 U	<0.0076 U	<0.0054 U	<0.0054 U	<0.0053 U	<0.0076 U	<0.0053 U	<0.011 U	<0.0095 U	<0.01 U	<0.008 U	<0.0089 U	<0.0051 U
1,2-Dichlorobenzene	95-50-1	1.1	1.1	100	mg/kg	<0.0054 U	<0.0083 U	<0.0075 U	<0.009 U	<0.0079 U	<0.0076 U	<0.0054 U	<0.0054 U	<0.0053 U	<0.0076 U	<0.0053 U	<0.011 U	<0.0095 U	<0.01 U	<0.008 U	<0.0089 U	<0.0051 U
1,2-Dichloroethane	107-06-2	0.02	0.02	5.8	mg/kg	<0.0054 U	<0.0083 U	<0.0075 U	<0.009 U	<0.0079 U	<0.0076 U	<0.0054 U	<0.0054 U	<0.0053 U	<0.0076 U	<0.0053 U	<0.011 U	<0.0095 U	<0.01 U	<0.008 U	<0.0089 U	<0.0051 U
1,2-Dichloropropane	78-87-5	NS	NS	NS	mg/kg	<0.0054 U	<0.0083 U	<0.0075 U	<0.009 U	<0.0079 U	<0.0076 U	<0.0054 U	<0.0054 U	<0.0053 U	<0.0076 U	<0.0053 U	<0.011 U	<0.0095 U	<0.01 U	<0.008 U	<0.0089 U	<0.0051 U
1,3,5-Trimethylbenzene (Mesitylene)	108-67-8	3.1	3.1	100	mg/kg	<0.0054 U	<0.0083 U	<0.0075 U	<0.009 U	<0.0079 U	<0.0076 U	<0.0054 U	<0.0054 U	<0.0053 U	<0.0076 U	<0.0053 U	<0.011 U	<0.0095 U	<0.01 U	<0.008 U	<0.0089 U	<0.0051 U
1,3-Dichlorobenzene	541-73-1	2.6	2.6	38	mg/kg	<0.0054 U	<0.0083 U	<0.0075 U	<0.009 U	<0.0079 U	<0.0076 U	<0.0054 U	<0.0054 U	<0.0053 U	<0.0076 U	<0.0053 U	<0.011 U	<0.0095 U	<0.01 U	<0.008 U	<0.0089 U	<0.0051 U
1,3-Dichloropropane	142-28-9	NS	NS	NS	mg/kg	<0.0054 U	<0.0083 U	<0.0075 U	<0.009 U	<0.0079 U	<0.0076 U	<0.0054 U	<0.0054 U	<0.0053 U	<0.0076 U	<0.0053 U	<0.011 U	<0.0095 U	<0.01 U	<0.008 U	<0.0089 U	NA
1,4-Dichlorobenzene	106-46-7	1.8	1.8	24	mg/kg	<0.0054 U	<0.0083 U	<0.0075 U	<0.009 U	<0.0079 U	<0.0076 U	<0.0054 U	<0.0054 U	<0.0053 U	<0.0076 U	<0.0053 U	<0.011 U	<0.0095 U	<0.01 U	<0.008 U	<0.0089 U	<0.0051 U
1,4-Dioxane (P-Dioxane)	123-91-1	0.1	0.1	5.7	mg/kg	<0.11 U	NA	NA	NA	NA	NA	NA	<0.11 U	<0.11 U	NA	NA	NA	NA	NA	NA	NA	<0.076 U
2,2-Dichloropropane	594-20-7	NS	NS	NS	mg/kg	<0.0054 U	<0.0083 U	<0.0075 U	<0.009 U	<0.0079 U	<0.0076 U	<0.0054 U	<0.0054 U	<0.0053 U	<0.0076 U	<0.0053 U	<0.011 U	<0.0095 U	<0.01 U	<0.008 U	<0.0089 U	NA
2-Chlorotoluene	95-49-8	NS	NS	NS	mg/kg	<0.0054 U	<0.0083 U	<0.0075 U	<0.009 U	<0.0079 U	<0.0076 U	<0.0054 U	<0.0054 U	<0.0053 U	<0.0076 U	<0.0053 U	<0.011 U	<0.0095 U	<0.01 U	<0.008 U	<0.0089 U	NA
2-Hexanone (MBK)	591-78-6	NS	NS	NS	mg/kg	<0.0054 U	<0.0083 U	<0.0075 U	<0.009 U	<0.0079 U	<0.0076 U	<0.0054 U	<0.0054 U	<0.0053 U	<0.0076 U	<0.0053 U	<0.011 U	<0.0095 U	<0.01 U	<0.008 U	<0.0089 U	<0.025 U
4-Chlorotoluene	106-43-4	NS	NS	NS	mg/kg	<0.0054 U	<0.0083 U	<0.0075 U	<0.009 U	<0.0079 U	<0.0076 U	<0.0054 U	<0.0054 U	<0.0053 U	<0.0076 U	<0.0053 U	<0.011 U	<0.0095 U	<0.01 U	<0.008 U	<0.0089 U	NA
Acetone	67-64-1	**0.03**	0.03	100	mg/kg	**0.031**	**0.086**	**0.12 J**	**0.14**	**0.23**	**0.051**	**0.049**	**0.052**	**0.061**	<0.015 U	**0.041**	**0.35 J**	0.024 J	**0.094**	**0.17 J**	**0.17**	<0.025 U
Acrolein	107-02-8	NS	NS	NS	mg/kg	<0.011 U	<0.017 U	<0.015 U	<0.018 U	<0.016 U	<0.015 U	<0.011 U	<0.011 U	<0.011 U	<0.015 U	<0.011 U	<0.021 U	<0.019 U	<0.02 U	<0.016 U	<0.018 U	NA
Acrylonitrile	107-13-1	NS	NS	NS	mg/kg	<0.0054 U	<0.0083 U	<0.0075 U	<0.009 U	<0.0079 U	<0.0076 U	<0.0054 U	<0.0054 U	<0.0053 U	<0.0076 U	<0.0053 U	<0.011 U	<0.0095 U	<0.01 U	<0.008 U	<0.0089 U	NA
Benzene	71-43-2	0.06	0.06	3.7	mg/kg	<0.0054 U	<0.0083 U	<0.0075 U	<0.009 U	<0.0079 U	<0.0076 U	<0.0054 U	<0.0054 U	<0.0053 U	<0.0076 U	<0.0053 U	<0.011 U	<0.0095 U	<0.01 U	<0.008 U	<0.0089 U	<0.0051 U
Bromobenzene	108-86-1	NS	NS	NS	mg/kg	<0.0054 U	<0.0083 U	<0.0075 U	<0.009 U	<0.0079 U	<0.0076 U	<0.0054 U	<0.0054 U	<0.0053 U	<0.0076 U	<0.0053 U	<0.011 U	<0.0095 U	<0.01 U	<0.008 U	<0.0089 U	NA
Bromochloromethane	74-97-5	NS	NS	NS	mg/kg	<0.0054 U	<0.0083 U	<0.0075 U	<0.009 U	<0.0079 U	<0.0076 U	<0.0054 U	<0.0054 U	<0.0053 U	<0.0076 U	<0.0053 U	<0.011 U	<0.0095 U	<0.01 U	<0.008 U	<0.0089 U	<0.0051 U
Bromodichloromethane	75-27-4	NS	NS	NS	mg/kg	<0.0054 U	<0.0083 U	<0.0075 U	<0.009 U	<0.0079 U	<0.0076 U	<0.0054 U	<0.0054 U	<0.0053 U	<0.0076 U	<0.0053 U	<0.011 U	<0.0095 U	<0.01 U	<0.008 U	<0.0089 U	<0.0051 U
Bromoform	75-25-2	NS	NS	NS	mg/kg	<0.0054 U	<0.0083 U	<0.0075 U	<0.009 U	<0.0079 U	<0.0076 U	<0.0054 UJ	<0.0054 U	<0.0053 U	<0.0076 U	<0.0053 U	<0.011 U	<0.0095 U	<0.01 U	<0.008 U	<0.0089 U	<0.0051 U
Bromomethane	74-83-9	NS	NS	NS	mg/kg	<0.0054 U	<0.0083 U	<0.0075 U	<0.009 U	<0.0079 U	<0.0076 U	<0.0054 U	<0.0054 U	<0.0053 U	<0.0076 U	<0.0053 U	<0.011 U	<0.0095 U	<0.01 U	<0.008 U	<0.0089 U	<0.0051 U
Carbon Disulfide	75-15-0	NS	NS	NS	mg/kg	<0.0054 U	<0.0083 U	0.007 J	0.0078 J	<0.0079 U	<0.0076 U	<0.0054 U	<0.0054 U	<0.0053 U	<0.0076 U	<0.0053 U	0.01 J	<0.0095 U	<0.01 U	0.015 J	<0.0089 U	<0.0051 U
Carbon Tetrachloride	56-23-5	0.76	0.76	7.1	mg/kg	<0.0054 U	<0.0083 U	<0.0075 U	<0.009 U	<0.0079 U	<0.0076 U	<0.0054 U	<0.0054 U	<0.0053 U	<0.0076 U	<0.0053 U	<0.011 U	<0.0095 U	<0.01 U	<0.008 U	<0.0089 U	<0.0051 U
Chlorobenzene	108-90-7	4.5	4.5	100	mg/kg	<0.0054 U	<0.0083 U	<0.0075 U	<0.009 U	<0.0079 U	<0.0076 U	<0.0054 U	<0.0054 U	<0.0053 U	<0.0076 U	<0.0053 U	<0.011 U	<0.0095 U	<0.01 U	<0.008 U	<0.0089 U	<0.0051 U
Chloroethane	75-00-3	NS	NS	NS	mg/kg	<0.0054 U	<0.0083 U	<0.0075 U	<0.009 U	<0.0079 U	<0.0076 U	<0.0054 U	<0.0054 U	<0.0053 U	<0.0076 U	<0.0053 U	<0.011 U	<0.0095 U	<0.01 U	<0.008 U	<0.0089 U	<0.0051 U
Chloroform	67-66-3	0.37	0.37	24	mg/kg	<0.0054 U	<0.0083 U	<0.0075 U	<0.009 U	<0.0079 U	<0.0076 U	<0.0054 UJ	<0.0054 U	<0.0053 U	<0.0076 U	<0.0053 U	<0.011 U	<0.0095 U	<0.01 U	<0.008 U	<0.0089 U	<0.0051 U
Chloromethane	74-87-3	NS	NS	NS	mg/kg	<0.0054 U	<0.0083 U	<0.0075 U	<0.009 U	<0.0079 U	<0.0076 U	<0.0054 U	<0.0054 U	<0.0053 U	<0.0076 U	<0.0053 UJ	<0.011 U	<0.0095 U	<0.01 U	<0.008 U	<0.0089 U	<0.0051 U
Cis-1,2-Dichloroethene	156-59-2	0.19	0.19	41	mg/kg	<0.0054 U	<0.0083 U	<0.0075 U	<0.009 U	<0.0079 U	<0.0076 U	<0.0054 U	<0.0054 U	<0.0053 U	<0.0076 U	<0.0053 U	<0.011 U	<0.0095 U	<0.01 U	<0.008 U	<0.0089 U	<0.0051 U
Cis-1,3-Dichloropropene	10061-01-5	NS	NS	NS	mg/kg	<0.0054 U	<0.0083 U	<0.0075 U	<0.009 U	<0.0079 U	<0.0076 U	<0.0054 U	<0.0054 U	<0.0053 U	<0.0076 U	<0.0053 U	<0.011 U	<0.0095 U	<0.01 U	<0.008 U	<0.0089 U	<0.0051 U
Cyclohexane	110-82-7	NS	NS	NS	mg/kg	<0.0054 U	<0.0083 U	<0.0075 U	<0.009 U	<0.0079 U	<0.0076 U	<0.0054 U	<0.0054 U	0.0038 J	<0.0076 U	<0.0053 U	<0.011 U	<0.0095 U	<0.01 U	<0.008 U	<0.0089 U	<0.0051 U
Cymene	99-87-6	NS	NS	NS	mg/kg	<0.0054 U	<0.0083 U	<0.0075 U	<0.009 U	<0.0079 U	<0.0076 U	<0.0054 U	<0.0054 U	<0.0053 U	<0.0076 U	<0.0053 U	<0.011 U	<0.0095 U	<0.01 U	<0.008 U	<0.0089 U	NA
Dibromochloromethane	124-48-1	NS	NS	NS	mg/kg	<0.0054 U	<0.0083 U	<0.0075 U	<0.009 U	<0.0079 U	<0.0076 U	<0.0054 U	<0.0054 U	<0.0053 U	<0.0076 U	<0.0053 U	<0.011 U	<0.0095 U	<0.01 U	<0.008 U	<0.0089 U	<0.0051 U
Dibromomethane	74-95-3	NS	NS	NS	mg/kg	<0.0054 U	<0.0083 U	<0.0075 U	<0.009 U	<0.0079 U	<0.0076 U	<0.0054 U	<0.0054 U	<0.0053 U	<0.0076 U	<0.0053 U	<0.011 U	<0.0095 U	<0.01 U	<0.008 U	<0.0089 U	NA
Dichlorodifluoromethane	75-71-8	NS	NS	NS	mg/kg	<0.0054 UJ	<0.0083 U	<0.0075 U	<0.009 U	<0.0079 U	<0.0076 UJ	<0.0054 U	<0.0054 UJ	<0.0053 UJ	<0.0076 U	<0.0053 UJ	<0.011 U	<0.0095 U	<0.01 U	<0.008 U	<0.0089 U	<0.0051 U
Ethylbenzene	100-41-4	1	1	76	mg/kg	<0.0054 U	<0.0083 U	<0.0075 U	<0.009 U	<0.0079 U	<0.0076 U	<0.0054 U	<0.0054 U	<0.0053 U	<0.0076 U	<0.0053 U	<0.011 U	<0.0095 U	<0.01 U	<0.008 U	<0.0089 U	<0.0051 U
Hexachlorobutadiene	87-68-3	NS	NS	NS	mg/kg	<0.0054 U	<0.0083 U	<0.0075 U	<0.009 U	<0.0079 U	<0.0076 U	<0.0054 UJ	<0.0054 U	<0.0053 U	<0.0076 U	<0.0053 U	<0.011 U	<0.0095 U	<0.01 U	<0.008 U	<0.0089 U	NA
Isopropylbenzene (Cumene)	98-82-8	NS	NS	NS	mg/kg	<0.0054 U	<0.0083 U	<0.0075 U	<0.009 U	<0.0079 U	<0.0076 U	<0.0054 U	<0.0054 U	<0.0053 U	<0.0076 U	<0.0053 U	<0.011 U	<0.0095 U	<0.01 U	<0.008 U	<0.0089 U	<0.0051 U
M,P-Xylene	179601-23-1	NS	NS	NS	mg/kg	<0.011 U	<0.017 U	<0.015 U	<0.018 U	<0.016 U	<0.015 U	<0.011 U	<0.011 U	<0.011 U	<0.015 U	<0.011 U	<0.021 U	<0.019 U	<0.02 U	<0.016 U	<0.018 U	<0.0051 U
Methyl Acetate	79-20-9	NS	NS	NS	mg/kg	<0.0054 U	<0.0083 U	<0.0075 U	<0.009 U	<0.0079 U	<0.0076 UJ	<0.0054 U	<0.0054 U	0.0035 J	<0.0076 U	<0.0053 U	0.025	<0.0095 U	<0.01 U	<0.008 U	<0.0089 U	<0.051 U
Methyl Ethyl Ketone (2-Butanone)	78-93-3	0.1	0.1	100	mg/kg	0.0061	0.03	0.013 J	0.012	0.055	0.0044 J	0.0041 J	0.01	0.013	<0.0076 U	0.01	0.051 J	<0.0095 UJ	<0.01 U	<0.008 UJ	<0.0089 UJ	<0.03 U
Methyl Isobutyl Ketone (4-Methyl-2-Pentanone)	108-10-1	NS	NS	NS	mg/kg	<0.0054 U	<0.0083 U	<0.0075 U	<0.009 U	<0.0079 U	<0.0076 U	<0.0054 U	<0.0054 U	<0.0053 U	<0.0076 U	<0.0053 U	<0.011 U	<0.0095 U	<0.01 U	<0.008 U	<0.0089 U	<0.025 U
Methylcyclohexane	108-87-2	NS	NS	NS	mg/kg	<0.0054 U	<0.0083 U	0.0057 J	<0.009 U	<0.0079 U	<0.0076 U	<0.0054 U	<0.0054 U	0.01	<0.0076 U	<0.0053 U	<0.011 U	<0.0095 U	<0.01 U	<0.008 U	<0.0089 U	<0.0051 U
Methylene Chloride	75-09-2	0.05	0.05	81	mg/kg	<0.011 U	<0.017 U	<0.015 U	<0.018 U	<0.016 U	<0.015 U	<0.011 U	<0.011 U	<0.011 U	<0.015 U	<0.011 U	<0.021 U	<0.019 U	<0.02 U	<0.016 U	<0.018 U	<0.0051 U
n-Butylbenzene	104-51-8	18	18	100	mg/kg	<0.0054 U	<0.0083 U	<0.0075 U	<0.009 U	<0.0079 U	<0.0076 U	<0.0054 U	<0.0054 U	<0.0053 U	<0.0076 U	<0.0053 U	<0.011 U	<0.0095 U	<0.01 U	<0.008 UJ	<0.0089 UJ	NA
n-Propylbenzene	103-65-1	5	5	100	mg/kg	<0.0054 U	<0.0083 U	<0.0075 U	<0.009 U	<0.0079 U	<0.0076 U	<0.0054 U	<0.0054 U	<0.0053 U	<0.0076 U	<0.0053 U	<0.011 U	<0.0095 U	<0.01 U	<0.008 U	<0.0089 U	NA
o-Xylene (1,2-Dimethylbenzene)	95-47-6	NS	NS	NS	mg/kg	<0.0054 U	<0.0083 U	<0.0075 U	<0.009 U	<0.0079 U	<0.0076 U	<0.0054 U	<0.0054 U	<0.0053 U	<0.0076 U	<0.0053 U	<0.011 U	<0.0095 U	<0.01 U	<0.008 U	<0.0089 U	<0.0051 U
Sec-Butylbenzene	135-98-8	25	25	100	mg/kg	<0.0054 U	<0.0083 U	<0.0075 U	<0.009 U	<0.0079 U	<0.0076 U	<0.0054 U	<0.0054 U	<0.0053 U	<0.0076 U	<0.0053 U	<0.011 U	<0.0095 U	<0.01 U	<0.008 U	<0.0089 U	NA
Styrene	100-42-5	NS	NS	NS	mg/kg	<0.0054 U	<0.0083 U	<0.0075 U	<0.009 U	<0.0079 U	<0.0076 U	<0.0054 U	<0.0054 U	<0.0053 U	<0.0076 U	<0.0053 U	<0.011 U	<0.0095 U	<0.01 U	<0.008 U	<0.0089 U	<0.0051 U
T-Butylbenzene	98-06-6	11	11	100	mg/kg	<0.0054 U	<0.0083 U	<0.0075 UJ	<0.009 U	<0.0079 U	<0.0076 UJ	<0.0054 U	<0.0054 U	<0.0053 U	<0.0076 UJ	<0.0053 U	<0.011 U	<0.0095 U	<0.01 U	<0.008 UJ	<0.0089 UJ	NA
Tert-Butyl Alcohol	75-65-0	NS	NS	NS	mg/kg	<0.027 U	<0.041 U	<0.037 U	<0.045 U	0.034 J	<0.038 U	0.017 J	<0.027 U	<0.027 U	<0.038 U	<0.026 U	<0.053 U	<0.047 U	<0.05 U	<0.04 U	<0.045 U	NA
Tert-Butyl Methyl Ether (MTBE)	1634-04-4	0.1	0.1	100	mg/kg	<0.0054 U	<0.0083 U	<0.0075 U	<0.009 U	<0.0079 U	<0.0076 U	<0.0054 U	<0.0054 U	<0.0053 U	<0.0076 U	<0.0053 U	<0.011 U	<0.0095 U	<0.01 U	<0.008 U	<0.0089 U	<0.01 U
Tetrachloroethene (PCE)	127-18-4	1.3	1.3	18	mg/kg	<0.0054 U	<0.0083 U	<0.0075 U	<0.009 U	<0.0079 U	<0.0076 U	<0.0054 UJ	<0.0054 U	<0.0053 U	<0.0076 U	<0.0053 U	<0.011 U	<0.0095 U	<0.01 U	<0.008 U	<0.0089 U	<0.0051 U
Toluene	108-88-3	0.7	0.7	100	mg/kg	<0.0054 U	<0.0083 U	<0.0075 U	<0.009 U	<0.0079 U	<0.0076 U	<0.0054 U	<0.0054 U	<0.0053 U	<0.0076 U	<0.0053 U	<0.011 U	<0.0095 U	<0.01 U	<0.008 U	<0.0089 U	<0.0051 U
Total Xylenes	1330-20-7	0.26	1.2	100	mg/kg	<0.016 U	<0.025 U	<0.022 U	<0.027 U	<0.024 U	<0.023 U	<0.016 U	<0.016 U	<0.016 U	<0.023 U	<0.016 U	<0.032 U	<0.028 U	<0.03 U	<0.024 U	<0.027 U	NA
Trans-1,2-Dichloroethene	156-60-5	0.19	0.19	100	mg/kg	<0.0054 U	<0.0083 U	<0.0075 U	<0.009 U	<0.0079 U	<0.0076 U	<0.0054 U	<0.0054 U	<0.0053 U	<0.0076 U	<0.0053 U	<0.011 U	<0.0095 U	<0.01 U	<0.008 U	<0.0089 U	<0.0051 U
Trans-1,3-Dichloropropene	10061-02-6	NS	NS	NS	mg/kg	<0.0054 U	<0.0083 U	<0.0075 U	<0.009 U	<0.0079 U	<0.0076 U	<0.0054 U	<0.0054 U	<0.0053 U	<0.0076 U	<0.0053 U	<0.011 U	<0.0095 U	<0.01 U	<0.008 U	<0.0089 U	<0.0051 U
Trans-1,4-Dichloro-2-Butene	110-57-6	NS	NS	NS	mg/kg	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
Trichloroethene (TCE)	79-01-6	0.47	0.47	6.4	mg/kg	<0.0054 U	<0.0083 U	<0.0075 U	<0.009 U	<0.0079 U	<0.0076 U	<0.0054 U	<0.0054 U	<0.0053 U	<0.0076 U	<0.0053 U	<0.011 U	<0.0095 U	<0.01 U	<0.008 U	<0.0089 U	<0.0051 U
Trichlorofluoromethane	75-69-4	NS	NS	NS	mg/kg	<0.0054 U	<0.0083 U	<0.0075 U	<0.009 U	<0.0079 U	<0.0076 U	<0.0054 U	<0.0054 U	<0.0053 U	<0.0076 U	<0.0053 U	<0.011 U	<0.0095 U	<0.01 U	<0.008 U	<0.0089 U	<0.0051 U
Vinyl Chloride	75-01-4	0.03	0.03	0.48	mg/kg	<0.0054 U	<0.0083 U	<0.0075 U	<0.009 U	<0.0079 U	<0.0076 U	<0.0054 U	<0.0054 U	<0.0053 U	<0.0076 U	<0.0053 UJ	<0.011 U	<0.0095 U	<0.01 U	<0.008 U	<0.0089 U	<0.0051 U

Table 2
Site Management Plan
Soil Sample Analytical Results

12074 Flatlands Avenue p/o Lot 1 Site
Brooklyn, New York
BCP Site No. C224353
Langan Project No.: 100688803

Analyte	CAS Number	NYSDEC Part 375 Unrestricted Use SCOs	NYSDEC Part 375 Protection of Groundwater SCOs	NYSDEC Part 375 Restricted Use Restricted-Residential SCOs	Location	PE34	PE35	PE36	PE37	PE38	PE39	PE40	PE41	PE42	PE43	PE44	PE45	PE45	PE46	PE47	PE48	PE50
					Sample Name	PE34_20	PE35_18.5	PE36_18.5	PE37_19	PE38_20	PE39_18.5	PE40_18.5	PE41_20	PE42_20	PE43_19	PE44_19.5	PE45_19.5	DUP_08262025	PE46_19.5	PE47_19.5	PE48_19	PE50_19.5
					Sample Date	06/19/2025	08/11/2025	07/29/2025	07/24/2025	08/11/2025	07/24/2025	07/23/2025	06/19/2025	06/19/2025	09/02/2025	08/28/2025	08/26/2025	08/26/2025	08/26/2025	08/27/2025	08/27/2025	09/17/2025
					Sample Elevation	20	18.5	18.5	19	20	18.5	18.5	20	20	19	19.5	19.5	19.5	19.5	19.5	19	19.5
					Unit	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result
Semi-Volatile Organic Compounds																						
1,2,4,5-Tetrachlorobenzene	95-94-3	NS	NS	NS	mg/kg	<0.199 U	<0.213 UJ	<0.207 U	<0.226 U	<0.204 UJ	<0.214 U	<0.182 U	<0.184 U	<0.174 U	<0.201 U	<0.18 U	<0.251 U	<0.265 U	<0.212 U	<0.223 U	<0.236 U	<1.41 U
1,2,4-Trichlorobenzene	120-82-1	NS	NS	NS	mg/kg	<0.0997 U	<0.107 UJ	<0.104 U	<0.113 U	<0.102 UJ	<0.107 U	<0.0909 U	<0.0921 U	<0.087 U	<0.101 U	<0.09 U	<0.126 U	<0.132 U	<0.106 U	<0.112 U	<0.118 U	<0.705 U
1,2-Dichlorobenzene	95-50-1	1.1	1.1	100	mg/kg	<0.0997 U	<0.107 UJ	<0.104 U	<0.113 U	<0.102 UJ	<0.107 U	<0.0909 U	<0.0921 U	<0.087 U	<0.101 U	<0.09 U	<0.126 U	<0.132 U	<0.106 U	<0.112 U	<0.118 U	<0.705 U
1,2-Diphenylhydrazine	122-66-7	NS	NS	NS	mg/kg	<0.0997 U	<0.107 UJ	<0.104 U	<0.113 U	<0.102 UJ	<0.107 U	<0.0909 U	<0.0921 U	<0.087 U	<0.101 U	<0.09 U	<0.126 U	<0.132 U	<0.106 U	<0.112 U	<0.118 U	<0.705 U
1,3-Dichlorobenzene	541-73-1	2.6	2.6	38	mg/kg	<0.0997 U	<0.107 UJ	<0.104 U	<0.113 U	<0.102 UJ	<0.107 U	<0.0909 U	<0.0921 U	<0.087 U	<0.101 U	<0.09 U	<0.126 U	<0.132 U	<0.106 U	<0.112 U	<0.118 U	<0.705 U
1,4-Dichlorobenzene	106-46-7	1.8	1.8	24	mg/kg	<0.0997 U	<0.107 UJ	<0.104 U	<0.113 U	<0.102 UJ	<0.107 U	<0.0909 U	<0.0921 U	<0.087 U	<0.101 U	<0.09 U	<0.126 U	<0.132 U	<0.106 U	<0.112 U	<0.118 U	<0.705 U
1,4-Dioxane (P-Dioxane)	123-91-1	0.1	0.1	5.7	mg/kg	<0.0183 U	<0.0198 U	<0.0194 U	<0.0198 U	<0.0196 U	<0.0198 U	<0.0196 U	<0.0198 U	<0.0192 U	<0.0196 U	<0.0196 U	<0.0198 U	<0.0198 U	<0.0198 U	<0.0198 U	<0.0196 U	<0.0187 U
2,3,4,6-Tetrachlorophenol	58-90-2	NS	NS	NS	mg/kg	<0.199 U	<0.213 UJ	<0.207 U	<0.226 U	<0.204 UJ	<0.214 U	<0.182 U	<0.184 U	<0.174 U	<0.201 U	<0.18 U	<0.251 U	<0.265 U	<0.212 U	<0.223 U	<0.236 U	<1.41 U
2,4,5-Trichlorophenol	95-95-4	NS	NS	NS	mg/kg	<0.0997 U	<0.107 UJ	<0.104 U	<0.113 U	<0.102 UJ	<0.107 U	<0.0909 U	<0.0921 U	<0.087 U	<0.101 U	<0.09 U	<0.126 U	<0.132 U	<0.106 U	<0.112 U	<0.118 U	<0.705 U
2,4,6-Trichlorophenol	88-06-2	NS	NS	NS	mg/kg	<0.0997 U	<0.107 UJ	<0.104 U	<0.113 U	<0.102 UJ	<0.107 U	<0.0909 U	<0.0921 U	<0.087 U	<0.101 U	<0.09 U	<0.126 U	<0.132 U	<0.106 U	<0.112 U	<0.118 U	<0.705 U
2,4-Dichlorophenol	120-83-2	NS	NS	NS	mg/kg	<0.0997 U	<0.107 UJ	<0.104 U	<0.113 U	<0.102 UJ	<0.107 U	<0.0909 U	<0.0921 U	<0.087 U	<0.101 U	<0.09 U	<0.126 U	<0.132 U	<0.106 U	<0.112 U	<0.118 U	<0.705 U
2,4-Dimethylphenol	105-67-9	NS	NS	NS	mg/kg	<0.0997 U	<0.107 UJ	<0.104 U	<0.113 U	<0.102 UJ	<0.107 U	<0.0909 U	<0.0921 U	<0.087 U	<0.101 U	<0.09 U	<0.126 U	<0.132 U	<0.106 U	<0.112 U	<0.118 U	<0.705 U
2,4-Dinitrophenol	51-28-5	NS	NS	NS	mg/kg	<0.199 U	<0.213 UJ	<0.207 U	<0.226 U	0.52 J	<0.214 U	<0.182 U	<0.184 U	<0.174 U	<0.201 U	<0.18 U	<0.251 U	<0.265 U	<0.212 U	<0.223 UJ	<0.236 UJ	<1.41 U
2,4-Dinitrotoluene	121-14-2	NS	NS	NS	mg/kg	<0.0997 U	<0.107 UJ	<0.104 U	<0.113 U	<0.102 UJ	<0.107 U	<0.0909 U	<0.0921 U	<0.087 U	<0.101 U	<0.09 U	<0.126 U	<0.132 U	<0.106 U	<0.112 U	<0.118 U	<0.705 U
2,6-Dinitrotoluene	606-20-2	NS	NS	NS	mg/kg	<0.0997 U	<0.107 UJ	<0.104 U	<0.113 U	<0.102 UJ	<0.107 U	<0.0909 U	<0.0921 U	<0.087 U	<0.101 U	<0.09 U	<0.126 U	<0.132 U	<0.106 U	<0.112 U	<0.118 U	<0.705 U
2-Chloronaphthalene	91-58-7	NS	NS	NS	mg/kg	<0.0997 U	<0.107 UJ	<0.104 U	<0.113 U	<0.102 UJ	<0.107 U	<0.0909 U	<0.0921 U	<0.087 U	<0.101 U	<0.09 U	<0.126 U	<0.132 U	<0.106 U	<0.112 U	<0.118 U	<0.705 U
2-Chlorophenol	95-57-8	NS	NS	NS	mg/kg	<0.0997 U	<0.107 UJ	<0.104 U	<0.113 U	<0.102 UJ	<0.107 U	<0.0909 U	<0.0921 U	<0.087 U	<0.101 U	<0.09 U	<0.126 U	<0.132 U	<0.106 U	<0.112 U	<0.118 U	<0.705 U
2-Methylnaphthalene	91-57-6	NS	NS	NS	mg/kg	<0.0997 U	<0.107 UJ	<0.104 U	<0.113 U	<0.102 UJ	<0.107 U	0.064 JD	<0.0921 U	<0.087 U	<0.101 U	<0.09 U	<0.126 U	<0.132 U	<0.106 U	<0.112 U	<0.118 U	<0.705 U
2-Methylphenol (o-Cresol)	95-48-7	0.33	0.33	100	mg/kg	<0.0997 U	<0.107 UJ	<0.104 U	<0.113 U	<0.102 UJ	<0.107 U	<0.0909 U	<0.0921 U	<0.087 U	<0.101 U	<0.09 U	<0.126 U	<0.132 U	<0.106 U	<0.112 U	<0.118 U	<0.705 U
2-Nitroaniline	88-74-4	NS	NS	NS	mg/kg	<0.199 U	<0.213 UJ	<0.207 U	<0.226 U	<0.204 UJ	<0.214 U	<0.182 U	<0.184 U	<0.174 U	<0.201 U	<0.18 U	<0.251 U	<0.265 U	<0.212 U	<0.223 U	<0.236 U	<1.41 U
2-Nitrophenol	88-75-5	NS	NS	NS	mg/kg	<0.0997 U	<0.107 UJ	<0.104 U	<0.113 U	<0.102 UJ	<0.107 U	<0.0909 U	<0.0921 U	<0.087 U	<0.101 U	<0.09 U	<0.126 U	<0.132 U	<0.106 U	<0.112 U	<0.118 U	<0.705 U
3 & 4 Methylphenol (m&p Cresol)	65794-96-9	**0.33**	0.33	100	mg/kg	<0.0997 U	<0.107 UJ	<0.104 U	<0.113 U	<0.102 UJ	<0.107 U	<0.0909 U	<0.0921 U	<0.087 U	<0.101 U	<0.09 U	<0.126 U	<0.132 U	<0.106 U	<0.112 U	<0.118 U	<0.705 U
3,3'-Dichlorobenzidine	91-94-1	NS	NS	NS	mg/kg	<0.0997 U	<0.107 UJ	<0.104 U	<0.113 U	<0.102 UJ	<0.107 U	<0.0909 U	<0.0921 U	<0.087 U	<0.101 U	<0.09 U	<0.126 U	<0.132 U	<0.106 U	<0.112 U	<0.118 U	<0.705 U
3-Nitroaniline	99-09-2	NS	NS	NS	mg/kg	<0.199 U	<0.213 UJ	<0.207 U	<0.226 U	<0.204 UJ	<0.214 U	<0.182 U	<0.184 U	<0.174 U	<0.201 U	<0.18 U	<0.251 U	<0.265 U	<0.212 U	<0.223 U	<0.236 U	<1.41 U
4,6-Dinitro-2-Methylphenol	534-52-1	NS	NS	NS	mg/kg	<0.199 U	<0.213 UJ	<0.207 U	<0.226 U	<0.204 UJ	<0.214 U	<0.182 U	<0.184 U	<0.174 U	<0.201 U	<0.18 U	<0.251 U	<0.265 U	<0.212 U	<0.223 U	<0.236 U	<1.41 U
4-Bromophenyl Phenyl Ether	101-55-3	NS	NS	NS	mg/kg	<0.0997 U	<0.107 UJ	<0.104 U	<0.113 U	<0.102 UJ	<0.107 U	<0.0909 U	<0.0921 U	<0.087 U	<0.101 U	<0.09 U	<0.126 U	<0.132 U	<0.106 U	<0.112 U	<0.118 U	<0.705 U
4-Chloro-3-Methylphenol	59-50-7	NS	NS	NS	mg/kg	<0.0997 U	<0.107 UJ	<0.104 U	<0.113 U	<0.102 UJ	<0.107 U	<0.0909 U	<0.0921 U	<0.087 U	<0.101 U	<0.09 U	<0.126 U	<0.132 U	<0.106 U	<0.112 U	<0.118 U	<0.705 U
4-Chloroaniline	106-47-8	NS	NS	NS	mg/kg	<0.0997 U	<0.107 UJ	<0.104 U	<0.113 U	<0.102 UJ	<0.107 U	<0.0909 U	<0.0921 U	<0.087 U	<0.101 U	<0.09 U	<0.126 U	<0.132 U	<0.106 U	<0.112 U	<0.118 U	<0.705 U
4-Chlorophenyl Phenyl Ether	7005-72-3	NS	NS	NS	mg/kg	<0.0997 U	<0.107 UJ	<0.104 U	<0.113 U	<0.102 UJ	<0.107 U	<0.0909 U	<0.0921 U	<0.087 U	<0.101 U	<0.09 U	<0.126 U	<0.132 U	<0.106 U	<0.112 U	<0.118 U	<0.705 U
4-Nitroaniline	100-01-6	NS	NS	NS	mg/kg	<0.199 U	<0.213 UJ	<0.207 U	<0.226 U	<0.204 UJ	<0.214 U	<0.182 U	<0.184 U	<0.174 U	<0.201 U	<0.18 U	<0.251 U	<0.265 U	<0.212 U	<0.223 U	<0.236 U	<1.41 U
4-Nitrophenol	100-02-7	NS	NS	NS	mg/kg	<0.199 U	<0.213 UJ	<0.207 U	<0.226 U	<0.204 UJ	<0.214 U	<0.182 U	<0.184 U	<0.174 U	<0.201 U	<0.18 U	<0.251 U	<0.265 U	<0.212 U	<0.223 U	<0.236 U	<1.41 U
Acenaphthene	83-32-9	20	98	100	mg/kg	<0.0997 U	<0.107 UJ	<0.104 U	<0.113 U	<0.102 UJ	<0.107 U	0.0712 JD	<0.0921 U	0.0695 JD	<0.101 U	<0.09 U	<0.126 U	<0.132 U	<0.106 U	<0.112 U	<0.118 U	<0.705 U
Acenaphthylene	208-96-8	100	365	100	mg/kg	<0.0997 U	<0.107 UJ	<0.104 U	<0.113 U	<0.102 UJ	<0.107 U	<0.0909 U	<0.0921 U	<0.087 U	<0.101 U	<0.09 U	<0.126 U	0.138 D	<0.106 U	<0.112 U	<0.118 U	<0.705 U
Acetophenone	98-86-2	NS	NS	NS	mg/kg	<0.0997 U	<0.107 UJ	<0.104 U	<0.113 U	<0.102 UJ	<0.107 U	<0.0909 U	<0.0921 U	<0.087 U	<0.101 U	<0.09 U	<0.126 U	<0.132 U	<0.106 U	<0.112 U	<0.118 U	<0.705 U
Aniline (Phenylamine, Aminobenzene)	62-53-3	0.04	0.04	8.1	mg/kg	<0.399 U	<0.427 UJ	<0.415 U	<0.454 U	<0.409 UJ	<0.429 U	<0.364 U	<0.369 U	<0.348 U	<0.403 U	<0.36 U	<0.504 U	<0.531 U	<0.425 U	<0.447 U	<0.473 U	<2.82 U
Anthracene	120-12-7	100	1000	100	mg/kg	<0.0997 U	<0.107 UJ	<0.104 U	<0.113 U	<0.102 UJ	<0.107 U	0.146 D	<0.0921 U	0.134 D	0.111 D	<0.09 U	<0.126 U	0.18 D	<0.106 U	<0.112 U	<0.118 U	<0.705 U
Atrazine	1912-24-9	NS	NS	NS	mg/kg	<0.0997 U	<0.107 UJ	<0.104 U	<0.113 U	<0.102 UJ	<0.107 U	<0.0909 U	<0.0921 U	<0.087 U	<0.101 U	<0.09 U	<0.126 U	<0.132 U	<0.106 U	<0.112 U	<0.118 U	<0.705 U
Benzaldehyde	100-52-7	NS	NS	NS	mg/kg	<0.0997 U	<0.107 UJ	<0.104 U	<0.113 U	<0.102 UJ	<0.107 U	<0.0909 U	<0.0921 U	<0.087 U	<0.101 U	<0.09 U	<0.126 U	<0.132 U	<0.106 U	<0.112 U	<0.118 U	<0.705 U
Benzidine	92-87-5	NS	NS	NS	mg/kg	<0.399 U	<0.427 UJ	<0.415 U	<0.454 U	<0.409 UJ	<0.429 U	<0.364 U	<0.369 U	<0.348 U	<0.403 U	<0.36 U	<0.504 U	<0.531 U	<0.425 U	<0.447 U	<0.473 U	<2.82 U
Benzo(a)anthracene	56-55-3	**1**	1	1.4	mg/kg	0.0653 JD	0.105 J	<0.104 U	<0.113 U	0.14 J	<0.107 U	0.167 D	0.0927 D	0.193 D	0.227 D	<0.09 U	<0.126 UJ	0.499 J	0.0535 JD	<0.112 U	<0.118 U	0.389 JD
Benzo(a)pyrene	50-32-8	**1**	22	1	mg/kg	<0.0997 U	0.07 J	<0.104 U	<0.113 U	0.131 J	<0.107 U	0.145 D	0.0618 JD	0.158 D	0.192 D	<0.09 U	<0.126 UJ	0.439 J	<0.106 U	<0.112 U	<0.118 U	<0.705 U
Benzo(b)fluoranthene	205-99-2	**1**	2.1	1.4	mg/kg	<0.0997 U	0.132 J	<0.104 U	<0.113 U	0.182 J	<0.107 U	0.0894 JD	0.0567 JD	0.145 D	0.179 D	<0.09 U	<0.126 U	0.382 D	<0.106 U	<0.112 U	<0.118 U	<0.705 U
Benzo(g,h,i)Perylene	191-24-2	**0.64**	1000	4.9	mg/kg	<0.0997 U	0.0657 J	<0.104 U	<0.113 U	0.114 J	<0.107 U	0.0836 JD	0.0478 JD	0.113 D	0.0965 JD	<0.09 U	<0.126 U	0.236 D	<0.106 U	<0.112 U	<0.118 U	<0.705 U
Benzo(k)fluoranthene	207-08-9	**0.8**	2	4.9	mg/kg	<0.0997 U	0.0597 J	<0.104 U	<0.113 U	0.0637 J	<0.107 U	0.0945 D	0.0559 JD	0.133 D	0.176 D	<0.09 U	<0.126 UJ	0.434 J	<0.106 U	<0.112 U	<0.118 U	<0.705 U
Benzoic Acid	65-85-0	NS	NS	NS	mg/kg	<0.0997 U	<0.107 UJ	<0.104 U	<0.113 U	<0.102 UJ	<0.107 U	<0.0909 U	<0.0921 U	<0.087 U	<0.101 U	<0.09 U	<0.126 U	<0.132 U	<0.106 U	<0.112 U	<0.118 U	<0.705 U
Benzyl Alcohol	100-51-6	NS	NS	NS	mg/kg	<0.0997 U	<0.107 UJ	<0.104 U	<0.113 U	<0.102 UJ	<0.107 U	<0.0909 U	<0.0921 U	<0.087 U	<0.101 U	<0.09 U	<0.126 U	<0.132 U	<0.106 U	<0.112 U	<0.118 U	<0.705 U
Benzyl Butyl Phthalate	85-68-7	NS	NS	NS	mg/kg	<0.0997 U	<0.107 UJ	<0.104 U	<0.113 U	<0.102 UJ	<0.107 U	<0.0909 U	<0.0921 U	<0.087 U	<0.101 U	<0.09 U	<0.126 U	<0.132 U	<0.106 U	<0.112 U	<0.118 U	<0.705 U
Biphenyl (Diphenyl)	92-52-4	NS	NS	NS	mg/kg	<0.0997 U	<0.107 UJ	<0.104 U	<0.113 U	<0.102 UJ	<0.107 U	<0.0909 U	<0.0921 U	<0.087 U	<0.101 U	<0.09 U	<0.126 U	<0.132 U	<0.106 U	<0.112 U	<0.118 U	<0.705 U
Bis(2-chloroethoxy) methane	111-91-1	NS	NS	NS	mg/kg	<0.0997 U	<0.107 UJ	<0.104 U	<0.113 U	<0.102 UJ	<0.107 U	<0.0909 U	<0.0921 U	<0.087 U	<0.101 U	<0.09 U	<0.126 U	<0.132 U	<0.106 U	<0.112 U	<0.118 U	<0.705 U
Bis(2-chloroethyl) ether (2-chloroethyl ether)	111-44-4	NS	NS	NS	mg/kg	<0.0997 U	<0.107 UJ	<0.104 U	<0.113 U	<0.102 UJ	<0.107 U	<0.0909 U	<0.0921 U	<0.087 U	<0.101 U	<0.09 U	<0.126 U	<0.132 U	<0.106 U	<0.112 U	<0.118 U	<0.705 U
Bis(2-chloroisopropyl) ether	108-60-1	NS	NS	NS	mg/kg	<0.0997 U	<0.107 UJ	<0.104 U	<0.113 U	<0.102 UJ	<0.107 U	<0.0909 U	<0.0921 U	<0.087 U	<0.101 U	<0.09 U	<0.126 U	<0.132 U	<0.106 U	<0.112 U	<0.118 U	<0.705 U
Bis(2-ethylhexyl) phthalate	117-81-7	NS	NS	NS	mg/kg	<0.0997 U	0.673 J	<0.104 U	<0.113 U	0.248 J	<0.107 U	<0.0909 U	<0.0921 U	0.073 JD	0.453 D	<0.09 U	<0.126 UJ	0.394 J	0.722 D	0.674 D	0.0736 JD	0.394 JD
Caprolactam	105-60-2	NS	NS	NS	mg/kg	<0.199 U	<0.213 UJ	<0.207 U	<0.226 U	<0.204 UJ	<0.214 U	<0.182 U	<0.184 U	<0.174 U	<0.201 U	<0.18 U	<0.251 U	<0.265 U	<0.212 U	<0.223 U	<0.236 U	<1.41 U
Carbazole	86-74-8	NS	NS	NS	mg/kg	<0.0997 U	<0.107 UJ	<0.104 U	<0.113 U	<0.102 UJ	<0.107 U	<0.0909 U	<0.0921 U	0.0494 JD	<0.101 U	<0.09 U	<0.126 U	0.0699 JD	<0.106 U	<0.112 U	<0.118 U	<0.705 U
Chrysene	218-01-9	**1**	1	4.9	mg/kg	<0.0997 U	0.109 J	<0.104 U	<0.113 U	0.138 J	<0.107 U	0.197 D	0.0883 JD	0.203 D	0.224 D	<0.09 U	<0.126 UJ	0.525 J	0.136 D	<0.112 U	<0.118 U	0.372 JD
Dibenz(a,h)anthracene	53-70-3	**0.33**	1000	0.33	mg/kg	<0.0997 U	<0.107 UJ	<0.104 U	<0.113 U	<0.102 UJ	<0.107 U	<0.0909 U	<0.0921 U	<0.087 U	<0.101 U	<0.09 U	<0.126 U	<0.132 U	<0.106 U	<0.112 U	<0.118 U	<0.705 U
Dibenzofuran	132-64-9	**2.1**	110	18	mg/kg	<0.0997 U	<0.107 UJ	<0.104 U	<0.113 U	<0.102 UJ	<0.107 U	<0.0909 U	<0.0921 U	<0.087 U	<0.101 U	<0.09 U	<0.126 U	<0.132 U	<0.106 U	<0.112 U	<0.118 U	<0.705 U
Dibutyl phthalate	84-74-2	NS	NS	NS	mg/kg	<0.0997 U	<0.107 UJ	<0.104 U	<0.113 U	<0.102 UJ	<0.107 U	<0.0909 U	<0.0921 U	<0.087 U	<0.101 U	<0.09 U	<0.126 U	<0.132 U	<0.106 U	<0.112 U	<0.118 U	<0.705 U
Diethyl phthalate	84-66-2	NS	NS	NS	mg/kg	<0.0997 U	<0.107 UJ	<0.104 U	<0.113 U	<0.102 UJ	<0.107 U	<0.0909 U	<0.0921 U	<0.087 U	<0.101 U	<0.09 U	<0.126 U	<0.132 U	<0.106 U	<0.112 U	<0.118 U	<0.705 U
Dimethyl phthalate	131-11-3	NS	NS	NS	mg/kg	<0.0997 U	<0.107 UJ	<0.104 U	<0.113 U	<0.102 UJ	<0.107 U	<0.0909 U	<0.0921 U	<0.087 U	<0.101 U	<0.09 U	<0.126 U	<0.132 U	<0.106 U	<0.112 U	<0.118 U	<0.705 U
Dioctyl phthalate	117-84-0	NS	NS	NS	mg/kg	<0.0997 U	<0.107 UJ	<0.104 U	<0.113 U	<0.102 UJ	<0.107 U	<0.0909 U	<0.0921 U	<0.087 U	<0.101 U	<0.09 U	<0.126 U	<0.132 U	<0.106 U	<0.112 U	<0.118 U	<0.705 U
Fluoranthene	206-44-0	85	1000	100	mg/kg	0.107 D	0.188 J	<0.104 U	<0.113 U	0.23 J	<0.107 U	0.353 D	0.188 D	0.378 D	0.363 D	<0.09 U	<0.126 UJ	0.816 J	0.104 JD	<0.112 U	<0.118 U	0.738 D
Fluorene	86-73-7	30	386	100	mg/kg	<0.0997 U	<0.107 UJ	<0.104 U	<0.113 U	<0.102 UJ	<0.107 U	0.121 D	<0.0921 U	0.0911 D	0.0579 JD	<0.09 U	<0.126 U	0.0942 JD	<0.106 U	<0.112 U	<0.118 U	<0.705 U
Hexachlorobenzene	118-74-1	0.33	3.2	0.33	mg/kg	<0.0997 U	<0.107 UJ	<0.104 U	<0.113 U	<0.102 UJ	<0.107 U	<0.0909 U	<0.0921 U	<0.087 U	<0.101 U	<0.09 U	<0.126 U	<0.132 U	<0.106 U	<0.112 U	<0.118 U	<0.705 U
Hexachlorobutadiene	87-68-3	NS	NS	NS	mg/kg	<0.0997 U	<0.107 UJ	<0.104 U	<0.113 U	<0.102 UJ	<0.107 U	<0.0909 U	<0.0921 U	<0.087 U	<0.101 U	<0.09 U	<0.126 U	<0.132 U	<0.106 U	<0.112 U	<0.118 U	<0.705 U
Hexachlorocyclopentadiene	77-47-4	NS	NS	NS	mg/kg	<0.0997 UJ	<0.107 UJ	<0.104 U	<0.113 U	<0.102 UJ	<0.107 U	<0.0909 U	<0.0921 UJ	<0.087 UJ	<0.101 U	<0.09 U	<0.126 U	<0.132 U	<0.106 U	<0.112 U	<0.118 U	<0.705 U
Hexachloroethane	67-72-1	NS	NS	NS	mg/kg	<0.0997 U	<0.107 UJ	<0.104 U	<0.113 U	<0.102 UJ	<0.107 U	<0.0909 U	<0.0921 U	<0.087 U	<0.101 U	<0.09 U	<0.126 U	<0.132 U	<0.106 U	<0.112 U	<0.118 U	<0.705 U
Indeno(1,2,3-cd)pyrene	193-39-5	**0.5**	6.6	1.4	mg/kg	<0.0997 U	0.07 J	<0.104 U	<0.113 U	0.105 J	<0.107 U	0.0843 JD	<0.0921 U	0.0834 JD	0.0852 JD	<0.09 U	<0.126 U	0.21 D	<0.106 U	<0.112 U	<0.118 U	<0.705 U
Isophorone	78-59-1	NS	NS	NS	mg/kg	<0.0997 U	<0.107 UJ	<0.104 U	<0.113 U	<0.102 UJ	<0.107 U	<0.0909 U	<0.0921 U	<0.087 U	<0.101 U	<0.09 U	<0.126 U	<0.132 U	<0.106 U	<0.112 U	<0.118 U	<0.705 U
Naphthalene	91-20-3	12	12	100	mg/kg	<0.0997 U	<0.107 UJ	<0.104 U	0.105 JD	0.0882 J	0.0685 JD	<0.0909 U	<0.0921 U	0.0459 JD	0.09 JD	<0.09 U	<0.126 U	0.089 JD	<0.106 U	<0.112 U	<0.118 U	<0.705 U
Nitrobenzene	98-95-3	0.08	0.08	1.8	mg/kg	<0.0997 U	<0.107 UJ	<0.104 U	<0.113 U	<0.102 UJ	<0.107 U	<0.0909 U	<0.0921 U	<0.087 U	<0.101 U	<0.09 U	<0.126 U	<0.132 U	<0.106 U	<0.112 U	<0.118 U	<0.705 U
n-Nitrosodimethylamine	62-75-9	NS	NS	NS	mg/kg	<0.0997 U	<0.107 UJ	<0.104 U	<0.113 U	<0.102 UJ	<0.107 U	<0.0909 U	<0.0921 U	<0.087 U	<0.101 U	<0.09 U	<0.126 U	<0.132 U	<0.106 U	<0.112 U	<0.118 U	<0.705 U
n-Nitrosodi-N-Propylamine	621-64-7	NS	NS	NS	mg/kg	<0.0997 U	<0.107 UJ	<0.104 U	<0.113 U	<0.102 UJ	<0.107 U	<0.0909 U	<0.0921 U	<0.087 U	<0.101 U	<0.09 U	<0.126 U	<0.132 U	<0.106 U	<0.112 U	<0.118 U	<0.705 U
n-Nitrosodiphenylamine	86-30-6	NS	NS	NS	mg/kg	<0.0997 U	<0.107 UJ	<0.104 U	<0.113 U	<0.102 UJ	<0.107 U	<0.0909 U	<0.0921 U	<0.087 U	<0.101 U	<0.09 U	<0.126 U	<0.132 U	<0.106 U	<0.112 U	<0.118 U	<0.705 U
Pentachlorophenol	87-86-5	0.8	0.8	1.3	mg/kg	<0.0997 U	<0.107 UJ	<0.104 U	<0.113 U	<0.102 UJ	<0.107 U	<0.0909 U	<0.0921 U	<0.087 U	<0.101 U	<0.09 U	<0.126 U	<0.132 U	<0.106 U	<0.112 U	<0.118 U	<0.705 U
Phenanthrene	85-01-8	**1.1**	1000	4.9	mg/kg	0.0669 JD	0.142 J	<0.104 U	<0.113 U	0.135 J	<0.107 U	0.618 D	0.116 D	0.395 D	0.347 D	<0.09 U	<0.126 UJ	0.465 J	0.101 JD	<0.112 U	<0.118 U	0.451 JD
Phenol	108-95-2	0.33	0.33	100	mg/kg	<0.0997 U	<0.107 UJ	<0.104 U	<0.113 U	<0.102 UJ	<0.107 U	<0.0909 U	<0.0921 U	<0.087 U	<0.101 U	<0.09 U	<0.126 U	<0.132 U	<0.106 U	<0.112 U	<0.118 U	<0.705 U
Pyrene	129-00-0	64	1000	100	mg/kg	0.119 D	0.166 J	<0.104 U	<0.113 U	0.251 J	<0.107 U	0.489 D	0.248 D	0.623 D	0.447 D	<0.09 U	<0.126 UJ	0.947 J	0.11 D	0.0732 JD	<0.118 U	1.03 D
Pyridine	110-86-1	NS	NS	NS	mg/kg	<0.399 U	<0.427 UJ	<0.415 U	<0.454 U	<0.409 UJ	<0.429 U	<0.364 U	<0.369 U	<0.348 U	<0.403 U	<0.36 U	<0.504 U	<0.531 U	<0.425 U	<0.447 U	<0.473 U	<2.82 U

Table 2
Site Management Plan
Soil Sample Analytical Results

12074 Flatlands Avenue p/o Lot 1 Site
Brooklyn, New York
BCP Site No. C224353
Langan Project No.: 100688803

Analyte	CAS Number	NYSDEC Part 375 Unrestricted Use SCOs	NYSDEC Part 375 Protection of Groundwater SCOs	NYSDEC Part 375 Restricted Use Restricted-Residential SCOs	Location	PE34	PE35	PE36	PE37	PE38	PE39	PE40	PE41	PE42	PE43	PE44	PE45	PE45	PE46	PE47	PE48	PE50
					Sample Name	PE34_20	PE35_18.5	PE36_18.5	PE37_19	PE38_20	PE39_18.5	PE40_18.5	PE41_20	PE42_20	PE43_19	PE44_19.5	PE45_19.5	DUP_08262025	PE46_19.5	PE47_19.5	PE48_19	PE50_19.5
					Sample Date	06/19/2025	08/11/2025	07/29/2025	07/24/2025	08/11/2025	07/24/2025	07/23/2025	06/19/2025	06/19/2025	09/02/2025	08/28/2025	08/26/2025	08/26/2025	08/26/2025	08/27/2025	08/27/2025	09/17/2025
					Sample Elevation	20	18.5	18.5	19	20	18.5	18.5	20	20	19	19.5	19.5	19.5	19.5	19.5	19	19.5
					Unit	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result
Pesticides																						
4,4'-DDD	72-54-8	**0.0033**	14	5	mg/kg	<0.00198 U	<0.00213 UP	<0.00202 UP	<0.00221 UP	<0.00204 UP	<0.00209 UP	<0.00178 UP	0.00219 D	<0.00172 U	<0.00198 UP	<0.00177 UP	<0.00249 UJ	**0.00814 J**	<0.00209 UP	<0.00223 UP	<0.00236 UP	**0.037 DP**
4,4'-DDE	72-55-9	**0.0033**	9.3	3.4	mg/kg	<0.00198 U	<0.00213 UP	<0.00202 UP	<0.00221 UP	<0.00204 UP	<0.00209 UP	<0.00178 UP	<0.00179 U	<0.00172 U	<0.00198 UP	<0.00177 UP	<0.00249 UP	<0.00265 UP	<0.00209 UP	<0.00223 UP	<0.00236 UP	**0.0156 DP**
4,4'-DDT	50-29-3	**0.0033**	135	3.8	mg/kg	<0.00198 U	<0.00213 UP	<0.00202 UP	<0.00221 UP	<0.00204 UP	<0.00209 UP	<0.00178 UP	<0.00179 U	<0.00172 U	0.00207 DP	<0.00177 UP	<0.00249 UP	<0.00265 UP	<0.00209 UP	<0.00223 UP	<0.00236 UP	<0.00186 UP
Aldrin	309-00-2	0.0048	0.19	0.044	mg/kg	<0.00198 U	<0.00213 UP	<0.00202 UP	<0.00221 UP	<0.00204 UP	<0.00209 UP	<0.00178 UP	<0.00179 U	<0.00172 U	<0.00198 UP	<0.00177 UP	<0.00249 UP	<0.00265 UP	<0.00209 UP	<0.00223 UP	<0.00236 UP	<0.00186 UP
Alpha BHC (Alpha Hexachlorocyclohexane)	319-84-6	0.02	0.02	0.18	mg/kg	<0.00198 U	<0.00213 UP	<0.00202 UP	<0.00221 UP	<0.00204 UP	<0.00209 UP	<0.00178 UP	<0.00179 U	<0.00172 U	<0.00198 UP	<0.00177 UP	<0.00249 UP	<0.00265 UP	<0.00209 UP	<0.00223 UP	<0.00236 UP	<0.00186 UP
Alpha Chlordane	5103-71-9	**0.014**	4.5	0.65	mg/kg	<0.00198 U	<0.00213 UP	<0.00202 UP	<0.00221 UP	<0.00204 UP	<0.00209 UP	<0.00178 UP	<0.00179 U	<0.00172 U	<0.00198 UP	<0.00177 UP	<0.00249 UP	0.00269 DP	<0.00209 UP	<0.00223 UP	<0.00236 UP	0.00361 DP
Alpha Endosulfan	959-98-8	4.3	65	35	mg/kg	<0.00198 U	<0.00213 UP	<0.00202 UP	<0.00221 UP	<0.00204 UP	<0.00209 UP	<0.00178 UP	<0.00179 U	<0.00172 U	<0.00198 UP	<0.00177 UP	<0.00249 UP	<0.00265 UP	<0.00209 UP	<0.00223 UP	<0.00236 UP	<0.00186 UP
Beta Bhc (Beta Hexachlorocyclohexane)	319-85-7	0.021	0.09	0.18	mg/kg	<0.00198 U	<0.00213 UP	<0.00202 UP	<0.00221 UP	<0.00204 UP	<0.00209 UP	<0.00178 UP	<0.00179 U	<0.00172 U	<0.00198 UP	<0.00177 UP	<0.00249 UP	<0.00265 UP	<0.00209 UP	<0.00223 UP	<0.00236 UP	<0.00186 UP
Beta Endosulfan	33213-65-9	4.3	44	35	mg/kg	<0.00198 U	<0.00213 UP	<0.00202 UP	<0.00221 UP	<0.00204 UP	<0.00209 UP	<0.00178 UP	<0.00179 U	<0.00172 U	<0.00198 UP	<0.00177 UP	<0.00249 UP	<0.00265 UP	<0.00209 UP	<0.00223 UP	<0.00236 UP	<0.00186 UP
Delta Bhc (Delta Hexachlorocyclohexane)	319-86-8	0.04	0.1	100	mg/kg	<0.00198 U	<0.00213 UP	<0.00202 UP	<0.00221 UP	<0.00204 UP	<0.00209 UP	<0.00178 UP	<0.00179 U	<0.00172 U	<0.00198 UP	<0.00177 UP	<0.00249 UP	<0.00265 UP	<0.00209 UP	<0.00223 UP	<0.00236 UP	<0.00186 UP
Dieldrin	60-57-1	**0.005**	0.1	0.075	mg/kg	<0.00198 U	<0.00213 UP	<0.00202 UP	<0.00221 UP	<0.00204 UP	<0.00209 UP	<0.00178 UP	<0.00179 U	<0.00172 U	<0.00198 UP	<0.00177 UP	<0.00249 UP	<0.00265 UP	<0.00209 UP	<0.00223 UP	<0.00236 UP	<0.00186 U
Endosulfan Sulfate	1031-07-8	4.3	47	35	mg/kg	<0.00198 U	<0.00213 UP	<0.00202 UP	<0.00221 UP	<0.00204 UP	<0.00209 UP	<0.00178 UP	<0.00179 U	<0.00172 U	<0.00198 UP	<0.00177 UP	<0.00249 UP	<0.00265 UP	<0.00209 UP	<0.00223 UP	<0.00236 UP	<0.00186 UP
Endrin	72-20-8	0.014	0.06	5.3	mg/kg	<0.00198 U	<0.00213 UP	<0.00202 UP	<0.00221 UP	<0.00204 UP	<0.00209 UP	<0.00178 UP	<0.00179 U	<0.00172 U	<0.00198 UP	<0.00177 UP	<0.00249 UP	<0.00265 UP	<0.00209 UP	<0.00223 UP	<0.00236 UP	<0.00186 UP
Endrin Aldehyde	7421-93-4	NS	NS	NS	mg/kg	<0.00198 U	<0.00213 UP	<0.00202 UP	<0.00221 UP	<0.00204 UP	<0.00209 UP	<0.00178 UP	<0.00179 U	<0.00172 U	<0.00198 UP	<0.00177 UP	<0.00249 UP	<0.00265 UP	<0.00209 UP	<0.00223 UP	<0.00236 UP	<0.00186 UP
Endrin Ketone	53494-70-5	NS	NS	NS	mg/kg	<0.00198 U	<0.00213 UP	<0.00202 UP	<0.00221 UP	<0.00204 UP	<0.00209 UP	<0.00178 UP	<0.00179 U	<0.00172 U	<0.00198 UP	<0.00177 UP	<0.00249 UP	<0.00265 UP	<0.00209 UP	<0.00223 UP	<0.00236 UP	<0.00186 UP
Gamma Bhc (Lindane)	58-89-9	0.025	0.05	0.21	mg/kg	<0.00198 U	<0.00213 UP	<0.00202 UP	<0.00221 UP	<0.00204 UP	<0.00209 UP	<0.00178 UP	<0.00179 U	<0.00172 U	<0.00198 UP	<0.00177 UP	<0.00249 UP	<0.00265 UP	<0.00209 UP	<0.00223 UP	<0.00236 UP	<0.00186 UP
Gamma-Chlordane	5566-34-7	NS	NS	NS	mg/kg	<0.00198 U	<0.00213 UP	<0.00202 UP	<0.00221 UP	<0.00204 UP	<0.00209 UP	<0.00178 UP	<0.00179 U	<0.00172 U	<0.00198 UP	<0.00177 UP	<0.00249 UP	<0.00265 UP	<0.00209 UP	<0.00223 UP	<0.00236 UP	0.00599 J
Heptachlor	76-44-8	0.013	0.38	0.53	mg/kg	<0.00198 U	<0.00213 UP	<0.00202 UP	<0.00221 UP	<0.00204 UP	<0.00209 UP	<0.00178 UP	<0.00179 U	<0.00172 U	<0.00198 UP	<0.00177 UP	<0.00249 UP	<0.00265 UP	<0.00209 UP	<0.00223 UP	<0.00236 UP	<0.00186 UP
Heptachlor Epoxide	1024-57-3	NS	NS	NS	mg/kg	<0.00198 U	<0.00213 UP	<0.00202 UP	<0.00221 UP	<0.00204 UP	<0.00209 UP	<0.00178 UP	<0.00179 U	<0.00172 U	<0.00198 UP	<0.00177 UP	<0.00249 UP	<0.00265 UP	<0.00209 UP	<0.00223 UP	<0.00236 UP	<0.00186 UP
Methoxychlor	72-43-5	NS	NS	NS	mg/kg	<0.00198 U	<0.00213 UP	<0.00202 UP	<0.00221 UP	<0.00204 UP	<0.00209 UP	<0.00178 UP	<0.00179 U	<0.00172 U	<0.00198 UP	<0.00177 UP	<0.00249 UP	<0.00265 UP	<0.00209 UP	<0.00223 UP	<0.00236 UP	<0.00186 UP
Toxaphene	8001-35-2	NS	NS	NS	mg/kg	<0.198 U	<0.213 UP	<0.202 UP	<0.221 UP	<0.204 UP	<0.209 UP	<0.178 UP	<0.179 U	<0.172 U	<0.198 UP	<0.177 UP	<0.249 UP	<0.265 UP	<0.209 UP	<0.223 UP	<0.236 UP	<0.186 UP
Herbicides																						
2,4,5-T (Trichlorophenoxyacetic Acid)	93-76-5	NS	NS	NS	mg/kg	<0.0238 U	<0.0259 UP	<0.0246 UP	<0.0265 UP	<0.0248 UP	<0.025 UP	<0.0215 UP	<0.0219 U	<0.0211 U	<0.0243 UP	<0.0214 UP	<0.0302 UP	<0.0321 UP	<0.0255 UP	<0.0271 UP	<0.0287 UP	<0.0219 UP
2,4-D (Dichlorophenoxyacetic Acid)	94-75-7	NS	NS	NS	mg/kg	<0.0238 U	<0.0259 UP	<0.0246 UP	<0.0265 UP	<0.0248 UP	<0.025 UP	<0.0215 UP	<0.0219 U	<0.0211 U	<0.0243 UP	<0.0214 UP	<0.0302 UP	<0.0321 UP	<0.0255 UP	<0.0271 UP	<0.0287 UP	<0.0219 UP
2,4-Dichlorophenoxybutyric acid	94-82-6	NS	NS	NS	mg/kg	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	<0.0219 UP
Dalapon	75-99-0	NS	NS	NS	mg/kg	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	<0.0219 UP
Dicamba	1918-00-9	NS	NS	NS	mg/kg	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	<0.0219 UP
Silvex (2,4,5-Tp)	93-72-1	3.8	3.8	100	mg/kg	<0.0238 U	<0.0259 UP	<0.0246 UP	<0.0265 UP	<0.0248 UP	<0.025 UP	<0.0215 UP	<0.0219 U	<0.0211 U	<0.0243 UP	<0.0214 UP	<0.0302 UP	<0.0321 UP	<0.0255 UP	<0.0271 UP	<0.0287 UP	<0.0219 UP
Polychlorinated Biphenyl																						
PCB-1016 (Aroclor 1016)	12674-11-2	NS	NS	NS	mg/kg	<0.02 U	<0.0215 UP	<0.0206 UP	<0.0223 UP	<0.0206 UP	<0.0211 UP	<0.0179 UP	<0.0181 U	<0.0174 U	<0.02 UP	<0.0179 UP	<0.0251 UP	<0.0267 UP	<0.0211 UP	<0.0225 UP	<0.0238 UP	<0.0188 UP
PCB-1221 (Aroclor 1221)	11104-28-2	NS	NS	NS	mg/kg	<0.02 U	<0.0215 UP	<0.0206 UP	<0.0223 UP	<0.0206 UP	<0.0211 UP	<0.0179 UP	<0.0181 U	<0.0174 U	<0.02 UP	<0.0179 UP	<0.0251 UP	<0.0267 UP	<0.0211 UP	<0.0225 UP	<0.0238 UP	<0.0188 UP
PCB-1232 (Aroclor 1232)	11141-16-5	NS	NS	NS	mg/kg	<0.02 U	<0.0215 UP	<0.0206 UP	<0.0223 UP	<0.0206 UP	<0.0211 UP	<0.0179 UP	<0.0181 U	<0.0174 U	<0.02 UP	<0.0179 UP	<0.0251 UP	<0.0267 UP	<0.0211 UP	<0.0225 UP	<0.0238 UP	<0.0188 UP
PCB-1242 (Aroclor 1242)	53469-21-9	NS	NS	NS	mg/kg	<0.02 U	<0.0215 UP	<0.0206 UP	<0.0223 UP	<0.0206 UP	<0.0211 UP	<0.0179 UP	<0.0181 U	<0.0174 U	<0.02 UP	<0.0179 UP	<0.0251 UP	<0.0267 UP	<0.0211 UP	<0.0225 UP	<0.0238 UP	0.215 P
PCB-1248 (Aroclor 1248)	12672-29-6	NS	NS	NS	mg/kg	<0.02 U	<0.0215 UP	<0.0206 UP	<0.0223 UP	<0.0206 UP	<0.0211 UP	<0.0179 UP	<0.0181 U	<0.0174 U	<0.02 UP	<0.0179 UP	<0.0251 UP	<0.0267 UP	<0.0211 UP	<0.0225 UP	<0.0238 UP	<0.0188 UP
PCB-1254 (Aroclor 1254)	11097-69-1	NS	NS	NS	mg/kg	<0.02 U	<0.0215 UP	<0.0206 UP	<0.0223 UP	<0.0206 UP	<0.0211 UP	<0.0179 UP	<0.0181 U	<0.0174 U	<0.02 UP	<0.0179 UP	<0.0251 UJ	0.209 J	<0.0211 UP	<0.0225 UP	<0.0238 UP	<0.0188 UP
PCB-1260 (Aroclor 1260)	11096-82-5	NS	NS	NS	mg/kg	<0.02 U	<0.0215 UP	<0.0206 UP	<0.0223 UP	<0.0206 UP	<0.0211 UP	<0.0179 UP	<0.0181 U	<0.0174 U	0.0282 P	<0.0179 UP	<0.0251 UJ	0.11 J	<0.0211 UP	<0.0225 UP	<0.0238 UP	0.0376 P
PCB-1262 (Aroclor 1262)	37324-23-5	NS	NS	NS	mg/kg	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
PCB-1268 (Aroclor 1268)	11100-14-4	NS	NS	NS	mg/kg	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
Total PCBs	1336-36-3	**0.1**	3.2	1	mg/kg	<0.02 U	<0.0215 UP	<0.0206 UP	<0.0223 UP	<0.0206 UP	<0.0211 UP	<0.0179 UP	<0.0181 U	<0.0174 U	0.0282 P	<0.0179 UP	<0.0251 UJ	**0.319 J**	<0.0211 UP	<0.0225 UP	<0.0238 UP	**0.253 P**
Metals																						
Aluminum	7429-90-5	NS	NS	NS	mg/kg	4,750	5,400	2,970 J	6,190	5,380 J	4,390	6,170	9,230	4,290	5,820	5,620	4,620	4,790	5,170	3,870	6,130	6,650 B
Antimony	7440-36-0	NS	NS	NS	mg/kg	<2.51 U	<2.74 U	<2.61 UJ	<2.84 U	<2.62 U	<2.69 U	<2.28 U	<2.31 U	<2.22 U	<2.54 UJ	<2.26 U	<3.15 U	<3.37 UJ	<2.66 U	<2.83 U	<2.99 U	<2.35 U
Arsenic	7440-38-2	**13**	16	16	mg/kg	1.7	**24.7**	**16 J**	7.38	8.62	7.35	2.34	3.35	1.63	9.83	1.37	11	11.2 J	10.5	11.8	**18.1**	6.68
Barium	7440-39-3	**410**	820	410	mg/kg	97.8	**452**	**447 J**	**711**	**413**	239	20	139	57.2	**491 J**	278	**813**	**615 J**	**448**	**417**	**620**	**537**
Beryllium	7440-41-7	4.4	47	43	mg/kg	0.19	0.48	0.295	0.547	0.564 J	0.51	0.13	0.195	0.128	0.403 J	0.151	0.463	0.424	0.567	0.374	0.611	0.416
Cadmium	7440-43-9	**2.5**	7.5	2.5	mg/kg	0.331	0.964	0.626 J	0.511	0.944	0.473	<0.273 U	<0.277 U	0.355	2.34	0.271	1.1	1.85	1.06	1.58	0.897	1.75
Calcium	7440-70-2	NS	NS	NS	mg/kg	2,420	4,160	3,360 J	2,400	3,210 J	4,750	1,570	1,830	1,620	6,150	953	6,140	6,510	3,980	2,850	20,900	38,600
Chromium, Hexavalent	18540-29-9	1	19	1	mg/kg	<0.601 U	<0.657 U	<0.626 U	<0.682 U	<0.629 U	<0.645 U	<0.547 U	<0.554 U	<0.532 UJ	<0.609 UJ	<0.541 U	<0.756 U	<0.81 U	<0.639 U	<0.678 U	<0.718 U	<0.565 U
Chromium, Total	7440-47-3	NS	NS	NS	mg/kg	13.8	19.8	20.1	14.3	14.4	11.2	12	17.4	8.56	25.6 J	12.5	19.7	19.5	21.5	16.3	21.2	32.3
Chromium, Trivalent	16065-83-1	**30**	19	110	mg/kg	13.8	19.8	16	14.3	14.4	11.2	12	17.4	8.56	25.6	12.5	19.7	19.5	21.5	16.3	21.2	**32.3**
Cobalt	7440-48-4	NS	NS	NS	mg/kg	4.29	8.03	4.82 J	7.21	6.7	5.58	4.52	4.84	3.42	7.82	3.1	5.82	7.87	7.03	5.83	10.6	7.36
Copper	7440-50-8	**50**	1720	280	mg/kg	32.1	**57.3**	41.9 J	48.2	49.2	43.5	12.7	16.3	19.1	**316 J**	11.8	**162**	**98.9 J**	**81.9**	**97.5**	**64.7**	**119**
Cyanide	57-12-5	**2.3**	40	13	mg/kg	<0.601 U	<0.657 U	0.984	<0.682 U	<0.629 UJ	<0.645 U	<0.547 U	<0.554 U	<0.532 U	<0.609 U	<0.541 U	**13.7 J**	**2.47 J**	<0.639 U	<0.678 U	<0.718 U	0.922
Iron	7439-89-6	NS	NS	NS	mg/kg	11,000	51,000	27,200 J	7,480	11,000 J	15,000	10,300	16,300	9,110	33,100	6,750	30,300	37,000 J	16,700	27,400	60,400	22,300
Lead	7439-92-1	**63**	450	400	mg/kg	**81**	**295**	**237 J**	**255**	**561 J**	**222**	**287**	**121**	61.2	**348**	28.4	**1,090**	**720**	**366**	**1,140**	**379**	**1,040**
Magnesium	7439-95-4	NS	NS	NS	mg/kg	2,260	710	254 J	536	552 J	326	2,660	1,930	1,820	1,440	1,740	492	810	711	500	1,550	4,640
Manganese	7439-96-5	**1600**	2000	2000	mg/kg	314	269	171 J	59.9	75.1	86.4	128	200	152	235	49.7	184	183 J	143	111	410	279
Mercury	7439-97-6	**0.18**	0.73	0.3	mg/kg	0.0487	**0.668**	0.149	**0.192**	0.14	0.0931	<0.0328 U	0.0954	0.0806	**0.71**	<0.0325 U	**0.817 J**	**0.451 J**	**0.231**	0.116	**0.243**	**0.68**
Nickel	7440-02-0	**30**	130	320	mg/kg	27.5	20.5	9.71 J	18.1	16.7	13	17.6	13.8	13.6	25.3 J	13	23.4	19.7	17.6	13	22.2	29.8
Potassium	7440-09-7	NS	NS	NS	mg/kg	536	477	293 J	1,030 B	642 J	465 B	718	574	471	650	576	451	704 J	550	462	588	1,290
Selenium	7782-49-2	**3.9**	4	110	mg/kg	<2.51 U	<2.74 U	<2.61 U	<2.84 U	<2.62 U	<2.69 U	<2.28 U	<2.31 U	<2.22 U	<2.54 U	<2.26 U	<3.15 U	<3.37 U	<2.66 U	<2.83 U	<2.99 U	<2.35 U
Silver	7440-22-4	**2**	8.3	110	mg/kg	<0.505 U	<0.552 U	<0.525 U	0.58	<0.528 U	0.849	<0.459 U	<0.465 U	<0.447 U	1.54	<0.455 U	0.895	1.34 J	0.937	1.15	<0.603 U	<0.475 U
Sodium	7440-23-5	NS	NS	NS	mg/kg	143	297	203 J	351	274	234	88	114	80.8	345	73.9	304	294 J	323	288	457	<255 U
Thallium	7440-28-0	NS	NS	NS	mg/kg	<2.01 U	<2.19 U	<2.09 U	<2.28 U	<2.1 U	<2.15 U	<1.83 U	<1.85 U	<1.78 U	<2.03 U	<1.81 U	<2.53 U	<2.71 U	<2.13 U	<2.27 U	<2.4 U	<1.89 U
Vanadium	7440-62-2	NS	NS	NS	mg/kg	11.8	19.1	17.1	25.3	26	18.3	14.9	32.6	11.1	24.1	11.9	25.2	23.5	21.2	20.4	25.9	24.6
Zinc	7440-66-6	**109**	2480	6600	mg/kg	**171**	**231**	**324 J**	**162**	**258 J**	**127**	38.3	88.4	82.3	**634**	105	**376**	**569**	**542**	**474**	**472**	**587**

Table 2
Site Management Plan
Soil Sample Analytical Results

12074 Flatlands Avenue p/o Lot 1 Site
Brooklyn, New York
BCP Site No. C224353
Langan Project No.: 100688803

Analyte	CAS Number	NYSDEC Part 375 Unrestricted Use SCOs	NYSDEC Part 375 Protection of Groundwater SCOs	NYSDEC Part 375 Restricted Use Restricted-Residential SCOs	Location	PE34	PE35	PE36	PE37	PE38	PE39	PE40	PE41	PE42	PE43	PE44	PE45	PE45	PE46	PE47	PE48	PE50
					Sample Name	PE34_20	PE35_18.5	PE36_18.5	PE37_19	PE38_20	PE39_18.5	PE40_18.5	PE41_20	PE42_20	PE43_19	PE44_19.5	PE45_19.5	DUP_08262025	PE46_19.5	PE47_19.5	PE48_19	PE50_19.5
					Sample Date	06/19/2025	08/11/2025	07/29/2025	07/24/2025	08/11/2025	07/24/2025	07/23/2025	06/19/2025	06/19/2025	09/02/2025	08/28/2025	08/26/2025	08/26/2025	08/26/2025	08/27/2025	08/27/2025	09/17/2025
					Sample Elevation	20	18.5	18.5	19	20	18.5	18.5	20	20	19	19.5	19.5	19.5	19.5	19.5	19	19.5
					Unit	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result
Per- and Polyfluoroalkyl Substances																						
11-Chloroeicosafluoro-3-Oxaundecane-1-Sulfonic Acid (11Cl-PF3OUdS)	763051-92-9	NS	NS	NS	mg/kg	<0.000909 U	<0.000991 U	<0.000942 U	<0.00103 U	<0.000949 U	<0.000973 U	<0.000825 UJ	<0.000837 U	<0.0008 U	<0.000921 U	<0.000817 UJ	<0.00114 UJ	<0.00122 UJ	<0.000966 U	<0.00103 U	<0.00108 UJ	<0.000855 U
1H,1H,2H,2H-Perfluorodecane Sulfonic Acid (8:2 FTS)	39108-34-4	NS	NS	NS	mg/kg	<0.000924 U	<0.00101 U	<0.000957 U	<0.00105 U	<0.000964 U	<0.000988 U	<0.000838 U	<0.000851 U	<0.000812 U	<0.000935 U	<0.00083 U	<0.00116 UJ	<0.00124 UJ	<0.000981 U	<0.00104 UJ	<0.0011 UJ	<0.000868 U
1H,1H,2H,2H-Perfluorohexane Sulfonic Acid (4:2 FTS)	757124-72-4	NS	NS	NS	mg/kg	<0.000902 U	<0.000984 U	<0.000935 U	<0.00102 U	<0.000942 U	<0.000965 U	<0.000819 U	<0.000831 U	<0.000793 U	<0.000914 U	<0.000811 U	<0.00113 UJ	<0.00121 UJ	<0.000958 U	<0.00102 UJ	<0.00107 UJ	<0.000848 U
1H,1H,2H,2H-Perfluorooctane Sulfonic Acid (6:2 FTS)	27619-97-2	NS	NS	NS	mg/kg	<0.000914 U	0.000312 J	<0.000947 U	<0.00103 U	<0.000954 U	<0.000978 U	<0.00083 U	<0.000842 U	<0.000804 U	<0.000926 U	<0.000821 U	<0.00115 UJ	<0.00123 UJ	<0.000971 U	<0.00103 UJ	<0.00109 UJ	<0.000859 U
2H,2H,3H,3H-Perfluorooctanoic Acid (5:3 FTCA)	914637-49-3	NS	NS	NS	mg/kg	<0.00601 U	<0.00656 U	0.00131 J	<0.00681 U	<0.00628 U	<0.00643 U	<0.00546 U	<0.00554 U	<0.00529 U	<0.00609 U	<0.0054 U	<0.00753 UJ	<0.00808 UJ	<0.00639 U	<0.0068 UJ	<0.00715 UJ	<0.00565 U
3-Perfluoroheptyl Propanoic Acid (7:3 FTCA)	812-70-4	NS	NS	NS	mg/kg	<0.00601 U	<0.00656 U	0.00144 J	<0.00681 U	<0.00628 U	<0.00643 U	<0.00546 U	<0.00554 U	<0.00529 U	<0.00609 U	<0.0054 U	<0.00753 UJ	<0.00808 UJ	<0.00639 U	<0.0068 UJ	<0.00715 UJ	<0.00565 U
3-Perfluoropropyl Propanoic Acid (3:3 FTCA)	356-02-5	NS	NS	NS	mg/kg	<0.0012 UJ	<0.00131 U	<0.00125 U	<0.00136 U	<0.00126 U	<0.00129 U	<0.00109 U	<0.00111 UJ	<0.00106 UJ	<0.00122 U	<0.00108 U	<0.00151 UJ	<0.00162 UJ	<0.00128 U	<0.00136 UJ	<0.00143 UJ	<0.00113 U
4,8-Dioxa-3H-perfluorononanoic Acid (ADONA)	919005-14-4	NS	NS	NS	mg/kg	<0.000909 U	<0.000991 U	<0.000942 U	<0.00103 U	<0.000949 U	<0.000973 U	<0.000825 U	<0.000837 U	<0.0008 U	<0.000921 U	<0.000817 UJ	<0.00114 UJ	<0.00122 UJ	<0.000966 U	<0.00103 UJ	<0.00108 UJ	<0.000855 U
9-Chlorohexadecafluoro-3-Oxanonane-1-Sulfonic Acid (9Cl-PF3ONS)	756426-58-1	NS	NS	NS	mg/kg	<0.0009 U	<0.000981 UJ	<0.000932 U	<0.00102 UJ	<0.000939 UJ	<0.000962 UJ	<0.000817 UJ	<0.000828 U	<0.000791 U	<0.000911 UJ	<0.000808 UJ	<0.00113 UJ	<0.00121 UJ	<0.000956 UJ	<0.00102 UJ	<0.00107 UJ	<0.000846 UJ
Hexafluoropropylene Oxide Dimer Acid (HFPO-DA)	13252-13-6	NS	NS	NS	mg/kg	<0.000962 U	<0.00105 U	<0.000997 U	<0.00109 UJ	<0.001 U	0.000342 J	<0.000873 U	<0.000886 U	<0.000846 U	<0.000974 UJ	<0.000865 UJ	<0.00121 UJ	<0.00129 UJ	<0.00102 UJ	<0.00109 UJ	<0.00114 UJ	<0.000904 U
N-ethyl Perfluorooctanesulfonamide (NEtFOSA)	4151-50-2	NS	NS	NS	mg/kg	<0.000241 U	<0.000262 U	<0.000249 U	<0.000272 U	<0.000251 U	<0.000257 U	<0.000218 U	<0.000221 U	<0.000212 U	<0.000244 U	<0.000216 U	<0.000301 UJ	<0.000323 UJ	<0.000256 U	<0.000272 UJ	<0.000286 UJ	<0.000226 U
N-ethyl Perfluorooctanesulfonamidoacetic Acid (NEtFOSAA)	2991-50-6	NS	NS	NS	mg/kg	0.000242	<0.000262 U	<0.000249 U	<0.000272 U	<0.000251 U	<0.000257 U	<0.000218 U	0.000624	<0.000212 U	<0.000609 UJ	<0.0054 UJ	<0.000753 UJ	<0.000808 UJ	<0.000639 U	<0.00068 UJ	<0.000715 UJ	0.00643
N-ethyl Perfluorooctanesulfonamidoethanol (NEtFOSE)	1691-99-2	NS	NS	NS	mg/kg	<0.00241 U	<0.00262 U	<0.00249 U	<0.00272 U	<0.00251 U	<0.00257 U	<0.00218 U	<0.00221 U	<0.00212 U	<0.00244 U	<0.00216 U	<0.00301 UJ	<0.00323 UJ	<0.00256 U	<0.00272 UJ	<0.00286 UJ	0.00108 J
N-methyl Perfluorooctanesulfonamide (NMeFOSA)	31506-32-8	NS	NS	NS	mg/kg	<0.000241 U	<0.000262 U	<0.000249 U	<0.000272 U	<0.000251 U	<0.000257 U	<0.000218 U	<0.000221 U	<0.000212 U	<0.000244 U	<0.000216 U	<0.000301 UJ	<0.000323 UJ	<0.000256 U	<0.000272 UJ	<0.000286 UJ	<0.000226 U
N-methyl Perfluorooctanesulfonamidoacetic Acid (NMeFOSAA)	2355-31-9	NS	NS	NS	mg/kg	<0.000241 U	<0.000262 U	<0.000249 U	<0.000272 U	<0.000251 U	<0.000257 U	<0.000218 U	<0.000221 U	<0.000212 U	<0.000244 U	<0.000216 U	<0.000301 UJ	<0.000323 UJ	<0.000256 U	<0.000272 UJ	<0.000286 UJ	0.00106
N-methyl Perfluorooctanesulfonamidoethanol (NMeFOSE)	24448-09-7	NS	NS	NS	mg/kg	<0.00241 U	<0.00262 U	<0.00249 U	<0.00272 U	<0.00251 U	<0.00257 U	<0.00218 U	<0.00221 U	<0.00212 U	<0.00244 U	<0.00216 U	<0.00301 UJ	<0.00323 UJ	<0.00256 U	<0.00272 UJ	<0.00286 UJ	<0.00226 U
Nonafluoro-3,6-dioxaheptanoic Acid (NFDHA)	151772-58-6	NS	NS	NS	mg/kg	<0.000481 U	<0.000525 U	<0.000498 U	<0.000544 U	<0.000502 U	<0.000515 U	<0.000437 U	<0.000443 U	<0.000423 U	<0.000487 U	<0.000432 UJ	<0.000603 UJ	<0.000647 UJ	<0.000511 UJ	<0.000544 UJ	<0.000572 UJ	<0.000452 UJ
Perfluoro(2-ethoxyethane)sulfonic Acid (PFEESA)	113507-82-7	NS	NS	NS	mg/kg	<0.000428 U	<0.000467 UJ	<0.000444 U	<0.000485 U	<0.000447 UJ	<0.000458 U	<0.000389 U	<0.000394 U	<0.000377 U	<0.000434 U	<0.000385 U	<0.000536 UJ	<0.000576 UJ	<0.000455 U	<0.000484 UJ	<0.000509 UJ	<0.000402 U
Perfluoro-3-methoxypropanoic Acid (PFMPA)	377-73-1	NS	NS	NS	mg/kg	<0.000481 UJ	<0.000525 U	<0.000498 U	<0.000544 U	<0.000502 U	<0.000515 U	<0.000437 U	<0.000443 UJ	<0.000423 UJ	<0.000487 U	<0.000432 U	<0.000603 UJ	<0.000647 UJ	<0.000511 U	<0.000544 UJ	<0.000572 UJ	<0.000452 U
Perfluoro-4-methoxybutanoic Acid (PFMBA)	863090-89-5	NS	NS	NS	mg/kg	<0.000481 UJ	<0.000525 U	0.000175 J	<0.000544 U	<0.000502 U	<0.000515 U	<0.000437 U	<0.000443 UJ	<0.000423 UJ	<0.000487 U	<0.000432 U	<0.000603 UJ	<0.000647 UJ	<0.000511 U	<0.000544 UJ	<0.000572 UJ	<0.000452 U
Perfluorobutanesulfonic Acid (PFBS)	375-73-5	NS	NS	NS	mg/kg	<0.000213 U	<0.000232 U	0.0000995 J	<0.000241 U	<0.000222 U	<0.000228 U	<0.000193 U	<0.000196 U	<0.000187 U	<0.000216 U	<0.000191 U	<0.000267 UJ	<0.000286 UJ	<0.000226 U	<0.000241 UJ	<0.000253 UJ	<0.0002 U
Perfluorobutanoic Acid (PFBA)	375-22-4	NS	NS	NS	mg/kg	<0.000962 U	<0.00105 U	<0.000997 U	<0.00109 U	<0.001 U	<0.00103 U	<0.000873 U	<0.000886 U	<0.000846 U	<0.000974 U	<0.000865 U	<0.00121 UJ	<0.00129 UJ	<0.00102 U	<0.00109 UJ	<0.00114 UJ	<0.000904 U
Perfluorodecanesulfonic Acid (PFDS)	335-77-3	NS	NS	NS	mg/kg	<0.000232 U	<0.000253 U	<0.000241 U	<0.000263 U	<0.000242 U	<0.000248 U	<0.000211 U	<0.000214 U	<0.000204 U	<0.000235 U	<0.000209 U	<0.000291 UJ	<0.000312 UJ	<0.000247 U	<0.000262 UJ	<0.000276 UJ	<0.000218 U
Perfluorodecanoic Acid (PFDA)	335-76-2	NS	NS	NS	mg/kg	<0.000241 U	<0.000262 U	<0.000249 U	<0.000272 U	<0.000251 U	<0.000257 U	<0.000218 U	<0.000221 U	<0.000212 U	<0.000244 U	<0.000216 U	<0.000301 UJ	<0.000323 UJ	<0.000256 U	<0.000272 UJ	<0.000286 UJ	<0.000226 U
Perfluorododecanesulfonic Acid (PFDoS)	79780-39-5	NS	NS	NS	mg/kg	<0.000233 U	<0.000254 U	<0.000242 U	<0.000264 U	<0.000244 U	<0.00025 U	<0.000212 U	<0.000215 U	<0.000205 U	<0.000236 U	<0.00021 U	<0.000292 UJ	<0.000314 UJ	<0.000248 U	<0.000264 UJ	<0.000277 UJ	<0.000219 U
Perfluorododecanoic Acid (PFDoA)	307-55-1	NS	NS	NS	mg/kg	<0.000241 U	<0.000262 U	<0.000249 U	<0.000272 U	<0.000251 U	<0.000257 U	<0.000218 U	<0.000221 U	<0.000212 U	<0.000244 U	<0.000216 U	<0.000301 UJ	<0.000323 UJ	<0.000256 U	<0.000272 UJ	<0.000286 UJ	<0.000226 U
Perfluoroheptanesulfonic Acid (PFHpS)	375-92-8	NS	NS	NS	mg/kg	<0.000241 U	<0.000262 U	<0.000249 U	<0.000272 U	<0.000251 U	<0.000257 U	<0.000218 U	<0.000221 U	<0.000212 U	<0.000244 U	<0.000216 U	<0.000301 UJ	<0.000323 UJ	<0.000256 U	<0.000272 UJ	<0.000286 UJ	<0.000226 U
Perfluoroheptanoic Acid (PFHpA)	375-85-9	NS	NS	NS	mg/kg	<0.000241 U	<0.000262 U	<0.000249 U	<0.000272 U	<0.000251 U	<0.000257 U	<0.000218 U	<0.000221 U	<0.000212 U	<0.000244 U	<0.000216 U	<0.000301 UJ	<0.000323 UJ	<0.000256 U	<0.000272 UJ	<0.000286 UJ	<0.000226 U
Perfluorohexanesulfonic Acid (PFHxS)	355-46-4	NS	NS	NS	mg/kg	<0.00022 U	<0.00024 U	<0.000228 U	<0.000249 U	<0.00023 U	<0.000235 U	<0.0002 U	<0.000203 U	<0.000194 U	<0.000223 U	<0.000198 U	<0.000276 UJ	<0.000296 UJ	<0.000234 U	<0.000249 UJ	<0.000262 UJ	0.000228
Perfluorohexanoic Acid (PFHxA)	307-24-4	NS	NS	NS	mg/kg	<0.000241 U	0.0000679 J	<0.000249 U	<0.000272 U	<0.000251 U	<0.000257 U	<0.000218 U	<0.000221 U	<0.000212 U	<0.000244 U	<0.000216 U	<0.000301 UJ	<0.000323 UJ	<0.000256 U	<0.000272 UJ	<0.000286 UJ	<0.000226 U
Perfluorononanesulfonic Acid (PFNS)	68259-12-1	NS	NS	NS	mg/kg	<0.000231 U	<0.000252 U	<0.000239 U	<0.000261 U	<0.000241 U	<0.000247 U	<0.00021 U	<0.000213 U	<0.000203 U	<0.000234 UJ	<0.000207 UJ	<0.000289 UJ	<0.00031 UJ	<0.000245 U	<0.000261 UJ	<0.000274 UJ	<0.000217 U
Perfluorononanoic Acid (PFNA)	375-95-1	NS	NS	NS	mg/kg	<0.000241 U	<0.000262 U	<0.000249 U	<0.000272 U	<0.000251 U	<0.000257 U	<0.000218 U	<0.000221 U	<0.000212 U	<0.000244 U	<0.000216 U	<0.000301 UJ	<0.000323 UJ	<0.000256 U	<0.000272 UJ	<0.000286 UJ	<0.000226 U
Perfluorooctanesulfonamide (PFOSA)	754-91-6	NS	NS	NS	mg/kg	<0.000241 U	<0.000262 U	0.0000435 J	<0.000272 UJ	<0.000251 U	<0.000257 UJ	<0.000218 U	<0.000221 U	<0.000212 U	<0.000244 U	<0.000216 UJ	<0.000301 UJ	<0.000323 UJ	<0.000256 U	<0.000272 UJ	<0.000286 UJ	0.000523
Perfluorooctanesulfonic Acid (PFOS)	1763-23-1	**0.00088**	0.001	0.044	mg/kg	0.000642	<0.000244 U	0.000343	<0.000253 U	<0.000234 U	<0.000239 U	<0.000203 U	0.000437	0.000554	0.000292	<0.000201 U	<0.00028 UJ	<0.000301 UJ	<0.000238 U	<0.000253 UJ	<0.000266 UJ	**0.00297**
Perfluorooctanoic Acid (PFOA)	335-67-1	**0.00066**	0.0008	0.033	mg/kg	<0.000241 U	0.000383	0.000232 J	0.000131 J	0.000152 J	0.000202 J	<0.000218 U	<0.000221 U	<0.000212 U	0.000188 J	<0.000216 U	0.000312 J	0.000298 J	0.000316	0.000322 J	0.000226 J	0.00029
Perfluoropentanesulfonic Acid (PFPeS)	2706-91-4	NS	NS	NS	mg/kg	<0.000226 U	<0.000247 U	<0.000234 U	<0.000256 U	<0.000236 U	<0.000242 U	<0.000205 U	<0.000208 U	<0.000199 U	<0.000229 U	<0.000203 U	<0.000283 UJ	<0.000304 UJ	<0.00024 U	<0.000256 UJ	<0.000269 UJ	<0.000213 U
Perfluoropentanoic Acid (PFPeA)	2706-90-3	NS	NS	NS	mg/kg	<0.000481 U	<0.000525 U	<0.000498 U	<0.000544 U	<0.000502 U	<0.000515 U	<0.000437 U	<0.000443 U	<0.000423 U	<0.000487 U	<0.000432 U	<0.000603 UJ	<0.000647 UJ	<0.000511 U	<0.000544 UJ	<0.000572 UJ	0.0000931 J
Perfluorotetradecanoic Acid (PFTeDA)	376-06-7	NS	NS	NS	mg/kg	<0.000241 U	<0.000262 U	<0.000249 U	<0.000272 U	<0.000251 U	<0.000257 U	<0.000218 U	<0.000221 U	<0.000212 U	<0.000244 U	<0.000216 U	<0.000301 UJ	<0.000323 UJ	<0.000256 U	<0.000272 UJ	<0.000286 UJ	<0.000226 U
Perfluorotridecanoic Acid (PFTrDA)	72629-94-8	NS	NS	NS	mg/kg	<0.000241 U	<0.000262 U	<0.000249 U	<0.000272 U	<0.000251 U	<0.000257 U	<0.000218 U	<0.000221 U	<0.000212 U	<0.000244 U	<0.000216 UJ	<0.000301 UJ	<0.000323 UJ	<0.000256 U	<0.000272 UJ	<0.000286 UJ	<0.000226 U
Perfluoroundecanoic Acid (PFUnA)	2058-94-8	NS	NS	NS	mg/kg	<0.000241 U	<0.000262 U	<0.000249 U	<0.000272 U	<0.000251 U	<0.000257 U	<0.000218 U	<0.000221 U	<0.000212 U	<0.000244 U	<0.000216 U	<0.000301 UJ	<0.000323 UJ	<0.000256 U	<0.000272 UJ	<0.000286 UJ	<0.000226 U
General Chemistry																						
Solids, Percent	SOLID	NS	NS	NS	Percent	83.1	76.1	79.9	73.3	79.5	77.6	91.4	90.3	94	82.1	92.3	66.1	61.7	78.3	73.7	69.7	88.5

Table 2
Site Management Plan
Soil Sample Analytical Results

12074 Flatlands Avenue p/o Lot 1 Site
Brooklyn, New York
BCP Site No. C224353
Langan Project No.: 100688803

Analyte	CAS Number	NYSDEC Part 375 Unrestricted Use SCOs	NYSDEC Part 375 Protection of Groundwater SCOs	NYSDEC Part 375 Restricted Use Restricted-Residential SCOs	Location	PE51	PE52	PE53	PE54	PE54	PE55	PE56	PE57	PE58	PE59	PE60	PE61	PE62	PE63	PE64	PE65	PE66
					Sample Name	PE51_19.5	PE52_20	PE53_20	PE54_20	PE54_21	PE55_20	PE56_20	PE57_20	PE58_19.5	PE59_19.5	PE60_29	PE61_20.5	PE62_20.5	PE63_20.5	PE64_20.5	PE65_20	PE66_19.5
					Sample Date	09/17/2025	09/23/2025	09/23/2025	08/27/2025	09/17/2025	08/27/2025	08/27/2025	06/26/2025	09/17/2025	09/17/2025	10/28/2025	09/23/2025	08/28/2025	08/28/2025	08/28/2025	06/26/2025	09/17/2025
					Sample Elevation	19.5	20	20	20	21	20	20	20	19.5	19.5	29	20.5	20.5	20.5	20.5	20	19.5
					Unit	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result
Volatile Organic Compounds																						
1,1,1,2-Tetrachloroethane	630-20-6	NS	NS	NS	mg/kg	NA	NA	NA	<0.0079 U	NA	<0.007 U	<0.0049 U	<0.0085 U	NA	NA	<0.022 U	NA	<0.004 U	<0.0076 U	<0.0055 U	<0.0064 U	NA
1,1,1-Trichloroethane	71-55-6	0.68	0.68	100	mg/kg	<0.026 U	<0.0059 U	<0.007 U	<0.0079 U	<0.026 U	<0.007 U	<0.0049 U	<0.0085 U	<0.0058 U	<0.0055 U	<0.0054 U	<0.0077 U	<0.004 U	<0.0076 U	<0.0055 U	<0.0064 U	<0.0054 U
1,1,2,2-Tetrachloroethane	79-34-5	NS	NS	NS	mg/kg	<0.026 U	<0.0059 U	<0.007 U	<0.0079 U	<0.026 U	<0.007 U	<0.0049 U	<0.0085 U	<0.0058 U	<0.0055 U	<0.0054 U	<0.0077 U	<0.004 U	<0.0076 U	<0.0055 U	<0.0064 U	<0.0054 U
1,1,2-Trichloro-1,2,2-Trifluoroethane	76-13-1	NS	NS	NS	mg/kg	<0.026 U	<0.0059 U	<0.007 U	<0.0079 U	<0.026 U	<0.007 U	<0.0049 U	<0.0085 U	<0.0058 U	<0.0055 U	<0.0054 U	<0.0077 U	<0.004 U	<0.0076 U	<0.0055 U	<0.0064 U	<0.0054 U
1,1,2-Trichloroethane	79-00-5	NS	NS	NS	mg/kg	<0.026 U	<0.0059 U	<0.007 U	<0.0079 U	<0.026 U	<0.007 U	<0.0049 U	<0.0085 U	<0.0058 U	<0.0055 U	<0.0054 U	<0.0077 U	<0.004 U	<0.0076 U	<0.0055 U	<0.0064 U	<0.0054 U
1,1-Dichloroethane	75-34-3	0.27	0.27	47	mg/kg	<0.026 U	<0.0059 U	<0.007 U	<0.0079 UJ	<0.026 U	<0.007 UJ	<0.0049 UJ	<0.0085 U	<0.0058 U	<0.0055 U	<0.0054 U	<0.0077 U	<0.004 U	<0.0076 U	<0.0055 U	<0.0064 U	<0.0054 U
1,1-Dichloroethene	75-35-4	0.24	0.33	0.98	mg/kg	<0.026 U	<0.0059 U	<0.007 U	<0.0079 U	<0.026 U	<0.007 U	<0.0049 U	<0.0085 U	<0.0058 U	<0.0055 U	<0.0054 U	<0.0077 U	<0.004 U	<0.0076 U	<0.0055 U	<0.0064 U	<0.0054 U
1,1-Dichloropropene	563-58-6	NS	NS	NS	mg/kg	NA	NA	NA	<0.0079 U	NA	<0.007 U	<0.0049 U	<0.0085 U	NA	NA	NA	NA	<0.004 U	<0.0076 U	<0.0055 U	<0.0064 U	NA
1,2,3-Trichlorobenzene	87-61-6	NS	NS	NS	mg/kg	<0.026 U	<0.0059 U	<0.007 U	<0.0079 U	<0.026 U	<0.007 U	<0.0049 U	<0.0085 U	<0.0058 U	<0.0055 U	<0.0054 U	<0.0077 U	<0.004 U	<0.0076 U	<0.0055 U	<0.0064 U	<0.0054 U
1,2,3-Trichloropropane	96-18-4	NS	NS	NS	mg/kg	NA	NA	NA	<0.0079 U	NA	<0.007 U	<0.0049 U	<0.0085 U	NA	NA	<0.0054 U	NA	<0.004 U	<0.0076 U	<0.0055 U	<0.0064 U	NA
1,2,4-Trichlorobenzene	120-82-1	NS	NS	NS	mg/kg	<0.026 U	<0.0059 U	<0.007 U	<0.0079 U	<0.026 U	<0.007 U	<0.0049 U	<0.0085 U	<0.0058 U	<0.0055 U	<0.0054 U	<0.0077 U	<0.004 U	<0.0076 U	<0.0055 U	<0.0064 U	<0.0054 U
1,2,4-Trimethylbenzene	95-63-6	5.9	5.9	100	mg/kg	<0.026 U	<0.0059 U	<0.007 U	<0.0079 U	<0.026 U	<0.007 U	<0.0049 U	<0.0085 U	<0.0058 U	<0.0055 U	<0.0054 U	<0.0077 U	<0.004 U	<0.0076 U	<0.0055 U	<0.0064 U	<0.0054 U
1,2-Dibromo-3-Chloropropane	96-12-8	NS	NS	NS	mg/kg	<0.026 U	<0.0059 U	<0.007 U	<0.0079 U	<0.026 U	<0.007 U	<0.0049 U	<0.0085 U	<0.0058 U	<0.0055 U	<0.0054 U	<0.0077 U	<0.004 U	<0.0076 U	<0.0055 U	<0.0064 U	<0.0054 U
1,2-Dibromoethane (Ethylene Dibromide)	106-93-4	NS	NS	NS	mg/kg	<0.026 U	<0.0059 U	<0.007 U	<0.0079 U	<0.026 U	<0.007 U	<0.0049 U	<0.0085 U	<0.0058 U	<0.0055 U	<0.0054 U	<0.0077 U	<0.004 U	<0.0076 U	<0.0055 U	<0.0064 U	<0.0054 U
1,2-Dichlorobenzene	95-50-1	1.1	1.1	100	mg/kg	<0.026 U	<0.0059 U	<0.007 U	<0.0079 U	<0.026 U	<0.007 U	<0.0049 U	<0.0085 U	<0.0058 U	<0.0055 U	<0.0054 U	<0.0077 U	<0.004 U	<0.0076 U	<0.0055 U	<0.0064 U	<0.0054 U
1,2-Dichloroethane	107-06-2	0.02	0.02	5.8	mg/kg	<0.026 U	<0.0059 U	<0.007 U	<0.0079 U	<0.026 U	<0.007 U	<0.0049 U	<0.0085 U	<0.0058 U	<0.0055 U	<0.0054 U	<0.0077 U	<0.004 U	<0.0076 U	<0.0055 U	<0.0064 U	<0.0054 U
1,2-Dichloropropane	78-87-5	NS	NS	NS	mg/kg	<0.026 U	<0.0059 U	<0.007 U	<0.0079 U	<0.026 U	<0.007 U	<0.0049 U	<0.0085 U	<0.0058 U	<0.0055 U	<0.0054 U	<0.0077 U	<0.004 U	<0.0076 U	<0.0055 U	<0.0064 U	<0.0054 U
1,3,5-Trimethylbenzene (Mesitylene)	108-67-8	3.1	3.1	100	mg/kg	<0.026 U	<0.0059 U	<0.007 U	<0.0079 U	<0.026 U	<0.007 U	<0.0049 U	<0.0085 U	<0.0058 U	<0.0055 U	<0.0054 U	<0.0077 U	<0.004 U	<0.0076 U	<0.0055 U	<0.0064 U	<0.0054 U
1,3-Dichlorobenzene	541-73-1	2.6	2.6	38	mg/kg	<0.026 U	<0.0059 U	<0.007 U	<0.0079 U	<0.026 U	<0.007 U	<0.0049 U	<0.0085 U	<0.0058 U	<0.0055 U	<0.0054 U	<0.0077 U	<0.004 U	<0.0076 U	<0.0055 U	<0.0064 U	<0.0054 U
1,3-Dichloropropane	142-28-9	NS	NS	NS	mg/kg	NA	NA	NA	<0.0079 U	NA	<0.007 U	<0.0049 U	<0.0085 U	NA	NA	NA	NA	<0.004 U	<0.0076 U	<0.0055 U	<0.0064 U	NA
1,4-Dichlorobenzene	106-46-7	1.8	1.8	24	mg/kg	<0.026 U	<0.0059 U	<0.007 U	<0.0079 U	<0.026 U	<0.007 U	<0.0049 U	<0.0085 U	<0.0058 U	<0.0055 U	<0.0054 U	<0.0077 U	<0.004 U	<0.0076 U	<0.0055 U	<0.0064 U	<0.0054 U
1,4-Dioxane (P-Dioxane)	123-91-1	0.1	0.1	5.7	mg/kg	<0.39 U	<0.088 U	<0.1 U	NA	<0.39 U	NA	NA	<0.17 U	<0.087 U	<0.082 U	NA	<0.12 U	NA	NA	NA	<0.13 U	<0.08 U
2,2-Dichloropropane	594-20-7	NS	NS	NS	mg/kg	NA	NA	NA	<0.0079 U	NA	<0.007 U	<0.0049 U	<0.0085 U	NA	NA	NA	NA	<0.004 U	<0.0076 U	<0.0055 U	<0.0064 U	NA
2-Chlorotoluene	95-49-8	NS	NS	NS	mg/kg	NA	NA	NA	<0.0079 U	NA	<0.007 U	<0.0049 U	<0.0085 U	NA	NA	NA	NA	<0.004 U	<0.0076 U	<0.0055 U	<0.0064 U	NA
2-Hexanone (MBK)	591-78-6	NS	NS	NS	mg/kg	<0.13 U	<0.029 U	<0.035 U	<0.0079 U	<0.13 U	<0.007 U	<0.0049 U	<0.0085 U	<0.029 U	<0.027 U	<0.027 U	<0.038 U	<0.004 U	<0.0076 U	<0.0055 U	<0.0064 U	<0.027 U
4-Chlorotoluene	106-43-4	NS	NS	NS	mg/kg	NA	NA	NA	<0.0079 U	NA	<0.007 U	<0.0049 U	<0.0085 U	NA	NA	NA	NA	<0.004 U	<0.0076 U	<0.0055 U	<0.0064 U	NA
Acetone	67-64-1	**0.03**	0.03	100	mg/kg	<0.13 U	<0.029 U	<0.035 U	**0.062**	<0.13 U	**0.097**	**0.079**	0.017	<0.029 U	<0.027 U	<0.05 U	<0.038 U	**0.16**	**0.1**	**0.14**	**0.047**	<0.027 U
Acrolein	107-02-8	NS	NS	NS	mg/kg	NA	NA	NA	<0.016 U	NA	<0.014 U	<0.0097 U	<0.017 U	NA	NA	<0.0054 U	NA	<0.0081 U	<0.015 U	<0.011 U	<0.013 U	NA
Acrylonitrile	107-13-1	NS	NS	NS	mg/kg	NA	NA	NA	<0.0079 U	NA	<0.007 U	<0.0049 U	<0.0085 U	NA	NA	<0.022 U	NA	<0.004 U	<0.0076 U	<0.0055 U	<0.0064 U	NA
Benzene	71-43-2	0.06	0.06	3.7	mg/kg	<0.026 U	<0.0059 U	<0.007 U	<0.0079 U	<0.026 U	<0.007 U	<0.0049 U	<0.0085 U	<0.0058 U	<0.0055 U	<0.0054 U	<0.0077 U	<0.004 U	<0.0076 U	<0.0055 U	<0.0064 U	<0.0054 U
Bromobenzene	108-86-1	NS	NS	NS	mg/kg	NA	NA	NA	<0.0079 U	NA	<0.007 U	<0.0049 U	<0.0085 U	NA	NA	NA	NA	<0.004 U	<0.0076 U	<0.0055 U	<0.0064 U	NA
Bromochloromethane	74-97-5	NS	NS	NS	mg/kg	<0.026 U	<0.0059 U	<0.007 U	<0.0079 U	<0.026 U	<0.007 U	<0.0049 U	<0.0085 U	<0.0058 U	<0.0055 U	<0.0054 U	<0.0077 U	<0.004 U	<0.0076 U	<0.0055 U	<0.0064 U	<0.0054 U
Bromodichloromethane	75-27-4	NS	NS	NS	mg/kg	<0.026 U	<0.0059 U	<0.007 U	<0.0079 U	<0.026 U	<0.007 U	<0.0049 U	<0.0085 U	<0.0058 U	<0.0055 U	<0.0054 U	<0.0077 U	<0.004 U	<0.0076 U	<0.0055 U	<0.0064 U	<0.0054 U
Bromoform	75-25-2	NS	NS	NS	mg/kg	<0.026 U	<0.0059 U	<0.007 U	<0.0079 U	<0.026 U	<0.007 U	<0.0049 U	<0.0085 U	<0.0058 U	<0.0055 U	<0.0054 U	<0.0077 U	<0.004 U	<0.0076 U	<0.0055 U	<0.0064 U	<0.0054 U
Bromomethane	74-83-9	NS	NS	NS	mg/kg	<0.026 U	<0.0059 U	<0.007 U	<0.0079 U	<0.026 U	<0.007 U	<0.0049 U	<0.0085 U	<0.0058 U	<0.0055 U	<0.0054 U	<0.0077 U	<0.004 U	<0.0076 U	<0.0055 U	<0.0064 U	<0.0054 U
Carbon Disulfide	75-15-0	NS	NS	NS	mg/kg	<0.026 U	<0.0059 U	<0.007 U	<0.0079 U	<0.026 U	<0.007 U	<0.0049 U	0.0086	<0.0058 U	<0.0055 U	<0.0054 U	<0.0077 U	<0.004 U	<0.0076 U	<0.0055 U	<0.0064 U	<0.0054 U
Carbon Tetrachloride	56-23-5	0.76	0.76	7.1	mg/kg	<0.026 U	<0.0059 U	<0.007 U	<0.0079 U	<0.026 U	<0.007 U	<0.0049 U	<0.0085 U	<0.0058 U	<0.0055 U	<0.0054 U	<0.0077 U	<0.004 U	<0.0076 U	<0.0055 U	<0.0064 U	<0.0054 U
Chlorobenzene	108-90-7	4.5	4.5	100	mg/kg	<0.026 U	<0.0059 U	<0.007 U	<0.0079 U	<0.026 U	<0.007 U	<0.0049 U	<0.0085 U	<0.0058 U	<0.0055 U	<0.0054 U	<0.0077 U	<0.004 U	<0.0076 U	<0.0055 U	<0.0064 U	<0.0054 U
Chloroethane	75-00-3	NS	NS	NS	mg/kg	<0.026 U	<0.0059 U	<0.007 U	<0.0079 U	<0.026 U	<0.007 U	<0.0049 U	<0.0085 U	<0.0058 U	<0.0055 U	<0.0054 U	<0.0077 U	<0.004 U	<0.0076 U	<0.0055 U	<0.0064 U	<0.0054 U
Chloroform	67-66-3	0.37	0.37	24	mg/kg	<0.026 U	<0.0059 U	<0.007 U	<0.0079 U	<0.026 U	<0.007 U	<0.0049 U	<0.0085 U	<0.0058 U	<0.0055 U	<0.0054 U	<0.0077 U	<0.004 U	<0.0076 U	<0.0055 U	<0.0064 U	<0.0054 U
Chloromethane	74-87-3	NS	NS	NS	mg/kg	<0.026 U	<0.0059 U	<0.007 U	<0.0079 U	<0.026 U	<0.007 U	<0.0049 U	<0.0085 U	<0.0058 U	<0.0055 U	<0.0054 U	<0.0077 U	<0.004 UJ	<0.0076 UJ	<0.0055 UJ	<0.0064 U	<0.0054 U
Cis-1,2-Dichloroethene	156-59-2	0.19	0.19	41	mg/kg	<0.026 U	<0.0059 U	<0.007 U	<0.0079 U	<0.026 U	<0.007 U	<0.0049 U	<0.0085 U	<0.0058 U	<0.0055 U	<0.0054 U	<0.0077 U	<0.004 U	<0.0076 U	<0.0055 U	<0.0064 U	<0.0054 U
Cis-1,3-Dichloropropene	10061-01-5	NS	NS	NS	mg/kg	<0.026 U	<0.0059 U	<0.007 U	<0.0079 U	<0.026 U	<0.007 U	<0.0049 U	<0.0085 U	<0.0058 U	<0.0055 U	<0.0054 U	<0.0077 U	<0.004 U	<0.0076 U	<0.0055 U	<0.0064 U	<0.0054 U
Cyclohexane	110-82-7	NS	NS	NS	mg/kg	<0.026 U	<0.0059 U	<0.007 U	<0.0079 U	<0.026 U	<0.007 U	<0.0049 U	<0.0085 U	<0.0058 U	<0.0055 U	<0.0054 U	<0.0077 U	<0.004 U	<0.0076 U	<0.0055 U	<0.0064 U	<0.0054 U
Cymene	99-87-6	NS	NS	NS	mg/kg	NA	NA	NA	<0.0079 U	NA	<0.007 U	<0.0049 U	<0.0085 U	NA	NA	<0.0054 U	NA	<0.004 U	<0.0076 U	<0.0055 U	<0.0064 U	NA
Dibromochloromethane	124-48-1	NS	NS	NS	mg/kg	<0.026 U	<0.0059 U	<0.007 U	<0.0079 U	<0.026 U	<0.007 U	<0.0049 U	<0.0085 U	<0.0058 U	<0.0055 U	<0.0054 U	<0.0077 U	<0.004 U	<0.0076 U	<0.0055 U	<0.0064 U	<0.0054 U
Dibromomethane	74-95-3	NS	NS	NS	mg/kg	NA	NA	NA	<0.0079 U	NA	<0.007 U	<0.0049 U	<0.0085 U	NA	NA	<0.0054 U	NA	<0.004 U	<0.0076 U	<0.0055 U	<0.0064 U	NA
Dichlorodifluoromethane	75-71-8	NS	NS	NS	mg/kg	<0.026 U	<0.0059 U	<0.007 U	<0.0079 U	<0.026 U	<0.007 U	<0.0049 U	<0.0085 U	<0.0058 U	<0.0055 U	<0.0054 U	<0.0077 U	<0.004 UJ	<0.0076 UJ	<0.0055 UJ	<0.0064 U	<0.0054 U
Ethylbenzene	100-41-4	1	1	76	mg/kg	<0.026 U	<0.0059 U	<0.007 U	<0.0079 U	<0.026 U	<0.007 U	<0.0049 U	<0.0085 U	<0.0058 U	<0.0055 U	<0.0054 U	<0.0077 U	<0.004 U	<0.0076 U	<0.0055 U	<0.0064 U	<0.0054 U
Hexachlorobutadiene	87-68-3	NS	NS	NS	mg/kg	NA	NA	NA	<0.0079 U	NA	<0.007 U	<0.0049 U	<0.0085 U	NA	NA	<0.0054 U	NA	<0.004 U	<0.0076 U	<0.0055 U	<0.0064 U	NA
Isopropylbenzene (Cumene)	98-82-8	NS	NS	NS	mg/kg	<0.026 U	<0.0059 U	<0.007 U	<0.0079 U	<0.026 U	<0.007 U	<0.0049 U	<0.0085 U	<0.0058 U	<0.0055 U	<0.0054 U	<0.0077 U	<0.004 U	<0.0076 U	<0.0055 U	<0.0064 U	<0.0054 U
M,P-Xylene	179601-23-1	NS	NS	NS	mg/kg	<0.026 U	<0.0059 U	<0.007 U	<0.016 U	<0.026 U	<0.014 U	<0.0097 U	<0.017 U	<0.0058 U	<0.0055 U	<0.0054 U	<0.0077 U	<0.0081 U	<0.015 U	<0.011 U	<0.013 U	<0.0054 U
Methyl Acetate	79-20-9	NS	NS	NS	mg/kg	<0.26 U	<0.059 U	<0.07 U	<0.0079 U	<0.26 U	<0.007 U	<0.0049 U	<0.0085 U	<0.058 U	<0.055 U	<0.054 U	<0.077 U	<0.004 U	<0.0076 U	<0.0055 U	<0.0064 U	<0.054 U
Methyl Ethyl Ketone (2-Butanone)	78-93-3	0.1	0.1	100	mg/kg	<0.16 U	<0.035 U	<0.042 U	<0.0079 UJ	<0.16 U	<0.007 UJ	<0.0049 UJ	<0.0085 U	<0.035 U	<0.033 U	<0.032 U	<0.046 U	0.013	0.03	0.029	0.011	<0.032 U
Methyl Isobutyl Ketone (4-Methyl-2-Pentanone)	108-10-1	NS	NS	NS	mg/kg	<0.13 U	<0.029 U	<0.035 U	<0.0079 U	<0.13 U	<0.007 U	<0.0049 U	<0.0085 U	<0.029 U	<0.027 U	<0.027 U	<0.038 U	<0.004 U	<0.0076 U	<0.0055 U	<0.0064 U	<0.027 U
Methylcyclohexane	108-87-2	NS	NS	NS	mg/kg	<0.026 U	<0.0059 U	<0.007 U	<0.0079 U	<0.026 U	<0.007 U	<0.0049 U	<0.0085 U	<0.0058 U	<0.0055 U	<0.0054 U	<0.0077 U	<0.004 U	<0.0076 U	<0.0055 U	<0.0064 U	<0.0054 U
Methylene Chloride	75-09-2	0.05	0.05	81	mg/kg	<0.026 U	<0.0059 U	<0.007 U	<0.016 U	<0.026 U	<0.014 U	<0.0097 U	<0.017 U	<0.0058 U	<0.0055 U	<0.027 U	<0.0077 U	<0.0081 U	<0.015 U	<0.011 U	<0.013 U	<0.0054 U
n-Butylbenzene	104-51-8	18	18	100	mg/kg	NA	NA	NA	<0.0079 UJ	NA	<0.007 UJ	<0.0049 UJ	<0.0085 U	NA	NA	<0.0054 U	NA	<0.004 U	<0.0076 U	<0.0055 U	<0.0064 U	NA
n-Propylbenzene	103-65-1	5	5	100	mg/kg	NA	NA	NA	<0.0079 U	NA	<0.007 U	<0.0049 U	<0.0085 U	NA	NA	<0.0054 U	NA	<0.004 U	<0.0076 U	<0.0055 U	<0.0064 U	NA
o-Xylene (1,2-Dimethylbenzene)	95-47-6	NS	NS	NS	mg/kg	<0.026 U	<0.0059 U	<0.007 U	<0.0079 U	<0.026 U	<0.007 U	<0.0049 U	<0.0085 U	<0.0058 U	<0.0055 U	<0.0054 U	<0.0077 U	<0.004 U	<0.0076 U	<0.0055 U	<0.0064 U	<0.0054 U
Sec-Butylbenzene	135-98-8	25	25	100	mg/kg	NA	NA	NA	<0.0079 U	NA	<0.007 U	<0.0049 U	<0.0085 U	NA	NA	<0.0054 U	NA	<0.004 U	<0.0076 U	<0.0055 U	<0.0064 U	NA
Styrene	100-42-5	NS	NS	NS	mg/kg	<0.026 U	<0.0059 U	<0.007 U	<0.0079 U	<0.026 U	<0.007 U	<0.0049 U	<0.0085 U	<0.0058 U	<0.0055 U	<0.0054 U	<0.0077 U	<0.004 U	<0.0076 U	<0.0055 U	<0.0064 U	<0.0054 U
T-Butylbenzene	98-06-6	11	11	100	mg/kg	NA	NA	NA	<0.0079 UJ	NA	<0.007 UJ	<0.0049 UJ	<0.0085 UJ	NA	NA	<0.0054 U	NA	<0.004 U	<0.0076 U	<0.0055 U	<0.0064 UJ	NA
Tert-Butyl Alcohol	75-65-0	NS	NS	NS	mg/kg	NA	NA	NA	<0.04 U	NA	0.02 J	<0.024 U	<0.042 U	NA	NA	<0.11 U	NA	0.015 J	<0.038 U	0.018 J	<0.032 U	NA
Tert-Butyl Methyl Ether (MTBE)	1634-04-4	0.1	0.1	100	mg/kg	<0.052 U	<0.012 U	<0.014 U	<0.0079 U	<0.052 U	<0.007 U	<0.0049 U	<0.0085 U	<0.012 U	<0.011 U	<0.011 U	<0.015 U	<0.004 U	<0.0076 U	<0.0055 U	<0.0064 U	<0.011 U
Tetrachloroethene (PCE)	127-18-4	1.3	1.3	18	mg/kg	<0.026 U	<0.0059 U	<0.007 U	<0.0079 U	<0.026 U	<0.007 U	<0.0049 U	<0.0085 U	<0.0058 U	<0.0055 U	<0.0054 U	<0.0077 U	<0.004 U	<0.0076 U	<0.0055 U	<0.0064 U	<0.0054 U
Toluene	108-88-3	0.7	0.7	100	mg/kg	<0.026 U	<0.0059 U	<0.007 U	<0.0079 U	<0.026 U	<0.007 U	<0.0049 U	<0.0085 U	<0.0058 U	<0.0055 U	<0.0054 U	<0.0077 U	<0.004 U	<0.0076 U	<0.0055 U	<0.0064 U	<0.0054 U
Total Xylenes	1330-20-7	0.26	1.2	100	mg/kg	NA	NA	NA	<0.024 U	NA	<0.021 U	<0.015 U	<0.025 U	NA	NA	NA	NA	<0.012 U	<0.023 U	<0.016 U	<0.019 U	NA
Trans-1,2-Dichloroethene	156-60-5	0.19	0.19	100	mg/kg	<0.026 U	<0.0059 U	<0.007 U	<0.0079 U	<0.026 U	<0.007 U	<0.0049 U	<0.0085 U	<0.0058 U	<0.0055 U	<0.0054 U	<0.0077 U	<0.004 U	<0.0076 U	<0.0055 U	<0.0064 U	<0.0054 U
Trans-1,3-Dichloropropene	10061-02-6	NS	NS	NS	mg/kg	<0.026 U	<0.0059 U	<0.007 U	<0.0079 U	<0.026 U	<0.007 U	<0.0049 U	<0.0085 U	<0.0058 U	<0.0055 U	<0.0054 U	<0.0077 U	<0.004 U	<0.0076 U	<0.0055 U	<0.0064 U	<0.0054 U
Trans-1,4-Dichloro-2-Butene	110-57-6	NS	NS	NS	mg/kg	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	<0.011 U	NA	NA	NA	NA	NA	NA
Trichloroethene (TCE)	79-01-6	0.47	0.47	6.4	mg/kg	<0.026 U	<0.0059 U	<0.007 U	<0.0079 U	<0.026 U	<0.007 U	<0.0049 U	<0.0085 U	<0.0058 U	<0.0055 U	<0.0054 U	<0.0077 U	<0.004 U	<0.0076 U	<0.0055 U	<0.0064 U	<0.0054 U
Trichlorofluoromethane	75-69-4	NS	NS	NS	mg/kg	<0.026 U	<0.0059 U	<0.007 U	<0.0079 U	<0.026 U	<0.007 U	<0.0049 U	<0.0085 U	<0.0058 U	<0.0055 U	<0.0054 U	<0.0077 U	<0.004 U	<0.0076 U	<0.0055 U	<0.0064 U	<0.0054 U
Vinyl Chloride	75-01-4	0.03	0.03	0.48	mg/kg	<0.026 U	<0.0059 U	<0.007 U	<0.0079 U	<0.026 U	<0.007 U	<0.0049 U	<0.0085 U	<0.0058 U	<0.0055 U	<0.0054 U	<0.0077 U	<0.004 UJ	<0.0076 UJ	<0.0055 UJ	<0.0064 U	<0.0054 U

Table 2
Site Management Plan
Soil Sample Analytical Results

12074 Flatlands Avenue p/o Lot 1 Site
Brooklyn, New York
BCP Site No. C224353
Langan Project No.: 100688803

Analyte	CAS Number	NYSDEC Part 375 Unrestricted Use SCOs	NYSDEC Part 375 Protection of Groundwater SCOs	NYSDEC Part 375 Restricted Use Restricted-Residential SCOs	Location	PE51	PE52	PE53	PE54	PE54	PE55	PE56	PE57	PE58	PE59	PE60	PE61	PE62	PE63	PE64	PE65	PE66
					Sample Name	PE51_19.5	PE52_20	PE53_20	PE54_20	PE54_21	PE55_20	PE56_20	PE57_20	PE58_19.5	PE59_19.5	PE60_29	PE61_20.5	PE62_20.5	PE63_20.5	PE64_20.5	PE65_20	PE66_19.5
					Sample Date	09/17/2025	09/23/2025	09/23/2025	08/27/2025	09/17/2025	08/27/2025	08/27/2025	06/26/2025	09/17/2025	09/17/2025	10/28/2025	09/23/2025	08/28/2025	08/28/2025	08/28/2025	06/26/2025	09/17/2025
					Sample Elevation	19.5	20	20	20	21	20	20	20	19.5	19.5	29	20.5	20.5	20.5	20.5	20	19.5
					Unit	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result
Semi-Volatile Organic Compounds																						
1,2,4,5-Tetrachlorobenzene	95-94-3	NS	NS	NS	mg/kg	<1.45 U	<0.194 U	<0.193 U	<0.232 U	<0.205 U	<0.232 U	<0.175 U	<0.207 U	<0.183 UJ	<0.182 U	<0.178 UJ	<0.181 U	<0.185 U	<0.209 U	<0.178 U	<0.232 U	<0.194 U
1,2,4-Trichlorobenzene	120-82-1	NS	NS	NS	mg/kg	<0.728 U	<0.0969 U	<0.0967 U	<0.116 U	<0.102 U	<0.116 U	<0.0878 U	<0.104 U	<0.0915 UJ	<0.0911 U	<0.0891 UJ	<0.0907 U	<0.0925 U	<0.105 U	<0.0889 U	<0.116 U	<0.097 U
1,2-Dichlorobenzene	95-50-1	1.1	1.1	100	mg/kg	<0.728 U	<0.0969 U	<0.0967 U	<0.116 U	<0.102 U	<0.116 U	<0.0878 U	<0.104 U	<0.0915 UJ	<0.0911 U	<0.0891 UJ	<0.0907 U	<0.0925 U	<0.105 U	<0.0889 U	<0.116 U	<0.097 U
1,2-Diphenylhydrazine	122-66-7	NS	NS	NS	mg/kg	<0.728 U	<0.0969 U	<0.0967 U	<0.116 U	<0.102 U	<0.116 U	<0.0878 U	<0.104 U	<0.0915 UJ	<0.0911 U	<0.0891 UJ	<0.0907 U	<0.0925 U	<0.105 U	<0.0889 U	<0.116 U	<0.097 U
1,3-Dichlorobenzene	541-73-1	2.6	2.6	38	mg/kg	<0.728 U	<0.0969 U	<0.0967 U	<0.116 U	<0.102 U	<0.116 U	<0.0878 U	<0.104 U	<0.0915 UJ	<0.0911 U	<0.0891 UJ	<0.0907 U	<0.0925 U	<0.105 U	<0.0889 U	<0.116 U	<0.097 U
1,4-Dichlorobenzene	106-46-7	1.8	1.8	24	mg/kg	<0.728 U	<0.0969 U	<0.0967 U	<0.116 U	<0.102 U	<0.116 U	<0.0878 U	<0.104 U	<0.0915 UJ	<0.0911 U	<0.0891 UJ	<0.0907 U	<0.0925 U	<0.105 U	<0.0889 U	<0.116 U	<0.097 U
1,4-Dioxane (P-Dioxane)	123-91-1	0.1	0.1	5.7	mg/kg	<0.0192 U	<0.0196 U	<0.0196 U	<0.0198 U	<0.0198 U	<0.0198 U	<0.0198 U	<0.0198 U	<0.0187 U	<0.019 U	<0.02 U	<0.0196 U	<0.0196 U	<0.0196 U	<0.0196 U	<0.0198 U	<0.0189 U
2,3,4,6-Tetrachlorophenol	58-90-2	NS	NS	NS	mg/kg	<1.45 U	<0.194 U	<0.193 U	<0.232 U	<0.205 U	<0.232 U	<0.175 U	<0.207 U	<0.183 UJ	<0.182 U	<0.178 UJ	<0.181 U	<0.185 U	<0.209 U	<0.178 U	<0.232 U	<0.194 U
2,4,5-Trichlorophenol	95-95-4	NS	NS	NS	mg/kg	<0.728 U	<0.0969 U	<0.0967 U	<0.116 U	<0.102 U	<0.116 U	<0.0878 U	<0.104 U	<0.0915 UJ	<0.0911 U	<0.0891 UJ	<0.0907 U	<0.0925 U	<0.105 U	<0.0889 U	<0.116 U	<0.097 U
2,4,6-Trichlorophenol	88-06-2	NS	NS	NS	mg/kg	<0.728 U	<0.0969 U	<0.0967 U	<0.116 U	<0.102 U	<0.116 U	<0.0878 U	<0.104 U	<0.0915 UJ	<0.0911 U	<0.0891 UJ	<0.0907 U	<0.0925 U	<0.105 U	<0.0889 U	<0.116 U	<0.097 U
2,4-Dichlorophenol	120-83-2	NS	NS	NS	mg/kg	<0.728 U	<0.0969 U	<0.0967 U	<0.116 U	<0.102 U	<0.116 U	<0.0878 U	<0.104 U	<0.0915 UJ	<0.0911 U	<0.0891 UJ	<0.0907 U	<0.0925 U	<0.105 U	<0.0889 U	<0.116 U	<0.097 U
2,4-Dimethylphenol	105-67-9	NS	NS	NS	mg/kg	<0.728 U	<0.0969 U	<0.0967 U	<0.116 U	<0.102 U	<0.116 U	<0.0878 U	<0.104 U	<0.0915 UJ	<0.0911 U	<0.0891 UJ	<0.0907 U	<0.0925 U	<0.105 U	<0.0889 U	<0.116 U	<0.097 U
2,4-Dinitrophenol	51-28-5	NS	NS	NS	mg/kg	<1.45 U	<0.194 U	<0.193 U	<0.232 UJ	<0.205 U	<0.232 UJ	<0.175 UJ	<0.207 U	<0.183 UJ	<0.182 U	<0.178 UJ	<0.181 U	<0.185 U	<0.209 U	<0.178 U	<0.232 U	<0.194 U
2,4-Dinitrotoluene	121-14-2	NS	NS	NS	mg/kg	<0.728 U	<0.0969 U	<0.0967 U	<0.116 U	<0.102 U	<0.116 U	<0.0878 U	<0.104 U	<0.0915 UJ	<0.0911 U	<0.0891 UJ	<0.0907 U	<0.0925 U	<0.105 U	<0.0889 U	<0.116 U	<0.097 U
2,6-Dinitrotoluene	606-20-2	NS	NS	NS	mg/kg	<0.728 U	<0.0969 U	<0.0967 U	<0.116 U	<0.102 U	<0.116 U	<0.0878 U	<0.104 U	<0.0915 UJ	<0.0911 U	<0.0891 UJ	<0.0907 U	<0.0925 U	<0.105 U	<0.0889 U	<0.116 U	<0.097 U
2-Chloronaphthalene	91-58-7	NS	NS	NS	mg/kg	<0.728 U	<0.0969 U	<0.0967 U	<0.116 U	<0.102 U	<0.116 U	<0.0878 U	<0.104 U	<0.0915 UJ	<0.0911 U	<0.0891 UJ	<0.0907 U	<0.0925 U	0.077 JD	<0.0889 U	<0.116 U	<0.097 U
2-Chlorophenol	95-57-8	NS	NS	NS	mg/kg	<0.728 U	<0.0969 U	<0.0967 U	<0.116 U	<0.102 U	<0.116 U	<0.0878 U	<0.104 U	<0.0915 UJ	<0.0911 U	<0.0891 UJ	<0.0907 U	<0.0925 U	<0.105 U	<0.0889 U	<0.116 U	<0.097 U
2-Methylnaphthalene	91-57-6	NS	NS	NS	mg/kg	<0.728 U	0.133 D	0.0758 JD	<0.116 U	<0.102 U	0.418 D	<0.0878 U	<0.104 U	<0.0915 UJ	0.0677 JD	<0.0891 UJ	0.0675 JD	<0.0925 U	<0.105 U	<0.0889 U	0.231 D	0.0752 JD
2-Methylphenol (o-Cresol)	95-48-7	0.33	0.33	100	mg/kg	<0.728 U	<0.0969 U	<0.0967 U	<0.116 U	<0.102 U	<0.116 U	<0.0878 U	<0.104 U	<0.0915 UJ	<0.0911 U	<0.0891 UJ	<0.0907 U	<0.0925 U	<0.105 U	<0.0889 U	<0.116 U	<0.097 U
2-Nitroaniline	88-74-4	NS	NS	NS	mg/kg	<1.45 U	<0.194 U	<0.193 U	<0.232 U	<0.205 U	<0.232 U	<0.175 U	<0.207 U	<0.183 UJ	<0.182 U	<0.178 UJ	<0.181 U	<0.185 U	<0.209 U	<0.178 U	<0.232 U	<0.194 U
2-Nitrophenol	88-75-5	NS	NS	NS	mg/kg	<0.728 U	<0.0969 U	<0.0967 U	<0.116 U	<0.102 U	<0.116 U	<0.0878 U	<0.104 U	<0.0915 UJ	<0.0911 U	<0.0891 UJ	<0.0907 U	<0.0925 U	<0.105 U	<0.0889 U	<0.116 U	<0.097 U
3 & 4 Methylphenol (m&p Cresol)	65794-96-9	**0.33**	0.33	100	mg/kg	<0.728 U	<0.0969 U	<0.0967 U	<0.116 U	<0.102 U	<0.116 U	<0.0878 U	<0.104 U	<0.0915 UJ	<0.0911 U	<0.0891 UJ	<0.0907 U	<0.0925 U	<0.105 U	<0.0889 U	<0.116 U	<0.097 U
3,3'-Dichlorobenzidine	91-94-1	NS	NS	NS	mg/kg	<0.728 U	<0.0969 U	<0.0967 U	<0.116 U	<0.102 U	<0.116 U	<0.0878 U	<0.104 U	<0.0915 UJ	<0.0911 U	<0.0891 UJ	<0.0907 U	<0.0925 U	<0.105 U	<0.0889 U	<0.116 U	<0.097 U
3-Nitroaniline	99-09-2	NS	NS	NS	mg/kg	<1.45 U	<0.194 U	<0.193 U	<0.232 U	<0.205 U	<0.232 U	<0.175 U	<0.207 U	<0.183 UJ	<0.182 U	<0.178 UJ	<0.181 U	<0.185 U	<0.209 U	<0.178 U	<0.232 U	<0.194 U
4,6-Dinitro-2-Methylphenol	534-52-1	NS	NS	NS	mg/kg	<1.45 U	<0.194 U	<0.193 U	<0.232 UJ	<0.205 U	0.498 J	<0.175 UJ	<0.207 U	<0.183 UJ	<0.182 U	<0.178 UJ	<0.181 U	<0.185 U	<0.209 U	<0.178 U	<0.232 U	<0.194 U
4-Bromophenyl Phenyl Ether	101-55-3	NS	NS	NS	mg/kg	<0.728 U	<0.0969 U	<0.0967 U	<0.116 U	<0.102 U	<0.116 U	<0.0878 U	<0.104 U	<0.0915 UJ	<0.0911 U	<0.0891 UJ	<0.0907 U	<0.0925 U	<0.105 U	<0.0889 U	<0.116 U	<0.097 U
4-Chloro-3-Methylphenol	59-50-7	NS	NS	NS	mg/kg	<0.728 U	<0.0969 U	<0.0967 U	<0.116 U	<0.102 U	<0.116 U	<0.0878 U	<0.104 U	<0.0915 UJ	<0.0911 U	<0.0891 UJ	<0.0907 U	<0.0925 U	<0.105 U	<0.0889 U	<0.116 U	<0.097 U
4-Chloroaniline	106-47-8	NS	NS	NS	mg/kg	<0.728 U	<0.0969 U	<0.0967 U	<0.116 U	<0.102 U	<0.116 U	<0.0878 U	<0.104 U	<0.0915 UJ	<0.0911 U	<0.0891 UJ	<0.0907 U	<0.0925 U	<0.105 U	<0.0889 U	<0.116 U	<0.097 U
4-Chlorophenyl Phenyl Ether	7005-72-3	NS	NS	NS	mg/kg	<0.728 U	<0.0969 U	<0.0967 U	<0.116 U	<0.102 U	<0.116 U	<0.0878 U	<0.104 U	<0.0915 UJ	<0.0911 U	<0.0891 UJ	<0.0907 U	<0.0925 U	<0.105 U	<0.0889 U	<0.116 U	<0.097 U
4-Nitroaniline	100-01-6	NS	NS	NS	mg/kg	<1.45 U	<0.194 U	<0.193 U	<0.232 U	<0.205 U	<0.232 U	<0.175 U	<0.207 U	<0.183 UJ	<0.182 U	<0.178 UJ	<0.181 U	<0.185 U	<0.209 U	<0.178 U	<0.232 U	<0.194 U
4-Nitrophenol	100-02-7	NS	NS	NS	mg/kg	<1.45 U	<0.194 U	<0.193 U	<0.232 U	<0.205 U	<0.232 U	<0.175 U	<0.207 UJ	<0.183 UJ	<0.182 U	<0.178 UJ	<0.181 U	<0.185 U	<0.209 U	<0.178 U	<0.232 UJ	<0.194 U
Acenaphthene	83-32-9	20	98	100	mg/kg	<0.728 U	0.0744 JD	0.0618 JD	<0.116 U	<0.102 U	1.04 D	<0.0878 U	0.238 D	0.0614 J	0.161 D	<0.0891 UJ	<0.0907 U	0.154 D	0.0803 JD	<0.0889 U	1.73 D	0.222 D
Acenaphthylene	208-96-8	100	365	100	mg/kg	<0.728 U	0.0899 JD	0.058 JD	<0.116 U	<0.102 U	0.0603 JD	<0.0878 U	0.078 JD	<0.0915 UJ	0.21 D	<0.0891 UJ	0.0471 JD	0.0835 JD	<0.105 U	<0.0889 U	0.269 D	0.161 D
Acetophenone	98-86-2	NS	NS	NS	mg/kg	<0.728 U	<0.0969 U	<0.0967 U	<0.116 U	<0.102 U	<0.116 U	<0.0878 U	<0.104 U	<0.0915 UJ	0.0961 D	<0.0891 UJ	<0.0907 U	<0.0925 U	<0.105 U	<0.0889 U	<0.116 U	<0.097 U
Aniline (Phenylamine, Aminobenzene)	62-53-3	0.04	0.04	8.1	mg/kg	<2.92 U	<0.388 U	<0.387 U	<0.465 U	<0.41 U	<0.465 U	<0.352 U	<0.416 U	<0.366 UJ	<0.365 U	<0.357 UJ	<0.363 U	<0.37 U	<0.419 U	<0.356 U	<0.464 U	<0.389 U
Anthracene	120-12-7	100	1000	100	mg/kg	0.809 D	0.193 D	0.17 D	<0.116 U	<0.102 U	2.61 D	<0.0878 U	0.463 D	0.166 J	0.497 D	<0.0891 UJ	0.142 D	0.415 D	0.228 D	<0.0889 U	2.9 D	0.406 D
Atrazine	1912-24-9	NS	NS	NS	mg/kg	<0.728 U	<0.0969 U	<0.0967 U	<0.116 U	<0.102 U	<0.116 U	<0.0878 U	<0.104 U	<0.0915 UJ	<0.0911 U	<0.0891 UJ	<0.0907 U	<0.0925 U	<0.105 U	<0.0889 U	<0.116 U	<0.097 U
Benzaldehyde	100-52-7	NS	NS	NS	mg/kg	<0.728 U	<0.0969 U	<0.0967 U	<0.116 U	<0.102 U	<0.116 U	<0.0878 U	<0.104 U	<0.0915 UJ	0.059 JD	<0.0891 UJ	<0.0907 U	<0.0925 U	<0.105 U	<0.0889 U	<0.116 U	<0.097 U
Benzidine	92-87-5	NS	NS	NS	mg/kg	<2.92 U	<0.388 U	<0.387 U	<0.465 U	<0.41 U	<0.465 U	<0.352 U	<0.416 U	<0.366 UJ	<0.365 U	<0.357 UJ	<0.363 U	<0.37 U	<0.419 U	<0.356 U	<0.464 U	<0.389 U
Benzo(a)anthracene	56-55-3	**1**	1	1.4	mg/kg	**1.99 D**	0.537 D	0.427 D	0.149 D	<0.102 U	**4.99 D**	<0.0878 U	**1.19 D**	0.352 J	**1.12 D**	0.123 J	0.265 D	0.835 D	0.657 D	<0.0889 U	**3.47 D**	**1.2 D**
Benzo(a)pyrene	50-32-8	**1**	22	1	mg/kg	**1.45 D**	0.388 D	0.373 D	0.147 D	<0.102 U	**2.96 D**	<0.0878 U	0.911 D	0.25 J	0.868 D	0.14 J	0.26 D	0.788 D	0.639 D	<0.0889 U	**2.32 D**	**1.07 D**
Benzo(b)fluoranthene	205-99-2	**1**	2.1	1.4	mg/kg	**1.45 D**	0.577 D	0.356 D	0.121 D	<0.102 U	**3.03 D**	<0.0878 U	**1.27 D**	0.237 J	0.913 D	0.132 J	0.225 D	0.469 D	0.557 D	<0.0889 U	**3.06 D**	**1.06 D**
Benzo(g,h,i)Perylene	191-24-2	**0.64**	1000	4.9	mg/kg	**0.99 D**	0.301 D	0.259 D	0.138 D	<0.102 U	**1.86 D**	<0.0878 U	0.469 D	0.163 J	0.458 D	0.0556 J	0.128 D	0.438 D	0.376 D	<0.0889 U	**2.42 D**	0.551 D
Benzo(k)fluoranthene	207-08-9	**0.8**	2	4.9	mg/kg	**1.14 D**	0.429 D	0.274 D	0.108 JD	<0.102 U	**2.33 D**	<0.0878 U	0.552 J	0.246 J	0.724 D	0.13 J	0.22 D	0.592 D	0.561 D	<0.0889 U	**1.3 J**	**0.894 D**
Benzoic Acid	65-85-0	NS	NS	NS	mg/kg	<0.728 U	<0.0969 U	<0.0967 U	<0.116 U	<0.102 U	<0.116 U	<0.0878 U	<0.104 U	<0.0915 UJ	<0.0911 U	<0.0891 UJ	<0.0907 U	<0.0925 U	<0.105 U	<0.0889 U	<0.116 U	<0.097 U
Benzyl Alcohol	100-51-6	NS	NS	NS	mg/kg	<0.728 U	<0.0969 U	<0.0967 U	<0.116 U	<0.102 U	<0.116 U	<0.0878 U	<0.104 U	<0.0915 UJ	<0.0911 U	<0.0891 UJ	<0.0907 U	<0.0925 U	<0.105 U	<0.0889 U	<0.116 U	<0.097 U
Benzyl Butyl Phthalate	85-68-7	NS	NS	NS	mg/kg	<0.728 U	<0.0969 U	0.0657 JD	<0.116 U	<0.102 U	<0.116 U	<0.0878 U	<0.104 U	<0.0915 UJ	<0.0911 U	<0.0891 UJ	<0.0907 U	<0.0925 U	<0.105 U	<0.0889 U	0.17 D	<0.097 U
Biphenyl (Diphenyl)	92-52-4	NS	NS	NS	mg/kg	<0.728 U	<0.0969 U	<0.0967 U	<0.116 U	<0.102 U	0.115 JD	<0.0878 U	<0.104 U	<0.0915 UJ	<0.0911 U	<0.0891 UJ	<0.0907 U	<0.0925 U	<0.105 U	<0.0889 U	<0.116 U	<0.097 U
Bis(2-chloroethoxy) methane	111-91-1	NS	NS	NS	mg/kg	<0.728 U	<0.0969 U	<0.0967 U	<0.116 U	<0.102 U	<0.116 U	<0.0878 U	<0.104 U	<0.0915 UJ	<0.0911 U	<0.0891 UJ	<0.0907 U	<0.0925 U	<0.105 U	<0.0889 U	<0.116 U	<0.097 U
Bis(2-chloroethyl) ether (2-chloroethyl ether)	111-44-4	NS	NS	NS	mg/kg	<0.728 U	<0.0969 U	<0.0967 U	<0.116 U	<0.102 U	<0.116 U	<0.0878 U	<0.104 U	<0.0915 UJ	<0.0911 U	<0.0891 UJ	<0.0907 U	<0.0925 U	<0.105 U	<0.0889 U	<0.116 U	<0.097 U
Bis(2-chloroisopropyl) ether	108-60-1	NS	NS	NS	mg/kg	<0.728 U	<0.0969 U	<0.0967 U	<0.116 U	<0.102 U	<0.116 U	<0.0878 U	<0.104 U	<0.0915 UJ	<0.0911 U	<0.0891 UJ	<0.0907 U	<0.0925 U	<0.105 U	<0.0889 U	<0.116 U	<0.097 U
Bis(2-ethylhexyl) phthalate	117-81-7	NS	NS	NS	mg/kg	4.8 D	2.26 D	0.451 D	0.48 D	0.665 D	0.256 D	<0.0878 U	0.869 D	0.127 J	0.498 D	0.142 J	0.374 D	<0.0925 U	0.067 JD	<0.0889 U	17.7 D	0.34 D
Caprolactam	105-60-2	NS	NS	NS	mg/kg	<1.45 U	<0.194 U	<0.193 U	<0.232 U	<0.205 U	<0.232 U	<0.175 U	<0.207 U	<0.183 UJ	<0.182 U	<0.178 UJ	<0.181 U	<0.185 U	<0.209 U	<0.178 U	<0.232 U	<0.194 U
Carbazole	86-74-8	NS	NS	NS	mg/kg	<0.728 U	0.0852 JD	0.0549 JD	<0.116 U	<0.102 U	1.23 D	<0.0878 U	0.191 D	0.0585 J	0.161 D	<0.0891 UJ	<0.0907 U	<0.0925 U	0.12 D	<0.0889 U	0.555 D	0.146 D
Chrysene	218-01-9	**1**	1	4.9	mg/kg	**1.86 D**	0.609 D	0.382 D	0.148 D	<0.102 U	**4.99 D**	<0.0878 U	**1.17 D**	0.342 J	**1.26 D**	0.115 J	0.279 D	0.959 D	0.657 D	<0.0889 U	**3.11 D**	**1.29 D**
Dibenz(a,h)anthracene	53-70-3	**0.33**	1000	0.33	mg/kg	**0.378 JD**	0.106 D	<0.0967 U	<0.116 U	<0.102 U	**0.54 D**	<0.0878 U	0.136 D	0.0548 J	0.175 D	<0.0891 UJ	0.0566 JD	0.126 D	0.126 D	<0.0889 U	**0.655 D**	0.212 D
Dibenzofuran	132-64-9	**2.1**	110	18	mg/kg	<0.728 U	0.0535 JD	0.0618 JD	<0.116 U	<0.102 U	0.861 D	<0.0878 U	0.0946 JD	<0.0915 UJ	0.132 D	<0.0891 UJ	<0.0907 U	<0.0925 U	<0.105 U	<0.0889 U	0.413 D	0.122 D
Dibutyl phthalate	84-74-2	NS	NS	NS	mg/kg	<0.728 U	0.982 D	<0.0967 U	<0.116 U	<0.102 U	<0.116 U	<0.0878 U	0.256 D	<0.0915 UJ	<0.0911 U	<0.0891 UJ	0.0515 JD	<0.0925 U	<0.105 U	<0.0889 U	0.0983 JD	<0.097 U
Diethyl phthalate	84-66-2	NS	NS	NS	mg/kg	<0.728 U	<0.0969 U	<0.0967 U	<0.116 U	<0.102 U	<0.116 U	<0.0878 U	<0.104 U	<0.0915 UJ	<0.0911 U	<0.0891 UJ	<0.0907 U	<0.0925 U	<0.105 U	<0.0889 U	<0.116 U	<0.097 U
Dimethyl phthalate	131-11-3	NS	NS	NS	mg/kg	<0.728 U	<0.0969 U	<0.0967 U	<0.116 U	<0.102 U	<0.116 U	<0.0878 U	<0.104 U	<0.0915 UJ	<0.0911 U	<0.0891 UJ	<0.0907 U	<0.0925 U	<0.105 U	<0.0889 U	<0.116 U	<0.097 U
Dioctyl phthalate	117-84-0	NS	NS	NS	mg/kg	<0.728 U	<0.0969 U	<0.0967 U	<0.116 U	<0.102 U	<0.116 U	<0.0878 U	<0.104 U	<0.0915 UJ	<0.0911 U	<0.0891 UJ	<0.0907 U	<0.0925 U	<0.105 U	<0.0889 U	12.6 D	<0.097 U
Fluoranthene	206-44-0	85	1000	100	mg/kg	4.2 D	1.28 D	0.839 D	0.253 D	<0.102 U	11.2 D	<0.0878 U	3.2 D	0.831 J	2.33 D	0.249 J	0.342 D	1.44 D	1.3 D	<0.0889 U	7.4 D	2.13 D
Fluorene	86-73-7	30	386	100	mg/kg	<0.728 U	0.116 D	0.0819 JD	<0.116 U	<0.102 U	1.23 D	<0.0878 U	0.234 D	0.0643 J	0.213 D	<0.0891 UJ	0.074 JD	0.197 D	0.087 JD	<0.0889 U	1.43 D	0.203 D
Hexachlorobenzene	118-74-1	0.33	3.2	0.33	mg/kg	<0.728 U	<0.0969 U	<0.0967 U	<0.116 U	<0.102 U	<0.116 U	<0.0878 U	<0.104 U	<0.0915 UJ	<0.0911 U	<0.0891 UJ	<0.0907 U	<0.0925 U	<0.105 U	<0.0889 U	<0.116 U	<0.097 U
Hexachlorobutadiene	87-68-3	NS	NS	NS	mg/kg	<0.728 U	<0.0969 U	<0.0967 U	<0.116 U	<0.102 U	<0.116 U	<0.0878 U	<0.104 U	<0.0915 UJ	<0.0911 U	<0.0891 UJ	<0.0907 U	<0.0925 U	<0.105 U	<0.0889 U	<0.116 U	<0.097 U
Hexachlorocyclopentadiene	77-47-4	NS	NS	NS	mg/kg	<0.728 U	<0.0969 U	<0.0967 U	<0.116 UJ	<0.102 U	<0.116 UJ	<0.0878 UJ	<0.104 UJ	<0.0915 UJ	<0.0911 U	<0.0891 UJ	<0.0907 U	<0.0925 U	<0.105 U	<0.0889 U	<0.116 UJ	<0.097 U
Hexachloroethane	67-72-1	NS	NS	NS	mg/kg	<0.728 U	<0.0969 U	<0.0967 U	<0.116 U	<0.102 U	<0.116 U	<0.0878 U	<0.104 U	<0.0915 UJ	<0.0911 U	<0.0891 UJ	<0.0907 U	<0.0925 U	<0.105 U	<0.0889 U	<0.116 U	<0.097 U
Indeno(1,2,3-cd)pyrene	193-39-5	**0.5**	6.6	1.4	mg/kg	**0.862 D**	0.253 D	0.301 D	0.0862 JD	<0.102 U	**1.52 D**	<0.0878 U	0.493 D	0.137 J	0.434 D	0.0791 J	0.112 D	0.419 D	0.38 D	<0.0889 U	**2.7 D**	0.499 D
Isophorone	78-59-1	NS	NS	NS	mg/kg	<0.728 U	<0.0969 U	<0.0967 U	<0.116 U	<0.102 U	<0.116 U	<0.0878 U	<0.104 U	<0.0915 UJ	<0.0911 U	<0.0891 UJ	<0.0907 U	<0.0925 U	<0.105 U	<0.0889 U	<0.116 U	<0.097 U
Naphthalene	91-20-3	12	12	100	mg/kg	<0.728 U	0.725 D	0.396 D	<0.116 U	0.286 D	0.798 D	<0.0878 U	<0.104 U	<0.0915 UJ	0.136 D	<0.0891 UJ	0.589 D	<0.0925 U	0.0527 JD	<0.0889 U	0.114 JD	0.133 D
Nitrobenzene	98-95-3	0.08	0.08	1.8	mg/kg	<0.728 U	<0.0969 U	<0.0967 U	<0.116 U	<0.102 U	<0.116 U	<0.0878 U	<0.104 U	<0.0915 UJ	<0.0911 U	<0.0891 UJ	<0.0907 U	<0.0925 U	<0.105 U	<0.0889 U	<0.116 U	<0.097 U
n-Nitrosodimethylamine	62-75-9	NS	NS	NS	mg/kg	<0.728 U	<0.0969 U	<0.0967 U	<0.116 U	<0.102 U	<0.116 U	<0.0878 U	<0.104 U	<0.0915 UJ	<0.0911 U	<0.0891 UJ	<0.0907 U	<0.0925 U	<0.105 U	<0.0889 U	<0.116 U	<0.097 U
n-Nitrosodi-N-Propylamine	621-64-7	NS	NS	NS	mg/kg	<0.728 U	<0.0969 U	<0.0967 U	<0.116 U	<0.102 U	<0.116 U	<0.0878 U	<0.104 U	<0.0915 UJ	<0.0911 U	<0.0891 UJ	<0.0907 U	<0.0925 U	<0.105 U	<0.0889 U	<0.116 U	<0.097 U
n-Nitrosodiphenylamine	86-30-6	NS	NS	NS	mg/kg	<0.728 U	<0.0969 U	<0.0967 U	<0.116 U	<0.102 U	0.468 D	<0.0878 U	<0.104 U	<0.0915 UJ	<0.0911 U	<0.0891 UJ	<0.0907 U	<0.0925 U	<0.105 U	<0.0889 U	<0.116 U	<0.097 U
Pentachlorophenol	87-86-5	0.8	0.8	1.3	mg/kg	<0.728 U	<0.0969 U	<0.0967 U	<0.116 U	<0.102 U	<0.116 U	<0.0878 U	<0.104 U	<0.0915 UJ	<0.0911 U	<0.0891 UJ	<0.0907 U	<0.0925 U	<0.105 U	<0.0889 U	<0.116 U	<0.097 U
Phenanthrene	85-01-8	**1.1**	1000	4.9	mg/kg	**2.75 D**	0.93 D	0.476 D	0.148 D	<0.102 U	**12 D**	<0.0878 U	**1.86 D**	0.561 J	**1.61 D**	0.122 J	0.297 D	**1.36 D**	0.923 D	<0.0889 U	**3.05 D**	**1.25 D**
Phenol	108-95-2	0.33	0.33	100	mg/kg	<0.728 U	<0.0969 U	<0.0967 U	<0.116 U	<0.102 U	<0.116 U	<0.0878 U	<0.104 U	<0.0915 UJ	<0.0911 U	<0.0891 UJ	<0.0907 U	<0.0925 U	<0.105 U	<0.0889 U	<0.116 U	<0.097 U
Pyrene	129-00-0	64	1000	100	mg/kg	6.98 D	1.77 D	0.862 D	0.284 D	<0.102 U	9.07 D	<0.0878 U	2.33 D	1.48 J	3.25 DE	0.272 J	0.518 D	1.9 D	1.06 D	<0.0889 U	5.36 D	3.07 D
Pyridine	110-86-1	NS	NS	NS	mg/kg	<2.92 U	<0.388 U	<0.387 U	<0.465 U	<0.41 U	<0.465 U	<0.352 U	<0.416 U	<0.366 UJ	<0.365 U	<0.357 UJ	<0.363 U	<0.37 U	<0.419 U	<0.356 U	<0.464 U	<0.389 U

Table 2
Site Management Plan
Soil Sample Analytical Results

12074 Flatlands Avenue p/o Lot 1 Site
Brooklyn, New York
BCP Site No. C224353
Langan Project No.: 100688803

Analyte	CAS Number	NYSDEC Part 375 Unrestricted Use SCOs	NYSDEC Part 375 Protection of Groundwater SCOs	NYSDEC Part 375 Restricted Use Restricted-Residential SCOs	Location	PE51	PE52	PE53	PE54	PE54	PE55	PE56	PE57	PE58	PE59	PE60	PE61	PE62	PE63	PE64	PE65	PE66
					Sample Name	PE51_19.5	PE52_20	PE53_20	PE54_20	PE54_21	PE55_20	PE56_20	PE57_20	PE58_19.5	PE59_19.5	PE60_29	PE61_20.5	PE62_20.5	PE63_20.5	PE64_20.5	PE65_20	PE66_19.5
					Sample Date	09/17/2025	09/23/2025	09/23/2025	08/27/2025	09/17/2025	08/27/2025	08/27/2025	06/26/2025	09/17/2025	09/17/2025	10/28/2025	09/23/2025	08/28/2025	08/28/2025	08/28/2025	06/26/2025	09/17/2025
					Sample Elevation	19.5	20	20	20	21	20	20	20	19.5	19.5	29	20.5	20.5	20.5	20.5	20	19.5
					Unit	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result
Pesticides																						
4,4'-DDD	72-54-8	**0.0033**	14	5	mg/kg	**0.0358 DP**	**0.0265 J**	**0.00486 J**	<0.00227 UP	<0.00201 UP	<0.00229 UP	<0.00174 UP	**0.00477 DP**	**0.101 DP**	**0.0283 DP**	<0.00176 UP	0.00264 D	<0.00182 UP	0.00219 J	<0.00175 UP	**0.00537 DP**	**0.0109 DP**
4,4'-DDE	72-55-9	**0.0033**	9.3	3.4	mg/kg	**0.141 DP**	**0.0157 J**	**0.00694 J**	<0.00227 UP	<0.00201 UP	<0.00229 UP	<0.00174 UP	<0.00204 UP	**0.0275 DP**	**0.00867 DP**	<0.00176 UP	<0.00178 U	<0.00182 UP	<0.00208 UP	<0.00175 UP	<0.0023 UP	**0.00627 DP**
4,4'-DDT	50-29-3	**0.0033**	135	3.8	mg/kg	**0.0549 DP**	<0.00191 U	<0.0019 U	<0.00227 UP	<0.00201 UP	<0.00229 UP	<0.00174 UP	<0.00204 UP	**0.0356 J**	**0.0126 J**	0.00235 DP	<0.00178 U	<0.00182 UP	0.00313 J	<0.00175 UP	<0.0023 UP	0.00209 J
Aldrin	309-00-2	0.0048	0.19	0.044	mg/kg	<0.00191 UP	<0.00191 U	<0.0019 U	<0.00227 UP	<0.00201 UP	<0.00229 UP	<0.00174 UP	<0.00204 UP	<0.0018 UP	<0.00179 UP	0.00334 DP	<0.00178 U	<0.00182 UP	<0.00208 UP	<0.00175 UP	<0.0023 UP	<0.00191 UP
Alpha BHC (Alpha Hexachlorocyclohexane)	319-84-6	0.02	0.02	0.18	mg/kg	<0.00191 UP	<0.00191 U	<0.0019 U	<0.00227 UP	<0.00201 UP	<0.00229 UP	<0.00174 UP	<0.00204 UP	<0.0018 UP	<0.00179 UP	<0.00176 UP	<0.00178 U	<0.00182 UP	<0.00208 UP	<0.00175 UP	<0.0023 UP	<0.00191 UP
Alpha Chlordane	5103-71-9	**0.014**	4.5	0.65	mg/kg	0.00342 J	0.00515 J	<0.0019 U	<0.00227 UP	<0.00201 UP	<0.00229 UP	<0.00174 UP	<0.00204 UP	0.00607 J	0.00315 J	0.0103 DP	<0.00178 U	<0.00182 UP	<0.00208 UP	<0.00175 UP	<0.0023 UP	0.00288 DP
Alpha Endosulfan	959-98-8	4.3	65	35	mg/kg	<0.00191 UP	<0.00191 U	<0.0019 U	<0.00227 UP	<0.00201 UP	<0.00229 UP	<0.00174 UP	<0.00204 UP	<0.0018 UP	<0.00179 UP	<0.00176 UP	<0.00178 U	<0.00182 UP	<0.00208 UP	<0.00175 UP	<0.0023 UP	<0.00191 UP
Beta Bhc (Beta Hexachlorocyclohexane)	319-85-7	0.021	0.09	0.18	mg/kg	<0.00191 UP	<0.00191 U	<0.0019 U	<0.00227 UP	<0.00201 UP	<0.00229 UP	<0.00174 UP	<0.00204 UP	<0.0018 UP	<0.00179 UP	<0.00176 UP	<0.00178 U	<0.00182 UP	<0.00208 UP	<0.00175 UP	<0.0023 UP	<0.00191 UP
Beta Endosulfan	33213-65-9	4.3	44	35	mg/kg	<0.00191 UP	<0.00191 U	<0.0019 U	<0.00227 UP	<0.00201 UP	<0.00229 UP	<0.00174 UP	<0.00204 UP	<0.0018 UP	<0.00179 UP	<0.00176 UP	<0.00178 U	<0.00182 UP	<0.00208 UP	<0.00175 UP	<0.0023 UP	<0.00191 UP
Delta Bhc (Delta Hexachlorocyclohexane)	319-86-8	0.04	0.1	100	mg/kg	<0.00191 UP	<0.00191 U	<0.0019 U	<0.00227 UP	<0.00201 UP	<0.00229 UP	<0.00174 UP	<0.00204 UP	<0.0018 UP	<0.00179 UP	<0.00176 UP	<0.00178 U	<0.00182 UP	<0.00208 UP	<0.00175 UP	<0.0023 UP	<0.00191 UP
Dieldrin	60-57-1	**0.005**	0.1	0.075	mg/kg	<0.00191 UP	<0.00191 U	<0.0019 U	<0.00227 UP	<0.00201 UP	<0.00229 UP	<0.00174 UP	<0.00204 UP	<0.0018 UP	<0.00179 UP	0.00395 DP	<0.00178 U	<0.00182 UP	0.00209 J	<0.00175 UP	<0.0023 UP	<0.00191 UP
Endosulfan Sulfate	1031-07-8	4.3	47	35	mg/kg	<0.00191 UP	<0.00191 U	<0.0019 U	<0.00227 UP	<0.00201 UP	<0.00229 UP	<0.00174 UP	<0.00204 UP	<0.0018 UP	<0.00179 UP	<0.00176 UP	<0.00178 U	<0.00182 UP	<0.00208 UP	<0.00175 UP	<0.0023 UP	<0.00191 UP
Endrin	72-20-8	0.014	0.06	5.3	mg/kg	<0.00191 UP	<0.00191 U	<0.0019 U	<0.00227 UP	<0.00201 UP	<0.00229 UP	<0.00174 UP	<0.00204 UP	<0.0018 UP	<0.00179 UP	<0.00176 UP	<0.00178 U	<0.00182 UP	<0.00208 UP	<0.00175 UP	<0.0023 UP	<0.00191 UP
Endrin Aldehyde	7421-93-4	NS	NS	NS	mg/kg	<0.00191 UP	<0.00191 U	<0.0019 U	<0.00227 UP	<0.00201 UP	<0.00229 UP	<0.00174 UP	<0.00204 UP	<0.0018 UP	<0.00179 UP	<0.00176 UP	<0.00178 U	<0.00182 UP	<0.00208 UP	<0.00175 UP	<0.0023 UP	<0.00191 UP
Endrin Ketone	53494-70-5	NS	NS	NS	mg/kg	<0.00191 UP	<0.00191 U	<0.0019 U	<0.00227 UP	<0.00201 UP	<0.00229 UP	<0.00174 UP	<0.00204 UP	<0.0018 UP	<0.00179 UP	<0.00176 UP	<0.00178 U	<0.00182 UP	<0.00208 UP	<0.00175 UP	<0.0023 UP	<0.00191 UP
Gamma Bhc (Lindane)	58-89-9	0.025	0.05	0.21	mg/kg	<0.00191 UP	<0.00191 U	<0.0019 U	<0.00227 UP	<0.00201 UP	<0.00229 UP	<0.00174 UP	<0.00204 UP	<0.0018 UP	<0.00179 UP	<0.00176 UP	<0.00178 U	<0.00182 UP	<0.00208 UP	<0.00175 UP	<0.0023 UP	<0.00191 UP
Gamma-Chlordane	5566-34-7	NS	NS	NS	mg/kg	0.0269 D	0.00642 J	<0.0019 U	<0.00227 UP	<0.00201 UP	<0.00229 UP	<0.00174 UP	<0.00204 UP	0.0124 J	0.00372 J	0.0103 DP	<0.00178 U	<0.00182 UP	<0.00208 UP	<0.00175 UP	<0.0023 UP	0.00577 J
Heptachlor	76-44-8	0.013	0.38	0.53	mg/kg	<0.00191 UP	<0.00191 U	<0.0019 U	<0.00227 UP	<0.00201 UP	<0.00229 UP	<0.00174 UP	<0.00204 UP	<0.0018 UP	<0.00179 UP	<0.00176 UP	<0.00178 U	<0.00182 UP	<0.00208 UP	<0.00175 UP	<0.0023 UP	<0.00191 UP
Heptachlor Epoxide	1024-57-3	NS	NS	NS	mg/kg	<0.00191 UP	<0.00191 U	<0.0019 U	<0.00227 UP	<0.00201 UP	<0.00229 UP	<0.00174 UP	<0.00204 UP	<0.0018 UP	<0.00179 UP	<0.00176 U	<0.00178 U	<0.00182 UP	<0.00208 UP	<0.00175 UP	<0.0023 UP	<0.00191 UP
Methoxychlor	72-43-5	NS	NS	NS	mg/kg	<0.00191 UP	<0.00191 U	<0.0019 U	<0.00227 UP	<0.00201 UP	<0.00229 UP	<0.00174 UP	<0.00204 UP	<0.0018 UP	<0.00179 UP	<0.00176 UP	<0.00178 U	<0.00182 UP	<0.00208 UP	<0.00175 UP	<0.0023 UP	<0.00191 UP
Toxaphene	8001-35-2	NS	NS	NS	mg/kg	<0.191 UP	<0.191 U	<0.19 U	<0.227 UP	<0.201 UP	<0.229 UP	<0.174 UP	<0.204 UP	<0.18 UP	<0.179 UP	<0.176 UP	<0.178 U	<0.182 UP	<0.208 UP	<0.175 UP	<0.23 UP	<0.191 UP
Herbicides																						
2,4,5-T (Trichlorophenoxyacetic Acid)	93-76-5	NS	NS	NS	mg/kg	<0.0227 UP	<0.0231 U	<0.023 U	<0.028 UP	<0.0242 UP	<0.028 UP	<0.0212 UP	<0.0247 UP	<0.0214 UP	<0.0216 UP	NA	<0.0217 U	<0.0217 UP	<0.0254 UP	<0.0212 UP	<0.0281 UP	<0.023 UP
2,4-D (Dichlorophenoxyacetic Acid)	94-75-7	NS	NS	NS	mg/kg	<0.0227 UP	<0.0231 U	<0.023 U	<0.028 UP	<0.0242 UP	<0.028 UP	<0.0212 UP	<0.0247 UP	<0.0214 UP	<0.0216 UP	<0.0212 UP	<0.0217 U	<0.0217 UP	<0.0254 UP	<0.0212 UP	<0.0281 UP	<0.023 UP
2,4-Dichlorophenoxybutyric acid	94-82-6	NS	NS	NS	mg/kg	<0.0227 UP	NA	NA	NA	<0.0242 UP	NA	NA	NA	<0.0214 UP	<0.0216 UP	NA	NA	NA	NA	NA	NA	<0.023 UP
Dalapon	75-99-0	NS	NS	NS	mg/kg	<0.0227 UP	NA	NA	NA	<0.0242 UP	NA	NA	NA	<0.0214 UP	<0.0216 UP	NA	NA	NA	NA	NA	NA	<0.023 UP
Dicamba	1918-00-9	NS	NS	NS	mg/kg	<0.0227 UP	NA	NA	NA	<0.0242 UP	NA	NA	NA	<0.0214 UP	<0.0216 UP	NA	NA	NA	NA	NA	NA	<0.023 UP
Silvex (2,4,5-Tp)	93-72-1	3.8	3.8	100	mg/kg	<0.0227 UP	<0.0231 U	<0.023 U	<0.028 UP	<0.0242 UP	<0.028 UP	<0.0212 UP	<0.0247 UP	<0.0214 UP	<0.0216 UP	NA	<0.0217 U	<0.0217 UP	<0.0254 UP	<0.0212 UP	<0.0281 UP	<0.023 UP
Polychlorinated Biphenyl																						
PCB-1016 (Aroclor 1016)	12674-11-2	NS	NS	NS	mg/kg	<0.0194 UP	<0.0192 UJ	<0.0192 UJ	<0.0229 UP	<0.0203 UP	<0.0231 UP	<0.0176 UP	<0.0206 UP	<0.0182 UP	<0.0181 UP	<0.0177 UP	<0.018 U	<0.0184 UP	<0.021 UP	<0.0177 UP	1.51 J	<0.0193 UP
PCB-1221 (Aroclor 1221)	11104-28-2	NS	NS	NS	mg/kg	<0.0194 UP	<0.0192 UJ	<0.0192 UJ	<0.0229 UP	<0.0203 UP	<0.0231 UP	<0.0176 UP	<0.0206 UP	<0.0182 UP	<0.0181 UP	<0.0177 UP	<0.018 U	<0.0184 UP	<0.021 UP	<0.0177 UP	<0.0232 UP	<0.0193 UP
PCB-1232 (Aroclor 1232)	11141-16-5	NS	NS	NS	mg/kg	<0.0194 UP	<0.0192 UJ	<0.0192 UJ	<0.0229 UP	<0.0203 UP	<0.0231 UP	<0.0176 UP	<0.0206 UP	<0.0182 UP	<0.0181 UP	<0.0177 UP	<0.018 U	<0.0184 UP	<0.021 UP	<0.0177 UP	<0.0232 UP	<0.0193 UP
PCB-1242 (Aroclor 1242)	53469-21-9	NS	NS	NS	mg/kg	0.298 J	0.383 J	0.0705 J	<0.0229 UP	<0.0203 UP	<0.0231 UP	<0.0176 UP	<0.0206 UP	1.76 P	1.16 P	<0.0177 UP	<0.018 U	<0.0184 UP	<0.021 UP	<0.0177 UP	<0.0232 UP	<0.0193 UP
PCB-1248 (Aroclor 1248)	12672-29-6	NS	NS	NS	mg/kg	<0.0194 UP	<0.0192 UJ	<0.0192 UJ	<0.0229 UP	<0.0203 UP	<0.0231 UP	<0.0176 UP	<0.0206 UP	<0.0182 UP	<0.0181 UP	<0.0177 UP	<0.018 U	<0.0184 UP	<0.021 UP	<0.0177 UP	<0.0232 UP	<0.0193 UP
PCB-1254 (Aroclor 1254)	11097-69-1	NS	NS	NS	mg/kg	<0.0194 UP	0.534 J	0.168 J	<0.0229 UP	<0.0203 UP	<0.0231 UP	<0.0176 UP	<0.0206 UP	<0.0182 UP	0.858 P	<0.0177 UP	0.16	<0.0184 UP	<0.021 UP	<0.0177 UP	<0.0232 UP	0.11 P
PCB-1260 (Aroclor 1260)	11096-82-5	NS	NS	NS	mg/kg	0.213	<0.0192 UJ	<0.0192 UJ	<0.0229 UP	<0.0203 UP	<0.0231 UP	<0.0176 UP	<0.0206 UP	1.51 P	<0.0181 UP	<0.0177 UP	<0.018 U	<0.0184 UP	<0.021 UP	<0.0177 UP	<0.0232 UP	<0.0193 UP
PCB-1262 (Aroclor 1262)	37324-23-5	NS	NS	NS	mg/kg	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
PCB-1268 (Aroclor 1268)	11100-14-4	NS	NS	NS	mg/kg	NA	0.0733 J	0.0465 J	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
Total PCBs	1336-36-3	**0.1**	3.2	1	mg/kg	**0.511 J**	**0.991 J**	**0.285 J**	<0.0229 UP	<0.0203 UP	<0.0231 UP	<0.0176 UP	<0.0206 UP	**3.28 P**	**2.02 P**	<0.0177 UP	**0.16**	<0.0184 UP	<0.021 UP	<0.0177 UP	**1.51 J**	**0.11 P**
Metals																						
Aluminum	7429-90-5	NS	NS	NS	mg/kg	4,600 B	6,100	5,460	4,080	3,420 B	7,490	5,590	5,980	6,930 B	5,140 B	8,510	5,850	7,260	5,280	6,400	40,100 J	7,940 B
Antimony	7440-36-0	NS	NS	NS	mg/kg	<2.43 U	68	<2.42 UJ	3.61	<2.57 U	9.93	<2.21 U	<2.6 U	<2.3 U	<2.28 U	<2.23 U	<2.27 U	<2.32 U	<2.65 U	<2.23 UJ	<2.95 UJ	2.81
Arsenic	7440-38-2	**13**	16	16	mg/kg	10.9	**14.2**	**13.6 J**	9.87	5.84	**16.9**	2.13	6.13	6.35	5.14	4.09	3.38	2.41	9.41	2.71	6.29	5.14
Barium	7440-39-3	**410**	820	410	mg/kg	281	**574**	**474 J**	**1,290**	236	**596**	10.6	**516**	**693**	398	67.2	325	64.1	**602**	40.7 J	**574 J**	357
Beryllium	7440-41-7	4.4	47	43	mg/kg	0.311	0.179	0.247	0.459	0.462	0.575	0.112	0.321	0.428	0.239	0.142	0.152 J	0.138	0.27	0.211 J	0.177	0.364
Cadmium	7440-43-9	**2.5**	7.5	2.5	mg/kg	**6.95**	**4.64**	1.82	1.05	0.4	0.957	<0.265 U	2.02	**4.37**	**2.77**	0.295	0.691	0.278	**2.69**	<0.268 U	2.2	1.26
Calcium	7440-70-2	NS	NS	NS	mg/kg	32,900	21,000	15,100 J	6,810	2,140	4,250	851	69,300	52,200	49,600	6,190	71,800	2,450	3,270	2,910	30,200 J	14,600
Chromium, Hexavalent	18540-29-9	1	19	1	mg/kg	<0.584 U	<0.583 U	<0.582 U	<0.7 U	<0.616 U	<0.7 U	<0.53 U	<0.624 U	<0.552 U	<0.548 U	<0.536 U	<0.546 U	<0.556 U	<0.636 U	<0.536 U	<0.709 U	<0.584 U
Chromium, Total	7440-47-3	NS	NS	NS	mg/kg	63.1	36.7	<0.485 UJ	59.6	12.6	13.5	11	26.8	30.1	24.3	17.1	17.1	14.3	23.6	11.4	26 J	19.1
Chromium, Trivalent	16065-83-1	**30**	19	110	mg/kg	**63.1**	**36.7**	**31.4**	**59.6**	12.6	13.5	11	26.8	**30.1**	24.3	17.1	17.1	14.3	23.6	11.4	26	19.1
Cobalt	7440-48-4	NS	NS	NS	mg/kg	9.05	7.16	8.74	4.98	4.84	18.4	3.66	7.79	6.26	5.3	5.89	4.08	4.01	5.76	4.41	6.49	5.36
Copper	7440-50-8	**50**	1720	280	mg/kg	**231**	**180**	**391**	**177**	38.4	**65**	7.43	**99.5**	**91**	**102**	27.9	**65.6 J**	26.6	**114**	10.5	**165**	**116**
Cyanide	57-12-5	**2.3**	40	13	mg/kg	1.27	<0.583 U	<0.582 U	<0.7 U	<0.616 U	<0.7 U	<0.53 U	<0.624 U	0.821	1.21	<0.536 U	<0.546 U	<0.556 U	<0.636 U	<0.536 U	1.05	<0.584 U
Iron	7439-89-6	NS	NS	NS	mg/kg	128,000 D	40,100	32,400	17,300	6,860	15,000	9,250	23,300	28,500	26,100	15,700	12,200	9,910	26,800	12,300	31,300	21,200
Lead	7439-92-1	**63**	450	400	mg/kg	**1,250**	**2,430**	**477**	**2,010**	**214**	**401**	4.18	**701**	**554**	**320**	**78.1**	**160**	**72.1**	**527**	9.12	**540**	**407**
Magnesium	7439-95-4	NS	NS	NS	mg/kg	5,200	3,340	2,800 J	486	312	553	2,320	4,730	5,200	6,040	2,900	10,300	1,970	1,380	2,170	5,280	3,320
Manganese	7439-96-5	**1600**	2000	2000	mg/kg	534	276	223	113	42.5	107	99.7	294	341	224	320	245	102	182	143 J	354	174
Mercury	7439-97-6	**0.18**	0.73	0.3	mg/kg	**0.721**	**0.652**	**0.654**	**0.648**	**0.291**	**1.76**	<0.0318 U	**0.923**	**1.17**	**0.727**	0.122	0.1	0.137	**0.582**	<0.0322 U	**1.57**	**0.646**
Nickel	7440-02-0	**30**	130	320	mg/kg	**127**	**37.2**	<0.966 UJ	13.9	13.3	17.7	16.5	**54.8**	21.8	27.5	14.4	15.2	15.2	23.8	15.2	**30.4**	21.3
Potassium	7440-09-7	NS	NS	NS	mg/kg	929	655	666	446	511	745	532	1,010	1,390	952	1,060	892	694	567	627	823	1,210
Selenium	7782-49-2	**3.9**	4	110	mg/kg	<2.43 U	<2.43 U	<2.42 U	<2.92 U	<2.57 U	<2.92 U	<2.21 U	<2.6 U	<2.3 U	<2.28 U	<2.23 U	<2.27 U	<2.32 U	<2.65 U	<2.23 U	<2.95 U	<2.43 U
Silver	7440-22-4	**2**	8.3	110	mg/kg	1.03	0.943	0.902 J	1.51	<0.517 U	0.63	<0.445 U	<0.524 U	<0.464 U	<0.46 U	<0.45 U	<0.458 U	<0.467 U	0.541	<0.451 U	0.816 J	<0.49 U
Sodium	7440-23-5	NS	NS	NS	mg/kg	<283 U	268	235 J	313	<255 U	1,070	63.1	331	<342 U	<266 U	284 J	233	263	356	91.9	292 J	<299 U
Thallium	7440-28-0	NS	NS	NS	mg/kg	<1.95 U	<1.95 U	<1.94 U	<2.34 U	<2.06 U	<2.34 U	<1.77 U	<2.08 U	<1.84 U	<1.83 U	<1.79 U	<1.82 U	<1.86 U	<2.12 U	<1.79 U	<2.37 U	<1.95 U
Vanadium	7440-62-2	NS	NS	NS	mg/kg	15.7	31.5	26.5	23.2	21.3	21.2	14.4	20.9	21.7	15.6	23.2	18.4	18.9	22.4	16.6	22.3	24.3
Zinc	7440-66-6	**109**	2480	6600	mg/kg	**2,360**	**3,730 D**	**624**	**424**	**201**	**706**	25.6	**478**	**703**	**677**	77.4	**238**	77.4	**825**	37.1	**661**	**361**

Table 2
Site Management Plan
Soil Sample Analytical Results

12074 Flatlands Avenue p/o Lot 1 Site
Brooklyn, New York
BCP Site No. C224353
Langan Project No.: 100688803

Analyte	CAS Number	NYSDEC Part 375 Unrestricted Use SCOs	NYSDEC Part 375 Protection of Groundwater SCOs	NYSDEC Part 375 Restricted Use Restricted-Residential SCOs	Location	PE51	PE52	PE53	PE54	PE54	PE55	PE56	PE57	PE58	PE59	PE60	PE61	PE62	PE63	PE64	PE65	PE66
					Sample Name	PE51_19.5	PE52_20	PE53_20	PE54_20	PE54_21	PE55_20	PE56_20	PE57_20	PE58_19.5	PE59_19.5	PE60_29	PE61_20.5	PE62_20.5	PE63_20.5	PE64_20.5	PE65_20	PE66_19.5
					Sample Date	09/17/2025	09/23/2025	09/23/2025	08/27/2025	09/17/2025	08/27/2025	08/27/2025	06/26/2025	09/17/2025	09/17/2025	10/28/2025	09/23/2025	08/28/2025	08/28/2025	08/28/2025	06/26/2025	09/17/2025
					Sample Elevation	19.5	20	20	20	21	20	20	20	19.5	19.5	29	20.5	20.5	20.5	20.5	20	19.5
					Unit	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result
Per- and Polyfluoroalkyl Substances																						
11-Chloroeicosafluoro-3-Oxaundecane-1-Sulfonic Acid (11Cl-PF3OUdS)	763051-92-9	NS	NS	NS	mg/kg	<0.000883 U	<0.000882 U	<0.000879 U	<0.00106 UJ	<0.000931 UJ	<0.00106 UJ	<0.000801 U	<0.000938 UJ	<0.000835 UJ	<0.000827 UJ	<0.00081 U	<0.000825 U	<0.000839 UJ	<0.000958 U	<0.000809 U	<0.00106 UJ	<0.000882 UJ
1H,1H,2H,2H-Perfluorodecane Sulfonic Acid (8:2 FTS)	39108-34-4	NS	NS	NS	mg/kg	<0.000897 U	<0.000895 U	<0.000893 U	<0.00108 UJ	<0.000946 U	<0.00108 UJ	<0.000814 U	<0.000953 UJ	<0.000848 U	<0.00084 U	<0.000823 U	<0.000838 U	<0.000853 U	<0.000973 U	<0.000822 U	<0.00108 UJ	<0.000896 U
1H,1H,2H,2H-Perfluorohexane Sulfonic Acid (4:2 FTS)	757124-72-4	NS	NS	NS	mg/kg	<0.000876 U	<0.000875 U	<0.000873 U	<0.00105 UJ	<0.000924 U	<0.00105 UJ	<0.000795 U	<0.000931 U	<0.000828 U	<0.000821 U	<0.000804 U	<0.000819 U	<0.000833 U	<0.000951 UJ	<0.000803 U	<0.00106 UJ	<0.000875 U
1H,1H,2H,2H-Perfluorooctane Sulfonic Acid (6:2 FTS)	27619-97-2	NS	NS	NS	mg/kg	<0.000888 U	<0.000886 U	<0.000884 U	<0.00106 UJ	<0.000936 U	<0.00106 UJ	<0.000805 U	<0.000943 UJ	<0.000839 U	<0.000831 U	<0.000815 U	<0.00083 U	<0.000844 U	<0.000963 U	<0.000814 U	<0.00107 UJ	<0.000887 U
2H,2H,3H,3H-Perfluorooctanoic Acid (5:3 FTCA)	914637-49-3	NS	NS	NS	mg/kg	<0.00584 U	<0.00583 U	<0.00582 U	<0.007 UJ	<0.00616 U	<0.007 UJ	<0.0053 U	<0.0062 U	<0.00552 U	<0.00547 U	<0.00536 U	<0.00546 U	<0.00555 U	<0.00634 U	<0.00535 U	<0.00704 U	<0.00584 U
3-Perfluoroheptyl Propanoic Acid (7:3 FTCA)	812-70-4	NS	NS	NS	mg/kg	<0.00584 U	<0.00583 U	<0.00582 U	<0.007 UJ	<0.00616 U	<0.007 UJ	<0.0053 U	<0.0062 U	<0.00552 U	<0.00547 U	<0.00536 U	<0.00546 U	<0.00555 U	<0.00634 U	<0.00535 U	<0.00704 U	<0.00584 U
3-Perfluoropropyl Propanoic Acid (3:3 FTCA)	356-02-5	NS	NS	NS	mg/kg	<0.00117 U	<0.00117 U	<0.00116 U	<0.0014 UJ	<0.00123 U	<0.0014 UJ	<0.00106 U	<0.00124 U	<0.0011 U	<0.00109 U	<0.00107 U	<0.00109 U	<0.00111 U	<0.00127 U	<0.00107 U	<0.00141 U	<0.00117 U
4,8-Dioxa-3H-perfluorononanoic Acid (ADONA)	919005-14-4	NS	NS	NS	mg/kg	<0.000883 U	<0.000882 U	<0.000879 U	<0.00106 UJ	<0.000931 U	<0.00106 UJ	<0.000801 U	<0.000938 U	<0.000835 U	<0.000827 U	<0.00081 UJ	<0.000825 U	<0.000839 UJ	<0.000958 U	<0.000809 U	<0.00106 U	<0.000882 U
9-Chlorohexadecafluoro-3-Oxanonane-1-Sulfonic Acid (9Cl-PF3ONS)	756426-58-1	NS	NS	NS	mg/kg	<0.000874 UJ	<0.000872 UJ	<0.00087 UJ	<0.00105 UJ	<0.000922 UJ	<0.00105 UJ	<0.000793 UJ	<0.000928 U	<0.000826 UJ	<0.000818 UJ	<0.000802 UJ	<0.000816 UJ	<0.00083 UJ	<0.000948 UJ	<0.000801 UJ	<0.00105 U	<0.000873 UJ
Hexafluoropropylene Oxide Dimer Acid (HFPO-DA)	13252-13-6	NS	NS	NS	mg/kg	<0.000934 U	<0.000933 U	<0.000931 U	<0.00112 UJ	<0.000986 U	<0.00112 UJ	<0.000848 UJ	<0.000993 U	<0.000883 U	<0.000875 U	<0.000857 UJ	<0.000873 U	<0.000888 UJ	<0.00101 U	<0.000857 U	<0.00113 U	<0.000934 U
N-ethyl Perfluorooctanesulfonamide (NEtFOSA)	4151-50-2	NS	NS	NS	mg/kg	0.00127	<0.000233 U	<0.000233 U	<0.00028 UJ	<0.000246 U	<0.00028 UJ	<0.000212 U	<0.000248 U	0.00018 J	0.000384	<0.000214 U	<0.000218 U	<0.000222 U	<0.000253 U	<0.000214 U	0.000823	<0.000233 U
N-ethyl Perfluorooctanesulfonamidoacetic Acid (NEtFOSAA)	2991-50-6	NS	NS	NS	mg/kg	0.0202	0.0011	<0.000582 U	<0.0007 UJ	<0.000616 U	<0.0007 UJ	<0.00053 U	0.00701	0.0041	0.00409	<0.000536 U	<0.000546 U	<0.000555 UJ	<0.000634 UJ	<0.000535 UJ	0.00973 J	0.00104
N-ethyl Perfluorooctanesulfonamidoethanol (NEtFOSE)	1691-99-2	NS	NS	NS	mg/kg	0.00276	<0.00233 U	<0.00233 U	<0.0028 UJ	<0.00246 U	<0.0028 UJ	<0.00212 U	0.00154 J	0.00072 J	0.000921 J	<0.00214 U	<0.00218 U	<0.00222 U	<0.00253 U	<0.00214 U	<0.00281 U	<0.00233 U
N-methyl Perfluorooctanesulfonamide (NMeFOSA)	31506-32-8	NS	NS	NS	mg/kg	<0.000234 U	<0.000233 U	<0.000233 U	<0.00028 UJ	<0.000246 U	<0.00028 UJ	<0.000212 U	<0.000248 U	<0.000221 U	<0.000219 U	<0.000214 U	<0.000218 U	<0.000222 U	<0.000253 U	<0.000214 U	<0.000281 U	<0.000233 U
N-methyl Perfluorooctanesulfonamidoacetic Acid (NMeFOSAA)	2355-31-9	NS	NS	NS	mg/kg	0.00133	0.000131 J	<0.000233 U	<0.00028 UJ	<0.000246 UJ	<0.00028 UJ	<0.000212 U	0.0013	0.00093	0.000392	<0.000214 UJ	<0.000218 U	<0.000222 UJ	<0.000253 UJ	<0.000214 U	0.00131 J	0.000101 J
N-methyl Perfluorooctanesulfonamidoethanol (NMeFOSE)	24448-09-7	NS	NS	NS	mg/kg	<0.00234 U	<0.00233 U	<0.00233 U	<0.0028 UJ	<0.00246 U	<0.0028 UJ	<0.00212 U	<0.00248 U	<0.00221 U	<0.00219 U	<0.00214 U	<0.00218 U	<0.00222 U	<0.00253 U	<0.00214 U	<0.00281 U	<0.00233 U
Nonafluoro-3,6-dioxaheptanoic Acid (NFDHA)	151772-58-6	NS	NS	NS	mg/kg	<0.000467 UJ	<0.000466 U	<0.000465 U	<0.00056 UJ	<0.000493 UJ	<0.00056 UJ	<0.000424 U	<0.000496 U	<0.000442 UJ	<0.000438 UJ	<0.000429 UJ	<0.000437 U	<0.000444 UJ	<0.000507 UJ	<0.000428 UJ	<0.000563 U	<0.000467 UJ
Perfluoro(2-ethoxyethane)sulfonic Acid (PFEESA)	113507-82-7	NS	NS	NS	mg/kg	<0.000416 U	<0.000415 U	<0.000414 U	<0.000499 UJ	<0.000439 U	<0.000499 UJ	<0.000377 U	<0.000442 U	<0.000393 U	<0.000389 U	<0.000382 U	<0.000389 U	<0.000395 U	<0.000451 U	<0.000381 U	<0.000501 U	<0.000415 U
Perfluoro-3-methoxypropanoic Acid (PFMPA)	377-73-1	NS	NS	NS	mg/kg	<0.000467 U	<0.000466 U	<0.000465 U	<0.00056 UJ	<0.000493 U	<0.00056 UJ	<0.000424 U	<0.000496 UJ	<0.000442 U	<0.000438 U	<0.000429 U	<0.000437 U	<0.000444 U	<0.000507 U	<0.000428 U	<0.000563 UJ	<0.000467 U
Perfluoro-4-methoxybutanoic Acid (PFMBA)	863090-89-5	NS	NS	NS	mg/kg	<0.000467 U	<0.000466 U	<0.000465 U	<0.00056 UJ	<0.000493 U	<0.00056 UJ	<0.000424 U	<0.000496 U	<0.000442 U	<0.000438 U	<0.000429 U	<0.000437 U	<0.000444 U	<0.000507 U	<0.000428 U	<0.000563 U	<0.000467 U
Perfluorobutanesulfonic Acid (PFBS)	375-73-5	NS	NS	NS	mg/kg	<0.000207 U	<0.000206 U	<0.000206 U	<0.000248 UJ	<0.000218 U	<0.000248 UJ	<0.000188 U	<0.00022 U	<0.000195 U	<0.000194 U	<0.00019 U	<0.000193 U	<0.000197 U	<0.000224 U	<0.00019 U	<0.000249 U	<0.000207 U
Perfluorobutanoic Acid (PFBA)	375-22-4	NS	NS	NS	mg/kg	<0.000934 U	<0.000933 U	<0.000931 U	0.000315 J	<0.000986 U	<0.00112 UJ	<0.000848 U	<0.000993 U	<0.000883 U	<0.000875 U	<0.000857 U	<0.000873 U	<0.000888 U	<0.00101 U	<0.000857 U	<0.00113 U	<0.000934 U
Perfluorodecanesulfonic Acid (PFDS)	335-77-3	NS	NS	NS	mg/kg	<0.000225 U	<0.000225 U	<0.000225 U	<0.00027 UJ	<0.000238 U	<0.00027 UJ	<0.000204 U	<0.00024 U	<0.000213 U	<0.000211 U	<0.000207 U	<0.000211 U	<0.000214 U	<0.000245 U	<0.000207 U	<0.000272 U	<0.000225 U
Perfluorodecanoic Acid (PFDA)	335-76-2	NS	NS	NS	mg/kg	0.000179 J	0.000103 J	0.000107 J	<0.00028 UJ	<0.000246 U	<0.00028 UJ	<0.000212 U	<0.000248 U	0.000461	0.0000981 J	<0.000214 UJ	<0.000218 U	<0.000222 U	<0.000253 UJ	<0.000214 U	<0.000281 U	<0.000233 U
Perfluorododecanesulfonic Acid (PFDoS)	79780-39-5	NS	NS	NS	mg/kg	<0.000227 U	<0.000226 U	<0.000226 U	<0.000272 UJ	<0.000239 U	<0.000272 UJ	<0.000206 U	<0.000241 U	<0.000214 U	<0.000212 U	<0.000208 U	<0.000212 U	<0.000215 U	<0.000246 U	<0.000208 U	<0.000273 U	<0.000226 U
Perfluorododecanoic Acid (PFDoA)	307-55-1	NS	NS	NS	mg/kg	<0.000234 U	<0.000233 U	<0.000233 U	<0.00028 UJ	<0.000246 U	<0.00028 UJ	<0.000212 U	<0.000248 U	0.000177 J	<0.000219 U	<0.000214 U	<0.000218 U	<0.000222 U	<0.000253 U	<0.000214 U	<0.000281 U	<0.000233 U
Perfluoroheptanesulfonic Acid (PFHpS)	375-92-8	NS	NS	NS	mg/kg	<0.000234 U	<0.000233 U	<0.000233 U	<0.00028 UJ	<0.000246 U	<0.00028 UJ	<0.000212 U	<0.000248 U	<0.000221 U	<0.000219 U	<0.000214 U	<0.000218 U	<0.000222 U	<0.000253 U	<0.000214 U	<0.000281 U	<0.000233 U
Perfluoroheptanoic Acid (PFHpA)	375-85-9	NS	NS	NS	mg/kg	<0.000234 U	<0.000233 U	<0.000233 U	<0.00028 UJ	<0.000246 U	<0.00028 UJ	<0.000212 U	<0.000248 U	<0.000221 U	<0.000219 U	<0.000214 U	<0.000218 U	<0.000222 U	<0.000253 U	<0.000214 U	<0.000281 U	<0.000233 U
Perfluorohexanesulfonic Acid (PFHxS)	355-46-4	NS	NS	NS	mg/kg	0.000116 J	0.000409	0.000685	<0.000256 UJ	<0.000225 U	<0.000256 UJ	<0.000194 U	<0.000227 U	0.000135 J	<0.0002 U	0.000206	0.000134 J	<0.000203 U	<0.000232 U	<0.000196 U	<0.000257 U	0.000256
Perfluorohexanoic Acid (PFHxA)	307-24-4	NS	NS	NS	mg/kg	<0.000234 U	0.0000724 J	<0.000233 U	<0.00028 UJ	<0.000246 U	<0.00028 UJ	<0.000212 U	<0.000248 U	0.000149 J	0.0000717 J	<0.000214 U	<0.000218 U	<0.000222 U	<0.000253 U	<0.000214 U	<0.000281 U	<0.000233 U
Perfluorononanesulfonic Acid (PFNS)	68259-12-1	NS	NS	NS	mg/kg	<0.000224 U	<0.000224 U	<0.000223 U	<0.000269 UJ	<0.000237 U	<0.000269 UJ	<0.000203 U	<0.000238 U	<0.000212 U	<0.00021 U	<0.000206 U	<0.00021 U	<0.000213 UJ	<0.000243 UJ	<0.000206 UJ	<0.00027 U	<0.000224 U
Perfluorononanoic Acid (PFNA)	375-95-1	NS	NS	NS	mg/kg	<0.000234 U	<0.000233 U	<0.000233 U	<0.00028 UJ	<0.000246 U	<0.00028 UJ	<0.000212 U	<0.000248 U	0.000179 J	<0.000219 U	<0.000214 U	<0.000218 U	<0.000222 UJ	<0.000253 U	<0.000214 U	<0.000281 U	<0.000233 U
Perfluorooctanesulfonamide (PFOSA)	754-91-6	NS	NS	NS	mg/kg	0.00159	0.000188 J	0.00018 J	<0.00028 UJ	<0.000246 U	<0.00028 UJ	<0.000212 U	0.000306	0.00064	0.00105	<0.000214 U	0.000106 J	<0.000222 UJ	<0.000253 U	<0.000214 UJ	0.00113	0.000295
Perfluorooctanesulfonic Acid (PFOS)	1763-23-1	**0.00088**	0.001	0.044	mg/kg	**0.00653**	**0.00166**	**0.00281**	<0.00026 UJ	<0.000229 U	<0.000261 UJ	0.000191 J	**0.00174**	**0.00328**	**0.00375**	**0.00126**	**0.000883**	0.000216	0.000233 J	0.000172 J	**0.00498**	**0.00581**
Perfluorooctanoic Acid (PFOA)	335-67-1	**0.00066**	0.0008	0.033	mg/kg	0.000594	0.000366	0.00041	0.000246 J	0.000167 J	0.000224 J	<0.000212 U	<0.000248 U	0.000635	0.000326	0.000233	0.000145 J	<0.000222 U	0.000189 J	<0.000214 U	0.000266 J	0.000276
Perfluoropentanesulfonic Acid (PFPeS)	2706-91-4	NS	NS	NS	mg/kg	<0.00022 U	<0.000219 U	<0.000219 U	<0.000263 UJ	<0.000232 U	<0.000263 UJ	<0.000199 U	<0.000233 U	<0.000208 U	<0.000206 U	<0.000202 U	<0.000205 U	<0.000209 U	<0.000238 U	<0.000201 U	<0.000265 U	<0.000219 U
Perfluoropentanoic Acid (PFPeA)	2706-90-3	NS	NS	NS	mg/kg	0.000107 J	<0.000466 U	<0.000465 U	<0.00056 UJ	<0.000493 U	<0.00056 UJ	<0.000424 U	<0.000496 U	0.000194 J	<0.000438 U	<0.000429 U	<0.000437 U	<0.000444 U	<0.000507 U	<0.000428 U	<0.000563 U	<0.000467 U
Perfluorotetradecanoic Acid (PFTeDA)	376-06-7	NS	NS	NS	mg/kg	<0.000234 U	<0.000233 U	<0.000233 U	<0.00028 UJ	<0.000246 U	<0.00028 UJ	<0.000212 U	<0.000248 U	<0.000221 U	<0.000219 U	<0.000214 U	<0.000218 U	<0.000222 UJ	<0.000253 UJ	<0.000214 UJ	<0.000281 U	<0.000233 U
Perfluorotridecanoic Acid (PFTrDA)	72629-94-8	NS	NS	NS	mg/kg	<0.000234 U	<0.000233 U	<0.000233 U	<0.00028 UJ	<0.000246 U	<0.00028 UJ	<0.000212 U	<0.000248 U	<0.000221 U	<0.000219 U	<0.000214 U	<0.000218 U	<0.000222 UJ	<0.000253 UJ	<0.000214 UJ	<0.000281 U	<0.000233 U
Perfluoroundecanoic Acid (PFUnA)	2058-94-8	NS	NS	NS	mg/kg	<0.000234 U	<0.000233 U	<0.000233 U	<0.00028 UJ	<0.000246 U	<0.00028 UJ	<0.000212 U	<0.000248 U	<0.000221 U	<0.000219 U	<0.000214 U	<0.000218 U	<0.000222 U	<0.000253 UJ	<0.000214 U	<0.000281 U	<0.000233 U
General Chemistry																						
Solids, Percent	SOLID	NS	NS	NS	Percent	85.6	85.8	86	71.4	81.2	71.4	94.4	80.1	90.6	91.2	93.3	91.6	89.9	78.6	93.2	70.5	85.7

Table 2
Site Management Plan
Soil Sample Analytical Results

12074 Flatlands Avenue p/o Lot 1 Site
Brooklyn, New York
BCP Site No. C224353
Langan Project No.: 100688803

Analyte	CAS Number	NYSDEC Part 375 Unrestricted Use SCOs	NYSDEC Part 375 Protection of Groundwater SCOs	NYSDEC Part 375 Restricted Use Restricted-Residential SCOs	Location	PE67	PE68	PE68	PE69	PE70	PE71	PE72	PE73	PE74	PE75	PE76	PE77	PE77	PE78	PE79	PE80	PE81
					Sample Name	PE67_20	PE68_29	DUP_20251028	PE69_20	PE70_20	PE71_20	PE72_19	PE73_20	PE74_20	PE75_19.5	PE76_19.5	PE77_19.5	PE77_20.5	PE78_19.5	PE79_20	PE80_19	PE81_20
					Sample Date	09/17/2025	10/28/2025	10/28/2025	10/01/2025	09/23/2025	09/23/2025	09/17/2025	12/05/2025	11/19/2025	09/23/2025	09/23/2025	10/01/2025	10/14/2025	09/23/2025	09/23/2025	09/17/2025	12/05/2025
					Sample Elevation	20	29	29	20	20	20	19	20	20	19.5	19.5	19.5	20.5	19.5	20	19	20
					Unit	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result
Volatile Organic Compounds																						
1,1,1,2-Tetrachloroethane	630-20-6	NS	NS	NS	mg/kg	NA	<0.034 U	<0.05 U	<0.025 U	NA	NA	NA	<0.006 U	<0.0059 U	NA	NA	<0.024 U	<0.028 U	NA	NA	NA	<0.0059 U
1,1,1-Trichloroethane	71-55-6	0.68	0.68	100	mg/kg	<0.0066 U	<0.0084 U	<0.012 U	<0.0063 U	<0.0056 U	<0.0061 U	<0.0049 U	<0.006 U	<0.0059 U	<0.0058 U	<0.0054 U	<0.0061 U	<0.0071 U	<0.0056 U	<0.0066 U	<0.0055 U	<0.0059 U
1,1,2,2-Tetrachloroethane	79-34-5	NS	NS	NS	mg/kg	<0.0066 U	<0.0084 U	<0.012 U	<0.0063 U	<0.0056 U	<0.0061 U	<0.0049 U	<0.006 U	<0.0059 U	<0.0058 U	<0.0054 U	<0.0061 U	<0.57 U	<0.0056 U	<0.0066 U	<0.0055 U	<0.0059 U
1,1,2-Trichloro-1,2,2-Trifluoroethane	76-13-1	NS	NS	NS	mg/kg	<0.0066 U	<0.0084 U	<0.012 U	<0.0063 U	<0.0056 U	<0.0061 U	<0.0049 U	<0.006 U	<0.0059 U	<0.0058 U	<0.0054 U	<0.0061 U	<0.0071 U	<0.0056 U	<0.0066 U	<0.0055 U	<0.0059 U
1,1,2-Trichloroethane	79-00-5	NS	NS	NS	mg/kg	<0.0066 U	<0.0084 U	<0.012 U	<0.0063 U	<0.0056 U	<0.0061 U	<0.0049 U	<0.006 U	<0.0059 U	<0.0058 U	<0.0054 U	<0.0061 U	<0.0071 U	<0.0056 U	<0.0066 U	<0.0055 U	<0.0059 U
1,1-Dichloroethane	75-34-3	0.27	0.27	47	mg/kg	<0.0066 U	<0.0084 U	<0.012 U	<0.0063 U	<0.0056 U	<0.0061 U	<0.0049 U	<0.006 U	<0.0059 U	<0.0058 U	<0.0054 U	<0.0061 U	<0.0071 U	<0.0056 U	<0.0066 U	<0.0055 U	<0.0059 U
1,1-Dichloroethene	75-35-4	0.24	0.33	0.98	mg/kg	<0.0066 U	<0.0084 U	<0.012 U	<0.0063 U	<0.0056 U	<0.0061 U	<0.0049 U	<0.006 U	<0.0059 U	<0.0058 U	<0.0054 U	<0.0061 U	<0.0071 U	<0.0056 U	<0.0066 U	<0.0055 U	<0.0059 U
1,1-Dichloropropene	563-58-6	NS	NS	NS	mg/kg	NA	NA	NA	NA	NA	NA	NA	<0.006 U	<0.0059 U	NA	NA	NA	NA	NA	NA	NA	<0.0059 U
1,2,3-Trichlorobenzene	87-61-6	NS	NS	NS	mg/kg	<0.0066 U	<0.0084 U	<0.012 U	<0.0063 U	<0.0056 U	<0.0061 U	<0.0049 U	<0.006 U	<0.0059 U	<0.0058 U	<0.0054 U	<0.0061 U	<0.57 U	<0.0056 U	<0.0066 U	<0.0055 U	<0.0059 U
1,2,3-Trichloropropane	96-18-4	NS	NS	NS	mg/kg	NA	<0.0084 U	<0.012 U	<0.0063 U	NA	NA	NA	<0.006 U	<0.0059 U	NA	NA	<0.0061 U	<0.57 U	NA	NA	NA	<0.0059 U
1,2,4-Trichlorobenzene	120-82-1	NS	NS	NS	mg/kg	<0.0066 U	<0.0084 U	<0.012 U	<0.0063 U	<0.0056 U	<0.0061 U	<0.0049 U	<0.006 U	<0.0059 U	<0.0058 U	<0.0054 U	<0.0061 U	<0.57 U	<0.0056 U	<0.0066 U	<0.0055 U	<0.0059 U
1,2,4-Trimethylbenzene	95-63-6	5.9	5.9	100	mg/kg	<0.0066 U	<0.0084 U	<0.012 U	<0.0063 U	<0.0056 U	<0.0061 U	<0.0049 U	<0.006 U	<0.0059 U	<0.0058 U	<0.0054 U	<0.0061 U	<0.57 U	<0.0056 U	<0.0066 U	<0.0055 U	<0.0059 U
1,2-Dibromo-3-Chloropropane	96-12-8	NS	NS	NS	mg/kg	<0.0066 U	<0.0084 U	<0.012 U	<0.0063 U	<0.0056 U	<0.0061 U	<0.0049 U	<0.006 U	<0.0059 U	<0.0058 U	<0.0054 U	<0.0061 U	<0.57 U	<0.0056 U	<0.0066 U	<0.0055 U	<0.0059 U
1,2-Dibromoethane (Ethylene Dibromide)	106-93-4	NS	NS	NS	mg/kg	<0.0066 U	<0.0084 U	<0.012 U	<0.0063 U	<0.0056 U	<0.0061 U	<0.0049 U	<0.006 U	<0.0059 U	<0.0058 U	<0.0054 U	<0.0061 U	<0.0071 U	<0.0056 U	<0.0066 U	<0.0055 U	<0.0059 U
1,2-Dichlorobenzene	95-50-1	1.1	1.1	100	mg/kg	<0.0066 U	<0.0084 U	<0.012 U	<0.0063 U	<0.0056 U	<0.0061 U	<0.0049 U	<0.006 U	<0.0059 U	<0.0058 U	<0.0054 U	<0.0061 U	<0.57 U	<0.0056 U	<0.0066 U	<0.0055 U	<0.0059 U
1,2-Dichloroethane	107-06-2	0.02	0.02	5.8	mg/kg	<0.0066 U	<0.0084 U	<0.012 U	<0.0063 U	<0.0056 U	<0.0061 U	<0.0049 U	<0.006 U	<0.0059 U	<0.0058 U	<0.0054 U	<0.0061 U	<0.0071 U	<0.0056 U	<0.0066 U	<0.0055 U	<0.0059 U
1,2-Dichloropropane	78-87-5	NS	NS	NS	mg/kg	<0.0066 U	<0.0084 U	<0.012 U	<0.0063 U	<0.0056 U	<0.0061 U	<0.0049 U	<0.006 U	<0.0059 U	<0.0058 U	<0.0054 U	<0.0061 U	<0.0071 U	<0.0056 U	<0.0066 U	<0.0055 U	<0.0059 U
1,3,5-Trimethylbenzene (Mesitylene)	108-67-8	3.1	3.1	100	mg/kg	<0.0066 U	<0.0084 U	<0.012 U	<0.0063 U	<0.0056 U	<0.0061 U	<0.0049 U	<0.006 U	<0.0059 U	<0.0058 U	<0.0054 U	<0.0061 U	<0.57 U	<0.0056 U	<0.0066 U	<0.0055 U	<0.0059 U
1,3-Dichlorobenzene	541-73-1	2.6	2.6	38	mg/kg	<0.0066 U	<0.0084 U	<0.012 U	<0.0063 U	<0.0056 U	<0.0061 U	<0.0049 U	<0.006 U	<0.0059 U	<0.0058 U	<0.0054 U	<0.0061 U	<0.57 U	<0.0056 U	<0.0066 U	<0.0055 U	<0.0059 U
1,3-Dichloropropane	142-28-9	NS	NS	NS	mg/kg	NA	NA	NA	NA	NA	NA	NA	<0.006 U	<0.0059 U	NA	NA	NA	NA	NA	NA	NA	<0.0059 U
1,4-Dichlorobenzene	106-46-7	1.8	1.8	24	mg/kg	<0.0066 U	<0.0084 U	<0.012 U	<0.0063 U	<0.0056 U	<0.0061 U	<0.0049 U	<0.006 U	<0.0059 U	<0.0058 U	<0.0054 U	<0.0061 U	<0.57 U	<0.0056 U	<0.0066 U	<0.0055 U	<0.0059 U
1,4-Dioxane (P-Dioxane)	123-91-1	0.1	0.1	5.7	mg/kg	<0.099 U	NA	NA	NA	<0.084 U	<0.091 U	<0.073 U	NA	NA	<0.087 U	<0.081 U	NA	NA	<0.084 U	<0.099 U	<0.083 U	NA
2,2-Dichloropropane	594-20-7	NS	NS	NS	mg/kg	NA	NA	NA	NA	NA	NA	NA	<0.006 U	<0.0059 U	NA	NA	NA	NA	NA	NA	NA	<0.0059 U
2-Chlorotoluene	95-49-8	NS	NS	NS	mg/kg	NA	NA	NA	NA	NA	NA	NA	<0.006 U	<0.0059 U	NA	NA	NA	NA	NA	NA	NA	<0.0059 U
2-Hexanone (MBK)	591-78-6	NS	NS	NS	mg/kg	<0.033 U	<0.042 U	<0.062 U	<0.032 U	<0.028 U	<0.03 U	<0.024 U	<0.006 U	<0.0059 U	<0.029 U	<0.027 U	<0.031 U	<0.035 U	<0.028 U	<0.033 U	<0.028 U	<0.0059 U
4-Chlorotoluene	106-43-4	NS	NS	NS	mg/kg	NA	NA	NA	NA	NA	NA	NA	<0.006 U	<0.0059 U	NA	NA	NA	NA	NA	NA	NA	<0.0059 U
Acetone	67-64-1	**0.03**	0.03	100	mg/kg	<0.033 U	**0.07 S**	<0.05 U	<0.063 U	**0.07 S**	<0.03 U	<0.024 U	**0.072**	<0.012 U	<0.029 U	<0.027 U	<0.061 U	<0.05 U	0.025 JS	<0.033 U	<0.028 U	**0.093**
Acrolein	107-02-8	NS	NS	NS	mg/kg	NA	<0.0084 U	<0.012 U	<0.0063 U	NA	NA	NA	<0.012 U	<0.012 U	NA	NA	<0.0061 U	<0.0071 U	NA	NA	NA	<0.012 U
Acrylonitrile	107-13-1	NS	NS	NS	mg/kg	NA	<0.034 U	<0.05 U	<0.025 U	NA	NA	NA	<0.006 U	<0.0059 U	NA	NA	<0.024 U	<0.028 U	NA	NA	NA	<0.0059 U
Benzene	71-43-2	0.06	0.06	3.7	mg/kg	<0.0066 U	<0.0084 U	<0.012 U	<0.0063 U	0.00072 J	<0.0061 U	<0.0049 U	<0.006 U	<0.0059 U	<0.0058 U	<0.0054 U	<0.0061 U	<0.0071 U	<0.0056 U	<0.0066 U	<0.0055 U	<0.0059 U
Bromobenzene	108-86-1	NS	NS	NS	mg/kg	NA	NA	NA	NA	NA	NA	NA	<0.006 U	<0.0059 U	NA	NA	NA	NA	NA	NA	NA	<0.0059 U
Bromochloromethane	74-97-5	NS	NS	NS	mg/kg	<0.0066 U	<0.0084 U	<0.012 U	<0.0063 U	<0.0056 U	<0.0061 U	<0.0049 U	<0.006 U	<0.0059 U	<0.0058 U	<0.0054 U	<0.0061 U	<0.0071 U	<0.0056 U	<0.0066 U	<0.0055 U	<0.0059 U
Bromodichloromethane	75-27-4	NS	NS	NS	mg/kg	<0.0066 U	<0.0084 U	<0.012 U	<0.0063 U	<0.0056 U	<0.0061 U	<0.0049 U	<0.006 U	<0.0059 U	<0.0058 U	<0.0054 U	<0.0061 U	<0.0071 U	<0.0056 U	<0.0066 U	<0.0055 U	<0.0059 U
Bromoform	75-25-2	NS	NS	NS	mg/kg	<0.0066 U	<0.0084 U	<0.012 U	<0.0063 U	<0.0056 U	<0.0061 U	<0.0049 U	<0.006 U	<0.0059 U	<0.0058 U	<0.0054 U	<0.0061 U	<0.0071 U	<0.0056 U	<0.0066 U	<0.0055 U	<0.0059 U
Bromomethane	74-83-9	NS	NS	NS	mg/kg	<0.0066 U	<0.0084 U	<0.012 U	<0.0063 U	<0.0056 U	<0.0061 U	<0.0049 U	<0.006 U	<0.0059 U	<0.0058 U	<0.0054 U	<0.0061 U	<0.0071 U	<0.0056 U	<0.0066 U	<0.0055 U	<0.0059 U
Carbon Disulfide	75-15-0	NS	NS	NS	mg/kg	<0.0066 U	0.0026 J	0.0029 J	<0.0063 U	0.0073	<0.0061 U	<0.0049 U	<0.006 U	<0.0059 U	<0.0058 U	<0.0054 U	<0.0061 U	0.013	0.0013 J	<0.0066 U	<0.0055 U	<0.0059 U
Carbon Tetrachloride	56-23-5	0.76	0.76	7.1	mg/kg	<0.0066 U	<0.0084 U	<0.012 U	<0.0063 U	<0.0056 U	<0.0061 U	<0.0049 U	<0.006 U	<0.0059 U	<0.0058 U	<0.0054 U	<0.0061 U	<0.0071 U	<0.0056 U	<0.0066 U	<0.0055 U	<0.0059 U
Chlorobenzene	108-90-7	4.5	4.5	100	mg/kg	<0.0066 U	<0.0084 U	<0.012 U	<0.0063 U	<0.0056 U	<0.0061 U	<0.0049 U	<0.006 U	<0.0059 U	<0.0058 U	<0.0054 U	<0.0061 U	<0.0071 U	<0.0056 U	<0.0066 U	<0.0055 U	<0.0059 U
Chloroethane	75-00-3	NS	NS	NS	mg/kg	<0.0066 U	<0.0084 U	<0.012 U	<0.0063 U	<0.0056 U	<0.0061 U	<0.0049 U	<0.006 U	<0.0059 U	<0.0058 U	<0.0054 U	<0.0061 U	<0.0071 U	<0.0056 U	<0.0066 U	<0.0055 U	<0.0059 U
Chloroform	67-66-3	0.37	0.37	24	mg/kg	<0.0066 U	<0.0084 U	<0.012 U	<0.0063 U	<0.0056 U	<0.0061 U	<0.0049 U	<0.006 U	<0.0059 U	<0.0058 U	<0.0054 U	<0.0061 U	<0.0071 U	<0.0056 U	<0.0066 U	<0.0055 U	<0.0059 U
Chloromethane	74-87-3	NS	NS	NS	mg/kg	<0.0066 U	<0.0084 U	<0.012 U	<0.0063 U	<0.0056 U	<0.0061 U	<0.0049 U	<0.006 U	<0.0059 U	<0.0058 U	<0.0054 U	<0.0061 U	<0.0071 U	<0.0056 U	<0.0066 U	<0.0055 U	<0.0059 U
Cis-1,2-Dichloroethene	156-59-2	0.19	0.19	41	mg/kg	<0.0066 U	<0.0084 U	<0.012 U	<0.0063 U	<0.0056 U	<0.0061 U	<0.0049 U	<0.006 U	<0.0059 U	<0.0058 U	<0.0054 U	<0.0061 U	<0.0071 U	<0.0056 U	<0.0066 U	<0.0055 U	<0.0059 U
Cis-1,3-Dichloropropene	10061-01-5	NS	NS	NS	mg/kg	<0.0066 U	<0.0084 U	<0.012 U	<0.0063 U	<0.0056 U	<0.0061 U	<0.0049 U	<0.006 U	<0.0059 U	<0.0058 U	<0.0054 U	<0.0061 U	<0.0071 U	<0.0056 U	<0.0066 U	<0.0055 U	<0.0059 U
Cyclohexane	110-82-7	NS	NS	NS	mg/kg	<0.0066 U	<0.0084 U	<0.012 U	<0.0063 U	<0.0056 U	<0.0061 U	<0.0049 U	<0.006 U	<0.0059 U	<0.0058 U	<0.0054 U	<0.0061 U	0.0076	<0.0056 U	<0.0066 U	<0.0055 U	<0.0059 U
Cymene	99-87-6	NS	NS	NS	mg/kg	NA	<0.0084 U	0.0016 J	<0.0063 U	NA	NA	NA	<0.006 U	<0.0059 U	NA	NA	<0.0061 U	0.13 J	NA	NA	NA	<0.0059 U
Dibromochloromethane	124-48-1	NS	NS	NS	mg/kg	<0.0066 U	<0.0084 U	<0.012 U	<0.0063 U	<0.0056 U	<0.0061 U	<0.0049 U	<0.006 U	<0.0059 U	<0.0058 U	<0.0054 U	<0.0061 U	<0.0071 U	<0.0056 U	<0.0066 U	<0.0055 U	<0.0059 U
Dibromomethane	74-95-3	NS	NS	NS	mg/kg	NA	<0.0084 U	<0.012 U	<0.0063 U	NA	NA	NA	<0.006 U	<0.0059 U	NA	NA	<0.0061 U	<0.0071 U	NA	NA	NA	<0.0059 U
Dichlorodifluoromethane	75-71-8	NS	NS	NS	mg/kg	<0.0066 U	<0.0084 U	<0.012 U	<0.0063 U	<0.0056 U	<0.0061 U	<0.0049 U	<0.006 UJ	<0.0059 U	<0.0058 U	<0.0054 U	<0.0061 U	<0.0071 U	<0.0056 U	<0.0066 U	<0.0055 U	<0.0059 UJ
Ethylbenzene	100-41-4	1	1	76	mg/kg	<0.0066 U	<0.0084 U	<0.012 U	<0.0063 U	<0.0056 U	<0.0061 U	<0.0049 U	<0.006 U	<0.0059 U	<0.0058 U	<0.0054 U	<0.0061 U	<0.0071 U	<0.0056 U	<0.0066 U	<0.0055 U	<0.0059 U
Hexachlorobutadiene	87-68-3	NS	NS	NS	mg/kg	NA	<0.0084 U	<0.012 U	<0.0063 U	NA	NA	NA	<0.006 U	<0.0059 UJ	NA	NA	<0.0061 U	<0.57 U	NA	NA	NA	<0.0059 U
Isopropylbenzene (Cumene)	98-82-8	NS	NS	NS	mg/kg	<0.0066 U	<0.0084 U	<0.012 U	<0.0063 U	<0.0056 U	<0.0061 U	<0.0049 U	<0.006 U	<0.0059 U	<0.0058 U	<0.0054 U	<0.0061 U	<0.57 U	<0.0056 U	<0.0066 U	<0.0055 U	<0.0059 U
M,P-Xylene	179601-23-1	NS	NS	NS	mg/kg	<0.0066 U	<0.0084 U	<0.012 U	<0.0063 U	<0.0056 U	<0.0061 U	<0.0049 U	<0.012 U	<0.012 U	<0.0058 U	<0.0054 U	<0.0061 U	0.0014 J	<0.0056 U	<0.0066 U	<0.0055 U	<0.012 U
Methyl Acetate	79-20-9	NS	NS	NS	mg/kg	<0.066 U	<0.084 U	<0.12 U	<0.063 U	<0.056 U	<0.061 U	<0.049 U	0.015	<0.0059 U	<0.058 U	<0.054 U	<0.061 U	<0.071 U	<0.056 U	<0.066 U	<0.055 U	0.004 J
Methyl Ethyl Ketone (2-Butanone)	78-93-3	0.1	0.1	100	mg/kg	<0.04 U	0.024 J	<0.074 U	<0.038 U	0.013 J	<0.037 U	<0.029 U	0.0096	<0.0059 U	<0.035 U	<0.032 U	<0.037 U	<0.042 U	<0.034 U	<0.04 U	<0.033 U	0.013
Methyl Isobutyl Ketone (4-Methyl-2-Pentanone)	108-10-1	NS	NS	NS	mg/kg	<0.033 U	<0.042 U	<0.062 U	<0.032 U	<0.028 U	<0.03 U	<0.024 U	<0.006 U	<0.0059 U	<0.029 U	<0.027 U	<0.031 U	<0.035 U	<0.028 U	<0.033 U	<0.028 U	<0.0059 U
Methylcyclohexane	108-87-2	NS	NS	NS	mg/kg	<0.0066 U	<0.0084 U	<0.012 U	<0.0063 U	<0.0056 U	<0.0061 U	<0.0049 U	<0.006 U	<0.0059 U	<0.0058 U	<0.0054 U	<0.0061 U	<0.0071 U	<0.0056 U	<0.0066 U	<0.0055 U	<0.0059 U
Methylene Chloride	75-09-2	0.05	0.05	81	mg/kg	<0.0066 U	<0.042 U	<0.05 U	<0.032 U	<0.0056 U	<0.0061 U	<0.0049 U	<0.012 U	<0.012 U	<0.0058 U	<0.0054 U	<0.031 U	<0.035 U	<0.0056 U	<0.0066 U	<0.0055 U	<0.012 U
n-Butylbenzene	104-51-8	18	18	100	mg/kg	NA	<0.0084 U	<0.012 U	<0.0063 U	NA	NA	NA	<0.006 U	<0.0059 U	NA	NA	<0.0061 U	<0.57 U	NA	NA	NA	<0.0059 U
n-Propylbenzene	103-65-1	5	5	100	mg/kg	NA	<0.0084 U	<0.012 U	<0.0063 U	NA	NA	NA	<0.006 U	<0.0059 U	NA	NA	<0.0061 U	<0.57 U	NA	NA	NA	<0.0059 U
o-Xylene (1,2-Dimethylbenzene)	95-47-6	NS	NS	NS	mg/kg	<0.0066 U	<0.0084 U	<0.012 U	<0.0063 U	<0.0056 U	<0.0061 U	<0.0049 U	<0.006 U	<0.0059 U	<0.0058 U	<0.0054 U	<0.0061 U	<0.0071 U	<0.0056 U	<0.0066 U	<0.0055 U	<0.0059 U
Sec-Butylbenzene	135-98-8	25	25	100	mg/kg	NA	<0.0084 U	<0.012 U	<0.0063 U	NA	NA	NA	<0.006 U	<0.0059 U	NA	NA	<0.0061 U	<0.57 U	NA	NA	NA	<0.0059 U
Styrene	100-42-5	NS	NS	NS	mg/kg	<0.0066 U	<0.0084 U	<0.012 U	<0.0063 U	<0.0056 U	<0.0061 U	<0.0049 U	<0.006 U	<0.0059 U	<0.0058 U	<0.0054 U	<0.0061 U	<0.0071 U	<0.0056 U	<0.0066 U	<0.0055 U	<0.0059 U
T-Butylbenzene	98-06-6	11	11	100	mg/kg	NA	<0.0084 U	<0.012 U	<0.0063 U	NA	NA	NA	<0.006 U	<0.0059 U	NA	NA	<0.0061 U	<0.57 U	NA	NA	NA	<0.0059 U
Tert-Butyl Alcohol	75-65-0	NS	NS	NS	mg/kg	NA	<0.17 U	<0.25 U	<0.13 U	NA	NA	NA	<0.03 U	<0.03 U	NA	NA	<0.12 U	<0.14 U	NA	NA	NA	<0.03 U
Tert-Butyl Methyl Ether (MTBE)	1634-04-4	0.1	0.1	100	mg/kg	<0.013 U	<0.017 U	<0.025 U	<0.013 U	<0.011 U	<0.012 U	<0.0098 U	<0.006 U	<0.0059 U	<0.012 U	<0.011 U	<0.012 U	<0.014 U	<0.011 U	<0.013 U	<0.011 U	<0.0059 U
Tetrachloroethene (PCE)	127-18-4	1.3	1.3	18	mg/kg	<0.0066 U	<0.0084 U	<0.012 U	<0.0063 U	<0.0056 U	<0.0061 U	<0.0049 U	<0.006 U	<0.0059 U	<0.0058 U	<0.0054 U	<0.0061 U	<0.0071 U	<0.0056 U	<0.0066 U	<0.0055 U	<0.0059 U
Toluene	108-88-3	0.7	0.7	100	mg/kg	<0.0066 U	<0.0084 U	<0.012 U	<0.0063 U	<0.0056 U	<0.0061 U	<0.0049 U	<0.006 U	<0.0059 U	<0.0058 U	<0.0054 U	<0.0061 U	<0.0071 U	<0.0056 U	<0.0066 U	<0.0055 U	<0.0059 U
Total Xylenes	1330-20-7	0.26	1.2	100	mg/kg	NA	NA	NA	NA	NA	NA	NA	<0.018 U	<0.018 U	NA	NA	NA	NA	NA	NA	NA	<0.018 U
Trans-1,2-Dichloroethene	156-60-5	0.19	0.19	100	mg/kg	<0.0066 U	<0.0084 U	<0.012 U	<0.0063 U	<0.0056 U	<0.0061 U	<0.0049 U	<0.006 U	<0.0059 U	<0.0058 U	<0.0054 U	<0.0061 U	<0.0071 U	<0.0056 U	<0.0066 U	<0.0055 U	<0.0059 U
Trans-1,3-Dichloropropene	10061-02-6	NS	NS	NS	mg/kg	<0.0066 U	<0.0084 U	<0.012 U	<0.0063 U	<0.0056 U	<0.0061 U	<0.0049 U	<0.006 U	<0.0059 U	<0.0058 U	<0.0054 U	<0.0061 U	<0.0071 U	<0.0056 U	<0.0066 U	<0.0055 U	<0.0059 U
Trans-1,4-Dichloro-2-Butene	110-57-6	NS	NS	NS	mg/kg	NA	<0.017 U	<0.025 U	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
Trichloroethene (TCE)	79-01-6	0.47	0.47	6.4	mg/kg	<0.0066 U	<0.0084 U	<0.012 U	<0.0063 U	<0.0056 U	<0.0061 U	<0.0049 U	<0.006 U	<0.0059 U	<0.0058 U	<0.0054 U	<0.0061 U	<0.0071 U	<0.0056 U	<0.0066 U	<0.0055 U	<0.0059 U
Trichlorofluoromethane	75-69-4	NS	NS	NS	mg/kg	<0.0066 U	<0.0084 U	<0.012 U	<0.0063 U	<0.0056 U	<0.0061 U	<0.0049 U	<0.006 U	<0.0059 U	<0.0058 U	<0.0054 U	<0.0061 U	<0.0071 U	<0.0056 U	<0.0066 U	<0.0055 U	<0.0059 U
Vinyl Chloride	75-01-4	0.03	0.03	0.48	mg/kg	<0.0066 U	<0.0084 U	<0.012 U	<0.0063 U	<0.0056 U	<0.0061 U	<0.0049 U	<0.006 UJ	<0.0059 U	<0.0058 U	<0.0054 U	<0.0061 U	<0.0071 U	<0.0056 U	<0.0066 U	<0.0055 U	<0.0059 UJ

Table 2
Site Management Plan
Soil Sample Analytical Results

12074 Flatlands Avenue p/o Lot 1 Site
Brooklyn, New York
BCP Site No. C224353
Langan Project No.: 100688803

Analyte	CAS Number	NYSDEC Part 375 Unrestricted Use SCOs	NYSDEC Part 375 Protection of Groundwater SCOs	NYSDEC Part 375 Restricted Use Restricted-Residential SCOs	Location	PE67	PE68	PE68	PE69	PE70	PE71	PE72	PE73	PE74	PE75	PE76	PE77	PE77	PE78	PE79	PE80	PE81
					Sample Name	PE67_20	PE68_29	DUP_20251028	PE69_20	PE70_20	PE71_20	PE72_19	PE73_20	PE74_20	PE75_19.5	PE76_19.5	PE77_19.5	PE77_20.5	PE78_19.5	PE79_20	PE80_19	PE81_20
					Sample Date	09/17/2025	10/28/2025	10/28/2025	10/01/2025	09/23/2025	09/23/2025	09/17/2025	12/05/2025	11/19/2025	09/23/2025	09/23/2025	10/01/2025	10/14/2025	09/23/2025	09/23/2025	09/17/2025	12/05/2025
					Sample Elevation	20	29	29	20	20	20	19	20	20	19.5	19.5	19.5	20.5	19.5	20	19	20
					Unit	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result
Semi-Volatile Organic Compounds																						
1,2,4,5-Tetrachlorobenzene	95-94-3	NS	NS	NS	mg/kg	<0.189 U	<0.218 UJ	<0.292 UJ	<0.181 U	<0.2 U	<0.197 U	<0.19 U	<0.178 U	<0.172 U	<0.177 U	<0.179 U	<0.189 U	<0.194 U	<0.181 U	<0.183 U	<0.179 U	<0.178 U
1,2,4-Trichlorobenzene	120-82-1	NS	NS	NS	mg/kg	<0.0946 U	<0.109 UJ	<0.146 UJ	<0.0906 U	<0.0999 U	<0.0986 U	<0.0953 U	<0.0892 U	<0.0861 U	<0.0884 U	<0.0895 U	<0.0948 U	<0.097 U	<0.0905 U	<0.0917 U	<0.0898 U	<0.0889 U
1,2-Dichlorobenzene	95-50-1	1.1	1.1	100	mg/kg	<0.0946 U	<0.109 UJ	<0.146 UJ	<0.0906 U	<0.0999 U	<0.0986 U	<0.0953 U	<0.0892 U	<0.0861 U	<0.0884 U	<0.0895 U	<0.0948 U	<0.097 U	<0.0905 U	<0.0917 U	<0.0898 U	<0.0889 U
1,2-Diphenylhydrazine	122-66-7	NS	NS	NS	mg/kg	<0.0946 U	<0.109 UJ	<0.146 UJ	<0.0906 U	<0.0999 U	<0.0986 U	<0.0953 U	<0.0892 U	<0.0861 U	<0.0884 U	<0.0895 U	<0.0948 U	<0.097 U	<0.0905 U	<0.0917 U	<0.0898 U	<0.0889 U
1,3-Dichlorobenzene	541-73-1	2.6	2.6	38	mg/kg	<0.0946 U	<0.109 UJ	<0.146 UJ	<0.0906 U	<0.0999 U	<0.0986 U	<0.0953 U	<0.0892 U	<0.0861 U	<0.0884 U	<0.0895 U	<0.0948 U	<0.097 U	<0.0905 U	<0.0917 U	<0.0898 U	<0.0889 U
1,4-Dichlorobenzene	106-46-7	1.8	1.8	24	mg/kg	<0.0946 U	<0.109 UJ	<0.146 UJ	<0.0906 U	<0.0999 U	<0.0986 U	<0.0953 U	<0.0892 U	<0.0861 U	<0.0884 U	<0.0895 U	<0.0948 U	<0.097 U	<0.0905 U	<0.0917 U	<0.0898 U	<0.0889 U
1,4-Dioxane (P-Dioxane)	123-91-1	0.1	0.1	5.7	mg/kg	<0.0189 U	<0.02 U	<0.02 U	<0.0194 U	<0.0196 U	<0.0198 U	<0.0185 U	<0.0196 U	<0.0198 U	<0.0198 U	<0.0198 U	<0.0194 U	<0.0189 U	<0.0198 U	<0.0194 U	<0.0198 U	<0.0194 U
2,3,4,6-Tetrachlorophenol	58-90-2	NS	NS	NS	mg/kg	<0.189 U	<0.218 UJ	<0.292 UJ	<0.181 U	<0.2 U	<0.197 U	<0.19 U	<0.178 U	<0.172 U	<0.177 U	<0.179 U	<0.189 UJ	<0.194 U	<0.181 U	<0.183 U	<0.179 U	<0.178 U
2,4,5-Trichlorophenol	95-95-4	NS	NS	NS	mg/kg	<0.0946 U	<0.109 UJ	<0.146 UJ	<0.0906 U	<0.0999 U	<0.0986 U	<0.0953 U	<0.0892 U	<0.0861 U	<0.0884 U	<0.0895 U	<0.0948 UJ	<0.097 U	<0.0905 U	<0.0917 U	<0.0898 U	<0.0889 U
2,4,6-Trichlorophenol	88-06-2	NS	NS	NS	mg/kg	<0.0946 U	<0.109 UJ	<0.146 UJ	<0.0906 U	<0.0999 U	<0.0986 U	<0.0953 U	<0.0892 U	<0.0861 U	<0.0884 U	<0.0895 U	<0.0948 UJ	<0.097 U	<0.0905 U	<0.0917 U	<0.0898 U	<0.0889 U
2,4-Dichlorophenol	120-83-2	NS	NS	NS	mg/kg	<0.0946 U	<0.109 UJ	<0.146 UJ	<0.0906 U	<0.0999 U	<0.0986 U	<0.0953 U	<0.0892 U	<0.0861 U	<0.0884 U	<0.0895 U	<0.0948 UJ	<0.097 U	<0.0905 U	<0.0917 U	<0.0898 U	<0.0889 U
2,4-Dimethylphenol	105-67-9	NS	NS	NS	mg/kg	<0.0946 U	<0.109 UJ	<0.146 UJ	<0.0906 U	<0.0999 U	<0.0986 U	<0.0953 U	<0.0892 U	<0.0861 U	<0.0884 U	<0.0895 U	<0.0948 UJ	<0.097 U	<0.0905 U	<0.0917 U	<0.0898 U	<0.0889 U
2,4-Dinitrophenol	51-28-5	NS	NS	NS	mg/kg	<0.189 U	<0.218 UJ	<0.292 UJ	<0.181 U	<0.2 U	<0.197 U	<0.19 U	<0.178 UJ	<0.172 U	<0.177 U	<0.179 U	<0.189 UJ	<0.194 U	<0.181 U	<0.183 U	<0.179 U	<0.178 UJ
2,4-Dinitrotoluene	121-14-2	NS	NS	NS	mg/kg	<0.0946 U	<0.109 UJ	<0.146 UJ	<0.0906 U	<0.0999 U	<0.0986 U	<0.0953 U	<0.0892 U	<0.0861 U	<0.0884 U	<0.0895 U	<0.0948 UJ	<0.097 U	<0.0905 U	<0.0917 U	<0.0898 U	<0.0889 U
2,6-Dinitrotoluene	606-20-2	NS	NS	NS	mg/kg	<0.0946 U	<0.109 UJ	<0.146 UJ	<0.0906 U	<0.0999 U	<0.0986 U	<0.0953 U	<0.0892 U	<0.0861 U	<0.0884 U	<0.0895 U	<0.0948 UJ	<0.097 U	<0.0905 U	<0.0917 U	<0.0898 U	<0.0889 U
2-Chloronaphthalene	91-58-7	NS	NS	NS	mg/kg	<0.0946 U	<0.109 UJ	<0.146 UJ	<0.0906 U	<0.0999 U	<0.0986 U	<0.0953 U	<0.0892 U	<0.0861 U	<0.0884 U	<0.0895 U	<0.0948 U	<0.097 U	<0.0905 U	<0.0917 U	<0.0898 U	<0.0889 U
2-Chlorophenol	95-57-8	NS	NS	NS	mg/kg	<0.0946 U	<0.109 UJ	<0.146 UJ	<0.0906 U	<0.0999 U	<0.0986 U	<0.0953 U	<0.0892 U	<0.0861 U	<0.0884 U	<0.0895 U	<0.0948 UJ	<0.097 U	<0.0905 U	<0.0917 U	<0.0898 U	<0.0889 U
2-Methylnaphthalene	91-57-6	NS	NS	NS	mg/kg	<0.0946 U	<0.109 UJ	<0.146 UJ	0.0666 JD	<0.0999 U	0.0741 JD	0.219 D	<0.0892 U	<0.0861 U	<0.0884 U	<0.0895 U	0.097 D	<0.097 U	0.0485 JD	0.0843 JD	<0.0898 U	<0.0889 U
2-Methylphenol (o-Cresol)	95-48-7	0.33	0.33	100	mg/kg	<0.0946 U	<0.109 UJ	<0.146 UJ	<0.0906 U	<0.0999 U	<0.0986 U	<0.0953 U	<0.0892 U	<0.0861 U	<0.0884 U	<0.0895 U	<0.0948 UJ	<0.097 U	<0.0905 U	<0.0917 U	<0.0898 U	<0.0889 U
2-Nitroaniline	88-74-4	NS	NS	NS	mg/kg	<0.189 U	<0.218 UJ	<0.292 UJ	<0.181 U	<0.2 U	<0.197 U	<0.19 U	<0.178 U	<0.172 U	<0.177 U	<0.179 U	<0.189 U	<0.194 U	<0.181 U	<0.183 U	<0.179 U	<0.178 U
2-Nitrophenol	88-75-5	NS	NS	NS	mg/kg	<0.0946 U	<0.109 UJ	<0.146 UJ	<0.0906 U	<0.0999 U	<0.0986 U	<0.0953 U	<0.0892 U	<0.0861 U	<0.0884 U	<0.0895 U	<0.0948 UJ	<0.097 U	<0.0905 U	<0.0917 U	<0.0898 U	<0.0889 U
3 & 4 Methylphenol (m&p Cresol)	65794-96-9	**0.33**	0.33	100	mg/kg	<0.0946 U	<0.109 UJ	<0.146 UJ	0.0579 JD	<0.0999 U	<0.0986 U	<0.0953 U	<0.0892 U	<0.0861 U	<0.0884 U	<0.0895 U	<0.0948 UJ	<0.097 U	<0.0905 U	<0.0917 U	<0.0898 U	<0.0889 U
3,3'-Dichlorobenzidine	91-94-1	NS	NS	NS	mg/kg	<0.0946 U	<0.109 UJ	<0.146 UJ	<0.0906 U	<0.0999 U	<0.0986 U	<0.0953 U	<0.0892 U	<0.0861 U	<0.0884 U	<0.0895 U	<0.0948 U	<0.097 U	<0.0905 U	<0.0917 U	<0.0898 U	<0.0889 U
3-Nitroaniline	99-09-2	NS	NS	NS	mg/kg	<0.189 U	<0.218 UJ	<0.292 UJ	<0.181 U	<0.2 U	<0.197 U	<0.19 U	<0.178 U	<0.172 U	<0.177 U	<0.179 U	<0.189 U	<0.194 U	<0.181 U	<0.183 U	<0.179 U	<0.178 U
4,6-Dinitro-2-Methylphenol	534-52-1	NS	NS	NS	mg/kg	<0.189 U	<0.218 UJ	<0.292 UJ	<0.181 U	<0.2 U	<0.197 U	<0.19 U	<0.178 UJ	<0.172 U	<0.177 U	<0.179 U	<0.189 UJ	<0.194 U	<0.181 U	<0.183 U	<0.179 U	<0.178 UJ
4-Bromophenyl Phenyl Ether	101-55-3	NS	NS	NS	mg/kg	<0.0946 U	<0.109 UJ	<0.146 UJ	<0.0906 U	<0.0999 U	<0.0986 U	<0.0953 U	<0.0892 U	<0.0861 U	<0.0884 U	<0.0895 U	<0.0948 U	<0.097 U	<0.0905 U	<0.0917 U	<0.0898 U	<0.0889 U
4-Chloro-3-Methylphenol	59-50-7	NS	NS	NS	mg/kg	<0.0946 U	<0.109 UJ	<0.146 UJ	<0.0906 U	<0.0999 U	<0.0986 U	<0.0953 U	<0.0892 U	<0.0861 U	<0.0884 U	<0.0895 U	<0.0948 UJ	<0.097 U	<0.0905 U	<0.0917 U	<0.0898 U	<0.0889 U
4-Chloroaniline	106-47-8	NS	NS	NS	mg/kg	<0.0946 U	<0.109 UJ	<0.146 UJ	<0.0906 U	<0.0999 U	<0.0986 U	<0.0953 U	<0.0892 U	<0.0861 U	<0.0884 U	<0.0895 U	<0.0948 U	<0.097 U	<0.0905 U	<0.0917 U	<0.0898 U	<0.0889 U
4-Chlorophenyl Phenyl Ether	7005-72-3	NS	NS	NS	mg/kg	<0.0946 U	<0.109 UJ	<0.146 UJ	<0.0906 U	<0.0999 U	<0.0986 U	<0.0953 U	<0.0892 U	<0.0861 U	<0.0884 U	<0.0895 U	<0.0948 U	<0.097 U	<0.0905 U	<0.0917 U	<0.0898 U	<0.0889 U
4-Nitroaniline	100-01-6	NS	NS	NS	mg/kg	<0.189 U	<0.218 UJ	<0.292 UJ	<0.181 U	<0.2 U	<0.197 U	<0.19 U	<0.178 U	<0.172 U	<0.177 U	<0.179 U	<0.189 U	<0.194 U	<0.181 U	<0.183 U	<0.179 U	<0.178 U
4-Nitrophenol	100-02-7	NS	NS	NS	mg/kg	<0.189 U	<0.218 UJ	<0.292 UJ	<0.181 U	<0.2 U	<0.197 U	<0.19 U	<0.178 U	<0.172 U	<0.177 U	<0.179 U	<0.189 UJ	<0.194 U	<0.181 U	<0.183 U	<0.179 U	<0.178 U
Acenaphthene	83-32-9	20	98	100	mg/kg	0.0499 JD	0.0558 J	0.084 J	<0.0906 U	<0.0999 U	0.0851 JD	0.137 D	<0.0892 U	<0.0861 U	<0.0884 U	<0.0895 U	0.156 D	0.0705 JD	0.0782 JD	0.211 D	<0.0898 U	<0.0889 U
Acenaphthylene	208-96-8	100	365	100	mg/kg	<0.0946 U	<0.109 UJ	<0.146 UJ	<0.0906 U	<0.0999 U	0.078 JD	0.0899 JD	<0.0892 U	<0.0861 U	<0.0884 U	<0.0895 U	0.212 D	<0.097 U	0.103 D	0.0704 JD	<0.0898 U	<0.0889 U
Acetophenone	98-86-2	NS	NS	NS	mg/kg	<0.0946 U	<0.109 UJ	<0.146 UJ	<0.0906 U	<0.0999 U	<0.0986 U	<0.0953 U	<0.0892 U	<0.0861 U	<0.0884 U	<0.0895 U	<0.0948 U	<0.097 U	<0.0905 U	<0.0917 U	<0.0898 U	<0.0889 U
Aniline (Phenylamine, Aminobenzene)	62-53-3	0.04	0.04	8.1	mg/kg	<0.379 U	<0.437 UJ	<0.585 UJ	<0.363 U	<0.4 U	<0.395 U	<0.382 U	<0.357 U	<0.345 U	<0.354 U	<0.359 U	<0.38 U	<0.388 U	<0.363 U	<0.367 U	<0.359 U	<0.356 U
Anthracene	120-12-7	100	1000	100	mg/kg	0.0877 JD	0.0924 J	<0.146 UJ	0.084 JD	<0.0999 U	0.249 D	0.259 D	<0.0892 U	<0.0861 U	0.0664 JD	<0.0895 U	0.992 D	0.211 D	0.274 D	0.396 D	0.0466 JD	<0.0889 U
Atrazine	1912-24-9	NS	NS	NS	mg/kg	<0.0946 U	<0.109 UJ	<0.146 UJ	<0.0906 U	<0.0999 U	<0.0986 U	<0.0953 U	<0.0892 U	<0.0861 U	<0.0884 U	<0.0895 U	<0.0948 U	<0.097 U	<0.0905 U	<0.0917 U	<0.0898 U	<0.0889 U
Benzaldehyde	100-52-7	NS	NS	NS	mg/kg	<0.0946 U	<0.109 UJ	<0.146 UJ	<0.0906 U	<0.0999 U	<0.0986 U	<0.0953 U	<0.0892 U	<0.0861 U	<0.0884 U	<0.0895 U	<0.0948 U	<0.097 U	<0.0905 U	<0.0917 U	<0.0898 U	<0.0889 U
Benzidine	92-87-5	NS	NS	NS	mg/kg	<0.379 U	<0.437 UJ	<0.585 UJ	<0.363 U	<0.4 U	<0.395 U	<0.382 U	<0.357 U	<0.345 U	<0.354 U	<0.359 U	<0.38 U	<0.388 U	<0.363 U	<0.367 U	<0.359 U	<0.356 U
Benzo(a)anthracene	56-55-3	**1**	1	1.4	mg/kg	0.183 D	0.241 J	<0.146 UJ	0.211 D	<0.0999 U	0.512 D	0.451 D	<0.0892 U	0.0461 JD	0.126 D	0.0508 JD	**1.59 D**	0.677 D	0.648 D	0.877 D	0.169 D	<0.0889 U
Benzo(a)pyrene	50-32-8	**1**	22	1	mg/kg	0.116 D	0.221 J	<0.146 UJ	0.199 D	<0.0999 U	0.48 D	0.44 D	<0.0892 U	<0.0861 U	0.101 D	0.0472 JD	**1.51 D**	0.621 D	0.546 D	0.853 D	0.0847 JD	<0.0889 U
Benzo(b)fluoranthene	205-99-2	**1**	2.1	1.4	mg/kg	0.138 D	0.167 J	<0.146 UJ	0.182 D	<0.0999 U	0.345 D	0.417 D	<0.0892 U	<0.0861 U	0.0926 D	<0.0895 U	**1.49 D**	0.527 D	0.478 D	0.756 D	0.0969 D	<0.0889 U
Benzo(g,h,i)Perylene	191-24-2	**0.64**	1000	4.9	mg/kg	0.0764 JD	0.233 J	<0.146 UJ	0.125 D	<0.0999 U	0.347 D	0.452 D	<0.0892 U	<0.0861 U	0.0714 JD	<0.0895 U	0.502 D	0.282 D	0.354 D	0.582 D	0.0531 JD	<0.0889 U
Benzo(k)fluoranthene	207-08-9	**0.8**	2	4.9	mg/kg	0.104 D	0.166 J	<0.146 UJ	0.162 D	<0.0999 U	0.379 D	0.344 D	<0.0892 U	<0.0861 U	0.0911 D	<0.0895 U	**1.25 D**	0.464 D	0.404 D	0.678 D	0.0926 D	<0.0889 U
Benzoic Acid	65-85-0	NS	NS	NS	mg/kg	<0.0946 U	<0.109 UJ	<0.146 UJ	<0.0906 UJ	<0.0999 U	<0.0986 U	<0.0953 U	<0.0892 U	<0.0861 UJ	<0.0884 U	<0.0895 U	<0.0948 UJ	<0.097 UJ	<0.0905 U	<0.0917 U	<0.0898 U	<0.0889 U
Benzyl Alcohol	100-51-6	NS	NS	NS	mg/kg	<0.0946 U	<0.109 UJ	<0.146 UJ	<0.0906 U	<0.0999 U	<0.0986 U	<0.0953 U	<0.0892 U	<0.0861 U	<0.0884 U	<0.0895 U	<0.0948 U	<0.097 U	<0.0905 U	<0.0917 U	<0.0898 U	<0.0889 U
Benzyl Butyl Phthalate	85-68-7	NS	NS	NS	mg/kg	<0.0946 U	<0.109 UJ	<0.146 UJ	<0.0906 U	<0.0999 U	<0.0986 U	0.327 D	<0.0892 U	<0.0861 U	14 D	<0.0895 U	0.527 D	0.0597 JD	0.206 D	<0.0917 U	<0.0898 U	<0.0889 U
Biphenyl (Diphenyl)	92-52-4	NS	NS	NS	mg/kg	<0.0946 U	<0.109 UJ	<0.146 UJ	<0.0906 U	<0.0999 U	<0.0986 U	<0.0953 U	<0.0892 U	<0.0861 U	<0.0884 U	<0.0895 U	<0.0948 U	<0.097 U	<0.0905 U	<0.0917 U	<0.0898 U	<0.0889 U
Bis(2-chloroethoxy) methane	111-91-1	NS	NS	NS	mg/kg	<0.0946 U	<0.109 UJ	<0.146 UJ	<0.0906 U	<0.0999 U	<0.0986 U	<0.0953 U	<0.0892 U	<0.0861 U	<0.0884 U	<0.0895 U	<0.0948 U	<0.097 U	<0.0905 U	<0.0917 U	<0.0898 U	<0.0889 U
Bis(2-chloroethyl) ether (2-chloroethyl ether)	111-44-4	NS	NS	NS	mg/kg	<0.0946 U	<0.109 UJ	<0.146 UJ	<0.0906 U	<0.0999 U	<0.0986 U	<0.0953 U	<0.0892 U	<0.0861 U	<0.0884 U	<0.0895 U	<0.0948 U	<0.097 U	<0.0905 U	<0.0917 U	<0.0898 U	<0.0889 U
Bis(2-chloroisopropyl) ether	108-60-1	NS	NS	NS	mg/kg	<0.0946 U	<0.109 UJ	<0.146 UJ	<0.0906 U	<0.0999 U	<0.0986 U	<0.0953 U	<0.0892 U	<0.0861 U	<0.0884 U	<0.0895 U	<0.0948 U	<0.097 U	<0.0905 U	<0.0917 U	<0.0898 U	<0.0889 U
Bis(2-ethylhexyl) phthalate	117-81-7	NS	NS	NS	mg/kg	<0.0946 U	0.253 J	<0.146 UJ	0.301 D	<0.0999 U	0.1 D	1.09 D	<0.0892 U	0.35 D	<0.0884 U	<0.0895 U	11.8 D	0.587 D	1.33 D	0.0784 JD	<0.0898 U	0.0753 JD
Caprolactam	105-60-2	NS	NS	NS	mg/kg	<0.189 U	<0.218 UJ	<0.292 UJ	<0.181 U	<0.2 U	<0.197 U	<0.19 U	<0.178 U	<0.172 U	<0.177 U	<0.179 U	<0.189 U	<0.194 U	<0.181 U	<0.183 U	<0.179 U	<0.178 U
Carbazole	86-74-8	NS	NS	NS	mg/kg	<0.0946 U	<0.109 UJ	<0.146 UJ	<0.0906 U	<0.0999 U	<0.0986 U	0.0754 JD	<0.0892 U	<0.0861 U	<0.0884 U	<0.0895 U	0.177 D	0.0511 JD	0.0796 JD	0.105 D	<0.0898 U	<0.0889 U
Chrysene	218-01-9	**1**	1	4.9	mg/kg	0.221 D	0.25 J	<0.146 UJ	0.217 D	<0.0999 U	0.602 D	0.518 D	<0.0892 U	0.0454 JD	0.13 D	0.058 JD	**1.63 D**	0.632 D	0.601 D	**1.14 D**	0.181 D	<0.0889 U
Dibenz(a,h)anthracene	53-70-3	**0.33**	1000	0.33	mg/kg	<0.0946 U	0.0872 J	<0.146 UJ	<0.0906 U	<0.0999 U	0.107 D	0.137 D	<0.0892 U	<0.0861 U	<0.0884 U	<0.0895 U	0.183 D	0.105 D	<0.0905 U	0.189 D	<0.0898 U	<0.0889 U
Dibenzofuran	132-64-9	**2.1**	110	18	mg/kg	0.0991 D	<0.109 UJ	<0.146 UJ	<0.0906 U	<0.0999 U	<0.0986 U	0.0967 D	<0.0892 U	<0.0861 U	<0.0884 U	<0.0895 U	0.155 D	<0.097 U	0.0514 JD	0.0572 JD	<0.0898 U	<0.0889 U
Dibutyl phthalate	84-74-2	NS	NS	NS	mg/kg	<0.0946 U	<0.109 UJ	<0.146 UJ	<0.0906 U	<0.0999 U	<0.0986 U	<0.0953 U	<0.0892 U	<0.0861 U	<0.0884 U	<0.0895 U	0.187 D	<0.097 U	0.0565 JD	<0.0917 U	<0.0898 U	<0.0889 U
Diethyl phthalate	84-66-2	NS	NS	NS	mg/kg	<0.0946 U	<0.109 UJ	<0.146 UJ	<0.0906 U	<0.0999 U	<0.0986 U	<0.0953 U	<0.0892 U	<0.0861 U	<0.0884 U	<0.0895 U	<0.0948 U	<0.097 U	<0.0905 U	<0.0917 U	<0.0898 U	<0.0889 U
Dimethyl phthalate	131-11-3	NS	NS	NS	mg/kg	<0.0946 U	<0.109 UJ	<0.146 UJ	<0.0906 U	<0.0999 U	<0.0986 U	<0.0953 U	<0.0892 U	<0.0861 U	<0.0884 U	<0.0895 U	<0.0948 U	<0.097 U	<0.0905 U	<0.0917 U	<0.0898 U	<0.0889 U
Dioctyl phthalate	117-84-0	NS	NS	NS	mg/kg	<0.0946 U	<0.109 UJ	<0.146 UJ	0.24 D	<0.0999 U	<0.0986 U	<0.0953 U	<0.0892 U	<0.0861 U	<0.0884 U	<0.0895 U	4.55 D	<0.097 U	0.213 D	<0.0917 U	<0.0898 U	<0.0889 U
Fluoranthene	206-44-0	85	1000	100	mg/kg	0.6 D	0.454 J	0.102 J	0.389 D	<0.0999 U	1.12 D	0.785 D	<0.0892 U	0.0977 D	0.266 D	0.0973 D	2.83 D	1.34 D	1.27 D	2.18 D	0.119 D	<0.0889 U
Fluorene	86-73-7	30	386	100	mg/kg	0.0847 JD	<0.109 UJ	<0.146 UJ	0.0456 JD	<0.0999 U	0.148 D	0.161 D	<0.0892 U	<0.0861 U	<0.0884 U	<0.0895 U	0.446 D	0.0659 JD	0.132 D	0.32 D	<0.0898 U	<0.0889 U
Hexachlorobenzene	118-74-1	0.33	3.2	0.33	mg/kg	<0.0946 U	<0.109 UJ	<0.146 UJ	<0.0906 U	<0.0999 U	<0.0986 U	<0.0953 U	<0.0892 U	<0.0861 U	<0.0884 U	<0.0895 U	<0.0948 U	<0.097 U	<0.0905 U	<0.0917 U	<0.0898 U	<0.0889 U
Hexachlorobutadiene	87-68-3	NS	NS	NS	mg/kg	<0.0946 U	<0.109 UJ	<0.146 UJ	<0.0906 U	<0.0999 U	<0.0986 U	<0.0953 U	<0.0892 U	<0.0861 UJ	<0.0884 U	<0.0895 U	<0.0948 U	<0.097 U	<0.0905 U	<0.0917 U	<0.0898 U	<0.0889 U
Hexachlorocyclopentadiene	77-47-4	NS	NS	NS	mg/kg	<0.0946 U	<0.109 UJ	<0.146 UJ	<0.0906 UJ	<0.0999 U	<0.0986 U	<0.0953 U	<0.0892 UJ	<0.0861 U	<0.0884 U	<0.0895 U	<0.0948 UJ	<0.097 U	<0.0905 U	<0.0917 U	<0.0898 U	<0.0889 UJ
Hexachloroethane	67-72-1	NS	NS	NS	mg/kg	<0.0946 U	<0.109 UJ	<0.146 UJ	<0.0906 U	<0.0999 U	<0.0986 U	<0.0953 U	<0.0892 U	<0.0861 U	<0.0884 U	<0.0895 U	<0.0948 U	<0.097 U	<0.0905 U	<0.0917 U	<0.0898 U	<0.0889 U
Indeno(1,2,3-cd)pyrene	193-39-5	**0.5**	6.6	1.4	mg/kg	0.065 JD	0.18 J	<0.146 UJ	0.119 D	<0.0999 U	0.311 D	0.344 D	<0.0892 U	<0.0861 U	0.0692 JD	<0.0895 U	**0.561 D**	0.268 D	0.403 D	**0.556 D**	0.0545 JD	<0.0889 U
Isophorone	78-59-1	NS	NS	NS	mg/kg	<0.0946 U	<0.109 UJ	<0.146 UJ	<0.0906 U	<0.0999 U	<0.0986 U	<0.0953 U	<0.0892 U	<0.0861 U	<0.0884 U	<0.0895 U	<0.0948 U	<0.097 U	<0.0905 U	<0.0917 U	<0.0898 U	<0.0889 U
Naphthalene	91-20-3	12	12	100	mg/kg	0.0635 JD	0.0671 J	<0.146 UJ	0.576 D	<0.0999 U	0.136 D	0.478 D	<0.0892 U	<0.0861 U	0.107 D	<0.0895 U	0.263 D	<0.097 U	0.161 D	0.177 D	0.127 D	<0.0889 U
Nitrobenzene	98-95-3	0.08	0.08	1.8	mg/kg	<0.0946 U	<0.109 UJ	<0.146 UJ	<0.0906 U	<0.0999 U	<0.0986 U	<0.0953 U	<0.0892 U	<0.0861 U	<0.0884 U	<0.0895 U	<0.0948 U	<0.097 U	<0.0905 U	<0.0917 U	<0.0898 U	<0.0889 U
n-Nitrosodimethylamine	62-75-9	NS	NS	NS	mg/kg	<0.0946 U	<0.109 UJ	<0.146 UJ	<0.0906 U	<0.0999 U	<0.0986 U	<0.0953 U	<0.0892 U	<0.0861 U	<0.0884 U	<0.0895 U	<0.0948 U	<0.097 U	<0.0905 U	<0.0917 U	<0.0898 U	<0.0889 U
n-Nitrosodi-N-Propylamine	621-64-7	NS	NS	NS	mg/kg	<0.0946 U	<0.109 UJ	<0.146 UJ	<0.0906 U	<0.0999 U	<0.0986 U	<0.0953 U	<0.0892 U	<0.0861 U	<0.0884 U	<0.0895 U	<0.0948 U	<0.097 U	<0.0905 U	<0.0917 U	<0.0898 U	<0.0889 U
n-Nitrosodiphenylamine	86-30-6	NS	NS	NS	mg/kg	<0.0946 U	<0.109 UJ	<0.146 UJ	<0.0906 U	<0.0999 U	<0.0986 U	<0.0953 U	<0.0892 U	<0.0861 U	<0.0884 U	<0.0895 U	<0.0948 U	<0.097 U	<0.0905 U	<0.0917 U	<0.0898 U	<0.0889 U
Pentachlorophenol	87-86-5	0.8	0.8	1.3	mg/kg	<0.0946 U	<0.109 UJ	<0.146 UJ	<0.0906 U	<0.0999 U	<0.0986 U	<0.0953 U	<0.0892 U	<0.0861 U	<0.0884 U	<0.0895 U	<0.0948 UJ	<0.097 U	<0.0905 U	<0.0917 U	<0.0898 U	<0.0889 U
Phenanthrene	85-01-8	**1.1**	1000	4.9	mg/kg	0.423 D	0.284 J	<0.146 UJ	0.247 D	<0.0999 U	0.809 D	0.857 D	<0.0892 U	0.0544 JD	0.171 D	0.068 JD	**2.34 D**	0.56 D	0.867 D	**2 D**	0.0545 JD	<0.0889 U
Phenol	108-95-2	0.33	0.33	100	mg/kg	<0.0946 U	<0.109 UJ	<0.146 UJ	<0.0906 U	<0.0999 U	<0.0986 U	<0.0953 U	<0.0892 U	<0.0861 U	<0.0884 U	<0.0895 U	<0.0948 UJ	<0.097 U	<0.0905 U	<0.0917 U	<0.0898 U	<0.0889 U
Pyrene	129-00-0	64	1000	100	mg/kg	0.735 D	0.534 J	0.0957 J	0.352 D	<0.0999 U	1.3 D	1.16 D	<0.0892 U	0.0792 JD	0.259 D	0.116 D	2.63 D	1.14 D	1.4 D	2.39 D	0.163 D	<0.0889 U
Pyridine	110-86-1	NS	NS	NS	mg/kg	<0.379 U	<0.437 UJ	<0.585 UJ	<0.363 U	<0.4 U	<0.395 U	<0.382 U	<0.357 U	<0.345 U	<0.354 U	<0.359 U	<0.38 U	<0.388 U	<0.363 U	<0.367 U	<0.359 U	<0.356 U

Table 2
Site Management Plan
Soil Sample Analytical Results

12074 Flatlands Avenue p/o Lot 1 Site
Brooklyn, New York
BCP Site No. C224353
Langan Project No.: 100688803

Analyte	CAS Number	NYSDEC Part 375 Unrestricted Use SCOs	NYSDEC Part 375 Protection of Groundwater SCOs	NYSDEC Part 375 Restricted Use Restricted-Residential SCOs	Location	PE67	PE68	PE68	PE69	PE70	PE71	PE72	PE73	PE74	PE75	PE76	PE77	PE77	PE78	PE79	PE80	PE81
					Sample Name	PE67_20	PE68_29	DUP_20251028	PE69_20	PE70_20	PE71_20	PE72_19	PE73_20	PE74_20	PE75_19.5	PE76_19.5	PE77_19.5	PE77_20.5	PE78_19.5	PE79_20	PE80_19	PE81_20
					Sample Date	09/17/2025	10/28/2025	10/28/2025	10/01/2025	09/23/2025	09/23/2025	09/17/2025	12/05/2025	11/19/2025	09/23/2025	09/23/2025	10/01/2025	10/14/2025	09/23/2025	09/23/2025	09/17/2025	12/05/2025
					Sample Elevation	20	29	29	20	20	20	19	20	20	19.5	19.5	19.5	20.5	19.5	20	19	20
					Unit	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result
Pesticides																						
4,4'-DDD	72-54-8	**0.0033**	14	5	mg/kg	**0.00407 DP**	**0.00356 DP**	<0.00288 UP	0.00232 DP	<0.00196 U	0.00235 D	**0.0107 DP**	<0.00176 UP	<0.00171 UP	<0.00174 U	<0.00175 U	**0.0513 DP**	**0.0138 J**	**0.0206 D**	0.00212 J	<0.00182 UP	<0.00178 UP
4,4'-DDE	72-55-9	**0.0033**	9.3	3.4	mg/kg	**0.00531 DP**	**0.00622 J**	<0.00288 UP	<0.0018 UP	<0.00196 U	<0.00194 U	<0.00187 UP	<0.00176 UP	<0.00171 UP	<0.00174 U	<0.00175 U	**0.0276 DP**	**0.00933 DP**	**0.00487 J**	<0.00181 UJ	<0.00182 UP	<0.00178 UP
4,4'-DDT	50-29-3	**0.0033**	135	3.8	mg/kg	0.002 J	<0.00214 UP	<0.00288 UP	<0.0018 UP	<0.00196 U	<0.00194 U	**0.00916 J**	<0.00176 UP	<0.00171 UP	<0.00174 U	<0.00175 U	**0.0186 J**	**0.00468 J**	**0.00815 J**	0.00203 J	<0.00182 UP	<0.00178 UP
Aldrin	309-00-2	0.0048	0.19	0.044	mg/kg	<0.00186 UP	<0.00214 UP	<0.00288 UP	<0.0018 UP	<0.00196 U	0.00274 D	<0.00187 UP	<0.00176 UP	<0.00171 UP	<0.00174 U	<0.00175 U	<0.00189 UP	<0.00191 UP	<0.00178 U	<0.00181 UJ	<0.00182 UP	<0.00178 UP
Alpha BHC (Alpha Hexachlorocyclohexane)	319-84-6	0.02	0.02	0.18	mg/kg	<0.00186 UP	<0.00214 UP	<0.00288 UP	<0.0018 UP	<0.00196 U	<0.00194 U	<0.00187 UP	<0.00176 UP	<0.00171 UP	<0.00174 U	<0.00175 U	<0.00189 UP	<0.00191 UP	<0.00178 U	<0.00181 UJ	<0.00182 UP	<0.00178 UP
Alpha Chlordane	5103-71-9	**0.014**	4.5	0.65	mg/kg	<0.00186 U	<0.00214 UP	<0.00288 UP	<0.0018 UP	<0.00196 U	<0.00194 U	<0.00187 U	<0.00176 UP	<0.00171 UP	<0.00174 U	<0.00175 U	0.0118 J	0.00213 J	0.00421 D	<0.00181 UJ	<0.00182 UP	<0.00178 UP
Alpha Endosulfan	959-98-8	4.3	65	35	mg/kg	<0.00186 UP	<0.00214 UP	<0.00288 UP	<0.0018 UP	<0.00196 U	<0.00194 U	<0.00187 UP	<0.00176 UP	<0.00171 UP	<0.00174 U	<0.00175 U	<0.00189 UP	<0.00191 UP	<0.00178 U	<0.00181 UJ	<0.00182 UP	<0.00178 UP
Beta Bhc (Beta Hexachlorocyclohexane)	319-85-7	0.021	0.09	0.18	mg/kg	<0.00186 UP	<0.00214 UP	<0.00288 UP	<0.0018 UP	<0.00196 U	<0.00194 U	<0.00187 UP	<0.00176 UP	<0.00171 UP	<0.00174 U	<0.00175 U	<0.00189 UP	<0.00191 UP	<0.00178 U	<0.00181 UJ	<0.00182 UP	<0.00178 UP
Beta Endosulfan	33213-65-9	4.3	44	35	mg/kg	<0.00186 UP	<0.00214 UP	<0.00288 UP	<0.0018 UP	<0.00196 U	<0.00194 U	<0.00187 UP	<0.00176 UP	<0.00171 UP	<0.00174 U	<0.00175 U	<0.00189 UP	<0.00191 UP	<0.00178 U	<0.00181 UJ	<0.00182 UP	<0.00178 UP
Delta Bhc (Delta Hexachlorocyclohexane)	319-86-8	0.04	0.1	100	mg/kg	<0.00186 UP	<0.00214 UP	<0.00288 UP	<0.0018 UP	<0.00196 U	<0.00194 U	<0.00187 UP	<0.00176 UP	<0.00171 UP	<0.00174 U	<0.00175 U	<0.00189 UP	<0.00191 UP	<0.00178 U	<0.00181 UJ	<0.00182 UP	<0.00178 UP
Dieldrin	60-57-1	**0.005**	0.1	0.075	mg/kg	<0.00186 UP	<0.00214 UP	<0.00288 UP	<0.0018 UP	<0.00196 U	<0.00194 U	<0.00187 UP	<0.00176 UP	<0.00171 UP	<0.00174 U	<0.00175 U	**0.0251 DP**	**0.00774 J**	<0.00178 U	<0.00181 UJ	<0.00182 UP	<0.00178 UP
Endosulfan Sulfate	1031-07-8	4.3	47	35	mg/kg	<0.00186 UP	<0.00214 UP	<0.00288 UP	<0.0018 UP	<0.00196 U	<0.00194 U	<0.00187 UP	<0.00176 UP	<0.00171 UP	<0.00174 U	<0.00175 U	<0.00189 UP	<0.00191 UP	<0.00178 U	<0.00181 UJ	<0.00182 UP	<0.00178 UP
Endrin	72-20-8	0.014	0.06	5.3	mg/kg	<0.00186 UP	<0.00214 UP	<0.00288 UP	<0.0018 UP	<0.00196 U	<0.00194 U	<0.00187 UP	<0.00176 UP	<0.00171 UP	<0.00174 U	<0.00175 U	<0.00189 UP	<0.00191 UP	<0.00178 U	<0.00181 UJ	<0.00182 UP	<0.00178 UP
Endrin Aldehyde	7421-93-4	NS	NS	NS	mg/kg	<0.00186 UP	<0.00214 UP	<0.00288 UP	<0.0018 UP	<0.00196 U	<0.00194 U	<0.00187 UP	<0.00176 UP	<0.00171 UP	<0.00174 U	<0.00175 U	<0.00189 UP	<0.00191 UP	<0.00178 U	<0.00181 UJ	<0.00182 UP	<0.00178 UP
Endrin Ketone	53494-70-5	NS	NS	NS	mg/kg	<0.00186 UP	<0.00214 UP	<0.00288 UP	<0.0018 UP	<0.00196 U	<0.00194 U	<0.00187 UP	<0.00176 UP	<0.00171 UP	<0.00174 U	<0.00175 U	<0.00189 UP	<0.00191 UP	<0.00178 U	<0.00181 UJ	<0.00182 UP	<0.00178 UP
Gamma Bhc (Lindane)	58-89-9	0.025	0.05	0.21	mg/kg	<0.00186 UP	<0.00214 UP	<0.00288 UP	<0.0018 UP	<0.00196 U	<0.00194 U	<0.00187 UP	<0.00176 UP	<0.00171 UP	<0.00174 U	<0.00175 U	<0.00189 UP	<0.00191 UP	<0.00178 U	<0.00181 UJ	<0.00182 UP	<0.00178 UP
Gamma-Chlordane	5566-34-7	NS	NS	NS	mg/kg	0.00216 J	<0.00214 UP	<0.00288 UP	<0.0018 UP	<0.00196 U	<0.00194 U	<0.00187 U	<0.00176 UP	<0.00171 UP	<0.00174 U	<0.00175 U	0.0127 J	0.00474 J	0.00465 J	<0.00181 UJ	<0.00182 UP	<0.00178 UP
Heptachlor	76-44-8	0.013	0.38	0.53	mg/kg	<0.00186 UP	<0.00214 UP	<0.00288 UP	<0.0018 UP	<0.00196 U	<0.00194 U	<0.00187 UP	<0.00176 UP	<0.00171 UP	<0.00174 U	<0.00175 U	<0.00189 UP	<0.00191 UP	<0.00178 U	<0.00181 UJ	<0.00182 UP	<0.00178 UP
Heptachlor Epoxide	1024-57-3	NS	NS	NS	mg/kg	<0.00186 UP	<0.00214 UP	<0.00288 UP	<0.0018 UP	<0.00196 U	<0.00194 U	<0.00187 UP	<0.00176 UP	<0.00171 UP	<0.00174 U	<0.00175 U	<0.00189 UP	<0.00191 UP	<0.00178 U	<0.00181 UJ	<0.00182 UP	<0.00178 UP
Methoxychlor	72-43-5	NS	NS	NS	mg/kg	<0.00186 UP	<0.00214 UP	<0.00288 UP	<0.0018 UP	<0.00196 U	<0.00194 U	<0.00187 UP	<0.00176 UP	<0.00171 UP	<0.00174 U	<0.00175 U	<0.00189 UP	<0.00191 UP	<0.00178 U	<0.00181 UJ	<0.00182 UP	<0.00178 UP
Toxaphene	8001-35-2	NS	NS	NS	mg/kg	<0.186 UP	<0.214 UP	<0.288 UP	<0.18 UP	<0.196 U	<0.194 U	<0.187 UP	<0.176 UP	<0.171 UP	<0.174 U	<0.175 U	<0.189 UP	<0.191 UP	<0.178 U	<0.181 UJ	<0.182 UP	<0.178 UP
Herbicides																						
2,4,5-T (Trichlorophenoxyacetic Acid)	93-76-5	NS	NS	NS	mg/kg	<0.0225 UP	NA	NA	<0.0214 UP	<0.0238 U	<0.0235 U	<0.0225 UP	<0.0208 UP	<0.0209 UP	<0.0211 U	<0.0213 U	<0.0229 UP	<0.0235 UP	<0.0217 U	<0.0218 U	<0.0217 UP	<0.0213 UP
2,4-D (Dichlorophenoxyacetic Acid)	94-75-7	NS	NS	NS	mg/kg	<0.0225 UP	<0.0279 UP	<0.0375 UP	<0.0214 UP	<0.0238 U	<0.0235 U	<0.0225 UP	<0.0208 UP	<0.0209 UP	<0.0211 U	<0.0213 U	<0.0229 UP	<0.0235 UP	<0.0217 U	<0.0218 U	<0.0217 UP	<0.0213 UP
2,4-Dichlorophenoxybutyric acid	94-82-6	NS	NS	NS	mg/kg	<0.0225 UP	NA	NA	NA	NA	NA	<0.0225 UP	NA	NA	NA	NA	NA	NA	NA	NA	<0.0217 UP	NA
Dalapon	75-99-0	NS	NS	NS	mg/kg	<0.0225 UP	NA	NA	NA	NA	NA	<0.0225 UP	NA	NA	NA	NA	NA	NA	NA	NA	<0.0217 UP	NA
Dicamba	1918-00-9	NS	NS	NS	mg/kg	<0.0225 UP	NA	NA	NA	NA	NA	<0.0225 UP	NA	NA	NA	NA	NA	NA	NA	NA	<0.0217 UP	NA
Silvex (2,4,5-Tp)	93-72-1	3.8	3.8	100	mg/kg	<0.0225 UP	NA	NA	<0.0214 UP	<0.0238 U	<0.0235 U	<0.0225 UP	<0.0208 UP	<0.0209 UP	<0.0211 U	<0.0213 U	<0.0229 UP	<0.0235 UP	<0.0217 U	<0.0218 U	<0.0217 UP	<0.0213 UP
Polychlorinated Biphenyl																						
PCB-1016 (Aroclor 1016)	12674-11-2	NS	NS	NS	mg/kg	<0.0188 UP	<0.0216 UP	<0.0291 UP	<0.0182 UP	<0.02 UJ	<0.0197 U	<0.0189 UJ	<0.0177 UP	<0.0173 UP	<0.0177 U	<0.0179 U	<0.0191 UP	<0.0193 UP	<0.018 U	<0.0183 UJ	<0.0183 UP	<0.0179 UP
PCB-1221 (Aroclor 1221)	11104-28-2	NS	NS	NS	mg/kg	<0.0188 UP	<0.0216 UP	<0.0291 UP	<0.0182 UP	<0.02 UJ	<0.0197 U	<0.0189 UJ	<0.0177 UP	<0.0173 UP	<0.0177 U	<0.0179 U	<0.0191 UP	<0.0193 UP	<0.018 U	<0.0183 UJ	<0.0183 UP	<0.0179 UP
PCB-1232 (Aroclor 1232)	11141-16-5	NS	NS	NS	mg/kg	<0.0188 UP	<0.0216 UP	<0.0291 UP	<0.0182 UP	<0.02 UJ	<0.0197 U	<0.0189 UJ	<0.0177 UP	<0.0173 UP	<0.0177 U	<0.0179 U	<0.0191 UP	<0.0193 UP	<0.018 U	<0.0183 UJ	<0.0183 UP	<0.0179 UP
PCB-1242 (Aroclor 1242)	53469-21-9	NS	NS	NS	mg/kg	0.0562 P	0.189 J	<0.0291 UJ	0.0423 J	<0.02 UJ	0.109 J	0.107 J	<0.0177 UP	<0.0173 UP	<0.0177 U	<0.0179 U	0.186 J	0.422 P	0.243	0.0292 J	<0.0183 UP	<0.0179 UP
PCB-1248 (Aroclor 1248)	12672-29-6	NS	NS	NS	mg/kg	<0.0188 UP	<0.0216 UP	<0.0291 UP	<0.0182 UP	<0.02 UJ	<0.0197 U	<0.0189 UJ	<0.0177 UP	<0.0173 UP	0.0928	<0.0179 U	<0.0191 UP	<0.0193 UP	<0.018 U	<0.0183 UJ	<0.0183 UP	<0.0179 UP
PCB-1254 (Aroclor 1254)	11097-69-1	NS	NS	NS	mg/kg	<0.0188 UP	0.223 J	<0.0291 UJ	0.0512 J	<0.02 UJ	0.0825 J	0.207 J	<0.0177 UP	<0.0173 UP	<0.0177 U	<0.0179 U	0.246 J	0.131 P	0.239	0.03 J	<0.0183 UP	<0.0179 UP
PCB-1260 (Aroclor 1260)	11096-82-5	NS	NS	NS	mg/kg	0.028 P	<0.0216 UP	<0.0291 UP	<0.0182 UP	<0.02 UJ	<0.0197 U	0.16 J	<0.0177 UP	<0.0173 UP	0.022	<0.0179 U	<0.0191 UP	0.0629 P	0.126	<0.0183 UJ	<0.0183 UP	<0.0179 UP
PCB-1262 (Aroclor 1262)	37324-23-5	NS	NS	NS	mg/kg	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
PCB-1268 (Aroclor 1268)	11100-14-4	NS	NS	NS	mg/kg	NA	NA	NA	0.0262 J	NA	0.0358 J	NA	NA	NA	NA	0.0184	0.03 J	NA	NA	NA	NA	NA
Total PCBs	1336-36-3	**0.1**	3.2	1	mg/kg	0.0842 P	**0.412 J**	<0.0291 UJ	**0.12 J**	<0.02 UJ	**0.227 J**	**0.475 J**	<0.0177 UP	<0.0173 UP	**0.115**	0.0184	**0.461 J**	**0.616 P**	**0.609**	0.0591 J	<0.0183 UP	<0.0179 UP
Metals																						
Aluminum	7429-90-5	NS	NS	NS	mg/kg	5,570 B	6,600	8,020	5,300	6,920	6,930	5,580 B	6,100	5,220	3,720	7,510	6,300	7,730	7,010	6,500	6,060 B	6,040
Antimony	7440-36-0	NS	NS	NS	mg/kg	<2.37 U	10.5	<3.66 U	<2.28 U	4.26	<2.47 U	<2.39 U	<2.24 UJ	<2.19 UJ	<2.21 U	<2.24 U	<2.39 U	<2.45 U	<2.27 U	<2.3 U	<2.31 U	<2.26 U
Arsenic	7440-38-2	**13**	16	16	mg/kg	5.29	8.92	**14.7**	4.11	9.46	7.65	10.3	2.01	1.42	2.75	4.62	10.5	4.95	5.98	4.51	3.82	2.32
Barium	7440-39-3	**410**	820	410	mg/kg	172	338 J	**5,310 J**	169	346	393	340	10.7	30.2	86.6	77.3	**935**	296	326	226	104	76
Beryllium	7440-41-7	4.4	47	43	mg/kg	0.233	0.444	0.733	0.211	0.223 J	0.284 J	0.338	0.059 J	0.237	0.137 J	0.204 J	0.184	0.238	0.151 J	0.194 J	0.298	0.171
Cadmium	7440-43-9	**2.5**	7.5	2.5	mg/kg	**3.22**	1.45	2.23	0.565	**10.6**	1.83	**3.45**	<0.268 U	<0.263 U	0.434	0.709	1.42	1.38	1.21	0.708	<0.277 U	<0.272 U
Calcium	7440-70-2	NS	NS	NS	mg/kg	18,200	15,600 J	7,930 J	5,810	27,100	17,900	9,510	827	1,090	2,220	5,490	18,700	29,500	30,400	6,050	1,930	3,000
Chromium, Hexavalent	18540-29-9	1	19	1	mg/kg	<0.569 U	<0.658 U	<0.878 U	<0.547 U	<0.601 U	<0.593 U	<0.573 U	<0.537 U	<0.527 UJ	<0.532 UJ	<0.539 U	<0.574 U	<0.589 U	<0.545 U	<0.552 U	<0.554 U	<0.543 U
Chromium, Total	7440-47-3	NS	NS	NS	mg/kg	42.8	25.3	40	16.5	35.4	26	26	10.2	8.65	12.2	18.7	25	28.7	23.1	19.9	27.3	12.2
Chromium, Trivalent	16065-83-1	**30**	19	110	mg/kg	**42.8**	25.3	**40**	16.5	**35.4**	26	26	10.2	8.65	12.2	18.7	25	28.7	23.1	19.9	27.3	12.2
Cobalt	7440-48-4	NS	NS	NS	mg/kg	4.13	6.91	9.87	4.87	8.32	6.86	6.65	3.09	2.89	3.89	4.87	6.64	6.89	5.62	5.34	5.31	3.65
Copper	7440-50-8	**50**	1720	280	mg/kg	**300**	**111**	**116**	**86.8**	**332 J**	**143 J**	**166**	7.69	10.7	38.2 J	**83.4 J**	**84.6**	**129**	**106 J**	**83.9 J**	**71.6**	17.2
Cyanide	57-12-5	**2.3**	40	13	mg/kg	<0.569 U	0.694	<0.878 U	<0.547 U	<0.601 U	<0.593 U	<0.573 U	<0.537 U	<0.527 UJ	<0.532 U	<0.539 U	<0.574 U	<0.589 U	0.763	0.645	<0.554 U	<0.543 U
Iron	7439-89-6	NS	NS	NS	mg/kg	16,200	28,400	20,000	16,300	38,500	24,400	33,500	8,250	8,770	13,000	20,100	22,200	20,300	22,800	14,400	21,700	11,700
Lead	7439-92-1	**63**	450	400	mg/kg	**406**	**510 J**	**2,420 J**	**200**	**680**	**512**	**957**	3.34 J	11.9	**197**	**86.6**	**400**	**336**	**346**	**279**	**167**	62.1
Magnesium	7439-95-4	NS	NS	NS	mg/kg	4,900	2,550 J	1,020 J	2,200	4,630	2,950	4,080	1,770	2,090	1,550	2,090	3,360	5,290	7,040	2,260	2,060	2,270
Manganese	7439-96-5	**1600**	2000	2000	mg/kg	199	257	181	181	264	244	262	84.3 J	93.3	185	232	278	306	267	163	271	118
Mercury	7439-97-6	**0.18**	0.73	0.3	mg/kg	**0.545**	**0.299 J**	0.142 J	0.102	<0.0361 U	**0.839**	**0.336**	<0.0322 U	0.0342	**0.188**	0.0934	**0.337**	**0.665**	**0.369**	**0.224**	0.064	**0.206**
Nickel	7440-02-0	**30**	130	320	mg/kg	22.4	23.7	21.5	17.2	**36.6**	24.7	**32.3**	11.1	12.6	14	20.7	22.7	22	21.4	18.8	28.8	17.3
Potassium	7440-09-7	NS	NS	NS	mg/kg	1,330	768	874	631	1,080	916	627	665	576	438	654	1,080	1,110	967	759	678	795
Selenium	7782-49-2	**3.9**	4	110	mg/kg	<2.37 U	<2.74 U	<3.66 U	<2.28 U	<2.5 U	<2.47 U	<2.39 U	<2.24 U	<2.19 U	<2.21 U	<2.24 U	<2.39 U	<2.45 U	<2.27 U	<2.3 U	<2.31 U	<2.26 U
Silver	7440-22-4	**2**	8.3	110	mg/kg	<0.478 U	0.933	0.791	<0.459 U	0.942	1.06	<0.481 U	<0.451 U	<0.442 U	<0.447 U	<0.452 U	0.622	0.668	0.871	<0.463 U	<0.466 U	<0.456 U
Sodium	7440-23-5	NS	NS	NS	mg/kg	<425 U	424 J	949 J	144	326	305	<178 U	68.2	71.7 J	71.2	145	272	255	412	201	<125 U	115
Thallium	7440-28-0	NS	NS	NS	mg/kg	<1.9 U	<2.2 U	<2.93 U	<1.83 U	<2.01 U	<1.98 U	<1.91 U	<1.79 U	<1.76 U	<1.78 U	<1.8 U	<1.92 U	<1.97 U	<1.82 U	<1.84 U	<1.85 U	<1.82 U
Vanadium	7440-62-2	NS	NS	NS	mg/kg	20.1	25.5	30	17.5	51.3	23.2	30.8	15.4	12.2	12.4	20.2	21	25.7	19.8	23	16.8	13.8
Zinc	7440-66-6	**109**	2480	6600	mg/kg	**1,520**	**603**	**730**	**302**	**880**	**503**	**988**	15.6	35.7	**142**	**145**	**742**	**442**	**444**	**309**	**189**	82

Table 2
Site Management Plan
Soil Sample Analytical Results

12074 Flatlands Avenue p/o Lot 1 Site
Brooklyn, New York
BCP Site No. C224353
Langan Project No.: 100688803

Analyte	CAS Number	NYSDEC Part 375 Unrestricted Use SCOs	NYSDEC Part 375 Protection of Groundwater SCOs	NYSDEC Part 375 Restricted Use Restricted-Residential SCOs	Location	PE67	PE68	PE68	PE69	PE70	PE71	PE72	PE73	PE74	PE75	PE76	PE77	PE77	PE78	PE79	PE80	PE81
					Sample Name	PE67_20	PE68_29	DUP_20251028	PE69_20	PE70_20	PE71_20	PE72_19	PE73_20	PE74_20	PE75_19.5	PE76_19.5	PE77_19.5	PE77_20.5	PE78_19.5	PE79_20	PE80_19	PE81_20
					Sample Date	09/17/2025	10/28/2025	10/28/2025	10/01/2025	09/23/2025	09/23/2025	09/17/2025	12/05/2025	11/19/2025	09/23/2025	09/23/2025	10/01/2025	10/14/2025	09/23/2025	09/23/2025	09/17/2025	12/05/2025
					Sample Elevation	20	29	29	20	20	20	19	20	20	19.5	19.5	19.5	20.5	19.5	20	19	20
					Unit	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result
Per- and Polyfluoroalkyl Substances																						
11-Chloroeicosafluoro-3-Oxaundecane-1-Sulfonic Acid (11Cl-PF3OUdS)	763051-92-9	NS	NS	NS	mg/kg	<0.000859 UJ	<0.000995 U	<0.00133 U	<0.000827 U	<0.000909 U	<0.000897 U	<0.000867 UJ	<0.000811 UJ	<0.000795 U	<0.000804 U	<0.000814 U	<0.000868 U	<0.000891 UJ	<0.000823 U	<0.000834 U	<0.000838 UJ	<0.000822 U
1H,1H,2H,2H-Perfluorodecane Sulfonic Acid (8:2 FTS)	39108-34-4	NS	NS	NS	mg/kg	<0.000872 U	<0.00101 U	<0.00135 U	<0.00084 U	<0.000923 U	<0.000911 U	<0.00088 U	<0.000824 U	<0.000807 UJ	<0.000817 U	<0.000827 U	<0.000882 U	<0.000905 U	<0.000837 U	<0.000847 U	<0.000851 U	<0.000835 U
1H,1H,2H,2H-Perfluorohexane Sulfonic Acid (4:2 FTS)	757124-72-4	NS	NS	NS	mg/kg	<0.000852 U	<0.000987 U	<0.00132 UJ	<0.00082 U	<0.000902 U	<0.00089 U	<0.00086 U	<0.000805 U	<0.000788 U	<0.000797 U	<0.000808 U	<0.000861 UJ	<0.000883 U	<0.000817 U	<0.000827 U	<0.000831 U	<0.000815 U
1H,1H,2H,2H-Perfluorooctane Sulfonic Acid (6:2 FTS)	27619-97-2	NS	NS	NS	mg/kg	<0.000863 U	<0.001 U	<0.00134 U	<0.000831 U	<0.000914 U	<0.000902 U	<0.000871 U	<0.000816 U	<0.000799 U	<0.000808 U	<0.000819 U	<0.000873 U	<0.000895 U	<0.000828 U	<0.000838 U	<0.000842 U	<0.000826 U
2H,2H,3H,3H-Perfluorooctanoic Acid (5:3 FTCA)	914637-49-3	NS	NS	NS	mg/kg	<0.00568 U	<0.00658 U	<0.00878 U	<0.00547 U	<0.00601 U	<0.00593 U	<0.00573 U	<0.00537 U	<0.00525 U	<0.00532 U	<0.00539 U	<0.00574 U	<0.00589 U	<0.00545 U	<0.00552 U	<0.00554 U	<0.00543 U
3-Perfluoroheptyl Propanoic Acid (7:3 FTCA)	812-70-4	NS	NS	NS	mg/kg	<0.00568 U	<0.00658 U	<0.00878 U	<0.00547 U	<0.00601 U	<0.00593 U	<0.00573 U	<0.00537 U	<0.00525 U	<0.00532 U	<0.00539 U	<0.00574 U	<0.00589 U	<0.00545 U	<0.00552 U	<0.00554 U	<0.00543 U
3-Perfluoropropyl Propanoic Acid (3:3 FTCA)	356-02-5	NS	NS	NS	mg/kg	<0.00114 U	<0.00132 U	<0.00176 U	<0.00109 U	<0.0012 U	<0.00119 U	<0.00115 U	<0.00107 UJ	<0.00105 UJ	<0.00106 U	<0.00108 U	<0.00115 U	<0.00118 U	<0.00109 U	<0.0011 U	<0.00111 U	<0.00109 U
4,8-Dioxa-3H-perfluorononanoic Acid (ADONA)	919005-14-4	NS	NS	NS	mg/kg	<0.000859 U	<0.000995 UJ	<0.00133 UJ	<0.000827 U	<0.000909 U	<0.000897 U	<0.000867 U	<0.000811 UJ	<0.000795 U	<0.000804 U	<0.000814 U	<0.000868 U	<0.000891 UJ	<0.000823 U	<0.000834 U	<0.000838 U	<0.000822 U
9-Chlorohexadecafluoro-3-Oxanonane-1-Sulfonic Acid (9Cl-PF3ONS)	756426-58-1	NS	NS	NS	mg/kg	<0.00085 UJ	<0.000985 UJ	<0.00131 UJ	<0.000818 U	<0.000899 UJ	<0.000887 UJ	<0.000857 UJ	<0.000803 UJ	<0.000786 UJ	<0.000795 UJ	<0.000806 UJ	<0.000859 U	<0.000881 UJ	<0.000815 UJ	<0.000825 UJ	<0.000829 UJ	<0.000813 U
Hexafluoropropylene Oxide Dimer Acid (HFPO-DA)	13252-13-6	NS	NS	NS	mg/kg	<0.000909 U	<0.00105 UJ	<0.00141 UJ	<0.000875 U	<0.000962 U	<0.000949 U	<0.000917 U	<0.000859 UJ	<0.000841 UJ	<0.000851 U	<0.000862 U	<0.000919 U	<0.000942 UJ	<0.000871 U	<0.000882 U	<0.000887 U	<0.000869 U
N-ethyl Perfluorooctanesulfonamide (NEtFOSA)	4151-50-2	NS	NS	NS	mg/kg	<0.000227 U	<0.000263 U	<0.000351 U	<0.000219 U	<0.00024 U	<0.000237 U	<0.000229 U	<0.000215 U	<0.00021 U	<0.000213 U	<0.000215 U	<0.00023 U	<0.000236 U	<0.000218 U	<0.000221 U	<0.000222 U	<0.000217 U
N-ethyl Perfluorooctanesulfonamidoacetic Acid (NEtFOSAA)	2991-50-6	NS	NS	NS	mg/kg	0.00531	<0.000658 U	<0.000878 UJ	<0.000547 U	<0.000601 U	<0.000593 U	<0.000573 U	<0.000215 U	<0.00021 UJ	<0.000532 U	<0.000539 U	0.000998	0.0104 J	<0.000545 U	<0.000552 U	<0.000554 U	<0.000217 U
N-ethyl Perfluorooctanesulfonamidoethanol (NEtFOSE)	1691-99-2	NS	NS	NS	mg/kg	<0.00227 U	<0.00263 U	<0.00351 U	<0.00219 U	<0.0024 U	<0.00237 U	<0.00229 U	<0.00215 U	<0.0021 U	<0.00213 U	<0.00215 U	0.00099 J	<0.00236 U	<0.00218 U	<0.00221 U	<0.00222 U	<0.00217 U
N-methyl Perfluorooctanesulfonamide (NMeFOSA)	31506-32-8	NS	NS	NS	mg/kg	<0.000227 U	<0.000263 U	<0.000351 U	<0.000219 U	<0.00024 U	<0.000237 U	<0.000229 U	<0.000215 U	<0.00021 U	<0.000213 U	<0.000215 U	<0.00023 U	<0.000236 U	<0.000218 U	<0.000221 U	<0.000222 U	<0.000217 U
N-methyl Perfluorooctanesulfonamidoacetic Acid (NMeFOSAA)	2355-31-9	NS	NS	NS	mg/kg	0.000522	<0.000263 UJ	<0.000351 UJ	<0.000219 U	<0.00024 U	<0.000237 U	<0.000229 U	<0.000215 UJ	<0.00021 UJ	<0.000213 U	<0.000215 U	0.000212 J	0.000707	<0.000218 U	<0.000221 U	<0.000222 U	<0.000217 U
N-methyl Perfluorooctanesulfonamidoethanol (NMeFOSE)	24448-09-7	NS	NS	NS	mg/kg	<0.00227 U	<0.00263 U	<0.00351 U	<0.00219 U	<0.0024 U	<0.00237 U	<0.00229 U	<0.00215 U	<0.0021 U	<0.00213 U	<0.00215 U	<0.0023 U	<0.00236 U	<0.00218 U	<0.00221 U	<0.00222 U	<0.00217 U
Nonafluoro-3,6-dioxaheptanoic Acid (NFDHA)	151772-58-6	NS	NS	NS	mg/kg	<0.000454 UJ	<0.000527 UJ	<0.000703 UJ	<0.000437 UJ	<0.000481 U	<0.000475 U	<0.000459 UJ	<0.000429 U	<0.00042 UJ	<0.000425 U	<0.000431 U	<0.000459 UJ	<0.000471 U	<0.000436 U	<0.000441 U	<0.000443 UJ	<0.000435 U
Perfluoro(2-ethoxyethane)sulfonic Acid (PFEESA)	113507-82-7	NS	NS	NS	mg/kg	<0.000404 U	<0.000469 U	<0.000625 U	<0.000389 U	<0.000428 U	<0.000422 U	<0.000408 U	<0.000382 U	<0.000374 UJ	<0.000379 U	<0.000383 U	<0.000409 U	<0.000419 U	<0.000388 U	<0.000393 U	<0.000395 U	<0.000387 U
Perfluoro-3-methoxypropanoic Acid (PFMPA)	377-73-1	NS	NS	NS	mg/kg	<0.000454 U	<0.000527 U	<0.000703 U	<0.000437 U	<0.000481 U	<0.000475 U	<0.000459 U	<0.000429 UJ	<0.00042 UJ	<0.000425 U	<0.000431 U	<0.000459 U	<0.000471 U	<0.000436 U	<0.000441 U	<0.000443 U	<0.000435 U
Perfluoro-4-methoxybutanoic Acid (PFMBA)	863090-89-5	NS	NS	NS	mg/kg	<0.000454 U	<0.000527 U	<0.000703 U	<0.000437 U	<0.000481 U	<0.000475 U	<0.000459 U	<0.000429 UJ	<0.00042 UJ	<0.000425 U	<0.000431 U	<0.000459 U	<0.000471 U	<0.000436 U	<0.000441 U	<0.000443 U	<0.000435 U
Perfluorobutanesulfonic Acid (PFBS)	375-73-5	NS	NS	NS	mg/kg	<0.000201 U	<0.000233 U	<0.000311 U	<0.000194 U	<0.000213 U	<0.00021 U	<0.000203 U	<0.00019 U	<0.000186 UJ	<0.000188 U	<0.000191 U	<0.000203 U	<0.000209 U	<0.000193 U	<0.000195 U	<0.000196 U	<0.000192 U
Perfluorobutanoic Acid (PFBA)	375-22-4	NS	NS	NS	mg/kg	<0.000909 U	<0.00105 U	<0.00141 U	<0.000875 U	<0.000962 U	<0.000949 U	<0.000917 U	<0.000859 U	<0.000841 U	<0.000851 U	<0.000862 U	<0.000919 U	<0.000942 U	<0.000871 U	<0.000882 U	<0.000887 U	<0.000869 U
Perfluorodecanesulfonic Acid (PFDS)	335-77-3	NS	NS	NS	mg/kg	<0.000219 U	<0.000254 U	<0.000339 U	<0.000211 U	<0.000232 U	<0.000229 U	<0.000221 U	<0.000207 U	<0.000203 UJ	<0.000205 U	<0.000208 U	<0.000222 U	<0.000227 U	<0.00021 U	<0.000213 U	<0.000214 U	<0.00021 U
Perfluorodecanoic Acid (PFDA)	335-76-2	NS	NS	NS	mg/kg	0.000181 J	<0.000263 UJ	<0.000351 UJ	<0.000219 U	<0.00024 U	0.000108 J	<0.000229 U	<0.000215 U	<0.00021 U	<0.000213 U	<0.000215 U	<0.00023 U	<0.000236 U	0.0000908 J	<0.000221 U	<0.000222 U	<0.000217 U
Perfluorododecanesulfonic Acid (PFDoS)	79780-39-5	NS	NS	NS	mg/kg	<0.00022 U	<0.000255 U	<0.000341 U	<0.000212 U	<0.000233 U	<0.00023 U	<0.000222 U	<0.000208 U	<0.000204 UJ	<0.000206 U	<0.000209 U	<0.000223 U	<0.000229 U	<0.000211 U	<0.000214 U	<0.000215 U	<0.000211 U
Perfluorododecanoic Acid (PFDoA)	307-55-1	NS	NS	NS	mg/kg	<0.000227 U	<0.000263 U	<0.000351 U	<0.000219 U	<0.00024 U	<0.000237 U	<0.000229 U	<0.000215 U	<0.00021 U	<0.000213 U	<0.000215 U	<0.00023 U	<0.000236 U	<0.000218 U	<0.000221 U	<0.000222 U	<0.000217 U
Perfluoroheptanesulfonic Acid (PFHpS)	375-92-8	NS	NS	NS	mg/kg	0.000093 J	<0.000263 U	<0.000351 U	<0.000219 U	<0.00024 U	<0.000237 U	<0.000229 U	<0.000215 U	<0.00021 UJ	<0.000213 U	<0.000215 U	<0.00023 U	<0.000236 U	<0.000218 U	<0.000221 U	<0.000222 U	<0.000217 U
Perfluoroheptanoic Acid (PFHpA)	375-85-9	NS	NS	NS	mg/kg	<0.000227 U	<0.000263 U	<0.000351 U	<0.000219 U	<0.00024 U	<0.000237 U	<0.000229 U	<0.000215 U	<0.00021 U	<0.000213 U	<0.000215 U	<0.00023 U	<0.000236 U	<0.000218 U	<0.000221 U	<0.000222 U	<0.000217 U
Perfluorohexanesulfonic Acid (PFHxS)	355-46-4	NS	NS	NS	mg/kg	0.000352	<0.000241 U	0.000254 J	0.000229	<0.00022 U	0.000328	<0.00021 U	<0.000196 U	<0.000192 UJ	0.000452	0.00041	<0.00021 U	<0.000216 U	0.000171 J	<0.000202 U	<0.000203 U	<0.000199 U
Perfluorohexanoic Acid (PFHxA)	307-24-4	NS	NS	NS	mg/kg	<0.000227 U	<0.000263 U	<0.000351 U	<0.000219 U	<0.00024 U	<0.000237 U	<0.000229 U	<0.000215 U	<0.00021 U	<0.000213 U	<0.000215 U	<0.00023 U	<0.000236 U	<0.000218 U	<0.000221 U	<0.000222 U	<0.000217 U
Perfluorononanesulfonic Acid (PFNS)	68259-12-1	NS	NS	NS	mg/kg	<0.000218 U	<0.000253 U	<0.000337 U	<0.00021 U	<0.000231 U	<0.000228 U	<0.00022 U	<0.000206 U	<0.000202 UJ	<0.000204 U	<0.000207 U	<0.000221 U	<0.000226 U	<0.000209 U	<0.000212 U	<0.000213 U	<0.000209 U
Perfluorononanoic Acid (PFNA)	375-95-1	NS	NS	NS	mg/kg	<0.000227 U	<0.000263 U	<0.000351 U	<0.000219 U	<0.00024 U	<0.000237 U	<0.000229 U	<0.000215 U	<0.00021 UJ	<0.000213 U	<0.000215 U	<0.00023 U	<0.000236 U	<0.000218 U	<0.000221 U	<0.000222 U	<0.000217 U
Perfluorooctanesulfonamide (PFOSA)	754-91-6	NS	NS	NS	mg/kg	0.000324	<0.000263 U	<0.000351 U	<0.000219 U	0.000217 J	0.000121 J	<0.000229 U	<0.000215 UJ	<0.00021 UJ	<0.000213 U	<0.000215 U	0.000104 J	0.000213 J	0.000079 J	0.0000556 J	<0.000222 U	<0.000217 U
Perfluorooctanesulfonic Acid (PFOS)	1763-23-1	**0.00088**	0.001	0.044	mg/kg	**0.00839**	0.000163 J	**0.00179 J**	0.000483	**0.00119**	**0.00137**	0.000726	<0.0002 U	0.000417 J	**0.00162**	0.000456	0.000589	**0.00502**	0.00064	0.000345	0.000141 J	0.000118 J
Perfluorooctanoic Acid (PFOA)	335-67-1	**0.00066**	0.0008	0.033	mg/kg	0.00066	<0.000263 U	0.000433	0.00016 J	0.000334	0.000441	0.000108 J	0.0000863 J	<0.00021 U	0.000551	0.000319	0.000161 J	0.000302	0.000182 J	0.000202 J	0.000148 J	0.0000972 J
Perfluoropentanesulfonic Acid (PFPeS)	2706-91-4	NS	NS	NS	mg/kg	<0.000214 U	<0.000248 U	<0.00033 U	<0.000206 U	<0.000226 U	<0.000223 U	<0.000216 U	<0.000202 U	<0.000198 UJ	<0.0002 U	<0.000202 U	<0.000216 U	0.0000846 J	<0.000205 U	<0.000207 U	<0.000208 U	<0.000204 U
Perfluoropentanoic Acid (PFPeA)	2706-90-3	NS	NS	NS	mg/kg	<0.000454 U	<0.000527 U	<0.000703 U	<0.000437 U	<0.000481 U	<0.000475 U	<0.000459 U	<0.000429 UJ	<0.00042 UJ	<0.000425 U	<0.000431 U	<0.000459 U	<0.000471 U	<0.000436 U	<0.000441 U	<0.000443 U	<0.000435 U
Perfluorotetradecanoic Acid (PFTeDA)	376-06-7	NS	NS	NS	mg/kg	<0.000227 U	<0.000263 U	<0.000351 U	<0.000219 U	<0.00024 U	<0.000237 U	<0.000229 U	<0.000215 U	<0.00021 U	<0.000213 U	<0.000215 U	<0.00023 U	<0.000236 U	<0.000218 U	<0.000221 U	<0.000222 U	<0.000217 U
Perfluorotridecanoic Acid (PFTrDA)	72629-94-8	NS	NS	NS	mg/kg	<0.000227 U	<0.000263 U	<0.000351 U	<0.000219 U	<0.00024 U	<0.000237 U	<0.000229 U	<0.000215 U	<0.00021 U	<0.000213 U	<0.000215 U	<0.00023 U	<0.000236 U	<0.000218 U	<0.000221 U	<0.000222 U	<0.000217 U
Perfluoroundecanoic Acid (PFUnA)	2058-94-8	NS	NS	NS	mg/kg	<0.000227 U	<0.000263 U	<0.000351 U	<0.000219 U	<0.00024 U	<0.000237 U	<0.000229 U	<0.000215 U	<0.00021 U	<0.000213 U	<0.000215 U	<0.00023 U	<0.000236 U	<0.000218 U	<0.000221 U	<0.000222 U	<0.000217 U
General Chemistry																						
Solids, Percent	SOLID	NS	NS	NS	Percent	87.9	76	56.9	91.4	83.2	84.3	87.2	93.2	95	94	92.8	87.1	84.9	91.8	90.7	90.2	92

Table 2
Site Management Plan
Soil Sample Analytical Results

12074 Flatlands Avenue p/o Lot 1 Site
Brooklyn, New York
BCP Site No. C224353
Langan Project No.: 100688803

Analyte	CAS Number	NYSDEC Part 375 Unrestricted Use SCOs	NYSDEC Part 375 Protection of Groundwater SCOs	NYSDEC Part 375 Restricted Use Restricted-Residential SCOs	Location	PE82	PE83	PE84	PE84	PE84	PE84	PE85	PE86	PE87	PE88	PE89	PE90	PE91	PE92	PE93	PE94	PE95
					Sample Name	PE82_20	PE83_20	PE84_20	PE84_21	DUP_20251119	PE84_22	PE85_20	PE86_20	PE87_19.5	PE88_19.5	PE89_15	PE90_20	PE91_20	PE92_20	PE93_20	PE94_20	PE95_19.5
					Sample Date	11/19/2025	11/04/2025	10/28/2025	11/19/2025	11/19/2025	12/05/2025	10/28/2025	10/01/2025	10/01/2025	09/17/2025	10/14/2025	10/28/2025	11/04/2025	10/28/2025	10/28/2025	10/28/2025	10/01/2025
					Sample Elevation	20	20	20	21	21	22	20	20	19.5	19.5	15	20	20	20	20	20	19.5
					Unit	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result
Volatile Organic Compounds																						
1,1,1,2-Tetrachloroethane	630-20-6	NS	NS	NS	mg/kg	<0.0057 U	<0.025 U	<0.07 U	<0.0062 U	<0.0068 U	<0.0056 U	<0.029 U	<0.024 U	<0.023 U	NA	<0.022 U	<0.032 U	<0.026 U	<0.031 U	<0.045 U	<0.029 U	<0.025 U
1,1,1-Trichloroethane	71-55-6	0.68	0.68	100	mg/kg	<0.0057 U	<0.0063 U	<0.018 U	<0.0062 U	<0.0068 U	<0.0056 U	<0.0074 U	<0.0061 U	<0.0058 U	<0.007 U	<0.0056 U	<0.0081 U	<0.0065 U	<0.0078 U	<0.011 U	<0.0072 U	<0.0062 U
1,1,2,2-Tetrachloroethane	79-34-5	NS	NS	NS	mg/kg	<0.0057 U	<0.0063 U	<0.018 U	<0.0062 U	<0.0068 U	<0.0056 U	<0.0074 U	<0.0061 U	<0.0058 U	<0.007 U	<0.0056 U	<0.0081 U	<0.0065 U	<0.0078 U	<0.011 U	<0.0072 U	<0.59 U
1,1,2-Trichloro-1,2,2-Trifluoroethane	76-13-1	NS	NS	NS	mg/kg	<0.0057 U	<0.0063 U	<0.018 U	<0.0062 U	<0.0068 U	<0.0056 U	<0.0074 U	<0.0061 U	<0.0058 U	<0.007 U	<0.0056 U	<0.0081 U	<0.0065 U	<0.0078 U	<0.011 U	<0.0072 U	<0.0062 U
1,1,2-Trichloroethane	79-00-5	NS	NS	NS	mg/kg	<0.0057 U	<0.0063 U	<0.018 U	<0.0062 U	<0.0068 U	<0.0056 U	<0.0074 U	<0.0061 U	<0.0058 U	<0.007 U	<0.0056 U	<0.0081 U	<0.0065 U	<0.0078 U	<0.011 U	<0.0072 U	<0.0062 U
1,1-Dichloroethane	75-34-3	0.27	0.27	47	mg/kg	<0.0057 U	<0.0063 U	<0.018 U	<0.0062 U	<0.0068 U	<0.0056 U	<0.0074 U	<0.0061 U	<0.0058 U	<0.007 U	<0.0056 U	<0.0081 U	<0.0065 U	<0.0078 U	<0.011 U	<0.0072 U	<0.0062 U
1,1-Dichloroethene	75-35-4	0.24	0.33	0.98	mg/kg	<0.0057 U	<0.0063 U	<0.018 U	<0.0062 U	<0.0068 U	<0.0056 U	<0.0074 U	<0.0061 U	<0.0058 U	<0.007 U	<0.0056 U	<0.0081 U	<0.0065 U	<0.0078 U	<0.011 U	<0.0072 U	<0.0062 U
1,1-Dichloropropene	563-58-6	NS	NS	NS	mg/kg	<0.0057 U	NA	NA	<0.0062 U	<0.0068 U	<0.0056 U	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
1,2,3-Trichlorobenzene	87-61-6	NS	NS	NS	mg/kg	<0.0057 U	<0.0063 U	<0.018 U	<0.0062 U	<0.0068 U	<0.0056 U	<0.0074 U	<0.0061 U	<0.0058 U	<0.007 U	<0.0056 U	<0.0081 U	<0.0065 U	<0.0078 U	<0.011 U	<0.0072 U	<0.59 U
1,2,3-Trichloropropane	96-18-4	NS	NS	NS	mg/kg	<0.0057 U	<0.0063 U	<0.018 U	<0.0062 U	<0.0068 U	<0.0056 U	<0.0074 U	<0.0061 U	<0.0058 U	NA	<0.0056 U	<0.0081 U	<0.0065 U	<0.0078 U	<0.011 U	<0.0072 U	<0.59 U
1,2,4-Trichlorobenzene	120-82-1	NS	NS	NS	mg/kg	<0.0057 U	<0.0063 U	<0.018 U	<0.0062 U	<0.0068 U	<0.0056 U	<0.0074 U	<0.0061 U	<0.0058 U	<0.007 U	<0.0056 U	<0.0081 U	<0.0065 U	<0.0078 U	<0.011 U	<0.0072 U	<0.59 U
1,2,4-Trimethylbenzene	95-63-6	5.9	5.9	100	mg/kg	<0.0057 U	<0.0063 U	<0.018 U	<0.0062 U	<0.0068 U	<0.0056 U	<0.0074 U	<0.0061 U	<0.0058 U	<0.007 U	<0.0056 U	<0.0081 U	<0.0065 U	<0.0078 U	<0.011 U	<0.0072 U	<0.59 U
1,2-Dibromo-3-Chloropropane	96-12-8	NS	NS	NS	mg/kg	<0.0057 U	<0.0063 U	<0.018 U	<0.0062 U	<0.0068 U	<0.0056 U	<0.0074 U	<0.0061 U	<0.0058 U	<0.007 U	<0.0056 U	<0.0081 U	<0.0065 U	<0.0078 U	<0.011 U	<0.0072 U	<0.59 U
1,2-Dibromoethane (Ethylene Dibromide)	106-93-4	NS	NS	NS	mg/kg	<0.0057 U	<0.0063 U	<0.018 U	<0.0062 U	<0.0068 U	<0.0056 U	<0.0074 U	<0.0061 U	<0.0058 U	<0.007 U	<0.0056 U	<0.0081 U	<0.0065 U	<0.0078 U	<0.011 U	<0.0072 U	<0.0062 U
1,2-Dichlorobenzene	95-50-1	1.1	1.1	100	mg/kg	<0.0057 U	<0.0063 U	<0.018 U	<0.0062 U	<0.0068 U	<0.0056 U	<0.0074 U	<0.0061 U	<0.0058 U	<0.007 U	<0.0056 U	<0.0081 U	<0.0065 U	<0.0078 U	<0.011 U	<0.0072 U	<0.59 U
1,2-Dichloroethane	107-06-2	0.02	0.02	5.8	mg/kg	<0.0057 U	<0.0063 U	<0.018 U	<0.0062 U	<0.0068 U	<0.0056 U	<0.0074 U	<0.0061 U	<0.0058 U	<0.007 U	<0.0056 U	<0.0081 U	<0.0065 U	<0.0078 U	<0.011 U	<0.0072 U	<0.0062 U
1,2-Dichloropropane	78-87-5	NS	NS	NS	mg/kg	<0.0057 U	<0.0063 U	<0.018 U	<0.0062 U	<0.0068 U	<0.0056 U	<0.0074 U	<0.0061 U	<0.0058 U	<0.007 U	<0.0056 U	<0.0081 U	<0.0065 U	<0.0078 U	<0.011 U	<0.0072 U	<0.0062 U
1,3,5-Trimethylbenzene (Mesitylene)	108-67-8	3.1	3.1	100	mg/kg	<0.0057 U	<0.0063 U	<0.018 U	<0.0062 U	<0.0068 U	<0.0056 U	<0.0074 U	<0.0061 U	<0.0058 U	<0.007 U	<0.0056 U	<0.0081 U	<0.0065 U	<0.0078 U	<0.011 U	<0.0072 U	<0.59 U
1,3-Dichlorobenzene	541-73-1	2.6	2.6	38	mg/kg	<0.0057 U	<0.0063 U	<0.018 U	<0.0062 U	<0.0068 U	<0.0056 U	<0.0074 U	<0.0061 U	<0.0058 U	<0.007 U	<0.0056 U	<0.0081 U	<0.0065 U	<0.0078 U	<0.011 U	<0.0072 U	<0.59 U
1,3-Dichloropropane	142-28-9	NS	NS	NS	mg/kg	<0.0057 U	NA	NA	<0.0062 U	<0.0068 U	<0.0056 U	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
1,4-Dichlorobenzene	106-46-7	1.8	1.8	24	mg/kg	<0.0057 U	<0.0063 U	<0.018 U	<0.0062 U	<0.0068 U	<0.0056 U	<0.0074 U	<0.0061 U	<0.0058 U	<0.007 U	<0.0056 U	<0.0081 U	<0.0065 U	<0.0078 U	<0.011 U	<0.0072 U	<0.59 U
1,4-Dioxane (P-Dioxane)	123-91-1	0.1	0.1	5.7	mg/kg	NA	NA	NA	NA	NA	NA	NA	NA	NA	<0.11 U	NA	NA	NA	NA	NA	NA	NA
2,2-Dichloropropane	594-20-7	NS	NS	NS	mg/kg	<0.0057 U	NA	NA	<0.0062 U	<0.0068 U	<0.0056 U	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
2-Chlorotoluene	95-49-8	NS	NS	NS	mg/kg	<0.0057 U	NA	NA	<0.0062 U	<0.0068 U	<0.0056 U	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
2-Hexanone (MBK)	591-78-6	NS	NS	NS	mg/kg	<0.0057 U	<0.032 U	<0.088 U	<0.0062 U	<0.0068 U	<0.0056 U	<0.037 U	<0.031 U	<0.029 U	<0.035 U	<0.028 U	<0.041 U	<0.032 U	<0.039 U	<0.057 U	<0.036 U	<0.031 U
4-Chlorotoluene	106-43-4	NS	NS	NS	mg/kg	<0.0057 U	NA	NA	<0.0062 U	<0.0068 U	<0.0056 U	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
Acetone	67-64-1	**0.03**	0.03	100	mg/kg	**0.057**	0.03 JS	**0.098 S**	**0.063**	**0.098**	**0.059**	**0.059 S**	<0.061 U	<0.058 U	0.014 JS	<0.05 U	0.03 JS	<0.05 U	<0.05 U	<0.05 U	<0.05 U	<0.062 U
Acrolein	107-02-8	NS	NS	NS	mg/kg	<0.011 U	<0.0063 U	<0.018 U	<0.012 U	<0.014 U	<0.011 U	<0.0074 U	<0.0061 U	<0.0058 U	NA	<0.0056 U	<0.0081 U	<0.0065 U	<0.0078 U	<0.011 U	<0.0072 U	<0.0062 U
Acrylonitrile	107-13-1	NS	NS	NS	mg/kg	<0.0057 U	<0.025 U	<0.07 U	<0.0062 U	<0.0068 U	<0.0056 U	<0.029 U	<0.024 U	<0.023 U	NA	<0.022 U	<0.032 U	<0.026 U	<0.031 U	<0.045 U	<0.029 U	<0.025 U
Benzene	71-43-2	0.06	0.06	3.7	mg/kg	<0.0057 U	<0.0063 U	<0.018 U	<0.0062 U	<0.0068 U	<0.0056 U	<0.0074 U	<0.0061 U	<0.0058 U	<0.007 U	<0.0056 U	<0.0081 U	<0.0065 U	<0.0078 U	<0.011 U	<0.0072 U	<0.0062 U
Bromobenzene	108-86-1	NS	NS	NS	mg/kg	<0.0057 U	NA	NA	<0.0062 U	<0.0068 U	<0.0056 U	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
Bromochloromethane	74-97-5	NS	NS	NS	mg/kg	<0.0057 U	<0.0063 U	<0.018 U	<0.0062 U	<0.0068 U	<0.0056 U	<0.0074 U	<0.0061 U	<0.0058 U	<0.007 U	<0.0056 U	<0.0081 U	<0.0065 U	<0.0078 U	<0.011 U	<0.0072 U	<0.0062 U
Bromodichloromethane	75-27-4	NS	NS	NS	mg/kg	<0.0057 U	<0.0063 U	<0.018 U	<0.0062 U	<0.0068 U	<0.0056 U	<0.0074 U	<0.0061 U	<0.0058 U	<0.007 U	<0.0056 U	<0.0081 U	<0.0065 U	<0.0078 U	<0.011 U	<0.0072 U	<0.0062 U
Bromoform	75-25-2	NS	NS	NS	mg/kg	<0.0057 U	<0.0063 U	<0.018 U	<0.0062 U	<0.0068 U	<0.0056 U	<0.0074 U	<0.0061 U	<0.0058 U	<0.007 U	<0.0056 U	<0.0081 U	<0.0065 U	<0.0078 U	<0.011 U	<0.0072 U	<0.0062 U
Bromomethane	74-83-9	NS	NS	NS	mg/kg	<0.0057 U	<0.0063 U	<0.018 U	<0.0062 U	<0.0068 U	<0.0056 U	<0.0074 U	<0.0061 U	<0.0058 U	<0.007 U	<0.0056 U	<0.0081 U	<0.0065 U	<0.0078 U	<0.011 U	<0.0072 U	<0.0062 U
Carbon Disulfide	75-15-0	NS	NS	NS	mg/kg	<0.0057 U	<0.0063 U	0.0064 J	<0.0062 U	0.0044 J	<0.0056 U	0.0028 J	<0.0061 U	<0.0058 U	<0.007 U	<0.0056 U	<0.0081 U	<0.0065 U	<0.0078 U	<0.011 U	<0.0072 U	<0.0062 U
Carbon Tetrachloride	56-23-5	0.76	0.76	7.1	mg/kg	<0.0057 U	<0.0063 U	<0.018 U	<0.0062 U	<0.0068 U	<0.0056 U	<0.0074 U	<0.0061 U	<0.0058 U	<0.007 U	<0.0056 U	<0.0081 U	<0.0065 U	<0.0078 U	<0.011 U	<0.0072 U	<0.0062 U
Chlorobenzene	108-90-7	4.5	4.5	100	mg/kg	<0.0057 U	<0.0063 U	<0.018 U	<0.0062 U	<0.0068 U	<0.0056 U	<0.0074 U	<0.0061 U	<0.0058 U	<0.007 U	<0.0056 U	<0.0081 U	<0.0065 U	<0.0078 U	<0.011 U	<0.0072 U	<0.0062 U
Chloroethane	75-00-3	NS	NS	NS	mg/kg	<0.0057 U	<0.0063 U	<0.018 U	<0.0062 U	<0.0068 U	<0.0056 U	<0.0074 U	<0.0061 U	<0.0058 U	<0.007 U	<0.0056 U	<0.0081 U	<0.0065 U	<0.0078 U	<0.011 U	<0.0072 U	<0.0062 U
Chloroform	67-66-3	0.37	0.37	24	mg/kg	<0.0057 U	<0.0063 U	<0.018 U	<0.0062 U	<0.0068 U	<0.0056 U	<0.0074 U	<0.0061 U	<0.0058 U	<0.007 U	<0.0056 U	<0.0081 U	<0.0065 U	<0.0078 U	<0.011 U	<0.0072 U	<0.0062 U
Chloromethane	74-87-3	NS	NS	NS	mg/kg	<0.0057 U	<0.0063 U	<0.018 U	<0.0062 U	<0.0068 U	<0.0056 U	<0.0074 U	<0.0061 U	<0.0058 U	<0.007 U	<0.0056 U	<0.0081 U	<0.0065 U	<0.0078 U	<0.011 U	<0.0072 U	<0.0062 U
Cis-1,2-Dichloroethene	156-59-2	0.19	0.19	41	mg/kg	<0.0057 U	<0.0063 U	<0.018 U	<0.0062 U	<0.0068 U	<0.0056 U	<0.0074 U	<0.0061 U	<0.0058 U	<0.007 U	<0.0056 U	<0.0081 U	<0.0065 U	<0.0078 U	<0.011 U	<0.0072 U	<0.0062 U
Cis-1,3-Dichloropropene	10061-01-5	NS	NS	NS	mg/kg	<0.0057 U	<0.0063 U	<0.018 U	<0.0062 U	<0.0068 U	<0.0056 U	<0.0074 U	<0.0061 U	<0.0058 U	<0.007 U	<0.0056 U	<0.0081 U	<0.0065 U	<0.0078 U	<0.011 U	<0.0072 U	<0.0062 U
Cyclohexane	110-82-7	NS	NS	NS	mg/kg	<0.0057 U	<0.0063 U	<0.018 U	<0.0062 U	<0.0068 U	<0.0056 U	<0.0074 U	<0.0061 U	<0.0058 U	<0.007 U	<0.0056 U	<0.0081 U	<0.0065 U	<0.0078 U	<0.011 U	<0.0072 U	<0.0062 U
Cymene	99-87-6	NS	NS	NS	mg/kg	<0.0057 U	<0.0063 U	0.73 J	<0.0062 U	<0.0068 U	<0.0056 U	<0.0074 U	1.1	<0.0058 U	NA	<0.0056 U	<0.0081 U	<0.0065 U	<0.0078 U	<0.011 U	<0.0072 U	<0.59 U
Dibromochloromethane	124-48-1	NS	NS	NS	mg/kg	<0.0057 U	<0.0063 U	<0.018 U	<0.0062 U	<0.0068 U	<0.0056 U	<0.0074 U	<0.0061 U	<0.0058 U	<0.007 U	<0.0056 U	<0.0081 U	<0.0065 U	<0.0078 U	<0.011 U	<0.0072 U	<0.0062 U
Dibromomethane	74-95-3	NS	NS	NS	mg/kg	<0.0057 U	<0.0063 U	<0.018 U	<0.0062 U	<0.0068 U	<0.0056 U	<0.0074 U	<0.0061 U	<0.0058 U	NA	<0.0056 U	<0.0081 U	<0.0065 U	<0.0078 U	<0.011 U	<0.0072 U	<0.0062 U
Dichlorodifluoromethane	75-71-8	NS	NS	NS	mg/kg	<0.0057 U	<0.0063 U	<0.018 U	<0.0062 U	<0.0068 U	<0.0056 UJ	<0.0074 U	<0.0061 U	<0.0058 U	<0.007 U	<0.0056 U	<0.0081 U	<0.0065 U	<0.0078 U	<0.011 U	<0.0072 U	<0.0062 U
Ethylbenzene	100-41-4	1	1	76	mg/kg	<0.0057 U	<0.0063 U	<0.018 U	<0.0062 U	<0.0068 U	<0.0056 U	<0.0074 U	<0.0061 U	<0.0058 U	<0.007 U	<0.0056 U	<0.0081 U	<0.0065 U	<0.0078 U	<0.011 U	<0.0072 U	<0.0062 U
Hexachlorobutadiene	87-68-3	NS	NS	NS	mg/kg	<0.0057 UJ	<0.0063 U	<0.018 U	<0.0062 UJ	<0.0068 UJ	<0.0056 U	<0.0074 U	<0.0061 U	<0.0058 U	NA	<0.0056 U	<0.0081 U	<0.0065 U	<0.0078 U	<0.011 U	<0.0072 U	<0.59 U
Isopropylbenzene (Cumene)	98-82-8	NS	NS	NS	mg/kg	<0.0057 U	<0.0063 U	<0.018 U	<0.0062 U	<0.0068 U	<0.0056 U	<0.0074 U	<0.0061 U	<0.0058 U	<0.007 U	<0.0056 U	<0.0081 U	<0.0065 U	<0.0078 U	<0.011 U	<0.0072 U	<0.59 U
M,P-Xylene	179601-23-1	NS	NS	NS	mg/kg	<0.011 U	<0.0063 U	<0.018 U	<0.012 U	<0.014 U	<0.011 U	<0.0074 U	<0.0061 U	<0.0058 U	<0.007 U	<0.0056 U	<0.0081 U	<0.0065 U	<0.0078 U	<0.011 U	<0.0072 U	<0.0062 U
Methyl Acetate	79-20-9	NS	NS	NS	mg/kg	<0.0057 U	<0.063 U	<0.18 U	<0.0062 U	<0.0068 U	<0.0056 U	<0.074 U	<0.061 U	<0.058 U	<0.07 U	<0.056 U	<0.081 U	<0.065 U	<0.078 U	<0.11 U	<0.072 U	<0.062 U
Methyl Ethyl Ketone (2-Butanone)	78-93-3	0.1	0.1	100	mg/kg	<0.0057 U	<0.038 U	0.025 J	0.0066 J	0.01 J	<0.0056 U	0.014 J	<0.037 U	<0.035 U	<0.042 U	<0.034 U	<0.049 U	<0.039 U	<0.047 U	<0.068 U	<0.043 U	<0.037 U
Methyl Isobutyl Ketone (4-Methyl-2-Pentanone)	108-10-1	NS	NS	NS	mg/kg	<0.0057 U	<0.032 U	<0.088 U	<0.0062 U	<0.0068 U	<0.0056 U	<0.037 U	<0.031 U	<0.029 U	<0.035 U	<0.028 U	<0.041 U	<0.032 U	<0.039 U	<0.057 U	<0.036 U	<0.031 U
Methylcyclohexane	108-87-2	NS	NS	NS	mg/kg	<0.0057 U	<0.0063 U	<0.018 U	<0.0062 U	<0.0068 U	<0.0056 U	<0.0074 U	<0.0061 U	<0.0058 U	<0.007 U	<0.0056 U	<0.0081 U	<0.0065 U	<0.0078 U	<0.011 U	<0.0072 U	<0.0062 U
Methylene Chloride	75-09-2	0.05	0.05	81	mg/kg	<0.011 U	<0.032 U	<0.05 U	<0.012 U	<0.014 U	<0.011 U	<0.037 U	<0.031 U	<0.029 U	<0.007 U	<0.028 U	<0.041 U	<0.032 U	<0.039 U	<0.05 U	<0.036 U	<0.031 U
n-Butylbenzene	104-51-8	18	18	100	mg/kg	<0.0057 U	<0.0063 U	<0.018 U	<0.0062 U	<0.0068 U	<0.0056 U	<0.0074 U	<0.0061 U	<0.0058 U	NA	<0.0056 U	<0.0081 U	<0.0065 U	<0.0078 U	<0.011 U	<0.0072 U	<0.59 U
n-Propylbenzene	103-65-1	5	5	100	mg/kg	<0.0057 U	<0.0063 U	<0.018 U	<0.0062 U	<0.0068 U	<0.0056 U	<0.0074 U	<0.0061 U	<0.0058 U	NA	<0.0056 U	<0.0081 U	<0.0065 U	<0.0078 U	<0.011 U	<0.0072 U	<0.59 U
o-Xylene (1,2-Dimethylbenzene)	95-47-6	NS	NS	NS	mg/kg	<0.0057 U	<0.0063 U	<0.018 U	<0.0062 U	<0.0068 U	<0.0056 U	<0.0074 U	<0.0061 U	<0.0058 U	<0.007 U	<0.0056 U	<0.0081 U	<0.0065 U	<0.0078 U	<0.011 U	<0.0072 U	<0.0062 U
Sec-Butylbenzene	135-98-8	25	25	100	mg/kg	<0.0057 U	<0.0063 U	<0.018 U	<0.0062 U	<0.0068 U	<0.0056 U	<0.0074 U	<0.0061 U	<0.0058 U	NA	<0.0056 U	<0.0081 U	<0.0065 U	<0.0078 U	<0.011 U	<0.0072 U	<0.59 U
Styrene	100-42-5	NS	NS	NS	mg/kg	<0.0057 U	<0.0063 U	<0.018 U	<0.0062 U	<0.0068 U	<0.0056 U	<0.0074 U	<0.0061 U	<0.0058 U	<0.007 U	<0.0056 U	<0.0081 U	<0.0065 U	<0.0078 U	<0.011 U	<0.0072 U	<0.0062 U
T-Butylbenzene	98-06-6	11	11	100	mg/kg	<0.0057 U	<0.0063 U	<0.018 U	<0.0062 U	<0.0068 U	<0.0056 U	<0.0074 U	<0.0061 U	<0.0058 U	NA	<0.0056 U	<0.0081 U	<0.0065 U	<0.0078 U	<0.011 U	<0.0072 U	<0.59 U
Tert-Butyl Alcohol	75-65-0	NS	NS	NS	mg/kg	<0.028 U	<0.13 U	<0.35 U	<0.031 U	<0.034 U	<0.028 U	<0.15 U	<0.12 U	<0.12 U	NA	<0.11 U	<0.16 U	<0.13 U	<0.16 U	<0.23 U	<0.14 U	<0.12 U
Tert-Butyl Methyl Ether (MTBE)	1634-04-4	0.1	0.1	100	mg/kg	<0.0057 U	<0.013 U	<0.035 U	<0.0062 U	<0.0068 U	<0.0056 U	<0.015 U	<0.012 U	<0.012 U	<0.014 U	<0.011 U	<0.016 U	<0.013 U	<0.016 U	<0.023 U	<0.014 U	<0.012 U
Tetrachloroethene (PCE)	127-18-4	1.3	1.3	18	mg/kg	<0.0057 U	<0.0063 U	<0.018 U	<0.0062 U	<0.0068 U	<0.0056 U	<0.0074 U	<0.0061 U	<0.0058 U	<0.007 U	<0.0056 U	<0.0081 U	<0.0065 U	<0.0078 U	<0.011 U	<0.0072 U	<0.0062 U
Toluene	108-88-3	0.7	0.7	100	mg/kg	<0.0057 U	<0.0063 U	<0.018 U	<0.0062 U	<0.0068 U	<0.0056 U	<0.0074 U	<0.0061 U	<0.0058 U	<0.007 U	<0.0056 U	<0.0081 U	<0.0065 U	<0.0078 U	<0.011 U	<0.0072 U	<0.0062 U
Total Xylenes	1330-20-7	0.26	1.2	100	mg/kg	<0.017 U	NA	NA	<0.018 U	<0.02 U	<0.017 U	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
Trans-1,2-Dichloroethene	156-60-5	0.19	0.19	100	mg/kg	<0.0057 U	<0.0063 U	<0.018 U	<0.0062 U	<0.0068 U	<0.0056 U	<0.0074 U	<0.0061 U	<0.0058 U	<0.007 U	<0.0056 U	<0.0081 U	<0.0065 U	<0.0078 U	<0.011 U	<0.0072 U	<0.0062 U
Trans-1,3-Dichloropropene	10061-02-6	NS	NS	NS	mg/kg	<0.0057 U	<0.0063 U	<0.018 U	<0.0062 U	<0.0068 U	<0.0056 U	<0.0074 U	<0.0061 U	<0.0058 U	<0.007 U	<0.0056 U	<0.0081 U	<0.0065 U	<0.0078 U	<0.011 U	<0.0072 U	<0.0062 U
Trans-1,4-Dichloro-2-Butene	110-57-6	NS	NS	NS	mg/kg	NA	<0.013 U	<0.035 U	NA	NA	NA	<0.015 U	NA	NA	NA	NA	<0.016 U	<0.013 U	<0.016 U	<0.023 U	<0.014 U	NA
Trichloroethene (TCE)	79-01-6	0.47	0.47	6.4	mg/kg	<0.0057 U	<0.0063 U	<0.018 U	<0.0062 U	<0.0068 U	<0.0056 U	<0.0074 U	<0.0061 U	<0.0058 U	<0.007 U	<0.0056 U	<0.0081 U	<0.0065 U	<0.0078 U	<0.011 U	<0.0072 U	<0.0062 U
Trichlorofluoromethane	75-69-4	NS	NS	NS	mg/kg	<0.0057 U	<0.0063 U	<0.018 U	<0.0062 U	<0.0068 U	<0.0056 U	<0.0074 U	<0.0061 U	<0.0058 U	<0.007 U	<0.0056 U	<0.0081 U	0.0015 J	<0.0078 U	<0.011 U	<0.0072 U	<0.0062 U
Vinyl Chloride	75-01-4	0.03	0.03	0.48	mg/kg	<0.0057 U	<0.0063 U	<0.018 U	<0.0062 U	<0.0068 U	<0.0056 UJ	<0.0074 U	<0.0061 U	<0.0058 U	<0.007 U	<0.0056 U	<0.0081 U	<0.0065 U	<0.0078 U	<0.011 U	<0.0072 U	<0.0062 U

Table 2
Site Management Plan
Soil Sample Analytical Results

12074 Flatlands Avenue p/o Lot 1 Site
Brooklyn, New York
BCP Site No. C224353
Langan Project No.: 100688803

Analyte	CAS Number	NYSDEC Part 375 Unrestricted Use SCOs	NYSDEC Part 375 Protection of Groundwater SCOs	NYSDEC Part 375 Restricted Use Restricted-Residential SCOs	Location	PE82	PE83	PE84	PE84	PE84	PE84	PE85	PE86	PE87	PE88	PE89	PE90	PE91	PE92	PE93	PE94	PE95
					Sample Name	PE82_20	PE83_20	PE84_20	PE84_21	DUP_20251119	PE84_22	PE85_20	PE86_20	PE87_19.5	PE88_19.5	PE89_15	PE90_20	PE91_20	PE92_20	PE93_20	PE94_20	PE95_19.5
					Sample Date	11/19/2025	11/04/2025	10/28/2025	11/19/2025	11/19/2025	12/05/2025	10/28/2025	10/01/2025	10/01/2025	09/17/2025	10/14/2025	10/28/2025	11/04/2025	10/28/2025	10/28/2025	10/28/2025	10/01/2025
					Sample Elevation	20	20	20	21	21	22	20	20	19.5	19.5	15	20	20	20	20	20	19.5
					Unit	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result
Semi-Volatile Organic Compounds																						
1,2,4,5-Tetrachlorobenzene	95-94-3	NS	NS	NS	mg/kg	<0.177 U	<0.177 U	<0.228 UJ	<0.205 U	<0.198 U	<0.174 U	<0.196 UJ	<0.187 U	<0.181 U	<0.194 U	<0.194 U	<0.193 UJ	<0.197 U	<0.191 UJ	<0.185 UJ	<0.185 UJ	<0.183 U
1,2,4-Trichlorobenzene	120-82-1	NS	NS	NS	mg/kg	<0.0884 U	<0.0887 U	<0.114 UJ	<0.102 U	<0.0989 U	<0.0873 U	<0.0981 UJ	<0.0936 U	<0.0907 U	<0.0973 U	<0.0973 U	<0.0965 UJ	<0.0984 U	<0.0958 UJ	<0.0924 UJ	<0.0926 UJ	<0.0918 U
1,2-Dichlorobenzene	95-50-1	1.1	1.1	100	mg/kg	<0.0884 U	<0.0887 U	<0.114 UJ	<0.102 U	<0.0989 U	<0.0873 U	<0.0981 UJ	<0.0936 U	<0.0907 U	<0.0973 U	<0.0973 U	<0.0965 UJ	<0.0984 U	<0.0958 UJ	<0.0924 UJ	<0.0926 UJ	<0.0918 U
1,2-Diphenylhydrazine	122-66-7	NS	NS	NS	mg/kg	<0.0884 U	<0.0887 U	<0.114 UJ	<0.102 U	<0.0989 U	<0.0873 U	<0.0981 UJ	<0.0936 U	<0.0907 U	<0.0973 U	<0.0973 U	<0.0965 UJ	<0.0984 U	<0.0958 UJ	<0.0924 UJ	<0.0926 UJ	<0.0918 U
1,3-Dichlorobenzene	541-73-1	2.6	2.6	38	mg/kg	<0.0884 U	<0.0887 U	<0.114 UJ	<0.102 U	<0.0989 U	<0.0873 U	<0.0981 UJ	<0.0936 U	<0.0907 U	<0.0973 U	<0.0973 U	<0.0965 UJ	<0.0984 U	<0.0958 UJ	<0.0924 UJ	<0.0926 UJ	0.118 D
1,4-Dichlorobenzene	106-46-7	1.8	1.8	24	mg/kg	<0.0884 U	<0.0887 U	<0.114 UJ	<0.102 U	<0.0989 U	<0.0873 U	<0.0981 UJ	<0.0936 U	<0.0907 U	<0.0973 U	<0.0973 U	<0.0965 UJ	<0.0984 U	<0.0958 UJ	<0.0924 UJ	<0.0926 UJ	0.117 D
1,4-Dioxane (P-Dioxane)	123-91-1	0.1	0.1	5.7	mg/kg	<0.0192 U	<0.0196 U	<0.02 U	<0.019 U	<0.0198 U	<0.0196 U	<0.02 U	<0.0194 U	<0.0196 U	<0.0198 U	<0.0192 U	<0.02 U	<0.0196 U	<0.02 U	<0.02 U	<0.02 U	<0.0196 U
2,3,4,6-Tetrachlorophenol	58-90-2	NS	NS	NS	mg/kg	<0.177 U	<0.177 U	<0.228 UJ	<0.205 U	<0.198 U	<0.174 U	<0.196 UJ	<0.187 U	<0.181 UJ	<0.194 U	<0.194 U	<0.193 UJ	<0.197 U	<0.191 UJ	<0.185 UJ	<0.185 UJ	<0.183 U
2,4,5-Trichlorophenol	95-95-4	NS	NS	NS	mg/kg	<0.0884 U	<0.0887 U	<0.114 UJ	<0.102 U	<0.0989 U	<0.0873 U	<0.0981 UJ	<0.0936 U	<0.0907 UJ	<0.0973 U	<0.0973 U	<0.0965 UJ	<0.0984 U	<0.0958 UJ	<0.0924 UJ	<0.0926 UJ	<0.0918 U
2,4,6-Trichlorophenol	88-06-2	NS	NS	NS	mg/kg	<0.0884 U	<0.0887 U	<0.114 UJ	<0.102 U	<0.0989 U	<0.0873 U	<0.0981 UJ	<0.0936 U	<0.0907 UJ	<0.0973 U	<0.0973 U	<0.0965 UJ	<0.0984 U	<0.0958 UJ	<0.0924 UJ	<0.0926 UJ	<0.0918 U
2,4-Dichlorophenol	120-83-2	NS	NS	NS	mg/kg	<0.0884 U	<0.0887 U	<0.114 UJ	<0.102 U	<0.0989 U	<0.0873 U	<0.0981 UJ	<0.0936 U	<0.0907 UJ	<0.0973 U	<0.0973 U	<0.0965 UJ	<0.0984 U	<0.0958 UJ	<0.0924 UJ	<0.0926 UJ	<0.0918 U
2,4-Dimethylphenol	105-67-9	NS	NS	NS	mg/kg	<0.0884 U	<0.0887 U	<0.114 UJ	<0.102 U	<0.0989 U	<0.0873 U	<0.0981 UJ	<0.0936 U	<0.0907 UJ	<0.0973 U	<0.0973 U	<0.0965 UJ	<0.0984 U	<0.0958 UJ	<0.0924 UJ	<0.0926 UJ	<0.0918 U
2,4-Dinitrophenol	51-28-5	NS	NS	NS	mg/kg	<0.177 U	<0.177 U	<0.228 UJ	<0.205 U	<0.198 U	<0.174 UJ	<0.196 UJ	<0.187 U	<0.181 UJ	<0.194 U	<0.194 U	<0.193 UJ	<0.197 U	<0.191 UJ	<0.185 UJ	<0.185 UJ	<0.183 U
2,4-Dinitrotoluene	121-14-2	NS	NS	NS	mg/kg	<0.0884 U	<0.0887 U	<0.114 UJ	<0.102 U	<0.0989 U	<0.0873 U	<0.0981 UJ	<0.0936 U	<0.0907 UJ	<0.0973 U	<0.0973 U	<0.0965 UJ	<0.0984 U	<0.0958 UJ	<0.0924 UJ	<0.0926 UJ	<0.0918 U
2,6-Dinitrotoluene	606-20-2	NS	NS	NS	mg/kg	<0.0884 U	<0.0887 U	<0.114 UJ	<0.102 U	<0.0989 U	<0.0873 U	<0.0981 UJ	<0.0936 U	<0.0907 UJ	<0.0973 U	<0.0973 U	<0.0965 UJ	<0.0984 U	<0.0958 UJ	<0.0924 UJ	<0.0926 UJ	<0.0918 U
2-Chloronaphthalene	91-58-7	NS	NS	NS	mg/kg	<0.0884 U	<0.0887 U	<0.114 UJ	<0.102 U	<0.0989 U	<0.0873 U	<0.0981 UJ	<0.0936 U	<0.0907 U	<0.0973 U	<0.0973 U	<0.0965 UJ	<0.0984 U	<0.0958 UJ	<0.0924 UJ	<0.0926 UJ	<0.0918 U
2-Chlorophenol	95-57-8	NS	NS	NS	mg/kg	<0.0884 U	<0.0887 U	<0.114 UJ	<0.102 U	<0.0989 U	<0.0873 U	<0.0981 UJ	<0.0936 U	<0.0907 UJ	<0.0973 U	<0.0973 U	<0.0965 UJ	<0.0984 U	<0.0958 UJ	<0.0924 UJ	<0.0926 UJ	<0.0918 U
2-Methylnaphthalene	91-57-6	NS	NS	NS	mg/kg	<0.0884 U	<0.0887 U	<0.114 UJ	<0.102 U	<0.0989 U	<0.0873 U	<0.0981 UJ	0.0524 JD	<0.0907 U	0.0646 JD	<0.0973 U	0.113 J	0.132 D	<0.0958 UJ	<0.0924 UJ	0.257 J	0.147 D
2-Methylphenol (o-Cresol)	95-48-7	0.33	0.33	100	mg/kg	<0.0884 U	<0.0887 U	<0.114 UJ	<0.102 U	<0.0989 U	<0.0873 U	<0.0981 UJ	<0.0936 U	<0.0907 UJ	<0.0973 U	<0.0973 U	<0.0965 UJ	<0.0984 U	<0.0958 UJ	<0.0924 UJ	<0.0926 UJ	<0.0918 U
2-Nitroaniline	88-74-4	NS	NS	NS	mg/kg	<0.177 U	<0.177 U	<0.228 UJ	<0.205 U	<0.198 U	<0.174 U	<0.196 UJ	<0.187 U	<0.181 U	<0.194 U	<0.194 U	<0.193 UJ	<0.197 U	<0.191 UJ	<0.185 UJ	<0.185 UJ	<0.183 U
2-Nitrophenol	88-75-5	NS	NS	NS	mg/kg	<0.0884 U	<0.0887 U	<0.114 UJ	<0.102 U	<0.0989 U	<0.0873 U	0.0792 J	<0.0936 U	<0.0907 UJ	<0.0973 U	<0.0973 U	<0.0965 UJ	<0.0984 U	<0.0958 UJ	<0.0924 UJ	<0.0926 UJ	<0.0918 U
3 & 4 Methylphenol (m&p Cresol)	65794-96-9	**0.33**	0.33	100	mg/kg	<0.0884 U	<0.0887 U	<0.114 UJ	<0.102 U	<0.0989 U	<0.0873 U	<0.0981 UJ	<0.0936 U	<0.0907 UJ	<0.0973 U	<0.0973 U	<0.0965 UJ	0.153 D	<0.0958 UJ	<0.0924 UJ	<0.0926 UJ	0.0763 JD
3,3'-Dichlorobenzidine	91-94-1	NS	NS	NS	mg/kg	<0.0884 U	<0.0887 U	<0.114 UJ	<0.102 U	<0.0989 U	<0.0873 U	<0.0981 UJ	<0.0936 U	<0.0907 U	<0.0973 U	<0.0973 U	<0.0965 UJ	<0.0984 U	<0.0958 UJ	<0.0924 UJ	<0.0926 UJ	<0.0918 U
3-Nitroaniline	99-09-2	NS	NS	NS	mg/kg	<0.177 U	<0.177 U	<0.228 UJ	<0.205 U	<0.198 U	<0.174 U	<0.196 UJ	<0.187 U	<0.181 U	<0.194 U	<0.194 U	<0.193 UJ	<0.197 U	<0.191 UJ	<0.185 UJ	<0.185 UJ	<0.183 U
4,6-Dinitro-2-Methylphenol	534-52-1	NS	NS	NS	mg/kg	<0.177 U	<0.177 U	<0.228 UJ	<0.205 U	<0.198 U	<0.174 UJ	<0.196 UJ	<0.187 U	<0.181 UJ	<0.194 U	<0.194 U	<0.193 UJ	<0.197 U	<0.191 UJ	<0.185 UJ	<0.185 UJ	<0.183 U
4-Bromophenyl Phenyl Ether	101-55-3	NS	NS	NS	mg/kg	<0.0884 U	<0.0887 U	<0.114 UJ	<0.102 U	<0.0989 U	<0.0873 U	<0.0981 UJ	<0.0936 U	<0.0907 U	<0.0973 U	<0.0973 U	<0.0965 UJ	<0.0984 U	<0.0958 UJ	<0.0924 UJ	<0.0926 UJ	<0.0918 U
4-Chloro-3-Methylphenol	59-50-7	NS	NS	NS	mg/kg	<0.0884 U	<0.0887 U	<0.114 UJ	<0.102 U	<0.0989 U	<0.0873 U	<0.0981 UJ	<0.0936 U	<0.0907 UJ	<0.0973 U	<0.0973 U	<0.0965 UJ	<0.0984 U	<0.0958 UJ	<0.0924 UJ	<0.0926 UJ	<0.0918 U
4-Chloroaniline	106-47-8	NS	NS	NS	mg/kg	<0.0884 U	<0.0887 U	<0.114 UJ	<0.102 U	<0.0989 U	<0.0873 U	<0.0981 UJ	<0.0936 U	<0.0907 U	<0.0973 U	<0.0973 U	<0.0965 UJ	<0.0984 U	<0.0958 UJ	<0.0924 UJ	<0.0926 UJ	<0.0918 U
4-Chlorophenyl Phenyl Ether	7005-72-3	NS	NS	NS	mg/kg	<0.0884 U	<0.0887 U	<0.114 UJ	<0.102 U	<0.0989 U	<0.0873 U	<0.0981 UJ	<0.0936 U	<0.0907 U	<0.0973 U	<0.0973 U	<0.0965 UJ	<0.0984 U	<0.0958 UJ	<0.0924 UJ	<0.0926 UJ	<0.0918 U
4-Nitroaniline	100-01-6	NS	NS	NS	mg/kg	<0.177 U	<0.177 U	<0.228 UJ	<0.205 U	<0.198 U	<0.174 U	<0.196 UJ	<0.187 U	<0.181 U	<0.194 U	<0.194 U	<0.193 UJ	<0.197 U	<0.191 UJ	<0.185 UJ	<0.185 UJ	<0.183 U
4-Nitrophenol	100-02-7	NS	NS	NS	mg/kg	<0.177 U	<0.177 U	<0.228 UJ	<0.205 U	<0.198 U	<0.174 U	<0.196 UJ	<0.187 U	<0.181 UJ	<0.194 U	<0.194 U	<0.193 UJ	<0.197 U	<0.191 UJ	<0.185 UJ	<0.185 UJ	<0.183 U
Acenaphthene	83-32-9	20	98	100	mg/kg	<0.0884 U	<0.0887 U	<0.114 UJ	<0.102 U	<0.0989 U	<0.0873 U	0.756 J	<0.0936 U	<0.0907 U	0.0498 JD	0.098 D	<0.0965 UJ	0.157 D	<0.0958 UJ	0.107 J	0.787 J	0.287 D
Acenaphthylene	208-96-8	100	365	100	mg/kg	<0.0884 U	<0.0887 U	<0.114 UJ	<0.102 U	<0.0989 U	<0.0873 U	0.415 J	<0.0936 U	0.0674 JD	<0.0973 U	0.119 D	0.653 J	0.0928 JD	<0.0958 UJ	0.374 J	0.498 J	0.401 D
Acetophenone	98-86-2	NS	NS	NS	mg/kg	<0.0884 U	<0.0887 U	<0.114 UJ	<0.102 U	<0.0989 U	<0.0873 U	<0.0981 UJ	<0.0936 U	<0.0907 U	<0.0973 U	<0.0973 U	<0.0965 UJ	<0.0984 U	<0.0958 UJ	<0.0924 UJ	<0.0926 UJ	<0.0918 U
Aniline (Phenylamine, Aminobenzene)	62-53-3	0.04	0.04	8.1	mg/kg	<0.354 U	<0.355 U	<0.457 UJ	<0.41 U	<0.396 U	<0.35 U	<0.393 UJ	<0.375 U	<0.363 U	<0.39 U	<0.39 U	<0.386 UJ	<0.394 U	<0.384 UJ	<0.37 UJ	<0.371 UJ	<0.368 U
Anthracene	120-12-7	100	1000	100	mg/kg	0.101 D	<0.0887 U	<0.114 UJ	0.147 D	<0.0989 U	<0.0873 U	1.64 J	0.0921 JD	0.17 D	0.122 D	0.402 D	1.48 J	0.293 D	<0.0958 UJ	0.372 J	2.35 J	1.71 D
Atrazine	1912-24-9	NS	NS	NS	mg/kg	<0.0884 U	<0.0887 U	<0.114 UJ	<0.102 U	<0.0989 U	<0.0873 U	<0.0981 UJ	<0.0936 U	<0.0907 U	<0.0973 U	<0.0973 U	<0.0965 UJ	<0.0984 U	<0.0958 UJ	<0.0924 UJ	<0.0926 UJ	<0.0918 U
Benzaldehyde	100-52-7	NS	NS	NS	mg/kg	<0.0884 U	<0.0887 U	<0.114 UJ	<0.102 U	<0.0989 U	<0.0873 U	<0.0981 UJ	<0.0936 U	<0.0907 U	<0.0973 U	<0.0973 U	<0.0965 UJ	<0.0984 U	<0.0958 UJ	<0.0924 UJ	<0.0926 UJ	<0.0918 U
Benzidine	92-87-5	NS	NS	NS	mg/kg	<0.354 U	<0.355 U	<0.457 UJ	<0.41 U	<0.396 U	<0.35 U	<0.393 UJ	<0.375 U	<0.363 U	<0.39 U	<0.39 U	<0.386 UJ	<0.394 U	<0.384 UJ	<0.37 UJ	<0.371 UJ	<0.368 U
Benzo(a)anthracene	56-55-3	**1**	1	1.4	mg/kg	0.231 D	0.0553 JD	0.0575 J	0.156 D	0.0609 JD	<0.0873 U	**4.02 J**	0.334 D	0.403 D	0.32 D	**1.18 D**	**3.64 J**	0.525 D	<0.0958 UJ	**1.16 J**	**2.63 J**	<0.918 U
Benzo(a)pyrene	50-32-8	**1**	22	1	mg/kg	0.215 D	0.0468 JD	<0.114 UJ	0.0893 JD	<0.0989 U	<0.0873 U	**2.56 J**	0.341 D	0.434 D	0.289 D	**1.13 D**	**2.83 J**	0.438 D	0.0865 J	**1.72 J**	**2.24 J**	<0.918 U
Benzo(b)fluoranthene	205-99-2	**1**	2.1	1.4	mg/kg	0.189 D	0.0475 JD	0.35 J	0.0704 JD	<0.0989 U	<0.0873 U	**2.3 J**	0.293 D	0.41 D	0.244 D	**1.01 D**	**2.62 J**	0.398 D	0.0559 J	**1.73 J**	**2.02 J**	<0.918 U
Benzo(g,h,i)Perylene	191-24-2	**0.64**	1000	4.9	mg/kg	0.135 D	<0.0887 U	0.0839 J	0.0598 JD	<0.0989 U	<0.0873 U	**2.61 J**	0.141 D	0.238 D	0.192 D	0.551 D	**2.45 J**	0.265 D	0.204 J	0.207 J	**2.72 J**	**1.72 D**
Benzo(k)fluoranthene	207-08-9	**0.8**	2	4.9	mg/kg	0.181 D	<0.0887 U	0.314 J	0.0704 JD	<0.0989 U	<0.0873 U	**2.18 J**	0.292 D	0.355 D	0.235 D	**0.859 D**	**2.78 J**	0.404 D	<0.0958 UJ	**1.64 J**	**1.17 J**	**2.89 D**
Benzoic Acid	65-85-0	NS	NS	NS	mg/kg	<0.0884 UJ	<0.0887 UJ	<0.114 UJ	<0.102 UJ	<0.0989 UJ	<0.0873 U	<0.0981 UJ	<0.0936 U	<0.0907 UJ	<0.0973 U	<0.0973 UJ	<0.0965 UJ	<0.0984 UJ	<0.0958 UJ	<0.0924 UJ	<0.0926 UJ	<0.0918 UJ
Benzyl Alcohol	100-51-6	NS	NS	NS	mg/kg	<0.0884 U	<0.0887 U	<0.114 UJ	<0.102 U	<0.0989 U	<0.0873 U	<0.0981 UJ	<0.0936 U	<0.0907 U	<0.0973 U	<0.0973 U	<0.0965 UJ	<0.0984 U	<0.0958 UJ	<0.0924 UJ	<0.0926 UJ	<0.0918 U
Benzyl Butyl Phthalate	85-68-7	NS	NS	NS	mg/kg	0.894 D	<0.0887 U	<0.114 UJ	<0.102 U	<0.0989 U	<0.0873 U	0.216 J	<0.0936 U	0.0783 JD	<0.0973 U	0.362 D	0.642 J	0.53 D	1.14 J	0.0879 J	0.727 J	0.101 D
Biphenyl (Diphenyl)	92-52-4	NS	NS	NS	mg/kg	<0.0884 U	<0.0887 U	<0.114 UJ	<0.102 U	<0.0989 U	<0.0873 U	<0.0981 UJ	<0.0936 U	<0.0907 U	<0.0973 U	<0.0973 U	<0.0965 UJ	<0.0984 U	<0.0958 UJ	<0.0924 UJ	<0.0926 UJ	0.0462 JD
Bis(2-chloroethoxy) methane	111-91-1	NS	NS	NS	mg/kg	<0.0884 U	<0.0887 U	<0.114 UJ	<0.102 U	<0.0989 U	<0.0873 U	<0.0981 UJ	<0.0936 U	<0.0907 U	<0.0973 U	<0.0973 U	<0.0965 UJ	<0.0984 U	<0.0958 UJ	<0.0924 UJ	<0.0926 UJ	<0.0918 U
Bis(2-chloroethyl) ether (2-chloroethyl ether)	111-44-4	NS	NS	NS	mg/kg	<0.0884 U	<0.0887 U	<0.114 UJ	<0.102 U	<0.0989 U	<0.0873 U	<0.0981 UJ	<0.0936 U	<0.0907 U	<0.0973 U	<0.0973 U	<0.0965 UJ	<0.0984 U	<0.0958 UJ	<0.0924 UJ	<0.0926 UJ	<0.0918 U
Bis(2-chloroisopropyl) ether	108-60-1	NS	NS	NS	mg/kg	<0.0884 U	<0.0887 U	<0.114 UJ	<0.102 U	<0.0989 U	<0.0873 U	<0.0981 UJ	<0.0936 U	<0.0907 U	<0.0973 U	<0.0973 U	<0.0965 UJ	<0.0984 U	<0.0958 UJ	<0.0924 UJ	<0.0926 UJ	<0.0918 U
Bis(2-ethylhexyl) phthalate	117-81-7	NS	NS	NS	mg/kg	7.12 D	0.258 D	<0.114 UJ	0.365 D	0.208 D	<0.0873 U	2.21 J	0.427 D	0.509 D	0.0607 JD	4.39 D	5.38 J	3.84 D	2.51 J	0.459 J	3.9 J	1.59 D
Caprolactam	105-60-2	NS	NS	NS	mg/kg	<0.177 U	<0.177 U	<0.228 UJ	<0.205 U	<0.198 U	<0.174 U	<0.196 UJ	<0.187 U	<0.181 U	<0.194 U	<0.194 U	<0.193 UJ	<0.197 U	<0.191 UJ	<0.185 UJ	<0.185 UJ	<0.183 U
Carbazole	86-74-8	NS	NS	NS	mg/kg	<0.0884 U	<0.0887 U	<0.114 UJ	<0.102 U	<0.0989 U	<0.0873 U	0.776 J	<0.0936 U	<0.0907 U	<0.0973 U	0.151 D	<0.0965 UJ	0.0881 JD	<0.0958 UJ	0.161 J	0.607 J	0.391 D
Chrysene	218-01-9	**1**	1	4.9	mg/kg	0.232 D	0.0667 JD	0.0593 J	0.154 D	0.0498 JD	<0.0873 U	**3.01 J**	0.323 D	0.429 D	0.347 D	**1.12 D**	**3.37 J**	0.565 D	<0.0958 UJ	**1.27 J**	**2.59 J**	<0.918 U
Dibenz(a,h)anthracene	53-70-3	**0.33**	1000	0.33	mg/kg	<0.0884 U	<0.0887 U	<0.114 UJ	<0.102 U	<0.0989 U	<0.0873 U	**0.996 J**	0.0509 JD	0.0834 JD	0.0576 JD	0.198 D	**2.06 J**	0.0873 JD	0.0544 J	**0.401 J**	**0.946 J**	**0.786 D**
Dibenzofuran	132-64-9	**2.1**	110	18	mg/kg	<0.0884 U	<0.0887 U	<0.114 UJ	<0.102 U	<0.0989 U	<0.0873 U	<0.0981 UJ	<0.0936 U	<0.0907 U	<0.0973 U	0.063 JD	<0.0965 UJ	0.116 D	<0.0958 UJ	<0.0924 UJ	<0.0926 UJ	0.329 D
Dibutyl phthalate	84-74-2	NS	NS	NS	mg/kg	0.048 JD	<0.0887 U	<0.114 UJ	<0.102 U	<0.0989 U	<0.0873 U	<0.0981 UJ	<0.0936 U	<0.0907 U	<0.0973 U	<0.0973 U	<0.0965 UJ	0.111 D	<0.0958 UJ	<0.0924 UJ	0.0496 J	<0.0918 U
Diethyl phthalate	84-66-2	NS	NS	NS	mg/kg	<0.0884 U	<0.0887 U	<0.114 UJ	<0.102 U	<0.0989 U	<0.0873 U	<0.0981 UJ	<0.0936 U	<0.0907 U	<0.0973 U	<0.0973 U	<0.0965 UJ	<0.0984 U	<0.0958 UJ	<0.0924 UJ	<0.0926 UJ	<0.0918 U
Dimethyl phthalate	131-11-3	NS	NS	NS	mg/kg	<0.0884 U	<0.0887 U	<0.114 UJ	<0.102 U	<0.0989 U	<0.0873 U	<0.0981 UJ	<0.0936 U	<0.0907 U	<0.0973 U	<0.0973 U	<0.0965 UJ	<0.0984 U	<0.0958 UJ	<0.0924 UJ	<0.0926 UJ	<0.0918 U
Dioctyl phthalate	117-84-0	NS	NS	NS	mg/kg	0.336 D	<0.0887 U	<0.114 UJ	<0.102 U	<0.0989 U	<0.0873 U	<0.0981 UJ	<0.0936 U	<0.0907 U	<0.0973 U	0.157 D	<0.0965 UJ	1.77 D	0.118 J	<0.0924 UJ	0.318 J	<0.0918 U
Fluoranthene	206-44-0	85	1000	100	mg/kg	0.461 D	0.104 D	1.01 J	0.439 J	0.115 J	<0.0873 U	11 J	0.59 D	0.832 D	0.756 D	2.53 D	7.44 J	1.31 D	0.536 J	2.07 J	5.55 J	0.616 JD
Fluorene	86-73-7	30	386	100	mg/kg	0.0466 JD	<0.0887 U	<0.114 UJ	0.0565 JD	<0.0989 U	<0.0873 U	1.03 J	0.0651 JD	0.0769 JD	0.0669 JD	0.154 D	<0.0965 UJ	0.199 D	<0.0958 UJ	0.152 J	1.14 J	0.658 D
Hexachlorobenzene	118-74-1	0.33	3.2	0.33	mg/kg	<0.0884 U	<0.0887 U	<0.114 UJ	<0.102 U	<0.0989 U	<0.0873 U	<0.0981 UJ	<0.0936 U	<0.0907 U	<0.0973 U	<0.0973 U	<0.0965 UJ	<0.0984 U	<0.0958 UJ	<0.0924 UJ	<0.0926 UJ	<0.0918 U
Hexachlorobutadiene	87-68-3	NS	NS	NS	mg/kg	<0.0884 UJ	<0.0887 U	<0.114 UJ	<0.102 UJ	<0.0989 UJ	<0.0873 U	<0.0981 UJ	<0.0936 U	<0.0907 U	<0.0973 U	<0.0973 U	<0.0965 UJ	<0.0984 U	<0.0958 UJ	<0.0924 UJ	<0.0926 UJ	<0.0918 U
Hexachlorocyclopentadiene	77-47-4	NS	NS	NS	mg/kg	<0.0884 U	<0.0887 U	<0.114 UJ	<0.102 U	<0.0989 U	<0.0873 UJ	<0.0981 UJ	<0.0936 U	<0.0907 UJ	<0.0973 U	<0.0973 U	<0.0965 UJ	<0.0984 U	<0.0958 UJ	<0.0924 UJ	<0.0926 UJ	<0.0918 UJ
Hexachloroethane	67-72-1	NS	NS	NS	mg/kg	<0.0884 U	<0.0887 U	<0.114 UJ	<0.102 U	<0.0989 U	<0.0873 U	<0.0981 UJ	<0.0936 U	<0.0907 U	<0.0973 U	<0.0973 U	<0.0965 UJ	<0.0984 U	<0.0958 UJ	<0.0924 UJ	<0.0926 UJ	<0.0918 U
Indeno(1,2,3-cd)pyrene	193-39-5	**0.5**	6.6	1.4	mg/kg	0.155 D	<0.0887 U	0.239 J	<0.102 U	<0.0989 U	<0.0873 U	**2.59 J**	0.15 D	0.241 D	0.17 D	**0.53 D**	**1.68 J**	0.26 D	0.126 J	**1.07 J**	**2.57 J**	**1.86 D**
Isophorone	78-59-1	NS	NS	NS	mg/kg	<0.0884 U	<0.0887 U	<0.114 UJ	<0.102 U	<0.0989 U	<0.0873 U	<0.0981 UJ	<0.0936 U	<0.0907 U	<0.0973 U	<0.0973 U	<0.0965 UJ	<0.0984 U	<0.0958 UJ	<0.0924 UJ	<0.0926 UJ	<0.0918 U
Naphthalene	91-20-3	12	12	100	mg/kg	<0.0884 U	<0.0887 U	<0.114 UJ	0.0582 JD	0.0609 JD	<0.0873 U	0.413 J	0.267 D	0.0986 D	0.179 D	0.0622 JD	<0.0965 UJ	0.797 D	<0.0958 UJ	0.0532 J	0.481 J	0.452 D
Nitrobenzene	98-95-3	0.08	0.08	1.8	mg/kg	<0.0884 U	<0.0887 U	<0.114 UJ	<0.102 U	<0.0989 U	<0.0873 U	<0.0981 UJ	<0.0936 U	<0.0907 U	<0.0973 U	<0.0973 U	<0.0965 UJ	<0.0984 U	<0.0958 UJ	<0.0924 UJ	<0.0926 UJ	<0.0918 U
n-Nitrosodimethylamine	62-75-9	NS	NS	NS	mg/kg	<0.0884 U	<0.0887 U	<0.114 UJ	<0.102 U	<0.0989 U	<0.0873 U	<0.0981 UJ	<0.0936 U	<0.0907 U	<0.0973 U	<0.0973 U	<0.0965 UJ	<0.0984 U	<0.0958 UJ	<0.0924 UJ	<0.0926 UJ	<0.0918 U
n-Nitrosodi-N-Propylamine	621-64-7	NS	NS	NS	mg/kg	<0.0884 U	<0.0887 U	<0.114 UJ	<0.102 U	<0.0989 U	<0.0873 U	<0.0981 UJ	<0.0936 U	<0.0907 U	<0.0973 U	<0.0973 U	<0.0965 UJ	<0.0984 U	<0.0958 UJ	<0.0924 UJ	<0.0926 UJ	<0.0918 U
n-Nitrosodiphenylamine	86-30-6	NS	NS	NS	mg/kg	<0.0884 U	<0.0887 U	<0.114 UJ	<0.102 U	<0.0989 U	<0.0873 U	<0.0981 UJ	<0.0936 U	<0.0907 U	<0.0973 U	<0.0973 U	<0.0965 UJ	<0.0984 U	<0.0958 UJ	<0.0924 UJ	<0.0926 UJ	<0.0918 U
Pentachlorophenol	87-86-5	0.8	0.8	1.3	mg/kg	<0.0884 U	<0.0887 U	<0.114 UJ	<0.102 U	<0.0989 U	<0.0873 U	<0.0981 UJ	<0.0936 U	<0.0907 UJ	<0.0973 U	<0.0973 U	<0.0965 UJ	<0.0984 U	<0.0958 UJ	<0.0924 UJ	<0.0926 UJ	<0.0918 U
Phenanthrene	85-01-8	**1.1**	1000	4.9	mg/kg	0.329 D	0.0695 JD	0.885 J	0.121 D	0.0546 JD	<0.0873 U	**8.21 J**	0.306 D	0.437 D	0.631 D	**1.33 D**	**6.05 J**	0.896 D	<0.0958 UJ	0.871 J	**4.35 J**	<0.918 U
Phenol	108-95-2	0.33	0.33	100	mg/kg	<0.0884 U	<0.0887 U	<0.114 UJ	<0.102 U	<0.0989 U	<0.0873 U	<0.0981 UJ	<0.0936 U	<0.0907 UJ	<0.0973 U	<0.0973 U	<0.0965 UJ	<0.0984 U	<0.0958 UJ	<0.0924 UJ	<0.0926 UJ	<0.0918 U
Pyrene	129-00-0	64	1000	100	mg/kg	0.382 D	0.106 D	<0.114 UJ	0.371 J	0.0988 J	<0.0873 U	9.78 J	0.567 D	0.687 D	0.76 D	2.21 D	7.02 J	1.11 D	0.577 J	2.73 J	5.55 J	0.829 JD
Pyridine	110-86-1	NS	NS	NS	mg/kg	<0.354 U	<0.355 U	<0.457 UJ	<0.41 U	<0.396 U	<0.35 U	<0.393 UJ	<0.375 U	<0.363 U	<0.39 U	<0.39 U	<0.386 UJ	<0.394 U	<0.384 UJ	<0.37 UJ	<0.371 UJ	<0.368 U

Table 2
Site Management Plan
Soil Sample Analytical Results

12074 Flatlands Avenue p/o Lot 1 Site
Brooklyn, New York
BCP Site No. C224353
Langan Project No.: 100688803

Analyte	CAS Number	NYSDEC Part 375 Unrestricted Use SCOs	NYSDEC Part 375 Protection of Groundwater SCOs	NYSDEC Part 375 Restricted Use Restricted-Residential SCOs	Location	PE82	PE83	PE84	PE84	PE84	PE84	PE85	PE86	PE87	PE88	PE89	PE90	PE91	PE92	PE93	PE94	PE95
					Sample Name	PE82_20	PE83_20	PE84_20	PE84_21	DUP_20251119	PE84_22	PE85_20	PE86_20	PE87_19.5	PE88_19.5	PE89_15	PE90_20	PE91_20	PE92_20	PE93_20	PE94_20	PE95_19.5
					Sample Date	11/19/2025	11/04/2025	10/28/2025	11/19/2025	11/19/2025	12/05/2025	10/28/2025	10/01/2025	10/01/2025	09/17/2025	10/14/2025	10/28/2025	11/04/2025	10/28/2025	10/28/2025	10/28/2025	10/01/2025
					Sample Elevation	20	20	20	21	21	22	20	20	19.5	19.5	15	20	20	20	20	20	19.5
					Unit	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result
Pesticides																						
4,4'-DDD	72-54-8	**0.0033**	14	5	mg/kg	0.00311 DP	<0.00176 UP	<0.00224 UP	<0.002 UP	<0.00194 UP	<0.00175 UP	**0.0332 DP**	**0.00639 DP**	0.00199 DP	**0.00384 DP**	**0.0166 J**	<0.0019 UJ	0.00261 J	<0.00192 UP	**0.239 J**	**0.0437 J**	0.00213 DP
4,4'-DDE	72-55-9	**0.0033**	9.3	3.4	mg/kg	<0.00173 UP	<0.00176 UP	<0.00224 UP	<0.002 UP	<0.00194 UP	<0.00175 UP	**0.0134 J**	0.00196 J	<0.00178 UP	<0.00192 UP	**0.00742 J**	**0.0112 J**	<0.00195 UJ	<0.00192 UP	**0.0406 DP**	**0.0138 J**	<0.00183 UP
4,4'-DDT	50-29-3	**0.0033**	135	3.8	mg/kg	<0.00173 UP	<0.00176 UP	<0.00224 UP	<0.002 UP	<0.00194 UP	<0.00175 UP	<0.00192 UP	<0.00185 UP	<0.00178 UP	0.00226 J	**0.00764 J**	<0.0019 UJ	0.00287 J	<0.00192 UP	**0.0156 J**	**0.00702 J**	<0.00183 UP
Aldrin	309-00-2	0.0048	0.19	0.044	mg/kg	<0.00173 UP	<0.00176 UP	<0.00224 UP	<0.002 UP	<0.00194 UP	<0.00175 UP	<0.00192 UP	<0.00185 UP	<0.00178 UP	<0.00192 UP	<0.00193 UP	<0.0019 UJ	<0.00195 UJ	<0.00192 UP	<0.00183 UP	<0.00184 UP	<0.00183 UP
Alpha BHC (Alpha Hexachlorocyclohexane)	319-84-6	0.02	0.02	0.18	mg/kg	<0.00173 UP	<0.00176 UP	<0.00224 UP	<0.002 UP	<0.00194 UP	<0.00175 UP	<0.00192 UP	<0.00185 UP	<0.00178 UP	<0.00192 UP	<0.00193 UP	<0.0019 UJ	<0.00195 UJ	<0.00192 UP	<0.00183 UP	<0.00184 UP	<0.00183 UP
Alpha Chlordane	5103-71-9	**0.014**	4.5	0.65	mg/kg	<0.00173 UP	<0.00176 UP	<0.00224 UP	<0.002 UP	<0.00194 UP	<0.00175 UP	0.00291 J	<0.00185 UP	<0.00178 UP	<0.00192 UP	0.0108 J	**0.0538 J**	<0.00195 UJ	0.00211 J	**0.0165 J**	0.00736 J	<0.00183 UP
Alpha Endosulfan	959-98-8	4.3	65	35	mg/kg	<0.00173 UP	<0.00176 UP	<0.00224 UP	<0.002 UP	<0.00194 UP	<0.00175 UP	<0.00192 UP	<0.00185 UP	<0.00178 UP	<0.00192 UP	<0.00193 UP	<0.0019 UJ	<0.00195 UJ	<0.00192 UP	<0.00183 UP	<0.00184 UP	<0.00183 UP
Beta Bhc (Beta Hexachlorocyclohexane)	319-85-7	0.021	0.09	0.18	mg/kg	<0.00173 UP	<0.00176 UP	<0.00224 UP	<0.002 UP	<0.00194 UP	<0.00175 UP	<0.00192 UP	<0.00185 UP	<0.00178 UP	<0.00192 UP	<0.00193 UP	<0.0019 UJ	<0.00195 UJ	<0.00192 UP	<0.00183 UP	<0.00184 UP	<0.00183 UP
Beta Endosulfan	33213-65-9	4.3	44	35	mg/kg	<0.00173 UP	<0.00176 UP	<0.00224 UP	<0.002 UP	<0.00194 UP	<0.00175 UP	<0.00192 UP	<0.00185 UP	<0.00178 UP	<0.00192 UP	<0.00193 UP	<0.0019 UJ	<0.00195 UJ	<0.00192 UP	<0.00183 UP	<0.00184 UP	<0.00183 UP
Delta Bhc (Delta Hexachlorocyclohexane)	319-86-8	0.04	0.1	100	mg/kg	<0.00173 UP	<0.00176 UP	<0.00224 UP	<0.002 UP	<0.00194 UP	<0.00175 UP	<0.00192 UP	<0.00185 UP	<0.00178 UP	<0.00192 UP	<0.00193 UP	<0.0019 UJ	<0.00195 UJ	<0.00192 UP	<0.00183 UP	<0.00184 UP	<0.00183 UP
Dieldrin	60-57-1	**0.005**	0.1	0.075	mg/kg	<0.00173 UP	<0.00176 UP	<0.00224 UP	<0.002 UP	<0.00194 UP	<0.00175 UP	<0.00192 UP	<0.00185 UP	<0.00178 UP	<0.00192 UP	<0.00193 UP	**0.00802 J**	<0.00195 UJ	<0.00192 UP	**0.0224 DP**	**0.00991 J**	<0.00183 UP
Endosulfan Sulfate	1031-07-8	4.3	47	35	mg/kg	<0.00173 UP	<0.00176 UP	<0.00224 UP	<0.002 UP	<0.00194 UP	<0.00175 UP	<0.00192 UP	<0.00185 UP	<0.00178 UP	<0.00192 UP	<0.00193 UP	<0.0019 UJ	<0.00195 UJ	<0.00192 UP	<0.00183 UP	<0.00184 UP	<0.00183 UP
Endrin	72-20-8	0.014	0.06	5.3	mg/kg	<0.00173 UP	<0.00176 UP	<0.00224 UP	<0.002 UP	<0.00194 UP	<0.00175 UP	<0.00192 UP	<0.00185 UP	<0.00178 UP	<0.00192 UP	<0.00193 UP	<0.0019 UJ	<0.00195 UJ	<0.00192 UP	<0.00183 UP	<0.00184 UP	<0.00183 UP
Endrin Aldehyde	7421-93-4	NS	NS	NS	mg/kg	<0.00173 UP	<0.00176 UP	<0.00224 UP	<0.002 UP	<0.00194 UP	<0.00175 UP	<0.00192 UP	<0.00185 UP	<0.00178 UP	<0.00192 UP	<0.00193 UP	<0.0019 UJ	<0.00195 UJ	<0.00192 UP	<0.00183 UP	<0.00184 UP	<0.00183 UP
Endrin Ketone	53494-70-5	NS	NS	NS	mg/kg	<0.00173 UP	<0.00176 UP	<0.00224 UP	<0.002 UP	<0.00194 UP	<0.00175 UP	<0.00192 UP	<0.00185 UP	<0.00178 UP	<0.00192 UP	<0.00193 UP	<0.0019 UJ	<0.00195 UJ	<0.00192 UP	<0.00183 UP	<0.00184 UP	<0.00183 UP
Gamma Bhc (Lindane)	58-89-9	0.025	0.05	0.21	mg/kg	<0.00173 UP	<0.00176 UP	<0.00224 UP	<0.002 UP	<0.00194 UP	<0.00175 UP	<0.00192 UP	<0.00185 UP	<0.00178 UP	<0.00192 UP	<0.00193 UP	<0.0019 UJ	<0.00195 UJ	<0.00192 UP	<0.00183 UP	<0.00184 UP	<0.00183 UP
Gamma-Chlordane	5566-34-7	NS	NS	NS	mg/kg	<0.00173 UP	<0.00176 UP	<0.00224 UP	<0.002 UP	<0.00194 UP	<0.00175 UP	0.00514 J	<0.00185 UP	<0.00178 UP	<0.00192 U	0.0152 J	0.0859 J	<0.00195 UJ	0.00236 J	0.0256 J	0.0084 J	<0.00183 UP
Heptachlor	76-44-8	0.013	0.38	0.53	mg/kg	<0.00173 UP	<0.00176 UP	<0.00224 UP	<0.002 UP	<0.00194 UP	<0.00175 UP	<0.00192 UP	<0.00185 UP	<0.00178 UP	<0.00192 UP	<0.00193 UP	<0.0019 UJ	0.0054 J	<0.00192 UP	<0.00183 UP	<0.00184 UP	<0.00183 UP
Heptachlor Epoxide	1024-57-3	NS	NS	NS	mg/kg	<0.00173 UP	<0.00176 UP	<0.00224 UP	<0.002 UP	<0.00194 UP	<0.00175 UP	<0.00192 UP	<0.00185 UP	<0.00178 UP	<0.00192 UP	<0.00193 UP	<0.0019 UJ	<0.00195 UJ	<0.00192 UP	<0.00183 UP	<0.00184 UP	<0.00183 UP
Methoxychlor	72-43-5	NS	NS	NS	mg/kg	<0.00173 UP	<0.00176 UP	<0.00224 UP	<0.002 UP	<0.00194 UP	<0.00175 UP	<0.00192 UP	<0.00185 UP	<0.00178 UP	<0.00192 UP	<0.00193 UP	<0.0019 UJ	<0.00195 UJ	<0.00192 UP	<0.00183 UP	<0.00184 UP	<0.00183 UP
Toxaphene	8001-35-2	NS	NS	NS	mg/kg	<0.173 UP	<0.176 UP	<0.224 UP	<0.2 UP	<0.194 UP	<0.175 UP	<0.192 UP	<0.185 UP	<0.178 UP	<0.192 UP	<0.193 UP	<0.19 UJ	<0.195 UJ	<0.192 UP	<0.183 UP	<0.184 UP	<0.183 UP
Herbicides																						
2,4,5-T (Trichlorophenoxyacetic Acid)	93-76-5	NS	NS	NS	mg/kg	<0.0212 UP	<0.0213 UP	NA	<0.0245 UP	<0.0238 UP	<0.0212 UP	NA	<0.0225 UP	<0.0216 UP	<0.023 UP	<0.0236 UP	NA	<0.0236 UP	NA	NA	NA	<0.022 UP
2,4-D (Dichlorophenoxyacetic Acid)	94-75-7	NS	NS	NS	mg/kg	<0.0212 UP	<0.0213 UP	<0.0273 UP	<0.0245 UP	<0.0238 UP	<0.0212 UP	<0.0234 UP	<0.0225 UP	<0.0216 UP	<0.023 UP	<0.0236 UP	<0.0232 UP	<0.0236 UP	<0.0233 UP	<0.0222 UP	<0.0223 UP	<0.022 UP
2,4-Dichlorophenoxybutyric acid	94-82-6	NS	NS	NS	mg/kg	NA	NA	NA	NA	NA	NA	NA	NA	NA	<0.023 UP	NA	NA	NA	NA	NA	NA	NA
Dalapon	75-99-0	NS	NS	NS	mg/kg	NA	NA	NA	NA	NA	NA	NA	NA	NA	<0.023 UP	NA	NA	NA	NA	NA	NA	NA
Dicamba	1918-00-9	NS	NS	NS	mg/kg	NA	NA	NA	NA	NA	NA	NA	NA	NA	<0.023 UP	NA	NA	NA	NA	NA	NA	NA
Silvex (2,4,5-Tp)	93-72-1	3.8	3.8	100	mg/kg	<0.0212 UP	<0.0213 UP	NA	<0.0245 UP	<0.0238 UP	<0.0212 UP	NA	<0.0225 UP	<0.0216 UP	<0.023 UP	<0.0236 UP	NA	<0.0236 UP	NA	NA	NA	<0.022 UP
Polychlorinated Biphenyl																						
PCB-1016 (Aroclor 1016)	12674-11-2	NS	NS	NS	mg/kg	<0.0175 UP	<0.0177 UP	<0.0226 UP	<0.0202 UP	<0.0196 UP	<0.0176 UP	<0.0194 UP	<0.0187 UJ	<0.0181 UP	<0.0193 UP	<0.0195 UP	<0.0193 UP	<0.0197 UJ	<0.0194 UP	<0.0185 UP	<0.0186 UP	<0.0183 UJ
PCB-1221 (Aroclor 1221)	11104-28-2	NS	NS	NS	mg/kg	<0.0175 UP	<0.0177 UP	<0.0226 UP	<0.0202 UP	<0.0196 UP	<0.0176 UP	<0.0194 UP	<0.0187 UJ	<0.0181 UP	<0.0193 UP	<0.0195 UP	<0.0193 UP	<0.0197 UJ	<0.0194 UP	<0.0185 UP	<0.0186 UP	<0.0183 UJ
PCB-1232 (Aroclor 1232)	11141-16-5	NS	NS	NS	mg/kg	<0.0175 UP	<0.0177 UP	<0.0226 UP	<0.0202 UP	<0.0196 UP	<0.0176 UP	<0.0194 UP	<0.0187 UJ	<0.0181 UP	<0.0193 UP	<0.0195 UP	<0.0193 UP	<0.0197 UJ	<0.0194 UP	<0.0185 UP	<0.0186 UP	<0.0183 UJ
PCB-1242 (Aroclor 1242)	53469-21-9	NS	NS	NS	mg/kg	0.0615 P	<0.0177 UP	<0.0226 UP	0.0626 P	0.0234 P	<0.0176 UP	0.0225 P	0.0552 J	0.0277 P	0.138 P	0.177 P	0.042 P	0.182 J	<0.0194 UP	<0.0185 UP	0.157 P	0.246 J
PCB-1248 (Aroclor 1248)	12672-29-6	NS	NS	NS	mg/kg	<0.0175 UP	<0.0177 UP	<0.0226 UP	<0.0202 UP	<0.0196 UP	<0.0176 UP	<0.0194 UP	<0.0187 UJ	<0.0181 UP	<0.0193 UP	<0.0195 UP	<0.0193 UP	<0.0197 UJ	<0.0194 UP	<0.0185 UP	<0.0186 UP	<0.0183 UJ
PCB-1254 (Aroclor 1254)	11097-69-1	NS	NS	NS	mg/kg	0.0782 P	<0.0177 UP	<0.0226 UP	0.0537 P	<0.0196 UP	<0.0176 UP	<0.0194 UP	0.0846 J	0.0421 P	<0.0193 UP	0.281 P	0.0824 P	0.156 J	<0.0194 UP	0.0256 P	0.16 P	0.272 J
PCB-1260 (Aroclor 1260)	11096-82-5	NS	NS	NS	mg/kg	<0.0175 UP	<0.0177 UP	<0.0226 UP	<0.0202 UP	<0.0196 UP	<0.0176 UP	<0.0194 UP	<0.0187 UJ	<0.0181 UP	0.0482 P	0.11 P	0.0566 P	<0.0197 UJ	<0.0194 UP	0.0215 P	<0.0186 UP	<0.0183 UJ
PCB-1262 (Aroclor 1262)	37324-23-5	NS	NS	NS	mg/kg	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
PCB-1268 (Aroclor 1268)	11100-14-4	NS	NS	NS	mg/kg	NA	NA	NA	0.0247 P	0.0198 P	NA	NA	0.045 J	0.0205 P	NA	NA	NA	NA	3.48 J	NA	0.0189 P	0.0383 J
Total PCBs	1336-36-3	**0.1**	3.2	1	mg/kg	**0.14 P**	<0.0177 UP	<0.0226 UP	**0.141 J**	0.0432 J	<0.0176 UP	0.0225 P	**0.185 J**	0.0903 P	**0.187 P**	**0.568 P**	**0.181 P**	**0.338 J**	**3.48 J**	0.0471 P	**0.336 P**	**0.556 J**
Metals																						
Aluminum	7429-90-5	NS	NS	NS	mg/kg	8,040	6,880	7,100	5,730	5,350	4,680	9,360	7,060	5,900	5,940 B	7,540	7,730	6,540	7,100	11,500	6,560	6,520
Antimony	7440-36-0	NS	NS	NS	mg/kg	<2.22 U	<2.23 U	<2.87 U	<2.57 U	<2.5 U	<2.22 U	<2.46 U	<2.35 UJ	<2.28 U	<2.44 U	<2.46 UJ	<2.43 U	<2.47 U	3.75	<2.32 UJ	<2.34 U	<2.32 U
Arsenic	7440-38-2	**13**	16	16	mg/kg	2.68	1.86	**34**	**15.2 J**	9.11 J	1.97	5.67	8.09	12.7	6.1	7.26	**29.8**	9.47	**14**	12 J	7.69	7.48
Barium	7440-39-3	**410**	820	410	mg/kg	72.8	13.3	**1,830**	**973 J**	**549 J**	12.7	**414**	277 J	217	**470**	308	**507**	**464**	**454**	**453 J**	**654**	339
Beryllium	7440-41-7	4.4	47	43	mg/kg	0.318	0.145	0.721	0.7	0.584	0.126	0.226	0.231	0.179	0.391	0.166	0.183	0.295	0.405	0.432 J	0.207	0.215
Cadmium	7440-43-9	**2.5**	7.5	2.5	mg/kg	<0.267 U	<0.268 U	**8.8**	**2.76 J**	0.629 J	<0.267 U	0.61	1.33	0.785	0.624	2.29	**8.17**	1.92	1.85	0.678	**4.22**	1.53
Calcium	7440-70-2	NS	NS	NS	mg/kg	4,640	947	13,100	8,980 J	4,830 J	1,490	34,900	20,100 J	20,300	4,860	46,000	52,600	11,300	23,300	38,600	49,200	31,400
Chromium, Hexavalent	18540-29-9	1	19	1	mg/kg	<0.533 U	<0.535 U	<0.688 U	<0.616 U	<0.599 U	<0.534 U	<0.59 U	<0.565 U	<0.547 U	<0.585 U	<0.591 U	<0.584 U	<0.592 U	<0.586 U	<0.558 UJ	<0.56 U	<0.556 U
Chromium, Total	7440-47-3	NS	NS	NS	mg/kg	15.4	10.3	266	25.2 J	13.4 J	13.1	20.8	19.7 J	15.3	15.1	29.8 J	90.1	23.7	27	13.6 J	30.9	42.7
Chromium, Trivalent	16065-83-1	**30**	19	110	mg/kg	15.4	10.3	**266**	25.2 J	13.4 J	13.1	20.8	19.7	15.3	15.1	29.8	**90.1**	23.7	27	13.6	**30.9**	**42.7**
Cobalt	7440-48-4	NS	NS	NS	mg/kg	4.47	3.11	11.9	8.43	6.71	3.38	10.4	5.73	4.58	5.83	6.73	16.5	7.42	7.77	5.33	7.35	6.3
Copper	7440-50-8	**50**	1720	280	mg/kg	22.8	8.43	**229**	**231 J**	**86 J**	8.19	**54.1**	**130**	**55.6**	**83.6**	**89.6 J**	**183**	**131**	**221**	24.5 J	**82.7**	**222**
Cyanide	57-12-5	**2.3**	40	13	mg/kg	<0.533 U	<0.535 U	1.02	<0.616 U	<0.599 U	<0.534 U	<0.59 U	<0.565 U	<0.547 U	0.6	0.998 J	0.987	<0.592 U	0.803	<0.558 UJ	0.639	0.923
Iron	7439-89-6	NS	NS	NS	mg/kg	11,300	8,790	50,100	26,600 J	11,700 J	10,900	18,400	21,900	12,300	17,700	34,000 J	37,100	34,200	31,300	12,000	24,000	23,300
Lead	7439-92-1	**63**	450	400	mg/kg	52.4	4.67	**4,170**	**604**	**365**	3.06	**470**	**533 J**	**178**	**255**	**456**	**1,160**	**508**	**919**	**248 J**	**716**	**393**
Magnesium	7439-95-4	NS	NS	NS	mg/kg	2,500	1,990	993	1,090 J	498 J	2,270	4,070	3,040	6,520	1,690	5,270	9,100	2,370	3,340	5,630	6,660	5,090
Manganese	7439-96-5	**1600**	2000	2000	mg/kg	107	71.6	253	194 J	84.1 J	110	372	225	158	144	399	391	269	358	245	279	263
Mercury	7439-97-6	**0.18**	0.73	0.3	mg/kg	0.0785	<0.0321 U	**0.894**	**8.3 J**	**0.797 J**	<0.032 U	**0.276**	**0.305 J**	**0.688**	0.15	**0.279**	**0.371**	**0.547**	**0.498**	**0.326**	**1.03**	**34 J**
Nickel	7440-02-0	**30**	130	320	mg/kg	15.6	13.1	30	23.9	20	15.8	17.8	25.1	15.4	18.5	24.3	**56.5**	26.6	**30.2**	12.5 J	24.5	**31**
Potassium	7440-09-7	NS	NS	NS	mg/kg	745	584	755	643	636	509	1,150	780	730	635	969 J	1,120	697	988	1,200 J	1,100	941
Selenium	7782-49-2	**3.9**	4	110	mg/kg	<2.22 U	<2.23 U	<2.87 U	<2.57 U	<2.5 U	<2.22 U	<2.46 U	<2.35 U	<2.28 U	<2.44 U	<2.46 U	<2.43 U	<2.47 U	<2.44 U	<2.32 U	<2.34 U	<2.32 U
Silver	7440-22-4	**2**	8.3	110	mg/kg	<0.448 U	<0.45 U	1.94	**2.33 J**	<0.503 UJ	<0.448 U	<0.495 U	0.659	<0.46 U	<0.492 U	0.542	1.11	0.759	0.937	<0.468 U	0.663	0.815
Sodium	7440-23-5	NS	NS	NS	mg/kg	119 J	98.6	415 J	346 J	307 J	62.8	257 J	295 J	226	<229 U	384 J	409 J	251	265 J	1,450 J	369 J	347
Thallium	7440-28-0	NS	NS	NS	mg/kg	<1.78 U	<1.79 U	<2.3 U	<2.06 U	<2 U	<1.78 U	<1.97 U	<1.89 U	<1.83 U	<1.96 U	<1.97 U	<1.95 U	<1.98 U	<1.96 U	<1.86 U	<1.87 U	<1.86 U
Vanadium	7440-62-2	NS	NS	NS	mg/kg	19.1	14.2	27.8	24.1	29.8	23	27.9	19.3	20.7	26.9	33.8	31.1	19.3	22.7	21.6	24.9	23.1
Zinc	7440-66-6	**109**	2480	6600	mg/kg	78.3	41.4	**2,130**	**900 J**	**394 J**	22.4	**289**	**517**	**260**	**393**	**647**	**5,240 D**	**589**	**895**	**305**	**1,210**	**574**

Table 2
Site Management Plan
Soil Sample Analytical Results

12074 Flatlands Avenue p/o Lot 1 Site
Brooklyn, New York
BCP Site No. C224353
Langan Project No.: 100688803

Analyte	CAS Number	NYSDEC Part 375 Unrestricted Use SCOs	NYSDEC Part 375 Protection of Groundwater SCOs	NYSDEC Part 375 Restricted Use Restricted-Residential SCOs	Location	PE82	PE83	PE84	PE84	PE84	PE84	PE85	PE86	PE87	PE88	PE89	PE90	PE91	PE92	PE93	PE94	PE95
					Sample Name	PE82_20	PE83_20	PE84_20	PE84_21	DUP_20251119	PE84_22	PE85_20	PE86_20	PE87_19.5	PE88_19.5	PE89_15	PE90_20	PE91_20	PE92_20	PE93_20	PE94_20	PE95_19.5
					Sample Date	11/19/2025	11/04/2025	10/28/2025	11/19/2025	11/19/2025	12/05/2025	10/28/2025	10/01/2025	10/01/2025	09/17/2025	10/14/2025	10/28/2025	11/04/2025	10/28/2025	10/28/2025	10/28/2025	10/01/2025
					Sample Elevation	20	20	20	21	21	22	20	20	19.5	19.5	15	20	20	20	20	20	19.5
					Unit	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result
Per- and Polyfluoroalkyl Substances																						
11-Chloroeicosafluoro-3-Oxaundecane-1-Sulfonic Acid (11Cl-PF3OUdS)	763051-92-9	NS	NS	NS	mg/kg	<0.000806 U	<0.00081 U	<0.00104 U	<0.000926 U	<0.000906 U	<0.000807 UJ	<0.000892 U	<0.000855 U	<0.000828 U	<0.000885 UJ	<0.000894 U	<0.000883 U	<0.000895 U	<0.000886 U	<0.000843 U	<0.000847 U	<0.00084 U
1H,1H,2H,2H-Perfluorodecane Sulfonic Acid (8:2 FTS)	39108-34-4	NS	NS	NS	mg/kg	<0.000819 UJ	<0.000822 U	<0.00106 U	<0.000941 UJ	<0.00092 UJ	<0.00082 U	<0.000906 U	<0.000868 U	<0.000841 U	<0.000899 U	<0.000908 U	<0.000897 U	<0.000909 U	<0.0009 U	<0.000857 U	<0.000861 U	<0.000854 U
1H,1H,2H,2H-Perfluorohexane Sulfonic Acid (4:2 FTS)	757124-72-4	NS	NS	NS	mg/kg	<0.0008 U	<0.000803 UJ	<0.00103 UJ	<0.000919 U	<0.000898 UJ	<0.000801 U	<0.000885 U	<0.000848 U	<0.000821 U	<0.000878 U	<0.000887 U	<0.000876 UJ	<0.000888 U	<0.000879 UJ	<0.000836 UJ	<0.000841 UJ	<0.000834 UJ
1H,1H,2H,2H-Perfluorooctane Sulfonic Acid (6:2 FTS)	27619-97-2	NS	NS	NS	mg/kg	<0.000811 U	<0.000814 U	<0.00105 U	<0.000931 U	<0.00091 U	<0.000812 U	<0.000897 U	<0.000859 U	<0.000832 U	<0.00089 U	<0.000898 U	<0.000888 U	<0.000899 U	<0.00089 U	<0.000848 U	<0.000852 U	<0.000845 U
2H,2H,3H,3H-Perfluorooctanoic Acid (5:3 FTCA)	914637-49-3	NS	NS	NS	mg/kg	<0.00533 UJ	<0.00535 U	<0.00688 U	<0.00613 U	<0.00599 U	<0.00534 U	<0.0059 U	<0.00565 U	<0.00547 U	<0.00585 U	<0.00591 U	<0.00584 U	<0.00592 U	<0.00586 U	<0.00558 U	<0.0056 U	<0.00556 U
3-Perfluoroheptyl Propanoic Acid (7:3 FTCA)	812-70-4	NS	NS	NS	mg/kg	<0.00533 UJ	<0.00535 U	<0.00688 U	<0.00613 U	<0.00599 U	<0.00534 U	<0.0059 U	<0.00565 U	<0.00547 U	<0.00585 U	<0.00591 U	<0.00584 U	<0.00592 U	<0.00586 U	<0.00558 U	<0.0056 U	<0.00556 U
3-Perfluoropropyl Propanoic Acid (3:3 FTCA)	356-02-5	NS	NS	NS	mg/kg	<0.00107 UJ	<0.00107 U	<0.00138 U	<0.00123 U	<0.0012 UJ	<0.00107 U	<0.00118 U	<0.00113 U	<0.00109 U	<0.00117 U	<0.00118 U	<0.00117 U	<0.00118 U	<0.00117 U	<0.00112 U	<0.00112 U	<0.00111 U
4,8-Dioxa-3H-perfluorononanoic Acid (ADONA)	919005-14-4	NS	NS	NS	mg/kg	<0.000806 U	<0.00081 UJ	<0.00104 UJ	<0.000926 U	<0.000906 U	<0.000807 UJ	<0.000892 UJ	<0.000855 U	<0.000828 U	<0.000885 U	<0.000894 U	<0.000883 UJ	<0.000895 UJ	<0.000886 UJ	<0.000843 UJ	<0.000847 U	<0.00084 U
9-Chlorohexadecafluoro-3-Oxanonane-1-Sulfonic Acid (9Cl-PF3ONS)	756426-58-1	NS	NS	NS	mg/kg	<0.000798 UJ	<0.000801 UJ	<0.00103 UJ	<0.000917 UJ	<0.000896 UJ	<0.000799 UJ	<0.000882 UJ	<0.000845 U	<0.000819 U	<0.000876 UJ	<0.000884 U	<0.000874 UJ	<0.000885 UJ	<0.000876 UJ	<0.000834 UJ	<0.000838 UJ	<0.000831 U
Hexafluoropropylene Oxide Dimer Acid (HFPO-DA)	13252-13-6	NS	NS	NS	mg/kg	<0.000853 UJ	<0.000857 UJ	<0.0011 UJ	<0.00098 UJ	<0.000958 UJ	<0.000854 UJ	<0.000944 UJ	<0.000904 U	<0.000876 U	<0.000937 U	<0.000946 U	<0.000935 UJ	<0.000947 UJ	<0.000937 UJ	<0.000892 UJ	<0.000897 U	<0.000889 U
N-ethyl Perfluorooctanesulfonamide (NEtFOSA)	4151-50-2	NS	NS	NS	mg/kg	<0.000213 U	<0.000214 U	<0.000275 U	<0.000245 U	<0.00024 U	<0.000214 U	<0.000236 U	<0.000226 U	<0.000219 U	<0.000234 U	<0.000236 U	<0.000234 U	<0.000237 U	<0.000234 U	<0.000223 U	<0.000224 U	<0.000222 U
N-ethyl Perfluorooctanesulfonamidoacetic Acid (NEtFOSAA)	2991-50-6	NS	NS	NS	mg/kg	0.000118 J	0.00105	<0.000688 U	<0.000245 UJ	<0.00024 UJ	<0.000214 U	0.001	<0.000565 U	<0.000547 U	<0.000585 U	0.000942	0.00162	<0.000592 U	<0.000586 U	0.000892	<0.00056 U	0.00123
N-ethyl Perfluorooctanesulfonamidoethanol (NEtFOSE)	1691-99-2	NS	NS	NS	mg/kg	<0.00213 U	<0.00214 U	<0.00275 U	<0.00245 U	<0.0024 U	<0.00214 U	<0.00236 U	<0.00226 U	<0.00219 U	<0.00234 U	<0.00236 U	<0.00234 U	<0.00237 U	<0.00234 U	<0.00223 U	<0.00224 U	0.001 J
N-methyl Perfluorooctanesulfonamide (NMeFOSA)	31506-32-8	NS	NS	NS	mg/kg	<0.000213 U	<0.000214 U	<0.000275 U	<0.000245 U	<0.00024 U	<0.000214 U	<0.000236 U	<0.000226 U	<0.000219 U	<0.000234 U	<0.000236 U	<0.000234 U	<0.000237 U	<0.000234 U	<0.000223 U	<0.000224 U	<0.000222 U
N-methyl Perfluorooctanesulfonamidoacetic Acid (NMeFOSAA)	2355-31-9	NS	NS	NS	mg/kg	<0.000213 UJ	<0.000214 UJ	<0.000275 UJ	<0.000245 UJ	<0.00024 UJ	<0.000214 U	<0.000236 UJ	<0.000226 U	<0.000219 U	<0.000234 U	0.000288	<0.000234 UJ	<0.000237 UJ	<0.000234 UJ	<0.000223 UJ	<0.000224 UJ	0.00014 J
N-methyl Perfluorooctanesulfonamidoethanol (NMeFOSE)	24448-09-7	NS	NS	NS	mg/kg	<0.00213 U	<0.00214 U	<0.00275 U	<0.00245 U	<0.0024 U	<0.00214 U	<0.00236 U	<0.00226 U	<0.00219 U	<0.00234 U	<0.00236 U	<0.00234 U	<0.00237 U	<0.00234 U	<0.00223 U	<0.00224 U	<0.00222 U
Nonafluoro-3,6-dioxaheptanoic Acid (NFDHA)	151772-58-6	NS	NS	NS	mg/kg	<0.000427 UJ	<0.000428 UJ	<0.000551 UJ	<0.00049 UJ	<0.000479 UJ	<0.000427 U	<0.000472 UJ	<0.000452 UJ	<0.000438 UJ	<0.000468 UJ	<0.000473 U	<0.000467 UJ	<0.000473 UJ	<0.000469 UJ	<0.000446 UJ	<0.000448 UJ	<0.000445 UJ
Perfluoro(2-ethoxyethane)sulfonic Acid (PFEESA)	113507-82-7	NS	NS	NS	mg/kg	<0.00038 UJ	<0.000381 U	<0.00049 U	<0.000436 UJ	<0.000426 UJ	<0.00038 U	<0.00042 U	<0.000402 U	<0.00039 U	<0.000417 U	<0.000421 U	<0.000416 U	<0.000421 U	<0.000417 U	<0.000397 U	<0.000399 U	<0.000396 U
Perfluoro-3-methoxypropanoic Acid (PFMPA)	377-73-1	NS	NS	NS	mg/kg	<0.000427 UJ	<0.000428 U	<0.000551 U	<0.00049 U	<0.000479 UJ	<0.000427 U	<0.000472 U	<0.000452 U	<0.000438 U	<0.000468 U	<0.000473 U	<0.000467 U	<0.000473 U	<0.000469 U	<0.000446 U	<0.000448 U	<0.000445 U
Perfluoro-4-methoxybutanoic Acid (PFMBA)	863090-89-5	NS	NS	NS	mg/kg	<0.000427 UJ	<0.000428 U	<0.000551 U	<0.00049 U	<0.000479 UJ	<0.000427 U	<0.000472 U	<0.000452 U	<0.000438 U	<0.000468 U	<0.000473 U	<0.000467 U	<0.000473 U	<0.000469 U	<0.000446 U	<0.000448 U	<0.000445 U
Perfluorobutanesulfonic Acid (PFBS)	375-73-5	NS	NS	NS	mg/kg	<0.000189 UJ	<0.00019 UJ	<0.000244 U	<0.000217 U	<0.000212 UJ	<0.000189 U	<0.000209 U	<0.0002 U	<0.000194 U	<0.000207 U	<0.000209 U	<0.000207 U	<0.000209 UJ	<0.000207 UJ	<0.000197 UJ	<0.000198 U	0.000115 J
Perfluorobutanoic Acid (PFBA)	375-22-4	NS	NS	NS	mg/kg	<0.000853 U	<0.000857 U	<0.0011 U	<0.00098 U	<0.000958 U	<0.000854 U	<0.000944 U	<0.000904 U	<0.000876 U	<0.000937 U	<0.000946 U	<0.000935 U	<0.000947 U	<0.000937 U	<0.000892 U	<0.000897 U	<0.000889 U
Perfluorodecanesulfonic Acid (PFDS)	335-77-3	NS	NS	NS	mg/kg	<0.000206 UJ	<0.000207 U	<0.000266 UJ	<0.000237 U	<0.000231 U	<0.000206 U	<0.000228 U	<0.000218 U	<0.000211 U	<0.000226 U	<0.000228 U	<0.000226 U	<0.000228 UJ	<0.000226 U	<0.000215 U	<0.000216 U	<0.000215 U
Perfluorodecanoic Acid (PFDA)	335-76-2	NS	NS	NS	mg/kg	<0.000213 UJ	<0.000214 UJ	<0.000275 UJ	<0.000245 U	<0.00024 U	<0.000214 U	<0.000236 UJ	<0.000226 U	<0.000219 U	<0.000234 U	0.00039	0.000647 J	<0.000237 UJ	<0.000234 UJ	<0.000223 UJ	<0.000224 U	0.00013 J
Perfluorododecanesulfonic Acid (PFDoS)	79780-39-5	NS	NS	NS	mg/kg	<0.000207 UJ	<0.000208 U	<0.000267 UJ	<0.000238 U	<0.000232 U	<0.000207 U	<0.000229 U	<0.000219 U	<0.000212 U	<0.000227 U	<0.000229 U	<0.000227 U	<0.000023 UJ	<0.000227 U	<0.000216 U	<0.000217 U	<0.000216 U
Perfluorododecanoic Acid (PFDoA)	307-55-1	NS	NS	NS	mg/kg	<0.000213 U	<0.000214 U	<0.000275 U	<0.000245 U	<0.00024 U	<0.000214 U	<0.000236 U	<0.000226 U	<0.000219 U	<0.000234 U	0.000363	0.000313	<0.000237 UJ	<0.000234 U	<0.000223 U	<0.000224 U	<0.000222 U
Perfluoroheptanesulfonic Acid (PFHpS)	375-92-8	NS	NS	NS	mg/kg	<0.000213 UJ	<0.000214 U	<0.000275 UJ	<0.000245 U	<0.00024 U	<0.000214 U	<0.000236 U	<0.000226 U	<0.000219 U	<0.000234 U	<0.000236 U	<0.000234 U	<0.000237 UJ	<0.000234 U	<0.000223 U	<0.000224 U	<0.000222 U
Perfluoroheptanoic Acid (PFHpA)	375-85-9	NS	NS	NS	mg/kg	<0.000213 U	<0.000214 U	<0.000275 U	<0.000245 U	<0.00024 U	<0.000214 U	<0.000236 U	<0.000226 U	<0.000219 U	<0.000234 U	<0.000236 U	0.000141 J	<0.000237 U	<0.000234 U	<0.000223 U	<0.000224 U	<0.000222 U
Perfluorohexanesulfonic Acid (PFHxS)	355-46-4	NS	NS	NS	mg/kg	0.0001 J	0.000312	0.00144	0.00158	0.00172	0.000231	<0.000216 U	0.000121 J	<0.0002 U	<0.000214 U	0.000155 J	<0.000214 UJ	<0.000217 UJ	<0.000214 UJ	<0.000204 UJ	<0.000205 U	0.000596
Perfluorohexanoic Acid (PFHxA)	307-24-4	NS	NS	NS	mg/kg	<0.000213 UJ	<0.000214 U	<0.000275 U	<0.000245 U	<0.00024 U	<0.000214 U	<0.000236 U	<0.000226 U	<0.000219 U	<0.000234 U	0.000109 J	<0.000234 U	<0.000237 U	<0.000234 U	<0.000223 U	<0.000224 U	<0.000222 U
Perfluorononanesulfonic Acid (PFNS)	68259-12-1	NS	NS	NS	mg/kg	<0.000205 UJ	<0.000206 U	<0.000264 UJ	<0.000235 UJ	<0.00023 UJ	<0.000205 U	<0.000227 U	<0.000217 U	<0.00021 U	<0.000225 U	<0.000227 U	<0.000224 U	<0.000227 UJ	<0.000225 U	<0.000214 U	<0.000215 U	<0.000213 U
Perfluorononanoic Acid (PFNA)	375-95-1	NS	NS	NS	mg/kg	<0.000213 UJ	<0.000214 U	<0.000275 U	<0.000245 UJ	<0.00024 UJ	<0.000214 U	<0.000236 U	<0.000226 U	<0.000219 U	<0.000234 U	0.000326	<0.000234 U	<0.000237 U	<0.000234 U	<0.000223 U	<0.000224 U	<0.000222 U
Perfluorooctanesulfonamide (PFOSA)	754-91-6	NS	NS	NS	mg/kg	<0.000213 UJ	<0.000214 U	<0.000275 U	<0.000245 U	<0.00024 U	<0.000214 UJ	<0.000236 U	0.0000983 J	0.0000495 J	<0.000234 U	0.000583	0.000296	<0.000237 U	<0.000234 U	<0.000223 U	<0.000224 U	0.000271
Perfluorooctanesulfonic Acid (PFOS)	1763-23-1	**0.00088**	0.001	0.044	mg/kg	0.000243 J	0.000688	0.000478 J	0.000334	0.000367	<0.000199 U	0.000691	**0.00196**	0.000374	<0.000218 U	**0.00335**	**0.00187**	<0.00022 UJ	0.000405	0.000503	**0.00126**	**0.00289**
Perfluorooctanoic Acid (PFOA)	335-67-1	**0.00066**	0.0008	0.033	mg/kg	0.000171 J	0.000241	**0.00106**	**0.00122**	**0.00129**	0.000204 J	<0.000236 U	0.000229	0.000142 J	<0.000234 U	0.000553	0.00066	<0.000237 U	0.000145 J	<0.000223 UJ	0.0000922 J	0.000408
Perfluoropentanesulfonic Acid (PFPeS)	2706-91-4	NS	NS	NS	mg/kg	<0.000201 UJ	<0.000201 U	<0.000259 U	<0.00023 U	<0.000225 U	<0.000201 U	<0.000222 U	<0.000213 U	<0.000206 U	<0.00022 U	<0.000222 U	<0.00022 UJ	<0.000222 UJ	<0.00022 UJ	<0.00021 UJ	<0.000211 U	<0.000209 U
Perfluoropentanoic Acid (PFPeA)	2706-90-3	NS	NS	NS	mg/kg	<0.000427 UJ	<0.000428 U	<0.000551 U	<0.00049 U	<0.000479 UJ	<0.000427 U	<0.000472 U	<0.000452 U	<0.000438 U	<0.000468 U	<0.000473 U	<0.000467 U	<0.000473 U	<0.000469 U	<0.000446 U	<0.000448 U	<0.000445 U
Perfluorotetradecanoic Acid (PFTeDA)	376-06-7	NS	NS	NS	mg/kg	<0.000213 U	<0.000214 U	<0.000275 U	<0.000245 U	<0.00024 U	<0.000214 U	<0.000236 U	<0.000226 U	<0.000219 U	<0.000234 U	0.000164 J	<0.000234 U	<0.000237 U	<0.000234 U	<0.000223 U	<0.000224 U	<0.000222 U
Perfluorotridecanoic Acid (PFTrDA)	72629-94-8	NS	NS	NS	mg/kg	<0.000213 U	<0.000214 U	<0.000275 U	<0.000245 U	<0.00024 U	<0.000214 U	<0.000236 U	<0.000226 U	<0.000219 U	<0.000234 U	<0.000236 U	<0.000234 U	<0.000237 U	<0.000234 U	<0.000223 U	<0.000224 U	<0.000222 U
Perfluoroundecanoic Acid (PFUnA)	2058-94-8	NS	NS	NS	mg/kg	<0.000213 U	<0.000214 U	<0.000275 U	<0.000245 U	<0.00024 U	<0.000214 U	<0.000236 U	<0.000226 U	<0.000219 U	<0.000234 U	<0.000236 U	<0.000234 U	<0.000237 UJ	<0.000234 U	<0.000223 U	<0.000224 U	<0.000222 U
General Chemistry																						
Solids, Percent	SOLID	NS	NS	NS	Percent	93.7	93.4	72.6	81.1	83.5	93.7	84.8	88.5	91.3	85.4	84.6	85.6	84.5	85.4	89.7	89.2	90

Table 2
Site Management Plan
Soil Sample Analytical Results

12074 Flatlands Avenue p/o Lot 1 Site
Brooklyn, New York
BCP Site No. C224353
Langan Project No.: 100688803

Analyte	CAS Number	NYSDEC Part 375 Unrestricted Use SCOs	NYSDEC Part 375 Protection of Groundwater SCOs	NYSDEC Part 375 Restricted Use Restricted-Residential SCOs	Location	PE96	PE96	PE97	PE98	PE99	PE100	PE101
					Sample Name	PE96_19	DUP_10012025	PE97_20	PE98_20	PE99_20	PE100_20	PE101_20
					Sample Date	10/01/2025	10/01/2025	11/11/2025	11/11/2025	11/11/2025	11/11/2025	11/11/2025
					Sample Elevation	19	19	20	20	20	20	20
					Unit	Result	Result	Result	Result	Result	Result	Result
Volatile Organic Compounds												
1,1,1,2-Tetrachloroethane	630-20-6	NS	NS	NS	mg/kg	<0.0077 U	<0.0083 U	<0.0063 U	<0.0061 U	<0.0055 U	<0.0065 U	<0.0056 U
1,1,1-Trichloroethane	71-55-6	0.68	0.68	100	mg/kg	<0.0077 U	<0.0083 U	<0.0063 U	<0.0061 U	<0.0055 U	<0.0065 U	<0.0056 U
1,1,2,2-Tetrachloroethane	79-34-5	NS	NS	NS	mg/kg	<0.0077 U	<0.0083 U	<0.0063 U	<0.0061 U	<0.0055 U	<0.0065 U	<0.0056 U
1,1,2-Trichloro-1,2,2-Trifluoroethane	76-13-1	NS	NS	NS	mg/kg	<0.0077 U	<0.0083 U	<0.0063 U	<0.0061 U	<0.0055 U	<0.0065 U	<0.0056 U
1,1,2-Trichloroethane	79-00-5	NS	NS	NS	mg/kg	<0.0077 U	<0.0083 U	<0.0063 U	<0.0061 U	<0.0055 U	<0.0065 U	<0.0056 U
1,1-Dichloroethane	75-34-3	0.27	0.27	47	mg/kg	<0.0077 U	<0.0083 U	<0.0063 U	<0.0061 U	<0.0055 U	<0.0065 U	<0.0056 U
1,1-Dichloroethene	75-35-4	0.24	0.33	0.98	mg/kg	<0.0077 U	<0.0083 U	<0.0063 U	<0.0061 U	<0.0055 U	<0.0065 U	<0.0056 U
1,1-Dichloropropene	563-58-6	NS	NS	NS	mg/kg	NA	NA	NA	NA	NA	NA	NA
1,2,3-Trichlorobenzene	87-61-6	NS	NS	NS	mg/kg	<0.0077 U	<0.0083 U	<0.0063 U	<0.0061 U	<0.0055 U	<0.0065 U	<0.0056 U
1,2,3-Trichloropropane	96-18-4	NS	NS	NS	mg/kg	<0.0077 U	<0.0083 U	<0.0063 U	<0.0061 U	<0.0055 U	<0.0065 U	<0.0056 U
1,2,4-Trichlorobenzene	120-82-1	NS	NS	NS	mg/kg	<0.0077 U	<0.0083 U	<0.0063 U	<0.0061 U	<0.0055 U	<0.0065 U	<0.0056 U
1,2,4-Trimethylbenzene	95-63-6	5.9	5.9	100	mg/kg	<0.0077 U	<0.0083 U	<0.0063 U	<0.0061 U	<0.0055 U	<0.0065 U	<0.0056 U
1,2-Dibromo-3-Chloropropane	96-12-8	NS	NS	NS	mg/kg	<0.0077 U	<0.0083 U	<0.0063 U	<0.0061 U	<0.0055 U	<0.0065 U	<0.0056 U
1,2-Dibromoethane (Ethylene Dibromide)	106-93-4	NS	NS	NS	mg/kg	<0.0077 U	<0.0083 U	<0.0063 U	<0.0061 U	<0.0055 U	<0.0065 U	<0.0056 U
1,2-Dichlorobenzene	95-50-1	1.1	1.1	100	mg/kg	<0.0077 U	<0.0083 U	<0.0063 U	<0.0061 U	<0.0055 U	<0.0065 U	<0.0056 U
1,2-Dichloroethane	107-06-2	0.02	0.02	5.8	mg/kg	<0.0077 U	<0.0083 U	<0.0063 U	<0.0061 U	<0.0055 U	<0.0065 U	<0.0056 U
1,2-Dichloropropane	78-87-5	NS	NS	NS	mg/kg	<0.0077 U	<0.0083 U	<0.0063 U	<0.0061 U	<0.0055 U	<0.0065 U	<0.0056 U
1,3,5-Trimethylbenzene (Mesitylene)	108-67-8	3.1	3.1	100	mg/kg	<0.0077 U	<0.0083 U	<0.0063 U	<0.0061 U	<0.0055 U	<0.0065 U	<0.0056 U
1,3-Dichlorobenzene	541-73-1	2.6	2.6	38	mg/kg	<0.0077 U	<0.0083 U	<0.0063 U	<0.0061 U	<0.0055 U	<0.0065 U	<0.0056 U
1,3-Dichloropropane	142-28-9	NS	NS	NS	mg/kg	NA	NA	NA	NA	NA	NA	NA
1,4-Dichlorobenzene	106-46-7	1.8	1.8	24	mg/kg	<0.0077 U	<0.0083 U	<0.0063 U	<0.0061 U	<0.0055 U	<0.0065 U	<0.0056 U
1,4-Dioxane (P-Dioxane)	123-91-1	0.1	0.1	5.7	mg/kg	NA	NA	NA	NA	NA	NA	NA
2,2-Dichloropropane	594-20-7	NS	NS	NS	mg/kg	NA	NA	NA	NA	NA	NA	NA
2-Chlorotoluene	95-49-8	NS	NS	NS	mg/kg	NA	NA	NA	NA	NA	NA	NA
2-Hexanone (MBK)	591-78-6	NS	NS	NS	mg/kg	<0.039 U	<0.041 U	<0.031 U	<0.03 U	<0.028 U	<0.032 U	<0.028 U
4-Chlorotoluene	106-43-4	NS	NS	NS	mg/kg	NA	NA	NA	NA	NA	NA	NA
Acetone	67-64-1	**0.03**	0.03	100	mg/kg	<0.077 U	<0.083 U	<0.05 U	<0.05 U	<0.05 U	<0.05 U	<0.05 U
Acrolein	107-02-8	NS	NS	NS	mg/kg	<0.0077 U	<0.0083 U	<0.0063 U	<0.0061 U	<0.0055 U	<0.0065 U	<0.0056 U
Acrylonitrile	107-13-1	NS	NS	NS	mg/kg	<0.031 U	<0.033 U	<0.025 U	<0.024 U	<0.022 U	<0.026 U	<0.022 U
Benzene	71-43-2	0.06	0.06	3.7	mg/kg	<0.0077 U	<0.0083 U	<0.0063 U	<0.0061 U	<0.0055 U	<0.0065 U	<0.0056 U
Bromobenzene	108-86-1	NS	NS	NS	mg/kg	NA	NA	NA	NA	NA	NA	NA
Bromochloromethane	74-97-5	NS	NS	NS	mg/kg	<0.0077 U	<0.0083 U	<0.0063 U	<0.0061 U	<0.0055 U	<0.0065 U	<0.0056 U
Bromodichloromethane	75-27-4	NS	NS	NS	mg/kg	<0.0077 U	<0.0083 U	<0.0063 U	<0.0061 U	<0.0055 U	<0.0065 U	<0.0056 U
Bromoform	75-25-2	NS	NS	NS	mg/kg	<0.0077 U	<0.0083 U	<0.0063 U	<0.0061 U	<0.0055 U	<0.0065 U	<0.0056 U
Bromomethane	74-83-9	NS	NS	NS	mg/kg	<0.0077 U	<0.0083 U	<0.0063 U	<0.0061 U	<0.0055 U	<0.0065 U	<0.0056 U
Carbon Disulfide	75-15-0	NS	NS	NS	mg/kg	<0.0077 U	<0.0083 U	<0.0063 U	<0.0061 U	<0.0055 U	<0.0065 U	<0.0056 U
Carbon Tetrachloride	56-23-5	0.76	0.76	7.1	mg/kg	<0.0077 U	<0.0083 U	<0.0063 U	<0.0061 U	<0.0055 U	<0.0065 U	<0.0056 U
Chlorobenzene	108-90-7	4.5	4.5	100	mg/kg	<0.0077 U	<0.0083 U	<0.0063 U	<0.0061 U	<0.0055 U	<0.0065 U	<0.0056 U
Chloroethane	75-00-3	NS	NS	NS	mg/kg	<0.0077 U	<0.0083 U	<0.0063 U	<0.0061 U	<0.0055 U	<0.0065 U	<0.0056 U
Chloroform	67-66-3	0.37	0.37	24	mg/kg	<0.0077 U	<0.0083 U	<0.0063 U	<0.0061 U	<0.0055 U	<0.0065 U	<0.0056 U
Chloromethane	74-87-3	NS	NS	NS	mg/kg	<0.0077 U	<0.0083 U	<0.0063 U	<0.0061 U	<0.0055 U	<0.0065 U	<0.0056 U
Cis-1,2-Dichloroethene	156-59-2	0.19	0.19	41	mg/kg	<0.0077 U	<0.0083 U	<0.0063 U	<0.0061 U	<0.0055 U	<0.0065 U	<0.0056 U
Cis-1,3-Dichloropropene	10061-01-5	NS	NS	NS	mg/kg	<0.0077 U	<0.0083 U	<0.0063 U	<0.0061 U	<0.0055 U	<0.0065 U	<0.0056 U
Cyclohexane	110-82-7	NS	NS	NS	mg/kg	<0.0077 U	<0.0083 U	<0.0063 U	<0.0061 U	<0.0055 U	<0.0065 U	<0.0056 U
Cymene	99-87-6	NS	NS	NS	mg/kg	<0.0077 U	<0.0083 U	0.00079 J	<0.0061 U	<0.0055 U	<0.0065 U	<0.0056 U
Dibromochloromethane	124-48-1	NS	NS	NS	mg/kg	<0.0077 U	<0.0083 U	<0.0063 U	<0.0061 U	<0.0055 U	<0.0065 U	<0.0056 U
Dibromomethane	74-95-3	NS	NS	NS	mg/kg	<0.0077 U	<0.0083 U	<0.0063 U	<0.0061 U	<0.0055 U	<0.0065 U	<0.0056 U
Dichlorodifluoromethane	75-71-8	NS	NS	NS	mg/kg	<0.0077 U	<0.0083 U	<0.0063 U	<0.0061 U	<0.0055 U	<0.0065 U	<0.0056 U
Ethylbenzene	100-41-4	1	1	76	mg/kg	<0.0077 U	<0.0083 U	<0.0063 U	<0.0061 U	<0.0055 U	<0.0065 U	<0.0056 U
Hexachlorobutadiene	87-68-3	NS	NS	NS	mg/kg	<0.0077 U	<0.0083 U	<0.0063 U	<0.0061 U	<0.0055 U	<0.0065 U	<0.0056 U
Isopropylbenzene (Cumene)	98-82-8	NS	NS	NS	mg/kg	<0.0077 U	<0.0083 U	<0.0063 U	<0.0061 U	<0.0055 U	<0.0065 U	<0.0056 U
M,P-Xylene	179601-23-1	NS	NS	NS	mg/kg	<0.0077 U	<0.0083 U	<0.0063 U	<0.0061 U	<0.0055 U	<0.0065 U	<0.0056 U
Methyl Acetate	79-20-9	NS	NS	NS	mg/kg	<0.077 U	<0.083 U	<0.063 U	<0.061 U	<0.055 U	<0.065 U	<0.056 U
Methyl Ethyl Ketone (2-Butanone)	78-93-3	0.1	0.1	100	mg/kg	<0.046 U	<0.05 U	<0.038 U	<0.036 U	<0.033 U	<0.039 U	<0.034 U
Methyl Isobutyl Ketone (4-Methyl-2-Pentanone)	108-10-1	NS	NS	NS	mg/kg	<0.039 U	<0.041 U	<0.031 U	<0.03 U	<0.028 U	<0.032 U	<0.028 U
Methylcyclohexane	108-87-2	NS	NS	NS	mg/kg	<0.0077 U	<0.0083 U	<0.0063 U	<0.0061 U	<0.0055 U	<0.0065 U	<0.0056 U
Methylene Chloride	75-09-2	0.05	0.05	81	mg/kg	<0.039 U	<0.041 U	<0.031 U	<0.03 U	<0.028 U	<0.032 U	<0.028 U
n-Butylbenzene	104-51-8	18	18	100	mg/kg	<0.0077 U	<0.0083 U	<0.0063 U	<0.0061 U	<0.0055 U	<0.0065 U	<0.0056 U
n-Propylbenzene	103-65-1	5	5	100	mg/kg	<0.0077 U	<0.0083 U	<0.0063 U	<0.0061 U	<0.0055 U	<0.0065 U	<0.0056 U
o-Xylene (1,2-Dimethylbenzene)	95-47-6	NS	NS	NS	mg/kg	<0.0077 U	<0.0083 U	<0.0063 U	<0.0061 U	<0.0055 U	<0.0065 U	<0.0056 U
Sec-Butylbenzene	135-98-8	25	25	100	mg/kg	<0.0077 U	<0.0083 U	<0.0063 U	<0.0061 U	<0.0055 U	<0.0065 U	<0.0056 U
Styrene	100-42-5	NS	NS	NS	mg/kg	<0.0077 U	<0.0083 U	<0.0063 U	<0.0061 U	<0.0055 U	<0.0065 U	<0.0056 U
T-Butylbenzene	98-06-6	11	11	100	mg/kg	<0.0077 U	<0.0083 U	<0.0063 U	<0.0061 U	<0.0055 U	<0.0065 U	<0.0056 U
Tert-Butyl Alcohol	75-65-0	NS	NS	NS	mg/kg	<0.15 U	<0.17 U	<0.13 U	<0.12 U	<0.11 U	<0.13 U	<0.11 U
Tert-Butyl Methyl Ether (MTBE)	1634-04-4	0.1	0.1	100	mg/kg	<0.015 U	<0.017 U	<0.013 U	<0.012 U	<0.011 U	<0.013 U	<0.011 U
Tetrachloroethene (PCE)	127-18-4	1.3	1.3	18	mg/kg	<0.0077 U	<0.0083 U	<0.0063 U	<0.0061 U	<0.0055 U	<0.0065 U	<0.0056 U
Toluene	108-88-3	0.7	0.7	100	mg/kg	<0.0077 U	<0.0083 U	<0.0063 U	<0.0061 U	<0.0055 U	<0.0065 U	<0.0056 U
Total Xylenes	1330-20-7	0.26	1.2	100	mg/kg	NA	NA	NA	NA	NA	NA	NA
Trans-1,2-Dichloroethene	156-60-5	0.19	0.19	100	mg/kg	<0.0077 U	<0.0083 U	<0.0063 U	<0.0061 U	<0.0055 U	<0.0065 U	<0.0056 U
Trans-1,3-Dichloropropene	10061-02-6	NS	NS	NS	mg/kg	<0.0077 U	<0.0083 U	<0.0063 U	<0.0061 U	<0.0055 U	<0.0065 U	<0.0056 U
Trans-1,4-Dichloro-2-Butene	110-57-6	NS	NS	NS	mg/kg	NA	NA	<0.013 U	<0.012 U	<0.011 U	<0.013 U	<0.011 U
Trichloroethene (TCE)	79-01-6	0.47	0.47	6.4	mg/kg	<0.0077 U	<0.0083 U	<0.0063 U	<0.0061 U	<0.0055 U	<0.0065 U	<0.0056 U
Trichlorofluoromethane	75-69-4	NS	NS	NS	mg/kg	<0.0077 U	<0.0083 U	<0.0063 U	<0.0061 U	<0.0055 U	<0.0065 U	<0.0056 U
Vinyl Chloride	75-01-4	0.03	0.03	0.48	mg/kg	<0.0077 U	<0.0083 U	<0.0063 U	<0.0061 U	<0.0055 U	<0.0065 U	<0.0056 U

Table 2
Site Management Plan
Soil Sample Analytical Results

12074 Flatlands Avenue p/o Lot 1 Site
Brooklyn, New York
BCP Site No. C224353
Langan Project No.: 100688803

Analyte	CAS Number	NYSDEC Part 375 Unrestricted Use SCOs	NYSDEC Part 375 Protection of Groundwater SCOs	NYSDEC Part 375 Restricted Use Restricted-Residential SCOs	Location	PE96	PE96	PE97	PE98	PE99	PE100	PE101
					Sample Name	PE96_19	DUP_10012025	PE97_20	PE98_20	PE99_20	PE100_20	PE101_20
					Sample Date	10/01/2025	10/01/2025	11/11/2025	11/11/2025	11/11/2025	11/11/2025	11/11/2025
					Sample Elevation	19	19	20	20	20	20	20
					Unit	Result	Result	Result	Result	Result	Result	Result
Semi-Volatile Organic Compounds												
1,2,4,5-Tetrachlorobenzene	95-94-3	NS	NS	NS	mg/kg	<0.184 U	<0.193 U	<0.202 UJ	<0.192 UJ	<0.198 UJ	<0.207 UJ	<0.191 UJ
1,2,4-Trichlorobenzene	120-82-1	NS	NS	NS	mg/kg	<0.0922 U	<0.0965 U	<0.101 UJ	<0.0961 UJ	<0.0991 UJ	<0.104 UJ	<0.0956 UJ
1,2-Dichlorobenzene	95-50-1	1.1	1.1	100	mg/kg	<0.0922 U	<0.0965 U	<0.101 UJ	<0.0961 UJ	<0.0991 UJ	<0.104 UJ	<0.0956 UJ
1,2-Diphenylhydrazine	122-66-7	NS	NS	NS	mg/kg	<0.0922 U	<0.0965 U	<0.101 UJ	<0.0961 UJ	<0.0991 UJ	<0.104 UJ	<0.0956 UJ
1,3-Dichlorobenzene	541-73-1	2.6	2.6	38	mg/kg	<0.0922 U	<0.0965 U	<0.101 UJ	<0.0961 UJ	<0.0991 UJ	<0.104 UJ	<0.0956 UJ
1,4-Dichlorobenzene	106-46-7	1.8	1.8	24	mg/kg	<0.0922 U	<0.0965 U	<0.101 UJ	<0.0961 UJ	<0.0991 UJ	<0.104 UJ	<0.0956 UJ
1,4-Dioxane (P-Dioxane)	123-91-1	0.1	0.1	5.7	mg/kg	<0.0198 U	<0.0198 U	<0.0198 U	<0.0189 U	<0.0189 U	<0.0198 U	<0.0198 U
2,3,4,6-Tetrachlorophenol	58-90-2	NS	NS	NS	mg/kg	<0.184 U	<0.193 U	<0.202 UJ	<0.192 UJ	<0.198 UJ	<0.207 UJ	<0.191 UJ
2,4,5-Trichlorophenol	95-95-4	NS	NS	NS	mg/kg	<0.0922 U	<0.0965 U	<0.101 UJ	<0.0961 UJ	<0.0991 UJ	<0.104 UJ	<0.0956 UJ
2,4,6-Trichlorophenol	88-06-2	NS	NS	NS	mg/kg	<0.0922 U	<0.0965 U	<0.101 UJ	<0.0961 UJ	<0.0991 UJ	<0.104 UJ	<0.0956 UJ
2,4-Dichlorophenol	120-83-2	NS	NS	NS	mg/kg	<0.0922 U	<0.0965 U	<0.101 UJ	<0.0961 UJ	<0.0991 UJ	<0.104 UJ	<0.0956 UJ
2,4-Dimethylphenol	105-67-9	NS	NS	NS	mg/kg	<0.0922 U	<0.0965 U	<0.101 UJ	<0.0961 UJ	<0.0991 UJ	<0.104 UJ	0.314 J
2,4-Dinitrophenol	51-28-5	NS	NS	NS	mg/kg	<0.184 U	<0.193 U	<0.202 UJ	<0.192 UJ	<0.198 UJ	<0.207 UJ	<0.191 UJ
2,4-Dinitrotoluene	121-14-2	NS	NS	NS	mg/kg	<0.0922 U	<0.0965 U	<0.101 UJ	<0.0961 UJ	<0.0991 UJ	<0.104 UJ	<0.0956 UJ
2,6-Dinitrotoluene	606-20-2	NS	NS	NS	mg/kg	<0.0922 U	<0.0965 U	<0.101 UJ	<0.0961 UJ	<0.0991 UJ	<0.104 UJ	<0.0956 UJ
2-Chloronaphthalene	91-58-7	NS	NS	NS	mg/kg	<0.0922 U	<0.0965 U	<0.101 UJ	<0.0961 UJ	<0.0991 UJ	<0.104 UJ	<0.0956 UJ
2-Chlorophenol	95-57-8	NS	NS	NS	mg/kg	<0.0922 U	<0.0965 U	<0.101 UJ	<0.0961 UJ	<0.0991 UJ	<0.104 UJ	<0.0956 UJ
2-Methylnaphthalene	91-57-6	NS	NS	NS	mg/kg	0.0464 JD	0.15 D	<0.101 UJ	0.0707 J	<0.0991 UJ	0.0996 J	7.92 J
2-Methylphenol (o-Cresol)	95-48-7	0.33	0.33	100	mg/kg	<0.0922 U	<0.0965 U	<0.101 UJ	<0.0961 UJ	<0.0991 UJ	<0.104 UJ	0.192 J
2-Nitroaniline	88-74-4	NS	NS	NS	mg/kg	<0.184 U	<0.193 U	<0.202 UJ	<0.192 UJ	<0.198 UJ	<0.207 UJ	<0.191 UJ
2-Nitrophenol	88-75-5	NS	NS	NS	mg/kg	<0.0922 U	<0.0965 U	<0.101 UJ	<0.0961 UJ	<0.0991 UJ	<0.104 UJ	<0.0956 UJ
3 & 4 Methylphenol (m&p Cresol)	65794-96-9	**0.33**	0.33	100	mg/kg	<0.0922 U	<0.0965 U	<0.101 UJ	<0.0961 UJ	<0.0991 UJ	<0.104 UJ	**0.435 J**
3,3'-Dichlorobenzidine	91-94-1	NS	NS	NS	mg/kg	<0.0922 U	<0.0965 U	<0.101 UJ	<0.0961 UJ	<0.0991 UJ	<0.104 UJ	<0.0956 UJ
3-Nitroaniline	99-09-2	NS	NS	NS	mg/kg	<0.184 U	<0.193 U	<0.202 UJ	<0.192 UJ	<0.198 UJ	<0.207 UJ	<0.191 UJ
4,6-Dinitro-2-Methylphenol	534-52-1	NS	NS	NS	mg/kg	<0.184 U	<0.193 U	<0.202 UJ	<0.192 UJ	<0.198 UJ	<0.207 UJ	<0.191 UJ
4-Bromophenyl Phenyl Ether	101-55-3	NS	NS	NS	mg/kg	<0.0922 U	<0.0965 U	<0.101 UJ	<0.0961 UJ	<0.0991 UJ	<0.104 UJ	<0.0956 UJ
4-Chloro-3-Methylphenol	59-50-7	NS	NS	NS	mg/kg	<0.0922 U	<0.0965 U	<0.101 UJ	<0.0961 UJ	<0.0991 UJ	<0.104 UJ	<0.0956 UJ
4-Chloroaniline	106-47-8	NS	NS	NS	mg/kg	<0.0922 U	<0.0965 U	<0.101 UJ	<0.0961 UJ	<0.0991 UJ	<0.104 UJ	<0.0956 UJ
4-Chlorophenyl Phenyl Ether	7005-72-3	NS	NS	NS	mg/kg	<0.0922 U	<0.0965 U	<0.101 UJ	<0.0961 UJ	<0.0991 UJ	<0.104 UJ	<0.0956 UJ
4-Nitroaniline	100-01-6	NS	NS	NS	mg/kg	<0.184 U	<0.193 U	<0.202 UJ	<0.192 UJ	<0.198 UJ	<0.207 UJ	<0.191 UJ
4-Nitrophenol	100-02-7	NS	NS	NS	mg/kg	<0.184 U	<0.193 U	<0.202 UJ	<0.192 UJ	<0.198 UJ	<0.207 UJ	<0.191 UJ
Acenaphthene	83-32-9	20	98	100	mg/kg	0.101 J	0.307 J	<0.101 UJ	0.439 J	0.0649 J	0.348 J	5.97 J
Acenaphthylene	208-96-8	100	365	100	mg/kg	<0.0922 UJ	0.588 J	<0.101 UJ	0.171 J	0.185 J	0.295 J	1.27 J
Acetophenone	98-86-2	NS	NS	NS	mg/kg	<0.0922 U	<0.0965 U	<0.101 UJ	<0.0961 UJ	<0.0991 UJ	<0.104 UJ	<0.0956 UJ
Aniline (Phenylamine, Aminobenzene)	62-53-3	0.04	0.04	8.1	mg/kg	<0.369 U	<0.386 U	<0.404 UJ	<0.385 UJ	<0.397 UJ	<0.416 UJ	<0.383 UJ
Anthracene	120-12-7	100	1000	100	mg/kg	0.19 J	1.63 J	<0.101 UJ	0.727 J	0.308 J	0.892 J	12.2 J
Atrazine	1912-24-9	NS	NS	NS	mg/kg	<0.0922 U	<0.0965 U	<0.101 UJ	<0.0961 UJ	<0.0991 UJ	<0.104 UJ	<0.0956 UJ
Benzaldehyde	100-52-7	NS	NS	NS	mg/kg	<0.0922 U	<0.0965 U	<0.101 UJ	<0.0961 UJ	<0.0991 UJ	<0.104 UJ	<0.0956 UJ
Benzidine	92-87-5	NS	NS	NS	mg/kg	<0.369 U	<0.386 U	<0.404 UJ	<0.385 UJ	<0.397 UJ	<0.416 UJ	<0.383 UJ
Benzo(a)anthracene	56-55-3	**1**	1	1.4	mg/kg	0.432 J	**3.55 J**	0.104 J	**1.38 J**	0.712 J	**1.45 J**	**13.4 J**
Benzo(a)pyrene	50-32-8	**1**	22	1	mg/kg	0.424 D	**2.3 D**	0.102 J	**1.13 J**	0.72 J	**1.23 J**	**10.9 J**
Benzo(b)fluoranthene	205-99-2	**1**	2.1	1.4	mg/kg	0.374 D	**2.14 D**	0.092 J	**1.15 J**	0.703 J	**1.19 J**	**9.11 J**
Benzo(g,h,i)Perylene	191-24-2	**0.64**	1000	4.9	mg/kg	0.231 J	**1.66 J**	0.0621 J	0.561 J	0.423 J	**0.662 J**	**6.16 J**
Benzo(k)fluoranthene	207-08-9	**0.8**	2	4.9	mg/kg	0.323 J	**1.92 J**	0.0944 J	**0.941 J**	0.6 J	**1.09 J**	**2.97 J**
Benzoic Acid	65-85-0	NS	NS	NS	mg/kg	<0.0922 UJ	<0.0965 UJ	<0.101 UJ	<0.0961 UJ	<0.0991 UJ	<0.104 UJ	<0.0956 UJ
Benzyl Alcohol	100-51-6	NS	NS	NS	mg/kg	<0.0922 U	<0.0965 U	<0.101 UJ	<0.0961 UJ	<0.0991 UJ	<0.104 UJ	<0.0956 UJ
Benzyl Butyl Phthalate	85-68-7	NS	NS	NS	mg/kg	<0.0922 U	0.258 D	<0.101 UJ	0.531 J	0.741 J	0.623 J	<0.0956 UJ
Biphenyl (Diphenyl)	92-52-4	NS	NS	NS	mg/kg	<0.0922 U	<0.0965 U	<0.101 UJ	<0.0961 UJ	<0.0991 UJ	<0.104 UJ	1.19 J
Bis(2-chloroethoxy) methane	111-91-1	NS	NS	NS	mg/kg	<0.0922 U	<0.0965 U	<0.101 UJ	<0.0961 UJ	<0.0991 UJ	<0.104 UJ	<0.0956 UJ
Bis(2-chloroethyl) ether (2-chloroethyl ether)	111-44-4	NS	NS	NS	mg/kg	<0.0922 U	<0.0965 U	<0.101 UJ	<0.0961 UJ	<0.0991 UJ	<0.104 UJ	<0.0956 UJ
Bis(2-chloroisopropyl) ether	108-60-1	NS	NS	NS	mg/kg	<0.0922 U	<0.0965 U	<0.101 UJ	<0.0961 UJ	<0.0991 UJ	<0.104 UJ	<0.0956 UJ
Bis(2-ethylhexyl) phthalate	117-81-7	NS	NS	NS	mg/kg	0.113 D	3.04 D	0.0871 J	1.22 J	0.634 J	4.91 J	0.525 J
Caprolactam	105-60-2	NS	NS	NS	mg/kg	<0.184 U	<0.193 U	<0.202 UJ	<0.192 UJ	<0.198 UJ	<0.207 UJ	<0.191 UJ
Carbazole	86-74-8	NS	NS	NS	mg/kg	0.0626 J	0.478 J	<0.101 UJ	0.253 J	0.109 J	0.217 J	2.6 J
Chrysene	218-01-9	**1**	1	4.9	mg/kg	0.45 J	**3.05 J**	0.116 J	**1.35 J**	0.786 J	**1.55 J**	**13.8 J**
Dibenz(a,h)anthracene	53-70-3	**0.33**	1000	0.33	mg/kg	0.0796 J	**0.609 J**	<0.101 UJ	0.235 J	<0.0991 UJ	0.255 J	**2.64 J**
Dibenzofuran	132-64-9	**2.1**	110	18	mg/kg	<0.0922 UJ	0.366 J	<0.101 UJ	0.262 J	<0.0991 UJ	0.184 J	**2.87 J**
Dibutyl phthalate	84-74-2	NS	NS	NS	mg/kg	<0.0922 U	0.0609 JD	<0.101 UJ	0.0614 J	<0.0991 UJ	0.293 J	<0.0956 UJ
Diethyl phthalate	84-66-2	NS	NS	NS	mg/kg	<0.0922 U	<0.0965 U	<0.101 UJ	<0.0961 UJ	<0.0991 UJ	<0.104 UJ	<0.0956 UJ
Dimethyl phthalate	131-11-3	NS	NS	NS	mg/kg	<0.0922 U	<0.0965 U	<0.101 UJ	<0.0961 UJ	<0.0991 UJ	<0.104 UJ	<0.0956 UJ
Dioctyl phthalate	117-84-0	NS	NS	NS	mg/kg	<0.0922 UJ	0.668 J	<0.101 UJ	0.0653 J	<0.0991 UJ	<0.104 UJ	<0.0956 UJ
Fluoranthene	206-44-0	85	1000	100	mg/kg	0.897 J	9.02 J	0.226 J	2.62 J	1.16 J	2.84 J	22.9 J
Fluorene	86-73-7	30	386	100	mg/kg	0.112 J	0.666 J	<0.101 UJ	0.486 J	0.0998 J	0.558 J	8.01 J
Hexachlorobenzene	118-74-1	0.33	3.2	0.33	mg/kg	<0.0922 U	<0.0965 U	<0.101 UJ	<0.0961 UJ	<0.0991 UJ	<0.104 UJ	<0.0956 UJ
Hexachlorobutadiene	87-68-3	NS	NS	NS	mg/kg	<0.0922 U	<0.0965 U	<0.101 UJ	<0.0961 UJ	<0.0991 UJ	<0.104 UJ	<0.0956 UJ
Hexachlorocyclopentadiene	77-47-4	NS	NS	NS	mg/kg	<0.0922 UJ	<0.0965 UJ	<0.101 UJ	<0.0961 UJ	<0.0991 UJ	<0.104 UJ	<0.0956 UJ
Hexachloroethane	67-72-1	NS	NS	NS	mg/kg	<0.0922 U	<0.0965 U	<0.101 UJ	<0.0961 UJ	<0.0991 UJ	<0.104 UJ	<0.0956 UJ
Indeno(1,2,3-cd)pyrene	193-39-5	**0.5**	6.6	1.4	mg/kg	0.234 J	**2.14 J**	0.0605 J	**0.646 J**	0.448 J	**0.694 J**	**5.84 J**
Isophorone	78-59-1	NS	NS	NS	mg/kg	<0.0922 U	<0.0965 U	<0.101 UJ	<0.0961 UJ	<0.0991 UJ	<0.104 UJ	<0.0956 UJ
Naphthalene	91-20-3	12	12	100	mg/kg	0.0936 J	0.416 J	<0.101 UJ	0.225 J	0.057 J	0.1 J	11.7 J
Nitrobenzene	98-95-3	0.08	0.08	1.8	mg/kg	<0.0922 U	<0.0965 U	<0.101 UJ	<0.0961 UJ	<0.0991 UJ	<0.104 UJ	<0.0956 UJ
n-Nitrosodimethylamine	62-75-9	NS	NS	NS	mg/kg	<0.0922 U	<0.0965 U	<0.101 UJ	<0.0961 UJ	<0.0991 UJ	<0.104 UJ	<0.0956 UJ
n-Nitrosodi-N-Propylamine	621-64-7	NS	NS	NS	mg/kg	<0.0922 U	<0.0965 U	<0.101 UJ	<0.0961 UJ	<0.0991 UJ	<0.104 UJ	<0.0956 UJ
n-Nitrosodiphenylamine	86-30-6	NS	NS	NS	mg/kg	<0.0922 U	<0.0965 U	<0.101 UJ	<0.0961 UJ	<0.0991 UJ	<0.104 UJ	<0.0956 UJ
Pentachlorophenol	87-86-5	0.8	0.8	1.3	mg/kg	<0.0922 U	<0.0965 U	<0.101 UJ	<0.0961 UJ	<0.0991 UJ	<0.104 UJ	<0.0956 UJ
Phenanthrene	85-01-8	**1.1**	1000	4.9	mg/kg	0.693 J	**2.87 J**	0.181 J	**1.85 J**	0.908 J	**2.39 J**	**38 J**
Phenol	108-95-2	0.33	0.33	100	mg/kg	<0.0922 U	<0.0965 U	<0.101 UJ	<0.0961 UJ	<0.0991 UJ	<0.104 UJ	0.287 J
Pyrene	129-00-0	64	1000	100	mg/kg	0.791 J	7.68 J	0.221 J	2.4 J	1.41 J	2.87 J	24.9 J
Pyridine	110-86-1	NS	NS	NS	mg/kg	<0.369 U	<0.386 U	<0.404 UJ	<0.385 UJ	<0.397 UJ	<0.416 UJ	<0.383 UJ

Table 2
Site Management Plan
Soil Sample Analytical Results

12074 Flatlands Avenue p/o Lot 1 Site
Brooklyn, New York
BCP Site No. C224353
Langan Project No.: 100688803

Analyte	CAS Number	NYSDEC Part 375 Unrestricted Use SCOs	NYSDEC Part 375 Protection of Groundwater SCOs	NYSDEC Part 375 Restricted Use Restricted-Residential SCOs	Location	PE96	PE96	PE97	PE98	PE99	PE100	PE101
					Sample Name	PE96_19	DUP_10012025	PE97_20	PE98_20	PE99_20	PE100_20	PE101_20
					Sample Date	10/01/2025	10/01/2025	11/11/2025	11/11/2025	11/11/2025	11/11/2025	11/11/2025
					Sample Elevation	19	19	20	20	20	20	20
					Unit	Result	Result	Result	Result	Result	Result	Result
Pesticides												
4,4'-DDD	72-54-8	**0.0033**	14	5	mg/kg	**0.0159 J**	**0.0526 J**	**0.00451 J**	**0.0154 DP**	**0.033 DP**	**0.0175 DP**	0.00211 DP
4,4'-DDE	72-55-9	**0.0033**	9.3	3.4	mg/kg	**0.00669 J**	**0.0158 J**	<0.00199 UP	**0.0122 DP**	**0.0163 DP**	**0.0112 J**	<0.00189 UP
4,4'-DDT	50-29-3	**0.0033**	135	3.8	mg/kg	**0.00426 J**	**0.00911 J**	<0.00199 UP	0.00305 J	**0.00393 J**	0.00259 J	<0.00189 UP
Aldrin	309-00-2	0.0048	0.19	0.044	mg/kg	<0.00182 UP	<0.00192 UP	<0.00199 UP	<0.00189 UP	<0.00199 UP	<0.00204 UP	<0.00189 UP
Alpha BHC (Alpha Hexachlorocyclohexane)	319-84-6	0.02	0.02	0.18	mg/kg	<0.00182 UP	<0.00192 UP	<0.00199 UP	<0.00189 UP	<0.00199 UP	<0.00204 UP	<0.00189 UP
Alpha Chlordane	5103-71-9	**0.014**	4.5	0.65	mg/kg	0.00195 J	0.00716 J	<0.00199 UP	0.00363 DP	0.00547 DP	0.00493 DP	<0.00189 UP
Alpha Endosulfan	959-98-8	4.3	65	35	mg/kg	<0.00182 UP	<0.00192 UP	<0.00199 UP	<0.00189 UP	<0.00199 UP	<0.00204 UP	<0.00189 UP
Beta Bhc (Beta Hexachlorocyclohexane)	319-85-7	0.021	0.09	0.18	mg/kg	<0.00182 UP	<0.00192 UP	<0.00199 UP	<0.00189 UP	<0.00199 UP	<0.00204 UP	<0.00189 UP
Beta Endosulfan	33213-65-9	4.3	44	35	mg/kg	<0.00182 UP	<0.00192 UP	<0.00199 UP	<0.00189 UP	<0.00199 UP	<0.00204 UP	<0.00189 UP
Delta Bhc (Delta Hexachlorocyclohexane)	319-86-8	0.04	0.1	100	mg/kg	<0.00182 UP	<0.00192 UP	<0.00199 UP	<0.00189 UP	<0.00199 UP	<0.00204 UP	<0.00189 UP
Dieldrin	60-57-1	**0.005**	0.1	0.075	mg/kg	0.00297 J	**0.0144 J**	<0.00199 UP	0.00207 J	**0.00646 J**	0.00313 J	<0.00189 UP
Endosulfan Sulfate	1031-07-8	4.3	47	35	mg/kg	<0.00182 UP	<0.00192 UP	<0.00199 UP	<0.00189 UP	<0.00199 UP	<0.00204 UP	<0.00189 UP
Endrin	72-20-8	0.014	0.06	5.3	mg/kg	<0.00182 UP	<0.00192 UP	<0.00199 UP	<0.00189 UP	<0.00199 UP	<0.00204 UP	<0.00189 UP
Endrin Aldehyde	7421-93-4	NS	NS	NS	mg/kg	<0.00182 UP	<0.00192 UP	<0.00199 UP	<0.00189 UP	<0.00199 UP	<0.00204 UP	<0.00189 UP
Endrin Ketone	53494-70-5	NS	NS	NS	mg/kg	<0.00182 UP	<0.00192 UP	<0.00199 UP	<0.00189 UP	<0.00199 UP	<0.00204 UP	<0.00189 UP
Gamma Bhc (Lindane)	58-89-9	0.025	0.05	0.21	mg/kg	<0.00182 UP	<0.00192 UP	<0.00199 UP	<0.00189 UP	<0.00199 UP	<0.00204 UP	<0.00189 UP
Gamma-Chlordane	5566-34-7	NS	NS	NS	mg/kg	0.00191 J	0.0156 J	<0.00199 UP	0.00459 J	0.00587 J	0.00632 J	<0.00189 UP
Heptachlor	76-44-8	0.013	0.38	0.53	mg/kg	<0.00182 UP	<0.00192 UP	<0.00199 UP	0.0022 J	0.00516 DP	<0.00204 UP	<0.00189 UP
Heptachlor Epoxide	1024-57-3	NS	NS	NS	mg/kg	<0.00182 UP	<0.00192 UP	<0.00199 UP	<0.00189 UP	<0.00199 UP	<0.00204 UP	<0.00189 UP
Methoxychlor	72-43-5	NS	NS	NS	mg/kg	<0.00182 UP	<0.00192 UP	<0.00199 UP	<0.00189 UP	<0.00199 UP	<0.00204 UP	<0.00189 UP
Toxaphene	8001-35-2	NS	NS	NS	mg/kg	<0.182 UP	<0.192 UP	<0.199 UP	<0.189 UP	<0.199 UP	<0.204 UP	<0.189 UP
Herbicides												
2,4,5-T (Trichlorophenoxyacetic Acid)	93-76-5	NS	NS	NS	mg/kg	<0.0222 UP	<0.0233 UP	<0.0243 UP	<0.0225 UP	<0.0241 UP	<0.0249 UP	<0.0231 UP
2,4-D (Dichlorophenoxyacetic Acid)	94-75-7	NS	NS	NS	mg/kg	<0.0222 UP	<0.0233 UP	<0.0243 UP	<0.0225 UP	<0.0241 UP	<0.0249 UP	<0.0231 UP
2,4-Dichlorophenoxybutyric acid	94-82-6	NS	NS	NS	mg/kg	NA	NA	NA	NA	NA	NA	NA
Dalapon	75-99-0	NS	NS	NS	mg/kg	NA	NA	NA	NA	NA	NA	NA
Dicamba	1918-00-9	NS	NS	NS	mg/kg	NA	NA	NA	NA	NA	NA	NA
Silvex (2,4,5-Tp)	93-72-1	3.8	3.8	100	mg/kg	<0.0222 UP	<0.0233 UP	<0.0243 UP	<0.0225 UP	<0.0241 UP	<0.0249 UP	<0.0231 UP
Polychlorinated Biphenyl												
PCB-1016 (Aroclor 1016)	12674-11-2	NS	NS	NS	mg/kg	<0.0184 UJ	<0.0193 UJ	<0.0201 UP	<0.0191 UP	<0.0201 UP	<0.0206 UP	<0.0191 UP
PCB-1221 (Aroclor 1221)	11104-28-2	NS	NS	NS	mg/kg	<0.0184 UJ	<0.0193 UJ	<0.0201 UP	<0.0191 UP	<0.0201 UP	<0.0206 UP	<0.0191 UP
PCB-1232 (Aroclor 1232)	11141-16-5	NS	NS	NS	mg/kg	<0.0184 UJ	<0.0193 UJ	<0.0201 UP	<0.0191 UP	<0.0201 UP	<0.0206 UP	<0.0191 UP
PCB-1242 (Aroclor 1242)	53469-21-9	NS	NS	NS	mg/kg	<0.0184 UJ	0.0245 J	<0.0201 UP	0.0782 P	0.0564 P	0.117 P	<0.0191 UP
PCB-1248 (Aroclor 1248)	12672-29-6	NS	NS	NS	mg/kg	<0.0184 UJ	<0.0193 UJ	<0.0201 UP	<0.0191 UP	<0.0201 UP	<0.0206 UP	<0.0191 UP
PCB-1254 (Aroclor 1254)	11097-69-1	NS	NS	NS	mg/kg	0.0211 J	0.0385 J	<0.0201 UP	0.117 P	0.0788 P	0.0817 P	<0.0191 UP
PCB-1260 (Aroclor 1260)	11096-82-5	NS	NS	NS	mg/kg	<0.0184 UJ	<0.0193 UJ	<0.0201 UP	<0.0191 UP	<0.0201 UP	<0.0206 UP	<0.0191 UP
PCB-1262 (Aroclor 1262)	37324-23-5	NS	NS	NS	mg/kg	NA	NA	NA	NA	NA	NA	NA
PCB-1268 (Aroclor 1268)	11100-14-4	NS	NS	NS	mg/kg	0.0441 J	<0.0193 UJ	NA	NA	NA	NA	NA
Total PCBs	1336-36-3	**0.1**	3.2	1	mg/kg	0.0652 J	0.063 J	<0.0201 UP	**0.195 P**	**0.135 P**	**0.198 P**	<0.0191 UP
Metals												
Aluminum	7429-90-5	NS	NS	NS	mg/kg	6,440	7,510	5,740	7,220	8,410	6,110	4,920
Antimony	7440-36-0	NS	NS	NS	mg/kg	<2.32 U	<2.43 U	<2.54 U	<2.42 U	<2.53 UJ	<2.6 U	<2.41 U
Arsenic	7440-38-2	**13**	16	16	mg/kg	5.9	8.06	8.01	3.92	5.31	8.2	3.75
Barium	7440-39-3	**410**	820	410	mg/kg	**618**	**914**	315	298	**505 J**	388	274
Beryllium	7440-41-7	4.4	47	43	mg/kg	0.199	0.246	0.241	0.138	0.132 J	0.232	0.145
Cadmium	7440-43-9	**2.5**	7.5	2.5	mg/kg	0.992	1.24	1.15	0.725	0.912	1.28	0.82
Calcium	7440-70-2	NS	NS	NS	mg/kg	12,500 J	23,100 J	4,890 J	20,600 J	50,700 J	45,800 J	6,670 J
Chromium, Hexavalent	18540-29-9	1	19	1	mg/kg	<0.556 U	<0.584 U	<0.609 U	<0.58 U	<0.608 UJ	<0.624 U	<0.579 U
Chromium, Total	7440-47-3	NS	NS	NS	mg/kg	23.9	22.1	22.7	20.2	27.5	40.5	20.7
Chromium, Trivalent	16065-83-1	**30**	19	110	mg/kg	23.9	22.1	22.7	20.2	27.5	**40.5**	20.7
Cobalt	7440-48-4	NS	NS	NS	mg/kg	6.17	6.15	5.92	6.04	6.12 J	6.93	4.95
Copper	7440-50-8	**50**	1720	280	mg/kg	**72.3**	**70.2**	**111**	34.7	**52.4 J**	**120**	**142**
Cyanide	57-12-5	**2.3**	40	13	mg/kg	<0.556 U	1.27	0.695	<0.58 U	1.2 J	1.87	<0.579 U
Iron	7439-89-6	NS	NS	NS	mg/kg	21,600	20,600	19,000	15,300	34,300	30,400	15,900
Lead	7439-92-1	**63**	450	400	mg/kg	**344**	**455**	**368 J**	**176 J**	**1,070 J**	**377 J**	**259 J**
Magnesium	7439-95-4	NS	NS	NS	mg/kg	3,200	3,720	1,570	4,660	4,930	16,400	2,530
Manganese	7439-96-5	**1600**	2000	2000	mg/kg	225	306	154	228	321	293	232
Mercury	7439-97-6	**0.18**	0.73	0.3	mg/kg	**0.434 J**	**0.984 J**	**0.347**	**0.272**	**1.08**	**0.393**	**0.356**
Nickel	7440-02-0	**30**	130	320	mg/kg	24.9	19.1	19.1	19.2	17.3 J	**37.1**	16.5
Potassium	7440-09-7	NS	NS	NS	mg/kg	752	931	636	1,630	1,070	1,260	741
Selenium	7782-49-2	**3.9**	4	110	mg/kg	<2.32 U	<2.43 U	<2.54 U	<2.42 U	<2.53 U	<2.6 U	<2.41 U
Silver	7440-22-4	**2**	8.3	110	mg/kg	0.779	<0.491 U	1.37 J	<0.487 UJ	<0.511 UJ	**86.5 J**	<0.486 UJ
Sodium	7440-23-5	NS	NS	NS	mg/kg	185 J	443 J	167 J	194 J	287 J	347 J	165 J
Thallium	7440-28-0	NS	NS	NS	mg/kg	<1.86 U	<1.95 U	<2.03 U	<1.94 U	<2.03 U	<2.09 U	<1.93 U
Vanadium	7440-62-2	NS	NS	NS	mg/kg	18.7	22.8	19.1	38.8	22	22.2	22
Zinc	7440-66-6	**109**	2480	6600	mg/kg	**432**	**583**	**337**	**281**	**582**	**1,600**	**347**

Table 2
Site Management Plan
Soil Sample Analytical Results

12074 Flatlands Avenue p/o Lot 1 Site
Brooklyn, New York
BCP Site No. C224353
Langan Project No.: 100688803

Analyte	CAS Number	NYSDEC Part 375 Unrestricted Use SCOs	NYSDEC Part 375 Protection of Groundwater SCOs	NYSDEC Part 375 Restricted Use Restricted-Residential SCOs	Location	PE96	PE96	PE97	PE98	PE99	PE100	PE101
					Sample Name	PE96_19	DUP_10012025	PE97_20	PE98_20	PE99_20	PE100_20	PE101_20
					Sample Date	10/01/2025	10/01/2025	11/11/2025	11/11/2025	11/11/2025	11/11/2025	11/11/2025
					Sample Elevation	19	19	20	20	20	20	20
					Unit	Result	Result	Result	Result	Result	Result	Result
Per- and Polyfluoroalkyl Substances												
11-Chloroeicosafluoro-3-Oxaundecane-1-Sulfonic Acid (11Cl-PF3OUdS)	763051-92-9	NS	NS	NS	mg/kg	<0.000841 UJ	<0.000883 U	<0.000921 UJ	<0.000877 UJ	<0.000919 UJ	<0.000944 UJ	<0.000875 UJ
1H,1H,2H,2H-Perfluorodecane Sulfonic Acid (8:2 FTS)	39108-34-4	NS	NS	NS	mg/kg	<0.000854 U	<0.000897 U	<0.000936 U	<0.000891 U	<0.000934 U	<0.000959 U	<0.000889 U
1H,1H,2H,2H-Perfluorohexane Sulfonic Acid (4:2 FTS)	757124-72-4	NS	NS	NS	mg/kg	<0.000834 UJ	<0.000876 UJ	<0.000914 UJ	<0.00087 UJ	<0.000912 UJ	<0.000936 UJ	<0.000868 UJ
1H,1H,2H,2H-Perfluorooctane Sulfonic Acid (6:2 FTS)	27619-97-2	NS	NS	NS	mg/kg	<0.000846 U	<0.000888 U	<0.000926 U	<0.000881 U	<0.000924 U	<0.000949 UJ	<0.00088 U
2H,2H,3H,3H-Perfluorooctanoic Acid (5:3 FTCA)	914637-49-3	NS	NS	NS	mg/kg	<0.00556 U	<0.00584 U	<0.00609 U	<0.0058 U	<0.00608 U	<0.00624 UJ	<0.00579 U
3-Perfluoroheptyl Propanoic Acid (7:3 FTCA)	812-70-4	NS	NS	NS	mg/kg	<0.00556 U	<0.00584 U	<0.00609 U	<0.0058 U	<0.00608 U	<0.00624 UJ	<0.00579 U
3-Perfluoropropyl Propanoic Acid (3:3 FTCA)	356-02-5	NS	NS	NS	mg/kg	<0.00111 U	<0.00117 U	<0.00122 U	<0.00116 U	<0.00122 U	<0.00125 UJ	<0.00116 U
4,8-Dioxa-3H-perfluorononanoic Acid (ADONA)	919005-14-4	NS	NS	NS	mg/kg	<0.000841 UJ	<0.000883 U	<0.000921 UJ	<0.000877 UJ	<0.000919 UJ	<0.000944 UJ	<0.000875 UJ
9-Chlorohexadecafluoro-3-Oxanonane-1-Sulfonic Acid (9Cl-PF3ONS)	756426-58-1	NS	NS	NS	mg/kg	<0.000832 UJ	<0.000874 U	<0.000911 UJ	<0.000867 UJ	<0.000909 UJ	<0.000934 UJ	<0.000866 UJ
Hexafluoropropylene Oxide Dimer Acid (HFPO-DA)	13252-13-6	NS	NS	NS	mg/kg	<0.00089 UJ	<0.000935 U	<0.000975 U	<0.000928 U	<0.000972 U	<0.000999 U	<0.000926 U
N-ethyl Perfluorooctanesulfonamide (NEtFOSA)	4151-50-2	NS	NS	NS	mg/kg	<0.000223 U	<0.000234 U	<0.000244 U	<0.000232 U	0.000211 J	<0.00025 U	<0.000231 U
N-ethyl Perfluorooctanesulfonamidoacetic Acid (NEtFOSAA)	2991-50-6	NS	NS	NS	mg/kg	<0.000556 U	0.00111	<0.00609 U	0.00127	0.00249	0.00182	<0.000579 U
N-ethyl Perfluorooctanesulfonamidoethanol (NEtFOSE)	1691-99-2	NS	NS	NS	mg/kg	<0.00223 U	0.000823 J	<0.00244 U	<0.00232 U	0.00108 J	<0.0025 U	<0.00231 U
N-methyl Perfluorooctanesulfonamide (NMeFOSA)	31506-32-8	NS	NS	NS	mg/kg	<0.000223 U	<0.000234 U	<0.000244 U	<0.000232 U	<0.000243 U	<0.00025 U	<0.000231 U
N-methyl Perfluorooctanesulfonamidoacetic Acid (NMeFOSAA)	2355-31-9	NS	NS	NS	mg/kg	<0.000223 U	<0.000234 U	<0.000244 UJ	<0.000232 U	0.000116 J	0.000197 J	<0.000231 U
N-methyl Perfluorooctanesulfonamidoethanol (NMeFOSE)	24448-09-7	NS	NS	NS	mg/kg	<0.00223 U	<0.00234 U	<0.00244 U	<0.00232 U	<0.00243 U	<0.0025 U	<0.00231 U
Nonafluoro-3,6-dioxaheptanoic Acid (NFDHA)	151772-58-6	NS	NS	NS	mg/kg	<0.000445 UJ	<0.000467 UJ	<0.000487 UJ	<0.000464 UJ	<0.000486 UJ	<0.000499 UJ	<0.000463 UJ
Perfluoro(2-ethoxyethane)sulfonic Acid (PFEESA)	113507-82-7	NS	NS	NS	mg/kg	<0.000396 U	<0.000416 U	<0.000434 U	<0.000413 U	<0.000433 U	<0.000445 UJ	<0.000412 U
Perfluoro-3-methoxypropanoic Acid (PFMPA)	377-73-1	NS	NS	NS	mg/kg	<0.000445 U	<0.000467 U	<0.000487 U	<0.000464 U	<0.000486 U	<0.000499 UJ	<0.000463 U
Perfluoro-4-methoxybutanoic Acid (PFMBA)	863090-89-5	NS	NS	NS	mg/kg	<0.000445 U	<0.000467 U	<0.000487 U	<0.000464 U	<0.000486 U	<0.000499 UJ	<0.000463 U
Perfluorobutanesulfonic Acid (PFBS)	375-73-5	NS	NS	NS	mg/kg	<0.000197 U	<0.000207 U	<0.000216 U	<0.000205 U	<0.000215 U	<0.000221 UJ	<0.000205 U
Perfluorobutanoic Acid (PFBA)	375-22-4	NS	NS	NS	mg/kg	<0.00089 U	<0.000935 U	<0.000975 U	<0.000928 U	<0.000972 U	<0.000999 UJ	<0.000926 U
Perfluorodecanesulfonic Acid (PFDS)	335-77-3	NS	NS	NS	mg/kg	<0.000215 U	<0.000226 U	<0.000235 U	<0.000224 U	<0.000235 U	<0.000241 U	<0.000223 U
Perfluorodecanoic Acid (PFDA)	335-76-2	NS	NS	NS	mg/kg	<0.000223 U	<0.000234 U	<0.000244 U	<0.000232 U	<0.000243 U	<0.00025 UJ	<0.000231 U
Perfluorododecanesulfonic Acid (PFDoS)	79780-39-5	NS	NS	NS	mg/kg	<0.000216 U	<0.000227 U	<0.000236 U	<0.000225 U	<0.000236 U	<0.000242 U	<0.000225 U
Perfluorododecanoic Acid (PFDoA)	307-55-1	NS	NS	NS	mg/kg	<0.000223 U	<0.000234 U	<0.000244 U	<0.000232 U	<0.000243 U	<0.00025 UJ	<0.000231 U
Perfluoroheptanesulfonic Acid (PFHpS)	375-92-8	NS	NS	NS	mg/kg	<0.000223 U	<0.000234 U	<0.000244 U	<0.000232 U	<0.000243 U	<0.00025 U	<0.000231 U
Perfluoroheptanoic Acid (PFHpA)	375-85-9	NS	NS	NS	mg/kg	<0.000223 U	<0.000234 U	<0.000244 U	<0.000232 U	<0.000243 U	<0.00025 U	<0.000231 U
Perfluorohexanesulfonic Acid (PFHxS)	355-46-4	NS	NS	NS	mg/kg	<0.000204 U	<0.000214 U	<0.000223 U	<0.000212 U	<0.000222 U	<0.000229 UJ	<0.000212 U
Perfluorohexanoic Acid (PFHxA)	307-24-4	NS	NS	NS	mg/kg	<0.000223 U	<0.000234 U	<0.000244 U	<0.000232 U	<0.000243 U	<0.00025 UJ	<0.000231 U
Perfluorononanesulfonic Acid (PFNS)	68259-12-1	NS	NS	NS	mg/kg	<0.000214 U	<0.000224 U	<0.000234 UJ	<0.000223 UJ	<0.000233 UJ	<0.00024 UJ	<0.000222 UJ
Perfluorononanoic Acid (PFNA)	375-95-1	NS	NS	NS	mg/kg	<0.000223 U	<0.000234 U	<0.000244 U	<0.000232 U	<0.000243 U	<0.00025 U	<0.000231 U
Perfluorooctanesulfonamide (PFOSA)	754-91-6	NS	NS	NS	mg/kg	0.0000612 J	0.0000792 J	<0.000244 U	<0.000232 U	0.000117 J	<0.00025 U	<0.000231 U
Perfluorooctanesulfonic Acid (PFOS)	1763-23-1	**0.00088**	0.001	0.044	mg/kg	0.000242 J	0.000866 J	0.000324	0.000377	**0.00126**	0.000561	0.000413
Perfluorooctanoic Acid (PFOA)	335-67-1	**0.00066**	0.0008	0.033	mg/kg	0.000144 J	0.000191 J	<0.000244 UJ	<0.000232 UJ	0.000174 J	0.000284 J	<0.000231 UJ
Perfluoropentanesulfonic Acid (PFPeS)	2706-91-4	NS	NS	NS	mg/kg	<0.000209 U	<0.00022 U	<0.000229 U	<0.000218 U	<0.000229 U	<0.000235 UJ	<0.000218 U
Perfluoropentanoic Acid (PFPeA)	2706-90-3	NS	NS	NS	mg/kg	<0.000445 U	<0.000467 U	<0.000487 U	<0.000464 U	<0.000486 U	<0.000499 UJ	<0.000463 U
Perfluorotetradecanoic Acid (PFTeDA)	376-06-7	NS	NS	NS	mg/kg	<0.000223 U	<0.000234 U	<0.000244 U	<0.000232 U	<0.000243 U	<0.00025 U	<0.000231 U
Perfluorotridecanoic Acid (PFTrDA)	72629-94-8	NS	NS	NS	mg/kg	<0.000223 U	<0.000234 U	<0.000244 U	<0.000232 U	<0.000243 U	<0.00025 U	<0.000231 U
Perfluoroundecanoic Acid (PFUnA)	2058-94-8	NS	NS	NS	mg/kg	<0.000223 U	<0.000234 U	<0.000244 U	<0.000232 U	<0.000243 U	<0.00025 U	<0.000231 U
General Chemistry												
Solids, Percent	SOLID	NS	NS	NS	Percent	89.9	85.6	82.1	86.2	82.3	80.1	86.4

Table 2
Site Management Plan
Soil Sample Analytical Results

12074 Flatlands Avenue p/o Lot 1 Site
Brooklyn, New York
BCP Site No. C224353
Langan Project No.: 100688803

Notes:

CAS - Chemical Abstract Service
NS - No standard
mg/kg - milligram per kilogram
NA - Not analyzed
RL - Reporting limit
<RL - Not detected

Soil sample analytical results are compared to the New York State Department of Environmental Conservation (NYSDEC) Title 6 of the Official Compilation of New York Codes, Rules, and Regulations (NYCRR) Part 375 Unrestricted Use, Protection of Groundwater, and Restricted Use Restricted-Residential Soil Cleanup Objectives (SCO) (December 2025).

Soil sample analytical results are compared to the New York State Department of Environmental Conservation (NYSDEC) Part 375 Remedial Programs Guidelines for Sampling and Analysis of Per- and Polyfluoroalkyl Substances (PFAS) Unrestricted Use, Restricted Use Restricted-Residential, and Protection of Groundwater Guidance Values (April 2023).

Criterion comparisons for 3- & 4-methylphenol (m&p cresol) are provided for reference. Promulgated SCOs are for 3-methylphenol (m-cresol) and 4-methylphenol (p-cresol).

Qualifiers:

D - The concentration reported is a result of a diluted sample.
E - The result is estimated and cannot be accurately reported due to levels encountered or interferences. (York)
P - The relative percent difference (RPD) between the results for the two columns exceeds the method-specified criteria.
B - The analyte was found in the associated analysis batch blank.
J - The analyte was positively identified and the associated numerical value is the approximate concentration of
UJ - The analyte was not detected at a level greater than or equal to the RL; however, the reported RL is approximate and may be inaccurate or imprecise.
U - The analyte was analyzed for, but was not detected at a level greater than or equal to the level of the RL or the sample concentration for results impacted by blank contamination.

S - Laboratory solvent, contamination is possible.

Exceedance Summary:

10 - Result exceeds Unrestricted Use SCOs
10 - Result exceeds Protection of Groundwater SCOs
10 - Result exceeds Restricted Use Restricted-Residential SCOs

Table 3
Site Management Plan
Groundwater Sample Analytical Results

12074 Flatlands Avenue p/o Lot 1 Site
Brooklyn, New York
NYSDEC BCP Site No.: C224353
Langan Project No.: 100688803

Analyte	CAS Number	NYSDEC SGVs	Location	LMW-4	LMW-4	LMW-6	LMW-6	LMW-15	LMW-16	LMW-17	LMW-18	LMW-19	LMW-20	LMW-21	LMW-21	LMW-22	LMW-23	LMW-24	LMW-25
			Sample Name	059_LMW-4	LMW-4_030823	055_LMW-6	LMW-6_030723	LMW-15_030723	LMW-16_030723	LMW-17_030723	LMW-18_030723	LMW-19_030723	LMW-20_030823	LMW-21_030823	DUP04_030823	LMW-22_030823	LMW-23_030823	LMW-24_030723	LMW-25_030723
			Sample Date	05/14/2018	03/08/2023	05/14/2018	03/07/2023	03/07/2023	03/07/2023	03/07/2023	03/07/2023	03/07/2023	03/08/2023	03/08/2023	03/08/2023	03/08/2023	03/08/2023	03/07/2023	03/07/2023
			Unit	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result
Volatile Organic Compounds																			
1,1,1,2-Tetrachloroethane	630-20-6	5	ug/l	<0.2 U	<2.5 U	<0.2 UJ	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<25 U	<25 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U
1,1,1-Trichloroethane	71-55-6	5	ug/l	<0.2 U	<2.5 U	<0.2 UJ	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<25 U	<25 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U
1,1,2,2-Tetrachloroethane	79-34-5	5	ug/l	<0.2 U	<0.5 U	<0.2 U	<0.5 U	<0.5 U	<0.5 U	<0.5 U	<0.5 U	<0.5 U	<0.5 U	<5 U	<5 U	<0.5 U	<0.5 U	<0.5 U	<0.5 U
1,1,2-Trichloro-1,2,2-Trifluoroethane	76-13-1	5	ug/l	<0.2 UJ	NA	<0.2 U	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
1,1,2-Trichloroethane	79-00-5	1	ug/l	<0.2 U	<1.5 U	<0.2 U	<1.5 U	<1.5 U	<1.5 U	<1.5 U	<1.5 U	<1.5 U	<1.5 U	<15 U	<15 U	<1.5 U	<1.5 U	<1.5 U	<1.5 U
1,1-Dichloroethane	75-34-3	5	ug/l	<0.2 U	<2.5 U	<0.2 UJ	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<25 U	<25 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U
1,1-Dichloroethene	75-35-4	5	ug/l	<0.2 U	<0.5 U	<0.2 U	<0.5 U	<0.5 U	<0.5 U	<0.5 U	<0.5 U	<0.5 U	<0.5 U	<5 U	<5 U	<0.5 U	<0.5 U	<0.5 U	<0.5 U
1,1-Dichloropropene	563-58-6	5	ug/l	<0.2 U	<2.5 U	<0.2 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<25 U	<25 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U
1,2,3-Trichlorobenzene	87-61-6	5	ug/l	<0.2 U	<2.5 U	<0.2 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<25 U	<25 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U
1,2,3-Trichloropropane	96-18-4	0.04	ug/l	<0.2 U	<2.5 U	<0.2 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<25 U	<25 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U
1,2,4,5-Tetramethylbenzene	95-93-2	5	ug/l	NA	<2 U	NA	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<20 U	<20 U	<2 U	<2 U	<2 U	<2 U
1,2,4-Trichlorobenzene	120-82-1	5	ug/l	<0.2 U	<2.5 U	<0.2 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<25 U	<25 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U
1,2,4-Trimethylbenzene	95-63-6	5	ug/l	<0.2 U	<2.5 U	<0.2 U	<2.5 U	0.8 J	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<25 U	<25 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U
1,2-Dibromo-3-Chloropropane	96-12-8	0.04	ug/l	<0.2 U	<2.5 U	<0.2 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<25 U	<25 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U
1,2-Dibromoethane (Ethylene Dibromide)	106-93-4	0.0006	ug/l	<0.2 U	<2 U	<0.2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<20 U	<20 U	<2 U	<2 U	<2 U	<2 U
1,2-Dichlorobenzene	95-50-1	3	ug/l	<0.2 U	<2.5 U	<0.2 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<25 U	<25 U	1 J	<2.5 U	<2.5 U	<2.5 U
1,2-Dichloroethane	107-06-2	0.6	ug/l	<0.2 U	<0.5 U	<0.2 U	<0.5 U	<0.5 U	<0.5 U	<0.5 U	<0.5 U	<0.5 U	<0.5 U	<5 U	<5 U	<0.5 U	<0.5 U	<0.5 U	<0.5 U
1,2-Dichloropropane	78-87-5	1	ug/l	<0.2 U	<1 U	<0.2 U	<1 U	<1 U	<1 U	<1 U	<1 U	<1 U	<1 U	<10 U	<10 U	<1 U	<1 U	<1 U	<1 U
1,3,5-Trimethylbenzene (Mesitylene)	108-67-8	5	ug/l	<0.2 U	<2.5 U	<0.2 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<25 U	<25 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U
1,3-Dichlorobenzene	541-73-1	3	ug/l	<0.2 U	<2.5 U	<0.2 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<25 U	<25 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U
1,3-Dichloropropane	142-28-9	5	ug/l	<0.2 U	<2.5 U	<0.2 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<25 U	<25 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U
1,4-Dichlorobenzene	106-46-7	3	ug/l	<0.2 UJ	<2.5 U	0.75 J	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<25 U	<25 U	0.98 J	<2.5 U	<2.5 U	<2.5 U
1,4-Diethyl Benzene	105-05-5	NS	ug/l	NA	<2 U	NA	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<20 U	<20 U	<2 U	<2 U	<2 U	<2 U
1,4-Dioxane (P-Dioxane)	123-91-1	0.35	ug/l	<40 UJ	<250 U	<40 UJ	<250 U	<250 U	<250 U	<250 U	<250 U	<250 U	<250 U	<2,500 U	<2,500 U	<250 U	<250 U	<250 U	<250 U
2,2-Dichloropropane	594-20-7	5	ug/l	<0.2 U	<2.5 U	<0.2 UJ	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<25 U	<25 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U
2-Chlorotoluene	95-49-8	5	ug/l	<0.2 U	<2.5 U	0.45 J	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<25 U	<25 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U
2-Hexanone (MBK)	591-78-6	50	ug/l	<0.2 U	<5 U	<0.2 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<50 U	<50 U	<5 U	<5 U	<5 U	<5 U
4-Chlorotoluene	106-43-4	5	ug/l	<0.2 U	<2.5 U	<0.2 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<25 U	<25 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U
4-Ethyltoluene	622-96-8	NS	ug/l	NA	<2 U	NA	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<20 U	<20 U	<2 U	<2 U	<2 U	<2 U
Acetone	67-64-1	50	ug/l	<2.94 U	3.1 J	<2 U	22	<5 U	<5 U	2.2 J	1.8 J	<5 U	<5 U	24 J	17 J	5.7	<5 U	<5 U	<5 U
Acrolein	107-02-8	5	ug/l	<0.2 U	NA	<0.2 U	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
Acrylonitrile	107-13-1	5	ug/l	<0.2 U	<5 U	<0.2 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<50 U	<50 U	<5 U	<5 U	<5 U	<5 U
Benzene	71-43-2	1	ug/l	<0.2 U	<0.5 U	<0.2 U	<0.5 U	<0.5 U	<0.5 U	<0.5 U	<0.5 U	<0.5 U	<0.5 U	<5 U	<5 U	<0.5 U	<0.5 U	<0.5 U	<0.5 U
Bromobenzene	108-86-1	5	ug/l	<0.2 U	<2.5 U	<0.2 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<25 U	<25 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U
Bromochloromethane	74-97-5	5	ug/l	<0.2 U	<2.5 U	<0.2 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<25 U	<25 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U
Bromodichloromethane	75-27-4	50	ug/l	<0.2 U	<0.5 U	<0.2 U	<0.5 U	<0.5 U	<0.5 U	<0.5 U	<0.5 U	<0.5 U	<0.5 U	<5 U	<5 U	<0.5 U	<0.5 U	<0.5 U	<0.5 U
Bromoform	75-25-2	50	ug/l	<0.2 U	<2 U	<0.2 UJ	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<20 U	<20 U	<2 U	<2 U	<2 U	<2 U
Bromomethane	74-83-9	5	ug/l	<0.2 UJ	<2.5 U	<0.2 UJ	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<25 U	<25 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U
Carbon Disulfide	75-15-0	60	ug/l	<0.2 U	<5 U	<0.2 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<50 U	<50 U	<5 U	<5 U	<5 U	<5 U
Carbon Tetrachloride	56-23-5	5	ug/l	<0.2 U	<0.5 U	<0.2 UJ	<0.5 U	<0.5 U	<0.5 U	<0.5 U	<0.5 U	<0.5 U	<0.5 U	<5 U	<5 U	<0.5 U	<0.5 U	<0.5 U	<0.5 U
Chlorobenzene	108-90-7	5	ug/l	<0.2 U	<2.5 U	0.24 J	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<25 U	<25 U	3	1.9 J	<2.5 U	<2.5 U
Chloroethane	75-00-3	5	ug/l	<0.2 U	<2.5 U	<0.2 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<25 U	<25 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U
Chloroform	67-66-3	7	ug/l	<0.2 U	<2.5 U	<0.2 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<25 U	<25 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U
Chloromethane	74-87-3	5	ug/l	<0.2 U	<2.5 U	<0.2 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<25 U	<25 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U
Cis-1,2-Dichloroethene	156-59-2	5	ug/l	<0.2 U	<2.5 U	<0.2 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<25 U	<25 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U
Cis-1,3-Dichloropropene	10061-01-5	0.4	ug/l	<0.2 U	<0.5 U	<0.2 U	<0.5 U	<0.5 U	<0.5 U	<0.5 U	<0.5 U	<0.5 U	<0.5 U	<5 U	<5 U	<0.5 U	<0.5 U	<0.5 U	<0.5 U
Cyclohexane	110-82-7	NS	ug/l	<0.2 U	NA	0.84	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
Cymene	99-87-6	5	ug/l	NA	<2.5 U	NA	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<25 U	<25 U	1.3 J	<2.5 U	<2.5 U	<2.5 U
Dibromochloromethane	124-48-1	50	ug/l	<0.2 U	<0.5 U	<0.2 UJ	<0.5 U	<0.5 U	<0.5 U	<0.5 U	<0.5 U	<0.5 U	<0.5 U	<5 U	<5 U	<0.5 U	<0.5 U	<0.5 U	<0.5 U
Dibromomethane	74-95-3	5	ug/l	<0.2 U	<5 U	<0.2 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<50 U	<50 U	<5 U	<5 U	<5 U	<5 U
Dichlorodifluoromethane	75-71-8	5	ug/l	<0.2 UJ	<5 U	<0.2 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<50 U	<50 U	<5 U	<5 U	<5 U	<5 U
Diethyl Ether (Ethyl Ether)	60-29-7	NS	ug/l	NA	<2.5 U	NA	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<25 U	<25 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U
Ethylbenzene	100-41-4	5	ug/l	<0.2 U	<2.5 U	<0.2 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<25 U	<25 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U
Hexachlorobutadiene	87-68-3	0.5	ug/l	<0.2 UJ	<2.5 U	<0.2 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<25 U	<25 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U
Isopropylbenzene (Cumene)	98-82-8	5	ug/l	<0.2 U	<2.5 U	0.24 J	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<25 U	<25 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U
M,P-Xylene	179601-23-1	5	ug/l	<0.5 U	<2.5 U	<0.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<25 U	<25 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U
Methyl Acetate	79-20-9	NS	ug/l	<0.2 U	NA	<0.2 U	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
Methyl Ethyl Ketone (2-Butanone)	78-93-3	50	ug/l	1.62	<5 U	<0.2 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<50 U	<50 U	<5 U	<5 U	<5 U	<5 U
Methyl Isobutyl Ketone (4-Methyl-2-Pentan	108-10-1	NS	ug/l	<0.2 U	<5 U	<0.2 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<50 U	<50 U	<5 U	<5 U	<5 U	<5 U
Methylcyclohexane	108-87-2	NS	ug/l	<0.2 UJ	NA	1.2	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
Methylene Chloride	75-09-2	5	ug/l	<1 U	<2.5 U	<1 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<25 U	<25 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U
Naphthalene	91-20-3	**10**	ug/l	NA	<2.5 U	NA	<2.5 U	**110**	<2.5 U	<2.5 U	<2.5 U	**44**	<2.5 U	<25 U	<25 U	<2.5 U	<2.5 U	<2.5 U	1.1 J
n-Butylbenzene	104-51-8	5	ug/l	<0.2 U	<2.5 U	0.31 J	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<25 U	<25 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U
n-Propylbenzene	103-65-1	5	ug/l	<0.2 UJ	<2.5 U	<0.2 UJ	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<25 U	<25 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U
o-Xylene (1,2-Dimethylbenzene)	95-47-6	5	ug/l	<0.2 U	<2.5 U	0.39 J	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<25 U	<25 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U
p-Cymene (p-Isopropyltoluene)	CYMP	NS	ug/l	0.54	NA	<0.2 U	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
Sec-Butylbenzene	135-98-8	5	ug/l	<0.2 U	<2.5 U	0.32 J	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<25 U	<25 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U
Styrene	100-42-5	5	ug/l	<0.2 U	<2.5 U	<0.2 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<25 U	<25 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U
T-Butylbenzene	98-06-6	5	ug/l	<0.2 U	<2.5 U	<0.2 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<25 U	<25 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U
Tert-Butyl Alcohol	75-65-0	NS	ug/l	<0.5 U	NA	<0.5 U	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
Tert-Butyl Methyl Ether	1634-04-4	**10**	ug/l	**19.9**	4.3	2.5	1.1 J	<2.5 U	<2.5 U	2 J	1.4 J	<2.5 U	3.1	<25 U	<25 U	<2.5 U	<2.5 U	1.4 J	<2.5 U
Tetrachloroethene (PCE)	127-18-4	5	ug/l	<0.2 U	<0.5 U	<0.2 U	<0.5 U	<0.5 U	<0.5 U	<0.5 U	<0.5 U	<0.5 U	<0.5 U	<5 U	<5 U	<0.5 U	<0.5 U	<0.5 U	<0.5 U
Toluene	108-88-3	5	ug/l	0.23 J	<2.5 U	<0.2 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<25 U	<25 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U
Total 1,2-Dichloroethene (Cis and Trans)	540-59-0	NS	ug/l	NA	<2.5 U	NA	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<25 U	<25 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U
Total Xylenes	1330-20-7	5	ug/l	<0.6 U	<2.5 U	0.62 J	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<25 U	<25 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U
Total, 1,3-Dichloropropene (Cis And Trans)	542-75-6	0.4	ug/l	NA	<0.5 U	NA	<0.5 U	<0.5 U	<0.5 U	<0.5 U	<0.5 U	<0.5 U	<0.5 U	<5 U	<5 U	<0.5 U	<0.5 U	<0.5 U	<0.5 U
Trans-1,2-Dichloroethene	156-60-5	5	ug/l	<0.2 U	<2.5 U	<0.2 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<25 U	<25 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U
Trans-1,3-Dichloropropene	10061-02-6	0.4	ug/l	<0.2 U	<0.5 U	<0.2 U	<0.5 U	<0.5 U	<0.5 U	<0.5 U	<0.5 U	<0.5 U	<0.5 U	<5 U	<5 U	<0.5 U	<0.5 U	<0.5 U	<0.5 U
Trans-1,4-Dichloro-2-Butene	110-57-6	5	ug/l	NA	<2.5 U	NA	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<25 U	<25 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U
Trichloroethene (TCE)	79-01-6	5	ug/l	<0.2 U	<0.5 U	<0.2 U	<0.5 U	<0.5 U	<0.5 U	<0.5 U	<0.5 U	<0.5 U	<0.5 U	<5 U	<5 U	<0.5 U	<0.5 U	<0.5 U	<0.5 U
Trichlorofluoromethane	75-69-4	5	ug/l	<0.2 U	<2.5 U	<0.2 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U	<25 U	<25 U	<2.5 U	<2.5 U	<2.5 U	<2.5 U
Vinyl Acetate	108-05-4	NS	ug/l	NA	<5 U	NA	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<50 U	<50 U	<5 U	<5 U	<5 U	<5 U
Vinyl Chloride	75-01-4	2	ug/l	<0.2 U	<1 U	<0.2 U	<1 U	<1 U	<1 U	<1 U	<1 U	<1 U	<1 U	<10 U	<10 U	<1 U	<1 U	<1 U	<1 U

Table 3
Site Management Plan
Groundwater Sample Analytical Results

12074 Flatlands Avenue p/o Lot 1 Site
Brooklyn, New York
NYSDEC BCP Site No.: C224353
Langan Project No.: 100688803

Analyte	CAS Number	NYSDEC SGVs	Location	LMW-4	LMW-4	LMW-6	LMW-6	LMW-15	LMW-16	LMW-17	LMW-18	LMW-19	LMW-20	LMW-21	LMW-21	LMW-22	LMW-23	LMW-24	LMW-25
			Sample Name	059_LMW-4	LMW-4_030823	055_LMW-6	LMW-6_030723	LMW-15_030723	LMW-16_030723	LMW-17_030723	LMW-18_030723	LMW-19_030723	LMW-20_030823	LMW-21_030823	DUP04_030823	LMW-22_030823	LMW-23_030823	LMW-24_030723	LMW-25_030723
			Sample Date	05/14/2018	03/08/2023	05/14/2018	03/07/2023	03/07/2023	03/07/2023	03/07/2023	03/07/2023	03/07/2023	03/08/2023	03/08/2023	03/08/2023	03/08/2023	03/08/2023	03/07/2023	03/07/2023
			Unit	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result
Semi-Volatile Organic Compounds																			
1,2,4,5-Tetrachlorobenzene	95-94-3	5	ug/l	<2.86 U	<10 U	<2.63 U	<10 U	<10 U	<10 U	<10 U	<10 U	<10 U	<10 U	<10 U	<10 U	<10 U	<10 U	<10 U	<10 U
1,2,4-Trichlorobenzene	120-82-1	5	ug/l	<2.86 U	<5 U	<2.63 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U
1,2-Dichlorobenzene	95-50-1	3	ug/l	<2.86 U	<2 U	<2.63 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	0.49 J	<2 U	<2 U	<2 U
1,2-Diphenylhydrazine	122-66-7	0	ug/l	<2.86 UJ	NA	<2.63 UJ	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
1,3-Dichlorobenzene	541-73-1	3	ug/l	<2.86 U	<2 U	<2.63 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U
1,4-Dichlorobenzene	106-46-7	3	ug/l	<2.86 U	<2 U	<2.63 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	0.44 J	<2 U	<2 U	<2 U
1,4-Dioxane (P-Dioxane)	123-91-1	**0.35**	ug/l	NA	**2.35**	NA	**0.732**	0.0711 J	<0.147 U	**4.3**	**10.4**	0.0431 J	**3.17**	**0.873**	**1.08**	0.306	0.1 J	0.304	<0.147 U
2,3,4,6-Tetrachlorophenol	58-90-2	NS	ug/l	<2.86 U	NA	<2.63 U	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
2,4,5-Trichlorophenol	95-95-4	NS	ug/l	<2.86 U	<5 U	<2.63 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U
2,4,6-Trichlorophenol	88-06-2	NS	ug/l	<2.86 U	<5 U	<2.63 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U
2,4-Dichlorophenol	120-83-2	1	ug/l	<2.86 U	<5 U	<2.63 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U
2,4-Dimethylphenol	105-67-9	1	ug/l	<2.86 U	<5 U	<2.63 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U
2,4-Dinitrophenol	51-28-5	1	ug/l	<2.86 UJ	<20 U	<2.63 UJ	<20 U	<20 U	<20 U	<20 U	<20 U	<20 U	<20 U	<20 U	<20 U	<20 U	<20 U	<20 U	<20 U
2,4-Dinitrotoluene	121-14-2	5	ug/l	<2.86 UJ	<5 U	<2.63 UJ	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U
2,6-Dinitrotoluene	606-20-2	5	ug/l	<2.86 UJ	<5 U	<2.63 UJ	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 UJ	<5 U	<5 U
2-Chloronaphthalene	91-58-7	10	ug/l	<2.86 U	<0.2 U	<2.63 U	<0.2 U	<0.2 U	<0.2 U	<0.2 U	<0.2 U	<0.2 U	<0.2 U	<0.2 U	<0.2 U	<0.2 U	0.02 J	<0.2 U	<0.2 U
2-Chlorophenol	95-57-8	NS	ug/l	<2.86 U	<2 U	<2.63 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U
2-Methylnaphthalene	91-57-6	NS	ug/l	<2.86 U	<0.1 U	<2.63 U	0.04 J	18	<0.1 U	<0.1 U	0.06 J	10	0.04 J	0.06 J	0.04 J	0.1	0.06 J	0.05 J	<0.1 U
2-Methylphenol (o-Cresol)	95-48-7	NS	ug/l	<2.86 U	<5 U	<2.63 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U
2-Nitroaniline	88-74-4	5	ug/l	<2.86 UJ	<5 U	<2.63 UJ	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U
2-Nitrophenol	88-75-5	NS	ug/l	<2.86 UJ	<10 U	<2.63 UJ	<10 U	<10 U	<10 U	<10 U	<10 U	<10 U	<10 U	<10 U	<10 U	<10 U	<10 U	<10 U	<10 U
3 & 4 Methylphenol (m&p Cresol)	65794-96-9	NS	ug/l	6.43	<5 U	<2.63 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	0.88 J	<5 U	<5 U	<5 U	<5 U
3,3'-Dichlorobenzidine	91-94-1	5	ug/l	<2.86 U	<5 UJ	<2.63 U	<5 UJ	<5 UJ	<5 UJ	<5 UJ	<5 UJ	<5 UJ	<5 UJ	<5 UJ	<5 UJ	<5 UJ	<5 UJ	<5 UJ	<5 UJ
3-Nitroaniline	99-09-2	5	ug/l	<2.86 UJ	<5 U	<2.63 UJ	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U
4,6-Dinitro-2-Methylphenol	534-52-1	NS	ug/l	<2.86 UJ	<10 U	<2.63 UJ	<10 U	<10 U	<10 U	<10 U	<10 U	<10 U	<10 U	<10 U	<10 U	<10 U	<10 U	<10 U	<10 U
4-Bromophenyl Phenyl Ether	101-55-3	NS	ug/l	<2.86 U	<2 U	<2.63 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U
4-Chloro-3-Methylphenol	59-50-7	NS	ug/l	<2.86 U	<2 U	<2.63 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U
4-Chloroaniline	106-47-8	5	ug/l	<2.86 U	<5 UJ	<2.63 U	<5 UJ	<5 UJ	<5 UJ	<5 UJ	<5 UJ	<5 UJ	<5 UJ	<5 UJ	<5 UJ	<5 UJ	<5 UJ	<5 UJ	<5 UJ
4-Chlorophenyl Phenyl Ether	7005-72-3	NS	ug/l	<2.86 U	<2 U	<2.63 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U
4-Nitroaniline	100-01-6	5	ug/l	<2.86 UJ	<5 U	<2.63 UJ	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U
4-Nitrophenol	100-02-7	NS	ug/l	<5.71 U	<10 U	<5.26 U	<10 U	<10 U	<10 U	<10 U	<10 U	<10 U	<10 U	<10 U	<10 U	<10 U	<10 U	<10 U	<10 U
Acenaphthene	83-32-9	20	ug/l	0.126	<0.1 U	0.158	0.06 J	4.7	0.02 J	0.7	0.07 J	3.6	1.6	0.18	0.14	1.9	0.14	0.03 J	0.02 J
Acenaphthylene	208-96-8	NS	ug/l	<0.0571 U	<0.1 U	<0.0526 U	<0.1 U	0.19	<0.1 U	0.02 J	<0.1 U	0.13	0.02 J	0.02 J	0.02 J	0.08 J	<0.1 U	<0.1 U	<0.1 U
Acetophenone	98-86-2	NS	ug/l	<2.86 U	<5 U	<2.63 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U
Aniline (Phenylamine, Aminobenzene)	62-53-3	5	ug/l	<2.86 U	NA	<2.63 U	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
Anthracene	120-12-7	50	ug/l	0.08	<0.1 U	0.0632	0.03 J	1.3	<0.1 U	0.06 J	0.03 J	0.44	0.08 J	0.06 J	0.09 J	0.48	0.04 J	0.03 J	<0.1 U
Atrazine	1912-24-9	7.5	ug/l	<0.571 UJ	NA	<0.526 UJ	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
Benzaldehyde	100-52-7	NS	ug/l	<2.86 U	NA	<2.63 U	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
Benzidine	92-87-5	5	ug/l	<5.71 UJ	NA	<5.26 UJ	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
Benzo(a)anthracene	56-55-3	**0.002**	ug/l	<0.0571 U	<0.1 U	<0.0526 U	<0.1 U	**0.17 J**	<0.1 U	<0.1 U	<0.1 U	<0.1 U	<0.1 U	<0.1 U	<0.1 U	**0.13 J**	<0.1 U	<0.1 U	<0.1 U
Benzo(a)pyrene	50-32-8	**0**	ug/l	<0.0571 UJ	<0.1 U	<0.0526 UJ	<0.1 U	**0.13 J**	<0.1 U	<0.1 U	<0.1 U	<0.1 U	<0.1 U	<0.1 U	<0.1 U	**0.1 J**	<0.1 U	<0.1 U	<0.1 U
Benzo(b)fluoranthene	205-99-2	**0.002**	ug/l	<0.0571 U	<0.1 U	<0.0526 U	<0.1 U	**0.11 J**	<0.1 U	<0.1 U	<0.1 U	<0.1 U	<0.1 U	<0.1 U	<0.1 U	**0.12 J**	<0.1 U	<0.1 U	<0.1 U
Benzo(g,h,i)Perylene	191-24-2	NS	ug/l	<0.0571 U	<0.1 U	<0.0526 U	<0.1 U	0.07 J	<0.1 U	<0.1 U	<0.1 U	<0.1 U	<0.1 U	0.05 J	0.04 J	0.07 J	0.03 J	<0.1 U	<0.1 U
Benzo(k)fluoranthene	207-08-9	0.002	ug/l	<0.0571 U	<0.1 U	<0.0526 U	<0.1 U	<0.1 U	<0.1 U	<0.1 U	<0.1 U	<0.1 U	<0.1 U	<0.1 U	<0.1 U	<0.1 U	<0.1 U	<0.1 U	<0.1 U
Benzoic Acid	65-85-0	NS	ug/l	<28.6 UJ	<50 U	<26.3 UJ	6.5 J	6.8 J	6.3 J	6.7 J	7.4 J	<50 U	<50 U	7.5 J	9.3 J	<50 U	<50 U	6.5 J	6.4 J
Benzyl Alcohol	100-51-6	NS	ug/l	<2.86 U	<2 U	<2.63 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U
Benzyl Butyl Phthalate	85-68-7	50	ug/l	<2.86 U	<5 U	<2.63 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U
Biphenyl (Diphenyl)	92-52-4	5	ug/l	<2.86 U	<2 U	<2.63 U	<2 U	0.66 J	<2 U	<2 U	<2 U	0.75 J	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U
Bis(2-chloroethoxy) methane	111-91-1	5	ug/l	<2.86 U	<5 U	<2.63 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U
Bis(2-chloroethyl) ether (2-chloroethyl ether	111-44-4	1	ug/l	<1.14 U	<2 U	<1.05 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U
Bis(2-chloroisopropyl) ether	108-60-1	5	ug/l	<2.86 UJ	<2 U	<2.63 UJ	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U
Bis(2-ethylhexyl) phthalate	117-81-7	5	ug/l	<0.571 U	<3 U	<0.526 U	1.9 J	<3 U	<3 U	<3 U	1.6 J	<3 U	<3 U	<3 U	<3 U	<3 U	2 J	<3 U	<3 U
Caprolactam	105-60-2	NS	ug/l	<2.86 U	NA	<2.63 U	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
Carbazole	86-74-8	NS	ug/l	<2.86 U	<2 U	<2.63 U	<2 U	0.58 J	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U
Chrysene	218-01-9	**0.002**	ug/l	<0.0571 U	<0.1 U	<0.0526 U	<0.1 U	**0.18 J**	<0.1 U	<0.1 U	<0.1 U	<0.1 U	<0.1 U	<0.1 U	<0.1 U	**0.11 J**	<0.1 U	<0.1 U	<0.1 U
Dibenz(a,h)anthracene	53-70-3	NS	ug/l	<0.0571 U	<0.1 U	<0.0526 U	<0.1 U	<0.1 U	<0.1 U	<0.1 U	<0.1 U	<0.1 U	<0.1 U	0.02 J	<0.1 U	<0.1 U	<0.1 U	<0.1 U	<0.1 U
Dibenzofuran	132-64-9	NS	ug/l	<2.86 U	<2 U	<2.63 U	<2 U	0.67 J	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U
Dibutyl phthalate	84-74-2	50	ug/l	<2.86 U	<5 U	<2.63 U	<5 U	<5 U	<5 U	0.95 J	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U
Diethyl phthalate	84-66-2	50	ug/l	<2.86 U	<5 U	<2.63 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U
Dimethyl phthalate	131-11-3	50	ug/l	<2.86 U	<5 U	<2.63 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U
Dioctyl phthalate	117-84-0	50	ug/l	<2.86 U	<5 U	<2.63 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U
Fluoranthene	206-44-0	50	ug/l	0.194	<0.1 U	0.0632	0.04 J	1.3	0.03 J	0.06 J	0.04 J	0.31	0.12	0.17	0.13	0.58	0.06 J	0.03 J	<0.1 U
Fluorene	86-73-7	50	ug/l	0.286	<0.1 U	0.284	0.07 J	5.1	<0.1 U	0.22	0.04 J	2.7	0.72	0.16	0.11	1.7	0.1 J	0.03 J	<0.1 U
Hexachlorobenzene	118-74-1	0.04	ug/l	<0.0229 UJ	<0.8 U	<0.0211 UJ	<0.8 U	<0.8 U	<0.8 U	<0.8 U	<0.8 U	<0.8 U	<0.8 U	<0.8 U	<0.8 U	<0.8 U	<0.8 U	<0.8 U	<0.8 U
Hexachlorobutadiene	87-68-3	0.5	ug/l	<0.571 U	<0.5 U	<0.526 U	<0.5 U	<0.5 U	<0.5 U	<0.5 U	<0.5 U	<0.5 U	<0.5 U	<0.5 U	<0.5 U	<0.5 U	<0.5 U	<0.5 U	<0.5 U
Hexachlorocyclopentadiene	77-47-4	5	ug/l	<5.71 UJ	<20 UJ	<5.26 UJ	<20 UJ	<20 UJ	<20 UJ	<20 UJ	<20 UJ	<20 UJ	<20 UJ	<20 UJ	<20 UJ	<20 UJ	<20 UJ	<20 UJ	<20 UJ
Hexachloroethane	67-72-1	5	ug/l	<0.571 UJ	<0.8 U	<0.526 UJ	<0.8 U	<0.8 U	<0.8 U	<0.8 U	<0.8 U	<0.8 U	<0.8 U	<0.8 U	<0.8 U	<0.8 U	<0.8 U	<0.8 U	<0.8 U
Indeno(1,2,3-cd)pyrene	193-39-5	**0.002**	ug/l	<0.0571 U	<0.1 U	<0.0526 U	<0.1 U	**0.07 J**	<0.1 U	<0.1 U	<0.1 U	<0.1 U	<0.1 U	**0.06 J**	**0.04 J**	**0.07 J**	**0.03 J**	<0.1 U	<0.1 U
Isophorone	78-59-1	50	ug/l	<2.86 U	<5 U	<2.63 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U
Naphthalene	91-20-3	**10**	ug/l	0.206	<0.1 U	0.305	0.06 J	**28**	<0.1 U	<0.1 U	0.09 J	9.3	0.06 J	0.21	0.14	0.37	0.27	0.13	<0.1 U
Nitrobenzene	98-95-3	0.4	ug/l	<0.286 U	<2 U	<0.263 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U
n-Nitrosodimethylamine	62-75-9	NS	ug/l	<0.571 UJ	NA	<0.526 UJ	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
n-Nitrosodi-N-Propylamine	621-64-7	NS	ug/l	<2.86 U	<5 U	<2.63 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U
n-Nitrosodiphenylamine	86-30-6	50	ug/l	<2.86 U	<2 U	<2.63 U	<2 U	<2 U	<2 U	0.48 J	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U
Pentachlorophenol	87-86-5	1	ug/l	<0.286 UJ	<0.8 U	<0.263 UJ	0.15 J	<0.8 U	<0.8 U	<0.8 U	<0.8 U	0.11 J	<0.8 U	<0.8 U	<0.8 U	<0.8 U	<0.8 U	<0.8 U	<0.8 U
Phenanthrene	85-01-8	50	ug/l	0.389	<0.1 U	0.358	0.04 J	6.9	0.03 J	0.09 J	0.08 J	1.5	0.43	0.19	0.17	1.2	0.11	0.09 J	<0.1 U
Phenol	108-95-2	1	ug/l	<2.86 U	<5 U	<2.63 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U
Pyrene	129-00-0	50	ug/l	0.103	<0.1 U	<0.0526 U	<0.1 U	1.6	<0.1 U	<0.1 U	<0.1 U	0.32 J	<0.1 U	0.14 J	0.1 J	0.42 J	<0.1 U	<0.1 U	<0.1 U
Pyridine	110-86-1	50	ug/l	<2.86 UJ	NA	<2.63 UJ	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA

Table 3
Site Management Plan
Groundwater Sample Analytical Results

12074 Flatlands Avenue p/o Lot 1 Site
Brooklyn, New York
NYSDEC BCP Site No.: C224353
Langan Project No.: 100688803

Analyte	CAS Number	NYSDEC SGVs	Location	LMW-4	LMW-4	LMW-6	LMW-6	LMW-15	LMW-16	LMW-17	LMW-18	LMW-19	LMW-20	LMW-21	LMW-21	LMW-22	LMW-23	LMW-24	LMW-25
			Sample Name	059_LMW-4	LMW-4_030823	055_LMW-6	LMW-6_030723	LMW-15_030723	LMW-16_030723	LMW-17_030723	LMW-18_030723	LMW-19_030723	LMW-20_030823	LMW-21_030823	DUP04_030823	LMW-22_030823	LMW-23_030823	LMW-24_030723	LMW-25_030723
			Sample Date	05/14/2018	03/08/2023	05/14/2018	03/07/2023	03/07/2023	03/07/2023	03/07/2023	03/07/2023	03/07/2023	03/08/2023	03/08/2023	03/08/2023	03/08/2023	03/08/2023	03/07/2023	03/07/2023
			Unit	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result
Pesticides																			
4,4'-DDD	72-54-8	0.3	ug/l	<0.00457 U	<0.029 U	<0.00444 U	<0.029 U	<0.029 U	<0.029 U	<0.029 U	<0.029 U	<0.029 U	<0.029 U	<0.029 U	<0.029 U	0.007 J	<0.029 U	<0.029 U	<0.029 U
4,4'-DDE	72-55-9	0.2	ug/l	<0.00457 U	<0.029 U	<0.00444 U	<0.029 U	<0.029 U	<0.029 U	<0.029 U	<0.029 U	<0.029 U	<0.029 U	<0.029 U	<0.029 U	<0.029 U	<0.029 U	<0.029 U	<0.029 U
4,4'-DDT	50-29-3	0.2	ug/l	<0.00457 U	<0.029 U	<0.00444 U	<0.029 U	<0.029 U	<0.029 U	<0.029 U	<0.029 U	<0.029 U	<0.029 U	<0.029 U	<0.029 U	<0.029 U	0.041	<0.029 U	<0.029 U
Aldrin	309-00-2	0	ug/l	<0.00457 U	<0.014 U	<0.00444 U	<0.014 U	<0.014 U	<0.014 U	<0.014 U	<0.014 U	<0.014 U	<0.014 U	<0.014 U	<0.014 U	<0.014 U	<0.014 U	<0.014 U	<0.014 U
Alpha BHC (Alpha Hexachlorocyclohexane)	319-84-6	0.01	ug/l	<0.00457 U	<0.014 U	<0.00444 U	<0.014 U	<0.014 U	<0.014 U	<0.014 U	<0.014 U	<0.014 U	<0.014 U	<0.014 U	<0.014 U	<0.014 U	<0.014 U	<0.014 U	<0.014 U
Alpha Chlordane	5103-71-9	NS	ug/l	<0.00457 U	<0.014 U	<0.00444 U	<0.014 U	<0.014 U	<0.014 U	<0.014 U	<0.014 U	<0.014 U	<0.014 U	<0.014 U	<0.014 U	<0.014 U	<0.014 U	<0.014 U	<0.014 U
Alpha Endosulfan	959-98-8	NS	ug/l	<0.00457 U	<0.014 U	<0.00444 U	<0.014 U	<0.014 U	<0.014 U	<0.014 U	<0.014 U	<0.014 U	<0.014 U	<0.014 U	<0.014 U	<0.014 U	<0.014 U	<0.014 U	<0.014 U
Beta Bhc (Beta Hexachlorocyclohexane)	319-85-7	0.04	ug/l	<0.00457 U	<0.014 U	<0.00444 U	<0.014 U	<0.014 U	<0.014 U	<0.014 U	<0.014 U	<0.014 U	<0.014 U	<0.014 U	<0.014 U	<0.014 U	<0.014 U	<0.014 U	<0.014 U
Beta Endosulfan	33213-65-9	NS	ug/l	<0.00457 U	<0.029 U	<0.00444 U	<0.029 U	<0.029 U	<0.029 U	<0.029 U	<0.029 U	<0.029 U	<0.029 U	<0.029 U	<0.029 U	<0.029 U	<0.029 U	<0.029 U	<0.029 U
Chlordane (alpha and gamma)	57-74-9	0.05	ug/l	<0.0229 U	<0.143 U	<0.0222 U	<0.143 U	<0.143 U	<0.143 U	<0.143 U	<0.143 U	<0.143 U	<0.143 U	<0.143 U	<0.143 U	<0.143 U	<0.143 U	<0.143 U	<0.143 U
Delta Bhc (Delta Hexachlorocyclohexane)	319-86-8	0.04	ug/l	<0.00457 U	<0.014 U	<0.00444 U	<0.014 U	<0.014 U	<0.014 U	<0.014 U	<0.014 U	<0.014 U	<0.014 U	<0.014 U	<0.014 U	<0.014 U	<0.014 U	<0.014 U	<0.014 U
Dieldrin	60-57-1	0.004	ug/l	<0.00229 U	<0.029 U	<0.00222 U	<0.029 U	<0.029 U	<0.029 U	<0.029 U	<0.029 U	<0.029 U	<0.029 U	<0.029 U	<0.029 U	<0.029 U	<0.029 U	<0.029 U	<0.029 U
Endosulfan Sulfate	1031-07-8	NS	ug/l	<0.00457 U	<0.029 U	<0.00444 U	<0.029 U	<0.029 U	<0.029 U	<0.029 U	<0.029 U	<0.029 U	<0.029 U	<0.029 U	<0.029 U	<0.029 U	<0.029 U	<0.029 U	<0.029 U
Endrin	72-20-8	0	ug/l	<0.00457 U	<0.029 U	<0.00444 U	<0.029 U	<0.029 U	<0.029 U	<0.029 U	<0.029 U	<0.029 U	<0.029 U	<0.029 U	<0.029 U	<0.029 U	<0.029 U	<0.029 U	<0.029 U
Endrin Aldehyde	7421-93-4	5	ug/l	<0.0114 U	<0.029 U	<0.0111 U	<0.029 U	<0.029 U	<0.029 U	<0.029 U	<0.029 U	<0.029 U	<0.029 U	<0.029 U	<0.029 U	<0.029 U	<0.029 U	<0.029 U	<0.029 U
Endrin Ketone	53494-70-5	5	ug/l	<0.0114 U	<0.029 U	<0.0111 U	<0.029 U	<0.029 U	<0.029 U	<0.029 U	<0.029 U	<0.029 U	<0.029 U	<0.029 U	<0.029 U	<0.029 U	<0.029 U	<0.029 U	<0.029 U
Gamma Bhc (Lindane)	58-89-9	0.05	ug/l	<0.00457 U	<0.014 U	<0.00444 U	<0.014 U	<0.014 U	<0.014 U	<0.014 U	<0.014 U	<0.014 U	<0.014 U	<0.014 U	<0.014 U	<0.014 U	<0.014 U	<0.014 U	<0.014 U
Gamma Chlordane (Trans)	5103-74-2	NS	ug/l	NA	<0.014 U	NA	<0.014 U	<0.014 U	<0.014 U	<0.014 U	<0.014 U	<0.014 U	<0.014 U	<0.014 U	<0.014 U	<0.014 U	<0.014 U	<0.014 U	<0.014 U
Gamma-Chlordane	5566-34-7	NS	ug/l	<0.0114 U	NA	<0.0111 U	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
Heptachlor	76-44-8	0.04	ug/l	<0.00457 U	<0.014 U	<0.00444 U	<0.014 U	<0.014 U	<0.014 U	<0.014 U	<0.014 U	<0.014 U	<0.014 U	<0.014 U	<0.014 U	<0.014 U	<0.014 U	<0.014 U	<0.014 U
Heptachlor Epoxide	1024-57-3	0.03	ug/l	<0.00457 U	<0.014 U	<0.00444 U	<0.014 U	<0.014 U	<0.014 U	<0.014 U	<0.014 U	<0.014 U	<0.014 U	<0.014 U	<0.014 U	<0.014 U	<0.014 U	<0.014 U	<0.014 U
Methoxychlor	72-43-5	35	ug/l	<0.00457 U	<0.143 U	<0.00444 U	<0.143 U	<0.143 U	<0.143 U	<0.143 U	<0.143 U	<0.143 U	<0.143 U	<0.143 U	<0.143 U	<0.143 U	<0.143 U	<0.143 U	<0.143 U
Toxaphene	8001-35-2	0.06	ug/l	<0.114 U	<0.143 U	<0.111 U	<0.143 U	<0.143 U	<0.143 U	<0.143 U	<0.143 U	<0.143 U	<0.143 U	<0.143 U	<0.143 U	<0.143 U	<0.143 U	<0.143 U	<0.143 U
Herbicides																			
2,4,5-T (Trichlorophenoxyacetic Acid)	93-76-5	35	ug/l	NA	<2 U	NA	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U
2,4-D (Dichlorophenoxyacetic Acid)	94-75-7	50	ug/l	NA	<10 U	NA	<10 U	<10 U	<10 U	<10 U	<10 U	<10 U	<10 U	<10 U	<10 U	<10 U	<10 U	<10 U	<10 U
Silvex (2,4,5-Tp)	93-72-1	0.26	ug/l	NA	<2 U	NA	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U	<2 U
Polychlorinated Biphenyl																			
PCB-1016 (Aroclor 1016)	12674-11-2	NS	ug/l	<0.0571 UJ	<0.071 U	<0.0556 UJ	<0.071 U	<0.071 U	<0.071 U	<0.071 U	<0.071 U	<0.071 U	<0.071 U	<0.071 U	<0.071 U	<0.071 U	<0.071 U	<0.071 U	<0.071 U
PCB-1221 (Aroclor 1221)	11104-28-2	NS	ug/l	<0.0571 UJ	<0.071 U	<0.0556 UJ	<0.071 U	<0.071 U	<0.071 U	<0.071 U	<0.071 U	<0.071 U	<0.071 U	<0.071 U	<0.071 U	<0.071 U	<0.071 U	<0.071 U	<0.071 U
PCB-1232 (Aroclor 1232)	11141-16-5	NS	ug/l	<0.0571 UJ	<0.071 U	<0.0556 UJ	<0.071 U	<0.071 U	<0.071 U	<0.071 U	<0.071 U	<0.071 U	<0.071 U	<0.071 U	<0.071 U	<0.071 U	<0.071 U	<0.071 U	<0.071 U
PCB-1242 (Aroclor 1242)	53469-21-9	NS	ug/l	<0.0571 UJ	<0.071 U	<0.0556 UJ	<0.071 U	<0.071 U	<0.071 U	<0.071 U	<0.071 U	<0.071 U	<0.071 U	<0.071 U	<0.071 U	<0.071 U	<0.071 U	<0.071 U	<0.071 U
PCB-1248 (Aroclor 1248)	12672-29-6	NS	ug/l	<0.0571 UJ	<0.071 U	<0.0556 UJ	<0.071 U	<0.071 U	<0.071 U	<0.071 U	<0.071 U	<0.071 U	<0.071 U	<0.071 U	<0.071 U	<0.071 U	<0.071 U	<0.071 U	<0.071 U
PCB-1254 (Aroclor 1254)	11097-69-1	NS	ug/l	<0.0571 UJ	<0.071 U	0.341 J	<0.071 U	<0.071 U	<0.071 U	<0.071 U	<0.071 U	<0.071 U	<0.071 U	<0.071 U	<0.071 U	<0.071 U	<0.071 U	<0.071 U	<0.071 U
PCB-1260 (Aroclor 1260)	11096-82-5	NS	ug/l	<0.0571 UJ	<0.071 U	<0.0556 UJ	0.074	<0.071 U	<0.071 U	<0.071 U	<0.071 U	<0.071 U	<0.071 U	<0.071 U	<0.071 U	<0.071 U	<0.071 U	<0.071 U	<0.071 U
PCB-1262 (Aroclor 1262)	37324-23-5	NS	ug/l	NA	<0.071 U	NA	<0.071 U	<0.071 U	<0.071 U	<0.071 U	<0.071 U	<0.071 U	<0.071 U	<0.071 U	<0.071 U	<0.071 U	<0.071 U	<0.071 U	<0.071 U
PCB-1268 (Aroclor 1268)	11100-14-4	NS	ug/l	NA	<0.071 U	NA	<0.071 U	<0.071 U	<0.071 U	<0.071 U	<0.071 U	<0.071 U	<0.071 U	<0.071 U	<0.071 U	<0.071 U	<0.071 U	<0.071 U	<0.071 U
Total PCBs	1336-36-3	**0.09**	ug/l	<0.0571 UJ	<0.071 U	**0.341 J**	0.074	<0.071 U	<0.071 U	<0.071 U	<0.071 U	<0.071 U	<0.071 U	<0.071 U	<0.071 U	<0.071 U	<0.071 U	<0.071 U	<0.071 U
Metals - Dissolved																			
Aluminum	7429-90-5	NS	ug/l	<55.6 U	<10 U	<55.6 U	<10 U	<10 U	<10 U	<10 U	4.36 J	<10 U	5.76 J	14	5.43 J	<10 U	<10 U	<10 U	16.5
Antimony	7440-36-0	3	ug/l	<1.11 UJ	<4 U	<1.11 UJ	<4 U	<4 U	<4 U	<4 U	<4 U	<4 U	<4 U	0.48 J	<4 U	0.73 J	<4 U	<4 U	0.46 J
Arsenic	7440-38-2	25	ug/l	4.55	0.58	<1.11 U	0.55	0.22 J	0.17 J	0.2 J	0.9	0.76	0.35 J	1.16	1.21	0.39 J	0.53	0.57	1.06
Barium	7440-39-3	**1000**	ug/l	450	466.6	299	386.7	87.12	286.1	**1,080**	284.9	215	503.2	273	310	727.2	356.1	281.7	57.4
Beryllium	7440-41-7	3	ug/l	<1.11 UJ	<0.5 U	<1.11 UJ	<0.5 U	<0.5 U	<0.5 U	<0.5 U	<0.5 U	<0.5 U	<0.5 U	<0.5 U	<0.5 U	<0.5 U	<0.5 U	<0.5 U	<0.5 U
Cadmium	7440-43-9	5	ug/l	<1.11 U	<0.2 U	<1.11 U	<0.2 U	<0.2 U	<0.2 U	<0.2 U	<0.2 U	<0.2 U	<0.2 U	<0.2 U	<0.2 U	<0.2 U	<0.2 U	<0.2 U	0.07 J
Calcium	7440-70-2	NS	ug/l	156,000	103,000	135,000	142,000	162,000	71,500	117,000	105,000	70,000	128,000	248,000	237,000	165,000	139,000	81,500	117,000
Chromium, Total	7440-47-3	50	ug/l	<5.56 U	0.27 J	<5.56 U	0.3 J	0.22 J	<1 U	0.36 J	0.32 J	0.38 J	0.54 J	0.45 J	0.49 J	0.46 J	0.42 J	<1 U	0.34 J
Cobalt	7440-48-4	NS	ug/l	<5.56 U	1.05	<5.56 U	0.82	0.34 J	0.16 J	0.76	0.97	1.25	1.11	0.89	1.01	0.55	1.08	0.5	1.59
Copper	7440-50-8	200	ug/l	<5.56 U	<1 U	<5.56 U	0.89 J	<1 U	<1 U	<1 U	<1 U	<1 U	<1 U	<1 U	<1 U	1.71	<1 U	<1 U	0.67 J
Iron	7439-89-6	**300**	ug/l	**2,940**	**22,300**	**9,800**	**18,700**	**19,100**	**4,960**	**7,440**	**14,700**	**1,540**	**7,920**	**10,400**	**12,200**	**2,870**	**16,200**	**10,300**	**12,200**
Lead	7439-92-1	25	ug/l	<5.56 U	<1 U	<5.56 U	<1 U	<1 U	<1 U	<1 U	<1 U	<1 U	<1 U	1.16	<1 U	<1 U	<1 U	<1 U	<1 U
Magnesium	7439-95-4	**35000**	ug/l	21,200	10,800	13,800	15,000	12,200	3,150	20,100	15,400	11,000	26,000	**59,500**	**59,600**	25,000	21,300	7,210	4,720
Manganese	7439-96-5	**300**	ug/l	**309**	150.9	**513**	**315.6**	**2,326**	**609**	92.73	159.7	197.3	174.7	**544.5**	**538.1**	**391.1**	**346.6**	151.4	**981.2**
Mercury	7439-97-6	0.7	ug/l	<0.2 U	<0.2 U	<0.2 U	<0.2 U	<0.2 U	<0.2 U	<0.2 U	<0.2 U	<0.2 U	0.11 J	<0.2 U	<0.2 U	<0.2 U	<0.2 U	<0.2 U	<0.2 U
Nickel	7440-02-0	100	ug/l	<5.56 U	0.81 J	<5.56 U	0.65 J	<2 U	<2 U	0.84 J	1.13 J	<2 U	0.55 J	1.11 J	1.42 J	2.42	0.62 J	0.82 J	12.07
Potassium	7440-09-7	NS	ug/l	20,800	12,900	13,300	12,400	16,000	2,040	18,600	9,840	12,100	19,700	28,700	28,800	15,400	18,800	7,780	8,360
Selenium	7782-49-2	**10**	ug/l	**14.6**	<5 U	1.86	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U
Silver	7440-22-4	50	ug/l	<5.56 U	<0.4 U	<5.56 U	<0.4 U	<0.4 U	<0.4 U	<0.4 U	<0.4 U	<0.4 U	<0.4 U	<0.4 U	<0.4 U	<0.4 U	<0.4 U	<0.4 U	<0.4 U
Sodium	7440-23-5	**20000**	ug/l	**123,000**	**57,800**	**87,800**	**58,200**	**77,800**	9,870	**81,000**	**57,800**	**34,500**	**115,000**	**62,000**	**63,500**	**56,400**	**61,000**	**45,800**	**64,200**
Thallium	7440-28-0	0.5	ug/l	<1.11 U	<1 U	<1.11 U	<1 U	<1 U	<1 U	<1 U	<1 U	0.2 J	<1 U	<1 U	<1 U	<1 U	<1 U	<1 U	<1 U
Vanadium	7440-62-2	NS	ug/l	<11.1 U	<5 U	<11.1 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U
Zinc	7440-66-6	2000	ug/l	18.1	<10 U	<16.7 U	<10 U	<10 U	<10 U	12.53	8.5 J	<10 U	<10 U	<10 U	<10 U	<10 U	<10 U	<10 U	208.9

Table 3
Site Management Plan
Groundwater Sample Analytical Results

12074 Flatlands Avenue p/o Lot 1 Site
Brooklyn, New York
NYSDEC BCP Site No.: C224353
Langan Project No.: 100688803

Analyte	CAS Number	NYSDEC SGVs	Location	LMW-4	LMW-4	LMW-6	LMW-6	LMW-15	LMW-16	LMW-17	LMW-18	LMW-19	LMW-20	LMW-21	LMW-21	LMW-22	LMW-23	LMW-24	LMW-25
			Sample Name	059_LMW-4	LMW-4_030823	055_LMW-6	LMW-6_030723	LMW-15_030723	LMW-16_030723	LMW-17_030723	LMW-18_030723	LMW-19_030723	LMW-20_030823	LMW-21_030823	DUP04_030823	LMW-22_030823	LMW-23_030823	LMW-24_030723	LMW-25_030723
			Sample Date	05/14/2018	03/08/2023	05/14/2018	03/07/2023	03/07/2023	03/07/2023	03/07/2023	03/07/2023	03/07/2023	03/08/2023	03/08/2023	03/08/2023	03/08/2023	03/08/2023	03/07/2023	03/07/2023
			Unit	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result	Result
Metals - Total																			
Aluminum	7429-90-5	NS	ug/l	232	38.3	600	28	589	17.8	12.4	21.7	33.1	16.3	1,260 J	2,330 J	345	35.3	64.6	30.4
Antimony	7440-36-0	3	ug/l	<1.11 UJ	<4 U	<1.11 UJ	0.52 J	<4 U	<4 U	<4 U	<4 U	0.46 J	0.58 J	0.9 J	1.19 J	0.61 J	<4 U	<4 U	<4 U
Arsenic	7440-38-2	25	ug/l	9.57	1.75	<1.11 U	2.06	0.71	0.46 J	0.42 J	1.89	2.3	0.4 J	4.08	5.43	1.45	1.07	3.61	1.96
Barium	7440-39-3	**1000**	ug/l	81.4	667.7	388	605.9	107.3	340.4	**1,652**	381.2	286.9	676.5	465.8	585.7	844	511.5	436.8	63.14
Beryllium	7440-41-7	3	ug/l	<1.11 U	<0.5 U	<1.11 U	<0.5 U	<0.5 U	<0.5 U	<0.5 U	<0.5 U	<0.5 U	<0.5 U	<0.5 U	0.16 J	<0.5 U	<0.5 U	<0.5 U	<0.5 U
Cadmium	7440-43-9	5	ug/l	<1.11 U	0.09 J	<1.11 U	<0.2 U	<0.2 U	<0.2 U	<0.2 U	<0.2 U	<0.2 U	<0.2 U	0.27 J	0.47 J	0.06 J	<0.2 U	<0.2 U	0.13 J
Calcium	7440-70-2	NS	ug/l	82,500 J	108,000	102,000 J	150,000	175,000	75,100	126,000	109,000	74,400	130,000	257,000	239,000	170,000	144,000	89,000	124,000
Chromium, Hexavalent	18540-29-9	50	ug/l	<10 UJ	<10 U	<10 UJ	<10 U	<10 U	<10 U	<10 U	<10 U	<10 U	<10 U	<10 U	<10 U	<10 U	<10 U	<10 U	<10 U
Chromium, Total	7440-47-3	NS	ug/l	<5.56 U	0.87 J	<5.56 U	0.72 J	2.23	0.55 J	0.68 J	0.79 J	0.68 J	1.16	4.99 J	8.69 J	3.03	0.99 J	0.63 J	0.61 J
Chromium, Trivalent	16065-83-1	NS	ug/l	<10 U	<10 U	<10 U	<10 U	<10 U	<10 U	<10 U	<10 U	<10 U	<10 U	<10 U	<10 U	<10 U	<10 U	<10 U	<10 U
Cobalt	7440-48-4	NS	ug/l	6.15	1.42	<5.56 U	1.12	0.71	0.16 J	1.11	1.28	1.58	1.43	1.67 J	2.57 J	0.76	1.36	0.76	1.72
Copper	7440-50-8	200	ug/l	<5.56 U	1.7	12.5	0.78 J	1.76	0.9 J	0.78 J	0.94 J	0.57 J	0.67 J	18.31 J	33.99 J	2.9	0.95 J	2.11	0.64 J
Cyanide	57-12-5	200	ug/l	NA	<5 U	NA	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	6 J	<5 U	<5 U	<5 U	<5 U	<5 U
Iron	7439-89-6	**300**	ug/l	**532**	**39,400**	**34,400**	**44,300**	**31,900**	**11,400**	**29,600**	**26,700**	**13,000**	**21,600**	**30,300**	**34,400**	**12,300**	**33,300**	**33,000**	**16,000**
Lead	7439-92-1	**25**	ug/l	<5.56 U	10.05	**117**	4.26	2.4	0.59 J	2.1	4.34	2.71	1.28	**122.7 J**	**282.4 J**	**26.71**	8.06	14.84	0.78 J
Magnesium	7439-95-4	**35000**	ug/l	7,610	11,400	10,000	15,000	12,600	3,240	21,100	15,100	11,500	22,900	**54,500**	**53,500**	22,100	21,100	7,420	4,820
Manganese	7439-96-5	**300**	ug/l	**439**	163.9	**877**	**331.3**	**2,506**	**649.7**	101	165.9	211.2	183.1	**619.5**	**656**	**427**	**386.2**	165.4	**1,072**
Mercury	7439-97-6	0.7	ug/l	<0.2 U	<0.2 U	<0.2 U	0.1 J	0.14 J	0.15 J	0.15 J	0.1 J	0.11 J	<0.2 U	0.19 J	0.3	<0.2 U	<0.2 U	0.23	<0.2 U
Nickel	7440-02-0	100	ug/l	<5.56 U	0.93 J	<5.56 U	0.76 J	1.5 J	<2 U	1.11 J	1.39 J	0.65 J	<2 U	3.7 J	6.33 J	2.67	1.22 J	1.17 J	12.73
Potassium	7440-09-7	NS	ug/l	10,600	13,300	18,100	12,800	16,900	2,010	19,700	9,870	12,900	19,900	28,800	28,600	15,100	19,300	8,290	8,730
Selenium	7782-49-2	**10**	ug/l	**20.9**	<5 U	3.72 J	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U
Silver	7440-22-4	50	ug/l	<5.56 UJ	<0.4 U	<5.56 UJ	<0.4 U	<0.4 U	<0.4 U	<0.4 U	<0.4 U	<0.4 U	<0.4 U	<0.4 U	0.22 J	<0.4 U	<0.4 U	<0.4 U	<0.4 U
Sodium	7440-23-5	**20000**	ug/l	**76,100 J**	**52,800**	**181,000 J**	**60,000**	**81,000**	10,300	**87,200**	**59,100**	**36,200**	**105,000**	**57,300**	**59,800**	**50,400**	**58,000**	**48,600**	**68,400**
Thallium	7440-28-0	0.5	ug/l	<1.11 UJ	<1 U	<1.11 UJ	0.18 J	<1 U	<1 U	<1 U	<1 U	<1 U	0.15 J	<1 U	<1 U	<1 U	<1 U	<1 U	<1 U
Vanadium	7440-62-2	NS	ug/l	<11.1 U	<5 U	<11.1 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	<5 U	4.83 J	9.57	1.94 J	<5 U	<5 U	<5 U
Zinc	7440-66-6	2000	ug/l	<16.7 U	5.12 J	230	9.92 J	5.28 J	<10 U	64.03	15.29	<10 U	<10 U	63.44 J	131.3 J	25.04	7.52 J	13.15	216.8
Perfluorooctanoic acids																			
11-Chloroeicosafluoro-3-Oxaundecane-1-Su	763051-92-9	NS	ug/l	NA	<0.00599 U	NA	<0.00634 U	<0.00627 U	<0.00604 U	<0.006 U	<0.00609 U	<0.00623 U	<0.00638 U	<0.00635 U	<0.00619 U	<0.00611 U	<0.00602 U	<0.00621 U	<0.006 U
1H,1H,2H,2H-Perfluorohexanesulfonic Acid	6HPFHXSA	NS	ug/l	NA	<0.00599 U	NA	<0.00634 UJ	<0.00627 U	<0.00604 U	<0.006 UJ	<0.00609 U	<0.00623 U	<0.00638 UJ	<0.00635 UJ	<0.00619 UJ	<0.00611 UJ	<0.00602 UJ	<0.00621 U	<0.006 U
3:3 FTCA	356-02-5	NS	ug/l	NA	<0.00749 U	NA	<0.00793 U	<0.00784 U	<0.00756 U	<0.0075 U	<0.00761 U	<0.00779 U	<0.00797 U	<0.00793 U	<0.00774 U	<0.00764 U	<0.00752 U	<0.00777 U	<0.0075 U
4,8-Dioxa-3H-perfluorononanoic acid (ADO	919005-14-4	NS	ug/l	NA	<0.00599 U	NA	<0.00634 U	<0.00627 U	<0.00604 U	<0.006 U	<0.00609 U	<0.00623 U	<0.00638 U	<0.00635 U	<0.00619 U	<0.00611 U	<0.00602 U	<0.00621 U	<0.006 U
5:3 FTCA	914637-49-3	NS	ug/l	NA	<0.0374 U	NA	<0.0396 U	<0.0392 U	<0.0378 U	<0.0375 U	<0.038 U	<0.0389 U	<0.0399 U	<0.0397 U	<0.0387 U	<0.0382 U	<0.0376 U	<0.0388 U	<0.0375 U
7:3 FTCA	812-70-4	NS	ug/l	NA	<0.0374 U	NA	0.00785 J	0.00768 J	<0.0378 U	0.00967 J	0.00959 J	<0.0389 U	<0.0399 U	<0.0397 U	<0.0387 U	<0.0382 U	<0.0376 U	0.00645 J	<0.0375 U
9-Chlorohexadecafluoro-3-Oxanonane-1-Sul	756426-58-1	NS	ug/l	NA	<0.00599 U	NA	<0.00634 U	<0.00627 U	<0.00604 U	<0.006 U	<0.00609 U	<0.00623 U	<0.00638 U	<0.00635 U	<0.00619 U	<0.00611 U	<0.00602 U	<0.00621 U	<0.006 U
N-ethyl perfluorooctane- sulfonamidoacetic	2991-50-6	NS	ug/l	NA	<0.0015 U	NA	<0.00159 U	<0.00157 U	<0.00151 U	0.0574	<0.00152 U	<0.00156 U	0.046	0.00532	0.00441	0.186	<0.0015 U	<0.00155 U	<0.0015 U
N-ethylperfluorooctane sulfonamide	4151-50-2	NS	ug/l	NA	<0.0015 U	NA	<0.00159 U	<0.00157 U	<0.00151 U	<0.0015 U	<0.00152 U	<0.00156 U	0.00144 J	<0.00159 U	<0.00155 U	<0.00153 U	<0.0015 U	<0.00155 U	<0.0015 U
N-ethylperfluorooctane sulfonamidoe	1691-99-2	NS	ug/l	NA	<0.015 U	NA	<0.0159 U	<0.0157 U	<0.0151 U	<0.015 U	<0.0152 U	<0.0156 U	<0.0159 U	<0.0159 U	<0.0155 U	<0.0153 U	<0.015 U	<0.0155 U	<0.015 U
N-methyl perfluorooctane- sulfonamidoacet	2355-31-9	NS	ug/l	NA	<0.0015 UJ	NA	<0.00159 U	<0.00157 U	<0.00151 U	0.0184	<0.00152 U	<0.00156 U	0.00574	0.000952 J	0.00108 J	0.0185	<0.0015 U	<0.00155 U	<0.0015 U
N-methylperfluorooctane sulfonamide	31506-32-8	NS	ug/l	NA	<0.0015 U	NA	<0.00159 U	<0.00157 U	<0.00151 U	<0.0015 U	<0.00152 U	<0.00156 U	<0.00159 U	<0.00159 U	<0.00155 U	<0.00153 U	<0.0015 U	<0.00155 U	<0.0015 U
N-methylperfluorooctanesulfonamidol	24448-09-7	NS	ug/l	NA	<0.015 U	NA	<0.0159 U	<0.0157 U	<0.0151 U	<0.015 U	<0.0152 U	<0.0156 U	<0.0159 U	<0.0159 U	<0.0155 U	<0.0153 U	<0.015 U	<0.0155 U	<0.015 U
Nonafluoro-3,6-dioxaheptanoic acid	151772-58-6	NS	ug/l	NA	<0.00299 U	NA	<0.00317 U	<0.00314 U	<0.00302 U	<0.003 U	<0.00304 U	<0.00312 U	<0.00319 U	<0.00317 U	<0.00309 U	<0.00306 U	<0.00301 U	<0.00311 U	<0.003 U
Perfluoro(2-ethoxyethane)sulfonic acid	113507-82-7	NS	ug/l	NA	<0.00299 U	NA	<0.00317 U	<0.00314 U	<0.00302 U	<0.003 U	<0.00304 U	<0.00312 U	<0.00319 U	<0.00317 U	<0.00309 U	<0.00306 U	<0.00301 U	<0.00311 U	<0.003 U
Perfluoro-3-methoxypropanoic acid	377-73-1	NS	ug/l	NA	<0.00299 U	NA	0.000555 J	<0.00314 U	<0.00302 U	0.000525 J	<0.00304 U	<0.00312 U	<0.00319 U	<0.00317 U	<0.00309 U	<0.00306 U	<0.00301 U	0.000466 J	<0.003 U
Perfluoro-4-methoxybutanoic acid	863090-89-5	NS	ug/l	NA	<0.00299 U	NA	<0.00317 U	<0.00314 U	<0.00302 U	<0.003 U	<0.00304 U	<0.00312 U	<0.00319 U	<0.00317 U	<0.00309 U	<0.00306 U	<0.00301 U	<0.00311 U	<0.003 U
Perfluorobutanesulfonic Acid (PFBS)	375-73-5	NS	ug/l	NA	0.0015	NA	0.00309	0.00635	0.00068 J	0.00465	0.00282	0.00164	0.00279	0.00849	0.0089	0.00665	0.00361	0.00311	0.0121
Perfluorobutanoic acid (PFBA)	375-22-4	NS	ug/l	NA	0.00486 J	NA	0.0104	0.0172	0.00121 J	0.0111	0.00556 J	0.00125 J	0.0141	0.0309	0.0309	0.0202	0.00835	0.00419 J	0.019
Perfluorodecanesulfonic Acid (PFDS)	335-77-3	NS	ug/l	NA	<0.0015 U	NA	<0.00159 U	<0.00157 U	<0.00151 U	<0.0015 U	<0.00152 U	<0.00156 U	<0.00159 U	<0.00159 U	<0.00155 U	<0.00153 U	<0.0015 U	<0.00155 U	<0.0015 U
Perfluorodecanoic Acid (PFDA)	335-76-2	NS	ug/l	NA	<0.0015 U	NA	<0.00159 U	0.000706 J	<0.00151 U	0.00247	0.00122 J	<0.00156 U	0.00183 J	0.00119 J	0.000774 J	0.00244	<0.0015 U	<0.00155 U	0.000825 J
Perfluorododecanesulfonic Acid (PFDOS)	79780-39-5	NS	ug/l	NA	<0.0015 U	NA	<0.00159 U	<0.00157 U	<0.00151 U	<0.0015 U	<0.00152 U	<0.00156 U	<0.00159 U	<0.00159 U	<0.00155 U	<0.00153 U	<0.0015 U	<0.00155 U	<0.0015 U
Perfluorododecanoic Acid (PFDoA)	307-55-1	NS	ug/l	NA	<0.0015 U	NA	<0.00159 U	<0.00157 U	<0.00151 U	<0.0015 U	<0.00152 U	<0.00156 U	<0.00159 U	<0.00159 U	<0.00155 U	<0.00153 U	<0.0015 U	<0.00155 U	<0.0015 U
Perfluoroheptanesulfonic Acid (PFHpS)	375-92-8	NS	ug/l	NA	<0.0015 U	NA	<0.00159 U	0.000706 J	0.00068 J	0.00202	<0.00152 U	<0.00156 U	0.00207 J	0.00349	0.00302	0.00321	<0.0015 U	<0.00155 U	<0.0015 U
Perfluoroheptanoic acid (PFHpA)	375-85-9	NS	ug/l	NA	0.00928	NA	0.00436 J	0.00776	0.00204	0.0087 J	0.00396 J	0.00218	0.0189	0.0274	0.0282	0.0109	0.0094	0.00326	0.00608
Perfluorohexanesulfonic Acid (PFHxS)	355-46-4	NS	ug/l	NA	0.00427	NA	0.00365	0.00439	0.00748	0.0175	0.00594	0.024	0.0173	0.119	0.118	0.0149	0.00827	0.00412	0.0012 J
Perfluorohexanoic Acid (PFHxA)	307-24-4	NS	ug/l	NA	0.00734	NA	0.00785	0.0161	0.00113 J	0.014	0.00852	0.00226	0.0167	0.0319	0.0307	0.0128	0.00993	0.00583	0.0154
Perfluorononanesulfonic Acid (PFNS)	68259-12-1	NS	ug/l	NA	<0.0015 U	NA	<0.00159 U	<0.00157 U	<0.00151 U	<0.0015 U	<0.00152 U	<0.00156 U	<0.00159 U	<0.00159 U	<0.00155 U	<0.00153 U	<0.0015 U	<0.00155 U	<0.0015 U
Perfluorononanoic Acid (PFNA)	375-95-1	NS	ug/l	NA	<0.0015 U	NA	0.00206	0.00431	0.00136 J	0.00622	0.00175	0.00444	0.00606	0.00825	0.00735	0.0137	0.00662	0.0102	0.00413
Perfluorooctanesulfonamide (FOSA)	754-91-6	NS	ug/l	NA	<0.0015 U	NA	<0.00159 U	<0.00157 U	<0.00151 U	0.00472	<0.00152 U	<0.00156 U	0.00183	0.00135 J	0.00108 J	0.00474 J	<0.0015 U	<0.00155 U	<0.0015 U
Perfluorooctanesulfonic Acid (PFOS)	1763-23-1	**0.0027**	ug/l	NA	<0.0015 U	NA	**0.00452**	**0.0437**	**0.012**	**0.0774**	**0.00723 J**	**0.0167**	**0.0961**	**0.0932**	**0.0771**	**0.153**	**0.0171**	**0.00427**	**0.0176**
Perfluorooctanoic Acid (PFOA)	335-67-1	**0.0067**	ug/l	NA	**0.0668**	NA	**0.0493**	**0.0374**	**0.0104**	**0.0731**	**0.0345**	**0.0422**	**0.123**	**0.183**	**0.182**	**0.0799**	**0.0762**	**0.0228**	**0.0124**
Perfluoropentanesulfonic Acid	2706-91-4	NS	ug/l	NA	<0.0015 U	NA	0.00119 J	0.000941 J	0.000604 J	0.0036	0.00183 J	0.00109 J	0.00255	0.00651	0.00627	<0.00153 U	<0.0015 U	0.00132 J	<0.0015 U
Perfluoropentanoic Acid (PFPeA)	2706-90-3	NS	ug/l	NA	0.00764	NA	0.00833	0.0197	0.000982 J	0.0133	0.0103	0.00187 J	0.0163	0.0257	0.0262	0.0122	0.00978	0.00567	0.0194
Perfluorotetradecanoic Acid (PFTA)	376-06-7	NS	ug/l	NA	<0.0015 U	NA	<0.00159 U	<0.00157 U	<0.00151 U	<0.0015 U	<0.00152 U	<0.00156 U	<0.00159 U	<0.00159 U	<0.00155 U	<0.00153 U	<0.0015 U	<0.00155 U	<0.0015 U
Perfluorotridecanoic Acid (PFTrDA)	72629-94-8	NS	ug/l	NA	<0.0015 U	NA	<0.00159 U	<0.00157 U	<0.00151 U	<0.0015 U	<0.00152 U	<0.00156 U	<0.00159 U	<0.00159 U	<0.00155 U	<0.00153 U	<0.0015 U	<0.00155 U	<0.0015 U
Perfluoroundecanoic Acid (PFUnA)	2058-94-8	NS	ug/l	NA	<0.0015 U	NA	<0.00159 U	<0.00157 U	<0.00151 U	<0.0015 U	<0.00152 U	<0.00156 U	0.000957 J	<0.00159 U	<0.00155 U	<0.00153 U	<0.0015 U	<0.00155 U	<0.0015 U
Sodium 1H,1H,2H,2H-Perfluorodecane Sulf	39108-34-4	NS	ug/l	NA	<0.00599 U	NA	<0.00634 U	<0.00627 U	<0.00604 U	<0.006 U	<0.00609 U	<0.00623 U	<0.00638 UJ	<0.00635 UJ	<0.00619 UJ	<0.00611 UJ	<0.00602 UJ	<0.00621 U	<0.006 U
Sodium 1H,1H,2H,2H-Perfluorooctane Sulf	27619-97-2	NS	ug/l	NA	<0.00599 U	NA	<0.00634 U	0.0216	<0.00604 U	<0.006 U	<0.00609 U	<0.00623 U	0.00375 J	<0.00635 UJ	<0.00619 UJ	<0.00611 UJ	<0.00602 UJ	<0.00621 U	<0.006 U
Tetrafluoro-2- (heptafluoropropoxy) propanc	13252-13-6	NS	ug/l	NA	<0.00599 U	NA	<0.00634 U	<0.00627 U	<0.00604 U	<0.006 U	0.00342 J	<0.00623 U	<0.00638 U	0.00254 J	0.00193 J	0.00283 J	<0.00602 U	<0.00621 U	0.00188 J

Table 3
Site Management Plan
Groundwater Sample Analytical Results

12074 Flatlands Avenue p/o Lot 1 Site
Brooklyn, New York
NYSDEC BCP Site No.: C224353
Langan Project No.: 100688803

Notes:
CAS - Chemical Abstract Service
NS - No standard
ug/l - microgram per liter
NA - Not analyzed
RL - Reporting limit
<RL - Not detected

Groundwater sample analytical results are compared to the New York State Department of Environmental Conservation (NYSDEC) Title 6 Codes, Rules, and Regulations (NYCRR) Part 703.5 and the NYSDEC Technical and Operation Guidance Series (TOGS) 1.1.1 Ambient Water Quality Standards and Guidance Values for Class GA Water and published addenda (herein collectively referenced as "NYSDEC SGVs").

Qualifiers:

J - The analyte was positively identified and the associated numerical value is the approximate concentration of the analyte in the sample.

UJ - The analyte was not detected at a level greater than or equal to the RL; however, the reported RL is approximate and may be inaccurate or imprecise.

U - The analyte was analyzed for, but was not detected at a level greater than or equal to the level of the RL or the sample concentration for results impacted by blank contamination.

Exceedance Summary:
10 - Result exceeds NYSDEC SGVs

Table 4A
Site Management Plan
Soil Vapor Sample Analytical Results

12074 Flatlands Avenue p/o Lot 1 Site
Brooklyn, New York
NYSDEC BCP Site No.: C224353
Langan Project No.: 100688803

Analyte	CAS Number	NYSDOH Decision Matrices Minimum Concentrations	Location	AA01	AA02	LSV-9	LSV-10	LSV-11	LSV-12	LSV-13	LSV-13
			Sample Name	AMBIENT_022823	AMBIENT_030123	LSV-9_022823	LSV-10_022823	LSV-11_022823	LSV-12_022823	LSV-13_030123	DUP-1
			Sample Date	02/28/2023	03/01/2023	02/28/2023	02/28/2023	02/28/2023	02/28/2023	03/01/2023	03/01/2023
			Sample Type	AA	AA	SV	SV	SV	SV	SV	SV
			Unit	Result	Result	Result	Result	Result	Result	Result	Result
Volatile Organic Compounds											
1,1,1-Trichloroethane	71-55-6	100	ug/m3	<1.09 U	<1.09 U	<1.09 UJ	<2.73 UJ	<2.18 UJ	<5.46 UJ	<9.11 UJ	<186 UJ
1,1,2,2-Tetrachloroethane	79-34-5	NS	ug/m3	<1.37 U	<1.37 U	<1.37 UJ	<3.43 UJ	<2.75 UJ	<6.87 UJ	<11.5 UJ	<233 UJ
1,1,2-Trichloro-1,2,2-Trifluoroethane	76-13-1	NS	ug/m3	<1.53 U	<1.53 U	<1.53 UJ	<3.83 UJ	<3.07 UJ	<7.66 UJ	<12.8 UJ	<261 UJ
1,1,2-Trichloroethane	79-00-5	NS	ug/m3	<1.09 U	<1.09 U	<1.09 UJ	<2.73 UJ	<2.18 UJ	<5.46 UJ	<9.11 UJ	<186 UJ
1,1-Dichloroethane	75-34-3	NS	ug/m3	<0.809 U	<0.809 U	<0.809 UJ	<2.02 UJ	<1.62 UJ	<4.05 UJ	<6.76 UJ	<138 UJ
1,1-Dichloroethene	75-35-4	6	ug/m3	<0.793 U	<0.793 U	<0.793 UJ	<1.98 UJ	<1.59 UJ	<3.96 UJ	<6.62 UJ	<135 UJ
1,2,4-Trichlorobenzene	120-82-1	NS	ug/m3	<1.48 U	<1.48 U	<1.48 UJ	<3.71 UJ	<2.97 UJ	<7.42 UJ	<12.4 UJ	<252 UJ
1,2,4-Trimethylbenzene	95-63-6	NS	ug/m3	<0.983 U	<0.983 U	<0.983 UJ	32.8 J	24.7 J	38.1 J	<8.21 UJ	<167 UJ
1,2-Dibromoethane (Ethylene Dibromide)	106-93-4	NS	ug/m3	<1.54 U	<1.54 U	<1.54 UJ	<3.84 UJ	<3.07 UJ	<7.69 UJ	<12.8 UJ	<261 UJ
1,2-Dichlorobenzene	95-50-1	NS	ug/m3	<1.2 U	<1.2 U	<1.2 UJ	<3.01 UJ	<2.4 UJ	<6.01 UJ	<10 UJ	<204 UJ
1,2-Dichloroethane	107-06-2	NS	ug/m3	<0.809 U	<0.809 U	<0.809 UJ	<2.02 UJ	<1.62 UJ	<4.05 UJ	<6.76 UJ	<138 UJ
1,2-Dichloropropane	78-87-5	NS	ug/m3	<0.924 U	<0.924 U	<0.924 UJ	<2.31 UJ	<1.85 UJ	<4.62 UJ	28 J	<157 UJ
1,2-Dichlorotetrafluoroethane	76-14-2	NS	ug/m3	<1.4 U	<1.4 U	<1.4 UJ	<3.49 UJ	<2.8 UJ	<6.99 UJ	<11.7 UJ	<238 UJ
1,3,5-Trimethylbenzene (Mesitylene)	108-67-8	NS	ug/m3	<0.983 U	<0.983 U	<0.983 UJ	9 J	7.62 J	12.3 J	<8.21 UJ	<167 UJ
1,3-Butadiene	106-99-0	NS	ug/m3	<0.442 U	<0.442 U	<0.442 UJ	1.22 J	1.17 J	<2.21 UJ	4.36 J	<75.2 UJ
1,3-Dichlorobenzene	541-73-1	NS	ug/m3	<1.2 U	<1.2 U	<1.2 UJ	<3.01 UJ	<2.4 UJ	<6.01 UJ	<10 UJ	<204 UJ
1,4-Dichlorobenzene	106-46-7	NS	ug/m3	<1.2 U	<1.2 U	<1.2 UJ	<3.01 UJ	<2.4 UJ	<6.01 UJ	<10 UJ	<204 UJ
1,4-Dioxane (P-Dioxane)	123-91-1	NS	ug/m3	<0.721 U	<0.721 U	<0.721 UJ	<1.8 UJ	<1.44 UJ	<3.6 UJ	<6.02 UJ	<123 UJ
2,2,4-Trimethylpentane	540-84-1	NS	ug/m3	<0.934 U	<0.934 U	<0.934 UJ	13.5 J	85.5 J	743 J	3,000 J	4,570 J
2-Hexanone (MBK)	591-78-6	NS	ug/m3	<0.82 U	<0.82 U	<0.82 UJ	<2.05 UJ	<1.64 UJ	<4.1 UJ	<6.84 UJ	<139 UJ
4-Ethyltoluene	622-96-8	NS	ug/m3	<0.983 U	<0.983 U	<0.983 UJ	5.8 J	5.7 J	14.3 J	<8.21 UJ	<167 UJ
Acetone	67-64-1	NS	ug/m3	7.79	7.22	6.89 J	276 J	152 J	34.7 J	50.6 J	<404 UJ
Allyl Chloride (3-Chloropropene)	107-05-1	NS	ug/m3	<0.626 U	<0.626 U	<0.626 UJ	<1.57 UJ	<1.25 UJ	<3.13 UJ	<5.23 UJ	<106 UJ
Benzene	71-43-2	NS	ug/m3	1.22	0.853	1.7 J	6.96 J	13.1 J	29.1 J	45.4 J	<109 UJ
Benzyl Chloride	100-44-7	NS	ug/m3	<1.04 U	<1.04 U	<1.04 UJ	<2.59 UJ	<2.07 UJ	<5.18 UJ	<8.65 UJ	<176 UJ
Bromodichloromethane	75-27-4	NS	ug/m3	<1.34 U	<1.34 U	<1.34 UJ	<3.35 UJ	<2.68 UJ	<6.7 UJ	<11.2 UJ	<228 UJ
Bromoethene	593-60-2	NS	ug/m3	<0.874 U	<0.874 U	<0.874 UJ	<2.19 UJ	<1.75 UJ	<4.37 UJ	<7.3 UJ	<149 UJ
Bromoform	75-25-2	NS	ug/m3	<2.07 U	<2.07 U	<2.07 UJ	<5.17 UJ	<4.14 UJ	<10.3 UJ	<17.3 UJ	<352 UJ
Bromomethane	74-83-9	NS	ug/m3	<0.777 U	<0.777 U	<0.777 UJ	<1.94 UJ	<1.55 UJ	<3.88 UJ	<6.48 UJ	<132 UJ
Carbon Disulfide	75-15-0	NS	ug/m3	<0.623 U	<0.623 U	<0.623 UJ	213 J	210 J	51.7 J	73.2 J	<106 UJ
Carbon Tetrachloride	56-23-5	6	ug/m3	<1.26 U	<1.26 U	<1.26 UJ	<3.15 UJ	<2.52 UJ	<6.29 UJ	<10.5 UJ	<214 UJ
Chlorobenzene	108-90-7	NS	ug/m3	<0.921 U	<0.921 U	<0.921 UJ	<2.3 UJ	<1.84 UJ	<4.61 UJ	<7.69 UJ	<157 UJ
Chloroethane	75-00-3	NS	ug/m3	<0.528 U	<0.528 U	<0.528 UJ	<1.32 UJ	<1.06 UJ	12.8 J	<4.41 UJ	<89.7 UJ
Chloroform	67-66-3	NS	ug/m3	<0.977 U	<0.977 U	<0.977 UJ	<2.44 UJ	<1.95 UJ	<4.88 UJ	<8.16 UJ	<166 UJ
Chloromethane	74-87-3	NS	ug/m3	1.16	0.956	1.15 J	10.8 J	<0.826 UJ	<2.07 UJ	<3.45 UJ	<70.2 UJ
Cis-1,2-Dichloroethene	156-59-2	**6**	ug/m3	<0.793 U	<0.793 U	<0.793 UJ	<1.98 UJ	<1.59 UJ	**7.69 J**	**10.4 J**	<135 UJ
Cis-1,3-Dichloropropene	10061-01-5	NS	ug/m3	<0.908 U	<0.908 U	<0.908 UJ	<2.27 UJ	<1.82 UJ	<4.54 UJ	<7.58 UJ	<154 UJ
Cyclohexane	110-82-7	NS	ug/m3	<0.688 U	<0.688 U	<0.688 UJ	6.54 J	21.3 J	458 J	19,700 J	21,200 J
Dibromochloromethane	124-48-1	NS	ug/m3	<1.7 U	<1.7 U	<1.7 UJ	<4.26 UJ	<3.41 UJ	<8.52 UJ	<14.2 UJ	<290 UJ
Dichlorodifluoromethane	75-71-8	NS	ug/m3	2.26	2.22	2.24 J	2.58 J	3.25 J	47.7 J	<8.26 UJ	<168 UJ
Ethanol	64-17-5	NS	ug/m3	11.5	<9.42 U	12.5 J	27.1 J	53.3 J	<47.1 UJ	<78.6 UJ	<1,600 UJ
Ethyl Acetate	141-78-6	NS	ug/m3	<1.8 U	<1.8 U	<1.8 UJ	16.9 J	5.08 J	<9.01 UJ	<15 UJ	<306 UJ
Ethylbenzene	100-41-4	NS	ug/m3	<0.869 U	<0.869 U	1.09 J	17.4 J	19.8 J	72.1 J	<7.25 UJ	<148 UJ
Hexachlorobutadiene	87-68-3	NS	ug/m3	<2.13 U	<2.13 U	<2.13 UJ	<5.33 UJ	<4.27 UJ	<10.7 UJ	<17.8 UJ	<363 UJ
Isopropanol	67-63-0	NS	ug/m3	3.42	1.71	4.42 J	14.8 J	7.45 J	<6.15 UJ	<10.3 UJ	<209 UJ
M,P-Xylene	179601-23-1	NS	ug/m3	<1.74 U	<1.74 U	3.44 J	69.5 J	73 J	151 J	29.6 J	<295 UJ
Methyl Ethyl Ketone (2-Butanone)	78-93-3	NS	ug/m3	<1.47 U	<1.47 U	<1.47 UJ	56 J	31.6 J	<7.37 UJ	<12.3 UJ	<251 UJ
Methyl Isobutyl Ketone (4-Methyl-2-Pentanone)	108-10-1	NS	ug/m3	<2.05 U	<2.05 U	<2.05 UJ	<5.12 UJ	<4.1 UJ	<10.2 UJ	<17.1 UJ	<348 UJ
Methylene Chloride	75-09-2	100	ug/m3	<1.74 U	<1.74 U	<1.74 UJ	<4.34 UJ	<3.47 UJ	<8.69 UJ	<14.5 UJ	<295 UJ
n-Heptane	142-82-5	NS	ug/m3	<0.82 U	2.12	<0.82 UJ	40.1 J	32.7 J	68 J	13,200 J	15,200 J
n-Hexane	110-54-3	NS	ug/m3	0.916	<0.705 U	0.8 J	49.3 J	51.5 J	233 J	45,800 J	49,300 J
o-Xylene (1,2-Dimethylbenzene)	95-47-6	NS	ug/m3	<0.869 U	<0.869 U	1.39 J	34.4 J	45.2 J	95.1 J	10.6 J	<148 UJ
Styrene	100-42-5	NS	ug/m3	<0.852 U	<0.852 U	<0.852 UJ	<2.13 UJ	1.95 J	4.68 J	<7.11 UJ	<145 UJ
Tert-Butyl Alcohol	75-65-0	NS	ug/m3	<1.52 U	<1.52 U	<1.52 UJ	5.73 J	5.49 J	<7.58 UJ	<12.6 UJ	<258 UJ
Tert-Butyl Methyl Ether	1634-04-4	NS	ug/m3	<0.721 U	<0.721 U	<0.721 UJ	<1.8 UJ	<1.44 UJ	<3.61 UJ	<6.02 UJ	<123 UJ
Tetrachloroethene (PCE)	127-18-4	**100**	ug/m3	<1.36 U	<1.36 U	1.49 J	**177 J**	67 J	90.9 J	**186 J**	**235 J**
Tetrahydrofuran	109-99-9	NS	ug/m3	<1.47 U	<1.47 U	<1.47 UJ	<3.69 UJ	4.04 J	<7.37 UJ	<12.3 UJ	<251 UJ
Toluene	108-88-3	NS	ug/m3	2.61	1.1	4.56 J	40.7 J	39.9 J	139 J	169 J	210 J
Trans-1,2-Dichloroethene	156-60-5	NS	ug/m3	<0.793 U	<0.793 U	<0.793 UJ	<1.98 UJ	<1.59 UJ	<3.96 UJ	<6.62 UJ	<135 UJ
Trans-1,3-Dichloropropene	10061-02-6	NS	ug/m3	<0.908 U	<0.908 U	<0.908 UJ	<2.27 UJ	<1.82 UJ	<4.54 UJ	<7.58 UJ	<154 UJ
Trichloroethene (TCE)	79-01-6	6	ug/m3	<1.07 U	<1.07 U	<1.07 UJ	<2.69 UJ	<2.15 UJ	<5.37 UJ	<8.97 UJ	<183 UJ
Trichlorofluoromethane	75-69-4	NS	ug/m3	1.29	<1.12 U	1.37 J	<2.81 UJ	<2.25 UJ	<5.62 UJ	<9.38 UJ	<191 UJ
Vinyl Chloride	75-01-4	**6**	ug/m3	<0.511 U	<0.511 U	<0.511 UJ	<1.28 UJ	<1.02 UJ	**21.9 J**	**14.2 J**	<86.9 UJ

Table 4A
Site Management Plan
Soil Vapor Sample Analytical Results

12074 Flatlands Avenue p/o Lot 1 Site
Brooklyn, New York
NYSDEC BCP Site No.: C224353
Langan Project No.: 100688803

Analyte	CAS Number	NYSDOH Decision Matrices Minimum Concentrations	Location	LSV-14	LSV-15	LSV-16	LSV-17	LSV-18	LSV-19	LSV-20	LSV-21
			Sample Name	LSV-14_022823	LSV-15_030123	LSV-16_030123	LSV-17_030123	LSV-18_030123	LSV-19_030123	LSV-20_030123	LSV-21_022823
			Sample Date	02/28/2023	03/01/2023	03/01/2023	03/01/2023	03/01/2023	03/01/2023	03/01/2023	02/28/2023
			Sample Type	SV	SV	SV	SV	SV	SV	SV	SV
			Unit	Result	Result	Result	Result	Result	Result	Result	Result
Volatile Organic Compounds											
1,1,1-Trichloroethane	71-55-6	100	ug/m3	<4.2 U	<6.82 UJ	<5.46 UJ	<4.2 UJ	<3.21 U	<1.09 U	<6.06 UJ	<4.96 U
1,1,2,2-Tetrachloroethane	79-34-5	NS	ug/m3	<5.28 U	<8.58 UJ	<6.87 UJ	<5.28 UJ	<4.04 U	<1.37 U	<7.62 UJ	<6.24 U
1,1,2-Trichloro-1,2,2-Trifluoroethane	76-13-1	NS	ug/m3	<5.89 U	<9.58 UJ	<7.66 UJ	<5.89 UJ	<4.51 U	<1.53 U	<8.51 UJ	<6.97 U
1,1,2-Trichloroethane	79-00-5	NS	ug/m3	<4.2 U	<6.82 UJ	<5.46 UJ	<4.2 UJ	<3.21 U	<1.09 U	<6.06 UJ	<4.96 U
1,1-Dichloroethane	75-34-3	NS	ug/m3	<3.11 U	<5.06 UJ	<4.05 UJ	<3.11 UJ	3.91	<0.809 U	<4.49 UJ	<3.68 U
1,1-Dichloroethene	75-35-4	6	ug/m3	<3.05 U	<4.96 UJ	<3.96 UJ	<3.05 UJ	<2.33 U	<0.793 U	<4.4 UJ	<3.6 U
1,2,4-Trichlorobenzene	120-82-1	NS	ug/m3	<5.71 U	<9.28 UJ	<7.42 UJ	<5.71 UJ	<4.36 U	<1.48 U	<8.24 UJ	<6.75 U
1,2,4-Trimethylbenzene	95-63-6	NS	ug/m3	20.9	7.23 J	<4.92 UJ	<3.78 UJ	3.02	4.49	<5.46 UJ	28.4
1,2-Dibromoethane (Ethylene Dibromide)	106-93-4	NS	ug/m3	<5.91 U	<9.61 UJ	<7.69 UJ	<5.91 UJ	<4.52 U	<1.54 U	<8.53 UJ	<6.99 U
1,2-Dichlorobenzene	95-50-1	NS	ug/m3	<4.62 U	<7.52 UJ	<6.01 UJ	<4.62 UJ	<3.54 U	<1.2 U	<6.67 UJ	<5.47 U
1,2-Dichloroethane	107-06-2	NS	ug/m3	<3.11 U	<5.06 UJ	<4.05 UJ	<3.11 UJ	<2.38 U	<0.809 U	<4.49 UJ	<3.68 U
1,2-Dichloropropane	78-87-5	NS	ug/m3	<3.55 U	<5.78 UJ	<4.62 UJ	<3.55 UJ	<2.72 U	<0.924 U	<5.13 UJ	<4.2 U
1,2-Dichlorotetrafluoroethane	76-14-2	NS	ug/m3	<5.38 U	<8.74 UJ	<6.99 UJ	<5.38 UJ	<4.11 U	<1.4 U	<7.76 UJ	<6.35 U
1,3,5-Trimethylbenzene (Mesitylene)	108-67-8	NS	ug/m3	11.5	<6.15 UJ	<4.92 UJ	<3.78 UJ	<2.89 U	1.45	<5.46 UJ	7.72
1,3-Butadiene	106-99-0	NS	ug/m3	2.72	<2.77 UJ	4.42 J	<1.7 UJ	2.61	<0.442 U	3.19 J	5.64
1,3-Dichlorobenzene	541-73-1	NS	ug/m3	<4.62 U	<7.52 UJ	<6.01 UJ	<4.62 UJ	<3.54 U	<1.2 U	<6.67 UJ	<5.47 U
1,4-Dichlorobenzene	106-46-7	NS	ug/m3	<4.62 U	<7.52 UJ	<6.01 UJ	<4.62 UJ	<3.54 U	<1.2 U	<6.67 UJ	<5.47 U
1,4-Dioxane (P-Dioxane)	123-91-1	NS	ug/m3	<2.77 U	<4.5 UJ	<3.6 UJ	<2.77 UJ	<2.12 U	<0.721 U	<4 UJ	<3.28 U
2,2,4-Trimethylpentane	540-84-1	NS	ug/m3	270	995 J	108 J	69.6 J	142	68.7	91.1 J	370
2-Hexanone (MBK)	591-78-6	NS	ug/m3	<3.15 U	<5.12 UJ	<4.1 UJ	<3.15 UJ	<2.41 U	<0.82 U	<4.55 UJ	<3.73 U
4-Ethyltoluene	622-96-8	NS	ug/m3	14.3	<6.15 UJ	<4.92 UJ	<3.78 UJ	<2.89 U	2.77	<5.46 UJ	8.55
Acetone	67-64-1	NS	ug/m3	124	<14.8 UJ	126 J	26.1 J	15.9	4.66	36.8 J	133
Allyl Chloride (3-Chloropropene)	107-05-1	NS	ug/m3	<2.41 U	<3.91 UJ	<3.13 UJ	<2.41 UJ	<1.84 U	<0.626 U	<3.47 UJ	<2.85 U
Benzene	71-43-2	NS	ug/m3	275	31.9 J	16.4 J	3.87 J	33.5	15.7	5.94 J	21.2
Benzyl Chloride	100-44-7	NS	ug/m3	<3.98 U	<6.47 UJ	<5.18 UJ	<3.98 UJ	<3.04 U	<1.04 U	<5.75 UJ	<4.71 U
Bromodichloromethane	75-27-4	NS	ug/m3	<5.15 U	<8.37 UJ	<6.7 UJ	<5.15 UJ	<3.94 U	<1.34 U	<7.44 UJ	<6.09 U
Bromoethene	593-60-2	NS	ug/m3	<3.36 U	<5.47 UJ	<4.37 UJ	<3.36 UJ	<2.57 U	<0.874 U	<4.85 UJ	<3.97 U
Bromoform	75-25-2	NS	ug/m3	<7.95 U	<12.9 UJ	<10.3 UJ	<7.95 UJ	<6.08 U	<2.07 U	<11.5 UJ	<9.4 U
Bromomethane	74-83-9	NS	ug/m3	<2.99 U	<4.85 UJ	<3.88 UJ	<2.99 UJ	<2.28 U	<0.777 U	<4.31 UJ	<3.53 U
Carbon Disulfide	75-15-0	NS	ug/m3	26.3	22.8 J	26.3 J	19 J	52.6	9.5	86.9 J	49.8
Carbon Tetrachloride	56-23-5	6	ug/m3	<4.84 U	<7.86 UJ	<6.29 UJ	<4.84 UJ	<3.7 U	<1.26 U	<6.98 UJ	<5.72 U
Chlorobenzene	108-90-7	NS	ug/m3	<3.54 U	<5.76 UJ	<4.61 UJ	<3.54 UJ	<2.71 U	<0.921 U	<5.11 UJ	<4.19 U
Chloroethane	75-00-3	NS	ug/m3	<2.03 U	<3.3 UJ	<2.64 UJ	<2.03 UJ	5.57	2.3	<2.93 UJ	<2.4 U
Chloroform	67-66-3	NS	ug/m3	<3.76 U	<6.1 UJ	<4.88 UJ	<3.76 UJ	<2.87 U	1.26	<5.42 UJ	<4.44 U
Chloromethane	74-87-3	NS	ug/m3	<1.59 U	<2.58 UJ	<2.07 UJ	<1.59 UJ	1.34	<0.413 U	<2.29 UJ	<1.88 U
Cis-1,2-Dichloroethene	156-59-2	**6**	ug/m3	<3.05 U	4.96 J	**12.2 J**	<3.05 UJ	5.99	**8.88**	<4.4 UJ	<3.6 U
Cis-1,3-Dichloropropene	10061-01-5	NS	ug/m3	<3.49 U	<5.67 UJ	<4.54 UJ	<3.49 UJ	<2.67 U	<0.908 U	<5.04 UJ	<4.13 U
Cyclohexane	110-82-7	NS	ug/m3	537	874 J	181 J	59.9 J	75	32.7	45.4 J	326
Dibromochloromethane	124-48-1	NS	ug/m3	<6.55 U	<10.6 UJ	<8.52 UJ	<6.55 UJ	<5.01 U	<1.7 U	<9.46 UJ	<7.74 U
Dichlorodifluoromethane	75-71-8	NS	ug/m3	<3.8 U	9.49 J	26.3 J	136 J	269	53.9	65.3 J	24.6
Ethanol	64-17-5	NS	ug/m3	<36.2 U	<58.8 UJ	52 J	<36.2 UJ	<27.7 U	<9.42 U	<52.4 UJ	<42.8 U
Ethyl Acetate	141-78-6	NS	ug/m3	<6.92 U	<11.2 UJ	<9.01 UJ	<6.92 UJ	<5.3 U	<1.8 U	<10 UJ	9.95
Ethylbenzene	100-41-4	NS	ug/m3	162	23 J	10.5 J	5.39 J	8.04	7.69	5.95 J	23
Hexachlorobutadiene	87-68-3	NS	ug/m3	<8.2 U	<13.3 UJ	<10.7 UJ	<8.2 UJ	<6.27 U	<2.13 U	<11.8 UJ	<9.7 U
Isopropanol	67-63-0	NS	ug/m3	<4.72 U	11.8 J	13.8 J	11 J	3.79	2.85	<6.83 UJ	6.91
M,P-Xylene	179601-23-1	NS	ug/m3	174	49.1 J	35.4 J	20.8 J	27	28.1	20.9 J	76
Methyl Ethyl Ketone (2-Butanone)	78-93-3	NS	ug/m3	32.4	20.7 J	30.1 J	26.3 J	<4.34 U	<1.47 U	51.3 J	46
Methyl Isobutyl Ketone (4-Methyl-2-Pentanone)	108-10-1	NS	ug/m3	<7.87 U	<12.8 UJ	<10.2 UJ	14.3 J	<6.02 U	<2.05 U	<11.4 UJ	<9.3 U
Methylene Chloride	75-09-2	100	ug/m3	<6.67 U	<10.8 UJ	<8.69 UJ	<6.67 UJ	<5.11 U	<1.74 U	<9.66 UJ	<7.89 U
n-Heptane	142-82-5	NS	ug/m3	327	200 J	84 J	28.4 J	59.4	41.8	106 J	155
n-Hexane	110-54-3	NS	ug/m3	567	744 J	221 J	92.3 J	299	129	212 J	331
o-Xylene (1,2-Dimethylbenzene)	95-47-6	NS	ug/m3	155	29.4 J	15.5 J	8.04 J	12.5	13.3	8.73 J	38.3
Styrene	100-42-5	NS	ug/m3	4.56	<5.32 UJ	<4.26 UJ	<3.27 UJ	<2.5 U	1.19	<4.73 UJ	<3.87 U
Tert-Butyl Alcohol	75-65-0	NS	ug/m3	8.12	19.9 J	32.7 J	19.8 J	<4.46 U	<1.52 U	<8.43 UJ	<6.88 U
Tert-Butyl Methyl Ether	1634-04-4	NS	ug/m3	<2.77 U	46.9 J	<3.61 UJ	<2.77 UJ	<2.12 U	3.71	<4 UJ	<3.28 U
Tetrachloroethene (PCE)	127-18-4	**100**	ug/m3	**255**	**332 J**	**332 J**	**201 J**	**336**	**340**	**244 J**	67.7
Tetrahydrofuran	109-99-9	NS	ug/m3	<5.66 U	<9.2 UJ	<7.37 UJ	<5.66 UJ	<4.34 U	1.7	<8.2 UJ	<6.69 U
Toluene	108-88-3	NS	ug/m3	358	39.9 J	29.8 J	15.8 J	32	26.8	17.4 J	46
Trans-1,2-Dichloroethene	156-60-5	NS	ug/m3	<3.05 U	<4.96 UJ	<3.96 UJ	<3.05 UJ	<2.33 U	<0.793 U	<4.4 UJ	<3.6 U
Trans-1,3-Dichloropropene	10061-02-6	NS	ug/m3	<3.49 U	<5.67 UJ	<4.54 UJ	<3.49 UJ	<2.67 U	<0.908 U	<5.04 UJ	<4.13 U
Trichloroethene (TCE)	79-01-6	6	ug/m3	<4.13 U	<6.72 UJ	<5.37 UJ	<4.13 UJ	<3.16 U	1.83	<5.97 UJ	<4.89 U
Trichlorofluoromethane	75-69-4	NS	ug/m3	<4.32 U	<7.02 UJ	<5.62 UJ	<4.32 UJ	<3.3 U	<1.12 U	<6.24 UJ	<5.11 U
Vinyl Chloride	75-01-4	**6**	ug/m3	**6.26**	**68 J**	**23.1 J**	<1.97 UJ	**13.1**	**10.9**	<2.84 UJ	<2.32 U

Table 4A
Site Management Plan
Soil Vapor Sample Analytical Results

12074 Flatlands Avenue p/o Lot 1 Site
Brooklyn, New York
NYSDEC BCP Site No.: C224353
Langan Project No.: 100688803

Notes:
SV - Soil Vapor
CAS - Chemical Abstract Service
NS - No standard
ug/m3 - microgram per cubic meter
NA - Not analyzed
RL - Reporting limit
<RL - Not detected

Soil vapor sample analytical results are compared to the minimum soil vapor concentrations at which mitigation is recommended as set forth in the New York State Department of Health (NYSDOH) October 2006 Guidance for Evaluating Soil Vapor Intrusion in the State of New York Decision Matrices for Sub-Slab Vapor and Indoor Air and subsequent updates (2017).

Ambient air sample analytical results are shown for reference only.

Qualifiers:

J - The analyte was positively identified and the associated numerical value is the approximate concentration of the analyte in the sample.

UJ - The analyte was not detected at a level greater than or equal to the RL; however, the reported RL is approximate and may be inaccurate or imprecise.

U - The analyte was analyzed for, but was not detected at a level greater than or equal to the level of the RL or the sample concentration for results impacted by blank contamination.

Exceedance Summary:
10 - Result exceeds minimum soil vapor concentrations recommending mitigation

Table 4B
Site Management Plan
Methane Monitoring Results

12074 Flatlands Avenue p/o Lot 1 Site
Brooklyn, New York
NYSDEC BCP Site No.: C224353
Langan Project No.: 100688803

	Off-Site						**On-Site**		
Location	LSB-1	LSB-3	LSB-4	LSB-7	LSB-9	LSB-19	LSB-11	LSB-13	LSB-13
Date	5/11/2018	5/11/2018	5/11/2018	5/11/2018	5/9/2018	5/8/2018	5/9/2018	5/9/2018	5/9/2018
Sample Depth (feet bsl)	8	8	8	8	8	10	8	5	15
Monitoring/Purge Time (minutes)	**Methane Readings (%)**								
0	0	0	0	0	0	0	0	0	0
0.5	0	0	0	0	0	0	0	0	0
1	0	0	0	0	0	0	0	0	0
1.5	0	0	0	0	0	0	0	0	0
2	0	0	0	0	0	0	0	0	0
2.5	0	0	0	0	0	0	0	0	0
3	0	0	0	0	0	0	0	0	0
3.5	0	0	0	0	0	0	0	0	0
4	0	0	0	0	0	0	0	0	0
4.5	0	0	0	0	0	0	0	0	0
5	0	0	0	0	0	0	0	0	0

Table 5
Site Management Plan
Proposed Monitoring Well Construction Detail Summary

12074 Flatlands Avenue p/o Lot 1 Site
Brooklyn, New York
NYSDEC BCP Site No.: C224353
Langan Project No.: 100688803

Monitoring Well ID	Well Location	Approximate Ground Surface Elevation (NAVD88)	Physical Access Limitations	Anticipated Depth to Groundwater (feet bgs)	Anticipated Groundwater Elevation (feet NAVD88)	Well Inner Diameter (inch)	Well Casing and Screen Type	Pre-Packed Well Screen	Well Screen Slot Size (inch)	Proposed Well Screen Inverval (ft bgs)	Proposed Well Screen Inverval (ft NAVD88)	Well Screen Length (ft)	Approx. Borehole Diameter (inch)	Filter Pack Thickess (inch)	Filter Pack Type	Drilling/Installation Method
LMW-26	Refer to SMP Figure 7	13.5	No	11.4	2.1	2.00	Sch. 40 PVC	No	0.010	8-18	-4.5 - 5	10.00	6.00	2.00	WG #2	Hollow Stem Auger
LMW-27	Refer to SMP Figure 7	11	No	9	2	2.00	Sch. 40 PVC	No	0.010	6-16	-5 - 5	10.00	6.00	2.00	WG #2	Hollow Stem Auger
LMW-28	Refer to SMP Figure 7	20	No	18	2	2.00	Sch. 40 PVC	No	0.010	15-25	-5 - 5	10.00	6.00	2.00	WG #2	Hollow Stem Auger
LMW-29	Refer to SMP Figure 7	21	No	19	2	2.00	Sch. 40 PVC	No	0.010	16-26	-5 - 5	10.00	6.00	2.00	WG #2	Hollow Stem Auger
B5_LMW09	Refer to SMP Figure 7	14.5	No	12.6	1.9	2.00	Sch. 40 PVC	No	0.010	9-19	-4.5 - 5	10.00	6.00	2.00	WG #2	Hollow Stem Auger
B5_LMW06	Refer to SMP Figure 7	19	No	17.1	1.9	2.00	Sch. 40 PVC	No	0.010	14-24	-5 - 5	10.00	6.00	2.00	WG #2	Hollow Stem Auger

General Well Construction Notes:

1. A 6-inch bedding layer of filter pack will be placed at bottom of each borehole before placing well screen
2. The top of the well screen will be installed about 2 to 3 feet above the observed water table to account for seasonal fluctuations of the water table elevation. The proposed well screen interval may be modified based on field observations at the time of installation.
3. Filter pack will extend about 2 feet above top of well screen
4. Filter pack will be clean, inert, manufactured filtration sand/gravel media
5. A 2-foot thick bentonite (sodium bentonite) will be placed above the top of filter pack. Bentonite seal will be hydrated using drinking water from a public water supply source.
6. Well annulus above bentonite seal to be filled with clean soil cuttings with no detectable PID measurements and/or grossly-contaminated material, surplus filter pack, or a cement-bentonite mixture.
7. Monitoring wells to be completed with flushmounted protective steel casing with a diameter at least 2-inch greater than outer diameter of well casing and well plug.
8. Monitoring wells will be finished with a 2-ft x 2-ft x 6-inch deep concrete pad

FIGURES



LANGAN
Langan Engineering, Environmental, Surveying, Landscape Architecture and Geology, D.P.C.
300 Kimball Drive
Parsippany, NJ 07054
T: 973.560.4900 F: 973.560.4901 www.langan.com
NJ Certification of Authorization No. 24GA27996400

Project	**12074 FLATLANDS AVENUE SITE** **BCP SITE NO. C224353** **35 INSPIRATION LANE** **F/K/A 12074 FLATLANDS AVENUE** BLOCK 4434, LOT No. 1 BROOKLYN KINGS COUNTY NEW YORK
Figure Title	**SITE LOCATION MAP**
Project No.	100688801
Date	5/21/2026
Scale	1"=2,000'
Drawn By	RDB
Figure No.	1

© 2026 Langan

Path: \\Langan.com\data\PAR\data8\100688801\Project Data\ArcGIS\APRX\Christian Cultural Center_Overview

80 0 80

SCALE IN FEET

References:
1. Imagery provided through Langan's subscription to Nearmap.com. Flown on 07/03/2025.
2. Parcel boundaries obtained from the NYC Department of Planning's MapPLUTO 24v1, updated 2024.

STATE OF NEW YORK RONALD D. BOYER 085831 LICENSED PROFESSIONAL ENGINEER

SIGNATURE 5/22/2026 DATE SIGNED

RONALD BOYER
PROFESSIONAL ENGINEER NY LIC. No. 085831-1

LANGAN
300 Kimball Drive
Parsippany, NJ 07054
T: 973.560.4900 F: 973.560.4901 www.langan.com

Langan Engineering & Environmental Services, Inc.
Langan Engineering, Environmental, Surveying, Landscape Architecture and Geology, D.P.C.
Langan International LLC
Collectively known as Langan

NJ CERTIFICATE OF AUTHORIZATION No. 24GA27996400

Project
12074 FLATLANDS AVENUE SITE
BCP SITE NO. C224353
35 INSPIRATION LANE
F/K/A 12074 FLATLANDS AVENUE

BLOCK No. 4434, LOT No. 1

BROOKLYN

KINGS COUNTY NEW YORK

Drawing Title

SITE PLAN

Project No.	Figure
100688801	2
Date: 07/30/2025	
Scale: 1" = 80'	
Drawn By: RDB	

© 2026 Langan

Path: \\langan.com\data\PAR\data8\100688801\Project Data\ArcGIS\APRX\100688801\100688801_2024.aprx



NOTES:
1. PARCEL BOUNDARIES OBTAINED THROUGH THE NYC DEPARTMENT OF PLANNING'S MAPPLUTO 24V5, UPDATED 2024.
2. THE EXCAVATION EXTENTS PRESENTED ON THIS DRAWING ARE BASED ON VISUAL OBSERVATIONS IN THE FIELD BY A LANGAN REPRESENTATIVE AND FIELD-TAPING MEASUREMENTS.
3. SEGMENT 3 & 4 - FOUNDATION PLAN OBTAINED FROM FIGURE FO-100.00, PREPARED BY IUV PHASE 1B OWNER LLC.

0 40 80
SCALE IN FEET

Legend

- Site Boundary
- Mass Elevation Survey Point
- General Excavation to 15 feet bgs and removal of contaminated fill above the Restricted Residential RUSCOs
- Additional excavation to approximately 27.5 feet bgs for the removal of hazardous lead
- Additional excavation to approximately 20 feet bgs for the removal of hazardous lead
- Additional excavation to approximately 18.5 feet bgs for the removal of hazardous lead
- Additional excavation to between approximately 16.5 and 18.5 feet bgs for the removal of hazardous lead
- Over-excavation of endpoint sample location to 20.5 feet bgs for the removal of additional soil exceeding the Protection of Groundwater SCOs
- Over-excavation of endpoint sample location to 21 feet bgs for the removal of additional soil exceeding the Protection of Groundwater SCOs
- Over-excavation of endpoint sample location to 22 feet bgs for the removal of additional soil exceeding the Protection of Groundwater SCOs

STATE OF NEW YORK · RONALD D. BOYER · 085831 · LICENSED PROFESSIONAL ENGINEER

5/22/2026
SIGNATURE DATE SIGNED

RONALD BOYER
PROFESSIONAL ENGINEER NY LIC. No. 085831-1

LANGAN
Langan Engineering, Environmental, Surveying, Landscape Architecture and Geology, D.P.C.
300 Kimball Drive
Parsippany, NJ 07054
T: 973.560.4900 F: 973.560.4901 www.langan.com
NJ Certification of Authorization No. 24GA27996400

Project
12074 FLATLANDS AVENUE SITE
BCP SITE NO. C224353
35 INSPIRATION LANE
F/K/A 12074 FLATLANDS AVENUE
BLOCK NO. 4434, LOT NO. 1
BROOKLYN
KINGS COUNTY NEW YORK

Drawing Title
REMEDIAL EXCAVATION EXTENTS

Project No. 100688801	Figure 3A
Date 5/21/2026	
Scale 1" = 40 feet	
Drawn By RDB	

© 2026 Langan

Path: \\Langan.com\data\PAR\data8\100688801\Project Data\ArcGIS\APRX\Christian Cultural Center_Overview



Legend

- Mass Elevation Survey Point
- Remedial Excavation Elevation Topographic Lines
- Surface Elevation Topographic Lines
- Over-excavation of endpoint sample location to 20.5 feet bgs to removal additional soil exceeding the Protection of Groundwater SCOs
- Over-excavation of endpoint sample location to 21 feet bgs to removal additional soil exceeding the Protection of Groundwater SCOs
- Over-excavation of endpoint sample location to 22 feet bgs to removal additional soil exceeding the Protection of Groundwater SCOs
- Site Boundary

0 40 80

SCALE IN FEET

NOTES:
1. PARCEL BOUNDARIES OBTAINED THROUGH THE NYC DEPARTMENT OF PLANNING'S MAPPLUTO 24V5, UPDATED 2024.
2. GROUND CONTOURS ARE DISPLAYED IN FEET.
3. SEGMENT 3 & 4 - FOUNDATION PLAN OBTAINED FROM FIGURE FO-100.00, PREPARED BY IUV PHASE 1B OWNER LLC.
4. SURVEY ELEVATION POINTS AS PROVIDED BY CONTROL POINT ASSOCIATES INC. PC "FOUNDATION GRADE AS-BUILT SKETCH" ON 03 FEBRUARY 2026.

LANGAN

Langan Engineering, Environmental, Surveying, Landscape Architecture and Geology, D.P.C.

300 Kimball Drive
Parsippany, NJ 07054

T: 973.560.4900 F: 973.560.4901 www.langan.com
NJ Certification of Authorization No. 24GA27996400

Project
12074 FLATLANDS AVENUE SITE
BCP SITE NO. C224353
35 INSPIRATION LANE
F/K/A 12074 FLATLANDS AVENUE

BLOCK NO. 4434, LOT NO. 1

BROOKLYN

KINGS COUNTY NEW YORK

Drawing Title

REMEDIAL EXCAVATION EXTENTS

Project No.	Figure
100688801	3B
Date: 5/21/2026	
Scale: 1" = 40 feet	
Drawn By: RDB	

©2026 Langan

Path: \\Langan.com\data\PAR\data8\100688801\Project Data\ArcGIS\APRX\Christian Cultural Center_Overview



SUBSURFACE PROFILE A-A'
VERTICAL SCALE: 1" = 5'
HORIZONTAL SCALE: 1" = 10'



SUBSURFACE PROFILE B-B'
VERTICAL SCALE: 1" = 5'
HORIZONTAL SCALE: 1" = 10'



SUBSURFACE PROFILE C-C'

NOTES:
1. THIS PROFILE SHOWS GENERALIZED SUBSURFACE CONDITIONS AT THE RESPECTIVE BORING LOCATIONS. VARIATIONS IN SUBSURFACE CONDITIONS SHOULD BE EXPECTED BETWEEN BORINGS. FOR A DETAILED DESCRIPTION OF CONDITIONS ENCOUNTERED, SEE BORING LOGS INCLUDED WITHIN APPENDIX B AND APPENDIX H OF THE 2023 REMEDIAL INVESTIGATION REPORT PREPARED BY LANGAN.
2. GROUND SURFACE ELEVATIONS OF SOIL BORINGS WERE SURVEYED USING GPS LOCATING TECHNIQUES.
3. ELEVATIONS ARE REFERENCED TO THE NORTH AMERICAN VERTICAL DATUM OF 1988, NAVD88.
4. SOIL BORINGS LSB-10 THROUGH LSB-14 WERE COMPLETED ON 8 AND 9 MAY 2018 AS PART OF THE PHASE II INVESTIGATION. LSB-28 THROUGH LSB-42 WERE COMPLETED BETWEEN 14 AND 27 FEBRUARY 2023 AS PART OF THE 2023 REMEDIAL INVESTIGATION



KEY PLAN N.T.S.

BORING KEY:

B-X
(el XX±)
MATERIAL (AS SPECIFIED)

LEGEND:

B-X	DRILLED BORING IDENTIFICATION
el XX±	APPROXIMATE SURFACE ELEVATION AT THE TIME OF BORING (NAVD88)
	GROUNDWATER IN MONITORING WELL
	ASH LAYER OBSERVED
	APPROX. SURFACE ELEVATION
	2' SAMPLE INTERVAL HAD EXCEEDANCES OF NYSDEC PART 375 UNRESTRICTED USE SCOs (2018 PHASE II EI/2023 RI)
	2' SAMPLE INTERVAL HAD EXCEEDANCES OF NYSDEC PART 375 RESTRICTED RESIDENTIAL USE SCOs (2018 PHASE II EI/2023 RI)
	2' SAMPLE INTERVAL HAD NO EXCEEDANCES OF THE NYSDEC PART 375 UNRESTRICTED USE SCOs (2018 PHASE II EI/2023 RI)
	TRACK 2 REMEDIAL EXCAVATION DEPTH

WARNING: IT IS A VIOLATION OF THE NYS EDUCATION LAW ARTICLE 145 FOR ANY PERSON, UNLESS HE IS ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, LAND SURVEYOR OR GEOLOGIST, TO ALTER THIS ITEM IN ANY WAY.

LANGAN
Langan Engineering, Environmental, Surveying, Landscape Architecture and Geology, D.P.C.
300 Kimball Drive
Parsippany, NJ 07054
T: 973.560.4900 F: 973.560.4901 www.langan.com
NJ Certification of Authorization No. 24GA27996400

Project
12074 FLATLANDS AVENUE SITE
BCP SITE NO. C224353
35 INSPIRATION LANE
F/K/A 12074 FLATLANDS AVENUE
BLOCK NO. 4434, LOT NO. 1
BROOKLYN
KINGS COUNTY NEW YORK

Drawing Title
REMEDIAL EXCAVATION EXTENTS - SUBSURFACE PROFILES A-A', B-B', & C-C'

Project No.	Figure
100688801	3C
Date: 5/21/2026	
Scale: N/A	
Drawn By: RDB	

© 2026 Langan

Path: \\Langan.com\data\PAR\data\100688801\Project Data\ArcGIS\APRX\Christian Cultural Center_Overview



Location	PE11
Sample Name	PE11_16.5
Sample Date	08/13/2025
Sample Elevation	16.5
VOCs	
Acetone	<0.0067 U
SVOCs	
3,3,4 Methylphenol (m&p Cresol)	<0.0888 U
Benzo(a)anthracene	<0.0888 U
Benzo(a)pyrene	<0.0888 U
Benzo(b)fluoranthene	<0.0888 U
Benzo(g,h,i)Perylene	<0.0888 U
Benzo(k)fluoranthene	<0.0888 U
Chrysene	<0.0888 U
Dibenz(a,h)anthracene	<0.0888 U
Dibenzofuran	<0.0888 U
Indeno(1,2,3-cd)pyrene	<0.0888 U
Phenanthrene	<0.0888 U
Pesticides	
4,4'-DDD	<0.00176 U
4,4'-DDE	<0.00176 U
4,4'-DDT	<0.00176 U
Alpha Chlordane	<0.00176 U
Dieldrin	<0.00176 U
PCBs	
Total PCBs	0.0299
Metals	
Arsenic	1.52
Barium	16.2
Cadmium	<0.267 U
Chromium, Trivalent	8.15
Copper	9.19
Cyanide	<0.535 U
Lead	8.71 J
Manganese	290
Mercury	<0.0321 U
Nickel	16.9
Selenium	<2.23 U
Silver	<0.449 U
Zinc	29
PFAS	
Perfluorooctanesulfonic Acid (PFOS)	<0.000196 U
Perfluorooctanoic Acid (PFOA)	<0.000213 U

Location	PE03
Sample Name	PE03_15.5
Sample Date	08/15/2025
Sample Elevation	15.5
VOCs	
Acetone	0.03
SVOCs	
3,3,4 Methylphenol (m&p Cresol)	<0.0889 U
Benzo(a)anthracene	<0.0889 U
Benzo(a)pyrene	<0.0889 U
Benzo(b)fluoranthene	<0.0889 U
Benzo(g,h,i)Perylene	<0.0889 U
Benzo(k)fluoranthene	<0.0889 U
Chrysene	<0.0889 U
Dibenz(a,h)anthracene	<0.0889 U
Dibenzofuran	<0.0889 U
Indeno(1,2,3-cd)pyrene	<0.0889 U
Phenanthrene	<0.0889 U
Pesticides	
4,4'-DDD	<0.00172 U
4,4'-DDE	<0.00172 U
4,4'-DDT	<0.00172 U
Alpha Chlordane	<0.00172 U
Dieldrin	<0.00172 U
PCBs	
Total PCBs	<0.0126 U
Metals	
Arsenic	<1.34 U
Barium	13.6
Cadmium	<0.267 U
Chromium, Trivalent	9.22
Copper	8.88 J
Cyanide	<0.535 U
Lead	3.19 J
Manganese	136
Mercury	<0.0321 U
Nickel	14.1
Selenium	<2.23 U
Silver	<0.449 U
Zinc	47.3
PFAS	
Perfluorooctanesulfonic Acid (PFOS)	0.000169 J
Perfluorooctanoic Acid (PFOA)	<0.000213 U

Location	PE12
Sample Name	PE12_15
Sample Date	07/28/2025
Sample Elevation	15
VOCs	
Acetone	0.026
SVOCs	
3,3,4 Methylphenol (m&p Cresol)	<0.0878 UJ
Benzo(a)anthracene	0.17 J
Benzo(a)pyrene	<0.0878 UJ
Benzo(b)fluoranthene	<0.0878 UJ
Benzo(g,h,i)Perylene	0.0681 J
Benzo(k)fluoranthene	<0.0878 UJ
Chrysene	0.207 J
Dibenz(a,h)anthracene	<0.0878 UJ
Dibenzofuran	<0.0878 UJ
Indeno(1,2,3-cd)pyrene	<0.0878 UJ
Phenanthrene	0.118 J
Pesticides	
4,4'-DDD	<0.00175 UJ
4,4'-DDE	<0.00175 UJ
4,4'-DDT	<0.00175 UJ
Alpha Chlordane	<0.00175 UJ
Dieldrin	<0.00175 UJ
PCBs	
Total PCBs	**1.04 J**
Metals	
Arsenic	2.23
Barium	114
Cadmium	0.306
Chromium, Trivalent	10.6
Copper	19.2
Cyanide	<0.541 U
Lead	**90.4**
Manganese	219
Mercury	0.0444
Nickel	12.4
Selenium	<2.25 U
Silver	<0.454 U
Zinc	**147**
PFAS	
Perfluorooctanesulfonic Acid (PFOS)	<0.0002 U
Perfluorooctanoic Acid (PFOA)	0.000104 J

Location	PE04	PE04
Sample Name	PE04_15	DUP_07212025
Sample Date	07/21/2025	07/21/2025
Sample Elevation	15	15
VOCs		
Acetone	**0.13**	**0.055**
SVOCs		
3,3,4 Methylphenol (m&p Cresol)	<0.092 U	<0.092 U
Benzo(a)anthracene	<0.092 U	<0.092 U
Benzo(a)pyrene	<0.092 U	<0.092 U
Benzo(b)fluoranthene	<0.092 U	<0.092 U
Benzo(g,h,i)Perylene	<0.092 U	<0.092 U
Benzo(k)fluoranthene	<0.092 U	<0.092 U
Chrysene	<0.092 U	<0.092 U
Dibenz(a,h)anthracene	<0.092 U	<0.092 U
Dibenzofuran	<0.092 U	<0.092 U
Indeno(1,2,3-cd)pyrene	<0.092 U	<0.092 U
Phenanthrene	<0.092 U	<0.092 U
Pesticides		
4,4'-DDD	<0.00261 UP	<0.00222 UP
4,4'-DDE	<0.00261 UP	<0.00222 UP
4,4'-DDT	<0.00261 UP	<0.00222 UP
Alpha Chlordane	<0.00261 UP	<0.00222 UP
Dieldrin	<0.00261 UP	<0.00222 UP
PCBs		
Total PCBs	<0.0205 UP	<0.0221 UP
Metals		
Arsenic	**38.5**	10
Barium	226 J	341
Cadmium	**2.95 J**	0.697
Chromium, Trivalent	**40.9**	10.9
Copper	**169**	**60**
Cyanide	<0.951 U	**2.37 J**
Lead	**154 J**	**162 J**
Manganese	**1,720**	227
Mercury	0.17	0.0828
Nickel	**41.6 J**	11.8
Selenium	<3.95 U	<2.81 U
Silver	<0.676 U	0.742
Zinc	**119 J**	**237**
PFAS		
Perfluorooctanesulfonic Acid (PFOS)	0.000705	0.000681
Perfluorooctanoic Acid (PFOA)	0.000182 J	<0.000269 U

Location	PE05
Sample Name	PE05_15
Sample Date	07/28/2025
Sample Elevation	15
VOCs	
Acetone	**0.063**
SVOCs	
3,3,4 Methylphenol (m&p Cresol)	<0.124 U
Benzo(a)anthracene	<0.124 U
Benzo(a)pyrene	<0.124 U
Benzo(b)fluoranthene	<0.124 U
Benzo(g,h,i)Perylene	<0.124 U
Benzo(k)fluoranthene	<0.124 U
Chrysene	<0.124 U
Dibenz(a,h)anthracene	<0.124 U
Dibenzofuran	<0.124 U
Indeno(1,2,3-cd)pyrene	<0.124 U
Phenanthrene	<0.124 U
Pesticides	
4,4'-DDD	<0.00264 UP
4,4'-DDE	<0.00264 UP
4,4'-DDT	<0.00264 UP
Alpha Chlordane	<0.00264 UP
Dieldrin	<0.00264 UP
PCBs	
Total PCBs	<0.0267 UP
Metals	
Arsenic	**13.6**
Barium	180
Cadmium	<0.404 U
Chromium, Trivalent	9.27
Copper	25.3
Cyanide	<0.808 U
Lead	**89.6**
Manganese	247
Mercury	0.178
Nickel	19.9
Selenium	<3.37 U
Silver	<0.679 U
Zinc	**3,070**
PFAS	
Perfluorooctanesulfonic Acid (PFOS)	0.000227 J
Perfluorooctanoic Acid (PFOA)	<0.000321 U

Location	PE13
Sample Name	PE13_15
Sample Date	07/21/2025
Sample Elevation	15
VOCs	
Acetone	**0.067**
SVOCs	
3,3,4 Methylphenol (m&p Cresol)	<0.133 U
Benzo(a)anthracene	<0.133 U
Benzo(a)pyrene	<0.133 U
Benzo(b)fluoranthene	<0.133 U
Benzo(g,h,i)Perylene	<0.133 U
Benzo(k)fluoranthene	<0.133 U
Chrysene	<0.133 U
Dibenz(a,h)anthracene	<0.133 U
Dibenzofuran	<0.133 U
Indeno(1,2,3-cd)pyrene	<0.133 U
Phenanthrene	<0.133 U
Pesticides	
4,4'-DDD	<0.00261 UP
4,4'-DDE	<0.00261 UP
4,4'-DDT	<0.00261 UP
Alpha Chlordane	<0.00261 UP
Dieldrin	<0.00261 UP
PCBs	
Total PCBs	<0.0205 UP
Metals	
Arsenic	10.1
Barium	**718**
Cadmium	0.8
Chromium, Trivalent	18.9
Copper	**776**
Cyanide	<0.96 U
Lead	**747**
Manganese	117
Mercury	**0.235**
Nickel	19.4
Selenium	<4 U
Silver	1.5
Zinc	**221**
PFAS	
Perfluorooctanesulfonic Acid (PFOS)	<0.000357 U
Perfluorooctanoic Acid (PFOA)	<0.000384 U

Location	PE06
Sample Name	PE06_15
Sample Date	07/21/2025
Sample Elevation	15
VOCs	
Acetone	**0.046**
SVOCs	
3,3,4 Methylphenol (m&p Cresol)	<0.16 U
Benzo(a)anthracene	<0.16 U
Benzo(a)pyrene	<0.16 U
Benzo(b)fluoranthene	<0.16 U
Benzo(g,h,i)Perylene	<0.16 U
Benzo(k)fluoranthene	<0.16 U
Chrysene	<0.16 U
Dibenz(a,h)anthracene	<0.16 U
Dibenzofuran	<0.16 U
Indeno(1,2,3-cd)pyrene	<0.16 U
Phenanthrene	<0.16 U
Pesticides	
4,4'-DDD	<0.00316 UP
4,4'-DDE	<0.00316 UP
4,4'-DDT	<0.00316 UP
Alpha Chlordane	<0.00316 UP
Dieldrin	<0.00316 UP
PCBs	
Total PCBs	<0.0318 UP
Metals	
Arsenic	10.9
Barium	357
Cadmium	0.98
Chromium, Trivalent	12.9
Copper	**60.3**
Cyanide	0.72 J
Lead	**316 J**
Manganese	161
Mercury	0.104
Nickel	18.7
Selenium	<2.85 U
Silver	<0.576 U
Zinc	**365**
PFAS	
Perfluorooctanesulfonic Acid (PFOS)	0.000241 J
Perfluorooctanoic Acid (PFOA)	0.000161 J

Location	PE07
Sample Name	PE07_15
Sample Date	07/21/2025
Sample Elevation	15
VOCs	
Acetone	**0.057**
SVOCs	
3,3,4 Methylphenol (m&p Cresol)	<0.114 U
Benzo(a)anthracene	<0.114 U
Benzo(a)pyrene	<0.114 U
Benzo(b)fluoranthene	<0.114 U
Benzo(g,h,i)Perylene	<0.114 U
Benzo(k)fluoranthene	<0.114 U
Chrysene	<0.114 U
Dibenz(a,h)anthracene	<0.114 U
Dibenzofuran	<0.114 U
Indeno(1,2,3-cd)pyrene	<0.114 U
Phenanthrene	<0.114 U
Pesticides	
4,4'-DDD	<0.00225 UP
4,4'-DDE	<0.00225 UP
4,4'-DDT	<0.00225 UP
Alpha Chlordane	<0.00225 UP
Dieldrin	<0.00225 UP
PCBs	
Total PCBs	<0.0225 UP
Metals	
Arsenic	10.9
Barium	357
Cadmium	0.98
Chromium, Trivalent	12.9
Copper	**60.3**
Cyanide	0.72 J
Lead	**316 J**
Manganese	161
Mercury	0.104
Nickel	18.7
Selenium	<2.85 U
Silver	<0.576 U
Zinc	**365**
PFAS	
Perfluorooctanesulfonic Acid (PFOS)	0.000241 J
Perfluorooctanoic Acid (PFOA)	0.000161 J

Location	PE08
Sample Name	PE08_15
Sample Date	07/14/2025
Sample Elevation	15
VOCs	
Acetone	0.026
SVOCs	
3,3,4 Methylphenol (m&p Cresol)	<0.0988 U
Benzo(a)anthracene	<0.0988 U
Benzo(a)pyrene	<0.0988 U
Benzo(b)fluoranthene	<0.0988 U
Benzo(g,h,i)Perylene	<0.0988 U
Benzo(k)fluoranthene	<0.0988 U
Chrysene	<0.0988 U
Dibenz(a,h)anthracene	<0.0988 U
Dibenzofuran	<0.0988 U
Indeno(1,2,3-cd)pyrene	<0.0988 U
Phenanthrene	<0.0988 U
Pesticides	
4,4'-DDD	<0.00193 UP
4,4'-DDE	<0.00193 UP
4,4'-DDT	<0.00193 UP
Alpha Chlordane	<0.00193 UP
Dieldrin	<0.00193 UP
PCBs	
Total PCBs	<0.0195 UP
Metals	
Arsenic	<1.49 U
Barium	11
Cadmium	<0.297 U
Chromium, Trivalent	16.9
Copper	8.13
Cyanide	<0.594 U
Lead	4.7
Manganese	54.6
Mercury	<0.0257 U
Nickel	12.6
Selenium	<2.48 U
Silver	<0.499 U
Zinc	14
PFAS	
Perfluorooctanesulfonic Acid (PFOS)	<0.00022 U
Perfluorooctanoic Acid (PFOA)	<0.000237 U

Location	PE14
Sample Name	PE14_15
Sample Date	07/21/2025
Sample Elevation	15
VOCs	
Acetone	**0.078**
SVOCs	
3,3,4 Methylphenol (m&p Cresol)	<0.111 U
Benzo(a)anthracene	0.0857 JD
Benzo(a)pyrene	<0.111 U
Benzo(b)fluoranthene	<0.111 U
Benzo(g,h,i)Perylene	<0.111 U
Benzo(k)fluoranthene	<0.111 U
Chrysene	0.0960 JD
Dibenz(a,h)anthracene	<0.111 U
Dibenzofuran	<0.111 U
Indeno(1,2,3-cd)pyrene	<0.111 U
Phenanthrene	0.061 JD
Pesticides	
4,4'-DDD	<0.00233 UJ
4,4'-DDE	<0.00233 UJ
4,4'-DDT	<0.00233 UJ
Alpha Chlordane	<0.00233 UJ
Dieldrin	<0.00233 UJ
PCBs	
Total PCBs	**0.151 P**
Metals	
Arsenic	10.1
Barium	**618**
Cadmium	1.31
Chromium, Trivalent	18.9
Copper	**88.6**
Cyanide	<0.677 U
Lead	**381**
Manganese	196
Mercury	**0.183**
Nickel	14.6
Selenium	<2.82 U
Silver	<0.568 U
Zinc	**375**
PFAS	
Perfluorooctanesulfonic Acid (PFOS)	<0.000252 U
Perfluorooctanoic Acid (PFOA)	0.000139 J

Location	PE16
Sample Name	PE16_15
Sample Date	07/14/2025
Sample Elevation	15
VOCs	
Acetone	0.025
SVOCs	
3,3,4 Methylphenol (m&p Cresol)	<0.0934 U
Benzo(a)anthracene	<0.0934 U
Benzo(a)pyrene	<0.0934 U
Benzo(b)fluoranthene	<0.0934 U
Benzo(g,h,i)Perylene	<0.0934 U
Benzo(k)fluoranthene	<0.0934 U
Chrysene	<0.0934 U
Dibenz(a,h)anthracene	<0.0934 U
Dibenzofuran	<0.0934 U
Indeno(1,2,3-cd)pyrene	<0.0934 U
Phenanthrene	<0.0934 U
Pesticides	
4,4'-DDD	<0.00182 UP
4,4'-DDE	<0.00182 UP
4,4'-DDT	<0.00182 UP
Alpha Chlordane	<0.00182 UP
Dieldrin	<0.00182 UP
PCBs	
Total PCBs	<0.0184 UP
Metals	
Arsenic	1.83
Barium	6.96
Cadmium	<0.241 U
Chromium, Trivalent	14.1
Copper	8.99
Cyanide	<0.562 U
Lead	3.42
Manganese	48.6
Mercury	<0.0337 U
Nickel	14.9
Selenium	<2.34 U
Silver	<0.472 U
Zinc	13.1
PFAS	
Perfluorooctanesulfonic Acid (PFOS)	<0.000208 U
Perfluorooctanoic Acid (PFOA)	<0.000223 U

Location	PE24
Sample Name	PE24_16.5
Sample Date	07/14/2025
Sample Elevation	16.5
VOCs	
Acetone	**0.11**
SVOCs	
3,3,4 Methylphenol (m&p Cresol)	<0.128 U
Benzo(a)anthracene	0.0972 JD
Benzo(a)pyrene	0.0952 JD
Benzo(b)fluoranthene	0.123 JD
Benzo(g,h,i)Perylene	<0.128 U
Benzo(k)fluoranthene	<0.128 U
Chrysene	0.0891 JD
Dibenz(a,h)anthracene	<0.128 U
Dibenzofuran	<0.128 U
Indeno(1,2,3-cd)pyrene	<0.128 U
Phenanthrene	0.113 JD
Pesticides	
4,4'-DDD	<0.00251 UP
4,4'-DDE	<0.00251 UP
4,4'-DDT	<0.00251 UP
Alpha Chlordane	<0.00251 UP
Dieldrin	<0.00251 UP
PCBs	
Total PCBs	**0.968 P**
Metals	
Arsenic	8.59
Barium	**772**
Cadmium	1.09
Chromium, Trivalent	18.1
Copper	**81**
Cyanide	<0.77 U
Lead	**606**
Manganese	96.6
Mercury	**0.523**
Nickel	16.3
Selenium	<3.21 U
Silver	0.68
Zinc	**488**
PFAS	
Perfluorooctanesulfonic Acid (PFOS)	<0.000284 U
Perfluorooctanoic Acid (PFOA)	<0.000306 U

Location	PE15
Sample Name	PE15_23.5
Sample Date	07/21/2025
Sample Elevation	23.5
VOCs	
Acetone	**0.045**
SVOCs	
3,3,4 Methylphenol (m&p Cresol)	<0.118 U
Benzo(a)anthracene	<0.118 U
Benzo(a)pyrene	<0.118 U
Benzo(b)fluoranthene	<0.118 U
Benzo(g,h,i)Perylene	<0.118 U
Benzo(k)fluoranthene	<0.118 U
Chrysene	<0.118 U
Dibenz(a,h)anthracene	<0.118 U
Dibenzofuran	<0.118 U
Indeno(1,2,3-cd)pyrene	<0.118 U
Phenanthrene	<0.118 U
Pesticides	
4,4'-DDD	<0.00233 UP
4,4'-DDE	<0.00233 UP
4,4'-DDT	<0.00233 UP
Alpha Chlordane	<0.00233 UP
Dieldrin	<0.00233 UP
PCBs	
Total PCBs	<0.0234 UP
Metals	
Arsenic	10.8
Barium	256
Cadmium	1.33
Chromium, Trivalent	**32.8**
Copper	**68.9**
Cyanide	<0.707 U
Lead	**2,370**
Manganese	148
Mercury	**20.8 D**
Nickel	15.9
Selenium	<2.95 U
Silver	<0.594 U
Zinc	**191**
PFAS	
Perfluorooctanesulfonic Acid (PFOS)	<0.000263 U
Perfluorooctanoic Acid (PFOA)	0.000105 J

Location	PE18
Sample Name	PE18_15
Sample Date	06/19/2025
Sample Elevation	15
VOCs	
Acetone	**0.031**
SVOCs	
3,3,4 Methylphenol (m&p Cresol)	<0.0885 U
Benzo(a)anthracene	<0.0885 U
Benzo(a)pyrene	<0.0885 U
Benzo(b)fluoranthene	<0.0885 U
Benzo(g,h,i)Perylene	<0.0885 U
Benzo(k)fluoranthene	<0.0885 U
Chrysene	<0.0885 U
Dibenz(a,h)anthracene	<0.0885 U
Dibenzofuran	<0.0885 U
Indeno(1,2,3-cd)pyrene	<0.0885 U
Phenanthrene	<0.0885 U
Pesticides	
4,4'-DDD	<0.00179 U
4,4'-DDE	<0.00179 U
4,4'-DDT	<0.00179 U
Alpha Chlordane	<0.00179 U
Dieldrin	<0.00179 U
PCBs	
Total PCBs	<0.018 U
Metals	
Arsenic	1.4
Barium	12
Cadmium	<0.272 U
Chromium, Trivalent	8.13
Copper	9.66
Cyanide	<0.543 U
Lead	2.44
Manganese	160
Mercury	<0.0326 U
Nickel	14.3
Selenium	<2.26 U
Silver	<0.456 U
Zinc	18
PFAS	
Perfluorooctanesulfonic Acid (PFOS)	<0.000201 U
Perfluorooctanoic Acid (PFOA)	<0.000216 U

Location	PE17
Sample Name	PE17_15
Sample Date	06/19/2025
Sample Elevation	15
VOCs	
Acetone	0.029
SVOCs	
3,3,4 Methylphenol (m&p Cresol)	<0.0906 U
Benzo(a)anthracene	<0.0906 U
Benzo(a)pyrene	<0.0906 U
Benzo(b)fluoranthene	<0.0906 U
Benzo(g,h,i)Perylene	<0.0906 U
Benzo(k)fluoranthene	<0.0906 U
Chrysene	<0.0906 U
Dibenz(a,h)anthracene	<0.0906 U
Dibenzofuran	<0.0906 U
Indeno(1,2,3-cd)pyrene	<0.0906 U
Phenanthrene	<0.0906 U
Pesticides	
4,4'-DDD	<0.00176 U
4,4'-DDE	<0.00176 U
4,4'-DDT	<0.00176 U
Alpha Chlordane	<0.00176 U
Dieldrin	<0.00176 U
PCBs	
Total PCBs	<0.0177 U
Metals	
Arsenic	<1.36 U
Barium	11.5
Cadmium	<0.272 U
Chromium, Trivalent	8.12
Copper	7.63
Cyanide	<0.545 U
Lead	2.04
Manganese	103
Mercury	<0.0327 U
Nickel	12.8
Selenium	<2.27 U
Silver	<0.458 U
Zinc	12
PFAS	
Perfluorooctanesulfonic Acid (PFOS)	<0.000202 U
Perfluorooctanoic Acid (PFOA)	<0.000217 U

Location	PE26
Sample Name	PE26_15
Sample Date	06/19/2025
Sample Elevation	15
VOCs	
Acetone	<0.011 U
SVOCs	
3,3,4 Methylphenol (m&p Cresol)	<0.092 U
Benzo(a)anthracene	<0.092 U
Benzo(a)pyrene	<0.092 U
Benzo(b)fluoranthene	<0.092 U
Benzo(g,h,i)Perylene	<0.092 U
Benzo(k)fluoranthene	<0.092 U
Chrysene	<0.092 U
Dibenz(a,h)anthracene	<0.092 U
Dibenzofuran	<0.092 U
Indeno(1,2,3-cd)pyrene	<0.092 U
Phenanthrene	<0.092 U
Pesticides	
4,4'-DDD	<0.00181 U
4,4'-DDE	<0.00181 U
4,4'-DDT	<0.00181 U
Alpha Chlordane	<0.00181 U
Dieldrin	<0.00181 U
PCBs	
Total PCBs	<0.0183 U
Metals	
Arsenic	1.59
Barium	14.4
Cadmium	<0.279 U
Chromium, Trivalent	9.63
Copper	11.2
Cyanide	<0.557 U
Lead	10.4
Manganese	193
Mercury	<0.0334 U
Nickel	14.6
Selenium	<2.32 U
Silver	<0.468 U
Zinc	21.4
PFAS	
Perfluorooctanesulfonic Acid (PFOS)	<0.000207 U
Perfluorooctanoic Acid (PFOA)	<0.000222 U

Location	PE01
Sample Name	PE01_8
Sample Date	06/18/2025
Sample Elevation	8
VOCs	
Acetone	<0.012 U
SVOCs	
3,3,4 Methylphenol (m&p Cresol)	<0.0938 U
Benzo(a)anthracene	0.254 D
Benzo(a)pyrene	0.241 D
Benzo(b)fluoranthene	0.244 D
Benzo(g,h,i)Perylene	0.142 D
Benzo(k)fluoranthene	0.0984 JD
Chrysene	0.251 D
Dibenz(a,h)anthracene	<0.0938 U
Dibenzofuran	<0.0938 U
Indeno(1,2,3-cd)pyrene	0.14 D
Phenanthrene	0.444 D
Pesticides	
4,4'-DDD	<0.00186 U
4,4'-DDE	<0.00186 U
4,4'-DDT	<0.00186 U
Alpha Chlordane	<0.00186 U
Dieldrin	<0.00186 U
PCBs	
Total PCBs	<0.0188 U
Metals	
Arsenic	4.6
Barium	42.3
Cadmium	<0.284 U
Chromium, Trivalent	11.4
Copper	25.6
Cyanide	<0.568 U
Lead	51.4
Manganese	122
Mercury	0.0986
Nickel	14.4
Selenium	<2.39 U
Silver	<0.477 U
Zinc	73.5
PFAS	
Perfluorooctanesulfonic Acid (PFOS)	0.0007 J
Perfluorooctanoic Acid (PFOA)	<0.000225 U

Location	PE09
Sample Name	PE09_15
Sample Date	06/19/2025
Sample Elevation	15
VOCs	
Acetone	**0.033**
SVOCs	
3,3,4 Methylphenol (m&p Cresol)	<0.0971 U
Benzo(a)anthracene	<0.0971 U
Benzo(a)pyrene	<0.0971 U
Benzo(b)fluoranthene	<0.0971 U
Benzo(g,h,i)Perylene	<0.0971 U
Benzo(k)fluoranthene	<0.0971 U
Chrysene	<0.0971 U
Dibenz(a,h)anthracene	<0.0971 U
Dibenzofuran	<0.0971 U
Indeno(1,2,3-cd)pyrene	<0.0971 U
Phenanthrene	<0.0971 U
Pesticides	
4,4'-DDD	<0.00192 U
4,4'-DDE	<0.00192 U
4,4'-DDT	<0.00192 U
Alpha Chlordane	<0.00192 U
Dieldrin	<0.00192 U
PCBs	
Total PCBs	<0.0193 U
Metals	
Arsenic	1.59
Barium	174
Cadmium	0.428
Chromium, Trivalent	8.84
Copper	19.4
Cyanide	<0.594 U
Lead	21.3
Manganese	144
Mercury	<0.0351 U
Nickel	15.5
Selenium	<2.43 U
Silver	<0.491 U
Zinc	29.2
PFAS	
Perfluorooctanesulfonic Acid (PFOS)	<0.000216 U
Perfluorooctanoic Acid (PFOA)	<0.000233 U

Location	PE19
Sample Name	PE19_15.5
Sample Date	08/08/2025
Sample Elevation	15.5
VOCs	
Acetone	**0.061**
SVOCs	
3,3,4 Methylphenol (m&p Cresol)	<0.102 U
Benzo(a)anthracene	0.108 D
Benzo(a)pyrene	0.11 D
Benzo(b)fluoranthene	0.0817 JD
Benzo(g,h,i)Perylene	0.0727 JD
Benzo(k)fluoranthene	0.0841 JD
Chrysene	0.0939 JD
Dibenz(a,h)anthracene	<0.102 U
Dibenzofuran	<0.102 U
Indeno(1,2,3-cd)pyrene	0.0678 JD
Phenanthrene	0.105 D
Pesticides	
4,4'-DDD	<0.00203 UP
4,4'-DDE	<0.00203 UP
4,4'-DDT	<0.00203 UP
Alpha Chlordane	<0.00203 UP
Dieldrin	<0.00203 UP
PCBs	
Total PCBs	0.0302 P
Metals	
Arsenic	8.25
Barium	155
Cadmium	0.639
Chromium, Trivalent	12.2
Copper	**70.3**
Cyanide	<0.619 U
Lead	**290**
Manganese	157
Mercury	0.089
Nickel	215
Selenium	<2.58 U
Silver	<0.52 U
Zinc	**177**
PFAS	
Perfluorooctanesulfonic Acid (PFOS)	<0.00023 U
Perfluorooctanoic Acid (PFOA)	0.000142 J

Location	PE27
Sample Name	PE27_17
Sample Date	08/11/2025
Sample Elevation	17
VOCs	
Acetone	<0.0957 U
SVOCs	
3,3,4 Methylphenol (m&p Cresol)	<0.0957 U
Benzo(a)anthracene	0.324 J
Benzo(a)pyrene	0.251 J
Benzo(b)fluoranthene	0.548 J
Benzo(g,h,i)Perylene	0.187 J
Benzo(k)fluoranthene	<0.0957 U
Chrysene	0.375 J
Dibenz(a,h)anthracene	<0.0957 U
Dibenzofuran	<0.0957 U
Indeno(1,2,3-cd)pyrene	0.185 J
Phenanthrene	0.278 J
Pesticides	
4,4'-DDD	**0.0202 DP**
4,4'-DDE	<0.00191 U
4,4'-DDT	<0.00191 U
Alpha Chlordane	<0.00191 UP
Dieldrin	<0.00191 UP
PCBs	
Total PCBs	**0.648 J**
Metals	
Arsenic	11.3
Barium	**490**
Cadmium	**4.85**
Chromium, Trivalent	20.6
Copper	**146**
Cyanide	<0.589 U
Lead	**586**
Manganese	216
Mercury	**0.372**
Nickel	28.8
Selenium	<2.45 U
Silver	0.795
Zinc	**1,200**
PFAS	
Perfluorooctanesulfonic Acid (PFOS)	<0.000219 U
Perfluorooctanoic Acid (PFOA)	0.000197 J

Location	PE20	PE20
Sample Name	PE20_15.5	DUP_07282025
Sample Date	07/28/2025	07/28/2025
Sample Elevation	15.5	15.5
VOCs		
Acetone	**0.066**	**0.047**
SVOCs		
3,3,4 Meth

Block: 4411
Lot: 34

Block: 4412
Lot: 29

Block: 4435
Lot: 100

Block: 4435
Lot: 1

Block: 4434
Lot: 10

Block: 4434
Lot: 1

Block: 4434
Lot: 100

Block: 4434
Lot: 60

Block: 4431
Lot: 70

Block: 4452
Lot: 1

Lot: 75

Location	PE44
Sample Name	PE44_19.5
Sample Date	08/28/2025
Sample Elevation	19.5
VOCs	
Acetone	**0.041**
SVOCs	
3 & 4 Methylphenol (m&p Cresol)	<0.09 U
Benzo(a)anthracene	<0.09 U
Benzo(a)pyrene	<0.09 U
Benzo(b)fluoranthene	<0.09 U
Benzo(g,h,i)Perylene	<0.09 U
Benzo(k)fluoranthene	<0.09 U
Chrysene	<0.09 U
Dibenz(a,h)anthracene	<0.09 U
Dibenzofuran	<0.09 U
Indeno(1,2,3-cd)pyrene	<0.09 U
Phenanthrene	<0.09 U
Pesticides	
4,4'-DDD	<0.00177 UP
4,4'-DDE	<0.00177 UP
4,4'-DDT	<0.00177 UP
Alpha Chlordane	<0.00177 UP
Dieldrin	<0.00177 UP
PCBs	
Total PCBs	<0.0179 UP
Metals	
Arsenic	1.37
Barium	278
Cadmium	0.271
Chromium, Trivalent	12.5
Copper	11.8
Cyanide	<0.541 U
Lead	28.4
Manganese	49.7
Mercury	<0.0325 U
Nickel	13
Selenium	<2.26 U
Silver	<0.455 U
Zinc	105
PFAS	
Perfluorooctanesulfonic Acid (PFOS)	<0.000201 U
Perfluorooctanoic Acid (PFOA)	<0.000216 U

Location	PE36
Sample Name	PE36_18.5
Sample Date	07/29/2025
Sample Elevation	18.5
VOCs	
Acetone	**0.12 J**
SVOCs	
3 & 4 Methylphenol (m&p Cresol)	<0.104 U
Benzo(a)anthracene	<0.104 U
Benzo(a)pyrene	<0.104 U
Benzo(b)fluoranthene	<0.104 U
Benzo(g,h,i)Perylene	<0.104 U
Benzo(k)fluoranthene	<0.104 U
Chrysene	<0.104 U
Dibenz(a,h)anthracene	<0.104 U
Dibenzofuran	<0.104 U
Indeno(1,2,3-cd)pyrene	<0.104 U
Phenanthrene	<0.104 U
Pesticides	
4,4'-DDD	<0.00202 UP
4,4'-DDE	<0.00202 UP
4,4'-DDT	<0.00202 UP
Alpha Chlordane	<0.00202 UP
Dieldrin	<0.00202 UP
PCBs	
Total PCBs	<0.0206 UP
Metals	
Arsenic	**16 J**
Barium	**447 J**
Cadmium	0.626 J
Chromium, Trivalent	16
Copper	413 J
Cyanide	0.984
Lead	**237 J**
Manganese	171 J
Mercury	0.149
Nickel	9.71 J
Selenium	<2.61 U
Silver	<0.525 U
Zinc	**324 J**
PFAS	
Perfluorooctanesulfonic Acid (PFOS)	0.000343
Perfluorooctanoic Acid (PFOA)	0.000232 J

Location	PE45	PE45
Sample Name	PE45_19.5	DUP_08262025
Sample Date	08/26/2025	08/26/2025
Sample Elevation	19.5	19.5
VOCs		
Acetone	**0.35 J**	0.024 J
SVOCs		
3 & 4 Methylphenol (m&p Cresol)	<0.126 U	<0.122 U
Benzo(a)anthracene	<0.126 U	0.499 J
Benzo(a)pyrene	<0.126 U	0.439 J
Benzo(b)fluoranthene	<0.126 U	0.392 D
Benzo(g,h,i)Perylene	<0.126 U	0.236 D
Benzo(k)fluoranthene	<0.126 U	0.434 J
Chrysene	<0.126 U	0.525 J
Dibenz(a,h)anthracene	<0.126 U	<0.122 U
Dibenzofuran	<0.126 U	<0.122 U
Indeno(1,2,3-cd)pyrene	<0.126 U	0.21 D
Phenanthrene	<0.126 U	0.405 J
Pesticides		
4,4'-DDD	<0.00249 UJ	**0.00814 J**
4,4'-DDE	<0.00249 UP	<0.00265 UP
4,4'-DDT	<0.00249 UP	<0.00265 UP
Alpha Chlordane	<0.00249 UP	0.00269 DP
Dieldrin	<0.00249 UP	<0.00265 UP
PCBs		
Total PCBs	<0.0251 U	**0.319 J**
Metals		
Arsenic	11	11.2 J
Barium	**813**	**615 J**
Cadmium	1.1	1.85
Chromium, Trivalent	19.7	19.5
Copper	**162**	**98.9 J**
Cyanide	**13.7 J**	**7.47 J**
Lead	**1,090**	**720**
Manganese	184	183 J
Mercury	**0.817 J**	**0.451 J**
Nickel	23.4	19.7
Selenium	<3.15 U	<3.37 U
Silver	0.895	1.34 J
Zinc	**376**	**569**
PFAS		
Perfluorooctanesulfonic Acid (PFOS)	<0.00028 UJ	<0.000301 UJ
Perfluorooctanoic Acid (PFOA)	0.000212 J	0.000298 J

Location	PE37
Sample Name	PE37_19
Sample Date	07/24/2025
Sample Elevation	19
VOCs	
Acetone	**0.14**
SVOCs	
3 & 4 Methylphenol (m&p Cresol)	<0.113 U
Benzo(a)anthracene	<0.113 U
Benzo(a)pyrene	<0.113 U
Benzo(b)fluoranthene	<0.113 U
Benzo(g,h,i)Perylene	<0.113 U
Benzo(k)fluoranthene	<0.113 U
Chrysene	<0.113 U
Dibenz(a,h)anthracene	<0.113 U
Dibenzofuran	<0.113 U
Indeno(1,2,3-cd)pyrene	<0.113 U
Phenanthrene	<0.113 U
Pesticides	
4,4'-DDD	<0.00251 UP
4,4'-DDE	<0.00251 UP
4,4'-DDT	<0.00251 UP
Alpha Chlordane	<0.00251 UP
Dieldrin	<0.00251 UP
PCBs	
Total PCBs	<0.0223 UP
Metals	
Arsenic	7.38
Barium	**711**
Cadmium	0.511
Chromium, Trivalent	14.3
Copper	48.2
Cyanide	<0.592 U
Lead	**255**
Manganese	59.9
Mercury	**0.192**
Nickel	18.1
Selenium	<2.84 U
Silver	0.59
Zinc	**162**
PFAS	
Perfluorooctanesulfonic Acid (PFOS)	<0.000253 U
Perfluorooctanoic Acid (PFOA)	0.000131 J

Location	PE38
Sample Name	PE38_20
Sample Date	08/11/2025
Sample Elevation	20
VOCs	
Acetone	**0.23**
SVOCs	
3 & 4 Methylphenol (m&p Cresol)	<0.102 UJ
Benzo(a)anthracene	0.14 J
Benzo(a)pyrene	0.131 J
Benzo(b)fluoranthene	0.182 J
Benzo(g,h,i)Perylene	0.114 J
Benzo(k)fluoranthene	0.0637 J
Chrysene	0.138 J
Dibenz(a,h)anthracene	<0.102 UJ
Dibenzofuran	<0.102 UJ
Indeno(1,2,3-cd)pyrene	0.105 J
Phenanthrene	0.135 J
Pesticides	
4,4'-DDD	<0.00204 UJ
4,4'-DDE	<0.00204 JP
4,4'-DDT	<0.00204 JP
Alpha Chlordane	<0.00204 JP
Dieldrin	<0.00204 JP
PCBs	
Total PCBs	<0.0206 UP
Metals	
Arsenic	8.62
Barium	**413**
Cadmium	0.944
Chromium, Trivalent	14.4
Copper	49.2
Cyanide	<0.629 U
Lead	**561 J**
Manganese	75.1
Mercury	0.14
Nickel	16.7
Selenium	<2.62 U
Silver	<0.538 U
Zinc	**258 J**
PFAS	
Perfluorooctanesulfonic Acid (PFOS)	<0.000234 U
Perfluorooctanoic Acid (PFOA)	0.000152 J

Location	PE39
Sample Name	PE39_18.5
Sample Date	07/24/2025
Sample Elevation	18.5
VOCs	
Acetone	**0.051**
SVOCs	
3 & 4 Methylphenol (m&p Cresol)	<0.107 U
Benzo(a)anthracene	<0.107 U
Benzo(a)pyrene	<0.107 U
Benzo(b)fluoranthene	<0.107 U
Benzo(g,h,i)Perylene	<0.107 U
Benzo(k)fluoranthene	<0.107 U
Chrysene	<0.107 U
Dibenz(a,h)anthracene	<0.107 U
Dibenzofuran	<0.107 U
Indeno(1,2,3-cd)pyrene	<0.107 U
Phenanthrene	<0.107 U
Pesticides	
4,4'-DDD	<0.00221 UP
4,4'-DDE	<0.00221 UP
4,4'-DDT	<0.00221 UP
Alpha Chlordane	<0.00221 UP
Dieldrin	<0.00221 UP
PCBs	
Total PCBs	<0.0211 UP
Metals	
Arsenic	7.35
Barium	239
Cadmium	0.473
Chromium, Trivalent	11.2
Copper	43.5
Cyanide	<0.645 U
Lead	**222**
Manganese	86.4
Mercury	0.0931
Nickel	13
Selenium	<2.69 U
Silver	0.849
Zinc	**127**
PFAS	
Perfluorooctanesulfonic Acid (PFOS)	<0.000239 U
Perfluorooctanoic Acid (PFOA)	0.000202 J

Location	PE40
Sample Name	PE40_18.5
Sample Date	07/23/2025
Sample Elevation	18.5
VOCs	
Acetone	**0.049**
SVOCs	
3 & 4 Methylphenol (m&p Cresol)	<0.0909 U
Benzo(a)anthracene	0.167 D
Benzo(a)pyrene	0.145 D
Benzo(b)fluoranthene	0.0894 JD
Benzo(g,h,i)Perylene	0.0836 JD
Benzo(k)fluoranthene	0.0945 D
Chrysene	0.197 D
Dibenz(a,h)anthracene	<0.0909 U
Dibenzofuran	<0.0909 U
Indeno(1,2,3-cd)pyrene	0.0843 JD
Phenanthrene	0.618 D
Pesticides	
4,4'-DDD	<0.00178 UP
4,4'-DDE	<0.00178 UP
4,4'-DDT	<0.00178 UP
Alpha Chlordane	<0.00178 UP
Dieldrin	<0.00178 UP
PCBs	
Total PCBs	<0.0179 UP
Metals	
Arsenic	2.34
Barium	20
Cadmium	<0.273 U
Chromium, Trivalent	12
Copper	12.7
Cyanide	<0.547 U
Lead	**287**
Manganese	128
Mercury	<0.0239 U
Nickel	176
Selenium	<2.28 U
Silver	<0.459 U
Zinc	38.3
PFAS	
Perfluorooctanesulfonic Acid (PFOS)	<0.000203 U
Perfluorooctanoic Acid (PFOA)	<0.000218 U

Location	PE48
Sample Name	PE48_19
Sample Date	08/27/2025
Sample Elevation	19
VOCs	
Acetone	**0.17**
SVOCs	
3 & 4 Methylphenol (m&p Cresol)	<0.118 U
Benzo(a)anthracene	<0.118 U
Benzo(a)pyrene	<0.118 U
Benzo(b)fluoranthene	<0.118 U
Benzo(g,h,i)Perylene	<0.118 U
Benzo(k)fluoranthene	<0.118 U
Chrysene	<0.118 U
Dibenz(a,h)anthracene	<0.118 U
Dibenzofuran	<0.118 U
Indeno(1,2,3-cd)pyrene	<0.118 U
Phenanthrene	<0.118 U
Pesticides	
4,4'-DDD	<0.00236 UP
4,4'-DDE	<0.00236 UP
4,4'-DDT	<0.00236 UP
Alpha Chlordane	<0.00236 UP
Dieldrin	<0.00236 UP
PCBs	
Total PCBs	<0.0238 UP
Metals	
Arsenic	**18.1**
Barium	**620**
Cadmium	0.897
Chromium, Trivalent	21.2
Copper	**64.7**
Cyanide	<0.718 U
Lead	**379**
Manganese	410
Mercury	**0.243**
Nickel	22.2
Selenium	<2.99 U
Silver	<0.603 U
Zinc	**472**
PFAS	
Perfluorooctanesulfonic Acid (PFOS)	<0.000266 UJ
Perfluorooctanoic Acid (PFOA)	0.000226 J

Location	PE47
Sample Name	PE47_19.5
Sample Date	08/27/2025
Sample Elevation	19.5
VOCs	
Acetone	**0.17 J**
SVOCs	
3 & 4 Methylphenol (m&p Cresol)	<0.112 U
Benzo(a)anthracene	<0.112 U
Benzo(a)pyrene	<0.112 U
Benzo(b)fluoranthene	<0.112 U
Benzo(g,h,i)Perylene	<0.112 U
Benzo(k)fluoranthene	<0.112 U
Chrysene	<0.112 U
Dibenz(a,h)anthracene	<0.112 U
Dibenzofuran	<0.112 U
Indeno(1,2,3-cd)pyrene	<0.112 U
Phenanthrene	<0.112 U
Pesticides	
4,4'-DDD	<0.00223 UP
4,4'-DDE	<0.00223 UP
4,4'-DDT	<0.00223 UP
Alpha Chlordane	<0.00223 UP
Dieldrin	<0.00223 UP
PCBs	
Total PCBs	<0.0225 UP
Metals	
Arsenic	11.8
Barium	**417**
Cadmium	1.58
Chromium, Trivalent	16.3
Copper	**975**
Cyanide	<0.678 U
Lead	**1,140**
Manganese	111
Mercury	0.116
Nickel	13
Selenium	<2.83 U
Silver	1.15
Zinc	**474**
PFAS	
Perfluorooctanesulfonic Acid (PFOS)	<0.000253 U
Perfluorooctanoic Acid (PFOA)	0.000322 J

Location	PE55
Sample Name	PE55_20
Sample Date	08/27/2025
Sample Elevation	20
VOCs	
Acetone	**0.097**
SVOCs	
3 & 4 Methylphenol (m&p Cresol)	<0.116 U
Benzo(a)anthracene	**4.99 D**
Benzo(a)pyrene	**2.96 D**
Benzo(b)fluoranthene	**3.03 D**
Benzo(g,h,i)Perylene	**1.86 D**
Benzo(k)fluoranthene	**2.33 D**
Chrysene	**4.99 D**
Dibenz(a,h)anthracene	**0.54 D**
Dibenzofuran	0.861 D
Indeno(1,2,3-cd)pyrene	**1.52 D**
Phenanthrene	**12 D**
Pesticides	
4,4'-DDD	<0.00229 UP
4,4'-DDE	<0.00229 UP
4,4'-DDT	<0.00229 UP
Alpha Chlordane	<0.00229 UP
Dieldrin	<0.00229 UP
PCBs	
Total PCBs	<0.0231 UP
Metals	
Arsenic	**16.9**
Barium	**596**
Cadmium	0.957
Chromium, Trivalent	13.5
Copper	**65**
Cyanide	<0.7 U
Lead	**401**
Manganese	107
Mercury	**1.76**
Nickel	177
Selenium	<2.92 U
Silver	0.63
Zinc	**706**
PFAS	
Perfluorooctanesulfonic Acid (PFOS)	<0.000261 U
Perfluorooctanoic Acid (PFOA)	0.000224 J

Location	PE35
Sample Name	PE35_18.5
Sample Date	08/11/2025
Sample Elevation	18.5
VOCs	
Acetone	**0.086**
SVOCs	
3 & 4 Methylphenol (m&p Cresol)	<0.107 U
Benzo(a)anthracene	0.105 J
Benzo(a)pyrene	0.07 J
Benzo(b)fluoranthene	0.132 J
Benzo(g,h,i)Perylene	0.0697 J
Benzo(k)fluoranthene	0.0597 J
Chrysene	0.109 J
Dibenz(a,h)anthracene	<0.107 U
Dibenzofuran	<0.107 U
Indeno(1,2,3-cd)pyrene	0.07 J
Phenanthrene	0.142 J
Pesticides	
4,4'-DDD	<0.00213 UP
4,4'-DDE	<0.00213 UP
4,4'-DDT	<0.00213 UP
Alpha Chlordane	<0.00213 UP
Dieldrin	<0.00213 UP
PCBs	
Total PCBs	<0.0215 UP
Metals	
Arsenic	**24.7**
Barium	**452**
Cadmium	0.964
Chromium, Trivalent	**19.6**
Copper	**573**
Cyanide	<0.657 U
Lead	**295**
Manganese	269
Mercury	**0.668**
Nickel	20.5
Selenium	<2.74 U
Silver	<0.552 U
Zinc	**231**
PFAS	
Perfluorooctanesulfonic Acid (PFOS)	<0.000244 U
Perfluorooctanoic Acid (PFOA)	0.000383

Location	PE34
Sample Name	PE34_20
Sample Date	08/19/2025
Sample Elevation	20
VOCs	
Acetone	**0.031**
SVOCs	
3 & 4 Methylphenol (m&p Cresol)	<0.0997 U
Benzo(a)anthracene	0.0653 JD
Benzo(a)pyrene	<0.0997 U
Benzo(b)fluoranthene	<0.0997 U
Benzo(g,h,i)Perylene	<0.0997 U
Benzo(k)fluoranthene	<0.0997 U
Chrysene	<0.0997 U
Dibenz(a,h)anthracene	<0.0997 U
Dibenzofuran	<0.0997 U
Indeno(1,2,3-cd)pyrene	<0.0997 U
Phenanthrene	0.0669 JD
Pesticides	
4,4'-DDD	<0.00198 U
4,4'-DDE	<0.00198 U
4,4'-DDT	<0.00198 U
Alpha Chlordane	<0.00198 U
Dieldrin	<0.00198 U
PCBs	
Total PCBs	<0.02 U
Metals	
Arsenic	17
Barium	978
Cadmium	0.331
Chromium, Trivalent	13.8
Copper	321
Cyanide	<0.601 U
Lead	**81**
Manganese	314
Mercury	0.0487
Nickel	279
Selenium	<2.81 U
Silver	<0.505 U
Zinc	**171**
PFAS	
Perfluorooctanesulfonic Acid (PFOS)	0.000642
Perfluorooctanoic Acid (PFOA)	<0.000241 U

Location	PE42
Sample Name	PE42_20
Sample Date	08/19/2025
Sample Elevation	20
VOCs	
Acetone	**0.061**
SVOCs	
3 & 4 Methylphenol (m&p Cresol)	<0.0871 U
Benzo(a)anthracene	0.193 D
Benzo(a)pyrene	0.158 D
Benzo(b)fluoranthene	0.145 D
Benzo(g,h,i)Perylene	0.113 D
Benzo(k)fluoranthene	0.133 D
Chrysene	0.203 D
Dibenz(a,h)anthracene	<0.087 U
Dibenzofuran	<0.087 U
Indeno(1,2,3-cd)pyrene	0.0834 JD
Phenanthrene	0.395 D
Pesticides	
4,4'-DDD	<0.00172 U
4,4'-DDE	<0.00172 U
4,4'-DDT	<0.00172 U
Alpha Chlordane	<0.00172 U
Dieldrin	<0.00172 U
PCBs	
Total PCBs	<0.0134 U
Metals	
Arsenic	1.63
Barium	572
Cadmium	0.355
Chromium, Trivalent	8.56
Copper	19.1
Cyanide	<0.532 U
Lead	61.2
Manganese	153
Mercury	0.0806
Nickel	13.6
Selenium	<2.23 U
Silver	<0.447 U
Zinc	82.3
PFAS	
Perfluorooctanesulfonic Acid (PFOS)	0.000554
Perfluorooctanoic Acid (PFOA)	<0.000212 U

Location	PE64
Sample Name	PE64_20.5
Sample Date	08/28/2025
Sample Elevation	20.5
VOCs	
Acetone	**0.14**
SVOCs	
3 & 4 Methylphenol (m&p Cresol)	<0.0889 U
Benzo(a)anthracene	<0.0889 U
Benzo(a)pyrene	<0.0889 U
Benzo(b)fluoranthene	<0.0889 U
Benzo(g,h,i)Perylene	<0.0889 U
Benzo(k)fluoranthene	<0.0889 U
Chrysene	<0.0889 U
Dibenz(a,h)anthracene	<0.0889 U
Dibenzofuran	<0.0889 U
Indeno(1,2,3-cd)pyrene	<0.0889 U
Phenanthrene	<0.0889 U
Pesticides	
4,4'-DDD	<0.00175 UP
4,4'-DDE	<0.00175 UP
4,4'-DDT	<0.00175 UP
Alpha Chlordane	<0.00175 UP
Dieldrin	<0.00175 UP
PCBs	
Total PCBs	<0.0177 UP
Metals	
Arsenic	2.71
Barium	49.7 J
Cadmium	<0.268 U
Chromium, Trivalent	11.4
Copper	10.5
Cyanide	<0.536 U
Lead	9.12
Manganese	143 J
Mercury	<0.0322 U
Nickel	15.2
Selenium	<2.23 U
Silver	<0.451 U
Zinc	371
PFAS	
Perfluorooctanesulfonic Acid (PFOS)	0.000172 J
Perfluorooctanoic Acid (PFOA)	<0.000214 U

Location	PE63
Sample Name	PE63_20.5
Sample Date	08/28/2025
Sample Elevation	20.5
VOCs	
Acetone	**0.1**
SVOCs	
3 & 4 Methylphenol (m&p Cresol)	<0.108 U
Benzo(a)anthracene	0.657 D
Benzo(a)pyrene	0.639 D
Benzo(b)fluoranthene	0.557 D
Benzo(g,h,i)Perylene	0.376 D
Benzo(k)fluoranthene	0.561 D
Chrysene	0.657 D
Dibenz(a,h)anthracene	0.126 D
Dibenzofuran	<0.108 U
Indeno(1,2,3-cd)pyrene	0.39 D
Phenanthrene	0.923 D
Pesticides	
4,4'-DDD	0.00219 J
4,4'-DDE	<0.00208 UP
4,4'-DDT	0.00313 J
Alpha Chlordane	<0.00208 UP
Dieldrin	0.00209 J
PCBs	
Total PCBs	<0.021 UP
Metals	
Arsenic	9.41
Barium	**602**
Cadmium	**2.69**
Chromium, Trivalent	33.6
Copper	**114**
Cyanide	<0.639 U
Lead	**527**
Manganese	182
Mercury	**0.882**
Nickel	23.8
Selenium	<2.65 U
Silver	0.541
Zinc	**825**
PFAS	
Perfluorooctanesulfonic Acid (PFOS)	0.000233 J
Perfluorooctanoic Acid (PFOA)	0.000189 J

Location	PE61
Sample Name	PE61_20.5
Sample Date	09/23/2025
Sample Elevation	20.5
VOCs	
Acetone	<0.038 U
SVOCs	
3 & 4 Methylphenol (m&p Cresol)	<0.0907 U
Benzo(a)anthracene	0.265 D
Benzo(a)pyrene	0.22 D
Benzo(b)fluoranthene	0.225 D
Benzo(g,h,i)Perylene	0.128 D
Benzo(k)fluoranthene	0.22 D
Chrysene	0.279 D
Dibenz(a,h)anthracene	0.0566 JD
Dibenzofuran	<0.0907 U
Indeno(1,2,3-cd)pyrene	0.112 D
Phenanthrene	0.297 D
Pesticides	
4,4'-DDD	0.00264 D
4,4'-DDE	<0.00178 U
4,4'-DDT	<0.00178 U
Alpha Chlordane	<0.00178 U
Dieldrin	<0.00178 U
PCBs	
Total PCBs	**0.191 J**
Metals	
Arsenic	3.38
Barium	325
Cadmium	0.691
Chromium, Trivalent	17.1
Copper	**65.6 J**
Cyanide	<0.556 U
Lead	**160**
Manganese	245
Mercury	0.1
Nickel	15.2
Selenium	<2.27 U
Silver	<0.458 U
Zinc	**238**
PFAS	
Perfluorooctanesulfonic Acid (PFOS)	**0.000883**
Perfluorooctanoic Acid (PFOA)	0.000145 J

Location	PE53
Sample Name	PE53_20
Sample Date	09/23/2025
Sample Elevation	20
VOCs	
Acetone	**0.16**
SVOCs	
3 & 4 Methylphenol (m&p Cresol)	<0.0967 U
Benzo(a)anthracene	0.427 D
Benzo(a)pyrene	0.373 D
Benzo(b)fluoranthene	0.356 D
Benzo(g,h,i)Perylene	0.250 D
Benzo(k)fluoranthene	0.234 D
Chrysene	0.382 D
Dibenz(a,h)anthracene	<0.0967 U
Dibenzofuran	0.0618 JD
Indeno(1,2,3-cd)pyrene	0.301 D
Phenanthrene	0.476 D
Pesticides	
4,4'-DDD	**0.00488 J**
4,4'-DDE	**0.00694 J**
4,4'-DDT	<0.0019 U
Alpha Chlordane	<0.0019 U
Dieldrin	<0.0019 U
PCBs	
Total PCBs	**0.285 J**
Metals	
Arsenic	**13.6 J**
Barium	**476 J**
Cadmium	1.82
Chromium, Trivalent	**31.4**
Copper	**391**
Cyanide	<0.582 U
Lead	**677**
Manganese	223
Mercury	**0.854**
Nickel	22.2
Selenium	<2.42 U
Silver	0.963
Zinc	**624**
PFAS	
Perfluorooctanesulfonic Acid (PFOS)	**0.00281**
Perfluorooctanoic Acid (PFOA)	0.00041

Location	PE62
Sample Name	PE62_20.5
Sample Date	08/28/2025
Sample Elevation	20.5
VOCs	
Acetone	**0.079**
SVOCs	
3 & 4 Methylphenol (m&p Cresol)	<0.0878 U
Benzo(a)anthracene	<0.0878 U
Benzo(a)pyrene	<0.0878 U
Benzo(b)fluoranthene	<0.0878 U
Benzo(g,h,i)Perylene	<0.0878 U
Benzo(k)fluoranthene	<0.0878 U
Chrysene	<0.0878 U
Dibenz(a,h)anthracene	<0.0878 U
Dibenzofuran	<0.0878 U
Indeno(1,2,3-cd)pyrene	<0.0878 U
Phenanthrene	<0.0878 U
Pesticides	
4,4'-DDD	<0.00174 UP
4,4'-DDE	<0.00174 UP
4,4'-DDT	<0.00174 UP
Alpha Chlordane	<0.00174 UP
Dieldrin	<0.00174 UP
PCBs	
Total PCBs	<0.0176 UP
Metals	
Arsenic	2.13
Barium	10.6
Cadmium	<0.265 U
Chromium, Trivalent	11
Copper	7.43
Cyanide	<0.53 U
Lead	4.18
Manganese	99.7
Mercury	<0.0318 U
Nickel	16.5
Selenium	<2.21 U
Silver	<0.445 U
Zinc	29.6
PFAS	
Perfluorooctanesulfonic Acid (PFOS)	0.000191 J
Perfluorooctanoic Acid (PFOA)	<0.000212 U

Location	PE50
Sample Name	PE50_19.5
Sample Date	09/17/2025
Sample Elevation	19.5
VOCs	
Acetone	<0.025 U
SVOCs	
3 & 4 Methylphenol (m&p Cresol)	<0.705 U
Benzo(a)anthracene	0.389 JD
Benzo(a)pyrene	<0.705 U
Benzo(b)fluoranthene	<0.705 U
Benzo(g,h,i)Perylene	<0.705 U
Benzo(k)fluoranthene	<0.705 U
Chrysene	0.372 JD
Dibenz(a,h)anthracene	<0.705 U
Dibenzofuran	<0.705 U
Indeno(1,2,3-cd)pyrene	<0.705 U
Phenanthrene	0.451 JD
Pesticides	
4,4'-DDD	**0.037 DP**
4,4'-DDE	**0.0156 DP**
4,4'-DDT	<0.00186 UP
Alpha Chlordane	0.00361 DP
Dieldrin	<0.00186 U
PCBs	
Total PCBs	**0.253 P**
Metals	
Arsenic	6.68
Barium	**537**
Cadmium	1.75
Chromium, Trivalent	**32.3**
Copper	**119**
Cyanide	0.922
Lead	**1,040**
Manganese	279
Mercury	**0.68**
Nickel	29.8
Selenium	<2.35 U
Silver	<0.475 U
Zinc	**587**
PFAS	
Perfluorooctanesulfonic Acid (PFOS)	**0.00297**
Perfluorooctanoic Acid (PFOA)	0.00029

Location	PE57
Sample Name	PE57_20
Sample Date	08/26/2025
Sample Elevation	20
VOCs	
Acetone	0.017
SVOCs	
3 & 4 Methylphenol (m&p Cresol)	<0.104 U
Benzo(a)anthracene	**1.19 D**
Benzo(a)pyrene	0.911 D
Benzo(b)fluoranthene	**1.27 D**
Benzo(g,h,i)Perylene	0.469 D
Benzo(k)fluoranthene	0.562 J
Chrysene	**1.17 D**
Dibenz(a,h)anthracene	0.135 D
Dibenzofuran	0.0946 JD
Indeno(1,2,3-cd)pyrene	0.493 D
Phenanthrene	**1.86 D**
Pesticides	
4,4'-DDD	**0.00477 DP**
4,4'-DDE	<0.00204 UP
4,4'-DDT	<0.00204 UP
Alpha Chlordane	<0.00204 UP
Dieldrin	<0.00204 UP
PCBs	
Total PCBs	<0.0206 UP
Metals	
Arsenic	6.13
Barium	**516**
Cadmium	2.02
Chromium, Trivalent	**20.8**
Copper	**99.5**
Cyanide	<0.624 U
Lead	**701**
Manganese	294
Mercury	**0.923**
Nickel	**54.8**
Selenium	<2.6 U
Silver	<0.524 U
Zinc	**478**
PFAS	
Perfluorooctanesulfonic Acid (PFOS)	**0.00174**
Perfluorooctanoic Acid (PFOA)	<0.000248 U

Location	PE58
Sample Name	PE58_19.5
Sample Date	09/17/2025
Sample Elevation	19.5
VOCs	
Acetone	<0.029 U
SVOCs	
3 & 4 Methylphenol (m&p Cresol)	<0.0915 UJ
Benzo(a)anthracene	0.352 J
Benzo(a)pyrene	0.25 J
Benzo(b)fluoranthene	0.237 J
Benzo(g,h,i)Perylene	0.163 J
Benzo(k)fluoranthene	0.246 J
Chrysene	0.342 J
Dibenz(a,h)anthracene	0.0548 J
Dibenzofuran	<0.0915 UJ
Indeno(1,2,3-cd)pyrene	0.137 J
Phenanthrene	0.561 J
Pesticides	
4,4'-DDD	**0.101 DP**
4,4'-DDE	**0.275 DP**
4,4'-DDT	**0.0356 J**
Alpha Chlordane	0.00607 J
Dieldrin	<0.0018 UP
PCBs	
Total PCBs	**3.28 P**
Metals	
Arsenic	6.35
Barium	**693**
Cadmium	**4.37**
Chromium, Trivalent	**30.1**
Copper	**91**
Cyanide	0.921
Lead	**554**
Manganese	341
Mercury	**1.17**
Nickel	21.8
Selenium	<2.3 U
Silver	<0.464 U
Zinc	**703**
PFAS	
Perfluorooctanesulfonic Acid (PFOS)	**0.00328**
Perfluorooctano



Location	PE76
Sample Name	PE76_19.5
Sample Date	09/23/2025
Sample Elevation	19.5
VOCs	
Acetone	<0.027 U
SVOCs	
3,3,4 Methylphenol (m&p Cresol)	<0.0895 U
Benzo(a)anthracene	0.0506 JD
Benzo(a)pyrene	0.0472 JD
Benzo(b)fluoranthene	<0.0895 U
Benzo(g,h,i)Perylene	<0.0895 U
Benzo(k)fluoranthene	<0.0895 U
Chrysene	0.056 JD
Dibenz(a,h)anthracene	<0.0895 U
Dibenzofuran	<0.0895 U
Indeno(1,2,3-cd)pyrene	<0.0895 U
Phenanthrene	0.068 JD
Pesticides	
4,4'-DDD	<0.00176 UP
4,4'-DDE	<0.00176 UP
4,4'-DDT	<0.00176 UP
Alpha Chlordane	<0.00176 UP
Dieldrin	<0.00176 UP
PCBs	
Total PCBs	<0.0177 UP
Metals	
Arsenic	1.86
Barium	13.3
Cadmium	<0.268 U
Chromium, Trivalent	10.3
Copper	8.43
Cyanide	<0.535 U
Lead	4.67
Manganese	71.6
Mercury	<0.0321 U
Nickel	13.1
Selenium	<2.23 U
Silver	<0.45 U
Zinc	41.4
PFAS	
Perfluorooctanesulfonic Acid (PFOS)	0.000588
Perfluorooctanoic Acid (PFOA)	0.000241

Location	PE68	PE68
Sample Name	PE68_20	DUP_20251028
Sample Date	10/28/2025	10/28/2025
Sample Elevation	29	29
VOCs		
Acetone	**0.07 S**	<0.05 U
SVOCs		
3,3,4 Methylphenol (m&p Cresol)	<0.109 UJ	<0.146 UJ
Benzo(a)anthracene	0.241 J	<0.146 UJ
Benzo(a)pyrene	0.221 J	<0.146 UJ
Benzo(b)fluoranthene	0.167 J	<0.146 UJ
Benzo(g,h,i)Perylene	0.233 J	<0.146 UJ
Benzo(k)fluoranthene	0.166 J	<0.146 UJ
Chrysene	0.25 J	<0.146 UJ
Dibenz(a,h)anthracene	0.0672 J	<0.146 UJ
Dibenzofuran	<0.109 UJ	<0.146 UJ
Indeno(1,2,3-cd)pyrene	0.18 J	<0.146 UJ
Phenanthrene	0.284 J	<0.146 UJ
Pesticides		
4,4'-DDD	**0.00356 DP**	<0.00288 UP
4,4'-DDE	**0.00622 J**	<0.00288 UP
4,4'-DDT	<0.00214 UP	<0.00288 UP
Alpha Chlordane	<0.00214 UP	<0.00288 UP
Dieldrin	<0.00214 UP	<0.00288 UP
PCBs		
Total PCBs	**0.412 J**	<0.0291 UJ
Metals		
Arsenic	8.92	**14.7**
Barium	338 J	**5,210 J**
Cadmium	1.45	2.23
Chromium, Trivalent	28.3	**40**
Copper	**111**	**116**
Cyanide	0.694	<0.978 U
Lead	**519 J**	**2,420 J**
Manganese	257	181
Mercury	**0.299 J**	0.142 J
Nickel	23.7	21.5
Selenium	<2.74 U	<3.66 U
Silver	0.93	0.791
Zinc	**603**	**730**
PFAS		
Perfluorooctanesulfonic Acid (PFOS)	0.000163 J	**0.00179 J**
Perfluorooctanoic Acid (PFOA)	<0.000263 U	0.000433

Location	PE77	PE77_20.5
Sample Name	PE77_19.5	
Sample Date	10/01/2025	10/14/2025
Sample Elevation	19.5	20.5
VOCs		
Acetone	<0.061 U	<0.05 U
SVOCs		
3,3,4 Methylphenol (m&p Cresol)	<0.0948 U	<0.097 U
Benzo(a)anthracene	**1.59 D**	0.677 D
Benzo(a)pyrene	**1.51 D**	0.621 D
Benzo(b)fluoranthene	**1.49 D**	0.527 D
Benzo(g,h,i)Perylene	0.503 D	0.292 D
Benzo(k)fluoranthene	**1.25 D**	0.464 D
Chrysene	**1.63 D**	0.632 D
Dibenz(a,h)anthracene	0.183 D	0.105 D
Dibenzofuran	0.155 D	<0.097 U
Indeno(1,2,3-cd)pyrene	**0.561 D**	0.268 D
Phenanthrene	**2.34 D**	0.56 D
Pesticides		
4,4'-DDD	**0.0513 DP**	**0.0138 J**
4,4'-DDE	**0.0276 DP**	**0.00932 DP**
4,4'-DDT	**0.0188 J**	**0.00468 J**
Alpha Chlordane	0.0118 J	0.00213 J
Dieldrin	**0.0251 DP**	**0.00774 J**
PCBs		
Total PCBs	**0.461 J**	**0.616 P**
Metals		
Arsenic	10.5	4.95
Barium	**935**	296
Cadmium	1.42	1.39
Chromium, Trivalent	26	29.7
Copper	**84.6**	**129**
Cyanide	<0.571 U	<0.589 U
Lead	**400**	**336**
Manganese	278	306
Mercury	**0.337**	**0.665**
Nickel	22.7	23
Selenium	<2.39 U	<2.45 U
Silver	0.622	0.668
Zinc	**742**	**442**
PFAS		
Perfluorooctanesulfonic Acid (PFOS)	0.000569	**0.00562**
Perfluorooctanoic Acid (PFOA)	0.000161 J	0.000302

Location	PE69
Sample Name	PE69_20
Sample Date	10/01/2025
Sample Elevation	20
VOCs	
Acetone	<0.063 U
SVOCs	
3,3,4 Methylphenol (m&p Cresol)	0.0579 JD
Benzo(a)anthracene	0.211 D
Benzo(a)pyrene	0.199 D
Benzo(b)fluoranthene	0.182 D
Benzo(g,h,i)Perylene	0.125 D
Benzo(k)fluoranthene	0.162 D
Chrysene	0.217 D
Dibenz(a,h)anthracene	<0.0906 U
Dibenzofuran	<0.0906 U
Indeno(1,2,3-cd)pyrene	0.119 D
Phenanthrene	0.247 D
Pesticides	
4,4'-DDD	0.00232 DP
4,4'-DDE	<0.0018 UP
4,4'-DDT	<0.0018 UP
Alpha Chlordane	<0.0018 UP
Dieldrin	<0.0018 UP
PCBs	
Total PCBs	**0.12 J**
Metals	
Arsenic	4.11
Barium	169
Cadmium	0.565
Chromium, Trivalent	16.5
Copper	**86.8**
Cyanide	<0.547 U
Lead	**200**
Manganese	181
Mercury	0.102
Nickel	172
Selenium	<2.28 U
Silver	<0.459 U
Zinc	**302**
PFAS	
Perfluorooctanesulfonic Acid (PFOS)	0.000493
Perfluorooctanoic Acid (PFOA)	0.00018 J

Location	PE70
Sample Name	PE70_20
Sample Date	09/23/2025
Sample Elevation	20
VOCs	
Acetone	**0.07 S**
SVOCs	
3,3,4 Methylphenol (m&p Cresol)	<0.0999 U
Benzo(a)anthracene	<0.0999 U
Benzo(a)pyrene	<0.0999 U
Benzo(b)fluoranthene	<0.0999 U
Benzo(g,h,i)Perylene	<0.0999 U
Benzo(k)fluoranthene	<0.0999 U
Chrysene	0.0922 J
Dibenz(a,h)anthracene	<0.0999 U
Dibenzofuran	<0.0999 U
Indeno(1,2,3-cd)pyrene	<0.0999 U
Phenanthrene	<0.0999 U
Pesticides	
4,4'-DDD	<0.00196 U
4,4'-DDE	<0.00196 U
4,4'-DDT	<0.00196 U
Alpha Chlordane	<0.00196 U
Dieldrin	<0.00196 U
PCBs	
Total PCBs	<0.02 UJ
Metals	
Arsenic	9.46
Barium	246
Cadmium	**10.6**
Chromium, Trivalent	**35.4**
Copper	**332 J**
Cyanide	<0.601 U
Lead	**680**
Manganese	264
Mercury	<0.0361 U
Nickel	**36.6**
Selenium	<2.5 U
Silver	0.943
Zinc	**880**
PFAS	
Perfluorooctanesulfonic Acid (PFOS)	**0.00119**
Perfluorooctanoic Acid (PFOA)	0.000334

Location	PE78
Sample Name	PE78_19.5
Sample Date	09/23/2025
Sample Elevation	19.5
VOCs	
Acetone	0.025 JS
SVOCs	
3,3,4 Methylphenol (m&p Cresol)	<0.0905 U
Benzo(a)anthracene	0.648 D
Benzo(a)pyrene	0.546 D
Benzo(b)fluoranthene	0.478 D
Benzo(g,h,i)Perylene	0.354 D
Benzo(k)fluoranthene	0.404 D
Chrysene	0.601 D
Dibenz(a,h)anthracene	<0.0905 U
Dibenzofuran	0.0514 JD
Indeno(1,2,3-cd)pyrene	0.403 D
Phenanthrene	0.867 D
Pesticides	
4,4'-DDD	**0.0206 D**
4,4'-DDE	**0.00487 J**
4,4'-DDT	**0.00815 J**
Alpha Chlordane	0.00421 D
Dieldrin	<0.00178 U
PCBs	
Total PCBs	**0.609**
Metals	
Arsenic	5.98
Barium	226
Cadmium	1.21
Chromium, Trivalent	23.1
Copper	**108 J**
Cyanide	0.763
Lead	**346**
Manganese	267
Mercury	0.871
Nickel	214
Selenium	<2.27 U
Silver	0.671
Zinc	**444**
PFAS	
Perfluorooctanesulfonic Acid (PFOS)	0.00064
Perfluorooctanoic Acid (PFOA)	0.000182 J

Location	PE71	PE71_20
Sample Name	PE71_19.5	
Sample Date	09/23/2025	
Sample Elevation	19.5	20
VOCs		
Acetone	<0.03 U	
SVOCs		
3,3,4 Methylphenol (m&p Cresol)	<0.0986 U	
Benzo(a)anthracene	0.512 D	
Benzo(a)pyrene	0.49 D	
Benzo(b)fluoranthene	0.345 D	
Benzo(g,h,i)Perylene	0.347 D	
Benzo(k)fluoranthene	0.379 D	
Chrysene	0.522 D	
Dibenz(a,h)anthracene	0.107 D	
Dibenzofuran	<0.0986 U	
Indeno(1,2,3-cd)pyrene	0.311 D	
Phenanthrene	0.809 D	
Pesticides		
4,4'-DDD	0.00235 D	
4,4'-DDE	<0.00194 U	
4,4'-DDT	<0.00194 U	
Alpha Chlordane	<0.00187 U	
Dieldrin	<0.00194 U	
PCBs		
Total PCBs	**0.227 J**	
Metals		
Arsenic	7.65	
Barium	293	
Cadmium	1.83	
Chromium, Trivalent	25	
Copper	**166**	
Cyanide	<0.593 U	
Lead	**512**	
Manganese	262	
Mercury	**0.238**	
Nickel	24.7	
Selenium	<2.47 U	
Silver	1.06	
Zinc	**503**	
PFAS		
Perfluorooctanesulfonic Acid (PFOS)	**0.00137**	
Perfluorooctanoic Acid (PFOA)	0.000441	

Location	PE72	PE72_19
Sample Name		
Sample Date	09/17/2025	
Sample Elevation	19	
VOCs		
Acetone	<0.024 U	
SVOCs		
3,3,4 Methylphenol (m&p Cresol)	<0.0953 U	
Benzo(a)anthracene	0.451 D	
Benzo(a)pyrene	0.44 D	
Benzo(b)fluoranthene	0.417 D	
Benzo(g,h,i)Perylene	0.452 D	
Benzo(k)fluoranthene	0.344 D	
Chrysene	0.518 D	
Dibenz(a,h)anthracene	0.137 D	
Dibenzofuran	0.0967 D	
Indeno(1,2,3-cd)pyrene	0.344 D	
Phenanthrene	0.857 D	
Pesticides		
4,4'-DDD	**0.0107 DP**	
4,4'-DDE	<0.00187 UP	
4,4'-DDT	**0.00916 J**	
Alpha Chlordane	<0.00187 U	
Dieldrin	<0.00187 UP	
PCBs		
Total PCBs	**0.475 J**	
Metals		
Arsenic	10.3	
Barium	340	
Cadmium	**3.45**	
Chromium, Trivalent	30	
Copper	**168**	
Cyanide	<0.573 U	
Lead	**357**	
Manganese	183	
Mercury	**0.224**	
Nickel	18.8	
Selenium	<2.3 U	
Silver	<0.463 U	
Zinc	**988**	
PFAS		
Perfluorooctanesulfonic Acid (PFOS)	0.000276	
Perfluorooctanoic Acid (PFOA)	0.000142 J	

Location	PE79	PE79_20
Sample Name		
Sample Date	09/23/2025	
Sample Elevation	20	
VOCs		
Acetone	<0.033 U	
SVOCs		
3,3,4 Methylphenol (m&p Cresol)	<0.0917 U	
Benzo(a)anthracene	0.853 D	
Benzo(a)pyrene	0.756 D	
Benzo(b)fluoranthene	0.582 D	
Benzo(g,h,i)Perylene	0.678 D	
Benzo(k)fluoranthene	**1.14 D**	
Chrysene	0.189 D	
Dibenz(a,h)anthracene	0.0572 JD	
Dibenzofuran	<0.0917 U	
Indeno(1,2,3-cd)pyrene	**0.556 D**	
Phenanthrene	**2 D**	
Pesticides		
4,4'-DDD	0.00212 J	
4,4'-DDE	<0.00181 UJ	
4,4'-DDT	0.00203 J	
Alpha Chlordane	<0.00181 UJ	
Dieldrin	<0.00181 UJ	
PCBs		
Total PCBs	0.0591 J	
Metals		
Arsenic	4.51	
Barium	226	
Cadmium	0.708	
Chromium, Trivalent	19.9	
Copper	**83.9 J**	
Cyanide	0.645	
Lead	**279**	
Manganese	163	
Mercury	**0.224**	
Nickel	18.8	
Selenium	<2.3 U	
Silver	<0.463 U	
Zinc	**299**	
PFAS		
Perfluorooctanesulfonic Acid (PFOS)	0.000345	
Perfluorooctanoic Acid (PFOA)	0.000202 J	

Location	PE80	PE80_19
Sample Name		
Sample Date	09/17/2025	
Sample Elevation	19	
VOCs		
Acetone	<0.028 U	
SVOCs		
3,3,4 Methylphenol (m&p Cresol)	<0.0898 U	
Benzo(a)anthracene	0.169 D	
Benzo(a)pyrene	0.0847 D	
Benzo(b)fluoranthene	0.0969 D	
Benzo(g,h,i)Perylene	0.0531 JD	
Benzo(k)fluoranthene	0.0923 D	
Chrysene	0.181 D	
Dibenz(a,h)anthracene	<0.0898 U	
Dibenzofuran	<0.0898 U	
Indeno(1,2,3-cd)pyrene	0.0545 JD	
Phenanthrene	0.0545 JD	
Pesticides		
4,4'-DDD	<0.00182 UP	
4,4'-DDE	<0.00182 UP	
4,4'-DDT	<0.00182 UP	
Alpha Chlordane	<0.00182 UP	
Dieldrin	<0.00178 UP	
PCBs		
Total PCBs	0.0903 P	
Metals		
Arsenic	12.7	
Barium	217	
Cadmium	0.785	
Chromium, Trivalent	15.3	
Copper	**55.6**	
Cyanide	<0.547 U	
Lead	**178**	
Manganese	158	
Mercury	**0.688**	
Nickel	15.4	
Selenium	<2.28 U	
Silver	<0.46 U	
Zinc	**260**	
PFAS		
Perfluorooctanesulfonic Acid (PFOS)	0.000374	
Perfluorooctanoic Acid (PFOA)	0.000142 J	

Location	PE87	
Sample Name	PE87_19.5	
Sample Date	10/01/2025	
Sample Elevation	19.5	
VOCs		
Acetone	<0.058 U	
SVOCs		
3,3,4 Methylphenol (m&p Cresol)	<0.0907 U	
Benzo(a)anthracene	0.403 D	
Benzo(a)pyrene	0.434 D	
Benzo(b)fluoranthene	0.41 D	
Benzo(g,h,i)Perylene	0.238 D	
Benzo(k)fluoranthene	0.355 D	
Chrysene	0.429 D	
Dibenz(a,h)anthracene	0.0834 JD	
Dibenzofuran	<0.0907 U	
Indeno(1,2,3-cd)pyrene	0.241 D	
Phenanthrene	0.437 D	
Pesticides		
4,4'-DDD	0.00199 DP	
4,4'-DDE	<0.00178 UP	
4,4'-DDT	<0.00178 UP	
Alpha Chlordane	<0.00178 UP	
Dieldrin	<0.00178 UP	
PCBs		
Total PCBs	**0.187 P**	
Metals		
Arsenic	6.1	
Barium	**470**	
Cadmium	0.624	
Chromium, Trivalent	15.1	
Copper	**93.6**	
Cyanide	<0.547 U	
Lead	**178**	
Manganese	158	
Mercury	**0.688**	
Nickel	15.4	
Selenium	<2.28 U	
Silver	<0.46 U	
Zinc	**260**	
PFAS		
Perfluorooctanesulfonic Acid (PFOS)	0.000238	
Perfluorooctanoic Acid (PFOA)	0.000142 J	

Location	PE88	
Sample Name	PE88_19.5	
Sample Date	09/17/2025	
Sample Elevation	19.5	
VOCs		
Acetone	0.014 JS	
SVOCs		
3,3,4 Methylphenol (m&p Cresol)	<0.0973 U	
Benzo(a)anthracene	0.32 D	
Benzo(a)pyrene	0.269 D	
Benzo(b)fluoranthene	0.244 D	
Benzo(g,h,i)Perylene	0.192 D	
Benzo(k)fluoranthene	0.235 D	
Chrysene	0.347 D	
Dibenz(a,h)anthracene	0.0976 D	
Dibenzofuran	<0.0973 U	
Indeno(1,2,3-cd)pyrene	0.17 D	
Phenanthrene	0.631 D	
Pesticides		
4,4'-DDD	**0.00384 DP**	
4,4'-DDE	<0.00192 UP	
4,4'-DDT	0.00226 J	
Alpha Chlordane	<0.00192 UP	
Dieldrin	<0.00192 UP	
PCBs		
Total PCBs	**0.187 P**	
Metals		
Arsenic	6.1	
Barium	**470**	
Cadmium	0.624	
Chromium, Trivalent	15.1	
Copper	**93.6**	
Cyanide	<0.547 U	
Lead	**178**	
Manganese	158	
Mercury	**0.688**	
Nickel	15.4	
Selenium	<2.28 U	
Silver	<0.46 U	
Zinc	**260**	
PFAS		
Perfluorooctanesulfonic Acid (PFOS)	0.000218 U	
Perfluorooctanoic Acid (PFOA)	<0.000234 U	

Location	PE95	
Sample Name	PE95_19.5	
Sample Date	10/01/2025	
Sample Elevation	19.5	
VOCs		
Acetone	<0.062 U	
SVOCs		
3,3,4 Methylphenol (m&p Cresol)	0.0763 JD	
Benzo(a)anthracene	<0.918 U	
Benzo(a)pyrene	<0.918 U	
Benzo(b)fluoranthene	<0.918 U	
Benzo(g,h,i)Perylene	**1.72 D**	
Benzo(k)fluoranthene	**2.89 D**	
Chrysene	<0.918 U	
Dibenz(a,h)anthracene	**0.786 D**	
Dibenzofuran	0.329 D	
Indeno(1,2,3-cd)pyrene	**1.98 D**	
Phenanthrene	<0.918 U	
Pesticides		
4,4'-DDD	0.00213 DP	
4,4'-DDE	<0.00183 UP	
4,4'-DDT	<0.00183 UP	
Alpha Chlordane	<0.00183 UP	
Dieldrin	<0.00183 UP	
PCBs		
Total PCBs	**0.556 J**	
Metals		
Arsenic	7.49	
Barium	339	
Cadmium	1.83	
Chromium, Trivalent	**42.7**	
Copper	**222**	
Cyanide	0.923	
Lead	**393**	
Manganese	263	
Mercury	**24.2**	
Nickel	**31**	
Selenium	<2.32 U	
Silver	0.815	
Zinc	**574**	
PFAS		
Perfluorooctanesulfonic Acid (PFOS)	**0.00289**	
Perfluorooctanoic Acid (PFOA)	0.000408	

Location	PE96	PE96
Sample Name	PE96_19	DUP_10012025
Sample Date	10/01/2025	10/01/2025
Sample Elevation	19	19
VOCs		
Acetone	<0.077 U	<0.083 U
SVOCs		
3,3,4 Methylphenol (m&p Cresol)	<0.0922 U	<0.0905 U
Benzo(a)anthracene	0.432 J	**3.95 J**
Benzo(a)pyrene	0.424 D	**2.3 D**
Benzo(b)fluoranthene	0.374 D	**2.14 D**
Benzo(g,h,i)Perylene	0.231 J	**1.66 J**
Benzo(k)fluoranthene	0.323 J	**1.92 J**
Chrysene	0.45 J	**3.05 J**
Dibenz(a,h)anthracene	0.0796 J	**0.609 J**
Dibenzofuran	<0.0922 UJ	0.366 J
Indeno(1,2,3-cd)pyrene	0.234 J	**2.14 J**
Phenanthrene	0.693 J	**2.87 J**
Pesticides		
4,4'-DDD	**0.0159 J**	**0.0526 J**
4,4'-DDE	**0.00689 J**	**0.0158 J**
4,4'-DDT	**0.00426 J**	**0.00911 J**
Alpha Chlordane	0.00195 J	0.00716 J
Dieldrin	0.00297 J	**0.0144 J**
PCBs		
Total PCBs	0.0652 J	0.063 J
Metals		
Arsenic	5.9	8.06
Barium	**618**	**914**
Cadmium	0.992	1.24
Chromium, Trivalent	23.9	29.1
Copper	**72.3**	**70.2**
Cyanide	<0.556 U	1.27
Lead	**344**	**495**
Manganese	235	300
Mercury	**0.434 J**	**0.584 J**
Nickel	24.9	19.1
Selenium	<2.32 U	<2.43 U
Silver	0.779	<0.491 U
Zinc	**432**	**583**
PFAS		
Perfluorooctanesulfonic Acid (PFOS)	0.000242 J	0.000866 J
Perfluorooctanoic Acid (PFOA)	0.000144 J	0.000191 J

Location	PE97	
Sample Name	PE97_20	
Sample Date	11/11/2025	
Sample Elevation	20	
VOCs		
Acetone	<0.05 U	
SVOCs		
3,3,4 Methylphenol (m&p Cresol)	<0.101 UJ	
Benzo(a)anthracene	0.104 J	
Benzo(a)pyrene	0.102 J	
Benzo(b)fluoranthene	0.092 J	
Benzo(g,h,i)Perylene	0.0621 J	
Benzo(k)fluoranthene	0.0944 J	
Chrysene	0.116 J	
Dibenz(a,h)anthracene	<0.101 UJ	
Dibenzofuran	<0.101 UJ	
Indeno(1,2,3-cd)pyrene	0.0605 J	
Phenanthrene	0.181 J	
Pesticides		
4,4'-DDD	**0.00451 J**	
4,4'-DDE	<0.00199 UP	
4,4'-DDT	<0.00199 UP	
Alpha Chlordane	<0.00199 UP	
Dieldrin	<0.00199 UP	
PCBs		
Total PCBs	<0.0201 UP	
Metals		
Arsenic	8.01	
Barium	315	
Cadmium	1.15	
Chromium, Trivalent	23.7	
Copper	**111**	
Cyanide	0.695	
Lead	**368 J**	
Manganese	154	
Mercury	**0.242**	
Nickel	19.1	
Selenium	<2.54 U	
Silver	1.37 J	
Zinc	**337**	
PFAS		
Perfluorooctanesulfonic Acid (PFOS)	0.000324	
Perfluorooctanoic Acid (PFOA)	<0.000244 U	

Location	PE98	
Sample Name	PE98_20	
Sample Date	11/11/2025	
Sample Elevation	20	
VOCs		
Acetone	<0.05 U	
SVOCs		
3,3,4 Methylphenol (m&p Cresol)	<0.0961 UJ	
Benzo(a)anthracene	**1.38 J**	
Benzo(a)pyrene	**1.13 J**	
Benzo(b)fluoranthene	**1.15 J**	
Benzo(g,h,i)Perylene	0.561 J	
Benzo(k)fluoranthene	**0.941 J**	
Chrysene	**1.35 J**	
Dibenz(a,h)anthracene	0.235 J	
Dibenzofuran	0.202 J	
Indeno(1,2,3-cd)pyrene	**0.646 J**	
Phenanthrene	**1.85 J**	
Pesticides		
4,4'-DDD	**0.0154 DP**	
4,4'-DDE	**0.0122 DP**	
4,4'-DDT	0.00305 J	
Alpha Chlordane	0.00363 DP	
Dieldrin	0.00207 J	
PCBs		
Total PCBs	**0.195 P**	
Metals		
Arsenic	3.92	
Barium	236	
Cadmium	0.725	
Chromium, Trivalent	20.2	
Copper	34.7	
Cyanide	<0.58 U	
Lead	**176 J**	
Manganese	228	
Mercury	**0.272**	
Nickel	19.2	
Selenium	<2.42 U	
Silver	<0.487 U	
Zinc	**281**	
PFAS		
Perfluorooctanesulfonic Acid (PFOS)	0.000377	
Perfluorooctanoic Acid (PFOA)	<0.000232 U	

Location	PE99	
Sample Name	PE99_20	
Sample Date	11/11/2025	
Sample Elevation	20	
VOCs		
Acetone	<0.05 U	
SVOCs		
3,3,4 Methylphenol (m&p Cresol)	<0.0981 UJ	
Benzo(a)anthracene	0.712 J	
Benzo(a)pyrene	0.72 J	
Benzo(b)fluoranthene	0.703 J	
Benzo(g,h,i)Perylene	0.423 J	
Benzo(k)fluoranthene	0.6 J	
Chrysene	0.766 J	
Dibenz(a,h)anthracene	<0.0981 UJ	
Dibenzofuran	<0.0981 UJ	
Indeno(1,2,3-cd)pyrene	0.448 J	
Phenanthrene	0.908 J	
Pesticides		
4,4'-DDD	**0.033 DP**	
4,4'-DDE	**0.0163 DP**	
4,4'-DDT	**0.00393 J**	
Alpha Chlordane	0.00547 DP	
Dieldrin	**0.00646 J**	
PCBs		
Total PCBs	**0.135 P**	
Metals		
Arsenic	5.31	
Barium	**505 J**	
Cadmium	0.912	
Chromium, Trivalent	27.5	
Copper	**52.4 J**	
Cyanide	1.2 J	
Lead	**1,070 J**	
Manganese	321	
Mercury	**1.08**	
Nickel	173 J	
Selenium	<2.69 U	
Silver	<0.511 UJ	
Zinc	**582**	
PFAS		
Perfluorooctanesulfonic Acid (PFOS)	**0.00126**	
Perfluorooctanoic Acid (PFOA)	0.000136 J	

Location	PE81	
Sample Name	PE81_20	
Sample Date	12/05/2025	
Sample Elevation	20	
VOCs		
Acetone	**0.093**	
SVOCs		
3,3,4 Methylphenol (m&p Cresol)	<0.0889 U	
Benzo(a)anthracene	<0.0889 U	
Benzo(a)pyrene	<0.0889 U	
Benzo(b)fluoranthene	<0.0889 U	
Benzo(g,h,i)Perylene	<0.0889 U	
Benzo(k)fluoranthene	<0.0889 U	
Chrysene	<0.0889 U	
Dibenz(a,h)anthracene	<0.0889 U	
Dibenzofuran	<0.0889 U	
Indeno(1,2,3-cd)pyrene	<0.0889 U	
Phenanthrene	<0.0889 U	
Pesticides		
4,4'-DDD	**0.0166 J**	
4,4'-DDE	**0.00742 J**	
4,4'-DDT	**0.00764 J**	
Alpha Chlordane	0.0108 J	
Dieldrin	<0.00193 UP	
PCBs		
Total PCBs	**0.568 P**	
Metals		
Arsenic	2.32	
Barium	76	
Cadmium	<0.272 U	
Chromium, Trivalent	12.2	
Copper	17.2	
Cyanide	<0.543 U	
Lead	62.1	
Manganese	118	
Mercury	**0.206**	
Nickel	17.3	
Selenium	<2.26 U	
Silver	<0.456 U	
Zinc	82	
PFAS		
Perfluorooctanesulfonic Acid (PFOS)	0.000118 J	
Perfluorooctanoic Acid (PFOA)	0.0000972 J	

Location	PE89	
Sample Name	PE89_15	
Sample Date	10/14/2025	
Sample Elevation	15	
VOCs		
Acetone	<0.05 U	
SVOCs		
3,3,4 Methylphenol (m&p Cresol)	<0.0973 U	
Benzo(a)anthracene	**1.18 D**	
Benzo(a)pyrene	**1.13 D**	
Benzo(b)fluoranthene	**1.01 D**	
Benzo(g,h,i)Perylene	0.551 D	
Benzo(k)fluoranthene	**0.859 D**	
Chrysene	**1.12 D**	
Dibenz(a,h)anthracene	0.196 D	
Dibenzofuran	0.063 JD	
Indeno(1,2,3-cd)pyrene	**0.53 D**	
Phenanthrene	**1.33 D**	
Pesticides		
4,4'-DDD	**0.0166 J**	
4,4'-DDE	**0.00742 J**	
4,4'-DDT	**0.00764 J**	
Alpha Chlordane	0.0108 J	
Dieldrin	<0.00193 UP	
PCBs		
Total PCBs	**0.181 P**	
Metals		
Arsenic	**29.8**	
Barium	**507**	
Cadmium	**6.17**	
Chromium, Trivalent	**90.1**	
Copper	**183**	
Cyanide	0.967	
Lead	**1,160**	
Manganese	291	
Mercury	**0.371**	
Nickel	**56.5**	
Selenium	<2.43 U	
Silver	1.11	
Zinc	**5,240 D**	
PFAS		
Perfluorooctanesulfonic Acid (PFOS)	**0.00187**	
Perfluorooctanoic Acid (P

	Location	LMW-15
	Sample Name	LMW-15_030723
	Sample Date	03/07/2023
VOCs		
1,4-Dioxane (P-Dioxane)		<250 U
Tert-Butyl Methyl Ether		<2.5 U
Naphthalene		**110**
Tetrachloroethene (PCE)		<0.5 U
Trichloroethene (TCE)		<0.5 U
SVOCs		
1,4-Dioxane (P-Dioxane)		0.0711 J
Benzo(a)anthracene		**0.17 J**
Benzo(a)pyrene		**0.13 J**
Benzo(b)fluoranthene		**0.11 J**
Chrysene		**0.18 J**
Indeno(1,2,3-cd)pyrene		**0.07 J**
Naphthalene		**28**
PCBs		
Total PCBs		<0.071 U
Metals - Dissolved		
Barium		87.12
Iron		**19,100**
Lead		<1 U
Magnesium		12,200
Manganese		**2,326**
Selenium		<5 U
Sodium		**77,800**
Metals - Total		
Barium		107.3
Iron		**31,900**
Lead		2.4
Magnesium		12,600
Manganese		**2,506**
Selenium		<5 U
Sodium		**81,000**
PFAS		
Perfluorooctanesulfonic Acid (PFOS)		**0.0437**
Perfluorooctanoic Acid (PFOA)		**0.0374**

	Location	LMW-24
	Sample Name	LMW-24_030723
	Sample Date	03/07/2023
VOCs		
1,4-Dioxane (P-Dioxane)		<250 U
Tert-Butyl Methyl Ether		1.4 J
Naphthalene		<2.5 U
Tetrachloroethene (PCE)		<0.5 U
Trichloroethene (TCE)		<0.5 U
SVOCs		
1,4-Dioxane (P-Dioxane)		0.304
Benzo(a)anthracene		<0.1 U
Benzo(a)pyrene		<0.1 U
Benzo(b)fluoranthene		<0.1 U
Chrysene		<0.1 U
Indeno(1,2,3-cd)pyrene		<0.1 U
Naphthalene		0.13
PCBs		
Total PCBs		<0.071 U
Metals - Dissolved		
Barium		281.7
Iron		**10,300**
Lead		<1 U
Magnesium		7,210
Manganese		151.4
Selenium		<5 U
Sodium		**45,800**
Metals - Total		
Barium		436.8
Iron		**33,000**
Lead		14.84
Magnesium		7,420
Manganese		165.4
Selenium		<5 U
Sodium		**48,600**
PFAS		
Perfluorooctanesulfonic Acid (PFOS)		**0.00427**
Perfluorooctanoic Acid (PFOA)		**0.0228**

	Location	LMW-25
	Sample Name	LMW-25_030723
	Sample Date	03/07/2023
VOCs		
1,4-Dioxane (P-Dioxane)		<250 U
Tert-Butyl Methyl Ether		<2.5 U
Naphthalene		1.1 J
Tetrachloroethene (PCE)		<0.5 U
Trichloroethene (TCE)		<0.5 U
SVOCs		
1,4-Dioxane (P-Dioxane)		<0.147 U
Benzo(a)anthracene		<0.1 U
Benzo(a)pyrene		<0.1 U
Benzo(b)fluoranthene		<0.1 U
Chrysene		<0.1 U
Indeno(1,2,3-cd)pyrene		<0.1 U
Naphthalene		<0.1 U
PCBs		
Total PCBs		<0.071 U
Metals - Dissolved		
Barium		57.4
Iron		**12,200**
Lead		<1 U
Magnesium		4,720
Manganese		**981.2**
Selenium		<5 U
Sodium		**64,200**
Metals - Total		
Barium		63.14
Iron		**16,000**
Lead		0.78 J
Magnesium		4,820
Manganese		**1,072**
Selenium		<5 U
Sodium		**68,400**
PFAS		
Perfluorooctanesulfonic Acid (PFOS)		**0.0176**
Perfluorooctanoic Acid (PFOA)		**0.0124**

	Location	LMW-16
	Sample Name	LMW-16_030723
	Sample Date	03/07/2023
VOCs		
1,4-Dioxane (P-Dioxane)		<250 U
Tert-Butyl Methyl Ether		<2.5 U
Naphthalene		<2.5 U
Tetrachloroethene (PCE)		<0.5 U
Trichloroethene (TCE)		<0.5 U
SVOCs		
1,4-Dioxane (P-Dioxane)		<0.147 U
Benzo(a)anthracene		<0.1 U
Benzo(a)pyrene		<0.1 U
Benzo(b)fluoranthene		<0.1 U
Chrysene		<0.1 U
Indeno(1,2,3-cd)pyrene		<0.1 U
Naphthalene		<0.1 U
PCBs		
Total PCBs		<0.071 U
Metals - Dissolved		
Barium		286.1
Iron		**4,960**
Lead		<1 U
Magnesium		3,150
Manganese		**609**
Selenium		<5 U
Sodium		9,870
Metals - Total		
Barium		340.4
Iron		**11,400**
Lead		0.59 J
Magnesium		3,240
Manganese		**649.7**
Selenium		<5 U
Sodium		10,300
PFAS		
Perfluorooctanesulfonic Acid (PFOS)		**0.012**
Perfluorooctanoic Acid (PFOA)		**0.0104**

	Location	LMW-18
	Sample Name	LMW-18_030723
	Sample Date	03/07/2023
VOCs		
1,4-Dioxane (P-Dioxane)		<250 U
Tert-Butyl Methyl Ether		1.4 J
Naphthalene		<2.5 U
Tetrachloroethene (PCE)		<0.5 U
Trichloroethene (TCE)		<0.5 U
SVOCs		
1,4-Dioxane (P-Dioxane)		**10.4**
Benzo(a)anthracene		<0.1 U
Benzo(a)pyrene		<0.1 U
Benzo(b)fluoranthene		<0.1 U
Chrysene		<0.1 U
Indeno(1,2,3-cd)pyrene		<0.1 U
Naphthalene		0.09 J
PCBs		
Total PCBs		<0.071 U
Metals - Dissolved		
Barium		284.9
Iron		**14,700**
Lead		<1 U
Magnesium		15,400
Manganese		159.7
Selenium		<5 U
Sodium		**57,800**
Metals - Total		
Barium		381.2
Iron		**26,700**
Lead		4.34
Magnesium		15,100
Manganese		165.9
Selenium		<5 U
Sodium		**59,100**
PFAS		
Perfluorooctanesulfonic Acid (PFOS)		**0.00723 J**
Perfluorooctanoic Acid (PFOA)		**0.0345**

	Location	LMW-19
	Sample Name	LMW-19_030723
	Sample Date	03/07/2023
VOCs		
1,4-Dioxane (P-Dioxane)		<250 U
Tert-Butyl Methyl Ether		<2.5 U
Naphthalene		**44**
Tetrachloroethene (PCE)		<0.5 U
Trichloroethene (TCE)		<0.5 U
SVOCs		
1,4-Dioxane (P-Dioxane)		0.0431 J
Benzo(a)anthracene		<0.1 U
Benzo(a)pyrene		<0.1 U
Benzo(b)fluoranthene		<0.1 U
Chrysene		<0.1 U
Indeno(1,2,3-cd)pyrene		<0.1 U
Naphthalene		9.3
PCBs		
Total PCBs		<0.071 U
Metals - Dissolved		
Barium		215
Iron		**1,540**
Lead		<1 U
Magnesium		11,000
Manganese		197.3
Selenium		<5 U
Sodium		**34,500**
Metals - Total		
Barium		286.9
Iron		**13,000**
Lead		2.71
Magnesium		11,500
Manganese		211.2
Selenium		<5 U
Sodium		**36,200**
PFAS		
Perfluorooctanesulfonic Acid (PFOS)		**0.0167**
Perfluorooctanoic Acid (PFOA)		**0.0422**

	Location	LMW-6	LMW-6
	Sample Name	055_LMW-6	LMW-6_030723
	Sample Date	05/14/2018	03/07/2023
VOCs			
1,4-Dioxane (P-Dioxane)		<40 UJ	<250 U
Tert-Butyl Methyl Ether		2.5	1.1 J
Naphthalene		NA	<2.5 U
Tetrachloroethene (PCE)		<0.2 U	<0.5 U
Trichloroethene (TCE)		<0.2 U	<0.5 U
SVOCs			
1,4-Dioxane (P-Dioxane)		NA	**0.732**
Benzo(a)anthracene		<0.0526 U	<0.1 U
Benzo(a)pyrene		<0.0526 UJ	<0.1 U
Benzo(b)fluoranthene		<0.0526 U	<0.1 U
Chrysene		<0.0526 U	<0.1 U
Indeno(1,2,3-cd)pyrene		<0.0526 U	<0.1 U
Naphthalene		0.305	0.06 J
PCBs			
Total PCBs		**0.341 J**	0.074
Metals - Dissolved			
Barium		299	386.7
Iron		**9,800**	**18,700**
Lead		<5.56 U	<1 U
Magnesium		13,800	15,000
Manganese		**513**	**315.6**
Selenium		1.86	<5 U
Sodium		**87,800**	**58,200**
Metals - Total			
Barium		388	605.9
Iron		**34,400**	**44,300**
Lead		**117**	4.26
Magnesium		10,000	15,000
Manganese		**877**	**331.3**
Selenium		3.72 J	<5 U
Sodium		**181,000 J**	**60,000**
PFAS			
Perfluorooctanesulfonic Acid (PFOS)		NA	**0.00452**
Perfluorooctanoic Acid (PFOA)		NA	**0.0493**

	Location	LMW-4	LMW-4
	Sample Name	059_LMW-4	LMW-4_030823
	Sample Date	05/14/2018	03/08/2023
VOCs			
1,4-Dioxane (P-Dioxane)		<40 UJ	<250 U
Tert-Butyl Methyl Ether		**19.9**	4.3
Naphthalene		NA	<2.5 U
Tetrachloroethene (PCE)		<0.2 U	<0.5 U
Trichloroethene (TCE)		<0.2 U	<0.5 U
SVOCs			
1,4-Dioxane (P-Dioxane)		NA	**2.35**
Benzo(a)anthracene		<0.0571 U	<0.1 U
Benzo(a)pyrene		<0.0571 UJ	<0.1 U
Benzo(b)fluoranthene		<0.0571 U	<0.1 U
Chrysene		<0.0571 U	<0.1 U
Indeno(1,2,3-cd)pyrene		<0.0571 U	<0.1 U
Naphthalene		0.206	<0.1 U
PCBs			
Total PCBs		<0.0571 UJ	<0.071 U
Metals - Dissolved			
Barium		450	466.6
Iron		**2,940**	**22,300**
Lead		<5.56 U	<1 U
Magnesium		21,200	10,800
Manganese		**309**	150.9
Selenium		**14.6**	<5 U
Sodium		**123,000**	**57,800**
Metals - Total			
Barium		81.4	667.7
Iron		**532**	**39,400**
Lead		<5.56 U	10.05
Magnesium		7,610	11,400
Manganese		**439**	163.9
Selenium		**20.9**	<5 U
Sodium		**76,100 J**	**52,800**
PFAS			
Perfluorooctanesulfonic Acid (PFOS)		NA	<0.0015 U
Perfluorooctanoic Acid (PFOA)		NA	**0.0668**

	Location	LMW-17
	Sample Name	LMW-17_030723
	Sample Date	03/07/2023
VOCs		
1,4-Dioxane (P-Dioxane)		<250 U
Tert-Butyl Methyl Ether		2 J
Naphthalene		<2.5 U
Tetrachloroethene (PCE)		<0.5 U
Trichloroethene (TCE)		<0.5 U
SVOCs		
1,4-Dioxane (P-Dioxane)		**4.3**
Benzo(a)anthracene		<0.1 U
Benzo(a)pyrene		<0.1 U
Benzo(b)fluoranthene		<0.1 U
Chrysene		<0.1 U
Indeno(1,2,3-cd)pyrene		<0.1 U
Naphthalene		<0.1 U
PCBs		
Total PCBs		<0.071 U
Metals - Dissolved		
Barium		**1,080**
Iron		**7,440**
Lead		<1 U
Magnesium		20,100
Manganese		92.73
Selenium		<5 U
Sodium		**81,000**
Metals - Total		
Barium		**1,652**
Iron		**29,600**
Lead		2.1
Magnesium		21,100
Manganese		101
Selenium		<5 U
Sodium		**87,200**
PFAS		
Perfluorooctanesulfonic Acid (PFOS)		**0.0774**
Perfluorooctanoic Acid (PFOA)		**0.0731**

	Location	LMW-21	LMW-21
	Sample Name	LMW-21_030823	DUP04_030823
	Sample Date	03/08/2023	03/08/2023
VOCs			
1,4-Dioxane (P-Dioxane)		<2,500 U	<2,500 U
Tert-Butyl Methyl Ether		<25 U	<25 U
Naphthalene		<25 U	<25 U
Tetrachloroethene (PCE)		<5 U	<5 U
Trichloroethene (TCE)		<5 U	<5 U
SVOCs			
1,4-Dioxane (P-Dioxane)		**0.873**	**1.08**
Benzo(a)anthracene		<0.1 U	<0.1 U
Benzo(a)pyrene		<0.1 U	<0.1 U
Benzo(b)fluoranthene		<0.1 U	<0.1 U
Chrysene		<0.1 U	<0.1 U
Indeno(1,2,3-cd)pyrene		**0.06 J**	**0.04 J**
Naphthalene		0.21	0.14
PCBs			
Total PCBs		0.067 J	<0.071 U
Metals - Dissolved			
Barium		273	310
Iron		**10,400**	**12,200**
Lead		1.16	<1 U
Magnesium		**59,500**	**59,600**
Manganese		**544.5**	**538.1**
Selenium		<5 U	<5 U
Sodium		**62,000**	**63,500**
Metals - Total			
Barium		465.8	585.7
Iron		**30,300**	**34,400**
Lead		**122.7 J**	**282.4 J**
Magnesium		**54,500**	**53,500**
Manganese		**619.5**	**656**
Selenium		<5 U	<5 U
Sodium		**57,300**	**59,800**
PFAS			
Perfluorooctanesulfonic Acid (PFOS)		**0.0932**	**0.0771**
Perfluorooctanoic Acid (PFOA)		**0.183**	**0.182**

	Location	LMW-23
	Sample Name	LMW-23_030823
	Sample Date	03/08/2023
VOCs		
1,4-Dioxane (P-Dioxane)		<250 U
Tert-Butyl Methyl Ether		<2.5 U
Naphthalene		<2.5 U
Tetrachloroethene (PCE)		<0.5 U
Trichloroethene (TCE)		<0.5 U
SVOCs		
1,4-Dioxane (P-Dioxane)		0.1 J
Benzo(a)anthracene		<0.1 U
Benzo(a)pyrene		<0.1 U
Benzo(b)fluoranthene		<0.1 U
Chrysene		<0.1 U
Indeno(1,2,3-cd)pyrene		**0.03 J**
Naphthalene		0.27
PCBs		
Total PCBs		<0.071 U
Metals - Dissolved		
Barium		356.1
Iron		**16,200**
Lead		<1 U
Magnesium		21,300
Manganese		**346.6**
Selenium		<5 U
Sodium		**61,000**
Metals - Total		
Barium		511.5
Iron		**33,300**
Lead		8.06
Magnesium		21,100
Manganese		**386.2**
Selenium		<5 U
Sodium		**58,000**
PFAS		
Perfluorooctanesulfonic Acid (PFOS)		**0.0171**
Perfluorooctanoic Acid (PFOA)		**0.0762**

	Location	LMW-22
	Sample Name	LMW-22_030823
	Sample Date	03/08/2023
VOCs		
1,4-Dioxane (P-Dioxane)		<250 U
Tert-Butyl Methyl Ether		<2.5 U
Naphthalene		<2.5 U
Tetrachloroethene (PCE)		<0.5 U
Trichloroethene (TCE)		<0.5 U
SVOCs		
1,4-Dioxane (P-Dioxane)		0.306
Benzo(a)anthracene		**0.13 J**
Benzo(a)pyrene		**0.1 J**
Benzo(b)fluoranthene		**0.12 J**
Chrysene		**0.11 J**
Indeno(1,2,3-cd)pyrene		**0.07 J**
Naphthalene		0.37
PCBs		
Total PCBs		<0.071 U
Metals - Dissolved		
Barium		727.2
Iron		**2,870**
Lead		<1 U
Magnesium		25,000
Manganese		**391.1**
Selenium		<5 U
Sodium		**56,400**
Metals - Total		
Barium		844
Iron		**12,300**
Lead		**26.71**
Magnesium		22,100
Manganese		**427**
Selenium		<5 U
Sodium		**50,400**
PFAS		
Perfluorooctanesulfonic Acid (PFOS)		**0.153**
Perfluorooctanoic Acid (PFOA)		**0.0799**

	Location	LMW-20
	Sample Name	LMW-20_030823
	Sample Date	03/08/2023
VOCs		
1,4-Dioxane (P-Dioxane)		<250 U
Tert-Butyl Methyl Ether		3.1
Naphthalene		<2.5 U
Tetrachloroethene (PCE)		<0.5 U
Trichloroethene (TCE)		<0.5 U
SVOCs		
1,4-Dioxane (P-Dioxane)		**3.17**
Benzo(a)anthracene		<0.1 U
Benzo(a)pyrene		<0.1 U
Benzo(b)fluoranthene		<0.1 U
Chrysene		<0.1 U
Indeno(1,2,3-cd)pyrene		<0.1 U
Naphthalene		0.06 J
PCBs		
Total PCBs		<0.071 U
Metals - Dissolved		
Barium		503.2
Iron		**7,920**
Lead		<1 U
Magnesium		26,000
Manganese		174.7
Selenium		<5 U
Sodium		**115,000**
Metals - Total		
Barium		676.5
Iron		**21,600**
Lead		1.28
Magnesium		22,900
Manganese		183.1
Selenium		<5 U
Sodium		**105,000**
PFAS		
Perfluorooctanesulfonic Acid (PFOS)		**0.0961**
Perfluorooctanoic Acid (PFOA)		**0.123**



Analyte	NYSDEC SGVs
VOCs	
1,4-Dioxane (P-Dioxane)	0.35
Tert-Butyl Methyl Ether	10
Naphthalene	10
Tetrachloroethene (PCE)	5
Trichloroethene (TCE)	5
SVOCs	
1,4-Dioxane (P-Dioxane)	0.35
Benzo(a)anthracene	0.002
Benzo(a)pyrene	0
Benzo(b)fluoranthene	0.002
Chrysene	0.002
Indeno(1,2,3-cd)pyrene	0.002
Naphthalene	10
PCBs	
Total PCBs	0.09
Metals - Dissolved	
Barium	1000
Iron	300
Lead	25
Magnesium	35000
Manganese	300
Selenium	10
Sodium	20000
Metals - Total	
Barium	1000
Iron	300
Lead	25
Magnesium	35000
Manganese	300
Selenium	10
Sodium	20000
PFAS	
Perfluorooctanesulfonic Acid (PFOS)	0.0027
Perfluorooctanoic Acid (PFOA)	0.0067

Exceedance Summary:

10 - Result exceeds NYSDEC SGVs

0 60 120

SCALE IN FEET

Legend

- Site Boundary
- 2018 Phase II Test Pit Location
- Groundwater Flow Direction
- Groundwater Contour (NAVD88)
- Inferred Groundwater Contour (NAVD88)
- 2023 RI Monitoring Well / Soil Boring Location
- 2018 Phase II Monitoring Well / Soil Boring Location

NOTES:

1. AERIAL IMAGERY PROVIDED BY NEARMAP LTD., COLLECTED 07/03/2025.
2. 2018 PHASE II EI SAMPLE AND TEST PIT LOCATIONS OBTAINED FROM THE PHASE II EI REPORT CONDUCTED BY LANGAN ENGINEERING, ENVIRONMENTAL, SURVEY, LANDSCAPE ARCHITECTURE, AND GEOLOGY, D.P.C DATED 5/30/2018.
3. SAMPLE LOCATIONS FOR THE RI WERE COLLECTED USING GPS LOCATING TECHNIQUES. ELEVATION DATA FOR THE MONITORING WELLS ON THE SITE WERE COLLECTED USING CLASSICAL SURVEY TECHNIQUES.
4. LMW-22 WAS EXCLUDED FROM THE MARCH 2023 GROUNDWATER CONTOUR DATASET.

LANGAN

Langan Engineering, Environmental, Surveying, Landscape Architecture and Geology, D.P.C.

300 Kimball Drive
Parsippany, NJ 07054

T: 973.560.4900 F: 973.560.4901 www.langan.com
NJ Certification of Authorization No. 24GA27996400

Project

12074 FLATLANDS AVENUE SITE
BCP SITE NO. C224353
35 INSPIRATION LANE
F/K/A 12074 FLATLANDS AVENUE

BLOCK NO. 4434, LOT NO. 1

BROOKLYN

KINGS COUNTY NEW YORK

Drawing Title

GROUNDWATER CONTOURS AND ANALYTICAL RESULTS (2018 PHASE II EI / 2023 RI)

Project No. 100688801	Figure 5
Date 5/22/2026	
Scale 1" = 60 feet	
Drawn By RDB	

© 2026 Langan

Path: \\Langan.com\data\PAR\data8\100688801\Project Data\ArcGIS\APROX\Christian Cultural Center_Overview



Location	LSV-12
Sample Name	LSV-12_022823
Sample Date	2/28/2023
Sample Type	SV
VOCs	
1,1-Dichloroethane	<4.05 UJ
1,2,4-Trimethylbenzene	38.1 J
1,2-Dichloropropane	<4.62 UJ
1,3,5-Trimethylbenzene (Mesitylene)	12.3 J
1,3-Butadiene	<2.21 UJ
2,2,4-Trimethylpentane	743 J
4-Ethyltoluene	14.3 J
Acetone	34.7 J
Benzene	29.1 J
Carbon Disulfide	51.7 J
Chloroethane	12.8 J
Chloroform	<4.88 UJ
Chloromethane	<2.07 UJ
Cis-1,2-Dichloroethene	**7.69 J**
Cyclohexane	458 J
Dichlorodifluoromethane	47.7 J
Ethanol	<47.1 UJ
Ethyl Acetate	<9.01 UJ
Ethylbenzene	72.1 J
Isopropanol	<6.15 UJ
M,P-Xylene	151 J
Methyl Ethyl Ketone (2-Butanone)	<7.37 UJ
Methyl Isobutyl Ketone (4-Methyl-2-Pentanone)	<10.2 UJ
n-Heptane	68 J
n-Hexane	233 J
o-Xylene (1,2-Dimethylbenzene)	95.1 J
Styrene	4.68 J
Tert-Butyl Alcohol	<758 UJ
Tert-Butyl Methyl Ether	<3.61 UJ
Tetrachloroethene (PCE)	90.9 J
Tetrahydrofuran	<737 UJ
Toluene	139 J
Trichloroethene (TCE)	<5.37 UJ
Trichlorofluoromethane	<5.62 UJ
Vinyl Chloride	**21.9 J**

Location	LSV-20
Sample Name	LSV-20_030123
Sample Date	3/1/2023
Sample Type	SV
VOCs	
1,1-Dichloroethane	<4.49 UJ
1,2,4-Trimethylbenzene	<5.46 UJ
1,2-Dichloropropane	<5.13 UJ
1,3,5-Trimethylbenzene (Mesitylene)	<5.46 UJ
1,3-Butadiene	3.19 J
2,2,4-Trimethylpentane	91.1 J
4-Ethyltoluene	<5.46 UJ
Acetone	36.8 J
Benzene	5.94 J
Carbon Disulfide	86.9 J
Chloroethane	<2.93 UJ
Chloroform	<5.42 UJ
Chloromethane	<2.29 UJ
Cis-1,2-Dichloroethene	<4.4 UJ
Cyclohexane	45.4 J
Dichlorodifluoromethane	65.3 J
Ethanol	<52.4 UJ
Ethyl Acetate	<10 UJ
Ethylbenzene	5.95 J
Isopropanol	<6.83 UJ
M,P-Xylene	20.9 J
Methyl Ethyl Ketone (2-Butanone)	51.3 J
Methyl Isobutyl Ketone (4-Methyl-2-Pentanone)	<11.4 UJ
n-Heptane	106 J
n-Hexane	212 J
o-Xylene (1,2-Dimethylbenzene)	8.73 J
Styrene	<4.73 UJ
Tert-Butyl Alcohol	<8.43 UJ
Tert-Butyl Methyl Ether	<4 UJ
Tetrachloroethene (PCE)	**244 J**
Tetrahydrofuran	<8.2 UJ
Toluene	174 J
Trichloroethene (TCE)	<5.97 UJ
Trichlorofluoromethane	<6.24 UJ
Vinyl Chloride	<2.84 UJ

Location	LSV-16
Sample Name	LSV-16_030123
Sample Date	3/1/2023
Sample Type	SV
VOCs	
1,1-Dichloroethane	<4.05 UJ
1,2,4-Trimethylbenzene	<4.92 UJ
1,2-Dichloropropane	<4.62 UJ
1,3,5-Trimethylbenzene (Mesitylene)	<4.92 UJ
1,3-Butadiene	4.42 J
2,2,4-Trimethylpentane	108 J
4-Ethyltoluene	<4.92 UJ
Acetone	126 J
Benzene	16.4 J
Carbon Disulfide	26.3 J
Chloroethane	<2.64 UJ
Chloroform	<4.88 UJ
Chloromethane	<2.07 UJ
Cis-1,2-Dichloroethene	**12.2 J**
Cyclohexane	181 J
Dichlorodifluoromethane	26.3 J
Ethanol	52 J
Ethyl Acetate	<9.01 UJ
Ethylbenzene	10.5 J
Isopropanol	13.8 J
M,P-Xylene	35.4 J
Methyl Ethyl Ketone (2-Butanone)	30.1 J
Methyl Isobutyl Ketone (4-Methyl-2-Pentanone)	<10.2 UJ
n-Heptane	84 J
n-Hexane	221 J
o-Xylene (1,2-Dimethylbenzene)	15.5 J
Styrene	<4.26 UJ
Tert-Butyl Alcohol	32.7 J
Tert-Butyl Methyl Ether	<3.61 UJ
Tetrachloroethene (PCE)	**332 J**
Tetrahydrofuran	<737 UJ
Toluene	29.8 J
Trichloroethene (TCE)	<5.37 UJ
Trichlorofluoromethane	<5.62 UJ
Vinyl Chloride	**23.1 J**

Location	LSV-21
Sample Name	LSV-21_022823
Sample Date	2/28/2023
Sample Type	SV
VOCs	
1,1-Dichloroethane	<3.68 U
1,2,4-Trimethylbenzene	28.4
1,2-Dichloropropane	<4.2 U
1,3,5-Trimethylbenzene (Mesitylene)	7.72
1,3-Butadiene	5.64
2,2,4-Trimethylpentane	370
4-Ethyltoluene	8.55
Acetone	133
Benzene	21.2
Carbon Disulfide	49.8
Chloroethane	<2.4 U
Chloroform	<4.44 U
Chloromethane	<1.88 U
Cis-1,2-Dichloroethene	<3.6 U
Cyclohexane	326
Dichlorodifluoromethane	24.6
Ethanol	<42.8 U
Ethyl Acetate	9.95
Ethylbenzene	23
Isopropanol	6.91
M,P-Xylene	76
Methyl Ethyl Ketone (2-Butanone)	46
Methyl Isobutyl Ketone (4-Methyl-2-Pentanone)	<9.3 U
n-Heptane	155
n-Hexane	331
o-Xylene (1,2-Dimethylbenzene)	38.3
Styrene	<3.87 U
Tert-Butyl Alcohol	<6.88 U
Tert-Butyl Methyl Ether	<3.28 U
Tetrachloroethene (PCE)	67.7
Tetrahydrofuran	<6.69 U
Toluene	46
Trichloroethene (TCE)	<4.89 U
Trichlorofluoromethane	<5.11 U
Vinyl Chloride	<2.32 U

Location	LSV-9
Sample Name	LSV-9_022823
Sample Date	2/28/2023
Sample Type	SV
VOCs	
1,1-Dichloroethane	<0.809 UJ
1,2,4-Trimethylbenzene	<0.983 UJ
1,2-Dichloropropane	<0.924 UJ
1,3,5-Trimethylbenzene (Mesitylene)	<0.983 UJ
1,3-Butadiene	<0.442 UJ
2,2,4-Trimethylpentane	<0.934 UJ
4-Ethyltoluene	<0.983 UJ
Acetone	6.89 J
Benzene	1.7 J
Carbon Disulfide	<0.623 UJ
Chloroethane	<0.528 UJ
Chloroform	<0.977 UJ
Chloromethane	1.15 J
Cis-1,2-Dichloroethene	<0.793 UJ
Cyclohexane	<0.688 UJ
Dichlorodifluoromethane	2.24 J
Ethanol	12.5 J
Ethyl Acetate	<1.8 UJ
Ethylbenzene	1.09 J
Isopropanol	4.42 J
M,P-Xylene	3.44 J
Methyl Ethyl Ketone (2-Butanone)	<1.47 UJ
Methyl Isobutyl Ketone (4-Methyl-2-Pentanone)	<2.05 UJ
n-Heptane	<0.82 UJ
n-Hexane	0.8 J
o-Xylene (1,2-Dimethylbenzene)	1.39 J
Styrene	<0.852 UJ
Tert-Butyl Alcohol	<1.52 UJ
Tert-Butyl Methyl Ether	<0.721 UJ
Tetrachloroethene (PCE)	1.49 J
Tetrahydrofuran	<1.47 UJ
Toluene	4.56 J
Trichloroethene (TCE)	<1.07 UJ
Trichlorofluoromethane	1.37 J
Vinyl Chloride	<0.511 UJ

Location	LSV-10
Sample Name	LSV-10_022823
Sample Date	2/28/2023
Sample Type	SV
VOCs	
1,1-Dichloroethane	<2.02 UJ
1,2,4-Trimethylbenzene	32.8 J
1,2-Dichloropropane	<2.31 UJ
1,3,5-Trimethylbenzene (Mesitylene)	9 J
1,3-Butadiene	1.22 J
2,2,4-Trimethylpentane	13.5 J
4-Ethyltoluene	5.8 J
Acetone	276 J
Benzene	6.96 J
Carbon Disulfide	213 J
Chloroethane	<1.32 UJ
Chloroform	<2.44 UJ
Chloromethane	10.8 J
Cis-1,2-Dichloroethene	<1.98 UJ
Cyclohexane	6.54 J
Dichlorodifluoromethane	2.58 J
Ethanol	27.1 J
Ethyl Acetate	16.9 J
Ethylbenzene	17.4 J
Isopropanol	14.8 J
M,P-Xylene	69.5 J
Methyl Ethyl Ketone (2-Butanone)	56 J
Methyl Isobutyl Ketone (4-Methyl-2-Pentanone)	<5.12 UJ
n-Heptane	40.1 J
n-Hexane	49.3 J
o-Xylene (1,2-Dimethylbenzene)	34.4 J
Styrene	<2.13 UJ
Tert-Butyl Alcohol	5.73 J
Tert-Butyl Methyl Ether	<1.8 UJ
Tetrachloroethene (PCE)	**177 J**
Tetrahydrofuran	<3.69 UJ
Toluene	40.7 J
Trichloroethene (TCE)	<2.69 UJ
Trichlorofluoromethane	<2.81 UJ
Vinyl Chloride	<1.28 UJ

Location	AA01
Sample Name	AA01_022823
Sample Date	2/28/2023
Sample Type	AA
VOCs	
1,1-Dichloroethane	<0.809 U
1,2,4-Trimethylbenzene	<0.983 U
1,2-Dichloropropane	<0.924 U
1,3,5-Trimethylbenzene (Mesitylene)	<0.983 U
1,3-Butadiene	<0.442 U
2,2,4-Trimethylpentane	<0.934 U
4-Ethyltoluene	<0.983 U
Acetone	7.79
Benzene	1.22
Carbon Disulfide	<0.623 U
Chloroethane	<0.528 U
Chloroform	<0.977 U
Chloromethane	1.16
Cis-1,2-Dichloroethene	<0.793 U
Cyclohexane	<0.688 U
Dichlorodifluoromethane	2.26
Ethanol	11.5
Ethyl Acetate	<1.8 U
Ethylbenzene	<0.869 U
Isopropanol	3.42
M,P-Xylene	<1.74 U
Methyl Ethyl Ketone (2-Butanone)	<1.47 U
Methyl Isobutyl Ketone (4-Methyl-2-Pentanone)	<2.05 U
n-Heptane	<0.82 U
n-Hexane	0.916
o-Xylene (1,2-Dimethylbenzene)	<0.869 U
Styrene	<0.852 U
Tert-Butyl Alcohol	<1.52 U
Tert-Butyl Methyl Ether	<0.721 U
Tetrachloroethene (PCE)	<1.36 U
Tetrahydrofuran	<1.47 U
Toluene	2.61
Trichloroethene (TCE)	<1.07 U
Trichlorofluoromethane	<1.29
Vinyl Chloride	<0.511 U

Location	AA02
Sample Name	AA02_030123
Sample Date	3/1/2023
Sample Type	AA
VOCs	
1,1-Dichloroethane	<0.809 U
1,2,4-Trimethylbenzene	<0.983 U
1,2-Dichloropropane	<0.924 U
1,3,5-Trimethylbenzene (Mesitylene)	<0.983 U
1,3-Butadiene	<0.442 U
2,2,4-Trimethylpentane	<0.934 U
4-Ethyltoluene	<0.983 U
Acetone	7.22
Benzene	0.853
Carbon Disulfide	<0.623 U
Chloroethane	<0.528 U
Chloroform	<0.977 U
Chloromethane	0.956
Cis-1,2-Dichloroethene	<0.793 U
Cyclohexane	<0.688 U
Dichlorodifluoromethane	2.22
Ethanol	<9.42 U
Ethyl Acetate	<1.8 U
Ethylbenzene	<0.869 U
Isopropanol	1.71
M,P-Xylene	<1.74 U
Methyl Ethyl Ketone (2-Butanone)	<1.47 U
Methyl Isobutyl Ketone (4-Methyl-2-Pentanone)	<2.05 U
n-Heptane	2.12
n-Hexane	<0.705 U
o-Xylene (1,2-Dimethylbenzene)	<0.869 U
Styrene	<0.852 U
Tert-Butyl Alcohol	<1.52 U
Tert-Butyl Methyl Ether	<0.721 U
Tetrachloroethene (PCE)	<1.36 U
Tetrahydrofuran	<1.47 U
Toluene	1.1
Trichloroethene (TCE)	<1.07 U
Trichlorofluoromethane	<1.12 U
Vinyl Chloride	<0.511 U

Location	LSV-11
Sample Name	LSV-11_022823
Sample Date	2/28/2023
Sample Type	SV
VOCs	
1,1-Dichloroethane	<1.62 UJ
1,2,4-Trimethylbenzene	24.7 J
1,2-Dichloropropane	<1.85 UJ
1,3,5-Trimethylbenzene (Mesitylene)	7.62 J
1,3-Butadiene	1.17 J
2,2,4-Trimethylpentane	85.5 J
4-Ethyltoluene	5.7 J
Acetone	152 J
Benzene	13.1 J
Carbon Disulfide	210 J
Chloroethane	<1.06 UJ
Chloroform	<1.95 UJ
Chloromethane	<0.826 UJ
Cis-1,2-Dichloroethene	<1.59 UJ
Cyclohexane	21.3 J
Dichlorodifluoromethane	3.25 J
Ethanol	53.3 J
Ethyl Acetate	5.08 J
Ethylbenzene	19.8 J
Isopropanol	7.45 J
M,P-Xylene	73 J
Methyl Ethyl Ketone (2-Butanone)	31.6 J
Methyl Isobutyl Ketone (4-Methyl-2-Pentanone)	<4.1 UJ
n-Heptane	32.7 J
n-Hexane	51.5 J
o-Xylene (1,2-Dimethylbenzene)	45.2 J
Styrene	1.95 J
Tert-Butyl Alcohol	5.49 J
Tert-Butyl Methyl Ether	<1.44 UJ
Tetrachloroethene (PCE)	67 J
Tetrahydrofuran	4.04 J
Toluene	39.9 J
Trichloroethene (TCE)	<2.15 UJ
Trichlorofluoromethane	<2.25 UJ
Vinyl Chloride	<1.02 UJ

Location	LSV-14
Sample Name	LSV-14_022823
Sample Date	2/28/2023
Sample Type	SV
VOCs	
1,1-Dichloroethane	<3.11 U
1,2,4-Trimethylbenzene	20.9
1,2-Dichloropropane	<3.55 U
1,3,5-Trimethylbenzene (Mesitylene)	11.5
1,3-Butadiene	2.72
2,2,4-Trimethylpentane	270
4-Ethyltoluene	14.3
Acetone	124
Benzene	275
Carbon Disulfide	26.3
Chloroethane	<2.03 U
Chloroform	<3.76 U
Chloromethane	<1.59 U
Cis-1,2-Dichloroethene	<3.05 U
Cyclohexane	537
Dichlorodifluoromethane	<3.8 U
Ethanol	<36.2 U
Ethyl Acetate	<6.92 U
Ethylbenzene	162
Isopropanol	<4.72 U
M,P-Xylene	174
Methyl Ethyl Ketone (2-Butanone)	32.4
Methyl Isobutyl Ketone (4-Methyl-2-Pentanone)	<7.87 U
n-Heptane	327
n-Hexane	567
o-Xylene (1,2-Dimethylbenzene)	155
Styrene	4.56
Tert-Butyl Alcohol	8.12
Tert-Butyl Methyl Ether	<2.77 U
Tetrachloroethene (PCE)	**255**
Tetrahydrofuran	<5.66 U
Toluene	358
Trichloroethene (TCE)	<4.13 U
Trichlorofluoromethane	<4.32 U
Vinyl Chloride	**6.26**

Location	LSV-17
Sample Name	LSV-17_030123
Sample Date	3/1/2023
Sample Type	SV
VOCs	
1,1-Dichloroethane	<3.11 UJ
1,2,4-Trimethylbenzene	<3.78 UJ
1,2-Dichloropropane	<3.55 UJ
1,3,5-Trimethylbenzene (Mesitylene)	<3.78 UJ
1,3-Butadiene	<1.7 UJ
2,2,4-Trimethylpentane	69.6 J
4-Ethyltoluene	<3.78 UJ
Acetone	26.1 J
Benzene	3.87 J
Carbon Disulfide	19 J
Chloroethane	<2.03 UJ
Chloroform	<3.76 UJ
Chloromethane	<1.59 UJ
Cis-1,2-Dichloroethene	<3.05 UJ
Cyclohexane	59.9 J
Dichlorodifluoromethane	136 J
Ethanol	<36.2 UJ
Ethyl Acetate	<6.92 UJ
Ethylbenzene	5.39 J
Isopropanol	11 J
M,P-Xylene	20.8 J
Methyl Ethyl Ketone (2-Butanone)	26.3 J
Methyl Isobutyl Ketone (4-Methyl-2-Pentanone)	14.3 J
n-Heptane	28.4 J
n-Hexane	92.3 J
o-Xylene (1,2-Dimethylbenzene)	8.04 J
Styrene	<3.27 UJ
Tert-Butyl Alcohol	19.8 J
Tert-Butyl Methyl Ether	<2.77 UJ
Tetrachloroethene (PCE)	**201 J**
Tetrahydrofuran	<5.66 UJ
Toluene	15.8 J
Trichloroethene (TCE)	<4.13 UJ
Trichlorofluoromethane	<4.32 UJ
Vinyl Chloride	<1.97 UJ

Location	LSV-18
Sample Name	LSV-18_030123
Sample Date	3/1/2023
Sample Type	SV
VOCs	
1,1-Dichloroethane	3.91
1,2,4-Trimethylbenzene	3.02
1,2-Dichloropropane	<2.72 U
1,3,5-Trimethylbenzene (Mesitylene)	<2.89 U
1,3-Butadiene	2.61
2,2,4-Trimethylpentane	142
4-Ethyltoluene	<2.89 U
Acetone	15.9
Benzene	33.5
Carbon Disulfide	52.6
Chloroethane	5.57
Chloroform	<2.87 U
Chloromethane	1.34
Cis-1,2-Dichloroethene	5.99
Cyclohexane	75
Dichlorodifluoromethane	269
Ethanol	<277 U
Ethyl Acetate	<5.3 U
Ethylbenzene	8.04
Isopropanol	3.79
M,P-Xylene	27
Methyl Ethyl Ketone (2-Butanone)	<4.34 U
Methyl Isobutyl Ketone (4-Methyl-2-Pentanone)	<6.02 U
n-Heptane	59.4
n-Hexane	299
o-Xylene (1,2-Dimethylbenzene)	12.5
Styrene	<2.5 U
Tert-Butyl Alcohol	<4.46 U
Tert-Butyl Methyl Ether	<2.12 U
Tetrachloroethene (PCE)	**336**
Tetrahydrofuran	<4.34 U
Toluene	32
Trichloroethene (TCE)	<3.16 U
Trichlorofluoromethane	<3.3 U
Vinyl Chloride	**13.1**

Location	LSV-19
Sample Name	LSV-19_030123
Sample Date	3/1/2023
Sample Type	SV
VOCs	
1,1-Dichloroethane	<0.809 U
1,2,4-Trimethylbenzene	4.49
1,2-Dichloropropane	<0.924 U
1,3,5-Trimethylbenzene (Mesitylene)	1.45
1,3-Butadiene	<0.442 U
2,2,4-Trimethylpentane	68.7
4-Ethyltoluene	2.77
Acetone	4.66
Benzene	15.7
Carbon Disulfide	9.5
Chloroethane	2.3
Chloroform	1.26
Chloromethane	<0.413 U
Cis-1,2-Dichloroethene	**8.88**
Cyclohexane	32.7
Dichlorodifluoromethane	53.9
Ethanol	<9.42 U
Ethyl Acetate	<1.8 U
Ethylbenzene	7.69
Isopropanol	2.85
M,P-Xylene	28.1
Methyl Ethyl Ketone (2-Butanone)	<1.47 U
Methyl Isobutyl Ketone (4-Methyl-2-Pentanone)	<2.05 U
n-Heptane	41.8
n-Hexane	129
o-Xylene (1,2-Dimethylbenzene)	13.3
Styrene	1.19
Tert-Butyl Alcohol	<1.52 U
Tert-Butyl Methyl Ether	3.71
Tetrachloroethene (PCE)	**340**
Tetrahydrofuran	1.7
Toluene	26.8
Trichloroethene (TCE)	1.83
Trichlorofluoromethane	<1.12 U
Vinyl Chloride	**10.9**

Location	LSV-15
Sample Name	LSV-15_030123
Sample Date	3/1/2023
Sample Type	SV
VOCs	
1,1-Dichloroethane	<5.06 UJ
1,2,4-Trimethylbenzene	7.23 J
1,2-Dichloropropane	<5.78 UJ
1,3,5-Trimethylbenzene (Mesitylene)	<6.15 UJ
1,3-Butadiene	<2.77 UJ
2,2,4-Trimethylpentane	995 J
4-Ethyltoluene	<6.15 UJ
Acetone	<14.8 UJ
Benzene	31.9 J
Carbon Disulfide	22.8 J
Chloroethane	<3.3 UJ
Chloroform	<6.1 UJ
Chloromethane	<2.58 UJ
Cis-1,2-Dichloroethene	4.96 J
Cyclohexane	874 J
Dichlorodifluoromethane	9.49 J
Ethanol	<58.8 UJ
Ethyl Acetate	<11.2 UJ
Ethylbenzene	23 J
Isopropanol	11.8 J
M,P-Xylene	49.1 J
Methyl Ethyl Ketone (2-Butanone)	20.7 J
Methyl Isobutyl Ketone (4-Methyl-2-Pentanone)	<12.8 UJ
n-Heptane	200 J
n-Hexane	744 J
o-Xylene (1,2-Dimethylbenzene)	29.4 J
Styrene	<5.32 UJ
Tert-Butyl Alcohol	19.9 J
Tert-Butyl Methyl Ether	46.9 J
Tetrachloroethene (PCE)	**332 J**
Tetrahydrofuran	<9.2 UJ
Toluene	39.9 J
Trichloroethene (TCE)	<6.72 UJ
Trichlorofluoromethane	<7.02 UJ
Vinyl Chloride	**68 J**

Location	LSV-13	LSV-13
Sample Name	LSV-13_030123	DUP05_030123
Sample Date	3/1/2023	3/1/2023
Sample Type	SV	SV
VOCs		
1,1-Dichloroethane	<6.76 UJ	<138 UJ
1,2,4-Trimethylbenzene	<8.21 UJ	<167 UJ
1,2-Dichloropropane	28 J	<157 UJ
1,3,5-Trimethylbenzene (Mesitylene)	<8.21 UJ	<167 UJ
1,3-Butadiene	4.36 J	<75.2 UJ
2,2,4-Trimethylpentane	3,000 J	4,570 J
4-Ethyltoluene	<8.21 UJ	<167 UJ
Acetone	50.6 J	<404 UJ
Benzene	45.4 J	<109 UJ
Carbon Disulfide	73.2 J	<106 UJ
Chloroethane	<4.41 UJ	<89.7 UJ
Chloroform	<8.16 UJ	<166 UJ
Chloromethane	<3.45 UJ	<70.2 UJ
Cis-1,2-Dichloroethene	**10.4 J**	<135 UJ
Cyclohexane	19,700 J	21,200 J
Dichlorodifluoromethane	<8.26 UJ	<168 UJ
Ethanol	<78.6 UJ	<1,600 UJ
Ethyl Acetate	<15 UJ	<306 UJ
Ethylbenzene	<725 UJ	<148 UJ
Isopropanol	<10.3 UJ	<209 UJ
M,P-Xylene	29.6 J	<295 UJ
Methyl Ethyl Ketone (2-Butanone)	<12.3 UJ	<251 UJ
Methyl Isobutyl Ketone (4-Methyl-2-Pentanone)	<17.1 UJ	<348 UJ
n-Heptane	13,200 J	15,200 J
n-Hexane	45,800 J	49,300 J
o-Xylene (1,2-Dimethylbenzene)	10.6 J	<148 UJ
Styrene	<7.11 UJ	<145 UJ
Tert-Butyl Alcohol	<12.6 UJ	<258 UJ
Tert-Butyl Methyl Ether	<6.02 UJ	<123 UJ
Tetrachloroethene (PCE)	**186 J**	**235 J**
Tetrahydrofuran	<12.3 UJ	<251 UJ
Toluene	169 J	210 J
Trichloroethene (TCE)	<8.97 UJ	<183 UJ
Trichlorofluoromethane	<9.38 UJ	<191 UJ
Vinyl Chloride	**14.2 J**	<86.9 UJ

Analyte	NYSDOH Decision Matrices Minimum Concentrations
VOCs	
1,1-Dichloroethane	NS
1,2,4-Trimethylbenzene	NS
1,2-Dichloropropane	NS
1,3,5-Trimethylbenzene (Mesitylene)	NS
1,3-Butadiene	NS
2,2,4-Trimethylpentane	NS
4-Ethyltoluene	NS
Acetone	NS
Benzene	NS
Carbon Disulfide	NS
Chloroethane	NS
Chloroform	NS
Chloromethane	NS
Cis-1,2-Dichloroethene	6
Cyclohexane	NS
Dichlorodifluoromethane	NS
Ethanol	NS
Ethyl Acetate	NS
Ethylbenzene	NS
Isopropanol	NS
M,P-Xylene	NS
Methyl Ethyl Ketone (2-Butanone)	NS
Methyl Isobutyl Ketone (4-Methyl-2-Pentanone)	NS
n-Heptane	NS
n-Hexane	NS
o-Xylene (1,2-Dimethylbenzene)	NS
Styrene	NS
Tert-Butyl Alcohol	NS
Tert-Butyl Methyl Ether	NS
Tetrachloroethene (PCE)	100
Tetrahydrofuran	NS
Toluene	NS
Trichloroethene (TCE)	6
Trichlorofluoromethane	NS
Vinyl Chloride	6

Exceedance Summary:

10 - Result exceeds minimum soil vapor concentrations recommending mitigation

0 60 120

SCALE IN FEET

Legend

- Site Boundary
- Historical Test Pit Location
- 2023 RI Soil Vapor Point Location

NOTES:
1. AERIAL IMAGERY PROVIDED BY NEARMAP LTD., COLLECTED 07/03/2025.
2. 2018 PHASE II EI SAMPLE AND TEST PIT LOCATIONS OBTAINED FROM THE PHASE II EI REPORT CONDUCTED BY LANGAN ENGINEERING, ENVIRONMENTAL, SURVEY, LANDSCAPE ARCHITECTURE, AND GEOLOGY, D.P.C DATED 5/30/2018.
3. SAMPLE LOCATIONS FOR THE RI WERE COLLECTED USING GPS LOCATION TECHNIQUES.

LANGAN

Langan Engineering, Environmental, Surveying, Landscape Architecture and Geology, D.P.C.

300 Kimball Drive
Parsippany, NJ 07054

T: 973.560.4900 F: 973.560.4901 www.langan.com
NJ Certification of Authorization No. 24GA27996400

Project
12074 FLATLANDS AVENUE SITE
BCP SITE NO. C224353
35 INSPIRATION LANE
F/K/A 12074 FLATLANDS AVENUE

BLOCK NO. 4434, LOT NO. 1

BROOKLYN

KINGS COUNTY NEW YORK

Drawing Title

SOIL VAPOR ANALYTICAL RESULTS

Project No. 100688801	Figure 6
Date 5/22/2026	
Scale 1" = 60 feet	
Drawn By RDB	

© 2026 Langan

Path: I:\Langan.com\data\PAR\data8\100688801\Project Data\ArcGIS\APRX\Christian Cultural Center_Overview

Legend

- Site Boundary
- Tax Parcel
- Groundwater Flow Direction
- Proposed Monitoring Wells

FLATLANDS AVENUE

PENNSYLVANIA AVENUE

LMW-27

LMW-26

B5_ MW-09

B5_LMW-06

LMW-28

LMW-29

Block:4434
Lot:1

Block:4434
Lot:1

Block:4434
Lot:10

Block:4430
Lot:1

Block:4434
Lot:60

Block:4431
Lot:70

50 0 50

SCALE IN FEET

REFERENCES:
1. PARCEL BOUNDARIES OBTAINED FROM THE NEW YORK CITY DEPARTMENT OF PLANNING'S MAPPLUTO 25V1, UPDATED 2025.
2. SEGMENT 3 & 4 - FOUNDATION PLAN OBTAINED FROM FIGURE FO-100.00, PREPARED BY IUV PHASE 1B OWNER LLC.

STATE OF NEW YORK · RONALD D. BOYER · 085831 · LICENSED PROFESSIONAL ENGINEER

SIGNATURE 5/22/2026 DATE SIGNED

RONALD BOYER
PROFESSIONAL ENGINEER NY LIC. No. 085831-1

LANGAN
300 Kimball Drive
Parsippany, NJ 07054
T: 973.560.4900 F: 973.560.4901 www.langan.com

Langan Engineering & Environmental Services, Inc.
Langan Engineering, Environmental, Surveying, Landscape Architecture and Geology, D.P.C.
Langan International LLC
Collectively known as Langan

NJ CERTIFICATE OF AUTHORIZATION No. 24GA27996400

Project
12074 FLATLANDS AVENUE SITE
BCP SITE NO. C224353
35 INSPIRATION LANE
F/K/A 12074 FLATLANDS AVENUE

BLOCK No. 4434, LOT No. 1

BROOKLYN

KINGS COUNTY NEW YORK

Drawing Title

PROPOSED POST CONSTRUCTION MONITORING WELL LOCATION PLAN

Project No.	Figure
100688801	7
Date: 5/7/2026	
Scale: 1" = 50"	
Drawn By: RDB	

© 2026 Langan

Path: C:\Users\rboekenheide\Desktop\GIS_Projects\PAR - 101\Christian Cultural Center - 10068880_\APRX\Christian Cultural Center_Overview\Christian Cultural Center_Overview.aprx

LANGAN
300 Kimball Drive
Parsippany, NJ 07054
T: 973.560.4900 F: 973.560.4901 www.langan.com

Langan Engineering & Environmental Services, Inc.
Langan Engineering, Environmental, Surveying, Landscape Architecture and Geology, D.P.C.
Langan International LLC
Collectively known as Langan

NJ CERTIFICATE OF AUTHORIZATION No. 24GA27996400

Project
12074 Flatlands Avenue Site
BCP Site No. C224353
35 Inspiration Lane
F/K/A 12074 Flatlands Avenue
BLOCK No. 4434, LOT No. 1
BROOKLYN
KINGS COUNTY NEW YORK

Drawing Title
TRUCK ROUTE MAP

Project No. 100688801	Figure 8
Date 12/1/2023	
Scale 1"=7,000'	
Drawn By RDB	

© 2026 Langan

Path: \\Langan.com\data\PAR\data8\100688801\Project Data\ArcGIS\APRX\Christian Cultural Center_Overview

APPENDIX A

Environmental Easement, Site Survey and Metes/Bounds Description

LANGAN

NYC DEPARTMENT OF FINANCE
OFFICE OF THE CITY REGISTER

This page is part of the instrument. The City Register will rely on the information provided by you on this page for purposes of indexing this instrument. The information on this page will control for indexing purposes in the event of any conflict with the rest of the document.

2025092600676001001ECD71

RECORDING AND ENDORSEMENT COVER PAGE **PAGE 1 OF 13**

Document ID: 2025092600676001 Document Date: 09-17-2025 Preparation Date: 09-26-2025
Document Type: EASEMENT
Document Page Count: 11

PRESENTER:	**RETURN TO:**
81345645/2738253 STEWART TITLE GUARANTY COMPANY 711 WESTCHESTER AVENUE, SUITE 302 WHITE PLAINS, NY 10604 914-993-9393 NYMETRORECORDINGS@STEWART.COM	81345645/2738253 STEWART TITLE GUARANTY COMPANY 711 WESTCHESTER AVENUE, SUITE 302 WHITE PLAINS, NY 10604 914-993-9393 NYMETRORECORDINGS@STEWART.COM

PROPERTY DATA

Borough	Block	Lot	Unit	Address
BROOKLYN	4434	1	Entire Lot	35 INSPIRATION LANE

Property Type: NON-RESIDENTIAL VACANT LAND Easement

CROSS REFERENCE DATA

CRFN_____ *or* DocumentID_____ *or* _____ Year_____ Reel____ Page_____ *or* File Number_____

PARTIES

GRANTOR/SELLER:	**GRANTEE/BUYER:**
IUV PHASE 1B HOUSING DEVELOPMENT FUND CORPORATION C/O: CHRISTIAN CULTURAL CENTER, INC., 12020 FLATLANDS AVENUE ☒ Additional Parties Listed on Continuation Page	NYS DEPARTMENT OF ENVIRONMENTAL CONSERVATION 625 BROADWAY ALBANY, NY 12233-1500

FEES AND TAXES

Mortgage :		
Mortgage Amount:	$	0.00
Taxable Mortgage Amount:	$	0.00
Exemption:		
TAXES: County (Basic):	$	0.00
City (Additional):	$	0.00
Spec (Additional):	$	0.00
TASF:	$	0.00
MTA:	$	0.00
NYCTA:	$	0.00
Additional MRT:	$	0.00
TOTAL:	$	0.00
Recording Fee:	$	92.00
Affidavit Fee:	$	0.00

Filing Fee:	$	0.00
NYC Real Property Transfer Tax:	$	0.00
NYS Real Estate Transfer Tax:	$	0.00

RECORDED OR FILED IN THE OFFICE OF THE CITY REGISTER OF THE CITY OF NEW YORK
Recorded/Filed 09-26-2025 16:41
City Register File No.(CRFN): **2025000264211**

City Register Official Signature

NYC DEPARTMENT OF FINANCE
OFFICE OF THE CITY REGISTER

2025092600676001001CCFF1

RECORDING AND ENDORSEMENT COVER PAGE (CONTINUATION) PAGE 2 OF 13

Document ID: 2025092600676001 Document Date: 09-17-2025 Preparation Date: 09-26-2025
Document Type: EASEMENT

PARTIES

GRANTOR/SELLER:
IUV PHASE 1B LIHTC OWNER, LLC
C/O: GOTHAM ORGANIZATION, INC., 111 FIFTH AVENUE, 9TH FLOOR
NEW YORK, NY 10003

GRANTOR/SELLER:
IUV PHASE IB OWNER, LLC
C/O: GOTHAM ORGANIZTION, INC., 111 FIFTH AVENUE, 9TH FLOOR
NEW YORK, NY 10003

ENVIRONMENTAL EASEMENT GRANTED PURSUANT TO ARTICLE 71, TITLE 36 OF THE NEW YORK STATE ENVIRONMENTAL CONSERVATION LAW

THIS INDENTURE made this 17th day of September, 2025, between Owner(s), IUV Phase 1B Housing Development Fund Corporation, having an office at c/o: Christian Cultural Center Inc. 12020 Flatlands Avenue, Brooklyn, NY (Grantor Fee Owner and Leaseholder), IUV Phase 1B Owner, LLC, having an office at c/o Gotham Organization, Inc., 111 Fifth Avenue, 9th Floor, New York, NY (Grantor Beneficial Owner and Leaseholder), and IUV Phase 1B LIHTC Owner, LLC with an address of c/o Gotham Organization, Inc., 111 Fifth Avenue, 9th Floor, New York, NY (Grantor Beneficial Owner; and together with Grantor Fee Owner and Leaseholder and Grantor Beneficial Owner and Leaseholder collectively, the "Grantor"), and The People of the State of New York (the "Grantee"), acting through their Commissioner of the Department of Environmental Conservation (the "Commissioner", or "NYSDEC" or "Department" as the context requires) with its headquarters located at 625 Broadway, Albany, New York 12233,

WHEREAS, the Legislature of the State of New York has declared that it is in the public interest to encourage the remediation of abandoned and likely contaminated properties ("sites") that threaten the health and vitality of the communities they burden while at the same time ensuring the protection of public health and the environment; and

WHEREAS, the Legislature of the State of New York has declared that it is in the public interest to establish within the Department a statutory environmental remediation program that includes the use of Environmental Easements as an enforceable means of ensuring the performance of operation, maintenance, and/or monitoring requirements and the restriction of future uses of the land, when an environmental remediation project leaves residual contamination at levels that have been determined to be safe for a specific use, but not all uses, or which includes engineered structures that must be maintained or protected against damage to perform properly and be effective, or which requires groundwater use or soil management restrictions; and

WHEREAS, the Legislature of the State of New York has declared that Environmental Easement shall mean an interest in real property, created under and subject to the provisions of Article 71, Title 36 of the New York State Environmental Conservation Law ("ECL") which contains a use restriction and/or a prohibition on the use of land in a manner inconsistent with engineering controls which are intended to ensure the long term effectiveness of a site remedial program or eliminate potential exposure pathways to hazardous waste or petroleum; and

WHEREAS, Grantor Fee Owner, is the owner of real property located at the address of 35 Inspiration Lane a/k/a 12074 Flatlands Avenue, Brooklyn in the City of New York, County of Kings and State of New York, known and designated on the tax map of the County Clerk of Kings as tax map parcel number: Block 4434 Lot 1, being the same as that property conveyed to Grantor Fee Owner by deed dated March 21, 2025 and recorded in the City Register of the City of New York in CRFN 2025000083388. The property subject to this Environmental Easement (the "Controlled Property") comprises approximately 2.084 +/- acres and is hereinafter more fully described in the Land Title Survey dated December 12, 2024, last revised March 10, 2025, prepared by Andrew Joseph Flanagan, which will be attached to the Site Management Plan. The

https://a836-acris.nyc.gov/DS/DocumentSearch/DocumentImageView?doc_id=2025092600676001

Controlled Property description is set forth in and attached hereto as Schedule A;

WHEREAS, Grantor Beneficial Owner and Leaseholder, and Grantor Beneficial Owner, are the owners of the beneficial interest in the Controlled Property being the same as a portion of that beneficial interest conveyed to Grantor Beneficial Owners by means of a Declaration of Interest and Nominee Agreement between Grantor Fee Owner and Grantor Beneficial Owners dated as of March 21, 2025 and recorded in City Register of the City of New York on March 26, 2025 as CRFN # 2025000083389;

WHEREAS, Grantor Fee Owner and Leaseholder, and Beneficial Owner and Leaseholder, are the holders of a 40-year lease interest in the Controlled Property, as memorialized in a Memorandum of Master Lease dated March 21, 2025 and recorded in the City Register of the City of New York on March 26, 2025 as CRFN # 2025000083390; and

WHEREAS, the Department accepts this Environmental Easement in order to ensure the protection of public health and the environment and to achieve the requirements for remediation established for the Controlled Property until such time as this Environmental Easement is extinguished pursuant to ECL Article 71, Title 36; and

NOW THEREFORE, in consideration of the mutual covenants contained herein and the terms and conditions of Brownfield Cleanup Agreement Index Number: C224353-05-22, Grantor conveys to Grantee a permanent Environmental Easement pursuant to ECL Article 71, Title 36 in, on, over, under, and upon the Controlled Property as more fully described herein ("Environmental Easement").

1. Purposes. Grantor and Grantee acknowledge that the Purposes of this Environmental Easement are: to convey to Grantee real property rights and interests that will run with the land in perpetuity in order to provide an effective and enforceable means of encouraging the reuse and redevelopment of this Controlled Property at a level that has been determined to be safe for a specific use while ensuring the performance of operation, maintenance, and/or monitoring requirements; and to ensure the restriction of future uses of the land that are inconsistent with the above-stated purpose.

2. Institutional and Engineering Controls. The controls and requirements listed in the Department approved Site Management Plan ("SMP") including any and all Department approved amendments to the SMP are incorporated into and made part of this Environmental Easement. These controls and requirements apply to the use of the Controlled Property, run with the land, are binding on the Grantor and the Grantor's successors and assigns, and are enforceable in law or equity against any owner of the Controlled Property, any lessees and any person using the Controlled Property.

A. (1) The Controlled Property may be used for:

Restricted Residential as described in 6 NYCRR Part 375-1.8(g)(2)(ii), Commercial as described in 6 NYCRR Part 375-1.8(g)(2)(iii) and Industrial as described in 6 NYCRR Part 375-1.8(g)(2)(iv)

(2) All Engineering Controls must be operated and maintained as specified in

https://a836-acris.nyc.gov/DS/DocumentSearch/DocumentImageView?doc_id=2025092600676001

the Site Management Plan (SMP);

(3) All Engineering Controls must be inspected at a frequency and in a manner defined in the SMP;

(4) The use of groundwater underlying the property is prohibited without necessary water quality treatment as determined by the NYSDOH or the Kings County Department of Health to render it safe for use as drinking water or for industrial purposes, and the user must first notify and obtain written approval to do so from the Department;

(5) Groundwater and other environmental or public health monitoring must be performed as defined in the SMP;

(6) Data and information pertinent to Site Management of the Controlled Property must be reported at the frequency and in a manner defined in the SMP;

(7) All future activities on the property that will disturb remaining contaminated material must be conducted in accordance with the SMP;

(8) Monitoring to assess the performance and effectiveness of the remedy must be performed as defined in the SMP;

(9) Operation, maintenance, monitoring, inspection, and reporting of any mechanical or physical components of the remedy shall be performed as defined in the SMP;

(10) Access to the site must be provided to agents, employees or other representatives of the State of New York with reasonable prior notice to the property owner to assure compliance with the restrictions identified by this Environmental Easement.

B. The Controlled Property shall not be used for Residential purposes as defined in 6NYCRR 375-1.8(g)(2)(i), and the above-stated engineering controls may not be discontinued without an amendment or extinguishment of this Environmental Easement.

C. The SMP describes obligations that the Grantor assumes on behalf of Grantor, its successors and assigns. The Grantor's assumption of the obligations contained in the SMP which may include sampling, monitoring, and/or operating a treatment system, and providing certified reports to the NYSDEC, is and remains a fundamental element of the Department's determination that the Controlled Property is safe for a specific use, but not all uses. The SMP may be modified in accordance with the Department's statutory and regulatory authority. The Grantor and all successors and assigns, assume the burden of complying with the SMP and obtaining an up-to-date version of the SMP from:

Site Control Section
Division of Environmental Remediation
NYSDEC
625 Broadway
Albany, New York 12233
Phone: (518) 402-9553

https://a836-acris.nyc.gov/DS/DocumentSearch/DocumentImageView?doc_id=2025092600676001

D. Grantor must provide all persons who acquire any interest in the Controlled Property a true and complete copy of the SMP that the Department approves for the Controlled Property and all Department-approved amendments to that SMP.

E. Grantor covenants and agrees that until such time as the Environmental Easement is extinguished in accordance with the requirements of ECL Article 71, Title 36 of the ECL, the property deed and all subsequent instruments of conveyance relating to the Controlled Property shall state in at least fifteen-point bold-faced type:

This property is subject to an Environmental Easement held by the New York State Department of Environmental Conservation pursuant to Title 36 of Article 71 of the Environmental Conservation Law.

F. Grantor covenants and agrees that this Environmental Easement shall be incorporated in full or by reference in any leases, licenses, or other instruments granting a right to use the Controlled Property.

G. Grantor covenants and agrees that it shall, at such time as NYSDEC may require, submit to NYSDEC a written statement by an expert the NYSDEC may find acceptable certifying under penalty of perjury, in such form and manner as the Department may require, that:

(1) the inspection of the site to confirm the effectiveness of the institutional and engineering controls required by the remedial program was performed under the direction of the individual set forth at 6 NYCRR Part 375-1.8(h)(3).

(2) the institutional controls and/or engineering controls employed at such site:

(i) are in-place;

(ii) are unchanged from the previous certification, or that any identified changes to the controls employed were approved by the NYSDEC and that all controls are in the Department-approved format; and

(iii) that nothing has occurred that would impair the ability of such control to protect the public health and environment;

(3) the owner will continue to allow access to such real property to evaluate the continued maintenance of such controls;

(4) nothing has occurred that would constitute a violation or failure to comply with any site management plan for such controls;

(5) the report and all attachments were prepared under the direction of, and reviewed by, the party making the certification;

(6) to the best of his/her knowledge and belief, the work and conclusions described in this certification are in accordance with the requirements of the site remedial program, and generally accepted engineering practices; and

(7) the information presented is accurate and complete.

3. Right to Enter and Inspect. Grantee, its agents, employees, or other representatives of the

https://a836-acris.nyc.gov/DS/DocumentSearch/DocumentImageView?doc_id=2025092600676001

State may enter and inspect the Controlled Property in a reasonable manner and at reasonable times to assure compliance with the above-stated restrictions.

4. Reserved Grantor's Rights. Grantor reserves for itself, its assigns, representatives, and successors in interest with respect to the Property, all rights as fee owner of the Property, including:

A. Use of the Controlled Property for all purposes not inconsistent with, or limited by the terms of this Environmental Easement;

B. The right to give, sell, assign, or otherwise transfer part or all of the underlying fee interest to the Controlled Property, subject and subordinate to this Environmental Easement;

5. Enforcement

A. This Environmental Easement is enforceable in law or equity in perpetuity by Grantor, Grantee, or any affected local government, as defined in ECL Section 71-3603, against the owner of the Property, any lessees, and any person using the land. Enforcement shall not be defeated because of any subsequent adverse possession, laches, estoppel, or waiver. It is not a defense in any action to enforce this Environmental Easement that: it is not appurtenant to an interest in real property; it is not of a character that has been recognized traditionally at common law; it imposes a negative burden; it imposes affirmative obligations upon the owner of any interest in the burdened property; the benefit does not touch or concern real property; there is no privity of estate or of contract; or it imposes an unreasonable restraint on alienation.

B. If any person violates this Environmental Easement, the Grantee may revoke the Certificate of Completion with respect to the Controlled Property.

C. Grantee shall notify Grantor of a breach or suspected breach of any of the terms of this Environmental Easement. Such notice shall set forth how Grantor can cure such breach or suspected breach and give Grantor a reasonable amount of time from the date of receipt of notice in which to cure. At the expiration of such period of time to cure, or any extensions granted by Grantee, the Grantee shall notify Grantor of any failure to adequately cure the breach or suspected breach, and Grantee may take any other appropriate action reasonably necessary to remedy any breach of this Environmental Easement, including the commencement of any proceedings in accordance with applicable law.

D. The failure of Grantee to enforce any of the terms contained herein shall not be deemed a waiver of any such term nor bar any enforcement rights.

6. Notice. Whenever notice to the Grantee (other than the annual certification) or approval from the Grantee is required, the Party providing such notice or seeking such approval shall identify the Controlled Property by referencing the following information:

County, NYSDEC Site Number, NYSDEC Brownfield Cleanup Agreement, State Assistance Contract or Order Number, and the County tax map number or the Liber and Page or computerized system identification number.

Parties shall address correspondence to: Site Number: C224353

https://a836-acris.nyc.gov/DS/DocumentSearch/DocumentImageView?doc_id=2025092600676001 7/13

Office of General Counsel
NYSDEC
625 Broadway
Albany New York 12233-5500

With a copy to:

Site Control Section
Division of Environmental Remediation
NYSDEC
625 Broadway
Albany, NY 12233

All notices and correspondence shall be delivered by hand, by registered mail or by Certified mail and return receipt requested. The Parties may provide for other means of receiving and communicating notices and responses to requests for approval.

7. Recordation. Grantor shall record this instrument, within thirty (30) days of execution of this instrument by the Commissioner or her/his authorized representative in the office of the recording officer for the county or counties where the Property is situated in the manner prescribed by Article 9 of the Real Property Law.

8. Amendment. Any amendment to this Environmental Easement may only be executed by the Commissioner of the New York State Department of Environmental Conservation or the Commissioner's Designee and filed with the office of the recording officer for the county or counties where the Property is situated in the manner prescribed by Article 9 of the Real Property Law.

9. Extinguishment. This Environmental Easement may be extinguished only by a release by the Commissioner of the New York State Department of Environmental Conservation, or the Commissioner's Designee, and filed with the office of the recording officer for the county or counties where the Property is situated in the manner prescribed by Article 9 of the Real Property Law.

10. Joint Obligation. If there are two or more parties identified as Grantor herein, the obligations imposed by this instrument upon them shall be joint and several.

11. Consistency with the SMP. To the extent there is any conflict or inconsistency between the terms of this Environmental Easement and the SMP, regarding matters specifically addressed by the SMP, the terms of the SMP will control.

Remainder of Page Intentionally Left Blank

https://a836-acris.nyc.gov/DS/DocumentSearch/DocumentImageView?doc_id=2025092600676001 8/13

IN WITNESS WHEREOF, Grantor Fee Owner and Leaseholder has caused this instrument to be signed in its name.

IUV Phase 1B Housing Development Fund Corporation:

By: James Halek

Print Name: James Halek

Title: ~~Authorized Signatory~~ Date: 9-8-25

Grantor's Acknowledgment

STATE OF ~~NEW YORK~~ Texas)
) ss:
COUNTY OF Denton)

On the 8 day of September, in the year 2025 before me, the undersigned, personally appeared James Halek, personally known to me or proved to me on the basis of satisfactory evidence to be the individual(s) whose name is (are) subscribed to the within instrument and acknowledged to me that he/she/they executed the same in his/her/their capacity(ies), and that by his/her/their signature(s) on the instrument, the individual(s), or the person upon behalf of which the individual(s) acted, executed the instrument.

Nellie Halek
Notary Public - State of ~~New York~~ Texas

NELLIE HALEK
Notary Public, State of Texas
Comm. Expires 04-19-2028
Notary ID 11945201

IN WITNESS WHEREOF, Grantor Beneficial Owner and Leaseholder has caused this instrument to be signed in its name.

IUV Phase 1B Owner, LLC:

By: _____

Print Name: DAVID L. PICKET

Title: AUTHORIZED SIGNATORY Date: 8/20/2025

Grantor's Acknowledgment

STATE OF NEW YORK)
) ss:
COUNTY OF Kings)

On the 20 day of August, in the year 2025 before me, the undersigned, personally appeared David L. Picket, personally known to me or proved to me on the basis of satisfactory evidence to be the individual(s) whose name is (are) subscribed to the within instrument and acknowledged to me that he/she/they executed the same in his/her/their capacity(ies), and that by his/her/their signature(s) on the instrument, the individual(s), or the person upon behalf of which the individual(s) acted, executed the instrument.

_____
Notary Public - State of New York

LISA GERECITANO
NOTARY PUBLIC, STATE OF NEW YORK
Registration No. 01GE6350245
Qualified in Kings County
Commission Expires ~~November 7, 2024~~
March 21, 2029

https://a836-acris.nyc.gov/DS/DocumentSearch/DocumentImageView?doc_id=2025092600676001 10/13

IN WITNESS WHEREOF, Grantor Beneficial Owner has caused this instrument to be signed in its name.

IUV Phase 1B LIHTC Owner, LLC:

By: _____

Print Name: DAVID L. PICKET

Title: AUTHORIZED SIGNATORY Date: 8/20/2025

Grantor's Acknowledgment

STATE OF NEW YORK)
) ss:
COUNTY OF Kings)

On the 20 day of August, in the year 2025, before me, the undersigned, personally appeared David L. Picket, personally known to me or proved to me on the basis of satisfactory evidence to be the individual(s) whose name is (are) subscribed to the within instrument and acknowledged to me that he/she/they executed the same in his/her/their capacity(ies), and that by his/her/their signature(s) on the instrument, the individual(s), or the person upon behalf of which the individual(s) acted, executed the instrument.

_____
Notary Public - State of New York

LISA GERECITANO
NOTARY PUBLIC, STATE OF NEW YORK
Registration No. 01GE6350245
Qualfied in Kings County
Commission Expires November 7, 2024

March 21, 2029

THIS ENVIRONMENTAL EASEMENT IS HEREBY ACCEPTED BY THE PEOPLE OF THE STATE OF NEW YORK, Acting by and Through the Department of Environmental Conservation as Designee of the Commissioner,

By: Andrew Guglielmi
Andrew O. Guglielmi, Director
Division of Environmental Remediation

Grantee's Acknowledgment

STATE OF NEW YORK)
) ss:
COUNTY OF ALBANY)

On the 17th day of September in the year 2025 before me, the undersigned, personally appeared Andrew O. Guglielmi, personally known to me or proved to me on the basis of satisfactory evidence to be the individual(s) whose name is (are) subscribed to the within instrument and acknowledged to me that he/she/ executed the same in his/her/ capacity as Designee of the Commissioner of the State of New York Department of Environmental Conservation, and that by his/her/ signature on the instrument, the individual, or the person upon behalf of which the individual acted, executed the instrument.

Cheryl A. Salem
Notary Public - State of New York

Cheryl A. Salem
Notary Public State of New York
Registration No. 01SA0002177
Qualified in Albany County
My Commission Expires March 3, 2027

https://a836-acris.nyc.gov/DS/DocumentSearch/DocumentImageView?doc_id=2025092600676001 12/13

SCHEDULE "A" PROPERTY DESCRIPTION

Environmental Easement and Deed Description:

ALL THAT CERTAIN PLOT, PIECE OR PARCEL OF LAND, SITUATE, LYING AND BEING IN THE BOROUGH OF BROOKLYN, COUNTY OF KINGS, CITY AND STATE OF NEW YORK, BOUNDED AND DESCRIBED AS FOLLOWS:

BEGINNING AT A POINT ON THE SOUTHERLY RIGHT OF WAY LINE OF FLATLANDS AVENUE (110 FEET WIDE PUBLIC RIGHT OF WAY), SAID POINT BEING LOCATED 235.32 FEET WESTERLY AS MEASURED ALONG THE SAME FROM ITS INTERSECTION OF THE WESTERLY RIGHT OF WAY LINE OF PENNSYLVANIA AVENUE (120 FEET PUBLIC RIGHT OF WAY);

RUNNING THENCE THE FOLLOWING FOUR (4) COURSES AND DISTANCES:

1) SOUTHERLY, AT RIGHT ANGLES WITH THE PREVIOUS COURSE, A DISTANCE OF 369.50 FEET TO A POINT;
2) WESTERLY, AT RIGHT ANGLES WITH THE PREVIOUS COURSE, A DISTANCE OF 245.68 FEET TO A POINT;
3) NORTHERLY, AT RIGHT ANGLES WITH THE PREVIOUS COURSE, A DISTANCE OF 369.50 FEET TO THE SOUTHERLY SIDE OF FLATLANDS AVENUE;
4) EASTERLY, ALONG THE SOUTHERLY SIDE OF FLATLANDS AVENUE, A DISTANCE OF 245.68 FEET TO THE POINT OR PLACE OF BEGINNING.

ACREAGE 2.084

https://a836-acris.nyc.gov/DS/DocumentSearch/DocumentImageView?doc_id=2025092600676001 13/13

FLATLANDS AVENUE

(110' WIDE PUBLIC)
(ASPHALT ROADWAY)

NOTES:

1. PROPERTY KNOWN AS LOT 1, BLOCK 4434, AS SHOWN ON THE NEW YORK CITY DIGITAL TAX MAP OF THE BOROUGH OF BROOKLYN, KINGS COUNTY, CITY AND STATE OF NEW YORK.
2. LOT 1 AREA = 90,778± S.F. OR 2.084± AC.
3. LOCATION OF UNDERGROUND UTILITIES ARE APPROXIMATE. LOCATIONS AND SIZES ARE BASED ON UTILITY MARK-OUTS, ABOVE GROUND STRUCTURES THAT WERE VISIBLE & ACCESSIBLE IN THE FIELD, AND THE MAPS AS LISTED IN THE REFERENCES AVAILABLE AT THE TIME OF THE SURVEY. AVAILABLE ASBUILT PLANS AND UTILITY MARKOUT DOES NOT ENSURE MAPPING OF ALL UNDERGROUND UTILITIES AND STRUCTURES. BEFORE ANY EXCAVATION IS TO BEGIN, ALL UNDERGROUND UTILITIES SHOULD BE VERIFIED AS TO THEIR LOCATION, SIZE AND TYPE BY THE PROPER UTILITY COMPANIES. CONTROL POINT ASSOCIATES, INC. DOES NOT GUARANTEE THE UTILITIES SHOWN COMPRISE ALL SUCH UTILITIES IN THE AREA EITHER IN SERVICE OR ABANDONED.
4. THIS PLAN IS BASED ON INFORMATION PROVIDED BY A SURVEY PREPARED IN THE FIELD BY CONTROL POINT ASSOCIATES, INC. AND OTHER REFERENCE MATERIAL AS LISTED HEREON.
5. THIS SURVEY WAS PREPARED WITH REFERENCE TO A CERTIFICATE OF TITLE PREPARED BY FIRST AMERICAN TITLE INSURANCE COMPANY, TITLE No. 3020-18WNY02 WITH AN EFFECTIVE DATE OF 01/14/2025, AMENDED 01/29/2025. THE FOLLOWING SCHEDULE B EXCEPTIONS ARE NOTED:
6. BY GRAPHIC PLOTTING ONLY PROPERTY IS LOCATED IN FLOOD HAZARD ZONE X (AREAS DETERMINED TO BE OUTSIDE THE 0.2% ANNUAL CHANCE FLOODPLAIN) PER FIRM MAP (SEE REF #2), AND FLOOD HAZARD ZONE X-HATCHED (OTHER FLOOD AREAS) (AREAS OF 0.2% ANNUAL CHANCE FLOOD; AREAS OF 1% ANNUAL CHANCE FLOOD WITH AVERAGE DEPTHS OF LESS THAN FOOT OR WITH DRAINAGE AREAS LESS THAN 1 SQUARE MILE; AND AREAS PROTECTED BY LEVEES FROM 1% ANNUAL CHANCE FLOOD.) PER REF. #2.
7. THE EXISTENCE OF UNDERGROUND STORAGE TANKS, IF ANY, WAS NOT KNOWN AT THE TIME OF THE FIELD SURVEY.
8. ELEVATIONS REFER TO NORTH AMERICAN VERTICAL DATUM OF 1988 (NAVD88) WHICH IS 1.46' FEET BELOW THE BOROUGH OF BROOKLYN HIGHWAY DATUM AND 0.62 FEET BELOW THE BOROUGH OF BROOKLYN SEWER DATUM. ELEVATIONS ARE BASED ON GPS OBSERVATIONS UTILIZING THE VRS NETWORK (KEYNETGPS).

   TO CONVERT TO BROOKLYN HIGHWAY DATUM SUBTRACT 1.46 FEET FROM THE ELEVATIONS SHOWN.
   TO CONVERT TO NGVD 1929 ADD 1.10 FEET TO ELEVATIONS SHOWN.
   TEMPORARY BENCH MARKS SET:
   TBM-A: X-CUT SET IN THE MIDDLE OF A CONC. ISLAND ON FLATLANDS AVENUE, ELEVATION=83.03'.
   TBM-B: X-CUT SET IN CONC. WALK ON THE INTERSECTION OF THE NORTHERLY SIDE OF FLATLAND AVENUE AND THE WESTERLY SIDE OF PENNSYLVANIA AVENUE, ELEVATION=80.68'

   SEVEN (7) DAYS PRIOR TO CONSTRUCTION IT IS THE CONTRACTOR'S RESPONSIBILITY TO VERIFY THAT THE BENCHMARKS ILLUSTRATED ON THIS SURVEY HAVE NOT BEEN DISTURBED AND THEIR ELEVATIONS HAVE BEEN CONFIRMED. ANY CONFLICTS MUST BE REPORTED PRIOR TO CONSTRUCTION. SURVEYOR IS NOT RESPONSIBLE FOR CONTRACTOR'S FAILURE TO COMPLY.
9. THERE WERE NO NATURAL STREAMS OR WATERCOURSES VISIBLE AT THE TIME OF THE FIELD SURVEY.
10. ENCROACHMENTS AND VAULTS, IF ANY, BELOW SURFACE NOT SHOWN HEREON.
11. THE OFFSETS SHOWN ARE NOT TO BE USED FOR THE CONSTRUCTION OF ANY STRUCTURE, FENCE, PERMANENT ADDITION, ETC.
12. ANY DISCREPANCIES FOUND ON THE SURVEY SHOULD BE REPORTED TO THE SURVEYOR IMMEDIATELY.
13. THIS SURVEY WAS PREPARED FOR THE CLIENT, (BOHLER ENGINEERING NY, PLLC) AND INTENDED ONLY FOR THE USE BY THE CLIENT AS CONTRACTED FOR THE PROJECT AND THE PURPOSE ORIGINALLY INTENDED. NO FURTHER PARTIES OTHER THAN THOSE CERTIFIED HEREON SHALL RELY ON IT FOR ANY PURPOSE.
14. THE SUBJECT PROPERTY HAS DIRECT PHYSICAL ACCESS TO FLATLANDS AVENUE (A 110-FEET WIDE PUBLIC / A DEDICATED PUBLIC STREET OR HIGHWAY).
15. THERE WERE NO BUILDINGS OBSERVED ON THE SUBJECT PROPERTY AT THE TIME OF FIELD SURVEY (STAGING 1A, NOT ACTIVE CONSTRUCTION FOR THE 1B PROJECT).
16. THERE WERE NO PARKING SPACE OBSERVED ON THE SUBJECT PROPERTY AT THE TIME OF FIELD SURVEY (STAGING FOR 1A, NOT ACTIVE CONSTRUCTION FOR THE 1B PROJECT)
17. THERE WAS EVIDENCE OF RECENT EARTH MOVING WORK, TO FACILITATE SITE STAGING FOR 1A, NOT ACTIVE CONSTRUCTION OF THE 1B PROJECT.
18. NO PROPOSED CHANGES IN STREET RIGHT OF WAY LINES HAVE BEEN MADE AVAILABLE TO THE SURVEYOR BY THE CONTROLLING JURISDICTION (BOROUGH OF BROOKLYN TOPOGRAPHICAL BUREAU, KINGS COUNTY, CITY AND STATE OF NEW YORK, NYC STREET MAP ONLINE).
    THERE WAS EVIDENCE OF RECENT SIDEWALK CONSTRUCTION OBSERVED IN THE PROCESS OF CONDUCTING THE FIELD WORK FOR A PORTION OF THE SIDEWALK IN FRONT OF SUBJECT PROPERTY, ALONG FLATLANDS AVENUE.
19. THERE WAS NO EVIDENCE OF A CEMETERY OBSERVED ON THE SUBJECT PROPERTY IN THE PROCESS OF CONDUCTING THE FIELD WORK.
20. THE PROPERTY DESCRIBED HEREON IS THE SAME AS THE PROPERTY DESCRIBED IN THE CERTIFICATE OF TITLE PREPARED BY FIRST AMERICAN TITLE INSURANCE COMPANY, TITLE NO. 3020-18WNY02 WITH AN EFFECTIVE DATE OF 01/14/2025, AMENDED 01/29/2025 AND THAT ALL EASEMENTS, COVENANTS AND RESTRICTIONS REFERENCED IN SAID TITLE COMMITMENT OR APPARENT FROM A PHYSICAL INSPECTION OF THE SITE OR OTHERWISE KNOWN TO HAVE BEEN PLOTTED HEREON OR OTHERWISE NOTED AS TO THEIR EFFECT ON THE SUBJECT PROPERTY.
21. THE ACCOMPANYING SURVEY WAS MADE ON THE GROUND AND CORRECTLY SHOWS THE LOCATION OF ALL BUILDINGS, STRUCTURES AND OTHER IMPROVEMENTS SITUATED ON THE ABOVE PREMISES (SITE CURRENTLY UNDER CONSTRUCTION AS OF LAST FIELD WORK); AND WAS MADE IN ACCORDANCE WITH LAWS AND/ OR MINIMUM STANDARDS OF THE STATE OF NEW YORK. THERE ARE NO VISIBLE ENCROACHMENTS ON THE SUBJECT PROPERTY OR UPON ADJACENT LAND ABUTTING SAID PROPERTY EXCEPT AS SHOWN.
22. THE SUBJECT PARCEL IS IN ZONING R7-2 WITH C2-4 OVERLAY DISTRICT; USES, HEIGHT, SETBACKS, AND PARKING IN ACCORDANCE WITH CITY PLANNING COMMISSION APPROVALS C220312 ZMK.
23. SETBACKS IN ACCORDANCE WITH CITY PLANNING COMMISSION APPROVALS C220312 ZMK.
24. SUBJECT PARCEL'S LEGAL DESCRIPTION IS A MATHEMATICALLY CLOSED FIGURE.
25. NO SPECIFIC INFORMATION ON ITEM 20 TABLE "A" CERTIFICATION FOR ALTA/NSPS LAND TITLE SURVEY WAS PROVIDED BY THE CLIENT (NOT INCLUDED IN THE CERTIFICATION).
26 "OPTION PROPERTY", AS DEFINED IN THE DECLARATION, DATED SEPTEMBER 5, 1980, MADE BY MILTON MILLER AND STARRETT BROTHERS & EKEN DEVELOPMENT CORPORATION, IS NOT PART OF THE SURVEYED PROPERTY
27 SAID DESCRIBED PROPERTY IS LOCATED WITHIN AN AREA HAVING A ZONE DESIGNATION X BY THE FEDERAL EMERGENCY MANAGEMENT AGENCY (FEMA), ON FLOOD INSURANCE RATE MAP NO. 3604970219F, WITH A DATE OF IDENTIFICATION OF SEPTEMBER 5, 2007, FOR COMMUNITY PANEL NO. 219, IN KINGS COUNTY, STATE OF NEW YORK, WHICH IS THE CURRENT FLOOD INSURANCE RATE MAP FOR THE COMMUNITY IN WHICH SAID PREMISES IS SITUATED AND SAID DESCRIBED PROPERTY IS LOCATED WITHIN AN AREA HAVING A PRELIMINARY ZONE DESIGNATION X AND X (SHADED) BY THE FEDERAL EMERGENCY MANAGEMENT AGENCY (FEMA), ON FLOOD INSURANCE RATE MAP NO. 3604970219G, WITH A PRELIMINARY DATE OF IDENTIFICATION OF DECEMBER 5, 2013, FOR COMMUNITY PANEL NO. 219, IN KINGS COUNTY, STATE OF NEW YORK, WHICH IS THE CURRENT PRELIMINARY FLOOD INSURANCE RATE MAP FOR THE COMMUNITY IN WHICH SAID PREMISES IS SITUATED.
28 THE TOTAL NUMBER OF STRIPED PARKING SPACES REQUIRED BY THE NEW YORK CITY ZONING RESOLUTION UNDER NEW BUILDING APPLICATION NUMBER B00851732-I1 IS 2, 5% OF WHICH ARE TO BE DESIGNATED AS HANDICAPPED SPACES. THE NUMBER OF ACTUAL PARKING SPACES PROVIDED ON THE SUBJECT PROPERTY IS 102, INCLUDING 6 OF WHICH ARE DESIGNATED AS HANDICAPPED SPACES.
29 ***THIS PROPERTY IS SUBJECT TO AN ENVIRONMENTAL EASEMENT HELD BY THE NEW YORK STATE DEPARTMENT OF ENVIRONMENTAL CONSERVATION PURSUANT TO TITLE 36 OF ARTICLE 71 OF THE NEW YORK ENVIRONMENTAL CONSERVATION LAW. THE ENGINEERING AND INSTITUTIONAL CONTROLS FOR THIS EASEMENT ARE SET FORTH IN THE SITE MANAGEMENT PLAN (SMP). A COPY OF THE SMP MUST BE OBTAINED BY ANY PARTY WITH AN INTEREST IN THE PROPERTY. THE SMP CAN BE OBTAINED FROM NYS DEPARTMENT OF ENVIRONMENTAL CONSERVATION, DIVISION OF ENVIRONMENTAL REMEDIATION, SITE CONTROL SECTION, 625 BROADWAY, ALBANY, NY 12233 OR AT derweb@dec.ny.gov.***

REFERENCES:

1. THE NEW YORK CITY DIGITAL TAX MAP OF THE BOROUGH OF BROOKLYN, KINGS COUNTY, CITY AND STATE OF NEW YORK.
2. MAP ENTITLED "NATIONAL FLOOD INSURANCE PROGRAM, FIRM, FLOOD INSURANCE RATE MAP, CITY OF NEW YORK, NEW YORK, BRONX, RICHMOND, NEW YORK, QUEENS AND KINGS COUNTIES," PANEL NUMBER 219 OF 457, MAP NUMBER 3604970219F, MAP REVISED: SEPTEMBER 5, 2007.

   PRELIMINARY MAP ENTITLED "NATIONAL FLOOD INSURANCE PROGRAM, FIRM, FLOOD INSURANCE RATE MAP, CITY OF NEW YORK, NEW YORK, BRONX, RICHMOND, NEW YORK, QUEENS AND KINGS COUNTIES," PANEL NUMBER 219 OF 457, MAP NUMBER 3604970219G, PRELIMINARY : DECEMBER 5, 2013.
3. FINAL SECTION MAP NO. 59 PROVIDED BY CITY OF NEW YORK, BOROUGH OF BROOKLYN, OFFICE OF THE PRESIDENT TOPOGRAPHICAL BUREAU. MAP DATED AUGUST 10, 1995.
4. MAP ENTITLED "ALTA/NSPS LAND TITLE SURVEY, LOT 1, BLOCK 4434 FLATLANDS AVENUE BOROUGH OF BROOKLYN, KINGS COUNTY CITY AND STATE OF NEW YORK, JOB NO. 04-200032-01" PREPARED BY CONTROL POINT ASSOCIATES INC., DATED: 03-10-2025.

GRAPHIC SCALE
1 inch = 20 ft.
FEET: 20 0 10 20 40 80
METERS: 6 5 4 3 2 1 0 5 10 15 20 25

CONTROL POINT ASSOCIATES, INC. ALL RIGHTS RESERVED
THIS DOCUMENT IS AN INSTRUMENT OF SERVICE AND IS THE ORIGINAL PROJECT OR THE PURPOSE ORIGINALLY INTENDED. WITHOUT THE WRITTEN PERMISSION OF CONTROL POINT ASSOCIATES, INC. IS PROHIBITED





VICINITY MAP
© 2022 ESRI WORLD LIGHT GRAY CANVAS (NOT TO SCALE)

LEGEND

124 / 125	EXISTING CONTOUR		CATCH BASIN OR INLET
	DEPRESSED CURB	8"	TREE STUMP & SIZE
	HYDRANT	18	DECIDUOUS TREE & TRUNK SIZE
WV	WATER VALVE	PM	CONIFEROUS TREE & TRUNK SIZE
VALVE	UNKNOWN VALVE	C.L.F.	CHAIN LINK FENCE
GV	GAS VALVE	D.C.	DEPRESSED CURB
SMH (S)	SANITARY/SEWER MANHOLE	E.O.C.	EDGE OF CONC.
MH (M)	UNKNOWN MANHOLE	E.O.P.	EDGE OF PAVEMENT
WMH (F)	WATER MANHOLE	L.S.A.	LANDSCAPED AREA
UP	UTILITY POLE	MC	METAL COVER
	GUY WIRE	(TYP.)	TYPICAL
	STREET LIGHT	D.W.P.	DETECTABLE WARNING PAD
	TRAFFIC SIGNAL POLE	1.0'	OFFSET OF STRUCTURE AT GROUND LEVEL RELATIVE TO PROPERTY LINE
	TRAFFIC SIGNAL	O/L	ON LINE
	PAINTED ARROWS	W.C.	WALL CORNER
	SIGN	W.L.	WALL LINE
	BOLLARD	F.C.	FENCE CORNER
MW	MONITORING WELL	F.P.	FENCE POST
		F.L.	FENCE LINE
		P.O.B.	POINT OF BEGINNING
			BCP SITE ENVIRONMENTAL EASEMENT AREA

DEED DESCRIPTION / LEGAL DESCRIPTION OF ENVIRONMENTAL EASEMENT AREA

ALL THAT CERTAIN PLOT, PIECE OR PARCEL OF LAND, SITUATE, LYING AND BEING IN THE BOROUGH OF BROOKLYN, COUNTY OF KINGS, CITY AND STATE OF NEW YORK, BOUNDED AND DESCRIBED AS FOLLOWS:

BEGINNING AT A POINT ON THE SOUTHERLY RIGHT OF WAY LINE OF FLATLANDS AVENUE (110 FEET WIDE PUBLIC RIGHT OF WAY), SAID POINT BEING LOCATED 235.32 FEET WESTERLY AS MEASURED ALONG THE SAME FROM ITS INTERSECTION OF THE WESTERLY RIGHT OF WAY LINE OF PENNSYLVANIA AVENUE (120 FEET PUBLIC RIGHT OF WAY);

RUNNING THENCE THE FOLLOWING FOUR (4) COURSES AND DISTANCES:

1) SOUTHERLY, AT RIGHT ANGLES WITH THE PREVIOUS COURSE, A DISTANCE OF 369.50 FEET TO A POINT;

2) WESTERLY, AT RIGHT ANGLES WITH THE PREVIOUS COURSE, A DISTANCE OF 245.68 FEET TO A POINT;

3) NORTHERLY, AT RIGHT ANGLES WITH THE PREVIOUS COURSE, A DISTANCE OF 369.50 FEET TO THE SOUTHERLY SIDE OF FLATLANDS AVENUE;

4) EASTERLY, ALONG THE SOUTHERLY SIDE OF FLATLANDS AVENUE, A DISTANCE OF 245.68 FEET TO THE POINT OR PLACE OF BEGINNING.

CONTAINING 90,778 SQUARE FEET OR 2.084 ACRES

UTILITIES:

THE FOLLOWING COMPANIES WERE NOTIFIED BY THE NEW YORK CITY ONE-CALL SYSTEM (1-800-272-4480) AND REQUESTED TO MARK OUT UNDERGROUND FACILITIES AFFECTING AND SERVICING THIS SITE. THE UNDERGROUND UTILITY INFORMATION SHOWN HEREON IS BASED UPON THE UTILITY COMPANIES RESPONSE TO THIS REQUEST.
TICKET NUMBER: 200311053.

UTILITY COMPANY	PHONE NUMBER	STATUS
AT&T CORPORATION	800-241-3624	CLEAR/NO CONFLICT
NATIONAL GRID	646-235-8508	MARKED
CONSOLIDATED EDISON CO. OF N.Y	800-778-9140	MARKED
MCI	919-414-2782	CLEAR/NO CONFLICT
TIME WARNER CABLE - QUEENS	800-262-8600	CLEAR/NO CONFLICT
VERIZON COMMUNICATIONS	855-661-6323	CLEAR/NO CONFLICT

THIS SURVEY IS CERTIFIED TO:
- RSEP HOLDING, LLC, IT'S SUCCESSORS AND/OR ASSIGNS AS THEIR INTERESTS MAY APPEAR
- RED STONE EQUITY MANAGER, LLC, IT'S SUCCESSORS AND/OR ASSIGNS AS THEIR INTERESTS MAY APPEAR
- FIRST AMERICAN TITLE INSURANCE COMPANY OF NEW YORK
- NEW YORK CITY HOUSING DEVELOPMENT CORPORATION, IT'S SUCCESSORS AND/OR ASSIGNS AS THEIR INTERESTS MAY APPEAR
- CITY OF NEW YORK, IT'S SUCCESSORS AND/OR ASSIGNS AS THEIR INTERESTS MAY APPEAR
- IUV PHASE 1B OWNER, LLC
- IUV PHASE 1B LIHTC OWNER, LLC
- IUV PHASE 1B HOUSING DEVELOPMENT FUND CORPORATION
- JPMORGAN CHASE BANK, N.A.
- RSE IUV, LLC
- FNBC LEASING CORPORATION
- RED STONE EQUITY - FUND 102 JPMORGAN LIMITED PARTNERSHIP

THIS IS TO CERTIFY THAT THIS MAP OR PLAT AND THE SURVEY ON WHICH IT WAS BASED WERE MADE IN ACCORDANCE WITH THE "2021 MINIMUM STANDARD DETAIL REQUIREMENTS FOR ALTA/NSPS LAND TITLE SURVEYS", JOINTLY ESTABLISHED AND ADOPTED BY ALTA AND NSPS, AND INCLUDES ITEMS 1, 2, 3, 4, 5, 6(a), 6(b), 7(a), 7(b-1), 7(c), 8, 9, 10, 11(a), 11(b), 13, 14, 16, 17, 18 AND 19 OF TABLE A THEREOF. THE FIELD WORK WAS COMPLETED ON 02/11/2025.

UNAUTHORIZED ALTERATION OR ADDITION TO A SURVEY MAP BEARING A LICENSED LAND SURVEYOR'S SEAL IS A VIOLATION OF SECTION 7209, SUB-DIVISION 2, OF THE NEW YORK STATE EDUCATION LAW.

ONLY COPIES FROM THE ORIGINAL OF THIS SURVEY MARKED WITH AN ORIGINAL OF THE LAND SURVEYOR'S EMBOSSED OR INKED SEAL SHALL BE CONSIDERED TO BE VALID TRUE COPIES.

PREPARED BY:
CONTROL POINT ASSOCIATES INC PC
9 TIMES SQUARE,
200 WEST 41ST STREET, 14TH FLOOR
NEW YORK, NY 10036
646.780.0411 : 908.668.9595 FAX
WWW.CPASURVEY.COM

WARREN, NJ 908.668.0099 | ALBANY, NY 518.217.5010
OLLALONT, PA 215.712.9900 | ROCHESTER, NY 585.balance.764
MONTVALE, NJ 201.391.2099 | BINGHAMTON, NY 607.433.8450
MANHATTAN, NY 646.780.0411 | PHILADELPHIA, PA 215.712.9900
SOUTHBOROUGH, MA 508.948.3000 | HUDSON VALLEY, NY 845.691.7339
FT. LAUDERDALE, FL 954.763.7611

NO.	DATE	BY	DESCRIPTION	APPROVED
3	03-10-2025	J.H.	REVISED PER CLIENT COMMENTS	A.J.F.
2	02-27-2025	J.H.	SURVEY UPDATE	A.J.F.
1	01-13-2025	J.H.	PROPOSED EASEMENT ADDED	A.J.F.

REVISIONS

PROJECT NAME

LOT 1, BLOCK 4434
FLATLANDS AVENUE
BOROUGH OF BROOKLYN, KINGS COUNTY
CITY AND STATE OF NEW YORK

DRAWING TITLE

BCP SITE/ENVIRONMENTAL EASEMENT EXHIBIT

SEAL & SIGNATURE
NOT A VALID ORIGINAL DOCUMENT UNLESS EMBOSSED WITH RAISED IMPRESSION OR BLUE INK SEAL

STATE OF NEW YORK · ANDREW JOSEPH FLANAGAN · 050417 · LICENSED LAND SURVEYOR

05-20-2025
DATE

ANDREW J. FLANAGAN
NEW YORK PROFESSIONAL LAND SURVEYOR #050417
E-MAIL: AFLANAGAN@CPASURVEY.COM

FIELD DATE:	10-07-2024 02-11-2025
FIELD BK:	NYC 21-15 42
F. B. PAGE:	451 12
DATE:	12-12-2024
SCALE:	1"=20'
PROJECT No:	04-200032-01
DRAWING BY:	J.H.
CHK BY:	A.J.F.
APPROVED BY:	A.J.F.
DWG No:	V-001
CAD FILE No:	04-200032-01
PAGE No:	1 OF 1

APPENDIX B

List of Site Contacts

LIST OF SITE CONTACTS

Key contacts for this project are as follows:

Site Owner and Remedial Party:	Innovative Urban Living, LLC, IUV Phase 1B Owner, LLC, IUV Phase 1B LIHTC Owner, LLC Simeon Maleh Telephone: (212) 716-2536 E-mail: smaleh@gothamorg.com
Remedial Party's Consultant:	Langan Engineering Project Manager Amanda Forsburg, CHMM Telephone: (973) 560-4900 E-mail: aforsburg@langan.com Langan Engineering Remedial Engineer Ronald D. Boyer, P.E. Telephone: (973) 560-4900 E-mail: rboyer@langan.com Langan Engineering Health & Safety Officer Tony Moffa Telephone: (215) 756-2523 E-mail: tmoffa@langan.com Langan Engineering Field Safety Officer Ashley Sandve Telephone: (973) 560-4900 E-mail: asandve@langan.com
Qualified Environmental Professional:	Amanda Forsburg, CHMM Telephone: (973) 560-4900 E-mail: aforsburg@langan.com

NYSDEC:

NYSDEC Project Manager's Supervisor
Ms. Lisa Gorton
Telephone: (518) 402-9574
E-mail: Lisa.Gorton@dec.ny.gov

NYSDEC Project Manager
Mr. Rafi Alam
Telephone: (518) 402-8606
E-mail: Rafi.Alam@dec.ny.gov

NYSDEC Attorney
Mr. Kyle Pero
E-mail: kyle.pero@dec.ny.gov

NYSDOH:

NYSDOH Project Manager
Mr. Jim Sullivan
Telephone: (518) 402-5584
Email: beei@health.ny.gov

Remedial Party's Attorney:

Knauf Shaw LLP
Linda Shaw
Telephone: (585) 546-8430
E-mail: lshaw@nyenvlaw.com

APPENDIX C

Soil Boring and Monitoring Well Construction Logs

LANGAN

LANGAN

Log of Boring **LMW-4** Sheet 1 of 2

Project: 12074 Flatlands Avenue	Project No.: 100688801
Location: Brooklyn, New York	Elevation and Datum: 21.28-ft NAVD88
Drilling Company: AARCO Environmental Services Corp.	Date Started: 02/18/2023 — Date Finished: 02/18/2023
Drilling Equipment: Geoprobe 6610 DT	Completion Depth: 25 ft — Rock Depth: ---
Size and Type of Bit: 2-inch Direct Push	Number of Samples: Disturbed 5 — Undisturbed --- — Core ---
Casing Diameter (in): --- — Casing Depth (ft): ---	Water Level (ft.): First ▽ 20 — Completion ▼ --- — 24 HR. ▼ ---
Casing Hammer: --- — Weight (lbs): --- — Drop (in): ---	Drilling Foreman: Sergio Magana
Sampler: 1.75" x 5' Long Acetate Lined Macrocore	Field Engineer: Esther Arthur
Sampler Hammer: --- — Weight (lbs): --- — Drop (in): ---	

MATERIAL SYMBOL	Elev. (ft)	Sample Description	Depth Scale	Sample Data: Number	Type	Recov. (in)	Penetr. resist BL/6in	PID (ppm)	Remarks (Drilling Fluid, Depth of Casing, Fluid Loss, Drilling Resistance, etc.)
	+21.3		0					0.0	Started Drilling on 2/16/2023
	+20.8	CONCRETE						0.0	
		Brown fine-coarse SAND, some gravel, trace brick, trace concrete, trace glass (dry) [FILL]	1					0.0	
								0.0	
			2					0.0	
	+19.0			M-1	Macrocore	52		0.0	
	+18.5	CONCRETE						0.0	
		Dark brown fine-coarse SAND, some gravel, trace brick, trace wood (moist) [FILL]	3					0.0	
								0.0	
			4					0.0	
								0.0	
			5					0.0	
								0.0	
			6					0.0	
		Black fine-coarse SAND, trace concrete, trace brick, trace silt (moist) [FILL]						0.0	
			7	M-2	Macrocore	54		0.0	
								0.0	
			8					0.0	
		Brown to black fine-medium SAND, some concrete, trace wood, trace silt, trace gravel (moist) [FILL]						0.0	
			9					0.0	
								0.0	
			10					0.0	
								0.0	
			11					0.0	
		Brown to black fine-medium SAND, trace wood, trace slag, trace silt (moist) [FILL]						0.0	
			12	M-3	Macrocore	42		0.0	
								0.0	
			13					0.0	
								0.0	
			14					0.0	
								0.0	
			15					0.0	
								0.0	
			16					0.0	
								0.0	
		Black fine-coarse SAND, trace wood, trace silt, trace gravel (moist) [FILL]	17					0.0	
				M-4	Macrocore	48		0.0	
			18					0.0	
								0.0	
			19					0.0	
								0.0	
			20 ▽					0.0	

\LANGAN.COM\DATA\PAR\DATA8\100688801\PROJECT DATA_DISCIPLINE\ENVIRONMENTAL\GINTLOGS\100688801_PHASE 1B.GPJ... 6/14/2023 2:38:01 PM... Report: Log - LANGAN

LANGAN

Log of Boring **LMW-4** Sheet 2 of 2

Project	Project No.
12074 Flatlands Avenue	100688801
Location	**Elevation and Datum**
Brooklyn, New York	21.28-ft NAVD88

MATERIAL SYMBOL	Elev. (ft)	Sample Description	Depth Scale	Sample Data: Number	Type	Recov. (in)	Penetr. resist BL/6in	PID (ppm)	Remarks (Drilling Fluid, Depth of Casing, Fluid Loss, Drilling Resistance, etc.)
	+1.3	Black fine-coarse SAND, trace wood, trace silt, trace gravel (wet) [FILL]	20	M-5	Macrocore	46		0.0	
			21					0.0	
			22					0.0	
			23					0.0	
			24					0.0	
			25					0.0	
	-3.7		26						Bottom of boring at 25-feet bgs. LMW-4 installed to 25-feet bgs.
			27						
			28						
			29						
			30						
			31						
			32						
			33						
			34						
			35						
			36						
			37						
			38						
			39						
			40						
			41						
			42						
			43						
			44						
			45						

\\LANGAN.COM\DATA\PAR\DATA8\100688801\PROJECT DATA_DISCIPLINE\ENVIRONMENTAL\GINTLOGS\100688801_PHASE 1B.GPJ ... 6/14/2023 2:38:02 PM ... Report: Log - LANGAN

LANGAN

Log of Boring **LSB-28/LMW-15** Sheet 1 of 1

Project: 12074 Flatlands Avenue	Project No.: 100688801
Location: Brooklyn, New York	Elevation and Datum: 13.12-ft NAVD88
Drilling Company: AARCO Environmental Services Corp.	Date Started: 02/14/2023 / Date Finished: 02/14/2023
Drilling Equipment: Geoprobe 7822 DT	Completion Depth: 20 ft / Rock Depth: ---
Size and Type of Bit: 2-inch Direct Push	Number of Samples: Disturbed 4, Undisturbed ---, Core ---
Casing Diameter (in): --- / Casing Depth (ft): ---	Water Level (ft.): First ▽ 13, Completion ▼ ---, 24 HR. ▼ ---
Casing Hammer: --- / Weight (lbs): --- / Drop (in): ---	Drilling Foreman: Julio Galarzia
Sampler: 1.75" x 5' Long Acetate Lined Macrocore	Field Engineer: Esther Arthur
Sampler Hammer: --- / Weight (lbs): --- / Drop (in): ---	

Material Symbol	Elev. (ft)	Sample Description	Depth Scale	Sample Data: Number	Type	Recov. (in)	Penetr. resist BL/6in	PID (ppm)	Remarks (Drilling Fluid, Depth of Casing, Fluid Loss, Drilling Resistance, etc.)
	+13.1	Brown to black fine-coarse SAND, some gravel, brick fragments, concrete fragments (dry) [FILL]	0	M-1	Macrocore	48		0.0	Started Drilling on 2/14/2023
			1					0.0	
			2					0.0	Collected LSB-28_0-2 from 0 to 2-feet bgs. VOCs collected from 0.5- to 1-feet bgs
			3					0.0	
			4					0.0	
			5	M-2	Macrocore	50		0.0	
		Dark brown to black fine-coarse SAND, some gravel, brick fragments, concrete fragments, glass fragments (dry) [FILL]	6					0.0	Collected LSB-28_6-8 from 6- to 8-feet bgs. VOCs collected from 6- to 6.5-feet bgs
			7					0.0	
	+4.7		8					0.0	
		Brown fine-medium SAND, trace gravel (dry) [NATIVE]	9					0.0	
			10	M-3	Macrocore	48		0.0	
			11					0.0	
			12					0.0	
	+0.1		13 ▽					0.0	Collected LSB-28_13-15 from 13- to 15-feet bgs. VOCs collected from 13- to 13.5-feet bgs
		Brown fine-medium SAND, trace gravel (wet) [NATIVE]	14					0.0	
			15	M-4	Macrocore	52		0.0	
			16					0.0	
			17					0.0	
			18					0.0	LMW-15 installed to 18-feet bgs
			19					0.0	Bottom of boring at 20-feet bgs
	-6.9		20					0.0	

\\LANGAN.COM\DATA\PAR\DATA8\100688801\PROJECT DATA_DISCIPLINE\ENVIRONMENTAL\GINTLOGS\100688801_PHASE 1B.GPJ... 6/14/2023 2:38:04 PM... Report: Log - LANGAN

LANGAN

Log of Boring **LSB-29/LMW-25** Sheet 1 of 1

Project: 12074 Flatlands Avenue	Project No.: 100688801
Location: Brooklyn, New York	Elevation and Datum: 14.32-ft NAVD88
Drilling Company: AARCO Environmental Services Corp.	Date Started: 02/14/2023 / Date Finished: 02/14/2023
Drilling Equipment: Geoprobe 7822 DT	Completion Depth: 20 ft / Rock Depth: ---
Size and Type of Bit: 2-inch Direct Push	Number of Samples: Disturbed 4, Undisturbed ---, Core ---
Casing Diameter (in): --- / Casing Depth (ft): ---	Water Level (ft.): First ▽ 12, Completion ▼ ---, 24 HR. ▼ ---
Casing Hammer: --- / Weight (lbs): --- / Drop (in): ---	Drilling Foreman: Julio Galarzia
Sampler: 1.75" x 5' Long Acetate Lined Macrocore	Field Engineer: Esther Arthur
Sampler Hammer: --- / Weight (lbs): --- / Drop (in): ---	

Material Symbol	Elev. (ft)	Sample Description	Depth Scale	Sample Data: Number	Type	Recov. (in)	Penetr. resist BL/6in	PID (ppm)	Remarks (Drilling Fluid, Depth of Casing, Fluid Loss, Drilling Resistance, etc.)
	+14.3	Brown fine-coarse SAND, some gravel, trace wood, brick fragments (dry) [FILL]	0	M-1	Macrocore	46		0.0	Started Drilling on 2/14/2023
			1					0.0	Collected LSB-29_0-2 from 0 to 2-feet bgs. VOCs collected from 0.5- to 1-feet bgs
			2					0.0	
			3					0.0	
	+11.3							0.0	
	+11.0	CONCRETE						0.0	
		Brown fine-coarse SAND, some gravel, trace wood, brick fragments (dry) [FILL]	4					0.0	
								0.0	
		Brown to black fine-coarse SAND, some gravel, trace wood, trace glass (dry) [FILL]	5	M-2	Macrocore	46		0.0	
			6					0.0	Collected LSB-29_6-8 from 6- to 8-feet bgs. VOCs collected from 7- to 7.5-feet bgs
			7					0.0	
			8					0.0	
			9					0.0	
			10					0.0	
	+3.7							0.0	
		Dark gray to brown fine-medium SAND, trace gravel (wet) [NATIVE]	11	M-3	Macrocore	46		0.0	
			12 ▽					0.0	
			13					0.0	Collected LSB-29_13-15 from 13- to 15-feet bgs. VOCs collected from 13- to 13.5-feet bgs
			14					0.0	
			15					0.0	
			16	M-4	Macrocore	58		0.0	
			17					0.0	
			18					0.0	LMW-25 installed to 18-feet bgs.
			19					0.0	Bottom of boring at 20-feet bgs
	-5.7		20					0.0	

\\LANGAN.COM\DATA\PAR\DATA8\100688801\PROJECT DATA_DISCIPLINE\ENVIRONMENTAL\GINTLOGS\100688801_PHASE 1B.GPJ... 6/14/2023 2:38:06 PM... Report: Log - LANGAN

LANGAN

Log of Boring **LSB-30/LMW-16** Sheet 1 of 1

Project: 12074 Flatlands Avenue	Project No.: 100688801
Location: Brooklyn, New York	Elevation and Datum: 14.34-ft NAVD88
Drilling Company: AARCO Environmental Services Corp.	Date Started: 02/14/2023 / Date Finished: 02/14/2023
Drilling Equipment: Geoprobe 7822 DT	Completion Depth: 20 ft / Rock Depth: ---
Size and Type of Bit: 2-inch Direct Push	Number of Samples: Disturbed 4, Undisturbed ---, Core ---
Casing Diameter (in): --- / Casing Depth (ft): ---	Water Level (ft.): First ▽ 16, Completion ▼ ---, 24 HR. ▼ ---
Casing Hammer: --- / Weight (lbs): --- / Drop (in): ---	Drilling Foreman: Julio Galarzia
Sampler: 1.75" x 5' Long Acetate Lined Macrocore	Field Engineer: Esther Arthur
Sampler Hammer: --- / Weight (lbs): --- / Drop (in): ---	

MATERIAL SYMBOL	Elev. (ft)	Sample Description	Depth Scale	Sample Data: Number	Type	Recov. (in)	Penetr. resist BL/6in	PID (ppm)	Remarks (Drilling Fluid, Depth of Casing, Fluid Loss, Drilling Resistance, etc.)
	+14.3	Dark brown fine-coarse SAND, trace gravel, wood fragments (dry) [FILL]	0					0.0	Started Drilling on 2/14/2023
		Brown fine-coarse SAND, some gravel, concrete fragments (dry) [FILL]	1					0.0	Collected LSB-30_0-2 from 0 to 2-feet bgs. VOCs collected from 0.5- to 1-feet bgs
			2	M-1	Macrocore	44		0.0	
			3					0.0	
			4					0.0	
			5					0.0	
		Dark brown to black fine-coarse SAND, some gravel, glass fragments, wood fragments (dry) [FILL]	6					0.0	
			7	M-2	Macrocore	40		0.0	Collected LSB-30_7-9 from 7- to 9-feet bgs. VOCs collected from 8- to 8.5-feet bgs
			8					0.0	
			9					0.0	
			10					0.0	
		Dark brown to black fine-coarse SAND, some gravel, glass fragments, wood fragments (dry) [FILL]	11					0.0	
	+2.3		12	M-3	Macrocore	43		0.0	
		Dark gray fine-medium SAND, trace gravel (moist) [NATIVE]	13					0.0	Collected LSB-30_13-15 from 13- to 15-feet bgs. VOCs collected from 14- to 14.5-feet bgs
			14					0.0	
			15					0.0	
		Dark gray to brown fine-medium SAND, trace gravel (wet) [NATIVE]	16 ▽					0.0	
			17					0.0	
			18	M-4	Macrocore	55		0.0	
			19					0.0	
			20					0.0	Bottom of boring at 20-feet bgs. LMW-16 installed to 20-feet bgs.
	-5.7								

\\LANGAN.COM\DATA\PAR\DATA8\100688801\PROJECT DATA_DISCIPLINE\ENVIRONMENTAL\GINTLOGS\100688801_PHASE 1B.GPJ... 6/14/2023 2:38:08 PM... Report: Log - LANGAN

LANGAN

Log of Boring **LSB-31** Sheet 1 of 1

Project: 12074 Flatlands Avenue	Project No.: 100688801
Location: Brooklyn, New York	Elevation and Datum: 17.00-ft NAVD88
Drilling Company: AARCO Environmental Services Corp.	Date Started: 02/14/2023 — Date Finished: 02/14/2023
Drilling Equipment: Geoprobe 7822 DT	Completion Depth: 20 ft — Rock Depth: ---
Size and Type of Bit: 2-inch Direct Push	Number of Samples: Disturbed 4 — Undisturbed --- — Core ---
Casing Diameter (in): --- — Casing Depth (ft): ---	Water Level (ft.): First ▽ 14 — Completion ▼ --- — 24 HR. ▼ ---
Casing Hammer: --- — Weight (lbs): --- — Drop (in): ---	Drilling Foreman: Julio Galarzia
Sampler: 1.75" x 5' Long Acetate Lined Macrocore	Field Engineer: Esther Arthur
Sampler Hammer: --- — Weight (lbs): --- — Drop (in): ---	

Material Symbol	Elev. (ft)	Sample Description	Depth Scale	Sample Data: Number	Type	Recov. (in)	Penetr. resist BL/6in	PID (ppm)	Remarks (Drilling Fluid, Depth of Casing, Fluid Loss, Drilling Resistance, etc.)
	+17.0	Gray to brown fine-coarse SAND, some gravel, concrete fragments (dry) [FILL]	0					0.0	Started Drilling on 2/14/2023
			1					0.0	
								0.0	Collected LSB-31_0-2 from 0 to 2-feet bgs. VOCs collected from 0.5- to 1-feet bgs
								0.0	
	+15.0		2					0.0	
	+14.5	CONCRETE		M-1	Macrocore	48		0.0	
		Gray to brown fine-coarse SAND, some gravel, concrete fragments (dry) [FILL]	3					0.0	
								0.0	
			4					0.0	
								0.0	
		Gray to brown fine-coarse SAND, some gravel, trace brick, concrete fragments (dry) [FILL]	5					0.0	
								0.0	
			6					0.0	
								0.0	
			7					0.0	Collected LSB-31_7-9 from 7- to 9-feet bgs. VOCs collected from 8- to 8.5-feet bgs
				M-2	Macrocore	55		0.0	
			8					0.0	
								0.0	
			9					0.0	
								0.0	
		Black fine-coarse SAND, some wood, some gravel (wet) [FILL]	10					0.0	
								0.0	
			11					0.0	
								0.1	
			12					0.1	
				M-3	Macrocore	40		0.2	
			13					0.2	Collected LSB-31_13-15 from 13- to 15-feet bgs. VOCs collected from 14- to 14.5-feet bgs. Slight odors observed from 13- to 15-feet bgs
								0.4	
		▽	14					0.4	
								0.4	
	+2.0		15					0.1	
		Brown to gray fine-medium SAND, trace gravel (wet) [NATIVE]						0.1	
			16					0.1	
								0.0	
			17					0.0	Collected LSB-31_18-20 from 18- to 20-feet bgs. VOCs collected from 18- to 18.5-feet bgs
				M-4	Macrocore	55		0.0	
			18					0.0	
								0.0	
			19					0.0	
								0.0	Bottom of boring at 20-feet bgs
	-3.0		20					0.0	

\\LANGAN.COM\DATA\PAR\DATA8\100688801\PROJECT DATA_DISCIPLINE\ENVIRONMENTAL\GINTLOGS\100688801_PHASE 1B.GPJ... 6/14/2023 2:38:10 PM... Report: Log - LANGAN

LANGAN

Log of Boring **LSB-32/LMW-24** Sheet 1 of 2

Project: 12074 Flatlands Avenue	Project No.: 100688801
Location: Brooklyn, New York	Elevation and Datum: 18.38-ft NAVD88
Drilling Company: AARCO Environmental Services Corp.	Date Started: 02/15/2023 / Date Finished: 02/15/2023
Drilling Equipment: Geoprobe 7822 DT	Completion Depth: 25 ft / Rock Depth: ---
Size and Type of Bit: 2-inch Direct Push	Number of Samples: Disturbed 5, Undisturbed ---, Core ---
Casing Diameter (in): --- / Casing Depth (ft): ---	Water Level (ft.): First ▽ 19, Completion ▼ ---, 24 HR. ▼ ---
Casing Hammer: --- / Weight (lbs): --- / Drop (in): ---	Drilling Foreman: Julio Galarzia
Sampler: 1.75" x 5' Long Acetate Lined Macrocore	Field Engineer: Esther Arthur
Sampler Hammer: --- / Weight (lbs): --- / Drop (in): ---	

MATERIAL SYMBOL	Elev. (ft) +18.4	Sample Description	Depth Scale	Sample Data: Number	Type	Recov. (in)	Penetr. resist BL/6in	PID (ppm)	Remarks (Drilling Fluid, Depth of Casing, Fluid Loss, Drilling Resistance, etc.)
		Brown to gray fine-coarse SAND, some concrete, some gravel, brick fragments (dry) [FILL]	0					0.0	Started Drilling on 2/15/2023
			1					0.0	Collected LSB-32_0-2 from 0 to 2-feet bgs. VOCs collected from 0.5- to 1-feet bgs
			2	M-1	Macrocore	48		0.0	
			3					0.0	
			4					0.0	
			5					0.0	
		Dark brown to gray fine-coarse SAND, some concrete, some gravel, brick fragments (dry) [FILL]	6					0.1	
			7	M-2	Macrocore	54		0.2	
			8					0.6	Collected LSB-32_7-9 from 7- to 9-feet bgs. VOCs collected from 8- to 8.5-feet bgs
			9					33.6	
			10					25.6	
			11					18.4	
			12	M-3	Macrocore	48		5.6	
			13					0.6	Collected LSB-32_13-15 and DUP-1 from 13- to 15-feet bgs. VOCs collected from 13- to 13.5-feet bgs
			14					0.0	
		Dark brown to gray fine-coarse SAND, some concrete, some ash, some gravel, brick fragments (moist) [FILL]	15					0.0	
			16					0.0	
			17	M-4	Macrocore	52		0.0	
			18					0.0	Collected LSB-32_18-20 from 18- to 20-feet bgs. VOCs collected from 18- to 18.5-feet bgs
			19 ▽					0.0	
			20					0.0	

\\LANGAN.COM\DATA\PAR\DATA8\100688801\PROJECT DATA_DISCIPLINE\ENVIRONMENTAL\GINTLOGS\100688801_PHASE 1B.GPJ... 6/14/2023 2:38:12 PM... Report: Log - LANGAN

LANGAN

Log of Boring **LSB-32/LMW-24** Sheet 2 of 2

Project	Project No.
12074 Flatlands Avenue	100688801
Location	**Elevation and Datum**
Brooklyn, New York	18.38-ft NAVD88

MATERIAL SYMBOL	Elev. (ft)	Sample Description	Depth Scale	Sample Data: Number	Type	Recov. (in)	Penetr. resist BL/6in	PID (ppm)	Remarks (Drilling Fluid, Depth of Casing, Fluid Loss, Drilling Resistance, etc.)
	-1.6	Dark brown to gray fine-coarse SAND, some concrete, some ash, some gravel, brick fragments (wet) [FILL]	20	M-5	Macrocore	56		0.0	
			21					0.0	
			22					0.0	
			23					0.0	
			24					0.0	
			25					0.0	
	-6.6		26					0.0	LMW-24 installed to 24-feet bgs
			27						Bottom of boring at 25-feet bgs
			28						
			29						
			30						
			31						
			32						
			33						
			34						
			35						
			36						
			37						
			38						
			39						
			40						
			41						
			42						
			43						
			44						
			45						

\\LANGAN.COM\DATA\PAR\DATA8\100688801\PROJECT DATA_DISCIPLINE\ENVIRONMENTAL\GINTLOGS\100688801_PHASE 1B.GPJ ... 6/14/2023 2:38:13 PM ... Report: Log - LANGAN

LANGAN

Log of Boring **LSB-33** Sheet 1 of 2

Project: 12074 Flatlands Avenue	Project No.: 100688801
Location: Brooklyn, New York	Elevation and Datum: 18.34-ft NAVD88
Drilling Company: AARCO Environmental Services Corp.	Date Started: 02/15/2023 / Date Finished: 02/15/2023
Drilling Equipment: Geoprobe 7822 DT	Completion Depth: 25 ft / Rock Depth: ---
Size and Type of Bit: 2-inch Direct Push	Number of Samples: Disturbed 5 / Undisturbed --- / Core ---
Casing Diameter (in): --- / Casing Depth (ft): ---	Water Level (ft.): First ▽ 16 / Completion ▼ --- / 24 HR. ▼ ---
Casing Hammer: --- / Weight (lbs): --- / Drop (in): ---	Drilling Foreman: Julio Galarzia
Sampler: 1.75" x 5' Long Acetate Lined Macrocore	Field Engineer: Esther Arthur
Sampler Hammer: --- / Weight (lbs): --- / Drop (in): ---	

Material Symbol	Elev. (ft) +18.3	Sample Description	Depth Scale	Sample Data: Number	Type	Recov. (in)	Penetr. resist BL/6in	PID (ppm)	Remarks (Drilling Fluid, Depth of Casing, Fluid Loss, Drilling Resistance, etc.)
		Dark brown to black fine-coarse SAND, some coal, some gravel, brick fragments (dry) [FILL]	0	M-1	Macrocore	55		0.0	Started Drilling on 2/15/2023
			1					0.0	Collected LSB-33_0-2 from 0 to 2-feet bgs. VOCs collected from 0.5- to 1-feet bgs
			2					0.0	
			3					0.0	
			4					0.0	
		Dark brown to black fine-coarse SAND, some coal, some gravel, brick fragments (dry) [FILL]	5	M-2	Macrocore	57		0.0	
			6					0.0	Collected LSB-33_6-8 from 6- to 8-feet bgs. VOCs collected from 6- to 6.5-feet bgs
			7					0.0	
		Dark gray to black fine-coarse SAND, trace gravel (dry) [FILL]	8					0.0	
		Dark brown to black fine-medium SAND, some wood, trace gravel (dry) [FILL]	9					0.0	
			10	M-3	Macrocore	40		0.0	
			11					0.0	
			12					0.0	
			13					0.0	Collected LSB-33_13-15 from 13- to 15-feet bgs. VOCs collected from 13- to 13.5-feet bgs
			14					0.0	
		Dark brown to black fine-coarse SAND, some wood, some ash, trace gravel (wet) [FILL]	15					0.0	
			16 ▽					0.0	
			17	M-4	Macrocore	40		0.0	
			18					0.0	Collected LSB-33_19-21 from 19- to 21-feet bgs. VOCs collected from 20- to 20.5-feet bgs
			19					0.0	
			20					0.0	

\\LANGAN.COM\DATA\PAR\DATA8\100688801\PROJECT DATA_DISCIPLINE\ENVIRONMENTAL\GINTLOGS\100688801_PHASE 1B.GPJ... 6/14/2023 2:38:14 PM... Report: Log - LANGAN

LANGAN

Log of Boring **LSB-33** Sheet 2 of 2

Project	Project No.
12074 Flatlands Avenue	100688801
Location	**Elevation and Datum**
Brooklyn, New York	18.34-ft NAVD88

MATERIAL SYMBOL	Elev. (ft)	Sample Description	Depth Scale	Sample Data: Number	Type	Recov. (in)	Penetr. resist BL/6in	PID (ppm)	Remarks (Drilling Fluid, Depth of Casing, Fluid Loss, Drilling Resistance, etc.)
	-1.8	Dark gray to black fine-coarse SAND, some wood, trace ash, trace gravel (wet) [FILL]	20	M-5	Macrocore	50		0.0	
			21					0.0	
			22					0.0	
			23					0.0	
			24					0.0	
	-6.8		25					0.0	Bottom of boring at 25-feet bgs
			26						
			27						
			28						
			29						
			30						
			31						
			32						
			33						
			34						
			35						
			36						
			37						
			38						
			39						
			40						
			41						
			42						
			43						
			44						
			45						

\\LANGAN.COM\DATA\PAR\DATA8\100688801\PROJECT DATA_DISCIPLINE\ENVIRONMENTAL\GINTLOGS\100688801_PHASE 1B.GPJ ... 6/14/2023 2:38:15 PM ... Report: Log - LANGAN

LANGAN

Log of Boring **LSB-34/LMW-17** Sheet 1 of 2

Project: 12074 Flatlands Avenue	Project No.: 100688801
Location: Brooklyn, New York	Elevation and Datum: 19.93-ft NAVD88
Drilling Company: AARCO Environmental Services Corp.	Date Started: 02/16/2023 / Date Finished: 02/16/2023
Drilling Equipment: Geoprobe 7822 DT	Completion Depth: 25 ft / Rock Depth: ---
Size and Type of Bit: 2-inch Direct Push	Number of Samples: Disturbed 5 / Undisturbed --- / Core ---
Casing Diameter (in): --- / Casing Depth (ft): ---	Water Level (ft.): First ▽ 20 / Completion ▼ --- / 24 HR. ▼ ---
Casing Hammer: --- / Weight (lbs): --- / Drop (in): ---	Drilling Foreman: Julio Galarzia
Sampler: 1.75" x 5' Long Acetate Lined Macrocore	Field Engineer: Esther Arthur
Sampler Hammer: --- / Weight (lbs): --- / Drop (in): ---	

Material Symbol	Elev. (ft)	Sample Description	Depth Scale	Sample Data: Number	Type	Recov. (in)	Penetr. resist BL/6in	PID (ppm)	Remarks (Drilling Fluid, Depth of Casing, Fluid Loss, Drilling Resistance, etc.)
	+19.9								
	+19.7	ASPHALT	0					0.0	Started Drilling on 2/16/2023
		Dark gray to dark brown fine-coarse SAND, some brick, concrete fragments (dry) [FILL]	1					0.0	Collected LSB-34_0-2 from 0 to 2-feet bgs. VOCs collected from 0.5- to 1-feet bgs
			2	M-1	Macrocore	56		0.0	
			3					0.0	
			4					0.0	
		Gray to dark brown fine-medium SAND, some gravel, concrete lenses, brick lenses (dry) [FILL]	5					0.0	
			6					0.0	
			7	M-2	Macrocore	50		0.0	Collected LSB-34_7-9 from 7- to 9-feet bgs. VOCs collected from 7.5- to 8-feet bgs
			8					0.0	
			9					0.0	
		Dark brown to black fine-coarse SAND, some brick, some concrete, some wood, some gravel, glass fragments (moist) [FILL]	10					0.0	
			11					0.0	
			12	M-3	Macrocore	40		0.0	
			13					0.0	Collected LSB-34_13-15 from 13- to 15-feet bgs. VOCs collected from 13.5- to 14-feet bgs
			14					0.0	
			15					0.0	
			16					0.0	
			17	M-4	Macrocore	38		0.0	
			18					0.0	
			19					0.0	
			20 ▽					0.0	

\LANGAN.COM\DATA\PAR\DATA8\100688801\PROJECT DATA_DISCIPLINE\ENVIRONMENTAL\GINTLOGS\100688801_PHASE 1B.GPJ... 6/14/2023 2:38:17 PM... Report: Log - LANGAN

LANGAN

Log of Boring **LSB-34/LMW-17** Sheet 2 of 2

Project	Project No.
12074 Flatlands Avenue	100688801
Location	**Elevation and Datum**
Brooklyn, New York	19.93-ft NAVD88

MATERIAL SYMBOL	Elev. (ft)	Sample Description	Depth Scale	Sample Data: Number	Type	Recov. (in)	Penetr. resist BL/6in	PID (ppm)	Remarks (Drilling Fluid, Depth of Casing, Fluid Loss, Drilling Resistance, etc.)
	-0.1		20						
		Dark brown to black fine-coarse SAND, some brick, some concrete, some wood, some gravel, glass fragments (wet) [FILL]	21	M-5	Macrocore	40		0.0	Collected LSB-34_20-22 from 20- to 22-feet bgs. VOCs collected from 20- to 20.5-feet bgs
			22					0.0	
			23					0.0	
			24					0.0	
	-5.1		25					0.0	Bottom of boring at 25-feet bgs. LMW-17 installed to 25-feet bgs.
			26						
			27						
			28						
			29						
			30						
			31						
			32						
			33						
			34						
			35						
			36						
			37						
			38						
			39						
			40						
			41						
			42						
			43						
			44						
			45						

\\LANGAN.COM\DATA\PAR\DATA8\100688801\PROJECT DATA_DISCIPLINE\ENVIRONMENTAL\GINTLOGS\100688801_PHASE 1B.GPJ ... 6/14/2023 2:38:17 PM ... Report: Log - LANGAN

LANGAN

Log of Boring **LSB-35/LMW-18** Sheet 1 of 2

Project: 12074 Flatlands Avenue	Project No.: 100688801
Location: Brooklyn, New York	Elevation and Datum: 21.00-ft NAVD88
Drilling Company: AARCO Environmental Services Corp.	Date Started: 02/15/2023 / Date Finished: 02/15/2023
Drilling Equipment: Geoprobe 7822 DT	Completion Depth: 25 ft / Rock Depth: ---
Size and Type of Bit: 2-inch Direct Push	Number of Samples: Disturbed 5, Undisturbed ---, Core ---
Casing Diameter (in): --- / Casing Depth (ft): ---	Water Level (ft.): First ▽ 20, Completion ▼ ---, 24 HR. ▼ ---
Casing Hammer: --- / Weight (lbs): --- / Drop (in): ---	Drilling Foreman: Julio Galarzia
Sampler: 1.75" x 5' Long Acetate Lined Macrocore	Field Engineer: Esther Arthur
Sampler Hammer: --- / Weight (lbs): --- / Drop (in): ---	

MATERIAL SYMBOL	Elev. (ft) +21.0	Sample Description	Depth Scale	Sample Data: Number	Type	Recov. (in)	Penetr. resist BL/6in	PID (ppm)	Remarks (Drilling Fluid, Depth of Casing, Fluid Loss, Drilling Resistance, etc.)
		Dark brown to black fine-coarse SAND, some gravel, trace concrete, glass fragments (dry) [FILL]	0	M-1	Macrocore	45		0.0	Started Drilling on 2/15/2023
			1					0.0	Collected LSB-35_0-2 from 0 to 2-feet bgs. VOCs collected from 0.5- to 1-feet bgs
			2					0.0	
			3					0.0	
			4					0.0	
			5	M-2	Macrocore	60		0.0	
			6					0.0	Collected LSB-35_6-8 from 6- to 8-feet bgs. VOCs collected from 7- to 7.5-feet bgs
			7					0.0	
			8					0.0	
			9					0.0	
			10	M-3	Macrocore	50		0.0	
			11					0.0	
			12					0.0	
			13					0.0	Collected LSB-35_13-15 from 13- to 15-feet bgs. VOCs collected from 13- to 13.5-feet bgs
			14					0.0	
		Dark brown to black fine-medium SAND, some gravel, trace concrete, glass fragments (dry) [FILL]	15					0.0	
			16					0.0	
			17	M-4	Macrocore	48		0.0	
			18					0.0	Collected LSB-35_18-20 from 18- to 20-feet bgs. VOCs collected from 18- to 18.5-feet bgs
		Brown fine-medium SAND, trace gravel (dry) [FILL]	19					0.0	
		Dark brown to black fine-coarse SAND, some ash, some gravel, glass fragments (moist) [FILL] ▽	20					0.0	

\\LANGAN.COM\DATA\PAR\DATA8\100688801\PROJECT DATA_DISCIPLINE\ENVIRONMENTAL\GINTLOGS\100688801_PHASE 1B.GPJ... 6/14/2023 2:38:20 PM... Report: Log - LANGAN

LANGAN

Log of Boring **LSB-35/LMW-18** Sheet 2 of 2

Project	Project No.
12074 Flatlands Avenue	100688801
Location	**Elevation and Datum**
Brooklyn, New York	21.00-ft NAVD88

MATERIAL SYMBOL	Elev. (ft)	Sample Description	Depth Scale	Sample Data: Number	Type	Recov. (in)	Penetr. resist BL/6in	PID (ppm)	Remarks (Drilling Fluid, Depth of Casing, Fluid Loss, Drilling Resistance, etc.)
	+1.0	Dark brown to black fine-coarse SAND, some ash, some gravel, glass fragments (wet) [FILL]	20	M-5	Macrocore	40		0.0	
			21					0.0	
			22					0.0	
			23					0.0	
			24					0.0	
			25					0.0	
	-4.0		26						Bottom of boring at 25-feet bgs. LMW-18 installed to 25-feet bgs
			27						
			28						
			29						
			30						
			31						
			32						
			33						
			34						
			35						
			36						
			37						
			38						
			39						
			40						
			41						
			42						
			43						
			44						
			45						

\\LANGAN.COM\DATA\PAR\DATA8\100688801\PROJECT DATA_DISCIPLINE\ENVIRONMENTAL\GINTLOGS\100688801_PHASE 1B.GPJ ... 6/14/2023 2:38:20 PM ... Report: Log - LANGAN

LANGAN

Log of Boring **LSB-36/LMW-19** Sheet 1 of 2

Project: 12074 Flatlands Avenue	Project No.: 100688801
Location: Brooklyn, New York	Elevation and Datum: 20.09-ft NAVD88
Drilling Company: AARCO Environmental Services Corp.	Date Started: 02/15/2023 / Date Finished: 02/15/2023
Drilling Equipment: Geoprobe 7822 DT	Completion Depth: 25 ft / Rock Depth: ---
Size and Type of Bit: 2-inch Direct Push	Number of Samples: Disturbed 5 / Undisturbed --- / Core ---
Casing Diameter (in): --- / Casing Depth (ft): ---	Water Level (ft.): First ▽ 17 / Completion ▼ --- / 24 HR. ▼ ---
Casing Hammer: --- / Weight (lbs): --- / Drop (in): ---	Drilling Foreman: Julio Galarzia
Sampler: 1.75" x 5' Long Acetate Lined Macrocore	Field Engineer: Esther Arthur
Sampler Hammer: --- / Weight (lbs): --- / Drop (in): ---	

Material Symbol	Elev. (ft)	Sample Description	Depth Scale	Sample Data: Number	Type	Recov. (in)	Penetr. resist BL/6in	PID (ppm)	Remarks (Drilling Fluid, Depth of Casing, Fluid Loss, Drilling Resistance, etc.)
	+20.1	Brown to black fine-coarse SAND, some gravel, concrete fragments, brick fragments (dry) [FILL]	0	M-1	Macrocore	55		0.0	Started Drilling on 2/15/2023
			1					0.0	Collected LSB-36_0-2 from 0 to 2-feet bgs. VOCs collected from 0.5- to 1-feet bgs
			2					0.0	
			3					0.0	
			4					0.0	
	+15.8	CONCRETE						0.0	
	+15.1	Dark brown to black fine-coarse SAND, some concrete, some coal, some brick, some gravel (moist) [FILL]	5	M-2	Macrocore	53		0.0	
			6					0.0	
			7					0.0	Collected LSB-36_7-9 from 6- to 8-feet bgs. VOCs collected from 7- to 7.5-feet bgs
			8					0.0	
			9					0.0	
			10	M-3	Macrocore	38		0.0	
			11					0.0	
			12					0.0	
			13					0.0	Collected LSB-36_13-15 from 13- to 15-feet bgs. VOCs collected from 14- to 14.5-feet bgs
			14					0.0	
		Dark brown to black fine-coarse SAND, some concrete, some coal, some brick, some gravel (wet) [FILL]	15	M-4	Macrocore	48		0.0	
			16					0.0	
		▽	17					0.0	
			18					0.0	
			19					0.0	
			20					0.0	

\\LANGAN.COM\DATA\PAR\DATA8\100688801\PROJECT DATA_DISCIPLINE\ENVIRONMENTAL\GINTLOGS\100688801_PHASE 1B.GPJ... 6/14/2023 2:38:23 PM... Report: Log - LANGAN

LANGAN

Log of Boring **LSB-36/LMW-19** Sheet 2 of 2

Project	Project No.
12074 Flatlands Avenue	100688801
Location	**Elevation and Datum**
Brooklyn, New York	20.09-ft NAVD88

MATERIAL SYMBOL	Elev. (ft)	Sample Description	Depth Scale	Sample Data: Number	Type	Recov. (in)	Penetr. resist BL/6in	PID (ppm)	Remarks (Drilling Fluid, Depth of Casing, Fluid Loss, Drilling Resistance, etc.)
	+0.1	Dark brown to black fine-coarse SAND, some concrete, some coal, some brick, some gravel (wet) [FILL]	20	M-5	Macrocore	30		0.0	Collected LSB-36_20-22 from 20- to 22-feet bgs. VOCs collected from 20- to 20.5-feet bgs
			21					0.0	
			22					0.0	
			23					0.0	
			24					0.0	LMW-19 installed to 24-feet bgs
	-4.9		25					0.0	Bottom of boring at 25-feet bgs.
			26						
			27						
			28						
			29						
			30						
			31						
			32						
			33						
			34						
			35						
			36						
			37						
			38						
			39						
			40						
			41						
			42						
			43						
			44						
			45						

\\LANGAN.COM\DATA\PAR\DATA8\100688801\PROJECT DATA_DISCIPLINE\ENVIRONMENTAL\GINTLOGS\100688801_PHASE 1B.GPJ ... 6/14/2023 2:38:23 PM ... Report: Log - LANGAN

LANGAN

Log of Boring **LSB-37** Sheet 1 of 2

Project: 12074 Flatlands Avenue	Project No.: 100688801
Location: Brooklyn, New York	Elevation and Datum: 19.75-ft NAVD88
Drilling Company: AARCO Environmental Services Corp.	Date Started: 02/16/2023 / Date Finished: 02/16/2023
Drilling Equipment: Geoprobe 7822 DT	Completion Depth: 25 ft / Rock Depth: ---
Size and Type of Bit: 2-inch Direct Push	Number of Samples: Disturbed 5, Undisturbed ---, Core ---
Casing Diameter (in): --- / Casing Depth (ft): ---	Water Level (ft.): First ▽ 20, Completion ▼ ---, 24 HR. ▼ ---
Casing Hammer: --- / Weight (lbs): --- / Drop (in): ---	Drilling Foreman: Julio Galarzia
Sampler: 1.75" x 5' Long Acetate Lined Macrocore	Field Engineer: Esther Arthur
Sampler Hammer: --- / Weight (lbs): --- / Drop (in): ---	

MATERIAL SYMBOL	Elev. (ft) +19.8	Sample Description	Depth Scale	Sample Data: Number	Type	Recov. (in)	Penetr. resist BL/6in	PID (ppm)	Remarks (Drilling Fluid, Depth of Casing, Fluid Loss, Drilling Resistance, etc.)
		Dark brown fine-medium SAND, some gravel, trace brick (dry) [FILL]	0	M-1	Macrocore	45		0.0	Started Drilling on 2/16/2023
			1					0.0	
								0.0	Collected LSB-37_0-2 from 0 to 2-feet bgs. VOCs collected from 0.5- to 1-feet bgs
			2					0.0	
								0.0	
			3					0.0	
								0.0	
			4					0.0	
								0.0	
		Dark brown fine-medium SAND, some concrete, some wood, some gravel, trace brick, trace glass (dry) [FILL]	5	M-2	Macrocore	50		0.1	
								0.1	
			6					0.1	Collected LSB-37_6-8 from 6- to 8-feet bgs. VOCs collected from 6.5- to 7-feet bgs
								0.1	
			7					0.1	
								0.1	
			8					0.1	
								0.1	
			9					0.1	
								0.1	
			10	M-3	Macrocore	50		0.0	
								0.0	
			11					0.0	
								0.0	
			12					0.0	
								0.0	
			13					0.0	Collected LSB-37_13-15 from 13- to 15-feet bgs. VOCs collected from 13.5- to 14-feet bgs
								0.0	
			14					0.0	
								0.0	
			15	M-4	Macrocore	38		0.0	
								0.0	
			16					0.0	
								0.0	
			17					0.0	
								0.0	
			18					0.0	Collected LSB-37_18-20 from 18- to 20-feet bgs. VOCs collected from 18- to 18.5-feet bgs
								0.0	
			19					0.0	
								0.0	
			20 ▽						

\\LANGAN.COM\DATA\PAR\DATA8\100688801\PROJECT DATA_DISCIPLINE\ENVIRONMENTAL\GINTLOGS\100688801_PHASE 1B.GPJ... 6/14/2023 2:38:26 PM... Report: Log - LANGAN

LANGAN

Log of Boring **LSB-37** Sheet 2 of 2

Project	Project No.
12074 Flatlands Avenue	100688801
Location	**Elevation and Datum**
Brooklyn, New York	19.75-ft NAVD88

MATERIAL SYMBOL	Elev. (ft)	Sample Description	Depth Scale	Sample Data: Number	Type	Recov. (in)	Penetr. resist BL/6in	PID (ppm)	Remarks (Drilling Fluid, Depth of Casing, Fluid Loss, Drilling Resistance, etc.)
	-0.3	Brown fine-medium SAND, some concrete, some wood, some gravel, trace brick, trace glass (wet) [FILL]	20	M-5	Macrocore	38		0.0	
			21					0.0	
			22					0.0	
		Grayish olive to orange CLAY, some silt (wet) [FILL]	23					0.0	
		Black fine-medium SAND, some concrete, some wood, some gravel, trace brick, trace glass (wet) [FILL]	24					0.0	
	-5.3		25					0.0	Bottom of boring at 25-feet bgs.
			26						
			27						
			28						
			29						
			30						
			31						
			32						
			33						
			34						
			35						
			36						
			37						
			38						
			39						
			40						
			41						
			42						
			43						
			44						
			45						

\\LANGAN.COM\DATA\PAR\DATA8\100688801\PROJECT DATA_DISCIPLINE\ENVIRONMENTAL\GINTLOGS\100688801_PHASE 1B.GPJ ... 6/14/2023 2:38:26 PM ... Report: Log - LANGAN

LANGAN

Log of Boring **LSB-38/LMW-20** Sheet 1 of 2

Project: 12074 Flatlands Avenue	Project No.: 100688801
Location: Brooklyn, New York	Elevation and Datum: 21.86-ft NAVD88
Drilling Company: AARCO Environmental Services Corp.	Date Started: 02/16/2023 / Date Finished: 02/16/2023
Drilling Equipment: Geoprobe 7822 DT	Completion Depth: 26 ft / Rock Depth: ---
Size and Type of Bit: 2-inch Direct Push	Number of Samples: Disturbed 5 / Undisturbed --- / Core ---
Casing Diameter (in): --- / Casing Depth (ft): ---	Water Level (ft.): First ▽ 22 / Completion ▼ --- / 24 HR. ▼ ---
Casing Hammer: --- / Weight (lbs): --- / Drop (in): ---	Drilling Foreman: Julio Galarzia
Sampler: 1.75" x 5' Long Acetate Lined Macrocore	Field Engineer: Esther Arthur
Sampler Hammer: --- / Weight (lbs): --- / Drop (in): ---	

Material Symbol	Elev. (ft)	Sample Description	Depth Scale	Sample Data: Number	Type	Recov. (in)	Penetr. resist BL/6in	PID (ppm)	Remarks (Drilling Fluid, Depth of Casing, Fluid Loss, Drilling Resistance, etc.)
	+21.9	Dark brown fine-coarse SAND, some brick, some concrete, some gravel (dry) [FILL]	0	M-1	Macrocore	48		0.0	Started Drilling on 2/16/2023 Collected LSB-38_0-2 and DUP-2 from 0 to 2-feet bgs. VOCs collected from 0.5- to 1-feet bgs
		Gray to dark brown fine-coarse SAND, some gravel, trace glass, concrete fragments (dry) [FILL]	5	M-2	Macrocore	55		0.0	Collected LSB-38_7-9 from 7- to 9-feet bgs. VOCs collected from 7.5- to 8-feet bgs
		Brown fine-coarse SAND, some wood, some gravel, trace glass, concrete fragments (dry) [FILL]	10	M-3	Macrocore	60		0.0	Collected LSB-38_13-15 (Hold) from 13- to 15-feet bgs. VOCs collected from 13- to 13.5-feet bgs
	+4.7	CONCRETE	15	M-4	Macrocore	45		0.0	Collected LSB-38_16-18 (Hold) from 16- to 18-feet bgs. VOCs collected from 16- to 16.5-feet bgs
	+3.7	Brown fine-coarse SAND, some wood, some gravel, trace glass, concrete fragments (dry) [FILL]	20						

\LANGAN.COM\DATA\PAR\DATA8\100688801\PROJECT DATA_DISCIPLINE\ENVIRONMENTAL\GINTLOGS\100688801_PHASE 1B.GPJ... 6/14/2023 2:38:29 PM ... Report: Log - LANGAN

LANGAN

Log of Boring **LSB-38/LMW-20** Sheet 2 of 2

Project	Project No.
12074 Flatlands Avenue	100688801
Location	**Elevation and Datum**
Brooklyn, New York	21.86-ft NAVD88

Material Symbol	Elev. (ft)	Sample Description	Depth Scale	Sample Data: Number	Type	Recov. (in)	Penetr. resist BL/6in	PID (ppm)	Remarks (Drilling Fluid, Depth of Casing, Fluid Loss, Drilling Resistance, etc.)
	+1.9	Brown fine-coarse SAND, some wood, some gravel, trace glass, concrete fragments (wet) [FILL]	20	M-5	Macrocore	40		0.0	Collected LSB-38_20-22 from 20- to 22-feet bgs. VOCs collected from 20- to 20.5-feet bgs
			21					0.0	
			22					0.0	
			23					0.0	
			24					0.0	
			25					0.0	
				M-6	Macrocore	10		0.0	
	-4.1		26						Bottom of boring at 26-feet bgs. LMW-20 installed to 26-feet bgs
			27						
			28						
			29						
			30						
			31						
			32						
			33						
			34						
			35						
			36						
			37						
			38						
			39						
			40						
			41						
			42						
			43						
			44						
			45						

\\LANGAN.COM\DATA\PAR\DATA8\100688801\PROJECT DATA_DISCIPLINE\ENVIRONMENTAL\GINTLOGS\100688801_PHASE 1B.GPJ ... 6/14/2023 2:38:30 PM ... Report: Log - LANGAN

LANGAN

Log of Boring **LSB-39** Sheet 1 of 2

Project: 12074 Flatlands Avenue	Project No.: 100688801
Location: Brooklyn, New York	Elevation and Datum: 20.50-ft NAVD88
Drilling Company: AARCO Environmental Services Corp.	Date Started: 02/16/2023 / Date Finished: 02/16/2023
Drilling Equipment: Geoprobe 7822 DT	Completion Depth: 25 ft / Rock Depth: ---
Size and Type of Bit: 2-inch Direct Push	Number of Samples: Disturbed 5, Undisturbed ---, Core ---
Casing Diameter (in): --- / Casing Depth (ft): ---	Water Level (ft.): First ▽ 22, Completion ▼ ---, 24 HR. ▼ ---
Casing Hammer: --- / Weight (lbs): --- / Drop (in): ---	Drilling Foreman: Julio Galarzia
Sampler: 1.75" x 5' Long Acetate Lined Macrocore	Field Engineer: Esther Arthur
Sampler Hammer: --- / Weight (lbs): --- / Drop (in): ---	

MATERIAL SYMBOL	Elev. (ft)	Sample Description	Depth Scale	Sample Data: Number	Type	Recov. (in)	Penetr. resist BL/6in	PID (ppm)	Remarks (Drilling Fluid, Depth of Casing, Fluid Loss, Drilling Resistance, etc.)
	+20.5	Dark brown fine-coarse SAND, some wood, some gravel, trace concrete, trace brick, trace glass (dry) [FILL]	0	M-1	Macrocore	57		0.0	Started Drilling on 2/16/2023
			1					0.0	
								0.0	Collected LSB-39_0-2 from 0 to 2-feet bgs. VOCs collected from 0.5- to 1-feet bgs
			2					0.0	
								0.0	
			3					0.0	
								0.0	
			4					0.0	
								0.0	
		Brown fine-coarse SAND, some wood, some gravel, trace concrete, trace brick, trace glass (dry) [FILL]	5	M-2	Macrocore	52		0.0	
								0.0	
			6					0.0	
								0.0	
			7					0.0	Collected LSB-39_7-9 from 6- to 8-feet bgs. VOCs collected from 7- to 7.5-feet bgs
	+12.5							0.0	
	+12.1	CONCRETE	8					0.0	
		Brown fine-coarse SAND, some wood, some gravel, trace concrete, trace brick, trace glass (dry) [FILL]						0.0	
			9					0.0	
								0.0	
		Dark brown fine-coarse SAND, trace wood, trace gravel (dry) [FILL]	10	M-3	Macrocore	48		0.0	
								0.0	
			11					0.0	
								0.0	
			12					0.0	
								0.0	
			13					0.0	Collected LSB-39_13-15 from 13- to 15-feet bgs. VOCs collected from 13- to 13.5-feet bgs
								0.0	
			14					0.0	
								0.0	
			15	M-4	Macrocore	40		0.0	
								0.0	
			16					0.0	
								0.0	
			17					0.0	
								0.0	
			18					0.0	
								0.0	
			19					0.0	
								0.0	
			20					0.0	

\\LANGAN.COM\DATA\PAR\DATA8\100688801\PROJECT DATA_DISCIPLINE\ENVIRONMENTAL\GINTLOGS\100688801_PHASE 1B.GPJ... 6/14/2023 2:38:32 PM... Report: Log - LANGAN

LANGAN

Log of Boring **LSB-39** Sheet 2 of 2

Project	Project No.
12074 Flatlands Avenue	100688801
Location	**Elevation and Datum**
Brooklyn, New York	20.50-ft NAVD88

MATERIAL SYMBOL	Elev. (ft)	Sample Description	Depth Scale	Sample Data: Number	Type	Recov. (in)	Penetr. resist BL/6in	PID (ppm)	Remarks (Drilling Fluid, Depth of Casing, Fluid Loss, Drilling Resistance, etc.)
	+0.5	Dark brown fine-coarse SAND, trace wood, trace gravel, brick fragments (wet) [FILL]	20	M-5	Macrocore	38		0.0	Collected LSB-39_20-22 from 20- to 22-feet bgs. VOCs collected from 20- to 20.5-feet bgs
			21					0.0	
			22					0.0	
			23					0.0	
			24					0.0	
	-4.5		25					0.0	Bottom of boring at 25-feet bgs.
			26						
			27						
			28						
			29						
			30						
			31						
			32						
			33						
			34						
			35						
			36						
			37						
			38						
			39						
			40						
			41						
			42						
			43						
			44						
			45						

\\LANGAN.COM\DATA\PAR\DATA8\100688801\PROJECT DATA_DISCIPLINE\ENVIRONMENTAL\GINTLOGS\100688801_PHASE 1B.GPJ ... 6/14/2023 2:38:32 PM ... Report: Log - LANGAN

LANGAN

Log of Boring **LSB-40/LMW-21** Sheet 1 of 2

Project: 12074 Flatlands Avenue	Project No.: 100688801
Location: Brooklyn, New York	Elevation and Datum: 22.15-ft NAVD88
Drilling Company: AARCO Environmental Services Corp.	Date Started: 02/17/2023 / Date Finished: 02/17/2023
Drilling Equipment: Geoprobe 6610 DT	Completion Depth: 26 ft / Rock Depth: ---
Size and Type of Bit: 2-inch Direct Push	Number of Samples: Disturbed 5 / Undisturbed --- / Core ---
Casing Diameter (in): --- / Casing Depth (ft): ---	Water Level (ft.): First ▽ 21 / Completion ▼ --- / 24 HR. ▼ ---
Casing Hammer: --- / Weight (lbs): --- / Drop (in): ---	Drilling Foreman: Sergio Magana
Sampler: 1.75" x 5' Long Acetate Lined Macrocore	Field Engineer: Esther Arthur
Sampler Hammer: --- / Weight (lbs): --- / Drop (in): ---	

Material Symbol	Elev. (ft)	Sample Description	Depth Scale	Sample Data: Number	Type	Recov. (in)	Penetr. resist BL/6in	PID (ppm)	Remarks (Drilling Fluid, Depth of Casing, Fluid Loss, Drilling Resistance, etc.)
	+22.2	Black fine-coarse SAND, trace gravel (dry) [FILL]	0					0.0	Started Drilling on 2/17/2023
		Brown to dark brown fine-coarse SAND, some wood, some gravel, glass fragments (dry) [FILL]	1					0.0	Collected LSB-40_0-2 from 0 to 2-feet bgs. VOCs collected from 0.5- to 1-feet bgs
			2	M-1	Macrocore	56		0.0	
			3					0.0	
			4					0.0	
		Dark brown to black fine-coarse SAND, some wood, some gravel, glass fragments (dry) [FILL]	5					0.0	
			6					0.0	
			7	M-2	Macrocore	48		0.0	Collected LSB-40_7-9 from 7 to 9-feet bgs. VOCs collected from 7.5- to 8-feet bgs
			8					0.0	
			9					0.0	
		Dark brown to black fine-coarse SAND, some wood, some coal, some gravel, glass fragments (dry) [FILL]	10					0.0	
			11					0.0	
			12	M-3	Macrocore	40		0.0	
			13					0.0	
			14					0.0	
		Dark brown to black fine-coarse SAND, some wood, some gravel (wet) [FILL]	15					0.0	
			16					0.0	
			17	M-4	Macrocore	38		0.0	Collected LSB-40_17-19 from 17- to 19-feet bgs. VOCs collected from 17- to 17.5-feet bgs
			18					0.0	
			19					0.0	
			20					0.0	

\\LANGAN.COM\DATA\PAR\DATA8\100688801\PROJECT DATA_DISCIPLINE\ENVIRONMENTAL\GINTLOGS\100688801_PHASE 1B.GPJ... 6/14/2023 2:38:35 PM ... Report: Log - LANGAN

LANGAN

Log of Boring **LSB-40/LMW-21** Sheet 2 of 2

Project	Project No.
12074 Flatlands Avenue	100688801
Location	**Elevation and Datum**
Brooklyn, New York	22.15-ft NAVD88

Material Symbol	Elev. (ft)	Sample Description	Depth Scale	Sample Data: Number	Type	Recov. (in)	Penetr. resist BL/6in	PID (ppm)	Remarks (Drilling Fluid, Depth of Casing, Fluid Loss, Drilling Resistance, etc.)
	+2.2	Brown to black fine-coarse SAND, some wood, some gravel (wet) [FILL]	20	M-5	Macrocore	42		0.0	Collected LSB-40_20-22 from 20- to 22-feet bgs. VOCs collected from 21.5- to 22-feet bgs
			21					0.0	
		Brown fine-medium SAND, trace gravel (wet) [FILL]	22					0.0	
			23					0.0	
			24					0.0	
		Brown to black fine-coarse SAND, some wood, some gravel (wet) [FILL]	25	M-6	Macrocore	10		0.0	
	-3.9		26					0.0	Bottom of boring at 26-feet bgs. LMW-21 installed to 26-feet bgs.
			27						
			28						
			29						
			30						
			31						
			32						
			33						
			34						
			35						
			36						
			37						
			38						
			39						
			40						
			41						
			42						
			43						
			44						
			45						

\\LANGAN.COM\DATA\PAR\DATA8\100688801\PROJECT DATA_DISCIPLINE\ENVIRONMENTAL\GINTLOGS\100688801_PHASE 1B.GPJ ... 6/14/2023 2:38:35 PM ... Report: Log - LANGAN

LANGAN

Log of Boring **LSB-41/LMW-22** Sheet 1 of 2

Project: 12074 Flatlands Avenue	Project No.: 100688801
Location: Brooklyn, New York	Elevation and Datum: 22.21-ft NAVD88
Drilling Company: AARCO Environmental Services Corp.	Date Started: 02/17/2023 / Date Finished: 02/17/2023
Drilling Equipment: Geoprobe 6610 DT	Completion Depth: 25 ft / Rock Depth: ---
Size and Type of Bit: 2-inch Direct Push	Number of Samples: Disturbed 5 / Undisturbed --- / Core ---
Casing Diameter (in): --- / Casing Depth (ft): ---	Water Level (ft.): First ▽ 20 / Completion ▼ --- / 24 HR. ▼ ---
Casing Hammer: --- / Weight (lbs): --- / Drop (in): ---	Drilling Foreman: Sergio Magana
Sampler: 1.75" x 5' Long Acetate Lined Macrocore	Field Engineer: Esther Arthur
Sampler Hammer: --- / Weight (lbs): --- / Drop (in): ---	

Material Symbol	Elev. (ft)	Sample Description	Depth Scale	Sample Data: Number	Type	Recov. (in)	Penetr. resist BL/6in	PID (ppm)	Remarks (Drilling Fluid, Depth of Casing, Fluid Loss, Drilling Resistance, etc.)
	+22.2	Brown to dark brown fine-coarse SAND, some brick, some gravel, concrete fragments (dry) [FILL]	0	M-1	Macrocore	45		0.0	Started Drilling on 2/17/2023 Collected LSB-41_0-2 and DUP-3 from 0 to 2-feet bgs. VOCs collected from 0.5- to 1-feet bgs
			1					0.0	
			2					0.0	
			3					0.0	
			4					0.0	
		Dark brown to black fine-coarse SAND, some brick, some wood, some gravel, concrete fragments (dry) [FILL]	5	M-2	Macrocore	42		0.0	
			6					0.0	
			7					0.0	Collected LSB-41_7-9 from 7 to 9-feet bgs. VOCs collected from 7.5- to 8-feet bgs
			8					0.0	
			9					0.0	
			10	M-3	Macrocore	40		0.0	
			11					0.0	
			12					0.0	
			13					0.0	
			14					0.0	
			15	M-4	Macrocore	42		0.0	
			16					0.0	
			17					0.0	Collected LSB-41_17-19 from 17- to 19-feet bgs. VOCs collected from 17- to 17.5-feet bgs
			18					0.0	
			19					0.0	
	+2.7	CONCRETE	20					0.0	
	+2.2	▽							

\\LANGAN.COM\DATA\PAR\DATA8\100688801\PROJECT DATA_DISCIPLINE\ENVIRONMENTAL\GINTLOGS\100688801_PHASE 1B.GPJ... 6/14/2023 2:38:37 PM... Report: Log - LANGAN

LANGAN

Log of Boring **LSB-41/LMW-22** Sheet 2 of 2

Project	Project No.
12074 Flatlands Avenue	100688801
Location	**Elevation and Datum**
Brooklyn, New York	22.21-ft NAVD88

MATERIAL SYMBOL	Elev. (ft)	Sample Description	Depth Scale	Sample Data: Number	Type	Recov. (in)	Penetr. resist BL/6in	PID (ppm)	Remarks (Drilling Fluid, Depth of Casing, Fluid Loss, Drilling Resistance, etc.)
	+2.2	Dark brown to black fine-coarse SAND, some wood, some gravel (wet) [FILL]	20	M-5	Macrocore	55		0.0	Collected LSB-41_20-22 from 20- to 22-feet bgs. VOCs collected from 21.5- to 22-feet bgs
			21					0.0	
			22					0.0	
			23					0.0	
			24					0.0	
	-2.8		25					0.0	Refusal at 25-feeet bgs. Bottom of boring at 25-feet bgs. LMW-22 installed to 25-feet bgs.
			26					0.0	
			27						
			28						
			29						
			30						
			31						
			32						
			33						
			34						
			35						
			36						
			37						
			38						
			39						
			40						
			41						
			42						
			43						
			44						
			45						

\\LANGAN.COM\DATA\PAR\DATA8\100688801\PROJECT DATA_DISCIPLINE\ENVIRONMENTAL\GINTLOGS\100688801_PHASE 1B.GPJ ... 6/14/2023 2:38:37 PM ... Report: Log - LANGAN

LANGAN

Log of Boring **LSB-42/LMW-23** Sheet 1 of 2

Project: 12074 Flatlands Avenue	Project No.: 100688801
Location: Brooklyn, New York	Elevation and Datum: 22.09-ft NAVD88
Drilling Company: AARCO Environmental Services Corp.	Date Started: 02/17/2023 / Date Finished: 02/17/2023
Drilling Equipment: Geoprobe 6610 DT	Completion Depth: 26 ft / Rock Depth: ---
Size and Type of Bit: 2-inch Direct Push	Number of Samples: Disturbed 5, Undisturbed ---, Core ---
Casing Diameter (in): --- / Casing Depth (ft): ---	Water Level (ft.): First ▽ 20, Completion ▼ ---, 24 HR. ▼ ---
Casing Hammer: --- / Weight (lbs): --- / Drop (in): ---	Drilling Foreman: Sergio Magana
Sampler: 1.75" x 5' Long Acetate Lined Macrocore	Field Engineer: Esther Arthur
Sampler Hammer: --- / Weight (lbs): --- / Drop (in): ---	

MATERIAL SYMBOL	Elev. (ft) +22.1	Sample Description	Depth Scale	Sample Data: Number	Type	Recov. (in)	Penetr. resist BL/6in	PID (ppm)	Remarks (Drilling Fluid, Depth of Casing, Fluid Loss, Drilling Resistance, etc.)
		Brown to black fine-coarse SAND, some gravel (dry) [FILL]	0					0.0	Started Drilling on 2/17/2023
			1					0.0	
								0.0	Collected LSB-42_0-2 from 0 to 2-feet bgs. VOCs collected from 0.5- to 1-feet bgs
			2					0.0	
				M-1	Macrocore	44		0.0	
			3					0.0	
								0.0	
			4					0.0	
								0.0	
		Brown to black fine-coarse SAND, some wood, some gravel, glass fragments (dry) [FILL]	5					0.0	
								0.0	
			6					0.0	
								0.0	
			7					0.0	Collected LSB-42_6-8 from 6 to 8-feet bgs. VOCs collected from 7.5- to 8-feet bgs
				M-2	Macrocore	40		0.0	
			8					0.0	
								0.0	
			9					0.0	
								0.0	
			10					0.0	
								0.0	
			11					0.0	
								0.0	
			12					0.0	
				M-3	Macrocore	40		0.0	
			13					0.0	
								0.0	
			14					0.0	
								0.0	
			15					0.0	
		Brown to black fine-coarse SAND, some wood, some gravel, trace brick, glass fragments (dry) [FILL]						0.0	
			16					0.0	
								0.0	
			17					0.0	Collected LSB-42_17-19 from 17- to 19-feet bgs. VOCs collected from 17- to 17.5-feet bgs
				M-4	Macrocore	42		0.0	
			18					0.0	
								0.0	
			19					0.0	
								0.0	
			20 ▽					0.0	

\\LANGAN.COM\DATA\PAR\DATA8\100688801\PROJECT DATA_DISCIPLINE\ENVIRONMENTAL\GINTLOGS\100688801_PHASE 1B.GPJ... 6/14/2023 2:38:39 PM ... Report: Log - LANGAN

LANGAN

Log of Boring **LSB-42/LMW-23** Sheet 2 of 2

Project	Project No.
12074 Flatlands Avenue	100688801
Location	**Elevation and Datum**
Brooklyn, New York	22.09-ft NAVD88

MATERIAL SYMBOL	Elev. (ft)	Sample Description	Depth Scale	Sample Data: Number	Type	Recov. (in)	Penetr. resist BL/6in	PID (ppm)	Remarks (Drilling Fluid, Depth of Casing, Fluid Loss, Drilling Resistance, etc.)
	+2.1	Brown to black fine-coarse SAND, some gravel, trace brick (wet) [FILL]	20	M-5	Macrocore	42		0.0	Collected LSB-42_19-21 from 19- to 21-feet bgs. VOCs collected from 20.5- to 21-feet bgs
			21					0.0	
			22						
			23						
			24						
			25	M-6	Macrocore	9			
	-3.9		26						Bottom of boring at 26-feet bgs. LMW-21 installed to 26-feet bgs.
			27						
			28						
			29						
			30						
			31						
			32						
			33						
			34						
			35						
			36						
			37						
			38						
			39						
			40						
			41						
			42						
			43						
			44						
			45						

\\LANGAN.COM\DATA\PAR\DATA8\100688801\PROJECT DATA_DISCIPLINE\ENVIRONMENTAL\GINTLOGS\100688801_PHASE 1B.GPJ ... 6/14/2023 2:38:40 PM ... Report: Log - LANGAN

LANGAN

WELL CONSTRUCTION SUMMARY

Well No. LMW-4

Project: 12074 Flatlands Avenue	Project No.: 100688801
Location: Brooklyn, New York	Elevation And Datum: 21.28 NAVD88
Drilling Agency: AARCO Environmental Services Corp.	Date Started: 2/18/2023 / Date Finished: 2/18/2023
Drilling Equipment: Geoprobe 6610 DT	Driller: Sergio Magana
Size And Type of Bit: 3.75-inch Direct Push	Inspector: Esther Arthur

Method of Installation

AARCO installed a 20-slot Schedule 40 PVC screen from 15 to 25 feet bgs and Schedule 40 PVC riser to the surface. The annulus of the borehole was backfilled to 8-feet bgs with No. 2 Sand and a hydrated bentonite seal from 6 to 8 feet bgs. A manhole was installed and encased in concrete at grade.

Method of Well Development

LMW-4 was developed with a whale pump using surge pumping techniques across the well screen in two- to three-foot increments. After surging, the well was purged via pumping until the water became clear; approximately 30 gallons purged.

Type of Casing:	Diameter:
Type of Backfill Material: Non-Impacted Soil and Bentonite Grout	
Type of Screen: Schedule 40 PVC	Diameter: 2-inch
Type of Seal Material: Bentonite	
Borehole Diameter: 3.75-inch	
Type of Filter Material: No. 2 Sand	

	Elevation	Depth
Top of Casing	21.11'	0.17' bgs
Top of Seal	15.28'	6' bgs
Top of Filter	13.28'	8' bgs
Top of Screen	11.28'	10' bgs
Bottom of Filter	-3.72'	25' bgs
Bottom of Well	-3.72'	25' bgs

Screen Length: 15.0'	Slot Size: 0.020-slot

GROUNDWATER ELEVATIONS (ft)
(Measured from the Top of Casing)

Elevation	DTW	Date



Soil / Rock Classification	Depth (ft)
FILL	0.17
	6
	8
	10
	23
	25

\\LANGAN.COM\DATA\PAR\DATA8\100688801\PROJECT DATA_DISCIPLINE\ENVIRONMENTAL\GINTLOGS\100688801_PHASE 1B.GPJ ... 5/25/2023 4:05:15 PM ... Report: Log - LANGAN_WELL_CONSTRUCTION_SUMMARY

LANGAN

WELL CONSTRUCTION SUMMARY

Well No. LMW-15

Project: 12074 Flatlands Avenue	Project No.: 100688801
Location: Brooklyn, New York	Elevation And Datum: 13.12 NAVD88
Drilling Agency: AARCO Environmental Services Corp.	Date Started: 2/14/2023 / Date Finished: 2/14/2023
Drilling Equipment: Geoprobe 7822 DT	Driller: Julio Galarzia
Size And Type of Bit: 3.75-inch Direct Push	Inspector: Esther Arthur

Method of Installation

AARCO installed a 20-slot Schedule 40 PVC screen from 8 to 18 feet bgs and Schedule 40 PVC riser to the surface. The annulus of the borehole was backfilled to 6-feet bgs with No. 2 Sand and a hydrated bentonite seal from 6 to 8 feet bgs. A manhole was installed and encased in concrete at grade.

Method of Well Development

LMW-15 was developed with a whale pump using surge pumping techniques across the well screen in two- to three-foot increments. After surging, the well was purged via pumping until the water became clear; approximately 20 gallons purged.

Type of Casing: --- / Diameter: ---	Type of Backfill Material: Non-Impacted Soil and Bentonite Grout
Type of Screen: Schedule 40 PVC / Diameter: 2-inch	Type of Seal Material: Bentonite
Borehole Diameter: 3.75-inch	Type of Filter Material: No. 2 Sand

	Elevation	Depth
Top of Casing	12.65'	0.47' bgs
Top of Seal	9.12'	4' bgs
Top of Filter	7.12'	6' bgs
Top of Screen	5.12'	8' bgs
Bottom of Filter	-4.88'	18' bgs
Bottom of Well	-4.88'	18' bgs
Screen Length: 10.0'		Slot Size: 0.020-slot

GROUNDWATER ELEVATIONS (ft)
(Measured from the Top of Casing)

Elevation	DTW	Date



Soil / Rock Classification	Depth (ft)
FILL	0.47
	4
	6
	8
NATIVE	
	16
	18

\\LANGAN.COM\DATA\PAR\DATA8\100688801\PROJECT DATA_DISCIPLINE\ENVIRONMENTAL\GINTLOGS\100688801_PHASE 1B.GPJ ... 5/25/2023 4:05:16 PM ... Report: Log - LANGAN_WELL_CONSTRUCTION_SUMMARY

LANGAN

WELL CONSTRUCTION SUMMARY

Well No. LMW-25

Project: 12074 Flatlands Avenue	Project No.: 100688801
Location: Brooklyn, New York	Elevation And Datum: 14.32 NAVD88
Drilling Agency: AARCO Environmental Services Corp.	Date Started: 2/14/2023 / Date Finished: 2/14/2023
Drilling Equipment: Geoprobe 7822 DT	Driller: Julio Galarzia
Size And Type of Bit: 3.75-inch Direct Push	Inspector: Esther Arthur

Method of Installation

AARCO installed a 20-slot Schedule 40 PVC screen from 8 to 18 feet bgs and Schedule 40 PVC riser to the surface. The annulus of the borehole was backfilled to 6-feet bgs with No. 2 Sand and a hydrated bentonite seal from 6 to 8 feet bgs. A manhole was installed and encased in concrete at grade.

Method of Well Development

LMW-25 was developed with a whale pump using surge pumping techniques across the well screen in two- to three-foot increments. After surging, the well was purged via pumping until the water became clear; approximately 30 gallons purged.

Type of Casing: --- / Diameter: ---	Type of Backfill Material: Non-Impacted Soil and Bentonite Grout
Type of Screen: Schedule 40 PVC / Diameter: 2-inch	Type of Seal Material: Bentonite
Borehole Diameter: 3.75-inch	Type of Filter Material: No. 2 Sand

	Elevation	Depth
Top of Casing	13.99'	0.33' bgs
Top of Seal	10.32'	4' bgs
Top of Filter	8.32'	6' bgs
Top of Screen	6.32'	8' bgs
Bottom of Filter	-3.68'	18' bgs
Bottom of Well	-3.68'	18' bgs
Screen Length: 10.0'		Slot Size: 0.020-slot

GROUNDWATER ELEVATIONS (ft)
(Measured from the Top of Casing)

Elevation	DTW	Date



Soil / Rock Classification	Depth (ft)
FILL	0.33
	4
	6
	8
NATIVE	
	16
	18

\\LANGAN.COM\DATA\PAR\DATA8\100688801\PROJECT DATA_DISCIPLINE\ENVIRONMENTAL\GINTLOGS\100688801_PHASE 1B.GPJ ... 5/25/2023 4:05:17 PM ... Report: Log - LANGAN_WELL_CONSTRUCTION_SUMMARY

LANGAN

WELL CONSTRUCTION SUMMARY

Well No. LMW-16

Project: 12074 Flatlands Avenue	Project No.: 100688801
Location: Brooklyn, New York	Elevation And Datum: 14.34 NAVD88
Drilling Agency: AARCO Environmental Services Corp.	Date Started: 2/14/2023 / Date Finished: 2/14/2023
Drilling Equipment: Geoprobe 7822 DT	Driller: Julio Galarzia
Size And Type of Bit: 3.75-inch Direct Push	Inspector: Esther Arthur

Method of Installation

AARCO installed a 20-slot Schedule 40 PVC screen from 10 to 20 feet bgs and Schedule 40 PVC riser to the surface. The annulus of the borehole was backfilled to 8-feet bgs with No. 2 Sand and a hydrated bentonite seal from 6 to 8 feet bgs. A manhole was installed and encased in concrete at grade.

Method of Well Development

LMW-16 was developed with a whale pump using surge pumping techniques across the well screen in two- to three-foot increments. After surging, the well was purged via pumping until the water became clear; approximately 20 gallons purged.

Type of Casing: --- / Diameter: ---	Type of Backfill Material: Non-Impacted Soil and Bentonite Grout
Type of Screen: Schedule 40 PVC / Diameter: 2-inch	Type of Seal Material: Bentonite
Borehole Diameter: 3.75-inch	Type of Filter Material: No. 2 Sand

	Elevation	Depth
Top of Casing	14.19'	0.15' bgs
Top of Seal	8.34'	6' bgs
Top of Filter	6.34'	8' bgs
Top of Screen	4.34'	10' bgs
Bottom of Filter	-5.66'	20' bgs
Bottom of Well	-5.66'	20' bgs
Screen Length: 10.0'		Slot Size: 0.020-slot

GROUNDWATER ELEVATIONS (ft)
(Measured from the Top of Casing)

Elevation	DTW	Date



Soil / Rock Classification	Depth (ft)
FILL	0.15
	6
	8
	10
NATIVE	
	18
	20

\\LANGAN.COM\DATA\PAR\DATA8\100688801\PROJECT DATA_DISCIPLINE\ENVIRONMENTAL\GINTLOGS\100688801_PHASE 1B.GPJ ... 5/25/2023 4:05:18 PM ... Report: Log - LANGAN_WELL_CONSTRUCTION_SUMMARY

LANGAN

WELL CONSTRUCTION SUMMARY

Well No. LMW-24

Project: 12074 Flatlands Avenue	Project No.: 100688801
Location: Brooklyn, New York	Elevation And Datum: 18.38 NAVD88
Drilling Agency: AARCO Environmental Services Corp.	Date Started: 2/15/2023 / Date Finished: 2/15/2023
Drilling Equipment: Geoprobe 7822 DT	Driller: Julio Galarzia
Size And Type of Bit: 3.75-inch Direct Push	Inspector: Esther Arthur

Method of Installation

AARCO installed a 20-slot Schedule 40 PVC screen from 14 to 24 feet bgs and Schedule 40 PVC riser to the surface. The annulus of the borehole was backfilled to 12-feet bgs with No. 2 Sand and a hydrated bentonite seal from 10 to 12 feet bgs. A manhole was installed and encased in concrete at grade.

Method of Well Development

LMW-24 was developed with a whale pump using surge pumping techniques across the well screen in two- to three-foot increments. After surging, the well was purged via pumping until the water became clear; approximately 30 gallons purged.

Type of Casing: --- / Diameter: ---	Type of Backfill Material: Non-Impacted Soil and Bentonite Grout
Type of Screen: Schedule 40 PVC / Diameter: 2-inch	Type of Seal Material: Bentonite
Borehole Diameter: 3.75-inch	Type of Filter Material: No. 2 Sand

	Elevation	Depth
Top of Casing	18.10'	0.28' bgs
Top of Seal	8.38'	10' bgs
Top of Filter	6.38'	12' bgs
Top of Screen	4.38'	14' bgs
Bottom of Filter	-5.62'	24' bgs
Bottom of Well	-5.62'	24' bgs
Screen Length: 10.0'		Slot Size: 0.020-slot

GROUNDWATER ELEVATIONS (ft)
(Measured from the Top of Casing)

Elevation	DTW	Date



Soil / Rock Classification	Depth (ft)
FILL	0.28
	10
	12
	14
	21
	24

\\LANGAN.COM\DATA\PAR\DATA8\100688801\PROJECT DATA_DISCIPLINE\ENVIRONMENTAL\GINTLOGS\100688801_PHASE 1B.GPJ ... 5/25/2023 4:05:19 PM ... Report: Log - LANGAN_WELL_CONSTRUCTION_SUMMARY

LANGAN

WELL CONSTRUCTION SUMMARY

Well No. LMW-17

Project: 12074 Flatlands Avenue	Project No.: 100688801
Location: Brooklyn, New York	Elevation And Datum: 19.93 NAVD88
Drilling Agency: AARCO Environmental Services Corp.	Date Started: 2/16/2023 / Date Finished: 2/16/2023
Drilling Equipment: Geoprobe 7822 DT	Driller: Julio Galarzia
Size And Type of Bit: 3.75-inch Direct Push	Inspector: Esther Arthur

Method of Installation

AARCO installed a 20-slot Schedule 40 PVC screen from 15 to 25 feet bgs and Schedule 40 PVC riser to the surface. The annulus of the borehole was backfilled to 13-feet bgs with No. 2 Sand and a hydrated bentonite seal from 11 to 13 feet bgs. A manhole was installed and encased in concrete at grade.

Method of Well Development

LMW-17 was developed with a whale pump using surge pumping techniques across the well screen in two- to three-foot increments. After surging, the well was purged via pumping until the water became clear; approximately 25 gallons purged.

Type of Casing: --- / Diameter: ---	Type of Backfill Material: Non-Impacted Soil and Bentonite Grout
Type of Screen: Schedule 40 PVC / Diameter: 2-inch	Type of Seal Material: Bentonite
Borehole Diameter: 3.75-inch	Type of Filter Material: No. 2 Sand

	Elevation	Depth
Top of Casing	19.69'	0.24' bgs
Top of Seal	8.93'	11' bgs
Top of Filter	6.93'	13' bgs
Top of Screen	4.93'	15' bgs
Bottom of Filter	-5.07'	25' bgs
Bottom of Well	-5.07'	25' bgs
Screen Length: 10.0'		Slot Size: 0.020-slot

GROUNDWATER ELEVATIONS (ft)
(Measured from the Top of Casing)

Elevation	DTW	Date



Soil / Rock Classification	Depth (ft)
FILL	0.24
	11
	13
	15
	23
	25

\\LANGAN.COM\DATA\PAR\DATA8\100688801\PROJECT DATA_DISCIPLINE\ENVIRONMENTAL\GINTLOGS\100688801_PHASE 1B.GPJ ... 5/25/2023 4:05:20 PM ... Report: Log - LANGAN_WELL_CONSTRUCTION_SUMMARY

LANGAN

WELL CONSTRUCTION SUMMARY

Well No. LMW-18

Project: 12074 Flatlands Avenue	Project No.: 100688801
Location: Brooklyn, New York	Elevation And Datum: 21.00 NAVD88
Drilling Agency: AARCO Environmental Services Corp.	Date Started: 2/15/2023 / Date Finished: 2/15/2023
Drilling Equipment: Geoprobe 7822 DT	Driller: Julio Galarzia
Size And Type of Bit: 3.75-inch Direct Push	Inspector: Esther Arthur

Method of Installation

AARCO installed a 20-slot Schedule 40 PVC screen from 15 to 25 feet bgs and Schedule 40 PVC riser to the surface. The annulus of the borehole was backfilled to 13-feet bgs with No. 2 Sand and a hydrated bentonite seal from 11 to 13 feet bgs. A manhole was installed and encased in concrete at grade.

Method of Well Development

LMW-18 was developed with a whale pump using surge pumping techniques across the well screen in two- to three-foot increments. After surging, the well was purged via pumping until the water became clear; approximately 25 gallons purged.

Type of Casing: --- / Diameter: ---	Type of Backfill Material: Non-Impacted Soil and Bentonite Grout
Type of Screen: Schedule 40 PVC / Diameter: 2-inch	Type of Seal Material: Bentonite
Borehole Diameter: 3.75-inch	Type of Filter Material: No. 2 Sand

	Elevation	Depth
Top of Casing	20.56'	0.44' bgs
Top of Seal	10.00'	11' bgs
Top of Filter	8.00'	13' bgs
Top of Screen	6.00'	15' bgs
Bottom of Filter	-4.00'	25' bgs
Bottom of Well	-4.00'	25' bgs
Screen Length: 10.0'		Slot Size: 0.020-slot

GROUNDWATER ELEVATIONS (ft)
(Measured from the Top of Casing)

Elevation	DTW	Date



Soil / Rock Classification	Depth (ft)
FILL	0.44
	11
	13
	15
	23
	25

\\LANGAN.COM\DATA\PAR\DATA8\100688801\PROJECT DATA_DISCIPLINE\ENVIRONMENTAL\GINTLOGS\100688801_PHASE 1B.GPJ ... 5/25/2023 4:05:21 PM ... Report: Log - LANGAN_WELL_CONSTRUCTION_SUMMARY

LANGAN

WELL CONSTRUCTION SUMMARY

Well No. LMW-19

Project: 12074 Flatlands Avenue	Project No.: 100688801
Location: Brooklyn, New York	Elevation And Datum: 20.09 NAVD88
Drilling Agency: AARCO Environmental Services Corp.	Date Started: 2/15/2023 / Date Finished: 2/15/2023
Drilling Equipment: Geoprobe 7822 DT	Driller: Julio Galarzia
Size And Type of Bit: 3.75-inch Direct Push	Inspector: Esther Arthur

Method of Installation

AARCO installed a 20-slot Schedule 40 PVC screen from 14 to 24 feet bgs and Schedule 40 PVC riser to the surface. The annulus of the borehole was backfilled to 12-feet bgs with No. 2 Sand and a hydrated bentonite seal from 10 to 12 feet bgs. A manhole was installed and encased in concrete at grade.

Method of Well Development

LMW-19 was developed with a whale pump using surge pumping techniques across the well screen in two- to three-foot increments. After surging, the well was purged via pumping until the water became clear; approximately 20 gallons purged.

Type of Casing: --- / Diameter: ---	Type of Backfill Material: Non-Impacted Soil and Bentonite Grout
Type of Screen: Schedule 40 PVC / Diameter: 2-inch	Type of Seal Material: Bentonite
Borehole Diameter: 3.75-inch	Type of Filter Material: No. 2 Sand

	Elevation	Depth
Top of Casing	19.88'	0.21' bgs
Top of Seal	10.09'	10' bgs
Top of Filter	8.09'	12' bgs
Top of Screen	6.09'	14' bgs
Bottom of Filter	-3.91'	24' bgs
Bottom of Well	-3.91'	24' bgs
Screen Length: 10.0'		Slot Size: 0.020-slot

GROUNDWATER ELEVATIONS (ft)
(Measured from the Top of Casing)

Elevation	DTW	Date



Soil / Rock Classification	Depth (ft)
FILL	0.21
	10
	12
	14
	21
	24

\\LANGAN.COM\DATA\PAR\DATA8\100688801\PROJECT DATA_DISCIPLINE\ENVIRONMENTAL\GINTLOGS\100688801_PHASE 1B.GPJ ... 5/25/2023 4:05:22 PM ... Report: Log - LANGAN_WELL_CONSTRUCTION_SUMMARY

LANGAN

WELL CONSTRUCTION SUMMARY

Well No. LMW-20

Project: 12074 Flatlands Avenue	Project No.: 100688801
Location: Brooklyn, New York	Elevation And Datum: 21.86 NAVD88
Drilling Agency: AARCO Environmental Services Corp.	Date Started: 2/16/2023 / Date Finished: 2/16/2023
Drilling Equipment: Geoprobe 7822 DT	Driller: Julio Galarzia
Size And Type of Bit: 3.75-inch Direct Push	Inspector: Esther Arthur

Method of Installation

AARCO installed a 20-slot Schedule 40 PVC screen from 16 to 26 feet bgs and Schedule 40 PVC riser to the surface. The annulus of the borehole was backfilled to 14-feet bgs with No. 2 Sand and a hydrated bentonite seal from 12 to 14 feet bgs. A manhole was installed and encased in concrete at grade.

Method of Well Development

LMW-20 was developed with a whale pump using surge pumping techniques across the well screen in two- to three-foot increments. After surging, the well was purged via pumping until the water became clear; approximately 30 gallons purged.

Type of Casing: --- / Diameter: ---	Type of Backfill Material: Non-Impacted Soil and Bentonite Grout
Type of Screen: Schedule 40 PVC / Diameter: 2-inch	Type of Seal Material: Bentonite
Borehole Diameter: 3.75-inch	Type of Filter Material: No. 2 Sand

	Elevation	Depth
Top of Casing	21.36'	0.5' bgs
Top of Seal	9.86'	12' bgs
Top of Filter	7.86'	14' bgs
Top of Screen	5.86'	16' bgs
Bottom of Filter	-4.14'	26' bgs
Bottom of Well	-4.14'	26' bgs
Screen Length: 10.0'		Slot Size: 0.020-slot

GROUNDWATER ELEVATIONS (ft)
(Measured from the Top of Casing)

Elevation	DTW	Date



Soil / Rock Classification	Depth (ft)
FILL	0.5
	12
	14
	16
	24
	26

\\LANGAN.COM\DATA\PAR\DATA8\100688801\PROJECT DATA_DISCIPLINE\ENVIRONMENTAL\GINTLOGS\100688801_PHASE 1B.GPJ ... 5/25/2023 4:05:23 PM ... Report: Log - LANGAN_WELL_CONSTRUCTION_SUMMARY

LANGAN

WELL CONSTRUCTION SUMMARY

Well No. LMW-21

Project: 12074 Flatlands Avenue	Project No.: 100688801
Location: Brooklyn, New York	Elevation And Datum: 22.15 NAVD88
Drilling Agency: AARCO Environmental Services Corp.	Date Started: 2/17/2023 / Date Finished: 2/17/2023
Drilling Equipment: Geoprobe 6610 DT	Driller: Sergio Magana
Size And Type of Bit: 3.75-inch Direct Push	Inspector: Esther Arthur

Method of Installation

AARCO installed a 20-slot Schedule 40 PVC screen from 16 to 26 feet bgs and Schedule 40 PVC riser to the surface. The annulus of the borehole was backfilled to 14-feet bgs with No. 2 Sand and a hydrated bentonite seal from 12 to 14 feet bgs. A manhole was installed and encased in concrete at grade.

Method of Well Development

LMW-21 was developed with a whale pump using surge pumping techniques across the well screen in two- to three-foot increments. After surging, the well was purged via pumping until the water became clear; approximately 25 gallons purged.

Type of Casing: --- / Diameter: ---	Type of Backfill Material: Non-Impacted Soil and Bentonite Grout
Type of Screen: Schedule 40 PVC / Diameter: 2-inch	Type of Seal Material: Bentonite
Borehole Diameter: 3.75-inch	Type of Filter Material: No. 2 Sand

	Elevation	Depth
Top of Casing	21.91'	0.24' bgs
Top of Seal	10.15'	12' bgs
Top of Filter	8.15'	14' bgs
Top of Screen	6.15'	16' bgs
Bottom of Filter	-3.85'	26' bgs
Bottom of Well	-3.85'	26' bgs
Screen Length: 10.0'		Slot Size: 0.020-slot

GROUNDWATER ELEVATIONS (ft)
(Measured from the Top of Casing)

Elevation	DTW	Date



Well Details	Soil / Rock Classification	Depth (ft)
	FILL	0.24
		12
		14
		16
		24
		26

\\LANGAN.COM\DATA\PAR\DATA8\100688801\PROJECT DATA_DISCIPLINE\ENVIRONMENTAL\GINTLOGS\100688801_PHASE 1B.GPJ ... 5/25/2023 4:05:24 PM ... Report: Log - LANGAN_WELL_CONSTRUCTION_SUMMARY

LANGAN

WELL CONSTRUCTION SUMMARY

Well No. LMW-22

Project: 12074 Flatlands Avenue	Project No.: 100688801
Location: Brooklyn, New York	Elevation And Datum: 22.21 NAVD88
Drilling Agency: AARCO Environmental Services Corp.	Date Started: 2/17/2023 / Date Finished: 2/17/2023
Drilling Equipment: Geoprobe 6610 DT	Driller: Sergio Magana
Size And Type of Bit: 3.75-inch Direct Push	Inspector: Esther Arthur

Method of Installation

AARCO installed a 20-slot Schedule 40 PVC screen from 15 to 25 feet bgs and Schedule 40 PVC riser to the surface. The annulus of the borehole was backfilled to 13-feet bgs with No. 2 Sand and a hydrated bentonite seal from 11 to 13 feet bgs. A manhole was installed and encased in concrete at grade.

Method of Well Development

LMW-22 was developed with a whale pump using surge pumping techniques across the well screen in two- to three-foot increments. After surging, the well was purged via pumping until the water became clear; approximately 30 gallons purged.

Type of Casing: --- / Diameter: ---	Type of Backfill Material: Non-Impacted Soil and Bentonite Grout
Type of Screen: Schedule 40 PVC / Diameter: 2-inch	Type of Seal Material: Bentonite
Borehole Diameter: 3.75-inch	Type of Filter Material: No. 2 Sand

	Elevation	Depth
Top of Casing	22.02'	0.19' bgs
Top of Seal	11.21'	11' bgs
Top of Filter	9.21'	13' bgs
Top of Screen	7.21'	15' bgs
Bottom of Filter	-2.79'	25' bgs
Bottom of Well	-2.79'	25' bgs
Screen Length: 10.0'		Slot Size: 0.020-slot

GROUNDWATER ELEVATIONS (ft)
(Measured from the Top of Casing)

Elevation	DTW	Date



Soil / Rock Classification	Depth (ft)
FILL	0.19
	11
	13
	15
	23
	25

\\LANGAN.COM\DATA\PAR\DATA8\100688801\PROJECT DATA_DISCIPLINE\ENVIRONMENTAL\GINTLOGS\100688801_PHASE 1B.GPJ ... 5/25/2023 4:05:25 PM ... Report: Log - LANGAN_WELL_CONSTRUCTION_SUMMARY

LANGAN

WELL CONSTRUCTION SUMMARY

Well No. LMW-23

Project: 12074 Flatlands Avenue	Project No.: 100688801
Location: Brooklyn, New York	Elevation And Datum: 22.09 NAVD88
Drilling Agency: AARCO Environmental Services Corp.	Date Started: 2/17/2023 / Date Finished: 2/17/2023
Drilling Equipment: Geoprobe 6610 DT	Driller: Sergio Magana
Size And Type of Bit: 3.75-inch Direct Push	Inspector: Esther Arthur

Method of Installation

AARCO installed a 20-slot Schedule 40 PVC screen from 16 to 26 feet bgs and Schedule 40 PVC riser to the surface. The annulus of the borehole was backfilled to 14-feet bgs with No. 2 Sand and a hydrated bentonite seal from 12 to 14 feet bgs. A manhole was installed and encased in concrete at grade.

Method of Well Development

LMW-23 was developed with a whale pump using surge pumping techniques across the well screen in two- to three-foot increments. After surging, the well was purged via pumping until the water became clear; approximately 25 gallons purged.

Type of Casing: --- / Diameter: ---	Type of Backfill Material: Non-Impacted Soil and Bentonite Grout
Type of Screen: Schedule 40 PVC / Diameter: 2-inch	Type of Seal Material: Bentonite
Borehole Diameter: 3.75-inch	Type of Filter Material: No. 2 Sand

	Elevation	Depth
Top of Casing	21.71'	0.38' bgs
Top of Seal	10.09'	12' bgs
Top of Filter	8.09'	14' bgs
Top of Screen	6.09'	16' bgs
Bottom of Filter	-3.91'	26' bgs
Bottom of Well	-3.91'	26' bgs
Screen Length: 10.0'		Slot Size: 0.020-slot

GROUNDWATER ELEVATIONS (ft)
(Measured from the Top of Casing)

Elevation	DTW	Date



Well Details	Soil / Rock Classification	Depth (ft)
	FILL	0.38
		12
		14
		16
		24
		26

\\LANGAN.COM\DATA\PAR\DATA8\100688801\PROJECT DATA_DISCIPLINE\ENVIRONMENTAL\GINTLOGS\100688801_PHASE 1B.GPJ ... 5/25/2023 4:05:25 PM ... Report: Log - LANGAN_WELL_CONSTRUCTION_SUMMARY

APPENDIX D

Excavation Work Plan

EXCAVATION WORK PLAN (EWP)

1 NOTIFICATION

At least 15 days prior to the start of any activity that is anticipated to encounter remaining contamination or breach or alter the site's cover system, the site owner or their representative will notify the NYSDEC contacts listed in the table below. Table 1, below, includes contact information for the above notification. The information on this table will be updated as necessary to provide accurate contact information. A full listing of site-related contact information is provided in Appendix B of the SMP.

Table 1: Notifications*

NYSDEC Section Chief	Lisa Gorton Telephone: (518) 402-9574 Email: Lisa.Gorton@dec.ny.gov
NYSDOH Project Manager	Jim Sullivan Telephone: (518) 402-5584 Email: beei@health.ny.gov
NYSDEC Project Manager	Rafi Alam Telephone: (518) 402-8606 E-mail: Rafi.Alam@dec.ny.gov
Project Manager	Amanda Forsburg Telephone: (973) 560-4900 Email: aforsburg@langan.com
Qualified Environmental Professional	Amanda Forsburg, CHMM Telephone: (973) 560-4900 Email: aforsburg@langan.com
Remedial Engineer	Ronald Boyer, P.E. Telephone: (973) 560-4900 E-mail: rboyer@langan.com
Owner Representative	Innovative Urban Living, LLC, IUV Phase 1B Owner, LLC, IUV Phase 1B LIHTC Owner, LLC Simeon Maleh Telephone: (212) 716-2536 E-mail: smaleh@gothamorg.com

* Note: Notifications are subject to change and will be updated as necessary.

This notification will include:

- A detailed description of the work to be performed, including the location and areal extent of excavation, plans/drawings for site re-grading, intrusive elements or utilities to be installed below the soil cover, estimated volumes of contaminated soil to be excavated, any modifications of truck routes, and any work that may impact an engineering control;

- A summary of environmental conditions anticipated to be encountered in the work areas, including the nature and concentration levels of contaminants of concern, potential presence of grossly contaminated media, and plans for any pre-construction sampling;

- A schedule for the work, detailing the start and completion of all intrusive work, and submittals (e.g., reports) to the NYSDEC documenting the completed intrusive work;

- A summary of the applicable components of this EWP;

- A statement that the work will be performed in compliance with this EWP, 29 CFR 1910.120 and 29 CFR 1926 Subpart P;

- A copy of the contractor's health and safety plan (HASP), in electronic format, if it differs from the HASP provided in Appendix G of this SMP;

- Identification of disposal facilities for potential waste streams; and,

- Identification of sources of any anticipated backfill, along with the required request to import form and all supporting documentation including, but not limited to, chemical testing results.

The NYSDEC project manager will review the notification and may impose additional requirements for the excavation that are not listed in this EWP. The alteration, restoration and modification of engineering controls must conform with Article 145 Section 7209 of the Education Law regarding the application professional seals and alterations.

2 SOIL SCREENING METHODS

Visual, olfactory and instrument-based (e.g., photoionization detector) soil screening will be performed during all excavations into known or potentially contaminated material (remaining contamination) or a breach of the cover system. A qualified environmental professional as defined in 6 NYCRR Part 375, a PE who is licensed and registered in New York State, or a qualified person who directly reports to a PE who is licensed and registered in New York State or a QEP will perform the screening. Soil screening will be performed when invasive work is done and will

include all excavation and invasive work performed during development, such as excavations for foundations and utility work, after issuance of the COC.

Soils will be segregated based on previous environmental data and screening results into material that requires off-site disposal and material that requires testing to determine if the material can be reused on-site as soil beneath a cover or if the material can be used as cover soil. Further discussion of off-site disposal of materials and on-site reuse is provided in Sections 6 and 7 of this Appendix.

3 SOIL STAGING METHODS

Soil stockpiles will be continuously encircled with a berm and/or silt fence. Hay bales will be used as needed near catch basins, surface waters and other discharge points.

Stockpiles will be placed on and kept covered at all times with appropriately anchored tarps. Stockpiles will be routinely inspected and damaged tarp covers will be promptly replaced.

Stockpiles will be inspected at a minimum once each week and after every storm event. Results of inspections will be recorded in a logbook and maintained at the site and available for inspection by the NYSDEC.

4 MATERIALS EXCAVATION AND LOAD-OUT

A qualified environmental professional as defined in 6 NYCRR Part 375, a PE who is licensed and registered in New York State, or a qualified person who directly reports to a PE who is licensed and registered in New York State or a QEP will oversee all invasive work and the excavation and load-out of all excavated material.

The owner of the property and remedial party (if applicable) and its contractors are responsible for safe execution of all invasive and other work performed under this Plan.

The presence of utilities and easements on the site will be investigated by the qualified environmental professional and/or contractor. It will be determined whether a risk or impediment to the planned work under this SMP is posed by utilities or easements on the site. A site utility stakeout will be completed for all utilities prior to any ground intrusive activities at the site.

Loaded vehicles leaving the site will be appropriately lined, tarped, securely covered, manifested, and placarded in accordance with appropriate Federal, State, local, and NYSDOT requirements (and all other applicable transportation requirements). Trucks transporting contaminated soil must

have either tight-fitting opaque covers that are secured on the sides and/or back, or opaque covers that are locked on all sides.

A truck wash will be operated on-site, as appropriate. The qualified environmental professional will be responsible for ensuring that all outbound trucks will be washed at the truck wash before leaving the site until the activities performed under this section are complete. Truck wash waters will be collected and disposed of off-site in an appropriate manner.

Locations where vehicles enter or exit the site shall be inspected daily for evidence of off-site soil tracking.

The qualified environmental professional or field staff under their supervision will be responsible for ensuring that all egress points for truck and equipment transport from the site are clean of dirt and other materials derived from the site during intrusive excavation activities. Cleaning of the adjacent streets will be performed as needed to maintain a clean condition with respect to site-derived materials. Material accumulated from the street cleaning and egress cleaning activities will be disposed off-site at a permitted landfill facility in accordance with all applicable local, State, and Federal regulations.

5 MATERIALS TRANSPORT OFF-SITE

All transport of materials will be performed by licensed haulers in accordance with appropriate local, State, and Federal regulations, including 6 NYCRR Part 364. Haulers will be appropriately licensed and trucks properly placarded.

Material transported by trucks exiting the site will be secured with either tight-fitting opaque covers that are secured on the sides and/or back, or opaque covers that are locked on all sides. Loose-fitting canvas-type truck covers will be prohibited. If loads contain wet material capable of producing free liquid, truck liners will be used.

Truck transport routes are shown on Figure 8 of the SMP. All trucks loaded with site materials will exit the vicinity of the site using only these approved truck routes. This is the most appropriate route and takes into account: (a) limiting transport through residential areas and past sensitive sites; (b) use of city mapped truck routes; (c) prohibiting off-site queuing of trucks entering the facility; (d) limiting total distance to major highways; (e) promoting safety in access to highways; and (f) overall safety in transport.
Trucks will be prohibited from stopping and idling in the neighborhood outside the project site.

Egress points for truck and equipment transport from the site will be kept clean of dirt and other materials during site remediation and development.

Queuing of trucks will be performed on-site in order to minimize off-site disturbance. Off-site queuing will be prohibited.

6 MATERIALS DISPOSAL OFF-SITE

All material excavated and removed from the site will be treated as contaminated and regulated material and will be transported and disposed off-site to a permitted facility in accordance with all local, State and Federal regulations. If disposal of material from this site is proposed for unregulated off-site disposal (i.e. clean soil removed for development purposes), a formal request with an associated plan will be made to the NYSDEC project manager. Unregulated off-site management of materials from this site will not occur without formal NYSDEC project manager approval.

The following documentation will be obtained and reported by the QEP for each off-site disposal location used to fully demonstrate and document that the disposal of material derived from the site conforms to applicable laws:

1) A letter from the QEP or BCP Volunteer to the receiving facility describing the material to be disposed and requesting formal written acceptance of the material. This letter will state that material to be disposed is contaminated material generated at an environmental remediation site in New York State. The letter will provide the project identity and the name and phone number of the QEP. The letter will include as an attachment a summary of chemical data for the material being transported (including site characterization data); and

2) A letter from each receiving facility stating it is in receipt of the correspondence (above) and is approved to accept the material.

Off-site disposal locations for excavated soils will be identified in the pre-excavation notification. This will include estimated quantities and a breakdown by class of disposal facility if appropriate, (e.g., hazardous waste disposal facility, solid waste landfill, petroleum treatment facility, C&D debris recovery facility). Actual disposal quantities and associated documentation will be reported to the NYSDEC in the Periodic Review Report. This documentation will include, but will not be limited to: waste profiles, test results, facility acceptance letters, manifests, bills of lading and facility receipts.

Non-hazardous historic fill and contaminated soils taken off-site will be handled consistent with 6 NYCRR Parts 360, 361, 362, 363, 364 and 365. Material that does not meet Unrestricted SCOs is prohibited from being taken to a New York State C&D debris recovery facility (6 NYCRR Subpart 360-15 registered or permitted facility).

7 MATERIALS REUSE ON-SITE

The qualified environmental professional, as defined in 6 NYCRR Part 375, will ensure that procedures defined for materials reuse in this SMP are followed and that unacceptable material (i.e., contaminated) does not remain on-site. Contaminated on-site material, including historic fill and contaminated soil, that is acceptable for reuse on-site will be placed below the demarcation layer or impervious surface, and will not be reused within the cover system or within landscaping berms. Contaminated on-site material may only be used beneath the site cover as backfill for subsurface utility lines with prior approval from the DEC project manager.

Proposed materials for reuse on-site must be sampled for full suite analytical parameters including per- and polyfluoroalkyl substances (PFAS) and 1,4-dioxane. The sampling frequency will be in accordance with DER-10 Table 5.4(e)10 unless prior approval is obtained from the NYSDEC project manager for modification of the sampling frequency. The analytical results of soil/fill material testing must meet the site use criteria presented in NYSDEC DER-10 Appendix 5 – Allowable Constituent Levels for Imported Fill or Soil for all constituents listed, and the NYSDEC Sampling, Analysis, and Assessment of Per- and Polyfluoroalkyl Substances (dated April 2023) guidance values. Approvals for modifications to the analytical parameters must be obtained from the NYSDEC project manager prior to the sampling event.

Soil/fill material for reuse on-site will be segregated and staged as described in Sections 2 and 3 of this EWP. The anticipated size and location of stockpiles will be provided in the 15-day notification to the NYSDEC project manager. Stockpile locations will be based on the location of site excavation activities and proximity to nearby site features. Material reuse on-site will comply with requirements of NYSDEC DER-10 Section 5.4(e)4. Any modifications to the requirements of DER-10 Section 5.4(e)4 must be approved by the NYSDEC project manager.

Any demolition material proposed for reuse on-site will be sampled for asbestos and the results will be reported to the NYSDEC for acceptance. Concrete crushing or processing on-site will not be performed without prior NYSDEC approval. Organic matter (wood, roots, stumps, etc.) or other solid waste derived from clearing and grubbing of the site will not be reused on-site.

8 FLUIDS MANAGEMENT

All liquids to be removed from the site, including but not limited to, excavation dewatering, decontamination waters, and groundwater monitoring well purge and development waters, will be handled, transported and disposed off-site at a permitted facility in accordance with applicable local, State, and Federal regulations. Dewatering, purge, and development fluids will not be recharged back to the land surface or subsurface of the site, and will be managed off-site, unless prior approval is obtained from NYSDEC.

Discharge of water generated during large-scale construction activities to surface waters (i.e., a local pond, stream or river) will be performed under a SPDES permit.

9 BACKFILL FROM OFF-SITE SOURCES

All materials proposed for import onto the site will be approved by the qualified environmental professional, as defined in 6 NYCRR Part 375, and will be in compliance with provisions in this SMP prior to receipt at the site. A Request to Import/Reuse Fill or Soil form, which can be found at http://www.dec.ny.gov/regulations/67386.html, will be prepared and submitted to the NYSDEC project manager allowing a minimum of 5 business days for review.

Material from industrial sites, spill sites, other environmental remediation sites, or potentially contaminated sites will not be imported to the site.

All imported soils will meet the backfill and cover soil quality standards established in 6 NYCRR 375-6.7(d) and DER-10 Appendix 5 for Restricted-Residential Use. Based on an evaluation of the land use, protection of groundwater and protection of ecological resources criteria, the resulting soil quality standards are listed in Table 1 in the SMP. Soils that meet 'general' fill requirements under 6 NYCRR Part 360.13, but do not meet backfill or cover soil objectives for this site, will not be imported onto the site without prior approval by NYSDEC project manager. Soil material will be sampled for the full suite of analytical parameters, including PFAS and 1,4-dioxane. Solid waste will not be imported onto the site.

Trucks entering the site with imported soils will be securely covered with tight fitting covers. Imported soils will be stockpiled separately from excavated materials and covered to prevent dust releases.

10 STORMWATER POLLUTION PREVENTION

Barriers and hay bale checks will be installed and inspected once a week and after every storm event. Results of inspections will be recorded in a logbook and maintained at the site and available for inspection by the NYSDEC. All necessary repairs shall be made immediately.

Accumulated sediments will be removed as required to keep the barrier and hay bale check functional.

All undercutting or erosion of the silt fence toe anchor shall be repaired immediately with appropriate backfill materials.

Manufacturer's recommendations will be followed for replacing silt fencing damaged due to weathering.

Erosion and sediment control measures identified in the SMP shall be observed to ensure that they are operating correctly. Where discharge locations or points are accessible, they shall be inspected to ascertain whether erosion control measures are effective in preventing significant impacts to receiving waters.

Silt fencing or hay bales will be installed around the entire perimeter of the construction area.

11 EXCAVATION CONTINGENCY PLAN

If underground tanks or other previously unidentified contaminant sources are found during post-remedial subsurface excavations or development related construction, excavation activities will be suspended until sufficient equipment is mobilized to address the condition. The NYSDEC project manager will be promptly notified of the discovery.

Sampling will be performed on product, sediment and surrounding soils, etc. as necessary to determine the nature of the material and proper disposal method. Chemical analysis will be performed for a full list of analytes [TAL metals, TCL volatiles and semi-volatiles (including 1,4-dioxane), TCL pesticides and PCBs, and PFAS], unless the site history and previous sampling results provide sufficient justification to limit the list of analytes. In this case, a reduced list of analytes will be proposed to the NYSDEC project manager for approval prior to sampling. Any tanks will be closed as per NYSDEC regulations and guidance.

Identification of unknown or unexpected contaminated media identified by screening during invasive site work will be promptly communicated by phone within two hours to NYSDEC's Project Manager. Reportable quantities of petroleum product will also be reported to the NYSDEC spills hotline. These findings will be also included in the Periodic Review Report.

12 COMMUNITY AIR MONITORING PLAN

Community air monitoring will be conducted in compliance with the NYSDOH Generic CAMP outlined below and as provided in Appendix H of the SMP.

The CAMP will include real-time monitoring for VOCs and particulates at the upwind and downwind perimeter of each designated work area when ground-intrusive work is in progress. Continuous monitoring will be required for all ground-intrusive work. Ground-intrusive work includes, but is not limited to, soil/fill excavation and handling and utility trenching. Periodic monitoring for VOCs may be required during non-intrusive work such as the collection of soil samples. "Periodic" monitoring during sample collection might reasonably consist of taking a reading upon arrival at a sample location and taking a reading prior to leaving a sample location.

CAMP monitoring of total VOC levels will be conducted using PIDs, and monitoring for particulates will be conducted using particulate sensors equipped with filters that can detect airborne particulates less than 10 microns in diameter (PM10). Monitoring for particulates and odors will be conducted during ground-intrusive work by a field engineer, scientist, or geologist under the supervision of the RE. The work zone is defined as the general area in which machinery is operating in support of remediation. A portable PID will be used to monitor the work zone and for periodic monitoring of total VOC levels during work such as soil sampling. The Site perimeter will be visually monitored for fugitive dust emissions.

The following actions will be taken based on total VOC levels measured:

- If total VOC levels exceed 5 ppm above background for the 15-minute average at the perimeter, work will be temporarily halted and monitoring continued. If levels readily decrease (per instantaneous readings) below 5 ppm above background, work will resume with continued monitoring.
- If total VOC levels at the downwind perimeter of the work zone persist at levels in excess of 5 ppm above background but less than 25 ppm, work will be halted, the source of vapors identified, corrective actions taken to abate emissions, and monitoring continued. After these steps, work will resume provided that the total VOC level 200 feet downwind of the hot zone or half the distance to the nearest potential receptor or residential/ commercial structure, whichever is less – but in no case less than 20 feet, is below 5 ppm above background for the 15-minute average.

- If the total VOC level is above 25 ppm at the perimeter of the hot zone, work will be shut down.

The following actions will be taken based on dust levels measured or visual dust observations:

- If the downwind particulate level is 100 µg/m³ greater than background (upwind perimeter) for the 15-minute period or if airborne dust is observed leaving the work area, then dust suppression must be employed. Work may continue with dust suppression techniques provided that downwind PM10 levels do not exceed 150 µg/m³ above the background level and provided that no visible dust is migrating from the work area.
- If, after implementation of dust suppression techniques, downwind PM10 levels are greater than 150 µg/m³ above the background level, work must be stopped and a re-evaluation of activities initiated. Work can resume provided that dust suppression measures and other controls are successful in reducing the downwind PM10 concentration to within 150 µg/m³ of the upwind level and in preventing visible dust migration.

Exceedances of action levels listed in the CAMP will be reported to NYSDEC and NYSDOH Project Managers and included in the daily report.

12A SPECIAL REQUIREMENTS FOR WORK WITHIN 20 FEET OF POTENTIALLY EXPOSED INDIVIDUALS OR STRUCTURES

When work areas are within 20 feet of potentially exposed populations or occupied structures, the continuous monitoring locations for VOCs and particulates must reflect the nearest potentially exposed individuals and the location of ventilation system intakes for nearby structures. The use of engineering controls such as vapor/dust barriers, temporary negative-pressure enclosures, or special ventilation devices should be considered to prevent exposures related to the work activities and to control dust and odors. Consideration should be given to implementing the planned activities when potentially exposed populations are at a minimum, such as during weekends or evening hours in non-residential settings.

- If total VOC concentrations opposite the walls of occupied structures or next to intake vents exceed 1 part-per-million, monitoring should occur within the occupied structure(s). Depending upon the nature of contamination, chemical-specific colorimetric tubes of sufficient sensitivity may be necessary for comparing the exposure point concentrations with appropriate pre-determined response levels (response actions should also be pre-determined). Background readings in the occupied spaces must be taken prior to commencement of the planned work. Any unusual background readings should be discussed with NYSDOH prior to commencement of the work.

- If total particulate concentrations opposite the walls of occupied structures or next to intake vents exceed 150 micrograms per cubic meter, work activities should be suspended until controls are implemented and are successful in reducing the total particulate concentration to 150 micrograms per cubic meter or less at the monitoring point.
- Depending upon the nature of contamination and remedial activities, other parameters (e.g., explosivity, oxygen, hydrogen sulfide, carbon monoxide) may also need to be monitored. Response levels and actions should be pre-determined, as necessary, for each site.

12B SPECIAL REQUIREMENTS FOR INDOOR WORK WITH CO-LOCATED RESIDENCES OR FACILITIES

Unless a self-contained, negative-pressure enclosure with proper emission controls will encompass the work area, all individuals not directly involved with the planned work must be absent from the room in which the work will occur. Monitoring requirements shall be as stated above under "Special Requirements for Work Within 20 Feet of Potentially Exposed Individuals or Structures" except that in this instance "nearby/occupied structures" would be adjacent occupied rooms. Additionally, the location of all exhaust vents in the room and their discharge points, as well as potential vapor pathways (openings, conduits, etc.) relative to adjoining rooms, should be understood and the monitoring locations established accordingly. In these situations, it is strongly recommended that exhaust fans or other engineering controls be used to create negative air pressure within the work area during remedial activities. Additionally, it is strongly recommended that the planned work be implemented during hours (e.g. weekends or evenings) when building occupancy is at a minimum.

13 ODOR CONTROL PLAN

This odor control plan is capable of controlling emissions of nuisance odors off-site and on-site, if there are residents or tenants on the property. Specific odor control methods to be used on a routine basis may include the application of foam suppressants or tarps over the odorous material or VOC source areas. If nuisance odors are identified at the site boundary, or if odor complaints are received, work will be halted and the source of odors will be identified and corrected. Work will not resume until all nuisance odors have been abated. NYSDEC and NYSDOH will be notified of all odor events and of any other complaints about the project. Implementation of all odor controls, including the halt of work, is the responsibility of the remedial party's Remediation Engineer, and any measures that are implemented will be discussed in the Periodic Review Report.

All necessary means will be employed to prevent on- and off-site nuisances. At a minimum, these measures will include: (a) limiting the area of open excavations and size of soil stockpiles; (b) shrouding open excavations with tarps and other covers; and (c) using foams to cover exposed odorous soils. If odors develop and cannot be otherwise controlled, additional means to eliminate odor nuisances will include: (d) direct load-out of soils to trucks for off-site disposal; (e) use of chemical odorants in spray or misting systems; and, (f) use of staff to monitor odors in surrounding neighborhoods.

If nuisance odors develop during intrusive work that cannot be corrected, or where the control of nuisance odors cannot otherwise be achieved due to on-site conditions or close proximity to sensitive receptors, odor control will be achieved by sheltering the excavation and handling areas in a temporary containment structure equipped with appropriate air venting/filtering systems.

14 DUST CONTROL PLAN

Particulate monitoring must be conducted according to the Community Air Monitoring Plan (CAMP) provided in Section 13. If particulate levels at the site exceed the thresholds listed in the CAMP or if airborne dust is observed on the site or leaving the site, the dust suppression techniques listed below will be employed. The remedial party will also take measures listed below to prevent dust production on the site.

A dust suppression plan that addresses dust management during invasive on-site work will include, at a minimum, the items listed below:

- Dust suppression will be achieved using a dedicated on-site water truck for road wetting. The truck will be equipped with a water cannon capable of spraying water directly onto off-road areas including excavations and stockpiles.
- Gravel will be used on roadways to provide a clean and dust-free road surface.
- On-site roads will be limited in total area to minimize the area required for water truck sprinkling.

15 OTHER NUISANCES

A plan for rodent control will be developed and utilized by the contractor prior to and during site clearing and site grubbing, and during all remedial work.

A plan will be developed and utilized by the contractor for all remedial work to ensure compliance with local noise control ordinances.

APPENDIX E

Quality Assurance Project Plan

LANGAN

QUALITY ASSURANCE PROJECT PLAN

for

12074 FLATLANDS AVENUE P/O LOT 1 SITE
BROOKLYN, NEW YORK
NYSDEC BCP No. C224353

Prepared For:

Innovative Urban Living, LLC
IUV Phase 1B Owner, LLC
IUV Phase 1B LIHTC Owner, LLC
c/o Gotham Organization, LLC
111 Fifth Avenue, 9th Floor
New York, New York 10016

Prepared By:

Langan Engineering, Environmental, Surveying,
Landscape Architecture and Geology, D.P.C.
300 Kimball Drive
Parsippany, New Jersey 07054

July 2025
100688803

LANGAN

TABLE OF CONTENTS

1.0 PROJECT DESCRIPTION....1

1.1 Introduction....1

1.2 Project Objectives....1

1.3 Scope of Work....1

2.0 DATA QUALITY OBJECTIVES AND PROCESS....1

3.0 PROJECT ORGANIZATION AND RESPONSIBILITY....3

4.0 QUALITY ASSURANCE OBJECTIVES FOR COLLECTION OF DATA....4

5.0 SAMPLE COLLECTION AND FIELD DATA ACQUISITION PROCEDURES....7

5.1 Field Documentation Procedures....7

5.1.1 Field Data and Notes....7

5.1.2 Sample Labeling....9

5.2 Equipment Calibration and Preventative Maintenance....9

5.3 Sample Collection....10

5.3.1 Soil Samples....10

5.3.2 Groundwater Samples....12

5.3.3 Soil Vapor / Indoor Air Samples....13

5.3.4 PFAS Sampling Procedures....14

5.4 Sample Containers and Handling....16

5.5 Sample Preservation....17

5.6 Sample Shipment....17

5.6.1 Packaging....17

5.6.2 Shipping....18

5.7 Decontamination Procedures....18

5.8 Residuals Management....19

5.9 Chain of Custody Procedures....19

5.10 Laboratory Sample Storage Procedures....20

LANGAN

TABLE OF CONTENTS

6.0 DATA REDUCTION, VALIDATION, AND REPORTING 21

6.1 Introduction 21

6.2 Data Reduction 21

6.3 Data Validation 22

7.0 QUALITY ASSURANCE PERFORMANCE AUDITS AND SYSTEM AUDITS 23

7.1 Introduction 23

7.2 System Audits 24

7.3 Performance Audits 24

7.4 Formal Audits 24

8.0 CORRECTIVE ACTION 25

8.1 Introduction 25

8.2 Procedure Description 25

9.0 REFERENCES 28

LIST OF FIGURES

Figure 1 **Site Location Map**

Figure 2 **Proposed Post-Construction Monitoring Well Location Plan**

LIST OF ATTACHMENTS

Attachment A **Resumes**

Attachment B **Laboratory Reporting Limits and Method Detection Limits**

Attachment C **Analytical Methods / Quality Assurance Summary Table**

Attachment D **Sample Nomenclature**

Attachment E **Laboratory Standard Operating Procedures for PFAS Analysis**

Attachment F **ELAP Certification (York Analytical Laboratories, Inc.)**

1.0 PROJECT DESCRIPTION

1.1 Introduction

Langan Engineering, Environmental, Surveying, Landscape Architecture and Geology, D.P.C. (Langan) has prepared this Quality Assurance Project Plan (QAPP) on behalf of Innovative Urban Living, LLC, IUV Phase 1B Owner, LLC, and IUV Phase 1B LIHTC Owner, LLC c/o Gotham Organization, LLC (the Volunteer) for the property at 35 Inspiration Lane (Formerly Known As [F/K/A] 12074 Flatlands Avenue) (Tax Block 4434, Lot 1) in Brooklyn, New York (the Site). A Site Location Map is included as Figure 1.

This QAPP specifies analytical methods to be used to ensure that data collected during the Site Management Plan (SMP) are precise, accurate, representative, comparable, complete, and meet the sensitivity requirements of the project.

1.2 Project Objectives

The SMP involves biannual groundwater monitoring for volatile organic compounds (VOCs) and naphthalene. This QAPP addresses sampling and analytical methods that will be necessary in support of SMP activities. These objectives have been established in order to meet standards that will protect public health and the environment for the Site.

1.3 Scope of Work

The specific scope of work covered in this QAPP includes any performance groundwater sampling that will occur during implementation of the SMP.

2.0 DATA QUALITY OBJECTIVES AND PROCESS

Data Quality Objectives (DQOs) are qualitative and quantitative statements to help ensure that data of known and appropriate quality are obtained during the project. The overall objective is to evaluate the quality of groundwater.

DQOs for sampling activities are determined by evaluating five factors:

- Data needs and uses: The types of data required and how the data will be used after it is obtained.

- Parameters of Interest: The types of chemical or physical parameters required for the intended use.
- Level of Concern: Levels of constituents, which may require remedial actions or further investigations.
- Required Analytical Level: The level of data quality, data precision, and quality assurance/quality control (QA/QC) documentation required for chemical analysis.
- Required Detection Limits: The detection limits necessary based on the above information.

The quality assurance and quality control objectives for all measurement data include:

- Precision – an expression of the reproducibility of measurements of the same parameter under a given set of conditions. Field sampling precision will be determined by analyzing coded duplicate samples and analytical precision will be determined by analyzing internal QC duplicates and/or matrix spike duplicates.
- Accuracy – a measure of the degree of agreement of a measured value with the true or expected value of the quantity of concern. For soil samples, accuracy will be determined through the assessment of the analytical results of field blanks and trip blanks for each sample set. Analytical accuracy will be assessed by examining the percent recoveries of surrogate compounds that are added to each sample (organic analyses only), internal standards, laboratory method blanks, instrument calibration, and the percent recoveries of matrix spike compounds added to selected samples and laboratory blanks.
- Representativeness – expresses the degree to which sample data accurately and precisely represent a characteristic of a population, parameter variations at a sampling point, or an environmental condition. Representativeness is dependent upon the adequate design of the sampling program and will be satisfied by ensuring that the scope of work is followed and that specified sampling and analysis techniques are used. Representativeness in the laboratory is ensured by compliance to nationally-recognized analytical methods, meeting sample holding times, and maintaining sample integrity while the samples are in the laboratory's possession. This is accomplished by following all applicable methods, laboratory-issued standard operating procedures (SOPs), the laboratory's Quality Assurance Manual, and this QAPP. The laboratory is required to be properly certified and accredited.

- Completeness – the percentage of measurements made which are judged to be valid. Completeness will be assessed through data validation. The QC objective for completeness is generation of valid data for at least 90 percent of the analyses requested.
- Comparability – expresses the degree of confidence with which one data set can be compared to another. The comparability of all data collected for this project will be ensured using several procedures, including standard methods for sampling and analysis as documented in the QAPP, using standard reporting units and reporting formats, and data validation.
- Sensitivity – the ability of the instrument or method to detect target analytes at the levels of interest. The project manager will select, with input from the laboratory and QA personnel, sampling and analytical procedures that achieve the required levels of detection.

3.0 PROJECT ORGANIZATION AND RESPONSIBILITY

Implementation of the SMP will be overseen by Langan for Innovative Urban Living, LLC, IUV Phase 1B Owner, LLC, and IUV Phase 1B LIHTC Owner, LLC. The environmental consultant will also arrange data analysis and reporting tasks. The analytical services will be performed by an Environmental Laboratory Approval Program (ELAP)-certified laboratory. Data validation services will be performed by approved data validation contractor(s).

For the required sampling as stated in the SMP, sampling will be conducted by Langan, the analytical services will be performed by York Analytical Laboratories, Inc. (York) of Stratford, CT (New York State Department of Health [NYSDOH] ELAP certification number 10854).

Key contacts for this project are as follows:

Innovative Urban Living, LLC c/o Gotham Organization, LLC:	Bryan Kelly Telephone: (212) 716-2502
Langan Project Manager:	Amanda Forsburg Telephone: (973) 560-4900
Langan Quality Assurance Officer (QAO):	Steve Ciambruschini Telephone: (973) 560-4900

Langan Remedial Engineer:	Ron Boyer Telephone: (973) 560-4900
Program Quality Assurance Monitor (QAM):	Ashley Sandve Telephone: (973) 560-4900
Data Validator:	Joe Conboy Telephone: (215) 845-8985
Laboratory Representative:	York Analytical Laboratories, Inc. Allison Bennett Telephone: (203) 325-1371

4.0 QUALITY ASSURANCE OBJECTIVES FOR COLLECTION OF DATA

The overall quality assurance objective is to develop and implement procedures for sampling, laboratory analysis, field measurements, and reporting that will provide data of sufficient quality to evaluate groundwater conditions at the Site. The sample set, chemical analysis results, and interpretations must be based on data that meet or exceed quality assurance objectives established for the Site. Quality assurance objectives are usually expressed in terms of accuracy or bias, sensitivity, completeness, representativeness, comparability, and sensitivity of analysis. Variances from the quality assurance objectives at any stage of the investigation will result in the implementation of appropriate corrective measures and an assessment of the impact of corrective measures on the usability of the data.

Precision

Precision is a measure of the degree to which two or more measurements are in agreement. Field precision is assessed through the collection and measurement of field duplicates. Laboratory precision and sample heterogeneity also contribute to the uncertainty of field duplicate measurements. This uncertainty is taken into account during the data assessment process. For field duplicates, results less than 2x the reporting limit (RL) meet the precision criteria if the absolute difference is less than ±2X the RL. For results greater than 2X the RL, the acceptance criteria is a relative percent difference (RPD) of ≤50% (soil), and <30% (groundwater). RLs and method detection limits (MDL) are provided in Attachment B.

Accuracy

Accuracy is the measurement of the reproducibility of the sampling and analytical methodology. It should be noted that precise data may not be accurate data. For the purpose of this QAPP, bias is defined as the constant or systematic distortion of a

measurement process, which manifests itself as a persistent positive or negative deviation from the known or true value. This may be due to (but not limited to) improper sample collection, sample matrix interferences, poorly calibrated analytical or sampling equipment, or limitations or errors in analytical methods and techniques.

Accuracy in the field is assessed through the use of field blanks and through compliance to all sample handling, preservation, and holding time requirements. All field blanks should be non-detect when analyzed by the laboratory. Any contaminant detected in an associated field blank was evaluated against laboratory blanks (preparation or method) and evaluated against field samples collected on the same day to determine potential for bias.

Laboratory accuracy is assessed by evaluating the percent recoveries of MS/MSD samples, LCS/LCSDs, surrogate compound recoveries, internal standard responses and the results of method preparation blanks. MS/MSD, LCS/LCSD, internal standard responses and surrogate percent recoveries were compared to either method-specific control limits or laboratory-derived control limits. Sample volume permitting, samples displaying outliers should be reanalyzed. All associated method blanks should be non-detect when analyzed by the laboratory.

Completeness

Laboratory completeness is the ratio of total number of samples analyzed and verified as acceptable compared to the number of samples submitted to the fixed-base laboratory for analysis, expressed as a percent. Three measures of completeness are defined:

- Sampling completeness, defined as the number of valid samples collected relative to the number of samples planned for collection;
- Analytical completeness, defined as the number of valid sample measurements relative to the number of valid samples collected; and
- Overall completeness, defined as the number of valid sample measurements relative to the number of samples planned for collection.

Soil and groundwater data will meet a 90% completeness criterion. If the criterion is not met, sample results will be evaluated for trends in rejected and unusable data. The effect of unusable data required for a determination of compliance will also be evaluated.

Representativeness

Representativeness expresses the degree to which data accurately and precisely represents a characteristic of a population, parameter variations at a sampling point, a process condition, or an environmental condition within a defined spatial and/or temporal boundary. Representativeness is dependent upon the adequate design of the sampling program and was satisfied by ensuring that the scope of work is followed and that specified sampling and analysis techniques are used. This is performed by following applicable standard operating procedures (SOPs) and this QAPP. All field technicians will be given copies of appropriate documents prior to sampling events and will be required to read, understand, and follow each document as it pertains to the tasks at hand.

Representativeness in the laboratory is ensured by compliance to nationally-recognized analytical methods, meeting sample holding times, and maintaining sample integrity while the samples are in the laboratory's possession. This is performed by following all applicable EPA and standard methods, laboratory-issued SOPs, the laboratory's Quality Assurance Manual, and this QAPP. The laboratory is required to be properly certified and accredited.

Comparability

Comparability is an expression of the confidence with which one data set can be compared to another. Comparability is dependent upon the proper design of the sampling program and was satisfied by ensuring that the sampling plan is followed and that sampling is performed according to the SOPs or other project-specific procedures. Analytical data were comparable when similar sampling and analytical methods are used as documented in the QAPP. Comparability was controlled by requiring the use of specific nationally-recognized analytical methods and requiring consistent method performance criteria. Comparability is also dependent on similar quality assurance objectives. Previously collected data were evaluated to determine whether they may be combined with contemporary data sets.

Sensitivity

Sensitivity is the ability of the instrument or method to detect target analytes at the levels of interest (e.g., at the NYSDEC Subpart 375-6 Soil Cleanup Objectives). The Project Manager will select, with input from the laboratory and QA personnel, sampling and analytical procedures that achieve the required levels of detection and QC acceptance limits that meet established performance criteria. Concurrently, the Project Manager will select the level of data assessment to ensure that only data meeting the project DQOs are used in decision-making.

Field equipment will be used that can achieve the required levels of detection for analytical measurements in the field. In addition, the field sampling staff will collect and submit full volumes of samples as required by the laboratory for analysis, whenever possible. Full volume aliquots will help ensure achievement of the required limits of detection and allow for reanalysis if necessary. The concentration of the lowest level check standard in a multi-point calibration curve will represent the reporting limit.

Analytical methods and quality assurance parameters associated with the sampling program are presented in Attachment C. The frequency of associated field blanks and duplicate samples will be based on the recommendations listed in DER-10 and as described in Section 5.3.2.

5.0 SAMPLE COLLECTION AND FIELD DATA ACQUISITION PROCEDURES

Sampling will be conducted in accordance with the established NYSDEC protocols contained in DER-10/Technical Guidance for Site Investigation and Remediation (May 2010). The following sections describe procedures to be followed for specific tasks.

5.1 Field Documentation Procedures

Field documentation procedures will include summarizing field data in field books and proper sample labeling. These procedures are described in the following sections.

5.1.1 Field Data and Notes

Field notebooks contain the documentary evidence regarding procedures conducted by field personnel. Hard cover, bound field notebooks will be used because of their compact size, durability and secure page binding. The pages of the notebook will not be removed.

Entries were made in waterproof, permanent blue or black ink. No erasures will be allowed. Incorrect entries will be crossed out with a single strike mark and the change initialed and dated by the team member making the change.

Each entry will be dated. Entries will be legible and contain accurate and complete documentation of the individual or sampling team's activities or observations made. The level of detail will be sufficient to explain and reconstruct the activity conducted. Each entry will be signed by the person(s) making the entry.

The following types of information will be provided for each sampling task, as appropriate:

- Project name and number;
- Reasons for being on-Site or taking the sample;
- Date and time of activity;
- Sample identification numbers;
- Geographical location of sampling points with references to the Site, other facilities or a map coordinate system. Sketches were made in the field logbook when appropriate;
- Physical location of sampling locations such as depth below ground surface;
- Description of the method of sampling including procedures followed, equipment used and any departure from the specified procedures;
- Description of the sample including physical characteristics, odor, etc.;
- Readings obtained from health and safety equipment;
- Weather conditions at the time of sampling and previous meteorological events that may affect the representative nature of a sample;
- Photographic information including a brief description of what was photographed, the date and time, the compass direction of the picture and the number of the picture on the camera;
- Other pertinent observations such as the presence of other persons on the Site, actions by others that may affect performance of Site tasks, etc.; and,
- Names of sampling personnel and signature of persons making entries.

Field records will also be collected on field data sheets including boring logs, which will be used for geologic and drilling data during soil boring activities and groundwater parameter logs which will be used to track groundwater chemical parameter readings during groundwater sampling.

Field data sheets will include the project-specific number and stored in the field project files when not in use. At the completion of the field activities, the field data sheets will be maintained in the central project file.

5.1.2 Sample Labeling

Each sample collected will be assigned a unique identification number and placed in an appropriate sample container. Each sample container will have a sample label affixed to the outside with the date and time of sample collection and project name. In addition, the label will contain the sample identification number, analysis required and chemical preservatives added, if any. All documentation will be completed in waterproof ink. Sample nomenclature procedures are included in Attachment D.

5.2 Equipment Calibration and Preventative Maintenance

A photoionization detector (PID) will be used during all sampling activities to screen the monitoring wells. Field calibration and/or field checking of the PID will be the responsibility of the field team leader and the Site HSO, and will be accomplished by following the procedures outlined in the operating manual for the instrument. At a minimum, field calibration and/or field equipment checking will be performed once daily, prior to use. Field calibration will be documented in the field notebook. Entries made into the logbook regarding the status of field equipment will include the following information:

- Date and time of calibration
- Type of equipment serviced and identification number (such as serial number)
- Reference standard used for calibration
- Calibration and/or maintenance procedure used
- Other pertinent information

Equipment that fails calibration or becomes inoperable during use will be removed from service and segregated to prevent inadvertent utilization. The equipment will be properly tagged to indicate that it is out of calibration. Such equipment will be repaired and recalibrated to the manufacturer's specifications by qualified personnel. Equipment that cannot be repaired will be replaced.

Off-Site calibration and maintenance of field instruments will be conducted as appropriate throughout the duration of project activities. All field instrumentation, sampling equipment and accessories will be maintained in accordance with the manufacturer's recommendations and specifications and established field equipment practice. Off-Site calibration and maintenance will be performed by qualified personnel. A logbook will be kept to document that established calibration and maintenance procedures have been followed. Documentation will include both scheduled and unscheduled maintenance.

5.3 Sample Collection

5.3.1 Soil Samples

Soil sampling is not anticipated during SMP activities. In the event that soil sampling is required, soil samples will be visually classified and field screened using a PID to assess potential impacts from VOCs and for health and safety monitoring. Soil samples collected for analysis of VOCs will be collected using Terra Core® sampling equipment. For analysis of non-volatile parameters, samples will be homogenized and placed into glass jars. After collection, all sample jars will be capped and securely tightened, and placed in iced coolers and maintained at 4°C ±2°C until they are transferred to the laboratory for analysis, in accordance with the procedures outlined in Section 5.4. Analysis and/or extraction and digestion of collected soil samples will meet the holding times required for each analyte as specified in Attachment C. In addition, analysis of collected soil sample will meet all quality assurance criteria set forth by this QAPP and DER-10.

Soil samples analyzed for per- and poly-fluoro alkyl substances (PFAS) will be collected in an 8 ounce high-density polyethylene (HDPE) container provided by the laboratory and analyzed by using USEPA Method 1633A. The reporting limits for PFAS in soil are included in Attachment B. The laboratory standard operating procedures (SOP) for the analysis of PFAS is included in Attachment E. Soil samples analyzed for 1,4-dioxane will be collected in an 8-ounce jar provided by the laboratory and analyzed using USEPA Method 8270. The reporting limit for 1,4-dioxane in soil is 0.1 milligram per kilogram (mg/kg).

5.3.1.1 Sample Field Blanks and Duplicates

Use of dedicated sampling equipment is planned; therefore, collection of field blanks is not anticipated. If the use of reusable sampling equipment is required, proper decontamination procedures will be employed (as further described in Section 5.7) and field blanks will be collected for quality assurance purposes at a rate of one per 20 investigative soil samples. If required, field blanks will be obtained by pouring laboratory-demonstrated analyte-free water on or through a decontaminated sampling device following use and implementation of decontamination protocols. The water will be collected off of the sampling device into a laboratory-provided sample container for analysis. Field blanks will be collected at a rate of one per 20 samples and will be analyzed for the complete list of analytes on the day of sampling. If less than 20 samples are collected during a particular sampling event, one field blank sample will be collected. Equipment blanks will be collected at a rate of one per day when soil samples are analyzed for PFAS. Trip blanks will be collected at a rate of one per day if soil samples are analyzed for VOCs during that day.

Duplicate soil samples will be collected and analyzed for quality assurance purposes. Duplicate samples will be collected at a frequency of 1 per 20 investigative soil samples and will be submitted to the laboratory as "blind" samples. If less than 20 samples are collected during a particular sampling event, one duplicate sample will be collected.

Matrix Spike/Matrix Spike Duplicate (MS/MSD) samples (MS/MSD for organics; MS and laboratory duplicate for inorganics) will be taken at a frequency of one pair per 20 field samples. If less than 20 samples are collected during a particular sampling event, one MS/MSD sample will be collected. These samples are used to assess the effect of the sample matrix on the recovery of target compounds or target analytes.

5.3.2 Groundwater Samples

Groundwater samples will be collected into laboratory-supplied containers and will be sealed, labeled, and placed in a cooler containing ice (to maintain a temperature of approximately 4 degrees Celsius) for delivery to a NYSDOH ELAP-certified analytical laboratory. Analysis and/or extraction and digestion of collected groundwater samples will meet the holding times required for each analyte as specified in Attachment C. In addition, analysis of collected groundwater samples will meet all quality assurance criteria set forth by this QAPP and DER-10.

Sampling for PFAS is not anticipated. In the event that groundwater sampling for PFAS is required, groundwater samples analyzed for PFAS will be collected in three 500-milliliter (mL) HDPE containers provided by the laboratory and analyzed using USEPA Method 1633A. The reporting limits for PFAS in groundwater are provided in Attachment B. The laboratory SOP for the analysis of PFAS is included in Attachment E. Groundwater samples also be analyzed for 1,4-dioxane will be collected in a one-liter amber glass jar and analyzed using USEPA Method 8270 SIM. The reporting limit for 1,4-dioxane in groundwater is 0.35 micrograms per liter (ug/L).

5.3.2.1 Sample Field Blanks and Duplicates

Use of dedicated sampling equipment is planned; therefore, collection of field blanks is not anticipated. If the use of reusable sampling equipment is required, proper decontamination procedures will be employed (as further described in Section 5.7) and field blanks will be collected for quality assurance purposes at a rate of one per 20 investigative groundwater samples. If required, field blanks will be obtained by pouring laboratory-demonstrated analyte-free water on or through a decontaminated sampling device following use and implementation of decontamination protocols. The water will be collected off of the sampling device into a laboratory-provided sample container for analysis. Field blanks will be collected at a rate of one per 20 samples and will be analyzed for the complete list of analytes on the day of sampling. If less than 20 samples are collected during a particular sampling

event, one field blank sample will be collected. Equipment blanks will be collected at a rate of one per day when groundwater samples are analyzed for PFAS. Trip blanks will be collected at a rate of one per day if groundwater samples are analyzed for VOCs during that day.

Duplicate groundwater samples will be collected and analyzed for quality assurance purposes. Duplicate samples will be collected at a frequency of 1 per 20 investigative soil samples and will be submitted to the laboratory as "blind" samples. If less than 20 samples are collected during a particular sampling event, one duplicate sample will be collected.

MS/MSD samples (MS/MSD for organics; MS and laboratory duplicate for inorganics) will be taken at a frequency of one pair per 20 field samples. If less than 20 samples are collected during a particular sampling event, one MS/MSD sample will be collected. These samples are used to assess the effect of the sample matrix on the recovery of target compounds or target analytes.

5.3.3 Soil Vapor / Indoor Air Samples

Soil vapor and/or indoor air sampling is not anticipated during SMP activities. In the event that soil vapor sapling is required, samples will be collected in accordance with the Final Guidance for Evaluating Soil Vapor Intrusion in the State of New York (NYSDOH October 2006). Soil vapor implants will be set at a depth of approximately 14-feet below current Site grades which corresponds to the depth interval directly below the proposed development excavation depth. Each vapor probe will consist of a new, dedicated stainless steel screen implant connected to polyethylene or Teflon™ tubing extending to the target depth. About 1 foot of clean sand filter pack will be placed around the screen implant, and the remaining annular space will be backfilled to grade with hydrated bentonite. Sampling will occur for the duration of 2 hours.

Samples will be collected in appropriate sized Summa canisters that have been certified clean by the laboratory and samples will be analyzed by using USEPA Method TO-15. Flow rate for both purging and sampling will

not exceed 0.2 L/min. 24-hours following soil vapor probe installation, one to three implant volumes shall be purged prior to the collection of any soil-gas samples. A sample log sheet will be maintained summarizing sample identification, date and time of sample collection, sampling depth, identity of samplers, sampling methods and devices, soil vapor purge volumes, volume of the soil vapor extracted, vacuum of canisters before and after the samples are collected, apparent moisture content of the sampling zone, and chain of custody protocols.

As part of the vapor intrusion evaluation, a tracer gas will be used in accordance with NYSDOH protocols to serve as a quality assurance/quality control (QA/QC) device to verify the integrity of the soil vapor probe seal. A container (box, plastic pail, etc.) will serve to keep the tracer gas in contact with the probe during testing. A portable monitoring device will be used to analyze a sample of soil vapor for the tracer gas prior to sampling. If the tracer sample results show a significant presence of the tracer, the probe seals will be adjusted to prevent infiltration. At the conclusion of the sampling round, tracer monitoring will be performed a second time to confirm the integrity of the probe seals.

5.3.3.1 Soil Vapor / Indoor Air Sample Duplicates

Duplicate soil vapor / indoor air samples will be collected and analyzed for quality assurance purposes. Duplicate samples will be collected at a frequency of 1 per 20 investigative soil vapor / indoor air samples and will be submitted to the laboratory as "blind" samples. If less than 20 samples are collected during a particular sampling event, one duplicate sample will be collected.

5.3.4 PFAS Sampling Procedures

Field personnel conducting PFAS sampling will wear clothing and use equipment which does not contain PFAS materials including: powderless nitrile gloves, natural rubber overboots, and synthetic and natural fiber clothing. Clothing advertised as waterproof, water-repellant, and/or dirt and/or stain resistant will not be worn. Personal hygiene products with conditioning agents will be avoided prior to the sampling event. Insect repellent and sunscreen will be avoided. Consumption of food and/or beverages will be strictly prohibited during sampling activities, excluding

bottled water for hydration. Ballpoint pens will be used as the sole writing instrument to complete labels and record field notes. Waterproof field books, including "Rite-in-Rain"™ will be avoided.

Only sampling equipment known to be devoid of PFAS containing materials will be used. Acceptable materials for sampling include stainless steel, HDPE, PVC, silicone, acetate, and polypropylene. In general, PFAS-free pumps, tubing, interface probes, soil sampling equipment, and bottleware will be considered prior to the sampling event. It is not anticipated that groundwater samples will be collected for PFAS analysis; however, if required, peristaltic pumps will be utilized as the depth of groundwater is less than 20-feet. If groundwater is determined to be greater than 20 feet deep, bladder pumps (QED Sample Pro, or equivalent) with a fluoropolymer-free bladder will be used. HDPE will be used for tubing, soil sampling equipment, and bottleware.

Field personnel will follow standard discrete soil sampling and low flow procedures when sampling for PFAS. When possible, disposable and dedicated equipment will be used for each sample location to avoid potential cross contamination and limit errors from inadequate decontamination between samples. Bladder pumps and/or peristaltic pump tubing will not be re-used and therefore decontamination of sampling equipment between samples will not be necessary. Nitrile gloves will be changed between each step during set up and sampling.

When sampling for PFAS, no sampling equipment components or sample containers should come in to contact with aluminum foil, low density polyethylene, glass, or polytetrafluoroethylene (PTFE, Teflon™) materials including plumbers tape and sample bottle cap liners with a PTFE layer.

Whenever an action occurs outside of procedure, such as the writing of field notes, nitrile gloves will be changed. Sampling equipment will be staged 5-feet away from the boring or open wellhead. Equipment not directly related to sampling will be staged in a separate area away from the boring or open wellhead. When inserting the tubing into the well, the surrounding platform will be avoided as a source of transference. While stabilizing the well, the pump will not be allowed to stop as backflow from the water quality meter can pose a risk to cross contamination. Once

stability has been achieved, sampling will occur. PFAS sample bottleware must be made of HDPE and bottleware must be filled to the container neck. Soil sample bottleware must only be filled half-way. The PFAS field and equipment blanks will be collected immediately following completion of PFAS sampling at the frequency discussed above (Sections 5.3.1.1 and 5.3.2.1).

The PFAS compounds to be analyzed includes: Perfluorobutanesulfonic acid (PFBS), Perfluoropentanesulfonic acid (PFPeS), Perfluorohexanesulfonic acid (PFHxS), Perfluoroheptanesulfonic acid (PFHpS), Perfluorooctanesulfonic acid (PFOS), Perfluorononanesulfonic acid (PFNS), Perfluorodecanesulfonic acid (PFDS), Perfluorododecanesulfonic acid (PFDoS), Perfluorobutanoic acid (PFBA), Perfluoropentanoic acid (PFPeA), Perfluorohexanoic acid (PFHxA), Perfluoroheptanoic acid (PFHpA), Perfluorooctanoic acid (PFOA), Perfluorononanoic acid (PFNA), Perfluorodecanoic acid (PFDA), Perfluoroundecanoic acid (PFUnA), Perfluorododecanoic acid (PFDoA), Perfluorotridecanoic acid (PFTrDA), Perfluorotetradecanoic acid (PFTeDA), Hexafluoropropylene oxide dimer acid (HFPO-DA), 4,8-Dioxa-3H-perfluorononanoic acid (ADONA), Perfluoro-3-methoxypropanoic acid (PFMPA), Perfluoro-4-methoxybutanoic acid (PFMBA), Nonafluoro-3,6-dioxaheptanoic acid (NFDHA), 4:2 Fluorotelomer sulfonic acid (4:2-FTS), 6:2 Fluorotelomer sulfonic acid (6:2-FTS), 8:2 Fluorotelomer sulfonic acid (8:2-FTS), 3:3 Fluorotelomer carboxylic acid (3:3 FTCA), 5:3 Fluorotelomer carboxylic acid (5:3 FTCA), 7:3 Fluorotelomer carboxylic acid (7:3 FTCA), Perfluorooctane sulfonamide (PFOSA), N-methylperfluorooctane sulfonamide (NMeFOSA), N-ethylperfluorooctane sulfonamide (NEtFOSA), N-methylperfluorooctane sulfonamidoacetic acid (N-MeFOSAA), N-ethylperfluorooctane sulfonamidoacetic acid (N-EtFOSAA), N-methylperfluorooctane sulfonamidoethanol (NMeFOSE), N-ethylperfluorooctane sulfonamidoethanol (NEtFOSE), 9-Chlorohexadecafluoro-3-oxanonane-1-sulfonic acid (F-53B Major) (9Cl-PF3ONS), 11-Chloroeicosafluoro-3-oxaundecane-1-sulfonic acid (F-53B Minor) (11Cl-PF3OUdS), Perfluoro(2-ethoxyethane) sulfonic acid (PFEESA).

5.4 Sample Containers and Handling

Certified, commercially clean sample containers will be obtained from the analytical laboratory. The laboratory will also prepare and supply the required field blank sample containers and reagent preservatives. Sample containers, including

the field blank containers, will be placed in plastic coolers by the laboratory. These coolers will be received by the field sampling team within 24 hours of their preparation in the laboratory. Prior to the commencement of field work, Langan field personnel will fill the plastic coolers with regular ice only in Ziploc® bags (or equivalent) to maintain a temperature of 4°C±2° C.

Soil and/or groundwater samples collected in the field for laboratory analysis will be placed directly into the laboratory-supplied sample containers. Samples will then be placed and stored on-ice in laboratory provided coolers until shipment to the laboratory. The temperature in the coolers containing samples and associated field blanks will be maintained at a temperature of 4°C±2°C while on-Site and during sample shipment to the analytical laboratory.

Possession of samples collected in the field will be traceable from the time of collection until they are analyzed by the analytical laboratory or are properly disposed. Chain-of-custody procedures, described in Section 5.9, will be followed to maintain and document sample possession. Samples will be packaged and shipped as described in Section 5.6.

5.5 Sample Preservation

Sample preservation measures will be used in an attempt to prevent sample decomposition by contamination, degradation, biological transformation, chemical interactions and other factors during the time between sample collection and analysis. Preservation will commence at the time of sample collection and will continue until analyses are performed. Should chemical preservation be required, the analytical laboratory will add the preservatives to the appropriate sample containers before shipment to the office or field. Samples will be preserved according to the requirements of the specific analytical method selected, as shown in Attachment C.

5.6 Sample Shipment

5.6.1 Packaging

Sample containers will be placed in plastic coolers. Regular ice only in Ziploc® bags (or equivalent) will be placed around sample containers. Cushioning material will be added around the sample containers if necessary. Chains-of-custody and other paperwork will be placed in a Ziploc® bag (or equivalent) and placed inside the cooler and custody seals will be affixed to one side of the cooler at a minimum. If the samples are

being shipped by an express delivery company (third-party courier, e.g., FedEx) then laboratory address labels will be placed on top of the cooler.

5.6.2 Shipping

Standard procedures to be followed for shipping environmental samples to the analytical laboratory are outlined below.

- All environmental samples will be transported to the laboratory from the Site or Langan office by a laboratory provided courier under the chain-of-custody protocols described in Section 5.9. A third-party courier may be used if necessary.
- Prior notice will be provided to the laboratory regarding when to expect shipped samples. If the number, type or date of shipment changes due to Site constraints or program changes, the laboratory will be informed.

5.7 Decontamination Procedures

Though not anticipated, decontamination procedures will be used if non-dedicated sampling equipment is utilized during the RAWP. Field sampling equipment that is to be reused will be decontaminated in the field in accordance with the following procedures:

1. Laboratory-grade glassware detergent and tap water scrub to remove visual contamination
2. Generous tap water rinse
3. Distilled/de-ionized water rinse

Field sampling equipment that will be used for the collection of PFAS samples that is to be reused will be decontaminated in the field in accordance with the following procedures:

1. Laboratory-grade glassware detergent and clean, PFAS-free water scrub to remove visual contamination
2. Generous clean, PFAS-free water rinse

5.8 Residuals Management

Debris (e.g., paper, plastic and disposable PPE) will be collected in plastic garbage bags and disposed of as non-hazardous industrial waste. Debris is expected to be transported to a local municipal landfill for disposal.

5.9 Chain of Custody Procedures

A chain-of-custody protocol has been established for collected samples was and will be followed during sample handling activities in both field and laboratory operations. The primary purpose of the chain-of-custody procedures is to document the possession of the samples from collection through shipping, storage and analysis to data reporting and disposal. Chain-of-custody refers to actual possession of the samples. Samples are considered to be in custody if they are within sight of the individual responsible for their security or locked in a secure location. Each person who takes possession of the samples, except for third-party shipping couriers, is responsible for sample integrity and safe keeping. Chain-of-custody procedures are provided below:

- Chain-of-custody will be initiated by the laboratory supplying the pre-cleaned and prepared sample containers. Chain-of-custody forms will accompany the sample containers.
- Following sample collection, the chain-of-custody form will be completed for the samples collected. The sample identification number, date and time of sample collection, analysis requested and other pertinent information (e.g., preservatives) will be recorded on the form. Entries will be made in waterproof, permanent blue or black ink.
- Langan field personnel will be responsible for the care and custody of the samples collected until the samples are transferred to another party, dispatched to the laboratory, or disposed. The sampling/Field Team Leader will be responsible for enforcing chain-of-custody procedures during field work.
- When the form is full or when all samples have been collected that will fit in a single cooler, the sampling/Field Team Leader will check the form for possible errors and sign the chain-of-custody form. Any necessary corrections will be made to the record with a single strike mark, dated, and initialed.

Samples will be packaged for shipment or pickup via courier to the laboratory with the appropriate chain-of-custody form. If applicable, a shipping bill will be completed for each cooler and the shipping bill number recorded on the chain-of-custody form. A copy of the form will be retained by the Langan sampling team for the project file, and the original will be sent to the laboratory with the samples. Bills of lading will also be retained as part of the documentation for the chain-of-custody records, if applicable. When transferring custody of the samples, the individuals relinquishing and receiving custody of the samples will verify sample numbers and condition and will document the sample acquisition and transfer by signing and dating the chain-of-custody form. This process documents sample custody transfer from the sampler to the analytical laboratory.

Laboratory chain-of-custody will be maintained throughout the analytical processes as described in the laboratory's Quality Assurance Manual. The analytical laboratory will provide a copy of the chain-of-custody in the analytical data deliverable package. The chain-of-custody becomes the permanent record of sample handling and shipment.

5.10 Laboratory Sample Storage Procedures

The subcontracted laboratory will use a laboratory information management system (LIMS) to track and schedule samples upon receipt by the analytical laboratories. Any sample anomalies identified during sample log-in must be evaluated on individual merit for the impact upon the results and the data quality objectives of the project. When irregularities do exist, Langan must be notified to discuss recommended courses of action and documentation of the issue must be included in the project file.

For samples requiring thermal preservation, the temperature of each cooler will be immediately recorded. Each sample and container will be assigned a unique laboratory identification number and secured within the custody room walk-in coolers designated for new samples. Samples will be, as soon as practical, disbursed in a manner that is functional for the operational team. The temperature of all coolers and freezers will be monitored and recorded using a certified temperature sensor. Any temperature excursions outside of acceptance criteria (i.e., below 2°C or above 6°C) will initiate an investigation to determine whether any samples may have been affected. Following analysis, the laboratory's specific procedures for retention and disposal will be followed as specified in the laboratory's SOPs and/or QA manual.

6.0 DATA REDUCTION, VALIDATION, AND REPORTING

6.1 Introduction

Data collected during the field investigation will be reduced and reviewed by the laboratory QA personnel, and a report on the findings will be tabulated in a standard format. The criteria used to identify and quantify the analytes will be those specified for the applicable methods in the USEPA SW-846 and subsequent updates. The data package provided by the laboratory will contain all items specified in the USEPA SW-846 appropriate for the analyses to be performed, and be reported in standard format.

The completed copies of the chain-of-custody records (both external and internal) accompanying each sample from time of initial bottle preparation to completion of analysis shall be attached to the analytical reports.

6.2 Data Reduction

The Analytical Services Protocol (ASP) Category B data packages and an electronic data deliverable (EDD) will be provided by the laboratory after receipt of a complete sample delivery group. The Project Manager will immediately arrange for archiving the results and preparation of result tables. These tables will form the database for assessment of the Site contamination condition.

Each EDD deliverable must be formatted using a Microsoft Windows operating system and the NYSDEC data deliverable format for EQuIS. To avoid transcription errors, data will be loaded directly into the American Standard Code for Information Interchange (ASCII) format from the LIMS. If this cannot be accomplished, the consultant should be notified via letter of transmittal indicating that manual entry of data is required for a particular method of analysis. All EDDs must also undergo a QC check by the laboratory before delivery. The original data, tabulations, and electronic media are stored in a secure and retrievable fashion.

The Project Manager or Task Manager will maintain close contact with the QA reviewer to ensure all non-conformance issues are acted upon prior to data manipulation and assessment routines. Once the QA review has been completed, the Project Manager may direct the Team Leaders or others to initiate and finalize the analytical data assessment.

6.3 Data Validation

Data validation will be performed in accordance with the USEPA validation guidelines for organic and inorganic data review. Validation will include the following:

- Verification of the QC sample results,
- Verification of the identification of sample results (both positive hits and non-detects),
- Recalculation of 10 percent of all investigative sample results, and
- Preparation of Data Usability Summary Reports (DUSR).

A DUSR will be prepared and reviewed by the QAM before issuance. The DUSR will present the results of data validation, including a summary assessment of laboratory data packages, sample preservation and COC procedures, and a summary assessment of precision, accuracy, representativeness, comparability, and completeness for each analytical method. A detailed assessment of each SDG will follow. For each of the organic analytical methods, the following will be assessed:

- Holding times;
- Instrument tuning;
- Instrument calibrations;
- Blank results;
- System monitoring compounds or surrogate recovery compounds (as applicable);
- Internal standard recovery results;
- MS and MSD results;
- Target compound identification;
- Chromatogram quality;
- Pesticide cleanup (if applicable);
- Compound quantitation and reported detection limits;
- System performance; and
- Results verification.

For each of the inorganic compounds, the following will be assessed:

- Holding times;
- Calibrations;
- Blank results;
- Interference check sample;
- Laboratory check samples;
- Duplicates;
- Matrix Spike;
- Furnace atomic absorption analysis QC;
- Inductively couple plasma (ICP) serial dilutions; and
- Results verification and reported detection limits.

Based on the results of data validation, the validated analytical results reported by the laboratory will be assigned one of the following usability flags:

- "U" - Not detected. The associated number indicates the approximate sample concentration necessary to be detected significantly greater than the level of the highest associated blank;
- "UJ" - Not detected. Quantitation limit may be inaccurate or imprecise;
- "J" - Analyte is present. Reported value may be associated with a higher level of uncertainty than is normally expected with the analytical method;
- "N" – Tentative identification. Analyte is considered present in the sample;
- "R" – Unreliable result; data is rejected or unusable. Analyte may or may not be present in the sample; and,
- No Flag - Result accepted without qualification.

7.0 QUALITY ASSURANCE PERFORMANCE AUDITS AND SYSTEM AUDITS

7.1 Introduction

Quality assurance audits may be performed by the project quality assurance group under the direction and approval of the QAO. These audits will be implemented to evaluate the capability and performance of project and subcontractor personnel, items, activities, and documentation of the measurement system(s). Functioning

as an independent body and reporting directly to corporate quality assurance management, the QAO may plan, schedule, and approve system and performance audits based upon procedures customized to the project requirements. At times, the QAO may request additional personnel with specific expertise from company and/or project groups to assist in conducting performance audits. However, these personnel will not have responsibility for the project work associated with the performance audit.

7.2 System Audits

System audits may be performed by the QAO or designated auditors, and encompass a qualitative evaluation of measurement system components to ascertain their appropriate selection and application. In addition, field and laboratory quality control procedures and associated documentation may be system audited. These audits may be performed once during the performance of the project. However, if conditions adverse to quality are detected or if the Project Manager requests, additional audits may occur.

7.3 Performance Audits

The laboratory may be required to conduct an analysis of Performance Evaluation samples or provide proof that Performance Evaluation samples submitted by USEPA or a state agency have been analyzed within the past twelve months.

7.4 Formal Audits

Formal audits refer to any system or performance audit that is documented and implemented by the QA group. These audits encompass documented activities performed by qualified lead auditors to a written procedure or checklists to objectively verify that quality assurance requirements have been developed, documented, and instituted in accordance with contractual and project criteria. Formal audits may be performed on project and subcontractor work at various locations.

Audit reports will be written by auditors who have performed the Site audit after gathering and evaluating all data. Items, activities, and documents determined by lead auditors to be in noncompliance shall be identified at exit interviews conducted with the involved management. Non-compliances will be logged, and documented through audit findings, which are attached to and are a part of the integral audit report. These audit-finding forms are directed to management to satisfactorily resolve the noncompliance in a specified and timely manner.

The Project Manager has overall responsibility to ensure that all corrective actions necessary to resolve audit findings are acted upon promptly and satisfactorily. Audit reports must be submitted to the Project Manager within fifteen days of completion of the audit. Serious deficiencies will be reported to the Project Manager within 24 hours. All audit checklists, audit reports, audit findings, and acceptable resolutions are approved by the QAO prior to issue. Verification of acceptable resolutions may be determined by re-audit or documented surveillance of the item or activity. Upon verification acceptance, the QAO will close out the audit report and findings.

8.0 CORRECTIVE ACTION

8.1 Introduction

The following procedures have been established to ensure that conditions adverse to quality, such as malfunctions, deficiencies, deviations, and errors, are promptly investigated, documented, evaluated, and corrected.

8.2 Procedure Description

When a significant condition adverse to quality is noted at Site, laboratory, or subcontractor location, the cause of the condition will be determined and corrective action will be taken to preclude repetition. Condition identification, cause, reference documents, and corrective action planned to be taken will be documented and reported to the QAO, Project Manager, Field Team Leader and involved contractor management, at a minimum. Implementation of corrective action is verified by documented follow-up action.

All project personnel have the responsibility, as part of the normal work duties, to promptly identify, solicit approved correction, and report conditions adverse to quality. Corrective actions will be initiated as follows:

- When predetermined acceptance standards are not attained;
- When procedure or data compiled are determined to be deficient;
- When equipment or instrumentation is found to be faulty;
- When samples and analytical test results are not clearly traceable;
- When quality assurance requirements have been violated;
- When designated approvals have been circumvented;

- As a result of system and performance audits;
- As a result of a management assessment;
- As a result of laboratory/field comparison studies; and,
- As required by USEPA SW-846, and subsequent updates, or by the NYSDEC ASP.

Project management and staff, such as field investigation teams, remedial response planning personnel, and laboratory groups, monitor on-going work performance in the normal course of daily responsibilities. Work may be audited at the Sites, laboratories, or contractor locations. Activities, or documents ascertained to be noncompliant with quality assurance requirements will be documented. Corrective actions will be mandated through audit finding sheets attached to the audit report. Audit findings are logged, maintained, and controlled by the Task Manager.

Personnel assigned to quality assurance functions will have the responsibility to issue and control Corrective Action Request (CAR) Forms (Figure 8.1 or similar). The CAR identifies the out-of-compliance condition, reference document(s), and recommended corrective action(s) to be administered. The CAR is issued to the personnel responsible for the affected item or activity. A copy is also submitted to the Project Manager. The individual to whom the CAR is addressed returns the requested response promptly to the QA personnel, affixing his/her signature and date to the corrective action block, after stating the cause of the conditions and corrective action to be taken. The QA personnel maintain the log for status of CARs, confirms the adequacy of the intended corrective action, and verifies its implementation. CARs will be retained in the project file for the records.

Any project personnel may identify noncompliance issues; however, the designated QA personnel are responsible for documenting, numbering, logging, and verifying the close out action. The Project Manager will be responsible for ensuring that all recommended corrective actions are implemented, documented, and approved.

FIGURE 8.1

CORRECTIVE ACTION REQUEST

Number: _____ Date: _____

TO: _____

You are hereby requested to take corrective actions indicated below and as otherwise determined by you to (a) resolve the noted condition and (b) to prevent it from recurring. Your written response is to be returned to the project quality assurance manager by _____

CONDITION:

REFERENCE DOCUMENTS:

RECOMMENDED CORRECTIVE ACTIONS:

_____ _____ _____ _____ _____ _____

Originator Date Approval Date Approval Date

RESPONSE

CAUSE OF CONDITION

CORRECTIVE ACTION

(A) RESOLUTION

(B) PREVENTION

(C) AFFECTED DOCUMENTS

C.A. FOLLOWUP:

CORRECTIVE ACTION VERIFIED BY: _____ DATE:_____

9.0 REFERENCES

NYSDEC. Division of Environmental Remediation. DER-10/Technical Guidance for Site Investigation and Remediation, dated May 3, 2010.

NYSDEC. Division of Environmental Remediation. Sampling, Analysis, and Assessment of Per- and Polyfluoroalkyl Substances (PFAS) Under NYSDEC's Part 375 Remedial Programs, dated April 2023.

NYSDOH. Final Guidance for Evaluating Soil Vapor Intrusion in the State of New York, dated October 2006.

Taylor, J. K., 1987. Quality Assurance of Chemical Measurements. Lewis Publishers, Inc., Chelsea, Michigan

USEPA, 1986. SW-846 "Test Method for Evaluating Solid Waste," dated November 1986. U.S. Environmental Protection Agency, Washington, D.C.

USEPA, 1987. Data Quality Objectives for Remedial Response Actions Activities: Development Process, EPA/540/G-87/003, OSWER Directive 9355.0-7 - U.S. Environmental Protection Agency, Washington, D.C.

USEPA, 1992a. CLP Organics Data Review and Preliminary Review. SOP No. HW-6, Revision #8, dated January 1992. USEPA Region II.

USEPA, 1992b. Evaluation of Metals Data for the Contract Laboratory Program (CLP) based on SOW 3/90. SOP No. HW-2, Revision XI, dated January 1992. USEPA Region II.

USEPA. Hazardous Waste Support Section. Analysis of Volatile Organic Compounds in Air Contained in Canisters by Method TO-15. SOP No. HW-31, Revision #6, dated June 2014.

FIGURES



LANGAN

300 Kimball Drive
Parsippany, NJ 07054
T: 973.560.4900 F: 973.560.4901 www.langan.com

Langan Engineering & Environmental Services, Inc.
Langan Engineering, Environmental, Surveying, Landscape Architecture and Geology, D.P.C.
Langan International LLC
Collectively known as Langan

NJ CERTIFICATE OF AUTHORIZATION No. 24GA27996400

Project

12074 FLATLANDS AVENUE

BLOCK No. 4434, LOT No. 1

BROOKLYN

KINGS COUNTY NEW YORK

Drawing Title

SITE LOCATION MAP

Project No. 100688801	Figure 1
Date 5/25/2023	
Scale 1"=2,000'	
Drawn By IHB	

© 2018 Langan

Path: \\langan.com\data\PAR\data8\100688801\Project Data\ArcGIS\MXD\Environmental_Figures\2022-01 CCC RIWP\Figure 1 - Site Location Map.mxd

Legend

- Site Boundary
- Tax Parcel
- Groundwater Flow Direction
- Proposed Monitoring Wells
- Proposed Monitoring Wells (Pending Access Agreement with Adjacent Property to the South)

FLATLANDS AVENUE

PENNSYLVANIA AVENUE

Block:4430
Lot:1

Block:4434
Lot:1

Block:4434
Lot:10

Block:4434
Lot:60

Block:4431
Lot:70

N
W
E
S

50 0 50
SCALE IN FEET

References:
1. Parcel boundaries obtained from the New York City Department of Planning's MapPLUTO 23v3, updated 2023.
2. Aerial imagery obtained through Langan's subscription to Nearmap, dated 3/19/2023

LANGAN
300 Kimball Drive
Parsippany, NJ 07054
T: 973.560.4900 F: 973.560.4901 www.langan.com

Langan Engineering & Environmental Services, Inc.
Langan Engineering, Environmental, Surveying, Landscape Architecture and Geology, D.P.C.
Langan International LLC
Collectively known as Langan

NJ CERTIFICATE OF AUTHORIZATION No. 24GA27996400

Project
12074 FLATLANDS AVENUE
BLOCK No. 4434, LOT No. 1
BROOKLYN
KINGS COUNTY NEW YORK

Drawing Title
PROPOSED POST CONSTRUCTION MONITORING WELL LOCATION PLAN

Project No.	100688801
Date	12/1/2023
Scale	1 " = 50 '
Drawn By	IHB
Figure	2

© 2012 Langan

Path: \\Langan.com\data\PAR\data8\100688801\Project Data\ArcGIS\MXD\Environmental_Figures\2023-11 Phase 1B Update\Figure 12 - Proposed Post-Construction Monitoring Well Location Plan.mxd

ATTACHMENT A

Resumes

RONALD D. BOYER, PE

PRINCIPAL/VICE PRESIDENT

GEOTECHNICAL ENGINEERING

Mr. Boyer is an experienced geotechnical engineer whose practice involves coordination and supervision of subsurface investigations; establishment and monitoring of geotechnical instrumentation; design of shallow and deep foundation systems; evaluation of earth slope stability; design and inspection of subgrade improvement applications; preparation of geotechnical engineering reports and construction specifications; performance of pre-construction conditions documentation; coordination and supervision of construction inspection services; and monitoring of adjacent structures during demolition and construction.

SELECTED PROJECTS

- 11 Hubert Street, New York, NY
- 110 University Place, New York, NY
- 111 Murray Street Development, New York, NY
- 120 Neptune Avenue, Brooklyn, NY
- 125 Greenwich Street Development, New York, NY
- 150 Amsterdam Avenue, New York, NY
- 22 Thames Street, New York, NY
- 225 East 39th Street Development, New York, NY
- 2329 Nostrand Avenue, Brooklyn, NY
- 259 West 10th Street, New York, NY
- 315 East 46th Street, New York, NY
- 414 West 15thh Street, New York, NY
- 485 Fifth Avenue, New York, NY
- 510 West 22nd Street, New York, NY
- 57 Reade Street Development, New York, NY
- 92 Fulton Street, New York, NY
- American Dream Meadowlands, East Rutherford, NJ
- Avalon Bay, Boonton, NJ
- Bank Street Commons, White Plains, NY
- Brooklyn Law School Dormitory, Brooklyn, NY
- Cape Liberty Cruise Port, Bayonne, NJ
- CarMax - Waterbury, CT
- Christian Cultural Center, Brooklyn, NY
- Christiana Phase 2 Retail Development, Christiana, DE
- Circuit City Store, Wayne, NJ
- Clifton Commons, Clifton, NJ
- Colgate-Palmolive Waterfront Development, Various Locations
- Daily News Printing Press Facility, Jersey City, NJ
- DDC Rikers Island, New York, NY
- Essex Street Roadway Improvements, Hackensack, NJ
- Fifth Avenue Presbyterian Church, New York, NY
- General Motors - Lighthouse Landing, Sleepy Hollow, NY
- Giants Training Facility, East Rutherford, NJ
- Golden Orchards Geotechnical Support, Washington Township, NJ

EDUCATION

M.S., Civil Engineering (Geotechnical) Virginia Tech

B.S., Civil Engineering Virginia Tech

PROFESSIONAL REGISTRATION

Professional Engineer (PE) in NJ, NY

AFFILIATIONS

Deep Foundations Institute (DFI)

American Institute of Architects

Associated General Contractors of NJ

- Greenwich School, Greenwich, NJ
- Hudson County Courthouse, Jersey City, NJ
- K. Hovnanian at Bedminster Stormwater Detention System, Bedminster, NJ
- Kinko's, Norwalk, CT
- Kohl's Distribution Center, Mamakating, NY
- Lehman Brothers Data Center, Cranford, NJ
- Lehman Brothers Data Center, Piscataway, NJ
- Lowe's Norwalk, CT
- MetLife Stadium, East Rutherford, NJ
- Metropolitan Executive Towers, East Rutherford, NJ
- Morgan Stanley Data Center, Somerset, NJ
- Morristown Airport Hanger, Morristown, NJ
- MOMA West, New York, NY
- Newark International Airport, CONRac, Newark, NJ
- Newark International Airport, AirTrain Replacement, Newark, NJ
- New Britain Retail Center, New Britain, CT
- Northwest Airlines Cargo Facility, JFK International Airport, Queens, NY
- Norwalk Retail Development, Norwalk, CT
- One Bridge Plaza, Fort Lee, NJ
- PRBC - Medical Office Building, East Stroudsburg, PA
- Prospect Plaza, Brooklyn, NY
- PSEG Overhead Transmission, Throughout NJ
- River Bend at Port Imperial, West New York, NJ
- River Street Redevelopment, Hackensack, NJ
- Riverfront Stadium Redevelopment, Newark, NJ
- Riverside Square Mall Expansion, Hackensack, NJ
- Roosevelt Island DEP Seawall, New York, NY
- Roosevelt Island Park, Esplanade and Seawall, New York, NY
- Route 209 Expansion, Mamakating, NY
- Route 3 Flyover Bridge, Meadowlands, East Rutherford, NJ
- St Barnabas Hospital, Livingston, NJ
- Stevens Institute of Technology, Student Housing and University Center, Hoboken, NJ
- Stop & Shop, Various Locations
- T172 & S171N Transmission Lines, North Smithfield, RI
- Target Development, Bethel, CT
- Target Store, Horn Lake, MS
- Temporary Office Trailer Complex, East Rutherford, NJ
- The Standard, New York, NY
- The Venetian, Brooklyn, NY
- Westlakes Office Complex, Berwyn, PA
- Yonkers Avenue Bridge, Westchester County, NY

JOSEPH CONBOY

STAFF CHEMIST

ENVIRONMNETAL

Mr. Conboy has seven years of environmental chemistry, quality assurance, and environmental database management experience, with a current emphasis on validation of laboratory data for submittal to NJDEP via the New Jersey Data of Known Quality Protocols and to NYSDEC. Previous work experience includes performing validation of data for projects in USEPA Regions 2 and 3 while employing appropriate validation guidelines for each region, managing large data sets, updating appropriate regulatory limits, performing statistical evaluations, and preparing electronic data deliverables and report deliverables using the Earthsoft EQuIS database program, and acted as an intermediary between project managers, field staff, and laboratories. Mr. Conboy also has experience in field sampling techniques and maintains current OSHA HAZWOPER certification.

EDUCATION

B.Sc., Chemistry with a minor in Mathematics
Rowan University

CERTIFICATIONS & TRAINING

OSHA 40-Hour HAZWOPER 29 CFR 1910.120(e)(4) Certification

NJ Analytical Guidance and Data Usability Training

USEPA Data Validation Training

Earthsoft EQuIS Environmental Database Training

SELECTED PROJECTS

- 1400 Ferris, Bronx, NY – Completed validation of soil and groundwater data and prepared the Data Usability Summary Report for submittal to NYSDEC. USEPA Region II guidelines, with aide from National Functional Guidelines, were employed to perform validation of VOCs and SVOCs including 1,4-dioxane, and tangentially used based on professional judgment to perform validation of PFAS data.
- Broome Street Parking Lot, NY - Completed validation of waste characterization data and prepared the Data Usability Summary Report for submittal to NYSDEC. USEPA Region II guidelines, with aide from National Functional Guidelines, were employed to perform validation of VOCs, SVOCs, herbicides, PCBs, pesticides, metals including mercury, ignitability temperature, pH, reactive cyanide, reactive sulfide, cyanide, and hexavalent chromium. Toxicity characteristic leachate procedure extraction data for VOCs, SVOCs, herbicides, pesticides, metals, and mercury were also validated.
- 215 North 10th Street, Brooklyn, NY - Completed validation of soil and groundwater data and prepared the Data Usability Summary Report for submittal to NYSDEC. USEPA Region II guidelines, with aide from National Functional Guidelines, were employed to perform validation of VOC, SVOC, SVOC SIM, herbicide, PCB, pesticide, metals, mercury, cyanide, hexavalent chromium, trivalent chromium data.
- 35 Commercial Street, Brooklyn, NY - Completed validation of soil data and prepared the Data Usability Summary Report for submittal to NYSDEC. USEPA Region II guidelines, with aide from National Functional Guidelines, were employed to perform validation of VOC, SVOC, SVOC SIM, herbicide, PCB, pesticide, metals, mercury, cyanide, hexavalent chromium, trivalent chromium data, and tangentially used based on professional judgment to perform validation of PFAS data.
- Suffolk Street, Lower East Side, NY- Completed validation of soil, groundwater, and soil vapor data and prepared the Data Usability Summary Report for submittal to NYSDEC. USEPA Region II

guidelines, with aide from National Functional Guidelines, were employed to perform validation of VOC, VOCs by USEPA TO-15, SVOC, SVOC SIM, herbicide, PCB, pesticide, metals, mercury, cyanide, hexavalent chromium, trivalent chromium data, and tangentially used based on professional judgment to perform validation of PFAS data.

- Managed a database for a confidential client containing 10+ years of environmental chemical data from multiple laboratories, requiring select data validation in accordance with New Jersey Data of Known Quality Protocols and identifying areas of delineation from historic field information. Once identified, NJDEP designated groundwater, surface water, soil, sediment, soil vapor, and custom screening criteria were researched and applied to each area, requiring individualized flagging for reporting.*
- Prepared the New Jersey Data of Known Quality Protocol Data Usability Evaluation and managed the database for a confidential client for a data set greater than 20 years old. A DUE or any validation effort was not prepared in the 20 years prior to current. This included data from variations of methods for volatile organic compounds, semivolatile organic compounds, total and dissolved metals, pesticides, herbicides, natural attenuation parameters, and per- and polyfluoroalkyl substances in multiple media.*
- Performed 200+ Stage 2a validations for a combined 87-acre USEPA designated Corrective Action site under the Resource Conservation and Recovery Act, including a quick-turn USEPA required PCB by soxhlet extraction investigation across multiple plants. Once a former train car painting facility, USEPA required a quick-turn PCB by soxhlet extraction soil investigation.
- Preparation of a quality assurance program for a confidential client in West Virginia. A quick turn QAPP was prepared in a service location new to the consultant, resulting in research into state requirements for data usability and auditing newly employed laboratories. The QAPP was understood to be prepared for groundwater only, but the client did not reveal the need for sediment and soil. Two QAPPs were submitted for review to governing agencies.*
- Used statistical software to determine a localized background upper confidence limit of chromium for a confidential client's sand and gravel site. Validation was used to confirm laboratory procedures, and data was used in ProUCL calculations to compare to researched background chromium levels for Pennsylvania soils. *
- Prepared daily perimeter dust and air monitoring summaries and validation of low level mirex data for a confidential client's superfund site. Low level mirex data was generated by university laboratories and subject to validation following national functional guidelines to aide in river clean-up, including sediment, surface water, and treatment system water matrices.*

**Project completed prior to employment at LANGAN.*

MARLENA JEWETT

DATA ANALYST

CAD/GIS

1 year in the industry

Education

B.A., Environmental Economics
Colgate University

Work History

Equitable Advisors
Financial Advisor
9/7/2020-4/23/2021

Langan
Data Analyst
5/10/2021 – Present

Proposed Title: Field Technician

Ms. Jewett is a data analyst with experience in database design, management and visualization using EarthSoft's EQuIS™ database in support of environmental site characterizations for sites regulated under federal and state compliance programs. Her expertise includes integration of analytical databases and coordination with GIS users.

In her current role Marlena assists project teams with planning and implementation of project databases and data visualization. This includes coordinating with field staff and laboratories to define, workflows, SOPs and ensure the receipt of the proper deliverables for field and lab data; reviewing and managing project data and information using EQuIS™, Microsoft® Access, and Excel; generating data reports including tables, graphs, charts, and GIS compatible files; and generating and reviewing electronic data deliverables following project or agency specific formats.

SELECTED PROJECTS

EQuIS Management and NYSDEC deliverables – Data Analyst. Loaded and maintained soil, groundwater, and soil vapor data in an EQuIS database for a remedial investigation and waste characterizations of New York State Department of Environmental Conservation (NYSDEC) Brownfield Cleanup Program (BCP), NYC Office of Environmental Remediation (OER), and due diligence sites. Provided final report deliverables including sample summaries; tags; and exceedance summary exports from EQuIS. Completed this work for the following projects:

- **2-8 Main Street**
- **28-90 Review Avenue**
- **34-15 10th Street**
- **37-11 30th Street**
- **44-01 Northern Boulevard**
- **45 Commercial Avenue**
- **50 Jersey Avenue**
- **111 Willow Street**
- **118 West 13th Street**
- **122 Fifth Avenue**
- **155 Third Street**
- **160 East 125th Street**
- **210 Clarkson Avenue**
- **241 West 28th Street**
- **266 West 96th Street**
- **445 Gerard Avenue**
- **475 Bay Street and 31 Wave Street**

- **495 Peninsula Boulevard**
- **561 Greenwich Street**
- **563 Sackett Street**
- **805-825 Atlantic Avenue**
- **1525 Bedford Avenue**
- **2455 Third Avenue**
- **4650 Broadway**
- **ABC Block 27**
- **Bay Crane**
- **Broome Street**
- **Former Grant Hardware**
- **Forsyth and Delancy Street**
- **Gowanus Canal Northside**
- **Greenpoint Landing E1**
- **Greenpoint Landing Parcel H3**
- **John Evans**
- **Kissena Boulevard**
- **NYCHA Farragut**
- **Remeeder**

ASHLEY SANDVE

PROJECT ENGINEER

ENVIRONMENTAL ENGINEERING

Ms. Sandve's 9 years of experience includes field work and office work on environmental investigation and remediation projects. Her field work experience includes soil, soil vapor, indoor air and groundwater sampling; drilling oversight; air monitoring; soil management; and remediation oversight, including excavation and off-site soil disposal. Her office work experience includes environmental site background research, state environmental database research, EQuIS database management, data evaluation, remedial design, and report work, including, but not limited to, Phase I ESAs, Preliminary Assessment/Site Investigations, Spill Closure Reports, Remedial Investigation Reports, Remedial Action Work Plans, and Remedial Action Reports. Ms. Sandve is proficient in excel and database management and has ample experience researching sites through the online NJDEP and NYSDEC portals.

EDUCATION

M.Eng, Environmental Engineering
Stevens Institute of Technology

B.E., Environmental Engineering
Stevens Institute of Technology

PROFESSIONAL REGISTRATION

40 Hour HAZWOPER

OSHA 29 CFR 1910.120 Certification (HAZWOPER)

SELECTED PROJECTS

- 1 MacDonough Street, Brooklyn, NY
- 1 Nassau Place, Staten Island, NY
- 1 Washington Avenue, Fairfield, NJ
- 10 Godwin Avenue, Ridgewood, NJ
- 100 Jefferson Road, Parsippany, NJ
- 1011 Washington Avenue, Bronx, NY
- 1075 First Avenue, King of Prussia, PA
- 110 First Street, Jersey City, NJ
- 119 Division Avenue, Brooklyn, NY
- 12 West 48th Street, Phase II Environmental Investigation, New York, NY
- 1203 East New York Avenue, Brooklyn, NY
- 125 Greenbush Road, Soil and Groundwater Investigation, Orangeburg, NY
- 125 West End Avenue, New York, NY
- 138 Bruckner Boulevard, Bronx, NY
- 14-16 Burma Road, Jersey City, NJ
- 147-171 King Street, Brooklyn, NY
- 1487 First Avenue, New York, NY
- 150 52nd Street, Brooklyn, NY
- 1500 Harbor Boulevard, Weehawken, NJ
- 1538 Stillwell Avenue, NYCOER E-Designation and VCP Site Remediation, Bronx, NY
- 16 Court Street, Brooklyn, NY
- 160-186 Ease 22nd Street, Brooklyn, NY
- 16-63 Cody Avenue, Ridgewood, NY
- 171 River Road, Middlesex, NJ
- 174 Route 17 North, Rochelle Park, NJ
- 1921 Atlantic Avenue, NYSDEC BCP Site Remediation, Brooklyn, New York

ASHLEY SANDVE

- 2 Shore Lane, Jersey City, NJ
- 23-30 Borden Avenue, Long Island City, NY
- 239 10th Avenue, New York, NY
- 24-02 49th Avenue, New York, NY
- 2447 Third Avenue, Bronx, NY
- 28-90 Review Avenue, NYSDEC BCP Site Remediation, Queens, NY
- 29 Country Road, Tenafly, NJ
- 2924 8th Avenue, New York, NY
- 33-00 Northern Boulevard, Long Island City, NY
- 333 Johnson Avenue, Brooklyn, NY
- 363 Bond Street, Brooklyn, NY
- 384 Passaic Avenue, Fairfield, NJ
- 401 Washington Street, New York, NY
- 412 Greenwich Street, NYCOER E-Designation Remediation, New York, NY
- 425 Meadowlands Parkway, Secaucus, NJ
- 42-50 24th Street, Long Island City, NY
- 44 Whippany Road, Morristown, NJ
- 46 Crown Street, Brooklyn, NY
- 460 West 41st Street, New York, NY
- 479 Degraw Street, Brooklyn, NY
- 5055 Broadway, New York, NY
- 507 Osborn Street, Brooklyn, NY
- 507-511 West 19th Development, New York, NY
- 525 West 52nd Street, New York, NY
- 536-544 W. 26th Street Development, New York, NY
- 537 Columbia Street Development, Brooklyn, NY
- 540 West 26th Street, NYSDEC Spills Redevelopment, Remedial Action, New York, NY
- 550 Tenth Avenue, NYSDEC BCP Site Remediation, New York, NY
- 554 Old Water Works Road, Old Bridge, NJ
- 56 7th Avenue, New York, NY
- 60 East 9th Street, New York, NY
- 68 Charlton Street, NYCOER E-Designation Remediation, New York, NY
- 72 Caton Place, New York, NY
- 724 Park Place, Long Beach, NY
- 740 8th Avenue, New York, NY
- 75 Park Lane South, Jersey City, NJ
- 95 Worth Street, New York, NY
- Avalon Bay Portfolio, New York, NY
- Baker Center Redevelopment, Elizabeth, NJ
- Belleville Logistics Center, Belleville, NJ
- Bright Horizons, Preliminary Assessment and Site Investigation, Roseland, NJ
- Brixmor, Tinton Falls, NJ
- Brodson, Montville, NJ
- Broome Street Parking Lot Site, NYSDEC BCP Site Remediation, New York, NY
- Bryant Street, Brooklyn, NY
- CareOne, East Brunswick, NJ
- Carlyle Residential Portfolio, Brooklyn & Queens, NY
- Centerton Square Retail Shopping Center, Mount Laurel, NJ

- Christian Cultural Center, Brooklyn, NY
- Con Edison 11th Avenue & 50th Street, New York, NY
- Former BMS Campus, Hopewell, NJ
- Former Chevron Site, Bayonne, NJ
- Former Flintkote Facility, East Rutherford, NJ
- Former Hess Terminal, Remediation Oversight, Edgewater, NJ
- Former Penick Corporation Facility RCRA Site, Data Management, Remedial Investigation, and Remedial Action, Montville, NJ
- Giralda Farms, Chatham, NJ
- Haddonfield Road, Cherry Hill, NJ
- Icon Riverwalk, Plainsboro, NJ
- International House, New York, NY
- Kehilath Jeshurun Synagogue, New York, NY
- Lincoln Equities, Piscataway, NJ
- Marble Collegiate Church Office Building, New York, NY
- Mobil, Raritan, NJ
- Newels Development, Bloomfield, NJ
- NJ Turnpike Interchange 8, Hightstown, NJ
- Norfolk Street Site, NYCOER E-Designation Remediation, New York, NY
- One Burma Road, Jersey City, NJ
- Pan Graphics, Garfield, NJ
- Paragon, Cherry Hill, NJ
- Park Slope Portfolio, Brooklyn, NY
- Phase I Environmental Site Assessments and Due Diligence Investigations, Various Sites, NJ and NY
- Queens Plaza Park, Long Island City, NY
- Randallstown Maryland, Windsor Mill, MD
- Realterm, 1538 Stillwell Avenue, Bronx, NY
- RonBet Portfolio, New York, NY
- Self Storage Facility, Far Rockaway, NY
- Seward Park, New York, NY
- Shops at Pennsville, Pennsville, NJ
- Simply Self-Storage, Glen Rock, NJ
- Somerset Corporate Center, Bridgewater, NJ
- Stop & Shop, Raritan, NJ
- Stop & Shop, Soil Vapor Intrusion Investigation, Emerson, NJ
- Suffolk Street, New York NY
- Sunset Industrial Park, Brooklyn, NY
- Surf Avenue, Brooklyn, NY
- Target, Riverdale, NJ
- The Ritz Plaza, New York, NY
- ThorLabs, Groundwater and Soil Vapor Intrusion Investigation, Andover, NJ
- Z+G Residential Portfolio, Multiple Locations, Brooklyn, NY

AMANDA FORSBURG, CHMM

SENIOR PROJECT SCIENTIST

BROWNFIELD REDEVELOPMENT, DUE DILIGENCE AND SITE INVESTIGATION, REMEDIAL ACTIONS

Ms. Forsburg has 14 years of experience primarily focused on providing environmental support to redevelopment sites within the metropolitan New York area. She has experience with projects in the New York State Department of Environmental Conservation (NYSDEC) Brownfield Cleanup Program (BCP) and Spill Programs, New York City Office of Environmental Remediation (NYCOER) E-Designated and New York City Voluntary Cleanup Program (VCP) sites, and New York City Department of Environmental Protection (NYCDEP) remediation sites. Her field experience includes implementation and management of all phases of environmental projects involving soil, groundwater, and soil vapor contamination including Phase I inspections, Phase II site investigations, Remedial Investigations, and Remedial Actions.

During her tenure at Langan, Ms. Forsburg's experience has included schematic-, design-, and construction-phase project team involvement on numerous large scale construction projects requiring multi-disciplinary coordination and collaboration across different Langan teams and offices.

SELECTED PROJECTS

- 101 Murray Street, New York, NY (NYSDEC Spill Site, Multi-discipline)
- 110 University Place, New York, NY (NYSDEC Spill Site, Multi-discipline)
- 138 Willoughby Street, Brooklyn, NY (NYCOER E-Designation Site, Multi-discipline)
- 180 East 125th Street, New York, NY (NYCOER E-Designation Site, Multi-discipline)
- 1905 Surf Avenue, Brooklyn, NY (NYCOER E-Designation Site, Multi-discipline)
- 1921 Atlantic Avenue, Brooklyn, NY (NYSDEC BCP Site)
- 225 East 39th Street, New York, NY (NYCDEP Remediation Site, Multi-Discipline)
- 23-30 Borden Avenue, Queens, NY (NYSDEC BCP Site, Multi-discipline)
- 28-90 Review Avenue, Queens, NY (NYSDEC BCP Site, Multi-discipline)
- 280 West 155th Street, New York, NY (NYSDEC BCP Site, Multi-discipline)
- 311 West 42nd Street, New York, NY (NYCOER E-Designation Site, Multi-discipline)
- 363 and 365 Bond Street, Brooklyn, NY (NYSDEC BCP Site, Multi-discipline)
- 400 Park Avenue South, New York, NY (NYCOER E-Designation and VCP Site)
- 412 Greenwich Street, New York, NY (NYCOER E-Designation Site, Multi-discipline)

EDUCATION

B.A., Environmental Studies
Bucknell University

B.A., Environmental Geology
Bucknell University

PROFESSIONAL REGISTRATION

Certified Hazardous Materials Manager (CHMM)

OSHA 29 CFR 1910.120 Certification (HAZWOPER)

AFFILIATIONS

New Jersey Society of Women Environmental Professionals (NJSWEP) - MetroNet Committee

Association of Environmental and Engineering Geologists

Professional Women in Construction

Urban Land Institute, Norther New Jersey Chapter - Women's Leadership Initiative Co-Chair

- 42-50 24th Street, Queens, NY (NYSDEC Spill Site, Multi-discipline)
- 460 West 41st Street, New York, NY (NYCOER E-Designation Site, Multi-discipline)
- 505 West 19th Street, New York, NY (NYCOER E-Designation Site, Multi-discipline)
- 508 West 24th Street, New York, NY (NYCOER E-Designation and VCP Site, Multi-discipline)
- 525 West 52nd Street, New York, NY (NYCOER E-Designation Site, Multi-discipline)
- 53 West 53rd Street (MoMA Expansion), New York, NY (NYCOER E-Designation Site, Multi-discipline)
- 54 Crown Street, Brooklyn, NY (NYCOER E-Designation and VCP Site, Multi-discipline)
- 540 West 26th Street, New York, NY (NYSDEC Spill Site, Multi-discipline)
- 550 Tenth Avenue, New York, NY (NYCOER E-Designation Site, Multi-discipline)
- 68 Charlton Street, New York, NY (NYCOER E-Designation Site, Multi-discipline)
- Broome Street Parking Lot Site, New York, NY (NYSDEC BCP Site, Multi-discipline)
- Marble Collegiate Church Office Building, New York, NY (Multi-discipline)
- Norfolk Street Site, New York, NY (NYCOER E-Designation Site, Multi-discipline)

Steven Ciambruschini, PG, LEP

Principal/Vice President
Environmental Site Assessments/Investigations, Brownfield Remediation, UST Management

33 years in the industry ~ 28 years with Langan

Mr. Ciambruschini has over 30 years of experience in hydrogeologic and environmental investigations including management of environmental and geotechnical investigations relating to petroleum and chlorinated solvent spill sites, underground storage tank sites, manufactured gas plant sites, landfills, wastewater treatment facilities and industrial/commercial sites. His experience includes managing environmental compliance audits, remedial investigation, pre-acquisition due diligence and permitting assessment, feasibility studies and design, construction and operation of complex innovative remediation systems to treat, contain and recover contaminated soil and groundwater. These projects are managed under various NJDEP, PADEP, NYDEC, NYCDEP and CTDEP programs. Mr. Ciambruschini provides consultation to a diverse group of clients including private developers, utilities, retail and industrial facilities and is expert in assessing remediation options and funding options under various state and federal grant, loan and tax reimbursement programs including Brownfield programs.

Selected Projects

- Brodson Property, Montville NJ, (RCRA, NJDEP ACO Cleanup)
- Carroll Gardens, Brooklyn, NY (NY Brownfield, EPA Superfund, OER E-designated Site)
- Con Edison Appendix B Spill Sites - Various Locations, NY
- Former MGP Site, Brooklyn, NY (VCP Site)
- Extell Development, Hudson Yards, New York, NY (NYC E-designated, NYS Brownfield Site)
- Pan Graphics, Bergen County, NJ (ISRA, LSRP)
- New Jersey Turnpike General Environmental Services Contract, Various Sites, NJ
- Liberty Science Center, Jersey City, NJ (EO 215)
- Blue Back Square, West Hartford, CT (UST, Transfer Act, Brownfield)
- Hershey, Act II Investigation (PA VCP)
- Hershey, Naugatuck, CT (CT Transfer Act)
- Halby Chemical Sites, Various Sites, DE (CERCLA)
- Unisys, Middletown CT, (CT Transfer Act, Brownfield)
- Ryder Rental, Various Sites in CT (CT Transfer Act)
- St. Marks Avenue, Brooklyn, NY (Vapor Mitigation)
- Pan Graphics, Lodi, NJ (Eco Risk Assessment, LSRP)

Education

M.S., Geology
Montclair State University

M.A., Environmental Science
Montclair University

B.S., Environmental Science
Cook College, Rutgers University

Professional Registration

Professional Geologist (PG) in NY, DE, KY

Licensed Environmental Professional (LEP) in CT

Underground Storage Tank License in NJ

Affiliations

National Ground Water Association

Association of Ground Water Scientists and Engineers

American Association of Petroleum Geologists

Environmental Professionals of Connecticut

American Bar Association (ABA)

LANGAN

ATTACHMENT B

Laboratory Reporting Limits and Method Detection Limits

LANGAN

ATTACHMENT B

Laboratory Reporting Limits and Method Detection Limits

Method	Matrix	Analyte	MDL	RL	Units
VOC					
EPA 8260C	Water	1,1,1,2-Tetrachloroethane	0.2	0.5	ug/L
EPA 8260C	Water	1,1,1-Trichloroethane	0.2	0.5	ug/L
EPA 8260C	Water	1,1,2,2-Tetrachloroethane	0.2	0.5	ug/L
EPA 8260C	Water	1,1,2-Trichloro-1,2,2-trifluoroethane (Freon 113)	0.2	0.5	ug/L
EPA 8260C	Water	1,1,2-Trichloroethane	0.2	0.5	ug/L
EPA 8260C	Water	1,1-Dichloroethane	0.2	0.5	ug/L
EPA 8260C	Water	1,1-Dichloroethylene	0.2	0.5	ug/L
EPA 8260C	Water	Bromochloromethane	0.2	0.5	ug/L
EPA 8260C	Water	1,2,3-Trichloropropane	0.2	0.5	ug/L
EPA 8260C	Water	1,2,4-Trichlorobenzene	0.2	0.5	ug/L
EPA 8260C	Water	1,2,4-Trimethylbenzene	0.2	0.5	ug/L
EPA 8260C	Water	1,2-Dibromo-3-chloropropane	0.2	0.5	ug/L
EPA 8260C	Water	1,2-Dibromoethane	0.2	0.5	ug/L
EPA 8260C	Water	1,2-Dichlorobenzene	0.2	0.5	ug/L
EPA 8260C	Water	1,2-Dichloroethane	0.2	0.5	ug/L
EPA 8260C	Water	1,2-Dichloropropane	0.2	0.5	ug/L
EPA 8260C	Water	1,3,5-Trimethylbenzene	0.2	0.5	ug/L
EPA 8260C	Water	1,3-Dichlorobenzene	0.2	0.5	ug/L
EPA 8260C	Water	1,4-Dichlorobenzene	0.2	0.5	ug/L
EPA 8260C	Water	Cyclohexane	0.2	0.5	ug/L
EPA 8260C	Water	2-Butanone	0.2	0.5	ug/L
EPA 8260C	Water	2-Hexanone	0.2	0.5	ug/L
EPA 8260C	Water	4-Methyl-2-pentanone	0.2	0.5	ug/L
EPA 8260C	Water	Acetone	1	2	ug/L
EPA 8260C	Water	Acrolein	0.2	0.5	ug/L
EPA 8260C	Water	Acrylonitrile	0.2	0.5	ug/L
EPA 8260C	Water	Benzene	0.2	0.5	ug/L
EPA 8260C	Water	Bromodichloromethane	0.2	0.5	ug/L
EPA 8260C	Water	Bromoform	0.2	0.5	ug/L

ATTACHMENT B

Laboratory Reporting Limits and Method Detection Limits

Method	Matrix	Analyte	MDL	RL	Units
		VOC			
EPA 8260C	Water	Bromomethane	0.2	0.5	ug/L
EPA 8260C	Water	Carbon disulfide	0.2	0.5	ug/L
EPA 8260C	Water	Carbon tetrachloride	0.2	0.5	ug/L
EPA 8260C	Water	Chlorobenzene	0.2	0.5	ug/L
EPA 8260C	Water	Chloroethane	0.2	0.5	ug/L
EPA 8260C	Water	Chloroform	0.2	0.5	ug/L
EPA 8260C	Water	Chloromethane	0.2	0.5	ug/L
EPA 8260C	Water	cis-1,2-Dichloroethylene	0.2	0.5	ug/L
EPA 8260C	Water	cis-1,3-Dichloropropylene	0.2	0.5	ug/L
EPA 8260C	Water	Dibromochloromethane	0.2	0.5	ug/L
EPA 8260C	Water	Dibromomethane	0.2	0.5	ug/L
EPA 8260C	Water	Dichlorodifluoromethane	0.2	0.5	ug/L
EPA 8260C	Water	Naphthalene	1	2	ug/L
EPA 8260C	Water	Ethyl Benzene	0.2	0.5	ug/L
EPA 8260C	Water	Methylcyclohexane	0.2	0.5	ug/L
EPA 8260C	Water	Hexachlorobutadiene	0.2	0.5	ug/L
EPA 8260C	Water	Isopropylbenzene	0.2	0.5	ug/L
EPA 8260C	Water	Methyl acetate	0.2	0.5	ug/L
EPA 8260C	Water	Methyl tert-butyl ether (MTBE)	0.2	0.5	ug/L
EPA 8260C	Water	Methylene chloride	1	2	ug/L
EPA 8260C	Water	n-Butylbenzene	0.2	0.5	ug/L
EPA 8260C	Water	n-Propylbenzene	0.2	0.5	ug/L
EPA 8260C	Water	o-Xylene	0.2	0.5	ug/L
EPA 8260C	Water	p- & m- Xylenes	0.5	1	ug/L
EPA 8260C	Water	1,2,3-Trichlorobenzene	0.2	0.5	ug/L
EPA 8260C	Water	p-Isopropyltoluene	0.2	0.5	ug/L
EPA 8260C	Water	sec-Butylbenzene	0.2	0.5	ug/L
EPA 8260C	Water	Styrene	0.2	0.5	ug/L
EPA 8260C	Water	tert-Butyl alcohol (TBA)	0.5	1	ug/L

ATTACHMENT B

Laboratory Reporting Limits and Method Detection Limits

Method	Matrix	Analyte	MDL	RL	Units
VOC					
EPA 8260C	Water	tert-Butylbenzene	0.2	0.5	ug/L
EPA 8260C	Water	Tetrachloroethylene	0.2	0.5	ug/L
EPA 8260C	Water	Toluene	0.2	0.5	ug/L
EPA 8260C	Water	trans-1,2-Dichloroethylene	0.2	0.5	ug/L
EPA 8260C	Water	trans-1,3-Dichloropropylene	0.2	0.5	ug/L
EPA 8260C	Water	Trichloroethylene	0.2	0.5	ug/L
EPA 8260C	Water	Trichlorofluoromethane	0.2	0.5	ug/L
EPA 8260C	Water	Vinyl Chloride	0.2	0.5	ug/L
EPA 8260C	Water	Xylenes, Total	0.6	1.5	ug/L

ATTACHMENT B

Laboratory Reporting Limits and Method Detection Limits

Method	Matrix	Analyte	MDL	RL	Units
SVOC					
EPA 8270D	Water	Acenaphthene	0.05	0.05	ug/L
EPA 8270D	Water	Acenaphthylene	0.05	0.05	ug/L
EPA 8270D	Water	Acetophenone	2.5	5	ug/L
EPA 8270D	Water	Aniline	2.5	5	ug/L
EPA 8270D	Water	Anthracene	0.05	0.05	ug/L
EPA 8270D	Water	Atrazine	0.5	0.5	ug/L
EPA 8270D	Water	Benzaldehyde	2.5	5	ug/L
EPA 8270D	Water	Benzidine	10	20	ug/L
EPA 8270D	Water	Benzo(a)anthracene	0.05	0.05	ug/L
EPA 8270D	Water	Benzo(a)pyrene	0.05	0.05	ug/L
EPA 8270D	Water	Benzo(b)fluoranthene	0.05	0.05	ug/L
EPA 8270D	Water	Benzo(g,h,i)perylene	0.05	0.05	ug/L
EPA 8270D	Water	Benzoic acid	25	50	ug/L
EPA 8270D	Water	Benzo(k)fluoranthene	0.05	0.05	ug/L
EPA 8270D	Water	Benzyl alcohol	2.5	5	ug/L
EPA 8270D	Water	Benzyl butyl phthalate	2.5	5	ug/L
EPA 8270D	Water	1,1'-Biphenyl	2.5	5	ug/L
EPA 8270D	Water	4-Bromophenyl phenyl ether	2.5	5	ug/L
EPA 8270D	Water	Caprolactam	2.5	5	ug/L
EPA 8270D	Water	Carbazole	2.5	5	ug/L
EPA 8270D	Water	4-Chloro-3-methylphenol	2.5	5	ug/L
EPA 8270D	Water	4-Chloroaniline	2.5	5	ug/L
EPA 8270D	Water	Bis(2-chloroethoxy)methane	2.5	5	ug/L
EPA 8270D	Water	Bis(2-chloroethyl)ether	2.5	5	ug/L
EPA 8270D	Water	Bis(2-chloroisopropyl)ether	2.5	5	ug/L
EPA 8270D	Water	2-Chloronaphthalene	2.5	5	ug/L
EPA 8270D	Water	2-Chlorophenol	2.5	5	ug/L
EPA 8270D	Water	4-Chlorophenyl phenyl ether	2.5	5	ug/L
EPA 8270D	Water	Chrysene	0.05	0.05	ug/L

ATTACHMENT B

Laboratory Reporting Limits and Method Detection Limits

Method	Matrix	Analyte	MDL	RL	Units
SVOC					
EPA 8270D	Water	Dibenzo(a,h)anthracene	0.05	0.05	ug/L
EPA 8270D	Water	Dibenzofuran	2.5	5	ug/L
EPA 8270D	Water	Di-n-butyl phthalate	2.5	5	ug/L
EPA 8270D	Water	1,4-Dichlorobenzene	2.5	5	ug/L
EPA 8270D	Water	1,2-Dichlorobenzene	2.5	5	ug/L
EPA 8270D	Water	1,3-Dichlorobenzene	2.5	5	ug/L
EPA 8270D	Water	3,3'-Dichlorobenzidine	2.5	5	ug/L
EPA 8270D	Water	2,4-Dichlorophenol	2.5	5	ug/L
EPA 8270D	Water	Diethyl phthalate	2.5	5	ug/L
EPA 8270D	Water	2,4-Dimethylphenol	2.5	5	ug/L
EPA 8270D	Water	Dimethyl phthalate	2.5	5	ug/L
EPA 8270D	Water	4,6-Dinitro-2-methylphenol	2.5	5	ug/L
EPA 8270D	Water	2,4-Dinitrophenol	2.5	5	ug/L
EPA 8270D	Water	2,4-Dinitrotoluene	2.5	5	ug/L
EPA 8270D	Water	2,6-Dinitrotoluene	2.5	5	ug/L
EPA 8270D	Water	Di-n-octyl phthalate	2.5	5	ug/L
EPA 8270 SIM	Water	1,4-Dioxane	0.2	0.4	ug/L
EPA 8270D	Water	1,2-Diphenylhydrazine (as Azobenzene)	2.5	5	ug/L
EPA 8270D	Water	Bis(2-ethylhexyl)phthalate	0.5	0.5	ug/L
EPA 8270D	Water	Fluoranthene	0.05	0.05	ug/L
EPA 8270D	Water	Fluorene	0.05	0.05	ug/L
EPA 8270D	Water	Hexachlorobenzene	0.02	0.02	ug/L
EPA 8270D	Water	Hexachlorobutadiene	0.5	0.5	ug/L
EPA 8270D	Water	Hexachlorocyclopentadiene	2.5	5	ug/L
EPA 8270D	Water	Hexachloroethane	0.5	0.5	ug/L
EPA 8270D	Water	Indeno(1,2,3-cd)pyrene	0.05	0.05	ug/L
EPA 8270D	Water	Isophorone	2.5	5	ug/L
EPA 8270D	Water	2-Methylnaphthalene	2.5	5	ug/L
EPA 8270D	Water	2-Methylphenol	2.5	5	ug/L

ATTACHMENT B

Laboratory Reporting Limits and Method Detection Limits

Method	Matrix	Analyte	MDL	RL	Units
SVOC					
EPA 8270D	Water	3- & 4-Methylphenols	2.5	5	ug/L
EPA 8270D	Water	Naphthalene	0.05	0.05	ug/L
EPA 8270D	Water	3-Nitroaniline	2.5	5	ug/L
EPA 8270D	Water	4-Nitroaniline	2.5	5	ug/L
EPA 8270D	Water	2-Nitroaniline	2.5	5	ug/L
EPA 8270D	Water	Nitrobenzene	0.25	0.25	ug/L
EPA 8270D	Water	4-Nitrophenol	2.5	5	ug/L
EPA 8270D	Water	2-Nitrophenol	2.5	5	ug/L
EPA 8270D	Water	N-nitroso-di-n-propylamine	2.5	5	ug/L
EPA 8270D	Water	N-Nitrosodimethylamine	0.5	0.5	ug/L
EPA 8270D	Water	N-Nitrosodiphenylamine	2.5	5	ug/L
EPA 8270D	Water	Pentachlorophenol	0.25	0.25	ug/L
EPA 8270D	Water	Phenanthrene	0.05	0.05	ug/L
EPA 8270D	Water	Phenol	2.5	5	ug/L
EPA 8270D	Water	Pyrene	0.05	0.05	ug/L
EPA 8270D	Water	Pyridine	2.5	5	ug/L
EPA 8270D	Water	1,2,4,5-Tetrachlorobenzene	2.5	5	ug/L
EPA 8270D	Water	2,3,4,6-Tetrachlorophenol	2.5	5	ug/L
EPA 8270D	Water	1,2,4-Trichlorobenzene	2.5	5	ug/L
EPA 8270D	Water	2,4,6-Trichlorophenol	2.5	5	ug/L
EPA 8270D	Water	2,4,5-Trichlorophenol	2.5	5	ug/L

ATTACHMENT B

Laboratory Reporting Limits and Method Detection Limits

Method	Matrix	Analyte	MDL	RL	Units
Pesticides					
EPA 8081B	Water	Aldrin	0.004	0.004	ug/L
EPA 8081B	Water	alpha-BHC	0.004	0.004	ug/L
EPA 8081B	Water	beta-BHC	0.004	0.004	ug/L
EPA 8081B	Water	delta-BHC	0.004	0.004	ug/L
EPA 8081B	Water	gamma-BHC (Lindane)	0.004	0.004	ug/L
EPA 8081B	Water	gamma-Chlordane	0.01	0.01	ug/L
EPA 8081B	Water	alpha-Chlordane	0.004	0.004	ug/L
EPA 8081B	Water	Chlordane, total	0.04	0.04	ug/L
EPA 8081B	Water	4,4'-DDD	0.004	0.004	ug/L
EPA 8081B	Water	4,4'-DDE	0.004	0.004	ug/L
EPA 8081B	Water	4,4'-DDT	0.004	0.004	ug/L
EPA 8081B	Water	Dieldrin	0.002	0.002	ug/L
EPA 8081B	Water	Endosulfan I	0.004	0.004	ug/L
EPA 8081B	Water	Endosulfan II	0.004	0.004	ug/L
EPA 8081B	Water	Endosulfan sulfate	0.004	0.004	ug/L
EPA 8081B	Water	Endrin	0.004	0.004	ug/L
EPA 8081B	Water	Endrin aldehyde	0.01	0.01	ug/L
EPA 8081B	Water	Endrin ketone	0.01	0.01	ug/L
EPA 8081B	Water	Heptachlor	0.004	0.004	ug/L
EPA 8081B	Water	Heptachlor epoxide	0.004	0.004	ug/L
EPA 8081B	Water	Methoxychlor	0.004	0.004	ug/L
EPA 8081B	Water	Toxaphene	0.1	0.1	ug/L

ATTACHMENT B

Laboratory Reporting Limits and Method Detection Limits

Method	Matrix	Analyte	MDL	RL	Units
PCBs					
EPA 8082A	Water	Aroclor 1016	0.05	0.05	ug/L
EPA 8082A	Water	Aroclor 1221	0.05	0.05	ug/L
EPA 8082A	Water	Aroclor 1232	0.05	0.05	ug/L
EPA 8082A	Water	Aroclor 1242	0.05	0.05	ug/L
EPA 8082A	Water	Aroclor 1248	0.05	0.05	ug/L
EPA 8082A	Water	Aroclor 1254	0.05	0.05	ug/L
EPA 8082A	Water	Aroclor 1260	0.05	0.05	ug/L
EPA 8082A	Water	Aroclor 1262	0.05	0.05	ug/L
EPA 8082A	Water	Aroclor 1268	0.05	0.05	ug/L
EPA 8082A	Water	Total PCBs	0.05	0.05	ug/L

ATTACHMENT B

Laboratory Reporting Limits and Method Detection Limits

Method	Matrix	Analyte	MDL	RL	Units
Metals					
EPA 6010C	Water	Aluminum	0.01	0.01	mg/L
EPA 6010C	Water	Antimony	0.005	0.005	mg/L
EPA 6010C	Water	Arsenic	0.004	0.004	mg/L
EPA 6010C	Water	Barium	0.01	0.01	mg/L
EPA 6010C	Water	Beryllium	0.001	0.001	mg/L
EPA 6010C	Water	Cadmium	0.003	0.003	mg/L
EPA 6010C	Water	Calcium	0.05	0.05	mg/L
EPA 6010C	Water	Chromium	0.005	0.005	mg/L
EPA 6010C	Water	Cobalt	0.005	0.005	mg/L
EPA 6010C	Water	Copper	0.003	0.003	mg/L
EPA 6010C	Water	Iron	0.02	0.02	mg/L
EPA 6010C	Water	Lead	0.003	0.003	mg/L
EPA 6010C	Water	Magnesium	0.05	0.05	mg/L
EPA 6010C	Water	Manganese	0.005	0.005	mg/L
EPA 7473	Water	Mercury	0.002	0.002	mg/L
EPA 6010C	Water	Nickel	0.005	0.005	mg/L
EPA 6010C	Water	Potassium	0.05	0.05	mg/L
EPA 6010C	Water	Selenium	0.01	0.01	mg/L
EPA 6010C	Water	Silver	0.005	0.005	mg/L
EPA 6010C	Water	Sodium	0.1	0.1	mg/L
EPA 6010C	Water	Thallium	0.005	0.005	mg/L
EPA 6010C	Water	Vanadium	0.01	0.01	mg/L
EPA 6010C	Water	Zinc	0.01	0.01	mg/L

ATTACHMENT B

Laboratory Reporting Limits and Method Detection Limits

Method	Matrix	Analyte	MDL	RL	Units
PFAS					
Modified EPA 537	Water	Perfluorobutanesulfonic acid (PFBS)	0.294	2	ng/L
Modified EPA 537	Water	Perfluorohexanoic acid (PFHxA)	0.471	2	ng/L
Modified EPA 537	Water	Perfluoroheptanoic acid (PFHpA)	0.635	2	ng/L
Modified EPA 537	Water	Perfluorohexanesulfonic acid (PFHxS)	0.281	2	ng/L
Modified EPA 537	Water	Perfluorooctanoic acid (PFOA)	0.531	2	ng/L
Modified EPA 537	Water	Perfluorooctanesulfonic acid (PFOS)	0.292	2	ng/L
Modified EPA 537	Water	Perfluorononanoic acid (PFNA)	0.574	2	ng/L
Modified EPA 537	Water	Perfluorodecanoic acid (PFDA)	0.524	2	ng/L
Modified EPA 537	Water	Perfluoroundecanoic acid (PFUnA)	0.657	2	ng/L
Modified EPA 537	Water	Perfluorododecanoic acid (PFDoA)	0.777	2	ng/L
Modified EPA 537	Water	Perfluorotridecanoic acid (PFTrDA)	1.37	2	ng/L
Modified EPA 537	Water	Perfluorotetradecanoic acid (PFTA)	0.531	2	ng/L
Modified EPA 537	Water	N-MeFOSAA	0.529	2	ng/L
Modified EPA 537	Water	N-EtFOSAA	0.557	2	ng/L
Modified EPA 537	Water	Perfluoropentanoic acid (PFPeA)	0.452	2	ng/L
Modified EPA 537	Water	Perfluoro-1-octanesulfonamide (FOSA)	0.296	2	ng/L
Modified EPA 537	Water	Perfluoro-1-heptanesulfonic acid (PFHpS)	0.415	2	ng/L
Modified EPA 537	Water	Perfluoro-1-decanesulfonic acid (PFDS)	0.574	2	ng/L
Modified EPA 537	Water	1H,1H,2H,2H-Perfluorooctanesulfonic acid (6:2 FTS)	0.492	5	ng/L
Modified EPA 537	Water	1H,1H,2H,2H-Perfluorodecanesulfonic acid (8:2 FTS)	0.399	2	ng/L
Modified EPA 537	Water	Perfluoro-n-butanoic acid (PFBA)	1.63	2	ng/L

Notes

* = The contract labs has indicated that they are not able to achieve the reporting limits of 2 ng/L for 1H,1H,2H,2H-Perfluorooctanesulfonic acid (6:2 FTS). Site specific decisions will need to be made by the DEC project manager in consultation with the DEC remedial program chemist

ATTACHMENT B

Laboratory Reporting Limits and Method Detection Limits

Method	Matrix	Analyte	MDL	RL	Units
VOC					
EPA 8260C	Soil	1,1,1,2-Tetrachloroethane	2.5	5	ug/kg
EPA 8260C	Soil	1,1,1-Trichloroethane	2.5	5	ug/kg
EPA 8260C	Soil	1,1,2,2-Tetrachloroethane	2.5	5	ug/kg
EPA 8260C	Soil	1,1,2-Trichloro-1,2,2-trifluoroethane (Freon 113)	2.5	5	ug/kg
EPA 8260C	Soil	1,1,2-Trichloroethane	2.5	5	ug/kg
EPA 8260C	Soil	1,1-Dichloroethane	2.5	5	ug/kg
EPA 8260C	Soil	1,1-Dichloroethylene	2.5	5	ug/kg
EPA 8260C	Soil	Bromochloromethane	2.5	5	ug/kg
EPA 8260C	Soil	1,2,3-Trichloropropane	2.5	5	ug/kg
EPA 8260C	Soil	1,2,4-Trichlorobenzene	2.5	5	ug/kg
EPA 8260C	Soil	1,2,4-Trimethylbenzene	2.5	5	ug/kg
EPA 8260C	Soil	1,2-Dibromo-3-chloropropane	2.5	5	ug/kg
EPA 8260C	Soil	1,2-Dibromoethane	2.5	5	ug/kg
EPA 8260C	Soil	1,2-Dichlorobenzene	2.5	5	ug/kg
EPA 8260C	Soil	1,2-Dichloroethane	2.5	5	ug/kg
EPA 8260C	Soil	1,2-Dichloropropane	2.5	5	ug/kg
EPA 8260C	Soil	1,3,5-Trimethylbenzene	2.5	5	ug/kg
EPA 8260C	Soil	1,3-Dichlorobenzene	2.5	5	ug/kg
EPA 8260C	Soil	1,4-Dichlorobenzene	2.5	5	ug/kg
EPA 8260C	Soil	1,4-Dioxane	10	10	ug/kg
EPA 8260C	Soil	Cyclohexane	2.5	5	ug/kg
EPA 8260C	Soil	2-Butanone	2.5	5	ug/kg
EPA 8260C	Soil	2-Hexanone	2.5	5	ug/kg
EPA 8260C	Soil	4-Methyl-2-pentanone	2.5	5	ug/kg
EPA 8260C	Soil	Acetone	5	10	ug/kg
EPA 8260C	Soil	Acrolein	5	10	ug/kg
EPA 8260C	Soil	Acrylonitrile	2.5	5	ug/kg
EPA 8260C	Soil	Benzene	2.5	5	ug/kg
EPA 8260C	Soil	Bromodichloromethane	2.5	5	ug/kg

ATTACHMENT B

Laboratory Reporting Limits and Method Detection Limits

Method	Matrix	Analyte	MDL	RL	Units
VOC					
EPA 8260C	Soil	Bromoform	2.5	5	ug/kg
EPA 8260C	Soil	Bromomethane	2.5	5	ug/kg
EPA 8260C	Soil	Carbon disulfide	2.5	5	ug/kg
EPA 8260C	Soil	Carbon tetrachloride	2.5	5	ug/kg
EPA 8260C	Soil	Chlorobenzene	2.5	5	ug/kg
EPA 8260C	Soil	Chloroethane	2.5	5	ug/kg
EPA 8260C	Soil	Chloroform	2.5	5	ug/kg
EPA 8260C	Soil	Chloromethane	2.5	5	ug/kg
EPA 8260C	Soil	cis-1,2-Dichloroethylene	2.5	5	ug/kg
EPA 8260C	Soil	cis-1,3-Dichloropropylene	2.5	5	ug/kg
EPA 8260C	Soil	Dibromochloromethane	2.5	5	ug/kg
EPA 8260C	Soil	Dibromomethane	2.5	5	ug/kg
EPA 8260C	Soil	Dichlorodifluoromethane	2.5	5	ug/kg
EPA 8260C	Soil	Naphthalene	2.5	10	ug/kg
EPA 8260C	Soil	Ethyl Benzene	2.5	5	ug/kg
EPA 8260C	Soil	Methylcyclohexane	2.5	5	ug/kg
EPA 8260C	Soil	Hexachlorobutadiene	2.5	5	ug/kg
EPA 8260C	Soil	Isopropylbenzene	2.5	5	ug/kg
EPA 8260C	Soil	Methyl acetate	2.5	5	ug/kg
EPA 8260C	Soil	Methyl tert-butyl ether (MTBE)	2.5	5	ug/kg
EPA 8260C	Soil	Methylene chloride	5	10	ug/kg
EPA 8260C	Soil	n-Butylbenzene	2.5	5	ug/kg
EPA 8260C	Soil	n-Propylbenzene	2.5	5	ug/kg
EPA 8260C	Soil	1,2,3-Trichlorobenzene	2.5	5	ug/kg
EPA 8260C	Soil	o-Xylene	2.5	5	ug/kg
EPA 8260C	Soil	p- & m- Xylenes	5	10	ug/kg
EPA 8260C	Soil	p-Isopropyltoluene	2.5	5	ug/kg
EPA 8260C	Soil	sec-Butylbenzene	2.5	5	ug/kg
EPA 8260C	Soil	Styrene	2.5	5	ug/kg

ATTACHMENT B

Laboratory Reporting Limits and Method Detection Limits

Method	Matrix	Analyte	MDL	RL	Units
VOC					
EPA 8260C	Soil	tert-Butyl alcohol (TBA)	2.5	5	ug/kg
EPA 8260C	Soil	tert-Butylbenzene	2.5	5	ug/kg
EPA 8260C	Soil	Tetrachloroethylene	2.5	5	ug/kg
EPA 8260C	Soil	Toluene	2.5	5	ug/kg
EPA 8260C	Soil	trans-1,2-Dichloroethylene	2.5	5	ug/kg
EPA 8260C	Soil	trans-1,3-Dichloropropylene	2.5	5	ug/kg
EPA 8260C	Soil	Trichloroethylene	2.5	5	ug/kg
EPA 8260C	Soil	Trichlorofluoromethane	2.5	5	ug/kg
EPA 8260C	Soil	Vinyl Chloride	2.5	5	ug/kg
EPA 8260C	Soil	Xylenes, Total	7.5	15	ug/kg

ATTACHMENT B

Laboratory Reporting Limits and Method Detection Limits

Method	Matrix	Analyte	MDL	RL	Units
TCLP VOC					
EPA 8260C/1311	Soil	1,1,1,2-Tetrachloroethane	2.5	5.0	ug/L
EPA 8260C/1311	Soil	1,1,1-Trichloroethane	2.5	5.0	ug/L
EPA 8260C/1311	Soil	1,1,2,2-Tetrachloroethane	2.5	5.0	ug/L
EPA 8260C/1311	Soil	1,1,2-Trichloro-1,2,2-trifluoroethane (Freon 113)	2.5	5.0	ug/L
EPA 8260C/1311	Soil	1,1,2-Trichloroethane	2.5	5.0	ug/L
EPA 8260C/1311	Soil	1,1-Dichloroethane	2.5	5.0	ug/L
EPA 8260C/1311	Soil	1,1-Dichloroethylene	2.5	5.0	ug/L
EPA 8260C/1311	Soil	1,1-Dichloropropylene	2.5	5.0	ug/L
EPA 8260C/1311	Soil	1,2,3-Trichlorobenzene	2.5	5.0	ug/L
EPA 8260C/1311	Soil	1,2,3-Trichloropropane	2.5	5.0	ug/L
EPA 8260C/1311	Soil	1,2,4,5-Tetramethylbenzene	2.5	5.0	ug/L
EPA 8260C/1311	Soil	1,2,4-Trichlorobenzene	2.5	5.0	ug/L
EPA 8260C/1311	Soil	1,2,4-Trimethylbenzene	2.5	5.0	ug/L
EPA 8260C/1311	Soil	1,2-Dibromo-3-chloropropane	2.5	5.0	ug/L
EPA 8260C/1311	Soil	1,2-Dibromoethane	2.5	5.0	ug/L
EPA 8260C/1311	Soil	1,2-Dichlorobenzene	2.5	5.0	ug/L
EPA 8260C/1311	Soil	1,2-Dichloroethane	2.5	5.0	ug/L
EPA 8260C/1311	Soil	1,2-Dichloropropane	2.5	5.0	ug/L
EPA 8260C/1311	Soil	1,3,5-Trimethylbenzene	2.5	5.0	ug/L
EPA 8260C/1311	Soil	1,3-Dichlorobenzene	2.5	5.0	ug/L
EPA 8260C/1311	Soil	1,3-Dichloropropane	2.5	5.0	ug/L
EPA 8260C/1311	Soil	1,4-Dichlorobenzene	2.5	5.0	ug/L
EPA 8260C/1311	Soil	2,2-Dichloropropane	2.5	5.0	ug/L
EPA 8260C/1311	Soil	2-Butanone	2.5	5.0	ug/L
EPA 8260C/1311	Soil	2-Chloroethylvinyl ether	10	20	ug/L
EPA 8260C/1311	Soil	2-Chlorotoluene	2.5	5.0	ug/L
EPA 8260C/1311	Soil	2-Hexanone	2.5	5.0	ug/L
EPA 8260C/1311	Soil	4-Chlorotoluene	2.5	5.0	ug/L
EPA 8260C/1311	Soil	4-Methyl-2-pentanone	2.5	5.0	ug/L

ATTACHMENT B

Laboratory Reporting Limits and Method Detection Limits

Method	Matrix	Analyte	MDL	RL	Units
TCLP VOC					
EPA 8260C/1311	Soil	Acetone	5.0	10	ug/L
EPA 8260C/1311	Soil	Benzene	2.5	5.0	ug/L
EPA 8260C/1311	Soil	Bromobenzene	2.5	5.0	ug/L
EPA 8260C/1311	Soil	Bromochloromethane	2.5	5.0	ug/L
EPA 8260C/1311	Soil	Bromodichloromethane	2.5	5.0	ug/L
EPA 8260C/1311	Soil	Bromoform	2.5	5.0	ug/L
EPA 8260C/1311	Soil	4-Isopropyltoluene	2.1	5.0	ug/L
EPA 8260C/1311	Soil	Bromomethane	2.5	5.0	ug/L
EPA 8260C/1311	Soil	Carbon disulfide	2.5	5.0	ug/L
EPA 8260C/1311	Soil	Carbon tetrachloride	2.5	5.0	ug/L
EPA 8260C/1311	Soil	Chlorobenzene	2.5	5.0	ug/L
EPA 8260C/1311	Soil	Chloroethane	2.5	5.0	ug/L
EPA 8260C/1311	Soil	Chloroform	2.5	5.0	ug/L
EPA 8260C/1311	Soil	Chloromethane	2.5	5.0	ug/L
EPA 8260C/1311	Soil	cis-1,2-Dichloroethylene	2.5	5.0	ug/L
EPA 8260C/1311	Soil	cis-1,3-Dichloropropylene	2.5	5.0	ug/L
EPA 8260C/1311	Soil	Dibromochloromethane	2.5	5.0	ug/L
EPA 8260C/1311	Soil	Dibromomethane	2.5	5.0	ug/L
EPA 8260C/1311	Soil	Dichlorodifluoromethane	2.5	5.0	ug/L
EPA 8260C/1311	Soil	Ethyl Benzene	2.5	5.0	ug/L
EPA 8260C/1311	Soil	Hexachlorobutadiene	2.5	5.0	ug/L
EPA 8260C/1311	Soil	Isopropylbenzene	2.5	5.0	ug/L
EPA 8260C/1311	Soil	Methyl tert-butyl ether (MTBE)	2.5	5.0	ug/L
EPA 8260C/1311	Soil	Methylene chloride	2.5	10	ug/L
EPA 8260C/1311	Soil	Naphthalene	2.5	10	ug/L
EPA 8260C/1311	Soil	n-Butylbenzene	2.5	5.0	ug/L
EPA 8260C/1311	Soil	n-Propylbenzene	2.5	5.0	ug/L
EPA 8260C/1311	Soil	o-Xylene	2.5	5.0	ug/L
EPA 8260C/1311	Soil	p- & m- Xylenes	5.0	10	ug/L

ATTACHMENT B

Laboratory Reporting Limits and Method Detection Limits

Method	Matrix	Analyte	MDL	RL	Units
TCLP VOC					
EPA 8260C/1311	Soil	p-Diethylbenzene	2.5	5.0	ug/L
EPA 8260C/1311	Soil	p-Ethyltoluene	2.5	5.0	ug/L
EPA 8260C/1311	Soil	p-Isopropyltoluene	2.5	5.0	ug/L
EPA 8260C/1311	Soil	sec-Butylbenzene	2.5	5.0	ug/L
EPA 8260C/1311	Soil	Styrene	2.5	5.0	ug/L
EPA 8260C/1311	Soil	tert-Butylbenzene	2.5	5.0	ug/L
EPA 8260C/1311	Soil	Tetrachloroethylene	2.5	5.0	ug/L
EPA 8260C/1311	Soil	Toluene	2.5	5.0	ug/L
EPA 8260C/1311	Soil	trans-1,2-Dichloroethylene	2.5	5.0	ug/L
EPA 8260C/1311	Soil	trans-1,3-Dichloropropylene	2.5	5.0	ug/L
EPA 8260C/1311	Soil	Trichloroethylene	2.5	5.0	ug/L
EPA 8260C/1311	Soil	Trichlorofluoromethane	2.5	5.0	ug/L
EPA 8260C/1311	Soil	Vinyl Chloride	2.5	5.0	ug/L
EPA 8260C/1311	Soil	Xylenes, Total	7.5	15	ug/L

ATTACHMENT B

Laboratory Reporting Limits and Method Detection Limits

Method	Matrix	Analyte	MDL	RL	Units
SVOC					
EPA 8270D	Soil	Acenaphthene	20.9	41.7	ug/kg
EPA 8270D	Soil	Acenaphthylene	20.9	41.7	ug/kg
EPA 8270D	Soil	Acetophenone	20.9	41.7	ug/kg
EPA 8270D	Soil	Aniline	83.5	167	ug/kg
EPA 8270D	Soil	Anthracene	20.9	41.7	ug/kg
EPA 8270D	Soil	Atrazine	20.9	41.7	ug/kg
EPA 8270D	Soil	Benzaldehyde	20.9	41.7	ug/kg
EPA 8270D	Soil	Benzidine	83.5	167	ug/kg
EPA 8270D	Soil	Benzo(a)anthracene	20.9	41.7	ug/kg
EPA 8270D	Soil	Benzo(a)pyrene	20.9	41.7	ug/kg
EPA 8270D	Soil	Benzo(b)fluoranthene	20.9	41.7	ug/kg
EPA 8270D	Soil	Benzo(g,h,i)perylene	20.9	41.7	ug/kg
EPA 8270D	Soil	Benzoic acid	20.9	41.7	ug/kg
EPA 8270D	Soil	Benzo(k)fluoranthene	20.9	41.7	ug/kg
EPA 8270D	Soil	Benzyl alcohol	20.9	41.7	ug/kg
EPA 8270D	Soil	Benzyl butyl phthalate	20.9	41.7	ug/kg
EPA 8270D	Soil	1,1'-Biphenyl	20.9	41.7	ug/kg
EPA 8270D	Soil	4-Bromophenyl phenyl ether	20.9	41.7	ug/kg
EPA 8270D	Soil	Caprolactam	41.7	83.3	ug/kg
EPA 8270D	Soil	Carbazole	20.9	41.7	ug/kg
EPA 8270D	Soil	4-Chloro-3-methylphenol	20.9	41.7	ug/kg
EPA 8270D	Soil	4-Chloroaniline	20.9	41.7	ug/kg
EPA 8270D	Soil	Bis(2-chloroethoxy)methane	20.9	41.7	ug/kg
EPA 8270D	Soil	Bis(2-chloroethyl)ether	20.9	41.7	ug/kg
EPA 8270D	Soil	Bis(2-chloroisopropyl)ether	20.9	41.7	ug/kg
EPA 8270D	Soil	2-Chloronaphthalene	20.9	41.7	ug/kg
EPA 8270D	Soil	2-Chlorophenol	20.9	41.7	ug/kg
EPA 8270D	Soil	4-Chlorophenyl phenyl ether	20.9	41.7	ug/kg
EPA 8270D	Soil	Chrysene	20.9	41.7	ug/kg

ATTACHMENT B

Laboratory Reporting Limits and Method Detection Limits

Method	Matrix	Analyte	MDL	RL	Units
SVOC					
EPA 8270D	Soil	Dibenzo(a,h)anthracene	20.9	41.7	ug/kg
EPA 8270D	Soil	Dibenzofuran	20.9	41.7	ug/kg
EPA 8270D	Soil	Di-n-butyl phthalate	20.9	41.7	ug/kg
EPA 8270D	Soil	1,2-Dichlorobenzene	20.9	41.7	ug/kg
EPA 8270D	Soil	1,3-Dichlorobenzene	20.9	41.7	ug/kg
EPA 8270D	Soil	1,4-Dichlorobenzene	20.9	41.7	ug/kg
EPA 8270D	Soil	3,3'-Dichlorobenzidine	20.9	41.7	ug/kg
EPA 8270D	Soil	2,4-Dichlorophenol	20.9	41.7	ug/kg
EPA 8270D	Soil	Diethyl phthalate	20.9	41.7	ug/kg
EPA 8270D	Soil	2,4-Dimethylphenol	20.9	41.7	ug/kg
EPA 8270D	Soil	Dimethyl phthalate	20.9	41.7	ug/kg
EPA 8270D	Soil	4,6-Dinitro-2-methylphenol	41.7	83.3	ug/kg
EPA 8270D	Soil	2,4-Dinitrophenol	41.7	83.3	ug/kg
EPA 8270D	Soil	2,4-Dinitrotoluene	20.9	41.7	ug/kg
EPA 8270D	Soil	2,6-Dinitrotoluene	20.9	41.7	ug/kg
EPA 8270D	Soil	Di-n-octyl phthalate	20.9	41.7	ug/kg
EPA 8270D	Soil	1,2-Diphenylhydrazine (as Azobenzene)	20.9	41.7	ug/kg
EPA 8270D	Soil	Bis(2-ethylhexyl)phthalate	20.9	41.7	ug/kg
EPA 8270D	Soil	Fluoranthene	20.9	41.7	ug/kg
EPA 8270D	Soil	Fluorene	20.9	41.7	ug/kg
EPA 8270D	Soil	Hexachlorobenzene	20.9	41.7	ug/kg
EPA 8270D	Soil	Hexachlorobutadiene	20.9	41.7	ug/kg
EPA 8270D	Soil	Hexachlorocyclopentadiene	20.9	41.7	ug/kg
EPA 8270D	Soil	Hexachloroethane	20.9	41.7	ug/kg
EPA 8270D	Soil	Indeno(1,2,3-cd)pyrene	20.9	41.7	ug/kg
EPA 8270D	Soil	Isophorone	20.9	41.7	ug/kg
EPA 8270D	Soil	2-Methylnaphthalene	20.9	41.7	ug/kg
EPA 8270D	Soil	2-Methylphenol	20.9	41.7	ug/kg
EPA 8270D	Soil	3- & 4-Methylphenols	20.9	41.7	ug/kg

ATTACHMENT B

Laboratory Reporting Limits and Method Detection Limits

Method	Matrix	Analyte	MDL	RL	Units
SVOC					
EPA 8270D	Soil	Naphthalene	20.9	41.7	ug/kg
EPA 8270D	Soil	4-Nitroaniline	41.7	83.3	ug/kg
EPA 8270D	Soil	2-Nitroaniline	41.7	83.3	ug/kg
EPA 8270D	Soil	3-Nitroaniline	41.7	83.3	ug/kg
EPA 8270D	Soil	Nitrobenzene	20.9	41.7	ug/kg
EPA 8270D	Soil	2-Nitrophenol	20.9	41.7	ug/kg
EPA 8270D	Soil	4-Nitrophenol	41.7	83.3	ug/kg
EPA 8270D	Soil	N-nitroso-di-n-propylamine	20.9	41.7	ug/kg
EPA 8270D	Soil	N-Nitrosodimethylamine	20.9	41.7	ug/kg
EPA 8270D	Soil	N-Nitrosodiphenylamine	20.9	41.7	ug/kg
EPA 8270D	Soil	Pentachlorophenol	20.9	41.7	ug/kg
EPA 8270D	Soil	Phenanthrene	20.9	41.7	ug/kg
EPA 8270D	Soil	Phenol	20.9	41.7	ug/kg
EPA 8270D	Soil	Pyrene	20.9	41.7	ug/kg
EPA 8270D	Soil	Pyridine	83.5	167	ug/kg
EPA 8270D	Soil	1,2,4,5-Tetrachlorobenzene	41.7	83.3	ug/kg
EPA 8270D	Soil	2,3,4,6-Tetrachlorophenol	41.7	83.3	ug/kg
EPA 8270D	Soil	1,2,4-Trichlorobenzene	20.9	41.7	ug/kg
EPA 8270D	Soil	2,4,6-Trichlorophenol	20.9	41.7	ug/kg
EPA 8270D	Soil	2,4,5-Trichlorophenol	20.9	41.7	ug/kg

ATTACHMENT B

Laboratory Reporting Limits and Method Detection Limits

Method	Matrix	Analyte	MDL	RL	Units
TCLP SVOC					
EPA 8270D/1311	Soil	1,2,4-Trichlorobenzene	1.31	5.00	ug/L
EPA 8270D/1311	Soil	1,2-Dichlorobenzene	1.64	5.00	ug/L
EPA 8270D/1311	Soil	1,2-Diphenylhydrazine (as Azobenzene)	2.75	5.00	ug/L
EPA 8270D/1311	Soil	1,3-Dichlorobenzene	2.75	5.00	ug/L
EPA 8270D/1311	Soil	1,4-Dichlorobenzene	3.23	5.00	ug/L
EPA 8270D/1311	Soil	2,4,5-Trichlorophenol	3.61	5.00	ug/L
EPA 8270D/1311	Soil	2,4,6-Trichlorophenol	3.27	5.00	ug/L
EPA 8270D/1311	Soil	2,4-Dichlorophenol	3.09	5.00	ug/L
EPA 8270D/1311	Soil	2,4-Dimethylphenol	3.68	5.00	ug/L
EPA 8270D/1311	Soil	2,4-Dinitrophenol	9.60	10.0	ug/L
EPA 8270D/1311	Soil	2,4-Dinitrotoluene	2.37	5.00	ug/L
EPA 8270D/1311	Soil	2,6-Dinitrotoluene	3.51	5.00	ug/L
EPA 8270D/1311	Soil	2-Chloronaphthalene	3.49	5.00	ug/L
EPA 8270D/1311	Soil	2-Chlorophenol	3.42	5.00	ug/L
EPA 8270D/1311	Soil	2-Methylnaphthalene	3.07	5.00	ug/L
EPA 8270D/1311	Soil	2-Methylphenol	0.857	5.00	ug/L
EPA 8270D/1311	Soil	2-Nitroaniline	3.01	5.00	ug/L
EPA 8270D/1311	Soil	2-Nitrophenol	3.10	5.00	ug/L
EPA 8270D/1311	Soil	3- & 4-Methylphenols	3.72	5.00	ug/L
EPA 8270D/1311	Soil	3,3-Dichlorobenzidine	3.51	5.00	ug/L
EPA 8270D/1311	Soil	3-Nitroaniline	1.59	5.00	ug/L
EPA 8270D/1311	Soil	4,6-Dinitro-2-methylphenol	4.90	5.00	ug/L
EPA 8270D/1311	Soil	4-Bromophenyl phenyl ether	3.45	5.00	ug/L
EPA 8270D/1311	Soil	4-Chloro-3-methylphenol	3.63	5.00	ug/L
EPA 8270D/1311	Soil	4-Chloroaniline	3.74	5.00	ug/L
EPA 8270D/1311	Soil	4-Chlorophenyl phenyl ether	3.12	5.00	ug/L
EPA 8270D/1311	Soil	4-Nitroaniline	3.77	5.00	ug/L
EPA 8270D/1311	Soil	4-Nitrophenol	3.94	5.00	ug/L
EPA 8270D/1311	Soil	Acenaphthene	3.24	5.00	ug/L

ATTACHMENT B

Laboratory Reporting Limits and Method Detection Limits

Method	Matrix	Analyte	MDL	RL	Units
TCLP SVOC					
EPA 8270D/1311	Soil	Acenaphthylene	4.27	5.00	ug/L
EPA 8270D/1311	Soil	Aniline	1.97	5.00	ug/L
EPA 8270D/1311	Soil	Anthracene	3.66	5.00	ug/L
EPA 8270D/1311	Soil	Benzidine	3.62	5.00	ug/L
EPA 8270D/1311	Soil	Benzo(a)anthracene	4.07	5.00	ug/L
EPA 8270D/1311	Soil	Benzo(a)pyrene	4.85	5.00	ug/L
EPA 8270D/1311	Soil	Benzo(b)fluoranthene	4.12	5.00	ug/L
EPA 8270D/1311	Soil	Benzo(g,h,i)perylene	4.15	5.00	ug/L
EPA 8270D/1311	Soil	Benzo(k)fluoranthene	3.46	5.00	ug/L
EPA 8270D/1311	Soil	Benzoic acid	8.70	10.0	ug/L
EPA 8270D/1311	Soil	Benzyl alcohol	4.00	5.00	ug/L
EPA 8270D/1311	Soil	Benzyl butyl phthalate	2.30	5.00	ug/L
EPA 8270D/1311	Soil	Bis(2-chloroethoxy)methane	4.85	5.00	ug/L
EPA 8270D/1311	Soil	Bis(2-chloroethyl)ether	4.12	5.00	ug/L
EPA 8270D/1311	Soil	Bis(2-chloroisopropyl)ether	4.15	5.00	ug/L
EPA 8270D/1311	Soil	Bis(2-ethylhexyl)phthalate	2.57	5.00	ug/L
EPA 8270D/1311	Soil	Chrysene	4.15	5.00	ug/L
EPA 8270D/1311	Soil	Dibenzo(a,h)anthracene	3.10	5.00	ug/L
EPA 8270D/1311	Soil	Dibenzofuran	2.90	5.00	ug/L
EPA 8270D/1311	Soil	Diethyl phthalate	2.20	5.00	ug/L
EPA 8270D/1311	Soil	Dimethyl phthalate	4.85	5.00	ug/L
EPA 8270D/1311	Soil	Di-n-butyl phthalate	4.12	5.00	ug/L
EPA 8270D/1311	Soil	Di-n-octyl phthalate	4.15	5.00	ug/L
EPA 8270D/1311	Soil	Fluoranthene	1.59	5.00	ug/L
EPA 8270D/1311	Soil	Fluorene	3.22	5.00	ug/L
EPA 8270D/1311	Soil	Hexachlorobenzene	2.96	5.00	ug/L
EPA 8270D/1311	Soil	Hexachlorobutadiene	3.31	5.00	ug/L
EPA 8270D/1311	Soil	Hexachlorocyclopentadiene	3.45	5.00	ug/L
EPA 8270D/1311	Soil	Hexachloroethane	3.63	5.00	ug/L

ATTACHMENT B

Laboratory Reporting Limits and Method Detection Limits

Method	Matrix	Analyte	MDL	RL	Units
TCLP SVOC					
EPA 8270D/1311	Soil	Indeno(1,2,3-cd)pyrene	2.75	5.00	ug/L
EPA 8270D/1311	Soil	Isophorone	3.23	5.00	ug/L
EPA 8270D/1311	Soil	Naphthalene	3.86	5.00	ug/L
EPA 8270D/1311	Soil	Nitrobenzene	1.97	5.00	ug/L
EPA 8270D/1311	Soil	N-Nitrosodimethylamine	3.10	5.00	ug/L
EPA 8270D/1311	Soil	N-nitroso-di-n-propylamine	2.57	5.00	ug/L
EPA 8270D/1311	Soil	N-Nitrosodiphenylamine	3.62	5.00	ug/L
EPA 8270D/1311	Soil	Pentachlorophenol	3.76	5.00	ug/L
EPA 8270D/1311	Soil	Phenanthrene	3.61	5.00	ug/L
EPA 8270D/1311	Soil	Phenol	3.27	5.00	ug/L
EPA 8270D/1311	Soil	Pyrene	2.37	5.00	ug/L
EPA 8270D/1311	Soil	Pyridine	3.19	5.00	ug/L

ATTACHMENT B

Laboratory Reporting Limits and Method Detection Limits

Method	Matrix	Analyte	MDL	RL	Units
Pesticides					
EPA 8081B	Soil	Aldrin	0.33	0.33	ug/kg
EPA 8081B	Soil	alpha-BHC	0.33	0.33	ug/kg
EPA 8081B	Soil	beta-BHC	0.33	0.33	ug/kg
EPA 8081B	Soil	delta-BHC	0.33	0.33	ug/kg
EPA 8081B	Soil	gamma-BHC (Lindane)	0.33	0.33	ug/kg
EPA 8081B	Soil	gamma-Chlordane	0.33	0.33	ug/kg
EPA 8081B	Soil	alpha-Chlordane	0.33	0.33	ug/kg
EPA 8081B	Soil	Chlordane, total	1.32	1.32	ug/kg
EPA 8081B	Soil	4,4'-DDD	0.33	0.33	ug/kg
EPA 8081B	Soil	4,4'-DDE	0.33	0.33	ug/kg
EPA 8081B	Soil	4,4'-DDT	0.33	0.33	ug/kg
EPA 8081B	Soil	Dieldrin	0.33	0.33	ug/kg
EPA 8081B	Soil	Endosulfan I	0.33	0.33	ug/kg
EPA 8081B	Soil	Endosulfan II	0.33	0.33	ug/kg
EPA 8081B	Soil	Endosulfan sulfate	0.33	0.33	ug/kg
EPA 8081B	Soil	Endrin	0.33	0.33	ug/kg
EPA 8081B	Soil	Endrin aldehyde	0.33	0.33	ug/kg
EPA 8081B	Soil	Endrin ketone	0.33	0.33	ug/kg
EPA 8081B	Soil	Heptachlor	0.33	0.33	ug/kg
EPA 8081B	Soil	Heptachlor epoxide	0.33	0.33	ug/kg
EPA 8081B	Soil	Methoxychlor	1.65	1.65	ug/kg
EPA 8081B	Soil	Toxaphene	16.7	16.7	ug/kg

ATTACHMENT B

Laboratory Reporting Limits and Method Detection Limits

Method	Matrix	Analyte	MDL	RL	Units
TCLP Pesticides					
EPA 8081B/1311	Soil	4,4'-DDD	0.00400	0.00400	ug/L
EPA 8081B/1311	Soil	4,4'-DDE	0.00400	0.00400	ug/L
EPA 8081B/1311	Soil	4,4'-DDT	0.00400	0.00400	ug/L
EPA 8081B/1311	Soil	Aldrin	0.00400	0.00400	ug/L
EPA 8081B/1311	Soil	alpha-BHC	0.00400	0.00400	ug/L
EPA 8081B/1311	Soil	alpha-Chlordane	0.00400	0.00400	ug/L
EPA 8081B/1311	Soil	beta-BHC	0.00400	0.00400	ug/L
EPA 8081B/1311	Soil	Chlordane, total	0.0200	0.0200	ug/L
EPA 8081B/1311	Soil	delta-BHC	0.00400	0.00400	ug/L
EPA 8081B/1311	Soil	Dieldrin	0.00200	0.00200	ug/L
EPA 8081B/1311	Soil	Endosulfan I	0.00400	0.00400	ug/L
EPA 8081B/1311	Soil	Endosulfan II	0.00400	0.00400	ug/L
EPA 8081B/1311	Soil	Endosulfan sulfate	0.00400	0.00400	ug/L
EPA 8081B/1311	Soil	Endrin	0.00400	0.00400	ug/L
EPA 8081B/1311	Soil	Endrin aldehyde	0.0100	0.0100	ug/L
EPA 8081B/1311	Soil	Endrin ketone	0.0100	0.0100	ug/L
EPA 8081B/1311	Soil	gamma-BHC (Lindane)	0.00400	0.00400	ug/L
EPA 8081B/1311	Soil	gamma-Chlordane	0.0100	0.0100	ug/L
EPA 8081B/1311	Soil	Heptachlor	0.00400	0.00400	ug/L
EPA 8081B/1311	Soil	Heptachlor epoxide	0.00400	0.00400	ug/L
EPA 8081B/1311	Soil	Methoxychlor	0.00400	0.00400	ug/L
EPA 8081B/1311	Soil	Toxaphene	0.100	0.100	ug/L

ATTACHMENT B

Laboratory Reporting Limits and Method Detection Limits

Method	Matrix	Analyte	MDL	RL	Units
PCBs					
EPA 8082A	Soil	Aroclor 1016	0.0167	0.0167	mg/kg
EPA 8082A	Soil	Aroclor 1221	0.0167	0.0167	mg/kg
EPA 8082A	Soil	Aroclor 1232	0.0167	0.0167	mg/kg
EPA 8082A	Soil	Aroclor 1242	0.0167	0.0167	mg/kg
EPA 8082A	Soil	Aroclor 1248	0.0167	0.0167	mg/kg
EPA 8082A	Soil	Aroclor 1254	0.0167	0.0167	mg/kg
EPA 8082A	Soil	Aroclor 1260	0.0167	0.0167	mg/kg
EPA 8082A	Soil	Aroclor 1262	0.0167	0.0167	mg/kg
EPA 8082A	Soil	Aroclor 1268	0.0167	0.0167	mg/kg
EPA 8082A	Soil	Total PCBs	0.0167	0.0167	mg/kg

ATTACHMENT B

Laboratory Reporting Limits and Method Detection Limits

Method	Matrix	Analyte	MDL	RL	Units
Herbicides					
EPA 8151A	Soil	2,4,5-T	20.0	20.0	ug/kg
EPA 8151A	Soil	2,4,5-T [2C]	20.0	20.0	ug/kg
EPA 8151A	Soil	2,4,5-TP (Silvex)	20.0	20.0	ug/kg
EPA 8151A	Soil	2,4,5-TP (Silvex) [2C]	20.0	20.0	ug/kg
EPA 8151A	Soil	2,4-D	20.0	20.0	ug/kg
EPA 8151A	Soil	2,4-D [2C]	20.0	20.0	ug/kg
EPA 8151A	Soil	2,4-DB	20.0	20.0	ug/kg
EPA 8151A	Soil	2,4-DB [2C]	20.0	20.0	ug/kg
EPA 8151A	Soil	Dalapon	20.0	20.0	ug/kg
EPA 8151A	Soil	Dalapon [2C]	20.0	20.0	ug/kg
EPA 8151A	Soil	Dicamba	20.0	20.0	ug/kg
EPA 8151A	Soil	Dicamba [2C]	20.0	20.0	ug/kg

ATTACHMENT B

Laboratory Reporting Limits and Method Detection Limits

Method	Matrix	Analyte	MDL	RL	Units
TCLP Herbicides					
EPA 8151A/1311	Soil	2,4,5-T	5.00	5.00	ug/L
EPA 8151A/1311	Soil	2,4,5-T [2C]	5.00	5.00	ug/L
EPA 8151A/1311	Soil	2,4,5-TP (Silvex)	5.00	5.00	ug/L
EPA 8151A/1311	Soil	2,4,5-TP (Silvex) [2C]	5.00	5.00	ug/L
EPA 8151A/1311	Soil	2,4-D	5.00	5.00	ug/L
EPA 8151A/1311	Soil	2,4-D [2C]	5.00	5.00	ug/L
EPA 8151A/1311	Soil	2,4-DB	5.00	5.00	ug/L
EPA 8151A/1311	Soil	2,4-DB [2C]	5.00	5.00	ug/L
EPA 8151A/1311	Soil	Dalapon	5.00	5.00	ug/L
EPA 8151A/1311	Soil	Dalapon [2C]	5.00	5.00	ug/L
EPA 8151A/1311	Soil	Dicamba	5.00	5.00	ug/L
EPA 8151A/1311	Soil	Dicamba [2C]	5.00	5.00	ug/L

ATTACHMENT B

Laboratory Reporting Limits and Method Detection Limits

Method	Matrix	Analyte	MDL	RL	Units
Metals					
EPA 6010C	Soil	Aluminum	1	1	mg/kg
EPA 6010C	Soil	Antimony	0.5	0.5	mg/kg
EPA 6010C	Soil	Arsenic	1	1	mg/kg
EPA 6010C	Soil	Barium	1	1	mg/kg
EPA 6010C	Soil	Beryllium	0.1	0.1	mg/kg
EPA 6010C	Soil	Cadmium	0.3	0.3	mg/kg
EPA 6010C	Soil	Calcium	0.5	5	mg/kg
EPA 6010C	Soil	Chromium	0.5	0.5	mg/kg
EPA 7196A	Soil	Chromium, Hexavalent	0.350	0.500	mg/kg
EPA 6010C	Soil	Cobalt	0.5	0.5	mg/kg
EPA 6010C	Soil	Copper	0.5	0.5	mg/kg
EPA 9014/9010C	Soil	Cyanide, total	0.500	0.500	mg/kg
EPA 6010C	Soil	Iron	2	2	mg/kg
EPA 6010C	Soil	Lead	0.3	0.3	mg/kg
EPA 6010C	Soil	Magnesium	5	5	mg/kg
EPA 6010C	Soil	Manganese	0.5	0.5	mg/kg
EPA 7473	Soil	Mercury	0.03	0.03	mg/kg
EPA 6010C	Soil	Nickel	0.5	0.5	mg/kg
EPA 6010C	Soil	Potassium	5	5	mg/kg
EPA 6010C	Soil	Selenium	1	1	mg/kg
EPA 6010C	Soil	Silver	0.5	0.5	mg/kg
EPA 6010C	Soil	Sodium	10	10	mg/kg
EPA 6010C	Soil	Thallium	1	1	mg/kg
EPA 6010C	Soil	Vanadium	1	1	mg/kg
EPA 6010C	Soil	Zinc	1	1	mg/kg

ATTACHMENT B

Laboratory Reporting Limits and Method Detection Limits

Method	Matrix	Analyte	MDL	RL	Units
TCLP Metals					
EPA 6010D/1311	Soil	Aluminum	0.050	0.050	mg/L
EPA 6010D/1311	Soil	Antimony	0.025	0.025	mg/L
EPA 6010D/1311	Soil	Arsenic	0.015	0.015	mg/L
EPA 6010D/1311	Soil	Barium	0.025	0.025	mg/L
EPA 6010D/1311	Soil	Beryllium	0.0005	0.0005	mg/L
EPA 6010D/1311	Soil	Cadmium	0.003	0.003	mg/L
EPA 6010D/1311	Soil	Calcium	0.050	0.050	mg/L
EPA 6010D/1311	Soil	Chromium	0.005	0.005	mg/L
EPA 6010D/1311	Soil	Cobalt	0.004	0.004	mg/L
EPA 6010D/1311	Soil	Copper	0.020	0.020	mg/L
EPA 6010D/1311	Soil	Iron	0.250	0.250	mg/L
EPA 6010D/1311	Soil	Lead	0.005	0.005	mg/L
EPA 6010D/1311	Soil	Magnesium	0.050	0.050	mg/L
EPA 6010D/1311	Soil	Manganese	0.005	0.005	mg/L
EPA 7473/1311	Soil	Mercury	0.000039000	0.00020000	mg/L
EPA 6010D/1311	Soil	Nickel	0.010	0.010	mg/L
EPA 6010D/1311	Soil	Potassium	0.050	0.050	mg/L
EPA 6010D/1311	Soil	Selenium	0.025	0.025	mg/L
EPA 6010D/1311	Soil	Silver	0.005	0.005	mg/L
EPA 6010D/1311	Soil	Sodium	0.500	0.500	mg/L
EPA 6010D/1311	Soil	Thallium	0.025	0.025	mg/L
EPA 6010D/1311	Soil	Vanadium	0.010	0.010	mg/L
EPA 6010D/1311	Soil	Zinc	0.025	0.025	mg/L

ATTACHMENT B

Laboratory Reporting Limits and Method Detection Limits

Method	Matrix	Analyte	MDL	RL	Units
PFAs					
Modified EPA 537	Soil	Perfluorobutanesulfonic acid (PFBS)	0.5	0.5	ug/kg
Modified EPA 537	Soil	Perfluorohexanoic acid (PFHxA)	0.5	0.5	ug/kg
Modified EPA 537	Soil	Perfluoroheptanoic acid (PFHpA)	0.5	0.5	ug/kg
Modified EPA 537	Soil	Perfluorohexanesulfonic acid (PFHxS)	0.5	0.5	ug/kg
Modified EPA 537	Soil	Perfluorooctanoic acid (PFOA)	0.5	0.5	ug/kg
Modified EPA 537	Soil	Perfluorooctanesulfonic acid (PFOS)	0.5	0.5	ug/kg
Modified EPA 537	Soil	Perfluorononanoic acid (PFNA)	0.5	0.5	ug/kg
Modified EPA 537	Soil	Perfluorodecanoic acid (PFDA)	0.5	0.5	ug/kg
Modified EPA 537	Soil	Perfluoroundecanoic acid (PFUnA)	0.5	0.5	ug/kg
Modified EPA 537	Soil	Perfluorododecanoic acid (PFDoA)	0.5	0.5	ug/kg
Modified EPA 537	Soil	Perfluorotridecanoic acid (PFTrDA)	0.5	0.5	ug/kg
Modified EPA 537	Soil	Perfluorotetradecanoic acid (PFTA)	0.5	0.5	ug/kg
Modified EPA 537	Soil	N-MeFOSAA	0.5	0.5	ug/kg
Modified EPA 537	Soil	N-EtFOSAA	0.5	0.5	ug/kg
Modified EPA 537	Soil	Perfluoropentanoic acid (PFPeA)	0.5	0.5	ug/kg
Modified EPA 537	Soil	Perfluoro-1-octanesulfonamide (FOSA)	0.5	0.5	ug/kg
Modified EPA 537	Soil	Perfluoro-1-heptanesulfonic acid (PFHpS)	0.5	0.5	ug/kg
Modified EPA 537	Soil	Perfluoro-1-decanesulfonic acid (PFDS)	0.5	0.5	ug/kg
Modified EPA 537	Soil	1H,1H,2H,2H-Perfluorooctanesulfonic acid (6:2 FTS)	0.5	0.5	ug/kg
Modified EPA 537	Soil	1H,1H,2H,2H-Perfluorodecanesulfonic acid (8:2 FTS)	0.5	0.5	ug/kg
Modified EPA 537	Soil	Perfluoro-n-butanoic acid (PFBA)	0.5	0.5	ug/kg

ATTACHMENT B

Laboratory Reporting Limits and Method Detection Limits

Method	Matrix	Analyte	MDL	RL	Units
NJDEP EPH					
NJDEP EPH Rev 3.0	Soil	Total EPH	50.0	50.0	mg/kg

ATTACHMENT B

Laboratory Reporting Limits and Method Detection Limits

Method	Matrix	Analyte	MDL	RL	Units
RCRA Characteristics					
EPA SW-846 Ch.7.3.3	Soil	Reactivity - Cyanide	0.250	0.250	mg/kg
EPA SW-846 Ch.7.3.4	Soil	Reactivity - Sulfide	15.0	15.0	mg/kg
EPA 9045D	Soil	Corrosivity - pH	0.500	0.500	pH units
EPA 1030P	Soil	Ignitability	1	1	None

York Analytical Laboratories, Inc.

VOA MDLs and RLs	**1**
SVOA MDLs and RLs	**5**
Pesticide MDLs and RLs	**9**
PCB MDLs and RLs	**11**
Herbicides MDLs and RLs	**15**
ICP Metals MDLs and RLs	**16**
ICPMS Metals MDLs and RLs	**17**
Hexavalent Chromium MDLs and RLs	**18**
1,4-Dioxane MDLs and RLs	**20**
PFAS MDLs and RLs	**22**
TPH-DRO MDLs and RLs	**23**
TPH-GRO MDLs and RLs	**23**
NJEPH Cat. 2 NF MDLs and RLs	**23**
TO15 Air MDLs and RLs	**24**

Analytical Method Information

Printed: 07/12/2021 3:29 pm

Volatile Organics, 8260 - Comprehensive in Soil (EPA 8260C)

Preservation: Cool 4°C

Container: 03_5035 Vial Set **Amount Required:** 20 g. **Hold Time:** 14 days

Analyte	MDL	Reporting Limit	Surrogate %Rec	Duplicate RPD	----Matrix Spike---- %Rec	RPD	--Blank Spike / LCS-- %Rec	RPD
1,1,1,2-Tetrachloroethane	2.5	5.0 ug/kg			15-161	33	75-129	30
1,1,1-Trichloroethane	2.5	5.0 ug/kg			42-145	30	71-137	30
1,1,2,2-Tetrachloroethane	2.5	5.0 ug/kg			16-167	56	79-129	30
1,1,2-Trichloro-1,2,2-trifluoroethane (Freon 113)	2.5	5.0 ug/kg			11-160	31	58-146	30
1,1,2-Trichloroethane	2.5	5.0 ug/kg			44-145	40	83-123	30
1,1-Dichloroethane	2.5	5.0 ug/kg			46-142	36	75-130	30
1,1-Dichloroethylene	2.5	5.0 ug/kg			30-153	31	64-137	30
1,1-Dichloropropylene	2.5	5.0 ug/kg			40-133	28	77-127	30
1,2,3-Trichlorobenzene	2.5	5.0 ug/kg			10-157	47	81-140	30
1,2,3-Trichloropropane	2.5	5.0 ug/kg			38-155	48	81-126	30
1,2,4,5-Tetramethylbenzene	2.5	5.0 ug/kg			10-138	44	63-156	30
1,2,4-Trichlorobenzene	2.5	5.0 ug/kg			10-151	52	80-141	30
1,2,4-Trimethylbenzene	2.5	5.0 ug/kg			10-170	242	84-125	30
1,2-Dibromo-3-chloropropane	2.5	5.0 ug/kg			36-138	54	74-142	30
1,2-Dibromoethane	2.5	5.0 ug/kg			40-142	39	86-123	30
1,2-Dichlorobenzene	2.5	5.0 ug/kg			10-147	52	85-122	30
1,2-Dichloroethane	2.5	5.0 ug/kg			48-133	32	71-133	30
1,2-Dichloropropane	2.5	5.0 ug/kg			47-141	37	81-122	30
1,3,5-Trimethylbenzene	2.5	5.0 ug/kg			10-150	62	82-126	30
1,3-Dichlorobenzene	2.5	5.0 ug/kg			10-144	51	84-124	30
1,3-Dichloropropane	2.5	5.0 ug/kg			43-142	36	83-123	30
1,4-Dichlorobenzene	2.5	5.0 ug/kg			10-160	52	84-124	30
1,4-Dioxane	50	100 ug/kg			10-191	196	10-228	30
2,2-Dichloropropane	2.5	5.0 ug/kg			38-130	31	67-136	30
2-Butanone	2.5	5.0 ug/kg			10-189	67	58-147	30
2-Chlorotoluene	2.5	5.0 ug/kg			14-144	49	78-127	30
2-Hexanone	2.5	5.0 ug/kg			10-181	60	70-139	30
4-Chlorotoluene	2.5	5.0 ug/kg			15-138	39	79-125	30
4-Methyl-2-pentanone	2.5	5.0 ug/kg			10-166	47	72-132	30
Acetone	5.0	10 ug/kg			10-196	150	36-155	30
Acrolein	5.0	10 ug/kg			10-192	128	10-238	30
Acrylonitrile	2.5	5.0 ug/kg			13-161	48	66-141	30
Benzene	2.5	5.0 ug/kg			43-139	64	77-127	30
Bromobenzene	2.5	5.0 ug/kg			23-142	44	77-129	30
Bromochloromethane	2.5	5.0 ug/kg			38-145	30	74-129	30
Bromodichloromethane	2.5	5.0 ug/kg			38-147	37	81-124	30
Bromoform	2.5	5.0 ug/kg			29-156	51	80-136	30
Bromomethane	2.5	5.0 ug/kg			10-166	42	32-177	30
Carbon disulfide	2.5	5.0 ug/kg			10-131	36	10-136	30
Carbon tetrachloride	2.5	5.0 ug/kg			35-145	31	66-143	30
Chlorobenzene	2.5	5.0 ug/kg			21-154	32	86-120	30
Chloroethane	2.5	5.0 ug/kg			15-160	40	51-142	30
Chloroform	2.5	5.0 ug/kg			47-142	29	76-131	30
Chloromethane	2.5	5.0 ug/kg			10-159	31	49-132	30
cis-1,2-Dichloroethylene	2.5	5.0 ug/kg			42-144	30	74-132	30
cis-1,3-Dichloropropylene	2.5	5.0 ug/kg			18-159	39	81-129	30
Cyclohexane	2.5	5.0 ug/kg			70-130	30	70-130	30
Dibromochloromethane	2.5	5.0 ug/kg			10-179	41	10-200	30
Dibromomethane	2.5	5.0 ug/kg			47-143	41	83-124	30
Dichlorodifluoromethane	2.5	5.0 ug/kg			10-145	34	28-158	30
Ethyl Benzene	2.5	5.0 ug/kg			11-158	42	84-125	30
Hexachlorobutadiene	2.5	5.0 ug/kg			10-158	45	83-133	30
Isopropylbenzene	2.5	5.0 ug/kg			10-162	57	81-127	30

Analytical Method Information

(Continued)

Volatile Organics, 8260 - Comprehensive in Soil (EPA 8260C) (Continued)

Analyte	MDL	Reporting Limit	Surrogate %Rec	Duplicate RPD	----Matrix Spike---- %Rec	----Matrix Spike---- RPD	--Blank Spike / LCS-- %Rec	--Blank Spike / LCS-- RPD
Methyl acetate	2.5	5.0 ug/kg			10-149	64	41-143	30
Methyl tert-butyl ether (MTBE)	2.5	5.0 ug/kg			42-152	47	74-131	30
Methylcyclohexane	2.5	5.0 ug/kg			70-130	30	70-130	30
Methylene chloride	5.0	10 ug/kg			28-151	49	57-141	30
Naphthalene	2.5	10 ug/kg			10-158	95	86-141	30
n-Butylbenzene	2.5	5.0 ug/kg			10-162	96	80-130	30
n-Propylbenzene	2.5	5.0 ug/kg			10-155	56	74-136	30
o-Xylene	2.5	5.0 ug/kg			10-158	51	83-123	30
p- & m- Xylenes	5.0	10 ug/kg			10-156	47	82-128	30
p-Diethylbenzene	2.5	5.0 ug/kg			10-146	39	70-144	30
p-Ethyltoluene	2.5	5.0 ug/kg			10-135	40	84-123	30
p-Isopropyltoluene	2.5	5.0 ug/kg			10-147	60	85-125	30
sec-Butylbenzene	2.5	5.0 ug/kg			10-157	56	83-125	30
Styrene	2.5	5.0 ug/kg			13-171	39	86-126	30
tert-Butyl alcohol (TBA)	2.5	5.0 ug/kg			34-179	35	70-130	30
tert-Butylbenzene	2.5	5.0 ug/kg			10-160	79	80-127	30
Tetrachloroethylene	2.5	5.0 ug/kg			30-167	33	80-129	30
Toluene	2.5	5.0 ug/kg			21-160	50	85-121	30
trans-1,2-Dichloroethylene	2.5	5.0 ug/kg			29-153	30	72-132	30
trans-1,3-Dichloropropylene	2.5	5.0 ug/kg			18-155	30	78-132	30
trans-1,4-dichloro-2-butene	2.5	5.0 ug/kg			17-154	30	75-135	30
Trichloroethylene	2.5	5.0 ug/kg			24-169	30	84-123	30
Trichlorofluoromethane	2.5	5.0 ug/kg			35-142	30	62-140	30
Vinyl acetate	2.5	5.0 ug/kg			10-119	82	67-136	30
Vinyl Chloride	2.5	5.0 ug/kg			12-160	35	52-130	30
Xylenes, Total	7.5	15 ug/kg						
Chlorodifluoromethane (Freon 22)	2.5	5.0 ug/kg				30		30
Surr: SURR: 1,2-Dichloroethane-d4			77-125					
Surr: SURR: Toluene-d8			85-120					
Surr: SURR: p-Bromofluorobenzene			76-130					
ISTD: Fluorobenzene								
ISTD: Chlorobenzene-d5								
ISTD: 1,2-Dichlorobenzene-d4								

Analytical Method Information

Printed: 07/12/2021 3:29 pm

(Continued)

Volatile Organics, 8260 - Comprehensive in Water (EPA 8260C)

Preservation: Add HCl to pH<2; Store cool at 4°C

Container: 00_40mL Clear Vial (pre-pres.) HCl; Cool t **Amount Required:** 80 mL **Hold Time:** 14 days

Analyte	MDL	Reporting Limit	Surrogate %Rec	Duplicate RPD	----Matrix Spike---- %Rec	RPD	--Blank Spike / LCS-- %Rec	RPD
1,1,1,2-Tetrachloroethane	0.20	0.50 ug/L			45-161	30	82-126	30
1,1,1-Trichloroethane	0.20	0.50 ug/L			70-146	30	78-136	30
1,1,2,2-Tetrachloroethane	0.20	0.50 ug/L			74-121	30	76-129	30
1,1,2-Trichloro-1,2,2-trifluoroethane (Freon 113)	0.20	0.50 ug/L			21-217	30	54-165	30
1,1,2-Trichloroethane	0.20	0.50 ug/L			59-146	30	82-123	30
1,1-Dichloroethane	0.20	0.50 ug/L			54-146	30	82-129	30
1,1-Dichloroethylene	0.20	0.50 ug/L			44-165	30	68-138	30
1,1-Dichloropropylene	0.20	0.50 ug/L			82-134	30	83-133	30
1,2,3-Trichlorobenzene	0.20	0.50 ug/L			40-161	30	40-130	30
1,2,3-Trichloropropane	0.20	0.50 ug/L			74-127	30	77-128	30
1,2,4,5-Tetramethylbenzene	0.20	0.50 ug/L			27-190	30	85-140	30
1,2,4-Trichlorobenzene	0.20	0.50 ug/L			41-161	30	65-137	30
1,2,4-Trimethylbenzene	0.20	0.50 ug/L			72-129	30	82-132	30
1,2-Dibromo-3-chloropropane	0.20	0.50 ug/L			31-151	30	45-147	30
1,2-Dibromoethane	0.20	0.50 ug/L			75-125	30	83-124	30
1,2-Dichlorobenzene	0.20	0.50 ug/L			63-122	30	79-123	30
1,2-Dichloroethane	0.20	0.50 ug/L			68-131	30	73-132	30
1,2-Dichloropropane	0.20	0.50 ug/L			77-121	30	78-126	30
1,3,5-Trimethylbenzene	0.20	0.50 ug/L			69-126	30	80-131	30
1,3-Dichlorobenzene	0.20	0.50 ug/L			74-119	30	86-130	30
1,3-Dichloropropane	0.20	0.50 ug/L			77-119	30	81-125	30
1,4-Dichlorobenzene	0.20	0.50 ug/L			70-124	30	85-130	30
1,4-Dioxane	40	40 ug/L			10-310	30	10-349	30
2,2-Dichloropropane	0.20	0.50 ug/L			10-160	30	56-152	30
2-Butanone	0.20	0.50 ug/L			10-193	30	49-152	30
2-Chlorotoluene	0.20	0.50 ug/L			70-126	30	79-130	30
2-Hexanone	0.20	0.50 ug/L			53-133	30	51-146	30
4-Chlorotoluene	0.20	0.50 ug/L			69-124	30	79-128	30
4-Methyl-2-pentanone	0.20	0.50 ug/L			38-150	30	57-145	30
Acetone	1.0	2.0 ug/L			13-149	30	14-150	30
Acrolein	0.20	0.50 ug/L			10-195	30	10-153	30
Acrylonitrile	0.20	0.50 ug/L			37-165	30	51-150	30
Benzene	0.20	0.50 ug/L			38-155	30	85-126	30
Bromobenzene	0.20	0.50 ug/L			72-122	30	78-129	30
Bromochloromethane	0.20	0.50 ug/L			75-121	30	77-128	30
Bromodichloromethane	0.20	0.50 ug/L			70-129	30	79-128	30
Bromoform	0.20	0.50 ug/L			66-136	30	78-133	30
Bromomethane	0.20	0.50 ug/L			30-158	30	43-168	30
Carbon disulfide	0.20	0.50 ug/L			10-138	30	68-146	30
Carbon tetrachloride	0.20	0.50 ug/L			71-146	30	77-141	30
Chlorobenzene	0.20	0.50 ug/L			81-117	30	88-120	30
Chloroethane	0.20	0.50 ug/L			51-145	30	65-136	30
Chloroform	0.20	0.50 ug/L			80-124	30	82-128	30
Chloromethane	0.20	0.50 ug/L			16-163	30	43-155	30
cis-1,2-Dichloroethylene	0.20	0.50 ug/L			76-125	30	83-129	30
cis-1,3-Dichloropropylene	0.20	0.50 ug/L			58-131	30	80-131	30
Cyclohexane	0.20	0.50 ug/L			70-130	30	63-149	30
Dibromochloromethane	0.20	0.50 ug/L			71-129	30	80-130	30
Dibromomethane	0.20	0.50 ug/L			76-120	30	72-134	30
Dichlorodifluoromethane	0.20	0.50 ug/L			30-147	30	44-144	30
Ethyl Benzene	0.20	0.50 ug/L			72-128	30	80-131	30
Hexachlorobutadiene	0.20	0.50 ug/L			34-166	30	67-146	30
Isopropylbenzene	0.20	0.50 ug/L			66-139	30	76-140	30

Analytical Method Information

(Continued)

Printed: 07/12/2021 3:29 pm

Volatile Organics, 8260 - Comprehensive in Water (EPA 8260C) (Continued)

Analyte	MDL	Reporting Limit	Surrogate %Rec	Duplicate RPD	----Matrix Spike---- %Rec	----Matrix Spike---- RPD	--Blank Spike / LCS-- %Rec	--Blank Spike / LCS-- RPD
Methyl acetate	0.20	0.50 ug/L			10-200	30	51-139	30
Methyl tert-butyl ether (MTBE)	0.20	0.50 ug/L			75-128	30	76-135	30
Methylcyclohexane	0.20	0.50 ug/L			70-130	30	72-143	30
Methylene chloride	1.0	2.0 ug/L			57-128	30	55-137	30
Naphthalene	1.0	2.0 ug/L			39-158	30	50-147	30
n-Butylbenzene	0.20	0.50 ug/L			61-138	30	79-132	30
n-Propylbenzene	0.20	0.50 ug/L			66-134	30	78-133	30
o-Xylene	0.20	0.50 ug/L			69-126	30	78-130	30
p- & m- Xylenes	0.50	1.0 ug/L			67-130	30	77-133	30
p-Diethylbenzene	0.20	0.50 ug/L			52-150	30	84-134	30
p-Ethyltoluene	0.20	0.50 ug/L			76-127	30	88-129	30
p-Isopropyltoluene	0.20	0.50 ug/L			64-137	30	81-136	30
sec-Butylbenzene	0.20	0.50 ug/L			53-155	30	79-137	30
Styrene	0.20	0.50 ug/L			69-125	30	67-132	30
tert-Butyl alcohol (TBA)	0.50	1.0 ug/L			10-130	30	25-162	30
tert-Butylbenzene	0.20	0.50 ug/L			65-139	30	77-138	30
Tetrachloroethylene	0.20	0.50 ug/L			64-139	30	82-131	30
Toluene	0.20	0.50 ug/L			76-123	30	80-127	30
trans-1,2-Dichloroethylene	0.20	0.50 ug/L			79-131	30	80-132	30
trans-1,3-Dichloropropylene	0.20	0.50 ug/L			55-130	30	78-131	30
trans-1,4-dichloro-2-butene	0.20	0.50 ug/L			25-155	30	63-141	30
Trichloroethylene	0.20	0.50 ug/L			53-145	30	82-128	30
Trichlorofluoromethane	0.20	0.50 ug/L			61-142	30	67-139	30
Vinyl acetate	0.20	0.50 ug/L			10-87	30	60-130	30
Vinyl Chloride	0.20	0.50 ug/L			31-165	30	58-145	30
Xylenes, Total	0.60	1.5 ug/L						
Chlorodifluoromethane (Freon 22)	0.20	0.50 ug/L				30		30
Surr: SURR: 1,2-Dichloroethane-d4			69-130					
Surr: SURR: Toluene-d8			81-117					
Surr: SURR: p-Bromofluorobenzene			79-122					
ISTD: Fluorobenzene								
ISTD: Chlorobenzene-d5								
ISTD: 1,2-Dichlorobenzene-d4								

Analytical Method Information

Printed: 07/12/2021 3:31 pm

Semi-Volatiles, 8270 - Comprehensive in Soil (EPA 8270D)

Preservation: Cool 4°C

Container: 06_4 oz. WM Clear Glass Cool to 4° C **Amount Required:** 100 g **Hold Time:** 14 days

Analyte	MDL	Reporting Limit	Surrogate %Rec	Duplicate RPD	----Matrix Spike---- %Rec	RPD	--Blank Spike / LCS-- %Rec	RPD
1,1-Biphenyl	20.9	41.7 ug/kg			10-130	30	18-111	30
1,2,4,5-Tetrachlorobenzene	41.7	83.3 ug/kg			10-133	30	21-131	30
1,2,4-Trichlorobenzene	20.9	41.7 ug/kg			10-127	30	10-140	30
1,2-Dichlorobenzene	20.9	41.7 ug/kg			14-111	30	34-108	30
1,2-Diphenylhydrazine (as Azobenzene)	20.9	41.7 ug/kg			10-144	30	17-137	30
1,3-Dichlorobenzene	20.9	41.7 ug/kg			11-111	30	33-110	30
1,4-Dichlorobenzene	20.9	41.7 ug/kg			10-106	30	32-104	30
2,3,4,6-Tetrachlorophenol	41.7	83.3 ug/kg			30-130	30	30-130	30
2,4,5-Trichlorophenol	20.9	41.7 ug/kg			10-127	30	27-118	30
2,4,6-Trichlorophenol	20.9	41.7 ug/kg			10-132	30	31-120	30
2,4-Dichlorophenol	20.9	41.7 ug/kg			10-128	30	20-127	30
2,4-Dimethylphenol	20.9	41.7 ug/kg			10-137	30	14-132	30
2,4-Dinitrophenol	41.7	83.3 ug/kg			10-171	30	10-171	30
2,4-Dinitrotoluene	20.9	41.7 ug/kg			16-135	30	34-131	30
2,6-Dinitrotoluene	20.9	41.7 ug/kg			18-131	30	31-128	30
2-Chloronaphthalene	20.9	41.7 ug/kg			10-129	30	31-117	30
2-Chlorophenol	20.9	41.7 ug/kg			15-116	30	33-113	30
2-Methylnaphthalene	20.9	41.7 ug/kg			10-147	30	12-138	30
2-Methylphenol	20.9	41.7 ug/kg			10-136	30	10-136	30
2-Nitroaniline	41.7	83.3 ug/kg			10-137	30	27-132	30
2-Nitrophenol	20.9	41.7 ug/kg			10-129	30	17-129	30
3- & 4-Methylphenols	20.9	41.7 ug/kg			10-123	30	29-103	30
3,3-Dichlorobenzidine	20.9	41.7 ug/kg			10-155	30	22-149	30
3-Nitroaniline	41.7	83.3 ug/kg			12-133	30	20-133	30
4,6-Dinitro-2-methylphenol	41.7	83.3 ug/kg			10-155	30	10-143	30
4-Bromophenyl phenyl ether	20.9	41.7 ug/kg			14-128	30	29-120	30
4-Chloro-3-methylphenol	20.9	41.7 ug/kg			10-134	30	24-129	30
4-Chloroaniline	20.9	41.7 ug/kg			10-145	30	10-132	30
4-Chlorophenyl phenyl ether	20.9	41.7 ug/kg			14-130	30	27-124	30
4-Nitroaniline	41.7	83.3 ug/kg			10-147	30	16-128	30
4-Nitrophenol	41.7	83.3 ug/kg			10-137	30	10-141	30
Acenaphthene	20.9	41.7 ug/kg			10-146	30	30-121	30
Acenaphthylene	20.9	41.7 ug/kg			10-134	30	30-115	30
Acetophenone	20.9	41.7 ug/kg			10-116	30	20-112	30
Aniline	83.5	167 ug/kg			10-123	30	10-119	30
Anthracene	20.9	41.7 ug/kg			10-142	30	34-118	30
Atrazine	20.9	41.7 ug/kg			19-115	30	26-112	30
Benzaldehyde	20.9	41.7 ug/kg			10-125	30	21-100	30
Benzidine	83.5	167 ug/kg				30		30
Benzo(a)anthracene	20.9	41.7 ug/kg			10-158	30	32-122	30
Benzo(a)pyrene	20.9	41.7 ug/kg			10-180	30	29-133	30
Benzo(b)fluoranthene	20.9	41.7 ug/kg			10-200	30	25-133	30
Benzo(g,h,i)perylene	20.9	41.7 ug/kg			10-138	30	10-143	30
Benzo(k)fluoranthene	20.9	41.7 ug/kg			10-197	30	25-128	30
Benzoic acid	20.9	41.7 ug/kg			10-166	30	10-140	30
Benzyl alcohol	20.9	41.7 ug/kg			12-124	30	30-115	30
Benzyl butyl phthalate	20.9	41.7 ug/kg			10-154	30	26-126	30
Bis(2-chloroethoxy)methane	20.9	41.7 ug/kg			10-132	30	19-132	30
Bis(2-chloroethyl)ether	20.9	41.7 ug/kg			10-119	30	19-125	30
Bis(2-chloroisopropyl)ether	20.9	41.7 ug/kg			10-139	30	20-135	30
Bis(2-ethylhexyl)phthalate	20.9	41.7 ug/kg			10-167	30	10-155	30
Caprolactam	41.7	83.3 ug/kg			10-132	30	10-127	30
Carbazole	20.9	41.7 ug/kg			10-167	30	35-123	30

Analytical Method Information

(Continued)

Semi-Volatiles, 8270 - Comprehensive in Soil (EPA 8270D) (Continued)

Analyte	MDL	Reporting Limit	Surrogate %Rec	Duplicate RPD	----Matrix Spike---- %Rec	----Matrix Spike---- RPD	--Blank Spike / LCS-- %Rec	--Blank Spike / LCS-- RPD
Chrysene	20.9	41.7 ug/kg			10-156	30	32-123	30
Dibenzo(a,h)anthracene	20.9	41.7 ug/kg			10-137	30	10-136	30
Dibenzofuran	20.9	41.7 ug/kg			10-147	30	29-121	30
Diethyl phthalate	20.9	41.7 ug/kg			20-120	30	34-116	30
Dimethyl phthalate	20.9	41.7 ug/kg			18-131	30	35-124	30
Di-n-butyl phthalate	20.9	41.7 ug/kg			10-137	30	31-116	30
Di-n-octyl phthalate	20.9	41.7 ug/kg			10-180	30	26-136	30
Diphenylamine	41.7	83.3 ug/kg			40-140	30	40-140	30
Fluoranthene	20.9	41.7 ug/kg			10-160	30	33-122	30
Fluorene	20.9	41.7 ug/kg			10-157	30	29-123	30
Hexachlorobenzene	20.9	41.7 ug/kg			10-137	30	21-124	30
Hexachlorobutadiene	20.9	41.7 ug/kg			10-132	30	10-149	30
Hexachlorocyclopentadiene	20.9	41.7 ug/kg			10-106	30	10-129	30
Hexachloroethane	20.9	41.7 ug/kg			10-110	30	28-108	30
Indeno(1,2,3-cd)pyrene	20.9	41.7 ug/kg			10-144	30	10-135	30
Isophorone	20.9	41.7 ug/kg			10-132	30	20-132	30
Naphthalene	20.9	41.7 ug/kg			10-141	30	23-124	30
Nitrobenzene	20.9	41.7 ug/kg			10-131	30	13-132	30
N-Nitrosodimethylamine	20.9	41.7 ug/kg			10-126	30	11-129	30
N-nitroso-di-n-propylamine	20.9	41.7 ug/kg			10-125	30	24-119	30
N-Nitrosodiphenylamine	20.9	41.7 ug/kg			10-177	30	22-152	30
Pentachlorophenol	20.9	41.7 ug/kg			10-153	30	10-139	30
Phenanthrene	20.9	41.7 ug/kg			10-148	30	33-123	30
Phenol	20.9	41.7 ug/kg			10-126	30	23-115	30
Pyrene	20.9	41.7 ug/kg			10-165	30	32-130	30
Pyridine	83.5	167 ug/kg			10-83	30	10-91	30
Total PAH								
Benzo(a)pyrene (BAP)								
Equivalent-BAPE								
Surr: SURR: 2-Fluorophenol			20-108					
Surr: SURR: Phenol-d5			23-114					
Surr: SURR: Nitrobenzene-d5			22-108					
Surr: SURR: 2-Fluorobiphenyl			21-113					
Surr: SURR: 2,4,6-Tribromophenol			19-110					
Surr: SURR: Terphenyl-d14			24-116					
ISTD: 1,4-Dichlorobenzene-d4								
ISTD: Naphthalene-d8								
ISTD: Acenaphthene-d10								
ISTD: Phenanthrene-d10								
ISTD: Chrysene-d12								
ISTD: Perylene-d12								

Analytical Method Information

Printed: 07/12/2021 3:31 pm

(Continued)

Semi-Volatiles, 8270 - Comprehensive in Water (EPA 8270D)

Preservation: Cool 4°C

Container: 07_1000mL Amber Glass Cool to 4° C **Amount Required:** 1000 mL **Hold Time:** 7 days

Analyte	MDL	Reporting Limit	Surrogate %Rec	Duplicate RPD	----Matrix Spike---- %Rec	RPD	--Blank Spike / LCS-- %Rec	RPD
1,1-Biphenyl	2.50	5.00 ug/L			40-140	20	21-102	20
1,2,4,5-Tetrachlorobenzene	2.50	5.00 ug/L			40-140	20	28-105	20
1,2,4-Trichlorobenzene	2.50	5.00 ug/L			31-92	20	35-91	20
1,2-Dichlorobenzene	2.50	5.00 ug/L			31-91	20	42-85	20
1,2-Diphenylhydrazine (as Azobenzene)	2.50	5.00 ug/L			40-140	20	16-137	20
1,3-Dichlorobenzene	2.50	5.00 ug/L			24-93	20	45-80	20
1,4-Dichlorobenzene	2.50	5.00 ug/L			26-95	20	42-82	20
2,3,4,6-Tetrachlorophenol	2.50	5.00 ug/L			30-130	20	30-130	20
2,4,5-Trichlorophenol	2.50	5.00 ug/L			44-96	20	36-112	20
2,4,6-Trichlorophenol	2.50	5.00 ug/L			39-107	20	41-107	20
2,4-Dichlorophenol	2.50	5.00 ug/L			38-99	20	43-92	20
2,4-Dimethylphenol	2.50	5.00 ug/L			10-116	20	25-92	20
2,4-Dinitrophenol	2.50	5.00 ug/L			10-168	20	10-149	20
2,4-Dinitrotoluene	2.50	5.00 ug/L			26-120	20	41-114	20
2,6-Dinitrotoluene	2.50	5.00 ug/L			28-118	20	49-106	20
2-Chloronaphthalene	2.50	5.00 ug/L			33-99	20	40-96	20
2-Chlorophenol	2.50	5.00 ug/L			25-106	20	35-84	20
2-Methylnaphthalene	2.50	5.00 ug/L			29-102	20	33-101	20
2-Methylphenol	2.50	5.00 ug/L			10-118	20	10-90	20
2-Nitroaniline	2.50	5.00 ug/L			48-99	20	31-122	20
2-Nitrophenol	2.50	5.00 ug/L			36-103	20	37-97	20
3- & 4-Methylphenols	2.50	5.00 ug/L			10-102	20	10-101	20
3,3-Dichlorobenzidine	2.50	5.00 ug/L			10-140	20	25-155	20
3-Nitroaniline	2.50	5.00 ug/L			10-169	20	29-128	20
4,6-Dinitro-2-methylphenol	2.50	5.00 ug/L			10-142	20	10-135	20
4-Bromophenyl phenyl ether	2.50	5.00 ug/L			35-109	20	38-116	20
4-Chloro-3-methylphenol	2.50	5.00 ug/L			20-117	20	28-101	20
4-Chloroaniline	2.50	5.00 ug/L			24-116	20	10-154	20
4-Chlorophenyl phenyl ether	2.50	5.00 ug/L			31-112	20	34-112	20
4-Nitroaniline	2.50	5.00 ug/L			24-143	20	15-143	20
4-Nitrophenol	2.50	5.00 ug/L			10-119	20	10-112	20
Acenaphthene	0.0500	0.0500 ug/L			17-132	20	24-114	20
Acenaphthylene	0.0500	0.0500 ug/L			13-124	20	26-112	20
Acetophenone	2.50	5.00 ug/L			40-140	20	47-92	20
Aniline	2.50	5.00 ug/L			10-133	20	10-107	20
Anthracene	0.0500	0.0500 ug/L			40-105	20	35-114	20
Atrazine	0.500	0.500 ug/L			40-140	20	43-101	20
Benzaldehyde	2.50	5.00 ug/L			40-140	20	17-117	20
Benzidine	10.0	20.0 ug/L				20		20
Benzo(a)anthracene	0.0500	0.0500 ug/L			23-141	20	38-127	20
Benzo(a)pyrene	0.0500	0.0500 ug/L			46-118	20	30-146	20
Benzo(b)fluoranthene	0.0500	0.0500 ug/L			22-133	20	36-145	20
Benzo(g,h,i)perylene	0.0500	0.0500 ug/L			10-126	20	10-163	20
Benzo(k)fluoranthene	0.0500	0.0500 ug/L			18-152	20	16-149	20
Benzoic acid	25.0	50.0 ug/L			10-162	20	30-130	20
Benzyl alcohol	2.50	5.00 ug/L			10-114	20	18-75	20
Benzyl butyl phthalate	2.50	5.00 ug/L			31-121	20	28-129	20
Bis(2-chloroethoxy)methane	2.50	5.00 ug/L			23-110	20	27-112	20
Bis(2-chloroethyl)ether	2.50	5.00 ug/L			10-132	20	24-114	20
Bis(2-chloroisopropyl)ether	2.50	5.00 ug/L			12-132	20	21-124	20
Bis(2-ethylhexyl)phthalate	0.500	0.500 ug/L			14-131	20	10-171	20
Caprolactam	2.50	5.00 ug/L			40-140	20	10-29	20
Carbazole	2.50	5.00 ug/L			10-169	20	49-116	20

Analytical Method Information

(Continued)

Semi-Volatiles, 8270 - Comprehensive in Water (EPA 8270D) (Continued)

Analyte	MDL	Reporting Limit	Surrogate %Rec	Duplicate RPD	----Matrix Spike---- %Rec	----Matrix Spike---- RPD	--Blank Spike / LCS-- %Rec	--Blank Spike / LCS-- RPD
Chrysene	0.0500	0.0500 ug/L			30-127	20	33-120	20
Dibenzo(a,h)anthracene	0.0500	0.0500 ug/L			10-131	20	10-149	20
Dibenzofuran	2.50	5.00 ug/L			37-103	20	42-105	20
Diethyl phthalate	2.50	5.00 ug/L			41-106	20	38-112	20
Dimethyl phthalate	2.50	5.00 ug/L			38-105	20	49-106	20
Di-n-butyl phthalate	2.50	5.00 ug/L			24-121	20	36-110	20
Di-n-octyl phthalate	2.50	5.00 ug/L			25-141	20	12-149	20
Diphenylamine	2.50	5.00 ug/L			40-140	25	40-140	20
Fluoranthene	0.0500	0.0500 ug/L			29-123	20	33-126	20
Fluorene	0.0500	0.0500 ug/L			20-133	20	28-117	20
Hexachlorobenzene	0.0200	0.0200 ug/L			24-120	20	27-120	20
Hexachlorobutadiene	0.500	0.500 ug/L			26-98	20	25-106	20
Hexachlorocyclopentadiene	2.50	5.00 ug/L			10-103	20	10-99	20
Hexachloroethane	0.500	0.500 ug/L			11-102	20	33-84	20
Indeno(1,2,3-cd)pyrene	0.0500	0.0500 ug/L			10-130	20	10-150	20
Isophorone	2.50	5.00 ug/L			19-113	20	29-115	20
Naphthalene	0.0500	0.0500 ug/L			26-104	20	30-99	20
Nitrobenzene	0.250	0.250 ug/L			25-107	20	32-113	20
N-Nitrosodimethylamine	0.500	0.500 ug/L			10-110	20	10-63	20
N-nitroso-di-n-propylamine	2.50	5.00 ug/L			16-127	20	36-118	20
N-Nitrosodiphenylamine	2.50	5.00 ug/L			46-116	20	27-145	20
Pentachlorophenol	0.250	0.250 ug/L			10-181	20	19-127	20
Phenanthrene	0.0500	0.0500 ug/L			29-121	20	31-112	20
Phenol	2.50	5.00 ug/L			10-107	20	10-37	20
Pyrene	0.0500	0.0500 ug/L			34-129	20	42-125	20
Pyridine	2.50	5.00 ug/L			10-73	20	10-46	20
Surr: SURR: 2-Fluorophenol			19.7-63.1					
Surr: SURR: Phenol-d5			10.1-41.7					
Surr: SURR: Nitrobenzene-d5			50.2-113					
Surr: SURR: 2-Fluorobiphenyl			39.9-105					
Surr: SURR: 2,4,6-Tribromophenol			39.3-151					
Surr: SURR: Terphenyl-d14			30.7-106					
ISTD: 1,4-Dichlorobenzene-d4								
ISTD: Naphthalene-d8								
ISTD: Acenaphthene-d10								
ISTD: Phenanthrene-d10								
ISTD: Chrysene-d12								
ISTD: Perylene-d12								

Analytical Method Information

Printed: 07/12/2021 3:31 pm

Pesticides, 8081 target list in Soil (EPA 8081B)

Preservation: Cool 4°C

Container: 06_4 oz. WM Clear Glass Cool to 4° C **Amount Required:** 100 g **Hold Time:** 14 days

Analyte	MDL	Reporting Limit	Surrogate %Rec	Duplicate RPD	----Matrix Spike---- %Rec	RPD	--Blank Spike / LCS-- %Rec	RPD
4,4'-DDD	0.330	0.330 ug/kg			30-150	30	40-140	30
4,4'-DDD [2C]	0.330	0.330 ug/kg			30-150	30	40-140	30
4,4'-DDE	0.330	0.330 ug/kg			30-150	30	40-140	30
4,4'-DDE [2C]	0.330	0.330 ug/kg			30-150	30	40-140	30
4,4'-DDT	0.330	0.330 ug/kg			30-150	30	40-140	30
4,4'-DDT [2C]	0.330	0.330 ug/kg			30-150	30	40-140	30
Aldrin	0.330	0.330 ug/kg			30-150	30	40-140	30
Aldrin [2C]	0.330	0.330 ug/kg			30-150	30	40-140	30
alpha-BHC	0.330	0.330 ug/kg			30-150	30	40-140	30
alpha-BHC [2C]	0.330	0.330 ug/kg			30-150	30	40-140	30
alpha-Chlordane	0.330	0.330 ug/kg			30-150	30	40-140	30
alpha-Chlordane [2C]	0.330	0.330 ug/kg			30-150	30	40-140	30
beta-BHC	0.330	0.330 ug/kg			30-150	30	40-140	30
beta-BHC [2C]	0.330	0.330 ug/kg			30-150	30	40-140	30
Chlordane, total	6.60	6.60 ug/kg						30
Chlordane, total [2C]	6.60	6.60 ug/kg				30		30
delta-BHC	0.330	0.330 ug/kg			30-150	30	40-140	30
delta-BHC [2C]	0.330	0.330 ug/kg			30-150	30	40-140	30
Dieldrin	0.330	0.330 ug/kg			30-150	30	40-140	30
Dieldrin [2C]	0.330	0.330 ug/kg			30-150	30	40-140	30
Endosulfan I	0.330	0.330 ug/kg			30-150	30	40-140	30
Endosulfan I [2C]	0.330	0.330 ug/kg			30-150	30	40-140	30
Endosulfan II	0.330	0.330 ug/kg			30-150	30	40-140	30
Endosulfan II [2C]	0.330	0.330 ug/kg			30-150	30	40-140	30
Endosulfan sulfate	0.330	0.330 ug/kg			30-150	30	40-140	30
Endosulfan sulfate [2C]	0.330	0.330 ug/kg			30-150	30	40-140	30
Endrin	0.330	0.330 ug/kg			30-150	30	40-140	30
Endrin [2C]	0.330	0.330 ug/kg			30-150	30	40-140	30
Endrin aldehyde	0.330	0.330 ug/kg			30-150	30	40-140	30
Endrin aldehyde [2C]	0.330	0.330 ug/kg			30-150	30	40-140	30
Endrin ketone	0.330	0.330 ug/kg			30-150	30	40-140	30
Endrin ketone [2C]	0.330	0.330 ug/kg			30-150	30	40-140	30
gamma-BHC (Lindane)	0.330	0.330 ug/kg			30-150	30	40-140	30
gamma-BHC (Lindane) [2C]	0.330	0.330 ug/kg			30-150	30	40-140	30
gamma-Chlordane	0.330	0.330 ug/kg			30-150	30	40-140	30
gamma-Chlordane [2C]	0.330	0.330 ug/kg			30-150	30	40-140	30
Heptachlor	0.330	0.330 ug/kg			30-150	30	40-140	30
Heptachlor [2C]	0.330	0.330 ug/kg			30-150	30	40-140	30
Heptachlor epoxide	0.330	0.330 ug/kg			30-150	30	40-140	30
Heptachlor epoxide [2C]	0.330	0.330 ug/kg			30-150	30	40-140	30
Methoxychlor	1.65	1.65 ug/kg			30-150	30	40-140	30
Methoxychlor [2C]	0.330	0.330 ug/kg			30-150	30	40-140	30
Toxaphene	16.7	16.7 ug/kg				30		30
Toxaphene [2C]	33.0	33.0 ug/kg				30		30
Mirex	0.330	0.330 ug/kg			30-150	30	40-140	30
Surr: Decachlorobiphenyl			30-150					
Surr: Decachlorobiphenyl [2C]			30-150					
Surr: Tetrachloro-m-xylene			30-150					
Surr: Tetrachloro-m-xylene [2C]			30-150					

Analytical Method Information

Printed: 07/12/2021 3:31 pm

(Continued)

Pesticides, 8081 target list in Water (EPA 8081B)

Preservation: Cool 4°C

Container: 07_1000mL Amber Glass Cool to 4° C **Amount Required:** 1000 mL **Hold Time:** 7 days

Analyte	MDL	Reporting Limit	Surrogate %Rec	Duplicate RPD	----Matrix Spike---- %Rec	RPD	--Blank Spike / LCS-- %Rec	RPD
4,4'-DDD	0.00400	0.00400 ug/L			30-150	20	40-140	20
4,4'-DDD [2C]	0.00400	0.00400 ug/L			30-150	20	40-140	20
4,4'-DDE	0.00400	0.00400 ug/L			30-150	20	40-140	20
4,4'-DDE [2C]	0.00400	0.00400 ug/L			30-150	20	40-140	20
4,4'-DDT	0.00400	0.00400 ug/L			30-150	20	40-140	20
4,4'-DDT [2C]	0.00400	0.00400 ug/L			30-150	20	40-140	20
Aldrin	0.00400	0.00400 ug/L			30-150	20	40-140	20
Aldrin [2C]	0.00400	0.00400 ug/L			30-150	20	40-140	20
alpha-BHC	0.00400	0.00400 ug/L			30-150	20	40-140	20
alpha-BHC [2C]	0.00400	0.00400 ug/L			30-150	20	40-140	20
alpha-Chlordane	0.00400	0.00400 ug/L			30-150	20	40-140	20
alpha-Chlordane [2C]	0.00400	0.00400 ug/L			30-150	20	40-140	20
beta-BHC	0.00400	0.00400 ug/L			30-150	20	40-140	20
beta-BHC [2C]	0.00400	0.00400 ug/L			30-150	20	40-140	20
Chlordane, total	0.0200	0.0200 ug/L				20		20
Chlordane, total [2C]	0.0200	0.0200 ug/L				20		20
delta-BHC	0.00400	0.00400 ug/L			30-150	20	40-140	20
delta-BHC [2C]	0.00400	0.00400 ug/L			30-150	20	40-140	20
Dieldrin	0.00200	0.00200 ug/L			30-150	20	40-140	20
Dieldrin [2C]	0.00200	0.00200 ug/L			30-150	20	40-140	20
Endosulfan I	0.00400	0.00400 ug/L			30-150	20	40-140	20
Endosulfan I [2C]	0.00400	0.00400 ug/L			30-150	20	40-140	20
Endosulfan II	0.00400	0.00400 ug/L			30-150	20	40-140	20
Endosulfan II [2C]	0.00400	0.00400 ug/L			30-150	20	40-140	20
Endosulfan sulfate	0.00400	0.00400 ug/L			30-150	20	40-140	20
Endosulfan sulfate [2C]	0.00400	0.00400 ug/L			30-150	20	40-140	20
Endrin	0.00400	0.00400 ug/L			30-150	20	40-140	20
Endrin [2C]	0.00400	0.00400 ug/L			30-150	20	40-140	20
Endrin aldehyde	0.0100	0.0100 ug/L			30-150	20	40-140	20
Endrin aldehyde [2C]	0.0100	0.0100 ug/L			30-150	20	40-140	20
Endrin ketone	0.0100	0.0100 ug/L			30-150	20	40-140	20
Endrin ketone [2C]	0.0100	0.0100 ug/L			30-150	20	40-140	20
gamma-BHC (Lindane)	0.00400	0.00400 ug/L			30-150	20	40-140	20
gamma-BHC (Lindane) [2C]	0.00400	0.00400 ug/L			30-150	20	40-140	20
gamma-Chlordane	0.0100	0.0100 ug/L			30-150	20	40-140	20
gamma-Chlordane [2C]	0.0100	0.0100 ug/L			30-150	20	40-140	20
Heptachlor	0.00400	0.00400 ug/L			30-150	20	40-140	20
Heptachlor [2C]	0.00400	0.00400 ug/L			30-150	20	40-140	20
Heptachlor epoxide	0.00400	0.00400 ug/L			30-150	20	40-140	20
Heptachlor epoxide [2C]	0.00400	0.00400 ug/L			30-150	20	40-140	20
Methoxychlor	0.00400	0.00400 ug/L			30-150	20	40-140	20
Methoxychlor [2C]	0.00400	0.00400 ug/L			30-150	20	40-140	20
Toxaphene	0.100	0.100 ug/L				20		20
Toxaphene [2C]	0.100	0.100 ug/L				20		20
Mirex	0.00400	0.00400 ug/L			30-150	20	40-140	20
Surr: Decachlorobiphenyl			30-150					
Surr: Decachlorobiphenyl [2C]			30-150					
Surr: Tetrachloro-m-xylene			30-150					
Surr: Tetrachloro-m-xylene [2C]			30-150					

Analytical Method Information

Printed: 07/12/2021 3:34 pm

Polychlorinated Biphenyls (PCB) in Soil (EPA 8082A)

Preservation: Cool 4°C

Container: 06_8 oz. WM Clear Glass Cool to 4° C **Amount Required:** 100g **Hold Time:** 14 days

Analyte	MDL	Reporting Limit	Surrogate %Rec	Duplicate RPD	----Matrix Spike---- %Rec	RPD	--Blank Spike / LCS-- %Rec	RPD
Aroclor 1016	0.0167	0.0167 mg/kg			40-140	50	40-130	25
Aroclor 1016 (1)								
Aroclor 1016 (2)								
Aroclor 1016 (3)								
Aroclor 1016 (4)								
Aroclor 1016 (5)								
Aroclor 1016 [2C]	0.0167	0.0167 mg/kg			40-140	50	40-130	25
Aroclor 1016 (1) [2C]								
Aroclor 1016 (2) [2C]								
Aroclor 1016 (3) [2C]								
Aroclor 1016 (4) [2C]								
Aroclor 1016 (5) [2C]								
Aroclor 1221	0.0167	0.0167 mg/kg						
Aroclor 1221 (1)								
Aroclor 1221 (2)								
Aroclor 1221 (3)								
Aroclor 1221 [2C]	0.0167	0.0167 mg/kg						
Aroclor 1221 (1) [2C]								
Aroclor 1221 (2) [2C]								
Aroclor 1221 (3) [2C]								
Aroclor 1232	0.0167	0.0167 mg/kg						
Aroclor 1232 (1)								
Aroclor 1232 (2)								
Aroclor 1232 (3)								
Aroclor 1232 (4)								
Aroclor 1232 (5)								
Aroclor 1232 [2C]	0.0167	0.0167 mg/kg						
Aroclor 1232 (1) [2C]								
Aroclor 1232 (2) [2C]								
Aroclor 1232 (3) [2C]								
Aroclor 1232 (4) [2C]								
Aroclor 1232 (5) [2C]								
Aroclor 1242	0.0167	0.0167 mg/kg						
Aroclor 1242 (1)								
Aroclor 1242 (2)								
Aroclor 1242 (3)								
Aroclor 1242 (4)								
Aroclor 1242 (5)								
Aroclor 1242 [2C]	0.0167	0.0167 mg/kg						
Aroclor 1242 (1) [2C]								
Aroclor 1242 (2) [2C]								
Aroclor 1242 (3) [2C]								
Aroclor 1242 (4) [2C]								
Aroclor 1242 (5) [2C]								
Aroclor 1248	0.0167	0.0167 mg/kg						
Aroclor 1248 (1)								
Aroclor 1248 (2)								
Aroclor 1248 (3)								
Aroclor 1248 (4)								
Aroclor 1248 (5)								
Aroclor 1248 [2C]	0.0167	0.0167 mg/kg						
Aroclor 1248 (1) [2C]								
Aroclor 1248 (2) [2C]								
Aroclor 1248 (3) [2C]								

Polychlorinated Biphenyls (PCB) in Soil (EPA 8082A) (Continued)

Analyte	MDL	Reporting Limit	Surrogate %Rec	Duplicate RPD	----Matrix Spike---- %Rec	----Matrix Spike---- RPD	--Blank Spike / LCS-- %Rec	--Blank Spike / LCS-- RPD
Aroclor 1248 (4) [2C]								
Aroclor 1248 (5) [2C]								
Aroclor 1254	0.0167	0.0167 mg/kg				50		25
Aroclor 1254 (1)								
Aroclor 1254 (2)								
Aroclor 1254 (3)								
Aroclor 1254 (4)								
Aroclor 1254 (5)								
Aroclor 1254 [2C]	0.0167	0.0167 mg/kg						
Aroclor 1254 (1) [2C]								
Aroclor 1254 (2) [2C]								
Aroclor 1254 (3) [2C]								
Aroclor 1254 (4) [2C]								
Aroclor 1254 (5) [2C]								
Aroclor 1260	0.0167	0.0167 mg/kg			40-140	50	40-130	25
Aroclor 1260 (1)								
Aroclor 1260 (2)								
Aroclor 1260 (3)								
Aroclor 1260 (4)								
Aroclor 1260 (5)								
Aroclor 1260 [2C]	0.0167	0.0167 mg/kg			40-140	50	40-150	25
Aroclor 1260 (1) [2C]								
Aroclor 1260 (2) [2C]								
Aroclor 1260 (3) [2C]								
Aroclor 1260 (4) [2C]								
Aroclor 1260 (5) [2C]								
Aroclor 1262	0.0167	0.0167 mg/kg						
Aroclor 1262 (1)								
Aroclor 1262 (2)								
Aroclor 1262 (3)								
Aroclor 1262 (4)								
Aroclor 1262 (5)								
Aroclor 1262 [2C]	0.0167	0.0167 mg/kg						
Aroclor 1262 (1) [2C]								
Aroclor 1262 (2) [2C]								
Aroclor 1262 (3) [2C]								
Aroclor 1262 (4) [2C]								
Aroclor 1262 (5) [2C]								
Aroclor 1268	0.0167	0.0167 mg/kg						
Aroclor 1268 (1)								
Aroclor 1268 (2)								
Aroclor 1268 (3)								
Aroclor 1268 (4)								
Aroclor 1268 (5)								
Aroclor 1268 [2C]	0.0167	0.0167 mg/kg						
Aroclor 1268 (1) [2C]								
Aroclor 1268 (2) [2C]								
Aroclor 1268 (3) [2C]								
Aroclor 1268 (4) [2C]								
Aroclor 1268 (5) [2C]								
Total PCBs	0.0167	0.0167 mg/kg						
Total PCBs [2C]	0.0167	0.0167 mg/kg						
Surr: Tetrachloro-m-xylene			30-140					
Surr: Tetrachloro-m-xylene [2C]			30-140					
Surr: Decachlorobiphenyl			30-140					
Surr: Decachlorobiphenyl [2C]			30-140					

Polychlorinated Biphenyls (PCB) in Water (EPA 8082A)

Preservation: Cool 4°C

Container: 07_1000mL Amber Glass Cool to 4° C **Amount Required:** 1000 mL **Hold Time:** 7 days

Analyte	MDL	Reporting Limit	Surrogate %Rec	Duplicate RPD	----Matrix Spike---- %Rec	RPD	--Blank Spike / LCS-- %Rec	RPD
Aroclor 1016	0.0500	0.0500 ug/L		50	40-140	50	40-120	30
Aroclor 1016 (1)								
Aroclor 1016 (2)								
Aroclor 1016 (3)								
Aroclor 1016 (4)								
Aroclor 1016 (5)								
Aroclor 1016 [2C]	0.0500	0.0500 ug/L		50	40-140	50	40-120	30
Aroclor 1016 (1) [2C]								
Aroclor 1016 (2) [2C]								
Aroclor 1016 (3) [2C]								
Aroclor 1016 (4) [2C]								
Aroclor 1016 (5) [2C]								
Aroclor 1221	0.0500	0.0500 ug/L						
Aroclor 1221 (1)								
Aroclor 1221 (2)								
Aroclor 1221 (3)								
Aroclor 1221 [2C]	0.0500	0.0500 ug/L						
Aroclor 1221 (1) [2C]								
Aroclor 1221 (2) [2C]								
Aroclor 1221 (3) [2C]								
Aroclor 1232	0.0500	0.0500 ug/L						
Aroclor 1232 (1)								
Aroclor 1232 (2)								
Aroclor 1232 (3)								
Aroclor 1232 (4)								
Aroclor 1232 (5)								
Aroclor 1232 [2C]	0.0500	0.0500 ug/L						
Aroclor 1232 (1) [2C]								
Aroclor 1232 (2) [2C]								
Aroclor 1232 (3) [2C]								
Aroclor 1232 (4) [2C]								
Aroclor 1232 (5) [2C]								
Aroclor 1242	0.0500	0.0500 ug/L						
Aroclor 1242 (1)								
Aroclor 1242 (2)								
Aroclor 1242 (3)								
Aroclor 1242 (4)								
Aroclor 1242 (5)								
Aroclor 1242 [2C]	0.0500	0.0500 ug/L						
Aroclor 1242 (1) [2C]								
Aroclor 1242 (2) [2C]								
Aroclor 1242 (3) [2C]								
Aroclor 1242 (4) [2C]								
Aroclor 1242 (5) [2C]								
Aroclor 1248	0.0500	0.0500 ug/L						
Aroclor 1248 (1)								
Aroclor 1248 (2)								
Aroclor 1248 (3)								
Aroclor 1248 (4)								
Aroclor 1248 (5)								
Aroclor 1248 [2C]	0.0500	0.0500 ug/L						
Aroclor 1248 (1) [2C]								
Aroclor 1248 (2) [2C]								
Aroclor 1248 (3) [2C]								

Polychlorinated Biphenyls (PCB) in Water (EPA 8082A) (Continued)

Analyte	MDL	Reporting Limit	Surrogate %Rec	Duplicate RPD	----Matrix Spike---- %Rec	----Matrix Spike---- RPD	--Blank Spike / LCS-- %Rec	--Blank Spike / LCS-- RPD
Aroclor 1248 (4) [2C]								
Aroclor 1248 (5) [2C]								
Aroclor 1254	0.0500	0.0500 ug/L		50		50		30
Aroclor 1254 (1)								
Aroclor 1254 (2)								
Aroclor 1254 (3)								
Aroclor 1254 (4)								
Aroclor 1254 (5)								
Aroclor 1254 [2C]	0.0500	0.0500 ug/L						
Aroclor 1254 (1) [2C]								
Aroclor 1254 (2) [2C]								
Aroclor 1254 (3) [2C]								
Aroclor 1254 (4) [2C]								
Aroclor 1254 (5) [2C]								
Aroclor 1260	0.0500	0.0500 ug/L		50	40-140	50	40-120	30
Aroclor 1260 (1)								
Aroclor 1260 (2)								
Aroclor 1260 (3)								
Aroclor 1260 (4)								
Aroclor 1260 (5)								
Aroclor 1260 [2C]	0.0500	0.0500 ug/L		50	40-140	50	40-120	30
Aroclor 1260 (1) [2C]								
Aroclor 1260 (2) [2C]								
Aroclor 1260 (3) [2C]								
Aroclor 1260 (4) [2C]								
Aroclor 1260 (5) [2C]								
Aroclor 1262	0.0500	0.0500 ug/L						
Aroclor 1262 (1)								
Aroclor 1262 (2)								
Aroclor 1262 (3)								
Aroclor 1262 (4)								
Aroclor 1262 (5)								
Aroclor 1262 [2C]	0.0500	0.0500 ug/L						
Aroclor 1262 (1) [2C]								
Aroclor 1262 (2) [2C]								
Aroclor 1262 (3) [2C]								
Aroclor 1262 (4) [2C]								
Aroclor 1262 (5) [2C]								
Aroclor 1268	0.0500	0.0500 ug/L						
Aroclor 1268 (1)								
Aroclor 1268 (2)								
Aroclor 1268 (3)								
Aroclor 1268 (4)								
Aroclor 1268 (5)								
Aroclor 1268 [2C]	0.0500	0.0500 ug/L						
Aroclor 1268 (1) [2C]								
Aroclor 1268 (2) [2C]								
Aroclor 1268 (3) [2C]								
Aroclor 1268 (4) [2C]								
Aroclor 1268 (5) [2C]								
Total PCBs	0.0500	0.0500 ug/L						
Total PCBs [2C]	0.0500	0.0500 ug/L						
Surr: Tetrachloro-m-xylene			30-120					
Surr: Tetrachloro-m-xylene [2C]			30-120					
Surr: Decachlorobiphenyl			30-120					
Surr: Decachlorobiphenyl [2C]			30-120					

Analytical Method Information

Printed: 07/12/2021 3:32 pm

Herbicides, Target List in Soil (EPA 8151A)

Preservation: Cool 4°C

Container: 06_4 oz. WM Clear Glass Cool to 4° C **Amount Required:** 100 g. **Hold Time:** 14 days

Analyte	MDL	Reporting Limit	Surrogate %Rec	Duplicate RPD	----Matrix Spike---- %Rec	RPD	--Blank Spike / LCS-- %Rec	RPD
2,4,5-T	20.0	20.0 ug/kg			10-120	35	10-120	30
2,4,5-T [2C]	20.0	20.0 ug/kg			10-120	35	10-120	30
2,4,5-TP (Silvex)	20.0	20.0 ug/kg			10-120	35	10-120	30
2,4,5-TP (Silvex) [2C]	20.0	20.0 ug/kg			10-120	35	10-120	30
2,4-D	20.0	20.0 ug/kg			10-118	35	10-118	30
2,4-D [2C]	20.0	20.0 ug/kg			10-118	35	10-118	30
2,4-DB	20.0	20.0 ug/kg			10-128	35	10-128	30
2,4-DB [2C]	20.0	20.0 ug/kg			10-128	35	10-128	30
Dalapon	20.0	20.0 ug/kg			30-150	35	40-140	30
Dalapon [2C]	20.0	20.0 ug/kg			30-150	35	40-140	30
Dicamba	20.0	20.0 ug/kg			12-117	35	12-117	30
Dicamba [2C]	20.0	20.0 ug/kg			12-117	35	12-117	30
Surr: 2,4-Dichlorophenylacetic acid (DCAA)			21-150					
Surr: 2,4-Dichlorophenylacetic acid (DCAA) [2C]			21-150					

Herbicides, Target List in Water (EPA 8151A)

Preservation: Cool 4°C

Container: 07_1000mL Amber Glass Cool to 4° C **Amount Required:** 100 mL **Hold Time:** 7 days

Analyte	MDL	Reporting Limit	Surrogate %Rec	Duplicate RPD	----Matrix Spike---- %Rec	RPD	--Blank Spike / LCS-- %Rec	RPD
2,4,5-T	5.00	5.00 ug/L			30-150	30	10-140	30
2,4,5-T [2C]	5.00	5.00 ug/L			30-150	30	10-140	30
2,4,5-TP (Silvex)	5.00	5.00 ug/L			30-150	30	10-139	30
2,4,5-TP (Silvex) [2C]	5.00	5.00 ug/L			30-150	30	10-139	30
2,4-D	5.00	5.00 ug/L			30-150	30	10-140	30
2,4-D [2C]	5.00	5.00 ug/L			30-150	30	10-140	30
2,4-DB	5.00	5.00 ug/L			30-150	30	10-137	30
2,4-DB [2C]	5.00	5.00 ug/L			30-150	30	10-137	30
Dalapon	5.00	5.00 ug/L			30-150	30	40-140	30
Dalapon [2C]	5.00	5.00 ug/L			30-150	30	40-140	30
Dicamba	5.00	5.00 ug/L			30-150	30	10-124	30
Dicamba [2C]	5.00	5.00 ug/L			30-150	30	10-124	30
Surr: 2,4-Dichlorophenylacetic acid (DCAA)			30-150					
Surr: 2,4-Dichlorophenylacetic acid (DCAA) [2C]			30-150					

Analytical Method Information

Printed: 07/12/2021 3:34 pm

Metals, Target Analyte in Soil (EPA 6010D)

Preservation: Cool 4°C

Container: 06_4 oz. WM Clear Glass Cool to 4° C **Amount Required:** 50 **Hold Time:** 180 days

Analyte	MDL	Reporting Limit	Surrogate %Rec	Duplicate RPD	----Matrix Spike---- %Rec	RPD	--Blank Spike / LCS-- %Rec	RPD
Aluminum	5.00	5.00 mg/kg		35	75-125	35	80-120	
Antimony	2.50	2.50 mg/kg		35	75-125	35	80-120	
Arsenic	1.50	1.50 mg/kg		35	75-125	35	80-120	
Barium	2.50	2.50 mg/kg		35	75-125	35	80-120	
Beryllium	0.0500	0.0500 mg/kg		35	75-125	35	80-120	
Cadmium	0.300	0.300 mg/kg		35	75-125	35	80-120	
Calcium	0.500	5.00 mg/kg		35	75-125	35	80-120	
Chromium	0.500	0.500 mg/kg		35	75-125	35	80-120	
Cobalt	0.400	0.400 mg/kg		35	75-125	35	80-120	
Copper	2.00	2.00 mg/kg		35	75-125	35	80-120	
Iron	25.0	25.0 mg/kg		35	75-125	35	80-120	
Lead	0.500	0.500 mg/kg		35	75-125	35	80-120	
Magnesium	5.00	5.00 mg/kg		35	75-125	35	80-120	
Manganese	0.500	0.500 mg/kg		35	75-125	35	80-120	
Nickel	1.00	1.00 mg/kg		35	75-125	35	80-120	
Potassium	5.00	5.00 mg/kg		35	75-125	35	80-120	
Selenium	2.50	2.50 mg/kg		35	75-125	35	80-120	
Silver	0.500	0.500 mg/kg		35	75-125	35	80-120	
Sodium	50.0	50.0 mg/kg		35	75-125	35	80-120	
Thallium	2.50	2.50 mg/kg		35	75-125	35	80-120	
Vanadium	1.00	1.00 mg/kg		35	75-125	35	80-120	
Zinc	2.50	2.50 mg/kg		35	75-125	35	80-120	
Yttrium 371.029						35		

Metals, Target Analyte in Water (EPA 6010D)

Preservation: Add HNO3 to pH<2, Cool 4°C

Container: 10_250mL Plastic pH <2 w/ HNO3 **Amount Required:** 200 **Hold Time:** 180 days

Analyte	MDL	Reporting Limit	Surrogate %Rec	Duplicate RPD	----Matrix Spike---- %Rec	RPD	--Blank Spike / LCS-- %Rec	RPD
Aluminum	0.0500	0.0500 mg/L		20		20	80-120	
Antimony	0.0250	0.0250 mg/L		20	75-125	20	80-120	
Arsenic	0.0150	0.0150 mg/L		20	75-125	20	80-120	
Barium	0.0250	0.0250 mg/L		20	75-125	20	80-120	
Beryllium	0.000500	0.000500 mg/L		20	75-125	20	80-120	
Cadmium	0.00300	0.00300 mg/L		20	75-125	20	80-120	
Calcium	0.0500	0.0500 mg/L		20		20	80-120	
Chromium	0.00500	0.00500 mg/L		20	75-125	20	80-120	
Cobalt	0.00400	0.00400 mg/L		20	75-125	20	80-120	
Copper	0.0200	0.0200 mg/L		20	75-125	20	80-120	
Iron	0.250	0.250 mg/L		20	75-125	20	80-120	
Lead	0.00500	0.00500 mg/L		20	75-125	20	80-120	
Magnesium	0.0500	0.0500 mg/L		20		20	80-120	
Manganese	0.00500	0.00500 mg/L		20	75-125	20	80-120	
Nickel	0.0100	0.0100 mg/L		20	75-125	20	80-120	
Potassium	0.0500	0.0500 mg/L		20		20	80-120	
Selenium	0.0250	0.0250 mg/L		20	75-125	20	80-120	
Silver	0.00500	0.00500 mg/L		20	75-125	20	80-120	
Sodium	0.500	0.500 mg/L		20		20	80-120	
Thallium	0.0250	0.0250 mg/L		20	75-125	20	80-120	
Vanadium	0.0100	0.0100 mg/L		20	75-125	20	80-120	
Zinc	0.0250	0.0250 mg/L		20	75-125	20	80-120	
Yttrium 371.029								

Analytical Method Information

Printed: 06/09/2021 11:03 am

Metals, TAL, ICPMS in Soil (EPA 6020B)

Preservation: Cool 4°C

Container: 06_4 oz. WM Clear Glass Cool to 4° C **Amount Required:** 200 **Hold Time:** 180 days

Analyte	MDL	Reporting Limit	Surrogate %Rec	Duplicate RPD	----Matrix Spike---- %Rec	RPD	--Blank Spike / LCS-- %Rec	RPD
Aluminum	1.00	1.00 mg/kg		35	75-125		80-120	
Antimony	0.100	0.100 mg/kg		35	75-125		80-120	
Arsenic	0.100	0.100 mg/kg		35	75-125		80-120	
Barium	0.100	0.100 mg/kg		35	75-125		80-120	
Beryllium	0.100	0.100 mg/kg		35	75-125		80-120	
Cadmium	0.0500	0.0500 mg/kg		35	75-125		80-120	
Chromium	0.100	0.100 mg/kg		35	75-125		80-120	
Cobalt	0.100	0.100 mg/kg		35	75-125		80-120	
Copper	0.100	0.100 mg/kg		35	75-125		80-120	
Lead	0.100	0.100 mg/kg		35	75-125		80-120	
Iron	1.00	1.00 mg/kg		35	75-125	35	80-120	
Manganese	0.100	0.100 mg/kg		35	75-125		80-120	
Nickel	0.100	0.100 mg/kg		35	75-125		80-120	
Selenium	0.100	0.100 mg/kg		35	75-125		80-120	
Silver	0.100	0.100 mg/kg		35	75-125		80-120	
Thallium	0.100	0.100 mg/kg		35	75-125		80-120	
Vanadium	0.100	0.100 mg/kg		35	75-125		80-120	
Zinc	0.100	0.100 mg/kg		35	75-125		80-120	

Metals, TAL, ICPMS in Water (EPA 6020B)

Preservation: Add HNO3 to pH<2, Cool 4°C

Container: 10_250mL Plastic pH <2 w/ HNO3 **Amount Required:** 200 **Hold Time:** 180 days

Analyte	MDL	Reporting Limit	Surrogate %Rec	Duplicate RPD	----Matrix Spike---- %Rec	RPD	--Blank Spike / LCS-- %Rec	RPD
Aluminum	10.0	10.0 ug/L		20		20	80-120	
Antimony	1.00	1.00 ug/L		20	75-125	20	80-120	
Arsenic	1.00	1.00 ug/L		20	75-125	20	80-120	
Barium	1.00	1.00 ug/L		20	75-125	20	80-120	
Beryllium	0.300	0.300 ug/L		20	75-125	20	80-120	
Cadmium	0.500	0.500 ug/L		20	75-125	20	80-120	
Chromium	1.00	1.00 ug/L		20	75-125	20	80-120	
Cobalt	1.00	1.00 ug/L		20	75-125	20	80-120	
Copper	1.00	1.00 ug/L		20	75-125	20	80-120	
Iron	10.0	10.0 ug/L		20	75-125	20	80-120	
Lead	1.00	1.00 ug/L		20	75-125	20	80-120	
Manganese	1.00	1.00 ug/L		20	75-125	20	80-120	
Nickel	1.00	1.00 ug/L		20	75-125	20	80-120	
Selenium	1.00	1.00 ug/L		20	75-125	20	80-120	
Silver	1.00	1.00 ug/L		20	75-125	20	80-120	
Thallium	1.00	1.00 ug/L		20	75-125	20	80-120	
Vanadium	1.00	1.00 ug/L		20	75-125	20	80-120	
Zinc	1.00	1.00 ug/L		20	75-125	20	80-120	

Analytical Method Information

Printed: 07/12/2021 3:36 pm

Chromium, Hexavalent in Soil (EPA 7196A)

Preservation: Cool 4°C

Container: 06_4 oz. WM Clear Glass Cool to 4° C **Amount Required:** 25 g, **Hold Time:** 30 days

Analyte	MDL	Reporting Limit	Surrogate %Rec	Duplicate RPD	----Matrix Spike---- %Rec	RPD	--Blank Spike / LCS-- %Rec	RPD
Chromium, Hexavalent	0.350	0.500 mg/kg		35	75-125		18.8-206	

Chromium, Hexavalent in Water (EPA 7196A)

Preservation: Cool 4°C

Container: 10_250mL Plastic Cool to 4° C **Amount Required:** 100 mL **Hold Time:** 1 day

Analyte	MDL	Reporting Limit	Surrogate %Rec	Duplicate RPD	----Matrix Spike---- %Rec	RPD	--Blank Spike / LCS-- %Rec	RPD
Chromium, Hexavalent	0.0100	0.0100 mg/L		20	75-125		80-120	20

Analytical Method Information

Printed: 07/12/2021 3:38 pm

Semi-Volatiles, 1,4-Dioxane 8270 SIM-Aqueous in Water (EPA 8270D SIM)

Preservation: Cool 4°C

Container: 09_500 mL Glass Amber **Amount Required:** 500 mL **Hold Time:** 7 days

Analyte	MDL	Reporting Limit	Surrogate %Rec	Duplicate RPD	----Matrix Spike---- %Rec	RPD	--Blank Spike / LCS-- %Rec	RPD
1,4-Dioxane	0.200	0.300 ug/L		30	50-130	30	50-130	30
Surr: 1,4-Dioxane-d8	0.200		36.6-118					
1,2-Dichlorobenzene-d4								

Analytical Method Information

Printed: 06/09/2021 12:13 pm

Semi-Volatiles, 1,4-Dioxane 8270 SIM-Soil in Soil (EPA 8270D SIM)

Preservation: Cool 4°C

Container: 06_4 oz. WM Clear Glass Cool to 4° C **Amount Required:** 250 mL **Hold Time:** 14 days

Analyte	MDL	Reporting Limit	Surrogate %Rec	Duplicate RPD	----Matrix Spike---- %Rec	RPD	--Blank Spike / LCS-- %Rec	RPD
1,4-Dioxane	3.70	10.0 ug/kg		30	40-130	30	40-130	30
Surr: 1,4-Dioxane-d8	4.60		39-127.5					
1,2-Dichlorobenzene-d4								

Analytical Method Information

Printed: 07/12/2021 3:39 pm

PFAS, NYSDEC Target List in Soil (EPA 537m)

Preservation: Cool 4°C

Container: 10_250mL Plastic Cool to 4° C **Amount Required:** 250 mL **Hold Time:** 14 days

Analyte	MDL	Reporting Limit	Surrogate %Rec	Duplicate RPD	----Matrix Spike---- %Rec	RPD	--Blank Spike / LCS-- %Rec	RPD
Perfluorobutanesulfonic acid (PFBS)	0.200	0.250 ug/kg		30	25-150	35	50-130	30
Perfluorohexanoic acid (PFHxA)	0.0659	0.250 ug/kg		30	25-150	35	50-130	30
Perfluoroheptanoic acid (PFHpA)	0.0455	0.250 ug/kg		30	25-150	35	50-130	30
Perfluorohexanesulfonic acid (PFHxS)	0.0310	0.250 ug/kg		30	25-150	35	50-130	30
Perfluorooctanoic acid (PFOA)	0.0772	0.250 ug/kg		30	25-150	35	50-130	30
Perfluorooctanesulfonic acid (PFOS)	0.0438	0.250 ug/kg		30	25-150	35	50-130	30
Perfluorononanoic acid (PFNA)	0.0598	0.250 ug/kg		30	25-150	35	50-130	30
Perfluorodecanoic acid (PFDA)	0.0512	0.250 ug/kg		30	25-150	35	50-130	30
Perfluoroundecanoic acid (PFUnA)	0.116	0.250 ug/kg		30	25-150	35	50-130	30
Perfluorododecanoic acid (PFDoA)	0.0750	0.250 ug/kg		30	25-150	35	50-130	30
Perfluorotridecanoic acid (PFTrDA)	0.0435	0.250 ug/kg		30	25-150	35	50-130	30
Perfluorotetradecanoic acid (PFTA)	0.0747	0.250 ug/kg		30	25-150	35	50-130	30
N-MeFOSAA	0.104	0.250 ug/kg		30	25-150	35	50-130	30
N-EtFOSAA	0.104	0.250 ug/kg		30	25-150	35	50-130	30
Perfluoropentanoic acid (PFPeA)	0.0919	0.250 ug/kg		30	25-150	35	50-130	30
Perfluoro-1-octanesulfonamide (FOSA)	0.0467	0.250 ug/kg		30	25-150	35	50-130	30
Perfluoro-1-heptanesulfonic acid (PFHpS)	0.0493	0.250 ug/kg		30	25-150	35	50-130	30
Perfluoro-1-decanesulfonic acid (PFDS)	0.0512	0.250 ug/kg		30	25-150	35	50-130	30
1H,1H,2H,2H-Perfluorooctanesulfonic acid (6:2 FTS)	0.0660	0.250 ug/kg		30	25-150	35	50-130	30
1H,1H,2H,2H-Perfluorodecanesulfonic acid (8:2 FTS)	0.0256	0.250 ug/kg		30	25-150	35	50-130	30
Perfluoro-n-butanoic acid (PFBA)	0.183	0.250 ug/kg		30	25-150	35	50-130	30
Surr: M3PFBS			25-150					
Surr: M5PFHxA			25-150					
Surr: M4PFHpA			25-150					
Surr: M3PFHxS			25-150					
Surr: Perfluoro-n-[13C8]octanoic acid (M8PFOA)			25-150					
Surr: M6PFDA			25-150					
Surr: M7PFUdA			25-150					
Surr: Perfluoro-n-[1,2-13C2]dodecanoic acid (MPFDoA)			25-150					
Surr: M2PFTeDA			10-150					
Surr: Perfluoro-n-[13C4]butanoic acid (MPFBA)			25-150					
Surr: Perfluoro-1-[13C8]octanesulfonic acid (M8PFOS)			25-150					
Surr: Perfluoro-n-[13C5]pentanoic acid (M5PFPeA)			25-150					
Surr: Perfluoro-1-[13C8]octanesulfonamide (M8FOSA)			10-150					
Surr: d3-N-MeFOSAA			25-150					
Surr: d5-N-EtFOSAA			25-150					
Surr: M2-6:2 FTS			25-150					
Surr: M2-8:2 FTS			25-150					
Surr: M9PFNA			25-150					
MPFOA								

Analytical Method Information

Printed: 07/12/2021 3:39 pm

(Continued)

PFAS, NYSDEC Target List in Water (EPA 537m)

Preservation: Cool 4°C

Container: 10_250mL Plastic Cool to 4° C **Amount Required:** 250 mL **Hold Time:** 14 days

Analyte	MDL	Reporting Limit	Surrogate %Rec	Duplicate RPD	----Matrix Spike---- %Rec	RPD	--Blank Spike / LCS-- %Rec	RPD
Perfluorobutanesulfonic acid (PFBS)	0.294	2.00 ng/L		30	25-150	35	50-130	30
Perfluorohexanoic acid (PFHxA)	0.471	2.00 ng/L		30	25-150	35	50-130	30
Perfluoroheptanoic acid (PFHpA)	0.635	2.00 ng/L		30	25-150	35	50-130	30
Perfluorohexanesulfonic acid (PFHxS)	0.281	2.00 ng/L		30	25-150	35	50-130	30
Perfluorooctanoic acid (PFOA)	0.531	2.00 ng/L		30	25-150	35	50-130	30
Perfluorooctanesulfonic acid (PFOS)	0.292	2.00 ng/L		30	25-150	35	50-130	30
Perfluorononanoic acid (PFNA)	0.574	2.00 ng/L		30	25-150	35	50-130	30
Perfluorodecanoic acid (PFDA)	0.524	2.00 ng/L		30	25-150	35	50-130	30
Perfluoroundecanoic acid (PFUnA)	0.657	2.00 ng/L		30	25-150	35	50-130	30
Perfluorododecanoic acid (PFDoA)	0.777	2.00 ng/L		30	25-150	35	50-130	30
Perfluorotridecanoic acid (PFTrDA)	1.37	2.00 ng/L		30	25-150	35	50-130	30
Perfluorotetradecanoic acid (PFTA)	0.531	2.00 ng/L		30	25-150	35	50-130	30
N-MeFOSAA	0.529	2.00 ng/L		30	25-150	35	50-130	30
N-EtFOSAA	0.557	2.00 ng/L		30	25-150	35	50-130	30
Perfluoropentanoic acid (PFPeA)	0.452	2.00 ng/L		30	25-150	35	50-130	30
Perfluoro-1-octanesulfonamide (FOSA)	0.296	2.00 ng/L		30	25-150	35	50-130	30
Perfluoro-1-heptanesulfonic acid (PFHpS)	0.415	2.00 ng/L		30	25-150	35	50-130	30
Perfluoro-1-decanesulfonic acid (PFDS)	0.574	2.00 ng/L		30	25-150	35	50-130	30
1H,1H,2H,2H-Perfluorooctanesulfonic acid (6:2 FTS)	0.492	5.00 ng/L		30	25-150	35	50-130	30
1H,1H,2H,2H-Perfluorodecanesulfonic acid (8:2 FTS)	0.399	2.00 ng/L		30	25-150	35	50-130	30
Perfluoro-n-butanoic acid (PFBA)	1.63	2.00 ng/L		30	25-150	35	50-130	30
Surr: M3PFBS			25-150					
Surr: M5PFHxA			25-150					
Surr: M4PFHpA			25-150					
Surr: M3PFHxS			25-150					
Surr: Perfluoro-n-[13C8]octanoic acid (M8PFOA)			25-150					
Surr: M6PFDA			25-150					
Surr: M7PFUdA			25-150					
Surr: Perfluoro-n-[1,2-13C2]dodecanoic acid (MPFDoA)			25-150					
Surr: M2PFTeDA			10-150					
Surr: Perfluoro-n-[13C4]butanoic acid (MPFBA)			25-150					
Surr: Perfluoro-1-[13C8]octanesulfonic acid (M8PFOS)			25-150					
Surr: Perfluoro-n-[13C5]pentanoic acid (M5PFPeA)			25-150					
Surr: Perfluoro-1-[13C8]octanesulfonamide (M8FOSA)			10-150					
Surr: d3-N-MeFOSAA			25-150					
Surr: d5-N-EtFOSAA			25-150					
Surr: M2-6:2 FTS			25-150					
Surr: M2-8:2 FTS			25-150					
Surr: M9PFNA			25-150					
MPFOA		0.100 ng/L						

Analytical Method Information

Printed: 08/02/2021 3:30 pm

Total Petroleum Hydrocarbons-DRO (C10-C28) in Soil (EPA 8015D)

Preservation: Cool 4°C

Container: 06_4 oz. WM Clear Glass Cool to 4° C **Amount Required:** 100 g **Hold Time:** 14 days

Analyte	MDL	Reporting Limit	Surrogate %Rec	Duplicate RPD	----Matrix Spike---- %Rec	RPD	--Blank Spike / LCS-- %Rec	RPD
Total Petroleum Hydrocarbons-DRO	3.40	10.0 mg/kg		30	30-150	30	40-140	30
Surr: Triacontane			30-150	30				

Total Petroleum Hydrocarbons-DRO (C10-C28) in Water (EPA 8015D)

Preservation: Cool 4°C

Container: 07_1000mL Amber Glass Cool to 4° C **Amount Required:** 1000 mL **Hold Time:** 7 days

Analyte	MDL	Reporting Limit	Surrogate %Rec	Duplicate RPD	----Matrix Spike---- %Rec	RPD	--Blank Spike / LCS-- %Rec	RPD
Total Petroleum Hydrocarbons-DRO	0.0660	0.100 mg/L		30	40-120	30	40-120	30
Surr: Triacontane			40-150	30				

Analytical Method Information

Printed: 08/02/2021 3:30 pm

Total Petroleum Hydrocarbons-GRO (C5-C10) in Soil (EPA 8015D)

Preservation: Add HCl to pH<2; Store cool at 4°C

Container: 06_2 oz. WM Clear Glass Cool to 4° C **Amount Required:** 20 g. **Hold Time:** 14 days

Analyte	MDL	Reporting Limit	Surrogate %Rec	Duplicate RPD	----Matrix Spike---- %Rec	RPD	--Blank Spike / LCS-- %Rec	RPD
Total Petroleum Hydrocarbons-GRO	0.400	0.800 mg/kg		30	70-130	30		
Surr: SURR: p-Bromofluorobenzene			70-130			30		

Total Petroleum Hydrocarbons-GRO (C5-C10) in Water (EPA 8015D)

Preservation: Add HCl to pH<2; Store cool at 4°C

Container: 00_40mL Clear Vial (pre-pres.) HCl; Cool t **Amount Required:** 80 **Hold Time:** 14 days

Analyte	MDL	Reporting Limit	Surrogate %Rec	Duplicate RPD	----Matrix Spike---- %Rec	RPD	--Blank Spike / LCS-- %Rec	RPD
Total Petroleum Hydrocarbons-GRO	0.400	0.800 mg/L		30				
Surr: SURR: p-Bromofluorobenzene			70-130					

Analytical Method Information

Printed: 08/02/2021 3:32 pm

NJDEP EPH (Cat. 2 Non-Fractionated) in Soil (NJDEP EPH Rev 3.0)

Preservation: Cool 4°C

Container: 06_4 oz. WM Clear Glass Cool to 4° C **Amount Required:** 100 g **Hold Time:** 14 days

Analyte	MDL	Reporting Limit	Surrogate %Rec	Duplicate RPD	----Matrix Spike---- %Rec	RPD	--Blank Spike / LCS-- %Rec	RPD
Total EPH	50.0	50.0 mg/kg			30-140	30	40-140	30
Surr: 1-Chlorooctadecane			31.6-128					
Surr: o-Terphenyl			28.7-124					

NJDEP EPH (Cat. 2 Non-Fractionated) in Water (NJDEP EPH Rev 3.0)

Preservation: Cool 4°C

Container: 07_1000mL Amber Glass Cool to 4° C **Amount Required:** 1000 mL **Hold Time:** 14 days

Analyte	MDL	Reporting Limit	Surrogate %Rec	Duplicate RPD	----Matrix Spike---- %Rec	RPD	--Blank Spike / LCS-- %Rec	RPD
Total EPH	0.100	0.100 mg/L			40-140	50	40-140	30
Surr: 1-Chlorooctadecane			40-140					
Surr: o-Terphenyl			40-140					

Analytical Method Information

Printed: 07/12/2021 3:42 pm

Volatile Organics, EPA TO15 Full List in Air (EPA TO-15)

Preservation: None Required

Container: 12_Summa Canister, 6 Liter **Amount Required:** 6 L **Hold Time:** 30 days

Analyte	MDL	Reporting Limit	Surrogate %Rec	Duplicate RPD	----Matrix Spike---- %Rec	RPD	--Blank Spike / LCS-- %Rec	RPD
1,1,1,2-Tetrachloroethane	0.059	0.10 ppbv		25			70-130	
1,1,1-Trichloroethane	0.084	0.10 ppbv		25			70-130	
1,1,2,2-Tetrachloroethane	0.048	0.10 ppbv		25			70-130	
1,1,2-Trichloro-1,2,2-trifluoroethane (Freon 113)	0.096	0.10 ppbv		25			70-130	
1,1,2-Trichloroethane	0.043	0.10 ppbv		25			70-130	
1,1-Dichloroethane	0.083	0.10 ppbv		25			70-130	
1,1-Dichloroethylene	0.025	0.025 ppbv		25			70-130	
1,2,4-Trichlorobenzene	0.079	0.10 ppbv		25			70-130	
1,2,4-Trimethylbenzene	0.060	0.10 ppbv		25			70-130	
1,2-Dibromoethane	0.040	0.10 ppbv		25			70-130	
1,2-Dichlorobenzene	0.065	0.10 ppbv		25			70-130	
1,2-Dichloroethane	0.062	0.10 ppbv		25			70-130	
1,2-Dichloropropane	0.051	0.10 ppbv		25			70-130	
1,2-Dichlorotetrafluoroethane	0.098	0.10 ppbv		25			70-130	
1,3,5-Trimethylbenzene	0.054	0.10 ppbv		25			70-130	
1,3-Butadiene	0.038	0.30 ppbv		25			70-130	
1,3-Dichlorobenzene	0.067	0.10 ppbv		25			70-130	
1,3-Dichloropropane	0.031	0.10 ppbv		25			70-130	
1,4-Dichlorobenzene	0.060	0.10 ppbv		25			70-130	
1,4-Dioxane	0.083	0.20 ppbv		25			70-130	
2-Butanone	0.059	0.10 ppbv		25			70-130	
2-Hexanone	0.041	0.20 ppbv		25			70-130	
3-Chloropropene	0.076	0.50 ppbv		25			70-130	
4-Methyl-2-pentanone	0.085	0.10 ppbv		25			70-130	
Acetone	0.098	0.20 ppbv		25			70-130	
Acrolein	0.097	0.10 ppbv		25			70-130	
Acrylonitrile	0.079	0.10 ppbv		25			70-130	
Benzene	0.099	0.10 ppbv		25			70-130	
Benzyl chloride	0.054	0.10 ppbv		25			70-130	
Bromodichloromethane	0.034	0.10 ppbv		25			70-130	
Bromoform	0.049	0.10 ppbv		25			70-130	
Bromomethane	0.098	0.10 ppbv		25			70-130	
Carbon disulfide	0.094	0.10 ppbv		25			70-130	
Carbon tetrachloride	0.025	0.025 ppbv		25			70-130	
Chlorobenzene	0.056	0.10 ppbv		25			70-130	
Chloroethane	0.064	0.10 ppbv		25			70-130	
Chloroform	0.092	0.10 ppbv		25			70-130	
Chloromethane	0.049	0.10 ppbv		25			70-130	
cis-1,2-Dichloroethylene	0.025	0.025 ppbv		25			70-130	
cis-1,3-Dichloropropylene	0.041	0.10 ppbv		25			70-130	
Cyclohexane	0.086	0.10 ppbv		25			70-130	
Dibromochloromethane	0.049	0.10 ppbv		25			70-130	
Dichlorodifluoromethane	0.090	0.10 ppbv		25			70-130	
Ethanol	0.10	0.10 ppbv		25			70-130	
Ethyl acetate	0.068	0.20 ppbv		25			70-130	
Ethyl Benzene	0.069	0.10 ppbv		25			70-130	
Hexachlorobutadiene	0.085	0.10 ppbv		25			70-130	
Isopropanol	0.096	0.20 ppbv		25			70-130	
Isopropylbenzene	0.059	0.10 ppbv		25			70-130	
Methyl Methacrylate	0.031	0.10 ppbv		25			70-130	
Methyl tert-butyl ether (MTBE)	0.097	0.10 ppbv		25			70-130	
Methylene chloride	0.070	0.20 ppbv		25			70-130	
Naphthalene	0.097	0.20 ppbv		25			70-130	

Analytical Method Information

(Continued)

Printed: 07/12/2021 3:42 pm

Volatile Organics, EPA TO15 Full List in Air (EPA TO-15) (Continued)

Analyte	MDL	Reporting Limit	Surrogate %Rec	Duplicate RPD	----Matrix Spike---- %Rec	RPD	--Blank Spike / LCS-- %Rec	RPD
n-Butylbenzene	0.054	0.10 ppbv		25			70-130	
n-Heptane	0.043	0.10 ppbv		25			70-130	
n-Hexane	0.080	0.10 ppbv		25			70-130	
n-Propylbenzene	0.093	0.10 ppbv		25			70-130	
o-Xylene	0.024	0.10 ppbv		25			70-130	
p- & m- Xylenes	0.14	0.20 ppbv		25			70-130	
p-Ethyltoluene	0.076	0.10 ppbv		25			70-130	
p-Isopropyltoluene	0.030	0.10 ppbv		25			70-130	
Propylene	0.042	0.10 ppbv		25			70-130	
sec-Butylbenzene	0.056	0.10 ppbv		25			70-130	
Styrene	0.059	0.10 ppbv		25			70-130	
tert-Butylbenzene	0.051	0.10 ppbv		25			70-130	
Tetrachloroethylene	0.049	0.10 ppbv		25			70-130	
Tetrahydrofuran	0.053	0.20 ppbv		25			70-130	
Toluene	0.059	0.10 ppbv		25			70-130	
trans-1,2-Dichloroethylene	0.079	0.10 ppbv		25			70-130	
trans-1,3-Dichloropropylene	0.092	0.10 ppbv		25			70-130	
Trichloroethylene	0.025	0.025 ppbv		25			70-130	
Trichlorofluoromethane (Freon 11)	0.076	0.10 ppbv		25			70-130	
Vinyl acetate	0.062	0.10 ppbv		25			70-130	
Vinyl bromide	0.096	0.10 ppbv		25			70-130	
Vinyl Chloride	0.044	0.050 ppbv		25			70-130	
Xylenes, Total	0.17	0.30 ppbv						
Tentatively Identified Compounds								
Bromochloromethane								
ISTD: 1,4-Difluorobenzene								
ISTD: d5-Chlorobenzene								

ATTACHMENT C

Analytical Methods / Quality Assurance Summary Table

LANGAN

ATTACHMENT C
ANALYTICAL METHODS/QUALITY ASSURANCE SUMMARY TABLE

Matrix Type	Field Parameters	Laboratory Parameters	Analytical Methods	Sample Preservation	Sample Container Volume and Type	Sample Hold Time	Number of Samples to be Collected	Field Duplicate Samples	Equipment Blank Samples	Trip Blank Samples	Ambient Air Samples	MS/MSD Samples
Soil	Total VOCs via PID	Part 375 + TCL VOCs / CP-51 VOCs	EPA 8260C	Cool to 4°C	Two 40-ml VOC vials with 5ml H_2O, one with MeOH or 3 Encore Samplers (separate container for % solids)	14 days, freeze at lab within 48 hours	0	NA	NA	NA	NA	NA
		Part 375 + TCL SVOCs / CP-51 SVOCs	EPA 8270D	Cool to 4°C	4 oz. jar*	14 days extract, 40 days after extraction to analysis						
		1,4-Dioxane	EPA 8270D	Cool to 4°C	8 oz. jar	14 days extract, 40 days after extraction to analysis						
		Part 375 + TAL Metals	EPA 6010C, EPA 7470, EPA 7196A, EPA 9014/9010C	Cool to 4°C	2 oz. jar*	6 months, except Mercury 28 days						
		Hexavalent Chromium	EPA 7196A	Cool to 4°C	2 oz. jar*	28 days						
		Perfluoroalkyl Substances (PFAs)	EPA 1633	Cool to 4°C	8 oz HDPE bottle	90 days						
		Part 375 + TCL Herbicides	EPA 8151A	Cool to 4°C	4 oz. jar*	14 days extract, 40 days after extraction to analysis						
		Part 375 + TCL Pesticides	EPA 8081B	Cool to 4°C	4 oz. jar*	14 days extract, 40 days after extraction to analysis						
		Part 375 + TCL PCBs	EPA 8082A	Cool to 4°C	4 oz. jar*	14 days extract, 40 days after extraction to analysis						
Groundwater	Headspace VOCs via PID, synoptic groundwater level measurement, Temperature, Turbidity, pH, ORP, Conductivity	Part 375 + TCL VOCs	EPA 8260C	Cool to 4°C; HCl to pH <2;no headspace	Three 40-mL VOC vials with Teflon®-lined cap	14 days	6; twice a year	1 per 20 samples (minimum 1)	1 per 20 samples, if needed (minimum 1, if needed)	1 per shipment of VOC samples	NA	1 per 20 samples (minimum 1)
		Naphthalene	EPA 8270D	Cool to 4°C	Two 1-Liter Amber Glass	7 days to extract, 40 days after extraction to analysis						
Soil Vapor	Total VOCs via PID	Part 375 + TCL VOCs	EPA TO-15	NA	6L Summa Cannister	30 days	0	NA	NA	NA	NA	NA

Notes:
*can be combined in one or more 8 oz. jars
mL = milliliter
VOC = Volatile organic compound
SVOC = Semi-volatile organic compound
PCB = Polychlorinated biphenyls
TAL = Total Analyte List
TCL = Target Criteria List
PID = Photoionization detector
Part 375 = New York State Department of Environmental Conservation (NYSDEC) Title 6 New York City Rules and Regulation (NYCRR) Part 375 List.
ORP = Oxidation reduction potential
EPA = U.S. Environmental Protection Agency
NA = Not applicable
ºC = degree Celsius

ATTACHMENT D

Sample Nomenclature

LANGAN

Recommendations for Sample Nomenclature

The recommendations for sample nomenclature outlined below provide for consistency between sample events and projects but, most importantly, establish unique sample IDs that will avoid confusion months or years after the sample has been collected. Furthermore, unique sample IDs are required for any data submitted to the NYSDEC in EDD format or being uploaded to an EQuIS database.

Soil and Sediment Samples



Sample Type	Sample Location	Sample Depth (feet bgs)	Sample Name
Phase II/Remedial Investigation			
Grab	SB01	2 to 4	**SB01_2-4**
	SB02	4	**SB02_4**
Waste Characterization			
Grab	WC01	2 to 4	**WC01_2-4**
	WC02	4	**WC02_4**
Composite	WC01 + WC02	0 to 10	**COMP01_0-10**
Endpoint Sampling			
Grab	EPSW01_N	5	**EPSW01_N_5**
	EPSW01_S	5	**EPSW01_S_5**
	EPSW01_E	5	**EPSW01_E_5**
	EPSW01_W	5	**EPSW01_W_5**
	EPB01	6	**EPB01_6**

- Boring ID (**SB01**_0-0.5) is a sequential number (starting with 01) and should be a minimum of two digits.
- Sample Interval (SB01_**0-0.5**) is separated from the boring ID with an underscore, and the top and bottom interval with a dash. Soil and sediment sample intervals should always be in feet.

Groundwater and Surface Water Samples



Sample Type	Sample Location	Sample Date	Sample Name
Groundwater Sample	MW01	02/21/2013	**MW01_022113**
Surface Water Sample	SW01	02/21/2013	**SW01_022113**

- Well ID or surface water gauge ID (**MW01**_022113) is the common well name and should be a minimum of two digits.
- Sample date (MW01_**022113**) is separated from the well ID (or gauge location) with an underscore and should be provided in MMDDYY format [the date should contain no "/" or "-"].
- If groundwater samples are collected from multiple intervals within one well, you may assign a letter designation (in lower case) to the well ID to differentiate between intervals (i.e., MW01a_022113, MW01b_022113, and MW01c_022113). The letter "a" would indicate the shallowest interval and "c" the deepest. The actual depth intervals should be documented in the project field book or field sheets and the letter designations should be used consistently between sampling events.

Vapor Investigation Samples



Sample Type	Sample Location	Sample Date	Sample Name
Air Sample	IA01	02/21/2013	**IA01_022113**
Soil Vapor Sample	SV01	02/21/2013	**SV01_022113**
Vapor Extraction Well Sample	SVE01 (Inlet/Midpoint/Outlet)	02/21/2013	**SVE01_IN_022113** **SVE01_ MID_022113** **SVE01_ OUT_022113**

- Sample number (**IA01**_022113) should be separated from the sample date by an underscore. Sample numbers should be sequential in order and be a minimum of two digits. The location of each sequential sample number should be documented/ illustrated in project field books or field sheets.
- Sample date (IA01_**022113**) is separated from the sample number with an underscore and should be provided in MMDDYY format [the date should contain no "/" or "-"].

Duplicate Samples

Sample Type	Parent Sample Code	Date	Sample Name
Groundwater Duplicate Sample (DUP)	MW01_022113	02/21/2013	**DUP01_022113**

Field Blanks and Trip Blanks

Sample Type	Date	Sample Name
Equipment Blank (EB)	02/21/2013	**EB01_022113**
Field Blank (FB)	02/21/2013	**FB01_022113**
Trip Blank (TB)	02/21/2013	**TB01_022113**

Matrix Spike/Matrix Spike Duplicate (MS/MSD)

Sample Type	Sample Location	Parent Sample Name	Sample Name
Matrix Spike (MS)	SB01	SB01_2-4	**SB01_2-4_MS**
Matrix Spike Duplicate (MSD)	SB01	SB01_2-4	**SB01_2-4_MSD**

1.0 NOTES

1. Spaces should not be used in sample names.
2. Special characters should not be used in report naming with the exception of – and _.
3. Letter designations should be used consistently between sampling events.
4. According to USEPA's Contract Laboratory Program (CLP) Guidance for Field Samplers (January 2011), field duplicate samples should remain "blind" to the laboratory (i.e., they should have separate CLP Sample numbers). Assign two separate (unique) CLP sample numbers (i.e., one number to the field sample and one to the duplicate). Submit blind to the laboratory.

ATTACHMENT E

Laboratory Standard Operating Procedures for PFAS Analysis

LANGAN

Standard Operating Procedure

Determination of Target Per- and Polyfluoroalkyl Substances (PFAS) in Aqueous and Solid matrices by Isotope Dilution Analysis by HPLC/MS-MS According to EPA Method 1633 Draft 3

Approvals

Laboratory Director/QA Officer



Krys Trafalski

General Manager

Scott R. Hall

Scott Hall

UNCONTROLLED COPY

Controlled Copy No. PFAS_LCMSMS1633, Rev 1.2-____

Issued to: NA

Copyright © 2023
York Analytical Laboratories, Inc.

All rights reserved. The use and copying of this product is subject to approval by York Analytical Laboratories, Inc. Any other use is prohibited. No part of this book may be reproduced in any form or by any means, electronic, mechanical, photocopying, storage in a retrieval system, recording or otherwise, without the prior written permission of York. No part of this book may be translated into any other language without the prior written permission of York.

1. SCOPE AND APPLICATION

This method is used to identify and quantitate specific PFAS compounds in extracts of non-potable water and solid (soil/sediment) samples using HPLC/MS-MS (High Pressure Liquid Chromatography/Tandem Mass Spectrometry). Currently the compounds (40) that are measured by this methodology are listed in Table 1.0 below.

Table 1.0-Target PFAS

Perfluoroalkyl carboxylic acids		
Perfluorobutanoic acid	PFBA	375-22-4
Perfluoropentanoic acid	PFPeA	2706-90-3
Perfluorohexanoic acid	PFHxA	307-24-4
Perfluoroheptanoic acid	PFHpA	375-85-9
Perfluorooctanoic acid	PFOA	335-67-1
Perfluorononanoic acid	PFNA	375-95-1
Perfluorodecanoic acid	PFDA	335-76-2
Perfluoroundecanoic acid	PFUnA	2058-94-8
Perfluorododecanoic acid	PFDoA	307-55-1
Perfluorotridecanoic acid	PFTrDA	72629-94-8
Perfluorotetradecanoic acid	PFTeDA	376-06-7
Perfluoroalkyl sulfonic acids Acid Form		
Perfluorobutanesulfonic acid	PFBS	375-73-5
Perfluoropentansulfonic acid	PFPeS	2706-91-4
Perfluorohexanesulfonic acid	PFHxS	355-46-4
Perfluoroheptanesulfonic acid	PFHpS	375-92-8
Perfluorooctanesulfonic acid	PFOS	1763-23-1
Perfluorononanesulfonic acid	PFNS	68259-12-1
Perfluorodecanesulfonic acid	PFDS	335-77-3
Perfluorododecanesulfonic acid	PFDoS	79780-39-5
Fluorotelomer sulfonic acids		
1*H*,1*H*, 2*H*, 2*H*-Perfluorohexane sulfonic acid	4:2FTS	757124-72-4
1*H*,1*H*, 2*H*, 2*H*-Perfluorooctane sulfonic acid	6:2FTS	27619-97-2
1*H*,1*H*, 2*H*, 2*H*-Perfluorodecane sulfonic acid	8:2FTS	39108-34-4
Perfluorooctane sulfonamides		
Perfluorooctanesulfonamide	PFOSA	754-91-6
N-methyl perfluorooctanesulfonamide	NMeFOSA	31506-32-8
N-ethyl perfluorooctanesulfonamide	NEtFOSA	4151-50-2
Perfluorooctane sulfonamidoacetic acids		
N-methyl perfluorooctanesulfonamidoacetic acid	NMeFOSAA	2355-31-9
N-ethyl perfluorooctanesulfonamidoacetic acid	NEtFOSAA	2991-50-6
Perfluorooctane sulfonamide ethanols		
N-methyl perfluorooctanesulfonamidoethanol	NMeFOSE	24448-09-7
N-ethyl perfluorooctanesulfonamidoethanol	NEtFOSE	1691-99-2
Per- and Polyfluoroether carboxylic acids		
Hexafluoropropylene oxide dimer acid	HFPO-DA	13252-13-6
4,8-Dioxa-3*H*-perfluorononanoic acid	ADONA	919005-14-4
Perfluoro-3-methoxypropanoic acid	PFMPA	377-73-1
Perfluoro-4-methoxybutanoic acid	PFMBA	863090-89-5
Nonafluoro-3,6-dioxaheptanoic acid	NFDHA	151772-58-6
Ether sulfonic acids		
9-Chlorohexadecafluoro-3-oxanonane-1-sulfonic acid	9Cl-PF3ONS	756426-58-1
11-Chloroeicosafluoro-3-oxaundecane-1-sulfonic acid	11Cl-PF3OUdS	763051-92-9
Perfluoro(2-ethoxyethane)sulfonic acid	PFEESA	113507-82-7

Fluorotelomer carboxylic acids		
3-Perfluoropropyl propanoic acid	3:3FTCA	356-02-5
2*H*,2*H*,3*H*,3*H*-Perfluorooctanoic acid	5:3FTCA	914637-49-3
3-Perfluoroheptyl propanoic acid	7:3FTCA	812-70-4

The estimated reporting limits (MRL) based upon the preparation/analysis parameters herein at the time of this revision are approximately 2.0 - 25.0 ng/L (ppt) for aqueous samples and 0.5 - 5.0 µg/kg for solids. The linear range for these PFAS can be extended by dilution. These MRLs are based upon a volume of 250 mL - 500 mL extracted for aqueous samples and 2 - 5 g for solids. Please refer to *Appendix 1: Target Compound Reporting Limits* for limits of detection and quantitation based on a 5 g extract and 500 mL extract for soils and waters, respectively. Please note, MDL/LOD values are based on the initial November 2022 study and are subject to change based on ongoing study data. The most up-to-date study data will be kept on file by the Quality Department and readily available in the test code section(s) of Element LIMS.

This method is "performance-based," which means that modifications may be made without additional EPA review to improve performance (e.g., overcome interferences, or improve the sensitivity, accuracy, or precision of the results) *provided that all* performance criteria in this method are met. Requirements for establishing equivalency are in Section 9.1.2 and include 9.1.2.2c. For Clean Water Act (CWA) uses, additional flexibility is described at 40 CFR 136.6. Changes in performance, sensitivity, selectivity, precision, recovery, etc., that result from modifications within the scope of 40 CFR Part 136.6, and Section 9.0 of this method must be documented, as well as how these modifications compare to the specifications in this method. Changes outside the scope of 40 CFR Part 136.6 and Section 9.0 of this method may require prior review or approval.

2. SUMMARY

Environmental samples are prepared and extracted using method-specific procedures. Sample extracts are subjected to cleanup procedures designed to remove interferences. Analyses of the sample extracts are conducted by HPLC-MS/MS in the multiple reaction monitoring (MRM) mode. Sample concentrations are determined by isotope dilution or extracted internal standard quantification (see Section 10.3) using isotopically labeled compounds added to the samples before extraction.

2.1 Extraction

2.1.1 Aqueous samples are spiked with isotopically labeled standards, extracted using solid-phase extraction (SPE) cartridges and undergo cleanup using carbon before analysis.

2.1.2 Solid samples are spiked with isotopically labeled standards, extracted into basic methanol, and cleaned up by carbon and SPE cartridges before analysis.

2.2 Analysis

2.2.1 Extracts are analyzed by HPLC-MS/MS in MRM mode. Extracts contain Non-extracted Internal Standards (NIS) to monitor instrument performance and are used for quantitative analysis.

2.2.2 Individual PFAS analytes are identified through peak analysis of the quantification and confirmation ions (Precursor and product ions) where applicable.

2.2.3 The concentration of each analyte is calculated using the isotope dilution technique. This approach corrects the target analyte concentration based on recovery of isotopic analogues and essentially behave like extracted internal standards (EIS). For QC purposes, the percent recoveries of the isotope dilution analogues are calculated using the integrated peak areas of isotope performance standards, which are added to the final extract and function as traditional internal standards (non-extracted internal standards), exclusively applied to the isotope dilution analogues.

3. DEFINITIONS

3.1 ANALYTICAL SEQUENCE – A set of samples that are analyzed on the same instrument continuously over a period, typically a 24 hours. An analytical sequence may consist of multiple extraction batches and various matrices and is bracketed by method specific quality control analyses.

3.2 CALIBRATION STANDARD (CAL) – A solution of the method analytes, isotope dilution analogues, and isotope performance standards (Internal standards) prepared from primary dilution and stock standards. The calibration standards are used to calibrate the instrument response with respect to analyte concentration.

3.3 CONTINUING CALIBRATION VERIFICATION (CCV) – A calibration standard containing target compounds, isotopic analogues, and internal standards. The CCV is analyzed periodically to verify the accuracy of an existing calibration.

3.4 EXTRACTION BATCH – A set of up to 20 Field Samples (not including quality control samples) extracted together by the same person(s) during a workday using the same lot of standards and reagents.

3.5 FIELD DUPLICATES – Separate samples collected at the same time and sampling location, shipped, and stored under identical conditions. Method precision, including

the contribution from sample collection procedures, is estimated from the analysis of Field Duplicates. Field Duplicates may be used to prepare duplicate QC samples.

3.6 FIELD BLANK (FB) – An aliquot of reagent water free of constituents of concern that is placed in a sample container in the during field sampling and treated as a sample in all respects. This includes shipment to the sampling site, exposure to sampling site conditions, storage, preservation, and all analytical procedures. The purpose of the FB is to determine if method analytes or other interferences are introduced to the sample from shipping, storage, and the field environment.

3.7 ISOTOPE DILUTION ANALOGUES - Isotopically labeled analogues of the method analytes that are added to the sample prior to extraction in a known amount. Note: Not all target PFAS currently have an isotopically labeled analogue. In these cases, an alternate isotopically labeled analogue is used as detailed in this SOP and reference method.

3.8 ISOTOPE DILUTION TECHNIQUE - An analytical technique for measuring analyte concentration using the ratio of the peak area of a native analyte to that of an isotopically labeled analogue. The analogue is added to a sample in a known amount and carried through the entire analytical procedure. The ration is used to determine a correction factor that is applied to the native compound's result.

3.9 ISOTOPE PERFORMANCE STANDARDS (Internal Standards) - Quality control compounds that are added to all standard solutions and extracts in a known amount and used to measure the relative response of the isotopically labelled analogues that are components of the same solution. For this method, the isotope performance standards are three isotopically labeled analogues of the method analytes. The isotope performance standards are indicators of instrument performance and are used to calculate the recovery of the isotope dilution analogues through the extraction procedure. In this method, the isotope performance standards are not used in the calculation of the recovery of the native analytes.

3.10 METHOD BLANK – An aliquot of reagent water to which known quantities of the method analytes and isotope dilution analogues are added. The results of the MBLK verify method performance in the absence of sample matrix.

3.11 MATRIX SPIKE/MATRIX SPIKE DUPLICATE (MS/MSD) – Aliquots of field samples that have been fortified with a known concentration of target compounds, prior to sample preparation and extraction, and analyzed to measure the effect of matrix interferences. The use of MS/MSD samples is generally not required in isotope dilution methods because the labeled compounds added to every sample provide more performance data than spiking a single sample in each preparation batch.

3.11 SAMPLE DUPLICATE (DUP) – A duplicate aliquot of a field sample analyzed in the same manner as a parent sample to measure reproducibility.

3.12 LIMIT OF QUANTITATION (LOQ) – The smallest concentration that produces a quantitative result with known and recorded precision and bias. The LOQ shall be set at or above the concentration of the lowest initial calibration standard (the lowest calibration standard must fall within the linear range). Determined by matrix through the entire preparation and analysis process.

3.13 METHOD DETECTION LIMIT (MDL) – The minimum measured concentration of a substance that can be reported with 99% confidence that the measured analyte concentration is distinguishable from method blank results (40 CFR 136, Appendix B).

3.14 MINIMUM LEVEL OF QUANTITATION (ML) – The lowest level at which the entire analytical system must give a recognizable signal and acceptable calibration point for the analyte. The ML represents the lowest concentration at which an analyte can be measured with a known level of confidence. It may be equivalent to the concentration of the lowest calibration standard, assuming that all method-specified sample weights, volumes, and cleanup procedures have been employed. Alternatively, the ML may be established by multiplying the MDL (pooled or not pooled, as appropriate) by 3.18 and rounding the result to the number nearest to 1, 2, or 5 x 10n, where n is zero or an integer (see 68 FR 11770).

3.15 PRECURSOR ION – For the purpose of this method, the precursor ion is the deprotonated molecule ($[M-H]^-$) of the method analyte (except for HFPO-DA, in which the precursor ion is formed by decarboxylation). In MS/MS, the precursor ion is mass selected and fragmented by collisionally activated dissociation to produce distinctive product ions of smaller *m/z*.

3.16 PRIMARY DILUTION STANDARD (PDS) SOLUTION – A solution containing the analytes prepared in the laboratory from stock standard solutions and diluted as needed to prepare calibration solutions and other needed analyte solutions.

3.17 PRODUCT ION – For the purpose of this method, a product ion is one of the fragment ions produced in MS/MS by collisionally activated dissociation of the precursor ion.

3.18 INITIAL CALIBRATION VERIFICATION (ICV) – A calibration standard prepared independently from the primary calibration solutions. For this method, the ICV is a repeat of the entire dilution scheme starting with the same stock materials (neat compounds or purchased stock solutions) used to prepare the primary calibration solutions. Independent sources and separate lots of the starting materials are not required, provided the laboratory has obtained the purest form of the starting materials

commercially available. The purpose of the ICV is to verify the integrity of the primary calibration standards.

3.19 QUANTITATIVE STANDARD - A quantitative standard of assayed concentration and purity traceable to a Certificate of Analysis.

3.20 STOCK STANDARD SOLUTION - A concentrated solution containing one or more method analytes prepared in the laboratory using assayed reference materials or purchased from a reputable commercial source with a Certificate of Analysis.

3.21 TECHNICAL GRADE STANDARD – As defined for this method, a technical-grade standard includes a mixture of the branched and linear isomers of a method analyte. For the purposes of this method, technical-grade standards are used to identify retention times of branched and linear isomers of method analytes.

3.22 ANALYTE – A PFAS compound included in this method. The analytes are listed in Table 1.

3.23 CALIBRATION STANDARD (CS) – A solution prepared from a secondary standard and/or stock solutions and used to calibrate the response of the LC-MS/MS instrument.

3.24 CONTINUING CALIBRATION VERIFICATION (CCV) STANDARD – The mid-point calibration standard that is used to verify calibration.

3.25 CFR – Code of Federal Regulations

3.26 EXTRACTED INTERNAL STANDARD (EIS) QUANTIFICATION – The response of the target compound is compared to the response of the labeled analog of another compound in the same LOC.

3.27 INSTRUMENT SENSITIVITY CHECK – solution used to check the sensitivity of the instrument. The solution contains the native compounds at the concentration of the LOQ.

3.28 IPR – INITIAL PRECISION AND RECOVERY; four aliquots of a reference matrix spiked with the analytes of interest and labeled compounds and analyzed to establish the ability of the laboratory to generate acceptable precision and recovery. An IPR is performed prior to the first time this method is used and any time the method or instrumentation is modified.

3.29 OPR - ONGOING PRECISION AND RECOVERY- – Ongoing precision and recovery standard (OPR); a method blank spiked with known quantities of analytes. The OPR is analyzed exactly like a sample. Its purpose is to ensure that the results produced by the

laboratory remain within the limits specified in this method for precision and recovery. Applies to OPR and LLOPR (low level OPR at **2x** the LOQ level).

3.30 SPE – SOLID PHASE EXTRACTION; a technique in which an analyte is extracted from an aqueous solution or a solid extract by passage over or through a material capable of reversibly adsorbing an analyte. Also termed liquid-solid extraction.

4. INTERFERENCES

LC-MS/MS data from blanks, samples, and spikes must be evaluated for interferences. If any interferences are present, take corrective action if necessary. Do not use aluminum foil because PFAAs can be potentially transferred from the aluminum foil to the glassware. Only aluminum foil rinsed with LC/MS grade methanol can be used where necessary.

4.1 PFAS have been used in a wide variety of manufacturing processes, and laboratory supplies should be considered potentially contaminated until they have been tested and shown to be otherwise. The materials and supplies used during the method validation process have been tested and shown to be clean. These items are listed in the Reagents section.

4.2 Method interferences may be caused by contaminants in solvents, reagents (including DI water), sample bottles and caps, and other sample processing hardware that lead to discrete artifacts and/or elevated baselines in the chromatograms. All items such as these must be routinely demonstrated to be free from interferences (less than 1/2 the Reporting Limit), under the conditions of the analysis by analyzing Method Blanks. Subtracting blank values from sample results is not permitted.

4.3 PTFE products can be a source of PFAS (PFOA) contamination. The use of PTFE in the procedure should be avoided. Polypropylene (PP) or polyethylene (PE, HDPE) products may be used in place of PTFE products to minimize PFOA contamination.

4.3.1 Standards and samples are injected from polypropylene autosampler vials with polypropylene or polyolefin snap caps, once. Multiple injections may be performed on Primers when conditioning the instrument for analysis.

4.3.2 Random evaporation losses have been observed with the polypropylene caps causing high Internal Std. recovery after the vial was punctured and sample re-injected. For this reason, it is best to inject standards and samples once in the analytical sequence, then recap with polyolefin caps for storage.

4.3.2 Teflon-lined screw caps have detected PFAS at low concentrations. Repeated injection from the same Teflon-lined screw cap have detected PFNA at increasing concentration as each repeated injection was performed, therefore, it is best to use polypropylene snap caps.

4.3.3 Aqueous samples should not come in contact with any glass containers or pipettes as PFAS analytes can potentially adsorb to glass surfaces. Standards dissolved in organic solvent may be purchased in glass ampoules. These standards in organic solvent are acceptable and subsequent transfers may be performed using glass syringes and pipets. Following extraction, the eluate must be collected in a polypropylene tube prior to concentration to dryness. Concentration to dryness in glass tubes may cause poor recovery.

4.4 LC/MS grade methanol must be used for all steps where methanol is used in this method. HPLC grade methanol has been demonstrated to be acceptable if tested prior to use.

4.5 Matrix interferences may be caused by contaminants that are co-extracted from a sample. The extent of matrix interferences will vary considerably from source to source, depending upon the nature of the sample.

4.5.1 Co-extracted Organic Material - Under normal HPLC conditions matrix effects due to co-extracted organic material enhanced the ionization of 4:2 FTS appreciably. Total organic carbon (TOC) is a good indicator of humic content of the sample.

4.5.2 Solid phase extraction cartridges may be a source of interferences. The analysis of field and laboratory reagent blanks can provide important information regarding the presence or absence of such interferences. SPE cartridges should be sealed while in storage to prevent ambient contamination of the SPE sorbent.

4.6 Contamination by carryover can occur whenever a high-concentration and low concentration samples are sequentially analyzed. To reduce carryover, the sample syringe in automatically rinsed with solvent between injections. These operations are programmed into the LC multi-sampler system.

4.7 Volumetric glassware and syringes are difficult to clean after being used for solutions containing high levels of PFOA. These items should be labeled for use only with similarly concentrated solutions or verified clean prior to re-use. To the extent possible, disposable labware is used.

4.8 Both branched and linear PFAS isomers can potentially be found in the environment. Linear and branched isomers are known to exist for PFOS, PFOA, PFHxS, and PFBS, based upon scientific literature. We have also seen branched isomers for PFHpA, NMeFOSAA, NEtFOSAA and PFNA. If multiple isomers are present for one of these PFAS they likely are adjacent peaks that completely resolve or not, but usually with a deflection point resolved during peak integration. The later of these peaks matches the retention time of its labeled linear analog. In general, earlier peaks are the branched isomers and are not the result of peak splitting.

Currently, all these species are available as linear isomers. Some available branched and linear reference standards of the technical mixtures for these specific PFAS are used to ensure that all appropriate peaks are included during peak integration. These species currently include PFOA, PFHxS, NMeFOSAA, and NEtFOSAA. These branched isomers elute before the linear isomer and are integrated and reported as total for those species. Others are also included at this time such as those listed in section 7.3.4.

4.9 In an attempt to reduce PFOS bias, it is required that *m/z* 499>80 transition be used as the quantitation transition.

5. SAMPLE HANDLING

5.1 **Aqueous Samples** - samples are collected by our clients in 250 or 500ml HDPE bottles with unlined HDPE or polypropylene caps and filled to the neck. Each sample submitted should be submitted in triplicate-with one used for determination of Suspended solids and possible pre-screening. Sub-sampling should be avoided whenever possible. When historical data are available indicating high levels of PFAS, sub-sampling may be an advisable option.

5.2 **Soil Samples** – samples are collected in wide mouth 125- or 250-mL HDPE bottles with PP unlined caps.

5.3 SAMPLE SHIPMENT AND STORAGE/HOLDING TIMES – Maintain all aqueous samples protected from light at 0 - 6 ºC from the time of collection until shipped to the laboratory. Samples must be shipped as soon as practical with sufficient ice to maintain the sample temperature below 6 ºC during transport. Samples are to be received by the

laboratory within 48 hours of collection. The laboratory must confirm that the sample temperature is 0 - 6 ºC upon receipt. Once received by the laboratory, the samples may be stored at ≤ -20 ºC, or at 0 - 6 ºC, until sample preparation. However, the allowable holding time for samples depends on the storage temperature, as described below:

5.3.1 Aqueous samples may be held in the laboratory for up to 90 days from collection, when stored at ≤ -20 ºC and protected from the light. When stored at 0 - 6 ºC and protected from the light, aqueous samples may be held for up to **28 days**, with the caveat that issues were observed with certain perfluorooctane sulfonamide ethanols and perfluorooctane sulfonamidoacetic acids after **7 days**. These issues are more likely to elevate the observed concentrations of other PFAS compounds via the transformation of these precursors if they are present in the sample.

5.3.2 Solid samples (soils and sediments) may be held for up to 90 days, if stored in the dark at either 0 - 6 ºC or ≤ -20 ºC, with the caveat that samples may need to be extracted as soon as possible (within 7 days) if NFDHA is designated as an important analyte by the customer.

5.4 **SAMPLE EXTRACT HOLDING TIMES** – Store sample extracts in the dark at less than 0 - 4 ºC until analyzed. If stored in the dark at less than 0 - 4 ºC, sample extracts may be stored for up to 90 days, with the caveat that issues were observed for some ether sulfonates after 28 days. These issues may elevate the observed concentrations of the ether sulfonates in the extract over time. Samples may need to be extracted as soon as possible if NFDHA is an important analyte.

6. APPARATUS AND MATERIALS (as listed or demonstrated equivalents)

6.1 250 - 500 mL polypropylene bottles with polypropylene caps. VWR Scientific or equivalent: Part no. 414004-125, 12 pk. Alternate: White PP unlined lid L238WH and 16oz. clarified PP single wall jar 70-400 neck, item J066-Containers and Packaging.com or equivalent.

6.2 Transport Tube: Virgin Polypropylene, White, Plastic, 10 mL Capacity, 16 mm OD, 93 mm Overall Lg, Self-Standing, 250 PK, Item 710Z420, Gamut.com (Grainger), with PP cap or equivalent.

6.3 Graduated cylinders, 50, 100, 250, 500 and 1000mL, Polypropylene, VWR Scientific or equivalent

6.4 Analytical Balance, 0.0001g., checked for accuracy each day of use with Class S weights, certified annually by an outside service.

6.5 Extract concentrators: Organomation Model N-EVAP 112, 24 position concentrator with water batch control and nitrogen supply controls or equivalent

6.6 3.1 Micron in-line filters, Promochrom only

6.7 1.0-2.0 mL polypropylene snap cap vials, Agilent part no. 5182-0567 or equivalent

6.8 Snap caps, polypropylene or olefin, 11 mm, 11/9k, Agilent Part no. 5182-0542

6.9 Solid Phase Extraction Tubes: for EPA 1633: WAX (weak anion exchange mixed mode polymeric sorbent – Phenomenex No. 8B-S038-HCH 200 mg or Waters Oasis 150 mg Cat. # 186002493. Must have a pKa > 8 to remain positively charged during the extraction. Alternate is Agilent Bond Elute WAX 200 mg-cat. No. 5610-2151

6.10 Syringes, Hamilton or equivalent 5.0 µL, 10 µL 25 µL, 100 µL, 250 µL, 500 µL, Teflon free

6.11 Solid Phase Extraction System-automated-Promochrom 8 position autosampler system for 6 mL capacity SPE tubes. System retrofit to remove all PTFE components and replaced with PEEK tubing or PFAS free tubing. Automated bottle rinsing feature required with 3.1 um in line PP filters.

6.12 Nitrogen Evaporation System- TurboVap nitrogen evaporation system operated at less than 55C.

6.13 LC/MS-MS system- Agilent 1260 or 1290 HPLC system interfaced to an Agilent 6470A or 6460C Triple Quadrupole system. The instrument control and qualitative/quantitative software is Mass Hunter versions B.8.0 and B.9.0 or later.

6.13.1 HPLC System-Agilent 1260 or 1290 Infinity II

6.13.1.1 The Agilent 1260 or 1290 Infinity II HPLC system is configured with temperature-controlled column oven compartment. 4 column configuration, temperature controlled (refrigerated) auto sampler

compartments, injection valve, proportioning valves, variable flow controls and variable injection capabilities.

6.13.1.2 The delay column (PFAS and other interference removal) is an Agilent Eclipse Plus C18, 4.6mm x 50 mm, 3.5 um-Part no. 959943-902 or equivalent.

6.13.1.3 The analytical column is a Restek Raptor C18 part no. 9304252 50mm x 2.1 mm ID, 1.8 u particle size or equivalent.

6.13.2 Agilent LC/MS-MS- Agilent 6470AAR/6460C

6.14.2.1 Agilent model 6470AAR/6460C triple Quadrupole system with Agilent Jet Stream ESI source. UHP nitrogen is used as cell gas and High purity nitrogen is delivered for the sheath gas from a Peak Scientific nitrogen generator system.

6.14 Vortex Mixer- Benchmark Industries or equivalent

6.15 Variable Speed shaker table, 18" x 12"- Orbital Shaker- Jiangau Tenlin Instr. Co., Ltd., Model no. TLSK-III 20-230 RPM, 0-999 min, or equivalent

6.16 Centrifuge, 50 mL, Premiere Model XC-2450 Series Centrifuge 6 x 50 mL, 3500 RPM max., or equivalent

6.17 Mechanical Pipettors- 10-100 µL; 100-1000 µL; 1000-5000 µL-4 E'S Scientific or equivalent, calibrated quarterly.

6.18 Vortex Mixer- Benchmark Industries or equivalent

6.19 pH paper, short range 6-8 and full range with 0.5 pH readability- VWR Scientific or equivalent

6.20 15 mL PP or HDPE Centrifuge tubes, Corning Part no. 430791

6.21 3 mL Disposable Transfer pipets, PE, VWR part no. 16001-176

6.22 1.0 mL polypropylene snap cap vials, Agilent part no. 5182-0567

6.23 Snap caps, polypropylene, 11 mm, 11/9k, Agilent Part no. 5182-0542

6.24 2mL self-standing PP microcentrifuge snap cap tubes, SKS Scientific part no. 0747-17

6.25 Collection tubes, 15 mL graduated PP or HDPE Centrifuge tubes, Corning Part no. 430791

6.26 Disposable 10 mg scoops, PP

6.27 Ultrasonic mixer

6.28 10 mL disposable syringes, PP or HDPE, luer fitting

6.29 13mm or 25 mm 0.2 um Nylon membrane filters, PALL Acrodisc or equivalent

7. REAGENTS AND STANDARDS (as listed or demonstrated equivalents)

7.1 ALL REAGENTS and STANDARDS MUST BE LOGGED INTO THE ELEMENT LIMS SYSTEM. This includes lot numbers, expiration, open and prepared dates, receipt date, Certification/traceability documents from supplier(s) if provided and preparer.

7.2 SOLVENTS and REAGENTS-all as listed or equivalents

7.2.1 Methanol, hypergrade for LC/MS. (Merck) from Sigma Aldrich Part no. 1060354000 or equivalent (HPLC Plus grade is an acceptable alternate)

7.2.2 Water, hypergrade for LC/MS. (Merck) from Sigma Aldrich Part no. 1153334000 or equivalent (HPLC plus grade is an acceptable alternate). Alternatively, York PFAS free water demonstrated ion and PFAS free can be used.

7.2.3 Acetic Acid, glacial. ACS grade or equivalent.

7.2.4 Ammonium Hydroxide, conc. Cert. ACS grade, 28-30% in water, Sigma Aldrich part no.1054231000, or equivalent

7.2.5 Methanolic Potassium Hydroxide (0.05 M) – add 3.3 g of KOH to 1L MeOH.

7.2.6 Sodium Hydroxide, pellets, ACS grade- Sigma Aldrich part no. 221465-500G, or equivalent

7.2.7 Potassium Hydroxide, pellets, ACS grade

7.2.8 Ammonium Acetate – ACS grade or better, Ammonium Acetate, HPLC or cert. ACS grade. Sigma Aldrich Part no. 73594-100-G-F or equivalent.

7.2.9 Ammonium Acetate 5 mM for HPLC in aqueous solution: HPLC gradient A-- Weigh 0.3854 g (+ 0.0005) Ammonium Acetate and add to 1-liter hypergrade Water. Mix until dissolved then sonicate for 5 mins. To remove air bubbles. Stability - 2 weeks.

7.2.10 **Methanolic Ammonium Hydroxide 0.3 %** - take 2.5 mL of conc. ammonium hydroxide into 247 mL MeOH (measure the 247 mL in a PP graduated cylinder-they are under QQ1 somewhere). Use a mechanical pippetor to add the 2.5 mL (not strictly quantitative FYI)-**Make 4 bottles of this**. *Used for soil extractions*. - 1 month shelf life.

7.2.11 **Methanolic Ammonium Hydroxide 1.0 %** - take 8.25 mL of conc. ammonium hydroxide into 242 mL MeOH (measure the 242 mL in a PP graduated cylinder-they are under QQ1 somewhere). Use a mechanical pipet to add the 8.25 mL (not strictly quantitative FYI)- **Make 4 bottles of this -***used in Promochrom*-1 month life.

7.2.12 **Aqueous Ammonium Hydroxide 3%-** take 24.8 mL of ammonium hydroxide and add 242 mL PFAS free water. 3-month life- *used for pH adjustment*

7.2.13 **Methanol with 4% water, 1% ammonium hydroxide and 0.625% acetic acid** – add ammonium hydroxide (3.3 mL, 30%), reagent water (1.7 mL) and acetic acid (0.625 mL) to methanol (92 mL), store at room temperature, replace after 1 month. **This solution is used to prepare the instrument blank, calibration standards, and is used to dilute the extracts of samples that exceed the calibration range.**

7.2.14 **Formic Acid 0.1M-aqueous** – add 873 µL formic acid into 250 mL PFAS free water- **Make 2 bottles of this-***used to prepare 7.2.16 below.* 2-year life

7.2.15 **Formic Acid, 0.3M**-aqueous- add 2.62 mL (2619 µL) into 250 mL PFAS free water- **Make 4 bottles of this -***used in Promochrom*-2 year life

7.2.16 **Formic Acid methanolic 1:1, 0.1M formic acid**- mix equal volumes of Methanol and 0.1 M formic acid- **Make 4 bottles of this -***used in Promochrom*-2 year life

7.2.17 **Formic Acid 5% aqueous**- add 12.5 mL Formic acid into 250 mL PFAS free water. *Used for pH adjustment.* 2-year shelf life

7.3 **Stock Standards**

Stock Standards are purchased in mid to high concentration levels from Wellington Laboratories, Inc. Guelph, ONT, CA. Currently, Wellington is the preferred supplier of these materials. As a second source verification, prepare a mid-level from the stock independently from the preparation used for initial calibration. Document this preparation in Element. See Attachments 1,2, and 3 for detailed information.

7.3.1 Internal Standards (7-Non-Extracted –NIS)) used for the method are MPFOA, MPFOS, M3PFBA, MPFDA, MPFHxA, MPFHxS and MPFNA. These are purchased at 250 - 1000 ng/mL depending upon the ISTD in a

mixture. This mixture is purchased from Wellington Labs in 1.2 mL volumes with the following **part no.: MPFAC-HIF-IS**. Stored at 4C or less unopened this solution has a 5-year shelf life. Once opened, the life is one year from open date.

7.3.2 Isotopic Surrogate Analogs (24 isotopes) are purchased for the method described from Wellington Labs at 250-5000 ng/mL levels, depending upon the isotope. Part no. is **MPFAC-HIF-ES**.

7.3.3 Stock Standard mixtures of both linear and branched isomers of the EPA 1633 40 compound list are purchased from Wellington Labs at varying concentrations in 5 different mixtures under part nos. PFAC-MXJ, PFAS-MXI, PFAC-MXH, PFAC-MXG, PFAC-MXF.

7.3.4 Second source standard mixture of both linear and branched isomers of the EPA 1633 40 compound list is purchased from Absolute Standards at 2 µg/mL under part no. 65735.

7.3.5 Qualitative branched isomers mix- individual available branched and linear mixes for the following PFAS are used daily to allow for qualitative knowledge of the PFAS branched isomers so they are integrated/included in quantitative analysis: T-PFOA, lp-PFNA, br-FOSA, br-NEtFOSA, br-NMeFOSA, br-NEtFOSE and br-NMeFOSE. These are purchased at 50,000 ng/mL levels from Wellington Labs-the names above are the Catalogue nos. These have a 5-year life at stock concentrations.

Make a 100 ng/mL Intermediate mix by adding 2.0 µL of the individual stocks up to 1.0 mL with MeOH.

Make a working solution by taking 200 µL of the 100 ng/mL intermediate into 750 µL of cal matrix solution (7.2.13) and add 50 µL of 1:10 EIS mix.

Transfer 300 µL to an autosampler vials, add 3 µL of ISTD working mix, cap vortex, and store until needed. Shelf life is 1 year.

The summary below details the procurement requirements for this method - All from Wellington Laboratories, Inc. except the second source from Absolute Standards:

Description	Part nos.	Comes in
40 Compound Target 1633 list targets	PFAC-MXJ PFAS-MXI PFAC-MXH PFAC-MXG PFAC-MXF	4 Days – 1.2 mL
Isotopic Surrogates-24	MPFAC-HIF-ES	4 Days – 1.2 mL
EPA 1633 – 7 Internal Std.	MPFAC-HIF-IS	4 Days – 1.2 mL
Method 1633 PFCs – Cal Std.	65735	2 days – 1.2 mL

7.4 Preparation of Standards

7.4.1 Preparation of Working Standards and Intermediates from STOCK Materials

All stock standards are prepared by the vendor in methanol containing a bit of sodium hydroxide to prevent losses of target PFAS compounds due to potential esterification in methanolic solution. The stocks come prepared with 4 molar equivalents (a 3x excess) of sodium hydroxide for stocks at the 50 µg/mL levels. This insures their stability with respect to potential loss due to esterification. The basic solution ensures that any acidic sites on the glass ampules or acidic impurities in the methanol are neutralized to prevent ester formation and forms the sodium salt of the PFAS to stabilize it.

When preparing any intermediate level standards, the dilution must be prepared in alkaline methanol to prevent the above from occurring.

To do this, prepare a 5.0 mM NaOH in Hypergrade Methanol (or LC/MSMS grade) by dissolving 0.02 g. of sodium hydroxide into 100 mL of MeOH. This has a 2-week life.

For intermediate standards that are made to 10 mL final volume, add 100 µL of 5.0 mM NaOH/MeOH as part of the preparation. This results in a final concentration of NaOH at 0.05 mM.

For intermediate standards prepared to a final volume of 1.0 mL. add 10 µL of the 5.0 mM NaOH/MeOH.

For working calibration standards/CCV/SCV made to 500 µL final volume, using the mixture detailed in section 7.1.13 (MeOH/Water/acetic acid/ammonium hydroxide). This approximates the matrix of the final extracts for analysis.

7.4.2 Storage and Handling of Standards

All working standards should be stored at either room temperature or 4 °C provided the containers are sealed properly.

Stock Standards may be stored at 4 - 10 °C but before using must sit to allow equilibration to room temperature followed by either vigorous vortex mixing or sonication for 3-5 mins.

7.4.3 Detailed Standards Preparation Procedure-EPA 1633

7.4.4 Internal Standards-*See Attachment 1*

Internal Standards are purchased as a **stock mixture** at 250-1000 ng/mL.

These as transferred to a snap cap vial that has been pre-rinsed with 5 mM NaOH/MeOH then allowed to dry.

7.4.4.1 Working level of Non-Extracted Internal Standard (NIS) – make a 1:1 dilution of the stock by taking 500 µL of the Stock and adding 500 µL MeOH.

Use as is by adding 3 µL to 300 µL volumes for QC samples, or calibration.

7.4.5 Isotopic Surrogates (Extracted Internal Standards)- *See Attachment 2*

7.4.5.1 Stock Surrogates are purchased as a mixture at 250-5000 ng/mL. These are transferred to a snap cap vial that has been pre-rinsed with 5 mM NaOH/MeOH then allowed to dry.

Option 1- Use Stock as received and add 25 µL to all samples/QC to be extracted.

Option 2- Prepare **2** mL of Working EIS by preparing a 1:2 dilution to yield 125-2500 ng/mL for use as follows:

Take 1000 µL of the Surrogate Stock, plus 25 µL of 5 mM NaOH/MeOH and 975 µL MeOH to give 2.0 mL final volume**. 50 µL are added to ALL preparation blanks, samples, and QC**. This is sufficient for approx. 40 x 50 µL additions to all blanks, QC, and samples.

This corresponds to adding 5 to 100 ng of EIS compounds to the initial samples and QC. The final volume of extractions will typically be 5.0 ml so this yields 1-20 ng/mL of the isotope EISs in the final extract for analysis.

For calibration, the Stock mix at 250-5000 ng/mL is used by adding 100 uL up to 1.0 mL final volume to yield 25/500 ng/mL in each calibration level as directed in the calibration section 7.4.7.1.

7.4.6 Target Analytes- EPA 1633- *See Attachment 3*

The target analytes for this method are purchased commercially from Wellington Labs using the five part numbers described in Section 7.3.3. They contain the method target analytes only at varying concentrations. These mixtures are transferred from their glass ampules to snap cap vials that have been pre-rinsed with 5 mM NaOH/MeOH then allowed to dry. Again, these are the nominal concentrations and the actual anion concentrations for those present as salts are listed in the documentation and are reflected in both Mass Hunter and Element.

Preparation of a 1.0 mL volume of a 10x intermediate of each of the 5 mixes for Calibration. Some of the higher levels on the curve use aliquots of the stock as shown in Figure 2.

Scale the volume accordingly if less is desired. Note that the EPA 1633 mixes come 1.2 mL per vial so this recipe may consume one vial quickly.

7.4.6.1 OPR and LLOPR - these are a mid-level blank spike and low-level blank spike (at 2x the LOQ). These are prepared as follows from the EPA 1633 Target mixtures (5 components) by taking 200 µL of each STOCK into a snap cap vial giving 1.0 mL final volume.

1. Element ID Y22B199 - PFAC-MXF mix 200 µL.
2. Element ID Y22B200 - PFAC-MXG mix 200 µL.
3. Element ID Y22B201 - PFAC-MXH mix 200 µL.
4. Element ID Y22B204 - PFAC-MXI mix 200 µL.
5. Element ID Y22B205 - PFAC-MXJ mix 200 µL.

For OPR (BS) at mid-level add 100 µL to each matrix for the batch OPR and for the **LLOPR add 20 µL** of the spike mix and process through all steps of the specific matrix preparation.

7.4.7 Second Source Standard

The Second Source intermediate standard is prepared in a similar manner to Target Analytes detailed in the previous section whereby a 10x intermediate is prepared by diluting 100 µL of stock obtained from Absolute Standards (2 µg/mL) in 1.0 mL of solvent. The final concentration of this standard is nominally 200 ng/mL.

7.4.8 Calibration

Calibration of the LC-MSMS systems is done by an eight-level calibration covering the range 0.2 to 1650 ng/mL, nominal. Various PFAS species are present as salts and at differing concentrations and these are reflected in Mass Hunter and Element as their actual concentrations. Six to eight levels are prepared depending upon the analyte. These levels are prepared as directed below using the internal standards, surrogates, and target analytes from above.
This is made to a final volume of 1000 µL in the matrix described in section 7.1.13 (MeOH/Water/acetic acid/ammonium hydroxide)

This preparation excludes the ISTD in the initial preparation. After preparation as directed, withdraw 300 µL of each level into a 500 µL PP vial and add 3 µL of ISTD before analysis, cap, and vortex to mix.
These are stored at <10C and are stable for 6 months when prepared as directed.

7.4.7.1 Calibration Curve Preparation - Based upon a final volume of 1.0 mL in CAL Matrix Solution*

See Attachment 4 for details.

EPA 1633 Calibration Standard Preparation
Rev 1.,0 10/03/22

For Final volume of 1.0 mL
Recipe uses both a 1:10 intermediate for some levels AND the Stock for other points as indicated
All standards in Stds refrig. Adjacent to QQQ1 N2 generator in box labeled EPA 1633 standards- all are opened, labeled and good to use.

Level	*Stock: Y22B201* **1633 MXH Targets Intermediate @10x * uL of MXH 10x Interm.**	*Stock: Y22B200* **1633 MXG Targets Intermediate at 10x* ul of MXG interm.**	*Stock: Y22B199* **1633 MXF Targets Intermediate at 10x* ul of MXF interm.**	*Stock: Y22B204* **1633 MXI Targets Intermediate at 10x* ul of MXI interm.**	*Stock: Y22B205* **1633 MXJ Targets Intermediate at 10x* ul of MXJ interm.**	*Stock: Y22B198* **1633 EIS isotope Mix Intermediate at 10x uL of EIS Interm.**
1	2	2	4	2	2.5	50
2	5	5	10	5	6.25	50
3	12.5	12.5	25	12.5	15.6	50
4	25	25	50	25	31.3	50
5	50	50	100	50	62.5	50
6	125	125	250	125	15.6 of Stock	50
7	25 of Stock	25 of Stock	50 of Stock	25 of Stock	31.2 of Stock	50
8	62.5 of STOCK	62.5 of STOCK	125 of STOCK	62.5 of STOCK	78.0 of Stock	50

* 100 uL up to 1 mL in MeOH

*CAL MATRIX: Methanol with 4% water, 1% ammonium hydroxide and 0.625% acetic acid – Prepared by adding ammonium hydroxide (3.3 mL, 30%), reagent water (1.7 mL) and acetic acid (0.625 mL) to methanol (92 mL), store at room temperature, replace after 1 month. This solution is used to prepare the instrument blank and is used to dilute the extracts of samples that exceed the calibration range.

Amount of CAL Matrix to make up to 1.0 mL Final volumes:

CAL LEVEL	µL of CAL Matrix
1	937.5
2	918.8
3	871.9
4 *	793.7
5	637.5
6	309.0
7	843.8
8	609.5

INTERNAL STANDARD MIX (non-extracted IS-NIS). Mix 500 µL of STOCK ISTD at 250-1000 ng/mL with 500 µL of Methanol. This results in 125-500 ng/mL Intermediate ISTD. See 7.4.4.1.

Add 3.0 µL to 300 µL of each level 1-8 in a 500 µL PP autosampler vials and cap with polyolefin cap, vortex to mix and run. Add 3 µL to 300 µL of all sample/QC extracts before analysis.

*Level 4 is also used as the CCV for each analysis sequence run initially, then after every 10 samples and at the end of the sequence. Multiple vials should be prepared for this level.

7.4.9 Checking the Efficacy of the Surrogate/Spike Mixes

On a monthly basis the surrogate (EIS) and spike mixes from the vials used for spiking are assayed to ensure stability. These are prepared for the analysis by taking 3.0 µL of the surrogate (EIS) mix and 3 µL of the Spike mix into 294 µL MeOH/Water/Acetic Acid/Ammonium hydroxide from 7.1.13, then add 3 µL of NIS (ISTD). This yields a 1:100 dilution of the EIS and Spike mixes. Use 100 as the dilution factor in the Mass Hunter worklist.

7.4.10 Second Source - Initial Calibration Verification (ICV)

The initial calibration verification is prepared in a similar manner to calibration standards whereby 50 µL of intermediate stock is diluted in 1.0 mL of solvent. The final concentration of this standard is nominally 10 ng/mL.

8. PROCEDURE

8.1 Preventative and Routine Maintenance

HPLC/MS/MS Preventative Maintenance	
As Needed: Change pump seals. Change in-line filters in autosampler (HPLC). Check/replace in-line frit if excessive pressure or poor performance. Replace column if no change following in- line frit change. Clean needle. Replace or clean Capillary Replace fused silica tube in ESI interface. Clean lenses. Clean skimmer. Ballast rough pump 30 minutes. Check Nozzle flow pattern	**Daily (When in use)** Check solvent reservoirs for sufficient level of solvent. Verify that pump is primed, operating pulse free. (ripple < 1%) Check needle wash reservoir for sufficient solvent. Verify capillary heater temperature functioning. Verify vaporizer heater temperature. Verify rough pump oil levels. Verify turbo-pump functioning. Verify nitrogen pressure for auxiliary and sheath gasses. Possible Checktune
Semi-Annually Replace oil mist and odor elements. Replace activated alumina filter if applicable	**Annually** Vacuum system components including fans and fan covers. Clean/replace fan filters, if applicable.

8.2 Sample Preparation (Extraction, Clean-up and Concentration)- Aqueous Matrices

A summary of the steps for the steps related to aqueous samples are shown in Figure 1.0 and in the summary below.

1. Determine % Suspended Solids – 10.0 mL $\pm$ 0.02 mL through a tared 0.2 um PP filter. Dry filter $\geq$ 12 hours @ 105C, cool in desiccator. Calc % TSS.
2. Check pH with short range pH paper to insure pH = 6.5 $\pm$ 0.5. Adjust as necessary with either 5% aqueous formic acid to lower pH or with 3% aqueous ammonium hydroxide to raise pH.
3. Weigh sample bottle as is to $\pm$ 0.1 g.-remove cap first since that will not be weighed later since autosampler caps are used.
4. Homogenize sample by inversion 3-4 x-place full volume on Promochrom System using WAX SPE cartridges.
5. Set up MBLK, OPR at 2x LOQ (low LCS) and mid-level OPR (mid-level LCS)-spike with 10 µL of Spike mix for LLOPR and 100 µL of spike mix for mid-OPR.
6. Spike all with 25 µL EIS solution (isotopic surrogates)

7. Follow Promochrom method for EPA 1633
8. Initiate SPE program EPA1633AQ on the Promochrom system
9. Once the program is finished there will be 5 ml in the collection tube. If less, make up to exactly 5.0 mL with MeOH.
10. Remove the sample bottle from the Promochrom system and weigh the empty bottle. That will determine the weight (volume for water) assume 1 g = 1.0 mL. Enter this value into the element bench sheet and the initial volume.
11. Add 25 µL of concentrated acetic acid to each collection tube and vortex to mix.
12. Add 10 mg of activated carbon to all samples and QC. Hand mix and vortex mix for no more than 2 minutes.
13. Centrifuge at 2800 rpm for approx. 10 minutes.
14. Filter the final volume through 0.2 um nylon filter using a syringe.
15. If the client provides only 250 mL of sample, in order to meet reporting limits, it may be required to concentrate the unfiltered extract by a factor of at least 2 on a TurboVap at 1.2 Liters/min with nitrogen at <55 ^{o}C. For example, if the final volume is 5.0 mL, concentrate to 2.0 mL final volume (2.5 x concentration). If 500 mL is provided, skip this step.
16. Enter the final volume achieved into the bench sheet in Element.
17. Transfer a portion of the final extract to a 2 mL snap cap, labeled.
18. Take a 300 µL portion of the extract into a 500 µL PP autosampler vial, add 3 µL of NIS (non-extracted internal std.). Cap, vortex, store at <6 ^{o}C.
19. Sample is ready for analysis.

Figure 1.0 Aqueous Sample Preparation Steps



8.2.1 To measure sample initial volume for aqueous samples, remove the cap and weight the bottle and record the weight in the sample weight. For MBLK, LLOPR and OPR use 250-500 mL volumes). After SPE processing, be sure the empty bottle is dry and weight to determine the amount of sample in grams (essentially equal to volume in mL). Use that number for the initial volume in Element LIMS.

8.2.2 For every 20 field samples (Field blanks are considered field samples in as they are treated as such), a blank (MBLK), blank spikes, (2 levels-LLOPR and OPR as BS1 and BS2 respectively. A matrix spike is not necessary since isotope dilution is used. If an MS/MSD is required by a specific project, spike 100 µL of the mid-level BS mix (OPR).

8.2.3 All polypropylene equipment including graduated cylinders and sample transfer lines/reservoirs should be washed prior to using with extraction solvent (Methanol).

8.2.4 Add 25 µL of EIS (isotopic surrogates) (250/5000 ng/mL) to each sample and QC sample, recap, and invert to mix well.

8.2.5 Add, 20 µl (low level spike), 100 µL (mid-level spike)

8.2.6 Using the Promochrom automated system, run a cleaning run. Be sure the reservoirs of LC/MS grade methanol and HPLC plus grade water or equivalent are full. Prime all lines and align all components.

8.2.7. Load in the EPA1633 method and adjust the sample volume to 10 mL more than the highest volume container measured by visual comparison to a calibrated bottle of the same size. Please refer to *Appendix 2: Promochrom Method* detailing the automated SPE extraction method on the Promochrom system.

8.2.8 The SPE method solvents for extractions are as follows:

- Solvent 1 = MeOH
- Solvent 2 = H_2O
- Solvent 3 = 0.3 M Formic acid,
- Solvent 4 = 1:1 0.1M Formic Acid/MeOH,
- Solvent 5 = MeOH with 1% ammonium hydroxide (“Basic MeOH”)
  W1 = Aqueous waste, W2 = Organic waste

8.2.9 Place labeled 15 mL graduated collection vessels in the sample collection tray and use Element labels to identify the vials at this point. Print 2 sets of labels for each since they will be used after the concentration step as well. These are graduated.

8.2.10 Connect the bottles to the automated system.

8.2.12 Initiate the EPA1633Aq SPE Extraction Program. Each run is approximately 1 hour 45 minutes.

8.2.13 **Evaporation Options** - Aqueous Samples

N-EVAP systems

8.2.13.1 The resulting 5 mL extracts are not further concentrated unless Work Plan reporting limits need to be lower than standard RLs. When this is required by the Work Plan, the extracts and QC are transferred to the N-EVAP concentrator systems operated at 50-55 degrees C (never more than 55C) in their original collection vials. The nitrogen flow is initiated at 1.2 ml/min and adjusted on each individual sample to provide a gentle stream causing a slight disturbance at the surface of the methanol extracts.

8.2.13.2 As this evaporation proceeds the walls of each vessel are rinsed with methanol when the volume is approximately 2.5 mL and then again when the volume is reduced to just below 2.0 mL. Then Bring up the final volume to 2.5 mL. This is a 2x concentration when needed.

8.2.14 Swirl final extract, make up to 2.0 mL with methanol. Using a disposable polypropylene pipet, carefully transfer to a 2 mL PP snap cap vial.

8.2.15 Withdraw an aliquot of 300 µL into a 500 µL autosampler vial (PP) and add 3.0 µL of ISTD (NIS) mix.

8.2.16 Cap with polyolefin flexible caps and vortex to mix.

8.2.17 Store Extracts at <6^{o}C until analysis.

8.3 Sample Preparation (Extraction, Clean-up, and Concentration) - Soil Matrices

1. Determine % solids: use 5 grams; dry at 110C $\geq$ 12 hours.
2. Mix sample with a stainless-steel spatula to homogenize-exclude Sticks, vegetation, rocks and the like.
3. Remove 5.0 g. from the homogenized sample container. Add to a tared 50 mL centrifuge tube. Determine the weight $\pm$ 0.01 g.
4. Prepare QC using clean matrix (Ottawa Sand) wetted with 1 mL PFAS free water in 50 mL centrifuge tubes.
5. For all samples, QC blanks and LCSs (LLOPR and ML OPR) and a 25 µL aliquot of EIS onto the soil. The current Element standard ID is Y22J305. For the OPRs add

appropriate amount of spike solution (20 µL for LLOPR and 100 µL for OPR. The current Element Std ID is Y22J304.

6. Swirl the samples to mix then let sit for 30 minutes.
7. Add 10 mL of 0.3% methanolic ammonium hydroxide to each centrifuge tube.
8. Vortex to mix then shake on the shaker table for 30 minutes.
9. Next, centrifuge at 3500 rpm for 5 minutes or 2800 rpm for 10 minutes.
10. Transfer the supernatant liquid to a clean 50 mL centrifuge tube
11. Add 15 mL of 0.3% methanolic ammonium hydroxide to each of the original centrifuge tubes.
12. Vortex to mix then shake on the shaker table for 30 minutes.
13. Next, centrifuge at 3500 rpm for 5 minutes or 2800 rpm for 10 minutes.
14. Transfer the supernatant liquid to the centrifuge tubes from 10.0 above.
15. Add another 5 mL of 0.3% methanolic ammonium hydroxide to each of the original centrifuge tubes.
16. Vortex to mix then shake on shaker table for 30 minutes.
17. Next, centrifuge at 3500 rpm for 5 minutes or 2800 rpm for 10 minutes.
18. Transfer the supernatant liquid to the centrifuge tubes from 10.0 above.
19. Add 10 mg of activated carbon to the combined extract using a 10 mg scoop and hand swirl for 2 minutes (never more than 5 minutes of losses of Target PFAS will occur)
20. Centrifuge at 3500 rpm for 5 minutes or 2800 rpm for 10 minutes
21. Immediately Decant into a 50 mL centrifuge tube.
22. Place in TurboVap or on the N-EVAP system and concentrate at 55 deg. C to a final volume of approx. 7 mL at a nitrogen flow of 1.2 mL/min.
23. Add 35-40 mL of PFAS free water to the tube and vortex to mix.
24. Check the pH= 6.5 $\pm$ 0.5 if not adjust accordingly using 5% formic acid to lower pH or 3% aqueous ammonium hydroxide to raise pH to within this range.
25. Set up the soil EPA 1633 method on the Promochrom be sure volume is set to 50 ml for sample size. Please refer to *Appendix 2: Promochrom Method* detailing the automated SPE extraction method on the Promochrom system.
26. Place samples and QC centrifuge tubes on the autosampler
27. Once the program is finished, note the final volume and use that in the Element bench sheet as final volume. Should be 5.0 mL. If less make up to 5.0 mL with MeOH.
28. Add 25 µL of concentrated acetic acid to each collection tube and vortex to mix.
29. Add 10 mg of carbon to all samples and QC and mix for 2 minutes (no more than 5 minutes).
30. Immediately centrifuge at 2800 rpm for 10 minutes.

31. Filter the extract through a 0.2 um nylon membrane using a syringe and filter into a 2 mL snap cap vial.
32. When ready for analysis, remove 300 µL of extract and transfer to a 500 µL autosampler vial. Add 3 µL of NIS (internal standard), vortex to mix. Cap with polyolefin flexible caps and vortex to mix.
33. Store Extracts at <6°C until analysis
34. Samples/QC are now ready for analysis.

8.4 Sample Analysis--Running Samples/QC - Acquisition Method

The acquisition method is detailed in Attachment 4 (HPLC) and Attachment 5 (MS/MS) of this SOP. The method is an HPLC with dynamic MRM method with precursor and product ions with specific acquisition parameters to maximize sensitivity and specificity. This list may be modified to add other PFAS target analytes as necessary.

8.3.1 The triple Quadrupole (QQQ) system must be optimized for each target analyte (including surrogates and internal standards) using the Mass Hunter Optimizer program. This program determines the most abundant precursor and product ions for each compound and their abundances. These data are then used to build an MRM (multiple reaction monitor) method for acquisition. This is done initially or after any major maintenance procedures are performed to the triple quadrupole system. A high-level standard is used for this in the $[M-H]^-$ mode or M-COOH for HFPO-DA.

8.3.2 The MS/MS is checked for tuning on a weekly basis (if necessary) before analysis using the Tune context by selecting the CHECKTUNE radio button. This is done only in negative ion mode since that is what we are operating under. If the Checktune fails, run the Autotune program-note: this takes approx. 45 mins. in negative mode. After autotune or any tuning adjustment, a re-calibration of the instrument is required.

8.3.3 Before any QC or samples can be run, the HPLC must be allowed to purge for at least thirty minutes. This purge must be done using the initial mobile phase conditions used in the method must be allowed to run for 15 minutes or until pressure has stabilized (ripple must be < 1%)

8.3.4 An instrument sequence (Worklist) is then made. It should begin with a blank, a primer (5 ng/mL) followed by a blank with ISTD to establish system cleanliness.

8.3.5 After a successful initial calibration has been completed, the analytical sequence for a batch of samples analyzed during the same time period is as follows. Standards and sample extracts must be brought to room temperature and

vortexed prior to aliquoting into an instrument vial in order to ensure homogeneity of the extract.

8.3.6 **Analysis Sequence**

1. Instrument Blank *
2. Instrument Sensitivity Check –**LOQ Standard Level (SEQ-CAL 1) S/N > 3:1**
3. Calibration Verification Standard (CCV)
4. Qualitative Identification Standards –Branched PFAS
   PFOA, PFNA, PFOSA, NMeFOSA, NEtFOSA, NEtFOSE, and NMeFOSE.
5. Instrument Blank (SEQ-CCB) *
6. Method Blank (Batchxxxx-BLK1)
7. Low-level OPR (LLOPR) (Batchxxxx-BS1)
8. OPR (Batchxxxx-BS2)
9. Field Samples (10 or fewer)
10. Calibration Verification Standard (SEQ-CCVn)
11. Instrument Blank (SEQ-CCBn) *
12. Field Samples (10 or fewer)
13. Calibration Verification Standard (SEQ-CCVn)
14. Instrument Blank (SEQ-CCBn) *

* Contains solvent system for calibration, NIS, and EIS

8.3.7 The run can end with a script to put the instrument into standby mode.

8.4 Daily Sample Preparation/Analysis Sequence

- Prepare extracts for analysis by placing a 300 µl aliquot of sample extract containing 3 µL of internal standards into a PP auto-sampler vial. Apply Polyolefin cap.
- Confirm that the samples loaded on the auto-sampler were entered correctly in the injection log. Make any necessary corrections.
- Run instrument CCV checks at the RL (0.25-0.5 ng/mL), then at a mid-level and high level rotating every ten samples (5, 25 ng/mL) and ending with a mid-level CCV.
- Enter the Worklist (injection sequence) into the instrument software and load samples onto the auto-sampler in the order shown above in Section 8.3.6

8.5 Data Review

The Agilent Mass Hunter Quantitation program is used to review all data. All identifications are based upon retention time (RT) of the transition of the precursor to product ion represented by a peak. Retention times should not vary

more than ± 0.5 minutes as compared to the initial CCV analyzed for an analytical sequence. All positive detections of target PFAS must be less than the high point concentration of the calibration curve.

8.5.1 Since certain PFAS species are manufactured by different processes the presence of branched as well as linear isomers may be found. To properly quantitate these species, the analyst must sum the related branched and linear isomers. This affects the following species: PFOS, PFHxS, PFOA, PFNA, PFOSA, NMeFOSA, NEtFOSA, NEtFOSE, and NMeFOSE.

8.5.2 Any detection greater than the upper limit of the calibration curve requires dilution into the upper half of the curve, where possible.

9. CALIBRATION

9.1 Initial Calibration

The initial calibration covers the range 0.20 ng/mL to 1560 ng/mL nominal conc. or higher depending upon the linearity of the PFAS species. After acquisition, the data are quantitated in Mass Hunter and the default calibration model for target compounds is generated using Quadratic regression, FORCED through the origin where applicable. All same level species (EIS) used average response factor model. Depending upon the response and accuracy at each level as shown in the Mass Hunter program, use Linear, Forced, weighted (1/x) or quadratic, Forced, with or without weighting to achieve the best fit which is based upon the best accuracy on a compound-by-compound basis. In any case, the correlation coefficient must be greater than 0.990. Average Response Factor (RF) or Relative Standard Deviation (RSD) should be $\underline{\leq}$ 20% where used.

9.1.1 The calibration levels as shown in Section 7.4.7 use 8 levels. All points are included in the calibration with the exception of some species that saturate at levels 7 and 8.

9.2 Calibration Verification

9.2.1 Relative Standard Error (RSE): For calibrations using an average RF curve fit, the relative standard deviation (RSD) is the measure of relative error. However, if a quadratic regression is used RSE should be calculated for calibration curve. RSE is calculated by the Mass Hunter software. The RSE for all method analytes should be ≤ 20% to establish instrument linearity.

9.2.2 An independently prepared Initial Calibration Verification must be run immediately following initial calibration. The concentration of this standard should be in the middle of the calibration range (e.g., 5.0 ng/mL) and prepared from a separate preparation as that of the calibration. Unless project-specific data quality objectives are required, the values from the second-source check should be ± 30% of the expected concentration.

9.2.2.1 **Corrective Action**: Quantitative sample analyses should not proceed for a failing ICV. Recalibrate and re-run the ICV if necessary.

An independently prepared Initial Calibration Verification must be run immediately following initial calibration. The concentration of this standard should be in the middle of the calibration range (e.g., 5.0 ng/mL) and prepared from a separate preparation as that of the calibration. Unless project-specific data quality objectives are required, the values from the second-source check should be ± 30% of the expected concentration.

Corrective Action: Quantitative sample analyses should not proceed for a failing ICV. Recalibrate and re-run the ICV if necessary.

9.3 Continuing Calibration Verification

The first CCV is at a mid-level and analyzed every 10 client samples including a closing CCV.

The mid-Level CCV must be ± 30% of the true value.

Corrective Action: If any of the required calibration check criteria fail, the system must be evaluated, and any appropriate instrument repair or maintenance must be performed. Sample data are unacceptable and must be rerun. Reinjection of the standard may be done. If the calibration check standard still fails, the system must be recalibrated.

10. Quality Control

10.1 Initial Demonstration of Capability (IDOC)

10.1.1 The initial demonstration requirement of EPA 1633 must be acceptable before analysis of samples may begin. To establish the ability to generate acceptable precision and recovery, the laboratory must perform the following operations for each sample matrix type to which the method will be applied by that laboratory.

The IDOC includes the following key elements:

- Initial Demonstration of Precision and Recovery (IPR)
- MDL determination

10.1.2 Initial Demonstration of Precision and Recovery-IPR

- Extract, concentrate, and analyze four aliquots of aqueous and soil matrices spiked with 100 µL of the native spike solution OPR Mix Y22J304, 50 µL of the EIS solution no. Y22J305. At least one method blank, matching the matrix being analyzed, must be prepared with the IPR batches by matrix. All sample processing steps that are used for processing samples, including preparation and extractions, cleanup and concentration, must be included in this test.

- Using results of the set of four analyses, compute the average percent recovery (R) of the extracts and the relative standard deviation (RSD) of the concentration for each target and EIS compound.
- For each native and isotopically labeled compound, compare RSD and % recovery with the corresponding limits for initial precision and recovery in Table 5. If RSD and R for all compounds meet the acceptance criteria, system performance is acceptable, and analysis of blanks and samples may begin. *Note these acceptance criteria are not finalized and are based upon a single lab validation. Data for this table is derived from the single-laboratory validation study and are only provided as examples for this draft method. The data will be updated to reflect the inter-laboratory study results in a subsequent revision. Therefore, these criteria will change after inter-laboratory validation. Several sections of this method state that Table 5 criteria are required, this is standard language that will be applicable when the method is finalized.*

10.1.3 MDL Determination

MDL Determination –In order to perform the MDL study, 7 total extractions are performed on 3 different days (Extraction Day 1= 3 LRBs and 3 LFBs, Extraction Day 2 is 2 of each, and Extraction Day 3 is also 2 of each).

The levels extracted represent approx. 3-5 x the expected LOQ.

Once extracted, the analyses are conducted on 3 separate days the MDL is determined according to the EPA MDL protocol defined in Definition and

Procedure of the Determination of the Method Detection Limit, Revision 2 Dec. 2016 as detailed below:

Make all computations as specified in the analytical method and express the final results in the method-specified reporting units.

Calculate the sample standard deviation (SD) of the replicate spiked sample measurements and the sample standard deviation of the replicate method blank measurements from all instruments to which the MDL will be applied.

Compute the MDLs (the MDL based on spiked samples) as follows:

MDL_s = 3.143 x SD (for seven replicates; SD = Standard Deviation)

Compute the MDL_b (MDL based on method blanks-LRBs) as follows:

- If none of the blanks give numerical results, then the MDL_b does not apply.
- If only some of the blanks (but not all) give a result, set the MDL_b to the highest result found.
- If ALL method blanks show a detection, then use the following calculation to determine MDL_b:

MDL_b = Average of Blank Detections + (3.143 x Std. Dev.)

Calculate the final MDL by selecting the greater of MDL_s or MDL_b.

10.2 On-going QC Requirements

Preparation Batches are defined at the sample preparation step. Batches should be kept together through the whole analytical process as far as possible, but it is not mandatory to analyze prepared extracts on the same instrument or in the same sequence.

The quality control batch is a set of up to 20 samples of the same matrix processed using the same procedure and reagents within the same time period. The quality control batch may contain a matrix spike/matrix spike duplicate (MS/MSD), two laboratory control samples (LCS-LLOPR and OPR) and a method blank. Laboratory generated QC samples (Blank, LLOPR, OPR, MS/MSD) do not count toward the maximum 20 samples in a batch. Field QC samples are included in the batch count. In some cases, at client request, the MS/MSD may be replaced with a matrix spike and sample duplicate.

10.2.1 METHOD BLANK - One method blank must be extracted with every prep batch of similar matrix, not to exceed twenty (20) samples. For aqueous samples the matrix is Lab reagent water. For Soils the method blank matrix is

Ottawa sand. Criteria:

- The method blank must not contain any analyte at or above 1/2 the LOQ (Reporting Limit).

- Re-extraction and reanalysis of samples associated with an unacceptable method blank is required when reportable concentrations are determined in the samples.

10.2.2 LABORATORY CONTROL SAMPLES (LCS- also called OPR and LLOPR) must be extracted with every process batch of similar matrix, not to exceed twenty (20) samples. The LCS is an aliquot of laboratory matrix (e.g., water for aqueous spiked with analytes of known identity and concentration and isotopic surrogate analogs. The OPRs must be processed in the same manner and at the same time as the associated samples. Recovery for Aqueous low level OPR target analytes are 40-150% until more data are derived. For all other Aqueous OPR levels recovery targets are 50-150%. These data are based upon EPA 1633 draft ranges that will change and are not used for acceptance/rejection but are reported until such time that fully validated acceptance ranges are provided in the final version of the method.

10.2.3 Matrix spike/Matrix spike duplicate (MS/MSD or MS/MSD). These are not typically required since each sample contains isotopic PFAS analogues that correct for any matrix effects. If the client requests them, then they are processed accordingly but are not a requirement of this method. If done they are by matrix, not to exceed twenty (20) samples. An MS/MSD pair is aliquots of a selected field sample spiked with analytes of known identity and concentration. The MS/MSD pair must be processed in the same manner and at the same time as the associated samples. Spiked analytes with recoveries or precision outside of the Laboratory control limits are flagged accordingly. Until enough statistical data per matrix is available, no criteria are offered. If a specific QA Project Plan has required limits, this is preempted. Any outliers must be qualified accordingly.

10.2.4 Initial calibration verification (ICV) –A second source standard is not required for this method. A second independently prepared mid-level standard is prepared and used for this purpose and analyzed after the ICAL. The concentration should be at the mid-range of the curve and must recover within 70-130 % of expected value.

Corrective actions for the ICV include:

- Rerun the ICV
- Remake or acquire a new ICV.
- Evaluate the instrument conditions.

- Evaluate the initial calibration standards.
- Rerun the initial calibration.

10.2.5 Internal Standard- The Non-extracted Internal Standard (NIS) is added to each field and QC sample prior to analysis. The IS response (peak area) must not deviate by more than 50-200% from the mean response (peak area) of the initial calibration. If the areas are low for all the field samples and QC samples in the batch, it suggests a loss of instrument sensitivity, while low areas in only some field or QC samples suggests a possible bad injection.

Corrective action includes:

- Reinject the questionable samples.
- Verifying the CCV NIS areas are compliant with the range, if so, this suggests either matrix effects or may require a small dilution to mitigate interference if only some of the NIS compounds are affected.
- Qualify affected data.

10.3 Initial Demonstration of Capability (IDC)

Initial Demonstration of Capability involves the following processes listed ion Table 1.0 as follows.

Table 1.0 - Initial Demonstration of Capability (IDC)

Requirement	Specification and Frequency	Acceptance Criteria
Initial Demonstration of Precision and Recovery (IPR)	Extract, concentrate, and analyze four aliquots of the matrix (aqueous and soil) spiked with target native standard solution, EIS solution and finally the NIS (ISTD). Extract a method blank of each matrix with each matrix IPR batch. All steps that are used for processing samples, including preparation and extraction must be included.	Using results of the set of four analyses, compute the average percent recovery (R) of the extracts and the relative standard deviation (RSD) of the concentration for each target and EIS compound.
		For each native and isotopically labeled compound, compare RSD and % recovery with the corresponding limits for initial precision and recovery in Table 5. If RSD and R for all compounds meet the acceptance criteria, system performance is acceptable, and analysis of blanks and samples may begin.
Method Detection Limit (MDL)	Method detection limit (MDL) - Each laboratory must also establish MDLs for all the analytes using the MDL procedure at 40 CFR Part 136, Appendix B. An MDL determination must be performed for all target compounds.	The minimum level of quantification (ML) can be calculated by multiplying the MDL by 3.18 and rounding to the nearest integer

Calibration Verification (ICV or SCV) *Section 9.1.5*	Analyze a mid-level ICV, each time a new calibration is performed or at a minimum, quarterly. The ICV must be an independent dilution beginning with the common starting materials used for ICAL. No 2nd source is required due to availability.	Results must be 70-130% of true value.

10.4 **QC Requirements**

Ongoing QC requirements are detailed in Table 3.0 as follows.

Table 3.0 QC Requirements

Summary of Quality Control		
Method Reference	**Requirement**	**Specification and Frequency**
Section 10.1	Mass Calibration	Annually and on as-needed basis
Section 10.1.7	Mass Calibration Verification	After mass calibration
Section 10.3	Initial Calibration (ICAL)	Minimum 6 calibration standards for linear models and 7 calibration standards for non-linear models.
Sections 10.2.2, 14.4	Retention Time (RT) window	After ICAL and at the beginning of analytical sequence
Sections 7.3.1, 9.4	Extracted Internal Standard (EIS) Analytes	All CAL standards, batch QC and field samples
Sections 7.3.2	Non-extracted Internal Standards (NIS)	All CAL standards, batch QC and field samples
Sections 7.3.4, 10.3.1, 13.3	Instrument Sensitivity Check (ISC)	Daily, prior to analysis
Section 14.2	Calibration Verification (CV) (CCV)	At the beginning and every 10 samples and at the end
Section 14.6	Instrument Blank	Daily prior to analysis and after high standards
Sections 9.1.3, 9.5, 14.7	Method Blank (MB)	One per preparation batch
Section 14.5	Ongoing Precision Recovery (OPR)	One per preparation batch
Section 11.0	Limit of Quantitation Verification (LLOPR)	Prior to analyzing samples
Section 11.0	Matrix Spike (MS/MSD)	One per preparation batch (if required) Normally not needed, since Isotope dilution is employed

11.0 DATA REVIEW, CALCULATIONS AND REPORTING

Samples concentrations are determined using either linear regression or quadratic regression FORCED through the origin. Weighted ($1/x$ or $1/x^2$) may assist with low level accuracy and is recommended where necessary. All calibration curves have greater than 6 points. Any target analyte exceeding the calibration range will require dilution.

11.1 Data interpretation

All sample data calculations are performed by the Agilent Mass Hunter software in ng/mL and then final data are calculated considering final extract volumes and the initial sample volumes extracted which are entered into the Element bench sheet.

11.2 Linear and Branched Isomers are addressed in Section 8.5 and are reported for the noted species as Total which is a sum of the linear and branched isomers for affected species.

11.3 All Data are uploaded into Element LIMS and all final concentration calculations and associated recoveries are detailed. All pdfs of Mass Hunter Quant reports are uploaded to the Element Raw Data drive for association with ICALs and all batch and analysis sequence runs. Data are set to Analyzed status once uploaded and initially reviewed, then locked.

11.4 The Data is then evaluated using the York Qualinator ^{TM} data review tool which evaluates all data CCVs, QC, ISTDS, Recoveries, etc. and automatically assigns outlier qualifiers for review and acceptance by the reviewer. The accepted data are then uploaded to Element and final reviewed in Laboratory Data Entry/Review module. Once reviewed, the status is set to Reviewed indicating the data are ready to be Reported by the Reporting Group.

12. HEALTH AND SAFETY

12.1 General safety considerations and requirements are detailed in the York Laboratory Safety and Health Standard Operating Procedure No. Safety011600.

Specific safety rules applying to the conduct of this analysis requiring the following:

- When handling standards and samples, latex gloves are required.
- Also, when handling neat materials, a fume hood and safety glasses are required.
- When handling samples, gloves and glasses are required.
- Highly odorous samples must be handled in a fume hood.
- Refer to SDSs for specific safety/health information.

12.2 The analysts must exercise normal care and be supervised and trained to work in an analytical chemistry laboratory. The analysts will be handling fragile glassware, needles, syringes, volatile and flammable chemicals, toxic chemicals, and corrosive chemicals.

- No smoking or open flames are allowed.
- No food or food products may be brought into the laboratory.

Solvents should not be left uncovered on the laboratory benches.
All solvent transfers should be done in the hoods.

Hood doors must be kept in a position which yields approx. 100 fpm face velocity.
Solvent evaporation must be done in the hood with exhaust elevated and in the rear.

Waste containers that had solvents must be vented to a hood until all solvents have evaporated.

Safety glasses are provided and must always be worn in the laboratory.
Gloves are provided and must be worn when working with chemicals.
Laboratory coats are provided and should be worn to protect the analysts' clothes.
Syringes and needles must be kept in their original cases when not in use.
Care must be exercised in using and handling syringes to avoid injury.
Report any sticking with a needle immediately to your supervisor.

12.3 Specific Safety Concerns

12.3.1 Preliminary toxicity studies indicate that PFAS could have significant toxic effects. In the interest of keeping exposure levels as low as reasonably achievable, PFAS must be handled in the laboratory as hazardous and toxic chemicals.

12.3.2 Exercise caution when using syringes with attached filter disc assemblies. Application of excessive force has, upon occasion, caused a filter disc to burst during the process.

12.3.3 Laboratory procedures such as repetitive use of pipets, repetitive transferring of extracts and manipulation of filled separatory funnels and other glassware represent a significant potential for repetitive motion or other ergonomic injuries. Laboratory associates performing these procedures are in the best position to realize when they are at risk for these types of injuries.

12.3.4 Eye protection, laboratory coat, and nitrile gloves must be worn while handling samples, standards, solvents, and reagents. Disposable gloves that have been contaminated will be removed and discarded; other gloves will be cleaned immediately.

12.3.5 Perfluorocarboxylic acids are acids and are not compatible

with strong bases.

12.3.6 Primary Materials Used- The following is a list of the materials used in this method, which have a serious or significant hazard rating. NOTE: This list does not include all materials used in the method. The table contains a summary of the primary hazards listed in the SDS for each of the materials listed in the table. A complete list of materials used in the method can be found in the reagents and materials section. Employees must review the information in the SDS for each material before using it for the first time or when there are major changes to the SDS.

Methanol	-Flammable Poison -Irritant	200 ppm (TWA)	A slight irritant to the mucous membranes. Toxic effects exerted upon nervous system, particularly the optic nerve. Symptoms of overexposure may include headache, drowsiness and dizziness. Methyl alcohol is a defatting agent and may cause skin to become dry and cracked. Skin absorption can occur; symptoms may parallel inhalation exposure. Irritant to the eyes.
Acetic Acid, Glacial	-Flammable liquid and vapor. -Irritation	10 ppm TWA; 25 mg/m3 TWA	**Eye:** Causes severe eye irritation. Contact with liquid or vapor causes severe burns and possible irreversible eye damage. **Skin:** Causes skin burns. May be harmful if absorbed through the skin. Contact with the skin may cause blackening and hyperkeratosis of the skin of the hands. **Ingestion:** May cause severe and permanent damage to the digestive tract. Causes severe pain, nausea, vomiting, diarrhea, and shock. May cause polyuria, oliguria (excretion of a diminished amount of urine in relation to the fluid intake) and anuria (complete suppression of urination). Rapidly absorbed from the gastrointestinal tract. **Inhalation:** Effects may be delayed. Causes chemical burns to the respiratory tract. Exposure may lead to bronchitis, pharyngitis, and dental erosion. May be absorbed through the lungs. **Chronic:** Chronic exposure to acetic acid may cause erosion of dental enamel, bronchitis, eye irritation, darkening of the skin, and chronic inflammation of the respiratory tract. Acetic acid can cause occupational asthma. One case of a delayed asthmatic response to glacial acetic acid has been reported in a person with bronchial asthma. Skin sensitization to acetic acid is rare, but has
Ammonium Hydroxide, conc. 28-30%	- Inhalation hazard - Skin Corrosion -Eye Damage and Irritation	OSHA PEL: 35 mg/m3 ; 50 ppm OSHA TWA: 18 mg/m3; 25 ppm	Ammonia is an irritant and corrosive to the skin, eyes, respiratory tract and mucous membranes. May cause severe chemical burns to the eyes, lungs and skin. Skin and respiratory related diseases could be aggravated by exposure. The extent of injury produced by exposure to ammonia depends on the duration of the exposure, the concentration of the liquid or vapor and the depth of inhalation. Exposure Routes: Inhalation (vapors), skin and/or eye contact (vapors, liquid), ingestion (liquid).

Formic Acid, conc.	-Flammable liquid and vapor -Harmful if swallowed -Causes severe skin burns and eye damage -Toxic if inhaled -May cause respiratory irritation	OSHA TWA: 5 ppm or 9 mg/m3 OSHA PEL: 10 ppm	Formic acid is an irritant and corrosive to the skin, eyes, respiratory tract and mucous membranes. May cause severe chemical burns to the eyes, lungs and skin. Skin and respiratory related diseases could be aggravated by exposure. The extent of injury produced by exposure to ammonia depends on the duration of the exposure, the concentration of the liquid or vapor and the depth of inhalation. Exposure Routes: Inhalation (vapors), skin and/or eye contact (vapors, liquid), ingestion (liquid).

13. WASTE MANAGEMENT/POLLUTION PREVENTION

Neat Materials

Waste management procedures require the prudent use of neat materials. The ordering of neat standards and materials must be done to minimize unused material which would result in storage or handling of excess material. Quantities ordered should be sufficient to provide for necessary standards with consideration to shelf life. When ordering a unique material for a standard, be sure to order the smallest practical quantity.

Solvents

The solvents used at York for this procedure include isopropanol and Methanol. These solvents are used for sample extraction or LC cleanup, all amounts are either consumed during concentration or placed in one-liter amber jars in the hood areas for evaporation. Any remaining solvent/water is transferred to a drum designated for solvent waste.

Acids and Bases

The acids and bases used for this procedure include Acetic Acid and Formic Acid. The bases used are Ammonium hydroxide, sodium hydroxide and potassium hydroxide. Store concentrated base and acids separately whether waste or neat material.

Samples

Unused or remaining water samples are returned to the sample control room for continued storage for proper disposal by the sample control group.

14. REFERENCES

1. EPA METHOD 1633 Draft 3 December, 2022- Analysis of Per- and Polyfluoroalkyl Substances (PFAS) in Aqueous, Solid, Biosolids, and Tissue Samples by LC-MS/MS; EPA 821-D-22-001

15. REVISION HISTORY

Revision 1.0	10/24/2022	First issue.
Revision 1.1	02/10/2023	Modified LLOPR in Section 7.4.6.1 to reflect 2x the MRL
Revision 1.2	06/23/2023	Added *Appendix 1: Target Compound Reporting Limits*. Updated Section 9.2 to add acceptable limits for ICAL RSE. Described the Promochrom extraction method in Sections 8.2, 8.3, and added *Appendix 2: Promochrom Method*. Redefined analytical batch as analytical sequence. Updated Reference to EPA 1633 Draft 3. Added reference to and preparation procedures for a second source standard in Section 7. Revised qualitative identification requirements for analytes in Section 8. Minor formatting edits.

Appendix 1 – Target Compound Reporting Limits

Target Compoud	Soil		Water	
	MDL/LOD	RL/LOQ	MDL/LOD	RL/LOQ
	µg/kg	µg/kg	ng/L	ng/L
Perfluorobutanesulfonic acid (PFBS)	0.111	0.177	0.47	1.77
Perfluorohexanoic acid (PFHxA)	0.053	0.200	0.35	2.00
Perfluoroheptanoic acid (PFHpA)	0.105	0.200	0.71	2.00
Perfluorohexanesulfonic acid (PFHxS)	0.179	0.183	0.68	1.83
Perfluorooctanoic acid (PFOA)	0.172	0.200	0.42	2.00
Perfluorooctanesulfonic acid (PFOS)	0.167	0.186	0.82	1.86
Perfluorononanoic acid (PFNA)	0.189	0.200	0.52	2.00
Perfluorodecanoic acid (PFDA)	0.191	0.200	0.75	2.00
Perfluoroundecanoic acid (PFUnA)	0.198	0.200	1.13	2.00
Perfluorododecanoic acid (PFDoA)	0.163	0.200	0.88	2.00
Perfluorotridecanoic acid (PFTrDA)	0.125	0.200	0.74	2.00
Perfluorotetradecanoic acid (PFTA)	0.103	0.200	0.69	2.00
N-MeFOSAA	0.148	0.200	0.79	2.00
N-EtFOSAA	0.194	0.200	1.03	2.00
Perfluoropentanoic acid (PFPeA)	0.109	0.400	0.23	4.00
Perfluoro-1-octanesulfonamide (FOSA)	0.146	0.200	0.88	2.00
Perfluoro-1-heptanesulfonic acid (PFHpS)	0.155	0.200	0.91	1.91
Perfluoro-1-decanesulfonic acid (PFDS)	0.191	0.193	1.32	1.93
1H,1H,2H,2H-Perfluorooctanesulfonic acid (6:2 FTS)	0.595	0.760	1.06	7.60
1H,1H,2H,2H-Perfluorodecanesulfonic acid (8:2 FTS)	0.755	0.768	2.05	7.68
Perfluoro-n-butanoic acid (PFBA)	0.109	0.800	0.33	8.00
Perfluoro(2-ethoxyethane)sulfonic acid (PFEESA)	0.139	0.356	0.50	3.56
Perfluoro-3,6-dioxaheptanoic acid (NFDHA)	0.193	0.400	2.14	4.00
Perfluoro-4-oxapentanoic acid (PFMPA)	0.062	0.400	0.25	4.00
Perfluoro-5-oxahexanoic acid (PFMBA)	0.096	0.400	0.37	4.00
Perfluoro-1-pentanesulfonate (PFPeS)	0.157	0.188	0.76	1.88
1H,1H,2H,2H-Perfluorohexanesulfonic acid (4:2 FTS)	0.595	0.750	1.79	7.50
HFPO-DA (Gen-X)	0.608	0.800	3.23	8.00
11CL-PF3OUdS	0.311	0.756	1.38	7.56
9CL-PF3ONS	0.246	0.748	0.70	7.48
ADONA	0.174	0.756	0.53	7.56
Perfluorododecanesulfonic acid (PFDoS)	0.169	0.194	0.93	1.94
Perfluoro-1-nonanesulfonic acid (PFNS)	0.124	0.192	0.86	1.92
3-Perfluoropropyl propanoic acid (FPrPA or 3:3FTCA)	0.634	1.000	2.03	5.00
3-Perfluoropentyl propanoic acid (FPePA or 5:3 FTCA)	2.098	5.000	7.33	25.00
3-Perfluoroheptyl propanoic acid (FHpPA or 7:3FTCA)	1.500	5.000	9.47	25.00
N-MeFOSE	0.611	2.000	3.99	20.00
N-MeFOSA	0.180	0.200	1.58	2.00
N-EtFOSE	0.697	2.000	3.99	20.00
N-EtFOSA	0.198	0.200	1.80	2.00

Appendix 2: Promochrom Method

Step	Action	Inlet 1	Inlet 2	Flow (mL/min)	Volume (mL)	Target
1	Elute	1% Basic Methanol	-	8	15	Waste
2	Elute	0.3M Formic Acid	-	8	5	Waste
3	Add Sample	Sample Inlet	-	10	60 or 510*	Waste
4	Rinse Sample	Water	Air (20%)	70	2.5	Sample Container
5	Add Sample	Sample Inlet	-	5	5	Waste
6	Rinse Sample	Water	Air (20%)	70	5	Sample Container
7	Add Sample	Sample Inlet	-	5	5	Waste
8	Rinse Sample	Water	Air (20%)	70	5	Sample Container
9	Add Sample	Sample Inlet	-	5	5	Waste
10	Rinse Sample	1:1 0.1M Formic Acid/Methanol	Air (20%)	70	1.3	Sample Container
11	Add Sample	Sample Inlet	-	5	3	Waste
12	Rinse Sample	1:1 0.1M Formic Acid/Methanol	Air (20%)	70	5	Sample Container
13	Add Sample	Sample Inlet	-	5	5	Waste
14	Air Purge	SPE Cartridge	-	5	5 Minutes	
15	Add Sample	Sample Inlet	-	5	5	Waste
16	Blow N2	Sample Inlet	-	5	1 Minute	
17	Rinse Sample	1% Basic Methanol	Air (20%)	70	1.3	Sample Container
18	Collect	Sample Inlet	-	5	3	Centrifuge Tube
19	Rinse Sample	1% Basic Methanol	Air (20%)	70	5	Sample Container
20	Collect	Sample Inlet	-	5	5	Centrifuge Tube
21	Collect	Sample Inlet	-	5	5	Centrifuge Tube

*60 mL is used for soil matrices and 510 mL is used for aqueous matrices.

Attachment 1 – Non-Extracted Internal Standards (NIS)

YORK
ANALYTICAL LABORATORIES, INC.

Analytical Standard Record

Standard ID: **Y22B197**

Description:	MPFAC-HIF-IS-EPA 1633 ISTD STOCK	Prepared:	02/16/2022
Standard Type:	Other	Expires:	09/07/2026
Solvent:	Methanol/Water (<1%)	Prepared By:	Robert Q. Bradley
Final Volume (mls):	1	Department:	PFAS
Vials:	1	Lot No.:	MPFACHIFIS0921
Vendor:	Wellington Laboratories		

Comments: Stock ISTD for EPA method 1633

Analyte	CAS Number	Concentration	Units
M3PFBA		1	ug/mL
MPFDA		0.25	ug/mL
MPFHxA		0.5	ug/mL
MPFHxS		0.474	ug/mL
MPFNA		0.25	ug/mL
MPFOA		0.5	ug/mL
MPFOS		0.479	ug/mL

WELLINGTON LABORATORIES

CERTIFICATE OF ANALYSIS
DOCUMENTATION

MPFAC-HIF-IS

Mass-Labelled Perfluoroalkyl Substance Injection Standard Solution/Mixture

PRODUCT CODE:	MPFAC-HIF-IS
LOT NUMBER:	MPFACHIFIS0921
SOLVENT(S):	Methanol/Water (<1%)
DATE PREPARED: (mm/dd/yyyy)	09/07/2021
LAST TESTED: (mm/dd/yyyy)	09/07/2021
EXPIRY DATE: (mm/dd/yyyy)	09/07/2026
RECOMMENDED STORAGE:	Store ampoule in a cool, dark place

DESCRIPTION:

MPFAC-HIF-IS is a solution/mixture of five mass-labelled (^{13}C) perfluoroalkylcarboxylic acids (C_4, C_8, C_9-C_{10}) and two mass-labelled (^{18}O and ^{13}C) perfluoroalkanesulfonates (C_6 and C_8). The components and their concentrations are given in Table A.

The individual mass-labelled perfluoroalkylcarboxylic acids and mass-labelled perfluoroalkanesulfonates all have chemical purities of >98% and isotopic purities of ≥99% per ^{13}C or >94% per ^{18}O.

DOCUMENTATION/ DATA ATTACHED:

Table A: Components and Concentrations of the Solution/Mixture
Figure 1: LC/MS Data (SIR)
Figure 2: LC/MS/MS Data (Selected MRM Transitions)

ADDITIONAL INFORMATION:

- See page 2 for further details.
- Contains 4 mole eq. of NaOH to prevent conversion of the carboxylic acids to their respective methyl esters.

FOR LABORATORY USE ONLY: NOT FOR HUMAN OR DRUG USE

Wellington Laboratories Inc., 345 Southgate Dr. Guelph ON N1G 3M5 CANADA
519-822-2436 • Fax: 519-822-2849 • info@well-labs.com

Form#:13, Issued 2004-11-10
Revision#:9, Revised 2020-12-23

INTENDED USE:

The products prepared by Wellington Laboratories Inc. are for laboratory use only. This certified reference material (CRM) was designed to be used as a standard for the identification and/or quantification of the specific chemical compounds it contains.

HANDLING:

This product should only be used by qualified personnel familiar with its potential hazards and trained in the handling of hazardous chemicals. Due care should be exercised to prevent unnecessary human contact or ingestion. All procedures should be carried out in a well-functioning fume hood and suitable gloves, eye protection, and clothing should be worn at all times. Waste should be disposed of according to national and regional regulations. Safety Data Sheets (SDSs) are available upon request.

SYNTHESIS / CHARACTERIZATION:

Our products are synthesized using single-product unambiguous routes whenever possible. They are then characterized, and their structures and purities confirmed, using a combination of the most relevant techniques, such as NMR, GC/MS, LC/MS/MS, SFC/UV/MS/MS, x-ray crystallography, and melting point. Isotopic purities of mass-labelled compounds are also confirmed using HRGC/HRMS and/or LC/MS/MS.

HOMOGENEITY:

Prior to solution preparation, crystalline material is tested for homogeneity using a variety of techniques (as stated above) and its solubility in a given diluent is taken into consideration. Duplicate solutions of a new product are prepared from the same crystalline lot and, after the addition of an appropriate internal standard, they are compared by GC/MS, LC/MS/MS, and/or SFC/UV/MS/MS. The relative response factors of the analyte of interest in each solution are required to be <5% RSD. New solution lots of existing products, as well as mixtures and calibration solutions, are compared to older lots in a similar manner. This further confirms the homogeneity of the crystalline material as well as the stability and homogeneity of the solutions in the storage containers. In order to maintain the integrity of the assigned value(s), and associated uncertainty, the dilution or injection of a subsample of this product should be performed using calibrated measuring equipment.

UNCERTAINTY:

The maximum combined relative standard uncertainty of our reference standard solutions is calculated using the following equation:

The combined relative standard uncertainty, $u_c(y)$, of a value y and the uncertainty of the independent parameters $x_1, x_2, \ldots x_n$ on which it depends is:

$$u_c(y(x_1, x_2, \ldots x_n)) = \sqrt{\sum_{i=1}^{n} u(y, x_i)^2}$$

where x is expressed as a relative standard uncertainty of the individual parameter.

The individual uncertainties taken into account include those associated with weights (calibration of the balance) and volumes (calibration of the volumetric glassware). An expanded maximum combined percent relative uncertainty of ±5% (calculated with a coverage factor of 2 and a level of confidence of 95%) is stated on the Certificate of Analysis for all of our products.

TRACEABILITY:

All reference standard solutions are traceable to specific crystalline lots. The microbalances used for solution preparation are regularly calibrated by an external ISO/IEC 17025 accredited laboratory. In addition, their calibration is verified prior to each weighing using calibrated external weights traceable to an ISO/IEC 17025 accredited laboratory. All volumetric glassware used is calibrated, of Class A tolerance, and traceable to an ISO/IEC 17025 accredited laboratory. For certain products, traceability to international interlaboratory studies has also been established.

EXPIRY DATE / PERIOD OF VALIDITY:

Ongoing stability studies of this product have demonstrated stability in its composition and concentration, until the specified expiry date, in the unopened ampoule. Monitoring for any degradation or change in concentration of the listed analyte(s) is performed on a routine basis.

LIMITED WARRANTY:

At the time of shipment, all products are warranted to be free of defects in material and workmanship and to conform to the stated technical and purity specifications.

QUALITY MANAGEMENT:

This product was produced using a Quality Management System registered to the latest versions of ISO 9001 by SAI Global, ISO/IEC 17025 by the Canadian Association for Laboratory Accreditation Inc. (CALA; A1226), and ISO 17034 by ANSI National Accreditation Board (ANAB; AR-1523).

CALA Testing Accreditation No. A1226

ANAB ANSI National Accreditation Board ACCREDITED ISO 17034 REFERENCE MATERIAL PRODUCER

For additional information or assistance concerning this or any other products from Wellington Laboratories Inc., please visit our website at www.well-labs.com or contact us directly at info@well-labs.com

Table A: **MPFAC-HIF-IS; Components and Concentrations (ng/mL, ± 5% in methanol/water (<1%))**

Compound	Acronym	Concentration (ng/mL)		Peak Assignment in Figure 1
Perfluoro-n-(2,3,4-$^{13}C_3$)butanoic acid	M3PFBA	1000		1
Perfluoro-n-(1,2-$^{13}C_2$)hexanoic acid	MPFHxA	500		2
Perfluoro-n-(1,2,3,4-$^{13}C_4$)octanoic acid	MPFOA	500		4
Perfluoro-n-(1,2,3,4,5-$^{13}C_5$)nonanoic acid	MPFNA	250		5
Perfluoro-n-(1,2-$^{13}C_2$)decanoic acid	MPFDA	250		7
Compound	**Acronym**	**Concentration* (ng/mL)**		**Peak Assignment in Figure 1**
		as the salt	**as the acid**	
Sodium perfluoro-1-hexane($^{18}O_2$)sulfonate	MPFHxS	500	474	3
Sodium perfluoro-1-(1,2,3,4-$^{13}C_4$)octanesulfonate	MPFOS	500	479	6

* Concentrations have been rounded to three significant figures.

Certified By: _____ **Date:** 10/13/2021 (mm/dd/yyyy)

B.G. Chittim, General Manager

Figure 1: **MPFAC-HIF-IS; LC/MS Data (SIR)**



Conditions for Figure 1:

Waters Acquity Ultra Performance LC
Waters Xevo TQ-S micro MS

Chromatographic Conditions:

Column: Acquity UPLC BEH Shield RP_{18}
1.7 µm, 2.1 x 100 mm

Mobile phase: Gradient
Start: 50% H_2O / 50% (80:20 MeOH:ACN)
(both with 10 mM NH_4OAc buffer)
Ramp to 90% organic over 9 min and hold for
2 min before returning to initial conditions in 1 min.
Time: 15 min

Flow: 300 µL/min

MS Parameters:

Experiment: SIR

Source: Electrospray (negative)
Capillary Voltage (kV) = 2.00
Cone Voltage (V) = variable (2-6)
Desolvation Temperature (°C) = 350
Desolvation Gas Flow (L/hr) = 1000

Form#:13, Issued 2004-11-10
Revision#:9, Revised 2020-12-23

MPFACHIFIS0921 (4 of 5)
rev1

Figure 2: **MPFAC-HIF-IS; LC/MS/MS Data (Selected MRM Transitions)**



Conditions for Figure 2:

Injection: On-column (MPFAC-HIF-IS)

Mobile phase: Same as Figure 1

Flow: 300 µL/min

MS Parameters:

Collision Gas (mbar) = 3.18e-3
Collision Energy (eV) = 4-64 (variable)

Form#:13, Issued 2004-11-10
Revision#:9, Revised 2020-12-23

MPFACHIFIS0921 (5 of 5)
rev1

Attachment 2 – Extracted Internal Standards (EIS)

YORK
ANALYTICAL LABORATORIES, INC.

Analytical Standard Record

Standard ID: **Y22B198**

Description:	MPFAC-HIF-ES-EPA 1633 STOCK EIS mix	Prepared:	02/17/2022
Standard Type:	Other	Expires:	08/06/2024
Solvent:	MeOH/IPA/1% H2O	Prepared By:	Robert Q. Bradley
Final Volume (mls):	1	Department:	PFAS
Vials:	1	Lot No.:	MPFACHIFES0821
Vendor:	Wellington Laboratories		

Comments:

Analyte	CAS Number	Concentration	Units
d3-N-MeFOSAA		1	ug/mL
d5-N-EtFOSAA		1	ug/mL
d7-N-MeFOSE		5	ug/mL
d9-N-EtFOSE		5	ug/mL
d-N-EtFOSA		0.5	ug/mL
d-N-MeFOSA		0.5	ug/mL
M2-4:2FTS		0.938	ug/mL
M2-6:2FTS		0.951	ug/mL
M2-8:2FTS		0.96	ug/mL
M2PFTeDA		0.25	ug/mL
M3HFPO-DA		2	ug/mL
M3PFBS		0.466	ug/mL
M3PFHxS		0.474	ug/mL
M4PFHpA		0.5	ug/mL
M5PFHxA		0.5	ug/mL
M5PFPeA		1	ug/mL
M6PFDA		0.25	ug/mL
M7PFUdA		0.25	ug/mL
M8FOSA		0.5	ug/mL
M8PFOA		0.5	ug/mL
M8PFOS		0.479	ug/mL
M9PFNA		0.25	ug/mL
MPFBA		2	ug/mL
MPFDoA		0.25	ug/mL

WELLINGTON LABORATORIES

CERTIFICATE OF ANALYSIS
DOCUMENTATION

MPFAC-HIF-ES

Mass-Labelled Per- and Poly-fluoroalkyl Substance Extraction Standard Solution/Mixture

PRODUCT CODE:	MPFAC-HIF-ES
LOT NUMBER:	MPFACHIFES0821
SOLVENT(S):	Methanol/Isopropanol (1%)/Water (<1%)
DATE PREPARED: (mm/dd/yyyy)	08/05/2021
LAST TESTED: (mm/dd/yyyy)	08/16/2021
EXPIRY DATE: (mm/dd/yyyy)	08/16/2024
RECOMMENDED STORAGE:	Refrigerate ampoule

DESCRIPTION:

MPFAC-HIF-ES is a solution/mixture of ten mass-labelled (^{13}C) perfluoroalkylcarboxylic acids (C_4-C_{12}, C_{14}), three mass-labelled (^{13}C) perfluoroalkanesulfonates (C_4, C_8, and C_8), three mass-labelled (one ^{13}C and two ^{2}H) perfluoro-1-octanesulfonamides, three mass-labelled (^{13}C) fluorotelomer sulfonates (4:2, 6:2, and 8:2), two mass-labelled (^{2}H) perfluorooctanesulfonamidoacetic acids, two mass-labelled (^{2}H) perfluorooctanesulfonamidoethanols, and mass-labelled (^{13}C) hexafluoropropylene oxide dimer acid. The components and their concentrations are given in Table A.

The individual mass-labelled perfluoroalkylcarboxylic acids, mass-labelled perfluoroalkanesulfonates, mass-labelled fluorotelomer sulfonates, perfluoro-1-($^{13}C_8$)octanesulfonamide, and mass-labelled hexafluoropropylene oxide dimer acid all have chemical purities of >98% and isotopic purities of ≥99%. The individual mass-labelled perfluorooctanesulfonamidoacetic acids, mass-labelled perfluorooctanesulfonamidoethanols, and two mass-labelled (^{2}H) perfluoro-1-octanesulfonamides all have chemical purities of >98% and isotopic purities of ≥98%.

DOCUMENTATION/ DATA ATTACHED:

Table A: Components and Concentrations of the Solution/Mixture
Figure 1: LC/MS Data (SIR)
Figure 2: LC/MS/MS Data (Selected MRM Transitions)

ADDITIONAL INFORMATION:

- See page 2 for further details.
- Contains 4 mole eq. of NaOH to prevent conversion of the carboxylic acids to their respective methyl esters.

FOR LABORATORY USE ONLY: NOT FOR HUMAN OR DRUG USE

Wellington Laboratories Inc., 345 Southgate Dr. Guelph ON N1G 3M5 CANADA
519-822-2436 • Fax: 519-822-2849 • info@well-labs.com

INTENDED USE:

The products prepared by Wellington Laboratories Inc. are for laboratory use only. This certified reference material (CRM) was designed to be used as a standard for the identification and/or quantification of the specific chemical compounds it contains.

HANDLING:

This product should only be used by qualified personnel familiar with its potential hazards and trained in the handling of hazardous chemicals. Due care should be exercised to prevent unnecessary human contact or ingestion. All procedures should be carried out in a well-functioning fume hood and suitable gloves, eye protection, and clothing should be worn at all times. Waste should be disposed of according to national and regional regulations. Safety Data Sheets (SDSs) are available upon request.

SYNTHESIS / CHARACTERIZATION:

Our products are synthesized using single-product unambiguous routes whenever possible. They are then characterized, and their structures and purities confirmed, using a combination of the most relevant techniques, such as NMR, GC/MS, LC/MS/MS, SFC/UV/MS/MS, x-ray crystallography, and melting point. Isotopic purities of mass-labelled compounds are also confirmed using HRGC/HRMS and/or LC/MS/MS.

HOMOGENEITY:

Prior to solution preparation, crystalline material is tested for homogeneity using a variety of techniques (as stated above) and its solubility in a given diluent is taken into consideration. Duplicate solutions of a new product are prepared from the same crystalline lot and, after the addition of an appropriate internal standard, they are compared by GC/MS, LC/MS/MS, and/or SFC/UV/MS/MS. The relative response factors of the analyte of interest in each solution are required to be <5% RSD. New solution lots of existing products, as well as mixtures and calibration solutions, are compared to older lots in a similar manner. This further confirms the homogeneity of the crystalline material as well as the stability and homogeneity of the solutions in the storage containers. In order to maintain the integrity of the assigned value(s), and associated uncertainty, the dilution or injection of a subsample of this product should be performed using calibrated measuring equipment.

UNCERTAINTY:

The maximum combined relative standard uncertainty of our reference standard solutions is calculated using the following equation:

The combined relative standard uncertainty, $u_c(y)$, of a value y and the uncertainty of the independent parameters $x_1, x_2, \ldots x_n$ on which it depends is:

$$u_c(y(x_1, x_2, \ldots x_n)) = \sqrt{\sum_{i=1}^{n} u(y, x_i)^2}$$

where x is expressed as a relative standard uncertainty of the individual parameter.

The individual uncertainties taken into account include those associated with weights (calibration of the balance) and volumes (calibration of the volumetric glassware). An expanded maximum combined percent relative uncertainty of ±5% (calculated with a coverage factor of 2 and a level of confidence of 95%) is stated on the Certificate of Analysis for all of our products.

TRACEABILITY:

All reference standard solutions are traceable to specific crystalline lots. The microbalances used for solution preparation are regularly calibrated by an external ISO/IEC 17025 accredited laboratory. In addition, their calibration is verified prior to each weighing using calibrated external weights traceable to an ISO/IEC 17025 accredited laboratory. All volumetric glassware used is calibrated, of Class A tolerance, and traceable to an ISO/IEC 17025 accredited laboratory. For certain products, traceability to international interlaboratory studies has also been established.

EXPIRY DATE / PERIOD OF VALIDITY:

Ongoing stability studies of this product have demonstrated stability in its composition and concentration, until the specified expiry date, in the unopened ampoule. Monitoring for any degradation or change in concentration of the listed analyte(s) is performed on a routine basis.

LIMITED WARRANTY:

At the time of shipment, all products are warranted to be free of defects in material and workmanship and to conform to the stated technical and purity specifications.

QUALITY MANAGEMENT:

This product was produced using a Quality Management System registered to the latest versions of ISO 9001 by SAI Global, ISO/IEC 17025 by the Canadian Association for Laboratory Accreditation Inc. (CALA; A1226), and ISO 17034 by ANSI National Accreditation Board (ANAB; AR-1523).

CALA Testing Accreditation No. A1226

ANAB ANSI National Accreditation Board ACCREDITED ISO 17034 REFERENCE MATERIAL PRODUCER

For additional information or assistance concerning this or any other products from Wellington Laboratories Inc., please visit our website at www.well-labs.com or contact us directly at info@well-labs.com

Form#:13, Issued 2004-11-10
Revision#:9, Revised 2020-12-23

MPFACHIFES0821 (2 of 7)
rev1

Figure 2: **MPFAC-HIF-ES; LC/MS/MS Data (Selected MRM Transitions)**



Conditions for Figure 2:

Injection: On-column (MPFAC-HIF-ES)

Mobile phase: Same as Figure 1

Flow: 300 µL/min

MS Parameters:

Collision Gas (mbar) = 3.41e-3
Collision Energy (eV) = 4-64 (variable)

Form#:13, Issued 2004-11-10
Revision#:9, Revised 2020-12-23

MPFACHIFES0821 (7 of 7)
rev1

Table A: **MPFAC-HIF-ES; Components and Concentrations (ng/mL, ± 5% in Methanol/Isopropanol (1%)/Water (<1%))**

Compound	Acronym	Concentration (ng/mL)	Peak Assignment in Figure 1
Perfluoro-n-($^{13}C_4$)butanoic acid	MPFBA	2000	1
Perfluoro-n-($^{13}C_5$)pentanoic acid	M5PFPeA	1000	2
Perfluoro-n-(1,2,3,4,6-$^{13}C_5$)hexanoic acid	M5PFHxA	500	5
Perfluoro-n-(1,2,3,4-$^{13}C_4$)heptanoic acid	M4PFHpA	500	7
Perfluoro-n-($^{13}C_8$)octanoic acid	M8PFOA	500	10
Perfluoro-n-($^{13}C_9$)nonanoic acid	M9PFNA	250	11
Perfluoro-n-(1,2,3,4,5,6-$^{13}C_6$)decanoic acid	M6PFDA	250	14
Perfluoro-n-(1,2,3,4,5,6,7-$^{13}C_7$)undecanoic acid	M7PFUdA	250	17
Perfluoro-n-(1,2-$^{13}C_2$)dodecanoic acid	MPFDoA	250	19
Perfluoro-n-(1,2-$^{13}C_2$)tetradecanoic acid	M2PFTeDA	250	22
Perfluoro-1-($^{13}C_8$)octanesulfonamide	M8FOSA	500	18
N-methyl-d_3-perfluoro-1-octanesulfonamide	d-N-MeFOSA	500	21
N-ethyl-d_5-perfluoro-1-octanesulfonamide	d-N-EtFOSA	500	24
N-methyl-d_3-perfluoro-1-octanesulfonamidoacetic acid	d3-N-MeFOSAA	1000	15
N-ethyl-d_5-perfluoro-1-octanesulfonamidoacetic acid	d5-N-EtFOSAA	1000	16
2-(N-methyl-d_3-perfluoro-1-octanesulfonamido)ethan-d_4-ol	d7-N-MeFOSE	5000	20
2-(N-ethyl-d_5-perfluoro-1-octanesulfonamido)ethan-d_4-ol	d9-N-EtFOSE	5000	23
2,3,3,3-Tetrafluoro-2-(1,1,2,2,3,3,3-heptafluoropropoxy)($^{13}C_3$)propanoic acid	M3HFPO-DA	2000	6

Compound	Acronym	Concentration* (ng/mL)		Peak Assignment in Figure 1
		as the salt	as the acid	
Sodium perfluoro-1-(2,3,4-$^{13}C_3$)butanesulfonate	M3PFBS	500	466	3
Sodium perfluoro-1-(1,2,3-$^{13}C_3$)hexanesulfonate	M3PFHxS	500	474	8
Sodium perfluoro-1-($^{13}C_8$)octanesulfonate	M8PFOS	500	479	12
Sodium 1H,1H,2H,2H-perfluoro-(1,2-$^{13}C_2$)hexanesulfonate	M2-4:2FTS	1000	938	4
Sodium 1H,1H,2H,2H-perfluoro-(1,2-$^{13}C_2$)octanesulfonate	M2-6:2FTS	1000	951	9
Sodium 1H,1H,2H,2H-perfluoro-(1,2-$^{13}C_2$)decanesulfonate	M2-8:2FTS	1000	960	13

* Concentrations have been rounded to three significant figures.

Certified By: _____ **Date:** 10/13/2021 (mm/dd/yyyy)
B.G. Chittim, General Manager

Form#:13, Issued 2004-11-10
Revision#:9, Revised 2020-12-23

MPFACHIFES0821 (3 of 7)
rev1

Figure 1: **MPFAC-HIF-ES; LC/MS Data (SIR)**



Conditions for Figure 1:

Waters Acquity Ultra Performance LC
Waters Xevo TQ-S micro MS

Chromatographic Conditions:

Column: Acquity UPLC BEH Shield RP_{18}
1.7 µm, 2.1 x 100 mm

Mobile phase: Gradient
Start: 50% H_2O / 50% (80:20 MeOH:ACN)
(both with 10 mM NH_4OAc buffer)
Ramp to 90% organic over 9 min and hold for
2 min before returning to initial conditions in 1 min.
Time: 15 min

Flow: 300 µL/min

MS Parameters:

Experiment: SIR

Source: Electrospray (negative)
Capillary Voltage (kV) = 2.00
Cone Voltage (V) = variable (2-44)
Desolvation Temperature (°C) = 350
Desolvation Gas Flow (L/hr) = 1000

Form#:13, Issued 2004-11-10
Revision#:9, Revised 2020-12-23

MPFACHIFES0821 (4 of 7)
rev1

Figure 2: **MPFAC-HIF-ES; LC/MS/MS Data (Selected MRM Transitions)**



Form#:13, Issued 2004-11-10
Revision#:9, Revised 2020-12-23

MPFACHIFES0821 (5 of 7)
rev1

Figure 2: **MPFAC-HIF-ES; LC/MS/MS Data (Selected MRM Transitions)**



Form#:13, Issued 2004-11-10
Revision#:9, Revised 2020-12-23

MPFACHIFES0821 (6 of 7)
rev1

Attachment 3 – Target Analyte

Figure 2: PFAC-MXF; LC/MS/MS Data (Selected MRM Transitions)



Conditions for Figure 2:

Injection: On-column (PFAC-MXF)

Mobile phase: Same as Figure 1

Flow: 300 µL/min

MS Parameters:
Collision Gas (mbar) = 3.43e-3
Collision Energy (eV) = 6-60 (variable)

Mixtures

INTENDED USE:

The products prepared by Wellington Laboratories Inc. are for laboratory use only. This certified reference material (CRM) was designed to be used as a standard for the identification and/or quantification of the specific chemical compounds it contains.

HANDLING:

This product should only be used by qualified personnel familiar with its potential hazards and trained in the handling of hazardous chemicals. Due care should be exercised to prevent unnecessary human contact or ingestion. All procedures should be carried out in a well-functioning fume hood and suitable gloves, eye protection, and clothing should be worn at all times. Waste should be disposed of according to national and regional regulations. Safety Data Sheets (SDSs) are available upon request.

SYNTHESIS / CHARACTERIZATION:

Our products are synthesized using single-product unambiguous routes whenever possible. They are then characterized, and their structures and purities confirmed, using a combination of the most relevant techniques, such as NMR, GC/MS, LC/MS/MS, SFC/UV/MS/MS, x-ray crystallography, and melting point. Isotopic purities of mass-labelled compounds are also confirmed using HRGC/HRMS and/or LC/MS/MS.

HOMOGENEITY:

Prior to solution preparation, crystalline material is tested for homogeneity using a variety of techniques (as stated above) and its solubility in a given diluent is taken into consideration. Duplicate solutions of a new product are prepared from the same crystalline lot and, after the addition of an appropriate internal standard, they are compared by GC/MS, LC/MS/MS, and/or SFC/UV/MS/MS. The relative response factors of the analyte of interest in each solution are required to be <5% RSD. New solution lots of existing products, as well as mixtures and calibration solutions, are compared to older lots in a similar manner. This further confirms the homogeneity of the crystalline material as well as the stability and homogeneity of the solutions in the storage containers. In order to maintain the integrity of the assigned value(s), and associated uncertainty, the dilution or injection of a subsample of this product should be performed using calibrated measuring equipment.

UNCERTAINTY:

The maximum combined relative standard uncertainty of our reference standard solutions is calculated using the following equation:

The combined relative standard uncertainty, $u_c(y)$, of a value y and the uncertainty of the independent parameters $x_1, x_2, \ldots x_n$ on which it depends is:

$$u_c(y(x_1, x_2, \ldots x_n)) = \sqrt{\sum_{i=1}^{n} u(y, x_i)^2}$$

where x is expressed as a relative standard uncertainty of the individual parameter.

The individual uncertainties taken into account include those associated with weights (calibration of the balance) and volumes (calibration of the volumetric glassware). An expanded maximum combined percent relative uncertainty of ±5% (calculated with a coverage factor of 2 and a level of confidence of 95%) is stated on the Certificate of Analysis for all of our products.

TRACEABILITY:

All reference standard solutions are traceable to specific crystalline lots. The microbalances used for solution preparation are regularly calibrated by an external ISO/IEC 17025 accredited laboratory. In addition, their calibration is verified prior to each weighing using calibrated external weights traceable to an ISO/IEC 17025 accredited laboratory. All volumetric glassware used is calibrated, of Class A tolerance, and traceable to an ISO/IEC 17025 accredited laboratory. For certain products, traceability to international interlaboratory studies has also been established.

EXPIRY DATE / PERIOD OF VALIDITY:

Ongoing stability studies of this product have demonstrated stability in its composition and concentration, until the specified expiry date, in the unopened ampoule. Monitoring for any degradation or change in concentration of the listed analyte(s) is performed on a routine basis.

LIMITED WARRANTY:

At the time of shipment, all products are warranted to be free of defects in material and workmanship and to conform to the stated technical and purity specifications.

QUALITY MANAGEMENT:

This product was produced using a Quality Management System registered to the latest versions of ISO 9001 by SAI Global, ISO/IEC 17025 by the Canadian Association for Laboratory Accreditation Inc. (CALA; A1226), and ISO 17034 by ANSI National Accreditation Board (ANAB; AR-1523).

CALA Testing Accreditation No. A1226

ANAB ANSI National Accreditation Board ACCREDITED ISO 17034 REFERENCE MATERIAL PRODUCER

For additional information or assistance concerning this or any other products from Wellington Laboratories Inc., please visit our website at www.well-labs.com or contact us directly at info@well-labs.com

Form#:13, Issued 2004-11-10
Revision#:9, Revised 2020-12-23

PFACMXF0122 (2 of 5)
rev0

Table A: **PFAC-MXF; Components and Concentrations (ng/mL; ± 5% in Methanol/Water (<1%))**

Compound	Acronym	Concentration* (ng/ml)	Peak Assignment in Figure 1
2,3,3,3-Tetrafluoro-2-(1,1,2,2,3,3,3-heptafluoropropoxy)-propanoic acid	HFPO-DA	2000	A

Compound	Acronym	Concentration* (ng/mL)		Peak Assignment in Figure 1
		as the salt	as the acid	
Sodium dodecafluoro-3H-4,8-dioxanonanoate	NaDONA	2000	1890	B
Potassium 9-chlorohexadecafluoro-3-oxanonane-1-sulfonate	9Cl-PF3ONS	2000	1870	C
Potassium 11-chloroeicosafluoro-3-oxaundecane-1-sulfonate	11Cl-PF3OUdS	2000	1890	D

* Concentrations have been rounded to three significant figures.

Certified By: _____ **Date:** 01/12/2022 (mm/dd/yyyy)
B.G. Chittim, General Manager

Figure 1: **PFAC-MXF; LC/MS Data (SIR)**



Conditions for Figure 1:

Waters Acquity Ultra Performance LC
Waters Xevo TQ-S micro MS

Chromatographic Conditions:

Column: Acquity UPLC BEH Shield RP_{18}
1.7 µm, 2.1 x 100 mm

Mobile phase: Gradient
Start: 45% H_2O / 55% (80:20 MeOH:ACN)
(both with 10 mM NH_4OAc buffer)
Ramp to 90% organic over 8 min and hold for 2 min
before returning to initial conditions in 0.75 min.
Time: 12 min

Flow: 300 µL/min

MS Parameters:

Experiment: SIR

Source: Electrospray (negative)
Capillary Voltage (kV) = 2.00
Cone Voltage (V) = variable (15-74)
Desolvation Temperature (°C) = 325
Desolvation Gas Flow (L/hr) = 1000

Form#:13, Issued 2004-11-10
Revision#:9, Revised 2020-12-23

PFACMXF0122 (4 of 5)
rev0

YORK
ANALYTICAL LABORATORIES, INC.

Analytical Standard Record

Standard ID: **Y22B199**

Description:	PFAC-MXF-Native Repl.STOCK EPA 1633 PFAS	Prepared:	02/17/2022
Standard Type:	Other	**Expires:**	**01/11/2025**
Solvent:	MeOH/H20	Prepared By:	Robert Q. Bradley
Final Volume (mls):	1	Department:	PFAS
Vials:	1	Lot No.:	PFACMXF0122
Vendor:	Wellington Laboratories		

Comments:

Analyte	CAS Number	Concentration	Units
11CL-PF3OUdS	763051-92-9	1.89	ug/mL
9CL-PF3ONS	756426-58-1	1.87	ug/mL
ADONA	919005-14-4	1.89	ug/mL
HFPO-DA (Gen-X)	13252-13-6	2	ug/mL

Reviewed By Date

Page 1 of 1

WELLINGTON LABORATORIES

CERTIFICATE OF ANALYSIS
DOCUMENTATION

PFAC-MXF

Native Replacement PFAS Solution/Mixture

PRODUCT CODE:	PFAC-MXF
LOT NUMBER:	PFACMXF0122
SOLVENT(S):	Methanol / Water (<1%)
DATE PREPARED: (mm/dd/yyyy)	01/10/2022
LAST TESTED: (mm/dd/yyyy)	01/11/2022
EXPIRY DATE: (mm/dd/yyyy)	01/11/2025
RECOMMENDED STORAGE:	Refrigerate ampoule

DESCRIPTION:

PFAC-MXF is a solution/mixture of sodium dodecafluoro-3H-4,8-dioxanonanoate (NaDONA), the major and minor components of F-53B (9Cl-PF3ONS and 11Cl-PF3OUdS), and GenX (HFPO-DA). The components and their concentrations are given in Table A.

The individual native components of this mixture all have chemical purities of >98%.

DOCUMENTATION/ DATA ATTACHED:

Table A: Components and Concentrations of the Solution/Mixture
Figure 1: LC/MS Data (SIR)
Figure 2: LC/MS/MS Data (Selected MRM Transitions)

ADDITIONAL INFORMATION:

- See page 2 for further details.
- Contains 4 mole eq. of NaOH to prevent conversion of the carboxylic acid to the methyl ester.

FOR LABORATORY USE ONLY: NOT FOR HUMAN OR DRUG USE

Wellington Laboratories Inc., 345 Southgate Dr. Guelph ON N1G 3M5 CANADA
519-822-2436 • Fax: 519-822-2849 • info@well-labs.com

Table A: **PFAC-MXI; Components and Concentrations (µg/mL; ± 5% in methanol)**

Compound	Acronym	Concentration (µg/mL)	Peak Assignment in Figure 1
N-methylperfluoro-1-octanesulfonamide	N-MeFOSA	1.00	B
N-ethylperfluoro-1-octanesulfonamide	N-EtFOSA	1.00	D
2-(N-methylperfluoro-1-octanesulfonamido)-ethanol	N-MeFOSE	10.0	A
2-(N-ethylperfluoro-1-octanesulfonamido)-ethanol	N-EtFOSE	10.0	C

Certified By: _____ **Date:** 09/23/2021
(mm/dd/yyyy)
B.G. Chittim, General Manager

Form#:13, Issued 2004-11-10
Revision#:9, Revised 2020-12-23

PFACMXI0921 (3 of 5)
rev0

Figure 1: **PFAC-MXI; LC/MS Data (SIR)**



Conditions for Figure 1:

Waters Acquity Ultra Performance LC
Waters Xevo TQ-S micro MS

Chromatographic Conditions:

Column: Acquity UPLC BEH Shield RP_{18}
1.7 µm, 2.1 x 100 mm

Mobile phase: Gradient
Start: 50% H_2O / 50% (80:20 MeOH:ACN)
(both with 10 mM NH_4OAc buffer)
Ramp to 90% organic over 9 min and hold for
2 min before returning to initial conditions in 1 min.
Time: 15 min

Flow: 300 µL/min

MS Parameters:

Experiment: SIR

Source: Electrospray (negative)
Capillary Voltage (kV) = 2.50
Cone Voltage (V) = variable (2-74)
Desolvation Temperature (°C) = 350
Desolvation Gas Flow (L/hr) = 1000

Form#:13, Issued 2004-11-10
Revision#:9, Revised 2020-12-23

PFACMXI0921 (4 of 5)
rev0

Figure 2: **PFAC-MXI; LC/MS/MS Data (Selected MRM Transitions)**



Conditions for Figure 2:

Injection: On-column (PFAC-MXI)

Mobile phase: Same as Figure 1

Flow: 300 µL/min

MS Parameters:
Collision Gas (mbar) = 3.31e-3
Collision Energy (eV) = 6-60 (variable)

Form#:13, Issued 2004-11-10
Revision#:9, Revised 2020-12-23

PFACMXI0921 (5 of 5)
rev0

YORK
ANALYTICAL LABORATORIES, INC.

Analytical Standard Record

Standard ID: **Y22B204**

Description:	PFAC-MXI-EPA 1633 Stock	Prepared:	02/17/2022
Standard Type:	Other	**Expires:**	**02/17/2023**
Solvent:	Methanol	Prepared By:	Robert Q. Bradley
Final Volume (mls):	1	Department:	PFAS
Vials:	1	Lot No.:	PFACMXI0921
Vendor:	Wellington Laboratories		

Comments:

Analyte	CAS Number	Concentration	Units
N-EtFOSA	4151-50-2	1	ug/mL
N-EtFOSE	1691-99-2	10	ug/mL
N-MeFOSA	31506-32-8	1	ug/mL
N-MeFOSE	24448-09-7	10	ug/mL

Reviewed By Date

Page 1 of 1

WELLINGTON LABORATORIES

CERTIFICATE OF ANALYSIS
DOCUMENTATION

PFAC-MXI

Native Perfluorooctanesulfonamide and Perfluorooctanesulfonamidoethanol Solution/Mixture

PRODUCT CODE:	PFAC-MXI
LOT NUMBER:	PFACMXI0921
SOLVENT(S):	Methanol
DATE PREPARED: (mm/dd/yyyy)	09/08/2021
LAST TESTED: (mm/dd/yyyy)	09/14/2021
EXPIRY DATE: (mm/dd/yyyy)	09/14/2026
RECOMMENDED STORAGE:	Store ampoule in a cool, dark place

DESCRIPTION:

PFAC-MXI is a solution/mixture of two native perfluorooctanesulfonamides (FOSAs) and two native perfluorooctanesulfonamidoethanols (FOSEs). The components and their concentrations are given in Table A.

The individual components have a chemical purity of >98%.

DOCUMENTATION/ DATA ATTACHED:

Table A: Components and Concentrations of the Solution/Mixture
Figure 1: LC/MS Data (SIR)
Figure 2: LC/MS/MS Data (Selected MRM Transitions)

ADDITIONAL INFORMATION:

- See page 2 for further details.

FOR LABORATORY USE ONLY: NOT FOR HUMAN OR DRUG USE

Wellington Laboratories Inc., 345 Southgate Dr. Guelph ON N1G 3M5 CANADA
519-822-2436 • Fax: 519-822-2849 • info@well-labs.com

Form#:13, Issued 2004-11-10
Revision#:9, Revised 2020-12-23

INTENDED USE:

The products prepared by Wellington Laboratories Inc. are for laboratory use only. This certified reference material (CRM) was designed to be used as a standard for the identification and/or quantification of the specific chemical compounds it contains.

HANDLING:

This product should only be used by qualified personnel familiar with its potential hazards and trained in the handling of hazardous chemicals. Due care should be exercised to prevent unnecessary human contact or ingestion. All procedures should be carried out in a well-functioning fume hood and suitable gloves, eye protection, and clothing should be worn at all times. Waste should be disposed of according to national and regional regulations. Safety Data Sheets (SDSs) are available upon request.

SYNTHESIS / CHARACTERIZATION:

Our products are synthesized using single-product unambiguous routes whenever possible. They are then characterized, and their structures and purities confirmed, using a combination of the most relevant techniques, such as NMR, GC/MS, LC/MS/MS, SFC/UV/MS/MS, x-ray crystallography, and melting point. Isotopic purities of mass-labelled compounds are also confirmed using HRGC/HRMS and/or LC/MS/MS.

HOMOGENEITY:

Prior to solution preparation, crystalline material is tested for homogeneity using a variety of techniques (as stated above) and its solubility in a given diluent is taken into consideration. Duplicate solutions of a new product are prepared from the same crystalline lot and, after the addition of an appropriate internal standard, they are compared by GC/MS, LC/MS/MS, and/or SFC/UV/MS/MS. The relative response factors of the analyte of interest in each solution are required to be <5% RSD. New solution lots of existing products, as well as mixtures and calibration solutions, are compared to older lots in a similar manner. This further confirms the homogeneity of the crystalline material as well as the stability and homogeneity of the solutions in the storage containers. In order to maintain the integrity of the assigned value(s), and associated uncertainty, the dilution or injection of a subsample of this product should be performed using calibrated measuring equipment.

UNCERTAINTY:

The maximum combined relative standard uncertainty of our reference standard solutions is calculated using the following equation:

The combined relative standard uncertainty, $u_c(y)$, of a value y and the uncertainty of the independent parameters $x_1, x_2, \ldots x_n$ on which it depends is:

$$u_c(y(x_1, x_2, \ldots x_n)) = \sqrt{\sum_{i=1}^{n} u(y, x_i)^2}$$

where x is expressed as a relative standard uncertainty of the individual parameter.

The individual uncertainties taken into account include those associated with weights (calibration of the balance) and volumes (calibration of the volumetric glassware). An expanded maximum combined percent relative uncertainty of ±5% (calculated with a coverage factor of 2 and a level of confidence of 95%) is stated on the Certificate of Analysis for all of our products.

TRACEABILITY:

All reference standard solutions are traceable to specific crystalline lots. The microbalances used for solution preparation are regularly calibrated by an external ISO/IEC 17025 accredited laboratory. In addition, their calibration is verified prior to each weighing using calibrated external weights traceable to an ISO/IEC 17025 accredited laboratory. All volumetric glassware used is calibrated, of Class A tolerance, and traceable to an ISO/IEC 17025 accredited laboratory. For certain products, traceability to international interlaboratory studies has also been established.

EXPIRY DATE / PERIOD OF VALIDITY:

Ongoing stability studies of this product have demonstrated stability in its composition and concentration, until the specified expiry date, in the unopened ampoule. Monitoring for any degradation or change in concentration of the listed analyte(s) is performed on a routine basis.

LIMITED WARRANTY:

At the time of shipment, all products are warranted to be free of defects in material and workmanship and to conform to the stated technical and purity specifications.

QUALITY MANAGEMENT:

This product was produced using a Quality Management System registered to the latest versions of ISO 9001 by SAI Global, ISO/IEC 17025 by the Canadian Association for Laboratory Accreditation Inc. (CALA; A1226), and ISO 17034 by ANSI National Accreditation Board (ANAB; AR-1523).

CALA Testing Accreditation No. A1226

ANAB ANSI National Accreditation Board ACCREDITED ISO 17034 REFERENCE MATERIAL PRODUCER

For additional information or assistance concerning this or any other products from Wellington Laboratories Inc., please visit our website at www.well-labs.com or contact us directly at info@well-labs.com

Figure 2: **PFAC-MXF; LC/MS/MS Data (Selected MRM Transitions)**



Conditions for Figure 2:

Injection: On-column (PFAC-MXF)

Mobile phase: Same as Figure 1

Flow: 300 µL/min

MS Parameters:
Collision Gas (mbar) = 3.43e-3
Collision Energy (eV) = 6-60 (variable)

INTENDED USE:

The products prepared by Wellington Laboratories Inc. are for laboratory use only. This certified reference material (CRM) was designed to be used as a standard for the identification and/or quantification of the specific chemical compounds it contains.

HANDLING:

This product should only be used by qualified personnel familiar with its potential hazards and trained in the handling of hazardous chemicals. Due care should be exercised to prevent unnecessary human contact or ingestion. All procedures should be carried out in a well-functioning fume hood and suitable gloves, eye protection, and clothing should be worn at all times. Waste should be disposed of according to national and regional regulations. Safety Data Sheets (SDSs) are available upon request.

SYNTHESIS / CHARACTERIZATION:

Our products are synthesized using single-product unambiguous routes whenever possible. They are then characterized, and their structures and purities confirmed, using a combination of the most relevant techniques, such as NMR, GC/MS, LC/MS/MS, SFC/UV/MS/MS, x-ray crystallography, and melting point. Isotopic purities of mass-labelled compounds are also confirmed using HRGC/HRMS and/or LC/MS/MS.

HOMOGENEITY:

Prior to solution preparation, crystalline material is tested for homogeneity using a variety of techniques (as stated above) and its solubility in a given diluent is taken into consideration. Duplicate solutions of a new product are prepared from the same crystalline lot and, after the addition of an appropriate internal standard, they are compared by GC/MS, LC/MS/MS, and/or SFC/UV/MS/MS. The relative response factors of the analyte of interest in each solution are required to be <5% RSD. New solution lots of existing products, as well as mixtures and calibration solutions, are compared to older lots in a similar manner. This further confirms the homogeneity of the crystalline material as well as the stability and homogeneity of the solutions in the storage containers. In order to maintain the integrity of the assigned value(s), and associated uncertainty, the dilution or injection of a subsample of this product should be performed using calibrated measuring equipment.

UNCERTAINTY:

The maximum combined relative standard uncertainty of our reference standard solutions is calculated using the following equation:

The combined relative standard uncertainty, $u_c(y)$, of a value y and the uncertainty of the independent parameters $x_1, x_2, \ldots x_n$ on which it depends is:

$$u_c(y(x_1, x_2, \ldots x_n)) = \sqrt{\sum_{i=1}^{n} u(y, x_i)^2}$$

where x is expressed as a relative standard uncertainty of the individual parameter.

The individual uncertainties taken into account include those associated with weights (calibration of the balance) and volumes (calibration of the volumetric glassware). An expanded maximum combined percent relative uncertainty of ±5% (calculated with a coverage factor of 2 and a level of confidence of 95%) is stated on the Certificate of Analysis for all of our products.

TRACEABILITY:

All reference standard solutions are traceable to specific crystalline lots. The microbalances used for solution preparation are regularly calibrated by an external ISO/IEC 17025 accredited laboratory. In addition, their calibration is verified prior to each weighing using calibrated external weights traceable to an ISO/IEC 17025 accredited laboratory. All volumetric glassware used is calibrated, of Class A tolerance, and traceable to an ISO/IEC 17025 accredited laboratory. For certain products, traceability to international interlaboratory studies has also been established.

EXPIRY DATE / PERIOD OF VALIDITY:

Ongoing stability studies of this product have demonstrated stability in its composition and concentration, until the specified expiry date, in the unopened ampoule. Monitoring for any degradation or change in concentration of the listed analyte(s) is performed on a routine basis.

LIMITED WARRANTY:

At the time of shipment, all products are warranted to be free of defects in material and workmanship and to conform to the stated technical and purity specifications.

QUALITY MANAGEMENT:

This product was produced using a Quality Management System registered to the latest versions of ISO 9001 by SAI Global, ISO/IEC 17025 by the Canadian Association for Laboratory Accreditation Inc. (CALA; A1226), and ISO 17034 by ANSI National Accreditation Board (ANAB; AR-1523).

CALA Testing Accreditation No. A1226

ANAB ANSI National Accreditation Board ACCREDITED ISO 17034 REFERENCE MATERIAL PRODUCER

For additional information or assistance concerning this or any other products from Wellington Laboratories Inc., please visit our website at www.well-labs.com or contact us directly at info@well-labs.com

Form#:13, Issued 2004-11-10
Revision#:9, Revised 2020-12-23

PFACMXF0122 (2 of 5)
rev0

Table A: **PFAC-MXF; Components and Concentrations (ng/mL; ± 5% in Methanol/Water (<1%))**

Compound	Acronym	Concentration* (ng/ml)	Peak Assignment in Figure 1
2,3,3,3-Tetrafluoro-2-(1,1,2,2,3,3,3-heptafluoropropoxy)-propanoic acid	HFPO-DA	2000	A

Compound	Acronym	Concentration* (ng/mL)		Peak Assignment in Figure 1
		as the salt	as the acid	
Sodium dodecafluoro-3H-4,8-dioxanonanoate	NaDONA	2000	1890	B
Potassium 9-chlorohexadecafluoro-3-oxanonane-1-sulfonate	9Cl-PF3ONS	2000	1870	C
Potassium 11-chloroeicosafluoro-3-oxaundecane-1-sulfonate	11Cl-PF3OUdS	2000	1890	D

* Concentrations have been rounded to three significant figures.

Certified By: _____ **Date:** 01/12/2022 (mm/dd/yyyy)
B.G. Chittim, General Manager

Figure 1: **PFAC-MXF; LC/MS Data (SIR)**



Conditions for Figure 1:

Waters Acquity Ultra Performance LC
Waters Xevo TQ-S micro MS

Chromatographic Conditions:

Column: Acquity UPLC BEH Shield RP_{18}
1.7 µm, 2.1 x 100 mm

Mobile phase: Gradient
Start: 45% H_2O / 55% (80:20 MeOH:ACN)
(both with 10 mM NH_4OAc buffer)
Ramp to 90% organic over 8 min and hold for 2 min
before returning to initial conditions in 0.75 min.
Time: 12 min

Flow: 300 µL/min

MS Parameters:

Experiment: SIR

Source: Electrospray (negative)
Capillary Voltage (kV) = 2.00
Cone Voltage (V) = variable (15-74)
Desolvation Temperature (°C) = 325
Desolvation Gas Flow (L/hr) = 1000

Form#:13, Issued 2004-11-10
Revision#:9, Revised 2020-12-23

PFACMXF0122 (4 of 5)
rev0

YORK
ANALYTICAL LABORATORIES, INC.

Analytical Standard Record

Standard ID: **Y22B199**

Description:	PFAC-MXF-Native Repl.STOCK EPA 1633 PFAS	Prepared:	02/17/2022
Standard Type:	Other	**Expires:**	**01/11/2025**
Solvent:	MeOH/H20	Prepared By:	Robert Q. Bradley
Final Volume (mls):	1	Department:	PFAS
Vials:	1	Lot No.:	PFACMXF0122
Vendor:	Wellington Laboratories		

Comments:

Analyte	CAS Number	Concentration	Units
11CL-PF3OUdS	763051-92-9	1.89	ug/mL
9CL-PF3ONS	756426-58-1	1.87	ug/mL
ADONA	919005-14-4	1.89	ug/mL
HFPO-DA (Gen-X)	13252-13-6	2	ug/mL

Reviewed By Date

Page 1 of 1

WELLINGTON LABORATORIES

CERTIFICATE OF ANALYSIS
DOCUMENTATION

PFAC-MXF

Native Replacement PFAS Solution/Mixture

PRODUCT CODE:	PFAC-MXF
LOT NUMBER:	PFACMXF0122
SOLVENT(S):	Methanol / Water (<1%)
DATE PREPARED: (mm/dd/yyyy)	01/10/2022
LAST TESTED: (mm/dd/yyyy)	01/11/2022
EXPIRY DATE: (mm/dd/yyyy)	01/11/2025
RECOMMENDED STORAGE:	Refrigerate ampoule

DESCRIPTION:

PFAC-MXF is a solution/mixture of sodium dodecafluoro-3H-4,8-dioxanonanoate (NaDONA), the major and minor components of F-53B (9Cl-PF3ONS and 11Cl-PF3OUdS), and GenX (HFPO-DA). The components and their concentrations are given in Table A.

The individual native components of this mixture all have chemical purities of >98%.

DOCUMENTATION/ DATA ATTACHED:

Table A: Components and Concentrations of the Solution/Mixture
Figure 1: LC/MS Data (SIR)
Figure 2: LC/MS/MS Data (Selected MRM Transitions)

ADDITIONAL INFORMATION:

- See page 2 for further details.
- Contains 4 mole eq. of NaOH to prevent conversion of the carboxylic acid to the methyl ester.

FOR LABORATORY USE ONLY: NOT FOR HUMAN OR DRUG USE

Wellington Laboratories Inc., 345 Southgate Dr. Guelph ON N1G 3M5 CANADA
519-822-2436 • Fax: 519-822-2849 • info@well-labs.com

Form#:13, Issued 2004-11-10
Revision#:9, Revised 2020-12-23

Table A: **PFAC-MXJ; Components and Concentrations (µg/mL; ± 5% in methanol)**

Compound	Acronym	Concentration (µg/mL)
3-Perfluoropropyl propanoic acid	FPrPA	4.00
3-Perfluoropentyl propanoic acid	FPePA	20.0
3-Perfluoroheptyl propanoic acid	FHpPA	20.0

Certified By: _____ **Date:** 10/02/2021
(mm/dd/yyyy)
B.G. Chittim, General Manager

Form#:13, Issued 2004-11-10
Revision#:9, Revised 2020-12-23

PFACMXJ0921 (3 of 5)
rev1

Figure 1: **PFAC-MXJ; LC/MS Data (SIR)**



Conditions for Figure 1:

Waters Acquity Ultra Performance LC
Waters Xevo TQ-S micro MS

Chromatographic Conditions:

Column: Acquity UPLC BEH Shield RP_{18}
1.7 µm, 2.1 x 100 mm

Mobile phase: Gradient
Start: 50% H_2O / 50% (80:20 MeOH:ACN)
(both with 10 mM NH_4OAc buffer)
Ramp to 90% organic over 9 min and hold for
2 min before returning to initial conditions in 1 min.
Time: 15 min

Flow: 300 µL/min

MS Parameters:

Experiment: SIR

Source: Electrospray (negative)
Capillary Voltage (kV) = 2.50
Cone Voltage (V) = variable (2-74)
Desolvation Temperature (°C) = 350
Desolvation Gas Flow (L/hr) = 1000

Form#:13, Issued 2004-11-10
Revision#:9, Revised 2020-12-23

PFACMXJ0921 (4 of 5)
rev1

Figure 2: **PFAC-MXJ; LC/MS/MS Data (Selected MRM Transitions)**



Conditions for Figure 2:

Injection: On-column (PFAC-MXJ)

Mobile phase: Same as Figure 1

Flow: 300 µL/min

MS Parameters:
Collision Gas (mbar) = 3.31e-3
Collision Energy (eV) = 6-60 (variable)

Form#:13, Issued 2004-11-10
Revision#:9, Revised 2020-12-23

PFACMXJ0921 (5 of 5)
rev1

YORK
ANALYTICAL LABORATORIES, INC.

Analytical Standard Record

Standard ID: **Y22B205**

Description:	PFAC-MXJ-EPA 1633 Stock mix	Prepared:	02/17/2022
Standard Type:	Other	Expires:	09/14/2026
Solvent:	Methanol	Prepared By:	Robert Q. Bradley
Final Volume (mls):	1	Department:	PFAS
Vials:	1	Lot No.:	PFACMXJ0921
Vendor:	Wellington Laboratories		

Comments:

Analyte	CAS Number	Concentration	Units
3-Perfluoroheptyl propanoic acid (FHpPA	812-70-4	20	ug/mL
3-Perfluoropentyl propanoic acid (FPePA)	914637-49-3	20	ug/mL
3-Perfluoropropyl propanoic acid (FPrPA)	356-02-2	4	ug/mL

Reviewed By _____ Date _____

Page 1 of 1

WELLINGTON LABORATORIES

CERTIFICATE OF ANALYSIS
DOCUMENTATION

PFAC-MXJ

Native X:3 Fluorotelomer Carboxylic Acid Solution/Mixture

PRODUCT CODE:	PFAC-MXJ
LOT NUMBER:	PFACMXJ0921
SOLVENT(S):	Methanol
DATE PREPARED: (mm/dd/yyyy)	09/08/2021
LAST TESTED: (mm/dd/yyyy)	09/14/2021
EXPIRY DATE: (mm/dd/yyyy)	09/14/2026
RECOMMENDED STORAGE:	Store ampoule in a cool, dark place

DESCRIPTION:

PFAC-MXJ is a solution/mixture of three native X:3 fluorotelomer carboxylic acids. The components and their concentrations are given in Table A.

The individual components have a chemical purity of >98%.

DOCUMENTATION/ DATA ATTACHED:

Table A: Components and Concentrations of the Solution/Mixture
Figure 1: LC/MS Data (SIR)
Figure 2: LC/MS/MS Data (Selected MRM Transitions)

ADDITIONAL INFORMATION:

- See page 2 for further details.

FOR LABORATORY USE ONLY: NOT FOR HUMAN OR DRUG USE

Wellington Laboratories Inc., 345 Southgate Dr. Guelph ON N1G 3M5 CANADA
519-822-2436 • Fax: 519-822-2849 • info@well-labs.com

Form#:13, Issued 2004-11-10
Revision#:9, Revised 2020-12-23

INTENDED USE:

The products prepared by Wellington Laboratories Inc. are for laboratory use only. This certified reference material (CRM) was designed to be used as a standard for the identification and/or quantification of the specific chemical compounds it contains.

HANDLING:

This product should only be used by qualified personnel familiar with its potential hazards and trained in the handling of hazardous chemicals. Due care should be exercised to prevent unnecessary human contact or ingestion. All procedures should be carried out in a well-functioning fume hood and suitable gloves, eye protection, and clothing should be worn at all times. Waste should be disposed of according to national and regional regulations. Safety Data Sheets (SDSs) are available upon request.

SYNTHESIS / CHARACTERIZATION:

Our products are synthesized using single-product unambiguous routes whenever possible. They are then characterized, and their structures and purities confirmed, using a combination of the most relevant techniques, such as NMR, GC/MS, LC/MS/MS, SFC/UV/MS/MS, x-ray crystallography, and melting point. Isotopic purities of mass-labelled compounds are also confirmed using HRGC/HRMS and/or LC/MS/MS.

HOMOGENEITY:

Prior to solution preparation, crystalline material is tested for homogeneity using a variety of techniques (as stated above) and its solubility in a given diluent is taken into consideration. Duplicate solutions of a new product are prepared from the same crystalline lot and, after the addition of an appropriate internal standard, they are compared by GC/MS, LC/MS/MS, and/or SFC/UV/MS/MS. The relative response factors of the analyte of interest in each solution are required to be <5% RSD. New solution lots of existing products, as well as mixtures and calibration solutions, are compared to older lots in a similar manner. This further confirms the homogeneity of the crystalline material as well as the stability and homogeneity of the solutions in the storage containers. In order to maintain the integrity of the assigned value(s), and associated uncertainty, the dilution or injection of a subsample of this product should be performed using calibrated measuring equipment.

UNCERTAINTY:

The maximum combined relative standard uncertainty of our reference standard solutions is calculated using the following equation:

The combined relative standard uncertainty, $u_c(y)$, of a value y and the uncertainty of the independent parameters $x_1, x_2, \ldots x_n$ on which it depends is:

$$u_c(y(x_1, x_2, \ldots x_n)) = \sqrt{\sum_{i=1}^{n} u(y, x_i)^2}$$

where x is expressed as a relative standard uncertainty of the individual parameter.

The individual uncertainties taken into account include those associated with weights (calibration of the balance) and volumes (calibration of the volumetric glassware). An expanded maximum combined percent relative uncertainty of ±5% (calculated with a coverage factor of 2 and a level of confidence of 95%) is stated on the Certificate of Analysis for all of our products.

TRACEABILITY:

All reference standard solutions are traceable to specific crystalline lots. The microbalances used for solution preparation are regularly calibrated by an external ISO/IEC 17025 accredited laboratory. In addition, their calibration is verified prior to each weighing using calibrated external weights traceable to an ISO/IEC 17025 accredited laboratory. All volumetric glassware used is calibrated, of Class A tolerance, and traceable to an ISO/IEC 17025 accredited laboratory. For certain products, traceability to international interlaboratory studies has also been established.

EXPIRY DATE / PERIOD OF VALIDITY:

Ongoing stability studies of this product have demonstrated stability in its composition and concentration, until the specified expiry date, in the unopened ampoule. Monitoring for any degradation or change in concentration of the listed analyte(s) is performed on a routine basis.

LIMITED WARRANTY:

At the time of shipment, all products are warranted to be free of defects in material and workmanship and to conform to the stated technical and purity specifications.

QUALITY MANAGEMENT:

This product was produced using a Quality Management System registered to the latest versions of ISO 9001 by SAI Global, ISO/IEC 17025 by the Canadian Association for Laboratory Accreditation Inc. (CALA; A1226), and ISO 17034 by ANSI National Accreditation Board (ANAB; AR-1523).

CALA Testing Accreditation No. A1226

ANAB ANSI National Accreditation Board ACCREDITED ISO 17034 REFERENCE MATERIAL PRODUCER

For additional information or assistance concerning this or any other products from Wellington Laboratories Inc., please visit our website at www.well-labs.com or contact us directly at info@well-labs.com

Form#:13, Issued 2004-11-10
Revision#:9, Revised 2020-12-23

PFACMXJ0921 (2 of 5)
rev1

Figure 2: **PFAC-MXH; LC/MS/MS Data (Selected MRM Transitions)**



Form#:13, Issued 2004-11-10
Revision#:9, Revised 2020-12-23

PFACMXH0921 (10 of 11)
rev0

Figure 2: **PFAC-MXH; LC/MS/MS Data (Selected MRM Transitions)**



Conditions for Figure 2:

Injection: On-column (PFAC-MXH)

Mobile phase: Same as Figure 1

Flow: 300 µL/min

MS Parameters:
Collision Gas (mbar) = 3.31e-3
Collision Energy (eV) = 6-60 (variable)

Table E: **PFOSK; Isomeric Components and Percent Composition (by ^{19}F-NMR)***

Isomer	Compound	Structure	Percent Composition by ^{19}F-NMR	
1	Potassium perfluoro-1-octanesulfonate	$CF_3CF_2CF_2CF_2CF_2CF_2CF_2CF_2SO_3^-K^+$	78.8	78.8
2	Potassium 1-trifluoromethylperfluoroheptanesulfonate**	$CF_3CF_2CF_2CF_2CF_2CF_2CF(CF_3)SO_3^-K^+$	1.2	21.1
3	Potassium 2-trifluoromethylperfluoroheptanesulfonate	$CF_3CF_2CF_2CF_2CF_2CF(CF_3)CF_2SO_3^-K^+$	0.6	
4	Potassium 3-trifluoromethylperfluoroheptanesulfonate	$CF_3CF_2CF_2CF_2CF(CF_3)CF_2CF_2SO_3^-K^+$	1.9	
5	Potassium 4-trifluoromethylperfluoroheptanesulfonate	$CF_3CF_2CF_2CF(CF_3)CF_2CF_2CF_2SO_3^-K^+$	2.2	
6	Potassium 5-trifluoromethylperfluoroheptanesulfonate	$CF_3CF_2CF(CF_3)CF_2CF_2CF_2CF_2SO_3^-K^+$	4.5	
7	Potassium 6-trifluoromethylperfluoroheptanesulfonate	$CF_3CF(CF_3)CF_2CF_2CF_2CF_2CF_2SO_3^-K^+$	10.0	
8	Potassium 5,5-di(trifluoromethyl)perfluorohexanesulfonate	$CF_3C(CF_3)CF_2CF_2CF_2CF_2SO_3^-K^+$	0.2	
9	Potassium 4,4-di(trifluoromethyl)perfluorohexanesulfonate	$CF_3CF_2C(CF_3)CF_2CF_2CF_2SO_3^-K^+$	0.03	
10	Potassium 4,5-di(trifluoromethyl)perfluorohexanesulfonate	$CF_3CF(CF_3)CF_2CF_2CF_2SO_3^-K^+$	0.4	
11	Potassium 3,5-di(trifluoromethyl)perfluorohexanesulfonate	$CF_3CF(CF_3)CF_2CF_2CF_2SO_3^-K^+$	0.07	

* Percent of total perfluorooctanesulfonate isomers only.
** Systematic Name: Potassium perfluorooctane-2-sulfonate.

Figure 1: **PFAC-MXH; LC/MS Data (SIR)**



Conditions for Figure 1:

Waters Acquity Ultra Performance LC
Waters Xevo TQ-S micro MS

Chromatographic Conditions:

Column: Acquity UPLC BEH Shield RP_{18}
1.7 µm, 2.1 x 100 mm

Mobile phase: Gradient
Start: 50% H_2O / 50% (80:20 MeOH:ACN)
(both with 10 mM NH_4OAc buffer)
Ramp to 90% organic over 9 min and hold for 2 min
before returning to initial conditions in 1 min.
Time: 15 min

Flow: 300 µL/min

MS Parameters:

Experiment: SIR

Source: Electrospray (negative)
Capillary Voltage (kV) = 2.50
Cone Voltage (V) = variable (2-74)
Desolvation Temperature (°C) = 350
Desolvation Gas Flow (L/hr) = 1000

Form#:13, Issued 2004-11-10
Revision#:9, Revised 2020-12-23

PFACMXH0921 (8 of 11)
rev0

Figure 2: **PFAC-MXH; LC/MS/MS Data (Selected MRM Transitions)**



Form#:13, Issued 2004-11-10
Revision#:9, Revised 2020-12-23

PFACMXH0921 (9 of 11)
rev0

Table B: **br-NMeFOSAA; Isomeric Components and Percent Composition (by ^{19}F-NMR)***

Isomer	Compound	Structure	Percent Composition by ^{19}F-NMR	
1	N-methylperfluoro-1-octanesulfonamidoacetic acid	$CF_3(CF_2)_7SO_2N(CH_3)CH_2CO_2H$	76.0	76.0
2	N-methylperfluoro-3-methylheptanesulfonamidoacetic acid	$CF_3(CF_2)_3CF(CF_3)(CF_2)_2SO_2N(CH_3)CH_2CO_2H$	0.7	24.0
3	N-methylperfluoro-4-methylheptanesulfonamidoacetic acid	$CF_3(CF_2)_2CF(CF_3)(CF_2)_3SO_2N(CH_3)CH_2CO_2H$	2.0	
4	N-methylperfluoro-5-methylheptanesulfonamidoacetic acid	$CF_3CF_2CF(CF_3)(CF_2)_4SO_2N(CH_3)CH_2CO_2H$	6.0	
5	N-methylperfluoro-6-methylheptanesulfonamidoacetic acid	$CF_3CF(CF_3)(CF_2)_5SO_2N(CH_3)CH_2CO_2H$	14.0	
6	N-methylperfluoro-5,5-dimethylhexanesulfonamidoacetic acid	$CF_3C(CF_3)_2(CF_2)_4SO_2N(CH_3)CH_2CO_2H$	0.2	
7	Other Unidentified Isomers		1.1	

* Percent of total N-methylperfluorooctanesulfonamidoacetic acid isomers only.

Table C: **br-NEtFOSAA; Isomeric Components and Percent Composition (by ^{19}F-NMR)***

Isomer	Compound	Structure	Percent Composition by ^{19}F-NMR	
1	N-ethylperfluoro-1-octanesulfonamidoacetic acid	$CF_3(CF_2)_7SO_2N(C_2H_5)CH_2CO_2H$	77.5	77.5
2	N-ethylperfluoro-3-methylheptanesulfonamidoacetic acid	$CF_3(CF_2)_3CF(CF_3)(CF_2)_2SO_2N(C_2H_5)CH_2CO_2H$	2.3	22.5
3	N-ethylperfluoro-4-methylheptanesulfonamidoacetic acid	$CF_3(CF_2)_2CF(CF_3)(CF_2)_3SO_2N(C_2H_5)CH_2CO_2H$	2.2	
4	N-ethylperfluoro-5-methylheptanesulfonamidoacetic acid	$CF_3CF_2CF(CF_3)(CF_2)_4SO_2N(C_2H_5)CH_2CO_2H$	5.4	
5	N-ethylperfluoro-6-methylheptanesulfonamidoacetic acid	$CF_3CF(CF_3)(CF_2)_5SO_2N(C_2H_5)CH_2CO_2H$	10.4	
6	N-ethylperfluoro-5,5-dimethylhexanesulfonamidoacetic acid	$CF_3C(CF_3)_2(CF_2)_4SO_2N(C_2H_5)CH_2CO_2H$	0.3	
7	N-ethylperfluoro-4,5-dimethylhexanesulfonamidoacetic acid	$CF_3CF(CF_3)CF(CF_2)_3SO_2N(C_2H_5)CH_2CO_2H$	0.3	
8	N-ethylperfluoro-3,5-dimethylhexanesulfonamidoacetic acid	$CF_3CF(CF_3)CF_2CF(CF_2)_2SO_2N(C_2H_5)CH_2CO_2H$	0.3	
9	Other Unidentified Isomers		1.3	

* Percent of total N-ethylperfluorooctanesulfonamidoacetic acid isomers only.

Table D: **PFHxSK; Isomeric Components and Percent Composition (by ^{19}F-NMR)***

Isomer	Compound	Structure	Percent Composition by ^{19}F-NMR	
1	Potassium perfluoro-1-hexanesulfonate	$CF_3CF_2CF_2CF_2CF_2CF_2SO_3^-K^+$	81.1	81.1
2	Potassium 1-trifluoromethylperfluoropentanesulfonate**	$CF_3CF_2CF_2CF_2CF(CF_3)SO_3^-K^+$	2.9	18.9
3	Potassium 2-trifluoromethylperfluoropentanesulfonate	$CF_3CF_2CF_2CF(CF_3)CF_2SO_3^-K^+$	1.4	
4	Potassium 3-trifluoromethylperfluoropentanesulfonate	$CF_3CF_2CF(CF_3)CF_2CF_2SO_3^-K^+$	5.0	
5	Potassium 4-trifluoromethylperfluoropentanesulfonate	$CF_3CF(CF_3)CF_2CF_2CF_2SO_3^-K^+$	8.9	
6	Potassium 3,3-di(trifluoromethyl)perfluorobutanesulfonate	$CF_3C(CF_3)CF_2CF_2SO_3^-K^+$	0.2	
7	Other Unidentified Isomers		0.5	

* Percent of total perfluorohexanesulfonate isomers only.
** Systematic Name: Potassium perfluorohexane-2-sulfonate.

WELLINGTON LABORATORIES

CERTIFICATE OF ANALYSIS
DOCUMENTATION

PFAC-MXH

Native Per- and Poly-fluoroalkyl Substance Solution/Mixture

PRODUCT CODE:	PFAC-MXH
LOT NUMBER:	PFACMXH0921
SOLVENT(S):	Methanol / Isopropanol (2%) / Water (<1%)
DATE PREPARED: (mm/dd/yyyy)	09/09/2021
LAST TESTED: (mm/dd/yyyy)	09/14/2021
EXPIRY DATE: (mm/dd/yyyy)	09/14/2026
RECOMMENDED STORAGE:	Refrigerate ampoule

DESCRIPTION:

PFAC-MXH is a solution/mixture of eleven native linear perfluoroalkylcarboxylic acids (C_4-C_{14}), eight native perfluoroalkanesulfonates (C_4, C_5, C_7, C_9, C_{10} and C_{12} linear; C_6 and C_8 linear and branched), three native fluorotelomer sulfonates (4:2, 6:2, and 8:2), two native linear and branched perfluorooctanesulfonamidoacetic acids, and perfluoro-1-octanesulfonamide (FOSA). The components and their concentrations are given in Table A.

The individual components of this mixture all have chemical purities of >98%.

DOCUMENTATION/ DATA ATTACHED:

Table A: Components and Concentrations of the Solution/Mixture
Table B: Isomeric Components and Percent Composition of br-NMeFOSAA
Table C: Isomeric Components and Percent Composition of br-NEtFOSAA
Table D: Isomeric Components and Percent Composition of PFHxSK
Table E: Isomeric Components and Percent Composition of PFOSK
Figure 1: LC/MS Data (SIR)
Figure 2: LC/MS/MS Data (Selected MRM Transitions)

ADDITIONAL INFORMATION:

- See page 2 for further details.
- Contains 4 mole eq. of NaOH to prevent conversion of the carboxylic acids to their respective methyl esters.

FOR LABORATORY USE ONLY: NOT FOR HUMAN OR DRUG USE

Wellington Laboratories Inc., 345 Southgate Dr. Guelph ON N1G 3M5 CANADA
519-822-2436 • Fax: 519-822-2849 • info@well-labs.com

Form#:13, Issued 2004-11-10
Revision#:9, Revised 2020-12-23

INTENDED USE:

The products prepared by Wellington Laboratories Inc. are for laboratory use only. This certified reference material (CRM) was designed to be used as a standard for the identification and/or quantification of the specific chemical compounds it contains.

HANDLING:

This product should only be used by qualified personnel familiar with its potential hazards and trained in the handling of hazardous chemicals. Due care should be exercised to prevent unnecessary human contact or ingestion. All procedures should be carried out in a well-functioning fume hood and suitable gloves, eye protection, and clothing should be worn at all times. Waste should be disposed of according to national and regional regulations. Safety Data Sheets (SDSs) are available upon request.

SYNTHESIS / CHARACTERIZATION:

Our products are synthesized using single-product unambiguous routes whenever possible. They are then characterized, and their structures and purities confirmed, using a combination of the most relevant techniques, such as NMR, GC/MS, LC/MS/MS, SFC/UV/MS/MS, x-ray crystallography, and melting point. Isotopic purities of mass-labelled compounds are also confirmed using HRGC/HRMS and/or LC/MS/MS.

HOMOGENEITY:

Prior to solution preparation, crystalline material is tested for homogeneity using a variety of techniques (as stated above) and its solubility in a given diluent is taken into consideration. Duplicate solutions of a new product are prepared from the same crystalline lot and, after the addition of an appropriate internal standard, they are compared by GC/MS, LC/MS/MS, and/or SFC/UV/MS/MS. The relative response factors of the analyte of interest in each solution are required to be <5% RSD. New solution lots of existing products, as well as mixtures and calibration solutions, are compared to older lots in a similar manner. This further confirms the homogeneity of the crystalline material as well as the stability and homogeneity of the solutions in the storage containers. In order to maintain the integrity of the assigned value(s), and associated uncertainty, the dilution or injection of a subsample of this product should be performed using calibrated measuring equipment.

UNCERTAINTY:

The maximum combined relative standard uncertainty of our reference standard solutions is calculated using the following equation:

The combined relative standard uncertainty, $u_c(y)$, of a value y and the uncertainty of the independent parameters $x_1, x_2, \ldots x_n$ on which it depends is:

$$u_c(y(x_1, x_2, \ldots x_n)) = \sqrt{\sum_{i=1}^{n} u(y, x_i)^2}$$

where x is expressed as a relative standard uncertainty of the individual parameter.

The individual uncertainties taken into account include those associated with weights (calibration of the balance) and volumes (calibration of the volumetric glassware). An expanded maximum combined percent relative uncertainty of ±5% (calculated with a coverage factor of 2 and a level of confidence of 95%) is stated on the Certificate of Analysis for all of our products.

TRACEABILITY:

All reference standard solutions are traceable to specific crystalline lots. The microbalances used for solution preparation are regularly calibrated by an external ISO/IEC 17025 accredited laboratory. In addition, their calibration is verified prior to each weighing using calibrated external weights traceable to an ISO/IEC 17025 accredited laboratory. All volumetric glassware used is calibrated, of Class A tolerance, and traceable to an ISO/IEC 17025 accredited laboratory. For certain products, traceability to international interlaboratory studies has also been established.

EXPIRY DATE / PERIOD OF VALIDITY:

Ongoing stability studies of this product have demonstrated stability in its composition and concentration, until the specified expiry date, in the unopened ampoule. Monitoring for any degradation or change in concentration of the listed analyte(s) is performed on a routine basis.

LIMITED WARRANTY:

At the time of shipment, all products are warranted to be free of defects in material and workmanship and to conform to the stated technical and purity specifications.

QUALITY MANAGEMENT:

This product was produced using a Quality Management System registered to the latest versions of ISO 9001 by SAI Global, ISO/IEC 17025 by the Canadian Association for Laboratory Accreditation Inc. (CALA; A1226), and ISO 17034 by ANSI National Accreditation Board (ANAB; AR-1523).

CALA Testing Accreditation No. A1226

ANAB ANSI National Accreditation Board ACCREDITED ISO 17034 REFERENCE MATERIAL PRODUCER

For additional information or assistance concerning this or any other products from Wellington Laboratories Inc., please visit our website at www.well-labs.com or contact us directly at info@well-labs.com

Table A: **PFAC-MXH; Components and Concentrations (µg/mL, ± 5% in methanol / isopropanol (2%) / water (<1%))**

Compound	Acronym	Concentration* (µg/mL)	Peak Assignment in Figure 1
Perfluoro-n-butanoic acid	PFBA	4.00	1
Perfluoro-n-pentanoic acid	PFPeA	2.00	2
Perfluoro-n-hexanoic acid	PFHxA	1.00	5
Perfluoro-n-heptanoic acid	PFHpA	1.00	7
Perfluoro-n-octanoic acid	PFOA	1.00	11
Perfluoro-n-nonanoic acid	PFNA	1.00	14
Perfluoro-n-decanoic acid	PFDA	1.00	18
Perfluoro-n-undecanoic acid	PFUdA	1.00	23
Perfluoro-n-dodecanoic acid	PFDoA	1.00	26
Perfluoro-n-tridecanoic acid	PFTrDA	1.00	27
Perfluoro-n-tetradecanoic acid	PFTeDA	1.00	29
Perfluoro-1-octanesulfonamide	FOSA	1.00	25
N-methylperfluorooctanesulfonamidoacetic acid [a]	N-MeFOSAA: linear isomer	0.760	20
	N-MeFOSAA: ∑ branched isomers	0.240	17
N-ethylperfluorooctanesulfonamidoacetic acid [b]	N-EtFOSAA: linear isomer	0.775	22
	N-EtFOSAA: ∑ branched isomers	0.225	21

Compound	Acronym	Concentration* (µg/mL)		Peak Assignment in Figure 1
		as the salt	as the acid	
Potassium perfluoro-1-butanesulfonate	L-PFBS	1.00	0.887	3
Sodium perfluoro-1-pentanesulfonate	L-PFPeS	1.00	0.941	6
Potassium perfluorohexanesulfonate [c]	PFHxSK: linear isomer	0.811	0.741	9
	PFHxSK: ∑ branched isomers	0.189	0.173	8
Sodium perfluoro-1-heptanesulfonate	L-PFHpS	1.00	0.953	12
Potassium perfluorooctanesulfonate [d]	PFOSK: linear isomer	0.788	0.732	15
	PFOSK: ∑ branched isomers	0.211	0.196	13
Sodium perfluoro-1-nonanesulfonate	L-PFNS	1.00	0.962	19
Sodium perfluoro-1-decanesulfonate	L-PFDS	1.00	0.965	24
Sodium perfluoro-1-dodecanesulfonate	L-PFDoS	1.00	0.970	28
Sodium 1H,1H,2H,2H-perfluorohexanesulfonate	4:2FTS	4.00	3.75	4
Sodium 1H,1H,2H,2H-perfluorooctanesulfonate	6:2FTS	4.00	3.80	10
Sodium 1H,1H,2H,2H-perfluorodecanesulfonate	8:2FTS	4.00	3.84	16

[a] See Table B for percent composition of linear and branched N-MeFOSAA isomers.
[b] See Table C for percent composition of linear and branched N-EtFOSAA isomers.
[c] See Table D for percent composition of linear and branched PFHxSK isomers.
[d] See Table E for percent composition of linear and branched PFOSK isomers.

* Concentrations have been rounded to three significant figures.

Certified By: _____ **Date:** 09/23/2021 (mm/dd/yyyy)
B.G. Chittim, General Manager

Form#:13, Issued 2004-11-10
Revision#:9, Revised 2020-12-23

PFACMXH0921 (3 of 11)
rev0

YORK
ANALYTICAL LABORATORIES, INC.

Analytical Standard Record

Standard ID: **Y22B201**

Description:	PFAC-MXH STOCK PFAS EPA 1633	Prepared:	02/17/2022
Standard Type:	Other	**Expires:**	**09/14/2026**
Solvent:	MeOH/IPA/H2O	Prepared By:	Robert Q. Bradley
Final Volume (mls):	1	Department:	PFAS
Vials:	1	Lot No.:	PFACMXH0921
Vendor:	Wellington Laboratories		

Comments:

Analyte	CAS Number	Concentration	Units
1H,1H,2H,2H-Perfluorodecanesulfonic acid	39108-34-4	3.84	ug/mL
1H,1H,2H,2H-Perfluorohexanesulfonic acid	757124-72-4	3.75	ug/mL
1H,1H,2H,2H-Perfluorooctanesulfonic acid	27619-97-2	3.8	ug/mL
N-EtFOSAA	2991-50-6	1	ug/mL
N-MeFOSAA	2355-31-9	1	ug/mL
Perfluoro-1-decanesulfonic acid (PFDS)	335-77-3	0.965	ug/mL
Perfluoro-1-heptanesulfonic acid (PFHpS)	375-92-8	0.953	ug/mL
Perfluoro-1-nonanesulfonic acid (PFNS)	68259-12-1	0.962	ug/mL
Perfluoro-1-octanesulfonamide (FOSA)	754-91-6	1	ug/mL
Perfluoro-1-pentanesulfonate (PFPeS)	2706-91-4	0.941	ug/mL
Perfluorobutanesulfonic acid (PFBS)	375-73-5	0.887	ug/mL
Perfluorodecanesulfonic acid(PFDS)	335-77-3	0.965	ug/mL
Perfluorodecanoic acid (PFDA)	335-76-2	1	ug/mL
Perfluorododecanoic acid (PFDoA)	307-55-1	1	ug/mL
Perfluoroheptanoic acid (PFHpA)	375-85-9	1	ug/mL
Perfluorohexanesulfonic acid (PFHxS)	355-46-4	0.914	ug/mL
Perfluorohexanoic acid (PFHxA)	307-24-4	1	ug/mL
Perfluoro-n-butanoic acid (PFBA)	375-22-4	4	ug/mL
Perfluorononanoic acid (PFNA)	375-95-1	1	ug/mL
Perfluorooctanesulfonic acid (PFOS)	1763-23-1	0.928	ug/mL
Perfluorooctanoic acid (PFOA)	335-67-1	1	ug/mL
Perfluoropentanoic acid (PFPeA)	2706-90-3	1	ug/mL
Perfluorotetradecanoic acid (PFTA)	376-06-7	1	ug/mL
Perfluorotridecanoic acid (PFTrDA)	72629-94-8	1	ug/mL
Perfluoroundecanoic acid (PFUnA)	2058-94-8	1	ug/mL

Reviewed By Date

Page 1 of 1

Attachment 4 – Calibration Concentrations, nominal

Calibration Solutions (ng/mL) Compound CS1 (LOQ) CS2 Perfluoroalkyl carboxylic			CS3	CS4 (CV[1])	CS5	CS6	CS7[2]
acids							
PFBA	0.8	2	5	10	20	50	250
PFPeA	0.4	1	2.5	5	10	25	125
PFHxA	0.2	0.5	1.25	2.5	5	12.5	62.5
PFHpA	0.2	0.5	1.25	2.5	5	12.5	62.5
PFOA	0.2	0.5	1.25	2.5	5	12.5	62.5
PFNA	0.2	0.5	1.25	2.5	5	12.5	62.5
PFDA	0.2	0.5	1.25	2.5	5	12.5	62.5
PFUnA	0.2	0.5	1.25	2.5	5	12.5	62.5
PFDoA	0.2	0.5	1.25	2.5	5	12.5	62.5
PFTrDA	0.2	0.5	1.25	2.5	5	12.5	62.5
PFTeDA	0.2	0.5	1.25	2.5	5	12.5	62.5
Perfluoroalkyl sulfonic acids							
PFBS	0.2	0.5	1.25	2.5	5	12.5	62.5
PFPeS	0.2	0.5	1.25	2.5	5	12.5	62.5
PFHxS	0.2	0.5	1.25	2.5	5	12.5	62.5
PFHpS	0.2	0.5	1.25	2.5	5	12.5	62.5
PFOS	0.2	0.5	1.25	2.5	5	12.5	62.5
PFNS	0.2	0.5	1.25	2.5	5	12.5	62.5
PFDS	0.2	0.5	1.25	2.5	5	12.5	62.5
PFDoS	0.2	0.5	1.25	2.5	5	12.5	62.5
Fluorotelomer sulfonic acids							
4:2FTS	0.8	2	5	10	20	50	NA
6:2FTS	0.8	2	5	10	20	50	NA
8:2FTS	0.8	2	5	10	20	50	NA
Perfluorooctane sulfonamides							
PFOSA	0.2	0.5	1.25	2.5	5	12.5	62.5
NMeFOSA	0.2	0.5	1.25	2.5	5	12.5	62.5
NEtFOSA	0.2	0.5	1.25	2.5	5	12.5	62.5
Perfluorooctane sulfonamidoacetic acids							
NMeFOSAA	0.2	0.5	1.25	2.5	5	12.5	62.5
NEtFOSAA	0.2	0.5	1.25	2.5	5	12.5	62.5
Perfluorooctane sulfonamide ethanols							
NMeFOSE	2	5	12.5	25	50	125	625
NEtFOSE	2	5	12.5	25	50	125	625
Per- and polyfluoroether carboxylic acids							
HFPO-DA	0.8	2	5	10	20	50	250
ADONA	0.8	2	5	10	20	50	250
PFMPA	0.4	1	2.5	5	10	25	125
PFMBA	0.4	1	2.5	5	10	25	125
NFDHA	0.4	1	2.5	5	10	25	125
Ether sulfonic acids							
9Cl-PF3ONS	0.8	2	5	10	20	50	250
11Cl-PF3OUdS	0.8	2	5	10	20	50	250
PFEESA	0.4	1	2.5	5	10	25	125

Calibration Solutions (ng/mL) Compound CS1 (LOQ)	CS2 Fluorotelomer carboxylic		CS3	CS4 (CV[1])	CS5	CS6	CS7[2]
acids							
3:3FTCA	1.0	2.5	6.26	12.5	25	62.4	312
5:3FTCA	5.0	12.5	31.3	62.5	125	312	1560
7:3FTCA	5.0	12.5	31.3	62.5	125	312	1560
Extracted Internal Standard (EIS) Analytes							
$^{13}C_4$-PFBA	10	10	10	10	10	10	10
$^{13}C_5$-PFPeA	5	5	5	5	5	5	5
$^{13}C_5$-PFHxA	2.5	2.5	2.5	2.5	2.5	2.5	2.5
$^{13}C_4$-PFHpA	2.5	2.5	2.5	2.5	2.5	2.5	2.5
$^{13}C_8$-PFOA	2.5	2.5	2.5	2.5	2.5	2.5	2.5
$^{13}C_9$-PFNA	1.25	1.25	1.25	1.25	1.25	1.25	1.25
$^{13}C_6$-PFDA	1.25	1.25	1.25	1.25	1.25	1.25	1.25
$^{13}C_7$-PFUnA	1.25	1.25	1.25	1.25	1.25	1.25	1.25
$^{13}C_2$-PFDoA	1.25	1.25	1.25	1.25	1.25	1.25	1.25
$^{13}C_2$-PFTeDA	1.25	1.25	1.25	1.25	1.25	1.25	1.25
$^{13}C_3$-PFBS	2.5	2.5	2.5	2.5	2.5	2.5	2.5
$^{13}C_3$-PFHxS	2.5	2.5	2.5	2.5	2.5	2.5	2.5
$^{13}C_8$-PFOS	2.5	2.5	2.5	2.5	2.5	2.5	2.5
$^{13}C_2$-4:2FTS	5	5	5	5	5	5	5
$^{13}C_2$-6:2FTS	5	5	5	5	5	5	5
$^{13}C_2$-8:2FTS	5	5	5	5	5	5	5
$^{13}C_8$-PFOSA	2.5	2.5	2.5	2.5	2.5	2.5	2.5
D_3-NMeFOSA	2.5	2.5	2.5	2.5	2.5	2.5	2.5
D_5-NEtFOSA	2.5	2.5	2.5	2.5	2.5	2.5	2.5
D_3-NMeFOSAA	5	5	5	5	5	5	5
D_5-NEtFOSAA	5	5	5	5	5	5	5
D_7-NMeFOSE	25	25	25	25	25	25	25
D_9-NEtFOSE	25	25	25	25	25	25	25
$^{13}C_3$-HFPO-DA	10	10	10	10	10	10	10
Non-extracted Internal Standard (NIS) Analytes							
$^{13}C_3$-PFBA	5	5	5	5	5	5	5
$^{13}C_2$-PFHxA	2.5	2.5	2.5	2.5	2.5	2.5	2.5
$^{13}C_4$-PFOA	2.5	2.5	2.5	2.5	2.5	2.5	2.5
$^{13}C_5$-PFNA	1.25	1.25	1.25	1.25	1.25	1.25	1.25
$^{13}C_2$-PFDA	1.25	1.25	1.25	1.25	1.25	1.25	1.25
$^{18}O_2$-PFHxS	2.5	2.5	2.5	2.5	2.5	2.5	2.5
$^{13}C_4$-PFOS	2.5	2.5	2.5	2.5	2.5	2.5	2.5

[1] This calibration point is used as the calibration verification (CV)

[2] A minimum of six contiguous calibrations standards are required for linear models and a minimum of seven calibration standards are required for second-order models.

Attachment 5 -HPLC Method Parameters

HPLC Acquisition Method Report

Stroke A
- **Automatic Stroke Calculation A**: Yes

Compress A
- **Compressibility Mode A**: Compressibility Value Set
- **Compressibility A**: 70 10e-6/bar

Compress B
- **Compressibility Mode B**: Compressibility Value Set
- **Compressibility B**: 90 10e-6/bar

Stop Time
- **Stoptime Mode**: Time set
- **Stoptime**: 10.00 min

Post Time
- **Posttime Mode**: Time set
- **Posttime**: 1.50 min

Injection
- Injection with needle wash
- 3.00 µL

Solvent Composition

	Channel	Name 1	Name 2	Selected	Used	Percent
1	A	Water 5mM ammonium acetate		Ch. 1	Yes	90.00 %
2	B	Methanol		Ch. 1	Yes	10.00 %

Timetable

	Time	A	B	Flow
1	3.50 min	50.00 %	50.00 %	0.400 mL/min
2	8.00 min	10.00 %	90.00 %	0.400 mL/min
3	8.50 min	90.00 %	10.00 %	0.400 mL/min

Name: **Column Comp.** Module: **G1316C**

Left Temperature Control
- **Temperature Control Mode**: Temperature Set
- **Temperature**: 50.0 °C

Enable Analysis Left Temperature
- **Enable Analysis Left Temperature On**: Yes
- **Enable Analysis Left Temperature Value**: 0.8 °C

Right Temperature Control
- **Right temperature Control Mode**: Temperature Set
- **Right temperature**: 50.0 °C

Enable Analysis Right Temperature
- **Enable Analysis Right Temperature On**: Yes
- **Enable Analysis Right Temperature Value**: 0.8 °C

Stop Time
- **Stoptime Mode**: As pump/injector

Post Time
- **Posttime Mode**: Off

Timetable

Valve Position: Position 1 (Port 1 -> 2)

Ready when front door open: Yes

Attachment 6 - Triple Quadrupole Acquisition Method

Acquisition Method Report

Agilent Technologies

Acquisition Method Info

Method Name PFAS1633_ACQ_092922.m

Method Path D:\MassHunter\methods\PFAS1633_ACQ_092922.m

Method Description EPA 1633_Target PFAS Isotope Dilution_Acquisition

Device List

HiP Sampler
Binary Pump
Column Comp.
QQQ

MS QQQ Mass Spectrometer

Ion Source	AJS ESI	**Tune File**	D:\MassHunter\Tune\QQQ\G6460C\atunes.TUNE.XML
Stop Mode	No Limit/As Pump	**Stop Time (min)**	1
Time Filter	On	**Time Filter Width (min)**	0.07
LC->Waste Pre Row	N/A	**LC->Waste Post Row**	N/A

Time Segments

Index	Start Time (min)	Scan Type	Ion Mode	Div Valve	Delta EMV	Store	Cycle Time (ms)	Triggered?	MRM Repeats
1	0	DynamicMRM	ESI+Agilent Jet Stream	To MS	350	Yes	550	Yes	3

Time Segment 1

Scan Segments

Cpd Name	ISTD?	Prec Ion	MS1 Res	Prod Ion	MS2 Res	Primary	Trigger	Frag (V)	CE (V)	Cell Acc (V)	Ret Time (min)	Ret Window	Polarity
11-Cl-PF3OUdS	No	631	Unit/Enh (6490)	451	Unit/Enh (6490)	Yes	No	170	33	4	7.62	3	Negative
1H,1H,2H,2H-perfluoro-1-decanesulfonate (8 2F TS)	No	527	Unit/Enh (6490)	507	Unit/Enh (6490)	Yes	No	170	28	4	7.14	3	Negative
1H,1H,2H,2H-perfluoro-1-decanesulfonate (8 2F TS)	No	527	Unit/Enh (6490)	80.9	Unit/Enh (6490)	Yes	No	170	40	4	7.14	3	Negative
1H,1H,2H,2H-perfluoro-1-hexanesulfonate (4 2F TS)	No	327	Unit/Enh (6490)	307	Unit/Enh (6490)	Yes	No	162	20	4	4.788	3	Negative
1H,1H,2H,2H-perfluoro-1-hexanesulfonate (4 2F TS)	No	327	Unit/Enh (6490)	80.9	Unit/Enh (6490)	Yes	No	162	36	4	4.788	3	Negative
1H,1H,2H,2H-perfluoro-1-octanesulfonate (6 2F TS)	No	427	Unit/Enh (6490)	407	Unit/Enh (6490)	Yes	No	162	24	4	6.168	3	Negative
1H,1H,2H,2H-perfluoro-1-octanesulfonate (6 2F TS)	No	427	Unit/Enh (6490)	79.7	Unit/Enh (6490)	Yes	No	162	48	4	6.168	3	Negative
3:3FTCA	No	241	Unit/Enh (6490)	177	Unit/Enh (6490)	Yes	No	74	4	4	3.4	3	Negative
3-3FTCA	No	241	Unit/Enh (6490)	117	Unit/Enh (6490)	Yes	No	74	44	4	3.4	3	Negative

Report generation date: 18-Oct-2022 09:01:43 AM

Page 1 of 8

Acquisition Method Report

Agilent Technologies

Cpd Name	ISTD?	Prec Ion	MS1 Res	Prod Ion	MS2 Res	Primary	Trigger	Frag (V)	CE (V)	Cell Acc (V)	Ret Time (min)	Ret Window	Polarity
5-3FTCA	No	341	Unit/Enh (6490)	237	Unit/Enh (6490)	Yes	No	84	12	4	5.73	3	Negative
5-3FTCA	No	341	Unit/Enh (6490)	217	Unit/Enh (6490)	Yes	No	84	24	4	5.73	3	Negative
7-3FTCA	No	441	Unit/Enh (6490)	337	Unit/Enh (6490)	Yes	No	76	12	4	6.7	3	Negative
7-3FTCA	No	441	Unit/Enh (6490)	317	Unit/Enh (6490)	Yes	No	76	24	4	6.7	3	Negative
9-Cl-PF3ONS	No	531	Unit/Enh (6490)	351	Unit/Enh (6490)	Yes	No	175	29	4	6.89	3	Negative
ADONA	No	377	Unit/Enh (6490)	251	Unit/Enh (6490)	Yes	No	103	9	4	5.62	3	Negative
ADONA	No	377	Unit/Enh (6490)	85	Unit/Enh (6490)	Yes	No	103	37	4	5.62	3	Negative
d3-NMeFOSA	No	515	Unit/Enh (6490)	219	Unit/Enh (6490)	Yes	No	134	20	4	7.17	3	Negative
d3-N-MeFOSAA	No	572.99	Unit/Enh (6490)	418.8	Unit/Enh (6490)	Yes	No	130	20	4	7.17	3	Negative
d5-NEtFOSA	No	531	Unit/Enh (6490)	219	Unit/Enh (6490)	Yes	No	150	20	4	8.52	3	Negative
d5-NEtFOSA	No	531	Unit/Enh (6490)	169	Unit/Enh (6490)	Yes	No	150	20	4	8.52	3	Negative
d5-N-EtFOSAA	No	589.02	Unit/Enh (6490)	530.9	Unit/Enh (6490)	Yes	No	130	20	4	7.36	3	Negative
d5-N-EtFOSAA	No	589.02	Unit/Enh (6490)	418.8	Unit/Enh (6490)	Yes	No	130	20	4	7.36	3	Negative
d7-NMeFOSE	No	623	Unit/Enh (6490)	310	Unit/Enh (6490)	Yes	No	150	15	4	8.28	3	Negative
d7-NMeFOSE	No	623	Unit/Enh (6490)	59	Unit/Enh (6490)	Yes	No	88	15	4	8.28	3	Negative
d9-NEtFOSE	No	639	Unit/Enh (6490)	59	Unit/Enh (6490)	Yes	No	150	15	4	8.6	3	Negative
HFPO-DA	No	285	Unit/Enh (6490)	169.1	Unit/Enh (6490)	Yes	No	100	20	4	4.95	3	Negative
M2-4-2FTS	No	329	Unit/Enh (6490)	309	Unit/Enh (6490)	Yes	No	156	20	4	4.787	3	Negative
M2-4-2FTS	No	329	Unit/Enh (6490)	81	Unit/Enh (6490)	Yes	No	156	28	4	4.787	3	Negative
M2-6-2FTS	No	429	Unit/Enh (6490)	409	Unit/Enh (6490)	Yes	No	162	24	4	6.01	3	Negative
M2-6-2FTS	No	429	Unit/Enh (6490)	81	Unit/Enh (6490)	Yes	No	162	40	4	6.01	3	Negative
M2-8-2FTS	No	529	Unit/Enh (6490)	509	Unit/Enh (6490)	Yes	No	165	28	4	6.98	3	Negative
M2-8-2FTS	No	529	Unit/Enh (6490)	81	Unit/Enh (6490)	Yes	No	165	40	4	6.98	3	Negative
M2PFTeDA	No	715	Unit/Enh (6490)	670	Unit/Enh (6490)	Yes	No	62	12	4	8.25	3	Negative
M3-HFPO-DA	No	287	Unit/Enh (6490)	169	Unit/Enh (6490)	Yes	No	90	5	4	4.99	3	Negative
M3PFBA	Yes	216	Unit/Enh (6490)	172	Unit/Enh (6490)	Yes	No	90	5	4	1.2	2	Negative
M3PFBS	No	302	Unit/Enh (6490)	98.9	Unit/Enh (6490)	Yes	No	114	32	4	3.94	3	Negative
M3PFBS	No	302	Unit/Enh (6490)	79.9	Unit/Enh (6490)	Yes	No	114	40	4	3.94	3	Negative
M3PFHxS	No	402	Unit/Enh (6490)	98.9	Unit/Enh (6490)	Yes	No	165	40	4	5.55	3	Negative
M3PFHxS	No	402	Unit/Enh (6490)	80	Unit/Enh (6490)	Yes	No	165	48	4	5.55	3	Negative
M4PFHpA	No	367	Unit/Enh (6490)	322	Unit/Enh (6490)	Yes	No	124	8	4	5.601	3	Negative
M5PFHxA	No	318	Unit/Enh (6490)	273	Unit/Enh (6490)	Yes	No	70	4	4	5.47	3	Negative
M5PFHxA	No	318	Unit/Enh (6490)	120	Unit/Enh (6490)	Yes	No	70	4	4	5.47	3	Negative
M6PFDA	No	519	Unit/Enh (6490)	473.9	Unit/Enh (6490)	Yes	No	59	8	4	6.99	3	Negative
M7PFUdA	No	570	Unit/Enh (6490)	525	Unit/Enh (6490)	Yes	No	64	8	4	7.38	3	Negative
MPFDA	Yes	514.98	Unit/Enh (6490)	469.8	Unit/Enh (6490)	Yes	No	94	5	4	6.972	2	Negative
MPFHxA	Yes	314.99	Unit/Enh (6490)	269.8	Unit/Enh (6490)	Yes	No	86	4	4	4.705	2	Negative
MPFHxA	Yes	314.99	Unit/Enh (6490)	120	Unit/Enh (6490)	Yes	No	86	4	4	4.705	2	Negative
MPFHxS	Yes	403	Unit/Enh (6490)	103	Unit/Enh (6490)	Yes	No	110	37	4	5.63	2	Negative
MPFHxS	Yes	403	Unit/Enh (6490)	84	Unit/Enh (6490)	Yes	No	110	40	4	5.63	2	Negative
MPFNA	Yes	468	Unit/Enh (6490)	423	Unit/Enh (6490)	Yes	No	66	4	4	6.541	2	Negative
MPFOA	Yes	417	Unit/Enh (6490)	372	Unit/Enh (6490)	Yes	No	84	4	4	6.03	2	Negative
MPFOS	Yes	502.96	Unit/Enh (6490)	99	Unit/Enh (6490)	Yes	No	148	48	4	6.57	3	Negative

Acquisition Method Report

Agilent Technologies

Cpd Name	ISTD?	Prec Ion	MS1 Res	Prod Ion	MS2 Res	Primary	Trigger	Frag (V)	CE (V)	Cell Acc (V)	Ret Time (min)	Ret Window	Polarity
MPFOS	Yes	502.96	Unit/Enh (6490)	80	Unit/Enh (6490)	Yes	No	148	54	4	6.57	3	Negative
NEtFOSA	No	526	Unit/Enh (6490)	219	Unit/Enh (6490)	Yes	No	120	20	4	8.528	3	Negative
NEtFOSA	No	526	Unit/Enh (6490)	169	Unit/Enh (6490)	Yes	No	120	20	4	8.528	3	Negative
N-EtFOSAA	No	584	Unit/Enh (6490)	525.9	Unit/Enh (6490)	Yes	No	130	20	4	7.521	3	Negative
N-EtFOSAA	No	584	Unit/Enh (6490)	418.8	Unit/Enh (6490)	Yes	No	130	20	4	7.521	3	Negative
NEtFOSE	No	630	Unit/Enh (6490)	59	Unit/Enh (6490)	Yes	No	120	20	4	8.301	3	Negative
NFDHA	No	295	Unit/Enh (6490)	201.1	Unit/Enh (6490)	Yes	No	92	2	4	4.641	3	Negative
NFDHA	No	295	Unit/Enh (6490)	84.9	Unit/Enh (6490)	Yes	No	92	34	4	4.641	3	Negative
NMeFOSA	No	512	Unit/Enh (6490)	219	Unit/Enh (6490)	Yes	No	120	20	4	8.298	3	Negative
NMeFOSA	No	512	Unit/Enh (6490)	169	Unit/Enh (6490)	Yes	No	120	20	4	8.298	3	Negative
N-MeFOSAA	No	570	Unit/Enh (6490)	511.9	Unit/Enh (6490)	Yes	No	150	20	4	7.335	3	Negative
N-MeFOSAA	No	570	Unit/Enh (6490)	418.9	Unit/Enh (6490)	Yes	No	150	20	4	7.335	3	Negative
NMeFOSE	No	616	Unit/Enh (6490)	59	Unit/Enh (6490)	Yes	No	120	20	4	8.301	3	Negative
Perfluoro-1-[13C8]octanesulfonamide (M8FOSA)	No	506	Unit/Enh (6490)	78	Unit/Enh (6490)	Yes	No	162	48	4	7.59	3	Negative
Perfluoro-1-[13C8]octanesulfonic acid (M8PFOS)	No	507	Unit/Enh (6490)	98.9	Unit/Enh (6490)	Yes	No	174	48	4	6.59	3	Negative
Perfluoro-1-[13C8]octanesulfonic acid (M8PFOS)	No	507	Unit/Enh (6490)	80	Unit/Enh (6490)	Yes	No	174	54	4	6.59	3	Negative
Perfluoro-1-decanesulfonate (L-PFDS)	No	598.9	Unit/Enh (6490)	98.9	Unit/Enh (6490)	Yes	No	156	50	4	7.546	3	Negative
Perfluoro-1-decanesulfonate (L-PFDS)	No	598.9	Unit/Enh (6490)	98.9	Unit/Enh (6490)	Yes	No	100	60	4	7.546	3	Negative
Perfluoro-1-heptanesulfonate (L-PFHpS)	No	448.9	Unit/Enh (6490)	98.9	Unit/Enh (6490)	Yes	No	162	48	4	6.252	3	Negative
Perfluoro-1-heptanesulfonate (L-PFHpS)	No	448.9	Unit/Enh (6490)	80	Unit/Enh (6490)	Yes	No	162	48	4	6.252	3	Negative
Perfluoro-1-octanesulfonamide (FOSA)	No	497.9	Unit/Enh (6490)	478	Unit/Enh (6490)	Yes	No	156	100	4	7.651	3	Negative
Perfluoro-1-octanesulfonamide (FOSA)	No	497.9	Unit/Enh (6490)	78	Unit/Enh (6490)	Yes	No	156	40	4	7.651	3	Negative
Perfluoro-1-pentanesulfonate (L-PFPeS)	No	348.9	Unit/Enh (6490)	98.9	Unit/Enh (6490)	Yes	No	150	36	4	5.042	3	Negative
Perfluoro-1-pentanesulfonate (L-PFPeS)	No	348.9	Unit/Enh (6490)	79.9	Unit/Enh (6490)	Yes	No	150	40	4	5.042	3	Negative

Acquisition Method Report

Agilent Technologies

Cpd Name	ISTD?	Prec Ion	MS1 Res	Prod Ion	MS2 Res	Primary	Trigger	Frag (V)	CE (V)	Cell Acc (V)	Ret Time (min)	Ret Window	Polarity
Perfluorobutanesulfonic acid (PFBS)	No	298.9	Unit/Enh (6490)	98.9	Unit/Enh (6490)	Yes	No	150	32	4	4.042	3	Negative
Perfluorobutanesulfonic acid (PFBS)	No	298.9	Unit/Enh (6490)	79.9	Unit/Enh (6490)	Yes	No	150	36	4	4.042	3	Negative
Perfluorodecanoic acid (PFDA)	No	513	Unit/Enh (6490)	468.8	Unit/Enh (6490)	Yes	No	90	8	4	7.158	3	Negative
Perfluorodecanoic acid (PFDA)	No	513	Unit/Enh (6490)	268.8	Unit/Enh (6490)	Yes	No	90	16	4	7.158	3	Negative
Perfluorododecanesulfonic acid (PFDoS)	No	699	Unit/Enh (6490)	99	Unit/Enh (6490)	Yes	No	100	60	4	7.984	3	Negative
Perfluorododecanesulfonic acid (PFDoS)	No	699	Unit/Enh (6490)	80	Unit/Enh (6490)	Yes	No	156	50	4	7.984	3	Negative
Perfluorododecanoic acid (PFDoA)	No	613	Unit/Enh (6490)	568.8	Unit/Enh (6490)	Yes	No	90	12	4	7.876	3	Negative
Perfluorododecanoic acid (PFDoA)	No	613	Unit/Enh (6490)	168.7	Unit/Enh (6490)	Yes	No	90	28	4	7.876	3	Negative
Perfluoroheptanoic acid (PFHpA)	No	363	Unit/Enh (6490)	318.8	Unit/Enh (6490)	Yes	No	90	8	4	5.601	3	Negative
Perfluoroheptanoic acid (PFHpA)	No	363	Unit/Enh (6490)	168.9	Unit/Enh (6490)	Yes	No	90	16	4	5.601	3	Negative
Perfluorohexanesulfonic acid (PFHxS)	No	398.9	Unit/Enh (6490)	98.9	Unit/Enh (6490)	Yes	No	150	40	4	5.685	3	Negative
Perfluorohexanesulfonic acid (PFHxS)	No	398.9	Unit/Enh (6490)	79.9	Unit/Enh (6490)	Yes	No	150	44	4	5.685	3	Negative
Perfluorohexanoic acid (PFHxA)	No	313	Unit/Enh (6490)	268.9	Unit/Enh (6490)	Yes	No	70	4	4	4.856	3	Negative
Perfluorohexanoic acid (PFHxA)	No	313	Unit/Enh (6490)	119	Unit/Enh (6490)	Yes	No	70	20	4	4.856	3	Negative
Perfluoro-n-[1,2-13C2]dodecanoic acid (MPFDoA)	No	615	Unit/Enh (6490)	570	Unit/Enh (6490)	Yes	No	53	8	4	7.71	3	Negative
Perfluoro-n-[13C4]butanoic acid (MPFBA)	No	217	Unit/Enh (6490)	172	Unit/Enh (6490)	Yes	No	59	4	4	1.22	3	Negative
Perfluoro-n-[13C5]pentanoic acid (M5PFPeA)	No	268	Unit/Enh (6490)	223	Unit/Enh (6490)	Yes	No	62	4	4	3.44	3	Negative
Perfluoro-n-[13C8]octanoic acid (M8PFOA)	No	421	Unit/Enh (6490)	376	Unit/Enh (6490)	Yes	No	59	4	4	6.05	3	Negative
Perfluoro-n-[13C8]octanoic acid (M8PFOA)	No	421	Unit/Enh (6490)	172	Unit/Enh (6490)	Yes	No	59	16	4	6.05	3	Negative

Acquisition Method Report

Agilent Technologies

Cpd Name	ISTD?	Prec Ion	MS1 Res	Prod Ion	MS2 Res	Primary	Trigger	Frag (V)	CE (V)	Cell Acc (V)	Ret Time (min)	Ret Window	Polarity
Perfluoro-n-[13C9]nonanoic acid (M9PFNA)	No	472	Unit/Enh (6490)	427	Unit/Enh (6490)	Yes	No	59	8	4	6.56	3	Negative
Perfluoro-n-[13C9]nonanoic acid (M9PFNA)	No	472	Unit/Enh (6490)	223	Unit/Enh (6490)	Yes	No	59	16	4	6.56	3	Negative
Perfluoro-n-butanoic acid (PFBA)	No	213	Unit/Enh (6490)	169.9	Unit/Enh (6490)	Yes	No	70	4	4	1.246	3	Negative
Perfluorononanesulfonate (L-PFNS)	No	548.9	Unit/Enh (6490)	98.9	Unit/Enh (6490)	Yes	No	159	48	4	7.174	3	Negative
Perfluorononanesulfonate (L-PFNS)	No	548.9	Unit/Enh (6490)	79.9	Unit/Enh (6490)	Yes	No	159	48	4	7.174	3	Negative
Perfluorononanoic acid (PFNA)	No	463	Unit/Enh (6490)	418.8	Unit/Enh (6490)	Yes	No	90	8	4	6.718	3	Negative
Perfluorononanoic acid (PFNA)	No	463	Unit/Enh (6490)	218.8	Unit/Enh (6490)	Yes	No	90	16	4	6.718	3	Negative
Perfluoro-n-pentanoic acid (PFPeA)	No	263	Unit/Enh (6490)	219	Unit/Enh (6490)	Yes	No	62	4	4	3.526	3	Negative
Perfluorooctanesulfonic acid (PFOS)	No	498.9	Unit/Enh (6490)	98.9	Unit/Enh (6490)	Yes	No	150	44	4	6.743	3	Negative
Perfluorooctanesulfonic acid (PFOS)	No	498.9	Unit/Enh (6490)	79.9	Unit/Enh (6490)	Yes	No	150	84	4	6.743	3	Negative
Perfluorooctanoic acid (PFOA)	No	413	Unit/Enh (6490)	368.8	Unit/Enh (6490)	Yes	No	90	8	4	6.202	3	Negative
Perfluorooctanoic acid (PFOA)	No	413	Unit/Enh (6490)	168.9	Unit/Enh (6490)	Yes	No	90	16	4	6.202	3	Negative
Perfluorotetradecanoic acid (PFTA)	No	713	Unit/Enh (6490)	669	Unit/Enh (6490)	Yes	No	110	12	4	8.414	3	Negative
Perfluorotetradecanoic acid (PFTA)	No	713	Unit/Enh (6490)	168.8	Unit/Enh (6490)	Yes	No	110	28	4	8.414	3	Negative
Perfluorotridecanoic acid (PFTrDA)	No	663	Unit/Enh (6490)	618.8	Unit/Enh (6490)	Yes	No	90	12	4	8.164	3	Negative
Perfluoroundecanoic acid (PFUnA)	No	563	Unit/Enh (6490)	519	Unit/Enh (6490)	Yes	No	90	8	4	7.538	3	Negative
Perfluoroundecanoic acid (PFUnA)	No	563	Unit/Enh (6490)	169	Unit/Enh (6490)	Yes	No	90	24	4	7.538	3	Negative
PFEESA	No	315	Unit/Enh (6490)	135	Unit/Enh (6490)	Yes	No	112	26	4	4.464	3	Negative
PFEESA	No	315	Unit/Enh (6490)	83	Unit/Enh (6490)	Yes	No	112	14	4	4.464	3	Negative
PFMBA	No	279	Unit/Enh (6490)	85	Unit/Enh (6490)	Yes	No	75	18	4	4.011	3	Negative
PFMPA	No	229	Unit/Enh (6490)	85	Unit/Enh (6490)	Yes	No	59	6	4	2.15	3	Negative

Scan Parameters

Data Stg	Threshold
Centroid	0

Report generation date: 18-Oct-2022 09:01:44 AM

Page 5 of 8

Acquisition Method Report

Agilent Technologies

Source Parameters

Parameter	Value (+)	Value (-)
Gas Temp (°C)	230	230
Gas Flow (l/min)	5	5
Nebulizer (psi)	15	15
SheathGasHeater	350	350
SheathGasFlow	12	12
Capillary (V)	3500	2500
VCharging	500	0

Chromatograms

Chrom Type	Label	Offset	Y-Range
TIC	TIC	0	10000000

Instrument Curves

Actual

Name: HiP Sampler **Module: G4226A**

Auxiliary	
Draw Speed	100.0 µL/min
Eject Speed	400.0 µL/min
Draw Position Offset	1.5 mm
Wait Time After Drawing	1.2 s
Sample Flush Out Factor	5.0
Vial/Well bottom sensing	Yes
Injection	
Injection Mode	Injection with needle wash
Injection Volume	3.00 µL
Needle Wash	
Needle Wash Location	Flush Port
Wash Time	10.0 s
High throughput	
Automatic Delay Volume Reduction	No
Overlapped Injection	
Enable Overlapped Injection	No
Valve Switching	
Valve Movements	0
Valve Switch Time 1	
Switch Time 1 Enabled	No
Valve Switch Time 2	
Switch Time 2 Enabled	No
Valve Switch Time 3	
Switch Time 3 Enabled	No
Valve Switch Time 4	
Switch Time 4 Enabled	No
Stop Time	
Stoptime Mode	As pump/No limit
Post Time	
Posttime Mode	Off

Name: Binary Pump **Module: G4220A**

Flow	0.400 mL/min
Use Solvent Types	No
Stroke Mode	Synchronized
Low Pressure Limit	0.00 bar
High Pressure Limit	600.00 bar
Max. Flow Ramp Up	100.000 mL/min²
Max. Flow Ramp Down	100.000 mL/min²
Expected Mixer	No check

Report generation date: 18-Oct-2022 09:01:44 AM

Page 6 of 8

ATTACHMENT F

ELAP Certifications

LANGAN

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER

Expires 12:01 AM April 01, 2026
Issued April 01, 2025
Revised July 09, 2025

CERTIFICATE OF APPROVAL FOR LABORATORY SERVICE

Issued in accordance with and pursuant to section 502 Public Health Law of New York State

MS. CATHERINE L. MOSHER
YORK ANALYTICAL LABORATORIES INC
120 RESEARCH DRIVE
STRATFORD, CT 06615

NY Lab Id No: 10854

is hereby APPROVED as an Environmental Laboratory in conformance with the National Environmental Laboratory Accreditation Conference Standards (2016) for the category ENVIRONMENTAL ANALYSES NON POTABLE WATER
All approved analytes are listed below:

Acrylates

Acrolein (Propenal)	EPA 8260D
	EPA 8260C
	EPA 624.1
Acrylonitrile	EPA 8260D
	EPA 8260C
	EPA 624.1
Methyl methacrylate	EPA 8260D
	EPA 8260C

Amines

1,2-Diphenylhydrazine	EPA 8270D
	EPA 8270E
2-Nitroaniline	EPA 8270D
	EPA 8270E
3-Nitroaniline	EPA 8270D
	EPA 8270E
4-Chloroaniline	EPA 8270D
	EPA 8270E
4-Nitroaniline	EPA 8270D
	EPA 8270E
Aniline	EPA 625.1
	EPA 8270D
	EPA 8270E
Carbazole	EPA 625.1
	EPA 8270D
	EPA 8270E
Diphenylamine	EPA 8270D
	EPA 8270E

Serial No.: 71155

Property of the New York State Department of Health. Certificates are valid only at the address shown and must be conspicuously posted by the laboratory. Continued accreditation depends on the laboratory's successful ongoing participation in the Program. Consumers may verify a laboratory's accreditation status online at https://apps.health.ny.gov/pubdoh/applinks/wc/elappublicweb/, by phone (518) 485-5570 or by email to elap@health.ny.gov.

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER

Expires 12:01 AM April 01, 2026
Issued April 01, 2025
Revised July 09, 2025

CERTIFICATE OF APPROVAL FOR LABORATORY SERVICE

Issued in accordance with and pursuant to section 502 Public Health Law of New York State

MS. CATHERINE L. MOSHER
YORK ANALYTICAL LABORATORIES INC
120 RESEARCH DRIVE
STRATFORD, CT 06615

NY Lab Id No: 10854

is hereby APPROVED as an Environmental Laboratory in conformance with the National Environmental Laboratory Accreditation Conference Standards (2016) for the category ENVIRONMENTAL ANALYSES NON POTABLE WATER
All approved analytes are listed below:

Amines

Pyridine	EPA 625.1
	EPA 8270D
	EPA 8270E

Benzidines

3,3'-Dichlorobenzidine	EPA 625.1
	EPA 8270D
	EPA 8270E
Benzidine	EPA 625.1
	EPA 8270D
	EPA 8270E

Chlorinated Hydrocarbon Pesticides

4,4'-DDD	EPA 8081B
	EPA 608.3
4,4'-DDE	EPA 8081B
	EPA 608.3
4,4'-DDT	EPA 8081B
	EPA 608.3
Aldrin	EPA 8081B
	EPA 608.3
alpha-BHC	EPA 8081B
	EPA 608.3
alpha-Chlordane	EPA 8081B
beta-BHC	EPA 8081B
	EPA 608.3
Chlordane Total	EPA 8081B
	EPA 608.3

Serial No.: 71155

Property of the New York State Department of Health. Certificates are valid only at the address shown and must be conspicuously posted by the laboratory. Continued accreditation depends on the laboratory's successful ongoing participation in the Program. Consumers may verify a laboratory's accreditation status online at https://apps.health.ny.gov/pubdoh/applinks/wc/elappublicweb/, by phone (518) 485-5570 or by email to elap@health.ny.gov.

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER

Expires 12:01 AM April 01, 2026
Issued April 01, 2025
Revised July 09, 2025

CERTIFICATE OF APPROVAL FOR LABORATORY SERVICE

Issued in accordance with and pursuant to section 502 Public Health Law of New York State

MS. CATHERINE L. MOSHER
YORK ANALYTICAL LABORATORIES INC
120 RESEARCH DRIVE
STRATFORD, CT 06615

NY Lab Id No: 10854

is hereby APPROVED as an Environmental Laboratory in conformance with the National Environmental Laboratory Accreditation Conference Standards (2016) for the category ENVIRONMENTAL ANALYSES NON POTABLE WATER
All approved analytes are listed below:

Chlorinated Hydrocarbon Pesticides

delta-BHC	EPA 8081B
	EPA 608.3
Dieldrin	EPA 8081B
	EPA 608.3
Endosulfan I	EPA 8081B
	EPA 608.3
Endosulfan II	EPA 8081B
	EPA 608.3
Endosulfan sulfate	EPA 8081B
	EPA 608.3
Endrin	EPA 8081B
	EPA 608.3
Endrin aldehyde	EPA 8081B
	EPA 608.3
Endrin Ketone	EPA 8081B
gamma-Chlordane	EPA 8081B
Heptachlor	EPA 8081B
	EPA 608.3
Heptachlor epoxide	EPA 8081B
	EPA 608.3
Lindane	EPA 8081B
	EPA 608.3
Methoxychlor	EPA 8081B
	EPA 608.3
Mirex	EPA 8081B
Toxaphene	EPA 8081B
	EPA 608.3

Serial No.: 71155

Property of the New York State Department of Health. Certificates are valid only at the address shown and must be conspicuously posted by the laboratory. Continued accreditation depends on the laboratory's successful ongoing participation in the Program. Consumers may verify a laboratory's accreditation status online at https://apps.health.ny.gov/pubdoh/applinks/wc/elappublicweb/, by phone (518) 485-5570 or by email to elap@health.ny.gov.

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER

Expires 12:01 AM April 01, 2026
Issued April 01, 2025
Revised July 09, 2025

CERTIFICATE OF APPROVAL FOR LABORATORY SERVICE

Issued in accordance with and pursuant to section 502 Public Health Law of New York State

MS. CATHERINE L. MOSHER
YORK ANALYTICAL LABORATORIES INC
120 RESEARCH DRIVE
STRATFORD, CT 06615

NY Lab Id No: 10854

is hereby APPROVED as an Environmental Laboratory in conformance with the National Environmental Laboratory Accreditation Conference Standards (2016) for the category ENVIRONMENTAL ANALYSES NON POTABLE WATER
All approved analytes are listed below:

Chlorinated Hydrocarbons

1,2,3-Trichlorobenzene	EPA 8260D
	EPA 8260C
1,2,4,5-Tetrachlorobenzene	EPA 8270D
	EPA 8270E
1,2,4-Trichlorobenzene	EPA 625.1
	EPA 8270D
	EPA 8270E
2-Chloronaphthalene	EPA 625.1
	EPA 8270D
	EPA 8270E
Hexachlorobenzene	EPA 8270D
	EPA 8270E
Hexachlorobutadiene	EPA 625.1
	EPA 8270D
	EPA 8270E
Hexachlorocyclopentadiene	EPA 625.1
	EPA 8270D
	EPA 8270E
Hexachloroethane	EPA 625.1
	EPA 8270D
	EPA 8270E
Pentachlorobenzene	EPA 8270D
	EPA 8270E

Chlorophenoxy Acid Pesticides

2,4,5-T	EPA 8151A
2,4,5-TP (Silvex)	EPA 8151A
	SM 6640B-2006

Serial No.: 71155

Property of the New York State Department of Health. Certificates are valid only at the address shown and must be conspicuously posted by the laboratory. Continued accreditation depends on the laboratory's successful ongoing participation in the Program. Consumers may verify a laboratory's accreditation status online at https://apps.health.ny.gov/pubdoh/applinks/wc/elappublicweb/, by phone (518) 485-5570 or by email to elap@health.ny.gov.

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER

Expires 12:01 AM April 01, 2026
Issued April 01, 2025
Revised July 09, 2025

CERTIFICATE OF APPROVAL FOR LABORATORY SERVICE

Issued in accordance with and pursuant to section 502 Public Health Law of New York State

MS. CATHERINE L. MOSHER
YORK ANALYTICAL LABORATORIES INC
120 RESEARCH DRIVE
STRATFORD, CT 06615

NY Lab Id No: 10854

is hereby APPROVED as an Environmental Laboratory in conformance with the National Environmental Laboratory Accreditation Conference Standards (2016) for the category ENVIRONMENTAL ANALYSES NON POTABLE WATER
All approved analytes are listed below:

Chlorophenoxy Acid Pesticides

2,4-D	EPA 8151A
Dicamba	EPA 8151A

Demand

Biochemical Oxygen Demand	SM 5210B-2016
Carbonaceous BOD	SM 5210B-2016
Chemical Oxygen Demand	SM 5220D-2011

Fuel Oxygenates

Di-isopropyl ether	EPA 8260D
	EPA 8260C
Ethanol	EPA 8260D
	EPA 8260C
Methyl tert-butyl ether	EPA 8260D
	EPA 8260C
tert-amyl alcohol	EPA 8260D
	EPA 8260C
tert-amyl methyl ether (TAME)	EPA 8260D
	EPA 8260C
tert-butyl alcohol	EPA 8260D
	EPA 8260C
tert-butyl ethyl ether (ETBE)	EPA 8260D
	EPA 8260C

Haloethers

2,2'-Oxybis(1-chloropropane)	EPA 625.1
	EPA 8270D
	EPA 8270E
4-Bromophenylphenyl ether	EPA 625.1

Serial No.: 71155

Property of the New York State Department of Health. Certificates are valid only at the address shown and must be conspicuously posted by the laboratory. Continued accreditation depends on the laboratory's successful ongoing participation in the Program. Consumers may verify a laboratory's accreditation status online at https://apps.health.ny.gov/pubdoh/applinks/wc/elappublicweb/, by phone (518) 485-5570 or by email to elap@health.ny.gov.

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER

Expires 12:01 AM April 01, 2026
Issued April 01, 2025
Revised July 09, 2025

CERTIFICATE OF APPROVAL FOR LABORATORY SERVICE

Issued in accordance with and pursuant to section 502 Public Health Law of New York State

MS. CATHERINE L. MOSHER
YORK ANALYTICAL LABORATORIES INC
120 RESEARCH DRIVE
STRATFORD, CT 06615

NY Lab Id No: 10854

is hereby APPROVED as an Environmental Laboratory in conformance with the National Environmental Laboratory Accreditation Conference Standards (2016) for the category ENVIRONMENTAL ANALYSES NON POTABLE WATER
All approved analytes are listed below:

Haloethers

4-Bromophenylphenyl ether	EPA 8270D
	EPA 8270E
4-Chlorophenylphenyl ether	EPA 625.1
	EPA 8270D
	EPA 8270E
Bis(2-chloroethoxy)methane	EPA 625.1
	EPA 8270D
	EPA 8270E
Bis(2-chloroethyl)ether	EPA 625.1
	EPA 8270D
	EPA 8270E

Low Level Halocarbons

1,2,3-Trichloropropane, Low Level	EPA 8011
1,2-Dibromo-3-chloropropane, Low Le	EPA 8011
1,2-Dibromoethane, Low Level	EPA 8011

Low Level Polynuclear Aromatics

Acenaphthene Low Level	EPA 8270D
	EPA 8270E
	EPA 8270E SIM
Acenaphthylene Low Level	EPA 8270D
	EPA 8270E
	EPA 8270E SIM
Anthracene Low Level	EPA 8270D
	EPA 8270E
	EPA 8270E SIM
Benzo(a)anthracene Low Level	EPA 8270D

Serial No.: 71155

Property of the New York State Department of Health. Certificates are valid only at the address shown and must be conspicuously posted by the laboratory. Continued accreditation depends on the laboratory's successful ongoing participation in the Program. Consumers may verify a laboratory's accreditation status online at https://apps.health.ny.gov/pubdoh/applinks/wc/elappublicweb/, by phone (518) 485-5570 or by email to elap@health.ny.gov.

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER

Expires 12:01 AM April 01, 2026
Issued April 01, 2025
Revised July 09, 2025

CERTIFICATE OF APPROVAL FOR LABORATORY SERVICE

Issued in accordance with and pursuant to section 502 Public Health Law of New York State

MS. CATHERINE L. MOSHER
YORK ANALYTICAL LABORATORIES INC
120 RESEARCH DRIVE
STRATFORD, CT 06615

NY Lab Id No: 10854

is hereby APPROVED as an Environmental Laboratory in conformance with the National Environmental Laboratory Accreditation Conference Standards (2016) for the category ENVIRONMENTAL ANALYSES NON POTABLE WATER
All approved analytes are listed below:

Low Level Polynuclear Aromatics

Benzo(a)anthracene Low Level	EPA 8270E
	EPA 8270E SIM
Benzo(a)pyrene Low Level	EPA 8270D
	EPA 8270E
	EPA 8270E SIM
Benzo(b)fluoranthene Low Level	EPA 8270D
	EPA 8270E
	EPA 8270E SIM
Benzo(g,h,i)perylene Low Level	EPA 8270D
	EPA 8270E
	EPA 8270E SIM
Benzo(k)fluoranthene Low Level	EPA 8270D
	EPA 8270E
	EPA 8270E SIM
Chrysene Low Level	EPA 8270D
	EPA 8270E
	EPA 8270E SIM
Dibenzo(a,h)anthracene Low Level	EPA 8270D
	EPA 8270E
	EPA 8270E SIM
Fluoranthene Low Level	EPA 8270D
	EPA 8270E
	EPA 8270E SIM
Fluorene Low Level	EPA 8270D
	EPA 8270E
	EPA 8270E SIM
Indeno(1,2,3-cd)pyrene Low Level	EPA 8270D

Serial No.: 71155

Property of the New York State Department of Health. Certificates are valid only at the address shown and must be conspicuously posted by the laboratory. Continued accreditation depends on the laboratory's successful ongoing participation in the Program. Consumers may verify a laboratory's accreditation status online at https://apps.health.ny.gov/pubdoh/applinks/wc/elappublicweb/, by phone (518) 485-5570 or by email to elap@health.ny.gov.

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER

Expires 12:01 AM April 01, 2026
Issued April 01, 2025
Revised July 09, 2025

CERTIFICATE OF APPROVAL FOR LABORATORY SERVICE

Issued in accordance with and pursuant to section 502 Public Health Law of New York State

MS. CATHERINE L. MOSHER
YORK ANALYTICAL LABORATORIES INC
120 RESEARCH DRIVE
STRATFORD, CT 06615

NY Lab Id No: 10854

is hereby APPROVED as an Environmental Laboratory in conformance with the National Environmental Laboratory Accreditation Conference Standards (2016) for the category ENVIRONMENTAL ANALYSES NON POTABLE WATER
All approved analytes are listed below:

Low Level Polynuclear Aromatics

Indeno(1,2,3-cd)pyrene Low Level	EPA 8270E
	EPA 8270E SIM
Naphthalene Low Level	EPA 8270D
	EPA 8270E
	EPA 8270E SIM
Phenanthrene Low Level	EPA 8270D
	EPA 8270E
	EPA 8270E SIM
Pyrene Low Level	EPA 8270D
	EPA 8270E
	EPA 8270E SIM

Metals I

Barium, Total	EPA 200.7, Rev. 4.4 (1994)
	EPA 6010C
	EPA 6010D
Cadmium, Total	EPA 200.7, Rev. 4.4 (1994)
	EPA 6010C
	EPA 6010D
	EPA 6020A
	EPA 6020B
	EPA 200.8, Rev. 5.4 (1994)
Calcium, Total	EPA 200.7, Rev. 4.4 (1994)
	EPA 6010C
	EPA 6010D
Chromium, Total	EPA 200.7, Rev. 4.4 (1994)
	EPA 6010C
	EPA 6010D

Serial No.: 71155

Property of the New York State Department of Health. Certificates are valid only at the address shown and must be conspicuously posted by the laboratory. Continued accreditation depends on the laboratory's successful ongoing participation in the Program. Consumers may verify a laboratory's accreditation status online at https://apps.health.ny.gov/pubdoh/applinks/wc/elappublicweb/, by phone (518) 485-5570 or by email to elap@health.ny.gov.

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER

Expires 12:01 AM April 01, 2026
Issued April 01, 2025
Revised July 09, 2025

CERTIFICATE OF APPROVAL FOR LABORATORY SERVICE

Issued in accordance with and pursuant to section 502 Public Health Law of New York State

MS. CATHERINE L. MOSHER
YORK ANALYTICAL LABORATORIES INC
120 RESEARCH DRIVE
STRATFORD, CT 06615

NY Lab Id No: 10854

is hereby APPROVED as an Environmental Laboratory in conformance with the National Environmental Laboratory Accreditation Conference Standards (2016) for the category ENVIRONMENTAL ANALYSES NON POTABLE WATER
All approved analytes are listed below:

Metals I

Chromium, Total	EPA 6020A
	EPA 6020B
	EPA 200.8, Rev. 5.4 (1994)
Copper, Total	EPA 200.7, Rev. 4.4 (1994)
	EPA 6010C
	EPA 6010D
	EPA 6020A
	EPA 6020B
	EPA 200.8, Rev. 5.4 (1994)
Iron, Total	EPA 200.7, Rev. 4.4 (1994)
	EPA 6010C
	EPA 6010D
	EPA 6020A
	EPA 6020B
	EPA 200.8, Rev. 5.4 (1994)
Lead, Total	EPA 200.7, Rev. 4.4 (1994)
	EPA 6010C
	EPA 6010D
	EPA 6020A
	EPA 6020B
	EPA 200.8, Rev. 5.4 (1994)
Magnesium, Total	EPA 200.7, Rev. 4.4 (1994)
	EPA 6010C
	EPA 6010D
Manganese, Total	EPA 200.7, Rev. 4.4 (1994)
	EPA 6010C
	EPA 6010D

Serial No.: 71155

Property of the New York State Department of Health. Certificates are valid only at the address shown and must be conspicuously posted by the laboratory. Continued accreditation depends on the laboratory's successful ongoing participation in the Program. Consumers may verify a laboratory's accreditation status online at https://apps.health.ny.gov/pubdoh/applinks/wc/elappublicweb/, by phone (518) 485-5570 or by email to elap@health.ny.gov.

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER

Expires 12:01 AM April 01, 2026
Issued April 01, 2025
Revised July 09, 2025

CERTIFICATE OF APPROVAL FOR LABORATORY SERVICE

Issued in accordance with and pursuant to section 502 Public Health Law of New York State

MS. CATHERINE L. MOSHER
YORK ANALYTICAL LABORATORIES INC
120 RESEARCH DRIVE
STRATFORD, CT 06615

NY Lab Id No: 10854

is hereby APPROVED as an Environmental Laboratory in conformance with the National Environmental Laboratory Accreditation Conference Standards (2016) for the category ENVIRONMENTAL ANALYSES NON POTABLE WATER
All approved analytes are listed below:

Metals I

Manganese, Total	EPA 6020A
	EPA 6020B
	EPA 200.8, Rev. 5.4 (1994)
Nickel, Total	EPA 200.7, Rev. 4.4 (1994)
	EPA 6010C
	EPA 6010D
	EPA 6020A
	EPA 6020B
	EPA 200.8, Rev. 5.4 (1994)
Potassium, Total	EPA 200.7, Rev. 4.4 (1994)
	EPA 6010C
	EPA 6010D
Silver, Total	EPA 200.7, Rev. 4.4 (1994)
	EPA 6010C
	EPA 6010D
	EPA 6020A
	EPA 6020B
	EPA 200.8, Rev. 5.4 (1994)
Sodium, Total	EPA 200.7, Rev. 4.4 (1994)
	EPA 6010C
	EPA 6010D

Metals II

Aluminum, Total	EPA 200.7, Rev. 4.4 (1994)
	EPA 6010C
	EPA 6010D
	EPA 6020A
	EPA 6020B

Serial No.: 71155

Property of the New York State Department of Health. Certificates are valid only at the address shown and must be conspicuously posted by the laboratory. Continued accreditation depends on the laboratory's successful ongoing participation in the Program. Consumers may verify a laboratory's accreditation status online at https://apps.health.ny.gov/pubdoh/applinks/wc/elappublicweb/, by phone (518) 485-5570 or by email to elap@health.ny.gov.

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER

Expires 12:01 AM April 01, 2026
Issued April 01, 2025
Revised July 09, 2025

CERTIFICATE OF APPROVAL FOR LABORATORY SERVICE

Issued in accordance with and pursuant to section 502 Public Health Law of New York State

MS. CATHERINE L. MOSHER
YORK ANALYTICAL LABORATORIES INC
120 RESEARCH DRIVE
STRATFORD, CT 06615

NY Lab Id No: 10854

is hereby APPROVED as an Environmental Laboratory in conformance with the National Environmental Laboratory Accreditation Conference Standards (2016) for the category ENVIRONMENTAL ANALYSES NON POTABLE WATER
All approved analytes are listed below:

Metals II

Aluminum, Total	EPA 200.8, Rev. 5.4 (1994)
Antimony, Total	EPA 200.7, Rev. 4.4 (1994)
	EPA 6010C
	EPA 6010D
	EPA 6020A
	EPA 6020B
	EPA 200.8, Rev. 5.4 (1994)
Arsenic, Total	EPA 200.7, Rev. 4.4 (1994)
	EPA 6010C
	EPA 6010D
	EPA 6020A
	EPA 6020B
	EPA 200.8, Rev. 5.4 (1994)
Beryllium, Total	EPA 200.7, Rev. 4.4 (1994)
	EPA 6010C
	EPA 6010D
	EPA 6020A
	EPA 6020B
	EPA 200.8, Rev. 5.4 (1994)
Chromium VI	EPA 7196A
	SM 3500-Cr B-2011
Mercury, Total	EPA 245.1, Rev. 3.0 (1994)
	EPA 245.2 (Issued 1974, Rev. 1983)
	EPA 7470A
	EPA 7473
Selenium, Total	EPA 200.7, Rev. 4.4 (1994)
	EPA 6010C

Serial No.: 71155

Property of the New York State Department of Health. Certificates are valid only at the address shown and must be conspicuously posted by the laboratory. Continued accreditation depends on the laboratory's successful ongoing participation in the Program. Consumers may verify a laboratory's accreditation status online at https://apps.health.ny.gov/pubdoh/applinks/wc/elappublicweb/, by phone (518) 485-5570 or by email to elap@health.ny.gov.

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER

Expires 12:01 AM April 01, 2026
Issued April 01, 2025
Revised July 09, 2025

CERTIFICATE OF APPROVAL FOR LABORATORY SERVICE

Issued in accordance with and pursuant to section 502 Public Health Law of New York State

MS. CATHERINE L. MOSHER
YORK ANALYTICAL LABORATORIES INC
120 RESEARCH DRIVE
STRATFORD, CT 06615

NY Lab Id No: 10854

is hereby APPROVED as an Environmental Laboratory in conformance with the National Environmental Laboratory Accreditation Conference Standards (2016) for the category ENVIRONMENTAL ANALYSES NON POTABLE WATER
All approved analytes are listed below:

Metals II

Selenium, Total	EPA 6010D
Vanadium, Total	EPA 200.7, Rev. 4.4 (1994)
	EPA 6010C
	EPA 6010D
	EPA 6020A
	EPA 6020B
	EPA 200.8, Rev. 5.4 (1994)
Zinc, Total	EPA 200.7, Rev. 4.4 (1994)
	EPA 6010C
	EPA 6010D

Metals III

Cobalt, Total	EPA 200.7, Rev. 4.4 (1994)
	EPA 6010C
	EPA 6010D
	EPA 6020A
	EPA 6020B
	EPA 200.8, Rev. 5.4 (1994)
Molybdenum, Total	EPA 6020A
	EPA 200.8, Rev. 5.4 (1994)
Thallium, Total	EPA 200.7, Rev. 4.4 (1994)
	EPA 6010C
	EPA 6010D
	EPA 6020A
	EPA 6020B
	EPA 200.8, Rev. 5.4 (1994)
Tin, Total	EPA 6020A
	EPA 200.8, Rev. 5.4 (1994)

Serial No.: 71155

Property of the New York State Department of Health. Certificates are valid only at the address shown and must be conspicuously posted by the laboratory. Continued accreditation depends on the laboratory's successful ongoing participation in the Program. Consumers may verify a laboratory's accreditation status online at https://apps.health.ny.gov/pubdoh/applinks/wc/elappublicweb/, by phone (518) 485-5570 or by email to elap@health.ny.gov.

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER

Expires 12:01 AM April 01, 2026
Issued April 01, 2025
Revised July 09, 2025

CERTIFICATE OF APPROVAL FOR LABORATORY SERVICE

Issued in accordance with and pursuant to section 502 Public Health Law of New York State

MS. CATHERINE L. MOSHER
YORK ANALYTICAL LABORATORIES INC
120 RESEARCH DRIVE
STRATFORD, CT 06615

NY Lab Id No: 10854

is hereby APPROVED as an Environmental Laboratory in conformance with the National Environmental Laboratory Accreditation Conference Standards (2016) for the category ENVIRONMENTAL ANALYSES NON POTABLE WATER
All approved analytes are listed below:

Metals III

Titanium, Total	EPA 6020A
	EPA 200.8, Rev. 5.4 (1994)

Mineral

Alkalinity	SM 2320B-2011
Calcium Hardness	EPA 200.7, Rev. 4.4 (1994)
Chloride	EPA 300.0, Rev. 2.1 (1993)
Fluoride, Total	EPA 300.0, Rev. 2.1 (1993)
Hardness, Total	SM 2340B-2011
Sulfate (as SO4)	EPA 300.0, Rev. 2.1 (1993)

Miscellaneous

Boron, Total	EPA 6020A
	EPA 200.8, Rev. 5.4 (1994)
Bromide	EPA 300.0, Rev. 2.1 (1993)
Color	SM 2120B-2011
Cyanide, Total	SM 4500-CN E-2016
non-Polar Extractable Material (TPH)	EPA 1664A
Phenols	EPA 420.1 (Rev. 1978)
Specific Conductance	EPA 120.1 (Rev. 1982)
Sulfide (as S)	SM 4500-S2- F-2011
Surfactant (MBAS)	SM 5540C-2011
Turbidity	EPA 180.1, Rev. 2.0 (1993)

Nitroaromatics and Isophorone

2,4-Dinitrotoluene	EPA 625.1
	EPA 8270D
	EPA 8270E
2,6-Dinitrotoluene	EPA 625.1

Serial No.: 71155

Property of the New York State Department of Health. Certificates are valid only at the address shown and must be conspicuously posted by the laboratory. Continued accreditation depends on the laboratory's successful ongoing participation in the Program. Consumers may verify a laboratory's accreditation status online at https://apps.health.ny.gov/pubdoh/applinks/wc/elappublicweb/, by phone (518) 485-5570 or by email to elap@health.ny.gov.

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER

Expires 12:01 AM April 01, 2026
Issued April 01, 2025
Revised July 09, 2025

CERTIFICATE OF APPROVAL FOR LABORATORY SERVICE

Issued in accordance with and pursuant to section 502 Public Health Law of New York State

MS. CATHERINE L. MOSHER
YORK ANALYTICAL LABORATORIES INC
120 RESEARCH DRIVE
STRATFORD, CT 06615

NY Lab Id No: 10854

is hereby APPROVED as an Environmental Laboratory in conformance with the National Environmental Laboratory Accreditation Conference Standards (2016) for the category ENVIRONMENTAL ANALYSES NON POTABLE WATER
All approved analytes are listed below:

Nitroaromatics and Isophorone

2,6-Dinitrotoluene	EPA 8270D
	EPA 8270E
Isophorone	EPA 625.1
	EPA 8270D
	EPA 8270E
Nitrobenzene	EPA 625.1
	EPA 8270D
	EPA 8270E

Nitrosoamines

N-Nitrosodimethylamine	EPA 625.1
	EPA 8270D
	EPA 8270E
N-Nitrosodi-n-propylamine	EPA 625.1
	EPA 8270D
	EPA 8270E
N-Nitrosodiphenylamine	EPA 625.1
	EPA 8270D
	EPA 8270E

Nutrient

Ammonia (as N)	SM 4500-NH3 D-2011 or E-2011
Kjeldahl Nitrogen, Total	SM 4500-N Org D-2011
	SM 4500-NH3 D-2011 or E-2011
Nitrate (as N)	EPA 300.0, Rev. 2.1 (1993)
Nitrate-Nitrite (as N)	EPA 300.0, Rev. 2.1 (1993)
Nitrite (as N)	EPA 300.0, Rev. 2.1 (1993)
Orthophosphate (as P)	EPA 300.0, Rev. 2.1 (1993)

Serial No.: 71155

Property of the New York State Department of Health. Certificates are valid only at the address shown and must be conspicuously posted by the laboratory. Continued accreditation depends on the laboratory's successful ongoing participation in the Program. Consumers may verify a laboratory's accreditation status online at https://apps.health.ny.gov/pubdoh/applinks/wc/elappublicweb/, by phone (518) 485-5570 or by email to elap@health.ny.gov.

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER

Expires 12:01 AM April 01, 2026
Issued April 01, 2025
Revised July 09, 2025

CERTIFICATE OF APPROVAL FOR LABORATORY SERVICE

Issued in accordance with and pursuant to section 502 Public Health Law of New York State

MS. CATHERINE L. MOSHER
YORK ANALYTICAL LABORATORIES INC
120 RESEARCH DRIVE
STRATFORD, CT 06615

NY Lab Id No: 10854

is hereby APPROVED as an Environmental Laboratory in conformance with the National Environmental Laboratory Accreditation Conference Standards (2016) for the category ENVIRONMENTAL ANALYSES NON POTABLE WATER
All approved analytes are listed below:

Nutrient	
Orthophosphate (as P)	SM 4500-P E-2011
Organophosphate Pesticides	
Atrazine	EPA 8270D
	EPA 8270E
Parathion ethyl	EPA 8270D
	EPA 8270E
Petroleum Hydrocarbons	
Diesel Range Organics	EPA 8015D
Gasoline Range Organics	EPA 8015D
Phthalate Esters	
Benzyl butyl phthalate	EPA 625.1
	EPA 8270D
	EPA 8270E
Bis(2-ethylhexyl) phthalate	EPA 625.1
	EPA 8270D
	EPA 8270E
Diethyl phthalate	EPA 625.1
	EPA 8270D
	EPA 8270E
Dimethyl phthalate	EPA 625.1
	EPA 8270D
	EPA 8270E
Di-n-butyl phthalate	EPA 625.1
	EPA 8270D
	EPA 8270E
Di-n-octyl phthalate	EPA 625.1

Serial No.: 71155

Property of the New York State Department of Health. Certificates are valid only at the address shown and must be conspicuously posted by the laboratory. Continued accreditation depends on the laboratory's successful ongoing participation in the Program. Consumers may verify a laboratory's accreditation status online at https://apps.health.ny.gov/pubdoh/applinks/wc/elappublicweb/, by phone (518) 485-5570 or by email to elap@health.ny.gov.

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER

Expires 12:01 AM April 01, 2026
Issued April 01, 2025
Revised July 09, 2025

CERTIFICATE OF APPROVAL FOR LABORATORY SERVICE

Issued in accordance with and pursuant to section 502 Public Health Law of New York State

MS. CATHERINE L. MOSHER
YORK ANALYTICAL LABORATORIES INC
120 RESEARCH DRIVE
STRATFORD, CT 06615

NY Lab Id No: 10854

is hereby APPROVED as an Environmental Laboratory in conformance with the National Environmental Laboratory Accreditation Conference Standards (2016) for the category ENVIRONMENTAL ANALYSES NON POTABLE WATER
All approved analytes are listed below:

Phthalate Esters

Di-n-octyl phthalate	EPA 8270D
	EPA 8270E

Polychlorinated Biphenyls

Aroclor 1016 (PCB-1016)	EPA 8082A
	EPA 608.3
Aroclor 1221 (PCB-1221)	EPA 8082A
	EPA 608.3
Aroclor 1232 (PCB-1232)	EPA 8082A
	EPA 608.3
Aroclor 1242 (PCB-1242)	EPA 8082A
	EPA 608.3
Aroclor 1248 (PCB-1248)	EPA 8082A
	EPA 608.3
Aroclor 1254 (PCB-1254)	EPA 8082A
	EPA 608.3
Aroclor 1260 (PCB-1260)	EPA 8082A
	EPA 608.3
Aroclor 1262 (PCB-1262)	EPA 8082A
Aroclor 1268 (PCB-1268)	EPA 8082A

Polynuclear Aromatics

Acenaphthene	EPA 625.1
	EPA 8270D
	EPA 8270E
Acenaphthylene	EPA 625.1
	EPA 8270D
	EPA 8270E

Serial No.: 71155

Property of the New York State Department of Health. Certificates are valid only at the address shown and must be conspicuously posted by the laboratory. Continued accreditation depends on the laboratory's successful ongoing participation in the Program. Consumers may verify a laboratory's accreditation status online at https://apps.health.ny.gov/pubdoh/applinks/wc/elappublicweb/, by phone (518) 485-5570 or by email to elap@health.ny.gov.

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER

Expires 12:01 AM April 01, 2026
Issued April 01, 2025
Revised July 09, 2025

CERTIFICATE OF APPROVAL FOR LABORATORY SERVICE

Issued in accordance with and pursuant to section 502 Public Health Law of New York State

MS. CATHERINE L. MOSHER
YORK ANALYTICAL LABORATORIES INC
120 RESEARCH DRIVE
STRATFORD, CT 06615

NY Lab Id No: 10854

is hereby APPROVED as an Environmental Laboratory in conformance with the National Environmental Laboratory Accreditation Conference Standards (2016) for the category ENVIRONMENTAL ANALYSES NON POTABLE WATER
All approved analytes are listed below:

Polynuclear Aromatics

Anthracene	EPA 625.1
	EPA 8270D
	EPA 8270E
Benzo(a)anthracene	EPA 625.1
	EPA 8270D
	EPA 8270E
Benzo(a)pyrene	EPA 625.1
	EPA 8270D
	EPA 8270E
Benzo(b)fluoranthene	EPA 625.1
	EPA 8270D
	EPA 8270E
Benzo(g,h,i)perylene	EPA 625.1
	EPA 8270D
	EPA 8270E
Benzo(k)fluoranthene	EPA 625.1
	EPA 8270D
	EPA 8270E
Chrysene	EPA 625.1
	EPA 8270D
	EPA 8270E
Dibenzo(a,h)anthracene	EPA 625.1
	EPA 8270D
	EPA 8270E
Fluoranthene	EPA 625.1
	EPA 8270D
	EPA 8270E

Serial No.: 71155

Property of the New York State Department of Health. Certificates are valid only at the address shown and must be conspicuously posted by the laboratory. Continued accreditation depends on the laboratory's successful ongoing participation in the Program. Consumers may verify a laboratory's accreditation status online at https://apps.health.ny.gov/pubdoh/applinks/wc/elappublicweb/, by phone (518) 485-5570 or by email to elap@health.ny.gov.

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER

Expires 12:01 AM April 01, 2026
Issued April 01, 2025
Revised July 09, 2025

CERTIFICATE OF APPROVAL FOR LABORATORY SERVICE

Issued in accordance with and pursuant to section 502 Public Health Law of New York State

MS. CATHERINE L. MOSHER
YORK ANALYTICAL LABORATORIES INC
120 RESEARCH DRIVE
STRATFORD, CT 06615

NY Lab Id No: 10854

is hereby APPROVED as an Environmental Laboratory in conformance with the National Environmental Laboratory Accreditation Conference Standards (2016) for the category ENVIRONMENTAL ANALYSES NON POTABLE WATER
All approved analytes are listed below:

Polynuclear Aromatics

Fluorene	EPA 625.1
	EPA 8270D
	EPA 8270E
Indeno(1,2,3-cd)pyrene	EPA 625.1
	EPA 8270D
	EPA 8270E
Naphthalene	EPA 625.1
	EPA 8270D
	EPA 8270E
Phenanthrene	EPA 8270E
Pyrene	EPA 625.1
	EPA 8270D
	EPA 8270E

Priority Pollutant Phenols

2,3,4,6 Tetrachlorophenol	EPA 8270D
	EPA 8270E
2,4,5-Trichlorophenol	EPA 625.1
	EPA 8270D
	EPA 8270E
2,4,6-Trichlorophenol	EPA 625.1
	EPA 8270D
	EPA 8270E
2,4-Dichlorophenol	EPA 625.1
	EPA 8270D
	EPA 8270E
2,4-Dimethylphenol	EPA 625.1
	EPA 8270D

Serial No.: 71155

Property of the New York State Department of Health. Certificates are valid only at the address shown and must be conspicuously posted by the laboratory. Continued accreditation depends on the laboratory's successful ongoing participation in the Program. Consumers may verify a laboratory's accreditation status online at https://apps.health.ny.gov/pubdoh/applinks/wc/elappublicweb/, by phone (518) 485-5570 or by email to elap@health.ny.gov.

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER

Expires 12:01 AM April 01, 2026
Issued April 01, 2025
Revised July 09, 2025

CERTIFICATE OF APPROVAL FOR LABORATORY SERVICE

Issued in accordance with and pursuant to section 502 Public Health Law of New York State

MS. CATHERINE L. MOSHER
YORK ANALYTICAL LABORATORIES INC
120 RESEARCH DRIVE
STRATFORD, CT 06615

NY Lab Id No: 10854

is hereby APPROVED as an Environmental Laboratory in conformance with the National Environmental Laboratory Accreditation Conference Standards (2016) for the category ENVIRONMENTAL ANALYSES NON POTABLE WATER
All approved analytes are listed below:

Priority Pollutant Phenols

2,4-Dimethylphenol	EPA 8270E
2,4-Dinitrophenol	EPA 8270E
2-Chlorophenol	EPA 625.1
	EPA 8270D
	EPA 8270E
2-Methyl-4,6-dinitrophenol	EPA 625.1
	EPA 8270D
	EPA 8270E
2-Methylphenol	EPA 625.1
	EPA 8270D
	EPA 8270E
2-Nitrophenol	EPA 625.1
	EPA 8270D
	EPA 8270E
4-Chloro-3-methylphenol	EPA 625.1
	EPA 8270D
	EPA 8270E
4-Methylphenol	EPA 625.1
	EPA 8270D
	EPA 8270E
4-Nitrophenol	EPA 625.1
	EPA 8270D
	EPA 8270E
Cresols, Total	EPA 8270D
	EPA 8270E
Pentachlorophenol	EPA 625.1
	EPA 8270D

Serial No.: 71155

Property of the New York State Department of Health. Certificates are valid only at the address shown and must be conspicuously posted by the laboratory. Continued accreditation depends on the laboratory's successful ongoing participation in the Program. Consumers may verify a laboratory's accreditation status online at https://apps.health.ny.gov/pubdoh/applinks/wc/elappublicweb/, by phone (518) 485-5570 or by email to elap@health.ny.gov.

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER

Expires 12:01 AM April 01, 2026
Issued April 01, 2025
Revised July 09, 2025

CERTIFICATE OF APPROVAL FOR LABORATORY SERVICE

Issued in accordance with and pursuant to section 502 Public Health Law of New York State

MS. CATHERINE L. MOSHER
YORK ANALYTICAL LABORATORIES INC
120 RESEARCH DRIVE
STRATFORD, CT 06615

NY Lab Id No: 10854

is hereby APPROVED as an Environmental Laboratory in conformance with the National Environmental Laboratory Accreditation Conference Standards (2016) for the category ENVIRONMENTAL ANALYSES NON POTABLE WATER
All approved analytes are listed below:

Priority Pollutant Phenols	
Pentachlorophenol	EPA 8270E
Phenol	EPA 625.1
	EPA 8270D
	EPA 8270E
Residue	
Settleable Solids	SM 2540 F-2015
Solids, Total	SM 2540 B-2015
Solids, Total Dissolved	SM 2540 C-2015
Solids, Total Suspended	SM 2540 D-2015
Semi-Volatile Organics	
1,1'-Biphenyl	EPA 8270D
	EPA 8270E
1,2-Dichlorobenzene, Semi-volatile	EPA 8270D
	EPA 8270E
1,3-Dichlorobenzene, Semi-volatile	EPA 8270D
	EPA 8270E
1,4-Dichlorobenzene, Semi-volatile	EPA 8270D
	EPA 8270E
2-Methylnaphthalene	EPA 8270D
	EPA 8270E
Acetophenone	EPA 8270D
	EPA 8270E
alpha-Terpineol	EPA 625.1
	EPA 8270E
Benzaldehyde	EPA 8270D
	EPA 8270E

Serial No.: 71155

Property of the New York State Department of Health. Certificates are valid only at the address shown and must be conspicuously posted by the laboratory. Continued accreditation depends on the laboratory's successful ongoing participation in the Program. Consumers may verify a laboratory's accreditation status online at https://apps.health.ny.gov/pubdoh/applinks/wc/elappublicweb/, by phone (518) 485-5570 or by email to elap@health.ny.gov.

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER

Expires 12:01 AM April 01, 2026
Issued April 01, 2025
Revised July 09, 2025

CERTIFICATE OF APPROVAL FOR LABORATORY SERVICE

Issued in accordance with and pursuant to section 502 Public Health Law of New York State

MS. CATHERINE L. MOSHER
YORK ANALYTICAL LABORATORIES INC
120 RESEARCH DRIVE
STRATFORD, CT 06615

NY Lab Id No: 10854

is hereby APPROVED as an Environmental Laboratory in conformance with the National Environmental Laboratory Accreditation Conference Standards (2016) for the category ENVIRONMENTAL ANALYSES NON POTABLE WATER
All approved analytes are listed below:

Semi-Volatile Organics

Benzoic Acid	EPA 8270D
	EPA 8270E
Benzyl alcohol	EPA 8270D
	EPA 8270E
Caprolactam	EPA 8270D
	EPA 8270E
Dibenzofuran	EPA 8270D
	EPA 8270E

Volatile Aromatics

1,2,4-Trichlorobenzene, Volatile	EPA 8260D
	EPA 8260C
1,2,4-Trimethylbenzene	EPA 8260D
	EPA 8260C
1,2-Dichlorobenzene	EPA 8260D
	EPA 8260C
	EPA 624.1
1,3,5-Trimethylbenzene	EPA 8260D
	EPA 8260C
1,3-Dichlorobenzene	EPA 8260D
	EPA 8260C
	EPA 624.1
1,4-Dichlorobenzene	EPA 8260D
	EPA 8260C
	EPA 624.1
2-Chlorotoluene	EPA 8260D
	EPA 8260C
4-Chlorotoluene	EPA 8260D

Serial No.: 71155

Property of the New York State Department of Health. Certificates are valid only at the address shown and must be conspicuously posted by the laboratory. Continued accreditation depends on the laboratory's successful ongoing participation in the Program. Consumers may verify a laboratory's accreditation status online at https://apps.health.ny.gov/pubdoh/applinks/wc/elappublicweb/, by phone (518) 485-5570 or by email to elap@health.ny.gov.

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER

Expires 12:01 AM April 01, 2026
Issued April 01, 2025
Revised July 09, 2025

CERTIFICATE OF APPROVAL FOR LABORATORY SERVICE

Issued in accordance with and pursuant to section 502 Public Health Law of New York State

MS. CATHERINE L. MOSHER
YORK ANALYTICAL LABORATORIES INC
120 RESEARCH DRIVE
STRATFORD, CT 06615

NY Lab Id No: 10854

is hereby APPROVED as an Environmental Laboratory in conformance with the National Environmental Laboratory Accreditation Conference Standards (2016) for the category ENVIRONMENTAL ANALYSES NON POTABLE WATER
All approved analytes are listed below:

Volatile Aromatics

4-Chlorotoluene	EPA 8260C
Benzene	EPA 8260D
	EPA 8260C
	EPA 624.1
Bromobenzene	EPA 8260D
	EPA 8260C
Chlorobenzene	EPA 8260D
	EPA 8260C
	EPA 624.1
Ethyl benzene	EPA 8260D
	EPA 8260C
	EPA 624.1
Isopropylbenzene	EPA 8260D
	EPA 8260C
m/p-Xylenes	EPA 8260D
	EPA 8260C
	EPA 624.1
Naphthalene, Volatile	EPA 8260D
	EPA 8260C
n-Butylbenzene	EPA 8260D
	EPA 8260C
n-Propylbenzene	EPA 8260D
	EPA 8260C
o-Xylene	EPA 8260D
	EPA 8260C
	EPA 624.1
p-Isopropyltoluene (P-Cymene)	EPA 8260D

Serial No.: 71155

Property of the New York State Department of Health. Certificates are valid only at the address shown and must be conspicuously posted by the laboratory. Continued accreditation depends on the laboratory's successful ongoing participation in the Program. Consumers may verify a laboratory's accreditation status online at https://apps.health.ny.gov/pubdoh/applinks/wc/elappublicweb/, by phone (518) 485-5570 or by email to elap@health.ny.gov.

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER

Expires 12:01 AM April 01, 2026
Issued April 01, 2025
Revised July 09, 2025

CERTIFICATE OF APPROVAL FOR LABORATORY SERVICE

Issued in accordance with and pursuant to section 502 Public Health Law of New York State

MS. CATHERINE L. MOSHER
YORK ANALYTICAL LABORATORIES INC
120 RESEARCH DRIVE
STRATFORD, CT 06615

NY Lab Id No: 10854

is hereby APPROVED as an Environmental Laboratory in conformance with the National Environmental Laboratory Accreditation Conference Standards (2016) for the category ENVIRONMENTAL ANALYSES NON POTABLE WATER
All approved analytes are listed below:

Volatile Aromatics

p-Isopropyltoluene (P-Cymene)	EPA 8260C
sec-Butylbenzene	EPA 8260D
	EPA 8260C
Styrene	EPA 8260D
	EPA 8260C
	EPA 624.1
tert-Butylbenzene	EPA 8260D
	EPA 8260C
Toluene	EPA 8260D
	EPA 8260C
	EPA 624.1
Total Xylenes	EPA 8260D
	EPA 8260C
	EPA 624.1

Volatile Halocarbons

1,1,1,2-Tetrachloroethane	EPA 8260D
	EPA 8260C
1,1,1-Trichloroethane	EPA 8260D
	EPA 8260C
	EPA 624.1
1,1,2,2-Tetrachloroethane	EPA 8260D
	EPA 8260C
	EPA 624.1
1,1,2-Trichloro-1,2,2-Trifluoroethane	EPA 8260D
	EPA 8260C
1,1,2-Trichloroethane	EPA 8260D
	EPA 8260C

Serial No.: 71155

Property of the New York State Department of Health. Certificates are valid only at the address shown and must be conspicuously posted by the laboratory. Continued accreditation depends on the laboratory's successful ongoing participation in the Program. Consumers may verify a laboratory's accreditation status online at https://apps.health.ny.gov/pubdoh/applinks/wc/elappublicweb/, by phone (518) 485-5570 or by email to elap@health.ny.gov.

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER

Expires 12:01 AM April 01, 2026
Issued April 01, 2025
Revised July 09, 2025

CERTIFICATE OF APPROVAL FOR LABORATORY SERVICE

Issued in accordance with and pursuant to section 502 Public Health Law of New York State

MS. CATHERINE L. MOSHER
YORK ANALYTICAL LABORATORIES INC
120 RESEARCH DRIVE
STRATFORD, CT 06615

NY Lab Id No: 10854

is hereby APPROVED as an Environmental Laboratory in conformance with the National Environmental Laboratory Accreditation Conference Standards (2016) for the category ENVIRONMENTAL ANALYSES NON POTABLE WATER
All approved analytes are listed below:

Volatile Halocarbons

1,1,2-Trichloroethane	EPA 624.1
1,1-Dichloroethane	EPA 8260D
	EPA 8260C
	EPA 624.1
1,1-Dichloroethene	EPA 8260D
	EPA 8260C
	EPA 624.1
1,1-Dichloropropene	EPA 8260D
	EPA 8260C
1,2,3-Trichloropropane	EPA 8260D
	EPA 8260C
1,2-Dibromo-3-chloropropane	EPA 8260D
	EPA 8260C
1,2-Dibromoethane	EPA 8260D
	EPA 8260C
1,2-Dichloroethane	EPA 8260D
	EPA 8260C
	EPA 624.1
1,2-Dichloropropane	EPA 8260D
	EPA 8260C
	EPA 624.1
1,3-Dichloropropane	EPA 8260D
	EPA 8260C
2,2-Dichloropropane	EPA 8260D
	EPA 8260C
2-Chloroethylvinyl ether	EPA 8260D
	EPA 8260C

Serial No.: 71155

Property of the New York State Department of Health. Certificates are valid only at the address shown and must be conspicuously posted by the laboratory. Continued accreditation depends on the laboratory's successful ongoing participation in the Program. Consumers may verify a laboratory's accreditation status online at https://apps.health.ny.gov/pubdoh/applinks/wc/elappublicweb/, by phone (518) 485-5570 or by email to elap@health.ny.gov.

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER

Expires 12:01 AM April 01, 2026
Issued April 01, 2025
Revised July 09, 2025

CERTIFICATE OF APPROVAL FOR LABORATORY SERVICE

Issued in accordance with and pursuant to section 502 Public Health Law of New York State

MS. CATHERINE L. MOSHER
YORK ANALYTICAL LABORATORIES INC
120 RESEARCH DRIVE
STRATFORD, CT 06615

NY Lab Id No: 10854

is hereby APPROVED as an Environmental Laboratory in conformance with the National Environmental Laboratory Accreditation Conference Standards (2016) for the category ENVIRONMENTAL ANALYSES NON POTABLE WATER
All approved analytes are listed below:

Volatile Halocarbons

2-Chloroethylvinyl ether	EPA 624.1
Bromochloromethane	EPA 8260D
	EPA 8260C
Bromodichloromethane	EPA 8260D
	EPA 8260C
	EPA 624.1
Bromoform	EPA 8260D
	EPA 8260C
	EPA 624.1
Bromomethane	EPA 8260D
	EPA 8260C
	EPA 624.1
Carbon tetrachloride	EPA 8260D
	EPA 8260C
	EPA 624.1
Chloroethane	EPA 8260D
	EPA 8260C
	EPA 624.1
Chloroform	EPA 8260D
	EPA 8260C
	EPA 624.1
Chloromethane	EPA 8260D
	EPA 8260C
	EPA 624.1
cis-1,2-Dichloroethene	EPA 8260D
	EPA 8260C
	EPA 624.1

Serial No.: 71155

Property of the New York State Department of Health. Certificates are valid only at the address shown and must be conspicuously posted by the laboratory. Continued accreditation depends on the laboratory's successful ongoing participation in the Program. Consumers may verify a laboratory's accreditation status online at https://apps.health.ny.gov/pubdoh/applinks/wc/elappublicweb/, by phone (518) 485-5570 or by email to elap@health.ny.gov.

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER

Expires 12:01 AM April 01, 2026
Issued April 01, 2025
Revised July 09, 2025

CERTIFICATE OF APPROVAL FOR LABORATORY SERVICE

Issued in accordance with and pursuant to section 502 Public Health Law of New York State

MS. CATHERINE L. MOSHER
YORK ANALYTICAL LABORATORIES INC
120 RESEARCH DRIVE
STRATFORD, CT 06615

NY Lab Id No: 10854

is hereby APPROVED as an Environmental Laboratory in conformance with the National Environmental Laboratory Accreditation Conference Standards (2016) for the category ENVIRONMENTAL ANALYSES NON POTABLE WATER
All approved analytes are listed below:

Volatile Halocarbons

cis-1,3-Dichloropropene	EPA 8260D
	EPA 8260C
	EPA 624.1
Dibromochloromethane	EPA 8260D
	EPA 8260C
	EPA 624.1
Dibromomethane	EPA 8260D
	EPA 8260C
Dichlorodifluoromethane	EPA 8260D
	EPA 8260C
	EPA 624.1
Hexachlorobutadiene, Volatile	EPA 8260D
	EPA 8260C
Methylene chloride	EPA 8260D
	EPA 8260C
	EPA 624.1
Tetrachloroethene	EPA 8260D
	EPA 8260C
	EPA 624.1
trans-1,2-Dichloroethene	EPA 8260D
	EPA 8260C
	EPA 624.1
trans-1,3-Dichloropropene	EPA 8260D
	EPA 8260C
	EPA 624.1
trans-1,4-Dichloro-2-butene	EPA 8260D
	EPA 8260C

Serial No.: 71155

Property of the New York State Department of Health. Certificates are valid only at the address shown and must be conspicuously posted by the laboratory. Continued accreditation depends on the laboratory's successful ongoing participation in the Program. Consumers may verify a laboratory's accreditation status online at https://apps.health.ny.gov/pubdoh/applinks/wc/elappublicweb/, by phone (518) 485-5570 or by email to elap@health.ny.gov.

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER

Expires 12:01 AM April 01, 2026
Issued April 01, 2025
Revised July 09, 2025

CERTIFICATE OF APPROVAL FOR LABORATORY SERVICE

Issued in accordance with and pursuant to section 502 Public Health Law of New York State

MS. CATHERINE L. MOSHER
YORK ANALYTICAL LABORATORIES INC
120 RESEARCH DRIVE
STRATFORD, CT 06615

NY Lab Id No: 10854

is hereby APPROVED as an Environmental Laboratory in conformance with the National Environmental Laboratory Accreditation Conference Standards (2016) for the category ENVIRONMENTAL ANALYSES NON POTABLE WATER
All approved analytes are listed below:

Volatile Halocarbons

Trichloroethene	EPA 8260D
	EPA 8260C
	EPA 624.1
Trichlorofluoromethane	EPA 8260D
	EPA 8260C
	EPA 624.1
Vinyl chloride	EPA 8260D
	EPA 8260C
	EPA 624.1

Volatiles Organics

1,4-Dioxane	EPA 8260D
	EPA 8260C
	EPA 8270D SIM
	EPA 8270E
	EPA 8270E SIM
2-Butanone (Methylethyl ketone)	EPA 8260D
	EPA 8260C
2-Hexanone	EPA 8260D
	EPA 8260C
4-Methyl-2-Pentanone	EPA 8260D
	EPA 8260C
Acetone	EPA 8260D
	EPA 8260C
Carbon Disulfide	EPA 8260D
	EPA 8260C
Cyclohexane	EPA 8260D
	EPA 8260C

Serial No.: 71155

Property of the New York State Department of Health. Certificates are valid only at the address shown and must be conspicuously posted by the laboratory. Continued accreditation depends on the laboratory's successful ongoing participation in the Program. Consumers may verify a laboratory's accreditation status online at https://apps.health.ny.gov/pubdoh/applinks/wc/elappublicweb/, by phone (518) 485-5570 or by email to elap@health.ny.gov.

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER

Expires 12:01 AM April 01, 2026
Issued April 01, 2025
Revised July 09, 2025

CERTIFICATE OF APPROVAL FOR LABORATORY SERVICE

Issued in accordance with and pursuant to section 502 Public Health Law of New York State

MS. CATHERINE L. MOSHER
YORK ANALYTICAL LABORATORIES INC
120 RESEARCH DRIVE
STRATFORD, CT 06615

NY Lab Id No: 10854

is hereby APPROVED as an Environmental Laboratory in conformance with the National Environmental Laboratory Accreditation Conference Standards (2016) for the category ENVIRONMENTAL ANALYSES NON POTABLE WATER
All approved analytes are listed below:

Volatiles Organics

Methyl acetate	EPA 8260D
	EPA 8260C
Methyl cyclohexane	EPA 8260D
	EPA 8260C
Vinyl acetate	EPA 8260D
	EPA 8260C

Sample Preparation Methods

SM 4500-P B(5)-2011
EPA 5030C
SM 4500-CN B-2016 and C-2016
EPA 3015A
EPA 3010A
EPA 3005A
EPA 3510C
SM 4500-N Org B-2011 or C-2011

Serial No.: 71155

Property of the New York State Department of Health. Certificates are valid only at the address shown and must be conspicuously posted by the laboratory. Continued accreditation depends on the laboratory's successful ongoing participation in the Program. Consumers may verify a laboratory's accreditation status online at https://apps.health.ny.gov/pubdoh/applinks/wc/elappublicweb/, by phone (518) 485-5570 or by email to elap@health.ny.gov.

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER

Expires 12:01 AM April 01, 2026
Issued April 01, 2025
Revised June 26, 2025

CERTIFICATE OF APPROVAL FOR LABORATORY SERVICE

Issued in accordance with and pursuant to section 502 Public Health Law of New York State

MS. CATHERINE L. MOSHER
YORK ANALYTICAL LABORATORIES INC
120 RESEARCH DRIVE
STRATFORD, CT 06615

NY Lab Id No: 10854

is hereby APPROVED as an Environmental Laboratory in conformance with the National Environmental Laboratory Accreditation Conference Standards (2016) for the category ENVIRONMENTAL ANALYSES POTABLE WATER
All approved analytes are listed below:

Fuel Additives

Methyl tert-butyl ether	EPA 524.2
Naphthalene	EPA 524.2

Metals I

Arsenic, Total	EPA 200.8 Rev. 5.4
Barium, Total	EPA 200.7 Rev. 4.4
Cadmium, Total	EPA 200.7 Rev. 4.4
	EPA 200.8 Rev. 5.4
Chromium, Total	EPA 200.7 Rev. 4.4
	EPA 200.8 Rev. 5.4
Copper, Total	EPA 200.7 Rev. 4.4
	EPA 200.8 Rev. 5.4
Iron, Total	EPA 200.7 Rev. 4.4
Lead, Total	EPA 200.8 Rev. 5.4
Manganese, Total	EPA 200.7 Rev. 4.4
	EPA 200.8 Rev. 5.4
Mercury, Total	EPA 245.1 Rev. 3.0
Silver, Total	EPA 200.7 Rev. 4.4
	EPA 200.8 Rev. 5.4
Zinc, Total	EPA 200.7 Rev. 4.4

Metals II

Aluminum, Total	EPA 200.7 Rev. 4.4
	EPA 200.8 Rev. 5.4
Antimony, Total	EPA 200.8 Rev. 5.4
Beryllium, Total	EPA 200.7 Rev. 4.4
	EPA 200.8 Rev. 5.4
Molybdenum, Total	EPA 200.8 Rev. 5.4

Serial No.: 71121

Property of the New York State Department of Health. Certificates are valid only at the address shown and must be conspicuously posted by the laboratory. Continued accreditation depends on the laboratory's successful ongoing participation in the Program. Consumers may verify a laboratory's accreditation status online at https://apps.health.ny.gov/pubdoh/applinks/wc/elappublicweb/, by phone (518) 485-5570 or by email to elap@health.ny.gov.

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER

Expires 12:01 AM April 01, 2026
Issued April 01, 2025
Revised June 26, 2025

CERTIFICATE OF APPROVAL FOR LABORATORY SERVICE

Issued in accordance with and pursuant to section 502 Public Health Law of New York State

MS. CATHERINE L. MOSHER
YORK ANALYTICAL LABORATORIES INC
120 RESEARCH DRIVE
STRATFORD, CT 06615

NY Lab Id No: 10854

is hereby APPROVED as an Environmental Laboratory in conformance with the National Environmental Laboratory Accreditation Conference Standards (2016) for the category ENVIRONMENTAL ANALYSES POTABLE WATER
All approved analytes are listed below:

Metals II

Nickel, Total	EPA 200.7 Rev. 4.4
	EPA 200.8 Rev. 5.4
Thallium, Total	EPA 200.8 Rev. 5.4
Vanadium, Total	EPA 200.7 Rev. 4.4
	EPA 200.8 Rev. 5.4

Metals III

Calcium, Total	EPA 200.7 Rev. 4.4
Magnesium, Total	EPA 200.7 Rev. 4.4
Potassium, Total	EPA 200.7 Rev. 4.4
Sodium, Total	EPA 200.7 Rev. 4.4

Miscellaneous

1,4-Dioxane	EPA 522
Turbidity	EPA 180.1 Rev. 2.0

Non-Metals

Alkalinity	SM 21-23 2320B (-97)
Calcium Hardness	EPA 200.7 Rev. 4.4
Chloride	EPA 300.0 Rev. 2.1
Color	SM 21-23 2120B (-01)
Fluoride, Total	EPA 300.0 Rev. 2.1
Orthophosphate (as P)	EPA 300.0 Rev. 2.1
	SM 19, 21-23 4500-P E (-99)
Solids, Total Dissolved	SM 21-23 2540C (-97)
Specific Conductance	EPA 120.1 Rev. 1982
Sulfate (as SO4)	EPA 300.0 Rev. 2.1

Trihalomethanes

Bromodichloromethane	EPA 524.2

Serial No.: 71121

Property of the New York State Department of Health. Certificates are valid only at the address shown and must be conspicuously posted by the laboratory. Continued accreditation depends on the laboratory's successful ongoing participation in the Program. Consumers may verify a laboratory's accreditation status online at https://apps.health.ny.gov/pubdoh/applinks/wc/elappublicweb/, by phone (518) 485-5570 or by email to elap@health.ny.gov.

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER

Expires 12:01 AM April 01, 2026
Issued April 01, 2025
Revised June 26, 2025

CERTIFICATE OF APPROVAL FOR LABORATORY SERVICE

Issued in accordance with and pursuant to section 502 Public Health Law of New York State

MS. CATHERINE L. MOSHER
YORK ANALYTICAL LABORATORIES INC
120 RESEARCH DRIVE
STRATFORD, CT 06615

NY Lab Id No: 10854

is hereby APPROVED as an Environmental Laboratory in conformance with the National Environmental Laboratory Accreditation Conference Standards (2016) for the category ENVIRONMENTAL ANALYSES POTABLE WATER
All approved analytes are listed below:

Trihalomethanes

Bromoform	EPA 524.2
Chloroform	EPA 524.2
Dibromochloromethane	EPA 524.2

Volatile Aromatics

1,2,3-Trichlorobenzene	EPA 524.2
1,2,4-Trichlorobenzene	EPA 524.2
1,2,4-Trimethylbenzene	EPA 524.2
1,2-Dichlorobenzene	EPA 524.2
1,3,5-Trimethylbenzene	EPA 524.2
1,3-Dichlorobenzene	EPA 524.2
1,4-Dichlorobenzene	EPA 524.2
2-Chlorotoluene	EPA 524.2
4-Chlorotoluene	EPA 524.2
Benzene	EPA 524.2
Bromobenzene	EPA 524.2
Chlorobenzene	EPA 524.2
Ethyl benzene	EPA 524.2
Hexachlorobutadiene	EPA 524.2
Isopropylbenzene	EPA 524.2
n-Butylbenzene	EPA 524.2
n-Propylbenzene	EPA 524.2
p-Isopropyltoluene (P-Cymene)	EPA 524.2
sec-Butylbenzene	EPA 524.2
Styrene	EPA 524.2
tert-Butylbenzene	EPA 524.2
Toluene	EPA 524.2
Total Xylenes	EPA 524.2

Serial No.: 71121

Property of the New York State Department of Health. Certificates are valid only at the address shown and must be conspicuously posted by the laboratory. Continued accreditation depends on the laboratory's successful ongoing participation in the Program. Consumers may verify a laboratory's accreditation status online at https://apps.health.ny.gov/pubdoh/applinks/wc/elappublicweb/, by phone (518) 485-5570 or by email to elap@health.ny.gov.

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER

Expires 12:01 AM April 01, 2026
Issued April 01, 2025
Revised June 26, 2025

CERTIFICATE OF APPROVAL FOR LABORATORY SERVICE

Issued in accordance with and pursuant to section 502 Public Health Law of New York State

MS. CATHERINE L. MOSHER
YORK ANALYTICAL LABORATORIES INC
120 RESEARCH DRIVE
STRATFORD, CT 06615

NY Lab Id No: 10854

is hereby APPROVED as an Environmental Laboratory in conformance with the National Environmental Laboratory Accreditation Conference Standards (2016) for the category ENVIRONMENTAL ANALYSES POTABLE WATER
All approved analytes are listed below:

Volatile Halocarbons

1,1,1,2-Tetrachloroethane	EPA 524.2
1,1,1-Trichloroethane	EPA 524.2
1,1,2,2-Tetrachloroethane	EPA 524.2
1,1,2-Trichloroethane	EPA 524.2
1,1-Dichloroethane	EPA 524.2
1,1-Dichloroethene	EPA 524.2
1,1-Dichloropropene	EPA 524.2
1,2,3-Trichloropropane	EPA 524.2
1,2-Dichloroethane	EPA 524.2
1,2-Dichloropropane	EPA 524.2
1,3-Dichloropropane	EPA 524.2
2,2-Dichloropropane	EPA 524.2
Bromochloromethane	EPA 524.2
Bromomethane	EPA 524.2
Carbon tetrachloride	EPA 524.2
Chloroethane	EPA 524.2
Chloromethane	EPA 524.2
cis-1,2-Dichloroethene	EPA 524.2
cis-1,3-Dichloropropene	EPA 524.2
Dibromomethane	EPA 524.2
Dichlorodifluoromethane	EPA 524.2
Methylene chloride	EPA 524.2
Tetrachloroethene	EPA 524.2
trans-1,2-Dichloroethene	EPA 524.2
trans-1,3-Dichloropropene	EPA 524.2
Trichloroethene	EPA 524.2
Trichlorofluoromethane	EPA 524.2

Serial No.: 71121

Property of the New York State Department of Health. Certificates are valid only at the address shown and must be conspicuously posted by the laboratory. Continued accreditation depends on the laboratory's successful ongoing participation in the Program. Consumers may verify a laboratory's accreditation status online at https://apps.health.ny.gov/pubdoh/applinks/wc/elappublicweb/, by phone (518) 485-5570 or by email to elap@health.ny.gov.

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER

Expires 12:01 AM April 01, 2026
Issued April 01, 2025
Revised June 26, 2025

CERTIFICATE OF APPROVAL FOR LABORATORY SERVICE

Issued in accordance with and pursuant to section 502 Public Health Law of New York State

MS. CATHERINE L. MOSHER
YORK ANALYTICAL LABORATORIES INC
120 RESEARCH DRIVE
STRATFORD, CT 06615

NY Lab Id No: 10854

is hereby APPROVED as an Environmental Laboratory in conformance with the National Environmental Laboratory Accreditation Conference Standards (2016) for the category ENVIRONMENTAL ANALYSES POTABLE WATER
All approved analytes are listed below:

Volatile Halocarbons

Vinyl chloride	EPA 524.2

Serial No.: 71121

Property of the New York State Department of Health. Certificates are valid only at the address shown and must be conspicuously posted by the laboratory. Continued accreditation depends on the laboratory's successful ongoing participation in the Program. Consumers may verify a laboratory's accreditation status online at https://apps.health.ny.gov/pubdoh/applinks/wc/elappublicweb/, by phone (518) 485-5570 or by email to elap@health.ny.gov.

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER

Expires 12:01 AM April 01, 2026
Issued April 01, 2025
Revised June 13, 2025

CERTIFICATE OF APPROVAL FOR LABORATORY SERVICE

Issued in accordance with and pursuant to section 502 Public Health Law of New York State

MS. CATHERINE L. MOSHER
YORK ANALYTICAL LABORATORIES INC
120 RESEARCH DRIVE
STRATFORD, CT 06615

NY Lab Id No: 10854

is hereby APPROVED as an Environmental Laboratory in conformance with the National Environmental Laboratory Accreditation Conference Standards (2016) for the category ENVIRONMENTAL ANALYSES SOLID AND HAZARDOUS WASTE
All approved analytes are listed below:

Acrylates

Acrolein (Propenal)	EPA 8260D
	EPA 8260C
Acrylonitrile	EPA 8260D
	EPA 8260C
Methyl methacrylate	EPA 8260D
	EPA 8260C

Amines

1,2-Diphenylhydrazine	EPA 8270D
	EPA 8270E
2-Nitroaniline	EPA 8270D
	EPA 8270E
3-Nitroaniline	EPA 8270D
	EPA 8270E
4-Chloroaniline	EPA 8270D
	EPA 8270E
4-Nitroaniline	EPA 8270D
	EPA 8270E
Aniline	EPA 8270D
	EPA 8270E
Carbazole	EPA 8270D
	EPA 8270E
Diphenylamine	EPA 8270D
	EPA 8270E

Benzidines

3,3'-Dichlorobenzidine	EPA 8270D
	EPA 8270E

Serial No.: 71102

Property of the New York State Department of Health. Certificates are valid only at the address shown and must be conspicuously posted by the laboratory. Continued accreditation depends on the laboratory's successful ongoing participation in the Program. Consumers may verify a laboratory's accreditation status online at https://apps.health.ny.gov/pubdoh/applinks/wc/elappublicweb/, by phone (518) 485-5570 or by email to elap@health.ny.gov.

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER

Expires 12:01 AM April 01, 2026
Issued April 01, 2025
Revised June 13, 2025

CERTIFICATE OF APPROVAL FOR LABORATORY SERVICE

Issued in accordance with and pursuant to section 502 Public Health Law of New York State

MS. CATHERINE L. MOSHER
YORK ANALYTICAL LABORATORIES INC
120 RESEARCH DRIVE
STRATFORD, CT 06615

NY Lab Id No: 10854

is hereby APPROVED as an Environmental Laboratory in conformance with the National Environmental Laboratory Accreditation Conference Standards (2016) for the category ENVIRONMENTAL ANALYSES SOLID AND HAZARDOUS WASTE
All approved analytes are listed below:

Benzidines

Benzidine	EPA 8270D
	EPA 8270E

Characteristic Testing

Corrosivity (pH)	EPA 9045D
Free Liquids	EPA 9095B
Ignitability	EPA 1010A
Synthetic Precipitation Leaching Proc.	EPA 1312
TCLP	EPA 1311

Chlorinated Hydrocarbon Pesticides

4,4'-DDD	EPA 8081B
4,4'-DDE	EPA 8081B
4,4'-DDT	EPA 8081B
Aldrin	EPA 8081B
alpha-BHC	EPA 8081B
alpha-Chlordane	EPA 8081B
Atrazine	EPA 8270D
	EPA 8270E
beta-BHC	EPA 8081B
Chlordane Total	EPA 8081B
delta-BHC	EPA 8081B
Dieldrin	EPA 8081B
Endosulfan I	EPA 8081B
Endosulfan II	EPA 8081B
Endosulfan sulfate	EPA 8081B
Endrin	EPA 8081B
Endrin aldehyde	EPA 8081B

Serial No.: 71102

Property of the New York State Department of Health. Certificates are valid only at the address shown and must be conspicuously posted by the laboratory. Continued accreditation depends on the laboratory's successful ongoing participation in the Program. Consumers may verify a laboratory's accreditation status online at https://apps.health.ny.gov/pubdoh/applinks/wc/elappublicweb/, by phone (518) 485-5570 or by email to elap@health.ny.gov.

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER

Expires 12:01 AM April 01, 2026
Issued April 01, 2025
Revised June 13, 2025

CERTIFICATE OF APPROVAL FOR LABORATORY SERVICE

Issued in accordance with and pursuant to section 502 Public Health Law of New York State

MS. CATHERINE L. MOSHER
YORK ANALYTICAL LABORATORIES INC
120 RESEARCH DRIVE
STRATFORD, CT 06615

NY Lab Id No: 10854

is hereby APPROVED as an Environmental Laboratory in conformance with the National Environmental Laboratory Accreditation Conference Standards (2016) for the category ENVIRONMENTAL ANALYSES SOLID AND HAZARDOUS WASTE
All approved analytes are listed below:

Chlorinated Hydrocarbon Pesticides

Endrin Ketone	EPA 8081B
gamma-Chlordane	EPA 8081B
Heptachlor	EPA 8081B
Heptachlor epoxide	EPA 8081B
Lindane	EPA 8081B
Methoxychlor	EPA 8081B
Mirex	EPA 8081B
Toxaphene	EPA 8081B

Chlorinated Hydrocarbons

1,2,3-Trichlorobenzene	EPA 8260D
	EPA 8260C
1,2,4,5-Tetrachlorobenzene	EPA 8270D
	EPA 8270E
1,2,4-Trichlorobenzene	EPA 8270D
	EPA 8270E
2-Chloronaphthalene	EPA 8270D
	EPA 8270E
Hexachlorobenzene	EPA 8270D
	EPA 8270E
Hexachlorobutadiene	EPA 8270D
	EPA 8270E
Hexachlorocyclopentadiene	EPA 8270D
	EPA 8270E
Hexachloroethane	EPA 8270D
	EPA 8270E

Serial No.: 71102

Property of the New York State Department of Health. Certificates are valid only at the address shown and must be conspicuously posted by the laboratory. Continued accreditation depends on the laboratory's successful ongoing participation in the Program. Consumers may verify a laboratory's accreditation status online at https://apps.health.ny.gov/pubdoh/applinks/wc/elappublicweb/, by phone (518) 485-5570 or by email to elap@health.ny.gov.

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER

Expires 12:01 AM April 01, 2026
Issued April 01, 2025
Revised June 13, 2025

CERTIFICATE OF APPROVAL FOR LABORATORY SERVICE

Issued in accordance with and pursuant to section 502 Public Health Law of New York State

MS. CATHERINE L. MOSHER
YORK ANALYTICAL LABORATORIES INC
120 RESEARCH DRIVE
STRATFORD, CT 06615

NY Lab Id No: 10854

is hereby APPROVED as an Environmental Laboratory in conformance with the National Environmental Laboratory Accreditation Conference Standards (2016) for the category ENVIRONMENTAL ANALYSES SOLID AND HAZARDOUS WASTE
All approved analytes are listed below:

Chlorophenoxy Acid Pesticides

2,4,5-T	EPA 8151A
2,4,5-TP (Silvex)	EPA 8151A
2,4-D	EPA 8151A
Dicamba	EPA 8151A

Haloethers

2,2'-Oxybis(1-chloropropane)	EPA 8270D
	EPA 8270E
4-Bromophenylphenyl ether	EPA 8270D
	EPA 8270E
4-Chlorophenylphenyl ether	EPA 8270D
	EPA 8270E
Bis(2-chloroethoxy)methane	EPA 8270D
	EPA 8270E
Bis(2-chloroethyl)ether	EPA 8270D
	EPA 8270E

Metals I

Barium, Total	EPA 6010C
	EPA 6010D
Cadmium, Total	EPA 6010C
	EPA 6010D
	EPA 6020A
	EPA 6020B
Calcium, Total	EPA 6010C
	EPA 6010D
Chromium, Total	EPA 6010C
	EPA 6010D

Serial No.: 71102

Property of the New York State Department of Health. Certificates are valid only at the address shown and must be conspicuously posted by the laboratory. Continued accreditation depends on the laboratory's successful ongoing participation in the Program. Consumers may verify a laboratory's accreditation status online at https://apps.health.ny.gov/pubdoh/applinks/wc/elappublicweb/, by phone (518) 485-5570 or by email to elap@health.ny.gov.

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER

Expires 12:01 AM April 01, 2026
Issued April 01, 2025
Revised June 13, 2025

CERTIFICATE OF APPROVAL FOR LABORATORY SERVICE

Issued in accordance with and pursuant to section 502 Public Health Law of New York State

MS. CATHERINE L. MOSHER
YORK ANALYTICAL LABORATORIES INC
120 RESEARCH DRIVE
STRATFORD, CT 06615

NY Lab Id No: 10854

is hereby APPROVED as an Environmental Laboratory in conformance with the National Environmental Laboratory Accreditation Conference Standards (2016) for the category ENVIRONMENTAL ANALYSES SOLID AND HAZARDOUS WASTE
All approved analytes are listed below:

Metals I

Chromium, Total	EPA 6020A
	EPA 6020B
Copper, Total	EPA 6010C
	EPA 6010D
	EPA 6020A
	EPA 6020B
Iron, Total	EPA 6010C
	EPA 6010D
Lead, Total	EPA 6010C
	EPA 6010D
Magnesium, Total	EPA 6010C
	EPA 6010D
Manganese, Total	EPA 6010C
	EPA 6010D
	EPA 6020A
	EPA 6020B
Nickel, Total	EPA 6010C
	EPA 6010D
	EPA 6020A
	EPA 6020B
Potassium, Total	EPA 6010C
	EPA 6010D
Silver, Total	EPA 6010C
	EPA 6010D
	EPA 6020A
	EPA 6020B
Sodium, Total	EPA 6010C

Serial No.: 71102

Property of the New York State Department of Health. Certificates are valid only at the address shown and must be conspicuously posted by the laboratory. Continued accreditation depends on the laboratory's successful ongoing participation in the Program. Consumers may verify a laboratory's accreditation status online at https://apps.health.ny.gov/pubdoh/applinks/wc/elappublicweb/, by phone (518) 485-5570 or by email to elap@health.ny.gov.

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER

Expires 12:01 AM April 01, 2026
Issued April 01, 2025
Revised June 13, 2025

CERTIFICATE OF APPROVAL FOR LABORATORY SERVICE

Issued in accordance with and pursuant to section 502 Public Health Law of New York State

MS. CATHERINE L. MOSHER
YORK ANALYTICAL LABORATORIES INC
120 RESEARCH DRIVE
STRATFORD, CT 06615

NY Lab Id No: 10854

is hereby APPROVED as an Environmental Laboratory in conformance with the National Environmental Laboratory Accreditation Conference Standards (2016) for the category ENVIRONMENTAL ANALYSES SOLID AND HAZARDOUS WASTE
All approved analytes are listed below:

Metals I

Sodium, Total	EPA 6010D

Metals II

Aluminum, Total	EPA 6010C
	EPA 6010D
	EPA 6020A
	EPA 6020B
Antimony, Total	EPA 6010C
	EPA 6010D
	EPA 6020A
	EPA 6020B
Arsenic, Total	EPA 6010C
	EPA 6010D
	EPA 6020A
	EPA 6020B
Beryllium, Total	EPA 6010C
	EPA 6010D
Chromium VI	EPA 7196A
Mercury, Total	EPA 7471B
	EPA 7473
Selenium, Total	EPA 6010C
	EPA 6010D
	EPA 6020A
	EPA 6020B
Vanadium, Total	EPA 6010C
	EPA 6010D
	EPA 6020A
	EPA 6020B

Serial No.: 71102

Property of the New York State Department of Health. Certificates are valid only at the address shown and must be conspicuously posted by the laboratory. Continued accreditation depends on the laboratory's successful ongoing participation in the Program. Consumers may verify a laboratory's accreditation status online at https://apps.health.ny.gov/pubdoh/applinks/wc/elappublicweb/, by phone (518) 485-5570 or by email to elap@health.ny.gov.

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER

Expires 12:01 AM April 01, 2026
Issued April 01, 2025
Revised June 13, 2025

CERTIFICATE OF APPROVAL FOR LABORATORY SERVICE

Issued in accordance with and pursuant to section 502 Public Health Law of New York State

MS. CATHERINE L. MOSHER
YORK ANALYTICAL LABORATORIES INC
120 RESEARCH DRIVE
STRATFORD, CT 06615

NY Lab Id No: 10854

is hereby APPROVED as an Environmental Laboratory in conformance with the National Environmental Laboratory Accreditation Conference Standards (2016) for the category ENVIRONMENTAL ANALYSES SOLID AND HAZARDOUS WASTE
All approved analytes are listed below:

Metals II	
Zinc, Total	EPA 6010C
	EPA 6010D
	EPA 6020A
	EPA 6020B
Metals III	
Cobalt, Total	EPA 6010C
	EPA 6010D
	EPA 6020A
	EPA 6020B
Thallium, Total	EPA 6010C
	EPA 6010D
Tin, Total	EPA 6020A
	EPA 6020B
Titanium, Total	EPA 6020A
Miscellaneous	
Cyanide, Total	EPA 9014
Nitroaromatics and Isophorone	
2,4-Dinitrotoluene	EPA 8270D
	EPA 8270E
2,6-Dinitrotoluene	EPA 8270D
	EPA 8270E
Isophorone	EPA 8270D
	EPA 8270E
Nitrobenzene	EPA 8270D
	EPA 8270E
Pyridine	EPA 8270D

Serial No.: 71102

Property of the New York State Department of Health. Certificates are valid only at the address shown and must be conspicuously posted by the laboratory. Continued accreditation depends on the laboratory's successful ongoing participation in the Program. Consumers may verify a laboratory's accreditation status online at https://apps.health.ny.gov/pubdoh/applinks/wc/elappublicweb/, by phone (518) 485-5570 or by email to elap@health.ny.gov.

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER

Expires 12:01 AM April 01, 2026
Issued April 01, 2025
Revised June 13, 2025

CERTIFICATE OF APPROVAL FOR LABORATORY SERVICE

Issued in accordance with and pursuant to section 502 Public Health Law of New York State

MS. CATHERINE L. MOSHER
YORK ANALYTICAL LABORATORIES INC
120 RESEARCH DRIVE
STRATFORD, CT 06615

NY Lab Id No: 10854

is hereby APPROVED as an Environmental Laboratory in conformance with the National Environmental Laboratory Accreditation Conference Standards (2016) for the category ENVIRONMENTAL ANALYSES SOLID AND HAZARDOUS WASTE
All approved analytes are listed below:

Nitroaromatics and Isophorone	
Pyridine	EPA 8270E
Nitrosoamines	
N-Nitrosodimethylamine	EPA 8270D
	EPA 8270E
N-Nitrosodi-n-propylamine	EPA 8270D
	EPA 8270E
N-Nitrosodiphenylamine	EPA 8270D
	EPA 8270E
Organophosphate Pesticides	
Parathion ethyl	EPA 8270D
	EPA 8270E
Petroleum Hydrocarbons	
Diesel Range Organics	EPA 8015D
Gasoline Range Organics	EPA 8015D
Phthalate Esters	
Benzyl butyl phthalate	EPA 8270D
	EPA 8270E
Bis(2-ethylhexyl) phthalate	EPA 8270D
	EPA 8270E
Diethyl phthalate	EPA 8270D
	EPA 8270E
Dimethyl phthalate	EPA 8270D
	EPA 8270E
Di-n-butyl phthalate	EPA 8270D
	EPA 8270E
Di-n-octyl phthalate	EPA 8270D

Serial No.: 71102

Property of the New York State Department of Health. Certificates are valid only at the address shown and must be conspicuously posted by the laboratory. Continued accreditation depends on the laboratory's successful ongoing participation in the Program. Consumers may verify a laboratory's accreditation status online at https://apps.health.ny.gov/pubdoh/applinks/wc/elappublicweb/, by phone (518) 485-5570 or by email to elap@health.ny.gov.

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER

Expires 12:01 AM April 01, 2026
Issued April 01, 2025
Revised June 13, 2025

CERTIFICATE OF APPROVAL FOR LABORATORY SERVICE

Issued in accordance with and pursuant to section 502 Public Health Law of New York State

MS. CATHERINE L. MOSHER
YORK ANALYTICAL LABORATORIES INC
120 RESEARCH DRIVE
STRATFORD, CT 06615

NY Lab Id No: 10854

is hereby APPROVED as an Environmental Laboratory in conformance with the National Environmental Laboratory Accreditation Conference Standards (2016) for the category ENVIRONMENTAL ANALYSES SOLID AND HAZARDOUS WASTE
All approved analytes are listed below:

Phthalate Esters

Di-n-octyl phthalate	EPA 8270E

Polychlorinated Biphenyls

Aroclor 1016 (PCB-1016)	EPA 8082A
Aroclor 1016 (PCB-1016) in Oil	EPA 8082A
Aroclor 1221 (PCB-1221)	EPA 8082A
Aroclor 1221 (PCB-1221) in Oil	EPA 8082A
Aroclor 1232 (PCB-1232)	EPA 8082A
Aroclor 1232 (PCB-1232) in Oil	EPA 8082A
Aroclor 1242 (PCB-1242)	EPA 8082A
Aroclor 1242 (PCB-1242) in Oil	EPA 8082A
Aroclor 1248 (PCB-1248)	EPA 8082A
Aroclor 1248 (PCB-1248) in Oil	EPA 8082A
Aroclor 1254 (PCB-1254)	EPA 8082A
Aroclor 1254 (PCB-1254) in Oil	EPA 8082A
Aroclor 1260 (PCB-1260)	EPA 8082A
Aroclor 1260 (PCB-1260) in Oil	EPA 8082A
Aroclor 1262 (PCB-1262)	EPA 8082A
Aroclor 1262 (PCB-1262) in Oil	EPA 8082A
Aroclor 1268 (PCB-1268)	EPA 8082A
Aroclor 1268 (PCB-1268) in Oil	EPA 8082A

Polynuclear Aromatic Hydrocarbons

Acenaphthene	EPA 8270D
	EPA 8270E
Acenaphthylene	EPA 8270D
	EPA 8270E
Anthracene	EPA 8270D

Serial No.: 71102

Property of the New York State Department of Health. Certificates are valid only at the address shown and must be conspicuously posted by the laboratory. Continued accreditation depends on the laboratory's successful ongoing participation in the Program. Consumers may verify a laboratory's accreditation status online at https://apps.health.ny.gov/pubdoh/applinks/wc/elappublicweb/, by phone (518) 485-5570 or by email to elap@health.ny.gov.

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER

Expires 12:01 AM April 01, 2026
Issued April 01, 2025
Revised June 13, 2025

CERTIFICATE OF APPROVAL FOR LABORATORY SERVICE

Issued in accordance with and pursuant to section 502 Public Health Law of New York State

MS. CATHERINE L. MOSHER
YORK ANALYTICAL LABORATORIES INC
120 RESEARCH DRIVE
STRATFORD, CT 06615

NY Lab Id No: 10854

is hereby APPROVED as an Environmental Laboratory in conformance with the National Environmental Laboratory Accreditation Conference Standards (2016) for the category ENVIRONMENTAL ANALYSES SOLID AND HAZARDOUS WASTE
All approved analytes are listed below:

Polynuclear Aromatic Hydrocarbons

Anthracene	EPA 8270E
Benzo(a)anthracene	EPA 8270D
	EPA 8270E
Benzo(a)pyrene	EPA 8270D
	EPA 8270E
Benzo(b)fluoranthene	EPA 8270D
	EPA 8270E
Benzo(g,h,i)perylene	EPA 8270D
	EPA 8270E
Benzo(k)fluoranthene	EPA 8270D
	EPA 8270E
Chrysene	EPA 8270D
	EPA 8270E
Dibenzo(a,h)anthracene	EPA 8270D
	EPA 8270E
Fluoranthene	EPA 8270D
	EPA 8270E
Fluorene	EPA 8270D
	EPA 8270E
Indeno(1,2,3-cd)pyrene	EPA 8270D
	EPA 8270E
Naphthalene	EPA 8270D
	EPA 8270E
Phenanthrene	EPA 8270D
	EPA 8270E
Pyrene	EPA 8270D
	EPA 8270E

Serial No.: 71102

Property of the New York State Department of Health. Certificates are valid only at the address shown and must be conspicuously posted by the laboratory. Continued accreditation depends on the laboratory's successful ongoing participation in the Program. Consumers may verify a laboratory's accreditation status online at https://apps.health.ny.gov/pubdoh/applinks/wc/elappublicweb/, by phone (518) 485-5570 or by email to elap@health.ny.gov.

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER

Expires 12:01 AM April 01, 2026
Issued April 01, 2025
Revised June 13, 2025

CERTIFICATE OF APPROVAL FOR LABORATORY SERVICE

Issued in accordance with and pursuant to section 502 Public Health Law of New York State

MS. CATHERINE L. MOSHER
YORK ANALYTICAL LABORATORIES INC
120 RESEARCH DRIVE
STRATFORD, CT 06615

NY Lab Id No: 10854

is hereby APPROVED as an Environmental Laboratory in conformance with the National Environmental Laboratory Accreditation Conference Standards (2016) for the category ENVIRONMENTAL ANALYSES SOLID AND HAZARDOUS WASTE
All approved analytes are listed below:

Priority Pollutant Phenols

2,3,4,6 Tetrachlorophenol	EPA 8270D
	EPA 8270E
2,4,5-Trichlorophenol	EPA 8270D
	EPA 8270E
2,4,6-Trichlorophenol	EPA 8270D
	EPA 8270E
2,4-Dichlorophenol	EPA 8270D
	EPA 8270E
2,4-Dimethylphenol	EPA 8270D
	EPA 8270E
2,4-Dinitrophenol	EPA 8270D
	EPA 8270E
2-Chlorophenol	EPA 8270D
	EPA 8270E
2-Methyl-4,6-dinitrophenol	EPA 8270D
	EPA 8270E
2-Methylphenol	EPA 8270D
	EPA 8270E
2-Nitrophenol	EPA 8270D
	EPA 8270E
4-Chloro-3-methylphenol	EPA 8270D
	EPA 8270E
4-Methylphenol	EPA 8270D
	EPA 8270E
4-Nitrophenol	EPA 8270D
	EPA 8270E
Pentachlorophenol	EPA 8270D

Serial No.: 71102

Property of the New York State Department of Health. Certificates are valid only at the address shown and must be conspicuously posted by the laboratory. Continued accreditation depends on the laboratory's successful ongoing participation in the Program. Consumers may verify a laboratory's accreditation status online at https://apps.health.ny.gov/pubdoh/applinks/wc/elappublicweb/, by phone (518) 485-5570 or by email to elap@health.ny.gov.

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER

Expires 12:01 AM April 01, 2026
Issued April 01, 2025
Revised June 13, 2025

CERTIFICATE OF APPROVAL FOR LABORATORY SERVICE

Issued in accordance with and pursuant to section 502 Public Health Law of New York State

MS. CATHERINE L. MOSHER
YORK ANALYTICAL LABORATORIES INC
120 RESEARCH DRIVE
STRATFORD, CT 06615

NY Lab Id No: 10854

is hereby APPROVED as an Environmental Laboratory in conformance with the National Environmental Laboratory Accreditation Conference Standards (2016) for the category ENVIRONMENTAL ANALYSES SOLID AND HAZARDOUS WASTE
All approved analytes are listed below:

Priority Pollutant Phenols

Pentachlorophenol	EPA 8270E
Phenol	EPA 8270D
	EPA 8270E

Semi-Volatile Organics

1,1'-Biphenyl	EPA 8270D
	EPA 8270E
1,2-Dichlorobenzene, Semi-volatile	EPA 8270D
	EPA 8270E
1,3-Dichlorobenzene, Semi-volatile	EPA 8270D
	EPA 8270E
1,4-Dichlorobenzene, Semi-volatile	EPA 8270D
	EPA 8270E
2-Methylnaphthalene	EPA 8270D
	EPA 8270E
Acetophenone	EPA 8270D
	EPA 8270E
Benzaldehyde	EPA 8270D
	EPA 8270E
Benzoic Acid	EPA 8270D
	EPA 8270E
Benzyl alcohol	EPA 8270D
	EPA 8270E
Caprolactam	EPA 8270D
	EPA 8270E
Dibenzofuran	EPA 8270D
	EPA 8270E

Serial No.: 71102

Property of the New York State Department of Health. Certificates are valid only at the address shown and must be conspicuously posted by the laboratory. Continued accreditation depends on the laboratory's successful ongoing participation in the Program. Consumers may verify a laboratory's accreditation status online at https://apps.health.ny.gov/pubdoh/applinks/wc/elappublicweb/, by phone (518) 485-5570 or by email to elap@health.ny.gov.

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER

Expires 12:01 AM April 01, 2026
Issued April 01, 2025
Revised June 13, 2025

CERTIFICATE OF APPROVAL FOR LABORATORY SERVICE

Issued in accordance with and pursuant to section 502 Public Health Law of New York State

MS. CATHERINE L. MOSHER
YORK ANALYTICAL LABORATORIES INC
120 RESEARCH DRIVE
STRATFORD, CT 06615

NY Lab Id No: 10854

is hereby APPROVED as an Environmental Laboratory in conformance with the National Environmental Laboratory Accreditation Conference Standards (2016) for the category ENVIRONMENTAL ANALYSES SOLID AND HAZARDOUS WASTE
All approved analytes are listed below:

Volatile Aromatics

1,2,4-Trichlorobenzene, Volatile	EPA 8260D
	EPA 8260C
1,2,4-Trimethylbenzene	EPA 8260D
	EPA 8260C
1,2-Dichlorobenzene	EPA 8260D
	EPA 8260C
1,3,5-Trimethylbenzene	EPA 8260D
	EPA 8260C
1,3-Dichlorobenzene	EPA 8260D
	EPA 8260C
1,4-Dichlorobenzene	EPA 8260D
	EPA 8260C
2-Chlorotoluene	EPA 8260D
	EPA 8260C
4-Chlorotoluene	EPA 8260D
	EPA 8260C
Benzene	EPA 8260D
	EPA 8260C
Bromobenzene	EPA 8260D
	EPA 8260C
Chlorobenzene	EPA 8260D
	EPA 8260C
Ethyl benzene	EPA 8260D
	EPA 8260C
Isopropylbenzene	EPA 8260D
	EPA 8260C
m/p-Xylenes	EPA 8260D

Serial No.: 71102

Property of the New York State Department of Health. Certificates are valid only at the address shown and must be conspicuously posted by the laboratory. Continued accreditation depends on the laboratory's successful ongoing participation in the Program. Consumers may verify a laboratory's accreditation status online at https://apps.health.ny.gov/pubdoh/applinks/wc/elappublicweb/, by phone (518) 485-5570 or by email to elap@health.ny.gov.

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER

Expires 12:01 AM April 01, 2026
Issued April 01, 2025
Revised June 13, 2025

CERTIFICATE OF APPROVAL FOR LABORATORY SERVICE

Issued in accordance with and pursuant to section 502 Public Health Law of New York State

MS. CATHERINE L. MOSHER
YORK ANALYTICAL LABORATORIES INC
120 RESEARCH DRIVE
STRATFORD, CT 06615

NY Lab Id No: 10854

is hereby APPROVED as an Environmental Laboratory in conformance with the National Environmental Laboratory Accreditation Conference Standards (2016) for the category ENVIRONMENTAL ANALYSES SOLID AND HAZARDOUS WASTE
All approved analytes are listed below:

Volatile Aromatics

m/p-Xylenes	EPA 8260C
Naphthalene, Volatile	EPA 8260D
	EPA 8260C
n-Butylbenzene	EPA 8260D
	EPA 8260C
n-Propylbenzene	EPA 8260D
	EPA 8260C
o-Xylene	EPA 8260D
	EPA 8260C
p-Isopropyltoluene (P-Cymene)	EPA 8260D
	EPA 8260C
sec-Butylbenzene	EPA 8260D
	EPA 8260C
Styrene	EPA 8260D
	EPA 8260C
tert-Butylbenzene	EPA 8260D
	EPA 8260C
Toluene	EPA 8260D
	EPA 8260C
Total Xylenes	EPA 8260D
	EPA 8260C

Volatile Halocarbons

1,1,1,2-Tetrachloroethane	EPA 8260D
	EPA 8260C
1,1,1-Trichloroethane	EPA 8260D
	EPA 8260C
1,1,2,2-Tetrachloroethane	EPA 8260D

Serial No.: 71102

Property of the New York State Department of Health. Certificates are valid only at the address shown and must be conspicuously posted by the laboratory. Continued accreditation depends on the laboratory's successful ongoing participation in the Program. Consumers may verify a laboratory's accreditation status online at https://apps.health.ny.gov/pubdoh/applinks/wc/elappublicweb/, by phone (518) 485-5570 or by email to elap@health.ny.gov.

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER

Expires 12:01 AM April 01, 2026
Issued April 01, 2025
Revised June 13, 2025

CERTIFICATE OF APPROVAL FOR LABORATORY SERVICE

Issued in accordance with and pursuant to section 502 Public Health Law of New York State

MS. CATHERINE L. MOSHER
YORK ANALYTICAL LABORATORIES INC
120 RESEARCH DRIVE
STRATFORD, CT 06615

NY Lab Id No: 10854

is hereby APPROVED as an Environmental Laboratory in conformance with the National Environmental Laboratory Accreditation Conference Standards (2016) for the category ENVIRONMENTAL ANALYSES SOLID AND HAZARDOUS WASTE
All approved analytes are listed below:

Volatile Halocarbons

1,1,2,2-Tetrachloroethane	EPA 8260C
1,1,2-Trichloro-1,2,2-Trifluoroethane	EPA 8260D
	EPA 8260C
1,1,2-Trichloroethane	EPA 8260D
	EPA 8260C
1,1-Dichloroethane	EPA 8260D
	EPA 8260C
1,1-Dichloroethene	EPA 8260D
	EPA 8260C
1,1-Dichloropropene	EPA 8260D
	EPA 8260C
1,2,3-Trichloropropane	EPA 8260D
	EPA 8260C
1,2-Dibromo-3-chloropropane	EPA 8260D
	EPA 8260C
1,2-Dibromoethane	EPA 8260D
	EPA 8260C
1,2-Dichloroethane	EPA 8260D
	EPA 8260C
1,2-Dichloropropane	EPA 8260D
	EPA 8260C
1,3-Dichloropropane	EPA 8260D
	EPA 8260C
2,2-Dichloropropane	EPA 8260D
	EPA 8260C
2-Chloroethylvinyl ether	EPA 8260D
	EPA 8260C

Serial No.: 71102

Property of the New York State Department of Health. Certificates are valid only at the address shown and must be conspicuously posted by the laboratory. Continued accreditation depends on the laboratory's successful ongoing participation in the Program. Consumers may verify a laboratory's accreditation status online at https://apps.health.ny.gov/pubdoh/applinks/wc/elappublicweb/, by phone (518) 485-5570 or by email to elap@health.ny.gov.

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER

Expires 12:01 AM April 01, 2026
Issued April 01, 2025
Revised June 13, 2025

CERTIFICATE OF APPROVAL FOR LABORATORY SERVICE

Issued in accordance with and pursuant to section 502 Public Health Law of New York State

MS. CATHERINE L. MOSHER
YORK ANALYTICAL LABORATORIES INC
120 RESEARCH DRIVE
STRATFORD, CT 06615

NY Lab Id No: 10854

is hereby APPROVED as an Environmental Laboratory in conformance with the National Environmental Laboratory Accreditation Conference Standards (2016) for the category ENVIRONMENTAL ANALYSES SOLID AND HAZARDOUS WASTE
All approved analytes are listed below:

Volatile Halocarbons

Bromochloromethane	EPA 8260D
	EPA 8260C
Bromodichloromethane	EPA 8260D
	EPA 8260C
Bromoform	EPA 8260D
	EPA 8260C
Bromomethane	EPA 8260D
	EPA 8260C
Carbon tetrachloride	EPA 8260D
	EPA 8260C
Chloroethane	EPA 8260D
	EPA 8260C
Chloroform	EPA 8260D
	EPA 8260C
Chloromethane	EPA 8260D
	EPA 8260C
cis-1,2-Dichloroethene	EPA 8260D
	EPA 8260C
cis-1,3-Dichloropropene	EPA 8260D
	EPA 8260C
Dibromochloromethane	EPA 8260D
	EPA 8260C
Dibromomethane	EPA 8260D
	EPA 8260C
Dichlorodifluoromethane	EPA 8260D
	EPA 8260C
Hexachlorobutadiene, Volatile	EPA 8260D

Serial No.: 71102

Property of the New York State Department of Health. Certificates are valid only at the address shown and must be conspicuously posted by the laboratory. Continued accreditation depends on the laboratory's successful ongoing participation in the Program. Consumers may verify a laboratory's accreditation status online at https://apps.health.ny.gov/pubdoh/applinks/wc/elappublicweb/, by phone (518) 485-5570 or by email to elap@health.ny.gov.

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER

Expires 12:01 AM April 01, 2026
Issued April 01, 2025
Revised June 13, 2025

CERTIFICATE OF APPROVAL FOR LABORATORY SERVICE

Issued in accordance with and pursuant to section 502 Public Health Law of New York State

MS. CATHERINE L. MOSHER
YORK ANALYTICAL LABORATORIES INC
120 RESEARCH DRIVE
STRATFORD, CT 06615

NY Lab Id No: 10854

is hereby APPROVED as an Environmental Laboratory in conformance with the National Environmental Laboratory Accreditation Conference Standards (2016) for the category ENVIRONMENTAL ANALYSES SOLID AND HAZARDOUS WASTE
All approved analytes are listed below:

Volatile Halocarbons

Hexachlorobutadiene, Volatile	EPA 8260C
Methylene chloride	EPA 8260D
	EPA 8260C
Tetrachloroethene	EPA 8260D
	EPA 8260C
trans-1,2-Dichloroethene	EPA 8260D
	EPA 8260C
trans-1,3-Dichloropropene	EPA 8260D
	EPA 8260C
Trichloroethene	EPA 8260D
	EPA 8260C
Trichlorofluoromethane	EPA 8260D
	EPA 8260C
Vinyl chloride	EPA 8260D
	EPA 8260C

Volatile Organics

1,4-Dioxane	EPA 8260D
	EPA 8260C
	EPA 8270D SIM
	EPA 8270E
	EPA 8270E SIM
2-Butanone (Methylethyl ketone)	EPA 8260D
	EPA 8260C
2-Hexanone	EPA 8260D
	EPA 8260C
4-Methyl-2-Pentanone	EPA 8260D
	EPA 8260C

Serial No.: 71102

Property of the New York State Department of Health. Certificates are valid only at the address shown and must be conspicuously posted by the laboratory. Continued accreditation depends on the laboratory's successful ongoing participation in the Program. Consumers may verify a laboratory's accreditation status online at https://apps.health.ny.gov/pubdoh/applinks/wc/elappublicweb/, by phone (518) 485-5570 or by email to elap@health.ny.gov.

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER

Expires 12:01 AM April 01, 2026
Issued April 01, 2025
Revised June 13, 2025

CERTIFICATE OF APPROVAL FOR LABORATORY SERVICE

Issued in accordance with and pursuant to section 502 Public Health Law of New York State

MS. CATHERINE L. MOSHER
YORK ANALYTICAL LABORATORIES INC
120 RESEARCH DRIVE
STRATFORD, CT 06615

NY Lab Id No: 10854

is hereby APPROVED as an Environmental Laboratory in conformance with the National Environmental Laboratory Accreditation Conference Standards (2016) for the category ENVIRONMENTAL ANALYSES SOLID AND HAZARDOUS WASTE
All approved analytes are listed below:

Volatile Organics

Acetone	EPA 8260D
	EPA 8260C
Carbon Disulfide	EPA 8260D
	EPA 8260C
Cyclohexane	EPA 8260D
	EPA 8260C
Methyl acetate	EPA 8260D
	EPA 8260C
Methyl cyclohexane	EPA 8260D
	EPA 8260C
Methyl tert-butyl ether	EPA 8260D
	EPA 8260C
tert-butyl alcohol	EPA 8260D
	EPA 8260C
Vinyl acetate	EPA 8260D
	EPA 8260C

Sample Preparation Methods

EPA 5035A-L
EPA 5035A-H
EPA 3580A
EPA 3010A
EPA 3050B
EPA 3550C
EPA 3546
EPA 3545A
EPA 3060A
EPA 9010C

Serial No.: 71102

Property of the New York State Department of Health. Certificates are valid only at the address shown and must be conspicuously posted by the laboratory. Continued accreditation depends on the laboratory's successful ongoing participation in the Program. Consumers may verify a laboratory's accreditation status online at https://apps.health.ny.gov/pubdoh/applinks/wc/elappublicweb/, by phone (518) 485-5570 or by email to elap@health.ny.gov.

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER

Expires 12:01 AM April 01, 2026
Issued April 01, 2025
Revised April 16, 2025

CERTIFICATE OF APPROVAL FOR LABORATORY SERVICE

Issued in accordance with and pursuant to section 502 Public Health Law of New York State

JAMES DODSWORTH
YORK ANALYTICAL LABORATORIES, INC. (II)
132-02 89TH AVENUE SUITE 217
RICHMOND HILL, NY 11418

NY Lab Id No: 12058

is hereby APPROVED as an Environmental Laboratory in conformance with the National Environmental Laboratory Accreditation Conference Standards (2016) for the category ENVIRONMENTAL ANALYSES AIR AND EMISSIONS
All approved analytes are listed below:

Acrylates

Acrylonitrile	EPA TO-15
Methyl methacrylate	EPA TO-15

Chlorinated Hydrocarbons

1,2,4-Trichlorobenzene	EPA TO-15
Hexachlorobutadiene	EPA TO-15
Hexachloroethane	EPA TO-15

Purgeable Aromatics

1,2,4-Trimethylbenzene	EPA TO-15
1,2-Dichlorobenzene	EPA TO-15
1,3,5-Trimethylbenzene	EPA TO-15
1,3-Dichlorobenzene	EPA TO-15
1,4-Dichlorobenzene	EPA TO-15
Benzene	EPA TO-15
Chlorobenzene	EPA TO-15
Ethyl benzene	EPA TO-15
Isopropylbenzene	EPA TO-15
m/p-Xylenes	EPA TO-15
o-Xylene	EPA TO-15
Styrene	EPA TO-15
Toluene	EPA TO-15
Total Xylenes	EPA TO-15

Purgeable Halocarbons

1,1,1-Trichloroethane	EPA TO-15
1,1,2,2-Tetrachloroethane	EPA TO-15
1,1,2-Trichloro-1,2,2-Trifluoroethane	EPA TO-15
1,1,2-Trichloroethane	EPA TO-15

Serial No.: 70994

Property of the New York State Department of Health. Certificates are valid only at the address shown and must be conspicuously posted by the laboratory. Continued accreditation depends on the laboratory's successful ongoing participation in the Program. Consumers may verify a laboratory's accreditation status online at https://apps.health.ny.gov/pubdoh/applinks/wc/elappublicweb/, by phone (518) 485-5570 or by email to elap@health.ny.gov.

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER

Expires 12:01 AM April 01, 2026
Issued April 01, 2025
Revised April 16, 2025

CERTIFICATE OF APPROVAL FOR LABORATORY SERVICE

Issued in accordance with and pursuant to section 502 Public Health Law of New York State

JAMES DODSWORTH
YORK ANALYTICAL LABORATORIES, INC. (II)
132-02 89TH AVENUE SUITE 217
RICHMOND HILL, NY 11418

NY Lab Id No: 12058

is hereby APPROVED as an Environmental Laboratory in conformance with the National Environmental Laboratory Accreditation Conference Standards (2016) for the category ENVIRONMENTAL ANALYSES AIR AND EMISSIONS
All approved analytes are listed below:

Purgeable Halocarbons

1,1-Dichloroethane	EPA TO-15
1,1-Dichloroethene	EPA TO-15
1,2-Dibromoethane	EPA TO-15
1,2-Dichloroethane	EPA TO-15
1,2-Dichloropropane	EPA TO-15
3-Chloropropene (Allyl chloride)	EPA TO-15
Bromodichloromethane	EPA TO-15
Bromoform	EPA TO-15
Bromomethane	EPA TO-15
Carbon tetrachloride	EPA TO-15
Chloroethane	EPA TO-15
Chloroform	EPA TO-15
Chloromethane	EPA TO-15
cis-1,2-Dichloroethene	EPA TO-15
cis-1,3-Dichloropropene	EPA TO-15
Dibromochloromethane	EPA TO-15
Dichlorodifluoromethane	EPA TO-15
Methylene chloride	EPA TO-15
Tetrachloroethene	EPA TO-15
trans-1,2-Dichloroethene	EPA TO-15
trans-1,3-Dichloropropene	EPA TO-15
Trichloroethene	EPA TO-15
Trichlorofluoromethane	EPA TO-15
Vinyl bromide	EPA TO-15
Vinyl chloride	EPA TO-15

Volatile Chlorinated Organics

Benzyl chloride	EPA TO-15

Serial No.: 70994

Property of the New York State Department of Health. Certificates are valid only at the address shown and must be conspicuously posted by the laboratory. Continued accreditation depends on the laboratory's successful ongoing participation in the Program. Consumers may verify a laboratory's accreditation status online at https://apps.health.ny.gov/pubdoh/applinks/wc/elappublicweb/, by phone (518) 485-5570 or by email to elap@health.ny.gov.

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER

Expires 12:01 AM April 01, 2026
Issued April 01, 2025
Revised April 16, 2025

CERTIFICATE OF APPROVAL FOR LABORATORY SERVICE

Issued in accordance with and pursuant to section 502 Public Health Law of New York State

JAMES DODSWORTH *NY Lab Id No: 12058*
YORK ANALYTICAL LABORATORIES, INC. (II)
132-02 89TH AVENUE SUITE 217
RICHMOND HILL, NY 11418

is hereby APPROVED as an Environmental Laboratory in conformance with the National Environmental Laboratory Accreditation Conference Standards (2016) for the category ENVIRONMENTAL ANALYSES AIR AND EMISSIONS
All approved analytes are listed below:

Volatile Organics

1,2-Dichlorotetrafluoroethane	EPA TO-15
1,3-Butadiene	EPA TO-15
1,4-Dioxane	EPA TO-15
2-Butanone (Methylethyl ketone)	EPA TO-15
4-Methyl-2-Pentanone	EPA TO-15
Acetone	EPA TO-15
Carbon Disulfide	EPA TO-15
Cyclohexane	EPA TO-15
Hexane	EPA TO-15
Isopropanol	EPA TO-15
Methyl tert-butyl ether	EPA TO-15
n-Heptane	EPA TO-15
Vinyl acetate	EPA TO-15

Serial No.: 70994

Property of the New York State Department of Health. Certificates are valid only at the address shown and must be conspicuously posted by the laboratory. Continued accreditation depends on the laboratory's successful ongoing participation in the Program. Consumers may verify a laboratory's accreditation status online at https://apps.health.ny.gov/pubdoh/applinks/wc/elappublicweb/, by phone (518) 485-5570 or by email to elap@health.ny.gov.

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER

Expires 12:01 AM April 01, 2026
Issued April 01, 2025
Revised April 16, 2025

CERTIFICATE OF APPROVAL FOR LABORATORY SERVICE

Issued in accordance with and pursuant to section 502 Public Health Law of New York State

JAMES DODSWORTH
YORK ANALYTICAL LABORATORIES, INC. (II)
132-02 89TH AVENUE SUITE 217
RICHMOND HILL, NY 11418

NY Lab Id No: 12058

is hereby APPROVED as an Environmental Laboratory in conformance with the National Environmental Laboratory Accreditation Conference Standards (2016) for the category ENVIRONMENTAL ANALYSES NON POTABLE WATER
All approved analytes are listed below:

Acrylates	
Acrolein (Propenal)	EPA 8260D
	EPA 8260C
Acrylonitrile	EPA 8260D
	EPA 8260C
Methyl methacrylate	EPA 8260D
	EPA 8260C
Chlorinated Hydrocarbons	
1,2,3-Trichlorobenzene	EPA 8260D
	EPA 8260C
Fuel Oxygenates	
Di-isopropyl ether	EPA 8260D
	EPA 8260C
Ethanol	EPA 8260D
	EPA 8260C
Methyl tert-butyl ether	EPA 8260D
	EPA 8260C
tert-amyl alcohol	EPA 8260D
	EPA 8260C
tert-amyl methyl ether (TAME)	EPA 8260D
	EPA 8260C
tert-butyl alcohol	EPA 8260D
	EPA 8260C
tert-butyl ethyl ether (ETBE)	EPA 8260D
	EPA 8260C
Volatile Aromatics	
1,2,4-Trichlorobenzene, Volatile	EPA 8260D

Serial No.: 70990

Property of the New York State Department of Health. Certificates are valid only at the address shown and must be conspicuously posted by the laboratory. Continued accreditation depends on the laboratory's successful ongoing participation in the Program. Consumers may verify a laboratory's accreditation status online at https://apps.health.ny.gov/pubdoh/applinks/wc/elappublicweb/, by phone (518) 485-5570 or by email to elap@health.ny.gov.

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER

Expires 12:01 AM April 01, 2026
Issued April 01, 2025
Revised April 16, 2025

CERTIFICATE OF APPROVAL FOR LABORATORY SERVICE

Issued in accordance with and pursuant to section 502 Public Health Law of New York State

JAMES DODSWORTH *NY Lab Id No: 12058*
YORK ANALYTICAL LABORATORIES, INC. (II)
132-02 89TH AVENUE SUITE 217
RICHMOND HILL, NY 11418

is hereby APPROVED as an Environmental Laboratory in conformance with the National Environmental Laboratory Accreditation Conference Standards (2016) for the category ENVIRONMENTAL ANALYSES NON POTABLE WATER
All approved analytes are listed below:

Volatile Aromatics

1,2,4-Trichlorobenzene, Volatile	EPA 8260C
1,2,4-Trimethylbenzene	EPA 8260D
	EPA 8260C
1,2-Dichlorobenzene	EPA 8260D
	EPA 8260C
1,3,5-Trimethylbenzene	EPA 8260D
	EPA 8260C
1,3-Dichlorobenzene	EPA 8260D
	EPA 8260C
1,4-Dichlorobenzene	EPA 8260D
	EPA 8260C
2-Chlorotoluene	EPA 8260D
	EPA 8260C
4-Chlorotoluene	EPA 8260D
	EPA 8260C
Benzene	EPA 8260D
	EPA 8260C
Bromobenzene	EPA 8260D
	EPA 8260C
Chlorobenzene	EPA 8260D
	EPA 8260C
Ethyl benzene	EPA 8260D
	EPA 8260C
Isopropylbenzene	EPA 8260D
	EPA 8260C
m/p-Xylenes	EPA 8260D
	EPA 8260C

Serial No.: 70990

Property of the New York State Department of Health. Certificates are valid only at the address shown and must be conspicuously posted by the laboratory. Continued accreditation depends on the laboratory's successful ongoing participation in the Program. Consumers may verify a laboratory's accreditation status online at https://apps.health.ny.gov/pubdoh/applinks/wc/elappublicweb/, by phone (518) 485-5570 or by email to elap@health.ny.gov.

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER

Expires 12:01 AM April 01, 2026
Issued April 01, 2025
Revised April 16, 2025

CERTIFICATE OF APPROVAL FOR LABORATORY SERVICE

Issued in accordance with and pursuant to section 502 Public Health Law of New York State

JAMES DODSWORTH *NY Lab Id No: 12058*
YORK ANALYTICAL LABORATORIES, INC. (II)
132-02 89TH AVENUE SUITE 217
RICHMOND HILL, NY 11418

is hereby APPROVED as an Environmental Laboratory in conformance with the National Environmental Laboratory Accreditation Conference Standards (2016) for the category ENVIRONMENTAL ANALYSES NON POTABLE WATER
All approved analytes are listed below:

Volatile Aromatics

Naphthalene, Volatile	EPA 8260D
	EPA 8260C
n-Butylbenzene	EPA 8260D
	EPA 8260C
n-Propylbenzene	EPA 8260D
	EPA 8260C
o-Xylene	EPA 8260D
	EPA 8260C
p-Isopropyltoluene (P-Cymene)	EPA 8260D
	EPA 8260C
sec-Butylbenzene	EPA 8260D
	EPA 8260C
Styrene	EPA 8260D
	EPA 8260C
tert-Butylbenzene	EPA 8260D
	EPA 8260C
Toluene	EPA 8260D
	EPA 8260C
Total Xylenes	EPA 8260D
	EPA 8260C

Volatile Halocarbons

1,1,1,2-Tetrachloroethane	EPA 8260D
	EPA 8260C
1,1,1-Trichloroethane	EPA 8260D
	EPA 8260C
1,1,2,2-Tetrachloroethane	EPA 8260D
	EPA 8260C

Serial No.: 70990

Property of the New York State Department of Health. Certificates are valid only at the address shown and must be conspicuously posted by the laboratory. Continued accreditation depends on the laboratory's successful ongoing participation in the Program. Consumers may verify a laboratory's accreditation status online at https://apps.health.ny.gov/pubdoh/applinks/wc/elappublicweb/, by phone (518) 485-5570 or by email to elap@health.ny.gov.

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER

Expires 12:01 AM April 01, 2026
Issued April 01, 2025
Revised April 16, 2025

CERTIFICATE OF APPROVAL FOR LABORATORY SERVICE

Issued in accordance with and pursuant to section 502 Public Health Law of New York State

JAMES DODSWORTH
YORK ANALYTICAL LABORATORIES, INC. (II)
132-02 89TH AVENUE SUITE 217
RICHMOND HILL, NY 11418

NY Lab Id No: 12058

is hereby APPROVED as an Environmental Laboratory in conformance with the National Environmental Laboratory Accreditation Conference Standards (2016) for the category ENVIRONMENTAL ANALYSES NON POTABLE WATER
All approved analytes are listed below:

Volatile Halocarbons

1,1,2-Trichloro-1,2,2-Trifluoroethane	EPA 8260D
	EPA 8260C
1,1,2-Trichloroethane	EPA 8260D
	EPA 8260C
1,1-Dichloroethane	EPA 8260D
	EPA 8260C
1,1-Dichloroethene	EPA 8260D
	EPA 8260C
1,1-Dichloropropene	EPA 8260D
	EPA 8260C
1,2,3-Trichloropropane	EPA 8260D
	EPA 8260C
1,2-Dibromo-3-chloropropane	EPA 8260D
	EPA 8260C
1,2-Dibromoethane	EPA 8260D
	EPA 8260C
1,2-Dichloroethane	EPA 8260D
	EPA 8260C
1,2-Dichloropropane	EPA 8260D
	EPA 8260C
1,3-Dichloropropane	EPA 8260D
	EPA 8260C
2,2-Dichloropropane	EPA 8260D
	EPA 8260C
2-Chloroethylvinyl ether	EPA 8260D
	EPA 8260C
Bromochloromethane	EPA 8260D

Serial No.: 70990

Property of the New York State Department of Health. Certificates are valid only at the address shown and must be conspicuously posted by the laboratory. Continued accreditation depends on the laboratory's successful ongoing participation in the Program. Consumers may verify a laboratory's accreditation status online at https://apps.health.ny.gov/pubdoh/applinks/wc/elappublicweb/, by phone (518) 485-5570 or by email to elap@health.ny.gov.

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER

Expires 12:01 AM April 01, 2026
Issued April 01, 2025
Revised April 16, 2025

CERTIFICATE OF APPROVAL FOR LABORATORY SERVICE

Issued in accordance with and pursuant to section 502 Public Health Law of New York State

JAMES DODSWORTH
YORK ANALYTICAL LABORATORIES, INC. (II)
132-02 89TH AVENUE SUITE 217
RICHMOND HILL, NY 11418

NY Lab Id No: 12058

is hereby APPROVED as an Environmental Laboratory in conformance with the National Environmental Laboratory Accreditation Conference Standards (2016) for the category ENVIRONMENTAL ANALYSES NON POTABLE WATER
All approved analytes are listed below:

Volatile Halocarbons

Bromochloromethane	EPA 8260C
Bromodichloromethane	EPA 8260D
	EPA 8260C
Bromoform	EPA 8260D
	EPA 8260C
Bromomethane	EPA 8260D
	EPA 8260C
Carbon tetrachloride	EPA 8260D
	EPA 8260C
Chloroethane	EPA 8260D
	EPA 8260C
Chloroform	EPA 8260D
	EPA 8260C
Chloromethane	EPA 8260D
	EPA 8260C
cis-1,2-Dichloroethene	EPA 8260D
	EPA 8260C
cis-1,3-Dichloropropene	EPA 8260D
	EPA 8260C
Dibromochloromethane	EPA 8260D
	EPA 8260C
Dibromomethane	EPA 8260D
	EPA 8260C
Dichlorodifluoromethane	EPA 8260D
	EPA 8260C
Hexachlorobutadiene, Volatile	EPA 8260D
	EPA 8260C

Serial No.: 70990

Property of the New York State Department of Health. Certificates are valid only at the address shown and must be conspicuously posted by the laboratory. Continued accreditation depends on the laboratory's successful ongoing participation in the Program. Consumers may verify a laboratory's accreditation status online at https://apps.health.ny.gov/pubdoh/applinks/wc/elappublicweb/, by phone (518) 485-5570 or by email to elap@health.ny.gov.

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER

Expires 12:01 AM April 01, 2026
Issued April 01, 2025
Revised April 16, 2025

CERTIFICATE OF APPROVAL FOR LABORATORY SERVICE

Issued in accordance with and pursuant to section 502 Public Health Law of New York State

JAMES DODSWORTH *NY Lab Id No: 12058*
YORK ANALYTICAL LABORATORIES, INC. (II)
132-02 89TH AVENUE SUITE 217
RICHMOND HILL, NY 11418

is hereby APPROVED as an Environmental Laboratory in conformance with the National Environmental Laboratory Accreditation Conference Standards (2016) for the category ENVIRONMENTAL ANALYSES NON POTABLE WATER
All approved analytes are listed below:

Volatile Halocarbons

Methylene chloride	EPA 8260D
	EPA 8260C
Tetrachloroethene	EPA 8260D
	EPA 8260C
trans-1,2-Dichloroethene	EPA 8260D
	EPA 8260C
trans-1,3-Dichloropropene	EPA 8260D
	EPA 8260C
trans-1,4-Dichloro-2-butene	EPA 8260D
	EPA 8260C
Trichloroethene	EPA 8260D
	EPA 8260C
Trichlorofluoromethane	EPA 8260D
	EPA 8260C
Vinyl chloride	EPA 8260D
	EPA 8260C

Volatiles Organics

1,4-Dioxane	EPA 8260D
	EPA 8260C
2-Butanone (Methylethyl ketone)	EPA 8260D
	EPA 8260C
2-Hexanone	EPA 8260D
	EPA 8260C
4-Methyl-2-Pentanone	EPA 8260D
	EPA 8260C
Acetone	EPA 8260D
	EPA 8260C

Serial No.: 70990

Property of the New York State Department of Health. Certificates are valid only at the address shown and must be conspicuously posted by the laboratory. Continued accreditation depends on the laboratory's successful ongoing participation in the Program. Consumers may verify a laboratory's accreditation status online at https://apps.health.ny.gov/pubdoh/applinks/wc/elappublicweb/, by phone (518) 485-5570 or by email to elap@health.ny.gov.

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER

Expires 12:01 AM April 01, 2026
Issued April 01, 2025
Revised April 16, 2025

CERTIFICATE OF APPROVAL FOR LABORATORY SERVICE

Issued in accordance with and pursuant to section 502 Public Health Law of New York State

JAMES DODSWORTH *NY Lab Id No: 12058*
YORK ANALYTICAL LABORATORIES, INC. (II)
132-02 89TH AVENUE SUITE 217
RICHMOND HILL, NY 11418

is hereby APPROVED as an Environmental Laboratory in conformance with the National Environmental Laboratory Accreditation Conference Standards (2016) for the category ENVIRONMENTAL ANALYSES NON POTABLE WATER
All approved analytes are listed below:

Volatiles Organics

Carbon Disulfide	EPA 8260D
	EPA 8260C
Cyclohexane	EPA 8260D
	EPA 8260C
Methyl acetate	EPA 8260D
	EPA 8260C
Methyl cyclohexane	EPA 8260D
	EPA 8260C
Vinyl acetate	EPA 8260D
	EPA 8260C

Sample Preparation Methods

	EPA 5030C

Serial No.: 70990

Property of the New York State Department of Health. Certificates are valid only at the address shown and must be conspicuously posted by the laboratory. Continued accreditation depends on the laboratory's successful ongoing participation in the Program. Consumers may verify a laboratory's accreditation status online at https://apps.health.ny.gov/pubdoh/applinks/wc/elappublicweb/, by phone (518) 485-5570 or by email to elap@health.ny.gov.

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER

Expires 12:01 AM April 01, 2026
Issued April 01, 2025
Revised April 16, 2025

CERTIFICATE OF APPROVAL FOR LABORATORY SERVICE

Issued in accordance with and pursuant to section 502 Public Health Law of New York State

JAMES DODSWORTH *NY Lab Id No: 12058*
YORK ANALYTICAL LABORATORIES, INC. (II)
132-02 89TH AVENUE SUITE 217
RICHMOND HILL, NY 11418

is hereby APPROVED as an Environmental Laboratory for the category
ENVIRONMENTAL ANALYSES NON POTABLE WATER
All approved subcategories and/or analytes are listed below:

Perfluorinated Alkyl Acids

11Cl-PF3OUdS	EPA 1633 (Draft)
4:2FTS	EPA 1633 (Draft)
6:2FTS	EPA 1633 (Draft)
8:2FTS	EPA 1633 (Draft)
9Cl-PF3ONS	EPA 1633 (Draft)
ADONA	EPA 1633 (Draft)
HFPO-DA (GenX)	EPA 1633 (Draft)
NEtFOSAA	EPA 1633 (Draft)
NFDHA	EPA 1633 (Draft)
NMeFOSAA	EPA 1633 (Draft)
Perflourotridecanoic Acid (PFTrDA)	EPA 1633 (Draft)
Perfluordecanoic Acid (PFDA)	EPA 1633 (Draft)
Perfluoro-3-Methoxypropanoic Acid (F	EPA 1633 (Draft)
Perfluoro-4-Methoxybutanoic Acid (PF	EPA 1633 (Draft)
Perfluorobutanesulfonic Acid (PFBS)	EPA 1633 (Draft)
Perfluorobutanoic Acid (PFBA)	EPA 1633 (Draft)
Perfluorododecanoic Acid (PFDoA)	EPA 1633 (Draft)
Perfluoroheptanesulfonic Acid (PFHpS	EPA 1633 (Draft)
Perfluoroheptanoic Acid (PFHpA)	EPA 1633 (Draft)
Perfluorohexanesulfonic Acid (PFHxS	EPA 1633 (Draft)
Perfluorohexanoic Acid (PFHxA)	EPA 1633 (Draft)
Perfluorononanoic Acid (PFNA)	EPA 1633 (Draft)
Perfluorooctanesulfonic Acid (PFOS)	EPA 1633 (Draft)
Perfluorooctanoic Acid (PFOA)	EPA 1633 (Draft)
Perfluoropentanesulfonic Acid (PFPeS	EPA 1633 (Draft)
Perfluoropentanoic Acid (PFPeA)	EPA 1633 (Draft)
Perfluoroundecanoic Acid (PFUnA)	EPA 1633 (Draft)

Serial No.: 70991

Property of the New York State Department of Health. Certificates are valid only at the address shown and must be conspicuously posted by the laboratory. Continued accreditation depends on the laboratory's successful ongoing participation in the Program. Consumers may verify a laboratory's accreditation status online at https://apps.health.ny.gov/pubdoh/applinks/wc/elappublicweb/, by phone (518) 485-5570 or by email to elap@health.ny.gov.

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER

Expires 12:01 AM April 01, 2026
Issued April 01, 2025
Revised April 16, 2025

CERTIFICATE OF APPROVAL FOR LABORATORY SERVICE

Issued in accordance with and pursuant to section 502 Public Health Law of New York State

JAMES DODSWORTH *NY Lab Id No: 12058*
YORK ANALYTICAL LABORATORIES, INC. (II)
132-02 89TH AVENUE SUITE 217
RICHMOND HILL, NY 11418

is hereby APPROVED as an Environmental Laboratory for the category
ENVIRONMENTAL ANALYSES NON POTABLE WATER
All approved subcategories and/or analytes are listed below:

Perfluorinated Alkyl Acids

PFEESA	EPA 1633 (Draft)

Serial No.: 70991

Property of the New York State Department of Health. Certificates are valid only at the address shown and must be conspicuously posted by the laboratory. Continued accreditation depends on the laboratory's successful ongoing participation in the Program. Consumers may verify a laboratory's accreditation status online at https://apps.health.ny.gov/pubdoh/applinks/wc/elappublicweb/, by phone (518) 485-5570 or by email to elap@health.ny.gov.

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER

Expires 12:01 AM April 01, 2026
Issued April 01, 2025
Revised April 16, 2025

CERTIFICATE OF APPROVAL FOR LABORATORY SERVICE

Issued in accordance with and pursuant to section 502 Public Health Law of New York State

JAMES DODSWORTH
YORK ANALYTICAL LABORATORIES, INC. (II)
132-02 89TH AVENUE SUITE 217
RICHMOND HILL, NY 11418

NY Lab Id No: 12058

is hereby APPROVED as an Environmental Laboratory in conformance with the National Environmental Laboratory Accreditation Conference Standards (2016) for the category ENVIRONMENTAL ANALYSES POTABLE WATER
All approved analytes are listed below:

Perfluorinated Alkyl Acids

11Cl-PF3OUdS	EPA 533
	EPA 537.1, Version 2
4:2FTS	EPA 533
6:2FTS	EPA 533
8:2FTS	EPA 533
9Cl-PF3ONS	EPA 533
	EPA 537.1, Version 2
ADONA	EPA 533
	EPA 537.1, Version 2
HFPO-DA (GenX)	EPA 533
	EPA 537.1, Version 2
NEtFOSAA	EPA 537.1, Version 2
NFDHA	EPA 533
NMeFOSAA	EPA 537.1, Version 2
Perflourotridecanoic Acid (PFTrDA)	EPA 537.1, Version 2
Perfluordecanoic Acid (PFDA)	EPA 533
	EPA 537.1, Version 2
Perfluoro-3-Methoxypropanoic Acid (P	EPA 533
Perfluoro-4-Methoxybutanoic Acid (PF	EPA 533
Perfluorobutanesulfonic Acid (PFBS)	EPA 533
	EPA 537.1, Version 2
Perfluorobutanoic Acid (PFBA)	EPA 533
Perfluorododecanoic Acid (PFDoA)	EPA 533
	EPA 537.1, Version 2
Perfluoroheptanesulfonic Acid (PFHpS	EPA 533
Perfluoroheptanoic Acid (PFHpA)	EPA 533
	EPA 537.1, Version 2

Serial No.: 70989

Property of the New York State Department of Health. Certificates are valid only at the address shown and must be conspicuously posted by the laboratory. Continued accreditation depends on the laboratory's successful ongoing participation in the Program. Consumers may verify a laboratory's accreditation status online at https://apps.health.ny.gov/pubdoh/applinks/wc/elappublicweb/, by phone (518) 485-5570 or by email to elap@health.ny.gov.

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER

Expires 12:01 AM April 01, 2026
Issued April 01, 2025
Revised April 16, 2025

CERTIFICATE OF APPROVAL FOR LABORATORY SERVICE

Issued in accordance with and pursuant to section 502 Public Health Law of New York State

JAMES DODSWORTH *NY Lab Id No: 12058*
YORK ANALYTICAL LABORATORIES, INC. (II)
132-02 89TH AVENUE SUITE 217
RICHMOND HILL, NY 11418

is hereby APPROVED as an Environmental Laboratory in conformance with the National Environmental Laboratory Accreditation Conference Standards (2016) for the category ENVIRONMENTAL ANALYSES POTABLE WATER
All approved analytes are listed below:

Perfluorinated Alkyl Acids

Perfluorohexanesulfonic Acid (PFHxS	EPA 533
	EPA 537.1, Version 2
Perfluorohexanoic Acid (PFHxA)	EPA 533
	EPA 537.1, Version 2
Perfluorononanoic Acid (PFNA)	EPA 533
	EPA 537.1, Version 2
Perfluorooctanesulfonic Acid (PFOS)	EPA 533
	EPA 537.1, Version 2
Perfluorooctanoic Acid (PFOA)	EPA 533
	EPA 537.1, Version 2
Perfluoropentanesulfonic Acid (PFPeS	EPA 533
Perfluoropentanoic Acid (PFPeA)	EPA 533
Perfluorotetradecanoic Acid (PFTeDA)	EPA 537.1, Version 2
Perfluoroundecanoic Acid (PFUnA)	EPA 533
	EPA 537.1, Version 2
PFEESA	EPA 533

Serial No.: 70989

Property of the New York State Department of Health. Certificates are valid only at the address shown and must be conspicuously posted by the laboratory. Continued accreditation depends on the laboratory's successful ongoing participation in the Program. Consumers may verify a laboratory's accreditation status online at https://apps.health.ny.gov/pubdoh/applinks/wc/elappublicweb/, by phone (518) 485-5570 or by email to elap@health.ny.gov.

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER

Expires 12:01 AM April 01, 2026
Issued April 01, 2025
Revised April 16, 2025

CERTIFICATE OF APPROVAL FOR LABORATORY SERVICE

Issued in accordance with and pursuant to section 502 Public Health Law of New York State

JAMES DODSWORTH *NY Lab Id No: 12058*
YORK ANALYTICAL LABORATORIES, INC. (II)
132-02 89TH AVENUE SUITE 217
RICHMOND HILL, NY 11418

is hereby APPROVED as an Environmental Laboratory in conformance with the National Environmental Laboratory Accreditation Conference Standards (2016) for the category ENVIRONMENTAL ANALYSES SOLID AND HAZARDOUS WASTE
All approved analytes are listed below:

Acrylates	
Acrolein (Propenal)	EPA 8260D
	EPA 8260C
Acrylonitrile	EPA 8260D
	EPA 8260C
Methyl methacrylate	EPA 8260D
	EPA 8260C
Chlorinated Hydrocarbons	
1,2,3-Trichlorobenzene	EPA 8260D
	EPA 8260C
Volatile Aromatics	
1,2,4-Trichlorobenzene, Volatile	EPA 8260D
	EPA 8260C
1,2,4-Trimethylbenzene	EPA 8260D
	EPA 8260C
1,2-Dichlorobenzene	EPA 8260D
	EPA 8260C
1,3,5-Trimethylbenzene	EPA 8260D
	EPA 8260C
1,3-Dichlorobenzene	EPA 8260D
	EPA 8260C
1,4-Dichlorobenzene	EPA 8260D
	EPA 8260C
2-Chlorotoluene	EPA 8260D
	EPA 8260C
4-Chlorotoluene	EPA 8260D
	EPA 8260C

Serial No.: 70992

Property of the New York State Department of Health. Certificates are valid only at the address shown and must be conspicuously posted by the laboratory. Continued accreditation depends on the laboratory's successful ongoing participation in the Program. Consumers may verify a laboratory's accreditation status online at https://apps.health.ny.gov/pubdoh/applinks/wc/elappublicweb/, by phone (518) 485-5570 or by email to elap@health.ny.gov.

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER

Expires 12:01 AM April 01, 2026
Issued April 01, 2025
Revised April 16, 2025

CERTIFICATE OF APPROVAL FOR LABORATORY SERVICE

Issued in accordance with and pursuant to section 502 Public Health Law of New York State

JAMES DODSWORTH
YORK ANALYTICAL LABORATORIES, INC. (II)
132-02 89TH AVENUE SUITE 217
RICHMOND HILL, NY 11418

NY Lab Id No: 12058

is hereby APPROVED as an Environmental Laboratory in conformance with the National Environmental Laboratory Accreditation Conference Standards (2016) for the category ENVIRONMENTAL ANALYSES SOLID AND HAZARDOUS WASTE
All approved analytes are listed below:

Volatile Aromatics

Benzene	EPA 8260D
	EPA 8260C
Bromobenzene	EPA 8260D
	EPA 8260C
Chlorobenzene	EPA 8260D
	EPA 8260C
Ethyl benzene	EPA 8260D
	EPA 8260C
Isopropylbenzene	EPA 8260D
	EPA 8260C
m/p-Xylenes	EPA 8260D
	EPA 8260C
Naphthalene, Volatile	EPA 8260D
	EPA 8260C
n-Butylbenzene	EPA 8260D
	EPA 8260C
n-Propylbenzene	EPA 8260D
	EPA 8260C
o-Xylene	EPA 8260D
	EPA 8260C
p-Isopropyltoluene (P-Cymene)	EPA 8260D
	EPA 8260C
sec-Butylbenzene	EPA 8260D
	EPA 8260C
Styrene	EPA 8260D
	EPA 8260C
tert-Butylbenzene	EPA 8260D

Serial No.: 70992

Property of the New York State Department of Health. Certificates are valid only at the address shown and must be conspicuously posted by the laboratory. Continued accreditation depends on the laboratory's successful ongoing participation in the Program. Consumers may verify a laboratory's accreditation status online at https://apps.health.ny.gov/pubdoh/applinks/wc/elappublicweb/, by phone (518) 485-5570 or by email to elap@health.ny.gov.

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER

Expires 12:01 AM April 01, 2026
Issued April 01, 2025
Revised April 16, 2025

CERTIFICATE OF APPROVAL FOR LABORATORY SERVICE

Issued in accordance with and pursuant to section 502 Public Health Law of New York State

JAMES DODSWORTH *NY Lab Id No: 12058*
YORK ANALYTICAL LABORATORIES, INC. (II)
132-02 89TH AVENUE SUITE 217
RICHMOND HILL, NY 11418

is hereby APPROVED as an Environmental Laboratory in conformance with the National Environmental Laboratory Accreditation Conference Standards (2016) for the category ENVIRONMENTAL ANALYSES SOLID AND HAZARDOUS WASTE
All approved analytes are listed below:

Volatile Aromatics

tert-Butylbenzene	EPA 8260C
Toluene	EPA 8260D
	EPA 8260C
Total Xylenes	EPA 8260D
	EPA 8260C

Volatile Halocarbons

1,1,1,2-Tetrachloroethane	EPA 8260D
	EPA 8260C
1,1,1-Trichloroethane	EPA 8260D
	EPA 8260C
1,1,2,2-Tetrachloroethane	EPA 8260D
	EPA 8260C
1,1,2-Trichloro-1,2,2-Trifluoroethane	EPA 8260D
	EPA 8260C
1,1,2-Trichloroethane	EPA 8260D
	EPA 8260C
1,1-Dichloroethane	EPA 8260D
	EPA 8260C
1,1-Dichloroethene	EPA 8260D
	EPA 8260C
1,1-Dichloropropene	EPA 8260D
	EPA 8260C
1,2,3-Trichloropropane	EPA 8260D
	EPA 8260C
1,2-Dibromo-3-chloropropane	EPA 8260D
	EPA 8260C
1,2-Dibromoethane	EPA 8260D

Serial No.: 70992

Property of the New York State Department of Health. Certificates are valid only at the address shown and must be conspicuously posted by the laboratory. Continued accreditation depends on the laboratory's successful ongoing participation in the Program. Consumers may verify a laboratory's accreditation status online at https://apps.health.ny.gov/pubdoh/applinks/wc/elappublicweb/, by phone (518) 485-5570 or by email to elap@health.ny.gov.

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER

Expires 12:01 AM April 01, 2026
Issued April 01, 2025
Revised April 16, 2025

CERTIFICATE OF APPROVAL FOR LABORATORY SERVICE

Issued in accordance with and pursuant to section 502 Public Health Law of New York State

JAMES DODSWORTH
YORK ANALYTICAL LABORATORIES, INC. (II)
132-02 89TH AVENUE SUITE 217
RICHMOND HILL, NY 11418

NY Lab Id No: 12058

is hereby APPROVED as an Environmental Laboratory in conformance with the National Environmental Laboratory Accreditation Conference Standards (2016) for the category ENVIRONMENTAL ANALYSES SOLID AND HAZARDOUS WASTE
All approved analytes are listed below:

Volatile Halocarbons

1,2-Dibromoethane	EPA 8260C
1,2-Dichloroethane	EPA 8260D
	EPA 8260C
1,2-Dichloropropane	EPA 8260D
	EPA 8260C
1,3-Dichloropropane	EPA 8260D
	EPA 8260C
2,2-Dichloropropane	EPA 8260D
	EPA 8260C
2-Chloroethylvinyl ether	EPA 8260D
	EPA 8260C
Bromochloromethane	EPA 8260D
	EPA 8260C
Bromodichloromethane	EPA 8260D
	EPA 8260C
Bromoform	EPA 8260D
	EPA 8260C
Bromomethane	EPA 8260D
	EPA 8260C
Carbon tetrachloride	EPA 8260D
	EPA 8260C
Chloroethane	EPA 8260D
	EPA 8260C
Chloroform	EPA 8260D
	EPA 8260C
Chloromethane	EPA 8260D
	EPA 8260C

Serial No.: 70992

Property of the New York State Department of Health. Certificates are valid only at the address shown and must be conspicuously posted by the laboratory. Continued accreditation depends on the laboratory's successful ongoing participation in the Program. Consumers may verify a laboratory's accreditation status online at https://apps.health.ny.gov/pubdoh/applinks/wc/elappublicweb/, by phone (518) 485-5570 or by email to elap@health.ny.gov.

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER

Expires 12:01 AM April 01, 2026
Issued April 01, 2025
Revised April 16, 2025

CERTIFICATE OF APPROVAL FOR LABORATORY SERVICE

Issued in accordance with and pursuant to section 502 Public Health Law of New York State

JAMES DODSWORTH
YORK ANALYTICAL LABORATORIES, INC. (II)
132-02 89TH AVENUE SUITE 217
RICHMOND HILL, NY 11418

NY Lab Id No: 12058

is hereby APPROVED as an Environmental Laboratory in conformance with the National Environmental Laboratory Accreditation Conference Standards (2016) for the category ENVIRONMENTAL ANALYSES SOLID AND HAZARDOUS WASTE
All approved analytes are listed below:

Volatile Halocarbons

cis-1,2-Dichloroethene	EPA 8260D
	EPA 8260C
cis-1,3-Dichloropropene	EPA 8260D
	EPA 8260C
Dibromochloromethane	EPA 8260D
	EPA 8260C
Dibromomethane	EPA 8260D
	EPA 8260C
Dichlorodifluoromethane	EPA 8260D
	EPA 8260C
Hexachlorobutadiene, Volatile	EPA 8260D
	EPA 8260C
Methylene chloride	EPA 8260D
	EPA 8260C
Tetrachloroethene	EPA 8260D
	EPA 8260C
trans-1,2-Dichloroethene	EPA 8260D
	EPA 8260C
trans-1,3-Dichloropropene	EPA 8260D
	EPA 8260C
Trichloroethene	EPA 8260D
	EPA 8260C
Trichlorofluoromethane	EPA 8260D
	EPA 8260C
Vinyl chloride	EPA 8260D
	EPA 8260C

Serial No.: 70992

Property of the New York State Department of Health. Certificates are valid only at the address shown and must be conspicuously posted by the laboratory. Continued accreditation depends on the laboratory's successful ongoing participation in the Program. Consumers may verify a laboratory's accreditation status online at https://apps.health.ny.gov/pubdoh/applinks/wc/elappublicweb/, by phone (518) 485-5570 or by email to elap@health.ny.gov.

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER

Expires 12:01 AM April 01, 2026
Issued April 01, 2025
Revised April 16, 2025

CERTIFICATE OF APPROVAL FOR LABORATORY SERVICE

Issued in accordance with and pursuant to section 502 Public Health Law of New York State

JAMES DODSWORTH
YORK ANALYTICAL LABORATORIES, INC. (II)
132-02 89TH AVENUE SUITE 217
RICHMOND HILL, NY 11418

NY Lab Id No: 12058

is hereby APPROVED as an Environmental Laboratory in conformance with the National Environmental Laboratory Accreditation Conference Standards (2016) for the category ENVIRONMENTAL ANALYSES SOLID AND HAZARDOUS WASTE
All approved analytes are listed below:

Volatile Organics

1,4-Dioxane	EPA 8260D
	EPA 8260C
2-Butanone (Methylethyl ketone)	EPA 8260D
	EPA 8260C
2-Hexanone	EPA 8260D
	EPA 8260C
4-Methyl-2-Pentanone	EPA 8260D
	EPA 8260C
Acetone	EPA 8260D
	EPA 8260C
Carbon Disulfide	EPA 8260D
	EPA 8260C
Cyclohexane	EPA 8260D
	EPA 8260C
Methyl acetate	EPA 8260D
	EPA 8260C
Methyl cyclohexane	EPA 8260D
	EPA 8260C
Methyl tert-butyl ether	EPA 8260D
	EPA 8260C
tert-butyl alcohol	EPA 8260D
	EPA 8260C
Vinyl acetate	EPA 8260D
	EPA 8260C

Sample Preparation Methods

	EPA 5035A-L
	EPA 5035A-H

Serial No.: 70992

Property of the New York State Department of Health. Certificates are valid only at the address shown and must be conspicuously posted by the laboratory. Continued accreditation depends on the laboratory's successful ongoing participation in the Program. Consumers may verify a laboratory's accreditation status online at https://apps.health.ny.gov/pubdoh/applinks/wc/elappublicweb/, by phone (518) 485-5570 or by email to elap@health.ny.gov.

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER

Expires 12:01 AM April 01, 2026
Issued April 01, 2025
Revised April 16, 2025

CERTIFICATE OF APPROVAL FOR LABORATORY SERVICE

Issued in accordance with and pursuant to section 502 Public Health Law of New York State

JAMES DODSWORTH
YORK ANALYTICAL LABORATORIES, INC. (II)
132-02 89TH AVENUE SUITE 217
RICHMOND HILL, NY 11418

NY Lab Id No: 12058

is hereby APPROVED as an Environmental Laboratory for the category
ENVIRONMENTAL ANALYSES SOLID AND HAZARDOUS WASTE
All approved subcategories and/or analytes are listed below:

Perfluorinated Alkyl Acids

8:2FTS	EPA 1633 (Draft)
NEtFOSAA	EPA 1633 (Draft)
NMeFOSAA	EPA 1633 (Draft)
Perflourotridecanoic Acid (PFTrDA)	EPA 1633 (Draft)
Perfluordecanoic Acid (PFDA)	EPA 1633 (Draft)
Perfluorobutanoic Acid (PFBA)	EPA 1633 (Draft)
Perfluorododecanoic Acid (PFDoA)	EPA 1633 (Draft)
Perfluoroheptanoic Acid (PFHpA)	EPA 1633 (Draft)
Perfluorohexanoic Acid (PFHxA)	EPA 1633 (Draft)
Perfluorononanoic Acid (PFNA)	EPA 1633 (Draft)
Perfluorooctanesulfonic Acid (PFOS)	EPA 1633 (Draft)
Perfluorooctanoic Acid (PFOA)	EPA 1633 (Draft)
Perfluoropentanoic Acid (PFPeA)	EPA 1633 (Draft)
Perfluorotetradecanoic Acid (PFTeDA)	EPA 1633 (Draft)
Perfluoroundecanoic Acid (PFUnA)	EPA 1633 (Draft)

Serial No.: 70993

Property of the New York State Department of Health. Certificates are valid only at the address shown and must be conspicuously posted by the laboratory. Continued accreditation depends on the laboratory's successful ongoing participation in the Program. Consumers may verify a laboratory's accreditation status online at https://apps.health.ny.gov/pubdoh/applinks/wc/elappublicweb/, by phone (518) 485-5570 or by email to elap@health.ny.gov.

APPENDIX F

Green and Sustainable Remediation Footprint Analysis and Climate Screening Checklist

LANGAN

This worksheet allows the user to calculate the life cycle environmental footprint of the materials used	
Yellow cells	value chosen from drop down menu on input sheet
White cells	value entered on input sheet
Orange cells	provide the output of the tool
Blue Cells	tool calculations and automatic lookups

WELL MATERIALS

	WELL TYPE 1	WELL TYPE 2	WELL TYPE 3	WELL TYPE 4	WELL TYPE 5	WELL TYPE 6	WELL TYPE 7	WELL TYPE 8	WELL TYPE 9
Number of wells	6	0	0	0	0	0	0	0	0
Depth of wells (ft)	30	0	0	0	0	0	0	0	0
Specific casing material schedule	Sch 40 PVC	Sch 40 PVC	Sch 40 PVC	Sch 40 PVC	Sch 40 PVC	Sch 40 PVC	Sch 40 PVC	Sch 40 PVC	Sch 40 PVC
Well diameter from drop down menu (in)	2	1/8	1/8	1/8	1/8	1/8	1/8	1/8	1/8
Total weight of Sand (kg)	7.21E+02	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Total weight of Gravel (kg)	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Total weight of Bentonite (kg)	1.11E+02	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Total weight of Typical Cement (kg)	6.53E+02	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Total weight of General Concrete (kg)	2.22E+03	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Total weight of Steel (kg)	4.88E+02	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
Casing material type	PVC	PVC	PVC	PVC	PVC	PVC	PVC	PVC	PVC
Weight of casing material (lb/ft)	7.20E-01	5.10E-02	5.10E-02	5.10E-02	5.10E-02	5.10E-02	5.10E-02	5.10E-02	5.10E-02
Total length of casing material required (ft)	180	0	0	0	0	0	0	0	0
Total weight of casing material required (lbs)	130	0	0	0	0	0	0	0	0
Total weight of casing material required (kg)	58.8	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
CO_2 e emission factor (kg CO_2/kg material)	3.11E+00	3.11E+00	3.11E+00	3.11E+00	3.11E+00	3.11E+00	3.11E+00	3.11E+00	3.11E+00
NOx emission factor (g/kg)	6.00E+00	6.00E+00	6.00E+00	6.00E+00	6.00E+00	6.00E+00	6.00E+00	6.00E+00	6.00E+00
SOx emission factor (g/kg)	9.70E+00	9.70E+00	9.70E+00	9.70E+00	9.70E+00	9.70E+00	9.70E+00	9.70E+00	9.70E+00
PM_{10} emission factor (g/kg)	1.40E+00	1.40E+00	1.40E+00	1.40E+00	1.40E+00	1.40E+00	1.40E+00	1.40E+00	1.40E+00
MJ/kg material	67.5	67.5	67.5	67.5	67.5	67.5	67.5	67.5	67.5
ENERGY OUTPUT									
Energy used (BTU)	3.6E+09	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00
CO_2 OUTPUT									
CO_2 e emission (metric ton)	1.2E+01	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00
NOx, SOx and PM_{10} OUTPUT									
NOx emission (metric ton)	4.9E-03	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00
SOx emission (metric ton)	6.7E-03	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00
PM_{10} emission (metric ton)	8.9E-04	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00

TOTAL FROM WELL MATERIALS	
CO_2 e Emission (metric ton)	**1.2E+01**
Onsite NOx Emission (metric ton)	**NA**
Onsite SOx Emission (metric ton)	**NA**
Onsite PM_{10} Emission (metric ton)	**NA**
Offsite NOx Emission (metric ton)	**4.9E-03**
Offsite SOx Emission (metric ton)	**6.7E-03**
Offsite PM_{10} Emission (metric ton)	**8.9E-04**
Accident Risk - Fatality	**NA**
Accident Risk - Injury	**NA**
Water Used (gallons)	**NA**
Energy Used (BTU)	**3.6E+09**
Energy Used (MWh)	**NA**

TOTAL FROM MATERIAL PRODUCTION	
CO_2 e Emission (metric ton)	**1.2E+01**
Onsite NOx Emission (metric ton)	**NA**
Onsite SOx Emission (metric ton)	**NA**
Onsite PM_{10} Emission (metric ton)	**NA**
Offsite NOx Emission (metric ton)	**4.9E-03**
Offsite SOx Emission (metric ton)	**6.7E-03**
Offsite PM_{10} Emission (metric ton)	**8.9E-04**
Accident Risk - Fatality	**NA**
Accident Risk - Injury	**NA**
Water Used (gallons)	**NA**
Energy Used (MMBTU)	**3.6E+03**
Energy Used (MWh)	**NA**

This worksheet allows the user to calculate the	environmental footprint of personnel travel
Yellow cells	value chosen from drop down menu on input sheet
White cells	value entered on input sheet
Orange cells	provide the output of the tool
Blue Cells	tool calculations and automatic lookups

TRANSPORTATION - ROAD

	Trip 1	Trip 2	Trip 3	Trip 4	Trip 5	Trip 6	Trip 7	Trip 8	Trip 9	Trip 10	Trip 11	Trip 12
Vehicle type	Cars	Cars	Heavy Duty	Cars	Cars	Cars	Cars	Cars	Cars	Cars	Cars	Cars
Fuel used	Gasoline	Gasoline	Diesel	Gasoline	Gasoline	Gasoline	Gasoline	Gasoline	Gasoline	Gasoline	Gasoline	Gasoline
Distance traveled per trip (miles)	110	20	60	0	0	0	0	0	0	0	0	0
Number of trips taken	20	40	6	0	0	0	0	0	0	0	0	0
Number of travelers	1	1	2	0	0	0	0	0	0	0	0	0
Total distance traveled (miles)	2200	800	360	0	0	0	0	0	0	0	0	0
Will DIESEL-run vehicles be retrofitted with a particulate reduction technology?	No	No	No	No	No	No	No	No	No	No	No	No
Consumption rate (MPG)	29	29	7.4	29	29	29	29	29	29	29	29	29
Estimated MPG (input the default if not known)	0	0	0	0	0	0	0	0	0	0	0	0
Total fuel used (gallons)	75.9	27.6	48.6	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
BTU per gallon fuel used	139,015	139,015	135,847	139,015	139,015	139,015	139,015	139,015	139,015	139,015	139,015	139,015
CO_2 emission factor (g/mile)	3.67E+02	3.67E+02	1.37E+03	3.67E+02	3.67E+02	3.67E+02	3.67E+02	3.67E+02	3.67E+02	3.67E+02	3.67E+02	3.67E+02
N_2O emission factor (g/mile)	1.65E-02	1.65E-02	1.54E-02	1.65E-02	1.65E-02	1.65E-02	1.65E-02	1.65E-02	1.65E-02	1.65E-02	1.65E-02	1.65E-02
CH_4 emission factor (g/mile)	4.46E-01	4.46E-01	1.54E+00	4.46E-01	4.46E-01	4.46E-01	4.46E-01	4.46E-01	4.46E-01	4.46E-01	4.46E-01	4.46E-01
NOx emission factor (g/mile)	1.41E-01	1.41E-01	4.42E-01	1.41E-01	1.41E-01	1.41E-01	1.41E-01	1.41E-01	1.41E-01	1.41E-01	1.41E-01	1.41E-01
SOx emission factor (g/mile)	4.97E-03	4.97E-03	7.82E-03	4.97E-03	4.97E-03	4.97E-03	4.97E-03	4.97E-03	4.97E-03	4.97E-03	4.97E-03	4.97E-03
PM_{10} emission factor (g/mile)	2.86E-02	2.86E-02	3.93E-02	2.86E-02	2.86E-02	2.86E-02	2.86E-02	2.86E-02	2.86E-02	2.86E-02	2.86E-02	2.86E-02
ENERGY OUTPUT												
Energy used (BTU)	1.1E+07	3.8E+06	6.6E+06	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00
CO_2 OUTPUT												
CO_2 emission (metric ton)	8.1E-01	2.9E-01	4.9E-01	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00
N_2O emission (metric ton CO_2 e)	1.1E-02	4.1E-03	1.7E-03	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00
CH_4 emission (metric ton CO_2 e)	2.1E-02	7.5E-03	1.2E-02	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00
NOx, SOx and PM_{10} OUTPUT												
NOx emission (metric ton)	3.1E-04	1.1E-04	1.6E-04	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00
SOx emission (metric ton)	1.1E-05	4.0E-06	2.8E-06	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00
PM_{10} emission (metric ton)	6.3E-05	2.3E-05	1.4E-05	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00
ACCIDENT RISK												
Fatality risk	1.7E-05	6.2E-06	5.6E-06	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00
Injury risk	1.4E-03	5.0E-04	4.5E-04	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00

TOTAL FROM ROAD TRANSPORTATION	
CO_2 e Emission (metric ton)	1.6E+00
Onsite NOx Emission (metric ton)	NA
Onsite SOx Emission (metric ton)	NA
Onsite PM_{10} Emission (metric ton)	NA
Offsite NOx Emission (metric ton)	5.8E-04
Offsite SOx Emission (metric ton)	1.8E-05
Offsite PM_{10} Emission (metric ton)	1.0E-04
Accident Risk - Fatality	2.9E-05
Accident Risk - Injury	2.3E-03
Water Used (gallons)	NA
Energy Used (BTU)	2.1E+07
Energy Used (MWh)	NA

TOTAL FROM PERSONNEL TRANSPORTATION	
CO_2 e Emission (metric ton)	1.6E+00
Onsite NOx Emission (metric ton)	NA
Onsite SOx Emission (metric ton)	NA
Onsite PM_{10} Emission (metric ton)	NA
Offsite NOx Emission (metric ton)	5.8E-04
Offsite SOx Emission (metric ton)	1.8E-05
Offsite PM_{10} Emission (metric ton)	1.0E-04
Accident Risk - Fatality	2.9E-05
Accident Risk - Injury	2.3E-03
Water Used (gallons)	NA
Energy Used (MMBTU)	2.1E+01
Energy Used (MWh)	NA

This worksheet allows the user to calculate the environmental footprint of equipment and material transport	
Yellow cells	value chosen from drop down menu on input sheet
White cells	value entered on input sheet
Orange cells	provide the output of the tool
Blue Cells	tool calculations and automatic lookups

EQUIPMENT TRANSPORTATION - DEDICATED LOAD ROAD

	Trip 1	Trip 2	Trip 3	Trip 4	Trip 5	Trip 6	Trip 7	Trip 8	Trip 9	Trip 10	Trip 11	Trip 12
Vehicle	On road Truck	On road Truck	On road Truck	On road Truck	On road Truck	On road Truck	On road Truck	On road Truck	On road Truck	On road Truck	On road Truck	On road Truck
Will DIESEL-run vehicles be retrofitted with a particulate reduction technology?	No	No	No	No	No	No	No	No	No	No	No	No
Fuel used	Diesel	Gasoline	Gasoline	Gasoline	Gasoline	Gasoline	Gasoline	Gasoline	Gasoline	Gasoline	Gasoline	Gasoline
Account for an empty return trip?	No	No	No	No	No	No	No	No	No	No	No	No
Distance travelled (mi)	60	0	0	0	0	0	0	0	0	0	0	0
Weight of equipment transported (tons)	16.75	0	0	0	0	0	0	0	0	0	0	0
Fuel efficiency by weight of load (mpg)	5.7	7.4	7.4	7.4	7.4	7.4	7.4	7.4	7.4	7.4	7.4	7.4
Total fuel used (gal)	11	0	0	0	0	0	0	0	0	0	0	0
BTU per gallon fuel used	135,847	139,015	139,015	139,015	139,015	139,015	139,015	139,015	139,015	139,015	139,015	139,015
CO_2 emission factor (g/gal)	1.01E+04	9.84E+03	9.84E+03	9.84E+03	9.84E+03	9.84E+03	9.84E+03	9.84E+03	9.84E+03	9.84E+03	9.84E+03	9.84E+03
N_2O emission factor (g/gal)	1.14E-01	2.09E-01	2.09E-01	2.09E-01	2.09E-01	2.09E-01	2.09E-01	2.09E-01	2.09E-01	2.09E-01	2.09E-01	2.09E-01
CH_4 emission factor (g/gal)	1.14E+01	1.18E+01	1.18E+01	1.18E+01	1.18E+01	1.18E+01	1.18E+01	1.18E+01	1.18E+01	1.18E+01	1.18E+01	1.18E+01
NOx emission factor (g/gal)	3.27E+00	3.27E+00	3.27E+00	3.27E+00	3.27E+00	3.27E+00	3.27E+00	3.27E+00	3.27E+00	3.27E+00	3.27E+00	3.27E+00
SOx emission factor (g/gal)	5.79E-02	1.33E-01	1.33E-01	1.33E-01	1.33E-01	1.33E-01	1.33E-01	1.33E-01	1.33E-01	1.33E-01	1.33E-01	1.33E-01
PM_{10} emission factor (g/gal)	2.91E-01	2.65E-01	2.65E-01	2.65E-01	2.65E-01	2.65E-01	2.65E-01	2.65E-01	2.65E-01	2.65E-01	2.65E-01	2.65E-01
ENERGY OUTPUT												
Energy used (BTU)	1.4E+06	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00
CO_2 OUTPUT												
CO_2 emission (metric ton)	1.1E-01	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00
N_2O emission (metric ton CO_2 e)	3.7E-04	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00
CH_4 emissions (metric ton CO_2 e)	2.5E-03	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00
NOx, SOx and PM_{10} OUTPUT												
NOx emission (metric ton)	3.5E-05	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00
SOx emission (metric ton)	6.1E-07	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00
PM_{10} emission (metric ton)	3.1E-06	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00
ACCIDENT RISK												
Fatality risk	4.7E-07	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00
Injury risk	3.8E-05	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00

TOTAL FROM DEDICATED LOAD ROAD TRANSPORTATION	
CO_2 e Emission (metric ton)	1.1E-01
Onsite NOx Emission (metric ton)	NA
Onsite SOx Emission (metric ton)	NA
Onsite PM_{10} Emission (metric ton)	NA
Offsite NOx Emission (metric ton)	3.5E-05
Offsite SOx Emission (metric ton)	6.1E-07
Offsite PM_{10} Emission (metric ton)	3.1E-06
Accident Risk - Fatality	4.7E-07
Accident Risk - Injury	3.8E-05
Water Used (gallons)	NA
Energy Used (BTU)	1.4E+06
Energy Used (MWh)	NA

TOTAL FROM EQUIPMENT TRANSPORTATION	
CO_2 e Emission (metric ton)	1.1E-01
Onsite NOx Emission (metric ton)	NA
Onsite SOx Emission (metric ton)	NA
Onsite PM_{10} Emission (metric ton)	NA
Offsite NOx Emission (metric ton)	3.5E-05
Offsite SOx Emission (metric ton)	6.1E-07
Offsite PM_{10} Emission (metric ton)	3.1E-06
Accident Risk - Fatality	4.7E-07
Accident Risk - Injury	3.8E-05
Water Used (gallons)	NA
Energy Used (MMBTU)	1.4E+00
Energy Used (MWh)	NA

This worksheet allows the user to calculate the environmental footprint of earthwork activities

Yellow cells	value chosen from drop down menu on input sheet
White cells	value entered on input sheet
Orange cells	provide the output of the tool
Blue Cells	tool calculations and automatic lookups

WELL DRILLING EQUIPMENT

		Event 1	Event 2	Event 3	Event 4	Event 5	Event 6	Event 7	Event 8	Event 9	Event 10	Event 11	Event 12
	Number of injection and extraction points/wells	6	0	0	0	0	0	0	0	0	0	0	0
	Drilling method	Hollow Stem Auger	Direct Push	Direct Push	Direct Push	Direct Push	Direct Push	Direct Push	Direct Push	Direct Push	Direct Push	Direct Push	Direct Push
	Drilling fuel consumption rate (gal/hr)	7.6	0.8	0.8	0.8	0.8	0.8	0.8	0.8	0.8	0.8	0.8	0.8
	Time spent drilling each injection site (hr)	3	0	0	0	0	0	0	0	0	0	0	0
	Fuel type	Diesel	Diesel	Diesel	Diesel	Diesel	Diesel	Diesel	Diesel	Diesel	Diesel	Diesel	Diesel
	Total time drilling well (hr)	18.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
	Total fuel consumption during drilling (gal)	135.9	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
	BTU per gallon fuel used	135,847	135,847	135,847	135,847	135,847	135,847	135,847	135,847	135,847	135,847	135,847	135,847
	CO_2 emission factor (kg/gallon)	1.10E+01	1.10E+01	1.10E+01	1.10E+01	1.10E+01	1.10E+01	1.10E+01	1.10E+01	1.10E+01	1.10E+01	1.10E+01	1.10E+01
	N_2O emission factor (g/gal)	1.23E-01	1.23E-01	1.23E-01	1.23E-01	1.23E-01	1.23E-01	1.23E-01	1.23E-01	1.23E-01	1.23E-01	1.23E-01	1.23E-01
	CH_4 emission factor (g/gal)	1.24E+01	1.24E+01	1.24E+01	1.24E+01	1.24E+01	1.24E+01	1.24E+01	1.24E+01	1.24E+01	1.24E+01	1.24E+01	1.24E+01
	NOx emission factor (g/gal)	1.14E+02	1.14E+02	1.14E+02	1.14E+02	1.14E+02	1.14E+02	1.14E+02	1.14E+02	1.14E+02	1.14E+02	1.14E+02	1.14E+02
	SOx emission factor (g/gal)	1.42E+01	1.42E+01	1.42E+01	1.42E+01	1.42E+01	1.42E+01	1.42E+01	1.42E+01	1.42E+01	1.42E+01	1.42E+01	1.42E+01
	PM_{10} emission factor (g/gal)	1.06E+01	1.06E+01	1.06E+01	1.06E+01	1.06E+01	1.06E+01	1.06E+01	1.06E+01	1.06E+01	1.06E+01	1.06E+01	1.06E+01
	Offsite NOx emission factor (g/hr)	4.6E+01	4.9E+00	4.9E+00	4.9E+00	4.9E+00	4.9E+00	4.9E+00	4.9E+00	4.9E+00	4.9E+00	4.9E+00	4.9E+00
	Offsite SOx emission factor (g/hr)	2.4E+01	2.6E+00	2.6E+00	2.6E+00	2.6E+00	2.6E+00	2.6E+00	2.6E+00	2.6E+00	2.6E+00	2.6E+00	2.6E+00
	Offsite PM_{10} emission factor (g/hr)	7.0E+00	7.4E-01	7.4E-01	7.4E-01	7.4E-01	7.4E-01	7.4E-01	7.4E-01	7.4E-01	7.4E-01	7.4E-01	7.4E-01
	ENERGY OUTPUT												
	Energy used (BTU)	1.8E+07	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00
	CO_2 OUTPUT												
	CO_2 emission from drilling (metric ton)	1.5E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00
	N_2O emission (metric ton CO_2 e)	5.2E-03	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00
	CH_4 emission (metric ton CO_2 e)	3.5E-02	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00
	NOx, SOx and PM_{10} OUTPUT												
	Offsite NOx emission (metric ton)	8.4E-04	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00
	Offsite SOx emission (metric ton)	4.4E-04	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00
	Offsite PM_{10} emission (metric ton)	1.3E-04	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00
	Onsite NOx emission (metric ton)	1.5E-02	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00
	Onsite SOx emission (metric ton)	1.5E-03	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00
	Onsite PM_{10} emission (metric ton)	1.3E-03	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00
	ACCIDENT RISK												
	Fatality risk	1.6E-06	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00
	Injury risk	4.1E-04	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00

TOTAL FROM WELL DRILLING	
CO_2 e Emission (metric ton)	1.5E+00
Onsite NOx Emission (metric ton)	1.5E-02
Onsite SOx Emission (metric ton)	1.5E-03
Onsite PM_{10} Emission (metric ton)	1.3E-03
Offsite NOx Emission (metric ton)	8.4E-04
Offsite SOx Emission (metric ton)	4.4E-04
Offsite PM_{10} Emission (metric ton)	1.3E-04
Accident Risk - Fatality	1.6E-06
Accident Risk - Injury	4.1E-04
Water Used (gallons)	NA
Energy Used (MMBTU)	1.8E+01
Energy Used (MWh)	NA

TOTAL FROM EARTHWORK EQUIPMENT OPERATION	
CO_2 e Emission (metric ton)	1.5E+00
Onsite NOx Emission (metric ton)	1.5E-02
Onsite SOx Emission (metric ton)	1.5E-03
Onsite PM_{10} Emission (metric ton)	1.3E-03
Offsite NOx Emission (metric ton)	8.4E-04
Offsite SOx Emission (metric ton)	4.4E-04
Offsite PM_{10} Emission (metric ton)	1.3E-04
Accident Risk - Fatality	1.6E-06
Accident Risk - Injury	4.1E-04
Water Used (gallons)	NA
Energy Used (MMBTU)	1.8E+01
Energy Used (MWh)	NA

This worksheet allows the user to calculate the	environmental footprint of equipment use
Yellow cells	value chosen from drop down menu on input sheet
White cells	value entered on input sheet
Orange cells	provide the output of the tool
Blue Cells	tool calculations and automatic lookups

LABORATORY ANALYSIS

		Analysis 1	Analysis 2	Analysis 3	Analysis 4	Analysis 5	Analysis 6	Analysis 7	Analysis 8	Analysis 9	Analysis 10	Analysis 11	Analysis 12
	Dollars spent on laboratory analysis	300,000.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	Energy used (MMBTU/$)	6.49E-03	6.49E-03	6.49E-03	6.49E-03	6.49E-03	6.49E-03	6.49E-03	6.49E-03	6.49E-03	6.49E-03	6.49E-03	6.49E-03
	CO2 e emission factor (lb/$)	1.00E+00	1.00E+00	1.00E+00	1.00E+00	1.00E+00	1.00E+00	1.00E+00	1.00E+00	1.00E+00	1.00E+00	1.00E+00	1.00E+00
	NOx emission factor (lb/$)	4.80E-03	4.80E-03	4.80E-03	4.80E-03	4.80E-03	4.80E-03	4.80E-03	4.80E-03	4.80E-03	4.80E-03	4.80E-03	4.80E-03
	SOx emission factor (lb/$)	3.60E-03	3.60E-03	3.60E-03	3.60E-03	3.60E-03	3.60E-03	3.60E-03	3.60E-03	3.60E-03	3.60E-03	3.60E-03	3.60E-03
	PM10 emission factor (lb/$)	4.00E-04	4.00E-04	4.00E-04	4.00E-04	4.00E-04	4.00E-04	4.00E-04	4.00E-04	4.00E-04	4.00E-04	4.00E-04	4.00E-04
	ENERGY OUTPUT												
	Energy used (BTU)	1.9E+09	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00
	CO_2 OUTPUT												
	CO_2 emission (metric ton)	1.4E+02	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00
	NOx, SOx and PM_{10} OUTPUT												
	NOx emission (metric ton)	6.5E-01	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00
	SOx emission (metric ton)	4.9E-01	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00
	PM_{10} emission (metric ton)	5.4E-02	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00

TOTAL FROM LABORATORY ANALYSIS	
CO_2 e Emission (metric ton)	1.4E+02
Onsite NOx Emission (metric ton)	NA
Onsite SOx Emission (metric ton)	NA
Onsite PM_{10} Emission (metric ton)	NA
Offsite NOx Emission (metric ton)	6.5E-01
Offsite SOx Emission (metric ton)	4.9E-01
Offsite PM_{10} Emission (metric ton)	5.4E-02
Accident Risk - Fatality	NA
Accident Risk - Injury	NA
Water Used (gallons)	NA
Energy Used (MMBTU)	1.9E+03
Energy Used (MWh)	NA

TOTAL FROM OTHER EQUIPMENT OPERATIONS	
CO_2 e Emission (metric ton)	1.4E+02
Onsite NOx Emission (metric ton)	0.0E+00
Onsite SOx Emission (metric ton)	0.0E+00
Onsite PM_{10} Emission (metric ton)	0.0E+00
Offsite NOx Emission (metric ton)	6.5E-01
Offsite SOx Emission (metric ton)	4.9E-01
Offsite PM_{10} Emission (metric ton)	5.4E-02
Accident Risk - Fatality	0.0E+00
Accident Risk - Injury	0.0E+00
Water Used (gallons)	0.0E+00
Energy Used (MMBTU)	1.9E+03
Energy Used (MWh)	NA

This worksheet allows the user to calculate the environmental footprint of residual handling

The different columns allow the user to calculate and compare the emissions for different types of residue such as soil, water, and materials

Yellow cells	value chosen from drop down menu on input sheet
White cells	value entered on input sheet
Orange cells	provide the output of the tool
Blue Cells	tool calculations and automatic lookups

RESIDUE DISPOSAL/RECYCLING

	Soil Residue	Residual Water	Material Residue	Other Residuals	Other Residuals	Other Residuals	Other Residuals	Other Residuals	Other Residuals	Other Residuals	Other Residuals	Other Residuals
Will DIESEL-run vehicles be retrofitted with a particulate reduction technology?	No	No	No	No	No	No	No	No	No	No	No	No
Weight of the waste transported to landfill or recycling (tons)	0.5	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Fuel used	Diesel	Gasoline	Gasoline	Gasoline	Gasoline	Gasoline	Gasoline	Gasoline	Gasoline	Gasoline	Gasoline	Gasoline
Total number of trips	20.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Number of miles per trip	60.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total distance traveled (miles)	1200	0	0	0	0	0	0	0	0	0	0	0
Fuel efficiency by weight of load (mpg)	7.3	7.4	7.4	7.4	7.4	7.4	7.4	7.4	7.4	7.4	7.4	7.4
Total fuel used (gal)	163.3	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
BTU per gallon fuel used	135,847	139,015	139,015	139,015	139,015	139,015	139,015	139,015	139,015	139,015	139,015	139,015
CO_2 emission factor (g/gal)	1.01E+04	9.84E+03	9.84E+03	9.84E+03	9.84E+03	9.84E+03	9.84E+03	9.84E+03	9.84E+03	9.84E+03	9.84E+03	9.84E+03
N_2O emission factor (g/gal)	1.14E-01	2.09E-01	2.09E-01	2.09E-01	2.09E-01	2.09E-01	2.09E-01	2.09E-01	2.09E-01	2.09E-01	2.09E-01	2.09E-01
CH_4 emission factor (g/gal)	1.14E+01	1.18E+01	1.18E+01	1.18E+01	1.18E+01	1.18E+01	1.18E+01	1.18E+01	1.18E+01	1.18E+01	1.18E+01	1.18E+01
NOx emission factor (g/gal)	3.27E+00	3.27E+00	3.27E+00	3.27E+00	3.27E+00	3.27E+00	3.27E+00	3.27E+00	3.27E+00	3.27E+00	3.27E+00	3.27E+00
SOx emission factor (g/gal)	5.79E-02	1.33E-01	1.33E-01	1.33E-01	1.33E-01	1.33E-01	1.33E-01	1.33E-01	1.33E-01	1.33E-01	1.33E-01	1.33E-01
PM_{10} emission factor (g/gal)	2.91E-01	2.65E-01	2.65E-01	2.65E-01	2.65E-01	2.65E-01	2.65E-01	2.65E-01	2.65E-01	2.65E-01	2.65E-01	2.65E-01
ENERGY OUTPUT												
Energy used (BTU)	2.2E+07	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00
CO_2 OUTPUT												
CO_2 emission (metric ton)	1.7E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00
N_2O emission (metric ton CO_2 e)	5.8E-03	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00
CH_4 emissions (metric ton CO_2 e)	3.9E-02	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00
NOx, SOx and PM_{10} OUTPUT												
NOx emission (metric ton)	5.3E-04	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00
SOx emission (metric ton)	9.4E-06	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00
PM_{10} emission (metric ton)	4.7E-05	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00
ACCIDENT RISK												
Fatality risk	9.4E-06	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00
Injury risk	7.5E-04	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00	0.0E+00

TOTAL FROM RESIDUAL HANDLING	
CO_2 e Emission (metric ton)	1.7E+00
Onsite NOx Emission (metric ton)	NA
Onsite SOx Emission (metric ton)	NA
Onsite PM_{10} Emission (metric ton)	NA
Offsite NOx Emission (metric ton)	5.3E-04
Offsite SOx Emission (metric ton)	9.4E-06
Offsite PM_{10} Emission (metric ton)	4.7E-05
Accident Risk - Fatality	9.4E-06
Accident Risk - Injury	7.5E-04
Water Used (gallons)	NA
Energy Used (MMBTU)	2.2E+01
Energy Used (MWh)	NA

TOTAL FROM RESIDUAL HANDLING	
CO_2 e Emission (metric ton)	1.7E+00
Onsite NOx Emission (metric ton)	0.0E+00
Onsite SOx Emission (metric ton)	0.0E+00
Onsite PM_{10} Emission (metric ton)	0.0E+00
Offsite NOx Emission (metric ton)	5.3E-04
Offsite SOx Emission (metric ton)	9.4E-06
Offsite PM_{10} Emission (metric ton)	4.7E-05
Accident Risk - Fatality	9.4E-06
Accident Risk - Injury	7.5E-04
Water Used (gallons)	NA
Energy Used (MMBTU)	2.2E+01
Energy Used (MWh)	NA

Environmental Footprint Summary

Activities	CO_2 Emissions	Percent Total	Onsite NOx emissions	Percent Total	Onsite SOx Emissions	Percent Total	Onsite PM_{10} Emissions	Percent Total	Total NOx emissions	Percent Total	Total SOx Emissions	Percent Total	Total PM_{10} Emissions	Percent Total	Total Energy Used	Percent Total	Accident Risk Fatality	Percent Total	Accident Risk Injury	Percent Total
	metric ton	%	metric ton	%	metric ton	%	metric ton	%	metric ton	%	metric ton	%	metric ton	%	MMBTU	%		%		%
Material Productions	12.39	8.07	NA	-	NA	-	NA	-	4.9E-03	0.7	6.7E-03	1.3	8.9E-04	1.6	3.6E+03	64.10	NA	NA	NA	NA
Transportation-Personnel	1.65	1.08	NA	-	NA	-	NA	-	5.8E-04	0.1	1.8E-05	0.0	1.0E-04	0.2	2.1E+01	0.4	2.9E-05	71.7	2.3E-03	66.0
Transportation-Equip/materials	0.11	0.07	NA	-	NA	-	NA	-	3.5E-05	0.0	6.1E-07	0.0	3.1E-06	0.0	1.4E+00	0.0	4.7E-07	1.2	3.8E-05	1.1
Equipment Use and Misc	137.61	89.67	1.5E-02	100.0	1.5E-03	100.0	1.3E-03	100.0	6.7E-01	99.1	4.9E-01	98.7	5.6E-02	98.2	2.0E+03	35.1	1.6E-06	4.1	4.1E-04	11.7
Residual Handling	1.70	1.11	0.0E+00	-	0.0E+00	-	0.0E+00	-	5.3E-04	0.1	9.4E-06	0.0	4.7E-05	0.1	2.2E+01	0.4	9.4E-06	23.1	7.5E-04	21.3
Total	153.46	100	1.46E-02	100.0	1.49E-03	100	1.32E-03	100	6.75E-01	100	4.99E-01	100	5.69E-02	100	5.60E+03	100	4.0E-05	100	3.5E-03	100

Environmental Footprint Summary continued

Activities	Water Usage	Percent Total	Electrical Usage	Lost Hours - Injury	Percent Total
	gallons	%	MWH		%
Material Productions	NA	NA	NA	NA	NA
Transportation-Personnel	NA	NA	NA	1.9E-02	66.0
Transportation-Equipment	NA	NA	NA	3.0E-04	1.1
Equipment Use and Misc	0.00	-	0.00E+00	3.3E-03	11.7
Residual Handling	NA	NA	NA	6.0E-03	21.3
Total	0.00E+00	100	0.00E+00	2.83E-02	100.0

Footprint Reduction

Total electricity replacement (MWh)	0.00E+00
Total electricity replacement (mmBtu)	0.00E+00
Percent electricity from renewable sources (%)	0.0%
Landfill gas reduction (metric ton CO_2 e)	0.00E+00
GHG emissions (metric ton CO2 e)	0.00E+00
NOx emissions (metric ton)	0.00E+00
SOx emissions (metric ton)	0.00E+00
PM10 emissions (metric ton)	0.00E+00
Water consumption reduction (gallons)	0.00E+00

NA: Not Available or Not Applicable

Additional Sustainability Metrics

Non-Hazardous Waste Landfill Space (tons)	0.0
Hazardous Waste Landfill Space (tons)	0.0
Topsoil Consumption (yd^3)	0.0
Cost of Phase ($)	0.0
Lost Hours - Injury	0.0

Duration of Phase

Duration (unit time)	1


CO_2e Emissions
1%
8%
90%
Material Productions
Transportation-Personnel
Transportation-Equip/materials
Equipment Use and Misc
Residual Handling


Energy Usage
1%
35%
64%
Material Productions
Transportation-Personnel
Transportation-Equip/materials
Equipment Use and Misc
Residual Handling


NOx Emissions
99%
Material Productions
Transportation-Personnel
Transportation-Equip/materials
Equipment Use and Misc
Residual Handling


SOx Emissions
99%
Material Productions
Transportation-Personnel
Transportation-Equip/materials
Equipment Use and Misc
Residual Handling


PM_{10} Emissions
98%
Material Productions
Transportation-Personnel
Transportation-Equip/materials
Equipment Use and Misc
Residual Handling


Accident Risk (Fatality)
0%
23%
4%
1%
72%
Material Productions
Transportation-Personnel
Transportation-Equip/materials
Equipment Use and Misc
Residual Handling


Accident Risk (Injury)
0%
21%
12%
1%
66%
Material Productions
Transportation-Personnel
Transportation-Equip/materials
Equipment Use and Misc
Residual Handling


Water Consumption
0%
Material Productions
Transportation-Personnel
Transportation-Equipment
Equipment Use and Misc
Residual Handling

Sustainable Remediation - Environmental Footprint Summary
SMP

Phase	Activities	GHG Emissions	Total Energy Used	Water Consumption	Electricity Usage	Onsite NOx Emissions	Onsite SOx Emissions	Onsite PM10 Emissions	Total NOx Emissions	Total SOx Emissions	Total PM10 Emissions	Accident Risk Fatality	Accident Risk Injury
		metric ton	MMBTU	gallons	MWH	metric ton	metric ton	metric ton	metric ton	metric ton	metric ton		
Site Management	Consumables	12.39	3.6E+03	NA	NA	NA	NA	NA	4.9E-03	6.7E-03	8.9E-04	NA	NA
	Transportation-Personnel	1.65	2.1E+01	NA	NA	NA	NA	NA	5.8E-04	1.8E-05	1.0E-04	2.9E-05	2.3E-03
	Transportation-Equipment	0.11	1.4E+00	NA	NA	NA	NA	NA	3.5E-05	6.1E-07	3.1E-06	4.7E-07	3.8E-05
	Equipment Use and Misc	137.61	2.0E+03	0.0E+00	0.0E+00	1.5E-02	1.5E-03	1.3E-03	6.7E-01	4.9E-01	5.6E-02	1.6E-06	4.1E-04
	Residual Handling	1.70	2.2E+01	NA	NA	0.0E+00	0.0E+00	0.0E+00	5.3E-04	9.4E-06	4.7E-05	9.4E-06	7.5E-04
	Sub-Total	153.46	5.60E+03	0.00E+00	0.00E+00	1.46E-02	1.49E-03	1.32E-03	6.75E-01	4.99E-01	5.69E-02	4.05E-05	3.54E-03
Total		**1.5E+02**	**5.6E+03**	**0.0E+00**	**0.0E+00**	**1.5E-02**	**1.5E-03**	**1.3E-03**	**6.7E-01**	**5.0E-01**	**5.7E-02**	**4.0E-05**	**3.5E-03**

Remedial Alternative Phase	Non-Hazardous Waste Landfill Space	Hazardous Waste Landfill Space	Topsoil Consumption	Costing	Lost Hours - Injury	Percent electricity from renewable sources	Total Cost with Footprint Reduction
	tons	tons	cubic yards	$		%	
Site Management	0.0E+00	0.0E+00	0.0E+00	0	2.8E-02	0.0%	$0
Total	0.0E+00	0.0E+00	0.0E+00	$0	2.8E-02	0.0%	


GHG Emissions
180.00
160.00
140.00
120.00
100.00
80.00
60.00
40.00
20.00
0.00
Metric Tons
Site Management
Residual Handling
Equipment Use and Misc
Transportation-Equipment
Transportation-Personnel
Consumables


Total Energy Used
6.00E+03
5.00E+03
4.00E+03
3.00E+03
2.00E+03
1.00E+03
0.00E+00
MMBTU
Site Management
Residual Handling
Equipment Use and Misc
Transportation-Equipment
Transportation-Personnel
Consumables


Water Consumption
1.00E+00
9.00E-01
8.00E-01
7.00E-01
6.00E-01
5.00E-01
4.00E-01
3.00E-01
2.00E-01
1.00E-01
0.00E+00
Gallons
Site Management
Residual Handling
Equipment Use and Misc
Transportation-Equipment
Transportation-Personnel
Consumables


Onsite NOx Emissions
1.60E-02
1.40E-02
1.20E-02
1.00E-02
8.00E-03
6.00E-03
4.00E-03
2.00E-03
0.00E+00
Metric Ton
Site Management
Residual Handling
Equipment Use and Misc
Transportation-Equipment
Transportation-Personnel
Consumables


Onsite SOx Emissions
1.60E-03
1.40E-03
1.20E-03
1.00E-03
8.00E-04
6.00E-04
4.00E-04
2.00E-04
0.00E+00
Metric Ton
Site Management
Residual Handling
Equipment Use and Misc
Transportation-Equipment
Transportation-Personnel
Consumables


Onsite PM10 Emissions
1.40E-03
1.20E-03
1.00E-03
8.00E-04
6.00E-04
4.00E-04
2.00E-04
0.00E+00
Metric Ton
Site Management
Residual Handling
Equipment Use and Misc
Transportation-Equipment
Transportation-Personnel
Consumables


Total NOx Emissions
8.00E-01
7.00E-01
6.00E-01
5.00E-01
4.00E-01
3.00E-01
2.00E-01
1.00E-01
0.00E+00
Metric Ton
Site Management
Residual Handling
Equipment Use and Misc
Transportation-Equipment
Transportation-Personnel
Consumables


Total SOx Emissions
6.00E-01
5.00E-01
4.00E-01
3.00E-01
2.00E-01
1.00E-01
0.00E+00
Metric Ton
Site Management
Residual Handling
Equipment Use and Misc
Transportation-Equipment
Transportation-Personnel
Consumables


Total PM10 Emissions
6.00E-02
5.00E-02
4.00E-02
3.00E-02
2.00E-02
1.00E-02
0.00E+00
Metric Ton
Site Management
Residual Handling
Equipment Use and Misc
Transportation-Equipment
Transportation-Personnel
Consumables


Accident Risk - Fatality
4.50E-05
4.00E-05
3.50E-05
3.00E-05
2.50E-05
2.00E-05
1.50E-05
1.00E-05
5.00E-06
0.00E+00
Risk of Fatality
Site Management
Residual Handling
Equipment Use and Misc
Transportation-Equipment
Transportation-Personnel
Consumables


Accident Risk - Injury
4.00E-03
3.50E-03
3.00E-03
2.50E-03
2.00E-03
1.50E-03
1.00E-03
5.00E-04
0.00E+00
Risk of Injury
Site Management
Residual Handling
Equipment Use and Misc
Transportation-Equipment
Transportation-Personnel
Consumables

Non-Hazardous Waste Landfill Space
1.0E+00
9.0E-01
8.0E-01
7.0E-01
6.0E-01
5.0E-01
4.0E-01
3.0E-01
2.0E-01
1.0E-01
0.0E+00
Tons
Site Management

Hazardous Waste Landfill Space
1.0E+00
9.0E-01
8.0E-01
7.0E-01
6.0E-01
5.0E-01
4.0E-01
3.0E-01
2.0E-01
1.0E-01
0.0E+00
Tons
Site Management


Topsoil Consumption
1.0E+00
9.0E-01
8.0E-01
7.0E-01
6.0E-01
5.0E-01
4.0E-01
3.0E-01
2.0E-01
1.0E-01
0.0E+00
cubic yards
Site Management


Costing
1
1
1
1
1
1
0
0
0
0
0
$
Site Management


Lost Hours - Injury
3.0E-02
2.5E-02
2.0E-02
1.5E-02
1.0E-02
5.0E-03
0.0E+00
Hours
Site Management

Climate Screening Checklist

Background Information

- Project Manager: Rafi Alam, DEC Project Manager
- Site Name: 12074 Flatlands Avenue p/o Lot 1
- Site Number: NYSDEC BCP Site No. C224353
- Site Location: 35 Inspiration Lane (F/K/A 12074 Flatlands Avenue, Brooklyn, NY)
- Site Elevation (average above sea level): 19
- ClimAID Region (Responding Climate Change in New York State (ClimAID) - NYSERDA): Region 4
- Remedial Stage/site classification:

  Site Classification: Active

- Contamination - Media Impacted/ Contaminants of Concern:
  Impacted media include soil, groundwater, and soil vapor. Analytical data indicates that fill material contains SVOCs, pesticides, PCBs and metals at concentrations greater than the Unrestricted Use SCOs, Restricted-Residential RUSCOs, and/or the Protection of Groundwater SCOs and PFAS at concentrations greater than the Unrestricted Use Guidance Values. Groundwater contains SVOCs and metals above the SGVs and PFAS above the NYSDEC guidance thresholds. Soil vapor at the Site is impacted with low levels of petroleum-related VOCs and CVOCs (cis-1,2 DCE and vinyl chloride) which were detected at concentrations above the NYSDOH guidance levels which would trigger monitoring or mitigation if detected as part of a post-remediation soil vapor intrusion evaluation.
- Proposed/Current Remedy:
  The Track 2 Restricted-Residential Remedy includes excavation of fill material up to 15 feet below ground surface (bgs), excavation of two barium hotspot areas up to 22 feet bgs, excavation of hazardous material up to 27.5 feet bgs, collection of endpoint samples, installation of a vapor barrier membrane, recording of an Environmental Easement and established of a Site Management Plan.
- What is the predicted timeframe of the remedy? Will components of the remedy still be in place in 10+ years?

  The predicted time frame is 50+ years. Components of the remedy will still be in place in 10+ years.

- Is the site in proximity to any sensitive receptors? (e.g. wetlands, waterbodies, residential properties, hospitals, schools, drinking water supplies, etc.)

  Surrounding properties include commercial, industrial, and automotive uses to the north, residential properties to the east and south, and parking lots and the CCC building to the west. No sensitive receptors were identified within 500 feet of the Site.

Is the site in a disadvantaged community (DAC) or potential environmental justice area (PEJA) (Use DECinfolocator: DECinfo Locator (ny.gov))?

☒ **Yes** ☐ **No**

If the site is in a DAC or PEJA, will climate impacts be magnified? If yes, list how and why.

☐ **Yes** ☒ **No**

Should thresholds of concern be lowered to account for magnification of impacts? If yes, indicate how lower thresholds will be used in the screening.

N/A ☐ **Yes** ☐ **No**

Climate Screening Table*

Potential Climate Hazards	**Relevant to the Site Location** (Y/N/NA)[1]	**Projected Change** (Reference data source/Model)[3]	**Potential to Impact Remedy** (Y/N)	**Is remedy/site already resilient?** (Y/N)[4]
Precipitation	N	N (RAPT ArcGIS)	N/A	N/A
Temperature[2] (Extreme Heat or Cold Weather Impacts)	Y	3-7 Day Hazardous Heat (RAPT ArcGIS)	N	Y
Sea Level Rise	N	N (NOAA)	N/A	N/A
Flooding	N	N/A	N/A	N/A
Storm Surge	Y	<3 feet above ground (NHC Storm Surge Map)	N	Y
Wildfire	N	N/A	N/A	N/A
Drought	N	N/A	N/A	N/A
Storm Severity	N	N (RAPT ArcGIS)	N/A	N/A
Landslides	N	N/A	N/A	N/A
Other Hazards:	N/A	N/A	N/A	N/A

* Links to potential data sources can be found on the following page

[1] If the first column is N --> The rest of the columns will be N/A, the hazard is not applicable to the site.

[2] Extreme Heat: periods of three or more days above 90°F- Extreme Cold: Individual days with minimum temperatures at or below 0 degrees F (NYSERDA ClimAID report)

[3] List the projected change in specific terms or units e.g. inches of rain fall, feet of sea level rise, etc.

[4] If final column is Y, provide reasoning, if the final column is N --> Climate Vulnerability Assessment (CVA) required.

Required Next Steps (If no further action is required, provide justification):

Temperature hazards for building residents are not anticipated because the building will be constructed with a central HVAC system.

Storm surge hazards for building residents are not anticipated. Based on the National Hurricane Center Storm Surge Risk Maps dated 2021, a storm surge is likely to impact the site for a Category 3 or higher storm. The NYC Risk Landscape: Guide to Hazardous Mitigation cites the National Hurricane Center data point that Category 3 storms only impact NYC every 74 years.

APPENDIX G

Health and Safety Plan

LANGAN

HEALTH AND SAFETY PLAN

for

12074 FLATLANDS AVENUE P/O LOT 1 SITE
35 Inspiration Lane
F/K/A 12074 Flatlands Avenue
Brooklyn, New York

NYSDEC BCP Site No. C224353

Prepared For:

Innovative Urban Living, LLC
IUV Phase 1B Owner, LLC
IUV Phase 1B LIHTC Owner, LLC
c/o Gotham Organization, LLC
111 Fifth Avenue, 9th Floor
New York, New York 10016

Prepared By:

Langan Engineering, Environmental, Surveying,
Landscape Architecture and Geology, D.P.C.
300 Kimball Drive
Parsippany, New Jersey 07054

July 2025
100688803

LANGAN

ENVIRONMENTAL HEALTH AND SAFETY PLAN

Volunteer:	**Innovative Urban Living, LLC; IUV Phase 1B Owner, LLC; IUV Phase 1B LIHTC Owner, LLC**
Project:	**Annual Site Inspection and Groundwater Sampling**
Location:	**35 Inspiration Lane F/K/A 12074 Flatlands Avenue**
Chemical Hazards:	**Volatile Organic Compounds, Semi-Volatile Organic Compounds, Polychlorinated Biphenyls, Pesticides, Metals, Per- and polyfluoroalkyl substances**
Prepared By:	**Langan Engineering, Environmental, Surveying, Landscape Architecture and Geology, D.P.C.**
Version:	**1**
Date:	**July 2025**

Volunteer Contact:	**Bryan Kelly**	**(212) 599-0520**
Langan Project Manager (PM):	**Amanda Forsburg**	**(973) 560-4900**
Langan Health & Safety Manager (HSM):	**Tony Moffa, CHMM**	**(215) 491-6545**
Langan Health and Safety Officer (HSO):	**Field Personnel, TBD**	
WorkCare:		**1-888-449-7787**
Langan Incident/Injury Hotline:		**(973) 560-4699**

LANGAN ENGINEERING, ENVIRONMENTAL, SURVEYING, LANDSCAPE ARCHITECTURE AND GEOLOGY, D.P.C. (LANGAN), AND LANGAN SUBCONTRACTORS, DO NOT GUARANTEE THE HEALTH OR SAFETY OF ANY PERSON ENTERING THIS SITE. DUE TO THE NATURE OF THIS SITE AND THE ACTIVITY OCCURRING THEREON, IT IS NOT POSSIBLE TO DISCOVER, EVALUATE, AND PROVIDE PROTECTION FOR ALL POSSIBLE HAZARDS WHICH MAY BE ENCOUNTERED. STRICT ADHERENCE TO THE HEALTH AND SAFETY GUIDELINES SET FORTH HEREIN WILL REDUCE, BUT NOT ELIMINATE, THE POTENTIAL FOR INJURY AT THIS SITE. THE HEALTH AND SAFETY GUIDELINES IN THIS PLAN WERE PREPARED SPECIFICALLY FOR THIS SITE AND SHOULD NOT BE USED ON ANY OTHER SITE WITHOUT PRIOR RESEARCH AND EVALUATION BY A TRAINED HEALTH AND SAFETY SPECIALIST.

APPROVALS

By signature, the personnel identified below hereby acknowledge that they have reviewed this Health and Safely Plan (HASP) and agree to comply with the requirements contained therein as well as the applicable provisions of 29 CFR Parts 1910 and 1926. The undersigned also acknowledge and accept that this HASP is the project HASP for the site work described in the Site Management Plan (SMP). Furthermore, in reviewing and accepting this HASP, as currently written, the undersigned agree that to the best of their knowledge, this HASP adequately identifies the activities and hazards associated with work at this site and describes the appropriate and necessary precautions and protections for site workers required by the applicable OSHA statutes and regulations.

Amanda M. Forsburg	7/30/2025
LANGAN Project Manager / PM (Amanda Forsburg)	Date
LANGAN Health and Safety Manager (Tony Moffa, CHMM)	Date
LANGAN Health and Safety Officer – HSO	Date

TABLE OF CONTENTS

1.0 INTRODUCTION 1

1.1 Purpose and Policy 1
1.2 Site Descriptions 3
1.3 Scope of Work 3

2.0 PROJECT TEAM ORGANIZATION AND RESPONSIBILITIES 4

2.1 Langan Project Manager 4
2.2 Health and Safety Manager (HSM) 4
2.3 Health and Safety Officer (HSO) 5

3.0 HAZARDS ANALYSIS 5

3.1 General Hazard Assessment 6
3.2 Chemical Exposure Hazards 6
3.2.1 Specific Chemical Hazards Previously Detected at the Site 6
3.2.2 Chemical Hazard Exposure Routes 7
3.2.3 Control of Exposure to Chemical Hazards 7
3.3 Physical Hazards 8
3.3.1 Temperature Extremes 8
3.3.2 Noise and Air Resources 8
3.3.3 Hand and Power Tools 8
3.3.4 Slips, Trips, and Falls 9
3.3.5 Fire and Explosion 9
3.3.6 Material Handling 9
3.3.7 Confined Space/Excavation Hazards 10
3.3.8 Working Near Equipment 10
3.3.9 Drill Rig Operations 10
3.3.10 Electrical Safety 11
3.3.11 Utilities 11
3.3.12 Vehicular Traffic 12
3.4 Biological Hazards 12
3.4.1 Animals 12
3.4.2 Insects 12
3.4.3 Wound Care 12
3.5 Task Hazard Analysis 13
3.5.1 Monitoring Well Installation 13
3.5.2 Groundwater Sample Collection 13

4.0 PERSONAL PROTECTIVE EQUIPMENT (PPE) 14

4.1 Levels of Protection 14
4.2 Respirator Fit-Test 15
4.3 Respirator Cartridge Change-Out Schedule 15

5.0 AIR QUALITY MONITORING AND ACTIONS LEVELS 16

5.1 Monitoring During Site Operations 16
5.1.1 Volatile Organic Compounds 16
5.1.2 Dust 17
5.2 Monitoring Equipment Calibration and Maintenance 17
5.3 Determination of Background Levels 17

6.0 COMMUNITY HEALTH AND SAFETY CONSIDERATIONS 18

LANGAN

TABLE OF CONTENTS
(Continued)

7.0 WORK ZONES and DECONTAMINATION 18

7.1 Site Control 18
7.2 Contamination Control 19
7.2.1 Personnel Decontamination Station 19
7.2.2 Minimization of Contact with Contaminants 19
7.2.3 Personnel Decontamination Sequence 19
7.2.4 Emergency Decontamination 19
7.2.5 Hand-Held Equipment Decontamination 20
7.2.6 Heavy Equipment Decontamination 20
7.3 Communications 20

8.0 MEDICAL SURVEILLANCE 21

9.0 EMERGENCY RESPONSE PLAN 21

9.1 Responsibilities 21
9.1.1 Health and Safety Officer (HSO) 21
9.1.2 Emergency Coordinator 22
9.1.3 Site Personnel 22
9.2 Communications 22
9.3 Local Emergency Support Units 23
9.4 Pre-Emergency Planning 23
9.5 Emergency Medical Treatment 23
9.6 Non-Emergency Medical Treatment 24
9.7 Emergency Site Evacuation Routes and Procedures 24
9.8 Fire Prevention and Protection 25
9.8.1 Fire Prevention 25
9.9 Significant Vapor Release 25
9.10 Overt Chemical Exposure 26
9.11 Decontamination During Medical Emergencies 26
9.12 Incident Reporting 27
9.13 Adverse Weather Conditions 27
9.14 Spill Control and Response 28
9.15 Emergency Equipment 29
9.16 Restoration and Salvage 29

10.0 TRAINING 29

10.1 General Health and Safety Training 29
10.2 Site-Specific Training 30
10.3 Onsite Safety Briefings 30
10.4 Hazard Communication 30

11.0 RECORDKEEPING 30

11.1 Field Change Authorization Request 30
11.2 Medical and Training Records 31
11.3 Onsite Log 31
11.4 Daily Safety Meetings (“Tailgate Talks”) 31
11.5 Exposure Records 31
11.6 Hazard Communication Program/SDS 31
11.7 Documentation 31

12.0 FIELD PERSONNEL REVIEW 32

TABLE OF CONTENTS
(Continued)

TABLES

Table 1	Contaminants of Concern
Table 2	Selected Chemical Exposure Limits and Health Effects
Table 3	Hazard Analysis
Table 4	Instrument Action Levels
Table 5	Personal Protective Equipment

FIGURES

Figure 1	Site Location Map
Figure 2	Hospital Route Map

ATTACHMENTS

Attachment A	Health and Safety Briefing Statement
Attachment B	Field Procedures Change Authorization Form
Attachment C	Unsafe Conditions and Practices Form
Attachment D	Calibration Log
Attachment E	Emergency Notification Numbers
Attachment F	Accident / Incident Report Form
Attachment G	Safety Data Sheets (SDS)
Attachment H	Jobsite Safety Inspection Checklist
Attachment I	Langan Guidelines

1.0 INTRODUCTION

1.1 Purpose and Policy

This Health and Safety Plan (HASP) has been developed to comply with the regulations under Occupational Safety and Health Administration (OSHA) 29 CFR 1910.120(b)(4), Hazardous Waste Operations and Emergency Response. It addresses foreseeable activities associated with the site work activities to be conducted at 35 Inspiration Lane F/K/A 12074 Flatlands Avenue (see Figure 1). This HASP establishes personnel protection standards and mandatory safety practices and procedures. Additionally, it assigns responsibilities, establishes standard operating procedures, and provides for contingencies that may arise while operations are being conducted at known or suspected hazardous waste sites.

Langan personnel involved with inspection of site work activities which involve the displacement of soil and/or material groundwater during the implementation of the SMP shall comply with the requirements of this HASP. All Langan personnel engaged in onsite activities will read this document carefully and complete the Safety Briefing Form (Attachment A), a copy of which will be saved to Langan's Project files. Contractors and subcontractors conducting investigation- or construction-related activities which will disturb or displace soil in areas where a Track 2 restricted-residential restricted use remedy was achieved are required to develop and follow their own HASP which must be equal or more stringent than the Langan HASP. Contractors and subcontractors are responsible for their own workers Health and Safety and providing a safe working environment in accordance with all applicable federal, state and local requirements. Each Subcontractor will have a designated Site Health and Safety Manager who will be responsible for ensuring that the designated procedures are implemented in the field. Personnel who have any questions or concerns regarding implementation of this plan are encouraged to request clarification from the Langan Project Manager. Field personnel must follow the designated health and safety procedures, be alert to the hazards associated with working close to vehicles and equipment and use common sense and exercise reasonable caution at all times.

This HASP covers field activities which have the potential to disturb and/or displace remaining contaminated fill material or groundwater impacted with volatile organic compound (VOCs), semi-volatile organic compounds (SVOCs), metals, polychlorinated biphenyls (PCBs), Per- and Polyfluoroalkyl Substances (PFAS), and/or pesticides as identified in the Site Management Plan and Final Engineering Report.

This HASP was prepared in accordance with the following documents and/or guidelines:

- Occupational Safety and Health Administration (OSHA) regulations for hazardous site workers (29 CFR 1910.120 and 29 CFR 1926); and,
- NIOSH/OSHA/USCG/USEPA *Occupational Safety and Health Guidance Manual for Hazardous Waste Site Activities.*

Langan's Health and Safety Program and Safe Operating Procedures support this site-specific HASP.

The level of protection and the procedures specified in this HASP represent the minimum health and safety requirements to be observed by site personnel engaged in the referenced activities. Unknown conditions may exist and known conditions may change. Should an employee find themself in a potentially hazardous situation, the employee will immediately discontinue the hazardous procedures(s) and either personally effect appropriate preventative or corrective measures, or immediately notify the Health and Safety Officer or the Langan Project Manager of the nature of the hazard. In the event of an immediately dangerous or life- threatening situation, the employee always has "stop work" authority. Any necessary revision to the Health and Safety procedures will be recorded in the Field Procedure Change Authorization Form (Attachment B) and will require authorization from the Langan Health and Safety Officer and Project Manager.

The provisions of this HASP address worker health and safety within defined contaminant zones and assume that work will be completed within an active construction site and within a sidewalk. Additional provisions including the visual demarcation of the work zone and use of pedestrian control measures and will be employed in order to avoid possible hazards associated with construction activities and pedestrians.

THE ULTIMATE RESPONSIBILITY FOR THE HEALTH AND SAFETY OF THE INDIVIDUAL EMPLOYEE RESTS WITH THE EMPLOYEE AND HIS OR HER COLLEAGUES. Each employee is responsible for exercising the utmost care and good judgment in protecting their own health and safety and that of fellow employees. Should any employee observe a potentially unsafe condition or situation, it is the responsibility of that employee to immediately bring the observed condition to the attention of the appropriate health and safety personnel as designated above and to follow-up the verbal notification by completing the

Unsafe Conditions and Practices Form provided in Attachment C, a copy of which will be provided to the Langan Health and Safety Officer.

"Extenuating" circumstances such as budget or time constraints, equipment breakdown, changing or unexpected conditions, never justify unsafe work practices or procedures. In fact, the opposite is true. Under stressful circumstances all project personnel must be mindful of the potential to consciously or unconsciously compromise health and safety standards and be especially safety conscious. **ALL SITE PERSONNEL ARE EXPECTED TO CONSIDER "SAFETY FIRST" AT ALL TIMES.**

1.2 Site Descriptions

The Site is designated as Block 4434 Lot 1 by the New York City Department of Finance. The Site Location Plan is provided as Figure 1. The Site is an approximately 90,780-square-foot parcel and is bound to the north by Flatlands Avenue followed by an automobile dismantling company and used automobile parts business, medical offices, and the Oasis Hotel; to the east by a twelve-story multi-family residential apartment building and Block 4434 Lot 10 (BCP Site No. C224290), which is an active construction site; to the south by a twelve-story multi-family residential apartment building; and to the west by Block 4434 Lot 100, which is being used as a construction logistics zone for the Site, followed by the Christian Cultural Center (CCC) building and the surrounding asphalt-paved parking lot.

1.3 Scope of Work

The activities that will require the oversight by Langan personnel include the following task:

- Task 1 – Annual Site Inspection.
- Task 2 – Monitoring Well Installation.
- Task 3 – Groundwater Sampling.

The following activities, which would require oversight by Langan personnel, may be necessary if the Excavation Work Plan (Appendix D of the Site Management Plan) is implemented:

- Task 4 – Excavation and off-site disposal of excavated soil;
- Task 5 – Completion of excavation dewatering;
- Task 6 – Restoration of the building slab and/or asphalt pavement; and,
- Task 7 – Restoration of the vapor barrier.

Details of the scopes of work to be completed in each of the work areas for this project are provided within the 12074 Flatlands Avenue p/o Lot 1 Site - Site Management Plan (SMP).

All excavated soil/fill at the site will be either transported off site for disposal at an approved facility or reused on-site pending NYSDEC approval. Personnel conducting activities that will contact the impacted soil/fill or other impacted materials shall abide to the provisions of this HASP.

2.0 PROJECT TEAM ORGANIZATION AND RESPONSIBILITIES

This section specifies the Langan Engineering, Environmental, Surveying, Landscape Architecture and Geology, D.P.C. (Langan) Project Organization.

2.1 Langan Project Manager

The Langan Project Manager (PM) is Amanda Forsburg. The PM responsibilities include:

Responsibilities:

- Prepares and organizes the background review of site conditions, the site HASP, and the field team.
- Obtains permission for site access and coordinates activities with appropriate officials.
- Briefs the field team on their specific assignments.
- Coordinates with the Health and Safety Officer (HSO) to ensure that health and safety requirements are met.
- Serves as the liaison with public officials.
- Ensuring that this HASP is developed and approved prior to on-site activities.
- Ensuring that all the tasks in the project are performed in a manner consistent with Langan's comprehensive Health and Safety Program for Hazardous Waste Operations and this HASP.

2.2 Health and Safety Manager (HSM)

The Langan Corporate Health and Safety Manager (HSM) is Tony Moffa. His responsibilities include:

- Serving as a resource in the development and implementation of HASPs;
- Assist in reviewing results of Jobsite Safety Inspections;

- Assisting site Health and Safety Officer (HSO) with development of the HASP, updating HASP as dictated by changing conditions, jobsite inspection results, etc.;
- Maintaining all records on personnel (medical evaluation results, training and certifications, accident investigation results, etc.).

2.3 Health and Safety Officer (HSO)

The Langan Health and Safety Officer (HSO) will be identified prior to the start of field work. The HSO responsibilities include:

- Participating in the development and implementation of this HASP;
- Conducting Jobsite Safety Inspections (Attachment H) and correcting any shortcomings in a timely manner;
- Helping to select proper PPE (Personal Protective Equipment) and periodically inspecting it;
- Ensuring that PPE is properly stored and maintained;
- Controlling entry into and exit from the contaminated areas or zones of the site;
- Confirming each team member's suitability for work based on a current physician's recommendation;
- Monitoring the work parties for signs of stress, such as heat stress, fatigue, and cold exposure;
- Monitoring site hazards and conditions;
- Knowing (and ensuring that all site personnel also know) emergency procedures, evacuation routes, and the telephone numbers of the ambulance, local hospital, poison control center, fire department, and police department;
- Resolves conflicting situations which may arise concerning safety requirements and working conditions;
- Conducting daily tailgate meetings to review applicable JSAs as well as check-in with site personnel.

3.0 HAZARDS ANALYSIS

This section presents all assessment of the general, chemical, physical and biological hazards that may be encountered during the tasks specified under this HASP (Section 1.3). The types of potential contaminants of concerns Langan anticipates encountering during implementation of the SMP are listed in Tables 1 and 2 of this HASP.

3.1 General Hazard Assessment

A general hazard assessment was conducted for the required field work described in Section 1.3 and the following potential hazards have been identified:

- Inhalation of volatile contaminants;
- Skin and eye contact with contaminants;
- Ingestion of contaminants;
- Inhalation of dusts impacted with VOCs, SVOCs, pesticides, PCBs, PFAS, and metals;
- Physical hazards associated with the use of heavy equipment;
- Excavation hazards;
- Tripping hazards;
- Noise exposure;
- Heat stress (depending on weather conditions);
- Cold exposure (depending on weather conditions);
- Flammable hazards;
- Electrical hazards; and,
- Use of personal protective equipment.

These hazards are further described in the task-by-task hazard analysis in Table 3. Specific chemical, physical and biological hazards are discussed below.

Mitigation and controls will include as needed work procedures, work/rest regiment, dust control measures, personal protective equipment, and respiratory protection as appropriate.

3.2 Chemical Exposure Hazards

The following chemical hazard evaluation for the proposed site management activities is based on the previous environmental investigation and collection of post-excavation documentation soil samples at the site. The evaluation has been conducted to identify chemicals/materials that potentially may be present at the site, and to ensure that work activities, personnel protection, and emergency response are consistent with the specific contaminants that potentially could be encountered.

3.2.1 Specific Chemical Hazards Previously Detected at the Site

Contaminated fill material, which may be impacted with SVOCs, pesticides, PCBs, PFAS, and metals, remains at the Site as reported in the

Site Management Plan and Final Engineering Report. In addition, groundwater impacted with VOCs and metals, and soil vapor impacted with chlorinated VOCs and petroleum-related VOCs was identified on-site as documented in the Remedial Investigation Report.

Table 1 lists Contaminants of Concern and potentially affected media. The potential contaminants that might be encountered during the field activities and the exposure limits are listed in Table 2.

3.2.2 Chemical Hazard Exposure Routes

Potential hazards and their exposure routes include:

- Inhalation of organic vapors due to the presence of volatile organic compounds from diesel-powered equipment and minimal volatilization potential related to the presence of PAHs in soil.
- Inhalation of dust impacted with PAHs, PCBs, metals, PFAS, or pesticides associated with monitoring well installation and construction activity.
- Inadvertent ingestion of potentially toxic substances via hand to mouth contact or deliberate ingestion of materials inadvertently contaminated with potentially toxic materials.
- Dermal exposure and possible percutaneous (skin) absorption of certain lipophilic (readily absorbed through the skin) PAHs and pesticides.
- Skin and eye contact with contaminants at the site and decontamination activities.

Exposure limits and health effects of selected chemicals are in Table 2. The probability of exposure for each task is outlined in Table 3.

3.2.3 Control of Exposure to Chemical Hazards

To protect potentially exposed personnel the following procedures and protocols will be adopted and used as needed: work procedures will be adhered to, work zones will be established, dust control will be utilized, respirators (if required) and personal protective equipment will be worn, area air monitoring will be conducted during times of disturbance of the impacted fill material and strict personnel decontamination procedures will be followed.

3.3 Physical Hazards

3.3.1 Temperature Extremes

Hot Temperatures

Heat stress is a significant potential hazard, which is greatly exacerbated with the use of PPE, in hot environments. The potential hazards of working in hot environments include dehydration, cramps, heat rash, heat exhaustion, and heat stroke. If onsite workers exhibit the signs of heat exhaustion or heat stroke, they should seek immediate medical attention.

Cold Temperatures

Workers may be exposed to the hazard of working in a cold environment. Potential hazards in cold environments include frostbite, trench foot or immersion foot, hypothermia, as well as slippery surfaces, brittle equipment, poor judgment, and unauthorized procedural changes. In order to prevent frostbite, hypothermia, trench foot and immersion foot, the workers are responsible for dressing warmly in layers with thick socks, gloves, and appropriate head and face gear. Upon the onset of discomfort due to the cold, onsite workers should take regular five to ten minute breaks to warm up inside nearby buildings and to drink warm fluids. Please note that the NYCDEP statute prohibits idling an engine for more than three minutes (one-minute if adjacent to a school). This statue includes the use of a vehicle for the purpose of warming up employees. As such, all contractors and employees shall identify a place to warm up in advance. If discomfort continues and the onsite workers start to exhibit the signs of frostbite, hypothermia, trench foot or immersion foot, they should seek immediate medical attention.

3.3.2 Noise and Air Resources

Noise is a potential hazard associated with the operation of heavy equipment, power tools, pumps and generators. Hearing protection is required and shall be used in designated areas of the site as indicated by the posted signs.

3.3.3 Hand and Power Tools

In order to complete the various tasks for the project, personnel will utilize hand and power tools. The use of hand and power tools can present a variety of hazards, including physical harm from being struck by flying objects, being cut or struck by the tool, fire, and electrocution. Hand and

power tools will be inspected prior to use. Proper personal protective equipment shall be worn while utilizing hand and power tools. Ground Fault Circuit Interrupters (GFCIs) are required for all portable electric tools.

3.3.4 Slips, Trips, and Falls

Working in and around the site will pose slip, trip and fall hazards due to equipment, piping, slippery surfaces that may be oil covered, or from surfaces that are wet from rain or ice. Potential adverse health effects include falling to the ground and becoming injured or twisting an ankle. Good housekeeping at the site must be maintained at all times.

3.3.5 Fire and Explosion

Prior to starting all excavation work, a review of appropriate New York City maps will be conducted to identify potential hazards. The possibility of encountering fire and explosion hazards exists from underground utilities and gases. Therefore, all excavation equipment must be grounded.

3.3.6 Material Handling

Manual lifting of heavy objects may be required. Failure to follow proper lifting techniques can result in back injuries and strains. Back injuries are a serious concern as they are the most common workplace injury, often resulting in lost or restricted work time, and long treatment and recovery periods.

Whenever possible, heavy objects must be lifted and moved by mechanical devices rather than by manual effort. The mechanical devices will be appropriate for the lifting or moving task and will be operated only by trained and authorized personnel. Objects that require special handling or rigging will only be moved under the guidance of a person who has been specifically trained to move such objects, such as a Master Rigger or equivalent. Lifting devices, including equipment, slings, ropes, chains, and straps, will be inspected, certified, and labeled to confirm their weight capacities. Defective equipment will be taken out of service immediately and repaired or destroyed.

The wheels of any trucks being loaded or unloaded, and/or parked on an incline, will be chocked to prevent movement. If applicable, outriggers will be extended on a flat, firm surface during operation. The lift and swing path of a crane/equipment will be watched and maintained clear of

obstructions. Personnel will not pass under a raised load, nor will a suspended load be left unattended. Personnel will not be carried on lifting equipment, unless it is specifically designed to carry passengers.

All reciprocating, rotating, or other moving parts will be guarded at all times. Accessible fire extinguishers will be made available in all mechanical lifting devices. All material must be stored in tiers, racked, blocked, or otherwise secure to prevent sliding, falling, or collapse. All loads/material will be verified to be secure before transportation.

3.3.7 Confined Space/Excavation Hazards

Personnel entry into trenches or unshored (*e.g.,* lagging) excavations within the designated areas of concern will not be permitted. No other confined spaces are known to exist on Site. If entry into trenches or excavations is required, all work will stop until the HASP has been revised to address the new hazards.

3.3.8 Working Near Equipment

Personnel working in the immediate vicinity of heavy equipment (*e.g.*, excavators, loaders, etc.) may encounter physical hazards resulting from contact with equipment. Field personnel should be aware of the presence of these hazards at all times and take appropriate action to avoid them. Due to the limited ability to communicate when wearing respiratory protection, the risk is increased. Workers must be careful to communicate with heavy equipment operators regarding their location and should maintain a safe distance from operating equipment at all times. Prior to working around equipment, the site personnel will review appropriate hand signals with the operator.

Equipment will be equipped with back up alarms.

3.3.9 Drill Rig Operations

In order to install monitoring wells, a track-mounted Geoprobe drill rig will be used. Working with and near this equipment and associated power generators pose many potential hazards, including being struck by or against, or pinched/caught by moving parts. These hazards can result in serious physical harm. Other hazards include electrocution and explosion due to encountering overhead or underground utilities.

Drill rigs for hollow stem auger drilling and other machinery with exposed moving parts must be equipped with an operational emergency stop device. Drillers and other field personnel must be aware of the location of this device. This device must be tested prior to job initiation and periodically thereafter. The driller and helper shall not simultaneously handle augers unless there is a standby person to activate the emergency switch. Only equipment that has been approved by the manufacturer may be used in conjunction with site equipment and specifically to attach sections of drilling tools together. Pins that protrude excessively from augers shall not be allowed.

The driller must never leave the controls while the tools are rotating unless all personnel are kept clear of rotating equipment. A remote sampling device must be used to sample drill cuttings if the tools are rotating or if the tools are readily capable of rotating. Samplers must not reach into or near the rotating equipment. Drillers, helpers, and other field personnel must secure all loose clothing when in the vicinity of drilling operations. No person shall climb the drill mast while tools are rotating or without the use of ANSI-approved fall protection (approved belts, lanyards and a fall protection slide rail) or portable ladder that meets the requirement of the OSHA standard.

3.3.10 Electrical Safety

Personnel may utilize hand and power tools. The use of hand and power tools can present a variety of hazards, including physical harm from being struck by flying objects, being cut or struck by the tool, fire, and electrocution. Ground Fault Circuit Interrupters (GFCIs) are required for all portable electric tools.

3.3.11 Utilities

Prior to the start of any intrusive work, the location of aboveground and underground utilities and other structures will be completed by the contractor/subcontractor responsible for completing investigation and/or construction activities.

3.3.12 Vehicular Traffic

Portions of site activities (load in and load out) will be conducted in the street so vehicular and pedestrian traffic will be present. Appropriate precautions to protect the on-site workers and civilians should be used including the use of cones and traffic vests as appropriate.

3.4 Biological Hazards

During the course of the project, there is a potential for workers to come into contact with biological hazards such as animals and insects. As the potential for exposure to blood borne pathogens during implementation of the SMP is anticipated to be low, a Blood Borne Pathogen Exposure Plan (BBPEP) is not required. A BBPEP will be prepared if site operation requires its implementation.

3.4.1 Animals

During site operations, animals such as dogs, cats, pigeons, mice, and rats may be encountered. Workers shall use discretion and avoid all contact with animals. Bites and scratches from dogs and cats can be painful and if the animal is rabid, the potential for contracting rabies exists. Contact with rat and mice droppings may lead to contracting hantavirus. Inhalation of dried pigeon droppings may lead to psittacosis. Cryptococcosis and histoplasmosis are also diseases associated with exposure to dried bird droppings but these are less likely to occur in this occupational setting.

3.4.2 Insects

Insects, including bees, wasps, hornets, mosquitoes, spiders, and ticks may be present at the site. Some individuals may have a severe allergic reaction to an insect bite or sting that can result in a life threatening condition. In addition, mosquito bites may lead to St. Louis encephalitis or West Nile encephalitis.

3.4.3 Wound Care

A source of occupational exposure may occur when an employee gives First Aid and or CPR to an individual who had infectious blood. The occupational exposure occurs when there is the possibility for an employee's eyes, mucous membranes, non-intact skin (i.e., cut and abraded skin) to come into contact with potentially infectious materials from another employee. If an accident were to occur where First Aid

would need to be administered, the person administering the First Aid will presume that any wounds and materials used are contaminated with BBP and should wear the appropriate PPE to prevent contact with these materials. Additionally, should the use of First Aid materials and or clothing that was potentially contaminated with BBP be encountered these materials should be property containerized and transported to the nearest hospital for proper disposal.

3.5 Task Hazard Analysis

The tasks to be completed during the proposed site work activities, as summarized in Section 1.3, are listed in Table 3 with a Hazard Analysis for each task.

3.5.1 Monitoring Well Installation

Monitoring wells will be installed for the collection of groundwater samples. Special attention shall be given to establishing the location of any underground utilities prior to boring or drilling. Prior to beginning the site investigation work, the N.Y. One Call Center will be contacted by the boring/drilling contractor for utility mark-outs. Additionally, a private utility clearance subcontractor has been retained to complete a geophysical survey in the vicinity of each boring location to identify the potential presence of underground utility lines and to evaluate for the presence of USTs and any other subsurface anomalies. Pressure safety valves and hose whip prevention devices will be installed and operational on any air compressors, hoses, and their tools to be used on site.

Chemical exposure may also occur as temporary monitoring wells are installed. Activities will be conducted in Level D.

If evidence of unanticipated contamination is encountered during monitoring well installation other than what is part of the intended investigation, installation or drilling, work will be stopped and emergency contacts listed in Attachment D of this HASP will be immediately notified.

3.5.2 Groundwater Sample Collection

Chemical exposure may occur as groundwater samples are collected. Activities will be conducted in Level D.

If evidence of unanticipated contamination is encountered during groundwater sampling other than what is part of the intended investigation, installation or drilling, work will be stopped and emergency contacts listed in Attachment D of this HASP will be immediately notified.

4.0 PERSONAL PROTECTIVE EQUIPMENT (PPE)

4.1 Levels of Protection

PPE must protect workers from the specific hazards they are likely to encounter on site. Selection of the appropriate PPE must take into consideration: (1) identification of the hazards or suspected hazards; (2) potential exposure routes; and (3) the performance of the PPE construction (materials and seams) in providing a barrier to these hazards. Based on anticipated site conditions and the proposed work activities to be performed at the Site, Level D Protection will be used. The upgrading/downgrading of these levels of protection will be based on continuous air monitoring results as described in Section 5.0. The decision to modify standard PPE will be made by the HSO after conferring with the Langan Project Manager. The levels of protection are described below.

- **Level D Protection**

  a. Safety glasses with sideshields or chemical splash goggles
  b. Safety boots/shoes (toe-protected)
  c. Hard hat
  d. Long sleeve work shirt and work pants
  e. Nitrile gloves
  f. Hearing protection (as needed)
  g. Reflective traffic vest

- **Level D Protection (Modified)**

  a. Safety glasses with sideshields or chemical splash goggles
  b. Safety boots/shoes (toe-protected)
  c. Disposable chemical-resistant boot covers
  d. Coveralls (polycoated Tyvek or equivalent to be worn when contact with wet contaminated soil, groundwater, or non-aqueous phase liquids is anticipated)
  e. Hard hat
  f. Long sleeve work shirt and work pants
  g. Nitrile gloves
  h. Hearing protection (as needed)
  i. Reflective traffic vest

- **Level C Protection**

    a. Full face-piece, air-purifying, cartridge*-equipped, NIOSH-approved respirator [*combo cartridge P100/OV/CL/HC/SD/CD/HS (escape)]
    b. Inner (latex) and outer (nitrile) chemical-resistant glove
    c. Chemical-resistant safety boots/shoes (toe-protected)
    d. Disposable chemical-resistant boot covers
    e. Hard hat
    f. Long sleeve work shirt and work pants
    g. Coveralls (Tyvek or equivalent, poly-coated Tyvek will be worn when contact, or anticipated contact with wet contaminated soils, ground water, and/or non-aqueous phase liquids (NAPL) is anticipated)
    h. Hearing protection (as needed)
    i. Reflective traffic vest

The action levels used in determining the necessary levels of respiratory protection and upgrading to Level C are provided in Table 4. The written Respiratory Protection Program is maintained by Langan's H&S Department. The monitoring procedures and equipment are outlined in Section 5.0.

4.2 Respirator Fit-Test

All Langan employees and subcontractors performing site work who could be exposed to hazardous substances at the work site are in possession of a full face-piece, air-purifying respirator and have been successfully quantitative fit-tested within the past year. Quantitative fit-test records are maintained by Langan's H&S Department.

4.3 Respirator Cartridge Change-Out Schedule

Respiratory protection is required to be worn when certain action levels (Table 2) are reached. A respirator cartridge change-out schedule has been developed in order to comply with 29 CFR 1910.134. The respirator cartridge change-out schedule for this project is as follows:

- Cartridges shall be removed and disposed of at the end of each shift, when cartridges become wet or wearer experiences breakthrough, whichever occurs first.
- If the humidity exceeds 85%, then cartridges shall be removed and disposed of after 4 hours of use.

Respirators shall not be stored at the end of the shift with contaminated cartridges left on. Cartridges shall not be worn on the second day, no matter how short the time period was the previous day they were used.

5.0 AIR QUALITY MONITORING AND ACTIONS LEVELS

5.1 Monitoring During Site Operations

Atmospheric air monitoring results are used to provide data to determine when exclusion zones need to be established and when certain levels of personal protective equipment are required. For all instruments there are Site-specific action level criteria which are used in making field health and safety determinations. Other data, such as the visible presence of contamination or the steady state nature of air contaminant concentration, are also used in making field health and safety decisions. Therefore, the HSO may establish an exclusion zone or require a person to wear a respirator even though atmospheric air contaminant concentrations are below established HASP action levels.

During site work involving disturbance of soil/fill at the Site, real time air monitoring will be conducted for volatile organic compounds (VOCs). A photoionization detector (PID) and/or flame ionization detector (FID) will be used to monitor concentrations of VOCs at personnel breathing-zone height. Dust monitoring will be accomplished with an aerosol monitor. Air monitoring will be the responsibility of the HSO or designee. Air monitoring will be conducted approximately every 30 minutes during ground intrusive activities in the AOC on the project site. All manufacturers' instructions for instrumentation and calibration will be available onsite.

Subcontractors' air monitoring plans must be equal to or more stringent as the Langan plan.

An air monitoring calibration log is provided in Attachment D of this HASP.

5.1.1 Volatile Organic Compounds

Monitoring with a PID, such as a MiniRAE 2000 (10.6v) or equivalent will occur during intrusive work. Colormetric Indicator Tubes for benzene may be used as backup for the PID, if measurements remain above background monitor every 2 hours. The HSO will monitor the employee breathing zone at least every 30 minutes, or whenever there is any indication that concentrations may have changed (odors, visible gases, etc.) since the last

measurement. If VOC levels are observed above 5 ppm for longer than 5 minutes or if the site PPE is upgraded to Level C, the HSO will begin monitoring the site perimeter at a location downwind of the workzone every 30 minutes in addition to the employee breathing zone. Instrument action levels for monitored gases are provided in Table 4.

5.1.2 Dust

During invasive procedures which have the potential for creating airborne dust, such as excavation of dry soils, a real time airborne dust monitor such as a Thermo Personal DataRam (pDR) or a TSI DustTrak should be used to monitor for air particulates. The HSO will monitor the employee breathing zone at least every 30 minutes, or whenever there is any indication that concentrations may have changed (appearance of visible dust) since the last measurement. If dust levels are observed to be greater than 0.100 mg/m^3 or visible dust is observed for longer than 15 minutes or if the site PPE is upgraded to Level C, the HSO will begin monitoring the site perimeter at a location downwind of the AOC every 30 minutes in addition to the employee breathing zone. Instrument action levels for dust monitoring are provided in Table 4.

5.2 Monitoring Equipment Calibration and Maintenance

Instrument calibration shall be documented and included in a dedicated safety and health logbook or on separate calibration pages of the field book. All instruments shall be calibrated before and after each shift. Calibration checks may be used during the day to confirm instrument accuracy. Duplicate readings may be taken to confirm individual instrument response.

All instruments shall be operated in accordance with the manufacturers' specifications. Manufacturers' literature, including an operations manual for each piece of monitoring equipment will be maintained on site by the HSO for reference.

5.3 Determination of Background Levels

Background (BKD) levels for VOCs and dust will be established prior to intrusive activities within the AOC at an upwind location. A notation of BKD levels will be referenced in the daily monitoring log. BKD levels are a function of prevailing conditions. BKD levels will be taken in an appropriate upwind location as determined by the HSO.

Table 4 lists the instrument action levels.

6.0 COMMUNITY HEALTH AND SAFETY CONSIDERATIONS

Community air monitoring will be conducted during intrusive activity in compliance with the NYSDOH Generic Community Air Monitoring Program (CAMP) outlined below.

Langan will conduct monitoring for dust and VOCs during ground-intrusive work. Upwind concentrations of VOCs and dust will be monitored continuously each day to establish background concentrations. Langan will monitor VOCs and dust at the downwind perimeter of the work zone, which will be established at a point on the Site where the general public or site employees may be present. Monitoring for VOCs will be conducted with a PID equipped with a 10.6 eV bulb. Dust emissions will be monitored using real-time monitoring equipment capable of measuring PM-10 (e.g., DustTrak).

Sustained concentrations of VOCs or PM10 will be reported to the NYSDEC and NYSDOH Project Managers and included in the daily report. In addition, a map showing the location of the downwind and upwind CAMP stations will be included in the daily report.

7.0 WORK ZONES AND DECONTAMINATION

7.1 Site Control

Work zones are intended to control the potential spread of contamination throughout the site and to assure that only authorized individuals are permitted into potentially hazardous areas.

Any person working in an area where the potential for exposure to site contaminants exists will only be allowed access after providing the HSO with proper training and medical documentation.

Exclusion Zone (EZ) - All activities which may involve exposure to site contaminants, hazardous materials and/or conditions should be considered an EZ. Decontamination of field equipment will also be conducted in the Contaminant Reduction Zone (CRZ) which will be located on the perimeter of the EZ. The EZ and the CRZ will be clearly delineated by cones, tapes or other means. The HSO may establish more than one EZ where different levels of protection may be employed or different hazards exist. The size of the EZ shall be determined by the HSO allowing adequate space for the activity to be completed, field members and emergency equipment. For purposes of this HASP the exclusion zones are defined by the extent of the proposed excavations or a 10-foot buffer around each monitoring well location but may be expanded based on the results of air monitoring or any other field conditions identified by the HSO. All personnel

working in the EZ must have 40 hours HAZWOPER training and be enrolled in a medical monitoring program prior to conducting any site activities.

7.2 Contamination Control

7.2.1 Personnel Decontamination Station

Personal hygiene, coupled with diligent decontamination, will significantly reduce the potential for exposure.

7.2.2 Minimization of Contact with Contaminants

During completion of all site activities, personnel should attempt to minimize the chance of contact with contaminated materials. This involves a conscientious effort to keep "clean" during site activities. All personnel should minimize kneeling, splash generation, and other physical contact with contamination as PPE is intended to minimize accidental contact. This may ultimately minimize the degree of decontamination required and the generation of waste materials from site operations.

Field procedures will be developed to control over spray and runoff and to ensure that unprotected personnel working nearby are not affected.

7.2.3 Personnel Decontamination Sequence

Decontamination will be performed by removing all PPE used in EZ and placing it in drums/trash cans at the CRZ. Baby wipes shall be available for wiping hands and face. Drums/trash cans will be labeled by the field crews in accordance with all local, state, and federal requirements. Management plans for contaminated PPE, tools and Investigative Derived Waste (i.e., soil cutting) are provided below.

7.2.4 Emergency Decontamination

If circumstances dictate that contaminated clothing cannot be readily removed, then remove gross contamination and wrap injured personnel with clean garments/blankets to avoid contaminating other personnel or transporting equipment. If the injured person can be moved, he/she will be decontaminated by site personnel as described above before emergency responders handle the victim. If the person cannot be moved because of the extent of the injury (a back or neck injury), provisions shall be made to ensure that emergency response personnel will be able to respond to the

victim without being exposed to potentially hazardous atmospheric conditions. If the potential for inhalation hazards exist, such as with open excavation, this area will be covered with polyethylene sheeting to eliminate any potential inhalation hazards. All emergency personnel are to be immediately informed of the injured person's condition, potential contaminants, and provided with all pertinent data.

7.2.5 Hand-Held Equipment Decontamination

Hand-held equipment includes all monitoring instruments as stated earlier, samples, hand tools, and notebooks. The hand-held equipment is dropped at the first decontamination station to be decontaminated by one of the decontamination team members. These items must be decontaminated or discarded as waste prior to removal from the CRZ.

To aid in decontamination, monitoring instruments can be sealed in plastic bags or wrapped in polyethylene. This will also protect the instruments against contaminants. The instruments will be wiped clean using wipes or paper towels if contamination is visually evident. Sampling equipment, hand tools, etc. will be cleaned with non-phosphorous soap to remove any potentially contaminated soil, and rinsed with deionized water. All decontamination fluids will be containerized and stored on-site pending waste characterization sampling and appropriate off-site disposal.

7.2.6 Heavy Equipment Decontamination

All heavy equipment and vehicles arriving at the work site will be free from contamination from offsite sources. Any vehicles arriving to work that are suspected of being impacted will not be permitted on the work site. Potentially contaminated heavy equipment will not be permitted to leave the EZ unless it has been thoroughly decontaminated and visually inspected by the HSO or his designee.

7.3 Communications

The following communications equipment will be utilized as appropriate.

- Telephones - A cellular telephone will be located with the HSO for communication with the HSM and emergency support services/facilities.
- Hand Signals - Hand signals shall be used by field teams, along with the buddy system. The entire field team shall know them before operations commence

and their use covered during site-specific training. Typical hand signals are the following:

Signal	Meaning
Hand gripping throat	Out of air, can't breathe
Grip on partner's wrist or placement of both hands around partner's waist	Leave area immediately, no debate
Hands on top of head	Need assistance
Thumbs up	Okay, I'm all right, I understand
Thumbs down	No, negative

8.0 MEDICAL SURVEILLANCE

All personnel who will be performing field work involving potential exposure to toxic and hazardous substances will be required to have passed an initial baseline medical examination, with annual follow-up medical exams thereafter, consistent with 29 CFR 1910.120(f). Medical evaluations will be performed by, or under the direction of, a physician board-certified in occupational medicine. Results of medical evaluations are maintained by Langan's H&S Department.

9.0 EMERGENCY RESPONSE PLAN

This section establishes procedures and provides information for use during a project emergency. Emergencies happen unexpectedly and quickly, and require an immediate response; therefore, contingency planning and advanced training of staff is essential. Specific elements of emergency support procedures that are addressed in the following subsections include communications, local emergency support units, preparation for medical emergencies, first aid for injuries incurred on site, record keeping, and emergency site evacuation procedures. In case of emergency, in addition to 911 the Langan Incident/Injury Hotline (973-560-4699) should be called as soon as possible.

9.1 Responsibilities

9.1.1 Health and Safety Officer (HSO)

The HSO is responsible for ensuring that all personnel are evacuated safely and that machinery and processes are shut down or stabilized in the event of a stop work order or evacuation. The HSO is responsible for ensuring the HSM are notified of all incidents, all injuries, near misses, fires, spills,

releases or equipment damage. The HSO is required to immediately notify the HSM of any fatalities or catastrophes (three or more workers injured and hospitalized) so that the HSM can notify OSHA within the required time frame.

9.1.2 Emergency Coordinator

The HSO or their designated alternate will serve as the Emergency Coordinator. The Emergency Coordinator is responsible for ensuring that all personnel are evacuated safely and that machinery and processes are shut down or stabilized in the event of a stop work order or evacuation. They are also responsible for ensuring the HSM are notified of all incidents, all injuries, near misses, fires, spills, releases or equipment damage. The Emergency Coordinator is required to immediately notify the HSM of any fatalities or catastrophes (three or more workers injured and hospitalized.

The Emergency Coordinator shall locate emergency phone numbers and identify hospital routes prior *to beginning* work on the sites. The Emergency Coordinator shall make necessary arrangements to be prepared for any emergencies that could occur.

The Emergency Coordinator is responsible for implementing the Emergency Response Plan.

9.1.3 Site Personnel

Project site personnel are responsible for knowing the Emergency Response Plan and the procedures contained herein. Personnel are expected to notify the Emergency Coordinator of situations that could constitute a site emergency. Project site personnel, including all subcontractors will be trained in the Emergency Response Plan.

9.2 Communications

Once an emergency situation has been stabilized or as soon as practically possible, the HSO will contact the Langan Incident/Injury Hotline (973-560-4699) and Project Manager of identify any emergency situation.

9.3 Local Emergency Support Units

In order to be able to deal with any emergency that might occur during investigative activities at the site, Attachment E will be available in the field vehicles and provided to all personnel conducting work within the EZ.

Figure 2 shows the hospital route map. Outside emergency number 911 and local ambulance should be relied on for response to medical emergencies and transport to emergency rooms. Due to traffic congestion that is prevalent in the New York metropolitan area, alternate hospital routes will need to be considered. The Emergency Coordinator will determine the appropriate route based on time of day and traffic patterns. Changes in the referenced primary facilities shall be documented with the HASP Field Change Authorization Request Form (Attachment B).

The Emergency Phone Numbers listed are preliminary. Upon mobilization, the HSO shall verify all numbers and document the changes in the Site Logbook. Any changes shall also be documented with the HASP Field Change Authorization Request Form.

Hospital route maps will be provided to all field personnel.

9.4 Pre-Emergency Planning

Langan will communicate directly with administrative personnel from the emergency room at the hospital in order to determine whether the hospital has the facilities and personnel needed to treat cases of trauma resulting from any of the contaminants expected to be found on the site. Instructions for finding the hospital will be posted conspicuously in the site office and in each site vehicle.

9.5 Emergency Medical Treatment

The procedures and rules in this HASP are designed to prevent employee injury. However, should an injury occur, no matter how slight, it will be reported to the HSO on site immediately. First-aid equipment will be available on site at the following locations:

First Aid Kit:	Vehicles
Emergency Eye Wash:	Vehicles

During the site safety briefing, project personnel will be informed of the location of the first aid station(s) that has been set up. Unless they are in immediate danger, severely injured persons will not be moved until paramedics can attend to them. Some injuries, such as severe cuts and lacerations or burns, may require immediate treatment. Any first aid instructions that can be obtained from doctors or paramedics, before an emergency-response squad arrives at the site or before the injured person can be transported to the hospital, will be followed closely.

Personnel with current first aid and CPR certification will be identified.

Only in non-emergency situations will an injured person be transported to the hospital by means other than an ambulance.

Nearest hospital: **Brookdale University Hospital**
1 Brookdale Plaza
Brooklyn, NY 11212
(718) 240-5363
(directions from site to hospital found on Figure 2)

9.6 Non-Emergency Medical Treatment

In case of injury to personnel, which is not a medical emergency the employee will contact WorkCare at (1-888-449-7787). WorkCare provides access 24 hours / 7 days a week to experienced occupational health nurses and physicians who confer with employees at the onset of a work-related injury or illness. WorkCare will provide over the phone injury treatment or direct employees to medical treatment by third party provider, if appropriate.

9.7 Emergency Site Evacuation Routes and Procedures

All project personnel will be instructed on proper emergency response procedures and locations of emergency telephone numbers during the initial site safety meeting. If an emergency occurs, including but not limited to fire, explosion or significant release of toxic gas into the atmosphere, the Langan Project Manager will be verbally notified immediately. All heavy equipment will be shut down and all personnel will evacuate the work areas and assemble at the nearest intersection to be accounted for and to receive further instructions.

9.8 Fire Prevention and Protection

In the event of a fire or explosion, procedures will include immediately evacuating the site and notification of the Langan Project Manager of the investigation activities. Portable fire extinguishers will be provided at the work zone. The extinguishers located in the various locations should also be identified prior to the start of work. No personnel will fight a fire beyond the stage where it can be put out with a portable extinguisher (incipient stage).

9.8.1 Fire Prevention

Fires will be prevented by adhering to the following precautions:

- Good housekeeping and storage of materials.
- Storage of flammable liquids and gases away from oxidizers.
- Shutting off engines to refuel.
- Grounding and bonding metal containers during transfer of flammable liquids.
- Use of UL approved flammable storage cans.
- Fire extinguishers rated at least 10 pounds ABC located on all heavy equipment, in all trailers and near all hot work activities.

The person responsible for the control of fuel source hazards and the maintenance of fire prevention and/or control equipment is the HSO.

9.9 Significant Vapor Release

Based on the proposed tasks, the potential for a significant vapor release is low. However, if a release occurs, the following steps will be taken:

- Move all personnel to an upwind location. All non-essential personnel shall evacuate.
- Upgrade to Level C Respiratory Protection.
- Downwind perimeter locations shall be monitored for volatile organics.
- If the release poses a potential threat to human health or the environment in the community, the Emergency Coordinator shall notify the Langan Project Manager.
- Local emergency response coordinators will be notified.

9.10 Overt Chemical Exposure

The following are standard procedures to treat chemical exposures. Other, specific procedures detailed on the Safety Data Sheet (SDS) will be followed, when necessary.

SKIN AND EYE: Use copious amounts of soap and water from eye-wash kits and portable hand wash stations.

CONTACT: Wash/rinse affected areas thoroughly, then provide appropriate medical attention. Skin shall also be rinsed for 15 minutes if contact with caustics, acids or hydrogen peroxide occurs. Affected items of clothing shall also be removed from contact with skin.

Providing wash water and soap will be the responsibility of each individual contractor or subcontractor on-site.

9.11 Decontamination During Medical Emergencies

If emergency life-saving first aid and/or medical treatment is required, normal decontamination procedures may need to be abbreviated or omitted. The HSO or designee will accompany contaminated victims to the medical facility to advise on matters involving decontamination when necessary. The outer garments can be removed if they do not cause delays, interfere with treatment or aggravate the problem. Respiratory equipment must always be removed. Protective clothing can be cut away. If the outer contaminated garments cannot be safely removed on site, a plastic barrier placed between the injured individual and clean surfaces should be used to help prevent contamination of the inside of ambulances and/or medical personnel. Outer garments may then be removed at the medical facility. No attempt will be made to wash or rinse the victim if his/her injuries are life threatening, unless it is known that the individual has been contaminated with an extremely toxic or corrosive material which could also cause severe injury or loss of life to emergency response personnel. For minor medical problems or injuries, the normal decontamination procedures will be followed.

9.12 Incident Reporting

Once first aid and/or emergency response needs have been met, the following parties are to be contacted:

- WorkCare (1-888-449-7787)
- Langan Incident/Injury Report Hotline (973-560-4699)
- Langan Project Manager, Amanda Forsburg (973-560-4900)
- Langan Health and Safety Manager, Tony Moffa (215-491-6500)
- The employer of any injured worker who is not a Langan employee

For emergencies involving personal injury and/or exposure including near-misses, the HSO or designee will complete and submit an Incident Report form (Attachment F) within 24 hours. If the employee involved is not a Langan employee, his employer shall receive a copy of the report.

9.13 Adverse Weather Conditions

In the event of adverse weather conditions, the HSO will determine if work will continue without potentially risking the safety of all field workers. Some of the items to be considered prior to determining if work should continue are:

- Potential for heat stress and heat-related injuries.
- Potential for cold stress and cold-related injuries.
- Treacherous weather-related working conditions (hail, rain, snow, ice, high winds).
- Limited visibility (fog).
- Potential for electrical storms.
- Earthquakes.
- Other major incidents.

Site activities will be limited to daylight hours, or when suitable artificial light is provided, and acceptable weather conditions prevail. The HSO will determine the need to cease field operations or observe daily weather reports and evacuate, if necessary, in case of severe inclement weather conditions.

9.14 Spill Control and Response

All small spills/environmental releases shall be contained as close to the source as possible. Whenever possible, the SDS will be consulted to assist in determining proper waste characterization and the best means of containment and cleanup. For small spills, sorbent materials such as sand, sawdust or commercial sorbents should be placed directly on the substance to contain the spill and aid recovery. Any acid spills should be diluted or neutralized carefully prior to attempting recovery. Berms of earthen or sorbent materials can be used to contain the leading edge of the spills. All spill containment materials will be properly disposed. An exclusion zone of 50 to 100 feet around the spill area should be established depending on the size of the spill.

All contractor vehicles shall have spill kits on them with enough material to contain and absorb the worst-case spill from that vehicle. All vehicles and equipment shall be inspected prior to be admitted on site. Any vehicle or piece of equipment that develops a leak will be taken out of service and removed from the job site.

The following seven steps shall be taken by the Emergency Coordinator:

1. Determine the nature, identity and amounts of major spills.
2. Make sure all unnecessary persons are removed from the spill area.
3. Notify the HSO immediately.
4. Use proper PPE in consultation with the HSO.
5. If a flammable liquid, gas or vapor is involved, remove all ignition sources and use non-sparking and/or explosion-proof equipment to contain or clean up the spill (diesel-only vehicles, air-operated pumps, etc.)
6. If possible, try to stop the leak with appropriate material.
7. Remove all surrounding materials that can react or compound with the spill.

In addition to the spill control and response procedures described in this HASP, Langan personnel will coordinate with the designated project manager relative to spill response and control actions. Notification to the Project Manager must be immediate and, to the extent possible, include the following information:

- Time and location of the spill.
- Type and nature of the material spilled.
- Amount spilled.

- Whether the spill has affected or has a potential to affect a waterway or sewer.
- A brief description of affected areas/equipment.
- Whether the spill has been contained.
- Expected time of cleanup completion. If spill cleanup cannot be handled by Langan's on-site personnel alone, such fact must be conveyed to the Project Manager immediately.

Langan shall not make any notification of spills to outside agencies. The client will notify regulatory agencies as per their reporting procedures.

9.15 Emergency Equipment

The following minimum emergency equipment shall be kept and maintained on site:

- Industrial first aid kit.
- Fire extinguishers (one per site).

9.16 Restoration and Salvage

After an emergency, prompt restoration of utilities, fire protection equipment, medical supplies and other equipment will reduce the possibility of further losses. Some of the items that may need to be addressed are:

- Refilling fire extinguishers.
- Refilling medical supplies.
- Recharging eyewashes and/or showers.
- Replenishing spill control supplies.

10.0 TRAINING

10.1 General Health and Safety Training

Completion of an initial 40-hour Hazardous Waste Operations and Emergency Response (HAZWOPER) training program (or its equivalent) as detailed in OSHA's 29 CFR 1910.120(e) is required for all employees who will perform work in areas where the potential for a toxic exposure exists. Annual 8-hour refresher training is also required to maintain competencies to ensure a safe work environment.

10.2 Site-Specific Training

Prior to commencement of site activities, all field personnel assigned to the project will have completed training that will specifically address the activities, procedures, monitoring, and equipment used in the site operations. It will include a documented verbal review of the entire HASP and all the provisions within the HASP document. Should any new employees arrive on-site, they will also be given a documented full HASP review – or one that address the appropriate tasks that remain at the time of the new employee's arrival.

10.3 Onsite Safety Briefings

Project personnel and visitors will participate in documented daily on-site health and safety briefings ("Tailgate Talks") led by the HSO to assist site personnel in safely conducting their work activities. The briefings will include information on operations to be conducted that shift, changes in work practices or changes in the site's environmental conditions, as well as periodic reinforcement of previously discussed topics. The briefings will also provide a forum to facilitate conformance with safety requirements and to identify performance deficiencies related to safety during daily activities or as a result of safety inspections. The meetings will also be an opportunity for the work crews to be updated on monitoring results. Prior to starting any new activity, a training session will be held for crew members involved in the activity. The Safety Briefing form (Attachment A) can be used to facilitate this effort.

10.4 Hazard Communication

All material brought on-site will be in the appropriate containers and will be properly labeled. The SDS for unleaded gasoline, diesel fuel, and hydraulic fluid are attached, in addition to SDS for contaminants documented to be present at the Site. Langan's written Hazard Communication program, in compliance with 29 CFR 1910.1200, is maintained by Langan's H&S Department.

11.0 RECORDKEEPING

The following is a summary of required health and safety logs, reports and recordkeeping.

11.1 Field Change Authorization Request

A field change authorization request is to be completed for requesting a change to this HASP (Attachment B). Any changes to the work to be performed that is not included in the HASP will require an Addendum that is approved by the Langan

Project Manager and Langan HSM to be prepared. Approved changes will be reviewed with all field personnel at a safety briefing.

11.2 Medical and Training Records

Copies or verification of training (40-hour, 8-hour, supervisor, site-specific training, documentation of three-day OJT, and respirator fit-test records) and medical clearance for Site work and respirator use will be maintained in the office and available upon request. Records for all subcontractor employees must also be available upon request. All employee medical records will be maintained by Langan's H&S Department.

11.3 Onsite Log

A log of personnel on site each day will be kept by the HSO or designee.

11.4 Daily Safety Meetings ("Tailgate Talks")

Completed Safety Briefing forms will be maintained by the HSO.

11.5 Exposure Records

All personal monitoring results, laboratory reports, calculations and air sampling data sheets are part of an employee exposure record. These records will be maintained by the HSO during site work. At the end of the project they will be maintained according to 29 CFR 1910.1020.

11.6 Hazard Communication Program/SDS

Safety Data Sheets (SDS) have been obtained for applicable substances and are included in this HASP (Attachment G). Langan's written Hazard Communication program, in compliance with 29 CFR 1910.1200, is maintained by Langan's H&S Department.

11.7 Documentation

Employees are required to contact WorkCare at (1-888-449-7787) to document incidents/injuries which are not medical emergencies. Immediately following an incident or near miss, unless emergency medical treatment is required, either the employee or a coworker must contact the Langan Incident/Injury Hotline at (973-560-4699) and the client representative to report the incident or near miss. A written report must be completed and submitted to the client representative

within 24 hours of the incident. For emergencies involving personnel injury and/or exposure, employee will complete and submit the Langan Incident/Injury Report to the Langan Corporate Health and Safety Manager as soon as possible following the incident. Accidents will be investigated in-depth to identify all causes and to recommend hazard control measures.

12.0 FIELD PERSONNEL REVIEW

This form serves as documentation that field personnel have been verbally given a full HASP review by Langan personnel, and understand the provisions of this EHS Plan. It is maintained on site by the HSO as a project record.

Each field team member shall sign this section after Site-specific training is completed and before being permitted to work onsite.

Name (Print and Sign)	***Company***	***Date***

TABLES

TABLE 1
CONTAMINANTS OF CONCERN
12074 FLATLANDS AVENUE
BROOKLYN, NEW YORK

Contaminant of Concern	Affected Media
VOLATILES	
1,2,4-Trimethylbenzene	Soil
1,2-Dichlorobenzene	Soil
Acetone	Soil
Benzene	Soil
n-Propylbenzene	Soil
Toluene	Soil
Total Xylenes	Soil
Naphthalene	Groundwater
Tetrachloroethylene	Soil Vapor
1,2-cis-Dichloroethylene	Soil Vapor
Vinyl Chloride	Soil Vapor
SEMI-VOLATILES	
3 & 4 Methylphenol (m&p Cresol)	Soil
1,4-Dioxane	Groundwater
Acenaphthene	Soil
Benzo(a)anthracene	Soil
Benzo(a)pyrene	Soil
Benzo(b)fluoroanthene	Soil
Benzo(k)fluoroanthene	Soil
Chrysene	Soil
Dibenzo(a,h)anthracene	Soil
Fluorene	Soil
Indeno(1,2,3-cd)pyrene	Soil
Naphthalene	Soil
Phenanthrene	Soil
Pyrene	Soil
PESTICIDES	
4,4'-DDD	Soil
4,4'-DDE	Soil
4,4'-DDT	Soil
Dieldrin	Soil
PCBs	
Total PCBs	Soil
METALS	
Barium	Soil / Groundwater
Hexavalent Chromium	Soil
Copper	Soil
Lead	Soil

TABLE 1
CONTAMINANTS OF CONCERN
12074 FLATLANDS AVENUE
BROOKLYN, NEW YORK

METALS	
Mercury	Soil
Nickel	Soil
Selenium Silver	Groundwater
Zinc	Soil
Per- and Polyfluoroalkyl Substances (PFAS)	
Perfluorooctanesulfonic Acid (PFOS)	Soil / Groundwater
Perfluorooctanoic Acid (PFOA)	Soil / Groundwater

\\Langan.com\data\PAR\data8\100688801\Project Data_Discipline\Environmental\Reports_Block 4434 Lot 1 (Phase 1B)\2025-07 - SMP\Appendix G - HASP\Tables\HASP TABLE 1 - Contaminants of Concern.doc

TABLE 2
SELECTED POTENTIAL CHEMICAL EXPOSURE LIMITS AND HEALTH EFFECTS
12074 FLATLANDS AVENUE
BROOKLYN, NEW YORK

Chemical	Permissible Exposure Limit	IDLH Limit	Exposure Routes	Exposure Symptoms
1,2,4-Trimethylbenzene	---	---	Inhalation, ingestion, skin and/or eye contact	Irritation eyes, skin, nose, throat, respiratory system; bronchitis; hypochromic anemia; headache, drowsiness, lassitude (weakness, exhaustion), dizziness, nausea, incoordination; vomiting, confusion; chemical pneumonitis (aspiration liquid)
1,2-Dichlorobenzene	50 ppm	200 ppm	Inhalation, skin absorption, ingestion, skin and/or eye contact	Irritation eyes, nose; liver, kidney damage; skin blisters
n-Propylbenzene	---	---	Inhalation, ingestion, skin and/or eye contact	Irritation eyes, skin, nose, throat, respiratory system; headache, drowsiness, lassitude (weakness, exhaustion), dizziness, nausea, incoordination; vomiting
Acetone	1,000 ppm	2,500 ppm	Inhalation, ingestion, skin and/or eye contact	Irritation eyes, nose, throat; headache, dizziness, central nervous system depression; dermatitis
Benzene	1 ppm	50 ppm	Inhalation, Skin Absorption, Ingestion, skin and/or eye contact	Irritate eyes, skin, nose; respiratory system; giddiness; head, nausea, staggered gait; fatigue, anorexia, lassitude; dermatitis; bone marrow depression; [carcinogenic]

TABLE 2
SELECTED POTENTIAL CHEMICAL EXPOSURE LIMITS AND HEALTH EFFECTS
12074 FLATLANDS AVENUE
BROOKLYN, NEW YORK

Chemical	Permissible Exposure Limit	IDLH Limit	Exposure Routes	Exposure Symptoms
Naphthalene	10 ppm	250 ppm	Inhalation, skin absorption, ingestion, skin and/or eye contact	Irritation eyes; headache, confusion, excitement, malaise (vague feeling of discomfort); nausea, vomiting, abdominal pain; irritation bladder; profuse sweating; jaundice; hematuria (blood in the urine), renal shutdown; dermatitis, optical neuritis, corneal damage
Toluene	200 ppm	500 ppm	Inhalation, Skin Absorption, Ingestion, skin and/or eye contact	Irritate eyes, nose; fatigue, weakness, confusion, euphoria, dizziness, headache; dilated pupils, lacrimation; nervousness, muscle fatigue, insomnia; paresthesia; dermatitis; liver, kidney damage; mucous membrane; narcosis, coma
Xylenes	100 ppm	900 ppm	Inhalation, Skin Absorption, Ingestion, skin and/or eye contact	Irritate eyes, skin, nose, throat; dizziness, excitement, drowsiness, incoordination, staggering gait; corn vacuolization; anorexia, nausea, vomit, abdominal pain; dermatitis
2-Methylphenol	5 ppm	250 ppm	Inhalation, ingestion, skin and/or eye contact	Irritation eyes, skin, mucous membrane; central nervous system effects: confusion, depression, respiratory failure; dyspnea (breathing difficulty), irregular rapid respiratory, weak pulse; eye, skin burns; dermatitis; lung, liver, kidney, pancreas damage

TABLE 2
SELECTED POTENTIAL CHEMICAL EXPOSURE LIMITS AND HEALTH EFFECTS
12074 FLATLANDS AVENUE
BROOKLYN, NEW YORK

Chemical	Permissible Exposure Limit	IDLH Limit	Exposure Routes	Exposure Symptoms
3 & 4 Methylphenol (m&p-Cresol)	5 ppm	250 ppm	Inhalation, ingestion, skin and/or eye contact	Irritation eyes, skin, mucous membrane; central nervous system effects: confusion, depression, respiratory failure; dyspnea (breathing difficulty), irregular rapid respiratory, weak pulse; eye, skin burns; dermatitis; lung, liver, kidney, pancreas damage
Acenaphthene	0.2 mg/m^3	80 mg/m^3	Inhalation, skin absorption, ingestion	Irritate eyes, skin, mucous membrane, upper respiratory system; vomiting; kidney and liver damage
Benzo(a)anthracene	0.2 mg/m^3	80 mg/m^3	Inhalation, Skin Absorption, Ingestion	Irritate eyes, skin, upper respiratory system, cough
Benzo(a)pyrene	0.2 mg/m^3	80 mg/m^3	Inhalation, skin and/or eye contact	Dermatitis, bronchitis, [potential occupational carcinogen]
Benzo(b)fluoranthene	0.2 mg/m^3	80 mg/m^3	Inhalation, Skin Absorption, Ingestion	Irritate eyes, skin, upper respiratory system, cough
Benzo(k)fluoranthene	0.2 mg/m^3	80 mg/m^3	Inhalation, Skin Absorption, Ingestion	Irritate eyes, skin, upper respiratory system, cough
Chrysene	0.2 mg/m^3	80 mg/m^3	Inhalation, Skin Absorption, Ingestion	Irritate eyes, skin, upper respiratory system, cough
Dibenzo(a,h)anthracene	0.2 mg/m^3	80 mg/m^3	Inhalation, Skin Absorption, Ingestion	Irritate eyes, skin, upper respiratory system, cough
Indeno (1,2,3-cd) pyrene	0.2 mg/m^3	80 mg/m^3	Inhalation, Skin Absorption, Ingestion	Irritate eyes, skin, upper respiratory system, cough
Fluorene	- - -	- - -	Inhalation	Irritate eyes and skin
Phenanthrene	0.2 mg/m^3	80 mg/m^3	Inhalation, skin and/or eye contact	Dermatitis, bronchitis, [potential occupational carcinogen]
Pyrene	0.2 mg/m^3	80 mg/m^3	Inhalation, skin and/or eye contact	Dermatitis, bronchitis, [potential occupational carcinogen]

TABLE 2
SELECTED POTENTIAL CHEMICAL EXPOSURE LIMITS AND HEALTH EFFECTS
12074 FLATLANDS AVENUE
BROOKLYN, NEW YORK

Chemical	Permissible Exposure Limit	IDLH Limit	Exposure Routes	Exposure Symptoms
Pesticides	1 mg/mg^3	500 mg/m^3	Inhalation, skin absorption, ingestion, skin and/or eye contact	Irritation eyes, skin; paresthesia tongue, lips, face; tremor; anxiety, dizziness, confusion, malaise (vague feeling of discomfort), headache, lassitude (weakness, exhaustion); convulsions; paresis hands; vomiting; [potential occupational carcinogen]
Polychlorinated Biphenyls (PCBs)	0.5 mg/m^3	5 mg/m^3	Inhalation, skin absorption, ingestion, skin and/or eye contact	Irritation eyes, chloracne; liver damage; reproductive effects; [potential occupational carcinogen]
Arsenic	0.010 mg/m^3	5 mg/m^3	Inhalation, Ingestion, Skin Absorption, Skin and/or Eye Contact	Ulceration of nasal septum, dermatitis, gastrointestinal disturbances, peripheral neuropathy, resp irritation, hyperpigmentation of skin, [potential occupational carcinogen]
Barium (as barium chloride)	0.5 mg/m^3	50 mg/m^3	Inhalation, ingestion, skin and/or eye contact	Irritation eyes, skin, upper respiratory system; skin burns; gastroenteritis; muscle spasm; slow pulse, extrasystoles; hypokalemia
Cadmium	0.005 mg/ m^3	9 mg/m^3	Inhalation	Pulmonary edema, dyspnea (breathing difficulty), cough, chest tightness, substernal (occurring beneath the sternum) pain; headache; chills, muscle aches; nausea, vomiting, diarrhea; emphysema, proteinuria, anosmia (loss of the sense of smell), mild anemia; [potential occupational carcinogen]

TABLE 2
SELECTED POTENTIAL CHEMICAL EXPOSURE LIMITS AND HEALTH EFFECTS
12074 FLATLANDS AVENUE
BROOKLYN, NEW YORK

Chemical	Permissible Exposure Limit	IDLH Limit	Exposure Routes	Exposure Symptoms
Chromium	1 mg/m^3	250 mg/m^3	Inhalation, ingestion, skin and/or eye contact	Irritation eyes, skin; lung fibrosis (histologic)
Hexavalent Chromium	5 mg/m^3	250 mg/m^3	Inhalation, Ingestion, Skin and/or Eye Contact	Irritation eyes, skin; lung fibrosis (histologic)
Copper	1 mg/m3	100 mg/m3	Inhalation, Ingestion, skin and/or eye contact	Irritation eyes, respiratory system; cough, dyspnea (breathing difficulty), wheezing; [potential occupational carcinogen]
Lead	0.05 mg/m^3	100 mg/m^3	Inhalation, Ingestion, Skin and/or Eye Contact	Lassitude (weakness, exhaustion), insomnia; facial pallor; anorexia, weight loss, malnutrition; constipation, abdominal pain, colic; anemia; gingival lead line; tremor; paralysis wrist, ankles; encephalopathy; kidney disease; irritation eyes; hypertension
Mercury	0.1 mg/m3	10 mg/m3	Inhalation, Ingestion, Skin Absorption, Skin and/or Eye Contact	Irritation eyes, skin; cough, chest pain, dyspnea (breathing difficulty), bronchitis, pneumonitis; tremor, insomnia, irritability, indecision, headache, lassitude (weakness, exhaustion); stomatitis, salivation; gastrointestinal disturbance, anorexia, weight loss; proteinuria
Nickel	1 mg/m3	10 mg/m3	Inhalation, Skin Absorption, Ingestion, skin and/or eye contact	Irritation eyes, skin; cough, chest pain, dyspnea (breathing difficulty), bronchitis, pneumonitis; tremor, insomnia, irritability, indecision, headache, lassitude (weakness, exhaustion); stomatitis, salivation; gastrointestinal disturbance, anorexia, weight loss; proteinuria

TABLE 2
SELECTED POTENTIAL CHEMICAL EXPOSURE LIMITS AND HEALTH EFFECTS
12074 FLATLANDS AVENUE
BROOKLYN, NEW YORK

Chemical	Permissible Exposure Limit	IDLH Limit	Exposure Routes	Exposure Symptoms
Selenium	0.2 mg/m^3	1 mg/m^3	Inhalation, ingestion, skin and/or eye contact	Irritation eyes, skin, nose, throat; visual disturbance; headache; chills, fever; dyspnea (breathing difficulty), bronchitis; metallic taste, garlic breath, gastrointestinal disturbance; dermatitis; eye, skin burns; In Animals: anemia; liver necrosis, cirrhosis; kidney, spleen damage
Silver	0.01 mg/m^3	10 mg/m^3	Inhalation, ingestion, skin and/or eye contact	Blue-gray eyes, nasal septum, throat, skin; irritation, ulceration skin; gastrointestinal disturbance
Zinc	1 mg/m^3	10 mg/m^3	Inhalation, Ingestion	Sensitization dermatitis, allergic asthma, pneumonitis; (potential occupational carcinogen)
Perfluorooctanesulfonic Acid (PFOS)	---	---	Inhalation, Ingestion	High cholesterol, thyroid disorders, reproductive effects; (potential occupational carcinogen); accumulates in blood stream and liver
Perfluorooctanoic Acid (PFOA)	---	---	Inhalation, Ingestion	High cholesterol, thyroid disorders, reproductive effects; (potential occupational carcinogen); accumulates in blood stream and liver

--- No exposure limits listed in the NIOSH Pocket Guide to Chemical Hazards dated November 2010.

TABLE 3
HAZARD ANALYSIS
12074 FLATLANDS AVENUE
BROOKLYN, NEW YORK

Task	Potential Risk	Description	Control Measure
1, 2, 3, 4	Lifting equipment	Improper lifting/carrying of equipment and materials	Follow safe lifting and general material handling
2, 3, 4, 5, 6, 7	Noise	Loud sounds caused by the machines during drilling, or excavation	Wear proper PPE (hearing protection)
2, 3, 4, 5, 6, 7	Working near heavy machinery	Close proximity to drill rig and/or construction equipment	Be aware of surroundings, wear safety vest and hard hat
1, 2, 3, 4, 5, 6, 7	Slips, trips, and falls	Any number of injuries from slips, trips, and falls in carrying out these tasks	Good housekeeping at site, constant awareness and focus on the task
2, 4, 6, 7	Inhalation of Dust	Breathing in visible dust from earthwork using drills or excavators	Wear proper PPE, monitor air for dust concentrations, use dust suppression techniques
2, 3, 4, 5, 6, 7	Inhalation of Volatiles	Breathing in volatiles from earthwork using drills or excavators causing dust	Wear proper PPE, monitor air for volatile concentrations, use dust suppression techniques
2, 4	Utilities	Hitting utility lines during drilling and or excavating	Use proper mark out of underground utilities before beginning earthwork
2, 3, 4, 5, 6, 7	Skin contact with contaminated material	Material falls on skin; gets in eye	Wear proper PPE; follow safe work practices
2, 3, 4, 5, 6, 7	Ingestion of contaminated material	Material falls on skin; gets into mouth	Wear proper PPE; follow safe work practices
2, 3, 4, 5, 6, 7	Skin and eye contact with contaminated material	Material falls on skin; gets in eye	Wear proper PPE; follow safe work practices
1, 2, 3, 4, 5, 6, 7	Heat Stress	Stress or exhaustion related to high temperatures	Hydrate and rest as needed
1, 2, 3, 4, 5, 6	Cold Stress	Stress or exhaustion related to low temperatures; hypothermia	Wear proper PPE; follow safe work practices
1, 2, 3, 4, 5, 6,7	Bites and stings	Bee stings, ticks, snake bites	Wear proper PPE, be watchful, follow safe work practices
2, 3, 4, 5, 6, 7	Lacerations and abrasions	Many opportunities working with hand tools	Inspect equipment being used for sharp edges, wear proper PPE; follow safe work practices

TABLE 4
INSTRUMENTATION ACTION LEVELS
12074 FLATLANDS AVENUE
BROOKLYN, NEW YORK

Instrument	Action Level	Level of Protection / Action Required
PID	Background to 5 ppm	Level D/No respirator; no further action required
	> 5 ppm for > 5 minutes	1. Temporarily discontinue all activities and evaluate potential causes of the excessive readings. If these levels persist and cannot be mitigated (i.e., by slowing drilling or excavation activities), contact HSO to review conditions and determine source and appropriate response action. 2. If PID readings remain above 5 ppm, temporarily discontinue work and upgrade to Level C protection. 3. If sustained PID readings fall below 1 ppm, downgrading to Level D protection may be permitted
	> 5 ppm but < 150 ppm for > 5 minutes	Level C/ 1. Discontinue all work; all workers shall move to an area upwind of the jobsite. 2. Evaluate potential causes of the excessive readings and allow work area to vent until VOC concentrations fall below 5 ppm. 3. Level C protection will continue to be used until PID readings fall below 1 ppm.
	> 30 ppm (steady state condition) within AOC zone	Stop Work / Suppress Emissions / Evacuate and re-evaluate.
	> 150 ppm	Evacuate the work area

Total Dust Aerosol Monitor	> 0.100 mg/m^3 above BKD (steady state condition) at perimeter of AOC zone for 15-minutes or visible dust.	Stop Work / Implement dust control / Continue dust monitoring if dust levels are less than 150 mg/m3
	< 0.150 mg/m3 above BKD (following dust suppression measures)	Stop Work / implement dust control, continue work once levels are <150 mg/m3
	>5 mg/m3	Level C

Notes:

1. 1 ppm level based on OSHA Permissible Exposure Limit (PEL) for benzene.
2. 5 ppm level based on OSHA Short Term Exposure Limit (STEL) maximum exposure for vinyl chloride for any 15-minute period.
3. 150 ppm level based on NIOSH Immediately Dangerous to Life and Health (IDLH) for tetrachloroethylene

TABLE 5
PERSONAL PROTECTIVE EQUIPMENT
12074 FLATLANDS AVENUE
BROOKLYN, NEW YORK

Respiratory Protection*:*

Level D:	No respirator required.
Level C:	Half-face, Air Purifying Respirator (APR) with combination HEPA (dusts, fumes, aerosols) and organic vapor cartridges. The respirator will be NIOSH-approved.
Level C - supplemental by task	Fullface, Air Purifying Respirator (APR) with combination HEPA (dusts, fumes, aerosols), acid gas, organic vapor cartridges. The respirator will be NIOSH-approved.

Personal Protective Clothing*:*

Level D:	Hard-hat, traffic vest (if working on or adjacent to the roadway), long sleeve work shirt & work pants of natural fibers, safety glasses or goggles, steel-toed boots, hearing protection (if needed), nitril inner gloves and leather outer gloves.
Level D - supplemental PPE by task	Tyvek disposal suit
Level C:	Chemically resistant outer boots and Chemical resistant Tyvek disposal suite.

FIGURES



LANGAN

300 Kimball Drive
Parsippany, NJ 07054
T: 973.560.4900 F: 973.560.4901 www.langan.com

Langan Engineering & Environmental Services, Inc.
Langan Engineering, Environmental, Surveying, Landscape Architecture and Geology, D.P.C.
Langan International LLC
Collectively known as Langan

NJ CERTIFICATE OF AUTHORIZATION No. 24GA27996400

Project

12074 FLATLANDS AVENUE

BLOCK No. 4434, LOT No. 1

BROOKLYN

KINGS COUNTY NEW YORK

Drawing Title

SITE LOCATION MAP

Project No. 100688801	Figure 1
Date 5/25/2023	
Scale 1"=2,000'	
Drawn By IHB	

© 2018 Langan

Path: \\langan.com\data\PAR\data8\100688801\Project Data\ArcGIS\MXD\Environmental_Figures\2022-01 CCC RIWP\Figure 1 - Site Location Map.mxd



Emergency Route to Brookdale Medical Center: Emergency Room (Phone # (718) 240-5363) :

1 Head northeast on Flatlands Avenue towards Granville Payne Avenue/Pennsylvania Avenue
2 Turn left after Castrol Premium Lube Express (on the left)
3 Turn left onto Linden Blvd
4 Slight right toward Linden Blvd
5 Slight left toward Linden Blvd; the emergency room will be on the right

MAP REFERENCE: Google Maps

LANGAN

Project

12096 Flatlands Avenue
EMERGENGY HOSPITAL ROUTE MAP

bronx **New York**

Project	DATE	SCALE	FIGURE NO.
100688801	**5/12/2023**	**See Scale Bar**	**2**

ATTACHMENT A

Health and Safety Briefing Statement

LANGAN

ATTACHMENT A

HEALTH AND SAFETY BRIEFING STATEMENT

The following personnel were present at a pre-job safety briefing conducted at _____ (time) on _____ (date) at _____ (location), and have read this Health and Safety Plan for the above Site and are familiar with its provisions:

Name	Signature
_____	_____
_____	_____
_____	_____
_____	_____
_____	_____
_____	_____
_____	_____
_____	_____
_____	_____
_____	_____

Fully charged ABC class fire extinguisher available on Site? _____
Fully stocked First Aid Kit available on Site? _____
All project personnel advised of location of nearest phone? _____
All project personnel advised of location of designated medical facility? _____

_____
Name of Field Team Leader or Site Safety Officer

_____
Signature Date

ATTACHMENT B

Field Procedures Change Authorization Form

LANGAN

ATTACHMENT B

FIELD PROCEDURES CHANGE AUTHORIZATION FORM

Section to be changed: _____

Duration of Authorization Requested Date: _____

_____ Today only

_____ Duration of Task

_____ Other_____

_____

_____

Description of Procedures Modification:

_____

_____

_____

Justification:

_____ _____

Person Requesting Change Verbal Authorization Received From:

_____ _____

Name Name Time

_____ _____

Title Title

_____

Signature

Approvals:

_____

_____

_____

ATTACHMENT C

Unsafe Conditions and Practices Form

LANGAN

ATTACHMENT C

UNSAFE CONDITIONS AND PRACTICES FORM

DESCRIPTION OF CIRCUMSTANCES REGARDING UNSAFE CONDITION OR PRACTICE:

_____

_____

_____

_____

_____

_____

_____

IS THIS CONDITION EXISTING OR POTENTIAL? _____

REPORTED TO: _____

REPORTED BY:_____

DATE REPORTED: _____

COMMENTS:

_____

_____

_____

ATTACHMENT D

Calibration Log

ATTACHMENT D

PROJECT: _____

DATE: _____

CALIBRATION LOG

Time	Inst Type	Inst #	Media	Initial Reading	Span #	Calib Reading	Performed By:

ATTACHMENT E

Emergency Notification Numbers

ATTACHMENT E

EMERGENCY NOTIFICATION NUMBERS

The following list provides names and telephone numbers for emergency contact personnel.

ORGANIZATION	CONTACT		TELEPHONE
New York City Police			911
New York City Fire			911
Brookdale University Hospital			718-240-5363
WorkCare (Non-Emergency Medical Treatment)			1-888-449-7787
Langan Incident / Injury Hotline			973-560-4699
Langan Project Manager	Amanda Forsburg		973-560-4574
National Response Center			800-424-8802
Center for Disease Control			404-488-4100
CHEMTREC			800-424-9300
TSCA HOTLINE			202-554-1404
RCRA HOTLINE			800-424-9346
CDC		(DAY) (NIGHT)	404-452-4100 404-329-2888
BUREAU OF ALCOHOL, TOBACCO & FIREARMS			800-424-9555 202-566-7777
NATIONAL RESPONSE CENTER			800-424-8802
PESTICIDE INFORMATION SERVICE			800-424-9346
BUREAU OF EXPLOSIVES, A.A. RAILWAYS			202-835-9500
FEDERAL EXPRESS - HAZARDOUS MATERIAL INFO			901-922-1666

ATTACHMENT F

Accident / Incident Report Form

LANGAN

ATTACHMENT F

INCIDENT REPORT

LANGAN EMPLOYEE EXPOSURE/INJURY INCIDENT REPORT
(Submit a Separate Report for Each Employee and/or Incident)

Date: _____

Employee's Name: _____ Employee No: _____

Sex: M _____ F _____ Age: _____

Region: _____ Location:_____

Project: _____ Project No: _____

Incident: _____

Type: Possible Exposure _____ Exposure _____ Physical Injury _____

Location: _____

Date of Incident: _____ Time of Incident: _____

Date of Report Incident: _____

Person(s) to Whom Incident was Reported: _____

Weather Conditions During Incident: Temperature _____ Humidity _____

Wind Speed and Direction: _____ Cloud Cover: _____

Clear: _____ Precipitation: _____

Materials Potentially Encountered: _____

Chemical (give name of description - liquid, solid, gas, vapor, fume, mist):

_____

_____

Radiological: _____

Other: _____

Nature of the Exposure/Injury: (State the nature of the exposure/injury in detail and list the parts of the body affected. Attach extra sheets if necessary).

_____

_____

_____

_____

_____

Did you receive medical care? Yes _____ No _____ If so, when _____

Where? On-Site _____ Off-Site _____

By Whom: Name of Paramedic: _____

Name of Physician: _____

Other: _____

If Off-Site, name facility (hospital, clinic, etc):_____

_____

Length of stay at the facility? _____

Was the Site Safety Officer contacted? Yes _____ No _____ When?_____

Was the Corporate Health and Safety Officer contacted? Yes _____ No _____

If so, who was the contact? _____

Did the exposure/injury result in permanent disability? Yes _____ No _____

If so, explain: _____

_____

_____

_____

Has the employee returned to work? Yes _____ No _____

List the names of other persons affected during this incident:

_____

_____

_____

_____

_____

_____

List the names of persons who witnessed the exposure/injury incident:

_____

_____

_____

_____

_____

_____

_____

Possible cause of the exposure/injury incident: _____

_____

_____

_____

_____

_____

What was the name and title of the field team leader or immediate supervisor at the site of the incident?

_____

Was the operation being conducted under an established Health and Safety Plan?

Yes _____ No _____ If yes, attach a copy. If no, explain

_____

_____

_____

_____

_____

_____

Describe protective equipment and clothing used by the employee:

_____

_____

_____

_____

_____

_____

Did any limitations in safety equipment or protective clothing contribute to or affect exposure? If so, explain:

_____

_____

_____

What was the employee doing when the exposure/injury occurred? (Describe briefly as Site Reconnaissance, Site Characterization, or Sampling, etc.):

_____

_____

_____

_____

Where exactly on site or off site did the exposure/injury occur?

_____

_____

_____

_____

_____

How did the exposure/injury occur? (Describe fully what factors led up to and/or contributed to the incident):

_____

_____

_____

_____

_____

Name of person(s) initiating report, job title, phone number:

_____

_____

_____

_____ _____

Employee Signature Date

_____ _____

Site Safety Officer Signature or Field Team Leader Signature Date

ATTACHMENT G

Safety Data Sheets
(SDS)

LANGAN

Safety Data Sheet

1,1-Dichloro-2,2-bis(4-chlorophenyl-d_4)ethylene

Section 1. Chemical product and company identifications

Product code: D-3005
Chemical formula: $C_{14}D_8Cl_4$
CAS: 93952-19-3
CAS (unlabelled): 72-55-9
Synonyms: 4,4'-DDE, 2,2-Bis(4-chlorophenyl)-1,1-dichloroethylene

Supplier / Manufacturer:

C/D/N Isotopes Inc.
88 Leacock Street
Pointe-Claire (Québec) H9R 1H1
Phone: 514-697-6254
Toll-Free (Canada & USA): 1-800-565-4696
Fax: 514-697-6148
Website: www.cdnisotopes.com

In case of emergency:

TOXYSCAN HOTLINE: 1-855-780-0599

Section 2. Hazards identifications

Physical state: Solid
Warning: Harmful if swallowed. Suspected of causing cancer.
Routes of entry: Inhalation, skin and eyes

GHS (Globally Harmonized System of Classification and Labelling of Chemicals):

GHS Classification:
- Acute toxicity, Oral (Category 4)
- Carcinogenicity (Category 2)

GHS Label elements:
- Pictograms:
- Signal word: Warning

Hazards statement:
- H302 Harmful if swallowed.
- H351 Suspected of causing cancer.

Precautionary statement: - P281 Use personal protective equipment as required.

Section 3. Composition and information on ingredients

Name	CAS	Concentration %
1,1-Dichloro-2,2-bis(4-chlorophenyl-d_4)ethylene	93952-19-3	> 98

Section 4. First aid measures

Eye contact: Flush eyes with water as a precaution.
Skin contact: Wash off with soap and plenty of water. Consult a physician.
Inhalation: If breathed in, move person into fresh air. If not breathing, give artificial respiration. Consult a physician.
Ingestion: Never give anything by mouth to an unconscious person. Rinse mouth with water. Consult a physician.
General advice: Consult a physician. Show this safety data sheet to the doctor in attendance. Move out of dangerous area.

©2015 All rights reserved C/D/N Isotopes, Inc. / Toxyscan, Inc.

Section 5. Firefighting measures

Flammability of the product: Not flammable or combustible.
Lower explosion limit: No data available.
Upper explosion limit: No data available.
Auto-ignition temperature: No data available.
Flash point: No data available.
Products of combustion: Hazardous decomposition products formed under fire conditions: Carbon oxides, hydrogen chloride gas.
Firefighting media and instructions: Use water spray, alcohol-resistant foam, dry chemical or carbon dioxide.
Special protective equipment for firefighters: Wear self-contained breathing apparatus for firefighting if necessary.

Section 6. Accidental release measures

Personal precautions: Use personal protective equipment. Avoid dust formation. Avoid breathing vapours, mist or gas. Ensure adequate ventilation. Evacuate personnel to safe areas. Avoid breathing dust.
Environmental precautions: Prevent further leakage or spillage if safe to do so. Do not let product enter drains. Discharge into the environment must be avoided.
Methods for cleaning up: Pick up and arrange disposal without creating dust. Sweep up and shovel. Keep in suitable, closed containers for disposal.

Section 7. Handling and storage

Handling: Avoid contact with skin and eyes. Avoid formation of dust and aerosols. Provide appropriate exhaust ventilation at places where dust is formed. Normal measures for preventive fire protection.
Storage: Store at room temperature. Adequate ventilation. Protect from light.

Section 8. Exposure Controls, Personal Protections

Engineering controls: Use mechanical exhaust or laboratory fumehood to avoid exposure.
Eyes: Safety glasses with side-shields conforming to NIOSH (US).
Respiratory: Where risk assessment shows air-purifying respirators are appropriate use a full-face respirator with multi-purpose combination (US) or type ABEK (EN 14387) respirator cartridges as a backup to engineering controls. If the respirator is the sole means of protection, use a full-face supplied air respirator. Use respirators and components tested and approved under appropriate government standards such as NIOSH (US).
Hands: Handle with gloves. Dispose of contaminated gloves after use in accordance with applicable laws and good laboratory practices. Wash and dry hands.
Skin/body: Impervious clothing. The type of protective equipment must be selected according to the concentration and amount of the dangerous substance at the specific workplace.

Section 9. Physical and chemical properties (unlabelled)

Molecular weight: 318.03 g/mol
Physical status: Solid
Color: White-pale yellow
Odour: No data available
Density: No data available
Melting point: 88 - 90 °C (190 - 194 °F)
Boiling point: 336 °C (637 °F)
Vapour pressure: < 0.00001 hPa (< 0.00001 mmHg)
Vapour density: No data available
Partition coefficient (octanol/water): log Pow: 6.51
Water solubility: 0.04 mg/L

Section 10. Stability and reactivity

Stability and reactivity: Stable under recommended storage conditions.
Incompatibility: Strong oxidizing agents, strong bases.
Products of combustion: Hazardous decomposition products formed under fire conditions: Carbon oxides, hydrogen chloride gas.
Reactivity conditions: No data available.

©2015 All rights reserved C/D/N Isotopes, Inc. / Toxyscan, Inc.

Section 11. Toxicological information (unlabelled)

Toxicological data: 1,1-Dichloro-2,2-bis(4-chlorophenyl)ethylene

Information on ingredients:

Name	CAS	LD_{50}	LC_{50}
1,1-Dichloro-2,2-bis(4-chlorophenyl)ethylene	72-55-9	Oral - rat - 880 mg/kg	No data available

Potential acute effects

- **Eyes:** May cause eye irritation.
- **Skin:** Harmful if absorbed through skin. May cause skin irritation.
- **Inhalation:** May be harmful if inhaled. May cause respiratory tract irritation.
- **Ingestion:** Harmful if swallowed.

Potential chronic effects

- **Carcinogenic effects:** This product is or contains a component that has been reported to be possibly carcinogenic based on its IARC, ACGIH, NTP, or EPA classification. Limited evidence of carcinogenicity in animal studies. IARC: No component of this product present at levels greater than or equal to 0.1% is identified as probable, possible or confirmed human carcinogen by IARC. ACGIH: No component of this product present at levels greater than or equal to 0.1% is identified as a carcinogen or potential carcinogen by ACGIH.
- **Mutagenic effects:** No data available.
- **Teratogenic effects:** No data available.
- **Medical conditions aggravated by overexposure:** No data available.

Section 12. Ecological information

Ecological data:

Name	Results	Species	Period
1,1-Dichloro-2,2-bis	0.2 - 0.3 mg/l LC50	Lepomis macrochirus	96 h
(4-chlorophenyl)ethylene	0.03 - 0.04 mg/l LC50	Oncorhynchus mykiss	96 h
	0.05 - 0.18 mg/l LC50	Salmo salar	96 h

Effects on environment: An environmental hazard cannot be excluded in the event of unprofessional handling or disposal.
Mobility: No data available.
Environmental precautions: No data available.
Persistence and degradability: No data available.
Bioaccumulative potential: Gambusia affinis (Mosquito fish) - 33 d. Bioconcentration factor (BCF): 12,037.

Section 13. Disposal considerations

Waste disposal: Offer surplus and non-recyclable solutions to a licensed disposal company. Contact a licensed professional waste disposal service to dispose of this material. Dissolve or mix the material with a combustible solvent and burn in a chemical incinerator equipped with an afterburner and scrubber.

Section 14. Transportation information

Classification DOT/IMDG/IATA label:

Shipping name: Not dangerous goods
UN number: None
Class: None
Packaging group: None

Additional information: None

©2015 All rights reserved C/D/N Isotopes, Inc. / Toxyscan, Inc.

Section 15. Regulatory information

UNITED STATES:
NFPA classification

Health: 1
Flammable: 0
Reactivity: 0
Specials conditions: None

Legend: 4: Severe, 3: High, 2: Moderate, 1: Slightly, 0: Not hazardous

U.S. Federal regulations:

TSCA 8(b) inventory: 1,1-Dichloro-2,2-bis(4-chlorophenyl)ethylene
SARA 302/304/311/312 extremely hazardous substances: Not Listed
SARA 302/304 emergency planning and notification: Not Listed
SARA 302/304/311/312 hazardous chemicals: Not Listed
SARA 311/312 MSDS distribution - chemical inventory - hazard identification: Fire hazard, Immediate (acute) health hazard, Delayed (chronic) health hazard: Not Listed
CWA (Clean Water Act) 307: Not Listed
CWA (Clean Water Act) 311: Not Listed
CAA (Clean Air Act) 112 accidental release prevention: Not Listed
CAA (Clean Air Act) 112 regulated flammable substances: Not Listed
CAA (Clean Air Act) 112 regulated toxic substances: Not Listed

State regulations:

DEA List I Chemicals (Precursor Chemicals): Not Listed
DEA List II Chemicals (Essential Chemicals): Not Listed
Substances in Massachusetts: Not Listed
Dangerous substances in New Jersey: Not Listed
New York – Dangerous substances with acute effects: Not Listed
Dangerous substances in Pennsylvania – right to know: Not Listed

WHMIS (Canada):

Not WHMIS controlled.

Section 16. Additional information

References:

- ANSI Z400.1, MSDS Standard, 2001.
- Manufacturer's Material Safety Data Sheet.
- 29CFR Part1910.1200 OSHA MSDS Requirements.
- 49CFR Table List of Hazardous Materials, UN#, Proper Shipping Names, PG. -Canada
- Gazette Part II, Vol. 122, No. 2 Registration SOR/88-64 31 December, 1987 Hazardous Products Act "Ingredient Disclosure List".
- Federal act on the controlled products
- Canadian Transport of Dangerous Goods, Regulations and Schedules, Clear Language version 2002.
- Toxicological repertory, HSC.
- Material safety data sheet from the components.

Date of issue: **February 20th, 2017**
Version: 1
Elaborated by: **Toxyscan Inc., 1-866-780-0599**
Notice to reader: To the best of our knowledge, the information contained herein is accurate. However, C/D/N Isotopes Inc., Toxyscan Inc., or any of its subsidiaries assumes any liability whatsoever for the accuracy or completeness of the information contained herein. Final determination of suitability of any material is the sole responsibility of the user. All materials may present unknown hazards and should be used with caution. Although certain hazards are described herein, we cannot guarantee that these are the only hazards that exist.

©2015 All rights reserved C/D/N Isotopes, Inc. / Toxyscan, Inc.

Safety Data Sheet

Revision Date: 12/23/16
www.restek.com

1. IDENTIFICATION

Catalog Number / Product Name:	**32203 / 4,4'-DDT Standard**
Company:	Restek Corporation
Address:	110 Benner Circle Bellefonte, Pa. 16823
Phone#:	814-353-1300
Fax#:	814-353-1309
Emergency#:	800-424-9300 (CHEMTREC) 703-527-3887 (Outside the US)
Email:	www.restek.com
Revision Number:	8
Intended use:	For Laboratory use only

2. HAZARD(S)IDENTIFICATION

Emergency Overview:

GHS Hazard Symbols:

GHS Classification:
Specific Target Organ Systemic Toxicity (STOT) - Single Exposure Category 1
Flammable Liquid Category 2
Acute Toxicity - Inhalation Dust / Mist Category 3
Acute Toxicity - Dermal Category 3
Acute Toxicity - Oral Category 3

GHS Signal Word:
Danger

GHS Hazard:
Highly flammable liquid and vapour.
Toxic if swallowed, in contact with skin or if inhaled.
Causes damage to organs.

GHS Precautions:

Safety Precautions:
Keep away from heat/sparks/open flames/hot surfaces. – No smoking.
Ground/bond container and receiving equipment.
Use explosion-proof electrical/ventilation and lighting equipment.
Use only non-sparking tools.
Take precautionary measures against static discharge.
Do not breathe dust/fume/gas/mist/vapours/spray.
Wash hands and skin thoroughly after handling.
Do not eat, drink or smoke when using this product.
Use only outdoors or in a well-ventilated area.
Wear protective gloves/protective clothing/eye protection/face protection.

First Aid Measures:
IF SWALLOWED: Immediately call a POISON CENTER/doctor/....
IF ON SKIN: Wash with plenty of soap and water.
IF ON SKIN (or hair): Remove/Take off immediately all contaminated clothing. Rinse skin with water/shower.
IF INHALED: Remove victim to fresh air and keep at rest in a position comfortable for breathing.
IF exposed: Call a POISON CENTER or doctor/physician.
Call a POISON CENTER or doctor/physician.
Call a POISON CENTER or doctor/physician if you feel unwell.
Specific treatment see section 4.
Rinse mouth.
Take off immediately all contaminated clothing and wash it before reuse.
In case of fire: Use extinguishing media in section 5 for extinction.

Storage: Store in a well-ventilated place. Keep container tightly closed.
Store in a well-ventilated place. Keep cool.
Store locked up.

Disposal: Dispose of contents/container according to section 13 of the SDS.

Single Exposure Target Organs: No data available.

Repeated Exposure Target Organs: No data available.

3. COMPOSITION / INFORMATION ON INGREDIENT

Chemical Name	CAS #	EINEC #	% Composition
methanol	67-56-1	200-659-6	99.900000
4,4'-DDT	50-29-3	200-024-3	0.100000

4. FIRST-AID MEASURES

Inhalation: Remove to fresh air. If breathing is difficult, have a trained individual administer oxygen. If not breathing, give artificial respiration and have a trained individual administer oxygen. Get medical attention immediately

Eyes: Flush eyes with plenty of water for at least 20 minutes retracting eyelids often. Tilt the head to prevent chemical from transferring to the uncontaminated eye. Get immediate medical attention.

Skin Contact: Wash with soap and water. Remove contaminated clothing and launder. Get medical attention if irritation develops or persists.

Ingestion: Do not induce vomiting and seek medical attention immediately. Drink two glasses of water or milk to dilute. Provide medical care provider with this SDS.

5. FIRE- FIGHTING MEASURES

Extinguishing Media: Use alcohol resistant foam, carbon dioxide, or dry chemical extinguishing agents. Water may be ineffective but water spray can be used extinguish a fire if swept across the base of the flames. Water can absorb heat and keep exposed material from being damaged by fire.

Fire and/or Explosion Hazards: Vapors may be ignited by sparks, flames or other sources of ignition if material is above the flash point giving rise to a fire (Class B). Vapors are heavier than air and may travel to a source of ignition and flash back.

Fire Fighting Methods and Protection: Do not enter fire area without proper protection including self-contained breathing apparatus and full protective equipment. Fight fire from a safe distance and a protected location due to the potential of hazardous vapors and decomposition products. Flammable component(s) of this material may be lighter than water and burn while floating on the surface.

Hazardous Combustion Products: Carbon dioxide, Carbon monoxide

6. ACCIDENTAL RELEASE MEASURES

Personal Precautions and Equipment: Exposure to the spilled material may be severely irritating or toxic. Follow personal protective equipment recommendations found in Section 8 of this SDS. Personal protective equipment needs must be evaluated based on information provided on this sheet and the special circumstances created by the spill including; the material spilled, the quantity of the spill, the area in which the spill occurred, and the expertise of employees in the area responding to the spill. Never exceed any occupational exposure limits.

Methods for Clean-up: Prevent the spread of any spill to minimize harm to human health and the environment if safe to do so. Wear complete and proper personal protective equipment following the recommendation of Section 8 at a minimum. Dike with suitable absorbent material like granulated clay. Gather and store in a sealed container pending a waste disposal evaluation.

7. HANDLING AND STORAGE

Handling Technical Measures and Precautions:	Toxic or severely irritating material. Avoid contacting and avoid breathing the material. Use only in a well ventilated area. Use spark-proof tools and explosion-proof equipment
Storage Technical Measures and Conditions:	Store in a cool dry ventilated location. Isolate from incompatible materials and conditions. Keep container(s) closed. Keep away from sources of ignition

8. EXPOSURE CONTROLS / PERSONAL PROTECTION

United States:

Chemical Name	CAS No.	IDLH	ACGIH STEL	ACGIH TLV-TWA	OSHA Exposure Limit
methanol	67-56-1	6000 ppm IDLH	250 ppm STEL	200 ppm TWA	200 ppm TWA; 260 mg/m3 TWA
4,4'-DDT	50-29-3	500 mg/m3 IDLH		1 mg/m3 TWA	1 mg/m3 TWA (listed under Dichlorodiphenyltrichloroethane)

Personal Protection:

Engineering Measures:	Local exhaust ventilation is recommended when generating excessive levels of vapors from handling or thermal processing.
Respiratory Protection:	Respiratory protection may be required to avoid overexposure when handling this product. General or local exhaust ventilation is the preferred means of protection. Use a respirator if general room ventilation is not available or sufficient to eliminate symptoms.If an exposure limit is exceeded or if an operator is experiencing symptoms of inhalation overexposure as explained in Section 3, provide respiratory protection.
Eye Protection:	Wear chemically resistant safety glasses with side shields when handling this product. Do not wear contact lenses.
Skin Protection:	Wear protective gloves. Inspect gloves for chemical break-through and replace at regular intervals. Clean protective equipment regularly. Wash hands and other exposed areas with mild soap and water before eating, drinking, and when leaving work

9. PHYSICAL AND CHEMICAL PROPERTIES

Appearance, color:	No data available.
Odor:	Mild
Physical State:	No data available.
pH:	No data available.
Vapor Pressure:	No data available.
Vapor Density:	1.1 (air = 1)
Boiling Point:	No data available.
Melting Point:	-98 °C
Flash Point:	52
Flammability:	Highly Flammable
Upper Flammable/Explosive Limit, % in air:	36
Lower Flammable/Explosive Limit, % in air:	6
Autoignition Temperature:	464 deg C
Decomposition Temperature:	No data available.
Specific Gravity:	0.791 - 0.792 g/cm3 at 20 °C
Evaporation Rate:	No data available.
Odor Threshold:	No data available.
Solubility:	Moderate; 50-99%
Partition Coefficient: n-octanol in water:	No data available.
VOC % by weight:	99.9
Molecular Weight:	32.04

10. STABILITY AND REACTIVITY

Stability:	Stable under normal conditions.
Conditions to Avoid:	No data available.
Materials to Avoid / Chemical Incompatiability:	Strong oxidizing agents
Hazardous Decomposition Products:	Carbon dioxide Carbon monoxide

11. TOXICOLOGICAL INFORMATION

Routes of Entry:	Inhalation, Skin Contact, Eye Contact, Ingestion
Target Organs Potentially Affected By Exposure:	Eyes, Central nervous system stimulation, Skin, GI Tract, Respiratory Tract
Chemical Interactions That Change Toxicity:	None Known

Immediate (Acute) Health Effects by Route of Exposure:

Inhalation Irritation:	Can cause moderate respiratory irritation, dizziness, weakness, fatigue, nausea and headache.
Inhalation Toxicity:	Harmful! Can cause systemic damage (see "Target Organs)Methanol can cause central nervous system depression and overexposure can cause damage to the optic nerve resulting in visual impairment or blindness.
Skin Contact:	Can cause moderate skin irritation, defatting, and dermatitis. Not likely to cause permanent damage.
Eye Contact:	Can cause moderate irritation, tearing and reddening, but not likely to permanently injure eye tissue.
Ingestion Irritation:	Irritating to mouth, throat, and stomach. Can cause abdominal discomfort, nausea, vomiting and diarrhea.Highly toxic and may be fatal if swallowed.
Ingestion Toxicity:	Toxic if swallowed. May cause target organ failure and/or death.May be fatal if swallowed.

Long-Term (Chronic) Health Effects:

Carcinogenicity:	Contains a probable or known human carcinogen.
Reproductive and Developmental Toxicity:	Contains a known human reproductive and/or developmental hazard.
Inhalation:	Upon prolonged and/or repeated exposure, can cause moderate respiratory irritation, dizziness, weakness, fatigue, nausea and headache.Harmful! Can cause systemic damage upon prolonged and/or repeated exposure (see "Target Organs)
Skin Contact:	Upon prolonged or repeated contact, can cause moderate skin irritation, defatting, and dermatitis. Not likely to cause permanent damage.
Ingestion:	Toxic if swallowed. May cause target organ failure and/or death.

Component Toxicological Data:

NIOSH:

Chemical Name	CAS No.	LD50/LC50
Methanol	67-56-1	Inhalation LC50 Rat 22500 ppm 8 h
DDT	50-29-3	Dermal LD50 Rabbit 300 - 2820 mg/kg

Component Carcinogenic Data:

OSHA:

Chemical Name	CAS No.	
DDT	50-29-3	Present

ACGIH:

Chemical Name	CAS No.	
DDT	50-29-3	A3 - Confirmed Animal Carcinogen with Unknown Relevance to Humans

NIOSH:

Chemical Name	CAS No.	
DDT	50-29-3	potential occupational carcinogen

NTP:

Chemical Name	CAS No.
No data available.	

IARC:

Chemical Name	CAS No.	Group No.
No data.		Group 1
DDT	50-29-3	Group 2A
No data.		Group 2B

12. ECOLOGICAL INFORMATION

Overview:	Moderate ecological hazard. This product may be dangerous

to plants and/or wildlife.

Mobility: No data
Persistence: No data
Bioaccumulation: No data
Degradability: Biodegrades slowly.
Ecological Toxicity Data: No data available.

13. DISPOSAL CONSIDERATIONS

Waste Description of Spent Product: Spent or discarded material is a hazardous waste.
Disposal Methods: Dispose of by incineration following Federal, State, Local, or Provincial regulations.
Waste Disposal of Packaging: Comply with all Local, State, Federal, and Provincial Environmental Regulations.

14. TRANSPORTATION INFORMATION

United States:
DOT Proper Shipping Name: Methanol
UN Number: UN1230
Hazard Class: 3
Packing Group: II

International:
IATA Proper Shipping Name: Methanol
UN Number: UN1230
Hazard Class: 3(6.1)
Packing Group: II

Marine Pollutant: No

Chemical Name	CAS#	Marine Pollutant	Severe Marine Pollutant
No data available.			

15. REGULATORY INFORMATION

United States:

Chemical Name	CAS#	CERCLA	SARA 313	SARA EHS 313	TSCA
methanol	67-56-1	X	X	-	X
4,4'-DDT	50-29-3	X	-	-	X

The following chemicals are listed on CA Prop 65:

Chemical Name	CAS #	Regulation
DDT	50-29-3	Prop 65 Cancer
Methanol	67-56-1	Prop 65 Devolop Tox
p,p''-DDT	50-29-3	Prop 65 Devolop Tox
p,p''-DDT	50-29-3	Prop 65 Rep Female
p,p''-DDT	50-29-3	Prop 65 Rep Male

State Right To Know Listing:

Chemical Name	CAS#	New Jersey	Massachusetts	Pennsylvania	California
methanol	67-56-1	X	X	X	X
4,4'-DDT	50-29-3	X	X	X	X

16. OTHER INFORMATION

Prior Version Date: 09/30/14
Other Information: Any changes to the SDS compared to previous versions are marked by a vertical line in front of the concerned paragraph.
References: No data available.
Disclaimer: Restek Corporation provides the descriptions, data and information contained herein in good faith but makes no representation as to its comprehensiveness or accuracy. It is provided for your guidance only. Because many factors may affect processing or application/use, Restek Corporation recommends you perform an assessment to determine the suitability of a product for your particular purpose

prior to use. No warranties of any kind, either expressed or implied, including fitness for a particular purpose, are made regarding prodcuts described, data or information set forth. In no case shall the descriptions, information, or data provided be considered a part of our terms and conditions of sale. Further, the descriptions, data and information furnished hereunder are given gratis. No obligation or liability for the description, data and information given are assumed. All such being given and accepted at your risk.

SAFETY DATA SHEET

Version 4.7
Revision Date 05/23/2016
Print Date 06/23/2016

1. PRODUCT AND COMPANY IDENTIFICATION

1.1 Product identifiers

Product name : Arsenic

Product Number : 202657
Brand : Aldrich
Index-No. : 033-001-00-X

CAS-No. : 7440-38-2

1.2 Relevant identified uses of the substance or mixture and uses advised against

Identified uses : Laboratory chemicals, Synthesis of substances

1.3 Details of the supplier of the safety data sheet

Company : Sigma-Aldrich
3050 Spruce Street
SAINT LOUIS MO 63103
USA

Telephone : +1 800-325-5832
Fax : +1 800-325-5052

1.4 Emergency telephone number

Emergency Phone # : (314) 776-6555

2. HAZARDS IDENTIFICATION

2.1 Classification of the substance or mixture

GHS Classification in accordance with 29 CFR 1910 (OSHA HCS)
Acute toxicity, Oral (Category 4), H302
Acute toxicity, Inhalation (Category 3), H331
Acute aquatic toxicity (Category 1), H400
Chronic aquatic toxicity (Category 1), H410

For the full text of the H-Statements mentioned in this Section, see Section 16.

2.2 GHS Label elements, including precautionary statements

Pictogram

Signal word Danger

Hazard statement(s)
H302 Harmful if swallowed.
H331 Toxic if inhaled.
H410 Very toxic to aquatic life with long lasting effects.

Precautionary statement(s)
P261 Avoid breathing dust/ fume/ gas/ mist/ vapours/ spray.
P264 Wash skin thoroughly after handling.
P270 Do not eat, drink or smoke when using this product.
P271 Use only outdoors or in a well-ventilated area.
P273 Avoid release to the environment.

P301 + P312 + P330	IF SWALLOWED: Call a POISON CENTER/doctor if you feel unwell. Rinse mouth.
P304 + P340 + P311	IF INHALED: Remove person to fresh air and keep comfortable for breathing. Call a POISON CENTER/doctor.
P391	Collect spillage.
P403 + P233	Store in a well-ventilated place. Keep container tightly closed.
P405	Store locked up.
P501	Dispose of contents/ container to an approved waste disposal plant.

2.3 Hazards not otherwise classified (HNOC) or not covered by GHS - none

3. COMPOSITION/INFORMATION ON INGREDIENTS

3.1 Substances

Formula	:	As
Molecular weight	:	74.92 g/mol
CAS-No.	:	7440-38-2
EC-No.	:	231-148-6
Index-No.	:	033-001-00-X

Hazardous components

Component	Classification	Concentration
Arsenic		
	Acute Tox. 4; Acute Tox. 3; Aquatic Acute 1; Aquatic Chronic 1; H302, H331, H410	<= 100 %

For the full text of the H-Statements mentioned in this Section, see Section 16.

4. FIRST AID MEASURES

4.1 Description of first aid measures

General advice
Consult a physician. Show this safety data sheet to the doctor in attendance.Move out of dangerous area.

If inhaled
If breathed in, move person into fresh air. If not breathing, give artificial respiration. Consult a physician.

In case of skin contact
Wash off with soap and plenty of water. Take victim immediately to hospital. Consult a physician.

In case of eye contact
Flush eyes with water as a precaution.

If swallowed
Never give anything by mouth to an unconscious person. Rinse mouth with water. Consult a physician.

4.2 Most important symptoms and effects, both acute and delayed
The most important known symptoms and effects are described in the labelling (see section 2.2) and/or in section 11

4.3 Indication of any immediate medical attention and special treatment needed
No data available

5. FIREFIGHTING MEASURES

5.1 Extinguishing media

Suitable extinguishing media
Use water spray, alcohol-resistant foam, dry chemical or carbon dioxide.

5.2 Special hazards arising from the substance or mixture
No data available

5.3 Advice for firefighters
Wear self-contained breathing apparatus for firefighting if necessary.

5.4 Further information
No data available

6. ACCIDENTAL RELEASE MEASURES

6.1 Personal precautions, protective equipment and emergency procedures
Wear respiratory protection. Avoid dust formation. Avoid breathing vapours, mist or gas. Ensure adequate ventilation. Evacuate personnel to safe areas. Avoid breathing dust.
For personal protection see section 8.

6.2 Environmental precautions
Prevent further leakage or spillage if safe to do so. Do not let product enter drains. Discharge into the environment must be avoided.

6.3 Methods and materials for containment and cleaning up
Pick up and arrange disposal without creating dust. Sweep up and shovel. Keep in suitable, closed containers for disposal.

6.4 Reference to other sections
For disposal see section 13.

7. HANDLING AND STORAGE

7.1 Precautions for safe handling
Avoid contact with skin and eyes. Avoid formation of dust and aerosols.Further processing of solid materials may result in the formation of combustible dusts. The potential for combustible dust formation should be taken into consideration before additional processing occurs.
Provide appropriate exhaust ventilation at places where dust is formed.
For precautions see section 2.2.

7.2 Conditions for safe storage, including any incompatibilities
Keep container tightly closed in a dry and well-ventilated place.
Storage class (TRGS 510): Non-combustible, acute toxic Cat. 1 and 2 / very toxic hazardous materials

7.3 Specific end use(s)
Apart from the uses mentioned in section 1.2 no other specific uses are stipulated

8. EXPOSURE CONTROLS/PERSONAL PROTECTION

8.1 Control parameters

Components with workplace control parameters

Component	CAS-No.	Value	Control parameters	Basis
Arsenic	7440-38-2	TWA	0.01 mg/m3	USA. ACGIH Threshold Limit Values (TLV)
	Remarks	Lung cancer Substances for which there is a Biological Exposure Index or Indices (see BEI® section) Confirmed human carcinogen		
		C	0.0020 mg/m3	USA. NIOSH Recommended Exposure Limits
		Potential Occupational Carcinogen See Appendix A 15 minute ceiling value		

Biological occupational exposure limits

Component	CAS-No.	Parameters	Value	Biological specimen	Basis
Arsenic	7440-38-2	inorganic arsenic plus methylated metabolites	35µg As/l	In urine	ACGIH - Biological Exposure Indices (BEI)
	Remarks	End of the workweek (After four or five consecutive working days			

		with exposure)			
		inorganic arsenic plus methylated metabolites	35µg As/l	Urine	ACGIH - Biological Exposure Indices (BEI)
		End of the workweek (After four or five consecutive working days with exposure)			

8.2 Exposure controls

Appropriate engineering controls
Avoid contact with skin, eyes and clothing. Wash hands before breaks and immediately after handling the product.

Personal protective equipment

Eye/face protection
Face shield and safety glasses Use equipment for eye protection tested and approved under appropriate government standards such as NIOSH (US) or EN 166(EU).

Skin protection
Handle with gloves. Gloves must be inspected prior to use. Use proper glove removal technique (without touching glove's outer surface) to avoid skin contact with this product. Dispose of contaminated gloves after use in accordance with applicable laws and good laboratory practices. Wash and dry hands.

Full contact
Material: Nitrile rubber
Minimum layer thickness: 0.11 mm
Break through time: 480 min
Material tested:Dermatril® (KCL 740 / Aldrich Z677272, Size M)

Splash contact
Material: Nitrile rubber
Minimum layer thickness: 0.11 mm
Break through time: 480 min
Material tested:Dermatril® (KCL 740 / Aldrich Z677272, Size M)

data source: KCL GmbH, D-36124 Eichenzell, phone +49 (0)6659 87300, e-mail sales@kcl.de, test method: EN374
If used in solution, or mixed with other substances, and under conditions which differ from EN 374, contact the supplier of the CE approved gloves. This recommendation is advisory only and must be evaluated by an industrial hygienist and safety officer familiar with the specific situation of anticipated use by our customers. It should not be construed as offering an approval for any specific use scenario.

Body Protection
Complete suit protecting against chemicals, The type of protective equipment must be selected according to the concentration and amount of the dangerous substance at the specific workplace.

Respiratory protection
Where risk assessment shows air-purifying respirators are appropriate use a full-face particle respirator type N99 (US) or type P2 (EN 143) respirator cartridges as a backup to engineering controls. If the respirator is the sole means of protection, use a full-face supplied air respirator. Use respirators and components tested and approved under appropriate government standards such as NIOSH (US) or CEN (EU).

Control of environmental exposure
Prevent further leakage or spillage if safe to do so. Do not let product enter drains. Discharge into the environment must be avoided.

9. PHYSICAL AND CHEMICAL PROPERTIES

9.1 Information on basic physical and chemical properties

a)	Appearance	Form: Pieces Colour: grey
b)	Odour	No data available
c)	Odour Threshold	No data available

d)	pH	No data available
e)	Melting point/freezing point	Melting point/range: 817 °C (1,503 °F) - lit.
f)	Initial boiling point and boiling range	613 °C (1,135 °F) - lit.
g)	Flash point	Not applicable
h)	Evaporation rate	No data available
i)	Flammability (solid, gas)	No data available
j)	Upper/lower flammability or explosive limits	No data available
k)	Vapour pressure	No data available
l)	Vapour density	No data available
m)	Relative density	5.727 g/mL at 25 °C (77 °F)
n)	Water solubility	No data available
o)	Partition coefficient: n-octanol/water	No data available
p)	Auto-ignition temperature	No data available
q)	Decomposition temperature	No data available
r)	Viscosity	No data available
s)	Explosive properties	No data available
t)	Oxidizing properties	No data available

9.2 Other safety information
No data available

10. STABILITY AND REACTIVITY

10.1 Reactivity
No data available

10.2 Chemical stability
Stable under recommended storage conditions.

10.3 Possibility of hazardous reactions
No data available

10.4 Conditions to avoid
Heat Exposure to air may affect product quality.

10.5 Incompatible materials
Oxidizing agents, Halogens, Palladium undergoes a violent reaction with arsenic, Zinc, Platinum oxide, Nitrogen trichloride, Bromine azide

10.6 Hazardous decomposition products
Hazardous decomposition products formed under fire conditions. - Arsenic oxides
Other decomposition products - No data available
In the event of fire: see section 5

11. TOXICOLOGICAL INFORMATION

11.1 Information on toxicological effects

Acute toxicity
LD50 Oral - Rat - 763 mg/kg
Remarks: Behavioral:Ataxia. Diarrhoea

LD50 Oral - Mouse - 145 mg/kg
Remarks: Behavioral:Ataxia. Diarrhoea

Inhalation: No data available

Dermal: No data available

No data available

Skin corrosion/irritation
No data available

Serious eye damage/eye irritation
No data available

Respiratory or skin sensitisation
No data available

Germ cell mutagenicity
No data available

Carcinogenicity

This is or contains a component that has been reported to be carcinogenic based on its IARC, OSHA, ACGIH, NTP, or EPA classification.

IARC:	1 - Group 1: Carcinogenic to humans (Arsenic)
NTP:	Known to be human carcinogen (Arsenic)
	Known to be human carcinogen (Arsenic)
OSHA:	OSHA specifically regulated carcinogen (Arsenic)

Reproductive toxicity
No data available

No data available

Specific target organ toxicity - single exposure
No data available

Specific target organ toxicity - repeated exposure
No data available

Aspiration hazard
No data available

Additional Information
RTECS: CG0525000

Absorption into the body leads to the formation of methemoglobin which in sufficient concentration causes cyanosis. Onset may be delayed 2 to 4 hours or longer.

Stomach - Irregularities - Based on Human Evidence
Stomach - Irregularities - Based on Human Evidence

12. ECOLOGICAL INFORMATION

12.1 Toxicity

Toxicity to fish	LC50 - Pimephales promelas (fathead minnow) - 9.9 mg/l - 96.0 h
Toxicity to daphnia and other aquatic invertebrates	EC50 - Daphnia magna (Water flea) - 3.8 mg/l - 48 h

12.2 Persistence and degradability
No data available

12.3 Bioaccumulative potential
No data available

12.4 Mobility in soil
No data available

12.5 Results of PBT and vPvB assessment
PBT/vPvB assessment not available as chemical safety assessment not required/not conducted

12.6 Other adverse effects
An environmental hazard cannot be excluded in the event of unprofessional handling or disposal.
Very toxic to aquatic life with long lasting effects.

13. DISPOSAL CONSIDERATIONS

13.1 Waste treatment methods

Product
Offer surplus and non-recyclable solutions to a licensed disposal company. Contact a licensed professional waste disposal service to dispose of this material. Dissolve or mix the material with a combustible solvent and burn in a chemical incinerator equipped with an afterburner and scrubber.

Contaminated packaging
Dispose of as unused product.

14. TRANSPORT INFORMATION

DOT (US)
UN number: 1558 Class: 6.1 Packing group: II
Proper shipping name: Arsenic
Reportable Quantity (RQ): 1 lbs

Poison Inhalation Hazard: No

IMDG
UN number: 1558 Class: 6.1 Packing group: II EMS-No: F-A, S-A
Proper shipping name: ARSENIC
Marine pollutant:yes

IATA
UN number: 1558 Class: 6.1 Packing group: II
Proper shipping name: Arsenic

15. REGULATORY INFORMATION

SARA 302 Components
No chemicals in this material are subject to the reporting requirements of SARA Title III, Section 302.

SARA 313 Components
The following components are subject to reporting levels established by SARA Title III, Section 313:

	CAS-No.	Revision Date
Arsenic	7440-38-2	2007-07-01

SARA 311/312 Hazards
Acute Health Hazard, Chronic Health Hazard

Massachusetts Right To Know Components

	CAS-No.	Revision Date
Arsenic	7440-38-2	2007-07-01

Pennsylvania Right To Know Components

	CAS-No.	Revision Date
Arsenic	7440-38-2	2007-07-01

New Jersey Right To Know Components

	CAS-No.	Revision Date
Arsenic	7440-38-2	2007-07-01

California Prop. 65 Components

WARNING! This product contains a chemical known to the State of California to cause cancer.	CAS-No.	Revision Date
Arsenic	7440-38-2	2008-10-10

16. OTHER INFORMATION

Full text of H-Statements referred to under sections 2 and 3.

Acute Tox.	Acute toxicity
Aquatic Acute	Acute aquatic toxicity
Aquatic Chronic	Chronic aquatic toxicity
H302	Harmful if swallowed.
H331	Toxic if inhaled.
H400	Very toxic to aquatic life.
H410	Very toxic to aquatic life with long lasting effects.

HMIS Rating

Health hazard:	2
Chronic Health Hazard:	*
Flammability:	0
Physical Hazard	0

NFPA Rating

Health hazard:	2
Fire Hazard:	0
Reactivity Hazard:	0

Further information

Copyright 2016 Sigma-Aldrich Co. LLC. License granted to make unlimited paper copies for internal use only.
The above information is believed to be correct but does not purport to be all inclusive and shall be used only as a guide. The information in this document is based on the present state of our knowledge and is applicable to the product with regard to appropriate safety precautions. It does not represent any guarantee of the properties of the product. Sigma-Aldrich Corporation and its Affiliates shall not be held liable for any damage resulting from handling or from contact with the above product. See www.sigma-aldrich.com and/or the reverse side of invoice or packing slip for additional terms and conditions of sale.

Preparation Information

Sigma-Aldrich Corporation
Product Safety – Americas Region
1-800-521-8956

Version: 4.7 Revision Date: 05/23/2016 Print Date: 06/23/2016

SAFETY DATA SHEET

Version 5.6
Revision Date 06/02/2016
Print Date 07/20/2017

1. PRODUCT AND COMPANY IDENTIFICATION

1.1 Product identifiers

Product name : Benz[*a*]anthracene

Product Number : 48563
Brand : Supelco
Index-No. : 601-033-00-9

CAS-No. : 56-55-3

1.2 Relevant identified uses of the substance or mixture and uses advised against

Identified uses : Laboratory chemicals, Synthesis of substances

1.3 Details of the supplier of the safety data sheet

Company : Sigma-Aldrich
3050 Spruce Street
SAINT LOUIS MO 63103
USA

Telephone : +1 800-325-5832
Fax : +1 800-325-5052

1.4 Emergency telephone number

Emergency Phone # : +1-703-527-3887 (CHEMTREC)

2. HAZARDS IDENTIFICATION

2.1 Classification of the substance or mixture

GHS Classification in accordance with 29 CFR 1910 (OSHA HCS)
Carcinogenicity (Category 1B), H350
Acute aquatic toxicity (Category 1), H400
Chronic aquatic toxicity (Category 1), H410

For the full text of the H-Statements mentioned in this Section, see Section 16.

2.2 GHS Label elements, including precautionary statements

Pictogram

Signal word Danger

Hazard statement(s)
H350 May cause cancer.
H410 Very toxic to aquatic life with long lasting effects.

Precautionary statement(s)
P201 Obtain special instructions before use.
P202 Do not handle until all safety precautions have been read and understood.
P273 Avoid release to the environment.
P281 Use personal protective equipment as required.
P308 + P313 IF exposed or concerned: Get medical advice/ attention.
P391 Collect spillage.

P405	Store locked up.
P501	Dispose of contents/ container to an approved waste disposal plant.

2.3 Hazards not otherwise classified (HNOC) or not covered by GHS - none

3. COMPOSITION/INFORMATION ON INGREDIENTS

3.1 Substances

Synonyms	:	1,2-Benzanthracene Tetraphene
Formula	:	$C_{18}H_{12}$
Molecular weight	:	228.29 g/mol
CAS-No.	:	56-55-3
EC-No.	:	200-280-6
Index-No.	:	601-033-00-9

Hazardous components

Component	Classification	Concentration
Benz[a]anthracene		
	Carc. 1B; Aquatic Acute 1; Aquatic Chronic 1; H350, H410	<= 100 %

For the full text of the H-Statements mentioned in this Section, see Section 16.

4. FIRST AID MEASURES

4.1 Description of first aid measures

General advice
Consult a physician. Show this safety data sheet to the doctor in attendance.Move out of dangerous area.

If inhaled
If breathed in, move person into fresh air. If not breathing, give artificial respiration. Consult a physician.

In case of skin contact
Wash off with soap and plenty of water. Consult a physician.

In case of eye contact
Flush eyes with water as a precaution.

If swallowed
Never give anything by mouth to an unconscious person. Rinse mouth with water. Consult a physician.

4.2 Most important symptoms and effects, both acute and delayed
The most important known symptoms and effects are described in the labelling (see section 2.2) and/or in section 11

4.3 Indication of any immediate medical attention and special treatment needed
No data available

5. FIREFIGHTING MEASURES

5.1 Extinguishing media

Suitable extinguishing media
Use water spray, alcohol-resistant foam, dry chemical or carbon dioxide.

5.2 Special hazards arising from the substance or mixture
No data available

5.3 Advice for firefighters
Wear self-contained breathing apparatus for firefighting if necessary.

5.4 Further information
No data available

6. ACCIDENTAL RELEASE MEASURES

6.1 Personal precautions, protective equipment and emergency procedures

Use personal protective equipment. Avoid dust formation. Avoid breathing vapours, mist or gas. Ensure adequate ventilation. Evacuate personnel to safe areas. Avoid breathing dust.
For personal protection see section 8.

6.2 Environmental precautions

Prevent further leakage or spillage if safe to do so. Do not let product enter drains. Discharge into the environment must be avoided.

6.3 Methods and materials for containment and cleaning up

Pick up and arrange disposal without creating dust. Sweep up and shovel. Keep in suitable, closed containers for disposal.

6.4 Reference to other sections

For disposal see section 13.

7. HANDLING AND STORAGE

7.1 Precautions for safe handling

Avoid formation of dust and aerosols.Further processing of solid materials may result in the formation of combustible dusts. The potential for combustible dust formation should be taken into consideration before additional processing occurs.
Provide appropriate exhaust ventilation at places where dust is formed.
For precautions see section 2.2.

7.2 Conditions for safe storage, including any incompatibilities

Keep container tightly closed in a dry and well-ventilated place.
Storage class (TRGS 510): Non-combustible, acute toxic Cat.3 / toxic hazardous materials or hazardous materials causing chronic effects

7.3 Specific end use(s)

Apart from the uses mentioned in section 1.2 no other specific uses are stipulated

8. EXPOSURE CONTROLS/PERSONAL PROTECTION

8.1 Control parameters

Components with workplace control parameters
Contains no substances with occupational exposure limit values.

8.2 Exposure controls

Appropriate engineering controls
Handle in accordance with good industrial hygiene and safety practice. Wash hands before breaks and at the end of workday.

Personal protective equipment

Eye/face protection
Safety glasses with side-shields conforming to EN166 Use equipment for eye protection tested and approved under appropriate government standards such as NIOSH (US) or EN 166(EU).

Skin protection
Handle with gloves. Gloves must be inspected prior to use. Use proper glove removal technique (without touching glove's outer surface) to avoid skin contact with this product. Dispose of contaminated gloves after use in accordance with applicable laws and good laboratory practices. Wash and dry hands.

Full contact
Material: Nitrile rubber
Minimum layer thickness: 0.11 mm
Break through time: 480 min
Material tested:Dermatril® (KCL 740 / Aldrich Z677272, Size M)

Splash contact
Material: Nitrile rubber

Minimum layer thickness: 0.11 mm
Break through time: 480 min
Material tested:Dermatril® (KCL 740 / Aldrich Z677272, Size M)

data source: KCL GmbH, D-36124 Eichenzell, phone +49 (0)6659 87300, e-mail sales@kcl.de, test method: EN374
If used in solution, or mixed with other substances, and under conditions which differ from EN 374, contact the supplier of the CE approved gloves. This recommendation is advisory only and must be evaluated by an industrial hygienist and safety officer familiar with the specific situation of anticipated use by our customers. It should not be construed as offering an approval for any specific use scenario.

Body Protection
Impervious clothing, The type of protective equipment must be selected according to the concentration and amount of the dangerous substance at the specific workplace.

Respiratory protection
Where risk assessment shows air-purifying respirators are appropriate use a full-face particle respirator type N100 (US) or type P3 (EN 143) respirator cartridges as a backup to engineering controls. If the respirator is the sole means of protection, use a full-face supplied air respirator. Use respirators and components tested and approved under appropriate government standards such as NIOSH (US) or CEN (EU).

Control of environmental exposure
Prevent further leakage or spillage if safe to do so. Do not let product enter drains. Discharge into the environment must be avoided.

9. PHYSICAL AND CHEMICAL PROPERTIES

9.1 Information on basic physical and chemical properties

a)	Appearance	Form: solid
b)	Odour	No data available
c)	Odour Threshold	No data available
d)	pH	No data available
e)	Melting point/freezing point	Melting point/range: 157 - 159 °C (315 - 318 °F)
f)	Initial boiling point and boiling range	437.6 °C (819.7 °F)
g)	Flash point	No data available
h)	Evaporation rate	No data available
i)	Flammability (solid, gas)	No data available
j)	Upper/lower flammability or explosive limits	No data available
k)	Vapour pressure	No data available
l)	Vapour density	No data available
m)	Relative density	No data available
n)	Water solubility	No data available
o)	Partition coefficient: n-octanol/water	No data available
p)	Auto-ignition temperature	No data available
q)	Decomposition temperature	No data available
r)	Viscosity	No data available
s)	Explosive properties	No data available

t) Oxidizing properties No data available

9.2 Other safety information
No data available

10. STABILITY AND REACTIVITY

10.1 Reactivity
No data available

10.2 Chemical stability
Stable under recommended storage conditions.

10.3 Possibility of hazardous reactions
No data available

10.4 Conditions to avoid
No data available

10.5 Incompatible materials
Strong oxidizing agents

10.6 Hazardous decomposition products
Hazardous decomposition products formed under fire conditions. - Carbon oxides
Other decomposition products - No data available
In the event of fire: see section 5

11. TOXICOLOGICAL INFORMATION

11.1 Information on toxicological effects

Acute toxicity
No data available

Inhalation: No data available

Dermal: No data available

LD50 Intravenous - Rat - > 200 mg/kg

Skin corrosion/irritation
No data available

Serious eye damage/eye irritation
No data available

Respiratory or skin sensitisation
No data available

Germ cell mutagenicity
No data available

Carcinogenicity

This product is or contains a component that has been reported to be probably carcinogenic based on its IARC, OSHA, ACGIH, NTP, or EPA classification.

Possible human carcinogen

IARC:	2B - Group 2B: Possibly carcinogenic to humans (Benz[a]anthracene)
IARC:	2B - Group 2B: Possibly carcinogenic to humans (Benz[a]anthracene)
NTP:	Reasonably anticipated to be a human carcinogen (Benz[a]anthracene)
NTP:	Reasonably anticipated to be a human carcinogen (Benz[a]anthracene)
OSHA:	No component of this product present at levels greater than or equal to 0.1% is identified as a carcinogen or potential carcinogen by OSHA.

No component of this product present at levels greater than or equal to 0.1% is identified as a carcinogen or potential carcinogen by OSHA.

Reproductive toxicity
No data available

No data available

Specific target organ toxicity - single exposure
No data available

Specific target organ toxicity - repeated exposure
No data available

Aspiration hazard
No data available

Additional Information
RTECS: Not available

To the best of our knowledge, the chemical, physical, and toxicological properties have not been thoroughly investigated.

12. ECOLOGICAL INFORMATION

12.1 Toxicity
No data available

12.2 Persistence and degradability
No data available

12.3 Bioaccumulative potential
No data available

12.4 Mobility in soil
No data available

12.5 Results of PBT and vPvB assessment
PBT/vPvB assessment not available as chemical safety assessment not required/not conducted

12.6 Other adverse effects
An environmental hazard cannot be excluded in the event of unprofessional handling or disposal.
Very toxic to aquatic life with long lasting effects.

13. DISPOSAL CONSIDERATIONS

13.1 Waste treatment methods

Product
Offer surplus and non-recyclable solutions to a licensed disposal company. Contact a licensed professional waste disposal service to dispose of this material. Dissolve or mix the material with a combustible solvent and burn in a chemical incinerator equipped with an afterburner and scrubber.

Contaminated packaging
Dispose of as unused product.

14. TRANSPORT INFORMATION

DOT (US)
Not dangerous goods

IMDG
UN number: 3077 Class: 9 Packing group: III EMS-No: F-A, S-F
Proper shipping name: ENVIRONMENTALLY HAZARDOUS SUBSTANCE, SOLID, N.O.S. (Benz[a]anthracene)
Marine pollutant:yes

IATA
UN number: 3077 Class: 9 Packing group: III
Proper shipping name: Environmentally hazardous substance, solid, n.o.s. (Benz[a]anthracene)

Further information
EHS-Mark required (ADR 2.2.9.1.10, IMDG code 2.10.3) for single packagings and combination packagings containing inner packagings with Dangerous Goods > 5L for liquids or > 5kg for solids.

15. REGULATORY INFORMATION

SARA 302 Components
No chemicals in this material are subject to the reporting requirements of SARA Title III, Section 302.

SARA 313 Components
This material does not contain any chemical components with known CAS numbers that exceed the threshold (De Minimis) reporting levels established by SARA Title III, Section 313.

SARA 311/312 Hazards
Chronic Health Hazard

Massachusetts Right To Know Components

	CAS-No.	Revision Date
Benz[a]anthracene	56-55-3	1993-04-24

Pennsylvania Right To Know Components

	CAS-No.	Revision Date
Benz[a]anthracene	56-55-3	1993-04-24

New Jersey Right To Know Components

	CAS-No.	Revision Date
Benz[a]anthracene	56-55-3	1993-04-24

California Prop. 65 Components

WARNING! This product contains a chemical known to the State of California to cause cancer. Benz[a]anthracene	CAS-No. 56-55-3	Revision Date 2007-09-28
WARNING! This product contains a chemical known to the State of California to cause cancer. Benz[a]anthracene	CAS-No. 56-55-3	Revision Date 2007-09-28

16. OTHER INFORMATION

Full text of H-Statements referred to under sections 2 and 3.

Aquatic Acute	Acute aquatic toxicity
Aquatic Chronic	Chronic aquatic toxicity
Carc.	Carcinogenicity
H350	May cause cancer.
H400	Very toxic to aquatic life.
H410	Very toxic to aquatic life with long lasting effects.

HMIS Rating

Health hazard:	2
Chronic Health Hazard:	*
Flammability:	0
Physical Hazard	0

NFPA Rating

Health hazard:	2
Fire Hazard:	0
Reactivity Hazard:	0

Further information

Copyright 2016 Sigma-Aldrich Co. LLC. License granted to make unlimited paper copies for internal use only.
The above information is believed to be correct but does not purport to be all inclusive and shall be used only as a guide. The information in this document is based on the present state of our knowledge and is applicable to the product with regard to appropriate safety precautions. It does not represent any guarantee of the properties of the product. Sigma-Aldrich Corporation and its Affiliates shall not be held liable for any damage resulting from handling or from contact with the above product. See www.sigma-aldrich.com and/or the reverse side of invoice or packing slip for additional terms and conditions of sale.

Preparation Information

Sigma-Aldrich Corporation
Product Safety – Americas Region
1-800-521-8956

Version: 5.6 Revision Date: 06/02/2016 Print Date: 07/20/2017

SAFETY DATA SHEET

Revision Date 22-May-2017 **Revision Number** 2

1. Identification

Product Name **Benzo[a]pyrene, 98%**

Cat No. : **AC105600010; AC105601000**

Synonyms Benzo[def]chrysene.; 3,4-Benzopyrene; 3,4-Benzpyrene

Recommended Use Laboratory chemicals.
Uses advised against Not for food, drug, pesticide or biocidal product use

Details of the supplier of the safety data sheet

Company
Fisher Scientific
One Reagent Lane
Fair Lawn, NJ 07410
Tel: (201) 796-7100

Acros Organics
One Reagent Lane
Fair Lawn, NJ 07410

Emergency Telephone Number
For information **US** call: 001-800-ACROS-01 / **Europe** call: +32 14 57 52 11
Emergency Number **US:**001-201-796-7100 / **Europe:** +32 14 57 52 99
CHEMTREC Tel. No.**US:**001-800-424-9300 / **Europe:**001-703-527-3887

2. Hazard(s) identification

Classification
This chemical is considered hazardous by the 2012 OSHA Hazard Communication Standard (29 CFR 1910.1200)

Skin Sensitization	Category 1
Germ Cell Mutagenicity	Category 1A
Carcinogenicity	Category 1A
Reproductive Toxicity	Category 1A

Label Elements

Signal Word
Danger

Hazard Statements
May cause an allergic skin reaction
May cause genetic defects
May cause cancer
May damage fertility or the unborn child

Precautionary Statements
Prevention
Obtain special instructions before use
Do not handle until all safety precautions have been read and understood
Use personal protective equipment as required
Avoid breathing dust/fume/gas/mist/vapors/spray
Contaminated work clothing should not be allowed out of the workplace
Wear protective gloves
Response
IF exposed or concerned: Get medical attention/advice
Skin
IF ON SKIN: Wash with plenty of soap and water
If skin irritation or rash occurs: Get medical advice/attention
Wash contaminated clothing before reuse
Storage
Store locked up
Disposal
Dispose of contents/container to an approved waste disposal plant
Hazards not otherwise classified (HNOC)
Very toxic to aquatic life with long lasting effects
WARNING! This product contains a chemical known in the State of California to cause cancer.

3. Composition / information on ingredients

Component	CAS-No	Weight %
Benzo[a]pyrene	50-32-8	> 96

4. First-aid measures

Eye Contact Rinse immediately with plenty of water, also under the eyelids, for at least 15 minutes.

Skin Contact Wash off immediately with plenty of water for at least 15 minutes.

Inhalation Move to fresh air.

Ingestion Do not induce vomiting.

Most important symptoms/effects May cause allergic skin reaction. Symptoms of allergic reaction may include rash, itching, swelling, trouble breathing, tingling of the hands and feet, dizziness, lightheadedness, chest pain, muscle pain or flushing

Notes to Physician Treat symptomatically

5. Fire-fighting measures

Unsuitable Extinguishing Media No information available

Flash Point
Method - No information available

Autoignition Temperature No information available

Explosion Limits
Upper No data available
Lower No data available
Sensitivity to Mechanical Impact No information available
Sensitivity to Static Discharge No information available

Specific Hazards Arising from the Chemical
Keep product and empty container away from heat and sources of ignition.

Hazardous Combustion Products
None known
Protective Equipment and Precautions for Firefighters
As in any fire, wear self-contained breathing apparatus pressure-demand, MSHA/NIOSH (approved or equivalent) and full protective gear.

NFPA

Health	Flammability	Instability	Physical hazards
2	0	0	N/A

6. Accidental release measures

Personal Precautions Ensure adequate ventilation. Use personal protective equipment.
Environmental Precautions See Section 12 for additional ecological information. Avoid release to the environment. Collect spillage.

Methods for Containment and Clean Up No information available.

7. Handling and storage

Handling Ensure adequate ventilation.

Storage Keep containers tightly closed in a dry, cool and well-ventilated place.

8. Exposure controls / personal protection

Exposure Guidelines

Component	ACGIH TLV	OSHA PEL	NIOSH IDLH	Mexico OEL (TWA)
Benzo[a]pyrene		TWA: 0.2 mg/m³		

Legend

OSHA - Occupational Safety and Health Administration

Engineering Measures Ensure adequate ventilation, especially in confined areas.

Personal Protective Equipment

Eye/face Protection Wear appropriate protective eyeglasses or chemical safety goggles as described by OSHA's eye and face protection regulations in 29 CFR 1910.133 or European Standard EN166.

Skin and body protection Wear appropriate protective gloves and clothing to prevent skin exposure.

Respiratory Protection Follow the OSHA respirator regulations found in 29 CFR 1910.134 or European Standard EN 149. Use a NIOSH/MSHA or European Standard EN 149 approved respirator if exposure limits are exceeded or if irritation or other symptoms are experienced.

Hygiene Measures Handle in accordance with good industrial hygiene and safety practice.

9. Physical and chemical properties

Physical State	Powder Solid
Appearance	Dark yellow
Odor	aromatic
Odor Threshold	No information available
pH	
Melting Point/Range	175 179 °C
Boiling Point/Range	°C @ 760 mmHg

Flash Point	
Evaporation Rate	No information available
Flammability (solid,gas)	No information available
Flammability or explosive limits	
Upper	No data available
Lower	No data available
Vapor Pressure	No information available
Vapor Density	No information available
Specific Gravity	No information available
Solubility	Insoluble in water
Partition coefficient; n-octanol/water	No data available
Autoignition Temperature	No information available
Decomposition Temperature	No information available
Viscosity	No information available
Molecular Formula	C20H12
Molecular Weight	252.31

10. Stability and reactivity

Reactive Hazard None known, based on information available

Stability Stable under normal conditions.

Conditions to Avoid Incompatible products.

Incompatible Materials Strong oxidizing agents

Hazardous Decomposition Products None under normal use conditions

Hazardous Polymerization Hazardous polymerization does not occur.

Hazardous Reactions None under normal processing.

11. Toxicological information

Acute Toxicity

Component Information

Toxicologically Synergistic Products No information available

Delayed and immediate effects as well as chronic effects from short and long-term exposure

Irritation No information available

Sensitization No information available

Carcinogenicity The table below indicates whether each agency has listed any ingredient as a carcinogen.

Component	CAS-No	IARC	NTP	ACGIH	OSHA	Mexico
Benzo[a]pyrene	50-32-8	Group 1	Reasonably Anticipated	A2	X	Not listed

Mutagenic Effects No information available

Reproductive Effects No information available.

Developmental Effects No information available.

Teratogenicity No information available.

STOT - single exposure None known

STOT - repeated exposure None known

Aspiration hazard No information available

Symptoms / effects,both acute and delayed Symptoms of allergic reaction may include rash, itching, swelling, trouble breathing, tingling of the hands and feet, dizziness, lightheadedness, chest pain, muscle pain or flushing

Endocrine Disruptor Information No information available

Component	EU - Endocrine Disrupters Candidate List	EU - Endocrine Disruptors - Evaluated Substances	Japan - Endocrine Disruptor Information
Benzo[a]pyrene	Group III Chemical	Not applicable	Not applicable

Other Adverse Effects The toxicological properties have not been fully investigated.

12. Ecological information

Ecotoxicity

Do not empty into drains.

Persistence and Degradability No information available

Bioaccumulation/ Accumulation No information available.

Mobility No information available.

Component	log Pow
Benzo[a]pyrene	6.06

13. Disposal considerations

Waste Disposal Methods Chemical waste generators must determine whether a discarded chemical is classified as a hazardous waste. Chemical waste generators must also consult local, regional, and national hazardous waste regulations to ensure complete and accurate classification.

Component	RCRA - U Series Wastes	RCRA - P Series Wastes
Benzo[a]pyrene - 50-32-8	U022	-

14. Transport information

DOT

UN-No UN3077
Proper Shipping Name ENVIRONMENTALLY HAZARDOUS SUBSTANCE, SOLID, N.O.S.
Hazard Class 9
Packing Group III

TDG

UN-No UN3077
Proper Shipping Name ENVIRONMENTALLY HAZARDOUS SUBSTANCE, SOLID, N.O.S.
Hazard Class 9
Packing Group III

IATA

UN-No UN3077
Proper Shipping Name ENVIRONMENTALLY HAZARDOUS SUBSTANCE, SOLID, N.O.S.
Hazard Class 9
Packing Group III

IMDG/IMO

UN-No UN3077
Proper Shipping Name ENVIRONMENTALLY HAZARDOUS SUBSTANCE, SOLID, N.O.S.
Hazard Class 9
Packing Group III

15. Regulatory information

International Inventories

Component	TSCA	DSL	NDSL	EINECS	ELINCS	NLP	PICCS	ENCS	AICS	IECSC	KECL
Benzo[a]pyrene	X	X	-	200-028-5	-		X	-	-	X	X

Legend:
X - Listed
E - Indicates a substance that is the subject of a Section 5(e) Consent order under TSCA.
F - Indicates a substance that is the subject of a Section 5(f) Rule under TSCA.
N - Indicates a polymeric substance containing no free-radical initiator in its inventory name but is considered to cover the designated polymer made with any free-radical initiator regardless of the amount used.
P - Indicates a commenced PMN substance
R - Indicates a substance that is the subject of a Section 6 risk management rule under TSCA.
S - Indicates a substance that is identified in a proposed or final Significant New Use Rule
T - Indicates a substance that is the subject of a Section 4 test rule under TSCA.
XU - Indicates a substance exempt from reporting under the Inventory Update Rule, i.e. Partial Updating of the TSCA Inventory Data Base Production and Site Reports (40 CFR 710(B).
Y1 - Indicates an exempt polymer that has a number-average molecular weight of 1,000 or greater.
Y2 - Indicates an exempt polymer that is a polyester and is made only from reactants included in a specified list of low concern reactants that comprises one of the eligibility criteria for the exemption rule.

U.S. Federal Regulations

TSCA 12(b) Not applicable

SARA 313

Component	CAS-No	Weight %	SARA 313 - Threshold Values %
Benzo[a]pyrene	50-32-8	> 96	0.1

SARA 311/312 Hazard Categories

Acute Health Hazard	Yes
Chronic Health Hazard	Yes
Fire Hazard	No
Sudden Release of Pressure Hazard	No
Reactive Hazard	No

CWA (Clean Water Act)

Component	CWA - Hazardous Substances	CWA - Reportable Quantities	CWA - Toxic Pollutants	CWA - Priority Pollutants
Benzo[a]pyrene	-	-	X	X

Clean Air Act Not applicable

OSHA Occupational Safety and Health Administration
Not applicable

CERCLA
Not applicable

Component	Hazardous Substances RQs	CERCLA EHS RQs
Benzo[a]pyrene	1 lb	-

California Proposition 65 This product does not contain any Proposition 65 chemicals

Component	CAS-No	California Prop. 65	Prop 65 NSRL	Category
Benzo[a]pyrene	50-32-8	Carcinogen	0.06 µg/day	Carcinogen

U.S. State Right-to-Know Regulations

Component	Massachusetts	New Jersey	Pennsylvania	Illinois	Rhode Island
Benzo[a]pyrene	X	X	X	X	X

U.S. Department of Transportation

Reportable Quantity (RQ): N

DOT Marine Pollutant	N
DOT Severe Marine Pollutant	N

U.S. Department of Homeland Security
This product does not contain any DHS chemicals.

Other International Regulations

Mexico - Grade No information available

16. Other information

Prepared By
Regulatory Affairs
Thermo Fisher Scientific
Email: EMSDS.RA@thermofisher.com

Revision Date 22-May-2017
Print Date 22-May-2017
Revision Summary This document has been updated to comply with the US OSHA HazCom 2012 Standard replacing the current legislation under 29 CFR 1910.1200 to align with the Globally Harmonized System of Classification and Labeling of Chemicals (GHS).

Disclaimer
The information provided in this Safety Data Sheet is correct to the best of our knowledge, information and belief at the date of its publication. The information given is designed only as a guidance for safe handling, use, processing, storage, transportation, disposal and release and is not to be considered a warranty or quality specification. The information relates only to the specific material designated and may not be valid for such material used in combination with any other materials or in any process, unless specified in the text

End of SDS

SAFETY DATA SHEET

Revision Date 10-Feb-2015 **Revision Number** 1

1. Identification

Product Name **Barium**

Cat No. : **AC317860000; AC317860250; AC317861000; AC317865000**

Synonyms None Known.

Recommended Use Laboratory chemicals.

Uses advised against No Information available

Details of the supplier of the safety data sheet

Company
Fisher Scientific
One Reagent Lane
Fair Lawn, NJ 07410
Tel: (201) 796-7100

Entity / Business Name
Acros Organics
One Reagent Lane
Fair Lawn, NJ 07410

Emergency Telephone Number
For information **US** call: 001-800-ACROS-01 / **Europe** call: +32 14 57 52 11
Emergency Number **US:**001-201-796-7100 / **Europe:** +32 14 57 52 99
CHEMTREC Tel. No.**US:**001-800-424-9300 / **Europe:**001-703-527-3887

2. Hazard(s) identification

Classification
This chemical is considered hazardous by the 2012 OSHA Hazard Communication Standard (29 CFR 1910.1200)

Flammable solids	Category 2
Acute oral toxicity	Category 3
Skin Corrosion/irritation	Category 2
Serious Eye Damage/Eye Irritation	Category 2
Specific target organ toxicity (single exposure)	Category 3
Target Organs - Respiratory system.	

Label Elements

Signal Word
Danger

Hazard Statements
Flammable solid
Toxic if swallowed
Causes skin irritation
Causes serious eye irritation
May cause respiratory irritation

Precautionary Statements
Prevention
Wash face, hands and any exposed skin thoroughly after handling
Do not eat, drink or smoke when using this product
Wear protective gloves/protective clothing/eye protection/face protection
Avoid breathing dust/fume/gas/mist/vapors/spray
Use only outdoors or in a well-ventilated area
Keep away from heat/sparks/open flames/hot surfaces. - No smoking
Keep container tightly closed
Ground/bond container and receiving equipment
Use explosion-proof electrical/ventilating/lighting/equipment
Use only non-sparking tools
Take precautionary measures against static discharge
Response
Call a POISON CENTER or doctor/physician if you feel unwell
Inhalation
IF INHALED: Remove victim to fresh air and keep at rest in a position comfortable for breathing
Skin
IF ON SKIN: Wash with plenty of soap and water
If skin irritation occurs: Get medical advice/attention
Take off contaminated clothing and wash before reuse
Eyes
IF IN EYES: Rinse cautiously with water for several minutes. Remove contact lenses, if present and easy to do. Continue rinsing
If eye irritation persists: Get medical advice/attention
Ingestion
IF SWALLOWED: Immediately call a POISON CENTER or doctor/physician
Rinse mouth
Fire
Explosion risk in case of fire
Fight fire with normal precautions from a reasonable distance
Evacuate area
Storage
Store locked up
Store in a closed container
Store in a well-ventilated place. Keep cool
Disposal
Dispose of contents/container to an approved waste disposal plant
Hazards not otherwise classified (HNOC)
None identified

3. Composition / information on ingredients

Component	CAS-No	Weight %
Barium	7440-39-3	99.9

4. First-aid measures

Eye Contact Rinse immediately with plenty of water, also under the eyelids, for at least 15 minutes. Obtain medical attention.

Skin Contact Wash off immediately with plenty of water for at least 15 minutes. Obtain medical attention.

Inhalation Move to fresh air. If breathing is difficult, give oxygen. Obtain medical attention.

Ingestion Do not induce vomiting. Call a physician or Poison Control Center immediately.

Most important symptoms/effects No information available.
Notes to Physician Treat symptomatically

5. Fire-fighting measures

Suitable Extinguishing Media Dry chemical.

Unsuitable Extinguishing Media No information available

Flash Point No information available
Method - No information available

Autoignition Temperature No information available
Explosion Limits
Upper No data available
Lower No data available
Sensitivity to Mechanical Impact No information available
Sensitivity to Static Discharge No information available

Specific Hazards Arising from the Chemical
Contact with water liberates toxic gas. Water reactive. Combustible material. Produce flammable gases on contact with water.

Hazardous Combustion Products
None known
Protective Equipment and Precautions for Firefighters
As in any fire, wear self-contained breathing apparatus pressure-demand, MSHA/NIOSH (approved or equivalent) and full protective gear.

NFPA

Health	Flammability	Instability	Physical hazards
3	3	0	W

6. Accidental release measures

Personal Precautions Ensure adequate ventilation. Use personal protective equipment.
Environmental Precautions See Section 12 for additional ecological information.

Methods for Containment and Clean Up Sweep up or vacuum up spillage and collect in suitable container for disposal.

7. Handling and storage

Handling Avoid contact with skin and eyes. Do not breathe dust. Do not breathe vapors or spray mist. Handle under inert gas, protect from moisture. Wear personal protective equipment.

Storage Keep in a dry, cool and well-ventilated place. Keep container tightly closed. Protect from moisture. Never allow product to get in contact with water during storage. Store under an inert atmosphere.

8. Exposure controls / personal protection

Exposure Guidelines

Component	ACGIH TLV	OSHA PEL	NIOSH IDLH
Barium	TWA: 0.5 mg/m^3	(Vacated) TWA: 0.5 mg/m^3	

Component	Quebec	Mexico OEL (TWA)	Ontario TWAEV
Barium			TWA: 0.5 mg/m³

Legend

ACGIH - American Conference of Governmental Industrial Hygienists
OSHA - Occupational Safety and Health Administration

Engineering Measures Use explosion-proof electrical/ventilating/lighting/equipment. Ensure that eyewash stations and safety showers are close to the workstation location. Ensure adequate ventilation, especially in confined areas.

Personal Protective Equipment

Eye/face Protection Wear appropriate protective eyeglasses or chemical safety goggles as described by OSHA's eye and face protection regulations in 29 CFR 1910.133 or European Standard EN166.

Skin and body protection Wear appropriate protective gloves and clothing to prevent skin exposure.

Respiratory Protection Follow the OSHA respirator regulations found in 29 CFR 1910.134 or European Standard EN 149. Use a NIOSH/MSHA or European Standard EN 149 approved respirator if exposure limits are exceeded or if irritation or other symptoms are experienced.

Hygiene Measures Handle in accordance with good industrial hygiene and safety practice.

9. Physical and chemical properties

Physical State	Solid
Appearance	Grey
Odor	Odorless
Odor Threshold	No information available
pH	No information available
Melting Point/Range	725 °C / 1337 °F
Boiling Point/Range	1640 °C / 2984 °F
Flash Point	No information available
Evaporation Rate	No information available
Flammability (solid,gas)	No information available
Flammability or explosive limits	
Upper	No data available
Lower	No data available
Vapor Pressure	10 mmHg @ 1094 °C
Vapor Density	No information available
Relative Density	3.51 @ 20 °C
Solubility	No information available
Partition coefficient; n-octanol/water	No data available
Autoignition Temperature	No information available
Decomposition Temperature	No information available
Viscosity	No information available
Molecular Formula	Ba
Molecular Weight	137.34

10. Stability and reactivity

Reactive Hazard Yes

Stability Moisture sensitive. Air sensitive.

Conditions to Avoid Exposure to air. Incompatible products. Exposure to moisture.

Incompatible Materials Acids, Water, Alcohols, Halogens

Hazardous Decomposition Products None under normal use conditions

Hazardous Polymerization Hazardous polymerization does not occur.

Hazardous Reactions None under normal processing.

11. Toxicological information

Acute Toxicity

Product Information
Oral LD50 Category 3. ATE = 50 - 300 mg/kg.
Component Information

Component	LD50 Oral	LD50 Dermal	LC50 Inhalation
Barium	132 mg/kg (Rat)	Not listed	Not listed

Toxicologically Synergistic Products No information available

Delayed and immediate effects as well as chronic effects from short and long-term exposure

Irritation Irritating to eyes, respiratory system and skin

Sensitization No information available

Carcinogenicity The table below indicates whether each agency has listed any ingredient as a carcinogen.

Component	CAS-No	IARC	NTP	ACGIH	OSHA	Mexico
Barium	7440-39-3	Not listed	Not listed	Not listed	Not listed	Not listed

Mutagenic Effects No information available

Reproductive Effects No information available.

Developmental Effects No information available.

Teratogenicity No information available.

STOT - single exposure Respiratory system
STOT - repeated exposure None known

Aspiration hazard No information available

Symptoms / effects,both acute and delayed No information available
Endocrine Disruptor Information No information available

Other Adverse Effects The toxicological properties have not been fully investigated. See actual entry in RTECS for complete information.

12. Ecological information

Ecotoxicity
Do not empty into drains.

Persistence and Degradability No information available
Bioaccumulation/ Accumulation No information available.

Mobility No information available.

13. Disposal considerations

Waste Disposal Methods Chemical waste generators must determine whether a discarded chemical is classified as a hazardous waste. Chemical waste generators must also consult local, regional, and national hazardous waste regulations to ensure complete and accurate classification.

14. Transport information

DOT

UN-No	UN1400
Proper Shipping Name	BARIUM
Hazard Class	4.3
Packing Group	II

TDG

UN-No	UN1400
Proper Shipping Name	BARIUM
Hazard Class	4.3
Packing Group	II

IATA

UN-No	UN1400
Proper Shipping Name	Barium
Hazard Class	4.3
Packing Group	II

IMDG/IMO

UN-No	UN1400
Proper Shipping Name	Barium
Hazard Class	4.3
Packing Group	II

15. Regulatory information

International Inventories

Component	TSCA	DSL	NDSL	EINECS	ELINCS	NLP	PICCS	ENCS	AICS	IECSC	KECL
Barium	X	X	-	231-149-1	-		X	-	X	X	X

Legend:
X - Listed
E - Indicates a substance that is the subject of a Section 5(e) Consent order under TSCA.
F - Indicates a substance that is the subject of a Section 5(f) Rule under TSCA.
N - Indicates a polymeric substance containing no free-radical initiator in its inventory name but is considered to cover the designated polymer made with any free-radical initiator regardless of the amount used.
P - Indicates a commenced PMN substance
R - Indicates a substance that is the subject of a Section 6 risk management rule under TSCA.
S - Indicates a substance that is identified in a proposed or final Significant New Use Rule
T - Indicates a substance that is the subject of a Section 4 test rule under TSCA.
XU - Indicates a substance exempt from reporting under the Inventory Update Rule, i.e. Partial Updating of the TSCA Inventory Data Base Production and Site Reports (40 CFR 710(B).
Y1 - Indicates an exempt polymer that has a number-average molecular weight of 1,000 or greater.
Y2 - Indicates an exempt polymer that is a polyester and is made only from reactants included in a specified list of low concern reactants that comprises one of the eligibility criteria for the exemption rule.

U.S. Federal Regulations

TSCA 12(b) Not applicable

SARA 313

Component	CAS-No	Weight %	SARA 313 - Threshold Values %
Barium	7440-39-3	99.9	1.0

SARA 311/312 Hazardous Categorization

Acute Health Hazard	Yes
Chronic Health Hazard	No
Fire Hazard	Yes
Sudden Release of Pressure Hazard	No
Reactive Hazard	Yes

Clean Water Act Not applicable

Clean Air Act Not applicable

OSHA Occupational Safety and Health Administration
Not applicable

CERCLA
Not applicable

Component	Hazardous Substances RQs	CERCLA EHS RQs
Barium	1000 lb	-

California Proposition 65 This product does not contain any Proposition 65 chemicals

State Right-to-Know

Component	Massachusetts	New Jersey	Pennsylvania	Illinois	Rhode Island
Barium	X	X	X	-	X

U.S. Department of Transportation

Reportable Quantity (RQ): N
DOT Marine Pollutant N
DOT Severe Marine Pollutant N

U.S. Department of Homeland Security
This product does not contain any DHS chemicals.

Other International Regulations

Mexico - Grade No information available

Canada
This product has been classified in accordance with the hazard criteria of the Controlled Products Regulations (CPR) and the MSDS contains all the information required by the CPR

WHMIS Hazard Class
B4 Flammable solid
B6 Reactive flammable material
D2B Toxic materials
D1A Very toxic materials

16. Other information

Prepared By
Regulatory Affairs
Thermo Fisher Scientific
Email: EMSDS.RA@thermofisher.com

Revision Date 10-Feb-2015
Print Date 10-Feb-2015
Revision Summary This document has been updated to comply with the US OSHA HazCom 2012 Standard replacing the current legislation under 29 CFR 1910.1200 to align with the Globally Harmonized System of Classification and Labeling of Chemicals (GHS)

Disclaimer
The information provided on this Safety Data Sheet is correct to the best of our knowledge, information and belief at the date of its publication. The information given is designed only as a guide for safe handling, use, processing, storage,

transportation, disposal and release and is not to be considered as a warranty or quality specification. The information relates only to the specific material designated and may not be valid for such material used in combination with any other material or in any process, unless specified in the text.

End of SDS

Safety Data Sheet

Revision Date: 12/08/16
www.restek.com

1. IDENTIFICATION

Catalog Number / Product Name:	**31272 / Benzo(b)fluoranthene Standard**
Company:	Restek Corporation
Address:	110 Benner Circle Bellefonte, Pa. 16823
Phone#:	814-353-1300
Fax#:	814-353-1309
Emergency#:	800-424-9300 (CHEMTREC) 703-527-3887 (Outside the US)
Email:	www.restek.com
Revision Number:	9
Intended use:	For Laboratory use only

2. HAZARD(S)IDENTIFICATION

Emergency Overview:

GHS Hazard Symbols:

GHS Classification:	Flammable Liquid Category 2 Serious Eye Damage/Eye Irritation Category 2 Specific Target Organ Systemic Toxicity (STOT) - Single Exposure Category 3
GHS Signal Word:	Danger
GHS Hazard:	Highly flammable liquid and vapour. Causes serious eye irritation. May cause drowsiness or dizziness.
GHS Precautions:	
Safety Precautions:	Keep away from heat/sparks/open flames/hot surfaces. – No smoking. Ground/bond container and receiving equipment. Use explosion-proof electrical/ventilation and lighting equipment. Use only non-sparking tools. Take precautionary measures against static discharge. Avoid breathing dust/fume/gas/mist/vapours/spray. Wash hands and skin thoroughly after handling. Use only outdoors or in a well-ventilated area. Wear protective gloves/protective clothing/eye protection/face protection.
First Aid Measures:	IF ON SKIN (or hair): Remove/Take off immediately all contaminated clothing. Rinse skin with water/shower. IF INHALED: Remove victim to fresh air and keep at rest in a position comfortable for breathing. IF IN EYES: Rinse cautiously with water for several minutes. Remove contact lenses, if present and easy to do. Continue rinsing. Call a POISON CENTER or doctor/physician if you feel unwell. If eye irritation persists: Get medical advice/attention. In case of fire: Use extinguishing media in section 5 for extinction.
Storage:	Store in a well-ventilated place. Keep container tightly closed. Store in a well-ventilated place. Keep cool. Store locked up.
Disposal:	Dispose of contents/container according to section 13 of the SDS.

Single Exposure Target Organs: No data available.

Repeated Exposure Target Organs: No data available.

3. COMPOSITION / INFORMATION ON INGREDIENT

Chemical Name	CAS #	EINEC #	% Composition
Acetone	67-64-1	200-662-2	99.900000
benzo (b) fluoranthene	205-99-2	205-911-9	0.100000

4. FIRST-AID MEASURES

Inhalation: Remove to fresh air. If breathing is difficult, have a trained individual administer oxygen. If not breathing, give artificial respiration and have a trained individual administer oxygen. Get medical attention immediately

Eyes: Flush eyes with plenty of water for at least 20 minutes retracting eyelids often. Tilt the head to prevent chemical from transferring to the uncontaminated eye. Get immediate medical attention.

Skin Contact: Wash with soap and water. Remove contaminated clothing and launder. Get medical attention if irritation develops or persists.

Ingestion: Do not induce vomiting and seek medical attention immediately. Drink two glasses of water or milk to dilute. Provide medical care provider with this SDS.

5. FIRE- FIGHTING MEASURES

Extinguishing Media: Use alcohol resistant foam, carbon dioxide, or dry chemical extinguishing agents. Water spray or fog may also be effective for extinguishing if swept across the base of the fire. Water can also be used to absorb heat and keep exposed material from being damaged by fire. Flammable component(s) of this material may be lighter than water and burn while floating on the surface.

Fire and/or Explosion Hazards: Vapors may be ignited by heat, sparks, flames or other sources of ignition at or above the low flash point giving rise to a Class B fire. Vapors are heavier than air and may travel to a source of ignition and flash back

Fire Fighting Methods and Protection: Do not enter fire area without proper protection including self-contained toxic breathing apparatus and full protective equipment. Fight fire from a safe distance and a protected location due to the potential of hazardous vapors and decomposition products. Flammable component(s) of this material may be lighter than water and burn while floating on the surface. Use water spray/fog for cooling.

Hazardous Combustion Products: Carbon dioxide, Carbon monoxide

6. ACCIDENTAL RELEASE MEASURES

Personal Precautions and Equipment: Exposure to the spilled material may be irritating or harmful. Follow personal protective equipment recommendations found in Section 8 of this SDS. Additional precautions may be necessary based on special circumstances created by the spill including; the material spilled, the quantity of the spill, the area in which the spill occurred. Also consider the expertise of employees in the area responding to the spill.

Methods for Clean-up: Prevent the spread of any spill to minimize harm to human health and the environment if safe to do so. Wear complete and proper personal protective equipment following the recommendation of Section 8 at a minimum. Dike with suitable absorbent material like granulated clay. Gather and store in a sealed container pending a waste disposal evaluation.

7. HANDLING AND STORAGE

Handling Technical Measures and Precautions: Harmful or irritating material. Avoid contacting and avoid breathing the material. Use only in a well ventilated area. Use spark-proof tools and explosion-proof equipment

Storage Technical Measures and Conditions: Store in a cool dry ventilated location. Isolate from

incompatible materials and conditions. Keep container(s) closed. Keep away from sources of ignition

8. EXPOSURE CONTROLS / PERSONAL PROTECTION

United States:

Chemical Name	CAS No.	IDLH	ACGIH STEL	ACGIH TLV-TWA	OSHA Exposure Limit
Acetone	67-64-1	2500 ppm IDLH (10% LEL)	500 ppm STEL 750 ppm STEL; 1782 mg/m3 STEL	250 ppm TWA 500 ppm TWA; 1188 mg/m3 TWA	1000 ppm TWA; 2400 mg/m3 TWA
benzo (b) fluoranthene	205-99-2	ND		No TLV	No data available.

Personal Protection:

Engineering Measures: Local exhaust ventilation is recommended when generating excessive levels of vapors from handling or thermal processing.

Respiratory Protection: No respiratory protection required under normal conditions of use. Provide general room exhaust ventilation if symptoms of overexposure occur as explained Section 3. A respirator is not normally required.

Eye Protection: Wear chemically resistant safety glasses with side shields when handling this product. Do not wear contact lenses.

Skin Protection: Wear protective gloves. Inspect gloves for chemical break-through and replace at regular intervals. Clean protective equipment regularly. Wash hands and other exposed areas with mild soap and water before eating, drinking, and when leaving work

Medical Conditions Aggravated By Exposure: Respiratory disease including asthma and bronchitis

9. PHYSICAL AND CHEMICAL PROPERTIES

Appearance, color: Depends upon product selection
Odor: Strong
Physical State: No data available.
pH: No data available.
Vapor Pressure: No data available.
Vapor Density: 2.0 (air = 1)
Boiling Point: No data available.
Melting Point: -95.4 °C Melting Point
Flash Point: 39
Flammability: Highly Flammable
Upper Flammable/Explosive Limit, % in air: No data available.
Lower Flammable/Explosive Limit, % in air: No data available.
Autoignition Temperature: 465 deg C
Decomposition Temperature: No data available.
Specific Gravity: 0.7845 g/cm3 at 25 °C
Evaporation Rate: No data available.
Odor Threshold: ND
Solubility: Complete; 100%
Partition Coefficient: n-octanol in water: No data available.
VOC % by weight: 0
Molecular Weight: 58.08

10. STABILITY AND REACTIVITY

Stability: Stable under normal conditions.
Conditions to Avoid: No data available.
Materials to Avoid / Chemical Incompatiability: Strong oxidizing agents Strong acids
Hazardous Decomposition Products: Carbon dioxide Carbon monoxide

11. TOXICOLOGICAL INFORMATION

Routes of Entry: Inhalation, Skin Contact, Eye Contact, Ingestion
Target Organs Potentially Affected By Exposure: Eyes, Central nervous system stimulation, Respiratory Tract, Skin
Chemical Interactions That Change Toxicity: None Known

Immediate (Acute) Health Effects by Route of Exposure:

Inhalation Irritation:	Can cause minor respiratory irritation, dizziness, weakness, fatigue, nausea, and headache.
Skin Contact:	Can cause minor skin irritation, defatting, and dermatitis.
Eye Contact:	Can cause minor irritation, tearing and reddening.
Ingestion Irritation:	May be harmful if swallowed.
Ingestion Toxicity:	Harmful if swallowed. May cause systemic poisoning.

Long-Term (Chronic) Health Effects:

Carcinogenicity:	Contains a probable or known human carcinogen.
Reproductive and Developmental Toxicity:	No data available to indicate product or any components present at greater than 0.1% may cause birth defects.
Inhalation:	Upon prolonged and/or repeated exposure, can cause minor respiratory irritation, dizziness, weakness, fatigue, nausea, and headache.
Skin Contact:	Upon prolonged or repeated contact, can cause minor skin irritation, defatting, and dermatitis.

Component Toxicological Data:
NIOSH:

Chemical Name	**CAS No.**	**LD50/LC50**
Acetone	67-64-1	Dermal LD50 Rabbit >15700 mg/kg; Oral LD50 Rat 5800 mg/kg; Inhalation LC50 Rat 50100 mg/m3 8 h

Component Carcinogenic Data:
OSHA:

Chemical Name	**CAS No.**	
Benzo(b)fluoranthene	205-99-2	Present

ACGIH:

Chemical Name	**CAS No.**	
Acetone	67-64-1	A4 - Not Classifiable as a Human Carcinogen
Benzo[b]fluoranthene	205-99-2	A2 - Suspected Human Carcinogen

NIOSH:

Chemical Name	**CAS No.**
No data available.	

NTP:

Chemical Name	**CAS No.**
No data available.	

IARC:

Chemical Name	**CAS No.**	**Group No.**
No data.		Group 1
No data.		Group 2A
Benzo(b)fluoranthene	205-99-2	Group 2B

12. ECOLOGICAL INFORMATION

Overview:	This material is not expected to be harmful to the ecology.
Mobility:	No data
Persistence:	No data
Bioaccumulation:	No data
Degradability:	No data
Ecological Toxicity Data:	No data available.

13. DISPOSAL CONSIDERATIONS

Waste Description of Spent Product:	Spent or discarded material is a hazardous waste.
Disposal Methods:	Dispose of by incineration following Federal, State, Local, or Provincial regulations.
Waste Disposal of Packaging:	Comply with all Local, State, Federal, and Provincial Environmental Regulations.

14. TRANSPORTATION INFORMATION

United States:
DOT Proper Shipping Name: Acetone

UN Number: UN1090
Hazard Class: 3
Packing Group: II

International:
IATA Proper Shipping Name: Acetone
UN Number: UN1090
Hazard Class: 3
Packing Group: II

Marine Pollutant: No

Chemical Name	CAS#	Marine Pollutant	Severe Marine Pollutant
No data available.			

15. REGULATORY INFORMATION

United States:

Chemical Name	CAS#	CERCLA	SARA 313	SARA EHS 313	TSCA
Acetone	67-64-1	X	-	-	X
benzo (b) fluoranthene	205-99-2	X	X	-	-

The following chemicals are listed on CA Prop 65:

Chemical Name	CAS #	Regulation
Benzo[b]fluoranthene	205-99-2	Prop 65 Cancer

State Right To Know Listing:

Chemical Name	CAS#	New Jersey	Massachusetts	Pennsylvania	California
Acetone	67-64-1	X	X	X	X
benzo (b) fluoranthene	205-99-2	X	X	X	X

16. OTHER INFORMATION

Prior Version Date: 03/23/15
Other Information: Any changes to the SDS compared to previous versions are marked by a vertical line in front of the concerned paragraph.
References: No data available.
Disclaimer: Restek Corporation provides the descriptions, data and information contained herein in good faith but makes no representation as to its comprehensiveness or accuracy. It is provided for your guidance only. Because many factors may affect processing or application/use, Restek Corporation recommends you perform an assessment to determine the suitability of a product for your particular purpose prior to use. No warranties of any kind, either expressed or implied, including fitness for a particular purpose, are made regarding prodcuts described, data or information set forth. In no case shall the descriptions, information, or data provided be considered a part of our terms and conditions of sale. Further, the descriptions, data and information furnished hereunder are given gratis. No obligation or liability for the description, data and information given are assumed. All such being given and accepted at your risk.

1 Identification

Product identifier

Product name: Benzene

Stock number: L14012
CAS Number:
71-43-2
EC number:
200-753-7
Index number:
601-020-00-8
Relevant identified uses of the substance or mixture and uses advised against.
Identified use: SU24 Scientific research and development

Details of the supplier of the safety data sheet
Manufacturer/Supplier:
Alfa Aesar
Thermo Fisher Scientific Chemicals, Inc.
30 Bond Street
Ward Hill, MA 01835-8099
Tel: 800-343-0660
Fax: 800-322-4757
Email: tech@alfa.com
www.alfa.com
Information Department: Health, Safety and Environmental Department
Emergency telephone number:
During normal business hours (Monday-Friday, 8am-7pm EST), call (800) 343-0660. After normal business hours, call Carechem 24 at (866) 928-0789.

2 Hazard(s) identification

Classification of the substance or mixture in accordance with 29 CFR 1910 (OSHA HCS)

GHS02 Flame

Flam. Liq. 2 H225 Highly flammable liquid and vapor.

GHS08 Health hazard

Muta. 1B H340 May cause genetic defects.
Carc. 1A H350 May cause cancer.
STOT RE 1 H372 Causes damage to the lung, the kidneys, the liver, the spleen, the blood, the brain and the endocrine system through prolonged or repeated exposure. Route of exposure: Oral, Inhalative, Dermal.
Asp. Tox. 1 H304 May be fatal if swallowed and enters airways.

GHS07

Skin Irrit. 2 H315 Causes skin irritation.
Eye Irrit. 2 H319 Causes serious eye irritation.
Hazards not otherwise classified No information known.

Label elements
GHS label elements The product is classified and labeled in accordance with 29 CFR 1910 (OSHA HCS)
Hazard pictograms

GHS02 GHS07 GHS08

Signal word Danger
Hazard statements
H225 Highly flammable liquid and vapor.
H315 Causes skin irritation.
H319 Causes serious eye irritation.
H340 May cause genetic defects.
H350 May cause cancer.
H372 Causes damage to the lung, the kidneys, the liver, the spleen, the blood, the brain and the endocrine system through prolonged or repeated exposure. Route of exposure: Oral, Inhalative, Dermal.
H304 May be fatal if swallowed and enters airways.
Precautionary statements
P210 Keep away from heat/sparks/open flames/hot surfaces. No smoking.
P301+P310 IF SWALLOWED: Immediately call a POISON CENTER/ doctor/…
P303+P361+P353 If on skin (or hair): Take off immediately all contaminated clothing. Rinse skin with water/shower.
P305+P351+P338 IF IN EYES: Rinse cautiously with water for several minutes. Remove contact lenses, if present and easy to do. Continue rinsing.
P405 Store locked up.
P501 Dispose of contents/container in accordance with local/regional/national/international regulations.
WHMIS classification
B2 - Flammable liquid
D2A - Very toxic material causing other toxic effects

Classification system
HMIS ratings (scale 0-4)
(Hazardous Materials Identification System)

Health (acute effects) = 2
Flammability = 3
Physical Hazard = 1

(Contd. on page 2)

Product name: Benzene

(Contd. of page 1)

Other hazards
Results of PBT and vPvB assessment
PBT: Not applicable.
vPvB: Not applicable.

3 Composition/information on ingredients

Chemical characterization: Substances
CAS# Description:
71-43-2 Benzene
Identification number(s):
EC number: 200-753-7
Index number: 601-020-00-8

4 First-aid measures

Description of first aid measures
After inhalation
Supply fresh air. If required, provide artificial respiration. Keep patient warm.
Seek immediate medical advice.
After skin contact
Immediately wash with water and soap and rinse thoroughly.
Seek immediate medical advice.
After eye contact Rinse opened eye for several minutes under running water. Then consult a doctor.
After swallowing Seek medical treatment.
Information for doctor
Most important symptoms and effects, both acute and delayed No further relevant information available.
Indication of any immediate medical attention and special treatment needed No further relevant information available.

5 Fire-fighting measures

Extinguishing media
Suitable extinguishing agents Carbon dioxide, extinguishing powder or water spray. Fight larger fires with water spray or alcohol resistant foam.
Special hazards arising from the substance or mixture
If this product is involved in a fire, the following can be released:
Carbon monoxide and carbon dioxide
Advice for firefighters
Protective equipment:
Wear self-contained respirator.
Wear fully protective impervious suit.

6 Accidental release measures

Personal precautions, protective equipment and emergency procedures
Wear protective equipment. Keep unprotected persons away.
Ensure adequate ventilation
Keep away from ignition sources
Environmental precautions: Do not allow product to reach sewage system or any water course.
Methods and material for containment and cleaning up:
Absorb with liquid-binding material (sand, diatomite, acid binders, universal binders, sawdust).
Dispose of contaminated material as waste according to section 13.
Ensure adequate ventilation.
Prevention of secondary hazards: Keep away from ignition sources.
Reference to other sections
See Section 7 for information on safe handling
See Section 8 for information on personal protection equipment.
See Section 13 for disposal information.

7 Handling and storage

Handling
Precautions for safe handling
Keep container tightly sealed.
Store in cool, dry place in tightly closed containers.
Ensure good ventilation at the workplace.
Open and handle container with care.
Information about protection against explosions and fires:
Protect against electrostatic charges.
Fumes can combine with air to form an explosive mixture.
Keep ignition sources away.

Conditions for safe storage, including any incompatibilities
Storage
Requirements to be met by storerooms and receptacles: Store in a cool location.
Information about storage in one common storage facility:
Do not store together with acids.
Store away from strong bases.
Store away from oxidizing agents.
Store away from halogens.
Further information about storage conditions:
Keep container tightly sealed.
Store in cool, dry conditions in well sealed containers.
Specific end use(s) No further relevant information available.

8 Exposure controls/personal protection

Additional information about design of technical systems:
Properly operating chemical fume hood designed for hazardous chemicals and having an average face velocity of at least 100 feet per minute.

(Contd. on page 3)

Product name: Benzene

(Contd. of page 2)

Control parameters

Components with limit values that require monitoring at the workplace:

71-43-2 Benzene (100.0%)

PEL (USA)	Short-term value: 15* mg/m³, 5* ppm Long-term value: 3* mg/m³, 1* ppm *table Z-2 for exclusions in 29CFR1910.1028(d)
REL (USA)	Short-term value: 1 ppm Long-term value: 0.1 ppm See Pocket Guide App. A
TLV (USA)	Short-term value: 8 mg/m³, 2.5 ppm Long-term value: 1.6 mg/m³, 0.5 ppm Skin; BEI
EL (Canada)	Short-term value: 2.5 ppm Long-term value: 0.5 ppm Skin; ACGIH A1; IARC 1
EV (Canada)	Short-term value: 2.5 ppm Long-term value: 0.5 ppm Skin

Ingredients with biological limit values:

71-43-2 Benzene (100.0%)

BEI (USA)	25 µg/g creatinine Medium: urine Time: end of shift Parameter Parameter: S-Phenylmercapturic acid (background 500 µg/g creatinine Medium: urine Time: end of shift Parameter: t,t-Muconic acid (background)

Additional information: No data

Exposure controls
Personal protective equipment
General protective and hygienic measures
The usual precautionary measures for handling chemicals should be followed.
Keep away from foodstuffs, beverages and feed.
Remove all soiled and contaminated clothing immediately.
Wash hands before breaks and at the end of work.
Store protective clothing separately.
Avoid contact with the eyes and skin.
Maintain an ergonomically appropriate working environment.
Breathing equipment: Use suitable respirator when high concentrations are present.
Recommended filter device for short term use:
Use a respirator with organic vapor/acid gas cartridges as a backup to engineering controls. Risk assessment should be performed to determine if air-purifying respirators are appropriate. Only use equipment tested and approved under appropriate government standards such as NIOSH (USA) or CEN (EU).
Protection of hands:
Impervious gloves
Check protective gloves prior to each use for their proper condition.
The selection of suitable gloves not only depends on the material, but also on quality. Quality will vary from manufacturer to manufacturer.
Material of gloves Fluorocarbon rubber (Viton)
Penetration time of glove material (in minutes) Not determined
Eye protection: Safety glasses
Body protection: Protective work clothing.

9 Physical and chemical properties

Information on basic physical and chemical properties
General Information
Appearance:

Form:	Liquid
Color:	Colorless
Odor:	Aromatic
Odor threshold:	Not determined.
pH-value:	Not determined.
Change in condition	
Melting point/Melting range:	5 °C (41 °F)
Boiling point/Boiling range:	80 °C (176 °F)
Sublimation temperature / start:	Not determined
Flash point:	-11 °C (12 °F)
Flammability (solid, gaseous)	Not determined.
Ignition temperature:	555 °C (1031 °F)
Decomposition temperature:	Not determined
Auto igniting:	Not determined.
Danger of explosion:	Product is not explosive. However, formation of explosive air/vapor mixtures is possible.
Explosion limits:	
Lower:	1.2 Vol %
Upper:	8 Vol %
Vapor pressure at 20 °C (68 °F):	101 hPa (76 mm Hg)
Density at 20 °C (68 °F):	0.874 g/cm³ (7.294 lbs/gal)
Relative density	Not determined.
Vapor density	Not determined.
Evaporation rate	Not determined.
Solubility in / Miscibility with	
Water at 25 °C (77 °F):	1.8 g/l
Partition coefficient (n-octanol/water):	Not determined.
Viscosity:	
dynamic at 20 °C (68 °F):	0.66 mPas
kinematic:	Not determined.

(Contd. on page 4)

Product name: Benzene

(Contd. of page 3)

Other information No further relevant information available.

10 Stability and reactivity

Reactivity No information known.
Chemical stability Stable under recommended storage conditions.
Thermal decomposition / conditions to be avoided: Decomposition will not occur if used and stored according to specifications.
Possibility of hazardous reactions Reacts with strong oxidizing agents
Conditions to avoid No further relevant information available.
Incompatible materials:
Acids
Oxidizing agents
Bases
Halogens
Hazardous decomposition products: Carbon monoxide and carbon dioxide

11 Toxicological information

Information on toxicological effects
Acute toxicity: The Registry of Toxic Effects of Chemical Substances (RTECS) contains acute toxicity data for this substance.

LD/LC50 values that are relevant for classification:

Oral	LD50	930 mg/kg (rat)
Dermal	LD50	>9400 µL/kg (rabbit)
Inhalative	LC50/7H	10000 ppm/7H (rat)

Skin irritation or corrosion: Causes skin irritation.
Eye irritation or corrosion: Causes serious eye irritation.
Sensitization: No sensitizing effects known.
Germ cell mutagenicity:
May cause genetic defects.
The Registry of Toxic Effects of Chemical Substances (RTECS) contains mutation data for this substance.
Carcinogenicity:
May cause cancer.
EPA-A: human carcinogen: sufficient evidence from epidemiologic studies to support a causal association between exposure and cancer.
IARC-1: Carcinogenic to humans: sufficient evidence of carcinogenicity.
ACGIH A1: Confirmed human carcinogen: Agent is carcinogenic to humans based on epidemiologic studies of, or convincing clinical evidence in, exposed humans.
EPA-K: Known human carcinogens.
Carcinogen as defined by OSHA.
NTP-K: Known to be carcinogenic: sufficient evidence from human studies.
The Registry of Toxic Effects of Chemical Substances (RTECS) contains tumorigenic and/or carcinogenic and/or neoplastic data for this substance.
Reproductive toxicity: The Registry of Toxic Effects of Chemical Substances (RTECS) contains reproductive data for this substance.
Specific target organ system toxicity - repeated exposure:
Causes damage to the lung, the kidneys, the liver, the spleen, the blood, the brain and the endocrine system through prolonged or repeated exposure. Route of exposure: Oral, Inhalative, Dermal.
Specific target organ system toxicity - single exposure: No effects known.
Aspiration hazard: May be fatal if swallowed and enters airways.
Subacute to chronic toxicity: The Registry of Toxic Effects of Chemical Substances (RTECS) contains multiple dose toxicity data for this substance.
Additional toxicological information: To the best of our knowledge the acute and chronic toxicity of this substance is not fully known.

12 Ecological information

Toxicity
Aquatic toxicity: No further relevant information available.
Persistence and degradability No further relevant information available.
Bioaccumulative potential No further relevant information available.
Mobility in soil No further relevant information available.
Additional ecological information:
General notes:
Do not allow product to reach ground water, water course or sewage system, even in small quantities.
Danger to drinking water if even extremely small quantities leak into the ground.
Avoid transfer into the environment.
Results of PBT and vPvB assessment
PBT: Not applicable.
vPvB: Not applicable.
Other adverse effects No further relevant information available.

13 Disposal considerations

Waste treatment methods
Recommendation Consult state, local or national regulations to ensure proper disposal.
Uncleaned packagings:
Recommendation: Disposal must be made according to official regulations.

14 Transport information

UN-Number	
DOT, IMDG, IATA	UN1114
UN proper shipping name	
DOT	RQ Benzene
IMDG, IATA	BENZENE
Transport hazard class(es)	
DOT	

Class	3 Flammable liquids.
Label	3
Class	3 (F1) Flammable liquids

(Contd. on page 5)

Product name: Benzene

(Contd. of page 4)

Label **IMDG, IATA**	3
Class **Label**	3 Flammable liquids. 3
Packing group **DOT, IMDG, IATA**	II
Environmental hazards:	Not applicable.
Special precautions for user **EMS Number:**	Warning: Flammable liquids F-E,S-D
Transport in bulk according to Annex II of MARPOL73/78 and the IBC Code	Not applicable.
Transport/Additional information:	
DOT **Hazardous substance:** **Marine Pollutant (DOT):**	 10 lbs, 4.54 kg No
UN "Model Regulation":	UN1114, Benzene, 3, II

15 Regulatory information

Safety, health and environmental regulations/legislation specific for the substance or mixture
GHS label elements The product is classified and labeled in accordance with 29 CFR 1910 (OSHA HCS)
Hazard pictograms

GHS02 GHS07 GHS08

Signal word Danger
Hazard statements
H225 Highly flammable liquid and vapor.
H315 Causes skin irritation.
H319 Causes serious eye irritation.
H340 May cause genetic defects.
H350 May cause cancer.
H372 Causes damage to the lung, the kidneys, the liver, the spleen, the blood, the brain and the endocrine system through prolonged or repeated exposure. Route of exposure: Oral, Inhalative, Dermal.
H304 May be fatal if swallowed and enters airways.
Precautionary statements
P210 Keep away from heat/sparks/open flames/hot surfaces. No smoking.
P301+P310 IF SWALLOWED: Immediately call a POISON CENTER/ doctor/…
P303+P361+P353 If on skin (or hair): Take off immediately all contaminated clothing. Rinse skin with water/shower.
P305+P351+P338 IF IN EYES: Rinse cautiously with water for several minutes. Remove contact lenses, if present and easy to do. Continue rinsing.
P405 Store locked up.
P501 Dispose of contents/container in accordance with local/regional/national/international regulations.
National regulations
All components of this product are listed in the U.S. Environmental Protection Agency Toxic Substances Control Act Chemical substance Inventory.
All components of this product are listed on the Canadian Domestic Substances List (DSL).

SARA Section 313 (specific toxic chemical listings)

71-43-2	Benzene

California Proposition 65

Prop 65 - Chemicals known to cause cancer

71-43-2	Benzene

Prop 65 - Developmental toxicity

71-43-2	Benzene

Prop 65 - Developmental toxicity, female Substance is not listed.

Prop 65 - Developmental toxicity, male

71-43-2	Benzene

Information about limitation of use:
Workers are not allowed to be exposed to this hazardous material. Exceptions can be made by the authorities in certain cases.
For use only by technically qualified individuals.
Other regulations, limitations and prohibitive regulations
Substance of Very High Concern (SVHC) according to the REACH Regulations (EC) No. 1907/2006. Substance is not listed.
The conditions of restrictions according to Article 67 and Annex XVII of the Regulation (EC) No 1907/2006 (REACH) for the manufacturing, placing on the market and use must be observed.
Substance is not listed.
Annex XIV of the REACH Regulations (requiring Authorisation for use) Substance is not listed.
Chemical safety assessment: A Chemical Safety Assessment has not been carried out.

16 Other information

Employers should use this information only as a supplement to other information gathered by them, and should make independent judgement of suitability of this information to ensure proper use and protect the health and safety of employees. This information is furnished without warranty, and any use of the product not in conformance with this Material Safety Data Sheet, or in combination with any other product or process, is the responsibility of the user.

Department issuing SDS: Global Marketing Department
Date of preparation / last revision 11/23/2015 / -
Abbreviations and acronyms:
ADR: Accord européen sur le transport des marchandises dangereuses par Route (European Agreement concerning the International Carriage of Dangerous Goods by Road)
IMDG: International Maritime Code for Dangerous Goods
DOT: US Department of Transportation
IATA: International Air Transport Association
EINECS: European Inventory of Existing Commercial Chemical Substances
CAS: Chemical Abstracts Service (division of the American Chemical Society)
HMIS: Hazardous Materials Identification System (USA)
WHMIS: Workplace Hazardous Materials Information System (Canada)
LC50: Lethal concentration, 50 percent
LD50: Lethal dose, 50 percent
vPvB: very Persistent and very Bioaccumulative

(Contd. on page 6)

Product name: Benzene

(Contd. of page 5)

ACGIH: American Conference of Governmental Industrial Hygienists (USA)
OSHA: Occupational Safety and Health Administration (USA)
NTP: National Toxicology Program (USA)
IARC: International Agency for Research on Cancer
EPA: Environmental Protection Agency (USA)

SAFETY DATA SHEET

Version 4.6
Revision Date 12/29/2015
Print Date 05/01/2016

1. PRODUCT AND COMPANY IDENTIFICATION

1.1 Product identifiers

Product name : Beryllium

Product Number : 378135
Brand : Aldrich

CAS-No. : 7440-41-7

1.2 Relevant identified uses of the substance or mixture and uses advised against

Identified uses : Laboratory chemicals, Synthesis of substances

1.3 Details of the supplier of the safety data sheet

Company : Sigma-Aldrich
3050 Spruce Street
SAINT LOUIS MO 63103
USA

Telephone : +1 800-325-5832
Fax : +1 800-325-5052

1.4 Emergency telephone number

Emergency Phone # : (314) 776-6555

2. HAZARDS IDENTIFICATION

2.1 Classification of the substance or mixture

GHS Classification in accordance with 29 CFR 1910 (OSHA HCS)
Acute toxicity, Oral (Category 3), H301
Acute toxicity, Inhalation (Category 2), H330
Skin irritation (Category 2), H315
Eye irritation (Category 2A), H319
Skin sensitisation (Category 1), H317
Carcinogenicity (Category 1B), H350
Specific target organ toxicity - single exposure (Category 3), Respiratory system, H335
Specific target organ toxicity - repeated exposure (Category 1), H372

For the full text of the H-Statements mentioned in this Section, see Section 16.

2.2 GHS Label elements, including precautionary statements

Pictogram

Signal word Danger

Hazard statement(s)
H301 Toxic if swallowed.
H315 Causes skin irritation.
H317 May cause an allergic skin reaction.
H319 Causes serious eye irritation.
H330 Fatal if inhaled.
H335 May cause respiratory irritation.
H350 May cause cancer.

H372	Causes damage to organs through prolonged or repeated exposure.

Precautionary statement(s)

P201	Obtain special instructions before use.
P202	Do not handle until all safety precautions have been read and understood.
P260	Do not breathe dust/ fume/ gas/ mist/ vapours/ spray.
P264	Wash skin thoroughly after handling.
P270	Do not eat, drink or smoke when using this product.
P271	Use only outdoors or in a well-ventilated area.
P272	Contaminated work clothing should not be allowed out of the workplace.
P280	Wear protective gloves/ protective clothing/ eye protection/ face protection.
P284	Wear respiratory protection.
P301 + P310 + P330	IF SWALLOWED: Immediately call a POISON CENTER or doctor/ physician. Rinse mouth.
P302 + P352	IF ON SKIN: Wash with plenty of soap and water.
P304 + P340 + P310	IF INHALED: Remove person to fresh air and keep comfortable for breathing. Immediately call a POISON CENTER or doctor/ physician.
P305 + P351 + P338	IF IN EYES: Rinse cautiously with water for several minutes. Remove contact lenses, if present and easy to do. Continue rinsing.
P308 + P313	IF exposed or concerned: Get medical advice/ attention.
P333 + P313	If skin irritation or rash occurs: Get medical advice/ attention.
P337 + P313	If eye irritation persists: Get medical advice/ attention.
P362	Take off contaminated clothing and wash before reuse.
P403 + P233	Store in a well-ventilated place. Keep container tightly closed.
P405	Store locked up.
P501	Dispose of contents/ container to an approved waste disposal plant.

2.3 Hazards not otherwise classified (HNOC) or not covered by GHS - none

3. COMPOSITION/INFORMATION ON INGREDIENTS

3.1 Substances

Formula	:	Be
Molecular weight	:	9.01 g/mol
CAS-No.	:	7440-41-7
EC-No.	:	231-150-7

Hazardous components

Component	Classification	Concentration
Berylium foil		
	Acute Tox. 3; Acute Tox. 2; Skin Irrit. 2; Eye Irrit. 2A; Skin Sens. 1; Carc. 1B; STOT SE 3; STOT RE 1; H301, H315, H317, H319, H330, H335, H350, H372	<= 100 %

For the full text of the H-Statements mentioned in this Section, see Section 16.

4. FIRST AID MEASURES

4.1 Description of first aid measures

General advice
Consult a physician. Show this safety data sheet to the doctor in attendance.Move out of dangerous area.

If inhaled
If breathed in, move person into fresh air. If not breathing, give artificial respiration. Consult a physician.

In case of skin contact
Wash off with soap and plenty of water. Take victim immediately to hospital. Consult a physician.

In case of eye contact
Rinse thoroughly with plenty of water for at least 15 minutes and consult a physician.

If swallowed
Never give anything by mouth to an unconscious person. Rinse mouth with water. Consult a physician.

4.2 Most important symptoms and effects, both acute and delayed
The most important known symptoms and effects are described in the labelling (see section 2.2) and/or in section 11

4.3 Indication of any immediate medical attention and special treatment needed
No data available

5. FIREFIGHTING MEASURES

5.1 Extinguishing media

Suitable extinguishing media
Use water spray, alcohol-resistant foam, dry chemical or carbon dioxide.

5.2 Special hazards arising from the substance or mixture
Beryllium oxides

5.3 Advice for firefighters
Wear self-contained breathing apparatus for firefighting if necessary.

5.4 Further information
No data available

6. ACCIDENTAL RELEASE MEASURES

6.1 Personal precautions, protective equipment and emergency procedures
Wear respiratory protection. Avoid dust formation. Avoid breathing vapours, mist or gas. Ensure adequate ventilation. Evacuate personnel to safe areas. Avoid breathing dust.
For personal protection see section 8.

6.2 Environmental precautions
Prevent further leakage or spillage if safe to do so. Do not let product enter drains.

6.3 Methods and materials for containment and cleaning up
Pick up and arrange disposal without creating dust. Sweep up and shovel. Keep in suitable, closed containers for disposal.

6.4 Reference to other sections
For disposal see section 13.

7. HANDLING AND STORAGE

7.1 Precautions for safe handling
Avoid contact with skin and eyes. Avoid formation of dust and aerosols.Further processing of solid materials may result in the formation of combustible dusts. The potential for combustible dust formation should be taken into consideration before additional processing occurs.
Provide appropriate exhaust ventilation at places where dust is formed.
For precautions see section 2.2.

7.2 Conditions for safe storage, including any incompatibilities
Keep container tightly closed in a dry and well-ventilated place.

Keep in a dry place.
Storage class (TRGS 510): Non-combustible, acute toxic Cat. 1 and 2 / very toxic hazardous materials

7.3 Specific end use(s)
Apart from the uses mentioned in section 1.2 no other specific uses are stipulated

8. EXPOSURE CONTROLS/PERSONAL PROTECTION

8.1 Control parameters

Components with workplace control parameters

Component	CAS-No.	Value	Control parameters	Basis
Berylium foil	7440-41-7	TWA	2.000000 mg/m3	USA. Occupational Exposure Limits (OSHA) - Table Z-2
		CEIL	5.000000 mg/m3	USA. Occupational Exposure Limits (OSHA) - Table Z-2
		Peak	25.000000 mg/m3	USA. Occupational Exposure Limits (OSHA) - Table Z-2
		TWA	2.000000microgram per cubic meter	USA. Occupational Exposure Limits (OSHA) - Table Z-2
	Remarks	Z27.29-1970		
		CEIL	5.000000microgram per cubic meter	USA. Occupational Exposure Limits (OSHA) - Table Z-2
		Z27.29-1970		
		Peak	25.000000microgram per cubic meter	USA. Occupational Exposure Limits (OSHA) - Table Z-2
		Z27.29-1970		
		TWA	0.000050 mg/m3	USA. ACGIH Threshold Limit Values (TLV)
		Beryllium sensitization Chronic beryllium disease (berylliosis) Confirmed human carcinogen Danger of cutaneous absorption Sensitizer		
		C	0.000500 mg/m3	USA. NIOSH Recommended Exposure Limits
		Potential Occupational Carcinogen See Appendix A		
		See Table Z-2		
		TWA	2.000000microgram per cubic meter	USA. Occupational Exposure Limits (OSHA) - Table Z-2
		Z27.29-1970		
		TWA	2.000000microgram per cubic meter	USA. Occupational Exposure Limits (OSHA) - Table Z-2
		Z27.29-1970		
		CEIL	5.000000microgram per cubic meter	USA. Occupational Exposure Limits (OSHA) - Table Z-2
		Z27.29-1970		
		CEIL	5.000000microgram per cubic meter	USA. Occupational Exposure Limits (OSHA) - Table Z-2
		Z27.29-1970		
		Peak	25.000000microgram per cubic meter	USA. Occupational Exposure Limits (OSHA) - Table Z-2
		Z27.29-1970		
		Peak	25.000000microgram per cubic meter	USA. Occupational Exposure Limits (OSHA) - Table Z-2
		Z27.29-1970		
		TWA	0.000050 mg/m3	USA. ACGIH Threshold Limit Values (TLV)
		Beryllium sensitization		

		Chronic beryllium disease (berylliosis) Adopted values or notations enclosed are those for which changes are proposed in the NIC See Notice of Intended Changes (NIC) Confirmed human carcinogen Danger of cutaneous absorption Sensitizer		
		C	0.000500 mg/m3	USA. NIOSH Recommended Exposure Limits
		Potential Occupational Carcinogen See Appendix A		
		See Table Z-2		
		TWA	2microgram per cubic meter	USA. Occupational Exposure Limits (OSHA) - Table Z-2
		Z27.29-1970		
		CEIL	5microgram per cubic meter	USA. Occupational Exposure Limits (OSHA) - Table Z-2
		Z27.29-1970		
		Peak	25microgram per cubic meter	USA. Occupational Exposure Limits (OSHA) - Table Z-2
		Z27.29-1970		
		C	0.0005 mg/m3	USA. NIOSH Recommended Exposure Limits
		Potential Occupational Carcinogen See Appendix A		

8.2 Exposure controls

Appropriate engineering controls
Avoid contact with skin, eyes and clothing. Wash hands before breaks and immediately after handling the product.

Personal protective equipment

Eye/face protection
Face shield and safety glasses Use equipment for eye protection tested and approved under appropriate government standards such as NIOSH (US) or EN 166(EU).

Skin protection
Handle with gloves. Gloves must be inspected prior to use. Use proper glove removal technique (without touching glove's outer surface) to avoid skin contact with this product. Dispose of contaminated gloves after use in accordance with applicable laws and good laboratory practices. Wash and dry hands.

Full contact
Material: Nitrile rubber
Minimum layer thickness: 0.11 mm
Break through time: 480 min
Material tested:Dermatril® (KCL 740 / Aldrich Z677272, Size M)

Splash contact
Material: Nitrile rubber
Minimum layer thickness: 0.11 mm
Break through time: 480 min
Material tested:Dermatril® (KCL 740 / Aldrich Z677272, Size M)

data source: KCL GmbH, D-36124 Eichenzell, phone +49 (0)6659 87300, e-mail sales@kcl.de, test method: EN374
If used in solution, or mixed with other substances, and under conditions which differ from EN 374, contact the supplier of the CE approved gloves. This recommendation is advisory only and must be evaluated by an industrial hygienist and safety officer familiar with the specific situation of anticipated use by our customers. It should not be construed as offering an approval for any specific use scenario.

Body Protection
Complete suit protecting against chemicals, The type of protective equipment must be selected according to the concentration and amount of the dangerous substance at the specific workplace.

Respiratory protection
Where risk assessment shows air-purifying respirators are appropriate use a full-face particle respirator type N100 (US) or type P3 (EN 143) respirator cartridges as a backup to engineering controls. If the respirator is the sole means of protection, use a full-face supplied air respirator. Use respirators and components tested and approved under appropriate government standards such as NIOSH (US) or CEN (EU).

Control of environmental exposure
Prevent further leakage or spillage if safe to do so. Do not let product enter drains.

9. PHYSICAL AND CHEMICAL PROPERTIES

9.1 Information on basic physical and chemical properties

a)	Appearance	Form: powder Colour: grey
b)	Odour	odourless
c)	Odour Threshold	No data available
d)	pH	No data available
e)	Melting point/freezing point	Melting point/range: 1,278 °C (2,332 °F) - lit.
f)	Initial boiling point and boiling range	2,970 °C (5,378 °F) - lit.
g)	Flash point	No data available
h)	Evaporation rate	No data available
i)	Flammability (solid, gas)	No data available
j)	Upper/lower flammability or explosive limits	No data available
k)	Vapour pressure	No data available
l)	Vapour density	No data available
m)	Relative density	1.85 g/cm3 at 25 °C (77 °F)
n)	Water solubility	No data available
o)	Partition coefficient: n-octanol/water	No data available
p)	Auto-ignition temperature	No data available
q)	Decomposition temperature	No data available
r)	Viscosity	No data available
s)	Explosive properties	No data available
t)	Oxidizing properties	No data available

9.2 Other safety information
No data available

10. STABILITY AND REACTIVITY

10.1 Reactivity
No data available

10.2 Chemical stability
Stable under recommended storage conditions.

10.3 Possibility of hazardous reactions
No data available

10.4 Conditions to avoid
No data available

10.5 Incompatible materials
Alkali metals

10.6 Hazardous decomposition products
Other decomposition products - No data available
In the event of fire: see section 5

11. TOXICOLOGICAL INFORMATION

11.1 Information on toxicological effects

Acute toxicity
No data available

Inhalation: No data available

Dermal: No data available

LD50 Intravenous - Rat - 0.496 mg/kg
Remarks: Liver:Hepatitis (hepatocellular necrosis), zonal.

Skin corrosion/irritation
No data available

Serious eye damage/eye irritation
No data available

Respiratory or skin sensitisation
No data available

Germ cell mutagenicity
Hamster
Lungs
Result: negative

Carcinogenicity

Carcinogenicity - Rat - Intratracheal
Tumorigenic:Neoplastic by RTECS criteria. Lungs, Thorax, or Respiration:Tumors. Lungs, Thorax, or Respiration:Bronchiogenic carcinoma.

Carcinogenicity - Rabbit - Intravenous
Tumorigenic:Equivocal tumorigenic agent by RTECS criteria. Musculoskeletal:Tumors.

Possible human carcinogen

IARC:	1 - Group 1: Carcinogenic to humans (Berylium foil)
NTP:	Known to be human carcinogen (Berylium foil)
	Known to be human carcinogenThe reference note has been added by TD based on the background information of the NTP. (Berylium foil)
OSHA:	No component of this product present at levels greater than or equal to 0.1% is identified as a carcinogen or potential carcinogen by OSHA.

Reproductive toxicity
No data available

No data available

Specific target organ toxicity - single exposure
No data available

Specific target organ toxicity - repeated exposure
No data available

Aspiration hazard
No data available

Additional Information
RTECS: DS1750000

12. ECOLOGICAL INFORMATION

12.1 Toxicity
No data available

12.2 Persistence and degradability
No data available

12.3 Bioaccumulative potential
No data available

12.4 Mobility in soil
No data available

12.5 Results of PBT and vPvB assessment
PBT/vPvB assessment not available as chemical safety assessment not required/not conducted

12.6 Other adverse effects

No data available

13. DISPOSAL CONSIDERATIONS

13.1 Waste treatment methods

Product
Offer surplus and non-recyclable solutions to a licensed disposal company. Contact a licensed professional waste disposal service to dispose of this material. Dissolve or mix the material with a combustible solvent and burn in a chemical incinerator equipped with an afterburner and scrubber.

Contaminated packaging
Dispose of as unused product.

14. TRANSPORT INFORMATION

DOT (US)
UN number: 1567 Class: 6.1 (4.1) Packing group: II
Proper shipping name: Beryllium, powder
Reportable Quantity (RQ): 10 lbs

Poison Inhalation Hazard: No

IMDG
UN number: 1567 Class: 6.1 (4.1) Packing group: II EMS-No: F-G, S-G
Proper shipping name: BERYLLIUM POWDER

IATA
UN number: 1567 Class: 6.1 (4.1) Packing group: II
Proper shipping name: Beryllium powder

15. REGULATORY INFORMATION

SARA 302 Components
No chemicals in this material are subject to the reporting requirements of SARA Title III, Section 302.

SARA 313 Components
The following components are subject to reporting levels established by SARA Title III, Section 313:

	CAS-No.	Revision Date
Berylium foil	7440-41-7	1993-04-24

SARA 311/312 Hazards

Acute Health Hazard, Chronic Health Hazard

Massachusetts Right To Know Components

	CAS-No.	Revision Date
Berylium foil	7440-41-7	1993-04-24

Pennsylvania Right To Know Components

	CAS-No.	Revision Date
Berylium foil	7440-41-7	1993-04-24

New Jersey Right To Know Components

	CAS-No.	Revision Date
Berylium foil	7440-41-7	1993-04-24

California Prop. 65 Components

WARNING! This product contains a chemical known to the State of California to cause cancer.	CAS-No.	Revision Date
Berylium foil	7440-41-7	2008-10-10

16. OTHER INFORMATION

Full text of H-Statements referred to under sections 2 and 3.

Acute Tox.	Acute toxicity
Carc.	Carcinogenicity
Eye Irrit.	Eye irritation
H301	Toxic if swallowed.
H315	Causes skin irritation.
H317	May cause an allergic skin reaction.
H319	Causes serious eye irritation.
H330	Fatal if inhaled.
H335	May cause respiratory irritation.
H350	May cause cancer.
H372	Causes damage to organs through prolonged or repeated exposure.
Skin Irrit.	Skin irritation
Skin Sens.	Skin sensitisation

HMIS Rating

Health hazard:	4
Chronic Health Hazard:	*
Flammability:	0
Physical Hazard	0

NFPA Rating

Health hazard:	4
Fire Hazard:	3
Reactivity Hazard:	3

Further information

Copyright 2015 Sigma-Aldrich Co. LLC. License granted to make unlimited paper copies for internal use only.
The above information is believed to be correct but does not purport to be all inclusive and shall be used only as a guide. The information in this document is based on the present state of our knowledge and is applicable to the product with regard to appropriate safety precautions. It does not represent any guarantee of the properties of the product. Sigma-Aldrich Corporation and its Affiliates shall not be held liable for any damage resulting from handling or from contact with the above product. See www.sigma-aldrich.com and/or the reverse side of invoice or packing slip for additional terms and conditions of sale.

Preparation Information

Sigma-Aldrich Corporation
Product Safety – Americas Region
1-800-521-8956

Safety Data Sheet

Revision Date: 12/30/16
www.restek.com

1. IDENTIFICATION

Catalog Number / Product Name:	**31274 / Benzo(k)fluoranthene Standard**
Company:	Restek Corporation
Address:	110 Benner Circle Bellefonte, Pa. 16823
Phone#:	814-353-1300
Fax#:	814-353-1309
Emergency#:	800-424-9300 (CHEMTREC) 703-527-3887 (Outside the US)
Email:	www.restek.com
Revision Number:	10
Intended use:	For Laboratory use only

2. HAZARD(S)IDENTIFICATION

Emergency Overview:

GHS Hazard Symbols:

GHS Classification:	Flammable Liquid Category 2 Serious Eye Damage/Eye Irritation Category 2 Specific Target Organ Systemic Toxicity (STOT) - Single Exposure Category 3
GHS Signal Word:	Danger
GHS Hazard:	Highly flammable liquid and vapour. Causes serious eye irritation. May cause drowsiness or dizziness.
GHS Precautions:	
Safety Precautions:	Keep away from heat/sparks/open flames/hot surfaces. – No smoking. Ground/bond container and receiving equipment. Use explosion-proof electrical/ventilation and lighting equipment. Use only non-sparking tools. Take precautionary measures against static discharge. Avoid breathing dust/fume/gas/mist/vapours/spray. Wash hands and skin thoroughly after handling. Use only outdoors or in a well-ventilated area. Wear protective gloves/protective clothing/eye protection/face protection.
First Aid Measures:	IF ON SKIN (or hair): Remove/Take off immediately all contaminated clothing. Rinse skin with water/shower. IF INHALED: Remove victim to fresh air and keep at rest in a position comfortable for breathing. IF IN EYES: Rinse cautiously with water for several minutes. Remove contact lenses, if present and easy to do. Continue rinsing. Call a POISON CENTER or doctor/physician if you feel unwell. If eye irritation persists: Get medical advice/attention. In case of fire: Use extinguishing media in section 5 for extinction.
Storage:	Store in a well-ventilated place. Keep container tightly closed. Store in a well-ventilated place. Keep cool. Store locked up.
Disposal:	Dispose of contents/container according to section 13 of the SDS.

Single Exposure Target Organs: No data available.

Repeated Exposure Target Organs: No data available.

3. COMPOSITION / INFORMATION ON INGREDIENT

Chemical Name	CAS #	EINEC #	% Composition
Acetone	67-64-1	200-662-2	99.900000
benzo (k) fluoranthene	207-08-9	205-916-6	0.100000

4. FIRST-AID MEASURES

Inhalation: Remove to fresh air. If breathing is difficult, have a trained individual administer oxygen. If not breathing, give artificial respiration and have a trained individual administer oxygen. Get medical attention immediately

Eyes: Flush eyes with plenty of water for at least 20 minutes retracting eyelids often. Tilt the head to prevent chemical from transferring to the uncontaminated eye. Get immediate medical attention.

Skin Contact: Wash with soap and water. Remove contaminated clothing and launder. Get medical attention if irritation develops or persists.

Ingestion: Do not induce vomiting and seek medical attention immediately. Drink two glasses of water or milk to dilute. Provide medical care provider with this SDS.

5. FIRE- FIGHTING MEASURES

Extinguishing Media: Use alcohol resistant foam, carbon dioxide, or dry chemical extinguishing agents. Water spray or fog may also be effective for extinguishing if swept across the base of the fire. Water can also be used to absorb heat and keep exposed material from being damaged by fire. Flammable component(s) of this material may be lighter than water and burn while floating on the surface.

Fire and/or Explosion Hazards: Vapors may be ignited by heat, sparks, flames or other sources of ignition at or above the low flash point giving rise to a Class B fire. Vapors are heavier than air and may travel to a source of ignition and flash back

Fire Fighting Methods and Protection: Do not enter fire area without proper protection including self-contained toxic breathing apparatus and full protective equipment. Fight fire from a safe distance and a protected location due to the potential of hazardous vapors and decomposition products. Flammable component(s) of this material may be lighter than water and burn while floating on the surface. Use water spray/fog for cooling.

Hazardous Combustion Products: Carbon dioxide, Carbon monoxide

6. ACCIDENTAL RELEASE MEASURES

Personal Precautions and Equipment: Exposure to the spilled material may be irritating or harmful. Follow personal protective equipment recommendations found in Section 8 of this SDS. Additional precautions may be necessary based on special circumstances created by the spill including; the material spilled, the quantity of the spill, the area in which the spill occurred. Also consider the expertise of employees in the area responding to the spill.

Methods for Clean-up: Prevent the spread of any spill to minimize harm to human health and the environment if safe to do so. Wear complete and proper personal protective equipment following the recommendation of Section 8 at a minimum. Dike with suitable absorbent material like granulated clay. Gather and store in a sealed container pending a waste disposal evaluation.

7. HANDLING AND STORAGE

Handling Technical Measures and Precautions: Harmful or irritating material. Avoid contacting and avoid breathing the material. Use only in a well ventilated area. Use spark-proof tools and explosion-proof equipment

Storage Technical Measures and Conditions: Store in a cool dry ventilated location. Isolate from

incompatible materials and conditions. Keep container(s) closed. Keep away from sources of ignition

8. EXPOSURE CONTROLS / PERSONAL PROTECTION

United States:

Chemical Name	CAS No.	IDLH	ACGIH STEL	ACGIH TLV-TWA	OSHA Exposure Limit
Acetone	67-64-1	2500 ppm IDLH (10% LEL)	500 ppm STEL 750 ppm STEL; 1782 mg/m3 STEL	250 ppm TWA 500 ppm TWA; 1188 mg/m3 TWA	1000 ppm TWA; 2400 mg/m3 TWA
benzo (k) fluoranthene	207-08-9	ND		No TLV	No data available.

Personal Protection:

Engineering Measures: Local exhaust ventilation is recommended when generating excessive levels of vapors from handling or thermal processing.

Respiratory Protection: No respiratory protection required under normal conditions of use. Provide general room exhaust ventilation if symptoms of overexposure occur as explained Section 3. A respirator is not normally required.

Eye Protection: Wear chemically resistant safety glasses with side shields when handling this product. Do not wear contact lenses.

Skin Protection: Wear protective gloves. Inspect gloves for chemical break-through and replace at regular intervals. Clean protective equipment regularly. Wash hands and other exposed areas with mild soap and water before eating, drinking, and when leaving work

Medical Conditions Aggravated By Exposure: Respiratory disease including asthma and bronchitis

9. PHYSICAL AND CHEMICAL PROPERTIES

Appearance, color: Depends upon product selection
Odor: Strong
Physical State: No data available.
pH: No data available.
Vapor Pressure: No data available.
Vapor Density: 2.0 (air = 1)
Boiling Point: No data available.
Melting Point: -95.4 °C Melting Point
Flash Point: 39
Flammability: Highly Flammable
Upper Flammable/Explosive Limit, % in air: No data available.
Lower Flammable/Explosive Limit, % in air: No data available.
Autoignition Temperature: 465 deg C
Decomposition Temperature: No data available.
Specific Gravity: 0.7845 g/cm3 at 25 °C
Evaporation Rate: No data available.
Odor Threshold: ND
Solubility: Complete; 100%
Partition Coefficient: n-octanol in water: No data available.
VOC % by weight: 0
Molecular Weight: 58.08

10. STABILITY AND REACTIVITY

Stability: Stable under normal conditions.
Conditions to Avoid: No data available.
Materials to Avoid / Chemical Incompatiability: Strong oxidizing agents Strong acids
Hazardous Decomposition Products: Carbon dioxide Carbon monoxide

11. TOXICOLOGICAL INFORMATION

Routes of Entry: Inhalation, Skin Contact, Eye Contact, Ingestion
Target Organs Potentially Affected By Exposure: Eyes, Central nervous system stimulation, Respiratory Tract, Skin
Chemical Interactions That Change Toxicity: None Known

Immediate (Acute) Health Effects by Route of Exposure:

Inhalation Irritation:	Can cause minor respiratory irritation, dizziness, weakness, fatigue, nausea, and headache.
Skin Contact:	Can cause minor skin irritation, defatting, and dermatitis.
Eye Contact:	Can cause minor irritation, tearing and reddening.
Ingestion Irritation:	May be harmful if swallowed.
Ingestion Toxicity:	Harmful if swallowed. May cause systemic poisoning.

Long-Term (Chronic) Health Effects:

Carcinogenicity:	Contains a probable or known human carcinogen.
Reproductive and Developmental Toxicity:	No data available to indicate product or any components present at greater than 0.1% may cause birth defects.
Inhalation:	Upon prolonged and/or repeated exposure, can cause minor respiratory irritation, dizziness, weakness, fatigue, nausea, and headache.
Skin Contact:	Upon prolonged or repeated contact, can cause minor skin irritation, defatting, and dermatitis.

Component Toxicological Data:
NIOSH:

Chemical Name	**CAS No.**	**LD50/LC50**
Acetone	67-64-1	Dermal LD50 Rabbit >15700 mg/kg; Oral LD50 Rat 5800 mg/kg; Inhalation LC50 Rat 50100 mg/m3 8 h

Component Carcinogenic Data:
OSHA:

Chemical Name	**CAS No.**	
Benzo(k)fluoranthene	207-08-9	Present

ACGIH:

Chemical Name	**CAS No.**	
Acetone	67-64-1	A4 - Not Classifiable as a Human Carcinogen

NIOSH:

Chemical Name	**CAS No.**
No data available.	

NTP:

Chemical Name	**CAS No.**
No data available.	

IARC:

Chemical Name	**CAS No.**	**Group No.**
No data.		Group 1
No data.		Group 2A
Benzo(k)fluoranthene	207-08-9	Group 2B

12. ECOLOGICAL INFORMATION

Overview:	This material is not expected to be harmful to the ecology.
Mobility:	No data
Persistence:	No data
Bioaccumulation:	No data
Degradability:	No data
Ecological Toxicity Data:	No data available.

13. DISPOSAL CONSIDERATIONS

Waste Description of Spent Product:	Spent or discarded material is a hazardous waste.
Disposal Methods:	Dispose of by incineration following Federal, State, Local, or Provincial regulations.
Waste Disposal of Packaging:	Comply with all Local, State, Federal, and Provincial Environmental Regulations.

14. TRANSPORTATION INFORMATION

United States:	
DOT Proper Shipping Name:	Acetone
UN Number:	UN1090

Hazard Class: 3
Packing Group: II

International:
IATA Proper Shipping Name: Acetone
UN Number: UN1090
Hazard Class: 3
Packing Group: II

Marine Pollutant: No

Chemical Name	CAS#	Marine Pollutant	Severe Marine Pollutant
No data available.			

15. REGULATORY INFORMATION

United States:

Chemical Name	CAS#	CERCLA	SARA 313	SARA EHS 313	TSCA
Acetone	67-64-1	X	-	-	X
benzo (k) fluoranthene	207-08-9	X	X	-	-

The following chemicals are listed on CA Prop 65:

Chemical Name	CAS #	Regulation
Benzo[k]fluoranthene	207-08-9	Prop 65 Cancer

State Right To Know Listing:

Chemical Name	CAS#	New Jersey	Massachusetts	Pennsylvania	California
Acetone	67-64-1	X	X	X	X
benzo (k) fluoranthene	207-08-9	X	X	X	X

16. OTHER INFORMATION

Prior Version Date: 05/15/15
Other Information: Any changes to the SDS compared to previous versions are marked by a vertical line in front of the concerned paragraph.
References: No data available.
Disclaimer: Restek Corporation provides the descriptions, data and information contained herein in good faith but makes no representation as to its comprehensiveness or accuracy. It is provided for your guidance only. Because many factors may affect processing or application/use, Restek Corporation recommends you perform an assessment to determine the suitability of a product for your particular purpose prior to use. No warranties of any kind, either expressed or implied, including fitness for a particular purpose, are made regarding prodcuts described, data or information set forth. In no case shall the descriptions, information, or data provided be considered a part of our terms and conditions of sale. Further, the descriptions, data and information furnished hereunder are given gratis. No obligation or liability for the description, data and information given are assumed. All such being given and accepted at your risk.

SAFETY DATA SHEET

Creation Date 14-May-2010 **Revision Date** 23-Dec-2014 **Revision Number** 1

1. Identification

Product Name **Carbazole**

Cat No. : **AC108260000; AC108260010; AC108260050; AC108260250; AC108262500; AC108265000**

Synonyms 9-Azafluorene; Dibenzopyrrole; Diphenylenimine

Recommended Use Laboratory chemicals.

Uses advised against No Information available

Details of the supplier of the safety data sheet

Company
Fisher Scientific
One Reagent Lane
Fair Lawn, NJ 07410
Tel: (201) 796-7100

Entity / Business Name
Acros Organics
One Reagent Lane
Fair Lawn, NJ 07410

Emergency Telephone Number
For information **US** call: 001-800-ACROS-01 / **Europe** call: +32 14 57 52 11
Emergency Number **US:**001-201-796-7100 / **Europe:** +32 14 57 52 99
CHEMTREC Tel. No.**US:**001-800-424-9300 / **Europe:**001-703-527-3887

2. Hazard(s) identification

Classification
This chemical is considered hazardous by the 2012 OSHA Hazard Communication Standard (29 CFR 1910.1200)

Skin Corrosion/irritation	Category 2
Serious Eye Damage/Eye Irritation	Category 2
Carcinogenicity	Category 1B
Specific target organ toxicity (single exposure)	Category 3
Target Organs - Respiratory system.	

Label Elements

Signal Word
Danger

Hazard Statements
Causes skin irritation
Causes serious eye irritation
May cause respiratory irritation
May cause cancer

Precautionary Statements
Prevention
Obtain special instructions before use
Do not handle until all safety precautions have been read and understood
Use personal protective equipment as required
Wash face, hands and any exposed skin thoroughly after handling
Wear eye/face protection
Avoid breathing dust/fume/gas/mist/vapors/spray
Use only outdoors or in a well-ventilated area
Response
IF exposed or concerned: Get medical attention/advice
Inhalation
IF INHALED: Remove victim to fresh air and keep at rest in a position comfortable for breathing
Skin
IF ON SKIN: Wash with plenty of soap and water
If skin irritation occurs: Get medical advice/attention
Take off contaminated clothing and wash before reuse
Eyes
IF IN EYES: Rinse cautiously with water for several minutes. Remove contact lenses, if present and easy to do. Continue rinsing
If eye irritation persists: Get medical advice/attention
Storage
Store locked up
Store in a well-ventilated place. Keep container tightly closed
Disposal
Dispose of contents/container to an approved waste disposal plant
Hazards not otherwise classified (HNOC)
Very toxic to aquatic life with long lasting effects

3. Composition / information on ingredients

Component	CAS-No	Weight %
9H-Carbazole	86-74-8	>95

4. First-aid measures

Eye Contact Rinse immediately with plenty of water, also under the eyelids, for at least 15 minutes. Obtain medical attention.

Skin Contact Wash off immediately with soap and plenty of water while removing all contaminated clothes and shoes. Obtain medical attention.

Inhalation Remove from exposure, lie down. Move to fresh air. Obtain medical attention.

Ingestion Clean mouth with water. Get medical attention.

Most important symptoms/effects No information available.
Notes to Physician Treat symptomatically

5. Fire-fighting measures

Suitable Extinguishing Media Water spray. Carbon dioxide (CO_2). Dry chemical. chemical foam.

Unsuitable Extinguishing Media No information available

Flash Point 220 °C / 428 °F
Method - No information available

Autoignition Temperature 540 °C / 1004 °F
Explosion Limits
Upper No data available
Lower No data available
Sensitivity to Mechanical Impact No information available
Sensitivity to Static Discharge No information available

Specific Hazards Arising from the Chemical
Do not allow run-off from fire fighting to enter drains or water courses.

Hazardous Combustion Products
Nitrogen oxides (NOx) Carbon monoxide (CO) Carbon dioxide (CO_2)
Protective Equipment and Precautions for Firefighters
As in any fire, wear self-contained breathing apparatus pressure-demand, MSHA/NIOSH (approved or equivalent) and full protective gear.

NFPA

Health	Flammability	Instability	Physical hazards
2	1	0	N/A

6. Accidental release measures

Personal Precautions Ensure adequate ventilation. Use personal protective equipment.
Environmental Precautions Do not flush into surface water or sanitary sewer system. Do not allow material to contaminate ground water system. Prevent product from entering drains. Local authorities should be advised if significant spillages cannot be contained. See Section 12 for additional ecological information. Avoid release to the environment. Collect spillage.

Methods for Containment and Clean Up Sweep up or vacuum up spillage and collect in suitable container for disposal. Do not let this chemical enter the environment.

7. Handling and storage

Handling Avoid contact with skin and eyes. Do not breathe dust. Do not ingest. Use only in area provided with appropriate exhaust ventilation.

Storage Keep in a dry, cool and well-ventilated place. Keep container tightly closed.

8. Exposure controls / personal protection

Exposure Guidelines This product does not contain any hazardous materials with occupational exposure limits established by the region specific regulatory bodies.

Engineering Measures Ensure adequate ventilation, especially in confined areas. Ensure that eyewash stations and safety showers are close to the workstation location.

Personal Protective Equipment

Eye/face Protection Wear appropriate protective eyeglasses or chemical safety goggles as described by OSHA's eye and face protection regulations in 29 CFR 1910.133 or European Standard EN166.

Skin and body protection Wear appropriate protective gloves and clothing to prevent skin exposure.

Respiratory Protection Follow the OSHA respirator regulations found in 29 CFR 1910.134 or European Standard EN 149. Use a NIOSH/MSHA or European Standard EN 149 approved respirator if exposure limits are exceeded or if irritation or other symptoms are experienced.

Hygiene Measures Handle in accordance with good industrial hygiene and safety practice.

9. Physical and chemical properties

Physical State	Solid
Appearance	Beige
Odor	pungent
Odor Threshold	No information available
pH	No information available
Melting Point/Range	240 - 246 °C / 464 - 474.8 °F
Boiling Point/Range	355 °C / 671 °F @ 760 mmHg
Flash Point	220 °C / 428 °F
Evaporation Rate	Not applicable
Flammability (solid,gas)	No information available
Flammability or explosive limits	
Upper	No data available
Lower	No data available
Vapor Pressure	400 mmHg @ 323 °C
Vapor Density	Not applicable
Relative Density	1.1
Solubility	insoluble
Partition coefficient; n-octanol/water	No data available
Autoignition Temperature	540 °C / 1004 °F
Decomposition Temperature	No information available
Viscosity	Not applicable
Molecular Formula	C12 H9 N
Molecular Weight	167.21

10. Stability and reactivity

Reactive Hazard None known, based on information available

Stability Stable under normal conditions.

Conditions to Avoid Incompatible products.

Incompatible Materials Strong oxidizing agents, Strong bases

Hazardous Decomposition Products Nitrogen oxides (NOx), Carbon monoxide (CO), Carbon dioxide (CO_2)

Hazardous Polymerization Hazardous polymerization does not occur.

Hazardous Reactions None under normal processing.

11. Toxicological information

Acute Toxicity

Product Information

Component Information

Component	LD50 Oral	LD50 Dermal	LC50 Inhalation
9H-Carbazole	>5000 mg/kg (Rat)	Not listed	Not listed

Toxicologically Synergistic Products No information available

Delayed and immediate effects as well as chronic effects from short and long-term exposure

Irritation No information available

Sensitization No information available

Carcinogenicity The table below indicates whether each agency has listed any ingredient as a carcinogen. Limited evidence of a carcinogenic effect.

Component	CAS-No	IARC	NTP	ACGIH	OSHA	Mexico
9H-Carbazole	86-74-8	Group 2B	Not listed	Not listed	X	Not listed

Mutagenic Effects Not mutagenic in AMES Test

Reproductive Effects No information available.

Developmental Effects No information available.

Teratogenicity No information available.

STOT - single exposure Respiratory system
STOT - repeated exposure None known

Aspiration hazard No information available

Symptoms / effects,both acute and delayed No information available
Endocrine Disruptor Information No information available

Other Adverse Effects The toxicological properties have not been fully investigated. See actual entry in RTECS for complete information.

12. Ecological information

Ecotoxicity
Very toxic to aquatic organisms, may cause long-term adverse effects in the aquatic environment. The product contains following substances which are hazardous for the environment.

Component	Freshwater Algae	Freshwater Fish	Microtox	Water Flea
9H-Carbazole	6.7 mg/L EC50 = 60 h	1 mg/L LC50 48 h	EC50 = 10.6 mg/L 15 min EC50 = 11.6 mg/L 30 min EC50 = 13.6 mg/L 5 min	Not listed

Persistence and Degradability Insoluble in water Persistence is unlikely
Bioaccumulation/ Accumulation No information available.

Mobility . Is not likely mobile in the environment due its low water solubility.

Component	log Pow
9H-Carbazole	3.84

13. Disposal considerations

Waste Disposal Methods Chemical waste generators must determine whether a discarded chemical is classified as a hazardous waste. Chemical waste generators must also consult local, regional, and national hazardous waste regulations to ensure complete and accurate classification.

14. Transport information

DOT

UN-No UN3077
Proper Shipping Name Environmentally hazardous substance, solid, n.o.s.
Proper technical name 9H-Carbazole
Hazard Class 9
Packing Group III

TDG

UN-No UN3077
Proper Shipping Name Environmentally hazardous substance, solid, n.o.s.
Hazard Class 9
Packing Group III

IATA
UN-No UN3077
Proper Shipping Name Environmentally hazardous substance, solid, n.o.s.
Hazard Class 9
Packing Group III

IMDG/IMO
UN-No UN3077
Proper Shipping Name ENVIRONMENTALLY HAZARDOUS SUBSTANCE, SOLID, N.O.S.
Hazard Class 9
Packing Group III

15. Regulatory information

International Inventories

Component	TSCA	DSL	NDSL	EINECS	ELINCS	NLP	PICCS	ENCS	AICS	IECSC	KECL
9H-Carbazole	X	X	-	201-696-0	-		X	X	X	X	X

Legend:
X - Listed
E - Indicates a substance that is the subject of a Section 5(e) Consent order under TSCA.
F - Indicates a substance that is the subject of a Section 5(f) Rule under TSCA.
N - Indicates a polymeric substance containing no free-radical initiator in its inventory name but is considered to cover the designated polymer made with any free-radical initiator regardless of the amount used.
P - Indicates a commenced PMN substance
R - Indicates a substance that is the subject of a Section 6 risk management rule under TSCA.
S - Indicates a substance that is identified in a proposed or final Significant New Use Rule
T - Indicates a substance that is the subject of a Section 4 test rule under TSCA.
XU - Indicates a substance exempt from reporting under the Inventory Update Rule, i.e. Partial Updating of the TSCA Inventory Data Base Production and Site Reports (40 CFR 710(B).
Y1 - Indicates an exempt polymer that has a number-average molecular weight of 1,000 or greater.
Y2 - Indicates an exempt polymer that is a polyester and is made only from reactants included in a specified list of low concern reactants that comprises one of the eligibility criteria for the exemption rule.

U.S. Federal Regulations

TSCA 12(b) Not applicable

SARA 313 Not applicable

SARA 311/312 Hazardous Categorization
Acute Health Hazard Yes
Chronic Health Hazard Yes
Fire Hazard No
Sudden Release of Pressure Hazard No
Reactive Hazard No

Clean Water Act Not applicable

Clean Air Act Not applicable

OSHA Occupational Safety and Health Administration
Not applicable

CERCLA
Not applicable

California Proposition 65 This product contains the following Proposition 65 chemicals:

Component	CAS-No	California Prop. 65	Prop 65 NSRL	Category

9H-Carbazole	86-74-8	Carcinogen	4.1 µg/day	Carcinogen

State Right-to-Know Not applicable

U.S. Department of Transportation

Reportable Quantity (RQ): N
DOT Marine Pollutant N
DOT Severe Marine Pollutant N

U.S. Department of Homeland Security
This product does not contain any DHS chemicals.

Other International Regulations

Mexico - Grade No information available

Canada
This product has been classified in accordance with the hazard criteria of the Controlled Products Regulations (CPR) and the MSDS contains all the information required by the CPR

WHMIS Hazard Class D2A Very toxic materials



16. Other information

Prepared By Regulatory Affairs
Thermo Fisher Scientific
Email: EMSDS.RA@thermofisher.com

Creation Date 14-May-2010
Revision Date 23-Dec-2014
Print Date 23-Dec-2014
Revision Summary This document has been updated to comply with the US OSHA HazCom 2012 Standard replacing the current legislation under 29 CFR 1910.1200 to align with the Globally Harmonized System of Classification and Labeling of Chemicals (GHS)

Disclaimer
The information provided on this Safety Data Sheet is correct to the best of our knowledge, information and belief at the date of its publication. The information given is designed only as a guide for safe handling, use, processing, storage, transportation, disposal and release and is not to be considered as a warranty or quality specification. The information relates only to the specific material designated and may not be valid for such material used in combination with any other material or in any process, unless specified in the text.

End of SDS

SAFETY DATA SHEET

Version 5.4
Revision Date 04/21/2015
Print Date 05/13/2016

1. PRODUCT AND COMPANY IDENTIFICATION

1.1 Product identifiers

Product name : Chlordane - Sandy Loam 2

Product Number : CRM825
Brand : Sigma-Aldrich

1.2 Relevant identified uses of the substance or mixture and uses advised against

Identified uses : Laboratory chemicals, Manufacture of substances

1.3 Details of the supplier of the safety data sheet

Company : Sigma-Aldrich
3050 Spruce Street
SAINT LOUIS MO 63103
USA

Telephone : +1 800-325-5832
Fax : +1 800-325-5052

1.4 Emergency telephone number

Emergency Phone # : (314) 776-6555

2. HAZARDS IDENTIFICATION

2.1 Classification of the substance or mixture

GHS Classification in accordance with 29 CFR 1910 (OSHA HCS)
Carcinogenicity (Category 1A), H350
Specific target organ toxicity - repeated exposure, Inhalation (Category 2), H373
Acute aquatic toxicity (Category 3), H402
Chronic aquatic toxicity (Category 3), H412

For the full text of the H-Statements mentioned in this Section, see Section 16.

2.2 GHS Label elements, including precautionary statements

Pictogram

Signal word Danger

Hazard statement(s)
H350 May cause cancer.
H373 May cause damage to organs through prolonged or repeated exposure if inhaled.
H412 Harmful to aquatic life with long lasting effects.

Precautionary statement(s)
P201 Obtain special instructions before use.
P202 Do not handle until all safety precautions have been read and understood.
P260 Do not breathe dust/ fume/ gas/ mist/ vapours/ spray.
P273 Avoid release to the environment.
P281 Use personal protective equipment as required.
P308 + P313 IF exposed or concerned: Get medical advice/ attention.

P405	Store locked up.
P501	Dispose of contents/ container to an approved waste disposal plant.

2.3 Hazards not otherwise classified (HNOC) or not covered by GHS - none

3. COMPOSITION/INFORMATION ON INGREDIENTS

3.2 Mixtures

Hazardous components

Component		Classification	Concentration
Quartz			
CAS-No. EC-No.	14808-60-7 238-878-4	Carc. 2; STOT RE 2; H351, H373	>= 90 - <= 100 %
Chlordane			
CAS-No. EC-No. Index-No.	57-74-9 200-349-0 602-047-00-8	Acute Tox. 3; Carc. 2; Aquatic Acute 1; Aquatic Chronic 1; H301 + H311, H351, H410	< 0.1 %

For the full text of the H-Statements mentioned in this Section, see Section 16.

4. FIRST AID MEASURES

4.1 Description of first aid measures

General advice
Consult a physician. Show this safety data sheet to the doctor in attendance.Move out of dangerous area.

If inhaled
If breathed in, move person into fresh air. If not breathing, give artificial respiration. Consult a physician.

In case of skin contact
Wash off with soap and plenty of water. Consult a physician.

In case of eye contact
Flush eyes with water as a precaution.

If swallowed
Never give anything by mouth to an unconscious person. Rinse mouth with water. Consult a physician.

4.2 Most important symptoms and effects, both acute and delayed
The most important known symptoms and effects are described in the labelling (see section 2.2) and/or in section 11

4.3 Indication of any immediate medical attention and special treatment needed
No data available

5. FIREFIGHTING MEASURES

5.1 Extinguishing media

Suitable extinguishing media
Use water spray, alcohol-resistant foam, dry chemical or carbon dioxide.

5.2 Special hazards arising from the substance or mixture
silicon oxides

5.3 Advice for firefighters
Wear self-contained breathing apparatus for firefighting if necessary.

5.4 Further information
No data available

6. ACCIDENTAL RELEASE MEASURES

6.1 Personal precautions, protective equipment and emergency procedures

Use personal protective equipment. Avoid dust formation. Avoid breathing vapours, mist or gas. Ensure adequate ventilation. Evacuate personnel to safe areas. Avoid breathing dust.
For personal protection see section 8.

6.2 Environmental precautions

Prevent further leakage or spillage if safe to do so. Do not let product enter drains. Discharge into the environment must be avoided.

6.3 Methods and materials for containment and cleaning up

Pick up and arrange disposal without creating dust. Sweep up and shovel. Keep in suitable, closed containers for disposal.

6.4 Reference to other sections

For disposal see section 13.

7. HANDLING AND STORAGE

7.1 Precautions for safe handling

Avoid contact with skin and eyes. Avoid formation of dust and aerosols.Further processing of solid materials may result in the formation of combustible dusts. The potential for combustible dust formation should be taken into consideration before additional processing occurs.
Provide appropriate exhaust ventilation at places where dust is formed.
For precautions see section 2.2.

7.2 Conditions for safe storage, including any incompatibilities

Keep container tightly closed in a dry and well-ventilated place.

Store at Room Temperature.
Storage class (TRGS 510): Non Combustible Solids

7.3 Specific end use(s)

Apart from the uses mentioned in section 1.2 no other specific uses are stipulated

8. EXPOSURE CONTROLS/PERSONAL PROTECTION

8.1 Control parameters

Components with workplace control parameters

Component	CAS-No.	Value	Control parameters	Basis
Quartz	14808-60-7	TWA	0.025 mg/m3	USA. ACGIH Threshold Limit Values (TLV)
	Remarks	Suspected human carcinogen		
		TWA	0.025 mg/m3	USA. ACGIH Threshold Limit Values (TLV)
		Lung cancer Pulmonary fibrosis Suspected human carcinogen		

8.2 Exposure controls

Appropriate engineering controls

Handle in accordance with good industrial hygiene and safety practice. Wash hands before breaks and at the end of workday.

Personal protective equipment

Eye/face protection

Safety glasses with side-shields conforming to EN166 Use equipment for eye protection tested and approved under appropriate government standards such as NIOSH (US) or EN 166(EU).

Skin protection
Handle with gloves. Gloves must be inspected prior to use. Use proper glove removal technique (without touching glove's outer surface) to avoid skin contact with this product. Dispose of contaminated gloves after use in accordance with applicable laws and good laboratory practices. Wash and dry hands.

Body Protection
Complete suit protecting against chemicals, The type of protective equipment must be selected according to the concentration and amount of the dangerous substance at the specific workplace.

Respiratory protection
For nuisance exposures use type P95 (US) or type P1 (EU EN 143) particle respirator.For higher level protection use type OV/AG/P99 (US) or type ABEK-P2 (EU EN 143) respirator cartridges. Use respirators and components tested and approved under appropriate government standards such as NIOSH (US) or CEN (EU).

Control of environmental exposure
Prevent further leakage or spillage if safe to do so. Do not let product enter drains. Discharge into the environment must be avoided.

9. PHYSICAL AND CHEMICAL PROPERTIES

9.1 Information on basic physical and chemical properties

a)	Appearance	Form: solid
b)	Odour	No data available
c)	Odour Threshold	No data available
d)	pH	No data available
e)	Melting point/freezing point	No data available
f)	Initial boiling point and boiling range	No data available
g)	Flash point	No data available
h)	Evaporation rate	No data available
i)	Flammability (solid, gas)	No data available
j)	Upper/lower flammability or explosive limits	No data available
k)	Vapour pressure	No data available
l)	Vapour density	No data available
m)	Relative density	No data available
n)	Water solubility	No data available
o)	Partition coefficient: n-octanol/water	No data available
p)	Auto-ignition temperature	No data available
q)	Decomposition temperature	No data available
r)	Viscosity	No data available
s)	Explosive properties	No data available
t)	Oxidizing properties	No data available

9.2 Other safety information
No data available

10. STABILITY AND REACTIVITY

10.1 Reactivity
No data available

10.2 Chemical stability
Stable under recommended storage conditions.

10.3 Possibility of hazardous reactions
No data available

10.4 Conditions to avoid
No data available

10.5 Incompatible materials
Strong oxidizing agents

10.6 Hazardous decomposition products
Other decomposition products - No data available
In the event of fire: see section 5

11. TOXICOLOGICAL INFORMATION

11.1 Information on toxicological effects

Acute toxicity
No data available

Inhalation: No data available

Dermal: No data available

No data available

Skin corrosion/irritation
No data available

Serious eye damage/eye irritation
No data available

Respiratory or skin sensitisation
No data available

Germ cell mutagenicity
No data available

Carcinogenicity

IARC:	1 - Group 1: Carcinogenic to humans (Quartz)
ACGIH:	No component of this product present at levels greater than or equal to 0.1% is identified as a carcinogen or potential carcinogen by ACGIH.
NTP:	Known to be human carcinogen (Quartz)
OSHA:	No component of this product present at levels greater than or equal to 0.1% is identified as a carcinogen or potential carcinogen by OSHA.

Reproductive toxicity
No data available
No data available

Specific target organ toxicity - single exposure
No data available

Specific target organ toxicity - repeated exposure
No data available

Aspiration hazard
No data available

Additional Information
RTECS: Not available

To the best of our knowledge, the chemical, physical, and toxicological properties have not been thoroughly investigated.

Liver - Irregularities - Based on Human Evidence
Liver - Irregularities - Based on Human Evidence
Nerves. - (Chlordane)

12. ECOLOGICAL INFORMATION

12.1 Toxicity
No data available

12.2 Persistence and degradability
No data available

12.3 Bioaccumulative potential
No data available

12.4 Mobility in soil
No data available

12.5 Results of PBT and vPvB assessment
PBT/vPvB assessment not available as chemical safety assessment not required/not conducted

12.6 Other adverse effects
An environmental hazard cannot be excluded in the event of unprofessional handling or disposal.
Harmful to aquatic life with long lasting effects.

13. DISPOSAL CONSIDERATIONS

13.1 Waste treatment methods

Product
Offer surplus and non-recyclable solutions to a licensed disposal company. Contact a licensed professional waste disposal service to dispose of this material. Dissolve or mix the material with a combustible solvent and burn in a chemical incinerator equipped with an afterburner and scrubber.

Contaminated packaging
Dispose of as unused product.

14. TRANSPORT INFORMATION

DOT (US)
Not dangerous goods

IMDG
Not dangerous goods

IATA
Not dangerous goods

15. REGULATORY INFORMATION

SARA 302 Components
No chemicals in this material are subject to the reporting requirements of SARA Title III, Section 302.

SARA 313 Components
This material does not contain any chemical components with known CAS numbers that exceed the threshold (De Minimis) reporting levels established by SARA Title III, Section 313.

SARA 311/312 Hazards
Chronic Health Hazard

Massachusetts Right To Know Components

CAS-No. Revision Date

Quartz	14808-60-7	1994-04-01
Chlordane	57-74-9	2007-07-01

Pennsylvania Right To Know Components

	CAS-No.	Revision Date
Quartz	14808-60-7	1994-04-01
Chlordane	57-74-9	2007-07-01

New Jersey Right To Know Components

	CAS-No.	Revision Date
Quartz	14808-60-7	1994-04-01

California Prop. 65 Components

WARNING! This product contains a chemical known to the State of California to cause cancer.	CAS-No.	Revision Date
Chlordane	57-74-9	2007-09-28
Quartz	14808-60-7	2007-09-28

16. OTHER INFORMATION

Full text of H-Statements referred to under sections 2 and 3.

Acute Tox.	Acute toxicity
Aquatic Acute	Acute aquatic toxicity
Aquatic Chronic	Chronic aquatic toxicity
Carc.	Carcinogenicity
H301 + H311	Toxic if swallowed or in contact with skin
H350	May cause cancer.
H351	Suspected of causing cancer.
H373	May cause damage to organs through prolonged or repeated exposure if inhaled.
H402	Harmful to aquatic life.
H410	Very toxic to aquatic life with long lasting effects.
H412	Harmful to aquatic life with long lasting effects.
STOT RE	Specific target organ toxicity - repeated exposure

HMIS Rating

Health hazard:	0
Chronic Health Hazard:	*
Flammability:	0
Physical Hazard	0

NFPA Rating

Health hazard:	0
Fire Hazard:	0
Reactivity Hazard:	0

Further information

Copyright 2015 Sigma-Aldrich Co. LLC. License granted to make unlimited paper copies for internal use only.
The above information is believed to be correct but does not purport to be all inclusive and shall be used only as a guide. The information in this document is based on the present state of our knowledge and is applicable to the product with regard to appropriate safety precautions. It does not represent any guarantee of the properties of the product. Sigma-Aldrich Corporation and its Affiliates shall not be held liable for any damage resulting from handling or from contact with the above product. See www.sigma-aldrich.com and/or the reverse side of invoice or packing slip for additional terms and conditions of sale.

Preparation Information

Sigma-Aldrich Corporation
Product Safety – Americas Region
1-800-521-8956

Version: 5.4 Revision Date: 04/21/2015 Print Date: 05/13/2016

SAFETY DATA SHEET

Methyl Chloride (R40)

Section 1. Identification

GHS product identifier : Methyl Chloride (R40)

Chemical name : chloromethane

Other means of identification : methyl chloride; Methane, chloro-; Methane, chloro- (methyl chloride)

Product use : Synthetic/Analytical chemistry.

Synonym : methyl chloride; Methane, chloro-; Methane, chloro- (methyl chloride)

SDS # : 001036

Supplier's details : Airgas USA, LLC and its affiliates
259 North Radnor-Chester Road
Suite 100
Radnor, PA 19087-5283
1-610-687-5253

Emergency telephone number (with hours of operation) : 1-866-734-3438

Section 2. Hazards identification

OSHA/HCS status : This material is considered hazardous by the OSHA Hazard Communication Standard (29 CFR 1910.1200).

Classification of the substance or mixture : FLAMMABLE GASES - Category 1
GASES UNDER PRESSURE - Liquefied gas
ACUTE TOXICITY (inhalation) - Category 4
CARCINOGENICITY - Category 2
SPECIFIC TARGET ORGAN TOXICITY (REPEATED EXPOSURE) (central nervous system (CNS)) - Category 2

GHS label elements

Hazard pictograms :

Signal word : Danger

Hazard statements : Extremely flammable gas.
May form explosive mixtures with air.
Contains gas under pressure; may explode if heated.
May cause frostbite.
May displace oxygen and cause rapid suffocation.
Harmful if inhaled.
Suspected of causing cancer.
May cause damage to organs through prolonged or repeated exposure. (central nervous system (CNS))

Precautionary statements

Powered by IHS

Section 2. Hazards identification

General : Read and follow all Safety Data Sheets (SDS'S) before use. Read label before use. Keep out of reach of children. If medical advice is needed, have product container or label at hand. Close valve after each use and when empty. Use equipment rated for cylinder pressure. Do not open valve until connected to equipment prepared for use. Use a back flow preventative device in the piping. Use only equipment of compatible materials of construction. Always keep container in upright position. Approach suspected leak area with caution.

Prevention : Never Put cylinders into unventilated areas of passenger vehicles. Obtain special instructions before use. Do not handle until all safety precautions have been read and understood. Use personal protective equipment as required. Keep away from heat, sparks, open flames and hot surfaces. - No smoking. Use only outdoors or in a well-ventilated area. Do not breathe gas. Use and store only outdoors or in a well ventilated place.

Response : Get medical attention if you feel unwell. IF exposed or concerned: Get medical attention. IF INHALED: Remove victim to fresh air and keep at rest in a position comfortable for breathing. Call a POISON CENTER or physician if you feel unwell. Leaking gas fire: Do not extinguish, unless leak can be stopped safely. Eliminate all ignition sources if safe to do so.

Storage : Store locked up. Protect from sunlight. Protect from sunlight when ambient temperature exceeds 52°C/125°F. Store in a well-ventilated place.

Disposal : Dispose of contents and container in accordance with all local, regional, national and international regulations.

Hazards not otherwise classified : Liquid can cause burns similar to frostbite.

Section 3. Composition/information on ingredients

Substance/mixture : Substance

Chemical name : chloromethane

Other means of identification : methyl chloride; Methane, chloro-; Methane, chloro- (methyl chloride)

CAS number/other identifiers

CAS number : 74-87-3

Product code : 001036

Ingredient name	%	CAS number
chloromethane	100	74-87-3

There are no additional ingredients present which, within the current knowledge of the supplier and in the concentrations applicable, are classified as hazardous to health or the environment and hence require reporting in this section.

Occupational exposure limits, if available, are listed in Section 8.

Section 4. First aid measures

Description of necessary first aid measures

Eye contact : Immediately flush eyes with plenty of water, occasionally lifting the upper and lower eyelids. Check for and remove any contact lenses. Continue to rinse for at least 10 minutes. Get medical attention.

Powered by IHS

Section 4. First aid measures

Inhalation : Remove victim to fresh air and keep at rest in a position comfortable for breathing. If it is suspected that fumes are still present, the rescuer should wear an appropriate mask or self-contained breathing apparatus. If not breathing, if breathing is irregular or if respiratory arrest occurs, provide artificial respiration or oxygen by trained personnel. It may be dangerous to the person providing aid to give mouth-to-mouth resuscitation. Get medical attention. If necessary, call a poison center or physician. If unconscious, place in recovery position and get medical attention immediately. Maintain an open airway. Loosen tight clothing such as a collar, tie, belt or waistband. In case of inhalation of decomposition products in a fire, symptoms may be delayed. The exposed person may need to be kept under medical surveillance for 48 hours.

Skin contact : Flush contaminated skin with plenty of water. Remove contaminated clothing and shoes. To avoid the risk of static discharges and gas ignition, soak contaminated clothing thoroughly with water before removing it. Continue to rinse for at least 10 minutes. Get medical attention. In case of contact with liquid, warm frozen tissues slowly with lukewarm water and get medical attention. Do not rub affected area. Wash clothing before reuse. Clean shoes thoroughly before reuse.

Ingestion : Remove victim to fresh air and keep at rest in a position comfortable for breathing. Get medical attention. Ingestion of liquid can cause burns similar to frostbite. If frostbite occurs, get medical attention. Never give anything by mouth to an unconscious person. If unconscious, place in recovery position and get medical attention immediately. Maintain an open airway. Loosen tight clothing such as a collar, tie, belt or waistband. As this product rapidly becomes a gas when released, refer to the inhalation section.

Most important symptoms/effects, acute and delayed

Potential acute health effects

Eye contact : Liquid can cause burns similar to frostbite.

Inhalation : Harmful if inhaled. Exposure to decomposition products may cause a health hazard. Serious effects may be delayed following exposure.

Skin contact : Dermal contact with rapidly evaporating liquid could result in freezing of the tissues or frostbite.

Frostbite : Try to warm up the frozen tissues and seek medical attention.

Ingestion : Ingestion of liquid can cause burns similar to frostbite.

Over-exposure signs/symptoms

Eye contact : Adverse symptoms may include the following:
frostbite

Inhalation : No specific data.

Skin contact : Adverse symptoms may include the following:
frostbite

Ingestion : Adverse symptoms may include the following:
frostbite

Indication of immediate medical attention and special treatment needed, if necessary

Notes to physician : In case of inhalation of decomposition products in a fire, symptoms may be delayed. The exposed person may need to be kept under medical surveillance for 48 hours.

Specific treatments : No specific treatment.

Protection of first-aiders : No action shall be taken involving any personal risk or without suitable training. If it is suspected that fumes are still present, the rescuer should wear an appropriate mask or self-contained breathing apparatus. It may be dangerous to the person providing aid to give mouth-to-mouth resuscitation.

See toxicological information (Section 11)

Powered by IHS

Section 5. Fire-fighting measures

Extinguishing media

Suitable extinguishing media : Use an extinguishing agent suitable for the surrounding fire.

Unsuitable extinguishing media : None known.

Specific hazards arising from the chemical : Contains gas under pressure. Extremely flammable gas. In a fire or if heated, a pressure increase will occur and the container may burst, with the risk of a subsequent explosion. The vapor/gas is heavier than air and will spread along the ground. Gas may accumulate in low or confined areas or travel a considerable distance to a source of ignition and flash back, causing fire or explosion.

Hazardous thermal decomposition products : Decomposition products may include the following materials:
carbon dioxide
carbon monoxide
halogenated compounds
carbonyl halides

Special protective actions for fire-fighters : Promptly isolate the scene by removing all persons from the vicinity of the incident if there is a fire. No action shall be taken involving any personal risk or without suitable training. Contact supplier immediately for specialist advice. Move containers from fire area if this can be done without risk. Use water spray to keep fire-exposed containers cool. If involved in fire, shut off flow immediately if it can be done without risk. If this is impossible, withdraw from area and allow fire to burn. Fight fire from protected location or maximum possible distance. Eliminate all ignition sources if safe to do so.

Special protective equipment for fire-fighters : Fire-fighters should wear appropriate protective equipment and self-contained breathing apparatus (SCBA) with a full face-piece operated in positive pressure mode. For incidents involving large quantities, thermally insulated undergarments and thick textile or leather gloves should be worn.

Section 6. Accidental release measures

Personal precautions, protective equipment and emergency procedures

For non-emergency personnel : Accidental releases pose a serious fire or explosion hazard. No action shall be taken involving any personal risk or without suitable training. Evacuate surrounding areas. Keep unnecessary and unprotected personnel from entering. Do not touch or walk through spilled material. Shut off all ignition sources. No flares, smoking or flames in hazard area. Avoid breathing gas. Provide adequate ventilation. Wear appropriate respirator when ventilation is inadequate. Put on appropriate personal protective equipment.

For emergency responders : If specialised clothing is required to deal with the spillage, take note of any information in Section 8 on suitable and unsuitable materials. See also the information in "For non-emergency personnel".

Environmental precautions : Ensure emergency procedures to deal with accidental gas releases are in place to avoid contamination of the environment. Avoid dispersal of spilled material and runoff and contact with soil, waterways, drains and sewers. Inform the relevant authorities if the product has caused environmental pollution (sewers, waterways, soil or air).

Methods and materials for containment and cleaning up

Small spill : Immediately contact emergency personnel. Stop leak if without risk. Use spark-proof tools and explosion-proof equipment.

Large spill : Immediately contact emergency personnel. Stop leak if without risk. Use spark-proof tools and explosion-proof equipment. Note: see Section 1 for emergency contact information and Section 13 for waste disposal.

Powered by IHS

Section 7. Handling and storage

Precautions for safe handling

Protective measures : Put on appropriate personal protective equipment (see Section 8). Contains gas under pressure. Avoid exposure - obtain special instructions before use. Do not handle until all safety precautions have been read and understood. Do not get in eyes or on skin or clothing. Do not breathe gas. Use only with adequate ventilation. Wear appropriate respirator when ventilation is inadequate. Do not enter storage areas and confined spaces unless adequately ventilated. Store and use away from heat, sparks, open flame or any other ignition source. Use explosion-proof electrical (ventilating, lighting and material handling) equipment. Use only non-sparking tools. Empty containers retain product residue and can be hazardous. Do not puncture or incinerate container. Use equipment rated for cylinder pressure. Close valve after each use and when empty. Protect cylinders from physical damage; do not drag, roll, slide, or drop. Use a suitable hand truck for cylinder movement.

Advice on general occupational hygiene : Eating, drinking and smoking should be prohibited in areas where this material is handled, stored and processed. Workers should wash hands and face before eating, drinking and smoking. Remove contaminated clothing and protective equipment before entering eating areas. See also Section 8 for additional information on hygiene measures.

Conditions for safe storage, including any incompatibilities : Store in accordance with local regulations. Store in a segregated and approved area. Store away from direct sunlight in a dry, cool and well-ventilated area, away from incompatible materials (see Section 10). Store locked up. Eliminate all ignition sources. Keep container tightly closed and sealed until ready for use. Cylinders should be stored upright, with valve protection cap in place, and firmly secured to prevent falling or being knocked over. Cylinder temperatures should not exceed 52 °C (125 °F).

Section 8. Exposure controls/personal protection

Control parameters

Occupational exposure limits

Ingredient name	Exposure limits
chloromethane	**ACGIH TLV (United States, 3/2012).** **Absorbed through skin.** TWA: 50 ppm 8 hours. TWA: 103 mg/m³ 8 hours. STEL: 100 ppm 15 minutes. STEL: 207 mg/m³ 15 minutes. **OSHA PEL 1989 (United States, 3/1989).** TWA: 50 ppm 8 hours. TWA: 105 mg/m³ 8 hours. STEL: 100 ppm 15 minutes. STEL: 210 mg/m³ 15 minutes. **OSHA PEL Z2 (United States, 11/2006).** TWA: 100 ppm 8 hours. CEIL: 200 ppm AMP: 300 ppm 5 minutes.

Appropriate engineering controls : Use only with adequate ventilation. Use process enclosures, local exhaust ventilation or other engineering controls to keep worker exposure to airborne contaminants below any recommended or statutory limits. The engineering controls also need to keep gas, vapor or dust concentrations below any lower explosive limits. Use explosion-proof ventilation equipment.

Powered by IHS

Section 8. Exposure controls/personal protection

Environmental exposure controls : Emissions from ventilation or work process equipment should be checked to ensure they comply with the requirements of environmental protection legislation. In some cases, fume scrubbers, filters or engineering modifications to the process equipment will be necessary to reduce emissions to acceptable levels.

Individual protection measures

Hygiene measures : Wash hands, forearms and face thoroughly after handling chemical products, before eating, smoking and using the lavatory and at the end of the working period. Appropriate techniques should be used to remove potentially contaminated clothing. Wash contaminated clothing before reusing. Ensure that eyewash stations and safety showers are close to the workstation location.

Eye/face protection : Safety eyewear complying with an approved standard should be used when a risk assessment indicates this is necessary to avoid exposure to liquid splashes, mists, gases or dusts. If contact is possible, the following protection should be worn, unless the assessment indicates a higher degree of protection: safety glasses with side-shields.

Skin protection

Hand protection : Chemical-resistant, impervious gloves complying with an approved standard should be worn at all times when handling chemical products if a risk assessment indicates this is necessary. If contact with the liquid is possible, insulated gloves suitable for low temperatures should be worn. Considering the parameters specified by the glove manufacturer, check during use that the gloves are still retaining their protective properties. It should be noted that the time to breakthrough for any glove material may be different for different glove manufacturers. In the case of mixtures, consisting of several substances, the protection time of the gloves cannot be accurately estimated.

Body protection : Personal protective equipment for the body should be selected based on the task being performed and the risks involved and should be approved by a specialist before handling this product. When there is a risk of ignition from static electricity, wear anti-static protective clothing. For the greatest protection from static discharges, clothing should include anti-static overalls, boots and gloves.

Other skin protection : Appropriate footwear and any additional skin protection measures should be selected based on the task being performed and the risks involved and should be approved by a specialist before handling this product.

Respiratory protection : Use a properly fitted, air-purifying or air-fed respirator complying with an approved standard if a risk assessment indicates this is necessary. Respirator selection must be based on known or anticipated exposure levels, the hazards of the product and the safe working limits of the selected respirator.

Section 9. Physical and chemical properties

Appearance

Physical state : Gas. [Liquefied compressed gas.]

Color : Colorless.

Molecular weight : 50.49 g/mole

Molecular formula : C-H3-Cl

Boiling/condensation point : -23.7°C (-10.7°F)

Melting/freezing point : -97°C (-142.6°F)

Critical temperature : 143.65°C (290.6°F)

Odor : Mild. Sweetish.

Odor threshold : Not available.

pH : Not available.

Flash point : Closed cup: 10°C (50°F)

Powered by IHS

Section 9. Physical and chemical properties

Burning time : Not applicable.

Burning rate : Not applicable.

Evaporation rate : Not available.

Flammability (solid, gas) : Extremely flammable in the presence of the following materials or conditions: open flames, sparks and static discharge and oxidizing materials.

Lower and upper explosive (flammable) limits : Lower: 8.1%
Upper: 17.4%

Vapor pressure : 58.7 (psig)

Vapor density : 1.8 (Air = 1)

Specific Volume (ft^3/lb) : 1.0977

Gas Density (lb/ft^3) : 0.911 (25°C / 77 to °F)

Relative density : Not applicable.

Solubility : Not available.

Solubility in water : 5.32 g/l

Partition coefficient: n-octanol/water : 0.91

Auto-ignition temperature : 632°C (1169.6°F)

Decomposition temperature : Not available.

SADT : Not available.

Viscosity : Not applicable.

Section 10. Stability and reactivity

Reactivity : No specific test data related to reactivity available for this product or its ingredients.

Chemical stability : The product is stable.

Possibility of hazardous reactions : Under normal conditions of storage and use, hazardous reactions will not occur.

Conditions to avoid : Avoid all possible sources of ignition (spark or flame). Do not pressurize, cut, weld, braze, solder, drill, grind or expose containers to heat or sources of ignition. Do not allow gas to accumulate in low or confined areas.

Incompatibility with various substances : Extremely reactive or incompatible with the following materials: oxidizing materials.

Hazardous decomposition products : Under normal conditions of storage and use, hazardous decomposition products should not be produced.

Hazardous polymerization : Under normal conditions of storage and use, hazardous polymerization will not occur.

Powered by IHS

Section 11. Toxicological information

Information on toxicological effects

Acute toxicity

Product/ingredient name	Result	Species	Dose	Exposure
chloromethane	LC50 Inhalation Gas.	Rat	8300 ppm	4 hours

Irritation/Corrosion

Not available.

Sensitization

Not available.

Mutagenicity

Not available.

Carcinogenicity

Not available.

Classification

Product/ingredient name	OSHA	IARC	NTP
chloromethane	-	3	-

Reproductive toxicity

Not available.

Teratogenicity

Not available.

Specific target organ toxicity (single exposure)

Not available.

Specific target organ toxicity (repeated exposure)

Name	Category	Route of exposure	Target organs
chloromethane	Category 2	Not determined	central nervous system (CNS)

Aspiration hazard

Not available.

Information on the likely routes of exposure : Not available.

Potential acute health effects

Eye contact : Liquid can cause burns similar to frostbite.

Inhalation : Harmful if inhaled. Exposure to decomposition products may cause a health hazard. Serious effects may be delayed following exposure.

Skin contact : Dermal contact with rapidly evaporating liquid could result in freezing of the tissues or frostbite.

Ingestion : Ingestion of liquid can cause burns similar to frostbite.

Symptoms related to the physical, chemical and toxicological characteristics

Eye contact : Adverse symptoms may include the following:
frostbite

Powered by IHS

Section 11. Toxicological information

Inhalation : No specific data.

Skin contact : Adverse symptoms may include the following:
frostbite

Ingestion : Adverse symptoms may include the following:
frostbite

Delayed and immediate effects and also chronic effects from short and long term exposure

Short term exposure

Potential immediate effects : Not available.

Potential delayed effects : Not available.

Long term exposure

Potential immediate effects : Not available.

Potential delayed effects : Not available.

Potential chronic health effects

Not available.

General : May cause damage to organs through prolonged or repeated exposure.

Carcinogenicity : Suspected of causing cancer. Risk of cancer depends on duration and level of exposure.

Mutagenicity : No known significant effects or critical hazards.

Teratogenicity : No known significant effects or critical hazards.

Developmental effects : No known significant effects or critical hazards.

Fertility effects : No known significant effects or critical hazards.

Numerical measures of toxicity

Acute toxicity estimates

Not available.

Section 12. Ecological information

Toxicity

Product/ingredient name	Result	Species	Exposure
chloromethane	Acute LC50 270000 µg/l Marine water	Fish - Menidia beryllina	96 hours

Persistence and degradability

Not available.

Bioaccumulative potential

Product/ingredient name	$LogP_{ow}$	BCF	Potential
chloromethane	0.91	-	low

Mobility in soil

Powered by IHS

Section 12. Ecological information

Soil/water partition coefficient (K_{OC}) : Not available.

Other adverse effects : No known significant effects or critical hazards.

Section 13. Disposal considerations

Disposal methods : The generation of waste should be avoided or minimized wherever possible. Disposal of this product, solutions and any by-products should at all times comply with the requirements of environmental protection and waste disposal legislation and any regional local authority requirements. Dispose of surplus and non-recyclable products via a licensed waste disposal contractor. Waste should not be disposed of untreated to the sewer unless fully compliant with the requirements of all authorities with jurisdiction. Empty Airgas-owned pressure vessels should be returned to Airgas. Waste packaging should be recycled. Incineration or landfill should only be considered when recycling is not feasible. This material and its container must be disposed of in a safe way. Empty containers or liners may retain some product residues. Do not puncture or incinerate container.

United States - RCRA Toxic hazardous waste "U" List

Ingredient	CAS #	Status	Reference number
Methyl chloride (I,T); Methane, chloro- (I, T)	74-87-3	Listed	U045

Section 14. Transport information

	DOT	TDG	Mexico	IMDG	IATA
UN number	UN1063	UN1063	UN1063	UN1063	UN1063
UN proper shipping name	METHYL CHLORIDE, OR REFRIGERANT GAS R 40	METHYL CHLORIDE; OR REFRIGERANT GAS R 40	METHYL CHLORIDE, OR REFRIGERANT GAS R 40	METHYL CHLORIDE (REFRIGERANT GAS R 40)	METHYL CHLORIDE
Transport hazard class(es)	2.1	2.1	2.1	2.1	2.1
Packing group	-	-	-	-	-
Environment	No.	No.	No.	No.	No.
Additional information	**Reportable quantity** 100 lbs / 45.4 kg Package sizes shipped in quantities less than the product reportable quantity are not subject to the RQ (reportable quantity) transportation requirements. **Limited quantity** Yes. **Packaging instruction** **Passenger aircraft** Quantity limitation: 5 kg **Cargo aircraft** Quantity limitation: 100 kg	**Explosive Limit and Limited Quantity Index** 0.125 **ERAP Index** 3000 **Passenger Carrying Ship Index** Forbidden **Passenger Carrying Road or Rail Index** Forbidden	-	-	**Passenger and Cargo Aircraft** Quantity limitation: 0 Forbidden **Cargo Aircraft Only** Quantity limitation: 100 kg

Powered by IHS

Section 14. Transport information

	Special provisions T50				

"Refer to CFR 49 (or authority having jurisdiction) to determine the information required for shipment of the product."

Special precautions for user : **Transport within user's premises:** always transport in closed containers that are upright and secure. Ensure that persons transporting the product know what to do in the event of an accident or spillage.

Transport in bulk according to Annex II of MARPOL 73/78 and the IBC Code : Not available.

Section 15. Regulatory information

U.S. Federal regulations : **TSCA 8(a) CDR Exempt/Partial exemption**: Not determined

United States inventory (TSCA 8b): This material is listed or exempted.

Clean Water Act (CWA) 307: chloromethane

Clean Air Act (CAA) 112 regulated toxic substances: chloromethane

Clean Air Act Section 112 (b) Hazardous Air Pollutants (HAPs) : Listed

Clean Air Act Section 602 Class I Substances : Not listed

Clean Air Act Section 602 Class II Substances : Not listed

DEA List I Chemicals (Precursor Chemicals) : Not listed

DEA List II Chemicals (Essential Chemicals) : Not listed

SARA 302/304

Composition/information on ingredients

No products were found.

SARA 304 RQ : Not applicable.

SARA 311/312

Classification : Fire hazard
Sudden release of pressure
Immediate (acute) health hazard
Delayed (chronic) health hazard

Composition/information on ingredients

Name	%	Fire hazard	Sudden release of pressure	Reactive	Immediate (acute) health hazard	Delayed (chronic) health hazard
chloromethane	100	Yes.	Yes.	No.	Yes.	Yes.

SARA 313

Powered by IHS

Section 15. Regulatory information

	Product name	CAS number	%
Form R - Reporting requirements	chloromethane	74-87-3	100
Supplier notification	chloromethane	74-87-3	100

SARA 313 notifications must not be detached from the SDS and any copying and redistribution of the SDS shall include copying and redistribution of the notice attached to copies of the SDS subsequently redistributed.

State regulations

Massachusetts : This material is listed.

New York : This material is listed.

New Jersey : This material is listed.

Pennsylvania : This material is listed.

California Prop. 65

WARNING: This product contains a chemical known to the State of California to cause birth defects or other reproductive harm.

Ingredient name	Cancer	Reproductive	No significant risk level	Maximum acceptable dosage level
chloromethane	No.	Yes.	No.	No.

Canada inventory : This material is listed or exempted.

International regulations

International lists : **Australia inventory (AICS)**: This material is listed or exempted.
China inventory (IECSC): This material is listed or exempted.
Japan inventory: This material is listed or exempted.
Korea inventory: This material is listed or exempted.
Malaysia Inventory (EHS Register): Not determined.
New Zealand Inventory of Chemicals (NZIoC): This material is listed or exempted.
Philippines inventory (PICCS): This material is listed or exempted.
Taiwan inventory (CSNN): Not determined.

Chemical Weapons Convention List Schedule I Chemicals : Not listed

Chemical Weapons Convention List Schedule II Chemicals : Not listed

Chemical Weapons Convention List Schedule III Chemicals : Not listed

Canada

WHMIS (Canada) : Class A: Compressed gas.
Class B-1: Flammable gas.
Class B-6: Reactive flammable material
Class D-2A: Material causing other toxic effects (Very toxic).

CEPA Toxic substances: This material is not listed.
Canadian ARET: This material is not listed.
Canadian NPRI: This material is listed.
Alberta Designated Substances: This material is not listed.
Ontario Designated Substances: This material is not listed.
Quebec Designated Substances: This material is not listed.

Powered by IHS

Section 16. Other information

Canada Label requirements : Class A: Compressed gas.
Class B-1: Flammable gas.
Class B-6: Reactive flammable material
Class D-2A: Material causing other toxic effects (Very toxic).

Hazardous Material Information System (U.S.A.)

Health	*	2
Flammability		4
Physical hazards		2

Caution: HMIS® ratings are based on a 0-4 rating scale, with 0 representing minimal hazards or risks, and 4 representing significant hazards or risks Although HMIS® ratings are not required on SDSs under 29 CFR 1910. 1200, the preparer may choose to provide them. HMIS® ratings are to be used with a fully implemented HMIS® program. HMIS® is a registered mark of the National Paint & Coatings Association (NPCA). HMIS® materials may be purchased exclusively from J. J. Keller (800) 327-6868.

The customer is responsible for determining the PPE code for this material.

National Fire Protection Association (U.S.A.)

Reprinted with permission from NFPA 704-2001, Identification of the Hazards of Materials for Emergency Response Copyright ©1997, National Fire Protection Association, Quincy, MA 02269. This reprinted material is not the complete and official position of the National Fire Protection Association, on the referenced subject which is represented only by the standard in its entirety.

Copyright ©2001, National Fire Protection Association, Quincy, MA 02269. This warning system is intended to be interpreted and applied only by properly trained individuals to identify fire, health and reactivity hazards of chemicals. The user is referred to certain limited number of chemicals with recommended classifications in NFPA 49 and NFPA 325, which would be used as a guideline only. Whether the chemicals are classified by NFPA or not, anyone using the 704 systems to classify chemicals does so at their own risk.

History

Date of printing : 5/20/2015.

Date of issue/Date of revision : 5/20/2015.

Date of previous issue : 10/15/2014.

Version : 0.03

Key to abbreviations : ATE = Acute Toxicity Estimate
BCF = Bioconcentration Factor
GHS = Globally Harmonized System of Classification and Labelling of Chemicals
IATA = International Air Transport Association
IBC = Intermediate Bulk Container
IMDG = International Maritime Dangerous Goods
LogPow = logarithm of the octanol/water partition coefficient
MARPOL 73/78 = International Convention for the Prevention of Pollution From Ships, 1973 as modified by the Protocol of 1978. ("Marpol" = marine pollution)
UN = United NationsACGIH – American Conference of Governmental Industrial Hygienists
AIHA – American Industrial Hygiene Association
CAS – Chemical Abstract Services
CEPA – Canadian Environmental Protection Act
CERCLA – Comprehensive Environmental Response, Compensation, and Liability Act

Powered by IHS

Section 16. Other information

(EPA)
CFR – United States Code of Federal Regulations
CPR – Controlled Products Regulations
DSL – Domestic Substances List
GWP – Global Warming Potential
IARC – International Agency for Research on Cancer
ICAO – International Civil Aviation Organisation
Inh – Inhalation
LC – Lethal concentration
LD – Lethal dosage
NDSL – Non-Domestic Substances List
NIOSH – National Institute for Occupational Safety and Health
TDG – Canadian Transportation of Dangerous Goods Act and Regulations
TLV – Threshold Limit Value
TSCA – Toxic Substances Control Act
WEEL – Workplace Environmental Exposure Level
WHMIS – Canadian Workplace Hazardous Material Information System

References : Not available.

Indicates information that has changed from previously issued version.

Notice to reader

To the best of our knowledge, the information contained herein is accurate. However, neither the above-named supplier, nor any of its subsidiaries, assumes any liability whatsoever for the accuracy or completeness of the information contained herein.
Final determination of suitability of any material is the sole responsibility of the user. All materials may present unknown hazards and should be used with caution. Although certain hazards are described herein, we cannot guarantee that these are the only hazards that exist.

Powered by IHS

Fisher Scientific

Part of Thermo Fisher Scientific

SAFETY DATA SHEET

Creation Date 13-Sep-2013 **Revision Date** 21-Jul-2015 **Revision Number** 2

1. Identification

Product Name **Chromium**

Cat No. : **C318-500**

Synonyms Chrome

Recommended Use Laboratory chemicals.

Uses advised against No Information available

Details of the supplier of the safety data sheet

Company
Fisher Scientific
One Reagent Lane
Fair Lawn, NJ 07410
Tel: (201) 796-7100

Emergency Telephone Number
CHEMTREC®, Inside the USA: 800-424-9300
CHEMTREC®, Outside the USA: 001-703-527-3887

2. Hazard(s) identification

Classification

This chemical is considered hazardous by the 2012 OSHA Hazard Communication Standard (29 CFR 1910.1200)

Specific target organ toxicity (single exposure) Target Organs - Respiratory system.	Category 3

Label Elements

Signal Word
Warning

Hazard Statements
May cause respiratory irritation

Precautionary Statements
Prevention
Avoid breathing dust/fume/gas/mist/vapors/spray
Use only outdoors or in a well-ventilated area

Inhalation
IF INHALED: Remove victim to fresh air and keep at rest in a position comfortable for breathing
Call a POISON CENTER or doctor/physician if you feel unwell
Storage
Store in a well-ventilated place. Keep container tightly closed
Store locked up
Disposal
Dispose of contents/container to an approved waste disposal plant
Hazards not otherwise classified (HNOC)
Very toxic to aquatic life

3. Composition / information on ingredients

Component	CAS-No	Weight %
Chromium	7440-47-3	>95

4. First-aid measures

General Advice If symptoms persist, call a physician.

Eye Contact Rinse immediately with plenty of water, also under the eyelids, for at least 15 minutes. Obtain medical attention.

Skin Contact Wash off immediately with plenty of water for at least 15 minutes. Obtain medical attention.

Inhalation Move to fresh air. If breathing is difficult, give oxygen. Obtain medical attention.

Ingestion Do not induce vomiting. Obtain medical attention.

Most important symptoms/effects None reasonably foreseeable.
Notes to Physician Treat symptomatically

5. Fire-fighting measures

Unsuitable Extinguishing Media Carbon dioxide (CO2)

Flash Point Not applicable
Method - No information available

Autoignition Temperature Not applicable
Explosion Limits
Upper No data available
Lower No data available
Sensitivity to Mechanical Impact No information available
Sensitivity to Static Discharge No information available

Specific Hazards Arising from the Chemical
Dust can form an explosive mixture in air. Do not allow run-off from fire fighting to enter drains or water courses.

Hazardous Combustion Products
Chromium oxide
Protective Equipment and Precautions for Firefighters
As in any fire, wear self-contained breathing apparatus pressure-demand, MSHA/NIOSH (approved or equivalent) and full protective gear.

NFPA

Health	Flammability	Instability	Physical hazards
2	1	1	N/A

6. Accidental release measures

Personal Precautions Ensure adequate ventilation. Use personal protective equipment. Avoid dust formation.

Environmental Precautions Do not flush into surface water or sanitary sewer system. Do not allow material to contaminate ground water system. Prevent product from entering drains. Local authorities should be advised if significant spillages cannot be contained. See Section 12 for additional ecological information. Avoid release to the environment. Collect spillage.

Methods for Containment and Clean Up Avoid dust formation. Sweep up or vacuum up spillage and collect in suitable container for disposal. Keep in suitable, closed containers for disposal.

7. Handling and storage

Handling Avoid dust formation. Wear personal protective equipment. Ensure adequate ventilation. Do not get in eyes, on skin, or on clothing. Avoid ingestion and inhalation.

Storage Keep containers tightly closed in a dry, cool and well-ventilated place. Store under an inert atmosphere.

8. Exposure controls / personal protection

Exposure Guidelines

Component	ACGIH TLV	OSHA PEL	NIOSH IDLH
Chromium	TWA: 0.5 mg/m³	(Vacated) TWA: 1 mg/m³ TWA: 1 mg/m³	IDLH: 250 mg/m³ TWA: 0.5 mg/m³

Component	Quebec	Mexico OEL (TWA)	Ontario TWAEV
Chromium	TWA: 0.5 mg/m³	TWA: 0.5 mg/m³	TWA: 0.5 mg/m³

Legend

ACGIH - American Conference of Governmental Industrial Hygienists
OSHA - Occupational Safety and Health Administration
NIOSH IDLH: The National Institute for Occupational Safety and Health Immediately Dangerous to Life or Health

Engineering Measures Ensure adequate ventilation, especially in confined areas. Ensure that eyewash stations and safety showers are close to the workstation location.

Personal Protective Equipment

Eye/face Protection Wear appropriate protective eyeglasses or chemical safety goggles as described by OSHA's eye and face protection regulations in 29 CFR 1910.133 or European Standard EN166.

Skin and body protection Wear appropriate protective gloves and clothing to prevent skin exposure.

Respiratory Protection Follow the OSHA respirator regulations found in 29 CFR 1910.134 or European Standard EN 149. Use a NIOSH/MSHA or European Standard EN 149 approved respirator if exposure limits are exceeded or if irritation or other symptoms are experienced.

Hygiene Measures Handle in accordance with good industrial hygiene and safety practice.

9. Physical and chemical properties

Physical State	Powder
Appearance	Silver
Odor	Odorless
Odor Threshold	No information available
pH	No information available
Melting Point/Range	1857.2 °C / 3375 °F

Boiling Point/Range	2640 °C / 4784 °F
Flash Point	Not applicable
Evaporation Rate	Not applicable
Flammability (solid,gas)	No information available
Flammability or explosive limits	
Upper	No data available
Lower	No data available
Vapor Pressure	No information available
Vapor Density	Not applicable
Relative Density	7.2
Solubility	Insoluble in water
Partition coefficient; n-octanol/water	No data available
Autoignition Temperature	Not applicable
Decomposition Temperature	No information available
Viscosity	Not applicable
Molecular Formula	Cr
Molecular Weight	51.996

10. Stability and reactivity

Reactive Hazard None known, based on information available

Stability Sensitive to air.

Conditions to Avoid Incompatible products. Excess heat. Avoid dust formation.

Incompatible Materials Strong oxidizing agents, Strong acids

Hazardous Decomposition Products Chromium oxide

Hazardous Polymerization Hazardous polymerization does not occur.

Hazardous Reactions None under normal processing.

11. Toxicological information

Acute Toxicity

Component Information

Toxicologically Synergistic Products No information available

Delayed and immediate effects as well as chronic effects from short and long-term exposure

Irritation May cause irritation of respiratory tract

Sensitization No information available

Carcinogenicity The table below indicates whether each agency has listed any ingredient as a carcinogen.

Component	CAS-No	IARC	NTP	ACGIH	OSHA	Mexico
Chromium	7440-47-3	Not listed	Not listed	Not listed	Not listed	Not listed

Mutagenic Effects No information available

Reproductive Effects No information available.

Developmental Effects No information available.

Teratogenicity No information available.

STOT - single exposure Respiratory system

STOT - repeated exposure None known

Aspiration hazard No information available

Symptoms / effects,both acute and delayed No information available

Endocrine Disruptor Information No information available

Other Adverse Effects The toxicological properties have not been fully investigated. See actual entry in RTECS for complete information.

12. Ecological information

Ecotoxicity

The product contains following substances which are hazardous for the environment. Very toxic to aquatic organisms.

Component	Freshwater Algae	Freshwater Fish	Microtox	Water Flea
Chromium	Not listed	LC50: 14.3 mg/l/96 H (Pimephales promelas)	Not listed	EC50: 0.07 mg/l/48 H

Persistence and Degradability Insoluble in water

Bioaccumulation/ Accumulation No information available.

Mobility Is not likely mobile in the environment due its low water solubility.

13. Disposal considerations

Waste Disposal Methods Chemical waste generators must determine whether a discarded chemical is classified as a hazardous waste. Chemical waste generators must also consult local, regional, and national hazardous waste regulations to ensure complete and accurate classification.

14. Transport information

DOT

- **UN-No** UN3077
- **Proper Shipping Name** ENVIRONMENTALLY HAZARDOUS SUBSTANCES, SOLID, N.O.S.
- **Proper technical name** Chromium
- **Hazard Class** 9
- **Packing Group** III

TDG Not regulated

- **UN-No** UN3077
- **Proper Shipping Name** ENVIRONMENTALLY HAZARDOUS SUBSTANCES, SOLID, N.O.S.
- **Hazard Class** 9
- **Packing Group** III

IATA

- **UN-No** UN3077
- **Proper Shipping Name** Environmentally hazardous substance, solid, n.o.s
- **Hazard Class** 9
- **Packing Group** III

IMDG/IMO

- **UN-No** UN3077
- **Proper Shipping Name** Environmentally hazardous substance, solid, n.o.s
- **Hazard Class** 9
- **Packing Group** III

15. Regulatory information

International Inventories

Component	TSCA	DSL	NDSL	EINECS	ELINCS	NLP	PICCS	ENCS	AICS	IECSC	KECL
Chromium	X	X	-	231-157-5	-		X	-	X	X	X

Legend:
X - Listed
E - Indicates a substance that is the subject of a Section 5(e) Consent order under TSCA.

F - Indicates a substance that is the subject of a Section 5(f) Rule under TSCA.
N - Indicates a polymeric substance containing no free-radical initiator in its inventory name but is considered to cover the designated polymer made with any free-radical initiator regardless of the amount used.
P - Indicates a commenced PMN substance
R - Indicates a substance that is the subject of a Section 6 risk management rule under TSCA.
S - Indicates a substance that is identified in a proposed or final Significant New Use Rule
T - Indicates a substance that is the subject of a Section 4 test rule under TSCA.
XU - Indicates a substance exempt from reporting under the Inventory Update Rule, i.e. Partial Updating of the TSCA Inventory Data Base Production and Site Reports (40 CFR 710(B).
Y1 - Indicates an exempt polymer that has a number-average molecular weight of 1,000 or greater.
Y2 - Indicates an exempt polymer that is a polyester and is made only from reactants included in a specified list of low concern reactants that comprises one of the eligibility criteria for the exemption rule.

U.S. Federal Regulations

TSCA 12(b) Not applicable

SARA 313

Component	CAS-No	Weight %	SARA 313 - Threshold Values %
Chromium	7440-47-3	>95	1.0

SARA 311/312 Hazardous Categorization

Acute Health Hazard	Yes
Chronic Health Hazard	No
Fire Hazard	No
Sudden Release of Pressure Hazard	No
Reactive Hazard	No

Clean Water Act

Component	CWA - Hazardous Substances	CWA - Reportable Quantities	CWA - Toxic Pollutants	CWA - Priority Pollutants
Chromium	-	-	X	X

Clean Air Act

Component	HAPS Data	Class 1 Ozone Depletors	Class 2 Ozone Depletors
Chromium	X		-

OSHA Occupational Safety and Health Administration
Not applicable

CERCLA
Not applicable

Component	Hazardous Substances RQs	CERCLA EHS RQs
Chromium	5000 lb 10 lb	-

California Proposition 65 This product does not contain any Proposition 65 chemicals

State Right-to-Know

Component	Massachusetts	New Jersey	Pennsylvania	Illinois	Rhode Island
Chromium	X	X	X	X	X

U.S. Department of Transportation

Reportable Quantity (RQ): N
DOT Marine Pollutant N
DOT Severe Marine Pollutant N

U.S. Department of Homeland Security
This product does not contain any DHS chemicals.

Other International Regulations

Mexico - Grade No information available

Canada
This product has been classified in accordance with the hazard criteria of the Controlled Products Regulations (CPR) and the MSDS contains all the information required by the CPR

WHMIS Hazard Class D2B Toxic materials

16. Other information

Prepared By
Regulatory Affairs
Thermo Fisher Scientific
Email: EMSDS.RA@thermofisher.com

Creation Date 13-Sep-2013
Revision Date 21-Jul-2015
Print Date 21-Jul-2015
Revision Summary This document has been updated to comply with the US OSHA HazCom 2012 Standard replacing the current legislation under 29 CFR 1910.1200 to align with the Globally Harmonized System of Classification and Labeling of Chemicals (GHS)

Disclaimer
The information provided on this Safety Data Sheet is correct to the best of our knowledge, information and belief at the date of its publication. The information given is designed only as a guide for safe handling, use, processing, storage, transportation, disposal and release and is not to be considered as a warranty or quality specification. The information relates only to the specific material designated and may not be valid for such material used in combination with any other material or in any process, unless specified in the text.

End of SDS

SAFETY DATA SHEET

Version 5.3
Revision Date 03/04/2015
Print Date 05/13/2016

1. PRODUCT AND COMPANY IDENTIFICATION

1.1 Product identifiers

Product name	:	Chrysene
Product Number	:	35754
Brand	:	Sigma-Aldrich
Index-No.	:	601-048-00-0
CAS-No.	:	218-01-9

1.2 Relevant identified uses of the substance or mixture and uses advised against

Identified uses	:	Laboratory chemicals, Manufacture of substances

1.3 Details of the supplier of the safety data sheet

Company	:	Sigma-Aldrich 3050 Spruce Street SAINT LOUIS MO 63103 USA
Telephone	:	+1 800-325-5832
Fax	:	+1 800-325-5052

1.4 Emergency telephone number

Emergency Phone #	:	(314) 776-6555

2. HAZARDS IDENTIFICATION

2.1 Classification of the substance or mixture

GHS Classification in accordance with 29 CFR 1910 (OSHA HCS)
Germ cell mutagenicity (Category 2), H341
Carcinogenicity (Category 1B), H350
Acute aquatic toxicity (Category 1), H400
Chronic aquatic toxicity (Category 1), H410

For the full text of the H-Statements mentioned in this Section, see Section 16.

2.2 GHS Label elements, including precautionary statements

Pictogram

Signal word Danger

Hazard statement(s)

H341	Suspected of causing genetic defects.
H350	May cause cancer.
H410	Very toxic to aquatic life with long lasting effects.

Precautionary statement(s)

P201	Obtain special instructions before use.
P202	Do not handle until all safety precautions have been read and understood.
P273	Avoid release to the environment.
P281	Use personal protective equipment as required.
P308 + P313	IF exposed or concerned: Get medical advice/ attention.

P391	Collect spillage.
P405	Store locked up.
P501	Dispose of contents/ container to an approved waste disposal plant.

2.3 Hazards not otherwise classified (HNOC) or not covered by GHS - none

3. COMPOSITION/INFORMATION ON INGREDIENTS

3.1 Substances

Formula	:	$C_{18}H_{12}$
Molecular weight	:	228.29 g/mol
CAS-No.	:	218-01-9
EC-No.	:	205-923-4
Index-No.	:	601-048-00-0

Hazardous components

Component	Classification	Concentration
Chrysene		
	Muta. 2; Carc. 1B; Aquatic Acute 1; Aquatic Chronic 1; H341, H350, H410	<= 100 %

For the full text of the H-Statements mentioned in this Section, see Section 16.

4. FIRST AID MEASURES

4.1 Description of first aid measures

General advice
Consult a physician. Show this safety data sheet to the doctor in attendance.Move out of dangerous area.

If inhaled
If breathed in, move person into fresh air. If not breathing, give artificial respiration. Consult a physician.

In case of skin contact
Wash off with soap and plenty of water. Consult a physician.

In case of eye contact
Flush eyes with water as a precaution.

If swallowed
Never give anything by mouth to an unconscious person. Rinse mouth with water. Consult a physician.

4.2 Most important symptoms and effects, both acute and delayed
The most important known symptoms and effects are described in the labelling (see section 2.2) and/or in section 11

4.3 Indication of any immediate medical attention and special treatment needed
No data available

5. FIREFIGHTING MEASURES

5.1 Extinguishing media

Suitable extinguishing media
Use water spray, alcohol-resistant foam, dry chemical or carbon dioxide.

5.2 Special hazards arising from the substance or mixture
Carbon oxides

5.3 Advice for firefighters
Wear self-contained breathing apparatus for firefighting if necessary.

5.4 Further information
No data available

6. ACCIDENTAL RELEASE MEASURES

6.1 Personal precautions, protective equipment and emergency procedures

Use personal protective equipment. Avoid dust formation. Avoid breathing vapours, mist or gas. Ensure adequate ventilation. Evacuate personnel to safe areas. Avoid breathing dust.
For personal protection see section 8.

6.2 Environmental precautions

Prevent further leakage or spillage if safe to do so. Do not let product enter drains. Discharge into the environment must be avoided.

6.3 Methods and materials for containment and cleaning up

Pick up and arrange disposal without creating dust. Sweep up and shovel. Keep in suitable, closed containers for disposal.

6.4 Reference to other sections

For disposal see section 13.

7. HANDLING AND STORAGE

7.1 Precautions for safe handling

Avoid contact with skin and eyes. Avoid formation of dust and aerosols.
Provide appropriate exhaust ventilation at places where dust is formed.
For precautions see section 2.2.

7.2 Conditions for safe storage, including any incompatibilities

Keep container tightly closed in a dry and well-ventilated place.

7.3 Specific end use(s)

Apart from the uses mentioned in section 1.2 no other specific uses are stipulated

8. EXPOSURE CONTROLS/PERSONAL PROTECTION

8.1 Control parameters

Components with workplace control parameters

Component	CAS-No.	Value	Control parameters	Basis
	Remarks	Cancer Substances for which there is a Biological Exposure Index or Indices (see BEI® section), see BEI® for Polycyclic Aromatic Hydrocarbons (PAHs) Exposure by all routes should be carefully controlled to levels as low as possible. Confirmed animal carcinogen with unknown relevance to humans		
Chrysene	218-01-9	TWA	0.200000 mg/m3	USA. Occupational Exposure Limits (OSHA) - Table Z-1 Limits for Air Contaminants
		TWA	0.200000 mg/m3	USA. Occupational Exposure Limits (OSHA) - Table Z-1 Limits for Air Contaminants
		1910.1002 As used in §1910.1000 (Table Z-1), coal tar pitch volatiles include the fused polycyclic hydrocarbons which volatilize from the distillation residues of coal, petroleum (excluding asphalt), wood, and other organic matter. Asphalt (CAS 8052-42-4, and CAS 64742-93-4) is not covered under the 'coal tar pitch volatiles' standard OSHA specifically regulated carcinogen		
		TWA	0.100000 mg/m3	USA. NIOSH Recommended Exposure Limits
		Potential Occupational Carcinogen NIOSH considers coal tar, coal tar pitch, and creosote to be coal tar		

		products. cyclohexane-extractable fraction See Appendix C See Appendix A

Biological occupational exposure limits

Component	CAS-No.	Parameters	Value	Biological specimen	Basis
Chrysene	218-01-9	1-Hydroxypyrene (1-HP)		Urine	ACGIH - Biological Exposure Indices (BEI)
	Remarks	End of shift at end of workweek			

8.2 Exposure controls

Appropriate engineering controls
Handle in accordance with good industrial hygiene and safety practice. Wash hands before breaks and at the end of workday.

Personal protective equipment

Eye/face protection
Safety glasses with side-shields conforming to EN166 Use equipment for eye protection tested and approved under appropriate government standards such as NIOSH (US) or EN 166(EU).

Skin protection
Handle with gloves. Gloves must be inspected prior to use. Use proper glove removal technique (without touching glove's outer surface) to avoid skin contact with this product. Dispose of contaminated gloves after use in accordance with applicable laws and good laboratory practices. Wash and dry hands.

Full contact
Material: Nitrile rubber
Minimum layer thickness: 0.11 mm
Break through time: 480 min
Material tested:Dermatril® (KCL 740 / Aldrich Z677272, Size M)

Splash contact
Material: Nitrile rubber
Minimum layer thickness: 0.11 mm
Break through time: 480 min
Material tested:Dermatril® (KCL 740 / Aldrich Z677272, Size M)

data source: KCL GmbH, D-36124 Eichenzell, phone +49 (0)6659 87300, e-mail sales@kcl.de, test method: EN374
If used in solution, or mixed with other substances, and under conditions which differ from EN 374, contact the supplier of the CE approved gloves. This recommendation is advisory only and must be evaluated by an industrial hygienist and safety officer familiar with the specific situation of anticipated use by our customers. It should not be construed as offering an approval for any specific use scenario.

Body Protection
impervious clothing, The type of protective equipment must be selected according to the concentration and amount of the dangerous substance at the specific workplace.

Respiratory protection
Where risk assessment shows air-purifying respirators are appropriate use a full-face particle respirator type N100 (US) or type P3 (EN 143) respirator cartridges as a backup to engineering controls. If the respirator is the sole means of protection, use a full-face supplied air respirator. Use respirators and components tested and approved under appropriate government standards such as NIOSH (US) or CEN (EU).

Control of environmental exposure
Prevent further leakage or spillage if safe to do so. Do not let product enter drains. Discharge into the environment must be avoided.

9. PHYSICAL AND CHEMICAL PROPERTIES

9.1 Information on basic physical and chemical properties

a)	Appearance	Form: solid
b)	Odour	No data available
c)	Odour Threshold	No data available
d)	pH	No data available
e)	Melting point/freezing point	Melting point/range: 252 - 254 °C (486 - 489 °F) - lit.
f)	Initial boiling point and boiling range	448 °C (838 °F) - lit.
g)	Flash point	No data available
h)	Evaporation rate	No data available
i)	Flammability (solid, gas)	No data available
j)	Upper/lower flammability or explosive limits	No data available
k)	Vapour pressure	No data available
l)	Vapour density	No data available
m)	Relative density	No data available
n)	Water solubility	insoluble
o)	Partition coefficient: n-octanol/water	log Pow: 5.73
p)	Auto-ignition temperature	No data available
q)	Decomposition temperature	No data available
r)	Viscosity	No data available
s)	Explosive properties	No data available
t)	Oxidizing properties	No data available

9.2 Other safety information

No data available

10. STABILITY AND REACTIVITY

10.1 Reactivity

No data available

10.2 Chemical stability

Stable under recommended storage conditions.

10.3 Possibility of hazardous reactions

No data available

10.4 Conditions to avoid

No data available

10.5 Incompatible materials

Strong oxidizing agents

10.6 Hazardous decomposition products

Other decomposition products - No data available
In the event of fire: see section 5

11. TOXICOLOGICAL INFORMATION

11.1 Information on toxicological effects

Acute toxicity
No data available

Inhalation: No data available

Dermal: No data available

LD50 Intraperitoneal - Mouse - > 320 mg/kg

Skin corrosion/irritation
No data available

Serious eye damage/eye irritation
No data available

Respiratory or skin sensitisation
No data available

Germ cell mutagenicity
Laboratory experiments have shown mutagenic effects.
In vitro tests showed mutagenic effects

Carcinogenicity

This product is or contains a component that has been reported to be probably carcinogenic based on its IARC, OSHA, ACGIH, NTP, or EPA classification.

Possible human carcinogen

IARC:	2B - Group 2B: Possibly carcinogenic to humans (Chrysene)
NTP:	No component of this product present at levels greater than or equal to 0.1% is identified as a known or anticipated carcinogen by NTP.
OSHA:	OSHA specifically regulated carcinogen (Chrysene)

Reproductive toxicity
No data available

No data available

Specific target organ toxicity - single exposure
No data available

Specific target organ toxicity - repeated exposure
No data available

Aspiration hazard
No data available

Additional Information
RTECS: GC0700000

To the best of our knowledge, the chemical, physical, and toxicological properties have not been thoroughly investigated.

12. ECOLOGICAL INFORMATION

12.1 Toxicity

Toxicity to daphnia and other aquatic invertebrates	EC50 - Daphnia magna (Water flea) - 1.90 mg/l - 2 h

12.2 Persistence and degradability
No data available

12.3 Bioaccumulative potential
No data available

12.4 Mobility in soil
No data available

12.5 Results of PBT and vPvB assessment
PBT/vPvB assessment not available as chemical safety assessment not required/not conducted

12.6 Other adverse effects
An environmental hazard cannot be excluded in the event of unprofessional handling or disposal.
Very toxic to aquatic life.

No data available

13. DISPOSAL CONSIDERATIONS

13.1 Waste treatment methods

Product
Offer surplus and non-recyclable solutions to a licensed disposal company. Contact a licensed professional waste disposal service to dispose of this material. Dissolve or mix the material with a combustible solvent and burn in a chemical incinerator equipped with an afterburner and scrubber.

Contaminated packaging
Dispose of as unused product.

14. TRANSPORT INFORMATION

DOT (US)
UN number: 3077 Class: 9 Packing group: III
Proper shipping name: Environmentally hazardous substances, solid, n.o.s. (Chrysene)
Reportable Quantity (RQ): 100 lbs

Poison Inhalation Hazard: No

IMDG
UN number: 3077 Class: 9 Packing group: III EMS-No: F-A, S-F
Proper shipping name: ENVIRONMENTALLY HAZARDOUS SUBSTANCE, SOLID, N.O.S. (Chrysene)
Marine pollutant:yes

IATA
UN number: 3077 Class: 9 Packing group: III
Proper shipping name: Environmentally hazardous substance, solid, n.o.s. (Chrysene)

Further information
EHS-Mark required (ADR 2.2.9.1.10, IMDG code 2.10.3) for single packagings and combination packagings containing inner packagings with Dangerous Goods > 5L for liquids or > 5kg for solids.

15. REGULATORY INFORMATION

SARA 302 Components
No chemicals in this material are subject to the reporting requirements of SARA Title III, Section 302.

SARA 313 Components
The following components are subject to reporting levels established by SARA Title III, Section 313:

	CAS-No.	Revision Date
Chrysene	218-01-9	1994-04-01

SARA 311/312 Hazards
Chronic Health Hazard

Massachusetts Right To Know Components

	CAS-No.	Revision Date

Chrysene	218-01-9	1994-04-01

Pennsylvania Right To Know Components

	CAS-No.	Revision Date
Chrysene	218-01-9	1994-04-01

New Jersey Right To Know Components

	CAS-No.	Revision Date
Chrysene	218-01-9	1994-04-01

California Prop. 65 Components

WARNING! This product contains a chemical known to the State of California to cause cancer.	CAS-No.	Revision Date
Chrysene	218-01-9	2007-09-28

16. OTHER INFORMATION

Full text of H-Statements referred to under sections 2 and 3.

Aquatic Acute	Acute aquatic toxicity
Aquatic Chronic	Chronic aquatic toxicity
Carc.	Carcinogenicity
H341	Suspected of causing genetic defects.
H350	May cause cancer.
H400	Very toxic to aquatic life.
H410	Very toxic to aquatic life with long lasting effects.

HMIS Rating

Health hazard:	0
Chronic Health Hazard:	*
Flammability:	0
Physical Hazard	0

NFPA Rating

Health hazard:	0
Fire Hazard:	0
Reactivity Hazard:	0

Further information

Copyright 2015 Sigma-Aldrich Co. LLC. License granted to make unlimited paper copies for internal use only.
The above information is believed to be correct but does not purport to be all inclusive and shall be used only as a guide. The information in this document is based on the present state of our knowledge and is applicable to the product with regard to appropriate safety precautions. It does not represent any guarantee of the properties of the product. Sigma-Aldrich Corporation and its Affiliates shall not be held liable for any damage resulting from handling or from contact with the above product. See www.sigma-aldrich.com and/or the reverse side of invoice or packing slip for additional terms and conditions of sale.

Preparation Information

Sigma-Aldrich Corporation
Product Safety – Americas Region
1-800-521-8956

Version: 5.3 Revision Date: 03/04/2015 Print Date: 05/13/2016

SAFETY DATA SHEET

Creation Date 22-Sep-2009 **Revision Date** 10-Feb-2015 **Revision Number** 1

1. Identification

Product Name **cis-1,2-Dichloroethylene**

Cat No. : **AC113380000; AC113380025; AC113380100; AC113380500**

Synonyms cis-Acetylene dichloride.

Recommended Use Laboratory chemicals.

Uses advised against No Information available

Details of the supplier of the safety data sheet

Company
Fisher Scientific
One Reagent Lane
Fair Lawn, NJ 07410
Tel: (201) 796-7100

Entity / Business Name
Acros Organics
One Reagent Lane
Fair Lawn, NJ 07410

Emergency Telephone Number
For information **US** call: 001-800-ACROS-01 / **Europe** call: +32 14 57 52 11
Emergency Number **US:**001-201-796-7100 / **Europe:** +32 14 57 52 99
CHEMTREC Tel. No.**US:**001-800-424-9300 / **Europe:**001-703-527-3887

2. Hazard(s) identification

Classification
This chemical is considered hazardous by the 2012 OSHA Hazard Communication Standard (29 CFR 1910.1200)

Flammable liquids	Category 2
Acute oral toxicity	Category 4
Acute Inhalation Toxicity - Vapors	Category 4
Skin Corrosion/irritation	Category 2
Serious Eye Damage/Eye Irritation	Category 2
Specific target organ toxicity (single exposure)	Category 3
Target Organs - Respiratory system.	

Label Elements

Signal Word
Danger

Hazard Statements
Highly flammable liquid and vapor
Harmful if swallowed
Harmful if inhaled
Causes serious eye irritation
Causes skin irritation
May cause respiratory irritation

Precautionary Statements
Prevention
Wear protective gloves/protective clothing/eye protection/face protection
Use only outdoors or in a well-ventilated area
Avoid breathing dust/fume/gas/mist/vapors/spray
Keep away from heat/sparks/open flames/hot surfaces. - No smoking
Keep container tightly closed
Ground/bond container and receiving equipment
Take precautionary measures against static discharge
Do not eat, drink or smoke when using this product
Response
Call a POISON CENTER or doctor/physician if you feel unwell
Inhalation
IF INHALED: Remove victim to fresh air and keep at rest in a position comfortable for breathing
Call a POISON CENTER or doctor/physician if you feel unwell
Skin
IF ON SKIN: Wash with plenty of soap and water
Take off contaminated clothing and wash before reuse
If skin irritation occurs: Get medical advice/attention
Eyes
IF IN EYES: Rinse cautiously with water for several minutes. Remove contact lenses, if present and easy to do. Continue rinsing
If eye irritation persists: Get medical advice/attention
Ingestion
Rinse mouth
IF SWALLOWED: Call a POISON CENTER or doctor/physician if you feel unwell
Fire
Explosion risk in case of fire
Fight fire with normal precautions from a reasonable distance
Evacuate area
Storage
Store in a well-ventilated place. Keep cool
Store in a closed container
Store locked up
Disposal
Dispose of contents/container to an approved waste disposal plant
Hazards not otherwise classified (HNOC)
None identified

3. Composition / information on ingredients

Component	CAS-No	Weight %
cis-1,2-Dichloroethylene	156-59-2	97

4. First-aid measures

Eye Contact Rinse immediately with plenty of water, also under the eyelids, for at least 15 minutes. Obtain medical attention.

Skin Contact Wash off immediately with plenty of water for at least 15 minutes. Obtain medical attention.

Inhalation Move to fresh air. If breathing is difficult, give oxygen. Obtain medical attention.

Ingestion Do not induce vomiting. Obtain medical attention.

Most important symptoms/effects Breathing difficulties. Inhalation of high vapor concentrations may cause symptoms like headache, dizziness, tiredness, nausea and vomiting

Notes to Physician Treat symptomatically

5. Fire-fighting measures

Suitable Extinguishing Media Water spray. Carbon dioxide (CO_2). Dry chemical. Use water spray to cool unopened containers. chemical foam.

Unsuitable Extinguishing Media No information available

Flash Point 6 °C / 42.8 °F
Method - No information available

Autoignition Temperature 440 °C / 824 °F

Explosion Limits
Upper 12.80%
Lower 9.70%
Sensitivity to Mechanical Impact No information available
Sensitivity to Static Discharge No information available

Specific Hazards Arising from the Chemical
Flammable. Vapors may travel to source of ignition and flash back.

Hazardous Combustion Products
Hydrogen chloride gas Carbon monoxide (CO) Carbon dioxide (CO_2)
Protective Equipment and Precautions for Firefighters
As in any fire, wear self-contained breathing apparatus pressure-demand, MSHA/NIOSH (approved or equivalent) and full protective gear.

NFPA

Health	Flammability	Instability	Physical hazards
2	3	0	N/A

6. Accidental release measures

Personal Precautions Ensure adequate ventilation. Use personal protective equipment. Remove all sources of ignition. Take precautionary measures against static discharges. Avoid contact with skin, eyes and clothing.

Environmental Precautions See Section 12 for additional ecological information.

Methods for Containment and Clean Up Soak up with inert absorbent material (e.g. sand, silica gel, acid binder, universal binder, sawdust). Keep in suitable, closed containers for disposal. Remove all sources of ignition. Use spark-proof tools and explosion-proof equipment.

7. Handling and storage

Handling Ensure adequate ventilation. Wear personal protective equipment. Use explosion-proof equipment. Use only non-sparking tools. Avoid contact with skin, eyes and clothing. Avoid breathing dust/fume/gas/mist/vapours/spray. Avoid ingestion and inhalation. Keep away from open flames, hot surfaces and sources of ignition. Take precautionary measures against static discharges.

Storage Keep in a dry, cool and well-ventilated place. Keep container tightly closed. Keep away from heat and sources of ignition. Flammables area.

8. Exposure controls / personal protection

Exposure Guidelines

Component	ACGIH TLV	OSHA PEL	NIOSH IDLH
cis-1,2-Dichloroethylene	TWA: 200 ppm		

Component	Quebec	Mexico OEL (TWA)	Ontario TWAEV
cis-1,2-Dichloroethylene			TWA: 200 ppm

Legend

ACGIH - American Conference of Governmental Industrial Hygienists

Engineering Measures Ensure adequate ventilation, especially in confined areas. Use explosion-proof electrical/ventilating/lighting/equipment. Ensure that eyewash stations and safety showers are close to the workstation location.

Personal Protective Equipment

Eye/face Protection Wear appropriate protective eyeglasses or chemical safety goggles as described by OSHA's eye and face protection regulations in 29 CFR 1910.133 or European Standard EN166.

Skin and body protection Wear appropriate protective gloves and clothing to prevent skin exposure.

Respiratory Protection Follow the OSHA respirator regulations found in 29 CFR 1910.134 or European Standard EN 149. Use a NIOSH/MSHA or European Standard EN 149 approved respirator if exposure limits are exceeded or if irritation or other symptoms are experienced.

Hygiene Measures Handle in accordance with good industrial hygiene and safety practice.

9. Physical and chemical properties

Physical State	Liquid
Appearance	Colorless
Odor	aromatic
Odor Threshold	No information available
pH	No information available
Melting Point/Range	-80 °C / -112 °F
Boiling Point/Range	60 °C / 140 °F @ 760 mmHg
Flash Point	6 °C / 42.8 °F
Evaporation Rate	No information available
Flammability (solid,gas)	No information available
Flammability or explosive limits	
Upper	12.80%
Lower	9.70%
Vapor Pressure	201 mmHg @ 25 °C
Vapor Density	3.34 (Air = 1.0)
Relative Density	1.280
Solubility	No information available
Partition coefficient; n-octanol/water	No data available
Autoignition Temperature	440 °C / 824 °F
Decomposition Temperature	No information available
Viscosity	No information available
Molecular Formula	C2 H2 Cl2
Molecular Weight	96.94

10. Stability and reactivity

Reactive Hazard None known, based on information available

Stability Stable under normal conditions.

Conditions to Avoid Keep away from open flames, hot surfaces and sources of ignition. Exposure to air. Exposure to light. Incompatible products. Exposure to moist air or water.

Incompatible Materials Bases

Hazardous Decomposition Products Hydrogen chloride gas, Carbon monoxide (CO), Carbon dioxide (CO_2)

Hazardous Polymerization Hazardous polymerization does not occur.

Hazardous Reactions None under normal processing.

11. Toxicological information

Acute Toxicity

Product Information No acute toxicity information is available for this product

Component Information

Toxicologically Synergistic Products No information available

Delayed and immediate effects as well as chronic effects from short and long-term exposure

Irritation Irritating to eyes, respiratory system and skin

Sensitization No information available

Carcinogenicity The table below indicates whether each agency has listed any ingredient as a carcinogen.

Component	CAS-No	IARC	NTP	ACGIH	OSHA	Mexico
cis-1,2-Dichloroethylene	156-59-2	Not listed	Not listed	Not listed	Not listed	Not listed

Mutagenic Effects No information available

Reproductive Effects No information available.

Developmental Effects No information available.

Teratogenicity No information available.

STOT - single exposure Respiratory system

STOT - repeated exposure None known

Aspiration hazard No information available

Symptoms / effects,both acute and delayed Inhalation of high vapor concentrations may cause symptoms like headache, dizziness, tiredness, nausea and vomiting

Endocrine Disruptor Information No information available

Other Adverse Effects The toxicological properties have not been fully investigated. See actual entry in RTECS for complete information.

12. Ecological information

Ecotoxicity

Do not empty into drains. Do not flush into surface water or sanitary sewer system.

Component	Freshwater Algae	Freshwater Fish	Microtox	Water Flea
cis-1,2-Dichloroethylene	Not listed	Not listed	EC50 = 721 mg/L 5 min EC50 = 905 mg/L 30 min	Not listed

Persistence and Degradability No information available

Bioaccumulation/ Accumulation No information available.

Mobility No information available.

13. Disposal considerations

Waste Disposal Methods Chemical waste generators must determine whether a discarded chemical is classified as a hazardous waste. Chemical waste generators must also consult local, regional, and national hazardous waste regulations to ensure complete and accurate classification.

14. Transport information

DOT

UN-No	UN1150
Proper Shipping Name	1,2-DICHLOROETHYLENE
Hazard Class	3
Packing Group	II

TDG

UN-No	UN1150
Proper Shipping Name	1,2-DICHLOROETHYLENE
Hazard Class	3
Packing Group	II

IATA

UN-No	1150
Proper Shipping Name	1,2-DICHLOROETHYLENE
Hazard Class	3
Packing Group	II

IMDG/IMO

UN-No	1150
Proper Shipping Name	1,2-DICHLOROETHYLENE
Hazard Class	3
Packing Group	II

15. Regulatory information

International Inventories

Component	TSCA	DSL	NDSL	EINECS	ELINCS	NLP	PICCS	ENCS	AICS	IECSC	KECL
cis-1,2-Dichloroethylene	X	-	X	205-859-7	-		-	X	X	X	X

Legend:
X - Listed
E - Indicates a substance that is the subject of a Section 5(e) Consent order under TSCA.
F - Indicates a substance that is the subject of a Section 5(f) Rule under TSCA.
N - Indicates a polymeric substance containing no free-radical initiator in its inventory name but is considered to cover the designated polymer made with any free-radical initiator regardless of the amount used.
P - Indicates a commenced PMN substance
R - Indicates a substance that is the subject of a Section 6 risk management rule under TSCA.
S - Indicates a substance that is identified in a proposed or final Significant New Use Rule
T - Indicates a substance that is the subject of a Section 4 test rule under TSCA.
XU - Indicates a substance exempt from reporting under the Inventory Update Rule, i.e. Partial Updating of the TSCA Inventory Data Base Production and Site Reports (40 CFR 710(B).
Y1 - Indicates an exempt polymer that has a number-average molecular weight of 1,000 or greater.
Y2 - Indicates an exempt polymer that is a polyester and is made only from reactants included in a specified list of low concern reactants that comprises one of the eligibility criteria for the exemption rule.

U.S. Federal Regulations

TSCA 12(b) Not applicable

SARA 313 Not applicable

SARA 311/312 Hazardous Categorization

Acute Health Hazard	Yes
Chronic Health Hazard	No
Fire Hazard	Yes

Sudden Release of Pressure Hazard No
Reactive Hazard No

Clean Water Act Not applicable

Clean Air Act Not applicable

OSHA Occupational Safety and Health Administration
Not applicable

CERCLA

Component	Hazardous Substances RQs	CERCLA EHS RQs
cis-1,2-Dichloroethylene	1000 lb	-

California Proposition 65 This product does not contain any Proposition 65 chemicals

State Right-to-Know

Component	Massachusetts	New Jersey	Pennsylvania	Illinois	Rhode Island
cis-1,2-Dichloroethylene	X	-	X	-	-

U.S. Department of Transportation

Reportable Quantity (RQ): N
DOT Marine Pollutant N
DOT Severe Marine Pollutant N

U.S. Department of Homeland Security
This product does not contain any DHS chemicals.

Other International Regulations

Mexico - Grade No information available

Canada
This product has been classified in accordance with the hazard criteria of the Controlled Products Regulations (CPR) and the MSDS contains all the information required by the CPR

WHMIS Hazard Class B2 Flammable liquid
D1B Toxic materials
D2B Toxic materials

16. Other information

Prepared By Regulatory Affairs
Thermo Fisher Scientific
Email: EMSDS.RA@thermofisher.com

Creation Date 22-Sep-2009
Revision Date 10-Feb-2015
Print Date 10-Feb-2015
Revision Summary This document has been updated to comply with the US OSHA HazCom 2012 Standard replacing the current legislation under 29 CFR 1910.1200 to align with the Globally

Harmonized System of Classification and Labeling of Chemicals (GHS)

Disclaimer

The information provided on this Safety Data Sheet is correct to the best of our knowledge, information and belief at the date of its publication. The information given is designed only as a guide for safe handling, use, processing, storage, transportation, disposal and release and is not to be considered as a warranty or quality specification. The information relates only to the specific material designated and may not be valid for such material used in combination with any other material or in any process, unless specified in the text.

End of SDS

SAFETY DATA SHEET

COPPER

Section 1. Identification

GHS product identifier	:	COPPER
Chemical name	:	Mixture
CAS number	:	Mixture
Other means of identification	:	CC01053472
Product type	:	liquid

Relevant identified uses of the substance or mixture and uses advised against

Product use	:	Industrial applications. Plastics.

Supplier's details	:	**POLYONE CORPORATION** ColorMatrix Group Inc. 680 North Rocky River Drive, Berea, Ohio, 44017-1628, USA +1 216 622 0100
Emergency telephone number (with hours of operation)	:	**CHEMTREC 1-800-424-9300 (24hrs for spill, leak, fire, exposure or accident).**

Section 2. Hazards identification

This mixture has not been evaluated as a whole for health effects. Information provided on health effects of this product is based on the individual components. However, some vapors or contaminants may be released upon heating and the end-user (fabricator) must take the necessary precautions (mechanical ventilation, respiratory protection, etc.) to protect employees from exposure. See sections 8 and 11 for special precautions. After handling, always wash hands thoroughly with soap and water.

OSHA/HCS status	:	This material is considered hazardous by the OSHA Hazard Communication Standard (29 CFR 1910.1200).
Classification of the substance or mixture	:	SKIN CORROSION/IRRITATION - Category 2

GHS label elements

Hazard pictograms :

Signal word : Warning
Hazard statements : Causes skin irritation.

Precautionary statements

General : Not applicable.
Prevention : Wear protective gloves. Wash hands thoroughly after handling.
Response : IF ON SKIN: Wash with plenty of soap and water. Take off contaminated clothing. Wash contaminated clothing before reuse. If skin irritation occurs: Get medical attention.
Storage : Not applicable.
Disposal : Not applicable.
Supplemental label elements : None known.
Hazards not otherwise classified : None known.

Section 3. Composition/information on ingredients

Substance/mixture : Mixture
Chemical name : Mixture
Other means of identification : CC01053472

CAS number/other identifiers

Ingredient name	%	CAS number
Miscellaneous Compounds Distillates, petroleum, hydrotreated middle	10 - 30	Not available.
Titanium dioxide	5 - 10	13463-67-7

Any concentration shown as a range is to protect confidentiality or is due to batch variation.

There are no additional ingredients present which, within the current knowledge of the supplier and in the concentrations applicable, are classified as hazardous to health or the environment and hence require reporting in this section.

Occupational exposure limits, if available, are listed in Section 8.

Section 4. First aid measures

Description of necessary first aid measures

Eye contact	:	Immediately flush eyes with plenty of water, occasionally lifting the upper and lower eyelids. Check for and remove any contact lenses. Continue to rinse for at least 10 minutes. Get medical attention.
Inhalation	:	Remove victim to fresh air and keep at rest in a position comfortable for breathing. If not breathing, if breathing is irregular or if respiratory arrest occurs, provide artificial respiration or oxygen by trained personnel. It may be dangerous to the person providing aid to give mouth-to-mouth resuscitation. Get medical attention if adverse health effects persist or are severe. If unconscious, place in recovery position and get medical attention immediately. Maintain an open airway. Loosen tight clothing such as a collar, tie, belt or waistband.
Skin contact	:	Flush contaminated skin with plenty of water. Remove contaminated clothing and shoes. Continue to rinse for at least 10 minutes. Get medical attention. Wash clothing before reuse. Clean shoes thoroughly before reuse.
Ingestion	:	Wash out mouth with water. Remove dentures if any. Remove victim to fresh air and keep at rest in a position comfortable for breathing. If material has been swallowed and the exposed person is conscious, give small quantities of water to drink. Stop if the exposed person feels sick as vomiting may be dangerous. Do not induce vomiting unless directed to do so by medical personnel. If vomiting occurs, the head should be kept low so that vomit does not enter the lungs. Get medical attention if adverse health effects persist or are severe. Never give anything by mouth to an unconscious person. If unconscious, place in recovery position and get medical attention immediately. Maintain an open airway. Loosen tight clothing such as a collar, tie, belt or waistband.

Most important symptoms/effects, acute and delayed

Potential acute health effects

Eye contact	:	Causes serious eye irritation.
Inhalation	:	No known significant effects or critical hazards.
Skin contact	:	Causes skin irritation.
Ingestion	:	Irritating to mouth, throat and stomach.

Over-exposure signs/symptoms

Eye contact	:	Adverse symptoms may include the following: pain or irritation

watering
redness

Inhalation : No specific data.

Skin contact : Adverse symptoms may include the following:
irritation
redness

Ingestion : No specific data.

Indication of immediate medical attention and special treatment needed, if necessary

Notes to physician : Treat symptomatically. Contact poison treatment specialist immediately if large quantities have been ingested or inhaled.

Specific treatments : No specific treatment.

Protection of first-aiders : No action shall be taken involving any personal risk or without suitable training. It may be dangerous to the person providing aid to give mouth-to-mouth resuscitation.

See toxicological information (Section 11)

Section 5. Fire-fighting measures

Extinguishing media

Suitable extinguishing media : In case of fire, use water spray (fog), foam, dry chemical or CO_2.

Unsuitable extinguishing media : None known.

Specific hazards arising from the chemical : In a fire or if heated, a pressure increase will occur and the container may burst.

Hazardous thermal decomposition products : Decomposition products may include the following materials:
carbon dioxide
carbon monoxide
metal oxide/oxides

Special protective actions for fire-fighters : Promptly isolate the scene by removing all persons from the vicinity of the incident if there is a fire. No action shall be taken involving any personal risk or without suitable training.

Special protective equipment for fire-fighters : Fire-fighters should wear appropriate protective equipment and self-contained breathing apparatus (SCBA) with a full face-piece operated in positive pressure mode.

Section 6. Accidental release measures

Personal precautions, protective equipment and emergency procedures

For non-emergency personnel	:	No action shall be taken involving any personal risk or without suitable training. Evacuate surrounding areas. Keep unnecessary and unprotected personnel from entering. Do not touch or walk through spilled material. Avoid breathing vapor or mist. Provide adequate ventilation. Wear appropriate respirator when ventilation is inadequate. Put on appropriate personal protective equipment.
For emergency responders	:	If specialised clothing is required to deal with the spillage, take note of any information in Section 8 on suitable and unsuitable materials. See also the information in "For non-emergency personnel".
Environmental precautions	:	Avoid dispersal of spilled material and runoff and contact with soil, waterways, drains and sewers. Inform the relevant authorities if the product has caused environmental pollution (sewers, waterways, soil or air).

Methods and materials for containment and cleaning up

Small spill	:	Stop leak if without risk. Move containers from spill area. Dilute with water and mop up if water-soluble. Alternatively, or if water-insoluble, absorb with an inert dry material and place in an appropriate waste disposal container. Dispose of via a licensed waste disposal contractor.
Large spill	:	Stop leak if without risk. Move containers from spill area. Approach release from upwind. Prevent entry into sewers, water courses, basements or confined areas. Wash spillages into an effluent treatment plant or proceed as follows. Contain and collect spillage with non-combustible, absorbent material e.g. sand, earth, vermiculite or diatomaceous earth and place in container for disposal according to local regulations (see Section 13). Dispose of via a licensed waste disposal contractor. Contaminated absorbent material may pose the same hazard as the spilled product. Note: see Section 1 for emergency contact information and Section 13 for waste disposal.

Section 7. Handling and storage

Precautions for safe handling

Protective measures	:	Put on appropriate personal protective equipment (see Section 8). Do not ingest. Avoid contact with eyes, skin and clothing. Avoid breathing vapor or mist. Keep in the original container or an approved alternative made from a compatible material, kept tightly closed when not in use. Empty containers retain product residue and can be hazardous. Do not reuse container.

Advice on general occupational hygiene	:	Eating, drinking and smoking should be prohibited in areas where this material is handled, stored and processed. Workers should wash hands and face before eating, drinking and smoking. Remove contaminated clothing and protective equipment before entering eating areas. See also Section 8 for additional information on hygiene measures.
Conditions for safe storage, including any incompatibilities	:	Store in accordance with local regulations. Store in original container protected from direct sunlight in a dry, cool and well-ventilated area, away from incompatible materials (see Section 10) and food and drink. Keep container tightly closed and sealed until ready for use. Containers that have been opened must be carefully resealed and kept upright to prevent leakage. Do not store in unlabeled containers. Use appropriate containment to avoid environmental contamination.

Section 8. Exposure controls/personal protection

Control parameters

Occupational exposure limits

Ingredient name	Exposure limits
Titanium dioxide	**OSHA PEL 1989 (1989-03-01)** PEL: Permissible Exposure Level 10 mg/m3 Form: Total dust **OSHA PEL (1993-06-30)** PEL: Permissible Exposure Level 15 mg/m3 Form: Total dust **ACGIH TLV (1996-05-18)** TLV-TWA: Threshold Limit Value - Time weighted average PEL: Permissible Exposure Level 10 mg/m3

Appropriate engineering controls	:	Good general ventilation should be sufficient to control worker exposure to airborne contaminants.
Environmental exposure controls	:	Emissions from ventilation or work process equipment should be checked to ensure they comply with the requirements of environmental protection legislation. In some cases, fume scrubbers, filters or engineering modifications to the process equipment will be necessary to reduce emissions to acceptable levels.

Individual protection measures

Hygiene measures	:	Wash hands, forearms and face thoroughly after handling chemical products, before eating, smoking and using the lavatory and at the end of the working period. Appropriate techniques should be used to remove potentially contaminated clothing. Wash contaminated

clothing before reusing. Ensure that eyewash stations and safety showers are close to the workstation location.

Eye/face protection : Safety eyewear complying with an approved standard should be used when a risk assessment indicates this is necessary to avoid exposure to liquid splashes, mists, gases or dusts. If contact is possible, the following protection should be worn, unless the assessment indicates a higher degree of protection: chemical splash goggles.

Skin protection

Hand protection : Chemical-resistant, impervious gloves complying with an approved standard should be worn at all times when handling chemical products if a risk assessment indicates this is necessary. Considering the parameters specified by the glove manufacturer, check during use that the gloves are still retaining their protective properties. It should be noted that the time to breakthrough for any glove material may be different for different glove manufacturers. In the case of mixtures, consisting of several substances, the protection time of the gloves cannot be accurately estimated.

Body protection : Personal protective equipment for the body should be selected based on the task being performed and the risks involved and should be approved by a specialist before handling this product.

Other skin protection : Appropriate footwear and any additional skin protection measures should be selected based on the task being performed and the risks involved and should be approved by a specialist before handling this product.

Respiratory protection : Use a properly fitted, air-purifying or air-fed respirator complying with an approved standard if a risk assessment indicates this is necessary. Respirator selection must be based on known or anticipated exposure levels, the hazards of the product and the safe working limits of the selected respirator.

Section 9. Physical and chemical properties

Appearance

Physical state : liquid [liquid]
Color : BROWN
Odor : Faint odor.
Odor threshold : Not available.
pH : Not available.
Melting point : Not available.
Boiling point : Not available.
Flash point : Not available.
Burning time : Not available.

Burning rate	:	Not available.
Evaporation rate	:	Not available.
Flammability (solid, gas)	:	Not available.
Lower and upper explosive (flammable) limits	:	**Lower:** Not available. **Upper:** Not available.
Vapor pressure	:	Not available.
Vapor density	:	Not available.
Relative density	:	Not available.
Solubility	:	Not available.
Solubility in water	:	insoluble in water.
Partition coefficient: n-octanol/water	:	Not available.
Auto-ignition temperature	:	Not available.
Decomposition temperature	:	Not available.
SADT	:	Not available.
Viscosity	:	**Dynamic:** Not available. **Kinematic:** Not available.

Section 10. Stability and reactivity

Reactivity	:	No specific test data related to reactivity available for this product or its ingredients.
Chemical stability	:	Stable under recommended storage and handling conditions (see Section 7).
Possibility of hazardous reactions	:	Under normal conditions of storage and use, hazardous reactions will not occur.
Conditions to avoid	:	Keep away from extreme heat and oxidizing agents.
Incompatible materials	:	Keep away from strong acids. Oxidizer.
Hazardous decomposition products	:	Under normal conditions of storage and use, hazardous decomposition products should not be produced.

Section 11. Toxicological information

This mixture has not been evaluated as a whole for health effects. Exposure effects listed are based on existing health data for the individual components which comprise the mixture.

Information on toxicological effects

Acute toxicity

Product/ingredient name	Result	Species	Dose	Exposure
Titanium dioxide				

	LC50 Inhalation	Rat - Male	6.82 Mg/l	4 h
	LD50 Dermal	Rabbit	> 5,000 mg/kg	-

Conclusion/Summary : Mixture.Not fully tested.

Irritation/Corrosion

Conclusion/Summary
Skin : Mixture.Not fully tested.
Eyes : Mixture.Not fully tested.
Respiratory : Mixture.Not fully tested.

Sensitization

Conclusion/Summary
Skin : Mixture.Not fully tested.
Respiratory : Mixture.Not fully tested.

Mutagenicity

Conclusion/Summary : Mixture.Not fully tested.

Carcinogenicity

Conclusion/Summary : Mixture.Not fully tested.

Classification

Product/ingredient name	OSHA	IARC	NTP
Titanium dioxide		2B	

Reproductive toxicity

Conclusion/Summary : Mixture.Not fully tested.

Teratogenicity

Conclusion/Summary : Mixture.Not fully tested.

Specific target organ toxicity (single exposure)
Not available.

Specific target organ toxicity (repeated exposure)
Not available.

Aspiration hazard

Product/ingredient name	Result

Miscellaneous Compounds Distillates, petroleum, hydrotreated middle	ASPIRATION HAZARD - Category 1

Information on the likely routes of exposure : Not available.

Potential acute health effects

Eye contact : Causes serious eye irritation.
Inhalation : No known significant effects or critical hazards.
Skin contact : Causes skin irritation.
Ingestion : Irritating to mouth, throat and stomach.

Symptoms related to the physical, chemical and toxicological characteristics

Eye contact : Adverse symptoms may include the following:
pain or irritation
watering
redness
Inhalation : No specific data.
Skin contact : Adverse symptoms may include the following:
irritation
redness
Ingestion : No specific data.

Delayed and immediate effects and also chronic effects from short and long term exposure

Short term exposure

Potential immediate effects : Not available.
Potential delayed effects : Not available.

Long term exposure

Potential immediate effects : Not available.
Potential delayed effects : Not available.

Potential chronic health effects

Conclusion/Summary : Mixture.Not fully tested.

General : No known significant effects or critical hazards.
Carcinogenicity : No known significant effects or critical hazards.
Mutagenicity : No known significant effects or critical hazards.
Teratogenicity : No known significant effects or critical hazards.

Developmental effects : No known significant effects or critical hazards.
Fertility effects : No known significant effects or critical hazards.

Numerical measures of toxicity

Acute toxicity estimates

Route	ATE value
Inhalation (dusts and mists)	7.81 mg/l

Section 12. Ecological information

Toxicity

Product/ingredient name	Result	Species	Exposure
Titanium dioxide			
	Acute LC50 > 1,000,000 µg/l Marine water	Fish - Mummichog	96 h
	Acute LC50 > 1,000 mg/l Fresh water	Fish - Fathead minnow	96 h
	Acute LC50 13 mg/l Fresh water	Aquatic invertebrates. Water flea	48 h
	Acute LC50 6.5 mg/l Fresh water	Aquatic invertebrates. Water flea	48 h
	Acute EC50 19.3 mg/l Fresh water	Aquatic invertebrates. Water flea	48 h
	Acute EC50 27.8 mg/l Fresh water	Aquatic invertebrates. Water flea	48 h
	Acute EC50 35.306 mg/l Fresh water	Aquatic invertebrates. Water flea	48 h

Conclusion/Summary : Not available.

Persistence and degradability

Conclusion/Summary : Not available.

Bioaccumulative potential

Product/ingredient name	LogPow	BCF	Potential
Titanium dioxide		352.00	low

Mobility in soil

Soil/water partition coefficient (KOC)	:	Not available.
Other adverse effects	:	No known significant effects or critical hazards.

Section 13. Disposal considerations

Disposal methods : The generation of waste should be avoided or minimized wherever possible. Disposal of this product, solutions and any by-products should at all times comply with the requirements of environmental protection and waste disposal legislation and any regional local authority requirements. Dispose of surplus and non-recyclable products via a licensed waste disposal contractor. Waste should not be disposed of untreated to the sewer unless fully compliant with the requirements of all authorities with jurisdiction. Waste packaging should be recycled. Incineration or landfill should only be considered when recycling is not feasible. This material and its container must be disposed of in a safe way. Care should be taken when handling emptied containers that have not been cleaned or rinsed out. Empty containers or liners may retain some product residues. Avoid dispersal of spilled material and runoff and contact with soil, waterways, drains and sewers.

United States - RCRA Acute hazardous waste "P" List: Not listed

United States - RCRA Toxic hazardous waste "U" List: Not listed

Section 14. Transport information

U.S. DOT Classification	:	Not regulated for transportation.
ICAO/IATA	:	Not classified as dangerous good under transport regulations.
IMO/IMDG (maritime)	:	Not classified as dangerous good under transport regulations.

Section 15. Regulatory information

U.S. Federal regulations : **United States - TSCA 12(b) - Chemical export notification:** None of the components are listed.
United States - TSCA 4(a) - Final Test Rules: Not listed
United States - TSCA 4(a) - ITC Priority list: Not listed
United States - TSCA 4(a) - Proposed test rules: Not listed

United States - TSCA 4(f) - Priority risk review: Not listed
United States - TSCA 5(a)2 - Final significant new use rules: Not listed
United States - TSCA 5(a)2 - Proposed significant new use rules: Not listed
United States - TSCA 5(e) - Substances consent order: Not listed
United States - TSCA 6 - Final risk management: Not listed
United States - TSCA 6 - Proposed risk management: Not listed
United States - TSCA 8(a) - Chemical risk rules: Not listed
United States - TSCA 8(a) - Dioxin/Furane precusor: Not listed
United States - TSCA 8(a) - Chemical Data Reporting (CDR): Not determined
United States - TSCA 8(a) - Preliminary assessment report (PAIR): Not listed
United States - TSCA 8(c) - Significant adverse reaction (SAR): Not listed
United States - TSCA 8(d) - Health and safety studies: Not listed
United States - EPA Clean water act (CWA) section 307 - Priority pollutants: Not listed
United States - EPA Clean water act (CWA) section 311 - Hazardous substances: Not listed
United States - EPA Clean air act (CAA) section 112 - Accidental release prevention - Flammable substances: Not listed
United States - EPA Clean air act (CAA) section 112 - Accidental release prevention - Toxic substances: Not listed
United States - Department of commerce - Precursor chemical: Not listed

Clean Air Act Section 112(b) Hazardous Air Pollutants (HAPs)	:	Not listed
Clean Air Act Section 602 Class I Substances	:	Not listed
Clean Air Act Section 602 Class II Substances	:	Not listed
DEA List I Chemicals (Precursor Chemicals)	:	Not listed
DEA List II Chemicals (Essential Chemicals)	:	Not listed

US. EPA CERCLA Hazardous Substances (40 CFR 302)

not applicable

SARA 311/312

Classification	:	Immediate (acute) health hazard

Composition/information on ingredients

Name	%	Classification
Miscellaneous Compounds Distillates, petroleum, hydrotreated middle	10 - 30	AH
Titanium dioxide	5 - 10	CH

SARA 313
Not applicable.

State regulations

Massachusetts : The following components are listed:
Mica
Iron oxide
Titanium dioxide

New York : None of the components are listed.

New Jersey : The following components are listed:
Mica
Iron oxide
Titanium dioxide

Pennsylvania : The following components are listed:
Iron oxide
Titanium dioxide

California Prop. 65
WARNING: This product contains a chemical known to the State of California to cause cancer.

United States inventory (TSCA 8b) : All components are listed or exempted.

Canada inventory : All components are listed or exempted.

International regulations

International lists : **Australia inventory (AICS):** All components are listed or exempted.
Taiwan inventory (CSNN): Not determined.
Malaysia Inventory (EHS Register): Not determined.
EINECS: All components are listed or exempted.
Japan inventory: Not determined.
China inventory (IECSC): All components are listed or exempted.
Korea inventory: All components are listed or exempted.
New Zealand Inventory of Chemicals (NZIoC): Not determined.

Philippines inventory (PICCS): All components are listed or exempted.

Chemical Weapons Convention List Schedule I Chemicals	:	Not listed
Chemical Weapons Convention List Schedule II Chemicals	:	Not listed
Chemical Weapons Convention List Schedule III Chemicals	:	Not listed

Section 16. Other information

History

Date of printing	:	05/21/2015
Date of issue/Date of revision	:	05/18/2015
Date of previous issue	:	10/30/2014
Version	:	1.1
Key to abbreviations	:	ATE = Acute Toxicity Estimate BCF = Bioconcentration Factor GHS = Globally Harmonized System of Classification and Labelling of Chemicals IATA = International Air Transport Association IBC = Intermediate Bulk Container IMDG = International Maritime Dangerous Goods LogPow = logarithm of the octanol/water partition coefficient MARPOL 73/78 = International Convention for the Prevention of Pollution From Ships, 1973 as modified by the Protocol of 1978. ("Marpol" = marine pollution) UN = United Nations
References	:	Not available.

Notice to reader

To the best of our knowledge, the information contained herein is accurate. However, neither the above-named supplier, nor any of its subsidiaries, assumes any liability whatsoever for the accuracy or completeness of the information contained herein. Final determination of suitability of any material is the sole responsibility of the user. All materials may present unknown hazards and should be used with caution. Although certain hazards are described herein, we cannot guarantee that these are the only hazards that exist. Particularly this information may not be valid for such material used in conjunction with any other materials or in any process, unless specified in the text.

Safety Data Sheet

Revision Date: 01/06/17
www.restek.com

1. IDENTIFICATION

Catalog Number / Product Name:	**31276 / Dibenzo(a,h)anthracene Standard**
Company:	Restek Corporation
Address:	110 Benner Circle Bellefonte, Pa. 16823
Phone#:	814-353-1300
Fax#:	814-353-1309
Emergency#:	800-424-9300 (CHEMTREC) 703-527-3887 (Outside the US)
Email:	www.restek.com
Revision Number:	7
Intended use:	For Laboratory use only

2. HAZARD(S)IDENTIFICATION

Emergency Overview:

GHS Hazard Symbols:

GHS Classification:	Carcinogenicity Category 2
GHS Signal Word:	Warning
GHS Hazard:	Suspected of causing cancer.
GHS Precautions:	
Safety Precautions:	Obtain special instructions before use. Do not handle until all safety precautions have been read and understood. Wear protective gloves/protective clothing/eye protection/face protection.
First Aid Measures:	IF exposed or concerned: Get medical advice/attention.
Storage:	Store locked up.
Disposal:	Dispose of contents/container according to section 13 of the SDS.
Single Exposure Target Organs:	No data available.
Repeated Exposure Target Organs:	No data available.

3. COMPOSITION / INFORMATION ON INGREDIENT

Chemical Name	CAS #	EINEC #	% Composition
Dichloromethane	75-09-2	200-838-9	99.900000
dibenz (a,h) anthracene	53-70-3	200-181-8	0.100000

4. FIRST-AID MEASURES

Inhalation:	Remove to fresh air. If breathing is difficult, have a trained individual administer oxygen. If not breathing, give artificial respiration and have a trained individual administer oxygen. Get medical attention immediately
Eyes:	Immediately flush eyes with plenty of water for at least 20 minutes retracting eyelids often. Tilt the head to prevent chemical from transferring to the uncontaminated eye. Get immediate medical attention and monitor the eye daily as advised by your physician. Serious harm (damage) may result if treatment is delayed. Continue to flush eyes while awaiting medical attention
Skin Contact:	Wash with soap and water. Remove contaminated clothing, launder immediately, and discard contaminated leather goods. Get medical attention immediately.
Ingestion:	Do not induce vomiting and seek medical attention immediately. Drink two glasses of water or milk to dilute. Provide medical care provider with this SDS. Never give anything by mouth to an unconscious person

5. FIRE- FIGHTING MEASURES

Extinguishing Media:	Use alcohol resistant foam, carbon dioxide, or dry chemical when fighting fires. Water or foam may cause frothing if liquid is burning but it still may be a useful extinguishing agent if carefully applied to the surface of the fire. Do Not direct a stream of water into the hot burning liquid. Use methods suitable to fight surrounding fire.
Fire and/or Explosion Hazards:	No data.
Fire Fighting Methods and Protection:	Use methods for the surrounding fire.
Hazardous Combustion Products:	Carbon dioxide, Carbon monoxide

6. ACCIDENTAL RELEASE MEASURES

Personal Precautions and Equipment:	Exposure to the spilled material may be severely irritating or toxic. Follow personal protective equipment recommendations found in Section 8 of this SDS. Personal protective equipment needs must be evaluated based on information provided on this sheet and the special circumstances created by the spill including; the material spilled, the quantity of the spill, the area in which the spill occurred, and the expertise of employees in the area responding to the spill. Never exceed any occupational exposure limits.
Methods for Clean-up:	Prevent the spread of any spill to minimize harm to human health and the environment if safe to do so. Wear complete and proper personal protective equipment following the recommendation of Section 8 at a minimum. Dike with suitable absorbent material like granulated clay. Gather and store in a sealed container pending a waste disposal evaluation.

7. HANDLING AND STORAGE

Handling Technical Measures and Precautions:	Toxic or severely irritating material. Avoid contacting and avoid breathing the material. Use only in a well ventilated area.
Storage Technical Measures and Conditions:	Store in a cool dry place. Isolate from incompatible materials.

8. EXPOSURE CONTROLS / PERSONAL PROTECTION

United States:

Chemical Name	CAS No.	IDLH	ACGIH STEL	ACGIH TLV-TWA	OSHA Exposure Limit
Dichloromethane	75-09-2	2300 ppm IDLH	No data available.	50 ppm TWA	25 ppm TWA; 125 ppm STEL (15 min. TWA)
dibenz (a,h) anthracene	53-70-3	No data available.	No data available.	No data available.	No data available.

Personal Protection:

Engineering Measures:	Local exhaust ventilation or other engineering controls are normally required when handling or using this product to avoid overexposure.
Respiratory Protection:	Respiratory protection may be required to avoid overexposure when handling this product. General or local exhaust ventilation is the preferred means of protection. Use a respirator if general room ventilation is not available or sufficient to eliminate symptoms.
Eye Protection:	Wear chemically resistant safety glasses with side shields when handling this product. Wear additional eye protection such as chemical splash goggles and/or face shield when the possibility exists for eye contact with splashing or spraying

	liquid, or airborne material. Do not wear contact lenses. Have an eye wash station available.
Skin Protection:	Avoid skin contact by wearing chemically resistant gloves, an apron and other protective equipment depending upon conditions of use. Inspect gloves for chemical break-through and replace at regular intervals. Clean protective equipment regularly. Wash hands and other exposed areas with mild soap and water before eating, drinking, and when leaving work.
Medical Conditions Aggravated By Exposure:	Eye disease Skin disease including eczema and sensitization Respiratory disease including asthma and bronchitis

9. PHYSICAL AND CHEMICAL PROPERTIES

Appearance, color:	Colorless
Odor:	Strong
Physical State:	No data available.
pH:	No data available.
Vapor Pressure:	No data available.
Vapor Density:	2.93 (air = 1)
Boiling Point:	No data available.
Melting Point:	-96.7 °C
Flash Point:	No data available.
Upper Flammable/Explosive Limit, % in air:	No data available.
Lower Flammable/Explosive Limit, % in air:	No data available.
Autoignition Temperature:	556 deg C
Decomposition Temperature:	No data available.
Specific Gravity:	1.3254 - 1.3258 g/cm3 at 20 °C
Evaporation Rate:	No data available.
Odor Threshold:	ND
Solubility:	Moderate; 50-99%
Partition Coefficient: n-octanol in water:	No data available.
VOC % by weight:	0
Molecular Weight:	No data available.

10. STABILITY AND REACTIVITY

Stability:	Stable under normal conditions.
Conditions to Avoid:	No data available.Contamination High temperatures
Materials to Avoid / Chemical Incompatiability:	Strong oxidizing agents Caustics (bases)
Hazardous Decomposition Products:	Carbon dioxide Carbon monoxide

11. TOXICOLOGICAL INFORMATION

Routes of Entry:	Inhalation Absorption Ingestion Skin contact Eye contact
Target Organs Potentially Affected By Exposure:	Skin, Cardiovascular System, Eyes, Liver
Chemical Interactions That Change Toxicity:	None Known

Immediate (Acute) Health Effects by Route of Exposure:

Inhalation Irritation:	Can cause moderate respiratory irritation, dizziness, weakness, fatigue, nausea and headache.
Inhalation Toxicity:	Harmful! Can cause systemic damage (see "Target Organs)Inhalation may cause severe central nervous system depression (including unconsciousness).
Skin Contact:	Contact causes severe skin irritation and possible burns.
Skin Absorption:	Harmful if absorbed through the skin. May cause severe irritation and systemic damage.
Eye Contact:	Contact with the eyes may cause moderate to severe eye injury. Eye contact may result in tearing and reddening, but not likely to permanently injure eye tissue. Temporary vision impairment (cloudy or blurred vision) is possible.
Ingestion Irritation:	Irritating to mouth, throat, and stomach. Can cause abdominal discomfort, nausea, vomiting and diarrhea.
Ingestion Toxicity:	Harmful if swallowed. May cause systemic poisoning.

Long-Term (Chronic) Health Effects:

Carcinogenicity:	Contains a probable or known human carcinogen.
Reproductive and Developmental Toxicity:	No data available to indicate product or any components present at greater than 0.1% may cause birth defects.
Inhalation:	Upon prolonged and/or repeated exposure, can cause moderate respiratory irritation, dizziness, weakness, fatigue, nausea and headache.Harmful! Can cause systemic

damage upon prolonged and/or repeated exposure (see "Target Organs)

Skin Absorption: Upon prolonged or repeated exposure, harmful if absorbed through the skin. May cause severe irritation and systemic damage

Component Toxicological Data:
NIOSH:

Chemical Name	CAS No.	LD50/LC50
Methane, dichloro-	75-09-2	Inhalation LC50 Rat 53 mg/L 6 h

Component Carcinogenic Data:
OSHA:

Chemical Name	CAS No.	
Methylene chloride	75-09-2	25 ppm TWA (8 hr.); 125 ppm STEL (15 min.); 12.5 ppm Action Level (see 29 CFR 1910.1051); effective date for respiratory protection for certain employers to acheive the 8-hour TWA PEL is August 31, 1998; the start up date to install engineering controls is December 10, 1998.; {OSHA - 29 CFR 1910 Specifically Regulate
Dibenz[a,h]anthracene	53-70-3	Present

ACGIH:

Chemical Name	CAS No.	
Dichloromethane	75-09-2	A3 - Confirmed Animal Carcinogen with Unknown Relevance to Humans

NIOSH:

Chemical Name	CAS No.	
Methylene chloride	75-09-2	potential occupational carcinogen

NTP:

Chemical Name	CAS No.
No data available.	

IARC:

Chemical Name	CAS No.	Group No.
No data.		Group 1
Dichloromethane	75-09-2	Group 2A
Dibenz[a,h]anthracene	53-70-3	Group 2A
No data.		Group 2B

12. ECOLOGICAL INFORMATION

Overview: Moderate ecological hazard. This product may be dangerous to plants and/or wildlife. Keep out of waterways.
Mobility: No data
Persistence: No data
Bioaccumulation: No data
Degradability: No data
Ecological Toxicity Data: No data available.

13. DISPOSAL CONSIDERATIONS

Waste Description of Spent Product: Spent or discarded material is a hazardous waste.
Disposal Methods: Incinerate spent or discarded material a permitted hazardous waste facility.
Waste Disposal of Packaging: Comply with all Local, State, Federal, and Provincial Environmental Regulations.

14. TRANSPORTATION INFORMATION

United States:
DOT Proper Shipping Name: Dichloromethane
UN Number: UN1593
Hazard Class: 6.1
Packing Group: III

International:

IATA Proper Shipping Name:	Dichloromethane
UN Number:	UN1593
Hazard Class:	6.1
Packing Group:	III

Marine Pollutant: No

Chemical Name	CAS#	Marine Pollutant	Severe Marine Pollutant
No data available.			

15. REGULATORY INFORMATION

United States:

Chemical Name	CAS#	CERCLA	SARA 313	SARA EHS 313	TSCA
Dichloromethane	75-09-2	X	X	-	X
dibenz (a,h) anthracene	53-70-3	X	X	-	X

The following chemicals are listed on CA Prop 65:

Chemical Name	CAS #	Regulation
Dichloromethane Dichloromethane (Methylene chloride)	75-09-2	Prop 65 Cancer
Dibenz[a,h]anthracene	53-70-3	Prop 65 Cancer

State Right To Know Listing:

Chemical Name	CAS#	New Jersey	Massachusetts	Pennsylvania	California
Dichloromethane	75-09-2	X	X	X	X
dibenz (a,h) anthracene	53-70-3	X	X	X	X

16. OTHER INFORMATION

Prior Version Date: 05/15/14

Other Information: Any changes to the SDS compared to previous versions are marked by a vertical line in front of the concerned paragraph.

References: No data available.

Disclaimer: Restek Corporation provides the descriptions, data and information contained herein in good faith but makes no representation as to its comprehensiveness or accuracy. It is provided for your guidance only. Because many factors may affect processing or application/use, Restek Corporation recommends you perform an assessment to determine the suitability of a product for your particular purpose prior to use. No warranties of any kind, either expressed or implied, including fitness for a particular purpose, are made regarding prodcuts described, data or information set forth. In no case shall the descriptions, information, or data provided be considered a part of our terms and conditions of sale. Further, the descriptions, data and information furnished hereunder are given gratis. No obligation or liability for the description, data and information given are assumed. All such being given and accepted at your risk.

SAFETY DATA SHEET

Version 5.5
Revision Date 05/27/2016
Print Date 07/04/2016

1. PRODUCT AND COMPANY IDENTIFICATION

1.1 Product identifiers

Product name : Dieldrin

Product Number : 33491
Brand : Sigma-Aldrich
Index-No. : 602-049-00-9

CAS-No. : 60-57-1

1.2 Relevant identified uses of the substance or mixture and uses advised against

Identified uses : Laboratory chemicals, Synthesis of substances

1.3 Details of the supplier of the safety data sheet

Company : Sigma-Aldrich
3050 Spruce Street
SAINT LOUIS MO 63103
USA

Telephone : +1 800-325-5832
Fax : +1 800-325-5052

1.4 Emergency telephone number

Emergency Phone # : (314) 776-6555

2. HAZARDS IDENTIFICATION

2.1 Classification of the substance or mixture

GHS Classification in accordance with 29 CFR 1910 (OSHA HCS)
Acute toxicity, Oral (Category 2), H300
Acute toxicity, Dermal (Category 1), H310
Carcinogenicity (Category 2), H351
Specific target organ toxicity - repeated exposure, Oral (Category 1), H372
Acute aquatic toxicity (Category 1), H400
Chronic aquatic toxicity (Category 1), H410

For the full text of the H-Statements mentioned in this Section, see Section 16.

2.2 GHS Label elements, including precautionary statements

Pictogram

Signal word Danger

Hazard statement(s)
H300 + H310 Fatal if swallowed or in contact with skin
H351 Suspected of causing cancer.
H372 Causes damage to organs through prolonged or repeated exposure if swallowed.
H410 Very toxic to aquatic life with long lasting effects.

Precautionary statement(s)
P201 Obtain special instructions before use.

P202	Do not handle until all safety precautions have been read and understood.
P260	Do not breathe dust/ fume/ gas/ mist/ vapours/ spray.
P262	Do not get in eyes, on skin, or on clothing.
P264	Wash skin thoroughly after handling.
P270	Do not eat, drink or smoke when using this product.
P273	Avoid release to the environment.
P280	Wear protective gloves/ protective clothing/ eye protection/ face protection.
P301 + P310 + P330	IF SWALLOWED: Immediately call a POISON CENTER/doctor. Rinse mouth.
P302 + P350 + P310	IF ON SKIN: Gently wash with plenty of soap and water. Immediately call a POISON CENTER or doctor/ physician.
P308 + P313	IF exposed or concerned: Get medical advice/ attention.
P362	Take off contaminated clothing and wash before reuse.
P391	Collect spillage.
P405	Store locked up.
P501	Dispose of contents/ container to an approved waste disposal plant.

2.3 Hazards not otherwise classified (HNOC) or not covered by GHS - none

3. COMPOSITION/INFORMATION ON INGREDIENTS

3.1 Substances

Synonyms : 1,2,3,4,10,10-Hexachloro-1,4,4a,5,6,7,8,8a-octahydro-6,7-epoxy-1,4:5,8-dimethanonaphthalene

Formula : $C_{12}H_8Cl_6O$

Molecular weight : 380.91 g/mol

CAS-No. : 60-57-1

EC-No. : 200-484-5

Index-No. : 602-049-00-9

Hazardous components

Component	Classification	Concentration
Dieldrin		
	Acute Tox. 2; Acute Tox. 1; Carc. 2; STOT RE 1; Aquatic Acute 1; Aquatic Chronic 1; H300 + H310, H351, H372, H410	<= 100 %

For the full text of the H-Statements mentioned in this Section, see Section 16.

4. FIRST AID MEASURES

4.1 Description of first aid measures

General advice
Consult a physician. Show this safety data sheet to the doctor in attendance.Move out of dangerous area.

If inhaled
If breathed in, move person into fresh air. If not breathing, give artificial respiration. Consult a physician.

In case of skin contact
Wash off with soap and plenty of water. Take victim immediately to hospital. Consult a physician.

In case of eye contact
Flush eyes with water as a precaution.

If swallowed
Never give anything by mouth to an unconscious person. Rinse mouth with water. Consult a physician.

4.2 Most important symptoms and effects, both acute and delayed

The most important known symptoms and effects are described in the labelling (see section 2.2) and/or in section 11

4.3 Indication of any immediate medical attention and special treatment needed
No data available

5. FIREFIGHTING MEASURES

5.1 Extinguishing media

Suitable extinguishing media
Use water spray, alcohol-resistant foam, dry chemical or carbon dioxide.

5.2 Special hazards arising from the substance or mixture
No data available

5.3 Advice for firefighters
Wear self-contained breathing apparatus for firefighting if necessary.

5.4 Further information
No data available

6. ACCIDENTAL RELEASE MEASURES

6.1 Personal precautions, protective equipment and emergency procedures
Wear respiratory protection. Avoid dust formation. Avoid breathing vapours, mist or gas. Ensure adequate ventilation. Evacuate personnel to safe areas. Avoid breathing dust.
For personal protection see section 8.

6.2 Environmental precautions
Prevent further leakage or spillage if safe to do so. Do not let product enter drains. Discharge into the environment must be avoided.

6.3 Methods and materials for containment and cleaning up
Pick up and arrange disposal without creating dust. Sweep up and shovel. Keep in suitable, closed containers for disposal.

6.4 Reference to other sections
For disposal see section 13.

7. HANDLING AND STORAGE

7.1 Precautions for safe handling
Avoid contact with skin and eyes. Avoid formation of dust and aerosols.Further processing of solid materials may result in the formation of combustible dusts. The potential for combustible dust formation should be taken into consideration before additional processing occurs.
Provide appropriate exhaust ventilation at places where dust is formed.
For precautions see section 2.2.

7.2 Conditions for safe storage, including any incompatibilities
Keep container tightly closed in a dry and well-ventilated place.

7.3 Specific end use(s)
Apart from the uses mentioned in section 1.2 no other specific uses are stipulated

8. EXPOSURE CONTROLS/PERSONAL PROTECTION

8.1 Control parameters

Components with workplace control parameters

Component	CAS-No.	Value	Control parameters	Basis
Dieldrin	60-57-1	TWA	0.100000 mg/m3	USA. ACGIH Threshold Limit Values (TLV)
	Remarks	Central Nervous System impairment Liver damage Reproductive effects Confirmed animal carcinogen with unknown relevance to humans		

		Danger of cutaneous absorption		
		TWA	0.250000 mg/m3	USA. NIOSH Recommended Exposure Limits
		Potential Occupational Carcinogen See Appendix A Potential for dermal absorption		
		TWA	0.250000 mg/m3	USA. Occupational Exposure Limits (OSHA) - Table Z-1 Limits for Air Contaminants
		Skin designation		
		TWA	0.1 mg/m3	USA. ACGIH Threshold Limit Values (TLV)
		Central Nervous System impairment Liver damage Reproductive effects Confirmed animal carcinogen with unknown relevance to humans Danger of cutaneous absorption		
		TWA	0.25 mg/m3	USA. NIOSH Recommended Exposure Limits
		Potential Occupational Carcinogen See Appendix A Potential for dermal absorption		
		TWA	0.25 mg/m3	USA. Occupational Exposure Limits (OSHA) - Table Z-1 Limits for Air Contaminants
		Skin designation		
		TWA	0.25 mg/m3	USA. OSHA - TABLE Z-1 Limits for Air Contaminants - 1910.1000
		Skin notation		
		PEL	0.25 mg/m3	California permissible exposure limits for chemical contaminants (Title 8, Article 107)
		Skin		

8.2 Exposure controls

Appropriate engineering controls
Avoid contact with skin, eyes and clothing. Wash hands before breaks and immediately after handling the product.

Personal protective equipment

Eye/face protection
Face shield and safety glasses Use equipment for eye protection tested and approved under appropriate government standards such as NIOSH (US) or EN 166(EU).

Skin protection
Handle with gloves. Gloves must be inspected prior to use. Use proper glove removal technique (without touching glove's outer surface) to avoid skin contact with this product. Dispose of contaminated gloves after use in accordance with applicable laws and good laboratory practices. Wash and dry hands.

Full contact
Material: Nitrile rubber
Minimum layer thickness: 0.11 mm
Break through time: 480 min
Material tested:Dermatril® (KCL 740 / Aldrich Z677272, Size M)

Splash contact
Material: Nitrile rubber
Minimum layer thickness: 0.11 mm
Break through time: 480 min
Material tested:Dermatril® (KCL 740 / Aldrich Z677272, Size M)

data source: KCL GmbH, D-36124 Eichenzell, phone +49 (0)6659 87300, e-mail sales@kcl.de, test method: EN374

If used in solution, or mixed with other substances, and under conditions which differ from EN 374, contact the supplier of the CE approved gloves. This recommendation is advisory only and must be evaluated by an industrial hygienist and safety officer familiar with the specific situation of anticipated use by our customers. It should not be construed as offering an approval for any specific use scenario.

Body Protection
Complete suit protecting against chemicals, The type of protective equipment must be selected according to the concentration and amount of the dangerous substance at the specific workplace.

Respiratory protection
Where risk assessment shows air-purifying respirators are appropriate use a full-face particle respirator type N100 (US) or type P3 (EN 143) respirator cartridges as a backup to engineering controls. If the respirator is the sole means of protection, use a full-face supplied air respirator. Use respirators and components tested and approved under appropriate government standards such as NIOSH (US) or CEN (EU).

Control of environmental exposure
Prevent further leakage or spillage if safe to do so. Do not let product enter drains. Discharge into the environment must be avoided.

9. PHYSICAL AND CHEMICAL PROPERTIES

9.1 Information on basic physical and chemical properties

a)	Appearance	Form: solid
b)	Odour	No data available
c)	Odour Threshold	No data available
d)	pH	No data available
e)	Melting point/freezing point	Melting point/range: 143 - 144 °C (289 - 291 °F) - lit.
f)	Initial boiling point and boiling range	No data available
g)	Flash point	No data available
h)	Evaporation rate	No data available
i)	Flammability (solid, gas)	No data available
j)	Upper/lower flammability or explosive limits	No data available
k)	Vapour pressure	No data available
l)	Vapour density	No data available
m)	Relative density	No data available
n)	Water solubility	No data available
o)	Partition coefficient: n-octanol/water	No data available
p)	Auto-ignition temperature	No data available
q)	Decomposition temperature	No data available
r)	Viscosity	No data available
s)	Explosive properties	No data available
t)	Oxidizing properties	No data available

9.2 Other safety information
No data available

10. STABILITY AND REACTIVITY

10.1 Reactivity
No data available

10.2 Chemical stability
Stable under recommended storage conditions.

10.3 Possibility of hazardous reactions
No data available

10.4 Conditions to avoid
No data available

10.5 Incompatible materials
Strong oxidizing agents

10.6 Hazardous decomposition products
Hazardous decomposition products formed under fire conditions. - Carbon oxides, Hydrogen chloride gas
Other decomposition products - No data available
In the event of fire: see section 5

11. TOXICOLOGICAL INFORMATION

11.1 Information on toxicological effects

Acute toxicity
LD50 Oral - Rat - 38.3 mg/kg

Inhalation: No data available

Dermal: No data available

No data available

Skin corrosion/irritation
No data available

Serious eye damage/eye irritation
No data available

Respiratory or skin sensitisation
No data available

Germ cell mutagenicity
No data available

Carcinogenicity

This product is or contains a component that is not classifiable as to its carcinogenicity based on its IARC, ACGIH, NTP, or EPA classification.

Limited evidence of carcinogenicity in animal studies

IARC:	No component of this product present at levels greater than or equal to 0.1% is identified as probable, possible or confirmed human carcinogen by IARC.
NTP:	No component of this product present at levels greater than or equal to 0.1% is identified as a known or anticipated carcinogen by NTP.
OSHA:	No component of this product present at levels greater than or equal to 0.1% is identified as a carcinogen or potential carcinogen by OSHA.

Reproductive toxicity
No data available

No data available

Specific target organ toxicity - single exposure
No data available

Specific target organ toxicity - repeated exposure
Ingestion - Causes damage to organs through prolonged or repeated exposure.

Aspiration hazard
No data available

Additional Information
RTECS: IO1750000

Discomfort, Headache, Nausea, Vomiting, Dizziness, Tremors, tonic convulsions, clonic spasms, Coma., respiratory failure, To the best of our knowledge, the chemical, physical, and toxicological properties have not been thoroughly investigated.

Blood - Irregularities - Based on Human Evidence
Blood - Irregularities - Based on Human Evidence

12. ECOLOGICAL INFORMATION

12.1 Toxicity

Toxicity to fish	mortality LC50 - Carassius auratus (goldfish) - 1.6 µg/l - 96.0 h
Toxicity to daphnia and other aquatic invertebrates	Immobilization EC50 - Daphnia magna (Water flea) - 79.5 µg/l - 48 h

12.2 Persistence and degradability
No data available

12.3 Bioaccumulative potential
No data available

12.4 Mobility in soil
No data available

12.5 Results of PBT and vPvB assessment
PBT/vPvB assessment not available as chemical safety assessment not required/not conducted

12.6 Other adverse effects
An environmental hazard cannot be excluded in the event of unprofessional handling or disposal.
Very toxic to aquatic life with long lasting effects.

13. DISPOSAL CONSIDERATIONS

13.1 Waste treatment methods

Product
Offer surplus and non-recyclable solutions to a licensed disposal company. Contact a licensed professional waste disposal service to dispose of this material. Dissolve or mix the material with a combustible solvent and burn in a chemical incinerator equipped with an afterburner and scrubber.

Contaminated packaging
Dispose of as unused product.

14. TRANSPORT INFORMATION

DOT (US)
UN number: 2811 Class: 6.1 Packing group: I
Proper shipping name: Toxic solids, organic, n.o.s. (Dieldrin)
Reportable Quantity (RQ): 1 lbs
Marine pollutant:yes
Poison Inhalation Hazard: No

IMDG
UN number: 2811 Class: 6.1 Packing group: I EMS-No: F-A, S-A
Proper shipping name: TOXIC SOLID, ORGANIC, N.O.S. (Dieldrin)

Marine pollutant:yes

IATA

UN number: 2811 Class: 6.1 Packing group: I

Proper shipping name: Toxic solid, organic, n.o.s. (Dieldrin)

IATA Passenger: Not permitted for transport

15. REGULATORY INFORMATION

SARA 302 Components

No chemicals in this material are subject to the reporting requirements of SARA Title III, Section 302.

SARA 313 Components

This material does not contain any chemical components with known CAS numbers that exceed the threshold (De Minimis) reporting levels established by SARA Title III, Section 313.

SARA 311/312 Hazards

Acute Health Hazard, Chronic Health Hazard

Massachusetts Right To Know Components

	CAS-No.	Revision Date
Dieldrin	60-57-1	1993-04-24

Pennsylvania Right To Know Components

	CAS-No.	Revision Date
Dieldrin	60-57-1	1993-04-24

New Jersey Right To Know Components

	CAS-No.	Revision Date
Dieldrin	60-57-1	1993-04-24

California Prop. 65 Components

WARNING! This product contains a chemical known to the State of California to cause cancer. Dieldrin	CAS-No. 60-57-1	Revision Date 2007-09-28

16. OTHER INFORMATION

Full text of H-Statements referred to under sections 2 and 3.

Acute Tox.	Acute toxicity
Aquatic Acute	Acute aquatic toxicity
Aquatic Chronic	Chronic aquatic toxicity
Carc.	Carcinogenicity
H300	Fatal if swallowed.
H300 + H310	Fatal if swallowed or in contact with skin
H310	Fatal in contact with skin.
H351	Suspected of causing cancer.
H372	Causes damage to organs through prolonged or repeated exposure if swallowed.

HMIS Rating

Health hazard:	4
Chronic Health Hazard:	*
Flammability:	0
Physical Hazard	0

NFPA Rating

Health hazard:	4
Fire Hazard:	0
Reactivity Hazard:	0

Further information

Copyright 2016 Sigma-Aldrich Co. LLC. License granted to make unlimited paper copies for internal use only.
The above information is believed to be correct but does not purport to be all inclusive and shall be used only as a guide. The information in this document is based on the present state of our knowledge and is applicable to the product with regard to appropriate safety precautions. It does not represent any guarantee of the properties of the product. Sigma-Aldrich Corporation and its Affiliates shall not be held liable for any damage resulting from handling or from contact with the above product. See www.sigma-aldrich.com and/or the reverse side of invoice or packing slip for additional terms and conditions of sale.

Preparation Information

Sigma-Aldrich Corporation
Product Safety – Americas Region
1-800-521-8956

Version: 5.5 Revision Date: 05/27/2016 Print Date: 07/04/2016

SAFETY DATA SHEET

Version 5.7
Revision Date 06/03/2016
Print Date 07/04/2016

1. PRODUCT AND COMPANY IDENTIFICATION

1.1 Product identifiers

Product name : Diesel Fuel No. 2

Product Number : UST147
Brand : Sigma-Aldrich

1.2 Relevant identified uses of the substance or mixture and uses advised against

Identified uses : Laboratory chemicals, Synthesis of substances

1.3 Details of the supplier of the safety data sheet

Company : Sigma-Aldrich
3050 Spruce Street
SAINT LOUIS MO 63103
USA

Telephone : +1 800-325-5832
Fax : +1 800-325-5052

1.4 Emergency telephone number

Emergency Phone # : (314) 776-6555

2. HAZARDS IDENTIFICATION

2.1 Classification of the substance or mixture

GHS Classification in accordance with 29 CFR 1910 (OSHA HCS)
Skin irritation (Category 2), H315
Eye irritation (Category 2A), H319
Carcinogenicity (Category 2), H351
Specific target organ toxicity - single exposure (Category 3), Respiratory system, Central nervous system, H335, H336
Specific target organ toxicity - repeated exposure, Oral (Category 2), Liver, Blood, H373
Specific target organ toxicity - repeated exposure, Inhalation (Category 2), Central nervous system, H373

For the full text of the H-Statements mentioned in this Section, see Section 16.

2.2 GHS Label elements, including precautionary statements

Pictogram

Signal word Warning

Hazard statement(s)

H315	Causes skin irritation.
H319	Causes serious eye irritation.
H335	May cause respiratory irritation.
H336	May cause drowsiness or dizziness.
H351	Suspected of causing cancer.
H373	May cause damage to organs (Liver, Blood) through prolonged or repeated exposure if swallowed.
H373	May cause damage to organs (Central nervous system) through prolonged or repeated exposure if inhaled.

Precautionary statement(s)

P201	Obtain special instructions before use.
P202	Do not handle until all safety precautions have been read and understood.
P260	Do not breathe dust/ fume/ gas/ mist/ vapours/ spray.
P264	Wash skin thoroughly after handling.
P271	Use only outdoors or in a well-ventilated area.
P280	Wear protective gloves/ protective clothing/ eye protection/ face protection.
P302 + P352	IF ON SKIN: Wash with plenty of soap and water.
P304 + P340 + P312	IF INHALED: Remove person to fresh air and keep comfortable for breathing. Call a POISON CENTER/doctor if you feel unwell.
P305 + P351 + P338	IF IN EYES: Rinse cautiously with water for several minutes. Remove contact lenses, if present and easy to do. Continue rinsing.
P308 + P313	IF exposed or concerned: Get medical advice/ attention.
P332 + P313	If skin irritation occurs: Get medical advice/ attention.
P337 + P313	If eye irritation persists: Get medical advice/ attention.
P362	Take off contaminated clothing and wash before reuse.
P403 + P233	Store in a well-ventilated place. Keep container tightly closed.
P405	Store locked up.
P501	Dispose of contents/ container to an approved waste disposal plant.

2.3 Hazards not otherwise classified (HNOC) or not covered by GHS - none

3. COMPOSITION/INFORMATION ON INGREDIENTS

3.2 Mixtures

Hazardous components

Component		Classification	Concentration
Methylene chloride			
CAS-No. EC-No. Index-No.	75-09-2 200-838-9 602-004-00-3	Skin Irrit. 2; Eye Irrit. 2A; Carc. 2; STOT SE 3; STOT RE 2; H315, H319, H335, H336, H351, H373, H373	>= 90 - <= 100 %
Fuels, diesel, no. 2			
CAS-No. EC-No. Index-No.	68476-34-6 270-676-1 649-227-00-2	Flam. Liq. 4; Carc. 2; STOT SE 3; Asp. Tox. 1; Aquatic Acute 2; Aquatic Chronic 2; H227, H304, H336, H351, H411	>= 0.1 - < 1 %

For the full text of the H-Statements mentioned in this Section, see Section 16.

4. FIRST AID MEASURES

4.1 Description of first aid measures

General advice
Move out of dangerous area.Consult a physician. Show this safety data sheet to the doctor in attendance.

If inhaled
If breathed in, move person into fresh air. If not breathing, give artificial respiration. Consult a physician.

In case of skin contact
Wash off with soap and plenty of water. Consult a physician.

In case of eye contact
Rinse thoroughly with plenty of water for at least 15 minutes and consult a physician.

If swallowed
Never give anything by mouth to an unconscious person. Rinse mouth with water. Consult a physician.

4.2 Most important symptoms and effects, both acute and delayed

The most important known symptoms and effects are described in the labelling (see section 2.2) and/or in section 11

4.3 Indication of any immediate medical attention and special treatment needed
No data available

5. FIREFIGHTING MEASURES

5.1 Extinguishing media

Suitable extinguishing media
Use water spray, alcohol-resistant foam, dry chemical or carbon dioxide.

5.2 Special hazards arising from the substance or mixture
No data available

5.3 Advice for firefighters
Wear self-contained breathing apparatus for firefighting if necessary.

5.4 Further information
No data available

6. ACCIDENTAL RELEASE MEASURES

6.1 Personal precautions, protective equipment and emergency procedures
Use personal protective equipment. Avoid breathing vapours, mist or gas. Ensure adequate ventilation. Evacuate personnel to safe areas.
For personal protection see section 8.

6.2 Environmental precautions
Prevent further leakage or spillage if safe to do so. Do not let product enter drains.

6.3 Methods and materials for containment and cleaning up
Soak up with inert absorbent material and dispose of as hazardous waste. Keep in suitable, closed containers for disposal.

6.4 Reference to other sections
For disposal see section 13.

7. HANDLING AND STORAGE

7.1 Precautions for safe handling
Avoid contact with skin and eyes. Avoid inhalation of vapour or mist.
For precautions see section 2.2.

7.2 Conditions for safe storage, including any incompatibilities
Keep container tightly closed in a dry and well-ventilated place. Containers which are opened must be carefully resealed and kept upright to prevent leakage.

Store at Room Temperature.

7.3 Specific end use(s)
Apart from the uses mentioned in section 1.2 no other specific uses are stipulated

8. EXPOSURE CONTROLS/PERSONAL PROTECTION

8.1 Control parameters

Components with workplace control parameters

Component	CAS-No.	Value	Control parameters	Basis
	Remarks	Potential Occupational Carcinogen See Appendix A		
Methylene chloride	75-09-2	TWA	50.000000 ppm	USA. ACGIH Threshold Limit Values (TLV)
		Central Nervous System impairment Carboxyhemoglobinemia Substances for which there is a Biological Exposure Index or Indices (see BEI® section)		

		Confirmed animal carcinogen with unknown relevance to humans		
		TWA	50 ppm	USA. ACGIH Threshold Limit Values (TLV)
		Central Nervous System impairment Carboxyhemoglobinemia Substances for which there is a Biological Exposure Index or Indices (see BEI® section) Confirmed animal carcinogen with unknown relevance to humans		
		Substance listed; for more information see OSHA document 1910.1052		
		Substance listed; for more information see OSHA document 1910.1052		
		See Table Z-2		
		PEL	25.000000 ppm	OSHA Specifically Regulated Chemicals/Carcinogens
		1910.1052 This section applies to all occupational exposures to methylene chloride (MC), Chemical Abstracts Service Registry Number 75-09-2, in general industry, construction and shipyard employment. Methylene chloride (MC) means an organic compound with chemical formula, CH2Cl2. Its Chemical Abstracts Service Registry Number is 75-09-2. Its molecular weight is 84.9 g/mole OSHA specifically regulated carcinogen		
		STEL	125.000000 ppm	OSHA Specifically Regulated Chemicals/Carcinogens
		1910.1052 This section applies to all occupational exposures to methylene chloride (MC), Chemical Abstracts Service Registry Number 75-09-2, in general industry, construction and shipyard employment. Methylene chloride (MC) means an organic compound with chemical formula, CH2Cl2. Its Chemical Abstracts Service Registry Number is 75-09-2. Its molecular weight is 84.9 g/mole OSHA specifically regulated carcinogen		
		PEL	25 ppm 87 mg/m3	California permissible exposure limits for chemical contaminants (Title 8, Article 107)
		see section 5202		
		STEL	125 ppm 435 mg/m3	California permissible exposure limits for chemical contaminants (Title 8, Article 107)
		see section 5202		
Fuels, diesel, no. 2	68476-34-6	TWA	100.000000 mg/m3	USA. ACGIH Threshold Limit Values (TLV)
		Dermatitis Confirmed animal carcinogen with unknown relevance to humans Danger of cutaneous absorption varies		
		TWA	100.000000 mg/m3	USA. ACGIH Threshold Limit Values (TLV)
		Dermatitis Confirmed animal carcinogen with unknown relevance to humans Danger of cutaneous absorption varies		
		TWA	100 mg/m3	USA. ACGIH Threshold Limit Values (TLV)
		Dermatitis Confirmed animal carcinogen with unknown relevance to humans Danger of cutaneous absorption varies		

Biological occupational exposure limits

Component	CAS-No.	Parameters	Value	Biological specimen	Basis
Methylene chloride	75-09-2	Dichloromethane	0.3000 mg/l	Urine	ACGIH - Biological Exposure Indices (BEI)
	Remarks	End of shift (As soon as possible after exposure ceases)			

8.2 Exposure controls

Appropriate engineering controls
Handle in accordance with good industrial hygiene and safety practice. Wash hands before breaks and at the end of workday.

Personal protective equipment

Eye/face protection
Face shield and safety glasses Use equipment for eye protection tested and approved under appropriate government standards such as NIOSH (US) or EN 166(EU).

Skin protection
Handle with gloves. Gloves must be inspected prior to use. Use proper glove removal technique (without touching glove's outer surface) to avoid skin contact with this product. Dispose of contaminated gloves after use in accordance with applicable laws and good laboratory practices. Wash and dry hands.

Body Protection
Complete suit protecting against chemicals, The type of protective equipment must be selected according to the concentration and amount of the dangerous substance at the specific workplace.

Respiratory protection
Where risk assessment shows air-purifying respirators are appropriate use a full-face respirator with multi-purpose combination (US) or type ABEK (EN 14387) respirator cartridges as a backup to engineering controls. If the respirator is the sole means of protection, use a full-face supplied air respirator. Use respirators and components tested and approved under appropriate government standards such as NIOSH (US) or CEN (EU).

Control of environmental exposure
Prevent further leakage or spillage if safe to do so. Do not let product enter drains.

9. PHYSICAL AND CHEMICAL PROPERTIES

9.1 Information on basic physical and chemical properties

a)	Appearance	Form: liquid
b)	Odour	No data available
c)	Odour Threshold	No data available
d)	pH	No data available
e)	Melting point/freezing point	No data available
f)	Initial boiling point and boiling range	No data available
g)	Flash point	No data available
h)	Evaporation rate	No data available
i)	Flammability (solid, gas)	No data available
j)	Upper/lower flammability or explosive limits	No data available
k)	Vapour pressure	No data available
l)	Vapour density	No data available
m)	Relative density	No data available

n)	Water solubility	No data available
o)	Partition coefficient: n-octanol/water	No data available
p)	Auto-ignition temperature	No data available
q)	Decomposition temperature	No data available
r)	Viscosity	No data available
s)	Explosive properties	No data available
t)	Oxidizing properties	No data available

9.2 Other safety information
No data available

10. STABILITY AND REACTIVITY

10.1 Reactivity
No data available

10.2 Chemical stability
Stable under recommended storage conditions.

10.3 Possibility of hazardous reactions
No data available

10.4 Conditions to avoid
No data available

10.5 Incompatible materials
Strong oxidizing agents

10.6 Hazardous decomposition products
Hazardous decomposition products formed under fire conditions. - Carbon oxides, Hydrogen chloride gas
Hazardous decomposition products formed under fire conditions. - No data available
In the event of fire: see section 5

11. TOXICOLOGICAL INFORMATION

11.1 Information on toxicological effects

Acute toxicity
No data available

Inhalation: No data available

No data available

Skin corrosion/irritation
No data available

Serious eye damage/eye irritation
No data available

Respiratory or skin sensitisation
No data available

Germ cell mutagenicity
No data available

Carcinogenicity

IARC: No component of this product present at levels greater than or equal to 0.1% is identified as probable, possible or confirmed human carcinogen by IARC.

NTP: No component of this product present at levels greater than or equal to 0.1% is identified as a

known or anticipated carcinogen by NTP.

OSHA: OSHA specifically regulated carcinogen (Methylene chloride)

Reproductive toxicity
No data available
No data available

Specific target organ toxicity - single exposure
No data available

Specific target organ toxicity - repeated exposure
No data available

Aspiration hazard
No data available

Additional Information
RTECS: Not available

To the best of our knowledge, the chemical, physical, and toxicological properties have not been thoroughly investigated.

Stomach - Irregularities - Based on Human Evidence
Stomach - Irregularities - Based on Human Evidence

12. ECOLOGICAL INFORMATION

12.1 Toxicity
No data available

12.2 Persistence and degradability
No data available

12.3 Bioaccumulative potential
No data available

12.4 Mobility in soil
No data available

12.5 Results of PBT and vPvB assessment
PBT/vPvB assessment not available as chemical safety assessment not required/not conducted

12.6 Other adverse effects
No data available

13. DISPOSAL CONSIDERATIONS

13.1 Waste treatment methods

Product
Offer surplus and non-recyclable solutions to a licensed disposal company. Contact a licensed professional waste disposal service to dispose of this material. Dissolve or mix the material with a combustible solvent and burn in a chemical incinerator equipped with an afterburner and scrubber.

Contaminated packaging
Dispose of as unused product.

14. TRANSPORT INFORMATION

DOT (US)
UN number: 1593 Class: 6.1 Packing group: III
Proper shipping name: Dichloromethane, solution
Reportable Quantity (RQ): 10 lbs

Poison Inhalation Hazard: No

IMDG
UN number: 1593 Class: 6.1 Packing group: III EMS-No: F-A, S-A

Proper shipping name: DICHLOROMETHANE, SOLUTION

IATA
UN number: 1593 Class: 6.1 Packing group: III
Proper shipping name: Dichloromethane, solution

15. REGULATORY INFORMATION

SARA 302 Components
No chemicals in this material are subject to the reporting requirements of SARA Title III, Section 302.

SARA 313 Components
This material does not contain any chemical components with known CAS numbers that exceed the threshold (De Minimis) reporting levels established by SARA Title III, Section 313.

SARA 311/312 Hazards
Acute Health Hazard, Chronic Health Hazard

Massachusetts Right To Know Components

	CAS-No.	Revision Date
Methylene chloride	75-09-2	2007-07-01

Pennsylvania Right To Know Components

	CAS-No.	Revision Date
Methylene chloride	75-09-2	2007-07-01

New Jersey Right To Know Components

	CAS-No.	Revision Date
Methylene chloride	75-09-2	2007-07-01

California Prop. 65 Components

WARNING! This product contains a chemical known to the State of California to cause cancer.	CAS-No.	Revision Date
Methylene chloride	75-09-2	2007-09-28

16. OTHER INFORMATION

Full text of H-Statements referred to under sections 2 and 3.

Aquatic Acute	Acute aquatic toxicity
Aquatic Chronic	Chronic aquatic toxicity
Asp. Tox.	Aspiration hazard
Carc.	Carcinogenicity
Eye Irrit.	Eye irritation
Flam. Liq.	Flammable liquids
H227	Combustible liquid.
H304	May be fatal if swallowed and enters airways.
H315	Causes skin irritation.
H319	Causes serious eye irritation.
H335	May cause respiratory irritation.
H336	May cause drowsiness or dizziness.
H351	Suspected of causing cancer.
H373	May cause damage to organs (/$/*_2ORG_REP_ORA/$/) through prolonged or repeated exposure if swallowed.
H411	Toxic to aquatic life with long lasting effects.
Skin Irrit.	Skin irritation
STOT RE	Specific target organ toxicity - repeated exposure
STOT SE	Specific target organ toxicity - single exposure

HMIS Rating
Health hazard: 2
Chronic Health Hazard: *

Flammability:	0
Physical Hazard	1

NFPA Rating

Health hazard:	2
Fire Hazard:	0
Reactivity Hazard:	0

Further information

Copyright 2016 Sigma-Aldrich Co. LLC. License granted to make unlimited paper copies for internal use only.
The above information is believed to be correct but does not purport to be all inclusive and shall be used only as a guide. The information in this document is based on the present state of our knowledge and is applicable to the product with regard to appropriate safety precautions. It does not represent any guarantee of the properties of the product. Sigma-Aldrich Corporation and its Affiliates shall not be held liable for any damage resulting from handling or from contact with the above product. See www.sigma-aldrich.com and/or the reverse side of invoice or packing slip for additional terms and conditions of sale.

Preparation Information

Sigma-Aldrich Corporation
Product Safety – Americas Region
1-800-521-8956

Version: 5.7 Revision Date: 06/03/2016 Print Date: 07/04/2016

SAFETY DATA SHEET

Creation Date 06-Aug-2010 **Revision Date** 30-Oct-2014 **Revision Number** 2

1. Identification

Product Name **Ethylbenzene**

Cat No. : **AC433800000; AC433800010; AC433801000**

Synonyms Ethylbenzol; Phenylethane

Recommended Use Laboratory chemicals.

Uses advised against No Information available

Details of the supplier of the safety data sheet

Company
Fisher Scientific
One Reagent Lane
Fair Lawn, NJ 07410
Tel: (201) 796-7100

Entity / Business Name
Acros Organics
One Reagent Lane
Fair Lawn, NJ 07410

Emergency Telephone Number
For information **US** call: 001-800-ACROS-01 / **Europe** call: +32 14 57 52 11
Emergency Number **US:**001-201-796-7100 / **Europe:** +32 14 57 52 99
CHEMTREC Tel. No.**US:**001-800-424-9300 / **Europe:**001-703-527-3887

2. Hazard(s) identification

Classification

This chemical is considered hazardous by the 2012 OSHA Hazard Communication Standard (29 CFR 1910.1200)

Flammable liquids	Category 2
Acute Inhalation Toxicity - Vapors	Category 4
Carcinogenicity	Category 2
Specific target organ toxicity (single exposure)	Category 3
Target Organs - Respiratory system, Central nervous system (CNS).	
Specific target organ toxicity - (repeated exposure)	Category 2
Aspiration Toxicity	Category 1

Label Elements

Signal Word
Danger

Hazard Statements
Highly flammable liquid and vapor
May be fatal if swallowed and enters airways
Harmful if inhaled
May cause respiratory irritation
May cause drowsiness or dizziness
Suspected of causing cancer
May cause damage to organs through prolonged or repeated exposure

Precautionary Statements
Prevention
Obtain special instructions before use
Do not handle until all safety precautions have been read and understood
Use personal protective equipment as required
Use only outdoors or in a well-ventilated area
Do not breathe dust/fume/gas/mist/vapors/spray
Keep away from heat/sparks/open flames/hot surfaces. - No smoking
Keep container tightly closed
Ground/bond container and receiving equipment
Use explosion-proof electrical/ventilating/lighting/equipment
Use only non-sparking tools
Take precautionary measures against static discharge
Keep cool
Response
IF exposed or concerned: Get medical attention/advice
Inhalation
IF INHALED: Remove victim to fresh air and keep at rest in a position comfortable for breathing
Skin
IF ON SKIN (or hair): Take off immediately all contaminated clothing. Rinse skin with water/shower
Ingestion
IF SWALLOWED: Immediately call a POISON CENTER or doctor/physician
Do NOT induce vomiting
Fire
In case of fire: Use CO2, dry chemical, or foam for extinction
Storage
Store locked up
Store in a well-ventilated place. Keep container tightly closed
Disposal
Dispose of contents/container to an approved waste disposal plant
Hazards not otherwise classified (HNOC)
Harmful to aquatic life with long lasting effects

3. Composition / information on ingredients

Component	CAS-No	Weight %
Ethylbenzene	100-41-4	>95

4. First-aid measures

General Advice If symptoms persist, call a physician.

Eye Contact Rinse immediately with plenty of water, also under the eyelids, for at least 15 minutes. Obtain medical attention.

Skin Contact Wash off immediately with plenty of water for at least 15 minutes. Obtain medical attention.

Inhalation Move to fresh air. If breathing is difficult, give oxygen. Obtain medical attention. Aspiration into lungs can produce severe lung damage.

Ingestion Clean mouth with water and drink afterwards plenty of water. Do not induce vomiting. Call a physician or Poison Control Center immediately. If vomiting occurs naturally, have victim lean forward.

Most important symptoms/effects Breathing difficulties. . Inhalation of high vapor concentrations may cause symptoms like headache, dizziness, tiredness, nausea and vomiting: May cause central nervous system depression

Notes to Physician Treat symptomatically

5. Fire-fighting measures

Suitable Extinguishing Media Use water spray, alcohol-resistant foam, dry chemical or carbon dioxide. Cool closed containers exposed to fire with water spray.

Unsuitable Extinguishing Media Do not use a solid water stream as it may scatter and spread fire

Flash Point 15 °C / 59 °F
Method - No information available

Autoignition Temperature 432 °C / 810 °F

Explosion Limits
Upper 6.8%
Lower 1.2%
Sensitivity to Mechanical Impact No information available
Sensitivity to Static Discharge Yes

Specific Hazards Arising from the Chemical
Flammable. Containers may explode when heated. Vapors may form explosive mixtures with air. Vapors may travel to source of ignition and flash back.

Hazardous Combustion Products
Carbon monoxide (CO) Carbon dioxide (CO_2)
Protective Equipment and Precautions for Firefighters
As in any fire, wear self-contained breathing apparatus pressure-demand, MSHA/NIOSH (approved or equivalent) and full protective gear.

NFPA

Health	Flammability	Instability	Physical hazards
3	3	0	N/A

6. Accidental release measures

Personal Precautions Use personal protective equipment. Ensure adequate ventilation. Remove all sources of ignition. Take precautionary measures against static discharges.

Environmental Precautions Should not be released into the environment. Do not flush into surface water or sanitary sewer system. See Section 12 for additional ecological information. Avoid release to the environment. Collect spillage.

Methods for Containment and Clean Up Soak up with inert absorbent material. Keep in suitable, closed containers for disposal. Remove all sources of ignition. Use spark-proof tools and explosion-proof equipment.

7. Handling and storage

Handling Wear personal protective equipment. Do not get in eyes, on skin, or on clothing. Avoid ingestion and inhalation. Ensure adequate ventilation. Keep away from open flames, hot surfaces and sources of ignition. Use only non-sparking tools. To avoid ignition of vapors by static electricity discharge, all metal parts of the equipment must be grounded. Take precautionary measures against static discharges.

Storage Keep containers tightly closed in a dry, cool and well-ventilated place. Keep away from heat and sources of ignition. Flammables area.

8. Exposure controls / personal protection

Exposure Guidelines

Component	ACGIH TLV	OSHA PEL	NIOSH IDLH
Ethylbenzene	TWA: 20 ppm	(Vacated) TWA: 100 ppm (Vacated) TWA: 435 mg/m³ (Vacated) STEL: 125 ppm (Vacated) STEL: 545 mg/m³ TWA: 100 ppm TWA: 435 mg/m³	IDLH: 800 ppm TWA: 100 ppm TWA: 435 mg/m³ STEL: 125 ppm STEL: 545 mg/m³

Component	Quebec	Mexico OEL (TWA)	Ontario TWAEV
Ethylbenzene	TWA: 100 ppm TWA: 434 mg/m³ STEL: 125 ppm STEL: 543 mg/m³	TWA: 100 ppm TWA: 435 mg/m³ STEL: 125 ppm STEL: 545 mg/m³	TWA: 20 ppm

Legend

ACGIH - American Conference of Governmental Industrial Hygienists
OSHA - Occupational Safety and Health Administration
NIOSH IDLH: The National Institute for Occupational Safety and Health Immediately Dangerous to Life or Health

Engineering Measures Use only under a chemical fume hood. Ensure that eyewash stations and safety showers are close to the workstation location. Use explosion-proof electrical/ventilating/lighting/equipment. Ensure adequate ventilation, especially in confined areas.

Personal Protective Equipment

Eye/face Protection Wear appropriate protective eyeglasses or chemical safety goggles as described by OSHA's eye and face protection regulations in 29 CFR 1910.133 or European Standard EN166.

Skin and body protection Long sleeved clothing.

Respiratory Protection Follow the OSHA respirator regulations found in 29 CFR 1910.134 or European Standard EN 149. Use a NIOSH/MSHA or European Standard EN 149 approved respirator if exposure limits are exceeded or if irritation or other symptoms are experienced.

Hygiene Measures Handle in accordance with good industrial hygiene and safety practice.

9. Physical and chemical properties

Physical State	Liquid
Appearance	Colorless
Odor	aromatic
Odor Threshold	No information available
pH	No information available
Melting Point/Range	-95 °C / -139 °F
Boiling Point/Range	136 °C / 276.8 °F
Flash Point	15 °C / 59 °F
Evaporation Rate	No information available
Flammability (solid,gas)	Not applicable
Flammability or explosive limits	
Upper	6.8%
Lower	1.2%
Vapor Pressure	No information available
Vapor Density	No information available
Relative Density	0.860
Solubility	Slightly soluble in water
Partition coefficient; n-octanol/water	No data available

Autoignition Temperature	432 °C / 810 °F
Decomposition Temperature	No information available
Viscosity	No information available
Molecular Formula	C8 H10
Molecular Weight	106.17

10. Stability and reactivity

Reactive Hazard None known, based on information available

Stability Stable under normal conditions.

Conditions to Avoid Incompatible products. Excess heat. Keep away from open flames, hot surfaces and sources of ignition.

Incompatible Materials Strong oxidizing agents

Hazardous Decomposition Products Carbon monoxide (CO), Carbon dioxide (CO_2)

Hazardous Polymerization Hazardous polymerization does not occur.

Hazardous Reactions None under normal processing.

11. Toxicological information

Acute Toxicity

Product Information

Component Information

Component	LD50 Oral	LD50 Dermal	LC50 Inhalation
Ethylbenzene	3500 mg/kg (Rat)	15400 mg/kg (Rabbit)	17.2 mg/L (Rat) 4 h

Toxicologically Synergistic Products No information available

Delayed and immediate effects as well as chronic effects from short and long-term exposure

Irritation May cause eye, skin, and respiratory tract irritation

Sensitization No information available

Carcinogenicity The table below indicates whether each agency has listed any ingredient as a carcinogen.

Component	CAS-No	IARC	NTP	ACGIH	OSHA	Mexico
Ethylbenzene	100-41-4	Group 2B	Not listed	A3	X	Not listed

IARC: (International Agency for Research on Cancer)
Group 2B - Possibly Carcinogenic to Humans
IARC: (International Agency for Research on Cancer)
Group 1 - Carcinogenic to Humans
Group 2A - Probably Carcinogenic to Humans

ACGIH: (American Conference of Governmental Industrial Hygienists)
A1 - Known Human Carcinogen
A2 - Suspected Human Carcinogen
A3 - Animal Carcinogen
ACGIH: (American Conference of Governmental Industrial Hygienists)

Mutagenic Effects No information available

Reproductive Effects No information available.

Developmental Effects No information available.

Teratogenicity No information available.

STOT - single exposure Respiratory system Central nervous system (CNS)
STOT - repeated exposure None known

Aspiration hazard No information available

Symptoms / effects,both acute and delayed Inhalation of high vapor concentrations may cause symptoms like headache, dizziness, tiredness, nausea and vomiting: May cause central nervous system depression

Endocrine Disruptor Information No information available

Other Adverse Effects See actual entry in RTECS for complete information.

12. Ecological information

Ecotoxicity

Do not empty into drains. The product contains following substances which are hazardous for the environment. Toxic to aquatic organisms, may cause long-term adverse effects in the aquatic environment.

Component	Freshwater Algae	Freshwater Fish	Microtox	Water Flea
Ethylbenzene	2.6 - 11.3 mg/L EC50 72 h 438 mg/L EC50 > 96 h 4.6 mg/L EC50 = 72 h 1.7 - 7.6 mg/L EC50 96 h	9.6 mg/L LC50 96 h 9.1 - 15.6 mg/L LC50 96 h 32 mg/L LC50 96 h 7.55 - 11 mg/L LC50 96 h 4.2 mg/L LC50 96 h 11.0 - 18.0 mg/L LC50 96 h	EC50 = 9.68 mg/L 30 min EC50 = 96 mg/L 24 h	1.8 - 2.4 mg/L EC50 48 h

Persistence and Degradability Insoluble in water Persistence is unlikely based on information available.

Bioaccumulation/ Accumulation No information available.

Mobility . Is not likely mobile in the environment due its low water solubility. Will likely be mobile in the environment due to its volatility.

Component	log Pow
Ethylbenzene	3.118

13. Disposal considerations

Waste Disposal Methods Chemical waste generators must determine whether a discarded chemical is classified as a hazardous waste. Chemical waste generators must also consult local, regional, and national hazardous waste regulations to ensure complete and accurate classification.

14. Transport information

DOT

- **UN-No** UN1175
- **Proper Shipping Name** ETHYLBENZENE
- **Hazard Class** 3
- **Packing Group** II

TDG

- **UN-No** UN1175
- **Proper Shipping Name** ETHYLBENZENE
- **Hazard Class** 3
- **Packing Group** II

IATA

- **UN-No** UN1175
- **Proper Shipping Name** ETHYLBENZENE
- **Hazard Class** 3
- **Packing Group** II

IMDG/IMO

- **UN-No** UN1175
- **Proper Shipping Name** ETHYLBENZENE
- **Hazard Class** 3
- **Packing Group** II

15. Regulatory information

All of the components in the product are on the following Inventory lists: X = listed The product is classified and labeled

according to EC directives or corresponding national laws The product is classified and labeled in accordance with Directive 1999/45/EC

International Inventories

Component	TSCA	DSL	NDSL	EINECS	ELINCS	NLP	PICCS	ENCS	AICS	IECSC	KECL
Ethylbenzene	X	X	-	202-849-4	-		X	X	X	X	X

Legend:
X - Listed
E - Indicates a substance that is the subject of a Section 5(e) Consent order under TSCA.
F - Indicates a substance that is the subject of a Section 5(f) Rule under TSCA.
N - Indicates a polymeric substance containing no free-radical initiator in its inventory name but is considered to cover the designated polymer made with any free-radical initiator regardless of the amount used.
P - Indicates a commenced PMN substance
R - Indicates a substance that is the subject of a Section 6 risk management rule under TSCA.
S - Indicates a substance that is identified in a proposed or final Significant New Use Rule
T - Indicates a substance that is the subject of a Section 4 test rule under TSCA.
XU - Indicates a substance exempt from reporting under the Inventory Update Rule, i.e. Partial Updating of the TSCA Inventory Data Base Production and Site Reports (40 CFR 710(B).
Y1 - Indicates an exempt polymer that has a number-average molecular weight of 1,000 or greater.
Y2 - Indicates an exempt polymer that is a polyester and is made only from reactants included in a specified list of low concern reactants that comprises one of the eligibility criteria for the exemption rule.

U.S. Federal Regulations

TSCA 12(b) Not applicable

SARA 313

Component	CAS-No	Weight %	SARA 313 - Threshold Values %
Ethylbenzene	100-41-4	>95	0.1

SARA 311/312 Hazardous Categorization

Acute Health Hazard	Yes
Chronic Health Hazard	Yes
Fire Hazard	Yes
Sudden Release of Pressure Hazard	No
Reactive Hazard	No

Clean Water Act

Component	CWA - Hazardous Substances	CWA - Reportable Quantities	CWA - Toxic Pollutants	CWA - Priority Pollutants
Ethylbenzene	X	1000 lb	X	X

Clean Air Act

Component	HAPS Data	Class 1 Ozone Depletors	Class 2 Ozone Depletors
Ethylbenzene	X		-

OSHA Occupational Safety and Health Administration
Not applicable

CERCLA
This material, as supplied, contains one or more substances regulated as a hazardous substance under the Comprehensive Environmental Response Compensation and Liability Act (CERCLA) (40 CFR 302)

Component	Hazardous Substances RQs	CERCLA EHS RQs
Ethylbenzene	1000 lb	-

California Proposition 65 This product contains the following Proposition 65 chemicals:

Component	CAS-No	California Prop. 65	Prop 65 NSRL	Category
Ethylbenzene	100-41-4	Carcinogen	54 µg/day 41 µg/day	Carcinogen

State Right-to-Know

Component	Massachusetts	New Jersey	Pennsylvania	Illinois	Rhode Island
Ethylbenzene	X	X	X	X	X

U.S. Department of Transportation

Reportable Quantity (RQ): N
DOT Marine Pollutant N
DOT Severe Marine Pollutant N

U.S. Department of Homeland Security
This product does not contain any DHS chemicals.

Other International Regulations

Mexico - Grade Serious risk, Grade 3

Canada
This product has been classified in accordance with the hazard criteria of the Controlled Products Regulations (CPR) and the MSDS contains all the information required by the CPR

WHMIS Hazard Class B2 Flammable liquid
D2A Very toxic materials

16. Other information

Prepared By Regulatory Affairs
Thermo Fisher Scientific
Email: EMSDS.RA@thermofisher.com

Creation Date 06-Aug-2010
Revision Date 30-Oct-2014
Print Date 30-Oct-2014
Revision Summary This document has been updated to comply with the US OSHA HazCom 2012 Standard replacing the current legislation under 29 CFR 1910.1200 to align with the Globally Harmonized System of Classification and Labeling of Chemicals (GHS)

Disclaimer
The information provided on this Safety Data Sheet is correct to the best of our knowledge, information and belief at the date of its publication. The information given is designed only as a guide for safe handling, use, processing, storage, transportation, disposal and release and is not to be considered as a warranty or quality specification. The information relates only to the specific material designated and may not be valid for such material used in combination with any other material or in any process, unless specified in the text.

End of SDS

SAFETY DATA SHEET

Version 4.17
Revision Date 03/03/2015
Print Date 05/01/2016

1. PRODUCT AND COMPANY IDENTIFICATION

1.1 Product identifiers

Product name : Trichlorofluoromethane

Product Number : 254991
Brand : Aldrich

CAS-No. : 75-69-4

1.2 Relevant identified uses of the substance or mixture and uses advised against

Identified uses : Laboratory chemicals, Manufacture of substances

1.3 Details of the supplier of the safety data sheet

Company : Sigma-Aldrich
3050 Spruce Street
SAINT LOUIS MO 63103
USA

Telephone : +1 800-325-5832
Fax : +1 800-325-5052

1.4 Emergency telephone number

Emergency Phone # : (314) 776-6555

2. HAZARDS IDENTIFICATION

2.1 Classification of the substance or mixture

GHS Classification in accordance with 29 CFR 1910 (OSHA HCS)
Acute toxicity, Dermal (Category 4), H312

For the full text of the H-Statements mentioned in this Section, see Section 16.

2.2 GHS Label elements, including precautionary statements

Pictogram

Signal word Warning

Hazard statement(s)
H312 Harmful in contact with skin.

Precautionary statement(s)
P280 Wear protective gloves/ protective clothing.
P302 + P352 + P312 IF ON SKIN: Wash with plenty of soap and water. Call a POISON CENTER or doctor/ physician if you feel unwell.
P363 Wash contaminated clothing before reuse.
P501 Dispose of contents/ container to an approved waste disposal plant.

2.3 Hazards not otherwise classified (HNOC) or not covered by GHS - none

3. COMPOSITION/INFORMATION ON INGREDIENTS

3.1 Substances

Synonyms : Fluorotrichloromethane
CFC-11

Formula	:	CCl_3F CCl_3F
Molecular weight	:	137.37 g/mol
CAS-No.	:	75-69-4
EC-No.	:	200-892-3

Hazardous components

Component	Classification	Concentration
Trichlorofluoromethane		
	Acute Tox. 4; H312	<= 100 %

For the full text of the H-Statements mentioned in this Section, see Section 16.

4. FIRST AID MEASURES

4.1 Description of first aid measures

General advice
Consult a physician. Show this safety data sheet to the doctor in attendance.Move out of dangerous area.

If inhaled
If breathed in, move person into fresh air. If not breathing, give artificial respiration. Consult a physician.

In case of skin contact
Wash off with soap and plenty of water. Consult a physician.

In case of eye contact
Flush eyes with water as a precaution.

If swallowed
Never give anything by mouth to an unconscious person. Rinse mouth with water. Consult a physician.

4.2 Most important symptoms and effects, both acute and delayed
The most important known symptoms and effects are described in the labelling (see section 2.2) and/or in section 11

4.3 Indication of any immediate medical attention and special treatment needed
No data available

5. FIREFIGHTING MEASURES

5.1 Extinguishing media

Suitable extinguishing media
Use water spray, alcohol-resistant foam, dry chemical or carbon dioxide.

5.2 Special hazards arising from the substance or mixture
Carbon oxides, Hydrogen chloride gas, Hydrogen fluoride

5.3 Advice for firefighters
Wear self-contained breathing apparatus for firefighting if necessary.

5.4 Further information
No data available

6. ACCIDENTAL RELEASE MEASURES

6.1 Personal precautions, protective equipment and emergency procedures
Use personal protective equipment. Avoid breathing vapours, mist or gas. Ensure adequate ventilation.
For personal protection see section 8.

6.2 Environmental precautions
Do not let product enter drains.

6.3 Methods and materials for containment and cleaning up
Soak up with inert absorbent material and dispose of as hazardous waste. Keep in suitable, closed containers for disposal.

6.4 Reference to other sections
For disposal see section 13.

7. HANDLING AND STORAGE

7.1 Precautions for safe handling

Avoid contact with skin and eyes. Avoid inhalation of vapour or mist.
For precautions see section 2.2.

7.2 Conditions for safe storage, including any incompatibilities

Keep container tightly closed in a dry and well-ventilated place.

Recommended storage temperature 2 - 8 °C

Contents under pressure.
Storage class (TRGS 510): Non Combustible Liquids

7.3 Specific end use(s)

Apart from the uses mentioned in section 1.2 no other specific uses are stipulated

8. EXPOSURE CONTROLS/PERSONAL PROTECTION

8.1 Control parameters

Components with workplace control parameters

Component	CAS-No.	Value	Control parameters	Basis
Trichlorofluoromethane	75-69-4	C	1,000.000000 ppm	USA. ACGIH Threshold Limit Values (TLV)
	Remarks	Cardiac sensitization Not classifiable as a human carcinogen		
		C	1,000.000000 ppm 5,600.000000 mg/m3	USA. NIOSH Recommended Exposure Limits
		TWA	1,000.000000 ppm 5,600.000000 mg/m3	USA. Occupational Exposure Limits (OSHA) - Table Z-1 Limits for Air Contaminants
		The value in mg/m3 is approximate.		

8.2 Exposure controls

Appropriate engineering controls

Handle in accordance with good industrial hygiene and safety practice. Wash hands before breaks and at the end of workday.

Personal protective equipment

Eye/face protection

Face shield and safety glasses Use equipment for eye protection tested and approved under appropriate government standards such as NIOSH (US) or EN 166(EU).

Skin protection

Handle with gloves. Gloves must be inspected prior to use. Use proper glove removal technique (without touching glove's outer surface) to avoid skin contact with this product. Dispose of contaminated gloves after use in accordance with applicable laws and good laboratory practices. Wash and dry hands.

Full contact
Material: Nitrile rubber
Minimum layer thickness: 0.4 mm
Break through time: 480 min
Material tested:Camatril® (KCL 730 / Aldrich Z677442, Size M)

Splash contact
Material: Nitrile rubber
Minimum layer thickness: 0.2 mm
Break through time: 30 min

Material tested:Dermatril® P (KCL 743 / Aldrich Z677388, Size M)

data source: KCL GmbH, D-36124 Eichenzell, phone +49 (0)6659 87300, e-mail sales@kcl.de, test method: EN374
If used in solution, or mixed with other substances, and under conditions which differ from EN 374, contact the supplier of the CE approved gloves. This recommendation is advisory only and must be evaluated by an industrial hygienist and safety officer familiar with the specific situation of anticipated use by our customers. It should not be construed as offering an approval for any specific use scenario.

Body Protection
Complete suit protecting against chemicals, The type of protective equipment must be selected according to the concentration and amount of the dangerous substance at the specific workplace.

Respiratory protection
Where risk assessment shows air-purifying respirators are appropriate use a full-face respirator with multi-purpose combination (US) or type AXBEK (EN 14387) respirator cartridges as a backup to engineering controls. If the respirator is the sole means of protection, use a full-face supplied air respirator. Use respirators and components tested and approved under appropriate government standards such as NIOSH (US) or CEN (EU).

Control of environmental exposure
Do not let product enter drains.

9. PHYSICAL AND CHEMICAL PROPERTIES

9.1 Information on basic physical and chemical properties

a)	Appearance	Form: liquid, clear Colour: colourless
b)	Odour	No data available
c)	Odour Threshold	No data available
d)	pH	No data available
e)	Melting point/freezing point	-110.99 - -109.99 °C (-167.78 - -165.98 °F)
f)	Initial boiling point and boiling range	23.7 °C (74.7 °F) - lit.
g)	Flash point	No data available
h)	Evaporation rate	No data available
i)	Flammability (solid, gas)	No data available
j)	Upper/lower flammability or explosive limits	No data available
k)	Vapour pressure	885.7 hPa (664.3 mmHg) at 20.0 °C (68.0 °F) 2,701.2 hPa (2,026.1 mmHg) at 55.0 °C (131.0 °F)
l)	Vapour density	No data available
m)	Relative density	1.494 g/cm3 at 25 °C (77 °F)
n)	Water solubility	1 g/l
o)	Partition coefficient: n-octanol/water	log Pow: 2.53
p)	Auto-ignition temperature	No data available
q)	Decomposition temperature	No data available
r)	Viscosity	No data available
s)	Explosive properties	No data available

t) Oxidizing properties No data available

9.2 Other safety information

Surface tension 18.0 mN/m at 25.0 °C (77.0 °F)

10. STABILITY AND REACTIVITY

10.1 Reactivity
No data available

10.2 Chemical stability
Stable under recommended storage conditions.

10.3 Possibility of hazardous reactions
No data available

10.4 Conditions to avoid
No data available

10.5 Incompatible materials
Strong oxidizing agents, Sodium/sodium oxides, Potassium, Magnesium, Aluminum, Zinc

10.6 Hazardous decomposition products
Other decomposition products - No data available
In the event of fire: see section 5

11. TOXICOLOGICAL INFORMATION

11.1 Information on toxicological effects

Acute toxicity
LD50 Oral - Rat - > 15,000 mg/kg

LC50 Inhalation - Rat - 0.3 h - 130000 ppm
Remarks: Behavioral:Tremor. Behavioral:Convulsions or effect on seizure threshold. Respiratory disorder

No data available

Skin corrosion/irritation
No data available

Serious eye damage/eye irritation
No data available

Respiratory or skin sensitisation
No data available

Germ cell mutagenicity
No data available

Carcinogenicity

IARC: No component of this product present at levels greater than or equal to 0.1% is identified as probable, possible or confirmed human carcinogen by IARC.

NTP: No component of this product present at levels greater than or equal to 0.1% is identified as a known or anticipated carcinogen by NTP.

OSHA: No component of this product present at levels greater than or equal to 0.1% is identified as a carcinogen or potential carcinogen by OSHA.

Reproductive toxicity
No data available

No data available

Specific target organ toxicity - single exposure
No data available

Specific target organ toxicity - repeated exposure
No data available

Aspiration hazard
No data available

Additional Information
RTECS: PB6125000

To the best of our knowledge, the chemical, physical, and toxicological properties have not been thoroughly investigated., Nausea, Dizziness, Headache, Vomiting, Diarrhoea, Abdominal pain, Weakness, Unconsciousness

Liver -

12. ECOLOGICAL INFORMATION

12.1 Toxicity
No data available

12.2 Persistence and degradability
No data available

12.3 Bioaccumulative potential
No data available

12.4 Mobility in soil
No data available

12.5 Results of PBT and vPvB assessment
PBT/vPvB assessment not available as chemical safety assessment not required/not conducted

12.6 Other adverse effects

13. DISPOSAL CONSIDERATIONS

13.1 Waste treatment methods

Product
Offer surplus and non-recyclable solutions to a licensed disposal company.

Contaminated packaging
Dispose of as unused product.

14. TRANSPORT INFORMATION

DOT (US)
UN number: 3082 Class: 9 Packing group: III
Proper shipping name: Environmentally hazardous substance, liquid, n.o.s. (Trichlorofluoromethane)
Reportable Quantity (RQ): 5000 lbs

Poison Inhalation Hazard: No

IMDG
Not dangerous goods

IATA
Not dangerous goods

15. REGULATORY INFORMATION

SARA 302 Components
No chemicals in this material are subject to the reporting requirements of SARA Title III, Section 302.

SARA 313 Components
The following components are subject to reporting levels established by SARA Title III, Section 313:

	CAS-No.	Revision Date
Trichlorofluoromethane	75-69-4	2007-07-01

SARA 311/312 Hazards
Acute Health Hazard

Massachusetts Right To Know Components

	CAS-No.	Revision Date
Trichlorofluoromethane	75-69-4	2007-07-01

Pennsylvania Right To Know Components

	CAS-No.	Revision Date
Trichlorofluoromethane	75-69-4	2007-07-01

New Jersey Right To Know Components

	CAS-No.	Revision Date
Trichlorofluoromethane	75-69-4	2007-07-01

California Prop. 65 Components

This product does not contain any chemicals known to State of California to cause cancer, birth defects, or any other reproductive harm.

16. OTHER INFORMATION

Full text of H-Statements referred to under sections 2 and 3.

Acute Tox.	Acute toxicity
H312	Harmful in contact with skin.

HMIS Rating

Health hazard:	1
Chronic Health Hazard:	
Flammability:	0
Physical Hazard	0

NFPA Rating

Health hazard:	1
Fire Hazard:	0
Reactivity Hazard:	0

Further information

Copyright 2015 Sigma-Aldrich Co. LLC. License granted to make unlimited paper copies for internal use only.
The above information is believed to be correct but does not purport to be all inclusive and shall be used only as a guide. The information in this document is based on the present state of our knowledge and is applicable to the product with regard to appropriate safety precautions. It does not represent any guarantee of the properties of the product. Sigma-Aldrich Corporation and its Affiliates shall not be held liable for any damage resulting from handling or from contact with the above product. See www.sigma-aldrich.com and/or the reverse side of invoice or packing slip for additional terms and conditions of sale.

Preparation Information

Sigma-Aldrich Corporation
Product Safety – Americas Region
1-800-521-8956

Version: 4.17 Revision Date: 03/03/2015 Print Date: 05/01/2016

SAFETY DATA SHEET

Halocarbon R-12 (Dichlorodifluoromethane)

Section 1. Identification

GHS product identifier : Halocarbon R-12 (Dichlorodifluoromethane)

Chemical name : dichlorodifluoromethane

Other means of identification : ASPEN R-12, Methane, dichlorodifluoro-; Refrigerant 12; Propellant 12; Halon 122; Genetron 12; Freon 12; Fluorocarbon 12; Difluorodichloromethane; DICHLORODIFLUOROMETHANE (FC 12); CFC-12

Product use : Synthetic/Analytical chemistry.

Synonym : ASPEN R-12, Methane, dichlorodifluoro-; Refrigerant 12; Propellant 12; Halon 122; Genetron 12; Freon 12; Fluorocarbon 12; Difluorodichloromethane; DICHLORODIFLUOROMETHANE (FC 12); CFC-12

SDS # : 001018

Supplier's details : Airgas USA, LLC and its affiliates
259 North Radnor-Chester Road
Suite 100
Radnor, PA 19087-5283
1-610-687-5253

Emergency telephone number (with hours of operation) : 1-866-734-3438

Section 2. Hazards identification

OSHA/HCS status : This material is considered hazardous by the OSHA Hazard Communication Standard (29 CFR 1910.1200).

Classification of the substance or mixture : GASES UNDER PRESSURE - Liquefied gas
HAZARDOUS TO THE OZONE LAYER - Category 1

GHS label elements

Hazard pictograms :

Signal word : Warning

Hazard statements : Contains gas under pressure; may explode if heated.
May cause frostbite.
May displace oxygen and cause rapid suffocation.
Harms public health and the environment by destroying ozone in the upper atmosphere.

Precautionary statements

General : Read and follow all Safety Data Sheets (SDS'S) before use. Read label before use. Keep out of reach of children. If medical advice is needed, have product container or label at hand. Close valve after each use and when empty. Use equipment rated for cylinder pressure. Do not open valve until connected to equipment prepared for use. Use a back flow preventative device in the piping. Use only equipment of compatible materials of construction. Always keep container in upright position.

Prevention : Use and store only outdoors or in a well ventilated place.

Response : Not applicable.

Storage : Protect from sunlight. Protect from sunlight when ambient temperature exceeds 52°C/125°F. Store in a well-ventilated place.

Disposal : Refer to manufacturer/supplier for information on recovery/recycling.

Powered by IHS

Section 2. Hazards identification

Hazards not otherwise classified : Liquid can cause burns similar to frostbite.

Section 3. Composition/information on ingredients

Substance/mixture : Substance

Chemical name : dichlorodifluoromethane

Other means of identification : ASPEN R-12, Methane, dichlorodifluoro-; Refrigerant 12; Propellant 12; Halon 122; Genetron 12; Freon 12; Fluorocarbon 12; Difluorodichloromethane; DICHLORODIFLUOROMETHANE (FC 12); CFC-12

CAS number/other identifiers

CAS number : 75-71-8

Product code : 001018

Ingredient name	%	CAS number
Methane, dichlorodifluoro-	100	75-71-8

There are no additional ingredients present which, within the current knowledge of the supplier and in the concentrations applicable, are classified as hazardous to health or the environment and hence require reporting in this section.

Occupational exposure limits, if available, are listed in Section 8.

Section 4. First aid measures

Description of necessary first aid measures

Eye contact : Immediately flush eyes with plenty of water, occasionally lifting the upper and lower eyelids. Check for and remove any contact lenses. Continue to rinse for at least 10 minutes. Get medical attention if irritation occurs.

Inhalation : Remove victim to fresh air and keep at rest in a position comfortable for breathing. If not breathing, if breathing is irregular or if respiratory arrest occurs, provide artificial respiration or oxygen by trained personnel. It may be dangerous to the person providing aid to give mouth-to-mouth resuscitation. Get medical attention if adverse health effects persist or are severe. If unconscious, place in recovery position and get medical attention immediately. Maintain an open airway. Loosen tight clothing such as a collar, tie, belt or waistband. In case of inhalation of decomposition products in a fire, symptoms may be delayed. The exposed person may need to be kept under medical surveillance for 48 hours.

Skin contact : Flush contaminated skin with plenty of water. Remove contaminated clothing and shoes. Get medical attention if symptoms occur. In case of contact with liquid, warm frozen tissues slowly with lukewarm water and get medical attention. Do not rub affected area. Wash clothing before reuse. Clean shoes thoroughly before reuse.

Ingestion : Remove victim to fresh air and keep at rest in a position comfortable for breathing. Get medical attention if adverse health effects persist or are severe. Ingestion of liquid can cause burns similar to frostbite. If frostbite occurs, get medical attention. Never give anything by mouth to an unconscious person. If unconscious, place in recovery position and get medical attention immediately. Maintain an open airway. Loosen tight clothing such as a collar, tie, belt or waistband. As this product rapidly becomes a gas when released, refer to the inhalation section.

Most important symptoms/effects, acute and delayed

Potential acute health effects

Eye contact : Liquid can cause burns similar to frostbite.

Inhalation : Exposure to decomposition products may cause a health hazard. Serious effects may be delayed following exposure.

Powered by IHS

Section 4. First aid measures

Skin contact : Dermal contact with rapidly evaporating liquid could result in freezing of the tissues or frostbite.

Frostbite : Try to warm up the frozen tissues and seek medical attention.

Ingestion : Ingestion of liquid can cause burns similar to frostbite.

Over-exposure signs/symptoms

Eye contact : Adverse symptoms may include the following:
frostbite

Inhalation : No specific data.

Skin contact : Adverse symptoms may include the following:
frostbite

Ingestion : Adverse symptoms may include the following:
frostbite

Indication of immediate medical attention and special treatment needed, if necessary

Notes to physician : In case of inhalation of decomposition products in a fire, symptoms may be delayed. The exposed person may need to be kept under medical surveillance for 48 hours.

Specific treatments : No specific treatment.

Protection of first-aiders : No action shall be taken involving any personal risk or without suitable training. It may be dangerous to the person providing aid to give mouth-to-mouth resuscitation.

See toxicological information (Section 11)

Section 5. Fire-fighting measures

Extinguishing media

Suitable extinguishing media : Use an extinguishing agent suitable for the surrounding fire.

Unsuitable extinguishing media : None known.

Specific hazards arising from the chemical : Contains gas under pressure. In a fire or if heated, a pressure increase will occur and the container may burst or explode.

Hazardous thermal decomposition products : Decomposition products may include the following materials:
carbon dioxide
carbon monoxide
halogenated compounds
carbonyl halides

Special protective actions for fire-fighters : Promptly isolate the scene by removing all persons from the vicinity of the incident if there is a fire. No action shall be taken involving any personal risk or without suitable training. Contact supplier immediately for specialist advice. Move containers from fire area if this can be done without risk. Use water spray to keep fire-exposed containers cool.

Special protective equipment for fire-fighters : Fire-fighters should wear appropriate protective equipment and self-contained breathing apparatus (SCBA) with a full face-piece operated in positive pressure mode. For incidents involving large quantities, thermally insulated undergarments and thick textile or leather gloves should be worn.

Powered by IHS

Section 6. Accidental release measures

Personal precautions, protective equipment and emergency procedures

For non-emergency personnel : No action shall be taken involving any personal risk or without suitable training. Evacuate surrounding areas. Keep unnecessary and unprotected personnel from entering. Do not touch or walk through spilled material. Avoid breathing gas. Provide adequate ventilation. Wear appropriate respirator when ventilation is inadequate. Put on appropriate personal protective equipment.

For emergency responders : If specialised clothing is required to deal with the spillage, take note of any information in Section 8 on suitable and unsuitable materials. See also the information in "For non-emergency personnel".

Environmental precautions : Ensure emergency procedures to deal with accidental gas releases are in place to avoid contamination of the environment. Avoid dispersal of spilled material and runoff and contact with soil, waterways, drains and sewers. Inform the relevant authorities if the product has caused environmental pollution (sewers, waterways, soil or air). May be harmful to the environment if released in large quantities.

Methods and materials for containment and cleaning up

Small spill : Immediately contact emergency personnel. Stop leak if without risk.

Large spill : Immediately contact emergency personnel. Stop leak if without risk. Note: see Section 1 for emergency contact information and Section 13 for waste disposal.

Section 7. Handling and storage

Precautions for safe handling

Protective measures : Put on appropriate personal protective equipment (see Section 8). Contains gas under pressure. Do not get in eyes or on skin or clothing. Avoid breathing gas. Avoid release to the environment. Refer to special instructions/safety data sheet. Empty containers retain product residue and can be hazardous. Do not puncture or incinerate container. Use equipment rated for cylinder pressure. Close valve after each use and when empty. Protect cylinders from physical damage; do not drag, roll, slide, or drop. Use a suitable hand truck for cylinder movement.

Advice on general occupational hygiene : Eating, drinking and smoking should be prohibited in areas where this material is handled, stored and processed. Workers should wash hands and face before eating, drinking and smoking. Remove contaminated clothing and protective equipment before entering eating areas. See also Section 8 for additional information on hygiene measures.

Conditions for safe storage, including any incompatibilities : Store in accordance with local regulations. Store in a segregated and approved area. Store away from direct sunlight in a dry, cool and well-ventilated area, away from incompatible materials (see Section 10). Keep container tightly closed and sealed until ready for use. Cylinders should be stored upright, with valve protection cap in place, and firmly secured to prevent falling or being knocked over. Cylinder temperatures should not exceed 52 °C (125 °F).

Section 8. Exposure controls/personal protection

Control parameters

Occupational exposure limits

Powered by IHS

Section 8. Exposure controls/personal protection

Ingredient name	Exposure limits
Methane, dichlorodifluoro-	**ACGIH TLV (United States, 3/2012).** TWA: 4950 mg/m³ 8 hours. TWA: 1000 ppm 8 hours. **NIOSH REL (United States, 1/2013).** TWA: 4950 mg/m³ 10 hours. TWA: 1000 ppm 10 hours. **OSHA PEL (United States, 6/2010).** TWA: 4950 mg/m³ 8 hours. TWA: 1000 ppm 8 hours. **OSHA PEL 1989 (United States, 3/1989).** TWA: 4950 mg/m³ 8 hours. TWA: 1000 ppm 8 hours.

Appropriate engineering controls : Good general ventilation should be sufficient to control worker exposure to airborne contaminants.

Environmental exposure controls : Emissions from ventilation or work process equipment should be checked to ensure they comply with the requirements of environmental protection legislation. In some cases, fume scrubbers, filters or engineering modifications to the process equipment will be necessary to reduce emissions to acceptable levels.

Individual protection measures

Hygiene measures : Wash hands, forearms and face thoroughly after handling chemical products, before eating, smoking and using the lavatory and at the end of the working period. Appropriate techniques should be used to remove potentially contaminated clothing. Wash contaminated clothing before reusing. Ensure that eyewash stations and safety showers are close to the workstation location.

Eye/face protection : Safety eyewear complying with an approved standard should be used when a risk assessment indicates this is necessary to avoid exposure to liquid splashes, mists, gases or dusts. If contact is possible, the following protection should be worn, unless the assessment indicates a higher degree of protection: safety glasses with side-shields.

Skin protection

Hand protection : Chemical-resistant, impervious gloves complying with an approved standard should be worn at all times when handling chemical products if a risk assessment indicates this is necessary. If contact with the liquid is possible, insulated gloves suitable for low temperatures should be worn. Considering the parameters specified by the glove manufacturer, check during use that the gloves are still retaining their protective properties. It should be noted that the time to breakthrough for any glove material may be different for different glove manufacturers. In the case of mixtures, consisting of several substances, the protection time of the gloves cannot be accurately estimated.

Body protection : Personal protective equipment for the body should be selected based on the task being performed and the risks involved and should be approved by a specialist before handling this product.

Other skin protection : Appropriate footwear and any additional skin protection measures should be selected based on the task being performed and the risks involved and should be approved by a specialist before handling this product.

Respiratory protection : Use a properly fitted, air-purifying or air-fed respirator complying with an approved standard if a risk assessment indicates this is necessary. Respirator selection must be based on known or anticipated exposure levels, the hazards of the product and the safe working limits of the selected respirator.

Powered by IHS

Section 9. Physical and chemical properties

Appearance

Physical state : Gas. [Liquefied gas]

Color : Colorless.

Molecular weight : 120.91 g/mole

Molecular formula : C-Cl2-F2

Boiling/condensation point : -29.8°C (-21.6°F)

Melting/freezing point : -158°C (-252.4°F)

Critical temperature : 111.85°C (233.3°F)

Odor : Characteristic.

Odor threshold : Not available.

pH : Not available.

Flash point : [Product does not sustain combustion.]

Burning time : Not applicable.

Burning rate : Not applicable.

Evaporation rate : Not available.

Flammability (solid, gas) : Not available.

Lower and upper explosive (flammable) limits : Not available.

Vapor pressure : 84.9 (psia)

Vapor density : 4.2 (Air = 1)

Specific Volume (ft^3/lb) : 3.1746

Gas Density (lb/ft^3) : 0.315

Relative density : Not applicable.

Solubility : Not available.

Solubility in water : 0.3 g/l

Partition coefficient: n-octanol/water : 2.16

Auto-ignition temperature : Not available.

Decomposition temperature : Not available.

SADT : Not available.

Viscosity : Not applicable.

Section 10. Stability and reactivity

Reactivity : No specific test data related to reactivity available for this product or its ingredients.

Chemical stability : The product is stable.

Possibility of hazardous reactions : Under normal conditions of storage and use, hazardous reactions will not occur.

Conditions to avoid : No specific data.

Hazardous decomposition products : Under normal conditions of storage and use, hazardous decomposition products should not be produced.

Powered by IHS

Section 10. Stability and reactivity

Hazardous polymerization : Under normal conditions of storage and use, hazardous polymerization will not occur.

Section 11. Toxicological information

Information on toxicological effects

Acute toxicity

Not available.

Irritation/Corrosion

Not available.

Sensitization

Not available.

Mutagenicity

Not available.

Carcinogenicity

Not available.

Reproductive toxicity

Not available.

Teratogenicity

Not available.

Specific target organ toxicity (single exposure)

Not available.

Specific target organ toxicity (repeated exposure)

Not available.

Aspiration hazard

Not available.

Information on the likely routes of exposure : Not available.

Potential acute health effects

Eye contact : Liquid can cause burns similar to frostbite.

Inhalation : Exposure to decomposition products may cause a health hazard. Serious effects may be delayed following exposure.

Skin contact : Dermal contact with rapidly evaporating liquid could result in freezing of the tissues or frostbite.

Ingestion : Ingestion of liquid can cause burns similar to frostbite.

Symptoms related to the physical, chemical and toxicological characteristics

Eye contact : Adverse symptoms may include the following:
frostbite

Inhalation : No specific data.

Skin contact : Adverse symptoms may include the following:
frostbite

Powered by IHS

Section 11. Toxicological information

Ingestion : Adverse symptoms may include the following:
frostbite

Delayed and immediate effects and also chronic effects from short and long term exposure

Short term exposure

Potential immediate effects : Not available.

Potential delayed effects : Not available.

Long term exposure

Potential immediate effects : Not available.

Potential delayed effects : Not available.

Potential chronic health effects

Not available.

General : No known significant effects or critical hazards.

Carcinogenicity : No known significant effects or critical hazards.

Mutagenicity : No known significant effects or critical hazards.

Teratogenicity : No known significant effects or critical hazards.

Developmental effects : No known significant effects or critical hazards.

Fertility effects : No known significant effects or critical hazards.

Numerical measures of toxicity

Acute toxicity estimates

Not available.

Section 12. Ecological information

Toxicity

Not available.

Persistence and degradability

Not available.

Bioaccumulative potential

Product/ingredient name	$LogP_{ow}$	BCF	Potential
Methane, dichlorodifluoro-	2.16	6.17	low

Mobility in soil

Soil/water partition coefficient (K_{OC}) : Not available.

Other adverse effects : No known significant effects or critical hazards.

Powered by IHS

Section 13. Disposal considerations

Disposal methods : The generation of waste should be avoided or minimized wherever possible. Disposal of this product, solutions and any by-products should at all times comply with the requirements of environmental protection and waste disposal legislation and any regional local authority requirements. Dispose of surplus and non-recyclable products via a licensed waste disposal contractor. Waste should not be disposed of untreated to the sewer unless fully compliant with the requirements of all authorities with jurisdiction. Empty Airgas-owned pressure vessels should be returned to Airgas. Waste packaging should be recycled. Incineration or landfill should only be considered when recycling is not feasible. This material and its container must be disposed of in a safe way. Empty containers or liners may retain some product residues. Do not puncture or incinerate container.

United States - RCRA Toxic hazardous waste "U" List

Ingredient	CAS #	Status	Reference number
Dichlorodifluoromethane; Methane, dichlorodifluoro-	75-71-8	Listed	U075

Section 14. Transport information

	DOT	TDG	Mexico	IMDG	IATA
UN number	UN1028	UN1028	UN1028	UN1028	UN1028
UN proper shipping name	DICHLORODIFLUOROMETHANE OR REFRIGERANT GAS R 12	DICHLORODIFLUOROMETHANE; OR REFRIGERANT GAS R 12	DICHLORODIFLUOROMETHANE OR REFRIGERANT GAS R 12	DICHLORODIFLUOROMETHANE (REFRIGERANT GAS R 12)	DICHLORODIFLUOROMETHANE
Transport hazard class(es)	2.2	2.2	2.2	2.2	2.2
Packing group	-	-	-	-	-
Environment	No.	No.	No.	No.	No.
Additional information	**Reportable quantity** 5000 lbs / 2270 kg Package sizes shipped in quantities less than the product reportable quantity are not subject to the RQ (reportable quantity) transportation requirements. **Limited quantity** Yes. **Packaging instruction** **Passenger aircraft** Quantity limitation: 75 kg **Cargo aircraft** Quantity limitation: 150 kg **Special provisions** T50	**Explosive Limit and Limited Quantity Index** 0.125 **Passenger Carrying Road or Rail Index** 75	-	-	**Passenger and Cargo Aircraft** Quantity limitation: 75 kg **Cargo Aircraft Only** Quantity limitation: 150 kg

"Refer to CFR 49 (or authority having jurisdiction) to determine the information required for shipment of the product."

Powered by IHS

Section 14. Transport information

Special precautions for user : **Transport within user's premises:** always transport in closed containers that are upright and secure. Ensure that persons transporting the product know what to do in the event of an accident or spillage.

Transport in bulk according to Annex II of MARPOL 73/78 and the IBC Code : Not available.

Section 15. Regulatory information

U.S. Federal regulations : **TSCA 8(a) CDR Exempt/Partial exemption**: Not determined

TSCA 12(b) annual export notification: dichlorodifluoromethane

United States inventory (TSCA 8b): This material is listed or exempted.

Clean Air Act Section 112 (b) Hazardous Air Pollutants (HAPs) : Not listed

Clean Air Act Section 602 Class I Substances : Listed

Clean Air Act Section 602 Class II Substances : Not listed

DEA List I Chemicals (Precursor Chemicals) : Not listed

DEA List II Chemicals (Essential Chemicals) : Not listed

SARA 302/304

Composition/information on ingredients

No products were found.

SARA 304 RQ : Not applicable.

SARA 311/312

Classification : Sudden release of pressure

Composition/information on ingredients

Name	%	Fire hazard	Sudden release of pressure	Reactive	Immediate (acute) health hazard	Delayed (chronic) health hazard
Methane, dichlorodifluoro-	100	No.	Yes.	No.	No.	No.

SARA 313

	Product name	CAS number	%
Form R - Reporting requirements	dichlorodifluoromethane	75-71-8	100
Supplier notification	dichlorodifluoromethane	75-71-8	100

SARA 313 notifications must not be detached from the SDS and any copying and redistribution of the SDS shall include copying and redistribution of the notice attached to copies of the SDS subsequently redistributed.

State regulations

Massachusetts : This material is listed.

New York : This material is listed.

Powered by IHS

Section 15. Regulatory information

New Jersey : This material is listed.

Pennsylvania : This material is listed.

Canada inventory : This material is listed or exempted.

International regulations

International lists : **Australia inventory (AICS)**: This material is listed or exempted.
China inventory (IECSC): This material is listed or exempted.
Japan inventory: This material is listed or exempted.
Korea inventory: This material is listed or exempted.
Malaysia Inventory (EHS Register): Not determined.
New Zealand Inventory of Chemicals (NZIoC): This material is listed or exempted.
Philippines inventory (PICCS): This material is listed or exempted.
Taiwan inventory (CSNN): Not determined.

Chemical Weapons Convention List Schedule I Chemicals : Not listed

Chemical Weapons Convention List Schedule II Chemicals : Not listed

Chemical Weapons Convention List Schedule III Chemicals : Not listed

Canada

WHMIS (Canada) : Class A: Compressed gas.
CEPA Toxic substances: This material is listed.
Canadian ARET: This material is not listed.
Canadian NPRI: This material is listed.
Alberta Designated Substances: This material is not listed.
Ontario Designated Substances: This material is not listed.
Quebec Designated Substances: This material is not listed.

Section 16. Other information

Canada Label requirements : Class A: Compressed gas.

Hazardous Material Information System (U.S.A.)



Caution: HMIS® ratings are based on a 0-4 rating scale, with 0 representing minimal hazards or risks, and 4 representing significant hazards or risks Although HMIS® ratings are not required on SDSs under 29 CFR 1910. 1200, the preparer may choose to provide them. HMIS® ratings are to be used with a fully implemented HMIS® program. HMIS® is a registered mark of the National Paint & Coatings Association (NPCA). HMIS® materials may be purchased exclusively from J. J. Keller (800) 327-6868.

The customer is responsible for determining the PPE code for this material.

National Fire Protection Association (U.S.A.)

Powered by IHS

Section 16. Other information

Reprinted with permission from NFPA 704-2001, Identification of the Hazards of Materials for Emergency Response Copyright ©1997, National Fire Protection Association, Quincy, MA 02269. This reprinted material is not the complete and official position of the National Fire Protection Association, on the referenced subject which is represented only by the standard in its entirety.

Copyright ©2001, National Fire Protection Association, Quincy, MA 02269. This warning system is intended to be interpreted and applied only by properly trained individuals to identify fire, health and reactivity hazards of chemicals. The user is referred to certain limited number of chemicals with recommended classifications in NFPA 49 and NFPA 325, which would be used as a guideline only. Whether the chemicals are classified by NFPA or not, anyone using the 704 systems to classify chemicals does so at their own risk.

History

Date of printing : 5/21/2015.

Date of issue/Date of revision : 5/21/2015.

Date of previous issue : 5/21/2015.

Version : 2

Key to abbreviations : ATE = Acute Toxicity Estimate
BCF = Bioconcentration Factor
GHS = Globally Harmonized System of Classification and Labelling of Chemicals
IATA = International Air Transport Association
IBC = Intermediate Bulk Container
IMDG = International Maritime Dangerous Goods
LogPow = logarithm of the octanol/water partition coefficient
MARPOL 73/78 = International Convention for the Prevention of Pollution From Ships, 1973 as modified by the Protocol of 1978. ("Marpol" = marine pollution)
UN = United NationsACGIH – American Conference of Governmental Industrial Hygienists
AIHA – American Industrial Hygiene Association
CAS – Chemical Abstract Services
CEPA – Canadian Environmental Protection Act
CERCLA – Comprehensive Environmental Response, Compensation, and Liability Act (EPA)
CFR – United States Code of Federal Regulations
CPR – Controlled Products Regulations
DSL – Domestic Substances List
GWP – Global Warming Potential
IARC – International Agency for Research on Cancer
ICAO – International Civil Aviation Organisation
Inh – Inhalation
LC – Lethal concentration
LD – Lethal dosage
NDSL – Non-Domestic Substances List
NIOSH – National Institute for Occupational Safety and Health
TDG – Canadian Transportation of Dangerous Goods Act and Regulations
TLV – Threshold Limit Value
TSCA – Toxic Substances Control Act
WEEL – Workplace Environmental Exposure Level
WHMIS – Canadian Workplace Hazardous Material Information System

References : Not available.

Indicates information that has changed from previously issued version.

Other special considerations : WARNING: Contains (Dichlorodifluoromethane), a substance which harms the public health and environment by destroying ozone in the upper atmosphere.

Notice to reader

Powered by IHS

Section 16. Other information

To the best of our knowledge, the information contained herein is accurate. However, neither the above-named supplier, nor any of its subsidiaries, assumes any liability whatsoever for the accuracy or completeness of the information contained herein.

Final determination of suitability of any material is the sole responsibility of the user. All materials may present unknown hazards and should be used with caution. Although certain hazards are described herein, we cannot guarantee that these are the only hazards that exist.

Powered by IHS

1. IDENTIFICATION

Product Identifier: No. 2 Fuel Oil

Synonyms: No. 2 Heating Oil, #2 Fuel Oil, Heating Oil Plus™, Low Sulfur Heating Oil (LSHO), Ultra Low Sulfur Heating Oil (ULSHO)

Intended use of the product: Fuel

Contact:
Global Companies LLC
Water Mill Center
800 South St.
Waltham, MA 02454-9161
www.globalp.com

Contact Information: EMERGENCY TELEPHONE NUMBER (24 hrs.): CHEMTREC (800) 424-9300
COMPANY CONTACT (business hours): 800-542-0778

2. HAZARD IDENTIFICATION

According to OSHA 29 CFR 1910.1200 HCS

Classification of the Substance or Mixture

Classification (GHS-US):

Flam. Liquid	Category 3	H226
Skin Corrosion/Irritation	Category 2	H315
Aspiration Hazard	Category 1	H304
Acute toxicity – Inhalation	Category 4	H332
STOT SE	Category 3	H336
Carcinogenicity	Category 2	H350
Aquatic Chronic	Category 2	H411
Eye damage/Irritation	Category 2	H319

Labeling Elements

Signal Word (GHS-US): **Danger**

Hazard Statements (GHS-US):
H226 – Flammable liquid and vapor.
H315 – Causes Skin irritation.
H304 – May be fatal if swallowed and enters airways.
H332—Harmful if inhaled.
H336 – May cause drowsiness or dizziness.
H350 – May cause cancer.
H411 – Toxic to aquatic life with long lasting effects.
H319 – May cause eye damage/irritation.

Precautionary Statements (GHS-US):
P210 - Keep away from heat/sparks/open flames/hot surfaces. - No smoking.
P233 - Keep container tightly closed.
P240 – Ground/bond container and receiving equipment.

P241 – Use explosion-proof electrical/ventilating/lighting equipment pursuant to applicable electrical code.
P242 – Use only non-sparking tools.
P243 – Take precautionary measures against static discharge.
P261 – Avoid breathing dust/fume/gas/mist/vapors/spray.
P264 – Wash skin thoroughly after handling.
P271 – Use only outdoors or in a well-ventilated area.
P273 – Avoid release to the environment.
P280 - Wear protective gloves/protective clothing/eye protection/face protection.
P303+361+353 - If on skin (or hair): Take off immediately all contaminated clothing. Rinse with water/shower.
P308+311 - If exposed or concerned: Get medical advice/attention.
P301+310 - If swallowed: Immediately call a poison center/doctor/…
P331 - Do NOT induce vomiting.
P370+P378 – In case of fire use firefighting foam or other appropriate media for Class B fires to extinguish.
P403+235 - Store in a well-ventilated place. Keep cool.
P405 - Store locked up.
P501 – Dispose of contents/container in accordance with local/regional/national/international regulation.

Other information:

NFPA 704
Health: 1
Fire: 2
Reactivity: 0

3. COMPOSITION / INFORMATION ON INGREDIENTS

Chemical Composition Information
Mixture

Name	Product Identifier (CAS#)	% (w/w)	Classification
No. 2 Fuel Oil	68476-30-2	95-100	Flam Liq. 3, H226; Skin Irrit. 2, H315; Aspiration 1, H304; STOT SE 3, H336; Carc.2. H350; Aquatic chronic 2, H411
Methyl Esters	N/A	0-5	N/A
Naphthalene	91-20-3	0.1	Carc. 2, H351; Acute Tox. 4, H302; Aquatic Acute 1, H400; Aquatic Chronic 1, H411

Additional Formulation Information:
No. 2 Fuel Oil consists of C9+ hydrocarbons resulting from distillation of crude oil.

Low Sulfur Heating Oil typically contains less than 500 ppm of sulfur

Ultra Low Sulfur Heating Oil typically contains less than 15 ppm of sulfur

4. FIRST AID MEASURES

Route	Measures
Inhalation	Remove person to fresh air. If person is not breathing, ensure an open airway and provide artificial respiration. If necessary, provide additional oxygen once breathing is restored if trained to do so. Seek medical attention immediately.
Ingestion	Aspiration Hazard: DO NOT INDUCE VOMITING. Do not give liquids. Obtain immediate medical attention. If spontaneous vomiting occurs, lean victim forward to reduce the risk of aspiration. Ingestion may cause gastrointestinal disturbances including irritation, nausea, vomiting, and diarrhea, and central nervous system (brain) effects similar to alcohol intoxication. In severe cases, tremors, convulsions, loss of consciousness, coma, respiratory failure, and death.
Eye Contact	In case of contact with eyes, immediately flush with clean, low-pressure water for at least 15 min. Hold eyelids open to ensure adequate flushing. Seek medical attention. In case of contact lenses, remove immediately.
Skin Contact	Remove contaminated clothing and shoes. Wash contaminated areas thoroughly with soap and water or waterless hand cleanser. Obtain medical attention if irritation or redness develops. Thermal burns require immediate medical attention depending on the severity and of the area of the body burned.

Most Important Symptoms
Contact with eyes and face may cause irritation. Long-term exposure may cause dermatitis (itching, irritation, pain and swelling).

Inhalation may cause irritation and significant or long term exposure could cause respiratory insufficiency and pulmonary edema.

Ingestion may cause aspiration, gastrointestinal disturbance, and CNS effects.

Immediate Medical Attention and Special Treatment
For contact with skin or eyes, immediately wash or flush contaminated eyes with gently flowing water. If possible, irrigate each eye continuously with 0.9% saline (NS). If ingested, rinse mouth. Do NOT induce vomiting, as this may cause chemical pneumonia (fluid in the lungs).

If inhaled, administer oxygen or establish a patent airway if breathing is labored. Suction if necessary. Monitor closely, anticipate seizures. Consider orotracheal or nostracheal intubation of airway control if patient is unconscious or is in severe respiratory distress.

Discard any clothing or shoes contaminated as they may be flammable.

5. FIRE-FIGHTING MEASURES

Extinguishing Media
Foam, carbon dioxide, dry chemical are most suitable

SMALL FIRES: Any extinguisher suitable for Class B fires, dry chemical, C02, water spray, firefighting foam, or Halon. Small fires in the incipient (beginning) stage may typically be extinguished using handheld portable fire extinguishers and other firefighting equipment.

LARGE FIRES: Foam, carbon dioxide, dry chemical. Water may be ineffective for fighting the fire, but may be used to cool fire-exposed containers.

Specific Hazards / Products of Combustion
Moderate fire hazard when exposed to heat or flame with a very low flash point. Product is flammable and easily ignited when exposed to heat, spark, open flame or other source of ignition. Flowing product may be ignited by self-generated static electricity. When mixed with air and exposed to an ignition source, flammable vapors can burn in the open or explode in confined spaces. Being heavier than air, vapors may travel long distances to an ignition source and flash back. Runoff to sewer may cause fire or explosion hazard.

Combustion may produce smoke, carbon monoxide and other products of incomplete combustion.

Special Precautions and Protective Equipment for Firefighters
Isolate area around container involved in fire. Cool tanks, shells, and containers exposed to fire and excessive heat with water.

For massive fires the use of unmanned hose holders or monitor nozzles may be advantageous to further minimize personnel exposure. Major fires may require withdrawal, allowing the tank to burn. Large storage tank fires typically require specially trained personnel and equipment to extinguish the fire, often including the need for properly applied firefighting foam.

Fighting Equipment/Instructions
Firefighting activities that may result in potential exposure to high heat, smoke or toxic by-products of combustion should require NIOSH- approved pressure-demand self-contained breathing apparatus with full face piece and protective clothing.

Refer to Section 9 for fire properties of this chemical including flash point, auto ignition temperature, and explosive limits.

6. ACCIDENTAL RELEASE MEASURES

ACTIVATE FACILITY SPCC, SPILL CONTINGENCY or EMERGENCY PLAN.

Personal Precautions
Due to high vapor density, flammable / toxic vapors may be present in low lying areas, dikes, pits, drains, or trenches. Vapors may accumulate in low lying areas and reach ignitable concentrations. Ventilate the area. Use of non-sparking tools and intrinsically safe equipment is recommended. Potential for flammable atmosphere should be monitored using a combustible gas indicator positioned downwind of the spill area. Refer to Sections 2 and 7 for further hazard warnings and handling instructions.

Use appropriate personal protective equipment to prevent eye/skin contact and absorption. Use NIOSH approved respiratory protection, if warranted, to prevent exposures above permissible limits. Refer to Section 8. Contaminated clothing should not be near sources of ignition.

Emergency Measures
As an immediate precautionary measure, isolate spill or leak area for at least 50 meters (150 feet) in all directions. Consider wind direction. Secure all ignition sources (flame, spark, hot work, hot metal, etc.) from area. Evaluate the direction of product travel, diking sewers, etc. to confirm spill areas. Do not touch or walk-through spilled material. For large spills, isolate initial action distance downwind 1,000 ft. (300 m).

Environmental Precautions
Stop the spill to prevent environmental release if it can be done safely. Product is toxic to aquatic life. Take action to isolate environmental receptors including drains, storm sewers and natural water bodies. Keep on impervious surface if at all possible. Use water sparingly to prevent product from spreading. Foam and absorbents may be used to reduce / prevent airborne release.

Spills may infiltrate subsurface soil and groundwater; professional assistance may be necessary to determine the extent of subsurface impact.

Follow federal, state or local requirements for reporting environmental release where necessary. Refer to Section 15 for further information.

Containment and Clean-Up Methods
Carefully contain and stop the source of the spill, if safe to do so. Protect bodies of water by diking absorbents, or absorbent boom, if possible. Do not flush down sewer or drainage systems, unless system is designed and permitted to handle such material. The use of firefighting foam may be useful in certain situations to reduce vapors. The proper use of water spray may effectively disperse product vapors or the liquid itself, preventing contact with ignition sources or areas/equipment that require protection.

Take up with dry earth, sand or other non-combustible, inert oil absorbing materials. Carefully shovel, scoop or sweep up into a waste container with clean, non-sparking tools for reclamation or disposal. Response and cleanup crews must be properly trained and must utilize proper protective equipment. Refer to Section 8 for appropriate protective equipment.

7. HANDLING AND STORAGE

USE ONLY AS A FUEL.
DO NOT SIPHON BY MOUTH.

Handling Precautions
Handle as a flammable liquid. Keep away from heat, sparks, and open flame. No smoking. Electrical equipment should be approved for classified area. Bond and ground containers during product transfer pursuant to NFPA 70 and API RP 2003 to

reduce the possibility of static-initiated fire or explosion. Follow precautions to prevent static initiated fire.

Use good personal hygiene practices. Use only with protective equipment specified in Section 8. Avoid repeated and/or prolonged skin exposure. Use only outdoors or in well ventilated areas. Wash hands before eating, drinking, smoking, or using toilet facilities. Do not use as a cleaning solvent on the skin. Do not use solvents or harsh abrasive skin cleaners for washing this product from exposed skin areas. Waterless hand cleaners are effective. Promptly remove contaminated clothing and launder before reuse. Use care when laundering to prevent the formation of flammable vapors which could ignite via washer or dryer. Consider the need to discard contaminated leather shoes and gloves. Emergency eye wash capability should be available in the near proximity to operations presenting a potential splash exposure.

Special slow load procedures for "switch loading" must be followed to avoid the static ignition hazard that can exist when higher flash point material (such as fuel oil) is loaded into tanks previously containing low flash point products (such as this product) - see API RP 2003, "Protection Against Ignitions Arising Out Of Static, Lightning and Stray Currents."

Storage
Large quantities of fuel oil are stored in tanks or portable containers at an ambient storage temperature. Separate from incompatible chemicals (Refer to Section 10) by distance or secondary containment. Keep away from flame, sparks, excessive temperatures and open flame. Use approved vented containers that are clearly labeled. Label all secondary containers that this material is transferred into with the chemical name and associated hazard(s). Empty product containers or vessels may contain flammable vapors. Do not pressurize, cut, heat, weld or expose such containers to sources of ignition.

Storage tanks should have a venting system. If stored in small containers, the area should be well ventilated, away from ignition sources and protected from potential damage or vehicular traffic. Post “No Smoking” signs in product storage areas. This storage area should comply with NFPA 30 “Flammable and Combustible Liquid Code” or applicable building code. The cleaning of tanks previously containing this product should follow API Recommended Practice (RP) 2013 “Cleaning Mobile Tanks in Flammable and Combustible Liquid Service” and API RP 2015 “Safe Entry and Cleaning of Petroleum Storage Tanks”.

Incompatibles
Keep away from strong oxidizers, ignition sources and heat.

8. EXPOSURE CONTROLS / PERSONAL PROTECTION

Occupational Exposure Limits

Component	CAS #	List	Value
No. 2 Fuel Oil	68476-30-2	ACGIH TLV-TWA	100 mg/m3*
Naphthalene	91-20-3	ACGIH TLV-TWA OSHA PEL ACGIH STEL	10 ppm 10 ppm 15 ppm

*Critical effects; Skin; A3; CNS impairment.

Engineering Controls
Use adequate ventilation to keep vapor concentrations of this product below occupational exposure and flammability limits, particularly in confined spaces. Intrinsically safe equipment and non-sparking tools shall be used in circumstances where concentrations may exceed lower flammable limits. Grounding and bonding shall be used to prevent accumulation and discharge of static electricity. Emergency shower and eyewash should be provided in proximity to handling areas in the event of exposure to decontaminate.

Personal Protective Equipment

Exposure	Equipment
Eye / Face	Wear appropriate chemical protective glasses or goggles or face shields to prevent skin and eye contact especially caused from splashing.
Skin	Wear appropriate personal protective clothing to prevent skin contact. Gloves constructed of nitrile, neoprene or PVC are recommended when handling this material. Chemical protective clothing such as of E.I. DuPont TyChem®, Saranex® or equivalent recommended based on degree of exposure. Note: The resistance of specific material may vary from product to product as well as with degree of exposure.

Exposure	Equipment
Respiratory	A NIOSH/MSHA-approved air-purifying respirator with organic vapor cartridges or canister may be permissible under certain circumstances where airborne concentrations are or may be expected to exceed exposure limits or for odor or irritation. Protection provided by air-purifying respirators is limited. Refer to OSHA 29 CFR 1910.134, ANSI Z88.2-1992, NIOSH Respirator Decision Logic, and the manufacturer for additional guidance on respiratory protection selection and limitations. Use a positive pressure, air-supplied respirator if there is a potential for uncontrolled release, exposure levels are not known, in oxygen-deficient atmospheres, or any other circumstance where an air-purifying respirator may not provide adequate protection.
Thermal	Product is stored at ambient temperature. No thermal protection is required except for emergency operations involving actual or potential for fire. Use adequate ventilation to keep vapor concentrations of this product below occupational exposure and flammability limits, particularly in confined spaces.

9. PHYSICAL AND CHEMICAL PROPERTIES

Property	Value	
Appearance	Clear or straw-colored liquid dyed red for distribution	
Odor	Mild petroleum distillate odor.	
Odor Threshold	<1 ppm	
pH	Not available	
Melting Point	-15 ˚F (-26 ˚C)	
Boiling Point Range	320 to 690 ˚F (160 to 366 ˚C)	
Flash Point	>125.6 ˚F (52 ˚C) PMCC	
Evaporation Rate	Slow, varies with conditions	
Flammability	Flammable liquid	
Flammable Limits	0.6 % - 7.5%	
Vapor Pressure	0.009 psia @ 70 ˚F	
Vapor Density	>1	(air=1)
Specific Gravity	0.81-0.88 @ 60 ˚F (16 ˚C)	(water=1)
Solubility	Insoluble in water; miscible with other petroleum solvents.	
Partition Coefficient (N-octanol/water)	Log Kow range of 3.3 to >.6.0	
Autoignition Temperature	494 ˚F (257 ˚C)	
Decomposition Temperature	When heated it emits acrid smoke and irritating vapors.	
Viscosity	>3 cSt	
Percent Volatiles	95-100	

10. STABILITY AND REACTIVITY

Stability
This is a stable material that is flammable liquid (OSHA/GHS hazard category 3). Stable during transport.

Reactivity
Material is not self-reacting. Flammable concentrations may be present in air. Compound can react with oxidizing materials.

Possibility of Hazardous Reactions
Hazardous polymerization will not occur.

Incompatibility
Keep away from strong oxidizers such as nitric and sulfuric acids.

Conditions to Avoid
Avoid high temperatures, open flames, sparks, static electricity, welding, smoking and other ignition sources.

Hazardous Decomposition Products
Carbon monoxide, carbon dioxide and non-combusted hydrocarbons (smoke).

11. TOXICOLOGICAL INFORMATION

Acute Toxicity:
Acute Toxicity (Inhalation LC50)

No. 2 Fuel Oil (68476-30-2)
LC50 Inhalation Rat >4.6 mg/l/4h

Acute Toxicity (Dermal LD50)

No. 2 Fuel Oil (68476-30-2)
LD50 Dermal Rabbit >2000 mg/kg

Acute Toxicity (Oral LD50)

No. 2 Fuel Oil (68476-30-2)
LD50 Oral Rat >12000 mg/kg

Acute Toxicity (Oral LD50)

Methyl Esters
LD50 Oral Rat >14400 mg/kg

Skin Corrosion/Irritation: Prolonged and repeated contact may cause skin irritation leading to dermatitis. Liquid may be absorbed through the skin in toxic amounts if large areas of skin are exposed repeatedly.

Serious Eye Damage/Irritation: Causes serious eye irritation.

Respiratory or Skin Sensitization: Not classified

Germ Cell Mutagenicity: Not classified

Teratogenicity: Not available

Carcinogenicity: OSHA: NO, IARC: Group 3, NTP: NO, ACGIH: NOIC:A3, NIOSH: NO

IARC: Group 3 – Not classifiable as to their carcinogenicity to humans ACGIH: A3 – Confirmed animal carcinogen with unknown relevance to humans

Petroleum middle distillates have been shown to produce skin tumors in laboratory animals following repeated and prolonged exposures. The significance of this finding to human exposure has not been determined. Other studies with active skin carcinogens have shown that washing the animal's skin with soap and water between applications reduced tumor formation.

This product is similar to Diesel Fuel. IARC classifies whole diesel fuel exhaust particulates (byproduct of combustion of this material) carcinogenic to humans (Group 1) and NIOSH regards diesel fuel exhaust particulate as a potential occupational carcinogen.

Reproductive Toxicity: Not classified

Specific Target Organ Toxicity (Repeated Exposure): Not classified

Specific Target Organ Toxicity (Single Exposure): Inhalation exposure may cause drowsiness or dizziness by inhalation exposure.

Aspiration Hazard: The major health threat of ingestion occurs from the danger of aspiration (breathing) of liquid drops into the lungs, particularly from vomiting. Aspiration may result in chemical pneumonia (fluid in the lungs), severe lung damage, respiratory failure and even death.

Potential Health Effects: Vapor irritating to skin, eyes, nose, and throat. Ingestion may cause gastrointestinal disturbances, including irritation, nausea, vomiting and diarrhea, and central nervous system (brain) effects similar to alcohol intoxication. In severe cases, tremors, convulsions, loss of consciousness, coma, respiratory arrest, and death may occur.

WARNING: The burning of any hydrocarbon as a fuel in an area without adequate ventilation may result in hazardous levels of combustion products, including carbon monoxide, and inadequate oxygen levels, which may cause unconsciousness, suffocation, and death.

12. ECOLOGICAL INFORMATION

Toxicity
This material is expected to be toxic to aquatic organisms and may cause long-term adverse effects in the aquatic environment.

Data for Component: No. 2 Fuel Oil (68476-30-2)

Material is toxic to aquatic organisms based on an acute basis (LC50/EC50 >1 but $\leq$ 10 mg/L in the most sensitive species tested).

Material is a long-term aquatic hazard based on a chronic basis (LC50/EC50 >1 but $\leq$ 10 mg/L in the most sensitive species tested).

Persistence and Degradation: This material is not expected to be readily biodegradable.

Bioaccumulative Potential: Not available

Mobility in Soil: Not available

Other Adverse Effects: None known

Other Information: Avoid release to the environment.

13. DISPOSAL CONSIDERATIONS

Consult federal, state and local waste regulations to determine appropriate disposal options. May be considered a hazardous waste if disposed. Direct solid waste (landfill) or incineration at a solid waste facility is not permissible. Do not discharge to sanitary or storm sewer. Personnel handling waste containers should follow precautions provided in this document.

Shipping containers must be DOT authorized packages. Follow licensure and regulations for transport of hazardous material and hazardous waste as applicable.

14. TRANSPORT INFORMATION

US DOT

UN Identification Number	NA 1993
Proper Shipping Name	Fuel oil (No. 2)
Hazard Class and Packing Group	3, PGIII
Shipping Label	Combustible liquid
Placard / Bulk Package	Combustible liquid, 1993
Emergency Response Guidebook Guide Number	128

IATA Information

UN Identification Number	UN 1993
Proper Shipping Name	Fuel oil (No. 2)
Hazard Class and Packing Group	3, PGIII
ICAO Label	3
Packing Instructions Cargo	355
Max Quantity Per Package Cargo	220L
Packing Instructions Passenger	344Y
Max Quantity per Package	60L

ICAO

UN Identification Number	UN 1993
Shipping Name / Description	Fuel oil (No. 2)
Hazard Class and Packing Group	3, PG III
IMDG Label	3

IMDG

UN Identification Number	UN 1993
Shipping Name / Description	Heating Oil, Light
Hazard Class and Packing Group	3, PGIII
IMDG Label	3
EmS Number	N/A
Marine Pollutant	Yes

15. REGULATORY INFORMATION

U.S. Federal, State, and Local Regulatory Information
Any spill or uncontrolled release of this product, including any substantial threat of release, may be subject to federal, state and/or local reporting requirements. This product and/or its constituents may also be subject to other federal, state, or local regulations; consult those regulations applicable to your facility/operation.

OSHA Hazard Communication Standard
This product is a "Hazardous Chemical" as defined by the OSHA Hazard Communication Standard, 29 CFR 1910.1200.

Superfund Amendments and Reauthorization Act of 1986 Title III (Emergency Planning And Community Right-to-Know Act of 1986) Sections 311 and 312

Immediate (Acute) Health Hazard	Yes
Delayed (Chronic) Health Hazard	Yes
Fire Hazard	Yes
Reactive Hazard	No
Sudden Release of Pressure Hazard	No

Clean Water Act (Oil Spills)
Any spill or release of this product to “navigable waters” (Essentially any surface water, including certain wetlands) or adjoining shorelines sufficient to cause a visible sheen or deposit of a sludge or emulsion must be reported immediately to the National Response Center (1-800-424-8802) or, if not practical, the U.S. Coast Guard with follow up to the National Response Center, as required by U.S. Federal Law. Also contact appropriate state and local regulatory agencies as required.

CERCLA Section 103 and SARA Section 304 (Release to the Environment)
The CERCLA definition of hazardous substances contains a “petroleum exclusion” clause which exempts this material. This product does not contain any chemicals subject to the reporting requirements of CERCLA Section 103 or SARA 304.

SARA Section 313- Supplier Notification
This product does not contain any chemicals subject to the reporting requirements of Section 313 of the Emergency Planning and Community Right-To-Know Act (EPCRA) of 1986 and of 40 CFR 372.

EPA Notification (Oil Spills)
If the there is a discharge of more than 1,000-gallons of oil into or upon navigable waters of the United States, or if it is the second spill event of 42 gallons or more of oil into water within a twelve (12) month period, a written report must be submitted to the Regional Administrator of the EPA within sixty days of the event.

Pennsylvania Right to Know Hazardous Substance list:
The following product components are cited in the Pennsylvania Special Hazardous Substance List, and are present at levels which require reporting.

Component	CAS	Amount
No. 2 Fuel Oil	68476-30-2	100%

New Jersey Right to Know Hazardous Substance list:
The following product components are cited in the New Jersey Right to Know Hazardous Substance List, and are present at levels which require reporting.

Component	CAS	Amount
No. 2Fuel Oil	68476-30-2	100%

California Proposition 65 WARNING: This product contains chemicals known to the State of California to cause Cancer or Reproductive Toxicity.

Component	CAS	Amount
Naphthalene	91-20-3	<0.1%

U.S. Toxic Substances Control Act
All components of this product are on the TSCA Inventory or are exempt from TSCA Inventory requirements under 40 CFR 720.30.

CEPA - Domestic Substances List (DSL)
All substances contained in this product are listed on the Canadian Domestic Substances List (DSL) or are not required to be listed.

Canadian Regulatory Information (WHMIS)
Class B3 – Combustible Liquid
Class D2A – Materials causing other toxic effects. (Very Toxic)

16. OTHER INFORMATION

Version	4
Issue Date	May 20, 2016
Prior Issue Date	May 3, 2015

Description of Revisions
Revised to meet Globally Harmonized System for chemical hazard communication requirements pursuant to OSHA regulatory revisions 77 FR 17884, March 26, 2012.

Abbreviations

˚F	Degrees Fahrenheit (temperature)
<	Less than
=	Equal to
>	Greater than
AP	Approximately
C	Centigrade (temperature)
kg	Kilogram
L	Liter
mg	Milligrams
mL	Milliliter
mm^2	Square millimeters
mmHg	Millimeters of mercury (pressure)
N/A	Not applicable
N/D	Not determined
ppm	Parts per million
sec	Second
ug	Micrograms

Acronyms

ACGIH	American Conference of Governmental Industrial Hygienists
AIHA	American Industrial Hygiene Association
AL	Action Level
ANSI	American National Standards Institute
API	American Petroleum Institute
CAS	Chemical Abstract Service
CERCLA	Comprehensive Emergency Response, Compensation, and Liability Act
DOT	U.S. Department of Transportation
EC50	Ecological concentration 50%
EPA	U.S. Environmental Protection Agency
ERPG	Emergency Response Planning Guideline
GHS	Global Harmonized System

HMIS	Hazardous Materials Information System
IARC	International Agency for Research On Cancer
IATA	International Air Transport Association
IMDG	International Maritime Dangerous Goods
Koc	Soil Organic Carbon
LC50	Lethal concentration 50%
LD50	Lethal dose 50%
MSHA	Mine Safety and Health Administration
NFPA	National Fire Protection Association
NIOSH	National Institute of Occupational Safety and Health
NOIC	Notice of Intended Change
NTP	National Toxicology Program
OPA	Oil Pollution Act of 1990
OSHA	U.S. Occupational Safety & Health Administration
PEL	Permissible Exposure Limit (OSHA)
RCRA	Resource Conservation and Recovery Act Reauthorization Act of 1986 Title III
REL	Recommended Exposure Limit (NIOSH)
RVP	Reid Vapor Pressure
SARA	Superfund Amendments and
SCBA	Self Contained Breathing Apparatus
SPCC	Spill Prevention, Control, and Countermeasures
STEL	Short Term Exposure Limit (generally 15 minutes)
TLV	Threshold Limit Value (ACGIH)
TSCA	Toxic Substances Control Act
TWA	Time Weighted Average (8 hr.)
UN	United Nations
UNECE	United Nations Economic Commission for Europe
WEEL	Workplace Environmental Exposure Level (AIHA)
WHMIS	Canadian Workplace Hazardous Materials Information System

Disclaimer of Expressed and Implied Warranties

Information presented herein has been compiled from sources considered to be dependable, and is accurate and reliable to the best of our knowledge and belief, but is not guaranteed to be so. Since conditions of use are beyond our control, we make no warranties, expressed or implied, except those that may be contained in our written contract of sale or acknowledgment.

Vendor assumes no responsibility for injury to vendee or third persons proximately caused by the material if reasonable safety procedures are not adhered to as stipulated in the data sheet. Additionally, vendor assumes no responsibility for injury to vendee or third persons proximately caused by abnormal use of the material, even if reasonable safety procedures are followed. Furthermore, vendee assumes the risk in their use of the material.

** End of Safety Data Sheet **

SAFETY DATA SHEET

Version 5.5
Revision Date 05/27/2016
Print Date 07/13/2017

1. PRODUCT AND COMPANY IDENTIFICATION

1.1 Product identifiers

Product name : Indeno[1,2,3-*cd*]pyrene

Product Number : 48499
Brand : Supelco

CAS-No. : 193-39-5

1.2 Relevant identified uses of the substance or mixture and uses advised against

Identified uses : Laboratory chemicals, Synthesis of substances

1.3 Details of the supplier of the safety data sheet

Company : Sigma-Aldrich
3050 Spruce Street
SAINT LOUIS MO 63103
USA

Telephone : +1 800-325-5832
Fax : +1 800-325-5052

1.4 Emergency telephone number

Emergency Phone # : +1-703-527-3887 (CHEMTREC)

2. HAZARDS IDENTIFICATION

2.1 Classification of the substance or mixture

GHS Classification in accordance with 29 CFR 1910 (OSHA HCS)
Carcinogenicity (Category 2), H351

For the full text of the H-Statements mentioned in this Section, see Section 16.

2.2 GHS Label elements, including precautionary statements

Pictogram

Signal word Warning

Hazard statement(s)
H351 Suspected of causing cancer.

Precautionary statement(s)
P201 Obtain special instructions before use.
P202 Do not handle until all safety precautions have been read and understood.
P281 Use personal protective equipment as required.
P308 + P313 IF exposed or concerned: Get medical advice/ attention.
P405 Store locked up.
P501 Dispose of contents/ container to an approved waste disposal plant.

2.3 Hazards not otherwise classified (HNOC) or not covered by GHS - none

3. COMPOSITION/INFORMATION ON INGREDIENTS

3.1 Substances

Formula	:	$C_{22}H_{12}$
Molecular weight	:	276.33 g/mol
CAS-No.	:	193-39-5
EC-No.	:	205-893-2

Hazardous components

Component	Classification	Concentration
Indeno[1,2,3-cd]pyrene		
	Carc. 2; H351	<= 100 %

For the full text of the H-Statements mentioned in this Section, see Section 16.

4. FIRST AID MEASURES

4.1 Description of first aid measures

General advice
Consult a physician. Show this safety data sheet to the doctor in attendance.Move out of dangerous area.

If inhaled
If breathed in, move person into fresh air. If not breathing, give artificial respiration. Consult a physician.

In case of skin contact
Wash off with soap and plenty of water. Consult a physician.

In case of eye contact
Flush eyes with water as a precaution.

If swallowed
Never give anything by mouth to an unconscious person. Rinse mouth with water. Consult a physician.

4.2 Most important symptoms and effects, both acute and delayed

The most important known symptoms and effects are described in the labelling (see section 2.2) and/or in section 11

4.3 Indication of any immediate medical attention and special treatment needed

No data available

5. FIREFIGHTING MEASURES

5.1 Extinguishing media

Suitable extinguishing media
Use water spray, alcohol-resistant foam, dry chemical or carbon dioxide.

5.2 Special hazards arising from the substance or mixture

No data available

5.3 Advice for firefighters

Wear self-contained breathing apparatus for firefighting if necessary.

5.4 Further information

No data available

6. ACCIDENTAL RELEASE MEASURES

6.1 Personal precautions, protective equipment and emergency procedures

Use personal protective equipment. Avoid dust formation. Avoid breathing vapours, mist or gas. Ensure adequate ventilation. Evacuate personnel to safe areas. Avoid breathing dust.
For personal protection see section 8.

6.2 Environmental precautions

Prevent further leakage or spillage if safe to do so. Do not let product enter drains.

6.3 Methods and materials for containment and cleaning up

Pick up and arrange disposal without creating dust. Sweep up and shovel. Keep in suitable, closed containers for disposal.

6.4 Reference to other sections

For disposal see section 13.

7. HANDLING AND STORAGE

7.1 Precautions for safe handling

Avoid contact with skin and eyes. Avoid formation of dust and aerosols.Further processing of solid materials may result in the formation of combustible dusts. The potential for combustible dust formation should be taken into consideration before additional processing occurs.
Provide appropriate exhaust ventilation at places where dust is formed.
For precautions see section 2.2.

7.2 Conditions for safe storage, including any incompatibilities

Keep container tightly closed in a dry and well-ventilated place.
Storage class (TRGS 510): Non Combustible Solids

7.3 Specific end use(s)

Apart from the uses mentioned in section 1.2 no other specific uses are stipulated

8. EXPOSURE CONTROLS/PERSONAL PROTECTION

8.1 Control parameters

Components with workplace control parameters
Contains no substances with occupational exposure limit values.

8.2 Exposure controls

Appropriate engineering controls
Handle in accordance with good industrial hygiene and safety practice. Wash hands before breaks and at the end of workday.

Personal protective equipment

Eye/face protection
Safety glasses with side-shields conforming to EN166 Use equipment for eye protection tested and approved under appropriate government standards such as NIOSH (US) or EN 166(EU).

Skin protection
Handle with gloves. Gloves must be inspected prior to use. Use proper glove removal technique (without touching glove's outer surface) to avoid skin contact with this product. Dispose of contaminated gloves after use in accordance with applicable laws and good laboratory practices. Wash and dry hands.

Body Protection
Impervious clothing, The type of protective equipment must be selected according to the concentration and amount of the dangerous substance at the specific workplace.

Respiratory protection
Where risk assessment shows air-purifying respirators are appropriate use a full-face particle respirator type N100 (US) or type P3 (EN 143) respirator cartridges as a backup to engineering controls. If the respirator is the sole means of protection, use a full-face supplied air respirator. Use respirators and components tested and approved under appropriate government standards such as NIOSH (US) or CEN (EU).

Control of environmental exposure
Prevent further leakage or spillage if safe to do so. Do not let product enter drains.

9. PHYSICAL AND CHEMICAL PROPERTIES

9.1 Information on basic physical and chemical properties

a)	Appearance	Form: solid
b)	Odour	No data available
c)	Odour Threshold	No data available

d)	pH	No data available
e)	Melting point/freezing point	163.6 °C (326.5 °F)
f)	Initial boiling point and boiling range	536.0 °C (996.8 °F)
g)	Flash point	No data available
h)	Evaporation rate	No data available
i)	Flammability (solid, gas)	No data available
j)	Upper/lower flammability or explosive limits	No data available
k)	Vapour pressure	No data available
l)	Vapour density	No data available
m)	Relative density	No data available
n)	Water solubility	No data available
o)	Partition coefficient: n-octanol/water	No data available
p)	Auto-ignition temperature	No data available
q)	Decomposition temperature	No data available
r)	Viscosity	No data available
s)	Explosive properties	No data available
t)	Oxidizing properties	No data available

9.2 Other safety information
No data available

10. STABILITY AND REACTIVITY

10.1 Reactivity
No data available

10.2 Chemical stability
Stable under recommended storage conditions.

10.3 Possibility of hazardous reactions
No data available

10.4 Conditions to avoid
No data available

10.5 Incompatible materials
Strong oxidizing agents

10.6 Hazardous decomposition products
Hazardous decomposition products formed under fire conditions. - Carbon oxides
Other decomposition products - No data available
In the event of fire: see section 5

11. TOXICOLOGICAL INFORMATION

11.1 Information on toxicological effects

Acute toxicity
No data available

Inhalation: No data available

Dermal: No data available

No data available

Skin corrosion/irritation
No data available

Serious eye damage/eye irritation
No data available

Respiratory or skin sensitisation
No data available

Germ cell mutagenicity
No data available

Carcinogenicity

This product is or contains a component that has been reported to be possibly carcinogenic based on its IARC, ACGIH, NTP, or EPA classification.

Limited evidence of carcinogenicity in animal studies

IARC:	2B - Group 2B: Possibly carcinogenic to humans (Indeno[1,2,3-cd]pyrene)
IARC:	2B - Group 2B: Possibly carcinogenic to humans (Indeno[1,2,3-cd]pyrene)
ACGIH:	No component of this product present at levels greater than or equal to 0.1% is identified as a carcinogen or potential carcinogen by ACGIH.
NTP:	Reasonably anticipated to be a human carcinogen (Indeno[1,2,3-cd]pyrene)
NTP:	Reasonably anticipated to be a human carcinogen (Indeno[1,2,3-cd]pyrene)
OSHA:	No component of this product present at levels greater than or equal to 0.1% is identified as a carcinogen or potential carcinogen by OSHA.
	No component of this product present at levels greater than or equal to 0.1% is identified as a carcinogen or potential carcinogen by OSHA.

Reproductive toxicity
No data available

No data available

Specific target organ toxicity - single exposure
No data available

Specific target organ toxicity - repeated exposure
No data available

Aspiration hazard
No data available

Additional Information
RTECS: Not available

To the best of our knowledge, the chemical, physical, and toxicological properties have not been thoroughly investigated.

12. ECOLOGICAL INFORMATION

12.1 Toxicity
No data available

12.2 Persistence and degradability
No data available

12.3 Bioaccumulative potential
No data available

12.4 Mobility in soil
No data available

12.5 Results of PBT and vPvB assessment
PBT/vPvB assessment not available as chemical safety assessment not required/not conducted

12.6 Other adverse effects

No data available

13. DISPOSAL CONSIDERATIONS

13.1 Waste treatment methods

Product
Offer surplus and non-recyclable solutions to a licensed disposal company. Contact a licensed professional waste disposal service to dispose of this material. Dissolve or mix the material with a combustible solvent and burn in a chemical incinerator equipped with an afterburner and scrubber.

Contaminated packaging
Dispose of as unused product.

14. TRANSPORT INFORMATION

DOT (US)
Not dangerous goods

IMDG
Not dangerous goods

IATA
Not dangerous goods

15. REGULATORY INFORMATION

SARA 302 Components
No chemicals in this material are subject to the reporting requirements of SARA Title III, Section 302.

SARA 313 Components
This material does not contain any chemical components with known CAS numbers that exceed the threshold (De Minimis) reporting levels established by SARA Title III, Section 313.

SARA 311/312 Hazards
Chronic Health Hazard

Massachusetts Right To Know Components

	CAS-No.	Revision Date
Indeno[1,2,3-cd]pyrene	193-39-5	1993-04-24

Pennsylvania Right To Know Components

	CAS-No.	Revision Date
Indeno[1,2,3-cd]pyrene	193-39-5	1993-04-24

New Jersey Right To Know Components

	CAS-No.	Revision Date
Indeno[1,2,3-cd]pyrene	193-39-5	1993-04-24

California Prop. 65 Components

WARNING! This product contains a chemical known to the State of California to cause cancer. Indeno[1,2,3-cd]pyrene	CAS-No. 193-39-5	Revision Date 2007-09-28
WARNING! This product contains a chemical known to the State of California to cause cancer.	CAS-No. 193-39-5	Revision Date 2007-09-28

Indeno[1,2,3-cd]pyrene

16. OTHER INFORMATION

Full text of H-Statements referred to under sections 2 and 3.

Carc.	Carcinogenicity
H351	Suspected of causing cancer.

HMIS Rating

Health hazard:	0
Chronic Health Hazard:	*
Flammability:	0
Physical Hazard	0

NFPA Rating

Health hazard:	1
Fire Hazard:	0
Reactivity Hazard:	0

Further information

Copyright 2016 Sigma-Aldrich Co. LLC. License granted to make unlimited paper copies for internal use only.
The above information is believed to be correct but does not purport to be all inclusive and shall be used only as a guide. The information in this document is based on the present state of our knowledge and is applicable to the product with regard to appropriate safety precautions. It does not represent any guarantee of the properties of the product. Sigma-Aldrich Corporation and its Affiliates shall not be held liable for any damage resulting from handling or from contact with the above product. See www.sigma-aldrich.com and/or the reverse side of invoice or packing slip for additional terms and conditions of sale.

Preparation Information

Sigma-Aldrich Corporation
Product Safety – Americas Region
1-800-521-8956

Version: 5.5 Revision Date: 05/27/2016 Print Date: 07/13/2017

Iron Filings, 40 mesh

SECTION 1 : Identification of the substance/mixture and of the supplier

Product name : **Iron Filings, 40 mesh**

Manufacturer/Supplier Trade name:

Manufacturer/Supplier Article number: **S25369**

Recommended uses of the product and uses restrictions on use:

Manufacturer Details:

AquaPhoenix Scientific
9 Barnhart Drive, Hanover, PA 17331

Supplier Details:

Fisher Science Education
15 Jet View Drive, Rochester, NY 14624

Emergency telephone number:

Fisher Science Education Emergency Telephone No.: 800-535-5053

SECTION 2 : Hazards identification

Classification of the substance or mixture:

Not classified for physical or health hazards under GHS.

Signal word :Warning

Hazard statements:
Precautionary statements:
If medical advice is needed, have product container or label at hand
Keep out of reach of children
Read label before use
Do not eat, drink or smoke when using this product

Combustible Dust Hazard: :
May form combustible dust concentrations in air (during processing).

Other Non-GHS Classification:

WHMIS
NFPA/HMIS

NFPA SCALE (0-4)

HMIS RATINGS (0-4)

SECTION 3 : Composition/information on ingredients

Ingredients:		
CAS 7439-89-6	Iron	100 %
		Percentages are by weight

SECTION 4 : First aid measures

Description of first aid measures

After inhalation: Loosen clothing as necessary and position individual in a comfortable position.Move exposed to fresh air. Give artificial respiration if necessary. If breathing is difficult give oxygen.Get medical assistance if cough or other symptoms appear.

After skin contact: Rinse/flush exposed skin gently using soap and water for 15-20 minutes.Seek medical advice if discomfort or irritation persists.

After eye contact: Protect unexposed eye. Rinse/flush exposed eye(s) gently using water for 15-20 minutes. Remove contact lens(es) if able to do so during rinsing. Seek medical attention if irritation persists or if concerned.

After swallowing: Rinse mouth thoroughly. Do not induce vomiting. Have exposed individual drink sips of water. Seek medical attention if irritation, discomfort or vomiting persists.Never give anything by mouth to an unconscious person.

Most important symptoms and effects, both acute and delayed:

Irritation, Nausea,Headache, Shortness of breath.;

Indication of any immediate medical attention and special treatment needed:

If seeking medical attention, provide SDS document to physician.Physician should treat symptomatically.

SECTION 5 : Firefighting measures

Extinguishing media

Suitable extinguishing agents: Use appropriate fire suppression agents for adjacent combustible materials or sources of ignition. Use water, dry chemical, chemical foam, carbon dioxide, or alcohol-resistant foam.

For safety reasons unsuitable extinguishing agents:

Special hazards arising from the substance or mixture:

Combustion products may include carbon oxides or other toxic vapors.Thermal decomposition can lead to release of irritating gases and vapors.

Advice for firefighters:

Protective equipment: Use NIOSH-approved respiratory protection/breathing apparatus.

Additional information (precautions): Move product containers away from fire or keep cool with water spray as a protective measure, where feasible.Use spark-proof tools and explosion-proof equipment.Avoid generating dust; fine dust dispersed in air in sufficient concentrations, and in the presence of an ignition source is a potential dust explosion hazard.Avoid inhaling gases, fumes, dust, mist, vapor, and aerosols.Avoid contact with skin, eyes, and clothing.

SECTION 6 : Accidental release measures

Personal precautions, protective equipment and emergency procedures:

Wear protective equipment. Use spark-proof tools and explosion-proof equipment.Ensure that air-handling systems are operational.Ensure adequate ventilation.

Environmental precautions:

Prevent from reaching drains, sewer or waterway. Collect contaminated soil for characterization per Section 13. Should not be released into environment.

Methods and material for containment and cleaning up:

Keep in suitable closed containers for disposal.Wear protective eyeware, gloves, and clothing. Refer to Section 8.Always obey local regulations.Dust deposits should not be allowed to accumulate on surfaces, as these may form an explosive mixture if they are released into the atmosphere in sufficient concentration. Avoid dispersal of dust in the air (i.e., clearing dust surfaces with compressed air). Collect solids in powder form using vacuum with (HEPA filter). Evacuate personnel to safe areas.

Reference to other sections:

SECTION 7 : Handling and storage

Precautions for safe handling:

Minimize dust generation and accumulation. Follow good hygiene procedures when handling chemical materials. Refer to Section 8.Do not eat, drink, smoke, or use personal products when handling chemical substances. Avoid contact with eyes, skin, and clothing.

Conditions for safe storage, including any incompatibilities:

Store away from incompatible materials.Protect from freezing and physical damage.Keep away from food and beverages.Provide ventilation for containers. Avoid storage near extreme heat, ignition sources or open flame. Store in cool, dry conditions in well sealed containers. Store with like hazards

SECTION 8 : Exposure controls/personal protection

Control Parameters:	, , OSHA PEL TWA (Total Dust) 15 mg/m3 (50 mppcf*) , , ACGIH TLV TWA (inhalable particles) 10 mg/m3
Appropriate Engineering controls:	Emergency eye wash fountains and safety showers should be available in the immediate vicinity of use/handling.Provide exhaust ventilation or other engineering controls to keep the airborne concentrations of vapor or dusts (total/respirable) below the applicable workplace exposure limits (Occupational Exposure Limits-OELs) indicated above.It is recommended that all dust control equipment such as local exhaust ventilation and material transport systems involved in handling of this product contain explosion relief vents or an explosion suppression system or an oxygen deficient environment.Ensure that dust-handling systems (such as exhaust ducts, dust collectors, vessels, and processing equipment) are designed in a manner to prevent the escape of dust into the work area (i.e., there is no leakage from the equipment).Use under a fume hood
Respiratory protection:	Not required under normal conditions of use. Where risk assessment shows air-purifying respirators are appropriate use a full-face particle respirator type N100 (US) or type P3 (EN 143) respirator cartridges as a backup to engineering controls.When necessary use NIOSH approved breathing equipment.
Protection of skin:	Select glove material impermeable and resistant to the substance.Select glove material based on rates of diffusion and degradation.Dispose of contaminated gloves after use in accordance with applicable laws and good laboratory practices.Use proper glove removal technique without touching outer surface. Avoid skin contact with used gloves.Wear protective clothing.

Eye protection: Wear equipment for eye protection tested and approved under appropriate government standards such as NIOSH (US) or EN 166(EU).Safety glasses or goggles are appropriate eye protection.

General hygienic measures: Perform routine housekeeping.Wash hands before breaks and at the end of work.Avoid contact with skin, eyes, and clothing.Before wearing wash contaminated clothing.

SECTION 9 : Physical and chemical properties

Appearance (physical state,color):	Solid	**Explosion limit lower**: **Explosion limit upper**:	Not determined Not determined
Odor:	Not Determined	**Vapor pressure**:	Not determined
Odor threshold:	Not determined	**Vapor density**:	Not determined
pH-value:	Not Determined	**Relative density**:	Not determined
Melting/Freezing point:	Not determined	**Solubilities**:	
Boiling point/Boiling range:	Not determined	**Partition coefficient (n-octanol/water)**:	Not determined
Flash point (closed cup):	Not determined	**Auto/Self-ignition temperature**:	Not determined
Evaporation rate:	Not determined	**Decomposition temperature**:	Not determined
Flammability (solid,gaseous):	Not determined	**Viscosity**:	a. Kinematic:Not determined b. Dynamic: Not determined
Density: Not determined			

SECTION 10 : Stability and reactivity

Reactivity: Nonreactive under normal conditions.
Chemical stability: Stable under normal conditions.
Possible hazardous reactions: None under normal processing
Conditions to avoid: Incompatible Materials.
Incompatible materials: Strong acids.Strong bases.Oxidizing agents.
Hazardous decomposition products:

SECTION 11 : Toxicological information

Acute Toxicity: No additional information.	
Chronic Toxicity: No additional information.	
Corrosion Irritation: No additional information.	
Sensitization:	No additional information.
Single Target Organ (STOT):	No additional information.
Numerical Measures:	No additional information.

Carcinogenicity:	No additional information.
Mutagenicity:	No additional information.
Reproductive Toxicity:	No additional information.

SECTION 12 : Ecological information

Ecotoxicity Persistence and degradability:
Bioaccumulative potential:
Mobility in soil:
Other adverse effects:

SECTION 13 : Disposal considerations

Waste disposal recommendations:

Contact a licensed professional waste disposal service to dispose of this material.Dispose of empty containers as unused product.Product or containers must not be disposed with household garbage.It is the responsibility of the waste generator to properly characterize all waste materials according to applicable regulatory entities (US 40CFR262.11).Chemical waste generators must determine whether a discarded chemical is classified as a hazardous waste. Chemical waste generators must also consult local, regional, and national hazardous waste regulations. Ensure complete and accurate classification.

SECTION 14 : Transport information

UN-Number

Not Regulated.

UN proper shipping name

Not Regulated.

Transport hazard class(es)
Packing group:Not Regulated
Environmental hazard:
Transport in bulk:
Special precautions for user:

SECTION 15 : Regulatory information

United States (USA)

SARA Section 311/312 (Specific toxic chemical listings):

None of the ingredients is listed

SARA Section 313 (Specific toxic chemical listings):

None of the ingredients is listed

RCRA (hazardous waste code):

None of the ingredients is listed

TSCA (Toxic Substances Control Act):

All ingredients are listed.

CERCLA (Comprehensive Environmental Response, Compensation, and Liability Act):

None of the ingredients is listed

Proposition 65 (California):

Chemicals known to cause cancer:

None of the ingredients is listed

Chemicals known to cause reproductive toxicity for females:

None of the ingredients is listed

Chemicals known to cause reproductive toxicity for males:

None of the ingredients is listed

Chemicals known to cause developmental toxicity:

None of the ingredients is listed

Canada

Canadian Domestic Substances List (DSL):

All ingredients are listed.

Canadian NPRI Ingredient Disclosure list (limit 0.1%):

None of the ingredients is listed

Canadian NPRI Ingredient Disclosure list (limit 1%):

None of the ingredients is listed

SECTION 16 : Other information

This product has been classified in accordance with hazard criteria of the Controlled Products Regulations and the SDS contains all the information required by the Controlled Products Regulations.Note:. The responsibility to provide a safe workplace remains with the user.The user should consider the health hazards and safety information contained herein as a guide and should take those precautions required in an individual operation to instruct employees and develop work practice procedures for a safe work environment.The information contained herein is, to the best of our knowledge and belief, accurate.However, since the conditions of handling and use are beyond our control, we make no guarantee of results, and assume no liability for damages incurred by the use of this material.It is the responsibility of the user to comply with all applicable laws and regulations applicable to this material.

GHS Full Text Phrases:

Abbreviations and acronyms:
IMDG: International Maritime Code for Dangerous Goods
IATA: International Air Transport Association
GHS: Globally Harmonized System of Classification and Labelling of Chemicals
ACGIH: American Conference of Governmental Industrial Hygienists
CAS: Chemical Abstracts Service (division of the American Chemical Society)
NFPA: National Fire Protection Association (USA)
HMIS: Hazardous Materials Identification System (USA)
WHMIS: Workplace Hazardous Materials Information System (Canada)
DNEL: Derived No-Effect Level (REACH)
PNEC: Predicted No-Effect Concentration (REACH)
CFR: Code of Federal Regulations (USA)
SARA: Superfund Amendments and Reauthorization Act (USA)
RCRA: Resource Conservation and Recovery Act (USA)
TSCA: Toxic Substances Control Act (USA)
NPRI: National Pollutant Release Inventory (Canada)
DOT: US Department of Transportation

Effective date : 10.24.2014
Last updated : 03.23.2015

SAFETY DATA SHEET

Isobutylene

Section 1. Identification

GHS product identifier : Isobutylene

Chemical name : 2-methylpropene

Other means of identification : 1-Propene, 2-methyl-; Isobutene; Isobutylene; 1-Propene, 2-methyl- (isobutene)

Product use : Synthetic/Analytical chemistry.

Synonym : 1-Propene, 2-methyl-; Isobutene; Isobutylene; 1-Propene, 2-methyl- (isobutene)

SDS # : 001031

Supplier's details : Airgas USA, LLC and its affiliates
259 North Radnor-Chester Road
Suite 100
Radnor, PA 19087-5283
1-610-687-5253

24-hour telephone : 1-866-734-3438

Section 2. Hazards identification

OSHA/HCS status : This material is considered hazardous by the OSHA Hazard Communication Standard (29 CFR 1910.1200).

Classification of the substance or mixture : FLAMMABLE GASES - Category 1
GASES UNDER PRESSURE - Liquefied gas

GHS label elements

Hazard pictograms :

Signal word : Danger

Hazard statements : Extremely flammable gas.
May form explosive mixtures with air.
Contains gas under pressure; may explode if heated.
May cause frostbite.
May displace oxygen and cause rapid suffocation.

Precautionary statements

General : Read and follow all Safety Data Sheets (SDS'S) before use. Read label before use. Keep out of reach of children. If medical advice is needed, have product container or label at hand. Close valve after each use and when empty. Use equipment rated for cylinder pressure. Do not open valve until connected to equipment prepared for use. Use a back flow preventative device in the piping. Use only equipment of compatible materials of construction. Always keep container in upright position. Approach suspected leak area with caution.

Prevention : Keep away from heat, hot surfaces, sparks, open flames and other ignition sources. No smoking.

Response : Leaking gas fire: Do not extinguish, unless leak can be stopped safely. Eliminate all ignition sources if safe to do so.

Storage : Protect from sunlight when ambient temperature exceeds 52°C/125°F. Store in a well-ventilated place.

Disposal : Not applicable.

Hazards not otherwise classified : In addition to any other important health or physical hazards, this product may displace oxygen and cause rapid suffocation.

Section 3. Composition/information on ingredients

Substance/mixture : Substance

Chemical name : 2-methylpropene

Other means of identification : 1-Propene, 2-methyl-; Isobutene; Isobutylene; 1-Propene, 2-methyl- (isobutene)

CAS number/other identifiers

CAS number : 115-11-7

Product code : 001031

Ingredient name	%	CAS number
Isobutylene	100	115-11-7

Any concentration shown as a range is to protect confidentiality or is due to batch variation.

There are no additional ingredients present which, within the current knowledge of the supplier and in the concentrations applicable, are classified as hazardous to health or the environment and hence require reporting in this section.

Occupational exposure limits, if available, are listed in Section 8.

Section 4. First aid measures

Description of necessary first aid measures

Eye contact : Immediately flush eyes with plenty of water, occasionally lifting the upper and lower eyelids. Check for and remove any contact lenses. Continue to rinse for at least 10 minutes. Get medical attention if irritation occurs.

Inhalation : Remove victim to fresh air and keep at rest in a position comfortable for breathing. If not breathing, if breathing is irregular or if respiratory arrest occurs, provide artificial respiration or oxygen by trained personnel. It may be dangerous to the person providing aid to give mouth-to-mouth resuscitation. Get medical attention if adverse health effects persist or are severe. If unconscious, place in recovery position and get medical attention immediately. Maintain an open airway. Loosen tight clothing such as a collar, tie, belt or waistband.

Skin contact : Flush contaminated skin with plenty of water. Remove contaminated clothing and shoes. To avoid the risk of static discharges and gas ignition, soak contaminated clothing thoroughly with water before removing it. Get medical attention if symptoms occur. Wash clothing before reuse. Clean shoes thoroughly before reuse.

Ingestion : As this product is a gas, refer to the inhalation section.

Most important symptoms/effects, acute and delayed

Potential acute health effects

Eye contact : No known significant effects or critical hazards.

Inhalation : No known significant effects or critical hazards.

Skin contact : No known significant effects or critical hazards.

Frostbite : Try to warm up the frozen tissues and seek medical attention.

Ingestion : As this product is a gas, refer to the inhalation section.

Over-exposure signs/symptoms

Eye contact : No specific data.

Inhalation : No specific data.

Skin contact : No specific data.

Ingestion : No specific data.

Indication of immediate medical attention and special treatment needed, if necessary

Notes to physician : Treat symptomatically. Contact poison treatment specialist immediately if large quantities have been ingested or inhaled.

Specific treatments : No specific treatment.

Section 4. First aid measures

Protection of first-aiders : No action shall be taken involving any personal risk or without suitable training. It may be dangerous to the person providing aid to give mouth-to-mouth resuscitation.

See toxicological information (Section 11)

Section 5. Fire-fighting measures

Extinguishing media

Suitable extinguishing media : Use an extinguishing agent suitable for the surrounding fire.

Unsuitable extinguishing media : None known.

Specific hazards arising from the chemical : Contains gas under pressure. Extremely flammable gas. In a fire or if heated, a pressure increase will occur and the container may burst, with the risk of a subsequent explosion.

Hazardous thermal decomposition products : Decomposition products may include the following materials:
carbon dioxide
carbon monoxide

Special protective actions for fire-fighters : Promptly isolate the scene by removing all persons from the vicinity of the incident if there is a fire. No action shall be taken involving any personal risk or without suitable training. Contact supplier immediately for specialist advice. Move containers from fire area if this can be done without risk. Use water spray to keep fire-exposed containers cool. If involved in fire, shut off flow immediately if it can be done without risk. If this is impossible, withdraw from area and allow fire to burn. Fight fire from protected location or maximum possible distance. Eliminate all ignition sources if safe to do so.

Special protective equipment for fire-fighters : Fire-fighters should wear appropriate protective equipment and self-contained breathing apparatus (SCBA) with a full face-piece operated in positive pressure mode.

Section 6. Accidental release measures

Personal precautions, protective equipment and emergency procedures

For non-emergency personnel : Accidental releases pose a serious fire or explosion hazard. No action shall be taken involving any personal risk or without suitable training. Evacuate surrounding areas. Keep unnecessary and unprotected personnel from entering. Shut off all ignition sources. No flares, smoking or flames in hazard area. Avoid breathing gas. Provide adequate ventilation. Wear appropriate respirator when ventilation is inadequate. Put on appropriate personal protective equipment.

For emergency responders : If specialised clothing is required to deal with the spillage, take note of any information in Section 8 on suitable and unsuitable materials. See also the information in "For non-emergency personnel".

Environmental precautions : Ensure emergency procedures to deal with accidental gas releases are in place to avoid contamination of the environment. Inform the relevant authorities if the product has caused environmental pollution (sewers, waterways, soil or air).

Methods and materials for containment and cleaning up

Small spill : Immediately contact emergency personnel. Stop leak if without risk. Use spark-proof tools and explosion-proof equipment.

Large spill : Immediately contact emergency personnel. Stop leak if without risk. Use spark-proof tools and explosion-proof equipment. Note: see Section 1 for emergency contact information and Section 13 for waste disposal.

Section 7. Handling and storage

Precautions for safe handling

Protective measures : Put on appropriate personal protective equipment (see Section 8). Contains gas under pressure. Avoid contact with eyes, skin and clothing. Avoid breathing gas. Use only with adequate ventilation. Wear appropriate respirator when ventilation is inadequate. Do not enter storage areas and confined spaces unless adequately ventilated. Store and use away from heat, sparks, open flame or any other ignition source. Use explosion-proof electrical (ventilating, lighting and material handling) equipment. Use only non-sparking tools. Empty containers retain product residue and can be hazardous. Do not puncture or incinerate container. Use equipment rated for cylinder pressure. Close valve after each use and when empty. Protect cylinders from physical damage; do not drag, roll, slide, or drop. Use a suitable hand truck for cylinder movement.

Advice on general occupational hygiene : Eating, drinking and smoking should be prohibited in areas where this material is handled, stored and processed. Workers should wash hands and face before eating, drinking and smoking. Remove contaminated clothing and protective equipment before entering eating areas. See also Section 8 for additional information on hygiene measures.

Conditions for safe storage, including any incompatibilities : Store in accordance with local regulations. Store in a segregated and approved area. Store away from direct sunlight in a dry, cool and well-ventilated area, away from incompatible materials (see Section 10). Eliminate all ignition sources. Keep container tightly closed and sealed until ready for use. Cylinders should be stored upright, with valve protection cap in place, and firmly secured to prevent falling or being knocked over. Cylinder temperatures should not exceed 52 °C (125 °F).

Section 8. Exposure controls/personal protection

Control parameters

Occupational exposure limits

Ingredient name	Exposure limits
Isobutylene	**ACGIH TLV (United States, 3/2015).** TWA: 250 ppm 8 hours.

Appropriate engineering controls : Use only with adequate ventilation. Use process enclosures, local exhaust ventilation or other engineering controls to keep worker exposure to airborne contaminants below any recommended or statutory limits. The engineering controls also need to keep gas, vapor or dust concentrations below any lower explosive limits. Use explosion-proof ventilation equipment.

Environmental exposure controls : Emissions from ventilation or work process equipment should be checked to ensure they comply with the requirements of environmental protection legislation. In some cases, fume scrubbers, filters or engineering modifications to the process equipment will be necessary to reduce emissions to acceptable levels.

Individual protection measures

Hygiene measures : Wash hands, forearms and face thoroughly after handling chemical products, before eating, smoking and using the lavatory and at the end of the working period. Appropriate techniques should be used to remove potentially contaminated clothing. Wash contaminated clothing before reusing. Ensure that eyewash stations and safety showers are close to the workstation location.

Eye/face protection : Safety eyewear complying with an approved standard should be used when a risk assessment indicates this is necessary to avoid exposure to liquid splashes, mists, gases or dusts. If contact is possible, the following protection should be worn, unless the assessment indicates a higher degree of protection: safety glasses with side-shields.

Skin protection

Section 8. Exposure controls/personal protection

Hand protection : Chemical-resistant, impervious gloves complying with an approved standard should be worn at all times when handling chemical products if a risk assessment indicates this is necessary. Considering the parameters specified by the glove manufacturer, check during use that the gloves are still retaining their protective properties. It should be noted that the time to breakthrough for any glove material may be different for different glove manufacturers. In the case of mixtures, consisting of several substances, the protection time of the gloves cannot be accurately estimated.

Body protection : Personal protective equipment for the body should be selected based on the task being performed and the risks involved and should be approved by a specialist before handling this product. When there is a risk of ignition from static electricity, wear anti-static protective clothing. For the greatest protection from static discharges, clothing should include anti-static overalls, boots and gloves.

Other skin protection : Appropriate footwear and any additional skin protection measures should be selected based on the task being performed and the risks involved and should be approved by a specialist before handling this product.

Respiratory protection : Use a properly fitted, air-purifying or air-fed respirator complying with an approved standard if a risk assessment indicates this is necessary. Respirator selection must be based on known or anticipated exposure levels, the hazards of the product and the safe working limits of the selected respirator.

Section 9. Physical and chemical properties

Appearance

Physical state : Gas. [Liquefied compressed gas.]

Color : Colorless.

Molecular weight : 56.12 g/mole

Molecular formula : C4-H8

Boiling/condensation point : -6.9°C (19.6°F)

Melting/freezing point : -140.7°C (-221.3°F)

Critical temperature : 144.75°C (292.6°F)

Odor : Characteristic.

Odor threshold : Not available.

pH : Not available.

Flash point : Closed cup: -76.1°C (-105°F)

Burning time : Not applicable.

Burning rate : Not applicable.

Evaporation rate : Not available.

Flammability (solid, gas) : Extremely flammable in the presence of the following materials or conditions: open flames, sparks and static discharge and oxidizing materials.

Lower and upper explosive (flammable) limits : Lower: 1.8%
Upper: 9.6%

Vapor pressure : 24.3 (psig)

Vapor density : 1.94 (Air = 1)

Specific Volume (ft^3/lb) : 6.6845

Gas Density (lb/ft^3) : 0.1496 (25°C / 77 to °F)

Relative density : Not applicable.

Solubility : Not available.

Solubility in water : 0.263 g/l

Partition coefficient: n-octanol/water : 2.34

Auto-ignition temperature : 465°C (869°F)

Decomposition temperature : Not available.

SADT : Not available.

Section 9. Physical and chemical properties

Viscosity : Not applicable.

Section 10. Stability and reactivity

Reactivity : No specific test data related to reactivity available for this product or its ingredients.

Chemical stability : The product is stable.

Possibility of hazardous reactions : Under normal conditions of storage and use, hazardous reactions will not occur.

Conditions to avoid : Avoid all possible sources of ignition (spark or flame). Do not pressurize, cut, weld, braze, solder, drill, grind or expose containers to heat or sources of ignition.

Incompatible materials : Oxidizers

Hazardous decomposition products : Under normal conditions of storage and use, hazardous decomposition products should not be produced.

Hazardous polymerization : Under normal conditions of storage and use, hazardous polymerization will not occur.

Section 11. Toxicological information

Information on toxicological effects

Acute toxicity

Product/ingredient name	Result	Species	Dose	Exposure
Isobutylene	LC50 Inhalation Vapor	Rat	550000 mg/m³	4 hours

Irritation/Corrosion

Not available.

Sensitization

Not available.

Mutagenicity

Not available.

Carcinogenicity

Not available.

Reproductive toxicity

Not available.

Teratogenicity

Not available.

Specific target organ toxicity (single exposure)

Not available.

Specific target organ toxicity (repeated exposure)

Not available.

Aspiration hazard

Not available.

Section 11. Toxicological information

Information on the likely routes of exposure : Not available.

Potential acute health effects

Eye contact : No known significant effects or critical hazards.

Inhalation : No known significant effects or critical hazards.

Skin contact : No known significant effects or critical hazards.

Ingestion : As this product is a gas, refer to the inhalation section.

Symptoms related to the physical, chemical and toxicological characteristics

Eye contact : No specific data.

Inhalation : No specific data.

Skin contact : No specific data.

Ingestion : No specific data.

Delayed and immediate effects and also chronic effects from short and long term exposure

Short term exposure

Potential immediate effects : Not available.

Potential delayed effects : Not available.

Long term exposure

Potential immediate effects : Not available.

Potential delayed effects : Not available.

Potential chronic health effects

Not available.

General : No known significant effects or critical hazards.

Carcinogenicity : No known significant effects or critical hazards.

Mutagenicity : No known significant effects or critical hazards.

Teratogenicity : No known significant effects or critical hazards.

Developmental effects : No known significant effects or critical hazards.

Fertility effects : No known significant effects or critical hazards.

Numerical measures of toxicity

Acute toxicity estimates

Not available.

Section 12. Ecological information

Toxicity

Not available.

Persistence and degradability

Not available.

Bioaccumulative potential

Product/ingredient name	$LogP_{ow}$	BCF	Potential
Isobutylene	2.34	-	low

Section 12. Ecological information

Mobility in soil

Soil/water partition coefficient (K_{OC}) : Not available.

Other adverse effects : No known significant effects or critical hazards.

Section 13. Disposal considerations

Disposal methods : The generation of waste should be avoided or minimized wherever possible. Disposal of this product, solutions and any by-products should at all times comply with the requirements of environmental protection and waste disposal legislation and any regional local authority requirements. Dispose of surplus and non-recyclable products via a licensed waste disposal contractor. Waste should not be disposed of untreated to the sewer unless fully compliant with the requirements of all authorities with jurisdiction. Empty Airgas-owned pressure vessels should be returned to Airgas. Waste packaging should be recycled. Incineration or landfill should only be considered when recycling is not feasible. This material and its container must be disposed of in a safe way. Empty containers or liners may retain some product residues. Do not puncture or incinerate container.

Section 14. Transport information

	DOT	TDG	Mexico	IMDG	IATA
UN number	UN1055	UN1055	UN1055	UN1055	UN1055
UN proper shipping name	ISOBUTYLENE	ISOBUTYLENE	ISOBUTYLENE	ISOBUTYLENE	ISOBUTYLENE
Transport hazard class(es)	2.1	2.1	2.1	2.1	2.1
Packing group	-	-	-	-	-
Environment	No.	No.	No.	No.	No.
Additional information	**Limited quantity** Yes. **Packaging instruction** **Passenger aircraft** Quantity limitation: Forbidden. **Cargo aircraft** Quantity limitation: 150 kg **Special provisions** 19, T50	Product classified as per the following sections of the Transportation of Dangerous Goods Regulations: 2.13-2.17 (Class 2). **Explosive Limit and Limited Quantity Index** 0.125 **ERAP Index** 3000 **Passenger Carrying Ship Index** Forbidden **Passenger Carrying Road or Rail Index** Forbidden **Special provisions** 29	-	-	**Passenger and Cargo Aircraft**Quantity limitation: 0 Forbidden **Cargo Aircraft Only** Quantity limitation: 150 kg

"Refer to CFR 49 (or authority having jurisdiction) to determine the information required for shipment of the product."

Section 14. Transport information

Special precautions for user : **Transport within user's premises:** always transport in closed containers that are upright and secure. Ensure that persons transporting the product know what to do in the event of an accident or spillage.

Transport in bulk according to Annex II of MARPOL 73/78 and the IBC Code : Not available.

Section 15. Regulatory information

U.S. Federal regulations : **TSCA 8(a) CDR Exempt/Partial exemption**: Not determined

United States inventory (TSCA 8b): This material is listed or exempted.

Clean Air Act (CAA) 112 regulated flammable substances: isobutylene

Clean Air Act Section 112 (b) Hazardous Air Pollutants (HAPs) : Not listed

Clean Air Act Section 602 Class I Substances : Not listed

Clean Air Act Section 602 Class II Substances : Not listed

DEA List I Chemicals (Precursor Chemicals) : Not listed

DEA List II Chemicals (Essential Chemicals) : Not listed

SARA 302/304

Composition/information on ingredients

No products were found.

SARA 304 RQ : Not applicable.

SARA 311/312

Classification : Fire hazard
Sudden release of pressure

Composition/information on ingredients

Name	%	Fire hazard	Sudden release of pressure	Reactive	Immediate (acute) health hazard	Delayed (chronic) health hazard
Isobutylene	100	Yes.	Yes.	No.	No.	No.

State regulations

Massachusetts : This material is listed.

New York : This material is not listed.

New Jersey : This material is listed.

Pennsylvania : This material is listed.

International regulations

International lists

National inventory

Australia : This material is listed or exempted.

Canada : This material is listed or exempted.

China : This material is listed or exempted.

Europe : This material is listed or exempted.

Japan : This material is listed or exempted.

Malaysia : Not determined.

Section 15. Regulatory information

New Zealand : This material is listed or exempted.

Philippines : This material is listed or exempted.

Republic of Korea : This material is listed or exempted.

Taiwan : This material is listed or exempted.

Canada

WHMIS (Canada) : Class A: Compressed gas.
Class B-1: Flammable gas.

CEPA Toxic substances: This material is not listed.
Canadian ARET: This material is not listed.
Canadian NPRI: This material is listed.
Alberta Designated Substances: This material is not listed.
Ontario Designated Substances: This material is not listed.
Quebec Designated Substances: This material is not listed.

Section 16. Other information

Canada Label requirements : Class A: Compressed gas.
Class B-1: Flammable gas.

Hazardous Material Information System (U.S.A.)



Caution: HMIS® ratings are based on a 0-4 rating scale, with 0 representing minimal hazards or risks, and 4 representing significant hazards or risks Although HMIS® ratings are not required on SDSs under 29 CFR 1910. 1200, the preparer may choose to provide them. HMIS® ratings are to be used with a fully implemented HMIS® program. HMIS® is a registered mark of the National Paint & Coatings Association (NPCA). HMIS® materials may be purchased exclusively from J. J. Keller (800) 327-6868.

The customer is responsible for determining the PPE code for this material.

National Fire Protection Association (U.S.A.)

Reprinted with permission from NFPA 704-2001, Identification of the Hazards of Materials for Emergency Response Copyright ©1997, National Fire Protection Association, Quincy, MA 02269. This reprinted material is not the complete and official position of the National Fire Protection Association, on the referenced subject which is represented only by the standard in its entirety.

Copyright ©2001, National Fire Protection Association, Quincy, MA 02269. This warning system is intended to be interpreted and applied only by properly trained individuals to identify fire, health and reactivity hazards of chemicals. The user is referred to certain limited number of chemicals with recommended classifications in NFPA 49 and NFPA 325, which would be used as a guideline only. Whether the chemicals are classified by NFPA or not, anyone using the 704 systems to classify chemicals does so at their own risk.

Procedure used to derive the classification

Classification	Justification
Flam. Gas 1, H220 Press. Gas Liq. Gas, H280	Expert judgment Expert judgment

History

Date of printing : 7/11/2016

Date of issue/Date of revision : 7/11/2016

Date of previous issue : No previous validation

Section 16. Other information

Version : 0.01

Key to abbreviations : ATE = Acute Toxicity Estimate
BCF = Bioconcentration Factor
GHS = Globally Harmonized System of Classification and Labelling of Chemicals
IATA = International Air Transport Association
IBC = Intermediate Bulk Container
IMDG = International Maritime Dangerous Goods
LogPow = logarithm of the octanol/water partition coefficient
MARPOL 73/78 = International Convention for the Prevention of Pollution From Ships, 1973 as modified by the Protocol of 1978. ("Marpol" = marine pollution)
UN = United Nations

References : Not available.

Indicates information that has changed from previously issued version.

Notice to reader

To the best of our knowledge, the information contained herein is accurate. However, neither the above-named supplier, nor any of its subsidiaries, assumes any liability whatsoever for the accuracy or completeness of the information contained herein.
Final determination of suitability of any material is the sole responsibility of the user. All materials may present unknown hazards and should be used with caution. Although certain hazards are described herein, we cannot guarantee that these are the only hazards that exist.

Safety Data Sheet
Kerosene

NFPA:



SECTION 1. PRODUCT AND COMPANY IDENTIFICATION

Product name	:	Kerosene			
Synonyms	:	Dual Purpose, K1, Dyed K1, Kerosine, Low Aromatic Feedstock, SRK Solvent, Arctic Grade Fuel Oil (DFA), Heater Oil, Range Oil, Coal Oil, K2, Gas Oil, 888100004861			
SDS Number	:	888100004861	**Version**	:	2.16
Product Use Description	:	Fuel			
Company	:	For: Tesoro Refining & Marketing Co. 19100 Ridgewood Parkway, San Antonio, TX 78259			
Tesoro Call Center	:	(877) 783-7676	**Chemtrec (Emergency Contact)**	:	(800) 424-9300

SECTION 2. HAZARDS IDENTIFICATION

Classifications : Flammable Liquid – Category 3
Aspiration Hazard – Category 1
Skin Irritation – Category 2
Specific Target Organ Toxicity (Single Exposure) – Category 3
Chronic Aquatic Toxicity – Category 2

Pictograms

Signal Word : **Danger**

Hazard Statements : Flammable liquid and vapor.
May be fatal if swallowed and enters airways – do not siphon by mouth.
Causes skin irritation. Repeated or prolonged skin contact can cause skin irritation and dermatitis.
May cause drowsiness or dizziness by inhalation.
May cause irritation of respiratory system.
Toxic to aquatic life with long lasting effects.

Precautionary statements:

Prevention : Keep away from heat, sparks, open flames, welding and hot surfaces.

	No smoking. Keep container tightly closed. Ground and/or bond container and receiving equipment. Use explosion-proof electrical equipment. Use only non-sparking tools if tools are used in flammable atmosphere. Take precautionary measures against static discharge. Wear gloves, eye protection and face protection as needed to prevent skin and eye contact with liquid. Wash hands or liquid-contacted skin thoroughly after handling. Do not eat, drink or smoke when using this product. Do not breathe vapors or mists. Use only outdoors or in a well-ventilated area.
Response	In case of fire: Use dry chemical, CO2, water spray or fire fighting foam to extinguish. If swallowed: Immediately call a poison center, doctor, hospital emergency room, medical clinic or 911. Do NOT induce vomiting. Rinse mouth. If skin irritation persists, get medical attention. If inhaled: Remove person to fresh air and keep comfortable for breathing. Get medical attention if you feel unwell.
Storage	Store in a well ventilated place. Keep cool. Store locked up. Keep container tightly closed . Use only approved containers.
Disposal	Dispose of contents/containers to approved disposal site in accordance with local, regional, national, and/or international regulations.

SECTION 3. COMPOSITION/INFORMATION ON INGREDIENTS

Component	CAS-No.	Weight %
Kerosene (petroleum)	8008-20-6	100%
Naphthalene	91-20-3	0 to 3%
Ethyl Benzene	100-41-4	0 to 1%

SECTION 4. FIRST AID MEASURES

Inhalation	:	Move to fresh air. If not breathing, give artificial respiration. If necessary, provide additional oxygen once breathing is restored if trained to do so. Seek medical attention immediately.
Skin contact	:	Take off all contaminated clothing immediately. Wash off immediately with soap and plenty of water. Wash contaminated clothing before re-use. If skin irritation persists, seek medical attention.
Eye contact	:	Remove contact lenses. In case of eye contact, immediately flush with low pressure, cool water for at least 15 minutes, opening eyelids to ensure flushing. Seek medical advice.
Ingestion	:	Do NOT induce vomiting. If vomiting does occur naturally, keep head below the hips to reduce the risks of aspiration. Obtain medical attention. Do not give liquids. Small amounts of material which enter the mouth should be rinsed out until the

taste is dissipated.

Notes to physician : Symptoms: Aspiration may cause pulmonary edema and pneumonitis. Treatment: Do not induce vomiting, use gastric lavage only. Remove from further exposure and treat symptomatically.

SECTION 5. FIRE-FIGHTING MEASURES

Suitable extinguishing media : Carbon dioxide (CO2), Water spray, Dry chemical, Foam, Keep containers and surroundings cool with water spray., Water may be ineffective for fighting the fire, but may be used to cool fire-exposed containers.

Specific hazards during fire fighting : Fire Hazard Do not use a solid water stream as it may scatter and spread fire. Cool closed containers exposed to fire with water spray. Sealed containers may rupture when heated. Above the flash point, explosive vapor-air mixtures may be formed. Vapors can flow along surfaces to distant ignition source and flash back.

Special protective equipment for fire-fighters : Firefighting activities that may result in potential exposure to high heat, smoke or toxic by-products of combustion should require NIOSH/MSHA- approved pressure-demand self-contained breathing apparatus with full facepiece and full protective clothing.

Further information : Isolate area around container involved in fire. Cool tanks, shells, and containers exposed to fire and excessive heat with water. For massive fires the use of unmanned hose holders or monitor nozzles may be advantageous to further minimize personnel exposure. Major fires may require withdrawal, allowing the tank to burn. Large storage tank fires typically require specially trained personnel and equipment to extinguish the fire, often including the need for properly applied fire fighting foam.

SECTION 6. ACCIDENTAL RELEASE MEASURES

Personal precautions : ACTIVATE FACILITY'S SPILL CONTINGENCY OR EMERGENCY RESPONSE PLAN if applicable. Consider wind direction; stay upwind and uphill, if possible. Evacuate nonessential personnel and remove or secure all ignition sources. Evaluate the direction of product travel, diking, sewers, etc. to contain spill areas. Spills may infiltrate subsurface soil and groundwater; professional assistance may be necessary to determine the extent of subsurface impact.

Environmental precautions : Carefully contain and stop the source of the spill, if safe to do so. Protect bodies of water by diking, absorbents, or absorbent boom, if possible. Do not flush down sewer or drainage systems, unless system is designed and permitted to handle such material. The use of fire fighting foam may be useful in certain situations to reduce vapors. The proper use of water spray may effectively disperse product vapors or the liquid itself, preventing contact with ignition sources or areas/equipment that require protection.

Methods for cleaning up : Take up with sand or oil absorbing materials. Carefully shovel, scoop or sweep up into a waste container for reclamation or disposal - caution, flammable vapors may accumulate in closed containers. Response and clean-up crews must be properly trained and must utilize proper protective equipment (see Section 8).

SECTION 7. HANDLING AND STORAGE

Precautions for safe handling : Keep away from fire, sparks and heated surfaces. No smoking near areas where material is stored or handled. The product should only be stored and handled in

areas with intrinsically safe electrical classification.

: Hydrocarbon liquids including this product can act as a non-conductive flammable liquid (or static accumulators), and may form ignitable vapor-air mixtures in storage tanks or other containers. Precautions to prevent static-initated fire or explosion during transfer, storage or handling, include but are not limited to these examples:

(1) Ground and bond containers during product transfers. Grounding and bonding may not be adequate protection to prevent ignition or explosion of hydrocarbon liquids and vapors that are static accumulators.

(2) Special slow load procedures for "switch loading" must be followed to avoid the static ignition hazard that can exist when higher flash point material (such as fuel oil or diesel) is loaded into tanks previously containing low flash point products (such gasoline or naphtha).

(3) Storage tank level floats must be effectively bonded.

For more information on precautions to prevent static-initated fire or explosion, see NFPA 77, Recommended Practice on Static Electricity (2007), and API Recommended Practice 2003, Protection Against Ignitions Arising Out of Static, Lightning, and Stray Currents (2008).

Conditions for safe storage, including incompatibilities

: Keep away from flame, sparks, excessive temperatures and open flame. Use approved containers. Keep containers closed and clearly labeled. Empty or partially full product containers or vessels may contain explosive vapors. Do not pressurize, cut, heat, weld or expose containers to sources of ignition. Store in a well-ventilated area. The storage area should comply with NFPA 30 "Flammable and Combustible Liquid Code". The cleaning of tanks previously containing this product should follow API Recommended Practice (RP) 2013 "Cleaning Mobile Tanks In Flammable and Combustible Liquid Service" and API RP 2015 "Cleaning Petroleum Storage Tanks".

: Keep away from food, drink and animal feed. Incompatible with oxidizing agents. Incompatible with acids.

: Emergency eye wash capability should be available in the near proximity to operations presenting a potential splash exposure.

SECTION 8. EXPOSURE CONTROLS / PERSONAL PROTECTION

Exposure Guidelines

List	Components	CAS-No.	Type:	Value
OSHA Z1	Naphthalene	91-20-3	PEL	10 ppm 50 mg/m3
	Ethylbenzene	100-41-4	PEL	100ppm 435 mg/m3
ACGIH	Kerosene (petroleum)	8008-20-6	TWA	200 mg/m3
	Ethylbenzene	100-41-4	TWA STEL	100ppm 434 mg/m3 125ppm 543 mg/m3
	Naphthalene	91-20-3	TWA	10 ppm
		91-20-3	STEL	15 ppm

Engineering measures

: Use adequate ventilation to keep gas and vapor concentrations of this product below occupational exposure and flammability limits, particularly in confined spaces. Use only intrinsically safe electrical equipment approved for use in classified areas. Emergency eye wash capability should be available in the vicinity of any potential splash exposure.

Eye protection	:	Goggles and face shield as needed to prevent eye and face contact.
Hand protection	:	Gloves constructed of nitrile, neoprene, or PVC are recommended.
Skin and body protection	:	Chemical protective clothing such as DuPont TyChem ®, Barricade or equivalent, recommended based on degree of exposure. Consult manufacturer specifications for further information.
Respiratory protection	:	A NIOSH/ MSHA-approved air-purifying respirator with organic vapor cartridges or canister may be permissible under certain circumstances where airborne concentrations are or may be expected to exceed exposure limits or for odor or irritation. Protection provided by air-purifying respirators is limited. Refer to OSHA 29 CFR 1910.134, ANSI Z88.2-1992, NIOSH Respirator Decision Logic, and the manufacturer for additional guidance on respiratory protection selection. Use a NIOSH/ MSHA-approved positive-pressure supplied-air respirator if there is a potential for uncontrolled release, exposure levels are not known, in oxygen-deficient atmospheres, or any other circumstance where an air-purifying respirator may not provide adequate protection.
Work / Hygiene practices	:	Emergency eye wash capability should be available in the near proximity to operations presenting a potential splash exposure. Use good personal hygiene practices. Avoid repeated and/or prolonged skin exposure. Wash hands before eating, drinking, smoking, or using toilet facilities. Do not use as a cleaning solvent on the skin. Do not use solvents or harsh abrasive skin cleaners for washing this product from exposed skin areas. Waterless hand cleaners are effective. Promptly remove contaminated clothing and launder before reuse. Use care when laundering to prevent the formation of flammable vapors which could ignite via washer or dryer. Consider the need to discard contaminated leather shoes and gloves.

SECTION 9. PHYSICAL AND CHEMICAL PROPERTIES

Appearance	:	Clear to straw colored liquid
Odor		Characteristic petroleum or kerosene-like odor
Odor threshold		0.1 - 1 ppm typically reported
pH		Not applicable
Melting point/freezing point		Gel point can be about -15°F; freezing requires laboratory conditions
Initial boiling point & range		154 - 372 °C (310° - 702 °F)
Flash point		38°C (100°F) Minimum
Evaporation rate		Higher initially and declining as lighter components evaporate
Flammability (solid, gas)		Flammable vapor released by liquid
Upper explosive limit		5.0 %(V)
Lower explosive limit		0.7 %(V)
Vapor pressure		< 2 mm Hg at 20 °C
Vapor density (air = 1)		> 4.5
		0.8 g/mL

Relative density (water = 1)	
	0.0005 g/100 mL
Solubility (in water)	
	3.3 to 6 as log Pow
Partition coefficient (n-octanol/water)	
	210 °C (410°F)
Auto-ignition temperature	
	Will evaporate or boil and possibly ignite before decomposition occurs.
Decomposition temperature	
	1.6 mm^2/s at 40°C
Kinematic viscosity	

Conductivity (conductivity can be reduced by environmental factors such as a decrease in temperature	Diesel Fuel Oils at terminal load rack:	At least 25 pS/m
	Ultra Low Sulfur Diesel (ULSD) without conductivity additive:	0 pS/m to 5 pS/m
	ULSD at terminal load rack with conductivity additive:	At least 50 pS/m
	JP-8 at terminal load rack:	150 pS/m to 600 pS/m

SECTION 10. STABILITY AND REACTIVITY

Reactivity : Vapors may form explosive mixture with air. Hazardous polymerization does not occur.

Chemical stability : Stable under normal conditions.

Possibility of hazardous reactions Can react with strong oxidizing agents, peroxides, acids and alkalies

Conditions to avoid : Avoid high temperatures, open flames, sparks, welding, smoking and other ignition sources. Avoid static charge accumulation and discharge (see Section 7).

Hazardous decomposition products : Ignition and burning can release carbon monoxide, carbon dioxide, non-combusted hydrocarbons (smoke) and, depending on formulation, trace amounts of sulfur dioxide. Diesel exhaust particals may be a lung hazard (see Section 11).

SECTION 11. TOXICOLOGICAL INFORMATION

Skin irritation : Irritating to skin. Repeated or prolonged contact can cause dryness, cracking and dermatitis. Liquid may be absorbed through skin in toxic amounts if large areas of the skin are repeatedly exposed.

Eye irritation : May cause eye irritation.

Inhalation Inhalation of vapors or mist may result in respiratory tract irritation and central nervous system effects including headache, dizziness, loss of balance and coordination, unconsciousness, coma, respiratory failure and death.

Chronic Exposure Similar products produced skin cancer and systemic toxicity in laboratory animals following repeated applications. The significance of these results to human exposure has not been determined.

Further information : Kerosene does not have a measurable effect on human reproduction or development.
Kerosene is not listed as carcinogenic by NTP, OSHA, and ACGIH. IARC has listed kerosene as a probable human carcinogen.
Some petroleum distillates have been found to cause adverse reproductive effects

in laboratory animals.
Acute and chronic exposure to kerosene may result in CNS effects including irritability, restlessness, ataxia, drowsiness, convulsions, coma and death. The most common health effect associated with chronic kerosene exposure is dermatitis.

Component:

Kerosene (petroleum)	8008-20-6	Acute oral toxicity: LD50 rat 4 hour Dose: >5,000 mg/kg Acute dermal toxicity: LD50 rabbit Dose: >2,001 mg/kg Acute inhalation toxicity: LC50 rat Dose: >5,000 mg/l Exposure time: 4 h Skin irritation: Classification: Irritating to skin. Result: Skin irritation
Naphthalene	91-20-3	Acute oral toxicity: LD50 rat Dose: 2,001 mg/kg Acute dermal toxicity: LD50 rat Dose: 2,501 mg/kg Acute inhalation toxicity: LC50 rat Dose: 101 mg/l Exposure time: 4 h Skin irritation: Classification: Irritating to skin. Result: Mild skin irritation Eye irritation: Classification: Irritating to eyes. Result: Mild eye irritation Carcinogenicity: N11.00422130

Carcinogenicity

NTP	Naphthalene (CAS-No.: 91-20-3)
IARC	Kerosene is not listed as carcinogenic by NTP, OSHA, and ACGIH. IARC has listed kerosene as a probable human carcinogen. naphthalene (CAS-No.: 91-20-3) Kerosene (petroleum) (CAS-No.: 8008-20-6)
CA Prop 65	WARNING! This product contains a chemical known to the State of California to cause cancer. Naphthalene (CAS-No.: 91-20-3)

SECTION 12. ECOLOGICAL INFORMATION

Additional ecological information : Release of this product should be prevented from contaminating soil and water and from entering drainage and sewer systems. U.S.A. regulations require reporting spills of this material that could reach any surface waters. The toll free number for the U.S. Coast Guard National Response Center is (800) 424-8802. Naphthalene (91-20-3) one of the ingredients in this mixture is classified as a Marine Pollutant.

Component:

Naphthalene	91-20-3	Toxicity to algae: EC50 Species: Dose: 33 mg/l Exposure time: 24 h

SECTION 13. DISPOSAL CONSIDERATIONS

Disposal : Whatever cannot be saved for recovery or recycling should be handled as hazardous waste and sent to a RCRA approved waste facility.
Processing, use or contamination of this product may change the waste management options.
State and local disposal regulations may differ from federal disposal regulations.
Dispose of container and unused contents in accordance with federal, state and local requirements.

SECTION 14. TRANSPORT INFORMATION

CFR

Proper shipping name	: Kerosene
UN-No.	: 1223
Class	: 3
Packing group	: III

TDG

Proper shipping name	: Kerosene
UN-No.	: UN1223
Class	: 3
Packing group	: III

IATA Cargo Transport

UN UN-No.	: UN1223
Description of the goods	: Kerosene
Class	: 3
Packaging group	: III
ICAO-Labels	: 3
Packing instruction (cargo aircraft)	: 366
Packing instruction (cargo aircraft)	: Y344

IATA Passenger Transport

UN UN-No.	: UN1223
Description of the goods	: Kerosene
Class	: 3
Packaging group	: III
ICAO-Labels	: 3
Packing instruction (passenger aircraft)	: 355
Packing instruction (passenger aircraft)	: Y344

IMDG-Code

UN-No.	:	UN 1223
Description of the goods	:	Kerosene
Class	:	3
Packaging group	:	III
IMDG-Labels	:	3
EmS Number	:	F-E S-E
Marine pollutant	:	Yes

SECTION 15. REGULATORY INFORMATION

TSCA Status : On TSCA Inventory

DSL Status : All components of this product are on the Canadian DSL list.

SARA 311/312 Hazards : Acute Health Hazard
Chronic Health Hazard
Fire Hazard

CERCLA SECTION 103 and SARA SECTION 304 (RELEASE TO THE ENVIROMENT)
The CERCLA definition of hazardous substances contains a "petroleum exclusion" clause which exempts crude oil. Fractions of crude oil, and products (both finished and intermediate) from the crude oil refining process and any indigenous components of such from the CERCLA Section 103 reporting requirements. However, other federal reporting requirements, including SARA Section 304, as well as the Clean Water Act may still apply**.**

California Prop. 65 : WARNING! This product contains a chemical known to the State of California to cause cancer.

Naphthalene 91-20-3

SECTION 16. OTHER INFORMATION

Further information

The information provided in this Safety Data Sheet is correct to the best of our knowledge, information and belief at the date of its publication. The information given is designed only as guidance for safe handling, use, processing, storage, transportation, disposal and release and is not to be considered a warranty or quality specification. The information relates only to the specific material designated and may not be valid for such material used in combination with any other materials or in any process, unless specified in the text.

Revision Date : 11/17/2012

Fisher Scientific

Part of Thermo Fisher Scientific

SAFETY DATA SHEET

Creation Date 12-Sep-2014 **Revision Date** 12-Dec-2014 **Revision Number** 1

1. Identification

Product Name **Lead**

Cat No. : **L27-1RL**

Synonyms Lead metal.

Recommended Use Laboratory chemicals.

Uses advised against No Information available

Details of the supplier of the safety data sheet

Emergency Telephone Number
Chemtrec US: (800) 424-9300
Chemtrec EU: 001 (202) 483-7616

2. Hazard(s) identification

Classification

This chemical is considered hazardous by the 2012 OSHA Hazard Communication Standard (29 CFR 1910.1200)

Acute oral toxicity	Category 4
Acute Inhalation Toxicity - Dusts and Mists	Category 4
Carcinogenicity	Category 1B
Reproductive Toxicity	Category 1A
Specific target organ toxicity (single exposure)	Category 3
Target Organs - Central nervous system (CNS).	
Specific target organ toxicity - (repeated exposure)	Category 2
Target Organs - Kidney, Blood.	

Label Elements

Signal Word
Danger

Hazard Statements
Harmful if swallowed
Harmful if inhaled
May cause drowsiness or dizziness
May cause cancer
May damage the unborn child. Suspected of damaging fertility
May cause damage to organs through prolonged or repeated exposure

Precautionary Statements
Prevention
Obtain special instructions before use
Do not handle until all safety precautions have been read and understood
Use personal protective equipment as required
Wash face, hands and any exposed skin thoroughly after handling
Do not eat, drink or smoke when using this product
Use only outdoors or in a well-ventilated area
Do not breathe dust/fume/gas/mist/vapors/spray
Response
IF exposed or concerned: Get medical attention/advice
Inhalation
IF INHALED: Remove victim to fresh air and keep at rest in a position comfortable for breathing
Ingestion
IF SWALLOWED: Call a POISON CENTER or doctor/physician if you feel unwell
Rinse mouth
Storage
Store locked up
Store in a well-ventilated place. Keep container tightly closed
Disposal
Dispose of contents/container to an approved waste disposal plant
Hazards not otherwise classified (HNOC)
Very toxic to aquatic life with long lasting effects
Other hazards
WARNING! This product contains a chemical known in the State of California to cause cancer. WARNING! This product contains a chemical known in the State of California to cause birth defects or other reproductive harm.

3. Composition / information on ingredients

Component	CAS-No	Weight %
Lead	7439-92-1	> 99

4. First-aid measures

Eye Contact Rinse immediately with plenty of water, also under the eyelids, for at least 15 minutes.

Skin Contact Wash off immediately with plenty of water for at least 15 minutes.

Inhalation Move to fresh air.

Ingestion Do not induce vomiting.

Most important symptoms/effects No information available.
Notes to Physician Treat symptomatically

5. Fire-fighting measures

Unsuitable Extinguishing Media No information available

Flash Point No information available

Method - No information available

Autoignition Temperature No information available

Explosion Limits

Upper No data available

Lower No data available

Sensitivity to Mechanical Impact No information available

Sensitivity to Static Discharge No information available

Specific Hazards Arising from the Chemical

Keep product and empty container away from heat and sources of ignition.

Hazardous Combustion Products

None known

Protective Equipment and Precautions for Firefighters

As in any fire, wear self-contained breathing apparatus pressure-demand, MSHA/NIOSH (approved or equivalent) and full protective gear.

NFPA

Health	Flammability	Instability	Physical hazards
2	0	0	N/A

6. Accidental release measures

Personal Precautions Ensure adequate ventilation. Use personal protective equipment.

Environmental Precautions See Section 12 for additional ecological information. Avoid release to the environment. Collect spillage.

Methods for Containment and Clean Up No information available.

7. Handling and storage

Handling Wear personal protective equipment. Ensure adequate ventilation.

Storage Keep containers tightly closed in a dry, cool and well-ventilated place.

8. Exposure controls / personal protection

Exposure Guidelines

Component	ACGIH TLV	OSHA PEL	NIOSH IDLH
Lead	TWA: 0.05 mg/m³	TWA: 50 µg/m³	IDLH: 100 mg/m³ TWA: 0.050 mg/m³

Component	Quebec	Mexico OEL (TWA)	Ontario TWAEV
Lead	TWA: 0.05 mg/m³	TWA: 0.15 mg/m³	TWA: 0.05 mg/m³

Legend

ACGIH - American Conference of Governmental Industrial Hygienists
OSHA - Occupational Safety and Health Administration
NIOSH IDLH: The National Institute for Occupational Safety and Health Immediately Dangerous to Life or Health

Engineering Measures Ensure adequate ventilation, especially in confined areas. Ensure that eyewash stations and safety showers are close to the workstation location.

Personal Protective Equipment

Eye/face Protection Wear appropriate protective eyeglasses or chemical safety goggles as described by OSHA's eye and face protection regulations in 29 CFR 1910.133 or European Standard EN166.

Skin and body protection Wear appropriate protective gloves and clothing to prevent skin exposure.

Respiratory Protection	Follow the OSHA respirator regulations found in 29 CFR 1910.134 or European Standard EN 149. Use a NIOSH/MSHA or European Standard EN 149 approved respirator if exposure limits are exceeded or if irritation or other symptoms are experienced.
Hygiene Measures	Handle in accordance with good industrial hygiene and safety practice.

9. Physical and chemical properties

Physical State	Solid
Appearance	Light blue
Odor	Odorless
Odor Threshold	No information available
pH	Not applicable
Melting Point/Range	327.4 °C / 621.3 °F
Boiling Point/Range	1740 °C / 3164 °F
Flash Point	No information available
Evaporation Rate	No information available
Flammability (solid,gas)	No information available
Flammability or explosive limits	
Upper	No data available
Lower	No data available
Vapor Pressure	1.3 mmHg @ 970 °C
Vapor Density	No information available
Relative Density	11.3
Solubility	Insoluble in water
Partition coefficient; n-octanol/water	No data available
Autoignition Temperature	No information available
Decomposition Temperature	No information available
Viscosity	No information available
Molecular Formula	Pb
Molecular Weight	207.19

10. Stability and reactivity

Reactive Hazard	None known, based on information available
Stability	Stable under normal conditions.
Conditions to Avoid	Incompatible products.
Incompatible Materials	Strong oxidizing agents
Hazardous Decomposition Products	None under normal use conditions
Hazardous Polymerization	Hazardous polymerization does not occur.
Hazardous Reactions	None under normal processing.

11. Toxicological information

Acute Toxicity

Component Information

Toxicologically Synergistic Products	No information available

Delayed and immediate effects as well as chronic effects from short and long-term exposure

Irritation	No information available
Sensitization	No information available
Carcinogenicity	The table below indicates whether each agency has listed any ingredient as a carcinogen.

Component	CAS-No	IARC	NTP	ACGIH	OSHA	Mexico
Lead	7439-92-1	Group 2B	Reasonably Anticipated	A3	X	A3

IARC: (International Agency for Research on Cancer)

NTP: (National Toxicity Program)

ACGIH: (American Conference of Governmental Industrial Hygienists)

Mexico - Occupational Exposure Limits - Carcinogens

IARC: (International Agency for Research on Cancer)
Group 1 - Carcinogenic to Humans
Group 2A - Probably Carcinogenic to Humans
Group 2B - Possibly Carcinogenic to Humans

NTP: (National Toxicity Program)
Known - Known Carcinogen
Reasonably Anticipated - Reasonably Anticipated to be a Human Carcinogen

A1 - Known Human Carcinogen
A2 - Suspected Human Carcinogen
A3 - Animal Carcinogen
ACGIH: (American Conference of Governmental Industrial Hygienists)

Mexico - Occupational Exposure Limits - Carcinogens
A1 - Confirmed Human Carcinogen
A2 - Suspected Human Carcinogen
A3 - Confirmed Animal Carcinogen
A4 - Not Classifiable as a Human Carcinogen
A5 - Not Suspected as a Human Carcinogen

Mutagenic Effects No information available

Reproductive Effects No information available.

Developmental Effects No information available.

Teratogenicity No information available.

STOT - single exposure Central nervous system (CNS)
STOT - repeated exposure Kidney Blood

Aspiration hazard No information available

Symptoms / effects,both acute and delayed No information available

Endocrine Disruptor Information No information available

Other Adverse Effects The toxicological properties have not been fully investigated.

12. Ecological information

(Bad file name)

Ecotoxicity

.

Component	Freshwater Algae	Freshwater Fish	Microtox	Water Flea
Lead	Not listed	1.32 mg/L LC50 96 h 1.17 mg/L LC50 96 h 0.44 mg/L LC50 96 h	Not listed	600 µg/L EC50 = 48 h

Persistence and Degradability No information available

Bioaccumulation/ Accumulation No information available.

Mobility No information available.

13. Disposal considerations

Waste Disposal Methods Chemical waste generators must determine whether a discarded chemical is classified as a hazardous waste. Chemical waste generators must also consult local, regional, and national hazardous waste regulations to ensure complete and accurate classification.

14. Transport information

DOT Not regulated
TDG Not regulated
IATA Not regulated
IMDG/IMO Not regulated

15. Regulatory information

International Inventories

Component	TSCA	DSL	NDSL	EINECS	ELINCS	NLP	PICCS	ENCS	AICS	IECSC	KECL
Lead	X	X	-	231-100-4	-		X	X	X	X	X

Legend:
X - Listed
E - Indicates a substance that is the subject of a Section 5(e) Consent order under TSCA.
F - Indicates a substance that is the subject of a Section 5(f) Rule under TSCA.
N - Indicates a polymeric substance containing no free-radical initiator in its inventory name but is considered to cover the designated polymer made with any free-radical initiator regardless of the amount used.
P - Indicates a commenced PMN substance
R - Indicates a substance that is the subject of a Section 6 risk management rule under TSCA.
S - Indicates a substance that is identified in a proposed or final Significant New Use Rule
T - Indicates a substance that is the subject of a Section 4 test rule under TSCA.
XU - Indicates a substance exempt from reporting under the Inventory Update Rule, i.e. Partial Updating of the TSCA Inventory Data Base Production and Site Reports (40 CFR 710(B).
Y1 - Indicates an exempt polymer that has a number-average molecular weight of 1,000 or greater.
Y2 - Indicates an exempt polymer that is a polyester and is made only from reactants included in a specified list of low concern reactants that comprises one of the eligibility criteria for the exemption rule.

U.S. Federal Regulations

TSCA 12(b) Not applicable

SARA 313

Component	CAS-No	Weight %	SARA 313 - Threshold Values %
Lead	7439-92-1	> 99	0.1

SARA 311/312 Hazardous Categorization

Acute Health Hazard	Yes
Chronic Health Hazard	Yes
Fire Hazard	No
Sudden Release of Pressure Hazard	No
Reactive Hazard	No

Clean Water Act

Component	CWA - Hazardous Substances	CWA - Reportable Quantities	CWA - Toxic Pollutants	CWA - Priority Pollutants
Lead	-	-	X	X

Clean Air Act

Component	HAPS Data	Class 1 Ozone Depletors	Class 2 Ozone Depletors
Lead	X		-

OSHA Occupational Safety and Health Administration
Not applicable

Component	Specifically Regulated Chemicals	Highly Hazardous Chemicals
Lead	30 µg/m³ Action Level 50 µg/m³ TWA	-

CERCLA
This material, as supplied, contains one or more substances regulated as a hazardous substance under the Comprehensive Environmental Response Compensation and Liability Act (CERCLA) (40 CFR 302)

Component	Hazardous Substances RQs	CERCLA EHS RQs
Lead	10 lb	-

California Proposition 65 This product contains the following Proposition 65 chemicals:

Component	CAS-No	California Prop. 65	Prop 65 NSRL	Category
Lead	7439-92-1	Carcinogen Developmental Female Reproductive Male Reproductive	15 µg/day	Developmental Carcinogen

State Right-to-Know

Component	Massachusetts	New Jersey	Pennsylvania	Illinois	Rhode Island
Lead	X	X	X	X	X

U.S. Department of Transportation

Reportable Quantity (RQ): Y
DOT Marine Pollutant N
DOT Severe Marine Pollutant N

U.S. Department of Homeland Security
This product does not contain any DHS chemicals.

Other International Regulations

Mexico - Grade No information available

Canada
This product has been classified in accordance with the hazard criteria of the Controlled Products Regulations (CPR) and the MSDS contains all the information required by the CPR

WHMIS Hazard Class D2A Very toxic materials
D1B Toxic materials

16. Other information

Prepared By Regulatory Affairs
Thermo Fisher Scientific
Email: EMSDS.RA@thermofisher.com

Creation Date 12-Sep-2014
Revision Date 12-Dec-2014
Print Date 12-Dec-2014
Revision Summary This document has been updated to comply with the US OSHA HazCom 2012 Standard replacing the current legislation under 29 CFR 1910.1200 to align with the Globally Harmonized System of Classification and Labeling of Chemicals (GHS)

Disclaimer

The information provided on this Safety Data Sheet is correct to the best of our knowledge, information and belief at the date of its publication. The information given is designed only as a guide for safe handling, use, processing, storage, transportation, disposal and release and is not to be considered as a warranty or quality specification. The information relates only to the specific material designated and may not be valid for such material used in combination with any other material or in any process, unless specified in the text.

End of SDS

SAFETY DATA SHEET

Creation Date 17-Jan-2011 **Revision Date** 03-Aug-2015 **Revision Number** 3

1. Identification

Product Name **Magnesium**

Cat No. : **AC191080000; AC191080025; AC191080100; AC191085000**

Synonyms Magnesium metal (ribbons/turnings)

Recommended Use Laboratory chemicals.

Uses advised against No Information available

Details of the supplier of the safety data sheet

Company
Fisher Scientific
One Reagent Lane
Fair Lawn, NJ 07410
Tel: (201) 796-7100

Entity / Business Name
Acros Organics
One Reagent Lane
Fair Lawn, NJ 07410

Emergency Telephone Number
For information **US** call: 001-800-ACROS-01 / **Europe** call: +32 14 57 52 11
Emergency Number **US:**001-201-796-7100 / **Europe:** +32 14 57 52 99
CHEMTREC Tel. No.**US:**001-800-424-9300 / **Europe:**001-703-527-3887

2. Hazard(s) identification

Classification
This chemical is considered hazardous by the 2012 OSHA Hazard Communication Standard (29 CFR 1910.1200)

Flammable solids	Category 1
Self-heating substances and mixtures	Category 2
Substances/mixtures which, in contact with water, emit flammable gases	Category 2

Label Elements

Signal Word
Danger

Hazard Statements
Flammable solid
Self-heating in large quantities; may catch fire
In contact with water releases flammable gas

Precautionary Statements
Prevention
Keep away from heat/sparks/open flames/hot surfaces. - No smoking
Ground/bond container and receiving equipment
Use explosion-proof electrical/ventilating/lighting/equipment
Wear protective gloves/protective clothing/eye protection/face protection
Keep cool. Protect from sunlight
Keep away from any possible contact with water, because of violent reaction and possible flash fire
Handle under inert gas. Protect from moisture
Skin
Brush off loose particles from skin. Immerse in cool water/wrap with wet bandages
Fire
In case of fire: Use CO2, dry chemical, or foam for extinction
Storage
Maintain air gap between stacks/pallets
Store away from other materials
Store in a dry place. Store in a closed container
Store bulk masses at temperatures not exceeding manufacturer recommendations
Disposal
Dispose of contents/container to an approved waste disposal plant
Hazards not otherwise classified (HNOC)
May form combustible dust concentrations in air

3. Composition / information on ingredients

Component	CAS-No	Weight %
Magnesium	7439-95-4	>95

4. First-aid measures

Eye Contact Rinse immediately with plenty of water, also under the eyelids, for at least 15 minutes. Obtain medical attention.

Skin Contact Wash off immediately with plenty of water for at least 15 minutes. Obtain medical attention.

Inhalation Remove from exposure, lie down. Move to fresh air. If breathing is difficult, give oxygen. If not breathing, give artificial respiration.

Ingestion Do not induce vomiting. Get medical attention.

Most important symptoms/effects No information available.
Notes to Physician Treat symptomatically

5. Fire-fighting measures

Suitable Extinguishing Media Dry chemical. approved class D extinguishers. clay. sodium carbonate. Do not use a solid water stream as it may scatter and spread fire.

Unsuitable Extinguishing Media No information available

Flash Point 500 °C / 932 °F
Method - No information available

Autoignition Temperature 472.8 °C / 883 °F
Explosion Limits
Upper No data available
Lower No data available
Sensitivity to Mechanical Impact No information available

Sensitivity to Static Discharge No information available

Specific Hazards Arising from the Chemical
Dust can form an explosive mixture in air. Water reactive. Produce flammable gases on contact with water. Flammable.

Hazardous Combustion Products
Magnesium oxides
Protective Equipment and Precautions for Firefighters
As in any fire, wear self-contained breathing apparatus pressure-demand, MSHA/NIOSH (approved or equivalent) and full protective gear.

NFPA

Health	Flammability	Instability	Physical hazards
0	4	2	W

6. Accidental release measures

Personal Precautions Use personal protective equipment. Ensure adequate ventilation. Avoid dust formation. Remove all sources of ignition.

Environmental Precautions See Section 12 for additional ecological information.

Methods for Containment and Clean Up Sweep up or vacuum up spillage and collect in suitable container for disposal. Avoid dust formation. Remove all sources of ignition. Ground and bond containers when transferring material. Use spark-proof tools and explosion-proof equipment.

7. Handling and storage

Handling Avoid contact with skin and eyes. Do not breathe dust. Use explosion-proof equipment. Use only non-sparking tools. Wash hands before breaks and immediately after handling the product. Ensure adequate ventilation. Wear personal protective equipment. Avoid dust formation.

Storage Keep in a dry, cool and well-ventilated place. Keep container tightly closed. Keep away from heat and sources of ignition. Never allow product to get in contact with water during storage. Store under an inert atmosphere.

8. Exposure controls / personal protection

Exposure Guidelines This product does not contain any hazardous materials with occupational exposure limits established by the region specific regulatory bodies.

Engineering Measures Ensure adequate ventilation, especially in confined areas. Use explosion-proof electrical/ventilating/lighting/equipment. Ensure that eyewash stations and safety showers are close to the workstation location.

Personal Protective Equipment

Eye/face Protection Wear appropriate protective eyeglasses or chemical safety goggles as described by OSHA's eye and face protection regulations in 29 CFR 1910.133 or European Standard EN166.

Skin and body protection Wear appropriate protective gloves and clothing to prevent skin exposure.

Respiratory Protection Follow the OSHA respirator regulations found in 29 CFR 1910.134 or European Standard EN 149. Use a NIOSH/MSHA or European Standard EN 149 approved respirator if exposure limits are exceeded or if irritation or other symptoms are experienced.

Hygiene Measures Handle in accordance with good industrial hygiene and safety practice.

9. Physical and chemical properties

Physical State	Solid
Appearance	Silver
Odor	Odorless
Odor Threshold	No information available
pH	7
Melting Point/Range	651 °C / 1203.8 °F
Boiling Point/Range	1107 °C / 2024.6 °F
Flash Point	500 °C / 932 °F
Evaporation Rate	Not applicable
Flammability (solid,gas)	No information available
Flammability or explosive limits	
Upper	No data available
Lower	No data available
Vapor Pressure	negligible
Vapor Density	Not applicable
Specific Gravity	No information available
Solubility	No information available
Partition coefficient; n-octanol/water	No data available
Autoignition Temperature	472.8 °C / 883 °F
Decomposition Temperature	No information available
Viscosity	Not applicable
Molecular Formula	Mg
Molecular Weight	24.3

10. Stability and reactivity

Reactive Hazard Yes

Stability Stable under normal conditions. Air sensitive. Water reactive.

Conditions to Avoid Protect from water. Exposure to air. Incompatible products. Exposure to moist air or water.

Incompatible Materials Acids, Strong oxidizing agents, Halogens, Acid chlorides

Hazardous Decomposition Products Magnesium oxides

Hazardous Polymerization Hazardous polymerization does not occur.

Hazardous Reactions None under normal processing.

11. Toxicological information

Acute Toxicity

Component Information

Component	LD50 Oral	LD50 Dermal	LC50 Inhalation
Magnesium	230 mg/kg (Rat)	Not listed	Not listed

Toxicologically Synergistic Products No information available

Delayed and immediate effects as well as chronic effects from short and long-term exposure

Irritation May cause irritation

Sensitization No information available

Carcinogenicity The table below indicates whether each agency has listed any ingredient as a carcinogen.

Component	CAS-No	IARC	NTP	ACGIH	OSHA	Mexico
Magnesium	7439-95-4	Not listed	Not listed	Not listed	Not listed	Not listed

Mutagenic Effects	No information available
Reproductive Effects	No information available.
Developmental Effects	No information available.
Teratogenicity	No information available.
STOT - single exposure	None known
STOT - repeated exposure	None known
Aspiration hazard	No information available
Symptoms / effects,both acute and delayed	No information available
Endocrine Disruptor Information	No information available
Other Adverse Effects	See actual entry in RTECS for complete information.

12. Ecological information

Ecotoxicity

Do not empty into drains.

Persistence and Degradability	Insoluble in water
Bioaccumulation/ Accumulation	No information available.
Mobility	Is not likely mobile in the environment due its low water solubility.

13. Disposal considerations

Waste Disposal Methods Chemical waste generators must determine whether a discarded chemical is classified as a hazardous waste. Chemical waste generators must also consult local, regional, and national hazardous waste regulations to ensure complete and accurate classification.

14. Transport information

DOT

UN-No	UN1869
Proper Shipping Name	MAGNESIUM
Hazard Class	4.1
Packing Group	III

TDG

UN-No	UN1869
Proper Shipping Name	MAGNESIUM
Hazard Class	4.1
Packing Group	III

IATA

UN-No	UN1869
Proper Shipping Name	MAGNESIUM
Hazard Class	4.1
Packing Group	III

IMDG/IMO

UN-No	UN1869
Proper Shipping Name	MAGNESIUM
Hazard Class	4.1
Packing Group	III

15. Regulatory information

All of the components in the product are on the following Inventory lists: X = listed

International Inventories

Component	TSCA	DSL	NDSL	EINECS	ELINCS	NLP	PICCS	ENCS	AICS	IECSC	KECL
Magnesium	X	X	-	231-104-6	-		X	-	X	X	X

Legend:
X - Listed
E - Indicates a substance that is the subject of a Section 5(e) Consent order under TSCA.
F - Indicates a substance that is the subject of a Section 5(f) Rule under TSCA.
N - Indicates a polymeric substance containing no free-radical initiator in its inventory name but is considered to cover the designated polymer made with any free-radical initiator regardless of the amount used.
P - Indicates a commenced PMN substance
R - Indicates a substance that is the subject of a Section 6 risk management rule under TSCA.
S - Indicates a substance that is identified in a proposed or final Significant New Use Rule
T - Indicates a substance that is the subject of a Section 4 test rule under TSCA.
XU - Indicates a substance exempt from reporting under the Inventory Update Rule, i.e. Partial Updating of the TSCA Inventory Data Base Production and Site Reports (40 CFR 710(B).
Y1 - Indicates an exempt polymer that has a number-average molecular weight of 1,000 or greater.
Y2 - Indicates an exempt polymer that is a polyester and is made only from reactants included in a specified list of low concern reactants that comprises one of the eligibility criteria for the exemption rule.

U.S. Federal Regulations

TSCA 12(b) Not applicable

SARA 313 Not applicable

SARA 311/312 Hazardous Categorization

Acute Health Hazard	No
Chronic Health Hazard	No
Fire Hazard	Yes
Sudden Release of Pressure Hazard	No
Reactive Hazard	Yes

Clean Water Act Not applicable

Clean Air Act Not applicable

OSHA Occupational Safety and Health Administration
Not applicable

CERCLA
Not applicable

California Proposition 65 This product does not contain any Proposition 65 chemicals

State Right-to-Know

Component	Massachusetts	New Jersey	Pennsylvania	Illinois	Rhode Island
Magnesium	X	X	X	-	X

U.S. Department of Transportation

Reportable Quantity (RQ):	N
DOT Marine Pollutant	N
DOT Severe Marine Pollutant	N

U.S. Department of Homeland Security
This product does not contain any DHS chemicals.

Other International Regulations

Mexico - Grade No information available

Canada
This product has been classified in accordance with the hazard criteria of the Controlled Products Regulations (CPR) and the MSDS contains all the information required by the CPR

WHMIS Hazard Class
B6 Reactive flammable material
B4 Flammable solid
F Dangerously reactive material

16. Other information

Prepared By
Regulatory Affairs
Thermo Fisher Scientific
Email: EMSDS.RA@thermofisher.com

Creation Date 17-Jan-2011
Revision Date 03-Aug-2015
Print Date 03-Aug-2015
Revision Summary This document has been updated to comply with the US OSHA HazCom 2012 Standard replacing the current legislation under 29 CFR 1910.1200 to align with the Globally Harmonized System of Classification and Labeling of Chemicals (GHS)

Disclaimer
The information provided on this Safety Data Sheet is correct to the best of our knowledge, information and belief at the date of its publication. The information given is designed only as a guide for safe handling, use, processing, storage, transportation, disposal and release and is not to be considered as a warranty or quality specification. The information relates only to the specific material designated and may not be valid for such material used in combination with any other material or in any process, unless specified in the text.

End of SDS

SAFETY DATA SHEET

Version 4.6
Revision Date 10/09/2015
Print Date 05/01/2016

1. PRODUCT AND COMPANY IDENTIFICATION

1.1 Product identifiers

Product name : Manganese

Product Number : 266167
Brand : Aldrich

CAS-No. : 7439-96-5

1.2 Relevant identified uses of the substance or mixture and uses advised against

Identified uses : Laboratory chemicals, Synthesis of substances

1.3 Details of the supplier of the safety data sheet

Company : Sigma-Aldrich
3050 Spruce Street
SAINT LOUIS MO 63103
USA

Telephone : +1 800-325-5832
Fax : +1 800-325-5052

1.4 Emergency telephone number

Emergency Phone # : (314) 776-6555

2. HAZARDS IDENTIFICATION

2.1 Classification of the substance or mixture

GHS Classification in accordance with 29 CFR 1910 (OSHA HCS)
Acute aquatic toxicity (Category 2), H401

For the full text of the H-Statements mentioned in this Section, see Section 16.

2.2 GHS Label elements, including precautionary statements

Pictogram none

Signal word none

Hazard statement(s)
H401 Toxic to aquatic life.

Precautionary statement(s)
P273 Avoid release to the environment.
P501 Dispose of contents/ container to an approved waste disposal plant.

2.3 Hazards not otherwise classified (HNOC) or not covered by GHS - none

3. COMPOSITION/INFORMATION ON INGREDIENTS

3.1 Substances

Formula : Mn
Molecular weight : 54.94 g/mol
CAS-No. : 7439-96-5
EC-No. : 231-105-1

Hazardous components

Component	Classification	Concentration
Manganese		
	Aquatic Acute 2; H401	<= 100 %

For the full text of the H-Statements mentioned in this Section, see Section 16.

4. FIRST AID MEASURES

4.1 Description of first aid measures

General advice
Consult a physician. Show this safety data sheet to the doctor in attendance.Move out of dangerous area.

If inhaled
If breathed in, move person into fresh air. If not breathing, give artificial respiration. Consult a physician.

In case of skin contact
Wash off with soap and plenty of water. Consult a physician.

In case of eye contact
Flush eyes with water as a precaution.

If swallowed
Never give anything by mouth to an unconscious person. Rinse mouth with water. Consult a physician.

4.2 Most important symptoms and effects, both acute and delayed
The most important known symptoms and effects are described in the labelling (see section 2.2) and/or in section 11

4.3 Indication of any immediate medical attention and special treatment needed
No data available

5. FIREFIGHTING MEASURES

5.1 Extinguishing media

Suitable extinguishing media
Use water spray, alcohol-resistant foam, dry chemical or carbon dioxide.

5.2 Special hazards arising from the substance or mixture
Manganese/manganese oxides

5.3 Advice for firefighters
Wear self-contained breathing apparatus for firefighting if necessary.

5.4 Further information
No data available

6. ACCIDENTAL RELEASE MEASURES

6.1 Personal precautions, protective equipment and emergency procedures
Avoid dust formation. Avoid breathing vapours, mist or gas. Ensure adequate ventilation.
For personal protection see section 8.

6.2 Environmental precautions
Prevent further leakage or spillage if safe to do so. Do not let product enter drains. Discharge into the environment must be avoided.

6.3 Methods and materials for containment and cleaning up
Pick up and arrange disposal without creating dust. Sweep up and shovel. Keep in suitable, closed containers for disposal.

6.4 Reference to other sections
For disposal see section 13.

7. HANDLING AND STORAGE

7.1 Precautions for safe handling
Further processing of solid materials may result in the formation of combustible dusts. The potential for combustible dust formation should be taken into consideration before additional processing occurs.

Provide appropriate exhaust ventilation at places where dust is formed.
For precautions see section 2.2.

7.2 Conditions for safe storage, including any incompatibilities
Keep container tightly closed in a dry and well-ventilated place.

Moisture sensitive. Handle and store under inert gas.
Storage class (TRGS 510): Non Combustible Solids

7.3 Specific end use(s)
Apart from the uses mentioned in section 1.2 no other specific uses are stipulated

8. EXPOSURE CONTROLS/PERSONAL PROTECTION

8.1 Control parameters

Components with workplace control parameters

Component	CAS-No.	Value	Control parameters	Basis
Manganese	7439-96-5	TWA	0.200000 mg/m3	USA. ACGIH Threshold Limit Values (TLV)
	Remarks	Central Nervous System impairment Adopted values or notations enclosed are those for which changes are proposed in the NIC See Notice of Intended Changes (NIC)		
		C	5 mg/m3	USA. Occupational Exposure Limits (OSHA) - Table Z-1 Limits for Air Contaminants
		Ceiling limit is to be determined from breathing-zone air samples.		
		C	5.000000 mg/m3	USA. Occupational Exposure Limits (OSHA) - Table Z-1 Limits for Air Contaminants
		Ceiling limit is to be determined from breathing-zone air samples.		
		TWA	1.000000 mg/m3	USA. NIOSH Recommended Exposure Limits
		ST	3.000000 mg/m3	USA. NIOSH Recommended Exposure Limits
		TWA	1.000000 mg/m3	USA. NIOSH Recommended Exposure Limits
		ST	3.000000 mg/m3	USA. NIOSH Recommended Exposure Limits
		C	5.000000 mg/m3	USA. Occupational Exposure Limits (OSHA) - Table Z-1 Limits for Air Contaminants
		Ceiling limit is to be determined from breathing-zone air samples.		
		TWA	1.000000 mg/m3	USA. NIOSH Recommended Exposure Limits
		ST	3.000000 mg/m3	USA. NIOSH Recommended Exposure Limits
		TWA	0.200000 mg/m3	USA. ACGIH Threshold Limit Values (TLV)
		Central Nervous System impairment Adopted values or notations enclosed are those for which changes are proposed in the NIC See Notice of Intended Changes (NIC) varies		
		TWA	0.100000 mg/m3	USA. ACGIH Threshold Limit Values (TLV)
		Central Nervous System impairment 2015 Adoption varies		

		TWA	0.020000 mg/m3	USA. ACGIH Threshold Limit Values (TLV)
		Central Nervous System impairment 2015 Adoption varies		
		TWA	0.1 mg/m3	USA. ACGIH Threshold Limit Values (TLV)
		Central Nervous System impairment varies		
		TWA	0.02 mg/m3	USA. ACGIH Threshold Limit Values (TLV)
		Central Nervous System impairment varies		

8.2 Exposure controls

Appropriate engineering controls
Handle in accordance with good industrial hygiene and safety practice. Wash hands before breaks and at the end of workday.

Personal protective equipment

Eye/face protection
Use equipment for eye protection tested and approved under appropriate government standards such as NIOSH (US) or EN 166(EU).

Skin protection
Handle with gloves. Gloves must be inspected prior to use. Use proper glove removal technique (without touching glove's outer surface) to avoid skin contact with this product. Dispose of contaminated gloves after use in accordance with applicable laws and good laboratory practices. Wash and dry hands.

Body Protection
Choose body protection in relation to its type, to the concentration and amount of dangerous substances, and to the specific work-place., The type of protective equipment must be selected according to the concentration and amount of the dangerous substance at the specific workplace.

Respiratory protection
Respiratory protection is not required. Where protection from nuisance levels of dusts are desired, use type N95 (US) or type P1 (EN 143) dust masks. Use respirators and components tested and approved under appropriate government standards such as NIOSH (US) or CEN (EU).

Control of environmental exposure
Prevent further leakage or spillage if safe to do so. Do not let product enter drains. Discharge into the environment must be avoided.

9. PHYSICAL AND CHEMICAL PROPERTIES

9.1 Information on basic physical and chemical properties

a)	Appearance	Form: chips Colour: grey, brown, silver
b)	Odour	odourless
c)	Odour Threshold	No data available
d)	pH	No data available
e)	Melting point/freezing point	Melting point/range: 1,244 °C (2,271 °F) - lit.
f)	Initial boiling point and boiling range	1,962 °C (3,564 °F) - lit.
g)	Flash point	Not applicable
h)	Evaporation rate	No data available
i)	Flammability (solid, gas)	No data available

j)	Upper/lower flammability or explosive limits	No data available
k)	Vapour pressure	No data available
l)	Vapour density	No data available
m)	Relative density	7.3 g/mL at 25 °C (77 °F)
n)	Water solubility	0.0007 g/l at 20 °C (68 °F) - slightly soluble
o)	Partition coefficient: n-octanol/water	No data available
p)	Auto-ignition temperature	No data available
q)	Decomposition temperature	No data available
r)	Viscosity	No data available
s)	Explosive properties	No data available
t)	Oxidizing properties	No data available

9.2 Other safety information
No data available

10. STABILITY AND REACTIVITY

10.1 Reactivity
No data available

10.2 Chemical stability
Stable under recommended storage conditions.

10.3 Possibility of hazardous reactions
No data available

10.4 Conditions to avoid
Avoid moisture.

10.5 Incompatible materials
acids, Halogens, Bases, Phosphorus, Sulphur oxides, Hydrogen peroxide, Oxidizing agents, Nitric acid, Sodium Hydroxide, Carbon dioxide (CO2), Nitryl Flouride, Steam

10.6 Hazardous decomposition products
Other decomposition products - No data available
In the event of fire: see section 5

11. TOXICOLOGICAL INFORMATION

11.1 Information on toxicological effects

Acute toxicity
LD50 Oral - Rat - female - > 2,000 mg/kg
(OECD Test Guideline 420)

LC50 Inhalation - Rat - male and female - 4 h - > 5.14 mg/l
(OECD Test Guideline 403)

Dermal: No data available

No data available

Skin corrosion/irritation
Skin - Rabbit
Result: No skin irritation
(OECD Test Guideline 404)

Serious eye damage/eye irritation
Eyes - Rabbit
Result: No eye irritation - 72 h
(OECD Test Guideline 405)

Respiratory or skin sensitisation
- Mouse
Result: Does not cause skin sensitisation.
(OECD Test Guideline 429)

Germ cell mutagenicity
No data available

Carcinogenicity

IARC: No component of this product present at levels greater than or equal to 0.1% is identified as probable, possible or confirmed human carcinogen by IARC.

ACGIH: No component of this product present at levels greater than or equal to 0.1% is identified as a carcinogen or potential carcinogen by ACGIH.

NTP: No component of this product present at levels greater than or equal to 0.1% is identified as a known or anticipated carcinogen by NTP.

OSHA: No component of this product present at levels greater than or equal to 0.1% is identified as a carcinogen or potential carcinogen by OSHA.

Reproductive toxicity

Overexposure may cause reproductive disorder(s) based on tests with laboratory animals.

Specific target organ toxicity - single exposure
No data available

Specific target organ toxicity - repeated exposure
No data available

Aspiration hazard
No data available

Additional Information
RTECS: Not available

Men exposed to manganese dusts showed a decrease in fertility. Chronic manganese poisoning primarily involves the central nervous system. Early symptoms include languor, sleepiness and weakness in the legs. A stolid mask-like appearance of the face, emotional disturbances such as uncontrollable laughter and a spastic gait with tendency to fall in walking are findings in more advanced cases. High incidence of pneumonia has been found in workers exposed to the dust or fume of some manganese compounds., To the best of our knowledge, the chemical, physical, and toxicological properties have not been thoroughly investigated.

Stomach - Irregularities - Based on Human Evidence
Stomach - Irregularities - Based on Human Evidence

12. ECOLOGICAL INFORMATION

12.1 Toxicity

Toxicity to fish	semi-static test NOEC - Oncorhynchus mykiss (rainbow trout) - 3.6 mg/l - 96 h (OECD Test Guideline 203)
Toxicity to daphnia and other aquatic invertebrates	Immobilization NOEC - Daphnia magna (Water flea) - 1.6 mg/l - 48 h (OECD Test Guideline 202)
Toxicity to algae	Growth inhibition EC50 - Desmodesmus subspicatus (Scenedesmus subspicatus) - 4.5 mg/l - 72 h (OECD Test Guideline 201)
Toxicity to bacteria	Respiration inhibition EC50 - Sludge Treatment - 1,000 mg/l - 3 h (OECD Test Guideline 209)

12.2 Persistence and degradability
No data available

12.3 Bioaccumulative potential
No data available

12.4 Mobility in soil
No data available

12.5 Results of PBT and vPvB assessment
PBT/vPvB assessment not available as chemical safety assessment not required/not conducted

12.6 Other adverse effects
An environmental hazard cannot be excluded in the event of unprofessional handling or disposal.
Toxic to aquatic life.

13. DISPOSAL CONSIDERATIONS

13.1 Waste treatment methods

Product
Offer surplus and non-recyclable solutions to a licensed disposal company.

Contaminated packaging
Dispose of as unused product.

14. TRANSPORT INFORMATION

DOT (US)
Not dangerous goods

IMDG
Not dangerous goods

IATA
Not dangerous goods

15. REGULATORY INFORMATION

SARA 302 Components
No chemicals in this material are subject to the reporting requirements of SARA Title III, Section 302.

SARA 313 Components
The following components are subject to reporting levels established by SARA Title III, Section 313:

	CAS-No.	Revision Date
Manganese	7439-96-5	2007-07-01

SARA 311/312 Hazards
Chronic Health Hazard

Massachusetts Right To Know Components

	CAS-No.	Revision Date
Manganese	7439-96-5	2007-07-01

Pennsylvania Right To Know Components

	CAS-No.	Revision Date
Manganese	7439-96-5	2007-07-01

New Jersey Right To Know Components

	CAS-No.	Revision Date
Manganese	7439-96-5	2007-07-01

California Prop. 65 Components
This product does not contain any chemicals known to State of California to cause cancer, birth defects, or any other reproductive harm.

16. OTHER INFORMATION

Full text of H-Statements referred to under sections 2 and 3.

Aquatic Acute	Acute aquatic toxicity
H401	Toxic to aquatic life.

HMIS Rating

Health hazard:	0
Chronic Health Hazard:	*
Flammability:	0
Physical Hazard	0

NFPA Rating

Health hazard:	0
Fire Hazard:	0
Reactivity Hazard:	0

Further information

Copyright 2015 Sigma-Aldrich Co. LLC. License granted to make unlimited paper copies for internal use only.
The above information is believed to be correct but does not purport to be all inclusive and shall be used only as a guide. The information in this document is based on the present state of our knowledge and is applicable to the product with regard to appropriate safety precautions. It does not represent any guarantee of the properties of the product. Sigma-Aldrich Corporation and its Affiliates shall not be held liable for any damage resulting from handling or from contact with the above product. See www.sigma-aldrich.com and/or the reverse side of invoice or packing slip for additional terms and conditions of sale.

Preparation Information

Sigma-Aldrich Corporation
Product Safety – Americas Region
1-800-521-8956

Version: 4.6 Revision Date: 10/09/2015 Print Date: 05/01/2016

Safety Data Sheet
Mercury (Metallic)

SDS Revision Date: **05/01/2015**

1. Identification

1.1. Product identifier

Product Identity	Mercury (Metallic)
Alternate Names	Quicksilver; Hydrargyrum; Liquid Silver

1.2. Relevant identified uses of the substance or mixture and uses advised against

Intended use	See Technical Data Sheet.
Application Method	See Technical Data Sheet.

1.3. Details of the supplier of the safety data sheet

Company Name	WM Mercury Waste Inc. 21211 Durand Avenue Union Grove, WI 53182
Emergency	
CHEMTREC (USA)	(800) 424-9300
Customer Service: WM Mercury Waste Inc.	(800) 741-3343

2. Hazard(s) identification

2.1. Classification of the substance or mixture

Acute Tox. 2;H330	Fatal if inhaled.
Repr. 1B;H360D	May damage the unborn child.
STOT RE 1;H372	Causes damage to organs through prolonged or repeated exposure. Specific Target Organs: (Central Nervous System)
Aquatic Chronic 1;H410	Very toxic to aquatic life with long lasting effects.

2.2. Label elements

Using the Toxicity Data listed in section 11 and 12 the product is labeled as follows.

Danger

H330 Fatal if inhaled.

H360D May damage the unborn child.

H372 Causes damage to organs through prolonged or repeated exposure.

H410 Very toxic to aquatic life with long lasting effects.

SDS Revision Date: **05/01/2015**

[Prevention]:

P201 Obtain special instructions before use.

P202 Do not handle until all safety precautions have been read and understood.

P260 Do not breathe mist / vapors / spray.

P264 Wash thoroughly after handling.

P270 Do not eat, drink or smoke when using this product.

P271 Use only outdoors or in a well-ventilated area.

P273 Avoid release to the environment.

P281 Use personal protective equipment as required.

P284 Wear respiratory protection.

[Response]:

P304+340 IF INHALED: Remove victim to fresh air and keep at rest in a position comfortable for breathing.

P308+313 IF exposed or concerned: Get medical advice / attention.

P310 Immediately call a POISON CENTER or doctor / physician.

P314 Get Medical advice / attention if you feel unwell.

P320 Specific treatment is urgent (see information on this label).

P391 Collect spillage.

[Storage]:

P403+233 Store in a well ventilated place. Keep container tightly closed.

P405 Store locked up.

[Disposal]:

P501 Dispose of contents / container in accordance with local / national regulations.

3. Composition/information on ingredients

This product contains the following substances that present a hazard within the meaning of the relevant State and Federal Hazardous Substances regulations.

Ingredient/Chemical Designations	Weight %	GHS Classification	Notes
Mercury **CAS Number: 0007439-97-6**	**100**	**Repr. 1B;H360D** **Acute tox. 2;H330** **STOT RE 1;H372** **Aquatic Acute 1;H400** **Aquatic Chronic 1;H410**	**[1][2]**

In accordance with paragraph (i) of §1910.1200, the specific chemical identity and/or exact percentage (concentration) of composition has been withheld as a trade secret.

[1] Substance classified with a health or environmental hazard.

[2] Substance with a workplace exposure limit.

[3] PBT-substance or vPvB-substance.

*The full texts of the phrases are shown in Section 16.

4. First aid measures

4.1. Description of first aid measures

General In all cases of doubt, or when symptoms persist, seek medical attention.
Never give anything by mouth to an unconscious person.

Inhalation Remove to fresh air, keep patient warm and at rest. If breathing is irregular or stopped, give artificial respiration. If unconscious place in the recovery position and obtain immediate medical attention. Give nothing by mouth.

Eyes Irrigate copiously with clean water for at least 15 minutes, holding the eyelids apart and seek medical attention.

Skin Remove contaminated clothing. Wash skin thoroughly with soap and water or use a recognized skin cleanser.

Ingestion If swallowed, wash out mouth with water, obtain immediate medical attention. Keep at rest. Do NOT induce vomiting.

4.2. Most important symptoms and effects, both acute and delayed

Overview **Eye:** Contact with eyes may cause severe irritation, and possible eye burns. Vapors may cause eye irritation.
Skin: May cause skin irritation. May be absorbed through the skin in harmful amounts. May cause skin sensitization, an allergic reaction, which becomes evident upon re-exposure to this material. Chronic exposure to mercury may cause permanent central nervous system damage, fatigue, weight loss, tremors, and personality changes.
Ingestion: May cause gastrointestinal irritation with nausea, vomiting and diarrhea. May cause effects similar to those for inhalation exposure.
Inhalation: Causes respiratory tract irritation. Inhalation of fumes may cause metal fume fever, which is characterized by flu-like symptoms with metallic taste, fever, chills, cough, weakness, chest pain, muscle pain and increased white blood cell count. May cause central nervous system effects including vertigo, anxiety, depression, muscle incoordination, and emotional instability. May cause severe respiratory tract irritation.
Chronic: Chronic exposure to mercury may cause permanent central nervous system damage, fatigue, weight loss, tremors, and personality changes.

Notes to Physician: Treat symptomatically and supportively.
Antidote: The use of Dimercaprol or BAL (British Anti-Lewisite) as a chelating agent should be determined by qualified medical personnel. The use of d-Penicillamine as a chelating agent should be determined by qualified medical personnel. See section 2 for further details.

Inhalation Fatal if inhaled.

5. Fire-fighting measures

5.1. Extinguishing media

Substance is nonflammable; use agent most appropriate to extinguish surrounding fire.

5.2. Special hazards arising from the substance or mixture

Hazardous decomposition: Mercury/mercury oxides.

Do not breathe mist / vapors / spray.

5.3. Advice for fire-fighters

As in any fire, wear a self-contained breathing apparatus in pressure-demand, MSHA/NIOSH (approved or equivalent), and full protective gear. Combustion generates toxic fumes.

ERG Guide No. 172

6. Accidental release measures

6.1. Personal precautions, protective equipment and emergency procedures

Put on appropriate personal protective equipment (see section 8).

6.2. Environmental precautions

Do not allow spills to enter drains or waterways.

Use good personal hygiene practices. Wash hands before eating, drinking, smoking or using toilet. Promptly remove soiled clothing and wash thoroughly before reuse.

6.3. Methods and material for containment and cleaning up

Vacuum or sweep up material and place into a suitable disposal container. Wear a self contained breathing apparatus and appropriate personal protection. (See Exposure Controls, Personal Protection section).

7. Handling and storage

7.1. Precautions for safe handling

Wash thoroughly after handling. Remove contaminated clothing and wash before reuse. Use with adequate ventilation. Minimize dust generation and accumulation. Avoid breathing dust, vapor, mist, or gas. Avoid contact with eyes, skin, and clothing. Keep container tightly closed. Avoid ingestion and inhalation.

See section 2 for further details. - [Prevention]:

7.2. Conditions for safe storage, including any incompatibilities

Handle containers carefully to prevent damage and spillage.

Incompatible materials: Acetylene, ammonia, boron phosphodiiodide, chlorine, chlorine dioxide, methyl azide, sodium carbide, halogens, strong oxidizers.

Store in a cool, dry, well-ventilated area away from incompatible substances. Keep away from metals. Poison room locked.

See section 2 for further details. - [Storage]:

7.3. Specific end use(s)

No data available.

SDS Revision Date: **05/01/2015**

8. Exposure controls and personal protection

8.1. Control parameters

Exposure

CAS No.	Ingredient	Source	Value
0007439-97-6	Mercury	OSHA	TWA 0.1 mg/m3
		ACGIH	Alkyl compounds TWA: 0.01 mg/m3 STEL 0.03 mg/m3 Skin Aryl compounds TWA: 0.05 mg/m3 C 0.1 mg/m3 Skin Elemental/Inorganic 0.025mg/m3 Skin
		NIOSH	No Established Limit
		Supplier	No Established Limit

Carcinogen Data

CAS No.	Ingredient	Source	Value
0007439-97-6	Mercury	OSHA	Select Carcinogen: No
		NTP	Known: No; Suspected: No
		IARC	Group 1: No; Group 2a: No; Group 2b: No; Group 3: Yes; Group 4: No;

8.2. Exposure controls

Respiratory Follow the OSHA respirator regulations found in 29CFR §1910.134 or European Standard EN 149. Always use a NIOSH or European Standard EN 149 approved respirator when necessary.

Eyes Wear appropriate protective eyeglasses or chemical safety goggles as described by OSHA eye and face protection regulations in 29 CFR 1910.133 or European Standard EN166.

Skin Wear appropriate protective clothing to prevent skin exposure. Wear appropriate gloves to prevent skin exposure.

Engineering Controls Provide adequate ventilation. Where reasonably practicable this should be achieved by the use of local exhaust ventilation and good general extraction. If these are not sufficient to maintain concentrations of particulates and any vapor below occupational exposure limits suitable respiratory protection must be worn.

Other Work Practices Use good personal hygiene practices. Wash hands before eating, drinking, smoking or using toilet. Promptly remove soiled clothing and wash thoroughly before reuse.

See section 2 for further details. - [Prevention]:

9. Physical and chemical properties

Appearance	Silver Liquid
Odor	Odorless
Odor threshold	Not Measured
pH	Not Applicable
Melting point / freezing point	-38.87 deg C

SDS Revision Date: **05/01/2015**

Initial boiling point and boiling range	356.5 deg C @ 760.00mmHg
Flash Point	Not Measured
Evaporation rate (Ether = 1)	Not Available
Flammability (solid, gas)	Not Applicable
Upper/lower flammability or explosive limits	**Lower Explosive Limit:** Not Measured **Upper Explosive Limit:** Not Measured
Vapor pressure (Pa)	0.002 mmHg @ 25C
Vapor Density	7 (Air=1)
Specific Gravity	13.5400g/cm3 (Water=1)
Solubility in Water	Insoluble
Partition coefficient n-octanol/water (Log Kow)	Not Measured
Auto-ignition temperature	Not Measured
Decomposition temperature	Not Available
Viscosity (cSt)	1.554 cP 20.00
Molecular Formula	Hg
Molecular Weight	200.59

9.2. Other information

No other relevant information.

10. Stability and reactivity

10.1. Reactivity

Hazardous Polymerization will not occur.

10.2. Chemical stability

Stable under normal circumstances.

10.3. Possibility of hazardous reactions

No data available.

10.4. Conditions to avoid

High temperatures, incompatible materials, metals.

10.5. Incompatible materials

Acetylene, ammonia, boron phosphodiiodide, chlorine, chlorine dioxide, methyl azide, sodium carbide, halogens, strong oxidizers.

10.6. Hazardous decomposition products

Mercury/mercury oxides.

11. Toxicological information

Acute toxicity

Ingredient	Oral LD50, mg/kg	Skin LD50, mg/kg	Inhalation Vapor LC50, mg/L/4hr	Inhalation Dust/Mist LC50, mg/L/4hr	Inhalation Gas LC50, ppm

SDS Revision Date: **05/01/2015**

Mercury - (7439-97-6)	37.00, Rat - Category: 2	No data available	No data available	No data available	No data available

Note: When no route specific LD50 data is available for an acute toxin, the converted acute toxicity point estimate was used in the calculation of the product's ATE (Acute Toxicity Estimate).

Classification	Category	Hazard Description
Acute toxicity (oral)	2	Fatal if swallowed.
Acute toxicity (dermal)	---	Not Applicable
Acute toxicity (inhalation)	2	Fatal if inhaled.
Skin corrosion/irritation	---	Not Applicable
Serious eye damage/irritation	---	Not Applicable
Respiratory sensitization	---	Not Applicable
Skin sensitization	---	Not Applicable
Germ cell mutagenicity	---	Not Applicable
Carcinogenicity	---	Not Applicable
Reproductive toxicity	1B	May damage the unborn child.
STOT-single exposure	---	Not Applicable
STOT-repeated exposure	1	Causes damage to organs through prolonged or repeated exposure.
Aspiration hazard	---	Not Applicable

12. Ecological information

12.1. Toxicity

Very toxic to aquatic life with long lasting effects.

No additional information provided for this product. See Section 3 for chemical specific data.

Aquatic Ecotoxicity

Ingredient	96 hr LC50 fish, mg/l	48 hr EC50 crustacea, mg/l	ErC50 algae, mg/l
Mercury - (7439-97-6)	Not Available	0.0052, Daphnia magna	Not Available

12.2. Persistence and degradability

There is no data available on the preparation itself.

12.3. Bioaccumulative potential

Not Measured

12.4. Mobility in soil

No data available.

12.5. Results of PBT and vPvB assessment

SDS Revision Date: **05/01/2015**

This product contains no PBT/vPvB chemicals.

12.6. Other adverse effects

No data available.

13. Disposal considerations

13.1. Waste treatment methods

Observe all federal, state and local regulations when disposing of this substance.

14. Transport information

	DOT (Domestic Surface Transportation)	IMO / IMDG (Ocean Transportation)	ICAO/IATA
14.1. UN number	UN2809	UN2809	UN2809
14.2. UN proper shipping name	UN2809, Mercury, 8, III	Mercury	Mercury
14.3. Transport hazard class(es)	**DOT Hazard Class:** 8 (6.1)	**IMDG:** 8 **Sub Class:** 6.1	**Air Class:** 8
14.4. Packing group	III	III	III

14.5. Environmental hazards

IMDG Marine Pollutant: Yes (Mercury)

14.6. Special precautions for user

No further information

15. Regulatory information

Regulatory Overview The regulatory data in Section 15 is not intended to be all-inclusive, only selected regulations are represented.

Toxic Substance Control Act (TSCA) All components of this material are either listed or exempt from listing on the TSCA Inventory.

WHMIS Classification D1A

US EPA Tier II Hazards

Fire: No
Sudden Release of Pressure: No
Reactive: No
Immediate (Acute): Yes
Delayed (Chronic): Yes

EPCRA 311/312 Chemicals and RQs (lbs):

Mercury (1.00)

EPCRA 302 Extremely Hazardous:

To the best of our knowledge, there are no chemicals at levels which require reporting under this statute.

SDS Revision Date: **05/01/2015**

EPCRA 313 Toxic Chemicals:

Mercury

Proposition 65 - Carcinogens (>0.0%):
To the best of our knowledge, there are no chemicals at levels which require reporting under this statute.

Proposition 65 - Developmental Toxins (>0.0%):
Mercury

Proposition 65 - Female Repro Toxins (>0.0%):
To the best of our knowledge, there are no chemicals at levels which require reporting under this statute.

Proposition 65 - Male Repro Toxins (>0.0%):
To the best of our knowledge, there are no chemicals at levels which require reporting under this statute.

New Jersey RTK Substances (>1%):

Mercury

Pennsylvania RTK Substances (>1%):

Mercury

16. Other information

The information and recommendations contained herein are based upon data believed to be correct. However, no guarantee or warranty of any kind, expressed or implied, is made with respect to the information contained herein. We accept no responsibility and disclaim all liability for any harmful effects which may be caused by exposure to our products. Customers/users of this product must comply with all applicable health and safety laws, regulations, and orders.

The full text of the phrases appearing in section 3 is:

H330 Fatal if inhaled.

H360D May damage the unborn child.

H372 Causes damage to organs through prolonged or repeated exposure.

H400 Very toxic to aquatic life.

H410 Very toxic to aquatic life with long lasting effects.

This is the first version in the GHS SDS format. Listings of changes from previous versions in other formats are not applicable.

The information above is believed to be accurate and represents the best information currently available to us. However, we make no warranty of merchantability or any other warranty, express or implied, with respect to such information, and we assume no liability resulting from its use. Users should make their own investigations to determine the suitability of the information for their particular purposes. In no way shall WM Mercury Waste Inc. be liable for any claims, losses, or damages of any third party or for lost profits or any special, indirect, incidental, consequential or exemplary damages.

End of Document

Safety Data Sheet

Material Name: Hess 10W30 Motor Oil

SDS No. 8957
US GHS

Synonyms: Valvoline Product Code 52670413

* * * Section 1 - Product and Company Identification * * *

Manufacturer Information

Hess Corporation
1 Hess Plaza
Woodbridge, NJ 07095-0961

Phone: 732-750-6000 Corporate EHS
Emergency # 800-424-9300 CHEMTREC
www.hess.com (Environment, Health, Safety Internet Website)

* * * Section 2 - Hazards Identification * * *

GHS Classification:

Skin Corrosion/Irritation – Category 2
Specific Target Organ Toxicity – Category 3 (narcosis)
Carcinogenicity - Category 1B

GHS LABEL ELEMENTS

Symbol(s)

Signal Word

WARNING

Hazard Statements

Causes skin irritation.
May cause cancer.
May cause drowsiness or dizziness.

Precautionary Statements

Prevention

Wash hands and forearms thoroughly after handling.
Wear protective gloves/protective clothing/eye protection.
Obtain special instructions before use.
Do not handle until all safety precautions have been read and understood.
Avoid breathing fume/mist/vapors/spray.
Use only outdoors or in a well-ventilated area.

Response

If on skin: Wash with plenty of soap and water. Take off contaminated clothing and wash it before reuse. If skin irritation occurs: Get medical advice/attention.
If exposed or concerned: Get medical advice/attention.
If inhaled: Remove person to fresh air and keep in a position comfortable for breathing. Call poison center or doctor if you feel unwell.

Storage

Store locked up.
Store in a well-ventilated place.
Keep container tightly closed.

Disposal

Dispose of contents/container in accordance with local/regional/national/international regulations.

* * * Section 3 - Composition / Information on Ingredients * * *

CAS #	Component	Percent
64742-65-0	Petroleum distillates, solvent dewaxed heavy paraffinic	83-93

Petroleum-based lubricating oil with detergent/dispersant engine oil package with zinc compounds.

* * * Section 4 - First Aid Measures * * *

First Aid: Eyes

If symptoms develop, move individual away from exposure and into fresh air. Flush eyes gently with water while holding eyelids apart. If symptoms persist or there is visual difficulty, seek medical attention.

First Aid: Skin

Remove contaminated clothing. Wash exposed area with soap and water. If symptoms persist, seek medical attention. Launder clothing before reuse.

First Aid: Ingestion

Seek medical attention. If individual is drowsy or unconscious, do not give anything by mouth; place individual on the left side with the head down. Contact a physician, medical facility, or poison control center for advice about whether to induce vomiting. If possible, do not leave individual unattended.

First Aid: Inhalation

Remove person to fresh air. If person is not breathing provide artificial respiration. If necessary, provide additional oxygen once breathing is restored if trained to do so. Seek medical attention immediately.

First Aid: Notes to Physician

Acute aspiration of large amounts of oil-laden material may produce a serious aspiration hazard. Patients who aspirate these oils should be followed for the development of long-term sequelae. Repeated aspiration of mineral oil can produce chronic inflammation of the lungs (i.e. lipoid pneumonia) that may progress to pulmonary fibrosis. Symptoms are often subtle and radiological changes appear worse than clinical abnormalities. Occasionally, persistent cough, irritation of the upper respiratory tract, shortness of breath with exertion, fever, and bloody sputum occur. Inhalation exposure to oil mists below current workplace exposure limits is unlikely to cause pulmonary abnormalities. Preexisting disorders of the following organs (or organ systems) may be aggravated by exposure to this material: skin.

* * * Section 5 - Fire Fighting Measures * * *

General Fire Hazards

See Section 9 for Flammability Properties.
Never use welding or cutting torch on or near drum (even empty) because product (even just residue) can ignite explosively. No special fire hazards are known to be associated with this product. Dense smoke may be generated while burning.

Hazardous Combustion Products

May form: carbon dioxide and carbon monoxide, oxides of sulfur, nitrogen and phosphorous, various hydrocarbons.

Extinguishing Media

SMALL FIRES: Any extinguisher suitable for Class B fires, dry chemical, CO2, water spray, fire fighting foam, or gaseous extinguishing agent.

LARGE FIRES: Water spray, fog or fire fighting foam. Water may be ineffective for fighting the fire, but may be used to cool fire-exposed containers.

Unsuitable Extinguishing Media

None

Fire Fighting Equipment/Instructions

Small fires in the incipient (beginning) stage may typically be extinguished using handheld portable fire extinguishers and other fire fighting equipment. Firefighting activities that may result in potential exposure to high heat, smoke or toxic by-products of combustion should require NIOSH/MSHA- approved pressure-demand self-contained breathing apparatus with full facepiece and full protective clothing. Isolate area around container involved in fire. Cool tanks, shells, and containers exposed to fire and excessive heat with water. For massive fires the use of unmanned hose holders or monitor nozzles may be advantageous to further minimize personnel exposure. Major fires may require withdrawal, allowing the tank to burn. Large storage tank fires typically require specially trained personnel and equipment to extinguish the fire, often including the need for properly applied fire fighting foam.

* * * Section 6 - Accidental Release Measures * * *

Recovery and Neutralization

Carefully contain and stop the source of the spill, if safe to do so.

Materials and Methods for Clean-Up

Take up with sand or other oil absorbing materials. Carefully shovel, scoop or sweep up into a waste container for reclamation or disposal. Caution, flammable vapors may accumulate in closed containers.

SMALL SPILL: Absorb liquid on vermiculite, floor absorbent or other absorbent material. Persons not wearing proper personal protective equipment should be excluded from area of spill.

LARGE SPILL: Prevent run-off to sewers, streams, or other bodies of water. If run-off occurs, notify authorities as required, that a spill has occurred. Persons not wearing proper personal protective equipment should be excluded from area of spill until clean-up has been completed.

Emergency Measures

Evacuate nonessential personnel and remove or secure all ignition sources. Consider wind direction; stay upwind and uphill, if possible. Evaluate the direction of product travel, diking, sewers, etc. to confirm spill areas. Spills may infiltrate subsurface soil and groundwater; professional assistance may be necessary to determine the extent of subsurface impact.

Personal Precautions and Protective Equipment

Response and clean-up crews must be properly trained and must utilize proper protective equipment (see Section 8).

Environmental Precautions

Protect bodies of water by diking, absorbents, or absorbent boom, if possible. Do not flush down sewer or drainage systems, unless system is designed and permitted to handle such material. The use of fire fighting foam may be useful in certain situations to reduce vapors. The proper use of water spray may effectively disperse product vapors or the liquid itself, preventing contact with ignition sources or areas/equipment that require protection.

Prevention of Secondary Hazards

None

* * * Section 7 - Handling and Storage * * *

Handling Procedures

Handle as a combustible liquid. Keep away from heat, sparks, and open flame! Electrical equipment should be approved for classified area. Bond and ground containers during product transfer to reduce the possibility of static-initiated fire or explosion.

Special slow load procedures for "switch loading" must be followed to avoid the static ignition hazard that can exist when higher flash point material (such as fuel oil) is loaded into tanks previously containing low flash point products (such as this product) - see API Publication 2003, "Protection Against Ignitions Arising Out Of Static, Lightning and Stray Currents.

Storage Procedures

Keep away from flame, sparks, excessive temperatures and open flame. Use approved vented containers. Keep containers closed and clearly labeled. Empty product containers or vessels may contain explosive vapors. Do not pressurize, cut, heat, weld or expose such containers to sources of ignition.

Store in a well-ventilated area. This storage area should comply with NFPA 30 "Flammable and Combustible Liquid Code". Avoid storage near incompatible materials. The cleaning of tanks previously containing this product should follow API Recommended Practice (RP) 2013 "Cleaning Mobile Tanks In Flammable and Combustible Liquid Service" and API RP 2015 "Cleaning Petroleum Storage Tanks."

Incompatibilities

Avoid contact with: acids, halogens, strong oxidizing agents.

* * * Section 8 - Exposure Controls / Personal Protection * * *

Component Exposure Limits

ACGIH, OSHA, and NIOSH have not developed exposure limits for any of this product's components.

Engineering Measures

Use adequate ventilation to keep vapor concentrations of this product below occupational exposure and flammability limits, particularly in confined spaces.

Personal Protective Equipment: Respiratory

A NIOSH/MSHA-approved air-purifying respirator with organic vapor cartridges or canister may be permissible under certain circumstances where airborne concentrations are or may be expected to exceed exposure limits or for odor or irritation. Protection provided by air-purifying respirators is limited.

Use a positive pressure, air-supplied respirator if there is a potential for uncontrolled release, exposure levels are not known, in oxygen-deficient atmospheres, or any other circumstance where an air-purifying respirator may not provide adequate protection.

Personal Protective Equipment: Hands

Not normally required. However, wear resistant gloves such as nitrile rubber to prevent irritation which may result from prolonged or repeated skin contact with product.

Personal Protective Equipment: Eyes

Safety glasses or goggles are recommended where there is a possibility of splashing or spraying.

Personal Protective Equipment: Skin and Body

To prevent repeated or prolonged skin contact, wear impervious clothing and boots. Wear normal work clothing covering arms and legs.

Hygiene Measures

Emergency eye wash capability should be available in the near proximity to operations presenting a potential splash exposure. Use good personal hygiene practices. Avoid repeated and/or prolonged skin exposure. Wash hands before eating, drinking, smoking, or using toilet facilities. Do not use as a cleaning solvent on the skin. Do not use solvents or harsh abrasive skin cleaners for washing this product from exposed skin areas. Waterless hand cleaners are effective. Promptly remove contaminated clothing and launder before reuse. Use care when laundering to prevent the formation of flammable vapors which could ignite via washer or dryer. Consider the need to discard contaminated leather shoes and gloves.

* * * Section 9 - Physical & Chemical Properties * * *

Appearance:	Dry, clear and bright	**Odor:**	None
Physical State:	Liquid	**pH:**	ND
Vapor Pressure:	ND	**Vapor Density:**	ND
Boiling Point:	>425 °F (218.3°C) @ 760.00 mmHg	**Melting Point:**	ND
Solubility (H2O):	Negligible	**Specific Gravity:**	0.881 @ 60°F (16°C)
Evaporation Rate:	Slower than ethyl ether	**VOC:**	ND
Viscosity:	<= 3300.0 cps @ -20°C; 10.0 - 11.0 cst @ 100°C	**Octanol/H2O Coeff.:**	ND
Flash Point:	430 °F (221.1 °C)	**Flash Point Method:**	COC
Upper Flammability Limit (UFL):	ND	**Lower Flammability Limit (LFL):**	ND
Burning Rate:	ND	**Auto Ignition:**	ND

* * * Section 10 - Chemical Stability & Reactivity Information * * *

Chemical Stability

This is a stable material.

Hazardous Reaction Potential

Will not occur.

Conditions to Avoid

None

Incompatible Products

Avoid contact with: acids, halogens, strong oxidizing agents.

Hazardous Decomposition Products

May form: aldehydes, carbon dioxide and carbon monoxide, hydrogen sulfide, oxides of sulfur, nitrogen and phosphorus, toxic fumes, various hydrocarbons.

* * * Section 11 - Toxicological Information * * *

Acute Toxicity

A: General Product Information

Harmful if large amounts are swallowed.

B: Component Analysis - LD50/LC50

Petroleum distillates, solvent dewaxed heavy paraffinic (64742-65-0)

Inhalation LC50 Rat >4.7 mg/L 4 h; Oral LD50 Rat >5000 mg/kg; Dermal LD50 Rabbit >5000 mg/kg

Potential Health Effects: Skin Corrosion Property/Stimulativeness

May cause mild skin irritation. Prolonged or repeated contact may dry the skin. Symptoms include redness, burning, drying and cracking of the skin, and skin burns. Additional symptoms of skin contact include: acne. Passage of this material into the body through the skin is possible, but it is unlikely that this would result in harmful effects during safe handling and use.

Potential Health Effects: Eye Critical Damage/ Stimulativeness

May cause mild eye irritation. Symptoms include stinging, tearing, and redness.

Potential Health Effects: Ingestion

Swallowing small amounts of this material during normal handling is not likely to cause harmful effects. Swallowing large amounts may be harmful.

Potential Health Effects: Inhalation

It is possible to breathe this material under certain conditions of handling and use (for example, during heating, spraying, or stirring). Breathing small amounts of this material during normal handling is not likely to cause harmful effects. Breathing large amounts may be harmful. Symptoms usually occur at air concentrations higher than the recommended exposure limits.

Respiratory Organs Sensitization/Skin Sensitization

This product is not reported to have any skin sensitization effects.

Generative Cell Mutagenicity

This product is not reported to have any mutagenic effects.

Carcinogenicity

A: General Product Information

May cause cancer.

Used motor oil has been shown to cause skin cancer in laboratory animal continually exposed by repeated applications.

B: Component Carcinogenicity

None of this product's components are listed by ACGIH, IARC, OSHA, NIOSH, or NTP.

Reproductive Toxicity

This product is not reported to have any reproductive toxicity effects.

Specified Target Organ General Toxicity: Single Exposure

This product is not reported to have any specific target organ general toxicity single exposure effects.

Specified Target Organ General Toxicity: Repeated Exposure

This product is not reported to have any specific target organ general toxicity repeat exposure effects.

Aspiration Respiratory Organs Hazard

Acute aspiration of large amounts of oil-laden material may produce a serious aspiration hazard.

* * * Section 12 - Ecological Information * * *

Ecotoxicity

A: General Product Information

Keep out of sewers, drainage areas and waterways. Report spills and releases, as applicable, under Federal and State regulations.

B: Component Analysis - Ecotoxicity - Aquatic Toxicity

Petroleum distillates, solvent dewaxed heavy paraffinic (64742-65-0)

Test & Species		Conditions
96 Hr LC50 Oncorhynchus mykiss	>5000 mg/L	
48 Hr EC50 Daphnia magna	>1000 mg/L	

Persistence/Degradability

No information available.

Bioaccumulation

No information available.

Mobility in Soil

No information available.

* * * Section 13 - Disposal Considerations * * *

Waste Disposal Instructions

See Section 7 for Handling Procedures. See Section 8 for Personal Protective Equipment recommendations.

Disposal of Contaminated Containers or Packaging

Dispose of contents/container in accordance with local/regional/national/international regulations.

* * * Section 14 - Transportation Information * * *

DOT Information

Shipping Name: Not Regulated

* * * Section 15 - Regulatory Information * * *

Regulatory Information

Component Analysis

None of this products components are listed under SARA Section 302 (40 CFR 355 Appendix A), SARA Section 313 (40 CFR 372.65), or CERCLA (40 CFR 302.4).

SARA Section 311/312 – Hazard Classes

Acute Health	Chronic Health	Fire	Sudden Release of Pressure	Reactive
X	X	--	--	--

SARA SECTION 313 - SUPPLIER NOTIFICATION

ZINC C1-C14 ALKYLDITHIOPHOSPHATE (CAS No. 68649-42-3)

State Regulations

Component Analysis - State

None of this product's components are listed on the state lists from CA, MA, MN, NJ, PA, or RI.

Component Analysis - WHMIS IDL

No components are listed in the WHMIS IDL.

Additional Regulatory Information

Component Analysis - Inventory

Component	CAS #	TSCA	CAN	EEC
Petroleum distillates, solvent dewaxed heavy paraffinic	64742-65-0	Yes	DSL	EINECS

* * * Section 16 - Other Information * * *

NFPA® Hazard Rating

Health	1
Fire	1
Reactivity	0

HMIS® Hazard Rating

Health	1*	Slight
Fire	1	Slight
Physical	0	Minimal
		*Chronic

Key/Legend

EPA = Environmental Protection Agency; TSCA = Toxic Substance Control Act; ACGIH = American Conference of Governmental Industrial Hygienists; IARC = International Agency for Research on Cancer; NIOSH = National Institute for Occupational Safety and Health; NTP = National Toxicology Program; OSHA = Occupational Safety and Health Administration., NJTSR = New Jersey Trade Secret Registry.

Literature References

None

Other Information

Information presented herein has been compiled from sources considered to be dependable, and is accurate and reliable to the best of our knowledge and belief, but is not guaranteed to be so. Since conditions of use are beyond our control, we make no warranties, expressed or implied, except those that may be contained in our written contract of sale or acknowledgment.

Vendor assumes no responsibility for injury to vendee or third persons proximately caused by the material if reasonable safety procedures are not adhered to as stipulated in the data sheet. Additionally, vendor assumes no responsibility for injury to vendee or third persons proximately caused by abnormal use of the material, even if reasonable safety procedures are followed. Furthermore, vendee assumes the risk in their use of the material.

End of Sheet

SAFETY DATA SHEET

Version 5.5
Revision Date 05/27/2016
Print Date 07/13/2017

1. PRODUCT AND COMPANY IDENTIFICATION

1.1 Product identifiers

Product name : Methyl *tert*-butyl ether

Product Number : 48027
Brand : Supelco
Index-No. : 603-181-00-X

CAS-No. : 1634-04-4

1.2 Relevant identified uses of the substance or mixture and uses advised against

Identified uses : Laboratory chemicals, Synthesis of substances

1.3 Details of the supplier of the safety data sheet

Company : Sigma-Aldrich
3050 Spruce Street
SAINT LOUIS MO 63103
USA

Telephone : +1 800-325-5832
Fax : +1 800-325-5052

1.4 Emergency telephone number

Emergency Phone # : +1-703-527-3887 (CHEMTREC)

2. HAZARDS IDENTIFICATION

2.1 Classification of the substance or mixture

GHS Classification in accordance with 29 CFR 1910 (OSHA HCS)
Flammable liquids (Category 2), H225
Skin irritation (Category 2), H315

For the full text of the H-Statements mentioned in this Section, see Section 16.

2.2 GHS Label elements, including precautionary statements

Pictogram

Signal word Danger

Hazard statement(s)
H225 Highly flammable liquid and vapour.
H315 Causes skin irritation.

Precautionary statement(s)
P210 Keep away from heat/sparks/open flames/hot surfaces. No smoking.
P233 Keep container tightly closed.
P240 Ground/bond container and receiving equipment.
P241 Use explosion-proof electrical/ ventilating/ lighting/ equipment.
P242 Use only non-sparking tools.
P243 Take precautionary measures against static discharge.
P264 Wash skin thoroughly after handling.
P280 Wear protective gloves/ eye protection/ face protection.

P303 + P361 + P353	IF ON SKIN (or hair): Remove/ Take off immediately all contaminated clothing. Rinse skin with water/ shower.
P332 + P313	If skin irritation occurs: Get medical advice/ attention.
P362	Take off contaminated clothing and wash before reuse.
P370 + P378	In case of fire: Use dry sand, dry chemical or alcohol-resistant foam for extinction.
P403 + P235	Store in a well-ventilated place. Keep cool.
P501	Dispose of contents/ container to an approved waste disposal plant.

2.3 Hazards not otherwise classified (HNOC) or not covered by GHS - none

3. COMPOSITION/INFORMATION ON INGREDIENTS

3.1 Substances

Synonyms : MTBE
tert-Butyl methyl ether
Methyl *tert*-butyl ether

Formula : $C_5H_{12}O$
Molecular weight : 88.15 g/mol
CAS-No. : 1634-04-4
EC-No. : 216-653-1
Index-No. : 603-181-00-X
Registration number : 01-2119452786-27-XXXX

Hazardous components

Component	Classification	Concentration
tert-Butyl methyl ether		
	Flam. Liq. 2; Skin Irrit. 2; H225, H315	<= 100 %

For the full text of the H-Statements mentioned in this Section, see Section 16.

4. FIRST AID MEASURES

4.1 Description of first aid measures

General advice
Consult a physician. Show this safety data sheet to the doctor in attendance.Move out of dangerous area.

If inhaled
If breathed in, move person into fresh air. If not breathing, give artificial respiration. Consult a physician.

In case of skin contact
Wash off with soap and plenty of water. Consult a physician.

In case of eye contact
Flush eyes with water as a precaution.

If swallowed
Do NOT induce vomiting. Never give anything by mouth to an unconscious person. Rinse mouth with water. Consult a physician.

4.2 Most important symptoms and effects, both acute and delayed
The most important known symptoms and effects are described in the labelling (see section 2.2) and/or in section 11

4.3 Indication of any immediate medical attention and special treatment needed
No data available

5. FIREFIGHTING MEASURES

5.1 Extinguishing media

Suitable extinguishing media
Use water spray, alcohol-resistant foam, dry chemical or carbon dioxide.

5.2 Special hazards arising from the substance or mixture
No data available

5.3 Advice for firefighters
Wear self-contained breathing apparatus for firefighting if necessary.

5.4 Further information
Use water spray to cool unopened containers.

6. ACCIDENTAL RELEASE MEASURES

6.1 Personal precautions, protective equipment and emergency procedures
Use personal protective equipment. Avoid breathing vapours, mist or gas. Ensure adequate ventilation. Remove all sources of ignition. Evacuate personnel to safe areas. Beware of vapours accumulating to form explosive concentrations. Vapours can accumulate in low areas.
For personal protection see section 8.

6.2 Environmental precautions
Prevent further leakage or spillage if safe to do so. Do not let product enter drains.

6.3 Methods and materials for containment and cleaning up
Contain spillage, and then collect with an electrically protected vacuum cleaner or by wet-brushing and place in container for disposal according to local regulations (see section 13).

6.4 Reference to other sections
For disposal see section 13.

7. HANDLING AND STORAGE

7.1 Precautions for safe handling
Avoid contact with skin and eyes. Avoid inhalation of vapour or mist.
Use explosion-proof equipment.Keep away from sources of ignition - No smoking.Take measures to prevent the build up of electrostatic charge.
For precautions see section 2.2.

7.2 Conditions for safe storage, including any incompatibilities
Keep container tightly closed in a dry and well-ventilated place. Containers which are opened must be carefully resealed and kept upright to prevent leakage.
Storage class (TRGS 510): Flammable liquids

7.3 Specific end use(s)
Apart from the uses mentioned in section 1.2 no other specific uses are stipulated

8. EXPOSURE CONTROLS/PERSONAL PROTECTION

8.1 Control parameters

Components with workplace control parameters

Component	CAS-No.	Value	Control parameters	Basis
tert-Butyl methyl ether	1634-04-4	TWA	50.000000 ppm	USA. ACGIH Threshold Limit Values (TLV)
	Remarks	Upper Respiratory Tract irritation Kidney damage Confirmed animal carcinogen with unknown relevance to humans		
		PEL	40 ppm 144 mg/m3	California permissible exposure limits for chemical contaminants (Title 8, Article 107)

8.2 Exposure controls

Appropriate engineering controls
Handle in accordance with good industrial hygiene and safety practice. Wash hands before breaks and at the end of workday.

Personal protective equipment

Eye/face protection
Face shield and safety glasses Use equipment for eye protection tested and approved under appropriate government standards such as NIOSH (US) or EN 166(EU).

Skin protection
Handle with gloves. Gloves must be inspected prior to use. Use proper glove removal technique (without touching glove's outer surface) to avoid skin contact with this product. Dispose of contaminated gloves after use in accordance with applicable laws and good laboratory practices. Wash and dry hands.

Splash contact
Material: Nitrile rubber
Minimum layer thickness: 0.4 mm
Break through time: 230 min
Material tested:Camatril® (KCL 730 / Aldrich Z677442, Size M)

data source: KCL GmbH, D-36124 Eichenzell, phone +49 (0)6659 87300, e-mail sales@kcl.de, test method: EN374
If used in solution, or mixed with other substances, and under conditions which differ from EN 374, contact the supplier of the CE approved gloves. This recommendation is advisory only and must be evaluated by an industrial hygienist and safety officer familiar with the specific situation of anticipated use by our customers. It should not be construed as offering an approval for any specific use scenario.

Body Protection
Impervious clothing, Flame retardant antistatic protective clothing., The type of protective equipment must be selected according to the concentration and amount of the dangerous substance at the specific workplace.

Respiratory protection
Where risk assessment shows air-purifying respirators are appropriate use a full-face respirator with multi-purpose combination (US) or type AXBEK (EN 14387) respirator cartridges as a backup to engineering controls. If the respirator is the sole means of protection, use a full-face supplied air respirator. Use respirators and components tested and approved under appropriate government standards such as NIOSH (US) or CEN (EU).

Control of environmental exposure
Prevent further leakage or spillage if safe to do so. Do not let product enter drains.

9. PHYSICAL AND CHEMICAL PROPERTIES

9.1 Information on basic physical and chemical properties

a)	Appearance	Form: liquid
b)	Odour	No data available
c)	Odour Threshold	No data available
d)	pH	No data available
e)	Melting point/freezing point	Melting point/range: -108.6 °C (-163.5 °F)
f)	Initial boiling point and boiling range	55 - 56 °C (131 - 133 °F) - lit.
g)	Flash point	-33.0 °C (-27.4 °F) - closed cup
h)	Evaporation rate	No data available
i)	Flammability (solid, gas)	No data available
j)	Upper/lower flammability or explosive limits	Upper explosion limit: 15.1 %(V) Lower explosion limit: 1.6 %(V)
k)	Vapour pressure	1,018.7 hPa (764.1 mmHg) at 55.0 °C (131.0 °F) 279.2 hPa (209.4 mmHg) at 20.0 °C (68.0 °F)
l)	Vapour density	No data available
m)	Relative density	0.74 g/cm3 at 25 °C (77 °F)

n)	Water solubility	42 g/l at 20 °C (68 °F) - OECD Test Guideline 105
o)	Partition coefficient: n-octanol/water	log Pow: 1.06
p)	Auto-ignition temperature	374.0 °C (705.2 °F)
q)	Decomposition temperature	No data available
r)	Viscosity	0.464 mm2/s at 20 °C (68 °F) - 0.409 mm2/s at 40 °C (104 °F) -
s)	Explosive properties	No data available
t)	Oxidizing properties	No data available

9.2 Other safety information
No data available

10. STABILITY AND REACTIVITY

10.1 Reactivity
No data available

10.2 Chemical stability
Stable under recommended storage conditions.

10.3 Possibility of hazardous reactions
Vapours may form explosive mixture with air.

10.4 Conditions to avoid
Heat, flames and sparks.

10.5 Incompatible materials
Oxidizing agents, Strong acids

10.6 Hazardous decomposition products
Hazardous decomposition products formed under fire conditions. - Carbon oxides
Other decomposition products - No data available
In the event of fire: see section 5

11. TOXICOLOGICAL INFORMATION

11.1 Information on toxicological effects

Acute toxicity
LD50 Oral - Rat - 4,000 mg/kg

LC50 Inhalation - Rat - 4 h - 23576 ppm

Dermal: No data available

No data available

Skin corrosion/irritation
Skin - Rabbit
Result: Skin irritation

Serious eye damage/eye irritation
Eyes - Rabbit
Result: No eye irritation

Respiratory or skin sensitisation
Will not occur

Germ cell mutagenicity
No data available

Carcinogenicity

Reproductive toxicity
No data available

No data available

Specific target organ toxicity - single exposure
No data available

Specific target organ toxicity - repeated exposure
No data available

Aspiration hazard
No data available

Additional Information
RTECS: KN5250000

Nausea, Vomiting, Dizziness, Central nervous system depression, Aspiration or inhalation may cause chemical pneumonitis., MTBE (methyl-tert-butyl ether) is reported to metabolize to tert-butyl alcohol and formaldehyde by microsomal demethylation, MTBE (methyl-tert-butyl ether) should be considered a "potential human carcinogen" due to an increase in leydig interstitial cell tumors of testes in male rats and an increase in lymphomas, leukemias, and uterine sarcomas in female rats., In another unpublished study MTBE was shown to be carcinogenic due to "increased incidence of a rare type of kidney tumor" in male rats and an "increase in the incidence of hepatocellular adenomas" in female mice., To the best of our knowledge, the chemical, physical, and toxicological properties have not been thoroughly investigated.

Central nervous system -

12. ECOLOGICAL INFORMATION

12.1 Toxicity

Toxicity to fish	LC50 - Pimephales promelas (fathead minnow) - 672.00 mg/l - 96 h
	LC50 - other fish - > 1,000.00 mg/l - 96 h
Toxicity to daphnia and other aquatic invertebrates	EC50 - Daphnia magna (Water flea) - 472 mg/l - 48 h
Toxicity to algae	EC50 - Pseudokirchneriella subcapitata (green algae) - 491 mg/l - 96 h

12.2 Persistence and degradability

Biodegradability	Result: 0 % - Not readily biodegradable. (OECD Test Guideline 301D)

12.3 Bioaccumulative potential
No data available

12.4 Mobility in soil
No data available

12.5 Results of PBT and vPvB assessment
PBT/vPvB assessment not available as chemical safety assessment not required/not conducted

12.6 Other adverse effects

No data available

13. DISPOSAL CONSIDERATIONS

13.1 Waste treatment methods

Product
Burn in a chemical incinerator equipped with an afterburner and scrubber but exert extra care in igniting as this material is highly flammable. Offer surplus and non-recyclable solutions to a licensed disposal company. Contact a licensed professional waste disposal service to dispose of this material.

Contaminated packaging
Dispose of as unused product.

14. TRANSPORT INFORMATION

DOT (US)
UN number: 2398 Class: 3 Packing group: II
Proper shipping name: Methyl tert-butyl ether
Reportable Quantity (RQ): 1000 lbs

Poison Inhalation Hazard: No

IMDG
UN number: 2398 Class: 3 Packing group: II EMS-No: F-E, S-D
Proper shipping name: METHYL tert-BUTYL ETHER

IATA
UN number: 2398 Class: 3 Packing group: II
Proper shipping name: Methyl tert-butyl ether

15. REGULATORY INFORMATION

SARA 302 Components
No chemicals in this material are subject to the reporting requirements of SARA Title III, Section 302.

SARA 313 Components
The following components are subject to reporting levels established by SARA Title III, Section 313:

	CAS-No.	Revision Date
tert-Butyl methyl ether	1634-04-4	2007-07-01

SARA 311/312 Hazards
Fire Hazard, Acute Health Hazard

Massachusetts Right To Know Components

	CAS-No.	Revision Date
tert-Butyl methyl ether	1634-04-4	2007-07-01

Pennsylvania Right To Know Components

	CAS-No.	Revision Date
tert-Butyl methyl ether	1634-04-4	2007-07-01

New Jersey Right To Know Components

	CAS-No.	Revision Date
tert-Butyl methyl ether	1634-04-4	2007-07-01

16. OTHER INFORMATION

Full text of H-Statements referred to under sections 2 and 3.

Flam. Liq.	Flammable liquids
H225	Highly flammable liquid and vapour.
H315	Causes skin irritation.
Skin Irrit.	Skin irritation

HMIS Rating

Health hazard:	2
Chronic Health Hazard:	
Flammability:	3
Physical Hazard	0

NFPA Rating
Health hazard: 2

Fire Hazard:	3
Reactivity Hazard:	0

Further information

Copyright 2016 Sigma-Aldrich Co. LLC. License granted to make unlimited paper copies for internal use only.
The above information is believed to be correct but does not purport to be all inclusive and shall be used only as a guide. The information in this document is based on the present state of our knowledge and is applicable to the product with regard to appropriate safety precautions. It does not represent any guarantee of the properties of the product. Sigma-Aldrich Corporation and its Affiliates shall not be held liable for any damage resulting from handling or from contact with the above product. See www.sigma-aldrich.com and/or the reverse side of invoice or packing slip for additional terms and conditions of sale.

Preparation Information

Sigma-Aldrich Corporation
Product Safety – Americas Region
1-800-521-8956

Version: 5.5 Revision Date: 05/27/2016 Print Date: 07/13/2017

Fisher Scientific

Part of Thermo Fisher Scientific

SAFETY DATA SHEET

Creation Date 27-Sep-2010 **Revision Date** 12-Oct-2015 **Revision Number** 3

1. Identification

Product Name **Naphthalene**

Cat No. : **N7-500**

Synonyms Tar camphor; Naphthalin; Coal tar camphor

Recommended Use Laboratory chemicals.

Uses advised against No Information available

Details of the supplier of the safety data sheet

Emergency Telephone Number
Chemtrec US: (800) 424-9300
Chemtrec EU: 001 (202) 483-7616

2. Hazard(s) identification

Classification
This chemical is considered hazardous by the 2012 OSHA Hazard Communication Standard (29 CFR 1910.1200)

Flammable solids	Category 2
Acute oral toxicity	Category 4
Carcinogenicity	Category 1B
Target Organs - Liver, Kidney.	

Label Elements

Signal Word
Danger

Hazard Statements
Flammable solid
Harmful if swallowed
May cause cancer

Precautionary Statements
Prevention

Obtain special instructions before use
Do not handle until all safety precautions have been read and understood
Use personal protective equipment as required
Wash face, hands and any exposed skin thoroughly after handling
Do not eat, drink or smoke when using this product
Do not breathe dust/fume/gas/mist/vapors/spray
Use only outdoors or in a well-ventilated area
Keep away from heat/sparks/open flames/hot surfaces. - No smoking
Ground/bond container and receiving equipment
Use explosion-proof electrical/ventilating/lighting/equipment

Response

IF exposed or concerned: Get medical attention/advice

Inhalation

IF INHALED: Remove victim to fresh air and keep at rest in a position comfortable for breathing

Ingestion

IF SWALLOWED: Call a POISON CENTER or doctor/physician if you feel unwell
Rinse mouth

Fire

In case of fire: Use CO2, dry chemical, or foam for extinction

Storage

Store locked up
Store in a well-ventilated place. Keep container tightly closed

Disposal

Dispose of contents/container to an approved waste disposal plant

Hazards not otherwise classified (HNOC)

Very toxic to aquatic life with long lasting effects
WARNING! This product contains a chemical known in the State of California to cause cancer.

3. Composition / information on ingredients

Component	CAS-No	Weight %
Naphthalene	91-20-3	>95

4. First-aid measures

General Advice If symptoms persist, call a physician.

Eye Contact Rinse immediately with plenty of water, also under the eyelids, for at least 15 minutes. Obtain medical attention.

Skin Contact Wash off immediately with plenty of water for at least 15 minutes. Obtain medical attention.

Inhalation Move to fresh air. If breathing is difficult, give oxygen. Obtain medical attention.

Ingestion Clean mouth with water and drink afterwards plenty of water. Get medical attention if symptoms occur.

Most important symptoms/effects . Symptoms of overexposure may be headache, dizziness, tiredness, nausea and vomiting
Notes to Physician Treat symptomatically

5. Fire-fighting measures

Suitable Extinguishing Media Use water spray, alcohol-resistant foam, dry chemical or carbon dioxide. Cool closed containers exposed to fire with water spray.

Unsuitable Extinguishing Media No information available

Flash Point 78 °C / 172.4 °F
Method - No information available

Autoignition Temperature Not applicable 526 °C / 978.8 °F
Explosion Limits
Upper 5.9 vol %
Lower 0.9 vol %
Sensitivity to Mechanical Impact No information available
Sensitivity to Static Discharge No information available

Specific Hazards Arising from the Chemical
Combustible material. Containers may explode when heated. Do not allow run-off from fire fighting to enter drains or water courses.

Hazardous Combustion Products
Carbon monoxide (CO) Carbon dioxide (CO_2)
Protective Equipment and Precautions for Firefighters
As in any fire, wear self-contained breathing apparatus pressure-demand, MSHA/NIOSH (approved or equivalent) and full protective gear.

NFPA

Health	Flammability	Instability	Physical hazards
2	2	0	N/A

6. Accidental release measures

Personal Precautions Use personal protective equipment. Ensure adequate ventilation. Avoid dust formation. Remove all sources of ignition. Take precautionary measures against static discharges.

Environmental Precautions Do not flush into surface water or sanitary sewer system. Do not allow material to contaminate ground water system. Prevent product from entering drains. Local authorities should be advised if significant spillages cannot be contained.

Methods for Containment and Clean Up Sweep up or vacuum up spillage and collect in suitable container for disposal. Keep in suitable, closed containers for disposal. Remove all sources of ignition.

7. Handling and storage

Handling Wear personal protective equipment. Ensure adequate ventilation. Avoid ingestion and inhalation. Do not get in eyes, on skin, or on clothing. Avoid dust formation. Keep away from open flames, hot surfaces and sources of ignition.

Storage Keep containers tightly closed in a dry, cool and well-ventilated place. Keep away from heat and sources of ignition.

8. Exposure controls / personal protection

Exposure Guidelines

Component	ACGIH TLV	OSHA PEL	NIOSH IDLH
Naphthalene	TWA: 10 ppm Skin	(Vacated) TWA: 10 ppm (Vacated) TWA: 50 mg/m³ (Vacated) STEL: 15 ppm (Vacated) STEL: 75 mg/m³ TWA: 10 ppm TWA: 50 mg/m³	IDLH: 250 ppm TWA: 10 ppm TWA: 50 mg/m³ STEL: 15 ppm STEL: 75 mg/m³

Component	Quebec	Mexico OEL (TWA)	Ontario TWAEV
Naphthalene	TWA: 10 ppm TWA: 52 mg/m³ STEL: 15 ppm STEL: 79 mg/m³	TWA: 10 ppm TWA: 50 mg/m³ STEL: 15 ppm STEL: 75 mg/m³	TWA: 10 ppm STEL: 15 ppm Skin

Legend

ACGIH - American Conference of Governmental Industrial Hygienists
OSHA - Occupational Safety and Health Administration
NIOSH IDLH: The National Institute for Occupational Safety and Health Immediately Dangerous to Life or Health

Engineering Measures Use only under a chemical fume hood. Ensure that eyewash stations and safety showers are close to the workstation location. Use explosion-proof electrical/ventilating/lighting/equipment. Ensure adequate ventilation, especially in confined areas.

Personal Protective Equipment

Eye/face Protection Wear appropriate protective eyeglasses or chemical safety goggles as described by OSHA's eye and face protection regulations in 29 CFR 1910.133 or European Standard EN166.

Skin and body protection Long sleeved clothing.

Respiratory Protection Follow the OSHA respirator regulations found in 29 CFR 1910.134 or European Standard EN 149. Use a NIOSH/MSHA or European Standard EN 149 approved respirator if exposure limits are exceeded or if irritation or other symptoms are experienced.

Hygiene Measures Handle in accordance with good industrial hygiene and safety practice.

9. Physical and chemical properties

Physical State	Solid
Appearance	White
Odor	Characteristic
Odor Threshold	No information available
pH	No information available
Melting Point/Range	79 - 82 °C / 174.2 - 179.6 °F
Boiling Point/Range	218 °C / 424.4 °F
Flash Point	78 °C / 172.4 °F
Evaporation Rate	Not applicable
Flammability (solid,gas)	No information available
Flammability or explosive limits	
Upper	5.9 vol %
Lower	0.9 vol %
Vapor Pressure	0.08 mbar @ 20 °C
Vapor Density	Not applicable
Specific Gravity	0.990
Solubility	slightly soluble
Partition coefficient; n-octanol/water	No data available
Autoignition Temperature	Not applicable 526 °C / 978.8 °F
Decomposition Temperature	540 °C
Viscosity	Not applicable
Molecular Formula	C10H8
Molecular Weight	128.17

10. Stability and reactivity

Reactive Hazard Yes

Stability Stable under normal conditions.

Conditions to Avoid Incompatible products. Excess heat. Avoid dust formation. Keep away from open flames, hot surfaces and sources of ignition.

Incompatible Materials Strong oxidizing agents

Hazardous Decomposition Products Carbon monoxide (CO), Carbon dioxide (CO_2)

Hazardous Polymerization Hazardous polymerization does not occur.

Hazardous Reactions None under normal processing.

11. Toxicological information

Acute Toxicity

Product Information

Component Information

Component	LD50 Oral	LD50 Dermal	LC50 Inhalation
Naphthalene	LD50 = 490 mg/kg (Rat) LD50 = 1110 mg/kg (Rat)	LD50 > 20 g/kg (Rabbit) LD50 = 1120 mg/kg (Rabbit)	LC50 > 340 mg/m³ (Rat) 1 h

Toxicologically Synergistic Products No information available

Delayed and immediate effects as well as chronic effects from short and long-term exposure

Irritation No information available

Sensitization No information available

Carcinogenicity The table below indicates whether each agency has listed any ingredient as a carcinogen.

Component	CAS-No	IARC	NTP	ACGIH	OSHA	Mexico
Naphthalene	91-20-3	Group 2B	Reasonably Anticipated	A3	X	Not listed

IARC: (International Agency for Research on Cancer)

IARC: (International Agency for Research on Cancer)
Group 1 - Carcinogenic to Humans
Group 2A - Probably Carcinogenic to Humans
Group 2B - Possibly Carcinogenic to Humans

NTP: (National Toxicity Program)

NTP: (National Toxicity Program)
Known - Known Carcinogen
Reasonably Anticipated - Reasonably Anticipated to be a Human Carcinogen

ACGIH: (American Conference of Governmental Industrial Hygienists)

A1 - Known Human Carcinogen
A2 - Suspected Human Carcinogen
A3 - Animal Carcinogen
ACGIH: (American Conference of Governmental Industrial Hygienists)

Mutagenic Effects Not mutagenic in AMES Test

Reproductive Effects Experiments have shown reproductive toxicity effects on laboratory animals.

Developmental Effects Developmental effects have occurred in experimental animals.

Teratogenicity Teratogenic effects have occurred in experimental animals.

STOT - single exposure None known

STOT - repeated exposure Liver Kidney

Aspiration hazard No information available

Symptoms / effects,both acute and delayed Symptoms of overexposure may be headache, dizziness, tiredness, nausea and vomiting

Endocrine Disruptor Information No information available

Other Adverse Effects Tumorigenic effects have been reported in experimental animals.

12. Ecological information

Ecotoxicity

Very toxic to aquatic organisms, may cause long-term adverse effects in the aquatic environment. The product contains following substances which are hazardous for the environment.

Component	Freshwater Algae	Freshwater Fish	Microtox	Water Flea
Naphthalene	EC50: = 0.4 mg/L, 72h (Skeletonema costatum)	LC50 96 h 1-6.5 mg/L (Pimephales promelas)	EC50 = 0.93 mg/L 30 min EC50 > 20 mg/L 18 h	EC50: 1.09 - 3.4 mg/L, 48h Static (Daphnia magna) EC50: = 1.96 mg/L, 48h Flow through (Daphnia magna) LC50: = 2.16 mg/L, 48h (Daphnia magna)

Persistence and Degradability Soluble in water Persistence is unlikely based on information available.
Bioaccumulation/ Accumulation No information available.

Mobility . Will likely be mobile in the environment due to its water solubility.

Component	log Pow
Naphthalene	3.3

13. Disposal considerations

Waste Disposal Methods Chemical waste generators must determine whether a discarded chemical is classified as a hazardous waste. Chemical waste generators must also consult local, regional, and national hazardous waste regulations to ensure complete and accurate classification.

Component	RCRA - U Series Wastes	RCRA - P Series Wastes
Naphthalene - 91-20-3	U165	-

14. Transport information

DOT
- **UN-No** UN1334
- **Proper Shipping Name** NAPHTHALENE, CRUDE
- **Hazard Class** 4.1
- **Packing Group** III

TDG
- **UN-No** UN1334
- **Proper Shipping Name** NAPHTHALENE, CRUDE
- **Hazard Class** 4.1
- **Packing Group** III

IATA
- **UN-No** UN1334
- **Proper Shipping Name** NAPHTHALENE, CRUDE
- **Hazard Class** 4.1
- **Packing Group** III

IMDG/IMO
- **UN-No** UN1334
- **Proper Shipping Name** NAPHTHALENE, CRUDE
- **Hazard Class** 4.1
- **Packing Group** III

15. Regulatory information

All of the components in the product are on the following Inventory lists: X = listed

International Inventories

Component	TSCA	DSL	NDSL	EINECS	ELINCS	NLP	PICCS	ENCS	AICS	IECSC	KECL
Naphthalene	X	X	-	202-049-5	-		X	X	X	X	X

Legend:
X - Listed
E - Indicates a substance that is the subject of a Section 5(e) Consent order under TSCA.
F - Indicates a substance that is the subject of a Section 5(f) Rule under TSCA.
N - Indicates a polymeric substance containing no free-radical initiator in its inventory name but is considered to cover the designated polymer made with any free-radical initiator regardless of the amount used.

P - Indicates a commenced PMN substance
R - Indicates a substance that is the subject of a Section 6 risk management rule under TSCA.
S - Indicates a substance that is identified in a proposed or final Significant New Use Rule
T - Indicates a substance that is the subject of a Section 4 test rule under TSCA.
XU - Indicates a substance exempt from reporting under the Inventory Update Rule, i.e. Partial Updating of the TSCA Inventory Data Base Production and Site Reports (40 CFR 710(B).
Y1 - Indicates an exempt polymer that has a number-average molecular weight of 1,000 or greater.
Y2 - Indicates an exempt polymer that is a polyester and is made only from reactants included in a specified list of low concern reactants that comprises one of the eligibility criteria for the exemption rule.

U.S. Federal Regulations

TSCA 12(b)

SARA 313

Component	CAS-No	Weight %	SARA 313 - Threshold Values %
Naphthalene	91-20-3	>95	0.1

SARA 311/312 Hazard Categories

Acute Health Hazard	Yes
Chronic Health Hazard	Yes
Fire Hazard	Yes
Sudden Release of Pressure Hazard	No
Reactive Hazard	Yes

CWA (Clean Water Act)

Component	CWA - Hazardous Substances	CWA - Reportable Quantities	CWA - Toxic Pollutants	CWA - Priority Pollutants
Naphthalene	X	100 lb	X	X

Clean Air Act

Component	HAPS Data	Class 1 Ozone Depletors	Class 2 Ozone Depletors
Naphthalene	X		-

OSHA Occupational Safety and Health Administration
Not applicable

CERCLA
This material, as supplied, contains one or more substances regulated as a hazardous substance under the Comprehensive Environmental Response Compensation and Liability Act (CERCLA) (40 CFR 302)

Component	Hazardous Substances RQs	CERCLA EHS RQs
Naphthalene	100 lb 1 lb	-

California Proposition 65 This product contains the following proposition 65 chemicals

Component	CAS-No	California Prop. 65	Prop 65 NSRL	Category
Naphthalene	91-20-3	Carcinogen	5.8 µg/day	Carcinogen

U.S. State Right-to-Know Regulations

Component	Massachusetts	New Jersey	Pennsylvania	Illinois	Rhode Island
Naphthalene	X	X	X	X	X

U.S. Department of Transportation

Reportable Quantity (RQ):	N
DOT Marine Pollutant	N
DOT Severe Marine Pollutant	N

U.S. Department of Homeland Security
This product does not contain any DHS chemicals.

Other International Regulations

Mexico - Grade Moderate risk, Grade 2

Canada
This product has been classified in accordance with the hazard criteria of the Controlled Products Regulations (CPR) and the MSDS contains all the information required by the CPR

WHMIS Hazard Class
B3 Combustible liquid
D1B Toxic materials
D2A Very toxic materials

16. Other information

Prepared By
Regulatory Affairs
Thermo Fisher Scientific
Email: EMSDS.RA@thermofisher.com

Creation Date 27-Sep-2010
Revision Date 12-Oct-2015
Print Date 12-Oct-2015
Revision Summary This document has been updated to comply with the US OSHA HazCom 2012 Standard replacing the current legislation under 29 CFR 1910.1200 to align with the Globally Harmonized System of Classification and Labeling of Chemicals (GHS)

Disclaimer
The information provided on this Safety Data Sheet is correct to the best of our knowledge, information and belief at the date of its publication. The information given is designed only as a guide for safe handling, use, processing, storage, transportation, disposal and release and is not to be considered as a warranty or quality specification. The information relates only to the specific material designated and may not be valid for such material used in combination with any other material or in any process, unless specified in the text.

End of SDS

SAFETY DATA SHEET

Version 4.7
Revision Date 12/28/2015
Print Date 05/01/2016

1. PRODUCT AND COMPANY IDENTIFICATION

1.1 Product identifiers

Product name : Nickel

Product Number : 268259
Brand : Aldrich
Index-No. : 028-002-00-7

CAS-No. : 7440-02-0

1.2 Relevant identified uses of the substance or mixture and uses advised against

Identified uses : Laboratory chemicals, Synthesis of substances

1.3 Details of the supplier of the safety data sheet

Company : Sigma-Aldrich
3050 Spruce Street
SAINT LOUIS MO 63103
USA

Telephone : +1 800-325-5832
Fax : +1 800-325-5052

1.4 Emergency telephone number

Emergency Phone # : (314) 776-6555

2. HAZARDS IDENTIFICATION

2.1 Classification of the substance or mixture

GHS Classification in accordance with 29 CFR 1910 (OSHA HCS)
Skin sensitisation (Category 1), H317
Carcinogenicity (Category 2), H351
Specific target organ toxicity - repeated exposure, Inhalation (Category 1), H372
Acute aquatic toxicity (Category 3), H402
Chronic aquatic toxicity (Category 3), H412

For the full text of the H-Statements mentioned in this Section, see Section 16.

2.2 GHS Label elements, including precautionary statements

Pictogram

Signal word Danger

Hazard statement(s)
H317 May cause an allergic skin reaction.
H351 Suspected of causing cancer.
H372 Causes damage to organs through prolonged or repeated exposure if inhaled.
H412 Harmful to aquatic life with long lasting effects.

Precautionary statement(s)
P201 Obtain special instructions before use.
P202 Do not handle until all safety precautions have been read and

	understood.
P260	Do not breathe dust/ fume/ gas/ mist/ vapours/ spray.
P264	Wash skin thoroughly after handling.
P270	Do not eat, drink or smoke when using this product.
P272	Contaminated work clothing should not be allowed out of the workplace.
P273	Avoid release to the environment.
P280	Wear protective gloves/ protective clothing/ eye protection/ face protection.
P302 + P352	IF ON SKIN: Wash with plenty of soap and water.
P308 + P313	IF exposed or concerned: Get medical advice/ attention.
P333 + P313	If skin irritation or rash occurs: Get medical advice/ attention.
P363	Wash contaminated clothing before reuse.
P405	Store locked up.
P501	Dispose of contents/ container to an approved waste disposal plant.

2.3 Hazards not otherwise classified (HNOC) or not covered by GHS - none

3. COMPOSITION/INFORMATION ON INGREDIENTS

3.1 Substances

Formula	:	Ni
Molecular weight	:	58.69 g/mol
CAS-No.	:	7440-02-0
EC-No.	:	231-111-4
Index-No.	:	028-002-00-7

Hazardous components

Component	Classification	Concentration
Nickel		
	Skin Sens. 1; Carc. 2; STOT RE 1; Aquatic Acute 3; Aquatic Chronic 3; H317, H351, H372, H412	<= 100 %

For the full text of the H-Statements mentioned in this Section, see Section 16.

4. FIRST AID MEASURES

4.1 Description of first aid measures

General advice
Consult a physician. Show this safety data sheet to the doctor in attendance.Move out of dangerous area.

If inhaled
If breathed in, move person into fresh air. If not breathing, give artificial respiration. Consult a physician.

In case of skin contact
Wash off with soap and plenty of water. Take victim immediately to hospital. Consult a physician.

In case of eye contact
Flush eyes with water as a precaution.

If swallowed
Never give anything by mouth to an unconscious person. Rinse mouth with water. Consult a physician.

4.2 Most important symptoms and effects, both acute and delayed
The most important known symptoms and effects are described in the labelling (see section 2.2) and/or in section 11

4.3 Indication of any immediate medical attention and special treatment needed
No data available

5. FIREFIGHTING MEASURES

5.1 Extinguishing media

Suitable extinguishing media
Use water spray, alcohol-resistant foam, dry chemical or carbon dioxide.

5.2 Special hazards arising from the substance or mixture
Nickel/nickel oxides

5.3 Advice for firefighters
Wear self-contained breathing apparatus for firefighting if necessary.

5.4 Further information
No data available

6. ACCIDENTAL RELEASE MEASURES

6.1 Personal precautions, protective equipment and emergency procedures
Use personal protective equipment. Avoid dust formation. Avoid breathing vapours, mist or gas. Ensure adequate ventilation. Evacuate personnel to safe areas. Avoid breathing dust.
For personal protection see section 8.

6.2 Environmental precautions
Prevent further leakage or spillage if safe to do so. Do not let product enter drains. Discharge into the environment must be avoided.

6.3 Methods and materials for containment and cleaning up
Pick up and arrange disposal without creating dust. Sweep up and shovel. Keep in suitable, closed containers for disposal.

6.4 Reference to other sections
For disposal see section 13.

7. HANDLING AND STORAGE

7.1 Precautions for safe handling
Further processing of solid materials may result in the formation of combustible dusts. The potential for combustible dust formation should be taken into consideration before additional processing occurs.Avoid contact with skin and eyes. Avoid formation of dust and aerosols.
Provide appropriate exhaust ventilation at places where dust is formed.
For precautions see section 2.2.

7.2 Conditions for safe storage, including any incompatibilities
Keep container tightly closed in a dry and well-ventilated place.
Storage class (TRGS 510): Non-combustible, acute toxic Cat.3 / toxic hazardous materials or hazardous materials causing chronic effects

7.3 Specific end use(s)
Apart from the uses mentioned in section 1.2 no other specific uses are stipulated

8. EXPOSURE CONTROLS/PERSONAL PROTECTION

8.1 Control parameters

Components with workplace control parameters

Component	CAS-No.	Value	Control parameters	Basis
Nickel	7440-02-0	TWA	1.500000 mg/m3	USA. ACGIH Threshold Limit Values (TLV)
	Remarks	Dermatitis Pneumoconiosis Not suspected as a human carcinogen		
		TWA	1.000000 mg/m3	USA. Occupational Exposure Limits (OSHA) - Table Z-1 Limits for Air Contaminants
		TWA	0.015000 mg/m3	USA. NIOSH Recommended Exposure Limits
		Potential Occupational Carcinogen See Appendix A		

		TWA	1.000000 mg/m3	USA. Occupational Exposure Limits (OSHA) - Table Z-1 Limits for Air Contaminants
		TWA	0.015000 mg/m3	USA. NIOSH Recommended Exposure Limits
		Potential Occupational Carcinogen See Appendix A		
		TWA	1.5 mg/m3	USA. ACGIH Threshold Limit Values (TLV)
		Dermatitis Pneumoconiosis Not suspected as a human carcinogen		
		TWA	1 mg/m3	USA. Occupational Exposure Limits (OSHA) - Table Z-1 Limits for Air Contaminants
		TWA	0.015 mg/m3	USA. NIOSH Recommended Exposure Limits
		Potential Occupational Carcinogen See Appendix A		

8.2 Exposure controls

Appropriate engineering controls
Handle in accordance with good industrial hygiene and safety practice. Wash hands before breaks and at the end of workday.

Personal protective equipment

Eye/face protection
Face shield and safety glasses Use equipment for eye protection tested and approved under appropriate government standards such as NIOSH (US) or EN 166(EU).

Skin protection
Handle with gloves. Gloves must be inspected prior to use. Use proper glove removal technique (without touching glove's outer surface) to avoid skin contact with this product. Dispose of contaminated gloves after use in accordance with applicable laws and good laboratory practices. Wash and dry hands.

Full contact
Material: Nitrile rubber
Minimum layer thickness: 0.11 mm
Break through time: 480 min
Material tested:Dermatril® (KCL 740 / Aldrich Z677272, Size M)

Splash contact
Material: Nitrile rubber
Minimum layer thickness: 0.11 mm
Break through time: 480 min
Material tested:Dermatril® (KCL 740 / Aldrich Z677272, Size M)

data source: KCL GmbH, D-36124 Eichenzell, phone +49 (0)6659 87300, e-mail sales@kcl.de, test method: EN374
If used in solution, or mixed with other substances, and under conditions which differ from EN 374, contact the supplier of the CE approved gloves. This recommendation is advisory only and must be evaluated by an industrial hygienist and safety officer familiar with the specific situation of anticipated use by our customers. It should not be construed as offering an approval for any specific use scenario.

Body Protection
Complete suit protecting against chemicals, The type of protective equipment must be selected according to the concentration and amount of the dangerous substance at the specific workplace.

Respiratory protection
Where risk assessment shows air-purifying respirators are appropriate use a full-face particle respirator type N100 (US) or type P3 (EN 143) respirator cartridges as a backup to engineering controls. If the respirator is the sole means of protection, use a full-face supplied air respirator. Use respirators and components tested and approved under appropriate government standards such as NIOSH (US) or CEN (EU).

Control of environmental exposure
Prevent further leakage or spillage if safe to do so. Do not let product enter drains. Discharge into the environment must be avoided.

9. PHYSICAL AND CHEMICAL PROPERTIES

9.1 Information on basic physical and chemical properties

a)	Appearance	Form: Foil Colour: white, silver, metallic
b)	Odour	No data available
c)	Odour Threshold	No data available
d)	pH	No data available
e)	Melting point/freezing point	Melting point/range: 1,453 °C (2,647 °F) - lit.
f)	Initial boiling point and boiling range	2,732 °C (4,950 °F) - lit.
g)	Flash point	Not applicable
h)	Evaporation rate	No data available
i)	Flammability (solid, gas)	No data available
j)	Upper/lower flammability or explosive limits	No data available
k)	Vapour pressure	1 hPa (1 mmHg) at 1,810 °C (3,290 °F)
l)	Vapour density	No data available
m)	Relative density	8.9 g/mL at 25 °C (77 °F)
n)	Water solubility	insoluble
o)	Partition coefficient: n-octanol/water	No data available
p)	Auto-ignition temperature	No data available
q)	Decomposition temperature	No data available
r)	Viscosity	No data available
s)	Explosive properties	No data available
t)	Oxidizing properties	No data available

9.2 Other safety information
No data available

10. STABILITY AND REACTIVITY

10.1 Reactivity
No data available

10.2 Chemical stability
Stable under recommended storage conditions.

10.3 Possibility of hazardous reactions
No data available

10.4 Conditions to avoid
No data available

10.5 Incompatible materials
acids, Oxidizing agents, Sulphur compounds, Hydrogen gas, Oxygen, Methanol, organic solvents, Aluminium, Fluorine, Ammonia

10.6 Hazardous decomposition products
Other decomposition products - No data available
In the event of fire: see section 5

11. TOXICOLOGICAL INFORMATION

11.1 Information on toxicological effects

Acute toxicity
No data available

Inhalation: No data available

Dermal: No data available

No data available

Skin corrosion/irritation
No data available

Serious eye damage/eye irritation
No data available

Respiratory or skin sensitisation
May cause sensitisation by skin contact.

Germ cell mutagenicity
No data available

Carcinogenicity

Limited evidence of carcinogenicity in animal studies

IARC:	2B - Group 2B: Possibly carcinogenic to humans (Nickel)
	1 - Group 1: Carcinogenic to humans (Nickel)
	2B - Group 2B: Possibly carcinogenic to humans (Nickel)
IARC:	2B - Group 2B: Possibly carcinogenic to humans (Nickel)
	1 - Group 1: Carcinogenic to humans (Nickel)
	2B - Group 2B: Possibly carcinogenic to humans (Nickel)
NTP:	Reasonably anticipated to be a human carcinogen (Nickel)
	Reasonably anticipated to be a human carcinogen (Nickel)
OSHA:	No component of this product present at levels greater than or equal to 0.1% is identified as a carcinogen or potential carcinogen by OSHA.

Reproductive toxicity
No data available

No data available

Specific target organ toxicity - single exposure
No data available

Specific target organ toxicity - repeated exposure
Inhalation - Causes damage to organs through prolonged or repeated exposure.

Aspiration hazard
No data available

Additional Information
RTECS: QR5950000

Stomach - Irregularities - Based on Human Evidence
Stomach - Irregularities - Based on Human Evidence

12. ECOLOGICAL INFORMATION

12.1 Toxicity

Toxicity to fish	LC50 - Cyprinus carpio (Carp) - 1.3 mg/l - 96 h
Toxicity to daphnia and other aquatic invertebrates	EC50 - Daphnia magna (Water flea) - 1 mg/l - 48 h

12.2 Persistence and degradability
Not applicable

12.3 Bioaccumulative potential
No data available

12.4 Mobility in soil
No data available

12.5 Results of PBT and vPvB assessment
PBT/vPvB assessment not available as chemical safety assessment not required/not conducted

12.6 Other adverse effects
An environmental hazard cannot be excluded in the event of unprofessional handling or disposal.
Harmful to aquatic life with long lasting effects.

13. DISPOSAL CONSIDERATIONS

13.1 Waste treatment methods

Product
Offer surplus and non-recyclable solutions to a licensed disposal company. Contact a licensed professional waste disposal service to dispose of this material. Dissolve or mix the material with a combustible solvent and burn in a chemical incinerator equipped with an afterburner and scrubber.

Contaminated packaging
Dispose of as unused product.

14. TRANSPORT INFORMATION

DOT (US)
Not dangerous goods

IMDG
Not dangerous goods

IATA
Not dangerous goods

15. REGULATORY INFORMATION

SARA 302 Components
No chemicals in this material are subject to the reporting requirements of SARA Title III, Section 302.

SARA 313 Components
The following components are subject to reporting levels established by SARA Title III, Section 313:

	CAS-No.	Revision Date
Nickel	7440-02-0	2007-07-01

SARA 311/312 Hazards
Acute Health Hazard, Chronic Health Hazard

Massachusetts Right To Know Components

	CAS-No.	Revision Date
Nickel	7440-02-0	2007-07-01

Pennsylvania Right To Know Components

	CAS-No.	Revision Date
Nickel	7440-02-0	2007-07-01

New Jersey Right To Know Components

	CAS-No.	Revision Date
Nickel	7440-02-0	2007-07-01

California Prop. 65 Components

WARNING! This product contains a chemical known to the State of California to cause cancer.	CAS-No.	Revision Date
Nickel	7440-02-0	2007-09-28

16. OTHER INFORMATION

Full text of H-Statements referred to under sections 2 and 3.

Aquatic Acute	Acute aquatic toxicity
Aquatic Chronic	Chronic aquatic toxicity
Carc.	Carcinogenicity
H317	May cause an allergic skin reaction.
H351	Suspected of causing cancer.
H372	Causes damage to organs through prolonged or repeated exposure if inhaled.
H402	Harmful to aquatic life.
H412	Harmful to aquatic life with long lasting effects.

HMIS Rating

Health hazard:	2
Chronic Health Hazard:	*
Flammability:	0
Physical Hazard	0

NFPA Rating

Health hazard:	2
Fire Hazard:	0
Reactivity Hazard:	0

Further information

Copyright 2015 Sigma-Aldrich Co. LLC. License granted to make unlimited paper copies for internal use only.
The above information is believed to be correct but does not purport to be all inclusive and shall be used only as a guide. The information in this document is based on the present state of our knowledge and is applicable to the product with regard to appropriate safety precautions. It does not represent any guarantee of the properties of the product. Sigma-Aldrich Corporation and its Affiliates shall not be held liable for any damage resulting from handling or from contact with the above product. See www.sigma-aldrich.com and/or the reverse side of invoice or packing slip for additional terms and conditions of sale.

Preparation Information

Sigma-Aldrich Corporation
Product Safety – Americas Region
1-800-521-8956

Version: 4.7 Revision Date: 12/28/2015 Print Date: 05/01/2016

SAFETY DATA SHEET

Creation Date 10-Dec-2009 **Revision Date** 26-May-2017 **Revision Number** 4

1. Identification

Product Name **Tetrachloroethylene**

Cat No. : **AC445690000; ACR445690010; AC445690025; AC445691000**

Synonyms Perchloroethylene

Recommended Use Laboratory chemicals.
Uses advised against Not for food, drug, pesticide or biocidal product use

Details of the supplier of the safety data sheet

Company
Fisher Scientific
One Reagent Lane
Fair Lawn, NJ 07410
Tel: (201) 796-7100

Acros Organics
One Reagent Lane
Fair Lawn, NJ 07410

Emergency Telephone Number
For information **US** call: 001-800-ACROS-01 / **Europe** call: +32 14 57 52 11
Emergency Number **US:**001-201-796-7100 / **Europe:** +32 14 57 52 99
CHEMTREC Tel. No.**US:**001-800-424-9300 / **Europe:**001-703-527-3887

2. Hazard(s) identification

Classification
This chemical is considered hazardous by the 2012 OSHA Hazard Communication Standard (29 CFR 1910.1200)

Skin Corrosion/irritation	Category 2
Serious Eye Damage/Eye Irritation	Category 2
Skin Sensitization	Category 1
Carcinogenicity	Category 1B
Specific target organ toxicity (single exposure)	Category 3
Target Organs - Central nervous system (CNS).	
Specific target organ toxicity - (repeated exposure)	Category 2
Target Organs - Kidney, Liver, Blood.	

Label Elements

Signal Word
Danger

Hazard Statements
Causes skin irritation
Causes serious eye irritation
May cause an allergic skin reaction
May cause drowsiness or dizziness
May cause cancer
May cause damage to organs through prolonged or repeated exposure

Precautionary Statements
Prevention
Obtain special instructions before use
Do not handle until all safety precautions have been read and understood
Use personal protective equipment as required
Wash face, hands and any exposed skin thoroughly after handling
Contaminated work clothing should not be allowed out of the workplace
Do not breathe dust/fume/gas/mist/vapors/spray
Use only outdoors or in a well-ventilated area
Wear protective gloves/protective clothing/eye protection/face protection
Response
IF exposed or concerned: Get medical attention/advice
Inhalation
IF INHALED: Remove victim to fresh air and keep at rest in a position comfortable for breathing
Skin
IF ON SKIN: Wash with plenty of soap and water
Take off contaminated clothing and wash before reuse
If skin irritation or rash occurs: Get medical advice/attention
Eyes
IF IN EYES: Rinse cautiously with water for several minutes. Remove contact lenses, if present and easy to do. Continue rinsing
If eye irritation persists: Get medical advice/attention
Storage
Store locked up
Store in a well-ventilated place. Keep container tightly closed
Disposal
Dispose of contents/container to an approved waste disposal plant
Hazards not otherwise classified (HNOC)
Toxic to aquatic life with long lasting effects
WARNING! This product contains a chemical known in the State of California to cause cancer.

3. Composition / information on ingredients

Component	CAS-No	Weight %
Tetrachloroethylene	127-18-4	>95

4. First-aid measures

General Advice If symptoms persist, call a physician.

Eye Contact Rinse immediately with plenty of water, also under the eyelids, for at least 15 minutes. Obtain medical attention.

Skin Contact Wash off immediately with plenty of water for at least 15 minutes. If skin irritation persists, call a physician.

Inhalation Move to fresh air. If not breathing, give artificial respiration. Get medical attention if symptoms occur.

Ingestion Clean mouth with water and drink afterwards plenty of water.

Most important symptoms/effects None reasonably foreseeable. May cause allergic skin reaction. Inhalation of high vapor concentrations may cause symptoms like headache, dizziness, tiredness, nausea and vomiting: Symptoms of allergic reaction may include rash, itching, swelling, trouble breathing, tingling of the hands and feet, dizziness, lightheadedness, chest pain, muscle pain or flushing

Notes to Physician Treat symptomatically

5. Fire-fighting measures

Suitable Extinguishing Media Use water spray, alcohol-resistant foam, dry chemical or carbon dioxide.

Unsuitable Extinguishing Media No information available

Flash Point No information available
Method - No information available

Autoignition Temperature No information available
Explosion Limits
Upper No data available
Lower No data available
Sensitivity to Mechanical Impact No information available
Sensitivity to Static Discharge No information available

Specific Hazards Arising from the Chemical
Thermal decomposition can lead to release of irritating gases and vapors. Containers may explode when heated.

Hazardous Combustion Products
Chlorine Hydrogen chloride gas Phosgene
Protective Equipment and Precautions for Firefighters
As in any fire, wear self-contained breathing apparatus pressure-demand, MSHA/NIOSH (approved or equivalent) and full protective gear.

NFPA

Health	Flammability	Instability	Physical hazards
2	0	0	N/A

6. Accidental release measures

Personal Precautions Use personal protective equipment. Ensure adequate ventilation.
Environmental Precautions Do not flush into surface water or sanitary sewer system.

Methods for Containment and Clean Up Soak up with inert absorbent material. Keep in suitable, closed containers for disposal.

7. Handling and storage

Handling Wear personal protective equipment. Do not get in eyes, on skin, or on clothing. Ensure adequate ventilation. Avoid ingestion and inhalation.

Storage Keep containers tightly closed in a dry, cool and well-ventilated place. Protect from sunlight.

8. Exposure controls / personal protection

Exposure Guidelines

Component	ACGIH TLV	OSHA PEL	NIOSH IDLH	Mexico OEL (TWA)
Tetrachloroethylene	TWA: 25 ppm STEL: 100 ppm	(Vacated) TWA: 25 ppm (Vacated) TWA: 170 mg/m^3 Ceiling: 200 ppm TWA: 100 ppm	IDLH: 150 ppm	TWA: 100 ppm TWA: 670 mg/m^3 TWA: 200 ppm TWA: 1250 mg/m^3 STEL: 200 ppm STEL: 1340 mg/m^3

Legend

ACGIH - American Conference of Governmental Industrial Hygienists
OSHA - Occupational Safety and Health Administration
NIOSH IDLH: The National Institute for Occupational Safety and Health Immediately Dangerous to Life or Health

Engineering Measures Use only under a chemical fume hood. Ensure adequate ventilation, especially in confined areas. Ensure that eyewash stations and safety showers are close to the workstation location.

Personal Protective Equipment

Eye/face Protection Wear appropriate protective eyeglasses or chemical safety goggles as described by OSHA's eye and face protection regulations in 29 CFR 1910.133 or European Standard EN166.

Skin and body protection Long sleeved clothing.

Respiratory Protection Follow the OSHA respirator regulations found in 29 CFR 1910.134 or European Standard EN 149. Use a NIOSH/MSHA or European Standard EN 149 approved respirator if exposure limits are exceeded or if irritation or other symptoms are experienced.

Hygiene Measures Handle in accordance with good industrial hygiene and safety practice.

9. Physical and chemical properties

Physical State	Liquid
Appearance	Colorless
Odor	Characteristic, sweet
Odor Threshold	No information available
pH	No information available
Melting Point/Range	-22 °C / -7.6 °F
Boiling Point/Range	120 - 122 °C / 248 - 251.6 °F @ 760 mmHg
Flash Point	No information available
Evaporation Rate	6.0 (Ether = 1.0)
Flammability (solid,gas)	Not applicable
Flammability or explosive limits	
Upper	No data available
Lower	No data available
Vapor Pressure	18 mbar @ 20 °C
Vapor Density	No information available
Density	1.619
Specific Gravity	1.625
Solubility	0.15 g/L water (20°C)
Partition coefficient; n-octanol/water	No data available
Autoignition Temperature	No information available
Decomposition Temperature	> 150°C
Viscosity	0.89 mPa s at 20 °C
Molecular Formula	C2 Cl4
Molecular Weight	165.83

10. Stability and reactivity

Reactive Hazard None known, based on information available

Stability Stable under normal conditions.

Conditions to Avoid Incompatible products. Excess heat. Exposure to moist air or water.

Incompatible Materials Strong acids, Strong oxidizing agents, Strong bases, Metals, Zinc, Amines, Aluminium

Hazardous Decomposition Products Chlorine, Hydrogen chloride gas, Phosgene

Hazardous Polymerization Hazardous polymerization does not occur.

Hazardous Reactions None under normal processing.

11. Toxicological information

Acute Toxicity

Product Information

Component Information

Component	LD50 Oral	LD50 Dermal	LC50 Inhalation
Tetrachloroethylene	LD50 = 2629 mg/kg (Rat)	LD50 > 10000 mg/kg (Rat)	LC50 = 27.8 mg/L (Rat) 4 h

Toxicologically Synergistic Products No information available

Delayed and immediate effects as well as chronic effects from short and long-term exposure

Irritation Irritating to eyes and skin

Sensitization No information available

Carcinogenicity The table below indicates whether each agency has listed any ingredient as a carcinogen.

Component	CAS-No	IARC	NTP	ACGIH	OSHA	Mexico
Tetrachloroethylene	127-18-4	Group 2A	Reasonably Anticipated	A3	X	A3

IARC: (International Agency for Research on Cancer)

IARC: (International Agency for Research on Cancer)
Group 1 - Carcinogenic to Humans
Group 2A - Probably Carcinogenic to Humans
Group 2B - Possibly Carcinogenic to Humans

NTP: (National Toxicity Program)

NTP: (National Toxicity Program)
Known - Known Carcinogen
Reasonably Anticipated - Reasonably Anticipated to be a Human Carcinogen

ACGIH: (American Conference of Governmental Industrial Hygienists)

A1 - Known Human Carcinogen
A2 - Suspected Human Carcinogen
A3 - Animal Carcinogen
ACGIH: (American Conference of Governmental Industrial Hygienists)

Mexico - Occupational Exposure Limits - Carcinogens

Mexico - Occupational Exposure Limits - Carcinogens
A1 - Confirmed Human Carcinogen
A2 - Suspected Human Carcinogen
A3 - Confirmed Animal Carcinogen
A4 - Not Classifiable as a Human Carcinogen
A5 - Not Suspected as a Human Carcinogen

Mutagenic Effects No information available

Reproductive Effects No information available.

Developmental Effects No information available.

Teratogenicity No information available.

STOT - single exposure Central nervous system (CNS)
STOT - repeated exposure Kidney Liver Blood

Aspiration hazard No information available

Symptoms / effects,both acute and delayed Inhalation of high vapor concentrations may cause symptoms like headache, dizziness, tiredness, nausea and vomiting: Symptoms of allergic reaction may include rash, itching, swelling, trouble breathing, tingling of the hands and feet, dizziness, lightheadedness, chest

pain, muscle pain or flushing

Endocrine Disruptor Information

Component	EU - Endocrine Disrupters Candidate List	EU - Endocrine Disruptors - Evaluated Substances	Japan - Endocrine Disruptor Information
Tetrachloroethylene	Group II Chemical	Not applicable	Not applicable

Other Adverse Effects Tumorigenic effects have been reported in experimental animals.

12. Ecological information

Ecotoxicity

Toxic to aquatic organisms, may cause long-term adverse effects in the aquatic environment. The product contains following substances which are hazardous for the environment.

Component	Freshwater Algae	Freshwater Fish	Microtox	Water Flea
Tetrachloroethylene	EC50: > 500 mg/L, 96h (Pseudokirchneriella subcapitata)	LC50: 4.73 - 5.27 mg/L, 96h flow-through (Oncorhynchus mykiss) LC50: 11.0 - 15.0 mg/L, 96h static (Lepomis macrochirus) LC50: 8.6 - 13.5 mg/L, 96h static (Pimephales promelas) LC50: 12.4 - 14.4 mg/L, 96h flow-through (Pimephales promelas)	EC50 = 100 mg/L 24 h EC50 = 112 mg/L 24 h EC50 = 120.0 mg/L 30 min	EC50: 6.1 - 9.0 mg/L, 48h Static (Daphnia magna)

Persistence and Degradability Insoluble in water Persistence is unlikely based on information available.

Bioaccumulation/ Accumulation No information available.

Mobility . Is not likely mobile in the environment due its low water solubility. Will likely be mobile in the environment due to its volatility.

Component	log Pow
Tetrachloroethylene	2.88

13. Disposal considerations

Waste Disposal Methods Chemical waste generators must determine whether a discarded chemical is classified as a hazardous waste. Chemical waste generators must also consult local, regional, and national hazardous waste regulations to ensure complete and accurate classification.

Component	RCRA - U Series Wastes	RCRA - P Series Wastes
Tetrachloroethylene - 127-18-4	U210	-

14. Transport information

DOT

- **UN-No** UN1897
- **Proper Shipping Name** TETRACHLOROETHYLENE
- **Hazard Class** 6.1
- **Packing Group** III

TDG

- **UN-No** UN1897
- **Proper Shipping Name** TETRACHLOROETHYLENE
- **Hazard Class** 6.1
- **Packing Group** III

IATA

- **UN-No** UN1897
- **Proper Shipping Name** TETRACHLOROETHYLENE
- **Hazard Class** 6.1

Packing Group III

IMDG/IMO

UN-No UN1897
Proper Shipping Name TETRACHLOROETHYLENE
Hazard Class 6.1
Subsidiary Hazard Class P
Packing Group III

15. Regulatory information

All of the components in the product are on the following Inventory lists: X = listed

International Inventories

Component	TSCA	DSL	NDSL	EINECS	ELINCS	NLP	PICCS	ENCS	AICS	IECSC	KECL
Tetrachloroethylene	X	X	-	204-825-9	-		X	X	X	X	X

Legend:
X - Listed
E - Indicates a substance that is the subject of a Section 5(e) Consent order under TSCA.
F - Indicates a substance that is the subject of a Section 5(f) Rule under TSCA.
N - Indicates a polymeric substance containing no free-radical initiator in its inventory name but is considered to cover the designated polymer made with any free-radical initiator regardless of the amount used.
P - Indicates a commenced PMN substance
R - Indicates a substance that is the subject of a Section 6 risk management rule under TSCA.
S - Indicates a substance that is identified in a proposed or final Significant New Use Rule
T - Indicates a substance that is the subject of a Section 4 test rule under TSCA.
XU - Indicates a substance exempt from reporting under the Inventory Update Rule, i.e. Partial Updating of the TSCA Inventory Data Base Production and Site Reports (40 CFR 710(B).
Y1 - Indicates an exempt polymer that has a number-average molecular weight of 1,000 or greater.
Y2 - Indicates an exempt polymer that is a polyester and is made only from reactants included in a specified list of low concern reactants that comprises one of the eligibility criteria for the exemption rule.

U.S. Federal Regulations

TSCA 12(b) Not applicable

SARA 313

Component	CAS-No	Weight %	SARA 313 - Threshold Values %
Tetrachloroethylene	127-18-4	>95	0.1

SARA 311/312 Hazard Categories

Acute Health Hazard Yes
Chronic Health Hazard Yes
Fire Hazard No
Sudden Release of Pressure Hazard No
Reactive Hazard No

CWA (Clean Water Act)

Component	CWA - Hazardous Substances	CWA - Reportable Quantities	CWA - Toxic Pollutants	CWA - Priority Pollutants
Tetrachloroethylene	-	-	X	X

Clean Air Act

Component	HAPS Data	Class 1 Ozone Depletors	Class 2 Ozone Depletors
Tetrachloroethylene	X		-

OSHA Occupational Safety and Health Administration
Not applicable

CERCLA
This material, as supplied, contains one or more substances regulated as a hazardous substance under the Comprehensive

Environmental Response Compensation and Liability Act (CERCLA) (40 CFR 302)

Component	Hazardous Substances RQs	CERCLA EHS RQs
Tetrachloroethylene	100 lb 1 lb	-

California Proposition 65 This product contains the following proposition 65 chemicals

Component	CAS-No	California Prop. 65	Prop 65 NSRL	Category
Tetrachloroethylene	127-18-4	Carcinogen	14 µg/day	Carcinogen

U.S. State Right-to-Know Regulations

Component	Massachusetts	New Jersey	Pennsylvania	Illinois	Rhode Island
Tetrachloroethylene	X	X	X	X	X

U.S. Department of Transportation

Reportable Quantity (RQ): Y
DOT Marine Pollutant Y
DOT Severe Marine Pollutant N

U.S. Department of Homeland Security
This product does not contain any DHS chemicals.

Other International Regulations

Mexico - Grade No information available

16. Other information

Prepared By
Regulatory Affairs
Thermo Fisher Scientific
Email: EMSDS.RA@thermofisher.com

Creation Date 10-Dec-2009
Revision Date 26-May-2017
Print Date 26-May-2017
Revision Summary This document has been updated to comply with the US OSHA HazCom 2012 Standard replacing the current legislation under 29 CFR 1910.1200 to align with the Globally Harmonized System of Classification and Labeling of Chemicals (GHS).

Disclaimer
The information provided in this Safety Data Sheet is correct to the best of our knowledge, information and belief at the date of its publication. The information given is designed only as a guidance for safe handling, use, processing, storage, transportation, disposal and release and is not to be considered a warranty or quality specification. The information relates only to the specific material designated and may not be valid for such material used in combination with any other materials or in any process, unless specified in the text

End of SDS

SAFETY DATA SHEET

Section 1. Identification

CHS Inc.
P.O. Box 64089
Mail station 525
St. Paul, MN 55164-0089

Transportation Emergency (CHEMTREC) : **1-800-424-9300**
Technical Information : **1-651-355-8443**
SDS Information : **1-651-355-8445**

Product name	:	Regular, Midgrade & Premium Unleaded Gasoline	**SDS no.**	:	0147- M6A0
Common name	:	Unleaded Gasoline, Premium Unleaded Gasoline	**Revision date**	:	11/15/2013
Chemical name	:	Light Petroleum Distillate	**Chemical formula**	:	Mixture
Chemical family	:	Mixed Petroleum Hydrocarbon			

Relevant identified uses of the substance or mixture and uses advised against

Not available.

Section 2. Hazards identification

OSHA/HCS status : This material is considered hazardous by the OSHA Hazard Communication Standard (29 CFR 1910.1200).

Classification of the substance or mixture :
FLAMMABLE LIQUIDS - Category 1
SKIN CORROSION/IRRITATION - Category 2
GERM CELL MUTAGENICITY - Category 1B
CARCINOGENICITY - Category 1A
TOXIC TO REPRODUCTION (Fertility) - Category 2
TOXIC TO REPRODUCTION (Unborn child) - Category 2
SPECIFIC TARGET ORGAN TOXICITY (SINGLE EXPOSURE) (Narcotic effects) - Category 3
SPECIFIC TARGET ORGAN TOXICITY (REPEATED EXPOSURE) - Category 1
ASPIRATION HAZARD - Category 1
AQUATIC HAZARD (ACUTE) - Category 3
AQUATIC HAZARD (LONG-TERM) - Category 3

GHS label elements

Hazard pictograms :

Signal word : Danger

Hazard statements :
Extremely flammable liquid and vapor.
Causes skin irritation.
May cause genetic defects.
May cause cancer.
Suspected of damaging fertility or the unborn child.
May be fatal if swallowed and enters airways.
May cause drowsiness and dizziness.
Causes damage to organs through prolonged or repeated exposure.
Harmful to aquatic life with long lasting effects.

Precautionary statements

General : Read label before use. Keep out of reach of children. If medical advice is needed, have product container or label at hand.

Hazardous Material Information System (U.S.A.)	**Health :**	2 *	**Flammability :**	4	**Physical hazards :**	0
National Fire Protection Association (U.S.A.)	**Health :**	2	**Flammability :**	4	**Instability :**	0

Section 3. Composition/information on ingredients

Substance/mixture : Mixture

Chemical name : Light Petroleum Distillate

Other means of identification : Unleaded Gasoline, Premium Unleaded Gasoline

Ingredient name	%	CAS number
Toluene	10 - 30	108-88-3
Xylene	10 - 30	1330-20-7
Tert-butyl methyl ether	10 - 30	1634-04-4
Benzene	1 - 5	71-43-2
1,2,4-Trimethylbenzene	1 - 5	95-63-6
Ethylbenzene	1 - 5	100-41-4
n-Hexane	1 - 5	110-54-3
Butyl ethyl ether	0.1 - 1	628-81-9
Naphthalene	0.1 - 1	91-20-3

Any concentration shown as a range is to protect confidentiality or is due to batch variation.

There are no additional ingredients present which, within the current knowledge of the supplier and in the concentrations applicable, are classified as hazardous to health or the environment and hence require reporting in this section.

Occupational exposure limits, if available, are listed in Section 8.

Section 4. First aid measures

Description of necessary first aid measures

Eye contact : If material comes in contact with the eyes, immediately wash the eyes with large amounts of water for 15 minutes, occasionally lifting the lower and upper lids. Get medical attention.

Inhalation : If person breathes in large amounts of material, move the exposed person to fresh air at once. If breathing has stopped, perform artificial respiration. Keep the person warm and at rest. Get medical attention as soon as possible.

Skin contact : If the material comes in contact with the skin, wash the contaminated skin with soap and water promptly. If the material penetrates through clothing, remove the clothing and wash the skin with soap and water promptly. If irritation persists after washing, get medical attention immediately.

Ingestion : If material has been swallowed, do not induce vomiting. Get medical attention immediately.

Most important symptoms/effects, acute and delayed

Potential acute health effects

Eye contact : Causes serious eye irritation.

Inhalation : Can cause central nervous system (CNS) depression. May cause drowsiness and dizziness.

Skin contact : Causes skin irritation.

Ingestion : Can cause central nervous system (CNS) depression. May be fatal if swallowed and enters airways. Irritating to mouth, throat and stomach.

Over-exposure signs/symptoms

Eye contact : Adverse symptoms may include the following: pain or irritation, watering, redness.

Inhalation : Adverse symptoms may include the following: respiratory tract irritation, coughing.

Skin contact : Adverse symptoms may include the following: irritation, redness.

Ingestion : No known significant effects or critical hazards.

Indication of immediate medical attention and special treatment needed, if necessary

Notes to physician : Treat symptomatically. Contact poison treatment specialist immediately if large quantities have been ingested or inhaled.

Specific treatments : No specific treatment.

Protection of first-aiders : No action shall be taken involving any personal risk or without suitable training. If it is suspected that fumes are still present, the rescuer should wear an appropriate mask or self-contained breathing apparatus. It may be dangerous to the person providing aid to give mouth-to-mouth resuscitation. Wash contaminated clothing thoroughly with water before removing it, or wear gloves.

See toxicological information (Section 11)

Section 5. Fire-fighting measures

Extinguishing media

Suitable extinguishing media : Use dry chemical, CO_2, water spray (fog) or foam.

Unsuitable extinguishing media : Do not use water jet or water-based fire extinguishers.

Specific hazards arising from the chemical : Highly volatile material. Flowing gasoline can be ignited by self-generated static electricity; containers should be bonded and grounded. Vapors may travel along the ground to a source of ignition (pilot light, heater, electric motor) some distance away. Containers, drums (even empty) can explode when heat (welding, cutting, etc.) is applied.

Hazardous thermal decomposition products : Decomposition products may include the following materials:
carbon dioxide
carbon monoxide

Special protective actions for fire-fighters : Water may be ineffective on flames, but should be used to keep fire-exposed containers cool. Large fires, such as tank fires, should be fought with caution. If possible, pump the contents from the tank and keep adjoining structures cool and protect personnel. Avoid spreading burning liquid with water used for cooling purposes. Do not flush down public sewers. The use of a self-contained breathing apparatus and protective clothing is recommended for fire fighters. Avoid inhalation of vapors.

Special protective equipment for fire-fighters : Fire-fighters should wear appropriate protective equipment and self-contained breathing apparatus (SCBA) with a full face-piece operated in positive pressure mode.

Section 6. Accidental release measures

Personal precautions, protective equipment and emergency procedures

For non-emergency personnel : Keep unnecessary and unprotected personnel from entering. Avoid breathing vapor or mist. Provide adequate ventilation. Wear appropriate respirator when ventilation is inadequate. Put on appropriate personal protective equipment.

Methods and materials for containment and cleaning up

Spill : Contain with dikes or absorbent to prevent migration to sewers/streams. Take up small spill with dry chemical absorbent; large spills may require pump or vacuum prior to absorbent. May require excavation of severely contaminated soil.

Section 7. Handling and storage

Precautions for safe handling

Protective measures : Put on appropriate personal protective equipment (see Section 8). Do not get in eyes or on skin or clothing. Do not breathe vapor or mist. Do not ingest. Use only with adequate ventilation. Wear appropriate respirator when ventilation is inadequate.

Advice on general occupational hygiene : Eating, drinking and smoking should be prohibited in areas where this material is handled, stored and processed. Workers should wash hands and face before eating, drinking and smoking.

Conditions for safe storage, including any incompatibilities : Do not store above the following temperature: 113°C (235.4°F). Odorous and toxic fumes may form from the decomposition of this product if stored at excessive temperatures for extended periods of time. Store in accordance with local regulations. Store in a dry, cool and well-ventilated area, away from incompatible materials (see Section 10). Use appropriate containment to avoid environmental contamination.

Section 8. Exposure controls/personal protection

Control parameters

Occupational exposure limits

Ingredient name	Exposure limits
Toluene	**NIOSH REL (United States, 6/2009).** STEL: 560 mg/m³ 15 minutes. STEL: 150 ppm 15 minutes. TWA: 375 mg/m³ 10 hours. TWA: 100 ppm 10 hours. **OSHA PEL Z2 (United States, 11/2006).** AMP: 500 ppm 10 minutes. CEIL: 300 ppm TWA: 200 ppm 8 hours. **ACGIH TLV (United States, 3/2012).** TWA: 20 ppm 8 hours.
Xylene	**ACGIH TLV (United States, 3/2012).** STEL: 651 mg/m³ 15 minutes. STEL: 150 ppm 15 minutes. TWA: 434 mg/m³ 8 hours. TWA: 100 ppm 8 hours. **OSHA PEL (United States, 6/2010).** TWA: 100 ppm 8 hours.

	TWA: 435 mg/m³ 8 hours.
Tert-butyl methyl ether	**ACGIH TLV (United States, 1/2005).** TWA: 50 ppm 8 hours. Form: All forms. **ACGIH TLV (United States, 2/2010).** TWA: 50 ppm 8 hours.
Benzene	**ACGIH TLV (United States, 3/2012). Absorbed through skin.** STEL: 8 mg/m³ 15 minutes. STEL: 2.5 ppm 15 minutes. TWA: 1.6 mg/m³ 8 hours. TWA: 0.5 ppm 8 hours. **NIOSH REL (United States, 6/2009).** STEL: 1 ppm 15 minutes. TWA: 0.1 ppm 10 hours. **OSHA PEL (United States, 6/2010).** STEL: 5 ppm 15 minutes. TWA: 1 ppm 8 hours. **OSHA PEL Z2 (United States, 11/2006).** AMP: 50 ppm 10 minutes. CEIL: 25 ppm TWA: 10 ppm 8 hours.
1,2,4-Trimethylbenzene	**ACGIH TLV (United States, 3/2012).** TWA: 123 mg/m³ 8 hours. TWA: 25 ppm 8 hours. **NIOSH REL (United States, 1/2013).** TWA: 125 mg/m³ 10 hours. TWA: 25 ppm 10 hours. **OSHA PEL 1989 (United States, 3/1989).** TWA: 25 ppm 8 hours. TWA: 125 mg/m³ 8 hours.
Ethylbenzene	**ACGIH TLV (United States, 3/2012).** TWA: 20 ppm 8 hours. **NIOSH REL (United States, 6/2009).** STEL: 545 mg/m³ 15 minutes. STEL: 125 ppm 15 minutes. TWA: 435 mg/m³ 10 hours. TWA: 100 ppm 10 hours. **OSHA PEL (United States, 6/2010).** TWA: 435 mg/m³ 8 hours. TWA: 100 ppm 8 hours.
n-Hexane	**ACGIH TLV (United States, 3/2012). Absorbed through skin.** TWA: 50 ppm 8 hours. **NIOSH REL (United States, 6/2009).** TWA: 180 mg/m³ 10 hours. TWA: 50 ppm 10 hours. **OSHA PEL (United States, 6/2010).** TWA: 1800 mg/m³ 8 hours. TWA: 500 ppm 8 hours.
Naphthalene	**ACGIH TLV (United States, 3/2012). Absorbed through skin.** STEL: 79 mg/m³ 15 minutes. STEL: 15 ppm 15 minutes. TWA: 52 mg/m³ 8 hours. TWA: 10 ppm 8 hours. **NIOSH REL (United States, 1/2013).** STEL: 75 mg/m³ 15 minutes. STEL: 15 ppm 15 minutes. TWA: 50 mg/m³ 10 hours. TWA: 10 ppm 10 hours. **OSHA PEL (United States, 6/2010).** TWA: 50 mg/m³ 8 hours. TWA: 10 ppm 8 hours.

Appropriate engineering controls : Use only with adequate ventilation.

Environmental exposure controls : Emissions from ventilation or work process equipment should be checked to ensure they comply with the requirements of environmental protection legislation.

Individual protection measures

Hygiene measures : Wash hands, forearms and face thoroughly after handling chemical products, before eating, smoking and using the lavatory and at the end of the working period. Ensure that eyewash stations and safety showers are close to the workstation location.

Eye/face protection : Recommended: Splash goggles and a face shield, where splash hazard exists.

Skin protection

Hand protection : 4 - 8 hours (breakthrough time): Nitrile gloves.

Body protection : Recommended: Long sleeved coveralls.

Other skin protection : Recommended: Impervious boots.

Respiratory protection : If ventilation is inadequate, use a NIOSH-certified respirator with an organic vapor cartridge and P95 particulate filter.

Section 9. Physical and chemical properties

Appearance

Physical state : Liquid.

Color : Reddish golden brown.

Odor : Gasoline

Odor threshold : 10 ppm

pH : Not available.

Melting point : Not available.

Boiling point : 26.66°C (80°F)

Flash point : Closed cup: -40°C (-40°F) [Pensky-Martens.]

Flammability : Not available.

Lower and upper explosive (flammable) limits : Lower: 1.4%
Upper: 7.6%

Relative density : 0.72

Evaporation rate : Slower.

Solubility : Insoluble in the following materials: cold water and hot water.

Solubility in water : Negligible.

Partition coefficient: n-octanol/water : Not available.

Auto-ignition temperature : 257.22 to 454.44°C (495 to 850°F)

Decomposition temperature : Not available.

SADT : Not available.

Viscosity : Not available.

Vapor pressure : 53.3 kPa (400 mm Hg) (68°F)

Vapor density : 4 [Air = 1]

Section 10. Stability and reactivity

Reactivity : No specific test data related to reactivity available for this product or its ingredients.

Chemical stability : The product is stable.

Possibility of hazardous reactions : Under normal conditions of storage and use, hazardous reactions will not occur.

Conditions to avoid : Avoid all possible sources of ignition (spark or flame). Do not pressurize, cut, weld, braze, solder, drill, grind or expose containers to heat or sources of ignition. Do not allow vapor to accumulate in low or confined areas.

Incompatible materials : Reactive or incompatible with the following materials: oxidizing materials, acids and alkalis.

Hazardous decomposition products : Under normal conditions of storage and use, hazardous decomposition products should not be produced.

Section 11. Toxicological information

Information on toxicological effects

Acute toxicity

Product/ingredient name	Result	Species	Dose	Exposure
Toluene	LC50 Inhalation Vapor	Rat	49 g/m³	4 hours
	LD50 Oral	Rat	636 mg/kg	-
Xylene	LC50 Inhalation Gas.	Rat	5000 ppm	4 hours
	LD50 Oral	Rat	4300 mg/kg	-
Tert-butyl methyl ether	LC50 Inhalation Gas.	Rat	23576 ppm	4 hours
	LC50 Inhalation Vapor	Rat	41000 mg/m³	4 hours
	LD50 Oral	Rat	>4 g/kg	-
Benzene	LD50 Oral	Rat	930 mg/kg	-
1,2,4-Trimethylbenzene	LC50 Inhalation Vapor	Rat	18000 mg/m³	4 hours
	LD50 Oral	Rat	5 g/kg	-
Ethylbenzene	LD50 Dermal	Rabbit	>5000 mg/kg	-
	LD50 Oral	Rat	3500 mg/kg	-
n-Hexane	LC50 Inhalation Gas.	Rat	48000 ppm	4 hours
	LD50 Oral	Rat	15840 mg/kg	-
Butyl ethyl ether	LD50 Oral	Rat	1870 mg/kg	-
Naphthalene	LD50 Dermal	Rabbit	>20 g/kg	-
	LD50 Oral	Rat	490 mg/kg	-

Irritation/Corrosion

Product/ingredient name	Result	Species	Score	Exposure	Observation
Toluene	Eyes - Mild irritant	Rabbit	-	0.5 minutes 100 mg	-
	Skin - Moderate irritant	Rabbit	-	24 hours 20 mg	-
	Eyes - Mild irritant	Rabbit	-	870 µg	-
	Eyes - Severe irritant	Rabbit	-	24 hours 2 mg	-
	Skin - Mild irritant	Pig	-	24 hours 250 µL	-
	Skin - Mild irritant	Rabbit	-	435 mg	-
	Skin - Moderate irritant	Rabbit	-	500 mg	-
Xylene	Eyes - Mild irritant	Rabbit	-	87 mg	-
	Eyes - Severe irritant	Rabbit	-	24 hours 5 mg	-
	Skin - Mild irritant	Rat	-	8 hours 60 µL	-
	Skin - Moderate irritant	Rabbit	-	24 hours 500 mg	-
	Skin - Moderate irritant	Rabbit	-	100%	-
Benzene	Eyes - Moderate irritant	Rabbit	-	88 mg	-
	Skin - Moderate irritant	Rabbit	-	24 hours 20 mg	-
	Eyes - Severe irritant	Rabbit	-	24 hours 2 mg	-
	Skin - Mild irritant	Rat	-	8 hours 60 µL	-
	Skin - Mild irritant	Rabbit	-	24 hours 15 mg	-
Ethylbenzene	Eyes - Severe irritant	Rabbit	-	500 mg	-
	Skin - Mild irritant	Rabbit	-	24 hours 15 mg	-
n-Hexane	Eyes - Mild irritant	Rabbit	-	10 mg	-
Naphthalene	Skin - Mild irritant	Rabbit	-	495 mg	-
	Skin - Severe irritant	Rabbit	-	24 hours 0.05 mL	-

Sensitization

Skin : There is no data available.

Respiratory : There is no data available.

Mutagenicity

There is no data available.

Carcinogenicity

There is no data available.

Classification

Product/ingredient name	OSHA	IARC	NTP
Toluene	-	3	-
Xylene	-	3	-
Tert-butyl methyl ether	-	3	-
Benzene	+	1	Known to be a human carcinogen.
Ethylbenzene	-	2B	-
Naphthalene	-	2B	Reasonably anticipated to be a human carcinogen.

Reproductive toxicity

There is no data available.

Teratogenicity

There is no data available.

Specific target organ toxicity (single exposure)

Name	Category	Route of exposure	Target organs
Toluene	Category 3	Not applicable.	Narcotic effects
1,2,4-Trimethylbenzene	Category 3	Not applicable.	Respiratory tract irritation
n-Hexane	Category 3	Not applicable.	Narcotic effects

Specific target organ toxicity (repeated exposure)

Name	Category	Route of exposure	Target organs
Toluene	Category 2	Not determined	Not determined
Benzene	Category 1	Not determined	Not determined
n-Hexane	Category 2	Not determined	Not determined

Aspiration hazard

Name	Result
Toluene	ASPIRATION HAZARD - Category 1
Benzene	ASPIRATION HAZARD - Category 1
n-Hexane	ASPIRATION HAZARD - Category 1

Information on the likely routes of exposure : Dermal contact. Eye contact. Inhalation. Ingestion.

Section 12. Ecological information

Toxicity

Product/ingredient name	Result	Species	Exposure
Toluene	Acute EC50 433 ppm Marine water	Algae - Skeletonema costatum	96 hours
	Acute EC50 12500 µg/l Fresh water	Algae - Pseudokirchneriella subcapitata	72 hours
	Acute EC50 11600 µg/l Fresh water	Crustaceans - Gammarus pseudolimnaeus - Adult	48 hours
	Acute EC50 6000 µg/l Fresh water	Daphnia - Daphnia magna - Juvenile (Fledgling, Hatchling, Weanling)	48 hours
	Acute LC50 5500 µg/l Fresh water	Fish - Oncorhynchus kisutch - Fry	96 hours
	Chronic NOEC 500000 µg/l Fresh water	Algae - Pseudokirchneriella subcapitata	96 hours
	Chronic NOEC 1000 µg/l Fresh water	Daphnia - Daphnia magna	21 days
Xylene	Acute IC50 10 mg/L	Algae	72 hours
	Acute LC50 8500 µg/l Marine water	Crustaceans - Palaemonetes pugio	48 hours
	Acute LC50 13400 µg/l Fresh water	Fish - Pimephales promelas	96 hours
Tert-butyl methyl ether	Acute LC50 672000 µg/l Fresh water	Fish - Pimephales promelas	96 hours
Benzene	Acute EC50 29000 µg/l Fresh water	Algae - Pseudokirchneriella subcapitata	72 hours
	Acute EC50 1360000 µg/l Fresh water	Algae - Scenedesmus abundans	96 hours
	Acute EC50 9230 µg/l Fresh water	Daphnia - Daphnia magna - Neonate	48 hours
	Acute LC50 21000 µg/l Marine water	Crustaceans - Artemia salina - Nauplii	48 hours
	Acute LC50 5.28 ul/L Fresh water	Fish - Oncorhynchus gorbuscha - Fry	96 hours
	Chronic NOEC 1.5 to 5.4 ul/L Marine water	Fish - Morone saxatilis - Juvenile (Fledgling, Hatchling, Weanling)	4 weeks
1,2,4-Trimethylbenzene	Acute LC50 4910 µg/l Marine water	Crustaceans - Elasmopus pectenicrus - Adult	48 hours
	Acute LC50 22.4 mg/L Fresh water	Fish - Tilapia zillii	96 hours
Ethylbenzene	Acute EC50 4600 µg/l Fresh water	Algae - Pseudokirchneriella subcapitata	72 hours
	Acute EC50 3600 µg/l Fresh water	Algae - Pseudokirchneriella subcapitata	96 hours
	Acute EC50 2970 µg/l Fresh water	Daphnia - Daphnia magna - Neonate	48 hours
	Acute LC50 5200 µg/l Marine water	Crustaceans - Americamysis bahia	48 hours
	Acute LC50 4200 µg/l Fresh water	Fish - Oncorhynchus mykiss	96 hours
	Chronic NOEC 1000 µg/l Fresh water	Algae - Pseudokirchneriella subcapitata	96 hours
n-Hexane	Acute LC50 113000 µg/l Fresh water	Fish - Oreochromis mossambicus	96 hours
Naphthalene	Acute EC50 1600 µg/l Fresh water	Daphnia - Daphnia magna - Neonate	48 hours
	Acute LC50 2350 µg/l Marine water	Crustaceans - Palaemonetes pugio	48 hours
	Acute LC50 213 µg/l Fresh water	Fish - Melanotaenia fluviatilis - Larvae	96 hours

Persistence and degradability

There is no data available.

Bioaccumulative potential

Product/ingredient name	$LogP_{ow}$	BCF	Potential
Toluene	2.73	90	low
Xylene	3.12	8.1 to 25.9	low
Tert-butyl methyl ether	1.04	1.5	low
Benzene	2.13	11	low
1,2,4-Trimethylbenzene	3.63	243	low
Ethylbenzene	3.6	-	low
n-Hexane	4	501.187	high
Butyl ethyl ether	2.03	-	low
Naphthalene	3.4	36.5 to 168	low

Mobility in soil

Soil/water partition coefficient (K_{OC}) : There is no data available.

Other adverse effects : No known significant effects or critical hazards.

Section 13. Disposal considerations

Disposal methods : Disposal of this product, solutions and any by-products should comply with the requirements of environmental protection and waste disposal legislation and any regional local authority requirements.

Section 14. Transport information

DOT IDENTIFICATION NUMBER UN1203 **DOT proper shipping name** GASOLINE (Toluene, Xylene) RQ (Benzene, Xylene)

DOT Hazard Class(es) 3 **PG** I **DOT EMER. RESPONSE GUIDE NO.** 128

Section 15. Regulatory information

U.S. Federal regulations : **TSCA 8(a) PAIR**: Naphthalene
TSCA 8(a) CDR Exempt/Partial exemption: Not determined
United States inventory (TSCA 8b): All components are listed or exempted.
Clean Water Act (CWA) 307: Toluene; Benzene; Ethylbenzene; Naphthalene
Clean Water Act (CWA) 311: Toluene; Xylene; Benzene; Ethylbenzene; Naphthalene

Clean Air Act Section 602 Class I Substances : Not listed
Clean Air Act Section 602 Class II Substances : Not listed
Clean Air Act Section 112(b) Hazardous Air Pollutants (HAPs) : Listed
DEA List I Chemicals (Precursor Chemicals) : Not listed
DEA List II Chemicals (Essential Chemicals) : Listed

SARA 302/304

Composition/information on ingredients

No products were found.

SARA 304 RQ : Not applicable.

SARA 311/312

Classification : Fire hazard
Immediate (acute) health hazard
Delayed (chronic) health hazard

Composition/information on ingredients

Name	%	Fire hazard	Sudden release of pressure	Reactive	Immediate (acute) health hazard	Delayed (chronic) health hazard
Toluene	10 - 30	Yes.	No.	No.	Yes.	Yes.
Xylene	10 - 30	Yes.	No.	No.	Yes.	No.
Tert-butyl methyl ether	10 - 30	Yes.	No.	No.	Yes.	No.
Benzene	1 - 5	Yes.	No.	No.	Yes.	Yes.
1,2,4-Trimethylbenzene	1 - 5	Yes.	No.	No.	Yes.	No.
Ethylbenzene	1 - 5	Yes.	No.	No.	Yes.	Yes.
n-Hexane	1 - 5	Yes.	No.	No.	Yes.	Yes.
Butyl ethyl ether	0.1 - 1	Yes.	No.	No.	Yes.	No.
Naphthalene	0.1 - 1	No.	No.	No.	Yes.	Yes.

SARA 313 : This product (does/not) contain toxic chemicals subject to the reporting requirements of SARA Section 313 of the Emergency Planning and Community Right-To-Know Act of 1986 and of 40 CFR 372.

Product name	CAS number	%
Toluene	108-88-3	Up to 18.1
Xylene	1330-20-7	Up to 15.3
Benzene	71-43-2	Up to 5.3
1,2,4-Trimethylbenzene	95-63-6	Up to 4.8
Ethylbenzene	100-41-4	Up to 2.6
n-Hexane	110-54-3	Up to 4
Naphthalene	91-20-3	Up to 1

SARA 313 notifications must not be detached from the SDS and any copying and redistribution of the SDS shall include copying and redistribution of the notice attached to copies of the SDS subsequently redistributed.

State regulations

Massachusetts : The following components are listed: Toluene; Xylene; Tert-butyl methyl ether; Benzene; 1,2,4-Trimethylbenzene; Ethylbenzene; n-Hexane; Butyl ethyl ether

New York : The following components are listed: Toluene; Xylene; Tert-butyl methyl ether; Benzene; Ethylbenzene; n-Hexane; Naphthalene

New Jersey : The following components are listed: Toluene; Xylene; Tert-butyl methyl ether; Benzene; 1,2,4-Trimethylbenzene; Ethylbenzene; n-Hexane; Butyl ethyl ether; Naphthalene

Pennsylvania : The following components are listed: Toluene; Xylene; Tert-butyl methyl ether; Benzene; 1,2,4-Trimethylbenzene; Ethylbenzene; n-Hexane; Butyl ethyl ether; Naphthalene

California Prop. 65 : **WARNING:** This product contains a chemical known to the State of California to cause cancer and birth defects or other reproductive harm.

Ingredient name	Cancer	Reproductive	No significant risk level	Maximum acceptable dosage level
Toluene	No.	Yes.	No.	7000 µg/day (ingestion) 13000 µg/day (inhalation)
Benzene	Yes.	Yes.	6.4 µg/day (ingestion) 13 µg/day (inhalation)	24 µg/day (ingestion) 49 µg/day (inhalation)
Ethylbenzene	Yes.	No.	41 µg/day (ingestion) 54 µg/day (inhalation)	No.
Naphthalene	Yes.	No.	Yes.	No.

Section 16. Other information

Revision date : 11/15/2013 **Supersedes** : 01/23/2013

Revised Section(s) : 1, 2, 3, 4, 5, 6, 7, 8, 9, 10, 11, 12, 13, 14, 15, 16. **Prepared by** : KMK Regulatory Services Inc.

Notice to reader
THE INFORMATION CONTAINED IN THIS SDS RELATES ONLY TO THE SPECIFIC MATERIAL IDENTIFIED. IT DOES NOT COVER USE OF THAT MATERIAL IN COMBINATION WITH ANY OTHER MATERIAL OR IN ANY PARTICULAR PROCESS. IN COMPLIANCE WITH 29 C.F.R. 1910.1200(g), CHS HAS PREPARED THIS SDS IN SEGMENTS, WITH THE INTENT THAT THOSE SEGMENTS BE READ TOGETHER AS A WHOLE WITHOUT TEXTUAL OMISSIONS OR ALTERATIONS. CHS BELIEVES THE INFORMATION CONTAINED HEREIN TO BE ACCURATE, BUT MAKES NO REPRESENTATION, GUARANTEE, OR WARRANTY, EXPRESS OR IMPLIED, ABOUT THE ACCURACY, RELIABILITY, OR COMPLETENESS OF THE INFORMATION OR ABOUT THE FITNESS OF CONTENTS HEREIN FOR EITHER GENERAL OR PARTICULAR PURPOSES. PERSONS REVIEWING THIS SDS SHOULD MAKE THEIR OWN DETERMINATION AS TO THE MATERIAL'S SUITABILITY AND COMPLETENESS FOR USE IN THEIR PARTICULAR APPLICATIONS.

CENEX
OUR ENERGY COMES THROUGH!®

A BRAND OF CHS

RegenOx® – Part A (Oxidizer Complex)

Material Safety Data Sheet (MSDS)

Last Revised: June 24, 2010

Section 1 – Supplier Information and Material Identification

Supplier:

1011 Calle Sombra
San Clemente, CA 92673
Telephone: 949.366.8000
Fax: 949.366.8090
E-mail: info@regenesis.com

Chemical Description:	A mixture of sodium percarbonate [$2Na_2CO_3 \cdot 3H_2O_2$], sodium carbonate [Na_2CO_3], sodium silicate and silica gel.
Chemical Family:	Inorganic Chemicals
Trade Name:	RegenOx® – Part A (Oxidizer Complex)
Product Use:	Used to remediate contaminated soil and groundwater (environmental applications)

Section 2 – Chemical Information/Other Designations

CAS No.	Chemical	Percentage
15630-89-4	Sodium Percarbonate	60 -100 %
5968-11-6	Sodium Carbonate Monohydrate	10 – 30 %
7699-11-6	Silicic Acid	< 1 %
63231-67-4	Silica Gel	< 1 %

Section 3 – Physical Data

Form:	Powder
Color:	White
Odor:	Odorless
Melting Point:	NA
Boiling Point:	NA

Section 3 – Physical Data (cont)	
Flammability/Flash Point:	NA
Vapor Pressure:	NA
Bulk Density:	0.9 – 1.2 g/cm^3
Solubility:	Min 14.5g/100g water @ 20 ºC
Viscosity:	NA
pH (3% solution):	≈ 10.5
Decomposition Temperature:	Self-accelerating decomposition with oxygen release starts at 50 ºC.

Section 4 – Reactivity Data	
Stability:	Stable under normal conditions
Conditions to Avoid/Incompatibility:	Acids, bases, salts of heavy metals, reducing agents, and flammable substances
Hazardous Decomposition Products:	Oxygen. Contamination with many substances will cause decomposition. The rate of decomposition increases with increasing temperature and may be very vigorous with rapid generation of oxygen and steam.

Section 5 – Regulations	
TSCA Inventory Listed:	Yes
CERCLA Hazardous Substance (40 CFR Part 302)	
Listed Substance:	*No*
Unlisted Substance:	*Yes*
SARA, Title III, Sections 313 (40 CFR Part 372) – Toxic Chemical Release Reporting: Community Right-To-Know	
Extremely Hazardous Substance:	No
WHMIS Classification:	C, D2B
Canadian Domestic Substance List:	Appears

Section 6 – Protective Measures, Storage and Handling

Technical Protective Measures

Storage:	Oxidizer. Store in a cool, well ventilated area away from all sources of ignition and out of the direct sunlight. Store in a dry location away from heat and in temperatures less than 40 °C. Keep away from incompatible materials and keep lids tightly closed. Do not store in improperly labeled containers. Protect from moisture. Do not store near combustible materials. Keep containers well sealed. Store separately from reducing materials. Avoid contamination which may lead to decomposition.
Handling:	Avoid contact with eyes, skin and clothing. Use with adequate ventilation. Do not swallow. Avoid breathing vapors, mists or dust. Do not eat, drink or smoke in the work area. Label containers and keep them tightly closed when not in use. Wash hands thoroughly after handling.

Personal Protective Equipment (PPE)

Engineering Controls:	General room ventilation is required if used indoors. Local exhaust ventilation, process enclosures or other engineering controls may be needed to maintain airborne levels below recommended exposure limits. Avoid creating dust or mists. Maintain adequate ventilation at all times. Do not use in confined areas. Keep levels below recommended exposure limits. To determine actual exposure limits, monitoring should be performed on a routine basis.
Respiratory Protection:	For many conditions, no respiratory protection is necessary; however, in dusty or unknown conditions or when exposures exceed limit values a NIOSH approved respirator should be used.
Hand Protection:	Wear chemical resistant gloves (neoprene, rubber, or PVC).

Section 6 – Protective Measures, Storage and Handling (cont)

Eye Protection:	Wear chemical safety goggles. A full face shield may be worn in lieu of safety goggles.
Skin Protection:	Try to avoid skin contact with this product. Chemical resistant gloves (neoprene, PVC or rubber) and protective clothing should be worn during use.
Other:	Eye wash station.
Protection Against Fire & Explosion:	Product is non-explosive. In case of fire, evacuate all non-essential personnel, wear protective clothing and a self-contained breathing apparatus, stay upwind of fire, and use water to spray cool fire-exposed containers.

Section 7 – Hazards Identification

Potential Health Effects

Inhalation:	Causes irritation to the respiratory tract. Symptoms may include coughing, shortness of breath, and irritations to mucous membranes, nose and throat.
Eye Contact:	Causes irritation, redness and pain.
Skin Contact:	Causes slight irritation.
Ingestion:	May be harmful if swallowed (vomiting and diarrhea).

Section 8 – Measures in Case of Accidents and Fire

After Spillage/Leakage:	Eliminate all ignition sources. Evacuate unprotected personnel and never exceed any occupational exposure limit. Shovel or sweep spilt material into plastic bags or vented containers for disposal. Do not return spilled or contaminated material to the inventory.
Extinguishing Media:	Water

First Aid

Eye Contact:	Flush eyes with running water for at least 15 minutes with eyelids held open. Seek a specialist.
Inhalation:	Remove affected person to fresh air. Seek medical attention if the effects persist.
Ingestion:	If the individual is conscious and not convulsing, give two-four cups of water to dilute the chemical and seek medical attention immediately. **Do Not** induce vomiting.

Section 8 – Measures in Case of Accidents and Fire (cont)

Skin Contact:	Wash affected areas with soap and a mild detergent and large amounts of water.

Section 9 – Accidental Release Measures

Precautions:	
Cleanup Methods:	Shovel or sweep spilt material into plastic bags or vented containers for disposal. Do not return spilled or contaminated material to the inventory.

Section 10 – Information on Toxicology

Toxicity Data	
LD50 Oral (rat):	2,400 mg/kg
LD50 Dermal (rabbit):	Min 2,000 mg/kg
LD50 Inhalation (rat):	Min 4,580 mg/kg

Section 11 – Information on Ecology

Ecology Data	
Ecotoxicological Information:	NA

Section 12 – Disposal Considerations

Waste Disposal Method	
Waste Treatment:	Dispose of in an approved waste facility operated by an authorized contactor in compliance with local regulations.
Package (Pail) Treatment:	The empty and clean containers are to be recycled or disposed of in conformity with local regulations.

Section 13 – Shipping/Transport Information

D.O.T. Shipping Name:	Oxidizing Solid, N.O.S. [A mixture of sodium percarbonate [$2Na_2CO_3 \cdot 3H2O_2$], sodium carbonate [Na_2CO_3], sodium silicate and silica gel.]
UN Number:	1479
Hazard Class:	5.1
Labels:	5.1 (Oxidizer)
Packaging Group:	III

Section 14 – Other Information

HMIS® Rating	Health – 1 (slight)	Reactivity – 1 (slight)
	Flammability – 0 (none)	Lab PPE – goggles, gloves, and lab coat

HMIS® is a registered trademark of the National Painting and Coating Association.

Section 15 – Further Information

The information contained in this document is the best available to the supplier at the time of writing, but is provided without warranty of any kind. Some possible hazards have been determined by analogy to similar classes of material. The items in this document are subject to change and clarification as more information become available. This document is intended only as a guide to the appropriate precautionary handling of the material by a properly trained person. Individuals receiving this information must exercise their independent judgment in determining its appropriateness for a particular purpose.

RegenOx® – Part B (Activator Complex)

Material Safety Data Sheet (MSDS)

Last Revised: June 4, 2010

Section 1 – Supplier Information and Material Identification

Supplier:

REGENESIS
1011 Calle Sombra
San Clemente, CA 92673
Telephone: 949.366.8000
Fax: 949.366.8090
E-mail: info@regenesis.com

Chemical Description:	A mixture of sodium silicate solution, silica gel and ferrous sulfate
Chemical Family:	Inorganic Chemicals
Trade Name:	RegenOx® – Part B (Activator Complex)
Product Use:	Used for environmental remediation of contaminated soils and groundwater

Section 2 – Chemical Information/Other Designations

CAS No.	Chemical
1344-09-8	Silicic Acid, Sodium Salt, Sodium Silicate
63231-67-4	Silica Gel
7720-78-7	Ferrous Sulfate
7732-18-5	Water

Section 3 – Physical Data

Form:	Liquid
Color:	Blue/Green
Odor:	Odorless
Melting Point:	NA
Boiling Point:	NA
Flammability/Flash Point:	NA
Vapor Pressure:	NA

Section 3 – Physical Data (cont)	
Specific Gravity	1.39 g/cm^3
Solubility:	Miscible
Viscosity:	NA
pH (3% solution):	11
Hazardous Decomposition Products:	Oxides of carbon and silicon may be formed when heated to decomposition.

Section 4 – Reactivity Data	
Stability:	Stable under normal conditions.
Conditions to Avoid:	None.
Incompatibility:	Avoid hydrogen fluoride, fluorine, oxygen difluoride, chlorine trifluoride, strong acids, strong bases, oxidizers, aluminum, fiberglass, copper, brass, zinc, and galvanized containers.

Section 5 – Regulations	
TSCA Inventory Listed:	Yes
CERCLA Hazardous Substance (40 CFR Part 302)	
Listed Substance:	*No*
Unlisted Substance:	*Yes*
SARA, Title III, Sections 302/303 (40 CFR Part 355) – Emergency Planning and Notification	
Extremely Hazardous Substance:	No
SARA, Title III, Sections 311/312 (40 CFR Part 370) – Hazardous Chemical Reporting: Community Right-To-Know	
Hazard Category:	Acute
SARA, Title III, Sections 313 (40 CFR Part 372) – Toxic Chemical Release Reporting: Community Right-To-Know	
Extremely Hazardous Substance:	No

Section 6 – Protective Measures, Storage and Handling

Technical Protective Measures

Storage:	Keep in a tightly closed container (steel or plastic) and store in a cool, well ventilated area away from all incompatible materials (acids, reactive metals, and ammonium salts). Store in a dry location away from heat above 60 degrees C and colder than 10 degrees C. Do not store in aluminum, fiberglass, copper, brass, zinc or galvanized containers.
Handling:	Avoid contact with eyes, skin and clothing. Avoid breathing spray mist. Use with adequate ventilation. Do not use product if it is brownish-yellow in color.

Personal Protective Equipment (PPE)

Engineering Controls:	General room ventilation is required if used indoors. Local exhaust ventilation, process enclosures or other engineering controls may be needed to maintain airborne levels below recommended exposure limits. Safety shower and eyewash station should be within direct access.
Respiratory Protection:	Use NIOSH-approved dust and mist respirator where spray mist exists. Respirators should be used in accordance with 29 CFR 1910.134.
Hand Protection:	Wear chemical resistant gloves.
Eye Protection:	Wear chemical safety goggles. A full face shield may be worn in lieu of safety goggles.
Skin Protection:	Try to avoid skin contact with this product. Gloves and protective clothing should be worn during use.
Other:	
Protection Against Fire & Explosion:	Product is non-explosive and non-combustible.

Section 7 – Hazards Identification

Potential Health Effects

Inhalation:	Causes irritation to the respiratory tract. Symptoms may include coughing, shortness of breath, and irritations to mucous membranes, nose and throat.
Eye Contact:	Causes irritation, redness and pain.
Skin Contact:	Causes irritation. Symptoms include redness, itching and pain.
Ingestion:	May cause irritation to mouth, esophagus, and stomach.

Section 8 – Measures in Case of Accidents and Fire

After Spillage/Leakage (small):	Mop up and neutralize liquid, then discharge to sewer in accordance with local, state and federal regulations.
After Spillage/Leakage (large):	Keep unnecessary personnel away; isolate hazard area and do not allow entrance into the affected area. Do not touch or walk through spilled material. Stop leak if possible without risking injury. Prevent runoff from entering into storm sewers and ditches that lead to natural waterways. Isolate the material if at all possible. Sand or earth may be used to contain the spill. If containment is not possible, neutralize the contaminated area and flush with large quantities of water.
Extinguishing Media:	Material is compatible with all extinguishing media.
Further Information:	

First Aid

Eye Contact:	Flush eyes with running water for at least 15 minutes with eyelids held open. Seek a specialist.
Inhalation:	Remove affected person to fresh air. Give artificial respiration if individual is not breathing. If breathing is difficult, give oxygen. Seek medical attention if the effects persist.
Ingestion:	If the individual is conscious and not convulsing, give two-four cups of water to dilute the chemical and seek medical attention immediately. **DO NOT** induce vomiting.
Skin Contact:	Wash affected areas with soap and a mild detergent and large amounts of water. Remove contaminated clothing and shoes.

Section 9 – Accidental Release Measures

Precautions:

PPE:	Wear chemical goggles, body-covering protective clothing, chemical resistant gloves, and rubber boots (see Section 6).
Environmental Hazards:	Sinks and mixes with water. High pH of this material may be harmful to aquatic life. Only water will evaporate from a spill of this material.
Cleanup Methods:	Pick-up and place in an appropriate container for reclamation or disposal. US regulations (CERCLA) require reporting spills and releases to soil, water and air in excess of reportable quantities.

Section 10 – Information on Toxicology

Toxicity Data

Sodium Silicate:	When tested for primary eye irritation potential according to OECD Guidelines, Section 405, a similar sodium silicate solution produced corneal, iridal and conjunctival irritation. Some eye irritation was still present 14 days after treatment, although the average primary irritation score has declined from 29.7 after 1 day to 4.0 after 14 days. When tested for primary skin irritation potential, a similar sodium silicate solution produced irritation with a primary irritation index of 3 to abraded skin and 0 to intact skin. Human experience confirms that irritation occurs when sodium silicates get on clothes at the collar, cuffs, or other areas where abrasion may exist. The acute oral toxicity of this product has not been tested.
Ferrous Sulfate:	LD50 Oral (rat): 319 mg/kg not a suspected carcinogen.

Section 11 – Information on Ecology

Ecology Data

Ecotoxicological Information:	Based on 100% solid sodium silicate, a 96 hour median tolerance for fish of 2,320 mg/l; a 96 hour median tolerance for water fleas of 247 mg/L; a 96 hour median tolerance for snail eggs of 632 mg/L; and a 96 hour median tolerance for Amphipoda of 160 mg/L.

Section 12 – Disposal Considerations

Waste Disposal Method

Waste Treatment:	Neutralize and landfill solids in an approved waste facility operated by an authorized contactor in compliance with local regulations.
Package (Pail) Treatment:	The empty and clean containers are to be recycled or disposed of in conformity with local regulations.

Section 13 – Shipping/Transport Information

D.O.T.	This product is not regulated as a hazardous material so there are no restrictions.

Section 14 – Other Information

HMIS® Rating	Health – 2 (moderate)	Reactivity – 0 (none)
	Flammability – 0 (none)	Lab PPE – goggles, gloves, and lab coat
	Contact – 1 (slight)	

HMIS® is a registered trademark of the National Painting and Coating Association.

Section 15 – Further Information

The information contained in this document is the best available to the supplier at the time of writing, but is provided without warranty of any kind. Some possible hazards have been determined by analogy to similar classes of material. The items in this document are subject to change and clarification as more information become available. This document is intended only as a guide to the appropriate precautionary handling of the material by a properly trained person. Individuals receiving this information must exercise their independent judgment in determining its appropriateness for a particular purpose.

SAFETY DATA SHEET

SILVER

Section 1. Identification

GHS product identifier	:	SILVER
Chemical name	:	Mixture
CAS number	:	Mixture
Other means of identification	:	CC01054908
Product type	:	liquid

Relevant identified uses of the substance or mixture and uses advised against

Product use	:	Industrial applications. Plastics.

Supplier's details	:	**POLYONE CORPORATION** ColorMatrix Group Inc. 680 North Rocky River Drive, Berea, Ohio, 44017-1628, USA +1 216 622 0100
Emergency telephone number (with hours of operation)	:	**CHEMTREC 1-800-424-9300 (24hrs for spill, leak, fire, exposure or accident).**

Section 2. Hazards identification

This mixture has not been evaluated as a whole for health effects. Information provided on health effects of this product is based on the individual components. However, some vapors or contaminants may be released upon heating and the end-user (fabricator) must take the necessary precautions (mechanical ventilation, respiratory protection, etc.) to protect employees from exposure. See sections 8 and 11 for special precautions. After handling, always wash hands thoroughly with soap and water.

OSHA/HCS status	:	This material is considered hazardous by the OSHA Hazard Communication Standard (29 CFR 1910.1200).
Classification of the substance or mixture	:	SKIN CORROSION/IRRITATION - Category 2

GHS label elements

Hazard pictograms :

Signal word : Warning
Hazard statements : Causes skin irritation.

Precautionary statements

General : Not applicable.
Prevention : Wear protective gloves. Wash hands thoroughly after handling.
Response : IF ON SKIN: Wash with plenty of soap and water. Take off contaminated clothing. Wash contaminated clothing before reuse. If skin irritation occurs: Get medical attention.
Storage : Not applicable.
Disposal : Not applicable.
Supplemental label elements : None known.
Hazards not otherwise classified : None known.

Section 3. Composition/information on ingredients

Substance/mixture : Mixture
Chemical name : Mixture
Other means of identification : CC01054908

CAS number/other identifiers

Ingredient name	%	CAS number
Miscellaneous Compounds Distillates, petroleum, hydrotreated middle	10 - 30	Not available.
Titanium dioxide	10 - 30	13463-67-7

Any concentration shown as a range is to protect confidentiality or is due to batch variation.

There are no additional ingredients present which, within the current knowledge of the supplier and in the concentrations applicable, are classified as hazardous to health or the environment and hence require reporting in this section.

Occupational exposure limits, if available, are listed in Section 8.

Section 4. First aid measures

Description of necessary first aid measures

Eye contact	:	Immediately flush eyes with plenty of water, occasionally lifting the upper and lower eyelids. Check for and remove any contact lenses. Continue to rinse for at least 10 minutes. Get medical attention.
Inhalation	:	Remove victim to fresh air and keep at rest in a position comfortable for breathing. If not breathing, if breathing is irregular or if respiratory arrest occurs, provide artificial respiration or oxygen by trained personnel. It may be dangerous to the person providing aid to give mouth-to-mouth resuscitation. Get medical attention if adverse health effects persist or are severe. If unconscious, place in recovery position and get medical attention immediately. Maintain an open airway. Loosen tight clothing such as a collar, tie, belt or waistband.
Skin contact	:	Flush contaminated skin with plenty of water. Remove contaminated clothing and shoes. Continue to rinse for at least 10 minutes. Get medical attention. Wash clothing before reuse. Clean shoes thoroughly before reuse.
Ingestion	:	Wash out mouth with water. Remove dentures if any. Remove victim to fresh air and keep at rest in a position comfortable for breathing. If material has been swallowed and the exposed person is conscious, give small quantities of water to drink. Stop if the exposed person feels sick as vomiting may be dangerous. Do not induce vomiting unless directed to do so by medical personnel. If vomiting occurs, the head should be kept low so that vomit does not enter the lungs. Get medical attention if adverse health effects persist or are severe. Never give anything by mouth to an unconscious person. If unconscious, place in recovery position and get medical attention immediately. Maintain an open airway. Loosen tight clothing such as a collar, tie, belt or waistband.

Most important symptoms/effects, acute and delayed

Potential acute health effects

Eye contact	:	Causes serious eye irritation.
Inhalation	:	No known significant effects or critical hazards.
Skin contact	:	Causes skin irritation.
Ingestion	:	Irritating to mouth, throat and stomach.

Over-exposure signs/symptoms

Eye contact	:	Adverse symptoms may include the following: pain or irritation

watering
redness

Inhalation	:	No specific data.
Skin contact	:	Adverse symptoms may include the following: irritation redness
Ingestion	:	No specific data.

Indication of immediate medical attention and special treatment needed, if necessary

Notes to physician	:	Treat symptomatically. Contact poison treatment specialist immediately if large quantities have been ingested or inhaled.
Specific treatments	:	No specific treatment.
Protection of first-aiders	:	No action shall be taken involving any personal risk or without suitable training. It may be dangerous to the person providing aid to give mouth-to-mouth resuscitation.

See toxicological information (Section 11)

Section 5. Fire-fighting measures

Extinguishing media

Suitable extinguishing media	:	In case of fire, use water spray (fog), foam, dry chemical or CO_2.
Unsuitable extinguishing media	:	None known.
Specific hazards arising from the chemical	:	In a fire or if heated, a pressure increase will occur and the container may burst.
Hazardous thermal decomposition products	:	Decomposition products may include the following materials: carbon dioxide carbon monoxide metal oxide/oxides
Special protective actions for fire-fighters	:	Promptly isolate the scene by removing all persons from the vicinity of the incident if there is a fire. No action shall be taken involving any personal risk or without suitable training.
Special protective equipment for fire-fighters	:	Fire-fighters should wear appropriate protective equipment and self-contained breathing apparatus (SCBA) with a full face-piece operated in positive pressure mode.

Section 6. Accidental release measures

Personal precautions, protective equipment and emergency procedures

For non-emergency personnel	:	No action shall be taken involving any personal risk or without suitable training. Evacuate surrounding areas. Keep unnecessary and unprotected personnel from entering. Do not touch or walk through spilled material. Avoid breathing vapor or mist. Provide adequate ventilation. Wear appropriate respirator when ventilation is inadequate. Put on appropriate personal protective equipment.
For emergency responders	:	If specialised clothing is required to deal with the spillage, take note of any information in Section 8 on suitable and unsuitable materials. See also the information in "For non-emergency personnel".
Environmental precautions	:	Avoid dispersal of spilled material and runoff and contact with soil, waterways, drains and sewers. Inform the relevant authorities if the product has caused environmental pollution (sewers, waterways, soil or air).

Methods and materials for containment and cleaning up

Small spill	:	Stop leak if without risk. Move containers from spill area. Dilute with water and mop up if water-soluble. Alternatively, or if water-insoluble, absorb with an inert dry material and place in an appropriate waste disposal container. Dispose of via a licensed waste disposal contractor.
Large spill	:	Stop leak if without risk. Move containers from spill area. Approach release from upwind. Prevent entry into sewers, water courses, basements or confined areas. Wash spillages into an effluent treatment plant or proceed as follows. Contain and collect spillage with non-combustible, absorbent material e.g. sand, earth, vermiculite or diatomaceous earth and place in container for disposal according to local regulations (see Section 13). Dispose of via a licensed waste disposal contractor. Contaminated absorbent material may pose the same hazard as the spilled product. Note: see Section 1 for emergency contact information and Section 13 for waste disposal.

Section 7. Handling and storage

Precautions for safe handling

Protective measures	:	Put on appropriate personal protective equipment (see Section 8). Do not ingest. Avoid contact with eyes, skin and clothing. Avoid breathing vapor or mist. Keep in the original container or an approved alternative made from a compatible material, kept tightly closed when not in use. Empty containers retain product residue and can be hazardous. Do not reuse container.

Advice on general occupational hygiene	:	Eating, drinking and smoking should be prohibited in areas where this material is handled, stored and processed. Workers should wash hands and face before eating, drinking and smoking. Remove contaminated clothing and protective equipment before entering eating areas. See also Section 8 for additional information on hygiene measures.
Conditions for safe storage, including any incompatibilities	:	Store in accordance with local regulations. Store in original container protected from direct sunlight in a dry, cool and well-ventilated area, away from incompatible materials (see Section 10) and food and drink. Keep container tightly closed and sealed until ready for use. Containers that have been opened must be carefully resealed and kept upright to prevent leakage. Do not store in unlabeled containers. Use appropriate containment to avoid environmental contamination.

Section 8. Exposure controls/personal protection

Control parameters

Occupational exposure limits

Ingredient name	Exposure limits
Titanium dioxide	**OSHA PEL 1989 (1989-03-01)** PEL: Permissible Exposure Level 10 mg/m3 Form: Total dust **OSHA PEL (1993-06-30)** PEL: Permissible Exposure Level 15 mg/m3 Form: Total dust **ACGIH TLV (1996-05-18)** TLV-TWA: Threshold Limit Value - Time weighted average PEL: Permissible Exposure Level 10 mg/m3

Appropriate engineering controls	:	Good general ventilation should be sufficient to control worker exposure to airborne contaminants.
Environmental exposure controls	:	Emissions from ventilation or work process equipment should be checked to ensure they comply with the requirements of environmental protection legislation. In some cases, fume scrubbers, filters or engineering modifications to the process equipment will be necessary to reduce emissions to acceptable levels.

Individual protection measures

Hygiene measures	:	Wash hands, forearms and face thoroughly after handling chemical products, before eating, smoking and using the lavatory and at the end of the working period. Appropriate techniques should be used to remove potentially contaminated clothing. Wash contaminated

clothing before reusing. Ensure that eyewash stations and safety showers are close to the workstation location.

Eye/face protection : Safety eyewear complying with an approved standard should be used when a risk assessment indicates this is necessary to avoid exposure to liquid splashes, mists, gases or dusts. If contact is possible, the following protection should be worn, unless the assessment indicates a higher degree of protection: chemical splash goggles.

Skin protection

Hand protection : Chemical-resistant, impervious gloves complying with an approved standard should be worn at all times when handling chemical products if a risk assessment indicates this is necessary. Considering the parameters specified by the glove manufacturer, check during use that the gloves are still retaining their protective properties. It should be noted that the time to breakthrough for any glove material may be different for different glove manufacturers. In the case of mixtures, consisting of several substances, the protection time of the gloves cannot be accurately estimated.

Body protection : Personal protective equipment for the body should be selected based on the task being performed and the risks involved and should be approved by a specialist before handling this product.

Other skin protection : Appropriate footwear and any additional skin protection measures should be selected based on the task being performed and the risks involved and should be approved by a specialist before handling this product.

Respiratory protection : Use a properly fitted, air-purifying or air-fed respirator complying with an approved standard if a risk assessment indicates this is necessary. Respirator selection must be based on known or anticipated exposure levels, the hazards of the product and the safe working limits of the selected respirator.

Section 9. Physical and chemical properties

Appearance

Physical state : liquid [liquid]
Color : SILVER
Odor : Faint odor.
Odor threshold : Not available.
pH : Not available.
Melting point : Not available.
Boiling point : Not available.
Flash point : Not available.
Burning time : Not available.

Burning rate	:	Not available.
Evaporation rate	:	Not available.
Flammability (solid, gas)	:	Not available.
Lower and upper explosive (flammable) limits	:	**Lower:** Not available. **Upper:** Not available.
Vapor pressure	:	Not available.
Vapor density	:	Not available.
Relative density	:	Not available.
Solubility	:	Not available.
Solubility in water	:	insoluble in water.
Partition coefficient: n-octanol/water	:	Not available.
Auto-ignition temperature	:	Not available.
Decomposition temperature	:	Not available.
SADT	:	Not available.
Viscosity	:	**Dynamic:** Not available. **Kinematic:** Not available.

Section 10. Stability and reactivity

Reactivity	:	No specific test data related to reactivity available for this product or its ingredients.
Chemical stability	:	Stable under recommended storage and handling conditions (see Section 7).
Possibility of hazardous reactions	:	Under normal conditions of storage and use, hazardous reactions will not occur.
Conditions to avoid	:	Keep away from extreme heat and oxidizing agents.
Incompatible materials	:	Keep away from strong acids. Oxidizer.
Hazardous decomposition products	:	Under normal conditions of storage and use, hazardous decomposition products should not be produced.

Section 11. Toxicological information

This mixture has not been evaluated as a whole for health effects. Exposure effects listed are based on existing health data for the individual components which comprise the mixture.

Information on toxicological effects

Acute toxicity

Product/ingredient name	Result	Species	Dose	Exposure
Titanium dioxide				

	LC50 Inhalation	Rat - Male	6.82 Mg/l	4 h
	LD50 Dermal	Rabbit	> 5,000 mg/kg	-

Conclusion/Summary : Mixture.Not fully tested.

Irritation/Corrosion

Conclusion/Summary
Skin : Mixture.Not fully tested.
Eyes : Mixture.Not fully tested.
Respiratory : Mixture.Not fully tested.

Sensitization

Conclusion/Summary
Skin : Mixture.Not fully tested.
Respiratory : Mixture.Not fully tested.

Mutagenicity

Conclusion/Summary : Mixture.Not fully tested.

Carcinogenicity

Conclusion/Summary : Mixture.Not fully tested.

Classification

Product/ingredient name	OSHA	IARC	NTP
Titanium dioxide		2B	

Reproductive toxicity

Conclusion/Summary : Mixture.Not fully tested.

Teratogenicity

Conclusion/Summary : Mixture.Not fully tested.

Specific target organ toxicity (single exposure)
Not available.

Specific target organ toxicity (repeated exposure)
Not available.

Aspiration hazard

Product/ingredient name	Result

Miscellaneous Compounds Distillates, petroleum, hydrotreated middle	ASPIRATION HAZARD - Category 1

Information on the likely routes of exposure : Not available.

Potential acute health effects

Eye contact : Causes serious eye irritation.
Inhalation : No known significant effects or critical hazards.
Skin contact : Causes skin irritation.
Ingestion : Irritating to mouth, throat and stomach.

Symptoms related to the physical, chemical and toxicological characteristics

Eye contact : Adverse symptoms may include the following:
pain or irritation
watering
redness
Inhalation : No specific data.
Skin contact : Adverse symptoms may include the following:
irritation
redness
Ingestion : No specific data.

Delayed and immediate effects and also chronic effects from short and long term exposure

Short term exposure

Potential immediate effects : Not available.
Potential delayed effects : Not available.

Long term exposure

Potential immediate effects : Not available.
Potential delayed effects : Not available.

Potential chronic health effects

Conclusion/Summary : Mixture.Not fully tested.

General : No known significant effects or critical hazards.
Carcinogenicity : No known significant effects or critical hazards.
Mutagenicity : No known significant effects or critical hazards.
Teratogenicity : No known significant effects or critical hazards.

Developmental effects : No known significant effects or critical hazards.
Fertility effects : No known significant effects or critical hazards.

Numerical measures of toxicity

Acute toxicity estimates

Route	ATE value
Inhalation (dusts and mists)	8.073 mg/l

Section 12. Ecological information

Toxicity

Product/ingredient name	Result	Species	Exposure
Titanium dioxide			
	Acute LC50 > 1,000,000 µg/l Marine water	Fish - Mummichog	96 h
	Acute LC50 > 1,000 mg/l Fresh water	Fish - Fathead minnow	96 h
	Acute LC50 13 mg/l Fresh water	Aquatic invertebrates. Water flea	48 h
	Acute LC50 6.5 mg/l Fresh water	Aquatic invertebrates. Water flea	48 h
	Acute EC50 19.3 mg/l Fresh water	Aquatic invertebrates. Water flea	48 h
	Acute EC50 27.8 mg/l Fresh water	Aquatic invertebrates. Water flea	48 h
	Acute EC50 35.306 mg/l Fresh water	Aquatic invertebrates. Water flea	48 h

Conclusion/Summary : Not available.

Persistence and degradability

Conclusion/Summary : Not available.

Bioaccumulative potential

Product/ingredient name	LogPow	BCF	Potential
Titanium dioxide		352.00	low

Mobility in soil

Soil/water partition coefficient (KOC)	:	Not available.
Other adverse effects	:	No known significant effects or critical hazards.

Section 13. Disposal considerations

Disposal methods : The generation of waste should be avoided or minimized wherever possible. Disposal of this product, solutions and any by-products should at all times comply with the requirements of environmental protection and waste disposal legislation and any regional local authority requirements. Dispose of surplus and non-recyclable products via a licensed waste disposal contractor. Waste should not be disposed of untreated to the sewer unless fully compliant with the requirements of all authorities with jurisdiction. Waste packaging should be recycled. Incineration or landfill should only be considered when recycling is not feasible. This material and its container must be disposed of in a safe way. Care should be taken when handling emptied containers that have not been cleaned or rinsed out. Empty containers or liners may retain some product residues. Avoid dispersal of spilled material and runoff and contact with soil, waterways, drains and sewers.

United States - RCRA Acute hazardous waste "P" List: Not listed

United States - RCRA Toxic hazardous waste "U" List: Not listed

Section 14. Transport information

U.S. DOT Classification	:	Not regulated for transportation.
ICAO/IATA	:	Not classified as dangerous good under transport regulations.
IMO/IMDG (maritime)	:	Not classified as dangerous good under transport regulations.

Section 15. Regulatory information

U.S. Federal regulations : **United States - TSCA 12(b) - Chemical export notification:** None of the components are listed.
United States - TSCA 4(a) - Final Test Rules: Not listed
United States - TSCA 4(a) - ITC Priority list: Not listed
United States - TSCA 4(a) - Proposed test rules: Not listed

United States - TSCA 4(f) - Priority risk review: Not listed
United States - TSCA 5(a)2 - Final significant new use rules: Not listed
United States - TSCA 5(a)2 - Proposed significant new use rules: Not listed
United States - TSCA 5(e) - Substances consent order: Not listed
United States - TSCA 6 - Final risk management: Not listed
United States - TSCA 6 - Proposed risk management: Not listed
United States - TSCA 8(a) - Chemical risk rules: Not listed
United States - TSCA 8(a) - Dioxin/Furane precusor: Not listed
United States - TSCA 8(a) - Chemical Data Reporting (CDR): Not determined
United States - TSCA 8(a) - Preliminary assessment report (PAIR): Not listed
United States - TSCA 8(c) - Significant adverse reaction (SAR): Not listed
United States - TSCA 8(d) - Health and safety studies: Not listed
United States - EPA Clean water act (CWA) section 307 - Priority pollutants: Listed **Chromium (III) oxide**

United States - EPA Clean water act (CWA) section 311 - Hazardous substances: Not listed
United States - EPA Clean air act (CAA) section 112 - Accidental release prevention - Flammable substances: Not listed
United States - EPA Clean air act (CAA) section 112 - Accidental release prevention - Toxic substances: Not listed
United States - Department of commerce - Precursor chemical: Not listed

Clean Air Act Section 112(b) Hazardous Air Pollutants (HAPs)	:	Not listed
Clean Air Act Section 602 Class I Substances	:	Not listed
Clean Air Act Section 602 Class II Substances	:	Not listed
DEA List I Chemicals (Precursor Chemicals)	:	Not listed
DEA List II Chemicals (Essential Chemicals)	:	Not listed

US. EPA CERCLA Hazardous Substances (40 CFR 302)

not applicable

SARA 311/312

Classification : Immediate (acute) health hazard

Composition/information on ingredients

Name	%	Classification
Miscellaneous Compounds Distillates, petroleum, hydrotreated middle	10 - 30	AH
Titanium dioxide	10 - 30	CH

SARA 313

	Product name	CAS number	%
Form R - Reporting requirements	Aluminum	7429-90-5	1 - 5
Supplier notification	Aluminum	7429-90-5	1 - 5

SARA 313 notifications must not be detached from the SDS and any copying and redistribution of the SDS shall include copying and redistribution of the notice attached to copies of the SDS subsequently redistributed.

State regulations

Massachusetts : The following components are listed:
Mica
Titanium dioxide
Aluminum

New York : None of the components are listed.

New Jersey : The following components are listed:
Mica
Titanium dioxide
Aluminum

Pennsylvania : The following components are listed:
Titanium dioxide
Aluminum

California Prop. 65

WARNING: This product contains a chemical known to the State of California to cause cancer.

United States inventory (TSCA 8b) : All components are listed or exempted.

Canada inventory : All components are listed or exempted.

International regulations

International lists	:	**Australia inventory (AICS):** Not determined. **Taiwan inventory (CSNN):** Not determined. **Malaysia Inventory (EHS Register):** Not determined. **EINECS:** All components are listed or exempted. **Japan inventory:** Not determined. **China inventory (IECSC):** All components are listed or exempted. **Korea inventory:** All components are listed or exempted. **New Zealand Inventory of Chemicals (NZIoC):** Not determined. **Philippines inventory (PICCS):** All components are listed or exempted.
Chemical Weapons Convention List Schedule I Chemicals	:	Not listed
Chemical Weapons Convention List Schedule II Chemicals	:	Not listed
Chemical Weapons Convention List Schedule III Chemicals	:	Not listed

Section 16. Other information

History

Date of printing	:	06/04/2015
Date of issue/Date of revision	:	06/03/2015
Date of previous issue	:	11/20/2014
Version	:	1.1
Key to abbreviations	:	ATE = Acute Toxicity Estimate BCF = Bioconcentration Factor GHS = Globally Harmonized System of Classification and Labelling of Chemicals IATA = International Air Transport Association IBC = Intermediate Bulk Container IMDG = International Maritime Dangerous Goods LogPow = logarithm of the octanol/water partition coefficient MARPOL 73/78 = International Convention for the Prevention of Pollution From Ships, 1973 as modified by the Protocol of 1978. ("Marpol" = marine pollution) UN = United Nations
References	:	Not available.

Notice to reader

To the best of our knowledge, the information contained herein is accurate. However, neither the above-named supplier, nor any of its subsidiaries, assumes any liability whatsoever for the accuracy or completeness of the information contained herein. Final determination of suitability of any material is the sole responsibility of the user. All materials may present unknown hazards and should be used with caution.

Although certain hazards are described herein, we cannot guarantee that these are the only hazards that exist. Particularly this information may not be valid for such material used in conjunction with any other materials or in any process, unless specified in the text.

SAFETY DATA SHEET

1. Identification

Product identifier: Trichloroethylene

Other means of identification
Product No.: 9464, 8600, 9458, 9454

Recommended use and restriction on use

Recommended use: Not available.
Restrictions on use: Not known.

Manufacturer/Importer/Supplier/Distributor Information

Manufacturer

Company Name:	Avantor Performance Materials, Inc.
Address:	3477 Corporate Parkway, Suite 200 Center Valley, PA 18034
Telephone:	
	Customer Service: 855-282-6867
Fax:	
Contact Person:	Environmental Health & Safety
e-mail:	info@avantormaterials.com

Emergency telephone number:
24 Hour Emergency: 908-859-2151

Chemtrec: 800-424-9300

2. Hazard(s) identification

Hazard Classification

Health Hazards

Skin Corrosion/Irritation	Category 2
Serious Eye Damage/Eye Irritation	Category 2A
Germ Cell Mutagenicity	Category 2
Carcinogenicity	Category 1B
Specific Target Organ Toxicity - Single Exposure	Category 3

Environmental Hazards

Chronic hazards to the aquatic environment	Category 3

Label Elements

Hazard Symbol:

Signal Word: Danger

Hazard Statement: May cause cancer.
Suspected of causing genetic defects.
Causes serious eye irritation.
Causes skin irritation.
Harmful to aquatic life with long lasting effects.

Precautionary Statement

Prevention: Obtain special instructions before use. Do not handle until all safety precautions have been read and understood. Wear protective gloves/protective clothing/eye protection/face protection. Wash hands thoroughly after handling. Avoid breathing dust/fume/gas/mist/vapors/spray. Avoid release to the environment.

Response: IF IN EYES: Rinse cautiously with water for several minutes. Remove contact lenses, if present and easy to do. Continue rinsing. If eye irritation persists: Get medical advice/attention. IF ON SKIN: Wash with plenty of soap and water. Take off contaminated clothing and wash before reuse. Call a POISON CENTER or doctor/physician if you feel unwell. IF INHALED: Remove victim to fresh air and keep at rest in a position comfortable for breathing.

Storage: Store locked up. Store in a well-ventilated place. Keep container tightly closed.

Disposal: Dispose of contents/container to an appropriate treatment and disposal facility in accordance with applicable laws and regulations, and product characteristics at time of disposal.

Other hazards which do not result in GHS classification: None.

3. Composition/information on ingredients

Substances

Chemical Identity	Common name and synonyms	CAS number	Content in percent (%)*
TRICHLOROETHYLENE		79-01-6	99 - 100%

* All concentrations are percent by weight unless ingredient is a gas. Gas concentrations are in percent by volume.

4. First-aid measures

General information: Get medical advice/attention if you feel unwell. Show this safety data sheet to the doctor in attendance.

Ingestion: Rinse mouth. Get medical attention if symptoms occur. Do not induce vomiting without advice from poison control center. If vomiting occurs, keep head low so that stomach content doesn't get into the lungs.

Inhalation: Move to fresh air. Get medical attention if symptoms persist. If breathing stops, provide artificial respiration.

Skin Contact: Immediately flush with plenty of water for at least 15 minutes while removing contaminated clothing and shoes. Get medical attention if irritation persists after washing. Wash contaminated clothing before reuse. Destroy or thoroughly clean contaminated shoes.

Eye contact: Immediately flush with plenty of water for at least 15 minutes. If easy to do, remove contact lenses. Get medical attention if irritation persists after washing.

Most important symptoms/effects, acute and delayed

Symptoms: Irritating to eyes, respiratory system and skin.

Indication of immediate medical attention and special treatment needed

Treatment: Treat symptomatically. Symptoms may be delayed.

5. Fire-fighting measures

General Fire Hazards: In case of fire and/or explosion do not breathe fumes.

Suitable (and unsuitable) extinguishing media

Suitable extinguishing media: Use fire-extinguishing media appropriate for surrounding materials.

Unsuitable extinguishing media: Do not use water jet as an extinguisher, as this will spread the fire.

Specific hazards arising from the chemical: Contact with metals may evolve flammable hydrogen gas. Fire may produce irritating, corrosive and/or toxic gases.

Special protective equipment and precautions for firefighters

Special fire fighting procedures: Move containers from fire area if you can do so without risk. Use water spray to keep fire-exposed containers cool. Cool containers exposed to flames with water until well after the fire is out.

Special protective equipment for fire-fighters: Firefighters must use standard protective equipment including flame retardant coat, helmet with face shield, gloves, rubber boots, and in enclosed spaces, SCBA.

6. Accidental release measures

Personal precautions, protective equipment and emergency procedures: Keep unauthorized personnel away. Use personal protective equipment. See Section 8 of the MSDS for Personal Protective Equipment. Ventilate closed spaces before entering them. Do not touch damaged containers or spilled material unless wearing appropriate protective clothing.

Methods and material for containment and cleaning up: Absorb spill with vermiculite or other inert material, then place in a container for chemical waste. Clean surface thoroughly to remove residual contamination. Dike far ahead of larger spill for later recovery and disposal.

Notification Procedures: Dike for later disposal. Prevent entry into waterways, sewer, basements or confined areas. Stop the flow of material, if this is without risk. Inform authorities if large amounts are involved.

Environmental Precautions: Do not contaminate water sources or sewer. Prevent further leakage or spillage if safe to do so. Avoid discharge into drains, water courses or onto the ground.

7. Handling and storage

Precautions for safe handling: Use personal protective equipment as required. Do not breathe mist or vapor. Do not taste or swallow. Do not eat, drink or smoke when using the product. Use only with adequate ventilation. Wash hands thoroughly after handling. See Section 8 of the MSDS for Personal Protective Equipment. Avoid contact with eyes. Avoid contact with skin. Obtain special instructions before use. Do not handle until all safety precautions have been read and understood. Wear protective gloves/protective clothing/eye protection/face protection. Avoid breathing dust/fume/gas/mist/vapors/spray. Wash contaminated clothing before reuse.

Conditions for safe storage, including any incompatibilities: Store locked up. Keep in a cool, well-ventilated place. Store in a dry place.

8. Exposure controls/personal protection

Control Parameters

Occupational Exposure Limits

Chemical Identity	Type	Exposure Limit Values	Source
TRICHLOROETHYLENE	TWA	10 ppm	US. ACGIH Threshold Limit Values (2011)
	STEL	25 ppm	US. ACGIH Threshold Limit Values (2011)
	REL	25 ppm	US. NIOSH: Pocket Guide to Chemical Hazards (2010)
	TWA	50 ppm 270 mg/m3	US. OSHA Table Z-1-A (29 CFR 1910.1000) (1989)
	STEL	200 ppm 1,080 mg/m3	US. OSHA Table Z-1-A (29 CFR 1910.1000) (1989)
	TWA	100 ppm	US. OSHA Table Z-2 (29 CFR 1910.1000) (02 2006)
	Ceiling	200 ppm	US. OSHA Table Z-2 (29 CFR 1910.1000) (02 2006)
	MAX. CONC	300 ppm	US. OSHA Table Z-2 (29 CFR 1910.1000) (02 2006)
	AN ESL	54 µg/m3	US. Texas. Effects Screening Levels (Texas Commission on Environmental Quality) (12 2010)

Biological Limit Values

Chemical Identity	Exposure Limit Values	Source
TRICHLOROETHYLENE (Trichloroacetic acid: Sampling time: End of shift at end of work week.)	15 mg/l (Urine)	ACGIH BEL (03 2013)
TRICHLOROETHYLENE (Trichloroethanol, without hydrolysis: Sampling time: End of shift at end of work week.)	0.5 mg/l (Blood)	ACGIH BEL (03 2013)

Appropriate Engineering Controls No data available.

Individual protection measures, such as personal protective equipment

General information: Good general ventilation (typically 10 air changes per hour) should be used. Ventilation rates should be matched to conditions. If applicable, use process enclosures, local exhaust ventilation, or other engineering controls to maintain airborne levels below recommended exposure limits. If exposure limits have not been established, maintain airborne levels to an acceptable level. An eye wash and safety shower must be available in the immediate work area.

Eye/face protection: Wear safety glasses with side shields (or goggles) and a face shield.

Skin Protection

Hand Protection: Chemical resistant gloves

Other: Wear suitable protective clothing.

Respiratory Protection: In case of inadequate ventilation use suitable respirator.

Hygiene measures: Provide eyewash station and safety shower. Observe good industrial hygiene practices. Wash hands before breaks and immediately after handling the product. Do not eat, drink or smoke when using the product. Wash contaminated clothing before reuse.

9. Physical and chemical properties

Appearance

Physical state:	Liquid
Form:	Liquid
Color:	Colorless
Odor:	Ether-like odor
Odor threshold:	No data available.
pH:	No data available.
Melting point/freezing point:	-84.7 °C
Initial boiling point and boiling range:	87.2 °C
Flash Point:	Not applicable
Evaporation rate:	No data available.
Flammability (solid, gas):	No data available.
Upper/lower limit on flammability or explosive limits	
Flammability limit - upper (%):	10.5 %(V) 90 %(V)
Flammability limit - lower (%):	8 %(V) 12.5 %(V)
Explosive limit - upper (%):	No data available.
Explosive limit - lower (%):	No data available.
Vapor pressure:	9.2 kPa (25 °C)
Vapor density:	4.53 AIR=1
Relative density:	1.47 (20 °C)
Solubility(ies)	
Solubility in water:	1 g/l (20 °C)
Solubility (other):	acetone: Soluble ethanol: Soluble
Partition coefficient (n-octanol/water):	2.61
Auto-ignition temperature:	420 °C
Decomposition temperature:	No data available.
Viscosity:	No data available.

Other information

Molecular weight: 131.39 g/mol (C_2HCl_3)

10. Stability and reactivity

Reactivity: No dangerous reaction known under conditions of normal use.

Chemical Stability:	Material is stable under normal conditions.
Possibility of Hazardous Reactions:	Hazardous polymerization does not occur.
Conditions to Avoid:	Heat, sparks, flames. Light. Moisture. Contact with incompatible materials.
Incompatible Materials:	Strong oxidizing agents. Alkalies. Caustics. Chemically active metals.
Hazardous Decomposition Products:	By heating and fire, toxic vapors/gases may be formed. Oxides of Carbon. Phosgene.

11. Toxicological information

Information on likely routes of exposure

Ingestion:	May be harmful if swallowed.
Inhalation:	May be harmful if inhaled.
Skin Contact:	Causes skin irritation.
Eye contact:	Causes serious eye irritation.

Information on toxicological effects

Acute toxicity (list all possible routes of exposure)

Oral
Product: LD 50 (Rat): 4,920 mg/kg

Dermal
Product: No data available.

Inhalation
Product: LC 50 (Rat, 4 h): 12000 ppm

Repeated Dose Toxicity
Product: No data available.

Skin Corrosion/Irritation
Product: Causes skin irritation.

Serious Eye Damage/Eye Irritation
Product: Causes serious eye irritation.

Respiratory or Skin Sensitization
Product: Not a skin sensitizer.

Carcinogenicity
Product: May cause cancer.

IARC Monographs on the Evaluation of Carcinogenic Risks to Humans:

TRICHLOROETHYLENE	Overall evaluation: 1. Carcinogenic to humans.

US. National Toxicology Program (NTP) Report on Carcinogens:

TRICHLOROETHYLENE	Reasonably Anticipated to be a Human Carcinogen.

US. OSHA Specifically Regulated Substances (29 CFR 1910.1001-1050):
No carcinogenic components identified

Germ Cell Mutagenicity

In vitro
Product: Suspected of causing genetic defects.

In vivo
Product: Suspected of causing genetic defects.

Reproductive Toxicity
Product: No components toxic to reproduction

Specific Target Organ Toxicity - Single Exposure
Product: May cause respiratory irritation. May cause drowsiness or dizziness.

Specific Target Organ Toxicity - Repeated Exposure
Product: No data available.

Aspiration Hazard
Product: Not classified

Other Effects: None known.

12. Ecological information

Ecotoxicity:

Acute hazards to the aquatic environment:

Fish
Product: No data available.

Specified substance(s):
TRICHLOROETHYLENE — LC 50 (Fathead minnow (Pimephales promelas), 96 h): 31.4 - 71.8 mg/l Mortality
LC 50 (Bluegill (Lepomis macrochirus), 96 h): 39 - 54 mg/l Mortality
EC 50 (Fathead minnow (Pimephales promelas), 96 h): 18.4 - 28.5 mg/l Intoxication

Aquatic Invertebrates
Product: No data available.

Specified substance(s):
TRICHLOROETHYLENE — LC 50 (Water flea (Daphnia magna), 48 h): 12 - 26 mg/l Mortality

Chronic hazards to the aquatic environment:

Fish
Product: No data available.

Aquatic Invertebrates
Product: No data available.

Toxicity to Aquatic Plants
Product: No data available.

Persistence and Degradability

Biodegradation
Product: There are no data on the degradability of this product.

BOD/COD Ratio
Product: No data available.

Bioaccumulative Potential
Bioconcentration Factor (BCF)
Product: No data available on bioaccumulation.

Partition Coefficient n-octanol / water (log Kow)
Product: Log Kow: 2.61

Mobility in Soil: The product is water soluble and may spread in water systems.

Other Adverse Effects: Harmful to aquatic life with long lasting effects.

13. Disposal considerations

Disposal instructions: Discharge, treatment, or disposal may be subject to national, state, or local laws.

Contaminated Packaging: Since emptied containers retain product residue, follow label warnings even after container is emptied.

14. Transport information

DOT

UN Number:	UN 1710
UN Proper Shipping Name:	Trichloroethylene
Transport Hazard Class(es)	
Class(es):	6.1
Label(s):	6.1
Packing Group:	III
Marine Pollutant:	No

IMDG

UN Number:	UN 1710
UN Proper Shipping Name:	TRICHLOROETHYLENE
Transport Hazard Class(es)	
Class(es):	6.1
Label(s):	6.1
EmS No.:	F-A, S-A
Packing Group:	III
Marine Pollutant:	No

IATA

UN Number:	UN 1710
Proper Shipping Name:	Trichloroethylene
Transport Hazard Class(es):	
Class(es):	6.1
Label(s):	6.1
Marine Pollutant:	No
Packing Group:	III

15. Regulatory information

US Federal Regulations

TSCA Section 12(b) Export Notification (40 CFR 707, Subpt. D)

US. OSHA Specifically Regulated Substances (29 CFR 1910.1001-1050)
None present or none present in regulated quantities.

CERCLA Hazardous Substance List (40 CFR 302.4):
TRICHLOROETHYLENE Reportable quantity: 100 lbs.

Superfund Amendments and Reauthorization Act of 1986 (SARA)

Hazard categories

X	Acute (Immediate)	X	Chronic (Delayed)		Fire		Reactive		Pressure Generating

SARA 302 Extremely Hazardous Substance
None present or none present in regulated quantities.

SARA 304 Emergency Release Notification

Chemical Identity	RQ
TRICHLOROETHYLENE	100 lbs.

SARA 311/312 Hazardous Chemical

Chemical Identity	Threshold Planning Quantity
TRICHLOROETHYLENE	500 lbs

SARA 313 (TRI Reporting)

Chemical Identity	Reporting threshold for other users	Reporting threshold for manufacturing and processing
TRICHLOROETHYLENE	10000 lbs	25000 lbs.

Clean Water Act Section 311 Hazardous Substances (40 CFR 117.3)
TRICHLOROETHYLENE Reportable quantity: 100 lbs.

Clean Air Act (CAA) Section 112(r) Accidental Release Prevention (40 CFR 68.130):
None present or none present in regulated quantities.

US State Regulations

US. California Proposition 65
TRICHLOROETHYLENE Carcinogenic.
TRICHLOROETHYLENE Male reproductive toxin.
TRICHLOROETHYLENE Developmental toxin.

US. New Jersey Worker and Community Right-to-Know Act
TRICHLOROETHYLENE Listed

US. Massachusetts RTK - Substance List
TRICHLOROETHYLENE Listed

US. Pennsylvania RTK - Hazardous Substances
TRICHLOROETHYLENE Listed

US. Rhode Island RTK
TRICHLOROETHYLENE Listed

Inventory Status:

Australia AICS:	On or in compliance with the inventory
Canada DSL Inventory List:	On or in compliance with the inventory
EINECS, ELINCS or NLP:	On or in compliance with the inventory
Japan (ENCS) List:	On or in compliance with the inventory
China Inv. Existing Chemical Substances:	Not in compliance with the inventory.
Korea Existing Chemicals Inv. (KECI):	On or in compliance with the inventory
Canada NDSL Inventory:	Not in compliance with the inventory.
Philippines PICCS:	On or in compliance with the inventory
US TSCA Inventory:	On or in compliance with the inventory
New Zealand Inventory of Chemicals:	On or in compliance with the inventory
Japan ISHL Listing:	On or in compliance with the inventory
Japan Pharmacopoeia Listing:	Not in compliance with the inventory.

16.Other information, including date of preparation or last revision

NFPA Hazard ID

Hazard rating: 0 - Minimal; 1 - Slight; 2 - Moderate; 3 - Serious; 4 - Severe

Issue Date:	01-08-2015
Revision Date:	No data available.
Version #:	1.1
Further Information:	No data available.

Disclaimer:

THE INFORMATION PRESENTED IN THIS MATERIAL SAFETY DATA SHEET (MSDS/SDS) WAS PREPARED BY TECHNICAL PERSONNEL BASED ON DATA THAT THEY BELIEVE IN THEIR GOOD FAITH JUDGMENT IS ACCURATE. HOWEVER, THE INFORMATION PROVIDED HEREIN IS PROVIDED “AS IS,” AND AVANTOR PERFORMANCE MATERIALS MAKES AND GIVES NO REPRESENTATIONS OR WARRANTIES WHATSOEVER, AND EXPRESSLY DISCLAIMS ALL WARRANTIES REGARDING SUCH INFORMATION AND THE PRODUCT TO WHICH IT RELATES, WHETHER EXPRESS, IMPLIED, OR STATUTORY, INCLUDING WITHOUT LIMITATION<(>,<)> WARRANTIES OF ACCURACY, COMPLETENESS, MERCHANTABILITY, NON-INFRINGEMENT, PERFORMANCE, SAFETY, SUITABILITY, STABILITY, AND FITNESS FOR A PARTICULAR PURPOSE, AND ANY WARRANTIES ARISING FROM COURSE OF DEALING, COURSE OF PERFORMANCE, OR USAGE OF TRADE. THIS MSDS/SDS IS INTENDED ONLY AS A GUIDE TO THE APPROPRIATE PRECAUTIONARY HANDLING OF THE MATERIAL BY A PROPERLY TRAINED PERSON USING THIS PRODUCT, AND IS NOT INTENDED TO BE COMPREHENSIVE AS TO THE MANNER AND CONDITIONS OF USE, HANDLING, STORAGE, OR DISPOSAL OF THE PRODUCT. INDIVIDUALS RECEIVING THIS MSDS/SDS MUST ALWAYS EXERCISE THEIR OWN INDEPENDENT JUDGMENT IN DETERMINING THE APPROPRIATENESS OF SUCH ISSUES. ACCORDINGLY, AVANTOR PERFORMANCE MATERIALS ASSUMES NO LIABILITY WHATSOEVER FOR THE USE OF OR RELIANCE UPON THIS INFORMATION. NO SUGGESTIONS FOR USE ARE INTENDED AS, AND NOTHING HEREIN SHALL BE CONSTRUED AS, A RECOMMENDATION TO INFRINGE ANY EXISTING PATENTS OR TO VIOLATE ANY FEDERAL, STATE, LOCAL, OR FOREIGN LAWS. AVANTOR PERFORMANCE MATERIALS REMINDS YOU THAT IT IS YOUR LEGAL DUTY TO MAKE ALL INFORMATION IN THIS MSDS/SDS AVAILABLE TO YOUR EMPLOYEES.

SAFETY DATA SHEET

Creation Date 10-Dec-2009 **Revision Date** 06-Nov-2015 **Revision Number** 2

1. Identification

Product Name **Tetrachloroethylene**

Cat No. : **AC167890000; AC167890010; AC167890025; AC167890100; AC167891000; AC167895000**

Synonyms Perchloroethylene

Recommended Use Laboratory chemicals.

Uses advised against No Information available

Details of the supplier of the safety data sheet

Company
Fisher Scientific
One Reagent Lane
Fair Lawn, NJ 07410
Tel: (201) 796-7100

Entity / Business Name
Acros Organics
One Reagent Lane
Fair Lawn, NJ 07410

Emergency Telephone Number
For information **US** call: 001-800-ACROS-01 / **Europe** call: +32 14 57 52 11
Emergency Number **US:**001-201-796-7100 / **Europe:** +32 14 57 52 99
CHEMTREC Tel. No.**US:**001-800-424-9300 / **Europe:**001-703-527-3887

2. Hazard(s) identification

Classification
This chemical is considered hazardous by the 2012 OSHA Hazard Communication Standard (29 CFR 1910.1200)

Skin Corrosion/irritation	Category 2
Serious Eye Damage/Eye Irritation	Category 2
Skin Sensitization	Category 1
Carcinogenicity	Category 1B
Specific target organ toxicity (single exposure)	Category 3
Target Organs - Respiratory system, Central nervous system (CNS).	
Specific target organ toxicity - (repeated exposure)	Category 2
Target Organs - Kidney, Liver, Blood.	

Label Elements

Signal Word
Danger

Hazard Statements
Causes skin irritation
Causes serious eye irritation
May cause an allergic skin reaction
May cause drowsiness or dizziness
May cause cancer
May cause damage to organs through prolonged or repeated exposure

Precautionary Statements
Prevention
Obtain special instructions before use
Do not handle until all safety precautions have been read and understood
Use personal protective equipment as required
Wash face, hands and any exposed skin thoroughly after handling
Contaminated work clothing should not be allowed out of the workplace
Do not breathe dust/fume/gas/mist/vapors/spray
Use only outdoors or in a well-ventilated area
Wear protective gloves/protective clothing/eye protection/face protection
Response
IF exposed or concerned: Get medical attention/advice
Inhalation
IF INHALED: Remove victim to fresh air and keep at rest in a position comfortable for breathing
Skin
IF ON SKIN: Wash with plenty of soap and water
Take off contaminated clothing and wash before reuse
If skin irritation or rash occurs: Get medical advice/attention
Eyes
IF IN EYES: Rinse cautiously with water for several minutes. Remove contact lenses, if present and easy to do. Continue rinsing
If eye irritation persists: Get medical advice/attention
Storage
Store locked up
Store in a well-ventilated place. Keep container tightly closed
Disposal
Dispose of contents/container to an approved waste disposal plant
Hazards not otherwise classified (HNOC)
Toxic to aquatic life with long lasting effects
WARNING! This product contains a chemical known in the State of California to cause cancer.

3. Composition / information on ingredients

Component	CAS-No	Weight %
Tetrachloroethylene	127-18-4	>95

4. First-aid measures

Eye Contact Rinse immediately with plenty of water, also under the eyelids, for at least 15 minutes. Obtain medical attention.

Skin Contact Wash off immediately with plenty of water for at least 15 minutes. Obtain medical attention.

Inhalation Move to fresh air. If breathing is difficult, give oxygen. Do not use mouth-to-mouth method if victim ingested or inhaled the substance; give artificial respiration with the aid of a pocket mask equipped with a one-way valve or other proper respiratory medical device. Obtain medical attention.

Ingestion Do not induce vomiting. Obtain medical attention.

Most important symptoms/effects Breathing difficulties. . May cause allergic skin reaction. Inhalation of high vapor

concentrations may cause symptoms like headache, dizziness, tiredness, nausea and vomiting: Symptoms of allergic reaction may include rash, itching, swelling, trouble breathing, tingling of the hands and feet, dizziness, lightheadedness, chest pain, muscle pain or flushing

Notes to Physician Treat symptomatically

5. Fire-fighting measures

Suitable Extinguishing Media Substance is nonflammable; use agent most appropriate to extinguish surrounding fire.

Unsuitable Extinguishing Media No information available

Flash Point No information available
Method - No information available

Autoignition Temperature No information available
Explosion Limits
Upper No data available
Lower No data available
Sensitivity to Mechanical Impact No information available
Sensitivity to Static Discharge No information available

Specific Hazards Arising from the Chemical
Thermal decomposition can lead to release of irritating gases and vapors. Containers may explode when heated.

Hazardous Combustion Products
Chlorine Hydrogen chloride gas Phosgene
Protective Equipment and Precautions for Firefighters
As in any fire, wear self-contained breathing apparatus pressure-demand, MSHA/NIOSH (approved or equivalent) and full protective gear.

NFPA

Health	Flammability	Instability	Physical hazards
2	0	0	N/A

6. Accidental release measures

Personal Precautions Use personal protective equipment. Ensure adequate ventilation. Avoid contact with skin, eyes and clothing.

Environmental Precautions Do not flush into surface water or sanitary sewer system. See Section 12 for additional ecological information. Avoid release to the environment. Collect spillage.

Methods for Containment and Clean Up Soak up with inert absorbent material. Keep in suitable, closed containers for disposal.

7. Handling and storage

Handling Use only under a chemical fume hood. Wear personal protective equipment. Do not breathe vapors or spray mist. Do not get in eyes, on skin, or on clothing.

Storage Keep containers tightly closed in a dry, cool and well-ventilated place. Protect from sunlight.

8. Exposure controls / personal protection

Exposure Guidelines

Component	ACGIH TLV	OSHA PEL	NIOSH IDLH
Tetrachloroethylene	TWA: 25 ppm STEL: 100 ppm	(Vacated) TWA: 25 ppm (Vacated) TWA: 170 mg/m^3 Ceiling: 200 ppm TWA: 100 ppm	IDLH: 150 ppm

Component	Quebec	Mexico OEL (TWA)	Ontario TWAEV
Tetrachloroethylene	TWA: 25 ppm TWA: 170 mg/m³ STEL: 100 ppm STEL: 685 mg/m³	TWA: 100 ppm TWA: 670 mg/m³ TWA: 200 ppm TWA: 1250 mg/m³ STEL: 200 ppm STEL: 1340 mg/m³	TWA: 25 ppm STEL: 100 ppm

Legend

ACGIH - American Conference of Governmental Industrial Hygienists
OSHA - Occupational Safety and Health Administration
NIOSH IDLH: The National Institute for Occupational Safety and Health Immediately Dangerous to Life or Health

Engineering Measures Use only under a chemical fume hood. Ensure adequate ventilation, especially in confined areas. Ensure that eyewash stations and safety showers are close to the workstation location.

Personal Protective Equipment

Eye/face Protection Wear appropriate protective eyeglasses or chemical safety goggles as described by OSHA's eye and face protection regulations in 29 CFR 1910.133 or European Standard EN166.

Skin and body protection Wear appropriate protective gloves and clothing to prevent skin exposure.

Respiratory Protection Follow the OSHA respirator regulations found in 29 CFR 1910.134 or European Standard EN 149. Use a NIOSH/MSHA or European Standard EN 149 approved respirator if exposure limits are exceeded or if irritation or other symptoms are experienced.

Hygiene Measures Handle in accordance with good industrial hygiene and safety practice.

9. Physical and chemical properties

Physical State	Liquid
Appearance	Colorless
Odor	Characteristic, sweet
Odor Threshold	No information available
pH	No information available
Melting Point/Range	-22 °C / -7.6 °F
Boiling Point/Range	120 - 122 °C / 248 - 251.6 °F @ 760 mmHg
Flash Point	No information available
Evaporation Rate	6.0 (Ether = 1.0)
Flammability (solid,gas)	Not applicable
Flammability or explosive limits	
Upper	No data available
Lower	No data available
Vapor Pressure	18 mbar @ 20 °C
Vapor Density	No information available
Specific Gravity	1.625
Solubility	0.15 g/L water (20°C)
Partition coefficient; n-octanol/water	No data available
Autoignition Temperature	No information available
Decomposition Temperature	> 150°C
Viscosity	0.89 mPa s at 20 °C
Molecular Formula	C2 Cl4
Molecular Weight	165.83

10. Stability and reactivity

Reactive Hazard None known, based on information available

Stability Stable under normal conditions.

Conditions to Avoid Incompatible products. Excess heat. Exposure to moist air or water.

Incompatible Materials Strong acids, Strong oxidizing agents, Strong bases, Metals, Zinc, Amines

Hazardous Decomposition Products Chlorine, Hydrogen chloride gas, Phosgene

Hazardous Polymerization Hazardous polymerization does not occur.

Hazardous Reactions None under normal processing.

11. Toxicological information

Acute Toxicity

Product Information

Component Information

Component	LD50 Oral	LD50 Dermal	LC50 Inhalation
Tetrachloroethylene	LD50 = 2629 mg/kg (Rat)	LD50 > 10000 mg/kg (Rat)	LC50 = 27.8 mg/L (Rat) 4 h

Toxicologically Synergistic Products No information available

Delayed and immediate effects as well as chronic effects from short and long-term exposure

Irritation Irritating to eyes and skin

Sensitization May cause sensitization by skin contact

Carcinogenicity The table below indicates whether each agency has listed any ingredient as a carcinogen.

Component	CAS-No	IARC	NTP	ACGIH	OSHA	Mexico
Tetrachloroethylene	127-18-4	Group 2A	Reasonably Anticipated	A3	X	A3

IARC: (International Agency for Research on Cancer)

IARC: (International Agency for Research on Cancer)
Group 1 - Carcinogenic to Humans
Group 2A - Probably Carcinogenic to Humans
Group 2B - Possibly Carcinogenic to Humans

NTP: (National Toxicity Program)

NTP: (National Toxicity Program)
Known - Known Carcinogen
Reasonably Anticipated - Reasonably Anticipated to be a Human Carcinogen

ACGIH: (American Conference of Governmental Industrial Hygienists)

A1 - Known Human Carcinogen
A2 - Suspected Human Carcinogen
A3 - Animal Carcinogen
ACGIH: (American Conference of Governmental Industrial Hygienists)

Mutagenic Effects No information available

Reproductive Effects No information available.

Developmental Effects No information available.

Teratogenicity No information available.

STOT - single exposure Respiratory system Central nervous system (CNS)

STOT - repeated exposure Kidney Liver Blood

Aspiration hazard No information available

Symptoms / effects,both acute and delayed Inhalation of high vapor concentrations may cause symptoms like headache, dizziness, tiredness, nausea and vomiting: Symptoms of allergic reaction may include rash, itching, swelling, trouble breathing, tingling of the hands and feet, dizziness, lightheadedness, chest

pain, muscle pain or flushing

Endocrine Disruptor Information

Component	EU - Endocrine Disrupters Candidate List	EU - Endocrine Disruptors - Evaluated Substances	Japan - Endocrine Disruptor Information
Tetrachloroethylene	Group II Chemical	Not applicable	Not applicable

Other Adverse Effects Tumorigenic effects have been reported in experimental animals. See actual entry in RTECS for complete information.

12. Ecological information

Ecotoxicity

Toxic to aquatic organisms, may cause long-term adverse effects in the aquatic environment. The product contains following substances which are hazardous for the environment.

Component	Freshwater Algae	Freshwater Fish	Microtox	Water Flea
Tetrachloroethylene	EC50: > 500 mg/L, 96h (Pseudokirchneriella subcapitata)	LC50: 4.73 - 5.27 mg/L, 96h flow-through (Oncorhynchus mykiss) LC50: 11.0 - 15.0 mg/L, 96h static (Lepomis macrochirus) LC50: 8.6 - 13.5 mg/L, 96h static (Pimephales promelas) LC50: 12.4 - 14.4 mg/L, 96h flow-through (Pimephales promelas)	EC50 = 100 mg/L 24 h EC50 = 112 mg/L 24 h EC50 = 120.0 mg/L 30 min	EC50: 6.1 - 9.0 mg/L, 48h Static (Daphnia magna)

Persistence and Degradability Insoluble in water Persistence is unlikely based on information available.

Bioaccumulation/ Accumulation No information available.

Mobility . Is not likely mobile in the environment due its low water solubility. Will likely be mobile in the environment due to its volatility.

Component	log Pow
Tetrachloroethylene	2.88

13. Disposal considerations

Waste Disposal Methods Chemical waste generators must determine whether a discarded chemical is classified as a hazardous waste. Chemical waste generators must also consult local, regional, and national hazardous waste regulations to ensure complete and accurate classification.

Component	RCRA - U Series Wastes	RCRA - P Series Wastes
Tetrachloroethylene - 127-18-4	U210	-

14. Transport information

DOT

UN-No UN1897
Proper Shipping Name TETRACHLOROETHYLENE
Hazard Class 6.1
Packing Group III

TDG

UN-No UN1897
Proper Shipping Name TETRACHLOROETHYLENE
Hazard Class 6.1
Packing Group III

IATA

UN-No UN1897
Proper Shipping Name TETRACHLOROETHYLENE
Hazard Class 6.1
Packing Group III

IMDG/IMO

UN-No	UN1897
Proper Shipping Name	TETRACHLOROETHYLENE
Hazard Class	6.1
Packing Group	III

15. Regulatory information

International Inventories

Component	TSCA	DSL	NDSL	EINECS	ELINCS	NLP	PICCS	ENCS	AICS	IECSC	KECL
Tetrachloroethylene	X	X	-	204-825-9	-		X	X	X	X	X

Legend:
X - Listed
E - Indicates a substance that is the subject of a Section 5(e) Consent order under TSCA.
F - Indicates a substance that is the subject of a Section 5(f) Rule under TSCA.
N - Indicates a polymeric substance containing no free-radical initiator in its inventory name but is considered to cover the designated polymer made with any free-radical initiator regardless of the amount used.
P - Indicates a commenced PMN substance
R - Indicates a substance that is the subject of a Section 6 risk management rule under TSCA.
S - Indicates a substance that is identified in a proposed or final Significant New Use Rule
T - Indicates a substance that is the subject of a Section 4 test rule under TSCA.
XU - Indicates a substance exempt from reporting under the Inventory Update Rule, i.e. Partial Updating of the TSCA Inventory Data Base Production and Site Reports (40 CFR 710(B).
Y1 - Indicates an exempt polymer that has a number-average molecular weight of 1,000 or greater.
Y2 - Indicates an exempt polymer that is a polyester and is made only from reactants included in a specified list of low concern reactants that comprises one of the eligibility criteria for the exemption rule.

U.S. Federal Regulations

TSCA 12(b) Not applicable

SARA 313

Component	CAS-No	Weight %	SARA 313 - Threshold Values %
Tetrachloroethylene	127-18-4	>95	0.1

SARA 311/312 Hazard Categories

Acute Health Hazard	Yes
Chronic Health Hazard	Yes
Fire Hazard	No
Sudden Release of Pressure Hazard	No
Reactive Hazard	No

CWA (Clean Water Act)

Component	CWA - Hazardous Substances	CWA - Reportable Quantities	CWA - Toxic Pollutants	CWA - Priority Pollutants
Tetrachloroethylene	-	-	X	X

Clean Air Act

Component	HAPS Data	Class 1 Ozone Depletors	Class 2 Ozone Depletors
Tetrachloroethylene	X		-

OSHA Occupational Safety and Health Administration
Not applicable

CERCLA
This material, as supplied, contains one or more substances regulated as a hazardous substance under the Comprehensive Environmental Response Compensation and Liability Act (CERCLA) (40 CFR 302)

Component	Hazardous Substances RQs	CERCLA EHS RQs
Tetrachloroethylene	100 lb 1 lb	-

California Proposition 65 This product contains the following proposition 65 chemicals

Component	CAS-No	California Prop. 65	Prop 65 NSRL	Category
Tetrachloroethylene	127-18-4	Carcinogen	14 µg/day	Carcinogen

U.S. State Right-to-Know Regulations

Component	Massachusetts	New Jersey	Pennsylvania	Illinois	Rhode Island
Tetrachloroethylene	X	X	X	X	X

U.S. Department of Transportation

Reportable Quantity (RQ): Y
DOT Marine Pollutant Y
DOT Severe Marine Pollutant N

U.S. Department of Homeland Security
This product does not contain any DHS chemicals.

Other International Regulations

Mexico - Grade No information available

Canada
This product has been classified in accordance with the hazard criteria of the Controlled Products Regulations (CPR) and the MSDS contains all the information required by the CPR

WHMIS Hazard Class D1B Toxic materials
D2A Very toxic materials

16. Other information

Prepared By Regulatory Affairs
Thermo Fisher Scientific
Email: EMSDS.RA@thermofisher.com

Creation Date 10-Dec-2009
Revision Date 06-Nov-2015
Print Date 06-Nov-2015
Revision Summary This document has been updated to comply with the US OSHA HazCom 2012 Standard replacing the current legislation under 29 CFR 1910.1200 to align with the Globally Harmonized System of Classification and Labeling of Chemicals (GHS)

Disclaimer
The information provided in this Safety Data Sheet is correct to the best of our knowledge, information and belief at the date of its publication. The information given is designed only as a guidance for safe handling, use, processing, storage, transportation, disposal and release and is not to be considered a warranty or quality specification. The information relates only to the specific material designated and may not be valid for such material used in combination with any other materials or in any process, unless specified in the text

End of SDS

SAFETY DATA SHEET

1. Identification

Product identifier: TOLUENE

Other means of identification
Product No.: 9457, 4483, V560, 8604, 9476, 9466, 9460, 9456, 9364, 9351, 9336, 8608

Recommended use and restriction on use

Recommended use: Not available.
Restrictions on use: Not known.

Manufacturer/Importer/Supplier/Distributor information

Manufacturer

Company Name:	Avantor Performance Materials, Inc.
Address:	3477 Corporate Parkway, Suite 200 Center Valley, PA 18034
Telephone:	Customer Service: 855-282-6867
Fax:	
Contact Person:	Environmental Health & Safety
e-mail:	info@avantormaterials.com

Emergency telephone number:
24 Hour Emergency: 908-859-2151

Chemtrec: 800-424-9300

2. Hazard(s) identification

Hazard classification

Physical hazards

Flammable liquids	Category 2

Health hazards

Acute toxicity (Oral)	Category 4
Acute toxicity (Inhalation - vapor)	Category 4
Skin corrosion/irritation	Category 2
Serious eye damage/eye irritation	Category 2A
Toxic to reproduction	Category 2
Specific target organ toxicity - single exposure	Category 3
Specific target organ toxicity - repeated exposure	Category 2
Aspiration hazard	Category 1

Environmental hazards

Acute hazards to the aquatic environment	Category 2

Label elements

Hazard symbol:

Signal word: Danger

Hazard statement:
Highly flammable liquid and vapor.
Harmful if swallowed or if inhaled.
Causes skin irritation.
Causes serious eye irritation.
Suspected of damaging fertility or the unborn child.
May cause respiratory irritation.
May cause drowsiness or dizziness.
May be fatal if swallowed and enters airways.
May cause damage to organs through prolonged or repeated exposure.
Toxic to aquatic life.

Precautionary statement

Prevention: Obtain special instructions before use. Do not handle until all safety precautions have been read and understood. Use personal protective equipment as required. Keep away from heat/sparks/open flames/hot surfaces. No smoking. Keep container tightly closed. Ground/bond container and receiving equipment. Use explosion-proof electrical/ventilating/lighting/equipment. Use only non-sparking tools. Take precautionary measures against static discharge. Wear protective gloves/protective clothing/eye protection/face protection. Use only outdoors or in a well-ventilated area. Wash thoroughly after handling. Do not eat, drink or smoke when using this product. Avoid release to the environment.

Response: In case of fire: Use water spray, foam, dry powder or carbon dioxide for extinction. IF exposed or concerned: Get medical advice/attention. IF INHALED: Remove victim to fresh air and keep at rest in a position comfortable for breathing. Call a POISON CENTER or doctor/physician if you feel unwell. IF ON SKIN (or hair): Remove/take off immediately all contaminated clothing. Rinse skin with water/shower. If skin irritation occurs: Get medical advice/attention. Take off contaminated clothing and wash before reuse. IF IN EYES: Rinse cautiously with water for several minutes. Remove contact lenses, if present and easy to do. Continue rinsing. If eye irritation persists: Get medical advice/attention. IF SWALLOWED: Immediately call a POISON CENTER or doctor/physician. Do NOT induce vomiting.

Storage: Store locked up. Store in a well-ventilated place. Keep cool. Keep container tightly closed.

Disposal: Dispose of contents/container to an appropriate treatment and disposal facility in accordance with applicable laws and regulations, and product characteristics at time of disposal.

Other hazards which do not result in GHS classification: Static accumulating flammable liquid can become electrostatically charged even in bonded and grounded equipment. Sparks may ignite liquid and vapor. May cause flash fire or explosion.

3. Composition/information on ingredients

Substances

Chemical identity	Common name and synonyms	CAS number	Content in percent (%)*
TOLUENE		108-88-3	99 - 100%

* All concentrations are percent by weight unless ingredient is a gas. Gas concentrations are in percent by volume.

4. First-aid measures

General information: Get medical advice/attention if you feel unwell. Show this safety data sheet to the doctor in attendance.

Ingestion: Call a physician or poison control center immediately. Do NOT induce vomiting. If vomiting occurs, keep head low so that stomach content doesn't get into the lungs.

Inhalation: Move to fresh air. Get medical attention immediately.

Skin contact: Immediately flush with plenty of water for at least 15 minutes while removing contaminated clothing and shoes. Get medical attention. Wash contaminated clothing before reuse. Destroy or thoroughly clean contaminated shoes.

Eye contact: Immediately flush with plenty of water for at least 15 minutes. If easy to do, remove contact lenses. Get medical attention.

Most important symptoms/effects, acute and delayed

Symptoms: Harmful if swallowed. May be fatal if swallowed. Harmful if inhaled. Irritating to eyes, respiratory system and skin.

Indication of immediate medical attention and special treatment needed

Treatment: Treat symptomatically. Symptoms may be delayed.

5. Fire-fighting measures

General fire hazards: In case of fire and/or explosion do not breathe fumes.

Suitable (and unsuitable) extinguishing media

Suitable extinguishing media: Water spray, foam, dry powder or carbon dioxide.

Unsuitable extinguishing media: Avoid water in straight hose stream; will scatter and spread fire.

Specific hazards arising from the chemical: Vapors may cause a flash fire or ignite explosively. Vapors may travel considerable distance to a source of ignition and flash back. Prevent buildup of vapors or gases to explosive concentrations.

Special protective equipment and precautions for firefighters

Special fire fighting procedures: Use water spray to keep fire-exposed containers cool. Cool containers exposed to flames with water until well after the fire is out. Water may be ineffective in fighting the fire. Fight fire from a protected location. Move containers from fire area if you can do so without risk.

Special protective equipment for fire-fighters:	Firefighters must use standard protective equipment including flame retardant coat, helmet with face shield, gloves, rubber boots, and in enclosed spaces, SCBA.

6. Accidental release measures

Personal precautions, protective equipment and emergency procedures:	ELIMINATE all ignition sources (no smoking, flares, sparks or flames in immediate area). Keep unauthorized personnel away. Keep upwind. Use personal protective equipment. Do not touch damaged containers or spilled material unless wearing appropriate protective clothing. Ventilate closed spaces before entering them. See Section 8 of the MSDS for Personal Protective Equipment.
Methods and material for containment and cleaning up:	Eliminate all ignition sources if safe to do so. Take precautionary measures against static discharges. Stop leak if possible without any risk. Use only non-sparking tools. Absorb spill with vermiculite or other inert material, then place in a container for chemical waste. Clean surface thoroughly to remove residual contamination. Dike far ahead of larger spill for later recovery and disposal.
Notification Procedures:	Prevent entry into waterways, sewer, basements or confined areas. Inform authorities if large amounts are involved.
Environmental precautions:	Do not contaminate water sources or sewer. Prevent further leakage or spillage if safe to do so.

7. Handling and storage

Precautions for safe handling:	DO NOT handle, store or open near an open flame, sources of heat or sources of ignition. Protect material from direct sunlight. Take precautionary measures against static discharges. Ground/bond container and receiving equipment. Use explosion-proof electrical/ventilating/lighting/equipment. Use only non-sparking tools. Wear protective gloves/protective clothing/eye protection/face protection. Avoid contact with eyes, skin, and clothing. Use only with adequate ventilation. Wash hands thoroughly after handling.
Conditions for safe storage, including any incompatibilities:	Keep away from food, drink and animal feeding stuffs. Keep container tightly closed in a cool, well-ventilated place. Ground container and transfer equipment to eliminate static electric sparks. Comply with all national, state, and local codes pertaining to the storage, handling, dispensing, and disposal of flammable liquids.

8. Exposure controls/personal protection

Control parameters

Occupational exposure limits

Chemical identity	Type	Exposure Limit values		Source
TOLUENE	TWA	20 ppm		US. ACGIH Threshold Limit Values (2011)
	STEL	150 ppm	560 mg/m3	US. NIOSH: Pocket Guide to Chemical Hazards (2010)
	REL	100 ppm	375 mg/m3	US. NIOSH: Pocket Guide to Chemical Hazards (2010)
	TWA	100 ppm	375 mg/m3	US. OSHA Table Z-1-A (29 CFR 1910.1000) (1989)
	STEL	150 ppm	560 mg/m3	US. OSHA Table Z-1-A (29 CFR 1910.1000) (1989)
	TWA	200 ppm		US. OSHA Table Z-2 (29 CFR 1910.1000) (02 2006)
	Ceiling	300 ppm		US. OSHA Table Z-2 (29 CFR 1910.1000) (02 2006)
	MAX. CONC	500 ppm		US. OSHA Table Z-2 (29 CFR 1910.1000) (02 2006)

Biological limit values

Chemical identity	Exposure Limit values	Source
TOLUENE (o-Cresol, with hydrolysis: Sampling time: End of shift.)	0.3 mg/g (Creatinine in urine)	ACGIH BEL (2011)
TOLUENE (toluene: Sampling time: Prior to last shift of work week.)	0.02 mg/l (Blood)	ACGIH BEL (2011)
TOLUENE (toluene: Sampling time: End of shift.)	0.03 mg/l (Urine)	ACGIH BEL (2011)

Appropriate engineering controls No data available.

Individual protection measures, such as personal protective equipment

General information: Good general ventilation (typically 10 air changes per hour) should be used. Ventilation rates should be matched to conditions. If applicable, use process enclosures, local exhaust ventilation, or other engineering controls to maintain airborne levels below recommended exposure limits. If exposure limits have not been established, maintain airborne levels to an acceptable level. An eye wash and safety shower must be available in the immediate work area. Use explosion-proof ventilation equipment.

Eye/face protection: Wear safety glasses with side shields (or goggles) and a face shield.

Skin protection

Hand protection: Chemical resistant gloves

Other: Wear suitable protective clothing.

Respiratory protection: In case of inadequate ventilation use suitable respirator.

Hygiene measures: Provide eyewash station and safety shower. Always observe good personal hygiene measures, such as washing after handling the material and before eating, drinking, and/or smoking. Routinely wash work clothing to remove contaminants. Discard contaminated footwear that cannot be cleaned.

9. Physical and chemical properties

Appearance

Physical state:	Liquid
Form:	Liquid
Color:	Colorless
Odor:	Sweet aromatic odor
Odor threshold:	No data available.
pH:	No data available.
Melting point/freezing point:	-94.9 °C
Initial boiling point and boiling range:	110 °C
Flash Point:	4 °C (Closed Cup)
Evaporation rate:	2.24 (butyl acetate=1)
Flammability (solid, gas):	No data available.
Upper/lower limit on flammability or explosive limits	
Flammability limit - upper (%):	7.1 %(V)
Flammability limit - lower (%):	1.1 %(V)
Explosive limit - upper (%):	No data available.
Explosive limit - lower (%):	No data available.
Vapor pressure:	3.8 kPa (25 °C)
Vapor density:	3.1 AIR=1
Relative density:	0.86 (20 °C)
Solubility(ies)	
Solubility in water:	0.7 g/l (23.3 °C)
Solubility (other):	No data available.
Partition coefficient (n-octanol/water):	2.73
Auto-ignition temperature:	480 °C
Decomposition temperature:	No data available.
Viscosity:	No data available.

Other information

Molecular weight:	92.14 g/mol (C7H8)

10. Stability and reactivity

Reactivity:	No dangerous reaction known under conditions of normal use.
Chemical stability:	Material is stable under normal conditions.
Possibility of hazardous reactions:	Hazardous polymerization does not occur.
Conditions to avoid:	Heat, sparks, flames.
Incompatible materials:	Strong oxidizing agents. Chlorine.
Hazardous decomposition products:	Thermal decomposition may release oxides of carbon.

11. Toxicological information

Information on likely routes of exposure

Ingestion:	Harmful if swallowed.
Inhalation:	Harmful if inhaled. May cause irritation to the mucous membranes and upper respiratory tract.

Skin contact: Causes skin irritation.

Eye contact: Causes serious eye irritation.

Information on toxicological effects

Acute toxicity (list all possible routes of exposure)

Oral
Product: LD 50 (Rat): 636 mg/kg

Dermal
Product: LD 50 (Rabbit): 12,124 mg/kg

Inhalation
Product: LC 50 (Mouse, 24 h): 400 mg/l
LC 50 (Rat, 4 h): 8,000 mg/l

Repeated dose toxicity
Product: No data available.

Skin corrosion/irritation
Product: Causes skin irritation.

Serious eye damage/eye irritation
Product: Causes serious eye irritation.

Respiratory or skin sensitization
Product: Not a skin sensitizer.

Carcinogenicity
Product: This substance has no evidence of carcinogenic properties.

IARC Monographs on the Evaluation of Carcinogenic Risks to Humans:
No carcinogenic components identified

US. National Toxicology Program (NTP) Report on Carcinogens:
No carcinogenic components identified

US. OSHA Specifically Regulated Substances (29 CFR 1910.1001-1050):
No carcinogenic components identified

Germ cell mutagenicity

In vitro
Product: No mutagenic components identified

In vivo
Product: No mutagenic components identified

Reproductive toxicity
Product: May damage fertility or the unborn child.

Specific target organ toxicity - single exposure
Product: Narcotic effect. Respiratory tract irritation.

Specific target organ toxicity - repeated exposure
Product: Peripheral nervous system Central nervous system. Kidneys. auditory organs

Aspiration hazard
Product: May be fatal if swallowed and enters airways.

Other effects: No data available.

12. Ecological information

Ecotoxicity:

Acute hazards to the aquatic environment:

Fish

Product: No data available.

Specified substance(s):

TOLUENE — LC 50 (Fathead minnow (Pimephales promelas), 96 h): 12.6 mg/l Mortality
LC 50 (Coho salmon,silver salmon (Oncorhynchus kisutch), 96 h): 5.5 mg/l Mortality

Aquatic invertebrates

Product: No data available.

Specified substance(s):

TOLUENE — EC 50 (Brine shrimp (Artemia sp.), 24 h): 22.1 - 54.1 mg/l Intoxication
EC 50 (Water flea (Daphnia magna), 48 h): 5.46 - 9.83 mg/l Intoxication

Chronic hazards to the aquatic environment:

Fish

Product: No data available.

Aquatic invertebrates

Product: No data available.

Toxicity to Aquatic Plants

Product: No data available.

Persistence and degradability

Biodegradation

Product: Expected to be readily biodegradable.

BOD/COD ratio

Product: No data available.

Bioaccumulative potential

Bioconcentration factor (BCF)

Product: Bioaccumulation is unlikely to be significant because of the low water solubility of this product.

Partition coefficient n-octanol / water (log Kow)

Product: Log Kow: 2.73

Mobility in soil: The product is insoluble in water and will spread on the water surface.

Other adverse effects: Toxic to aquatic organisms.

13. Disposal considerations

Disposal instructions: Discharge, treatment, or disposal may be subject to national, state, or local laws. Residual vapors may explode on ignition; do not cut, drill, grind, or weld on or near this container.

Contaminated packaging: Since emptied containers retain product residue, follow label warnings even after container is emptied.

14. Transport information

DOT

UN number:	UN 1294
UN proper shipping name:	Toluene
Transport hazard class(es)	
Class(es):	3
Label(s):	3
Packing group:	II
Marine Pollutant:	No

IMDG

UN number:	UN 1294
UN proper shipping name:	TOLUENE
Transport hazard class(es)	
Class(es):	3
Label(s):	3
EmS No.:	F-E, S-D
Packing group:	II
Marine Pollutant:	No

IATA

UN number:	UN 1294
Proper Shipping Name:	Toluene
Transport hazard class(es):	
Class(es):	3
Label(s):	3
Marine Pollutant:	No
Packing group:	II

15. Regulatory information

US federal regulations

TSCA Section 12(b) Export Notification (40 CFR 707, Subpt. D)

US. OSHA Specifically Regulated Substances (29 CFR 1910.1001-1050)

None present or none present in regulated quantities.

CERCLA Hazardous Substance List (40 CFR 302.4):

TOLUENE Reportable quantity: 1000 lbs.

Superfund amendments and reauthorization act of 1986 (SARA)

Hazard categories

[X] Acute (Immediate) [X] Chronic (Delayed) [X] Fire [ ] Reactive [ ] Pressure Generating

SARA 302 Extremely hazardous substance

None present or none present in regulated quantities.

SARA 304 Emergency release notification

Chemical identity	RQ
TOLUENE	1000 lbs.

SARA 311/312 Hazardous chemical

Chemical identity	Threshold Planning Quantity
TOLUENE	500 lbs

SARA 313 (TRI reporting)

Chemical identity	Reporting threshold for other users	Reporting threshold for manufacturing and processing
TOLUENE	10000 lbs	25000 lbs.

Clean Water Act Section 311 Hazardous Substances (40 CFR 117.3)

TOLUENE Reportable quantity: 1000 lbs.

Clean Air Act (CAA) Section 112(r) Accidental Release Prevention (40 CFR 68.130):

None present or none present in regulated quantities.

US state regulations

US. California Proposition 65

TOLUENE Developmental toxin.
TOLUENE Female reproductive toxin.

US. New Jersey Worker and Community Right-to-Know Act

TOLUENE Listed

US. Massachusetts RTK - Substance List

TOLUENE Listed

US. Pennsylvania RTK - Hazardous Substances

TOLUENE Listed

US. Rhode Island RTK

TOLUENE Listed

Inventory Status:

Australia AICS:	On or in compliance with the inventory
Canada DSL Inventory List:	On or in compliance with the inventory
EU EINECS List:	On or in compliance with the inventory
EU ELINCS List:	Not in compliance with the inventory.
Japan (ENCS) List:	On or in compliance with the inventory
EU No Longer Polymers List:	Not in compliance with the inventory.
China Inv. Existing Chemical Substances:	On or in compliance with the inventory
Korea Existing Chemicals Inv. (KECI):	On or in compliance with the inventory
Canada NDSL Inventory:	Not in compliance with the inventory.
Philippines PICCS:	On or in compliance with the inventory
US TSCA Inventory:	On or in compliance with the inventory
New Zealand Inventory of Chemicals:	On or in compliance with the inventory
Switzerland Consolidated Inventory:	Not in compliance with the inventory.
Japan ISHL Listing:	On or in compliance with the inventory
Japan Pharmacopoeia Listing:	Not in compliance with the inventory.

16.Other information, including date of preparation or last revision

NFPA Hazard ID



Flammability
Health

Hazard rating: 0 - Minimal; 1 - Slight; 2 - Moderate; 3 - Serious; 4 - Severe

Issue date:	06-12-2014
Revision date:	No data available.
Version #:	1.0
Further information:	No data available.
Disclaimer:	THE INFORMATION PRESENTED IN THIS MATERIAL SAFETY DATA SHEET (MSDS/SDS) WAS PREPARED BY TECHNICAL PERSONNEL BASED ON DATA THAT THEY BELIEVE IN THEIR GOOD FAITH JUDGMENT IS ACCURATE. HOWEVER, THE INFORMATION PROVIDED HEREIN IS PROVIDED “AS IS,” AND AVANTOR PERFORMANCE MATERIALS MAKES AND GIVES NO REPRESENTATIONS OR WARRANTIES WHATSOEVER, AND EXPRESSLY DISCLAIMS ALL WARRANTIES REGARDING SUCH INFORMATION AND THE PRODUCT TO WHICH IT RELATES, WHETHER EXPRESS, IMPLIED, OR STATUTORY, INCLUDING WITHOUT LIMITATION<(>,<)> WARRANTIES OF ACCURACY, COMPLETENESS, MERCHANTABILITY, NON-INFRINGEMENT, PERFORMANCE, SAFETY, SUITABILITY, STABILITY, AND FITNESS FOR A PARTICULAR PURPOSE, AND ANY WARRANTIES ARISING FROM COURSE OF DEALING, COURSE OF PERFORMANCE, OR USAGE OF TRADE. THIS MSDS/SDS IS INTENDED ONLY AS A GUIDE TO THE APPROPRIATE PRECAUTIONARY HANDLING OF THE MATERIAL BY A PROPERLY TRAINED PERSON USING THIS PRODUCT, AND IS NOT INTENDED TO BE COMPREHENSIVE AS TO THE MANNER AND CONDITIONS OF USE, HANDLING, STORAGE, OR DISPOSAL OF THE PRODUCT. INDIVIDUALS RECEIVING THIS MSDS/SDS MUST ALWAYS EXERCISE THEIR OWN INDEPENDENT JUDGMENT IN DETERMINING THE APPROPRIATENESS OF SUCH ISSUES. ACCORDINGLY, AVANTOR PERFORMANCE MATERIALS ASSUMES NO LIABILITY WHATSOEVER FOR THE USE OF OR RELIANCE UPON THIS INFORMATION. NO SUGGESTIONS FOR USE ARE INTENDED AS, AND NOTHING HEREIN SHALL BE CONSTRUED AS, A RECOMMENDATION TO INFRINGE ANY EXISTING PATENTS OR TO VIOLATE ANY FEDERAL, STATE, LOCAL, OR FOREIGN LAWS. AVANTOR PERFORMANCE MATERIALS REMINDS YOU THAT IT IS YOUR LEGAL DUTY TO MAKE ALL INFORMATION IN THIS MSDS/SDS AVAILABLE TO YOUR EMPLOYEES.

Safety Data Sheet
Gasoline, Unleaded

NFPA:



TESORO

SECTION 1. PRODUCT AND COMPANY IDENTIFICATION

Product name	:	Gasoline, Unleaded			
Synonyms	:	Blend of Highly Flammable Petroleum Distillates, Regular, Mid-Grade, Premium, 888100008809			
SDS Number	:	888100008809	**Version**	:	1.1
Product Use Description	:	Fuel			
Company	:	For: Tesoro Refining & Marketing Co. 19100 Ridgewood Parkway, San Antonio, TX 78259			
Tesoro Call Center	:	(877) 783-7676	**Chemtrec (Emergency Contact)**	:	(800) 424-9300

SECTION 2. HAZARDS IDENTIFICATION

Classifications :

Flammable Liquid – Category 1 or 2 depending on formulation.
Aspiration Hazard – Category 1
Carcinogenicity – Category 2
Specific Target Organ Toxicity (Repeated Exposure) – Category 2
Specific Target Organ Toxicity (Single Exposure) – Category 3
Skin Irritation – Category 2
Eye Irritation – Category 2B
Chronic Aquatic Toxicity – Category 2

Pictograms :

Signal Word : **Danger**

Hazard Statements

Extremely flammable liquid and vapor.
May be fatal if swallowed and enters airways – do not siphon gasoline by mouth.
Suspected of causing blood cancer if repeated over-exposure by inhalation and/or skin contact occurs.
May cause damage to liver, kidneys and nervous system by repeated and prolonged inhalation or skin contact. Causes eye irritation. Can be absorbed through skin.
May cause drowsiness or dizziness. Extreme exposure such as intentional inhalation may cause unconsciousness, asphyxiation and death.
Repeated or prolonged skin contact can cause irritation and dermatitis.

Harmful to aquatic life.

Precautionary statements

Prevention : Obtain special instructions before use.
Do not handle until all safety precautions have been read and understood.
Keep away from heat, sparks, open flames, welding and hot surfaces.
No smoking.
Keep container tightly closed.
Ground and/or bond container and receiving equipment.
Use explosion-proof electrical equipment.
Use only non-sparking tools (if tools are used in flammable atmosphere).
Take precautionary measures against static discharge.
Wear gloves, eye protection and face protection (as needed to prevent skin and eye contact with liquid).
Wash hands or liquid-contacted skin thoroughly after handling.
Do not eat, drink or smoke when using this product.
Do not breathe vapors.
Use only outdoors or in a well-ventilated area.

Response : In case of fire: Use dry chemical, CO2, water spray or fire fighting foam to extinguish.
If swallowed: Immediately call a poison center, doctor, hospital emergency room, medical clinic or 911. Do NOT induce vomiting. Rinse mouth.
If on skin (or hair): Take off immediately all contaminated clothing. Rinse skin with water/shower.
If in eye: Rinse cautiously with water for several minutes. Remove contact lenses, if present and easy to do. Continue rinsing.
If skin or eye irritation persists, get medical attention.
If inhaled: Remove person to fresh air and keep comfortable for breathing.
Get medical attention if you feel unwell.

Storage : Store in a well ventilated place. Keep cool. Store locked up. Keep container tightly closed . Use only approved containers. Some containers not approved for gasoline may dissolve and release flammable gasoline liquid and vapors.

Disposal : Dispose of contents/containers to approved disposal site in accordance with local, regional, national, and/or international regulations.

SECTION 3. COMPOSITION/INFORMATION ON INGREDIENTS

Component	CAS-No.	Weight %
Gasoline, natural; Low boiling point naphtha	8006-61-9	10 - 30%
Toluene	108-88-3	10 - 30%
Xylene	1330-20-7	10 - 30%
Ethanol; ethyl alcohol	64-17-5	0-8.2%
Trimethylbenzene	25551-13-7	1 - 5%
Isopentane; 2-methylbutane	78-78-4	1 - 5%

Naphthalene	91-20-3	1 - 5%
Benzene	71-43-2	Less than 1.3%
Pentane	109-66-0	1 - 5%
Cyclohexane	110-82-7	1 - 5%
Ethylbenzene	100-41-4	1 - 5%
Butane	106-97-8	1 - 20%
Heptane [and isomers]	142-82-5	0.5 - 0.75%
N-hexane	110-54-3	0.5 - 0.75%

SECTION 4. FIRST AID MEASURES

Inhalation : If inhaled, remove to fresh air. If not breathing, give artificial respiration. If breathing is difficult, give oxygen. Seek medical attention immediately.

Skin contact : In case of contact, immediately flush skin with plenty of water. Take off contaminated clothing and shoes immediately. Wash contaminated clothing before re-use. Contaminated leather, particularly footwear, must be discarded. Note that contaminated clothing may be a fire hazard. Seek medical advice if symptoms persist or develop.

Eye contact : Remove contact lenses. Rinse immediately with plenty of water, also under the eyelids, for at least 15 minutes. Seek medical advice if symptoms persist or develop.

Ingestion : Do NOT induce vomiting. Never give anything by mouth to an unconscious person. Obtain medical attention.

Notes to physician : Symptoms: Dizziness, Discomfort, Headache, Nausea, Kidney disorders, Liver disorders. Aspiration may cause pulmonary edema and pneumonitis. Swallowing gasoline is more likely to be fatal for small children than adults, even if aspiration does not occur.

SECTION 5. FIRE-FIGHTING MEASURES

Suitable extinguishing media : SMALL FIRES: Any extinguisher suitable for Class B fires, dry chemical, CO2, water spray or fire fighting foam. LARGE FIRES: Water spray, fog or fire fighting foam. Water may be ineffective for fighting the fire, but may be used to cool fire-exposed containers. Keep containers and surroundings cool with water spray.

Specific hazards during fire fighting : Extremely flammable liquid and vapor. This material is combustible/flammable and is sensitive to fire, heat, and static discharge.

Special protective equipment for fire-fighters : Firefighting activities that may result in potential exposure to high heat, smoke or toxic by-products of combustion should require NIOSH/MSHA- approved pressure-demand self-contained breathing apparatus with full facepiece and full protective clothing.

Further information	:	Isolate area around container involved in fire. Cool tanks, shells, and containers exposed to fire and excessive heat with water. For massive fires the use of unmanned hose holders or monitor nozzles may be advantageous to further minimize personnel exposure. Major fires may require withdrawal, allowing the tank to burn. Large storage tank fires typically require specially trained personnel and equipment to extinguish the fire, often including the need for properly applied fire fighting foam. Exposure to decomposition products may be a hazard to health. Use extinguishing measures that are appropriate to local circumstances and the surrounding environment. Use water spray to cool unopened containers. Fire residues and contaminated fire extinguishing water must be disposed of in accordance with local regulations.

SECTION 6. ACCIDENTAL RELEASE MEASURES

Personal precautions	:	Evacuate personnel to safe areas. Ventilate the area. Remove all sources of ignition. Response and clean-up crews must be properly trained and must utilize proper protective equipment (see Section 8).
Environmental precautions	:	Discharge into the environment must be avoided. If the product contaminates rivers and lakes or drains inform respective authorities.
Methods for cleaning up	:	Contain and collect spillage with non-combustible absorbent material, (e.g. sand, earth, diatomaceous earth, vermiculite) and place in container for disposal according to local / national regulations.

SECTION 7. HANDLING AND STORAGE

Precautions for safe handling :

Keep away from fire, sparks and heated surfaces. No smoking near areas where material is stored or handled. The product should only be stored and handled in areas with intrinsically safe electrical classification.

Hydrocarbon liquids including this product can act as a non-conductive flammable liquid (or static accumulators), and may form ignitable vapor-air mixtures in storage tanks or other containers. Precautions to prevent static-initated fire or explosion during transfer, storage or handling, include but are not limited to these examples:

(1) Ground and bond containers during product transfers. Grounding and bonding may not be adequate protection to prevent ignition or explosion of hydrocarbon liquids and vapors that are static accumulators.

(2) Special slow load procedures for "switch loading" must be followed to avoid the static ignition hazard that can exist when higher flash point material (such as fuel oil or diesel) is loaded into tanks previously containing low flash point products (such gasoline or naphtha).

(3) Storage tank level floats must be effectively bonded.

For more information on precautions to prevent static-initated fire or explosion, see NFPA 77, Recommended Practice on Static Electricity (2007), and API Recommended Practice 2003, Protection Against Ignitions Arising Out of Static, Lightning, and Stray Currents (2008).

Conditions for safe storage, including incompatibilities : Keep away from flame, sparks, excessive temperatures and open flame. Use approved containers. Keep containers closed and clearly labeled. Empty or partially full product containers or vessels may contain explosive vapors. Do not pressurize, cut, heat, weld or expose containers to sources of ignition. Store in a well-ventilated area. The storage area should comply with NFPA 30 "Flammable and Combustible Liquid Code". The cleaning of tanks previously containing this product should follow API Recommended Practice (RP) 2013 "Cleaning Mobile Tanks In Flammable and Combustible Liquid Service" and API RP 2015 "Cleaning Petroleum Storage Tanks".

Reports suggest that government-mandated ethanol, if present, may not be compatible with fiberglass gasoline tanks. Ethanol may dissolve fiberglass resin, causing engine damage and possibly allow leakage of explosive gasoline.

Keep away from food, drink and animal feed. Incompatible with oxidizing agents. Incompatible with acids.

No decomposition if stored and applied as directed. Emergency eye wash capability should be available in the near proximity to operations presenting a potential splash exposure. Store only in containers approved and labeled for gasoline.

SECTION 8. EXPOSURE CONTROLS / PERSONAL PROTECTION

Exposure Guidelines

List	Components	CAS-No.	Type:	Value
OSHA	Benzene	71-43-2	TWA	1 ppm
		71-43-2	STEL	5 ppm
		71-43-2	OSHA_ACT	0.5 ppm
OSHA Z1	Xylene	1330-20-7	PEL	100 ppm 435 mg/m3
	Ethanol; Ethyl alcohol	64-17-5	PEL	1,000 ppm 1,900 mg/m3
	Naphthalene	91-20-3	PEL	10 ppm 50 mg/m3
	Cyclohexane	110-82-7	PEL	300 ppm 1,050 mg/m3
	Ethylbenzene	100-41-4	PEL	100 ppm 435 mg/m3
	Heptane [and isomers]	142-82-5	PEL	500 ppm 2,000 mg/m3
	N-hexane	110-54-3	PEL	500 ppm 1,800 mg/m3
ACGIH	Toluene	108-88-3	TWA	50 ppm
	Xylene	1330-20-7	TWA	100 ppm
		1330-20-7	STEL	150 ppm
	Ethanol; Ethyl alcohol	64-17-5	TWA	1,000 ppm
	Trimethylbenzene	25551-13-7	TWA	25 ppm
	Isopentane; 2-Methylbutane	78-78-4	TWA	600 ppm
	Naphthalene	91-20-3	TWA	10 ppm
		91-20-3	STEL	15 ppm
	Benzene	71-43-2	TWA	0.5 ppm
		71-43-2	STEL	2.5 ppm
	Pentane	109-66-0	TWA	600 ppm
	Cyclohexane	110-82-7	TWA	100 ppm
	Ethylbenzene	100-41-4	TWA	100 ppm
		100-41-4	STEL	125 ppm
	Heptane [and isomers]	142-82-5	TWA	400 ppm
		142-82-5	STEL	500 ppm

	N-hexane	110-54-3	TWA	50 ppm

Engineering measures : Use adequate ventilation to keep gas and vapor concentrations of this product below occupational exposure and flammability limits, particularly in confined spaces. Use only intrinsically safe electrical equipment approved for use in classified areas.

Eye protection : Safety glasses or goggles are recommended where there is a possibility of splashing or spraying. Ensure that eyewash stations and safety showers are close to the workstation location.

Hand protection : Gloves constructed of nitrile or neoprene are recommended. Consult manufacturer specifications for further information.

Skin and body protection : If needed to prevent skin contact, chemical protective clothing such as of DuPont TyChem®, Saranex or equivalent recommended based on degree of exposure. Flame resistant clothing such as Nomex ® is recommended in areas where material is stored or handled.

Respiratory protection : A NIOSH/ MSHA-approved air-purifying respirator with organic vapor cartridges or canister may be permissible under certain circumstances where airborne concentrations are or may be expected to exceed exposure limits or for odor or irritation. Protection provided by air-purifying respirators is limited. Refer to OSHA 29 CFR 1910.134, ANSI Z88.2-1992, NIOSH Respirator Decision Logic, and the manufacturer for additional guidance on respiratory protection selection. Use a NIOSH/ MSHA-approved positive-pressure supplied-air respirator if there is a potential for uncontrolled release, exposure levels are not known, in oxygen-deficient atmospheres, or any other circumstance where an air-purifying respirator may not provide adequate protection.

Work / Hygiene practices : Emergency eye wash capability should be available in the near proximity to operations presenting a potential splash exposure. Use good personal hygiene practices. Avoid repeated and/or prolonged skin exposure. Wash hands before eating, drinking, smoking, or using toilet facilities. Do not use as a cleaning solvent on the skin. Do not use solvents or harsh abrasive skin cleaners for washing this product from exposed skin areas. Waterless hand cleaners are effective. Promptly remove contaminated clothing and launder before reuse. Use care when laundering to prevent the formation of flammable vapors which could ignite via washer or dryer. Consider the need to discard contaminated leather shoes and gloves.

SECTION 9. PHYSICAL AND CHEMICAL PROPERTIES

Appearance : Clear to straw colored liquid

Odor : Characteristic hydrocarbon-like

Odor threshold 0.5 - 1.1 ppm

pH : Not applicable

Melting point/freezing point About -101°C (-150°F)

Initial boiling point & range Boiling point varies: 30 – 200°C (85 – 392°F)

Flash point < -21°C (-5.8°F)

Evaporation rate : Higher initially and declining as lighter components evaporate

Flammability (solid, gas) : Flammable vapor released by liquid

Upper explosive limit	7.6 %(V)
Lower explosive limit	1.3 %(V)
Vapor pressure	345 - 1,034 hPa at 37.8 °C (100.0 °F)
Vapor density (air = 1)	Approximately 3 to 4
Relative density (water = 1)	0.8 g/mL
Solubility (in water)	Negligible
Partition coefficient (n-octanol/water)	2 – 7 as log Pow
Auto-ignition temperature	Approximately 250°C (480°F)
Decomposition temperature	Will evaporate or boil and possibly ignite before decomposition occurs.
Kinematic viscosity	0.64 to 0.88 mm²/s range reported for gasoline
Conductivity (conductivity can be reduced by environmental factors such as a decrease in temperature)	: Hydrocarbon liquids without static dissipater additive may have conductivity below 1 picoSiemens per meter (pS/m). The highest electro-static ignition risks are associated with "ultra-low conductivities" below 5 pS/m. See Section 7 for sources of information on defining safe loading and handling procedures for low conductivity products.

SECTION 10. STABILITY AND REACTIVITY

Reactivity	: Vapors may form explosive mixture with air. Hazardous polymerization does not occur.
Chemical stability	: Stable under normal conditions.
Possibility of hazardous reactions	Can react with strong oxidizing agents, peroxides, alkaline products and strong acids. Contact with nitric and sulfuric acids will form nitrocresols that can decompose violently.
Conditions to avoid	: Avoid high temperatures, open flames, sparks, welding, smoking and other ignition sources. Avoid static charge accumulation and discharge (see Section 7).
Hazardous decomposition products	: Ignition and burning can release carbon monoxide, carbon dioxide and non-combusted hydrocarbons (smoke).

SECTION 11. TOXICOLOGICAL INFORMATION

Skin contact	: Irritating to skin. Can be partially absorbed through skin.
Eye contact	: Irritating to eyes.
Ingestion	: Aspiration hazard if liquid is inhaled into lungs, particularly from vomiting after ingestion. Aspiration may result in chemical pneumonia, severe lung damage, respiratory failure and even death. Ingestion may cause gastrointestinal disturbances, including irritation, nausea, vomiting and diarrhea, and central nervous (brain) effects similar to alcohol intoxication. In severe cases, tremors, convulsions, loss of consciousness, coma, respiratory arrest and death may occur.

Inhalation and further information

Acute toxicity of benzene results primarily from depression of the central nervous system (CNS). Inhalation of concentrations over 50 ppm can produce headache, lassitude, weariness, dizziness, drowsiness, over excitation. Exposure to very high levels can result in unconsciousness and death.

Repeated over-exposure may cause liver and kidney injuries.
Components of the product may affect the nervous system.

IARC has determined that gasoline and gasoline exhaust are possibly carcinogenic in humans. Inhalation exposure to completely vaporized unleaded gasoline caused kidney cancers in male rats and liver tumors in female mice. The U.S. EPA has determined that the male kidney tumors are species-specific and are irrelevant for human health risk assessment. The significance of the tumors seen in female mice is not known. Exposure to light hydrocarbons in the same boiling range as this product has been associated in animal studies with effects to the central and peripheral nervous systems, liver, and kidneys. The significance of these animal models to predict similar human response to gasoline is uncertain.
This product contains benzene. Human health studies indicate that prolonged and/or repeated overexposure to benzene may cause damage to the blood-forming system (particularly bone marrow), and serious blood disorders such as aplastic anemia and leukemia. Benzene is listed as a human carcinogen by the NTP, IARC, OSHA and ACGIH.

Component:

Gasoline, natural; Low boiling point naphtha	8006-61-9	Acute oral toxicity: LD50 rat Dose: 18.8 mg/kg Acute inhalation toxicity: LC50 rat Dose: 20.7 mg/l Exposure time: 4 h Skin irritation: Classification: Irritating to skin. Result: Mild skin irritation Eye irritation: Classification: Irritating to eyes. Result: Moderate eye irritation
Toluene	108-88-3	Acute oral toxicity: LD50 rat Dose: 636 mg/kg Acute dermal toxicity: LD50 rabbit Dose: 12,124 mg/kg Acute inhalation toxicity: LC50 rat Dose: 49 mg/l Exposure time: 4 h Skin irritation: Classification: Irritating to skin. Result: Mild skin irritation Prolonged skin contact may defat the skin and produce dermatitis. Eye irritation: Classification: Irritating to eyes. Result: Mild eye irritation
Xylene	1330-20-7	Acute oral toxicity: LD50 rat Dose: 2,840 mg/kg Acute dermal toxicity: LD50 rabbit Dose: ca. 4,500 mg/kg Acute inhalation toxicity: LC50 rat Dose: 6,350 mg/l Exposure time: 4 h Skin irritation: Classification: Irritating to skin. Result: Mild skin irritation

		Repeated or prolonged exposure may cause skin irritation and dermatitis, due to degreasing properties of the product. Eye irritation: Classification: Irritating to eyes. Result: Mild eye irritation
Ethanol; Ethyl alcohol	64-17-5	Acute oral toxicity: LD50 rat Dose: 6,200 mg/kg Acute dermal toxicity: LD50 rabbit Dose: 19,999 mg/kg Acute inhalation toxicity: LC50 rat Dose: 8,001 mg/l Exposure time: 4 h Skin irritation: Classification: Irritating to skin. Result: Mild skin irritation Prolonged skin contact may cause skin irritation and/or dermatitis. Eye irritation: Classification: Irritating to eyes. Result: Mild eye irritation Mild eye irritation
Naphthalene	91-20-3	Acute oral toxicity: LD50 rat Dose: 2,001 mg/kg Acute dermal toxicity: LD50 rat Dose: 2,501 mg/kg Acute inhalation toxicity: LC50 rat Dose: 101 mg/l Exposure time: 4 h Skin irritation: Classification: Irritating to skin. Result: Mild skin irritation Eye irritation: Classification: Irritating to eyes. Result: Mild eye irritation Carcinogenicity: N11.00422130
Benzene	71-43-2	Acute oral toxicity: LD50 rat Dose: 930 mg/kg Acute inhalation toxicity: LC50 rat Dose: 44 mg/l Exposure time: 4 h Skin irritation: Classification: Irritating to skin. Result: Mild skin irritation Repeated or prolonged exposure may cause skin irritation and dermatitis, due to degreasing properties of the product. Eye irritation: Classification: Irritating to eyes. Result: Risk of serious damage to eyes.
Pentane	109-66-0	Acute oral toxicity: LD50 rat Dose: 2,001 mg/kg Acute inhalation toxicity: LC50 rat Dose: 364 mg/l Exposure time: 4 h Skin irritation: Repeated or prolonged exposure may cause skin irritation and dermatitis, due to degreasing properties of the product. Eye irritation: Classification: Irritating to eyes. Result: Mild eye irritation
Cyclohexane	110-82-7	Acute dermal toxicity: LD50 rabbit Dose: 2,001 mg/kg Acute inhalation toxicity: LC50 rat Dose: 14 mg/l Exposure time: 4 h

		Skin irritation: Classification: Irritating to skin. Result: Skin irritation Eye irritation: Classification: Irritating to eyes. Result: Mild eye irritation
Ethylbenzene	100-41-4	Acute oral toxicity: LD50 rat Dose: 3,500 mg/kg Acute dermal toxicity: LD50 rabbit Dose: 15,500 mg/kg Acute inhalation toxicity: LC50 rat Dose: 18 mg/l Exposure time: 4 h Skin irritation: Classification: Irritating to skin. Result: Mild skin irritation Eye irritation: Classification: Irritating to eyes. Result: Risk of serious damage to eyes.
Heptane [and isomers]	142-82-5	Acute oral toxicity: LD50 rat Dose: 15,001 mg/kg Acute inhalation toxicity: LC50 rat Dose: 103 g/m3 Exposure time: 4 h Skin irritation: Classification: Irritating to skin. Result: Skin irritation Repeated or prolonged exposure may cause skin irritation and dermatitis, due to degreasing properties of the product. Eye irritation: Classification: Irritating to eyes. Result: Mild eye irritation
N-hexane	110-54-3	Acute oral toxicity: LD50 rat Dose: 25,000 mg/kg Acute dermal toxicity: LD50 rabbit Dose: 2,001 mg/kg Acute inhalation toxicity: LC50 rat Dose: 171.6 mg/l Exposure time: 4 h Skin irritation: Classification: Irritating to skin. Result: Skin irritation Eye irritation: Classification: Irritating to eyes. Result: Mild eye irritation Teratogenicity: N11.00418960

Carcinogenicity

NTP	:	Naphthalene (CAS-No.: 91-20-3) Benzene (CAS-No.: 71-43-2)
IARC	:	Gasoline, natural; Low boiling point naphtha (CAS-No.: 8006-61-9) Naphthalene (CAS-No.: 91-20-3) Benzene (CAS-No.: 71-43-2) Ethylbenzene (CAS-No.: 100-41-4)
OSHA	:	Benzene (CAS-No.: 71-43-2)
CA Prop 65	:	WARNING! This product contains a chemical known to the State of California to cause birth defects or other reproductive harm. Toluene (CAS-No.: 108-88-3)

Benzene (CAS-No.: 71-43-2)

SECTION 12. ECOLOGICAL INFORMATION

Additional ecological information : Keep out of sewers, drainage areas, and waterways. Report spills and releases, as applicable, under Federal and State regulations.

Component:

Toluene	108-88-3	Toxicity to fish: LC50 Species: Carassius auratus (goldfish) Dose: 13 mg/l Exposure time: 96 h Acute and prolonged toxicity for aquatic invertebrates: EC50 Species: Daphnia magna (Water flea) Dose: 11.5 mg/l Exposure time: 48 h Toxicity to algae: IC50 Species: Selenastrum capricornutum (green algae) Dose: 12 mg/l Exposure time: 72 h
Ethanol; Ethyl alcohol	64-17-5	Toxicity to fish: LC50 Species: Leuciscus idus (Golden orfe) Dose: 8,140 mg/l Exposure time: 48 h Acute and prolonged toxicity for aquatic invertebrates: EC50 Species: Daphnia magna (Water flea) Dose: 9,268 - 14,221 mg/l Exposure time: 48 h
Isopentane; 2-Methylbutane	78-78-4	Toxicity to fish: LC50 Species: Oncorhynchus mykiss (rainbow trout) Dose: 3.1 mg/l Exposure time: 96 h Acute and prolonged toxicity for aquatic invertebrates: EC50 Species: Daphnia magna (Water flea) Dose: 2.3 mg/l Exposure time: 96 h
Naphthalene	91-20-3	Toxicity to algae: EC50 Species: Dose: 33 mg/l Exposure time: 24 h
Pentane	109-66-0	Acute and prolonged toxicity for aquatic invertebrates: EC50 Species: Daphnia magna (Water flea) Dose: 9.74 mg/l Exposure time: 48 h
Cyclohexane	110-82-7	Acute and prolonged toxicity for aquatic invertebrates: EC50 Species: Daphnia magna (Water flea) Dose: 3.78 mg/l Exposure time: 48 h

Heptane [and isomers]	142-82-5	Toxicity to fish: LC50 Species: Carassius auratus (goldfish) Dose: 4 mg/l Exposure time: 24 h Acute and prolonged toxicity for aquatic invertebrates: EC50 Species: Daphnia magna (Water flea) Dose: 1.5 mg/l Exposure time: 48 h
N-hexane	110-54-3	Toxicity to fish: LC50 Species: Pimephales promelas (fathead minnow) Dose: 2.5 mg/l Exposure time: 96 h Acute and prolonged toxicity for aquatic invertebrates: EC50 Species: Daphnia magna (Water flea) Dose: 2.1 mg/l Exposure time: 48 h

SECTION 13. DISPOSAL CONSIDERATIONS

Disposal : Dispose of container and unused contents in accordance with federal, state and local requirements.

SECTION 14. TRANSPORT INFORMATION

CFR

Proper shipping name	: Petrol
UN-No.	: 1203
Class	: 3
Packing group	: II

TDG

Proper shipping name	: Gasoline
UN-No.	: UN1203
Class	: 3
Packing group	: II

IATA Cargo Transport

UN UN-No.	: UN1203
Description of the goods	: Gasoline
Class	: 3
Packaging group	: II
ICAO-Labels	: 3
Packing instruction (cargo aircraft)	: 364
Packing instruction (cargo aircraft)	: Y341

IATA Passenger Transport

UN UN-No.	: UN1203
Description of the goods	: Gasoline
Class	: 3

Packaging group	:	II
ICAO-Labels	:	3
Packing instruction (passenger aircraft)	:	353
Packing instruction (passenger aircraft)	:	Y341

IMDG-Code

UN-No.	:	UN 1203
Description of the goods	:	Gasoline
Class	:	3
Packaging group	:	II
IMDG-Labels	:	3
EmS Number	:	F-E S-E
Marine pollutant	:	No

SECTION 15. REGULATORY INFORMATION

OSHA Hazards : Flammable liquid
Highly toxic by ingestion
Moderate skin irritant
Severe eye irritant
Carcinogen

TSCA Status : On TSCA Inventory

DSL Status : . All components are on the Canadian DSL list.

SARA 311/312 Hazards : Fire Hazard
Acute Health Hazard
Chronic Health Hazard

CERCLA SECTION 103 and SARA SECTION 304 (RELEASE TO THE ENVIROMENT)
The CERCLA definition of hazardous substances contains a "petroleum exclusion" clause which exempts crude oil. Fractions of crude oil, and products (both finished and intermediate) from the crude oil refining process and any indigenous components of such from the CERCLA Section 103 reporting requirements. However, other federal reporting requirements, including SARA Section 304, as well as the Clean Water Act may still apply.

California Prop. 65 : WARNING! This product contains a chemical known to the State of California to cause birth defects or other reproductive harm.

Toluene	108-88-3
Benzene	71-43-2

SECTION 16. OTHER INFORMATION

Further information

The information provided in this Safety Data Sheet is correct to the best of our knowledge, information and belief at the date of its publication. The information given is designed only as guidance for safe handling, use, processing, storage, transportation, disposal and release and is not to be considered a warranty or quality specification. The information relates only to the specific material designated and may not be valid for such material used in combination with any other materials or in any process, unless specified in the text.

Revision Date : 08/09/2012

6, 8, 10, 12, 14, 16, 64, 68, 91, 112, 306, 1092, 1106, 1500, 1570, 1571, 1651, 1652, 1654, 1700, 1701, 1702, 1710, 1711, 1714, 1726, 1729, 1730, 1732, 1733, 1826, 1848, 1880, 1950

SAFETY DATA SHEET

Creation Date 13-Feb-2015 **Revision Date** 21-Feb-2014 **Revision Number** 3

SECTION 1: IDENTIFICATION OF THE SUBSTANCE/MIXTURE AND OF THE COMPANY/UNDERTAKING

1.1. Product identification

Product Description: **Xylene**
Cat No. : **6601, 6615, 6655, 9900-5, 9900-55, 6601E**
Synonyms Dimethylbenzene; Methyltoluene
Molecular Formula C8H10

1.2. Relevant identified uses of the substance or mixture and uses advised against

Recommended Use Laboratory chemicals.
Uses advised against No Information available

1.3. Details of the supplier of the safety data sheet

Company Richard Allan Scientific
A Subsidiary of Thermo Fisher Scientific
4481 Campus Drive
Kalamazoo, MI 49008
Tel: (800) 522-7270
E-mail address begel.sdsdesk@thermofisher.com

1.4. Emergency telephone number

Chemtrec US: (800) 424-9300
Chemtrec EU: 001 (202) 483-7616

SECTION 2: HAZARDS IDENTIFICATION

2.1. Classification of the substance or mixture

CLP Classification - Regulation (EC) No 1272/2008

Physical hazards

Flammable liquids	Category 3

Health hazards

Aspiration Toxicity	Category 1
Acute dermal toxicity	Category 4
Acute Inhalation Toxicity - Vapors	Category 4
Skin Corrosion/irritation	Category 2
Specific target organ toxicity - (repeated exposure)	Category 2

Environmental hazards
Based on available data, the classification criteria are not met

Classification according to EU Directives 67/548/EEC or 1999/45/EC

Symbol(s) Xn - Harmful
R-phrase(s) R10 - Flammable
R38 - Irritating to skin
R20/21 - Harmful by inhalation and in contact with skin

For the full text of the R-phrases and H-Statements mentioned in this Section, see Section 16.

2.2. Label elements

Signal Word **Danger**

Hazard Statements

H226 - Flammable liquid and vapor
H312 - Harmful in contact with skin
H332 - Harmful if inhaled
H315 - Causes skin irritation
H304 - May be fatal if swallowed and enters airways
H373 - May cause damage to organs through prolonged or repeated exposure

Precautionary Statements

P210 - Keep away from heat/sparks/open flames/hot surfaces. - No smoking
P280 - Wear protective gloves/ protective clothing
P302 + P352 - IF ON SKIN: Wash with plenty of soap and water
P312 - Call a POISON CENTER or doctor/ physician if you feel unwell
P304 + P340 - IF INHALED: Remove to fresh air and keep at rest in a position comfortable for breathing
P301 + P310 - IF SWALLOWED: Immediately call a POISON CENTER or doctor/ physician
P331 - Do NOT induce vomiting
P362 - Take off contaminated clothing and wash before reuse
P260 - Do not breathe dust/fume/gas/mist/vapors/spray

2.3. Other hazards

No information available

SECTION 3: COMPOSITION/INFORMATION ON INGREDIENTS

Component	CAS-No	EC-No.	Weight %	CLP Classification - Regulation (EC) No 1272/2008	DSD Classification - 67/548/EEC
Ethylbenzene	100-41-4	EEC No. 202-849-4	10 - 15	Flam. Liq. 2 (H225) Acute Tox. 4 (H332) Asp. Tox. 1 (H304) STOT RE 2 (H373) Aquatic Chronic 3 (H412)	F; R11 Xn; R20-48/20 R65
Xylenes (o-, m-, p- isomers)	1330-20-7	EEC No. 215-535-7	85	Acute Tox. 4 (H312) Acute Tox. 4 (H332) Skin Irrit. 2 (H315) Flam. Liq. 3 (H226)	R10 Xn; R20/21 Xi; R38
Toluene	108-88-3	EEC No. 203-625-9	0 - 0.5	Skin Irrit. 2 (H315) Repr. 2 (H361d) STOT SE 3 (H336) STOT RE 2 (H373) Asp. Tox. 1 (H304) Flam. Liq. 2 (H225)	F; R11 Xi; R38 Xn; R48/20-65 Repr.Cat.3; R63 R67
Benzene	71-43-2	EEC No. 200-753-7	0 - 0.01	Skin Irrit. 2 (H315) Eye Irrit. 2 (H319) Muta. 1B (H340) Carc. 1A (H350) STOT RE 1 (H372)	F; R11 Xi; R36/38 Carc.Cat.1; R45 Muta.Cat.2; R46 T; R48/23/24/25

				Asp. Tox. 1 (H304) Flam. Liq. 2 (H225)	Xn; R65

For the full text of the R-phrases and H-Statements mentioned in this Section, see Section 16.

SECTION 4: FIRST AID MEASURES

4.1. Description of first aid measures

General Advice If symptoms persist, call a physician. Show this safety data sheet to the doctor in attendance.

Eye Contact Rinse immediately with plenty of water, also under the eyelids, for at least 15 minutes. Immediate medical attention is required. Immediately flush with plenty of water. After initial flushing, remove any contact lenses and continue flushing for at least 15 minutes. Keep eye wide open while rinsing. If symptoms persist, call a physician.

Skin Contact Wash off immediately with plenty of water for at least 15 minutes. Immediate medical attention is required. Call a physician immediately. SPEEDY ACTION IS CRITICAL, GET MEDICAL AID IMMEDIATELY. If symptoms persist, call a physician. If skin irritation persists, call a physician. Wash off immediately with soap and plenty of water while removing all contaminated clothes and shoes.

Ingestion Do not induce vomiting. Call a physician or Poison Control Center immediately. Clean mouth with water and drink afterwards plenty of water. Do not induce vomiting without medical advice. Never give anything by mouth to an unconscious person. Consult a physician.

Inhalation Move to fresh air. If breathing is difficult, give oxygen. Do not use mouth-to-mouth resuscitation if victim ingested or inhaled the substance; induce artificial respiration with a respiratory medical device. Immediate medical attention is required. Immediate medical attention is not required. Move to fresh air in case of accidental inhalation of vapors. If symptoms persist, call a physician.

Protection of First-aiders Use personal protective equipment.

4.2. Most important symptoms and effects, both acute and delayed

Breathing difficulties. Symptoms of overexposure may be headache, dizziness, tiredness, nausea and vomiting

4.3. Indication of any immediate medical attention and special treatment needed

Notes to Physician Treat symptomatically.

SECTION 5: FIREFIGHTING MEASURES

5.1. Extinguishing media

Suitable Extinguishing Media
CO_2, dry chemical, dry sand, alcohol-resistant foam. Cool closed containers exposed to fire with water spray.

Extinguishing media which must not be used for safety reasons
No information available.

5.2. Special hazards arising from the substance or mixture

Flammable. Risk of ignition. Vapors may form explosive mixtures with air. Vapors may travel to source of ignition and flash back. Containers may explode when heated. Keep product and empty container away from heat and sources of ignition.

Hazardous Combustion Products
Carbon monoxide (CO), Carbon dioxide (CO_2), Hydrocarbons, Aldehydes.

5.3. Advice for firefighters

As in any fire, wear self-contained breathing apparatus pressure-demand, MSHA/NIOSH (approved or equivalent) and full protective gear. Thermal decomposition can lead to release of irritating gases and vapors.

SECTION 6: ACCIDENTAL RELEASE MEASURES

6.1. Personal precautions, protective equipment and emergency procedures

Use personal protective equipment. Remove all sources of ignition. Take precautionary measures against static discharges. Do not get in eyes, on skin, or on clothing. Evacuate personnel to safe areas. Keep people away from and upwind of spill/leak.

6.2. Environmental precautions

Should not be released into the environment. See Section 12 for additional ecological information. Do not flush into surface water or sanitary sewer system. Prevent further leakage or spillage if safe to do so. Prevent product from entering drains.

6.3. Methods and material for containment and cleaning up

Remove all sources of ignition. Soak up with inert absorbent material. Take precautionary measures against static discharges. Keep in suitable, closed containers for disposal.

6.4. Reference to other sections

Refer to protective measures listed in Sections 8 and 13.

SECTION 7: HANDLING AND STORAGE

7.1. Precautions for safe handling

Use only under a chemical fume hood. Wear personal protective equipment. Keep away from open flames, hot surfaces and sources of ignition. Take precautionary measures against static discharges. Do not breathe vapors or spray mist. Do not get in eyes, on skin, or on clothing. Do not ingest. Pay attention to flashback. No information available. Do not take internally.

7.2. Conditions for safe storage, including any incompatibilities

Keep containers tightly closed in a dry, cool and well-ventilated place. Keep away from heat and sources of ignition. Flammables area. Keep containers tightly closed in a cool, well-ventilated place. Keep in properly labeled containers.

7.3. Specific end use(s)

Use in laboratories

SECTION 8: EXPOSURE CONTROLS/PERSONAL PROTECTION

8.1. Control parameters

Exposure limits

Component	European Union	The United Kingdom	France	Belgium	Spain
Ethylbenzene	TWA: 100 ppm 8 hr TWA: 442 mg/m³ 8 hr STEL: 200 ppm 15 min STEL: 884 mg/m³ 15 min Possibility of significant uptake through the skin	STEL: 125 ppm 15 min STEL: 552 mg/m³ 15 min TWA: 100 ppm 8 hr TWA: 441 mg/m³ 8 hr Skin	TWA / VME: 20 ppm (8 heures). restrictive limit TWA / VME: 88.4 mg/m³ (8 heures). restrictive limit TWA / VME: 1000 mg/m³ (8 heures). STEL / VLCT: 100 ppm. restrictive limit STEL / VLCT: 442	TWA: 100 ppm 8 uren TWA: 442 mg/m³ 8 uren STEL: 125 ppm 15 minuten STEL: 551 mg/m³ 15 minuten Huid	STEL / VLA-EC: 200 ppm (15 minutos). STEL / VLA-EC: 884 mg/m³ (15 minutos). TWA / VLA-ED: 100 ppm (8 horas) TWA / VLA-ED: 441 mg/m³ (8 horas) Piel

			mg/m³. restrictive limit STEL / VLCT: 1500 mg/m³. Peau		
Xylenes (o-, m-, p-isomers)	TWA: 50 ppm 8 hr TWA: 221 mg/m³ 8 hr STEL: 100 ppm 15 min STEL: 442 mg/m³ 15 min Possibility of significant uptake through the skin	STEL: 100 ppm 15 min STEL: 441 mg/m³ 15 min TWA: 50 ppm 8 hr TWA: 220 mg/m³ 8 hr Skin	TWA / VME: 50 ppm (8 heures). restrictive limit TWA / VME: 221 mg/m³ (8 heures). restrictive limit TWA / VME: 1000 mg/m³ (8 heures). STEL / VLCT: 100 ppm. restrictive limit STEL / VLCT: 442 mg/m³. restrictive limit STEL / VLCT: 1500 mg/m³. Peau	TWA: 50 ppm 8 uren TWA: 221 mg/m³ 8 uren STEL: 100 ppm 15 minuten STEL: 442 mg/m³ 15 minuten Huid	STEL / VLA-EC: 100 ppm (15 minutos). STEL / VLA-EC: 442 mg/m³ (15 minutos). TWA / VLA-ED: 50 ppm (8 horas) TWA / VLA-ED: 221 mg/m³ (8 horas) Piel
Toluene	TWA: 50 ppm 8 hr TWA: 192 mg/m³ 8 hr STEL: 100 ppm 15 min STEL: 384 mg/m³ 15 min Skin	STEL: 100 ppm 15 min STEL: 384 mg/m³ 15 min TWA: 50 ppm 8 hr TWA: 191 mg/m³ 8 hr Skin	TWA / VME: 20 ppm (8 heures). restrictive limit TWA / VME: 76.8 mg/m³ (8 heures). restrictive limit TWA / VME: 1000 mg/m³ (8 heures). STEL / VLCT: 100 ppm. restrictive limit STEL / VLCT: 384 mg/m³. restrictive limit STEL / VLCT: 1500 mg/m³. Peau	TWA: 20 ppm 8 uren TWA: 77 mg/m³ 8 uren STEL: 100 ppm 15 minuten STEL: 384 mg/m³ 15 minuten Huid	STEL / VLA-EC: 100 ppm (15 minutos). STEL / VLA-EC: 384 mg/m³ (15 minutos). TWA / VLA-ED: 50 ppm (8 horas) TWA / VLA-ED: 192 mg/m³ (8 horas) Piel
Benzene	TWA: 1 ppm 8 hr measured or calculated in relation to a reference period of eight hours TWA: 3.25 mg/m³ 8 hr measured or calculated in relation to a reference period of eight hours Substantial contribution to the total body burden via dermal exposure possible	STEL: 3 ppm 15 min STEL: 9.75 mg/m³ 15 min TWA: 1 ppm 8 hr TWA: 3.25 mg/m³ 8 hr Carc. Skin	TWA / VME: 1 ppm (8 heures). restrictive limit TWA / VME: 3.25 mg/m³ (8 heures). restrictive limit TWA / VME: 1000 mg/m³ (8 heures). STEL / VLCT: 1500 mg/m³. Peau	TWA: 1 ppm 8 uren TWA: 3.25 mg/m³ 8 uren Huid	TWA / VLA-ED: 1 ppm (8 horas) TWA / VLA-ED: 3.25 mg/m³ (8 horas) Piel

Component	Italy	Germany	Portugal	The Netherlands	Finland
Ethylbenzene	TWA: 100 ppm 8 ore. TWA: 442 mg/m³ 8 ore. STEL: 200 ppm 15 minuti. Breve termine STEL: 884 mg/m³ 15 minuti. Breve termine Pelle	TWA: 20 ppm (8 Stunden). AGW - exposure factor 2 TWA: 88 mg/m³ (8 Stunden). AGW - exposure factor 2 TWA: 20 ppm (8 Stunden). MAK TWA: 88 mg/m³ (8 Stunden). MAK Höhepunkt: 40 ppm Höhepunkt: 176 mg/m³ Haut	STEL: 200 ppm 15 minutos STEL: 884 mg/m³ 15 minutos TWA: 100 ppm 8 horas TWA: 442 mg/m³ 8 horas Pele	huid STEL: 430 mg/m³ 15 minuten TWA: 215 mg/m³ 8 uren	TWA: 50 ppm 8 tunteina TWA: 220 mg/m³ 8 tunteina STEL: 200 ppm 15 minuutteina STEL: 880 mg/m³ 15 minuutteina Iho
Xylenes (o-, m-, p-isomers)	TWA: 50 ppm 8 ore. pure TWA: 221 mg/m³ 8 ore. pure STEL: 100 ppm 15 minuti. Breve termine pure STEL: 442 mg/m³ 15 minuti. Breve termine pure Pelle	TWA: 100 ppm (8 Stunden). AGW - exposure factor 2 TWA: 440 mg/m³ (8 Stunden). AGW - exposure factor 2 TWA: 100 ppm (8 Stunden). MAK all isomers TWA: 440 mg/m³ (8 Stunden). MAK all isomers	STEL: 100 ppm 15 minutos STEL: 442 mg/m³ 15 minutos TWA: 50 ppm 8 horas TWA: 221 mg/m³ 8 horas Pele	huid STEL: 442 mg/m³ 15 minuten TWA: 210 mg/m³ 8 uren	TWA: 50 ppm 8 tunteina TWA: 220 mg/m³ 8 tunteina STEL: 100 ppm 15 minuutteina STEL: 440 mg/m³ 15 minuutteina Iho

		Höhepunkt: 200 ppm Höhepunkt: 880 mg/m³ Haut Haut all isomers			
Toluene	TWA: 50 ppm 8 ore. TWA: 192 mg/m³ 8 ore. Pelle	TWA: 50 ppm (8 Stunden). AGW - exposure factor 4 TWA: 190 mg/m³ (8 Stunden). AGW - exposure factor 4 TWA: 50 ppm (8 Stunden). MAK TWA: 190 mg/m³ (8 Stunden). MAK Höhepunkt: 200 ppm Höhepunkt: 760 mg/m³ Haut	STEL: 100 ppm 15 minutos STEL: 384 mg/m³ 15 minutos TWA: 50 ppm 8 horas TWA: 192 mg/m³ 8 horas Pele	STEL: 384 mg/m³ 15 minuten TWA: 150 mg/m³ 8 uren	TWA: 25 ppm 8 tunteina TWA: 81 mg/m³ 8 tunteina STEL: 100 ppm 15 minuutteina STEL: 380 mg/m³ 15 minuutteina Iho
Benzene	TWA: 1 ppm 8 ore. TWA: 3.25 mg/m³ 8 ore. Pelle	Haut	STEL: 2.5 ppm 15 minutos TWA: 0.5 ppm 8 horas Pele	huid TWA: 3.25 mg/m³ 8 uren	TWA: 1 ppm 8 tunteina TWA: 3.25 mg/m³ 8 tunteina Iho

Component	Austria	Denmark	Switzerland	Poland	Norway
Ethylbenzene	Haut MAK-KZW: 200 ppm 15 Minuten MAK-KZW: 880 mg/m³ 15 Minuten MAK-TMW: 100 ppm 8 Stunden MAK-TMW: 440 mg/m³ 8 Stunden	TWA: 50 ppm 8 timer TWA: 217 mg/m³ 8 timer Hud	Haut/Peau STEL: 50 ppm 15 Minuten STEL: 220 mg/m³ 15 Minuten TWA: 50 ppm 8 Stunden TWA: 220 mg/m³ 8 Stunden	STEL: 400 mg/m³ 15 minutach TWA: 200 mg/m³ 8 godzinach	TWA: 5 ppm 8 timer TWA: 20 mg/m³ 8 timer STEL: 10 ppm 15 minutter. STEL: 30 mg/m³ 15 minutter. Hud
Xylenes (o-, m-, p-isomers)	Haut MAK-KZW: 100 ppm 15 Minuten MAK-KZW: 442 mg/m³ 15 Minuten MAK-TMW: 50 ppm 8 Stunden MAK-TMW: 221 mg/m³ 8 Stunden	TWA: 25 ppm 8 timer TWA: 109 mg/m³ 8 timer Hud	Haut/Peau STEL: 200 ppm 15 Minuten STEL: 870 mg/m³ 15 Minuten TWA: 100 ppm 8 Stunden TWA: 435 mg/m³ 8 Stunden	TWA: 100 mg/m³ 8 godzinach	TWA: 25 ppm 8 timer TWA: 108 mg/m³ 8 timer STEL: 37.5 ppm 15 minutter. STEL: 135 mg/m³ 15 minutter. Hud
Toluene	Haut MAK-KZW: 100 ppm 15 Minuten MAK-KZW: 380 mg/m³ 15 Minuten MAK-TMW: 50 ppm 8 Stunden MAK-TMW: 190 mg/m³ 8 Stunden	TWA: 25 ppm 8 timer TWA: 94 mg/m³ 8 timer Hud	Haut/Peau STEL: 200 ppm 15 Minuten STEL: 760 mg/m³ 15 Minuten TWA: 50 ppm 8 Stunden TWA: 190 mg/m³ 8 Stunden	STEL: 200 mg/m³ 15 minutach TWA: 100 mg/m³ 8 godzinach	TWA: 25 ppm 8 timer TWA: 94 mg/m³ 8 timer STEL: 37.5 ppm 15 minutter. STEL: 141 mg/m³ 15 minutter. Hud
Benzene	TRK-KZW: 4 ppm 15 Minuten TRK-KZW: 12.8 mg/m³ 15 Minuten Haut TRK-TMW: 1 ppm TRK-TMW: 3.2 mg/m³	TWA: 0.5 ppm 8 timer TWA: 1.6 mg/m³ 8 timer Hud	Haut/Peau TWA: 0.5 ppm 8 Stunden TWA: 1.6 mg/m³ 8 Stunden	TWA: 1.6 mg/m³ 8 godzinach	TWA: 1 ppm 8 timer TWA: 3 mg/m³ 8 timer STEL: 3 ppm 15 minutter. STEL: 6 mg/m³ 15 minutter.

Component	Bulgaria	Croatia	Ireland	Cyprus	Czech Republic
Ethylbenzene	TWA: 435 mg/m³ STEL : 545 mg/m³ Skin notation	kože TWA-GVI: 100 ppm 8 satima. TWA-GVI: 442 mg/m³ 8 satima. STEL-KGVI: 200 ppm 15 minutama. STEL-KGVI: 884 mg/m³ 15 minutama.	TWA: 100 ppm 8 hr. TWA: 442 mg/m³ 8 hr. STEL: 200 ppm 15 min STEL: 884 mg/m³ 15 min Skin	Skin-potential for cutaneous absorption STEL: 200 ppm STEL: 884 mg/m³ TWA: 100 ppm TWA: 442 mg/m³	TWA: 200 mg/m³ 8 hodinách. Potential for cutaneous absorption Ceiling: 500 mg/m³
Xylenes (o-, m-, p-	TWA: 50 ppm	kože	TWA: 50 ppm 8 hr.	Skin-potential for	TWA: 200 mg/m³ 8

isomers)	TWA: 221.0 mg/m³ STEL : 100 ppm STEL : 442 mg/m³ Skin notation	TWA-GVI: 50 ppm 8 satima. TWA-GVI: 221 mg/m³ 8 satima. STEL-KGVI: 100 ppm 15 minutama. STEL-KGVI: 442 mg/m³ 15 minutama.	TWA: 221 mg/m³ 8 hr. STEL: 100 ppm 15 min STEL: 442 mg/m³ 15 min Skin	cutaneous absorption STEL: 100 ppm STEL: 442 mg/m³ TWA: 50 ppm TWA: 221 mg/m³	hodinách. Potential for cutaneous absorption Ceiling: 400 mg/m³
Toluene	TWA: 50 ppm TWA: 192.0 mg/m³ STEL : 100 ppm STEL : 384.0 mg/m³ Skin notation	kože TWA-GVI: 50 ppm 8 satima. TWA-GVI: 192 mg/m³ 8 satima. STEL-KGVI: 100 ppm 15 minutama. STEL-KGVI: 384 mg/m³ 15 minutama.	TWA: 50 ppm 8 hr. TWA: 192 mg/m³ 8 hr. STEL: 384 mg/m³ 15 min STEL: 100 ppm 15 min Skin	Skin-potential for cutaneous absorption STEL: 100 ppm STEL: 384 mg/m³ TWA: 50 ppm TWA: 192 mg/m³	TWA: 200 mg/m³ 8 hodinách. Potential for cutaneous absorption Ceiling: 500 mg/m³
Benzene	TWA: 3.25 mg/m³ Skin notation	kože TWA-GVI: 1 ppm 8 satima. TWA-GVI: 3.25 mg/m³ 8 satima.	TWA: 1 ppm 8 hr. TWA: 3 mg/m³ 8 hr. STEL: 3 ppm 15 min STEL: 9 mg/m³ 15 min Skin	Skin-potential for cutaneous absorption TWA: 1 ppm TWA: 3.25 mg/m³	TWA: 3 mg/m³ 8 hodinách. Potential for cutaneous absorption Ceiling: 10 mg/m³

Component	Estonia	Gibraltar	Greece	Hungary	Iceland
Ethylbenzene	Nahk TWA: 100 ppm 8 tundides. TWA: 442 mg/m³ 8 tundides. STEL: 200 ppm 15 minutites. STEL: 884 mg/m³ 15 minutites. Ceiling: 0.01 ppm 5 min	Skin notation TWA: 100 ppm 8 hr TWA: 442 mg/m³ 8 hr STEL: 200 ppm 15 min STEL: 884 mg/m³ 15 min	STEL: 125 ppm STEL: 545 mg/m³ TWA: 100 ppm TWA: 435 mg/m³	STEL: 884 mg/m³ 15 percekben. CK TWA: 442 mg/m³ 8 órában. AK lehetséges borön keresztüli felszívódás	STEL: 200 ppm STEL: 884 mg/m³ TWA: 50 ppm 8 klukkustundum. TWA: 200 mg/m³ 8 klukkustundum. Skin notation Ceiling: 100 ppm Ceiling: 400 mg/m³
Xylenes (o-, m-, p-isomers)	Nahk TWA: 50 ppm 8 tundides. TWA: 221 mg/m³ 8 tundides. STEL: 100 ppm 15 minutites. STEL: 442 mg/m³ 15 minutites.	Skin notation TWA: 50 ppm 8 hr pure TWA: 221 mg/m³ 8 hr pure STEL: 100 ppm 15 min pure STEL: 442 mg/m³ 15 min pure	skin - potential for cutaneous absorption STEL: 150 ppm STEL: 650 mg/m³ TWA: 100 ppm TWA: 435 mg/m³	STEL: 442 mg/m³ 15 percekben. CK TWA: 221 mg/m³ 8 órában. AK lehetséges borön keresztüli felszívódás	STEL: 100 ppm STEL: 442 mg/m³ TWA: 25 ppm 8 klukkustundum. TWA: 109 mg/m³ 8 klukkustundum. Skin notation Ceiling: 50 ppm Ceiling: 218 mg/m³
Toluene	Nahk TWA: 50 ppm 8 tundides. TWA: 192 mg/m³ 8 tundides. STEL: 100 ppm 15 minutites. STEL: 384 mg/m³ 15 minutites.	Skin notation TWA: 50 ppm 8 hr TWA: 192 mg/m³ 8 hr STEL: 100 ppm 15 min STEL: 384 mg/m³ 15 min	skin - potential for cutaneous absorption STEL: 100 ppm STEL: 384 mg/m³ TWA: 50 ppm TWA: 192 mg/m³	STEL: 380 mg/m³ 15 percekben. CK TWA: 190 mg/m³ 8 órában. AK lehetséges borön keresztüli felszívódás	STEL: 50 ppm STEL: 188 mg/m³ TWA: 25 ppm 8 klukkustundum. TWA: 94 mg/m³ 8 klukkustundum. Skin notation Ceiling: 50 ppm Ceiling: 188 mg/m³
Benzene	Nahk TWA: 0.5 ppm 8 tundides. TWA: 1.5 mg/m³ 8 tundides. STEL: 3 ppm 15 minutites. STEL: 9 mg/m³ 15 minutites.		skin - potential for cutaneous absorption TWA: 1.0 ppm TWA: 3.19 mg/m³	lehetséges borön keresztüli felszívódás Ceiling: 3 mg/m³ MK	TWA: 0.5 ppm 8 klukkustundum. TWA: 1.6 mg/m³ 8 klukkustundum. Skin notation Ceiling: 1 ppm Ceiling: 3.2 mg/m³

Component	Latvia	Lithuania	Luxembourg	Malta	Romania
Ethylbenzene	skin - potential for cutaneous exposure STEL: 200 ppm STEL: 884 mg/m³ TWA: 100 ppm	TWA: 100 ppm IPRD TWA: 442 mg/m³ IPRD Oda STEL: 200 ppm STEL: 884 mg/m³	Possibility of significant uptake through the skin TWA: 100 ppm 8 Stunden TWA: 442 mg/m³ 8	possibility of significant uptake through the skin TWA: 100 ppm TWA: 442 mg/m³ STEL: 200 ppm 15	Skin notation TWA: 100 ppm 8 ore TWA: 442 mg/m³ 8 ore STEL: 200 ppm 15 minute

	TWA: 442 mg/m³		Stunden STEL: 200 ppm 15 Minuten STEL: 884 mg/m³ 15 Minuten	minuti STEL: 884 mg/m³ 15 minuti	STEL: 884 mg/m³ 15 minute
Xylenes (o-, m-, p-isomers)	skin - potential for cutaneous exposure STEL: 100 ppm STEL: 442 mg/m³ TWA: 50 ppm TWA: 221 mg/m³	TWA: 50 ppm IPRD TWA: 200 mg/m³ IPRD Oda STEL: 100 ppm STEL: 450 mg/m³	TWA: 50 ppm 8 Stunden TWA: 221 mg/m³ 8 Stunden STEL: 100 ppm 15 Minuten STEL: 442 mg/m³ 15 Minuten	possibility of significant uptake through the skin TWA: 50 ppm TWA: 221 mg/m³ STEL: 100 ppm 15 minuti STEL: 442 mg/m³ 15 minuti	Skin notation TWA: 50 ppm 8 ore TWA: 221 mg/m³ 8 ore STEL: 100 ppm 15 minute STEL: 442 mg/m³ 15 minute
Toluene	skin - potential for cutaneous exposure STEL: 40 ppm STEL: 150 mg/m³ TWA: 14 ppm TWA: 50 mg/m³	TWA: 50 ppm IPRD TWA: 192 mg/m³ IPRD Oda STEL: 100 ppm STEL: 384 mg/m³	Possibility of significant uptake through the skin TWA: 50 ppm 8 Stunden TWA: 192 mg/m³ 8 Stunden STEL: 100 ppm 15 Minuten STEL: 384 mg/m³ 15 Minuten	possibility of significant uptake through the skin TWA: 50 ppm TWA: 192 mg/m³ STEL: 100 ppm 15 minuti STEL: 384 mg/m³ 15 minuti	Skin notation TWA: 50 ppm 8 ore TWA: 192 mg/m³ 8 ore STEL: 100 ppm 15 minute STEL: 384 mg/m³ 15 minute
Benzene	skin - potential for cutaneous exposure TWA: 1 ppm TWA: 3.25 mg/m³	TWA: 1 ppm IPRD TWA: 3.25 mg/m³ IPRD Oda STEL: 6 ppm STEL: 19 mg/m³	TWA: 1 ppm 8 Stunden TWA: 3.25 mg/m³ 8 Stunden		Skin notation TWA: 1 ppm 8 ore TWA: 3.25 mg/m³ 8 ore

Component	Russia	Slovak Republic	Slovenia	Sweden	Turkey
Ethylbenzene	TWA: 50 mg/m³ STEL: 150 mg/m³ vapor	Ceiling: 884 mg/m³ Potential for cutaneous absorption TWA: 100 ppm TWA: 442 mg/m³	TWA: 100 ppm 8 urah TWA: 442 mg/m³ 8 urah Koža STEL: 200 ppm 15 minutah STEL: 884 mg/m³ 15 minutah	STV: 100 ppm 15 minuter STV: 450 mg/m³ 15 minuter LLV: 50 ppm 8 timmar. LLV: 200 mg/m³ 8 timmar.	Deri TWA: 100 ppm 8 saat TWA: 442 mg/m³ 8 saat STEL: 200 ppm 15 dakika STEL: 884 mg/m³ 15 dakika
Xylenes (o-, m-, p-isomers)	TWA: 50 mg/m³ 2-,3- and 4- isomers STEL: 150 mg/m³ vapor	Ceiling: 442 mg/m³ Potential for cutaneous absorption TWA: 50 ppm TWA: 221 mg/m³	TWA: 50 ppm 8 urah TWA: 221 mg/m³ 8 urah Koža STEL: 100 ppm 15 minutah STEL: 442 mg/m³ 15 minutah	STV: 100 ppm 15 minuter STV: 442 mg/m³ 15 minuter LLV: 50 ppm 8 timmar. LLV: 221 mg/m³ 8 timmar. Hud	Deri TWA: 50 ppm 8 saat TWA: 221 mg/m³ 8 saat STEL: 100 ppm 15 dakika STEL: 442 mg/m³ 15 dakika
Toluene	TWA: 50 mg/m³ STEL: 150 mg/m³ vapor	Ceiling: 384 mg/m³ Potential for cutaneous absorption TWA: 50 ppm TWA: 192 mg/m³	TWA: 50 ppm 8 urah TWA: 192 mg/m³ 8 urah Koža STEL: 200 ppm 15 minutah STEL: 384 mg/m³ 15 minutah	STV: 100 ppm 15 minuter STV: 384 mg/m³ 15 minuter LLV: 50 ppm 8 timmar. LLV: 192 mg/m³ 8 timmar. Hud	Deri TWA: 50 ppm 8 saat TWA: 192 mg/m³ 8 saat STEL: 100 ppm 15 dakika STEL: 384 mg/m³ 15 dakika
Benzene	TWA: 5 mg/m³ Skin notation STEL: 15 mg/m³ vapor	TWA: 1.0 ppm 8 hodinách TWA: 3.25 mg/m³ 8 hodinách Potential for cutaneous absorption STEL: 5.0 ppm 15 minútach STEL: 16.25 mg/m³ 15 minútach	TWA: 1 ppm 8 urah TWA: 3.25 mg/m³ 8 urah Koža STEL: 4 ppm 15 minutah STEL: 13 mg/m³ 15 minutah	STV: 3 ppm 15 minuter STV: 9 mg/m³ 15 minuter LLV: 0.5 ppm 8 timmar. LLV: 1.5 mg/m³ 8 timmar. Hud	

Biological limit values

Component	European Union	United Kingdom	France	Spain	Germany
Ethylbenzene			Mandelic acid: 1500	Mandelic acid plus	Mandelic acid plus

			mg/g creatinine urine end of shift at end of workweek	Phenylglyoxylic acid: 700 mg/g Creatinine urine end of workweek	Phenylglyoxylic acid: 300 mg/g urine (end of shift)
Xylenes (o-, m-, p-isomers)		Methyl hippuric acid: 650 mmol/mol creatinine urine Post shift	Methylhippuric acid: 1500 mg/g creatinine urine end of shift	Methylhippuric acids: 1 g/g Creatinine urine end of shift	Xylene: 1.5 mg/L whole blood (end of shift all isomers) Methylhippuric(tolur-)acid: 2000 mg/L urine (end of shift all isomers)
Toluene			Toluene: 1 mg/L blood end of shift Hippuric acid: 2500 mg/g creatinine urine end of shift	o-Cresol: 0.5 mg/L urine end of shift Hippuric acid: 1.6 g/g Creatinine urine end of shift Toluene: 0.05 mg/L blood start of last shift of workweek	Toluene: 600 µg/L whole blood (end of shift) o-Cresol: 1.5 mg/L urine (end of several shifts after hydrolysis; for long-term exposures)
Benzene			Muconic acid: 5 mg/L urine end of shift	S-Phenylmercapturic acid: 0.045 mg/g urine end of exposure or end of shift trans,trans-Muconic acid: 2 mg/L urine end of exposure or end of shift Total benzene: 5 µg/L blood end of exposure or end of shift	

Component	Italy	Finland	Denmark	Bulgaria	Romania
Ethylbenzene		Mandelic acid: 5.2 mmol/L urine end of shift at end of workweek.		Mandelic acid and Phenylglyoxylic acid - together: 2000 mg/g Creatinine urine at the end of exposure or end of shift Possible significant absorption through the skin	Mandelic acid: 1.5 g/g Creatinine urine end of work week
Xylenes (o-, m-, p-isomers)		Methylhippuric acid: 5.0 mmol/L urine end of shift.			Methylhippuric acid: 3 g/L urine end of shift
Toluene		Toluene concentrated: 500 nmol/L blood prior to shift.		Hippuric acid: 1.6 mmol/mmol Creatinine urine at the end of exposure or end of shift	Hippuric acid: 2 g/L urine end of shift o-Cresol: 3 mg/L urine end of shift
Benzene				Trans, trans-Muconic acid: 2.0 mg/L urine at the end of exposure or end of shift Possible significant absorption through the skin S-Phenyl Mercapturic acid: 0.045 mg/g Creatinine urine at the end of exposure or end of shift Possible significant absorption through the skin	S-Phenylmercapturic acid: 25 µg/g Creatinine urine end of shift total Phenols: 50 mg/L urine end of shift

Component	Gibraltar	Latvia	Slovak Republic	Luxembourg	Turkey
Ethylbenzene			2 and 4-Ethylphenol: 12 mg/L urine end of exposure or work shift also after all work shifts for long-term exposure Mandelic acid and phenylglycolic acid: 1600 mg/L urine end of exposure or work shift		

			also after all work shifts for long-term exposure		
Xylenes (o-, m-, p-isomers)			Xylene: 1.5 mg/L blood end of exposure or work shift all isomers Methylhippuric acid: 2000 mg/L urine end of exposure or work shift		
Toluene		Hippuric acid: 1.6 g/g Creatinine urine end of shift Toluene: 0.05 mg/l blood end of shift	Toluene: 600 µg/L blood end of exposure or work shift o-Cresol: 1.5 mg/L urine after all work shifts for long-term exposure o-Cresol: 1.5 mg/L urine end of exposure or work shift Hippuric acid: 1600 mg/g creatinine end of exposure or work shift		
Benzene		Phenol: 25 µg/g Creatinine urine end of shift			

Monitoring methods
BS EN 14042:2003 Title Identifier: Workplace atmospheres. Guide for the application and use of procedures for the assessment of exposure to chemical and biological agents.

Derived No Effect Level (DNEL) No information available

Route of exposure	Acute effects (local)	Acute effects (systemic)	Chronic effects (local)	Chronic effects (systemic)
Oral				
Dermal				
Inhalation				

Predicted No Effect Concentration (PNEC) No information available.

8.2. Exposure controls

Engineering Measures
Use only under a chemical fume hood. Use explosion-proof electrical/ventilating/lighting/equipment. Ensure that eyewash stations and safety showers are close to the workstation location.
Wherever possible, engineering control measures such as the isolation or enclosure of the process, the introduction of process or equipment changes to minimise release or contact, and the use of properly designed ventilation systems, should be adopted to control hazardous materials at source

Personal protective equipment

Eye Protection Safety glasses with side-shields (European standard - EN 166)

Hand Protection Protective gloves

Glove material	Breakthrough time	Glove thickness	EU standard	Glove comments
Disposable gloves	See manufacturers recommendations	-	EN 374	(minimum requirement)

Skin and body protection Long sleeved clothing Apron Impervious gloves

Inspect gloves before use.
Please observe the instructions regarding permeability and breakthrough time which are provided by the supplier of the gloves. (Refer to manufacturer/supplier for information)
Ensure gloves are suitable for the task: Chemical compatability, Dexterity, Operational conditions, User susceptibility, e.g. sensitisation effects, also take into consideration the specific local conditions under which the product is used, such as the danger of cuts, abrasion.
Remove gloves with care avoiding skin contamination.

Respiratory Protection When workers are facing concentrations above the exposure limit they must use

	appropriate certified respirators. To protect the wearer, respiratory protective equipment must be the correct fit and be used and maintained properly
Large scale/emergency use	In case of insufficient ventilation wear suitable respiratory equipment
Small scale/Laboratory use	Use a NIOSH/MSHA or European Standard EN 149:2001 approved respirator if exposure limits are exceeded or if irritation or other symptoms are experienced. When RPE is used a face piece Fit Test should be conducted
Hygiene Measures	When using, do not eat, drink or smoke. Provide regular cleaning of equipment, work area and clothing.
Environmental exposure controls	No information available.

SECTION 9: PHYSICAL AND CHEMICAL PROPERTIES

9.1. Information on basic physical and chemical properties

Appearance	Clear, Colorless	
Physical State	Liquid	
Odor	aromatic	
Odor Threshold	No data available	
pH	No data available	
Melting Point/Range	-47.2 °C / -53 °F	
Softening Point	No data available	
Boiling Point/Range	136.7 - 143.3 °C / 278 - 290 °F	
Flash Point	27.7 °C / 82 °F	**Method -** No information available
Evaporation Rate	No information available	
Flammability (solid,gas)	No information available	
Explosion Limits	**Lower** 1.1 vol % **Upper** 7.0 vol %	
Vapor Pressure	9 mmHg @ 25 °C	
Vapor Density	3.66 (Air = 1.0)	(Air = 1.0)
Specific Gravity / Density	No data available 0.87	
Bulk Density	No data available	
Water Solubility	No information available	
Solubility in other solvents	No information available	

Partition Coefficient (n-octanol/water)

Component	**log Pow**
Ethylbenzene	3.118
Xylenes (o-, m-, p- isomers)	3.15
Toluene	2.65
Benzene	1.83

Autoignition Temperature	527 °C / 980.6 °F
Decomposition Temperature	No data available
Viscosity	No data available
Explosive Properties	No information available
Oxidizing Properties	No information available

9.2. Other information

Molecular Formula	C8H10
Molecular Weight	106.17

SECTION 10: STABILITY AND REACTIVITY

10.1. Reactivity

None known, based on information available

10.2. Chemical stability

Stable under normal conditions

10.3. Possibility of hazardous reactions

Hazardous Polymerization Hazardous polymerization does not occur.
Hazardous Reactions No information available.

10.4. Conditions to avoid

Incompatible products. Heat, flames and sparks.

10.5. Incompatible materials

Strong oxidizing agents. Strong acids.

10.6. Hazardous decomposition products

Carbon monoxide (CO). Carbon dioxide (CO_2). Hydrocarbons. Aldehydes.

SECTION 11: TOXICOLOGICAL INFORMATION

11.1. Information on toxicological effects

Product Information No acute toxicity information is available for this product

(a) acute toxicity;
Oral No data available
Dermal No data available
Inhalation No data available

Component	LD50 Oral	LD50 Dermal	LC50 Inhalation
Ethylbenzene	3500 mg/kg (Rat)	15400 mg/kg (Rabbit)	17.2 mg/L (Rat) 4 h
Xylenes (o-, m-, p- isomers)	3500 mg/kg (Rat)	4350 mg/kg (Rabbit) 1700 mg/kg (Rabbit)	29.08 mg/L [MOE Risk Assessment Vol.1, 2002]
Toluene	> 5000 mg/kg (Rat)	12000 mg/kg (Rabbit)	26700 ppm (Rat) 1 h
Benzene	810 mg/kg (Rat) 1800 mg/kg (Rat)	8200 mg/kg (Rabbit)	44.66 mg/L (Rat) 4 h

(b) skin corrosion/irritation; No data available

(c) serious eye damage/irritation; No data available

(d) respiratory or skin sensitization;
Respiratory No data available
Skin No data available

(e) germ cell mutagenicity; No data available

(f) carcinogenicity; No data available

The table below indicates whether each agency has listed any ingredient as a carcinogen

Component	EU	UK	Germany	IARC
Ethylbenzene				Group 2B
Benzene	Carc Cat. 1A		Cat. 1	Group 1

(g) reproductive toxicity; No data available
Reproductive Effects Experiments have shown reproductive toxicity effects on laboratory animals.
Developmental Effects Developmental effects have occurred in experimental animals.
Teratogenicity Teratogenic effects have occurred in experimental animals.

(h) STOT-single exposure; No data available

(i) STOT-repeated exposure; No data available

Target Organs Eyes, Skin, Central nervous system (CNS), Liver, Kidney, Respiratory system.

(j) aspiration hazard; No data available

Other Adverse Effects Tumorigenic effects have been reported in experimental animals. See actual entry in RTECS for complete information

Symptoms / effects,both acute and delayed Symptoms of overexposure may be headache, dizziness, tiredness, nausea and vomiting

SECTION 12: ECOLOGICAL INFORMATION

12.1. Toxicity

Ecotoxicity effects Do not empty into drains.

Component	Freshwater Fish	Water Flea	Freshwater Algae	Microtox
Ethylbenzene	9.6 mg/L LC50 96 h 9.1 - 15.6 mg/L LC50 96 h 32 mg/L LC50 96 h 7.55 - 11 mg/L LC50 96 h 4.2 mg/L LC50 96 h 11.0 - 18.0 mg/L LC50 96 h	1.8 - 2.4 mg/L EC50 48 h	2.6 - 11.3 mg/L EC50 72 h 438 mg/L EC50 > 96 h 4.6 mg/L EC50 = 72 h 1.7 - 7.6 mg/L EC50 96 h	EC50 = 9.68 mg/L 30 min EC50 = 96 mg/L 24 h
Xylenes (o-, m-, p- isomers)	30.26 - 40.75 mg/L LC50 96 h 780 mg/L LC50 96 h 23.53 - 29.97 mg/L LC50 96 h 7.711 - 9.591 mg/L LC50 96 h 19 mg/L LC50 96 h 13.1 - 16.5 mg/L LC50 96 h 13.5 - 17.3 mg/L LC50 96 h 2.661 - 4.093 mg/L LC50 96 h 13.4 mg/L LC50 96 h	0.6 mg/L LC50 = 48 h 3.82 mg/L EC50 = 48 h		EC50 = 0.0084 mg/L 24 h
Toluene	50-70 mg/L LC50 96 h 5-7 mg/L LC50 96 h 15-19 mg/L LC50 96 h 28 mg/L LC50 96 h 12 mg/L LC50 96 h	11.5 mg/L EC50 = 48 h 5.46 - 9.83 mg/L EC50 48 h	12.5 mg/L EC50 = 72 h 433 mg/L EC50 > 96 h	EC50 = 19.7 mg/L 30 min
Benzene	70000 - 142000 µg/L LC50 96 h 22330 - 41160 µg/L LC50 96 h 28.6 mg/L LC50 96 h 22.49 mg/L LC50 96 h 5.3 mg/L LC50 96 h 10.7 - 14.7 mg/L LC50 96 h	10 mg/L EC50 = 48 h 8.76 - 15.6 mg/L EC50 48 h	29 mg/L EC50 = 72 h	

12.2. Persistence and degradability No information available

Component	Degradability
Toluene 108-88-3 (0 - 0.5)	86% (20d)

12.3. Bioaccumulative potential No information available

Component	log Pow	Bioconcentration factor (BCF)
Ethylbenzene	3.118	15
Xylenes (o-, m-, p- isomers)	3.15	0.6 - 15
Toluene	2.65	90
Benzene	1.83	3.5 - 4.4

12.4. Mobility in soil .

12.5. Results of PBT and vPvB assessment No data available for assessment.

12.6. Other adverse effects

Endocrine Disruptor Information	This product does not contain any known or suspected endocrine disruptors
Persistent Organic Pollutant	This product does not contain any known or suspected substance
Ozone Depletion Potential	This product does not contain any known or suspected substance

SECTION 13: DISPOSAL CONSIDERATIONS

13.1. Waste treatment methods

Waste from Residues / Unused Products	Chemical waste generators must determine whether a discarded chemical is classified as a hazardous waste. Chemical waste generators must also consult local, regional, and national hazardous waste regulations to ensure complete and accurate classification.
Contaminated Packaging	Empty remaining contents. Dispose of in accordance with local regulations. Do not re-use empty containers.
European Waste Catalogue (EWC)	According to the European Waste Catalogue, Waste Codes are not product specific, but application specific.
Other Information	Waste codes should be assigned by the user based on the application for which the product was used.

SECTION 14: TRANSPORT INFORMATION

IMDG/IMO

14.1. UN number	UN1307
14.2. UN proper shipping name	XYLENES
14.3. Transport hazard class(es)	3
14.4. Packing group	III

ADR

14.1. UN number	UN1307
14.2. UN proper shipping name	XYLENES
14.3. Transport hazard class(es)	3
14.4. Packing group	III

IATA

14.1. UN number	UN1307
14.2. UN proper shipping name	XYLENES
14.3. Transport hazard class(es)	3
14.4. Packing group	III

14.5. Environmental hazards	No hazards identified
14.6. Special precautions for user	No special precautions required
14.7. Transport in bulk according to Annex II of MARPOL73/78 and the IBC Code	Not applicable, packaged goods

SECTION 15: REGULATORY INFORMATION

15.1. Safety, health and environmental regulations/legislation specific for the substance or mixture

International Inventories Australia X = listed China Canada The product is classified and labeled according to EC directives or corresponding national laws The product is classified and labeled in accordance with Directive 1999/45/EC Europe TSCA Korea Philippines Japan

Component	EINECS	ELINCS	NLP	TSCA	DSL	NDSL	PICCS	ENCS	IECSC	AICS	KECL
Ethylbenzene	202-849-4	-		X	X	-	X	X	X	X	X
Xylenes (o-, m-, p- isomers)	215-535-7	-		X	X	-	X	X	X	X	X

Toluene	203-625-9	-		X	X	-	X	X	X	X	X
Benzene	200-753-7	-		X	X	-	X	X	X	X	X

Component	REACH (1907/2006) - Annex XIV - Substances Subject to Authorization	REACH (1907/2006) - Annex XVII - Restrictions on Certain Dangerous Substances	REACH Regulation (EC 1907/2006) article 59 - Candidate List of Substances of Very High Concern (SVHC)
Toluene		Use restricted. See item 48. (see *http://eur-lex.europa.eu/LexUriServ/LexUriServ.do?uri=CELEX:32006R1907:EN:NOT* for restriction details)	
Benzene		Use restricted. See item 5. (see *http://eur-lex.europa.eu/LexUriServ/LexUriServ.do?uri=CELEX:32006R1907:EN:NOT* for restriction details) Use restricted. See item 28. (see *http://eur-lex.europa.eu/LexUriServ/LexUriServ.do?uri=CELEX:32006R1907:EN:NOT* for restriction details) Use restricted. See item 29. (see *http://eur-lex.europa.eu/LexUriServ/LexUriServ.do?uri=CELEX:32006R1907:EN:NOT* for restriction details)	

National Regulations

Component	Germany - Water Classification (VwVwS)	Germany - TA-Luft Class
Ethylbenzene	WGK 1	
Xylenes (o-, m-, p- isomers)	WGK 2	
Toluene	WGK 2	
Benzene	WGK 3	Krebserzeugende Stoffe - Class III : 1 mg/m³ (Massenkonzentration)

Component	France - INRS (Tables of occupational diseases)
Ethylbenzene	Tableaux des maladies professionnelles (TMP) - RG 84
Xylenes (o-, m-, p- isomers)	Tableaux des maladies professionnelles (TMP) - RG 4bis,RG 84
Toluene	Tableaux des maladies professionnelles (TMP) - RG 4bis,RG 84
Benzene	Tableaux des maladies professionnelles (TMP) - RG 4,RG 4bis,RG 84

Take note of Control of Substances Hazardous to Health Regulations (COSHH) 2002 and 2005 Amendment.
Take note of Dir 94/33/EC on the protection of young people at work
Take note of Directive 98/24/EC on the protection of the health and safety of workers from the risks related to chemical agents at work

15.2. Chemical safety assessment

A Chemical Safety Assessment/Report (CSA/CSR) has not been conducted

SECTION 16: OTHER INFORMATION

Full text of R-phrases referred to under sections 2 and 3
R10 - Flammable
R11 - Highly flammable
R20 - Harmful by inhalation
R38 - Irritating to skin
R45 - May cause cancer
R46 - May cause heritable genetic damage
R63 - Possible risk of harm to the unborn child
R65 - Harmful: may cause lung damage if swallowed
R67 - Vapors may cause drowsiness and dizziness

R20/21 - Harmful by inhalation and in contact with skin
R36/38 - Irritating to eyes and skin
R48/20 - Harmful: danger of serious damage to health by prolonged exposure through inhalation
R48/23/24/25 - Toxic: danger of serious damage to health by prolonged exposure through inhalation, in contact with skin and if swallowed

Full text of H-Statements referred to under sections 2 and 3
H226 - Flammable liquid and vapor
H225 - Highly flammable liquid and vapor
H312 - Harmful in contact with skin
H332 - Harmful if inhaled
H315 - Causes skin irritation
H304 - May be fatal if swallowed and enters airways
H373 - May cause damage to organs through prolonged or repeated exposure

Legend

CAS - Chemical Abstracts Service

EINECS/ELINCS - European Inventory of Existing Commercial Chemical Substances/EU List of Notified Chemical Substances
PICCS - Philippines Inventory of Chemicals and Chemical Substances
IECSC - Chinese Inventory of Existing Chemical Substances
KECL - Korean Existing and Evaluated Chemical Substances

TSCA - United States Toxic Substances Control Act Section 8(b) Inventory
DSL/NDSL - Canadian Domestic Substances List/Non-Domestic Substances List
ENCS - Japanese Existing and New Chemical Substances
AICS - Australian Inventory of Chemical Substances
NZIoC - New Zealand Inventory of Chemicals

WEL - Workplace Exposure Limit
ACGIH - American Conference of Governmental Industrial Hygienists
DNEL - Derived No Effect Level
RPE - Respiratory Protective Equipment
LC50 - Lethal Concentration 50%
NOEC - No Observed Effect Concentration
PBT - Persistent, Bioaccumulative, Toxic

TWA - Time Weighted Average
IARC - International Agency for Research on Cancer
PNEC - Predicted No Effect Concentration
LD50 - Lethal Dose 50%
EC50 - Effective Concentration 50%
POW - Partition coefficient Octanol:Water
vPvB - very Persistent, very Bioaccumulative

ADR - European Agreement Concerning the International Carriage of Dangerous Goods by Road
IMO/IMDG - International Maritime Organization/International Maritime Dangerous Goods Code
OECD - Organisation for Economic Co-operation and Development
BCF - Bioconcentration factor

ICAO/IATA - International Civil Aviation Organization/International Air Transport Association
MARPOL - International Convention for the Prevention of Pollution from Ships
ATE - Acute Toxicity Estimate
VOC - Volatile Organic Compounds

Key literature references and sources for data
Suppliers safety data sheet, Chemadvisor - LOLI, Merck index, RTECS

Training Advice
Chemical hazard awareness training, incorporating labelling, Safety Data Sheets (SDS), Personal Protective Equipment (PPE) and hygiene.

Creation Date	13-Feb-2015
Revision Date	21-Feb-2014
Revision Summary	Not applicable.

This safety data sheet complies with the requirements of Regulation (EC) No. 1907/2006

Disclaimer

The information provided on this Safety Data Sheet is correct to the best of our knowledge, information and belief at the date of its publication. The information given is designed only as a guide for safe handling, use, processing, storage, transportation, disposal and release and is not to be considered as a warranty or quality specification. The information relates only to the specific material designated and may not be valid for such material used in combination with any other material or in any process, unless specified in the text.

End of Safety Data Sheet

SAFETY DATA SHEET

Version 5.8
Revision Date 10/12/2015
Print Date 05/01/2016

1. PRODUCT AND COMPANY IDENTIFICATION

1.1 Product identifiers

Product name	:	Zinc
Product Number	:	96454
Brand	:	Sigma-Aldrich
CAS-No.	:	7440-66-6

1.2 Relevant identified uses of the substance or mixture and uses advised against

Identified uses	:	Laboratory chemicals, Synthesis of substances

1.3 Details of the supplier of the safety data sheet

Company	:	Sigma-Aldrich 3050 Spruce Street SAINT LOUIS MO 63103 USA
Telephone	:	+1 800-325-5832
Fax	:	+1 800-325-5052

1.4 Emergency telephone number

Emergency Phone #	:	(314) 776-6555

2. HAZARDS IDENTIFICATION

2.1 Classification of the substance or mixture

GHS Classification in accordance with 29 CFR 1910 (OSHA HCS)
Combustible dust,
Acute aquatic toxicity (Category 1), H400
Chronic aquatic toxicity (Category 1), H410

For the full text of the H-Statements mentioned in this Section, see Section 16.

2.2 GHS Label elements, including precautionary statements

Pictogram

Signal word: Warning

Hazard statement(s)

	May form combustible dust concentrations in air
H410	Very toxic to aquatic life with long lasting effects.

Precautionary statement(s)

P273	Avoid release to the environment.
P391	Collect spillage.
P501	Dispose of contents/ container to an approved waste disposal plant.

2.3 Hazards not otherwise classified (HNOC) or not covered by GHS

Combustible dust

3. COMPOSITION/INFORMATION ON INGREDIENTS

3.2 Mixtures

Formula : Zn
Molecular weight : 65.39 g/mol

Hazardous components

Component		Classification	Concentration
Zinc powder (stabilized)			
CAS-No. EC-No. Index-No.	7440-66-6 231-175-3 030-001-01-9	Aquatic Acute 1; Aquatic Chronic 1; H410	<= 100 %
Zinc oxide			
CAS-No. EC-No. Index-No.	1314-13-2 215-222-5 030-013-00-7	Aquatic Acute 1; Aquatic Chronic 1; H410	>= 5 - < 10 %

For the full text of the H-Statements mentioned in this Section, see Section 16.

4. FIRST AID MEASURES

4.1 Description of first aid measures

General advice
Consult a physician. Show this safety data sheet to the doctor in attendance.

If inhaled
If breathed in, move person into fresh air. If not breathing, give artificial respiration. Consult a physician.

In case of skin contact
Wash off with soap and plenty of water. Consult a physician.

In case of eye contact
Flush eyes with water as a precaution.

If swallowed
Never give anything by mouth to an unconscious person. Rinse mouth with water. Consult a physician.

4.2 Most important symptoms and effects, both acute and delayed

The most important known symptoms and effects are described in the labelling (see section 2.2) and/or in section 11

4.3 Indication of any immediate medical attention and special treatment needed

No data available

5. FIREFIGHTING MEASURES

5.1 Extinguishing media

Suitable extinguishing media
Special powder against metal fire Dry sandUse water spray, alcohol-resistant foam, dry chemical or carbon dioxide.

Unsuitable extinguishing media
Water

5.2 Special hazards arising from the substance or mixture

Zinc/zinc oxides

5.3 Advice for firefighters

Wear self-contained breathing apparatus for firefighting if necessary.

5.4 Further information

No data available

6. ACCIDENTAL RELEASE MEASURES

6.1 Personal precautions, protective equipment and emergency procedures

Avoid dust formation. Avoid breathing vapours, mist or gas. Ensure adequate ventilation.
For personal protection see section 8.

6.2 Environmental precautions

Prevent further leakage or spillage if safe to do so. Do not let product enter drains. Discharge into the environment must be avoided.

6.3 Methods and materials for containment and cleaning up

Pick up and arrange disposal without creating dust. Sweep up and shovel. Keep in suitable, closed containers for disposal.

6.4 Reference to other sections

For disposal see section 13.

7. HANDLING AND STORAGE

7.1 Precautions for safe handling

Further processing of solid materials may result in the formation of combustible dusts. The potential for combustible dust formation should be taken into consideration before additional processing occurs.
Provide appropriate exhaust ventilation at places where dust is formed.
For precautions see section 2.2.

7.2 Conditions for safe storage, including any incompatibilities

Keep container tightly closed in a dry and well-ventilated place.

Keep in a dry place.
Storage class (TRGS 510): Non Combustible Solids

7.3 Specific end use(s)

Apart from the uses mentioned in section 1.2 no other specific uses are stipulated

8. EXPOSURE CONTROLS/PERSONAL PROTECTION

8.1 Control parameters

Components with workplace control parameters

Component	CAS-No.	Value	Control parameters	Basis
Zinc oxide	1314-13-2	TWA	2.000000 mg/m3	USA. ACGIH Threshold Limit Values (TLV)
	Remarks	metal fume fever		
		STEL	10.000000 mg/m3	USA. ACGIH Threshold Limit Values (TLV)
		metal fume fever		

		TWA	5.000000 mg/m3	USA. NIOSH Recommended Exposure Limits
		TWA	5.000000 mg/m3	USA. NIOSH Recommended Exposure Limits
		ST	10.000000 mg/m3	USA. NIOSH Recommended Exposure Limits
		C	15.000000 mg/m3	USA. NIOSH Recommended Exposure Limits
		TWA	5.000000 mg/m3	USA. Occupational Exposure Limits (OSHA) - Table Z-1 Limits for Air Contaminants
		TWA	15.000000 mg/m3	USA. Occupational Exposure Limits (OSHA) - Table Z-1 Limits for Air Contaminants
		TWA	5.000000 mg/m3	USA. Occupational Exposure Limits (OSHA) - Table Z-1 Limits for Air Contaminants
		TWA	5.000000 mg/m3	USA. Occupational Exposure Limits (OSHA) - Table Z-1 Limits for Air Contaminants

8.2 Exposure controls

Appropriate engineering controls
Handle in accordance with good industrial hygiene and safety practice. Wash hands before breaks and at the end of workday.

Personal protective equipment

Eye/face protection
Use equipment for eye protection tested and approved under appropriate government standards such as NIOSH (US) or EN 166(EU).

Skin protection
Handle with gloves. Gloves must be inspected prior to use. Use proper glove removal technique (without touching glove's outer surface) to avoid skin contact with this product. Dispose of contaminated gloves after use in accordance with applicable laws and good laboratory practices. Wash and dry hands.

Full contact
Material: Nitrile rubber
Minimum layer thickness: 0.11 mm
Break through time: 480 min
Material tested:Dermatril® (KCL 740 / Aldrich Z677272, Size M)

Splash contact
Material: Nitrile rubber
Minimum layer thickness: 0.11 mm
Break through time: 480 min
Material tested:Dermatril® (KCL 740 / Aldrich Z677272, Size M)

data source: KCL GmbH, D-36124 Eichenzell, phone +49 (0)6659 87300, e-mail sales@kcl.de, test method: EN374
If used in solution, or mixed with other substances, and under conditions which differ from EN 374, contact the supplier of the CE approved gloves. This recommendation is advisory only and must be evaluated by an industrial hygienist and safety officer familiar with the specific situation of anticipated use by our customers. It should not be construed as offering an approval for any specific use scenario.

Body Protection
Choose body protection in relation to its type, to the concentration and amount of dangerous substances, and to the specific work-place., The type of protective equipment must be selected according to the concentration and amount of the dangerous substance at the specific workplace.

Respiratory protection
Respiratory protection is not required. Where protection from nuisance levels of dusts are desired, use type N95 (US) or type P1 (EN 143) dust masks. Use respirators and components tested and approved under appropriate government standards such as NIOSH (US) or CEN (EU).

Control of environmental exposure
Prevent further leakage or spillage if safe to do so. Do not let product enter drains. Discharge into the environment must be avoided.

9. PHYSICAL AND CHEMICAL PROPERTIES

9.1 Information on basic physical and chemical properties

a)	Appearance	Form: powder Colour: grey
b)	Odour	odourless
c)	Odour Threshold	No data available
d)	pH	Not applicable
e)	Melting point/freezing point	Melting point/range: 420 °C (788 °F) - lit.
f)	Initial boiling point and boiling range	907 °C (1,665 °F) - lit.
g)	Flash point	Not applicable
h)	Evaporation rate	No data available
i)	Flammability (solid, gas)	May form combustible dust concentrations in air
j)	Upper/lower flammability or explosive limits	No data available
k)	Vapour pressure	Not applicable
l)	Vapour density	No data available
m)	Relative density	7.133 g/mL at 25 °C (77 °F)
n)	Water solubility	insoluble
o)	Partition coefficient: n-octanol/water	Not applicable
p)	Auto-ignition temperature	does not ignite
q)	Decomposition temperature	No data available
r)	Viscosity	No data available
s)	Explosive properties	During processing, dust may form explosive mixture in air.
t)	Oxidizing properties	No data available

9.2 Other safety information

Bulk density	1.8 - 3.2 kg/m3

10. STABILITY AND REACTIVITY

10.1 Reactivity
No data available

10.2 Chemical stability
Stable under recommended storage conditions.

10.3 Possibility of hazardous reactions
Dust may form explosive mixture in air.

10.4 Conditions to avoid
No data available

10.5 Incompatible materials
Strong oxidizing agents, Acids and bases

10.6 Hazardous decomposition products
Other decomposition products - No data available
In the event of fire: see section 5

11. TOXICOLOGICAL INFORMATION

11.1 Information on toxicological effects

Acute toxicity
No data available (Zinc powder (stabilized))

Inhalation: No data available (Zinc powder (stabilized))

Dermal: No data available (Zinc powder (stabilized))

No data available (Zinc powder (stabilized))

Skin corrosion/irritation
No data available (Zinc powder (stabilized))

Serious eye damage/eye irritation
No data available (Zinc powder (stabilized))

Respiratory or skin sensitisation
Did not cause sensitisation on laboratory animals. (Zinc powder (stabilized))

Germ cell mutagenicity
No data available (Zinc powder (stabilized))

Carcinogenicity

IARC: No component of this product present at levels greater than or equal to 0.1% is identified as probable, possible or confirmed human carcinogen by IARC.

ACGIH: No component of this product present at levels greater than or equal to 0.1% is identified as a carcinogen or potential carcinogen by ACGIH.

NTP: No component of this product present at levels greater than or equal to 0.1% is identified as a known or anticipated carcinogen by NTP.

OSHA: No component of this product present at levels greater than or equal to 0.1% is identified as a carcinogen or potential carcinogen by OSHA.

Reproductive toxicity
No data available (Zinc powder (stabilized))

No data available (Zinc powder (stabilized))

Specific target organ toxicity - single exposure
No data available (Zinc powder (stabilized))

Specific target organ toxicity - repeated exposure
No data available

Aspiration hazard
No data available (Zinc powder (stabilized))

Additional Information
RTECS: ZG8600000

To the best of our knowledge, the chemical, physical, and toxicological properties have not been thoroughly investigated.

Effects due to ingestion may include:, chills, dry throat, sweet taste, Fever, Cough, Nausea, Vomiting, Weakness, Contact with eyes or skin may cause:, Irritation (Zinc powder (stabilized))

12. ECOLOGICAL INFORMATION

12.1 Toxicity

Toxicity to fish	LC50 - Cyprinus carpio (Carp) - 450 µg/l - 96 h (Zinc powder (stabilized))
Toxicity to daphnia and other aquatic invertebrates	LC50 - Daphnia magna (Water flea) - 0.068 mg/l - 48 h (Zinc powder (stabilized))
	mortality NOEC - Daphnia (water flea) - 0.101 - 0.14 mg/l - 7 d (Zinc powder (stabilized))

12.2 Persistence and degradability

The methods for determining the biological degradability are not applicable to inorganic substances.

12.3 Bioaccumulative potential

Bioaccumulation	Algae - 7 d at 16 °C - 5 µg/l (Zinc powder (stabilized))
	Bioconcentration factor (BCF): 466

12.4 Mobility in soil

No data available (Zinc powder (stabilized))

12.5 Results of PBT and vPvB assessment

PBT/vPvB assessment not available as chemical safety assessment not required/not conducted

12.6 Other adverse effects

An environmental hazard cannot be excluded in the event of unprofessional handling or disposal.
Very toxic to aquatic life with long lasting effects.

No data available

13. DISPOSAL CONSIDERATIONS

13.1 Waste treatment methods

Product
Offer surplus and non-recyclable solutions to a licensed disposal company.

Contaminated packaging
Dispose of as unused product.

14. TRANSPORT INFORMATION

DOT (US)
UN number: 3077 Class: 9 Packing group: III
Proper shipping name: Environmentally hazardous substances, solid, n.o.s. (Zinc powder (stabilized))
Reportable Quantity (RQ): 1020 lbs

Poison Inhalation Hazard: No

IMDG
UN number: 3077 Class: 9 Packing group: III EMS-No: F-A, S-F
Proper shipping name: ENVIRONMENTALLY HAZARDOUS SUBSTANCE, SOLID, N.O.S. (Zinc powder (stabilized))
Marine pollutant:yes

IATA
UN number: 3077 Class: 9 Packing group: III
Proper shipping name: Environmentally hazardous substance, solid, n.o.s. (Zinc powder (stabilized))

Further information
EHS-Mark required (ADR 2.2.9.1.10, IMDG code 2.10.3) for single packagings and combination packagings containing inner packagings with Dangerous Goods > 5L for liquids or > 5kg for solids.

15. REGULATORY INFORMATION

SARA 302 Components
No chemicals in this material are subject to the reporting requirements of SARA Title III, Section 302.

SARA 313 Components
The following components are subject to reporting levels established by SARA Title III, Section 313:

	CAS-No.	Revision Date
Zinc oxide	1314-13-2	2007-03-01
Zinc powder (stabilized)	7440-66-6	1993-04-24

SARA 311/312 Hazards
No SARA Hazards

Massachusetts Right To Know Components

	CAS-No.	Revision Date
Zinc powder (stabilized)	7440-66-6	1993-04-24
Zinc oxide	1314-13-2	2007-03-01

Pennsylvania Right To Know Components

	CAS-No.	Revision Date
Zinc powder (stabilized)	7440-66-6	1993-04-24
Zinc oxide	1314-13-2	2007-03-01

New Jersey Right To Know Components

	CAS-No.	Revision Date
Zinc powder (stabilized)	7440-66-6	1993-04-24
Zinc oxide	1314-13-2	2007-03-01

California Prop. 65 Components
This product does not contain any chemicals known to State of California to cause cancer, birth defects, or any other reproductive harm.

16. OTHER INFORMATION

Full text of H-Statements referred to under sections 2 and 3.

	May form combustible dust concentrations in air
Aquatic Acute	Acute aquatic toxicity
Aquatic Chronic	Chronic aquatic toxicity
H400	Very toxic to aquatic life.
H410	Very toxic to aquatic life with long lasting effects.

HMIS Rating

Health hazard:	0
Chronic Health Hazard:	
Flammability:	0
Physical Hazard	0

NFPA Rating

Health hazard:	0
Fire Hazard:	0
Reactivity Hazard:	0

Further information
Copyright 2015 Sigma-Aldrich Co. LLC. License granted to make unlimited paper copies for internal use only.
The above information is believed to be correct but does not purport to be all inclusive and shall be used only as a guide. The information in this document is based on the present state of our knowledge and is applicable to the product with regard to appropriate safety precautions. It does not represent any guarantee of the properties of the product. Sigma-Aldrich Corporation and its Affiliates shall not be held liable for any damage resulting from handling or from contact with the above product. See www.sigma-aldrich.com and/or the reverse side of invoice or packing slip for additional terms and conditions of sale.

Preparation Information
Sigma-Aldrich Corporation
Product Safety – Americas Region
1-800-521-8956

Version: 5.8 Revision Date: 10/12/2015 Print Date: 05/01/2016

Material Safety Data Sheet
2-Methylnaphthalene, 99% (gc)

MSDS# 69451

Section 1 - Chemical Product and Company Identification

MSDS Name:	2-Methylnaphthalene, 99% (gc)
Catalog Numbers:	AC414550000, AC414550050, AC414551000, AC414555000
Synonyms:	
Company Identification:	Acros Organics BVBA Janssen Pharmaceuticalaan 3a 2440 Geel, Belgium
Company Identification: (USA)	Acros Organics One Reagent Lane Fair Lawn, NJ 07410
For information in the US, call:	800-ACROS-01
For information in Europe, call:	+32 14 57 52 11
Emergency Number, Europe:	+32 14 57 52 99
Emergency Number US:	201-796-7100
CHEMTREC Phone Number, US:	800-424-9300
CHEMTREC Phone Number, Europe:	703-527-3887

Section 2 - Composition, Information on Ingredients

CAS#:	91-57-6
Chemical Name:	2-Methylnaphthalene
%:	99.0
EINECS#:	202-078-3

Hazard Symbols: XN

Risk Phrases: 22

Section 3 - Hazards Identification

EMERGENCY OVERVIEW

Warning! May cause respiratory tract irritation. May cause allergic skin reaction. May be harmful if swallowed. Causes eye and skin irritation. Target Organs: Eyes, skin.

Potential Health Effects

Eye:	Causes eye irritation.
Skin:	Causes skin irritation. May cause photosensitive skin reactions in certain individuals.
Ingestion:	May be harmful if swallowed.
Inhalation:	Inhalation of dust may cause respiratory tract irritation.
Chronic:	No information found.

Section 4 - First Aid Measures

Eyes:	Flush eyes with plenty of water for at least 15 minutes, occasionally lifting the upper and lower eyelids. Get medical aid immediately.

Skin:	Get medical aid. Flush skin with plenty of water for at least 15 minutes while removing contaminated clothing and shoes.
Ingestion:	If victim is conscious and alert, give 2-4 cupfuls of milk or water. Never give anything by mouth to an unconscious person. Get medical aid immediately.
Inhalation:	Remove from exposure and move to fresh air immediately. If not breathing, give artificial respiration. If breathing is difficult, give oxygen. Get medical aid.
Notes to Physician:	

Section 5 - Fire Fighting Measures

General Information:	As in any fire, wear a self-contained breathing apparatus in pressure-demand, MSHA/NIOSH (approved or equivalent), and full protective gear. Dusts at sufficient concentrations can form explosive mixtures with air. During a fire, irritating and highly toxic gases may be generated by thermal decomposition or combustion.
Extinguishing Media:	Use water spray, dry chemical, carbon dioxide, or chemical foam.
Autoignition Temperature:	Not available
Flash Point:	Not available
Explosion Limits: Lower:	Not available
Explosion Limits: Upper:	Not available
NFPA Rating:	health: 1; flammability: 1; instability: 0;

Section 6 - Accidental Release Measures

General Information:	Use proper personal protective equipment as indicated in Section 8.
Spills/Leaks:	Sweep up, then place into a suitable container for disposal. Avoid generating dusty conditions. Provide ventilation.

Section 7 - Handling and Storage

Handling:	Wash thoroughly after handling. Remove contaminated clothing and wash before reuse. Minimize dust generation and accumulation. Avoid contact with eyes, skin, and clothing. Keep container tightly closed. Avoid ingestion and inhalation.
Storage:	Keep container closed when not in use. Store in a tightly closed container. Store in a cool, dry, well-ventilated area away from incompatible substances.

Section 8 - Exposure Controls, Personal Protection

Chemical Name	ACGIH	NIOSH	OSHA - Final PELs
2-Methylnaphthalene	0.5 ppm; Skin - potential significant contribution to overall exposure by the cutaneous r oute	none listed	none listed

OSHA Vacated PELs: 2-Methylnaphthalene: None listed

Engineering Controls:

Use adequate ventilation to keep airborne concentrations low.

Exposure Limits

Personal Protective Equipment

Eyes:	Wear appropriate protective eyeglasses or chemical safety goggles as described by OSHA's eye and face protection regulations in 29 CFR 1910.133 or European Standard EN166.
Skin:	Wear appropriate protective gloves to prevent skin exposure.

Clothing: Wear appropriate protective clothing to prevent skin exposure.

Respirators: Follow the OSHA respirator regulations found in 29 CFR 1910.134 or European Standard EN 149. Use a NIOSH/MSHA or European Standard EN 149 approved respirator if exposure limits are exceeded or if irritation or other symptoms are experienced.

Section 9 - Physical and Chemical Properties

Physical State: Solid
Color: Not available
Odor: none reported
pH: Not available
Vapor Pressure: < 1 mm Hg @25c
Vapor Density: Not available
Evaporation Rate: Not available
Viscosity: Not available
Boiling Point: 241.1 deg C (465.98°F)
Freezing/Melting Point: 37-38c
Decomposition Temperature: Not available
Solubility in water: Insoluble
Specific Gravity/Density: 1.0000g/cm3
Molecular Formula: C11H10
Molecular Weight: 142.20

Section 10 - Stability and Reactivity

Chemical Stability: Stable under normal temperatures and pressures.
Conditions to Avoid: Incompatible materials, dust generation, strong oxidants.
Incompatibilities with Other Materials: Not available
Hazardous Decomposition Products: Carbon monoxide, carbon monoxide, carbon dioxide.
Hazardous Polymerization: Has not been reported.

Section 11 - Toxicological Information

RTECS#: CAS# 91-57-6: QJ9635000

RTECS:

LD50/LC50: **CAS# 91-57-6:** Oral, rat: LD50 = 1630 mg/kg;

.

Carcinogenicity: 2-Methylnaphthalene - Not listed as a carcinogen by ACGIH, IARC, NTP, or CA Prop 65.

Other: See actual entry in RTECS for complete information.

Section 12 - Ecological Information

Not available

Section 13 - Disposal Considerations

Dispose of in a manner consistent with federal, state, and local regulations.

Section 14 - Transport Information

US DOT
Shipping Name: Please contact Fisher Scientific for shipping information
Hazard Class:
UN Number:
Packing Group:
Canada TDG
Shipping Name: Not available
Hazard Class:
UN Number:
Packing Group:

Section 15 - Regulatory Information

European/International Regulations

European Labeling in Accordance with EC Directives

Hazard Symbols: XN

Risk Phrases:

R 22 Harmful if swallowed.

Safety Phrases:

WGK (Water Danger/Protection)

CAS# 91-57-6: Not available

Canada

CAS# 91-57-6 is listed on Canada's DSL List

Canadian WHMIS Classifications: Not available

This product has been classified in accordance with the hazard criteria of the Controlled Products Regulations and the MSDS contains all of the information required by those regulations.

CAS# 91-57-6 is not listed on Canada's Ingredient Disclosure List.

US Federal

TSCA

CAS# 91-57-6 is listed on the TSCA Inventory.

Section 16 - Other Information

MSDS Creation Date: 7/15/1998

Revision #5 Date 7/20/2009

The information above is believed to be accurate and represents the best information currently available to us. However, we make no warranty of merchantibility or any other warranty, express or implied, with respect to such information, and we assume no liability resulting from its use. Users should make their own investigations to determine the suitability of the information for their particular purposes. In no event shall the company be liable for any claims, losses, or damages of any third party or for lost profits or any special, indirect, incidental, consequential, or exemplary damages howsoever arising, even if the company has been advised of the possibility of such damages.

SAFETY DATA SHEET
p,p'-DDE

Revision: 06/25/2018

according to Regulation (EC) No. 1907/2006 as amended by (EC) No. 1272/2008

Section 1. Identification of the Substance/Mixture and of the Company/Undertaking

1.1 Product Code: 24241

Product Name: p,p'-DDE

Synonyms: 1,1'-(2,2-dichloroethenylidene)bis[4-chloro-benzene]; 4,4'-DDE; p,p'-Dichlorodiphenyldichloroethylene; NSC 1153;

1.2 Relevant identified uses of the substance or mixture and uses advised against:

Relevant identified uses: For research use only, not for human or veterinary use.

1.3 Details of the Supplier of the Safety Data Sheet:

Company Name: Cayman Chemical Company
1180 E. Ellsworth Rd.
Ann Arbor, MI 48108

Web site address: www.caymanchem.com

Information: Cayman Chemical Company +1 (734)971-3335

1.4 Emergency telephone number:

Emergency Contact: CHEMTREC Within USA and Canada: +1 (800)424-9300
CHEMTREC Outside USA and Canada: +1 (703)527-3887

Section 2. Hazards Identification

2.1 Classification of the Substance or Mixture:

Acute Toxicity: Inhalation, Category 4

Acute Toxicity: Oral, Category 4

Skin Corrosion/Irritation, Category 2

Aquatic Toxicity (Chronic), Category 1

2.2 Label Elements:

GHS Signal Word: **Warning**

GHS Hazard Phrases:

H302: Harmful if swallowed.

H315: Causes skin irritation.

H332: Harmful if inhaled.

H410: Very toxic to aquatic life with long lasting effects.

GHS Precaution Phrases:

P261: Avoid breathing {dust/fume/gas/mist/vapors/spray}.

P264: Wash {hands} thoroughly after handling.

P273: Avoid release to the environment.

P280: Wear {protective gloves/protective clothing/eye protection/face protection}.

GHS Response Phrases:

P301+312: IF SWALLOWED: P312: Call a POISON CENTER or doctor/physician if you feel unwell.

P302+352: IF ON SKIN: Wash with plenty of soap and water.

P304+340: IF INHALED: Remove victim to fresh air and keep at rest in a position comfortable for breathing.

P330: Rinse mouth.

P332+313: If skin irritation occurs, get medical advice/attention.

P362+364: Take off contaminated clothing and wash it before reuse.

P391: Collect spillage.

GHS Storage and Disposal Phrases:

Please refer to Section 7 for Storage and Section 13 for Disposal information.

2.3 Adverse Human Health Effects and Symptoms: Causes skin irritation.
Harmful if inhaled or swallowed..
Material may be irritating to the mucous membranes and upper respiratory tract.
May be harmful by skin absorption.
May cause eye or respiratory system irritation.
Very toxic to aquatic life with long lasting effects.
To the best of our knowledge, the toxicological properties have not been thoroughly investigated.

Section 3. Composition/Information on Ingredients

CAS # / RTECS #	Hazardous Components (Chemical Name)/ REACH Registration No.	Concentration	EC No./ EC Index No.	GHS Classification
72-55-9 KV9450000	DDE {p,p'-DDE; 2,2-Bis(4-chlorophenyl)-1,1-dichloroethylene; 4,4-DDE}	100.0 %	200-784-6 NA	Acute Tox.(O) 4: H302 Skin Corr. 2: H315 Aquatic (C) 1: H410 Acute Tox.(I) 4: H332

Section 4. First Aid Measures

4.1 Description of First Aid Measures:

In Case of Inhalation: Remove to fresh air. If not breathing, give artificial respiration or give oxygen by trained personnel. Get immediate medical attention.

In Case of Skin Contact: Immediately wash skin with soap and plenty of water for at least 15 minutes. Remove contaminated clothing. Get medical attention if symptoms occur. Wash clothing before reuse.

In Case of Eye Contact: Hold eyelids apart and flush eyes with plenty of water for at least 15 minutes. Have eyes examined and tested by medical personnel.

In Case of Ingestion: Wash out mouth with water provided person is conscious. Never give anything by mouth to an unconscious person. Get medical attention. Do NOT induce vomiting unless directed to do so by medical personnel.

Section 5. Fire Fighting Measures

5.1 Suitable Extinguishing Media: Use alcohol-resistant foam, carbon dioxide, water, or dry chemical spray.
Use water spray to cool fire-exposed containers.

Unsuitable Extinguishing Media: A solid water stream may be inefficient.

5.2 Flammable Properties and Hazards: No data available.

No data available.

Flash Pt: No data.

Explosive Limits: LEL: No data. UEL: No data.

Autoignition Pt: No data.

5.3 Fire Fighting Instructions: As in any fire, wear self-contained breathing apparatus pressure-demand (NIOSH approved or equivalent), and full protective gear to prevent contact with skin and eyes.

Section 6. Accidental Release Measures

6.1 Protective Precautions, Protective Equipment and Emergency Procedures: Avoid raising and breathing dust, and provide adequate ventilation. As conditions warrant, wear a NIOSH approved self-contained breathing apparatus, or respirator, and appropriate personal protection (rubber boots, safety goggles, and heavy rubber gloves).

6.2 Environmental Precautions: Take steps to avoid release into the environment, if safe to do so.

6.3 Methods and Material For Containment and Cleaning Up: Contain spill and collect, as appropriate. Transfer to a chemical waste container for disposal in accordance with local regulations.

Section 7. Handling and Storage

7.1 Precautions To Be Taken in Handling: Avoid breathing dust/fume/gas/mist/vapours/spray. Avoid prolonged or repeated exposure.

7.2 Precautions To Be Taken in Storing: Keep container tightly closed. Store in accordance with information listed on the product insert.

Section 8. Exposure Controls/Personal Protection

8.1 Exposure Parameters:

8.2 Exposure Controls:

8.2.1 Engineering Controls (Ventilation etc.): Use process enclosures, local exhaust ventilation, or other engineering controls to control airborne levels below recommended exposure limits.

8.2.2 Personal protection equipment:

Eye Protection: Safety glasses

Protective Gloves: Compatible chemical-resistant gloves

Other Protective Clothing: Lab coat

Respiratory Equipment (Specify Type): NIOSH approved respirator, as conditions warrant.

Work/Hygienic/Maintenance Practices: Do not take internally. Facilities storing or utilizing this material should be equipped with an eyewash and a safety shower. Wash thoroughly after handling.

No data available.

Section 9. Physical and Chemical Properties

9.1 Information on Basic Physical and Chemical Properties

Physical States:	[ ] Gas [ ] Liquid [X] Solid
Appearance and Odor:	A solid
pH:	No data.
Melting Point:	No data.
Boiling Point:	No data.
Flash Pt:	No data.
Evaporation Rate:	No data.
Flammability (solid, gas):	No data available.
Explosive Limits:	LEL: No data. UEL: No data.
Vapor Pressure (vs. Air or mm Hg):	No data.
Vapor Density (vs. Air = 1):	No data.

	Specific Gravity (Water = 1):	No data.
	Solubility in Water:	No data.
	Solubility Notes:	Soluble (slightly) in: chloroform;
	Octanol/Water Partition Coefficient:	No data.
	Autoignition Pt:	No data.
	Decomposition Temperature:	No data.
	Viscosity:	No data.
9.2	**Other Information**	
	Percent Volatile:	No data.
	Molecular Formula & Weight:	C14H8Cl4 318.0

Section 10. Stability and Reactivity

10.1	**Reactivity:**	No data available.
10.2	**Stability:**	Unstable [ ] Stable [X]
10.3	**Stability Note(s):**	Stable if stored in accordance with information listed on the product insert.
	Polymerization:	Will occur [ ] Will not occur [X]
10.4	**Conditions To Avoid:**	No data available.
10.5	**Incompatibility - Materials To Avoid:**	strong bases strong oxidizing agents
10.6	**Hazardous Decomposition or Byproducts:**	carbon dioxide carbon monoxide hydrogen chloride gas

Section 11. Toxicological Information

11.1	**Information on Toxicological Effects:**	The toxicological effects of this product have not been thoroughly studied. p,p'-DDE - Toxicity Data: Oral LD50 (rat): 880 mg/kg; Oral LD50 (mouse): 700 mg/kg; Intraperitoneal LD50 (rat): 159 mg/kg; Intraperitoneal LD50 (mouse): 500 ug/kg;
	Chronic Toxicological Effects:	p,p'-DDE - Investigated as an agricultural chemical, mutagen, reproductive effector, and tumorigen. Only select Registry of Toxic Effects of Chemical Substances (RTECS) data is presented here. See actual entry in RTECS for complete information. p,p'-DDE RTECS Number: KV9450000

CAS #	Hazardous Components (Chemical Name)	NTP	IARC	ACGIH	OSHA
72-55-9	DDE {p,p'-DDE; 2,2-Bis(4-chlorophenyl)-1,1-dichloroethylene; 4,4-DDE}	n.a.	n.a.	n.a.	n.a.

Section 12. Ecological Information

12.1	**Toxicity:**	Avoid release into the environment. Runoff from fire control or dilution water may cause pollution.
12.2	**Persistence and Degradability:**	No data available.
12.3	**Bioaccumulative Potential:**	No data available.
12.4	**Mobility in Soil:**	No data available.
12.5	**Results of PBT and vPvB assessment:**	No data available.
12.6	**Other adverse effects:**	No data available.

Section 13. Disposal Considerations

13.1 Waste Disposal Method: Dispose in accordance with local, state, and federal regulations.

Section 14. Transport Information

14.1 LAND TRANSPORT (US DOT):

DOT Proper Shipping Name: Environmentally hazardous substances, solid, n.o.s. (p,p'-DDE)
DOT Hazard Class: 9 CLASS 9
UN/NA Number: UN3077 **Packing Group:** III

14.1 LAND TRANSPORT (European ADR/RID):

ADR/RID Shipping Name: Environmentally hazardous substances, solid, n.o.s. (p,p'-DDE)
UN Number: 3077 **Packing Group:** III
Hazard Class: 9 - CLASS 9

14.3 AIR TRANSPORT (ICAO/IATA):

ICAO/IATA Shipping Name: Environmentally hazardous substances, solid, n.o.s. (p,p'-DDE)
UN Number: 3077 **Packing Group:** III
Hazard Class: 9 - CLASS 9 **IATA Classification:** 9

Additional Transport Information: Transport in accordance with local, state, and federal regulations.
When sold in quantities of less than or equal to 1 mL, or 1 g, with an Excepted Quantity Code of E1, E2, E4, or E5, this item meets the De Minimis Quantities exemption, per IATA 2.6.10. Therefore packaging does not have to be labeled as Dangerous Goods/Excepted Quantity.

Section 15. Regulatory Information

EPA SARA (Superfund Amendments and Reauthorization Act of 1986) Lists

CAS #	Hazardous Components (Chemical Name)	S. 302 (EHS)	S. 304 RQ	S. 313 (TRI)
72-55-9	DDE {p,p'-DDE; 2,2-Bis(4-chlorophenyl)-1,1-dichloroethylene; 4,4-DDE}	No	Yes 1 LB	No

CAS #	Hazardous Components (Chemical Name)	Other US EPA or State Lists
72-55-9	DDE {p,p'-DDE; 2,2-Bis(4-chlorophenyl)-1,1-dichloroethylene; 4,4-DDE}	CAA HAP,ODC: HAP; CWA NPDES: Yes; TSCA: No; CA PROP.65: Yes: RDTox(M)

Regulatory Information Statement: This SDS was prepared in accordance with 29 CFR 1910.1200 and Regulation (EC) No.1272/2008.

Section 16. Other Information

Revision Date:	06/25/2018
Additional Information About This Product:	No data available.
Company Policy or Disclaimer:	DISCLAIMER: This information is believed to be accurate and represents the best information currently available to us. However, we make no warranty of merchantability or any other warranty, express or implied, with respect to such information, and we assume no liability resulting from its use. Users should make their own investigations to determine the suitability of the information for their particular purposes.

Safety Data Sheet

Revision Date: 09/13/18
www.restek.com

2 Letter ISO country code/language code: US/EN

1. IDENTIFICATION

Catalog Number / Product Name:	**32203 / 4,4'-DDT Standard**
Company:	Restek Corporation
Address:	110 Benner Circle Bellefonte, Pa. 16823
Phone#:	814-353-1300
Fax#:	814-353-1309
Emergency#:	800-424-9300 (CHEMTREC) 703-527-3887 (Outside the US)
Email:	www.restek.com
Revision Number:	9
Intended use:	For Laboratory use only

2. HAZARD(S)IDENTIFICATION

Emergency Overview:

GHS Hazard Symbols:

GHS Classification:	Specific Target Organ Systemic Toxicity (STOT) - Single Exposure Category 1 Flammable Liquid Category 2 Carcinogenicity Category 2 Acute Toxicity - Dermal Category 3 Acute Toxicity - Oral Category 3
GHS Signal Word:	Danger
GHS Hazard:	Highly flammable liquid and vapour. Toxic if swallowed or in contact with skin. Suspected of causing cancer. Causes damage to organs.
GHS Precautions:	
Safety Precautions:	Obtain special instructions before use. Do not handle until all safety precautions have been read and understood. Keep away from heat/sparks/open flames/hot surfaces. – No smoking. Keep container tightly closed. Ground/bond container and receiving equipment. Use explosion-proof electrical/ventilation and lighting equipment. Use only non-sparking tools. Take precautionary measures against static discharge. Do not breathe dust/fume/gas/mist/vapours/spray. Wash hands and skin thoroughly after handling. Do not eat, drink or smoke when using this product. Wear protective gloves/protective clothing/eye protection/face protection.
First Aid Measures:	IF SWALLOWED: Immediately call a POISON CENTER/doctor/.... IF ON SKIN: Wash with plenty of soap and water. IF ON SKIN (or hair): Remove/Take off immediately all contaminated clothing. Rinse skin with water/shower. IF exposed: Call a POISON CENTER or doctor/physician. IF exposed or concerned: Get medical advice/attention. Call a POISON CENTER or doctor/physician if you feel unwell. Specific treatment see section 4.

Rinse mouth.
Take off immediately all contaminated clothing and wash it before reuse.
In case of fire: Use extinguishing media in section 5 for extinction.

Storage: Keep container tightly closed.
Store in a well-ventilated place. Keep cool.
Store locked up.

Disposal: Dispose of contents/container according to section 13 of the SDS.

Single Exposure Target Organs: Specific target organ toxicity - Single exposure - STOT SE 1: H370 Causes damage to organs. (C >= 10 %; No information to prove exclusion of certain routes of exposure); Specific target organ toxicity - Single exposure - STOT SE 2: H371 May cause damage to organs. (3 % <= C <10 %; Concentration limits for acute toxicity cannot be translated into GHS from the DSD especially when minimum classifications are given)

Repeated Exposure Target Organs: Specific target organ toxicity - Repeated exposure - STOT RE 1: H372 Causes damage to organs through prolonged or repeated exposure. (No information to prove exclusion of certain routes of exposure)

3. COMPOSITION / INFORMATION ON INGREDIENT

Chemical Name	CAS #	EINEC #	% Composition
methanol	67-56-1	200-659-6	99.9
4,4'-DDT	50-29-3	200-024-3	0.1

4. FIRST-AID MEASURES

Inhalation: Remove to fresh air. If breathing is difficult, have a trained individual administer oxygen. If not breathing, give artificial respiration and have a trained individual administer oxygen. Get medical attention immediately

Eyes: Flush eyes with plenty of water for at least 20 minutes retracting eyelids often. Tilt the head to prevent chemical from transferring to the uncontaminated eye. Get immediate medical attention.

Skin Contact: Wash with soap and water. Remove contaminated clothing and launder. Get medical attention if irritation develops or persists.

Ingestion: Do not induce vomiting and seek medical attention immediately. Drink two glasses of water or milk to dilute. Provide medical care provider with this SDS.

5. FIRE- FIGHTING MEASURES

Extinguishing Media: Use alcohol resistant foam, carbon dioxide, or dry chemical extinguishing agents. Water may be ineffective but water spray can be used extinguish a fire if swept across the base of the flames. Water can absorb heat and keep exposed material from being damaged by fire.

Fire and/or Explosion Hazards: Vapors may be ignited by sparks, flames or other sources of ignition if material is above the flash point giving rise to a fire (Class B). Vapors are heavier than air and may travel to a source of ignition and flash back.

Fire Fighting Methods and Protection: Do not enter fire area without proper protection including self-contained breathing apparatus and full protective equipment. Fight fire from a safe distance and a protected location due to the potential of hazardous vapors and decomposition products. Flammable component(s) of this material may be lighter than water and burn while floating on the surface.

Hazardous Combustion Products: Carbon dioxide, Carbon monoxide

6. ACCIDENTAL RELEASE MEASURES

Personal Precautions and Equipment: Exposure to the spilled material may be severely irritating or toxic. Follow personal protective equipment recommendations found in Section 8 of this SDS. Personal protective equipment needs must be evaluated based on information provided on this sheet and the special circumstances created by the spill including; the material spilled, the quantity of the spill, the area in which the spill occurred, and the expertise of employees in the area responding to the spill. Never exceed any occupational exposure limits.

Methods for Clean-up: Prevent the spread of any spill to minimize harm to human health and the environment if safe to do so. Wear complete and proper personal protective equipment following the recommendation of Section 8 at a minimum. Dike with suitable absorbent material like granulated clay.

Gather and store in a sealed container pending a waste disposal evaluation.

7. HANDLING AND STORAGE

Handling Technical Measures and Precautions: Toxic or severely irritating material. Avoid contacting and avoid breathing the material. Use only in a well ventilated area. Use spark-proof tools and explosion-proof equipment

Storage Technical Measures and Conditions: Store in a cool dry ventilated location. Isolate from incompatible materials and conditions. Keep container(s) closed. Keep away from sources of ignition

8. EXPOSURE CONTROLS / PERSONAL PROTECTION

United States:

Chemical Name	CAS No.	IDLH	ACGIH STEL	ACGIH TLV-TWA	OSHA Exposure Limit
methanol	67-56-1	6000 ppm IDLH	250 ppm STEL	200 ppm TWA	200 ppm TWA; 260 mg/m3 TWA
4,4'-DDT	50-29-3	500 mg/m3 IDLH	None Known	1 mg/m3 TWA	1 mg/m3 TWA (listed under Dichlorodiphenyltrichloroethane)

Personal Protection:

Engineering Measures: Local exhaust ventilation is recommended when generating excessive levels of vapours from handling or thermal processing.

Respiratory Protection: Respiratory protection may be required to avoid overexposure when handling this product. General or local exhaust ventilation is the preferred means of protection. Use a respirator if general room ventilation is not available or sufficient to eliminate symptoms.If an exposure limit is exceeded or if an operator is experiencing symptoms of inhalation overexposure as explained in Section 3, provide respiratory protection.

Eye Protection: Wear chemically resistant safety glasses with side shields when handling this product. Do not wear contact lenses.

Skin Protection: Wear protective gloves. Inspect gloves for chemical break-through and replace at regular intervals. Clean protective equipment regularly. Wash hands and other exposed areas with mild soap and water before eating, drinking, and when leaving work

9. PHYSICAL AND CHEMICAL PROPERTIES

Appearance, color:	No data available
Odor:	Mild
Physical State:	No data available
pH:	Not applicable
Vapor Pressure:	No data available
Vapor Density:	1.1 (air = 1)
Boiling Point (°C):	260 °C 64.7 °C at 760 mmHg (HSDB)
Melting Point (°C):	-98 °C
Flash Point (°F):	52
Flammability:	Highly Flammable
Upper Flammable/Explosive Limit, % in air:	36
Lower Flammable/Explosive Limit, % in air:	6
Autoignition Temperature (°C):	464 deg C
Decomposition Temperature (°C):	No data available
Specific Gravity:	0.791 - 0.792 g/cm3 at 20 °C
Evaporation Rate:	No data available
Odor Threshold:	No data available
Solubility:	Moderate; 50-99%
Partition Coefficient: n-octanol in water:	No data available
VOC % by weight:	0
Molecular Weight:	32.04

10. STABILITY AND REACTIVITY

Stability:	Stable under normal conditions.
Conditions to Avoid:	None known.
Materials to Avoid / Chemical Incompatiability:	Strong oxidizing agents

Hazardous Decomposition Products: Carbon dioxide Carbon monoxide

11. TOXICOLOGICAL INFORMATION

Routes of Entry: Inhalation, Skin Contact, Eye Contact, Ingestion
Target Organs Potentially Affected By Exposure: Eyes, Central nervous system stimulation, Skin, GI Tract, Respiratory Tract
Chemical Interactions That Change Toxicity: None Known

Immediate (Acute) Health Effects by Route of Exposure:

Inhalation Irritation: Can cause moderate respiratory irritation, dizziness, weakness, fatigue, nausea and headache.

Inhalation Toxicity: Harmful! Can cause systemic damage (see "Target Organs)Methanol can cause central nervous system depression and overexposure can cause damage to the optic nerve resulting in visual impairment or blindness.

Skin Contact: Can cause moderate skin irritation, defatting, and dermatitis. Not likely to cause permanent damage.

Eye Contact: Can cause moderate irritation, tearing and reddening, but not likely to permanently injure eye tissue.

Ingestion Irritation: Irritating to mouth, throat, and stomach. Can cause abdominal discomfort, nausea, vomiting and diarrhea.Highly toxic and may be fatal if swallowed.

Ingestion Toxicity: Toxic if swallowed. May cause target organ failure and/or death.May be fatal if swallowed.

Long-Term (Chronic) Health Effects:

Carcinogenicity: Contains a probable or known human carcinogen.

Reproductive and Developmental Toxicity: Contains a known human reproductive and/or developmental hazard.

Inhalation: Upon prolonged and/or repeated exposure, can cause moderate respiratory irritation, dizziness, weakness, fatigue, nausea and headache.Harmful! Can cause systemic damage upon prolonged and/or repeated exposure (see "Target Organs)

Skin Contact: Upon prolonged or repeated contact, can cause moderate skin irritation, defatting, and dermatitis. Not likely to cause permanent damage.

Ingestion: Toxic if swallowed. May cause target organ failure and/or death.

Component Toxicological Data:
NIOSH:

Chemical Name	CAS No.	LD50/LC50
DDT	50-29-3	Dermal LD50 Rabbit 300 - 2820 mg/kg
Methanol	67-56-1	Inhalation LC50 Rat 22500 ppm 8 h

Component Carcinogenic Data:
OSHA:

Chemical Name	CAS No.	
DDT	50-29-3	Present

ACGIH:

Chemical Name	CAS No.	
DDT	50-29-3	A3 - Confirmed Animal Carcinogen with Unknown Relevance to Humans

NIOSH:

Chemical Name	CAS No.	
DDT	50-29-3	potential occupational carcinogen

NTP:

Chemical Name	CAS No.
No data available	

IARC:

Chemical Name	CAS No.	Group No.
Monograph 113 [in preparation]; Monograph 53 [1991]; Supplement 7 [1987]	50-29-3	Group 2A

12. ECOLOGICAL INFORMATION

Overview:	Moderate ecological hazard. This product may be dangerous to plants and/or wildlife.
Mobility:	No data
Persistence:	No data
Bioaccumulation:	No data
Degradability:	Biodegrades slowly.
Ecological Toxicity Data:	No data available

13. DISPOSAL CONSIDERATIONS

Waste Description of Spent Product:	Spent or discarded material is a hazardous waste.Mixing spent or discarded material with other materials may render the mixture hazardous. Perform a hazardous waste determination on mixtures.
Disposal Methods:	Dispose of by incineration following Federal, State, Local, or Provincial regulations.
Waste Disposal of Packaging:	Comply with all Local, State, Federal, and Provincial Environmental Regulations.

14. TRANSPORTATION INFORMATION

United States:	
DOT Proper Shipping Name:	Methanol
UN Number:	UN1230
Hazard Class:	3
Packing Group:	II
International:	
IATA Proper Shipping Name:	Methanol
UN Number:	UN1230
Hazard Class:	3(6.1)
Packing Group:	II

Marine Pollutant: No

Chemical Name	CAS#	Marine Pollutant	Severe Marine Pollutant
No data available			

15. REGULATORY INFORMATION

United States:

Chemical Name	CAS#	CERCLA	SARA 313	SARA EHS 313	TSCA
methanol	67-56-1	X	X	-	X
4,4'-DDT	50-29-3	X	-	-	X

The following chemicals are listed on CA Prop 65:

Chemical Name	CAS #	Regulation
DDT	50-29-3	Prop 65 Cancer
p,p''-DDT	50-29-3	Prop 65 Devolop Tox
Methanol	67-56-1	Prop 65 Devolop Tox
p,p''-DDT	50-29-3	Prop 65 Rep Female
p,p''-DDT	50-29-3	Prop 65 Rep Male

State Right To Know Listing:

Chemical Name	CAS#	New Jersey	Massachusetts	Pennsylvania	California
methanol	67-56-1	X	X	X	X
4,4'-DDT	50-29-3	X	X	X	X

16. OTHER INFORMATION

Prior Version Date: 12/23/16
Other Information: Any changes to the SDS compared to previous versions are marked by a vertical

line in front of the concerned paragraph.

References: No data available

Disclaimer: Restek Corporation provides the descriptions, data and information contained herein in good faith but makes no representation as to its comprehensiveness or accuracy. It is provided for your guidance only. Because many factors may affect processing or application/use, Restek Corporation recommends you perform an assessment to determine the suitability of a product for your particular purpose prior to use. No warranties of any kind, either expressed or implied, including fitness for a particular purpose, are made regarding products described, data or information set forth. In no case shall the descriptions, information, or data provided be considered a part of our terms and conditions of sale. Further, the descriptions, data and information furnished hereunder are given gratis. No obligation or liability for the description, data and information given are assumed. All such being given and accepted at your risk.

Safety Data Sheet

Revision Date: 03/05/18
www.restek.com

2 Letter ISO country code/language code: US/EN

1. IDENTIFICATION

Catalog Number / Product Name:	**32011 / Aroclor® 1254 Standard**
Company:	Restek Corporation
Address:	110 Benner Circle Bellefonte, Pa. 16823
Phone#:	814-353-1300
Fax#:	814-353-1309
Emergency#:	800-424-9300 (CHEMTREC) 703-527-3887 (Outside the US)
Email:	www.restek.com
Revision Number:	12
Intended use:	For Laboratory use only

2. HAZARD(S)IDENTIFICATION

Emergency Overview:

GHS Hazard Symbols:

GHS Classification:
Flammable Liquid Category 2
Skin Corrosion/Irritation Category 2
Specific Target Organ Systemic Toxicity (STOT) - Repeated Exposure Category 2
Hazardous to the aquatic environment - Chronic Category 2
Specific Target Organ Systemic Toxicity (STOT) - Single Exposure Category 3

GHS Signal Word:
Danger

GHS Hazard:
Highly flammable liquid and vapour.
Causes skin irritation.
May cause drowsiness or dizziness.
May cause damage to organs through prolonged or repeated exposure.
Toxic to aquatic life with long lasting effects.

GHS Precautions:

Safety Precautions:
Keep away from heat/sparks/open flames/hot surfaces. – No smoking.
Ground/bond container and receiving equipment.
Use explosion-proof electrical/ventilation and lighting equipment.
Use only non-sparking tools.
Take precautionary measures against static discharge.
Do not breathe dust/fume/gas/mist/vapours/spray.
Wash hands and skin thoroughly after handling.
Use only outdoors or in a well-ventilated area.
Avoid release to the environment.
Wear protective gloves/protective clothing/eye protection/face protection.

First Aid Measures:
IF ON SKIN: Wash with plenty of soap and water.
IF ON SKIN (or hair): Remove/Take off immediately all contaminated clothing. Rinse skin with water/shower.
IF INHALED: Remove victim to fresh air and keep at rest in a position comfortable for breathing.
Call a POISON CENTER or doctor/physician if you feel unwell.
Specific treatment see section 4.
If skin irritation occurs: Get medical advice/attention.
Take off contaminated clothing and wash it before reuse.
In case of fire: Use extinguishing media in section 5 for extinction.

Collect spillage.

Storage: Store in a well-ventilated place. Keep container tightly closed.
Store in a well-ventilated place. Keep cool.
Store locked up.

Disposal: Dispose of contents/container according to section 13 of the SDS.

Single Exposure Target Organs: Specific target organ toxicity - Single exposure - STOT SE 3: H336 May cause drowsiness or dizziness.

Repeated Exposure Target Organs: Specific target organ toxicity - Repeated exposure - STOT RE 2: H373 May cause damage to organs through prolonged or repeated exposure. (C >= 5 %; Minimum classification, No information to prove exclusion of certain routes of exposure)

3. COMPOSITION / INFORMATION ON INGREDIENT

Chemical Name	CAS #	EINEC #	% Composition
hexane	110-54-3	203-777-6	99.9
aroclor® 1254	11097-69-1		0.1

4. FIRST-AID MEASURES

Inhalation: Remove to fresh air. If breathing is difficult, have a trained individual administer oxygen.

Eyes: Flush eyes with plenty of water for at least 20 minutes retracting eyelids often. Tilt the head to prevent chemical from transferring to the uncontaminated eye. Get immediate medical attention.

Skin Contact: Wash with soap and water. Remove contaminated clothing and launder. Get medical attention if irritation develops or persists.

Ingestion: Do not induce vomiting and seek medical attention immediately. Drink two glasses of water or milk to dilute. Provide medical care provider with this SDS.

5. FIRE- FIGHTING MEASURES

Extinguishing Media: Use alcohol resistant foam, carbon dioxide, or dry chemical extinguishing agents. Water spray or fog may also be effective for extinguishing if swept across the base of the fire. Water can also be used to absorb heat and keep exposed material from being damaged by fire.

Fire and/or Explosion Hazards: Vapors may be ignited by heat, sparks, flames or other sources of ignition at or above the low flash point giving rise to a Class B fire. Vapors are heavier than air and may travel to a source of ignition and flash back

Fire Fighting Methods and Protection: Do not enter fire area without proper protection including self-contained toxic breathing apparatus and full protective equipment. Fight fire from a safe distance and a protected location due to the potential of hazardous vapors and decomposition products. Flammable component(s) of this material may be lighter than water and burn while floating on the surface. Use water spray/fog for cooling. Flammable component(s) of this material may be lighter than water and burn while floating on the surface.

Hazardous Combustion Products: Carbon dioxide, Carbon monoxide

6. ACCIDENTAL RELEASE MEASURES

Personal Precautions and Equipment: Exposure to the spilled material may be irritating or harmful. Follow personal protective equipment recommendations found in Section 8 of this SDS. Additional precautions may be necessary based on special circumstances created by the spill including; the material spilled, the quantity of the spill, the area in which the spill occurred. Also consider the expertise of employees in the area responding to the spill.

Methods for Clean-up: Prevent the spread of any spill to minimize harm to human health and the environment if safe to do so. Wear complete and proper personal protective equipment following the recommendation of Section 8 at a minimum. Dike with suitable absorbent material like granulated clay. Gather and store in a sealed container pending a waste disposal evaluation.

7. HANDLING AND STORAGE

Handling Technical Measures and Precautions:	Harmful or irritating material. Avoid contacting and avoid breathing the material. Use only in a well ventilated area. Use spark-proof tools and explosion-proof equipment
Storage Technical Measures and Conditions:	Store in a cool dry ventilated location. Isolate from incompatible materials and conditions. Keep container(s) closed. Keep away from sources of ignition

8. EXPOSURE CONTROLS / PERSONAL PROTECTION

United States:

Chemical Name	CAS No.	IDLH	ACGIH STEL	ACGIH TLV-TWA	OSHA Exposure Limit
hexane	110-54-3	1100 ppm IDLH (10% LEL)	1000 ppm	50 ppm TWA	500 ppm TWA; 1800 mg/m3 TWA
aroclor® 1254	11097-69-1	5 mg/m3 IDLH	None Known	0.5 mg/m3 TWA	0.5 mg/m3 TWA

Personal Protection:

Engineering Measures:	Local exhaust ventilation is recommended when generating excessive levels of vapours from handling or thermal processing.
Respiratory Protection:	Respiratory protection may be required to avoid overexposure when handling this product. General or local exhaust ventilation is the preferred means of protection. Use a respirator if general room ventilation is not available or sufficient to eliminate symptoms.
Eye Protection:	Wear chemically resistant safety glasses with side shields when handling this product. Do not wear contact lenses.
Skin Protection:	Wear protective gloves. Inspect gloves for chemical break-through and replace at regular intervals. Clean protective equipment regularly. Wash hands and other exposed areas with mild soap and water before eating, drinking, and when leaving work

9. PHYSICAL AND CHEMICAL PROPERTIES

Appearance, color:	No data available
Odor:	Mild
Physical State:	Liquid
pH:	Not applicable
Vapor Pressure:	No data available
Vapor Density:	2.97 (air = 1)
Boiling Point (°C):	68.73 °C (HSDB)
Melting Point (°C):	-95 °C Melting Point
Flash Point (°F):	-8
Flammability:	Highly Flammable Extremely Flammable
Upper Flammable/Explosive Limit, % in air:	No data available
Lower Flammable/Explosive Limit, % in air:	No data available
Autoignition Temperature (°C):	No data available deg C
Decomposition Temperature (°C):	No data available
Specific Gravity:	0.672 g/cm3 at 15 °C
Evaporation Rate:	No data available
Odor Threshold:	No data available
Solubility:	Negligible; 0-1%
Partition Coefficient: n-octanol in water:	No data available
VOC % by weight:	0
Molecular Weight:	No data available

10. STABILITY AND REACTIVITY

Stability:	Stable under normal conditions.
Conditions to Avoid:	None known.
Materials to Avoid / Chemical Incompatiability:	Strong oxidizing agents
Hazardous Decomposition Products:	No data available

11. TOXICOLOGICAL INFORMATION

Routes of Entry:	Inhalation Contact Absorption Ingestion
Target Organs Potentially Affected By Exposure:	Eyes, Central nervous system stimulation,

Respiratory Tract, Skin, Peripheral Nervous System

Chemical Interactions That Change Toxicity: None Known

Immediate (Acute) Health Effects by Route of Exposure:

Inhalation Irritation: Can cause severe respiratory irritation, dizziness, weakness, fatigue, nausea, headache and possible unconsciousness.

Skin Contact: Can cause moderate skin irritation, defatting, and dermatitis. Not likely to cause permanent damage.

Skin Absorption: May cause irritation and minor systemic damage.Harmful if absorbed through the skin.

Eye Contact: Can cause moderate irritation, tearing and reddening, but not likely to permanently injure eye tissue.

Ingestion Irritation: Irritating to mouth, throat, and stomach. Can cause abdominal discomfort, nausea, vomiting and diarrhea.Harmful if swallowed.

Ingestion Toxicity: Toxic if swallowed. May cause target organ failure and/or death.

Long-Term (Chronic) Health Effects:

Carcinogenicity: No data.

Reproductive and Developmental Toxicity: No data available to indicate product or any components present at greater than 0.1% may cause birth defects.

Inhalation: Upon prolonged and/or repeated exposure, can cause severe respiratory irritation, dizziness, weakness, fatigue, nausea, headache and possible unconsciousness.

Skin Contact: Upon prolonged or repeated contact, can cause moderate skin irritation, defatting, and dermatitis. Not likely to cause permanent damage.

Skin Absorption: Upon prolonged or repeated exposure, harmful if absorbed through the skin. May cause minor systemic damage.

Component Toxicological Data:

NIOSH:

Chemical Name	CAS No.	LD50/LC50
Aroclor 1254	11097-69-1	Oral LD50 Rat 1010 mg/kg
n-Hexane	110-54-3	Dermal LD50 Rabbit 3000 mg/kg; Inhalation LC50 Rat 48000 ppm 4 h; Oral LD50 Rat 25 g/kg

Component Carcinogenic Data:

OSHA:

Chemical Name	CAS No.	
Aroclor 1254	11097-69-1	Present

ACGIH:

Chemical Name	CAS No.	
Chlorodiphenyl (54% chlorine)	11097-69-1	A3 - Confirmed Animal Carcinogen with Unknown Relevance to Humans

NIOSH:

Chemical Name	CAS No.	
Chlorodiphenyl (54% chlorine)	11097-69-1	potential occupational carcinogen

NTP:

Chemical Name	CAS No.
No data available	

IARC:

Chemical Name	CAS No.	Group No.

12. ECOLOGICAL INFORMATION

Overview: Moderate ecological hazard. This product may be dangerous to plants and/or wildlife.

Mobility: No data

Persistence: No data

Bioaccumulation: No data

Degradability: No data

Ecological Toxicity Data: No data available

13. DISPOSAL CONSIDERATIONS

Waste Description of Spent Product: Spent or discarded material is a hazardous waste.Mixing spent or discarded material with other materials may render the mixture hazardous. Perform a hazardous waste determination on mixtures.

Disposal Methods: Dispose of by incineration following Federal, State, Local, or Provincial regulations.

Waste Disposal of Packaging: Comply with all Local, State, Federal, and Provincial Environmental Regulations.

14. TRANSPORTATION INFORMATION

United States:

DOT Proper Shipping Name: Hexanes
UN Number: UN1208
Hazard Class: 3
Packing Group: II

International:

IATA Proper Shipping Name: Hexanes
UN Number: UN1208
Hazard Class: 3
Packing Group: II

Marine Pollutant: Yes

Chemical Name	CAS#	Marine Pollutant	Severe Marine Pollutant
hexane	110-54-3	Y	N

15. REGULATORY INFORMATION

United States:

Chemical Name	CAS#	CERCLA	SARA 313	SARA EHS 313	TSCA
hexane	110-54-3	X	X	-	X
aroclor® 1254	11097-69-1	X	-	-	-

The following chemicals are listed on CA Prop 65:

Chemical Name	CAS #	Regulation

State Right To Know Listing:

Chemical Name	CAS#	New Jersey	Massachusetts	Pennsylvania	California
hexane	110-54-3	X	X	X	-
aroclor® 1254	11097-69-1	-	X	X	X

16. OTHER INFORMATION

Prior Version Date: 09/20/16

Other Information: Any changes to the SDS compared to previous versions are marked by a vertical line in front of the concerned paragraph.

References: No data available

Disclaimer: Restek Corporation provides the descriptions, data and information contained herein in good faith but makes no representation as to its comprehensiveness or accuracy. It is provided for your guidance only. Because many factors may affect processing or application/use, Restek Corporation recommends you perform an assessment to determine the suitability of a product for your particular purpose prior to use. No warranties of any kind, either expressed or implied, including fitness for a particular purpose, are made regarding products described, data or information set forth. In no case shall the descriptions, information, or data provided be considered a part of our terms and conditions of sale. Further, the descriptions, data and information furnished hereunder are given gratis. No obligation or liability for the description, data and information given are assumed. All such being given and accepted at your risk.

Safety Data Sheet
acc. to OSHA HCS

Printing date 01/17/2019 Reviewed on 01/17/2019

1 Identification

· **Product identifier**

· **Product Name: Aroclor 1260**

· **Part Number:** PCB-1260
· **Application of the substance / the mixture** Certified Reference Material

· **Details of the supplier of the safety data sheet**
· **Manufacturer/Supplier:**
SPEX CertiPrep, LLC.
203 Norcross Ave, Metuchen,
NJ 08840 USA

· **Information department:** product safety department
· **Emergency telephone number:**
Emergency Phone Number (24 hours)
CHEMTREC (800-424-9300)
Outside US: 703-527-3887

2 Hazard(s) identification

· **Classification of the substance or mixture**

GHS02 Flame

Flam. Liq. 2 H225 Highly flammable liquid and vapor.

GHS08 Health hazard

Repr. 2 H361 Suspected of damaging fertility or the unborn child.
STOT RE 2 H373 May cause damage to organs through prolonged or repeated exposure.
Asp. Tox. 1 H304 May be fatal if swallowed and enters airways.

GHS07

Skin Irrit. 2 H315 Causes skin irritation.
STOT SE 3 H336 May cause drowsiness or dizziness.

· **Label elements**
· **GHS label elements** The product is classified and labeled according to the Globally Harmonized System (GHS).
· **Hazard pictograms**

GHS02 GHS07 GHS08

· **Signal word** Danger

· **Hazard-determining components of labeling:**
n-hexane
· **Hazard statements**
H225 Highly flammable liquid and vapor.
H315 Causes skin irritation.
H361 Suspected of damaging fertility or the unborn child.
H336 May cause drowsiness or dizziness.
H373 May cause damage to organs through prolonged or repeated exposure.
H304 May be fatal if swallowed and enters airways.
· **Precautionary statements**
If medical advice is needed, have product container or label at hand.
Keep out of reach of children.
Read label before use.
If swallowed: Immediately call a poison center/doctor.
Specific treatment (see on this label).
Do NOT induce vomiting.
If on skin (or hair): Take off immediately all contaminated clothing. Rinse skin with water/shower.

(Contd. on page 2)

Safety Data Sheet
acc. to OSHA HCS

Printing date 01/17/2019 Reviewed on 01/17/2019

Product Name: Aroclor 1260

(Contd. of page 1)

Take off contaminated clothing and wash it before reuse.
Store locked up.
Dispose of contents/container in accordance with local/regional/national/international regulations.
· **Classification system:**
· **NFPA ratings (scale 0 - 4)**

Health = 1
Fire = 3
Reactivity = 0

· **HMIS-ratings (scale 0 - 4)**

Health = 1
Fire = 3
Reactivity = 0

· **Other hazards**
· **Results of PBT and vPvB assessment**
· **PBT:** Not applicable.
· **vPvB:** Not applicable.

3 Composition/information on ingredients

· **Chemical characterization: Mixtures**
· **Description:** Mixture of the substances listed below with nonhazardous additions.

· **Dangerous components:**		
110-54-3	n-hexane	99.98%

· **Chemical identification of the substance/preparation**		
11096-82-5	aroclor 1260	0.02%

4 First-aid measures

· **Description of first aid measures**
· **General information:**
Immediately remove any clothing soiled by the product.
Symptoms of poisoning may even occur after several hours; therefore medical observation for at least 48 hours after the accident.
· **After inhalation:** Supply fresh air; consult doctor in case of complaints.
· **After skin contact:** Immediately rinse with water.
· **After eye contact:** Rinse opened eye for several minutes under running water.
· **After swallowing:** Do not give anything to eat or drink - Do not induce vomitting
· **Information for Doctor:**
· **Most important symptoms and effects, both acute and delayed** No further relevant information available.
· **Indication of any immediate medical attention and special treatment needed** No further relevant information available.

5 Fire-fighting measures

· **Extinguishing media**
· **Suitable extinguishing agents:** CO2, extinguishing powder or water spray. Fight larger fires with water spray or alcohol resistant foam.
· **For safety reasons unsuitable extinguishing agents:** Water with full jet
· **Special hazards arising from the substance or mixture** During heating or in case of fire poisonous gases are produced.
· **Advice for firefighters**
· **Protective equipment:** Mouth respiratory protective device.

6 Accidental release measures

· **Personal precautions, protective equipment and emergency procedures**
Mount respiratory protective device.
Wear protective equipment. Keep unprotected persons away.
· **Environmental precautions:** Do not allow to enter sewers/ surface or ground water.
· **Methods and material for containment and cleaning up:**
Absorb with liquid-binding material (sand, diatomite, acid binders, universal binders, sawdust).
Dispose contaminated material as waste according to item 13.
Ensure adequate ventilation.

(Contd. on page 3)

Safety Data Sheet
acc. to OSHA HCS

Product Name: Aroclor 1260

(Contd. of page 2)

· **Reference to other sections**
See Section 7 for information on safe handling.
See Section 8 for information on personal protection equipment.
See Section 13 for disposal information.
· **Protective Action Criteria for Chemicals**

· **PAC-1:**		
110-54-3	n-hexane	260 ppm
11096-82-5	aroclor 1260	0.41 mg/m³

· **PAC-2:**		
110-54-3	n-hexane	2900* ppm
11096-82-5	aroclor 1260	4.5 mg/m³

· **PAC-3:**		
110-54-3	n-hexane	8600** ppm
11096-82-5	aroclor 1260	260 mg/m³

7 Handling and storage

· **Handling:**
· **Precautions for safe handling**
Ensure good ventilation/exhaustion at the workplace.
Open and handle receptacle with care.
Prevent formation of aerosols.
· **Information about protection against explosions and fires:**
Keep ignition sources away - Do not smoke.
Protect against electrostatic charges.
Keep respiratory protective device available.

· **Conditions for safe storage, including any incompatibilities**
· **Storage:**
· **Requirements to be met by storerooms and receptacles:** Store in a cool location.
· **Information about storage in one common storage facility:** Not required.
· **Further information about storage conditions:**
Keep receptacle tightly sealed.
Store in cool, dry conditions in well sealed receptacles.
· **Specific end use(s)** No further relevant information available.

8 Exposure controls/personal protection

· **Additional information about design of technical systems:** No further data; see item 7.

· **Control parameters**

· **Components with limit values that require monitoring at the workplace:**	
110-54-3 n-hexane	
PEL	Long-term value: 1800 mg/m³, 500 ppm
REL	Long-term value: 180 mg/m³, 50 ppm
TLV	Long-term value: 176 mg/m³, 50 ppm Skin; BEI

· **Ingredients with biological limit values:**	
110-54-3 n-hexane	
BEI	0.4 mg/L Medium: urine Time: end of shift at end of workweek Parameter: 2.5-Hexanedione without hydrolysis

· **Additional information:** The lists that were valid during the creation were used as basis.

· **Exposure controls**
· **Personal protective equipment:**
· **General protective and hygienic measures:**
Keep away from foodstuffs, beverages and feed.
Immediately remove all soiled and contaminated clothing.
Wash hands before breaks and at the end of work.
Store protective clothing separately.
· **Respiratory protection:**
In case of brief exposure or low pollution use respiratory filter device. In case of intensive or longer exposure use respiratory protective device that is independent of circulating air.

(Contd. on page 4)

Safety Data Sheet
acc. to OSHA HCS

Product Name: Aroclor 1260

(Contd. of page 3)

· **Protection of hands:**

Protective gloves

The glove material has to be impermeable and resistant to the product/ the substance/ the preparation.
Due to missing tests no recommendation to the glove material can be given for the product/ the preparation/ the chemical mixture.
Selection of the glove material on consideration of the penetration times, rates of diffusion and the degradation

· **Material of gloves**
The selection of the suitable gloves does not only depend on the material, but also on further marks of quality and varies from manufacturer to manufacturer. As the product is a preparation of several substances, the resistance of the glove material can not be calculated in advance and has therefore to be checked prior to the application.

· **Penetration time of glove material**
The exact break through time has to be found out by the manufacturer of the protective gloves and has to be observed.

· **Eye protection:**

Tightly sealed goggles

9 Physical and chemical properties

· **Information on basic physical and chemical properties**	
· **General Information**	
· **Appearance:**	
Form:	Liquid
Color:	According to product specification
· **Odor:**	Characteristic
· **Odour Threshold:**	Not applicable.
· **pH-value:**	Not applicable.
· **Change in condition**	
Melting point/Melting range:	Undetermined.
Boiling point/Boiling range:	69 °C (156.2 °F)
· **Flash point:**	< 0 °C (<32 °F)
· **Flammability (solid, gaseous):**	Not applicable.
· **Ignition temperature:**	240 °C (464 °F)
· **Decomposition temperature:**	Not applicable.
· **Auto igniting:**	Product is not selfigniting.
· **Danger of explosion:**	Product is not explosive. However, formation of explosive air/vapor mixtures are possible.
· **Explosion limits:**	
Lower:	1.2 Vol %
Upper:	7.4 Vol %
· **Vapor pressure at 20 °C (68 °F):**	160 hPa (120 mm Hg)
· **Density at 20 °C (68 °F)**	0.87912 g/cm³ (7.33626 lbs/gal)
· **Relative density**	Not applicable.
· **Vapor density**	Not applicable.
· **Evaporation rate**	Not applicable.
· **Solubility in / Miscibility with**	
Water:	Not miscible or difficult to mix.
· **Partition coefficient (n-octanol/water):**	Not applicable.
· **Viscosity:**	
Dynamic:	Not applicable.
Kinematic:	Not applicable.
· **Solvent content:**	
Organic solvents:	100.0 %
VOC content:	99.98 %
Solids content:	0.0 %

(Contd. on page 5)

Safety Data Sheet
acc. to OSHA HCS

Printing date 01/17/2019 Reviewed on 01/17/2019

Product Name: Aroclor 1260

(Contd. of page 4)

· **Other information** No further relevant information available.

10 Stability and reactivity

· **Reactivity** No further relevant information available.
· **Chemical stability**
· **Thermal decomposition / conditions to be avoided:** No decomposition if used according to specifications.
· **Possibility of hazardous reactions** No dangerous reactions known.
· **Conditions to avoid** No further relevant information available.
· **Incompatible materials:** No further relevant information available.
· **Hazardous decomposition products:** No dangerous decomposition products known.

11 Toxicological information

· **Information on toxicological effects**
· **Acute toxicity:**
· **Primary irritant effect:**
· **on the skin:** Irritant to skin and mucous membranes.
· **on the eye:** No irritating effect.
· **Sensitization:** No sensitizing effects known.
· **Additional toxicological information:**
The product shows the following dangers according to internally approved calculation methods for preparations:
Irritant
Product is suspected to cause damage to fertility.
Product is suspected to cause birth defects.

· **Carcinogenic categories**

· **IARC (International Agency for Research on Cancer)**		
None of the ingredients is listed.		

· **NTP (National Toxicology Program)**		
11096-82-5	aroclor 1260	R

· **OSHA-Ca (Occupational Safety & Health Administration)**
None of the ingredients is listed.

12 Ecological information

· **Toxicity**
· **Aquatic toxicity:** No further relevant information available.
· **Persistence and degradability** No further relevant information available.
· **Behavior in environmental systems:**
· **Bioaccumulative potential** No further relevant information available.
· **Mobility in soil** No further relevant information available.
· **Additional ecological information:**
· **General notes:**
Water hazard class 2 (Self-assessment): hazardous for water
Do not allow product to reach ground water, water course or sewage system.
Danger to drinking water if even small quantities leak into the ground.
· **Results of PBT and vPvB assessment**
· **PBT:** Not applicable.
· **vPvB:** Not applicable.
· **Other adverse effects** No further relevant information available.

13 Disposal considerations

· **Waste treatment methods**
· **Recommendation:** Must not be disposed of together with household garbage. Do not allow product to reach sewage system.

· **Uncleaned packagings:**
· **Recommendation:** Disposal must be made according to official regulations.

(Contd. on page 6)

Safety Data Sheet
acc. to OSHA HCS

Product Name: Aroclor 1260

(Contd. of page 5)

14 Transport information

· **UN-Number**	
· **DOT, ADR, IMDG, IATA**	UN1208
· **UN proper shipping name**	
· **DOT**	Hexanes
· **ADR**	1208 Hexanes, ENVIRONMENTALLY HAZARDOUS
· **IMDG**	HEXANES, MARINE POLLUTANT
· **IATA**	HEXANES
· **Transport hazard class(es)**	
· **DOT**	

· **Class**	3 Flammable liquids
· **Label**	3
· **ADR, IMDG**	

· **Class**	3 Flammable liquids
· **Label**	3
· **IATA**	

· **Class**	3 Flammable liquids
· **Label**	3
· **Packing group**	
· **DOT, ADR, IMDG, IATA**	II
· **Environmental hazards:**	Product contains environmentally hazardous substances: n-hexane
· **Marine pollutant:**	Symbol (fish and tree)
· **Special marking (ADR):**	Symbol (fish and tree)
· **Special precautions for user**	Warning: Flammable liquids
· **Danger code (Kemler):**	33
· **EMS Number:**	F-E,S-D
· **Stowage Category**	E
· **Transport in bulk according to Annex II of MARPOL73/78 and the IBC Code**	Not applicable.
· **Transport/Additional information:**	
· **ADR**	
· **Excepted quantities (EQ)**	Code: E2 Maximum net quantity per inner packaging: 30 ml Maximum net quantity per outer packaging: 500 ml
· **IMDG**	
· **Limited quantities (LQ)**	1L
· **Excepted quantities (EQ)**	Code: E2 Maximum net quantity per inner packaging: 30 ml Maximum net quantity per outer packaging: 500 ml
· **UN "Model Regulation":**	UN 1208 HEXANES, 3, II, ENVIRONMENTALLY HAZARDOUS

US

(Contd. on page 7)

Safety Data Sheet
acc. to OSHA HCS

Product Name: Aroclor 1260

(Contd. of page 6)

15 Regulatory information

· **Safety, health and environmental regulations/legislation specific for the substance or mixture**
· **Sara**

· **Section 313 (Specific toxic chemical listings):**

110-54-3	n-hexane

· **TSCA (Toxic Substances Control Act):**

110-54-3	n-hexane

· **Proposition 65**

· **Chemicals known to cause cancer:**

11096-82-5	aroclor 1260

· **Chemicals known to cause reproductive toxicity for females:**
None of the ingredients is listed.

· **Chemicals known to cause reproductive toxicity for males:**

110-54-3	n-hexane

· **Chemicals known to cause developmental toxicity:**
None of the ingredients is listed.

· **Carcinogenic categories**

· **EPA (Environmental Protection Agency)**

110-54-3	n-hexane	II

· **TLV (Threshold Limit Value established by ACGIH)**
None of the ingredients is listed.

· **NIOSH-Ca (National Institute for Occupational Safety and Health)**
None of the ingredients is listed.

· **GHS label elements** The product is classified and labeled according to the Globally Harmonized System (GHS).
· **Hazard pictograms**

GHS02 GHS07 GHS08

· **Signal word** Danger

· **Hazard-determining components of labeling:**
n-hexane
· **Hazard statements**
H225 Highly flammable liquid and vapor.
H315 Causes skin irritation.
H361 Suspected of damaging fertility or the unborn child.
H336 May cause drowsiness or dizziness.
H373 May cause damage to organs through prolonged or repeated exposure.
H304 May be fatal if swallowed and enters airways.
· **Precautionary statements**
If medical advice is needed, have product container or label at hand.
Keep out of reach of children.
Read label before use.
If swallowed: Immediately call a poison center/doctor.
Specific treatment (see on this label).
Do NOT induce vomiting.
If on skin (or hair): Take off immediately all contaminated clothing. Rinse skin with water/shower.
Take off contaminated clothing and wash it before reuse.
Store locked up.
Dispose of contents/container in accordance with local/regional/national/international regulations.
· **Chemical safety assessment:** A Chemical Safety Assessment has not been carried out.

16 Other information

This information is based on our present knowledge. However, this shall not constitute a guarantee for any specific product features and shall not establish a legally valid contractual relationship.

· **Department issuing SDS:** product safety department

(Contd. on page 8)

Safety Data Sheet
acc. to OSHA HCS

Product Name: Aroclor 1260

(Contd. of page 7)

· **Contact:**
SPEX CertiPrep, LLC.
1-732-549-7144
· **Date of preparation / last revision** 01/17/2019 / -
· **Abbreviations and acronyms:**
ADR: Accord européen sur le transport des marchandises dangereuses par Route (European Agreement concerning the International Carriage of Dangerous Goods by Road)
IMDG: International Maritime Code for Dangerous Goods
DOT: US Department of Transportation
IATA: International Air Transport Association
ACGIH: American Conference of Governmental Industrial Hygienists
EINECS: European Inventory of Existing Commercial Chemical Substances
ELINCS: European List of Notified Chemical Substances
CAS: Chemical Abstracts Service (division of the American Chemical Society)
NFPA: National Fire Protection Association (USA)
HMIS: Hazardous Materials Identification System (USA)
VOC: Volatile Organic Compounds (USA, EU)
PBT: Persistent, Bioaccumulative and Toxic
vPvB: very Persistent and very Bioaccumulative
NIOSH: National Institute for Occupational Safety
OSHA: Occupational Safety & Health
TLV: Threshold Limit Value
PEL: Permissible Exposure Limit
REL: Recommended Exposure Limit
BEI: Biological Exposure Limit
Flam. Liq. 2: Flammable liquids – Category 2
Skin Irrit. 2: Skin corrosion/irritation – Category 2
Repr. 2: Reproductive toxicity – Category 2
STOT SE 3: Specific target organ toxicity (single exposure) – Category 3
STOT RE 2: Specific target organ toxicity (repeated exposure) – Category 2
Asp. Tox. 1: Aspiration hazard – Category 1

SAFETY DATA SHEET
Dieldrin

Revision: 04/28/2018

according to Regulation (EC) No. 1907/2006 as amended by (EC) No. 1272/2008

Section 1. Identification of the Substance/Mixture and of the Company/Undertaking

1.1 Product Code: 24043

Product Name: Dieldrin

Synonyms: rel-3,4,5,6,9,9-hexachloro-1aR,2R,2aS,3S,6R,6aR,7S,7aS-octahydro-2,7:3,6-dimethanonaphth[2,3-b]oxirene; Aldrin epoxide; Dieldrex; exo-Dieldrin;

1.2 Relevant identified uses of the substance or mixture and uses advised against:

Relevant identified uses: For research use only, not for human or veterinary use.

1.3 Details of the Supplier of the Safety Data Sheet:

Company Name: Cayman Chemical Company
1180 E. Ellsworth Rd.
Ann Arbor, MI 48108

Web site address: www.caymanchem.com

Information: Cayman Chemical Company +1 (734)971-3335

1.4 Emergency telephone number:

Emergency Contact: CHEMTREC Within USA and Canada: +1 (800)424-9300
CHEMTREC Outside USA and Canada: +1 (703)527-3887

Section 2. Hazards Identification

2.1 Classification of the Substance or Mixture:

Acute Toxicity: Oral, Category 3

Acute Toxicity: Skin, Category 1

Carcinogenicity, Category 2

Specific Target Organ Toxicity (repeated exposure), Category 1

Aquatic Toxicity (Acute), Category 1

Aquatic Toxicity (Chronic), Category 1

2.2 Label Elements:

GHS Signal Word: **Danger**

GHS Hazard Phrases:

H301: Toxic if swallowed.

H310: Fatal in contact with skin.

H351: Suspected of causing cancer.

H372: Causes damage to organs through prolonged or repeated exposure.

H400: Very toxic to aquatic life.

H410: Very toxic to aquatic life with long lasting effects.

GHS Precaution Phrases:

P201: Obtain special instructions before use.

P202: Do not handle until all safety precautions have been read and understood.

P260: Do not breathe {dust/fume/gas/mist/vapors/spray}.

P262: Do not get in eyes, on skin, or on clothing.

P264: Wash {hands} thoroughly after handling.

P273: Avoid release to the environment.

P280: Wear {protective gloves/protective clothing/eye protection/face protection}.

GHS Response Phrases:

P301+310: IF SWALLOWED: P310: Immediately call a POISON CENTER or doctor/physician.
P302+352: IF ON SKIN: Wash with plenty of soap and water.
P308+313: IF exposed or concerned: Get medical attention/advice.
P314: Get medical attention/advice if you feel unwell.
P321: Specific treatment {see ... on this label}.
P330: Rinse mouth.
P361+364: Take off immediately all contaminated clothing and wash it before reuse.
P391: Collect spillage.

GHS Storage and Disposal Phrases:

Please refer to Section 7 for Storage and Section 13 for Disposal information.

2.3 Adverse Human Health Effects and Symptoms:

Causes damage to organs through prolonged or repeated exposure.
Fatal in contact with skin.
Material may be irritating to the mucous membranes and upper respiratory tract.
May be harmful by inhalation.
May cause eye, skin, or respiratory system irritation.
Suspected of causing cancer.
Toxic if swallowed.
Very toxic to aquatic life with long lasting effects.
To the best of our knowledge, the toxicological properties have not been thoroughly investigated.

Section 3. Composition/Information on Ingredients

CAS # / RTECS #	Hazardous Components (Chemical Name)/ REACH Registration No.	Concentration	EC No./ EC Index No.	GHS Classification
60-57-1 IO1750000	Dieldrin	100.0 %	200-484-5 602-049-00-9	Acute Tox.(O) 3: H301 Acute Tox.(D) 1: H310 Carcinogen 2: H351 STOT (RE) 1: H372 Aquatic (A) 1: H400 Aquatic (C) 1: H410

Section 4. First Aid Measures

4.1 Description of First Aid Measures:

In Case of Inhalation: Remove to fresh air. If not breathing, give artificial respiration or give oxygen by trained personnel. Get immediate medical attention.

In Case of Skin Contact: Immediately wash skin with soap and plenty of water for at least 15 minutes. Remove contaminated clothing. Get medical attention if symptoms occur. Wash clothing before reuse.

In Case of Eye Contact: Hold eyelids apart and flush eyes with plenty of water for at least 15 minutes. Have eyes examined and tested by medical personnel.

In Case of Ingestion: Wash out mouth with water provided person is conscious. Never give anything by mouth to an unconscious person. Get medical attention. Do NOT induce vomiting unless directed to do so by medical personnel.

Section 5. Fire Fighting Measures

5.1 Suitable Extinguishing Media: Use alcohol-resistant foam, carbon dioxide, water, or dry chemical spray.
Use water spray to cool fire-exposed containers.

Unsuitable Extinguishing Media: A solid water stream may be inefficient.

5.2 Flammable Properties and Hazards: No data available.

No data available.

Flash Pt: No data.

Explosive Limits: LEL: No data. UEL: No data.

Autoignition Pt: No data.

5.3 Fire Fighting Instructions: As in any fire, wear self-contained breathing apparatus pressure-demand (NIOSH approved or equivalent), and full protective gear to prevent contact with skin and eyes.

Section 6. Accidental Release Measures

6.1 Protective Precautions, Protective Equipment and Emergency Procedures: Avoid raising and breathing dust, and provide adequate ventilation.
As conditions warrant, wear a NIOSH approved self-contained breathing apparatus, or respirator, and appropriate personal protection (rubber boots, safety goggles, and heavy rubber gloves).

6.2 Environmental Precautions: Take steps to avoid release into the environment, if safe to do so.

6.3 Methods and Material For Containment and Cleaning Up: Contain spill and collect, as appropriate.
Transfer to a chemical waste container for disposal in accordance with local regulations.

Section 7. Handling and Storage

7.1 Precautions To Be Taken in Handling: Avoid breathing dust/fume/gas/mist/vapours/spray.
Avoid prolonged or repeated exposure.

7.2 Precautions To Be Taken in Storing: Keep container tightly closed.
Store in accordance with information listed on the product insert.

Section 8. Exposure Controls/Personal Protection

8.1 Exposure Parameters:

CAS #	Chemical Name	Jurisdiction	Recommended Exposure Limits	Notations
60-57-1	Dieldrin	ACGIH TLV	TLV: 0.1 mg/m3 (IFV)	
		France VL	TWA: 0.25 mg/m3	
		OSHA PELs	PEL: 0.25 mg/m3	

8.2 Exposure Controls:

8.2.1 Engineering Controls (Ventilation etc.): Use process enclosures, local exhaust ventilation, or other engineering controls to control airborne levels below recommended exposure limits.

8.2.2 Personal protection equipment:

Eye Protection: Safety glasses

Protective Gloves: Compatible chemical-resistant gloves

Other Protective Clothing: Lab coat

Respiratory Equipment (Specify Type): NIOSH approved respirator, as conditions warrant.

Work/Hygienic/Maintenance Practices: Do not take internally.
Facilities storing or utilizing this material should be equipped with an eyewash and a safety shower.

Wash thoroughly after handling.

No data available.

Section 9. Physical and Chemical Properties

9.1 Information on Basic Physical and Chemical Properties

Physical States:	[ ] Gas [ ] Liquid [X] Solid
Appearance and Odor:	A solid
pH:	No data.
Melting Point:	No data.
Boiling Point:	No data.
Flash Pt:	No data.
Evaporation Rate:	No data.
Flammability (solid, gas):	No data available.
Explosive Limits:	LEL: No data. UEL: No data.
Vapor Pressure (vs. Air or mm Hg):	No data.
Vapor Density (vs. Air = 1):	No data.
Specific Gravity (Water = 1):	No data.
Solubility in Water:	No data.
Solubility Notes:	Soluble (slightly) in: chloroform;
Octanol/Water Partition Coefficient:	No data.
Autoignition Pt:	No data.
Decomposition Temperature:	No data.
Viscosity:	No data.

9.2 Other Information

Percent Volatile:	No data.
Molecular Formula & Weight:	C12H8Cl6O 380.9

Section 10. Stability and Reactivity

10.1	**Reactivity:**	No data available.
10.2	**Stability:**	Unstable [ ] Stable [X]
10.3	**Stability Note(s):**	Stable if stored in accordance with information listed on the product insert.
	Polymerization:	Will occur [ ] Will not occur [X]
10.4	**Conditions To Avoid:**	No data available.
10.5	**Incompatibility - Materials To Avoid:**	strong oxidizing agents
10.6	**Hazardous Decomposition or Byproducts:**	carbon dioxide carbon monoxide phosgene

Section 11. Toxicological Information

11.1 Information on Toxicological Effects: The toxicological effects of this product have not been thoroughly studied.
Dieldrin - Toxicity Data: Oral LDLO (man): 65 mg/kg; Oral LD50 (rat): 38300 ug/kg; Intraperitoneal LD50 (rat): 35 mg/kg; Subcutaneous LD50 (rat): 49 mg/kg; Oral LD50 (mouse): 38 mg/kg; Intraperitoneal LDLO (mouse): 26 mg/kg;

Chronic Toxicological Effects: Dieldrin - Investigated as an agricultural chemical, mutagen, reproductive effector, and tumorigen.
Only select Registry of Toxic Effects of Chemical Substances (RTECS) data is presented here. See actual entry in RTECS for complete information.
Dieldrin RTECS Number: IO1750000

CAS #	Hazardous Components (Chemical Name)	NTP	IARC	ACGIH	OSHA
60-57-1	Dieldrin	n.a.	3	A4	n.a.

Section 12. Ecological Information

12.1 Toxicity: Avoid release into the environment.
Runoff from fire control or dilution water may cause pollution.

12.2 Persistence and Degradability: No data available.

12.3 Bioaccumulative Potential: No data available.

12.4 Mobility in Soil: No data available.

12.5 Results of PBT and vPvB assessment: No data available.

12.6 Other adverse effects: No data available.

Section 13. Disposal Considerations

13.1 Waste Disposal Method: Dispose in accordance with local, state, and federal regulations.

Section 14. Transport Information

14.1 LAND TRANSPORT (US DOT):

DOT Proper Shipping Name: Toxic solid, organic, n.o.s. (Dieldrin)
DOT Hazard Class: 6.1 POISON
UN/NA Number: UN2811 **Packing Group:** I

14.1 LAND TRANSPORT (European ADR/RID):

ADR/RID Shipping Name: Toxic solid, organic, n.o.s. (Dieldrin)
UN Number: 2811 **Packing Group:** I
Hazard Class: 6.1 - POISON

14.3 AIR TRANSPORT (ICAO/IATA):

ICAO/IATA Shipping Name: Toxic solid, organic, n.o.s. (Dieldrin)
UN Number: 2811 **Packing Group:** I
Hazard Class: 6.1 - POISON **IATA Classification:** 6.1

Additional Transport Information: Transport in accordance with local, state, and federal regulations.
When sold in quantities of less than or equal to 1 mL, or 1 g, with an Excepted Quantity Code of E1, E2, E4, or E5, this item meets the De Minimis Quantities exemption, per IATA 2.6.10.

Therefore packaging does not have to be labeled as Dangerous Goods/Excepted Quantity.

Section 15. Regulatory Information

EPA SARA (Superfund Amendments and Reauthorization Act of 1986) Lists

CAS #	Hazardous Components (Chemical Name)	S. 302 (EHS)	S. 304 RQ	S. 313 (TRI)
60-57-1	Dieldrin	No	Yes 1 LB	No

CAS #	Hazardous Components (Chemical Name)	Other US EPA or State Lists
60-57-1	Dieldrin	CAA HAP,ODC: No; CWA NPDES: Yes; TSCA: Yes - Inventory; CA PROP.65: Yes: Canc.

Regulatory Information Statement: This SDS was prepared in accordance with 29 CFR 1910.1200 and Regulation (EC) No.1272/2008.

Section 16. Other Information

Revision Date: 04/28/2018

Additional Information About This Product: No data available.

Company Policy or Disclaimer: DISCLAIMER: This information is believed to be accurate and represents the best information currently available to us. However, we make no warranty of merchantability or any other warranty, express or implied, with respect to such information, and we assume no liability resulting from its use. Users should make their own investigations to determine the suitability of the information for their particular purposes.

Material Safety Data Sheet
Iron

ACC# 11490

Section 1 - Chemical Product and Company Identification

MSDS Name: Iron
Catalog Numbers: S71953, S71953-1, S71953-2, S93268, I60-3, I60-500, I62-500
Synonyms: Iron Dust; Iron Metal; Iron Powder.
Company Identification:
Fisher Scientific
1 Reagent Lane
Fair Lawn, NJ 07410
For information, call: 201-796-7100
Emergency Number: 201-796-7100
For CHEMTREC assistance, call: 800-424-9300
For International CHEMTREC assistance, call: 703-527-3887

Section 2 - Composition, Information on Ingredients

CAS#	Chemical Name	Percent	EINECS/ELINCS
7439-89-6	IRON	>97	231-096-4

Section 3 - Hazards Identification

EMERGENCY OVERVIEW

Appearance: black to gray solid.
Warning! Flammable solid. May cause mechanical eye and skin irritation. May cause blood abnormalities. May cause lung damage. Inhalation of fumes may cause metal-fume fever. May cause cardiac disturbances. May cause liver damage.
Target Organs: Liver, respiratory system, cardiovascular system, pancreas.

Potential Health Effects

Eye: Exposure to particulates or solution may cause conjunctivitis, ulceration, and corneal abnormalities.
Skin: May cause skin irritation.
Ingestion: May cause gastrointestinal irritation with nausea, vomiting and diarrhea. Acute toxicity may include weakness, shock, cyanosis and acidosis. Delayed symptoms may include liver
Inhalation: Inhalation of fumes may cause metal fume fever, which is characterized by flu-like symptoms with metallic taste, fever, chills, cough, weakness, chest pain, muscle pain and increased white blood cell count. May cause lung damage.
Chronic: Chronic exposure may lead to liver and lung damage. Repeated exposure may cause pancreatic damage, diabetes, and cardiac abnormalities.

Section 4 - First Aid Measures

Eyes: Immediately flush eyes with plenty of water for at least 15 minutes, occasionally lifting the upper and lower eyelids. Get medical aid imme diately.
Skin: Immediately flush skin with plenty of water for at least 15 minutes while removing contaminated

clothing and shoes. Get medical aid if irritation develops or persists.
Ingestion: If victim is conscious and alert, give 2-4 cupfuls of milk or water. Get medical aid immediately.
Inhalation: Remove from exposure and move to fresh air immediately. If not breathing, give artificial respiration. If breathing is difficult, give oxygen. Get medical aid if cough or other symptoms appear.
Notes to Physician: Treat symptomatically and supportively.
Antidote: The use of Deferoxamine as a chelating agent should be determined only by qualified medical personnel.

Section 5 - Fire Fighting Measures

General Information: As in any fire, wear a self-contained breathing apparatus in pressure-demand, MSHA/NIOSH (approved or equivalent), and full protective gear. Dusts at sufficient concentrations can form explosive mixtures with air. Combustion generates toxic fumes.
Extinguishing Media: Use only graphite powder, soda ash, powdered sodium chloride, or an appropriate metal-fire-extinguishing dry powder.
Flash Point: Not applicable.
Autoignition Temperature: Not applicable.
Explosion Limits, Lower: Not available.
Upper: Not available.
NFPA Rating: (estimated) Health: 2; Flammability: 1; Instability: 1

Section 6 - Accidental Release Measures

General Information: Use proper personal protective equipment as indicated in Section 8.
Spills/Leaks: Sweep up or absorb material, then place into a suitable clean, dry, closed container for disposal. Avoid generating dusty conditions. Remove all sources of ignition.

Section 7 - Handling and Storage

Handling: Wash thoroughly after handling. Remove contaminated clothing and wash before reuse. Use with adequate ventilation. Minimize dust generation and accumulation. Avoid contact with eyes, skin, and clothing. Keep container tightly closed. Avoid ingestion and inhalation.
Storage: Keep from contact with oxidizing materials. Store in a cool, dry, well-ventilated area away from incompatible substances.

Section 8 - Exposure Controls, Personal Protection

Engineering Controls: Use process enclosure, local exhaust ventilation, or other engineering controls to control airborne levels.
Exposure Limits

Chemical Name	ACGIH	NIOSH	OSHA - Final PELs
IRON	none listed	none listed	none listed

OSHA Vacated PELs: IRON: No OSHA Vacated PELs are listed for this chemical.
Personal Protective Equipment
Eyes: Wear appropriate protective eyeglasses or chemical safety goggles as described by OSHA's eye and face protection regulations in 29 CFR 1910.133 or European Standard EN166.
Skin: Wear impervious gloves.
Clothing: Wear appropriate protective clothing to prevent skin exposure.
Respirators: Follow the OSHA respirator regulations found in 29 CFR 1910.134 or European Standard EN

149. Use a NIOSH/MSHA or European Standard EN 149 approved respirator if exposure limits are exceeded or if irritation or other symptoms are experienced.

Section 9 - Physical and Chemical Properties

Physical State: Solid
Appearance: black to gray
Odor: none reported
pH: Not available.
Vapor Pressure: 1 mm Hg @ 1787 deg C
Vapor Density: Not available.
Evaporation Rate: Negligible.
Viscosity: Not available.
Boiling Point: 2750 deg C
Freezing/Melting Point:1535 deg C
Decomposition Temperature: Not available.
Solubility: Insoluble in water.
Specific Gravity/Density:7.86 @ 20°C
Molecular Formula: Fe
Molecular Weight:55.847

Section 10 - Stability and Reactivity

Chemical Stability: Decomposes when heated. Oxidizes when exposed to air.
Conditions to Avoid: Incompatible materials, moisture, exposure to air, excess heat.
Incompatibilities with Other Materials: Acetaldehyde, ammonium peroxodisulfate, chloroformamidinium, chloric acid, ammonium nitrate, halogens, dinitrogen tetroxide, nitryl fluoride, polystyrene, sodium acetylide, potassium dichromate, peroxyformic acid, nitryl fluoride, sulfuric acid, sodium carbide.
Hazardous Decomposition Products: Oxides of iron.
Hazardous Polymerization: Has not been reported.

Section 11 - Toxicological Information

RTECS#:
CAS# 7439-89-6: NO4565500; NO8225000
LD50/LC50:
CAS# 7439-89-6:
Oral, rat: LD50 = 30 gm/kg;
.

Carcinogenicity:
CAS# 7439-89-6: Not listed by ACGIH, IARC, NTP, or CA Prop 65.

Epidemiology: No information available.
Teratogenicity: No information available.
Reproductive Effects: No information available.
Mutagenicity: No information available.
Neurotoxicity: No information available.
Other Studies:

Section 12 - Ecological Information

Ecotoxicity: No data available. No information available.
Environmental: No information reported.
Physical: No information available.
Other: None.

Section 13 - Disposal Considerations

Chemical waste generators must determine whether a discarded chemical is classified as a hazardous waste. US EPA guidelines for the classification determination are listed in 40 CFR Parts 261.3. Additionally, waste generators must consult state and local hazardous waste regulations to ensure complete and accurate classification.
RCRA P-Series: None listed.
RCRA U-Series: None listed.

Section 14 - Transport Information

	US DOT	Canada TDG
Shipping Name:	METAL POWDERS, FLAMMABLE, N.O.S.	METAL POWDER FLAMMABLE NOS (IRON)
Hazard Class:	4.1	4.1
UN Number:	UN3089	UN3089
Packing Group:	II	III

Section 15 - Regulatory Information

US FEDERAL

TSCA
CAS# 7439-89-6 is listed on the TSCA inventory.
Health & Safety Reporting List
None of the chemicals are on the Health & Safety Reporting List.
Chemical Test Rules
None of the chemicals in this product are under a Chemical Test Rule.
Section 12b
None of the chemicals are listed under TSCA Section 12b.
TSCA Significant New Use Rule
None of the chemicals in this material have a SNUR under TSCA.
CERCLA Hazardous Substances and corresponding RQs
None of the chemicals in this material have an RQ.
SARA Section 302 Extremely Hazardous Substances
None of the chemicals in this product have a TPQ.
SARA Codes
CAS # 7439-89-6: immediate, fire.
Section 313 No chemicals are reportable under Section 313.
Clean Air Act:
This material does not contain any hazardous air pollutants.
This material does not contain any Class 1 Ozone depletors.
This material does not contain any Class 2 Ozone depletors.
Clean Water Act:
None of the chemicals in this product are listed as Hazardous Substances under the CWA.
None of the chemicals in this product are listed as Priority Pollutants under the CWA.
None of the chemicals in this product are listed as Toxic Pollutants under the CWA.
OSHA:

None of the chemicals in this product are considered highly hazardous by OSHA.

STATE

CAS# 7439-89-6 can be found on the following state right to know lists: California.

California Prop 65

California No Significant Risk Level: None of the chemicals in this product are listed.

European/International Regulations

European Labeling in Accordance with EC Directives

Hazard Symbols:

Not available.

Risk Phrases:

Safety Phrases:

WGK (Water Danger/Protection)

CAS# 7439-89-6: 0

Canada - DSL/NDSL

CAS# 7439-89-6 is listed on Canada's DSL List.

Canada - WHMIS

This product has a WHMIS classification of B4, D2B.

This product has been classified in accordance with the hazard criteria of the Controlled Products Regulations and the MSDS contains all of the information required by those regulations.

Canadian Ingredient Disclosure List

Section 16 - Additional Information

MSDS Creation Date: 12/12/1997
Revision #4 Date: 11/06/2007

The information above is believed to be accurate and represents the best information currently available to us. However, we make no warranty of merchantability or any other warranty, express or implied, with respect to such information, and we assume no liability resulting from its use. Users should make their own investigations to determine the suitability of the information for their particular purposes. In no event shall Fisher be liable for any claims, losses, or damages of any third party or for lost profits or any special, indirect, incidental, consequential or exemplary damages, howsoever arising, even if Fisher has been advised of the possibility of such damages.

SAFETY DATA SHEET

Methane

Section 1. Identification

GHS product identifier : Methane

Chemical name : methane

Other means of identification : Methane or natural gas; Marsh gas; Methyl hydride; CH4; Fire Damp;

Product type : Gas.

Product use : Synthetic/Analytical chemistry.

Synonym : Methane or natural gas; Marsh gas; Methyl hydride; CH4; Fire Damp;

SDS # : 001033

Supplier's details : Airgas USA, LLC and its affiliates
259 North Radnor-Chester Road
Suite 100
Radnor, PA 19087-5283
1-610-687-5253

24-hour telephone : 1-866-734-3438

Section 2. Hazards identification

OSHA/HCS status : This material is considered hazardous by the OSHA Hazard Communication Standard (29 CFR 1910.1200).

Classification of the substance or mixture : FLAMMABLE GASES - Category 1
GASES UNDER PRESSURE - Compressed gas

GHS label elements

Hazard pictograms :

Signal word : Danger

Hazard statements : Extremely flammable gas.
May form explosive mixtures with air.
Contains gas under pressure; may explode if heated.
May displace oxygen and cause rapid suffocation.

Precautionary statements

General : Read and follow all Safety Data Sheets (SDS'S) before use. Read label before use. Keep out of reach of children. If medical advice is needed, have product container or label at hand. Close valve after each use and when empty. Use equipment rated for cylinder pressure. Do not open valve until connected to equipment prepared for use. Use a back flow preventative device in the piping. Use only equipment of compatible materials of construction. Approach suspected leak area with caution.

Prevention : Keep away from heat, hot surfaces, sparks, open flames and other ignition sources. No smoking.

Response : Leaking gas fire: Do not extinguish, unless leak can be stopped safely. Eliminate all ignition sources if safe to do so.

Storage : Protect from sunlight. Store in a well-ventilated place.

Disposal : Not applicable.

Hazards not otherwise classified : In addition to any other important health or physical hazards, this product may displace oxygen and cause rapid suffocation.

Section 3. Composition/information on ingredients

Substance/mixture : Substance

Chemical name : methane

Other means of identification : Methane or natural gas; Marsh gas; Methyl hydride; CH4; Fire Damp;

Product code : 001033

CAS number/other identifiers

CAS number : 74-82-8

Ingredient name	%	CAS number
methane	100	74-82-8

Any concentration shown as a range is to protect confidentiality or is due to batch variation.

There are no additional ingredients present which, within the current knowledge of the supplier and in the concentrations applicable, are classified as hazardous to health or the environment and hence require reporting in this section.

Occupational exposure limits, if available, are listed in Section 8.

Section 4. First aid measures

Description of necessary first aid measures

Eye contact : Immediately flush eyes with plenty of water, occasionally lifting the upper and lower eyelids. Check for and remove any contact lenses. Continue to rinse for at least 10 minutes. Get medical attention if irritation occurs.

Inhalation : Remove victim to fresh air and keep at rest in a position comfortable for breathing. If not breathing, if breathing is irregular or if respiratory arrest occurs, provide artificial respiration or oxygen by trained personnel. It may be dangerous to the person providing aid to give mouth-to-mouth resuscitation. Get medical attention if adverse health effects persist or are severe. If unconscious, place in recovery position and get medical attention immediately. Maintain an open airway. Loosen tight clothing such as a collar, tie, belt or waistband.

Skin contact : Wash contaminated skin with soap and water. Remove contaminated clothing and shoes. To avoid the risk of static discharges and gas ignition, soak contaminated clothing thoroughly with water before removing it. Get medical attention if symptoms occur. Wash clothing before reuse. Clean shoes thoroughly before reuse.

Ingestion : As this product is a gas, refer to the inhalation section.

Most important symptoms/effects, acute and delayed

Potential acute health effects

Eye contact : Contact with rapidly expanding gas may cause burns or frostbite.

Inhalation : No known significant effects or critical hazards.

Skin contact : Contact with rapidly expanding gas may cause burns or frostbite.

Frostbite : Try to warm up the frozen tissues and seek medical attention.

Ingestion : As this product is a gas, refer to the inhalation section.

Over-exposure signs/symptoms

Eye contact : No specific data.

Inhalation : No specific data.

Skin contact : No specific data.

Ingestion : No specific data.

Indication of immediate medical attention and special treatment needed, if necessary

Notes to physician : Treat symptomatically. Contact poison treatment specialist immediately if large quantities have been ingested or inhaled.

Specific treatments : No specific treatment.

Section 4. First aid measures

Protection of first-aiders : No action shall be taken involving any personal risk or without suitable training. It may be dangerous to the person providing aid to give mouth-to-mouth resuscitation.

See toxicological information (Section 11)

Section 5. Fire-fighting measures

Extinguishing media

Suitable extinguishing media : Use an extinguishing agent suitable for the surrounding fire.

Unsuitable extinguishing media : None known.

Specific hazards arising from the chemical : Contains gas under pressure. Extremely flammable gas. In a fire or if heated, a pressure increase will occur and the container may burst, with the risk of a subsequent explosion.

Hazardous thermal decomposition products : Decomposition products may include the following materials:
carbon dioxide
carbon monoxide

Special protective actions for fire-fighters : Promptly isolate the scene by removing all persons from the vicinity of the incident if there is a fire. No action shall be taken involving any personal risk or without suitable training. Contact supplier immediately for specialist advice. Move containers from fire area if this can be done without risk. Use water spray to keep fire-exposed containers cool. If involved in fire, shut off flow immediately if it can be done without risk. If this is impossible, withdraw from area and allow fire to burn. Fight fire from protected location or maximum possible distance. Eliminate all ignition sources if safe to do so.

Special protective equipment for fire-fighters : Fire-fighters should wear appropriate protective equipment and self-contained breathing apparatus (SCBA) with a full face-piece operated in positive pressure mode.

Section 6. Accidental release measures

Personal precautions, protective equipment and emergency procedures

For non-emergency personnel : Accidental releases pose a serious fire or explosion hazard. No action shall be taken involving any personal risk or without suitable training. Evacuate surrounding areas. Keep unnecessary and unprotected personnel from entering. Shut off all ignition sources. No flares, smoking or flames in hazard area. Avoid breathing gas. Provide adequate ventilation. Wear appropriate respirator when ventilation is inadequate. Put on appropriate personal protective equipment.

For emergency responders : If specialized clothing is required to deal with the spillage, take note of any information in Section 8 on suitable and unsuitable materials. See also the information in "For non-emergency personnel".

Environmental precautions : Ensure emergency procedures to deal with accidental gas releases are in place to avoid contamination of the environment. Inform the relevant authorities if the product has caused environmental pollution (sewers, waterways, soil or air).

Methods and materials for containment and cleaning up

Small spill : Immediately contact emergency personnel. Stop leak if without risk. Use spark-proof tools and explosion-proof equipment.

Large spill : Immediately contact emergency personnel. Stop leak if without risk. Use spark-proof tools and explosion-proof equipment. Note: see Section 1 for emergency contact information and Section 13 for waste disposal.

Section 7. Handling and storage

Precautions for safe handling

Protective measures : Put on appropriate personal protective equipment (see Section 8). Contains gas under pressure. Avoid breathing gas. Use only with adequate ventilation. Wear appropriate respirator when ventilation is inadequate. Do not enter storage areas and confined spaces unless adequately ventilated. Do not puncture or incinerate container. Use equipment rated for cylinder pressure. Close valve after each use and when empty. Protect cylinders from physical damage; do not drag, roll, slide, or drop. Use a suitable hand truck for cylinder movement.

Use only non-sparking tools. Avoid contact with eyes, skin and clothing. Empty containers retain product residue and can be hazardous. Store and use away from heat, sparks, open flame or any other ignition source. Use explosion-proof electrical (ventilating, lighting and material handling) equipment.

Advice on general occupational hygiene : Eating, drinking and smoking should be prohibited in areas where this material is handled, stored and processed. Workers should wash hands and face before eating, drinking and smoking. Remove contaminated clothing and protective equipment before entering eating areas. See also Section 8 for additional information on hygiene measures.

Conditions for safe storage, including any incompatibilities : Store in accordance with local regulations. Store in a segregated and approved area. Store away from direct sunlight in a dry, cool and well-ventilated area, away from incompatible materials (see Section 10). Eliminate all ignition sources. Cylinders should be stored upright, with valve protection cap in place, and firmly secured to prevent falling or being knocked over. Cylinder temperatures should not exceed 52 °C (125 °F). Keep container tightly closed and sealed until ready for use. See Section 10 for incompatible materials before handling or use.

Section 8. Exposure controls/personal protection

Control parameters

Occupational exposure limits

Ingredient name	Exposure limits
methane	None.

Appropriate engineering controls : Use only with adequate ventilation. Use process enclosures, local exhaust ventilation or other engineering controls to keep worker exposure to airborne contaminants below any recommended or statutory limits. The engineering controls also need to keep gas, vapor or dust concentrations below any lower explosive limits. Use explosion-proof ventilation equipment.

Environmental exposure controls : Emissions from ventilation or work process equipment should be checked to ensure they comply with the requirements of environmental protection legislation. In some cases, fume scrubbers, filters or engineering modifications to the process equipment will be necessary to reduce emissions to acceptable levels.

Individual protection measures

Hygiene measures : Wash hands, forearms and face thoroughly after handling chemical products, before eating, smoking and using the lavatory and at the end of the working period. Appropriate techniques should be used to remove potentially contaminated clothing. Wash contaminated clothing before reusing. Ensure that eyewash stations and safety showers are close to the workstation location.

Eye/face protection : Safety eyewear complying with an approved standard should be used when a risk assessment indicates this is necessary to avoid exposure to liquid splashes, mists, gases or dusts. If contact is possible, the following protection should be worn, unless the assessment indicates a higher degree of protection: safety glasses with side-shields.

Skin protection

Section 8. Exposure controls/personal protection

Hand protection : Chemical-resistant, impervious gloves complying with an approved standard should be worn at all times when handling chemical products if a risk assessment indicates this is necessary. Considering the parameters specified by the glove manufacturer, check during use that the gloves are still retaining their protective properties. It should be noted that the time to breakthrough for any glove material may be different for different glove manufacturers. In the case of mixtures, consisting of several substances, the protection time of the gloves cannot be accurately estimated.

Body protection : Personal protective equipment for the body should be selected based on the task being performed and the risks involved and should be approved by a specialist before handling this product. When there is a risk of ignition from static electricity, wear anti-static protective clothing. For the greatest protection from static discharges, clothing should include anti-static overalls, boots and gloves.

Other skin protection : Appropriate footwear and any additional skin protection measures should be selected based on the task being performed and the risks involved and should be approved by a specialist before handling this product.

Respiratory protection : Based on the hazard and potential for exposure, select a respirator that meets the appropriate standard or certification. Respirators must be used according to a respiratory protection program to ensure proper fitting, training, and other important aspects of use. Respirator selection must be based on known or anticipated exposure levels, the hazards of the product and the safe working limits of the selected respirator.

Section 9. Physical and chemical properties

Appearance

Physical state : Gas. [Compressed gas.]

Color : Colorless.

Odor : Odorless.

Odor threshold : Not available.

pH : Not available.

Melting point : -187.6°C (-305.7°F)

Boiling point : -161.48°C (-258.7°F)

Critical temperature : -82.45°C (-116.4°F)

Flash point : Closed cup: -104°C (-155.2°F)

Evaporation rate : Not available.

Flammability (solid, gas) : Extremely flammable in the presence of the following materials or conditions: open flames, sparks and static discharge and oxidizing materials.

Lower and upper explosive (flammable) limits : Lower: 5%
Upper: 14%

Vapor pressure : Not available.

Vapor density : 0.6 (Air = 1)

Specific Volume (ft ^{3}/lb) : 23.6407

Gas Density (lb/ft ^{3}) : 0.0423 (25°C / 77 to °F)

Relative density : Not applicable.

Solubility : Not available.

Solubility in water : 0.02 g/l

Partition coefficient: n-octanol/water : 1.09

Auto-ignition temperature : 537°C (998.6°F)

Decomposition temperature : Not available.

Viscosity : Not applicable.

Flow time (ISO 2431) : Not available.

Molecular weight : 16.05 g/mole

Aerosol product

Heat of combustion : -50048542 J/kg

Section 10. Stability and reactivity

Reactivity : No specific test data related to reactivity available for this product or its ingredients.

Chemical stability : The product is stable.

Possibility of hazardous reactions : Under normal conditions of storage and use, hazardous reactions will not occur.

Conditions to avoid : Avoid all possible sources of ignition (spark or flame). Do not pressurize, cut, weld, braze, solder, drill, grind or expose containers to heat or sources of ignition.

Incompatible materials : Oxidizers

Hazardous decomposition products : Under normal conditions of storage and use, hazardous decomposition products should not be produced.

Hazardous polymerization : Under normal conditions of storage and use, hazardous polymerization will not occur.

Section 11. Toxicological information

Information on toxicological effects

Acute toxicity

Not available.

Irritation/Corrosion

Not available.

Sensitization

Not available.

Mutagenicity

Not available.

Carcinogenicity

Not available.

Reproductive toxicity

Not available.

Teratogenicity

Not available.

Specific target organ toxicity (single exposure)

Not available.

Specific target organ toxicity (repeated exposure)

Not available.

Aspiration hazard

Not available.

Information on the likely routes of exposure : Not available.

Potential acute health effects

Eye contact : Contact with rapidly expanding gas may cause burns or frostbite.

Inhalation : No known significant effects or critical hazards.

Section 11. Toxicological information

Skin contact : Contact with rapidly expanding gas may cause burns or frostbite.

Ingestion : As this product is a gas, refer to the inhalation section.

Symptoms related to the physical, chemical and toxicological characteristics

Eye contact : No specific data.

Inhalation : No specific data.

Skin contact : No specific data.

Ingestion : No specific data.

Delayed and immediate effects and also chronic effects from short and long term exposure

Short term exposure

Potential immediate effects : Not available.

Potential delayed effects : Not available.

Long term exposure

Potential immediate effects : Not available.

Potential delayed effects : Not available.

Potential chronic health effects

Not available.

General : No known significant effects or critical hazards.

Carcinogenicity : No known significant effects or critical hazards.

Mutagenicity : No known significant effects or critical hazards.

Teratogenicity : No known significant effects or critical hazards.

Developmental effects : No known significant effects or critical hazards.

Fertility effects : No known significant effects or critical hazards.

Numerical measures of toxicity

Acute toxicity estimates

Not available.

Section 12. Ecological information

Toxicity

Not available.

Persistence and degradability

Not available.

Bioaccumulative potential

Product/ingredient name	$LogP_{ow}$	BCF	Potential
methane	1.09	-	low

Mobility in soil

Soil/water partition coefficient (K_{OC}) : Not available.

Section 12. Ecological information

Other adverse effects : No known significant effects or critical hazards.

Section 13. Disposal considerations

Disposal methods : The generation of waste should be avoided or minimized wherever possible. Disposal of this product, solutions and any by-products should at all times comply with the requirements of environmental protection and waste disposal legislation and any regional local authority requirements. Dispose of surplus and non-recyclable products via a licensed waste disposal contractor. Waste should not be disposed of untreated to the sewer unless fully compliant with the requirements of all authorities with jurisdiction. Empty Airgas-owned pressure vessels should be returned to Airgas. Waste packaging should be recycled. Incineration or landfill should only be considered when recycling is not feasible. This material and its container must be disposed of in a safe way. Empty containers or liners may retain some product residues. Do not puncture or incinerate container.

Section 14. Transport information

	DOT	TDG	Mexico	IMDG	IATA
UN number	UN1971	UN1971	UN1971	UN1971	UN1971
UN proper shipping name	Methane, compressed	Methane, compressed or Methane or Natural gas, compressed (with high methane content)	Methane, compressed	Methane, compressed	Methane, compressed
Transport hazard class(es)	2.1	2.1	2.1	2.1	2.1
Packing group	-	-	-	-	-
Environmental hazards	No.	No.	No.	No.	No.

"Refer to CFR 49 (or authority having jurisdiction) to determine the information required for shipment of the product."

Additional information

TDG Classification : Product classified as per the following sections of the Transportation of Dangerous Goods Regulations: 2.13-2.17 (Class 2).
Explosive Limit and Limited Quantity Index 0.125
ERAP Index 3000
Passenger Carrying Ship Index Forbidden
Passenger Carrying Road or Rail Index Forbidden

IATA : **Quantity limitation** Passenger and Cargo Aircraft: Forbidden. Cargo Aircraft Only: 150 kg.

Special precautions for user : **Transport within user's premises:** always transport in closed containers that are upright and secure. Ensure that persons transporting the product know what to do in the event of an accident or spillage.

Transport in bulk according to Annex II of MARPOL and the IBC Code : Not available.

Section 15. Regulatory information

U.S. Federal regulations : **TSCA 8(a) CDR Exempt/Partial exemption**: Not determined

Clean Air Act (CAA) 112 regulated flammable substances: methane

Clean Air Act Section 112 (b) Hazardous Air Pollutants (HAPs) : Not listed

Clean Air Act Section 602 Class I Substances : Not listed

Clean Air Act Section 602 Class II Substances : Not listed

DEA List I Chemicals (Precursor Chemicals) : Not listed

DEA List II Chemicals (Essential Chemicals) : Not listed

SARA 302/304

Composition/information on ingredients

No products were found.

SARA 304 RQ : Not applicable.

SARA 311/312

Classification : Refer to Section 2: Hazards Identification of this SDS for classification of substance.

State regulations

Massachusetts : This material is listed.

New York : This material is not listed.

New Jersey : This material is listed.

Pennsylvania : This material is listed.

International regulations

Chemical Weapon Convention List Schedules I, II & III Chemicals

Not listed.

Montreal Protocol (Annexes A, B, C, E)

Not listed.

Stockholm Convention on Persistent Organic Pollutants

Not listed.

Rotterdam Convention on Prior Informed Consent (PIC)

Not listed.

UNECE Aarhus Protocol on POPs and Heavy Metals

Not listed.

Inventory list

Australia : This material is listed or exempted.

Canada : This material is listed or exempted.

China : This material is listed or exempted.

Europe : This material is listed or exempted.

Japan : **Japan inventory (ENCS)**: This material is listed or exempted.
Japan inventory (ISHL): Not determined.

Malaysia : This material is listed or exempted.

New Zealand : This material is listed or exempted.

Philippines : This material is listed or exempted.

Republic of Korea : This material is listed or exempted.

Section 15. Regulatory information

Taiwan : This material is listed or exempted.

Thailand : Not determined.

Turkey : This material is listed or exempted.

United States : This material is listed or exempted.

Viet Nam : Not determined.

Section 16. Other information

Hazardous Material Information System (U.S.A.)



Caution: HMIS® ratings are based on a 0-4 rating scale, with 0 representing minimal hazards or risks, and 4 representing significant hazards or risks. Although HMIS® ratings and the associated label are not required on SDSs or products leaving a facility under 29 CFR 1910.1200, the preparer may choose to provide them. HMIS® ratings are to be used with a fully implemented HMIS® program. HMIS® is a registered trademark and service mark of the American Coatings Association, Inc.

The customer is responsible for determining the PPE code for this material. For more information on HMIS® Personal Protective Equipment (PPE) codes, consult the HMIS® Implementation Manual.

National Fire Protection Association (U.S.A.)

Reprinted with permission from NFPA 704-2001, Identification of the Hazards of Materials for Emergency Response Copyright ©1997, National Fire Protection Association, Quincy, MA 02269. This reprinted material is not the complete and official position of the National Fire Protection Association, on the referenced subject which is represented only by the standard in its entirety.

Copyright ©2001, National Fire Protection Association, Quincy, MA 02269. This warning system is intended to be interpreted and applied only by properly trained individuals to identify fire, health and reactivity hazards of chemicals. The user is referred to certain limited number of chemicals with recommended classifications in NFPA 49 and NFPA 325, which would be used as a guideline only. Whether the chemicals are classified by NFPA or not, anyone using the 704 systems to classify chemicals does so at their own risk.

Procedure used to derive the classification

Classification	Justification
FLAMMABLE GASES - Category 1 GASES UNDER PRESSURE - Compressed gas	Expert judgment According to package

History

Date of printing : 3/14/2019

Date of issue/Date of revision : 3/14/2019

Date of previous issue : 3/14/2019

Version : 1.07

Key to abbreviations : ATE = Acute Toxicity Estimate
BCF = Bioconcentration Factor
GHS = Globally Harmonized System of Classification and Labelling of Chemicals
IATA = International Air Transport Association
IBC = Intermediate Bulk Container
IMDG = International Maritime Dangerous Goods
LogPow = logarithm of the octanol/water partition coefficient
MARPOL = International Convention for the Prevention of Pollution From Ships, 1973

Section 16. Other information

as modified by the Protocol of 1978. ("Marpol" = marine pollution)
UN = United Nations

References : Not available.

Notice to reader

To the best of our knowledge, the information contained herein is accurate. However, neither the above-named supplier, nor any of its subsidiaries, assumes any liability whatsoever for the accuracy or completeness of the information contained herein.
Final determination of suitability of any material is the sole responsibility of the user. All materials may present unknown hazards and should be used with caution. Although certain hazards are described herein, we cannot guarantee that these are the only hazards that exist.

SAFETY DATA SHEET

Creation Date 02-Jun-2010 **Revision Date** 18-Jan-2018 **Revision Number** 3

1. Identification

Product Name **Zinc Metal Powder**

Cat No. : **Z5-500; Z46-3**

CAS-No 7440-66-6
Synonyms Zinc Dust (Certified/Technical)

Recommended Use Laboratory chemicals.
Uses advised against Not for food, drug, pesticide or biocidal product use

Details of the supplier of the safety data sheet

Company
Fisher Scientific
One Reagent Lane
Fair Lawn, NJ 07410
Tel: (201) 796-7100

Emergency Telephone Number
CHEMTREC®, Inside the USA: 800-424-9300
CHEMTREC®, Outside the USA: 001-703-527-3887

2. Hazard(s) identification

Classification
This chemical is considered hazardous by the 2012 OSHA Hazard Communication Standard (29 CFR 1910.1200)

Substances/mixtures which, in contact with water, emit flammable gases	Category 1
Pyrophoric solids	Category 1
Combustible dust	Yes

Label Elements

Signal Word
Danger

Hazard Statements
May form combustible dust concentrations in air
In contact with water releases flammable gases which may ignite spontaneously
Catches fire spontaneously if exposed to air

Precautionary Statements
Prevention
Keep away from heat/sparks/open flames/hot surfaces. - No smoking
Do not allow contact with air
Wear protective gloves/protective clothing/eye protection/face protection
Keep away from any possible contact with water, because of violent reaction and possible flash fire
Handle under inert gas. Protect from moisture
Skin
Brush off loose particles from skin. Immerse in cool water/wrap with wet bandages
Fire
In case of fire: Use CO2, dry chemical, or foam for extinction
Storage
Store under an inert atmosphere
Store in a dry place. Store in a closed container
Store in a well-ventilated place. Keep container tightly closed
Disposal
Dispose of contents/container to an approved waste disposal plant
Hazards not otherwise classified (HNOC)
Very toxic to aquatic life with long lasting effects

3. Composition/Information on Ingredients

Component	CAS-No	Weight %
Zinc powder - zinc dust (pyrophoric)	7440-66-6	100

4. First-aid measures

Eye Contact Rinse immediately with plenty of water, also under the eyelids, for at least 15 minutes. Get medical attention.

Skin Contact Wash off immediately with plenty of water for at least 15 minutes. Get medical attention if symptoms occur.

Inhalation Move to fresh air. If breathing is difficult, give oxygen. Get medical attention if symptoms occur.

Ingestion Do not induce vomiting. Obtain medical attention.

Most important symptoms and effects No information available.

Notes to Physician Treat symptomatically

5. Fire-fighting measures

Suitable Extinguishing Media Dry sand, clay, approved class D extinguishers.

Unsuitable Extinguishing Media DO NOT USE WATER, Carbon dioxide (CO2), Dry chemical, Foam

Flash Point No information available

Method - No information available

Autoignition Temperature 460 °C / 860 °F

Explosion Limits

Upper	No data available
Lower	No data available
Sensitivity to Mechanical Impact	No information available
Sensitivity to Static Discharge	No information available

Specific Hazards Arising from the Chemical
Flammable. Fine dust dispersed in air may ignite. Pyrophoric: Spontaneously flammable in air. Water reactive. Contact with water liberates extremely flammable gases. Thermal decomposition can lead to release of irritating gases and vapors. Keep product and empty container away from heat and sources of ignition.

Hazardous Combustion Products
Hydrogen
Protective Equipment and Precautions for Firefighters
As in any fire, wear self-contained breathing apparatus pressure-demand, MSHA/NIOSH (approved or equivalent) and full protective gear.

NFPA

Health	Flammability	Instability	Physical hazards
1	4	3	W

6. Accidental release measures

Personal Precautions Use personal protective equipment. Remove all sources of ignition. Avoid dust formation. Take precautionary measures against static discharges. Do not get in eyes, on skin, or on clothing.

Environmental Precautions Should not be released into the environment. See Section 12 for additional ecological information.

Methods for Containment and Clean Up Remove all sources of ignition. Do not expose spill to water. Sweep up or vacuum up spillage and collect in suitable container for disposal. Use spark-proof tools and explosion-proof equipment. Avoid dust formation.

7. Handling and storage

Handling Use only under a chemical fume hood. Wear personal protective equipment. Avoid dust formation. Avoid contact with skin, eyes and clothing. Avoid ingestion and inhalation. Handle under an inert atmosphere. Do not allow contact with air. Do not allow contact with water. Keep away from open flames, hot surfaces and sources of ignition. Use spark-proof tools and explosion-proof equipment. Take precautionary measures against static discharges.

Storage Keep containers tightly closed in a dry, cool and well-ventilated place. Store under an inert atmosphere. Keep away from heat and sources of ignition. Keep away from water.

8. Exposure controls / personal protection

Exposure Guidelines This product does not contain any hazardous materials with occupational exposure limitsestablished by the region specific regulatory bodies.

Engineering Measures Use only under a chemical fume hood. Use explosion-proof electrical/ventilating/lighting/equipment. Ensure that eyewash stations and safety showers are close to the workstation location.

Personal Protective Equipment

Eye/face Protection	Wear appropriate protective eyeglasses or chemical safety goggles as described by OSHA's eye and face protection regulations in 29 CFR 1910.133 or European Standard EN166.
Skin and body protection	Wear appropriate protective gloves and clothing to prevent skin exposure.
Respiratory Protection	Follow the OSHA respirator regulations found in 29 CFR 1910.134 or European Standard EN 149. Use a NIOSH/MSHA or European Standard EN 149 approved respirator if exposure limits are exceeded or if irritation or other symptoms are experienced.
Hygiene Measures	Handle in accordance with good industrial hygiene and safety practice.

9. Physical and chemical properties

Physical State	Solid
Appearance	Light blue
Odor	Odorless
Odor Threshold	No information available
pH	No information available
Melting Point/Range	419 °C / 786.2 °F
Boiling Point/Range	908 °C / 1666.4 °F
Flash Point	No information available
Evaporation Rate	No information available
Flammability (solid,gas)	No information available
Flammability or explosive limits	
Upper	No data available
Lower	No data available
Vapor Pressure	1 mmHg @ 487 °C
Vapor Density	No information available
Specific Gravity	7.14
Solubility	Insoluble in water
Partition coefficient; n-octanol/water	No data available
Autoignition Temperature	460 °C / 860 °F
Decomposition Temperature	No information available
Viscosity	No information available
Molecular Formula	Zn
Molecular Weight	65.37

10. Stability and reactivity

Reactive Hazard	Yes
Stability	Water reactive. Moisture sensitive. Air sensitive. Pyrophoric: Spontaneously flammable in air.
Conditions to Avoid	Avoid dust formation. Incompatible products. Exposure to air. Exposure to moist air or water. Keep away from open flames, hot surfaces and sources of ignition.
Incompatible Materials	Strong oxidizing agents, Strong acids, Strong bases, Amines
Hazardous Decomposition Products	Hydrogen
Hazardous Polymerization	Hazardous polymerization does not occur.
Hazardous Reactions	Contact with water liberates extremely flammable gases. Pyrophoric: Spontaneously flammable in air.

11. Toxicological information

Acute Toxicity

Product Information No acute toxicity information is available for this product

Component Information

Component	LD50 Oral	LD50 Dermal	LC50 Inhalation
Zinc powder - zinc dust (pyrophoric)	LD50 = 630 mg/kg (Rat)	Not listed	Not listed

Toxicologically Synergistic Products No information available

Delayed and immediate effects as well as chronic effects from short and long-term exposure

Irritation No information available

Sensitization No information available

Carcinogenicity The table below indicates whether each agency has listed any ingredient as a carcinogen.

Component	CAS-No	IARC	NTP	ACGIH	OSHA	Mexico
Zinc powder - zinc dust (pyrophoric)	7440-66-6	Not listed	Not listed	Not listed	Not listed	Not listed

Mutagenic Effects No information available

Reproductive Effects No information available.

Developmental Effects No information available.

Teratogenicity No information available.

STOT - single exposure None known

STOT - repeated exposure None known

Aspiration hazard No information available

Symptoms / effects,both acute and delayed No information available

Endocrine Disruptor Information No information available

Other Adverse Effects Tumorigenic effects have been reported in experimental animals. See actual entry in RTECS for complete information.

12. Ecological information

Ecotoxicity

This product contains the following substance(s) which are hazardous for the environment.

Component	Freshwater Algae	Freshwater Fish	Microtox	Water Flea
Zinc powder - zinc dust (pyrophoric)	EC50: 0.09 - 0.125 mg/L, 72h static (Pseudokirchneriella subcapitata) EC50: 0.11 - 0.271 mg/L, 96h static (Pseudokirchneriella subcapitata)	LC50: 0.211 - 0.269 mg/L, 96h semi-static (Pimephales promelas) LC50: = 2.66 mg/L, 96h static (Pimephales promelas) LC50: = 30 mg/L, 96h (Cyprinus carpio) LC50: = 0.45 mg/L, 96h semi-static (Cyprinus carpio) LC50: = 7.8 mg/L, 96h static (Cyprinus carpio) LC50: = 3.5 mg/L, 96h static (Lepomis macrochirus) LC50: = 0.24 mg/L, 96h flow-through (Oncorhynchus mykiss)	Not listed	EC50: 0.139 - 0.908 mg/L, 48h Static (Daphnia magna)

		LC50: = 0.59 mg/L, 96h semi-static (Oncorhynchus mykiss) LC50: 2.16 - 3.05 mg/L, 96h flow-through (Pimephales promelas) LC50: = 0.41 mg/L, 96h static (Oncorhynchus mykiss)		

Persistence and Degradability No information available

Bioaccumulation/ Accumulation No information available.

Mobility No information available.

13. Disposal considerations

Waste Disposal Methods Chemical waste generators must determine whether a discarded chemical is classified as a hazardous waste. Chemical waste generators must also consult local, regional, and national hazardous waste regulations to ensure complete and accurate classification.

14. Transport information

DOT

UN-No	UN1436
Proper Shipping Name	ZINC POWDER
Hazard Class	4.3
Subsidiary Hazard Class	4.2
Packing Group	II

TDG

UN-No	UN1436
Proper Shipping Name	ZINC POWDER
Hazard Class	4.3
Subsidiary Hazard Class	4.2
Packing Group	II

IATA

UN-No	UN1436
Proper Shipping Name	ZINC POWDER
Hazard Class	4.3
Subsidiary Hazard Class	4.2
Packing Group	II

IMDG/IMO

UN-No	UN1436
Proper Shipping Name	ZINC POWDER
Hazard Class	4.3
Subsidiary Hazard Class	4.2
Packing Group	II

15. Regulatory information

International Inventories

Component	TSCA	DSL	NDSL	EINECS	ELINCS	NLP	PICCS	ENCS	AICS	IECSC	KECL
Zinc powder - zinc dust (pyrophoric)	X	X	-	231-175-3	-		X	-	X	X	X

Legend:
X - Listed
E - Indicates a substance that is the subject of a Section 5(e) Consent order under TSCA.
F - Indicates a substance that is the subject of a Section 5(f) Rule under TSCA.
N - Indicates a polymeric substance containing no free-radical initiator in its inventory name but is considered to cover the designated polymer made with any free-radical initiator regardless of the amount used.
P - Indicates a commenced PMN substance

R - Indicates a substance that is the subject of a Section 6 risk management rule under TSCA.
S - Indicates a substance that is identified in a proposed or final Significant New Use Rule
T - Indicates a substance that is the subject of a Section 4 test rule under TSCA.
XU - Indicates a substance exempt from reporting under the Inventory Update Rule, i.e. Partial Updating of the TSCA Inventory Data Base Production and Site Reports (40 CFR 710(B).
Y1 - Indicates an exempt polymer that has a number-average molecular weight of 1,000 or greater.
Y2 - Indicates an exempt polymer that is a polyester and is made only from reactants included in a specified list of low concern reactants that comprises one of the eligibility criteria for the exemption rule.

U.S. Federal Regulations

TSCA 12(b) Not applicable

SARA 313

Component	CAS-No	Weight %	SARA 313 - Threshold Values %
Zinc powder - zinc dust (pyrophoric)	7440-66-6	100	1.0

SARA 311/312 Hazard Categories See section 2 for more information

CWA (Clean Water Act)

Component	CWA - Hazardous Substances	CWA - Reportable Quantities	CWA - Toxic Pollutants	CWA - Priority Pollutants
Zinc powder - zinc dust (pyrophoric)	-	-	X	X

Clean Air Act Not applicable

OSHA Occupational Safety and Health Administration
Not applicable

CERCLA This material, as supplied, contains one or more substances regulated as a hazardous substance under the Comprehensive Environmental Response Compensation and Liability Act (CERCLA) (40 CFR 302)

Component	Hazardous Substances RQs	CERCLA EHS RQs
Zinc powder - zinc dust (pyrophoric)	1000 lb	-

California Proposition 65 This product does not contain any Proposition 65 chemicals

U.S. State Right-to-Know Regulations

Component	Massachusetts	New Jersey	Pennsylvania	Illinois	Rhode Island
Zinc powder - zinc dust (pyrophoric)	X	X	X	-	X

U.S. Department of Transportation

Reportable Quantity (RQ): N
DOT Marine Pollutant N
DOT Severe Marine Pollutant N

U.S. Department of Homeland Security
This product does not contain any DHS chemicals.

Other International Regulations

Mexico - Grade No information available

16. Other information

Prepared By Regulatory Affairs
Thermo Fisher Scientific

Email: EMSDS.RA@thermofisher.com

Creation Date	02-Jun-2010
Revision Date	18-Jan-2018
Print Date	18-Jan-2018
Revision Summary	This document has been updated to comply with the US OSHA HazCom 2012 Standard replacing the current legislation under 29 CFR 1910.1200 to align with the Globally Harmonized System of Classification and Labeling of Chemicals (GHS).

Disclaimer

The information provided in this Safety Data Sheet is correct to the best of our knowledge, information and belief at the date of its publication. The information given is designed only as a guidance for safe handling, use, processing, storage, transportation, disposal and release and is not to be considered a warranty or quality specification. The information relates only to the specific material designated and may not be valid for such material used in combination with any other materials or in any process, unless specified in the text

End of SDS

SAFETY DATA SHEET

Creation Date 24-Nov-2010 **Revision Date** 19-Jan-2018 **Revision Number** 3

1. Identification

Product Name **Manganese, powder, -325 mesh**

Cat No. : **AC317440000; AC317440010; AC317442500**

CAS-No 7439-96-5
Synonyms No information available

Recommended Use Laboratory chemicals.
Uses advised against Not for food, drug, pesticide or biocidal product use

Details of the supplier of the safety data sheet

Company
Fisher Scientific
One Reagent Lane
Fair Lawn, NJ 07410
Tel: (201) 796-7100

Acros Organics
One Reagent Lane
Fair Lawn, NJ 07410

Emergency Telephone Number
For information **US** call: 001-800-ACROS-01 / **Europe** call: +32 14 57 52 11
Emergency Number **US:**001-201-796-7100 / **Europe:** +32 14 57 52 99
CHEMTREC Tel. No.**US:**001-800-424-9300 / **Europe:**001-703-527-3887

2. Hazard(s) identification

Classification
This chemical is considered hazardous by the 2012 OSHA Hazard Communication Standard (29 CFR 1910.1200)

Flammable solids	Category 2
Serious Eye Damage/Eye Irritation	Category 2

Label Elements

Signal Word
Warning

Hazard Statements
Flammable solid
Causes serious eye irritation

Precautionary Statements
Prevention
Wash face, hands and any exposed skin thoroughly after handling
Keep away from heat/sparks/open flames/hot surfaces. - No smoking
Ground/bond container and receiving equipment
Use explosion-proof electrical/ventilating/lighting/equipment
Wear protective gloves/protective clothing/eye protection/face protection
Eyes
IF IN EYES: Rinse cautiously with water for several minutes. Remove contact lenses, if present and easy to do. Continue rinsing
If eye irritation persists: Get medical advice/attention
Fire
In case of fire: Use CO2, dry chemical, or foam for extinction
Hazards not otherwise classified (HNOC)
None identified

3. Composition/Information on Ingredients

Component	CAS-No	Weight %
Manganese	7439-96-5	>95

4. First-aid measures

Eye Contact Rinse immediately with plenty of water, also under the eyelids, for at least 15 minutes. Get medical attention.

Skin Contact Wash off immediately with soap and plenty of water while removing all contaminated clothes and shoes. Obtain medical attention.

Inhalation Remove from exposure, lie down. Move to fresh air. If breathing is difficult, give oxygen. If not breathing, give artificial respiration. Obtain medical attention.

Ingestion Clean mouth with water. Get medical attention.

Most important symptoms and effects No information available.

Notes to Physician Treat symptomatically

5. Fire-fighting measures

Suitable Extinguishing Media Dry chemical.

Unsuitable Extinguishing Media No information available

Flash Point No information available
Method - No information available

Autoignition Temperature
Explosion Limits
Upper No data available
Lower No data available
Sensitivity to Mechanical Impact No information available
Sensitivity to Static Discharge No information available

Specific Hazards Arising from the Chemical
Combustible material.

Hazardous Combustion Products
None known

Protective Equipment and Precautions for Firefighters
As in any fire, wear self-contained breathing apparatus pressure-demand, MSHA/NIOSH (approved or equivalent) and full protective gear.

NFPA

Health	Flammability	Instability	Physical hazards
2	2	0	N/A

6. Accidental release measures

Personal Precautions Ensure adequate ventilation. Use personal protective equipment.
Environmental Precautions See Section 12 for additional ecological information.

Methods for Containment and Clean Up Remove all sources of ignition. Use spark-proof tools and explosion-proof equipment. Sweep up or vacuum up spillage and collect in suitable container for disposal.

7. Handling and storage

Handling Avoid contact with skin and eyes. Do not breathe dust. Use explosion-proof equipment. Use only non-sparking tools.

Storage Keep in a dry, cool and well-ventilated place. Keep container tightly closed. Keep away from heat and sources of ignition. Keep under nitrogen.

8. Exposure controls / personal protection

Exposure Guidelines

Component	ACGIH TLV	OSHA PEL	NIOSH IDLH	Mexico OEL (TWA)
Manganese	TWA: 0.02 mg/m³ TWA: 0.1 mg/m³	(Vacated) TWA: 1 mg/m³ Ceiling: 5 mg/m³ (Vacated) STEL: 3 mg/m³ (Vacated) Ceiling: 5 mg/m³	IDLH: 500 mg/m³ TWA: 1 mg/m³ STEL: 3 mg/m³	TWA: 0.2 mg/m³ TWA: 1 mg/m³ STEL: 3 mg/m³

Legend

ACGIH - American Conference of Governmental Industrial Hygienists
OSHA - Occupational Safety and Health Administration
NIOSH IDLH: The National Institute for Occupational Safety and Health Immediately Dangerous to Life or Health

Engineering Measures Ensure adequate ventilation, especially in confined areas.

Personal Protective Equipment

Eye/face Protection Wear appropriate protective eyeglasses or chemical safety goggles as described by OSHA's eye and face protection regulations in 29 CFR 1910.133 or European Standard EN166.

Skin and body protection Wear appropriate protective gloves and clothing to prevent skin exposure.

Respiratory Protection No protective equipment is needed under normal use conditions.

Hygiene Measures Handle in accordance with good industrial hygiene and safety practice.

9. Physical and chemical properties

Physical State	Powder Solid
Appearance	Dark brown
Odor	No information available
Odor Threshold	No information available
pH	No information available

Melting Point/Range	1260 °C / 2300 °F
Boiling Point/Range	1900 °C / 3452 °F
Flash Point	No information available
Evaporation Rate	Not applicable
Flammability (solid,gas)	No information available
Flammability or explosive limits	
Upper	No data available
Lower	No data available
Vapor Pressure	No information available
Vapor Density	Not applicable
Specific Gravity	No information available
Solubility	No information available
Partition coefficient; n-octanol/water	No data available
Autoignition Temperature	
Decomposition Temperature	No information available
Viscosity	Not applicable
Molecular Formula	Mn
Molecular Weight	54.94

10. Stability and reactivity

Reactive Hazard None known, based on information available

Stability Moisture sensitive.

Conditions to Avoid Incompatible products. Exposure to moisture.

Incompatible Materials Acids, Bases, Halogens

Hazardous Decomposition Products None under normal use conditions

Hazardous Polymerization Hazardous polymerization does not occur.

Hazardous Reactions None under normal processing.

11. Toxicological information

Acute Toxicity

Product Information

Component Information

Component	LD50 Oral	LD50 Dermal	LC50 Inhalation
Manganese	LD50 = 9 g/kg (Rat)	Not listed	Not listed

Toxicologically Synergistic Products No information available

Delayed and immediate effects as well as chronic effects from short and long-term exposure

Irritation No information available

Sensitization No information available

Carcinogenicity The table below indicates whether each agency has listed any ingredient as a carcinogen.

Component	CAS-No	IARC	NTP	ACGIH	OSHA	Mexico
Manganese	7439-96-5	Not listed	Not listed	Not listed	Not listed	Not listed

Mutagenic Effects No information available

Reproductive Effects No information available.

Developmental Effects No information available.

Teratogenicity No information available.

STOT - single exposure None known
STOT - repeated exposure None known

Aspiration hazard No information available

Symptoms / effects,both acute and delayed No information available

Endocrine Disruptor Information No information available

Other Adverse Effects The toxicological properties have not been fully investigated. See actual entry in RTECS for complete information.

12. Ecological information

Ecotoxicity
Do not empty into drains.

Persistence and Degradability Insoluble in water

Bioaccumulation/ Accumulation No information available.

Mobility Is not likely mobile in the environment due its low water solubility.

13. Disposal considerations

Waste Disposal Methods Chemical waste generators must determine whether a discarded chemical is classified as a hazardous waste. Chemical waste generators must also consult local, regional, and national hazardous waste regulations to ensure complete and accurate classification.

14. Transport information

DOT
- **UN-No** UN3089
- **Hazard Class** 4.1
- **Packing Group** III

TDG
- **UN-No** UN3089
- **Hazard Class** 4.1
- **Packing Group** III

IATA
- **UN-No** 3089
- **Proper Shipping Name** METAL POWDER, FLAMMABLE, N.O.S.
- **Hazard Class** 4.1
- **Packing Group** III

IMDG/IMO
- **UN-No** 3089
- **Proper Shipping Name** METAL POWDER, FLAMMABLE, N.O.S.
- **Hazard Class** 4.1
- **Packing Group** III

15. Regulatory information

International Inventories

Component	TSCA	DSL	NDSL	EINECS	ELINCS	NLP	PICCS	ENCS	AICS	IECSC	KECL
Manganese	X	X	-	231-105-1	-		X	-	X	X	X

Legend:
X - Listed

E - Indicates a substance that is the subject of a Section 5(e) Consent order under TSCA.
F - Indicates a substance that is the subject of a Section 5(f) Rule under TSCA.
N - Indicates a polymeric substance containing no free-radical initiator in its inventory name but is considered to cover the designated polymer made with any free-radical initiator regardless of the amount used.
P - Indicates a commenced PMN substance
R - Indicates a substance that is the subject of a Section 6 risk management rule under TSCA.
S - Indicates a substance that is identified in a proposed or final Significant New Use Rule
T - Indicates a substance that is the subject of a Section 4 test rule under TSCA.
XU - Indicates a substance exempt from reporting under the Inventory Update Rule, i.e. Partial Updating of the TSCA Inventory Data Base Production and Site Reports (40 CFR 710(B).
Y1 - Indicates an exempt polymer that has a number-average molecular weight of 1,000 or greater.
Y2 - Indicates an exempt polymer that is a polyester and is made only from reactants included in a specified list of low concern reactants that comprises one of the eligibility criteria for the exemption rule.

U.S. Federal Regulations

TSCA 12(b) Not applicable

SARA 313

Component	CAS-No	Weight %	SARA 313 - Threshold Values %
Manganese	7439-96-5	>95	1.0

SARA 311/312 Hazard Categories See section 2 for more information

CWA (Clean Water Act) Not applicable

Clean Air Act

Component	HAPS Data	Class 1 Ozone Depletors	Class 2 Ozone Depletors
Manganese	X		-

OSHA Occupational Safety and Health Administration
Not applicable

CERCLA Not applicable

California Proposition 65 This product does not contain any Proposition 65 chemicals

U.S. State Right-to-Know Regulations

Component	Massachusetts	New Jersey	Pennsylvania	Illinois	Rhode Island
Manganese	X	X	X	X	X

U.S. Department of Transportation

Reportable Quantity (RQ): N
DOT Marine Pollutant N
DOT Severe Marine Pollutant N

U.S. Department of Homeland Security
This product does not contain any DHS chemicals.

Other International Regulations

Mexico - Grade No information available

16. Other information

Prepared By Regulatory Affairs
Thermo Fisher Scientific
Email: EMSDS.RA@thermofisher.com

Creation Date	24-Nov-2010
Revision Date	19-Jan-2018
Print Date	19-Jan-2018
Revision Summary	This document has been updated to comply with the US OSHA HazCom 2012 Standard replacing the current legislation under 29 CFR 1910.1200 to align with the Globally Harmonized System of Classification and Labeling of Chemicals (GHS).

Disclaimer

The information provided in this Safety Data Sheet is correct to the best of our knowledge, information and belief at the date of its publication. The information given is designed only as a guidance for safe handling, use, processing, storage, transportation, disposal and release and is not to be considered a warranty or quality specification. The information relates only to the specific material designated and may not be valid for such material used in combination with any other materials or in any process, unless specified in the text

End of SDS

SAFETY DATA SHEET

Creation Date 02-Jun-2010 **Revision Date** 18-Jan-2018 **Revision Number** 3

1. Identification

Product Name **Zinc Metal Powder**

Cat No. : **Z5-500; Z46-3**

CAS-No 7440-66-6
Synonyms Zinc Dust (Certified/Technical)

Recommended Use Laboratory chemicals.
Uses advised against Not for food, drug, pesticide or biocidal product use

Details of the supplier of the safety data sheet

Company
Fisher Scientific
One Reagent Lane
Fair Lawn, NJ 07410
Tel: (201) 796-7100

Emergency Telephone Number
CHEMTREC®, Inside the USA: 800-424-9300
CHEMTREC®, Outside the USA: 001-703-527-3887

2. Hazard(s) identification

Classification
This chemical is considered hazardous by the 2012 OSHA Hazard Communication Standard (29 CFR 1910.1200)

Substances/mixtures which, in contact with water, emit flammable gases	Category 1
Pyrophoric solids	Category 1
Combustible dust	Yes

Label Elements

Signal Word
Danger

Hazard Statements
May form combustible dust concentrations in air
In contact with water releases flammable gases which may ignite spontaneously
Catches fire spontaneously if exposed to air

Precautionary Statements
Prevention
Keep away from heat/sparks/open flames/hot surfaces. - No smoking
Do not allow contact with air
Wear protective gloves/protective clothing/eye protection/face protection
Keep away from any possible contact with water, because of violent reaction and possible flash fire
Handle under inert gas. Protect from moisture
Skin
Brush off loose particles from skin. Immerse in cool water/wrap with wet bandages
Fire
In case of fire: Use CO2, dry chemical, or foam for extinction
Storage
Store under an inert atmosphere
Store in a dry place. Store in a closed container
Store in a well-ventilated place. Keep container tightly closed
Disposal
Dispose of contents/container to an approved waste disposal plant
Hazards not otherwise classified (HNOC)
Very toxic to aquatic life with long lasting effects

3. Composition/Information on Ingredients

Component	CAS-No	Weight %
Zinc powder - zinc dust (pyrophoric)	7440-66-6	100

4. First-aid measures

Eye Contact Rinse immediately with plenty of water, also under the eyelids, for at least 15 minutes. Get medical attention.

Skin Contact Wash off immediately with plenty of water for at least 15 minutes. Get medical attention if symptoms occur.

Inhalation Move to fresh air. If breathing is difficult, give oxygen. Get medical attention if symptoms occur.

Ingestion Do not induce vomiting. Obtain medical attention.

Most important symptoms and effects No information available.

Notes to Physician Treat symptomatically

5. Fire-fighting measures

Suitable Extinguishing Media Dry sand, clay, approved class D extinguishers.

Unsuitable Extinguishing Media DO NOT USE WATER, Carbon dioxide (CO2), Dry chemical, Foam

Flash Point No information available

Method - No information available

Autoignition Temperature 460 °C / 860 °F

Explosion Limits

Upper	No data available
Lower	No data available
Sensitivity to Mechanical Impact	No information available
Sensitivity to Static Discharge	No information available

Specific Hazards Arising from the Chemical
Flammable. Fine dust dispersed in air may ignite. Pyrophoric: Spontaneously flammable in air. Water reactive. Contact with water liberates extremely flammable gases. Thermal decomposition can lead to release of irritating gases and vapors. Keep product and empty container away from heat and sources of ignition.

Hazardous Combustion Products
Hydrogen
Protective Equipment and Precautions for Firefighters
As in any fire, wear self-contained breathing apparatus pressure-demand, MSHA/NIOSH (approved or equivalent) and full protective gear.

NFPA

Health	Flammability	Instability	Physical hazards
1	4	3	W

6. Accidental release measures

Personal Precautions Use personal protective equipment. Remove all sources of ignition. Avoid dust formation. Take precautionary measures against static discharges. Do not get in eyes, on skin, or on clothing.

Environmental Precautions Should not be released into the environment. See Section 12 for additional ecological information.

Methods for Containment and Clean Up Remove all sources of ignition. Do not expose spill to water. Sweep up or vacuum up spillage and collect in suitable container for disposal. Use spark-proof tools and explosion-proof equipment. Avoid dust formation.

7. Handling and storage

Handling Use only under a chemical fume hood. Wear personal protective equipment. Avoid dust formation. Avoid contact with skin, eyes and clothing. Avoid ingestion and inhalation. Handle under an inert atmosphere. Do not allow contact with air. Do not allow contact with water. Keep away from open flames, hot surfaces and sources of ignition. Use spark-proof tools and explosion-proof equipment. Take precautionary measures against static discharges.

Storage Keep containers tightly closed in a dry, cool and well-ventilated place. Store under an inert atmosphere. Keep away from heat and sources of ignition. Keep away from water.

8. Exposure controls / personal protection

Exposure Guidelines This product does not contain any hazardous materials with occupational exposure limitsestablished by the region specific regulatory bodies.

Engineering Measures Use only under a chemical fume hood. Use explosion-proof electrical/ventilating/lighting/equipment. Ensure that eyewash stations and safety showers are close to the workstation location.

Personal Protective Equipment

Eye/face Protection	Wear appropriate protective eyeglasses or chemical safety goggles as described by OSHA's eye and face protection regulations in 29 CFR 1910.133 or European Standard EN166.
Skin and body protection	Wear appropriate protective gloves and clothing to prevent skin exposure.
Respiratory Protection	Follow the OSHA respirator regulations found in 29 CFR 1910.134 or European Standard EN 149. Use a NIOSH/MSHA or European Standard EN 149 approved respirator if exposure limits are exceeded or if irritation or other symptoms are experienced.
Hygiene Measures	Handle in accordance with good industrial hygiene and safety practice.

9. Physical and chemical properties

Physical State	Solid
Appearance	Light blue
Odor	Odorless
Odor Threshold	No information available
pH	No information available
Melting Point/Range	419 °C / 786.2 °F
Boiling Point/Range	908 °C / 1666.4 °F
Flash Point	No information available
Evaporation Rate	No information available
Flammability (solid,gas)	No information available
Flammability or explosive limits	
Upper	No data available
Lower	No data available
Vapor Pressure	1 mmHg @ 487 °C
Vapor Density	No information available
Specific Gravity	7.14
Solubility	Insoluble in water
Partition coefficient; n-octanol/water	No data available
Autoignition Temperature	460 °C / 860 °F
Decomposition Temperature	No information available
Viscosity	No information available
Molecular Formula	Zn
Molecular Weight	65.37

10. Stability and reactivity

Reactive Hazard	Yes
Stability	Water reactive. Moisture sensitive. Air sensitive. Pyrophoric: Spontaneously flammable in air.
Conditions to Avoid	Avoid dust formation. Incompatible products. Exposure to air. Exposure to moist air or water. Keep away from open flames, hot surfaces and sources of ignition.
Incompatible Materials	Strong oxidizing agents, Strong acids, Strong bases, Amines
Hazardous Decomposition Products	Hydrogen
Hazardous Polymerization	Hazardous polymerization does not occur.
Hazardous Reactions	Contact with water liberates extremely flammable gases. Pyrophoric: Spontaneously flammable in air.

11. Toxicological information

Acute Toxicity

Product Information No acute toxicity information is available for this product

Component Information

Component	LD50 Oral	LD50 Dermal	LC50 Inhalation
Zinc powder - zinc dust (pyrophoric)	LD50 = 630 mg/kg (Rat)	Not listed	Not listed

Toxicologically Synergistic Products No information available

Delayed and immediate effects as well as chronic effects from short and long-term exposure

Irritation No information available

Sensitization No information available

Carcinogenicity The table below indicates whether each agency has listed any ingredient as a carcinogen.

Component	CAS-No	IARC	NTP	ACGIH	OSHA	Mexico
Zinc powder - zinc dust (pyrophoric)	7440-66-6	Not listed	Not listed	Not listed	Not listed	Not listed

Mutagenic Effects No information available

Reproductive Effects No information available.

Developmental Effects No information available.

Teratogenicity No information available.

STOT - single exposure None known

STOT - repeated exposure None known

Aspiration hazard No information available

Symptoms / effects,both acute and delayed No information available

Endocrine Disruptor Information No information available

Other Adverse Effects Tumorigenic effects have been reported in experimental animals. See actual entry in RTECS for complete information.

12. Ecological information

Ecotoxicity

This product contains the following substance(s) which are hazardous for the environment.

Component	Freshwater Algae	Freshwater Fish	Microtox	Water Flea
Zinc powder - zinc dust (pyrophoric)	EC50: 0.09 - 0.125 mg/L, 72h static (Pseudokirchneriella subcapitata) EC50: 0.11 - 0.271 mg/L, 96h static (Pseudokirchneriella subcapitata)	LC50: 0.211 - 0.269 mg/L, 96h semi-static (Pimephales promelas) LC50: = 2.66 mg/L, 96h static (Pimephales promelas) LC50: = 30 mg/L, 96h (Cyprinus carpio) LC50: = 0.45 mg/L, 96h semi-static (Cyprinus carpio) LC50: = 7.8 mg/L, 96h static (Cyprinus carpio) LC50: = 3.5 mg/L, 96h static (Lepomis macrochirus) LC50: = 0.24 mg/L, 96h flow-through (Oncorhynchus mykiss)	Not listed	EC50: 0.139 - 0.908 mg/L, 48h Static (Daphnia magna)

		LC50: = 0.59 mg/L, 96h semi-static (Oncorhynchus mykiss) LC50: 2.16 - 3.05 mg/L, 96h flow-through (Pimephales promelas) LC50: = 0.41 mg/L, 96h static (Oncorhynchus mykiss)		

Persistence and Degradability No information available

Bioaccumulation/ Accumulation No information available.

Mobility No information available.

13. Disposal considerations

Waste Disposal Methods Chemical waste generators must determine whether a discarded chemical is classified as a hazardous waste. Chemical waste generators must also consult local, regional, and national hazardous waste regulations to ensure complete and accurate classification.

14. Transport information

DOT

UN-No	UN1436
Proper Shipping Name	ZINC POWDER
Hazard Class	4.3
Subsidiary Hazard Class	4.2
Packing Group	II

TDG

UN-No	UN1436
Proper Shipping Name	ZINC POWDER
Hazard Class	4.3
Subsidiary Hazard Class	4.2
Packing Group	II

IATA

UN-No	UN1436
Proper Shipping Name	ZINC POWDER
Hazard Class	4.3
Subsidiary Hazard Class	4.2
Packing Group	II

IMDG/IMO

UN-No	UN1436
Proper Shipping Name	ZINC POWDER
Hazard Class	4.3
Subsidiary Hazard Class	4.2
Packing Group	II

15. Regulatory information

International Inventories

Component	TSCA	DSL	NDSL	EINECS	ELINCS	NLP	PICCS	ENCS	AICS	IECSC	KECL
Zinc powder - zinc dust (pyrophoric)	X	X	-	231-175-3	-		X	-	X	X	X

Legend:
X - Listed
E - Indicates a substance that is the subject of a Section 5(e) Consent order under TSCA.
F - Indicates a substance that is the subject of a Section 5(f) Rule under TSCA.
N - Indicates a polymeric substance containing no free-radical initiator in its inventory name but is considered to cover the designated polymer made with any free-radical initiator regardless of the amount used.
P - Indicates a commenced PMN substance

R - Indicates a substance that is the subject of a Section 6 risk management rule under TSCA.
S - Indicates a substance that is identified in a proposed or final Significant New Use Rule
T - Indicates a substance that is the subject of a Section 4 test rule under TSCA.
XU - Indicates a substance exempt from reporting under the Inventory Update Rule, i.e. Partial Updating of the TSCA Inventory Data Base Production and Site Reports (40 CFR 710(B).
Y1 - Indicates an exempt polymer that has a number-average molecular weight of 1,000 or greater.
Y2 - Indicates an exempt polymer that is a polyester and is made only from reactants included in a specified list of low concern reactants that comprises one of the eligibility criteria for the exemption rule.

U.S. Federal Regulations

TSCA 12(b) Not applicable

SARA 313

Component	CAS-No	Weight %	SARA 313 - Threshold Values %
Zinc powder - zinc dust (pyrophoric)	7440-66-6	100	1.0

SARA 311/312 Hazard Categories See section 2 for more information

CWA (Clean Water Act)

Component	CWA - Hazardous Substances	CWA - Reportable Quantities	CWA - Toxic Pollutants	CWA - Priority Pollutants
Zinc powder - zinc dust (pyrophoric)	-	-	X	X

Clean Air Act Not applicable

OSHA Occupational Safety and Health Administration
Not applicable

CERCLA This material, as supplied, contains one or more substances regulated as a hazardous substance under the Comprehensive Environmental Response Compensation and Liability Act (CERCLA) (40 CFR 302)

Component	Hazardous Substances RQs	CERCLA EHS RQs
Zinc powder - zinc dust (pyrophoric)	1000 lb	-

California Proposition 65 This product does not contain any Proposition 65 chemicals

U.S. State Right-to-Know Regulations

Component	Massachusetts	New Jersey	Pennsylvania	Illinois	Rhode Island
Zinc powder - zinc dust (pyrophoric)	X	X	X	-	X

U.S. Department of Transportation

Reportable Quantity (RQ): N
DOT Marine Pollutant N
DOT Severe Marine Pollutant N

U.S. Department of Homeland Security
This product does not contain any DHS chemicals.

Other International Regulations

Mexico - Grade No information available

16. Other information

Prepared By Regulatory Affairs
Thermo Fisher Scientific

Email: EMSDS.RA@thermofisher.com

Creation Date	02-Jun-2010
Revision Date	18-Jan-2018
Print Date	18-Jan-2018
Revision Summary	This document has been updated to comply with the US OSHA HazCom 2012 Standard replacing the current legislation under 29 CFR 1910.1200 to align with the Globally Harmonized System of Classification and Labeling of Chemicals (GHS).

Disclaimer

The information provided in this Safety Data Sheet is correct to the best of our knowledge, information and belief at the date of its publication. The information given is designed only as a guidance for safe handling, use, processing, storage, transportation, disposal and release and is not to be considered a warranty or quality specification. The information relates only to the specific material designated and may not be valid for such material used in combination with any other materials or in any process, unless specified in the text

End of SDS

Safety Data Sheet
acc. to OSHA HCS

Printing date 03/23/2019 Version Number 2 Reviewed on 03/23/2019

*
1 Identification

· **Product identifier**

· **Trade name: Perfluorooctanoic Acid (PFOA)**

· **Part number:** N-1588
· **CAS Number:**
335-67-1
· **EC number:**
206-397-9
· **Index number:**
607-704-00-2
· **Application of the substance / the mixture** Reagents and Standards for Analytical Chemical Laboratory Use

· **Details of the supplier of the safety data sheet**
· **Manufacturer/Supplier:**
Agilent Technologies, Inc.
5301 Stevens Creek Blvd.
Santa Clara, CA 95051 USA

· **Information department:**
Telephone: 800-227-9770
e-mail: pdl-msds_author@agilent.com
· **Emergency telephone number:** CHEMTREC®: 1-800-424-9300

*
2 Hazard(s) identification

· **Classification of the substance or mixture**

GHS08 Health hazard

Carc. 2 H351 Suspected of causing cancer.
Repr. 1B H360 May damage fertility or the unborn child.
STOT RE 1 H372 Causes damage to the liver through prolonged or repeated exposure.

GHS05 Corrosion

Eye Dam. 1 H318 Causes serious eye damage.

GHS07

Acute Tox. 4 H302 Harmful if swallowed.
Acute Tox. 4 H332 Harmful if inhaled.

· **Label elements**
· **GHS label elements** The substance is classified and labeled according to the Globally Harmonized System (GHS).

(Contd. on page 2)

Safety Data Sheet
acc. to OSHA HCS

Printing date 03/23/2019 Version Number 2 Reviewed on 03/23/2019

Trade name: Perfluorooctanoic Acid (PFOA)

(Contd. of page 1)

· **Hazard pictograms**

GHS05 GHS07 GHS08

· **Signal word** Danger

· **Hazard-determining components of labeling:**
perfluorooctanoic acid (PFOA)
· **Hazard statements**
Harmful if swallowed or if inhaled.
Causes serious eye damage.
Suspected of causing cancer.
May damage fertility or the unborn child.
Causes damage to the liver through prolonged or repeated exposure.
· **Precautionary statements**
Obtain special instructions before use.
Do not handle until all safety precautions have been read and understood.
Do not breathe dust/fume/gas/mist/vapors/spray.
Wash thoroughly after handling.
Do not eat, drink or smoke when using this product.
Use only outdoors or in a well-ventilated area.
Wear protective gloves/protective clothing/eye protection/face protection.
If swallowed: Call a poison center/doctor if you feel unwell.
Rinse mouth.
IF INHALED: Remove person to fresh air and keep comfortable for breathing.
If in eyes: Rinse cautiously with water for several minutes. Remove contact lenses, if present and easy to do.
Continue rinsing.
Immediately call a poison center/doctor.
IF exposed or concerned: Get medical advice/attention.
Get medical advice/attention if you feel unwell.
Store locked up.
Dispose of contents/container in accordance with local/regional/national/international regulations.
· **Classification system:**
· **NFPA ratings (scale 0 - 4)**

Health = 3
Fire = 0
Reactivity = 0

· **HMIS-ratings (scale 0 - 4)**

Health = *3
Fire = 0
Reactivity = 0

· **Other hazards**
· **Results of PBT and vPvB assessment**
· **PBT:** Not applicable.

(Contd. on page 3)

Safety Data Sheet
acc. to OSHA HCS

Trade name: Perfluorooctanoic Acid (PFOA)

(Contd. of page 2)

· **vPvB:** Not applicable.

3 Composition/information on ingredients

· **Chemical characterization: Substances**
· **CAS No. Description**
335-67-1 perfluorooctanoic acid (PFOA)
· **Identification number(s)**
· **EC number:** 206-397-9
· **Index number:** 607-704-00-2

4 First-aid measures

· **Description of first aid measures**
· **General information:**
Symptoms of poisoning may even occur after several hours; therefore medical observation for at least 48 hours after the accident.
· **After inhalation:**
Supply fresh air. If required, provide artificial respiration. Keep patient warm. Consult doctor if symptoms persist.
In case of unconsciousness place patient stably in side position for transportation.
· **After skin contact:** Generally the product does not irritate the skin.
· **After eye contact:** Rinse opened eye for several minutes under running water. Then consult a doctor.
· **After swallowing:** Immediately call a doctor.
· **Information for doctor:**
· **Most important symptoms and effects, both acute and delayed** No further relevant information available.
· **Indication of any immediate medical attention and special treatment needed**
No further relevant information available.

5 Fire-fighting measures

· **Extinguishing media**
· **Suitable extinguishing agents:** Use fire fighting measures that suit the environment.
· **Special hazards arising from the substance or mixture**
During heating or in case of fire poisonous gases are produced.
· **Advice for firefighters**
· **Protective equipment:** Mouth respiratory protective device.

6 Accidental release measures

· **Personal precautions, protective equipment and emergency procedures**
Mount respiratory protective device.
Wear protective equipment. Keep unprotected persons away.
· **Environmental precautions:** Do not allow to enter sewers/ surface or ground water.
· **Methods and material for containment and cleaning up:**
Use neutralizing agent.
Dispose contaminated material as waste according to item 13.
Ensure adequate ventilation.

(Contd. on page 4)

(Contd. of page 3)

· **Reference to other sections**
See Section 7 for information on safe handling.
See Section 8 for information on personal protection equipment.
See Section 13 for disposal information.
· **Protective Action Criteria for Chemicals**

· **PAC-1:**
1.1 mg/m³

· **PAC-2:**
12 mg/m³

· **PAC-3:**
75 mg/m³

7 Handling and storage

· **Handling:**
· **Precautions for safe handling**
Thorough dedusting.
Ensure good ventilation/exhaustion at the workplace.
Open and handle receptacle with care.
· **Information about protection against explosions and fires:** Keep respiratory protective device available.

· **Conditions for safe storage, including any incompatibilities**
· **Storage:**
· **Requirements to be met by storerooms and receptacles:** No special requirements.
· **Information about storage in one common storage facility:** Not required.
· **Further information about storage conditions:** Keep receptacle tightly sealed.
· **Specific end use(s)** No further relevant information available.

*
8 Exposure controls/personal protection

· **Additional information about design of technical systems:** No further data; see item 7.

· **Control parameters**
· **Components with limit values that require monitoring at the workplace:** Not required.
· **Additional information:** The lists that were valid during the creation were used as basis.

· **Exposure controls**
· **Personal protective equipment:**
· **General protective and hygienic measures:**
Keep away from foodstuffs, beverages and feed.
Immediately remove all soiled and contaminated clothing.
Wash hands before breaks and at the end of work.
Store protective clothing separately.
Avoid contact with the eyes.
Avoid contact with the eyes and skin.
· **Breathing equipment:**
When used as intended with Agilent instruments, the use of the product under normal laboratory conditions and with standard practices does not result in significant airborne exposures and therefore respiratory protection is not needed.
Under an emergency condition where a respirator is deemed necessary, use a NIOSH or equivalent approved device/equipment with appropriate organic or acid gas cartridge.

(Contd. on page 5)

(Contd. of page 4)

· **Protection of hands:**
Although not recommended for constant contact with the chemicals or for clean-up, nitrile gloves 11-13 mil thickness are recommended for normal use. The breakthrough time is 1 hr. For cleaning a spill where there is direct contact of the chemical, butyl rubber gloves are recommended 12-15 mil thickness with breakthrough times exceeding 4 hrs. Supplier recommendations should be followed.
· **Material of gloves**
For normal use: nitrile rubber, 11-13 mil thickness
For direct contact with the chemical: butyl rubber, 12-15 mil thickness
The selection of the suitable gloves does not only depend on the material, but also on further marks of quality and varies from manufacturer to manufacturer.
· **Penetration time of glove material**
For normal use: nitrile rubber: 1 hour
For direct contact with the chemical: butyl rubber: >4 hours
· **Eye protection:**

Tightly sealed goggles

9 Physical and chemical properties

· **Information on basic physical and chemical properties**	
· **General Information**	
· **Appearance:**	
Form:	Solid
Color:	Not determined.
· **Odor:**	Characteristic
· **Odor threshold:**	Not determined.
· **pH-value:**	Not applicable.
· **Change in condition**	
Melting point/Melting range:	55-56 °C (131-132.8 °F)
Boiling point/Boiling range:	190 °C (374 °F)
· **Flash point:**	Not applicable.
· **Flammability (solid, gaseous):**	Product is not flammable.
· **Decomposition temperature:**	Not determined.
· **Auto igniting:**	Not determined.
· **Danger of explosion:**	Product does not present an explosion hazard.
· **Explosion limits:**	
Lower:	Not determined.
Upper:	Not determined.
· **Vapor pressure at 20 °C (68 °F):**	0.69 hPa (0.5 mm Hg)
· **Density at 20 °C (68 °F):**	0.9 g/cm³ (7.5105 lbs/gal)
· **Relative density**	Not determined.
· **Vapor density**	Not applicable.

(Contd. on page 6)

(Contd. of page 5)

· **Evaporation rate**	Not applicable.
· **Solubility in / Miscibility with Water at 20 °C (68 °F):**	3.4 g/l
· **Partition coefficient (n-octanol/water):**	Not determined.
· **Viscosity:**	
Dynamic:	Not applicable.
Kinematic:	Not applicable.
VOC content:	0.00 % 0.0 g/l / 0.00 lb/gal
Solids content:	100.0 %
· **Other information**	No further relevant information available.

10 Stability and reactivity

· **Reactivity** No further relevant information available.
· **Chemical stability**
· **Thermal decomposition / conditions to be avoided:** No decomposition if used according to specifications.
· **Possibility of hazardous reactions** No dangerous reactions known.
· **Conditions to avoid** No further relevant information available.
· **Incompatible materials:** No further relevant information available.
· **Hazardous decomposition products:** No dangerous decomposition products known.

11 Toxicological information

· **Information on toxicological effects**
· **Acute toxicity:**

· **LD/LC50 values that are relevant for classification:**

ATE (Acute Toxicity Estimate)

Oral	LD50	500 mg/kg
Inhalative	LC50/4 h	1.5 mg/L

· **Primary irritant effect:**
· **on the skin:** No irritant effect.
· **on the eye:** Strong irritant with the danger of severe eye injury.
· **Sensitization:** No sensitizing effects known.
· **Additional toxicological information:**

· **Carcinogenic categories**

· **IARC (International Agency for Research on Cancer)**

2B

· **NTP (National Toxicology Program)**

Substance is not listed.

(Contd. on page 7)

Safety Data Sheet
acc. to OSHA HCS

Trade name: Perfluorooctanoic Acid (PFOA)

(Contd. of page 6)

· **OSHA-Ca (Occupational Safety & Health Administration)**

Substance is not listed.

12 Ecological information

· **Toxicity**
· **Aquatic toxicity:** No further relevant information available.
· **Persistence and degradability** No further relevant information available.
· **Behavior in environmental systems:**
· **Bioaccumulative potential** No further relevant information available.
· **Mobility in soil** No further relevant information available.
· **Additional ecological information:**
· **General notes:**
Water hazard class 2 (Assessment by list): hazardous for water
Do not allow product to reach ground water, water course or sewage system.
Must not reach bodies of water or drainage ditch undiluted or unneutralized.
Danger to drinking water if even small quantities leak into the ground.
· **Results of PBT and vPvB assessment**
· **PBT:** Not applicable.
· **vPvB:** Not applicable.
· **Other adverse effects** No further relevant information available.

13 Disposal considerations

· **Waste treatment methods**
· **Recommendation:**
Must not be disposed of together with household garbage. Do not allow product to reach sewage system.

· **Uncleaned packagings:**
· **Recommendation:** Disposal must be made according to official regulations.

14 Transport information

· **UN-Number**	
· **DOT, IMDG, IATA**	UN3261
· **UN proper shipping name**	
· **DOT**	Corrosive solid, acidic, organic, n.o.s. (perfluorooctanoic acid (PFOA))
· **IMDG, IATA**	CORROSIVE SOLID, ACIDIC, ORGANIC, N.O.S. (perfluorooctanoic acid (PFOA))

(Contd. on page 8)

(Contd. of page 7)

· **Transport hazard class(es)**

· **IATA**

· **Class**	8 Corrosive substances
· **Label**	8
· **Environmental hazards:**	Not applicable.
· **Special precautions for user**	Warning: Corrosive substances
· **Danger code (Kemler):**	80
· **EMS Number:**	F-A,S-B
· **Segregation groups**	Acids
· **Transport in bulk according to Annex II of MARPOL73/78 and the IBC Code**	Not applicable.
· **Transport/Additional information:**	
· **DOT**	
· **Quantity limitations**	On passenger aircraft/rail: 25 kg On cargo aircraft only: 100 kg
· **IMDG**	
· **Limited quantities (LQ)**	5 kg
· **Excepted quantities (EQ)**	Code: E1 Maximum net quantity per inner packaging: 30 g Maximum net quantity per outer packaging: 1000 g
· **UN "Model Regulation":**	UN 3261 CORROSIVE SOLID, ACIDIC, ORGANIC, N.O.S. (PERFLUOROOCTANOIC ACID (PFOA)), 8, III

15 Regulatory information

· **Safety, health and environmental regulations/legislation specific for the substance or mixture**

· **Sara**

· **Section 355 (extremely hazardous substances):**

Substance is not listed.

· **Section 313 (Specific toxic chemical listings):**

Substance is not listed.

· **TSCA (Toxic Substances Control Act):**

Substance is listed.

· **Proposition 65**

· **Chemicals known to cause cancer:**

Substance is not listed.

· **Chemicals known to cause reproductive toxicity for females:**

Substance is not listed.

(Contd. on page 9)

Safety Data Sheet
acc. to OSHA HCS

Trade name: Perfluorooctanoic Acid (PFOA)

(Contd. of page 8)

· **Chemicals known to cause reproductive toxicity for males:**
Substance is not listed.

· **Chemicals known to cause developmental toxicity:**
Substance is listed.

· **Carcinogenic categories**

· **EPA (Environmental Protection Agency)**
Substance is not listed.

· **TLV (Threshold Limit Value established by ACGIH)**
Substance is not listed.

· **NIOSH-Ca (National Institute for Occupational Safety and Health)**
Substance is not listed.

· **Chemical safety assessment:** A Chemical Safety Assessment has not been carried out.

*
16 Other information

The information contained in this document is based on Agilent's state of knowledge at the time of preparation. No warranty as to its accurateness, completeness or suitability for a particular purpose is expressed or implied.

· **Date of preparation / last revision** 03/23/2019 / 1

· **Abbreviations and acronyms:**
ADR: Accord européen sur le transport des marchandises dangereuses par Route (European Agreement concerning the International Carriage of Dangerous Goods by Road)
IMDG: International Maritime Code for Dangerous Goods
DOT: US Department of Transportation
IATA: International Air Transport Association
ACGIH: American Conference of Governmental Industrial Hygienists
EINECS: European Inventory of Existing Commercial Chemical Substances
CAS: Chemical Abstracts Service (division of the American Chemical Society)
NFPA: National Fire Protection Association (USA)
HMIS: Hazardous Materials Identification System (USA)
VOC: Volatile Organic Compounds (USA, EU)
LC50: Lethal concentration, 50 percent
LD50: Lethal dose, 50 percent
PBT: Persistent, Bioaccumulative and Toxic
vPvB: very Persistent and very Bioaccumulative
NIOSH: National Institute for Occupational Safety
OSHA: Occupational Safety & Health
TLV: Threshold Limit Value
PEL: Permissible Exposure Limit
REL: Recommended Exposure Limit
Acute Tox. 4: Acute toxicity – Category 4
Eye Dam. 1: Serious eye damage/eye irritation – Category 1
Carc. 2: Carcinogenicity – Category 2
Repr. 1B: Reproductive toxicity – Category 1B
STOT RE 1: Specific target organ toxicity (repeated exposure) – Category 1

· *** Data compared to the previous version altered.**

Safety data sheet
according to 1907/2006/EC, Article 31

Printing date 11.04.2023 *Version number 1* *Revision: 11.04.2023*

SECTION 1: Identification of the substance/mixture and of the company/undertaking

· **1.1 Product identifier**

· **Trade name: Perfluorooctane sulfonic acid [CAS:1763-23-1] (SB25441)**
· **CAS Number:**
1763-23-1
· **EC number:**
217-179-8
· **Index number:**
607-624-00-8
· **Registration number**
A registration number is not available for this substance as the substance or its uses are exempted for registration, the annual tonnage does not require a registration or the registration is envisaged for a later registration deadline.
· **1.2 Relevant identified uses of the substance or mixture and uses advised against**
No further relevant information available.
· **Application of the substance / the mixture** Laboratory Reagent

· **1.3 Details of the supplier of the safety data sheet**
· **Manufacturer/Supplier:**
CPAchem Ltd.
2 Ivanka Terzieva Str.
Bogomilovo 6065
Stara Zagora, BULGARIA
info@cpachem.com
+359 42952901

· **Further information obtainable from:** Product safety department
· **1.4 Emergency telephone number:**
EMERGENCY HEALTH INFORMATION:
Austria +43 1 31304 5620, Belgium +32022649636, Bulgaria +359 2 9154 409, Croatia +38514686910, Cyprus +3572240561, Czech Republic +420267082257, Denmark +45 72 54 40 00, Estonia +3726943384, Finland +358 5052 000, France +33 3 85 21 92, Germany +49-30-18412-0, Greece +302106479250, Hungary +34 (1) 476 1136, Ireland +35318092566, Italy +390649906140, Latvia +371 67032600, Lithuania +370 70662008, Luxembourg +352 24785551, Netherland +31 88 75 585 61,
Norway +47 21 07 70 00, Poland +48 42 2530 400, Portugal +351213303271, Romania +40213183606, Slovakia +421 2 5465 2307, Slovenia +38614006039, Spain +34 917689800, Sweden +46104566750, United Kingdom (England or Wales) 0845 46 47 or Scotland 08454 24 24 24 (UK only).

SECTION 2: Hazards identification

· **2.1 Classification of the substance or mixture**
· **Classification according to Regulation (EC) No 1272/2008**

GHS08 health hazard

Carc. 2	H351	Suspected of causing cancer.
Repr. 1B	H360D-H362	May damage the unborn child. May cause harm to breast-fed children.
STOT RE 1	H372	Causes damage to organs through prolonged or repeated exposure.

GHS05 corrosion

Skin Corr. 1B	H314	Causes severe skin burns and eye damage.

(Contd. on page 2)

Safety data sheet
according to 1907/2006/EC, Article 31

Printing date 11.04.2023 *Version number 1* *Revision: 11.04.2023*

Trade name: Perfluorooctane sulfonic acid [CAS:1763-23-1] (SB25441)

(Contd. of page 1)

GHS09 environment

Aquatic Chronic 2 H411 *Toxic to aquatic life with long lasting effects.*

GHS07

Acute Tox. 4 *H302* *Harmful if swallowed.*
Acute Tox. 4 *H332* *Harmful if inhaled.*

· ***2.2 Label elements***
· ***Labelling according to Regulation (EC) No 1272/2008***
The substance is classified and labelled according to the CLP regulation.
· ***Hazard pictograms***

GHS05 GHS07 GHS08 GHS09

· ***Signal word*** *Danger*

· ***Hazard-determining components of labelling:***
perfluorooctane sulfonic acid
· ***Hazard statements***
H302+H332 Harmful if swallowed or if inhaled.
H314 Causes severe skin burns and eye damage.
H351 Suspected of causing cancer.
H360D-H362 May damage the unborn child. May cause harm to breast-fed children.
H372 Causes damage to organs through prolonged or repeated exposure.
H411 Toxic to aquatic life with long lasting effects.
· ***Precautionary statements***
P263 Avoid contact during pregnancy and while nursing.
P303+P361+P353 IF ON SKIN (or hair): Take off immediately all contaminated clothing. Rinse skin with water [or shower].
P305+P351+P338 IF IN EYES: Rinse cautiously with water for several minutes. Remove contact lenses, if present and easy to do. Continue rinsing.
P310 Immediately call a POISON CENTER/doctor.
P321 Specific treatment (see on this label).
P405 Store locked up.
P501 Dispose of contents/container in accordance with local/regional/national/international regulations.
· ***2.3 Other hazards***
· ***Results of PBT and vPvB assessment***
· ***PBT:*** *Not applicable.*
· ***vPvB:*** *Not applicable.*

SECTION 3: Composition/information on ingredients

· ***3.1 Substances***
· ***CAS No. Description***
1763-23-1 perfluorooctane sulfonic acid
· ***Identification number(s)***
· ***EC number:*** *217-179-8*

(Contd. on page 3)

Safety data sheet
according to 1907/2006/EC, Article 31

Printing date 11.04.2023 Version number 1 Revision: 11.04.2023

Trade name: Perfluorooctane sulfonic acid [CAS:1763-23-1] (SB25441)

(Contd. of page 2)

· **Index number:** 607-624-00-8

SECTION 4: First aid measures

· **4.1 Description of first aid measures**
· **General information:**
Symptoms of poisoning may even occur after several hours; therefore medical observation for at least 48 hours after the accident.
· **After inhalation:**
Supply fresh air. If required, provide artificial respiration. Keep patient warm. Consult doctor if symptoms persist.
In case of unconsciousness place patient stably in side position for transportation.
· **After skin contact:** Generally the product does not irritate the skin.
· **After eye contact:** Rinse opened eye for several minutes under running water. Then consult a doctor.
· **After swallowing:** Call for a doctor immediately.
· **4.2 Most important symptoms and effects, both acute and delayed** No further relevant information available.
· **4.3 Indication of any immediate medical attention and special treatment needed**
No further relevant information available.

SECTION 5: Firefighting measures

· **5.1 Extinguishing media**
· **Suitable extinguishing agents:**
CO2, powder or water spray. Fight larger fires with water spray or alcohol resistant foam.
· **5.2 Special hazards arising from the substance or mixture** No further relevant information available.
· **5.3 Advice for firefighters**
· **Protective equipment:** Mouth respiratory protective device.

SECTION 6: Accidental release measures

· **6.1 Personal precautions, protective equipment and emergency procedures** Not required.
· **6.2 Environmental precautions:**
Inform respective authorities in case of seepage into water course or sewage system.
Do not allow to enter sewers/ surface or ground water.
· **6.3 Methods and material for containment and cleaning up:**
Dispose contaminated material as waste according to item 13.
Ensure adequate ventilation.
· **6.4 Reference to other sections**
See Section 7 for information on safe handling.
See Section 8 for information on personal protection equipment.
See Section 13 for disposal information.

SECTION 7: Handling and storage

· **7.1 Precautions for safe handling**
Thorough dedusting.
Ensure good ventilation/exhaustion at the workplace.
Open and handle receptacle with care.
· **Information about fire - and explosion protection:** Keep respiratory protective device available.

· **7.2 Conditions for safe storage, including any incompatibilities**
· **Storage:**
· **Requirements to be met by storerooms and receptacles:** No special requirements.
· **Information about storage in one common storage facility:** Not required.
· **Further information about storage conditions:** Keep container tightly sealed.

(Contd. on page 4)

Safety data sheet
according to 1907/2006/EC, Article 31

Printing date 11.04.2023 *Version number 1* *Revision: 11.04.2023*

Trade name: Perfluorooctane sulfonic acid [CAS:1763-23-1] (SB25441)

(Contd. of page 3)

· ***7.3 Specific end use(s)*** *No further relevant information available.*

SECTION 8: Exposure controls/personal protection

· ***8.1 Control parameters***
· ***Ingredients with limit values that require monitoring at the workplace:*** *Not required.*
· ***Additional information:*** *The lists valid during the making were used as basis.*

· ***8.2 Exposure controls***
· ***Appropriate engineering controls*** *No further data; see item 7.*
· ***Individual protection measures, such as personal protective equipment***
· ***General protective and hygienic measures:***
Keep away from foodstuffs, beverages and feed.
Immediately remove all soiled and contaminated clothing
Wash hands before breaks and at the end of work.
Store protective clothing separately.
· ***Respiratory protection:***
In case of brief exposure or low pollution use respiratory filter device. In case of intensive or longer exposure use self-contained respiratory protective device.
· ***Hand protection***

Protective gloves

The glove material has to be impermeable and resistant to the product/ the substance/ the preparation.
Due to missing tests no recommendation to the glove material can be given for the product/ the preparation/ the chemical mixture.
Selection of the glove material on consideration of the penetration times, rates of diffusion and the degradation
· ***Material of gloves***
The selection of the suitable gloves does not only depend on the material, but also on further marks of quality and varies from manufacturer to manufacturer.
· ***Penetration time of glove material***
The exact break through time has to be found out by the manufacturer of the protective gloves and has to be observed.
· ***Eye/face protection*** *Not required.*

SECTION 9: Physical and chemical properties

· ***9.1 Information on basic physical and chemical properties***
· ***General Information***

· ***Physical state***	*Solid*
· ***Colour:***	*Not determined.*
· ***Odour:***	*Characteristic*
· ***Odour threshold:***	*Not determined.*
· ***Melting point/freezing point:***	*90 °C*
· ***Boiling point or initial boiling point and boiling range***	*260 °C*
· ***Flammability***	*Product is not flammable.*
· ***Lower and upper explosion limit***	
· ***Lower:***	*Not determined.*
· ***Upper:***	*Not determined.*
· ***Flash point:***	*11 °C*
· ***Decomposition temperature:***	*Not determined.*
· ***pH***	*Not applicable.*

(Contd. on page 5)

Safety data sheet
according to 1907/2006/EC, Article 31

Printing date 11.04.2023 *Version number 1* *Revision: 11.04.2023*

Trade name: Perfluorooctane sulfonic acid [CAS:1763-23-1] (SB25441)

(Contd. of page 4)

· **Viscosity:**	
· **Kinematic viscosity**	Not applicable.
· **Dynamic:**	Not applicable.
· **Solubility**	
· **water:**	Insoluble.
· **Partition coefficient n-octanol/water (log value)**	Not determined.
· **Vapour pressure:**	Not applicable.
· **Density and/or relative density**	
· **Density at 20 °C:**	1.25 g/cm³
· **Relative density**	Not determined.
· **Vapour density**	Not applicable.
· **Particle characteristics**	See item 3.

· **9.2 Other information**	
· **Appearance:**	
· **Form:**	Solid
· **Important information on protection of health and environment, and on safety.**	
· **Ignition temperature:**	Not determined.
· **Explosive properties:**	Product does not present an explosion hazard.
· **Solids content:**	99.2 %
· **Molecular weight**	500.13 g/mol
· **Change in condition**	
· **Evaporation rate**	Not applicable.

· **Information with regard to physical hazard classes**	
· **Explosives**	Void
· **Flammable gases**	Void
· **Aerosols**	Void
· **Oxidising gases**	Void
· **Gases under pressure**	Void
· **Flammable liquids**	Void
· **Flammable solids**	Void
· **Self-reactive substances and mixtures**	Void
· **Pyrophoric liquids**	Void
· **Pyrophoric solids**	Void
· **Self-heating substances and mixtures**	Void
· **Substances and mixtures, which emit flammable gases in contact with water**	Void
· **Oxidising liquids**	Void
· **Oxidising solids**	Void
· **Organic peroxides**	Void
· **Corrosive to metals**	Void
· **Desensitised explosives**	Void

SECTION 10: Stability and reactivity

· **10.1 Reactivity** No further relevant information available.
· **10.2 Chemical stability**
· **Thermal decomposition / conditions to be avoided:** No decomposition if used according to specifications.
· **10.3 Possibility of hazardous reactions** No dangerous reactions known.
· **10.4 Conditions to avoid** No further relevant information available.
· **10.5 Incompatible materials:** No further relevant information available.
· **10.6 Hazardous decomposition products:** No dangerous decomposition products known.

(Contd. on page 6)

Safety data sheet
according to 1907/2006/EC, Article 31

Printing date 11.04.2023 Version number 1 Revision: 11.04.2023

Trade name: Perfluorooctane sulfonic acid [CAS:1763-23-1] (SB25441)

(Contd. of page 5)

SECTION 11: Toxicological information

· **11.1 Information on hazard classes as defined in Regulation (EC) No 1272/2008**
· **Acute toxicity** Harmful if swallowed or if inhaled.

· LD/LC50 values relevant for classification:		
ATE (Acute Toxicity Estimates)		
Oral	LD50	500 mg/kg
Inhalative	LC50/4 h	1.5 mg/l

1763-23-1 perfluorooctane sulfonic acid		
Oral	LD50	500 mg/kg (ATE)
Inhalative	LC50/4 h	1.5 mg/l (ATE)

· **Skin corrosion/irritation** Causes severe skin burns and eye damage.
· **Serious eye damage/irritation** Based on available data, the classification criteria are not met.
· **Respiratory or skin sensitisation** Based on available data, the classification criteria are not met.
· **Germ cell mutagenicity** Based on available data, the classification criteria are not met.
· **Carcinogenicity** Suspected of causing cancer.
· **Reproductive toxicity** May damage the unborn child. May cause harm to breast-fed children.
· **STOT-single exposure** Based on available data, the classification criteria are not met.
· **STOT-repeated exposure** Causes damage to organs through prolonged or repeated exposure.
· **Aspiration hazard** Based on available data, the classification criteria are not met.
· **11.2 Information on other hazards**

· Endocrine disrupting properties
Substance is not listed.

SECTION 12: Ecological information

· **12.1 Toxicity**
· **Aquatic toxicity:** No further relevant information available.
· **12.2 Persistence and degradability** No further relevant information available.
· **12.3 Bioaccumulative potential** No further relevant information available.
· **12.4 Mobility in soil** No further relevant information available.
· **12.5 Results of PBT and vPvB assessment**
· **PBT:** Not applicable.
· **vPvB:** Not applicable.
· **12.6 Endocrine disrupting properties**
The product does not contain substances with endocrine disrupting properties.
· **12.7 Other adverse effects**
· **Remark:** Toxic for fish
· **Additional ecological information:**
· **General notes:**
Water hazard class 3 (German Regulation) (Self-assessment): extremely hazardous for water
Do not allow product to reach ground water, water course or sewage system, even in small quantities.
Danger to drinking water if even extremely small quantities leak into the ground.
Also poisonous for fish and plankton in water bodies.
Toxic for aquatic organisms

SECTION 13: Disposal considerations

· **13.1 Waste treatment methods**
· **Recommendation**
Must not be disposed together with household garbage. Do not allow product to reach sewage system.

(Contd. on page 7)

Safety data sheet
according to 1907/2006/EC, Article 31

Printing date 11.04.2023 *Version number 1* *Revision: 11.04.2023*

Trade name: Perfluorooctane sulfonic acid [CAS:1763-23-1] (SB25441)

(Contd. of page 6)

· **Uncleaned packaging:**
· **Recommendation:** Disposal must be made according to official regulations.

SECTION 14: Transport information

· **14.1 UN number or ID number**	
· **ADR, IMDG, IATA**	UN3261
· **14.2 UN proper shipping name**	
· **ADR**	3261 CORROSIVE SOLID, ACIDIC, ORGANIC, N.O.S. (perfluorooctane sulfonic acid), ENVIRONMENTALLY HAZARDOUS
· **IMDG**	CORROSIVE SOLID, ACIDIC, ORGANIC, N.O.S. (perfluorooctane sulfonic acid), MARINE POLLUTANT
· **IATA**	CORROSIVE SOLID, ACIDIC, ORGANIC, N.O.S. (perfluorooctane sulfonic acid)
· **14.3 Transport hazard class(es)**	
· **ADR, IMDG**	
· **Class**	8 Corrosive substances.
· **Label**	8
· **IATA**	
· **Class**	8 Corrosive substances.
· **Label**	8
· **14.4 Packing group**	
· **ADR, IMDG, IATA**	II
· **14.5 Environmental hazards:**	
· **Marine pollutant:**	Symbol (fish and tree)
· **Special marking (ADR):**	Symbol (fish and tree)
· **14.6 Special precautions for user**	Warning: Corrosive substances.
· **EMS Number:**	F-A,S-B
· **Segregation groups**	(SGG1) Acids
· **Stowage Category**	B
· **14.7 Maritime transport in bulk according to IMO instruments**	Not applicable.
· **Transport/Additional information:**	
· **ADR**	
· **Limited quantities (LQ)**	1 kg
· **Excepted quantities (EQ)**	Code: E2 Maximum net quantity per inner packaging: 30 g Maximum net quantity per outer packaging: 500 g
· **Transport category**	2
· **Tunnel restriction code**	E

(Contd. on page 8)

Safety data sheet
according to 1907/2006/EC, Article 31

Printing date 11.04.2023 *Version number 1* *Revision: 11.04.2023*

Trade name: Perfluorooctane sulfonic acid [CAS:1763-23-1] (SB25441)

(Contd. of page 7)

· ***IMDG***	
· ***Limited quantities (LQ)***	*1 kg*
· ***Excepted quantities (EQ)***	*Code: E2* *Maximum net quantity per inner packaging: 30 g* *Maximum net quantity per outer packaging: 500 g*
· ***UN "Model Regulation":***	*UN 3261 CORROSIVE SOLID, ACIDIC, ORGANIC, N.O.S. (PERFLUOROOCTANE SULFONIC ACID), 8, II, ENVIRONMENTALLY HAZARDOUS*

SECTION 15: Regulatory information

· ***15.1 Safety, health and environmental regulations/legislation specific for the substance or mixture***
· ***Labelling according to Regulation (EC) No 1272/2008***
The substance is classified and labelled according to the CLP regulation.
· ***Hazard pictograms***

GHS05 GHS07 GHS08 GHS09

· ***Signal word*** *Danger*

· ***Hazard-determining components of labelling:***
perfluorooctane sulfonic acid
· ***Hazard statements***
H302+H332 Harmful if swallowed or if inhaled.
H314 Causes severe skin burns and eye damage.
H351 Suspected of causing cancer.
H360D-H362 May damage the unborn child. May cause harm to breast-fed children.
H372 Causes damage to organs through prolonged or repeated exposure.
H411 Toxic to aquatic life with long lasting effects.
· ***Precautionary statements***
P263 Avoid contact during pregnancy and while nursing.
P303+P361+P353 IF ON SKIN (or hair): Take off immediately all contaminated clothing. Rinse skin with water [or shower].
P305+P351+P338 IF IN EYES: Rinse cautiously with water for several minutes. Remove contact lenses, if present and easy to do. Continue rinsing.
P310 Immediately call a POISON CENTER/doctor.
P321 Specific treatment (see on this label).
P405 Store locked up.
P501 Dispose of contents/container in accordance with local/regional/national/international regulations.

· ***Directive 2012/18/EU***
· ***Named dangerous substances - ANNEX I*** *Substance is not listed.*
· ***Seveso category*** *E2 Hazardous to the Aquatic Environment*
· ***Qualifying quantity (tonnes) for the application of lower-tier requirements*** *200 t*
· ***Qualifying quantity (tonnes) for the application of upper-tier requirements*** *500 t*

· ***REGULATION (EU) 2019/1021 on persistent organic pollutants (POP)***
Annex I Part A *Annex IV*

· ***REGULATION (EC) No 1907/2006 ANNEX XVII*** *Conditions of restriction: 30*

(Contd. on page 9)

Safety data sheet
according to 1907/2006/EC, Article 31

Printing date 11.04.2023 *Version number 1* *Revision: 11.04.2023*

Trade name: Perfluorooctane sulfonic acid [CAS:1763-23-1] (SB25441)

(Contd. of page 8)

· ***Regulation (EU) No 649/2012***

Annex I Part 1
Annex I Part 2
Annex I Part 3
Annex V Part 1

· ***DIRECTIVE 2011/65/EU on the restriction of the use of certain hazardous substances in electrical and electronic equipment – Annex II***

Substance is not listed.

· ***REGULATION (EU) 2019/1148***

· ***Annex I - RESTRICTED EXPLOSIVES PRECURSORS (Upper limit value for the purpose of licensing under Article 5(3))***

Substance is not listed.

· ***Annex II - REPORTABLE EXPLOSIVES PRECURSORS***

Substance is not listed.

· ***Regulation (EC) No 273/2004 on drug precursors***

Substance is not listed.

· ***Regulation (EC) No 111/2005 laying down rules for the monitoring of trade between the Community and third countries in drug precursors***

Substance is not listed.

· ***15.2 Chemical safety assessment:*** *A Chemical Safety Assessment has not been carried out.*

SECTION 16: Other information

This information is based on our present knowledge. However, this shall not constitute a guarantee for any specific product features and shall not establish a legally valid contractual relationship.

· ***Department issuing SDS:*** *Product safety department*
· ***Contact:*** *Mrs. Taralova*
· ***Date of previous version:*** *09.12.2022*
· ***Abbreviations and acronyms:***
ADR: Accord relatif au transport international des marchandises dangereuses par route (European Agreement Concerning the International Carriage of Dangerous Goods by Road)
IMDG: International Maritime Code for Dangerous Goods
IATA: International Air Transport Association
GHS: Globally Harmonised System of Classification and Labelling of Chemicals
EINECS: European Inventory of Existing Commercial Chemical Substances
CAS: Chemical Abstracts Service (division of the American Chemical Society)
LC50: Lethal concentration, 50 percent
LD50: Lethal dose, 50 percent
PBT: Persistent, Bioaccumulative and Toxic
vPvB: very Persistent and very Bioaccumulative
Acute Tox. 4: Acute toxicity – Category 4
Skin Corr. 1B: Skin corrosion/irritation – Category 1B
Carc. 2: Carcinogenicity – Category 2
Repr. 1B: Reproductive toxicity – Category 1B
STOT RE 1: Specific target organ toxicity (repeated exposure) – Category 1
Aquatic Chronic 2: Hazardous to the aquatic environment - long-term aquatic hazard – Category 2

ATTACHMENT H

Jobsite Safety Inspection Checklist

LANGAN

LANGAN

ATTACHMENT H

JOBSITE SAFETY INSPECTION CHECKLIST

Client: _____ Inspection Date: _____

Site: _____ Inspector: _____

Employees: _____

Notes:_____

_____

_____

Check one of the following: **A:** Acceptable **NA**: Not Applicable **D**: Deficiency

	A	NA	D	Remarks
GENERAL				
Appropriate PPE being worn by Langan employees and subcontractors?				
Air monitoring instruments calibrated daily and results recorded on the Daily Instrument Calibration check sheet?				
Air monitoring readings recorded on the air monitoring data sheet/field log book?				
Incident reporting procedures known?				
Site security an issue?				
Vehicle /pedestrian traffic issue?				
Adequate size/type fire extinguisher supplied?				
Evidence that drilling operator is responsible for the safety of his rig.				
First Aid kit available?				
PERSONAL PROTECTIVE EQUIPMENT				
Eye Protection?				
Head protection?				
Safety Shoes?				
Safety vests?				
Hand protection?				
Other?				
Deficiencies??				
HOUSEKEEPING				
Work area kept clean/tidy to minimize potential hazards?				
Waste being disposed of quickly and properly				
Adequate lighting for job?				
Portable water available?				
HAND TOOLS				
Are tools in good condition and properly used? (INSPECT)				
Are proper tools being used?				
Are tools safety stored when not in use?				
Have tools been inspected prior to use?				
Are employees familiar with using tools?				
Is additional PPE required for tools? Available?				
POWER TOOLS				
Are tools in good condition and properly used? (INSPECT)				
Are tools properly grounded?				
Safety guards in place and used correctly?				
Competent instruction / supervision?				
Cords include in inspection?				

HAZWOPER				
Employees have current 40-hr./8-hr./Supervisor HAZWOPER training?				
Project staff medically cleared to work in hazardous waste sites and fit-tested to wear respirators, if needed?				
Respiratory protection readily available?				
Subcontract workers have current 40-hr./8-hr./Spvsr. HAZWOPER training, as appropriate?				
Subcontract workers medically cleared to work on site, and fit-tested for respirator wear?				
Subcontract workers have respirators readily available?				
HEALTH & SAFETY PLAN				
HASP available on site for inspection?				
Health & Safety Compliance agreement (in HASP) appropriately signed by Langan employees and subcontractors?				
Hospital route map with directions posted on site?				
Emergency Notification List posted on site?				
Personnel trained in CPR/First Aid on site?				
MSDSs readily available, and all workers knowledgeable about the specific chemicals and compounds to which they may be exposed?				
Project site safe practices ("Standing Orders") posted?				
Health & Safety Incident Report forms available?				
Decontamination procedures being followed as outlined in HASP?				
UNDERGROUND UTILITY				
Mark outs of underground utilities done prior to initiating any subsurface activities?				
Underground utilities located and authorities contacted before digging?				
Visually observed mark-outs?				
Is subsurface work within three feet of underground utilities?				
- Is so, is or was soft dig techniques used?				
Drilling performed in areas free from underground utilities?				
EXCAVATION / TRENCH				
Are excavations/trenches over 5 feet deep sloped, shored or a trench box used?				
Operations supervised by a Competent Person?				
Is Competent Person preforming daily inspections of excavation/trench?				
Adequate barricades in place?				
Have underground utilities been identified?				
Ladders / means of egress in trench with 25-foot of every worker?				
Has PE designed or approved protective system?				
Excavated material and other objects placed more than 2 feet away from excavation edge?				
Public protected from exposure to open excavation?				
CONFINED / PERMIT-ENTRY CONFINED SPACE				
People entering the excavation regarding it as a permit-required confined space and following appropriate procedures?				
Confined space entry permit is completed and posted?				
All persons knowledgeable about the conditions and characteristics of the confined space?				
All persons engaged in confined space operations have been trained in safe entry and rescue (non-entry)?				
Full body harnesses, lifelines, and hoisting apparatus available for rescue needs?				
Attendant and/or supervisor certified in basic first aid and CPR?				
Confined space atmosphere checked before entry and continuously while the work is going on?				
Results of confined space atmosphere testing recorded?				
Evidence of coordination with off-site rescue services to perform entry rescue, if needed?				
ELECTRICAL SAFETY				
Equipment at least 10 feet from overhead power lines?				
Is equipment grounded?				
GFCI used and tested where required?				
Are extension cords rated for this work being used and are they properly maintained?				
Electrical dangers posted at site?				

FLAMMABLE LIQUIDS				
Are flammable liquids used at site?				
Are flammable liquids stored in appropriate containers?				
Are flammable liquids kept away from combustion sources?				
Do flammable liquid containers have warning labels?				
LADDERS				
Are ladders used at site?				
Were ladders inspected prior to use?				
Are ladders in good working condition?				
Are ladders secured to prevent slipping, sliding or falling?				
Do side rails extend three feet above top of landing area?				
Are top two steps of stepladders being used?				
Is extension on ladder facing out?				
Are ladders sufficient for task?				
Are ladders sufficient for task?				

Unsafe acts observed? _____

Additional remarks _____

Notes:_____

Distribution: Project Manager - Name: _____
Health & Safety Officer - Name: _____
Health & Safety Manager- Name: Anthony Moffa, CHMM

ATTACHMENT I

Langan Guidelines

LANGAN

ATTACHMENT I

LANGAN GUIDELINES

GENERAL

- No smoking, eating, or drinking in this work zone.
- Upon leaving the work zone, personnel will thoroughly wash their hands and face.
- Minimize contact with contaminated materials through proper planning of work areas and decontamination areas, and by following proper procedures. Do not place equipment on the ground. Do not sit on contaminated materials.
- No open flames in the work zone.
- Only properly trained and equipped personnel are permitted to work in potentially contaminated areas.
- Always use the appropriate level of personal protective equipment (PPE).
- Maintain close contact with your buddy in the work zone
- Contaminated material will be contained in the Exclusion Zone (EZ).
- Report any unusual conditions.
- Work areas will be kept clear and uncluttered. Debris and other slip, trip, and fall hazards will be removed as frequently as possible.
- The number of personnel and equipment in the work zone will be kept to an essential minimum.
- Be alert to the symptoms of fatigue and heat/cold stress, and their effects on the normal caution and judgment of personnel.
- Conflicting situations which may arise concerning safety requirements and working conditions must be addressed and resolved quickly by the site HSO.

TOOLS AND HEAVY EQUIPMENT

- Do not, under any circumstances, enter or ride in or on any backhoe bucket, materials hoist, or any other device not specifically designed to carrying passengers.
- Loose-fitting clothing or loose long hair is prohibited around moving machinery.
- Ensure that heavy equipment operators and all other personnel in the work zone are using the same hand signals to communicate.
- Drilling/excavating within 10 feet in any direction of overhead power lines is prohibited.
- The locations of all underground utilities must be identified and marked out prior to initiating any subsurface activities.
- Check to insure that the equipment operator has lowered all blades and buckets to the ground before shutting off the vehicle.
- If the equipment has an emergency stop device, have the operator show all personnel its location and how to activate it.
- Help the operator ensure adequate clearances when the equipment must negotiate in tight quarters; serve as a signalman to direct backing as necessary.
- Ensure that all heavy equipment that is used in the Exclusion Zone is kept in that zone until the job is done, and that such equipment is completely decontaminated before moving it into the clean area of the work zone.
- Samplers must not reach into or get near rotating equipment such as the drill rig. If personnel must work near any tools that could rotate, the equipment operator must completely shut down the rig prior to initiating such work. It may be necessary to use a remote sampling device.

APPENDIX H

NYSDEC Community Air Monitoring Plan

LANGAN

New York State Department of Health Generic Community Air Monitoring Plan

A Community Air Monitoring Plan (CAMP) requires real-time monitoring for volatile organic compounds (VOCs) and particulates (i.e., dust) at the downwind perimeter of each designated work area and when certain activities are in progress at contaminated sites. The CAMP is not intended for use in establishing action levels for worker respiratory protection. Rather, its intent is to provide a measure of protection for the downwind community (i.e., off-site receptors including residences and businesses and on-site workers not directly involved with the subject work activities) from potential airborne contaminant releases as a direct result of investigative and remedial work activities. The action levels specified herein require increased monitoring, corrective actions to abate emissions, and/or work shutdown. Additionally, the CAMP helps to confirm that work activities did not spread contamination off-site through the air.

The generic CAMP presented below will be sufficient to cover many, if not most, sites. Specific requirements should be reviewed for each situation in consultation with NYSDOH to ensure proper applicability. In some cases, a separate site-specific CAMP or supplement may be required. Depending upon the nature of contamination, chemical specific monitoring with appropriately-sensitive methods may be required. Depending upon the proximity of potentially exposed individuals, more stringent monitoring or response levels than those presented below may be required. Special requirements will be necessary for work within 20 feet of potentially exposed individuals or structures and for indoor work with co-located residences or facilities. These requirements should be determined in consultation with NYSDOH.
Reliance on the CAMP should not preclude simple, common-sense measures to keep VOCs, dust, and odors at a minimum around the work areas.

Community Air Monitoring Plan

Depending upon the nature of known or potential contaminants at each site, real-time air monitoring for volatile organic compounds (VOCs) and/or particulate levels at the perimeter of the exclusion zone or work area will be necessary. Most sites will involve VOC and particulate monitoring; sites known to be contaminated with heavy metals alone may only require particulate monitoring. If radiological contamination is a concern, additional monitoring requirements may be necessary per consultation with appropriate NYSDEC/NYSDOH staff.

Continuous monitoring will be required at one upwind and two downwind stations for all ground intrusive activities and during the demolition of contaminated or potentially contaminated structures. Ground intrusive activities include, but are not limited to, soil/waste excavation and handling, test pitting or trenching, and the installation of soil borings or monitoring wells.

Periodic monitoring for VOCs will be required during non-intrusive activities such as the collection of soil and sediment samples or the collection of groundwater samples from existing monitoring wells. "Periodic" monitoring during sample collection might reasonably consist of taking a reading upon arrival at a sample location, monitoring while opening a well cap or overturning soil, monitoring during well baling/purging, and taking a reading prior to leaving a sample location. In some instances, depending upon the proximity of potentially exposed individuals, continuous monitoring may be required during sampling activities. Examples of such situations include groundwater sampling at wells on the curb of a busy urban street, in the midst of a public park, or adjacent to a school or residence.

VOC Monitoring, Response Levels, and Actions

Volatile organic compounds (VOCs) must be monitored at the downwind perimeter of the immediate work area (i.e., the exclusion zone) on a **continuous** bases or as otherwise specified. Upwind concentrations should be measured at the start of each workday and periodically thereafter to establish background

conditions. The monitoring work should be performed using equipment appropriate to measure the types of contaminants known or suspected to be present. The equipment should be calibrated at least daily for the contaminant(s) of concern or for an appropriate surrogate. The equipment should be capable of calculating 15-minute running average concentrations, which will be compared to the levels specified below.

- If the ambient air concentration of total organic vapors at the downwind perimeter of the work area or exclusion zone exceeds 5 parts per million (ppm) above background for the 15-minute average, work activities must be temporarily halted and monitoring continued. If the total organic vapor level readily decreases (per instantaneous readings) below 5 ppm over background, work activities can resume with continued monitoring.

- If total organic vapor levels at the downwind perimeter of the work area or exclusion zone persist at levels in excess of 5 ppm over background but less than 25 ppm, work activities must be halted, the source of vapors identified, corrective actions taken to abate emissions, and monitoring continued. After these steps, work activities can resume provided that the total organic vapor level 200 feet downwind of the exclusion zone or half the distance to the nearest potential receptor or residential/commercial structure, whichever is less – but in no case less than 20 feet, is below 5 ppm over background for the 15-minute average.

- If the organic vapor level is above 25 ppm at the perimeter of the work area, activities must be shutdown.

All 15-minute readings must be recorded and available for State (DEC and DOH) personnel to review. Instantaneous readings, if any, used for decision purposes should also be recorded.

Particulate Monitoring, Response Levels, and Actions

Particulate concentrations should be monitored **continuously** at the upwind and downwind perimeters of the exclusion zone at temporary particulate monitoring stations. The particulate monitoring should be performed using real-time monitoring equipment capable of measuring particulate matter less than 10 micrometers in size (PM-10) and capable of integrating over a period of 15 minutes (or less) for comparison to the airborne particulate action level. The equipment must be equipped with an audible alarm to indicate exceedance of the action level. In addition, fugitive dust migration should be visually assessed during all work activities.

- If the downwind PM-10 particulate level is 100 micrograms per cubic meter (mcg/m3) greater than background (upwind perimeter) for the 15-minute period or if airborne dust is observed leaving the work area, then dust suppression techniques must be employed. Work may continue with dust suppression techniques provided that downwind PM-10 particulate levels do not exceed 150 mcg/m3 above the upwind level and provided that no visible dust is migrating from the work area.

- If, after implementation of dust suppression techniques, downwind PM-10 particulate levels are greater than 150 mcg/m3 above the upwind level, work must be stopped and a re-evaluation of activities initiated. Work can resume provided that dust suppression measures and other controls are successful in reducing the downwind PM-10 particulate concentration to within 150 mcg/m3 of the upwind level and in preventing visible dust migration.

All readings must be recorded and be available for State (DEC and DOH) personnel to review.

Special Requirements for Work Within 20 Feet of Potentially Exposed Individuals or Structures

When work areas are within 20 feet of potentially exposed populations or occupied structures, the continuous monitoring locations for VOCs and particulates must reflect the nearest potentially exposed individuals and the location of ventilation system intakes for nearby structures. The use of engineering controls such as vapor/dust barriers, temporary negative-pressure enclosures, or special ventilation devices should be considered to prevent exposures related to the work activities and to control dust and odors. Consideration should be given to implementing the planned activities when potentially exposed populations are at a minimum, such as during weekends or evening hours in non-residential settings.

- If total VOC concentrations opposite the walls of occupied structures or next to intake vents exceed 1 ppm, monitoring should occur within the occupied structure(s). Background readings in the occupied spaces must be taken prior to commencement of the planned work. Any unusual background readings should be discussed with NYSDOH prior to commencement of the work.

- If total particulate concentrations opposite the walls of occupied structures or next to intake vents exceed 150 mcg/m3, work activities should be suspended until controls are implemented and are successful in reducing the total particulate concentration to 150 mcg/m3 or less at the monitoring point.

- Depending upon the nature of contamination and remedial activities, other parameters (e.g., explosivity, oxygen, hydrogen sulfide, carbon monoxide) may also need to be monitored. Response levels and actions should be pre-determined, as necessary, for each site.

Special Requirements for Indoor Work with Co-Located Residences or Facilities

Unless a self-contained, negative-pressure enclosure with proper emission controls will encompass the work area, all individuals not directly involved with the planned work must be absent from the room in which the work will occur. Monitoring requirements shall be as stated above under “Special Requirements for Work Within 20 Feet of Potentially Exposed Individuals or Structures” except that in this instance “nearby/occupied structures” would be adjacent occupied rooms. Additionally, the location of all exhaust vents in the room and their discharge points, as well as potential vapor pathways (openings conduits, etc.) relative to adjoining rooms, should be understood and the monitoring locations established accordingly. In these situations, it is strongly recommended that exhaust fans or other engineering controls be used to create negative air pressure within the work area during remedial activities. Additionally, it is strongly recommended that the planned work be implemented during hours (e.g. weekends or evenings) when building occupancy is at a minimum.

APPENDIX I

Site Management Forms

Summary of Green Remediation Metrics for Site Management

Site Name: 12074 Flatlands Avenue p/o Lot 1 Site Site Code: C224353
Address: 35 Inspiration Lane City: Brooklyn
State: NY Zip Code: 11236 County: Kings

Initial Report Period (Start Date of period covered by the Initial Report submittal)
Start Date: _____

Current Reporting Period
Reporting Period From: _____ To: _____

Contact Information
Preparer's Name: _____ Phone No.: _____
Preparer's Affiliation: _____

I. Energy Usage: Quantify the amount of energy used directly on-site and the portion of that derived from renewable energy sources.

	Current Reporting Period	**Total to Date**
Fuel Type 1 (e.g. natural gas (cf))		
Fuel Type 2 (e.g. fuel oil, propane (gals))		
Electricity (kWh)		
Of that Electric usage, provide quantity:		
Derived from renewable sources (e.g. solar, wind)		
Other energy sources (e.g. geothermal, solar thermal (Btu))		

Provide a description of all energy usage reduction programs for the site in the space provided on Page 3.

II. Solid Waste Generation: Quantify the management of solid waste generated on-site.

	Current Reporting Period (tons)	**Total to Date (tons)**
Total waste generated on-site		
OM&M generated waste		
Of that total amount, provide quantity:		
Transported off-site to landfills		
Transported off-site to other disposal facilities		
Transported off-site for recycling/reuse		
Reused on-site		

Provide a description of any implemented waste reduction programs for the site in the space provided on Page 3.

III. Transportation/Shipping: Quantify the distances travelled for delivery of supplies and lab-supplied bottles, shipping of laboratory samples, and the removal of waste.

	Current Reporting Period (miles)	**Total to Date (miles)**
Standby Engineer/Contractor		
Laboratory Courier/Delivery Service (bottle and sample delivery)		
Waste Removal/Hauling		

Provide a description of all mileage reduction programs for the site in the space provided on Page 3. Include specifically any local vendor/services utilized that are within 50 miles of the site.

IV. Water Usage: Quantify the volume of water used on-site from various sources.

	Current Reporting Period (gallons)	**Total to Date (gallons)**
Total quantity of water used on-site (not including treated water)		
Of that total amount, provide quantity:		
Public potable water supply usage		
Surface water usage		
On-site groundwater usage		
Collected or diverted storm water usage		

Provide a description of any implemented water consumption reduction programs for the site in the space provided on Page 3.

V. Land Use and Ecosystems: Quantify the amount of land and/or ecosystems disturbed and the area of land and/or ecosystems restored to a pre-development condition (i.e. Green Infrastructure).

	Current Reporting Period (acres)	**Total to Date (acres)**
Land disturbed		
Land restored		

Provide a description of any implemented land restoration/green infrastructure programs for the site in the space provided on Page 3.

Description of green remediation programs reported above (Attach additional sheets if needed)
Energy Usage:
Waste Generation:
Transportation/Shipping:
Water usage:
Land Use and Ecosystems:
Recommendations/Other:

CONTRACTOR CERTIFICATION
I, _____ (**Name**) do hereby certify that I am _____ (**Title**) of _____ (**Contractor Name**), which is responsible for the work documented on this form. According to my knowledge and belief, all of the information provided in this form is accurate and the site management program complies with the DER-10, DER-31, and CP-49 policies. _____ **Date** **Contractor**

SITE INSPECTION CHECKLIST

Site Name: 12074 Flatlands Avenue p/o Lot 1 Site Location: Brooklyn, NY Project Number: 100688803

Inspector Name: _____ Date: _____ Weather Conditions: _____

Reason for Inspection (i.e., routine, severe condition, etc.): _____

Check one of the following:
(Y: Yes N: No N/A: Not Applicable)

		Y	N	N/A	Normal Situation	Remarks
	General					
1	What are the current site conditions?	-	-	-		
2	Are all applicable site records (e.g., documentation of construction activity, most current easement, etc.) complete and up to date?				Y	
	Environmental Easement					
3	Has site use (Restricted-Residential) remained the same?				Y	
4	Does it appear that all environmental easement restrictions have been followed?				Y	
	Impervious Site Cover					
5	Are there any indications of a breach in the building slab, roadways, or sidewalks at the time of this inspection?				N	
6	Are there any cracks in the building slab, roadways, or sidewalks?				N	
7	Are there any cracks in the basement walls?				N	
8	Is there any construction activity, or indication of any construction activity within the past certification year (including any tenant improvements), that included the breaching of the building slab, roadways, or sidewalks on-site at the time of this inspection?				N	
9	If YES to number 8, is there documentation that the Soil Management Plan, HASP, and CAMP for the site was/is being followed?					

***** If the answer to any of the above questions indicate non-compliance with any Institutional Controls (ICs) for the site, additional remarks must be provided and, where applicable, documentation attached to this checklist detailing additional inspection and repair activities.**

Additional remarks: _____

Minimum Inspection Schedule:

- Site-wide inspections will be conducted annually, per certification year, at a minimum.
- Additional inspections will also be conducted at times of severe weather condition events.
- All inspection events will use this checklist.

LOW FLOW SAMPLING FIELD PARAMETER MEASUREMENTS

Project:	12074 Flatlands Avenue p/o Lot 1 Site	**Site Location:**	35 Inspiration Lane, Brooklyn, NY	**Well No:**	**Date:**
Job Number:	100688803	**Weather:**		**Sampler(s):**	
Initial DTW (ft):		**Well Depth (ft):**		**Pump Depth (ft):**	
Background PID (ppm):		**Well PID (ppm):**		**Screen Interval (ft):**	
Water Quality Meter:		**Water Quality Meter ID:**			

TIME	TEMP. °C	pH (std. Units)	ORP (mV)	COND. (mS/cm)	Turbidity (NTU)	DO (mg/L)	DTW (ft)	Q (mL/m)	NOTES color, odor etc.
		+/- 0.1 pH	+/- 10 mV	+/- 3%	+/- 10 NTU	+/- 10%	<0.3' drawdown		

Notes:

Sample Number:		Sample Time:		Sample Analyses:	
QA/QC Sample Number:		QA/QC Sample Time:		A/QC Sample Analyses:	

LANGAN

APPENDIX J

Remedial System Optimization Report Outline

LANGAN

REMEDIAL SYSTEM OPTIMIZATION REPORT

TABLE OF CONTENTS

1.0 INTRODUCTION

1.1 SITE OVERVIEW

1.2 PROJECT OBJECTIVES AND SCOPE OF WORK

1.3 REPORT OVERVIEW

2.0 REMEDIAL ACTION DESCRIPTION

2.1 SITE LOCATION AND HISTORY

2.2 REGULATORY HISTORY AND REQUIREMENTS

2.3 CLEAN-UP GOALS AND SITE CLOSURE CRITERIA

2.4 PREVIOUS REMEDIAL ACTIONS

2.5 DESCRIPTION OF EXISTING REMEDY

2.5.1 System Goals and Objectives

2.5.2 System Description

2.5.3 Maintenance Program

3.0 FINDINGS AND OBSERVATIONS

3.1 SYSTEM PERFORMANCE

3.2 REGULATORY COMPLIANCE

3.3 MAJOR COST COMPONENTS OR PROCESSES

3.4 SAFETY RECORD

4.0 RECOMMENDATIONS

4.1 RECOMMENDATIONS TO ACHIEVE OR ACCELERATE SITE CLOSURE

4.1.1 Source Reduction/Treatment

4.1.2 Sampling

4.1.3 Conceptual Site Model (Risk Assessment)

4.2 RECOMMENDATIONS TO IMPROVE PERFORMANCE

4.2.1 Maintenance Improvements

4.2.2 Monitoring Improvements

4.2.3 Process Modifications

4.3 RECOMMENDATIONS TO REDUCE COSTS

4.3.1 Supply Management

4.3.2 Process Improvements or Changes

4.3.3 Optimize Monitoring Program

4.3.4 Maintenance and Repairs

4.4 RECOMMENDATIONS FOR IMPLEMENTATION