260 West 126th Street
Remedial Investigation Report

260 West 126th Street
New York, New York
Block 1931, Lot 56
BCP Site No. C231164

Submitted to:
New York State Department of Environmental Conservation
Division of Environmental Remediation
625 Broadway, 12th Floor
Albany, NY 12233

Prepared for:
S & F 126 ST. LLC
320 Roebling Street, Suite 749
Brooklyn, NY 11211

Prepared by:

TENEN ENVIRONMENTAL
465 East 188th Street, #112
Bronx, NY 10458

September 2026

TABLE OF CONTENTS

1.0 INTRODUCTION 4
1.1 Report Organization 5
2.0 BACKGROUND AND SETTING 6
2.1 Site Description and Surrounding Uses 6
2.2 Site Characteristics 7
2.3 Site History and Historic Operations 7
2.4 Regulatory Interaction 8
3.0 PREVIOUS ENVIRONMENTAL INVESTIGATIONS 9
4.0 REMEDIAL INVESTIGATION SCOPE OF WORK 12
4.1 Soil Sampling 12
4.1.1 Soil Sampling Scope of Work 12
4.1.2 Soil Sampling Methodology 12
4.2 Soil Vapor Sampling 14
4.2.1 Soil Vapor Sampling Scope of Work 14
4.2.2 Soil Vapor Sampling Methodology 14
4.3 Groundwater Sampling 15
4.3.1 Groundwater Well Installation and Sampling 16
4.4 Quality Assurance / Quality Control (QA/QC) 17
4.5 Deviations from the Remedial Investigation Work Plan 17
5.0 INVESTIGATION RESULTS 19
5.1 Field Observations 19
5.2 Analytical Results 19
5.2.1 Soil 19
5.2.2 Groundwater 23
5.2.3 Soil Vapor 24
6.0 QUALITATIVE EXPOSURE ASSESSMENT 27
6.1 Contaminant Sources 27
6.2 Contaminant Release and Transport Mechanisms 27
6.3 Potential Receptor Populations 28
6.4 Potential Routes and Points of Exposure 28
6.5 Summary of Qualitative Exposure Assessment 29
7.0 SUMMARY 31
7.1 Soil 31

7.2 Groundwater 31
7.3 Soil Vapor 31
7.4 Recommendations 31
8.0 REFERENCES 32

Figures

Figure 1 – Site Location Map
Figure 2 – Site Boundary Map
Figure 3 – Groundwater Contour Map
Figure 4 – Historic Sample Locations – 2016 EBC RI
Figure 5 – Historic Soil Concentrations – 2016 EBC RI
Figure 6 – Historic Groundwater Concentrations – 2016 EBC RI
Figure 7 – Historic Soil Vapor Concentrations – 2016 EBC RI
Figure 8 – RI Sample Locations
Figure 9 – Soil Analytical Results
Figure 10 – Groundwater Analytical Results
Figure 11 – Soil Vapor Analytical Results
Figure 12 – Geologic Cross-Section
Figure 13 – Sensitive Receptor Map

Tables

Table 1 – Summary of Historic Soil Sample Exceedances
Table 2 – Summary of Historic Groundwater Sample Exceedances
Table 3 – Summary of Volatile Organic Compounds in Historic Soil Vapor Samples
Table 4a – Volatile Organic Compounds in Soil
Table 4b – Semivolatile Organic Compounds in Soil
Table 4c – Total Metals in Soil
Table 4d – Pesticides, Herbicides, and Polychlorinated Biphenyls in Soil
Table 4e – Emerging Contaminants in Soil
Table 5a – Volatile Organic Compounds in Groundwater
Table 5b – Semivolatile Organic Compounds in Groundwater
Table 5c – Total and Dissolved Metals in Groundwater
Table 5d – Pesticides, Herbicides, and Polychlorinated Biphenyls in Groundwater
Table 5e – Emerging Contaminants in Groundwater
Table 6 – Volatile Organic Compounds in Soil Vapor

Appendices

Appendix A – Previous Reports (Submitted Under Separate Cover)
Appendix B – Laboratory Data Packages and Data Usability Summary Report (Submitted Under Separate Cover)
Appendix C – Community Air Monitoring Plan (CAMP) Results
Appendix D – Soil Boring and Monitoring Well Construction Logs
Appendix E – Monitoring Well Purging and Sampling Logs and Monitoring Well Survey
Appendix F – Soil Vapor Sampling Logs

CERTIFICATION

I, Mohamed Ahmed, certify that I am currently a Qualified Environmental Professional as defined in 6 NYCRR Part 375 and that this Remedial Investigation Report was prepared in accordance with all applicable statutes and regulations and in substantial conformance with the DER Technical Guidance for Site Investigation and Remediation (DER-10) and DER Green Remediation (DER-31) and that all activities were performed in full accordance with the DER-approved work plan and any DER-approved modifications.

DRAFT _____ _____

Mohamed Ahmed, PG Date

LIST OF ACRONYMS

AGV	NYSDOH Air Guidance Value
AOC	area of concern
AA	Ambient Air
AS	air sparging
BCA	Brownfield Cleanup Agreement
BCP	Brownfield Cleanup Program
ECL	Environmental Conservation Law
BTEX	benzene, toluene, ethylbenzene and xylenes
CAMP	Community Air Monitoring Program
C&D	construction and demolition
CDS	construction dewatering system
Class GA Standards	NYSDEC TOGS 1.1.1 Class GA Ambient Water Quality Standards and Guidance Values
CEQR	City Environmental Quality Review
CFR	Code of Federal Regulations
CPP	Citizen Participation Plan
COC	Certificate of Completion
DCE	Dichloroethylene
DER-10	NYSDEC Division of Environmental Remediation (DER), DER-10 / Technical Guidance for Site Investigation and Remediation
DRO	diesel range organics
DOC	dissolved organic carbon
DUSR	Data Usability Summary Report
EC	Engineering Control
ESA	Environmental Site Assessment
EZ	exclusion zone
FB	field blanks
FER	Final Engineering Report
ft-bsg	feet below sidewalk grade
ft-bg	feet below existing grade
ft-msl	feet above mean sea level
GPM	Gallons per minute
HASP	Health and Safety Plan
HSA	Hollow Stem Auger
HSO	Health and Safety Officer
IA	Indoor Air
IC	Institutional Control
ISCO	*in-situ* chemical oxidation
IRM	Interim Remedial Measure
MW	monitoring well
NAVD	North American Vertical Datum of 1988
NGVD	National Geodetic Vertical Datum of 1929
NIOSH	National Institute for Occupational Safety and Health
NYCDEP	New York City Department of Environmental Protection
NYCDEP Limits	NYCDEP Limitations for Effluent to Sanitary or Combined Sewers
NYCDOB	New York City Department of Buildings
NYCDOT	New York City Department of Transportation

NYCRR	New York Codes, Rules and Regulations
NYSDEC	New York State Department of Environmental Conservation
NYSDOH	New York State Department of Health
NYSDOH-ELAP	NYSDOH Environmental Laboratory Approval Program
O&M Plan	Operations and Maintenance Plan
OSHA	Occupational Safety and Health Association
PCB	polychlorinated biphenyl
PCE	perchloroethylene, aka tetrachloroethylene
PID	photoionization detector
PGWSCOs	6 NYCRR 375-6.8(b) and CP-51 Protection of Groundwater Soil Cleanup Objectives
PP Metals	Priority Pollutant Metals
PPE	personal protective equipment
QA/QC	quality assurance / quality control
QAPP	Quality Assurance Project Plan
RAWP	Remedial Action Work Plan
RIWP	Remedial Investigation Work Plan
RI	Remedial Investigation
RIR	Remedial Investigation Report
RCNY	Rules of the City of New York
RAO	Remedial Action Objective
RE	Remedial Engineer
RSCOs	Recommended Soil Cleanup Objectives
RCSCOs	6 NYCRR 375-6.8(b) and CP-51 Track 2 – Restricted Commercial Use Soil Cleanup Objectives
SB	soil boring
SCGs	Standards, Criteria and Guidance
SV	soil vapor
SMP	Site Management Plan
SMMP	Soil/Material Management Plan
SSDS	sub-slab depressurization system
SVE	soil vapor extraction
SVOC	semi-volatile organic compound
TAL	Target Analyte List
TAGM 4046	NYSDEC Technical and Administrative Guidance Memorandum #4046
TB	trip blanks
TCE	Trichloroethylene
TCL	Target Compound List
TCLP	Toxicity Characteristic Leaching Procedure
TCLP Limits	USEPA Maximum Concentrations of Contaminants for the Toxicity Characteristic
TOC	total organic carbon
USEPA	United States Environmental Protection Agency
USGS	United States Geological Survey
UST	underground storage tank
UUSCOs	6 NYCRR 375-6.8(a) Track 1 Unrestricted Use Soil Cleanup Objectives
VOC	volatile organic compound

1.0 INTRODUCTION

On behalf of S & F 126 ST. LLC (the "Volunteer"), Tenen Environmental, LLC (Tenen) has prepared this Remedial Investigation Report (RIR) for the property located at 260 West 126th Street (Block 1931, Lot 56) in the Borough of Manhattan, New York City, New York (the "Site"). The Site location and boundaries are identified on Figures 1 and 2, respectively. This RIR presents the methodology and findings of the Remedial Investigation (RI) conducted in accordance with the December 2025 Remedial Investigation Work Plan (RIWP), which was approved by the New York State Department of Environmental Conservation (NYSDEC).

The objective of the RI was to further investigate and characterize the nature and extent of contamination previously identified on the Site. The scope of work included investigation of subsurface soils, soil vapor and groundwater in areas where historical operations potentially impacted the Site or surrounding areas.

RI activities were conducted in January, June, and July 2026. The results of this investigation were used to prepare the qualitative exposure assessment (QEA) included in Section 6.0 of this RIR. This RIR has been prepared in accordance with the NYSDEC Division of Environmental Remediation (DER) Technical Guidance for Site Investigation and Remediation (DER-10, May 3, 2010).

A prior Remedial Investigation performed in 2016 and detailed in Section 3, has confirmed the presence of onsite contamination. Specifically, the prior Site investigation has identified: (i) metals at concentrations above applicable regulatory standards in soil and groundwater, (ii) polycyclic aromatic hydrocarbons (PAHs) at concentrations above applicable regulatory standards in groundwater and soil, and (iii) concentrations of chlorinated solvents and petroleum-related VOCs in soil vapor. Soil is impacted with PAHs and metals consistent with the presence of historic fill material typically found in New York City. Previous investigations indicate that a layer of historic fill material exists across the Site, extending to at least twelve feet below grade (ft-bg).

Based on the above, Tenen determined that further investigation would be required to characterize the nature and extent of soil, groundwater and soil vapor contamination on the Site to determine if contaminant levels related to historic fill material and historic operations on surrounding properties are a threat to public health and/or the environment. To fully characterize the Site, the following investigatory tasks were completed in January, June, and July 2026 in accordance with the approved NYSDEC-approved RIWP:

- Soil borings were advanced at nine onsite locations.
- A total of 29 soil samples (including quality assurance/quality control [QA/QC] samples) were collected at depths ranging from 0 to 24 ft-bg and analyzed for volatile organic compounds (VOCs), semivolatile organic compounds (SVOCs), Target Analyte List (TAL) metals, pesticides, herbicides, polychlorinated biphenyls (PCBs), total cyanide, trivalent/hexavalent chromium, 1,4-dioxane and per- and polyfluoroalkyl substances (PFAS).
- Six permanent groundwater monitoring wells were installed. Groundwater samples were collected from six newly installed wells and analyzed for VOCs, SVOCs, total and dissolved metals, pesticides, herbicides, PCBs, total cyanide, trivalent/hexavalent chromium, 1,4-dioxane and PFAS.
- Soil vapor samples were collected from seven locations across the Site and analyzed for VOCs. Two ambient air samples were collected and analyzed for VOCs (one per soil vapor sampling event).

The analytical results of the RI sampling confirmed the presence of heavy metals, primarily barium, lead, mercury, manganese, and hexavalent chromium, in soil at the Site, likely due to historic filling at the Site. The bulk of the metals contamination in soil is in the shallow (0-2 ft-bg) sampling interval. The analytical results of the RI sampling also confirmed the presence of historic fill-related SVOCs in exceedance of applicable standards in shallow (0-2 ft-bg) soil at the Site. Pesticides were detected in two soil samples collected at 0-2 ft-bg and 10-12 ft-bg in exceedance of applicable standards. PFAS, specifically perfluorooctane sulfonic acid (PFOS), was detected in exceedance of applicable guidance values in two shallow (0-2 ft-bg) soil samples and one duplicate sample. Two PFAS analytes, PFOS and perfluorooctanoic acid (PFOA), were also detected in groundwater across the Site in exceedance of applicable regulatory standards. SVOCs and heavy metals detected in exceedance of applicable regulatory standards in the 2016 Remedial Investigation were not detected in exceedance of applicable regulatory standards in groundwater during Tenen's 2026 RI. The SVOC and heavy metals exceedances in previous groundwater sampling events are likely due to turbidity in the samples due to sampling being conducted with temporary, one-inch diameter monitoring wells. All wells sampled during this RI were two-inch diameter, were developed following installation, and were purged until turbidity of less than 50 NTU was achieved and/or water quality measurement readings were stabilized. Chlorinated solvents and petroleum-related VOCs were detected at low concentrations in soil vapor at the Site. Chlorinated solvents and petroleum-related VOCs were generally not detected or detected at very low concentrations in soil and groundwater at the Site. Therefore, it is Tenen's opinion that the minor chlorinated solvent and petroleum-related VOC impacts to soil vapor are generally due to one or more offsite sources.

1.1 Report Organization

This RIR details the findings of the RI tasks completed by Tenen in January, June, and July 2026, including soil, groundwater and soil vapor sampling. The RI data was used to characterize the current environmental conditions at the Site. Data from prior investigations has also been summarized. This RIR is organized as follows:

- Section 1 – Introduction
- Section 2 – Background and Setting
- Section 3 – Previous Environmental Investigations
- Section 4 – Remedial Investigation Scope of Work
- Section 5 – Investigation Results
- Section 6 – Qualitative Exposure Assessment
- Section 7 – Summary
- Section 8 – References

Supporting tables, figures and appendices referenced throughout are included at the end of this report. As required by NYSDEC Division of Environmental Remediation (DER) Technical Guidance for Site Investigation and Remediation (DER-10) Section 3.13(c), the electronic data summary (EDS), including results of all analyses associated with the RI was submitted to NYSDEC on September 17, 2026 and was accepted by NYSDEC on the same day. Data usability summary reports (DUSRs) and laboratory deliverables for all samples collected during the RI are included in Appendix B.

2.0 BACKGROUND AND SETTING

This section includes a description of the Site and adjacent and surrounding area uses, and summaries of Site characteristics, historic operations and regulatory interactions.

2.1 Site Description and Surrounding Uses

The Site, located at 260 West 126th Street, New York, New York (Borough of Manhattan, Tax Block 1931, Lot 56), is a rectangular-shaped parcel located on the southern side of West 126th Street, between Frederick Douglass Boulevard (formerly Eighth Avenue) and Adam C. Powell Boulevard, in the Harlem section of Manhattan. The Site is approximately 12,490 square feet (SF) and has approximately 125 feet of frontage along West 126th Street and is approximately 100 feet deep. The Site is bounded to the north by West 126th Street, a 60-foot wide public right of way, and to the south and east by the Apollo Theater, an individually designated New York City landmark. The properties adjoining the Site to the north and west are improved with mixed commercial and residential buildings. Land use in the surrounding area is predominantly commercial and residential, with the 125th Street commercial corridor located one block south of the Site.

The Site was most recently developed with a two-story church building with a full cellar level covering approximately 2,725 SF of the western portion of the property. The church building was demolished in June 2026 to accommodate implementation of the RIWP. The basement slab was left intact following the demolition at the request of NYSDEC. The basement of the church building extended to approximately 10 feet below sidewalk grade (ft-bsg) and was partially backfilled immediately following demolition above the basement slab with construction and demolition (C&D) debris generated from the building demolition. The proposed soil, groundwater, and soil vapor sample locations in the NYSDEC-approved RIWP within the basement footprint were not backfilled, and ramps for Geoprobe access to the sampling locations were created with the C&D material used as backfill in the remainder of the building footprint. All soil, soil vapor and groundwater sampling within the former building footprint was completed on July 9, 2026. Final backfilling of the entire building footprint to grade with C&D material was completed on July 21, 2026. The remainder of the property is a partially paved, vacant parking lot.

The Site lot is zoned C4-4D, denoting a commercial contextual district that has bulk and density regulations and also allows for some residential uses. Site location, layout and surrounding property usage are depicted on Figures 1 and 2, and sensitive receptors in the vicinity of the Site are identified in Section 6.3 and shown on Figure 13.

Anticipated Redevelopment Plans

The Site is proposed for redevelopment with a 14-story mixed-use building containing residential dwelling units, commercial and community facility space, and cellar level parking. Based on present design and plans, the redevelopment will include approximately 20-25 affordable residential units (approximately 30%) at 80% area median income (AMI) utilizing the Voluntary Inclusionary Housing (VIH) and 421-a programs. The proposed cellar occupies the full lot area. Based on the New York City Department of Buildings (NYC DOB) approved support of excavation (SOE) and foundation drawings, excavation will extend to approximately 12 feet below existing grade across the majority of the Site, locally deeper at the core mat and elevator pit, and to approximately 3.6 feet below grade beneath the caisson supported mat strips along the Apollo

Theater and along West 126th Street. Foundation support is provided by caissons socketed into bedrock.

2.2 Site Characteristics

Site Topography

Based on the U.S. Geological Survey (USGS 7.5 Minute Topographic Quadrangles: Central Park, NY) topographic map, the Site is located at an elevation of approximately 32 feet above mean sea level (msl) and is relatively flat.

Site Geology and Hydrogeology

The Site outside of the former building footprint is underlain by a historic fill layer (sand, ash, gravel, asphalt and brick fragments) extending to depths ranging from five to 12.5 ft-bsg. The western portion of the Site in the former building footprint is underlain by a historic fill layer (sand, silt, gravel, concrete and brick fragments) extending to depths ranging from 20 to 22 ft-bsg. Native brown, medium- to coarse-grained sand with gravel and cobbles underlies the fill layers to a depth of at least 30 ft-bsg. Bedrock was not encountered in any soil boring or monitoring well advanced during the RI, the deepest of which extended to 30 ft-bsg. Depth to bedrock is anticipated at greater than 100 feet below grade. A geologic cross-section is included as Figure 12.

Depth to groundwater at the Site was measured during the RI at depths ranging from 22.15 to 24.40 ft-bsg in monitoring wells installed across the Site. Groundwater beneath the Site occurs under unconfined conditions within the native sand. The groundwater contours generated indicate a hydraulic gradient across the Site toward the southeast, converging in the southeastern portion of the Site in the vicinity of monitoring wells MW-2 and MW-6. The regional gradient in this part of Manhattan would be expected to trend easterly toward the Harlem River. The local deflection toward the southeast is attributed to the influence of sub-grade structures on and immediately adjacent to the Site. The nearest subway line is located two blocks east of the Site along Malcolm X Boulevard and, due to that distance, is not expected to influence groundwater flow at the Site.

Depth-to-water measurements were collected from monitoring wells MW-1, MW-2, MW-3 and MW-6 on January 22, 2026 and from monitoring wells MW-4 and MW-5 on July 9, 2026, on the dates each group of wells was sampled. During the mobilization on July 9, 2026, monitoring wells MW-1, MW-2, MW-3, and MW-6 could not be located in the field. It is assumed that these wells were destroyed during the demolition of the onsite building.

2.3 Site History and Historic Operations

The Site lot has been developed since at least 1902. In 1902, the Site lot was divided into six separate tax parcels with six tightly grouped four-story residential buildings present on the north side of the Site, along West 126th Street. By 1951, the six residential buildings had been demolished. A four-story storefront building used for lumber storage occupied the western portion of the Site, and the remainder of the Site was undeveloped. The four-story storefront building was subsequently demolished and, by 1962, had been replaced on the same western portion of the Site by the two-story church building with a full cellar level described in Section 2.1. From 1962 until 2026 the Site remained substantially unchanged, with the church building on the western portion of the Site and licensed parking on the eastern portion of the Site.

The church building was demolished in June 2026 and the licensed parking use of the eastern portion of the Site was discontinued. As of June 2026, the site remains vacant. The Site is not currently in active use and is enclosed by a gated and locked construction fence.

2.4 Regulatory Interaction

A BCP application was submitted for the Site in July 2025. Following a 30-day public comment period, a Brownfield Cleanup Agreement (BCA) was executed by the Volunteers and NYSDEC on December 1, 2025. The RIWP, including a Health and Safety Plan, was approved by NYSDEC on December 15, 2025. The Citizen Participation Plan (CPP) was approved by NYSDEC on January 2, 2026.

3.0 PREVIOUS ENVIRONMENTAL INVESTIGATIONS

The following environmental investigations were previously conducted at the Site:

- *Phase I Environmental Site Assessment Report, 260 West 126th Street, New York, NY, Environmental Business Consultants, October 2016.*
- *Remedial Investigation Report, 260 West 126th Street, New York, NY, Environmental Business Consultants, December 2016.*

The findings of the above investigations are summarized below. A geophysical investigation was not conducted at the Site during any previous environmental investigations. Previous soil, groundwater and soil vapor results are depicted on Tables 1 through 3 and on Figures 4 through 7, respectively. The referenced reports are provided in Appendix A, Previous Reports, which is submitted under separate cover, together with the laboratory deliverables for the previous analytical data. The NYSDEC-approved RIWP is available on the NYSDEC DECinfo Locator and in the Site document repositories and is therefore not reproduced in this RIR.

Phase I Environmental Site Assessment Report, 260 West 126th Street, New York, NY, Environmental Business Consultants, October 2016.

A Phase I ESA was completed for the Site by EBC in October 2016 on behalf of Velocity Framers of Brooklyn, New York. The Phase I ESA did not identify any Recognized Environmental Conditions (RECs) in connection with the Site. However, EBC did identify three other environmental concerns (non-RECs), which are summarized as follows:

- The Site has an E-Designation (E-201) for Hazardous Materials, Noise, and Air as a result of the 125th Street Corridor Rezoning and Related Actions. The HazMat E-Designation required a Phase I and Phase II Testing Protocol. The Air E-Designation requires that any new residential and/or commercial development must endure that the heating, ventilation and air conditioning (HVAC) stacks are located at least 79 and 63 feet for No. 4 fuel oil and No. 2 fuel oil from the lot lines, respectively, or use natural gas as the type of fuel for space heating and hot water systems to avoid any potential significant adverse air quality impacts. The Noise E-Designation required a 40 dBA attenuation level for indoor spaces.
- Due to the age of the onsite building, the potential for the presence of asbestos-containing materials (ACMs) is considered likely. Specifically, asphaltic roofing materials, adhesives, plasters, and exterior use caulks commonly contain asbestos in older and newer buildings alike. EBC recommended conducting an ACM survey to identify building materials and components with asbestos content prior to demolition or disturbance.
- Due to the age of the onsite building, the potential for the presence of lead-based paint (LBP) is also considered likely. No significant damaged or peeling paints were identified; however, LBP may be present in hidden or inaccessible portions of the Site. Additionally, no children currently reside at the Site, which greatly reduces the risks associated with the potential presence of LBP. EBC recommended conducting a lead survey to evaluate the presence of LBP at the Site prior to demolition or disturbance.

Remedial Investigation Report, 260 West 126th Street, New York, NY, Environmental Business Consultants, December 2016.

The November 2016 RI was conducted by EBC on behalf of Velocity Framers in accordance with the requirements of the NYC OER E-Designation program and consisted of the installation of eight soil borings, the collection of 17 soil samples (including QA/QC samples), the installation of four groundwater monitoring wells, the collection of four groundwater samples (including QA/QC samples), the installation of five soil vapor points, and the collection of five soil vapor samples (one sub-slab soil vapor sample and four exterior soil vapor samples). All soil and groundwater samples collected during the November 2016 RI were analyzed for VOCs, SVOCs, target analyte list (TAL) metals (total metals only for groundwater), pesticides, and PCBs and all soil vapor samples collected during the RI were analyzed for TO-15 VOCs. The results of the November 2016 RI are detailed below:

Soil

Soil results were compared to the December 31, 2025 updated 6 NYCRR Part 375 Unrestricted Use Soil Cleanup Objectives (SCOs, UUSCOs) and Restricted-Residential Use SCOs (RRSCOs) as listed in 6 NYCRR Part 375-6.8(a) and (b). UUSCOs are the most stringent cleanup standards and are used as comparison for site-specific proposed cleanup standards. The RRSCOs are consistent with the assumed future use of the Site.

Soil sampling indicated the following:

- Several SVOCs, most notably PAHs, were detected in one shallow (0-2 ft-bg) soil sample collected from the parking lot at concentrations exceeding the UUSCOs, with one PAH, benzo(a)pyrene, also exceeding its RRSCO. Total SVOCs were detected at a max. concentration of 13.07 parts-per-million (ppm).
- A variety of metals, including arsenic, barium, copper, chromium, lead, mercury, nickel, and zinc, were detected in shallow (0-2 ft-bg) and deep (10-12 ft-bg) soil samples across the Site in exceedance of UUSCOs. Of these, barium (max. 2,760 ppm) and lead (max. 2,040 ppm) were each detected in four shallow (0-2 ft-bg) and one deep (10-12 ft-bg) soil samples at concentrations exceeding their respective RRSCOs, and mercury (max. 0.75 ppm) was detected in three shallow (0-2 ft-bg) and three deep (10-12 ft-bg) soil samples at concentrations exceeding the RRSCO.
- Two pesticides, 4,4'-DDE and 4,4'-DDT, were detected in exceedance of their respective UUSCOs in three shallow (0-2 ft-bg) and one intermediate (2-4 ft-bg) soil samples, with the highest concentrations occurring in the shallow sample collected from the northeastern corner of the Site. 4,4'-DDE was detected at a max. concentration of 0.022 ppm and 4,4'-DDT was detected at a concentration of 0.025 ppm. Pesticides were not detected in exceedance of RRSCOs in any soil samples.
- Volatile organic compounds (VOCs) and polychlorinated biphenyls were not detected in exceedance of UUSCOs or RRSCOs in any soil samples.

Groundwater

Groundwater results were compared to NYSDEC Technical and Operational Guidance Series (TOGS) 1.1.1 Ambient Water Quality Standards (AWQS) and Guidance Values (Class GA Standards).

Groundwater sampling indicated the following:

- A variety of SVOCs, specifically PAHs, were detected slightly in exceedance of Class GA Standards in groundwater samples collected from the southern portion of the Site.
- A variety of metals, including arsenic, barium, beryllium, cadmium, chromium, copper, iron, lead, magnesium, manganese, nickel, sodium, and thallium were detected in exceedance of Class GA Standards in unfiltered groundwater samples collected across the Site. Filtered groundwater samples were not analyzed as part of the 2016 RI.
- VOCs, pesticides, and PCBs were not detected in exceedance of Class GA Standards in any groundwater samples.

Soil Vapor

One sub-slab soil vapor sample was collected at six inches below grade (in-bg) within the onsite building and four exterior soil vapor samples were collected at 12 ft-bg across the Site. The results of the soil vapor sampling indicated the following:

- Chlorinated VOCs (cVOCs) were detected in soil vapor across the Site, specifically tetrachloroethene (PCE), trichloroethene (TCE), and carbon tetrachloride. PCE was detected at a concentration of 11.3 micrograms per cubic meter (ug/m3) in the sub-slab soil vapor sample and at a max. concentration of 16.5 ug/m3 in exterior soil vapor; TCE was detected at a concentration of 0.38 ug/m3 in the sub-slab soil vapor sample and at a max. concentration of 0.62 ug/m3 in exterior soil vapor; and, carbon tetrachloride was detected at a concentration of 0.52 ug/m3 in the sub-slab soil vapor sample and at a max. concentration of 0.35 ug/m3 in exterior soil vapor. In general, the highest concentrations of cVOCs were detected in the exterior soil vapor sample collected from the southern portion of the parking lot, along the southern perimeter of the Site.
- A variety of petroleum-related VOCs were detected in sub-slab soil vapor and exterior soil vapor across the Site, including benzene, toluene, ethylbenzene, p/m-xylene, o-xylene, 1,2,4-trimethylbenzene, 1,3,5-trimethylbenzene, heptane, styrene, cyclohexane, and propylene. Total BTEX concentrations ranged from 20.58 ug/m3 to 41.44 ug/m3. Of the BTEX compounds, the highest concentration was detected for toluene at 16.5 ug/m3. In general, the highest concentrations of petroleum-related VOCs were detected in the southern portions of the onsite building and parking lot.

4.0 REMEDIAL INVESTIGATION SCOPE OF WORK

The RI, as described in the NYSDEC-approved RIWP and Section 1.0 of this RIR, included the installation and sampling of soil borings, soil vapor sampling points and monitoring wells. A Community Air Monitoring Program (CAMP) was instituted during all ground-intrusive activities. CAMP results are included in Appendix C.

The field activities were conducted in January, June, and July 2026. A subsurface utility mark-out was completed at the Site prior to the start of intrusive work. A geophysical investigation (i.e., ground penetrating radar) was not conducted as part of the RI.

4.1 Soil Sampling

4.1.1 Soil Sampling Scope of Work

The following scope of work was proposed to further investigate previously detected contamination in the soil and to vertically and horizontally delineate its extent across the Site.

A subsurface soil investigation was performed on January 5 and 6, 2026 outside of the former building footprint and on June 26, 2026 within the former building footprint; the scope of work consisted of the following:

- Installation of nine soil borings (SB-1 through SB-9) to 30 feet below sidewalk grade (ft-bsg). This was accomplished by installing soil borings SB-1, SB-2, SB-3, SB-5, SB-6, SB-8, and SB-9 to approximately 30 ft-bg, and installing soil borings SB-4 and SB-7 to approximately 20 feet below basement grade;
- Collection of 27 soil samples: three from each soil boring (SB-1 through SB-9). Soil samples were collected from grade to two ft-bg, from the two foot interval of native soil layer directly below the historic fill material, and from the two foot interval directly above the groundwater interface from each boring, with the exception of SB-4, from which the third soil sample was collected from the one foot interval directly above the groundwater interface. Two sets of quality assurance/quality control (QA/QC) samples (duplicate, field blank, and MS/MSD) were also collected; and,
- Analyzed all soil samples for VOCs, SVOCs, pesticides, herbicides, PCBs, TAL metals (including total cyanide, tri- and hexavalent chromium), per- and polyfluoroalkyl substances (PFAS), and 1,4-dioxane.

4.1.2 Soil Sampling Methodology

A direct-push track-mounted Geoprobe® was used to advance all soil borings (SB-1 through SB-9). The sampling methodology is detailed below.

In general, selected soil intervals were screened between grade and the terminal depth of the boring. All soil borings were advanced to approximately 30 ft-bsg (30 ft-bg for soil borings SB-1, SB-2, SB-3, SB-5, SB-6, SB-8, and SB-9, and 20 feet below basement grade for soil borings SB-4 and SB-7). At all soil boring locations, the collected soil volumes were screened with a photoionization detector (PID) and visual [e.g., source areas – sumps, floor drains, stains, sheens, blebs, presence of non-aqueous phase liquid (NAPL)] and olfactory observations were recorded in boring logs [Appendix D]. If evidence of VOC impacts were detected and drilling conditions allowed, the borehole was extended vertically until no impacts were detected. The full extent of each boring was

screened, and samples were collected based upon field observations and readings. At each soil boring, three soil samples were collected: one from grade to two ft-bg, one from the two foot interval of native soil layer directly below the historic fill material, and one from the two foot interval directly above the groundwater interface, with the exception of SB-4, from which the third soil sample was collected from the one foot interval directly above the groundwater interface.

Samples were collected in laboratory-supplied glass jars and were sealed, labeled, and placed in a cooler containing ice (to maintain a temperature of approximately 4 degrees Celsius) for delivery to York Analytical Laboratories, a New York State Department of Health (NYSDOH) Environmental Laboratory Accreditation Program (ELAP)-certified analytical laboratory. All soil samples collected from soil characterization borings were analyzed for TCL VOCs, TCL SVOCs, pesticides, herbicides, PCBs, TAL Metals (including total cyanide, trivalent and hexavalent chromium) 1,4-dioxane and PFAS with a Category B deliverable package.

The table below summarizes the sample designations of all analyzed samples, locations and depths.

Sample Designation (depth in ft-bg.)	Sample Depth (ft-bg)	Sample Location
SB-1 (0-2)	0-2	Northeast corner of the lot
SB-1 (6-8)	6-8	Northeast corner of the lot
SB-1 (21-23)	21-23	Northeast corner of the lot
SB-2 (0-2)	0-2	Southeast corner of the lot
SB-2 (0-2)_DUP[1]	0-2	Southeast corner of the lot
SB-2 (6-8)	6-8	Southeast corner of the lot
SB-2 (22-24)	22-24	Southeast corner of the lot
SB-3 (0-2)	0-2	Central western portion of the lot
SB-3 (8-10)	8-10	Central western portion of the lot
SB-3 (22-24)	22-24	Central western portion of the lot
SB-4 (0-2)	0-2	Southwest corner of the lot, in the former building footprint
SB-4 (12-14)	12-14	Southwest corner of the lot, in the former building footprint
SB-4 (14-15)	14-15	Southwest corner of the lot, in the former building footprint
SB-5 (0-2)	0-2	Northwestern portion of the lot
SB-5 (12.5-14.5)	12.5-14.5	Northwestern portion of the lot
SB-5 (22-24)	22-24	Northwestern portion of the lot
SB-5 (22-24) _DUP[1]	22-24	Northwestern portion of the lot
SB-6 (0-2)	0-2	Southwestern portion of the lot
SB-6 (8-10)	8-10	Southwestern portion of the lot
SB-6 (22-24)	22-24	Southwestern portion of the lot
SB-7 (0-2)	0-2	Northwest corner of the lot, in the former building footprint
SB-7 (10-12)	10-12	Northwest corner of the lot, in the former building footprint
SB-7 (12-14)	12-14	Northwest corner of the lot, in the former building footprint
SB-8 (0-2)	0-2	Southeastern portion of the lot
SB-8 (8-10)	8-10	Southeastern portion of the lot

Sample Designation (depth in ft-bg.)	Sample Depth (ft-bg)	Sample Location
SB-8 (22-24)	22-24	Southeastern portion of the lot
SB-9 (0-2)	0-2	Central eastern portion of the lot
SB-9 (6-8)	6-8	Central eastern portion of the lot
SB-9 (22-24)	22-24	Central eastern portion of the lot

[1] Duplicate sample.

A record of each sample, including PID readings, notation of any odors, color, and other observations of the sample matrix, was kept in the sampler's field logbook. A chain of custody was maintained throughout the field sampling, transport of samples to the laboratory, and during lab analysis. All soil borings were backfilled with drill cuttings that were determined to not be grossly contaminated and/or clean sand.

4.2 Soil Vapor Sampling

4.2.1 Soil Vapor Sampling Scope of Work

The following scope of work was proposed to determine the potential existence of soil vapor intrusion pathways onsite, the potential for exposure to soil vapor, and to develop information needed for the qualitative exposure assessment.

Soil vapor and ambient air sampling was conducted on January 22, 2026 outside of the former building footprint and on July 9, 2026 within the former building footprint. The scope of work for the sampling events consisted of the following:

- Installation of seven soil vapor points across the Site. The soil vapor sample probes were installed at 22 ft-bsg (SV-1), 8 ft-bsg (SV-2 through SV-6) and 1 foot below basement grade (11 ft-bsg) (SV-7).
- Purging and collection of soil vapor samples at each location. Soil vapor samples were collected over a period of two hours;
- Collection of one ambient air sample during each soil vapor sampling event over a period of two hours; and,
- Analysis of soil vapor and ambient air samples for TO-15 VOCs.

4.2.2 Soil Vapor Sampling Methodology

All samples were collected in general accordance with the *Final Guidance for Evaluating Soil Vapor Intrusion in the State of New York* (NYSDOH, October 2006, as updated).

A direct-push track-mounted Geoprobe® was used to install all soil vapor sampling probes to the following depths: SV-1 to 22 ft-bsg; SV-2 through SV-6 to 8 ft-bsg; and SV-7 to 1 foot below basement grade (11 ft-bsg). The NYSDEC-approved RIWP specified that soil vapor probes SV-4 through SV-7 would be installed along the southern, eastern and western perimeters of the Site at the anticipated depth of the nearest neighboring building's foundation. Soil vapor probes SV-4 through SV-6 were installed at 8 ft-bsg, the depth anticipated in the field for the foundations of the nearest adjoining buildings. Soil vapor probe SV-7 was installed at one foot below the slab of the former on-Site basement, 11 ft-bsg. The western portion of the Site was occupied at the time of the RI by the former church building, which had a full cellar extending to approximately 10 ft-bsg.

Installing the probe one foot beneath that slab (11 ft-bsg) was the closest depth that could be achieved to match the anticipated depth of the nearest neighboring building's foundation, due to the Site building's former foundation extending to 10 ft-bsg. All of the closest neighboring buildings to SV-4 through SV-7 appear to contain basements. A disposable sampling probe, consisting of a 1.5-inch long hardened point and a six-inch long perforated vapor intake, was installed at the target depth at each sample location. The screen of each sampling probe was surrounded by #1-size quartzite sand to approximately one foot above the top of the screen. The screen and sand pack were isolated from ambient air by placing wetted bentonite pellets to grade.

The soil vapor sampling probe was connected by 1/4-inch diameter tubing to the surface. The borehole above the sampling probe to grade was sealed using a sand pack and an inert sealant to prevent ambient air mixing with the soil vapor. Ambient air was purged from the boring hole by attaching the surface end of the 1/4-inch diameter tubing to an air valve and then to a vacuum pump. The vacuum pump removed one to three volumes of air (volume of the sample probe and tube) prior to all soil vapor sample collection.

All soil vapor samples were screened for organic vapors using a PID. Soil vapor samples were collected in 6-liter batch-certified clean Summa canisters using two-hour regulators. The flow rate of both purging and sampling did not exceed 0.2 liters per minute (L/min). A sample log sheet was maintained summarizing sample identification, date and time of sample collection, sampling depth, identity of samplers, sampling methods and devices, soil vapor purge volumes, volume of the soil vapor extracted, vacuum of canisters before and after the samples were collected, apparent moisture content of the sampling zone, and chain of custody protocols. Soil vapor sampling logs are included in Appendix F.

Helium tracer gas was used as a quality assurance/quality control (QA/QC) measure to verify the integrity of the soil vapor probe seal. A portable monitoring device was used to analyze a sample of soil vapor for the tracer gas prior to sampling. If this analysis showed a significant presence of the tracer, the probe seals were adjusted to prevent infiltration. At the conclusion of the sampling, tracer monitoring was performed a second time to confirm the integrity of the probe seals.

The ambient air samples (AA-1 and AA-2) were collected from the breathing zone, approximately three to five feet above the ground. The ambient air samples were collected in 6-liter batch-certified clean Summa canister using two-hour regulators. The sampling flow rate did not exceed 0.2 L/min.

The summa canisters were transported to York Analytical Laboratories, a New York State ELAP-certified laboratory, under chain of custody procedures and the samples analyzed for VOCs using EPA method TO-15 with a Category B deliverable package.

4.3 Groundwater Sampling

The following scope of work was proposed to further characterize the groundwater at the Site and develop information for use in the qualitative exposure assessment.

Tenen installed four permanent monitoring wells outside of the former building footprint between January 6 and 9, 2026 and installed two permanent monitoring wells within the former building footprint on June 26, 2026. Tenen conducted groundwater sampling on January 22, 2026 outside of the former building footprint and on July 9, 2026 within the former building footprint. The scope of work for the sampling events consisted of the following:

- Six permanent groundwater monitoring wells (MW-1 through MW-6) were installed onsite concurrent with soil borings SB-1, SB-2, SB-3, SB-4, SB-7 and SB-8, respectively. Monitoring wells MW-1, MW-2, and MW-6 were installed outside of the former building footprint to a depth of 30 ft-bsg, monitoring well MW-3 was installed outside of the former building footprint to a depth of 26 ft-bsg, and monitoring wells MW-4 and MW-5 were installed within the former building footprint to a depth of 20 feet below basement grade (30 ft-bsg);
- Gauged and collected groundwater samples from six newly installed groundwater monitoring wells;
- Groundwater samples were analyzed for VOCs, SVOCs, pesticides, herbicides, PCBs, total and dissolved TAL metals (including total cyanide, tri- and hexavalent chromium), 1,4-dioxane and PFAS; and
- All newly installed wells were surveyed.

4.3.1 Groundwater Well Installation and Sampling

As previously described, six soil borings (SB-1, SB-2, SB-3, SB-4, SB-7 and SB-8) were converted into permanent groundwater monitoring wells MW-1, MW-2, MW-3, MW-4, MW-5 and MW-6, respectively. All six monitoring wells were constructed using 2" diameter slotted PVC well screen. Monitoring wells MW-1, MW-2, and MW-6 were installed outside of the former building footprint to a depth of 30 ft-bsg; monitoring well MW-3 was installed outside of the former building footprint to a depth of 26 ft-bsg; and, monitoring wells MW-4 and MW-5 were installed within the former building footprint to a depth of 20 feet below basement grade (30 ft-bsg). All six newly installed monitoring wells were installed with ten feet of PVC screen (0.020-inch slot). The annular space around the well was backfilled with No. 2 Morie quartz sand to a depth of two feet above the top of the well screen. The annular space around the casing above the filter pack of sand was sealed with bentonite pellets for an interval of two feet. The annular space above the bentonite pellets to one ft-bg was backfilled with unimpacted drill cuttings and/or clean sand. Monitoring wells MW-1, MW-3, MW-4 and MW-5 were installed with a direct-push track-mounted Geoprobe® and monitoring wells MW-2 and MW-6 were installed with a sonic drill rig.

Monitoring wells MW-1 through MW-6 were developed following installation by pumping using dedicated high-density polyethylene (HDPE) tubing. Groundwater generated during well development and sampling was containerized on-Site in 55-gallon drums staged within the fenced Site perimeter, pending waste characterization and off-Site disposal at a permitted facility. All wells were sampled approximately two weeks after development. All sampling equipment was decontaminated prior to use. Prior to sampling, water levels were measured using an electronic product-water level indicator and recorded in the field logbook.

Water quality measurements, including temperature, pH, oxidation-reduction potential (ORP), turbidity, dissolved oxygen (DO) and total dissolved solids (TDS) were collected and recorded at approximately 10-minute intervals. Samples were collected only after temperature, pH and DO readings stabilized to within 10 percent of the previous reading and turbidity was below 50 Nephelometric Turbidity Units (NTUs). Sufficient sample volume was collected for each analysis. All samples were collected in laboratory-provided glass containers and preserved in accordance with the Quality Assurance Project Plan (QAPP). Water quality measurements are provided in Appendix E.

Samples were collected using low-flow techniques in accordance with EPA Region 1 Low-Stress (Low-Flow) "Purging and Sampling Procedure for the Collection of Groundwater Samples from

Monitoring Wells", (EQASOP-GW 001, Revision 3, dated July 30, 1996; Revised: January 19, 2010). Groundwater samples collected from all newly installed monitoring wells were analyzed for TCL VOCs, TCL SVOCs, pesticides, herbicides, PCBs, TAL Metals (total and dissolved), total cyanide, trivalent and hexavalent chromium, 1,4-dioxane and PFAS with a Category B deliverable package.

Newly installed monitoring wells MW-1, MW-2, MW-3, and MW-6 were surveyed to a common datum on February 12, 2026 and newly installed monitoring wells MW-4 and MW-5 were surveyed to a common datum on July 13, 2026. One round of depth-to-water measurements were collected during the RI from monitoring wells MW-1, MW-2, MW-3, and MW-6 on January 22, 2026 and from monitoring wells MW-4 and MW-5 on July 9, 2026. A groundwater contour map, inclusive of the entire well network, is included as Figure 3.

The table below summarizes the sampling designations and locations.

Sample Designation	Onsite or Offsite	Sample Location
MW-1	Onsite	Northeast corner of the lot
MW-2	Onsite	Southeast corner of the lot
MW-3	Onsite	Central western portion of the lot
MW-4	Onsite	Southwest corner of the lot, within the former building footprint
MW-5	Onsite	Northwest corner of the lot, within the former building footprint
MW-6	Onsite	Southeastern portion of the lot
MW-6_DUP[1]	Onsite	Southeastern portion of the lot

[1] Duplicate sample.

4.4 Quality Assurance / Quality Control (QA/QC)

Quality assurance/quality control (QA/QC) samples were collected at a rate of one set of QA/QC per 20 samples. QA/QC includes field duplicate, field blank, and matrix spike/matrix spike duplicate (MS/MSD) samples. In addition, one trip blank was submitted for VOC analysis with every shipment of soil or groundwater samples to be analyzed for VOCs. A Data Usability Summary Report (DUSR) was also prepared and is included in Appendix B of this RIR.

4.5 Deviations from the Remedial Investigation Work Plan

1. The NYSDEC-approved RIWP indicated groundwater monitoring wells would be installed with ten feet of screen straddling the groundwater interface (five feet above and five feet below). Due to refusal encountered at monitoring well location MW-3 at 26 ft-bsg during installation, this well was only installed to a depth of 26 ft-bsg. A groundwater sample was still collected from this well in accordance with the NYSDEC-approved RIWP.
2. The NYSDEC-approved RIWP indicated that three soil samples would be collected from each boring: a sample from 0-2 ft-bg, a sample from the two-foot interval of native soil directly below the historic fill layer, and a sample from the two-foot interval of soil directly above the groundwater interface. In soil boring SB-4, historic fill was encountered to a depth of approximately 12 ft-bg, and the groundwater interface was encountered at approximately 15 ft-bg. The soil sample collected from the native soil directly below the

historic fill layer was collected at a depth of 12 to 14 ft-bg. Following collection of this sample, only one foot of material remained between the 12-14 ft-bg sample and the groundwater interface. Therefore, the third soil sample collected from soil boring SB-4 was collected from the one-foot interval of soil directly above the groundwater interface (14-15 ft-bg).

5.0 INVESTIGATION RESULTS

This section provides a discussion of the results of the January, June, and July 2026 RI soil, groundwater and soil vapor investigations. Sample results are included in Tables 4a through 6. All results are summarized in Figures 9 through 11 and laboratory deliverables are included in Appendix B.

As previously discussed, sample results were compared to the following:

- Soil – NYSDEC Part 375 Unrestricted Use, Protection of Groundwater, and Restricted-Residential Use Soil Cleanup Objectives (SCOs) and proposed Unrestricted Use, Protection of Groundwater, and Restricted-Residential Use SCOs as listed in NYSDEC's Guidelines for Sampling, Analysis, and Assessment of PFAS Under NYSDEC's Part 375 Remedial Programs (PFAS Guidelines), dated April 2023, for PFAS.
- Groundwater – NYSDEC Division of Water Technical and Operational Guidance Series (TOGS) 1.1.1 Class GA Water Quality Standards and Guidance Values (Class GA Standards) including the February 2023 Addendum.
- Soil vapor – Ambient (background) air concentrations

5.1 Field Observations

Soil

The Site outside of the former building footprint is underlain by a historic fill layer (sand, ash, gravel, asphalt and brick fragments) extending to depths ranging from five to 12.5 ft-bsg. The western portion of the Site in the former building footprint is underlain by a historic fill layer (sand, silt, gravel, concrete and brick fragments) extending to depths ranging from 20 to 22 ft-bsg. Native brown, medium- to coarse-grained sand with gravel and cobbles underlies the fill layers to a depth of at least 30 ft-bsg. Soil boring logs from the remedial investigation are included in Appendix D.

Groundwater

Depth to groundwater at the Site was measured during the RI at depths ranging from 22.15 to 24.40 ft-bsg in monitoring wells installed across the Site. No sheen was observed and no odors were noted in purge water during groundwater sampling. Depth to water and water quality measurements are summarized in Appendix E. Based on the results of the well survey, groundwater flow is generally to the southeast. A groundwater contour map is included as Figure 3. A well survey is included in Appendix E.

Soil Vapor

PID readings in soil vapor were 0.6 ppm at SV-6. PID readings at all other soil vapor sample locations were non-detect.

5.2 Analytical Results

5.2.1 Soil

A total of 27 soil samples and two duplicates were collected between grade and 24 ft-bg. All soil characterization samples were analyzed for TCL VOCs, TCL SVOCs, pesticides, herbicides, PCBs, TAL metals, total cyanide, trivalent/hexavalent chromium, 1,4-dioxane and PFAS. All soil sample locations are depicted on Figure 8.

Sample results were compared with the New York State Part 375 Unrestricted Use SCOs (UUSCOs) and Restricted-Residential Use SCOs (RRSCOs). As discussed in Section 5.2.2, below,

only manganese, sodium, PFOS, and PFOA were detected above the Class GA Standards in groundwater samples collected at the Site during this RI; therefore, only manganese, sodium, PFOS and PFOA were compared to the Protection of Groundwater SCOs (PGWSCOs). The soil analytical results are discussed below. Soil analytical results in excess of SCOs are depicted on Figure 9. The table below summarizes all contaminants detected in soil above RRSCOs and/or PGWSCOs, as applicable.

Summary of Soil Exceedances of the Applicable SCOs

Contaminant	Number of Exceedances	Maximum Detection (ppm)	PGWSCO (ppm)	RRSCO (ppm)	Location of Maximum Detection
Benzo(a)anthracene	2	16.7	N/A	1.4	SB-2 (0-2)
Benzo(a)pyrene	3	13.6	N/A	1	SB-2 (0-2)
Benzo(b)fluoranthene	2	24.1	N/A	1.4	SB-2 (0-2)
Benzo(g,h,i)perylene	1	8.99	N/A	4.9	SB-2 (0-2)
Chrysene	2	16.4	N/A	4.9	SB-2 (0-2)
Dibenzo(a,h)anthracene	2	1.43	N/A	0.33	SB-2 (0-2)
Indeno(1,2,3-cd)pyrene	2	7.26	N/A	1.4	SB-2 (0-2)
Phenanthrene	2	23.3	N/A	4.9	SB-2 (0-2)
Barium	7	3160	N/A	410	SB-9 (0-2)
Chromium, Hexavalent	6	5.08	N/A	1	SB-9 (0-2)
Lead	6	4430	N/A	400	SB-2 (0-2)
Manganese	2	2410	2000	2000	SB-8 (22-24)
Mercury	6	2.52	N/A	0.3	SB-8 (0-2)
PFOS	3	1.74	1	44	SB-3 (0-2)

Notes: RRSCOs are those set out in 6 NYCRR Part 375-6.8(b) as amended effective December 31, 2025. PGWSCOs are only shown for manganese and PFOS, as noted above.

VOCs

One VOC, acetone, was detected in exceedance of its UUSCO of 0.03 ppm in one shallow soil sample. Acetone was detected at a concentration of 0.049 ppm in SB-7 (0-2). Acetone is a common laboratory artifact. No other VOCs were detected in exceedance of UUSCOs in any soil samples. VOCs were not detected in exceedance of RRSCOs in any soil samples.

SVOCs

A variety of SVOCs, specifically polyaromatic hydrocarbons (PAHs), were detected in exceedance of UUSCOs and/or RRSCOs in three shallow (0-2 ft-bg) soil samples. Benzo(a)anthracene, benzo(a)pyrene, benzo(b)fluoranthene, benzo(g,h,i)perylene, chrysene, and indeno(1,2,3-cd)pyrene were detected in three samples in exceedance of UUSCOs and benzo(k)fluoranthene, dibenzo(a,h)anthracene and phenanthrene were detected in two samples in exceedance of UUSCOs. The RRSCO is the same as the UUSCO for benzo(a)pyrene and dibenzo(a,h)anthracene. Therefore, all samples that exceeded the UUSCOs for these analytes also exceeded the RRSCOs. In addition, benzo(a)anthracene, benzo(b)fluoranthene, chrysene, indeno(1,2,3-cd)pyrene, and phenanthrene were also detected in exceedance of their RRSCOs in two samples. Benzo(g,h,i)perylene was also detected in exceedance of its RRSCO in one sample. In general, the highest concentrations of SVOCs were detected in SB-2 (0-2). It should be noted that SVOCs detected in the duplicate sample collected from SB-2 (0-2) did not exceed UUSCOs or RRSCOs for any analytes.

Benzo(a)anthracene was detected at a max. concentration of 16.7 ppm in SB-2 (0-2) with a UUSCO of 1 ppm and a RRSCO of 1.4 ppm; benzo(a)pyrene was detected at a max. concentration of 13.6 ppm in SB-2 (0-2) with UUSCOs and RRSCOs of 1 ppm; benzo(b)fluoranthene was detected at a max. concentration of 24.1 ppm in SB-2 (0-2) with a UUSCO of 1 ppm and a RRSCO of 1.4 ppm; benzo(g,h,i)perylene was detected at a max. concentration of 8.99 ppm in SB-2 (0-2) with a UUSCO of 0.64 ppm and a RRSCO of 4.9 ppm; chrysene was detected at a max. concentration of 16.4 ppm in SB-2 (0-2) with a UUSCO of 1 ppm and a RRSCO of 4.9 ppm; indeno(1,2,3-cd)pyrene was detected at a max. concentration of 7.26 ppm in SB-2 (0-2) with a UUSCO of 0.5 ppm and a RRSCO of 1.4 ppm; benzo(k)fluoranthene was detected at a max. concentration of 2.66 ppm in SB-9 (0-2) with a UUSCO of 0.8 ppm and a RRSCO of 4.9 ppm; dibenzo(a,h)anthreacene was detected at a max. concentration of 1.43 ppm in SB-2 (0-2) with a UUSCO and RRSCO of 0.33 ppm; and, phenanthrene was detected at a max. concentration of 23.3 ppm in SB-2 (0-2) with a UUSCO of 1.1 ppm and a RRSCO of 4.9 ppm. No other SVOCs were detected in exceedance of UUSCOs or RRSCOs in any soil samples. Total SVOCs were less than 500 ppm in all samples.

Pesticides, Herbicides, and PCBs

Three pesticides, 4,4'-DDD, 4,4'-DDE and 4,4'-DDT, were detected in one or more soil samples in exceedance of UUSCOs, but below RRSCOs. 4,4'-DDD was detected in one soil sample, SB-4 (12-14), at a concentration of 0.00489 ppm; 4,4'-DDE was detected in one soil sample, SB-4 (12-14), at a concentration of 0.00658 ppm; and, 4,4'-DDT was detected in two soil samples, at a max. concentration of 0.0138 ppm in SB-2 (0-2). The aforementioned analytes have UUSCOs of 0.0033 ppm. It should be noted that while 4,4'-DDT was detected in exceedance of the UUSCO in SB-2 (0-2), the concentration detected in the duplicate sample collected from this parent sample did not exceed the UUSCO. No other pesticides were detected in exceedance of UUSCOs in any soil samples. Pesticides were not detected in exceedance of RRSCOs in any soil samples.

Herbicides and PCBs were not detected in exceedance of UUSCOs or RRSCOs in any soil samples analyzed.

Metals

A variety of metals, specifically arsenic, barium, copper, lead, manganese, mercury, nickel, zinc, hexavalent chromium, and trivalent chromium were detected in exceedance of UUSCOs in one or more soil samples. Of these, barium, lead, manganese, mercury and hexavalent chromium were also detected in exceedance of RRSCOs in one or more samples. Manganese also exceeded its PGWSCO in two samples. The bulk of the metals contamination was detected in the shallow (0-2 ft-bg) sampling interval. Arsenic was detected in one sample in exceedance of its UUSCO, but below its RRSCO [max. 15.8 ppm in SB-8 (0-2) with a UUSCO of 13 ppm and a RRSCO of 16 ppm]; barium was detected in six samples and one duplicate sample in exceedance of its UUSCO and RRSCO [max. 3,160 ppm in SB-9 (0-2) with a UUSCO and RRSCO of 410 ppm]; copper was detected in six samples in exceedance of its UUSCO, but below its RRSCO [max. 129 ppm in SB-8 (0-2) with a UUSCO of 50 ppm and a RRSCO of 280 ppm]; lead was detected in eight samples and one duplicate sample in exceedance of the UUSCO and in six samples in exceedance of the RRSCO [max. 4,430 ppm in SB-2 (0-2) with a UUSCO of 63 ppm and a RRSCO of 400 ppm]; manganese was detected in exceedance of its UUSCO, PGWSCO, and RRSCO in two samples [max. 2,410 ppm in SB-8 (22-24) with a UUSCO of 1,600 ppm and a PGWSCO and RRSCO of 2,000 ppm]; mercury was detected in seven samples in exceedance of the UUSCO and in six samples in exceedance of the RRSCO [max. 2.52 ppm in SB-8 (0-2) with a UUSCO of 0.18 ppm and a RRSCO of 0.3 ppm]; nickel was detected in two samples in exceedance of its UUSCO [max. 41.2 ppm in SB-3 (8-10) with a UUSCO of 30 ppm and a RRSCO of 320 ppm]; zinc was detected in eight samples and one duplicate sample in exceedance of its UUSCO [max. 1,730 ppm in SB-9

(0-2) with a UUSCO of 109 ppm and a RRSCO of 6,600 ppm]; hexavalent chromium was detected in five samples and one duplicate sample in exceedance of its UUSCO and RRSCO [max. 5.08 ppm in SB-9 (0-2) with a UUSCO and RRSCO of 1 ppm]; and, trivalent chromium was detected in two samples in exceedance of its UUSCO [max. 55.2 ppm in SB-6 (22-24) with a UUSCO of 30 ppm and a RRSCO of 110 ppm]. No other metals were detected in exceedance of UUSCOs or RRSCOs in any soil samples.

Emerging Contaminants (1,4-Dioxane and PFAS)
In April 2023, NYSDEC released their revised Guidelines for Sampling and Analysis of PFAS Under NYSDEC's Part 375 Remedial Programs (PFAS Guidelines). The guidelines dictate that when potentially affected media samples are collected and analyzed for the standard Target Analyte List/Target Compound List (TAL/TCL) under a NYSDEC Part 375 remedial programs, PFAS analysis must also be performed. This sampling protocol includes sampling soil and groundwater for 1,4-dioxane, PFOS, PFOA and other associated perfluorinated chemicals (PFCs) (collectively, PFAS).

A total of 27 soil samples and both duplicate samples were analyzed for 1,4-dioxane and PFAS. 1,4-dioxane was non-detect in all soil samples analyzed.

One PFAS analyte, PFOS, was detected in exceedance of its proposed UUSCO and PGWSCO, but below its proposed RRSCO, in two shallow (0-2 ft-bg) soil samples and one shallow (0-2 ft-bg) duplicate sample. PFOS was detected at a max. concentration of 1.74 ppb in SB-3 (0-2) with a proposed UUSCO of 0.88 ppb, a proposed PGWSCO of 1.0 ppb, and a proposed RRSCO of 44 ppb. No other PFAS were detected in exceedance of the proposed UUSCOs, PGWSCOs, or RRSCOs in any soil samples.

Summary of Soil Analytical Results

- PCBs and herbicides were not detected in exceedance of UUSCOs or RRSCOs in any soil samples.
- One VOC, acetone, was detected slightly in exceedance of its UUSCO, but below its RRSCO, in one shallow (0-2 ft-bg) soil sample. Acetone is a common laboratory artifact. No other VOCs were detected in exceedance of UUSCOs or RRSCOs in any soil samples.
- A variety of historic fill-related SVOCs, specifically PAHs, were detected in exceedance of UUSCOs and RRSCOs in three shallow (0-2 ft-bg) soil samples, with the highest concentrations occurring in SB-2 (0-2).
- Pesticides were detected in exceedance of UUSCOs, but below RRSCOs, in two soil samples, SB-2 (0-2) and SB-4 (12-14).
- A variety of metals, specifically arsenic, barium, copper, lead, manganese, mercury, nickel, zinc, hexavalent chromium, and trivalent chromium, were detected in exceedance of UUSCOs in one or more soil samples. Of these, barium, lead, manganese, mercury and hexavalent chromium were also detected in exceedance of RRSCOs in one or more samples. The bulk of the metals contamination was detected in the shallow (0-2 ft-bg) sampling interval.
- 1,4-dioxane was not detected in any soil samples.
- One PFAS analyte, PFOS, was detected in exceedance of its proposed UUSCO and PGWSCO, but below its proposed RRSCO, in two shallow (0-2 ft-bg) soil samples and one shallow (0-2 ft-bg) duplicate sample.

5.2.2 Groundwater

A total of six groundwater samples and one duplicate sample were collected from six newly-installed monitoring wells (MW-1 through MW-6). All groundwater samples were analyzed for TCL VOCs, TCL SVOCs, TAL metals (total and dissolved), pesticides, herbicides, PCBs, total cyanide, trivalent and hexavalent chromium, 1,4-dioxane and PFAS. Groundwater samples were collected using low-flow techniques utilizing a peristaltic pump. Analytical results were compared to the Class GA Standards and are discussed below. Groundwater analytical results above Class GA Standards are depicted on Figure 10. The table below summarizes all contaminants detected in groundwater above the Class GA Ambient Water Quality Standard or Guidance Values (AWQSGV).

Summary of Groundwater Exceedances of the Class GA Standards

Contaminant	No. of Exceedances	Maximum Detection	AWQSGV	Location of Maximum Detection
Manganese (total)	2	567 ppb	300 ppb	MW-6
Manganese (dissolved)	2	574 ppb	300 ppb	MW-6
Sodium (total)	6	82,300 ppb	20,000 ppb	MW-6
Sodium (dissolved)	6	82,000 ppb	20,000 ppb	MW-6
PFOS	6	101.737 ppt	2.7 ppt	MW-5
PFOA	6	31.3 ppt	6.7 ppt	MW-1

VOCs

VOCs were not detected in exceedance of Class GA Standards in any groundwater samples.

SVOCs

SVOCs were not detected in exceedance of Class GA Standards in any groundwater samples.

Pesticides, Herbicides, and PCBs

Pesticides, herbicides, and PCBs were not detected in exceedance of Class GA Standards in any groundwater samples.

Metals, Total and Dissolved

Two naturally occurring earth metals, manganese and sodium, were detected in exceedance of Class GA Standards in one or more groundwater samples. Total manganese was detected in two samples and the duplicate sample in exceedance of the Class GA Standard of 300 ug/L (max. 567 ppb in MW-6) and total sodium was detected in all six samples and the duplicate sample in exceedance of the Class GA Standard of 20,000 ug/L (max. 82,500 ppb in MW-6_DUP). Both manganese and sodium also exceeded their respective Class GA Standards in one or more dissolved groundwater samples. Dissolved manganese was detected in two samples and the duplicate sample in exceedance of the Class GA Standard of 300 ug/L (max. 574 ppb in MW-6) and dissolved sodium was detected in all six samples and the duplicate sample in exceedance of the Class GA Standard of 20,000 ug/L (max. 82,000 ug/L in MW-6). No other metals were detected in exceedance of Class GA Standards in any total or dissolved groundwater samples.

Emerging Contaminants (1,4-Dioxane and PFAS)

In February 2023, NYSDEC released an addendum to the June 1998 Division of Water Technical and Operational Guidance Series (TOGS) 1.1.1 Class GA Ambient Water Quality Standards and Guidance Values and Groundwater Effluent Limitations, which created Class GA Standards of PFOA, PFOS and 1,4-dioxane.

Concentrations of PFAS, specifically PFOA and PFOS, were detected in exceedance of the newly released Class GA Standards in all six groundwater samples and the duplicate sample. PFOA was detected at a max. concentration of 31.3 parts-per-trillion (ppt) in MW-1 with a Class GA Standard of 6.7 ng/L and PFOS was detected at a max. concentration of 101.737 ppt in MW-5 with a Class GA Standard of 2.7 ng/L. No other PFAS were detected in exceedance of Class GA Standards in any groundwater samples.

1,4-dioxane was not detected in any groundwater samples.

Groundwater is not and will not be used as a potable source for the Site or surrounding community. Potable water is provided from reservoirs in upstate New York by the New York City Department of Environmental Protection (NYCDEP).

Summary of Groundwater Analytical Results

- No VOCs, SVOCs, pesticides, herbicides or PCBs were detected above Class GA Standards in any groundwater samples.
- SVOCs were detected in exceedance of Class GA Standards during previous sampling events, but were not detected in exceedance of Class GA Standards in any monitoring wells during this RI. The SVOC exceedances in previous sampling events are likely due to turbidity in the samples due to sampling being conducted with temporary, one-inch diameter monitoring wells. All wells sampled during this RI were two-inch diameter, were developed following installation, and were purged until turbidity of less than 50 NTU was achieved and/or water quality measurement readings were stabilized. Since all two-inch wells sampled indicated no exceedances of SVOCs in groundwater, it is Tenen's opinion that Protection of Groundwater SCOs for SVOCs in soil are not applicable at this Site.
- Naturally occurring earth metals manganese and sodium, were detected in total and dissolved groundwater samples across the Site.
- PFAS were detected in groundwater samples across the Site. PFOA and PFOS were detected in exceedance of the Class GA Standards in all six groundwater samples and the duplicate sample.
- 1,4-dioxane was not detected in any groundwater samples.

5.2.3 Soil Vapor

Seven soil vapor samples were collected from across the Site and two ambient air samples were collected, one during each soil vapor sampling event. Soil vapor samples SV-1 through SV-6 were compared to background (ambient) concentrations detected in AA-1, and soil vapor sample SV-7 was compared to background (ambient) concentrations detected in AA-2. All samples were analyzed for VOCs using USEPA method TO-15. Soil vapor analytical results in exceedance of ambient air concentrations are depicted on Figure 11. The table below summarizes all compounds detected in soil vapor.

Summary of Soil Vapor Detections

Compound	No. of Detections	Maximum Detection (ug/m3)	Location of Maximum Detection
1,2,4-Trimethylbenzene	1	1.081	SV-3
2,2,4-Trimethylpentane	1	1.027	SV-1
2-Butanone	5	2.27	SV-2

Compound	No. of Detections	Maximum Detection (ug/m3)	Location of Maximum Detection
4-Methyl-2-pentanone	1	30.302	SV-2
Acetone	7	26.119	SV-2
Acrylonitrile	1	9.7	SV-7
Benzene	5	1.182	SV-3
Carbon disulfide	4	9.339	SV-6
Chloroform	1	8.297	SV-1
Dichlorodifluoromethane	7	2.224	SV-3
Ethylbenzene	5	1.085	SV-1
Isopropylbenzene	1	0.251	SV-1
Methylene chloride	1	0.177	SV-1
n-Hexane	4	1.867	SV-6
o-Xylene	6	1.693	SV-1
p/m-Xylene	6	4.21	SV-6
Propylene	5	2.581	SV-6
Tetrachloroethene	5	5.627	SV-1
Tetrahydrofuran	3	1.769	SV-1
Toluene	7	9.417	SV-3
Trichlorofluoromethane	7	1.300	SV-7
Xylenes, Total	6	5.642	SV-1

Three cVOCs, specifically PCE, methylene chloride, and chloroform were detected in one or more soil vapor samples at concentrations exceeding background concentrations. PCE was detected in five soil vapor samples exceeding the background concentration, and methylene chloride and chloroform were each detected in one soil vapor sample exceeding the background concentration. PCE was detected at a max. concentration of 5.627 micrograms per cubic meter (ug/m^3) in SV-1 and was non-detect in AA-1; methylene chloride was detected at a concentration of 0.177 ug/m^3 in SV-1 and was detected non-detect in AA-1; and, chloroform was detected at a concentration of 8.297 ug/m^3 in SV-1 and was non-detect in AA-1. Of the above-mentioned analytes, chloroform is a common laboratory artifact. No other cVOCs were detected in exceedance of background concentrations in any soil vapor samples.

A variety of petroleum-related VOCs were detected in soil vapor samples across the Site in exceedance of background concentrations, including benzene, toluene, ethylbenzene, p/m-xylene, o-xylene, 1,2,4-trimethylbenzene, 2,2,4-trimethylpentane, and n-hexane. Toluene, p/m-xylene, and o-xylene were detected in six soil vapor samples in exceedance of background concentrations; ethylbenzene was detected in five soil vapor samples in exceedance of background concentrations; n-hexane was detected in two soil vapor samples in exceedance of the background concentrations; and, benzene, 1,2,4-trimethylbenzene, and 2,2,4-trimethylpentane were each detected in one soil vapor sample in exceedance of background concentrations. Benzene was detected at a concentration of 1.182 ug/m^3 in SV-3 and was detected at a concentration of 1.022 ug/m^3 in AA-1; toluene was detected at a max. concentration of 9.417 ug/m^3 in SV-3 and was detected at a concentration of 1.733 ug/m^3 in AA-1; ethylbenzene was detected at a max. concentration of 1.085 ug/m^3 in SV-1 and SV-6 and was detected at a concentration of 0.317 ug/m^3 in AA-1; p/m-xylene was detected at a max. concentration of 4.21 ug/m^3 in SV-6 and was detected at a concentration of 0.868 ug/m^3 in AA-1; o-xylene was detected at a max. concentration of 1.693 ug/m^3 in SV-1 and

was detected at a concentration of 0.317 ug/m^3 in AA-1; 1,2,4-trimethylbenzene was detected at a concentration of 1.081 ug/m^3 in SV-3 and was non-detect in AA-1; 2,2,4-trimethylpentane was detected at a concentration of 1.027 ug/m^3 in SV-1 and was non-detect in AA-1; and, n-hexane was detected at a max. concentration of 1.867 ug/m^3 in SV-6 and was detected at a concentration of 0.705 ug/m^3 in AA-1. No other petroleum-related VOCs were detected in exceedance of background concentrations in any soil vapor samples.

A variety of other VOCs were detected at low concentrations in one or more soil vapor samples in exceedance of background concentrations. Dichlorodifluoromethane was detected in all seven soil vapor samples in exceedance of background concentrations; acetone was detected in six soil vapor samples in exceedance of background concentrations; 2-butanone and propylene were detected in five soil vapor samples in exceedance of background concentrations; carbon disulfide was detected in four soil vapor samples in exceedance of background concentrations; tetrahydrofuran and trichlorofluoromethane were detected in three soil vapor samples in exceedance of background concentrations; and, 4-methyl-2-pentanone, acrylonitrile, and isopropylbenzene were each detected in one soil vapor sample in exceedance of background concentrations. Dichlorodifluoromethane was detected at a max. concentration of 2.224 ug/m^3 in SV-3 and was detected at a concentration of 1.78 ug/m^3 in AA-1; acetone was detected at a max. concentration of 26.119 ug/m^3 in SV-2 and was detected at a concentration of 8.073 ug/m^3 in AA-1; 2-butanone was detected at a max. concentration of 2.27 ug/m^3 in SV-2 and was detected at a concentration of 0.943 ug/m^3 in AA-1; propylene was detected at a max. concentration of 2.581 ug/m^3 in SV-6 and was non-detect in AA-1; carbon disulfide was detected at a max. concentration of 9.339 ug/m^3 in SV-6 and was non-detect in AA-1; tetrahydrofuran was detected at a max. concentration of 1.769 ug/m^3 in SV-1 and was non-detect in AA-1; trichlorofluoromethane was detected at a max. concentration of 1.179 ug/m^3 in SV-6 and was detected at a concentration of 1.011 ug/m^3 in AA-1; 4-methyl-2-pentanone was detected at a concentration of 30.302 ug/m^3 in SV-2 and was non-detect in AA-1; acrylonitrile was detected at a concentration of 9.7 ug/m^3 in SV-7 and was non-detect in AA-2; and, isopropylbenzene was detected at a concentration of 0.251 ug/m^3 in SV-1 and was non-detect in AA-1. Of the aforementioned analytes, acetone and 2-butanone are common laboratory artifacts.

Summary of Soil Vapor Analytical Results

- Three cVOCs, specifically PCE, methylene chloride, and chloroform, were detected in exceedance of background concentrations in one or more soil vapor samples. PCE was detected at low concentrations in five soil vapor samples (max. 5.627 ug/m^3 in SV-1) and methylene chloride and chloroform were each detected at low concentrations in one soil vapor sample, SV-1.
- A variety of petroleum-related VOCs, specifically benzene, toluene, ethylbenzene, p/m-xylene, o-xylene, 1,2,4-trimethylbenzene, 2,2,4-trimethylpentane, and n-hexane, were detected at low concentrations in exceedance of background in soil vapor samples across the Site.
- A variety of other VOCs, including dichlorodifluoromethane, acetone, 2-butanone, propylene, carbon disulfide, tetrahydrofuran, trichlorofluoromethane, 4-methyl-2-pentanone, acrylonitrile, and isopropylbenzene were detected at low concentrations in exceedance of background concentrations in one or more soil vapor samples.

6.0 QUALITATIVE EXPOSURE ASSESSMENT

A qualitative exposure assessment (EA) has been completed in accordance with Section 3.3(c)4 of DER-10 and the NYSDOH guidance for performing a qualitative EA (NYSDEC DER-10; Technical Guidance for Site Investigation and Remediation; Appendix 3 B).

The objectives of the qualitative exposure assessment are to evaluate and document how humans might be exposed to Site-related contaminants and to assess whether there are any complete or potentially complete exposure pathways now and under the reasonably anticipated future land use of the Site.

An exposure pathway describes the means by which an individual may be exposed to contaminants originating from a site. An exposure pathway has five elements: (1) a contaminant source; (2) contaminant release and transport mechanisms to an exposed population; (3) a receptor population; (4) a route of exposure; and (5) a point of exposure to a receptor population. The following sections discuss the potential exposure pathways to Site-related contaminants at the Site. A table describing the environmental media, potential exposure routes and a human exposure assessment is included at the end of this section.

6.1 Contaminant Sources

Based on the results of previous sampling and the RI, the contaminants of concern at the Site are heavy metals, specifically lead, barium, mercury, manganese, and hexavalent chromium, historic fill-related SVOCs and pesticides, and PFAS.

The soil is impacted with heavy metals, specifically lead, barium, mercury, manganese, and hexavalent chromium, likely due to historic fill material. The soil is also impacted with historic fill-related SVOCs and pesticides, consistent with concentrations typically found in historic fill throughout New York City. A layer of historic fill is present across the Site at depths ranging from five to 12.5 ft-bsg outside of the former building footprint and 20 to 22 ft-bsg in the former building footprint.

The groundwater is impacted with PFAS, specifically PFOA and PFOS. Minor exceedances of PFOS above applicable standards were also noted in shallow (0-2 ft-bg) soil samples collected at the Site.

Soil vapor is impacted with low concentrations of chlorinated VOCs and petroleum-related VOCs. Chlorinated and petroleum-related VOC concentrations in soil and groundwater are low or non-detect, indicating the low concentrations in soil vapor are likely due to one or more offsite sources.

6.2 Contaminant Release and Transport Mechanisms

Soil is impacted with heavy metals, specifically lead, barium, mercury, manganese, and hexavalent chromium, likely due to historic fill present across the Site. Soil is also impacted with historic fill-related SVOCs and pesticides due to the quality of historic fill present across the Site at depths ranging five to 12.5 ft-bsg outside of the former building footprint and 20 to 22 ft-bsg in the former building footprint.

Low concentrations of chlorinated and petroleum-related VOCs were detected in soil vapor across the Site. Chlorinated and petroleum-related VOCs were either not detected in any soil or

groundwater samples collected during this RI or were detected at low concentrations. It is Tenen's opinion that the chlorinated and petroleum-related VOCs detected in soil vapor are due to one or more offsite sources. Historic industrial operations have been documented at offsite properties adjoining the Site and cross- or upgradient of the Site.

6.3 Potential Receptor Populations

The potential onsite receptors include construction workers, visitors and trespassers. The potential off-site receptors include off-site workers and off-site residents. Sensitive receptors within ¼-mile radius of the Site, including schools, day cares, and health care facilities, are shown on Figure 13.

6.4 Potential Routes and Points of Exposure

The findings of prior investigations and the RI indicate the presence of heavy metals, specifically barium, lead, mercury, manganese, and hexavalent chromium, and historic fill-related SVOCs and pesticides at elevated concentrations exceeding applicable cleanup objectives in soil across the Site. In addition, cVOCs and petroleum-related VOCs have been detected at low concentrations in soil vapor at the Site.

Earlier investigations and the RI documented shallow soil contamination at the Site with potential for exposure via dermal adsorption, inhalation and incidental ingestion if proper protective measures are not implemented. There is potential for exposure via these pathways during ground-intrusive sampling and Site remediation; however, due to the presence of a gated and locked construction fence surrounding the Site lot, onsite exposures unrelated to remedial activities are not likely. Exposure of environmental professionals during sampling will be mitigated by adherence to a HASP. During remediation activities, the potential for exposure of Site construction workers and nearby residents to contaminated soil via onsite handling and off-site transportation of disturbed soil will be avoided by implementation of a CAMP and HASP.

Concentrations of PFAS were detected in onsite groundwater monitoring wells above the Class GA Standards, which were developed to be protective of public health based upon groundwater as a potential drinking water source. While concentrations of these constituents exceed Class GA Standards and PFAS Guidelines and there is the potential for these constituents to migrate off Site, exposure to contaminants via drinking water is not applicable to the Site given the fact that the Site and surrounding community are supplied by the New York City municipal potable water system which is supplied by upstate reservoirs.

Dermal and inhalation exposure to contaminants detected in groundwater, based on the depth to groundwater, should be limited to Site construction workers involved in dewatering and excavation below the groundwater table and Site workers collecting groundwater samples for environmental analysis. These exposures would be mitigated by adherence to a HASP during sampling activities and implementation of a CAMP and HASP during construction.

Exposure to residual contaminants in soil and soil vapor following redevelopment will be mitigated by the proposed building's foundation and minimum 20-mil vapor barrier, which will cover the entire Site footprint.

The compounds detected in soil vapor at the Site are volatile by nature, but the potential for

volatilization to ambient air on-Site, and to ambient air and indoor air off-Site, is low for the following reasons. The soil vapor concentrations measured at the Site are low, with a maximum tetrachloroethylene concentration of 5.627 ug/m3, and a number of the compounds detected in soil vapor were reported at concentrations at or below those measured in the corresponding ambient air samples. There is no onsite building and no enclosed onsite space in which soil vapor could accumulate, so vapor reaching grade is diluted in outdoor air. The soil and groundwater data do not indicate an onsite source of these compounds that would sustain a vapor source over time. Exposure to site workers and nearby residents during remediation will be mitigated by adherence to a HASP during sampling activities and to a HASP and CAMP during remediation.

6.5 Summary of Qualitative Exposure Assessment

The table below summarizes the potential exposure routes and receptors and presents a human exposure assessment for each.

Potential Exposure Route	Potential Receptors	Human Exposure Assessment
Dermal contact with surface soils and incidental ingestion	Site workers during sampling activities and construction workers during site remediation.	The potential for on- and off-site exposure during ground-intrusive activities will be avoided by implementation of a HASP and CAMP during sampling events and Site redevelopment. Present-day exposures will be prevented by a gated and locked construction fence restricting access to the Site, which extends around the perimeter of the Site.
Ingestion of groundwater	Area residents through ingestion of groundwater.	Groundwater is not nor will be used as a potable source for the Site or surrounding community. Potable water is provided from reservoirs in upstate New York by the New York City Department of Environmental Protection (NYCDEP).
Dermal contact with groundwater/ Inhalation of volatile groundwater constituents	Site workers during sampling activities and construction workers during site remediation.	Exposure will be avoided by having environmental professionals sampling groundwater and workers engaged in construction dewatering adhering to a HASP. Present-day exposures will be prevented by a gated and locked construction fence restricting access to the Site, which extends around the perimeter of the Site.

Potential Exposure Route	Potential Receptors	Human Exposure Assessment
Inhalation of vapors	Construction workers during site remediation and nearby residents and workers.	The Site is currently unimproved with any buildings, with access prevented by a gated and locked construction fence, preventing present-day onsite exposure. Exposures to onsite workers during Site remediation will be mitigated through implementation of a HASP and CAMP. Exposure to nearby residents and workers is currently mitigated by the site security fencing, offsite building foundations and vapor barriers (if present), and exposure during Site remediation will be mitigated through implementation of CAMP.

7.0 SUMMARY

7.1 Soil

The results of previous investigations and the RI indicate the presence of heavy metals, specifically barium, lead, mercury, manganese, and hexavalent chromium, in exceedance of Unrestricted Use and Restricted-Residential Use SCOs in soil across the Site. The results of previous investigations and the RI indicate the presence of SVOCs (specifically PAHs) at concentrations exceeding Unrestricted Use and Restricted-Residential use SCOs in one or more soil samples collected from historic fill material that is present across the Site. Pesticides were detected in exceedance of Unrestricted Use SCOs in one or more soil samples collected from historic fill material or from the native material immediately below the historic fill material at the Site. PFOS was detected in exceedance of its proposed Unrestricted Use and Protection of Groundwater SCOs in two shallow (0-2 ft-bg) soil samples and one duplicate sample collected from the historic fill layer at the Site.

7.2 Groundwater

Groundwater results from samples collected at the Site during previous investigations and the RI indicate the presence of naturally-occurring earth metals (manganese and sodium) and PFAS in exceedance of Class GA Standards. Groundwater impacts are minimal across the Site and groundwater is not utilized as a source of potable water in this area of New York City.

7.3 Soil Vapor

Soil vapor results from samples collected at the Site during previous investigation and the RI indicate the presence of low concentrations of chlorinated solvents and petroleum-related VOCs. Due to the lack of cVOCs and petroleum-related VOCs detected in soil and groundwater across the Site during previous investigations and the RI, it is Tenen's opinion that the soil vapor impacts are likely due to one or more offsite sources.

7.4 Recommendations

The findings of the RI confirm the presence of contamination above applicable standards in soil at the Site, and remediation is necessary. Based upon the findings of the previous investigations and the RI**,** an evaluation of remedial alternatives will be conducted and presented to NYSDEC in a Remedial Action Work Plan.

8.0 REFERENCES

New York State Department of Environmental Conservation (NYSDEC), Division of Environmental Remediation. DER Technical Guidance for Site Investigation and Remediation (DER-10). NYSDEC 2010.

NYSDEC Policy. Commissioner's Policy 51 – Soil Cleanup Guidance. October 21, 2010. NYSDEC 2010.

New York State Department of Environmental Conservation. Guidelines for Sampling and Analysis of Per- and Polyfluoroalkyl Substances (PFAS) Under NYSDEC's Part 375 Remedial Programs. April 2023. NYSDEC 2023.


New York State Department of Health (NYSDOH). Final Guidance for Evaluating Soil Vapor Intrusion in the State of New York (NYSDOH, October 2006).

Phase I Environmental Site Assessment Report, 260 West 126th Street, New York, New York. Environmental Business Consultants. October 2016.

Remedial Investigation Report, 260 West 126th Street, New York, New York. Environmental Business Consultants. December 2016.

Remedial Investigation Work Plan, 260 West 126th Street, New York, New York. Tenen Environmental, LLC. December 2025.


Figures



Basemap: USGS Topographic Map, 7.5 Minute Quadrangles: Brooklyn, NY; Central Park, NY; Jersey City, NJ; Weehawken, NJ

Site Location

0 2,000 4,000 Feet



propertyinformationportal.nyc.gov

Department of Finance Digital Tax Map



NYC OpenData, State of New Jersey, Esri, HERE, Garmin, INCREMENT P, USGS, EPA, USDA

Department of City Planning MapPluto 2026 v1

0 200 400 Feet

260 West 126th Street
New York, New York
Block 1931, Lot 56

TENEN ENVIRONMENTAL
Tenen Environmental, LLC
465 East 188th Street, #112
Bronx, NY 10458
O: (646) 606-2332; F: (646) 606-2379

Drawn By	Checked By	Date	Scale
LM	AP	August 2026	As Noted

Drawing Title: Site Location Map

Drawing No.: Figure 1

Legend

- Site Boundary
- NYC Tax Lots

0 40 80 160 Feet

Reference:
NYS ITS Geospatial Services - 2024 Aerial
Parcel Boundaries: Contributing counties, NYS Office of Information Technology Services GIS Program Office (GPO) and NYS Department of Taxation and Finance's Office of Real Property Tax Services (ORPTS).


260 West 126th Street
New York, New York
Block 1931, Lot 56

TENEN ENVIRONMENTAL
Tenen Environmental, LLC
465 East 188th Street, #112
Bronx, NY 10458
O: (646) 606-2332; F: (646) 606-2379

Drawn By	LM
Checked By	SB
Date	August 2026
Scale	As Noted

Drawing Title: Site Boundary Map

Drawing No.: Figure 2



Legend

- Monitoring Well Location
- Groundwater Elevation Contour
- Groundwater Flow Direction
- NYC Tax Lots
- Site Boundary

Note:
All groundwater elevation measurements were collected on January 22, 2026 (MW-1, MW-2, MW-3, and MW-6) and July 9, 2026 (MW-4 and MW-5).

An assumed common datum was used for all elevations.

0 15 30 60 Feet

Reference:
6/1/2024 Nearmap Aerial
Parcel Boundaries: Contributing counties, NYS Office of Information Technology Services GIS Program Office (GPO) and NYS Department of Taxation and Finance's Office of Real Property Tax Services (ORPTS).

260 West 126th Street
New York, New York
Block 1931, Lot 56

TENEN ENVIRONMENTAL
Tenen Environmental, LLC
465 East 188th Street, #112
Bronx, NY 10458
O: (646) 606-2332; F: (646) 606-2379

Drawn By	LM
Checked By	AP
Date	September 2026
Scale	As Noted

Drawing Title: Groundwater Contour Map

Drawing No.: Figure 3



Legend

- Soil Boring Location (2016 EBC RI)
- Monitoring Well Location (2016 EBC RI)
- Soil Vapor Sample Location (2016 EBC RI)
- NYC Tax Lots
- Site Boundary

0 15 30 60 Feet

Reference:
6/1/2024 Nearmap Aerial
Parcel Boundaries: Contributing counties, NYS Office of Information Technology Services GIS Program Office (GPO) and NYS Department of Taxation and Finance's Office of Real Property Tax Services (ORPTS).


260 West 126th Street
New York, New York
Block 1931, Lot 56

TENEN ENVIRONMENTAL
Tenen Environmental, LLC
465 East 188th Street, #112
Bronx, NY 10458
O: (646) 606-2332; F: (646) 606-2379

Drawn By: LM
Checked By: SB
Date: August 2026
Scale: As Noted

Drawing Title: Historic Sampling Locations - 2016 EBC RI

Drawing No.: Figure 4



Sample Location	SB1	
Sample Depth (ft-bg)	0-2	2-4
Date	11/15/2016	
SVOCs	ppm	
Benzo(a)anthracene	ND	ND
Benzo(a)pyrene	ND	ND
Benzo(b)fluoranthene	ND	ND
Benzo(k)fluoranthene	ND	ND
Chrysene	ND	ND
Indeno(1,2,3-cd)pyrene	ND	ND
Total Metals		
Arsenic	2.38	1.45
Barium	56.7	35.6
Chromium	15.4	12.8
Copper	19.9	14
Lead	38.3	23.4
Mercury	**0.53**	ND
Nickel	14.6	14.4
Zinc	30.5	16.8
Pesticides		
4,4'-DDE	ND	ND
4,4'-DDT	ND	ND

Sample Location	SB2	
Sample Depth (ft-bg)	0-2	10-12
Date	11/10/2016	
SVOCs	ppm	
Benzo(a)anthracene	0.18	ND
Benzo(a)pyrene	0.19	ND
Benzo(b)fluoranthene	0.2	ND
Benzo(k)fluoranthene	0.18	ND
Chrysene	0.26	0.15
Indeno(1,2,3-cd)pyrene	0.13	ND
Total Metals		
Arsenic	4.6	2.9
Barium	102	142
Chromium	14.1	15.6
Copper	**76.4**	47.8
Lead	**138**	**189**
Mercury	0.02	**0.48**
Nickel	**43.6**	13.4
Zinc	**167**	75.3
Pesticides		
4,4'-DDE	ND	ND
4,4'-DDT	ND	ND

Sample Location	SB3	
Sample Depth (ft-bg)	0-2	10-12
Date	11/10/2016	
SVOCs	ppm	
Benzo(a)anthracene	0.67	ND
Benzo(a)pyrene	0.68	ND
Benzo(b)fluoranthene	0.69	ND
Benzo(k)fluoranthene	0.65	ND
Chrysene	0.83	ND
Indeno(1,2,3-cd)pyrene	0.49	ND
Total Metals		
Arsenic	7.95	1.78
Barium	**901**	154
Chromium	28.1	16.1
Copper	**67.4**	26.1
Lead	**562**	**134**
Mercury	**0.25**	0.04
Nickel	**36.1**	**34.6**
Zinc	**685**	81.5
Pesticides		
4,4'-DDE	0.022	ND
4,4'-DDT	0.025	ND

Sample Location	SB6	
Sample Depth (ft-bg)	0-2	2-4
Date	11/10/2016	
SVOCs	ppm	
Benzo(a)anthracene	ND	ND
Benzo(a)pyrene	ND	ND
Benzo(b)fluoranthene	ND	ND
Benzo(k)fluoranthene	ND	ND
Chrysene	ND	ND
Indeno(1,2,3-cd)pyrene	ND	ND
Total Metals		
Arsenic	3.05	2.26
Barium	56.2	122
Chromium	8.48	26.9
Copper	14.1	32.5
Lead	**235**	21.2
Mercury	**0.45**	0.09
Nickel	9.77	30
Zinc	92.8	38.9
Pesticides		
4,4'-DDE	**0.012**	**0.0038**
4,4'-DDT	**0.0039**	**0.013**

Sample Location	SB5	
Sample Depth (ft-bg)	0-2	10-12
Date	11/10/2016	
SVOCs	ppm	
Benzo(a)anthracene	**1.1**	ND
Benzo(a)pyrene	**1.1**	ND
Benzo(b)fluoranthene	**1.1**	ND
Benzo(k)fluoranthene	**1.1**	ND
Chrysene	**1.3**	ND
Indeno(1,2,3-cd)pyrene	**0.81**	ND
Total Metals		
Arsenic	**15.7**	1.52
Barium	**729**	33
Chromium	14.7	19
Copper	28.4	26.8
Lead	**2040**	4.1
Mercury	**0.34**	ND
Nickel	14.2	14.1
Zinc	**690**	29.2
Pesticides		
4,4'-DDE	ND	ND
4,4'-DDT	ND	ND

Sample Location	SB4	
Sample Depth (ft-bg)	0-2	10-12
Date	11/10/2016	
SVOCs	ppm	
Benzo(a)anthracene	0.28	0.51
Benzo(a)pyrene	0.3	0.54
Benzo(b)fluoranthene	0.25	0.55
Benzo(k)fluoranthene	0.27	0.53
Chrysene	0.31	0.65
Indeno(1,2,3-cd)pyrene	0.18	0.45
Total Metals		
Arsenic	6.67	5.65
Barium	**993**	394
Chromium	**44.1**	**30.2**
Copper	36.2	45.1
Lead	**642**	**247**
Mercury	**0.25**	0.16
Nickel	**228**	**67.7**
Zinc	**664**	**260**
Pesticides		
4,4'-DDE	ND	ND
4,4'-DDT	ND	ND

Sample Location	SB7	
Sample Depth (ft-bg)	0-2	10-12
Date	11/10/2016	
SVOCs	ppm	
Benzo(a)anthracene	0.34	ND
Benzo(a)pyrene	0.33	ND
Benzo(b)fluoranthene	0.27	ND
Benzo(k)fluoranthene	0.28	ND
Chrysene	0.36	ND
Indeno(1,2,3-cd)pyrene	0.23	ND
Total Metals		
Arsenic	8.51	2.71
Barium	**2760**	131
Chromium	27.7	**35.5**
Copper	**53.9**	**64.5**
Lead	**696**	58.3
Mercury	**0.26**	**0.42**
Nickel	19.2	26.2
Zinc	**1960**	83.5
Pesticides		
4,4'-DDE	ND	ND
4,4'-DDT	**0.0048**	ND

Sample Location	SB8	
Sample Depth (ft-bg)	0-2	10-12
Date	11/10/2016	
SVOCs	ppm	
Benzo(a)anthracene	0.14	0.66
Benzo(a)pyrene	0.12	0.65
Benzo(b)fluoranthene	ND	0.57
Benzo(k)fluoranthene	0.12	0.63
Chrysene	0.14	0.71
Indeno(1,2,3-cd)pyrene	ND	0.43
Total Metals		
Arsenic	1.91	7.13
Barium	73.6	**703**
Chromium	16.8	17.5
Copper	35.3	19.6
Lead	30.8	**782**
Mercury	**0.23**	**0.75**
Nickel	15.9	13.6
Zinc	37.5	**400**
Pesticides		
4,4'-DDE	ND	ND
4,4'-DDT	ND	ND

Analyte	NY-UNRES	NY-RESRR
SVOCs	ppm	
Benzo(a)anthracene	1	1.4
Benzo(a)pyrene	1	1
Benzo(b)fluoranthene	1	1.4
Benzo(k)fluoranthene	0.8	4.9
Chrysene	1	4.9
Indeno(1,2,3-cd)pyrene	0.5	1.4
Total Metals		
Arsenic	13	16
Barium	410	410
Chromium	30	110
Copper	50	280
Lead	63	400
Mercury	0.18	0.3
Nickel	30	320
Zinc	109	6600
Pesticides		
4,4'-DDE	0.0033	3.4
4,4'-DDT	0.0033	3.8

Notes:

1. **Bold and shaded yellow value indicates concentration exceeds NY-UNRES SCOs**
2. **Bold and shaded orange value indicates concentration exceeds NY-RESRR SCOs**
3. NY-UNRES = 6 NYCRR Part 375 Unrestricted Use Soil Cleanup Objectives
4. NY-RESRR = 6 NYCRR Part 375 Restricted-Residential Use Soil Cleanup Objectives
5. ND = Not detected
6. ppm = parts per million

Legend

- Soil Boring Location (2016 EBC RI)
- NYC Tax Lots
- Site Boundary

0 15 30 60 Feet

Reference:
6/1/2024 Nearmap Aerial
Parcel Boundaries: Contributing counties, NYS Office of Information Technology Services GIS Program Office (GPO) and NYS Department of Taxation and Finance's Office of Real Property Tax Services (ORPTS).


260 West 126th Street
New York, New York
Block 1931, Lot 56

TENEN ENVIRONMENTAL
Tenen Environmental, LLC
465 East 188th Street, #112
Bronx, NY 10458
O: (646) 606-2332; F: (646) 606-2379

Drawn By: LM
Checked By: SB
Date: August 2026
Scale: As Noted

Drawing Title: Historic Soil Concentrations - 2016 EBC RI

Drawing No.: Figure 5



Sample ID	MW1
Date	11/18/2016
SVOCs	ppb
Benzo(a)anthracene	ND
Benzo(a)pyrene	ND
Benzo(b)fluoranthene	ND
Benzo(k)fluoranthene	ND
Chrysene	ND
Indeno(1,2,3-cd)pyrene	ND
Unfiltered Metals	
Arsenic	**54**
Barium	**4960**
Beryllium	**24**
Cadmium	**14**
Chromium	**304**
Copper	**2,260**
Iron	**264,000**
Lead	**408**
Magnesium	**90,500**
Manganese	**71,100**
Nickel	**1,160**
Sodium	**226000**
Thallium	ND

Sample ID	MW2
Date	11/18/2016
SVOCs	ppb
Benzo(a)anthracene	ND
Benzo(a)pyrene	ND
Benzo(b)fluoranthene	ND
Benzo(k)fluoranthene	ND
Chrysene	ND
Indeno(1,2,3-cd)pyrene	ND
Unfiltered Metals	
Arsenic	**41**
Barium	**3630**
Beryllium	**19**
Cadmium	**9**
Chromium	**236**
Copper	**1,830**
Iron	**191,000**
Lead	**160**
Magnesium	**75,400**
Manganese	**41,700**
Nickel	**880**
Sodium	**148000**
Thallium	ND

Sample ID	MW3
Date	11/18/2016
SVOCs	ppb
Benzo(a)anthracene	**0.03**
Benzo(a)pyrene	ND
Benzo(b)fluoranthene	ND
Benzo(k)fluoranthene	ND
Chrysene	ND
Indeno(1,2,3-cd)pyrene	ND
Unfiltered Metals	
Arsenic	**47**
Barium	**4110**
Beryllium	**17**
Cadmium	**10**
Chromium	**710**
Copper	**1,740**
Iron	**349,000**
Lead	**347**
Magnesium	**128,000**
Manganese	**52,000**
Nickel	**754**
Sodium	**165000**
Thallium	**1**

Sample ID	MW4
Date	11/18/2016
SVOCs	ppb
Benzo(a)anthracene	**0.38**
Benzo(a)pyrene	**0.38**
Benzo(b)fluoranthene	**0.34**
Benzo(k)fluoranthene	**0.3**
Chrysene	**0.39**
Indeno(1,2,3-cd)pyrene	**0.26**
Unfiltered Metals	
Arsenic	**65**
Barium	**5620**
Beryllium	**28**
Cadmium	**17**
Chromium	**559**
Copper	**2,400**
Iron	**376,000**
Lead	**535**
Magnesium	**146,000**
Manganese	**84,700**
Nickel	**1,330**
Sodium	**177000**
Thallium	ND

Analyte	NY-AWQS
SVOCs	ppb
Benzo(a)anthracene	0.002
Benzo(a)pyrene	0
Benzo(b)fluoranthene	0.002
Benzo(k)fluoranthene	0.002
Chrysene	0.002
Indeno(1,2,3-cd)pyrene	0.002
Total Metals	
Arsenic	25
Barium	1,000
Beryllium	3
Cadmium	5
Chromium	50
Copper	200
Iron	300
Lead	25
Magnesium	35,000
Manganese	300
Nickel	300
Sodium	20,000
Thallium	0.5

Notes:
1. Bold and shaded yellow value indicates concentration exceeds NY-AWQS
2. NY-AWQS = NYSDEC Division of Technical and Operational Guidance Series (TOGS) 1.1.1 Ambient Water Quality Standards (AWQS)
3. ND = Not detected
4. ppb = parts per billion

Legend

- Monitoring Well Location (2016 EBC RI)
- NYC Tax Lots
- Site Boundary

0 15 30 60 Feet

Reference:
6/1/2024 Nearmap Aerial
Parcel Boundaries: Contributing counties, NYS Office of Information Technology Services GIS Program Office (GPO) and NYS Department of Taxation and Finance's Office of Real Property Tax Services (ORPTS).


260 West 126th Street
New York, New York
Block 1931, Lot 56

TENEN ENVIRONMENTAL
Tenen Environmental, LLC
465 East 188th Street, #112
Bronx, NY 10458
O: (646) 606-2332; F: (646) 606-2379

Drawn By: LM
Checked By: SB
Date: August 2026
Scale: As Noted

Drawing Title: Historic Groundwater Concentrations - 2016 EBC RI

Drawing No.: Figure 6



Sample ID:	SG1
Date:	11/18/2016
Sampling Depth:	6 in-bg
VOCs	µg/m^3
Tetrachloroethene	11.3
Trichloroethene	0.38
Carbon tetrachloride	0.52
Chloroform	2.24

Sample ID:	SG2
Date:	11/18/2016
Sampling Depth:	12 ft-bg
VOCs	µg/m^3
Tetrachloroethene	5.24
Trichloroethene	ND
Carbon tetrachloride	0.34
Chloroform	ND

Sample ID:	SG4
Date:	11/18/2016
Sampling Depth:	12 ft-bg
VOCs	µg/m^3
Tetrachloroethene	7.25
Trichloroethene	0.27
Carbon tetrachloride	0.35
Chloroform	ND

Sample ID:	SG5
Date:	11/18/2016
Sampling Depth:	12 ft-bg
VOCs	µg/m^3
Tetrachloroethene	16.5
Trichloroethene	0.62
Carbon tetrachloride	0.31
Chloroform	7.76

Sample ID:	SG3
Date:	11/18/2016
Sampling Depth:	12 ft-bg
VOCs	µg/m^3
Tetrachloroethene	3.99
Trichloroethene	ND
Carbon tetrachloride	0.32
Chloroform	ND

Notes:
1. ND = Not Detected
2. µg/m3 = micrograms per cubic meter
3. ft-bg = feet below grade
4. in-bg = inches below grade

Legend

- Soil Vapor Sample Location (2016 EBC RI)
- NYC Tax Lots
- Site Boundary

0 15 30 60 Feet

Reference:
6/1/2024 Nearmap Aerial
Parcel Boundaries: Contributing counties, NYS Office of Information Technology Services GIS Program Office (GPO) and NYS Department of Taxation and Finance's Office of Real Property Tax Services (ORPTS).

260 West 126th Street
New York, New York
Block 1931, Lot 56

TENEN ENVIRONMENTAL
Tenen Environmental, LLC
465 East 188th Street, #112
Bronx, NY 10458
O: (646) 606-2332; F: (646) 606-2379

Drawn By: LM
Checked By: SB
Date: August 2026
Scale: As Noted

Drawing Title: Historic Soil Vapor Concentrations - 2016 EBC RI

Drawing No.: Figure 7



Legend

- Soil Boring Location
- Soil Boring/ Monitoring Well Location
- Soil Vapor Sampling Location
- Ambient Air Sample Location
- NYC Tax Lots
- Site Boundary
- Former Building Footprint Extents

Note:
The former basement slab depth is approximately 10 ft-bg.

0 15 30 60 Feet

Reference:
6/1/2024 Nearmap Aerial
Parcel Boundaries: Contributing counties, NYS Office of Information Technology Services GIS Program Office (GPO) and NYS Department of Taxation and Finance's Office of Real Property Tax Services (ORPTS).


260 West 126th Street
New York, New York
Block 1931, Lot 56

TENEN ENVIRONMENTAL
Tenen Environmental, LLC
465 East 188th Street, #112
Bronx, NY 10458
O: (646) 606-2332; F: (646) 606-2379

Drawn By	Checked By	Date	Scale
LM	AP	September 2026	As Noted

Drawing Title: RI Sample Locations

Drawing No.: Figure 8



Sample Location	SB-7		
Sample Depth (ft-bg)	0-2	10-12	12-14
Date	6/26/2026		
SVOCs	ppm		
Benzo(a)anthracene	ND	ND	ND
Benzo(a)pyrene	ND	ND	ND
Benzo(b)fluoranthene	ND	ND	ND
Benzo(g,h,i)perylene	ND	ND	ND
Benzo(k)fluoranthene	ND	ND	ND
Chrysene	ND	ND	ND
Dibenzo(a,h)anthracene	ND	ND	ND
Indeno(1,2,3-cd)pyrene	ND	ND	ND
Phenanthrene	ND	ND	ND
Total Metals			
Arsenic	4.13	ND	ND
Barium	70.8	24.9	16.4
Copper	9.36	7.79	7.6
Lead	38.8	2.11	2.59
Manganese	2160	243	203
Mercury	ND	ND	ND
Nickel	7.79	8.36	5.99
Zinc	110	8.5	7.51
Chromium, Hexavalent	ND	ND	ND
Chromium, Trivalent	11.7	7.01	8.05
Pesticides			
4,4'-DDD	ND	ND	ND
4,4'-DDE	ND	ND	ND
4,4'-DDT	ND	ND	ND
PFAS	ppb		
PFOS	0.038 J	ND	0.043 J

Sample Location	SB-5			
Sample Depth (ft-bg)	0-2	12.5-14.5	22-24	22-24 (DUP)
Date	1/5/2026			
SVOCs	ppm			
Benzo(a)anthracene	0.731 D	ND	ND	ND
Benzo(a)pyrene	0.582 D	ND	ND	ND
Benzo(b)fluoranthene	0.498 D	ND	ND	ND
Benzo(g,h,i)perylene	0.287 D	ND	ND	ND
Benzo(k)fluoranthene	0.483 D	ND	ND	ND
Chrysene	0.631 D	ND	ND	ND
Dibenzo(a,h)anthracene	0.117 D	ND	ND	ND
Indeno(1,2,3-cd)pyrene	0.351 D	ND	ND	ND
Phenanthrene	0.685 D	ND	ND	ND
Total Metals				
Arsenic	8.29	ND	ND	ND
Barium	458	30	27.5	31.6
Copper	128	8.39	16.5	8.61
Lead	424	2.35	18.7	3.12
Manganese	312	136	414	343
Mercury	0.135	ND	ND	ND
Nickel	18.8	5.4	10.8	8.44
Zinc	440	8.62	16.9	12
Chromium, Hexavalent	1.18	ND	ND	ND
Chromium, Trivalent	22.2	8.22	13.8	9.85
Pesticides				
4,4'-DDD	ND	ND	ND	ND
4,4'-DDE	ND	ND	ND	ND
4,4'-DDT	ND	ND	ND	ND
PFAS	ppb			
PFOS	1.29 D	ND	ND	ND

Sample Location	SB-3		
Sample Depth (ft-bg)	0-2	8-10	22-24
Date	1/5/2026		
SVOCs	ppm		
Benzo(a)anthracene	ND	ND	ND
Benzo(a)pyrene	ND	ND	ND
Benzo(b)fluoranthene	ND	ND	ND
Benzo(g,h,i)perylene	ND	ND	ND
Benzo(k)fluoranthene	ND	ND	ND
Chrysene	ND	ND	ND
Dibenzo(a,h)anthracene	ND	ND	ND
Indeno(1,2,3-cd)pyrene	ND	ND	ND
Phenanthrene	ND	ND	ND
Total Metals			
Arsenic	4.06	1.88	2.11
Barium	270	81.6	48
Copper	22.6	39.7	29.3
Lead	46.3	4.84	4.72
Manganese	285	761	510
Mercury	0.132	ND	ND
Nickel	21.4	41.2	16.3
Zinc	158	24.5	23.1
Chromium, Hexavalent	ND	ND	ND
Chromium, Trivalent	18.7	29.7	17.3
Pesticides			
4,4'-DDD	ND	ND	ND
4,4'-DDE	ND	ND	ND
4,4'-DDT	ND	ND	ND
PFAS	ppb		
PFOS	1.74	ND	ND

Sample Location	SB-4		
Sample Depth (ft-bg)	0-2	12-14	14-15
Date	6/26/2026		
SVOCs	ppm		
Benzo(a)anthracene	ND	0.432	ND
Benzo(a)pyrene	ND	0.45	ND
Benzo(b)fluoranthene	ND	0.429	ND
Benzo(g,h,i)perylene	ND	0.219	ND
Benzo(k)fluoranthene	ND	0.358	ND
Chrysene	ND	0.427	ND
Dibenzo(a,h)anthracene	ND	ND	ND
Indeno(1,2,3-cd)pyrene	ND	0.267	ND
Phenanthrene	ND	1.05	ND
Total Metals			
Arsenic	ND	2.06	ND
Barium	35.8	107	23.9
Copper	13.9	32	11.5
Lead	3.41	129	2.87
Manganese	278	275	216
Mercury	ND	0.406	ND
Nickel	7.8	11.3	9.78
Zinc	10.9	63	9.42
Chromium, Hexavalent	ND	ND	ND
Chromium, Trivalent	7.99	15.5	7.87
Pesticides			
4,4'-DDD	ND	0.00489 D	ND
4,4'-DDE	ND	0.00658 D	ND
4,4'-DDT	ND	0.00986 D	ND
PFAS	ppb		
PFOS	0.457 J	0.24 J	0.224 J

Sample Location	SB-1		
Sample Depth (ft-bg)	0-2	6-8	21-23
Date	1/6/2026		
SVOCs	ppm		
Benzo(a)anthracene	1.26 D	0.0498 JD	ND
Benzo(a)pyrene	1.28 D	ND	ND
Benzo(b)fluoranthene	1.12 D	ND	ND
Benzo(g,h,i)perylene	0.658 D	ND	ND
Benzo(k)fluoranthene	1.13 D	ND	ND
Chrysene	1.25 D	ND	ND
Dibenzo(a,h)anthracene	0.322 D	ND	ND
Indeno(1,2,3-cd)pyrene	0.792 D	ND	ND
Phenanthrene	0.503 D	ND	ND
Total Metals			
Arsenic	4.55	ND	ND
Barium	798	31.2	16.4
Copper	38.4	16	7.73
Lead	908	2.46	1.72
Manganese	275	260	210
Mercury	0.201	ND	ND
Nickel	13.6	11	5.25
Zinc	368	12.4	10.7
Chromium, Hexavalent	1.26	ND	ND
Chromium, Trivalent	15.9	7.75	5.9
Pesticides			
4,4'-DDD	ND	ND	ND
4,4'-DDE	ND	ND	ND
4,4'-DDT	ND	ND	ND
PFAS	ppb		
PFOS	ND	ND	ND

Sample Location	SB-6		
Sample Depth (ft-bg)	0-2	8-10	22-24
Date	1/5/2026		
SVOCs	ppm		
Benzo(a)anthracene	0.158 D	ND	ND
Benzo(a)pyrene	0.216 D	ND	ND
Benzo(b)fluoranthene	0.188 D	ND	ND
Benzo(g,h,i)perylene	0.121 D	ND	ND
Benzo(k)fluoranthene	0.178 D	ND	ND
Chrysene	0.173 D	ND	ND
Dibenzo(a,h)anthracene	ND	ND	ND
Indeno(1,2,3-cd)pyrene	0.0971 D	ND	ND
Phenanthrene	0.162 D	ND	ND
Total Metals			
Arsenic	5.93	1.58	3.2
Barium	1590	38.7	65.7
Copper	21.9	36.5	38.4
Lead	841	67.1	29.1
Manganese	264	125	219
Mercury	0.66	0.713	0.151
Nickel	11.2	19.4	21.5
Zinc	550	17.9	34.7
Chromium, Hexavalent	ND	ND	2.01
Chromium, Trivalent	18.9	21.1	55.2
Pesticides			
4,4'-DDD	ND	ND	ND
4,4'-DDE	ND	ND	ND
4,4'-DDT	ND	ND	ND
PFAS	ppb		
PFOS	0.732	ND	ND

Sample Location	SB-8		
Sample Depth (ft-bg)	0-2	8-10	22-24
Date	1/5/2026	1/6/2026	
SVOCs	ppm		
Benzo(a)anthracene	0.649 D	ND	ND
Benzo(a)pyrene	0.726 D	ND	ND
Benzo(b)fluoranthene	0.648 D	ND	ND
Benzo(g,h,i)perylene	0.417 D	ND	ND
Benzo(k)fluoranthene	0.647 D	ND	ND
Chrysene	0.69 D	ND	ND
Dibenzo(a,h)anthracene	0.139 D	ND	ND
Indeno(1,2,3-cd)pyrene	0.352 D	ND	ND
Phenanthrene	0.904 D	ND	ND
Total Metals			
Arsenic	15.8	2.81	ND
Barium	2430	79.6	50.9
Copper	129	79.2	ND
Lead	1230	6.57	3.45
Manganese	482	585	2410
Mercury	2.52	ND	ND
Nickel	23.3	36.5	2.72
Zinc	877	31.9	5.01
Chromium, Hexavalent	ND	0.581	ND
Chromium, Trivalent	29.1	30.4	0.505
Pesticides			
4,4'-DDD	ND	ND	ND
4,4'-DDE	ND	ND	ND
4,4'-DDT	ND	ND	ND
PFAS	ppb		
PFOS	ND	ND	0.0753 J

Sample Location	SB-2			
Sample Depth (ft-bg)	0-2	0-2 (DUP)	6-8	22-24
Date	1/6/2026			
SVOCs	ppm			
Benzo(a)anthracene	16.7 D	0.403 D	0.22 D	ND
Benzo(a)pyrene	13.6 D	0.344 D	0.166 D	ND
Benzo(b)fluoranthene	24.1 D	0.32 D	0.154 D	ND
Benzo(g,h,i)perylene	8.99 D	0.21 D	0.0992 D	ND
Benzo(k)fluoranthene	ND	0.298 D	0.145 D	ND
Chrysene	16.4 D	0.39 D	0.218 D	ND
Dibenzo(a,h)anthracene	1.43 D	0.0852 JD	ND	ND
Indeno(1,2,3-cd)pyrene	7.26 D	0.257 D	0.127 D	ND
Phenanthrene	23.3 D	0.451 D	0.278 D	ND
Total Metals				
Arsenic	6.04	3.41	1.75	2.38
Barium	2370	494	53.6	88.1
Copper	27.8	31.4	25.4	62.8
Lead	4430	160	5.16	7.5
Manganese	376	197	256	294
Mercury	0.53	ND	0.0732	ND
Nickel	13.6	10.7	11.7	14.3
Zinc	848	223	13.5	25.2
Chromium, Hexavalent	ND	1.22	0.739	1.06
Chromium, Trivalent	13.3	10.3	14.5	16.6
Pesticides				
4,4'-DDD	ND	ND	ND	ND
4,4'-DDE	0.00289 DP	ND	ND	ND
4,4'-DDT	0.0138 D	0.00234 D	ND	ND
PFAS	ppb			
PFOS	0.218 J	1.38	ND	ND

Sample Location	SB-9		
Sample Depth (ft-bg)	0-2	6-8	22-24
Date	1/6/2026		
SVOCs	ppm		
Benzo(a)anthracene	5.94 D	0.104 D	ND
Benzo(a)pyrene	4.44 JD	0.0822 JD	ND
Benzo(b)fluoranthene	3.04 D	0.0691 JD	ND
Benzo(g,h,i)perylene	1.97 D	0.0493 JD	ND
Benzo(k)fluoranthene	2.66 D	0.0609 JD	ND
Chrysene	5.4 D	0.0876 D	ND
Dibenzo(a,h)anthracene	0.79 D	ND	ND
Indeno(1,2,3-cd)pyrene	2.29 D	0.0513 JD	ND
Phenanthrene	9.58 D	0.172 D	ND
Total Metals			
Arsenic	9.19	2.06	2.64
Barium	3160	168	82.3
Copper	18.4	72	103
Lead	3160	1.36	3.77
Manganese	273	495	344
Mercury	1.25	0.0617	ND
Nickel	14.7	19.1	9.48
Zinc	1730	59.2	32.9
Chromium, Hexavalent	5.08	0.574	0.647
Chromium, Trivalent	11.6	12.8	4.37
Pesticides			
4,4'-DDD	ND	ND	ND
4,4'-DDE	ND	ND	ND
4,4'-DDT	ND	ND	ND
PFAS	ppb		
PFOS	ND	ND	ND

Analyte	NY-UNRES	NY-PGW	NY-RESRR
SVOCs	ppm		
Benzo(a)anthracene	1	--	1.4
Benzo(a)pyrene	1	--	1
Benzo(b)fluoranthene	1	--	1.4
Benzo(g,h,i)perylene	0.64	--	4.9
Benzo(k)fluoranthene	0.8	--	4.9
Chrysene	1	--	4.9
Dibenzo(a,h)anthracene	0.33	--	0.33
Indeno(1,2,3-cd)pyrene	0.5	--	1.4
Phenanthrene	1.1	--	4.9
Total Metals			
Arsenic	13	--	16
Barium	410	--	410
Copper	50	--	280
Lead	63	--	400
Manganese	1,600	2,000	2,000
Mercury	0.18	--	0.3
Nickel	30	--	320
Zinc	109	--	6,600
Chromium, Hexavalent	1	--	1
Chromium, Trivalent	30	--	110
Pesticides			
4,4'-DDD	0.0033	--	5
4,4'-DDE	0.0033	--	3.4
4,4'-DDT	0.0033	--	3.8
PFAS	ppb		
PFOS	0.88	1	44

Notes:

1. **Bold and shaded yellow value indicates concentration exceeds NY-UNRES SCOs**
2. **Bold and shaded blue value indicates concentration exceeds NY-UNRES and NY-PGW SCOs**
3. **Bold and shaded orange value indicates concentration exceeds NY-UNRES and NY-RESRR SCOs**
4. **Bold and shaded red value indicates concentration exceeds NY-UNRES, NY-PGW, and NY-RESRR SCOs**
5. NY-UNRES = 6 NYCRR Part 375 Unrestricted Use Soil Cleanup Objectives
6. NY-PGW = 6 NYCRR Part 375 Restricted Protection of Groundwater Soil Cleanup Objectives
7. NY-RESRR = 6 NYCRR Part 375 Restricted-Residential Use Soil Cleanup Objectives
8. J = Estimated value
9. D = Diluted
10. ND = Not detected
11. Only manganese and PFOS are compared to the NY-PGW SCOs, as these analytes also exceeded the Class GA Standards in one or more onsite groundwater monitoring wells sampled as part of this RI.

Legend

- Soil Boring Location
- NYC Tax Lots
- Site Boundary
- Former Building Footprint Extents

Note:
The former basement slab depth is approximately 10 ft-bg.

0 15 30 60 Feet

Reference:
6/1/2024 Nearmap Aerial
Parcel Boundaries: Contributing counties, NYS Office of Information Technology Services GIS Program Office (GPO) and NYS Department of Taxation and Finance's Office of Real Property Tax Services (ORPTS).


260 West 126th Street
New York, New York
Block 1931, Lot 56

TENEN ENVIRONMENTAL
Tenen Environmental, LLC
465 East 188th Street, #112
Bronx, NY 10458
O: (646) 606-2332; F: (646) 606-2379

Drawn By: LM
Checked By: AP
Date: September 2026
Scale: As Noted

Drawing Title: Soil Analytical Results

Drawing No.: Figure 9



Sample ID	MW-5
Date	7/9/2026
Total Metals	**ppb**
Manganese	66.4
Sodium	**61,500**
Dissolved Metals	
Manganese	61.2
Sodium	**60,500**
PFAS	**ppt**
PFOS	**101.737**
PFOA	**23.236**

Sample ID	MW-3
Date	1/22/2026
Total Metals	**ppb**
Manganese	7.22
Sodium	**75,900**
Dissolved Metals	
Manganese	ND
Sodium	**72,800**
PFAS	**ppt**
PFOS	**67.6**
PFOA	**8.29**

Sample ID	MW-1
Date	1/22/2026
Total Metals	**ppb**
Manganese	ND
Sodium	**69,200**
Dissolved Metals	
Manganese	ND
Sodium	**67,300**
PFAS	**ppt**
PFOS	**30.9**
PFOA	**31.3**

Sample ID	MW-4
Date	7/9/2026
Total Metals	**ppb**
Manganese	37
Sodium	**63,500**
Dissolved Metals	
Manganese	16.7
Sodium	**62,000**
PFAS	**ppt**
PFOS	**72.601**
PFOA	**17.053**

Sample ID	MW-6	
Date	1/22/2026	1/22/2026 (DUP)
Total Metals	**ppb**	
Manganese	**567**	**540**
Sodium	**82,300**	**82,500**
Dissolved Metals		
Manganese	**574**	**551**
Sodium	**82,000**	**80,300**
PFAS	**ppt**	
PFOS	**24.2**	**25**
PFOA	**10.4**	**12**

Sample ID	MW-2
Date	1/22/2026
Total Metals	**ppb**
Manganese	**353**
Sodium	**66,200**
Dissolved Metals	
Manganese	**352**
Sodium	**63,900**
PFAS	**ppt**
PFOS	**11.5**
PFOA	**14.8**

Analyte	NY-AWQS
Total Metals	**ppb**
Manganese	300
Sodium	20,000
Dissolved Metals	
Manganese	300
Sodium	20,000
PFAS	**ppt**
PFOS	2.7
PFOA	6.7

Notes:

1. Bold and shaded yellow value indicates concentration exceeds NY-AWQS

2. NY-AWQS = NYSDEC Division of Technical and Operational Guidance Series (TOGS) 1.1.1 Ambient Water Quality Standards (AWQS)

3. ND = Not detected

4. ppb = parts per billion

5. ppt = parts per trillion

Legend

- Monitoring Well Location
- NYC Tax Lots
- Site Boundary
- Former Building Footprint Extents

Note:
The former basement slab depth is approximately 10 ft-bg.

0 15 30 60 Feet

Reference:
6/1/2024 Nearmap Aerial
Parcel Boundaries: Contributing counties, NYS Office of Information Technology Services GIS Program Office (GPO) and NYS Department of Taxation and Finance's Office of Real Property Tax Services (ORPTS).


260 West 126th Street
New York, New York
Block 1931, Lot 56

TENEN ENVIRONMENTAL
Tenen Environmental, LLC
465 East 188th Street, #112
Bronx, NY 10458
O: (646) 606-2332; F: (646) 606-2379

Drawn By: LM
Checked By: AP
Date: September 2026
Scale: As Noted

Drawing Title: Groundwater Analytical Results

Drawing No.: Figure 10



Sample ID:	SV-2
Date:	1/22/2026
Sampling Depth:	8 ft-bg
VOCs	µg/m³
1,2,4-Trimethylbenzene	0.265 U
2,2,4-Trimethylpentane	0.374 U
2-Butanone	**2.270 J**
4-Methyl-2-pentanone	**30.302**
Acetone	**26.119**
Acrylonitrile	3.254 U
Benzene	1.022
Carbon disulfide	**0.560**
Chloroform	0.22 U
Dichlorodifluoromethane	**2.126**
Ethyl Benzene	**1.042**
Isopropylbenzene	0.143 U
Methylene chloride	0.187 U
n-Hexane	0.634
o-Xylene	**1.519**
p- & m- Xylenes	**4.167**
Propylene	**0.585**
Tetrachloroethylene	**1.085**
Tetrahydrofuran	**0.855 J**
Toluene	**4.520**
Trichlorofluoromethane	**1.067**
Xylenes, Total	**5.642**

Sample ID:	AA-1
Date:	1/22/2026
VOCs	µg/m³
1,2,4-Trimethylbenzene	0.118 U
2,2,4-Trimethylpentane	0.56
2-Butanone	0.943 J
4-Methyl-2-pentanone	0.131 U
Acetone	8.073 J
Acrylonitrile	17.571
Benzene	1.022
Carbon disulfide	0.0591 U
Chloroform	0.0976 U
Dichlorodifluoromethane	1.780
Ethyl Benzene	0.317
Isopropylbenzene	0.0639 U
Methylene chloride	0.0833 U
n-Hexane	0.705
o-Xylene	0.317
p- & m- Xylenes	0.868
Propylene	0.0705 U
Tetrachloroethylene	0.115 U
Tetrahydrofuran	0.0708 U
Toluene	1.733
Trichlorofluoromethane	1.011
Xylenes, Total	1.215

Sample ID:	SV-3
Date:	1/22/2026
Sampling Depth:	8 ft-bg
VOCs	µg/m³
1,2,4-Trimethylbenzene	**1.081**
2,2,4-Trimethylpentane	0.35 U
2-Butanone	**1.415 J**
4-Methyl-2-pentanone	0.27 U
Acetone	**17.334 J**
Acrylonitrile	3.037 U
Benzene	**1.182**
Carbon disulfide	**0.778**
Chloroform	0.205 U
Dichlorodifluoromethane	**2.224**
Ethyl Benzene	**0.825**
Isopropylbenzene	0.133 U
Methylene chloride	0.174 U
n-Hexane	0.166 U
o-Xylene	**1.302**
p- & m- Xylenes	**3.385**
Propylene	**0.895**
Tetrachloroethylene	**1.220**
Tetrahydrofuran	0.147 U
Toluene	**9.417**
Trichlorofluoromethane	**1.067**
Xylenes, Total	**4.774**

Sample ID:	SV-7
Date:	7/9/2026
Sampling Depth:	11 ft-bg
VOCs	µg/m³
1,2,4-Trimethylbenzene	0.23 U
2,2,4-Trimethylpentane	0.33 U
2-Butanone	0.71 U
4-Methyl-2-pentanone	0.26 U
Acetone	4.5 J
Acrylonitrile	**9.7 J**
Benzene	0.16 U
Carbon disulfide	0.11 U
Chloroform	0.19 U
Dichlorodifluoromethane	**2**
Ethyl Benzene	0.21 U
Isopropylbenzene	0.13 U
Methylene chloride	0.17 U
n-Hexane	0.16 U
o-Xylene	0.22 U
p- & m- Xylenes	0.32 U
Propylene	0.14 U
Tetrachloroethylene	0.23 U
Tetrahydrofuran	0.14 U
Toluene	0.59
Trichlorofluoromethane	1.3
Xylenes, Total	0.51 U

Sample ID:	AA-2
Date:	7/9/2026
VOCs	µg/m³
1,2,4-Trimethylbenzene	0.23 U
2,2,4-Trimethylpentane	0.33 U
2-Butanone	1.2 J
4-Methyl-2-pentanone	0.26 U
Acetone	9 J
Acrylonitrile	2.9 U
Benzene	0.54
Carbon disulfide	0.11 U
Chloroform	0.19 U
Dichlorodifluoromethane	1.9
Ethyl Benzene	0.21 U
Isopropylbenzene	0.13 U
Methylene chloride	0.17 U
n-Hexane	0.75
o-Xylene	0.22 U
p- & m- Xylenes	1.4
Propylene	0.14 U
Tetrachloroethylene	0.23 U
Tetrahydrofuran	0.14 U
Toluene	1.5
Trichlorofluoromethane	1.3
Xylenes, Total	1.4 J

Sample ID:	SV-6
Date:	1/22/2026
Sampling Depth:	8 ft-bg
VOCs	µg/m³
1,2,4-Trimethylbenzene	0.241 U
2,2,4-Trimethylpentane	0.346 U
2-Butanone	**2.182 J**
4-Methyl-2-pentanone	0.266 U
Acetone	**23.745**
Acrylonitrile	3.037 U
Benzene	0.990
Carbon disulfide	**9.339**
Chloroform	0.2 U
Dichlorodifluoromethane	**2.175**
Ethyl Benzene	**1.085**
Isopropylbenzene	0.133 U
Methylene chloride	0.17 U
n-Hexane	**1.867**
o-Xylene	**1.519**
p- & m- Xylenes	**4.210**
Propylene	**2.581**
Tetrachloroethylene	**3.525**
Tetrahydrofuran	**1.297**
Toluene	**6.027**
Trichlorofluoromethane	**1.179**
Xylenes, Total	**5.642**

Sample ID:	SV-1
Date:	1/22/2026
Sampling Depth:	22 ft-bg
VOCs	µg/m³
1,2,4-Trimethylbenzene	0.211 U
2,2,4-Trimethylpentane	**1.027**
2-Butanone	**1.504 J**
4-Methyl-2-pentanone	0.233 U
Acetone	**21.133**
Acrylonitrile	2.603 U
Benzene	0.894
Carbon disulfide	0.103 U
Chloroform	**8.297**
Dichlorodifluoromethane	**1.829**
Ethyl Benzene	**1.085**
Isopropylbenzene	**0.251 J**
Methylene chloride	**0.177 J**
n-Hexane	**1.691**
o-Xylene	**1.693**
p- & m- Xylenes	**4.036**
Propylene	**0.585**
Tetrachloroethylene	**5.627**
Tetrahydrofuran	**1.769**
Toluene	**4.144**
Trichlorofluoromethane	0.955
Xylenes, Total	**5.642**

Sample ID:	SV-5
Date:	1/22/2026
Sampling Depth:	8 ft-bg
VOCs	µg/m³
1,2,4-Trimethylbenzene	0.256 U
2,2,4-Trimethylpentane	0.36 U
2-Butanone	**1.032 J**
4-Methyl-2-pentanone	0.278 U
Acetone	**10.448 J**
Acrylonitrile	3.254 U
Benzene	0.176 U
Carbon disulfide	**0.778**
Chloroform	0.21 U
Dichlorodifluoromethane	**2.126**
Ethyl Benzene	**0.738**
Isopropylbenzene	0.138 U
Methylene chloride	0.181 U
n-Hexane	0.423 J
o-Xylene	**1.215**
p- & m- Xylenes	**3.082**
Propylene	**2.236**
Tetrachloroethylene	**4.000**
Tetrahydrofuran	0.153 U
Toluene	**2.034**
Trichlorofluoromethane	1.011
Xylenes, Total	**4.297**

Sample ID:	SV-4
Date:	1/22/2026
Sampling Depth:	8 ft-bg
VOCs	µg/m³
1,2,4-Trimethylbenzene	0.236 U
2,2,4-Trimethylpentane	0.336 U
2-Butanone	0.708 U
4-Methyl-2-pentanone	0.262 U
Acetone	**12.585 J**
Acrylonitrile	3.037 U
Benzene	0.607
Carbon disulfide	0.115 U
Chloroform	0.195 U
Dichlorodifluoromethane	**1.977**
Ethyl Benzene	0.208 U
Isopropylbenzene	0.128 U
Methylene chloride	0.167 U
n-Hexane	0.159 U
o-Xylene	**0.738**
p- & m- Xylenes	**2.040**
Propylene	0.141 U
Tetrachloroethylene	0.231 U
Tetrahydrofuran	0.142 U
Toluene	**1.770**
Trichlorofluoromethane	0.955
Xylenes, Total	**2.821**

Notes:

1. Concentrations detected in soil vapor are compared to ambient a (AA-1 or AA-2) concentrations.
2. **Bold and shaded gray value indicates concentration exceeds ambient air concentration.**
3. Soil vapor samples SV-1, SV-2, SV-3, SV-4, SV-5, and SV-6 are compared to AA-1 concentrations. Soil vapor sample SV-7 is compared to AA-2 concentrations.
4. U = Analyte not detected at or above the detection level indicated.
5. J = Estimated concentration
6. µg/m3 = micrograms per cubic meter
7. Soil vapor sample SV-7 was collected 1 foot beneath the basement slab of the former onsite building. The basement slab is approximately 10 feet below Site grade.
8. ft-bg = feet below Site grade

Legend

- Soil Vapor Sampling Location
- Ambient Air Sample Location
- NYC Tax Lots
- Site Boundary
- Former Building Footprint Extents

Note:
The former basement slab depth is approximately 10 ft-bg.

0 15 30 60 Feet

Reference:
6/1/2024 Nearmap Aerial
Parcel Boundaries: Contributing counties, NYS Office of Information Technology Services GIS Program Office (GPO) and NYS Department of Taxation and Finance's Office of Real Property Tax Services (ORPTS).


260 West 126th Street
New York, New York
Block 1931, Lot 56

TENEN ENVIRONMENTAL
Tenen Environmental, LLC
465 East 188th Street, #112
Bronx, NY 10458
O: (646) 606-2332; F: (646) 606-2379


Drawn By: LM
Checked By: AP
Date: September 2026
Scale: As Noted

Drawing Title: Soil Vapor Analytical Results


Drawing No.: Figure 11




Profile A-A'




Profile B-B'





Plan View



Legend

- Soil Boring Sample Location
- NYC Tax Lots
- Site Boundary

C&D = Construction & Demolition Debris

The former building foundation is approximately 10 ft-bg and was backfilled to grade with C&D from the building demolition.

Borings were ended at 30 ft-bg

Reference:
6/1/2024 Nearmap Aerial
Parcel Boundaries: Contributing counties, NYS Office of Information Technology Services GIS Program Office (GPO) and NYS Department of Taxation and Finance's Office of Real Property Tax Services (ORPTS).

260 West 126th Street
New York, New York
Block 1931, Lot 56

TENEN ENVIRONMENTAL
Tenen Environmental, LLC
465 East 188th Street, #112
Bronx, NY 10458
O: (646) 606-2332; F: (646) 606-2379

Drawn By	Checked By	Date	Scale
LM	AP	September 2026	As Noted

Drawing Title: Geologic Cross Section

Drawing No.: Figure 12

Legend

- School
- Day Care
- Health Care Facility
- 1/4-Mile Radius Around Site Boundary
- Site Boundary

0 200 400 800 Feet

Reference:
Source: NYC OTI - 2024 Aerial
Parcel Boundaries: Contributing counties, NYS Office of Information Technology Services GIS Program Office (GPO) and NYS Department of Taxation and Finance's Office of Real Property Tax Services (ORPTS).

260 West 126th Street
New York, New York
Block 1931, Lot 56

TENEN ENVIRONMENTAL
Tenen Environmental, LLC
465 East 188th Street, #112
Bronx, NY 10458
O: (646) 606-2332; F: (646) 606-2379

Drawn By	LM
Checked By	SB
Date	September 2026
Scale	As Noted

Drawing Title: Sensitive Receptor Map

Drawing No.: Figure 13

Tables

Table 1. Summary of Historic Soil Sample Exceedances
260 West 126th Street - New York, NY
BCP Site No. C231164

LOCATION	NY-UNRES	NY-RESRR	Units	SB-1	SB-1	SB-2	SB-2	SB-3
SAMPLE DEPTH (FT-BG)				0-2	2-4	0-2	10-12	0-2
SAMPLING DATE				11/15/2016	11/15/2016	11/10/2016	11/10/2016	11/10/2016
LAB SAMPLE ID				BV85796	BV85797	BV81727	BV81728	BV81729
				Qual	Qual	Qual	Qual	Qual
Semivolatile Organic Compounds								
Benzo(a)anthracene	1	1.4	ppm	ND	ND	0.18	ND	0.67
Benzo(a)pyrene	1	1	ppm	ND	ND	0.19	ND	0.68
Benzo(b)fluoranthene	1	1.4	ppm	ND	ND	0.2	ND	0.69
Benzo(k)fluoranthene	0.8	4.9	ppm	ND	ND	0.18	ND	0.65
Chrysene	1	4.9	ppm	ND	ND	0.26	0.15	0.83
Indeno(1,2,3-cd)pyrene	0.5	1.4	ppm	ND	ND	0.13	ND	0.49
Total Metals								
Arsenic	13	16	ppm	2.38	1.45	4.6	2.9	7.95
Barium	410	410	ppm	56.7	35.6	102	142	**901**
Chromium	30	110	ppm	15.4	12.8	14.1	15.6	28.1
Copper	50	280	ppm	19.9	14	**76.4**	47.8	**67.4**
Lead	63	400	ppm	38.3	23.4	**138**	**189**	**562**
Mercury	0.18	0.3	ppm	**0.53**	ND	0.02	**0.48**	**0.25**
Nickel	30	320	ppm	14.6	14.4	**43.6**	13.4	**36.1**
Zinc	109	6,600	ppm	30.5	16.8	**167**	75.3	**685**
Pesticides								
4,4'-DDE	0.0033	3.4	ppm	ND	ND	ND	ND	**0.022**
4,4'-DDT	0.0033	3.8	ppm	ND	ND	ND	ND	**0.025**

Notes:

Bold and shaded yellow value indicates concentration exceeds NY-UNRES SCOs

Bold and shaded orange value indicates concentration exceeds NY-RESRR SCOs

NY-UNRES = 6 NYCRR Part 375 Unrestricted Use Soil Cleanup Objectives

NY-RESRR = 6 NYCRR Part 375 Restricted-Residential Soil Cleanup Objectives

ND = Not detected

ppm = parts-per-million

Table 1. Summary of Historic Soil Sample Exceedances
260 West 126th Street - New York, NY
BCP Site No. C231164

LOCATION	NY-UNRES	NY-RESRR	Units	SB-3	SB-4	SB-4	SB-5	SB-5	SB-6
SAMPLE DEPTH (FT-BG)				10-12	0-2	10-12	0-2	10-12	0-2
SAMPLING DATE				11/10/2016	11/10/2016	11/10/2016	11/10/2016	11/10/2016	11/15/2016
LAB SAMPLE ID				BV81730	BV81731	BV81732	BV81733	BV81734	BV85798
				Qual	Qual	Qual	Qual	Qual	Qual
Semivolatile Organic Compounds									
Benzo(a)anthracene	1	1.4	ppm	ND	0.28	0.51	**1.1**	ND	ND
Benzo(a)pyrene	1	1	ppm	ND	0.3	0.54	**1.1**	ND	ND
Benzo(b)fluoranthene	1	1.4	ppm	ND	0.25	0.55	**1.1**	ND	ND
Benzo(k)fluoranthene	0.8	4.9	ppm	ND	0.27	0.53	**1.1**	ND	ND
Chrysene	1	4.9	ppm	ND	0.31	0.65	**1.3**	ND	ND
Indeno(1,2,3-cd)pyrene	0.5	1.4	ppm	ND	0.18	0.45	**0.81**	ND	ND
Total Metals									
Arsenic	13	16	ppm	1.78	6.67	5.65	**15.7**	1.52	3.05
Barium	410	410	ppm	154	**993**	394	**729**	33	56.2
Chromium	30	110	ppm	16.1	**44.1**	**30.2**	14.7	19	8.48
Copper	50	280	ppm	26.1	36.2	45.1	28.4	26.8	14.1
Lead	63	400	ppm	**134**	**642**	**247**	**2,040**	4.1	**235**
Mercury	0.18	0.3	ppm	0.04	**0.25**	0.16	**0.34**	ND	**0.45**
Nickel	30	320	ppm	**34.6**	**228**	**67.7**	14.2	14.1	9.77
Zinc	109	6,600	ppm	81.5	**664**	**260**	**690**	29.2	92.8
Pesticides									
4,4'-DDE	0.0033	3.4	ppm	ND	ND	ND	ND	ND	**0.012**
4,4'-DDT	0.0033	3.8	ppm	ND	ND	ND	ND	ND	**0.0039**

Notes:

Bold and shaded yellow value indicates concentration exceeds NY-UNRES SCOs

Bold and shaded orange value indicates concentration exceeds NY-RESRR SCOs

NY-UNRES = 6 NYCRR Part 375 Unrestricted Use Soil Cleanup Objectives

NY-RESRR = 6 NYCRR Part 375 Restricted-Residential Soil Cleanup Objectives

ND = Not detected

ppm = parts-per-million

Table 1. Summary of Historic Soil Sample Exceedances
260 West 126th Street - New York, NY
BCP Site No. C231164

LOCATION	NY-UNRES	NY-RESRR	Units	SB-6	SB-7	SB-7	SB-8	SB-8
SAMPLE DEPTH (FT-BG)				2-4	0-2	10-12	0-2	10-12
SAMPLING DATE				11/15/2016	11/10/2016	11/10/2016	11/10/2016	11/10/2016
LAB SAMPLE ID				BV85799	BV81735	BV81736	BV81737	BV81738
				Qual	Qual	Qual	Qual	Qual
Semivolatile Organic Compounds								
Benzo(a)anthracene	1	1.4	ppm	ND	0.34	ND	0.14	0.66
Benzo(a)pyrene	1	1	ppm	ND	0.33	ND	0.12	0.65
Benzo(b)fluoranthene	1	1.4	ppm	ND	0.27	ND	ND	0.57
Benzo(k)fluoranthene	0.8	4.9	ppm	ND	0.28	ND	0.12	0.63
Chrysene	1	4.9	ppm	ND	0.36	ND	0.14	0.71
Indeno(1,2,3-cd)pyrene	0.5	1.4	ppm	ND	0.23	ND	ND	0.43
Total Metals								
Arsenic	13	16	ppm	2.26	8.51	2.71	1.91	7.13
Barium	410	410	ppm	122	**2,760**	131	73.6	**703**
Chromium	30	110	ppm	26.9	27.7	**35.5**	16.8	17.5
Copper	50	280	ppm	32.5	**53.9**	**64.5**	35.3	19.6
Lead	63	400	ppm	21.2	**696**	58.3	30.8	**782**
Mercury	0.18	0.3	ppm	0.09	**0.26**	**0.42**	**0.23**	**0.75**
Nickel	30	320	ppm	30	19.2	26.2	15.9	13.6
Zinc	109	6,600	ppm	38.9	**1,960**	83.5	37.5	**400**
Pesticides								
4,4'-DDE	0.0033	3.4	ppm	**0.0038**	ND	ND	ND	ND
4,4'-DDT	0.0033	3.8	ppm	**0.013**	**0.0048**	ND	ND	ND

Notes:

Bold and shaded yellow value indicates concentration exceeds NY-UNRES SCOs

Bold and shaded orange value indicates concentration exceeds NY-RESRR SCOs

NY-UNRES = 6 NYCRR Part 375 Unrestricted Use Soil Cleanup Objectives

NY-RESRR = 6 NYCRR Part 375 Restricted-Residential Soil Cleanup Objectives

ND = Not detected

ppm = parts-per-million

Table 2. Summary of Historic Groundwater Sample Exceedances
260 West 126th Street - New York, NY
BCP Site No. C231164

LOCATION	NY-AWQS	Units	MW1	MW2	MW3	MW4
SAMPLING DATE			11/18/2016	11/18/2016	11/18/2016	11/18/2016
LAB SAMPLE ID			BV88459	BV88460	BV88461	BV88462
			Qual	Qual	Qual	Qual
Semivolatile Organic Compounds						
Benzo(a)anthracene	0.002	ppb	ND	ND	**0.03**	**0.38**
Benzo(a)pyrene	0	ppb	ND	ND	ND	**0.38**
Benzo(b)fluoranthene	0.002	ppb	ND	ND	ND	**0.34**
Benzo(k)fluoranthene	0.002	ppb	ND	ND	ND	**0.3**
Chrysene	0.002	ppb	ND	ND	ND	**0.39**
Indeno(1,2,3-cd)pyrene	0.002	ppb	ND	ND	ND	**0.26**
Total Metals						
Arsenic	25	ppb	**54**	**41**	**47**	**65**
Barium	1,000	ppb	**4,960**	**3,630**	**4,110**	**5,620**
Beryllium	3	ppb	**24**	**19**	**17**	**28**
Cadmium	5	ppb	**14**	**9**	**10**	**17**
Chromium	50	ppb	**304**	**236**	**710**	**559**
Copper	200	ppb	**2,260**	**1,830**	**1,740**	**2,400**
Iron	300	ppb	**264,000**	**191,000**	**349,000**	**376,000**
Lead	25	ppb	**408.00**	**160**	**347**	**535**
Magnesium	35,000	ppb	**90,500**	**75,400**	**128,000**	**146,000**
Manganese	300	ppb	**71,100**	**41,700**	**52,000**	**84,700**
Nickel	100	ppb	**1,160**	**880**	**754**	**1,330**
Sodium	20,000	ppb	**226,000**	**148,000**	**165,000**	**177,000**
Thallium	0.5	ppb	ND	ND	**1**	ND

Notes:

Bold and shaded yellow value indicates concentration exceeds NY-AWQS

NY-AWQS = NYSDEC Division of Technical and Operational Guidance Series (TOGS) 1.1.1 Ambient Water Quality Standards

ND = Not detected

ppb = parts-per-billion

Table 3. Summary of Volatile Organic Compounds in Historic Soil Vapor Samples
260 West 126th Street - New York, NY
BCP Site No. C231164

LOCATION	Units	SG1	SG2	SG3	SG4	SG5
SAMPLING DATE		11/18/2016	11/18/2016	11/18/2016	11/18/2016	11/18/2016
LAB SAMPLE ID		BV88458	BV88456	BV88457	BV88455	BV88454
		Qual	Qual	Qual	Qual	Qual
Volatile Organic Compounds						
Trichloroethene	ug/m^3	0.38	ND	ND	0.27	0.62
cis-1,2-Dichloroethene	ug/m^3	ND	ND	ND	ND	ND
1,1-Dichloroethene	ug/m^3	ND	ND	ND	ND	ND
Carbon tetrachloride	ug/m^3	0.52	0.34	0.32	0.35	0.31
Tetrachloroethene	ug/m^3	11.3	5.24	3.99	7.25	16.5
1,1,1-Trichloroethane	ug/m^3	ND	ND	ND	ND	ND
Methylene chloride	ug/m^3	ND	ND	ND	ND	ND
Vinyl chloride	ug/m^3	ND	ND	ND	ND	ND
Benzene	ug/m^3	2.64	2.88	1.98	3.29	11.3
Ethylbenzene	ug/m^3	3.95	1.38	1.28	1.89	1.94
Cyclohexane	ug/m^3	15.2	ND	ND	ND	3.29
1,2,4-Trimethylbenzene	ug/m^3	4.69	1.39	ND	2.2	2.14
1,3,5-Trimethylbenzene	ug/m^3	1.29	ND	ND	ND	ND
o-Xylene	ug/m^3	4.95	1.73	1.64	2.37	2.48
p/m-Xylene	ug/m^3	13.6	5.81	5.12	6.64	6.68
Heptane	ug/m^3	2.58	1.05	ND	1.14	1.45
Hexane	ug/m^3	6.73	2.03	ND	1.68	16.1
Toluene	ug/m^3	16.3	8.78	16.5	15.1	15.3

Notes:

ND = Not detected

ug/m^3 = micrograms per cubic meter

Table 4a. Volatile Organic Compounds in Soil
260 West 126th Street - New York, NY
BCP Site No. C231164

CLIENT SAMPLE ID	NY-UUSCO	NY-RESRR	Units	SB-5 (0-2)	SB-5 (12.5-14.5)	SB-5 (22-24)	SB-5 (22-24)_DUP
SAMPLING DATE				1/5/2026	1/5/2026	1/5/2026	1/5/2026
SAMPLE DEPTH (FT-BG)				0-2	12.5-14.5	22-24	22-24
LAB SAMPLE ID				26A0061-01	26A0061-02	26A0061-03	26A0061-04
				Qual	Qual	Qual	Qual
General Chemistry							
Solids, Total	NS	NS	%	86.4	97.7	98	98.3
Volatile Organic Compounds							
1,1,1,2-Tetrachloroethane	NS	NS	ppm	ND	ND	ND	ND
1,1,1-Trichloroethane	0.68	100	ppm	ND	ND	ND	ND
1,1,2,2-Tetrachloroethane	NS	NS	ppm	ND	ND	ND	ND
1,1,2-Trichloro-1,2,2-trifluoroethane (Freon 113)	NS	NS	ppm	ND	ND	ND	ND
1,1,2-Trichloroethane	NS	NS	ppm	ND	ND	ND	ND
1,1-Dichloroethane	0.27	47	ppm	ND	ND	ND	ND
1,1-Dichloroethylene	0.24	0.98	ppm	ND	ND	ND	ND
1,1-Dichloropropylene	NS	NS	ppm	ND	ND	ND	ND
1,2,3-Trichlorobenzene	NS	NS	ppm	ND	ND	ND	ND
1,2,3-Trichloropropane	NS	NS	ppm	ND	ND	ND	ND
1,2,4-Trichlorobenzene	NS	NS	ppm	ND	ND	ND	ND
1,2,4-Trimethylbenzene	5.9	100	ppm	ND	ND	ND	ND
1,2-Dibromo-3-chloropropane	NS	NS	ppm	ND	ND	ND	ND
1,2-Dibromoethane	NS	NS	ppm	ND	ND	ND	ND
1,2-Dichlorobenzene	1.1	100	ppm	ND	ND	ND	ND
1,2-Dichloroethane	0.02	5.8	ppm	ND	ND	ND	ND
1,2-Dichloropropane	NS	NS	ppm	ND	ND	ND	ND
1,3,5-Trimethylbenzene	3.1	100	ppm	ND	ND	ND	ND
1,3-Dichlorobenzene	2.6	38	ppm	ND	ND	ND	ND
1,3-Dichloropropane	NS	NS	ppm	ND	ND	ND	ND
1,4-Dichlorobenzene	1.8	24	ppm	ND	ND	ND	ND
2,2-Dichloropropane	NS	NS	ppm	ND	ND	ND	ND
2-Butanone	0.10	100	ppm	ND	ND	ND	ND
2-Chlorotoluene	NS	NS	ppm	ND	ND	ND	ND
2-Hexanone	NS	NS	ppm	ND	ND	ND	ND
4-Chlorotoluene	NS	NS	ppm	ND	ND	ND	ND

Table 4a. Volatile Organic Compounds in Soil
260 West 126th Street - New York, NY
BCP Site No. C231164

CLIENT SAMPLE ID	NY-UUSCO	NY-RESRR	Units	SB-5 (0-2)		SB-5 (12.5-14.5)		SB-5 (22-24)		SB-5 (22-24)_DUP	
SAMPLING DATE				1/5/2026		1/5/2026		1/5/2026		1/5/2026	
SAMPLE DEPTH (FT-BG)				0-2		12.5-14.5		22-24		22-24	
LAB SAMPLE ID				26A0061-01		26A0061-02		26A0061-03		26A0061-04	
					Qual		Qual		Qual		Qual
4-Methyl-2-pentanone	NS	NS	ppm	ND		ND		ND		ND	
Acetone	0.03	100	ppm	ND		ND		ND		ND	
Acrolein	NS	NS	ppm	ND		ND		ND		ND	
Acrylonitrile	NS	NS	ppm	ND		ND		ND		ND	
Benzene	0.06	3.7	ppm	ND		ND		ND		ND	
Bromobenzene	NS	NS	ppm	ND		ND		ND		ND	
Bromochloromethane	NS	NS	ppm	ND		ND		ND		ND	
Bromodichloromethane	NS	NS	ppm	ND		ND		ND		ND	
Bromoform	NS	NS	ppm	ND		ND		ND		ND	
Bromomethane	NS	NS	ppm	ND		ND		ND		ND	
Carbon disulfide	NS	NS	ppm	ND		ND		ND		ND	
Carbon tetrachloride	0.76	7.1	ppm	ND		ND		ND		ND	
Chlorobenzene	4.5	100	ppm	ND		ND		ND		ND	
Chloroethane	NS	NS	ppm	ND		ND		ND		ND	
Chloroform	0.37	24	ppm	ND		ND		ND		ND	
Chloromethane	NS	NS	ppm	ND		ND		ND		ND	
cis-1,2-Dichloroethylene	0.19	41	ppm	ND		ND		ND		ND	
cis-1,3-Dichloropropylene	NS	NS	ppm	ND		ND		ND		ND	
Cyclohexane	NS	NS	ppm	ND		ND		ND		ND	
Dibromochloromethane	NS	NS	ppm	ND		ND		ND		ND	
Dibromomethane	NS	NS	ppm	ND		ND		ND		ND	
Dichlorodifluoromethane	NS	NS	ppm	ND		ND		ND		ND	
Ethyl Benzene	1	76	ppm	ND		ND		ND		ND	
Hexachlorobutadiene	NS	NS	ppm	ND		ND		ND		ND	
Isopropylbenzene	NS	NS	ppm	ND		ND		ND		ND	
Methyl acetate	NS	NS	ppm	ND		ND		ND		ND	
Methyl tert-butyl ether (MTBE)	0.1	100	ppm	ND		ND		ND		ND	
Methylcyclohexane	NS	NS	ppm	ND		ND		ND		ND	
Methylene chloride	0.05	81	ppm	ND		ND		ND		ND	

Table 4a. Volatile Organic Compounds in Soil
260 West 126th Street - New York, NY
BCP Site No. C231164

CLIENT SAMPLE ID	NY-UUSCO	NY-RESRR	Units	SB-5 (0-2)	SB-5 (12.5-14.5)	SB-5 (22-24)	SB-5 (22-24)_DUP
SAMPLING DATE				1/5/2026	1/5/2026	1/5/2026	1/5/2026
SAMPLE DEPTH (FT-BG)				0-2	12.5-14.5	22-24	22-24
LAB SAMPLE ID				26A0061-01	26A0061-02	26A0061-03	26A0061-04
				Qual	Qual	Qual	Qual
n-Butylbenzene	18	100	ppm	ND	ND	ND	ND
n-Propylbenzene	5	100	ppm	ND	ND	ND	ND
o-Xylene	NS	NS	ppm	ND	ND	ND	ND
p- & m- Xylenes	NS	NS	ppm	ND	ND	ND	ND
p-Isopropyltoluene	NS	NS	ppm	ND	ND	ND	ND
sec-Butylbenzene	25	100	ppm	ND	ND	ND	ND
Styrene	NS	NS	ppm	ND	ND	ND	ND
tert-Butyl alcohol (TBA)	NS	NS	ppm	ND	ND	ND	ND
tert-Butylbenzene	11	100	ppm	ND	ND	ND	ND
Tetrachloroethylene	1.3	18	ppm	ND	ND	ND	ND
Toluene	0.7	100	ppm	ND	ND	ND	ND
trans-1,2-Dichloroethylene	0.19	100	ppm	ND	ND	ND	ND
trans-1,3-Dichloropropylene	NS	NS	ppm	ND	ND	ND	ND
Trichloroethylene	0.47	6.4	ppm	ND	ND	ND	ND
Trichlorofluoromethane	NS	NS	ppm	ND	ND	ND	ND
Vinyl acetate	NS	NS	ppm	ND	ND	ND	ND
Vinyl Chloride	0.03	0.48	ppm	ND	ND	ND	ND
Xylenes, Total	0.26	100	ppm	ND	ND	ND	ND

Notes:

Bold and shaded yellow value indicates concentration exceeds NY-UNRES SCOs

Bold and shaded orange value indicates concentration exceeds NY-UNRES and NY-RESRR SCOs

NY-UNRES = 6 NYCRR Part 375 Unrestricted Use Soil Cleanup Objectives

NY-RESRR = 6 NYCRR Part 375 Restricted-Residential Use Soil Cleanup Objectives

J = Estimated value

ND = Not detected

NS = No standard

ppm = parts per million

Table 4a. Volatile Organic Compounds in Soil
260 West 126th Street - New York, NY
BCP Site No. C231164

CLIENT SAMPLE ID	NY-UUSCO	NY-RESRR	Units	SB-3 (0-2)	SB-3 (8-10)	SB-3 (22-24)	SB-6 (0-2)
SAMPLING DATE				1/5/2026	1/5/2026	1/5/2026	1/5/2026
SAMPLE DEPTH (FT-BG)				0-2	8-10	22-24	0-2
LAB SAMPLE ID				26A0061-05	26A0061-06	26A0061-07	26A0061-08
				Qual	Qual	Qual	Qual
General Chemistry							
Solids, Total	NS	NS	%	96.5	96.1	97.1	90.6
Volatile Organic Compounds							
1,1,1,2-Tetrachloroethane	NS	NS	ppm	ND	ND	ND	ND
1,1,1-Trichloroethane	0.68	100	ppm	ND	ND	ND	ND
1,1,2,2-Tetrachloroethane	NS	NS	ppm	ND	ND	ND	ND
1,1,2-Trichloro-1,2,2-trifluoroethane (Freon 113)	NS	NS	ppm	ND	ND	ND	ND
1,1,2-Trichloroethane	NS	NS	ppm	ND	ND	ND	ND
1,1-Dichloroethane	0.27	47	ppm	ND	ND	ND	ND
1,1-Dichloroethylene	0.24	0.98	ppm	ND	ND	ND	ND
1,1-Dichloropropylene	NS	NS	ppm	ND	ND	ND	ND
1,2,3-Trichlorobenzene	NS	NS	ppm	ND	ND	ND	ND
1,2,3-Trichloropropane	NS	NS	ppm	ND	ND	ND	ND
1,2,4-Trichlorobenzene	NS	NS	ppm	ND	ND	ND	ND
1,2,4-Trimethylbenzene	5.9	100	ppm	ND	ND	ND	ND
1,2-Dibromo-3-chloropropane	NS	NS	ppm	ND	ND	ND	ND
1,2-Dibromoethane	NS	NS	ppm	ND	ND	ND	ND
1,2-Dichlorobenzene	1.1	100	ppm	ND	ND	ND	ND
1,2-Dichloroethane	0.02	5.8	ppm	ND	ND	ND	ND
1,2-Dichloropropane	NS	NS	ppm	ND	ND	ND	ND
1,3,5-Trimethylbenzene	3.1	100	ppm	ND	ND	ND	ND
1,3-Dichlorobenzene	2.6	38	ppm	ND	ND	ND	ND
1,3-Dichloropropane	NS	NS	ppm	ND	ND	ND	ND
1,4-Dichlorobenzene	1.8	24	ppm	ND	ND	ND	ND
2,2-Dichloropropane	NS	NS	ppm	ND	ND	ND	ND
2-Butanone	0.10	100	ppm	ND	ND	ND	ND
2-Chlorotoluene	NS	NS	ppm	ND	ND	ND	ND
2-Hexanone	NS	NS	ppm	ND	ND	ND	ND
4-Chlorotoluene	NS	NS	ppm	ND	ND	ND	ND

Table 4a. Volatile Organic Compounds in Soil
260 West 126th Street - New York, NY
BCP Site No. C231164

CLIENT SAMPLE ID	NY-UUSCO	NY-RESRR	Units	SB-3 (0-2)		SB-3 (8-10)		SB-3 (22-24)		SB-6 (0-2)	
SAMPLING DATE				1/5/2026		1/5/2026		1/5/2026		1/5/2026	
SAMPLE DEPTH (FT-BG)				0-2		8-10		22-24		0-2	
LAB SAMPLE ID				26A0061-05		26A0061-06		26A0061-07		26A0061-08	
					Qual		Qual		Qual		Qual
4-Methyl-2-pentanone	NS	NS	ppm	ND		ND		ND		ND	
Acetone	0.03	100	ppm	ND		ND		ND		ND	
Acrolein	NS	NS	ppm	ND		ND		ND		ND	
Acrylonitrile	NS	NS	ppm	ND		ND		ND		ND	
Benzene	0.06	3.7	ppm	ND		ND		ND		ND	
Bromobenzene	NS	NS	ppm	ND		ND		ND		ND	
Bromochloromethane	NS	NS	ppm	ND		ND		ND		ND	
Bromodichloromethane	NS	NS	ppm	ND		ND		ND		ND	
Bromoform	NS	NS	ppm	ND		ND		ND		ND	
Bromomethane	NS	NS	ppm	ND		ND		ND		ND	
Carbon disulfide	NS	NS	ppm	ND		ND		ND		ND	
Carbon tetrachloride	0.76	7.1	ppm	ND		ND		ND		ND	
Chlorobenzene	4.5	100	ppm	ND		ND		ND		ND	
Chloroethane	NS	NS	ppm	ND		ND		ND		ND	
Chloroform	0.37	24	ppm	ND		ND		ND		ND	
Chloromethane	NS	NS	ppm	ND		ND		ND		ND	
cis-1,2-Dichloroethylene	0.19	41	ppm	ND		ND		ND		ND	
cis-1,3-Dichloropropylene	NS	NS	ppm	ND		ND		ND		ND	
Cyclohexane	NS	NS	ppm	ND		ND		ND		ND	
Dibromochloromethane	NS	NS	ppm	ND		ND		ND		ND	
Dibromomethane	NS	NS	ppm	ND		ND		ND		ND	
Dichlorodifluoromethane	NS	NS	ppm	ND		ND		ND		ND	
Ethyl Benzene	1	76	ppm	ND		ND		ND		ND	
Hexachlorobutadiene	NS	NS	ppm	ND		ND		ND		ND	
Isopropylbenzene	NS	NS	ppm	ND		ND		ND		ND	
Methyl acetate	NS	NS	ppm	ND		ND		ND		ND	
Methyl tert-butyl ether (MTBE)	0.1	100	ppm	ND		ND		ND		ND	
Methylcyclohexane	NS	NS	ppm	ND		ND		ND		ND	
Methylene chloride	0.05	81	ppm	ND		ND		ND		ND	

Table 4a. Volatile Organic Compounds in Soil
260 West 126th Street - New York, NY
BCP Site No. C231164

CLIENT SAMPLE ID	NY-UUSCO	NY-RESRR	Units	SB-3 (0-2)		SB-3 (8-10)		SB-3 (22-24)		SB-6 (0-2)	
SAMPLING DATE				1/5/2026		1/5/2026		1/5/2026		1/5/2026	
SAMPLE DEPTH (FT-BG)				0-2		8-10		22-24		0-2	
LAB SAMPLE ID				26A0061-05		26A0061-06		26A0061-07		26A0061-08	
					Qual		Qual		Qual		Qual
n-Butylbenzene	18	100	ppm	ND		ND		ND		ND	
n-Propylbenzene	5	100	ppm	ND		ND		ND		ND	
o-Xylene	NS	NS	ppm	ND		ND		ND		ND	
p- & m- Xylenes	NS	NS	ppm	ND		ND		ND		ND	
p-Isopropyltoluene	NS	NS	ppm	ND		ND		ND		ND	
sec-Butylbenzene	25	100	ppm	ND		ND		ND		ND	
Styrene	NS	NS	ppm	ND		ND		ND		ND	
tert-Butyl alcohol (TBA)	NS	NS	ppm	ND		ND		ND		ND	
tert-Butylbenzene	11	100	ppm	ND		ND		ND		ND	
Tetrachloroethylene	1.3	18	ppm	ND		ND		ND		ND	
Toluene	0.7	100	ppm	ND		ND		ND		ND	
trans-1,2-Dichloroethylene	0.19	100	ppm	ND		ND		ND		ND	
trans-1,3-Dichloropropylene	NS	NS	ppm	ND		ND		ND		ND	
Trichloroethylene	0.47	6.4	ppm	ND		ND		ND		ND	
Trichlorofluoromethane	NS	NS	ppm	ND		ND		ND		ND	
Vinyl acetate	NS	NS	ppm	ND		ND		ND		ND	
Vinyl Chloride	0.03	0.48	ppm	ND		ND		ND		ND	
Xylenes, Total	0.26	100	ppm	ND		ND		ND		ND	

Notes:

Bold and shaded yellow value indicates concentration exceeds NY-UNRES SCOs

Bold and shaded orange value indicates concentration exceeds NY-UNRES and NY-RESRR SCOs

NY-UNRES = 6 NYCRR Part 375 Unrestricted Use Soil Cleanup Objectives

NY-RESRR = 6 NYCRR Part 375 Restricted-Residential Use Soil Cleanup Objectives

J = Estimated value

ND = Not detected

NS = No standard

ppm = parts per million

Table 4a. Volatile Organic Compounds in Soil
260 West 126th Street - New York, NY
BCP Site No. C231164

CLIENT SAMPLE ID	NY-UUSCO	NY-RESRR	Units	SB-6 (8-10)	SB-6 (22-24)	SB-8 (0-2)	SB-8 (8-10)
SAMPLING DATE				1/5/2026	1/5/2026	1/5/2026	1/6/2026
SAMPLE DEPTH (FT-BG)				8-10	22-24	0-2	8-10
LAB SAMPLE ID				26A0061-09	26A0061-10	26A0061-11	26A0111-02
				Qual	Qual	Qual	Qual
General Chemistry							
Solids, Total	NS	NS	%	97.9	95	82	95
Volatile Organic Compounds							
1,1,1,2-Tetrachloroethane	NS	NS	ppm	ND	ND	ND	ND
1,1,1-Trichloroethane	0.68	100	ppm	ND	ND	ND	ND
1,1,2,2-Tetrachloroethane	NS	NS	ppm	ND	ND	ND	ND
1,1,2-Trichloro-1,2,2-trifluoroethane (Freon 113)	NS	NS	ppm	ND	ND	ND	ND
1,1,2-Trichloroethane	NS	NS	ppm	ND	ND	ND	ND
1,1-Dichloroethane	0.27	47	ppm	ND	ND	ND	ND
1,1-Dichloroethylene	0.24	0.98	ppm	ND	ND	ND	ND
1,1-Dichloropropylene	NS	NS	ppm	ND	ND	ND	ND
1,2,3-Trichlorobenzene	NS	NS	ppm	ND	ND	ND	ND
1,2,3-Trichloropropane	NS	NS	ppm	ND	ND	ND	ND
1,2,4-Trichlorobenzene	NS	NS	ppm	ND	ND	ND	ND
1,2,4-Trimethylbenzene	5.9	100	ppm	ND	ND	ND	ND
1,2-Dibromo-3-chloropropane	NS	NS	ppm	ND	ND	ND	ND
1,2-Dibromoethane	NS	NS	ppm	ND	ND	ND	ND
1,2-Dichlorobenzene	1.1	100	ppm	ND	ND	ND	ND
1,2-Dichloroethane	0.02	5.8	ppm	ND	ND	ND	ND
1,2-Dichloropropane	NS	NS	ppm	ND	ND	ND	ND
1,3,5-Trimethylbenzene	3.1	100	ppm	ND	ND	ND	ND
1,3-Dichlorobenzene	2.6	38	ppm	ND	ND	ND	ND
1,3-Dichloropropane	NS	NS	ppm	ND	ND	ND	ND
1,4-Dichlorobenzene	1.8	24	ppm	ND	ND	ND	ND
2,2-Dichloropropane	NS	NS	ppm	ND	ND	ND	ND
2-Butanone	0.10	100	ppm	ND	ND	ND	ND
2-Chlorotoluene	NS	NS	ppm	ND	ND	ND	ND
2-Hexanone	NS	NS	ppm	ND	ND	ND	ND
4-Chlorotoluene	NS	NS	ppm	ND	ND	ND	ND

Table 4a. Volatile Organic Compounds in Soil
260 West 126th Street - New York, NY
BCP Site No. C231164

CLIENT SAMPLE ID	NY-UUSCO	NY-RESRR	Units	SB-6 (8-10)		SB-6 (22-24)		SB-8 (0-2)		SB-8 (8-10)	
SAMPLING DATE				1/5/2026		1/5/2026		1/5/2026		1/6/2026	
SAMPLE DEPTH (FT-BG)				8-10		22-24		0-2		8-10	
LAB SAMPLE ID				26A0061-09		26A0061-10		26A0061-11		26A0111-02	
					Qual		Qual		Qual		Qual
4-Methyl-2-pentanone	NS	NS	ppm	ND		ND		ND		ND	
Acetone	0.03	100	ppm	ND		ND		ND		0.011	
Acrolein	NS	NS	ppm	ND		ND		ND		ND	
Acrylonitrile	NS	NS	ppm	ND		ND		ND		ND	
Benzene	0.06	3.7	ppm	ND		ND		ND		ND	
Bromobenzene	NS	NS	ppm	ND		ND		ND		ND	
Bromochloromethane	NS	NS	ppm	ND		ND		ND		ND	
Bromodichloromethane	NS	NS	ppm	ND		ND		ND		ND	
Bromoform	NS	NS	ppm	ND		ND		ND		ND	
Bromomethane	NS	NS	ppm	ND		ND		ND		ND	
Carbon disulfide	NS	NS	ppm	ND		ND		ND		ND	
Carbon tetrachloride	0.76	7.1	ppm	ND		ND		ND		ND	
Chlorobenzene	4.5	100	ppm	ND		ND		ND		ND	
Chloroethane	NS	NS	ppm	ND		ND		ND		ND	
Chloroform	0.37	24	ppm	ND		ND		ND		ND	
Chloromethane	NS	NS	ppm	ND		ND		ND		ND	
cis-1,2-Dichloroethylene	0.19	41	ppm	ND		ND		ND		ND	
cis-1,3-Dichloropropylene	NS	NS	ppm	ND		ND		ND		ND	
Cyclohexane	NS	NS	ppm	ND		ND		ND		ND	
Dibromochloromethane	NS	NS	ppm	ND		ND		ND		ND	
Dibromomethane	NS	NS	ppm	ND		ND		ND		ND	
Dichlorodifluoromethane	NS	NS	ppm	ND		ND		ND		ND	
Ethyl Benzene	1	76	ppm	ND		ND		ND		ND	
Hexachlorobutadiene	NS	NS	ppm	ND		ND		ND		ND	
Isopropylbenzene	NS	NS	ppm	ND		ND		ND		ND	
Methyl acetate	NS	NS	ppm	ND		ND		ND		ND	
Methyl tert-butyl ether (MTBE)	0.1	100	ppm	ND		ND		ND		ND	
Methylcyclohexane	NS	NS	ppm	ND		ND		ND		ND	
Methylene chloride	0.05	81	ppm	ND		ND		ND		0.012	

Table 4a. Volatile Organic Compounds in Soil
260 West 126th Street - New York, NY
BCP Site No. C231164

CLIENT SAMPLE ID	NY-UUSCO	NY-RESRR	Units	SB-6 (8-10)		SB-6 (22-24)		SB-8 (0-2)		SB-8 (8-10)	
SAMPLING DATE				1/5/2026		1/5/2026		1/5/2026		1/6/2026	
SAMPLE DEPTH (FT-BG)				8-10		22-24		0-2		8-10	
LAB SAMPLE ID				26A0061-09		26A0061-10		26A0061-11		26A0111-02	
					Qual		Qual		Qual		Qual
n-Butylbenzene	18	100	ppm	ND		ND		ND		ND	
n-Propylbenzene	5	100	ppm	ND		ND		ND		ND	
o-Xylene	NS	NS	ppm	ND		ND		ND		ND	
p- & m- Xylenes	NS	NS	ppm	ND		ND		ND		ND	
p-Isopropyltoluene	NS	NS	ppm	ND		ND		ND		ND	
sec-Butylbenzene	25	100	ppm	ND		ND		ND		ND	
Styrene	NS	NS	ppm	ND		ND		ND		ND	
tert-Butyl alcohol (TBA)	NS	NS	ppm	ND		ND		ND		ND	
tert-Butylbenzene	11	100	ppm	ND		ND		ND		ND	
Tetrachloroethylene	1.3	18	ppm	ND		ND		ND		ND	
Toluene	0.7	100	ppm	ND		ND		ND		ND	
trans-1,2-Dichloroethylene	0.19	100	ppm	ND		ND		ND		ND	
trans-1,3-Dichloropropylene	NS	NS	ppm	ND		ND		ND		ND	
Trichloroethylene	0.47	6.4	ppm	ND		ND		ND		ND	
Trichlorofluoromethane	NS	NS	ppm	ND		ND		ND		ND	
Vinyl acetate	NS	NS	ppm	ND		ND		ND		ND	
Vinyl Chloride	0.03	0.48	ppm	ND		ND		ND		ND	
Xylenes, Total	0.26	100	ppm	ND		ND		ND		ND	

Notes:

Bold and shaded yellow value indicates concentration exceeds NY-UNRES SCOs

Bold and shaded orange value indicates concentration exceeds NY-UNRES and NY-RESRR SCOs

NY-UNRES = 6 NYCRR Part 375 Unrestricted Use Soil Cleanup Objectives

NY-RESRR = 6 NYCRR Part 375 Restricted-Residential Use Soil Cleanup Objectives

J = Estimated value

ND = Not detected

NS = No standard

ppm = parts per million

Table 4a. Volatile Organic Compounds in Soil
260 West 126th Street - New York, NY
BCP Site No. C231164

CLIENT SAMPLE ID	NY-UUSCO	NY-RESRR	Units	SB-8 (22-24)	SB-2 (0-2)	SB-2 (0-2)_DUP	SB-2 (6-8)
SAMPLING DATE				1/6/2026	1/6/2026	1/6/2026	1/6/2026
SAMPLE DEPTH (FT-BG)				22-24	0-2	21-23	6-8
LAB SAMPLE ID				26A0111-03	26A0111-04	26A0111-13	26A0111-05
				Qual	Qual	Qual	Qual
General Chemistry							
Solids, Total	NS	NS	%	96.2	83.7	87.9	96.1
Volatile Organic Compounds							
1,1,1,2-Tetrachloroethane	NS	NS	ppm	ND	ND	ND	ND
1,1,1-Trichloroethane	0.68	100	ppm	ND	ND	ND	ND
1,1,2,2-Tetrachloroethane	NS	NS	ppm	ND	ND	ND	ND
1,1,2-Trichloro-1,2,2-trifluoroethane (Freon 113)	NS	NS	ppm	ND	ND	ND	ND
1,1,2-Trichloroethane	NS	NS	ppm	ND	ND	ND	ND
1,1-Dichloroethane	0.27	47	ppm	ND	ND	ND	ND
1,1-Dichloroethylene	0.24	0.98	ppm	ND	ND	ND	ND
1,1-Dichloropropylene	NS	NS	ppm	ND	ND	ND	ND
1,2,3-Trichlorobenzene	NS	NS	ppm	ND	ND	ND	ND
1,2,3-Trichloropropane	NS	NS	ppm	ND	ND	ND	ND
1,2,4-Trichlorobenzene	NS	NS	ppm	ND	ND	ND	ND
1,2,4-Trimethylbenzene	5.9	100	ppm	ND	ND	ND	ND
1,2-Dibromo-3-chloropropane	NS	NS	ppm	ND	ND	ND	ND
1,2-Dibromoethane	NS	NS	ppm	ND	ND	ND	ND
1,2-Dichlorobenzene	1.1	100	ppm	ND	ND	ND	ND
1,2-Dichloroethane	0.02	5.8	ppm	ND	ND	ND	ND
1,2-Dichloropropane	NS	NS	ppm	ND	ND	ND	ND
1,3,5-Trimethylbenzene	3.1	100	ppm	ND	ND	ND	ND
1,3-Dichlorobenzene	2.6	38	ppm	ND	ND	ND	ND
1,3-Dichloropropane	NS	NS	ppm	ND	ND	ND	ND
1,4-Dichlorobenzene	1.8	24	ppm	ND	ND	ND	ND
2,2-Dichloropropane	NS	NS	ppm	ND	ND	ND	ND
2-Butanone	0.10	100	ppm	ND	ND	ND	ND
2-Chlorotoluene	NS	NS	ppm	ND	ND	ND	ND
2-Hexanone	NS	NS	ppm	ND	ND	ND	ND
4-Chlorotoluene	NS	NS	ppm	ND	ND	ND	ND

Table 4a. Volatile Organic Compounds in Soil
260 West 126th Street - New York, NY
BCP Site No. C231164

CLIENT SAMPLE ID	NY-UUSCO	NY-RESRR	Units	SB-8 (22-24)		SB-2 (0-2)		SB-2 (0-2)_DUP		SB-2 (6-8)	
SAMPLING DATE				1/6/2026		1/6/2026		1/6/2026		1/6/2026	
SAMPLE DEPTH (FT-BG)				22-24		0-2		21-23		6-8	
LAB SAMPLE ID				26A0111-03		26A0111-04		26A0111-13		26A0111-05	
					Qual		Qual		Qual		Qual
4-Methyl-2-pentanone	NS	NS	ppm	ND		ND		ND		ND	
Acetone	0.03	100	ppm	ND		ND		0.0095	J	ND	
Acrolein	NS	NS	ppm	ND		ND		ND		ND	
Acrylonitrile	NS	NS	ppm	ND		ND		ND		ND	
Benzene	0.06	3.7	ppm	ND		ND		ND		ND	
Bromobenzene	NS	NS	ppm	ND		ND		ND		ND	
Bromochloromethane	NS	NS	ppm	ND		ND		ND		ND	
Bromodichloromethane	NS	NS	ppm	ND		ND		ND		ND	
Bromoform	NS	NS	ppm	ND		ND		ND		ND	
Bromomethane	NS	NS	ppm	ND		ND		ND		ND	
Carbon disulfide	NS	NS	ppm	ND		ND		ND		ND	
Carbon tetrachloride	0.76	7.1	ppm	ND		ND		ND		ND	
Chlorobenzene	4.5	100	ppm	ND		ND		ND		ND	
Chloroethane	NS	NS	ppm	ND		ND		ND		ND	
Chloroform	0.37	24	ppm	ND		ND		ND		ND	
Chloromethane	NS	NS	ppm	ND		ND		ND		ND	
cis-1,2-Dichloroethylene	0.19	41	ppm	ND		ND		ND		ND	
cis-1,3-Dichloropropylene	NS	NS	ppm	ND		ND		ND		ND	
Cyclohexane	NS	NS	ppm	ND		ND		ND		ND	
Dibromochloromethane	NS	NS	ppm	ND		ND		ND		ND	
Dibromomethane	NS	NS	ppm	ND		ND		ND		ND	
Dichlorodifluoromethane	NS	NS	ppm	ND		ND		ND		ND	
Ethyl Benzene	1	76	ppm	ND		ND		ND		ND	
Hexachlorobutadiene	NS	NS	ppm	ND		ND		ND		ND	
Isopropylbenzene	NS	NS	ppm	ND		ND		ND		ND	
Methyl acetate	NS	NS	ppm	ND		ND		ND		ND	
Methyl tert-butyl ether (MTBE)	0.1	100	ppm	ND		ND		ND		ND	
Methylcyclohexane	NS	NS	ppm	ND		ND		ND		ND	
Methylene chloride	0.05	81	ppm	0.012		ND		ND		0.01	J

Table 4a. Volatile Organic Compounds in Soil
260 West 126th Street - New York, NY
BCP Site No. C231164

CLIENT SAMPLE ID	NY-UUSCO	NY-RESRR	Units	SB-8 (22-24)	SB-2 (0-2)	SB-2 (0-2)_DUP	SB-2 (6-8)
SAMPLING DATE				1/6/2026	1/6/2026	1/6/2026	1/6/2026
SAMPLE DEPTH (FT-BG)				22-24	0-2	21-23	6-8
LAB SAMPLE ID				26A0111-03	26A0111-04	26A0111-13	26A0111-05
				Qual	Qual	Qual	Qual
n-Butylbenzene	18	100	ppm	ND	ND	ND	ND
n-Propylbenzene	5	100	ppm	ND	ND	ND	ND
o-Xylene	NS	NS	ppm	ND	ND	ND	ND
p- & m- Xylenes	NS	NS	ppm	ND	ND	ND	ND
p-Isopropyltoluene	NS	NS	ppm	ND	ND	ND	ND
sec-Butylbenzene	25	100	ppm	ND	ND	ND	ND
Styrene	NS	NS	ppm	ND	ND	ND	ND
tert-Butyl alcohol (TBA)	NS	NS	ppm	ND	ND	ND	ND
tert-Butylbenzene	11	100	ppm	ND	ND	ND	ND
Tetrachloroethylene	1.3	18	ppm	ND	ND	ND	ND
Toluene	0.7	100	ppm	ND	ND	ND	ND
trans-1,2-Dichloroethylene	0.19	100	ppm	ND	ND	ND	ND
trans-1,3-Dichloropropylene	NS	NS	ppm	ND	ND	ND	ND
Trichloroethylene	0.47	6.4	ppm	ND	ND	ND	ND
Trichlorofluoromethane	NS	NS	ppm	ND	ND	ND	ND
Vinyl acetate	NS	NS	ppm	ND	ND	ND	ND
Vinyl Chloride	0.03	0.48	ppm	ND	ND	ND	ND
Xylenes, Total	0.26	100	ppm	ND	ND	ND	ND

Notes:

Bold and shaded yellow value indicates concentration exceeds NY-UNRES SCOs

Bold and shaded orange value indicates concentration exceeds NY-UNRES and NY-RESRR SCOs

NY-UNRES = 6 NYCRR Part 375 Unrestricted Use Soil Cleanup Objectives

NY-RESRR = 6 NYCRR Part 375 Restricted-Residential Use Soil Cleanup Objectives

J = Estimated value

ND = Not detected

NS = No standard

ppm = parts per million

Table 4a. Volatile Organic Compounds in Soil
260 West 126th Street - New York, NY
BCP Site No. C231164

CLIENT SAMPLE ID	NY-UUSCO	NY-RESRR	Units	SB-2 (22-24)	SB-9 (0-2)	SB-9 (6-8)	SB-9 (22-24)
SAMPLING DATE				1/6/2026	1/6/2026	1/6/2026	1/6/2026
SAMPLE DEPTH (FT-BG)				22-24	0-2	6-8	22-24
LAB SAMPLE ID				26A0111-06	26A0111-07	26A0111-08	26A0111-09
				Qual	Qual	Qual	Qual
General Chemistry							
Solids, Total	NS	NS	%	96.5	85.8	96.1	93.6
Volatile Organic Compounds							
1,1,1,2-Tetrachloroethane	NS	NS	ppm	ND	ND	ND	ND
1,1,1-Trichloroethane	0.68	100	ppm	ND	ND	ND	ND
1,1,2,2-Tetrachloroethane	NS	NS	ppm	ND	ND	ND	ND
1,1,2-Trichloro-1,2,2-trifluoroethane (Freon 113)	NS	NS	ppm	ND	ND	ND	ND
1,1,2-Trichloroethane	NS	NS	ppm	ND	ND	ND	ND
1,1-Dichloroethane	0.27	47	ppm	ND	ND	ND	ND
1,1-Dichloroethylene	0.24	0.98	ppm	ND	ND	ND	ND
1,1-Dichloropropylene	NS	NS	ppm	ND	ND	ND	ND
1,2,3-Trichlorobenzene	NS	NS	ppm	ND	ND	ND	ND
1,2,3-Trichloropropane	NS	NS	ppm	ND	ND	ND	ND
1,2,4-Trichlorobenzene	NS	NS	ppm	ND	ND	ND	ND
1,2,4-Trimethylbenzene	5.9	100	ppm	ND	ND	ND	ND
1,2-Dibromo-3-chloropropane	NS	NS	ppm	ND	ND	ND	ND
1,2-Dibromoethane	NS	NS	ppm	ND	ND	ND	ND
1,2-Dichlorobenzene	1.1	100	ppm	ND	ND	ND	ND
1,2-Dichloroethane	0.02	5.8	ppm	ND	ND	ND	ND
1,2-Dichloropropane	NS	NS	ppm	ND	ND	ND	ND
1,3,5-Trimethylbenzene	3.1	100	ppm	ND	ND	ND	ND
1,3-Dichlorobenzene	2.6	38	ppm	ND	ND	ND	ND
1,3-Dichloropropane	NS	NS	ppm	ND	ND	ND	ND
1,4-Dichlorobenzene	1.8	24	ppm	ND	ND	ND	ND
2,2-Dichloropropane	NS	NS	ppm	ND	ND	ND	ND
2-Butanone	0.10	100	ppm	ND	ND	ND	ND
2-Chlorotoluene	NS	NS	ppm	ND	ND	ND	ND
2-Hexanone	NS	NS	ppm	ND	ND	ND	ND
4-Chlorotoluene	NS	NS	ppm	ND	ND	ND	ND

Table 4a. Volatile Organic Compounds in Soil
260 West 126th Street - New York, NY
BCP Site No. C231164

CLIENT SAMPLE ID	NY-UUSCO	NY-RESRR	Units	SB-2 (22-24)		SB-9 (0-2)		SB-9 (6-8)		SB-9 (22-24)	
SAMPLING DATE				1/6/2026		1/6/2026		1/6/2026		1/6/2026	
SAMPLE DEPTH (FT-BG)				22-24		0-2		6-8		22-24	
LAB SAMPLE ID				26A0111-06		26A0111-07		26A0111-08		26A0111-09	
					Qual		Qual		Qual		Qual
4-Methyl-2-pentanone	NS	NS	ppm	ND		ND		ND		ND	
Acetone	0.03	100	ppm	0.0068	J	ND		ND		0.0094	J
Acrolein	NS	NS	ppm	ND		ND		ND		ND	
Acrylonitrile	NS	NS	ppm	ND		ND		ND		ND	
Benzene	0.06	3.7	ppm	ND		ND		ND		ND	
Bromobenzene	NS	NS	ppm	ND		ND		ND		ND	
Bromochloromethane	NS	NS	ppm	ND		ND		ND		ND	
Bromodichloromethane	NS	NS	ppm	ND		ND		ND		ND	
Bromoform	NS	NS	ppm	ND		ND		ND		ND	
Bromomethane	NS	NS	ppm	ND		ND		ND		ND	
Carbon disulfide	NS	NS	ppm	ND		ND		ND		ND	
Carbon tetrachloride	0.76	7.1	ppm	ND		ND		ND		ND	
Chlorobenzene	4.5	100	ppm	ND		ND		ND		ND	
Chloroethane	NS	NS	ppm	ND		ND		ND		ND	
Chloroform	0.37	24	ppm	ND		ND		ND		ND	
Chloromethane	NS	NS	ppm	ND		ND		ND		ND	
cis-1,2-Dichloroethylene	0.19	41	ppm	ND		ND		ND		ND	
cis-1,3-Dichloropropylene	NS	NS	ppm	ND		ND		ND		ND	
Cyclohexane	NS	NS	ppm	ND		ND		ND		ND	
Dibromochloromethane	NS	NS	ppm	ND		ND		ND		ND	
Dibromomethane	NS	NS	ppm	ND		ND		ND		ND	
Dichlorodifluoromethane	NS	NS	ppm	ND		ND		ND		ND	
Ethyl Benzene	1	76	ppm	ND		ND		ND		ND	
Hexachlorobutadiene	NS	NS	ppm	ND		ND		ND		ND	
Isopropylbenzene	NS	NS	ppm	ND		ND		ND		ND	
Methyl acetate	NS	NS	ppm	ND		ND		ND		ND	
Methyl tert-butyl ether (MTBE)	0.1	100	ppm	ND		ND		ND		ND	
Methylcyclohexane	NS	NS	ppm	ND		ND		ND		ND	
Methylene chloride	0.05	81	ppm	0.01	J	ND		0.011		0.011	

Table 4a. Volatile Organic Compounds in Soil
260 West 126th Street - New York, NY
BCP Site No. C231164

CLIENT SAMPLE ID	NY-UUSCO	NY-RESRR	Units	SB-2 (22-24)	SB-9 (0-2)	SB-9 (6-8)	SB-9 (22-24)
SAMPLING DATE				1/6/2026	1/6/2026	1/6/2026	1/6/2026
SAMPLE DEPTH (FT-BG)				22-24	0-2	6-8	22-24
LAB SAMPLE ID				26A0111-06	26A0111-07	26A0111-08	26A0111-09
				Qual	Qual	Qual	Qual
n-Butylbenzene	18	100	ppm	ND	ND	ND	ND
n-Propylbenzene	5	100	ppm	ND	ND	ND	ND
o-Xylene	NS	NS	ppm	ND	ND	ND	ND
p- & m- Xylenes	NS	NS	ppm	ND	ND	ND	ND
p-Isopropyltoluene	NS	NS	ppm	ND	ND	ND	ND
sec-Butylbenzene	25	100	ppm	ND	ND	ND	ND
Styrene	NS	NS	ppm	ND	ND	ND	ND
tert-Butyl alcohol (TBA)	NS	NS	ppm	ND	ND	ND	ND
tert-Butylbenzene	11	100	ppm	ND	ND	ND	ND
Tetrachloroethylene	1.3	18	ppm	ND	ND	ND	ND
Toluene	0.7	100	ppm	ND	ND	ND	ND
trans-1,2-Dichloroethylene	0.19	100	ppm	ND	ND	ND	ND
trans-1,3-Dichloropropylene	NS	NS	ppm	ND	ND	ND	ND
Trichloroethylene	0.47	6.4	ppm	ND	ND	ND	ND
Trichlorofluoromethane	NS	NS	ppm	ND	ND	ND	ND
Vinyl acetate	NS	NS	ppm	ND	ND	ND	ND
Vinyl Chloride	0.03	0.48	ppm	ND	ND	ND	ND
Xylenes, Total	0.26	100	ppm	ND	ND	ND	ND

Notes:

Bold and shaded yellow value indicates concentration exceeds NY-UNRES SCOs

Bold and shaded orange value indicates concentration exceeds NY-UNRES and NY-RESRR SCOs

NY-UNRES = 6 NYCRR Part 375 Unrestricted Use Soil Cleanup Objectives

NY-RESRR = 6 NYCRR Part 375 Restricted-Residential Use Soil Cleanup Objectives

J = Estimated value

ND = Not detected

NS = No standard

ppm = parts per million

Table 4a. Volatile Organic Compounds in Soil
260 West 126th Street - New York, NY
BCP Site No. C231164

CLIENT SAMPLE ID	NY-UUSCO	NY-RESRR	Units	SB-1 (0-2)	SB-1 (6-8)	SB-1 (21-23)	SB-7 (0-2)
SAMPLING DATE				1/6/2026	1/6/2026	1/6/2026	6/26/2026
SAMPLE DEPTH (FT-BG)				0-2	6-8	21-23	0-2
LAB SAMPLE ID				26A0111-10	26A0111-11	26A0111-12	26F1687-01
				Qual	Qual	Qual	Qual
General Chemistry							
Solids, Total	NS	NS	%	93.6	96	96.1	96.4
Volatile Organic Compounds							
1,1,1,2-Tetrachloroethane	NS	NS	ppm	ND	ND	ND	ND
1,1,1-Trichloroethane	0.68	100	ppm	ND	ND	ND	ND
1,1,2,2-Tetrachloroethane	NS	NS	ppm	ND	ND	ND	ND
1,1,2-Trichloro-1,2,2-trifluoroethane (Freon 113)	NS	NS	ppm	ND	ND	ND	ND
1,1,2-Trichloroethane	NS	NS	ppm	ND	ND	ND	ND
1,1-Dichloroethane	0.27	47	ppm	ND	ND	ND	ND
1,1-Dichloroethylene	0.24	0.98	ppm	ND	ND	ND	ND
1,1-Dichloropropylene	NS	NS	ppm	ND	ND	ND	ND
1,2,3-Trichlorobenzene	NS	NS	ppm	ND	ND	ND	ND
1,2,3-Trichloropropane	NS	NS	ppm	ND	ND	ND	ND
1,2,4-Trichlorobenzene	NS	NS	ppm	ND	ND	ND	ND
1,2,4-Trimethylbenzene	5.9	100	ppm	ND	ND	ND	ND
1,2-Dibromo-3-chloropropane	NS	NS	ppm	ND	ND	ND	ND
1,2-Dibromoethane	NS	NS	ppm	ND	ND	ND	ND
1,2-Dichlorobenzene	1.1	100	ppm	ND	ND	ND	ND
1,2-Dichloroethane	0.02	5.8	ppm	ND	ND	ND	ND
1,2-Dichloropropane	NS	NS	ppm	ND	ND	ND	ND
1,3,5-Trimethylbenzene	3.1	100	ppm	ND	ND	ND	ND
1,3-Dichlorobenzene	2.6	38	ppm	ND	ND	ND	ND
1,3-Dichloropropane	NS	NS	ppm	ND	ND	ND	ND
1,4-Dichlorobenzene	1.8	24	ppm	ND	ND	ND	ND
2,2-Dichloropropane	NS	NS	ppm	ND	ND	ND	ND
2-Butanone	0.10	100	ppm	ND	ND	ND	ND
2-Chlorotoluene	NS	NS	ppm	ND	ND	ND	ND
2-Hexanone	NS	NS	ppm	ND	ND	ND	ND
4-Chlorotoluene	NS	NS	ppm	ND	ND	ND	ND

Table 4a. Volatile Organic Compounds in Soil
260 West 126th Street - New York, NY
BCP Site No. C231164

CLIENT SAMPLE ID	NY-UUSCO	NY-RESRR	Units	SB-1 (0-2)		SB-1 (6-8)		SB-1 (21-23)		SB-7 (0-2)	
SAMPLING DATE				1/6/2026		1/6/2026		1/6/2026		6/26/2026	
SAMPLE DEPTH (FT-BG)				0-2		6-8		21-23		0-2	
LAB SAMPLE ID				26A0111-10		26A0111-11		26A0111-12		26F1687-01	
					Qual		Qual		Qual		Qual
4-Methyl-2-pentanone	NS	NS	ppm	ND		ND		ND		ND	
Acetone	0.03	100	ppm	ND		0.0085	J	0.0062	J	**0.049**	
Acrolein	NS	NS	ppm	ND		ND		ND		ND	
Acrylonitrile	NS	NS	ppm	ND		ND		ND		ND	
Benzene	0.06	3.7	ppm	ND		ND		ND		ND	
Bromobenzene	NS	NS	ppm	ND		ND		ND		ND	
Bromochloromethane	NS	NS	ppm	ND		ND		ND		ND	
Bromodichloromethane	NS	NS	ppm	ND		ND		ND		ND	
Bromoform	NS	NS	ppm	ND		ND		ND		ND	
Bromomethane	NS	NS	ppm	ND		ND		ND		ND	
Carbon disulfide	NS	NS	ppm	ND		ND		ND		ND	
Carbon tetrachloride	0.76	7.1	ppm	ND		ND		ND		ND	
Chlorobenzene	4.5	100	ppm	ND		ND		ND		ND	
Chloroethane	NS	NS	ppm	ND		ND		ND		ND	
Chloroform	0.37	24	ppm	ND		ND		ND		ND	
Chloromethane	NS	NS	ppm	ND		ND		ND		ND	
cis-1,2-Dichloroethylene	0.19	41	ppm	ND		ND		ND		ND	
cis-1,3-Dichloropropylene	NS	NS	ppm	ND		ND		ND		ND	
Cyclohexane	NS	NS	ppm	ND		ND		ND		ND	
Dibromochloromethane	NS	NS	ppm	ND		ND		ND		ND	
Dibromomethane	NS	NS	ppm	ND		ND		ND		ND	
Dichlorodifluoromethane	NS	NS	ppm	ND		ND		ND		ND	
Ethyl Benzene	1	76	ppm	ND		ND		ND		ND	
Hexachlorobutadiene	NS	NS	ppm	ND		ND		ND		ND	
Isopropylbenzene	NS	NS	ppm	ND		ND		ND		ND	
Methyl acetate	NS	NS	ppm	ND		ND		ND		ND	
Methyl tert-butyl ether (MTBE)	0.1	100	ppm	ND		ND		ND		ND	
Methylcyclohexane	NS	NS	ppm	ND		ND		ND		ND	
Methylene chloride	0.05	81	ppm	ND		ND		0.008	J	ND	

Table 4a. Volatile Organic Compounds in Soil
260 West 126th Street - New York, NY
BCP Site No. C231164

CLIENT SAMPLE ID	NY-UUSCO	NY-RESRR	Units	SB-1 (0-2)		SB-1 (6-8)		SB-1 (21-23)		SB-7 (0-2)	
SAMPLING DATE				1/6/2026		1/6/2026		1/6/2026		6/26/2026	
SAMPLE DEPTH (FT-BG)				0-2		6-8		21-23		0-2	
LAB SAMPLE ID				26A0111-10		26A0111-11		26A0111-12		26F1687-01	
					Qual		Qual		Qual		Qual
n-Butylbenzene	18	100	ppm	ND		ND		ND		ND	
n-Propylbenzene	5	100	ppm	ND		ND		ND		ND	
o-Xylene	NS	NS	ppm	ND		ND		ND		ND	
p- & m- Xylenes	NS	NS	ppm	ND		ND		ND		ND	
p-Isopropyltoluene	NS	NS	ppm	ND		ND		ND		ND	
sec-Butylbenzene	25	100	ppm	ND		ND		ND		ND	
Styrene	NS	NS	ppm	ND		ND		ND		ND	
tert-Butyl alcohol (TBA)	NS	NS	ppm	ND		ND		ND		ND	
tert-Butylbenzene	11	100	ppm	ND		ND		ND		ND	
Tetrachloroethylene	1.3	18	ppm	ND		ND		ND		ND	
Toluene	0.7	100	ppm	ND		ND		ND		ND	
trans-1,2-Dichloroethylene	0.19	100	ppm	ND		ND		ND		ND	
trans-1,3-Dichloropropylene	NS	NS	ppm	ND		ND		ND		ND	
Trichloroethylene	0.47	6.4	ppm	ND		ND		ND		ND	
Trichlorofluoromethane	NS	NS	ppm	ND		ND		ND		ND	
Vinyl acetate	NS	NS	ppm	ND		ND		ND		ND	
Vinyl Chloride	0.03	0.48	ppm	ND		ND		ND		ND	
Xylenes, Total	0.26	100	ppm	ND		ND		ND		ND	

Notes:

Bold and shaded yellow value indicates concentration exceeds NY-UNRES SCOs

Bold and shaded orange value indicates concentration exceeds NY-UNRES and NY-RESRR SCOs

NY-UNRES = 6 NYCRR Part 375 Unrestricted Use Soil Cleanup Objectives

NY-RESRR = 6 NYCRR Part 375 Restricted-Residential Use Soil Cleanup Objectives

J = Estimated value

ND = Not detected

NS = No standard

ppm = parts per million

Table 4a. Volatile Organic Compounds in Soil
260 West 126th Street - New York, NY
BCP Site No. C231164

CLIENT SAMPLE ID	NY-UUSCO	NY-RESRR	Units	SB-7 (10-12)	SB-7 (12-14)	SB-4 (0-2)	SB-4 (12-14)
SAMPLING DATE				6/26/2026	6/26/2026	6/26/2026	6/26/2026
SAMPLE DEPTH (FT-BG)				10-12	12-14	0-2	12-14
LAB SAMPLE ID				26F1687-02	26F1687-03	26F1687-04	26F1687-05
				Qual	Qual	Qual	Qual
General Chemistry							
Solids, Total	NS	NS	%	98.3	98.7	97.4	98.5
Volatile Organic Compounds							
1,1,1,2-Tetrachloroethane	NS	NS	ppm	ND	ND	ND	ND
1,1,1-Trichloroethane	0.68	100	ppm	ND	ND	ND	ND
1,1,2,2-Tetrachloroethane	NS	NS	ppm	ND	ND	ND	ND
1,1,2-Trichloro-1,2,2-trifluoroethane (Freon 113)	NS	NS	ppm	ND	ND	ND	ND
1,1,2-Trichloroethane	NS	NS	ppm	ND	ND	ND	ND
1,1-Dichloroethane	0.27	47	ppm	ND	ND	ND	ND
1,1-Dichloroethylene	0.24	0.98	ppm	ND	ND	ND	ND
1,1-Dichloropropylene	NS	NS	ppm	ND	ND	ND	ND
1,2,3-Trichlorobenzene	NS	NS	ppm	ND	ND	ND	ND
1,2,3-Trichloropropane	NS	NS	ppm	ND	ND	ND	ND
1,2,4-Trichlorobenzene	NS	NS	ppm	ND	ND	ND	ND
1,2,4-Trimethylbenzene	5.9	100	ppm	ND	ND	ND	ND
1,2-Dibromo-3-chloropropane	NS	NS	ppm	ND	ND	ND	ND
1,2-Dibromoethane	NS	NS	ppm	ND	ND	ND	ND
1,2-Dichlorobenzene	1.1	100	ppm	ND	ND	ND	ND
1,2-Dichloroethane	0.02	5.8	ppm	ND	ND	ND	ND
1,2-Dichloropropane	NS	NS	ppm	ND	ND	ND	ND
1,3,5-Trimethylbenzene	3.1	100	ppm	ND	ND	ND	ND
1,3-Dichlorobenzene	2.6	38	ppm	ND	ND	ND	ND
1,3-Dichloropropane	NS	NS	ppm	ND	ND	ND	ND
1,4-Dichlorobenzene	1.8	24	ppm	ND	ND	ND	ND
2,2-Dichloropropane	NS	NS	ppm	ND	ND	ND	ND
2-Butanone	0.10	100	ppm	ND	ND	ND	ND
2-Chlorotoluene	NS	NS	ppm	ND	ND	ND	ND
2-Hexanone	NS	NS	ppm	ND	ND	ND	ND
4-Chlorotoluene	NS	NS	ppm	ND	ND	ND	ND

Table 4a. Volatile Organic Compounds in Soil
260 West 126th Street - New York, NY
BCP Site No. C231164

CLIENT SAMPLE ID	NY-UUSCO	NY-RESRR	Units	SB-7 (10-12)		SB-7 (12-14)		SB-4 (0-2)		SB-4 (12-14)	
SAMPLING DATE				6/26/2026		6/26/2026		6/26/2026		6/26/2026	
SAMPLE DEPTH (FT-BG)				10-12		12-14		0-2		12-14	
LAB SAMPLE ID				26F1687-02		26F1687-03		26F1687-04		26F1687-05	
					Qual		Qual		Qual		Qual
4-Methyl-2-pentanone	NS	NS	ppm	ND		ND		ND		ND	
Acetone	0.03	100	ppm	0.0068	J	0.0056	J	0.0057	J	0.025	
Acrolein	NS	NS	ppm	ND		ND		ND		ND	
Acrylonitrile	NS	NS	ppm	ND		ND		ND		ND	
Benzene	0.06	3.7	ppm	ND		ND		ND		ND	
Bromobenzene	NS	NS	ppm	ND		ND		ND		ND	
Bromochloromethane	NS	NS	ppm	ND		ND		ND		ND	
Bromodichloromethane	NS	NS	ppm	ND		ND		ND		ND	
Bromoform	NS	NS	ppm	ND		ND		ND		ND	
Bromomethane	NS	NS	ppm	ND		ND		ND		ND	
Carbon disulfide	NS	NS	ppm	ND		ND		ND		ND	
Carbon tetrachloride	0.76	7.1	ppm	ND		ND		ND		ND	
Chlorobenzene	4.5	100	ppm	ND		ND		ND		ND	
Chloroethane	NS	NS	ppm	ND		ND		ND		ND	
Chloroform	0.37	24	ppm	ND		ND		ND		ND	
Chloromethane	NS	NS	ppm	ND		ND		ND		ND	
cis-1,2-Dichloroethylene	0.19	41	ppm	ND		ND		ND		ND	
cis-1,3-Dichloropropylene	NS	NS	ppm	ND		ND		ND		ND	
Cyclohexane	NS	NS	ppm	ND		ND		ND		ND	
Dibromochloromethane	NS	NS	ppm	ND		ND		ND		ND	
Dibromomethane	NS	NS	ppm	ND		ND		ND		ND	
Dichlorodifluoromethane	NS	NS	ppm	ND		ND		ND		ND	
Ethyl Benzene	1	76	ppm	ND		ND		ND		ND	
Hexachlorobutadiene	NS	NS	ppm	ND		ND		ND		ND	
Isopropylbenzene	NS	NS	ppm	ND		ND		ND		ND	
Methyl acetate	NS	NS	ppm	ND		ND		ND		ND	
Methyl tert-butyl ether (MTBE)	0.1	100	ppm	ND		ND		ND		ND	
Methylcyclohexane	NS	NS	ppm	ND		ND		ND		ND	
Methylene chloride	0.05	81	ppm	ND		ND		ND		ND	

Table 4a. Volatile Organic Compounds in Soil
260 West 126th Street - New York, NY
BCP Site No. C231164

CLIENT SAMPLE ID	NY-UUSCO	NY-RESRR	Units	SB-7 (10-12)		SB-7 (12-14)		SB-4 (0-2)		SB-4 (12-14)	
SAMPLING DATE				6/26/2026		6/26/2026		6/26/2026		6/26/2026	
SAMPLE DEPTH (FT-BG)				10-12		12-14		0-2		12-14	
LAB SAMPLE ID				26F1687-02		26F1687-03		26F1687-04		26F1687-05	
					Qual		Qual		Qual		Qual
n-Butylbenzene	18	100	ppm	ND		ND		ND		ND	
n-Propylbenzene	5	100	ppm	ND		ND		ND		ND	
o-Xylene	NS	NS	ppm	ND		ND		ND		ND	
p- & m- Xylenes	NS	NS	ppm	ND		ND		ND		ND	
p-Isopropyltoluene	NS	NS	ppm	ND		ND		ND		ND	
sec-Butylbenzene	25	100	ppm	ND		ND		ND		ND	
Styrene	NS	NS	ppm	ND		ND		ND		ND	
tert-Butyl alcohol (TBA)	NS	NS	ppm	ND		ND		ND		ND	
tert-Butylbenzene	11	100	ppm	ND		ND		ND		ND	
Tetrachloroethylene	1.3	18	ppm	ND		ND		ND		ND	
Toluene	0.7	100	ppm	0.0031	J	ND		ND		ND	
trans-1,2-Dichloroethylene	0.19	100	ppm	ND		ND		ND		ND	
trans-1,3-Dichloropropylene	NS	NS	ppm	ND		ND		ND		ND	
Trichloroethylene	0.47	6.4	ppm	ND		ND		ND		ND	
Trichlorofluoromethane	NS	NS	ppm	ND		ND		ND		ND	
Vinyl acetate	NS	NS	ppm	ND		ND		ND		ND	
Vinyl Chloride	0.03	0.48	ppm	ND		ND		ND		ND	
Xylenes, Total	0.26	100	ppm	ND		ND		ND		ND	

Notes:

Bold and shaded yellow value indicates concentration exceeds NY-UNRES SCOs

Bold and shaded orange value indicates concentration exceeds NY-UNRES and NY-RESRR SCOs

NY-UNRES = 6 NYCRR Part 375 Unrestricted Use Soil Cleanup Objectives

NY-RESRR = 6 NYCRR Part 375 Restricted-Residential Use Soil Cleanup Objectives

J = Estimated value

ND = Not detected

NS = No standard

ppm = parts per million

Table 4a. Volatile Organic Compounds in Soil
260 West 126th Street - New York, NY
BCP Site No. C231164

CLIENT SAMPLE ID	NY-UUSCO	NY-RESRR	Units	SB-4 (14-15)
SAMPLING DATE				6/26/2026
SAMPLE DEPTH (FT-BG)				14-15
LAB SAMPLE ID				26F1687-06
				Qual
General Chemistry				
Solids, Total	NS	NS	%	97.8
Volatile Organic Compounds				
1,1,1,2-Tetrachloroethane	NS	NS	ppm	ND
1,1,1-Trichloroethane	0.68	100	ppm	ND
1,1,2,2-Tetrachloroethane	NS	NS	ppm	ND
1,1,2-Trichloro-1,2,2-trifluoroethane (Freon 113)	NS	NS	ppm	ND
1,1,2-Trichloroethane	NS	NS	ppm	ND
1,1-Dichloroethane	0.27	47	ppm	ND
1,1-Dichloroethylene	0.24	0.98	ppm	ND
1,1-Dichloropropylene	NS	NS	ppm	ND
1,2,3-Trichlorobenzene	NS	NS	ppm	ND
1,2,3-Trichloropropane	NS	NS	ppm	ND
1,2,4-Trichlorobenzene	NS	NS	ppm	ND
1,2,4-Trimethylbenzene	5.9	100	ppm	ND
1,2-Dibromo-3-chloropropane	NS	NS	ppm	ND
1,2-Dibromoethane	NS	NS	ppm	ND
1,2-Dichlorobenzene	1.1	100	ppm	ND
1,2-Dichloroethane	0.02	5.8	ppm	ND
1,2-Dichloropropane	NS	NS	ppm	ND
1,3,5-Trimethylbenzene	3.1	100	ppm	ND
1,3-Dichlorobenzene	2.6	38	ppm	ND
1,3-Dichloropropane	NS	NS	ppm	ND
1,4-Dichlorobenzene	1.8	24	ppm	ND
2,2-Dichloropropane	NS	NS	ppm	ND
2-Butanone	0.10	100	ppm	ND
2-Chlorotoluene	NS	NS	ppm	ND
2-Hexanone	NS	NS	ppm	ND
4-Chlorotoluene	NS	NS	ppm	ND

Table 4a. Volatile Organic Compounds in Soil
260 West 126th Street - New York, NY
BCP Site No. C231164

CLIENT SAMPLE ID	NY-UUSCO	NY-RESRR	Units	SB-4 (14-15)
SAMPLING DATE				6/26/2026
SAMPLE DEPTH (FT-BG)				14-15
LAB SAMPLE ID				26F1687-06
				Qual
4-Methyl-2-pentanone	NS	NS	ppm	ND
Acetone	0.03	100	ppm	ND
Acrolein	NS	NS	ppm	ND
Acrylonitrile	NS	NS	ppm	ND
Benzene	0.06	3.7	ppm	ND
Bromobenzene	NS	NS	ppm	ND
Bromochloromethane	NS	NS	ppm	ND
Bromodichloromethane	NS	NS	ppm	ND
Bromoform	NS	NS	ppm	ND
Bromomethane	NS	NS	ppm	ND
Carbon disulfide	NS	NS	ppm	ND
Carbon tetrachloride	0.76	7.1	ppm	ND
Chlorobenzene	4.5	100	ppm	ND
Chloroethane	NS	NS	ppm	ND
Chloroform	0.37	24	ppm	ND
Chloromethane	NS	NS	ppm	ND
cis-1,2-Dichloroethylene	0.19	41	ppm	ND
cis-1,3-Dichloropropylene	NS	NS	ppm	ND
Cyclohexane	NS	NS	ppm	ND
Dibromochloromethane	NS	NS	ppm	ND
Dibromomethane	NS	NS	ppm	ND
Dichlorodifluoromethane	NS	NS	ppm	ND
Ethyl Benzene	1	76	ppm	ND
Hexachlorobutadiene	NS	NS	ppm	ND
Isopropylbenzene	NS	NS	ppm	ND
Methyl acetate	NS	NS	ppm	ND
Methyl tert-butyl ether (MTBE)	0.1	100	ppm	ND
Methylcyclohexane	NS	NS	ppm	ND
Methylene chloride	0.05	81	ppm	ND

Table 4a. Volatile Organic Compounds in Soil
260 West 126th Street - New York, NY
BCP Site No. C231164

CLIENT SAMPLE ID	NY-UUSCO	NY-RESRR	Units	SB-4 (14-15)
SAMPLING DATE				6/26/2026
SAMPLE DEPTH (FT-BG)				14-15
LAB SAMPLE ID				26F1687-06
				Qual
n-Butylbenzene	18	100	ppm	ND
n-Propylbenzene	5	100	ppm	ND
o-Xylene	NS	NS	ppm	ND
p- & m- Xylenes	NS	NS	ppm	ND
p-Isopropyltoluene	NS	NS	ppm	ND
sec-Butylbenzene	25	100	ppm	ND
Styrene	NS	NS	ppm	ND
tert-Butyl alcohol (TBA)	NS	NS	ppm	ND
tert-Butylbenzene	11	100	ppm	ND
Tetrachloroethylene	1.3	18	ppm	ND
Toluene	0.7	100	ppm	ND
trans-1,2-Dichloroethylene	0.19	100	ppm	ND
trans-1,3-Dichloropropylene	NS	NS	ppm	ND
Trichloroethylene	0.47	6.4	ppm	ND
Trichlorofluoromethane	NS	NS	ppm	ND
Vinyl acetate	NS	NS	ppm	ND
Vinyl Chloride	0.03	0.48	ppm	ND
Xylenes, Total	0.26	100	ppm	ND

Notes:

Bold and shaded yellow value indicates concentration exceeds NY-UNRES SCOs

Bold and shaded orange value indicates concentration exceeds NY-UNRES and NY-RESRR SCOs

NY-UNRES = 6 NYCRR Part 375 Unrestricted Use Soil Cleanup Objectives

NY-RESRR = 6 NYCRR Part 375 Restricted-Residential Use Soil Cleanup Objectives

J = Estimated value

ND = Not detected

NS = No standard

ppm = parts per million

Table 4b. Semivolatile Organic Compounds in Soil
260 West 126th Street - New York, NY
BCP Site No. C231164

CLIENT SAMPLE ID	NY-UUSCO	NY-RESRR	Units	SB-5 (0-2)	SB-5 (12.5-14.5)	SB-5 (22-24)	SB-5 (22-24)_DUP
SAMPLING DATE				1/5/2026	1/5/2026	1/5/2026	1/5/2026
SAMPLE DEPTH (FT-BG)				0-2	12.5-14.5	22-24	22-24
LAB SAMPLE ID				26A0061-01	26A0061-02	26A0061-03	26A0061-04
				Qual	Qual	Qual	Qual
Semivolatile Organic Compounds							
1,1-Biphenyl	NS	NS	ppm	ND	ND	ND	ND
1,2,4,5-Tetrachlorobenzene	NS	NS	ppm	ND	ND	ND	ND
2,3,4,6-Tetrachlorophenol	NS	NS	ppm	ND	ND	ND	ND
2,4,5-Trichlorophenol	NS	NS	ppm	ND	ND	ND	ND
2,4,6-Trichlorophenol	NS	NS	ppm	ND	ND	ND	ND
2,4-Dichlorophenol	NS	NS	ppm	ND	ND	ND	ND
2,4-Dimethylphenol	NS	NS	ppm	ND	ND	ND	ND
2,4-Dinitrophenol	NS	NS	ppm	ND	ND	ND	ND
2,4-Dinitrotoluene	NS	NS	ppm	ND	ND	ND	ND
2,6-Dinitrotoluene	NS	NS	ppm	ND	ND	ND	ND
2-Chloronaphthalene	NS	NS	ppm	ND	ND	ND	ND
2-Chlorophenol	NS	NS	ppm	ND	ND	ND	ND
2-Methylnaphthalene	NS	NS	ppm	ND	ND	ND	ND
2-Methylphenol	0.33	100	ppm	ND	ND	ND	ND
2-Nitroaniline	NS	NS	ppm	ND	ND	ND	ND
2-Nitrophenol	NS	NS	ppm	ND	ND	ND	ND
3- & 4-Methylphenols	0.33	100	ppm	ND	ND	ND	ND
3,3-Dichlorobenzidine	NS	NS	ppm	ND	ND	ND	ND
3-Nitroaniline	NS	NS	ppm	ND	ND	ND	ND
4,6-Dinitro-2-methylphenol	NS	NS	ppm	ND	ND	ND	ND
4-Bromophenyl phenyl ether	NS	NS	ppm	ND	ND	ND	ND
4-Chloro-3-methylphenol	NS	NS	ppm	ND	ND	ND	ND
4-Chloroaniline	NS	NS	ppm	ND	ND	ND	ND
4-Chlorophenyl phenyl ether	NS	NS	ppm	ND	ND	ND	ND
4-Nitroaniline	NS	NS	ppm	ND	ND	ND	ND
4-Nitrophenol	NS	NS	ppm	ND	ND	ND	ND
Acenaphthene	20	100	ppm	ND	ND	ND	ND
Acenaphthylene	100	100	ppm	ND	ND	ND	ND

Table 4b. Semivolatile Organic Compounds in Soil
260 West 126th Street - New York, NY
BCP Site No. C231164

CLIENT SAMPLE ID	NY-UUSCO	NY-RESRR	Units	SB-5 (0-2)		SB-5 (12.5-14.5)	SB-5 (22-24)	SB-5 (22-24)_DUP
SAMPLING DATE				1/5/2026		1/5/2026	1/5/2026	1/5/2026
SAMPLE DEPTH (FT-BG)				0-2		12.5-14.5	22-24	22-24
LAB SAMPLE ID				26A0061-01		26A0061-02	26A0061-03	26A0061-04
					Qual	Qual	Qual	Qual
Semivolatile Organic Compounds								
Acetophenone	NS	NS	ppm	ND		ND	ND	ND
Anthracene	100	100	ppm	0.183	D	ND	ND	ND
Atrazine	NS	NS	ppm	ND		ND	ND	ND
Benzaldehyde	NS	NS	ppm	ND		ND	ND	ND
Benzo(a)anthracene	1	1.4	ppm	0.731	D	ND	ND	ND
Benzo(a)pyrene	1	1	ppm	0.582	D	ND	ND	ND
Benzo(b)fluoranthene	1	1.4	ppm	0.498	D	ND	ND	ND
Benzo(g,h,i)perylene	0.64	4.9	ppm	0.287	D	ND	ND	ND
Benzo(k)fluoranthene	0.8	4.9	ppm	0.483	D	ND	ND	ND
Benzyl butyl phthalate	NS	NS	ppm	ND		ND	ND	ND
Bis(2-chloroethoxy)methane	NS	NS	ppm	ND		ND	ND	ND
Bis(2-chloroethyl)ether	NS	NS	ppm	ND		ND	ND	ND
Bis(2-chloroisopropyl)ether	NS	NS	ppm	ND		ND	ND	ND
Bis(2-ethylhexyl)phthalate	NS	NS	ppm	ND		ND	ND	ND
Caprolactam	NS	NS	ppm	ND		ND	ND	ND
Carbazole	NS	NS	ppm	ND		ND	ND	ND
Chrysene	1	4.9	ppm	0.631	D	ND	ND	ND
Dibenzo(a,h)anthracene	0.33	0.33	ppm	0.117	D	ND	ND	ND
Dibenzofuran	2.1	18	ppm	ND		ND	ND	ND
Diethyl phthalate	NS	NS	ppm	ND		ND	ND	ND
Dimethyl phthalate	NS	NS	ppm	ND		ND	ND	ND
Di-n-butyl phthalate	NS	NS	ppm	ND		ND	ND	ND
Di-n-octyl phthalate	NS	NS	ppm	ND		ND	ND	ND
Fluoranthene	85	100	ppm	1.3	D	ND	ND	ND
Fluorene	30	100	ppm	0.0504	JD	ND	ND	ND
Hexachlorobenzene	0.33	0.33	ppm	ND		ND	ND	ND
Hexachlorobutadiene	NS	NS	ppm	ND		ND	ND	ND
Hexachlorocyclopentadiene	NS	NS	ppm	ND		ND	ND	ND

Table 4b. Semivolatile Organic Compounds in Soil
260 West 126th Street - New York, NY
BCP Site No. C231164

CLIENT SAMPLE ID	NY-UUSCO	NY-RESRR	Units	SB-5 (0-2)		SB-5 (12.5-14.5)	SB-5 (22-24)	SB-5 (22-24)_DUP
SAMPLING DATE				1/5/2026		1/5/2026	1/5/2026	1/5/2026
SAMPLE DEPTH (FT-BG)				0-2		12.5-14.5	22-24	22-24
LAB SAMPLE ID				26A0061-01		26A0061-02	26A0061-03	26A0061-04
					Qual	Qual	Qual	Qual
Semivolatile Organic Compounds								
Hexachloroethane	NS	NS	ppm	ND		ND	ND	ND
Indeno(1,2,3-cd)pyrene	0.5	1.4	ppm	0.351	D	ND	ND	ND
Isophorone	NS	NS	ppm	ND		ND	ND	ND
Naphthalene	12	100	ppm	ND		ND	ND	ND
Nitrobenzene	0.08	1.8	ppm	ND		ND	ND	ND
N-nitroso-di-n-propylamine	NS	NS	ppm	ND		ND	ND	ND
N-Nitrosodiphenylamine	NS	NS	ppm	ND		ND	ND	ND
Pentachlorophenol	0.8	1.3	ppm	ND		ND	ND	ND
Phenanthrene	1.1	4.9	ppm	0.685	D	ND	ND	ND
Phenol	0.33	100	ppm	ND		ND	ND	ND
Pyrene	64	100	ppm	1.34	D	ND	ND	ND

Notes:

Bold and shaded yellow value indicates concentration exceeds NY-UNRES SCOs

Bold and shaded orange value indicates concentration exceeds NY-UNRES and NY-RESRR SCOs

NY-UNRES = 6 NYCRR Part 375 Unrestricted Use Soil Cleanup Objectives

NY-RESRR = 6 NYCRR Part 375 Restricted-Residential Use Soil Cleanup Objectives

J = Estimated value

D = Diluted

ND = Not detected

NS = No standard

ppm = parts per million

Table 4b. Semivolatile Organic Compounds in Soil
260 West 126th Street - New York, NY
BCP Site No. C231164

CLIENT SAMPLE ID	NY-UUSCO	NY-RESRR	Units	SB-3 (0-2)	SB-3 (8-10)	SB-3 (22-24)	SB-6 (0-2)
SAMPLING DATE				1/5/2026	1/5/2026	1/5/2026	1/5/2026
SAMPLE DEPTH (FT-BG)				0-2	8-10	22-24	0-2
LAB SAMPLE ID				26A0061-05	26A0061-06	26A0061-07	26A0061-08
				Qual	Qual	Qual	Qual
Semivolatile Organic Compounds							
1,1-Biphenyl	NS	NS	ppm	ND	ND	ND	ND
1,2,4,5-Tetrachlorobenzene	NS	NS	ppm	ND	ND	ND	ND
2,3,4,6-Tetrachlorophenol	NS	NS	ppm	ND	ND	ND	ND
2,4,5-Trichlorophenol	NS	NS	ppm	ND	ND	ND	ND
2,4,6-Trichlorophenol	NS	NS	ppm	ND	ND	ND	ND
2,4-Dichlorophenol	NS	NS	ppm	ND	ND	ND	ND
2,4-Dimethylphenol	NS	NS	ppm	ND	ND	ND	ND
2,4-Dinitrophenol	NS	NS	ppm	ND	ND	ND	ND
2,4-Dinitrotoluene	NS	NS	ppm	ND	ND	ND	ND
2,6-Dinitrotoluene	NS	NS	ppm	ND	ND	ND	ND
2-Chloronaphthalene	NS	NS	ppm	ND	ND	ND	ND
2-Chlorophenol	NS	NS	ppm	ND	ND	ND	ND
2-Methylnaphthalene	NS	NS	ppm	ND	ND	ND	ND
2-Methylphenol	0.33	100	ppm	ND	ND	ND	ND
2-Nitroaniline	NS	NS	ppm	ND	ND	ND	ND
2-Nitrophenol	NS	NS	ppm	ND	ND	ND	ND
3- & 4-Methylphenols	0.33	100	ppm	ND	ND	ND	ND
3,3-Dichlorobenzidine	NS	NS	ppm	ND	ND	ND	ND
3-Nitroaniline	NS	NS	ppm	ND	ND	ND	ND
4,6-Dinitro-2-methylphenol	NS	NS	ppm	ND	ND	ND	ND
4-Bromophenyl phenyl ether	NS	NS	ppm	ND	ND	ND	ND
4-Chloro-3-methylphenol	NS	NS	ppm	ND	ND	ND	ND
4-Chloroaniline	NS	NS	ppm	ND	ND	ND	ND
4-Chlorophenyl phenyl ether	NS	NS	ppm	ND	ND	ND	ND
4-Nitroaniline	NS	NS	ppm	ND	ND	ND	ND
4-Nitrophenol	NS	NS	ppm	ND	ND	ND	ND
Acenaphthene	20	100	ppm	ND	ND	ND	ND
Acenaphthylene	100	100	ppm	ND	ND	ND	ND

Table 4b. Semivolatile Organic Compounds in Soil
260 West 126th Street - New York, NY
BCP Site No. C231164

CLIENT SAMPLE ID	NY-UUSCO	NY-RESRR	Units	SB-3 (0-2)		SB-3 (8-10)		SB-3 (22-24)		SB-6 (0-2)	
SAMPLING DATE				1/5/2026		1/5/2026		1/5/2026		1/5/2026	
SAMPLE DEPTH (FT-BG)				0-2		8-10		22-24		0-2	
LAB SAMPLE ID				26A0061-05		26A0061-06		26A0061-07		26A0061-08	
					Qual		Qual		Qual		Qual
Semivolatile Organic Compounds											
Acetophenone	NS	NS	ppm	ND		ND		ND		ND	
Anthracene	100	100	ppm	ND		ND		ND		ND	
Atrazine	NS	NS	ppm	ND		ND		ND		ND	
Benzaldehyde	NS	NS	ppm	ND		ND		ND		ND	
Benzo(a)anthracene	1	1.4	ppm	ND		ND		ND		0.158	D
Benzo(a)pyrene	1	1	ppm	ND		ND		ND		0.216	D
Benzo(b)fluoranthene	1	1.4	ppm	ND		ND		ND		0.188	D
Benzo(g,h,i)perylene	0.64	4.9	ppm	ND		ND		ND		0.121	D
Benzo(k)fluoranthene	0.8	4.9	ppm	ND		ND		ND		0.178	D
Benzyl butyl phthalate	NS	NS	ppm	ND		ND		ND		ND	
Bis(2-chloroethoxy)methane	NS	NS	ppm	ND		ND		ND		ND	
Bis(2-chloroethyl)ether	NS	NS	ppm	ND		ND		ND		ND	
Bis(2-chloroisopropyl)ether	NS	NS	ppm	ND		ND		ND		ND	
Bis(2-ethylhexyl)phthalate	NS	NS	ppm	ND		0.0892	D	ND		0.0554	JD
Caprolactam	NS	NS	ppm	ND		ND		ND		ND	
Carbazole	NS	NS	ppm	ND		ND		ND		ND	
Chrysene	1	4.9	ppm	ND		ND		ND		0.173	D
Dibenzo(a,h)anthracene	0.33	0.33	ppm	ND		ND		ND		ND	
Dibenzofuran	2.1	18	ppm	ND		ND		ND		ND	
Diethyl phthalate	NS	NS	ppm	ND		ND		ND		ND	
Dimethyl phthalate	NS	NS	ppm	ND		ND		ND		ND	
Di-n-butyl phthalate	NS	NS	ppm	ND		ND		ND		ND	
Di-n-octyl phthalate	NS	NS	ppm	ND		ND		ND		ND	
Fluoranthene	85	100	ppm	0.0725	JD	ND		ND		0.322	D
Fluorene	30	100	ppm	ND		ND		ND		ND	
Hexachlorobenzene	0.33	0.33	ppm	ND		ND		ND		ND	
Hexachlorobutadiene	NS	NS	ppm	ND		ND		ND		ND	
Hexachlorocyclopentadiene	NS	NS	ppm	ND		ND		ND		ND	

Table 4b. Semivolatile Organic Compounds in Soil
260 West 126th Street - New York, NY
BCP Site No. C231164

CLIENT SAMPLE ID	NY-UUSCO	NY-RESRR	Units	SB-3 (0-2)		SB-3 (8-10)	SB-3 (22-24)	SB-6 (0-2)	
SAMPLING DATE				1/5/2026		1/5/2026	1/5/2026	1/5/2026	
SAMPLE DEPTH (FT-BG)				0-2		8-10	22-24	0-2	
LAB SAMPLE ID				26A0061-05		26A0061-06	26A0061-07	26A0061-08	
					Qual				Qual
Semivolatile Organic Compounds									
Hexachloroethane	NS	NS	ppm	ND		ND	ND	ND	
Indeno(1,2,3-cd)pyrene	0.5	1.4	ppm	ND		ND	ND	0.0971	D
Isophorone	NS	NS	ppm	ND		ND	ND	ND	
Naphthalene	12	100	ppm	ND		ND	ND	ND	
Nitrobenzene	0.08	1.8	ppm	ND		ND	ND	ND	
N-nitroso-di-n-propylamine	NS	NS	ppm	ND		ND	ND	ND	
N-Nitrosodiphenylamine	NS	NS	ppm	ND		ND	ND	ND	
Pentachlorophenol	0.8	1.3	ppm	ND		ND	ND	ND	
Phenanthrene	1.1	4.9	ppm	ND		ND	ND	0.162	D
Phenol	0.33	100	ppm	ND		ND	ND	ND	
Pyrene	64	100	ppm	0.0691	JD	ND	ND	0.232	D

Notes:

Bold and shaded yellow value indicates concentration exceeds NY-UNRES SCOs

Bold and shaded orange value indicates concentration exceeds NY-UNRES and NY-RESRR SCOs

NY-UNRES = 6 NYCRR Part 375 Unrestricted Use Soil Cleanup Objectives

NY-RESRR = 6 NYCRR Part 375 Restricted-Residential Use Soil Cleanup Objectives

J = Estimated value

D = Diluted

ND = Not detected

NS = No standard

ppm = parts per million

Table 4b. Semivolatile Organic Compounds in Soil
260 West 126th Street - New York, NY
BCP Site No. C231164

CLIENT SAMPLE ID	NY-UUSCO	NY-RESRR	Units	SB-6 (8-10)	SB-6 (22-24)	SB-8 (0-2)	SB-8 (8-10)
SAMPLING DATE				1/5/2026	1/5/2026	1/5/2026	1/6/2026
SAMPLE DEPTH (FT-BG)				8-10	22-24	0-2	8-10
LAB SAMPLE ID				26A0061-09	26A0061-10	26A0061-11	26A0111-02
				Qual	Qual	Qual	Qual
Semivolatile Organic Compounds							
1,1-Biphenyl	NS	NS	ppm	ND	ND	ND	ND
1,2,4,5-Tetrachlorobenzene	NS	NS	ppm	ND	ND	ND	ND
2,3,4,6-Tetrachlorophenol	NS	NS	ppm	ND	ND	ND	ND
2,4,5-Trichlorophenol	NS	NS	ppm	ND	ND	ND	ND
2,4,6-Trichlorophenol	NS	NS	ppm	ND	ND	ND	ND
2,4-Dichlorophenol	NS	NS	ppm	ND	ND	ND	ND
2,4-Dimethylphenol	NS	NS	ppm	ND	ND	ND	ND
2,4-Dinitrophenol	NS	NS	ppm	ND	ND	ND	ND
2,4-Dinitrotoluene	NS	NS	ppm	ND	ND	ND	ND
2,6-Dinitrotoluene	NS	NS	ppm	ND	ND	ND	ND
2-Chloronaphthalene	NS	NS	ppm	ND	ND	ND	ND
2-Chlorophenol	NS	NS	ppm	ND	ND	ND	ND
2-Methylnaphthalene	NS	NS	ppm	ND	ND	ND	ND
2-Methylphenol	0.33	100	ppm	ND	ND	ND	ND
2-Nitroaniline	NS	NS	ppm	ND	ND	ND	ND
2-Nitrophenol	NS	NS	ppm	ND	ND	ND	ND
3- & 4-Methylphenols	0.33	100	ppm	ND	ND	ND	ND
3,3-Dichlorobenzidine	NS	NS	ppm	ND	ND	ND	ND
3-Nitroaniline	NS	NS	ppm	ND	ND	ND	ND
4,6-Dinitro-2-methylphenol	NS	NS	ppm	ND	ND	ND	ND
4-Bromophenyl phenyl ether	NS	NS	ppm	ND	ND	ND	ND
4-Chloro-3-methylphenol	NS	NS	ppm	ND	ND	ND	ND
4-Chloroaniline	NS	NS	ppm	ND	ND	ND	ND
4-Chlorophenyl phenyl ether	NS	NS	ppm	ND	ND	ND	ND
4-Nitroaniline	NS	NS	ppm	ND	ND	ND	ND
4-Nitrophenol	NS	NS	ppm	ND	ND	ND	ND
Acenaphthene	20	100	ppm	ND	ND	0.0749 JD	ND
Acenaphthylene	100	100	ppm	ND	ND	0.0892 JD	ND

Table 4b. Semivolatile Organic Compounds in Soil
260 West 126th Street - New York, NY
BCP Site No. C231164

CLIENT SAMPLE ID	NY-UUSCO	NY-RESRR	Units	SB-6 (8-10)		SB-6 (22-24)		SB-8 (0-2)		SB-8 (8-10)	
SAMPLING DATE				1/5/2026		1/5/2026		1/5/2026		1/6/2026	
SAMPLE DEPTH (FT-BG)				8-10		22-24		0-2		8-10	
LAB SAMPLE ID				26A0061-09		26A0061-10		26A0061-11		26A0111-02	
					Qual		Qual		Qual		Qual
Semivolatile Organic Compounds											
Acetophenone	NS	NS	ppm	ND		ND		ND		ND	
Anthracene	100	100	ppm	ND		ND		0.211	D	ND	
Atrazine	NS	NS	ppm	ND		ND		ND		ND	
Benzaldehyde	NS	NS	ppm	ND		ND		ND		ND	
Benzo(a)anthracene	1	1.4	ppm	ND		ND		0.649	D	ND	
Benzo(a)pyrene	1	1	ppm	ND		ND		0.726	D	ND	
Benzo(b)fluoranthene	1	1.4	ppm	ND		ND		0.648	D	ND	
Benzo(g,h,i)perylene	0.64	4.9	ppm	ND		ND		0.417	D	ND	
Benzo(k)fluoranthene	0.8	4.9	ppm	ND		ND		0.647	D	ND	
Benzyl butyl phthalate	NS	NS	ppm	ND		ND		ND		ND	
Bis(2-chloroethoxy)methane	NS	NS	ppm	ND		ND		ND		ND	
Bis(2-chloroethyl)ether	NS	NS	ppm	ND		ND		ND		ND	
Bis(2-chloroisopropyl)ether	NS	NS	ppm	ND		ND		ND		ND	
Bis(2-ethylhexyl)phthalate	NS	NS	ppm	ND		ND		0.055	JD	ND	
Caprolactam	NS	NS	ppm	ND		ND		ND		ND	
Carbazole	NS	NS	ppm	ND		ND		0.118	D	ND	
Chrysene	1	4.9	ppm	ND		ND		0.69	D	ND	
Dibenzo(a,h)anthracene	0.33	0.33	ppm	ND		ND		0.139	D	ND	
Dibenzofuran	2.1	18	ppm	ND		ND		ND		ND	
Diethyl phthalate	NS	NS	ppm	ND		ND		ND		ND	
Dimethyl phthalate	NS	NS	ppm	ND		ND		ND		ND	
Di-n-butyl phthalate	NS	NS	ppm	ND		ND		ND		ND	
Di-n-octyl phthalate	NS	NS	ppm	ND		ND		ND		ND	
Fluoranthene	85	100	ppm	ND		ND		1.4	D	ND	
Fluorene	30	100	ppm	ND		ND		0.0669	JD	ND	
Hexachlorobenzene	0.33	0.33	ppm	ND		ND		ND		ND	
Hexachlorobutadiene	NS	NS	ppm	ND		ND		ND		ND	
Hexachlorocyclopentadiene	NS	NS	ppm	ND		ND		ND		ND	

Table 4b. Semivolatile Organic Compounds in Soil
260 West 126th Street - New York, NY
BCP Site No. C231164

CLIENT SAMPLE ID	NY-UUSCO	NY-RESRR	Units	SB-6 (8-10)	SB-6 (22-24)	SB-8 (0-2)	SB-8 (8-10)
SAMPLING DATE				1/5/2026	1/5/2026	1/5/2026	1/6/2026
SAMPLE DEPTH (FT-BG)				8-10	22-24	0-2	8-10
LAB SAMPLE ID				26A0061-09	26A0061-10	26A0061-11	26A0111-02
				Qual	Qual	Qual	Qual
Semivolatile Organic Compounds							
Hexachloroethane	NS	NS	ppm	ND	ND	ND	ND
Indeno(1,2,3-cd)pyrene	0.5	1.4	ppm	ND	ND	0.352 D	ND
Isophorone	NS	NS	ppm	ND	ND	ND	ND
Naphthalene	12	100	ppm	ND	ND	ND	ND
Nitrobenzene	0.08	1.8	ppm	ND	ND	ND	ND
N-nitroso-di-n-propylamine	NS	NS	ppm	ND	ND	ND	ND
N-Nitrosodiphenylamine	NS	NS	ppm	ND	ND	ND	ND
Pentachlorophenol	0.8	1.3	ppm	ND	ND	ND	ND
Phenanthrene	1.1	4.9	ppm	ND	ND	0.904 D	ND
Phenol	0.33	100	ppm	ND	ND	ND	ND
Pyrene	64	100	ppm	ND	ND	0.975 D	ND

Notes:

Bold and shaded yellow value indicates concentration exceeds NY-UNRES SCOs

Bold and shaded orange value indicates concentration exceeds NY-UNRES and NY-RESRR SCOs

NY-UNRES = 6 NYCRR Part 375 Unrestricted Use Soil Cleanup Objectives

NY-RESRR = 6 NYCRR Part 375 Restricted-Residential Use Soil Cleanup Objectives

J = Estimated value

D = Diluted

ND = Not detected

NS = No standard

ppm = parts per million

Table 4b. Semivolatile Organic Compounds in Soil
260 West 126th Street - New York, NY
BCP Site No. C231164

CLIENT SAMPLE ID	NY-UUSCO	NY-RESRR	Units	SB-8 (22-24)		SB-2 (0-2)		SB-2 (0-2)_DUP		SB-2 (6-8)	
SAMPLING DATE				1/6/2026		1/6/2026		1/6/2026		1/6/2026	
SAMPLE DEPTH (FT-BG)				22-24		0-2		21-23		6-8	
LAB SAMPLE ID				26A0111-03		26A0111-04		26A0111-13		26A0111-05	
					Qual		Qual		Qual		Qual
Semivolatile Organic Compounds											
1,1-Biphenyl	NS	NS	ppm	ND		ND		ND		ND	
1,2,4,5-Tetrachlorobenzene	NS	NS	ppm	ND		ND		ND		ND	
2,3,4,6-Tetrachlorophenol	NS	NS	ppm	ND		ND		ND		ND	
2,4,5-Trichlorophenol	NS	NS	ppm	ND		ND		ND		ND	
2,4,6-Trichlorophenol	NS	NS	ppm	ND		ND		ND		ND	
2,4-Dichlorophenol	NS	NS	ppm	ND		ND		ND		ND	
2,4-Dimethylphenol	NS	NS	ppm	ND		ND		ND		ND	
2,4-Dinitrophenol	NS	NS	ppm	ND		ND		ND		ND	
2,4-Dinitrotoluene	NS	NS	ppm	ND		ND		ND		ND	
2,6-Dinitrotoluene	NS	NS	ppm	ND		ND		ND		ND	
2-Chloronaphthalene	NS	NS	ppm	ND		ND		ND		ND	
2-Chlorophenol	NS	NS	ppm	ND		ND		ND		ND	
2-Methylnaphthalene	NS	NS	ppm	ND		1.04	D	0.107	D	ND	
2-Methylphenol	0.33	100	ppm	ND		ND		ND		ND	
2-Nitroaniline	NS	NS	ppm	ND		ND		ND		ND	
2-Nitrophenol	NS	NS	ppm	ND		ND		ND		ND	
3- & 4-Methylphenols	0.33	100	ppm	ND		ND		ND		ND	
3,3-Dichlorobenzidine	NS	NS	ppm	ND		ND		ND		ND	
3-Nitroaniline	NS	NS	ppm	ND		ND		ND		ND	
4,6-Dinitro-2-methylphenol	NS	NS	ppm	ND		ND		ND		ND	
4-Bromophenyl phenyl ether	NS	NS	ppm	ND		ND		ND		ND	
4-Chloro-3-methylphenol	NS	NS	ppm	ND		ND		ND		ND	
4-Chloroaniline	NS	NS	ppm	ND		ND		ND		ND	
4-Chlorophenyl phenyl ether	NS	NS	ppm	ND		ND		ND		ND	
4-Nitroaniline	NS	NS	ppm	ND		ND		ND		ND	
4-Nitrophenol	NS	NS	ppm	ND		ND		ND		ND	
Acenaphthene	20	100	ppm	ND		0.51	D	ND		ND	
Acenaphthylene	100	100	ppm	ND		1.16	D	0.0482	JD	ND	

Table 4b. Semivolatile Organic Compounds in Soil
260 West 126th Street - New York, NY
BCP Site No. C231164

CLIENT SAMPLE ID	NY-UUSCO	NY-RESRR	Units	SB-8 (22-24)		SB-2 (0-2)		SB-2 (0-2)_DUP		SB-2 (6-8)	
SAMPLING DATE				1/6/2026		1/6/2026		1/6/2026		1/6/2026	
SAMPLE DEPTH (FT-BG)				22-24		0-2		21-23		6-8	
LAB SAMPLE ID				26A0111-03		26A0111-04		26A0111-13		26A0111-05	
					Qual		Qual		Qual		Qual
Semivolatile Organic Compounds											
Acetophenone	NS	NS	ppm	ND		ND		ND		ND	
Anthracene	100	100	ppm	ND		2.09	D	0.466	D	0.0627	JD
Atrazine	NS	NS	ppm	ND		ND		ND		ND	
Benzaldehyde	NS	NS	ppm	ND		ND		ND		ND	
Benzo(a)anthracene	1	1.4	ppm	ND		**16.7**	**D**	0.403	D	0.22	D
Benzo(a)pyrene	1	1	ppm	ND		**13.6**	**D**	0.344	D	0.166	D
Benzo(b)fluoranthene	1	1.4	ppm	ND		**24.1**	**D**	0.32	D	0.154	D
Benzo(g,h,i)perylene	0.64	4.9	ppm	ND		**8.99**	**D**	0.21	D	0.0992	D
Benzo(k)fluoranthene	0.8	4.9	ppm	ND		ND		0.298	D	0.145	D
Benzyl butyl phthalate	NS	NS	ppm	ND		ND		ND		ND	
Bis(2-chloroethoxy)methane	NS	NS	ppm	ND		ND		ND		ND	
Bis(2-chloroethyl)ether	NS	NS	ppm	ND		ND		ND		ND	
Bis(2-chloroisopropyl)ether	NS	NS	ppm	ND		ND		ND		ND	
Bis(2-ethylhexyl)phthalate	NS	NS	ppm	ND		0.17	D	ND		ND	
Caprolactam	NS	NS	ppm	ND		ND		ND		ND	
Carbazole	NS	NS	ppm	ND		0.88	D	0.0505	JD	ND	
Chrysene	1	4.9	ppm	ND		**16.4**	**D**	0.39	D	0.218	D
Dibenzo(a,h)anthracene	0.33	0.33	ppm	ND		**1.43**	**D**	0.0852	JD	ND	
Dibenzofuran	2.1	18	ppm	ND		ND		ND		ND	
Diethyl phthalate	NS	NS	ppm	ND		ND		ND		ND	
Dimethyl phthalate	NS	NS	ppm	ND		ND		ND		ND	
Di-n-butyl phthalate	NS	NS	ppm	ND		ND		ND		ND	
Di-n-octyl phthalate	NS	NS	ppm	ND		ND		ND		ND	
Fluoranthene	85	100	ppm	ND		30.6	D	0.835	D	0.433	D
Fluorene	30	100	ppm	ND		0.584	D	ND		ND	
Hexachlorobenzene	0.33	0.33	ppm	ND		ND		ND		ND	
Hexachlorobutadiene	NS	NS	ppm	ND		ND		ND		ND	
Hexachlorocyclopentadiene	NS	NS	ppm	ND		ND		ND		ND	

Table 4b. Semivolatile Organic Compounds in Soil
260 West 126th Street - New York, NY
BCP Site No. C231164

CLIENT SAMPLE ID	NY-UUSCO	NY-RESRR	Units	SB-8 (22-24)		SB-2 (0-2)		SB-2 (0-2)_DUP		SB-2 (6-8)	
SAMPLING DATE				1/6/2026		1/6/2026		1/6/2026		1/6/2026	
SAMPLE DEPTH (FT-BG)				22-24		0-2		21-23		6-8	
LAB SAMPLE ID				26A0111-03		26A0111-04		26A0111-13		26A0111-05	
					Qual		Qual		Qual		Qual
Semivolatile Organic Compounds											
Hexachloroethane	NS	NS	ppm	ND		ND		ND		ND	
Indeno(1,2,3-cd)pyrene	0.5	1.4	ppm	ND		**7.26**	**D**	0.257	D	0.127	D
Isophorone	NS	NS	ppm	ND		ND		ND		ND	
Naphthalene	12	100	ppm	ND		0.997	D	0.0942	JD	ND	
Nitrobenzene	0.08	1.8	ppm	ND		ND		ND		ND	
N-nitroso-di-n-propylamine	NS	NS	ppm	ND		ND		ND		ND	
N-Nitrosodiphenylamine	NS	NS	ppm	ND		ND		ND		ND	
Pentachlorophenol	0.8	1.3	ppm	ND		ND		ND		ND	
Phenanthrene	1.1	4.9	ppm	ND		**23.3**	**D**	0.451	D	0.278	D
Phenol	0.33	100	ppm	ND		ND		ND		ND	
Pyrene	64	100	ppm	ND		34.8	D	0.8	D	0.413	D

Notes:

Bold and shaded yellow value indicates concentration exceeds NY-UNRES SCOs

Bold and shaded orange value indicates concentration exceeds NY-UNRES and NY-RESRR SCOs

NY-UNRES = 6 NYCRR Part 375 Unrestricted Use Soil Cleanup Objectives

NY-RESRR = 6 NYCRR Part 375 Restricted-Residential Use Soil Cleanup Objectives

J = Estimated value

D = Diluted

ND = Not detected

NS = No standard

ppm = parts per million

Table 4b. Semivolatile Organic Compounds in Soil
260 West 126th Street - New York, NY
BCP Site No. C231164

CLIENT SAMPLE ID	NY-UUSCO	NY-RESRR	Units	SB-2 (22-24)		SB-9 (0-2)		SB-9 (6-8)		SB-9 (22-24)	
SAMPLING DATE				1/6/2026		1/6/2026		1/6/2026		1/6/2026	
SAMPLE DEPTH (FT-BG)				22-24		0-2		6-8		22-24	
LAB SAMPLE ID				26A0111-06		26A0111-07		26A0111-08		26A0111-09	
					Qual		Qual		Qual		Qual
Semivolatile Organic Compounds											
1,1-Biphenyl	NS	NS	ppm	ND		ND		ND		ND	
1,2,4,5-Tetrachlorobenzene	NS	NS	ppm	ND		ND		ND		ND	
2,3,4,6-Tetrachlorophenol	NS	NS	ppm	ND		ND		ND		ND	
2,4,5-Trichlorophenol	NS	NS	ppm	ND		ND		ND		ND	
2,4,6-Trichlorophenol	NS	NS	ppm	ND		ND		ND		ND	
2,4-Dichlorophenol	NS	NS	ppm	ND		ND		ND		ND	
2,4-Dimethylphenol	NS	NS	ppm	ND		ND		ND		ND	
2,4-Dinitrophenol	NS	NS	ppm	ND		ND		ND		ND	
2,4-Dinitrotoluene	NS	NS	ppm	ND		ND		ND		ND	
2,6-Dinitrotoluene	NS	NS	ppm	ND		ND		ND		ND	
2-Chloronaphthalene	NS	NS	ppm	ND		ND		ND		ND	
2-Chlorophenol	NS	NS	ppm	ND		ND		ND		ND	
2-Methylnaphthalene	NS	NS	ppm	ND		0.201	D	ND		ND	
2-Methylphenol	0.33	100	ppm	ND		ND		ND		ND	
2-Nitroaniline	NS	NS	ppm	ND		ND		ND		ND	
2-Nitrophenol	NS	NS	ppm	ND		ND		ND		ND	
3- & 4-Methylphenols	0.33	100	ppm	ND		ND		ND		ND	
3,3-Dichlorobenzidine	NS	NS	ppm	ND		ND		ND		ND	
3-Nitroaniline	NS	NS	ppm	ND		ND		ND		ND	
4,6-Dinitro-2-methylphenol	NS	NS	ppm	ND		ND		ND		ND	
4-Bromophenyl phenyl ether	NS	NS	ppm	ND		ND		ND		ND	
4-Chloro-3-methylphenol	NS	NS	ppm	ND		ND		ND		ND	
4-Chloroaniline	NS	NS	ppm	ND		ND		ND		ND	
4-Chlorophenyl phenyl ether	NS	NS	ppm	ND		ND		ND		ND	
4-Nitroaniline	NS	NS	ppm	ND		ND		ND		ND	
4-Nitrophenol	NS	NS	ppm	ND		ND		ND		ND	
Acenaphthene	20	100	ppm	ND		0.874	D	ND		ND	
Acenaphthylene	100	100	ppm	ND		0.0866	JD	ND		ND	

Table 4b. Semivolatile Organic Compounds in Soil
260 West 126th Street - New York, NY
BCP Site No. C231164

CLIENT SAMPLE ID	NY-UUSCO	NY-RESRR	Units	SB-2 (22-24)		SB-9 (0-2)		SB-9 (6-8)		SB-9 (22-24)	
SAMPLING DATE				1/6/2026		1/6/2026		1/6/2026		1/6/2026	
SAMPLE DEPTH (FT-BG)				22-24		0-2		6-8		22-24	
LAB SAMPLE ID				26A0111-06		26A0111-07		26A0111-08		26A0111-09	
					Qual		Qual		Qual		Qual
Semivolatile Organic Compounds											
Acetophenone	NS	NS	ppm	ND		ND		ND		ND	
Anthracene	100	100	ppm	ND		1.67	D	ND		ND	
Atrazine	NS	NS	ppm	ND		ND		ND		ND	
Benzaldehyde	NS	NS	ppm	ND		ND		ND		ND	
Benzo(a)anthracene	1	1.4	ppm	ND		**5.94**	**D**	0.104	D	ND	
Benzo(a)pyrene	1	1	ppm	ND		**4.44**	**JD**	0.0822	JD	ND	
Benzo(b)fluoranthene	1	1.4	ppm	ND		**3.04**	**D**	0.0691	JD	ND	
Benzo(g,h,i)perylene	0.64	4.9	ppm	ND		**1.97**	**D**	0.0493	JD	ND	
Benzo(k)fluoranthene	0.8	4.9	ppm	ND		**2.66**	**D**	0.0609	JD	ND	
Benzyl butyl phthalate	NS	NS	ppm	ND		ND		ND		ND	
Bis(2-chloroethoxy)methane	NS	NS	ppm	ND		ND		ND		ND	
Bis(2-chloroethyl)ether	NS	NS	ppm	ND		ND		ND		ND	
Bis(2-chloroisopropyl)ether	NS	NS	ppm	ND		ND		ND		ND	
Bis(2-ethylhexyl)phthalate	NS	NS	ppm	ND		ND		ND		ND	
Caprolactam	NS	NS	ppm	ND		ND		ND		ND	
Carbazole	NS	NS	ppm	ND		0.839	D	ND		ND	
Chrysene	1	4.9	ppm	ND		**5.4**	**D**	0.0876	D	ND	
Dibenzo(a,h)anthracene	0.33	0.33	ppm	ND		**0.79**	**D**	ND		ND	
Dibenzofuran	2.1	18	ppm	ND		0.376	D	ND		ND	
Diethyl phthalate	NS	NS	ppm	ND		ND		ND		ND	
Dimethyl phthalate	NS	NS	ppm	ND		ND		ND		ND	
Di-n-butyl phthalate	NS	NS	ppm	ND		ND		ND		ND	
Di-n-octyl phthalate	NS	NS	ppm	ND		ND		ND		ND	
Fluoranthene	85	100	ppm	ND		10.3	D	0.203	D	ND	
Fluorene	30	100	ppm	ND		0.715	D	ND		ND	
Hexachlorobenzene	0.33	0.33	ppm	ND		ND		ND		ND	
Hexachlorobutadiene	NS	NS	ppm	ND		ND		ND		ND	
Hexachlorocyclopentadiene	NS	NS	ppm	ND		ND		ND		ND	

Table 4b. Semivolatile Organic Compounds in Soil
260 West 126th Street - New York, NY
BCP Site No. C231164

CLIENT SAMPLE ID	NY-UUSCO	NY-RESRR	Units	SB-2 (22-24)		SB-9 (0-2)		SB-9 (6-8)		SB-9 (22-24)	
SAMPLING DATE				1/6/2026		1/6/2026		1/6/2026		1/6/2026	
SAMPLE DEPTH (FT-BG)				22-24		0-2		6-8		22-24	
LAB SAMPLE ID				26A0111-06		26A0111-07		26A0111-08		26A0111-09	
					Qual		Qual		Qual		Qual
Semivolatile Organic Compounds											
Hexachloroethane	NS	NS	ppm	ND		ND		ND		ND	
Indeno(1,2,3-cd)pyrene	0.5	1.4	ppm	ND		**2.29**	**D**	0.0513	JD	ND	
Isophorone	NS	NS	ppm	ND		ND		ND		ND	
Naphthalene	12	100	ppm	ND		0.343	D	ND		ND	
Nitrobenzene	0.08	1.8	ppm	ND		ND		ND		ND	
N-nitroso-di-n-propylamine	NS	NS	ppm	ND		ND		ND		ND	
N-Nitrosodiphenylamine	NS	NS	ppm	ND		ND		ND		ND	
Pentachlorophenol	0.8	1.3	ppm	ND		ND		ND		ND	
Phenanthrene	1.1	4.9	ppm	ND		**9.58**	**D**	0.172	D	ND	
Phenol	0.33	100	ppm	ND		ND		ND		ND	
Pyrene	64	100	ppm	ND		12.2	D	0.185	D	ND	

Notes:

Bold and shaded yellow value indicates concentration exceeds NY-UNRES SCOs

Bold and shaded orange value indicates concentration exceeds NY-UNRES and NY-RESRR SCOs

NY-UNRES = 6 NYCRR Part 375 Unrestricted Use Soil Cleanup Objectives

NY-RESRR = 6 NYCRR Part 375 Restricted-Residential Use Soil Cleanup Objectives

J = Estimated value

D = Diluted

ND = Not detected

NS = No standard

ppm = parts per million

Table 4b. Semivolatile Organic Compounds in Soil
260 West 126th Street - New York, NY
BCP Site No. C231164

CLIENT SAMPLE ID	NY-UUSCO	NY-RESRR	Units	SB-1 (0-2)		SB-1 (6-8)	SB-1 (21-23)	SB-7 (0-2)
SAMPLING DATE				1/6/2026		1/6/2026	1/6/2026	6/26/2026
SAMPLE DEPTH (FT-BG)				0-2		6-8	21-23	0-2
LAB SAMPLE ID				26A0111-10		26A0111-11	26A0111-12	26F1687-01
					Qual	Qual	Qual	Qual
Semivolatile Organic Compounds								
1,1-Biphenyl	NS	NS	ppm	ND		ND	ND	ND
1,2,4,5-Tetrachlorobenzene	NS	NS	ppm	ND		ND	ND	ND
2,3,4,6-Tetrachlorophenol	NS	NS	ppm	ND		ND	ND	ND
2,4,5-Trichlorophenol	NS	NS	ppm	ND		ND	ND	ND
2,4,6-Trichlorophenol	NS	NS	ppm	ND		ND	ND	ND
2,4-Dichlorophenol	NS	NS	ppm	ND		ND	ND	ND
2,4-Dimethylphenol	NS	NS	ppm	ND		ND	ND	ND
2,4-Dinitrophenol	NS	NS	ppm	ND		ND	ND	ND
2,4-Dinitrotoluene	NS	NS	ppm	ND		ND	ND	ND
2,6-Dinitrotoluene	NS	NS	ppm	ND		ND	ND	ND
2-Chloronaphthalene	NS	NS	ppm	ND		ND	ND	ND
2-Chlorophenol	NS	NS	ppm	ND		ND	ND	ND
2-Methylnaphthalene	NS	NS	ppm	ND		ND	ND	ND
2-Methylphenol	0.33	100	ppm	ND		ND	ND	ND
2-Nitroaniline	NS	NS	ppm	ND		ND	ND	ND
2-Nitrophenol	NS	NS	ppm	ND		ND	ND	ND
3- & 4-Methylphenols	0.33	100	ppm	ND		ND	ND	ND
3,3-Dichlorobenzidine	NS	NS	ppm	ND		ND	ND	ND
3-Nitroaniline	NS	NS	ppm	ND		ND	ND	ND
4,6-Dinitro-2-methylphenol	NS	NS	ppm	ND		ND	ND	ND
4-Bromophenyl phenyl ether	NS	NS	ppm	ND		ND	ND	ND
4-Chloro-3-methylphenol	NS	NS	ppm	ND		ND	ND	ND
4-Chloroaniline	NS	NS	ppm	ND		ND	ND	ND
4-Chlorophenyl phenyl ether	NS	NS	ppm	ND		ND	ND	ND
4-Nitroaniline	NS	NS	ppm	ND		ND	ND	ND
4-Nitrophenol	NS	NS	ppm	ND		ND	ND	ND
Acenaphthene	20	100	ppm	ND		ND	ND	ND
Acenaphthylene	100	100	ppm	0.0454	JD	ND	ND	ND

Table 4b. Semivolatile Organic Compounds in Soil
260 West 126th Street - New York, NY
BCP Site No. C231164

CLIENT SAMPLE ID	NY-UUSCO	NY-RESRR	Units	SB-1 (0-2)		SB-1 (6-8)		SB-1 (21-23)		SB-7 (0-2)	
SAMPLING DATE				1/6/2026		1/6/2026		1/6/2026		6/26/2026	
SAMPLE DEPTH (FT-BG)				0-2		6-8		21-23		0-2	
LAB SAMPLE ID				26A0111-10		26A0111-11		26A0111-12		26F1687-01	
					Qual		Qual		Qual		Qual
Semivolatile Organic Compounds											
Acetophenone	NS	NS	ppm	ND		ND		ND		ND	
Anthracene	100	100	ppm	0.196	D	ND		ND		ND	
Atrazine	NS	NS	ppm	ND		ND		ND		ND	
Benzaldehyde	NS	NS	ppm	ND		ND		ND		ND	
Benzo(a)anthracene	1	1.4	ppm	**1.26**	**D**	0.0498	JD	ND		ND	
Benzo(a)pyrene	1	1	ppm	**1.28**	**D**	ND		ND		ND	
Benzo(b)fluoranthene	1	1.4	ppm	**1.12**	**D**	ND		ND		ND	
Benzo(g,h,i)perylene	0.64	4.9	ppm	**0.658**	**D**	ND		ND		ND	
Benzo(k)fluoranthene	0.8	4.9	ppm	**1.13**	**D**	ND		ND		ND	
Benzyl butyl phthalate	NS	NS	ppm	ND		ND		ND		ND	
Bis(2-chloroethoxy)methane	NS	NS	ppm	ND		ND		ND		ND	
Bis(2-chloroethyl)ether	NS	NS	ppm	ND		ND		ND		ND	
Bis(2-chloroisopropyl)ether	NS	NS	ppm	ND		ND		ND		ND	
Bis(2-ethylhexyl)phthalate	NS	NS	ppm	ND		ND		ND		ND	
Caprolactam	NS	NS	ppm	ND		ND		ND		ND	
Carbazole	NS	NS	ppm	ND		ND		ND		ND	
Chrysene	1	4.9	ppm	**1.25**	**D**	ND		ND		ND	
Dibenzo(a,h)anthracene	0.33	0.33	ppm	0.322	D	ND		ND		ND	
Dibenzofuran	2.1	18	ppm	ND		ND		ND		ND	
Diethyl phthalate	NS	NS	ppm	ND		ND		ND		ND	
Dimethyl phthalate	NS	NS	ppm	ND		ND		ND		ND	
Di-n-butyl phthalate	NS	NS	ppm	ND		ND		ND		ND	
Di-n-octyl phthalate	NS	NS	ppm	ND		ND		ND		ND	
Fluoranthene	85	100	ppm	2.46	D	0.0747	JD	ND		ND	
Fluorene	30	100	ppm	ND		ND		ND		ND	
Hexachlorobenzene	0.33	0.33	ppm	ND		ND		ND		ND	
Hexachlorobutadiene	NS	NS	ppm	ND		ND		ND		ND	
Hexachlorocyclopentadiene	NS	NS	ppm	ND		ND		ND		ND	

Table 4b. Semivolatile Organic Compounds in Soil
260 West 126th Street - New York, NY
BCP Site No. C231164

CLIENT SAMPLE ID	NY-UUSCO	NY-RESRR	Units	SB-1 (0-2)		SB-1 (6-8)		SB-1 (21-23)		SB-7 (0-2)	
SAMPLING DATE				1/6/2026		1/6/2026		1/6/2026		6/26/2026	
SAMPLE DEPTH (FT-BG)				0-2		6-8		21-23		0-2	
LAB SAMPLE ID				26A0111-10		26A0111-11		26A0111-12		26F1687-01	
					Qual		Qual		Qual		Qual
Semivolatile Organic Compounds											
Hexachloroethane	NS	NS	ppm	ND		ND		ND		ND	
Indeno(1,2,3-cd)pyrene	0.5	1.4	ppm	**0.792**	**D**	ND		ND		ND	
Isophorone	NS	NS	ppm	ND		ND		ND		ND	
Naphthalene	12	100	ppm	ND		ND		ND		ND	
Nitrobenzene	0.08	1.8	ppm	ND		ND		ND		ND	
N-nitroso-di-n-propylamine	NS	NS	ppm	ND		ND		ND		ND	
N-Nitrosodiphenylamine	NS	NS	ppm	ND		ND		ND		ND	
Pentachlorophenol	0.8	1.3	ppm	ND		ND		ND		ND	
Phenanthrene	1.1	4.9	ppm	0.503	D	ND		ND		ND	
Phenol	0.33	100	ppm	ND		ND		ND		ND	
Pyrene	64	100	ppm	2.41	D	0.074	JD	ND		ND	

Notes:

Bold and shaded yellow value indicates concentration exceeds NY-UNRES SCOs

Bold and shaded orange value indicates concentration exceeds NY-UNRES and NY-RESRR SCOs

NY-UNRES = 6 NYCRR Part 375 Unrestricted Use Soil Cleanup Objectives

NY-RESRR = 6 NYCRR Part 375 Restricted-Residential Use Soil Cleanup Objectives

J = Estimated value

D = Diluted

ND = Not detected

NS = No standard

ppm = parts per million

Table 4b. Semivolatile Organic Compounds in Soil
260 West 126th Street - New York, NY
BCP Site No. C231164

CLIENT SAMPLE ID	NY-UUSCO	NY-RESRR	Units	SB-7 (10-12)	SB-7 (12-14)	SB-4 (0-2)	SB-4 (12-14)
SAMPLING DATE				6/26/2026	6/26/2026	6/26/2026	6/26/2026
SAMPLE DEPTH (FT-BG)				10-12	12-14	0-2	12-14
LAB SAMPLE ID				26F1687-02	26F1687-03	26F1687-04	26F1687-05
				Qual	Qual	Qual	Qual
Semivolatile Organic Compounds							
1,1-Biphenyl	NS	NS	ppm	ND	ND	ND	ND
1,2,4,5-Tetrachlorobenzene	NS	NS	ppm	ND	ND	ND	ND
2,3,4,6-Tetrachlorophenol	NS	NS	ppm	ND	ND	ND	ND
2,4,5-Trichlorophenol	NS	NS	ppm	ND	ND	ND	ND
2,4,6-Trichlorophenol	NS	NS	ppm	ND	ND	ND	ND
2,4-Dichlorophenol	NS	NS	ppm	ND	ND	ND	ND
2,4-Dimethylphenol	NS	NS	ppm	ND	ND	ND	ND
2,4-Dinitrophenol	NS	NS	ppm	ND	ND	ND	ND
2,4-Dinitrotoluene	NS	NS	ppm	ND	ND	ND	ND
2,6-Dinitrotoluene	NS	NS	ppm	ND	ND	ND	ND
2-Chloronaphthalene	NS	NS	ppm	ND	ND	ND	ND
2-Chlorophenol	NS	NS	ppm	ND	ND	ND	ND
2-Methylnaphthalene	NS	NS	ppm	ND	ND	ND	ND
2-Methylphenol	0.33	100	ppm	ND	ND	ND	ND
2-Nitroaniline	NS	NS	ppm	ND	ND	ND	ND
2-Nitrophenol	NS	NS	ppm	ND	ND	ND	ND
3- & 4-Methylphenols	0.33	100	ppm	ND	ND	ND	ND
3,3-Dichlorobenzidine	NS	NS	ppm	ND	ND	ND	ND
3-Nitroaniline	NS	NS	ppm	ND	ND	ND	ND
4,6-Dinitro-2-methylphenol	NS	NS	ppm	ND	ND	ND	ND
4-Bromophenyl phenyl ether	NS	NS	ppm	ND	ND	ND	ND
4-Chloro-3-methylphenol	NS	NS	ppm	ND	ND	ND	ND
4-Chloroaniline	NS	NS	ppm	ND	ND	ND	ND
4-Chlorophenyl phenyl ether	NS	NS	ppm	ND	ND	ND	ND
4-Nitroaniline	NS	NS	ppm	ND	ND	ND	ND
4-Nitrophenol	NS	NS	ppm	ND	ND	ND	ND
Acenaphthene	20	100	ppm	ND	ND	ND	0.0707
Acenaphthylene	100	100	ppm	ND	ND	ND	0.105

Table 4b. Semivolatile Organic Compounds in Soil
260 West 126th Street - New York, NY
BCP Site No. C231164

CLIENT SAMPLE ID	NY-UUSCO	NY-RESRR	Units	SB-7 (10-12)	SB-7 (12-14)	SB-4 (0-2)	SB-4 (12-14)
SAMPLING DATE				6/26/2026	6/26/2026	6/26/2026	6/26/2026
SAMPLE DEPTH (FT-BG)				10-12	12-14	0-2	12-14
LAB SAMPLE ID				26F1687-02	26F1687-03	26F1687-04	26F1687-05
				Qual	Qual	Qual	Qual
Semivolatile Organic Compounds							
Acetophenone	NS	NS	ppm	ND	ND	ND	ND
Anthracene	100	100	ppm	ND	ND	ND	0.219
Atrazine	NS	NS	ppm	ND	ND	ND	ND
Benzaldehyde	NS	NS	ppm	ND	ND	ND	ND
Benzo(a)anthracene	1	1.4	ppm	ND	ND	ND	0.432
Benzo(a)pyrene	1	1	ppm	ND	ND	ND	0.45
Benzo(b)fluoranthene	1	1.4	ppm	ND	ND	ND	0.429
Benzo(g,h,i)perylene	0.64	4.9	ppm	ND	ND	ND	0.219
Benzo(k)fluoranthene	0.8	4.9	ppm	ND	ND	ND	0.358
Benzyl butyl phthalate	NS	NS	ppm	ND	ND	ND	ND
Bis(2-chloroethoxy)methane	NS	NS	ppm	ND	ND	ND	ND
Bis(2-chloroethyl)ether	NS	NS	ppm	ND	ND	ND	ND
Bis(2-chloroisopropyl)ether	NS	NS	ppm	ND	ND	ND	ND
Bis(2-ethylhexyl)phthalate	NS	NS	ppm	ND	ND	ND	4.09 D
Caprolactam	NS	NS	ppm	ND	ND	ND	ND
Carbazole	NS	NS	ppm	ND	ND	ND	0.0998
Chrysene	1	4.9	ppm	ND	ND	ND	0.427
Dibenzo(a,h)anthracene	0.33	0.33	ppm	ND	ND	ND	ND
Dibenzofuran	2.1	18	ppm	ND	ND	ND	0.0648
Diethyl phthalate	NS	NS	ppm	ND	ND	ND	ND
Dimethyl phthalate	NS	NS	ppm	ND	ND	ND	ND
Di-n-butyl phthalate	NS	NS	ppm	ND	ND	ND	ND
Di-n-octyl phthalate	NS	NS	ppm	ND	ND	ND	ND
Fluoranthene	85	100	ppm	ND	ND	ND	1.26
Fluorene	30	100	ppm	ND	ND	ND	0.0701
Hexachlorobenzene	0.33	0.33	ppm	ND	ND	ND	ND
Hexachlorobutadiene	NS	NS	ppm	ND	ND	ND	ND
Hexachlorocyclopentadiene	NS	NS	ppm	ND	ND	ND	ND

Table 4b. Semivolatile Organic Compounds in Soil
260 West 126th Street - New York, NY
BCP Site No. C231164

CLIENT SAMPLE ID	NY-UUSCO	NY-RESRR	Units	SB-7 (10-12)	SB-7 (12-14)	SB-4 (0-2)	SB-4 (12-14)
SAMPLING DATE				6/26/2026	6/26/2026	6/26/2026	6/26/2026
SAMPLE DEPTH (FT-BG)				10-12	12-14	0-2	12-14
LAB SAMPLE ID				26F1687-02	26F1687-03	26F1687-04	26F1687-05
				Qual	Qual	Qual	Qual
Semivolatile Organic Compounds							
Hexachloroethane	NS	NS	ppm	ND	ND	ND	ND
Indeno(1,2,3-cd)pyrene	0.5	1.4	ppm	ND	ND	ND	0.267
Isophorone	NS	NS	ppm	ND	ND	ND	ND
Naphthalene	12	100	ppm	ND	ND	ND	0.042
Nitrobenzene	0.08	1.8	ppm	ND	ND	ND	ND
N-nitroso-di-n-propylamine	NS	NS	ppm	ND	ND	ND	ND
N-Nitrosodiphenylamine	NS	NS	ppm	ND	ND	ND	ND
Pentachlorophenol	0.8	1.3	ppm	ND	ND	ND	ND
Phenanthrene	1.1	4.9	ppm	ND	ND	ND	1.05
Phenol	0.33	100	ppm	ND	ND	ND	ND
Pyrene	64	100	ppm	ND	ND	ND	0.96

Notes:

Bold and shaded yellow value indicates concentration exceeds NY-UNRES SCOs

Bold and shaded orange value indicates concentration exceeds NY-UNRES and NY-RESRR SCOs

NY-UNRES = 6 NYCRR Part 375 Unrestricted Use Soil Cleanup Objectives

NY-RESRR = 6 NYCRR Part 375 Restricted-Residential Use Soil Cleanup Objectives

J = Estimated value

D = Diluted

ND = Not detected

NS = No standard

ppm = parts per million

Table 4b. Semivolatile Organic Compounds in Soil
260 West 126th Street - New York, NY
BCP Site No. C231164

CLIENT SAMPLE ID	NY-UUSCO	NY-RESRR	Units	SB-4 (14-15)
SAMPLING DATE				6/26/2026
SAMPLE DEPTH (FT-BG)				14-15
LAB SAMPLE ID				26F1687-06
				Qual
Semivolatile Organic Compounds				
1,1-Biphenyl	NS	NS	ppm	ND
1,2,4,5-Tetrachlorobenzene	NS	NS	ppm	ND
2,3,4,6-Tetrachlorophenol	NS	NS	ppm	ND
2,4,5-Trichlorophenol	NS	NS	ppm	ND
2,4,6-Trichlorophenol	NS	NS	ppm	ND
2,4-Dichlorophenol	NS	NS	ppm	ND
2,4-Dimethylphenol	NS	NS	ppm	ND
2,4-Dinitrophenol	NS	NS	ppm	ND
2,4-Dinitrotoluene	NS	NS	ppm	ND
2,6-Dinitrotoluene	NS	NS	ppm	ND
2-Chloronaphthalene	NS	NS	ppm	ND
2-Chlorophenol	NS	NS	ppm	ND
2-Methylnaphthalene	NS	NS	ppm	ND
2-Methylphenol	0.33	100	ppm	ND
2-Nitroaniline	NS	NS	ppm	ND
2-Nitrophenol	NS	NS	ppm	ND
3- & 4-Methylphenols	0.33	100	ppm	ND
3,3-Dichlorobenzidine	NS	NS	ppm	ND
3-Nitroaniline	NS	NS	ppm	ND
4,6-Dinitro-2-methylphenol	NS	NS	ppm	ND
4-Bromophenyl phenyl ether	NS	NS	ppm	ND
4-Chloro-3-methylphenol	NS	NS	ppm	ND
4-Chloroaniline	NS	NS	ppm	ND
4-Chlorophenyl phenyl ether	NS	NS	ppm	ND
4-Nitroaniline	NS	NS	ppm	ND
4-Nitrophenol	NS	NS	ppm	ND
Acenaphthene	20	100	ppm	ND
Acenaphthylene	100	100	ppm	ND

Table 4b. Semivolatile Organic Compounds in Soil
260 West 126th Street - New York, NY
BCP Site No. C231164

CLIENT SAMPLE ID	NY-UUSCO	NY-RESRR	Units	SB-4 (14-15)
SAMPLING DATE				6/26/2026
SAMPLE DEPTH (FT-BG)				14-15
LAB SAMPLE ID				26F1687-06
				Qual
Semivolatile Organic Compounds				
Acetophenone	NS	NS	ppm	ND
Anthracene	100	100	ppm	ND
Atrazine	NS	NS	ppm	ND
Benzaldehyde	NS	NS	ppm	ND
Benzo(a)anthracene	1	1.4	ppm	ND
Benzo(a)pyrene	1	1	ppm	ND
Benzo(b)fluoranthene	1	1.4	ppm	ND
Benzo(g,h,i)perylene	0.64	4.9	ppm	ND
Benzo(k)fluoranthene	0.8	4.9	ppm	ND
Benzyl butyl phthalate	NS	NS	ppm	ND
Bis(2-chloroethoxy)methane	NS	NS	ppm	ND
Bis(2-chloroethyl)ether	NS	NS	ppm	ND
Bis(2-chloroisopropyl)ether	NS	NS	ppm	ND
Bis(2-ethylhexyl)phthalate	NS	NS	ppm	ND
Caprolactam	NS	NS	ppm	ND
Carbazole	NS	NS	ppm	ND
Chrysene	1	4.9	ppm	ND
Dibenzo(a,h)anthracene	0.33	0.33	ppm	ND
Dibenzofuran	2.1	18	ppm	ND
Diethyl phthalate	NS	NS	ppm	ND
Dimethyl phthalate	NS	NS	ppm	ND
Di-n-butyl phthalate	NS	NS	ppm	ND
Di-n-octyl phthalate	NS	NS	ppm	ND
Fluoranthene	85	100	ppm	ND
Fluorene	30	100	ppm	ND
Hexachlorobenzene	0.33	0.33	ppm	ND
Hexachlorobutadiene	NS	NS	ppm	ND
Hexachlorocyclopentadiene	NS	NS	ppm	ND

Table 4b. Semivolatile Organic Compounds in Soil
260 West 126th Street - New York, NY
BCP Site No. C231164

CLIENT SAMPLE ID	NY-UUSCO	NY-RESRR	Units	SB-4 (14-15)
SAMPLING DATE				6/26/2026
SAMPLE DEPTH (FT-BG)				14-15
LAB SAMPLE ID				26F1687-06
				Qual
Semivolatile Organic Compounds				
Hexachloroethane	NS	NS	ppm	ND
Indeno(1,2,3-cd)pyrene	0.5	1.4	ppm	ND
Isophorone	NS	NS	ppm	ND
Naphthalene	12	100	ppm	ND
Nitrobenzene	0.08	1.8	ppm	ND
N-nitroso-di-n-propylamine	NS	NS	ppm	ND
N-Nitrosodiphenylamine	NS	NS	ppm	ND
Pentachlorophenol	0.8	1.3	ppm	ND
Phenanthrene	1.1	4.9	ppm	ND
Phenol	0.33	100	ppm	ND
Pyrene	64	100	ppm	ND

Notes:

Bold and shaded yellow value indicates concentration exceeds NY-UNRES SCOs

Bold and shaded orange value indicates concentration exceeds NY-UNRES and NY-RESRR SCOs

NY-UNRES = 6 NYCRR Part 375 Unrestricted Use Soil Cleanup Objectives

NY-RESRR = 6 NYCRR Part 375 Restricted-Residential Use Soil Cleanup Objectives

J = Estimated value

D = Diluted

ND = Not detected

NS = No standard

ppm = parts per million

Table 4c. Metals in Soil
260 West 126th Street - New York, NY
BCP Site No. C231164

CLIENT SAMPLE ID	NY-UUSCO	NY-PGW	NY-RESRR	Units	SB-5 (0-2)	SB-5 (12.5-14.5)	SB-5 (22-24)	SB-5 (22-24)_DUP	SB-3 (0-2)	SB-3 (8-10)	SB-3 (22-24)
SAMPLING DATE					1/5/2026	1/5/2026	1/5/2026	1/5/2026	1/5/2026	1/5/2026	1/5/2026
SAMPLE DEPTH (FT-BG)					0-2	12.5-14.5	22-24	22-24	0-2	8-10	22-24
LAB SAMPLE ID					26A0061-01	26A0061-02	26A0061-03	26A0061-04	26A0061-05	26A0061-06	26A0061-07
					Qual	Qual	Qual	Qual	Qual	Qual	Qual
Total Metals											
Aluminum	NS	NS	NS	ppm	7260	3410	7710	3670	9860	10600	9640
Antimony	NS	NS	NS	ppm	ND	ND	ND	ND	ND	ND	ND
Arsenic	13	16	16	ppm	8.29	ND	ND	ND	4.06	1.88	2.11
Barium	410	820	410	ppm	**458**	30	27.5	31.6	270	81.6	48
Beryllium	4.4	47	43	ppm	0.346	0.137	0.24	0.22	0.371	0.537	0.463
Cadmium	2.5	7.5	2.5	ppm	1.08	ND	ND	ND	ND	ND	ND
Calcium	NS	NS	NS	ppm	45000	1100	4070	1170	9700	3270	4760
Chromium	NS	NS	NS	ppm	23.4	8.22	13.8	9.85	18.7	29.7	17.3
Cobalt	NS	NS	NS	ppm	9.22	2.69	4.83	2.81	7.33	12	6.02
Copper	50	1,720	280	ppm	**128**	8.39	16.5	8.61	22.6	39.7	29.3
Iron	NS	NS	NS	ppm	31300	4630	6310	5380	11800	13400	10800
Lead	63	450	400	ppm	**424**	2.35	1.87	3.12	46.3	4.84	4.72
Magnesium	NS	NS	NS	ppm	13300	1370	2820	1710	4310	6600	3720
Manganese	1,600	2,000	2,000	ppm	312	136	414	343	285	761	510
Mercury	0.18	0.73	0.3	ppm	0.135	ND	ND	ND	0.132	ND	ND
Nickel	30	130	320	ppm	18.8	5.4	10.8	8.44	21.4	**41.2**	16.3
Potassium	NS	NS	NS	ppm	1670	813	1100	997	1150	1320	1160
Selenium	3.9	4	110	ppm	ND	ND	ND	ND	ND	ND	ND
Silver	2	8.3	110	ppm	ND	ND	ND	ND	ND	ND	ND
Sodium	NS	NS	NS	ppm	730	132	743	197	401	516	859
Thallium	NS	NS	NS	ppm	ND	ND	ND	ND	ND	ND	ND
Vanadium	NS	NS	NS	ppm	37.8	7.77	13.5	7.83	20.5	20.6	21.8
Zinc	109	2480	6600	ppm	**440**	8.62	16.9	12	**158**	24.5	23.1
Cyanide, total	2.3	40	13	ppm	ND	ND	ND	ND	ND	ND	ND
Chromium											
Chromium, Hexavalent	1	19	1	ppm	**1.18**	ND	ND	ND	ND	ND	ND
Chromium, Trivalent	30	NS	110	ppm	22.2	8.22	13.8	9.85	18.7	29.7	17.3

Notes:

Bold and shaded yellow value indicates concentration exceeds NY-UNRES SCOs

Bold and shaded orange value indicates concentration exceeds NY-UNRES and NY-RESRR SCOs

Bold and shaded red value indicates concentration exceeds NY-UNRES, NY-PGW, and NY-RESRR SCOs

NY-UNRES = 6 NYCRR Part 375 Unrestricted Use Soil Cleanup Objectives

NY-PGW = 6 NYCRR Part 375 Protection of Groundwater Soil Cleanup Objectives

NY-RESRR = 6 NYCRR Part 375 Restricted-Residential Use Soil Cleanup Objectives

ND = Not detected

NS = No standard

B = Analyte detected in associated blank sample

ppm = parts per million

Only manganese and sodium are compared to the NY-RESGW SCOs

Table 4c. Metals in Soil
260 West 126th Street - New York, NY
BCP Site No. C231164

CLIENT SAMPLE ID	NY-UUSCO	NY-PGW	NY-RESRR	Units	SB-6 (0-2)	SB-6 (8-10)	SB-6 (22-24)	SB-8 (0-2)	SB-8 (8-10)	SB-8 (22-24)	SB-2 (0-2)
SAMPLING DATE					1/5/2026	1/5/2026	1/5/2026	1/5/2026	1/6/2026	1/6/2026	1/6/2026
SAMPLE DEPTH (FT-BG)					0-2	8-10	22-24	0-2	8-10	22-24	0-2
LAB SAMPLE ID					26A0061-08	26A0061-09	26A0061-10	26A0061-11	26A0111-02	26A0111-03	26A0111-04
					Qual	Qual	Qual	Qual	Qual	Qual	Qual
Total Metals											
Aluminum	NS	NS	NS	ppm	10000	11400	8750	12000	15100	1970	6560
Antimony	NS	NS	NS	ppm	ND	ND	ND	ND	ND	ND	ND
Arsenic	13	16	16	ppm	5.93	1.58	3.2	**15.8**	2.81	ND	6.04
Barium	410	820	410	ppm	**1590**	38.7	65.7	**2430**	79.6	50.9	**2370**
Beryllium	4.4	47	43	ppm	0.397	0.268	0.473	0.672	0.602	0.146	0.349
Cadmium	2.5	7.5	2.5	ppm	0.515	ND	ND	2.18	ND	ND	1.28
Calcium	NS	NS	NS	ppm	22100	4690	3980	7710	8310	2130	74500
Chromium	NS	NS	NS	ppm	18.9	21.1	57.2	29.1	31	0.918	13.3
Cobalt	NS	NS	NS	ppm	4.84	10.3	7.94	9.02	12.5	2.99	4.19
Copper	50	1,720	280	ppm	21.9	36.5	38.4	**129**	**79.2**	ND	27.8
Iron	NS	NS	NS	ppm	12800	11100	16700	17900	20500	747	9530
Lead	63	450	400	ppm	**841**	**67.1**	29.1	**1230**	6.57	3.45	**4430**
Magnesium	NS	NS	NS	ppm	2780	6300	4710	2870	6910	689	4210
Manganese	1,600	2,000	2,000	ppm	264	125	219	482	585	**2410**	376
Mercury	0.18	0.73	0.3	ppm	**0.66**	**0.713**	0.151	**2.52**	ND	ND	**0.53**
Nickel	30	130	320	ppm	11.2	19.4	21.5	23.3	**36.5**	2.72	13.6
Potassium	NS	NS	NS	ppm	810	1780	1850	1240	1610 B	1260 B	828 B
Selenium	3.9	4	110	ppm	ND	ND	ND	ND	ND	ND	ND
Silver	2	8.3	110	ppm	ND	ND	ND	0.701	ND	ND	ND
Sodium	NS	NS	NS	ppm	136	1030	474	331	1180	137	199
Thallium	NS	NS	NS	ppm	ND	ND	ND	ND	ND	ND	ND
Vanadium	NS	NS	NS	ppm	23.7	26.6	29.6	32.7	35.1	8.32	37.6
Zinc	109	2480	6600	ppm	**550**	17.9	34.7	**877**	31.9	5.01	**848**
Cyanide, total	2.3	40	13	ppm	ND	ND	ND	ND	ND	ND	ND
Chromium											
Chromium, Hexavalent	1	19	1	ppm	ND	ND	**2.01**	ND	0.581	ND	ND
Chromium, Trivalent	30	NS	110	ppm	18.9	21.1	**55.2**	29.1	**30.4**	0.505	13.3

Notes:

Bold and shaded yellow value indicates concentration exceeds NY-UNRES SCOs

Bold and shaded orange value indicates concentration exceeds NY-UNRES and NY-RESRR SCOs

Bold and shaded red value indicates concentration exceeds NY-UNRES, NY-PGW, and NY-RESRR SCOs

NY-UNRES = 6 NYCRR Part 375 Unrestricted Use Soil Cleanup Objectives

NY-PGW = 6 NYCRR Part 375 Protection of Groundwater Soil Cleanup Objectives

NY-RESRR = 6 NYCRR Part 375 Restricted-Residential Use Soil Cleanup Objectives

ND = Not detected

NS = No standard

B = Analyte detected in associated blank sample

ppm = parts per million

Only manganese and sodium are compared to the NY-RESGW SCOs

Table 4c. Metals in Soil
260 West 126th Street - New York, NY
BCP Site No. C231164

CLIENT SAMPLE ID	NY-UUSCO	NY-PGW	NY-RESRR	Units	SB-2 (0-2)_DUP		SB-2 (6-8)		SB-2 (22-24)		SB-9 (0-2)		SB-9 (6-8)		SB-9 (22-24)		SB-1 (0-2)	
SAMPLING DATE					1/6/2026		1/6/2026		1/6/2026		1/6/2026		1/6/2026		1/6/2026		1/6/2026	
SAMPLE DEPTH (FT-BG)					21-23		6-8		22-24		0-2		6-8		22-24		0-2	
LAB SAMPLE ID					26A0111-13		26A0111-05		26A0111-06		26A0111-07		26A0111-08		26A0111-09		26A0111-10	
						Qual		Qual		Qual		Qual		Qual		Qual		Qual
Total Metals																		
Aluminum	NS	NS	NS	ppm	7170		6500		10600		8680		15900		6600		7300	
Antimony	NS	NS	NS	ppm	ND		ND		ND		ND		ND		ND		ND	
Arsenic	13	16	16	ppm	3.41		1.75		2.38		9.19		2.06		2.64		4.55	
Barium	410	820	410	ppm	**494**		53.6		88.1		**3160**		168		82.3		**798**	
Beryllium	4.4	47	43	ppm	0.329		0.484		0.433		0.389		1.01		0.398		0.399	
Cadmium	2.5	7.5	2.5	ppm	ND		ND		ND		1.06		ND		ND		0.463	
Calcium	NS	NS	NS	ppm	64900		1760		5630		69800		5160		4920		65300	
Chromium	NS	NS	NS	ppm	11.5		15.2		17.7		16.7		13.4		5.02		17.2	
Cobalt	NS	NS	NS	ppm	4.84		4.96		7.06		5.66		8.16		9.65		5.06	
Copper	50	1,720	280	ppm	31.4		25.4		**62.8**		18.4		**72**		**103**		38.4	
Iron	NS	NS	NS	ppm	12500		10500		15900		12400		24800		22200		12300	
Lead	63	450	400	ppm	**160**		5.16		7.5		**3160**		1.36		3.77		**908**	
Magnesium	NS	NS	NS	ppm	4530		2390		3540		4050		6050		5630		25700	
Manganese	1,600	2,000	2,000	ppm	197		256		294		273		495		344		275	
Mercury	0.18	0.73	0.3	ppm	ND		0.0732		ND		**1.25**		0.0617		ND		**0.201**	
Nickel	30	130	320	ppm	10.7		11.7		14.3		14.7		19.1		9.48		13.6	
Potassium	NS	NS	NS	ppm	943	B	1510	B	2100	B	1100	B	5750	B	1700	B	964	B
Selenium	3.9	4	110	ppm	ND		ND		ND		ND		ND		ND		ND	
Silver	2	8.3	110	ppm	ND		ND		ND		ND		ND		ND		ND	
Sodium	NS	NS	NS	ppm	318		211		906		350		306		367		396	
Thallium	NS	NS	NS	ppm	ND		ND		ND		ND		ND		ND		ND	
Vanadium	NS	NS	NS	ppm	28		18.5		23.2		23.3		24.1		24.5		29.4	
Zinc	109	2480	6600	ppm	**223**		13.5		25.2		**1730**		59.2		32.9		**368**	
Cyanide, total	2.3	40	13	ppm	ND		ND		ND		ND		ND		ND		ND	
Chromium																		
Chromium, Hexavalent	1	19	1	ppm	**1.22**		0.739		**1.06**		**5.08**		0.574		0.647		**1.26**	
Chromium, Trivalent	30	NS	110	ppm	10.3		14.5		16.6		11.6		12.8		4.37		15.9	

Notes:

Bold and shaded yellow value indicates concentration exceeds NY-UNRES SCOs

Bold and shaded orange value indicates concentration exceeds NY-UNRES and NY-RESRR SCOs

Bold and shaded red value indicates concentration exceeds NY-UNRES, NY-PGW, and NY-RESRR SCOs

NY-UNRES = 6 NYCRR Part 375 Unrestricted Use Soil Cleanup Objectives

NY-PGW = 6 NYCRR Part 375 Protection of Groundwater Soil Cleanup Objectives

NY-RESRR = 6 NYCRR Part 375 Restricted-Residential Use Soil Cleanup Objectives

ND = Not detected

NS = No standard

B = Analyte detected in associated blank sample

ppm = parts per million

Only manganese and sodium are compared to the NY-RESGW SCOs

Table 4c. Metals in Soil
260 West 126th Street - New York, NY
BCP Site No. C231164

CLIENT SAMPLE ID	NY-UUSCO	NY-PGW	NY-RESRR	Units	SB-1 (6-8)		SB-1 (21-23)		SB-7 (0-2)	SB-7 (10-12)	SB-7 (12-14)	SB-4 (0-2)	SB-4 (12-14)
SAMPLING DATE					1/6/2026		1/6/2026		6/26/2026	6/26/2026	6/26/2026	6/26/2026	6/26/2026
SAMPLE DEPTH (FT-BG)					6-8		21-23		0-2	10-12	12-14	0-2	12-14
LAB SAMPLE ID					26A0111-11		26A0111-12		26F1687-01	26F1687-02	26F1687-03	26F1687-04	26F1687-05
						Qual		Qual	Qual	Qual	Qual	Qual	Qual
Total Metals													
Aluminum	NS	NS	NS	ppm	5420		3140		7900	3010	2870	3870	5670
Antimony	NS	NS	NS	ppm	ND		ND		ND	ND	ND	ND	ND
Arsenic	13	16	16	ppm	ND		ND		4.13	ND	ND	ND	2.06
Barium	410	820	410	ppm	31.2		16.4		70.8	24.9	16.4	35.8	107
Beryllium	4.4	47	43	ppm	0.347		0.221		0.454	0.135	0.144	0.158	0.134
Cadmium	2.5	7.5	2.5	ppm	ND		ND		ND	ND	ND	ND	ND
Calcium	NS	NS	NS	ppm	1440		1010		3990	1600	829	1200	20600
Chromium	NS	NS	NS	ppm	8.16		5.9		11.7	7.01	8.05	7.99	15.7
Cobalt	NS	NS	NS	ppm	3.85		2.1		9.87	2.88	2.51	3.35	4.28
Copper	50	1,720	280	ppm	16		7.73		9.36	7.79	7.6	13.9	32
Iron	NS	NS	NS	ppm	7510		4760		21400	6040	5020	6660	12400
Lead	63	450	400	ppm	2.46		1.72		38.8	2.11	2.59	3.41	**129**
Magnesium	NS	NS	NS	ppm	1940		1460		6220	1660	1210	1570	3280
Manganese	1,600	2,000	2,000	ppm	260		210		**2160**	243	203	278	275
Mercury	0.18	0.73	0.3	ppm	ND		ND		ND	ND	ND	ND	**0.406**
Nickel	30	130	320	ppm	11		5.25		7.79	8.36	5.99	7.8	11.3
Potassium	NS	NS	NS	ppm	871	B	644	B	789	781	567	924	1140
Selenium	3.9	4	110	ppm	ND		ND		ND	ND	ND	ND	ND
Silver	2	8.3	110	ppm	ND		ND		ND	ND	ND	ND	ND
Sodium	NS	NS	NS	ppm	234		130		123	69.5	71.9	113	406
Thallium	NS	NS	NS	ppm	ND		ND		ND	ND	ND	ND	ND
Vanadium	NS	NS	NS	ppm	9.75		5.7		35.1	16.5	9.61	11.4	21.2
Zinc	109	2480	6600	ppm	12.4		10.7		**110**	8.5	7.51	10.9	63
Cyanide, total	2.3	40	13	ppm	ND		ND		ND	ND	ND	ND	ND
Chromium													
Chromium, Hexavalent	1	19	1	ppm	ND		ND		ND	ND	ND	ND	ND
Chromium, Trivalent	30	NS	110	ppm	7.75		5.9		11.7	7.01	8.05	7.99	15.5

Notes:

Bold and shaded yellow value indicates concentration exceeds NY-UNRES SCOs

Bold and shaded orange value indicates concentration exceeds NY-UNRES and NY-RESRR SCOs

Bold and shaded red value indicates concentration exceeds NY-UNRES, NY-PGW, and NY-RESRR SCOs

NY-UNRES = 6 NYCRR Part 375 Unrestricted Use Soil Cleanup Objectives

NY-PGW = 6 NYCRR Part 375 Protection of Groundwater Soil Cleanup Objectives

NY-RESRR = 6 NYCRR Part 375 Restricted-Residential Use Soil Cleanup Objectives

ND = Not detected

NS = No standard

B = Analyte detected in associated blank sample

ppm = parts per million

Only manganese and sodium are compared to the NY-RESGW SCOs

Table 4c. Metals in Soil
260 West 126th Street - New York, NY
BCP Site No. C231164

CLIENT SAMPLE ID	NY-UUSCO	NY-PGW	NY-RESRR	Units	SB-4 (14-15)
SAMPLING DATE					6/26/2026
SAMPLE DEPTH (FT-BG)					14-15
LAB SAMPLE ID					26F1687-06
					Qual
Total Metals					
Aluminum	NS	NS	NS	ppm	3730
Antimony	NS	NS	NS	ppm	ND
Arsenic	13	16	16	ppm	ND
Barium	410	820	410	ppm	23.9
Beryllium	4.4	47	43	ppm	0.123
Cadmium	2.5	7.5	2.5	ppm	ND
Calcium	NS	NS	NS	ppm	1500
Chromium	NS	NS	NS	ppm	7.87
Cobalt	NS	NS	NS	ppm	3.52
Copper	50	1,720	280	ppm	11.5
Iron	NS	NS	NS	ppm	6180
Lead	63	450	400	ppm	2.87
Magnesium	NS	NS	NS	ppm	2240
Manganese	1,600	2,000	2,000	ppm	216
Mercury	0.18	0.73	0.3	ppm	ND
Nickel	30	130	320	ppm	9.78
Potassium	NS	NS	NS	ppm	790
Selenium	3.9	4	110	ppm	ND
Silver	2	8.3	110	ppm	ND
Sodium	NS	NS	NS	ppm	170
Thallium	NS	NS	NS	ppm	ND
Vanadium	NS	NS	NS	ppm	10.2
Zinc	109	2480	6600	ppm	9.42
Cyanide, total	2.3	40	13	ppm	ND
Chromium					
Chromium, Hexavalent	1	19	1	ppm	ND
Chromium, Trivalent	30	NS	110	ppm	7.87

Notes:

Bold and shaded yellow value indicates concentration exceeds NY-UNRES SCOs

Bold and shaded orange value indicates concentration exceeds NY-UNRES and NY-RESRR SCOs

Bold and shaded red value indicates concentration exceeds NY-UNRES, NY-PGW, and NY-RESRR SCOs

NY-UNRES = 6 NYCRR Part 375 Unrestricted Use Soil Cleanup Objectives

NY-PGW = 6 NYCRR Part 375 Protection of Groundwater Soil Cleanup Objectives

NY-RESRR = 6 NYCRR Part 375 Restricted-Residential Use Soil Cleanup Objectives

ND = Not detected

NS = No standard

B = Analyte detected in associated blank sample

ppm = parts per million

Only manganese and sodium are compared to the NY-RESGW SCOs

Table 4d. Pesticides, Herbicides, and Polychlorinated Biphenyls in Soil
260 West 126th Street - New York, NY
BCP Site No. C231164

CLIENT SAMPLE ID	NY-UUSCO	NY-RESRR	Units	SB-5 (0-2)	SB-5 (12.5-14.5)	SB-5 (22-24)	SB-5 (22-24)_DUP
SAMPLING DATE				1/5/2026	1/5/2026	1/5/2026	1/5/2026
SAMPLE DEPTH (FT-BG)				0-2	12.5-14.5	22-24	22-24
LAB SAMPLE ID				26A0061-01	26A0061-02	26A0061-03	26A0061-04
				Qual	Qual	Qual	Qual
Polychlorinated Biphenyls							
Aroclor 1016	NS	NS	ppm	ND	ND	ND	ND
Aroclor 1221	NS	NS	ppm	ND	ND	ND	ND
Aroclor 1232	NS	NS	ppm	ND	ND	ND	ND
Aroclor 1242	NS	NS	ppm	ND	ND	ND	ND
Aroclor 1248	NS	NS	ppm	ND	ND	ND	ND
Aroclor 1254	NS	NS	ppm	ND	ND	ND	ND
Aroclor 1260	NS	NS	ppm	ND	ND	ND	ND
Aroclor 1262	NS	NS	ppm	--	--	--	--
Aroclor 1268	NS	NS	ppm	--	--	--	--
Total PCBs	0.1	1	ppm	ND	ND	ND	ND
Pesticides							
4,4'-DDD	0.0033	5	ppm	ND	ND	ND	ND
4,4'-DDE	0.0033	3.4	ppm	ND	ND	ND	ND
4,4'-DDT	0.0033	3.8	ppm	ND	ND	ND	ND
Aldrin	0.0048	0.044	ppm	ND	ND	ND	ND
alpha-BHC	0.02	0.18	ppm	ND	ND	ND	ND
alpha-Chlordane	0.014	0.65	ppm	ND	ND	ND	ND
beta-BHC	0.021	0.18	ppm	ND	ND	ND	ND
Chlordane, total	NS	NS	ppm	ND	ND	ND	ND
delta-BHC	0.04	100	ppm	ND	ND	ND	ND
Dieldrin	0.005	0.075	ppm	ND	ND	ND	ND
Endosulfan I	4.3	35	ppm	ND	ND	ND	ND
Endosulfan II	4.3	35	ppm	ND	ND	ND	ND
Endosulfan sulfate	4.3	35	ppm	ND	ND	ND	ND
Endrin	0.014	5.3	ppm	ND	ND	ND	ND
Endrin aldehyde	NS	NS	ppm	ND	ND	ND	ND
Endrin ketone	NS	NS	ppm	ND	ND	ND	ND
gamma-BHC (Lindane)	0.025	0.21	ppm	ND	ND	ND	ND

Table 4d. Pesticides, Herbicides, and Polychlorinated Biphenyls in Soil
260 West 126th Street - New York, NY
BCP Site No. C231164

CLIENT SAMPLE ID	NY-UUSCO	NY-RESRR	Units	SB-5 (0-2)	SB-5 (12.5-14.5)	SB-5 (22-24)	SB-5 (22-24)_DUP
SAMPLING DATE				1/5/2026	1/5/2026	1/5/2026	1/5/2026
SAMPLE DEPTH (FT-BG)				0-2	12.5-14.5	22-24	22-24
LAB SAMPLE ID				26A0061-01	26A0061-02	26A0061-03	26A0061-04
				Qual	Qual	Qual	Qual
gamma-Chlordane	NS	NS	ppm	ND	ND	ND	ND
Heptachlor	0.013	0.53	ppm	ND	ND	ND	ND
Heptachlor epoxide	NS	NS	ppm	ND	ND	ND	ND
Methoxychlor	NS	NS	ppm	ND	ND	ND	ND
Toxaphene	NS	NS	ppm	ND	ND	ND	ND
Herbicides							
2,4,5-T	NS	NS	ppm	ND	ND	ND	ND
2,4,5-TP (Silvex)	NS	NS	ppm	ND	ND	ND	ND
2,4-D	NS	NS	ppm	ND	ND	ND	ND

Notes:

Bold and shaded yellow value indicates concentration exceeds NY-UNRES SCOs

Bold and shaded orange value indicates concentration exceeds NY-UNRES and NY-RESRR SCOs

NY-UNRES = 6 NYCRR Part 375 Unrestricted Use Soil Cleanup Objectives

NY-RESRR = 6 NYCRR Part 375 Restricted-Residential Use Soil Cleanup Objectives

D = Diluted

ND = Not detected

NS = No standard

-- = Not analyzed

P = The RPD between the results for the two columns exceeds the method-specified criteria.

ppm = parts per million

Table 4d. Pesticides, Herbicides, and Polychlorinated Biphenyls in Soil
260 West 126th Street - New York, NY
BCP Site No. C231164

CLIENT SAMPLE ID	NY-UUSCO	NY-RESRR	Units	SB-3 (0-2)	SB-3 (8-10)	SB-3 (22-24)	SB-6 (0-2)
SAMPLING DATE				1/5/2026	1/5/2026	1/5/2026	1/5/2026
SAMPLE DEPTH (FT-BG)				0-2	8-10	22-24	0-2
LAB SAMPLE ID				26A0061-05	26A0061-06	26A0061-07	26A0061-08
				Qual	Qual	Qual	Qual
Polychlorinated Biphenyls							
Aroclor 1016	NS	NS	ppm	ND	ND	ND	ND
Aroclor 1221	NS	NS	ppm	ND	ND	ND	ND
Aroclor 1232	NS	NS	ppm	ND	ND	ND	ND
Aroclor 1242	NS	NS	ppm	ND	ND	ND	ND
Aroclor 1248	NS	NS	ppm	ND	ND	ND	ND
Aroclor 1254	NS	NS	ppm	ND	ND	ND	ND
Aroclor 1260	NS	NS	ppm	ND	ND	ND	ND
Aroclor 1262	NS	NS	ppm	--	--	--	--
Aroclor 1268	NS	NS	ppm	--	--	--	--
Total PCBs	0.1	1	ppm	ND	ND	ND	ND
Pesticides							
4,4'-DDD	0.0033	5	ppm	ND	ND	ND	ND
4,4'-DDE	0.0033	3.4	ppm	ND	ND	ND	ND
4,4'-DDT	0.0033	3.8	ppm	ND	ND	ND	ND
Aldrin	0.0048	0.044	ppm	ND	ND	ND	ND
alpha-BHC	0.02	0.18	ppm	ND	ND	ND	ND
alpha-Chlordane	0.014	0.65	ppm	ND	ND	ND	ND
beta-BHC	0.021	0.18	ppm	ND	ND	ND	ND
Chlordane, total	NS	NS	ppm	ND	ND	ND	ND
delta-BHC	0.04	100	ppm	ND	ND	ND	ND
Dieldrin	0.005	0.075	ppm	ND	ND	ND	ND
Endosulfan I	4.3	35	ppm	ND	ND	ND	ND
Endosulfan II	4.3	35	ppm	ND	ND	ND	ND
Endosulfan sulfate	4.3	35	ppm	ND	ND	ND	ND
Endrin	0.014	5.3	ppm	ND	ND	ND	ND
Endrin aldehyde	NS	NS	ppm	ND	ND	ND	ND
Endrin ketone	NS	NS	ppm	ND	ND	ND	ND
gamma-BHC (Lindane)	0.025	0.21	ppm	ND	ND	ND	ND

Table 4d. Pesticides, Herbicides, and Polychlorinated Biphenyls in Soil
260 West 126th Street - New York, NY
BCP Site No. C231164

CLIENT SAMPLE ID	NY-UUSCO	NY-RESRR	Units	SB-3 (0-2)		SB-3 (8-10)		SB-3 (22-24)		SB-6 (0-2)	
SAMPLING DATE				1/5/2026		1/5/2026		1/5/2026		1/5/2026	
SAMPLE DEPTH (FT-BG)				0-2		8-10		22-24		0-2	
LAB SAMPLE ID				26A0061-05		26A0061-06		26A0061-07		26A0061-08	
					Qual		Qual		Qual		Qual
gamma-Chlordane	NS	NS	ppm	ND		ND		ND		ND	
Heptachlor	0.013	0.53	ppm	ND		ND		ND		ND	
Heptachlor epoxide	NS	NS	ppm	ND		ND		ND		ND	
Methoxychlor	NS	NS	ppm	ND		ND		ND		ND	
Toxaphene	NS	NS	ppm	ND		ND		ND		ND	
Herbicides											
2,4,5-T	NS	NS	ppm	ND		ND		ND		ND	
2,4,5-TP (Silvex)	NS	NS	ppm	ND		ND		ND		ND	
2,4-D	NS	NS	ppm	ND		ND		ND		ND	

Notes:

Bold and shaded yellow value indicates concentration exceeds NY-UNRES SCOs

Bold and shaded orange value indicates concentration exceeds NY-UNRES and NY-RESRR SCOs

NY-UNRES = 6 NYCRR Part 375 Unrestricted Use Soil Cleanup Objectives

NY-RESRR = 6 NYCRR Part 375 Restricted-Residential Use Soil Cleanup Objectives

D = Diluted

ND = Not detected

NS = No standard

-- = Not analyzed

P = The RPD between the results for the two columns exceeds the method-specified criteria.

ppm = parts per million

Table 4d. Pesticides, Herbicides, and Polychlorinated Biphenyls in Soil
260 West 126th Street - New York, NY
BCP Site No. C231164

CLIENT SAMPLE ID	NY-UUSCO	NY-RESRR	Units	SB-6 (8-10)	SB-6 (22-24)	SB-8 (0-2)	SB-8 (8-10)
SAMPLING DATE				1/5/2026	1/5/2026	1/5/2026	1/6/2026
SAMPLE DEPTH (FT-BG)				8-10	22-24	0-2	8-10
LAB SAMPLE ID				26A0061-09	26A0061-10	26A0061-11	26A0111-02
				Qual	Qual	Qual	Qual
Polychlorinated Biphenyls							
Aroclor 1016	NS	NS	ppm	ND	ND	ND	ND
Aroclor 1221	NS	NS	ppm	ND	ND	ND	ND
Aroclor 1232	NS	NS	ppm	ND	ND	ND	ND
Aroclor 1242	NS	NS	ppm	ND	ND	ND	ND
Aroclor 1248	NS	NS	ppm	ND	ND	ND	ND
Aroclor 1254	NS	NS	ppm	ND	ND	ND	ND
Aroclor 1260	NS	NS	ppm	ND	ND	0.0667	ND
Aroclor 1262	NS	NS	ppm	--	--	--	--
Aroclor 1268	NS	NS	ppm	--	--	--	--
Total PCBs	0.1	1	ppm	ND	ND	0.0667	ND
Pesticides							
4,4'-DDD	0.0033	5	ppm	ND	ND	ND	ND
4,4'-DDE	0.0033	3.4	ppm	ND	ND	ND	ND
4,4'-DDT	0.0033	3.8	ppm	ND	ND	ND	ND
Aldrin	0.0048	0.044	ppm	ND	ND	ND	ND
alpha-BHC	0.02	0.18	ppm	ND	ND	ND	ND
alpha-Chlordane	0.014	0.65	ppm	ND	ND	ND	ND
beta-BHC	0.021	0.18	ppm	ND	ND	ND	ND
Chlordane, total	NS	NS	ppm	ND	ND	ND	ND
delta-BHC	0.04	100	ppm	ND	ND	ND	ND
Dieldrin	0.005	0.075	ppm	ND	ND	ND	ND
Endosulfan I	4.3	35	ppm	ND	ND	ND	ND
Endosulfan II	4.3	35	ppm	ND	ND	ND	ND
Endosulfan sulfate	4.3	35	ppm	ND	ND	ND	ND
Endrin	0.014	5.3	ppm	ND	ND	ND	ND
Endrin aldehyde	NS	NS	ppm	ND	ND	ND	ND
Endrin ketone	NS	NS	ppm	ND	ND	ND	ND
gamma-BHC (Lindane)	0.025	0.21	ppm	ND	ND	ND	ND

Table 4d. Pesticides, Herbicides, and Polychlorinated Biphenyls in Soil
260 West 126th Street - New York, NY
BCP Site No. C231164

CLIENT SAMPLE ID	NY-UUSCO	NY-RESRR	Units	SB-6 (8-10)	SB-6 (22-24)	SB-8 (0-2)	SB-8 (8-10)
SAMPLING DATE				1/5/2026	1/5/2026	1/5/2026	1/6/2026
SAMPLE DEPTH (FT-BG)				8-10	22-24	0-2	8-10
LAB SAMPLE ID				26A0061-09	26A0061-10	26A0061-11	26A0111-02
				Qual	Qual	Qual	Qual
gamma-Chlordane	NS	NS	ppm	ND	ND	ND	ND
Heptachlor	0.013	0.53	ppm	ND	ND	ND	ND
Heptachlor epoxide	NS	NS	ppm	ND	ND	ND	ND
Methoxychlor	NS	NS	ppm	ND	ND	ND	ND
Toxaphene	NS	NS	ppm	ND	ND	ND	ND
Herbicides							
2,4,5-T	NS	NS	ppm	ND	ND	ND	ND
2,4,5-TP (Silvex)	NS	NS	ppm	ND	ND	ND	ND
2,4-D	NS	NS	ppm	ND	ND	ND	ND

Notes:

Bold and shaded yellow value indicates concentration exceeds NY-UNRES SCOs

Bold and shaded orange value indicates concentration exceeds NY-UNRES and NY-RESRR SCOs

NY-UNRES = 6 NYCRR Part 375 Unrestricted Use Soil Cleanup Objectives

NY-RESRR = 6 NYCRR Part 375 Restricted-Residential Use Soil Cleanup Objectives

D = Diluted

ND = Not detected

NS = No standard

-- = Not analyzed

P = The RPD between the results for the two columns exceeds the method-specified criteria.

ppm = parts per million

Table 4d. Pesticides, Herbicides, and Polychlorinated Biphenyls in Soil
260 West 126th Street - New York, NY
BCP Site No. C231164

CLIENT SAMPLE ID	NY-UUSCO	NY-RESRR	Units	SB-8 (22-24)	SB-2 (0-2)	SB-2 (0-2)_DUP	SB-2 (6-8)
SAMPLING DATE				1/6/2026	1/6/2026	1/6/2026	1/6/2026
SAMPLE DEPTH (FT-BG)				22-24	0-2	21-23	6-8
LAB SAMPLE ID				26A0111-03	26A0111-04	26A0111-13	26A0111-05
				Qual	Qual	Qual	Qual
Polychlorinated Biphenyls							
Aroclor 1016	NS	NS	ppm	ND	ND	ND	ND
Aroclor 1221	NS	NS	ppm	ND	ND	ND	ND
Aroclor 1232	NS	NS	ppm	ND	ND	ND	ND
Aroclor 1242	NS	NS	ppm	ND	ND	ND	ND
Aroclor 1248	NS	NS	ppm	ND	ND	ND	ND
Aroclor 1254	NS	NS	ppm	ND	ND	ND	ND
Aroclor 1260	NS	NS	ppm	ND	0.0369	ND	ND
Aroclor 1262	NS	NS	ppm	--	--	--	--
Aroclor 1268	NS	NS	ppm	--	--	--	--
Total PCBs	0.1	1	ppm	ND	0.0369	ND	ND
Pesticides							
4,4'-DDD	0.0033	5	ppm	ND	ND	ND	ND
4,4'-DDE	0.0033	3.4	ppm	ND	0.00289 DP	ND	ND
4,4'-DDT	0.0033	3.8	ppm	ND	**0.0138 D**	0.00234 D	ND
Aldrin	0.0048	0.044	ppm	ND	ND	ND	ND
alpha-BHC	0.02	0.18	ppm	ND	ND	ND	ND
alpha-Chlordane	0.014	0.65	ppm	ND	0.00823 D	ND	ND
beta-BHC	0.021	0.18	ppm	ND	ND	ND	ND
Chlordane, total	NS	NS	ppm	ND	0.103 D	ND	ND
delta-BHC	0.04	100	ppm	ND	ND	ND	ND
Dieldrin	0.005	0.075	ppm	ND	0.00229 D	ND	ND
Endosulfan I	4.3	35	ppm	ND	ND	ND	ND
Endosulfan II	4.3	35	ppm	ND	ND	ND	ND
Endosulfan sulfate	4.3	35	ppm	ND	ND	ND	ND
Endrin	0.014	5.3	ppm	ND	ND	ND	ND
Endrin aldehyde	NS	NS	ppm	ND	ND	ND	ND
Endrin ketone	NS	NS	ppm	ND	ND	ND	ND
gamma-BHC (Lindane)	0.025	0.21	ppm	ND	ND	ND	ND

Table 4d. Pesticides, Herbicides, and Polychlorinated Biphenyls in Soil
260 West 126th Street - New York, NY
BCP Site No. C231164

CLIENT SAMPLE ID	NY-UUSCO	NY-RESRR	Units	SB-8 (22-24)		SB-2 (0-2)		SB-2 (0-2)_DUP		SB-2 (6-8)	
SAMPLING DATE				1/6/2026		1/6/2026		1/6/2026		1/6/2026	
SAMPLE DEPTH (FT-BG)				22-24		0-2		21-23		6-8	
LAB SAMPLE ID				26A0111-03		26A0111-04		26A0111-13		26A0111-05	
					Qual		Qual		Qual		Qual
gamma-Chlordane	NS	NS	ppm	ND		0.00842	D	ND		ND	
Heptachlor	0.013	0.53	ppm	ND		0.00241	D	ND		ND	
Heptachlor epoxide	NS	NS	ppm	ND		ND		ND		ND	
Methoxychlor	NS	NS	ppm	ND		ND		ND		ND	
Toxaphene	NS	NS	ppm	ND		ND		ND		ND	
Herbicides											
2,4,5-T	NS	NS	ppm	ND		ND		ND		ND	
2,4,5-TP (Silvex)	NS	NS	ppm	ND		ND		ND		ND	
2,4-D	NS	NS	ppm	ND		ND		ND		ND	

Notes:

Bold and shaded yellow value indicates concentration exceeds NY-UNRES SCOs

Bold and shaded orange value indicates concentration exceeds NY-UNRES and NY-RESRR SCOs

NY-UNRES = 6 NYCRR Part 375 Unrestricted Use Soil Cleanup Objectives

NY-RESRR = 6 NYCRR Part 375 Restricted-Residential Use Soil Cleanup Objectives

D = Diluted

ND = Not detected

NS = No standard

-- = Not analyzed

P = The RPD between the results for the two columns exceeds the method-specified criteria.

ppm = parts per million

Table 4d. Pesticides, Herbicides, and Polychlorinated Biphenyls in Soil
260 West 126th Street - New York, NY
BCP Site No. C231164

CLIENT SAMPLE ID	NY-UUSCO	NY-RESRR	Units	SB-2 (22-24)	SB-9 (0-2)	SB-9 (6-8)	SB-9 (22-24)
SAMPLING DATE				1/6/2026	1/6/2026	1/6/2026	1/6/2026
SAMPLE DEPTH (FT-BG)				22-24	0-2	6-8	22-24
LAB SAMPLE ID				26A0111-06	26A0111-07	26A0111-08	26A0111-09
				Qual	Qual	Qual	Qual
Polychlorinated Biphenyls							
Aroclor 1016	NS	NS	ppm	ND	ND	ND	ND
Aroclor 1221	NS	NS	ppm	ND	ND	ND	ND
Aroclor 1232	NS	NS	ppm	ND	ND	ND	ND
Aroclor 1242	NS	NS	ppm	ND	ND	ND	ND
Aroclor 1248	NS	NS	ppm	ND	ND	ND	ND
Aroclor 1254	NS	NS	ppm	ND	ND	ND	ND
Aroclor 1260	NS	NS	ppm	ND	ND	ND	ND
Aroclor 1262	NS	NS	ppm	--	--	--	--
Aroclor 1268	NS	NS	ppm	--	--	--	--
Total PCBs	0.1	1	ppm	ND	ND	ND	ND
Pesticides							
4,4'-DDD	0.0033	5	ppm	ND	ND	ND	ND
4,4'-DDE	0.0033	3.4	ppm	ND	ND	ND	ND
4,4'-DDT	0.0033	3.8	ppm	ND	ND	ND	ND
Aldrin	0.0048	0.044	ppm	ND	ND	ND	ND
alpha-BHC	0.02	0.18	ppm	ND	ND	ND	ND
alpha-Chlordane	0.014	0.65	ppm	ND	ND	ND	ND
beta-BHC	0.021	0.18	ppm	ND	ND	ND	ND
Chlordane, total	NS	NS	ppm	ND	ND	ND	ND
delta-BHC	0.04	100	ppm	ND	ND	ND	ND
Dieldrin	0.005	0.075	ppm	ND	ND	ND	ND
Endosulfan I	4.3	35	ppm	ND	ND	ND	ND
Endosulfan II	4.3	35	ppm	ND	ND	ND	ND
Endosulfan sulfate	4.3	35	ppm	ND	ND	ND	ND
Endrin	0.014	5.3	ppm	ND	ND	ND	ND
Endrin aldehyde	NS	NS	ppm	ND	ND	ND	ND
Endrin ketone	NS	NS	ppm	ND	ND	ND	ND
gamma-BHC (Lindane)	0.025	0.21	ppm	ND	ND	ND	ND

Table 4d. Pesticides, Herbicides, and Polychlorinated Biphenyls in Soil
260 West 126th Street - New York, NY
BCP Site No. C231164

CLIENT SAMPLE ID	NY-UUSCO	NY-RESRR	Units	SB-2 (22-24)	SB-9 (0-2)	SB-9 (6-8)	SB-9 (22-24)
SAMPLING DATE				1/6/2026	1/6/2026	1/6/2026	1/6/2026
SAMPLE DEPTH (FT-BG)				22-24	0-2	6-8	22-24
LAB SAMPLE ID				26A0111-06	26A0111-07	26A0111-08	26A0111-09
				Qual	Qual	Qual	Qual
gamma-Chlordane	NS	NS	ppm	ND	ND	ND	ND
Heptachlor	0.013	0.53	ppm	ND	ND	ND	ND
Heptachlor epoxide	NS	NS	ppm	ND	ND	ND	ND
Methoxychlor	NS	NS	ppm	ND	ND	ND	ND
Toxaphene	NS	NS	ppm	ND	ND	ND	ND
Herbicides							
2,4,5-T	NS	NS	ppm	ND	ND	ND	ND
2,4,5-TP (Silvex)	NS	NS	ppm	ND	ND	ND	ND
2,4-D	NS	NS	ppm	ND	ND	ND	ND

Notes:

Bold and shaded yellow value indicates concentration exceeds NY-UNRES SCOs

Bold and shaded orange value indicates concentration exceeds NY-UNRES and NY-RESRR SCOs

NY-UNRES = 6 NYCRR Part 375 Unrestricted Use Soil Cleanup Objectives

NY-RESRR = 6 NYCRR Part 375 Restricted-Residential Use Soil Cleanup Objectives

D = Diluted

ND = Not detected

NS = No standard

-- = Not analyzed

P = The RPD between the results for the two columns exceeds the method-specified criteria.

ppm = parts per million

Table 4d. Pesticides, Herbicides, and Polychlorinated Biphenyls in Soil
260 West 126th Street - New York, NY
BCP Site No. C231164

CLIENT SAMPLE ID	NY-UUSCO	NY-RESRR	Units	SB-1 (0-2)	SB-1 (6-8)	SB-1 (21-23)	SB-7 (0-2)
SAMPLING DATE				1/6/2026	1/6/2026	1/6/2026	6/26/2026
SAMPLE DEPTH (FT-BG)				0-2	6-8	21-23	0-2
LAB SAMPLE ID				26A0111-10	26A0111-11	26A0111-12	26F1687-01
				Qual	Qual	Qual	Qual
Polychlorinated Biphenyls							
Aroclor 1016	NS	NS	ppm	ND	ND	ND	ND
Aroclor 1221	NS	NS	ppm	ND	ND	ND	ND
Aroclor 1232	NS	NS	ppm	ND	ND	ND	ND
Aroclor 1242	NS	NS	ppm	ND	ND	ND	ND
Aroclor 1248	NS	NS	ppm	ND	ND	ND	ND
Aroclor 1254	NS	NS	ppm	ND	ND	ND	ND
Aroclor 1260	NS	NS	ppm	ND	ND	ND	ND
Aroclor 1262	NS	NS	ppm	--	--	--	ND
Aroclor 1268	NS	NS	ppm	--	--	--	ND
Total PCBs	0.1	1	ppm	ND	ND	ND	ND
Pesticides							
4,4'-DDD	0.0033	5	ppm	ND	ND	ND	ND
4,4'-DDE	0.0033	3.4	ppm	ND	ND	ND	ND
4,4'-DDT	0.0033	3.8	ppm	ND	ND	ND	ND
Aldrin	0.0048	0.044	ppm	ND	ND	ND	ND
alpha-BHC	0.02	0.18	ppm	ND	ND	ND	ND
alpha-Chlordane	0.014	0.65	ppm	ND	ND	ND	ND
beta-BHC	0.021	0.18	ppm	ND	ND	ND	ND
Chlordane, total	NS	NS	ppm	ND	ND	ND	ND
delta-BHC	0.04	100	ppm	ND	ND	ND	ND
Dieldrin	0.005	0.075	ppm	ND	ND	ND	ND
Endosulfan I	4.3	35	ppm	ND	ND	ND	ND
Endosulfan II	4.3	35	ppm	ND	ND	ND	ND
Endosulfan sulfate	4.3	35	ppm	ND	ND	ND	ND
Endrin	0.014	5.3	ppm	ND	ND	ND	ND
Endrin aldehyde	NS	NS	ppm	ND	ND	ND	ND
Endrin ketone	NS	NS	ppm	ND	ND	ND	ND
gamma-BHC (Lindane)	0.025	0.21	ppm	ND	ND	ND	ND

Table 4d. Pesticides, Herbicides, and Polychlorinated Biphenyls in Soil
260 West 126th Street - New York, NY
BCP Site No. C231164

CLIENT SAMPLE ID	NY-UUSCO	NY-RESRR	Units	SB-1 (0-2)		SB-1 (6-8)		SB-1 (21-23)		SB-7 (0-2)	
SAMPLING DATE				1/6/2026		1/6/2026		1/6/2026		6/26/2026	
SAMPLE DEPTH (FT-BG)				0-2		6-8		21-23		0-2	
LAB SAMPLE ID				26A0111-10		26A0111-11		26A0111-12		26F1687-01	
					Qual		Qual		Qual		Qual
gamma-Chlordane	NS	NS	ppm	ND		ND		ND		ND	
Heptachlor	0.013	0.53	ppm	ND		ND		ND		ND	
Heptachlor epoxide	NS	NS	ppm	ND		ND		ND		ND	
Methoxychlor	NS	NS	ppm	ND		ND		ND		ND	
Toxaphene	NS	NS	ppm	ND		ND		ND		ND	
Herbicides											
2,4,5-T	NS	NS	ppm	ND		ND		ND		ND	
2,4,5-TP (Silvex)	NS	NS	ppm	ND		ND		ND		ND	
2,4-D	NS	NS	ppm	ND		ND		ND		ND	

Notes:

Bold and shaded yellow value indicates concentration exceeds NY-UNRES SCOs

Bold and shaded orange value indicates concentration exceeds NY-UNRES and NY-RESRR SCOs

NY-UNRES = 6 NYCRR Part 375 Unrestricted Use Soil Cleanup Objectives

NY-RESRR = 6 NYCRR Part 375 Restricted-Residential Use Soil Cleanup Objectives

D = Diluted

ND = Not detected

NS = No standard

-- = Not analyzed

P = The RPD between the results for the two columns exceeds the method-specified criteria.

ppm = parts per million

Table 4d. Pesticides, Herbicides, and Polychlorinated Biphenyls in Soil
260 West 126th Street - New York, NY
BCP Site No. C231164

CLIENT SAMPLE ID	NY-UUSCO	NY-RESRR	Units	SB-7 (10-12)	SB-7 (12-14)	SB-4 (0-2)	SB-4 (12-14)
SAMPLING DATE				6/26/2026	6/26/2026	6/26/2026	6/26/2026
SAMPLE DEPTH (FT-BG)				10-12	12-14	0-2	12-14
LAB SAMPLE ID				26F1687-02	26F1687-03	26F1687-04	26F1687-05
				Qual	Qual	Qual	Qual
Polychlorinated Biphenyls							
Aroclor 1016	NS	NS	ppm	ND	ND	ND	ND
Aroclor 1221	NS	NS	ppm	ND	ND	ND	ND
Aroclor 1232	NS	NS	ppm	ND	ND	ND	ND
Aroclor 1242	NS	NS	ppm	ND	ND	ND	ND
Aroclor 1248	NS	NS	ppm	ND	ND	ND	ND
Aroclor 1254	NS	NS	ppm	ND	ND	ND	ND
Aroclor 1260	NS	NS	ppm	ND	ND	ND	ND
Aroclor 1262	NS	NS	ppm	ND	ND	ND	ND
Aroclor 1268	NS	NS	ppm	ND	ND	ND	ND
Total PCBs	0.1	1	ppm	ND	ND	ND	ND
Pesticides							
4,4'-DDD	0.0033	5	ppm	ND	ND	ND	**0.00489 D**
4,4'-DDE	0.0033	3.4	ppm	ND	ND	ND	**0.00658 D**
4,4'-DDT	0.0033	3.8	ppm	ND	ND	ND	**0.00986 D**
Aldrin	0.0048	0.044	ppm	ND	ND	ND	ND
alpha-BHC	0.02	0.18	ppm	ND	ND	ND	ND
alpha-Chlordane	0.014	0.65	ppm	ND	ND	ND	ND
beta-BHC	0.021	0.18	ppm	ND	ND	ND	ND
Chlordane, total	NS	NS	ppm	ND	ND	ND	ND
delta-BHC	0.04	100	ppm	ND	ND	ND	ND
Dieldrin	0.005	0.075	ppm	ND	ND	ND	ND
Endosulfan I	4.3	35	ppm	ND	ND	ND	ND
Endosulfan II	4.3	35	ppm	ND	ND	ND	ND
Endosulfan sulfate	4.3	35	ppm	ND	ND	ND	ND
Endrin	0.014	5.3	ppm	ND	ND	ND	ND
Endrin aldehyde	NS	NS	ppm	ND	ND	ND	ND
Endrin ketone	NS	NS	ppm	ND	ND	ND	ND
gamma-BHC (Lindane)	0.025	0.21	ppm	ND	ND	ND	ND

Table 4d. Pesticides, Herbicides, and Polychlorinated Biphenyls in Soil
260 West 126th Street - New York, NY
BCP Site No. C231164

CLIENT SAMPLE ID	NY-UUSCO	NY-RESRR	Units	SB-7 (10-12)	SB-7 (12-14)	SB-4 (0-2)	SB-4 (12-14)
SAMPLING DATE				6/26/2026	6/26/2026	6/26/2026	6/26/2026
SAMPLE DEPTH (FT-BG)				10-12	12-14	0-2	12-14
LAB SAMPLE ID				26F1687-02	26F1687-03	26F1687-04	26F1687-05
				Qual	Qual	Qual	Qual
gamma-Chlordane	NS	NS	ppm	ND	ND	ND	ND
Heptachlor	0.013	0.53	ppm	ND	ND	ND	ND
Heptachlor epoxide	NS	NS	ppm	ND	ND	ND	ND
Methoxychlor	NS	NS	ppm	ND	ND	ND	ND
Toxaphene	NS	NS	ppm	ND	ND	ND	ND
Herbicides							
2,4,5-T	NS	NS	ppm	ND	ND	ND	ND
2,4,5-TP (Silvex)	NS	NS	ppm	ND	ND	ND	ND
2,4-D	NS	NS	ppm	ND	ND	ND	ND

Notes:

Bold and shaded yellow value indicates concentration exceeds NY-UNRES SCOs

Bold and shaded orange value indicates concentration exceeds NY-UNRES and NY-RESRR SCOs

NY-UNRES = 6 NYCRR Part 375 Unrestricted Use Soil Cleanup Objectives

NY-RESRR = 6 NYCRR Part 375 Restricted-Residential Use Soil Cleanup Objectives

D = Diluted

ND = Not detected

NS = No standard

-- = Not analyzed

P = The RPD between the results for the two columns exceeds the method-specified criteria.

ppm = parts per million

Table 4d. Pesticides, Herbicides, and Polychlorinated Biphenyls in Soil
260 West 126th Street - New York, NY
BCP Site No. C231164

CLIENT SAMPLE ID	NY-UUSCO	NY-RESRR	Units	SB-4 (14-15)
SAMPLING DATE				6/26/2026
SAMPLE DEPTH (FT-BG)				14-15
LAB SAMPLE ID				26F1687-06
				Qual
Polychlorinated Biphenyls				
Aroclor 1016	NS	NS	ppm	ND
Aroclor 1221	NS	NS	ppm	ND
Aroclor 1232	NS	NS	ppm	ND
Aroclor 1242	NS	NS	ppm	ND
Aroclor 1248	NS	NS	ppm	ND
Aroclor 1254	NS	NS	ppm	ND
Aroclor 1260	NS	NS	ppm	ND
Aroclor 1262	NS	NS	ppm	ND
Aroclor 1268	NS	NS	ppm	ND
Total PCBs	0.1	1	ppm	ND
Pesticides				
4,4'-DDD	0.0033	5	ppm	ND
4,4'-DDE	0.0033	3.4	ppm	ND
4,4'-DDT	0.0033	3.8	ppm	ND
Aldrin	0.0048	0.044	ppm	ND
alpha-BHC	0.02	0.18	ppm	ND
alpha-Chlordane	0.014	0.65	ppm	ND
beta-BHC	0.021	0.18	ppm	ND
Chlordane, total	NS	NS	ppm	ND
delta-BHC	0.04	100	ppm	ND
Dieldrin	0.005	0.075	ppm	ND
Endosulfan I	4.3	35	ppm	ND
Endosulfan II	4.3	35	ppm	ND
Endosulfan sulfate	4.3	35	ppm	ND
Endrin	0.014	5.3	ppm	ND
Endrin aldehyde	NS	NS	ppm	ND
Endrin ketone	NS	NS	ppm	ND
gamma-BHC (Lindane)	0.025	0.21	ppm	ND

Table 4d. Pesticides, Herbicides, and Polychlorinated Biphenyls in Soil
260 West 126th Street - New York, NY
BCP Site No. C231164

CLIENT SAMPLE ID	NY-UUSCO	NY-RESRR	Units	SB-4 (14-15)
SAMPLING DATE				6/26/2026
SAMPLE DEPTH (FT-BG)				14-15
LAB SAMPLE ID				26F1687-06
				Qual
gamma-Chlordane	NS	NS	ppm	ND
Heptachlor	0.013	0.53	ppm	ND
Heptachlor epoxide	NS	NS	ppm	ND
Methoxychlor	NS	NS	ppm	ND
Toxaphene	NS	NS	ppm	ND
Herbicides				
2,4,5-T	NS	NS	ppm	ND
2,4,5-TP (Silvex)	NS	NS	ppm	ND
2,4-D	NS	NS	ppm	ND

Notes:

Bold and shaded yellow value indicates concentration exceeds NY-UNRES SCOs

Bold and shaded orange value indicates concentration exceeds NY-UNRES and NY-RESRR SCOs

NY-UNRES = 6 NYCRR Part 375 Unrestricted Use Soil Cleanup Objectives

NY-RESRR = 6 NYCRR Part 375 Restricted-Residential Use Soil Cleanup Objectives

D = Diluted

ND = Not detected

NS = No standard

-- = Not analyzed

P = The RPD between the results for the two columns exceeds the method-specified criteria.

ppm = parts per million

Table 4e. Emerging Contaminants in Soil
260 West 126th Street - New York, NY
BCP Site No. C231164

CLIENT SAMPLE ID	NY-UUSCO	NY-PGW	NY-RESRR	Units	SB-5 (0-2)	SB-5 (12.5-14.5)	SB-5 (22-24)	SB-5 (22-24)_DUP	SB-3 (0-2)	SB-3 (8-10)	SB-3 (22-24)	SB-6 (0-2)	SB-6 (8-10)	SB-6 (22-24)	SB-8 (0-2)	SB-8 (8-10)	SB-8 (22-24)
SAMPLING DATE					1/5/2026	1/5/2026	1/5/2026	1/5/2026	1/5/2026	1/5/2026	1/5/2026	1/5/2026	1/5/2026	1/5/2026	1/5/2026	1/6/2026	1/6/2026
SAMPLE DEPTH (FT-BG)					0-2	12.5-14.5	22-24	22-24	0-2	8-10	22-24	0-2	8-10	22-24	0-2	8-10	22-24
LAB SAMPLE ID					26A0061-01	26A0061-02	26A0061-03	26A0061-04	26A0061-05	26A0061-06	26A0061-07	26A0061-08	26A0061-09	26A0061-10	26A0061-11	26A0111-02	26A0111-03
					Qual	Qual	Qual	Qual	Qual	Qual	Qual	Qual	Qual	Qual	Qual	Qual	Qual
1,4-Dioxane																	
1,4-Dioxane	0.1	0.1	5.7	ppm	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Per- and Polyfluoroalkyl Substances																	
Perfluoro-3,6-dioxaheptanoic acid (NFDHA)	NS	NS	NS	ppb	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
11CL-PF3OUdS	NS	NS	NS	ppb	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1H,1H,2H,2H-Perfluorodecanesulfonic acid (8:2 FTS)	NS	NS	NS	ppb	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1H,1H,2H,2H-Perfluorohexanesulfonic acid (4:2 FTS)	NS	NS	NS	ppb	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1H,1H,2H,2H-Perfluorooctanesulfonic acid (6:2 FTS)	NS	NS	NS	ppb	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
2H,2H,3H,3H-Perfluorodecanoic acid (7:3FTCA)	NS	NS	NS	ppb	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
2H,2H,3H,3H-Perfluorooctanoic acid (5:3FTCA)	NS	NS	NS	ppb	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
4,4,5,5,6,6,6-Heptafluorohexanoic acid (3:3FTCA)	NS	NS	NS	ppb	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
9CL-PF3ONS	NS	NS	NS	ppb	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
ADONA	NS	NS	NS	ppb	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
HFPO-DA (Gen-X)	NS	NS	NS	ppb	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
N-EtFOSA	NS	NS	NS	ppb	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
N-EtFOSAA	NS	NS	NS	ppb	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
N-EtFOSE	NS	NS	NS	ppb	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
N-MeFOSA	NS	NS	NS	ppb	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
N-MeFOSAA	NS	NS	NS	ppb	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
N-MeFOSE	NS	NS	NS	ppb	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Perfluoro(2-ethoxyethane)sulfonic acid (PFEESA)	NS	NS	NS	ppb	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Perfluoro-1-decanesulfonic acid (PFDS)	NS	NS	NS	ppb	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Perfluoro-1-heptanesulfonic acid (PFHpS)	NS	NS	NS	ppb	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Perfluoro-1-nonanesulfonic acid (PFNS)	NS	NS	NS	ppb	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Perfluoro-1-octanesulfonamide (FOSA)	NS	NS	NS	ppb	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Perfluoro-1-pentanesulfonate (PFPeS)	NS	NS	NS	ppb	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Perfluoro-4-oxapentanoic acid (PFMPA)	NS	NS	NS	ppb	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Perfluoro-5-oxahexanoic acid (PFMBA)	NS	NS	NS	ppb	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Perfluorobutanesulfonic acid (PFBS)	NS	NS	NS	ppb	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Perfluorodecanoic acid (PFDA)	NS	NS	NS	ppb	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Perfluorododecanesulfonic acid (PFDoS)	NS	NS	NS	ppb	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Perfluorododecanoic acid (PFDoA)	NS	NS	NS	ppb	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Perfluoroheptanoic acid (PFHpA)	NS	NS	NS	ppb	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Perfluorohexanesulfonic acid (PFHxS)	NS	NS	NS	ppb	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Perfluorohexanoic acid (PFHxA)	NS	NS	NS	ppb	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Perfluoro-n-butanoic acid (PFBA)	NS	NS	NS	ppb	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Perfluorononanoic acid (PFNA)	NS	NS	NS	ppb	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Perfluorooctanesulfonic acid (PFOS)	0.88	1	44	ppb	**1.29 D**	ND	ND	ND	**1.74**	ND	ND	0.732	ND	ND	ND	ND	0.0753 J
Perfluorooctanoic acid (PFOA)	0.66	0.8	33	ppb	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	0.0927 J	ND	ND
Perfluoropentanoic acid (PFPeA)	NS	NS	NS	ppb	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Perfluorotetradecanoic acid (PFTA)	NS	NS	NS	ppb	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Perfluorotridecanoic acid (PFTrDA)	NS	NS	NS	ppb	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Perfluoroundecanoic acid (PFUnA)	NS	NS	NS	ppb	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND

Notes:

Bold and shaded yellow value indicates concentration exceeds NY-UNRES SCOs

Bold and shaded blue value indicates concentration exceeds NY-UNRES and NY-PGW SCOs

Bold and shaded orange value indicates concentration exceeds NY-UNRES, NY-PGW, and NY-RESRR SCOs

NY-UNRES = 6 NYCRR Part 375 Unrestricted Use Soil Cleanup Objectives

NY-PGW = 6 NYCRR Part 375 Protection of Groundwater Soil Cleanup Objectives

NY-RESRR = 6 NYCRR Part 375 Restricted-Residential Use Soil Cleanup Objectives

The SCOs for all PFAS analytes are proposed per NYSDEC's *Sampling, Analysis, and Assessment of PFAS Under NYSDEC's Part 375 Remedial Programs* , April 2023

J = Estimated value

D = Diluted

ND = Not detected

NS = No standard

ppm = parts per million

ppb = parts per billion

Table 4e. Emerging Contaminants in Soil
260 West 126th Street - New York, NY
BCP Site No. C231164

CLIENT SAMPLE ID	NY-UUSCO	NY-PGW	NY-RESRR	Units	SB-2 (0-2)		SB-2 (0-2)_DUP		SB-2 (6-8)		SB-2 (22-24)		SB-9 (0-2)		SB-9 (6-8)		SB-9 (22-24)		SB-1 (0-2)		SB-1 (6-8)		SB-1 (21-23)		SB-7 (0-2)		SB-7 (10-12)		SB-7 (12-14)	
SAMPLING DATE					1/6/2026		1/6/2026		1/6/2026		1/6/2026		1/6/2026		1/6/2026		1/6/2026		1/6/2026		1/6/2026		1/6/2026		6/26/2026		6/26/2026		6/26/2026	
SAMPLE DEPTH (FT-BG)					0-2		21-23		6-8		22-24		0-2		6-8		22-24		0-2		6-8		21-23		0-2		10-12		12-14	
LAB SAMPLE ID					26A0111-04		26A0111-13		26A0111-05		26A0111-06		26A0111-07		26A0111-08		26A0111-09		26A0111-10		26A0111-11		26A0111-12		26F1687-01		26F1687-02		26F1687-03	
						Qual		Qual		Qual		Qual		Qual		Qual		Qual		Qual		Qual		Qual		Qual		Qual		Qual
1,4-Dioxane																														
1,4-Dioxane	0.1	0.1	5.7	ppm	ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		ND	
Per- and Polyfluoroalkyl Substances																														
Perfluoro-3,6-dioxaheptanoic acid (NFDHA)	NS	NS	NS	ppb	ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		ND	
11CL-PF3OUdS	NS	NS	NS	ppb	ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		ND	
1H,1H,2H,2H-Perfluorodecanesulfonic acid (8:2 FTS)	NS	NS	NS	ppb	ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		ND	
1H,1H,2H,2H-Perfluorohexanesulfonic acid (4:2 FTS)	NS	NS	NS	ppb	ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		ND	
1H,1H,2H,2H-Perfluorooctanesulfonic acid (6:2 FTS)	NS	NS	NS	ppb	ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		0.047	J	0.053	J	0.039	J
2H,2H,3H,3H-Perfluorodecanoic acid (7:3FTCA)	NS	NS	NS	ppb	ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		ND	
2H,2H,3H,3H-Perfluorooctanoic acid (5:3FTCA)	NS	NS	NS	ppb	ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		ND	
4,4,5,5,6,6,6-Heptafluorohexanoic acid (3:3FTCA)	NS	NS	NS	ppb	ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		1.647	J	ND	
9CL-PF3ONS	NS	NS	NS	ppb	ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		ND	
ADONA	NS	NS	NS	ppb	ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		ND	
HFPO-DA (Gen-X)	NS	NS	NS	ppb	ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		ND	
N-EtFOSA	NS	NS	NS	ppb	ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		ND	
N-EtFOSAA	NS	NS	NS	ppb	ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		ND	
N-EtFOSE	NS	NS	NS	ppb	ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		ND	
N-MeFOSA	NS	NS	NS	ppb	ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		ND	
N-MeFOSAA	NS	NS	NS	ppb	ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		ND	
N-MeFOSE	NS	NS	NS	ppb	ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		ND	
Perfluoro(2-ethoxyethane)sulfonic acid (PFEESA)	NS	NS	NS	ppb	ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		ND	
Perfluoro-1-decanesulfonic acid (PFDS)	NS	NS	NS	ppb	ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		ND	
Perfluoro-1-heptanesulfonic acid (PFHpS)	NS	NS	NS	ppb	ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		ND	
Perfluoro-1-nonanesulfonic acid (PFNS)	NS	NS	NS	ppb	ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		ND	
Perfluoro-1-octanesulfonamide (FOSA)	NS	NS	NS	ppb	ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		ND	
Perfluoro-1-pentanesulfonate (PFPeS)	NS	NS	NS	ppb	ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		ND	
Perfluoro-4-oxapentanoic acid (PFMPA)	NS	NS	NS	ppb	ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		ND	
Perfluoro-5-oxahexanoic acid (PFMBA)	NS	NS	NS	ppb	ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		ND	
Perfluorobutanesulfonic acid (PFBS)	NS	NS	NS	ppb	ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		ND	
Perfluorodecanoic acid (PFDA)	NS	NS	NS	ppb	ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		ND	
Perfluorododecanesulfonic acid (PFDoS)	NS	NS	NS	ppb	ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		ND	
Perfluorododecanoic acid (PFDoA)	NS	NS	NS	ppb	ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		ND	
Perfluoroheptanoic acid (PFHpA)	NS	NS	NS	ppb	ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		ND	
Perfluorohexanesulfonic acid (PFHxS)	NS	NS	NS	ppb	ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		ND	
Perfluorohexanoic acid (PFHxA)	NS	NS	NS	ppb	0.0934	J	ND		ND		ND		0.242		ND		ND		ND		ND		ND		0.017	J	ND		ND	
Perfluoro-n-butanoic acid (PFBA)	NS	NS	NS	ppb	ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		0.02	J	ND	
Perfluorononanoic acid (PFNA)	NS	NS	NS	ppb	ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		ND	
Perfluorooctanesulfonic acid (PFOS)	0.88	1	44	ppb	0.218	J	**1.38**		ND		ND		ND		ND		ND		ND		ND		ND		0.038	J	ND		0.043	J
Perfluorooctanoic acid (PFOA)	0.66	0.8	33	ppb	0.159	J	ND		ND		ND		ND		ND		ND		0.0972	J	ND		ND		ND		ND		ND	
Perfluoropentanoic acid (PFPeA)	NS	NS	NS	ppb	0.0969	J	ND		ND		ND		ND		ND		ND		ND		ND		ND		0.027	J	ND		ND	
Perfluorotetradecanoic acid (PFTA)	NS	NS	NS	ppb	ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		ND	
Perfluorotridecanoic acid (PFTrDA)	NS	NS	NS	ppb	ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		ND	
Perfluoroundecanoic acid (PFUnA)	NS	NS	NS	ppb	ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		ND		ND	

Notes:

Bold and shaded yellow value indicates concentration exceeds NY-UNRES SCOs

Bold and shaded blue value indicates concentration exceeds NY-UNRES and NY-PGW SCOs

Bold and shaded orange value indicates concentration exceeds NY-UNRES, NY-PGW, and NY-RESRR SCOs

NY-UNRES = 6 NYCRR Part 375 Unrestricted Use Soil Cleanup Objectives

NY-PGW = 6 NYCRR Part 375 Protection of Groundwater Soil Cleanup Objectives

NY-RESRR = 6 NYCRR Part 375 Restricted-Residential Use Soil Cleanup Objectives

The SCOs for all PFAS analytes are proposed per NYSDEC's *Sampling, Analysis, and Assessment of PFAS Under NYSDEC's Part 375 Remedial Programs*, April 2023

J = Estimated value

D = Diluted

ND = Not detected

NS = No standard

ppm = parts per million

ppb = parts per billion

Table 4e. Emerging Contaminants in Soil
260 West 126th Street - New York, NY
BCP Site No. C231164

CLIENT SAMPLE ID	NY-UUSCO	NY-PGW	NY-RESRR	Units	SB-4 (0-2)		SB-4 (12-14)		SB-4 (14-15)	
SAMPLING DATE					6/26/2026		6/26/2026		6/26/2026	
SAMPLE DEPTH (FT-BG)					0-2		12-14		14-15	
LAB SAMPLE ID					26F1687-04		26F1687-05		26F1687-06	
						Qual		Qual		Qual
1,4-Dioxane										
1,4-Dioxane	0.1	0.1	5.7	ppm	ND		ND		ND	
Per- and Polyfluoroalkyl Substances										
Perfluoro-3,6-dioxaheptanoic acid (NFDHA)	NS	NS	NS	ppb	ND		ND		ND	
11CL-PF3OUdS	NS	NS	NS	ppb	ND		ND		ND	
1H,1H,2H,2H-Perfluorodecanesulfonic acid (8:2 FTS)	NS	NS	NS	ppb	ND		ND		ND	
1H,1H,2H,2H-Perfluorohexanesulfonic acid (4:2 FTS)	NS	NS	NS	ppb	ND		ND		ND	
1H,1H,2H,2H-Perfluorooctanesulfonic acid (6:2 FTS)	NS	NS	NS	ppb	0.057	J	0.057	J	0.058	J
2H,2H,3H,3H-Perfluorodecanoic acid (7:3FTCA)	NS	NS	NS	ppb	ND		ND		ND	
2H,2H,3H,3H-Perfluorooctanoic acid (5:3FTCA)	NS	NS	NS	ppb	ND		ND		ND	
4,4,5,5,6,6,6-Heptafluorohexanoic acid (3:3FTCA)	NS	NS	NS	ppb	ND		ND		ND	
9CL-PF3ONS	NS	NS	NS	ppb	ND		ND		ND	
ADONA	NS	NS	NS	ppb	ND		ND		ND	
HFPO-DA (Gen-X)	NS	NS	NS	ppb	ND		ND		ND	
N-EtFOSA	NS	NS	NS	ppb	ND		0.04	J	ND	
N-EtFOSAA	NS	NS	NS	ppb	0.06	J	0.148	J	ND	
N-EtFOSE	NS	NS	NS	ppb	ND		0.06	J	ND	
N-MeFOSA	NS	NS	NS	ppb	ND		ND		ND	
N-MeFOSAA	NS	NS	NS	ppb	ND		ND		ND	
N-MeFOSE	NS	NS	NS	ppb	ND		0.041	J	ND	
Perfluoro(2-ethoxyethane)sulfonic acid (PFEESA)	NS	NS	NS	ppb	ND		ND		ND	
Perfluoro-1-decanesulfonic acid (PFDS)	NS	NS	NS	ppb	0.069	J	0.087	J	ND	
Perfluoro-1-heptanesulfonic acid (PFHpS)	NS	NS	NS	ppb	ND		ND		ND	
Perfluoro-1-nonanesulfonic acid (PFNS)	NS	NS	NS	ppb	ND		ND		ND	
Perfluoro-1-octanesulfonamide (FOSA)	NS	NS	NS	ppb	0.044	J	0.029	J	ND	
Perfluoro-1-pentanesulfonate (PFPeS)	NS	NS	NS	ppb	ND		ND		ND	
Perfluoro-4-oxapentanoic acid (PFMPA)	NS	NS	NS	ppb	ND		ND		ND	
Perfluoro-5-oxahexanoic acid (PFMBA)	NS	NS	NS	ppb	ND		ND		ND	
Perfluorobutanesulfonic acid (PFBS)	NS	NS	NS	ppb	ND		ND		ND	
Perfluorodecanoic acid (PFDA)	NS	NS	NS	ppb	ND		0.025	J	ND	
Perfluorododecanesulfonic acid (PFDoS)	NS	NS	NS	ppb	ND		ND		ND	
Perfluorododecanoic acid (PFDoA)	NS	NS	NS	ppb	ND		ND		ND	
Perfluoroheptanoic acid (PFHpA)	NS	NS	NS	ppb	0.015	J	0.036	J	ND	
Perfluorohexanesulfonic acid (PFHxS)	NS	NS	NS	ppb	0.033	J	0.025	J	0.023	J
Perfluorohexanoic acid (PFHxA)	NS	NS	NS	ppb	0.013	J	0.055	J	0.01	J
Perfluoro-n-butanoic acid (PFBA)	NS	NS	NS	ppb	0.021	J	0.039	J	0.019	J
Perfluorononanoic acid (PFNA)	NS	NS	NS	ppb	ND		0.019	J	ND	
Perfluorooctanesulfonic acid (PFOS)	0.88	1	44	ppb	0.457	J	0.24	J	0.224	J
Perfluorooctanoic acid (PFOA)	0.66	0.8	33	ppb	0.106	J	0.229	J	0.059	J
Perfluoropentanoic acid (PFPeA)	NS	NS	NS	ppb	0.016	J	0.038	J	0.016	J
Perfluorotetradecanoic acid (PFTA)	NS	NS	NS	ppb	ND		ND		ND	
Perfluorotridecanoic acid (PFTrDA)	NS	NS	NS	ppb	ND		ND		ND	
Perfluoroundecanoic acid (PFUnA)	NS	NS	NS	ppb	ND		ND		ND	

Notes:

Bold and shaded yellow value indicates concentration exceeds NY-UNRES SCOs

Bold and shaded blue value indicates concentration exceeds NY-UNRES and NY-PGW SCOs

Bold and shaded orange value indicates concentration exceeds NY-UNRES, NY-PGW, and NY-RESRR SCOs

NY-UNRES = 6 NYCRR Part 375 Unrestricted Use Soil Cleanup Objectives

NY-PGW = 6 NYCRR Part 375 Protection of Groundwater Soil Cleanup Objectives

NY-RESRR = 6 NYCRR Part 375 Restricted-Residential Use Soil Cleanup Objectives

The SCOs for all PFAS analytes are proposed per NYSDEC's *Sampling, Analysis, and Assessment of PFAS Under NYSDEC's Part 375 Remedial Programs* , April 2023

J = Estimated value

D = Diluted

ND = Not detected

NS = No standard

ppm = parts per million

ppb = parts per billion

Table 5a. Volatile Organic Compounds in Groundwater
260 West 126th Street - New York, NY
BCP Site No. C231164

Sample ID:	NY-AWQS	Units	MW-1	MW-2	MW-3	MW-4	MW-5
Laboratory ID:			26A1069-01	26A1069-02	26A1069-03	26G0536-01	26G0536-02
Sampling Date:			1/22/2026	1/22/2026	1/22/2026	7/9/2026	7/9/2026
			Qual	Qual	Qual	Qual	Qual
Volatile Organic Compounds							
1,1,1,2-Tetrachloroethane	5	ppb	ND	ND	ND	ND	ND
1,1,1-Trichloroethane	5	ppb	ND	ND	ND	ND	ND
1,1,2,2-Tetrachloroethane	5	ppb	ND	ND	ND	ND	ND
1,1,2-Trichloro-1,2,2-trifluoroethane (Freon 113)	5	ppb	ND	ND	ND	ND	ND
1,1,2-Trichloroethane	1	ppb	ND	ND	ND	ND	ND
1,1-Dichloroethane	5	ppb	ND	ND	ND	ND	ND
1,1-Dichloroethylene	5	ppb	ND	ND	ND	ND	ND
1,1-Dichloropropylene	5	ppb	ND	ND	ND	ND	ND
1,2,3-Trichlorobenzene	5	ppb	ND	ND	ND	ND	ND
1,2,3-Trichloropropane	0.04	ppb	ND	ND	ND	ND	ND
1,2,4,5-Tetramethylbenzene	NS	ppb	ND	ND	ND	ND	ND
1,2,4-Trichlorobenzene	5	ppb	ND	ND	ND	ND	ND
1,2,4-Trimethylbenzene	5	ppb	ND	ND	ND	ND	ND
1,2-Dibromo-3-chloropropane	0.04	ppb	ND	ND	ND	ND	ND
1,2-Dibromoethane	0.0006	ppb	ND	ND	ND	ND	ND
1,2-Dichlorobenzene	3	ppb	ND	ND	ND	ND	ND
1,2-Dichloroethane	0.6	ppb	ND	ND	ND	ND	ND
1,2-Dichloropropane	1	ppb	ND	ND	ND	ND	ND
1,3,5-Trimethylbenzene	5	ppb	ND	ND	ND	ND	ND
1,3-Dichlorobenzene	3	ppb	ND	ND	ND	ND	ND
1,3-Dichloropropane	5	ppb	ND	ND	ND	ND	ND
1,4-Dichlorobenzene	3	ppb	ND	ND	ND	ND	ND
2,2-Dichloropropane	5	ppb	ND	ND	ND	ND	ND
2-Butanone	50	ppb	ND	ND	ND	ND	ND
2-Chlorotoluene	5	ppb	ND	ND	ND	ND	ND
2-Hexanone	50	ppb	ND	ND	ND	ND	ND
4-Chlorotoluene	5	ppb	ND	ND	ND	ND	ND
4-Methyl-2-pentanone	NS	ppb	ND	ND	ND	ND	ND
Acetone	50	ppb	ND	3.27	ND	ND	ND

Table 5a. Volatile Organic Compounds in Groundwater
260 West 126th Street - New York, NY
BCP Site No. C231164

Sample ID:	NY-AWQS	Units	MW-1		MW-2		MW-3	MW-4	MW-5
Laboratory ID:			26A1069-01		26A1069-02		26A1069-03	26G0536-01	26G0536-02
Sampling Date:			1/22/2026		1/22/2026		1/22/2026	7/9/2026	7/9/2026
				Qual		Qual	Qual	Qual	Qual
Volatile Organic Compounds									
Acrolein	5	ppb	ND		ND		ND	ND	ND
Acrylonitrile	NS	ppb	ND		ND		ND	ND	ND
Benzene	1	ppb	ND		ND		ND	ND	ND
Bromobenzene	5	ppb	ND		ND		ND	ND	ND
Bromochloromethane	5	ppb	ND		ND		ND	ND	ND
Bromodichloromethane	50	ppb	0.25	J	ND		ND	ND	ND
Bromoform	50	ppb	ND		ND		ND	ND	ND
Bromomethane	5	ppb	ND		ND		ND	ND	ND
Carbon disulfide	NS	ppb	ND		ND		ND	ND	ND
Carbon tetrachloride	5	ppb	ND		ND		ND	ND	ND
Chlorobenzene	5	ppb	ND		ND		ND	ND	ND
Chloroethane	5	ppb	ND		ND		ND	ND	ND
Chloroform	7	ppb	1.96		3.35		0.66	0.82	0.88
Chloromethane	5	ppb	ND		ND		ND	ND	ND
cis-1,2-Dichloroethylene	5	ppb	ND		ND		ND	ND	ND
cis-1,3-Dichloropropylene	0.4	ppb	ND		ND		ND	ND	ND
Cyclohexane	NS	ppb	ND		ND		ND	ND	ND
Dibromochloromethane	50	ppb	ND		ND		ND	ND	ND
Dibromomethane	NS	ppb	ND		ND		ND	ND	ND
Dichlorodifluoromethane	5	ppb	ND		ND		ND	ND	ND
Ethyl Benzene	5	ppb	ND		ND		ND	ND	ND
Hexachlorobutadiene	0.5	ppb	ND		ND		ND	ND	ND
Isopropylbenzene	5	ppb	ND		ND		ND	ND	ND
Methyl acetate	NS	ppb	ND		ND		ND	ND	ND
Methyl tert-butyl ether (MTBE)	10	ppb	ND		ND		ND	ND	ND
Methylcyclohexane	NS	ppb	ND		ND		ND	ND	ND
Methylene chloride	5	ppb	ND		ND		ND	ND	ND
Naphthalene	10	ppb	0.26	JB	0.26	JB	ND	ND	ND
n-Butylbenzene	5	ppb	ND		ND		ND	ND	ND

Table 5a. Volatile Organic Compounds in Groundwater
260 West 126th Street - New York, NY
BCP Site No. C231164

Sample ID:	NY-AWQS	Units	MW-1		MW-2		MW-3		MW-4		MW-5	
Laboratory ID:			26A1069-01		26A1069-02		26A1069-03		26G0536-01		26G0536-02	
Sampling Date:			1/22/2026		1/22/2026		1/22/2026		7/9/2026		7/9/2026	
				Qual		Qual		Qual		Qual		Qual
Volatile Organic Compounds												
n-Propylbenzene	5	ppb	ND		ND		ND		ND		ND	
o-Xylene	5	ppb	ND		ND		ND		ND		ND	
p- & m- Xylenes	NS	ppb	ND		ND		ND		ND		ND	
p-Isopropyltoluene	5	ppb	ND		ND		ND		ND		ND	
sec-Butylbenzene	5	ppb	ND		ND		ND		ND		ND	
Styrene	5	ppb	ND		ND		ND		ND		ND	
tert-Butyl alcohol (TBA)	NS	ppb	ND		2.93		ND		ND		ND	
tert-Butylbenzene	5	ppb	ND		ND		ND		ND		ND	
Tetrachloroethylene	5	ppb	ND		0.24	J	0.39	J	0.5		0.59	
Toluene	5	ppb	ND		ND		ND		ND		ND	
trans-1,2-Dichloroethylene	5	ppb	ND		ND		ND		ND		ND	
trans-1,3-Dichloropropylene	0.4	ppb	ND		ND		ND		ND		ND	
Trichloroethylene	5	ppb	ND		ND		ND		0.16	J	0.18	J
Trichlorofluoromethane	5	ppb	ND		ND		ND		ND		ND	
Vinyl acetate	NS	ppb	ND		ND		ND		ND		ND	
Vinyl Chloride	2	ppb	ND		ND		ND		ND		ND	
Xylenes, Total	5	ppb	ND		ND		ND		ND		ND	

Notes:

Bold and shaded yellow value indicates concentration exceeds NY-AWQS

NY-AWQS = NYSDEC Technical and Operational Guidance Series (TOGS) 1.1.1 Class GA Ambient Water Quality Standards

J = Estimated value

B = Analyte detected in the associated blank sample

ND = Not detected

NS = No standard

ppb = parts per billion

Table 5a. Volatile Organic Compounds in Groundwater
260 West 126th Street - New York, NY
BCP Site No. C231164

Sample ID:	NY-AWQS	Units	MW-6		MW-6_DUP		FB		TB		Trip Blank	
Laboratory ID:			26A1069-04		26A1069-05		26A1069-06		26A1069-07		26G0536-03	
Sampling Date:			1/22/2026		1/22/2026		1/22/2026		1/22/2026		7/9/2026	
				Qual		Qual		Qual		Qual		Qual
Volatile Organic Compounds												
1,1,1,2-Tetrachloroethane	5	ppb	ND		ND		ND		ND		ND	
1,1,1-Trichloroethane	5	ppb	ND		ND		ND		ND		ND	
1,1,2,2-Tetrachloroethane	5	ppb	ND		ND		ND		ND		ND	
1,1,2-Trichloro-1,2,2-trifluoroethane (Freon 113)	5	ppb	ND		ND		ND		ND		ND	
1,1,2-Trichloroethane	1	ppb	ND		ND		ND		ND		ND	
1,1-Dichloroethane	5	ppb	ND		ND		ND		ND		ND	
1,1-Dichloroethylene	5	ppb	ND		ND		ND		ND		ND	
1,1-Dichloropropylene	5	ppb	ND		ND		ND		ND		ND	
1,2,3-Trichlorobenzene	5	ppb	ND		ND		ND		ND		ND	
1,2,3-Trichloropropane	0.04	ppb	ND		ND		ND		ND		ND	
1,2,4,5-Tetramethylbenzene	NS	ppb	ND		ND		ND		ND		ND	
1,2,4-Trichlorobenzene	5	ppb	ND		ND		ND		ND		ND	
1,2,4-Trimethylbenzene	5	ppb	ND		ND		ND		ND		ND	
1,2-Dibromo-3-chloropropane	0.04	ppb	ND		ND		ND		ND		ND	
1,2-Dibromoethane	0.0006	ppb	ND		ND		ND		ND		ND	
1,2-Dichlorobenzene	3	ppb	ND		ND		ND		ND		ND	
1,2-Dichloroethane	0.6	ppb	ND		ND		ND		ND		ND	
1,2-Dichloropropane	1	ppb	ND		ND		ND		ND		ND	
1,3,5-Trimethylbenzene	5	ppb	ND		ND		ND		ND		ND	
1,3-Dichlorobenzene	3	ppb	ND		ND		ND		ND		ND	
1,3-Dichloropropane	5	ppb	ND		ND		ND		ND		ND	
1,4-Dichlorobenzene	3	ppb	ND		ND		ND		ND		ND	
2,2-Dichloropropane	5	ppb	ND		ND		ND		ND		ND	
2-Butanone	50	ppb	ND		ND		ND		ND		ND	
2-Chlorotoluene	5	ppb	ND		ND		ND		ND		ND	
2-Hexanone	50	ppb	ND		ND		ND		ND		ND	
4-Chlorotoluene	5	ppb	ND		ND		ND		ND		ND	
4-Methyl-2-pentanone	NS	ppb	ND		ND		ND		ND		ND	
Acetone	50	ppb	1.46	J	1.38	J	1.41	J	ND		ND	

Table 5a. Volatile Organic Compounds in Groundwater
260 West 126th Street - New York, NY
BCP Site No. C231164

Sample ID:	NY-AWQS	Units	MW-6	MW-6_DUP	FB	TB	Trip Blank
Laboratory ID:			26A1069-04	26A1069-05	26A1069-06	26A1069-07	26G0536-03
Sampling Date:			1/22/2026	1/22/2026	1/22/2026	1/22/2026	7/9/2026
			Qual	Qual	Qual	Qual	Qual
Volatile Organic Compounds							
Acrolein	5	ppb	ND	ND	ND	ND	ND
Acrylonitrile	NS	ppb	ND	ND	ND	ND	ND
Benzene	1	ppb	ND	ND	ND	ND	ND
Bromobenzene	5	ppb	ND	ND	ND	ND	ND
Bromochloromethane	5	ppb	ND	ND	ND	ND	ND
Bromodichloromethane	50	ppb	ND	ND	0.48 J	ND	ND
Bromoform	50	ppb	ND	ND	ND	ND	ND
Bromomethane	5	ppb	ND	ND	ND	ND	ND
Carbon disulfide	NS	ppb	ND	ND	ND	ND	ND
Carbon tetrachloride	5	ppb	ND	ND	ND	ND	ND
Chlorobenzene	5	ppb	ND	ND	ND	ND	ND
Chloroethane	5	ppb	ND	ND	ND	ND	ND
Chloroform	7	ppb	0.91	0.95	**24.5**	ND	ND
Chloromethane	5	ppb	ND	ND	ND	ND	ND
cis-1,2-Dichloroethylene	5	ppb	ND	ND	ND	ND	ND
cis-1,3-Dichloropropylene	0.4	ppb	ND	ND	ND	ND	ND
Cyclohexane	NS	ppb	ND	ND	ND	ND	ND
Dibromochloromethane	50	ppb	ND	ND	ND	ND	ND
Dibromomethane	NS	ppb	ND	ND	ND	ND	ND
Dichlorodifluoromethane	5	ppb	ND	ND	ND	ND	ND
Ethyl Benzene	5	ppb	ND	ND	ND	ND	ND
Hexachlorobutadiene	0.5	ppb	ND	ND	ND	ND	ND
Isopropylbenzene	5	ppb	ND	ND	ND	ND	ND
Methyl acetate	NS	ppb	ND	ND	ND	ND	ND
Methyl tert-butyl ether (MTBE)	10	ppb	ND	ND	ND	ND	ND
Methylcyclohexane	NS	ppb	ND	ND	ND	ND	ND
Methylene chloride	5	ppb	ND	ND	ND	ND	ND
Naphthalene	10	ppb	ND	ND	0.31 JB	0.36 JB	ND
n-Butylbenzene	5	ppb	ND	ND	ND	ND	ND

Table 5a. Volatile Organic Compounds in Groundwater
260 West 126th Street - New York, NY
BCP Site No. C231164

Sample ID:	NY-AWQS	Units	MW-6		MW-6_DUP		FB	TB	Trip Blank
Laboratory ID:			26A1069-04		26A1069-05		26A1069-06	26A1069-07	26G0536-03
Sampling Date:			1/22/2026		1/22/2026		1/22/2026	1/22/2026	7/9/2026
				Qual		Qual	Qual	Qual	Qual
Volatile Organic Compounds									
n-Propylbenzene	5	ppb	ND		ND		ND	ND	ND
o-Xylene	5	ppb	ND		ND		ND	ND	ND
p- & m- Xylenes	NS	ppb	ND		ND		ND	ND	ND
p-Isopropyltoluene	5	ppb	ND		ND		ND	ND	ND
sec-Butylbenzene	5	ppb	ND		ND		ND	ND	ND
Styrene	5	ppb	ND		ND		ND	ND	ND
tert-Butyl alcohol (TBA)	NS	ppb	6.54		ND		ND	ND	ND
tert-Butylbenzene	5	ppb	ND		ND		ND	ND	ND
Tetrachloroethylene	5	ppb	0.38	J	0.42	J	ND	ND	ND
Toluene	5	ppb	ND		ND		ND	ND	ND
trans-1,2-Dichloroethylene	5	ppb	ND		ND		ND	ND	ND
trans-1,3-Dichloropropylene	0.4	ppb	ND		ND		ND	ND	ND
Trichloroethylene	5	ppb	ND		ND		ND	ND	ND
Trichlorofluoromethane	5	ppb	ND		ND		ND	ND	ND
Vinyl acetate	NS	ppb	ND		ND		ND	ND	ND
Vinyl Chloride	2	ppb	ND		ND		ND	ND	ND
Xylenes, Total	5	ppb	ND		ND		ND	ND	ND

Notes:

Bold and shaded yellow value indicates concentration exceeds NY-AWQS

NY-AWQS = NYSDEC Technical and Operational Guidance Series (TOGS) 1.1.1 Class GA Ambient Water Quality Standards

J = Estimated value

B = Analyte detected in the associated blank sample

ND = Not detected

NS = No standard

ppb = parts per billion

Table 5b. Semivolatile Organic Compounds in Groundwater
260 West 126th Street - New York, NY
BCP Site No. C231164

Sample ID:	NY-AWQS	Units	MW-1	MW-2	MW-3	MW-4	MW-5
Laboratory ID:			26A1069-01	26A1069-02	26A1069-03	26G0536-01	26G0536-02
Sampling Date:			1/22/2026	1/22/2026	1/22/2026	7/9/2026	7/9/2026
			Qual	Qual	Qual	Qual	Qual
Semivolatile Organic Compounds							
1,1-Biphenyl	NS	ppb	ND	ND	ND	ND	ND
1,2,4,5-Tetrachlorobenzene	NS	ppb	ND	ND	ND	ND	ND
1,2,4-Trichlorobenzene	5	ppb	ND	ND	ND	ND	ND
1,2-Dichlorobenzene	3	ppb	ND	ND	ND	ND	ND
1,2-Diphenylhydrazine (as Azobenzene)	NS	ppb	ND	ND	ND	ND	ND
1,3-Dichlorobenzene	3	ppb	ND	ND	ND	ND	ND
1,4-Dichlorobenzene	3	ppb	ND	ND	ND	ND	ND
2,3,4,6-Tetrachlorophenol	NS	ppb	ND	ND	ND	ND	ND
2,4,5-Trichlorophenol	1	ppb	ND	ND	ND	ND	ND
2,4,6-Trichlorophenol	1	ppb	ND	ND	ND	ND	ND
2,4-Dichlorophenol	5	ppb	ND	ND	ND	ND	ND
2,4-Dimethylphenol	50	ppb	ND	ND	ND	ND	ND
2,4-Dinitrophenol	10	ppb	ND	ND	ND	ND	ND
2,4-Dinitrotoluene	5	ppb	ND	ND	ND	ND	ND
2,6-Dinitrotoluene	5	ppb	ND	ND	ND	ND	ND
2-Chloronaphthalene	10	ppb	ND	ND	ND	ND	ND
2-Chlorophenol	1	ppb	ND	ND	ND	ND	ND
2-Methylnaphthalene	NS	ppb	ND	ND	ND	ND	ND
2-Methylphenol	1	ppb	ND	ND	ND	ND	ND
2-Nitroaniline	5	ppb	ND	ND	ND	ND	ND
2-Nitrophenol	1	ppb	ND	ND	ND	ND	ND
3- & 4-Methylphenols	NS	ppb	ND	ND	ND	ND	ND
3,3-Dichlorobenzidine	5	ppb	ND	ND	ND	ND	ND
3-Nitroaniline	5	ppb	ND	ND	ND	ND	ND
4,6-Dinitro-2-methylphenol	NS	ppb	ND	ND	ND	ND	ND
4-Bromophenyl phenyl ether	NS	ppb	ND	ND	ND	ND	ND
4-Chloro-3-methylphenol	1	ppb	ND	ND	ND	ND	ND
4-Chloroaniline	5	ppb	ND	ND	ND	ND	ND

Table 5b. Semivolatile Organic Compounds in Groundwater
260 West 126th Street - New York, NY
BCP Site No. C231164

Sample ID:	NY-AWQS	Units	MW-1	MW-2	MW-3	MW-4	MW-5
Laboratory ID:			26A1069-01	26A1069-02	26A1069-03	26G0536-01	26G0536-02
Sampling Date:			1/22/2026	1/22/2026	1/22/2026	7/9/2026	7/9/2026
			Qual	Qual	Qual	Qual	Qual
Semivolatile Organic Compounds							
4-Chlorophenyl phenyl ether	NS	ppb	ND	ND	ND	ND	ND
4-Nitroaniline	5	ppb	ND	ND	ND	ND	ND
4-Nitrophenol	1	ppb	ND	ND	ND	ND	ND
Acetophenone	NS	ppb	ND	ND	ND	ND	ND
Aniline	5	ppb	ND	ND	ND	ND	ND
Benzaldehyde	NS	ppb	ND	ND	ND	ND	ND
Benzidine	NS	ppb	ND	ND	ND	ND	ND
Benzoic acid	NS	ppb	ND	ND	ND	ND	ND
Benzyl alcohol	NS	ppb	ND	ND	ND	ND	ND
Benzyl butyl phthalate	50	ppb	ND	ND	ND	ND	ND
Bis(2-chloroethoxy)methane	5	ppb	ND	ND	ND	ND	ND
Bis(2-chloroethyl)ether	1	ppb	ND	ND	ND	ND	ND
Bis(2-chloroisopropyl)ether	5	ppb	ND	ND	ND	ND	ND
Caprolactam	NS	ppb	ND	ND	ND	ND	ND
Carbazole	NS	ppb	ND	ND	ND	ND	ND
Dibenzofuran	NS	ppb	ND	ND	ND	ND	ND
Diethyl phthalate	50	ppb	ND	ND	ND	ND	ND
Dimethyl phthalate	50	ppb	ND	ND	ND	ND	ND
Di-n-butyl phthalate	50	ppb	ND	ND	ND	ND	ND
Di-n-octyl phthalate	50	ppb	ND	ND	ND	ND	ND
Hexachlorocyclopentadiene	5	ppb	ND	ND	ND	ND	ND
Isophorone	50	ppb	ND	ND	ND	ND	ND
N-nitroso-di-n-propylamine	NS	ppb	ND	ND	ND	ND	ND
N-Nitrosodiphenylamine	50	ppb	ND	ND	ND	ND	ND
Phenol	1	ppb	ND	ND	ND	ND	ND
Pyridine	50	ppb	ND	ND	ND	ND	ND
Acenaphthene	20	ppb	ND	ND	ND	ND	ND
Acenaphthylene	NS	ppb	ND	ND	ND	ND	ND

Table 5b. Semivolatile Organic Compounds in Groundwater
260 West 126th Street - New York, NY
BCP Site No. C231164

Sample ID:	NY-AWQS	Units	MW-1	MW-2	MW-3	MW-4	MW-5
Laboratory ID:			26A1069-01	26A1069-02	26A1069-03	26G0536-01	26G0536-02
Sampling Date:			1/22/2026	1/22/2026	1/22/2026	7/9/2026	7/9/2026
			Qual	Qual	Qual	Qual	Qual
Semivolatile Organic Compounds							
Anthracene	50	ppb	ND	ND	ND	ND	ND
Atrazine	NS	ppb	ND	ND	ND	ND	ND
Benzo(a)anthracene	0.002	ppb	ND	ND	ND	ND	ND
Benzo(a)pyrene	0	ppb	ND	ND	ND	ND	ND
Benzo(b)fluoranthene	0.002	ppb	ND	ND	ND	ND	ND
Benzo(g,h,i)perylene	NS	ppb	ND	ND	ND	ND	ND
Benzo(k)fluoranthene	0.002	ppb	ND	ND	ND	ND	ND
Bis(2-ethylhexyl)phthalate	5	ppb	ND	0.583	ND	ND	ND
Chrysene	0.002	ppb	ND	ND	ND	ND	ND
Dibenzo(a,h)anthracene	NS	ppb	ND	ND	ND	ND	ND
Fluoranthene	50	ppb	0.0609	0.0614	0.0614	ND	ND
Fluorene	50	ppb	ND	ND	ND	ND	ND
Hexachlorobenzene	0.04	ppb	ND	ND	ND	ND	ND
Hexachlorobutadiene	0.5	ppb	ND	ND	ND	ND	ND
Hexachloroethane	5	ppb	ND	ND	ND	ND	ND
Indeno(1,2,3-cd)pyrene	0.002	ppb	ND	ND	ND	ND	ND
Naphthalene	10	ppb	ND	ND	ND	ND	ND
Nitrobenzene	0.4	ppb	ND	ND	ND	ND	ND
N-Nitrosodimethylamine	NS	ppb	ND	ND	ND	ND	ND
Pentachlorophenol	1	ppb	ND	ND	ND	ND	ND
Phenanthrene	50	ppb	0.102	0.115	0.104	ND	ND
Pyrene	50	ppb	0.0588	0.0642	0.0608	ND	ND

Notes:

Bold and shaded yellow value indicates concentration exceeds NY-AWQS

NY-AWQS = NYSDEC Technical and Operational Guidance Series (TOGS) 1.1.1 Class GA Ambient Water Quality Standards

ND = Not detected

Table 5b. Semivolatile Organic Compounds in Groundwater
260 West 126th Street - New York, NY
BCP Site No. C231164

Sample ID:	NY-AWQS	Units	MW-1	MW-2	MW-3	MW-4	MW-5
Laboratory ID:			26A1069-01	26A1069-02	26A1069-03	26G0536-01	26G0536-02
Sampling Date:			1/22/2026	1/22/2026	1/22/2026	7/9/2026	7/9/2026
			Qual	Qual	Qual	Qual	Qual
Semivolatile Organic Compounds							

NS = No standard

ppb = parts per billion

Table 5b. Semivolatile Organic Compounds in Groundwater
260 West 126th Street - New York, NY
BCP Site No. C231164

Sample ID:	NY-AWQS	Units	MW-6	MW-6_DUP	FB
Laboratory ID:			26A1069-04	26A1069-05	26A1069-06
Sampling Date:			1/22/2026	1/22/2026	1/22/2026
			Qual	Qual	Qual
Semivolatile Organic Compounds					
1,1-Biphenyl	NS	ppb	ND	ND	ND
1,2,4,5-Tetrachlorobenzene	NS	ppb	ND	ND	ND
1,2,4-Trichlorobenzene	5	ppb	ND	ND	ND
1,2-Dichlorobenzene	3	ppb	ND	ND	ND
1,2-Diphenylhydrazine (as Azobenzene)	NS	ppb	ND	ND	ND
1,3-Dichlorobenzene	3	ppb	ND	ND	ND
1,4-Dichlorobenzene	3	ppb	ND	ND	ND
2,3,4,6-Tetrachlorophenol	NS	ppb	ND	ND	ND
2,4,5-Trichlorophenol	1	ppb	ND	ND	ND
2,4,6-Trichlorophenol	1	ppb	ND	ND	ND
2,4-Dichlorophenol	5	ppb	ND	ND	ND
2,4-Dimethylphenol	50	ppb	ND	ND	ND
2,4-Dinitrophenol	10	ppb	ND	ND	ND
2,4-Dinitrotoluene	5	ppb	ND	ND	ND
2,6-Dinitrotoluene	5	ppb	ND	ND	ND
2-Chloronaphthalene	10	ppb	ND	ND	ND
2-Chlorophenol	1	ppb	ND	ND	ND
2-Methylnaphthalene	NS	ppb	ND	ND	ND
2-Methylphenol	1	ppb	ND	ND	ND
2-Nitroaniline	5	ppb	ND	ND	ND
2-Nitrophenol	1	ppb	ND	ND	ND
3- & 4-Methylphenols	NS	ppb	ND	ND	ND
3,3-Dichlorobenzidine	5	ppb	ND	ND	ND
3-Nitroaniline	5	ppb	ND	ND	ND
4,6-Dinitro-2-methylphenol	NS	ppb	ND	ND	ND
4-Bromophenyl phenyl ether	NS	ppb	ND	ND	ND
4-Chloro-3-methylphenol	1	ppb	ND	ND	ND
4-Chloroaniline	5	ppb	ND	ND	ND

Table 5b. Semivolatile Organic Compounds in Groundwater
260 West 126th Street - New York, NY
BCP Site No. C231164

Sample ID:	NY-AWQS	Units	MW-6	MW-6_DUP	FB
Laboratory ID:			26A1069-04	26A1069-05	26A1069-06
Sampling Date:			1/22/2026	1/22/2026	1/22/2026
			Qual	Qual	Qual
Semivolatile Organic Compounds					
4-Chlorophenyl phenyl ether	NS	ppb	ND	ND	ND
4-Nitroaniline	5	ppb	ND	ND	ND
4-Nitrophenol	1	ppb	ND	ND	ND
Acetophenone	NS	ppb	ND	ND	ND
Aniline	5	ppb	ND	ND	ND
Benzaldehyde	NS	ppb	ND	ND	ND
Benzidine	NS	ppb	ND	ND	ND
Benzoic acid	NS	ppb	ND	ND	ND
Benzyl alcohol	NS	ppb	ND	ND	ND
Benzyl butyl phthalate	50	ppb	ND	ND	ND
Bis(2-chloroethoxy)methane	5	ppb	ND	ND	ND
Bis(2-chloroethyl)ether	1	ppb	ND	ND	ND
Bis(2-chloroisopropyl)ether	5	ppb	ND	ND	ND
Caprolactam	NS	ppb	ND	ND	ND
Carbazole	NS	ppb	ND	ND	ND
Dibenzofuran	NS	ppb	ND	ND	ND
Diethyl phthalate	50	ppb	ND	ND	ND
Dimethyl phthalate	50	ppb	ND	ND	ND
Di-n-butyl phthalate	50	ppb	ND	ND	ND
Di-n-octyl phthalate	50	ppb	ND	ND	ND
Hexachlorocyclopentadiene	5	ppb	ND	ND	ND
Isophorone	50	ppb	ND	ND	ND
N-nitroso-di-n-propylamine	NS	ppb	ND	ND	ND
N-Nitrosodiphenylamine	50	ppb	ND	ND	ND
Phenol	1	ppb	ND	ND	ND
Pyridine	50	ppb	ND	ND	ND
Acenaphthene	20	ppb	ND	ND	ND
Acenaphthylene	NS	ppb	ND	ND	ND

Table 5b. Semivolatile Organic Compounds in Groundwater
260 West 126th Street - New York, NY
BCP Site No. C231164

Sample ID:	NY-AWQS	Units	MW-6	MW-6_DUP	FB
Laboratory ID:			26A1069-04	26A1069-05	26A1069-06
Sampling Date:			1/22/2026	1/22/2026	1/22/2026
			Qual	Qual	Qual
Semivolatile Organic Compounds					
Anthracene	50	ppb	ND	ND	ND
Atrazine	NS	ppb	ND	ND	ND
Benzo(a)anthracene	0.002	ppb	ND	ND	ND
Benzo(a)pyrene	0	ppb	ND	ND	ND
Benzo(b)fluoranthene	0.002	ppb	ND	ND	ND
Benzo(g,h,i)perylene	NS	ppb	ND	ND	ND
Benzo(k)fluoranthene	0.002	ppb	ND	ND	ND
Bis(2-ethylhexyl)phthalate	5	ppb	ND	ND	ND
Chrysene	0.002	ppb	ND	ND	ND
Dibenzo(a,h)anthracene	NS	ppb	ND	ND	ND
Fluoranthene	50	ppb	0.0724	0.0636	ND
Fluorene	50	ppb	ND	ND	ND
Hexachlorobenzene	0.04	ppb	ND	ND	ND
Hexachlorobutadiene	0.5	ppb	ND	ND	ND
Hexachloroethane	5	ppb	ND	ND	ND
Indeno(1,2,3-cd)pyrene	0.002	ppb	ND	ND	ND
Naphthalene	10	ppb	ND	ND	ND
Nitrobenzene	0.4	ppb	ND	ND	ND
N-Nitrosodimethylamine	NS	ppb	ND	ND	ND
Pentachlorophenol	1	ppb	ND	ND	ND
Phenanthrene	50	ppb	0.13	0.117	ND
Pyrene	50	ppb	0.0751	0.0668	ND

Notes:

Bold and shaded yellow value indicates concentration exceeds NY-AWQS

NY-AWQS = NYSDEC Technical and Operational Guidance Series (TOGS) 1.1.1 Class GA Ambient Water Quality Standards

ND = Not detected

Table 5b. Semivolatile Organic Compounds in Groundwater
260 West 126th Street - New York, NY
BCP Site No. C231164

Sample ID:	NY-AWQS	Units	MW-6	MW-6_DUP	FB
Laboratory ID:			26A1069-04	26A1069-05	26A1069-06
Sampling Date:			1/22/2026	1/22/2026	1/22/2026
			Qual	Qual	Qual
Semivolatile Organic Compounds					

NS = No standard

ppb = parts per billion

Table 5c. Metals in Groundwater
260 West 126th Street - New York, NY
BCP Site No. C231164

Sample ID:	NY-AWQS	Units	MW-1	MW-2	MW-3	MW-4	MW-5
Laboratory ID:			26A1069-01	26A1069-02	26A1069-03	26G0536-01	26G0536-02
Sampling Date:			1/22/2026	1/22/2026	1/22/2026	7/9/2026	7/9/2026
			Qual	Qual	Qual	Qual	Qual
Total Metals							
Aluminum	NS	ppb	ND	ND	ND	ND	ND
Barium	1,000	ppb	51.4	31.3	ND	ND	ND
Calcium	NS	ppb	45400	46100	43900	15900	19000
Chromium	50	ppb	ND	ND	ND	ND	ND
Cobalt	NS	ppb	ND	ND	ND	ND	ND
Copper	200	ppb	ND	ND	ND	ND	ND
Iron	300	ppb	ND	ND	ND	ND	ND
Lead	25	ppb	ND	ND	ND	ND	ND
Magnesium	35,000	ppb	6220	5650	3690	3330	4200
Manganese	300	ppb	ND	**353**	7.22	37	66.4
Nickel	100	ppb	ND	ND	ND	ND	ND
Potassium	NS	ppb	4340	5120	4780	3890	3840
Selenium	10	ppb	ND	ND	ND	ND	ND
Silver	50	ppb	ND	ND	ND	ND	ND
Sodium	20,000	ppb	**69200**	**66200**	**75900**	**63500**	**61500**
Vanadium	NS	ppb	ND	ND	ND	ND	ND
Zinc	2,000	ppb	ND	ND	ND	ND	ND
Antimony	3	ppb	ND	ND	ND	ND	ND
Arsenic	25	ppb	ND	ND	ND	ND	ND
Beryllium	3	ppb	ND	ND	ND	ND	ND
Cadmium	5	ppb	ND	ND	ND	ND	ND
Thallium	0.5	ppb	ND	ND	ND	ND	ND
Mercury	0.7	ppb	ND	ND	ND	ND	ND
Total Cyanide	200	ppb	ND	ND	ND	ND	ND
Dissolved Metals							
Aluminum	NS	ppb	ND	ND	ND	ND	ND
Barium	1,000	ppb	50.7	32.8	28.4	ND	ND
Calcium	NS	ppb	45600	45600	42700	15900	18400

Table 5c. Metals in Groundwater
260 West 126th Street - New York, NY
BCP Site No. C231164

Sample ID:	NY-AWQS	Units	MW-1	MW-2	MW-3	MW-4	MW-5
Laboratory ID:			26A1069-01	26A1069-02	26A1069-03	26G0536-01	26G0536-02
Sampling Date:			1/22/2026	1/22/2026	1/22/2026	7/9/2026	7/9/2026
			Qual	Qual	Qual	Qual	Qual
Chromium	50	ppb	ND	ND	ND	ND	ND
Cobalt	NS	ppb	ND	ND	ND	ND	ND
Copper	200	ppb	ND	ND	ND	ND	ND
Iron	300	ppb	ND	ND	ND	ND	ND
Lead	25	ppb	ND	ND	ND	ND	ND
Magnesium	35,000	ppb	6220	5600	3640	3250	4170
Manganese	300	ppb	ND	**352**	ND	16.7	61.2
Nickel	100	ppb	ND	ND	ND	ND	ND
Potassium	NS	ppb	4250	5000	4630	3930	3820
Selenium	10	ppb	ND	ND	ND	ND	ND
Silver	50	ppb	ND	ND	ND	ND	ND
Sodium	20,000	ppb	**67300**	**63900**	**72800**	**62000**	**60500**
Vanadium	NS	ppb	ND	ND	ND	ND	ND
Zinc	2,000	ppb	ND	ND	ND	ND	ND
Antimony	3	ppb	ND	ND	ND	ND	ND
Arsenic	25	ppb	ND	ND	ND	ND	ND
Beryllium	3	ppb	ND	ND	ND	ND	ND
Cadmium	5	ppb	ND	ND	ND	ND	ND
Thallium	0.5	ppb	ND	ND	ND	ND	ND
Mercury	0.7	ppb	ND	ND	ND	ND	ND
Chromium							
Chromium, Hexavalent	50	ppb	ND	ND	ND	ND	ND
Chromium, Trivalent	NS	ppb	ND	ND	ND	ND	ND

Notes:

Bold and shaded yellow value indicates concentration exceeds NY-AWQS

NY-AWQS = NYSDEC Technical and Operational Guidance Series (TOGS) 1.1.1 Class GA Ambient Water Quality Standards

ND = Not detected

Table 5c. Metals in Groundwater
260 West 126th Street - New York, NY
BCP Site No. C231164

Sample ID:	NY-AWQS	Units	MW-1	MW-2	MW-3	MW-4	MW-5
Laboratory ID:			26A1069-01	26A1069-02	26A1069-03	26G0536-01	26G0536-02
Sampling Date:			1/22/2026	1/22/2026	1/22/2026	7/9/2026	7/9/2026
			Qual	Qual	Qual	Qual	Qual

NS = No standard

ppb = parts per billion

Table 5c. Metals in Groundwater
260 West 126th Street - New York, NY
BCP Site No. C231164

Sample ID:	NY-AWQS	Units	MW-6	MW-6_DUP	FB
Laboratory ID:			26A1069-04	26A1069-05	26A1069-06
Sampling Date:			1/22/2026	1/22/2026	1/22/2026
			Qual	Qual	Qual
Total Metals					
Aluminum	NS	ppb	ND	ND	ND
Barium	1,000	ppb	ND	ND	ND
Calcium	NS	ppb	22500	22500	ND
Chromium	50	ppb	ND	ND	ND
Cobalt	NS	ppb	ND	ND	ND
Copper	200	ppb	ND	ND	ND
Iron	300	ppb	ND	ND	ND
Lead	25	ppb	ND	ND	ND
Magnesium	35,000	ppb	4640	4650	ND
Manganese	300	ppb	**567**	**540**	ND
Nickel	100	ppb	ND	ND	ND
Potassium	NS	ppb	4680	4560	ND
Selenium	10	ppb	ND	ND	ND
Silver	50	ppb	ND	ND	ND
Sodium	20,000	ppb	**82300**	**82500**	ND
Vanadium	NS	ppb	ND	ND	ND
Zinc	2,000	ppb	ND	ND	ND
Antimony	3	ppb	ND	ND	ND
Arsenic	25	ppb	ND	ND	ND
Beryllium	3	ppb	ND	ND	ND
Cadmium	5	ppb	ND	ND	ND
Thallium	0.5	ppb	ND	ND	ND
Mercury	0.7	ppb	ND	ND	ND
Total Cyanide	200	ppb	ND	ND	ND
Dissolved Metals					
Aluminum	NS	ppb	ND	ND	ND
Barium	1,000	ppb	ND	ND	ND
Calcium	NS	ppb	22900	22300	ND

Table 5c. Metals in Groundwater
260 West 126th Street - New York, NY
BCP Site No. C231164

Sample ID:	**NY-AWQS**	**Units**	**MW-6**	**MW-6_DUP**	**FB**
Laboratory ID:			**26A1069-04**	**26A1069-05**	**26A1069-06**
Sampling Date:			**1/22/2026**	**1/22/2026**	**1/22/2026**
			Qual	**Qual**	**Qual**
Chromium	50	ppb	ND	ND	ND
Cobalt	NS	ppb	ND	ND	ND
Copper	200	ppb	ND	ND	ND
Iron	300	ppb	ND	ND	ND
Lead	25	ppb	ND	ND	ND
Magnesium	35,000	ppb	4730	4640	82.4
Manganese	300	ppb	**574**	**551**	ND
Nickel	100	ppb	ND	ND	ND
Potassium	NS	ppb	4560	4490	ND
Selenium	10	ppb	ND	ND	ND
Silver	50	ppb	ND	ND	ND
Sodium	20,000	ppb	**82000**	**80300**	ND
Vanadium	NS	ppb	ND	ND	ND
Zinc	2,000	ppb	ND	ND	ND
Antimony	3	ppb	ND	ND	ND
Arsenic	25	ppb	ND	ND	ND
Beryllium	3	ppb	ND	ND	ND
Cadmium	5	ppb	ND	ND	ND
Thallium	0.5	ppb	ND	ND	ND
Mercury	0.7	ppb	ND	ND	ND
Chromium					
Chromium, Hexavalent	50	ppb	ND	ND	ND
Chromium, Trivalent	NS	ppb	ND	ND	ND

Notes:

Bold and shaded yellow value indicates concentration exceeds NY-AWQS

NY-AWQS = NYSDEC Technical and Operational Guidance Series (TOGS) 1.1.1 Class GA Ambient Water Quality Standards

ND = Not detected

Table 5c. Metals in Groundwater
260 West 126th Street - New York, NY
BCP Site No. C231164

Sample ID:	NY-AWQS	Units	MW-6	MW-6_DUP	FB
Laboratory ID:			26A1069-04	26A1069-05	26A1069-06
Sampling Date:			1/22/2026	1/22/2026	1/22/2026
			Qual	Qual	Qual

NS = No standard

ppb = parts per billion

Table 5d. Pesticides, Herbicides, and Polychlorinated Biphenyls in Groundwater
260 West 126th Street - New York, NY
BCP Site No. C231164

Sample ID:	NY-AWQS	Units	MW-1	MW-2	MW-3	MW-4	MW-5
Laboratory ID:			26A1069-01	26A1069-02	26A1069-03	26G0536-01	26G0536-02
Sampling Date:			1/22/2026	1/22/2026	1/22/2026	7/9/2026	7/9/2026
			Qual	Qual	Qual	Qual	Qual
Pesticides							
4,4'-DDD	0.3	ppb	ND	ND	ND	ND	ND
4,4'-DDE	0.2	ppb	ND	ND	ND	ND	ND
4,4'-DDT	0.2	ppb	ND	ND	ND	ND	ND
Aldrin	NS	ppb	ND	ND	ND	ND	ND
alpha-BHC	0.01	ppb	ND	ND	ND	ND	ND
alpha-Chlordane	NS	ppb	ND	ND	ND	ND	ND
beta-BHC	0.04	ppb	ND	ND	ND	ND	ND
Chlordane, total	0.05	ppb	ND	ND	ND	ND	ND
delta-BHC	0.04	ppb	ND	ND	ND	ND	ND
Dieldrin	0.004	ppb	ND	ND	ND	ND	ND
Endosulfan I	NS	ppb	ND	ND	ND	ND	ND
Endosulfan II	NS	ppb	ND	ND	ND	ND	ND
Endosulfan sulfate	NS	ppb	ND	ND	ND	ND	ND
Endrin	NS	ppb	ND	ND	ND	ND	ND
Endrin aldehyde	5	ppb	ND	ND	ND	ND	ND
Endrin ketone	5	ppb	ND	ND	ND	ND	ND
gamma-BHC (Lindane)	0.05	ppb	ND	ND	ND	ND	ND
gamma-Chlordane	NS	ppb	ND	ND	ND	ND	ND
Heptachlor	0.04	ppb	ND	ND	ND	ND	ND
Heptachlor epoxide	0.03	ppb	ND	ND	ND	ND	ND
Methoxychlor	35	ppb	ND	ND	ND	ND	ND
Toxaphene	0.06	ppb	ND	ND	ND	ND	ND
Herbicides							
2,4,5-T	35	ppb	ND	ND	ND	ND	ND
2,4,5-TP (Silvex)	0.26	ppb	ND	ND	ND	ND	ND
2,4-D	50	ppb	ND	ND	ND	ND	ND
Polychlorinated Biphenyls							
Aroclor 1016	NS	ppb	ND	ND	ND	ND	ND

Table 5d. Pesticides, Herbicides, and Polychlorinated Biphenyls in Groundwater
260 West 126th Street - New York, NY
BCP Site No. C231164

Sample ID:	NY-AWQS	Units	MW-1		MW-2		MW-3		MW-4		MW-5	
Laboratory ID:			26A1069-01		26A1069-02		26A1069-03		26G0536-01		26G0536-02	
Sampling Date:			1/22/2026		1/22/2026		1/22/2026		7/9/2026		7/9/2026	
				Qual		Qual		Qual		Qual		Qual
Aroclor 1221	NS	ppb	ND		ND		ND		ND		ND	
Aroclor 1232	NS	ppb	ND		ND		ND		ND		ND	
Aroclor 1242	NS	ppb	ND		ND		ND		ND		ND	
Aroclor 1248	NS	ppb	ND		ND		ND		ND		ND	
Aroclor 1254	NS	ppb	ND		ND		ND		ND		ND	
Aroclor 1260	NS	ppb	ND		ND		ND		ND		ND	
Aroclor 1262	NS	ppb	ND		ND		ND		ND		ND	
Aroclor 1268	NS	ppb	ND		ND		ND		ND		ND	
Total PCBs	0.09	ppb	ND		ND		ND		ND		ND	

Notes:

Bold and shaded yellow value indicates concentration exceeds NY-AWQS

NY-AWQS = NYSDEC Technical and Operational Guidance Series (TOGS) 1.1.1 Class GA Ambient Water Quality Standards

ND = Not detected

NS = No standard

ppb = parts per billion

Table 5d. Pesticides, Herbicides, and Polychlorinated Biphenyls in Groundwater
260 West 126th Street - New York, NY
BCP Site No. C231164

Sample ID:	NY-AWQS	Units	MW-6	MW-6_DUP	FB
Laboratory ID:			26A1069-04	26A1069-05	26A1069-06
Sampling Date:			1/22/2026	1/22/2026	1/22/2026
			Qual	Qual	Qual
Pesticides					
4,4'-DDD	0.3	ppb	ND	ND	ND
4,4'-DDE	0.2	ppb	ND	ND	ND
4,4'-DDT	0.2	ppb	ND	ND	ND
Aldrin	NS	ppb	ND	ND	ND
alpha-BHC	0.01	ppb	ND	ND	ND
alpha-Chlordane	NS	ppb	ND	ND	ND
beta-BHC	0.04	ppb	ND	ND	ND
Chlordane, total	0.05	ppb	ND	ND	ND
delta-BHC	0.04	ppb	ND	ND	ND
Dieldrin	0.004	ppb	ND	ND	ND
Endosulfan I	NS	ppb	ND	ND	ND
Endosulfan II	NS	ppb	ND	ND	ND
Endosulfan sulfate	NS	ppb	ND	ND	ND
Endrin	NS	ppb	ND	ND	ND
Endrin aldehyde	5	ppb	ND	ND	ND
Endrin ketone	5	ppb	ND	ND	ND
gamma-BHC (Lindane)	0.05	ppb	ND	ND	ND
gamma-Chlordane	NS	ppb	ND	ND	ND
Heptachlor	0.04	ppb	ND	ND	ND
Heptachlor epoxide	0.03	ppb	ND	ND	ND
Methoxychlor	35	ppb	ND	ND	ND
Toxaphene	0.06	ppb	ND	ND	ND
Herbicides					
2,4,5-T	35	ppb	ND	ND	ND
2,4,5-TP (Silvex)	0.26	ppb	ND	ND	ND
2,4-D	50	ppb	ND	ND	ND
Polychlorinated Biphenyls					
Aroclor 1016	NS	ppb	ND	ND	ND

Table 5d. Pesticides, Herbicides, and Polychlorinated Biphenyls in Groundwater
260 West 126th Street - New York, NY
BCP Site No. C231164

Sample ID:	**NY-AWQS**	**Units**	**MW-6**	**MW-6_DUP**	**FB**
Laboratory ID:			**26A1069-04**	**26A1069-05**	**26A1069-06**
Sampling Date:			**1/22/2026**	**1/22/2026**	**1/22/2026**
			Qual	**Qual**	**Qual**
Aroclor 1221	NS	ppb	ND	ND	ND
Aroclor 1232	NS	ppb	ND	ND	ND
Aroclor 1242	NS	ppb	ND	ND	ND
Aroclor 1248	NS	ppb	ND	ND	ND
Aroclor 1254	NS	ppb	ND	ND	ND
Aroclor 1260	NS	ppb	ND	ND	ND
Aroclor 1262	NS	ppb	ND	ND	ND
Aroclor 1268	NS	ppb	ND	ND	ND
Total PCBs	0.09	ppb	ND	ND	ND

Notes:

Bold and shaded yellow value indicates concentration exceeds NY-AWQS

NY-AWQS = NYSDEC Technical and Operational Guidance Series (TOGS) 1.1.1 Class GA Ambient Water Quality Standards

ND = Not detected

NS = No standard

ppb = parts per billion

Table 5e. Emerging Contaminants in Groundwater
260 West 126th Street - New York, NY
BCP Site No. C231164

Sample ID:	NY-AWQS	Units	MW-1		MW-2		MW-3		MW-4		MW-5	
Laboratory ID:			26A1069-01		26A1069-02		26A1069-03		26G0536-01		26G0536-02	
Sampling Date:			1/22/2026		1/22/2026		1/22/2026		7/9/2026		7/9/2026	
				Qual		Qual		Qual		Qual		Qual
Per- and Polyfluoroalkyl Substances												
11CL-PF3OUdS	NS	ppt	ND		ND		ND		ND		ND	
1H,1H,2H,2H-Perfluorodecanesulfonic acid (8:2 FTS)	NS	ppt	ND		ND		ND		ND		ND	
1H,1H,2H,2H-Perfluorohexanesulfonic acid (4:2 FTS)	NS	ppt	ND		ND		ND		ND		ND	
1H,1H,2H,2H-Perfluorooctanesulfonic acid (6:2 FTS)	NS	ppt	ND		ND		ND		ND		ND	
2H,2H,3H,3H-Perfluorodecanoic acid (7:3FTCA)	NS	ppt	ND		ND		ND		ND		ND	
2H,2H,3H,3H-Perfluorooctanoic acid (5:3FTCA)	NS	ppt	ND		ND		ND		ND		ND	
4,4,5,5,6,6,6-Heptafluorohexanoic acid (3:3FTCA)	NS	ppt	ND		ND		ND		ND		ND	
9CL-PF3ONS	NS	ppt	ND		ND		ND		ND		ND	
ADONA	NS	ppt	ND		ND		ND		ND		ND	
HFPO-DA (Gen-X)	NS	ppt	ND		ND		ND		ND		ND	
N-EtFOSA	NS	ppt	ND		ND		ND		ND		ND	
N-EtFOSAA	NS	ppt	ND		ND		ND		ND		ND	
N-EtFOSE	NS	ppt	ND		ND		ND		ND		ND	
N-MeFOSA	NS	ppt	ND		ND		ND		ND		ND	
N-MeFOSAA	NS	ppt	ND		ND		ND		ND		ND	
N-MeFOSE	NS	ppt	ND		ND		ND		ND		ND	
Perfluoro(2-ethoxyethane)sulfonic acid (PFEESA)	NS	ppt	ND		ND		ND		ND		ND	
Perfluoro-1-decanesulfonic acid (PFDS)	NS	ppt	ND		ND		ND		0.357	J	ND	
Perfluoro-1-heptanesulfonic acid (PFHpS)	NS	ppt	ND		ND		ND		0.446	J	0.742	J
Perfluoro-1-nonanesulfonic acid (PFNS)	NS	ppt	ND		ND		ND		ND		ND	
Perfluoro-1-octanesulfonamide (FOSA)	NS	ppt	ND		ND		ND		ND		ND	
Perfluoro-1-pentanesulfonate (PFPeS)	NS	ppt	ND		ND		ND		0.285	J	0.38	J
Perfluoro-3,6-dioxaheptanoic acid (NFDHA)	NS	ppt	ND		ND		ND		ND		ND	
Perfluoro-4-oxapentanoic acid (PFMPA)	NS	ppt	ND		ND		ND		ND		ND	
Perfluoro-5-oxahexanoic acid (PFMBA)	NS	ppt	ND		ND		ND		ND		ND	
Perfluorobutanesulfonic acid (PFBS)	NS	ppt	5.48		4.46		4.57		3.728		3.909	
Perfluorodecanoic acid (PFDA)	NS	ppt	1.05	J	1.25	J	1.02	J	1.909		1.991	
Perfluorododecanesulfonic acid (PFDoS)	NS	ppt	ND		ND		ND		ND		ND	

Table 5e. Emerging Contaminants in Groundwater
260 West 126th Street - New York, NY
BCP Site No. C231164

Sample ID:	NY-AWQS	Units	MW-1		MW-2		MW-3		MW-4		MW-5	
Laboratory ID:			26A1069-01		26A1069-02		26A1069-03		26G0536-01		26G0536-02	
Sampling Date:			1/22/2026		1/22/2026		1/22/2026		7/9/2026		7/9/2026	
				Qual		Qual		Qual		Qual		Qual
Perfluorododecanoic acid (PFDoA)	NS	ppt	ND		ND		ND		ND		ND	
Perfluoroheptanoic acid (PFHpA)	NS	ppt	7.58		4.19		3.74		4.62		4.18	
Perfluorohexanesulfonic acid (PFHxS)	NS	ppt	2.97		1.57	J	1.15	J	1.802		2.515	
Perfluorohexanoic acid (PFHxA)	NS	ppt	51.3		13.8		7.19		7.207		7.112	
Perfluoro-n-butanoic acid (PFBA)	NS	ppt	23.2		9.62		6.68	J	7.653		6.587	
Perfluorononanoic acid (PFNA)	NS	ppt	2.41		1.6	J	4.33		6.386		7.781	
Perfluorooctanesulfonic acid (PFOS)	2.7	ppt	**30.9**		**11.5**		**67.6**		**72.601**		**101.737**	
Perfluorooctanoic acid (PFOA)	6.7	ppt	**31.3**		**14.8**		**8.29**		**17.053**		**23.236**	
Perfluoropentanoic acid (PFPeA)	NS	ppt	82.9		21.6		9.87		10.774		10.731	
Perfluorotetradecanoic acid (PFTA)	NS	ppt	ND		ND		ND		ND		ND	
Perfluorotridecanoic acid (PFTrDA)	NS	ppt	ND		ND		ND		ND		ND	
Perfluoroundecanoic acid (PFUnA)	NS	ppt	ND		ND		ND		0.339	J	ND	
1,4-Dioxane												
1,4-Dioxane	0.35	ppb	ND		ND		ND		ND		ND	

Notes:

Bold and shaded yellow value indicates concentration exceeds NY-AWQS

NY-AWQS = NYSDEC Technical and Operational Guidance Series (TOGS) 1.1.1 Class GA Ambient Water Quality Standards

J = Estimated value

ND = Not detected

NS = No standard

ppb = parts per billion

ppt = parts per trillion

Table 5e. Emerging Contaminants in Groundwater
260 West 126th Street - New York, NY
BCP Site No. C231164

Sample ID:	NY-AWQS	Units	MW-6		MW-6_DUP		FB	
Laboratory ID:			26A1069-04		26A1069-05		26A1069-06	
Sampling Date:			1/22/2026		1/22/2026		1/22/2026	
				Qual		Qual		Qual
Per- and Polyfluoroalkyl Substances								
11CL-PF3OUdS	NS	ppt	ND		ND		ND	
1H,1H,2H,2H-Perfluorodecanesulfonic acid (8:2 FTS)	NS	ppt	ND		ND		ND	
1H,1H,2H,2H-Perfluorohexanesulfonic acid (4:2 FTS)	NS	ppt	ND		ND		ND	
1H,1H,2H,2H-Perfluorooctanesulfonic acid (6:2 FTS)	NS	ppt	ND		ND		ND	
2H,2H,3H,3H-Perfluorodecanoic acid (7:3FTCA)	NS	ppt	ND		ND		ND	
2H,2H,3H,3H-Perfluorooctanoic acid (5:3FTCA)	NS	ppt	ND		ND		ND	
4,4,5,5,6,6,6-Heptafluorohexanoic acid (3:3FTCA)	NS	ppt	ND		ND		ND	
9CL-PF3ONS	NS	ppt	ND		ND		ND	
ADONA	NS	ppt	ND		ND		ND	
HFPO-DA (Gen-X)	NS	ppt	ND		ND		ND	
N-EtFOSA	NS	ppt	ND		ND		ND	
N-EtFOSAA	NS	ppt	ND		ND		ND	
N-EtFOSE	NS	ppt	ND		ND		ND	
N-MeFOSA	NS	ppt	ND		ND		ND	
N-MeFOSAA	NS	ppt	ND		ND		ND	
N-MeFOSE	NS	ppt	ND		ND		ND	
Perfluoro(2-ethoxyethane)sulfonic acid (PFEESA)	NS	ppt	ND		ND		ND	
Perfluoro-1-decanesulfonic acid (PFDS)	NS	ppt	ND		ND		ND	
Perfluoro-1-heptanesulfonic acid (PFHpS)	NS	ppt	ND		ND		ND	
Perfluoro-1-nonanesulfonic acid (PFNS)	NS	ppt	ND		ND		ND	
Perfluoro-1-octanesulfonamide (FOSA)	NS	ppt	ND		ND		ND	
Perfluoro-1-pentanesulfonate (PFPeS)	NS	ppt	ND		ND		ND	
Perfluoro-3,6-dioxaheptanoic acid (NFDHA)	NS	ppt	ND		ND		ND	
Perfluoro-4-oxapentanoic acid (PFMPA)	NS	ppt	ND		ND		ND	
Perfluoro-5-oxahexanoic acid (PFMBA)	NS	ppt	ND		ND		ND	
Perfluorobutanesulfonic acid (PFBS)	NS	ppt	5.41		4.83		ND	
Perfluorodecanoic acid (PFDA)	NS	ppt	1.56	J	1.66	J	ND	
Perfluorododecanesulfonic acid (PFDoS)	NS	ppt	ND		ND		ND	

Table 5e. Emerging Contaminants in Groundwater
260 West 126th Street - New York, NY
BCP Site No. C231164

Sample ID:	NY-AWQS	Units	MW-6		MW-6_DUP		FB	
Laboratory ID:			26A1069-04		26A1069-05		26A1069-06	
Sampling Date:			1/22/2026		1/22/2026		1/22/2026	
				Qual		Qual		Qual
Perfluorododecanoic acid (PFDoA)	NS	ppt	ND		ND		ND	
Perfluoroheptanoic acid (PFHpA)	NS	ppt	3.92		3.63		ND	
Perfluorohexanesulfonic acid (PFHxS)	NS	ppt	1.69	J	1.67	J	ND	
Perfluorohexanoic acid (PFHxA)	NS	ppt	10.3		9.85		ND	
Perfluoro-n-butanoic acid (PFBA)	NS	ppt	7.98		8.38		ND	
Perfluorononanoic acid (PFNA)	NS	ppt	1.88	J	2.05		ND	
Perfluorooctanesulfonic acid (PFOS)	2.7	ppt	**24.2**		**25**		ND	
Perfluorooctanoic acid (PFOA)	6.7	ppt	**10.4**		**12**		ND	
Perfluoropentanoic acid (PFPeA)	NS	ppt	14.4		14.2		ND	
Perfluorotetradecanoic acid (PFTA)	NS	ppt	ND		ND		ND	
Perfluorotridecanoic acid (PFTrDA)	NS	ppt	ND		ND		ND	
Perfluoroundecanoic acid (PFUnA)	NS	ppt	ND		ND		ND	
1,4-Dioxane								
1,4-Dioxane	0.35	ppb	ND		ND		ND	

Notes:

Bold and shaded yellow value indicates concentration exceeds NY-AWQS

NY-AWQS = NYSDEC Technical and Operational Guidance Series (TOGS) 1.1.1 Class GA Ambient Water Quality Standards

J = Estimated value

ND = Not detected

NS = No standard

ppb = parts per billion

ppt = parts per trillion

Table 6. Volatile Organic Compounds in Soil Vapor
260 West 126th Street - New York, NY
BCP Site No. C231164

Sample ID:	Units	SV-1		SV-2		SV-3		SV-4		SV-5		SV-6		AA-1		SV-7		AA-2	
Laboratory ID:		26A1066-01		26A1066-02		26A1066-03		26A1066-04		26A1066-05		26A1066-06		26A1066-07		26G0520-01		26G0520-02	
Sampling Date:		1/22/2026		1/22/2026		1/22/2026		1/22/2026		1/22/2026		1/22/2026		1/22/2026		7/9/2026		7/9/2026	
Sample Depth (ft-bg):		22		8		8		8		8		8		N/A		1		N/A	
Matrix:		Soil Vapor		Soil Vapor		Soil Vapor		Soil Vapor		Soil Vapor		Soil Vapor		Outdoor Ambient Air		Soil Vapor		Outdoor Ambient Air	
			Qual		Qual		Qual		Qual		Qual		Qual		Qual		Qual		Qual
Volatile Organic Compounds																			
1,1,1,2-Tetrachloroethane	ug/m3	ND		ND		ND		ND		ND		ND		ND		ND		ND	
1,1,1-Trichloroethane	ug/m3	ND		ND		ND		ND		ND		ND		ND		ND		ND	
1,1,2,2-Tetrachloroethane	ug/m3	ND		ND		ND		ND		ND		ND		ND		ND		ND	
1,1,2-Trichloro-1,2,2-trifluoroethane (Freon 113)	ug/m3	ND		ND		ND		ND		ND		ND		ND		ND		ND	
1,1,2-Trichloroethane	ug/m3	ND		ND		ND		ND		ND		ND		ND		ND		ND	
1,1-Dichloroethane	ug/m3	ND		ND		ND		ND		ND		ND		ND		ND		ND	
1,1-Dichloroethylene	ug/m3	ND		ND		ND		ND		ND		ND		ND		ND		ND	
1,2,4-Trichlorobenzene	ug/m3	ND		ND		ND		ND		ND		ND		ND		ND		ND	
1,2,4-Trimethylbenzene	ug/m3	ND		ND		**1.081**	**D**	ND		ND		ND		ND		ND		ND	
1,2-Dibromoethane	ug/m3	ND		ND		ND		ND		ND		ND		ND		ND		ND	
1,2-Dichlorobenzene	ug/m3	ND		ND		ND		ND		ND		ND		ND		ND		ND	
1,2-Dichloroethane	ug/m3	ND		ND		ND		ND		ND		ND		ND		ND		ND	
1,2-Dichloropropane	ug/m3	ND		ND		ND		ND		ND		ND		ND		ND		ND	
1,2-Dichlorotetrafluoroethane	ug/m3	ND		ND		ND		ND		ND		ND		ND		ND		ND	
1,3,5-Trimethylbenzene	ug/m3	ND		ND		ND		ND		ND		ND		ND		ND		ND	
1,3-Butadiene	ug/m3	ND		ND		ND		ND		ND		ND		ND		ND		ND	
1,3-Dichlorobenzene	ug/m3	ND		ND		ND		ND		ND		ND		ND		ND		ND	
1,3-Dichloropropane	ug/m3	ND		ND		ND		ND		ND		ND		ND		ND		ND	
1,4-Dichlorobenzene	ug/m3	ND		ND		ND		ND		ND		ND		ND		ND		ND	
1,4-Dioxane	ug/m3	ND		ND		ND		ND		ND		ND		ND		ND		ND	
2,2,4-Trimethylpentane	ug/m3	**1.027**	**D**	ND		ND		ND		ND		ND		ND		ND		ND	
2-Butanone	ug/m3	**1.504**	**JD**	**2.270**	**JD**	**1.415**	**JD**	ND		**1.032**	**JD**	**2.182**	**JD**	0.943	JD	ND		1.2	JD
2-Hexanone	ug/m3	ND		ND		ND		ND		ND		ND		ND		ND		ND	
3-Chloropropene	ug/m3	ND		ND		ND		ND		ND		ND		ND		ND		ND	
4-Methyl-2-pentanone	ug/m3	ND		**30.302**	**D**	ND		ND		ND		ND		ND		ND		ND	
Acetone	ug/m3	**21.133**	**D**	**26.119**	**D**	**17.334**	**JD**	**12.585**	**JD**	**10.448**	**JD**	**23.745**	**D**	8.073	JD	4.5	JD	9	JD
Acrolein	ug/m3	0.298	D	ND		ND		ND		ND		ND		0.344	D	ND		ND	
Acrylonitrile	ug/m3	ND		ND		ND		ND		ND		ND		17.571	D	**9.7**	**JD**	ND	
Benzene	ug/m3	0.894	D	1.022	D	**1.182**	**D**	0.607	D	ND		0.990	D	1.022	D	ND		0.54	D
Benzyl chloride	ug/m3	ND		ND		ND		ND		ND		ND		ND		ND		ND	
Bromodichloromethane	ug/m3	ND		ND		ND		ND		ND		ND		ND		ND		ND	
Bromoform	ug/m3	ND		ND		ND		ND		ND		ND		ND		ND		ND	
Bromomethane	ug/m3	ND		ND		ND		ND		ND		ND		ND		ND		ND	
Carbon disulfide	ug/m3	ND		**0.560**	**D**	**0.778**	**D**	ND		**0.778**	**D**	**9.339**	**D**	ND		ND		ND	
Carbon tetrachloride	ug/m3	ND		ND		ND		0.358	D	ND		ND		0.365	D	ND		ND	
Chlorobenzene	ug/m3	ND		ND		ND		ND		ND		ND		ND		ND		ND	
Chloroethane	ug/m3	ND		ND		ND		ND		ND		ND		ND		ND		ND	
Chloroform	ug/m3	**8.297**	**D**	ND		ND		ND		ND		ND		ND		ND		ND	
Chloromethane	ug/m3	ND		ND		ND		0.330	D	ND		ND		1.156	D	ND		1.1	D
cis-1,2-Dichloroethylene	ug/m3	ND		ND		ND		ND		ND		ND		ND		ND		0.34	D
cis-1,3-Dichloropropylene	ug/m3	ND		ND		ND		ND		ND		ND		ND		ND		ND	
Cyclohexane	ug/m3	ND		ND		ND		ND		ND		ND		ND		ND		ND	
Dibromochloromethane	ug/m3	ND		ND		ND		ND		ND		ND		ND		ND		ND	
Dichlorodifluoromethane	ug/m3	**1.829**	**D**	**2.126**	**D**	**2.224**	**D**	**1.977**	**D**	**2.126**	**D**	**2.175**	**D**	1.780	D	**2**	**D**	1.9	D
Ethyl acetate	ug/m3	2.197	JD	1.801	JD	4.682	JD	1.081	JD	1.333	JD	0.648	JD	8.644	JD	ND		1.6	JD
Ethyl Benzene	ug/m3	**1.085**	**D**	**1.042**	**D**	**0.825**	**D**	ND		**0.738**	**D**	**1.085**	**D**	0.317	D	ND		ND	
Hexachlorobutadiene	ug/m3	ND		ND		ND		ND		ND		ND		ND		ND		ND	
Isopropanol	ug/m3	1.057	JD	1.057	JD	1.204	JD	0.737	JD	0.909	JD	0.663	JD	2.703	D	ND		4.2	D
Isopropylbenzene	ug/m3	**0.251**	**JD**	ND		ND		ND		ND		ND		ND		ND		ND	
Methyl Methacrylate	ug/m3	ND		ND		ND		ND		ND		ND		0.409	D	ND		ND	
Methyl tert-butyl ether (MTBE)	ug/m3	ND		ND		ND		ND		ND		ND		ND		ND		ND	
Methylene chloride	ug/m3	**0.177**	**JD**	ND		ND		ND		ND		ND		ND		ND		ND	
Naphthalene	ug/m3	ND		ND		ND		ND		ND		ND		ND		ND		ND	
n-Butylbenzene	ug/m3	ND		ND		ND		ND		ND		ND		ND		ND		ND	
n-Heptane	ug/m3	ND		ND		ND		ND		ND		ND		ND		ND		ND	
n-Hexane	ug/m3	**1.691**	**D**	0.634	D	ND		ND		0.423	JD	**1.867**	**D**	0.705	D	ND		0.75	D
n-Propylbenzene	ug/m3	ND		ND		ND		ND		ND		ND		ND		ND		ND	
o-Xylene	ug/m3	**1.693**	**D**	**1.519**	**D**	**1.302**	**D**	**0.738**	**D**	**1.215**	**D**	**1.519**	**D**	0.317	D	ND		ND	
p- & m- Xylenes	ug/m3	**4.036**	**D**	**4.167**	**D**	**3.385**	**D**	**2.040**	**D**	**3.082**	**D**	**4.210**	**D**	0.868	D	ND		1.4	D
p-Ethyltoluene	ug/m3	ND		ND		ND		ND		ND		ND		ND		ND		ND	
p-Isopropyltoluene	ug/m3	ND		ND		ND		ND		ND		ND		ND		ND		ND	
Propylene	ug/m3	**0.585**	**D**	**0.585**	**D**	**0.895**	**D**	ND		**2.236**	**D**	**2.581**	**D**	ND		ND		ND	
sec-Butylbenzene	ug/m3	ND		ND		ND		ND		ND		ND		ND		ND		ND	
Styrene	ug/m3	ND		ND		ND		ND		ND		ND		ND		ND		ND	
tert-Butylbenzene	ug/m3	ND		ND		ND		ND		ND		ND		ND		ND		ND	
Tetrachloroethylene	ug/m3	**5.627**	**D**	**1.085**	**D**	**1.220**	**D**	ND		**4.000**	**D**	**3.525**	**D**	ND		ND		ND	
Tetrahydrofuran	ug/m3	**1.769**	**D**	**0.855**	**JD**	ND		ND		ND		**1.297**	**D**	ND		ND		ND	
Toluene	ug/m3	**4.144**	**D**	**4.520**	**D**	**9.417**	**D**	**1.770**	**D**	**2.034**	**D**	**6.027**	**D**	1.733	D	0.59	D	1.5	D
trans-1,2-Dichloroethylene	ug/m3	ND		ND		ND		ND		ND		ND		ND		ND		ND	
trans-1,3-Dichloropropylene	ug/m3	ND		ND		ND		ND		ND		ND		ND		ND		ND	
Trichloroethylene	ug/m3	ND		ND		ND		ND		ND		ND		ND		ND		ND	

Table 6. Volatile Organic Compounds in Soil Vapor
260 West 126th Street - New York, NY
BCP Site No. C231164

Sample ID:	**Units**	**SV-1**		**SV-2**		**SV-3**		**SV-4**		**SV-5**		**SV-6**		**AA-1**		**SV-7**		**AA-2**	
Laboratory ID:		**26A1066-01**		**26A1066-02**		**26A1066-03**		**26A1066-04**		**26A1066-05**		**26A1066-06**		**26A1066-07**		**26G0520-01**		**26G0520-02**	
Sampling Date:		**1/22/2026**		**1/22/2026**		**1/22/2026**		**1/22/2026**		**1/22/2026**		**1/22/2026**		**1/22/2026**		**7/9/2026**		**7/9/2026**	
Sample Depth (ft-bg):		**22**		**8**		**8**		**8**		**8**		**8**		**N/A**		**1**		**N/A**	
Matrix:		**Soil Vapor**		**Soil Vapor**		**Soil Vapor**		**Soil Vapor**		**Soil Vapor**		**Soil Vapor**		**Outdoor Ambient Air**		**Soil Vapor**		**Outdoor Ambient Air**	
			Qual		**Qual**		**Qual**		**Qual**		**Qual**		**Qual**		**Qual**		**Qual**		**Qual**
Volatile Organic Compounds																			
Trichlorofluoromethane (Freon 11)	ug/m^3	0.955	D	**1.067**	**D**	**1.067**	**D**	0.955	D	1.011	D	**1.179**	**D**	1.011	D	1.3	D	1.3	D
Vinyl acetate	ug/m^3	ND		ND		ND		ND		ND		ND		ND		ND		ND	
Vinyl bromide	ug/m^3	ND		ND		ND		ND		ND		ND		ND		ND		ND	
Vinyl Chloride	ug/m^3	ND		ND		ND		ND		ND		ND		ND		ND		ND	
Xylenes, Total	ug/m^3	**5.642**	**D**	**5.642**	**D**	**4.774**	**D**	**2.821**	**D**	**4.297**	**D**	**5.642**	**D**	1.215	D	ND		1.4	JD

Notes:

Bold and shaded gray value indicates concentration exceeds ambient air (AA-1 or AA-2) concentration

Soil vapor samples SV-1 through SV-6 are compared to AA-1 results. Soil vapor sample SV-7 is compared to AA-2 results.

ug/m^3 = micrograms per cubic meter

D = Diluted

J = Estimated concentration

ND = Not detected

Appendix A
Previous Reports (Submitted Under Separate Cover)

Appendix B
Laboratory Data Packages
Data Usability Summary Reports
(Submitted Under Separate Cover)

Appendix C
Community Air Monitoring Plan (CAMP) Results

Downwind CAMP Data
260 West 126th Street - New York, NY
Remedial Investigation

Date / Time	Particulates - 15-min Average (mg/m^3)	VOCs - 15-min Average (ppm)
1/2/2026, 8:25:00 AM	0.059	
1/2/2026, 8:26:00 AM	0.038	
1/2/2026, 8:27:00 AM	0.063	
1/2/2026, 8:29:00 AM	0.051	
1/2/2026, 8:30:00 AM	0.022	
1/2/2026, 8:31:00 AM	0.015	
1/2/2026, 8:32:00 AM	0.011	
1/2/2026, 8:33:00 AM	0.008	
1/2/2026, 8:34:00 AM	0.006	
1/2/2026, 8:35:00 AM	0.005	
1/2/2026, 8:36:00 AM	0.004	
1/2/2026, 8:37:00 AM	0.003	
1/2/2026, 8:39:00 AM	0.029	
1/2/2026, 8:40:00 AM	0.025	
1/2/2026, 8:41:00 AM	0.016	
1/2/2026, 8:42:00 AM	0.012	
1/2/2026, 8:43:00 AM	0.009	
1/2/2026, 8:44:00 AM	0.008	
1/2/2026, 8:45:00 AM	0.006	
1/2/2026, 8:46:00 AM	0.005	
1/2/2026, 8:47:00 AM	0.005	
1/2/2026, 8:48:00 AM	0.004	
1/2/2026, 8:49:00 AM	0.004	
1/2/2026, 8:50:00 AM	0.003	
1/2/2026, 8:51:00 AM	0.004	
1/2/2026, 8:52:00 AM	0.003	
1/2/2026, 8:53:00 AM	0.003	
1/2/2026, 8:54:00 AM	0.003	
1/2/2026, 8:55:00 AM	0.003	
1/2/2026, 8:56:00 AM	0.002	
1/2/2026, 8:57:00 AM	0.002	
1/2/2026, 8:58:00 AM	0.002	
1/2/2026, 8:59:00 AM	0.002	
1/2/2026, 9:00:00 AM	0.002	
1/2/2026, 9:01:00 AM	0.002	
1/2/2026, 9:02:00 AM	0.002	
1/2/2026, 9:03:00 AM	0.002	
1/2/2026, 9:04:00 AM	0.002	
1/2/2026, 9:05:00 AM	0.002	
1/2/2026, 9:06:00 AM	0.003	
1/2/2026, 9:07:00 AM	0.002	
1/2/2026, 9:08:00 AM	0.002	
1/2/2026, 9:09:00 AM	0.002	

Downwind CAMP Data
260 West 126th Street - New York, NY
Remedial Investigation

Date / Time	Particulates - 15-min Average (mg/m^3)	VOCs - 15-min Average (ppm)
1/2/2026, 9:10:00 AM	0.002	
1/2/2026, 9:11:00 AM	0.002	
1/2/2026, 9:12:00 AM	0.002	
1/2/2026, 9:13:00 AM	0.045	
1/2/2026, 9:14:00 AM	0.029	
1/2/2026, 9:15:00 AM	0.019	
1/2/2026, 9:16:00 AM	0.015	
1/2/2026, 9:17:00 AM	0.011	
1/2/2026, 9:18:00 AM	0.009	
1/2/2026, 9:19:00 AM	0.008	
1/2/2026, 9:20:00 AM	0.007	
1/2/2026, 9:21:00 AM	0.005	
1/2/2026, 9:22:00 AM	0.004	
1/2/2026, 9:23:00 AM	0.004	
1/2/2026, 9:24:00 AM	0.003	
1/2/2026, 9:25:00 AM	0.003	
1/2/2026, 9:26:00 AM	0.002	
1/2/2026, 9:27:00 AM	0.002	
1/2/2026, 9:28:00 AM	0.002	
1/2/2026, 9:29:00 AM	0.002	
1/2/2026, 9:30:00 AM	0.002	
1/2/2026, 9:31:00 AM	0.002	
1/2/2026, 9:32:00 AM	0.002	
1/2/2026, 9:33:00 AM	0.002	
1/2/2026, 9:34:00 AM	0.002	
1/2/2026, 9:35:00 AM	0.002	
1/2/2026, 9:36:00 AM	0.002	
1/2/2026, 9:37:00 AM	0.002	
1/2/2026, 9:38:00 AM	0.002	
1/2/2026, 9:39:00 AM	0.002	
1/2/2026, 9:40:00 AM	0.002	
1/2/2026, 9:41:00 AM	0.002	
1/2/2026, 9:42:00 AM	0.002	
1/2/2026, 9:43:00 AM	0.002	
1/2/2026, 9:44:00 AM	0.013	
1/2/2026, 9:45:00 AM	0.013	
1/2/2026, 9:46:00 AM	0.009	
1/2/2026, 9:47:00 AM	0.007	
1/2/2026, 9:48:00 AM	0.005	
1/2/2026, 9:49:00 AM	0.004	
1/2/2026, 9:50:00 AM	0.004	
1/2/2026, 9:51:00 AM	0.004	
1/2/2026, 9:52:00 AM	0.003	

Downwind CAMP Data
260 West 126th Street - New York, NY
Remedial Investigation

Date / Time	Particulates - 15-min Average (mg/m^3)	VOCs - 15-min Average (ppm)
1/2/2026, 9:53:00 AM	0.003	
1/2/2026, 9:54:00 AM	0.003	
1/2/2026, 9:55:00 AM	0.003	
1/2/2026, 9:56:00 AM	0.003	
1/2/2026, 9:57:00 AM	0.002	
1/2/2026, 9:58:00 AM	0.002	
1/2/2026, 9:59:00 AM	0.002	
1/2/2026, 10:00:00 AM	0.001	
1/2/2026, 10:01:00 AM	0.001	
1/2/2026, 10:02:00 AM	0.001	
1/2/2026, 10:03:00 AM	0.001	
1/2/2026, 10:04:00 AM	0.001	
1/2/2026, 10:05:00 AM	0.001	
1/2/2026, 10:06:00 AM	0.001	
1/2/2026, 10:07:00 AM	0.001	
1/2/2026, 10:08:00 AM	0.002	
1/2/2026, 10:09:00 AM	0.002	
1/2/2026, 10:10:00 AM	0.002	
1/2/2026, 10:11:00 AM	0.002	
1/2/2026, 10:12:00 AM	0.002	
1/2/2026, 10:13:00 AM	0.001	
1/2/2026, 10:14:00 AM	0.001	
1/2/2026, 10:15:00 AM	0.001	
1/2/2026, 10:16:00 AM	0.001	
1/2/2026, 10:17:00 AM	0.001	
1/2/2026, 10:18:00 AM	0.001	
1/2/2026, 10:19:00 AM	0.001	
1/2/2026, 10:20:00 AM	0.001	
1/2/2026, 10:21:00 AM	0.002	
1/2/2026, 10:22:00 AM	0.003	
1/2/2026, 10:23:00 AM	0.003	
1/2/2026, 10:24:00 AM	0.002	
1/2/2026, 10:25:00 AM	0.002	
1/2/2026, 10:26:00 AM	0.002	
1/2/2026, 10:27:00 AM	0.001	
1/2/2026, 10:28:00 AM	0.001	
1/2/2026, 10:29:00 AM	0.001	
1/2/2026, 10:30:00 AM	0.001	
1/2/2026, 10:31:00 AM	0.001	
1/2/2026, 10:32:00 AM	0.001	
1/2/2026, 10:33:00 AM	0.001	
1/2/2026, 10:34:00 AM	0.001	
1/2/2026, 10:35:00 AM	0.001	

Downwind CAMP Data
260 West 126th Street - New York, NY
Remedial Investigation

Date / Time	Particulates - 15-min Average (mg/m^3)	VOCs - 15-min Average (ppm)
1/2/2026, 10:36:00 AM	0.001	
1/2/2026, 10:37:00 AM	0.001	
1/2/2026, 10:38:00 AM	0.001	
1/2/2026, 10:39:00 AM	0.001	
1/2/2026, 10:40:00 AM	0.001	
1/2/2026, 10:41:00 AM	0.001	
1/2/2026, 10:42:00 AM	0.001	
1/2/2026, 10:43:00 AM	0.001	
1/2/2026, 10:44:00 AM	0.001	
1/2/2026, 10:45:00 AM	0.001	
1/2/2026, 10:46:00 AM	0.001	
1/2/2026, 10:47:00 AM	0	
1/2/2026, 10:48:00 AM	0.001	
1/2/2026, 10:49:00 AM	0.002	
1/2/2026, 10:50:00 AM	0.002	
1/2/2026, 10:51:00 AM	0.001	
1/2/2026, 10:52:00 AM	0.001	
1/2/2026, 10:53:00 AM	0.001	
1/2/2026, 10:54:00 AM	0.002	
1/2/2026, 10:55:00 AM	0.002	
1/2/2026, 10:56:00 AM	0.002	
1/2/2026, 10:57:00 AM	0.002	
1/2/2026, 10:58:00 AM	0.002	
1/2/2026, 10:59:00 AM	0.001	
1/2/2026, 11:00:00 AM	0.002	
1/2/2026, 11:01:00 AM	0.002	
1/2/2026, 11:02:00 AM	0.001	
1/2/2026, 11:03:00 AM	0.001	
1/2/2026, 11:04:00 AM	0.001	
1/2/2026, 11:05:00 AM	0.001	
1/2/2026, 11:06:00 AM	0.001	
1/2/2026, 11:07:00 AM	0.001	
1/2/2026, 11:08:00 AM	0.001	
1/2/2026, 11:09:00 AM	0.001	
1/2/2026, 11:10:00 AM	0.001	
1/2/2026, 11:11:00 AM	0.001	
1/2/2026, 11:12:00 AM	0.001	
1/2/2026, 11:13:00 AM	0.001	
1/2/2026, 11:14:00 AM	0.001	
1/2/2026, 11:15:00 AM	0.001	
1/2/2026, 11:16:00 AM	0.001	
1/2/2026, 11:17:00 AM	0.001	
1/2/2026, 11:18:00 AM	0.001	

Downwind CAMP Data
260 West 126th Street - New York, NY
Remedial Investigation

Date / Time	Particulates - 15-min Average (mg/m^3)	VOCs - 15-min Average (ppm)
1/2/2026, 11:19:00 AM	0.001	
1/2/2026, 11:20:00 AM	0.001	
1/2/2026, 11:21:00 AM	0.001	
1/2/2026, 11:22:00 AM	0.001	
1/2/2026, 11:23:00 AM	0.001	
1/2/2026, 11:24:00 AM	0	
1/2/2026, 11:25:00 AM	0.001	
1/2/2026, 11:26:00 AM	0.001	
1/2/2026, 11:27:00 AM	0.001	
1/2/2026, 11:28:00 AM	0.001	
1/2/2026, 11:29:00 AM	0.001	
1/2/2026, 11:30:00 AM	0.001	
1/2/2026, 11:31:00 AM	0.001	
1/2/2026, 11:32:00 AM	0.001	
1/2/2026, 11:33:00 AM	0.001	
1/2/2026, 11:34:00 AM	0.001	
1/2/2026, 11:35:00 AM	0.001	
1/2/2026, 11:36:00 AM	0.001	
1/2/2026, 11:37:00 AM	0.001	
1/2/2026, 11:38:00 AM	0	
1/2/2026, 11:39:00 AM	0.001	
1/2/2026, 11:40:00 AM	0	
1/2/2026, 11:41:00 AM	0	
1/2/2026, 11:42:00 AM	0.001	
1/2/2026, 11:43:00 AM	0.001	
1/2/2026, 11:44:00 AM	0.001	
1/2/2026, 11:45:00 AM	0.001	
1/2/2026, 11:46:00 AM	0	
1/2/2026, 11:47:00 AM	0	
1/2/2026, 11:48:00 AM	0.001	
1/2/2026, 11:49:00 AM	0.001	
1/2/2026, 11:50:00 AM	0.001	
1/2/2026, 11:51:00 AM	0.001	
1/2/2026, 11:52:00 AM	0.001	
1/2/2026, 11:53:00 AM	0.001	
1/2/2026, 11:54:00 AM	0	
1/2/2026, 11:55:00 AM	0	
1/2/2026, 11:56:00 AM	0	
1/2/2026, 11:57:00 AM	0	
1/2/2026, 11:58:00 AM	0	
1/2/2026, 11:59:00 AM	0	
1/2/2026, 12:00:00 PM	0	
1/2/2026, 12:01:00 PM	0	

Downwind CAMP Data
260 West 126th Street - New York, NY
Remedial Investigation

Date / Time	Particulates - 15-min Average (mg/m^3)	VOCs - 15-min Average (ppm)
1/2/2026, 12:02:00 PM	0	
1/2/2026, 12:03:00 PM	0	
1/2/2026, 12:04:00 PM	0	
1/2/2026, 12:05:00 PM	0	
1/2/2026, 12:06:00 PM	0	
1/2/2026, 12:07:00 PM	0	
1/2/2026, 12:08:00 PM	0.023	
1/2/2026, 12:09:00 PM	0.019	
1/2/2026, 12:10:00 PM	0.009	
1/2/2026, 12:11:00 PM	0.006	
1/2/2026, 12:12:00 PM	0.004	
1/2/2026, 12:13:00 PM	0.003	
1/2/2026, 12:14:00 PM	0.002	
1/2/2026, 12:15:00 PM	0.002	
1/2/2026, 12:16:00 PM	0.001	
1/2/2026, 12:17:00 PM	0.001	
1/2/2026, 12:18:00 PM	0.001	
1/2/2026, 12:19:00 PM	0	
1/5/2026, 7:47:00 AM		
1/5/2026, 7:48:00 AM	0.012	
1/5/2026, 7:49:00 AM	0.012	
1/5/2026, 7:50:00 AM	0.014	
1/5/2026, 7:51:00 AM	0.012	
1/5/2026, 7:52:00 AM	0.013	
1/5/2026, 7:53:00 AM	0.013	
1/5/2026, 7:54:00 AM	0.013	
1/5/2026, 7:55:00 AM	0.012	
1/5/2026, 7:56:00 AM	0.013	
1/5/2026, 7:57:00 AM	0.012	
1/5/2026, 7:59:00 AM	0.012	
1/5/2026, 8:00:00 AM	0.012	
1/5/2026, 8:01:00 AM	0.012	
1/5/2026, 8:02:00 AM	0.012	
1/5/2026, 8:03:00 AM	0.013	
1/5/2026, 8:04:00 AM	0.013	
1/5/2026, 8:05:00 AM	0.013	
1/5/2026, 8:06:00 AM	0.012	
1/5/2026, 8:07:00 AM	0.012	
1/5/2026, 8:08:00 AM	0.013	
1/5/2026, 8:09:00 AM	0.012	
1/5/2026, 8:10:00 AM	0.013	
1/5/2026, 8:11:00 AM	0.012	
1/5/2026, 8:12:00 AM	0.012	

Downwind CAMP Data
260 West 126th Street - New York, NY
Remedial Investigation

Date / Time	Particulates - 15-min Average (mg/m^3)	VOCs - 15-min Average (ppm)
1/5/2026, 8:13:00 AM	0.012	
1/5/2026, 8:14:00 AM	0.012	
1/5/2026, 8:15:00 AM	0.013	
1/5/2026, 8:16:00 AM	0.014	
1/5/2026, 8:17:00 AM	0.013	
1/5/2026, 8:18:00 AM	0.013	
1/5/2026, 8:19:00 AM	0.014	
1/5/2026, 8:20:00 AM	0.011	
1/5/2026, 8:21:00 AM	0.013	
1/5/2026, 8:22:00 AM	0.012	
1/5/2026, 8:23:00 AM	0.013	
1/5/2026, 8:24:00 AM	0.012	
1/5/2026, 8:25:00 AM	0.012	
1/5/2026, 8:26:00 AM	0.012	
1/5/2026, 8:27:00 AM	0.013	
1/5/2026, 8:28:00 AM	0.014	
1/5/2026, 8:29:00 AM	0.013	
1/5/2026, 8:30:00 AM	0.012	
1/5/2026, 8:31:00 AM	0.013	
1/5/2026, 8:32:00 AM	0.013	
1/5/2026, 8:33:00 AM	0.013	
1/5/2026, 8:34:00 AM	0.014	
1/5/2026, 8:35:00 AM	0.014	
1/5/2026, 8:36:00 AM	0.013	
1/5/2026, 8:37:00 AM	0.014	
1/5/2026, 8:38:00 AM	0.014	
1/5/2026, 8:39:00 AM	0.014	
1/5/2026, 8:40:00 AM	0.013	
1/5/2026, 8:41:00 AM	0.014	
1/5/2026, 8:42:00 AM	0.013	
1/5/2026, 8:43:00 AM	0.013	
1/5/2026, 8:44:00 AM	0.014	
1/5/2026, 8:45:00 AM	0.014	
1/5/2026, 8:46:00 AM	0.014	
1/5/2026, 8:47:00 AM	0.015	
1/5/2026, 8:48:00 AM	0.014	
1/5/2026, 8:49:00 AM	0.014	
1/5/2026, 8:50:00 AM	0.014	
1/5/2026, 8:51:00 AM	0.014	
1/5/2026, 8:52:00 AM	0.015	
1/5/2026, 8:53:00 AM	0.014	
1/5/2026, 8:54:00 AM	0.014	
1/5/2026, 8:55:00 AM	0.014	

Downwind CAMP Data
260 West 126th Street - New York, NY
Remedial Investigation

Date / Time	Particulates - 15-min Average (mg/m^3)	VOCs - 15-min Average (ppm)
1/5/2026, 8:56:00 AM	0.013	
1/5/2026, 8:57:00 AM	0.013	
1/5/2026, 8:58:00 AM	0.013	
1/5/2026, 8:59:00 AM	0.013	
1/5/2026, 9:00:00 AM	0.014	0
1/5/2026, 9:01:00 AM	0.014	
1/5/2026, 9:02:00 AM	0.023	
1/5/2026, 9:03:00 AM	0.024	
1/5/2026, 9:04:00 AM	0.026	
1/5/2026, 9:05:00 AM	0.026	
1/5/2026, 9:06:00 AM	0.026	
1/5/2026, 9:07:00 AM	0.026	
1/5/2026, 9:08:00 AM	0.026	
1/5/2026, 9:09:00 AM	0.027	
1/5/2026, 9:10:00 AM	0.027	
1/5/2026, 9:11:00 AM	0.028	
1/5/2026, 9:12:00 AM	0.027	
1/5/2026, 9:13:00 AM	0.029	
1/5/2026, 9:14:00 AM	0.029	
1/5/2026, 9:15:00 AM	0.028	0
1/5/2026, 9:16:00 AM	0.027	
1/5/2026, 9:17:00 AM	0.026	
1/5/2026, 9:18:00 AM	0.027	
1/5/2026, 9:19:00 AM	0.025	
1/5/2026, 9:20:00 AM	0.025	
1/5/2026, 9:21:00 AM	0.025	
1/5/2026, 9:22:00 AM	0.025	
1/5/2026, 9:23:00 AM	0.028	
1/5/2026, 9:24:00 AM	0.028	
1/5/2026, 9:25:00 AM	0.027	
1/5/2026, 9:26:00 AM	0.027	
1/5/2026, 9:27:00 AM	0.027	
1/5/2026, 9:28:00 AM	0.028	
1/5/2026, 9:29:00 AM	0.029	
1/5/2026, 9:30:00 AM	0.029	0
1/5/2026, 9:31:00 AM	0.028	
1/5/2026, 9:32:00 AM	0.027	
1/5/2026, 9:33:00 AM	0.027	
1/5/2026, 9:34:00 AM	0.028	
1/5/2026, 9:35:00 AM	0.027	
1/5/2026, 9:36:00 AM	0.027	
1/5/2026, 9:37:00 AM	0.027	
1/5/2026, 9:38:00 AM	0.026	

Downwind CAMP Data
260 West 126th Street - New York, NY
Remedial Investigation

Date / Time	Particulates - 15-min Average (mg/m^3)	VOCs - 15-min Average (ppm)
1/5/2026, 9:39:00 AM	0.026	
1/5/2026, 9:40:00 AM	0.026	
1/5/2026, 9:41:00 AM	0.026	
1/5/2026, 9:42:00 AM	0.026	
1/5/2026, 9:43:00 AM	0.026	
1/5/2026, 9:44:00 AM	0.027	
1/5/2026, 9:45:00 AM	0.026	0
1/5/2026, 9:46:00 AM	0.026	
1/5/2026, 9:47:00 AM	0.025	
1/5/2026, 9:48:00 AM	0.025	
1/5/2026, 9:49:00 AM	0.024	
1/5/2026, 9:50:00 AM	0.024	
1/5/2026, 9:51:00 AM	0.025	
1/5/2026, 9:52:00 AM	0.025	
1/5/2026, 9:53:00 AM	0.025	
1/5/2026, 9:54:00 AM	0.026	
1/5/2026, 9:55:00 AM	0.035	
1/5/2026, 9:56:00 AM	0.025	
1/5/2026, 9:57:00 AM	0.029	
1/5/2026, 9:58:00 AM	0.056	
1/5/2026, 9:59:00 AM	0.028	
1/5/2026, 10:00:00 AM	0.026	0
1/5/2026, 10:01:00 AM	0.028	
1/5/2026, 10:02:00 AM	0.024	
1/5/2026, 10:03:00 AM	0.025	
1/5/2026, 10:04:00 AM	0.025	
1/5/2026, 10:05:00 AM	0.025	
1/5/2026, 10:06:00 AM	0.025	
1/5/2026, 10:07:00 AM	0.026	
1/5/2026, 10:08:00 AM	0.025	
1/5/2026, 10:09:00 AM	0.025	
1/5/2026, 10:10:00 AM	0.026	
1/5/2026, 10:11:00 AM	0.026	
1/5/2026, 10:12:00 AM	0.026	
1/5/2026, 10:13:00 AM	0.026	
1/5/2026, 10:14:00 AM	0.027	
1/5/2026, 10:15:00 AM	0.027	0
1/5/2026, 10:16:00 AM	0.025	
1/5/2026, 10:17:00 AM	0.026	
1/5/2026, 10:18:00 AM	0.025	
1/5/2026, 10:19:00 AM	0.026	
1/5/2026, 10:20:00 AM	0.026	
1/5/2026, 10:21:00 AM	0.026	

Downwind CAMP Data
260 West 126th Street - New York, NY
Remedial Investigation

Date / Time	Particulates - 15-min Average (mg/m^3)	VOCs - 15-min Average (ppm)
1/5/2026, 10:22:00 AM	0.026	
1/5/2026, 10:23:00 AM	0.026	
1/5/2026, 10:24:00 AM	0.025	
1/5/2026, 10:25:00 AM	0.025	
1/5/2026, 10:26:00 AM	0.025	
1/5/2026, 10:27:00 AM	0.027	
1/5/2026, 10:28:00 AM	0.029	
1/5/2026, 10:29:00 AM	0.03	
1/5/2026, 10:30:00 AM	0.029	0
1/5/2026, 10:31:00 AM	0.028	
1/5/2026, 10:32:00 AM	0.028	
1/5/2026, 10:33:00 AM	0.029	
1/5/2026, 10:34:00 AM	0.029	
1/5/2026, 10:35:00 AM	0.029	
1/5/2026, 10:36:00 AM	0.028	
1/5/2026, 10:37:00 AM	0.027	
1/5/2026, 10:38:00 AM	0.029	
1/5/2026, 10:39:00 AM	0.029	
1/5/2026, 10:40:00 AM	0.025	
1/5/2026, 10:41:00 AM	0.025	
1/5/2026, 10:42:00 AM	0.026	
1/5/2026, 10:43:00 AM	0.027	
1/5/2026, 10:44:00 AM	0.028	
1/5/2026, 10:45:00 AM	0.025	0
1/5/2026, 10:46:00 AM	0.025	
1/5/2026, 10:47:00 AM	0.021	
1/5/2026, 10:48:00 AM	0.021	
1/5/2026, 10:49:00 AM	0.017	
1/5/2026, 10:50:00 AM	0.014	
1/5/2026, 10:51:00 AM	0.015	
1/5/2026, 10:52:00 AM	0.016	
1/5/2026, 10:53:00 AM	0.016	
1/5/2026, 10:54:00 AM	0.018	
1/5/2026, 10:55:00 AM	0.018	
1/5/2026, 10:56:00 AM	0.022	
1/5/2026, 10:57:00 AM	0.025	
1/5/2026, 10:58:00 AM	0.023	
1/5/2026, 10:59:00 AM	0.03	
1/5/2026, 11:00:00 AM	0.023	0
1/5/2026, 11:01:00 AM	0.02	
1/5/2026, 11:02:00 AM	0.024	
1/5/2026, 11:03:00 AM	0.025	
1/5/2026, 11:04:00 AM	0.024	

Downwind CAMP Data
260 West 126th Street - New York, NY
Remedial Investigation

Date / Time	Particulates - 15-min Average (mg/m^3)	VOCs - 15-min Average (ppm)
1/5/2026, 11:05:00 AM	0.023	
1/5/2026, 11:06:00 AM	0.024	
1/5/2026, 11:07:00 AM	0.03	
1/5/2026, 11:08:00 AM	0.02	
1/5/2026, 11:09:00 AM	0.019	
1/5/2026, 11:10:00 AM	0.018	
1/5/2026, 11:11:00 AM	0.017	
1/5/2026, 11:12:00 AM	0.017	
1/5/2026, 11:13:00 AM	0.017	
1/5/2026, 11:14:00 AM	0.017	
1/5/2026, 11:15:00 AM	0.017	0
1/5/2026, 11:16:00 AM	0.021	
1/5/2026, 11:17:00 AM	0.022	
1/5/2026, 11:18:00 AM	0.019	
1/5/2026, 11:19:00 AM	0.017	
1/5/2026, 11:20:00 AM	0.017	
1/5/2026, 11:21:00 AM	0.018	
1/5/2026, 11:22:00 AM	0.016	
1/5/2026, 11:23:00 AM	0.018	
1/5/2026, 11:24:00 AM	0.019	
1/5/2026, 11:25:00 AM	0.018	
1/5/2026, 11:26:00 AM	0.019	
1/5/2026, 11:27:00 AM	0.019	
1/5/2026, 11:28:00 AM	0.019	
1/5/2026, 11:29:00 AM	0.019	
1/5/2026, 11:30:00 AM	0.02	0
1/5/2026, 11:31:00 AM	0.02	
1/5/2026, 11:32:00 AM	0.021	
1/5/2026, 11:33:00 AM	0.024	
1/5/2026, 11:34:00 AM	0.023	
1/5/2026, 11:35:00 AM	0.022	
1/5/2026, 11:36:00 AM	0.028	
1/5/2026, 11:37:00 AM	0.028	
1/5/2026, 11:38:00 AM	0.027	
1/5/2026, 11:39:00 AM	0.028	
1/5/2026, 11:40:00 AM	0.024	
1/5/2026, 11:41:00 AM	0.023	
1/5/2026, 11:42:00 AM	0.026	
1/5/2026, 11:43:00 AM	0.023	
1/5/2026, 11:44:00 AM	0.026	
1/5/2026, 11:45:00 AM	0.022	0
1/5/2026, 11:46:00 AM	0.022	
1/5/2026, 11:47:00 AM	0.02	

Downwind CAMP Data
260 West 126th Street - New York, NY
Remedial Investigation

Date / Time	Particulates - 15-min Average (mg/m^3)	VOCs - 15-min Average (ppm)
1/5/2026, 11:48:00 AM	0.021	
1/5/2026, 11:49:00 AM	0.02	
1/5/2026, 11:50:00 AM	0.021	
1/5/2026, 11:51:00 AM	0.022	
1/5/2026, 11:52:00 AM	0.022	
1/5/2026, 12:00:00 PM		0
1/5/2026, 12:15:00 PM		0
1/5/2026, 12:30:00 PM		0
1/5/2026, 12:45:00 PM		0
1/5/2026, 1:00:00 PM		0
1/5/2026, 1:11:00 PM	0.02	
1/5/2026, 1:12:00 PM	0.02	
1/5/2026, 1:13:00 PM	0.0193	
1/5/2026, 1:14:00 PM	0.019	
1/5/2026, 1:15:00 PM	0.0196	0
1/5/2026, 1:16:00 PM	0.0193	
1/5/2026, 1:17:00 PM	0.019	
1/5/2026, 1:18:00 PM	0.0189	
1/5/2026, 1:19:00 PM	0.0188	
1/5/2026, 1:20:00 PM	0.0187	
1/5/2026, 1:21:00 PM	0.0187	
1/5/2026, 1:22:00 PM	0.0187	
1/5/2026, 1:23:00 PM	0.019	
1/5/2026, 1:24:00 PM	0.0196	
1/5/2026, 1:25:00 PM	0.0197	
1/5/2026, 1:26:00 PM	0.0196	
1/5/2026, 1:27:00 PM	0.0197	
1/5/2026, 1:28:00 PM	0.0199	
1/5/2026, 1:29:00 PM	0.0199	
1/5/2026, 1:30:00 PM	0.0197	0
1/5/2026, 1:31:00 PM	0.0197	
1/5/2026, 1:32:00 PM	0.0198	
1/5/2026, 1:33:00 PM	0.0197	
1/5/2026, 1:34:00 PM	0.0197	
1/5/2026, 1:35:00 PM	0.0197	
1/5/2026, 1:36:00 PM	0.0196	
1/5/2026, 1:37:00 PM	0.0195	
1/5/2026, 1:38:00 PM	0.0191	
1/5/2026, 1:39:00 PM	0.0183	
1/5/2026, 1:40:00 PM	0.0181	
1/5/2026, 1:41:00 PM	0.0179	
1/5/2026, 1:42:00 PM	0.0175	
1/5/2026, 1:46:00 PM	0.0169	0

Downwind CAMP Data
260 West 126th Street - New York, NY
Remedial Investigation

Date / Time	Particulates - 15-min Average (mg/m^3)	VOCs - 15-min Average (ppm)
1/5/2026, 1:47:00 PM	0.0169	0
1/5/2026, 1:48:00 PM	0.0173	0
1/5/2026, 1:49:00 PM	0.0173	0
1/5/2026, 1:50:00 PM	0.0174	0
1/5/2026, 1:51:00 PM	0.0176	0
1/5/2026, 1:52:00 PM	0.018	0
1/5/2026, 1:53:00 PM	0.018	0
1/5/2026, 1:54:00 PM	0.0181	0
1/5/2026, 1:55:00 PM	0.0183	0
1/5/2026, 1:56:00 PM	0.0187	0
1/5/2026, 1:57:00 PM	0.0192	0
1/5/2026, 1:58:00 PM	0.0192	0
1/5/2026, 1:59:00 PM	0.0191	0
1/5/2026, 2:00:00 PM	0.0193	0
1/5/2026, 2:01:00 PM	0.0195	0
1/5/2026, 2:02:00 PM	0.0195	0
1/5/2026, 2:03:00 PM	0.0193	0
1/5/2026, 2:04:00 PM	0.0195	0
1/5/2026, 2:05:00 PM	0.0194	0
1/5/2026, 2:06:00 PM	0.0191	0
1/5/2026, 2:07:00 PM	0.0189	0
1/5/2026, 2:08:00 PM	0.019	0
1/5/2026, 2:09:00 PM	0.0191	0
1/5/2026, 2:10:00 PM	0.0192	0
1/5/2026, 2:11:00 PM	0.0193	0
1/5/2026, 2:12:00 PM	0.019	0
1/5/2026, 2:13:00 PM	0.0189	0
1/5/2026, 2:14:00 PM	0.0191	0
1/5/2026, 2:15:00 PM	0.019	0
1/5/2026, 2:16:00 PM	0.0189	0
1/5/2026, 2:17:00 PM	0.019	0
1/5/2026, 2:18:00 PM	0.0193	0
1/5/2026, 2:19:00 PM	0.0196	0
1/5/2026, 2:20:00 PM	0.0197	0
1/5/2026, 2:21:00 PM	0.0199	0
1/5/2026, 2:22:00 PM	0.02	0
1/5/2026, 2:23:00 PM	0.0202	0
1/5/2026, 2:24:00 PM	0.0203	0
1/5/2026, 2:25:00 PM	0.0203	0
1/5/2026, 2:26:00 PM	0.0202	0
1/5/2026, 2:27:00 PM	0.0204	0
1/5/2026, 2:28:00 PM	0.0216	0
1/5/2026, 2:29:00 PM	0.0216	0

Downwind CAMP Data
260 West 126th Street - New York, NY
Remedial Investigation

Date / Time	Particulates - 15-min Average (mg/m^3)	VOCs - 15-min Average (ppm)
1/5/2026, 2:30:00 PM	0.022	0
1/5/2026, 2:31:00 PM	0.0223	0
1/5/2026, 2:32:00 PM	0.0223	0
1/5/2026, 2:33:00 PM	0.0222	0
1/5/2026, 2:34:00 PM	0.0219	0
1/5/2026, 2:35:00 PM	0.0223	0
1/5/2026, 2:36:00 PM	0.0226	0
1/5/2026, 2:37:00 PM	0.0231	0
1/5/2026, 2:38:00 PM	0.0239	0
1/5/2026, 2:39:00 PM	0.0242	0
1/5/2026, 2:40:00 PM	0.0243	0
1/5/2026, 2:41:00 PM	0.0247	0
1/5/2026, 2:42:00 PM	0.0248	0
1/5/2026, 2:43:00 PM	0.024	0
1/5/2026, 2:44:00 PM	0.0242	0
1/5/2026, 2:45:00 PM	0.0241	0
1/5/2026, 2:46:00 PM	0.0244	0
1/5/2026, 2:47:00 PM	0.0246	0
1/5/2026, 2:48:00 PM	0.0248	0
1/5/2026, 2:49:00 PM	0.0251	0
1/5/2026, 2:50:00 PM	0.0249	0
1/5/2026, 2:51:00 PM	0.025	0
1/5/2026, 2:52:00 PM		0
1/5/2026, 2:53:00 PM		0
1/5/2026, 2:54:00 PM		0
1/5/2026, 2:55:00 PM		0
1/5/2026, 2:56:00 PM		0
1/5/2026, 2:57:00 PM		0
1/5/2026, 2:58:00 PM		0
1/5/2026, 2:59:00 PM		0
1/5/2026, 3:00:00 PM		0
1/5/2026, 3:01:00 PM		0
1/5/2026, 3:02:00 PM		0
1/5/2026, 3:03:00 PM		0
1/5/2026, 3:04:00 PM		0
1/5/2026, 3:05:00 PM		0
1/5/2026, 3:06:00 PM		0
1/5/2026, 3:07:00 PM		0
1/5/2026, 3:08:00 PM		0
1/5/2026, 3:09:00 PM		0
1/5/2026, 3:10:00 PM		0
1/5/2026, 3:11:00 PM		0
1/5/2026, 3:12:00 PM		0

Downwind CAMP Data
260 West 126th Street - New York, NY
Remedial Investigation

Date / Time	Particulates - 15-min Average (mg/m^3)	VOCs - 15-min Average (ppm)
1/5/2026, 3:13:00 PM		0
1/5/2026, 3:14:00 PM		0
1/5/2026, 3:15:00 PM		0
1/5/2026, 3:16:00 PM		0
1/5/2026, 3:17:00 PM		0
1/5/2026, 3:18:00 PM		0
1/5/2026, 3:19:00 PM		0
1/5/2026, 3:20:00 PM		0
1/5/2026, 3:21:00 PM		0
1/5/2026, 3:22:00 PM		0
1/5/2026, 3:23:00 PM		0
1/5/2026, 3:24:00 PM		0
1/5/2026, 3:25:00 PM		0
1/5/2026, 3:26:00 PM		0
1/5/2026, 3:27:00 PM		0
1/5/2026, 3:28:00 PM		0
1/5/2026, 3:29:00 PM		0
1/5/2026, 3:30:00 PM		0
1/5/2026, 3:31:00 PM		0
1/5/2026, 3:32:00 PM		0
1/5/2026, 3:33:00 PM		0
1/5/2026, 3:34:00 PM		0
1/5/2026, 3:35:00 PM		0
1/5/2026, 3:36:00 PM		0
1/6/2026, 7:35:00 AM		0
1/6/2026, 7:36:00 AM	0.088	0
1/6/2026, 7:37:00 AM	0.087	0
1/6/2026, 7:38:00 AM	0.0867	0
1/6/2026, 7:39:00 AM	0.0863	0
1/6/2026, 7:40:00 AM	0.0858	0
1/6/2026, 7:41:00 AM	0.0855	0
1/6/2026, 7:42:00 AM	0.0854	0
1/6/2026, 7:43:00 AM	0.0859	0
1/6/2026, 7:44:00 AM	0.0858	0
1/6/2026, 7:45:00 AM	0.086	0
1/6/2026, 7:46:00 AM	0.086	0
1/6/2026, 7:47:00 AM	0.0859	0
1/6/2026, 7:48:00 AM	0.0856	0
1/6/2026, 7:49:00 AM	0.0854	0
1/6/2026, 7:50:00 AM	0.0852	0
1/6/2026, 7:51:00 AM	0.0849	0
1/6/2026, 7:52:00 AM	0.0847	0
1/6/2026, 7:53:00 AM	0.0844	0

Downwind CAMP Data
260 West 126th Street - New York, NY
Remedial Investigation

Date / Time	Particulates - 15-min Average (mg/m^3)	VOCs - 15-min Average (ppm)
1/6/2026, 7:54:00 AM	0.0847	0
1/6/2026, 7:55:00 AM	0.0853	0
1/6/2026, 7:56:00 AM	0.0863	0
1/6/2026, 7:57:00 AM	0.0897	0
1/6/2026, 7:58:00 AM	0.0927	0
1/6/2026, 7:59:00 AM	0.0945	0
1/6/2026, 8:00:00 AM	0.0956	0
1/6/2026, 8:01:00 AM	0.0986	0
1/6/2026, 8:02:00 AM	0.1027	0
1/6/2026, 8:03:00 AM	0.1051	0
1/6/2026, 8:04:00 AM	0.1074	0
1/6/2026, 8:05:00 AM	0.1104	0
1/6/2026, 8:06:00 AM	0.1137	0
1/6/2026, 8:07:00 AM	0.1149	0
1/6/2026, 8:08:00 AM	0.1149	0
1/6/2026, 8:09:00 AM	0.1146	0
1/6/2026, 8:10:00 AM	0.1142	0
1/6/2026, 8:11:00 AM	0.113	0
1/6/2026, 8:12:00 AM	0.1092	0
1/6/2026, 8:13:00 AM	0.1056	0
1/6/2026, 8:14:00 AM	0.1033	0
1/6/2026, 8:15:00 AM	0.1017	0
1/6/2026, 8:16:00 AM	0.0983	0
1/6/2026, 8:17:00 AM	0.0938	0
1/6/2026, 8:18:00 AM	0.0912	0
1/6/2026, 8:19:00 AM	0.0894	0
1/6/2026, 8:20:00 AM	0.0872	0
1/6/2026, 8:21:00 AM	0.0831	0
1/6/2026, 8:22:00 AM	0.081	0
1/6/2026, 8:23:00 AM	0.0801	0
1/6/2026, 8:24:00 AM	0.079	0
1/6/2026, 8:25:00 AM	0.0778	0
1/6/2026, 8:26:00 AM	0.077	0
1/6/2026, 8:27:00 AM	0.0762	0
1/6/2026, 8:28:00 AM	0.0755	0
1/6/2026, 8:29:00 AM	0.0749	0
1/6/2026, 8:30:00 AM	0.0741	0
1/6/2026, 8:31:00 AM	0.0735	0
1/6/2026, 8:32:00 AM	0.073	0
1/6/2026, 8:33:00 AM	0.0723	0
1/6/2026, 8:34:00 AM	0.071	0
1/6/2026, 8:35:00 AM	0.0692	0
1/6/2026, 8:36:00 AM	0.0689	0

Downwind CAMP Data
260 West 126th Street - New York, NY
Remedial Investigation

Date / Time	Particulates - 15-min Average (mg/m^3)	VOCs - 15-min Average (ppm)
1/6/2026, 8:37:00 AM	0.0689	0
1/6/2026, 8:38:00 AM	0.0689	0
1/6/2026, 8:39:00 AM	0.0688	0
1/6/2026, 8:40:00 AM	0.0689	0
1/6/2026, 8:41:00 AM	0.069	0
1/6/2026, 8:42:00 AM	0.0691	0
1/6/2026, 8:43:00 AM	0.0691	0
1/6/2026, 8:44:00 AM	0.0692	0
1/6/2026, 8:45:00 AM	0.0691	0
1/6/2026, 8:46:00 AM	0.069	0
1/6/2026, 8:47:00 AM	0.0687	0
1/6/2026, 8:48:00 AM	0.0685	0
1/6/2026, 8:49:00 AM	0.0683	0
1/6/2026, 8:50:00 AM	0.0682	0
1/6/2026, 8:51:00 AM	0.0681	0
1/6/2026, 8:52:00 AM	0.0681	0
1/6/2026, 8:53:00 AM	0.0681	0
1/6/2026, 8:54:00 AM	0.0681	0
1/6/2026, 8:55:00 AM	0.068	0
1/6/2026, 8:56:00 AM	0.0677	0
1/6/2026, 8:57:00 AM	0.0673	0
1/6/2026, 8:58:00 AM	0.0671	0
1/6/2026, 8:59:00 AM	0.0667	0
1/6/2026, 9:00:00 AM	0.0667	0
1/6/2026, 9:01:00 AM	0.0666	0
1/6/2026, 9:02:00 AM	0.0667	0
1/6/2026, 9:03:00 AM	0.0667	0
1/6/2026, 9:04:00 AM	0.0666	0
1/6/2026, 9:05:00 AM	0.0665	0
1/6/2026, 9:06:00 AM	0.0665	0
1/6/2026, 9:07:00 AM	0.0663	0
1/6/2026, 9:08:00 AM	0.0663	0
1/6/2026, 9:09:00 AM	0.0661	0
1/6/2026, 9:10:00 AM	0.0661	0
1/6/2026, 9:11:00 AM	0.0663	0
1/6/2026, 9:12:00 AM	0.0665	0
1/6/2026, 9:13:00 AM	0.0667	0
1/6/2026, 9:14:00 AM	0.067	0
1/6/2026, 9:15:00 AM	0.0672	0
1/6/2026, 9:16:00 AM	0.0676	0
1/6/2026, 9:17:00 AM	0.0681	0
1/6/2026, 9:18:00 AM	0.0687	0
1/6/2026, 9:19:00 AM	0.0693	0

Downwind CAMP Data
260 West 126th Street - New York, NY
Remedial Investigation

Date / Time	Particulates - 15-min Average (mg/m^3)	VOCs - 15-min Average (ppm)
1/6/2026, 9:20:00 AM	0.0698	0
1/6/2026, 9:21:00 AM	0.0704	0
1/6/2026, 9:22:00 AM	0.0711	0
1/6/2026, 9:23:00 AM	0.0717	0
1/6/2026, 9:24:00 AM	0.0724	0
1/6/2026, 9:25:00 AM	0.0729	0
1/6/2026, 9:26:00 AM	0.0731	0
1/6/2026, 9:27:00 AM	0.0735	0
1/6/2026, 9:28:00 AM	0.074	0
1/6/2026, 9:29:00 AM	0.0745	0
1/6/2026, 9:30:00 AM	0.0749	0
1/6/2026, 9:31:00 AM	0.0749	0
1/6/2026, 9:32:00 AM	0.0749	0
1/6/2026, 9:33:00 AM	0.0762	0
1/6/2026, 9:34:00 AM	0.0765	0
1/6/2026, 9:35:00 AM	0.0765	0
1/6/2026, 9:36:00 AM	0.0768	0
1/6/2026, 9:37:00 AM	0.0769	0
1/6/2026, 9:38:00 AM	0.0767	0
1/6/2026, 9:39:00 AM	0.0765	0
1/6/2026, 9:40:00 AM	0.0764	0
1/6/2026, 9:41:00 AM	0.0766	0
1/6/2026, 9:42:00 AM	0.0766	0
1/6/2026, 9:43:00 AM	0.0766	0
1/6/2026, 9:44:00 AM	0.0764	0
1/6/2026, 9:45:00 AM	0.0763	0
1/6/2026, 9:46:00 AM	0.0763	0
1/6/2026, 9:47:00 AM	0.0762	0
1/6/2026, 9:48:00 AM	0.075	0
1/6/2026, 9:49:00 AM	0.0749	0
1/6/2026, 9:50:00 AM	0.0749	0
1/6/2026, 9:51:00 AM	0.0747	0
1/6/2026, 9:52:00 AM	0.0745	0
1/6/2026, 9:53:00 AM	0.0746	0
1/6/2026, 9:54:00 AM	0.0747	0
1/6/2026, 9:55:00 AM	0.0748	0
1/6/2026, 9:56:00 AM	0.0749	0
1/6/2026, 9:57:00 AM	0.0751	0
1/6/2026, 9:58:00 AM	0.0753	0
1/6/2026, 9:59:00 AM	0.0755	0
1/6/2026, 10:00:00 AM	0.0759	0
1/6/2026, 10:01:00 AM	0.0762	0
1/6/2026, 10:02:00 AM	0.0765	0

Downwind CAMP Data
260 West 126th Street - New York, NY
Remedial Investigation

Date / Time	Particulates - 15-min Average (mg/m^3)	VOCs - 15-min Average (ppm)
1/6/2026, 10:03:00 AM	0.0767	0
1/6/2026, 10:04:00 AM	0.077	0
1/6/2026, 10:05:00 AM	0.0774	0
1/6/2026, 10:06:00 AM	0.078	0
1/6/2026, 10:07:00 AM	0.0789	0
1/6/2026, 10:08:00 AM	0.0798	0
1/6/2026, 10:09:00 AM	0.0805	0
1/6/2026, 10:10:00 AM	0.081	0
1/6/2026, 10:11:00 AM	0.0815	0
1/6/2026, 10:12:00 AM	0.0819	0
1/6/2026, 10:13:00 AM	0.0837	0
1/6/2026, 10:14:00 AM	0.0845	0
1/6/2026, 10:15:00 AM	0.085	0
1/6/2026, 10:16:00 AM	0.0853	0
1/6/2026, 10:17:00 AM	0.0856	0
1/6/2026, 10:18:00 AM	0.0858	0
1/6/2026, 10:19:00 AM	0.0861	0
1/6/2026, 10:20:00 AM	0.0861	0
1/6/2026, 10:21:00 AM	0.0862	0
1/6/2026, 10:22:00 AM	0.0859	0
1/6/2026, 10:23:00 AM	0.0857	0
1/6/2026, 10:24:00 AM	0.0856	0
1/6/2026, 10:25:00 AM	0.0857	0
1/6/2026, 10:26:00 AM	0.0854	0
1/6/2026, 10:27:00 AM	0.0853	0
1/6/2026, 10:28:00 AM	0.0837	0
1/6/2026, 10:29:00 AM	0.0833	0
1/6/2026, 10:30:00 AM	0.0834	0
1/6/2026, 10:31:00 AM	0.0839	0
1/6/2026, 10:32:00 AM	0.0843	0
1/6/2026, 10:33:00 AM	0.0846	0
1/6/2026, 10:34:00 AM	0.0848	0
1/6/2026, 10:35:00 AM	0.0851	0
1/6/2026, 10:36:00 AM	0.0851	0
1/6/2026, 10:37:00 AM	0.0853	0
1/6/2026, 10:38:00 AM	0.0854	0
1/6/2026, 10:39:00 AM	0.0857	0
1/6/2026, 10:40:00 AM	0.086	0
1/6/2026, 10:41:00 AM	0.0865	0
1/6/2026, 10:42:00 AM	0.087	0
1/6/2026, 10:43:00 AM	0.0875	0
1/6/2026, 10:44:00 AM	0.0879	0
1/6/2026, 10:45:00 AM	0.0879	0

Downwind CAMP Data
260 West 126th Street - New York, NY
Remedial Investigation

Date / Time	Particulates - 15-min Average (mg/m^3)	VOCs - 15-min Average (ppm)
1/6/2026, 10:46:00 AM	0.0877	0
1/6/2026, 10:47:00 AM	0.0877	0
1/6/2026, 10:48:00 AM	0.0876	0
1/6/2026, 10:49:00 AM	0.0875	0
1/6/2026, 10:50:00 AM	0.0874	0
1/6/2026, 10:51:00 AM	0.0873	0
1/6/2026, 10:52:00 AM	0.0873	0
1/6/2026, 10:53:00 AM	0.0872	0
1/6/2026, 10:54:00 AM	0.0871	0
1/6/2026, 10:55:00 AM	0.0869	0
1/6/2026, 10:56:00 AM	0.0867	0
1/6/2026, 10:57:00 AM	0.0867	0
1/6/2026, 10:58:00 AM	0.0867	0
1/6/2026, 10:59:00 AM	0.0867	0
1/6/2026, 11:00:00 AM	0.087	0
1/6/2026, 11:01:00 AM	0.0871	0
1/6/2026, 11:02:00 AM	0.0869	0
1/6/2026, 11:03:00 AM	0.0873	0
1/6/2026, 11:04:00 AM	0.0881	0
1/6/2026, 11:05:00 AM	0.0887	0
1/6/2026, 11:06:00 AM	0.0892	0
1/6/2026, 11:07:00 AM	0.0895	0
1/6/2026, 11:08:00 AM	0.0897	0
1/6/2026, 11:09:00 AM	0.0898	0
1/6/2026, 11:10:00 AM	0.0902	0
1/6/2026, 11:11:00 AM	0.0901	0
1/6/2026, 11:12:00 AM	0.0899	0
1/6/2026, 11:13:00 AM	0.0898	0
1/6/2026, 11:14:00 AM	0.0893	0
1/6/2026, 11:15:00 AM	0.0887	0
1/6/2026, 11:16:00 AM	0.0884	0
1/6/2026, 11:17:00 AM	0.0882	0
1/6/2026, 11:18:00 AM	0.0874	0
1/6/2026, 11:19:00 AM	0.0864	0
1/6/2026, 11:20:00 AM	0.0856	0
1/6/2026, 11:21:00 AM	0.0849	0
1/6/2026, 11:22:00 AM	0.0842	0
1/6/2026, 11:23:00 AM	0.0837	0
1/6/2026, 11:24:00 AM	0.0833	0
1/6/2026, 11:25:00 AM	0.0827	0
1/6/2026, 11:26:00 AM	0.0825	0
1/6/2026, 11:27:00 AM	0.0823	0
1/6/2026, 11:28:00 AM	0.0821	0

Downwind CAMP Data
260 West 126th Street - New York, NY
Remedial Investigation

Date / Time	Particulates - 15-min Average (mg/m^3)	VOCs - 15-min Average (ppm)
1/6/2026, 11:29:00 AM	0.0821	0
1/6/2026, 11:30:00 AM	0.082	0
1/6/2026, 11:31:00 AM	0.082	0
1/6/2026, 11:32:00 AM	0.0825	0
1/6/2026, 11:33:00 AM	0.0825	0
1/6/2026, 11:34:00 AM	0.0825	0
1/6/2026, 11:35:00 AM	0.0824	0
1/6/2026, 11:36:00 AM	0.0825	0
1/6/2026, 11:37:00 AM	0.0825	0
1/6/2026, 11:38:00 AM	0.0824	0
1/6/2026, 11:39:00 AM	0.0823	0
1/6/2026, 11:40:00 AM	0.0821	0
1/6/2026, 11:41:00 AM	0.0819	0
1/6/2026, 11:42:00 AM	0.0817	0
1/6/2026, 11:43:00 AM	0.0816	0
1/6/2026, 11:44:00 AM	0.0815	0
1/6/2026, 11:45:00 AM	0.0812	0
1/6/2026, 11:46:00 AM	0.081	0
1/6/2026, 11:47:00 AM	0.0805	0
1/6/2026, 11:48:00 AM	0.0804	0
1/6/2026, 11:49:00 AM	0.0804	0
1/6/2026, 11:50:00 AM	0.0805	0
1/6/2026, 11:51:00 AM	0.0804	0
1/6/2026, 11:52:00 AM	0.0806	0
1/6/2026, 11:53:00 AM	0.0806	0
1/6/2026, 11:54:00 AM	0.0805	0
1/6/2026, 11:55:00 AM	0.0805	0
1/6/2026, 11:56:00 AM	0.0805	0
1/6/2026, 11:57:00 AM	0.0805	0
1/6/2026, 11:58:00 AM	0.0804	0
1/6/2026, 11:59:00 AM	0.0804	0
1/6/2026, 12:00:00 PM	0.0807	0
1/6/2026, 12:01:00 PM	0.0805	0
1/6/2026, 12:02:00 PM	0.0806	0
1/6/2026, 12:03:00 PM	0.0806	0
1/6/2026, 12:04:00 PM	0.0805	0
1/6/2026, 12:05:00 PM	0.0803	0
1/6/2026, 12:06:00 PM	0.0801	0
1/6/2026, 12:07:00 PM	0.0797	0
1/6/2026, 12:08:00 PM	0.0796	0
1/6/2026, 12:09:00 PM	0.0796	0
1/6/2026, 12:10:00 PM	0.0796	0
1/6/2026, 12:11:00 PM	0.0797	0

Downwind CAMP Data
260 West 126th Street - New York, NY
Remedial Investigation

Date / Time	Particulates - 15-min Average (mg/m^3)	VOCs - 15-min Average (ppm)
1/6/2026, 12:12:00 PM	0.0797	0
1/6/2026, 12:13:00 PM	0.0797	0
1/6/2026, 12:14:00 PM	0.0797	0
1/6/2026, 12:15:00 PM	0.0795	0
1/6/2026, 12:16:00 PM	0.0795	0
1/6/2026, 12:17:00 PM	0.0793	0
1/6/2026, 12:18:00 PM	0.0791	0
1/6/2026, 12:19:00 PM	0.079	0
1/6/2026, 12:20:00 PM	0.0789	0
1/6/2026, 12:21:00 PM	0.079	0
1/6/2026, 12:22:00 PM	0.0791	0
1/6/2026, 12:23:00 PM	0.0792	0
1/6/2026, 12:24:00 PM	0.0793	0
1/6/2026, 12:25:00 PM	0.0793	0
1/6/2026, 12:26:00 PM	0.0794	0
1/6/2026, 12:27:00 PM	0.0796	0
1/6/2026, 12:28:00 PM	0.08	0
1/6/2026, 12:29:00 PM	0.0802	0
1/6/2026, 12:30:00 PM	0.0803	0
1/6/2026, 12:31:00 PM	0.0805	0
1/6/2026, 12:32:00 PM	0.0806	0
1/6/2026, 12:33:00 PM	0.0807	0
1/6/2026, 12:34:00 PM	0.0808	0
1/6/2026, 12:35:00 PM	0.0809	0
1/6/2026, 12:36:00 PM	0.081	0
1/6/2026, 12:37:00 PM	0.0811	0
1/6/2026, 12:38:00 PM	0.0812	0
1/6/2026, 12:39:00 PM	0.0812	0
1/6/2026, 12:40:00 PM	0.0812	0
1/6/2026, 12:41:00 PM	0.0811	0
1/6/2026, 12:42:00 PM	0.0809	0
1/6/2026, 12:43:00 PM	0.0805	0
1/6/2026, 12:44:00 PM	0.0802	0
1/6/2026, 12:45:00 PM	0.0801	0
1/6/2026, 12:46:00 PM	0.08	0
1/6/2026, 12:47:00 PM	0.0799	0
1/6/2026, 12:48:00 PM	0.0798	0
1/6/2026, 12:49:00 PM	0.0797	0
1/6/2026, 12:50:00 PM	0.0796	0
1/6/2026, 12:51:00 PM	0.0795	0
1/6/2026, 12:52:00 PM	0.0793	0
1/6/2026, 12:53:00 PM	0.0792	0
1/6/2026, 12:54:00 PM	0.0793	0

Downwind CAMP Data
260 West 126th Street - New York, NY
Remedial Investigation

Date / Time	Particulates - 15-min Average (mg/m^3)	VOCs - 15-min Average (ppm)
1/6/2026, 12:55:00 PM	0.0795	0
1/6/2026, 12:56:00 PM	0.0797	0
1/6/2026, 12:57:00 PM	0.0801	0
1/6/2026, 12:58:00 PM	0.0805	0
1/6/2026, 12:59:00 PM	0.0808	0
1/6/2026, 1:00:00 PM	0.081	0
1/6/2026, 1:01:00 PM	0.0813	0
1/6/2026, 1:02:00 PM	0.0819	0
1/6/2026, 1:03:00 PM	0.0823	0
1/6/2026, 1:04:00 PM	0.0825	0
1/6/2026, 1:05:00 PM	0.083	0
1/6/2026, 1:06:00 PM	0.0833	0
1/6/2026, 1:07:00 PM	0.0837	0
1/6/2026, 1:08:00 PM	0.0841	0
1/6/2026, 1:09:00 PM	0.0845	0
1/6/2026, 1:10:00 PM	0.0846	0
1/6/2026, 1:11:00 PM	0.0846	0
1/6/2026, 1:12:00 PM	0.0845	0
1/6/2026, 1:13:00 PM	0.0846	0
1/6/2026, 1:14:00 PM	0.0846	0
1/6/2026, 1:15:00 PM	0.0847	0
1/6/2026, 1:16:00 PM	0.0846	0
1/6/2026, 1:17:00 PM	0.0841	0
1/6/2026, 1:18:00 PM	0.084	0
1/6/2026, 1:19:00 PM	0.0839	0
1/6/2026, 1:20:00 PM	0.0837	0
1/6/2026, 1:21:00 PM	0.0836	0
1/6/2026, 1:22:00 PM	0.0835	0
1/6/2026, 1:23:00 PM	0.0835	0
1/6/2026, 1:24:00 PM	0.0832	0
1/6/2026, 1:25:00 PM	0.0831	0
1/6/2026, 1:26:00 PM	0.0833	0
1/6/2026, 1:27:00 PM	0.0832	0
1/6/2026, 1:28:00 PM	0.083	0
1/6/2026, 1:29:00 PM	0.0831	0
1/6/2026, 1:30:00 PM	0.0833	0
1/6/2026, 1:31:00 PM	0.0835	0
1/6/2026, 1:32:00 PM	0.0837	0
1/6/2026, 1:33:00 PM	0.0839	0
1/6/2026, 1:34:00 PM	0.0842	0
1/6/2026, 1:35:00 PM	0.0844	0
1/6/2026, 1:36:00 PM	0.0846	0
1/6/2026, 1:37:00 PM	0.0847	0

Downwind CAMP Data
260 West 126th Street - New York, NY
Remedial Investigation

Date / Time	Particulates - 15-min Average (mg/m^3)	VOCs - 15-min Average (ppm)
1/6/2026, 1:38:00 PM	0.0847	0
1/6/2026, 1:39:00 PM	0.0849	0
1/6/2026, 1:40:00 PM	0.0851	0
1/6/2026, 1:41:00 PM	0.0851	0
1/6/2026, 1:42:00 PM	0.0851	0
1/6/2026, 1:43:00 PM	0.0851	0
1/6/2026, 1:44:00 PM	0.0849	0
1/6/2026, 1:45:00 PM	0.0846	0
1/6/2026, 1:46:00 PM	0.0843	0
1/6/2026, 1:47:00 PM	0.0843	0
1/6/2026, 1:48:00 PM	0.0842	0
1/6/2026, 1:49:00 PM	0.084	0
1/6/2026, 1:50:00 PM	0.084	0
1/6/2026, 1:51:00 PM	0.0837	0
1/6/2026, 1:52:00 PM	0.0833	0
1/6/2026, 1:53:00 PM	0.083	0
1/6/2026, 1:54:00 PM	0.0826	0
1/6/2026, 1:55:00 PM	0.0823	0
1/6/2026, 1:56:00 PM	0.0821	0
1/6/2026, 1:57:00 PM	0.0821	0
1/6/2026, 1:58:00 PM	0.0821	0
1/6/2026, 1:59:00 PM	0.082	0
1/6/2026, 2:00:00 PM	0.0822	0
1/6/2026, 2:01:00 PM	0.0822	0
1/6/2026, 2:02:00 PM	0.0819	0
1/6/2026, 2:03:00 PM	0.0817	0
1/6/2026, 2:04:00 PM	0.0815	0
1/6/2026, 2:05:00 PM	0.0811	0
1/6/2026, 2:06:00 PM	0.0811	0
1/6/2026, 2:07:00 PM	0.0812	0
1/6/2026, 2:08:00 PM	0.0811	0
1/6/2026, 2:09:00 PM	0.0809	0
1/6/2026, 2:10:00 PM	0.0807	0
1/6/2026, 2:11:00 PM	0.0804	0
1/6/2026, 2:12:00 PM	0.0802	0
1/6/2026, 2:13:00 PM	0.0798	0
1/6/2026, 2:14:00 PM	0.0795	0
1/6/2026, 2:15:00 PM	0.0791	0
1/6/2026, 2:16:00 PM	0.0789	0
1/6/2026, 2:17:00 PM	0.0787	0
1/6/2026, 2:18:00 PM	0.0786	0
1/6/2026, 2:19:00 PM	0.0785	0
1/6/2026, 2:20:00 PM	0.0783	0

Downwind CAMP Data
260 West 126th Street - New York, NY
Remedial Investigation

Date / Time	Particulates - 15-min Average (mg/m^3)	VOCs - 15-min Average (ppm)
1/6/2026, 2:21:00 PM	0.0782	0
1/6/2026, 2:22:00 PM	0.0779	0
1/6/2026, 2:23:00 PM	0.0778	0
1/6/2026, 2:24:00 PM	0.0778	0
1/6/2026, 2:25:00 PM	0.0777	0
1/6/2026, 2:26:00 PM	0.0776	0
1/6/2026, 2:27:00 PM	0.0775	0
1/6/2026, 2:28:00 PM	0.0773	0
1/6/2026, 2:29:00 PM	0.0773	0
1/6/2026, 2:30:00 PM	0.0773	0
1/6/2026, 2:31:00 PM	0.0771	0
1/6/2026, 2:32:00 PM	0.0771	0
1/6/2026, 2:33:00 PM	0.0771	0
1/6/2026, 2:34:00 PM	0.077	0
1/6/2026, 2:35:00 PM	0.077	0
1/6/2026, 2:36:00 PM	0.077	0
1/6/2026, 2:37:00 PM	0.0773	0
1/6/2026, 2:38:00 PM	0.0776	0
1/6/2026, 2:39:00 PM	0.0777	0
1/6/2026, 2:40:00 PM	0.0779	0
1/6/2026, 2:41:00 PM	0.0781	0
1/6/2026, 2:42:00 PM	0.078	0
1/6/2026, 2:43:00 PM	0.0782	0
1/6/2026, 2:44:00 PM	0.0785	0
1/6/2026, 2:45:00 PM	0.0787	0
1/6/2026, 2:46:00 PM	0.0789	0
1/6/2026, 2:47:00 PM	0.0788	0
1/6/2026, 2:48:00 PM	0.0788	0
1/6/2026, 2:49:00 PM	0.0787	0
1/6/2026, 2:50:00 PM	0.0786	0
1/6/2026, 2:51:00 PM	0.0785	0
1/6/2026, 2:52:00 PM	0.078	0
1/6/2026, 2:53:00 PM	0.0777	0
1/6/2026, 2:54:00 PM	0.0775	0
1/6/2026, 2:55:00 PM	0.0773	0
1/6/2026, 2:56:00 PM	0.0772	0
1/6/2026, 2:57:00 PM	0.0772	0
1/6/2026, 2:58:00 PM	0.0769	0
1/6/2026, 2:59:00 PM	0.0766	0
1/6/2026, 3:00:00 PM	0.0762	0
1/6/2026, 3:01:00 PM	0.0759	0
1/6/2026, 3:02:00 PM	0.0758	0
1/6/2026, 3:03:00 PM	0.0756	0

Downwind CAMP Data
260 West 126th Street - New York, NY
Remedial Investigation

Date / Time	Particulates - 15-min Average (mg/m^3)	VOCs - 15-min Average (ppm)
1/6/2026, 3:04:00 PM	0.0756	0
1/6/2026, 3:05:00 PM	0.0756	0
1/6/2026, 3:06:00 PM	0.0756	0
1/6/2026, 3:07:00 PM	0.0757	0
1/6/2026, 3:08:00 PM	0.0758	0
1/6/2026, 3:09:00 PM	0.0758	0
1/6/2026, 3:10:00 PM	0.0757	0
1/6/2026, 3:11:00 PM	0.0756	0
1/6/2026, 3:12:00 PM	0.0755	0
1/6/2026, 3:13:00 PM	0.0755	0
1/6/2026, 3:14:00 PM	0.0755	0
1/6/2026, 3:15:00 PM	0.0755	0
1/6/2026, 3:16:00 PM	0.0755	0
1/6/2026, 3:17:00 PM	0.0754	0
1/6/2026, 3:18:00 PM	0.0753	0
1/6/2026, 3:19:00 PM	0.0751	0
1/6/2026, 3:20:00 PM	0.0751	0
1/6/2026, 3:21:00 PM	0.0749	0
1/6/2026, 3:22:00 PM	0.0747	0
1/6/2026, 3:23:00 PM	0.0743	0
1/7/2026, 8:16:00 AM		0
1/7/2026, 8:17:00 AM	0.123	0
1/7/2026, 8:18:00 AM	0.1255	0
1/7/2026, 8:19:00 AM	0.125	0
1/7/2026, 8:20:00 AM	0.1243	0
1/7/2026, 8:21:00 AM	0.1236	0
1/7/2026, 8:22:00 AM	0.1232	0
1/7/2026, 8:23:00 AM	0.124	0
1/7/2026, 8:24:00 AM	0.1246	0
1/7/2026, 8:25:00 AM	0.1256	0
1/7/2026, 8:26:00 AM	0.1256	0
1/7/2026, 8:27:00 AM	0.1248	0
1/7/2026, 8:28:00 AM	0.1245	0
1/7/2026, 8:29:00 AM	0.1239	0
1/7/2026, 8:30:00 AM	0.1233	0
1/7/2026, 8:31:00 AM	0.1225	0
1/7/2026, 8:32:00 AM	0.1218	0
1/7/2026, 8:33:00 AM	0.1205	0
1/7/2026, 8:34:00 AM	0.1193	0
1/7/2026, 8:35:00 AM	0.1182	0
1/7/2026, 8:36:00 AM	0.1171	0
1/7/2026, 8:37:00 AM	0.1159	0
1/7/2026, 8:38:00 AM	0.1142	0

Downwind CAMP Data
260 West 126th Street - New York, NY
Remedial Investigation

Date / Time	Particulates - 15-min Average (mg/m^3)	VOCs - 15-min Average (ppm)
1/7/2026, 8:39:00 AM	0.1124	0
1/7/2026, 8:40:00 AM	0.1104	0
1/7/2026, 8:41:00 AM	0.1091	0
1/7/2026, 8:42:00 AM	0.1084	0
1/7/2026, 8:43:00 AM	0.1077	0
1/7/2026, 8:44:00 AM	0.1068	0
1/7/2026, 8:45:00 AM	0.1059	0
1/7/2026, 8:46:00 AM	0.1053	0
1/7/2026, 8:47:00 AM	0.1051	0
1/7/2026, 8:48:00 AM	0.1047	0
1/7/2026, 8:49:00 AM	0.1046	0
1/7/2026, 8:50:00 AM	0.1047	0
1/7/2026, 8:51:00 AM	0.1053	0
1/7/2026, 8:52:00 AM	0.1057	0
1/7/2026, 8:53:00 AM	0.1062	0
1/7/2026, 8:54:00 AM	0.1065	0
1/7/2026, 8:55:00 AM	0.1065	0
1/7/2026, 8:56:00 AM	0.1062	0
1/7/2026, 8:57:00 AM	0.1056	0
1/7/2026, 8:58:00 AM	0.1048	0
1/7/2026, 8:59:00 AM	0.1046	0
1/7/2026, 9:00:00 AM	0.1045	0
1/7/2026, 9:01:00 AM	0.1047	0
1/7/2026, 9:02:00 AM	0.1041	0
1/7/2026, 9:03:00 AM	0.1033	0
1/7/2026, 9:04:00 AM	0.1025	0
1/7/2026, 9:05:00 AM	0.1013	0
1/7/2026, 9:06:00 AM	0.0995	0
1/7/2026, 9:07:00 AM	0.0981	0
1/7/2026, 9:08:00 AM	0.0964	0
1/7/2026, 9:09:00 AM	0.0951	0
1/7/2026, 9:10:00 AM	0.0942	0
1/7/2026, 9:11:00 AM	0.0933	0
1/7/2026, 9:12:00 AM	0.0927	0
1/7/2026, 9:13:00 AM	0.0919	0
1/7/2026, 9:14:00 AM	0.0909	0
1/7/2026, 9:15:00 AM	0.09	0
1/7/2026, 9:16:00 AM	0.0887	0
1/7/2026, 9:17:00 AM	0.0879	0
1/7/2026, 9:18:00 AM	0.0874	0
1/7/2026, 9:19:00 AM	0.0874	0
1/7/2026, 9:20:00 AM	0.0873	0
1/7/2026, 9:21:00 AM	0.0874	0

Downwind CAMP Data
260 West 126th Street - New York, NY
Remedial Investigation

Date / Time	Particulates - 15-min Average (mg/m^3)	VOCs - 15-min Average (ppm)
1/7/2026, 9:22:00 AM	0.0875	0
1/7/2026, 9:23:00 AM	0.0875	0
1/7/2026, 9:24:00 AM	0.0873	0
1/7/2026, 9:25:00 AM	0.087	0
1/7/2026, 9:26:00 AM	0.0867	0
1/7/2026, 9:27:00 AM	0.0865	0
1/7/2026, 9:28:00 AM	0.0863	0
1/7/2026, 9:29:00 AM	0.0861	0
1/7/2026, 9:30:00 AM	0.0859	0
1/7/2026, 9:31:00 AM	0.0857	0
1/7/2026, 9:32:00 AM	0.0855	0
1/7/2026, 9:33:00 AM	0.0854	0
1/7/2026, 9:34:00 AM	0.0849	0
1/7/2026, 9:35:00 AM	0.0846	0
1/7/2026, 9:36:00 AM	0.0843	0
1/7/2026, 9:37:00 AM	0.084	0
1/7/2026, 9:38:00 AM	0.0839	0
1/7/2026, 9:39:00 AM	0.0838	0
1/7/2026, 9:40:00 AM	0.0837	0
1/7/2026, 9:41:00 AM	0.0837	0
1/7/2026, 9:42:00 AM	0.0856	0.082
1/7/2026, 9:43:00 AM	0.0856	0.097
1/7/2026, 9:44:00 AM	0.0857	0.097
1/7/2026, 9:45:00 AM	0.0858	0.097
1/7/2026, 9:46:00 AM	0.086	0.097
1/7/2026, 9:47:00 AM	0.0863	0.097
1/7/2026, 9:48:00 AM	0.0865	0.097
1/7/2026, 9:49:00 AM	0.0867	0.097
1/7/2026, 9:50:00 AM	0.0868	0.097
1/7/2026, 9:51:00 AM	0.0871	0.097
1/7/2026, 9:52:00 AM	0.0874	0.097
1/7/2026, 9:53:00 AM	0.0875	0.097
1/7/2026, 9:54:00 AM	0.0875	0.097
1/7/2026, 9:55:00 AM	0.0876	0.097
1/7/2026, 9:56:00 AM	0.0876	0.097
1/7/2026, 9:57:00 AM	0.0857	0.014
1/7/2026, 9:58:00 AM	0.0837	0
1/7/2026, 9:59:00 AM	0.0838	0
1/7/2026, 10:00:00 AM	0.0841	0
1/7/2026, 10:01:00 AM	0.0843	0
1/7/2026, 10:02:00 AM	0.0844	0
1/7/2026, 10:03:00 AM	0.0845	0
1/7/2026, 10:04:00 AM	0.0847	0

Downwind CAMP Data
260 West 126th Street - New York, NY
Remedial Investigation

Date / Time	Particulates - 15-min Average (mg/m^3)	VOCs - 15-min Average (ppm)
1/7/2026, 10:05:00 AM	0.0849	0
1/7/2026, 10:06:00 AM	0.0849	0
1/7/2026, 10:07:00 AM	0.085	0
1/7/2026, 10:08:00 AM	0.0853	0
1/7/2026, 10:09:00 AM	0.0856	0
1/7/2026, 10:10:00 AM	0.0859	0
1/7/2026, 10:11:00 AM	0.0862	0
1/7/2026, 10:12:00 AM	0.0865	0
1/7/2026, 10:13:00 AM	0.0889	0
1/7/2026, 10:14:00 AM	0.089	0
1/7/2026, 10:15:00 AM	0.089	0
1/7/2026, 10:16:00 AM	0.089	0
1/7/2026, 10:17:00 AM	0.089	0
1/7/2026, 10:18:00 AM	0.089	0
1/7/2026, 10:19:00 AM	0.089	0
1/7/2026, 10:20:00 AM	0.089	0
1/7/2026, 10:21:00 AM	0.089	0
1/7/2026, 10:22:00 AM	0.089	0
1/7/2026, 10:23:00 AM	0.089	0
1/7/2026, 10:24:00 AM	0.089	0
1/7/2026, 10:25:00 AM	0.089	0
1/7/2026, 10:26:00 AM	0.089	0
1/7/2026, 10:27:00 AM	0.089	0
1/7/2026, 10:28:00 AM	0.089	0
1/7/2026, 10:29:00 AM	0.089	0
1/7/2026, 10:30:00 AM	0.089	0
1/7/2026, 10:31:00 AM	0.089	0
1/7/2026, 10:32:00 AM	0.089	0
1/7/2026, 10:33:00 AM	0.089	0
1/7/2026, 10:34:00 AM	0.089	0
1/7/2026, 10:35:00 AM	0.089	0
1/7/2026, 10:36:00 AM	0.089	0
1/7/2026, 10:37:00 AM	0.089	0
1/7/2026, 10:38:00 AM	0.089	0
1/7/2026, 10:39:00 AM	0.089	0
1/7/2026, 10:40:00 AM	0.089	0
1/9/2026, 7:19:00 AM		0
1/9/2026, 7:20:00 AM	0.068	0
1/9/2026, 7:21:00 AM	0.0525	0
1/9/2026, 7:22:00 AM	0.0463	0
1/9/2026, 7:23:00 AM	0.0433	0
1/9/2026, 7:24:00 AM	0.0414	0
1/9/2026, 7:25:00 AM	0.0402	0

Downwind CAMP Data
260 West 126th Street - New York, NY
Remedial Investigation

Date / Time	Particulates - 15-min Average (mg/m^3)	VOCs - 15-min Average (ppm)
1/9/2026, 7:26:00 AM	0.0393	0
1/9/2026, 7:27:00 AM	0.0386	0
1/9/2026, 7:28:00 AM	0.0381	0
1/9/2026, 7:29:00 AM	0.0377	0
1/9/2026, 7:30:00 AM	0.0374	0
1/9/2026, 7:31:00 AM	0.0371	0
1/9/2026, 7:32:00 AM	0.0368	0
1/9/2026, 7:33:00 AM	0.0366	0
1/9/2026, 7:34:00 AM	0.0365	0
1/9/2026, 7:35:00 AM	0.0342	0
1/9/2026, 7:36:00 AM	0.034	0
1/9/2026, 7:37:00 AM	0.034	0
1/9/2026, 7:38:00 AM	0.034	0
1/9/2026, 7:39:00 AM	0.034	0
1/9/2026, 7:40:00 AM	0.034	0
1/9/2026, 7:41:00 AM	0.034	0
1/9/2026, 7:42:00 AM	0.034	0
1/9/2026, 7:43:00 AM	0.034	0
1/9/2026, 7:44:00 AM	0.034	0
1/9/2026, 7:45:00 AM	0.034	0
1/9/2026, 7:46:00 AM	0.034	0
1/9/2026, 7:47:00 AM	0.034	0
1/9/2026, 7:48:00 AM	0.034	0
1/9/2026, 7:49:00 AM	0.034	0
1/9/2026, 7:50:00 AM	0.034	0
1/9/2026, 7:51:00 AM	0.034	0
1/9/2026, 7:55:00 AM	0.0368	0
1/9/2026, 7:56:00 AM	0.0398	0
1/9/2026, 7:57:00 AM	0.0428	0
1/9/2026, 7:58:00 AM	0.0455	0
1/9/2026, 7:59:00 AM	0.0482	0
1/9/2026, 8:00:00 AM	0.0507	0
1/9/2026, 8:01:00 AM	0.0531	0
1/9/2026, 8:02:00 AM	0.0553	0
1/9/2026, 8:03:00 AM	0.0571	0
1/9/2026, 8:04:00 AM	0.0588	0
1/9/2026, 8:05:00 AM	0.0608	0
1/9/2026, 8:06:00 AM	0.0625	0
1/9/2026, 8:07:00 AM	0.0619	0
1/9/2026, 8:08:00 AM	0.0631	0
1/9/2026, 8:09:00 AM	0.0627	0
1/9/2026, 8:10:00 AM	0.0616	0
1/9/2026, 8:11:00 AM	0.0605	0

Downwind CAMP Data
260 West 126th Street - New York, NY
Remedial Investigation

Date / Time	Particulates - 15-min Average (mg/m^3)	VOCs - 15-min Average (ppm)
1/9/2026, 8:12:00 AM	0.0592	0
1/9/2026, 8:13:00 AM	0.058	0
1/9/2026, 8:14:00 AM	0.0569	0
1/9/2026, 8:15:00 AM	0.0557	0
1/9/2026, 8:16:00 AM	0.0548	0
1/9/2026, 8:17:00 AM	0.0539	0
1/9/2026, 8:18:00 AM	0.0532	0
1/9/2026, 8:19:00 AM	0.0523	0
1/9/2026, 8:20:00 AM	0.0512	0
1/9/2026, 8:21:00 AM	0.0505	0
1/9/2026, 8:22:00 AM	0.0498	0
1/9/2026, 8:23:00 AM	0.0483	0
1/9/2026, 8:24:00 AM	0.0491	0
1/9/2026, 8:25:00 AM	0.0502	0
1/9/2026, 8:26:00 AM	0.0509	0
1/9/2026, 8:27:00 AM	0.0519	0
1/9/2026, 8:28:00 AM	0.0529	0
1/9/2026, 8:29:00 AM	0.0538	0
1/9/2026, 8:30:00 AM	0.0549	0
1/9/2026, 8:31:00 AM	0.0559	0
1/9/2026, 8:32:00 AM	0.0568	0
1/9/2026, 8:33:00 AM	0.0579	0
1/9/2026, 8:34:00 AM	0.0589	0
1/9/2026, 8:35:00 AM	0.0598	0
1/9/2026, 8:36:00 AM	0.0609	0
1/9/2026, 8:37:00 AM	0.0621	0
1/9/2026, 8:38:00 AM	0.0629	0
1/9/2026, 8:39:00 AM	0.0629	0
1/9/2026, 8:40:00 AM	0.0632	0
1/9/2026, 8:41:00 AM	0.0623	0
1/9/2026, 8:42:00 AM	0.0616	0
1/9/2026, 8:43:00 AM	0.0612	0
1/9/2026, 8:44:00 AM	0.0609	0
1/9/2026, 8:45:00 AM	0.0604	0
1/9/2026, 8:46:00 AM	0.0599	0
1/9/2026, 8:47:00 AM	0.0588	0
1/9/2026, 8:48:00 AM	0.0574	0
1/9/2026, 8:49:00 AM	0.0561	0
1/9/2026, 8:50:00 AM	0.0547	0
1/9/2026, 8:51:00 AM	0.0528	0
1/9/2026, 8:52:00 AM	0.0507	0
1/9/2026, 8:53:00 AM	0.0483	0
1/9/2026, 8:54:00 AM	0.0456	0

Downwind CAMP Data
260 West 126th Street - New York, NY
Remedial Investigation

Date / Time	Particulates - 15-min Average (mg/m^3)	VOCs - 15-min Average (ppm)
1/9/2026, 8:55:00 AM	0.0428	0
1/9/2026, 8:56:00 AM	0.0413	0
1/9/2026, 8:57:00 AM	0.0396	0
1/9/2026, 8:58:00 AM	0.0376	0
1/9/2026, 8:59:00 AM	0.0357	0
1/9/2026, 9:00:00 AM	0.0339	0
1/9/2026, 9:01:00 AM	0.0327	0
1/9/2026, 9:02:00 AM	0.0335	0
1/9/2026, 9:03:00 AM	0.0334	0
1/9/2026, 9:04:00 AM	0.0335	0
1/9/2026, 9:05:00 AM	0.034	0
1/9/2026, 9:06:00 AM	0.0343	0
1/9/2026, 9:07:00 AM	0.0345	0
1/9/2026, 9:08:00 AM	0.0348	0
1/9/2026, 9:09:00 AM	0.0352	0
1/9/2026, 9:10:00 AM	0.0356	0
1/9/2026, 9:11:00 AM	0.0363	0
1/9/2026, 9:12:00 AM	0.0368	0
1/9/2026, 9:13:00 AM	0.0374	0
1/9/2026, 9:14:00 AM	0.0379	0
1/9/2026, 9:15:00 AM	0.0385	0
1/9/2026, 9:16:00 AM	0.0385	0
1/9/2026, 9:17:00 AM	0.0372	0
1/9/2026, 9:18:00 AM	0.0371	0
1/9/2026, 9:19:00 AM	0.0371	0
1/9/2026, 9:20:00 AM	0.0367	0
1/9/2026, 9:21:00 AM	0.0366	0
1/9/2026, 9:22:00 AM	0.0365	0
1/9/2026, 9:23:00 AM	0.0363	0
1/9/2026, 9:24:00 AM	0.0362	0
1/9/2026, 9:25:00 AM	0.0362	0
1/9/2026, 9:26:00 AM	0.0363	0
1/9/2026, 9:27:00 AM	0.0361	0
1/9/2026, 9:28:00 AM	0.0359	0
1/9/2026, 9:29:00 AM	0.0359	0
1/9/2026, 9:30:00 AM	0.0357	0
1/9/2026, 9:31:00 AM	0.0355	0
1/9/2026, 9:32:00 AM	0.0352	0
1/9/2026, 9:33:00 AM	0.0349	0
1/9/2026, 9:34:00 AM	0.0349	0
1/9/2026, 9:35:00 AM	0.0349	0
1/9/2026, 9:36:00 AM	0.0349	0
1/9/2026, 9:37:00 AM	0.0348	0

Downwind CAMP Data
260 West 126th Street - New York, NY
Remedial Investigation

Date / Time	Particulates - 15-min Average (mg/m^3)	VOCs - 15-min Average (ppm)
1/9/2026, 9:38:00 AM	0.0347	0
1/9/2026, 9:39:00 AM	0.0346	0
1/9/2026, 9:40:00 AM	0.0345	0
1/9/2026, 9:41:00 AM	0.0341	0
1/9/2026, 9:42:00 AM	0.0342	0
1/9/2026, 9:43:00 AM	0.0345	0
1/9/2026, 9:44:00 AM	0.0345	0
1/9/2026, 9:45:00 AM	0.0351	0
1/9/2026, 9:46:00 AM	0.0355	0
1/9/2026, 9:47:00 AM	0.0357	0
1/9/2026, 9:48:00 AM	0.0357	0
1/9/2026, 9:49:00 AM	0.0352	0
1/9/2026, 9:50:00 AM	0.0348	0
1/9/2026, 9:51:00 AM	0.0345	0
1/9/2026, 9:52:00 AM	0.0343	0
1/9/2026, 9:53:00 AM	0.0341	0
1/9/2026, 9:54:00 AM	0.0342	0
1/9/2026, 9:55:00 AM	0.0343	0
1/9/2026, 9:56:00 AM	0.0341	0
1/9/2026, 9:57:00 AM	0.0337	0
1/9/2026, 9:58:00 AM	0.0332	0
1/9/2026, 9:59:00 AM	0.0327	0
1/9/2026, 10:00:00 AM	0.0318	0
1/9/2026, 10:01:00 AM	0.0312	0
1/9/2026, 10:02:00 AM	0.0308	0
1/9/2026, 10:03:00 AM	0.031	0
1/9/2026, 10:04:00 AM	0.0317	0
1/9/2026, 10:05:00 AM	0.0316	0
6/26/2026, 6:40:00 AM		0
6/26/2026, 6:41:00 AM	0.036	0
6/26/2026, 6:42:00 AM	0.033	0
6/26/2026, 6:43:00 AM	0.032	0
6/26/2026, 6:44:00 AM	0.0318	0
6/26/2026, 6:45:00 AM	0.0316	0
6/26/2026, 6:46:00 AM	0.0313	0
6/26/2026, 6:47:00 AM	0.031	0
6/26/2026, 6:48:00 AM	0.0308	0
6/26/2026, 6:49:00 AM	0.0307	0
6/26/2026, 6:50:00 AM	0.0306	0
6/26/2026, 6:51:00 AM	0.0303	0
6/26/2026, 6:52:00 AM	0.03	0
6/26/2026, 6:53:00 AM	0.0298	0
6/26/2026, 6:54:00 AM	0.0297	0

Downwind CAMP Data
260 West 126th Street - New York, NY
Remedial Investigation

Date / Time	Particulates - 15-min Average (mg/m^3)	VOCs - 15-min Average (ppm)
6/26/2026, 6:55:00 AM	0.0296	0
6/26/2026, 6:56:00 AM	0.029	0
6/26/2026, 6:57:00 AM	0.0287	0
6/26/2026, 6:58:00 AM	0.0285	0
6/26/2026, 6:59:00 AM	0.0281	0
6/26/2026, 7:00:00 AM	0.0278	0
6/26/2026, 7:01:00 AM	0.0275	0
6/26/2026, 7:02:00 AM	0.0273	0
6/26/2026, 7:03:00 AM	0.0271	0
6/26/2026, 7:04:00 AM	0.0267	0
6/26/2026, 7:05:00 AM	0.0264	0
6/26/2026, 7:06:00 AM	0.0264	0
6/26/2026, 7:07:00 AM	0.0264	0
6/26/2026, 7:08:00 AM	0.0263	0
6/26/2026, 7:09:00 AM	0.0261	0
6/26/2026, 7:10:00 AM	0.0259	0
6/26/2026, 7:11:00 AM	0.0258	0
6/26/2026, 7:12:00 AM	0.0257	0
6/26/2026, 7:13:00 AM	0.0257	0
6/26/2026, 7:14:00 AM	0.0257	0
6/26/2026, 7:15:00 AM	0.0256	0
6/26/2026, 7:16:00 AM	0.0255	0
6/26/2026, 7:17:00 AM	0.0255	0
6/26/2026, 7:18:00 AM	0.0255	0
6/26/2026, 7:19:00 AM	0.0254	0
6/26/2026, 7:20:00 AM	0.0254	0
6/26/2026, 7:21:00 AM	0.0253	0
6/26/2026, 7:22:00 AM	0.0251	0
6/26/2026, 7:23:00 AM	0.025	0
6/26/2026, 7:24:00 AM	0.025	0
6/26/2026, 7:25:00 AM	0.025	0
6/26/2026, 7:26:00 AM	0.025	0
6/26/2026, 7:27:00 AM	0.0249	0
6/26/2026, 7:28:00 AM	0.0247	0
6/26/2026, 7:29:00 AM	0.0246	0
6/26/2026, 7:30:00 AM	0.0245	0
6/26/2026, 7:31:00 AM	0.0246	0
6/26/2026, 7:32:00 AM	0.0247	0
6/26/2026, 7:33:00 AM	0.0247	0
6/26/2026, 7:34:00 AM	0.0247	0
6/26/2026, 7:35:00 AM	0.0248	0
6/26/2026, 7:36:00 AM	0.0248	0
6/26/2026, 7:37:00 AM	0.0308	0

Downwind CAMP Data
260 West 126th Street - New York, NY
Remedial Investigation

Date / Time	Particulates - 15-min Average (mg/m^3)	VOCs - 15-min Average (ppm)
6/26/2026, 7:38:00 AM	0.0411	0
6/26/2026, 7:39:00 AM	0.0468	0
6/26/2026, 7:40:00 AM	0.0491	0
6/26/2026, 7:41:00 AM	0.0525	0
6/26/2026, 7:42:00 AM	0.0563	0
6/26/2026, 7:43:00 AM	0.0582	0
6/26/2026, 7:44:00 AM	0.0627	0
6/26/2026, 7:45:00 AM	0.0656	0
6/26/2026, 7:46:00 AM	0.0676	0
6/26/2026, 7:47:00 AM	0.0681	0
6/26/2026, 7:48:00 AM	0.0683	0
6/26/2026, 7:49:00 AM	0.0685	0
6/26/2026, 7:50:00 AM	0.0685	0
6/26/2026, 7:51:00 AM	0.0685	0
6/26/2026, 7:52:00 AM	0.0625	0
6/26/2026, 7:53:00 AM	0.0522	0
6/26/2026, 7:54:00 AM	0.0465	0
6/26/2026, 7:55:00 AM	0.0442	0
6/26/2026, 7:56:00 AM	0.0407	0
6/26/2026, 7:57:00 AM	0.0372	0
6/26/2026, 7:58:00 AM	0.0355	0
6/26/2026, 7:59:00 AM	0.0321	0
6/26/2026, 8:00:00 AM	0.0327	0
6/26/2026, 8:01:00 AM	0.0339	0
6/26/2026, 8:02:00 AM	0.0367	0
6/26/2026, 8:03:00 AM	0.0384	0
6/26/2026, 8:04:00 AM	0.0394	0
6/26/2026, 8:05:00 AM	0.0405	0
6/26/2026, 8:06:00 AM	0.0408	0
6/26/2026, 8:07:00 AM	0.0413	0
6/26/2026, 8:08:00 AM	0.0437	0
6/26/2026, 8:09:00 AM	0.0437	0
6/26/2026, 8:10:00 AM	0.0451	0
6/26/2026, 8:11:00 AM	0.0457	0
6/26/2026, 8:12:00 AM	0.0459	0
6/26/2026, 8:13:00 AM	0.0469	0
6/26/2026, 8:14:00 AM	0.0464	0
6/26/2026, 8:15:00 AM	0.0435	0
6/26/2026, 8:16:00 AM	0.0407	0
6/26/2026, 8:17:00 AM	0.0383	0
6/26/2026, 8:18:00 AM	0.037	0
6/26/2026, 8:19:00 AM	0.036	0
6/26/2026, 8:20:00 AM	0.035	0

Downwind CAMP Data
260 West 126th Street - New York, NY
Remedial Investigation

Date / Time	Particulates - 15-min Average (mg/m^3)	VOCs - 15-min Average (ppm)
6/26/2026, 8:21:00 AM	0.0349	0
6/26/2026, 8:22:00 AM	0.0346	0
6/26/2026, 8:23:00 AM	0.033	0
6/26/2026, 8:24:00 AM	0.0337	0
6/26/2026, 8:25:00 AM	0.0327	0
6/26/2026, 8:26:00 AM	0.0324	0
6/26/2026, 8:27:00 AM	0.0325	0
6/26/2026, 8:28:00 AM	0.0315	0
6/26/2026, 8:29:00 AM	0.0307	0
6/26/2026, 8:30:00 AM	0.0303	0
6/26/2026, 8:31:00 AM	0.0295	0
6/26/2026, 8:32:00 AM	0.0281	0
6/26/2026, 8:33:00 AM	0.0272	0
6/26/2026, 8:34:00 AM	0.0267	0
6/26/2026, 8:35:00 AM	0.0261	0
6/26/2026, 8:36:00 AM	0.0256	0
6/26/2026, 8:37:00 AM	0.0251	0
6/26/2026, 8:38:00 AM	0.0239	0
6/26/2026, 8:39:00 AM	0.0228	0
6/26/2026, 8:40:00 AM	0.0219	0
6/26/2026, 8:41:00 AM	0.0213	0
6/26/2026, 8:42:00 AM	0.0205	0
6/26/2026, 8:43:00 AM	0.0204	0
6/26/2026, 8:44:00 AM	0.021	0
6/26/2026, 8:45:00 AM	0.022	0
6/26/2026, 8:46:00 AM	0.0224	0
6/26/2026, 8:47:00 AM	0.0227	0
6/26/2026, 8:48:00 AM	0.0231	0
6/26/2026, 8:49:00 AM	0.0233	0
6/26/2026, 8:50:00 AM	0.0251	0
6/26/2026, 8:51:00 AM	0.0256	0
6/26/2026, 8:52:00 AM	0.0257	0
6/26/2026, 8:53:00 AM	0.0259	0
6/26/2026, 8:54:00 AM	0.026	0
6/26/2026, 8:55:00 AM	0.0261	0
6/26/2026, 8:56:00 AM	0.0264	0
6/26/2026, 8:57:00 AM	0.0271	0
6/26/2026, 8:58:00 AM	0.0277	0
6/26/2026, 8:59:00 AM	0.0273	0
6/26/2026, 9:00:00 AM	0.0261	0
6/26/2026, 9:01:00 AM	0.0284	0
6/26/2026, 9:02:00 AM	0.0287	0
6/26/2026, 9:03:00 AM	0.0291	0

Downwind CAMP Data
260 West 126th Street - New York, NY
Remedial Investigation

Date / Time	Particulates - 15-min Average (mg/m^3)	VOCs - 15-min Average (ppm)
6/26/2026, 9:04:00 AM	0.0295	0
6/26/2026, 9:05:00 AM	0.0282	0
6/26/2026, 9:06:00 AM	0.0281	0
6/26/2026, 9:07:00 AM	0.0285	0
6/26/2026, 9:08:00 AM	0.0289	0
6/26/2026, 9:09:00 AM	0.0301	0
6/26/2026, 9:10:00 AM	0.0309	0
6/26/2026, 9:11:00 AM	0.0314	0
6/26/2026, 9:12:00 AM	0.0319	0
6/26/2026, 9:13:00 AM	0.0323	0
6/26/2026, 9:14:00 AM	0.0327	0
6/26/2026, 9:15:00 AM	0.0339	0
6/26/2026, 9:16:00 AM	0.0319	0
6/26/2026, 9:17:00 AM	0.032	0
6/26/2026, 9:18:00 AM	0.0317	0
6/26/2026, 9:19:00 AM	0.0316	0
6/26/2026, 9:20:00 AM	0.0315	0
6/26/2026, 9:21:00 AM	0.0315	0
6/26/2026, 9:22:00 AM	0.0314	0
6/26/2026, 9:23:00 AM	0.0313	0
6/26/2026, 9:24:00 AM	0.0305	0
6/26/2026, 9:25:00 AM	0.0299	0
6/26/2026, 9:26:00 AM	0.0295	0
6/26/2026, 9:27:00 AM	0.0287	0
6/26/2026, 9:28:00 AM	0.0277	0
6/26/2026, 9:29:00 AM	0.0273	0
6/26/2026, 9:30:00 AM	0.0261	0
6/26/2026, 9:31:00 AM	0.0255	0
6/26/2026, 9:32:00 AM	0.0249	0
6/26/2026, 9:33:00 AM	0.0245	0
6/26/2026, 9:34:00 AM	0.0242	0
6/26/2026, 9:35:00 AM	0.0239	0
6/26/2026, 9:36:00 AM	0.0235	0
6/26/2026, 9:37:00 AM	0.0233	0
6/26/2026, 9:38:00 AM	0.0229	0
6/26/2026, 9:39:00 AM	0.0227	0
6/26/2026, 9:40:00 AM	0.0224	0
6/26/2026, 9:41:00 AM	0.0223	0
6/26/2026, 9:42:00 AM	0.0223	0
6/26/2026, 9:43:00 AM	0.0222	0
6/26/2026, 9:44:00 AM	0.0221	0
6/26/2026, 9:45:00 AM	0.0222	0
6/26/2026, 9:46:00 AM	0.0222	0

Downwind CAMP Data
260 West 126th Street - New York, NY
Remedial Investigation

Date / Time	Particulates - 15-min Average (mg/m^3)	VOCs - 15-min Average (ppm)
6/26/2026, 9:47:00 AM	0.0224	0
6/26/2026, 9:48:00 AM	0.0227	0
6/26/2026, 9:49:00 AM	0.0231	0
6/26/2026, 9:50:00 AM	0.0235	0
6/26/2026, 9:51:00 AM	0.0239	0
6/26/2026, 9:52:00 AM	0.0242	0
6/26/2026, 9:53:00 AM	0.0247	0
6/26/2026, 9:54:00 AM	0.0251	0
6/26/2026, 9:55:00 AM	0.0255	0
6/26/2026, 9:56:00 AM	0.0257	0
6/26/2026, 9:57:00 AM	0.026	0
6/26/2026, 9:58:00 AM	0.0263	0
6/26/2026, 9:59:00 AM	0.0266	0
6/26/2026, 10:00:00 AM	0.0269	0
6/26/2026, 10:01:00 AM	0.0271	0
6/26/2026, 10:02:00 AM	0.0273	0
6/26/2026, 10:03:00 AM	0.0275	0
6/26/2026, 10:04:00 AM	0.0277	0
6/26/2026, 10:05:00 AM	0.0277	0
6/26/2026, 10:06:00 AM	0.0277	0
6/26/2026, 10:07:00 AM	0.0277	0
6/26/2026, 10:08:00 AM	0.0275	0
6/26/2026, 10:09:00 AM	0.0271	0
6/26/2026, 10:10:00 AM	0.0268	0
6/26/2026, 10:11:00 AM	0.0265	0
6/26/2026, 10:12:00 AM	0.0263	0
6/26/2026, 10:13:00 AM	0.0261	0
6/26/2026, 10:14:00 AM	0.0258	0
6/26/2026, 10:15:00 AM	0.0255	0
6/26/2026, 10:16:00 AM	0.0251	0
6/26/2026, 10:17:00 AM	0.0249	0
6/26/2026, 10:18:00 AM	0.0247	0
6/26/2026, 10:19:00 AM	0.0244	0
6/26/2026, 10:20:00 AM	0.0241	0
6/26/2026, 10:21:00 AM	0.0239	0
6/26/2026, 10:22:00 AM	0.0238	0
6/26/2026, 10:23:00 AM	0.0239	0
6/26/2026, 10:24:00 AM	0.0242	0
6/26/2026, 10:25:00 AM	0.0243	0
6/26/2026, 10:26:00 AM	0.0245	0
6/26/2026, 10:27:00 AM	0.0246	0
6/26/2026, 10:28:00 AM	0.0247	0
6/26/2026, 10:29:00 AM	0.0247	0

Downwind CAMP Data
260 West 126th Street - New York, NY
Remedial Investigation

Date / Time	Particulates - 15-min Average (mg/m^3)	VOCs - 15-min Average (ppm)
6/26/2026, 10:30:00 AM	0.0248	0
6/26/2026, 10:31:00 AM	0.0249	0
6/26/2026, 10:32:00 AM	0.025	0
6/26/2026, 10:33:00 AM	0.0249	0
6/26/2026, 10:34:00 AM	0.0249	0
6/26/2026, 10:35:00 AM	0.0249	0
6/26/2026, 10:36:00 AM	0.025	0
6/26/2026, 10:37:00 AM	0.0251	0
6/26/2026, 10:38:00 AM	0.0251	0
6/26/2026, 10:39:00 AM	0.0251	0
6/26/2026, 10:40:00 AM	0.0252	0
6/26/2026, 10:41:00 AM	0.0252	0
6/26/2026, 10:42:00 AM	0.0254	0
6/26/2026, 10:43:00 AM	0.0256	0
6/26/2026, 10:44:00 AM	0.0259	0
6/26/2026, 10:45:00 AM	0.0266	0
6/26/2026, 10:46:00 AM	0.0272	0
6/26/2026, 10:47:00 AM	0.0275	0
6/26/2026, 10:48:00 AM	0.0278	0
6/26/2026, 10:49:00 AM	0.0279	0
6/26/2026, 10:50:00 AM	0.0281	0
6/26/2026, 10:51:00 AM	0.0283	0
6/26/2026, 10:52:00 AM	0.0283	0
6/26/2026, 10:53:00 AM	0.0284	0
6/26/2026, 10:54:00 AM	0.0285	0
6/26/2026, 10:55:00 AM	0.0286	0
6/26/2026, 10:56:00 AM	0.0288	0
6/26/2026, 10:57:00 AM	0.0289	0
6/26/2026, 10:58:00 AM	0.0289	0
6/26/2026, 10:59:00 AM	0.0289	0
6/26/2026, 11:00:00 AM	0.0284	0
6/26/2026, 11:01:00 AM	0.0279	0
6/26/2026, 11:02:00 AM	0.0279	0
6/26/2026, 11:03:00 AM	0.028	0
6/26/2026, 11:04:00 AM	0.0282	0
6/26/2026, 11:05:00 AM	0.0283	0
6/26/2026, 11:06:00 AM	0.0284	0
6/26/2026, 11:07:00 AM	0.0286	0
6/26/2026, 11:08:00 AM	0.0287	0
6/26/2026, 11:09:00 AM	0.0289	0
6/26/2026, 11:10:00 AM	0.0289	0.001
6/26/2026, 11:11:00 AM	0.029	0.001
6/26/2026, 11:12:00 AM	0.0293	0.001

Downwind CAMP Data
260 West 126th Street - New York, NY
Remedial Investigation

Date / Time	Particulates - 15-min Average (mg/m^3)	VOCs - 15-min Average (ppm)
6/26/2026, 11:13:00 AM	0.0295	0.002
6/26/2026, 11:14:00 AM	0.0299	0.002
6/26/2026, 11:15:00 AM	0.0303	0.002
6/26/2026, 11:16:00 AM	0.0307	0.003
6/26/2026, 11:17:00 AM	0.0307	0.003
6/26/2026, 11:18:00 AM	0.0308	0.004
6/26/2026, 11:19:00 AM	0.0309	0.005
6/26/2026, 11:20:00 AM	0.0311	0.006
6/26/2026, 11:21:00 AM	0.0313	0.007
6/26/2026, 11:22:00 AM	0.0314	0.007
6/26/2026, 11:23:00 AM	0.0315	0.008
6/26/2026, 11:24:00 AM	0.0317	0.008
6/26/2026, 11:25:00 AM	0.0319	0.009
6/26/2026, 11:26:00 AM	0.0323	0.01
6/26/2026, 11:27:00 AM	0.0325	0.011
6/26/2026, 11:28:00 AM	0.0328	0.012
6/26/2026, 11:29:00 AM	0.0327	0.013
6/26/2026, 11:30:00 AM	0.0327	0.015
6/26/2026, 11:31:00 AM	0.0328	0.016
6/26/2026, 11:32:00 AM	0.033	0.017
6/26/2026, 11:33:00 AM	0.0333	0.018
6/26/2026, 11:34:00 AM	0.0336	0.02
6/26/2026, 11:35:00 AM	0.0339	0.021
6/26/2026, 11:36:00 AM	0.0341	0.022
6/26/2026, 11:37:00 AM	0.0342	0.024
6/26/2026, 11:38:00 AM	0.0344	0.026
6/26/2026, 11:39:00 AM	0.0346	0.027
6/26/2026, 11:40:00 AM	0.0348	0.029
6/26/2026, 11:41:00 AM	0.0349	0.03
6/26/2026, 11:42:00 AM	0.035	0.031
6/26/2026, 11:43:00 AM	0.035	0.032
6/26/2026, 11:44:00 AM	0.0351	0.034
6/26/2026, 11:45:00 AM	0.0354	0.035
6/26/2026, 11:46:00 AM	0.0356	0.036
6/26/2026, 11:47:00 AM	0.0359	0.037
6/26/2026, 11:48:00 AM	0.0361	0.038
6/26/2026, 11:49:00 AM	0.0362	0.039
6/26/2026, 11:50:00 AM	0.0365	0.04
6/26/2026, 11:51:00 AM	0.0366	0.041
6/26/2026, 11:52:00 AM	0.0368	0.042
6/26/2026, 11:53:00 AM	0.0369	0.043
6/26/2026, 11:54:00 AM	0.0371	0.045
6/26/2026, 11:55:00 AM	0.0373	0.046

Downwind CAMP Data
260 West 126th Street - New York, NY
Remedial Investigation

Date / Time	Particulates - 15-min Average (mg/m^3)	VOCs - 15-min Average (ppm)
6/26/2026, 11:56:00 AM	0.0378	0.047
6/26/2026, 11:57:00 AM	0.0381	0.049
6/26/2026, 11:58:00 AM	0.0383	0.051
6/26/2026, 11:59:00 AM	0.0385	0.052
6/26/2026, 12:00:00 PM	0.0384	0.054
6/26/2026, 12:01:00 PM	0.0383	0.056
6/26/2026, 12:02:00 PM	0.0382	0.058
6/26/2026, 12:03:00 PM	0.0383	0.059
6/26/2026, 12:04:00 PM	0.0383	0.061
6/26/2026, 12:05:00 PM	0.0385	0.063
6/26/2026, 12:06:00 PM	0.0387	0.064
6/26/2026, 12:07:00 PM	0.0389	0.066
6/26/2026, 12:08:00 PM	0.0392	0.067
6/26/2026, 12:09:00 PM	0.0394	0.068
6/26/2026, 12:10:00 PM	0.0396	0.069
6/26/2026, 12:11:00 PM	0.0393	0.07
6/26/2026, 12:12:00 PM	0.0391	0.071
6/26/2026, 12:13:00 PM	0.0389	0.071
6/26/2026, 12:14:00 PM	0.0389	0.072
6/26/2026, 12:15:00 PM	0.0391	0.072
6/26/2026, 12:16:00 PM	0.0393	0.073
6/26/2026, 12:17:00 PM	0.0393	0.073
6/26/2026, 12:18:00 PM	0.0393	0.074
6/26/2026, 12:19:00 PM	0.0393	0.075
6/26/2026, 12:20:00 PM	0.0391	0.075
6/26/2026, 12:21:00 PM	0.039	0.075
6/26/2026, 12:22:00 PM	0.0388	0.076
6/26/2026, 12:23:00 PM	0.0387	0.076
6/26/2026, 12:24:00 PM	0.0385	0.077
6/26/2026, 12:25:00 PM	0.0382	0.077
6/26/2026, 12:26:00 PM	0.0381	0.077
6/26/2026, 12:27:00 PM	0.0381	0.077
6/26/2026, 12:28:00 PM	0.0382	0.078
6/26/2026, 12:29:00 PM	0.0382	0.079
6/26/2026, 12:30:00 PM	0.0381	0.079
6/26/2026, 12:31:00 PM	0.0381	0.079
6/26/2026, 12:32:00 PM	0.0381	0.08
6/26/2026, 12:33:00 PM	0.0382	0.08
6/26/2026, 12:34:00 PM	0.0383	0.08
6/26/2026, 12:35:00 PM	0.0386	0.08
6/26/2026, 12:36:00 PM	0.0388	0.079
6/26/2026, 12:37:00 PM	0.0391	0.079
6/26/2026, 12:38:00 PM	0.0393	0.08

Downwind CAMP Data
260 West 126th Street - New York, NY
Remedial Investigation

Date / Time	Particulates - 15-min Average (mg/m^3)	VOCs - 15-min Average (ppm)
6/26/2026, 12:39:00 PM	0.0396	0.08
6/26/2026, 12:40:00 PM	0.0401	0.08
6/26/2026, 12:41:00 PM	0.0401	0.08
6/26/2026, 12:42:00 PM	0.0402	0.081
6/26/2026, 12:43:00 PM	0.0403	0.082
6/26/2026, 12:44:00 PM	0.0404	0.083
6/26/2026, 12:45:00 PM	0.0405	0.083
6/26/2026, 12:46:00 PM	0.0405	0.083
6/26/2026, 12:47:00 PM	0.0406	0.083
6/26/2026, 12:48:00 PM	0.0407	0.084
6/26/2026, 12:49:00 PM	0.0407	0.084
6/26/2026, 12:50:00 PM	0.0406	0.085
6/26/2026, 12:51:00 PM	0.0407	0.086
6/26/2026, 12:52:00 PM	0.0405	0.086
6/26/2026, 12:53:00 PM	0.0404	0.087
6/26/2026, 12:54:00 PM	0.0405	0.088
6/26/2026, 12:55:00 PM	0.0403	0.088
6/26/2026, 12:56:00 PM	0.0405	0.088
6/26/2026, 12:57:00 PM	0.0407	0.088
6/26/2026, 12:58:00 PM	0.0409	0.089
6/26/2026, 12:59:00 PM	0.041	0.089
6/26/2026, 1:00:00 PM	0.0411	0.089
6/26/2026, 1:01:00 PM	0.0412	0.09
6/26/2026, 1:02:00 PM	0.0413	0.09
6/26/2026, 1:03:00 PM	0.0415	0.09
6/26/2026, 1:04:00 PM	0.0415	0.091
6/26/2026, 1:05:00 PM	0.0416	0.091
6/26/2026, 1:06:00 PM	0.0415	0.091
6/26/2026, 1:07:00 PM	0.0415	0.091
6/26/2026, 1:08:00 PM	0.0415	0.092
6/26/2026, 1:09:00 PM	0.0415	0.091
6/26/2026, 1:10:00 PM	0.0414	0.091
6/26/2026, 1:11:00 PM	0.0413	0.091
6/26/2026, 1:12:00 PM	0.0412	0.091
6/26/2026, 1:13:00 PM	0.0412	0.091
6/26/2026, 1:14:00 PM	0.0413	0.091
6/26/2026, 1:15:00 PM	0.0415	0.091
6/26/2026, 1:16:00 PM	0.0414	0.091
6/26/2026, 1:17:00 PM	0.0414	0.091
6/26/2026, 1:18:00 PM	0.0415	0.091
6/26/2026, 1:19:00 PM	0.0415	0.091
6/26/2026, 1:20:00 PM	0.0414	0.091
6/26/2026, 1:21:00 PM	0.0414	0.091

Downwind CAMP Data
260 West 126th Street - New York, NY
Remedial Investigation

Date / Time	Particulates - 15-min Average (mg/m^3)	VOCs - 15-min Average (ppm)
6/26/2026, 1:22:00 PM	0.0414	0.091
6/26/2026, 1:23:00 PM	0.0412	0.091
6/26/2026, 1:24:00 PM	0.0408	0.091
6/26/2026, 1:25:00 PM	0.0405	0.091
6/26/2026, 1:26:00 PM	0.0402	0.091
6/26/2026, 1:27:00 PM	0.0399	0.091
6/26/2026, 1:28:00 PM	0.0395	0.091
6/26/2026, 1:29:00 PM	0.0392	0.091
6/26/2026, 1:30:00 PM	0.0389	0.091
6/26/2026, 1:31:00 PM	0.0387	0.091
6/26/2026, 1:32:00 PM	0.0384	0.091
6/26/2026, 1:33:00 PM	0.038	0.09
6/26/2026, 1:34:00 PM	0.0377	0.09
6/26/2026, 1:35:00 PM	0.0374	0.091
6/26/2026, 1:36:00 PM	0.0372	0.091
6/26/2026, 1:37:00 PM	0.0371	0.091
6/26/2026, 1:38:00 PM	0.0369	0.091
6/26/2026, 1:39:00 PM	0.0372	0.091
6/26/2026, 1:40:00 PM	0.0372	0.091
6/26/2026, 1:41:00 PM	0.0371	0.091
6/26/2026, 1:42:00 PM	0.0371	0.091
6/26/2026, 1:43:00 PM	0.0375	0.091
6/26/2026, 1:44:00 PM	0.0377	0.091
6/26/2026, 1:45:00 PM	0.0378	0.091
6/26/2026, 1:46:00 PM	0.0379	0.09
6/26/2026, 1:47:00 PM	0.038	0.09
6/26/2026, 1:48:00 PM	0.0381	0.09
6/26/2026, 1:49:00 PM	0.0382	0.089
6/26/2026, 1:50:00 PM	0.0383	0.089
6/26/2026, 1:51:00 PM	0.0385	0.089
6/26/2026, 1:52:00 PM	0.0385	0.088
6/26/2026, 1:53:00 PM	0.0386	0.088
6/26/2026, 1:54:00 PM	0.0385	0.087
6/26/2026, 1:55:00 PM	0.0385	0.086
6/26/2026, 1:56:00 PM	0.0387	0.086
6/26/2026, 1:57:00 PM	0.0387	0.086
6/26/2026, 1:58:00 PM	0.0382	0.085
6/26/2026, 1:59:00 PM	0.0379	0.085
6/26/2026, 2:00:00 PM	0.0379	0.085
6/26/2026, 2:01:00 PM	0.0378	0.086
6/26/2026, 2:02:00 PM	0.0377	0.086
6/26/2026, 2:03:00 PM	0.0381	0.086
6/26/2026, 2:04:00 PM	0.0379	0.086

Downwind CAMP Data
260 West 126th Street - New York, NY
Remedial Investigation

Date / Time	Particulates - 15-min Average (mg/m^3)	VOCs - 15-min Average (ppm)
6/26/2026, 2:05:00 PM	0.0379	0.086
6/26/2026, 2:06:00 PM	0.0377	0.086
6/26/2026, 2:07:00 PM	0.0376	0.087
6/26/2026, 2:08:00 PM	0.0375	0.087
6/26/2026, 2:09:00 PM	0.0375	0.088
6/26/2026, 2:10:00 PM	0.0373	0.089
6/26/2026, 2:11:00 PM	0.0371	0.09
6/26/2026, 2:12:00 PM	0.0369	0.091
6/26/2026, 2:13:00 PM	0.0367	0.093
6/26/2026, 2:14:00 PM	0.0371	0.094
6/26/2026, 2:15:00 PM	0.0369	0.095
6/26/2026, 2:16:00 PM	0.0367	0.096
6/26/2026, 2:17:00 PM	0.0363	0.097
6/26/2026, 2:18:00 PM	0.0357	0.097
6/26/2026, 2:19:00 PM	0.0355	0.098
6/26/2026, 2:20:00 PM	0.0352	0.099
6/26/2026, 2:21:00 PM	0.0351	0.1
6/26/2026, 2:22:00 PM	0.0349	0.101
6/26/2026, 2:23:00 PM	0.0346	0.102
6/26/2026, 2:24:00 PM	0.0343	0.102
6/26/2026, 2:25:00 PM	0.0343	0.103
6/26/2026, 2:26:00 PM	0.0342	0.103
6/26/2026, 2:27:00 PM	0.0341	0.103
6/26/2026, 2:28:00 PM	0.0339	0.103
6/26/2026, 2:29:00 PM	0.0332	0.103
6/26/2026, 2:30:00 PM	0.0329	0.104
6/26/2026, 2:31:00 PM	0.0328	0.105
6/26/2026, 2:32:00 PM	0.0327	0.106
6/26/2026, 2:33:00 PM	0.0325	0.107
6/26/2026, 2:34:00 PM	0.0325	0.108
6/26/2026, 2:35:00 PM	0.0324	0.109
6/26/2026, 2:36:00 PM	0.0322	0.111
6/26/2026, 2:37:00 PM	0.032	0.113

Upwind CAMP Data
260 West 126th Street - New York, NY
Remedial Investigation

Date / Time	Particulates - 15-min Average (mg/m^3)	VOCs - 15-min Average (ppm)
1/5/2026, 9:00:00 AM	0.027	0
1/5/2026, 9:15:00 AM	0.021	0
1/5/2026, 9:30:00 AM	0.019	0
1/5/2026, 9:45:00 AM	0.021	0
1/5/2026, 10:00:00 AM	0.027	0
1/5/2026, 10:15:00 AM	0.029	0
1/5/2026, 10:30:00 AM	0.034	0
1/5/2026, 10:45:00 AM	0.022	0
1/5/2026, 11:00:00 AM	0.021	0
1/5/2026, 11:15:00 AM	0.021	0
1/5/2026, 11:30:00 AM	0.029	0
1/5/2026, 11:45:00 AM	0.03	0
1/5/2026, 12:00:00 PM	0.024	0
1/5/2026, 12:15:00 PM	0.041	0
1/5/2026, 12:30:00 PM	0.024	0
1/5/2026, 12:45:00 PM	0.02	0
1/5/2026, 13:00:00 PM	0.017	0
1/5/2026, 13:15:00 PM	0.029	0
1/5/2026, 13:30:00 PM	0.034	0
1/5/2026, 13:45:00 PM	0.025	0
1/5/2026, 14:00:00 PM	0.028	0
1/5/2026, 14:15:00 PM	0.027	0
1/5/2026, 14:30:00 PM	0.024	0
1/5/2026, 14:45:00 PM	0.029	0
1/5/2026, 15:00:00 PM	0.034	0
1/5/2026, 15:15:00 PM	0.037	0
1/5/2026, 15:30:00 PM	0.028	0
1/5/2026, 15:45:00 PM	0.024	0
1/6/2026, 7:30:00 AM	0.029	0
1/6/2026, 7:45:00 AM	0.034	0
1/6/2026, 8:00:00 AM	0.031	0
1/6/2026, 8:15:00 AM	0.035	0
1/6/2026, 8:30:00 AM	0.029	0
1/6/2026, 8:45:00 AM	0.034	0
1/6/2026, 9:00:00 AM	0.031	0
1/6/2026, 9:15:00 AM	0.037	0
1/6/2026, 9:30:00 AM	0.034	0
1/6/2026, 9:45:00 AM	0.032	0
1/6/2026, 10:00:00 AM	0.032	0
1/6/2026, 10:15:00 AM	0.030	0
1/6/2026, 10:30:00 AM	0.054	0
1/6/2026, 10:45:00 AM	0.035	0
1/6/2026, 11:00:00 AM	0.037	0

Upwind CAMP Data
260 West 126th Street - New York, NY
Remedial Investigation

Date / Time	Particulates - 15-min Average (mg/m^3)	VOCs - 15-min Average (ppm)
1/6/2026, 11:15:00 AM	0.029	0
1/6/2026, 11:30:00 AM	0.034	0
1/6/2026, 11:45:00 AM	0.037	0
1/6/2026, 12:00:00 PM	0.034	0
1/6/2026, 12:15:00 PM	0.035	0
1/6/2026, 12:30:00 PM	0.029	0
1/6/2026, 12:45:00 PM	0.037	0
1/6/2026, 13:00:00 PM	0.032	0
1/6/2026, 13:15:00 PM	0.031	0
1/6/2026, 13:30:00 PM	0.031	0
1/6/2026, 13:45:00 PM	0.039	0
1/6/2026, 14:00:00 PM	0.034	0
1/6/2026, 14:15:00 PM	0.038	0
1/6/2026, 14:30:00 PM	0.042	0
1/6/2026, 14:45:00 PM	0.047	0
1/6/2026, 15:00:00 PM	0.034	0
1/6/2026, 15:15:00 PM	0.031	0
1/6/2026, 15:30:00 PM	0.029	0
1/6/2026, 15:45:00 PM	0.035	0
1/7/2026, 8:00:00 AM	0.064	0
1/7/2026, 8:15:00 AM	0.076	0
1/7/2026, 8:30:00 AM	0.088	0
1/7/2026, 8:45:00 AM	0.072	0
1/7/2026, 9:00:00 AM	0.077	0
1/7/2026, 9:15:00 AM	0.062	0
1/7/2026, 9:30:00 AM	0.051	0
1/7/2026, 9:45:00 AM	0.071	0
1/7/2026, 10:00:00 AM	0.079	0
1/7/2026, 10:15:00 AM	0.090	0
1/7/2026, 10:30:00 AM	0.082	0
1/6/2026, 7:30:00 AM	0.023	0
1/9/2026, 7:45:00 AM	0.032	0
1/9/2026, 8:00:00 AM	0.035	0
1/9/2026, 8:15:00 AM	0.031	0
1/9/2026, 8:30:00 AM	0.032	0
1/9/2026, 8:45:00 AM	0.030	0
1/9/2026, 9:00:00 AM	0.022	0
1/9/2026, 9:15:00 AM	0.024	0
1/9/2026, 9:30:00 AM	0.021	0
1/9/2026, 9:45:00 AM	0.019	0
1/9/2026, 10:00:00 AM	0.026	0
6/26/2026, 6:41:00 AM		0
6/26/2026, 6:42:00 AM	0.02	0

Upwind CAMP Data
260 West 126th Street - New York, NY
Remedial Investigation

Date / Time	Particulates - 15-min Average (mg/m^3)	VOCs - 15-min Average (ppm)
6/26/2026, 6:43:00 AM	0.0195	0
6/26/2026, 6:44:00 AM	0.019	0
6/26/2026, 6:45:00 AM	0.0188	0
6/26/2026, 6:46:00 AM	0.0184	0
6/26/2026, 6:47:00 AM	0.018	0
6/26/2026, 6:48:00 AM	0.0177	0
6/26/2026, 6:49:00 AM	0.0175	0
6/26/2026, 6:50:00 AM	0.0173	0
6/26/2026, 6:51:00 AM	0.0171	0
6/26/2026, 6:52:00 AM	0.0169	0
6/26/2026, 6:53:00 AM	0.0168	0
6/26/2026, 6:54:00 AM	0.0166	0
6/26/2026, 6:55:00 AM	0.0165	0
6/26/2026, 6:56:00 AM	0.0164	0
6/26/2026, 6:57:00 AM	0.016	0
6/26/2026, 6:58:00 AM	0.0157	0
6/26/2026, 6:59:00 AM	0.0155	0
6/26/2026, 7:00:00 AM	0.0152	0
6/26/2026, 7:01:00 AM	0.0151	0
6/26/2026, 7:02:00 AM	0.0149	0
6/26/2026, 7:03:00 AM	0.0149	0
6/26/2026, 7:04:00 AM	0.0147	0
6/26/2026, 7:05:00 AM	0.0146	0
6/26/2026, 7:06:00 AM	0.0146	0
6/26/2026, 7:07:00 AM	0.0147	0
6/26/2026, 7:08:00 AM	0.0147	0
6/26/2026, 7:09:00 AM	0.0147	0
6/26/2026, 7:10:00 AM	0.0147	0
6/26/2026, 7:11:00 AM	0.0147	0
6/26/2026, 7:12:00 AM	0.0147	0
6/26/2026, 7:13:00 AM	0.0149	0
6/26/2026, 7:14:00 AM	0.0149	0
6/26/2026, 7:15:00 AM	0.015	0
6/26/2026, 7:16:00 AM	0.015	0
6/26/2026, 7:17:00 AM	0.0151	0
6/26/2026, 7:18:00 AM	0.0151	0
6/26/2026, 7:19:00 AM	0.0151	0
6/26/2026, 7:20:00 AM	0.0152	0
6/26/2026, 7:21:00 AM	0.0152	0
6/26/2026, 7:22:00 AM	0.0151	0
6/26/2026, 7:23:00 AM	0.0151	0
6/26/2026, 7:24:00 AM	0.0151	0
6/26/2026, 7:25:00 AM	0.0151	0

Upwind CAMP Data
260 West 126th Street - New York, NY
Remedial Investigation

Date / Time	Particulates - 15-min Average (mg/m^3)	VOCs - 15-min Average (ppm)
6/26/2026, 7:26:00 AM	0.0151	0
6/26/2026, 7:27:00 AM	0.0151	0
6/26/2026, 7:28:00 AM	0.0149	0
6/26/2026, 7:29:00 AM	0.0149	0
6/26/2026, 7:30:00 AM	0.0149	0
6/26/2026, 7:31:00 AM	0.0148	0
6/26/2026, 7:32:00 AM	0.0148	0
6/26/2026, 7:33:00 AM	0.0148	0
6/26/2026, 7:34:00 AM	0.0147	0
6/26/2026, 7:35:00 AM	0.0147	0
6/26/2026, 7:36:00 AM	0.0153	0
6/26/2026, 7:37:00 AM	0.0153	0
6/26/2026, 7:38:00 AM	0.0153	0
6/26/2026, 7:39:00 AM	0.0153	0
6/26/2026, 7:40:00 AM	0.0154	0
6/26/2026, 7:41:00 AM	0.0159	0
6/26/2026, 7:42:00 AM	0.0162	0
6/26/2026, 7:43:00 AM	0.022	0
6/26/2026, 7:44:00 AM	0.0225	0
6/26/2026, 7:45:00 AM	0.0227	0
6/26/2026, 7:46:00 AM	0.0235	0
6/26/2026, 7:47:00 AM	0.0256	0
6/26/2026, 7:48:00 AM	0.0273	0
6/26/2026, 7:49:00 AM	0.0283	0
6/26/2026, 7:50:00 AM	0.0289	0
6/26/2026, 7:51:00 AM	0.0287	0
6/26/2026, 7:52:00 AM	0.0293	0
6/26/2026, 7:53:00 AM	0.0297	0
6/26/2026, 7:54:00 AM	0.0301	0
6/26/2026, 7:55:00 AM	0.0301	0
6/26/2026, 7:56:00 AM	0.0295	0
6/26/2026, 7:57:00 AM	0.0294	0
6/26/2026, 7:58:00 AM	0.0237	0
6/26/2026, 7:59:00 AM	0.0233	0
6/26/2026, 8:00:00 AM	0.024	0
6/26/2026, 8:01:00 AM	0.0237	0
6/26/2026, 8:02:00 AM	0.0223	0
6/26/2026, 8:03:00 AM	0.0208	0
6/26/2026, 8:04:00 AM	0.0201	0
6/26/2026, 8:05:00 AM	0.0198	0
6/26/2026, 8:06:00 AM	0.0195	0
6/26/2026, 8:07:00 AM	0.0189	0
6/26/2026, 8:08:00 AM	0.0185	0

Upwind CAMP Data
260 West 126th Street - New York, NY
Remedial Investigation

Date / Time	Particulates - 15-min Average (mg/m^3)	VOCs - 15-min Average (ppm)
6/26/2026, 8:09:00 AM	0.0181	0
6/26/2026, 8:10:00 AM	0.0181	0
6/26/2026, 8:11:00 AM	0.0181	0
6/26/2026, 8:12:00 AM	0.0185	0
6/26/2026, 8:13:00 AM	0.0189	0
6/26/2026, 8:14:00 AM	0.0191	0
6/26/2026, 8:15:00 AM	0.0196	0
6/26/2026, 8:16:00 AM	0.0197	0
6/26/2026, 8:17:00 AM	0.0198	0
6/26/2026, 8:18:00 AM	0.0199	0
6/26/2026, 8:19:00 AM	0.0199	0
6/26/2026, 8:20:00 AM	0.0205	0
6/26/2026, 8:21:00 AM	0.0235	0
6/26/2026, 8:22:00 AM	0.0245	0
6/26/2026, 8:23:00 AM	0.0248	0
6/26/2026, 8:24:00 AM	0.0253	0
6/26/2026, 8:25:00 AM	0.0257	0
6/26/2026, 8:26:00 AM	0.026	0
6/26/2026, 8:27:00 AM	0.0259	0
6/26/2026, 8:28:00 AM	0.0257	0
6/26/2026, 8:29:00 AM	0.0257	0
6/26/2026, 8:30:00 AM	0.0244	0
6/26/2026, 8:31:00 AM	0.0237	0
6/26/2026, 8:32:00 AM	0.0226	0
6/26/2026, 8:33:00 AM	0.022	0
6/26/2026, 8:34:00 AM	0.0215	0
6/26/2026, 8:35:00 AM	0.0204	0
6/26/2026, 8:36:00 AM	0.0169	0
6/26/2026, 8:37:00 AM	0.0156	0
6/26/2026, 8:38:00 AM	0.015	0
6/26/2026, 8:39:00 AM	0.0141	0
6/26/2026, 8:40:00 AM	0.0134	0
6/26/2026, 8:41:00 AM	0.0133	0
6/26/2026, 8:42:00 AM	0.013	0
6/26/2026, 8:43:00 AM	0.0126	0
6/26/2026, 8:44:00 AM	0.0131	0
6/26/2026, 8:45:00 AM	0.0149	0
6/26/2026, 8:46:00 AM	0.0153	0
6/26/2026, 8:47:00 AM	0.0157	0
6/26/2026, 8:48:00 AM	0.0188	0
6/26/2026, 8:49:00 AM	0.0225	0
6/26/2026, 8:50:00 AM	0.023	0
6/26/2026, 8:51:00 AM	0.0232	0

Upwind CAMP Data
260 West 126th Street - New York, NY
Remedial Investigation

Date / Time	Particulates - 15-min Average (mg/m^3)	VOCs - 15-min Average (ppm)
6/26/2026, 8:52:00 AM	0.0233	0
6/26/2026, 8:53:00 AM	0.0236	0
6/26/2026, 8:54:00 AM	0.0239	0
6/26/2026, 8:55:00 AM	0.0244	0
6/26/2026, 8:56:00 AM	0.0241	0
6/26/2026, 8:57:00 AM	0.024	0
6/26/2026, 8:58:00 AM	0.0241	0
6/26/2026, 8:59:00 AM	0.0232	0
6/26/2026, 9:00:00 AM	0.0213	0
6/26/2026, 9:01:00 AM	0.0209	0
6/26/2026, 9:02:00 AM	0.0209	0
6/26/2026, 9:03:00 AM	0.0181	0
6/26/2026, 9:04:00 AM	0.0148	0
6/26/2026, 9:05:00 AM	0.0146	0
6/26/2026, 9:06:00 AM	0.0148	0
6/26/2026, 9:07:00 AM	0.0151	0
6/26/2026, 9:08:00 AM	0.0153	0
6/26/2026, 9:09:00 AM	0.0157	0
6/26/2026, 9:10:00 AM	0.0155	0
6/26/2026, 9:11:00 AM	0.0157	0
6/26/2026, 9:12:00 AM	0.016	0
6/26/2026, 9:13:00 AM	0.0162	0
6/26/2026, 9:14:00 AM	0.0163	0
6/26/2026, 9:15:00 AM	0.0165	0
6/26/2026, 9:16:00 AM	0.0166	0
6/26/2026, 9:17:00 AM	0.0167	0
6/26/2026, 9:18:00 AM	0.0166	0
6/26/2026, 9:19:00 AM	0.0165	0
6/26/2026, 9:20:00 AM	0.0165	0
6/26/2026, 9:21:00 AM	0.0164	0
6/26/2026, 9:22:00 AM	0.0164	0
6/26/2026, 9:23:00 AM	0.0163	0
6/26/2026, 9:24:00 AM	0.0161	0
6/26/2026, 9:25:00 AM	0.0159	0
6/26/2026, 9:26:00 AM	0.0157	0
6/26/2026, 9:27:00 AM	0.0155	0
6/26/2026, 9:28:00 AM	0.0153	0
6/26/2026, 9:29:00 AM	0.0152	0
6/26/2026, 9:30:00 AM	0.0151	0
6/26/2026, 9:31:00 AM	0.0149	0
6/26/2026, 9:32:00 AM	0.0147	0
6/26/2026, 9:33:00 AM	0.0144	0
6/26/2026, 9:34:00 AM	0.0142	0

Upwind CAMP Data
260 West 126th Street - New York, NY
Remedial Investigation

Date / Time	Particulates - 15-min Average (mg/m^3)	VOCs - 15-min Average (ppm)
6/26/2026, 9:35:00 AM	0.014	0
6/26/2026, 9:36:00 AM	0.0138	0
6/26/2026, 9:37:00 AM	0.0135	0
6/26/2026, 9:38:00 AM	0.0133	0
6/26/2026, 9:39:00 AM	0.0131	0
6/26/2026, 9:40:00 AM	0.0129	0
6/26/2026, 9:41:00 AM	0.0129	0
6/26/2026, 9:42:00 AM	0.0128	0
6/26/2026, 9:43:00 AM	0.0128	0
6/26/2026, 9:44:00 AM	0.0128	0
6/26/2026, 9:45:00 AM	0.0129	0
6/26/2026, 9:46:00 AM	0.013	0
6/26/2026, 9:47:00 AM	0.0131	0
6/26/2026, 9:48:00 AM	0.0133	0
6/26/2026, 9:49:00 AM	0.0136	0
6/26/2026, 9:50:00 AM	0.0139	0
6/26/2026, 9:51:00 AM	0.0142	0
6/26/2026, 9:52:00 AM	0.0145	0
6/26/2026, 9:53:00 AM	0.0147	0
6/26/2026, 9:54:00 AM	0.0151	0
6/26/2026, 9:55:00 AM	0.0153	0
6/26/2026, 9:56:00 AM	0.0155	0
6/26/2026, 9:57:00 AM	0.0157	0
6/26/2026, 9:58:00 AM	0.0158	0
6/26/2026, 9:59:00 AM	0.016	0
6/26/2026, 10:00:00 AM	0.0161	0
6/26/2026, 10:01:00 AM	0.0163	0
6/26/2026, 10:02:00 AM	0.0164	0
6/26/2026, 10:03:00 AM	0.0165	0
6/26/2026, 10:04:00 AM	0.0166	0
6/26/2026, 10:05:00 AM	0.0166	0
6/26/2026, 10:06:00 AM	0.0167	0
6/26/2026, 10:07:00 AM	0.0167	0
6/26/2026, 10:08:00 AM	0.0165	0
6/26/2026, 10:09:00 AM	0.0163	0
6/26/2026, 10:10:00 AM	0.0161	0
6/26/2026, 10:11:00 AM	0.0159	0
6/26/2026, 10:12:00 AM	0.0157	0
6/26/2026, 10:13:00 AM	0.0155	0
6/26/2026, 10:14:00 AM	0.0153	0
6/26/2026, 10:15:00 AM	0.0151	0
6/26/2026, 10:16:00 AM	0.0149	0
6/26/2026, 10:17:00 AM	0.0147	0

Upwind CAMP Data
260 West 126th Street - New York, NY
Remedial Investigation

Date / Time	Particulates - 15-min Average (mg/m^3)	VOCs - 15-min Average (ppm)
6/26/2026, 10:18:00 AM	0.0145	0
6/26/2026, 10:19:00 AM	0.0144	0
6/26/2026, 10:20:00 AM	0.0143	0
6/26/2026, 10:21:00 AM	0.0142	0
6/26/2026, 10:22:00 AM	0.0141	0
6/26/2026, 10:23:00 AM	0.0141	0
6/26/2026, 10:24:00 AM	0.0142	0
6/26/2026, 10:25:00 AM	0.0143	0
6/26/2026, 10:26:00 AM	0.0144	0
6/26/2026, 10:27:00 AM	0.0145	0
6/26/2026, 10:28:00 AM	0.0145	0
6/26/2026, 10:29:00 AM	0.0145	0
6/26/2026, 10:30:00 AM	0.016	0
6/26/2026, 10:31:00 AM	0.0236	0
6/26/2026, 10:32:00 AM	0.0318	0
6/26/2026, 10:33:00 AM	0.0352	0
6/26/2026, 10:34:00 AM	0.0388	0
6/26/2026, 10:35:00 AM	0.0391	0
6/26/2026, 10:36:00 AM	0.0404	0
6/26/2026, 10:37:00 AM	0.0457	0
6/26/2026, 10:38:00 AM	0.046	0
6/26/2026, 10:39:00 AM	0.0521	0
6/26/2026, 10:40:00 AM	0.0523	0
6/26/2026, 10:41:00 AM	0.0579	0
6/26/2026, 10:42:00 AM	0.0593	0
6/26/2026, 10:43:00 AM	0.0619	0
6/26/2026, 10:44:00 AM	0.0629	0.001
6/26/2026, 10:45:00 AM	0.0625	0.002
6/26/2026, 10:46:00 AM	0.0553	0.003
6/26/2026, 10:47:00 AM	0.0527	0.004
6/26/2026, 10:48:00 AM	0.0494	0.004
6/26/2026, 10:49:00 AM	0.0461	0.006
6/26/2026, 10:50:00 AM	0.0459	0.007
6/26/2026, 10:51:00 AM	0.0452	0.009
6/26/2026, 10:52:00 AM	0.0401	0.011
6/26/2026, 10:53:00 AM	0.0403	0.013
6/26/2026, 10:54:00 AM	0.0345	0.014
6/26/2026, 10:55:00 AM	0.035	0.015
6/26/2026, 10:56:00 AM	0.0297	0.016
6/26/2026, 10:57:00 AM	0.0291	0.018
6/26/2026, 10:58:00 AM	0.0277	0.019
6/26/2026, 10:59:00 AM	0.0268	0.019
6/26/2026, 11:00:00 AM	0.0268	0.019

Upwind CAMP Data
260 West 126th Street - New York, NY
Remedial Investigation

Date / Time	Particulates - 15-min Average (mg/m^3)	VOCs - 15-min Average (ppm)
6/26/2026, 11:01:00 AM	0.0271	0.02
6/26/2026, 11:02:00 AM	0.0221	0.021
6/26/2026, 11:03:00 AM	0.0284	0.022
6/26/2026, 11:04:00 AM	0.0299	0.022
6/26/2026, 11:05:00 AM	0.0375	0.022
6/26/2026, 11:06:00 AM	0.0491	0.023
6/26/2026, 11:07:00 AM	0.0515	0.023
6/26/2026, 11:08:00 AM	0.0523	0.023
6/26/2026, 11:09:00 AM	0.0534	0.023
6/26/2026, 11:10:00 AM	0.0531	0.025
6/26/2026, 11:11:00 AM	0.0531	0.026
6/26/2026, 11:12:00 AM	0.0579	0.026
6/26/2026, 11:13:00 AM	0.0585	0.027
6/26/2026, 11:14:00 AM	0.0599	0.028
6/26/2026, 11:15:00 AM	0.0629	0.028
6/26/2026, 11:16:00 AM	0.0649	0.028
6/26/2026, 11:17:00 AM	0.0735	0.027
6/26/2026, 11:18:00 AM	0.0764	0.026
6/26/2026, 11:19:00 AM	0.0771	0.029
6/26/2026, 11:20:00 AM	0.0722	0.028
6/26/2026, 11:21:00 AM	0.0623	0.026
6/26/2026, 11:22:00 AM	0.0617	0.024
6/26/2026, 11:23:00 AM	0.0629	0.023
6/26/2026, 11:24:00 AM	0.0631	0.021
6/26/2026, 11:25:00 AM	0.0638	0.021
6/26/2026, 11:26:00 AM	0.0657	0.021
6/26/2026, 11:27:00 AM	0.0641	0.02
6/26/2026, 11:28:00 AM	0.0643	0.018
6/26/2026, 11:29:00 AM	0.0631	0.016
6/26/2026, 11:30:00 AM	0.0599	0.015
6/26/2026, 11:31:00 AM	0.0583	0.014
6/26/2026, 11:32:00 AM	0.0552	0.014
6/26/2026, 11:33:00 AM	0.0528	0.016
6/26/2026, 11:34:00 AM	0.0507	0.015
6/26/2026, 11:35:00 AM	0.0484	0.016
6/26/2026, 11:36:00 AM	0.0471	0.018
6/26/2026, 11:37:00 AM	0.046	0.02
6/26/2026, 11:38:00 AM	0.0442	0.024
6/26/2026, 11:39:00 AM	0.0432	0.026
6/26/2026, 11:40:00 AM	0.0427	0.026
6/26/2026, 11:41:00 AM	0.0417	0.028
6/26/2026, 11:42:00 AM	0.0386	0.03
6/26/2026, 11:43:00 AM	0.0392	0.033

Upwind CAMP Data
260 West 126th Street - New York, NY
Remedial Investigation

Date / Time	Particulates - 15-min Average (mg/m^3)	VOCs - 15-min Average (ppm)
6/26/2026, 11:44:00 AM	0.0411	0.037
6/26/2026, 11:45:00 AM	0.0424	0.04
6/26/2026, 11:46:00 AM	0.0424	0.042
6/26/2026, 11:47:00 AM	0.038	0.043
6/26/2026, 11:48:00 AM	0.033	0.043
6/26/2026, 11:49:00 AM	0.0337	0.041
6/26/2026, 11:50:00 AM	0.0338	0.041
6/26/2026, 11:51:00 AM	0.0335	0.04
6/26/2026, 11:52:00 AM	0.0332	0.04
6/26/2026, 11:53:00 AM	0.0339	0.039
6/26/2026, 11:54:00 AM	0.0341	0.039
6/26/2026, 11:55:00 AM	0.0346	0.039
6/26/2026, 11:56:00 AM	0.0354	0.039
6/26/2026, 11:57:00 AM	0.0359	0.04
6/26/2026, 11:58:00 AM	0.0344	0.039
6/26/2026, 11:59:00 AM	0.0329	0.037
6/26/2026, 12:00:00 PM	0.0314	0.036
6/26/2026, 12:01:00 PM	0.0309	0.036
6/26/2026, 12:02:00 PM	0.0301	0.037
6/26/2026, 12:03:00 PM	0.0299	0.037
6/26/2026, 12:04:00 PM	0.0301	0.038
6/26/2026, 12:05:00 PM	0.0303	0.038
6/26/2026, 12:06:00 PM	0.0313	0.04
6/26/2026, 12:07:00 PM	0.0315	0.039
6/26/2026, 12:08:00 PM	0.0311	0.039
6/26/2026, 12:09:00 PM	0.0311	0.038
6/26/2026, 12:10:00 PM	0.0309	0.037
6/26/2026, 12:11:00 PM	0.0299	0.036
6/26/2026, 12:12:00 PM	0.0293	0.034
6/26/2026, 12:13:00 PM	0.0301	0.033
6/26/2026, 12:14:00 PM	0.0304	0.033
6/26/2026, 12:15:00 PM	0.0305	0.031
6/26/2026, 12:16:00 PM	0.0307	0.027
6/26/2026, 12:17:00 PM	0.0307	0.026
6/26/2026, 12:18:00 PM	0.0297	0.024
6/26/2026, 12:19:00 PM	0.0291	0.024
6/26/2026, 12:20:00 PM	0.0291	0.023
6/26/2026, 12:21:00 PM	0.0281	0.022
6/26/2026, 12:22:00 PM	0.0279	0.023
6/26/2026, 12:23:00 PM	0.0277	0.023
6/26/2026, 12:24:00 PM	0.0275	0.023
6/26/2026, 12:25:00 PM	0.0273	0.024
6/26/2026, 12:26:00 PM	0.0271	0.025

Upwind CAMP Data
260 West 126th Street - New York, NY
Remedial Investigation

Date / Time	Particulates - 15-min Average (mg/m^3)	VOCs - 15-min Average (ppm)
6/26/2026, 12:27:00 PM	0.0268	0.025
6/26/2026, 12:28:00 PM	0.026	0.027
6/26/2026, 12:29:00 PM	0.0256	0.028
6/26/2026, 12:30:00 PM	0.0255	0.03
6/26/2026, 12:31:00 PM	0.0254	0.032
6/26/2026, 12:32:00 PM	0.0255	0.034
6/26/2026, 12:33:00 PM	0.0254	0.037
6/26/2026, 12:34:00 PM	0.0255	0.038
6/26/2026, 12:35:00 PM	0.0255	0.04
6/26/2026, 12:36:00 PM	0.0256	0.04
6/26/2026, 12:37:00 PM	0.0257	0.042
6/26/2026, 12:38:00 PM	0.0259	0.042
6/26/2026, 12:39:00 PM	0.0261	0.043
6/26/2026, 12:40:00 PM	0.0262	0.043
6/26/2026, 12:41:00 PM	0.0263	0.044
6/26/2026, 12:42:00 PM	0.0264	0.046
6/26/2026, 12:43:00 PM	0.0264	0.047
6/26/2026, 12:44:00 PM	0.0265	0.048
6/26/2026, 12:45:00 PM	0.0265	0.05
6/26/2026, 12:46:00 PM	0.0265	0.051
6/26/2026, 12:47:00 PM	0.0265	0.052
6/26/2026, 12:48:00 PM	0.0264	0.053
6/26/2026, 12:49:00 PM	0.0263	0.054
6/26/2026, 12:50:00 PM	0.0261	0.056
6/26/2026, 12:51:00 PM	0.0262	0.057
6/26/2026, 12:52:00 PM	0.0261	0.059
6/26/2026, 12:53:00 PM	0.0261	0.061
6/26/2026, 12:54:00 PM	0.026	0.063
6/26/2026, 12:55:00 PM	0.0261	0.064
6/26/2026, 12:56:00 PM	0.0263	0.065
6/26/2026, 12:57:00 PM	0.0265	0.065
6/26/2026, 12:58:00 PM	0.0266	0.066
6/26/2026, 12:59:00 PM	0.0267	0.067
6/26/2026, 1:00:00 PM	0.0269	0.068
6/26/2026, 1:01:00 PM	0.0271	0.068
6/26/2026, 1:02:00 PM	0.0273	0.069
6/26/2026, 1:03:00 PM	0.0274	0.069
6/26/2026, 1:04:00 PM	0.0275	0.068
6/26/2026, 1:05:00 PM	0.0277	0.068
6/26/2026, 1:06:00 PM	0.0277	0.068
6/26/2026, 1:07:00 PM	0.0284	0.068
6/26/2026, 1:08:00 PM	0.0295	0.066
6/26/2026, 1:09:00 PM	0.0298	0.063

Upwind CAMP Data
260 West 126th Street - New York, NY
Remedial Investigation

Date / Time	Particulates - 15-min Average (mg/m^3)	VOCs - 15-min Average (ppm)
6/26/2026, 1:10:00 PM	0.0298	0.061
6/26/2026, 1:11:00 PM	0.0297	0.057
6/26/2026, 1:12:00 PM	0.0297	0.055
6/26/2026, 1:13:00 PM	0.0297	0.054
6/26/2026, 1:14:00 PM	0.0299	0.053
6/26/2026, 1:15:00 PM	0.0299	0.052
6/26/2026, 1:16:00 PM	0.0299	0.052
6/26/2026, 1:17:00 PM	0.0309	0.05
6/26/2026, 1:18:00 PM	0.0313	0.049
6/26/2026, 1:19:00 PM	0.0313	0.048
6/26/2026, 1:20:00 PM	0.0313	0.046
6/26/2026, 1:21:00 PM	0.0313	0.046
6/26/2026, 1:22:00 PM	0.0306	0.045
6/26/2026, 1:23:00 PM	0.0295	0.045
6/26/2026, 1:24:00 PM	0.029	0.047
6/26/2026, 1:25:00 PM	0.0306	0.05
6/26/2026, 1:26:00 PM	0.031	0.051
6/26/2026, 1:27:00 PM	0.0308	0.051
6/26/2026, 1:28:00 PM	0.0318	0.05
6/26/2026, 1:29:00 PM	0.0328	0.05
6/26/2026, 1:30:00 PM	0.0327	0.046
6/26/2026, 1:31:00 PM	0.0325	0.043
6/26/2026, 1:32:00 PM	0.0313	0.041
6/26/2026, 1:33:00 PM	0.0312	0.039
6/26/2026, 1:34:00 PM	0.0311	0.037
6/26/2026, 1:35:00 PM	0.0309	0.034
6/26/2026, 1:36:00 PM	0.0309	0.031
6/26/2026, 1:37:00 PM	0.0317	0.03
6/26/2026, 1:38:00 PM	0.0347	0.029
6/26/2026, 1:39:00 PM	0.0372	0.027
6/26/2026, 1:40:00 PM	0.0374	0.023
6/26/2026, 1:41:00 PM	0.0379	0.02
6/26/2026, 1:42:00 PM	0.0419	0.017
6/26/2026, 1:43:00 PM	0.0439	0.015
6/26/2026, 1:44:00 PM	0.0433	0.012
6/26/2026, 1:45:00 PM	0.0435	0.011
6/26/2026, 1:46:00 PM	0.0437	0.011
6/26/2026, 1:47:00 PM	0.0438	0.009
6/26/2026, 1:48:00 PM	0.0435	0.008
6/26/2026, 1:49:00 PM	0.0439	0.008
6/26/2026, 1:50:00 PM	0.044	0.008
6/26/2026, 1:51:00 PM	0.0439	0.007
6/26/2026, 1:52:00 PM	0.0432	0.006

Upwind CAMP Data
260 West 126th Street - New York, NY
Remedial Investigation

Date / Time	Particulates - 15-min Average (mg/m^3)	VOCs - 15-min Average (ppm)
6/26/2026, 1:53:00 PM	0.0402	0.005
6/26/2026, 1:54:00 PM	0.0378	0.004
6/26/2026, 1:55:00 PM	0.0357	0.005
6/26/2026, 1:56:00 PM	0.0345	0.006
6/26/2026, 1:57:00 PM	0.0311	0.008
6/26/2026, 1:58:00 PM	0.0281	0.009
6/26/2026, 1:59:00 PM	0.0276	0.01
6/26/2026, 2:00:00 PM	0.028	0.01
6/26/2026, 2:01:00 PM	0.0279	0.01
6/26/2026, 2:02:00 PM	0.0278	0.01
6/26/2026, 2:03:00 PM	0.0287	0.01
6/26/2026, 2:04:00 PM	0.0281	0.009
6/26/2026, 2:05:00 PM	0.0279	0.009
6/26/2026, 2:06:00 PM	0.0278	0.009
6/26/2026, 2:07:00 PM	0.0276	0.009
6/26/2026, 2:08:00 PM	0.0274	0.008
6/26/2026, 2:09:00 PM	0.029	0.009
6/26/2026, 2:10:00 PM	0.0289	0.009
6/26/2026, 2:11:00 PM	0.0295	0.009
6/26/2026, 2:12:00 PM	0.0298	0.007
6/26/2026, 2:13:00 PM	0.0301	0.006
6/26/2026, 2:14:00 PM	0.03	0.006
6/26/2026, 2:15:00 PM	0.0293	0.006
6/26/2026, 2:16:00 PM	0.0317	0.007
6/26/2026, 2:17:00 PM	0.0325	0.007
6/26/2026, 2:18:00 PM	0.0315	0.007
6/26/2026, 2:19:00 PM	0.0328	0.008
6/26/2026, 2:20:00 PM	0.0335	0.007
6/26/2026, 2:21:00 PM	0.0338	0.007
6/26/2026, 2:22:00 PM	0.0342	0.007
6/26/2026, 2:23:00 PM	0.0343	0.006
6/26/2026, 2:24:00 PM	0.0331	0.004
6/26/2026, 2:25:00 PM	0.0339	0.003
6/26/2026, 2:26:00 PM	0.0345	0.002
6/26/2026, 2:27:00 PM	0.0349	0.002
6/26/2026, 2:28:00 PM	0.0351	0.002
6/26/2026, 2:29:00 PM	0.0354	0.002
6/26/2026, 2:30:00 PM	0.0357	0.002
6/26/2026, 2:31:00 PM	0.0329	0.001
6/26/2026, 2:32:00 PM	0.0319	0.001
6/26/2026, 2:33:00 PM	0.0317	0.001
6/26/2026, 2:34:00 PM	0.0301	0.001
6/26/2026, 2:35:00 PM	0.0292	0.002

Appendix D
Soil Boring and Monitoring Well Construction Logs

TENEN ENVIRONMENTAL

Boring No.	**SB-1 / MW-1**		
Sheet	**1 of 1**		
Site:	**260 West 126th Street - New York, NY**	**Drilling Method:**	Geoprobe Direct-Push
Date:	**1/6/2026**	**Soil Sampling Method:**	Acetate Liner
Weather:	**40°F, Overcast**	**DTW:**	23 ft-bg
Observer:	**H. Lau**	**Driller :**	Coastal Environmental

Depth (feet)	PID Reading (ppm)	Soil Recovery	Soil Samples	Depth to Water	Well Construction	Soil Description
1	0.0		SB-1 (0-2')		2" PVC Riser (0-20')	0'-5' - FILL, brown, medium SAND with ash and brick fragments
2	0.0	28"				
3						
4	0.0					
5						
6	0.0					5'-6' - FILL, brown, medium SAND with ash and brick fragments 6'-10' - Brown, coarse SAND with gravel
7			SB-1 (6-8')			
8	0.0	14"				
9						
10	0.0					
11	0.0					10'-15' - Brown, medium to coarse SAND with gravel
12						
13	0.0	40"				
14						
15	0.0					
16	0.0					15'-20' - Brown, medium to coarse SAND with gravel
17						
18	0.0	16"				
19						
20	0.0					
21	0.0				2" PVC Screen (20-30')	20'-25' - Brown, medium to coarse SAND with gravel, wet @ 23 ft-bg
22			SB-1 (21-23')			
23	0.0	50"		▽		
24						
25	0.0					
26	0.0					25'-30' - Brown, medium to coarse SAND with gravel **EOB @ 30 ft-bg**
27						
28	0.0	50"				
29						
30	0.0					

Notes:

Legend:

DTW - Depth to Water
EOB - End of Boring
ft-bg - Feet Below Grade
SM - Silty Sand
SW - Well-graded Sand
GW - Groundwater
PID - Photoionization Detector
SAA - Same as Above
NR - Not Recorded
SP - Poorly Graded Sand
GP - Poorly Graded Gravel

TENEN ENVIRONMENTAL

		Boring No.	**SB-2 / MW-2**
		Sheet	**1 of 1**
Site:	**260 West 126th Street - New York, NY**	**Drilling Method:**	Geoprobe Direct-Push & Sonic
Date:	**1/6/2026 & 1/9/2026**	**Soil Sampling Method:**	Acetate Liner
Weather:	**40°F, Overcast**	**DTW:**	24 ft-bg
Observer:	**H. Lau**	**Driller :**	Coastal Environmental

Depth (feet)	PID Reading (ppm)	Soil Recovery	Soil Samples	Depth to Water	Well Construction	Soil Description
1	0.0		SB-2 (0-2')		2" PVC Riser (0-20')	0'-5' - FILL, brown, fine to medium SAND with ash, brick fragments, and asphalt
2						
3	0.0	28"				
4						
5	0.0					
6	0.0					5'-6' - FILL, brown, fine to medium SAND with ash, brick fragments, and asphalt 6'-10' - Brown to reddish brown, medium to coarse SAND with gravel
7			SB-2 (6-8')			
8	0.0	15"				
9						
10	0.0					
11	0.0					10'-15' - Brown, medium to coarse SAND with gravel
12						
13	0.0	18"				
14						
15	0.0					
16	0.0					15'-20' - Brown, coarse SAND with gravel
17						
18	0.0	17"				
19						
20	0.0					
21	0.0				2" PVC Screen (20-30')	20'-25' - Brown, coarse SAND with gravel, wet @ 24 ft-bg
22						
23	0.0	16"	SB-2 (22-24')	▼		
24						
25	0.0					
26	0.0					25'-30' - Brown, coarse SAND with gravel **EOB @ 30 ft-bg**
27						
28	0.0	16"				
29						
30	0.0					

Notes:

Legend:

DTW - Depth to Water
EOB - End of Boring
ft-bg - Feet Below Grade
SM - Silty Sand
SW - Well-graded Sand
GW - Groundwater
PID - Photoionization Detector
SAA - Same as Above
NR - Not Recorded
SP - Poorly Graded Sand
GP - Poorly Graded Gravel

TENEN ENVIRONMENTAL

		Boring No.	**SB-3 / MW-3**
		Sheet	**1 of 1**
Site:	**260 West 126th Street - New York, NY**	**Drilling Method:**	Geoprobe Direct-Push
Date:	**1/5/2026 & 1/6/2026**	**Soil Sampling Method:**	Acetate Liner
Weather:	**34°F, Overcast**	**DTW:**	24 ft-bg
Observer:	**H. Lau**	**Driller :**	Coastal Environmental

Depth (feet)	PID Reading (ppm)	Soil Recovery	Soil Samples	Depth to Water	Well Construction	Soil Description
1	0.0		SB-3 (0-2')		2" PVC Riser (0-16')	0'-5' - FILL, brown, medium to fine SAND with ash, brick fragments, and asphalt
2	0.0	22"				
3						
4	0.0					
5						
6	0.0					5'-8' - FILL, brown, medium to fine SAND with ash, brick fragments, and asphalt
7						
8	0.0	29"				8'-10' - Brown, fine to medium SAND with gravel
9			SB-3 (8-10')			
10	0.0					
11	0.0					10'-15' - Brown, fine to medium SAND with gravel
12						
13	0.0	30"				
14						
15	0.0					
16	0.0					15'-20' - Brown, medium to coarse SAND with gravel
17						
18	0.0	20"				
19						
20	0.0					
21	0.0				2" PVC Screen (16-26')	20'-25' - Brown, medium to coarse SAND with gravel, wet @ 24 ft-bg
22						
23	0.0	40"	SB-3 (22-24')	▽		
24						
25	0.0					
26	0.0					25'-30' - Brown, medium to coarse SAND with gravel
27						
28	0.0	40"				**EOB @ 30 ft-bg**
29						
30	0.0					

Notes:

Legend:

DTW - Depth to Water
EOB - End of Boring
ft-bg - Feet Below Grade
SM - Silty Sand
SW - Well-graded Sand
GW - Groundwater
PID - Photoionization Detector
SAA - Same as Above
NR - Not Recorded
SP - Poorly Graded Sand
GP - Poorly Graded Gravel

TENEN ENVIRONMENTAL

		Boring No.	**SB-4 / MW-4**
		Sheet	**1 of 1**
Site:	**260 West 126th Street - New York, NY**	**Drilling Method:**	Geoprobe Direct-Push
Date:	**6/26/2026**	**Soil Sampling Method:**	Acetate Liner
Weather:	**72°F, Overcast/Rain**	**DTW:**	15 ft-bg
Observer:	**A. Platt**	**Driller :**	PG Environmental

Depth (feet)	PID Reading (ppm)	Soil Recovery	Soil Samples	Depth to Water	Well Construction	Soil Description
1	0.0	28"	SB-4 (0-2')		2" PVC Riser (0-10')	0'-4" - Concrete Basement Slab 4'"-5' - FILL, brown, fine to coarse SAND, trace silt and gravel, concrete fragments, and brick fragments
2						
3	0.0					
4						
5	0.0					
6	0.0	60"				5'-10' - FILL, brown, fine to coarse SAND trace silt and gravel, concrete fragments, and brick fragments
7						
8	0.0					
9						
10	0.0					
11	0.0	60"			2" PVC Screen (10-20')	10'-12' - FILL, brown, fine to coarse SAND trace silt and gravel, concrete fragments, and brick fragments
12						
13	0.0		SB-4 (12-14')			12'-15' - Brown, medium to coarse SAND, trace gravel, medium dense, wet @ 15 ft-bg
14						
15	0.0		SB-4 (14-15')	▼		
16		0"				15'-20' - No recovery **EOB @ 20 ft-bg (approximately 30 feet below sidewalk grade)**
17						
18						
19						
20						

Notes: Basement slab where boring was started is approximately 10 feet below sidewalk grade.

Legend:

DTW - Depth to Water
EOB - End of Boring
ft-bg - Feet Below Grade
SM - Silty Sand
SW - Well-graded Sand
GW - Groundwater
PID - Photoionization Detector
SAA - Same as Above
NR - Not Recorded
SP - Poorly Graded Sand
GP - Poorly Graded Gravel

TEN EN ENVIRONMENTAL		Boring No.	SB-5
		Sheet	1 of 1
Site:	260 West 126th Street - New York, NY	Drilling Method:	Geoprobe Direct-Push
Date:	1/5/2026	Soil Sampling Method:	Acetate Liner
Weather:	34°F, Overcast	DTW:	24 ft-bg
Observer:	H. Lau	Driller :	Coastal Environmental

Depth (feet)	PID Reading (ppm)	Soil Recovery	Soil Samples	Soil Description
1	0.0		SB-5 (0-2')	0'-5' - FILL, brown, medium to fine SAND with gravel, brick fragments, and asphalt
2				
3	0.0	20"		
4				
5	0.0			
6	0.0			5'-10' - FILL, brown, medium to fine SAND with gravel, brick fragments, and asphalt.
7				
8	0.0	34"		
9				
10	0.0			
11	0.0			10'-12.5' - FILL, brown, medium to fine SAND with gravel, brick fragments, asphalt, and ash.
12				
13	0.0	51"		12.5'-15' - Brown, medium to coarse SAND with gravel
14			SB-5 (12.5-14.5')	
15	0.0			
16	0.0			15'-20' - Brown to reddish brown, medium to coarse SAND with gravel
17				
18	0.0	29"		
19				
20	0.0			
21	0.0			20'-25' - Brown, medium to coarse SAND, wet @ 24 ft-bg
22				
23	0.0	29"	SB-5 (22-24')	
24				
25	0.0			
26	0.0			25'-30' - Brown, medium to coarse SAND
27				
28	0.0	25"		**EOB @ 30 ft-bg**
29				
30	0.0			

Notes:

Legend:

DTW - Depth to Water
EOB - End of Boring
ft-bg - Feet Below Grade
SM - Silty Sand
SW - Well-graded Sand
GW - Groundwater
PID - Photoionization Detector
SAA - Same as Above
NR - Not Recorded
SP - Poorly Graded Sand
GP - Poorly Graded Gravel

TENEN ENVIRONMENTAL		Boring No.	SB-6
		Sheet	1 of 1
Site:	260 West 126th Street - New York, NY	Drilling Method:	Geoprobe Direct-Push
Date:	1/5/2026	Soil Sampling Method:	Acetate Liner
Weather:	34°F, Overcast	DTW:	24 ft-bg
Observer:	H. Lau	Driller :	Coastal Environmental

Depth (feet)	PID Reading (ppm)	Soil Recovery	Soil Samples	Soil Description
1	0.0	16"	SB-6 (0-2')	0'-5' - FILL, brown, medium to fine SAND with gravel and asphalt
2				
3	0.0			
4				
5	0.0			
6	0.0	24"		5'-8' - FILL, brown, medium to fine SAND with gravel, and brick fragments
7				
8	0.0			8-10' - Brown, medium to fine SAND with gravel
9			SB-6 (8-10')	
10	0.0			
11	0.0	15"		10'-15' - Brown, medium to fine SAND with gravel
12				
13	0.0			
14				
15	0.0			
16	0.0	34"		15'-20' - Brown, medium to fine SAND with gravel
17				
18	0.0			
19				
20	0.0			
21	0.0	34"		20'-25' - Brown, medium to coarse SAND with gravel, wet @ 24 ft-bg
22				
23	0.0		SB-6 (22-24')	
24				
25	0.0			
26	0.0	17"		25'-30' - Brown, medium to coarse SAND with gravel
27				
28	0.0			**EOB @ 30 ft-bg**
29				
30	0.0			

Notes:

Legend:

DTW - Depth to Water
EOB - End of Boring
ft-bg - Feet Below Grade
SM - Silty Sand
SW - Well-graded Sand
GW - Groundwater
PID - Photoionization Detector
SAA - Same as Above
NR - Not Recorded
SP - Poorly Graded Sand
GP - Poorly Graded Gravel

TENEN ENVIRONMENTAL

		Boring No.	**SB-7 / MW-5**
		Sheet	**1 of 1**
Site:	**260 West 126th Street - New York, NY**	**Drilling Method:**	Geoprobe Direct-Push
Date:	**6/26/2026**	**Soil Sampling Method:**	Acetate Liner
Weather:	**72°F, Overcast/Rain**	**DTW:**	14 ft-bg
Observer:	**A. Platt**	**Driller :**	PG Environmental

Depth (feet)	PID Reading (ppm)	Soil Recovery	Soil Samples	Depth to Water	Well Construction	Soil Description
1	0.0	31"	SB-7 (0-2')		2" PVC Riser (0-10')	0'-4" - Concrete Basement Slab 4"'-5' - FILL, brown, fine to coarse SAND, trace silt and gravel, concrete fragments, and brick fragments
2						
3	0.0					
4						
5	0.0					
6	0.0	17"				5'-10' - FILL, brown, fine to coarse SAND trace silt and gravel, concrete fragments, and brick fragments
7						
8	0.0					
9						
10	0.0					
11	0.0	31"	SB-7 (10-12')		2" PVC Screen (10-20')	10'-15' - Brown, medium to coarse SAND with gravel, wet @ 14 ft-bg
12						
13	0.0		SB-7 (12-14')	▼		
14						
15	0.0					
16	0.0	60"				15'-20' - Brown, fine to coarse SAND with gravel, trace silt **EOB @ 20 ft-bg (approximately 30 feet below sidewalk grade)**
17						
18	0.0					
19						
20	0.0					

Notes: Basement slab where boring was started is approximately 10 feet below sidewalk grade.

Legend:

DTW - Depth to Water
EOB - End of Boring
ft-bg - Feet Below Grade
SM - Silty Sand
SW - Well-graded Sand
GW - Groundwater
PID - Photoionization Detector
SAA - Same as Above
NR - Not Recorded
SP - Poorly Graded Sand
GP - Poorly Graded Gravel

TENEN ENVIRONMENTAL

Boring No.	**SB-8 / MW-6**		
Sheet	**1 of 1**		
Site:	**260 West 126th Street - New York, NY**	**Drilling Method:**	Geoprobe Direct-Push & Sonic
Date:	**1/5/2026, 1/6/2026, & 1/9/2026**	**Soil Sampling Method:**	Acetate Liner
Weather:	**34-40°F, Overcast**	**DTW:**	24 ft-bg
Observer:	**H. Lau**	**Driller :**	Coastal Environmental

Depth (feet)	PID Reading (ppm)	Soil Recovery	Soil Samples	Depth to Water	Well Construction	Soil Description
1	0.0		SB-8 (0-2')		2" PVC Riser (0-20')	0'-5' - FILL, brown, fine SAND with ash, brick fragments, and asphalt
2	0.0	21"				
3						
4	0.0					
5						
6	0.0					5'-8' - FILL, brown, fine SAND with ash, brick fragments, and asphalt
7						
8	0.0	2"				8'-10' - Brown, medium to coarse SAND with gravel
9			SB-8 (8-10')			
10	0.0					
11	0.0					10'-15' - Brown, medium to coarse SAND with gravel
12						
13	0.0	18"				
14						
15	0.0					
16	0.0					15'-20' - Brown, coarse SAND with gravel
17						
18	0.0	38"				
19						
20	0.0					
21	0.0				2" PVC Screen (20-30')	20'-25' - Brown, coarse SAND with gravel, wet @ 24 ft-bg
22						
23	0.0	40"	SB-8 (22-24')	▽		
24						
25	0.0					
26	0.0					25'-30' - Brown, coarse SAND with gravel
27						
28	0.0	38"				**EOB @ 30 ft-bg**
29						
30	0.0					

Notes:

Legend:

DTW - Depth to Water
EOB - End of Boring
ft-bg - Feet Below Grade
SM - Silty Sand
SW - Well-graded Sand
GW - Groundwater
PID - Photoionization Detector
SAA - Same as Above
NR - Not Recorded
SP - Poorly Graded Sand
GP - Poorly Graded Gravel

TEN EN ENVIRONMENTAL		Boring No.	SB-9
		Sheet	1 of 1
Site:	260 West 126th Street - New York, NY	Drilling Method:	Geoprobe Direct-Push
Date:	1/6/2026	Soil Sampling Method:	Acetate Liner
Weather:	40°F, Overcast	DTW:	24 ft-bg
Observer:	H. Lau	Driller :	Coastal Environmental

Depth (feet)	PID Reading (ppm)	Soil Recovery	Soil Samples	Soil Description
1	0.0	36"	SB-9 (0-2')	0'-5' - FILL, brown, medium SAND with ash, brick fragments, and asphalt
2				
3	0.0			
4				
5	0.0			
6	0.0	16"		5'-6' - FILL, brown, medium SAND with ash, brick fragments, and asphalt 6-10' - Brown, medium to coarse SAND with gravel
7			SB-9 (6-8')	
8	0.0			
9				
10	0.0			
11	0.0	22"		10'-15' - Brown, coarse SAND with gravel
12				
13	0.0			
14				
15	0.0			
16	0.0	23"		15'-20' - Brown, coarse SAND with gravel
17				
18	0.0			
19				
20	0.0			
21	0.0	22"		20'-25' - Brown, coarse SAND with gravel, wet @ 24 ft-bg
22				
23	0.0		SB-9 (22-24')	
24				
25	0.0			
26	0.0	12"		25'-30' - Brown, coarse SAND with gravel **EOB @ 30 ft-bg**
27				
28	0.0			
29				
30	0.0			

Notes:

Legend:

DTW - Depth to Water
EOB - End of Boring
ft-bg - Feet Below Grade
SM - Silty Sand
SW - Well-graded Sand
GW - Groundwater
PID - Photoionization Detector
SAA - Same as Above
NR - Not Recorded
SP - Poorly Graded Sand
GP - Poorly Graded Gravel

Appendix E
Monitoring Well Purging and Sampling Logs and Monitoring Well Survey

GROUNDWATER SAMPLING LOG

Site Name	260 West 126th Street	Date	1/22/2026
Well No.	MW-1	Sample ID	MW-1

Well Diameter	2 inches	Depth to Water	23.03 ft-bg
Well Screen Interval	20-30 ft-bg	Depth to Bottom	29.72 ft-bg
Headspace PID	0.0 ppm		
Weather	30s-40s, fair		

Pump	Peristaltic
Water Quality Meter	Horiba U-52
Total Volume Purged	5 gallons

Time	Temperature deg-C	pH SU	ORP mV	Conductivity mS/cm	Turbidity NTU	Dissolved Oxygen mg/L	Total Dissolved Solids ppm
8:15	14.58	7.54	105	0.716	154	5.96	0.453
8:25	15.74	7.32	121	0.648	21.4	5.38	0.415
8:35	15.95	7.30	134	0.641	3.2	4.73	0.410
8:45	16.27	7.29	143	0.639	0.6	7.36	0.406
8:55	16.01	7.30	148	0.639	0.1	4.78	0.406

Notes: Begin purging @ 8:08. Hookup Horiba @8:12. Sample MW-1 @ 9:05, MS @ 9:10, and MSD @ 9:15.

GROUNDWATER SAMPLING LOG

Site Name	260 West 126th Street	Date	1/22/2026
Well No.	MW-2	Sample ID	MW-2

Well Diameter	2 inches	Depth to Water	23.95 ft-bg
Well Screen Interval	20-30 ft-bg	Depth to Bottom	29.98 ft-bg
Headspace PID	16.4 ppm		
Weather	30s-40s,Fair		

Pump	Peristaltic
Water Quality Meter	Horiba U-52
Total Volume Purged	4 gallons

Time	Temperature deg-C	pH SU	ORP mV	Conductivity mS/cm	Turbidity NTU	Dissolved Oxygen mg/L	Total Dissolved Solids ppm
11:15	14.83	7.34	-421	0.508	50.3	0.18	0.325
11:25	14.9	7.42	-423	0.500	27.8	0.00	0.325
11:35	15.3	7.44	-397	0.492	11.1	0.00	0.320
11:45	15.46	7.41	-383	0.486	7.1	0.00	0.316

Notes: Begin purging @ 11:10. Hookup Horiba @ 11:12. Sample MW-2 @ 11:50.

GROUNDWATER SAMPLING LOG

Site Name	260 West 126th Street	Date	1/22/2026
Well No.	MW-3	Sample ID	MW-3

Well Diameter	2 inches	Depth to Water	23.66 ft-bg
Well Screen Interval	16-26 ft-bg	Depth to Bottom	26.35 ft-bg
Headspace PID	0.0 ppm		
Weather	30s-40s, Fair		

Pump	Peristaltic
Water Quality Meter	Horiba U-52
Total Volume Purged	4 gallons

Time	Temperature deg-C	pH SU	ORP mV	Conductivity mS/cm	Turbidity NTU	Dissolved Oxygen mg/L	Total Dissolved Solids ppm
11:10	15.14	7.36	166	0.617	6.4	3.87	0.395
11:20	16.41	7.41	160	0.607	0.0	3.79	0.388
11:30	16.61	7.40	160	0.605	0.0	3.62	0.387
11:40	16.33	7.41	160	0.608	0.0	3.96	0.389

Notes: Begin purging @ 11:05. Hookup Horiba @ 11:09. Sample MW-3 @ 11:45.

GROUNDWATER SAMPLING LOG

Site Name	260 West 126th Street	Date	7/9/2026
Well No.	MW-4	Sample ID	MW-4

Well Diameter	2 inches	Depth to Water	14.40 ft-bg
Well Screen Interval	10-20 ft-bg	Depth to Bottom	20.22 ft-bg
Headspace PID	0.0 ppm		
Weather	70s-80s, Fair		

Pump	Peristaltic
Water Quality Meter	Horiba U-52
Total Volume Purged	6 gallons

Time	Temperature deg-C	pH SU	ORP mV	Conductivity mS/cm	Turbidity NTU	Dissolved Oxygen mg/L	Total Dissolved Solids ppm
7:25	21.67	8.87	179	0.450	296.0	4.54	0.289
7:35	19.50	7.95	168	0.380	42.6	2.95	0.246
7:45	19.08	7.77	162	0.377	26.6	2.97	0.245
7:55	19.03	7.74	164	0.376	16.2	2.85	0.245

Notes: Begin purging @ 6:45. Hookup Horiba @ 7:23. Sample MW-4 @ 8:00.

GROUNDWATER SAMPLING LOG

Site Name	260 West 126th Street	Date	7/9/2026
Well No.	MW-5	Sample ID	MW-5

Well Diameter	2 inches	Depth to Water	12.15 ft-bg
Well Screen Interval	10-20 ft-bg	Depth to Bottom	19.40 ft-bg
Headspace PID	0.0 ppm		
Weather	70s-80s, Fair		

Pump	Peristaltic
Water Quality Meter	Horiba U-52
Total Volume Purged	12 gallons

Time	Temperature deg-C	pH SU	ORP mV	Conductivity mS/cm	Turbidity NTU	Dissolved Oxygen mg/L	Total Dissolved Solids ppm
8:35	19.16	7.63	169	0.414	238.0	4.44	0.269
8:45	19.16	7,53	173	0.403	68.7	4.07	0.262
8:55	19.19	7,48	171	0.395	19.3	3.81	0.257
9:05	19.18	7.47	170	0.394	10.6	3.69	0.256

Notes: Begin purging @ 7:30. Hookup Horiba @ 8:30. Sample MW-5 @ 9:10.

GROUNDWATER SAMPLING LOG


Site Name	260 West 126th Street	Date	1/22/2026
Well No.	MW-6	Sample ID	MW-6

Well Diameter	2 inches	Depth to Water	23.88 ft-bg
Well Screen Interval	20-30 ft-bg	Depth to Bottom	30.40 ft-bg
Headspace PID	11.0 ppm		
Weather	30s-40s, Fair		

Pump	Peristaltic
Water Quality Meter	Horiba U-52
Total Volume Purged	5 gallons

Time	Temperature deg-C	pH SU	ORP mV	Conductivity mS/cm	Turbidity NTU	Dissolved Oxygen mg/L	Total Dissolved Solids ppm
8:20	14.71	7.37	-281	0.469	106	1.06	0.304
8:30	15.33	7.26	-338	0.461	74.8	0.00	0.299
8:40	15.81	7.28	-345	0.457	24.3	0.00	0.297
8:50	15.99	7.28	-378	0.448	12.7	0.00	0.291
9:00	15.99	7.3	-408	0.448	9.2	0.00	0.291

Notes: Begin purging @ 8:15. Hookup Horiba @ 8:17. Sample MW-6 @ 9:20 and MW-6_DUP @ 9:25.



WELL ELEVATION TABLE

WELL I.D.	ELEVATIONS GROUND	PVC RISER
MW- 1	28.37	29.07
MW-2	29.27	30.62
MW-3	28.97	31.19
MW-4	19.81	24.91
MW-5	19.29	25.39
MW-6	29.23	30.15

NOTES:

-HORIZONTAL DATUM: ASSUMED

-VERTICAL DATUM: ASSUMED

-MW-4 AND MW-5 SURVEYED ON JULY 13, 2026

I HEREBY CERTIFY THAT THIS MAP IS BASED ON AN ACTUAL FIELD SURVEY COMPLETED ON FEBRUARY 12, 2026.

DONALD R. STEDGE, L.S., NYS LIC. NO. 49759

REVISED: JULY 13, 2026- MW-4 & MW-5, BUILDING, MACADAM PARKING

WELL ELEVATION SURVEY PREPARED FOR

260 WEST 126th STREET

MANHATTAN

NEW YORK COUNTY
SCALE: 1" = 15'

NEW YORK
FEBRUARY 12, 2026

DONALD R. STEDGE, P.L.S.
549 ROUTE 94 N
WARWICK, NY 10990
(845) 325-9734
donstedge@gmail.com

JOB NO. 2273

Traverse PC

Appendix F
Soil Vapor Sampling Logs

TENEN ENVIRONMENTAL

Site:	**260 West 126th Street - New York, NY**
Weather:	**30s-40s °F, Fair / 70s-80s °F, Fair**
Date:	**1/22/2026 / 7/9/2026**
Observers:	**A. Platt & H. Lau**

Sample ID	He (ppm)	PID (ppm)	Can ID	Flow ID	Sample Date	Initial Time	Final Time	Initial Pressure (in-Hg)	Final Pressure (in-Hg)
SV-1	0	0.0	16975	21023	1/22/2026	8:48	10:36	-30	-2
SV-2	0	0.0	10044	19436	1/22/2026	8:57	10:45	-29	-2
SV-3	0	0.0	36459	21035	1/22/2026	8:43	10:43	-30	-5
SV-4	0	0.0	51119	19396	1/22/2026	8:45	10:43	-30	-4
SV-5	0	0.0	34496	16417	1/22/2026	8:50	10:44	-30	-5
SV-6	0	0.6	16974	12183	1/22/2026	8:54	10:50	-30	-5
SV-7	0	0.0	50316	17203	7/9/2026	6:33	8:30	-29	-2
AA-1	N/A	N/A	18313	20423	1/22/2026	8:58	11:10	-30	-4
AA-2	N/A	N/A	20947	20922	7/9/2026	6:20	8:25	-30	-2

Notes: All soil vapor probes were constructed by installing a disposable sampling probe consisting of a 1.5-inch long hardened point and a 6-inch long perforated vapor intake to the target depth at each sample location (22 ft-bsg for SV-1, 8 ft-bsg forSV-2, SV-3, SV-4, SV-5, and SV-6, and 1 ft-bsg for SV-7). The screen of each sampling probe was surrounded by #1-size quartzite sand to approx. one foot above the top of the screen, followed by wetted bentonite pellets to grade.

ppm: parts per million in-Hg: inches mercury