

# INTERIM REMEDIAL MEASURE WORK PLAN

NYSDEC BCP SITE # C734108

AOC-4, Celi Drive BCP Site  
Town of Dewitt, Onondaga County, New York

**PREPARED BY:**

K. Teter Consulting, LLC  
32 Clinton Street  
Homer, New York 13077

and

GeoLogic NY, P.C.  
PO Box 350  
37 Copeland Avenue  
Homer, New York 13077

**PREPARED FOR:**

GSP Holdings, Inc.  
P.O. Box 41  
Fayetteville, New York 13066



December 2022



**K.TETER CONSULTING**

32 Clinton Street, Homer, NY 13077  
Phone: (607) 423-3595 kteter@twcny.ny.com

# CERTIFICATION

I, Kenneth J. Teter, certify that I am currently a NYS registered professional engineer and that this Interim Remedial Measure Work Plan was prepared in accordance with all applicable statutes and regulations and in substantial conformance with the DER Technical Guidance for Site Investigation and Remediation (DER-10).



A handwritten signature in blue ink, appearing to read "Kenneth J. Teter", written over a horizontal line.

Kenneth J. Teter, P.E.

12/15/22

Date

Seal/Signature

NYS Professional Engineer

# 081583

It is a violation of Article 145 of the New York State Education Law for any person to alter this document in any way without the express written verification of adoption by any New York State licensed engineer in accordance with Section 7209(2), Article 145, New York State Education Law.

## **ACKNOWLEDGEMENT OF ALTERATION**

The previous version of this report was dated January 2022 and was prepared by Asbestos & Environmental Consulting Corporation (E. Syracuse, NY) and Lakeside Engineering (Geneva, NY). Based on comments received from the NYS Department of Environmental Conservation, K. Teter Consulting of Homer NY was hired to review, revise and resubmit the IRMWP, which resulted in this document. Knowing that the previous report had been reviewed by the NYSDEC, went through a public comment period, and was found to be fundamentally acceptable and in accordance with all applicable regulations and guidance documents, this new report presents the same data and approach as the previous with only minor revisions. Consequently Kenneth J. Teter, P.E. contacted the previous engineer of record (Robert Harner, P.E. of Lakeside Engineering) and fully disclosed the fact that K. Teter Consulting will be utilizing the previous report as the basis of this new document.

# Table of Contents

<b>1.0 INTRODUCTION</b> .....	1
1.1 Background and Purpose.....	1
1.2 AOC-4.....	2
<b>2.0 REMEDIAL ACTION OBJECTIVES</b> .....	3
2.1 Groundwater RAOs.....	3
2.2 Soil RAOs.....	3
2.3 Surface Water RAOs.....	4
2.4 Sediment RAOs.....	4
<b>3.0 PROPOSED REMEDY</b> .....	4
<b>4.0 IRM OVERVIEW</b> .....	5
4.1 Project Planning and Coordination.....	7
4.1.1 Site Access Authorizations and Permits.....	7
4.1.2 Wetland Delineation and Permit Acquisition.....	8
4.1.3 Utility Location (Planning Phase).....	9
4.1.4 Pre-Construction Survey.....	9
4.1.5 Construction Plans and Specifications and Contractor Bidding.....	10
4.2 Mobilization and Site Preparation.....	10
4.2.1 Utility Clearance (Construction Phase).....	10
4.2.2 Construction Access, Staging Areas and Erosion and Sediment Control...10	
4.2.3 Clearing.....	10
4.3 Remedial Construction.....	11
4.3.1 Soil/Sediment Excavation.....	11
4.3.2 Water Management.....	11
4.3.3 Culvert Cleaning.....	12
4.3.4 Confirmation Sampling.....	12
4.3.5 Waste Characterization, Transportation, and Disposal.....	13
4.3.6 Site Restoration.....	13
4.3.7 Imported Fill Materials.....	13
4.3.8 Post-Remediation Survey.....	14
4.3.9 Construction Completion Report.....	14
<b>5.0 GENERAL SITE-SPECIFIC HEALTH AND SAFETY PLAN</b> .....	15
<b>6.0 COMMUNITY AIR MONITORING PROGRAM</b> .....	16
<b>7.0 QUALITY ASSURANCE/QUALITY CONTROL</b> .....	16
<b>8.0 ANTICIPATED REMEDIATION SCHEDULE</b> .....	16

## **FIGURES**

Figure 1: AOC-4 Location Plan

Figure 2: Tax Parcel Layout

Figure 3: BCP Area and AOCs-1,2,3 Location Plan

## **APPENDICES**

Appendix A: Figures from 2014 Remedial Alternatives Analysis Report (GHD)

Appendix B: 2017 Remedial Alternatives Analysis Report (GHD)

Appendix C: 2020 Wetlands Delineation Report (GHD)

Appendix D: Health and Safety Plan

Appendix E: Community Air Monitoring Plan

Appendix F: Quality Assurance Project Plan

# Interim Remedial Measure Work Plan – AOC-4, Celi Drive, BCP Site #C734108

## **1.0 INTRODUCTION**

### **1.1 Background and Purpose**

This Interim Remedial Measure Work Plan (IRMWP) has been prepared for GSP Holdings, Inc. to outline proposed remedial actions to be implemented to address remaining off-site contamination that exists in Area of Concern #4 (“AOC-4”) of the Celi Drive BCP Site (the “Site”). The Celi Drive BCP Site is associated with the former General Super Plating Co., Inc./GSP Holdings, Inc. facility located at 5762 Celi Drive in the Town of DeWitt, Onondaga County (the “GSP Facility”). The GSP Facility is situated on a +/- 1.45 acre tax parcel identified as Onondaga County Tax Parcel 053-02-17.2. This parcel is occupied by a +/- 47,098 square foot building that had been used as a metal plating facility from the mid-1970’s until these operations were ceased by GSP in 2015. All related equipment and contents were subsequently removed, and the Site has remained vacant since that time.

An accidental release of wastewater generated by metal-plating operations occurred at the GSP Facility on May 10, 2005. This release was subsequently investigated and found to have impacted soil, groundwater, and surface water at the GSP Facility, as well as soil/sediment and surface water within a series of adjacent and downgradient surface drainage features (swales, culverts, catch basins) associated with the Town of Dewitt Bridge Street Drainage District. To address contamination associated with the release, the Site was accepted into the New York State Department of Environmental Conservation (NYSDEC) Brownfield Cleanup Program (BCP) and GSP executed a Brownfield Cleanup Agreement (BCA) with the NYSDEC in January 2008. The Site is identified by NYSDEC Site No. C734108.

Based on the results of the initial investigation performed by Environmental Resources Management (ERM) in 2005, four (4) Areas of Concern (AOCs) were identified. These include:

- AOC-1: Impacted soil that was identified adjacent to and beneath the southeast corner of the manufacturing building on the site;
- AOC-2: Impacted soil/sediment present within a drainage swale located immediately east of the manufacturing building on the Celi Drive site. For purposes of the BCP, this swale is referred to as “the GSP swale”;
- AOC-3: Water and solids within a buried storm water culvert pipe and catch basins associated with the Town of Dewitt Bridge Street Drainage District. This culvert begins at the north end of the GSP swale (AOC #2) and discharges on the north side of Bridge Street;
- AOC-4: Impacted soil/sediment present within a drainage swale located north of Bridge Street.

Remedial activities have occurred at AOC-1, AOC-2, AOC-3, and a small section (southern extent) of the AOC-4 swale (see Figure 3 – Additional Areas of Concern, for the locations/extents of AOC-1, AOC-2, and AOC-3). However, the remedial work at AOC-1 and AOC-2 had been completed prior to NYSDEC’s approval of the associated IRMs, and the

## Interim Remedial Measure Work Plan – AOC-4, Celi Drive, BCP Site #C734108

remediated area included real property that is not part of the current BCP site. Construction Completion Reports for AOC-1 and AOC-2, as well as an amendment to include the additional real property into the BCP site, have been submitted to the NYSDEC and approval is pending. This IRMWP is intended to address the remaining portions of AOC-4 that have not yet been remediated.

### **1.2 AOC-4**

AOC-4 of the Site corresponds to a drainage swale (Bridge Street swale or AOC-4 swale) located north of Bridge Street. A portion of the Bridge Street swale is part of the Bridge Street Drainage District controlled and maintained by the Town of Dewitt. The Bridge Street swale was impacted by contaminants associated with the 2005 GSP wastewater release after the release entered a drainage ditch/swale, the release drained into the buried culvert located adjacent to and to the North of the GSP Facility (AOC-3), then conveyed via the AOC-3 culvert and discharged to the southern end of the AOC-4 swale at the north edge of Bridge Street.

The nature and extent of impacts to the Bridge Street swale were assessed during an initial investigation performed by ERM in 2005, and supplemental data gap sampling subsequently performed by ERM and GHD. The Contaminants of Concern (COC) identified in AOC-4 as a result of these investigation activities include chromium (total), chromium (hexavalent), copper (total), nickel (total), and cyanide (total). The extent of contamination within AOC-4 was evaluated and delineated with respect to concentrations that exceed (1) Unrestricted Soil Cleanup Objectives (SCOs) established in 6 NYCRR Part 375, and (2) Protection of Ecological Resources SCOs established in 6 NYCRR Part 375.

In 2014, an emergency remedial action was conducted to remove impacted soil/sediment and water from AOC-3 and the southern portion of AOC-4. This work was undertaken in connection with the development of the commercial properties at 5805 and 5821 Bridge Street (Tax Parcels 044-07-15.0 and 044-07-16.0, respectively). The section of the AOC-4 swale remediated during this work is depicted on attached Figures 1 and 2.

In 2017, a draft Remedial Alternatives Analysis (RAA) Report was prepared for the Site by GHD and submitted to the NYSDEC and the New York State Department of Health (NYSDOH) for review. The remedy proposed for AOC-4 is to excavate/remove impacted soil/sediment from the AOC-4 swale where contaminant concentrations exceed the Protection of Ecological Resources SCOs established in 6 NYCRR Part 375.

According to the draft RAA, approximately 2,800 linear feet of the AOC-4 swale will require remediation. The swale segments within AOC-4 that require remediation, and which will therefore be the subject of the work described herein, are depicted on attached Figures 1 and 2, and on the figures contained in Appendix A (excerpts from the GHD draft RAA Report).

Following completion of all planned IRMs, a revised RAA will be submitted to the NYSDEC/NYSDOH for approval. The RAA will identify the IRMs performed and approved by the Departments and address areas of AOC-4 that require remediation based upon current environmental conditions (if any). Since it has been determined that the Site constitutes a

## Interim Remedial Measure Work Plan – AOC-4, Celi Drive, BCP Site #C734108

Significant Threat to the environment and public health, the final remedy will be selected by the Departments, based upon information provided within the approved RAA.

### **2.0 REMEDIAL ACTION OBJECTIVES**

RAOs are development in accordance with appropriate, relevant, and applicable requirements. These requirements are known as standards, criteria, and guidance (SCGs), and include the NYSDEC Division of Environmental Remediation (DER) regulations and guidance documents, as well as regulations and guidance from other divisions within the NYSDEC, other State Agencies and Departments, and external agencies such as the U.S. Environmental Protection Agency (USEPA) and the Occupational Safety and Health Agency (OSHA).

The following Remedial Action Objectives are proposed for the AOC-4 IRM:

#### **2.1 Groundwater RAOs**

##### *RAOs for Public Health Protection*

- Prevent ingestion of groundwater with contaminant levels exceeding drinking water standards.
- Prevent contact with, or inhalation of volatiles, from contaminated groundwater.

##### *RAOs for Environmental Protection*

- Restore ground water aquifer to pre-disposal/pre-release conditions, to the extent practicable.
- Prevent the discharge of contaminants to groundwater
- Remove the source of ground water contamination.

#### **2.2 Soil RAOs**

##### *RAOs for Public Health Protection*

- Prevent ingestion/direct contact with contaminated soil.
- Prevent inhalation exposure to contaminants volatilizing from soil.

##### *RAOs for Environmental Protection*

- Prevent migration of contaminants that would result in (include all appropriate media: groundwater, surface water, or sediment) contamination.
- Prevent impacts to biota from ingestion/direct contact with soil causing toxicity or impacts from bioaccumulation through the terrestrial food chain.
- Remove the source of soil contamination.



# Interim Remedial Measure Work Plan – AOC-4, Celi Drive, BCP Site #C734108

## **2.3 Surface Water RAOs**

### *RAOs for Public Health Protection*

- Prevent ingestion of water impacted by contaminants.
- Prevent contact or inhalation of contaminants from impacted water bodies.
- Prevent surface water contamination which may result in fish advisories.

### *RAOs for Environmental Protection*

- Restore surface water to ambient water quality criteria for the Contaminants of Concern.
- Prevent impacts to biota from ingestion/direct contact with surface water causing toxicity and impacts from bioaccumulation through the marine or aquatic food chain.
- Remove the source of surface water contamination.

## **2.4 Sediment RAOs**

### *RAOs for Public Health Protection*

- Prevent direct contact with contaminated sediments.
- Prevent surface water contamination which may result in fish advisories.

### *RAOs for Environmental Protection*

- Prevent releases of contaminant(s) from sediments that would result in surface water levels in excess of (ambient water quality criteria).
- Prevent impacts to biota from ingestion/direct contact with sediments causing toxicity or impacts from bioaccumulation through the marine or aquatic food chain.
- Restore sediments to pre-release/background conditions to the extent feasible.
- Remove the source of sediment contamination.

## **3.0 PROPOSED REMEDY**

The current and anticipated future use of AOC-4 is as a drainage swale, including a limited number of culverts.

The proposed remedial approach identified as a result of the RAOs is to “*focus on soil/sediment and surface water contaminants and the potential exposures to humans and the environment through direct contact and/or ingestion and the potential migration of contaminants downstream*”. Toward that end, the draft RAA identified and compared two (2) potential remedial actions for AOC-4. These included:

- Restoration to pre-disposal conditions or Unrestricted SCOs (Alternative 1), and
- Restoration to Protection of Ecological Resources SCOs (Alternative 2)

## Interim Remedial Measure Work Plan – AOC-4, Celi Drive, BCP Site #C734108

The Alternatives were evaluated with respect to nine (9) criteria identified in 6 NYCRR Part 375-1.8(f), including:

- Compliance with SCGs
- Protection of human health and the environment
- Short-term impact and effectiveness
- Long-term impact and effectiveness
- Reduction of toxicity, mobility, or volume of contamination
- Implement-ability
- Cost effectiveness
- Land Use
- Community acceptance

The draft RAA report acknowledged that community acceptance would require further evaluation during public comment periods, but community acceptance is likely to be received since the selected remedial alternative should provide a tangible benefit to the local community by achieving RAOs consistent with the current and reasonably anticipated future use of AOC-4.

Based on the evaluation of the above criteria, Alternative 2 (restoration to Protection of Ecological Resources SCOs) was the proposed remedy selected for AOC-4. This serves as the basis for the work proposed herein.

### **4.0 IRM OVERVIEW**

The interim remedial measure proposed for AOC-r is to remove contaminated soil/sediment with the AOC-r swale to achieve Protection of Ecological Resources SCOs established in 6 NYCRR Part 375-6.6. Remedial processes similar to those described herein were previously employed in 2014 to address contaminated sediment located at the southern section of the AC-4 swale. This prior remediation was successful in achieving the Protection of Ecological Resources SCOs for that section of the swale.

The intent of the proposed interim remedial measure will be to remove contaminated soil/sediments, as necessary, to achieve Protection of Ecological Resources SCOs within the remaining contaminated portion of the AOC-4 swale, as delineated during previous investigation activities and identified in the draft RAA report. Copies of the figures from the draft RAA report that depict these portions of the swale are contained in Appendix A.

The interim remedial measure work will begin at the northern extent of the 2014 remediation area (southern, upstream portion of AOC-4), and encompass the remainder of the swale. The following are the key elements of the proposed interim remedial measures, in anticipated sequence of performance (items in “bold” will be provided to NYSDEC for review and approval prior to conducting the AOC-4 IRM):

- Meet with NYSDEC, local municipalities, public utilities and other stakeholder agencies.
- **Establish site access agreements with property owners**

## Interim Remedial Measure Work Plan – AOC-4, Celi Drive, BCP Site #C734108

- **Establish site access and use agreement with National Grid for access and use of their site as a staging and material handling location**
- **Obtain highway work permits (each contractor) from NYDOT for work within highway rights-of-way**
- **Coordinate and establish project requirements with the Town of Dewitt**
- **Establish need for additional delineation of wetlands and request jurisdictional determination from the US Army Corps of Engineers (USACOE)**
- **If applicable, submit Pre-Construction Notification (PCN) to USACOE for Nationwide Permit 38, which may include 401 Water Quality Certification from NYSDEC.**
- Complete location and mark-out of buried utilities throughout remediation site to avoid conflicts during remediation
- Complete pre-construction survey of remediation site
- Coordinate with prospective waste disposal facilities for project-derived wastes (soil/sediment, water)
- **Complete the preparation of construction documents (plans and specifications)**
- Review of construction documents by NYSDEC and NYSDOH
- Contractor bidding and selection
- Mobilization and Site Preparation
- Confirm the location and mark-out of buried utilities throughout remediation site.
- Construction of stabilized construction entrance and installation of erosion and sediment control measures
- Mobilization of equipment, frac tanks, etc.
- Clearing (if required)
- Remedial Construction
- Soil/sediment removal
- Water management, treatment, and disposal
- Culvert cleaning
- Confirmation Sampling
- Channel backfill/restoration
- Waste transportation and disposal
- Site restoration (including removal of Erosion and Sediment Control measures once vegetation has been established)
- Demobilization of equipment
- Project Closeout
- Post-remediation survey
- Preparation and submittal of Construction Completion Report

## Interim Remedial Measure Work Plan – AOC-4, Celi Drive, BCP Site #C734108

### 4.1 Project Planning and Coordination

#### 4.1.1 Site Access Authorizations and Permits

The drainage swale associated with AOC-4 extends through several privately-owned commercial parcels and extends into the New York State Department of Transportation Right-of-Way along NYS Route 690. A portion of the swale is also part of the Town of Dewitt Bridge Street Drainage District. As such, completion of the remediation work will require coordination with and establishment of access agreements with the associated landowners and agencies. Figure 2 depicts the layout of the swale with respect to existing property boundaries. The following table contains information relating to the affected properties for which access agreements will be required:

Address	Tax I.D.	Owner of Record*	Current Use	Current Zoning*
5841 Bridge Street	044-07-17.0	Graziano Zazzara & Graziano Zazzaro Jr. 334 S. Warren St., #202 Syracuse, New York 13202	Retail	Business (B)
Erie Boulevard	044-07-11.1	Steven Kravec 101 Halton Road Syracuse, NY 13224	Vacant Commercial	Business (B)
Electrical Substation -Bridge Street	053-01-03.1	National Grid 300 Erie Blvd West Syracuse, NY 13202	Electrical Substation	Business (B)
Bridge Street	053-01-01.1	Steven Kravec 101 Halton Road Syracuse, NY 13224	Vacant Commercial	Business (B)
Bridge Street	053-01-02.1	Champion Bridge St Properties 1992 Penfold Way Baldwinsville, NY 13027	Vacant Commercial	Business (B)
Electrical Substation – Bridge Street	007-01-01.1	National Grid 300 Erie Blvd West Syracuse, NY 13202	Electrical Substation	Business (B)
NYS 690 Right-of-Way	Not Applicable	NYS Department of Transportation	Highway Right-of-Way	Not applicable – Public Thoroughfare

\*Current ownership as listed in Onondaga County online real property records and the Syracuse-Onondaga County G.I.S. On The Web portal.

\*Current zoning as shown on Town of Dewitt Zoning Map (2008).

## Interim Remedial Measure Work Plan – AOC-4, Celi Drive, BCP Site #C734108

It is currently anticipated that the primary access to the remediation area will be through the National Grid parcels (Tax I.D. 007-01-01.1 and 053-01-03.1), and that associated equipment and material handling and staging will primarily occur proximal to the swale on the eastern portion of the 053-01-03.1 parcel. We understand that National Grid has indicated a willingness to provide such access during prior discussions with the current property owner; however, a formal site access and use agreement has not yet been established. Additional coordination with National grid and establishment of a formal site access and use agreement will be conducted prior to completing the construction plans and specifications and prior to undertaking the remediation activities.

In addition to the above, portions of the work will occur within the NYSDOT right-of-way adjacent to and along the east-bound off-ramp from NYS Route 690 to Bridge Street. Completion of work within the right-of-way will require that highway work permits be obtained from NYSDOT. It is expected that each firm/contractor performing work within the right-of-way will be required to obtain a permit from NYSDOT for their respective activities. Coordination of these permits will occur during the project planning phase.

As the swale is associated with the Town of Dewitt Bridge Street Drainage District, the proposed work will also be coordinated with the Town, to inform of the planned work and to identify any specific channel restoration requirements that may be requested by the Town.

### 4.1.2 Wetland Delineation and Permit Acquisition

Much of the area along the swale is identified on the NYSDEC Environmental Resource Mapper database as either “State-regulated freshwater wetland” or “State-regulated wetland check zone”. Additionally, the area north of the NYS Route 690 east-bound off-ramp to Bridge Street (at northeastern extent of remediation) is identified on the National Wetland Inventory as being Freshwater Emergent Wetland. Printouts from the Resource Mapper that depict the approximate boundaries of each wetland area are attached as Figures 3 (NYSDEC freshwater wetlands) and 4 (National Wetland Inventory wetlands).

In June 2020 GHD completed the “Wetland Delineation Report” for the project site (Appendix C) which provided a definitive identification of the various wetlands present at the site. As such, this report appears to provide sufficient information which will eliminate the necessity for a new delineation report for the entire site. As described in more detail below, it may be necessary to complete some additional tasks to satisfy both or either the NYSDEC and the United States Army Corps of Engineers (USACOE) in pursuing the required permits.

The Environmental Resource Mapper database is intended to show the approximate location of wetlands and does not depict precise wetland boundaries. A field delineation to accurately locate wetland boundaries is required prior to conducting activities that may impact or disturb wetland resources. As such, a field delineation may be needed to be performed by a wetland scientist before beginning remediation. Both the USACOE and NYSDEC will be contacted to establish the level and necessity for completing additional delineations at the site. Prior to the delineation, the NYSDEC Region 7 Biologist will be contacted to allow for an opportunity to assist in the delineation. The field delineation will encompass all areas (as needed) that will be

## Interim Remedial Measure Work Plan – AOC-4, Celi Drive, BCP Site #C734108

impacted by the remediation activities (i.e., swale channel, banks, and peripheral areas; routes of access/egress; equipment and material handling and staging areas). Following completion of the delineation, a request will be submitted to the USACOE and the NYSDEC to obtain an Approved Jurisdictional Determination from each agency. This will serve to determine whether the wetlands, if present, fall under the jurisdiction of the Clean Water Act and/or the New York State Freshwater Wetlands Act, and will therefore be subject to permitting requirements by either or both agencies.

It is anticipated that a NYSDEC wetland permit will not be required for the proposed remediation, as remedial projects are exempt from the requirement to obtain NYSDEC-issued permits (subject to certain conditions) under 6 NYCRR Part 375. This exemption, however, does not obviate the need for obtaining federal permits, if applicable. Therefore, in the event that wetlands under federal jurisdiction are identified and confirmed to be present as a result of the Jurisdictional Determination, and the planned work will impact such wetlands, a permit under Section 404 of the Clean Water Act will likely be required. Given the nature of the planned work, it is expected that the activities may be eligible for coverage under Nationwide Permit 38 (*Cleanup of Hazardous and Toxic Waste*). Coverage under Nationwide Permit 38, if applicable, may also likely require a 401 Water Quality Certification to be issued by NYSDEC, if a blanket Water Quality Certification has not been issued.

The wetland delineation, Approved Jurisdictional Determinations, agency coordination, and any required permit acquisition or notification will occur prior to the start of the remediation activities.

### 4.1.3 Utility Location (Planning Phase)

During the project planning phase, Dig Safely New York, will be notified (in the form of a “survey and design request”) to request a markout of all utilities within the remediation site that are registered with that organization. Additionally, a third-party independent utility locator will be retained to search for and verify the nature and location of any additional buried utilities that may exist within the remediation site. These mark-outs will serve to identify the nature and location of any buried site utilities, so that any impacts on the proposed remediation scope and methods may be addressed in the project planning phase. The marked locations will be recorded during the pre-construction survey described below.

### 4.1.4 Pre-construction Survey

A pre-construction survey will be performed to establish the locations of pertinent site features (swale channel, culverts, marked utilities), pre-work topographic conditions, pre-work channel geometry (depth, width), wetland delineation boundaries (if applicable), and reference stations and elevation reference benchmarks for use during excavation activities. The survey will encompass the swale channel and adjacent area (approximately 25 feet on either side of channel), the planned route of access (anticipated to be via National grid parcel) and expected staging and lay-down areas.

## Interim Remedial Measure Work Plan – AOC-4, Celi Drive, BCP Site #C734108

### 4.1.5 Construction Plans and Specifications and Contractor Bidding

Construction plans and specifications will be prepared to reflect the information developed during the project planning phase and the specific requirements for executing the provisions of this Work Plan. These documents will be submitted to NYSDEC and NYSDOH for review, comment, and approval. Once approved by NYSDEC and NYSDOH, these documents will serve as the basis for obtaining bids from qualified remediation contractor(s) for execution of the work.

## **4.2 Mobilization and Site Preparation**

### 4.2.1 Utility Clearance (Construction Phase)

Prior to initiating intrusive site work associated with the remediation, the remediation contractor(s) will be required to notify Dig Safely New York to request a current mark-out of all utilities within the remediation site that are registered with that organization. Similarly and if required the third party independent locator will also provide a current mark-out.

### 4.2.2 Construction Access, Staging Areas, and Erosion and Sediment Control

As previously indicated, it is presently anticipated that primary access to the remediation site will occur thorough the National grid parcel (subject to execution of a site access and use agreement). A stabilized construction entrance will be installed to minimize impact to and disturbance of native soil and facilitate access to on-site staging areas by trucks, solid waste receptacles, frac tanks, and other equipment. Additionally, erosion and sediment control measures will be installed to mitigate transport of sediment from the work activities. The site-specific plan and/or specifications prepared for erosion and sediment control will be submitted to NYSDE for review and approval, prior to finalization and use. Once approved, the construction entrance and erosion and sediment control measures will be installed in general conformance with the specifications contained in the New York State Standards and Specifications for Erosion and Sediment Control (NYSDEC, November 2016). These measures will remain in place until such time as final site restoration is complete and suitable vegetation has been established in the disturbed areas.

### 4.2.3 Clearing

Based on existing conditions, it is not anticipated that extensive clearing will be required to execute the remediation work. However, limited and isolated clearance of vegetation may be necessary to facilitate the work. The need for such clearing will be reviewed during the project planning phase, and, if necessary, will be discussed with the affected property owners. If necessary and acceptable to the respective property owners, the clearing provisions will be incorporated into the property access agreements.

## Interim Remedial Measure Work Plan – AOC-4, Celi Drive, BCP Site #C734108

### **4.3 Remedial Construction**

#### 4.3.1 Soil/Sediment Excavation

The remediation will begin at the northern edge of the 2014 emergency remediation area (west side of 5841 Bridge Street parcel, Tax Parcel 044-07-17) and will progress northward along the course of the swale (i.e., downstream) to the northern, northeastern, and northwestern limits defined by the previous investigations (see Figures 1 and 2, and draft RAA report figures contained in Appendix A). For this work, sections of the swale will be isolated with temporary cofferdams (placed upstream and downstream of the isolated section) to allow management of water, mitigate re-introduction of contaminants from downstream areas, and advance the remediation from upstream to downstream in a controlled manner. The size of each isolated section will be based upon field conditions and will be determined at the time of the work. Following placement of the upstream and downstream cofferdams, the target section of swale will be dewatered, soil/sediment will be excavated, and verification sampling will be performed.

The data collected during the previous investigations and the conditions encountered during the 2014 emergency remedial action conducted just upstream of the work proposed herein suggest that removal of approximately 1 to 2 feet of soil/sediment from the bottom and walls of the swale would achieve Protection of Ecological Resources SCOs. Initially, approximately 12 inches of soil/sediment will be removed along the isolated, dewatered section of swale. Initial verification sampling, for the constituents set forth in section 4.3.4 below, will be performed to determine whether Protection of Ecological Resources SCOs have been achieved. If initial verification sampling identifies locations where concentrations of contaminants remain above Protection of Ecological Resources SCOs, additional excavation will be performed in those areas until the Protection of Ecological Resources SCOs are achieved. Once the SCOs are achieved, the section of swale will be backfilled (if deemed necessary or required by USACOE, NYSDEC, Town of Dewitt) and excavation activities will progress to the next downstream section of swale.

The excavated soil/sediment will be transferred to an on-site dewatering containment (refer to section 4.3.2 below).

#### 4.3.2 Water Management

Management of surface water will be necessary during the work to limit sediment and contaminant suspension and downstream transport, limit re-introduction of suspended contaminants into excavated areas from downstream water, limit dispersion of contaminants to uncontaminated soil during handling and on-site transport of excavated sediments, and reduce moisture content in excavation spoils to allow over-the-road transport and disposal at a permitted waste disposal facility. Surface water within the channel will be managed by isolating distinct sections of the swale with temporary cofferdams and evacuating existing surface water to frac tanks to be staged on-site for storage and settling prior to treatment/disposal of the water as required.

Consistent with the dewatering methods used during the 2014 emergency remediation, excavated soil and sediment will be placed in a dewatering containment. The dewatering



## Interim Remedial Measure Work Plan – AOC-4, Celi Drive, BCP Site #C734108

containment will be constructed by placing earthen berms to form a perimeter, and lining the interior of the bermed area with two layers of fiber-reinforced polyethylene sheeting. A layer of medium to fine gravel will be placed over the sheeting, and non-woven geotextile will be placed over the gravel bedding. Excavation spoils will be placed onto the surface of the geotextile layer and allowed to drain into the underlying gravel layer. The polyethylene liner will be sloped to promote drainage within the gravel layer to a collection sump installed at the downgradient end of the containment. Water collected in the sump will be transferred to the on-site frac tanks for proper treatment/disposal as required. Once sufficiently dewatered, the soil/sediment will be staged on-site (either in lined roll-off containers or in a polyethylene-lined staging cell) and sampled for the pre-disposal waste characterization requirement of the selected waste disposal facility.

The locations of the soil/sediment dewatering containment areas will be depicted on drawings submitted as part of the Construction Documents (see Section 4.1.5).

Potential treatment/disposal options for the collected water will be evaluated during the project planning phase.

### 4.3.3 Culvert Cleaning

Three (3) existing culverts are located along the course of the swale, and a fourth extends beneath the NYS Route 690 east-bound off-ramp to Bridge Street at the northern edge of AOC-4. These culverts will be cleaned of sediment as the remediation progresses along the route of the swale. The sediments will be flushed by jetting each culvert with high-pressure water. Water used to flush the culverts will be captured at the discharge of the culvert and pumped to the frac tanks for management with the evacuated swale water. The flushed sediments will be removed concurrent with the soil/sediment at the discharge end of the culvert, or, if suspended and transferred with the jetting water, captured in the frac tank.

### 4.3.4 Confirmation Sampling

Confirmation sampling will be conducted pursuant to the Quality Assurance Project Plan (QAPP) included as Appendix F. Sampling will be performed as the soil/sediment removal progresses along the route of the swale. Samples will be collected at transects positioned at fifty (50) feet intervals along the route of the swale. Three (3) grab samples will be collected across the swale profile (one at bottom of channel and one from each bank/sidewall) at each transect location after the initial +/- 12 inches of soil/sediment is excavated. The three (3) samples will be composited to form a single sample representative of the conditions at the given transect location.

These samples will be subjected to laboratory analysis for total chromium, hexavalent chromium, total copper, total nickel, and total cyanide. The analysis results will be compared to the Protection of Ecological Resources SCOs for each compound. If any compound concentration remains above the respective SCO, additional excavation will be performed within that section of swale. Additional excavation, if necessary, will advance in approximately 6 inch depth increments, with additional confirmation sampling at each increment. This

## Interim Remedial Measure Work Plan – AOC-4, Celi Drive, BCP Site #C734108

iterative process will continue until such time as the concentrations of the target contaminants no longer exceed the Protection of Ecological Resources SCOs.

### 4.3.5 Waste Characterization, Transportation, and Disposal

All project-generated waste streams will be transported under applicable bills-of-lading/manifest by appropriately permitted waste haulers, and disposed of at appropriately permitted waste disposal facilities. Pre-disposal characterization will be performed for each waste stream as required by the respective disposal facility. The results of pre-disposal characterization analyses, copies of waste manifests/bills of lading (as applicable), disposal facility receipts will be incorporated into the Construction Completion Report for the project.

### 4.3.6 Site Restoration

The specific scope of site restoration and decisions as to whether the excavated channel will be backfilled will be determined during the planning process, and will reflect input from the Town of Dewitt, the NYSDEC and/or conditions of the USACOE permit, if required. It is expected that the restoration work will include, at a minimum, backfilling as required, grading, seeding, and mulching of all areas of surface disturbance; maintenance of erosion and sediment control measures until suitable vegetation growth has been established to stabilize disturbed soil; and removal of erosion and sediment control measures following establishment of new vegetation. The final restoration plan will be incorporated into the construction design documents.

### 4.3.7 Imported Fill Materials

Fill materials from off-site sources are expected to be required to construct the stabilized construction entrance, backfill/restore the channel bottom (if deemed necessary or required by USACOE, NYSDEC, or Town of Dewitt), restore the vegetative surface disturbed by construction traffic along the route of the channel, and restore disturbance at the equipment and material handling and staging area(s). These materials may consist of soil-based materials, and/or non-soil materials (i.e., virgin stone material).

Soil materials will be sampled and analyzed prior to arrival at the site, to verify that the materials meet the chemical analysis requirements set forth in NYSDEC's *Technical Guidance for Site Investigation and Remediation (DER-10)*, dated May 3, 2010, as amended, and the criteria for emerging contaminants (Per- and Polyfluoroalkyl Substances and 1,3-Dioxane), in accordance with NYSDEC's *Guidelines for Sampling and Analysis for PFAS Under NYSDEC's Part 375 Remedial Programs*, dated June 2021 (NYSDEC 2021 PFAS Guidelines). Sampling type and frequency will be based on the quantity of material to be imported, as established in DER-10, as follows:

Contaminant	VOCs		SVOCs, Inorganics & PCBs/Pesticides	
	Discrete Samples	Composite Samples	Discrete Samples/Composite	
0-50	1	1	3-5 discrete samples from different locations in the fill being provided will comprise a	
50-100	2	1		

## Interim Remedial Measure Work Plan – AOC-4, Celi Drive, BCP Site #C734108

100-200	3	1	composite sample for analysis.
200-300	4	1	
300-400	4	2	
400-500	5	2	
500-800	6	2	
800-1000	7	2	
>1000	Add an additional 2 VOC and 1 composite for each additional 1000 cubic yards		

The chemical characterization samples will be analyzed for the specific metals, semi-volatile organic compounds, volatile organic compounds, PCBs, and pesticides listed in Appendix 5 of DER-10. The samples shall also be analyzed for emerging contaminants (Per- and Polyfluoroalkyl Substances and 1,4-Dioxane), in accordance with NYSDEC 2021 PFAS Guidelines. The analysis results shall indicate that all analyte concentrations are below the Allowable Constituent Levels for Imported Fill or Soil for Protection of Ecological Resources established in Appendix 5 of DER-10, and below the soil criteria for emerging contaminants established in the NYSDEC 2021 PFAS Guidelines.

Non-soil fill materials meeting the conditions set forth in Section 5.4(e)5 of DER-10 (gravel, rock, or stone, consisting of virgin material from a permitted mine or quarry, and containing less than 10% by weight of material passing a size 80 sieve) will be exempt from the chemical analysis requirements.

Ann analysis results and non-soil fill source documentation will be submitted to NYSDEC for review and acceptance prior to selection of the material for on-site use.

### 4.3.8 Post-Remediation Survey

A post-remediation survey will be performed to establish final site topography, post-excavation channel geometry (depth, width), sample transect locations, and other relevant post-remediation conditions.

### 4.3.9 Construction Completion Report

Following completion of the work and receipt of all waste disposal documentation, a Construction Completion Report will be prepared and submitted to NYSDEC and NYSDOH for review. The Construction Completion Report will be prepared in accordance with the guidance contained in the NYSDEC's *Program Policy DER-10, Technical Guidance for Site Investigation and Remediation*, dated May 3, 2010 (DER-10), and any applicable updates. As consistent with the guidance contained in DER-10, the Construction Completion Report will document the work completed at the site and all supporting data and documentation. The Construction Completion Report will also contain a certification by a NYS Licensed Professional Engineer that the work was completed in accordance with the NYSDEC-approved Work Plan(s) and construction design documents, and provide detail of any necessary field modifications to the scope that were approved by NYSDEC, if applicable.

## Interim Remedial Measure Work Plan – AOC-4, Celi Drive, BCP Site #C734108

The Construction Completion Report will contain:

- A description of completed work, as constructed, pursuant to the NYSDEC-approved Work Plan(s) and construction design documents;
- A description of any problems or field conditions encountered during the work and a description of their resolution;
- A description of any changes to the tasks outlined in the Work Plan, as approved in advance by NYSDEC, and why the changes were necessary;
- Laboratory analysis reports (refer to Appendix F – QAPP, Section 6.2.2 for reporting details) and associated sample custody documentation for confirmation samples and waste characterization samples;
- A Data Usability Summary Report (DUSR) for all confirmation samples;
- Identification and quantities of all waste streams (soil, water, PPE) generated in the course of the work, and documentation of the means of transport and location of disposal for each;
- Copies of waste manifests/Bills of Lading (as applicable), and disposal facility receipt documentation (i.e., “tipping receipts”);
- Laboratory analysis data (refer to Appendix F – QAPP, Section 6.2.2 for reporting details) relating to testing of imported fill material, per the requirements of DER-10;
- Data recorded during real-time monitoring of particulate/dust levels under the Community Air Monitoring Program;
- As-built/Record Drawings showing extent of soil removals, sample collection points, and details relating to site work, bearing a NYS Licensed Professional Engineer stamp and signature.

### **5.0 GENERAL SITE-SPECIFIC HEALTH AND SAFETY PLAN**

A general Site-Specific Health and Safety Plan (SSHASP) sets forth requirements for maintaining the health and safety of persons at the Site. The SSHASP addresses general health and safety issues related to the presence of specific chemical and physical hazards that may be encountered during performance of the work activities at the Site. The SSHASP includes an Emergency Response Plan, which presents the procedures to be followed in the event of an emergency situation.

The general SSHASO for the remediation work is presented as Appendix D. The selected remediation contractor(s) will be required to provide a Contractor Site-Specific Health and Safety Plan (CSSHASP) that applies to their personnel and accounts for specific hazards that may be associated with the means and methods of the work to be completed by the respective contractor. At a minimum, the CSSHASP must incorporate the provisions of the general SSHASP and meet applicable requirements of the United States Occupational Health and Safety Administration (OSHA).

## **6.0 COMMUNITY AIR MONITORING PROGRAM**

The intent of the CAMP is to provide a measure of protection for the downwind community (i.e., off-site receptors including residences and businesses and on-site workers not directly involved with the subject work activities) from potential airborne contaminant releases as a direct result of investigative and remedial work activities. Additionally, the CAMP helps to confirm that work activities did not spread contamination off-site through the air. Exceedance of the action levels specified within the Plan requires increased monitoring, corrective actions to abate emissions, and/or work shutdown.

The site-specific CAMP, prepared in accordance with Appendix 1A of DER-10, is presented as Appendix E.

## **7.0 QUALITY ASSURANCE/QUALITY CONTROL**

A Quality Assurance Project Plan (QAPP) describes the manner in which quality assurance/quality control (QA/QC) procedures will be implemented during the RA activities to assure the accuracy and precision of the data collection. Guidance for the selection of QAPP objectives was obtained from NYSDEC's *DER-10 Technical Guidance for Site Investigation and Remediation* (May 2010).

Quality Assurance (QA) refers to the conduct of all planned and systematic actions necessary to perform satisfactorily all task-specific activities and to provide information and data confidence as a result of such activities. The QA for task-specific activities includes the development of procedures, auditing, monitoring, and surveillance of the performance.

Quality Control (QC) refers to the activity performed to determine if the work activities conform to the requirements. This includes activities such as inspections of the work activities in the field. QA is an overview monitoring of the performance of QC facilities through audits rather than first time inspections.

The project specific QAPP is presented as Appendix F.

## **8.0 ANTICIPATED REMEDIATION SCHEDULE**

The project schedule will be contingent upon several factors, including, but not limited to the transfer of ownership/title, transfer of the BCA, execution of site access agreements with affected landowners, procurement of environmental permits related to wetlands, and procurement of a highway work permit from NYSDOT. These critical path items are discussed in more detail in the following paragraphs. Given the aquatic nature of the work, it is advantageous to perform this work during the summer to minimize the challenges associated with higher precipitation seasons.

There are several distinct property owners who will be affected by the remediation activities from whom access agreements will need to be obtained. This activity is anticipated to require over a month to complete.

## Interim Remedial Measure Work Plan – AOC-4, Celi Drive, BCP Site #C734108

The project is located in an area with both state and federal wetlands and the remediation effort will involve work within an aquatic environment. Therefore, as part of the planning steps for the IRM, a wetland delineation will need to be performed and permits obtained for the work in both the wetlands and the associated drainage areas. USACE and NYSDEC wetland personnel will be consulted during the development of the project design to find ways to minimize the wetland impacts and define restoration requirements for the project. Seasonal limitations associated with performing wetland delineation and obtaining regulatory review of the delineation areas necessitates delaying this work until early spring.

Portions of the project will involve work within the NYSDOT right-of-way and will, in one instance require work from the roadway. Therefore, a highway use permit will also be required from NYSDOT.

DEC Approval of IRM Work Plan.....	Month 0
Procure Access Agreements from Property Owners.....	Month 1-2
Procure Highway Work Permit from NYSDOT.....	Month 1-2
Conduct Additional Wetland Delineation as Needed.....	Month 2-3
Submit Environmental Easement Package.....	Month 3-4
Submit Environmental Permit Applications.....	Month 3-4
Finalize Construction Plans.....	Month 5-6
Receive Permits.....	Month 6
<b>Submit Executed Environmental Easement Package.....</b>	<b>Month 6-7</b>
Procure Remediation Contractor.....	Month 7
Submit Fact Sheet Announcing Start of Construction.....	Month 7
<b>Begin Construction/Remediation.....</b>	<b>Month 7-8</b>
Complete Remediation (Excavation, restoration).....	Month 8
Submit Construction Completion Report to NYSDEC.....	Month 9
DEC/DOH Review of Draft Site Management Plan.....	Month 10
<b>Submit Site Management Plan.....</b>	<b>Month 11</b>
DEC/DOH Review of Draft Final Engineering Report.....	Month 12
<b>Submit Final Engineering Report.....</b>	<b>Month 13</b>



32 CLINTON STREET,  
HOMER, NY 13077  
(607) 423-3595  
kteter@twcny.rr.com

**AOC – 4 IRM Work Plan**  
Celi Drive BCP, #4  
BCP Site # C734108  
Town of Dewitt, Onondaga County, New York



DRAWING TITLE:  
Area to be Remediated

PROJECT NO.:	222028A
SCALE:	AS SHOWN
DRAWN BY:	JAM
REVIEWED BY:	FCE
DATE:	DECEMBER 2022

DRAWING NO.  
**1**



Google



**LEGEND:**

- SWALE AREA TO BE REMEDIATED
- APPROXIMATE CULVERT LOCATION
- SECTION OF AOC-4 SWALE PREVIOUSLY REMEDIATED (2014)



32 CLINTON STREET,  
HOMER, NY 13077  
(607) 423-3595  
kteter@twcnny.com




**AOC - 4 IRM Work Plan**

Celi Drive BCP, #4  
BCP Site # C734108  
Town of Dewitt, Onondaga County, New York

DRAWING TITLE:  
Tax Parcel Layout

PROJECT NO.:	222028A
SCALE:	AS SHOWN
DRAWN BY:	JAM
REVIEWED BY:	FCE
DATE:	DECEMBER 2022

DRAWING NO.  
2



**LEGEND:**

	PARCEL AFFECTED BY WORK (SITE ACCESS AGREEMENTS REQUIRED)		SWALE AREA TO BE REMEDIATED
	APPROXIMATE PROPERTY LINE		APPROXIMATE CULVERT LOCATION
			SECTION OF AOC-4 SWALE PREVIOUSLY REMEDIATED (2014)






32 CLINTON STREET,  
 HOMER, NY 13077  
 (607) 423-3595  
 kteter@twcny.rr.com

**AOC – 4 IRM Work Plan**  
 Celi Drive BCP, #4  
 BCP Site # C734108  
 Town of Dewitt, Onondaga County, New York

DRAWING TITLE:  
 BCP Area and AOC's – 1,2,3  
 Location Plan

PROJECT NO.:	222028A
SCALE:	AS SHOWN
DRAWN BY:	JAM
REVIEWED BY:	FCE
DATE:	DECEMBER 2022

DRAWING NO.  
**3**



AOC-3 BURIED  
 CULVERT PIPE


CURRENT BCP  
 AREA

AOC-1  
 SUB-SLAB SOIL

SITE PROPERTY  
 BOUNDARY

AOC-2 G5P SWALE

Google



*APPENDIX A*

*Figures From 2014 Remedial Alternative Analysis Report  
Prepared by GHD*



LEI END

- Source Identification Investigation Sample Locations (E: M, 2) (1)
- ▲ Data Acquisition Investigation Soil Boring Location (E: M, 2) (1)
- ▨ Area of Utility Excavation (1' to 1' to Meet Protection of Ecological Resources SCOs (Approximate))
- ▨ Area of Utility Excavation (1' to 2' to Meet Protection of Ecological Resources SCOs (Approximate))

NOTES:  
 1) Base map and sample locations taken from the Data Acquisition Investigation Report (E: M, June 2) (12)

SCALE 1" = 100' AT ORIGINAL SIZE

GSP Holdings, Inc.  
 Cell Drive BCP Site (BCP Site #C734108)  
 Remedial Alternatives Analysis  
 Area of Remediation to Meet Protection of Eco. Resources SCOs in AOC-4

One Remington Park Drive  
 Cazenovia NY 13035 USA  
 T 1 315 679 5800 F 1 315 679 5801  
 E cazmail@ghd.com W www.ghd.com

Job Number | 37-11082  
 Revision | A  
 Date | 06.06.2014 **Figure 7-4a**



LEGEND

- Source Identification Investigation Sample Locations (EIM, 2010)
- ▲ Data Point Investigation Soil Boring Location (EIM, 2010)
- ▨ Area of Excavation (0' to 2' to Meet Protection of Ecological Resources SCOs (Approximate))



NOTES  
 1. Base map and sample locations taken from the Data Point Investigation Report (EIM, June 2012)



GSP Holdings, Inc.  
 Celi Drive BCP Site (BCP Site #C734108)  
 Remedial Alternatives Analysis  
 Area of Remediation to Meet Protection  
 of Eco. Resources SCOs in AOC-4

Job Number | 37-11082  
 Revision | A  
 Date | 06.06.2014

Figure 7-4b

*APPENDIX B*

*2014 Remedial Alternative Analysis Report  
Prepared by GHD*



GSP Holdings, Inc.  
Celi Drive BCP Site (BCP Site #C734108)  
Remedial Alternatives Analysis

September 2017

# Table of Contents

1.	Introduction.....	1
1.1	Site Description.....	1
1.2	Purpose.....	2
1.3	Scope and Limitations.....	2
1.4	Assumptions .....	3
2.	Summary of Previous Investigations.....	4
2.1	Comprehensive Site Investigation Report .....	4
2.1.1	Response to the Release .....	4
2.1.2	Site Investigation Sampling .....	5
2.1.3	Site Investigation Results .....	7
2.1.4	Summary and Recommendations .....	11
2.2	Data Gap Investigation Report .....	11
2.2.1	AOC-1 – Sub-Slab Area.....	11
2.2.2	AOC-2 – GSP Swale.....	12
2.2.3	AOC-3 – Buried Culvert Pipe.....	12
2.2.4	AOC-4 – Bridge Street Swale .....	13
2.2.5	Groundwater .....	13
2.3	Bridge Street Swale Dredging .....	14
2.4	Background Sediment Sampling .....	15
2.5	Groundwater Sampling 2014.....	16
2.6	Construction Completion Report.....	17
2.7	Supplemental Sampling Activities.....	18
2.7.1	Groundwater .....	18
2.7.2	Soil/Sediment.....	19
2.8	Summary of Remaining Contamination .....	20
2.9	Fish and Wildlife Resources Impact Analysis .....	23
2.10	Qualitative Human Health Exposure Assessment.....	24
3.	Remedial Goals and Remedial Action Objectives .....	25
3.1	Overview .....	25
3.2	AOC-1 .....	25
3.3	AOC-2.....	26
3.4	AOC-3.....	28
3.5	AOC-4.....	30
4.	AOC-1 .....	32
4.1	Remedial Alternatives Analysis .....	32
4.1.1	Restoration to Pre-Disposal or Unrestricted Conditions Alternative.....	32
4.1.2	Commercial Uses with Site Management Alternative.....	33
4.2	Evaluation of Remedial Alternatives .....	35

4.2.1	Compliance with Standards, Criteria, and Guidance.....	35
4.2.2	Protection of Human Health and the Environment .....	36
4.2.3	Short-Term Effectiveness .....	36
4.2.4	Long-Term Effectiveness and Performance .....	37
4.2.5	Reduction of Toxicity, Mobility, and Volume.....	37
4.2.6	Implementability .....	37
4.2.7	Costs.....	37
4.2.8	Land Use.....	38
4.2.9	Community Acceptance.....	38
5.	AOC-2 .....	39
5.1	Remedial Alternatives Analysis .....	39
5.1.1	Restoration to Pre-Disposal or Unrestricted Conditions Alternative.....	40
5.1.2	Restoration to Commercial Uses with Site Management Alternative .....	41
5.2	Evaluation of Remedial Alternatives .....	43
5.2.1	Compliance with Standards, Criteria, and Guidance.....	43
5.2.2	Protection of Human Health and the Environment .....	44
5.2.3	Short-Term Effectiveness .....	44
5.2.4	Long-Term Effectiveness and Performance .....	45
5.2.5	Reduction of Toxicity, Mobility, and Volume.....	45
5.2.6	Implementability .....	45
5.2.7	Costs.....	46
5.2.8	Land Use.....	46
5.2.9	Community Acceptance.....	46
6.	AOC-3 .....	48
6.1	Remedial Alternatives Analysis .....	48
6.1.1	Restoration to Pre-Disposal or Unrestricted Conditions Alternative.....	49
6.1.2	No Further Action Alternative.....	50
6.2	Evaluation of Remedial Alternatives .....	50
6.2.1	Compliance with Standards, Criteria, and Guidance.....	51
6.2.2	Protection of Human Health and the Environment .....	51
6.2.3	Short-Term Effectiveness .....	51
6.2.4	Long-Term Effectiveness and Performance .....	52
6.2.5	Reduction of Toxicity, Mobility, and Volume.....	52
6.2.6	Implementability .....	52
6.2.7	Costs.....	52
6.2.8	Land Use.....	53
6.2.9	Community Acceptance.....	53
7.	AOC-4 .....	54
7.1	Remedial Alternatives Analysis .....	54
7.1.1	Restoration to Pre-Disposal or Unrestricted Conditions Alternative.....	55
7.1.2	Restoration to Protection of Ecological Resources Conditions Alternative .....	56
7.2	Evaluation of Remedial Alternatives .....	57
7.2.1	Compliance with Standards, Criteria, and Guidance.....	58
7.2.2	Protection of Human Health and the Environment .....	58
7.2.3	Short-Term Effectiveness .....	58
7.2.4	Long-Term Effectiveness and Performance .....	59
7.2.5	Reduction of Toxicity, Mobility, and Volume.....	59
7.2.6	Implementability .....	59
7.2.7	Costs.....	59
7.2.8	Land Use.....	60



7.2.9	Community Acceptance .....	60
8.	Selected Remedy.....	61
8.1	AOC-1 .....	61
8.2	AOC-2 .....	61
8.3	AOC-3 .....	62
8.4	AOC-4 .....	62
8.5	Future BCP Site Activities.....	63

## Figure Index

Figure 1-1	– Property Location Map
Figure 1-2	– Site Layout
Figure 4-1	– Exceedances of Unrestricted Use SCOs in AOC-1
Figure 4-2	– Exceedances of Commercial Use SCOs in AOC-1
Figure 5-1	– Exceedances of Unrestricted Use SCOs in AOC-2
Figure 5-2	– Area of Remediation to Meet Unrestricted Use SCOs in AOC-2
Figure 5-3	– Exceedances of Commercial Use SCOs in AOC-2
Figure 5-4	– Area of Remediation to Meet Commercial Use SCOs in AOC-2
Figure 5-5	– Exceedances of SCOs Remaining Below Upper Foot in AOC-2
Figure 6-1	– Exceedances of Unrestricted Use SCOs in AOC-3
Figure 7-1a	– Exceedances of Unrestricted Use SCOs in AOC-4
Figure 7-1b	– Exceedances of Unrestricted Use SCOs in AOC-4
Figure 7-2a	– Area of Remediation to Meet Unrestricted Use SCOs in AOC-4
Figure 7-2b	– Area of Remediation to Meet Unrestricted Use SCOs in AOC-4
Figure 7-3a	– Exceedances of Protection of Eco. Resources SCOs in AOC-4
Figure 7-3b	– Exceedances of Protection of Eco. Resources SCOs in AOC-4
Figure 7-4a	– Area of Remediation to Meet Protection of Eco. Resources SCOs in AOC-4
Figure 7-4b	– Area of Remediation to Meet Protection of Eco. Resources SCOs in AOC-4

## Table Index

Table 4-1	– Alternative Analysis Preliminary Estimates of Cost for AOC-1
Table 5-1	– Alternative Analysis Preliminary Estimates of Cost for AOC-2
Table 6-1	– Alternative Analysis Preliminary Estimates of Cost for AOC-3
Table 7-1	– Alternative Analysis Preliminary Estimates of Cost for AOC-4

# Attachments

Attachment A – Tax Map

Attachment B – Excerpts from Previous Investigation Reports

Attachment B-1 – Comprehensive Site Investigation Report, ERM, November 2005

Attachment B-2 – Data Gap Investigation Report, ERM, June 2012

Attachment B-3 – Work Plan to Address Areas of Concern 1, 2, & 3, ERM, November 2012

Attachment B-4 – Monthly Progress Report – October 2012, ERM, November 9, 2012

Attachment B-5 – Emergency Remedial Work Plan, GHD, June 2013

Attachment B-6 – Background Sediment Sampling Letter Report, GHD, October 2013

Attachment B-7 – Groundwater Sampling Letter Report, GHD, April 16, 2014

Attachment B-8 – Construction Completion Report – AOC-3 and AOC-4, GHD, January 2106

Attachment B-9 – Supplemental Sampling Activities Summary Letter Report, GHD, October 3, 2016

# 1. Introduction

## 1.1 Site Description

GSP Holdings, Inc. (formerly known as GSP, Inc.; or GSP) is investigating and remediating a historic accidental release under the New York State Brownfield Cleanup Program (BCP, Index #B7-0713-06-03 effective March 27, 2008, Site #C734108). The facility is located at 5762 Celi Drive in the Town of Dewitt, Onondaga County, New York (the 'Site', Figure 1-1). The Site is identified as Tax Parcel 053.-02-17.2 on the Onondaga County Real Property Tax Map (Attachment A). The Site consists of approximately 1.45-acres of land with an approximately 47,098-square foot building (Figure 1-2). The remainder of the Site is covered by either asphalt pavement parking areas and driving lanes or minor landscaping areas. The Site is located in a mixed commercial and industrial use area north of Towpath Road, east of Celi Drive, south of adjacent commercial properties, and west of Whirlybird Lane.

The Site is generally flat with a slight slope to the north and is at an elevation of approximately 410 feet above mean sea level, according to the United States Geological Survey (USGS) 7.5-Minute Topographic Map Series for the Syracuse East, New York Quadrangle (USGS, 2016). Surface runoff drains to the north via a drainage swale constructed along the east side of the Site building.

The Site was historically used primarily for processes related to chrome, nickel, and copper plating of plastic and metal substrates, and consisted of plating areas, storage and staging areas, a waste water treatment system, and associated office areas. The Site tenant's operations ceased in 2015, all equipment and materials/products were removed, and the Site is currently vacant and listed for sale.

Under the BCP, a Remedial Investigation (RI) was completed by ERM Consulting and Engineering, Inc. (ERM) between 2005 and 2012. The RI consisted of initial Site investigation and abatement activities performed in direct response to the accidental release (summarized in the *Comprehensive Site Investigation Report*, ERM, 2005) and subsequent investigations performed in connection with the Site (summarized in the *Data Gap Investigation Report*, ERM, 2012). These reports identified four (4) areas of concern (AOCs) for the Site, including:

- AOC-1: Affected soil and groundwater located adjacent to and beneath the southeast corner of the manufacturing building (Figure 2 in Attachment B-3);
- AOC-2: Affected soil/sediment and groundwater located in the drainage swale immediately east of the manufacturing building (Figure 2 in Attachment B-3);
- AOC-3: Residual solids in the buried stormwater culvert pipe (Town of DeWitt Bridge Street Drainage District) beginning at the north end of the GSP Swale and terminating at Bridge Street and soil located at the culvert discharge into the Bridge Street drainage swale (Figure 2 in Attachment B-3); and
- AOC-4: Affected soil/sediment and surface water located in the drainage swale on the north side of Bridge Street (Figure 4 in Attachment B-2). The initial section of the swale is controlled by the Town of DeWitt as part of the Bridge Street Drainage District (Area 1). The Extension of the swale from the confluence of the Bridge Street swale and the NYS Route 690 drainage swale to areas downstream (Area 2) is reportedly part of a Right of Way (R.O.W.) controlled and maintained by the NYS Department of Transportation (NYSDOT).

Portions of the swale are located on National Grid property which the Town of DeWitt easement crosses.

## 1.2 Purpose

This Remedial Alternatives Analysis (RAA) has been prepared by GHD Consulting Services Inc. (GHD) to evaluate remedial alternatives based on the findings of the RI and subsequent environmental investigations. This RAA relies on these previous findings as a basis for the screening and selecting of an appropriate remedial alternative to be protective of human health and the environment. This RAA identifies and evaluates remedial alternatives for each of the four (4) AOCs for the Site, and recommends a remedy for each AOC.

## 1.3 Scope and Limitations

This report: has been prepared by GHD for GSP Holdings, Inc. and may only be used and relied on by GSP Holdings, Inc. for the purpose agreed between GHD and GSP Holdings, Inc. as set out in section 1.2 of this report. GHD otherwise disclaims responsibility to any person other than GSP Holdings, Inc. arising in connection with this report. GHD also excludes implied warranties and conditions, to the extent legally permissible.

The services undertaken by GHD in connection with preparing this report were limited to those specifically detailed in the report and are subject to the scope limitations set out in the report.

The opinions, conclusions and any recommendations in this report are based on conditions encountered and information reviewed at the date of preparation of the report. GHD has no responsibility or obligation to update this report to account for events or changes occurring subsequent to the date that the report was prepared.

The opinions, conclusions and any recommendations in this report are based on assumptions made by GHD described in this report (refer section 1.4 of this report). GHD disclaims liability arising from any of the assumptions being incorrect.

GHD has prepared this report on the basis of information provided by GSP Holdings, Inc. and others who provided information to GHD, which GHD has not independently verified or checked beyond the agreed scope of work. GHD does not accept liability in connection with such unverified information, including errors and omissions in the report which were caused by errors or omissions in that information.

GHD has prepared the preliminary Cost Estimates set out in Sections 4, 5, 6 and 7 of this report ("Costs") using information reasonably available to GHD, who prepared this report; and based on assumptions and judgments made by GHD.

The Cost Estimates have been prepared for the purpose of the assessment of remedial alternatives and must not be used for any other purpose.

The Cost Estimates are preliminary estimates only. Actual prices, costs and other variables may be different to those used to prepare the Cost Estimate and may change. Unless as otherwise specified in this report, no detailed quotation has been obtained for actions identified in this report. GHD does not represent, warrant or guarantee that the project can or will be undertaken at a cost which is the same or less than the Cost Estimates.

Where estimates of potential costs are provided with an indicated level of confidence, notwithstanding the conservatism of the level of confidence selected as the planning level, there remains a chance that the cost will be greater than the planning estimate, and any funding would

not be adequate. The confidence level considered to be most appropriate for planning purposes will vary depending on the conservatism of the user and the nature of the project. The user should therefore select appropriate confidence levels to suit their particular risk profile.

The opinions, conclusions and any recommendations in this report are based on information obtained from, and testing undertaken at or in connection with, specific sample points. Site conditions at other parts of the site may be different from the site conditions found at the specific sample points.

Investigations undertaken in respect of this report are constrained by the particular site conditions, such as the location of buildings, services and vegetation. As a result, not all relevant site features and conditions may have been identified in this report.

Site conditions (including the presence of hazardous substances and/or site contamination) may change after the date of this Report. GHD does not accept responsibility arising from, or in connection with, any change to the site conditions. GHD is also not responsible for updating this report if the site conditions change.

#### 1.4 Assumptions

GHD has prepared this report in part on the basis of information provided by GSP Holdings, Inc. and others who provided information to GHD, which GHD has not independently verified or checked beyond the agreed scope of work. GHD does not accept liability in connection with such unverified information, including errors and omissions in the report which were caused by errors or omissions in that information. The information provided includes site investigation results and findings completed by others (including ERM) on behalf of GSP and as provided by GSP to GHD.

In addition, the assessment of alternatives for AOC-2 includes the prospective purchase of land that encompasses the GSP swale to the east of the GSP buildings. The proposed purchase of land will encompass the swale from the top of bank to the east to the current GSP property line adjacent to the building. The purchase of land will facilitate the proposed remedial approach and allow for appropriate institutional controls to be placed on the area of concern.

## 2. Summary of Previous Investigations

The results of previous investigations, along with figures, analytical data tables, and laboratory analytical reports, were provided in the following reports:

- Comprehensive Site Investigation Report, ERM, October 2005
- Data Gap Investigation Report, ERM, June 2012
- Work Plan to Address Areas of Concern 1, 2, & 3, ERM, November 2012
- Monthly Progress Report – October 2012, ERM, November 9, 2012
- Emergency Remedial Work Plan, GHD, June 2013
- Background Sediment Sampling Letter Report, GHD, October 2013
- Groundwater Sampling Letter Report, GHD, April 16, 2014
- Construction Completion Report – AOC-3 and AOC-4, GHD, January 2016
- Supplemental Sampling Activities Summary Letter Report, GHD, October 3, 2016.

This section of the RAA provides a general summary of the results of previous investigations and remedial measures. Results discussed below are summarized in Tables in Attachments B-1, B-2, B-3, B-4, B-5, B-6, B-7, B-8, and B-9. Locations discussed are shown on Figures in Attachments B-1, B-2, B-3, B-4, B-5, B-6, B-7, B-8, and B-9.

### 2.1 Comprehensive Site Investigation Report

The New York State Department of Environmental Conservation (NYSDEC) notified GSP of a potential release from their facility on May 10, 2005. NYSDEC and GSP personnel walked the Site to identify potential sources of the release. Stagnant water was observed in the roof drain area located immediately east of the manufacturing building along the GSP Swale. NYSDEC requested that soil and groundwater samples be collected from the area for laboratory analysis. As a result, GSP contracted ERM to assist with investigation and remediation of the release. The initial phase of Site investigation and remediation summarized in this report was conducted immediately following discovery of the accidental release, prior to the Site's entry into the BCP.

#### 2.1.1 Response to the Release

GSP and ERM conducted an inspection and testing program to identify the source of the release and the extent of the impacts. Based on inspection of water collection areas within the manufacturing building, it was determined that the plastic plating line wastewater equalization tank was the source of the release as the result of the negligent installation of the tank lining by a third party. GSP constructed a tank within a tank to contain wastewater, which prevented further release of potentially contaminated water.

During June 2005, Environmental Products and Services (EPS) pumped ponded water from the roof drain area and GSP Swale to a temporary storage tank located at the GSP Facility. The water was treated and released with authority to the Onondaga County Waste Water Treatment Facility. EPS constructed a temporary earthen berm around the area to prevent further release. The berm was lined with polyethylene sheeting and surrounded by temporary fencing. The roof drain leader was plugged to prevent release of additional rain water into the area. Water entering the roof drain area was pumped into temporary storage tanks located at the GSP Facility.

Water samples were taken from the GSP Swale Area, and Bridge Street Swale by Upstate Laboratories, Inc. (Upstate) and ERM personnel. Laboratory analytical results of the samples indicated that water in the Bridge Street Swale contained some metals similar to those identified at the GSP facility that were associated with the release. As a result, EPS removed approximately 67,000-gallons of water from the Bridge Street Swale and staged it in temporary storage tanks located at the GSP Facility. The water was treated and released with authority to the Onondaga County Waste Water Treatment Facility.

Based on observations made during the initial response to the release, it was determined necessary to conduct a Site investigation to determine the full extent of impacts from the release.

### 2.1.2 Site Investigation Sampling

Soil, sediment, ponded water, and groundwater samples were taken from the GSP Swale Area and Bridge Street Swale as follows:

- **May 2005:**
  - GSP personnel collected a soil sample (sample GSP-1 on Table 5-1 and Figure 4-1 in Attachment B-1) and a water sample (sample GSP-2 on Table 5-7 and Figure 4-1 in Attachment B-1) from the GSP Swale Area, as requested by NYSDEC, on May 10, 2005. The soil sample was analyzed for cadmium, total chromium, copper, lead, nickel, silver, and zinc. The water sample was analyzed for cadmium, total chromium, copper, lead, nickel, silver, and zinc;
  - Upstate personnel collected and analyzed soil samples (samples Drain Point and Ditch on Table 5-1 and Figure 4-1 in Attachment B-1) from the GSP Swale Area, and water samples from the GSP Swale Area (sample Drain Point on Table 5-7 and Figure 4-1 in Attachment B-1) and from the Bridge Street Swale (sample Bridge Street Swale on Table 5-9 and Figure 4-3 in Attachment B-1), as requested by NYSDEC, on May 18, 2005. The soil samples were analyzed for metals (arsenic, barium, cadmium, total chromium, copper, lead, mercury, nickel, selenium, silver, zinc, total cyanide, and hexavalent chromium), Target Compound List (TCL) volatile organic compounds (VOCs), TCL semi-volatile organic compounds (SVOCs), ignitability, pH, reactive cyanide, and reactive sulfide. The water sample was analyzed for metals (arsenic, barium, cadmium, total chromium, copper, lead, mercury, nickel, selenium, silver, zinc, total cyanide, and hexavalent chromium), TCL VOCs, TCL SVOCs, ignitability, pH, reactive cyanide, and reactive sulfide;
  - ERM personnel collected grab soil samples from the near surface (6- to 8-inch interval) and the shallow subsurface (16- to 18-inch interval) from fourteen (14) locations on May 27, 2005 (samples GSP-001 through GSP-014 on Table 5-2 and Figure 4-1 in Attachment B-1). The samples were analyzed for total chromium, copper, nickel, zinc, and total cyanide;
  - ERM personnel collected two (2) composite soil samples (samples GSP-COMP1(1) and GSP-COMP2(1) on Table 5-3 and Figure 4-1 in Attachment B-1) from approximately 1-foot bgs in the GSP Swale Area for Toxicity Characteristic Leaching Procedure (TCLP) analysis on May 27, 2005;
  - ERM personnel collected four (4) soil samples (samples GSP-020A@4', GSP-021A@6"-1', GSP-022A@6"-1', and GSP-023A@(DUPE) on Table 5-3a and Figure 4-1 in Attachment B-1) from the Roof Drain Area and GSP Swale on May 31, 2005 to confirm

reports of volatile organic compounds (VOCs) detected in Upstate's soil samples. The Roof Drain Area sample was taken from approximately 4-feet bgs, and the GSP Swale samples were taken from 0.5-feet to 1-foot bgs; and

- ERM personnel collected two (2) soil samples (samples GSP-024A@6"-1' and GSP-025A@6"-1' on Table 5-3a and Figure 4-1 in Attachment B-1) from the 6-inch to 1-foot interval of the GSP Swale Area for total cyanide analysis on May 31, 2005, at the request of NYSDEC.
- **June 2005:**
  - ERM collected surface water samples (samples Swale-101 through Swale-105 and BSS-Swale-01 through BSS-Swale-06 on Table 5-10 and Figure 4-3 in Attachment B-1) from the Bridge Street Swale on June 2, and June 9, 2005. Samples were analyzed for total chromium, copper, nickel, zinc, total cyanide, and hexavalent chromium;
  - ERM collected soil samples from twenty-two (22) locations along the Bridge Street Swale on June 3, 2005. Samples were taken from the near surface (3- to 6-inch bgs) and the shallow subsurface (13- to 16-inch bgs) intervals, for a total of thirty-four (34) samples for laboratory analysis (samples GSP-200 through GSP-221 on Table 5-5 and Figure 4-3 in Attachment B-1). Each sample was analyzed for total chromium, copper, nickel, zinc, and total cyanide;
  - ERM collected four (4) soil samples (samples CON-001, CON-001A, CON-002, and CON-003 on Table 5-4 and Figure 4-1 in Attachment B-1) from an excavation completed in the Roof Drain Area by EPS on June 7, 2005. Three (3) soil samples were taken from 3-feet bgs and one (1) soil sample was taken from 4.5-feet bgs. Each sample was analyzed for total chromium, copper, nickel, zinc, and total cyanide;
  - ERM collected soil samples from thirteen (13) locations along the GSP Swale Area on June 9, 2005 to further delineate the extent of metals impacts. Soil samples were taken from 1- to 3-inches bgs and 13- to 15-inches bgs from each location, for a total of twenty-six (26) soil samples for laboratory analysis (samples GSP-SWALE-015 through GSP-SWALE-027 on Table 5-2 and Figure 4-1 in Attachment B-1). Each sample was analyzed for total chromium, copper, nickel, zinc, and total cyanide;
  - ERM collected soil samples from eleven (11) locations along the Bridge Street Swale on June 10, 2005. Samples were taken from the near surface (1- to 3-inch bgs) and the shallow subsurface (13- to 15-inch bgs) intervals, for a total of nineteen (19) samples for laboratory analysis (samples BSS-S-222 through BSS-S-232 on Table 5-5 and Figure 4-3 in Attachment B-1). Each sample was analyzed for chromium, copper, nickel, zinc, and total cyanide;
  - ERM collected soil samples from four (4) test pits completed by EPS along the east wall of the GSP Facility on June 14, 2005. Two (2) samples were taken from each test pit for a total of eight (8) soil samples (samples TP-1 through TP-4 on Table 5-4 and Figure 4-2 in Attachment B-1). The soil samples were taken from various locations between 2- to 7-feet bgs and were analyzed for total chromium, copper, nickel, zinc, and total cyanide; and
  - ERM collected groundwater samples (samples TPW-1 through TPW-4 on Table 5-11 and Figure 4-2 in Attachment B-1) from temporary groundwater monitoring wells installed along the east side of the Site building on June 17, 2005. Each sample was analyzed for total chromium, copper, nickel, zinc, and total cyanide.



- **July 2005:**
  - ERM collected soil samples from twelve (12) sub-slab soil borings completed throughout the manufacturing building during the week on July 6, 2005. Two (2) samples were taken from each boring, one (1) from immediately below the concrete slab and one (1) from the 12- to 18-inch bgs interval, for a total of twenty-four (24) soil samples (samples B-1 through B-12 on Table 5-6 and Figure 4-5 in Attachment B-1). Each sample was analyzed for total chromium, copper, nickel, zinc, and total cyanide. One (1) sample (B-4 on Table 5-6a) was also analyzed for TCL VOCs, TCL SVOCs, PCBs, metals (arsenic, barium, cadmium, total chromium, copper, lead, mercury, nickel, selenium, silver, zinc, total cyanide, and hexavalent chromium), ignitability, pH, reactive cyanide, and reactive sulfide; and
  - ERM collected four (4) groundwater samples (samples TW-1 through TW-4 on Table 5-8 and Figure 5-4 in Attachment B-1) from temporary groundwater monitoring wells installed in the sub-slab soil borings discussed above on July 8, 2005. Each sample was analyzed for total chromium, copper, nickel, zinc, and total cyanide.
- **August 2005:**
  - ERM installed three (3) groundwater monitoring wells to an approximate depth of 16-feet bgs on August 18, 2005; and
  - ERM collected groundwater samples (samples GSP-MW-1 through GSP-MW-3 on Table 5-12 and Figure 5-9 in Attachment B-1) from the previously installed wells on August 22, 2005. Each sample was analyzed for total chromium, copper, nickel, zinc, total cyanide, and hexavalent chromium.

In total, 158 soil samples, 14 ponded/surface water samples, and 12 groundwater samples (including quality assurance/quality control duplicate samples) were taken during Site Investigation activities.

### 2.1.3 Site Investigation Results

Results of the 2005 Site Investigation sampling identified the following:

- **GSP Swale Area:**
  - Soil impacted with metals contamination from the ground surface to a maximum depth of 6-feet bgs, specifically the following analytes compared to 6 NYCRR Subpart 375-6 Remedial Program Soil Clean-up Objectives (SCOs):

Analyte	Lowest Identified Concentration (mg/kg)	Highest Identified Concentration (mg/kg)	Total Number of Samples Taken	Unrestricted Use SCO (mg/kg)	Commercial Use SCO (mg/kg)
Cadmium	Non-Detect	4.7	3	2.5	9.3
Total Chromium	8.47	4,100	69	31	1,900
Copper	7.8	13,000	69	50	270
Nickel	7.6	3,720	69	30	310

Analyte	Lowest Identified Concentration (mg/kg)	Highest Identified Concentration (mg/kg)	Total Number of Samples Taken	Unrestricted Use SCO (mg/kg)	Commercial Use SCO (mg/kg)
Selenium	3.5	4.7	2	3.9	1,500
Zinc	11.8	2,340	69	109	10,000
Cyanide	Non-Detect	903	50	27	27

- o Ponded water samples identified the following contaminant of concern concentrations that are compared to New York State Technical and Operational Guidance Series (TOGS)

1.1.1 Ambient Water Quality Standards:

Analyte	TOGS Standard or Guidance (G) Value (ug/L)	Lowest Identified Concentration (ug/L)	Highest Identified Concentration (ug/L)	Total Number of Samples Taken
Acetone	50 (G)	100	100	1
Total Chromium	50	26,000	55,000	2
Copper	200	110,000	110,000	2
Nickel	100	110,000	120,000	2
Zinc	2,000 (G)	180	680	2
Hexavalent Chromium	50	57,000	57,000	1
Cyanide	200	Non-Detect	Non-Detect	1

The impacted water was pumped from the swale, treated, and discharged to the Onondaga County Waste Water Treatment Facility.

- **Bridge Street Swale:**

- o Soil impacts were identified from Bridge Street to the Interstate 690 off-ramp and points west with the following metals concentrations, which are compared to 6 NYCRR Subpart 375-6 SCOs:

Analyte	Lowest Identified Concentration (mg/kg)	Highest Identified Concentration (mg/kg)	Total Number of Samples Taken	Protection of Ecological Resources SCO (mg/kg)	Unrestricted Use SCO (mg/kg)	Commercial Use SCO (mg/kg)
Total Chromium	5.51	966	53	42	31	1,900

Analyte	Lowest Identified Concentration (mg/kg)	Highest Identified Concentration (mg/kg)	Total Number of Samples Taken	Protection of Ecological Resources SCO (mg/kg)	Unrestricted Use SCO (mg/kg)	Commercial Use SCO (mg/kg)
Copper	5.47	7,170	53	50	50	270
Nickel	6.32	2,330	53	30	30	310
Zinc	30.6	473	19	109	109	10,000
Cyanide	Non-Detect	15.7	53	No Standard	27	27

The majority of soil impacts occur along the central axis of the swale;

- o The surface water sample analytical results identified the following analytes, which are compared to New York State TOGS 1.1.1 Ambient Water Quality Standards:

Analyte	TOGS Standard or Guidance (G) Value (ug/L)	Identified Concentration (ug/L)
Acetone	50	62
Total Chromium	50	6,400
Copper	200	23,000
Nickel	100	12,000
Zinc	2,000 (G)	120
Hexavalent Chromium	50	Matrix interference prevented quantification
Cyanide	200	Non-Detect

The impacted water was pumped from the swale, treated, and discharged to the Onondaga County Waste Water Treatment Facility.

- o After pumping out the impacted water, additional surface water sampling identified the following analytes, which are compared to New York State TOGS 1.1.1 Ambient Water Quality Standards:

Analyte	TOGS Standard or Guidance (G) Value (ug/L)	Lowest Identified Concentration (ug/L)	Highest Identified Concentration (ug/L)	Total Number of Samples Taken
Total Chromium	50	Non-Detect	650	13
Copper	200	Non-Detect	1,920	13

Analyte	TOGS Standard or Guidance (G) Value (ug/L)	Lowest Identified Concentration (ug/L)	Highest Identified Concentration (ug/L)	Total Number of Samples Taken
Nickel	100	Non-Detect	962	13
Zinc	2,000 (G)	Non-Detect	120	6
Hexavalent Chromium	50	Non-Detect	630	6
Cyanide	200	Non-Detect	12	12

- **Sub-Slab Area:**

- Soil samples were identified as impacted with the following metals concentrations, which are compared to 6 NYCRR Subpart 375-6 SCOs:

Analyte	Lowest Identified Concentration (mg/kg)	Highest Identified Concentration (mg/kg)	Total Number of Samples Taken	Unrestricted Use SCO (mg/kg)	Commercial Use SCO (mg/kg)
Total Chromium	7.3	1,300	25	31	1,900
Copper	11.9	87,400	24	50	270
Nickel	10.5	5,780	24	30	310
Zinc	Non-Detect	745	24	109	10,000
Cyanide	Non-Detect	2.82	25	27	27

- **Groundwater:**

- Groundwater samples were impacted with analytes at concentrations that are compared to New York State TOGS 1.1.1 Ambient Water Quality Standards, as follows:

Analyte	TOGS Standard or Guidance (G) Value (ug/L)	Lowest Identified Concentration (ug/L)	Highest Identified Concentration (ug/L)	Total Number of Samples Taken
Total Chromium	50	Non-Detect	389,000	19
Copper	200	Non-Detect	22.6	19
Nickel	100	Non-Detect	1,880	19
Zinc	2,000 (G)	Non-Detect	371	19

Analyte	TOGS Standard or Guidance (G) Value (ug/L)	Lowest Identified Concentration (ug/L)	Highest Identified Concentration (ug/L)	Total Number of Samples Taken
Hexavalent Chromium	50	Non-Detect	14.0	14
Cyanide	200	Non-Detect	93.8	19

- o Impacted groundwater was identified in samples taken adjacent to the east wall of the GSP Facility, both in the GSP Swale Area and in the Sub-Slab Area, where the release originated.

#### 2.1.4 Summary and Recommendations

The contaminants of concern for the Site were determined to be chromium, copper, nickel, and zinc. It was noted by GSP that although zinc was detected in soil samples above Unrestricted SCOs, zinc was not identified as one of the metals used in the GSP process and was not associated with the release. These contaminants occur in on-Site and off-Site soil, sediment, and surface water, and in discrete areas of on-Site groundwater. The Comprehensive Site Investigation Report (ERM, 2005) recommended that additional investigation and remediation of soil and groundwater be completed in the Sub-Slab Area and GSP Swale, and that additional investigation and remediation of soil, sediment, and surface water be completed in the Bridge Street Swale.

## 2.2 Data Gap Investigation Report

The *Comprehensive Site Investigation Report* (ERM, 2005) was submitted to the NYSDEC along with a Brownfield Cleanup Program (BCP) Application for the Site on November 29, 2005. The Site was admitted into the BCP on March 27, 2008, at which time a Remedial Investigation (RI) was required. The *Data Gap Investigation Report* (ERM, June 2012), in conjunction with the *Site Investigation Report* (ERM, 2005), satisfied the requirements for an RI under the BCP and was approved by the NYSDEC (September 23, 2013). The Data Gap Investigation activities were completed in 2010, and included the following activities.

### 2.2.1 AOC-1 – Sub-Slab Area

To further delineate sub-slab soil exceedances identified during the initial investigation in 2005, four (4) sub-slab soil borings (B-340, B-341, B-342, and B-343 on Figure 5 in Attachment B-2) were completed in the southeast corner of the manufacturing building. Soil borings B-340 and B-341 were completed vertically using a hand auger and soil borings B-342 and B-343 were completed horizontally using a hand auger. A soil sample was taken from each boring and analyzed for total chromium, copper, nickel, zinc, total cyanide, and hexavalent chromium (Table 1 in Attachment B-2).

Sub-slab soil sample laboratory analytical results from the initial Site investigation and data gap investigation indicated that soils samples exceed Industrial Use Soil Cleanup Objectives (SCOs) for copper and nickel. Based on analytical results, the extent of impacts appear to be well defined, and is bound by soil boring B-343 to the north, the exterior foundation wall to the east and south, and soil boring B-340 to the west (Figure 10 in Attachment B-2).

### 2.2.2 AOC-2 – GSP Swale

To further delineate impacts identified during the initial investigation in 2005, fourteen (14) direct push soil borings (B-307 through B-320 on Figure 11 in Attachment B-2) were completed to a depth of 8-feet bgs within, and in proximity to, the GSP Swale. Two (2) soil samples were taken from each boring, one (1) from the 4- to 6-foot interval and one (1) from the 6- to 8-foot interval, for a total of twenty-eight (28) samples. Each soil sample was analyzed for total chromium, copper, nickel, zinc, total cyanide, and hexavalent chromium (Table 2 in Attachment B-2).

Two (2) additional soil borings (B-316 and B-350 on Figure 11 in Attachment B-2) were completed to the east of the GSP Swale. A groundwater monitoring well (MW-8) was completed in soil boring B-316. Soil boring B-350 was completed to 4-feet bgs and one (1) sample was taken from the 1- to 1.5-foot bgs interval. The soil sample was analyzed for total chromium, copper, nickel, zinc, total cyanide, hexavalent chromium, acetone (select samples), and methylene chloride (select samples) (Table 2 in Attachment B-2).

In addition, surface soil samples were taken from the upper 4-inches of soil at the four (4) borings closest to the roof drain area (borings B-313, B-315, B-316, and B-317 on Figure 11 in Attachment B-2). Each soil sample was analyzed for total chromium, copper, nickel, zinc, total cyanide, hexavalent chromium, acetone, and methylene chloride (Table 2 in Attachment B-2).

GSP Swale soil sample laboratory analytical results from the initial Site investigation and the data gap investigation identified exceedances of Commercial Use SCOs in the following samples:

Sample ID (Depth Interval)	Analyte	Commercial Use SCO (mg/kg)	Identified Concentration (mg/kg)
GSP-006 (16- to 18-inches bgs)	Copper	270	635
GSP-010 (6- to 8-inches bgs)	Total Chromium	1,900	3,830
	Copper	270	11,900
GSP-010 (16- to 18-inches bgs)	Total Chromium	1,900	2,700
	Copper	270	13,000
GSP-012 (16- to 18-inches bgs)	Copper	270	672
GSP-013 (6- to 8-inches bgs)	Copper	270	1,310
GSP-013 (16- to 18-inches bgs)	Copper	270	1,830
GSP-SWALE-024 (13- to 15-inches bgs)	Copper	270	477

Based on these results, ERM concluded in their report that soil contamination due to contaminants of concern is limited to shallow soil in the GSP Swale (Figure 11 in Attachment B-2). Of particular note is that only one sample exceeded Industrial SCOs and only for copper.

### 2.2.3 AOC-3 – Buried Culvert Pipe

In order to assess soil conditions in proximity to the buried culvert pipe, six (6) soil borings were advanced adjacent to the pipe (GSP-344 through GSP-349 on Figure 12 in Attachment B-2). Each boring was completed using direct push drilling methods. One (1) soil sample was taken from the

bottom of five (5) of the soil borings (GSP-344, GSP-345, GSP-346, GSP-347, and GSP-348 on Table 3 in Attachment B-2) and analyzed for total chromium, copper, nickel, zinc, total cyanide, and hexavalent chromium. Two (2) soil samples were taken from soil boring GSP-349, one (1) from the 2- to 2.5-foot bgs interval and one (1) from the 5- to 5.5-foot bgs interval, and analyzed for total chromium, copper, nickel, zinc, total cyanide, and hexavalent chromium (Table 3 in Attachment B-2).

Data collected during the RI indicate that one (1) subsurface soil sample (GSP-348) in proximity to AOC-3, and, in an area adjacent to Bridge Street and other commercial businesses, exceeded the Commercial Use SCOs for copper and nickel; and zinc and total chromium for Unrestricted SCOs at approximately 5.5- to 6.5-foot bgs. In addition, one other sample (GSP-349) had an exceedance of Unrestricted SCOs for hexavalent chromium (1.12 versus 1 mg/kg) and for zinc at a depth of 5-5.5 feet bgs. All other soil samples collected associated with AOC-3 were below Unrestricted SCOs.

#### 2.2.4 AOC-4 – Bridge Street Swale

Eight (8) soil borings (soil borings GSP-321 through GSP-328 on Figures 13A and 13B in Attachment B-2) were completed in the Bridge Street Swale using a hand auger or manually operated soil coring device. Each soil sample was taken from the soil/water interface and analyzed for total chromium, copper, nickel, zinc, total cyanide, hexavalent chromium, acetone (select samples), and methylene chloride (select samples) (Table 4 in Attachment B-2).

Eleven (11) soil borings (soil borings GSP B-329 through GSP-B-339 on Figures 13A and 13B in Attachment B-2) were completed adjacent to the Bridge Street Swale. Three (3) soil samples were taken from each boring, one (1) from the 0- to 2-inch bgs interval, one (1) from the 12- to 14-inch bgs interval, and one (1) from the 22- to 24-inch bgs interval, for a total of thirty-three (33) soil samples for laboratory analysis. Each soil sample was analyzed for total chromium, copper, nickel, zinc, total cyanide, hexavalent chromium, acetone (select samples), and methylene chloride (select samples) (Table 4 in Attachment B-2).

At the request of the NYSDEC, one (1) surface water sample was taken from the Bridge Street Swale to further assess detections of acetone and methylene chloride from the initial Site investigation. The sample was analyzed for acetone and methylene chloride (sample GSP-Surface Water).

The sediment sample laboratory analytical results reported by ERM indicate that contaminants of concern, mainly copper and nickel, exceeded Commercial Use SCOs along the Bridge Street Swale in two (2) locations: along the north-south trending portion, from its intersection with Bridge Street for a distance approximately 800-feet north; and along the approximately east-west trending portion from sample location GSP-325 to sample location GSP-233 (Figures 13A and 13B in Attachment B-2).

Surface water sample laboratory analytical results indicate that methylene chloride was not detected above laboratory detection limits and acetone was identified at a concentration of 11.2 ug/L, which is below the New York State TOGS 1.1.1 Ambient Water Quality guidance value (50 ug/L). Neither of these contaminants is considered contaminants of concern.

#### 2.2.5 Groundwater

Based on detections identified during the initial Site investigation in 2005, five (5) additional groundwater monitoring wells were installed in 2010 (groundwater monitoring wells MW-4 through MW-8 on Figure 9 in Attachment B-2). Groundwater monitoring well MW-8 is located east of the

GSP Swale, on an adjacent property. Groundwater samples were taken from each of the groundwater monitoring wells and analyzed for total chromium, copper, nickel, zinc, total cyanide, hexavalent chromium, acetone, and methylene chloride (Table 5 in Attachment B-2).

Groundwater sample laboratory analytical results indicate that nickel was detected above New York State TOGS 1.1.1 Ambient Water Quality standards in samples MW-3 and MW-4 (Figure 14 in Attachment B-2). Hexavalent chromium was detected above TOGS 1.1.1 standards in the sample from groundwater monitoring well MW-3 during the initial Site investigation, but was not detected during data gap investigation sampling. ERM concluded in their report that groundwater impacts are limited to a small area proximal to the southeast corner of the building, where the initial release occurred.

### 2.3 Bridge Street Swale Dredging

Town of Dewitt personnel excavated material from a portion of the Bridge Street Swale on March 8, 2012 using a track-mounted excavator. The excavated material was reportedly placed on the ground near the eastern and western edges of the Bridge Street Swale, within the swing radius of the excavator. ERM personnel discovered the excavation activity on March 8, 2012 and notified GSP and NYSDEC. GSP subcontracted EPS to cover the excavated materials with polyethylene sheeting.

ERM personnel collected four (4) composite soil samples from the excavated materials on March 9, 2012, for disposal characterization purposes. Each of the composite samples was analyzed for the following:

- Extractable petroleum hydrocarbons;
- Toxicity characteristics leaching procedure (TCLP) metals;
- Percent solids;
- pH;
- Free liquids: and
- Ignitability.

The excavated material was loaded into roll-off containers and transported off-Site for disposal as non-hazardous waste. In total, approximately 166.5 tons of material was transported for disposal at the Seneca Meadows Landfill in Seneca Falls, New York in October 2012. ERM personnel collected three (3) confirmatory soil samples from the excavated portion of the Bridge Street Swale and had them analyzed for chromium, copper, nickel, zinc, and cyanide (Table 1 in Attachment B-4). Laboratory analytical results, as reported by ERM, identified one (1) copper concentration in excess of the Commercial Use SCO (545 mg/kg in sample 402, Figure 1 in Attachment B-4). All other identified concentrations were below the Unrestricted Use SCOs, except:

Sample Identification	Analyte	Unrestricted Use SCO (mg/kg)	Identified Concentration (mg/kg)
401	Copper	50	50.8
	Zinc	109	166



Sample Identification	Analyte	Unrestricted Use SCO (mg/kg)	Identified Concentration (mg/kg)
402	Chromium	31	143
	Copper	50	545
	Nickel	30	202
	Zinc	109	401

## 2.4 Background Sediment Sampling

On September 3, 2013, GHD personnel completed background sediment sampling at five (5) locations (locations A, B, C, D, and E on Figure 2 in Attachment B-6) that appeared similar in character to the Bridge Street Swale (AOC-4 of the Site). The objectives of the background sediment sampling were to establish background reference values for comparison to Bridge Street Swale conditions. Sediment samples were taken from three (3) intervals at each sample location: one (1) sample from the 0- to 6-inch bgs interval, one (1) sample from the 12- to 14-inch bgs interval, and one (1) sample from the 22- to 24-inch bgs interval, for a total of fifteen (15) samples for laboratory analysis. Each sediment sample was analyzed for total chromium, hexavalent chromium, total copper, total cyanide, total nickel, and total zinc.

Background sediment sample laboratory analytical results were summarized and compared to Unrestricted Use, Commercial Use, and Protection of Ecological Resources SCOs (Table 2 in Attachment B-6). Total cyanide and hexavalent chromium were not detected above laboratory detection limits in any of the background sediment samples. Total nickel was detected in all of the background sediment samples; however, the detected concentrations did not exceed the Unrestricted Use SCO.

Laboratory analytical results indicated that ten (10) of the fifteen (15) background sediment samples exceed the Unrestricted Use SCOs for at least one analyte, as follows:

Analyte	Sample Identification	Concentration (mg/kg)
<b>Total Chromium</b> Protection of Ecological Resources SCO – 42 mg/kg Unrestricted Use SCO – 31 mg/kg Commercial Use SCO – 1,900 mg/kg	Background C1	80
	Background C2	48
	Background D1	40
	Background D2	48
	Background D3	31
	<b>Total Copper</b> Protection of Ecological Resources SCO – 50 mg/kg Unrestricted Use SCO – 50 mg/kg Commercial Use SCO – 270 mg/kg	Background A2
Background B1		60
Background C3		51

Analyte	Sample Identification	Concentration (mg/kg)
<b>Total Zinc</b> Protection of Ecological Resources SCO – 109 mg/kg Unrestricted Use SCO – 109 mg/kg Commercial Use SCO – 10,000 mg/kg	Background A2	300
	Background B1	140
	Background C2	120
	Background D1	140
	Background E1	290
	Background E2	130

Each of these concentrations also exceed the Protection of Ecological Resources SCOs, with the exception of total chromium in Background D1 and Background D3.

Based on laboratory analytical results, it was concluded that background concentrations of copper and zinc exceed Protection of Ecological Resources SCOs over a wide area. Exceedances of total chromium were also identified; however, they were limited to two (2) sample locations, both of which were from the same drainage feature.

## 2.5 Groundwater Sampling 2014

GHD personnel conducted sampling of seven (7) of the eight (8) permanent groundwater monitoring wells (MW-1 through MW-7 on Figure 2 in Attachment B-7) on January 31, 2014. The objectives of the groundwater sampling were to obtain more recent groundwater data that could be used to further refine the Remedial Alternatives Analysis relative to groundwater contamination and to confirm the groundwater flow direction.

Groundwater samples were taken from each of the groundwater monitoring wells utilizing low flow purging and sampling techniques, after depth to water measurements were recorded. Wells were purged until field parameters (i.e., temperature, conductivity, salinity, dissolved oxygen, pH, oxidation reduction potential, and turbidity) stabilized, at which point the groundwater sample was taken. Since groundwater samples were analyzed for metals, an effort was made to reduce the turbidity of the sample water to less than 50 Nephelometric Turbidity Units (NTUs). Turbidity of the sample water was less than 50 NTUs for each sample, except samples MW-4 and MW-5. Extended purging of these two wells did not achieve a turbidity of less than 50 NTUs; therefore, the samples were taken after achieving a reasonable purge volume. In addition to the seven (7) groundwater samples, one (1) duplicate sample, one (1) matrix spike sample, and one (1) matrix spike duplicate sample were also taken for quality assurance/quality control purposes, for a total of ten (10) samples for laboratory analysis. Each groundwater sample was analyzed for total chromium, total copper, total nickel, total zinc, hexavalent chromium, and total cyanide,

Permanent groundwater monitoring well samples laboratory analytical results were summarized and compared to the NYSDEC Division of Water Technical and Operational Guidance Series (TOGS) Class GA ambient water quality standards or guidance values (Table 3 in Attachment B-7). Laboratory analytical results of groundwater samples did not identify hexavalent chromium or total cyanide at concentrations above laboratory detection limits in any of the groundwater samples analyzed. Laboratory analytical results did identify detections of total chromium, total copper, total nickel, and total zinc in each of the groundwater samples analyzed. Of these detections, only nickel exceeded the applicable Class GA standards or guidance values in samples taken from two (2) of

the groundwater monitoring wells (samples MW-3 and MW-4). These results are similar to the previous data for samples collected in March 2010.

Based on laboratory analytical results, it was concluded that metals were below Class GA standards or guidance values, except for nickel concentrations in two (2) groundwater samples. It was also concluded that it appears that the extent of groundwater contamination is limited to the drainage swale area east of the GSP facility building, based on laboratory analytical results obtained during this, and past, groundwater sampling events and the presumed groundwater flow direction.

## 2.6 Construction Completion Report

An Emergency Remedial Work Plan (Work Plan, June 2013) was prepared by GHD to address certain work associated with the excavation and removal of soils from the existing Bridge Street Swale in connection with the development of the area by others. The Work Plan outlined necessary activities that needed to be implemented during development of the area by others in order to satisfy the Brownfield Cleanup Agreement. The Work Plan pertained to the Bridge Street Swale from the area immediately adjacent to Bridge Street and extending north approximately 500 feet.

The Work Plan provided details on survey requirements, buried culvert cleaning, swale excavation techniques, work sequencing, backfilling requirements, and required project documentation among others. The Work Plan stated that work was to be completed in accordance with an approved health and safety plan and in accordance with a community air monitoring plan. The Work Plan was approved by the NYSDEC on June 12, 2013. Applicable excerpts from the Work Plan are included in Attachment B-5.

The emergency remedial actions were completed in accordance with the NYSDEC-approved Emergency Remedial Work Plan during the spring and summer of 2014. A Construction Completion Report, which documented the emergency remedial activities, was prepared by GHD in January 2016 and applicable excerpts are included in Attachment B-8.

Emergency remedial actions included:

- cleaning and flushing of the existing buried culvert (AOC-3) located south (“up-stream”) of AOC-4
- excavating contaminated soil/sediment in the Bridge Street Swale, the Main Swale, and the Chimney Plaza Swale
- backfilling the swales with structural fill to grades required by the development activities.

Culvert flushing and cleaning activities began at the southern end of the buried culvert pipe adjacent to the GSP facility and progressed to the north from one catch basin to the next. As the pipe cleaning progressed, jetting water and sediment were removed at each catch basin via a vacuum truck. A buried box culvert, which receives discharges from stormwater drains along Bridge Street as well as the culvert pipe associated with AOC-3, is located immediately adjacent to Bridge Street. The box culvert’s discharge pipe discharges into the Bridge Street Swale on the north side of Bridge Street. The sediment accumulated in this box culvert was also removed and the box culvert flushed with clean water that was collected via the vacuum truck. Recovered water and suspended solids were placed in two (2) frac tanks staged at the development site adjacent to Bridge Street, and recovered sediment was placed in an isolated portion (i.e., coffer dams) of the Main Swale to be removed with subsequent swale excavation activities. In total, approximately 31,255 gallons of water, including jetting water, was removed from the culvert pipe and catch

basins. The water was characterized and appropriately disposed of off-site. Approximately 20 cubic yards (approximately 15 tons) of residual solids were removed from the bottom of the frac tank, placed in a lined roll-off container, characterized, and appropriately disposed of off-site.

Excavation of the swales began at the discharge of the buried culvert pipe and progressed parallel to Bridge Street and then north (“downstream”) to the edge of the proposed development site. Discrete areas of the swales were isolated from the remainder of the swales by placing earthen coffer dams across the swales to the north and west. The area was dewatered by pumping water from the area into the Main Swale and soil was excavated from the swale and transported via off-road dump truck to the dewatering/containment area on-site. Following excavation, end-point soil samples were taken and analyzed for chromium (total and hexavalent), copper (total), cyanide (total), and nickel (total). Following the completion of excavation activities, none of the end-point soil samples identified contaminants of concern at concentrations above Protection of Ecological Resources SCOs, with the exception of one (1) isolated exceedance for hexavalent chromium, and backfilling of the swales to allow for the development activities to proceed was approved by the NYSDEC.

Excavated materials were staged in an on-site containment/dewatering area, were characterized, and were transported for off-site disposal at a permitted facility. In total, approximately 1,000 tons of contaminated soil/sediment was taken to Seneca Meadows landfill for disposal.

## 2.7 Supplemental Sampling Activities

GHD personnel conducted installation and development of a replacement groundwater monitoring well for MW-8, sampling of seven (7) of the eight (8) permanent groundwater monitoring wells (MW-1 through MW-5 and MW-7 and MW-8), inspection of AOC-3 stormwater catch basins, sediment sampling in the Bridge Street Swale, and sediment sampling in the AOC-4 swale in 2016 in accordance with the NYSDEC approved Work Plan (GHD, July 15, 2016). The objectives of the supplemental sampling activities were to further refine the nature and extent of soil/sediment and groundwater contamination in order to develop appropriate remedial actions. The methods and findings of the supplemental sampling were submitted to the NYSDEC in the Supplemental Sampling Activities Summary Letter Report (GHD, October 3, 2016).

### 2.7.1 Groundwater

Groundwater samples were analyzed for the full list of contaminants identified in the BCP. The groundwater analytical results indicated there were no identified volatile organic compounds (VOC's), or semi-volatile organic compounds (SVOCs) that were considered contaminants of concern for the Site (see Figures and Tables in Attachment B-9). For the contaminants of concern, there were no exceedances for copper, total chromium, hexavalent chromium or cyanide.

The following analytes were identified at concentrations that exceed applicable groundwater standards or guidance values:

- Arsenic (MW-7)
- Barium (MW-1 and MW-4)
- Iron (all samples)
- Magnesium (MW-1, MW-2, MW-3, MW-8, and Duplicate)
- Manganese (MW-2, MW-3, MW-4, MW-7, and Duplicate)

- Nickel (MW-3, MW-4, and Duplicate)
- Sodium (all samples)
- Total PCBs (MW-4)

The detected iron, magnesium, manganese, and sodium concentrations are likely naturally occurring earth metals based on the widespread occurrence at the Site. The remainder of the data is similar to historical sampling events and indicates that migration of metals contaminants of concern from the historic release area via groundwater is limited. Additional groundwater and soil sampling was recommended to assess the occurrence of arsenic in the groundwater sample taken from off-site well MW-7; PCB detected in the groundwater sample from off-site well MW-4; and the continued elevated nickel concentrations in on-Site well MW-3 (considered the upgradient monitoring well).

### 2.7.2 Soil/Sediment

The inspection of the catch basins associated with AOC-3 during the supplemental sampling activities completed during August 2016 did not identify any appreciable accumulation of sediment in the sump of the catch basins.

A representative sediment sample was taken in the vicinity of the discharge of the stormwater pipe on the north side of Bridge Street (within the area excavated during the Community Bank development) by compositing three (3) grab samples taken across the width of the swale. The three (3) grab samples consisted of the upper 6 inches of sediment and were composited into a single sample for laboratory analysis.

The composite sample was analyzed for total chromium, total copper, total nickel, hexavalent chromium, and total cyanide. Laboratory analytical results for the Bridge Street Swale sediment sample were compared to the Protection of Ecological Resources SCOs. One analyte, total chromium (55 mg/kg), was identified at a concentration that exceeded the applicable Protection of Ecological Resources SCO of 41 mg/kg.

The detected concentration in the composite sample is similar to total chromium concentrations detected in background samples taken in proximity to the site as identified in the Background Sediment Sampling Letter Report (GHD, October 24, 2013). This portion of the Bridge Street Swale was previously excavated during the Community Bank development activities (Construction Completion Report-AOC-3 and AOC-4, GHD, January 2016).

In addition, three (3) sediment samples were taken from the upper 6 inches of sediment at each of seven (7) sample transects spaced at approximately 100-foot intervals along the portion of the main swale extending north from the Community Bank development to the intersection of the Interstate 690 right-of-way. The three (3) samples taken along each transect for laboratory analysis consisted of one (1) from just below the edge of water on each side of the swale (as determined at the time of sampling) and one (1) from the bottom of the swale at the approximate mid-point of the width at each location. A total of twenty-three (23) sediment samples, which includes two (2) blind field duplicate samples for QA/QC purposes, were analyzed for total chromium, total copper, total nickel, hexavalent chromium, and total cyanide.

Laboratory analytical results for the Downstream Swale sediment samples were compared to the Protection of Ecological Resources SCOs. Hexavalent chromium and cyanide were not detected at concentrations that exceed applicable Protection of Ecological Resources SCOs in any of the 23 samples taken. Total chromium, total copper, and total nickel were identified at concentrations that

exceed applicable Protection of Ecological Resources SCOs. The sample analytical results identified exceedances of Protection of Ecological Resources SCOs at each sample transect for at least one contaminant of concern. The concentrations are similar to those previously identified in this area by ERM during remedial investigation activities.

## 2.8 Summary of Remaining Contamination

Soil sample analytical results are compared to Unrestricted Use SCOs and groundwater, surface water, and release water sample analytical results are compared to New York State TOGS 1.1.1 Class GA Ambient Water Quality Standards or Guidance Values in accordance with DER-10. The following summary table only includes the lowest and highest identified concentrations for each analyte with a concentration detected above laboratory detection limits in at least one sample; see tables in the Attachments for a complete summary of laboratory analytical results.

Based on findings of the Remedial Investigation and subsequent investigations, contaminants that exceed identified standards for the Site, and the frequency of the exceedance relative to the number of samples taken and analyzed, are as follows:

AOC	Contaminant of Concern	Affected Media	Lowest Identified Concentration	Highest Identified Concentration	Number of Samples Exceeding Standards
AOC-1	Total Chromium	Soil	7.3 mg/kg	1,300 mg/kg	13 of 29
		Groundwater <sup>(1)</sup>	9.1 ug/L	181,000 ug/L	1 of 4
	Copper	Soil	11.9 mg/kg	87,400 mg/kg	21 of 28
		Groundwater <sup>(1)</sup>	6.8 ug/L	15.5 ug/L	0 of 4
	Nickel	Soil	10.5 mg/kg	10,700 mg/kg	18 of 28
		Groundwater <sup>(1)</sup>	74 ug/L	884 ug/L	2 of 4
Zinc	Soil	Non-Detect	745 mg/kg	2 of 28	
	Groundwater <sup>(1)</sup>	Non-Detect	238 ug/L	0 of 4	
Hexavalent Chromium	Soil	0.735 mg/kg	8.79 mg/kg	3 of 4	
	Soil	Non-Detect	2.82 mg/kg	0 of 29	
Cyanide	Groundwater <sup>(1)</sup>	Non-Detect	78.2 ug/L	0 of 4	
	Soil	Non-Detect	Non-Detect	Non-Detect	Non-Detect
AOC-2	Total Chromium	Soil	8.47 mg/kg	4,100 mg/kg	57 of 99
		Release Water <sup>(2)</sup>	26,000 ug/L	55,000 ug/L	2 of 2
		Groundwater <sup>(3)</sup>	Non-Detect	389,000 ug/L	2 of 4

AOC	Contaminant of Concern	Affected Media	Lowest Identified Concentration	Highest Identified Concentration	Number of Samples Exceeding Standards
AOC-2	Hexavalent Chromium	Soil Release Water <sup>(2)</sup>	Non-Detect 57,000 ug/L	140 mg/kg 57,000 ug/L	16 of 31 1 of 1
	Copper	Soil Release Water <sup>(2)</sup>	7.8 mg/kg 110,000 ug/L	13,000 mg/kg 110,000 ug/L	44 of 99 1 of 2
		Groundwater <sup>(3)</sup>	Non-Detect	20 ug/L	0 of 4
	Cyanide	Soil	Non-Detect	903 mg/kg	2 of 83
		Groundwater <sup>(3)</sup>	Non-Detect	93.8 ug/L	0 of 4
Nickel	Soil Release Water <sup>(2)</sup>	7.6 mg/kg 110,000 ug/L	3,720 mg/kg 120,000 ug/L	62 of 99 2 of 2	
	Groundwater <sup>(3)</sup>	Non-Detect	1,880 ug/L	3 of 4	
Zinc	Soil Release Water <sup>(2)</sup>	11.8 mg/kg 180 ug/L	2,340 mg/kg 680 ug/L	17 of 70 0 of 2	
	Groundwater <sup>(3)</sup>	Non-Detect	371 ug/L	0 of 4	
AOC-3	Total Chromium	Soil	12.9 mg/kg	207 mg/kg	1 of 7
	Hexavalent Chromium	Soil	Non-Detect	1.12 mg/kg	1 of 7
	Copper	Soil	17.3 mg/kg	543 mg/kg	1 of 7
	Cyanide	Soil	Non-Detect	0.896 mg/kg	0 of 7
	Nickel	Soil	12.5 mg/kg	375 mg/kg	1 of 7
	Zinc	Soil	31.1 mg/kg	342 mg/kg	2 of 7
AOC-4 <sup>(4)</sup>	Total Chromium	Soil	5.51 mg/kg	1,080 mg/kg	57 of 121
		Surface Water <sup>(5)</sup>	Non-Detect	650 ug/L	8 of 13
	Hexavalent Chromium	Soil Surface Water <sup>(5)</sup>	Non-Detect Non-Detect	22 mg/kg 630 ug/L	23 of 68 3 of 6

AOC	Contaminant of Concern	Affected Media	Lowest Identified Concentration	Highest Identified Concentration	Number of Samples Exceeding Standards
AOC-4 <sup>(4)</sup>	Copper	Soil	5.47 mg/kg	7,170 mg/kg	64 of 121
		Surface Water <sup>(5)</sup>	Non-Detect	1,920 ug/L	9 of 13
	Cyanide	Soil	Non-Detect	22.7 mg/kg	0 of 121
		Surface Water <sup>(5)</sup>	Non-Detect	12 ug/L	0 of 12
Nickel	Soil	6.32 mg/kg	2,330 mg/kg	55 of 121	
	Surface Water <sup>(5)</sup>	Non-Detect	962 ug/L	8 of 13	
Zinc	Soil	30.6 mg/kg	981 mg/kg	23 of 63	
	Surface Water <sup>(5)</sup>	Non-Detect	120 ug/L	0 of 6	
Site-Wide Groundwater Quality Monitoring Network	Total Chromium	Groundwater	Non-Detect	29 ug/L	0 of 28
	Hexavalent Chromium	Groundwater	Non-Detect	14 ug/L	0 of 28
	Copper	Groundwater	Non-Detect	93 ug/L	0 of 28
	Nickel	Groundwater	Non-Detect	680 ug/L	8 of 28
	Zinc	Groundwater	Non-Detect	23 ug/L	0 of 28
	Arsenic	Groundwater	Non-Detect	63 ug/L	1 of 8
	Barium	Groundwater	91 ug/L	1,400 ug/L	2 of 8
	Iron	Groundwater	3,600 ug/L	15,300 ug/L	8 of 8
	Magnesium	Groundwater	28,400 ug/L	101,000 ug/L	5 of 8
	Manganese	Groundwater	54 ug/L	1,200 ug/L	5 of 8
	Sodium	Groundwater	94,500 ug/L	319,000 ug/L	8 of 8
	Total PCBs	Groundwater	Non-Detect	4.6 ug/L	1 of 8
	Methyl tert-butyl ether (MTBE)	Groundwater	Non-Detect	1.2 ug/L	0 of 8

(1) - AOC-1 groundwater results represent results of grab groundwater samples taken from temporary groundwater monitoring wells installed through the concrete slab of the building and do not represent Site-wide groundwater quality.



(2) - Release Water indicates samples taken from water ponded in the area of the initial release from the building and do not represent Site-wide surface water or groundwater quality.

(3) - AOC-2 groundwater samples represent results of grab groundwater samples taken from temporary groundwater monitoring wells installed in test pits dug along the exterior wall of the building in the vicinity of the release and do not represent Site-wide groundwater quality.

(4) - Since the Site investigations were completed, a portion of AOC-4 was remediated under the NYSDEC-approved Emergency Remedial Work Plan (GHD, June 2013). As a result, some of the concentrations identified above may no longer be present in AOC-4.

(5) - Surface Water results represent results of surface water samples taken from the Bridge Street Swale area after the water impacted by the initial release, which identified much higher concentrations on contaminants of concern, was pumped out and treated for off-site disposal.

## 2.9 Fish and Wildlife Resources Impact Analysis

The purpose of conducting a Fish and Wildlife Resources Impact Analysis (FWRIA) on-Site was to identify, describe, and evaluate existing or predicted fish and wildlife resources associated with the Site and its surroundings, and assess what impacts, if any, may originate from or result from the disturbance of the Site. The FWRIA for the Site was conducted by ERM.

Results of the FWRIA indicated that there are seven (7) cover types within ½-mile of the Site. These cover types include:

- Urban land;
- Mowed roadside/pathway;
- Mowed lawns with trees;
- Paved roadways;
- Forested wetland;
- Ditch/Artificial intermittent stream;
- Stream banks; and
- Riparian zone.

Results also indicated that most precipitation will leave the Site as runoff that flows to the GSP Swale and/or Bridge Street Swale, which ultimately connects to the NYS Route 690 swale north of the Site. No obvious signs of contaminant-induced stress were observed at the Site. The FWRIA concluded that a biologically driven migration/exposure pathway exists since fish and wildlife under current conditions are potentially exposed to affected media in AOC-2 and AOC-4. The pathway consists of the potential for uptake of contaminants through direct contact and ingestion, which includes the possibility of bioaccumulation. This pathway has not been verified at the Site, but the potential exists. Although AOC-4 was identified as having the potential for fish and wildlife habitat the area is periodically altered and disturbed during routine maintenance of the drainage swale that can entail removal of standing water and dredging of soils/sediment.

Fish and wildlife resources were determined to be minimal at and in the areas immediately surrounding the Site. Concentrations in excess of Protection of Ecological Resources SCOs in AOC-4 and Commercial Use SCOs in AOC-2 were identified in soil samples taken from AOC-2 and AOC-4. As a result, it was proposed by ERM that soil in AOC-2 and AOC-4 be excavated to preclude the potential exposure scenario outlined above and to eliminate potential future migration of, and exposure to, contaminants of concern.

## 2.10 Qualitative Human Health Exposure Assessment

The potential for human receptors to be exposed to contaminants that exist on-Site is based on current and reasonably anticipated future Site uses. As previously discussed, based on the historic release chromium, copper, cyanide, nickel, and zinc have been identified as the contaminants of concern (COCs) at the Site.

Under existing Site conditions, a potentially complete exposure pathway exists for Site soils based on direct contact, ingestion, and inhalation. Based on current Site conditions, possible on-Site receptors include current and future employees (currently limited as there are no ongoing operations), developers/Site users, public and private utility workers, maintenance workers, trespassers, and remedial contractors. Future on-Site exposure pathways and receptors are the same, if no remedial action is performed in these areas.

If remedial action is performed, exposure pathways will likely increase for a short duration during remedial action, after which they can be greatly reduced or eliminated. To limit exposure during remedial action, all work would be performed in accordance with a Site-specific health and safety plan and a community air monitoring plan.

Under existing Site conditions, a potentially complete exposure pathway does not exist for Site groundwater based on direct contact and ingestion. Based on current Site conditions, possible on-Site receptors include current or future employees (currently limited as there are no ongoing operations), developers/Site users, public and private utility workers, maintenance workers, trespassers, and remedial contractors; however, there is minimal potential for contact with, or ingestion of, contaminated groundwater due to the limited area of groundwater impacts and the fact that there are no groundwater users or water supply wells at, or in the vicinity of, the Site.

Future on-Site exposure to groundwater could potentially occur during ground intrusive work through contact with, or ingestion of, contaminated groundwater. Possible future on-Site receptors would include Site construction and/or remedial workers during remedial action, public and private utility workers, and future developers. To limit exposure during remedial action, all work would be performed in accordance with a Site-specific health and safety plan and a community air monitoring plan. It is unlikely that future groundwater users or water supply wells would be present at the Site since the Site and surrounding areas are serviced by a public water supply system.

# 3. Remedial Goals and Remedial Action Objectives

## 3.1 Overview

The review of remedial goals and action objectives are based on the identified contaminants of potential concern, which are primarily heavy metals, including total chromium, hexavalent chromium, copper, and nickel. In addition, zinc, which was not identified as a metal directly associated with the release, and cyanide were requested by the NYSDEC to be included as contaminants of potential concern based on the initial findings of the RI. Because these are inorganic compounds, the potential exposure via soil gas or vapors is precluded. The remedial goals and action objectives are focused on exposure pathways associated with groundwater, soil/sediment, and surface water. The following sections provide an overview of each AOC's remedial goals and remedial action objectives.

## 3.2 AOC-1

The overall remedial goal for AOC-1 – Sub-Slab Area (Figure 2 in Attachment B-3) is to protect human health and the environment from AOC-related contamination in a manner that is consistent with current, intended, and reasonably anticipated future uses of the AOC. The appropriate remedial action to meet these goals depends on the nature and extent of contamination, the planned future uses of the AOC, and the existence of exposure pathways to contamination relative to the planned uses. Based on previous uses and current zoning of the Site, the reasonable anticipated future use of this AOC is for commercial or industrial use. There is no identified surface water located within AOC-1 and therefore is not included in the RAO goals. In addition, the identified contaminants of concern do not include VOCs or SVOCs and therefore the potential for exposure to soil vapor is precluded as there is no identified source. As such RAOs for soil vapor are not considered for AOC-1.

In order to achieve AOC-1 remedial goals, the following Remedial Action Objectives (RAOs) have been identified:

- Groundwater
  - RAOs for Public Health Protection
    - Prevent ingestion and/or direct contact with potentially contaminated groundwater with contaminant levels that exceed New York State drinking water standards or guidance values.
  - RAOs for Environmental Protection
    - Restore groundwater to pre-disposal or pre-release conditions, to the extent practicable.
- Soil
  - RAOs for Public Health Protection
    - Prevent ingestion and/or direct contact with potentially contaminated soils that exceed Commercial Use SCOs.
  - RAOs for Environmental Protection

- Prevent migration of contaminants that would result in groundwater or surface water contamination
- Prevent impacts to biota from ingestion and/or direct contact with soil causing toxicity or impacts from bioaccumulation through the terrestrial food chain.

Remedial alternatives are evaluated in this RAA to review if they achieve the identified RAOs. Because AOC-1 remedial objectives are related to contaminants in soil and groundwater, the alternatives evaluated include:

- Restoration to Pre-Disposal or Unrestricted Conditions (Alternative 1, Figure 4-1)
- Restoration to Commercial Uses with Site Management via Soil Cover Engineering Controls (ECs) and Institutional Controls (ICs) (Alternative 2, Figure 4-2).

Restoration to Pre-Disposal or Unrestricted Conditions allows for all potential uses to occur in AOC-1.

The Restoration to Commercial Uses with Site Management alternative will allow for the following commercial uses of AOC-1, or higher industrial uses if allowed by local zoning, in accordance with *DER-10 Technical Guidance for Site Investigation and Remediation* (NYSDEC, May 2010):

- The commercial use category anticipates use by businesses with the primary purpose of buying, selling, or trading of merchandise or services. The commercial use category:
  - Restricts the use to commercial activities including the buying and/or selling of goods or services, or other uses identified below
  - Requires a SMP to manage remaining soil contamination and institutional/engineering controls at the site
  - Is the appropriate use category for the following site uses:
    - Health care facilities, including hospitals, clinics, etc.
    - College academic and administrative facilities
  - Allows for passive recreational, which includes recreational uses with limited potential for soil contact, such as:
    - Artificial surface fields
    - Outdoor tennis or basketball courts
    - Other paved recreational facilities used for roller hockey, roller skating, shuffle board, etc.
    - Outdoor pools
    - Indoor sports or recreational facilities
    - Golf courses
    - Paved (raised) bike or walking paths.

### 3.3 AOC-2

The overall remedial goal for AOC-2 – GSP Swale (Figure 2 in Attachment B-3) is to protect human health and the environment from AOC-related contamination in a manner that is consistent with current, intended, and reasonably anticipated future uses of the AOC. The appropriate remedial

action to meet these goals depends on the nature and extent of contamination, the planned future uses of the AOC, and the existence of exposure pathways to contamination relative to the planned uses. Based on previous uses and current zoning of the Site, the future contemplated use of AOC-2 is for commercial or industrial use, which is consistent with its current function as a stormwater conveyance swale that directs stormwater into the Town of DeWitt stormwater collection system (Bridge Street Drainage District).

Currently a portion of AOC-2 is located on the adjacent property not owned by GSP. GSP and the adjacent property owner have executed a Letter of Intent (LOI) to acquire the land that encompasses AOC-2. It is planned to incorporate the additional property into the BCP Site to be subject to an environmental easement, which will allow for placement of engineering and institutional controls.

In addition, the identified contaminants of concern do not include VOCs or SVOCs and therefore the potential for exposure to soil vapor is precluded as there is no identified source. As such RAOs for soil vapor media are not considered for AOC-2.

In order to achieve AOC-2 remedial goals, the following RAOs have been identified:

- Groundwater
  - RAOs for Public Health Protection
    - Prevent ingestion and/or direct contact with potentially contaminated groundwater with contaminant levels that exceed New York State drinking water standards or guidance values.
  - RAOs for Environmental Protection
    - Restore groundwater to pre-disposal or pre-release conditions, to the extent practicable.
- Soil/Sediment
  - RAOs for Public Health Protection
    - Prevent ingestion and/or direct contact with potentially contaminated soils that exceed Commercial Use SCOs.
  - RAOs for Environmental Protection
    - Prevent migration of contaminants that would result in groundwater or surface water contamination
    - Prevent impacts to biota from ingestion and/or direct contact with soil causing toxicity or impacts from bioaccumulation through the terrestrial food chain.
- Surface Water
  - RAOs for Public Health Protection
    - Prevent ingestion and/or direct contact with potentially contaminated surface water that exceeds New York State Ambient Water Quality Standards or guidance values.
  - RAOs for Environmental Protection
    - Prevent migration of contaminants that would result in groundwater, surface water, or sediment contamination

- Prevent impacts to biota from ingestion and/or direct contact with surface water causing toxicity or impacts from bioaccumulation through the terrestrial food chain.

Remedial alternatives are evaluated in this RAA to review if they achieve these RAOs. Because AOC-2 remedial objectives are related to contaminants in soil/sediment, groundwater, and surface water, the alternatives evaluated include:

- Restoration to Pre-Disposal or Unrestricted Conditions (Alternative 1, Figures 5-1 and 5-2)
- Restoration to Commercial Uses with Site Management via Soil Cover ECs and ICs (Alternative 2, Figures 5-3 and 5-4).

Restoration to Pre-Disposal or Unrestricted Conditions allows for all potential uses to occur in AOC-2.

Restoration to Commercial Uses with Site Management will allow for the following commercial uses of AOC-2, or higher industrial uses if allowed by local zoning, in accordance with *DER-10 Technical Guidance for Site Investigation and Remediation* (NYSDEC, May 2010):

- The commercial use category anticipates use by businesses with the primary purpose of buying, selling, or trading of merchandise or services. The commercial use category:
  - Restricts the use to commercial activities including the buying and/or selling of goods or services, or other uses identified below
  - Requires a SMP to manage remaining soil contamination and institutional/engineering controls at the site
  - Is the appropriate use category for the following site uses:
    - Health care facilities, including hospitals, clinics, etc.
    - College academic and administrative facilities
  - Allows for passive recreational, which includes recreational uses with limited potential for soil contact, such as:
    - Artificial surface fields
    - Outdoor tennis or basketball courts
    - Other paved recreational facilities used for roller hockey, roller skating, shuffle board, etc.
    - Outdoor pools
    - Indoor sports or recreational facilities
    - Golf courses
    - Paved (raised) bike or walking paths.

### 3.4 AOC-3

The overall remedial goal for AOC-3 – Buried Culvert Pipe (Figure 2 in Attachment B-3) is to protect human health and the environment from AOC-related contamination in a manner that is consistent with current, intended, and reasonably anticipated future uses of the AOC. The appropriate remedial action to meet these goals depends on the nature and extent of contamination, the

planned future uses of the AOC, and the existence of exposure pathways to contamination relative to the planned uses. The primary media of concern is the residual solids that may have been transported via stormwater from AOC-2 and collected in the stormwater pipe. The future contemplated use of this AOC is for commercial uses, based on current zoning of the property and its use for stormwater management and conveyance to the Town of DeWitt Bridge Street Drainage District.

There is no identified surface water body located within AOC-3 and therefore is not included in the RAO goals. Based on Site groundwater data, the contaminants of potential concern do not appear to be migrating from the BCP Site and therefore, RAOs for groundwater are not included for AOC-3. In addition, the identified contaminants of concern do not include VOCs or SVOCs and therefore the potential for exposure to soil vapor is precluded as there is no identified source associated with the Site. As such RAOs for soil vapor are not considered for AOC-3.

In order to achieve AOC-3 remedial goals, the following RAOs have been identified:

- Soil
  - RAOs for Public Health Protection
    - Prevent ingestion and/or direct contact with potentially contaminated soils.
  - RAOs for Environmental Protection
    - Prevent migration of contaminants that would result in groundwater, surface water, or sediment contamination
    - Prevent impacts to biota from ingestion and/or direct contact with soil causing toxicity or impacts from bioaccumulation through the terrestrial food chain.
- Residual Solids in Buried Culvert Pipe
  - RAOs for Public Health Protection
    - Prevent ingestion and/or direct contact with potentially contaminated solids
    - Prevent migration of potentially contaminated solids that could result in groundwater, surface water, or downgradient sediment contamination.
  - RAOs for Environmental Protection
    - Prevent migration of contaminants that could result in groundwater, surface water, or downgradient sediment contamination
    - Prevent impacts to biota from ingestion and/or direct contact with solids causing toxicity or impacts from bioaccumulation through the terrestrial food chain.

Remedial alternatives are evaluated in this RAA to review if they achieve these RAOs. Because AOC-3 remedial objectives are related to contaminants in soil and residual solids in the culvert pipe, the alternatives evaluated include:

- Restoration to Pre-Disposal or Unrestricted Conditions (Alternative 1, Figure 6-1)
- No Further Action (Alternative 2).

Restoration to Pre-Disposal or Unrestricted Conditions allows for all potential uses to occur in AOC-3.

The No Further Action alternative would allow for the current use of the AOC as a stormwater conveyance pipe. The Emergency Remedial Work Plan (GHD, June 2013) included the flushing and removal of sediment from the drainage culvert from the GSP swale to the discharge at Bridge Street. This work was associated with the development of a Community Bank facility adjacent to the Bridge Street Swale and was completed in the spring of 2014. Work activities were documented in a Construction Completion Report (CCR), which was submitted to the NYSDEC for their review.

### 3.5 AOC-4

The overall remedial goal for AOC-4 – Bridge Street Swale (Figure 4 in Attachment B-2) is to protect human health and the environment from AOC-related contamination in a manner that is consistent with current, intended, and reasonably anticipated future uses of the AOC. The appropriate remedial action to meet these goals depends on the nature and extent of contamination, the planned future uses of the AOC, and the existence of exposure pathways to contamination relative to the planned uses. The future contemplated use of this AOC is, based on current zoning of the property and the use of the swale for stormwater management by the Town of DeWitt (Bridge Street Drainage District), National Grid, and the NYSDOT ROW. The NYSDEC approval of the Emergency Remedial Work Plan (GHD, June 2013) included a NYSDEC request to achieve Protection of Ecological Resources SCOs in those areas of the swale that were not being backfilled as part of the Community Bank development, as well as portion further “downstream” (NYSDEC, June 12, 2013).

In order to achieve AOC-4 remedial goals, the following RAOs have been identified:

- Soil/Sediment
  - RAOs for Public Health Protection
    - Prevent ingestion and/or direct contact with potentially contaminated soils that exceed Protection of Ecological Resources SCOs.
  - RAOs for Environmental Protection
    - Prevent migration of contaminants that would result in groundwater or surface water contamination
    - Prevent impacts to biota from ingestion and/or direct contact with soil causing toxicity or impacts from bioaccumulation through the terrestrial food chain.
- Surface Water
  - RAOs for Public Health Protection
    - Prevent ingestion and/or direct contact with potentially contaminated surface water that exceeds New York State Ambient Water Quality Standards or guidance values.
  - RAOs for Environmental Protection
    - Prevent migration of contaminants that would result in groundwater or surface water contamination
    - Prevent impacts to biota from ingestion and/or direct contact with surface water causing toxicity or impacts from bioaccumulation through the terrestrial food chain.



Remedial alternatives are evaluated in this RAA to review if they achieve these RAOs. Because AOC-4 remedial objectives are related to inorganic contaminants in soil/sediment and surface water, the alternatives evaluated include:

- Restoration to Pre-Disposal or Unrestricted SCO Conditions (Alternative 1, Figures 7-1a, 7-1b, 7-2a, and 7-2b)
- Soil/Sediment removal from the swale to Protection of Ecological Resources SCOs (Alternative 2, Figures 7-3a, 7-3b, 7-4a, and 7-4b).

Restoration to Pre-Disposal or Unrestricted SCO Conditions (Alternative 1) and Restoration to Protection of Ecological Resources SCO Conditions (Alternative 2) would both allow for all potential uses to occur in AOC-4 and would be protective of fish and wildlife.

## 4. AOC-1

### 4.1 Remedial Alternatives Analysis

As identified in the RAOs, the remedial approach for AOC-1 is focused on soil and groundwater contaminants and the potential exposures to humans and the environment through direct contact and/or ingestion. Data collected during the RI indicate that samples taken from eight (8) sub-slab soil borings exceed the Commercial Use SCO for copper (soil boring samples B-4, B-8, B-12, B-341, B-342, and B-343) and nickel (soil boring sample B-1, B-4, B-8, B-10, B-12, B-341, B-342, and B-343). The exceedances occur from just beneath the bottom of the slab to a depth of approximately 3-feet bgs. Potential for direct contact and/or ingestion of these soils is limited by the fact that they occur under the building's concrete slab.

No specific remedial actions are proposed relative to groundwater for this AOC, since RI data indicate that groundwater impacts are likely limited to an isolated area of AOC-1 and AOC-2. In addition, on-Site and off-Site contact with groundwater is effectively preempted by the fact that the Site, and surrounding areas, are serviced by a municipal water supply.

This RAA identifies and compares potential AOC specific remedies. In accordance with DER-10, the alternatives to be evaluated for AOC-1 are: Restoration to Pre-Disposal or Unrestricted Conditions, and Restoration to Commercial Uses with Site Management.

The proposed alternatives are each evaluated and compared in terms of nine (9) specific criteria identified in 6 NYCRR Part 375-1.8(f), including:

- Compliance with standards, criteria, and guidance (SCGs)
- Protection of human health and the environment
- Short-term impact and effectiveness
- Long-term effectiveness and permanence
- Reduction of toxicity, mobility, or volume of contamination
- Implementability
- Cost effectiveness
- Land use
- Community acceptance.

The ninth criterion, community acceptance, will be further evaluated during public comment periods when feedback may be provided in relation to the proposed remedial alternative. The selected remedial alternative should produce a tangible benefit to the local community by achieving RAOs consistent with the current and reasonably anticipated future use of AOC-1.

The following is an overview and a comparative evaluation of the two (2) alternatives for AOC-1, with respect to the nine (9) evaluation criteria.

#### 4.1.1 Restoration to Pre-Disposal or Unrestricted Conditions Alternative

A Restoration to Pre-Disposal or Unrestricted Conditions alternative would maximize the range of potential land use scenarios for AOC-1. This alternative would require a remedial approach that would result in no further restrictions to AOC-1 use (i.e. the level of cleanup should permit all types

of future reuse scenarios) and no institutional/engineering controls to address exposure and achieve the RAOs. However, it would allow for short-term groundwater use restrictions to be placed on AOC-1.

A Restoration to Pre-Disposal or Unrestricted Conditions alternative requires that AOC-1 remediation be completed to meet Unrestricted Use SCOs, thereby meeting SCGs for soils. This would permanently remove the volume of contaminated soils that exists in AOC-1 by requiring excavation of soil across the majority of the AOC to achieve Unrestricted Use SCOs, an estimated depth of 1.5- to 4-feet (Figure 4-1). This would require that a remedial design be prepared for the AOC and submitted to NYSDEC for review and acceptance, as well as preparation of contract documents and selection of a contractor. To accomplish this alternative, the building would need to be razed, groundwater would need to be managed, excavated soils would need to be transported and disposed of off-Site, an equivalent amount of off-Site soil would need to be imported to reestablish grades, and the building would have to be replaced in order to allow for commercial activities to occur in the AOC. It is assumed that the backfill soil would include general soil fill overlain by 6- to 12-inches of gravel sub-base, which would be covered by a minimum of 6-inches of concrete. The general soil fill must meet the following criteria:

- Requirements set forth in 6 NYCRR Part 375-6.7(d) and DER-10 Section 5.4(e)
- Be free of extraneous debris or solid waste
- Consist of soil or other unregulated material as set forth in 6 NYCRR Part 360
- Will not exceed the allowable constituent levels for imported fill or soil for the use of the AOC (Unrestricted Use SCOs).

Once the remedial action is completed, a Final Engineering Report (FER) would need to be prepared that certifies that the remedial action was completed in accordance with an approved Remedial Work Plan or Remedial Design Document. The FER would summarize the remedial activities, include laboratory analytical data, and would be certified by a Professional Engineer licensed in New York State.

This alternative would eliminate the potential risk associated with direct human contact with contaminated soil, and would provide a benefit in relation to potential wildlife exposure by removing contaminated media from the AOC.

This remedy would create short-term risks associated with soil excavation, off-Site transport and disposal of contaminated soil, and transport of clean soil fill to the AOC; however, long-term risk associated with site contamination would be minimal. For this remedy, excavated soil would need to be transported to a facility permitted to receive and manage the soil, which would generate increased truck traffic on local roadways. An equivalent amount of off-Site soil would need to be hauled to the AOC to backfill the excavation, which would add to the increased truck traffic.

It is determined that the Restoration to Pre-Disposal or Unrestricted Conditions alternative is cost prohibitive and not feasible for the Site due to the presence of the Site building, and the costs associated with razing the building, remediating the AOC, and rebuilding the building to allow for future commercial use of the AOC.

#### 4.1.2 Commercial Uses with Site Management Alternative

The remedial approach for Commercial Uses with Site Management alternatives would allow for commercial or industrial use of AOC-1. This alternative would require a remedial approach that would meet Commercial Use SCOs in AOC-1 and would allow for institutional/engineering controls

to address potential exposure and achieve the RAOs. It would also allow a groundwater use restriction to be placed on AOC-1.

This alternative for AOC-1 would include the following controls:

- Engineering Controls – Engineering controls for the AOC would include a soil cover system to protect against potential human contact with contaminated soils remaining in place. A soil cover currently exists in AOC-1 in the form of the building’s concrete slab. The requirements for maintaining the engineering control (i.e. soil cover) will be described in a SMP, which will be referenced in the Environmental Easement. The Environmental Easement and SMP will require on-going annual certification of the engineering controls effectiveness, unless otherwise provided in writing by the NYSDEC. The annual certification will be signed by a Professional Engineer or by a qualified environmental professional as approved by the NYSDEC. For purposes of this RAA, the assumed life span of the engineering controls is 30 years.
- Institutional Controls – Institutional controls recorded in the form of an Environmental Easement for the controlled property would include:
  - Requirements that the remedial party or Site owner complete and submit to the Department a periodic certification of institutional and engineering controls in accordance with Part 375-1.8(h)(3)
  - Allowing the use and development of the controlled property for commercial or industrial uses as defined by Part 375-1.8(g), although land use is subject to local zoning laws
  - Restricting the use of groundwater as a source of potable or process water, without necessary water quality treatment as determined by the New York State Department of Health (NYSDOH) or County Department of Health
  - Prohibiting agriculture or vegetable gardens on the controlled property
  - Requiring compliance with the Department approved SMP.
- Site Management Plan - As part of the Environmental Easement, a SMP would be prepared to address how AOC-1 soil and groundwater would be characterized and handled for any future ground intrusive work that takes place in AOC-1 after the remedial action is complete. The SMP would also specify how the engineering controls (i.e. soil cover) are to be periodically inspected and maintained to preclude potential exposure to AOC-1 contaminants.
- These engineering/institutional controls will be identified in the Environmental Easement filed with the Onondaga County Clerk’s Office within 30 days of the NYSDEC’s acceptance of the Environmental Easement. A copy will be provided to NYSDEC certifying that the Environmental Easement was recorded by the County Clerk.

The combination of engineering and institutional controls would meet the stated RAOs for this AOC and support the current, intended, and reasonably anticipated future uses of the Site.

Once the remedial action is completed, a FER would need to be prepared that certifies that the remedial action was completed in accordance with an approved Remedial Work Plan or Remedial Design Document. The FER would summarize the remedial activities, include laboratory analytical data, and would be certified by a Professional Engineer licensed in New York State. A SMP and Environmental Easement would also need to be prepared, which outline ongoing Site inspection, maintenance, and reporting requirements and use restrictions.

This alternative would mitigate the potential risk associated with direct human contact and/or ingestion of contaminated soil by preventing future exposure through placement of a soil cover engineering control and implementation of institutional controls via an Environmental Easement.

This remedy would have no short-term risks associated with groundwater management, soil excavation, off-Site transport and disposal of contaminated soil, and transport of clean soil fill. Long-term risk due to potential contact with contaminated soil would be managed by maintaining the engineering controls and institutional controls.

It is estimated that the alternative for Commercial Uses with engineering and institutional controls with a SMP would have a capital cost of approximately \$20,000 (Table 4-1) to implement and an ongoing annual cost of approximately \$5,000 (Table 4-1) to maintain, inspect, and report on the soil cover engineering control. Based on these estimates, the Present Worth of this alternative would be approximately \$121,000, based on an estimated 30-year operating life of the engineering controls (Table 4-1).

## 4.2 Evaluation of Remedial Alternatives

This evaluation of alternatives compares the Restoration to Pre-Disposal or Unrestricted Conditions (Alternative 1), and the Commercial Uses with Site Management (Alternative 2) alternatives.

In accordance with BCP guidance, the selected remedy will provide protection of public health and the environment, taking into account the current, intended, and reasonably anticipated future land uses of the AOC.

An evaluation has been prepared to identify a suitable remedial action in accordance with 6 NYCRR Part 375-1.10(c)(1-6). In the specific context of the contemplated end use of the AOC, the selected remedy should be:

- Consistent with applicable SCGs
- Protective of public health and the environment
- Effective for both short-term and long-term
- Able to reduce toxicity, mobility, and volume of the hazardous constituents
- Feasible from implementability and cost effectiveness perspectives
- Reasonably anticipated to be acceptable to the local community.

### 4.2.1 Compliance with Standards, Criteria, and Guidance

A review of the SCGs documents pertinent to AOC specific conditions has been completed. The SCGs for soil are the 6 NYCRR Part 375-6.8(b) Unrestricted Use SCOs for Alternative 1 and the Commercial Use SCOs for Alternative 2.

Alternative 1 will meet the SCGs for all soil within the AOC boundary. Alternative 2 will comply with soil SCGs for the designated commercial use of the AOC even though copper in six (6) sub-slab soil samples and nickel in eight (8) sub-slab soil samples exceeded Commercial Use SCOs in the subsurface soils. These exceedances will be managed via a soil cover engineering control and Environmental Easement, which will preclude potential human contact with remaining contamination.

Since RI analytical data indicate groundwater quality is not significantly impacted outside of AOC-1 and/or AOC-2, it is unlikely that the soil removal required to meet Unrestricted Use SCOs would

provide a measurable improvement in groundwater quality compared to the soil cover engineering controls required by Alternative 2. In addition, Alternative 2 would restrict groundwater use at the AOC to eliminate any potential direct human exposure to groundwater impacts, which makes it equally protective.

#### 4.2.2 Protection of Human Health and the Environment

Each of the alternatives is protective of human health and the environment. Alternative 1 would remove soil contamination to meet soil SCGs, whereas Alternative 2 would leave some subsurface soils in place above Unrestricted Use SCOs below engineering controls, where it will not be accessible to humans. The SMP under Alternative 2 will provide further protection if soils are encountered during future intrusive activities in the AOC.

Each of the alternatives permit groundwater use restrictions and are equally protective of human health relative to groundwater exposure. As previously noted, AOC-1 groundwater is marginally impacted by the release with no significant off-site migration identified, so the significant soil removal required to meet Unrestricted Use SCOs is not likely to produce a measurable improvement to groundwater quality compared to Alternative 2.

#### 4.2.3 Short-Term Effectiveness

Alternative 1 would require removal of the existing building and concrete slab, excavation of soils that exceed Unrestricted Use SCOs, placement of clean fill to return the area to original grade, and replacement of the building and concrete slab. Alternative 2 would require maintaining the existing concrete building slab as an engineering control to preclude direct contact with potentially contaminated sub-slab soils. Future construction activities, if any, could potentially involve excavation and disturbance of subsurface soils or fill material that are left in place under Alternative 2.

Alternative 1 has a greater potential for short-term exposure to workers and the community due to the volume and duration of soil disturbance associated with the soil excavation, transport, and disposal of soil and building materials. There also exists a potential for airborne contamination (i.e. dust) to be released from AOC-1 under Alternative 1.

Each proposed alternative would include a Health and Safety Plan (HASP) and Community Air Monitoring Plan (CAMP) to identify requirements for action levels, personal protective equipment, and emergency procedures to address potential short-term impacts during remedial activities, which makes them both equally effective over the short-term. The SMP required under Alternative 2 will ensure that if ground intrusive work were completed in the future, soil and groundwater encountered in the AOC is properly characterized and managed in order to address potential exposure issues to AOC contaminants, and would also require implementation of a HASP and CAMP during future ground intrusive activities in the AOC.

Another short-term impact under Alternative 1 would be the increase in truck traffic on local roads as a result of hauling excavated soil from the AOC and hauling clean fill to the AOC. The increased truck traffic required by Alternative 1 could have a negative impact on local roadways and the local community. Alternative 2 would have no impact on truck traffic on local roads due to the fact that no soils would need to be removed from, or transported to, the AOC.

#### 4.2.4 Long-Term Effectiveness and Performance

Alternative 1 and Alternative 2 each provide a long-term and effective solution to potential AOC contamination in soil and groundwater, and will reduce human and environmental exposure to contaminants of potential concern (COPCs). Alternative 1 would provide a permanent solution due to the removal of all soils that do not meet Unrestricted Use SCOs.

Alternative 2 will require engineering/institutional controls to be recorded with the deed to the property via an Environmental Easement. These remedies are considered equally as effective and permanent as an Unrestricted Use remedy for the AOC based on the current, intended, and reasonably anticipated future commercial or industrial use of the Site. The SMP will be referenced in the Environmental Easement and will require annual certifications of all engineering and institutional controls and implementation of the SMP during future Site activities.

#### 4.2.5 Reduction of Toxicity, Mobility, and Volume

Alternative 1 would result in a greater reduction in the volume of soil COPCs in the AOC compared to Alternative 2 but it may not have a measurable effect on toxicity of soil COPCs compared to Alternative 2 since each alternative effectively mitigates exposure. During implementation of Alternative 1 the mobility of soil COPCs may be temporarily higher than that for Alternative 2 since Alternative 1 will require more extensive excavation and transportation of soils. Although Alternative 1 removes the potentially contaminated soil from the Site for off-site disposal, it does not effectively reduce the toxicity or volume of the inorganic contaminants, especially as they will likely be landfilled. Following implementation, there is not likely to be a difference in toxicity of AOC contaminants between the alternatives based on the current, intended, and reasonably anticipated future uses of the AOC.

Based on RI data, the soil COPCs have not significantly impacted groundwater as evidenced by concentrations detected in Site groundwater monitoring wells. As a result, neither alternative would likely have a significant impact on the toxicity or volume of COPCs identified in groundwater.

#### 4.2.6 Implementability

Technical and administrative tasks required to implement the alternatives are all technically achievable. The implementation of Alternative 1 would likely not be cost-effective for the planned end use of the AOC, due to costs associated with demolishing the Site building and handling, transporting, treating, and disposing of large volumes of soil. The total removal of potentially impacted soil is likely to be restricted by the presence of underground utilities resulting in some impacted soils being left behind. More significant short-term exposures are also created by the implementation of Alternative 1.

Alternative 1 would support the widest range of future AOC uses. Alternative 2 will not prevent or interrupt the productive use of the Site that is anticipated to be present in the foreseeable future. Installation and maintenance of the engineering/institutional controls under Alternative 2 are all readily implemented.

#### 4.2.7 Costs

Alternative 1 would involve removing from the AOC a significant quantity of soil to meet Unrestricted Use SCOs. Alternative 1 is determined unfeasible based on having to demolish the building in order to implement the remedy. As a result, no cost estimate was developed for this alternative. Implementation of Alternative 2 is estimated to have a capital cost of approximately \$20,000 and an

annual cost of approximately \$5,000 (Table 4-1). The Present Worth cost for Alternative 2 is approximately \$121,000 (Table 4-1), based on an estimated 30 year operating life span for the engineering controls (i.e. soil cover system).

Alternative	Capital Cost (A)	Annual Cost	Present Worth Annual Cost (B)	Present Worth (C)
<b>Alternative 2 – Restoration to Commercial Uses with Site Management via Soil Excavation</b>	\$20,000	\$5,000	\$100,942	\$121,000

Notes:  
 Estimated Present Worth (C) = A + B  
 Estimated Present Worth values rounded to the nearest \$1,000.

#### 4.2.8 Land Use

Alternative 1 would allow for all uses including higher uses (i.e. residential) that are not consistent with current zoning or neighboring land uses. Alternative 2 commercial or industrial uses are consistent with the current zoning and neighboring land uses. Current and foreseeable future neighboring land uses are consistent with commercial and industrial uses.

#### 4.2.9 Community Acceptance

Alternative 1 would provide a level of cleanup that exceeds what is necessary to support the AOC's intended commercial or industrial use, such that the additional work required to achieve the necessary cleanup may potentially reduce public acceptance. Alternative 1 would increase the duration of remediation work to excavate soils, cause an increase in construction traffic and noise, and create additional truckloads of soil to be hauled to and from the AOC. These potential nuisances would not be present during implementation of Alternative 2.

Alternative 2 coupled with current, intended, and reasonably anticipated future Site uses is aligned with community development interests.

In order to obtain the necessary community acceptance, the selected approach will be made available for public review and comment prior to initiating remedial activities.



## 5. AOC-2

### 5.1 Remedial Alternatives Analysis

As identified in the RAOs, the remedial approach for AOC-2 is focused on groundwater, soil and surface water contaminants and the potential exposures to humans and the environment through direct contact and/or ingestion and the potential migration of contaminants. A portion of AOC-2 is currently in the process of being acquired by GSP and incorporated into the BCP Site. This evaluation of alternatives for AOC-2 is based on the premise that the property will be purchased and incorporated into the BCP Site.

No specific remedial actions are proposed relative to groundwater for this AOC, since RI data and subsequent groundwater monitoring indicate that groundwater impacts are likely limited to the area of AOC-1 and AOC-2. In addition, on-Site and off-Site contact with groundwater is effectively preempted by the fact that the Site, and surrounding areas, are serviced by a municipal water supply.

Data collected during the RI indicate that soils that exceed the applicable Commercial Use SCOs occur throughout AOC-2 ranging from 0- to 6-feet bgs (Table 5-1 and Table 5-4 in Attachment B-1, Table 2 in Attachment B-2, and Figure 4 in Attachment B-3). COPCs in this area are primarily copper and nickel, but total chromium exceeds the applicable SCO in several samples adjacent to the area of release. Potential for direct contact and/or ingestion of these soils is limited due to the current use of this area and limited access due to fencing that surrounds AOC-2; however, remedial action to deal with the area is warranted to meet the remedial goals for AOC-2 to further limit potential exposure and/or migration via surface soils transported in stormwater flows.

Data collected during the RI also indicated that ponded stormwater in the GSP Swale Area previously exceeded applicable New York State Ambient Water Quality standards for total chromium, copper, nickel, and hexavalent chromium (Table 5-7 in Attachment B-1). Once identified, the impacted water was removed from the swale, treated, and discharged to the Onondaga County Waste Water Treatment Facility. The focus is on the mitigation of the potential for contaminated soils to migrate via stormwater flows in the swale and be transported downstream to other areas.

This RAA identifies and compares two (2) potential AOC remedies. In accordance with DER-10, the alternatives to be evaluated are: Restoration to Pre-Disposal or Unrestricted Conditions, and Restoration to Commercial Use with Site Management, which would allow for a commercial or industrial use of the AOC.

The proposed alternatives are each evaluated and compared in terms of nine (9) specific criteria identified in 6 NYCRR Part 375-1.8(f), including:

- Compliance with SCGs
- Protection of human health and the environment
- Short-term impact and effectiveness
- Long-term effectiveness and permanence
- Reduction of toxicity, mobility, or volume of contamination
- Implementability
- Cost effectiveness

- Land use
- Community acceptance.

The ninth criterion, community acceptance, will be further evaluated during public comment periods when feedback may be provided in relation to the proposed remedial alternative. The selected remedial alternative should produce a tangible benefit to the local community by achieving RAOs consistent with the current and reasonably anticipated future use of the AOC. The following is an overview of each alternative and a comparative evaluation of the two (2) alternatives for the AOC, with respect to the nine (9) evaluation criteria.

#### 5.1.1 Restoration to Pre-Disposal or Unrestricted Conditions Alternative

A Restoration to Pre-Disposal or Unrestricted Conditions alternative would maximize the range of potential land use scenarios for AOC-2. This alternative would require a remedial approach that would result in no further restrictions to AOC-2 use (i.e. the level of cleanup should permit all types of future reuse scenarios) and no institutional/engineering controls to address exposure and achieve the RAOs. However, it would allow for short-term groundwater use restrictions to be placed on AOC-2.

A Restoration to Pre-Disposal or Unrestricted Conditions alternative requires that AOC-2 remediation be completed to meet Unrestricted Use SCOs, thereby meeting SCGs for soils. This would permanently remove the volume of contaminated soils that exists in AOC-2 by requiring excavation of soil to an estimated depth of 0.5- to 8-feet bgs (Figure 5-1) across the majority of the AOC to achieve Unrestricted Use SCOs. The excavation of soils from this area would entail removal of approximately 2,700 cubic yards of soils. This would require that a remedial design be prepared for the AOC and submitted to NYSDEC for review and acceptance, as well as preparation of contract documents and selection of a contractor. To accomplish this alternative, groundwater and surface water would need to be managed, excavated soils would need to be transported and disposed of off-site, and an equivalent amount of off-site soil would need to be imported to the AOC to reestablish grades and promote drainage. It is assumed that the backfill soil would include general soil fill overlain by 4-inches of topsoil, which would be seeded to establish vegetative cover in areas that will not be underwater. The general soil fill must meet the following criteria:

- Requirements set forth in 6 NYCRR Part 375-6.7(d) and DER-10 Section 5.4(e)
- Be free of extraneous debris or solid waste
- Consist of soil or other unregulated material as set forth in 6 NYCRR Part 360
- Will not exceed the allowable constituent levels for imported fill or soil for the use of the AOC (Unrestricted Use SCOs).

Once the remedial action is completed, a FER would need to be prepared that certifies that the remedial action was completed in accordance with an approved Remedial Work Plan. The FER would summarize the remedial activities, include laboratory analytical data, and would be certified by a Professional Engineer licensed in New York State.

This alternative would eliminate the potential risk associated with ingestion and/or direct human contact with contaminated soil by removing contaminated media from the AOC.

For this remedy, groundwater and surface water would need to be managed during excavation. Excavated soil would need to be transported to a facility permitted to receive and manage the soil, which would generate increased truck traffic on local roadways. An equivalent amount of off-site soil

would need to be hauled to the AOC to backfill the excavation, which would add to the increased truck traffic.

This remedy would create short-term potential exposure risks associated with groundwater and surface water management, soil excavation, off-site transport and disposal of contaminated soil, and transport of clean soil fill to the AOC; however, long-term risks would be mitigated.

It is estimated that the Restoration to Pre-Disposal or Unrestricted Conditions alternative would have a capital cost of approximately \$763,000 (Table 5-1) to implement and no ongoing annual costs (Table 5-1) associated with the AOC once this alternative is completed. Therefore, the Present Worth of this alternative would be approximately \$763,000, based on an estimated 30-year operating life (Table 5-1).

#### 5.1.2 Restoration to Commercial Uses with Site Management Alternative

The Restoration to Commercial Uses with Site Management alternative requires that AOC-2 remediation be completed to meet Commercial Use SCOs with the placement of soil cover engineering controls, thereby meeting SCGs for soils. Because the AOC-2 area has exceedances of Commercial Use SCOs in the top 1 foot of soil (Figure 5-3), it is proposed to remove the top 1 foot of soil and replace it with clean off-site fill to preclude the potential for migration of potentially impacted surface soils via stormwater flows. This alternative would require that a remedial design be prepared for the AOC and submitted to NYSDEC for review and acceptance, as well as preparation of contract documents and selection of a contractor.

This alternative would remove the top 1 foot of soil from the majority of AOC-2 (Figure 5-4). The excavation of soils from this area would entail removal of approximately 500 cubic yards of soil. Stormwater and groundwater, if encountered, would need to be managed during excavation. Because of the shallow excavation (1 foot), it is less likely that groundwater will be encountered based on measured depths to groundwater in monitoring wells at the Site. Excavated soils would need to be disposed of off-site at a facility permitted to accept the material. A soil cover engineering control would be placed over the excavated area to a depth of 1 foot. Backfill would include placement of a demarcation layer overlain by either 1 foot of granular stone material as a drainage layer or 1 foot of general soil fill including a minimum of 4-inches of topsoil, which would be seeded to promote vegetative cover. The soil cover would be graded to promote positive drainage towards the existing catch basin inlet. The soil cover fill material must meet the following criteria:

- Requirements set forth in 6 NYCRR Part 375-6.7(d) and DER-10 Section 5.4(e)
- Be free of extraneous debris or solid waste
- Consist of soil or other unregulated material as set forth in 6 NYCRR Part 360
- Will not exceed the allowable constituent levels for imported fill or soil for the use of the AOC (Restricted-Residential Use SCOs).

This alternative for AOC-2 would also include the following:

- Engineering Controls – Engineering controls for the AOC would include the soil cover engineering control to preclude potential human and wildlife contact with contaminated soils that may remain in place (Figure 5-5). The soil cover engineering control will consist of a demarcation layer overlain by a minimum of 1-foot of clean soil. The requirements for maintaining the engineering control (i.e. soil cover) will be described in a SMP, which will be referenced in the Environmental Easement. The Environmental Easement and SMP will require on-going annual certification of the engineering controls effectiveness, unless

otherwise provided in writing by the NYSDEC. The annual certification will be signed by a Professional Engineer or by a qualified environmental professional as approved by the NYSDEC. For purposes of this RAA, the assumed life span of the engineering control is 30 years.

- Institutional Controls – Institutional controls recorded in the form of an Environmental Easement for the controlled property would:
  - Require that the remedial party or Site owner complete and submit to the Department a periodic certification of institutional and engineering controls in accordance with Part 375-1.8(h)(3)
  - Allow the use and development of the controlled property for commercial or industrial uses as defined by Part 375-1.8(g), although land use is subject to local zoning laws
  - Restrict the use of groundwater as a source of potable or process water, without necessary water quality treatment as determined by the NYSDOH or County Department of Health
  - Prohibit agriculture or vegetable gardens on the controlled property
  - Require compliance with the Department approved SMP.
- Environmental Easement - As part of the Environmental Easement, a SMP would be prepared to address how AOC-2 remaining soil and groundwater would be characterized and handled for any future ground intrusive work that takes place in the AOC after the remedial action is complete. The SMP would also specify how the engineering controls (i.e. soil cover) are to be periodically inspected, maintained, and certified to preclude potential exposure to AOC contaminants.
- These engineering/institutional controls will be identified in the Environmental Easement filed with the Onondaga County Clerk's Office within 30 days of the NYSDEC's acceptance of the Environmental Easement. A copy will be provided to NYSDEC certifying that the Environmental Easement was recorded by the County Clerk.

The combination of soil excavation and implementation of engineering/institutional controls would meet the stated RAOs for this AOC and support the current, intended, and reasonably anticipated future uses of the AOC.

Once the remedial action is completed, an FER would need to be prepared that certifies that the remedial action was completed in accordance with an approved Remedial Work Plan. The FER would summarize the remedial activities, include laboratory analytical data, and would be certified by a Professional Engineer licensed in New York State. A SMP would also need to be prepared that outlines ongoing AOC inspection, maintenance, and reporting requirements.

This alternative would mitigate the potential risk associated with direct human contact and/or ingestion of contaminated soil by removing a portion of the volume of contamination, placement of a soil cover engineering control, and implementation of an Environmental Easement. This alternative would also provide a benefit in relation to potential wildlife exposure by removing a portion of the contaminated media from the AOC and installing a soil cover engineering control.

For this remedy, stormwater would need to be managed during excavation. Groundwater could be encountered and will need to be managed as needed. Excavated soil would need to be transported to a facility permitted to receive and manage the soil, which would generate increased truck traffic on local roadways. An equivalent amount of off-site soil would need to be imported to the AOC to

backfill the excavation, which would further add to the increased truck traffic. However, these impacts would be greatly reduced for this alternative compared to the Restoration to Pre-Disposal or Unrestricted Conditions alternative based on the lesser volume of material that would need to be managed and disposed of and brought on-Site.

This remedy would create short-term risks associated with groundwater and surface water management, soil excavation, off-site transport and disposal of contaminated soil, and transport of clean soil fill to the AOC. However, these risks would be greatly reduced compared to Alternative 1 and long-term risk due to potential contact with contaminated soil would be effectively mitigated.

It is estimated that the Restoration to Commercial Uses with Site Management alternative would have a capital cost of approximately \$260,000 (Table 5-1) to implement and an ongoing annual cost of approximately \$31,000 (Table 5-1) to maintain, inspect, and report on the soil cover engineering control. Based on these estimates, the Present Worth of this alternative would be approximately \$484,000 (Table 5-1).

## 5.2 Evaluation of Remedial Alternatives

This evaluation of alternatives compares the Restoration to Pre-Disposal or Unrestricted Conditions (Alternative 1) and the Restoration to Commercial Uses with Site Management (Alternative 2) alternatives.

In accordance with BCP guidance, the selected remedy will provide protection of public health and the environment, taking into account the current, intended, and reasonably anticipated future land uses of the Site.

An evaluation has been prepared to identify a suitable remedial action in accordance with 6 NYCRR Part 375-1.10(c)(1-6). In the specific context of the contemplated end use of the AOC, the selected remedy should be:

- Consistent with applicable SCGs
- Protective of public health and the environment
- Effective for both short-term and long-term
- Able to reduce toxicity, mobility, and volume of the hazardous constituents
- Feasible from implementability and cost effectiveness perspectives
- Reasonably anticipated to be acceptable to the local community.

### 5.2.1 Compliance with Standards, Criteria, and Guidance

A review of the SCGs documents pertinent to AOC specific conditions has been completed. The SCGs for soil are the 6 NYCRR Part 375-6.8(b) Unrestricted Use SCOs for Alternative 1 and the Commercial Use SCOs for Alternative 2. Alternative 1 will meet the SCGs for all soil within the AOC boundary. Alternative 2 will comply with soil SCGs for the designated use of the AOC.

Since RI analytical data indicate groundwater quality is not significantly impacted by the release, it is unlikely that additional soil removal required to meet Unrestricted Use SCOs would provide a measurable improvement in groundwater quality compared to the soil removal required by Alternative 2. In addition, both Alternative 1 and Alternative 2 can restrict groundwater use at the AOC to eliminate any potential human exposure to groundwater impacts, which makes them equally protective, and the Site and surrounding areas are serviced by a municipal water supply.

### 5.2.2 Protection of Human Health and the Environment

Both Alternative 1 and Alternative 2 are protective of human health and the environment. Alternative 1 would remove soil contamination to meet soil SCGs, whereas Alternative 2 would leave some subsurface soils in place above Unrestricted Use SCOs below engineering controls, where it will not be readily accessible to humans or wildlife. The SMP under Alternative 2 will provide further protection during potential future intrusive activities in the AOC against exposure to potentially contaminated soil and groundwater.

Both Alternative 1 and Alternative 2 permit groundwater use restrictions and are equally protective of human health relative to groundwater exposure. As previously noted, AOC-2 groundwater is impacted by the release in an isolated area of AOC-2, so the significant soil removal required to meet Unrestricted Use SCOs is not likely to produce a measurable improvement to groundwater quality compared to the soil removal required by Alternative 2 coupled with restrictions on groundwater use. In addition, groundwater is not used on-Site since the Site and surrounding area are serviced by a municipal water supply.

### 5.2.3 Short-Term Effectiveness

Alternative 1 would require management of groundwater and surface water, excavation of soils that exceed Unrestricted Use SCOs, and placement of clean fill to return the area to original grade and promote drainage. Alternative 2 would require management of groundwater and surface water, excavation of soils from the top 1 foot, placement of a demarcation layer, and placement of clean fill to return the area to original grade and promote drainage.

Future construction activities, if any, could potentially involve contact with groundwater and surface water and excavation and disturbance of subsurface soils or fill material that are left in place under Alternative 2. However, this alternative has less potential for short-term exposure to workers and the community than Alternative 1 due to the reduced volume and duration of soil excavation required to implement the remedy.

The risk of future exposure would be lower after remediation under Alternative 1 than Alternative 2. However, this is offset by a relatively greater exposure risk during implementation of Alternative 1 since more soil would need to be excavated and transported off-site for disposal at a solid waste permitted facility under this alternative. Each proposed alternative would include a HASP and CAMP to identify requirements for action levels, personal protective equipment, and emergency procedures to address potential short-term impacts during soil excavation and backfilling, which makes them both equally protective of workers over the short-term. The SMP under Alternative 2 will ensure during potential future ground intrusive activities, if any, that encounter soil, groundwater, and surface water in the AOC is properly characterized and managed in order to address potential exposure issues to AOC contaminants, and would also require implementation of the HASP and CAMP during future ground intrusive activities in the AOC.

The potential exists for airborne contamination to be released from the AOC under both the alternatives; however, the potential for airborne release is greater under Alternative 1 than Alternative 2 since the amount of excavation would be more extensive and occur over a longer period of time.

Airborne release potentially includes particulate (i.e. dust). During excavation activities, under either of the alternatives, potential airborne releases will be mitigated by control measures put in place. Dust control measures may include wetting of travel areas that are exposed to soil surfaces that are prone to produce airborne dust. Under both alternatives, the implementation of a CAMP during

excavation activities would monitor airborne dust that could potentially migrate beyond the AOC and provide a means to identify controls that need to be implemented, if any.

Another short-term impact under both alternatives would be the increase in truck traffic on local roads as a result of hauling excavated soil from the AOC and hauling clean fill to the AOC. This impact would be of a lesser extent under Alternative 2 than Alternative 1. The increased truck traffic required by Alternative 1 could have a negative impact on local roadways and community acceptance.

#### 5.2.4 Long-Term Effectiveness and Performance

Both Alternative 1 and Alternative 2 provide a long-term and effective solution to AOC contamination, and will reduce human and environmental exposure to COPCs. Alternative 1 would provide a permanent solution due to the removal of all soils that do not meet Unrestricted Use SCOs.

Alternative 2 will require engineering/institutional controls to be recorded with the deed to the property via an Environmental Easement. This remedy is considered equally as effective and permanent as an Unrestricted Use remedy for the AOC based on the current, intended, and reasonably anticipated future commercial use. The SMP will be referenced in the Environmental Easement and will require annual certifications of all controls and implementation of the SMP.

#### 5.2.5 Reduction of Toxicity, Mobility, and Volume

Alternative 1 would result in a greater reduction in the volume of soil COPCs in the AOC compared to Alternative 2, but it may not have a measurable effect on toxicity of soil COPCs since both alternatives effectively mitigate exposure. Although Alternative 1 removes the potentially contaminated soil from the AOC for off-site disposal, it does not effectively reduce the toxicity or volume of the inorganic contaminants, especially as they will likely be landfilled. During implementation of Alternative 1 the mobility of soil COPCs may be temporarily higher than that for Alternative 2 since it will require more extensive excavation and transportation of soils. Following implementation of Alternative 1, mobility of AOC contaminants at the Site will be lower than under Alternative 2 since all contaminants will be removed to Unrestricted Use SCOs.

Based on RI data, the soil COPCs have not significantly impacted groundwater as evidenced by concentrations detected in groundwater monitoring wells. Groundwater quality may improve further following soil removal; however, neither alternative would likely have a significant impact on the toxicity or volume of COPCs identified in groundwater.

#### 5.2.6 Implementability

Technical and administrative tasks required to implement both the alternatives are all achievable. However, the implementation of Alternative 1 is not cost-effective relative to the primary use of AOC-2 as a stormwater drainage swale relative to the elevated costs and extensive amount of time associated with handling, transporting, treating, and disposing of groundwater, stormwater, and soil. Alternative 1 is also more difficult to implement than Alternative 2 owing to more extensive remedial activity that would likely be required to meet SCOs and potential impacts to the local community (i.e. truck traffic, noise, etc.). The removal of all potentially impacted soil may also be restricted by proximity to the buildings foundation, proximity to the property boundary, and presence of underground utilities. Excavations beyond four feet in depth along the entire length of the building, as proposed for Alternative 1, could have the potential to undermine or structurally compromise the building during remedial excavation activities. Management of groundwater and surface water,

excavation of soils, and installation and maintenance of the engineering/institutional controls under Alternative 2 are all readily implemented.

Alternative 1 would support the widest range of future AOC uses. Under Alternative 2 institutional controls will apply, but will not prevent the productive end use of the AOC that is currently anticipated. GSP will have to acquire the property that encompasses AOC-2 and incorporate the property into the BCP Site. This process is feasible and is underway with the anticipated purchase of the property prior to implementation of the AOC-2 remedy.

### 5.2.7 Costs

Alternative 1 would involve removing from the AOC approximately 2,700 cubic yards of soil compared to Alternative 2, which will require removal of approximately 459 cubic yards of soil to meet Commercial Use SCOs. There would be no annual maintenance costs associated with Alternative 1; however, there would be a significant capital cost of approximately \$763,000, which means the estimated Present Worth cost is approximately \$763,000 (Table 5-1). Alternative 2 is estimated to have a capital cost of approximately \$260,000 to implement and an annual cost of approximately \$31,000 to monitor, inspect, maintain, and certify the engineering controls (Table 5-1). The Present Worth cost for Alternative 2 is estimated to be approximately \$484,000 (Table 5-1), based on an estimated 30 year operating life span for the engineering controls (i.e. soil cover system).

Alternative	Capital Cost (A)	Annual Cost	Present Worth Annual Cost (B)	Present Worth (C)
<b>Alternative 1 – Restoration to Pre-Disposal or Unrestricted Conditions</b>	\$763,000	\$0	\$0	\$763,000
<b>Alternative 2 – Restoration to Commercial Uses with Site Management</b>	\$260,000	\$31,000	\$224,000	\$484,000

Notes:

Estimated Present Worth (C) = A + B

Estimated Present Worth values rounded to the nearest \$1,000.

### 5.2.8 Land Use

Alternative 1 would support an end use (i.e. residential) that is not consistent with current zoning or neighboring land uses. Alternative 2 has an end use that is consistent with the current zoning and neighboring land uses. Neighboring land uses are consistent with commercial and industrial uses and the majority of the AOC is associated with stormwater conveyance.

### 5.2.9 Community Acceptance

Alternative 1 would provide a level of cleanup that exceeds what is necessary to support the AOC's intended use, such that the additional work required to achieve the necessary cleanup may potentially reduce public acceptance. Alternative 1 would increase the duration of remediation work



to manage groundwater and surface water and to excavate soils, cause an increase in construction traffic and noise, and create additional truckloads of soil to be hauled to and from the AOC. These potential nuisances would be to a significantly lesser degree and have a shorter duration for Alternative 2.

Alternative 2 coupled with current, intended, and reasonably anticipated future AOC uses is aligned with community development interests. It is therefore anticipated that a commercial use with institutional and engineering controls will receive a favorable response from the local community. In order to obtain the necessary community acceptance, the selected approach will be made available for public review and comment prior to initiating.

## 6. AOC-3

### 6.1 Remedial Alternatives Analysis

As identified in the RAOs, the remedial approach for AOC-3 is focused on soil and sediment contaminants and the potential exposures to humans and the environment through direct contact and/or ingestion. Data collected during the RI indicate that one (1) subsurface soil sample at approximately 5.5- to 6.5-foot bgs (GSP-348) in proximity to AOC-3 and in an area adjacent to Bridge Street exceeded the Commercial Use SCOs for copper and nickel and the Unrestricted Use SCOs for copper, nickel, zinc, and total chromium. In addition, one other sample at a depth of 5-5.5 feet bgs in the same general vicinity (GSP-349) had an exceedance of the Unrestricted Use SCOs for hexavalent chromium (1.12 mg/kg versus the SCO of 1 mg/kg) and for zinc. Other soil samples collected associated with AOC-3 were below Unrestricted Use SCOs. As mentioned previously, zinc was not identified as a metal directly associated with the GSP release. Potential for direct contact and/or ingestion of these residual solids associated with AOC-3 is limited by the fact that they occur in the subsurface and are contained in a stormwater conveyance pipe. However, the potential for transport of contaminants adsorbed to soil particles in the pipe and discharge into the Bridge Street Swale is a potential mechanism for contaminants to migrate to areas where potential exposure could occur (AOC-4).

Based on the isolated soil sample, which was not immediately adjacent to AOC-3 stormwater pipe, with exceedances of copper and nickel no remedial actions relative to AOC-3 soil or groundwater are proposed. The remedial alternatives will focus on the residual solids that have settled in the stormwater pipe and catch basins associated with AOC-3. . This RAA identifies and compares potential AOC remedies. In accordance with DER-10, the alternatives to be evaluated are: Restoration to Pre-Disposal or Unrestricted Conditions and No Further Action, which would allow for the ongoing current Use of this AOC as a stormwater conveyance. The Emergency Remedial Work Plan (GHD, June 2013) included the flushing and removal of solids from the catch basins and culvert pipe from the GSP swale catch basin to the Bridge Street discharge. The summary of the emergency remedial activities were documented in a Construction Completion Report (GHD, January 2016) that was submitted to the NYSDEC and NYSDOH for review and approval. The inspection of the catch basins during the supplemental sampling activities completed during August 2016 did not identify any appreciable accumulation of sediment in the sump of the catch basins.

The proposed alternatives are each evaluated and compared in terms of nine (9) specific criteria identified in 6 NYCRR Part 375-1.8(f), including:

- Compliance with SCGs
- Protection of human health and the environment
- Short-term impact and effectiveness
- Long-term effectiveness and permanence
- Reduction of toxicity, mobility, or volume of contamination
- Implementability
- Cost effectiveness
- Land use
- Community acceptance.

The ninth criterion, community acceptance, will be further evaluated during public comment periods when feedback may be provided in relation to the proposed remedial alternative. The selected remedial alternative should produce a tangible benefit to the local community by achieving RAOs consistent with the current and reasonably anticipated future use of the AOC.

The following is an overview of each alternative and a comparative evaluation of the two (2) alternatives for the AOC, with respect to the nine (9) evaluation criteria.

#### 6.1.1 Restoration to Pre-Disposal or Unrestricted Conditions Alternative

A Restoration to Pre-Disposal or Unrestricted Conditions alternative would maximize the range of potential land use scenarios for AOC-3. This alternative would require a remedial approach that would result in no restrictions to AOC-3 use (i.e. the level of cleanup should permit all types of future reuse scenarios) and no institutional/engineering controls to address exposure and achieve the RAOs.

A Restoration to Pre-Disposal or Unrestricted Conditions alternative requires that AOC-3 remediation be completed to meet Unrestricted Use SCOs, thereby meeting SCGs for soils. This would permanently remove soils that exists in AOC-3 to achieve Unrestricted Use SCOs, to an estimated depth of 6.5-feet bgs (Figure 6-1). This would require that a remedial design be prepared for the AOC and submitted to NYSDEC for review and acceptance, as well as preparation of contract documents and selection of a contractor. To accomplish this alternative, access to off-site properties would need to be obtained, stormwater and groundwater would need to be managed, excavated soil would need to be transported and disposed of off-site, and an equivalent amount of off-site soil would need to be imported to the AOC to reestablish grades and promote drainage. The general soil fill must meet the following criteria:

- Requirements set forth in 6 NYCRR Part 375-6.7(d) and DER-10 Section 5.4(e)
- Be free of extraneous debris or solid waste
- Consist of soil or other unregulated material as set forth in 6 NYCRR Part 360
- Will not exceed the allowable constituent levels for imported fill or soil for the use of the AOC (Unrestricted Use SCOs).

This alternative would also require that the buried culvert pipe and associated catch basins be cleaned to remove potentially impacted sediments and water. It is anticipated that the cleaning process would begin at the southern end of the buried culvert pipe (northern edge of AOC-2) and progress north from one catch basin to the next. The culvert pipe and catch basins would be cleaned by pressure washing until sediment is removed and water reaches an acceptable turbidity, as determined by visual inspection in the field. Water and sediments would be pumped from the catch basins with a vacuum truck and staged in containers awaiting characterization and proper off-site disposal and/or treatment. Following cleaning of the buried culvert pipe and catch basins, the southern-most catch basin (located within AOC-2) would be replaced since it is currently in a state of disrepair (Catch Basin 1 on Figure 4 in Attachment B-3). The replacement of the catch basin could be completed during excavation activities being proposed as an element of the remedy associated with AOC-2.

Once the remedial action is completed, a FER would need to be prepared that certifies that the remedial action was completed in accordance with an approved Remedial Work Plan. The FER would summarize the remedial activities, include laboratory analytical data, and would be certified by a Professional Engineer licensed in New York State.

This alternative would eliminate the potential risk associated with ingestion and/or direct human contact with contaminated soil and residual solids, and would provide a benefit in relation to potential wildlife exposure by removing contaminated media from the AOC.

For this remedy, excavated soil, staged stormwater and groundwater, and staged sediment would need to be transported to a facility permitted to receive and manage the material, which would generate increased truck traffic on local roadways. An equivalent amount of off-site soil would need to be hauled to the AOC to backfill the excavation, which would add to the increased truck traffic.

This remedy would create short-term risks associated with stormwater and groundwater management, soil excavation, cleaning the buried culvert pipe and catch basins, off-site transport and disposal of contaminated soil, water, and sediment, and transport of clean soil fill to the AOC; however, long-term risks would be mitigated.

It is estimated that the Restoration to Pre-Disposal or Unrestricted Conditions alternative would have a capital cost of approximately \$559,000 (Table 6-1) to implement; however, there would be no ongoing annual costs associated with the AOC once this alternative is completed. Therefore, the Present Worth of this alternative would be approximately \$559,000.

#### 6.1.2 No Further Action Alternative

The No Further Action alternative would allow for the current and continued use of the AOC as a stormwater conveyance feature and would be protective of human health and the environment since the buried culvert pipe and catch basins were already flushed of their residual solids during the Emergency Remedial Measures previously complete.

The previous cleaning of the buried culvert pipe and catch basins meets the stated RAOs for this AOC and supports the current, intended, and reasonably anticipated future uses of the AOC as a stormwater conveyance pipe maintained by the Town of DeWitt.

An FER needs to be prepared that certifies that the remedial action was completed in accordance with an approved Remedial Work Plan (Emergency Remedial Work Plan, GHD, June 2013). The FER would summarize the remedial activities as documented in the Construction Completion Report, (GHD January 2016) and would be certified by a Professional Engineer licensed in New York State.

This alternative would mitigate the potential risk associated with direct human contact and/or ingestion of contaminated residual solids. This alternative also provides a benefit in relation to potential fish and wildlife exposure as the potentially contaminated media from the buried culvert pipe and catch basins were flushed and removed from the pipe.

The No Further Action alternative would have no additional capital costs to implement and no ongoing annual costs associated with the AOC.

## 6.2 Evaluation of Remedial Alternatives

This evaluation of alternatives compares the Restoration to Pre-Disposal or Unrestricted Conditions (Alternative 1) and the No Further Action (Alternative 2) alternatives.

In accordance with BCP guidance, the selected remedy will provide protection of public health and the environment, taking into account the current, intended, and reasonably anticipated future land uses of the AOC.

An evaluation has been prepared to identify a suitable remedial action in accordance with 6 NYCRR Part 375-1.10(c)(1-6). In the specific context of the contemplated end use of the AOC, the selected remedy should be:

- Consistent with applicable SCGs
- Protective of public health and the environment
- Effective for both short-term and long-term
- Able to reduce toxicity, mobility, and volume of the hazardous constituents
- Feasible from implementability and cost effectiveness perspectives
- Reasonably anticipated to be acceptable to the local community.

#### 6.2.1 Compliance with Standards, Criteria, and Guidance

A review of the SCGs documents pertinent to AOC specific conditions has been completed. The SCGs for soil are the 6 NYCRR Part 375-6.8(b) Unrestricted Use SCOs for Alternative 1. Alternative 2 remedial approach was the removal of solid residue in the culvert pipe and catch basins and does not have applicable SCGs. Alternative 1 will meet the SCGs for all soil within the AOC boundary.

#### 6.2.2 Protection of Human Health and the Environment

Both Alternative 1 and Alternative 2 are protective of human health and the environment. Alternative 1 would remove soil contamination to meet soil SCGs. Alternative 2 would leave subsurface soils identified at two sample locations adjacent to Bridge Street in place above Unrestricted Use SCOs, where it will not be accessible to humans or wildlife.

#### 6.2.3 Short-Term Effectiveness

Alternative 1 would require excavation of soils that exceed Unrestricted Use SCOs and placement of clean fill to return the area to original grade and promote drainage. Future construction activities, if any, could potentially involve excavation and disturbance of subsurface soils or fill material that are left in place under Alternative 2; however, this alternative has less potential for short-term exposure to workers and the community than Alternative 1 due to no need for soil excavation to implement the remedy.

The risk of future exposure would be lower after remediation under Alternative 1 than Alternative 2. However, this is offset by a relatively greater exposure risk during implementation of Alternative 1 since more stormwater and groundwater would need to be managed and more soil would need to be excavated and transported off-site for disposal at a solid waste permitted facility under this alternative. The potential exists for airborne contamination to be released in the form of particulates (i.e., dust) from the AOC under Alternative 1 due to excavation of soils and a longer duration for the work.

During excavation activities, potential airborne releases can be mitigated by control measures that could be put in place. Dust control measures may include wetting of travel areas that are exposed to soil surfaces that are prone to produce airborne dust. The implementation of a CAMP during excavation activities would monitor airborne dust that could potentially migrate beyond the AOC and provide a means to identify what controls need to be implemented.

Another short-term impact under Alternative 1 would be the increase in truck traffic on local roads as a result of hauling excavated soil or solids and flushing water from the AOC and hauling clean fill

to the AOC. This impact would not exist under Alternative 2. The increased truck traffic required by Alternative 1 could have a negative impact on local roadways and the local community.

#### 6.2.4 Long-Term Effectiveness and Performance

Both Alternative 1 and Alternative 2 provide a long-term and effective solution to AOC-3 contamination, and will reduce human and environmental exposure to COPCs. Alternative 1 would provide a permanent solution due to the removal of all soils that do not meet Unrestricted Use SCOs. Alternative 2 included the removal of residual solids from the pipe and catch basin to preclude migration to downstream areas and potential exposure to workers during future maintenance activities.

#### 6.2.5 Reduction of Toxicity, Mobility, and Volume

Alternative 1 would result in a greater reduction in the volume of soil COPCs in the AOC compared to Alternative 2, but it may not have a measurable effect on toxicity of soil COPCs compared to Alternative 2 since both alternatives effectively mitigate exposure. During implementation of Alternative 1 the mobility of soil COPCs may be temporarily higher than that for Alternative 2 since Alternative 1 will require more extensive excavation and transportation of soils. Following implementation, mobility of AOC contaminants under Alternative 1 and 2 would be similar as both would remove contaminants that could migrate within the pipe to downstream locations.

#### 6.2.6 Implementability

Technical and administrative tasks required to implement the alternatives are all achievable. However, the implementation of Alternative 1 would likely not be cost-effective for the planned end use of the AOC, due to costs and an extensive amount of time associated with handling, transporting, treating, and disposing of large volumes of stormwater, groundwater, and soil and having to obtain access to off-site properties in order to implement the remedial activities. Alternative 1 is also more difficult to implement than Alternative 2 owing to more extensive remedial activity that would likely be required to meet SCOs and potential negative impacts to the local community (i.e. truck traffic, noise, etc.). The removal of all potentially impacted soil may also be restricted by proximity to buildings, roadways, and the presence of underground utilities. More significant short-term exposures are also created by the implementation of Alternative 1.

Alternative 1 would support the widest range of future AOC uses. Under Alternative 2 the current and anticipated use of the AOC as a stormwater conveyance feature would be maintained.

#### 6.2.7 Costs

Alternative 1 would involve removing from the AOC soil to meet Unrestricted Use SCOs. There would be no annual costs associated with Alternative 1; however, there would be a significant capital cost of approximately \$559,000, which means the estimated Present Worth cost is approximately \$559,000 (Table 6-1). Alternative 2 will have no additional capital costs since the flushing of the culvert pipe and catch basins was already completed as part of the Emergency Remedial Actions associated with previous development of a portion of AOC-4. The significant cost of Alternative 1 would likely make it cost prohibitive for the intended future use of the AOC.

Alternative	Capital Cost (A)	Annual Cost	Present Worth Annual Cost (B)	Present Worth (C)
<b>Alternative 1 – Restoration to Pre-Disposal or Unrestricted Conditions</b>	\$559,000	\$0	\$0	\$559,000
<b>Alternative 2 – No Further Action</b>	\$0	\$0	\$0	\$0

Notes:

Estimated Present Worth (C) = A + B

Estimated Present Worth values rounded to the nearest \$1,000.

#### 6.2.8 Land Use

Alternative 1 would support an end use that is not consistent with current zoning or neighboring land uses. Alternative 2 has an end use that is consistent with the current zoning and neighboring land uses and would allow for the continued use of the AOC for stormwater conveyance. Neighboring land uses are consistent with commercial and industrial uses.

#### 6.2.9 Community Acceptance

Alternative 1 would provide a level of cleanup that exceeds what is necessary to support the AOC's intended use, such that the additional work required to achieve the necessary cleanup may potentially reduce public acceptance. Alternative 1 would increase the duration of remediation work to manage stormwater and groundwater, excavate soils, cause an increase in construction traffic and noise, and create additional truckloads of soil to be hauled to and from the AOC.

Alternative 2 coupled with current, intended, and reasonably anticipated future AOC uses is aligned with community development interests. In order to obtain the necessary community acceptance, the selected approach will be made available for public review and comment prior to initiating.

## 7. AOC-4

### 7.1 Remedial Alternatives Analysis

As identified in the RAOs, the remedial approach for AOC-4 is focused on soil/sediment and surface water contaminants and the potential exposures to humans and the environment through direct contact and/or ingestion and the potential migration of contaminants downstream. Data collected during the RI and subsequent investigations indicated that soils that exceed the applicable Protection of Ecological Resources SCOs occur in areas of AOC-4 ranging from 0- to 24-inches bgs (Figures 13A and 13B in Attachment B-2). Contaminants of concern in this area are primarily total chromium, copper, nickel, and zinc, and to a lesser extent, hexavalent chromium. Potential for direct contact and/or ingestion of these soils is limited; however, remedial action to deal with the area is warranted to meet the remedial goals for AOC-4.

Data collected during the RI and subsequent investigations also indicated that at the time of sampling surface water exceeded applicable New York State Ambient Water Quality standards for total chromium, copper, nickel, and hexavalent chromium (Tables 5-9 and 5-10 in Attachment B-1). Once identified, the impacted surface water was removed from the swale, treated, and discharged to the Onondaga County Waste Water Treatment Facility. Confirmatory surface water samples indicated that surface water exceeds applicable New York State Ambient Water Quality standards for total chromium, copper, nickel, and hexavalent chromium; however, the magnitude of the impacts is greatly reduced from that identified in initial samples. No specific remedial actions are proposed relative to surface water for this AOC at this time.

The Emergency Remedial Work Plan (GHD, June 2103) included the excavation and removal of soils from a portion of the Bridge Street Swale that is in proximity to the Community Bank development adjacent to Bridge Street. The NYSDEC required that the soils in the Bridge Street Swale be removed to achieve Protection of Ecological Resources SCOs in those areas that would not be backfilled during construction of the bank. This RAA identifies and compares two (2) potential AOC remedies, in accordance with DER-10 and the NYSDEC requirement for soil removal associated with the Community Bank development. The alternatives to be evaluated are: Restoration to Pre-Disposal or Unrestricted Conditions (Alternative 1) and Restoration to Protection of Ecological Resources Conditions (Alternative 2). The RI and subsequent investigations data indicated that concentrations of the metals of concern were inconsistent and highly variable, especially in the downstream sections of the swale in the vicinity of Route 690.

The proposed alternatives are each evaluated and compared in terms of nine (9) specific criteria identified in 6 NYCRR Part 375-1.8(f), including:

- Compliance with SCGs
- Protection of human health and the environment
- Short-term impact and effectiveness
- Long-term effectiveness and permanence
- Reduction of toxicity, mobility, or volume of contamination
- Implementability
- Cost effectiveness
- Land use



- Community acceptance.

The ninth criterion, community acceptance, will be further evaluated during public comment periods when feedback may be provided in relation to the proposed remedial alternative. The selected remedial alternative should produce a tangible benefit to the local community by achieving RAOs consistent with the current and reasonably anticipated future use of the AOC.

The following is an overview of each alternative and a comparative evaluation of the two (2) alternatives for AOC-4, with respect to the nine (9) evaluation criteria.

#### 7.1.1 Restoration to Pre-Disposal or Unrestricted Conditions Alternative

A Restoration to Pre-Disposal or Unrestricted Conditions alternative would maximize the range of potential land use scenarios for AOC-4. This alternative would require a remedial approach that would result in no further restrictions to AOC-4 use (i.e. the level of cleanup should permit all types of future reuse scenarios) and no institutional/engineering controls to address exposure and achieve the RAOs.

A Restoration to Pre-Disposal or Unrestricted Conditions alternative requires that AOC-4 remediation be completed to meet Unrestricted Use SCOs, thereby meeting SCGs for soils. This would permanently remove the volume of contaminated soils that exists in AOC-4 by requiring excavation of soil across the majority of the AOC to achieve Unrestricted Use SCOs, to an estimated depth of 0.5- to 2-feet bgs (Figures 7-2a and 7-2b). This would require that a remedial design be prepared for the AOC and submitted to NYSDEC for review and acceptance, as well as preparation of contract documents and selection of a contractor. To accomplish this alternative would entail the following:

- the entire length of the swale would need to be cleared of vegetation and trees
- the swale would need to be dewatered in segments
- access across off-site properties would need to be arranged
- NYS Route 690 traffic controls would need to be implemented during work activities along the right of way
- Staging, access roads and turn around areas would need to be created for trucks and equipment
- excavated soil/sediment ,surface water and groundwater would need to be managed and contained as appropriate
- excavated soil/sediment ,surface water and groundwater would need to be transported and disposed of off-site as appropriate
- clean off-site soil could need to be imported to the AOC to reestablish grades and promote drainage in some areas
- the area above the water line would need to be reseeded to establish vegetation.

It is assumed that the backfill soil would include general soil fill covered with a minimum of 4-inches of topsoil, which would be seeded to establish vegetative cover, in areas that will not be underwater. The general soil fill must meet the following criteria:

- Requirements set forth in 6 NYCRR Part 375-6.7(d) and DER-10 Section 5.4(e)
- Be free of extraneous debris or solid waste

- Consist of soil or other unregulated material as set forth in 6 NYCRR Part 360
- Will not exceed the allowable constituent levels for imported fill or soil for the use of the AOC (Unrestricted Use SCOs).

Once the remedial action is completed, a FER would need to be prepared that certifies that the remedial action was completed in accordance with an approved Remedial Design Document. The FER would summarize the remedial activities, include laboratory analytical data, and would be certified by a Professional Engineer licensed in New York State.

This alternative would eliminate the potential risk associated with ingestion and/or direct human contact with contaminated soil, and would provide a benefit in relation to potential fish and wildlife exposure by removing contaminated media from the AOC.

For this remedy, soil and surface water would need to be managed and transported to a facility permitted to receive and manage the material, which would generate increased truck traffic on local roadways. Clean off-site soil would need to be hauled to the AOC to backfill the excavation in isolated areas, which would add to the increased truck traffic.

This remedy would create short-term risks associated with soil, surface water and groundwater management, excavation, off-site transport and disposal of contaminated material, and transport of clean soil fill to the AOC; however, long-term risks would be mitigated.

It is estimated that the Restoration to Pre-Disposal or Unrestricted Conditions alternative would have a capital cost of approximately \$1,268,000 (Table 7-1) to implement and no ongoing annual costs associated with the AOC once this alternative is completed. Therefore, the Present Worth of this alternative would be approximately \$1,268,000 (Table 7-1).

#### 7.1.2 Restoration to Protection of Ecological Resources Conditions Alternative

A Restoration to Protection of Ecological Resources Conditions alternative would ensure protection of ecological resources as well as maximize the range of potential land use scenarios for AOC-4. The NYSDEC has indicated that they would accept the remediation of AOC-4 to achieve Protection of Ecological Resources SCOs. This alternative would require a remedial approach that would result in no further restrictions to AOC-4 use (i.e. the level of cleanup should permit all types of future reuse scenarios) and no institutional/engineering controls to address exposure and achieve the RAOs. For the metals of concern there is, for all intents and purposes, little difference in the remedial approach for Alternative 2 compared to Alternative 1. Effectively for the metals of concern only Total Chromium has a different SCO for Protection of Ecological Resources (42 mg/kg) compared to Unrestricted Use (31 mg/kg).

A Restoration to Protection of Ecological Resources Conditions alternative requires that AOC-4 remediation be completed to meet Protection of Ecological Resources SCOs, thereby meeting SCGs for soils. This alternative essential would entail the same remedial action as Alternative 1. This would permanently remove the volume of contaminated soils that exists in AOC-4 by requiring excavation of soil across the majority of the AOC to achieve Protection of Ecological Resources SCOs, to an estimated depth of 1-foot bgs (Figures 7-4a and 7-4b) with some areas requiring additional excavations to approximately 1.5-feet. The depth of excavation is, in part, based on the experience of soil removal from the swale during the Emergency Remedial Activities associated with the Community Bank development. During those activities the removal of approximately 1-foot bgs was adequate to meet the Protection of Ecological Resources SCOs based on confirmation sampling and analysis. Typically, the concentrations of the metal COPC downstream of the Bridge

Street area were detected at lower concentrations the further away from Bridge Street the samples were taken. This alternative would require that a remedial design be prepared for the AOC and submitted to NYSDEC for review and acceptance, as well as preparation of contract documents and selection of a contractor. To accomplish this alternative, soil, surface water and groundwater would need to be managed and material would need to be transported off-site for disposal. In general, to promote drainage in the swale it is proposed not to backfill soil to pre-excavation elevations. This approach is consistent with the expressed interest of the entities that currently own or manage the swale (Town of DeWitt, National Grid, and NYSDOT) from Bridge Street to the point where it flows under Route 690. Areas of the excavation that will not be underwater would be seeded to establish vegetative cover. . If general soil fill is needed to fill in low spots it must meet the following criteria:

- Requirements set forth in 6 NYCRR Part 375-6.7(d) and DER-10 Section 5.4(e)
- Be free of extraneous debris or solid waste
- Consist of soil or other unregulated material as set forth in 6 NYCRR Part 360
- Will not exceed the allowable constituent levels for imported fill or soil for the use of the AOC (Protection of Ecological Resources SCOs).

Once the remedial action is completed, a FER would need to be prepared that certifies that the remedial action was completed in accordance with an approved Remedial Design Document. The FER would summarize the remedial activities, include laboratory analytical data, and would be certified by a Professional Engineer licensed in New York State.

This alternative would eliminate the potential risk associated with ingestion and/or direct human contact with contaminated soil/sediment, and would provide a benefit in relation to potential fish and wildlife exposure by removing contaminated media from the AOC.

For this remedy, soil and dewatering water would need to be transported to a facility permitted to receive and manage the material, which would generate increased truck traffic on local roadways. Clean off-site soil would need to be hauled to the AOC to backfill the excavation in isolated areas, which could add to the increased truck traffic. These impacts would be similar to impacts under the Restoration to Pre-Disposal or Unrestricted Conditions alternative since both alternatives require an equal amount of excavation.

This remedy would create short-term risks associated with surface water and groundwater management, excavation, off-site transport and disposal of contaminated material, and transport of clean soil fill to the AOC; however, long-term risks would be mitigated.

It is estimated that the Restoration to Protection of Ecological Resources Conditions alternative would have a capital cost of approximately \$1,268,000 (Table 7-1) to implement and no ongoing annual cost associated with the AOC once this alternative is completed. Therefore, the Present Worth of this alternative would be approximately \$1,268,000 (Table 7-1).

## 7.2 Evaluation of Remedial Alternatives

This evaluation of alternatives compares the Restoration to Pre-Disposal or Unrestricted Conditions (Alternative 1) and the Restoration to Protection of Ecological Resources Conditions (Alternative 2) alternatives.

In accordance with BCP guidance, the selected remedy will provide protection of public health and the environment, taking into account the current, intended, and reasonably anticipated future land uses of the AOC.

An evaluation has been prepared to identify a suitable remedial action in accordance with 6 NYCRR Part 375-1.10(c)(1-6). In the specific context of the contemplated end use of the AOC, the selected remedy should be:

- Consistent with applicable SCGs
- Protective of public health and the environment
- Effective for both short-term and long-term
- Able to reduce toxicity, mobility, and volume of the hazardous constituents
- Feasible from implementability and cost effectiveness perspectives
- Reasonably anticipated to be acceptable to the local community.

#### 7.2.1 Compliance with Standards, Criteria, and Guidance

A review of the SCGs documents pertinent to AOC specific conditions has been completed. The SCGs for soil are the 6 NYCRR Part 375-6.8(b) Unrestricted Use SCOs for Alternative 1 and the Protection of Ecological Resources SCOs for Alternative 2. Alternative 1 and Alternative 2 will meet the SCGs for soil within the AOC boundary.

#### 7.2.2 Protection of Human Health and the Environment

Each of the two (2) alternatives are protective of human health and the environment. Alternative 1 and Alternative 2 would remove soil contamination to meet soil SCGs. The excavation of the swale will create a short term disturbance of wildlife habitat that can be mitigated by managing the relocation of wildlife that may be encounter in the swale during excavation activities.

#### 7.2.3 Short-Term Effectiveness

Alternative 1 would require excavation of soils that exceed Unrestricted Use SCOs and placement of clean fill in isolated areas to return the area to original grade and promote drainage. Alternative 2 would require excavation of soils that exceed Protection of Ecological Resources SCOs and placement of clean fill in isolated areas to return the area to original grade and promote drainage.

The risk of future exposure would be equal after remediation under Alternative 1 and Alternative 2.

Each proposed alternative would include a HASP and CAMP to identify requirements for action levels, personal protective equipment, and emergency procedures to address potential short-term impacts during soil excavation and backfilling, which makes them both equally effective over the short-term.

The potential exists for airborne contamination to be released from the AOC under both of the alternatives; however, the potential for airborne release is minimized by the fact that the majority of excavation activities will be occurring in drainage swales where wet/moist soils will be encountered.

Airborne releases potentially include particulate (i.e., dust) contaminants. During excavation activities, under either of the alternatives, potential airborne releases will be mitigated by control measures put in place. Dust control measures may include wetting of travel areas that are exposed to soil surfaces that are prone to produce airborne dust. Under both alternatives, the implementation of a CAMP during excavation activities would monitor airborne dust that could potentially migrate beyond the AOC and provide a means to identify what controls need to be implemented.

Another short-term impact under each of the alternatives would be an increase in truck traffic on local roads as a result of hauling excavated soil and collected water from the AOC and hauling clean fill to the AOC. The increased truck traffic required by Alternative 1 and Alternative 2 could have a negative impact on local roadways and community acceptance of the alternative, but the magnitude of the increased traffic would be the same for each alternative.

Alternative 1 and Alternative 2 may also require work within the NYS Route 690 R.O.W. which could increase traffic safety concerns during the implementation of the remedy.

#### 7.2.4 Long-Term Effectiveness and Performance

Alternative 1 and Alternative 2 both provide a long-term and effective solution to AOC contamination, and will reduce human and environmental exposure to COPCs. Alternative 1 would provide a permanent solution due to the removal of all soils that do not meet Unrestricted Use SCOs. Alternative 2 would provide a permanent solution due to the removal of all soils that do not meet Protection of Ecological Resources SCOs.

#### 7.2.5 Reduction of Toxicity, Mobility, and Volume

Alternative 1 and Alternative 2 would result in a greater reduction in the volume of soil COPCs in the AOC, but they may not have a measurable effect on toxicity of soil COPCs. Although both alternatives remove the potentially contaminated soil from the AOC for off-site disposal, neither one effectively reduces the toxicity or volume of the inorganic contaminants, especially as they will likely be landfilled. During implementation of Alternative 1 and Alternative 2 the mobility of soil COPCs may be temporarily higher since Alternative 1 and Alternative 2 will require extensive dewatering and excavation and transportation of soils and water. Following implementation, mobility of AOC contaminants under both alternatives would be lower since the alternatives would not leave contamination in the AOC above the corresponding SCOs.

#### 7.2.6 Implementability

Technical and administrative tasks required to implement the alternatives are all achievable. However, the removal of all potentially impacted soil under both alternatives may be restricted by proximity to the property features, roadways, and presence of underground and overhead utilities. More significant short-term exposures are also created by the implementation of Alternative 1 and Alternative 2.

Alternative 1 and Alternative 2 would support the widest range of future AOC uses and would mitigate future exposure potential.

#### 7.2.7 Costs

Alternative 1 and Alternative 2 would involve removing from the AOC a large quantity of soil to meet Unrestricted Use SCOs or Protection of Ecological Resources SCOs, respectively. The capital costs associated with Alternative 1 and Alternative 2 are the same and are estimated to be approximately \$1,268,000 (Table 7-1) and neither of these alternatives have annual costs, which means the estimated Present Worth costs are approximately \$1,268,000 for both Alternative 1 and Alternative 2 (Table 7-1).

Alternative	Capital Cost (A)	Annual Cost	Present Worth Annual Cost (B)	Present Worth (C)
<b>Alternative 1 – Restoration to Pre-Disposal or Unrestricted Conditions</b>	\$1,268,000	\$0	\$0	\$1,268,000
<b>Alternative 2 – Restoration to Protection of Ecological Resources Conditions</b>	\$1,268,000	\$0	\$0	\$1,268,000

Notes:

Estimated Present Worth (C) = A + B

Estimated Present Worth values rounded to the nearest \$1,000.

#### 7.2.8 Land Use

Alternative 1 and Alternative 2 would support an end use that is consistent with current zoning or neighboring land uses and that is higher than necessary to allow for the continued use of the AOC as a drainage/stormwater conveyance. Neighboring land uses are consistent with commercial and industrial uses.

#### 7.2.9 Community Acceptance

Alternative 1 and Alternative 2 would provide a level of cleanup that exceeds what is necessary to support the AOC's intended use, such that the additional work required to achieve the necessary cleanup may potentially reduce public acceptance. Alternative 1 and Alternative 2 would increase the duration of remediation work to manage surface water and groundwater and excavate materials, cause an increase in construction traffic and noise, and create additional truckloads of soil and water to be hauled from the AOC. In order to obtain the necessary community acceptance, the selected approach will be made available for public review and comment prior to initiating remedial action.

## 8. Selected Remedy

### 8.1 AOC-1

Based on the results of the investigations completed at the AOC, the reasonably anticipated future use of the Site, and the evaluation presented above (Section 4), Alternative 2 – Restoration to Commercial Uses with Site Management, including implementation of engineering/institutional controls pursuant to an Environmental Easement, is the proposed remedy for AOC-1. This remedy is protective of human health and the environment and satisfies the remediation objectives described in Section 3 above, based on the future commercial or industrial use of the Site.

The main elements of the proposed remedy include:

- Establishing the existing concrete floor as a soil cover engineering control
- Inspection of the building's concrete slab for cracks and repairing as necessary
- Preparation and submittal of an FER for NYSDEC and NYSDOH review and approval
- Institutional controls in the form of an Environmental Easement
- Development of a SMP to be filed with an Environmental Easement
- Commercial/industrial use deed restriction filed with the Onondaga County Clerk's Office in the form of an Environmental Easement
- Groundwater use restrictions in the form of an Environmental Easement filed with the Onondaga County Clerk's Office
- Ongoing inspection, maintenance, and reporting on the soil cover system engineering control as defined in the SMP.

### 8.2 AOC-2

Based on the results of the investigations completed at the AOC, the reasonably anticipated future use of the Site, and the evaluation presented above (Section 5), Alternative 2 – Restoration to Commercial Uses with Site Management, including implementation of engineering/institutional controls pursuant to an Environmental Easement, is the proposed remedy for AOC-2. This remedy is protective of human health and the environment and satisfies the remediation objectives described in Section 3 above, based on the future commercial or industrial use of the Site.

The main elements of the proposed remedy include:

- Acquisition of a portion of the adjacent property that is encompassed by AOC-2 and incorporation of this area into the BCP Site; a written purchase Agreement has been agreed to in principle and is subject to seller's board approval
- Repair of the catch basin located in the swale of AOC-2. The catch basin is a part of the Town of Dewitt stormwater conveyance system, and repairs will require coordination with the Town
- Removal of trees and root systems from AOC-2 and off-site disposal at a permitted facility
- Excavation of soils from the top 1 foot and grading to promote proper surface drainage in the area delineated on Figure 5-4 with off-site disposal of soils at a permitted facility
- Documentation soil sampling on a predetermined sample grid and laboratory sample analysis

- Placement of a demarcation layer and backfilling excavated area with a minimum of 1-foot of clean off-site fill to create a soil cover system
- Preparation and submittal of an FER for NYSDEC and NYSDOH review and approval
- Development of a SMP to be filed with an Environmental Easement
- Commercial/industrial use deed restriction filed with the Onondaga County Clerk's Office in the form of an Environmental Easement
- Groundwater use restrictions in the form of an Environmental Easement filed with the Onondaga County Clerk's Office
- Ongoing inspection, maintenance, and reporting on the soil cover system engineering control as defined in the SMP.

### 8.3 AOC-3

Based on the results of the investigations completed in AOC-3, the Emergency Remedial activities per the NYSDEC-approved Work Plan (GHD, June 2013), which included water jetting the residual solids located in the buried culvert pipe and catch basins with off-site disposal of contaminated solids and flush water at permitted facilities, and the evaluation presented above (Section 6), Alternative 2 – No Further Action is the proposed remedy for AOC-3. During the implementation of the AOC-2 remedial activities, the stormwater culvert pipe will be managed to preclude sediment from entering the pipe and being transported downstream. The culvert pipe will be inspected for sediment after AOC-2 remedial work is completed.

### 8.4 AOC-4

Based on: (1) the results of the investigations completed AOC-4; (2) the Emergency Remedial activities that included removal of the solids from the portion of the swale with the higher concentrations of contaminants of concern; (3) the Town of Dewitt maintenance activities on a portion of the swale; (4) the findings reported in the Supplemental Sampling Activities Summary Letter Report (GHD, October 3, 2016), and (5) the evaluation presented above (Section 7), Alternative 2 – Restoration to Protection of Ecological Resources Conditions is the proposed remedy for AOC-4. The proposed remedial approach includes excavation of swale soils downstream from the Emergency Remedial activities and documentation soil sampling and analysis to verify that remaining soils achieve the Protection of Ecological Resources SCOs. This remedy is protective of human health and the environment and satisfies the remediation objectives described in Section 3 above.

The main elements of the proposed remedy include:

- Swale from Bridge Street to the extent of the Emergency Remedial activities: no further actions
- Swale from the extent of the Emergency Remedial activities downstream, including the swale section within the NYSDOT R.O.W. for Interstate 690:
  - Obtaining necessary permits and regulatory approvals, along with property access agreements, to complete soil excavation remedial activities
  - Clearing of vegetation and establishing temporary access roads for excavation and hauling equipment
  - Establish work areas and dewater sections of the swale in phases as work progresses



- Establish temporary access and staging areas to remove and stage excavated soils
- Excavate a minimum of 1-foot of soil from the swale, dewater and characterize the soil, and transport the soil off-site for proper disposal
- Confirmation soil sampling and analysis on a predetermined grid of 50-feet with samples taken from each sidewall and the bottom of the swale (three samples at each sample grid location). Soil samples will be analyzed for metal contaminants of concern to establish that remaining soils in the swale meet the Protection of Ecological Resources SCOs
- If the soil samples indicate the remaining soils do not achieve the Protection of Ecological Resources SCOs, additional excavation of 6- to 12-inches will be completed and subsequent confirmation soil samples collected and analyzed
- The areas of excavation will not be backfilled (backfilling is not proposed as removal of soils will be considered swale maintenance to retain grades and remove built up sediment associated with stormwater conveyance). If swale excavation proceeds to additional depths as a result of confirmation sampling, backfilling of isolated areas of the swale may be necessary.
- The disturbed areas above the swale water level will be seeded and stabilized
- Preparation and submittal of a Construction Completion Report for NYSDEC and NYSDOH review and approval.

## 8.5 Future BCP Site Activities

There are currently no plans to further develop AOC-1 or AOC-2. Specific actions would need to be implemented to mitigate exposure of humans and the environment to potentially contaminated media during any future construction activities conducted in these AOCs. These actions will be described in the SMP, which will have sections dedicated to AOC-1 and AOC-2.

The required SMP will include the following:

- An Engineering and Institutional Control Plan that identifies all use restrictions and engineering controls for the AOCs and details the steps and media-specific requirements necessary to ensure the following engineering/institutional controls remain in place and effective:
  - Engineering Controls: The soil cover system discussed above
  - Institutional Controls: The deed restrictions in the form of an Environmental Easement and the groundwater use restrictions in the form of an Environmental Easement, both of which are discussed above
- A Soil Management Plan which details the provisions for management of future excavations in areas of remaining contamination
- A Monitoring Plan that will assess the performance and effectiveness of the remedy, which will include, but may not be limited to, the following:
  - A schedule of monitoring and frequency of submittals to the NYSDEC
  - Monitoring and maintenance of AOC-1 and AOC-2 engineering controls


- Descriptions of the provisions of the Environmental Easement including any land use and/or groundwater use restrictions
- Provisions for the management and inspection of the identified engineering controls
- Maintain AOC access controls and NYSDEC notification
- The steps necessary for the periodic review and certification of the engineering/institutional controls.

The AOC-4 drainage swales are currently maintained by the Town of Dewitt, National Grid, and the NYSDOT as a stormwater drainage conveyance. Maintenance includes periodic dewatering and excavation of the swale by the Town of Dewitt and NYSDOT to provide adequate drainage.

Future actions associated with implementing the remedy for the Celi Drive BCP Site will include:


- Finalization of the purchase of the AAA property that encompasses AOC-2
- Review and approval of this RAA by NYSDEC and NYSDOH.
- Issuance of a Record of Decision Document by the NYSDEC
- Development of Remedial Work Plans or Remedial Design Documents as Appropriate for NYSDEC and NYSDOH approval
- Citizen Participation as required under the BCA
- Implementation of remedial activities associated with AOC-1 and AOC-2
- Implementation of remedial activities associated with AOC-4
- Preparation of a Construction Completion Report for AOC-4
- Preparation of the Final Engineering Report for AOC-1 and AOC-2
- Preparation of Site Management Plan for AOC-1 and AOC-2
- Development, execution, and implementation of Institutional Controls in the form of an Environmental Easement for AOC-1 and AOC-2
- Filing with the County Clerk's Office of the executed Environmental Easement and Deed Restrictions
- Issuance of the Certificate of Completion by the NYSDEC.

Figures



CONTOUR INTERVAL: 10 FEET

MAPS TAKEN FROM: USGS 7.5 MINUTE SERIES  
 TOPOGRAPHIC QUADRANGLES:  
 SYRACUSE EAST, NY (2016)  
 (U.S. GEOLOGICAL SURVEY WEBSITE)



GSP Holdings, Inc.  
 Celi Drive BCP Site (BCP Site #C734108)  
 Remedial Alternatives Analysis

Job Number | 37-11082  
 Revision | A  
 Date | 06.30.2017

Property Location Map

Figure 1-1



NOTES:  
 1. Aerial photographs are low resolution color orthorectified imagery from the National Aerial Photography Mission (NAPM) site (<http://earthexplorer.usgs.gov>)




GSP Holdings, Inc.  
 Celi Drive BCP Site (BCP Site #C734108)  
 Remedial Alternatives Analysis

Site Layout

Job Number | 37-11082  
 Revision | A  
 Date | 05.12.2014

Figure 1-2

# Shipping Department



NOT TO SCALE



NOTES:  
 1) Base (ap and sa) ple locations (a) en (ro) Data (ap Invest) ation (e) port (E) M, 2) 000  
 2) Only analytes that exceed (n) restricted (se SCOs are shown, (or a) complete su) (y  
 (o) analytical results see (a) les in Attach) ent B)



GSP Holdings, Inc.  
 Celi Drive BCP Site (BCP Site #C734108)  
 Remedial Alternatives Analysis  
 Exceedances of Unrestricted Use  
 SCOs in AOC-1

Job Number | 37-11082  
 Revision | A  
 Date | 11.12.2013  
**Figure 4-1**

# Shipping Department

SAMPLE ID - B-1	DEPTH - 0" - 6"
ANALYTE	CONC
Nic:el	000

SAMPLE ID - B-343	DEPTH - 12" - 24"
ANALYTE	CONC
Copper	200
Nic:el	1,030

SAMPLE ID - B-342	DEPTH - 12" - 24"
ANALYTE	CONC
Copper	33,000
Nic:el	2,000

SAMPLE ID - B-4	DEPTH - 0" - 6"	DEPTH - 12" - 18"
ANALYTE	CONC	CONC
Copper	00,400	00,000
Nic:el	0,000	1,300

SAMPLE ID - B-341	DEPTH - 12" - 36"
ANALYTE	CONC
Copper	330
Nic:el	10,000

SAMPLE ID - B-8	DEPTH - 12" - 18"
ANALYTE	CONC
Copper	000
Nic:el	412


SAMPLE ID - B-10	DEPTH - 12" - 18"
ANALYTE	CONC
Nic:el	000

SAMPLE ID - B-12	DEPTH - 0" - 6"
ANALYTE	CONC
Copper	1,200
Nic:el	400

LE END

- Suil-Sla Borin Location (E) M, 2000
- Data ap Investi ation Borin Location (E) M, 20100
- Data ap Investi ation ori ontal Borin Location (E) M, 20100

NOT TO SCALE




NOTES:  
 1) Base ap and sa ple locations ta en (ro) Data ap Investi ation (E) M, 0000  
 2) Only analytes that exceed Co ercial use SCOs are shown, for a co plete su il any  
 oi analytical results see ta les in Attach ent B.



GSP Holdings, Inc.  
 Celi Drive BCP Site (BCP Site #C734108)  
 Remedial Alternatives Analysis  
 Exceedances of Commercial Use  
 SCOs in AOC-1

Job Number | 37-11082  
 Revision | A  
 Date | 11.12.2013  
**Figure 4-2**




LE END

**Inset A Scale (1"=5')**

SAMPLE ID - CON-003	DEPTH - 3'	ANALYTE	CONC
Total Chro: iu	2.0		
Copper	1.0		
Ni: el	0.1		

SAMPLE ID - CON-001	DEPTH - 3'	ANALYTE	CONC
Ni: el	4.0		

SAMPLE ID - CON-002	DEPTH - 3'	ANALYTE	CONC
Total Chro: iu	3.0		
Ni: el	0.0		




SAMPLE ID - Ditch	DEPTH -	ANALYTE	CONC
Total Chro: iu	4.0		
Copper	0.2		
Ni: el	1.0		
inc	1.0		
Cad: iu	4.0		
exavalent Chro: iu	14.0		
Lead	0.3		

SAMPLE ID - GSP-1	DEPTH -	ANALYTE	CONC
Total Chro: iu	1.0		
Copper	1.0		
Ni: el	2.0		

**NOTES:**

- Base map and sample locations taken from the Data Investigation Report (E) M, 2( ) 12( )
- Only analytes that exceed restricted use SCOs are shown, for a complete summary of analytical results see tables in Attachment B.




GSP Holdings, Inc.  
Cell Drive BCP Site (BCP Site #C734108)  
Remedial Alternatives Analysis  
Exceedances of Unrestricted Use SCOs in AOC-2




Job Number 37-11082  
Revision A  
Date 11.12.2013 **Figure 5-1**





LE END

- Source Identification Investigation Sample Locations (E, M, 2)
- ⊕ Groundwater Monitoring Wells (E, M, 2)
- ▲ Data Acquisition Investigation Soil Boring Location (E, M, 2)
- ⊕ Data Acquisition Investigation Groundwater Monitoring Wells (E, M, 2)
- ▨ Area of Excavation (0' to 2' to Meet Unrestricted Use SCOs (Approximate))
- ▩ Area of Excavation (0' to 1' to Meet Unrestricted Use SCOs (Approximate))
- ▧ Area of Excavation (0' to 0' to Meet Unrestricted Use SCOs (Approximate))
- BCP Site Boundary (Approximate)
- Property Boundary (Approximate)
- Property to be Purchased (Approximate)



GSP Holdings, Inc.  
 Celli Drive BCP Site (BCP Site #C734108)  
 Remedial Alternatives Analysis  
 Area of Remediation to Meet  
 Unrestricted Use SCOs in AOC-2




One Remington Park Drive  
 Cazenovia NY 13035 USA  
 T 1 315 679 5800 F 1 315 679 5801  
 E cazmail@ghd.com W www.ghd.com

NOTES:  
 1. Base map and sample locations taken from the Data Acquisition Investigation Report (E, M, June 2012)


Job Number | 37-11082  
 Revision | A  
 Date | 05.12.2014

Figure 5-2



LE END

- Source Identification Investigation Sample Locations (E) M, 2
- ⊕ Groundwater Monitoring Wells (E) M, 2
- ▲ Data Tap Investigation Soil Boring Location (E) M, 2
- ⊕ Data Tap Investigation Groundwater Monitoring Wells (E) M, 2
- BCP Site Boundary (Approximate)
- Property Boundary (Approximate)
- Property to be Purchased (Approximate)



**NOTES:**

- 1) Base map and sample locations taken from the Data Tap Investigation Report (E) M, June 2012
- 2) Only analytes that exceed Commercial Use SCOs are shown, for a complete summary of analytical results see tables in Attachment B




GSP Holdings, Inc.  
Cell Drive BCP Site (BCP Site #C734108)  
Remedial Alternatives Analysis  
Exceedances of Commercial Use  
SCOs in AOC-2




One Remington Park Drive  
Cazenovia NY 13035 USA  
T 1 315 679 5800 F 1 315 679 5801  
E cazmail@ghd.com W www.ghd.com

Job Number | 37-11082  
Revision | A  
Date | 11.12.2013 **Figure 5-3**



LEI END

- Source Identification Investigation Sample Locations (EIM, 2010)
- ⊕ Groundwater Monitoring Wells (EIM, 2010)
- ▲ Data Acquisition Investigation Soil Boring Location (EIM, 2010)
- ⊕ Data Acquisition Investigation Groundwater Monitoring Wells (EIM, 2010)
- ▨ Area of Interim Excavation (0' to 1' to Meet Commercial Use SCOs (Approximate))
- ▩ Area of Interim Excavation (0' to 2' to Meet Commercial Use SCOs (Approximate))
- ▧ Area of Interim Excavation (0' to 3' to Meet Commercial Use SCOs (Approximate))
- BCP Site Boundary (Approximate)
- Property Boundary (Approximate)
- Property to be Purchased (Approximate)



GSP Holdings, Inc.  
 Cell Drive BCP Site (BCP Site #C734108)  
 Remedial Alternatives Analysis  
 Area of Remediation to Meet  
 Commercial Use SCOs in AOC-2




One Remington Park Drive  
 Cazenovia NY 13035 USA  
 T 1 315 679 5800 F 1 315 679 5801  
 E cazmail@ghd.com W www.ghd.com

NOTES:  
 1. Base map and sample locations taken from the Data Acquisition Investigation Report (EIM, June 2012)

Job Number | 37-11082  
 Revision | A  
 Date | 05.12.2014

Figure 5-4



LE END

● Source Identification Investigation Sample Locations (E, M, 2)

⊕ Groundwater Monitoring Wells (E, M, 2)

▲ Data Acquisition Soil Boring Location (E, M, 2)


⊕ Data Acquisition Groundwater Monitoring Wells (E, M, 2)

Red line: BCP Site Boundary (Approximate)

Black line: Property Boundary (Approximate)

Black dashed line: Property to be Purchased (Approximate)


White box: Indicates Analyte also Exceeds Commercial Use SCO



**NOTES:**

1) Base map and sample locations taken from the Data Acquisition Report (E, M, 2) 12/12/13


2) Only analytes that exceed restricted use SCOs below the upper foot of soil are shown, for a complete list of analytical results see tables in Attachment B



GSP Holdings, Inc.  
 Cell Drive BCP Site (BCP Site #C734108)  
 Remedial Alternatives Analysis  
 Exceedances of SCOs Remaining  
 Below Upper Foot in AOC-2



Job Number | 37-11082  
 Revision | A  
 Date | 11.12.2013 Figure 5-5



SAMPLE ID - 348	DEPTH - 5.5' - 6.5'
<b>ANALYTE</b>	<b>CONC</b> [ ] [ ] [ ] [ ] [ ]
Total Chro: iul	2 [ ]
Copper	43 [ ]
Nickel	3 [ ]
inc	1 [ ]

SAMPLE ID - 349	DEPTH - 5.5' - 6.5'
<b>ANALYTE</b>	<b>CONC</b> [ ] [ ] [ ] [ ] [ ]
hexavalent Chro: iul	1 [ ] 12 [ ]
inc	342 [ ]

**Inferred Location of Culvert** →

- LE [ ] END [ ]
- ▲ Data [ ] ap Invest[ ] ation Soil Borin[ ] Location [ ] E [ ] M, [ ] 2 [ ] 1 [ ] [ ]
  - Stor[ ] water Catch Basin Location [ ] Approx[ ] [ ] ate [ ]

**NOTES**


- 1) Base [ ] ap and sa [ ] ple locations tai en [ ] rol [ ] the Data [ ] ap Invest[ ] ation [ ] eport [ ] E [ ] M, [ ] [ ] une 2 [ ] 12 [ ] [ ]
- 2) Only analytes that exceed [ ] nrestricted [ ] se SCOs are shown, [ ] or a co [ ] plete su [ ] [ ] ary o [ ] analytical results see tai [ ] les in Attach [ ] ent B [ ]



GSP Holdings, Inc.  
 Celi Drive BCP Site (BCP Site #C734108)  
 Remedial Alternatives Analysis  
**Exceedances of Unrestricted Use SCOs in AOC-3**

One Remington Park Drive  
 Cazenovia NY 13035 USA  
 T +1 315 679 5800 F +1 315 679 5801  
 E cazmail@ghd.com W www.ghd.com

Job Number 37-11082  
 Revision A  
 Date 11.12.2013 **Figure 6-1**



SAMPLE ID - 339	DEPTH - 0" - 2"	DEPTH - 12" - 14"	DEPTH - 22" - 24"
ANALYTE	CONC	CONC	CONC
exavalent Chro: iul	14		4
inc	132		

SAMPLE ID - 326	DEPTH - 0" - 2"
ANALYTE	CONC
Total Chro: iul	1,000
exavalent Chro: iul	14
Copper	1,4
Nici: el	331
inc	1

SAMPLE ID - 221	DEPTH - 3" - 6"
ANALYTE	CONC
Total Chro: iul	
Copper	20
Nici: el	

SAMPLE ID - 325	DEPTH - 0" - 2"
ANALYTE	CONC
Total Chro: iul	31
exavalent Chro: iul	22
Copper	44
Nici: el	143
inc	4

SAMPLE ID - 206	DEPTH - 13" - 16"
ANALYTE	CONC
Nici: el	32.3

SAMPLE ID - 208	DEPTH - 3" - 6"
ANALYTE	CONC
Total Chro: iul	31
Copper	112
Nici: el	44

SAMPLE ID - 203	DEPTH - 3" - 6"	DEPTH - 13" - 16"
ANALYTE	CONC	CONC
Total Chro: iul		
Copper	3	121
Nici: el		4

SAMPLE ID - 204	DEPTH - 3" - 6"
ANALYTE	CONC
Total Chro: iul	13
Copper	4
Nici: el	21

SAMPLE ID - 201	DEPTH - 3" - 6"
ANALYTE	CONC
Total Chro: iul	11
Copper	311
Nici: el	12

SAMPLE ID - 202	DEPTH - 3" - 6"	DEPTH - 13" - 16"
ANALYTE	CONC	CONC
Total Chro: iul	3.3	2.1
Copper	3.4	31
Nici: el	244	22

SAMPLE ID - 225	DEPTH - 0" - 2"
ANALYTE	CONC
inc	1

SAMPLE ID - 224	DEPTH - 0" - 2"
ANALYTE	CONC
Total Chro: iul	3
Copper	3
inc	2

SAMPLE ID - 337	DEPTH - 0" - 2"	DEPTH - 12" - 14"
ANALYTE	CONC	CONC
Total Chro: iul	12.3	12
exavalent Chro: iul	14	1
Copper	4.1	3
Nici: el	34	23
inc		

SAMPLE ID - 336	DEPTH - 0" - 2"
ANALYTE	CONC
exavalent Chro: iul	3

SAMPLE ID - 331	DEPTH - 0" - 2"	DEPTH - 12" - 14"
ANALYTE	CONC	CONC
exavalent Chro: iul	14	22

SAMPLE ID - 330	DEPTH - 0" - 2"
ANALYTE	CONC
Total Chro: iul	3.3
exavalent Chro: iul	
Copper	1.0
Nici: el	10
inc	3

SAMPLE ID - 214	DEPTH - 3" - 6"	DEPTH - 12" - 16"
ANALYTE	CONC	CONC
Total Chro: iul	2	4.3
Copper	3	14
Nici: el	2.2	

SAMPLE ID - 213	DEPTH - 6" - 12"
ANALYTE	CONC
Total Chro: iul	
Copper	4.3
Nici: el	2

SAMPLE ID - 218	DEPTH - 3" - 6"
ANALYTE	CONC
Total Chro: iul	321
Copper	1.1
Nici: el	412

SAMPLE ID - 217	DEPTH - 3" - 6"	DEPTH - 13" - 16"
ANALYTE	CONC	CONC
Copper	41	
Nici: el		1

SAMPLE ID - 334	DEPTH - 0" - 2"	DEPTH - 12" - 14"	DEPTH - 22" - 24"
ANALYTE	CONC	CONC	CONC
exavalent Chro: iul	22	4	2

SAMPLE ID - 333	DEPTH - 0" - 2"	DEPTH - 22" - 24"
ANALYTE	CONC	CONC
Total Chro: iul	3	13
exavalent Chro: iul	3	2
Copper	313	
Nici: el	2.1	
inc	1	

SAMPLE ID - 321	DEPTH - 0" - 2"
ANALYTE	CONC
Total Chro: iul	1
Copper	1.3
Nici: el	121

SAMPLE ID - 216	DEPTH - 3" - 6"
ANALYTE	CONC
Total Chro: iul	31
Copper	1.1
Nici: el	2.33

SAMPLE ID - 332	DEPTH - 0" - 2"	DEPTH - 22" - 24"
ANALYTE	CONC	CONC
exavalent Chro: iul		1.1

SAMPLE ID - 335	DEPTH - 0" - 2"	DEPTH - 12" - 14"	DEPTH - 22" - 24"
ANALYTE	CONC	CONC	CONC
Total Chro: iul		22	1
exavalent Chro: iul		3.3	1.1
Copper		23	2
Nici: el		2	1
inc	1	4	4

SAMPLE ID - 200	DEPTH - 3" - 6"	DEPTH - 13" - 16"
ANALYTE	CONC	CONC
Total Chro: iul	1.4	
Copper	22	1.2
Nici: el	1	

SAMPLE ID - 227	DEPTH - 1" - 3"	DEPTH - 13" - 15"
ANALYTE	CONC	CONC
Total Chro: iul	3.4	
Copper	4	
Nici: el		3
inc	1.3	

SAMPLE ID - 212	DEPTH - 3" - 6"	DEPTH - 13" - 16"
ANALYTE	CONC	CONC
Total Chro: iul	3.3	
Copper	1	1

SAMPLE ID - 329	DEPTH - 0" - 2"
ANALYTE	CONC
Total Chro: iul	3
Copper	
inc	22

SAMPLE ID - 231	DEPTH - 0" - 2"
ANALYTE	CONC
Total Chro: iul	4
Copper	1
inc	3

SAMPLE ID - 322	DEPTH - 0" - 2"
ANALYTE	CONC
Total Chro: iul	22
Copper	1.22
Nici: el	333
inc	3.3

SAMPLE ID - 232	DEPTH - 0" - 2"	DEPTH - 13" - 15"
ANALYTE	CONC	CONC
Copper	1	
inc	1.4	

SAMPLE ID - 215	DEPTH - 3" - 6"
ANALYTE	CONC
Copper	1

NOTES:  
 1) Base map and sample locations taken from the Data Investigation Report (EIM, June 2012).  
 2) Only analytes that exceed the restricted use SCOs are shown, for a complete summary of analytical results see tables in Attachment B.



GSP Holdings, Inc.  
 Cell Drive BCP Site (BCP Site #C734108)  
 Remedial Alternatives Analysis  
 Exceedances of Unrestricted Use  
 SCOs in AOC-4

One Remington Park Drive  
 Cazenovia NY 13035 USA  
 T 1 315 679 5800 F 1 315 679 5801  
 E cazmail@ghd.com W www.ghd.com


Job Number 37-11082  
 Revision A  
 Date 11.12.2013 Figure 7-1a

LEI END  
 ● Source Identification Investigation Sample Locations (EIM, 2012)  
 ▲ Data Investigation Soil Boring Location (EIM, 2012)



LE END

- Source Identification Investigation Sample Locations (E, M, 2)
- ▲ Data Acquisition Soil Boring Location (E, M, 2)



NOTES:  
 1) Base map and sample locations taken from the Data Acquisition Report (E, M, 2) June 2012.  
 2) Only analytes that exceed unrestricted use SCOs are shown, for a complete suite of analytical results see tables in Attachment B.



GSP Holdings, Inc.  
 Celi Drive BCP Site (BCP Site #C734108)  
 Remedial Alternatives Analysis  
 Exceedances of Unrestricted Use  
 SCOs in AOC-4

Job Number | 37-11082  
 Revision | A  
 Date | 11.12.2013  
**Figure 7-1b**



LEI ENDI

- Source Identification Investigation Sample Locations (E) M, 2000
- ▲ Data Acquisition Investigation Soil Boring Location (E) M, 2010
- ▨ Area of Excavation (to 1' to Meet Unrestricted Use SCOs (Approximate))
- ▨ Area of Excavation (to 2' to Meet Unrestricted Use SCOs (Approximate))

NOTES:  
 1) Base map and sample locations taken from the Data Acquisition Investigation Report (E) M, June 2012

SCALE 1" = 100' AT ORIGINAL SIZE

GSP Holdings, Inc.  
 Cell Drive BCP Site (BCP Site #C734108)  
 Remedial Alternatives Analysis  
 Area of Remediation to Meet  
 Unrestricted Use SCOs in AOC-4

One Remington Park Drive  
 Cazenovia NY 13035 USA  
 T 1 315 679 5800 F 1 315 679 5801  
 E cazmail@ghd.com W www.ghd.com


Job Number | 37-11082  
 Revision | A  
 Date | 06.06.2014 **Figure 7-2a**





LEGEND

- Source Identification Investigation Sample Locations (EIM, June 2012)
- ▲ Data Support Investigation Soil Boring Location (EIM, June 2012)
- ▨ Area of Required Excavation (0' to 2' to Meet Unrestricted Use SCOs (Approximate))



NOTES


1. Base map and sample locations taken from the Data Support Investigation Report (EIM, June 2012)



GSP Holdings, Inc.  
 Celi Drive BCP Site (BCP Site #C734108)  
 Remedial Alternatives Analysis  
**Area of Remediation to Meet  
 Unrestricted Use SCOs in AOC-4**

Job Number | 37-11082  
 Revision | A  
 Date | 06.06.2014

**Figure 7-2b**



SAMPLE ID - 339	DEPTH - 0" - 2"	DEPTH - 12" - 14"	DEPTH - 22" - 24"
ANALYTE	CONC	CONC	CONC
exavalent Chro: iul	14		4
inc	132		

SAMPLE ID - 326	DEPTH - 0" - 2"
ANALYTE	CONC
Total Chro: iul	1
exavalent Chro: iul	14
Copper	1.4
Nici: el	331
inc	1

SAMPLE ID - 221	DEPTH - 3" - 6"
ANALYTE	CONC
Total Chro: iul	
Copper	2
Nici: el	

SAMPLE ID - 325	DEPTH - 0" - 2"
ANALYTE	CONC
Total Chro: iul	31
exavalent Chro: iul	22
Copper	44
Nici: el	143
inc	4

SAMPLE ID - 206	DEPTH - 13" - 16"
ANALYTE	CONC
Nici: el	32.3

SAMPLE ID - 338	DEPTH - 12" - 14"	DEPTH - 22" - 24"
ANALYTE	CONC	CONC
inc	4	32

SAMPLE ID - 208	DEPTH - 3" - 6"
ANALYTE	CONC
Copper	112
Nici: el	4

SAMPLE ID - 203	DEPTH - 3" - 6"	DEPTH - 13" - 16"
ANALYTE	CONC	CONC
Total Chro: iul		
Copper	3	121
Nici: el		4

SAMPLE ID - 204	DEPTH - 3" - 6"
ANALYTE	CONC
Total Chro: iul	13
Copper	4
Nici: el	21

SAMPLE ID - 201	DEPTH - 3" - 6"
ANALYTE	CONC
Total Chro: iul	11
Copper	311
Nici: el	12

SAMPLE ID - 202	DEPTH - 3" - 6"	DEPTH - 13" - 16"
ANALYTE	CONC	CONC
Total Chro: iul	3.3	2.1
Copper	3.4	31
Nici: el	244	22

SAMPLE ID - 225	DEPTH - 0" - 2"
ANALYTE	CONC
inc	1

SAMPLE ID - 224	DEPTH - 0" - 2"
ANALYTE	CONC
Copper	3
inc	2

SAMPLE ID - 335	DEPTH - 0" - 2"	DEPTH - 12" - 14"	DEPTH - 22" - 24"
ANALYTE	CONC	CONC	CONC
Total Chro: iul		22	1
exavalent Chro: iul		3.3	1.1
Copper		23	2
Nici: el		2	1
inc	1	4	4

SAMPLE ID - 200	DEPTH - 3" - 6"	DEPTH - 13" - 16"
ANALYTE	CONC	CONC
Total Chro: iul	1.4	
Copper	22	1.2
Nici: el	1	

SAMPLE ID - 227	DEPTH - 1" - 3"	DEPTH - 13" - 15"
ANALYTE	CONC	CONC
Total Chro: iul	3.4	
Copper	4	
Nici: el		3
inc	1.3	

SAMPLE ID - 212	DEPTH - 3" - 6"	DEPTH - 13" - 16"
ANALYTE	CONC	CONC
Copper	1	1

SAMPLE ID - 329	DEPTH - 0" - 2"
ANALYTE	CONC
Copper	
inc	22

SAMPLE ID - 231	DEPTH - 0" - 2"
ANALYTE	CONC
Total Chro: iul	4
Copper	1
inc	3

SAMPLE ID - 322	DEPTH - 0" - 2"
ANALYTE	CONC
Total Chro: iul	22
Copper	1.22
Nici: el	333
inc	3.3

SAMPLE ID - 232	DEPTH - 0" - 2"	DEPTH - 13" - 15"
ANALYTE	CONC	CONC
Copper	1	
inc	1.4	

SAMPLE ID - 215	DEPTH - 3" - 6"
ANALYTE	CONC
Copper	1

SAMPLE ID - 337	DEPTH - 0" - 2"	DEPTH - 12" - 14"
ANALYTE	CONC	CONC
Total Chro: iul	12.3	12
exavalent Chro: iul	14	1
Copper	4.1	3
Nici: el	34	23
inc		

SAMPLE ID - 336	DEPTH - 0" - 2"
ANALYTE	CONC
exavalent Chro: iul	3

SAMPLE ID - 331	DEPTH - 0" - 2"	DEPTH - 12" - 14"
ANALYTE	CONC	CONC
exavalent Chro: iul	14	22

SAMPLE ID - 330	DEPTH - 0" - 2"
ANALYTE	CONC
Total Chro: iul	3.3
exavalent Chro: iul	
Copper	1
Nici: el	1
inc	3

SAMPLE ID - 214	DEPTH - 3" - 6"	DEPTH - 12" - 16"
ANALYTE	CONC	CONC
Total Chro: iul	2	4.3
Copper	3	14
Nici: el	2.2	

SAMPLE ID - 213	DEPTH - 6" - 12"
ANALYTE	CONC
Total Chro: iul	
Copper	4.3
Nici: el	2

SAMPLE ID - 218	DEPTH - 3" - 6"
ANALYTE	CONC
Total Chro: iul	321
Copper	1.1
Nici: el	412

SAMPLE ID - 217	DEPTH - 3" - 6"	DEPTH - 13" - 16"
ANALYTE	CONC	CONC
Copper	41	
Nici: el		1

SAMPLE ID - 334	DEPTH - 0" - 2"	DEPTH - 12" - 14"	DEPTH - 22" - 24"
ANALYTE	CONC	CONC	CONC
exavalent Chro: iul	22	4	4.2


SAMPLE ID - 333	DEPTH - 0" - 2"	DEPTH - 22" - 24"
ANALYTE	CONC	CONC
Total Chro: iul	3	13
exavalent Chro: iul	3	13
Copper	313	1.2
Nici: el	2.1	
inc	1	

SAMPLE ID - 216	DEPTH - 3" - 6"
ANALYTE	CONC
Total Chro: iul	31
Copper	1.1
Nici: el	2.33

SAMPLE ID - 332	DEPTH - 0" - 2"	DEPTH - 22" - 24"
ANALYTE	CONC	CONC
exavalent Chro: iul		1.1

SAMPLE ID - 321	DEPTH - 0" - 2"
ANALYTE	CONC
Total Chro: iul	1
Copper	1.3
Nici: el	121

NOTES:  
 1) Base map and sample locations taken from the Data map Investigation Report (EIM, June 2012)  
 2) Only analytes that exceed Protection of Ecological Resources SCOs are shown, for a complete summary of analytical results see tables in Attachment B



GSP Holdings, Inc.  
 Cell Drive BCP Site (BCP Site #C734108)  
 Remedial Alternatives Analysis  
 Exceedances of Protection of  
 Eco. Resources SCOs in AOC-4

One Remington Park Drive  
 Cazenovia NY 13035 USA  
 T 1 315 679 5800 F 1 315 679 5801  
 E cazmail@ghd.com W www.ghd.com

Job Number 37-11082  
 Revision A  
 Date 11.12.2013 Figure 7-3a

LEI END  
 ● Source Identification Investigation Sample Locations (EIM, 2012)  
 ▲ Data Map Investigation Soil Boring Location (EIM, 2012)



LE END

- Source Identification Investigation Sample Locations (E, M, 2)
- ▲ Data Acquisition Soil Boring Location (E, M, 2)



NOTES:  
 1) Base map and sample locations taken from the Data Acquisition Report (E, M, 2) June 12, 2013.  
 2) Only analytes that exceed Protection of Ecological Resources SCOs are shown, for a complete summary of any other analytical results see tables in Attachment B.



GSP Holdings, Inc.  
 Celi Drive BCP Site (BCP Site #C734108)  
 Remedial Alternatives Analysis  
 Exceedances of Protection of Ecological Resources SCOs in AOC-4

Job Number | 37-11082  
 Revision | A  
 Date | 11.12.2013  
**Figure 7-3b**



LEI ENDI

- Source Identification Investigation Sampling Locations (E) M, 20' ±
- ▲ Data Investigation Soil Boring Location (E) M, 2' ±
- ▨ Area of Utility Excavation (0' to 1' to Meet Protection of Ecological Resources SCOs (Approximate))
- ▨ Area of Utility Excavation (0' to 2' to Meet Protection of Ecological Resources SCOs (Approximate))

NOTES:  
 1) Base map and sampling locations taken from the Data Investigation Report (E) M, June 2012

SCALE 1" = 100' AT ORIGINAL SIZE

GSP Holdings, Inc.  
 Cell Drive BCP Site (BCP Site #C734108)  
 Remedial Alternatives Analysis  
 Area of Remediation to Meet Protection of Eco. Resources SCOs in AOC-4

One Remington Park Drive  
 Cazenovia NY 13035 USA  
 T 1 315 679 5800 F 1 315 679 5801  
 E cazmail@ghd.com W www.ghd.com

Job Number | 37-11082  
 Revision | A  
 Date | 06.06.2014 **Figure 7-4a**



Legend

- Source Identification Investigation Sample Locations (EIM, 2011)
- ▲ Data Support Investigation Soil Boring Location (EIM, 2011)
- ▨ Area of Required Excavation (0' to 2' to Meet Protection of Ecological Resources SCOs (Approximate))



NOTES:  
 1. Base map and sample locations taken from the Data Support Investigation Report (EIM, June 2012)



GSP Holdings, Inc.  
 Celi Drive BCP Site (BCP Site #C734108)  
 Remedial Alternatives Analysis  
 Area of Remediation to Meet Protection  
 of Eco. Resources SCOs in AOC-4

Job Number | 37-11082  
 Revision | A  
 Date | 06.06.2014

Figure 7-4b

Tables



**Table 4-1 - Alternative Analysis Preliminary Estimates of Cost for AOC-1**

**Remedial Alternatives Analysis**

Celi Drive BCP Site

BCP Site No C734108

July 2017

		<b>Track 4: Commercial Uses with Site Management</b>		
Elements of Cost	Units	Quantity	Unit Cost (\$)	Sub Cost
<b>Estimated Capital Costs</b>				
Remedial Design	LS	1	5,000	5,000
Evaluation of slab and sealing of cracks	LS	1	10,000	10,000
(1) Documentation	LS	1	5,000	5,000
			<b>Present Worth Capital Cost:</b>	<b>\$20,000</b>
<b>Estimated Annual Costs</b>				
(2) Annual Operating Costs				0
Annual Certification Reporting	Annual Cost			5,000
			<b>(a) Present Worth Annual Cost:</b>	<b>\$100,942</b>
			<b>Total Estimated Present Worth Cost:</b>	<b>\$120,942</b>
			<b>Rounded to nearest \$1,000:</b>	<b>\$121,000</b>

Notes:

This cost estimate is preliminary based on preliminary concepts and available information, and is subject to change.

A Remedial Design has not been prepared, so this estimate has considerable uncertainty based on final scope of work and regulatory approvals.

This cost estimate does not include any remedial action associated with groundwater.

Future maintenance of soil cover including repairs are considered part of current site operations costs and are not included here.

A Track 1 Unrestricted Use Alternative would require removal of the entire building, which is deemed not feasible.

(1) Documentation includes Final Engineering Report and an Environmental Easement for on-Site areas.

(2) No annual operating cost based on assumption there is no required groundwater or surface water monitoring.

(a) Present worth annual cost based on 30 years of annual costs at a net interest rate of 3%



**Table 5-1 - Alternative Analysis Preliminary Estimates of Costs for AOC-2 Remedial Alternatives Analysis**  
 Celi Drive BCP Site  
 BCP Site No C734108  
 July 2017

		Track 1: Restoration to Pre-Disposal or Unrestricted Conditions by Excavating to Unrestricted Standards (~11,100 sq. ft. - 0.25 acres)			Track 4: Restoration to Commercial Uses with Site Management by 1 Foot Soil Cover Engineering Control (~12,400 sq. ft. - 0.28 acres)		
Elements of Cost	Units	Quantity	Unit Cost (\$)	Sub Cost	Quantity	Unit Cost (\$)	Sub Cost
<b>Estimated Capital Costs</b>							
Remedial Design	LS	1	45,000	45,000	1	15,000	15,000
Contract Documents/Contractor Selection	LS	1	25,000	25,000	1	15,000	15,000
<b>Sediment/Erosion Control</b>							
Plan	LS	1	10,000	10,000	1	8,000	8,000
Perimeter Controls	lf	500	3	1,500	600	3	1,800
Contractor Mobilization	LS	1	8,000	8,000	1	8,000	8,000
Grading/Clearing/Grubbing	sf	12,765	0.50	6,383	14,260	0.75	10,695
Survey Pre/Post	ls	1	15,000	15,000	1	12,000	12,000
<b>Soil Removal</b>							
(1) Excavate	cy	2,700	15	40,500	528	15	7,922
Haul/Disposal	tons	4,455	80	356,400	882	80	70,561
Sampling/Analysis	each	36	500	18,000	30	500	15,000
Dewatering and Disposal	gal	10,000	1	10,000	2,500	1	2,500
<b>Backfill</b>							
(2) Off-site Topsoil	cy	420	35	14,700	264	35	9,243
(2) Off-site Gen Fill	cy	2,280	25	57,000	264	25	6,602
Sampling/Analysis	each	5	2,000	10,000	3	2,000	6,000
Demarcation Layer	sy				1,222	4	4,278
Reinstall Fencing	LS	1	5,000	5,000	1	5,000	5,000
Seeding/Fertilizer-Hydroseed	acre	0.50	1,500	750	0.28	1,500	420
Site Representative/Contract Admin	day	30	3,000	90,000	15	2,500	37,500
(3) Documentation	LS	1	50,000	50,000	1	25,000	25,000
				<b>Present Worth Capital Cost:</b>	<b>\$763,233</b>	<b>Present Worth Capital Cost:</b>	
						<b>\$260,520</b>	
<b>Estimated Annual Costs</b>							
(4) Annual Operating Costs				0	4	6500	26,000
Annual Certification Reporting	Annual Cost			0			5,000
				<b>(a) Present Worth Annual Cost:</b>	<b>\$0</b>	<b>Present Worth Annual Cost:</b>	
						<b>\$223,587</b>	
				<b>Total Estimated Present Worth Cost:</b>	<b>\$763,233</b>	<b>Total Estimated Present Worth Cost:</b>	
				<b>Rounded to nearest \$1,000:</b>	<b>\$763,000</b>	<b>Rounded to nearest \$1,000:</b>	
						<b>\$484,107</b>	
						<b>\$484,000</b>	

Notes:

- This cost estimate is preliminary based on preliminary concepts and available information, and is subject to change.
- A Remedial Design has not been prepared, so this estimate has considerable uncertainty based on final scope of work and regulatory approvals.
- This cost estimate does not include any remedial action associated with groundwater.
- Future maintenance of soil cover including repairs and/or mowing are considered part of current site operations costs and are not included here.
- This cost estimate does not include any costs associated with acquiring property from the adjacent property owner.
- (1) Assumes excavation up to 8 feet bgs across the AOC to achieve Unrestricted Use SCOs.
- (2) Assumes up to 7 feet of general fill and 1 foot of topsoil across the excavated area.
- (3) Documentation for both alternatives include Final Engineering Report. Documentation for Track 4 Alternative also includes an Environmental Easement for on-Site areas.
- (4) Operating cost for Track 1 based on no monitoring, Track 4 based on assumption there is quarterly groundwater monitoring for a period of 5 years.
- (a) Present worth annual cost based on 30 years of annual reporting costs and 5 years of annual monitoring costs at a net interest rate of 3%





**Table 6-1 - Alternative Analysis Preliminary Estimates of Costs for AOC-3 Remedial Alternatives Analysis**  
 Celi Drive BCP Site  
 BCP Site No C734108  
 July 2017

		<b>Track 1: Restoration to Pre-Disposal or Unrestricted Conditions by Excavating to Unrestricted Standards and Cleaning Culvert Pipe (~1,600 sq. ft. - 0.04 acres and ~1,100 feet of culvert*)</b>		
Elements of Cost	Units	Quantity	Unit Cost (\$)	Sub Cost
<b>Estimated Capital Costs</b>				
Remedial Design	LS	1	20,000	20,000
Contract Documents/Contractor Selection	LS	1	15,000	15,000
Site Access	LS	1	10,000	10,000
Sediment/Erosion Control				
Plan	LS	1	8,000	8,000
Perimeter Controls	lf	160	3	480
Contractor Mobilization	LS	1	7,500	7,500
Grading/Clearing/Grubbing	sf	1,600	0.50	800
Soil Removal				
(1) Excavate	cy	2,000	15	30,000
Haul/Disposal	tons	3,300	80	264,000
Sampling/Analysis	each	6	500	3,000
Backfill				
(2) Off-site Topsoil	cy	60	35	2,100
(2) Off-site Gen Fill	cy	2,000	25	50,000
Sampling/Analysis	each	4	2,000	8,000
Pressure Wash Culvert Pipe/Disposal	LS	1	50,000	50,000
Seeding/Fertilizer-Hydroseed	acre	0.04	1,000	40
Site Representative/Contract Admin	day	20	3,000	60,000
(3) Documentation	LS	1	30,000	30,000
			<b>Present Worth Annual Cost:</b>	<b>\$558,920</b>
<b>Estimated Annual Costs</b>				
(4) Annual Operating Costs				0
			<b>(a) Present Worth Annual Cost:</b>	<b>\$0</b>
			<b>Total Estimated Present Worth Cost:</b>	<b>\$558,920</b>
			<b>Rounded to nearest \$1,000:</b>	<b>\$559,000</b>

Notes:

This cost estimate is preliminary based on preliminary concepts and available information, and is subject to change.

A Remedial Design has not been prepared, so this estimate has considerable uncertainty based on final scope of work and regulatory approvals.

This cost estimate does not include any remedial action associated with groundwater.

\* Excavation required in a discrete area of the culvert pipe to a depth of 7 feet to meet Unrestricted SCOs.

(1) Assumes excavation up to 6 feet bgs in area of the AOC-3 to achieve Unrestricted Use SCOs along entire length.

(2) Assumes up to 5 feet of general fill and 1 foot of topsoil across the excavated area.

(3) Documentation includes Final Engineering Report.

(4) No annual operating cost based on assumption there is no required groundwater or surface water monitoring.

(a) Present worth annual cost based on 30 years of annual costs at a net interest rate of 3%



**Table 7-1 - Alternative Analysis Preliminary Estimates of Costs for AOC-4 Remedial Alternatives Analysis**  
 Celi Drive BCP Site  
 BCP Site No C734108  
 July 2017

		<b>Track 1: Restoration to Pre-Disposal or Unrestricted Conditions (Alternative 1) and Protection of Ecological Resources (Alternative 2) Conditions by Excavating to Standards (~78,000 sq. ft. - 1.8 acres)</b>		
Elements of Cost	Units	Quantity	Unit Cost (\$)	Sub Cost
<b>Estimated Capital Costs</b>				
Remedial Design	LS	1	40,000	40,000
Contract Documents/Contractor Selection	LS	1	25,000	25,000
<b>Sediment/Erosion Control</b>				
Plan	LS	1	25,000	25,000
Perimeter Controls	lf	9,000	3	27,000
<b>Contractor Mobilization</b>				
Access, ROW Work, and Permits	LS	1	25,000	25,000
Grading/Clearing/Grubbing	sf	80,000	0.50	40,000
Survey Pre/Post	LS	1	25,000	25,000
<b>Soil Removal</b>				
(1) Excavate	cy	5,778	15	86,667
Haul/Disposal	tons	9,533	65	619,667
Disposal Sampling/Analysis	each	10	1,500	15,000
Dewatering/Disposal	gal	50,000	1	50,000
Documentation Sampling and Analysis	each	210	300	63,000
<b>Backfill</b>				
(2) Off-site Topsoil	cy	0		
(2) Off-site Gen Fill	cy	2,204	25	55,100
Sampling/Analysis	each	4	1,000	4,000
Seeding/Fertilizer-Hydroseed	acre	1.80	1,500	2,700
Site Representative/Contract Admin	day	40	2,500	100,000
(3) Documentation	LS	1	50,000	50,000
<b>Present Worth Capital Cost:</b>				<b>\$1,268,133</b>
<b>Estimated Annual Costs</b>				
(4) Annual Operating Costs				0
Annual Certification Reporting	Annual Cost			0
<b>(a) Present Worth Annual Cost:</b>				<b>\$0</b>
<b>Total Estimated Present Worth Cost:</b>				<b>\$1,268,133</b>
<b>Rounded to nearest \$1,000:</b>				<b>\$1,268,000</b>

Notes:

This cost estimate is preliminary based on preliminary concepts and available information, and is subject to change.

The preliminary cost estimate assumes that the area associated with the Community Bank Development adjacent to Bridge Street will require no further remedial action. A Remedial Design has not been prepared, so this estimate has considerable uncertainty based on final scope of work and regulatory approvals.



This cost estimate does not include any remedial action associated with groundwater.

- (1) Assumes excavation up to 2 feet bgs across the AOC to achieve Unrestricted Use or Protection of Ecological Resources SCOs.
- (2) Assumes up to 1 foot of general fill and no backfill in top 1 foot across the excavated area as sediment will be removed to maintain flow.
- (3) Documentation for both alternatives include Final Engineering Report.
- (4) No annual operating cost based on assumption there is no required groundwater or surface water monitoring.
- (a) Present worth annual cost based on 30 years of annual costs at a net interest rate of 3%

Attachments

# Attachment A – Tax Map





Empire Zone  
Pt of Lot 51 Town of DeWitt  
Onondaga Co., N.Y.

Scale 1' = 60'

November 08, 2002



**D. W. HANNIG L.S., P.C.**

SURVEYORS - PLANNERS - CONSULTANTS  
THE MARKET PLACE, BUILDING #1  
MANLIUS, NEW YORK 13104  
PHONE: (315) 682-5225 - FAX: (315) 682-7774





THE UNDERSIGNED HEREBY CERTIFIES THAT THIS  
MAP WAS MADE FROM AN ACTUAL SURVEY, AND THAT  
BOTH MAP AND SURVEY ARE CORRECT. CERTIFICATION  
VOID UNLESS SIGNED WITH RED INK.

DAVID WILLIAM HANNIG, P.L.S., - N.Y.S. LIC. NO. 47411



Legend  
- - - Property Line  
- - - Easement Line

<b>Celi Drive Site</b>		
PREPARED FOR:	BCP / GSP	
 <b>ERM</b>	SCALE	1"=120'
	DATE	NOVEMBER 2005
	FIGURE	<b>1</b> BCP Application



M 1,112,000

BRIDGE DRIVE

CELL DRIVE

WHIRLYBIRD LANE

BRIDGE STREET

TOWPATH

CELL DRIVE SITE:

TAX MAP NO. 053-02-17.2

WATER 23.1  
WATER 155a(C)

STREET LIGHT 708.0

WATER EX 1 C

SEWER DIST. 1.13a(D)

3.30a(C)

BRIDGE STREET 770.3

STATE

STATE FOR HWY

08.1  
1.8a(C)

6

22.1

21.1

20.1

02.1

03

05

04

17.1

18

17.2

15

14

22.1

21.1

20.1

02.1

03

05

04

17.1

18

17.2



15

14




# Attachment B – Excerpts from Previous Investigation Reports

Attachment B-1 – Excerpts from Comprehensive  
Site Investigation Report, ERM, November 2005




- Legend**
- Property Line
  - Easement Line
  - 021A Soil/Sediment Sample Location
  - Comp 1 TCLP Soil Sample Location (composite)




<b>GSP / 5762 Celi Drive</b>		
<b>GSP Swale Layout</b>		
PREPARED FOR:	GENERAL SUPER PLATING	
Scale:	1"=20'	Sheet:
DATE:	SEPTEMBER 2005	4-1

E:\Projects\5762 Celi Drive\GSP Swale Layout.dwg (11/14/05) - 2500px Base



- Legend**
- - - Property Line
  - - - Easement Line
  - TP-1 □ Test Pit Locations
  - TPW-1 ⊕ Test Pit Well Locations

<b>GSP / 5762 Celi Drive</b>		
<b>GSP Swale - Test Pit Locations</b>		
PREPARED FOR: GENERAL SUPER PLATING		
	SCALE	FIGURE
	1"=50'	4-2
	DATE	
	SEPTEMBER 2005	



220

219  
(Sample collected at culvert pipe under  
Route 690 1/4 mile west of BSS)

221

NYS Rte. 690

208 207 206  
229 105 230

Bally's

209 210 211

Bridge Street Swale

205 204 222  
223 104 203

Bridge Street

Cellular One Building  
1-St. Conc. Block & Metal Siding

Bridge Street


226 225 224  
228 202 200  
103 201

214 213 212 231 218  
217 232 216 215 2101

Upstate "Bridge Street Swale"

106


- Legend
- Property Line
  - Easement Line
  - 200 Soil/Sediment Sample Location
  - 101 Surface Water Sample Location



GSP / 5762 Cell Drive  
 Bridge Street Swale - Sample Locations  
 GENERAL SUPER PLATING

Scale	1"=40'
DATE	SEPTEMBER 2005
Sheet	4-3

E:\Projects\5762 Cell Drive\5762 Cell Drive.dwg (11/14/05) - 2389a.dwg




**LEGEND**

● Sub-Slab Boring Location

<b>GSP SUB-SLAB SAMPLE LOCATIONS</b>		
PREPARED FOR: <b>GSP</b>		
	SCALE: <b>NTS</b>	FIGURE: <b>4-5</b>
	DATE: <b>September 2005</b>	




SHIPPING METALS #3




**LEGEND**

- Sub-Slab Boring Location
- ⊕ Temporary Monitoring Well Location

Conc. = Concentration of Contaminant at Specified Depth in Soil in mg/kg

<b>GSP Sub-Slab Total Chromium in Soil</b>		
PREPARED FOR:		GSP
 <b>ERM</b>	SCALE	NTS
	DATE	September 2005
		FIGURE <b>5-4</b>



1-St Brick  
5,632+- Sq. Ft  
General Super Plating N/F

47,089+- Sq Ft  
General Super Plating N/F  
5762 Celi Drive

Chrome Wastewater  
Equalization Tank

AA Wastewater  
Equalization Tank

Wastewater  
Pre-Treatment Plant

408.5  
GSP-MW-1  
408.64

408.35  
GSP-MW-2

409.0

409.5

410.0

410.48  
GSP-MW-3

### Site Groundwater

PREPARED FOR: GENERAL SUPER PLATING



SCALE  
1"=50'

DATE  
SEPTEMBER 2005

FIGURE  
5-9

- Legend**
- Property Line
  - Easement Line
  - Estimated Groundwater Contour
  - Estimated Groundwater Flow Direction
  - 410.48 Elevation of Groundwater Table at Monitoring Well Location



**TABLE 5-1**  
**Summary of GSP and Upstate Analytical Data - Soil**  
**Roof Drain Area and GSP Swale Area**  
**General Super Plating Company**  
**NYSDEC Spill No.: 0550288**  
**ERM Project No.: 0032572**

Sample ID/Location Matrix Date Sampled	Guidance NYSDEC TAGM #4046	* GSP-1 soil 5/10/2005	** Drain Point (solid) Solid 5/18/2005	**Ditch Solid 5/18/2005
<b>Metals (mg/Kg)</b>				
Cadmium	1 or SB	ND	NA	NA
Total Chromium	10 or SB	<b>1900.0</b>	NA	NA
Copper	25 or SB	<b>1500.0</b>	NA	NA
Lead	SB	22.0	NA	NA
Nickel	13 or SB	<b>210.0</b>	NA	NA
Silver	SB	ND	NA	NA
Zinc	20 or SB	<b>35</b>	NA	NA
<b>PCB (mg/Kg)</b>	1/10	NA	ND	ND
<b>Metals (mg/Kg)</b>				
Arsenic	7.5 or SB	NA	ND	ND
Barium	300 or SB	NA	ND	ND
Cadmium	1 or SB	NA	<b>3.1</b>	<b>4.7</b>
Total Chromium	10 or SB	NA	<b>1200.0</b>	<b>4100.0</b>
Copper	25 or SB	NA	<b>2700.0</b>	<b>7200.0</b>
Lead	SB	NA	29.0	83.0
Nickel	13 or SB	NA	<b>390.0</b>	<b>1500.0</b>
Selenium	2 or SB	NA	<b>4.7</b>	<b>3.5</b>
Silver	SB	NA	ND	ND
Zinc	20 or SB	NA	<b>69</b>	<b>170</b>
<b>Mercury (mg/Kg)</b>	0.1	NA	ND	ND
<b>TCL-SVOC (ug/Kg)</b>				
Benzo(b)fluoranthene	1,100	NA	ND	740.0
Bis(2-ethylhexyl)phthalate	50,000	NA	1200.0	ND
Fluoranthene	50,000	NA	ND	790.0
<b>TCL VOC (ug/Kg)</b>				
Acetone	200	NA	160	82
Methylene Chloride	100	NA	3.9	6.8
<b>Ignitability</b>	N/A	NA	>60	>60
<b>pH</b>	N/A	NA	5.19	5.4
<b>Total Cyanide (mg/Kg)</b>	NS	NA	3.95	8.23
<b>Reactive Cyanide (mg/Kg)</b>	NS	NA	ND	ND
<b>Reactive Sulfide (mg/Kg)</b>	NS	NA	ND	ND
<b>Hexavalent Chrome (mg/Kg)</b>	NS	NA	110.0	140.0

**Notes:**

Exceedances of Standard is shown in **Bold**

\* = Sample Collected by GSP on 10 May 2005

\*\* = Sample collected by Upstate on 18 May 2005.

SB = Site Background

ND = Not Detected

NA=Not Analyzed

NS=No Standard

N/A=Not Applicable

TAGM #4046 = NYSDEC TAGM No. 4046

**TABLE 5-2**  
**Summary of Analytical Data - Soil**  
**GSP Swale Area**  
**General Super Plating Company**  
**NYSDEC Spill No.: 0550288**  
**ERM Project No.: 0032572**

Sample Location Sample Depth (ft.) Date Sampled	Standard NYSDEC TAGM #4046	GSP-001 6"-8" 5/27/2005	GSP-001 16"-18" 5/27/2005	GSP-002 6"-8" 5/27/2005	GSP-002 16"-18" 5/27/2005	GSP-003 6"-8" 5/27/2005	GSP-003 16"-18" 5/27/2005	GSP-004 6"-8" 5/27/2005	GSP-004 16"-18" 5/27/2005
<b>Metals (mg/kg)</b>									
Total Chromium	10	555	89.4	1,100	574	104	324	3,450	1,580
Copper	25 or SB	217	59.1	123	65.5	48.9	54.2	163	56.5
Nickel	13 or SB	2,400	307	546	74.8	51.1	44.7	2,180	419
Zinc	20 or SB	NA	NA	NA	NA	NA	NA	NA	NA
<b>Inorganics (mg/kg)</b>									
Total Cyanide	NS	NA	NA	78.5	5.99	NA	NA	903	17.6

Sample Location Sample Depth (ft.) Date Sampled	Standard NYSDEC TAGM #4046	GSP-005 6"-8" 5/27/2005	GSP-005 16"-18" 5/27/2005	GSP-006 6"-8" 5/27/2005	GSP-006 16"-18" 5/27/2005	GSP-007 6"-8" 5/27/2005	GSP-007 16"-18" 5/27/2005	GSP-008 6"-8" 5/27/2005	GSP-008 16"-18" 5/27/2005
<b>Metals (mg/kg)</b>									
Total Chromium	10	605	430	85.8	149	3,560	1,350	534	199
Copper	25 or SB	63.7	20.3	114	635	9,280	1,940	192	95.5
Nickel	13 or SB	621	252	447	709	2,130	1,740	220	118
Zinc	20 or SB	NA	NA	NA	NA	NA	NA	NA	NA
<b>Inorganics (mg/kg)</b>									
Total Cyanide	NS	NA	NA	NA	NA	2.5	ND	NA	NA

Sample Location Sample Depth (ft.) Date Sampled	Standard NYSDEC TAGM #4046	GSP-009 6"-8" 5/27/2005	GSP-009 16"-18" 5/27/2005	GSP-010 6"-8" 5/27/2005	GSP-010 16"-18" 5/27/2005	GSP-011 6"-8" 5/27/2005	GSP-011 16"-18" 5/27/2005	GSP-012 6"-8" 5/27/2005	GSP-012 16"-18" 5/27/2005
<b>Metals (mg/kg)</b>									
Total Chromium	10	53	52.2	3,830	2,700	61.6	66.7	720	1,350
Copper	25 or SB	93.6	111	11,900	13,000	108	154	210	672
Nickel	13 or SB	91.9	277	3,720	2,440	85	84.4	176	376
Zinc	20 or SB	NA	NA	NA	NA	NA	NA	NA	NA
<b>Inorganics (mg/kg)</b>									
Total Cyanide	NS	NA	NA	ND	ND	NA	NA	NA	NA

TABLE 5-2 (Continued)

Sample Location Sample Depth (ft.) Date Sampled	Standard NYSDEC TAGM #4046	GSP-013 6"-8" 5/27/2005	GSP-013 16"-18" 5/27/2005	GSP-014 6"-8" 5/27/2005	GSP-014 16"-18" 5/27/2005	GSP-Dupe1 6"-8" 5/27/2005	GSP-SWALE-015 1"-3" 6/9/2005	GSP-SWALE-015 13"-15" 6/9/2005	GSP-SWALE-016 1"-3" 6/9/2005
<b>Metals (mg/kg)</b>									
Total Chromium	10	868	768	334	309	687	51.2	88.8	22.6
Copper	25 or SB	1,310	1,830	246	325	63.4	21.5	32.5	33.1
Nickel	13 or SB	967	1,240	1,060	845	106	276	294	27.6
Zinc	20 or SB	NA	NA	NA	NA	NA	46.2	62.4	50.6
<b>Inorganics (mg/kg)</b>									
Total Cyanide	NS	ND	ND	NA	NA	NA	ND	ND	ND

Sample Location Sample Depth (ft.) Date Sampled	Standard NYSDEC TAGM #4046	GSP-SWALE-016 13"-15" 6/9/2005	GSP-SWALE-017 1"-3" 6/9/2005	GSP-SWALE-017 13"-15" 6/9/2005	GSP-SWALE-018 1"-3" 6/9/2005	GSP-SWALE-018 13"-15" 6/9/2005	GSP-SWALE-019 1"-3" 6/9/2005	GSP-SWALE-019 13"-15" 6/9/2005	GSP-SWALE-020 1"-3" 6/9/2005
<b>Metals (mg/kg)</b>									
Total Chromium	10	8.47	125	94.8	327	172	81.7	47.4	354
Copper	25 or SB	18.8	80.5	28.7	40.9	16.4	194	136	62.2
Nickel	13 or SB	12.1	46.2	22.3	59.4	60.7	222	125	75.1
Zinc	20 or SB	103	219	79.0	116	60.0	442	185	116
<b>Inorganics (mg/kg)</b>									
Total Cyanide	NS	ND	ND	ND	4.52	3.79	ND	ND	ND

Sample Location Sample Depth (ft.) Date Sampled	Standard NYSDEC TAGM #4046	GSP-SWALE-020 13"-15" 6/9/2005	GSP-SWALE-021 1"-3" 6/9/2005	GSP-SWALE-021 13"-15" 6/9/2005	GSP-SWALE-022 1"-3" 6/9/2005	GSP-SWALE-022 13"-15" 6/9/2005	GSP-SWALE-023 1"-3" 6/9/2005	GSP-SWALE-023 13"-15" 6/9/2005	GSP-SWALE-024 1"-3" 6/9/2005
<b>Metals (mg/kg)</b>									
Total Chromium	10	290	21.6	18.5	162	22.9	19.3	40.4	65.6
Copper	25 or SB	46.3	28.7	26.5	342	34.9	20.9	27.9	261
Nickel	13 or SB	69.5	21.6	147	231	36.7	20.0	23.1	768
Zinc	20 or SB	105	144	104	1,740	96.9	204	194	621
<b>Inorganics (mg/kg)</b>									
Total Cyanide	NS	ND	ND	ND	ND	3.79	ND	ND	ND

TABLE 5-2 (Continued)

Sample Location	Standard	GSP-SWALE-024	GSP-SWALE-025	GSP-SWALE-025	GSP-SWALE-026	GSP-SWALE-026	GSP-SWALE-027	GSP-SWALE-027	GSP-SWALE-DUP-1
Sample Depth (ft.)	NYSDEC	13"-15"	1"-3"	13"-15"	1"-3"	13"-15"	1"-3"	13"-15"	
Date Sampled	TAGM #4046	6/9/2005	6/9/2005	6/9/2005	6/9/2005	6/9/2005	6/9/2005	6/9/2005	6/9/2005
<b>Metals (mg/kg)</b>									
Total Chromium	10	149	18.0	14.5	27.6	20.4	32.7	98.5	233
Copper	25 or SB	477	86.0	67.4	56.5	47.5	17.5	64.3	53.0
Nickel	13 or SB	468	18.5	14.7	26.0	19.5	16.3	36.7	97.4
Zinc	20 or SB	2,340	337	170	166	144	57.0	75.9	90.3
<b>Inorganics (mg/kg)</b>									
Total Cyanide	NS	1.20	ND	ND	ND	ND	ND	ND	ND

Sample Location	Standard	GSP-SWALE-DUP-1							
Sample Depth (ft.)	NYSDEC								
Date Sampled	TAGM #4046	6/9/2005							
<b>Metals (mg/kg)</b>									
Total Chromium	10	21.3							
Copper	25 or SB	45.5							
Nickel	13 or SB	22.6							
Zinc	20 or SB	157							
<b>Inorganics (mg/kg)</b>									
Total Cyanide	NS	ND							

**Notes:**

Exceedances of Standard is shown in **Bold**

NS = no standard

NA = not analyzed

ND = the compound was not detected at a concentration above the reported method detection limit

SB = Site Background

mg/kg = miligram/kilogram

TAGM #4046 = NYSDEC TAGM No. 4046

**TABLE 5-3**  
**TCLP Analyses**  
**GSP Swale Area**  
**General Super Plating Company**  
**NYSDEC Spill No.: 0550288**  
**ERM Project No.: 0032572**

Sample Location Sample Depth (ft.) Date Sampled	Standard USEPA SW-846	GSP-COMP1(1) 1 5/27/2005	GSP-COMP2(1) 1 5/27/2005	* GSP-DUPE2 1 5/27/2005
<b>TCLP Metals (mg/L)</b>				
Total Chromium	5	0.452	0.696	0.89
Copper	NS	0.722	33.2	33.4
Nickel	NS	3.28	9.04	8.19
<b>Inorganics (mg/L)</b>				
TCLP Cyanide	NS	ND	ND	NA

**TABLE 5-3a**  
**Summary of Analytical Data - VOC Soil**  
**GSP Swale Area**  
**General Super Plating Company**  
**NYSDEC Spill No.: 0550288**  
**ERM Project No.: 0032572**

Sample Location Sample Depth (ft.) Date Sampled	Standard NYSDEC TAGM 4046	GSP-020A@4' 4' 5/31/2005	GSP-021A@6"-1' 6"-1' 5/31/2005	GSP-022A@6"-1' 6"-1' 5/31/2005	*** GSP-023A(DUPE) 6"-1' 5/31/2005	GSP-024A@6"-1' 6"-1' 5/31/2005	GSP-025A@6"-1' 6"-1' 5/31/2005
<b>** VOCs (ug/kg)</b>							
2-Chlorotoluene	NS	ND	188	ND	186	NA	NA
<b>Inorganics (mg/kg)</b>							
Total Cyanide	0.2	NA	NA	NA	NA	ND	ND

**Notes:**

Exceedances of Standard is shown in **Bold**

\* = duplicate sample collected from GSP-Comp-2

\*\* = samples were analyzed for the full list of VOCs, only detected compounds presented

\*\*\* = duplicate sample collected from GSP-021@ 6"-1'

NS = no standard

NA = not analyzed

ND = the compound was not detected at a concentration above the reported method detection limit

mg/L = milligram/liter

TAGM #4046 = NYSDEC TAGM No. 4046

**TABLE 5-4**  
**RDA Excavation and Test Pit Analytical Data - Soil**  
**GSP Swale Area**  
**General Super Plating Company**  
**NYSDEC Spill No.: 0550288**  
**ERM Project No.: 0032572**

Sample Location	Standard	CON- 001	CON- 001A	CON-002	CON-003	DUPE 1*	TP-1
Sample Depth (ft.)	NYSDEC	----	----	----	----	----	2 ft
Date Sampled	TAGM #4046	6/7/2005	6/7/2005	6/7/2005	6/7/2005	6/7/2005	6/14/2005
<b>Metals (mg/kg)</b>							
Total Chromium	10	<b>19.2</b>	<b>27.9</b>	<b>38.6</b>	<b>279.0</b>	<b>558.0</b>	<b>71.2</b>
Copper	25 or SB	15.4	<b>40.6</b>	<b>35.6</b>	<b>153.0</b>	<b>193.0</b>	<b>141.0</b>
Nickel	13 or SB	<b>419.0</b>	<b>23.3</b>	<b>79.5</b>	<b>571.0</b>	<b>941.0</b>	<b>419.0</b>
Zinc	20 or SB	<b>60.1</b>	<b>74.4</b>	<b>33.3</b>	<b>26.4</b>	<b>60.8</b>	<b>39.2</b>
<b>Inorganics (mg/kg)</b>							
Total Cyanide	NS	ND	ND	ND	ND	ND	ND

Sample Location	Standard	TP-1	TP-2	TP-2	TP-3	TP-3	TP-4	TP-4
Sample Depth (ft.)	NYSDEC	6 ft	3 ft	7 ft	3 ft	7 ft	2.5 ft	7 ft
Date Sampled	TAGM #4046	6/14/2005	6/14/2005	6/14/2005	6/14/2005	6/14/2005	6/14/2005	6/14/2005
<b>Metals (mg/kg)</b>								
Total Chromium	10	<b>79.2</b>	<b>10.5</b>	<b>24.2</b>	<b>348.0</b>	<b>98.2</b>	<b>321.0</b>	<b>8.7</b>
Copper	25 or SB	8.9	14.7	15.4	<b>26.0</b>	13.7	<b>32.9</b>	7.8
Nickel	13 or SB	<b>74.6</b>	<b>16.5</b>	<b>26.0</b>	<b>75.8</b>	<b>27.3</b>	<b>45.6</b>	7.6
Zinc	20 or SB	<b>25.0</b>	<b>22.9</b>	<b>22.9</b>	<b>20.0</b>	<b>25.3</b>	14.6	11.8
<b>Inorganics (mg/kg)</b>								
Total Cyanide	NS	ND	ND	ND	ND	ND	14.9	ND

**Notes:**

Exceedances of Standard is shown in **Bold**

\* = Duplicate of CON-3 on 7 June 2005

NS = no standard

NA = not analyzed

ND = the compound was not detected at a concentration above the reported method detection limit

SB = Site Background

mg/kg = miligram/kilogram

TAGM #4046 = NYSDEC TAGM No. 4046

TOGS 1.1.1 = NYSDEC Ambient Water Quality Standards and Guidance Values

**TABLE 5-5**  
**Summary of Analytical Data - Soil**  
**Bridge Street Swale Area**  
**General Super Plating Company**  
**NYSDEC Spill No.: 0550288**  
**ERM Project No.: 0032572**

Sample Location	Standard	GSP-200	GSP-200	GSP-201	GSP-202	GSP-202	GSP-203	GSP-203	GSP-204
Sample Depth (ft.)	NYSDEC	3"-6"	13"-16"	3"-6"	3"-6"	13"-16"	3"-6"	13"-16"	3"-6"
Date Sampled	TAGM #4046	6/3/2005	6/3/2005	6/3/2005	6/3/2005	6/3/2005	6/3/2005	6/3/2005	6/3/2005
<b>Metals (mg/kg)</b>									
Total Chromium	10	174.0	59.0	118.0	363.0	251.0	29.5	58.0	137.0
Copper	25 or SB	227.0	162.0	311.0	384.0	318.0	83.0	121.0	450.0
Nickel	13 or SB	175.0	76.0	127.0	244.0	225.0	22.0	40.9	219.0
<b>Inorganics (mg/kg)</b>									
Total Cyanide	NS	ND	ND	ND	4.53	4.32	ND	ND	ND

Sample Location	Standard	GSP-205	GSP-205	GSP-206	GSP-206	GSP-207	GSP-208	GSP-208	GSP-209
Sample Depth (ft.)	NYSDEC	3"-6"	13"-16"	3"-6"	13"-16"	3"-6"	3"-6"	13"-16"	3"-6"
Date Sampled	TAGM #4046	6/3/2005	6/3/2005	6/3/2005	6/3/2005	6/3/2005	6/3/2005	6/3/2005	6/3/2005
<b>Metals (mg/kg)</b>									
Total Chromium	10	17.2	17.1	15.1	17.0	21.7	31.6	16.2	8.1
Copper	25 or SB	22.9	23.8	41.7	47.5	38.4	112.0	27.6	10.7
Nickel	13 or SB	18.8	17.6	28.8	32.3	19.8	96.4	28.8	11.2
<b>Inorganics (mg/kg)</b>									
Total Cyanide	NS	1.34	2.41	ND	ND	1.93	1.74	ND	ND

Sample Location	Standard	GSP-209	GSP-210	GSP-211 *	GSP-211	GSP-212	GSP-212	GSP-213	GSP-214
Sample Depth (ft.)	NYSDEC	13"-16"	3"-6"	3"-6"	13"-16"	3"-6"	13"-16"	6"-12"	3"-6"
Date Sampled	TAGM #4046	6/3/2005	6/3/2005	6/3/2005	6/3/2005	6/3/2005	6/3/2005	6/3/2005	6/3/2005
<b>Metals (mg/kg)</b>									
Total Chromium	10	6.7	11.8	12.9	11.4	36.3	17.3	966.0	257.0
Copper	25 or SB	10.3	23.4	16.7	19.4	185.0	105.0	4350.0	763.0
Nickel	13 or SB	10.3	14.2	13.2	12.9	25.0	13.5	927.0	262.0
<b>Inorganics (mg/kg)</b>									
Total Cyanide	NS	ND	ND	ND	ND	ND	ND	2.66	ND

**Notes:**

Exceedances of Standard is shown in **Bold**

\* = Laboratory Report misprinted sample identification as GSP-21(3"-6")

NS = no standard

NA = not analyzed

ND = the compound was not detected at a concentration above the reported method detection limit

SB = Site Background

mg/kg = miligram/kilogram

TAGM #4046 = NYSDEC TAGM No. 4046

TABLE 5-5 (Continued)

Sample Location	Standard	GSP-214	GSP-215	GSP-215	GSP-216	GSP-217	GSP-217	GSP-218	GSP-219
Sample Depth (ft.)	NYSDEC	12"-16"	3"-6"	13"-16"	3"-6"	3"-6"	13"-16"	3"-6"	3"-6"
Date Sampled	TAGM #4046	6/3/2005	6/3/2005	6/3/2005	6/3/2005	6/3/2005	6/3/2005	6/3/2005	6/3/2005
<b>Metals (mg/kg)</b>									
Total Chromium	10	74.3	10.8	6.7	731.0	20.1	26.7	321.0	14.8
Copper	25 or SB	149.0	109.0	15.5	7170.0	42.7	66.8	1150.0	36.6
Nickel	13 or SB	99.8	13.7	9.4	2330.0	41.5	51.6	412.0	22.0
<b>Inorganics (mg/kg)</b>									
Total Cyanide	NS	ND	ND	ND	ND	ND	ND	4.13	ND

Sample Location	Standard	GSP-220	GSP-221	BSS-S-222	BSS-S-222	BSS-S-223	BSS-S-223	BSS-S-224	BSS-S-225
Sample Depth (ft.)	NYSDEC	3"-6"	3"-6"	1"-3"	13"-15"	1"-3"	13"-15"	0"-2"	0"-2"
Date Sampled	TAGM #4046	6/3/2005	6/3/2005	6/10/2005	6/10/2005	6/10/2005	6/10/2005	6/10/2005	6/10/2005
<b>Metals (mg/kg)</b>									
Total Chromium	10	465.0	69.0	11.4	10.8	9.17	11.4	38.6	15.5
Copper	25 or SB	547.0	207.0	14.4	14.3	11.1	9.85	73.7	24.4
Nickel	13 or SB	190.0	78.5	12	9.33	11.5	12.2	26.6	15.3
Zinc	20 or SB	NA	NA	62.8	48.1	32.7	45.7	269	109
<b>Inorganics (mg/kg)</b>									
Total Cyanide	NS	ND	ND	ND	ND	ND	ND	1.72	ND

Sample Location	Standard	BSS-S-226	BSS-S-227	BSS-S-227	BSS-S-228	BSS-S-228	BSS-S-229	BSS-S-229	BSS-S-230
Sample Depth (ft.)	NYSDEC	0"-2"	1"-3"	13"-15"	1"-3"	13"-15"	1"-3"	13"-15"	1"-3"
Date Sampled	TAGM #4046	6/10/2005	6/10/2005	6/10/2005	6/10/2005	6/10/2005	6/10/2005	6/10/2005	6/10/2005
<b>Metals (mg/kg)</b>									
Total Chromium	10	22.7	53.4	25.2	6.24	5.51	6.92	8.27	8.66
Copper	25 or SB	31.9	90.4	57.5	5.47	8.33	8.41	23.8	18
Nickel	13 or SB	19.5	67.5	36.5	6.32	7.24	8.39	11.4	12.2
Zinc	20 or SB	100	163	87.8	46	30.6	42.9	45.7	64
<b>Inorganics (mg/kg)</b>									
Total Cyanide	NS	ND	ND	ND	ND	ND	ND	1.72	ND

Notes:

Exceedances of Standard is shown in **Bold**

NS = no standard

NA = not analyzed

ND = the compound was not detected at a concentration above the reported method detection limit

SB = Site Background

mg/kg = miligram/kilogram

TAGM #4046 = NYSDEC TAGM No. 4046



TABLE 5-5 (Continued)

Sample Location	Standard	BSS-S-230	BSS-S-231	BSS-S-231	BSS-S-232	BSS-S-232	BSS-S-DUPE1	BSS-S-DUPE2
Sample Depth (ft.)	NYSDEC	13"-15"	0"-2"	13"-15"	0"-2"	13"-15"		
Date Sampled	TAGM #4046	6/10/2005	6/10/2005	6/10/2005	6/10/2005	6/10/2005	6/10/2005	6/10/2005
<b>Metals (mg/kg)</b>								
Total Chromium	10	8.50	<b>45.5</b>	<b>12.1</b>	<b>21.8</b>	<b>11.3</b>	<b>23.2</b>	<b>50.4</b>
Copper	25 or SB	18.6	<b>81.9</b>	<b>44.9</b>	<b>88.1</b>	<b>76.5</b>	<b>58.8</b>	<b>128</b>
Nickel	13 or SB	11.9	<b>14.3</b>	8.88	<b>24.3</b>	<b>13.3</b>	<b>34.5</b>	<b>18.7</b>
Zinc	20 or SB	<b>71.5</b>	<b>385</b>	<b>74.3</b>	<b>164</b>	<b>80.9</b>	<b>227</b>	<b>473</b>
<b>Inorganics (mg/kg)</b>								
Total Cyanide	NS	ND	15.7	ND	ND	ND	ND	14.4

**Notes:**

Exceedances of Standard is shown in **Bold**

NS = no standard

NA = not analyzed

ND = the compound was not detected at a concentration above the reported method detection limit

SB = Site Background

mg/kg = miligram/kilogram

TAGM #4046 = NYSDEC TAGM No. 4046

**TABLE 5-6**  
**Summary of Analytical Data - Soil**  
**Sub-Slab Investigation**  
**General Super Plating Company**  
**NYSDEC Spill No.: 0550288**  
**ERM Project No.: 0032572**

Sample Location	Standard	B-1	B-1	B-2	B-2	B-3	B-3	B-4	B-4	B-5	B-5	B-6	B-6
Sample Depth (ft.)	NYSDEC	0"-6"	12"-18"	0"-6"	12"-18"	0"-6"	12"-18"	0"-6"	12"-18"	0"-6"	12"-18"	0"-6"	12"-18"
Date Sampled	TAGM #4046	7/6/2005	7/6/2005	7/6/2005	7/6/2005	7/6/2005	7/6/2005	7/5/2005	7/5/2005	7/6/2005	7/6/2005	7/6/2005	7/6/2005
<b>Metals (mg/kg)</b>													
Total Chromium	10	546.0	51.9	15.9	21.5	19.1	13.7	1,300.0	9.3	10.5	41.5	10.9	7.3
Copper	25 or SB	132.0	51.7	61.2	16.0	113.0	25.2	87,400.0	91.8	57.8	137.0	54.1	63.9
Nickel	13 or SB	969.0	54.3	13.4	14.1	29.3	16.4	5,780.0	1,300.0	33.8	109.0	32.3	27.6
Zinc	20 or SB	745.0	46.6	21.3	ND	30.3	34.1	41.8	16.0	41.2	671.0	37.5	36.1
<b>Inorganics (mg/kg)</b>													
Total Cyanide	NS	1.7	ND	ND	ND	1.7	ND	ND	ND	ND	ND	ND	ND

Sample Location	Standard	B-7	B-7	B-8	B-8	B-9	B-9	B-10	B-10	B-11	B-11	B-12	B-12
Sample Depth (ft.)	NYSDEC	0"-6"	12"-18"	0"-6"	12"-18"	0"-6"	12"-18"	0"-6"	12"-18"	0"-6"	12"-18"	0"-6"	12"-18"
Date Sampled	TAGM #4046	7/6/2005	7/6/2005	7/7/2005	7/7/2005	7/5/2005	7/5/2005	7/7/2005	7/7/2005	7/7/2005	7/7/2005	7/5/2005	7/5/2005
<b>Metals (mg/kg)</b>													
Total Chromium	10	21.2	169.0	22.9	338.0	18.0	10.9	65.5	34.0	13.0	16.4	398.0	24.1
Copper	25 or SB	13.3	11.9	59.8	855.0	73.1	56.1	55.3	102.0	12.7	20.4	1,260.0	60.7
Nickel	13 or SB	18.7	124.0	18.5	412.0	40.1	35.7	78.5	560.0	10.5	19.6	495.0	33.9
Zinc	20 or SB	27.7	29.2	34.4	52.9	39.7	44.0	41.6	65.7	ND	40.5	58.6	31.0
<b>Inorganics (mg/kg)</b>													
Total Cyanide	NS	ND	ND	ND	ND	ND	ND	ND	2.82	ND	ND	ND	ND

**Notes:**

Exceedances of Standard is shown in **Bold**

NS = no standard

NA = not analyzed

ND = the compound was not detected at a concentration above the reported method detection limit

SB = Site Background

mg/kg = miligram/kilogram

TAGM #4046 = NYSDEC TAGM No. 4046

**TABLE 5-6a**  
**Summary of Analytical Data - Soil**  
**Sub-Slab Investigation**  
**General Super Plating Company**  
**NYSDEC Spill No.: 0550288**  
**ERM Project No.: 0032572**

Sample ID/Location	Guidance	B-4
Sample Depth (ft.)	NYSDEC	0"-6"
Date Sampled	TAGM #4046	7/7/2005
<b>PCB (mg/Kg)</b>	10	ND
<b>Metals (mg/Kg)</b>		
Arsenic	7.5 or SB	ND
Barium	300 or SB	8.93
Cadmium	1 or SB	0.457
Total Chromium	10 or SB	<b>64.4</b>
Copper	25 or SB	NA
Lead	SB	9.0
Nickel	13 or SB	NA
Selenium	2 or SB	ND
Silver	SB	ND
Zinc	20 or SB	NA
<b>Mercury (mg/Kg)</b>	0.1	ND
<b>** TCL-SVOC (ug/Kg)</b>		
Benzo(b)fluoranthene	1,100	ND
Bis(2-ethylhexyl)phthalate	50,000	ND
Fluoranthene	50,000	ND
<b>** TCL VOC (ug/Kg)</b>		
Acetone	200	ND
Methylene Chloride	100	ND
<b>Ignitability</b>	NA	NA
<b>pH</b>	NA	7.39
<b>Total Cyanide (mg/L)</b>	0.20	ND
<b>Reactive Cyanide (mg/L)</b>	NA	ND
<b>Reactive Sulfide (mg/L)</b>	NA	ND
<b>Hexavalent Chrome (mg/L)</b>	0.05	NA

**Notes:**

Exceedances of Standard is shown in **Bold**

NS = no standard

NA = not analyzed

ND = the compound was not detected at a concentration above the reported method detection limit

SB = Site Background

mg/kg = miligram/kilogram

TAGM #4046 = NYSDEC TAGM No. 4046

**TABLE 5-7**  
**Summary of Analytical Data - Water**  
**GSP and Upstate Laboratory Samples**  
**General Super Plating Company**  
**NYSDEC Spill No.: 0550288**  
**ERM Project No.: 0032572**

Sample ID/Location Matrix Date Sampled	Standard TOGS 1.1.1 or TAGM 4046	^ GSP-2 Water 5/10/2005	* Drain Point Water 5/18/2005
PCB (mg/L)	0.0009	NA	ND
Metals (mg/L)			
Arsenic	0.05	NA	ND
Barium	1.00	NA	ND
Cadmium	0.005	ND	ND
Total Chromium	0.05	<b>26.0</b>	<b>55.0</b>
Copper	0.20	<b>110.0</b>	ND
Lead	0.05	ND	ND
Nickel	0.10	<b>110.0</b>	<b>120.0</b>
Selenium	0.01	NA	ND
Silver	0.05	ND	ND
Zinc	<b>***2.00</b>	0.68	0.18
Mercury (mg/Kg)	0.0007	NA	ND
** TCL-SVOC (ug/L)			
Benzo(b)fluoranthene	0.002	NA	ND
Bis(2-ethylhexyl)phthalate	50.00	NA	ND
Fluoranthene	50.00	NA	ND
** TCL VOC (ug/L)			
Acetone	50.00	NA	<b>100</b>
Methylene Chloride	5.00	NA	ND
Ignitability	N/A	NA	>60
pH	N/A	NA	2.4
Total Cyanide (mg/L)	0.20	NA	ND
Reactive Cyanide (mg/L)	N/A	NA	ND
Reactive Sulfide (mg/L)	N/A	NA	ND
Hexavalent Chrome (mg/L)	0.05	NA	<b>57.0</b>

**Notes:**

Exceedances of Standard is shown in **Bold**

TOGS 1.1.1 = NYS - Ambient Water Quality Standards

TAGM #4046 = NYSDEC TAGM No. 4046

^ =collected by GSP

\* = collected by Upstate Laboratory personnel

\*\* = full TCL scan completed, detected compounds only reported

\*\*\* = Guidance Value

N/A = Not Applicable

ND = Not Detected

NA = Not Analyzed

mg/kg = miligram/kilogram

mg/L = miligram/liter

ug/L = microgram/liter

**TABLE 5-8**  
**Summary of Analytical Data - Groundwater**  
**Sub-Slab Investigation - Temporary Monitoring Wells**  
**General Super Plating Company**  
**NYSDEC Spill No.: 0550288**  
**ERM Project No.: 0032572**

Sample Location Date Sampled	Standard TOGS 1.1.1	TW-1 7/8/2005	TW-2 7/8/2005	TW-3 7/8/2005	TW-4 7/8/2005
<b>Metals (mg/L)</b>					
Total Chromium	0.05	<b>181</b>	0.0236	0.0091	0.0368
Copper	0.2	ND	0.0068	ND	0.0155
Nickel	0.1	ND	<b>0.166</b>	0.074	<b>0.884</b>
Zinc	* 2.0	0.238	ND	ND	ND
<b>Inorganics (mg/L)</b>					
Total Cyanide	0.2	0.0782	ND	ND	0.0252

**Notes:**

Exceedances of Standard is shown in **Bold**

\* 2.0 = Guidance Value, not a standard

NA = not analyzed

ND = the compound was not detected at a concentration above the reported method detection limit

mg/L = milligram/liter

TOGS 1.1.1 = NYS Division of Water - Ambient Water Quality Standards and Guidance Values

**TABLE 5-9**  
**Summary of Analytical Data - Water**  
**Upstate Laboratory Sample**  
**General Super Plating Company**  
**NYSDEC Spill No.: 0550288**  
**ERM Project No.: 0032572**

Sample ID/Location Matrix Date Sampled	Standard TOGS 1.1.1 or TAGM 4046	* Bridge Street Swale Water 5/18/2005
PCB (mg/L)	0.00009	ND
Metals (mg/L)		
Arsenic	0.05	ND
Barium	1.00	ND
Cadmium	0.01	ND
Total Chromium	0.05	<b>6.4</b>
Copper	0.20	<b>23.0</b>
Lead	0.05	ND
Nickel	0.10	<b>12.0</b>
Selenium	0.01	ND
Silver	0.05	ND
Zinc	***2.00	0.12
Mercury (mg/Kg)	0.0007	ND
** TCL-SVOC (ug/L)		
Benzo(b)fluoranthene	0.002	ND
Bis(2-ethylhexyl)phthalate	0.05	ND
Fluoranthene	*** 0.05	ND
** TCL VOC (ug/L)		
Acetone	50.00	<b>62</b>
Methylene Chloride	5.00	ND
Ignitability	N/A	>60
pH	N/A	6.6
Total Cyanide (mg/L)	0.20	ND
Reactive Cyanide (mg/L)	N/A	ND
Reactive Sulfide (mg/L)	N/A	ND
Hexavalent Chrome (mg/L)	0.05	MI

**Notes:**

Exceedances of Standard is shown in **Bold**

TOGS 1.1.1 = NYS - Ambient Water Quality Standards

TAGM #4046 = NYSDEC TAGM No. 4046

\* = collected by Upstate Laboratory personnel

\*\* = full TCL scan completed, detected compounds only reported

\*\*\* = Guidance Value

N/A = Not Applicable

ND = Not Detected

MI = Matrix Interference prevented quantification

mg/kg = milligram/kilogram

mg/L = milligram/liter

ug/L : microgram/liter

**TABLE 5-10**  
**Summary of Analytical Data - Surface Water**  
**Bridge Street Swale Area**  
**General Super Plating Company**  
**NYSDEC Spill No.: 0550288**  
**ERM Project No.: 0032572**

Sample Location	Standard	Swale-101	BSS-Swale-01	Swale-102	BSS-Swale-02	Swale-103	BSS-Swale-03	Swale-104	BSS-Swale-04
Sample Depth (ft.)	NYSDOW	--	--	--	--	--	--	--	--
Date Sampled	TOGS 1.1.1	6/2/2005	6/9/2005	6/2/2005	6/9/2005	6/2/2005	6/9/2005	6/2/2005	6/9/2005
<b>Metals (mg/L)</b>									
Total Chromium	0.05	<b>0.542</b>	<b>0.650</b>	<b>0.342</b>	<b>0.627</b>	ND	ND	0.036	<b>0.239</b>
Hexavalent Chromium	0.011	NA	<b>0.430</b>	NA	<b>0.630</b>	NA	ND	NA	<b>0.059</b>
Copper	0.2	<b>1.24</b>	<b>1.69</b>	<b>1.76</b>	<b>0.74</b>	ND	ND	0.122	<b>0.866</b>
Nickel	0.1	<b>0.661</b>	<b>0.448</b>	<b>0.603</b>	<b>0.672</b>	ND	ND	0.04	<b>0.141</b>
Zinc	** 2.0	NA	0.115	NA	0.071	NA	ND	NA	0.12
<b>Inorganics (mg/L)</b>									
Total Cyanide	0.2	ND	ND	ND	ND	ND	ND	ND	0.0104

Sample Location	Standard	Swale-105	BSS-Swale-05	BSS-Swale-06	Large Culver	Bridge Street	* Swale-106	BSS - Dupe	
Sample Depth (ft.)	NYSDOW	--	--	--	--	--	Dupe of 102	Dupe of 01	
Date Sampled	TOGS 1.1.1	6/2/2005	6/9/2005	6/9/2005	5/24/2005	6/1/2005	6/2/2005	6/9/2005	
<b>Metals (mg/L)</b>									
Total Chromium	0.05	<b>0.636</b>	0.0496	<b>0.0782</b>	<b>0.257</b>	0.019	<b>0.367</b>	<b>0.419</b>	
Hexavalent Chromium	0.011	NA	0.009	ND	NA	NA	NA	<b>0.45</b>	
Copper	0.2	<b>1.63</b>	<b>0.25</b>	<b>0.677</b>	<b>0.997</b>	0.0388	<b>1.92</b>	<b>0.533</b>	
Nickel	0.1	<b>0.962</b>	0.0872	<b>0.406</b>	<b>0.525</b>	0.0064	<b>0.648</b>	<b>0.402</b>	
Zinc	** 2.0	NA	ND	0.0288	NA	NA	NA	0.0702	
<b>Inorganics (mg/L)</b>									
Total Cyanide	0.2	ND	ND	ND	NA	0.012	ND	ND	

**Notes:**

TOGS 1.1.1 = NYS Division of Water (DOW) - Ambient Water Quality Standards and Guidance Values

Exceedances of Standard is shown in **Bold**

\* = Duplicate of Swale-102 on 2 June 2005

\*\* 2.0 = Guidance Value, not a standard

NA = not analyzed

ND = the compound was not detected at a concentration above the reported method detection limit

mg/L = miligram/liter

**TABLE 5-11**  
**Summary of Analytical Data - Groundwater**  
**Test Pit Monitoring Wells**  
**General Super Plating Company**  
**NYSDEC Spill No.: 0550288**  
**ERM Project No.: 0032572**

Sample Location Date Sampled	Standard TOGS 1.1.1	TPW-1 6/17/2005	TPW-2 6/17/2005	TPW-3 6/17/2005	TPW-4 6/17/2005
<b>Metals (mg/L)</b>					
Total Chromium	0.05	0.0040	0.0035	<b>389.0000</b>	<b>293.0000</b>
Copper	0.2	0.0053	ND	0.0113	0.0200
Nickel	0.1	0.0712	<b>1.1500</b>	<b>1.6400</b>	<b>1.8800</b>
Zinc	* 2.0	ND	ND	0.3710	0.3230
<b>Inorganics (mg/L)</b>					
Total Cyanide	0.2	ND	ND	0.0609	0.0938

**Notes:**

TOGS 1.1.1 = NYS Division of Water - Ambient Water Quality Standards and Guidance Values  
 Exceedances of Standard is shown in **Bold**

\* 2.0 = Guidance Value, not a standard

ND = the compound was not detected at a concentration above the reported method detection limit  
 mg/L = miligram/liter



**TABLE 5-12**  
**Summary of Analytical Data - Groundwater**  
**Site Monitoring Wells**  
**General Super Plating Company**  
**NYSDEC Spill No.: 0550288**  
**ERM Project No.: 0032572**

Sample Location Date Sampled	Standard TOGS 1.1.1	GSP-MW-1 8/22/2005	GSP-MW-2 8/22/2005	GSP-MW-3 8/22/2005	GSP-Dupe 8/23/2005
<b>Metals (mg/L)</b>					
Total Chromium	0.05	ND	ND	ND	ND
Hexavalent Chromium	0.011	0.0110	0.0090	<b>0.0140</b>	0.0100
Copper	0.2	ND	0.0036	ND	ND
Nickel	0.1	ND	0.0059	0.0047	ND
Zinc	* 2.0	ND	ND	ND	ND
<b>Inorganics (mg/L)</b>					
Total Cyanide	0.2	ND	ND	ND	ND

**Notes:**

TOGS 1.1.1 = NYS Division of Water - Ambient Water Quality Standards and Guidance Values

Exceedances of Standard is shown in **Bold**



\* 2.0 = Guidance Value, not a standard


ND = the compound was not detected at a concentration above the reported method detection limit

mg/L = milligram/liter

GSP-Dupe was taken at the MW-1 location.

Attachment B-2 – Excerpts from Data Gap  
Investigation Report, ERM, June 2012



<b>Site Location Map</b>		
Prepared For:		General Super Plating
	Scale	Figure
	1:24,000	<b>1</b>
Date	28 Mar 2011	

Source: U.S. Department of Transportation 1990



NYS Route 690

National Grid Sub-Station

National Grid Sub-Station

Planet Fitness

Paradise Plaza

AT&T Building

Bridge Street

The Home Depot

Erie Blvd. East

Celi Drive

GSP

Site Boundary

### Aerial View of Site

PREPARED FOR  
General Super Plating - Dewitt, New York



SCALE  
See Scale Bar


DATE  
May 2012

FIGURE  
**2**






AOC-4  
Bridge Street Swale



Phase 3 -Area of Concern


PREPARED FOR  
General Super Plating - Dewitt, New York



SCALE  
See Scale Bar  
DATE  
May 2012


FIGURE  
**4**


Shipping Department



Legend


- -Sub-Slab Boring Location 2005
- -Data Gap Investigation Boring Location- 2010
- -Data Gap Investigation Horizontal Boring Location- 2010

GSP Sub-Slab Sample Location		
Prepared For:		General Super Plating
	Scale	NTS
	Date	27 April 2010
		5



Legend

- MW-5  -Monitoring Well
- TPW-1  -Test Pit Monitoring Well


Monitoring Well Locations		
Prepared For:		General Super Plating
	Scale	Figure
	Date	9
	NTS	
	30 June 2010	

Shipping Department

342	Soil
Sample Date	8-April-10
Metals (mg/kq)	Result
Total Chromium	398
Hexavalent Chromium	8.79 J
Copper	<b>33,000 J</b>
Nickel	2,860
Zinc	19.7 J


4	Soil
Sample Date	5-Jul-05
Metals (mg/kq)	Result
Total Chromium	1,300
Hexavalent Chromium	NA
Copper	<b>87,400</b>
Nickel	5.780
Zinc	41.8

341	Soil
Sample Date	8-April-10
Metals (mg/kq)	Result
Total Chromium	17.8
Hexavalent Chromium	0.735 J
Copper	336 J
Nickel	<b>10,700</b>
Zinc	22.3 J




Legend

- -Sub-Slab Boring Location 2005
- -Data Gap Investigation Boring Location- 2010
- ┆ -Data Gap Investigation Horizontal Boring Location- 2010
- -Exceedance of Part 375 Restricted-Industrial Soil Cleanup Objective

GSP Sub-Slab- Exceedances of Metals in Soil		
Prepared For:	General Super Plating	
	Scale	Figure
	Date	
	NTS	<b>10</b>
	30 June 2010	





021		Depth 1-3 in.
Sample Date	9-Jun-05	Result
Metals (mg/kg)		
Total Chromium	6.6	
Copper	<b>261</b>	
Nickel	<b>768</b>	
Zinc	621	

021		Depth 13-15 in.
Sample Date	9-Jun-05	Result
Metals (mg/kg)		
Total Chromium	.49	
Copper	<b>477</b>	
Nickel	<b>466</b>	
Zinc	2940	

006		Depth 6-8 in.
Sample Date	27-May-05	Result
Metals (mg/kg)		
Total Chromium	83.3	
Copper	114	
Nickel	<b>447</b>	
Zinc	NA	

006		Depth 16-18 in.
Sample Date	27-May-05	Result
Metals (mg/kg)		
Total Chromium	149	
Copper	<b>635</b>	
Nickel	<b>709</b>	
Zinc	NA	

315		Depth 4-6 ft.
Sample Date	1-Mar-10	Result
Metals (mg/kg)		
Total Chromium	19.9	
Hexavalent Chromium	0.82	
Copper	14.7	
Nickel	<b>445</b>	
Zinc	47.1	

010		Depth 6-8 in.
Sample Date	27-May-05	Result
Metals (mg/kg)		
Total Chromium	3,830	
Copper	<b>11,800</b>	
Nickel	<b>3,720</b>	
Zinc	NA	

010		Depth 16-18 in.
Sample Date	27-May-05	Result
Metals (mg/kg)		
Total Chromium	2,700	
Copper	<b>18,400</b>	
Nickel	<b>2,440</b>	
Zinc	NA	

013		Depth 6-8 in.
Sample Date	27 May 05	Result
Metals (mg/kg)		
Total Chromium	868	
Copper	<b>1,310</b>	
Nickel	<b>967</b>	
Zinc	NA	


013		Depth 16-18 in.
Sample Date	27 May 05	Result
Metals (mg/kg)		
Total Chromium	768	
Copper	<b>1,830</b>	
Nickel	<b>1,240</b>	
Zinc	NA	

012		Depth 16-18 in.
Sample Date	27-May-05	Result
Metals (mg/kg)		
Total Chromium	1,030	
Copper	<b>672</b>	
Nickel	<b>376</b>	
Zinc	NA	

014		Depth 6-8 in.
Sample Date	27-May-05	Result
Metals (mg/kg)		
Total Chromium	334	
Copper	<b>246</b>	
Nickel	<b>1,060</b>	
Zinc	NA	

014		Depth 16-18 in.
Sample Date	27 May 05	Result
Metals (mg/kg)		
Total Chromium	309	
Copper	<b>335</b>	
Nickel	<b>845</b>	
Zinc	NA	

- Legend
- Source Identification Investigation Sample Locations (20' x 20')
  - ⊕ Monitoring Wells Installed (20' x 20')
  - ▲ Daily Soil Boring Locations (20' x 10')
  - ⊕ Daily Monitoring Wells (20' x 10')
  - Bold** Exceedance of Part 300 Restricted-Commercial Soil Cleanup Objective
  - □ □ □ Milligrams per Kilogram
  - - - - - Approximate Location of Property Line




**GSP Swale**  
**Exceedances of Metals in Soil**

PREPARED FOR  
**General Super Plating - Dewitt, New York**


SCALE	FIGURE
See Scale Bar	<b>11</b>
DATE	
June 2012	


348	Depth 5.5-6.5 ft.
Sample Date	8-Apr-10
Metals (mg/kg)	Result
Total Chromium	207
Hexavalent Chromium	0.693
Copper	543
Nickel	375
Zinc	159




Inferred Location of Culvert →

**Legend**  
 ▲ DGI Soil Boring Locations (2010)  
**Bold** Exceedance of Part 375 Restricted-Commercial Soil Cleanup Objective  
 mg/kg Milligrams per kilogram



<b>Buried Culvert Pipe Exceedances of Metals in Soil</b>		
PREPARED FOR		
<b>General Super Plating - Dewitt, New York</b>		
SCALE See Scale Bar	FIGURE	
	<b>12</b>	
DATE June 2010		
		



Sediments	
Sample Date	Result
Metals (mg/kg)	
Total Chromium	11
Hexavalent Chromium	11
Copper	36
Nickel	11
Zinc	36

Sediments	
Sample Date	Result
Metals (mg/kg)	
Total Chromium	11
Hexavalent Chromium	11
Copper	36
Nickel	11
Zinc	36

Depth 3-6 in.	
Sample Date	Result
Metals (mg/kg)	
Total Chromium	11
Hexavalent Chromium	11
Copper	<b>311</b>
Nickel	127
Zinc	11

Depth 3-6 in.	
Sample Date	Result
Metals (mg/kg)	
Total Chromium	363
Hexavalent Chromium	11
Copper	<b>361</b>
Nickel	211
Zinc	11

Depth 13-16 ft.	
Sample Date	Result
Metals (mg/kg)	
Total Chromium	257
Hexavalent Chromium	11
Copper	<b>318</b>
Nickel	225
Zinc	11

Depth 3-6 in.	
Sample Date	Result
Metals (mg/kg)	
Total Chromium	327
Hexavalent Chromium	11
Copper	<b>1,150</b>
Nickel	412
Zinc	11

Sediments	
Sample Date	Result
Metals (mg/kg)	
Total Chromium	11
Hexavalent Chromium	11
Copper	11
Nickel	33
Zinc	33

Depth 3-6 in.	
Sample Date	Result
Metals (mg/kg)	
Total Chromium	16.8
Hexavalent Chromium	11
Copper	<b>309</b>
Nickel	15.7
Zinc	11

Depth 3-6 in.	
Sample Date	Result
Metals (mg/kg)	
Total Chromium	762
Hexavalent Chromium	11
Copper	<b>7,170</b>
Nickel	2,330
Zinc	11

Depth 0-2 in.	
Sample Date	Result
Metals (mg/kg)	
Total Chromium	436
Hexavalent Chromium	7.31
Copper	<b>1,710</b>
Nickel	412
Zinc	760

Depth 3-6 in.	
Sample Date	Result
Metals (mg/kg)	
Total Chromium	237
Hexavalent Chromium	11
Copper	<b>450</b>
Nickel	2.2
Zinc	11

Depth 12-14 in.	
Sample Date	Result
Metals (mg/kg)	
Total Chromium	295
Hexavalent Chromium	0.05
Copper	<b>521</b>
Nickel	207
Zinc	409

Depth 22-24 in.	
Sample Date	Result
Metals (mg/kg)	
Total Chromium	760
Hexavalent Chromium	15.1
Copper	<b>287</b>
Nickel	176
Zinc	450

Depth 3-6 in.	
Sample Date	Result
Metals (mg/kg)	
Total Chromium	257
Hexavalent Chromium	11
Copper	<b>763</b>
Nickel	312
Zinc	11

Depth 22-24 in.	
Sample Date	Result
Metals (mg/kg)	
Total Chromium	373
Hexavalent Chromium	7.87
Copper	<b>1,050</b>
Nickel	175
Zinc	369

Depth 6-12 ft.	
Sample Date	Result
Metals (mg/kg)	
Total Chromium	966
Hexavalent Chromium	11
Copper	<b>1,150</b>
Nickel	<b>927</b>
Zinc	11

Legend

- Source Identification Investigation Sample Locations
- ▲ Drill Soil Boring Locations
- Exceedance of Part 300 Restricted-Commercial Soil Cleanup Objective**
- Millirals per iloral

Scale 0' 100' 200'

### Bridge Street Swale Area Exceedances of Metals in Soil

PREPARED FOR  
General Super Plating - Dewitt, New York

SCALE: See Scale Bar

DATE: May 2012


FIGURE: **13A**



233		Depth 0-2 in.
Sample Date		19-Oct-16
Metals (mg/kg)		Result
Total Chromium		436
Hexavalent Chromium		3.31
Copper		1,210
Nickel		442
Zinc		360

220		Depth 0-6 in.
Sample Date		3-Jan-05
Metals (mg/kg)		Result
Total Chromium		465
Hexavalent Chromium		N/A
Copper		547
Nickel		190
Zinc		615

**Legend**  
 ● Source Identification Investigation Sample Locations (2015)  
 ▲ Direct Soil Borings Locations (2011)  
**Bold** Exceedance of Part 300 Restricted-Commercial Soil Cleanup Objective  
 100 Milligrams per kilogram



**Bridge Street Swale Area  
Exceedances of Metals in Soil**

PREPARED FOR  
**General Super Plating - Dewitt, New York**




**SCALE**  
See Scale Bar


**DATE**  
May 2012

**FIGURE**  
**13B**




**Legend**

-  -Groundwater Flow Direction
-  -Groundwater Elevation (dashed where estimated)
-  -Monitoring Well


Site Ground Water- Flow Direction		
Prepared For:	General Super Plating	
	Scale	Figure
	Date	14
	NTS	
	29 June 2010	

Shipping Department



Legend


- -Sub-Slab Boring Location 2005
- -Data Gap Investigation Boring Location- 2010
- -Data Gap Investigation Horizontal Boring Location- 2010
- Area of Proposed Remediation

GSP Sub-Slab IRM Area of Proposed Remediation		
Prepared For:		General Super Plating
	Scale	NTS
	Date	30 April 2010
		Figure 20



Legend

- Source Identification Investigation Sample Locations (20' x 20')
- ⊕ Monitoring Wells Installed (20' x 20')
- ▲ Daily Soil Borings Locations (20' x 10')
- ⊕ Daily Monitoring Wells (20' x 10')
- ▨ Proposed Excavation - 1'
- ▨ Proposed Excavation - 2'
- ▨ Proposed Excavation - 3'



GSP Swale IRM  
Proposed Area of Remediation


PREPARED FOR  
General Super Plating - Dewitt, New York




SCALE  
See Scale Bar

DATE  
June 2012

FIGURE  
21



- Legend
- Source Identification Investigation Sample Locations
  - ▲ D/I Soil Boring Locations
  - ▨ Proposed Excavation -1'
  - ▨ Proposed Excavation -2'



### Bridge Street Swale IRM Proposed Area of Remediation

PREPARED FOR  
General Super Plating - Dewitt, New York



SCALE  
See Scale Bar


DATE  
June 2012

FIGURE  
**22A**





- Legend
- Source Identification Investigation Sample Locations (2000)
  - ▲ Daily Soil Borehole Locations (2010)
  - ▨ Proposed Excavation (-1')



<b>Bridge Street Swale IRM Proposed Area of Remediation</b>	
PREPARED FOR <b>General Super Plating - Dewitt, New York</b>	
	SCALE See Scale Bar
	DATE May 2012
<b>FIGURE 22B</b>	

**TABLE 1**  
**Summary of Analytical Data - Sub-Slab -Soil**  
**General Super Plating Company**  
**Data Gap Investigation**  
**NYSDEC BCP No.: C734108**  
**ERM Project No.: 0111860**

Sample Location	NYSDEC	B-1		B-2		B-3		B-4		B-5		B-6		B-7	
Sample Depth	Industrial	0 - 6	12 - 18	0 - 6	12 - 18	0 - 6	12 - 18	0 - 6	12 - 18	0 - 6	12 - 18	0 - 6	12 - 18	0 - 6	12 - 18
Date Sampled	Standard <sup>1</sup>	6-Jul-05	6-Jul-05	6-Jul-05	6-Jul-05	6-Jul-05	6-Jul-05	5-Jul-05	5-Jul-05	6-Jul-05	6-Jul-05	6-Jul-05	6-Jul-05	6-Jul-05	6-Jul-05
<b>Metals (mg/kg)</b>															
Total Chromium <sup>2</sup>	7,600	546	51.9	15.9	21.5	19.1	13.7	1,300	9.3	10.5	41.5	10.9	7.3	21.2	169
Hexavalent Chromium	800	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
Copper	10,000	132	51.7	61.2	16.0	113	25.2	87,400	91.8	57.8	137	54.1	63.9	13.3	11.9
Nickel	10,000	969	54.3	13.4	14.1	29.3	16.4	5,780	1,300	33.8	109	32.3	27.6	18.7	124
Zinc	10,000	745	46.6	21.3	ND	30.3	34.1	41.8	16.0	41.2	671	37.5	36.1	27.7	29.2
<b>Inorganics (mg/kg)</b>															
Total Cyanide	10,000	1.7	ND	ND	ND	1.7	ND	ND	ND	ND	ND	ND	ND	ND	ND
<b>Sample Location</b>															
Sample Location	NYSDEC	B-8		B-9		B-10		B-11		B-12		B-340	B-341	B-342	B-343
Sample Depth	Industrial	0 - 6	12 - 18	0 - 6	12 - 18	0 - 6	12 - 18	0 - 6	12 - 18	0 - 6	12 - 18	24 - 48	12 - 36	12 - 24	12 - 24
Date Sampled	Standard <sup>1</sup>	7-Jul-05	7-Jul-05	5-Jul-05	5-Jul-05	7-Jul-05	7-Jul-05	7-Jul-05	7-Jul-05	5-Jul-05	5-Jul-05	8-Apr-10	8-Apr-10	8-Apr-10	8-Apr-10
<b>Metals (mg/kg)</b>															
Total Chromium <sup>2</sup>	7,600	22.9	338	18.0	10.9	65.5	34.0	13.0	16.4	398	24.1	38.5	17.8	398	39.6
Hexavalent Chromium	800	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	2.12 J	0.735 J	8.79 J	5.1 J
Copper	10,000	59.8	855	73.1	56.1	55.3	102.0	12.7	20.4	1,260	60.7	29 J	336 J	33,000 J	276 J
Nickel	10,000	18.5	412	40.1	35.7	78.5	560	10.5	19.6	495	33.9	26.6	10,700	2,860	1,530
Zinc	10,000	34.4	52.9	39.7	44.0	41.6	65.7	ND	40.5	58.6	31.0	52.6 J	22.3 J	19.7 J	16.6 J
<b>Inorganics (mg/kg)</b>															
Total Cyanide	10,000	ND	ND	ND	ND	ND	2.82	ND	ND	ND	ND	ND	ND	1.43	ND

**Notes:**

Exceedance of Site SCG

<sup>d</sup> = Duplicate Sample

mg/kg = milligrams per kilogram

NA = Not Analyzed

ND = Not detected at a concentration above the method detection limit.

<sup>1</sup> = NYSDEC 6 NYCRR Part 375 Table 375-6.8(b), Restricted Use Soil Cleanup Objectives, Protection of Public Health; 14 December 2006.

<sup>2</sup> = Cleanup objective is the sum of the hexavalent and trivalent chromium restricted use soil cleanup objective.

<sup>3</sup> = Sub-slab boring locations are located on-site and are therefore compared to NYSDEC Industrial Standards only.

Sample depths are measured in inches.

**Table 2**  
**Summary of Analytical Data - GSP Swale -Soil**  
**General Super Plating Company**  
**Data Gap Investigation**  
**NYSDEC BCP No.: C734108**  
**ERM Project No.: 0111860**

Sample Location	NYSDEC Commercial Standard <sup>1,3</sup>	GSP-001		GSP-002		GSP-003		GSP-004		GSP-005		GSP-006		GSP-007	
Sample Depth		6 - 8	16 - 18	6 - 8	16 - 18	6 - 8	16 - 18	6 - 8	16 - 18	6 - 8	16 - 18	6 - 8	16 - 18	6 - 8	16 - 18
Date Sampled		27-May-05	27-May-05	27-May-05	27-May-05	27-May-05	27-May-05	27-May-05	27-May-05	27-May-05	27-May-05	27-May-05	27-May-05	27-May-05	27-May-05
<b>Metals (mg/kg)</b>															
Total Chromium <sup>2</sup>	1,900	555	89.4	1,100	574	104	324	3,450	1,580	605	430	85.8	149	3,560	1,350
Copper	270	217	59.1	123	65.5	48.9	54.2	163	56.5	63.7	20.3	114	635	9,280	1,940
Nickel	310	2,400	307	546	74.8	51.1	44.7	2,180	419	621	252	447	709	2,130	1,740
Zinc	10,000	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
<b>Inorganics (mg/kg)</b>															
Total Cyanide	27	NA	NA	78.5	5.99	NA	NA	903	17.6	NA	NA	NA	NA	2.5	ND

Sample Location	NYSDEC Commercial Standard <sup>1,3</sup>	GSP-008		GSP-009		GSP-010		GSP-011		GSP-012		GSP-013		GSP-014		
Sample Depth		6 - 8	16 - 18	6 - 8	16 - 18	6 - 8	16 - 18	6 - 8	16 - 18	6 - 8	16 - 18	6 - 8	16 - 18	6 - 8	6 - 8 <sup>d</sup>	16 - 18
Date Sampled		27-May-05	27-May-05	27-May-05	27-May-05	27-May-05	27-May-05	27-May-05	27-May-05	27-May-05	27-May-05	27-May-05	27-May-05	27-May-05	27-May-05	27-May-05
<b>Metals (mg/kg)</b>																
Total Chromium <sup>2</sup>	1,900	534	199	53.0	52.2	3,830	2,700	61.6	66.7	720	1,350	868	768	334	687	309
Copper	270	192	95.5	93.6	111	11,900	13,000	108	154	210	672	1,310	1,830	246	63.4	325
Nickel	310	220	118	91.9	277	3,720	2,440	85	84.4	176	376	967	1,240	1,060	106	845
Zinc	10,000	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
<b>Inorganics (mg/kg)</b>																
Total Cyanide	27	NA	NA	NA	NA	ND	ND	NA	NA	NA	NA	ND	ND	NA	NA	NA

Sample Location	NYSDEC Commercial Standard <sup>1,3</sup>	GSP-SWALE-015		GSP-SWALE-016		GSP-SWALE-017		GSP-SWALE-018		GSP-SWALE-019		GSP-SWALE-020		GSP-SWALE-021	
Sample Depth		1 - 3	13 - 15	1 - 3	13 - 15	1 - 3	13 - 15	1 - 3	13 - 15	1 - 3	13 - 15	1 - 3	13 - 15	1 - 3	13 - 15
Date Sampled		9-Jun-05	9-Jun-05	9-Jun-05	9-Jun-05	9-Jun-05	9-Jun-05	9-Jun-05	9-Jun-05	9-Jun-05	9-Jun-05	9-Jun-05	9-Jun-05	9-Jun-05	9-Jun-05
<b>Metals (mg/kg)</b>															
Total Chromium <sup>2</sup>	1,900	51.2	88.8	22.6	8.47	125	94.8	327	172	81.7	47.4	354	290	21.6	18.5
Copper	270	21.5	32.5	33.1	18.8	80.5	28.7	40.9	16.4	194	136	62.2	46.3	28.7	26.5
Nickel	310	276	294	27.6	12.1	46.2	22.3	59.4	60.7	222	125	75.1	69.5	21.6	147
Zinc	10,000	46.2	62.4	50.6	103	219	79.0	116	60.0	442	185	116	105	144	104
<b>Inorganics (mg/kg)</b>															
Total Cyanide	27	ND	ND	ND	ND	ND	ND	4.52	3.79	ND	ND	ND	ND	ND	ND

Sample Location	NYSDEC Commercial Standard <sup>1,3</sup>	GSP-SWALE-022		GSP-SWALE-023		GSP-SWALE-024		GSP-SWALE-025		GSP-SWALE-026		GSP-SWALE-027	
Sample Depth		1 - 3	13 - 15	1 - 3	13 - 15	1 - 3	13 - 15	1 - 3	13 - 15	1 - 3	13 - 15	1 - 3	13 - 15
Date Sampled		9-Jun-05	9-Jun-05	9-Jun-05	9-Jun-05	9-Jun-05	9-Jun-05	9-Jun-05	9-Jun-05	9-Jun-05	9-Jun-05	9-Jun-05	9-Jun-05
<b>Metals (mg/kg)</b>													
Total Chromium <sup>2</sup>	1,900	162	22.9	19.3	40.4	65.6	149	18.0	14.5	27.6	20.4	32.7	98.5
Copper	270	342	34.9	20.9	27.9	261	477	86.0	67.4	56.5	47.5	17.5	64.3
Nickel	310	231	36.7	20.0	23.1	768	468	18.5	14.7	26.0	19.5	16.3	36.7
Zinc	10,000	1,740	96.9	204	194	621	2,340	337	170	166	144	57.0	75.9
<b>Inorganics (mg/kg)</b>													
Total Cyanide	27	ND	3.79	ND	ND	ND	1.20	ND	ND	ND	ND	ND	ND

**Notes:**

  Exceedance of Site SCG

<sup>d</sup> = Duplicate Sample

mg/kg = milligrams per kilogram

NA = Not Analyzed

ND = Not detected at a concentration above the method detection limit.

<sup>1</sup> = NYSDEC 6 NYCRR Part 375 Table 375-6.8(b), Restricted Use Soil Cleanup Objectives, Protection of Public Health; 14 December 2006.

<sup>2</sup> = Cleanup objective is the sum of the hexavalent and trivalent chromium restricted use soil cleanup objective.

Sample depths are measured in inches.

Sample intervals are measured in feet below ground surface.

**Table 2 (continued)**  
**Summary of Analytical Data - GSP Swale - Soil**  
**General Super Plating Company**  
**Data Gap Investigation**  
**NYSDEC BCP No.: C734108**  
**ERM Project No.: 0111860**

Sample Location	NYSDEC Commercial Standard <sup>1,3</sup>	B-307		B-308		B-309		B-310		B-311		B-312	
		4 - 6	6 - 8	4 - 6	6 - 8	4 - 6	6 - 8	4 - 6	6 - 8	4 - 6	6 - 8	4 - 6	6 - 8
		Date Sampled	1-Mar-10	1-Mar-10	1-Mar-10	1-Mar-10	1-Mar-10	1-Mar-10	1-Mar-10	1-Mar-10	1-Mar-10	1-Mar-10	1-Mar-10
<b>Metals (mg/kg)</b>													
Total Chromium <sup>2</sup>	1,900	63.7	26.2	24.6	14.1	24.2	10.6	20.2	18.7	29.8	14.1	140	232
Hexavalent Chromium	400	1.47 J	2.44 J	0.924 J	0.96 J	3.62 J	1.05 J	2.31	2.16	0.804 J	1.76	4.46	0.44 J
Copper	270	40.4	34.2	15.4	23.1	20.0	12.7	16.9	17.8	18.2	17.1	114	25.8
Nickel	310	24.8	28.9	24.5	13.8	23.3	11.1	20.4	19.6	26.6	13.6	324	177
Zinc	10,000	64.2	103	58.0	34.1	74.1	23.4	42.4	39.3	64.2	29.0	58.8	71.5
<b>Inorganics (mg/kg)</b>													
Total Cyanide	27	ND	ND	1.37	ND	1.68	ND	ND	ND	ND	ND	ND	ND
<b>Volatile organic Compounds (mg/kg)</b>													
Acetone	500	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
Methylene Chloride	500	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA

Sample Location	NYSDEC Commercial Standard <sup>1,3</sup>	B-313			B-314		B-315			B-316			B-317		
		0 - 1	4 - 6	6 - 8	4 - 6	6 - 8	0 - 1	4 - 6	6 - 8	0 - 1	4 - 6	6 - 8	0 - 1	4 - 6	6 - 8
		Date Sampled	1-Mar-10	1-Mar-10	1-Mar-10	1-Mar-10	1-Mar-10	1-Mar-10	1-Mar-10	1-Mar-10	1-Mar-10	1-Mar-10	1-Mar-10	2-Mar-10	2-Mar-10
<b>Metals (mg/kg)</b>															
Total Chromium <sup>2</sup>	1,900	NA	11.6	17.1	25.2	16.4	NA	19.9	17.1	NA	25.3	8.77	NA	16.7	9.8
Hexavalent Chromium	400	NA	1.1 J	2.18	0.323 J	2.14	NA	0.84 J	0.926 J	NA	9.65 J	0.613 J	NA	0.264 J	0.615 J
Copper	270	NA	19.0	19.9	16.6	19.4	NA	14.7	21.3	NA	37.8	20.9	NA	16.0	17.1
Nickel	310	NA	29.8	19.0	54.6	20.2	NA	445	55.6	NA	77.8	13.8	NA	15.3	12.6
Zinc	10,000	NA	28.6	38.7	49.7	42.9	NA	47.1	42.2	NA	76.8	25.6	NA	38	23.3
<b>Inorganics (mg/kg)</b>															
Total Cyanide	27	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
<b>Volatile organic Compounds (mg/kg)</b>															
Acetone	500	ND	ND	NA	NA	NA	ND	ND	NA	ND	ND	NA	ND	ND	NA
Methylene Chloride	500	ND	ND	NA	NA	NA	ND	ND	NA	ND	ND	NA	ND	ND	NA

Sample Location	NYSDEC Commercial Standard <sup>1,3</sup>	B-318		B-319		B-320		B-350
		4 - 6	6 - 8	4 - 6	6 - 8	4 - 6	6 - 8	1.1-1.7
		Date Sampled	2-Mar-10	2-Mar-10	2-Mar-10	2-Mar-10	2-Mar-10	2-Mar-10
<b>Metals (mg/kg)</b>								
Total Chromium <sup>2</sup>	1,900	39.4	27.3	12.7	18.0	258	20.1	11.2 J
Hexavalent Chromium	400	0.559 J	0.61 J	2.77 J	0.744 J	5.82 J	0.715 J	0.442
Copper	270	22.7	14.3	21.9	26.4	33.5	24.1	20.5
Nickel	310	36.7	14.3	12.7	20.8	18.6	21.5	11.5 J
Zinc	10,000	77.0	34.8	47.1	51.4	114	51.6	26.3 J
<b>Inorganics (mg/kg)</b>								
Total Cyanide	27	ND	ND	ND	ND	2.33	1.62	ND
<b>Volatile organic Compounds (mg/kg)</b>								
Acetone	500	NA	NA	NA	NA	NA	NA	NA
Methylene Chloride	500	NA	NA	NA	NA	NA	NA	NA

**Notes:**

  Exceedance of Site SCG

<sup>d</sup> = Duplicate Sample

mg/kg = milligrams per kilogram

NA = Not Analyzed

ND = Not detected at a concentration above the method detection limit.

<sup>1</sup> = NYSDEC 6 NYCRR Part 375 Table 375-6.8(b), Restricted Use Soil Cleanup Objectives, Protection of Public Health; 14 December 2006.

<sup>2</sup> = Cleanup objective is the sum of the hexavalent and trivalent chromium restricted use soil cleanup objective.

Sample depths are measured in inches.

Sample intervals are measured in feet below ground surface.

**TABLE 3**  
**Summary of Analytical Data - Burried Culvert Pipe - Soil**  
**General Super Plating Company**  
**Data Gap Investigation**  
**NYSDEC BCP No.: C734108**  
**ERM Project No.: 0111860**

Sample Location	NYSDEC	GSP-344	GSP-345	GSP-346	GSP-347	GSP-348	GSP-349	GSP-349
Sample Depth	Commercial	5.5 - 6.5	5.5 - 6.5	6.5 - 7.5	5.5 - 6.5	5.5 - 6.5	2.5-3	5-5.5
Date Sampled	Standard <sup>1</sup>	22-Apr-10	22-Apr-10	22-Apr-10	22-Apr-10	22-Apr-10	27-May-10	27-May-10
<b>Metals (mg/kg)</b>								
Total Chromium	1,900	15.8 J	14.8 J	13.5 J	15 J	207 J	12.9 J	13.8 J
Hexavalent Chromium	400	ND	0.74 J	0.489 J	0.585 J	0.693 J	0.6 J	1.12 J
Copper	270	40.6 J	17.5 J	20.7 J	18.7 J	543 J	17.3	24
Nickel	310	16.1 J	15.7 J	16.3 J	15 J	375 J	12.6 J	12.5 J
Zinc	10,000	47.2 J	34 J	35.4 J	31.1 J	159 J	42.7 J	342 J
<b>Inorganics (mg/kg)</b>								
Total Cyanide	27	0.896 J	ND	ND	ND	ND	ND	ND
<b>Volatile Organic Compounds (mg/kg)</b>								
Acetone	500	NA	NA	NA	NA	NA	NA	NA
Methylene Chloride	500	NA	NA	NA	NA	NA	NA	NA

Notes:

Exceedance of Site SCG

<sup>d</sup> = Duplicate Sample

mg/kg = milligrams per kilogram

NA = Not Analyzed

ND = Not detected at a concentration above the method detection limit.

<sup>1</sup> = NYSDEC 6 NYCRR Part 375 Table 375-6.8(b), Restricted Use Soil Cleanup Objectives, Protection of Public Health; 14 December 2006.

<sup>2</sup> = Clean up objective is the sum of the hexavalent and trivalent chromium restricted use soil cleanup objective.

<sup>3</sup> = Sample locations are located off-site and are therefore compared to NYSDEC Commercial standards only.

Sample intervals are measured in feet below ground surface.

**Table 4**  
**Summary of Analytical Data - Bridge Street Swale - Soil**  
**General Super Plating Company**  
**Data Gap Investigation**  
**NYSDEC BCP No.: C734108**  
**ERM Project No.: 0111860**

Sample Location	NYSDEC Commercial Standard <sup>1</sup>	GSP-200		GSP-201	GSP-202		GSP-203		GSP-204	GSP-205		GSP-206		GSP-207
		3 - 6	13 - 16	3 - 6	3 - 6	13 - 16	3 - 6	13 - 16	3 - 6	3 - 6	13 - 16	3 - 6	13 - 16	3 - 6
		Date Sampled	3-Jun-05	3-Jun-05	3-Jun-05	3-Jun-05	3-Jun-05	3-Jun-05	3-Jun-05	3-Jun-05	3-Jun-05	3-Jun-05	3-Jun-05	3-Jun-05
<b>Metals (mg/kg)</b>														
Total Chromium <sup>2</sup>	1,900	174	59.0	118	363	251	29.5	58.0	137	17.2	17.1	15.1	17.0	21.7
Hexavalent Chromium	400	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
Copper	270	227	162	311	384	318	83.0	121	450	22.9	23.8	41.7	47.5	38.4
Nickel	310	175	76.0	127	244	225	22.0	40.9	219	18.8	17.6	28.8	32.3	19.8
Zinc	10,000	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
<b>Inorganics (mg/kg)</b>														
Total Cyanide	27	ND	ND	ND	4.53	4.32	ND	ND	ND	1.34	2.41	ND	ND	1.93
<b>Volatile Organic Compounds (mg/kg)</b>														
Acetone	500	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
Methylene Chloride	500	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA

Sample Location	NYSDEC Commercial Standard <sup>1</sup>	GSP-208		GSP-209		GSP-210	GSP-211 *	GSP-211	GSP-212		GSP-213	GSP-214	
		3 - 6	13 - 16	3 - 6	13 - 16	3 - 6	3 - 6	13 - 16	3 - 6	13 - 16	6 - 12	3 - 6	12 - 16
		Date Sampled	3-Jun-05	3-Jun-05	3-Jun-05	3-Jun-05	3-Jun-05	3-Jun-05	3-Jun-05	3-Jun-05	3-Jun-05	3-Jun-05	3-Jun-05
<b>Metals (mg/kg)</b>													
Total Chromium <sup>2</sup>	1,900	31.6	16.2	8.1	6.7	11.8	12.9	11.4	36.3	17.3	966	257	74.3
Hexavalent Chromium	400	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
Copper	270	112	27.6	10.7	10.3	23.4	16.7	19.4	185	105	4,350	763	149
Nickel	310	96.4	28.8	11.2	10.3	14.2	13.2	12.9	25.0	13.5	927	262	99.8
Zinc	10,000	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
<b>Inorganics (mg/kg)</b>													
Total Cyanide	27	1.74	ND	ND	ND	ND	ND	ND	ND	ND	2.66	ND	ND
<b>Volatile Organic Compounds (mg/kg)</b>													
Acetone	500	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
Methylene Chloride	500	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA

Sample Location	NYSDEC Commercial Standard <sup>1</sup>	GSP-215		GSP-216	GSP-217		GSP-218	GSP-219	GSP-220	GSP-221	BSS-S-222		BSS-S-223	
		3 - 6	13 - 16	3 - 6	3 - 6	13 - 16	3 - 6	3 - 6	3 - 6	3 - 6	1 - 3	13 - 15	1 - 3	13 - 15
		Date Sampled	3-Jun-05	3-Jun-05	3-Jun-05	3-Jun-05	3-Jun-05	3-Jun-05	3-Jun-05	3-Jun-05	3-Jun-05	10-Jun-05	10-Jun-05	10-Jun-05
<b>Metals (mg/kg)</b>														
Total Chromium <sup>2</sup>	1,900	10.8	6.7	731	20.1	26.7	321	14.8	465	69.0	11.4	10.8	9.17	11.4
Hexavalent Chromium	400	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
Copper	270	109	15.5	7,170	42.7	66.8	1,150	36.6	547	207	14.4	14.3	11.1	9.85
Nickel	310	13.7	9.4	2,330	41.5	51.6	412	22.0	190	78.5	11.8	9.33	11.5	12.2
Zinc	10,000	NA	NA	NA	NA	NA	NA	NA	NA	NA	62.8	48.1	32.7	45.7
<b>Inorganics (mg/kg)</b>														
Total Cyanide	27	ND	ND	ND	ND	ND	4.13	ND	ND	ND	ND	ND	ND	ND
<b>Volatile Organic Compounds (mg/kg)</b>														
Acetone	500	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
Methylene Chloride	500	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA

**Notes:**

  Exceedance of Site SCG

<sup>d</sup> = Duplicate Sample

mg/kg = milligrams per kilogram

mg/L = milligrams per liter

NA = Not Analyzed

ND = Not detected at a concentration above the method detection limit.

µg/kg = micrograms per kilogram

<sup>1</sup> = NYSDEC 6 NYCRR Part 375, Restricted Use Soil Cleanup Objectives, Protection of Public Health.

<sup>2</sup> = Cleanup objective is the sum of the hexavalent and trivalent chromium restricted use soil cleanup objective.

<sup>3</sup> = Sample locations are located off-site and are therefore compared to NYSDEC Commercial standards only.

Sample depths are measured in inches.

TABLE 4 (continued)  
 Summary of Analytical Data - Bridge Street Swale - Soil  
 General Super Plating Company  
 Data Gap Investigation  
 NYSDEC BCP No.: C734108  
 ERM Project No.: 0111860

Sample Location	NYSDEC Commercial Standard <sup>1</sup>	BSS-S-224		BSS-S-225		BSS-S-226		BSS-S-227		BSS-S-228		BSS-S-229		BSS-S-230		BSS-S-231	
		0 - 2		0 - 2		0 - 2		1 - 3	13 - 15	1 - 3	13 - 15	1 - 3	13 - 15	1 - 3	13 - 15	0 - 2	13 - 15
		Date Sampled		10-Jun-05	10-Jun-05	10-Jun-05	10-Jun-05	10-Jun-05	10-Jun-05	10-Jun-05	10-Jun-05	10-Jun-05	10-Jun-05	10-Jun-05	10-Jun-05	10-Jun-05	10-Jun-05
<b>Metals (mg/kg)</b>																	
Total Chromium <sup>2</sup>	1,900	38.6	15.5	22.7	53.4	25.2	6.24	5.51	6.92	8.27	8.66	8.50	45.5	12.1			
Hexavalent Chromium	400	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
Copper	250	73.7	24.4	31.9	90.4	57.5	5.47	8.33	8.41	23.8	18.0	18.6	81.9	44.9			
Nickel	310	26.6	15.3	19.5	67.5	36.5	6.32	7.24	8.39	11.4	12.2	11.9	14.3	8.88			
Zinc	10,000	269	109	100	163	87.8	46.0	30.6	42.9	45.7	64.0	71.5	385	74.3			
<b>Inorganics (mg/kg)</b>																	
Total Cyanide	27	1.72	ND	ND	ND	ND	ND	ND	ND	1.72	ND	ND	15.7	ND			
<b>Volatile Organic Compounds (mg/kg)</b>																	
Acetone	500	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
Methylene Chloride	500	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA

Sample Location	NYSDEC Commercial Standard <sup>1</sup>	BSS-S-232		GSP-233	GSP-234	GSP-235	GSP-321	GSP-322	GSP-323	GSP-324	GSP-325	GSP-326	GSP-327	GSP-328	
		0 - 2		13 - 15	6 - 12	6 - 18	6 - 18	0 - 2	0 - 2	0 - 2	0 - 2	0 - 2	0 - 2	0 - 2	0 - 2
		Date Sampled		10-Jun-05	10-Jun-05	16-Oct-06	16-Oct-06	16-Oct-06	7-Apr-10	7-Apr-10	7-Apr-10	7-Apr-10	7-Apr-10	7-Apr-10	7-Apr-10
<b>Metals (mg/kg)</b>															
Total Chromium <sup>2</sup>	1,900	21.8	11.3	426	144	117	55.1	226	0.844 J	17.6	318	1,080	33.6	43.1	
Hexavalent Chromium	400	NA	NA	5.31	2.6	ND	ND	0.97 J	0.155 J	0.331 J	22 J	14.8 J	ND	13.4 J	
Copper	270	88.1	76.5	1,710	220	99.0	153	1,220	ND	29.0	544	1,040	57.9	84.1	
Nickel	310	24.3	13.3	442	104	61.0	121	333	1.95	17.5	143	331	29.4	31.1	
Zinc	10,000	164	80.9	760	576	238	78.4	303	11.1	40.4	554	981	99.1	126	
<b>Inorganics (mg/kg)</b>															
Total Cyanide	27	ND	ND	ND	ND	ND	0.848 J	ND	1.11 J	1.11 J	13.6	4.17	ND	2.37	
<b>Volatile Organic Compounds (mg/kg)</b>															
Acetone	500	NA	NA	NA	NA	NA	123	ND	NA	NA	NA	NA	NA	NA	
Methylene Chloride	500	NA	NA	NA	NA	NA	ND	ND	NA	NA	NA	NA	NA	NA	

Sample Location	NYSDEC Commercial Standard <sup>1</sup>	GSP-B-329			GSP-B-330			GSP-B-331			GSP-B-332			
		0 - 2		12 - 14	22 - 24		0 - 2	12 - 14	22 - 24		0 - 2	12 - 14	22 - 24	
		Date Sampled		8-Apr-10	8-Apr-10	8-Apr-10	8-Apr-10	8-Apr-10	8-Apr-10	8-Apr-10	8-Apr-10	8-Apr-10	8-Apr-10	8-Apr-10
<b>Metals (mg/kg)</b>														
Total Chromium <sup>2</sup>	1,900	39.6	9.07	16.1	373	15.5	9.55	18.3	18.6	12.8	30.3	25.5	8.63	
Hexavalent Chromium	400	ND	ND	0.322 J	7.87 J	0.236 J	0.215 J	9.14 J	7.22 J	ND	8.09 J	ND	1.1	
Copper	270	56.7	10.6	17.8	1,050	24.9	12.8	28.2	26.0	13.9	36.9	21.8	12.9	
Nickel	310	18.2	6.11	10.7	175	12.9	7.57	14.2	14.6	9.34	17.7	17.6	7.41	
Zinc	10,000	227	43.5	65.4	369	33.1	22.3	73.4	54.4	37.4	86.0	43.2	40.5	
<b>Inorganics (mg/kg)</b>														
Total Cyanide	27	1.7	22.7	1.66	5.78	ND	ND	0.061 J	ND	ND	0.759 J	ND	ND	
<b>Volatile Organic Compounds (mg/kg)</b>														
Acetone	500	NA	NA	NA	ND	NA	ND	NA	NA	NA	NA	NA	NA	
Methylene Chloride	500	NA	NA	NA	ND	NA	ND	NA	NA	NA	NA	NA	NA	

Notes:

- Exceedance of Site SCG
- <sup>d</sup> = Duplicate Sample
- mg/kg = milligrams per kilogram
- mg/L = milligrams per liter
- NA = Not Analyzed
- ND = Not detected at a concentration above the method detection limit.
- µg/kg = micrograms per kilogram
- <sup>1</sup> = NYSDEC 6 NYCRR Part 375, Restricted Use Soil Cleanup Objectives, Protection of Public Health.
- <sup>2</sup> = Cleanup objective is the sum of the hexavalent and trivalent chromium restricted use soil cleanup objective.
- <sup>3</sup> = Sample locations are located off-site and are therefore compared to NYSDEC Commercial standards only. Sample depths are measured in inches.

TABLE 4 (continued)  
 Summary of Analytical Data - Bridge Street Swale - Soil  
 General Super Plating Company  
 Data Gap Investigation  
 NYSDEC BCP No.: C734108  
 ERM Project No.: 0111860

Sample Location Sample Depth Date Sampled	NYSDEC Commercial Standard <sup>1</sup>	GSP-B-333			GSP-B-334			GSP-B-335			GSP-B-336		
		0 - 2	12 - 14	22 - 24	0 - 2	12 - 14	22 - 24	0 - 2	12 - 14	22 - 24	0 - 2	12 - 14	22 - 24
		8-Apr-10	8-Apr-10	8-Apr-10	8-Apr-10	8-Apr-10	8-Apr-10	8-Apr-10	8-Apr-10	8-Apr-10	8-Apr-10	8-Apr-10	8-Apr-10
<b>Metals (mg/kg)</b>													
Total Chromium <sup>2</sup>	1,900	83.6	12.3	19.1	13.4	13.9	14.4	28.0	225	160	14.4	15.0	15.8
Hexavalent Chromium	400	7.3 J	ND	13.9 J	6.22 J	7.84 J	4.02 J	0.553 J	3.35 J	15.1	9.53 J	ND	ND
Copper	270	313	25.4	95.2	23.5	26.9	20.0	35.4	523	287	22.2	22.2	19.1
Nickel	310	251	18.3	25.6	19.2	17.9	14.5	52.8	207	175	15.2	15.6	15.4
Zinc	10,000	175	26.2	63.3	39.3	42.0	40.7	109	409	459	50.3	39	42.8
<b>Inorganics (mg/kg)</b>													
Total Cyanide	27	1.24 J	ND	ND	1.08 J	0.616 J	4.02	ND	2.37	2.65	ND	ND	ND
<b>Volatile Organic Compounds (mg/kg)</b>													
Acetone	500	ND	NA	ND	NA	NA	NA	NA	NA	NA	NA	NA	NA
Methylene Chloride	500	ND	NA	ND	NA	NA	NA	NA	NA	NA	NA	NA	NA

Sample Location Sample Depth Date Sampled	NYSDEC Commercial Standard <sup>1</sup>	GSP-B-337			GSP-B-338			GSP-B-339		
		0 - 2	12 - 14	22 - 24	0 - 2	12 - 14	22 - 24	0 - 2	12 - 14	22 - 24
		8-Apr-10	8-Apr-10	8-Apr-10	8-Apr-10	8-Apr-10	8-Apr-10	8-Apr-10	8-Apr-10	8-Apr-10
<b>Metals (mg/kg)</b>										
Total Chromium <sup>2</sup>	1,900	90.1	58.6	19.5	28.1	17.8	21.1	26.4	22.4	18.3
Hexavalent Chromium	400	12.3 J	5.12 J	0.286 J	0.232 J	0.209 J	ND	5.49 J	9.68 J	9.45 J
Copper	270	146	150	21.4	43.3	23.3	18.8	44.5	32.8	13.7
Nickel	310	48.1	38.5	19.2	29.1	14.1	14.3	22.0	20.1	16.9
Zinc	10,000	534	236	50.3	98.2	406	328	132	91.8	51.7
<b>Inorganics (mg/kg)</b>										
Total Cyanide	27	2.05	1.35	ND	ND	ND	0.61 J	0.846 J	ND	ND
<b>Volatile Organic Compounds (mg/kg)</b>										
Acetone	500	NA	NA	NA	NA	NA	NA	NA	NA	NA
Methylene Chloride	500	NA	NA	NA	NA	NA	NA	NA	NA	NA

- Notes:
- Exceedance of Site SCG
  - <sup>d</sup> = Duplicate Sample
  - mg/kg = milligrams per kilogram
  - mg/L = milligrams per liter
  - NA = Not Analyzed
  - ND = Not detected at a concentration above the method detection limit.
  - µg/kg = micrograms per kilogram
  - <sup>1</sup> = NYSDEC 6 NYCRR Part 375, Restricted Use Soil Cleanup Objectives, Protection of Public Health.
  - <sup>2</sup> = Cleanup objective is the sum of the hexavalent and trivalent chromium restricted use soil cleanup objective.
  - <sup>3</sup> = Sample locations are located off-site and are therefore compared to NYSDEC Commercial standards only.  
Sample depths are measured in inches.




**TABLE 5**  
**Summary of Analytical Data - Site Permanent Monitoring Wells- Ground Water**  
**General Super Plating Company**  
**Data Gap Investigation**  
**NYSDEC BCP No.: C734108**  
**ERM Project No.: 0111860**

Sample Location	NYSDEC Standard <sup>1</sup>	MW-1		MW-2		MW-3		MW-4	MW-5	MW-6	MW-7	MW-8
		22-Aug-05	18-Mar-10	22-Aug-05	18-Mar-10	22-Aug-05	18-Mar-10	18-Mar-10	18-Mar-10	18-Mar-10	18-Mar-10	18-Mar-10
<b>Metals (mg/L)</b>												
Total Chromium	0.05	ND	ND	ND	0.0024 J	ND	ND	0.010	ND	ND	ND	ND
Hexavalent Chromium	0.011	0.0110	ND	0.0090	ND	0.0140	ND	ND	0.010 J	ND	ND	ND
Copper	0.2	ND	ND	0.0036	ND	ND	0.0041 J	0.0226	ND	ND	ND	ND
Nickel	0.1	ND	0.0014 J	0.0059	0.0084	0.0047	0.102	0.237	0.0031 J	0.010	0.0018 J	0.0042 J
Zinc	2.0***	ND	0.0094 J	ND	0.0104 J	ND	0.0118 J	0.022	0.0119 J	0.0114 J	0.0138 J	0.0145
<b>Volatile Organic Compounds (µg/L)</b>												
Acetone	0.05***	NA	ND	NA	ND	NA	ND	ND	ND	ND	ND	ND
Methylene Chloride	0.005	NA	ND	NA	ND	NA	ND	ND	ND	ND	ND	ND
<b>Inorganics (mg/L)</b>												
Total Cyanide	0.2	ND	ND	ND	0.00356 J	ND	0.00371 J	ND	ND	ND	0.00777	0.00410 J

Notes:

- Exceedance of Site SCG
- J = An estimated value.
- mg/L = milligrams per liter
- NA = Not Analyzed
- ND = Not detected at a concentration above the method detection limit.
- µg/L = micrograms per liter
- <sup>1</sup> = NYSDEC Technical and Operational Guidance Series (TOGS) 1.1.1 Ambient Water Quality Standards
- \*\*\* = Guidance Value

Attachment B-3 – Excerpts from Work Plan to  
Address Areas of Concern 1, 2, & 3, ERM, November  
2012




**AOC-3**  
Buried Culvert Pipe

**Site Property Boundary**

**AOC-1**  
Sub-Slab Soil

**AOC-2**  
GSP Swale



Site Layout Map and Areas of Concern

PREPARED FOR  
GSP Holdings, Inc.



SCALE  
See Scale Bar  
DATE  
November 2012

FIGURE  
**2**



001	Depth 6-8 in.
Sample Date	27-May-05
Nickel	2400

002	Depth 6-8 in.
Sample Date	27-May-05
Nickel	546

004	Depth 6-8 in.	Depth 16-18 in.
Sample Date	27-May-05	27-May-05
Total Chromium	3,450	1,580
Nickel	2180	419

005	Depth 6-8 in.
Sample Date	27-May-05
Nickel	621

022	Depth 16-18 in.
Sample Date	27-May-05
Copper	342

312	Depth 4-6 ft.
Sample Date	1-Mar-10
Nickel	324

024	Depth 1-3 in.	Depth 13-15 in.
Sample Date	9-Jun-05	9-Jun-05
Copper	261	477
Nickel	768	468

007	Depth 6-8 in.	Depth 16-18 in.
Sample Date	27-May-05	27-May-05
Total Chromium	3,560	1,350
Copper	9,280	1,940
Nickel	2,130	1,740

006	Depth 6-8 in.	Depth 16-18 in.
Sample Date	27-May-05	27-May-05
Copper	114	635
Nickel	447	709

315	Depth 4-6 ft.
Sample Date	1-Mar-10
Nickel	445

010	Depth 6-8 in.	Depth 16-18 in.
Sample Date	27-May-05	27-May-05
Total Chromium	3,830	2,700
Copper	11,900	13,000
Nickel	3,720	2,440

013	Depth 6-8 in.	Depth 16-18 in.
Sample Date	27-May-05	27-May-05
Copper	1,310	1,830
Nickel	967	1,240

012	Depth 16-18 in.
Sample Date	27-May-05
Copper	672
Nickel	376

014	Depth 6-8 in.	Depth 16-18 in.
Sample Date	27-May-05	27-May-05
Copper	246	325
Nickel	1,060	845

**Legend**

- Site Property Boundary
  - Source Identification Investigation Sample Locations (2005)
  - ▲ DGI Soil Boring Locations (2010)
  - Exceedance of Part 375 Restricted-Commercial Soil Cleanup Objective
  - Exceedance of Part 375 Restricted-Industrial Soil Cleanup Objective
  - TW-1 Temporary Well Location
  - TPW-1 Test Pit Well Location
  - CB-1 Catch Basin
- \*Note: Unit concentrations for samples are milligrams per kilogram



**AOC-2 - GSPH Swale  
Concentration of Metals in Soil**

PREPARED FOR  
GSP Holdings, Inc.



SCALE  
See Scale Bar  
DATE  
November 2012

FIGURE  
**4**




348	Depth 5.5-6.5 in.
Sample Depth	22-Apr-10
Nickel	375 J

**Estimated Location of Culvert** →

**Legend**


- Site Property Boundary
- DGI Soil Boring Locations (2010)
- Exceedance of Part 375 Restricted-Commercial Soil Cleanup Objective
- CB-1 Catch Basin

\*Note: Unit concentrations for samples are milligrams per kilogram




<b>AOC-3 - Buried Culvert Pipe Concentration of Metals in Soil</b>		
PREPARED FOR <b>GSP Holdings, Inc.</b>		
 <b>ERM</b>	SCALE See Scale Bar	<b>FIGURE 5</b>
	DATE November 2012	

Attachment B-4 – Excerpts from Monthly  
Progress Report – October 2012, ERM, November 9,  
2012




- Legend**
- Source Identification Investigation Sample Locations (2005)
  - ▲ DGI Soil Boring Locations (2010)
  - Sample Locations (2012)



**Bridge Street Swale Area  
Sample Locations**

PREPARED FOR  
**General Super Plating - Dewitt, New York**

 ERM	SCALE See Scale Bar	FIGURE
	DATE October 2012	1

G:\Projects\2012\11\02\2012 - 12 Super Plating

**Table 1: Analytical Summary of Soil Samples Reported in October 2012**  
**Celi Drive Site - Dewitt, New York**  
 NYSDEC BCP Site No.: C734108

	Date Collected	Sample Depth (ft)	NYSDEC Restricted Use Soil Cleanup Objective-Commercial				
			1,500	270	310	10,000	27
Sample Location			Chromium	Copper	Nickel	Zinc	Cyanide
GSPH-400	10/17/2012	0-0.5	16.7	38.7	17.5	57.4	<0.524
GSPH-401	10/17/2012	0-0.5	30.4	50.8	25.3	166	<0.586
GSPH-Dup 01*	10/17/2012	0-0.5	24.2	41.4	27.3	146	<0.526
GSPH-402	10/17/2012	0-0.5	143	545	202	401	<0.906

**Notes:**

<: Analyte was not detected above the method detection limit.

\*: Blind duplicate sample, parent sample is GSPH-401.




Analyte reported above the restricted commercial soil cleanup objective value.




Attachment B-5 – Excerpts from Emergency  
Remedial Work Plan, GHD, June 2013



LEGEND:

-  CATCH BASIN AND BURIED CULVERT (APPROXIMATE)
-  AREA OF EXISTING BRIDGE STREET SWALE AFFECTED BY DEVELOPMENT (APPROXIMATE)
-  AREA OF NEW DEVELOPMENT (APPROXIMATE)

NOT TO SCALE




GSP Holdings, Inc.  
 Celi Drive BCP Site (Site #C734108)  
 Emergency Remedial Work Plan  
 Site Plan View

Job Number | 37-11082  
 Revision | A  
 Date | June 2013

Figure 02


Attachment B-6 – Excerpts from Background  
Sediment Sampling Letter Report, GHD, October 2013



LEGEND:

- BACKGROUND SEDIMENT SAMPLE LOCATION (APPROXIMATE)

NOT TO SCALE



NOTES:  
 1. AERIAL PHOTOGRAPHS ARE 2012 HALF FOOT 4 BAND CENTRAL ZONE INDEX FROM THE NYSGIS CLEARINGHOUSE WEBSITE: <http://gis.ny.gov/>  
 2. BACKGROUND SEDIMENT SAMPLE LOCATIONS ARE APPROXIMATE.



GSP Holdings, Inc.  
 Celi Drive BCP Site  
 BCP Site #C734108  
 Background Sediment Sample Locations

Job Number | 37-11082  
 Revision | A  
 Date | 10.08.13

Figure 2



Table 2 - (Page 1 of 5): Summary of Background Sediment Sample Laboratory Analytical Results, Celi Drive BCP Site (BCP Site #C734108), Syracuse, NY.

ANALYTE (mg/kg)	SOIL CLEANUP OBJECTIVES				Rural Soil Background Concentrations*	TAGM #4046 - Eastern USA Background^	SAMPLE IDENTIFICATION					
	UNRESTRICTED USE	COMMERCIAL USE	PROTECTION OF ECOLOGICAL RESOURCES				Background A1		Background A2		Background A3	
Sample Date							9/3/2013		9/3/2013		9/3/2013	
Sample Depth (ft. bgs)							0 - 6"		12 - 14"		22 - 24"	
<b>Metals by EPA Method 6010C</b>								R.L.		R.L.		R.L.
Chromium, Total	30	1,500	41	30	1.5 - 40**	17			27		17	
Copper, Total	50	270	50		1 - 50	34			<b>67</b>		24	
Nickel, Total	30	310	30		0.5 - 25	20			16		22	
Zinc, Total	109	10,000	109		9 - 50	84			<b>300</b>		51	
<b>Cyanide by EPA Method 9010C</b>												
Cyanide, Total	27	27	NS		N/A		U 1.4		U 2.7		U 1.3	
<b>Chromium by EPA Method 7196A</b>												
Chromium, Hexavalent	1	400	1	NE			U 1.2		U 2.4		U 1.1	

All values reported as mg/kg (parts per million)

Soil Cleanup Objectives from 6 NYCRR Part 375-6.8(b) (December 2006) and Supplemental Soil Cleanup Objectives (October 2010)

\* - Rural Soil Background Concentrations from New York State Brownfield Cleanup Program - Development of Cleanup Objectives Technical Support Document (NYSDEC and NYSDOH, September, 2006)

^ - Eastern USA Background from Appendix A of Tagm #4046 (NYSDEC, June, 1994)

U - Analyzed for but not detected above the laboratory reporting limit

J - Estimated value

R.L. - Laboratory Reporting Limit

NE - Not Established

NS - Not Specified

N/A - Not Available

\*\* - New York State Background

\*\*\* - Background levels vary widely. Average levels in undeveloped, rural areas range from 4 - 61 ppm. Average background levels in metropolitan or suburban areas or near highways typically range from 200 - 500 ppm.

Bold and thick outlined cell indicates analyte exceeds the Unrestricted Use Soil Cleanup Objective

Bold, thick outlined, and shaded cell indicates analyte exceeds the Protection of Ecological Resources and the Unrestricted Use Soil Cleanup Objectives



Table 2 - (Page 2 of 5): Summary of Background Sediment Sample Laboratory Analytical Results. Celi Drive BCP Site (BCP Site #C734108), Syracuse, NY.

ANALYTE (mg/kg)	SOIL CLEANUP OBJECTIVES				Rural Soil Background Concentrations*	TAGM #4046 - Eastern USA Background^	SAMPLE IDENTIFICATION					
	UNRESTRICTED USE	COMMERCIAL USE	PROTECTION OF ECOLOGICAL RESOURCES				Background B1		Background B2		Background B3	
Sample Date							9/3/2013		9/3/2013		9/3/2013	
Sample Depth (ft. bgs)							0 - 6"		12 - 14"		22 - 24"	
<b>Metals by EPA Method 6010C</b>								R.L.		R.L.		R.L.
Chromium, Total	30	1,500	41	30	1.5 - 40**	27			11		18	
Copper, Total	50	270	50		1 - 50	<b>60</b>			22		33	
Nickel, Total	30	310	30		0.5 - 25	<b>26</b>			12		22	
Zinc, Total	109	10,000	109		9 - 50	<b>140</b>			42		57	
<b>Cyanide by EPA Method 9010C</b>												
Cyanide, Total	27	27	NS		N/A		U 2.2		U 1.3		U 1.6	
<b>Chromium by EPA Method 7196A</b>												
Chromium, Hexavalent	1	400	1	NE			U 1.8		U 1.1		U 1.4	

All values reported as mg/kg (parts per million)

Soil Cleanup Objectives from 6 NYCRR Part 375-6.8(b) (December 2006) and Supplemental Soil Cleanup Objectives (October 2010)

\* - Rural Soil Background Concentrations from New York State Brownfield Cleanup Program - Development of Cleanup Objectives Technical Support Document (NYSDEC and NYSDOH, September, 2006)

^ - Eastern USA Background from Appendix A of Tagm #4046 (NYSDEC, June, 1994)

U - Analyzed for but not detected above the laboratory reporting limit

J - Estimated value

R.L. - Laboratory Reporting Limit

NE - Not Established

NS - Not Specified

N/A - Not Available

\*\* - New York State Background

\*\*\* - Background levels vary widely. Average levels in undeveloped, rural areas range from 4 - 61 ppm. Average background levels in metropolitan or suburban areas or near highways typically range from 200 - 500 ppm.

Bold and thick outlined cell indicates analyte exceeds the Unrestricted Use Soil Cleanup Objective

Bold, thick outlined, and shaded cell indicates analyte exceeds the Protection of Ecological Resources and the Unrestricted Use Soil Cleanup Objectives



Table 2 - (Page 3 of 5): Summary of Background Sediment Sample Laboratory Analytical Results. Celi Drive BCP Site (BCP Site #C734108), Syracuse, NY.

ANALYTE (mg/kg)	SOIL CLEANUP OBJECTIVES				SAMPLE IDENTIFICATION						
	UNRESTRICTED USE	COMMERCIAL USE	PROTECTION OF ECOLOGICAL RESOURCES	Rural Soil Background Concentrations*	TAGM #4046 - Eastern USA Background^	Background C1		Background C2		Background C3	
Sample Date						9/3/2013		9/3/2013		9/3/2013	
Sample Depth (ft. bgs)						0 - 6"		12 - 14"		22 - 24"	
<b>Metals by EPA Method 6010C</b>							R.L.		R.L.		R.L.
Chromium, Total	30	1,500	41	30	1.5 - 40**	<b>80</b>		<b>48</b>		19	
Copper, Total	50	270	50		1 - 50	14		49		<b>51</b>	
Nickel, Total	30	310	30		0.5 - 25	6.8		16		18	
Zinc, Total	109	10,000	109		9 - 50	85		<b>120</b>		100	
<b>Cyanide by EPA Method 9010C</b>											
Cyanide, Total	27	27	NS		N/A	U	1.3	U	1.5	U	1.5
<b>Chromium by EPA Method 7196A</b>											
Chromium, Hexavalent	1	400	1	NE		U	1	U	1.2	U	1.3

All values reported as mg/kg (parts per million)

Soil Cleanup Objectives from 6 NYCRR Part 375-6.8(b) (December 2006) and Supplemental Soil Cleanup Objectives (October 2010)

\* - Rural Soil Background Concentrations from New York State Brownfield Cleanup Program - Development of Cleanup Objectives Technical Support Document (NYSDEC and NYSDOH, September, 2006)

^ - Eastern USA Background from Appendix A of Tagm #4046 (NYSDEC, June, 1994)

U - Analyzed for but not detected above the laboratory reporting limit

J - Estimated value

R.L. - Laboratory Reporting Limit

NE - Not Established

NS - Not Specified

N/A - Not Available

\*\* - New York State Background

\*\*\* - Background levels vary widely. Average levels in undeveloped, rural areas range from 4 - 61 ppm. Average background levels in metropolitan or suburban areas or near highways typically range from 200 - 500 ppm.

Bold and thick outlined cell indicates analyte exceeds the Unrestricted Use Soil Cleanup Objective

Bold, thick outlined, and shaded cell indicates analyte exceeds the Protection of Ecological Resources and the Unrestricted Use Soil Cleanup Objectives



Table 2 - (Page 4 of 5): Summary of Background Sediment Sample Laboratory Analytical Results. Celi Drive BCP Site (BCP Site #C734108), Syracuse, NY.

ANALYTE (mg/kg)	SOIL CLEANUP OBJECTIVES			Rural Soil Background Concentrations*	TAGM #4046 - Eastern USA Background^	SAMPLE IDENTIFICATION			
	UNRESTRICTED USE	COMMERCIAL USE	PROTECTION OF ECOLOGICAL RESOURCES			Background D1	Background D2	Background D3	Duplicate
Sample Date						9/3/2013	9/3/2013	9/3/2013	9/3/2013
Sample Depth (ft. bgs)						0 - 6"	12 - 14"	22 - 24"	0 - 6" (Background D1)
<b>Metals by EPA Method 6010C</b>									
Chromium, Total	30	1,500	41	30	1.5 - 40**	<b>40</b>	<b>48</b>	<b>31</b>	<b>38</b>
Copper, Total	50	270	50		1 - 50	38	30	40	35
Nickel, Total	30	310	30		0.5 - 25	15	16	20	15
Zinc, Total	109	10,000	109		9 - 50	<b>140</b>	51	67	<b>130</b>
<b>Cyanide by EPA Method 9010C</b>									
Cyanide, Total	27	27	NS		N/A	U 1.6	U 1.4	U 1.7	U 1.6
<b>Chromium by EPA Method 7196A</b>									
Chromium, Hexavalent	1	400	1	NE		U 1.4	U 1.1	U 1.4	U 1.4

All values reported as mg/kg (parts per million)

Soil Cleanup Objectives from 6 NYCRR Part 375-6.8(b) (December 2006) and Supplemental Soil Cleanup Objectives (October 2010)

\* - Rural Soil Background Concentrations from New York State Brownfield Cleanup Program - Development of Cleanup Objectives Technical Support Document (NYSDEC and NYSDOH, September, 2006)

^ - Eastern USA Background from Appendix A of Tagm #4046 (NYSDEC, June, 1994)

U - Analyzed for but not detected above the laboratory reporting limit

J - Estimated value

R.L. - Laboratory Reporting Limit

NE - Not Established

NS - Not Specified

N/A - Not Available

\*\* - New York State Background

\*\*\* - Background levels vary widely. Average levels in undeveloped, rural areas range from 4 - 61 ppm. Average background levels in metropolitan or suburban areas or near highways typically range from 200 - 500 ppm.

Bold and thick outlined cell indicates analyte exceeds the Unrestricted Use Soil Cleanup Objective

Bold, thick outlined, and shaded cell indicates analyte exceeds the Protection of Ecological Resources and the Unrestricted Use Soil Cleanup Objectives





Table 2 - (Page 5 of 5): Summary of Background Sediment Sample Laboratory Analytical Results. Celi Drive BCP Site (BCP Site #C734108), Syracuse, NY.

ANALYTE (mg/kg)	SOIL CLEANUP OBJECTIVES				Rural Soil Background Concentrations*	TAGM #4046 - Eastern USA Background^	SAMPLE IDENTIFICATION					
	UNRESTRICTED USE	COMMERCIAL USE	PROTECTION OF ECOLOGICAL RESOURCES				Background E1		Background E2		Background E3	
Sample Date							9/3/2013		9/3/2013		9/3/2013	
Sample Depth (ft. bgs)							0 - 6"		12 - 14"		22 - 24"	
<b>Metals by EPA Method 6010C</b>								R.L.		R.L.		R.L.
Chromium, Total	30	1,500	41	30	1.5 - 40**	9.1			16		14	
Copper, Total	50	270	50		1 - 50	31			46		24	
Nickel, Total	30	310	30		0.5 - 25	10			19		19	
Zinc, Total	109	10,000	109		9 - 50	<b>290</b>			<b>130</b>		46	
<b>Cyanide by EPA Method 9010C</b>												
Cyanide, Total	27	27	NS		N/A		U 1.8		U 1.7		U 1.2	
<b>Chromium by EPA Method 7196A</b>												
Chromium, Hexavalent	1	400	1	NE			U 1.5		U 1.5		U 1	

All values reported as mg/kg (parts per million)

Soil Cleanup Objectives from 6 NYCRR Part 375-6.8(b) (December 2006) and Supplemental Soil Cleanup Objectives (October 2010)

\* - Rural Soil Background Concentrations from New York State Brownfield Cleanup Program - Development of Cleanup Objectives Technical Support Document (NYSDEC and NYSDOH, September, 2006)

^ - Eastern USA Background from Appendix A of Tagm #4046 (NYSDEC, June, 1994)

U - Analyzed for but not detected above the laboratory reporting limit

J - Estimated value

R.L. - Laboratory Reporting Limit

NE - Not Established

NS - Not Specified

N/A - Not Available


\*\* - New York State Background

\*\*\* - Background levels vary widely. Average levels in undeveloped, rural areas range from 4 - 61 ppm. Average background levels in metropolitan or suburban areas or near highways typically range from 200 - 500 ppm.

Bold and thick outlined cell indicates analyte exceeds the Unrestricted Use Soil Cleanup Objective


Bold, thick outlined, and shaded cell indicates analyte exceeds the Protection of Ecological Resources and the Unrestricted Use Soil Cleanup Objectives

Attachment B-7 – Excerpts from Groundwater  
Sampling Letter Report, GHD, April 16, 2014



**NOTES:**

- 1) Site features are from a field survey completed by DJW on 11/11/14. LSI, P.C. dated November 11, 2012 and revised 11-1-2011, 3-2-2011, 11-10-2011, 11-10-2011, 11-24-2011, and 4-1-2014.
- 2) Aerial photographs are 2012, 12/11/14 and central zone index from the NYS: IS Clearing house website: <http://isny.gov>
- 3) MW-1 could not be located in the field and was not surveyed previously!



GSP Holdings, Inc.  
 Celi Drive BCP Site (BCP Site #C734108)  
 Groundwater Sampling Report  
 Site Layout

Job Number | 37-11082

Revision | A

Date | 02.26.14

Figure 2



Table 1: (Page 1 of 1) Groundwater Elevation Data. Celi Drive BCP Site, Syracuse, NY.

Monitoring Well I.D.	Date	Reference Point	Reference Elevation (feet)	DTW (feet)	DOW (feet)	Water Elevation (feet)	Volume (gal)
MW-1	1/31/2014	Top of PVC	413.46	3.58	16.16	409.88	2.01
MW-2	1/31/2014	Top of PVC	414.05	2.92	14.85	411.13	1.91
MW-3	1/31/2014	Top of PVC	416.10	4.46	14.58	411.64	1.62
MW-4	1/31/2014	Top of PVC	415.88	4.30	14.75	411.58	1.67
MW-5	1/31/2014	Top of PVC	415.01	4.07	13.90	410.94	1.57
MW-6	1/31/2014	Top of PVC	413.16	2.95	13.76	410.21	1.73
MW-7	1/31/2014	Top of PVC	412.92	3.05	13.14	409.87	1.61
MW-8	1/31/2014	Top of PVC	NM	NM	NM	NM	NM

DTW - depth to water

DOW - depth of well

NM - Not Measured because well could not be located



Table 2: (Page 1 of 2) Groundwater Field Parameter Data, Cell Drive BCP Site, Syracuse, NY.

Well I.D.	Date	Time	Temp (°C)	Conductivity (mmhos/cm)	Salinity (%)	Dissolved Oxygen (mg/L)	pH (units)	ORP (mV)	Turbidity (NTU)	DTW (feet)	Amount Purged (liters)	Comments
MW-1	1/31/2014	7:51	9.16	1.436	1.05	3.2	8.12	45.3	1401.5	3.72	14.0	Purged 14 liters at 3 cycles per minute. Water started cloudy light yellowish brown with some sediment and cleared quickly. Sample water was clear with no sheen or odor.
		7:55	10.82	1.501	1.06	0.89	7.09	9.3	1145.4	3.70		
		7:58	10.78	1.504	1.06	0.75	7.04	-0.7	800.8	3.70		
		8:01	10.76	1.502	1.06	0.62	7.03	1.2	687.4	3.70		
		8:04	10.74	1.503	1.06	0.57	7.03	-2.0	501.7	3.70		
		8:07	10.73	1.502	1.06	0.55	7.03	-6.5	346.4	3.70		
		8:13	10.61	1.507	1.07	0.47	7.05	-15.9	164.6	3.70		
		8:16	10.62	1.511	1.07	0.45	6.98	-16.2	117.4	3.70		
		8:19	10.60	1.511	1.07	0.42	6.98	-19.5	95.4	3.70		
		8:23	10.61	1.517	1.08	0.41	7.00	-23.2	68.6	3.70		
		8:26	10.54	1.519	1.08	0.40	7.01	-26.2	56.8	3.70		
		8:30	10.55	1.521	1.08	0.39	7.02	-29.2	49.4	3.70		
		8:33	10.57	1.521	1.08	0.41	7.04	-34.0	45.1	3.70		
		8:36	10.55	1.522	1.08	0.39	7.04	-25.4	42.2	3.70		
MW-2	1/31/2014	11:41	8.20	1.290	0.97	2.95	7.70	88.5	1268.4	3.80	16.0	Purged 16 liters at 2 cycles per minute. Water started turbid brown and took a long time to clear. Sample water was clear with a blocky sheen and no odor.
		11:45	9.63	1.332	0.96	0.78	7.37	55.6	1398.5	4.20		
		11:49	10.22	1.354	0.97	0.54	7.31	38.2	1445.3	4.40		
		11:53	10.25	1.355	0.96	0.48	7.27	27.1	1442.1	4.32		
		11:57	10.53	1.361	0.96	0.54	7.29	35.2	1442.1	4.25		
		12:00	10.54	1.364	0.96	0.52	7.23	25.4	1442.2	4.23		
		12:05	10.72	1.368	0.96	0.45	7.23	10.3	1400.2	4.23		
		12:10	10.82	1.371	0.96	0.39	7.22	2.4	1032.5	4.23		
		12:15	10.83	1.370	0.96	0.38	7.20	-2.7	669.6	4.23		
		12:20	10.82	1.369	0.96	0.38	7.18	-6.7	412.9	4.23		
		12:25	10.82	1.368	0.96	0.39	7.17	-9.2	278.5	4.23		
		12:30	10.79	1.365	0.96	0.40	7.14	-10.5	175.8	4.23		
		12:35	10.82	1.363	0.95	0.40	7.13	-12.8	131.9	4.23		
		12:40	10.84	1.361	0.95	0.40	7.14	-15.3	108.5	4.23		
12:45	10.93	1.363	0.95	0.39	7.14	-17.7	83.4	4.23				
12:50	11.00	1.366	0.95	0.38	7.13	-18.5	72.9	4.23				
12:55	11.03	1.367	0.95	0.38	7.13	-19.9	48.7	4.23				
MW-3	1/31/2014	15:21	7.04	0.811	0.62	2.77	7.48	108.0	901.0	4.52	12.0	Purged 12 liters at 2 cycles per minute. Water started cloudy and cleared fairly quickly. Sample water was slightly cloudy with no sheen or odor.
		15:24	7.67	0.812	0.61	1.06	7.08	96.8	518.4	4.72		
		15:28	7.85	0.817	0.61	0.76	6.85	91.6	344.3	4.83		
		15:31	7.98	0.825	0.61	0.65	6.72	90.6	278.9	4.90		
		15:34	8.12	0.831	0.61	0.56	6.66	89.2	190.1	4.99		
		15:39	8.04	0.831	0.62	0.51	6.61	87.0	158.5	4.85		
		15:44	8.19	0.834	0.61	0.47	6.66	80.8	126.0	4.85		
		15:49	8.32	0.835	0.61	0.44	6.63	79.3	94.7	4.85		
		15:53	8.35	0.835	0.61	0.42	6.62	78.1	74.1	4.85		
		15:58	8.44	0.836	0.61	0.41	6.61	77.5	66.3	4.85		
		16:03	8.51	0.836	0.61	0.42	6.61	76.6	63.5	4.85		
16:08	8.57	0.836	0.61	0.41	6.60	75.3	49.3	4.85				
MW-4	1/31/2014	16:38	5.18	0.865	0.70	4.22	7.22	132.3	1004.3	5.05	14.0	Purged 14 liters at 2 cycles per minute. Water started slightly cloudy and cleared fairly quickly. Sample water was slightly cloudy with no sheen or odor. Sample taken prior to reaching less than 50 NTUs due to running out of daylight.
		16:41	6.16	0.907	0.71	1.07	7.05	107.7	511.1	5.60		
		16:45	6.03	0.906	0.71	0.71	7.03	87.3	429.8	5.65		
		16:49	5.98	0.909	0.72	0.60	6.98	74.1	394.9	5.65		
		16:54	6.10	0.918	0.72	0.55	6.96	53.7	336.6	5.65		
		16:59	6.17	0.929	0.73	0.58	6.97	54.5	279.8	5.65		
		17:04	6.20	0.934	0.73	0.62	6.93	45.7	224.6	5.65		
		17:09	6.21	0.938	0.74	0.49	7.02	33.8	212.9	5.65		
		17:13	6.19	0.943	0.74	0.43	7.01	27.7	171.4	5.65		
		17:18	6.25	0.948	0.74	0.40	6.98	23.5	148.9	5.65		
		17:23	6.25	0.952	0.75	0.39	6.97	20.3	133.4	5.65		
		17:28	6.23	0.954	0.75	0.37	6.95	16.6	146.3	5.65		
		17:33	6.24	0.956	0.75	0.37	6.95	14.1	121.9	5.65		
		17:37	6.26	0.957	0.75	0.36	6.96	12.7	114.7	5.65		

Field parameters collected during purging using a YSI 6920 with flow thru cell and 2-inch bladder pump.

Field parameters recorded after every liter of purge.



Table 2: (Page 2 of 2) Groundwater Field Parameter Data, Celi Drive BCP Site, Syracuse, NY.

Well I.D.	Date	Time	Temp (°C)	Conductivity (mmhos/cm)	Salinity (%)	Dissolved Oxygen (mg/L)	pH (units)	ORP (mV)	Turbidity (NTU)	DTW (feet)	Amount Purged (liters)	Comments
MW-5	1/31/2014	13:34	7.80	1.540	1.18	3.92	7.72	106.5	1420.8	4.38	22.0	Purged 22 liters at 3 cycles per minute. Water started turbid brown and cleared slowly. Sample water was slightly cloudy with no sheen or odor. Sample taken prior to reaching less than 50 NTUs due to minimal improvement in water clarity.
		13:37	9.19	1.692	1.26	1.12	7.35	86.6	1427.2	4.60		
		13:40	9.21	1.681	1.24	0.92	7.29	74.9	1422.4	4.65		
		13:43	9.08	1.675	1.24	0.89	7.20	66.3	1188.4	4.65		
		13:46	9.09	1.675	1.24	0.85	7.16	60.0	1138.7	4.65		
		13:49	9.11	1.685	1.25	0.87	7.12	54.8	1356.4	4.65		
		13:53	9.17	1.702	1.26	0.82	7.11	48.2	1350.2	4.65		
		13:55	9.11	1.708	1.27	0.88	7.12	44.1	1204.2	4.65		
		13:58	8.97	1.704	1.27	1.02	7.23	47.6	1171.3	4.65		
		14:00	8.86	1.703	1.27	1.19	7.09	48.0	1081.1	4.65		
		14:03	8.85	1.708	1.28	1.05	7.08	43.8	950.0	4.65		
		14:07	8.85	1.705	1.28	1.03	7.08	38.5	755.2	4.65		
		14:11	8.95	1.726	1.29	0.95	7.09	34.3	636.4	4.65		
		14:14	8.91	1.711	1.28	0.97	7.11	29.8	545.3	4.65		
		14:17	8.88	1.710	1.28	0.97	7.11	27.7	494.4	4.65		
		14:20	8.99	1.718	1.28	0.91	7.11	25.2	377.4	4.65		
		14:24	9.02	1.723	1.28	0.94	7.12	22.2	333.8	4.65		
		14:27	9.06	1.725	1.28	0.91	7.12	21.0	304.7	4.65		
		14:30	9.00	1.724	1.29	0.94	7.12	19.4	243.0	4.65		
		14:34	9.07	1.729	1.29	0.90	7.12	18.1	211.7	4.65		
14:37	9.05	1.730	1.29	0.88	7.12	17.1	104.5	4.65				
14:41	9.05	1.728	1.29	0.88	7.11	17.0	150.3	4.65				
MW-6	1/31/2014	10:34	8.30	1.839	1.40	3.31	7.77	76.0	232.6	3.36	10.0	Purged 10 liters at 3 cycles per minute. Water started slightly yellowish brown and cleared quickly. Sample water was clear with no sheen or odor.
		10:37	9.69	1.952	1.44	1.06	7.48	25.8	195.4	3.45		
		10:40	9.45	1.948	1.44	0.72	7.38	2.7	104.8	3.47		
		10:43	9.44	1.948	1.44	0.58	7.34	-10.6	94.7	3.50		
		10:46	9.48	1.960	1.45	0.52	7.31	-18.9	70.8	3.50		
		10:48	9.51	1.971	1.46	0.48	7.29	-25.2	60.3	3.50		
		10:51	9.56	1.991	1.48	0.45	7.27	-30.1	50.4	3.52		
		10:55	9.63	2.001	1.48	0.44	7.27	-35.1	46.9	3.52		
		10:58	9.70	2.012	1.48	0.42	7.25	-38.3	36.8	3.52		
		11:01	9.70	2.017	1.49	0.41	7.23	-39.8	32.1	3.52		
		11:04	9.72	2.027	1.49	0.38	7.21	-42.0	29.5	3.52		
MW-7	1/31/2014	9:12	8.29	1.627	1.23	2.92	7.44	56.6	842.7	3.52	13.0	Purged 13 liters at 3 cycles per minute. Water started cloudy brown with little sediment and cleared quickly. Sample water was clear with no sheen or odor.
		9:16	9.40	1.708	1.26	0.95	7.27	-1.4	419.0	3.72		
		9:19	8.86	1.683	1.26	0.68	7.27	-19.5	224.4	3.72		
		9:23	8.86	1.687	1.26	0.56	7.24	-33.4	169.0	3.65		
		9:26	8.93	1.659	1.24	0.56	7.24	-39.4	122.2	3.75		
		9:29	8.95	1.638	1.22	0.49	7.24	-43.0	102.2	3.75		
		9:32	8.97	1.625	1.21	0.46	7.23	-47.5	92.6	3.75		
		9:35	9.10	1.610	1.19	0.43	7.23	-50.6	82.3	3.75		
		9:38	9.10	1.599	1.18	0.41	7.23	-52.9	74.4	3.75		
		9:41	9.12	1.588	1.18	0.40	7.23	-55.3	62.8	3.75		
		9:44	9.15	1.580	1.17	0.38	7.23	-57.0	54.0	3.75		
		9:48	9.19	1.576	1.16	0.38	7.23	-58.6	48.1	3.75		
		9:51	9.19	1.568	1.16	0.36	7.23	-59.9	48.9	3.75		
9:54	9.21	1.564	1.15	0.36	7.22	-61.2	41.6	3.75				
MW-8	1/31/2014	NM	NM	NM	NM	NM	NM	NM	NM	NM	-	Well could not be located to be sampled.

Field parameters collected during purging using a YSI 6920 with flow thru cell and 2-inch bladder pump.

Field parameters recorded after every liter of purge.

NM - Not Measured



Table 3: (Page 1 of 2) Summary of Groundwater Laboratory Analytical Results. Celi Drive BCP Site, Syracuse, NY.

Analyte	GW Std (ug/L)	Sample Identification					D.L.
		MW-1					
Date Sampled		Aug-05*	Mar-10*	Jan-14			
<b>Metals by EPA Method 6010C</b>							
Total Chromium	50	U	U	2.3	J		1
Copper	200	U	U	4.4	J^B		1.6
Nickel	100	U	1.4	J	3.8	J	1.3
Zinc	2,000 (G)	U	9.4	J	7.7	JB	1.5
<b>Hexavalent Chromium by EPA Method 7196A</b>							
Hexavalent Chromium	50	11		U		U	5
<b>Cyanide by EPA Method 9012B</b>							
Cyanide	200	U		U		U	5

Analyte	GW Std (ug/L)	Sample Identification					D.L.
		MW-2					
Date Sampled		Aug-05*	Mar-10*	Jan-14			
<b>Metals by EPA Method 6010C</b>							
Total Chromium	50	U	2.4	J	3.7	J	1
Copper	200	3.6		U	4.1	JB	1.6
Nickel	100	5.9	8.4	J	7.8	J	1.3
Zinc	2,000 (G)	U	10.4	J	6.4	JB	1.5
<b>Hexavalent Chromium by EPA Method 7196A</b>							
Hexavalent Chromium	50	9		U		U	5
<b>Cyanide by EPA Method 9012B</b>							
Cyanide	200	U	3.56	J		U	5

Analyte	GW Std (ug/L)	Sample Identification					D.L.
		MW-3					
Date Sampled		Aug-05*	Mar-10*	Jan-14			
<b>Metals by EPA Method 6010C</b>							
Total Chromium	50	U	U	5.1			1
Copper	200	U	4.1	J	10	B	1.6
Nickel	100	4.7		<b>102</b>	<b>120</b>		1.3
Zinc	2,000 (G)	U	11.8	J	12	B	1.5
<b>Hexavalent Chromium by EPA Method 7196A</b>							
Hexavalent Chromium	50	14		U		U	5
<b>Cyanide by EPA Method 9012B</b>							
Cyanide	200	U	3.71	J		UJ	5

All values reported as ug/L

GW Std - Class GA Groundwater Quality Standard or Guidance Value from New York State Department of Environmental Conservation (NYSDEC) Division of Water Technical and Operational Guidance Series (June 1998).

(G) - Guidance value

\* - Historic samples taken by ERM

U - Analyzed for but Not Detected

J - Indicates an estimated value

B - Compound was found in the blank and sample

^ - Instrument related QC exceeds the control limits

NS - Not sampled because well could not be located

D.L. - Laboratory Detection Limit

**Bold and boxed results indicate an exceedance of Groundwater Standards**



Table 3: (Page 2 of 2) Summary of Groundwater Laboratory Analytical Results. Celi Drive BCP Site, Syracuse, NY.

Analyte	GW Std (ug/L)	Sample Identification							
		MW-4				MW-5			
Date Sampled		Mar-10*		Jan-14		Mar-10*		Jan-14	
<b>Metals by EPA Method 6010C</b>									
Total Chromium	50	10	29		D.L.	U	10		D.L.
Copper	200	22.6	93	B	1.6	U	11	B	1.6
Nickel	100	<b>237</b>	<b>340</b>		1.3	3.1	J	12	1.3
Zinc	2,000 (G)	22	23	B	1.5	11.9	J	18	B 1.5
<b>Hexavalent Chromium by EPA Method 7196A</b>									
Hexavalent Chromium	50		U	U	5	10	J		U 5
<b>Cyanide by EPA Method 9012B</b>									
Cyanide	200		U	U	5		U		U 5

Analyte	GW Std (ug/L)	Sample Identification							
		MW-6				MW-7			
Date Sampled		Mar-10*		Jan-14		Mar-10*		Jan-14	
<b>Metals by EPA Method 6010C</b>									
Total Chromium	50		U	2.0	J 1	D.L.	U	3.1	J 1
Copper	200		U	3.4	JB 1.6		U	5.7	JB 1.6
Nickel	100		10	3.9	J 1.3		1.8	J 4.5	J 1.3
Zinc	2,000 (G)		11.4	J 7.0	JB 1.5		13.8	J 11	B 1.5
<b>Hexavalent Chromium by EPA Method 7196A</b>									
Hexavalent Chromium	50		U		U 5		U		UJ 5
<b>Cyanide by EPA Method 9012B</b>									
Cyanide	200		U		U 5		7.77		U 5

Analyte	GW Std (ug/L)	Sample Identification							
		MW-8				Duplicate			
Date Sampled		Mar-10*		Jan-14		Aug-05* (MW-1)		Jan-14 (MW-3)	
<b>Metals by EPA Method 6010C</b>									
Total Chromium	50		U	NS	D.L.		U	4.7	1 8.16%
Copper	200		U	NS			U	9.6	JB 1.6 4.08%
Nickel	100		4.2	J	NS		U	<b>120</b>	1.3 0.00%
Zinc	2,000 (G)		14.5		NS		U	9.8	JB 1.5 20.18%
<b>Hexavalent Chromium by EPA Method 7196A</b>									
Hexavalent Chromium	50		U	NS			10		UJ 5 N/A
<b>Cyanide by EPA Method 9012B</b>									
Cyanide	200		4.1	J	NS		U		U 5 N/A

All values reported as ug/L

GW Std - Class GA Groundwater Quality Standard or Guidance Value from New York State Department of Environmental Conservation (NYSDEC) Division of Water Technical and Operational Guidance Series (June 1998).

(G) - Guidance value

\* - Historic samples taken by ERM

U - Analyzed for but Not Detected

J - Indicates an estimated value

B - Compound was found in the blank and sample

^ - Instrument related QC exceeds the control limits

NS - Not sampled because well could not be located



D.L. - Laboratory Detection Limit

RPD - Relative Percent Difference between sample and blind field duplicate

**Bold and boxed results indicate an exceedance of Groundwater Standards**



Attachment B-8 – Excerpts from Construction  
Completion Report – AOC-3 and AOC-4, GHD,  
January 2016



NOTES:  
 1. Aerial photographs are low resolution color orthorectified imagery from the US Geological Survey website (<http://earthexplorer.usgs.gov>)






GSP Holdings, Inc.  
 Construction Completion Report  
 Celi Drive BCP Site (BCP Site #C734108)

Site Layout

Job Number | 37-11082  
 Revision | A  
 Date | 02.03.2015

Figure 2



**NOTES:**

- 1) Sample locations surveyed by January 14, 2015 (see Plans Land Surveying, P.C. 10-23-2014, 10-30-2014, and 11-02-2014)
- 2) Edge of water surveyed by January 14, 2015 (see Plans Land Surveying, P.C. 10-23-2014, 10-30-2014, and 11-02-2014)
- 3) Edge of water post-excavation surveyed by January 14, 2015 (see Plans Land Surveying, P.C. 10-23-2014, 10-30-2014, and 11-02-2014)
- 4) Aerial photographs are 10-foot resolution color orthorectified by the USGS National Geospatial Survey website (<http://earthexplorer.usgs.gov>)




GSP Holdings, Inc.  
 Construction Completion Report  
 Celi Drive BCP Site (BCP Site #C734108)

**AOC-4 Sample Locations**

Job Number | 37-11082  
 Revision | A  
 Date | 01.28.2015

**Figure 3**




LE END

SW-1A Excavation End-Point Soil Sample Location and ID (Surveyed)

Edible Water Post-Excavation (Surveyed)

Analyte	Concentration
Sample ID	Concentration

- Indicates an estimated value  
 ND - Non-Detect at the laboratory detection limits  
 - Selected by the Data Availability Survey report






- NOTES:
- 1) Only analytical results of end-point soil samples are shown here! For a complete survey of soil sample analytical results refer to tables in the Construction Completion Report.
  - 2) All analytical results reported as milligrams per liter (mg/L), parts per million (ppm).
  - 3) Total Chromium Soil Cleanup Objectives (SCOs) are 30, 30, and 41 mg/L for unrestricted use, residential use, and Protection of Ecological Resources, respectively.
  - 4) Hexavalent Chromium SCOs are 1, 22, and 1 mg/L for unrestricted use, residential use, and Protection of Ecological Resources, respectively.
- Sample locations surveyed by January 2015 of the Land Surveying, P.C. 2013-2014, and 2014-2015.  
 Edible water post-excavation surveyed by January 2015 of the Land Surveying, P.C. 2013-2014.  
 Aerial photographs are 10-foot resolution color orthorectified by the U.S. Geological Survey website (<http://earthexplorer.usgs.gov/>).



GSP Holdings, Inc.  
 Construction Completion Report  
 Celi Drive BCP Site (BCP Site #C734108)  
**AOC-4 End-Point Sample Results -  
 Total and Hexavalent Chromium**

Job Number | 37-11082  
 Revision | A  
 Date | 03.16.2015  
**Figure 4**





**NOTES:**

- 1) Only analytical results of end-point soil samples are shown here! For a complete summary of soil sample analytical results refer to tables in the Construction Completion Report.
- 2) All analytical results reported as milligrams per kilogram (mg/kg), parts per million (ppm).
- 3) Total Nickel Soil Cleanup Objectives (SCOs) are 3, 14, and 30 mg/kg for unrestricted use, residential use, and Protection of Ecological Resources, respectively.
- 4) Sample locations surveyed by January 2015: Plans Land Surveying, P.C. 11-23-21 14, 11-30-21 14, and 11-21-21 14.
- 5) End of water post-excavation surveyed by January 2015: Plans Land Surveying, P.C. 11-30-21 14.
- 6) Aerial photographs are 1-foot resolution color orthorectified from the USGS National Aerial Photography Facility (NAIP) website: <http://earthexplorer.usgs.gov/>



GSP Holdings, Inc.  
 Construction Completion Report  
 Celi Drive BCP Site (BCP Site #C734108)  
**AOC-4 End-Point Sample Results -  
 Total Nickel**

Job Number | 37-11082  
 Revision | A  
 Date | 03.16.2015  
**Figure 6**



Table 1 - (Page 1 of 19): Summary of Post-Excavation Soil Sample Laboratory Analytical Results. Celi Drive BCP Site (BCP Site #C734108). Syracuse, NY.

ANALYTE (mg/kg)	SOIL CLEANUP OBJECTIVES			SAMPLE IDENTIFICATION											
	UNRESTRICTED USE	RESIDENTIAL USE	PROTECTION OF ECOLOGICAL RESOURCES	BRIDGE STREET SWALE											
				SW-1A			SW-1B			SW-1C					
Sample Date				5/6/2014			5/6/2014			5/6/2014					
<b>Metals by EPA Method 6010C</b>						D.L.	R.L.			D.L.	R.L.			D.L.	R.L.
Chromium, Total	30	36	41	22	J			14	J			8.9	J		
Copper, Total	50	270	50	49	J			18	J			17	J		
Nickel, Total	30	140	30	24	J			13	J			8.9	J		
<b>Cyanide by EPA Method 9010C</b>															
Cyanide, Total	27	27	NS	U	0.27	1.2		U	0.28	1.2		U	0.24	1	
<b>Chromium by EPA Method 7196A</b>															
Chromium, Hexavalent	1	22	1	U	0.2	0.99		U	0.20	0.99		U	0.18	0.88	

All values reported as mg/kg (parts per million)

Soil Cleanup Objectives from 6 NYCRR Part 375-6.8(b) (December 2006) and Supplemental Soil Cleanup Objectives (October 2010)

U - Analyzed for but not detected above the laboratory reporting limit

J - Estimated value

D.L. - Laboratory Detection Limit

R.L. - Laboratory Reporting Limit

NS - Not Specified

Bold and thick outlined cell indicates analyte exceeds the Unrestricted Use Soil Cleanup Objective

Bold, thick outlined, and shaded cell indicates analyte exceeds the Protection of Ecological Resources and the Unrestricted Use Soil Cleanup Objectives



Table 1 - (Page 2 of 19): Summary of Post-Excavation Soil Sample Laboratory Analytical Results. Celi Drive BCP Site (BCP Site #C734108). Syracuse, NY.

ANALYTE (mg/kg)	SOIL CLEANUP OBJECTIVES			SAMPLE IDENTIFICATION								
	UNRESTRICTED USE	RESIDENTIAL USE	PROTECTION OF ECOLOGICAL RESOURCES	BRIDGE STREET SWALE								
				SW-2A		SW-2B		SW-2B-1				
Sample Date				5/6/2014		5/6/2014		5/23/2014				
<b>Metals by EPA Method 6010C</b>					D.L.	R.L.		D.L.	R.L.			
Chromium, Total	30	36	41	18	J		<b>410 *</b>		12			
Copper, Total	50	270	50	39	J		<b>1,400 *</b>		19			
Nickel, Total	30	140	30	20	J		<b>570 *</b>		14			
<b>Cyanide by EPA Method 9010C</b>												
Cyanide, Total	27	27	NS	0.42	J	0.28	1.2	2.0	U	0.27	1.2	
<b>Chromium by EPA Method 7196A</b>												
Chromium, Hexavalent	1	22	1	U	0.2	1	U	0.34	1.7	UJ	0.2	0.98

ANALYTE (mg/kg)	SOIL CLEANUP OBJECTIVES			SAMPLE IDENTIFICATION					
	UNRESTRICTED USE	RESIDENTIAL USE	PROTECTION OF ECOLOGICAL RESOURCES	BRIDGE STREET SWALE					
				SW-2C		SW-2C-1			
Sample Date				5/6/2014		5/23/2014			
<b>Metals by EPA Method 6010C</b>					D.L.	R.L.		D.L.	R.L.
Chromium, Total	30	36	41	<b>730 *</b>			14		
Copper, Total	50	270	50	<b>1,200 *</b>			21		
Nickel, Total	30	140	30	<b>590 *</b>			17		
<b>Cyanide by EPA Method 9010C</b>									
Cyanide, Total	27	27	NS	2.3			U	0.27	1.2
<b>Chromium by EPA Method 7196A</b>									
Chromium, Hexavalent	1	22	1	U	0.36	1.8	UJ	0.20	0.98

All values reported as mg/kg (parts per million)

Soil Cleanup Objectives from 6 NYCRR Part 375-6.8(b) (December 2006) and Supplemental Soil Cleanup Objectives (October 2010)

U - Analyzed for but not detected above the laboratory reporting limit

J - Estimated value

D.L. - Laboratory Detection Limit

R.L. - Laboratory Reporting Limit

NS - Not Specified

Bold and thick outlined cell indicates analyte exceeds the Unrestricted Use Soil Cleanup Objective

Bold, thick outlined, and shaded cell indicates analyte exceeds the Protection of Ecological Resources and the Unrestricted Use Soil Cleanup Objectives

Bold, thick outlined, shaded, and asterisk cell indicates analyte exceeds the Protection of Ecological Resources, the Unrestricted Use, and the Residential Use Soil Cleanup Objectives





Table 1 - (Page 3 of 19): Summary of Post-Excavation Soil Sample Laboratory Analytical Results. Celi Drive BCP Site (BCP Site #C734108). Syracuse, NY.

ANALYTE (mg/kg)	SOIL CLEANUP OBJECTIVES			SAMPLE IDENTIFICATION								
	UNRESTRICTED USE	RESIDENTIAL USE	PROTECTION OF ECOLOGICAL RESOURCES	BRIDGE STREET SWALE								
				SW-3A		SW-3A-1		SW-3B				
Sample Date				5/7/2014		5/22/2014		5/7/2014				
<b>Metals by EPA Method 6010C</b>					D.L.	R.L.		D.L.	R.L.		D.L.	R.L.
Chromium, Total	30	36	41	12			12			<b>130</b>	*	
Copper, Total	50	270	50	<b>130</b>			29			<b>140</b>		
Nickel, Total	30	140	30	<b>31</b>			14			<b>51</b>		
<b>Cyanide by EPA Method 9010C</b>												
Cyanide, Total	27	27	NS	U	0.7	3	U	0.28	1.2	2.1		
<b>Chromium by EPA Method 7196A</b>												
Chromium, Hexavalent	1	22	1	U	2.4	12	UJ	0.2	1	U	0.33	1.6

ANALYTE (mg/kg)	SOIL CLEANUP OBJECTIVES			SAMPLE IDENTIFICATION					
	UNRESTRICTED USE	RESIDENTIAL USE	PROTECTION OF ECOLOGICAL RESOURCES	BRIDGE STREET SWALE					
				SW-3B-1			SW-3C		
Sample Date				5/22/2014			5/7/2014		
<b>Metals by EPA Method 6010C</b>					D.L.	R.L.		D.L.	R.L.
Chromium, Total	30	36	41	16			5.6	J	
Copper, Total	50	270	50	22			13	J	
Nickel, Total	30	140	30	19			7.8		
<b>Cyanide by EPA Method 9010C</b>									
Cyanide, Total	27	27	NS	U	0.3	1.3	U	0.49	2.1
<b>Chromium by EPA Method 7196A</b>									
Chromium, Hexavalent	1	22	1	UJ	0.21	1	UJ	0.18	0.89

All values reported as mg/kg (parts per million)

Soil Cleanup Objectives from 6 NYCRR Part 375-6.8(b) (December 2006) and Supplemental Soil Cleanup Objectives (October 2010)

U - Analyzed for but not detected above the laboratory reporting limit

J - Estimated value

D.L. - Laboratory Detection Limit

R.L. - Laboratory Reporting Limit

NS - Not Specified

Bold and thick outlined cell indicates analyte exceeds the Unrestricted Use Soil Cleanup Objective

Bold, thick outlined, and shaded cell indicates analyte exceeds the Protection of Ecological Resources and the Unrestricted Use Soil Cleanup Objectives

Bold, thick outlined, shaded, and asterisk cell indicates analyte exceeds the Protection of Ecological Resources, the Unrestricted Use, and the Residential Use Soil Cleanup Objectives



Table 1 - (Page 4 of 19): Summary of Post-Excavation Soil Sample Laboratory Analytical Results. Celi Drive BCP Site (BCP Site #C734108). Syracuse, NY.

ANALYTE (mg/kg)	SOIL CLEANUP OBJECTIVES			SAMPLE IDENTIFICATION					
	UNRESTRICTED USE	RESIDENTIAL USE	PROTECTION OF ECOLOGICAL RESOURCES	BRIDGE STREET SWALE					
				SW-4A		SW-4B		SW-4C	
Sample Date				5/7/2014		5/7/2014		5/7/2014	
<b>Metals by EPA Method 6010C</b>					D.L.	R.L.		D.L.	R.L.
Chromium, Total	30	36	41	14	J		<b>34</b>	J	
Copper, Total	50	270	50	21	J		42	J	
Nickel, Total	30	140	30	22			28		
<b>Cyanide by EPA Method 9010C</b>									
Cyanide, Total	27	27	NS	U	0.54	2.3	U	0.31	1.3
<b>Chromium by EPA Method 7196A</b>									
Chromium, Hexavalent	1	22	1	UJ	0.2	0.98	UJ	0.22	1.1

All values reported as mg/kg (parts per million)

Soil Cleanup Objectives from 6 NYCRR Part 375-6.8(b) (December 2006) and Supplemental Soil Cleanup Objectives (October 2010)

U - Analyzed for but not detected above the laboratory reporting limit

J - Estimated value

D.L. - Laboratory Detection Limit

R.L. - Laboratory Reporting Limit

NS - Not Specified

Bold and thick outlined cell indicates analyte exceeds the Unrestricted Use Soil Cleanup Objective

Bold, thick outlined, and shaded cell indicates analyte exceeds the Protection of Ecological Resources and the Unrestricted Use Soil Cleanup Objectives



Table 1 - (Page 5 of 19): Summary of Post-Excavation Soil Sample Laboratory Analytical Results. Celi Drive BCP Site (BCP Site #C734108). Syracuse, NY.

ANALYTE (mg/kg)	SOIL CLEANUP OBJECTIVES			SAMPLE IDENTIFICATION								
	UNRESTRICTED USE	RESIDENTIAL USE	PROTECTION OF ECOLOGICAL RESOURCES	BRIDGE STREET SWALE								
				SW-5A		SW-5A-1		SW-5A-2				
Sample Date				5/7/2014		5/22/2014		5/28/2014				
<b>Metals by EPA Method 6010C</b>					D.L.	R.L.		D.L.	R.L.		D.L.	R.L.
Chromium, Total	30	36	41	<b>30</b>			19			9.0		
Copper, Total	50	270	50	<b>100</b>			<b>69</b>			16		
Nickel, Total	30	140	30	<b>81</b>			<b>35</b>			12		
<b>Cyanide by EPA Method 9010C</b>												
Cyanide, Total	27	27	NS	U	0.32	1.4	U	0.29	1.2	0.50	J	0.27 1.2
<b>Chromium by EPA Method 7196A</b>												
Chromium, Hexavalent	1	22	1	U	0.24	1.2	U	0.2	1	U	0.19	0.97

ANALYTE (mg/kg)	SOIL CLEANUP OBJECTIVES			SAMPLE IDENTIFICATION					
	UNRESTRICTED USE	RESIDENTIAL USE	PROTECTION OF ECOLOGICAL RESOURCES	BRIDGE STREET SWALE					
				SW-5B		SW-5C			
Sample Date				5/7/2014		5/7/2014			
<b>Metals by EPA Method 6010C</b>					D.L.	R.L.		D.L.	R.L.
Chromium, Total	30	36	41	23	J		19	J	
Copper, Total	50	270	50	30	J		24	J	
Nickel, Total	30	140	30	25			21		
<b>Cyanide by EPA Method 9010C</b>									
Cyanide, Total	27	27	NS	U	0.35	1.5	U	0.29	1.2
<b>Chromium by EPA Method 7196A</b>									
Chromium, Hexavalent	1	22	1	U	0.24	1.2	U	0.21	1

All values reported as mg/kg (parts per million)

Soil Cleanup Objectives from 6 NYCRR Part 375-6.8(b) (December 2006) and Supplemental Soil Cleanup Objectives (October 2010)

U - Analyzed for but not detected above the laboratory reporting limit

J - Estimated value

D.L. - Laboratory Detection Limit

R.L. - Laboratory Reporting Limit

NS - Not Specified

Bold and thick outlined cell indicates analyte exceeds the Unrestricted Use Soil Cleanup Objective

Bold, thick outlined, and shaded cell indicates analyte exceeds the Protection of Ecological Resources and the Unrestricted Use Soil Cleanup Objectives



Table 1 - (Page 6 of 19): Summary of Post-Excavation Soil Sample Laboratory Analytical Results. Celi Drive BCP Site (BCP Site #C734108). Syracuse, NY.

ANALYTE (mg/kg)	SOIL CLEANUP OBJECTIVES			SAMPLE IDENTIFICATION								
	UNRESTRICTED USE	RESIDENTIAL USE	PROTECTION OF ECOLOGICAL RESOURCES	BRIDGE STREET SWALE								
				SW-6A		SW-6A-1		SW-6B				
Sample Date				5/7/2014		5/22/2014		5/7/2014				
<b>Metals by EPA Method 6010C</b>					D.L.	R.L.		D.L.	R.L.		D.L.	R.L.
Chromium, Total	30	36	41	<b>31</b>			15			23	J	
Copper, Total	50	270	50	<b>73</b>			26			22	J	
Nickel, Total	30	140	30	<b>120</b>			23			27		
<b>Cyanide by EPA Method 9010C</b>												
Cyanide, Total	27	27	NS	U	0.32	1.3	U	0.28	1.2	U	0.35	1.5
<b>Chromium by EPA Method 7196A</b>												
Chromium, Hexavalent	1	22	1	U	0.23	1.1	UJ	0.19	0.97	U	0.26	1.3

ANALYTE (mg/kg)	SOIL CLEANUP OBJECTIVES			SAMPLE IDENTIFICATION		
	UNRESTRICTED USE	RESIDENTIAL USE	PROTECTION OF ECOLOGICAL RESOURCES	BRIDGE STREET SWALE		
				SW-6C		
Sample Date				5/7/2014		
<b>Metals by EPA Method 6010C</b>					D.L.	R.L.
Chromium, Total	30	36	41	12	J	
Copper, Total	50	270	50	33	J	
Nickel, Total	30	140	30	27		
<b>Cyanide by EPA Method 9010C</b>						
Cyanide, Total	27	27	NS	U	0.24	1
<b>Chromium by EPA Method 7196A</b>						
Chromium, Hexavalent	1	22	1	U	0.18	0.9

All values reported as mg/kg (parts per million)

Soil Cleanup Objectives from 6 NYCRR Part 375-6.8(b) (December 2006) and Supplemental Soil Cleanup Objectives (October 2010)

U - Analyzed for but not detected above the laboratory reporting limit

J - Estimated value

D.L. - Laboratory Detection Limit

R.L. - Laboratory Reporting Limit

NS - Not Specified

Bold and thick outlined cell indicates analyte exceeds the Unrestricted Use Soil Cleanup Objective

Bold, thick outlined, and shaded cell indicates analyte exceeds the Protection of Ecological Resources and the Unrestricted Use Soil Cleanup Objectives



Table 1 - (Page 7 of 19): Summary of Post-Excavation Soil Sample Laboratory Analytical Results. Celi Drive BCP Site (BCP Site #C734108). Syracuse, NY.

ANALYTE (mg/kg)	SOIL CLEANUP OBJECTIVES			SAMPLE IDENTIFICATION										
	UNRESTRICTED USE	RESIDENTIAL USE	PROTECTION OF ECOLOGICAL RESOURCES	MAIN SWALE										
				SW-7A		SW-7A-1		SW-7B						
Sample Date				5/8/2014		5/23/2014		5/8/2014						
<b>Metals by EPA Method 6010C</b>				D.L.	R.L.	D.L.	R.L.	D.L.	R.L.					
Chromium, Total	30	36	41	<b>36</b>		21		19						
Copper, Total	50	270	50	<b>46</b>		37		21						
Nickel, Total	30	140	30	<b>44</b>		25		20						
<b>Cyanide by EPA Method 9010C</b>														
Cyanide, Total	27	27	NS	U	0.28	1.2	U	0.36	1.5	0.81	J	0.28	1.2	
<b>Chromium by EPA Method 7196A</b>														
Chromium, Hexavalent	1	22	1	0.38	J	0.2	1	UJ	0.25	1.3	0.26	J	0.2	1

ANALYTE (mg/kg)	SOIL CLEANUP OBJECTIVES			SAMPLE IDENTIFICATION						
	UNRESTRICTED USE	RESIDENTIAL USE	PROTECTION OF ECOLOGICAL RESOURCES	MAIN SWALE						
				SW-7C		SW-7C-1				
Sample Date				5/8/2014		5/22/2014				
<b>Metals by EPA Method 6010C</b>				D.L.	R.L.	D.L.	R.L.	D.L.	R.L.	
Chromium, Total	30	36	41	<b>100</b>	*	21		21		
Copper, Total	50	270	50	<b>210</b>		23		23		
Nickel, Total	30	140	30	<b>93</b>		23				
<b>Cyanide by EPA Method 9010C</b>										
Cyanide, Total	27	27	NS	U	0.58	2.5	0.48	J	0.29	1.2
<b>Chromium by EPA Method 7196A</b>										
Chromium, Hexavalent	1	22	1	U	0.41	2.1	0.26	J	0.21	1

All values reported as mg/kg (parts per million)

Soil Cleanup Objectives from 6 NYCRR Part 375-6.8(b) (December 2006) and Supplemental Soil Cleanup Objectives (October 2010)

U - Analyzed for but not detected above the laboratory reporting limit

J - Estimated value

D.L. - Laboratory Detection Limit

R.L. - Laboratory Reporting Limit

NS - Not Specified

Bold and thick outlined cell indicates analyte exceeds the Unrestricted Use Soil Cleanup Objective

Bold, thick outlined, and shaded cell indicates analyte exceeds the Protection of Ecological Resources and the Unrestricted Use Soil Cleanup Objectives

Bold, thick outlined, shaded, and asterisk cell indicates analyte exceeds the Protection of Ecological Resources, the Unrestricted Use, and the Residential Use Soil Cleanup Objectives



Table 1 - (Page 8 of 19): Summary of Post-Excavation Soil Sample Laboratory Analytical Results. Celi Drive BCP Site (BCP Site #C734108). Syracuse, NY.

ANALYTE (mg/kg)	SOIL CLEANUP OBJECTIVES			SAMPLE IDENTIFICATION										
	UNRESTRICTED USE	RESIDENTIAL USE	PROTECTION OF ECOLOGICAL RESOURCES	MAIN SWALE										
				SW-8A		SW-8B		SW-8C						
Sample Date				5/8/2014		5/8/2014		5/8/2014						
<b>Metals by EPA Method 6010C</b>					D.L.	R.L.		D.L.	R.L.		D.L.	R.L.		
Chromium, Total	30	36	41	14			5.9			16				
Copper, Total	50	270	50	18			11			<b>110</b>				
Nickel, Total	30	140	30	17			8.0	J	2.1	13	23			
<b>Cyanide by EPA Method 9010C</b>														
Cyanide, Total	27	27	NS	U	0.28	1.2	U	0.3	1.3	U	0.66	2.8		
<b>Chromium by EPA Method 7196A</b>														
Chromium, Hexavalent	1	22	1	0.31	J	0.2	1	0.28	J	0.22	1.1	U	0.47	2.4

ANALYTE (mg/kg)	SOIL CLEANUP OBJECTIVES			SAMPLE IDENTIFICATION		
	UNRESTRICTED USE	RESIDENTIAL USE	PROTECTION OF ECOLOGICAL RESOURCES	MAIN SWALE		
				SW-8C-1		
Sample Date				5/22/2014		
<b>Metals by EPA Method 6010C</b>					D.L.	R.L.
Chromium, Total	30	36	41	21		
Copper, Total	50	270	50	11		
Nickel, Total	30	140	30	24		
<b>Cyanide by EPA Method 9010C</b>						
Cyanide, Total	27	27	NS	U	0.31	1.3
<b>Chromium by EPA Method 7196A</b>						
Chromium, Hexavalent	1	22	1	UJ	0.22	1.1

All values reported as mg/kg (parts per million)

Soil Cleanup Objectives from 6 NYCRR Part 375-6.8(b) (December 2006) and Supplemental Soil Cleanup Objectives (October 2010)

U - Analyzed for but not detected above the laboratory reporting limit

J - Estimated value

D.L. - Laboratory Detection Limit

R.L. - Laboratory Reporting Limit

NS - Not Specified

Bold and thick outlined cell indicates analyte exceeds the Unrestricted Use Soil Cleanup Objective

Bold, thick outlined, and shaded cell indicates analyte exceeds the Protection of Ecological Resources and the Unrestricted Use Soil Cleanup Objectives



Table 1 - (Page 9 of 19): Summary of Post-Excavation Soil Sample Laboratory Analytical Results. Celi Drive BCP Site (BCP Site #C734108). Syracuse, NY.

ANALYTE (mg/kg)	SOIL CLEANUP OBJECTIVES			SAMPLE IDENTIFICATION								
	UNRESTRICTED USE	RESIDENTIAL USE	PROTECTION OF ECOLOGICAL RESOURCES	MAIN SWALE								
				SW-9A		SW-9A-1		SW-9B				
Sample Date				5/20/2014		5/29/2014		5/20/2014				
<b>Metals by EPA Method 6010C</b>				D.L.	R.L.	D.L.	R.L.	D.L.	R.L.			
Chromium, Total	30	36	41	<b>68</b>	*	15	J	15	J			
Copper, Total	50	270	50	<b>160</b>		19	J	16	J			
Nickel, Total	30	140	30	<b>80</b>		19		17				
<b>Cyanide by EPA Method 9010C</b>												
Cyanide, Total	27	27	NS	U	0.31	1.3	U	0.26	1.1	UJ	0.27	1.2
<b>Chromium by EPA Method 7196A</b>												
Chromium, Hexavalent	1	22	1	U	0.23	1.1	U	0.19	0.97	UJ	0.2	1

ANALYTE (mg/kg)	SOIL CLEANUP OBJECTIVES			SAMPLE IDENTIFICATION						
	UNRESTRICTED USE	RESIDENTIAL USE	PROTECTION OF ECOLOGICAL RESOURCES	MAIN SWALE						
				SW-9C		SW-9C-1				
Sample Date				5/20/2014		5/29/2014				
<b>Metals by EPA Method 6010C</b>				D.L.	R.L.	D.L.	R.L.	D.L.	R.L.	
Chromium, Total	30	36	41	<b>50</b>	*	13	J			
Copper, Total	50	270	50	<b>63</b>		11	J			
Nickel, Total	30	140	30	<b>43</b>		8.5				
<b>Cyanide by EPA Method 9010C</b>										
Cyanide, Total	27	27	NS	0.55	J	0.26	1.1	U	0.52	2.2
<b>Chromium by EPA Method 7196A</b>										
Chromium, Hexavalent	1	22	1	U	0.19	0.96	0.28	J	0.18	0.9

All values reported as mg/kg (parts per million)

Soil Cleanup Objectives from 6 NYCRR Part 375-6.8(b) (December 2006) and Supplemental Soil Cleanup Objectives (October 2010)

U - Analyzed for but not detected above the laboratory reporting limit

J - Estimated value

D.L. - Laboratory Detection Limit

R.L. - Laboratory Reporting Limit

NS - Not Specified

Bold and thick outlined cell indicates analyte exceeds the Unrestricted Use Soil Cleanup Objective

Bold, thick outlined, and shaded cell indicates analyte exceeds the Protection of Ecological Resources and the Unrestricted Use Soil Cleanup Objectives

Bold, thick outlined, shaded, and asterisk cell indicates analyte exceeds the Protection of Ecological Resources, the Unrestricted Use, and the Residential Use Soil Cleanup Objectives



Table 1 - (Page 10 of 19): Summary of Post-Excavation Soil Sample Laboratory Analytical Results. Celi Drive BCP Site (BCP Site #C734108), Syracuse, NY.

ANALYTE (mg/kg)	SOIL CLEANUP OBJECTIVES			SAMPLE IDENTIFICATION										
	UNRESTRICTED USE	RESIDENTIAL USE	PROTECTION OF ECOLOGICAL RESOURCES	MAIN SWALE										
				SW-10A		SW-10A-1			SW-10B					
Sample Date				5/9/2014		5/19/2014			5/9/2014					
<b>Metals by EPA Method 6010C</b>					D.L.	R.L.		D.L.	R.L.		D.L.	R.L.		
Chromium, Total	30	36	41	11			16	J		18	J			
Copper, Total	50	270	50	<b>66</b>			20	J		36	J			
Nickel, Total	30	140	30	17			14			18				
<b>Cyanide by EPA Method 9010C</b>														
Cyanide, Total	27	27	NS	U	0.59	2.5	0.37	J	0.32	1.3	0.47	J	0.37	1.6
<b>Chromium by EPA Method 7196A</b>														
Chromium, Hexavalent	1	22	1	0.92	J	0.42	2.1	UJ	0.22	1.1	0.42	J	0.27	1.3

ANALYTE (mg/kg)	SOIL CLEANUP OBJECTIVES			SAMPLE IDENTIFICATION								
	UNRESTRICTED USE	RESIDENTIAL USE	PROTECTION OF ECOLOGICAL RESOURCES	MAIN SWALE								
				SW-10C		SW-10C-1						
Sample Date				5/9/2014		5/19/2014						
<b>Metals by EPA Method 6010C</b>					D.L.	R.L.		D.L.	R.L.			
Chromium, Total	30	36	41	24			12	J				
Copper, Total	50	270	50	<b>82</b>			12	J				
Nickel, Total	30	140	30	<b>50</b>			10					
<b>Cyanide by EPA Method 9010C</b>												
Cyanide, Total	27	27	NS	U	0.51	2.2	U	0.25	1			
<b>Chromium by EPA Method 7196A</b>												
Chromium, Hexavalent	1	22	1	U	0.36	1.8	UJ	0.17	0.87			

All values reported as mg/kg (parts per million)

Soil Cleanup Objectives from 6 NYCRR Part 375-6.8(b) (December 2006) and Supplemental Soil Cleanup Objectives (October 2010)

U - Analyzed for but not detected above the laboratory reporting limit

J - Estimated value

D.L. - Laboratory Detection Limit

R.L. - Laboratory Reporting Limit

NS - Not Specified

Bold and thick outlined cell indicates analyte exceeds the Unrestricted Use Soil Cleanup Objective

Bold, thick outlined, and shaded cell indicates analyte exceeds the Protection of Ecological Resources and the Unrestricted Use Soil Cleanup Objectives





Table 1 - (Page 11 of 19): Summary of Post-Excavation Soil Sample Laboratory Analytical Results. Celi Drive BCP Site (BCP Site #C734108), Syracuse, NY.

ANALYTE (mg/kg)	SOIL CLEANUP OBJECTIVES			SAMPLE IDENTIFICATION											
	UNRESTRICTED USE	RESIDENTIAL USE	PROTECTION OF ECOLOGICAL RESOURCES	MAIN SWALE											
				SW-11A			SW-11A-1			SW-11B					
Sample Date				5/9/2014			5/23/2014			5/9/2014					
<b>Metals by EPA Method 6010C</b>					D.L.	R.L.		D.L.	R.L.		D.L.	R.L.			
Chromium, Total	30	36	41	18			7.4			<b>40</b>	*				
Copper, Total	50	270	50	<b>110</b>			10			<b>96</b>					
Nickel, Total	30	140	30	<b>230</b>	*		10			<b>35</b>					
<b>Cyanide by EPA Method 9010C</b>															
Cyanide, Total	27	27	NS	0.54	J	0.47	2	0.26	J	0.26	1.1	1.4	J	0.4	1.7
<b>Chromium by EPA Method 7196A</b>															
Chromium, Hexavalent	1	22	1	0.76	J	0.34	1.7	UJ	0.19	0.94	0.77	J	0.3	1.5	

ANALYTE (mg/kg)	SOIL CLEANUP OBJECTIVES			SAMPLE IDENTIFICATION									
	UNRESTRICTED USE	RESIDENTIAL USE	PROTECTION OF ECOLOGICAL RESOURCES	MAIN SWALE									
				SW-11B-1				SW-11C					
Sample Date				5/23/2014				5/9/2014					
<b>Metals by EPA Method 6010C</b>					D.L.	R.L.		D.L.	R.L.				
Chromium, Total	30	36	41	12			18	J					
Copper, Total	50	270	50	11			19	J					
Nickel, Total	30	140	30	14			20						
<b>Cyanide by EPA Method 9010C</b>													
Cyanide, Total	27	27	NS	U	0.32	1.4	U	0.27	1.2				
<b>Chromium by EPA Method 7196A</b>													
Chromium, Hexavalent	1	22	1	UJ	0.23	1.1	0.46	J	0.2	1			

All values reported as mg/kg (parts per million)

Soil Cleanup Objectives from 6 NYCRR Part 375-6.8(b) (December 2006) and Supplemental Soil Cleanup Objectives (October 2010)

U - Analyzed for but not detected above the laboratory reporting limit

J - Estimated value

D.L. - Laboratory Detection Limit

R.L. - Laboratory Reporting Limit

NS - Not Specified

Bold and thick outlined cell indicates analyte exceeds the Unrestricted Use Soil Cleanup Objective

Bold, thick outlined, and shaded cell indicates analyte exceeds the Protection of Ecological Resources and the Unrestricted Use Soil Cleanup Objectives

Bold, thick outlined, and asterisk cell indicates analyte exceeds the Unrestricted Use and the Residential Use Soil Cleanup Objectives



Table 1 - (Page 12 of 19): Summary of Post-Excavation Soil Sample Laboratory Analytical Results. Celi Drive BCP Site (BCP Site #C734108). Syracuse, NY.

ANALYTE (mg/kg)	SOIL CLEANUP OBJECTIVES			SAMPLE IDENTIFICATION								
	UNRESTRICTED USE	RESIDENTIAL USE	PROTECTION OF ECOLOGICAL RESOURCES	BRIDGE STREET SWALE								
				SW-12A			SW-12B			SW-12C		
Sample Date				5/22/2014			5/22/2014			5/22/2014		
<b>Metals by EPA Method 6010C</b>					D.L.	R.L.		D.L.	R.L.		D.L.	R.L.
Chromium, Total	30	36	41	11			12			8.5		
Copper, Total	50	270	50	20			18			18		
Nickel, Total	30	140	30	19			12			9.1		
<b>Cyanide by EPA Method 9010C</b>												
Cyanide, Total	27	27	NS	U	0.25	1.1	U	0.3	1.3	U	0.24	1
<b>Chromium by EPA Method 7196A</b>												
Chromium, Hexavalent	1	22	1	UJ	0.18	0.91	UJ	0.23	1.1	UJ	0.18	0.9

All values reported as mg/kg (parts per million)

Soil Cleanup Objectives from 6 NYCRR Part 375-6.8(b) (December 2006) and Supplemental Soil Cleanup Objectives (October 2010)

U - Analyzed for but not detected above the laboratory reporting limit

J - Estimated value

D.L. - Laboratory Detection Limit

R.L. - Laboratory Reporting Limit

NS - Not Specified

Bold and thick outlined cell indicates analyte exceeds the Unrestricted Use Soil Cleanup Objective

Bold, thick outlined, and shaded cell indicates analyte exceeds the Protection of Ecological Resources and the Unrestricted Use Soil Cleanup Objectives



Table 1 - (Page 13 of 19): Summary of Post-Excavation Soil Sample Laboratory Analytical Results. Celi Drive BCP Site (BCP Site #C734108). Syracuse, NY.

ANALYTE (mg/kg)	SOIL CLEANUP OBJECTIVES			SAMPLE IDENTIFICATION										
	UNRESTRICTED USE	RESIDENTIAL USE	PROTECTION OF ECOLOGICAL RESOURCES	BRIDGE STREET SWALE										
				SW-13A		SW-13A-1		SW-13B						
Sample Date				5/22/2014		5/29/2014		5/22/2014						
<b>Metals by EPA Method 6010C</b>					D.L.	R.L.		D.L.	R.L.		D.L.	R.L.		
Chromium, Total	30	36	41	21			9.8	J			9.4			
Copper, Total	50	270	50	43			8.3	J			20			
Nickel, Total	30	140	30	<b>37</b>			10	J			16			
<b>Cyanide by EPA Method 9010C</b>														
Cyanide, Total	27	27	NS	U	0.32	1.4	U	0.25	1.1	U	0.27	1.2		
<b>Chromium by EPA Method 7196A</b>														
Chromium, Hexavalent	1	22	1	0.29	J	0.23	1.1	UR	0.49	0.95	0.24	J	0.19	0.97

ANALYTE (mg/kg)	SOIL CLEANUP OBJECTIVES			SAMPLE IDENTIFICATION		
	UNRESTRICTED USE	RESIDENTIAL USE	PROTECTION OF ECOLOGICAL RESOURCES	BRIDGE STREET SWALE		
				SW-13C		
Sample Date				5/22/2014		
<b>Metals by EPA Method 6010C</b>					D.L.	R.L.
Chromium, Total	30	36	41	7.4		
Copper, Total	50	270	50	21		
Nickel, Total	30	140	30	13		
<b>Cyanide by EPA Method 9010C</b>						
Cyanide, Total	27	27	NS	U	0.25	1.1
<b>Chromium by EPA Method 7196A</b>						
Chromium, Hexavalent	1	22	1	UJ	0.18	0.88

All values reported as mg/kg (parts per million)

Soil Cleanup Objectives from 6 NYCRR Part 375-6.8(b) (December 2006) and Supplemental Soil Cleanup Objectives (October 2010)

U - Analyzed for but not detected above the laboratory reporting limit

J - Estimated value

R - Result rejected by DUSR

D.L. - Laboratory Detection Limit

R.L. - Laboratory Reporting Limit

NS - Not Specified

Bold and thick outlined cell indicates analyte exceeds the Unrestricted Use Soil Cleanup Objective

Bold, thick outlined, and shaded cell indicates analyte exceeds the Protection of Ecological Resources and the Unrestricted Use Soil Cleanup Objectives



Table 1 - (Page 14 of 19): Summary of Post-Excavation Soil Sample Laboratory Analytical Results. Celi Drive BCP Site (BCP Site #C734108), Syracuse, NY.

ANALYTE (mg/kg)	SOIL CLEANUP OBJECTIVES			SAMPLE IDENTIFICATION										
	UNRESTRICTED USE	RESIDENTIAL USE	PROTECTION OF ECOLOGICAL RESOURCES	BRIDGE STREET SWALE										
				SW-14A		SW-14B		SW-14B-1						
Sample Date				5/22/2014		5/22/2014		5/29/2014						
<b>Metals by EPA Method 6010C</b>					D.L.	R.L.		D.L.	R.L.		D.L.	R.L.		
Chromium, Total	30	36	41	11			25			11				
Copper, Total	50	270	50	21			<b>67</b>			15				
Nickel, Total	30	140	30	19			<b>43</b>			13				
<b>Cyanide by EPA Method 9010C</b>														
Cyanide, Total	27	27	NS	U	0.27	1.2	0.28	J	0.28	1.2	U	0.54	2.3	
<b>Chromium by EPA Method 7196A</b>														
Chromium, Hexavalent	1	22	1	0.31	J	0.2	0.99	0.31	J	0.21	1	U	0.18	0.92

ANALYTE (mg/kg)	SOIL CLEANUP OBJECTIVES			SAMPLE IDENTIFICATION				
	UNRESTRICTED USE	RESIDENTIAL USE	PROTECTION OF ECOLOGICAL RESOURCES	BRIDGE STREET SWALE				
				SW-14C				
Sample Date				5/22/2014				
<b>Metals by EPA Method 6010C</b>					D.L.	R.L.		
Chromium, Total	30	36	41	12				
Copper, Total	50	270	50	28				
Nickel, Total	30	140	30	21				
<b>Cyanide by EPA Method 9010C</b>								
Cyanide, Total	27	27	NS	U	0.24	1		
<b>Chromium by EPA Method 7196A</b>								
Chromium, Hexavalent	1	22	1	UJ	0.18	0.89		

All values reported as mg/kg (parts per million)

Soil Cleanup Objectives from 6 NYCRR Part 375-6.8(b) (December 2006) and Supplemental Soil Cleanup Objectives (October 2010)

U - Analyzed for but not detected above the laboratory reporting limit

J - Estimated value

D.L. - Laboratory Detection Limit

R.L. - Laboratory Reporting Limit

NS - Not Specified

Bold and thick outlined cell indicates analyte exceeds the Unrestricted Use Soil Cleanup Objective

Bold, thick outlined, and shaded cell indicates analyte exceeds the Protection of Ecological Resources and the Unrestricted Use Soil Cleanup Objectives



Table 1 - (Page 15 of 19): Summary of Post-Excavation Soil Sample Laboratory Analytical Results. Celi Drive BCP Site (BCP Site #C734108), Syracuse, NY.

ANALYTE (mg/kg)	SOIL CLEANUP OBJECTIVES			SAMPLE IDENTIFICATION									
	UNRESTRICTED USE	RESIDENTIAL USE	PROTECTION OF ECOLOGICAL RESOURCES	BRIDGE STREET SWALE									
				SW-15A		SW-15B		SW-15C					
Sample Date				5/23/2014		5/23/2014		5/23/2014					
<b>Metals by EPA Method 6010C</b>					D.L.	R.L.		D.L.	R.L.		D.L.	R.L.	
Chromium, Total	30	36	41	13			17			25			
Copper, Total	50	270	50	38			23			<b>57</b>			
Nickel, Total	30	140	30	15			16			18			
<b>Cyanide by EPA Method 9010C</b>													
Cyanide, Total	27	27	NS	U	0.27	1.1	U	0.29	1.2	0.93	J	0.3	1.3
<b>Chromium by EPA Method 7196A</b>													
Chromium, Hexavalent	1	22	1	UJ	0.18	0.92	UJ	0.21	1	U	0.22	1.1	

ANALYTE (mg/kg)	SOIL CLEANUP OBJECTIVES			SAMPLE IDENTIFICATION		
	UNRESTRICTED USE	RESIDENTIAL USE	PROTECTION OF ECOLOGICAL RESOURCES	BRIDGE STREET SWALE		
				SW-15C-1		
Sample Date				5/29/2014		
<b>Metals by EPA Method 6010C</b>					D.L.	R.L.
Chromium, Total	30	36	41	22		
Copper, Total	50	270	50	50		
Nickel, Total	30	140	30	18		
<b>Cyanide by EPA Method 9010C</b>						
Cyanide, Total	27	27	NS	U	0.56	2.4
<b>Chromium by EPA Method 7196A</b>						
Chromium, Hexavalent	1	22	1	U	0.19	0.95

All values reported as mg/kg (parts per million)

Soil Cleanup Objectives from 6 NYCRR Part 375-6.8(b) (December 2006) and Supplemental Soil Cleanup Objectives (October 2010)

U - Analyzed for but not detected above the laboratory reporting limit

J - Estimated value

D.L. - Laboratory Detection Limit

R.L. - Laboratory Reporting Limit

NS - Not Specified

Bold and thick outlined cell indicates analyte exceeds the Unrestricted Use Soil Cleanup Objective

Bold, thick outlined, and shaded cell indicates analyte exceeds the Protection of Ecological Resources and the Unrestricted Use Soil Cleanup Objectives



Table 1 - (Page 16 of 19): Summary of Post-Excavation Soil Sample Laboratory Analytical Results. Celi Drive BCP Site (BCP Site #C734108), Syracuse, NY.

ANALYTE (mg/kg)	SOIL CLEANUP OBJECTIVES			SAMPLE IDENTIFICATION					
	UNRESTRICTED USE	RESIDENTIAL USE	PROTECTION OF ECOLOGICAL RESOURCES	CHIMNEY PLAZA SWALE					
				SW-16			SW-17		
Sample Date				5/27/2014			5/27/2014		
<b>Metals by EPA Method 6010C</b>					D.L.	R.L.		D.L.	R.L.
Chromium, Total	30	36	41	6.1			6.7		
Copper, Total	50	270	50	16			12		
Nickel, Total	30	140	30	9.2			9.0		
<b>Cyanide by EPA Method 9010C</b>									
Cyanide, Total	27	27	NS	U	0.27	1.1	U	0.26	1.1
<b>Chromium by EPA Method 7196A</b>									
Chromium, Hexavalent	1	22	1	<b>2.6</b>			U	0.19	0.97

All values reported as mg/kg (parts per million)

Soil Cleanup Objectives from 6 NYCRR Part 375-6.8(b) (December 2006) and Supplemental Soil Cleanup Objectives (October 2010)

U - Analyzed for but not detected above the laboratory reporting limit

J - Estimated value

D.L. - Laboratory Detection Limit

R.L. - Laboratory Reporting Limit

NS - Not Specified

Bold and thick outlined cell indicates analyte exceeds the Unrestricted Use Soil Cleanup Objective

Bold, thick outlined, and shaded cell indicates analyte exceeds the Protection of Ecological Resources and the Unrestricted Use Soil Cleanup Objectives



Table 1 - (Page 17 of 19): Summary of Post-Excavation Soil Sample Laboratory Analytical Results. Celi Drive BCP Site (BCP Site #C734108), Syracuse, NY.

ANALYTE (mg/kg)	SOIL CLEANUP OBJECTIVES			SAMPLE IDENTIFICATION							
	UNRESTRICTED USE	RESIDENTIAL USE	PROTECTION OF ECOLOGICAL RESOURCES	CHIMNEY PLAZA SWALE							
				SW-18				SW-19			
Sample Date				5/28/2014				5/28/2014			
<b>Metals by EPA Method 6010C</b>						D.L.	R.L.			D.L.	R.L.
Chromium, Total	30	36	41	11	J			8.1	J		
Copper, Total	50	270	50	27	J			14	J		
Nickel, Total	30	140	30	14				11			
<b>Cyanide by EPA Method 9010C</b>											
Cyanide, Total	27	27	NS		U	0.29	1.2		U	0.27	1.2
<b>Chromium by EPA Method 7196A</b>											
Chromium, Hexavalent	1	22	1	0.4	J	0.21	1	0.43	J	0.19	0.96

All values reported as mg/kg (parts per million)

Soil Cleanup Objectives from 6 NYCRR Part 375-6.8(b) (December 2006) and Supplemental Soil Cleanup Objectives (October 2010)

U - Analyzed for but not detected above the laboratory reporting limit

J - Estimated value

D.L. - Laboratory Detection Limit

R.L. - Laboratory Reporting Limit

NS - Not Specified

Bold and thick outlined cell indicates analyte exceeds the Unrestricted Use Soil Cleanup Objective

Bold, thick outlined, and shaded cell indicates analyte exceeds the Protection of Ecological Resources and the Unrestricted Use Soil Cleanup Objectives



Table 1 - (Page 18 of 19): Summary of Post-Excavation Soil Sample Laboratory Analytical Results. Celi Drive BCP Site (BCP Site #C734108). Syracuse, NY.

ANALYTE (mg/kg)	SOIL CLEANUP OBJECTIVES			SAMPLE IDENTIFICATION								
	UNRESTRICTED USE	RESIDENTIAL USE	PROTECTION OF ECOLOGICAL RESOURCES	MAIN SWALE								
				SW-20A		SW-20B		SW-20C				
Sample Date				6/4/2014		6/4/2014		6/4/2014				
<b>Metals by EPA Method 6010C</b>					D.L.	R.L.		D.L.	R.L.		D.L.	R.L.
Chromium, Total	30	36	41	5.4			7.4			11		
Copper, Total	50	270	50	9.2			16			15		
Nickel, Total	30	140	30	7.5	J		11	J		14	J	
<b>Cyanide by EPA Method 9010C</b>												
Cyanide, Total	27	27	NS	U	0.52	2.2	U	0.62	2.7	U	0.55	2.4
<b>Chromium by EPA Method 7196A</b>												
Chromium, Hexavalent	1	22	1	U	0.2	1	U	0.22	1.1	U	0.19	0.95

All values reported as mg/kg (parts per million)

Soil Cleanup Objectives from 6 NYCRR Part 375-6.8(b) (December 2006) and Supplemental Soil Cleanup Objectives (October 2010)

U - Analyzed for but not detected above the laboratory reporting limit

J - Estimated value

D.L. - Laboratory Detection Limit

R.L. - Laboratory Reporting Limit

NS - Not Specified

Bold and thick outlined cell indicates analyte exceeds the Unrestricted Use Soil Cleanup Objective

Bold, thick outlined, and shaded cell indicates analyte exceeds the Protection of Ecological Resources and the Unrestricted Use Soil Cleanup Objectives





Table 1 - (Page 19 of 19): Summary of Post-Excavation Soil Sample Laboratory Analytical Results. Celi Drive BCP Site (BCP Site #C734108). Syracuse, NY.

ANALYTE (mg/kg)	SOIL CLEANUP OBJECTIVES			SAMPLE IDENTIFICATION						
	UNRESTRICTED USE	RESIDENTIAL USE	PROTECTION OF ECOLOGICAL RESOURCES	DUP-1 (SW-8B)			DUPLICATE (SW-6A-1)			
Sample Date				5/8/2014			5/22/2014			
<b>Metals by EPA Method 6010C</b>					R.L.	RPD		R.L.	RPD	
Chromium, Total	30	36	41	4.5		26.92%	18		18.18%	
Copper, Total	50	270	50	7.7		35.29%	35		29.51%	
Nickel, Total	30	140	30	5.6		35.29%	<b>32</b>		32.73%	
<b>Cyanide by EPA Method 9010C</b>										
Cyanide, Total	27	27	NS	U	1.2	NA	0.28	J	1.1	NA
<b>Chromium by EPA Method 7196A</b>										
Chromium, Hexavalent	1	22	1	0.31	J	0.98	10.17%	UJ	0.98	NA

All values reported as mg/kg (parts per million)

Soil Cleanup Objectives from 6 NYCRR Part 375-6.8(b) (December 2006) and Supplemental Soil Cleanup Objectives (October 2010)

U - Analyzed for but not detected above the laboratory reporting limit

J - Estimated value

D.L. - Laboratory Detection Limit

R.L. - Laboratory Reporting Limit

NS - Not Specified



Bold and thick outlined cell indicates analyte exceeds the Unrestricted Use Soil Cleanup Objective

Bold, thick outlined, and shaded cell indicates analyte exceeds the Protection of Ecological Resources and the Unrestricted Use Soil Cleanup Objectives

RPD - Relative Percent Difference

$$RPD = \frac{2(\text{Sample Value} - \text{Duplicate Sample Value})}{\text{Sample Value} + \text{Duplicate Sample Value}}$$

$$(\text{Sample Value} + \text{Duplicate Sample Value})$$



KRAVEC SUBDIVISION

LOT 1


LOT 2

NEW 5841 BSA, LLC PARCEL

BRIDGE STREET

**NOTES:**  
 Elevations referred to N.G.V.D. 1929 (feet)  
 Location of underground utilities taken by field measurement where practicable, otherwise taken from various other sources and are approximate only.

- LEGEND:**
- ⊗ indicates sample point obtained 1/27/2014
  - ⊗ indicates sample point numbers between 1553 and 1630 obtained 5/23/2014
  - indicates sample point numbers between 1633 and 1673 obtained 5/30/2014
  - indicates sample point numbers 1677 through 1680 obtained 6/5/2014




TRACT MAP: KRAVEC SUBDIVISION  
 BY: C.T. MALE ASSOCIATES  
 DATE FILED: OCTOBER 23, 2013  
 MAP NO. 11759

<b>REVISIONS</b> 5 - 23 - 14 5 - 30 - 14 6 - 5 - 14 *3 - 17 - 15	SAMPLING POINTS PART OF <b>KRAVEC SUBDIVISION</b> AND <b>NEW 5841 BSA, LLC PARCEL</b> PART OF MILITARY LOT No. 51 TOWN OF DEWITT ONONDAGA COUNTY, NEW YORK		
	<b>IANUZI &amp; ROMANS</b> <b>LAND SURVEYING, P.C.</b> NORTH SYRACUSE, NY 13212 PHONE: (315) 457-7200 FAX: (315) 457-9251		
	DATE: JANUARY 27, 2014	SHEET NO.	
	SCALE: 1" = 20'	FILE NO.: 3553.001	


\*REVISIONS PER GHD COMMENTS/REQUEST 2-20-15

Attachment B-9 – Excerpts from Supplemental  
Sampling Activities Summary Letter Report, GHD,  
October 3, 2016



**NOTES:**

- Site features are from a field survey completed by D.W. [redacted] annual LIS, P.C. dated November 2012 and revised 11-1-2010, 3-2-2010, 11-10-2010, 11-10-2010, 11-24-2010, and 4-1-2014.
- Aerial photographs are from the hall foot 4 and central one index from the NYS Clearinghouse website: <http://isiny.gov/>




GSP Holdings, Inc.  
 Celi Drive BCP Site (BCP Site #C734108)  
 Supplemental Sampling Activities

Job Number | 37-11082  
 Revision | A  
 Date | 09.21.2016


**Groundwater Elevation and Flow**

**Figure 3**




**NOTES:**

- Site features are from a field survey completed by DWT on 11/11/15. PCBs dated November 1, 2012 and revised 1-1-2011, 3-2-2011, 1-1-2011, 1-1-2011, 1-24-2011, and 4-1-2014.
- Aerial photographs are 2011, 2004, and 2001. One index from the NYS DEC Clearinghouse website: <http://isiny.gov>
- Only analytes that exceed applicable Class A standards or guidance values are shown here!



GSP Holdings, Inc.  
Celi Drive BCP Site (BCP Site #C734108)  
Supplemental Sampling Activities  
Groundwater Exceedances of  
Class GA Standards

Job Number | 37-11082  
Revision | A  
Date | 09.21.2016  
**Figure 4**



LE END	
BSS-SED1-COMP	Composite Sediment Sample Location and ID (Approximate)
SW-1A	Excavation End-Point Soil Sample Location and ID (Surveyed)
---	Edge of Water Pre-Excavation (Surveyed)
- . -	Edge of Water Post-Excavation (Surveyed)



NOTES:  
 1) Aerial photographs are 2101-foot resolution color orthorectified by the NYS GIS Clearinghouse website (<http://gis.ny.gov/ateway/index.html>)  
 2) Previous sediment sample locations were surveyed



GSP Holdings, Inc.  
 Celi Drive BCP Site (BCP Site #C734108)  
 Supplemental Sampling Activities  
 Bridge Street Swale Sediment  
 Sample Locations

Job Number | 37-11082  
 Revision | A  
 Date | 09.21.2016


**Figure 5**



LEND

APPROXIMATE SEDIMENT  
SAMPLE LOCATION AND ID

POTENTIAL SEDIMENT  
SAMPLE LOCATION AND ID  
(SIGHTED)



NOTES:  
1. Aerial photographs are low resolution color orthorectified imagery from the National Aerial Photography Mission (NAPM) site (<http://earthexplorer.usgs.gov>)



GSP Holdings, Inc.  
Celi Drive BCP Site (BCP Site #C734108)  
Supplemental Sampling Activities

Job Number | 37-11082  
Revision | A  
Date | 09.21.2016

Approximate Swale Sample Locations **Figure 6**



Table 1: (Page 1 of 1) Groundwater Monitoring Well Development Log. Celi Drive BCP Site, Syracuse, NY.

Well I.D.	Date	PID	DTW	DOW	Time	Volume Removed (gallons)	Turbidity (NTU)	Comments
MW-8	8/26/2016	1.0	4.85	14.44	10:05	0.0	-	Removed 28 gallons of water with peristaltic pump and dedicated tubing. Pumped as fast as the pump would go the entire time and well never went dry. Shut off pump twice for approximately 10 minutes each time to empty buckets. Water started very turbid with lots of very fine silty sediment. Water cleared with development to little sediment at completion of development. Removed approximately 1.5 feet of sediment from well. Development water contained in steel 55-gallon drum staged on-site awaiting characterization and disposal.
					11:00	3.5	MAX	
					11:12	7.0	MAX	
					11:16	8.0	314.0	
					11:27	10.5	366.0	
					11:37	11.0	233.0	
					11:50	14.0	163.0	
					12:05	17.5	52.4	
					12:20	21.0	28.4	
					12:26	21.5	41.3	
					12:42	24.5	136.0	
					12:58	28.0	52.0	
					6.80	15.90	13:00	

Turbidity collected during development using a HACH2100Q.

MAX - turbidity meter maximum reading output was 1000 NTU.





Table 2: (Page 1 of 1) Groundwater Elevation Data. Celi Drive BCP Site, Syracuse, NY.

Monitoring Well I.D.	Date	Reference Point	Reference Elevation (feet)	DTW (feet)	DOW (feet)	Water Elevation (feet)	Volume (gal)
MW-1	1/31/2014	Top of PVC	413.46	3.58	16.16	409.88	2.01
	9/1/2016			4.01	16.37	409.45	1.98
MW-2	1/31/2014	Top of PVC	414.05	2.92	14.85	411.13	1.91
	9/1/2016			3.97	15.08	410.08	1.78
MW-3	1/31/2014	Top of PVC	416.10	4.46	14.58	411.64	1.62
	9/1/2016			4.44	14.83	411.66	1.66
MW-4	1/31/2014	Top of PVC	415.88	4.30	14.75	411.58	1.67
	9/1/2016			5.27	15.00	410.61	1.56
MW-5	1/31/2014	Top of PVC	415.01	4.07	13.90	410.94	1.57
	9/1/2016			4.49	14.00	410.52	1.52
MW-6	1/31/2014	Top of PVC	413.16	2.95	13.76	410.21	1.73
	9/1/2016			NM	NM	NM	NM
MW-7	1/31/2014	Top of PVC	412.92	3.05	13.14	409.87	1.61
	9/1/2016			3.43	13.33	409.49	1.58
MW-8	1/31/2014	Top of PVC	414.70	-	-	-	-
	9/1/2016			4.48	15.88	410.22	1.82

DTW - depth to water

DOW - depth of well

( - ) - Not Measured because well could not be located

NM - Not Measured because well was not sampled during this event



Table 3: (Page 1 of 8) Groundwater Field Parameter Data. Celi Drive BCP Site, Syracuse, NY.

Well I.D.	Date	Time	Temp (°C)	Conductivity (mmhos/cm)	Salinity (%)	Dissolved Oxygen (mg/L)	pH (units)	ORP (mV)	Turbidity (NTU)	Amount Purged (liters)	Comments
MW-1	1/31/2014	7:51	9.16	1.436	1.05	3.2	8.12	45.3	1401.5	14.0	Purged 14 liters at 3 cycles per minute with bladder pump. Water started cloudy light yellowish brown with some sediment and cleared quickly. Sample water was clear with no sheen or odor.
		7:55	10.82	1.501	1.06	0.89	7.09	9.3	1145.4		
		7:58	10.78	1.504	1.06	0.75	7.04	-0.7	800.8		
		8:01	10.76	1.502	1.06	0.62	7.03	1.2	687.4		
		8:04	10.74	1.503	1.06	0.57	7.03	-2.0	501.7		
		8:07	10.73	1.502	1.06	0.55	7.03	-6.5	346.4		
		8:13	10.61	1.507	1.07	0.47	7.05	-15.9	164.6		
		8:16	10.62	1.511	1.07	0.45	6.98	-16.2	117.4		
		8:19	10.60	1.511	1.07	0.42	6.98	-19.5	95.4		
		8:23	10.61	1.517	1.08	0.41	7.00	-23.2	68.6		
	8:26	10.54	1.519	1.08	0.40	7.01	-26.2	56.8			
	8:30	10.55	1.521	1.08	0.39	7.02	-29.2	49.4			
	8:33	10.57	1.521	1.08	0.41	7.04	-34.0	45.1			
	8:36	10.55	1.522	1.08	0.39	7.04	-25.4	42.2			
	9/1/2016	7:35	18.11	1.752	1.03	2.96	6.70	16.4	460.0	18.0	Purged 18 liters with peristaltic pump. Water cleared with purge, yellow tint, no sediment, no odor, no sheen. MS/MSD sample taken from this location.
		7:37	16.92	1.738	1.06	1.05	6.76	-28.8	246.5		
		7:39	17.24	1.754	1.06	1.53	6.73	-36.2	1169.8		
		7:42	17.53	1.767	1.06	1.83	6.75	-45.2	284.4		
		7:43	17.65	1.771	1.06	2.29	6.75	-47.9	1128.3		
		7:45	17.89	1.776	1.05	1.87	6.77	-53.4	276.2		
7:47		18.09	1.778	1.05	1.51	6.82	-58.4	149.9			
7:49		18.21	1.779	1.05	1.45	6.87	-62.2	119.6			
7:51		18.29	1.784	1.05	1.09	6.86	-67.8	59.2			
7:52		18.36	1.790	1.05	1.25	6.87	-67.4	43.8			
7:54	18.40	1.796	1.05	2.50	6.87	-69.0	45.6				
7:56	18.48	1.803	1.06	1.99	6.88	-71.5	27.2				
7:58	18.53	1.808	1.06	2.02	6.76	-73.6	23.9				
8:00	18.61	1.818	1.06	1.66	6.89	-75.9	17.4				
8:04	18.67	1.827	1.07	1.53	6.92	-77.8	13.4				
8:06	18.72	1.834	1.07	1.27	6.90	-78.4	20.3				

Field parameters collected during purging using a YSI 6920 with flow thru cell.

Field parameters recorded after every liter of purge.

NM - Not Measured



Table 3: (Page 2 of 8) Groundwater Field Parameter Data. Celi Drive BCP Site, Syracuse, NY.

Well I.D.	Date	Time	Temp (°C)	Conductivity (mmhos/cm)	Salinity (%)	Dissolved Oxygen (mg/L)	pH (units)	ORP (mV)	Turbidity (NTU)	Amount Purged (liters)	Comments
MW-2	1/31/2014	11:41	8.20	1.290	0.97	2.95	7.70	88.5	1268.4	16.0	Purged 16 liters at 2 cycles per minute with bladder pump. Water started turbid brown and took a long time to clear. Sample water was clear with a blocky sheen and no odor.
		11:45	9.63	1.332	0.96	0.78	7.37	55.6	1398.5		
		11:49	10.22	1.354	0.97	0.54	7.31	38.2	1445.3		
		11:53	10.25	1.355	0.96	0.48	7.27	27.1	1442.1		
		11:57	10.53	1.361	0.96	0.54	7.29	35.2	1442.1		
		12:00	10.54	1.364	0.96	0.52	7.23	25.4	1442.2		
		12:05	10.72	1.368	0.96	0.45	7.23	10.3	1400.2		
		12:10	10.82	1.371	0.96	0.39	7.22	2.4	1032.5		
		12:15	10.83	1.370	0.96	0.38	7.20	-2.7	669.6		
		12:20	10.82	1.369	0.96	0.38	7.18	-6.7	412.9		
		12:25	10.82	1.368	0.96	0.39	7.17	-9.2	278.5		
		12:30	10.79	1.365	0.96	0.40	7.14	-10.5	175.8		
		12:35	10.82	1.363	0.95	0.40	7.13	-12.8	131.9		
		12:40	10.84	1.361	0.95	0.40	7.14	-15.3	108.5		
		12:45	10.93	1.363	0.95	0.39	7.14	-17.7	83.4		
	12:50	11.00	1.366	0.95	0.38	7.13	-18.5	72.9			
	12:55	11.03	1.367	0.95	0.38	7.13	-19.9	48.7			
	9/1/2016	10:04	16.78	1.687	1.03	3.32	7.58	-34.5	1365.6	17.0	Purged 17 liters with peristaltic pump. Water turbid brown with lots of floaters at start. Floaters decreased with purge but turbidity didn't, no sheen, no odor.
		10:05	15.65	1.656	1.03	0.84	7.37	-42.0	1658.9		
		10:06	15.59	1.653	1.03	0.54	7.37	-44.5	646.2		
		10:08	15.67	1.657	1.03	0.40	7.19	-49.8	696.0		
		10:10	15.62	1.653	1.03	0.35	7.14	-50.8	597.8		
		10:11	15.60	1.653	1.03	0.33	7.11	-52.1	634.2		
		10:13	15.60	1.650	1.03	0.30	7.06	-54.0	424.6		
		10:15	15.62	1.648	1.03	0.28	7.08	-55.2	305.7		
10:16		15.60	1.648	1.03	0.30	7.05	-57.0	305.2			
10:18		15.61	1.646	1.03	0.26	7.06	-57.7	170.4			
10:20		15.58	1.639	1.03	0.25	7.05	-58.5	235.8			
10:22		15.61	1.633	1.02	0.24	7.03	-60.0	178.6			
10:25		15.80	1.645	1.02	0.27	7.07	-52.2	110.4			
10:27		15.53	1.624	1.02	1.98	7.08	-56.0	148.5			
10:29		15.55	1.621	1.01	1.88	7.06	-57.8	151.6			
10:31	15.51	1.620	1.01	2.23	7.08	-59.0	130.3				
10:33	15.51	1.617	1.01	1.93	7.07	-59.2	105.6				

Field parameters collected during purging using a YSI 6920 with flow thru cell.

Field parameters recorded after every liter of purge.

NM - Not Measured



Table 3: (Page 3 of 8) Groundwater Field Parameter Data. Celi Drive BCP Site, Syracuse, NY.

Well I.D.	Date	Time	Temp (°C)	Conductivity (mmhos/cm)	Salinity (%)	Dissolved Oxygen (mg/L)	pH (units)	ORP (mV)	Turbidity (NTU)	Amount Purged (liters)	Comments
MW-3	1/31/2014	15:21	7.04	0.811	0.62	2.77	7.48	108.0	901.0	12.0	Purged 12 liters at 2 cycles per minute with bladder pump. Water started cloudy and cleared fairly quickly. Sample water was slightly cloudy with no sheen or odor.
		15:24	7.67	0.812	0.61	1.06	7.08	96.8	518.4		
		15:28	7.85	0.817	0.61	0.76	6.85	91.6	344.3		
		15:31	7.98	0.825	0.61	0.65	6.72	90.6	278.9		
		15:34	8.12	0.831	0.61	0.56	6.66	89.2	190.1		
		15:39	8.04	0.831	0.62	0.51	6.61	87.0	158.5		
		15:44	8.19	0.834	0.61	0.47	6.66	80.8	126.0		
		15:49	8.32	0.835	0.61	0.44	6.63	79.3	94.7		
		15:53	8.35	0.835	0.61	0.42	6.62	78.1	74.1		
		15:58	8.44	0.836	0.61	0.41	6.61	77.5	66.3		
	16:03	8.51	0.836	0.61	0.42	6.61	76.6	63.5			
	16:08	8.57	0.836	0.61	0.41	6.60	75.3	49.3			
	9/1/2016	15:22	17.77	1.922	1.16	5.93	7.40	-57.4	220.9	12.0	Purged 12 liters with peristaltic pump. Water clear, no sheen, no odor. Duplicate sample taken from this location.
		15:24	14.73	1.777	1.14	0.80	7.24	-68.8	107.8		
		15:25	14.94	1.779	1.13	0.43	7.18	-71.1	100.7		
		15:27	15.14	1.786	1.13	0.38	7.11	-72.6	80.1		
		15:28	15.31	1.785	1.13	0.35	7.09	-72.6	82.6		
		15:30	15.42	1.781	1.12	0.34	7.07	-71.2	106.7		
		15:31	15.54	1.778	1.12	0.36	7.04	-68.3	98.2		
		15:33	15.56	1.776	1.12	0.35	7.02	-68.4	59.0		
15:34		15.45	1.772	1.12	0.34	7.01	-67.9	23.3			
15:36		15.33	1.771	1.12	0.32	6.99	-67.4	17.3			
15:38	15.29	1.772	1.13	0.30	6.99	-66.8	12.1				

Field parameters collected during purging using a YSI 6920 with flow thru cell.

Field parameters recorded after every liter of purge.

NM - Not Measured



Table 3: (Page 4 of 8) Groundwater Field Parameter Data. Celi Drive BCP Site, Syracuse, NY.

Well I.D.	Date	Time	Temp (°C)	Conductivity (mmhos/cm)	Salinity (%)	Dissolved Oxygen (mg/L)	pH (units)	ORP (mV)	Turbidity (NTU)	Amount Purged (liters)	Comments
MW-4	1/31/2014	16:38	5.18	0.865	0.70	4.22	7.22	132.3	1004.3	14.0	Purged 14 liters at 2 cycles per minute with bladder pump. Water started slightly cloudy and cleared fairly quickly. Sample water was slightly cloudy with no sheen or odor. Sample taken prior to reaching less than 50 NTUs due to running out of daylight.
		16:41	6.16	0.907	0.71	1.07	7.05	107.7	511.1		
		16:45	6.03	0.906	0.71	0.71	7.03	87.3	429.8		
		16:49	5.98	0.909	0.72	0.60	6.98	74.1	394.9		
		16:54	6.10	0.918	0.72	0.55	6.96	53.7	336.6		
		16:59	6.17	0.929	0.73	0.58	6.97	54.5	279.8		
		17:04	6.20	0.934	0.73	0.62	6.93	45.7	224.6		
		17:09	6.21	0.938	0.74	0.49	7.02	33.8	212.9		
		17:13	6.19	0.943	0.74	0.43	7.01	27.7	171.4		
		17:18	6.25	0.948	0.74	0.40	6.98	23.5	148.9		
		17:23	6.25	0.952	0.75	0.39	6.97	20.3	133.4		
		17:28	6.23	0.954	0.75	0.37	6.95	16.6	146.3		
		17:33	6.24	0.956	0.75	0.37	6.95	14.1	121.9		
	17:37	6.26	0.957	0.75	0.36	6.96	12.7	114.7			
	9/1/2016	13:52	19.18	1.146	0.65	3.95	7.44	-64.5	508.3	24.0	Purged 24 liters with peristaltic pump. Water slight brown tint at first and cleared with purged. Sample water clear with no sheen and no odor.
		13:54	16.52	0.914	0.54	1.91	7.37	-52.6	203.7		
		13:56	16.49	0.856	0.51	1.48	7.30	-43.1	147.0		
		13:58	16.81	0.839	0.49	1.20	7.32	-34.5	128.5		
		13:59	17.13	0.850	0.50	1.03	7.21	-29.0	166.0		
		14:00	17.48	0.881	0.51	0.94	7.20	-23.4	218.2		
		14:02	17.70	0.929	0.54	0.73	7.08	-20.9	300.0		
		14:04	17.67	0.989	0.58	0.68	7.14	-20.7	331.2		
		14:05	17.47	1.059	0.62	0.93	7.11	-24.4	326.1		
		14:07	17.24	1.103	0.65	1.45	7.09	-27.2	322.3		
		14:09	17.03	1.180	0.70	2.16	7.09	-29.5	298.1		
		14:11	16.85	1.266	0.76	2.70	7.07	-31.5	232.5		
		14:13	16.74	1.345	0.81	3.37	7.08	-32.4	150.0		
14:14		16.65	1.393	0.84	3.64	7.07	-32.1	129.7			
14:16	16.58	1.438	0.87	3.79	7.06	-32.3	92.7				
14:18	16.70	1.540	0.94	3.82	7.05	-34.5	102.8				
14:20	16.31	1.664	1.02	3.71	7.07	-34.8	90.8				
14:22	16.42	1.589	0.97	3.85	7.06	-36.7	120.0				
14:23	16.45	1.532	0.94	4.28	7.05	-36.2	121.6				
14:25	16.40	1.557	0.95	4.38	7.03	-35.1	126.9				
14:27	16.46	1.601	0.98	4.49	7.04	-33.7	94.0				
14:28	16.42	1.718	0.99	4.41	7.02	-33.0	66.5				
14:30	16.36	1.790	1.10	4.32	7.00	-33.2	49.7				
14:32	16.35	1.829	1.13	4.32	6.99	-33.5	39.7				

Field parameters collected during purging using a YSI 6920 with flow thru cell.

Field parameters recorded after every liter of purge.

NM - Not Measured



Table 3: (Page 5 of 8) Groundwater Field Parameter Data. Celi Drive BCP Site, Syracuse, NY.

Well I.D.	Date	Time	Temp (°C)	Conductivity (mmhos/cm)	Salinity (%)	Dissolved Oxygen (mg/L)	pH (units)	ORP (mV)	Turbidity (NTU)	Amount Purged (liters)	Comments
MW-5	1/31/2014	13:34	7.80	1.540	1.18	3.92	7.72	106.5	1420.8	22.0	Purged 22 liters at 3 cycles per minute with bladder pump. Water started turbid brown and cleared slowly. Sample water was slightly cloudy with no sheen or odor. Sample taken prior to reaching less than 50 NTUs due to minimal improvement in water clarity.
		13:37	9.19	1.692	1.26	1.12	7.35	86.6	1427.2		
		13:40	9.21	1.681	1.24	0.92	7.29	74.9	1422.4		
		13:43	9.08	1.675	1.24	0.89	7.20	66.3	1188.4		
		13:46	9.09	1.675	1.24	0.85	7.16	60.0	1138.7		
		13:49	9.11	1.685	1.25	0.87	7.12	54.8	1356.4		
		13:53	9.17	1.702	1.26	0.82	7.11	48.2	1350.2		
		13:55	9.11	1.708	1.27	0.88	7.12	44.1	1204.2		
		13:58	8.97	1.704	1.27	1.02	7.23	47.6	1171.3		
		14:00	8.86	1.703	1.27	1.19	7.09	48.0	1081.1		
		14:03	8.85	1.708	1.28	1.05	7.08	43.8	950.0		
		14:07	8.85	1.705	1.28	1.03	7.08	38.5	755.2		
		14:11	8.95	1.726	1.29	0.95	7.09	34.3	636.4		
		14:14	8.91	1.711	1.28	0.97	7.11	29.8	545.3		
		14:17	8.88	1.710	1.28	0.97	7.11	27.7	494.4		
		14:20	8.99	1.718	1.28	0.91	7.11	25.2	377.4		
		14:24	9.02	1.723	1.28	0.94	7.12	22.2	333.8		
		14:27	9.06	1.725	1.28	0.91	7.12	21.0	304.7		
		14:30	9.00	1.724	1.29	0.94	7.12	19.4	243.0		
	14:34	9.07	1.729	1.29	0.90	7.12	18.1	211.7			
	14:37	9.05	1.730	1.29	0.88	7.12	17.1	104.5			
	14:41	9.05	1.728	1.29	0.88	7.11	17.0	150.3			
	9/1/2016	11:14	18.58	1.775	1.04	5.11	7.41	-13.2	1375.4	13.0	Purged 13 liters with peristaltic pump. Water started rusty orange with lots of rusty orange floaters. Sample water clear with no sheen and no odor.
		11:16	16.59	1.722	1.05	1.02	7.39	-38.9	1381.3		
		11:18	16.52	1.710	1.05	0.65	7.31	-44.6	1143.3		
		11:21	16.94	1.714	1.04	0.72	7.32	-44.5	260.2		
11:22		16.84	1.701	1.03	0.73	7.29	-49.0	141.6			
11:24		17.01	1.689	1.02	0.37	7.24	-50.7	155.3			
11:26		17.14	1.677	1.01	0.33	7.20	-49.7	188.4			
11:28		17.25	1.674	1.01	0.35	7.22	-50.7	169.9			
11:29		17.25	1.646	1.01	0.37	7.18	-50.6	168.8			
11:31		17.25	1.682	1.01	0.39	7.18	-52.0	143.1			
11:32		17.24	1.686	1.01	0.39	7.17	-53.7	112.2			
11:34	17.21	1.692	1.02	0.40	7.12	-56.0	69.3				
11:36	17.21	1.697	1.02	0.39	7.18	-57.0	60.2				
11:37	17.20	1.702	1.02	0.36	7.13	-58.8	48.6				
11:39	17.22	1.706	1.03	0.38	7.18	-59.8	50.7				

Field parameters collected during purging using a YSI 6920 with flow thru cell.

Field parameters recorded after every liter of purge.

NM - Not Measured



Table 3: (Page 6 of 8) Groundwater Field Parameter Data. Celi Drive BCP Site, Syracuse, NY.

Well I.D.	Date	Time	Temp (°C)	Conductivity (mmhos/cm)	Salinity (%)	Dissolved Oxygen (mg/L)	pH (units)	ORP (mV)	Turbidity (NTU)	Amount Purged (liters)	Comments
MW-6	1/31/2014	10:34	8.30	1.839	1.40	3.31	7.77	76.0	232.6	10.0	Purged 10 liters at 3 cycles per minute with bladder pump. Water started slightly yellowish brown and cleared quickly. Sample water was clear with no sheen or odor.
		10:37	9.69	1.952	1.44	1.06	7.48	25.8	195.4		
		10:40	9.45	1.948	1.44	0.72	7.38	2.7	104.8		
		10:43	9.44	1.948	1.44	0.58	7.34	-10.6	94.7		
		10:46	9.48	1.960	1.45	0.52	7.31	-18.9	70.8		
		10:48	9.51	1.971	1.46	0.48	7.29	-25.2	60.3		
		10:51	9.56	1.991	1.48	0.45	7.27	-30.1	50.4		
		10:55	9.63	2.001	1.48	0.44	7.27	-35.1	46.9		
		10:58	9.70	2.012	1.48	0.42	7.25	-38.3	36.8		
		11:01	9.70	2.017	1.49	0.41	7.23	-39.8	32.1		
		11:04	9.72	2.027	1.49	0.38	7.21	-42.0	29.5		
9/1/2016	NM	NM	NM	NM	NM	NM	NM	NM	-	Well was not sampled during this event.	

Field parameters collected during purging using a YSI 6920 with flow thru cell.

Field parameters recorded after every liter of purge.

NM - Not Measured



Table 3: (Page 7 of 8) Groundwater Field Parameter Data. Celi Drive BCP Site, Syracuse, NY.

Well I.D.	Date	Time	Temp (°C)	Conductivity (mmhos/cm)	Salinity (%)	Dissolved Oxygen (mg/L)	pH (units)	ORP (mV)	Turbidity (NTU)	Amount Purged (liters)	Comments
MW-7	1/31/2014	9:12	8.29	1.627	1.23	2.92	7.44	56.6	842.7	13.0	Purged 13 liters at 3 cycles per minute with bladder pump. Water started cloudy brown with little sediment and cleared quickly. Sample water was clear with no sheen or odor.
		9:16	9.40	1.708	1.26	0.95	7.27	-1.4	419.0		
		9:19	8.86	1.683	1.26	0.68	7.27	-19.5	224.4		
		9:23	8.86	1.687	1.26	0.56	7.24	-33.4	169.0		
		9:26	8.93	1.659	1.24	0.56	7.24	-39.4	122.2		
		9:29	8.95	1.638	1.22	0.49	7.24	-43.0	102.2		
		9:32	8.97	1.625	1.21	0.46	7.23	-47.5	92.6		
		9:35	9.10	1.610	1.19	0.43	7.23	-50.6	82.3		
		9:38	9.10	1.599	1.18	0.41	7.23	-52.9	74.4		
		9:41	9.12	1.588	1.18	0.40	7.23	-55.3	62.8		
		9:44	9.15	1.580	1.17	0.38	7.23	-57.0	54.0		
		9:48	9.19	1.576	1.16	0.38	7.23	-58.6	48.1		
	9:51	9.19	1.568	1.16	0.36	7.23	-59.9	48.9			
	9:54	9.21	1.564	1.15	0.36	7.22	-61.2	41.6			
	9/1/2016	9:03	20.41	1.590	0.89	2.77	7.24	-72.6	55.6	11.0	Purged 11 liters with peristaltic pump. Water clear with lots of black floaters at start, floaters decreased with purge, sample water clear, petroleum like sheen, no odor.
		9:05	19.36	1.518	0.86	0.67	7.09	-87.5	49.7		
		9:07	19.74	1.506	0.85	0.43	7.15	-91.2	50.8		
		9:08	20.25	1.517	0.85	0.35	6.97	-94.1	53.5		
		9:09	20.78	1.540	0.85	0.29	6.94	-96.7	43.9		
9:10		21.09	1.561	0.85	0.28	7.01	-98.3	40.1			
9:12		21.30	1.580	0.86	0.27	6.94	-100.2	41.9			
9:14		21.31	1.595	0.87	0.27	6.93	-99.6	42.9			
9:15		21.29	1.609	0.88	0.27	6.99	-98.5	39.2			
9:17		21.28	1.627	0.89	0.26	6.94	-99.9	34.0			
9:19	21.17	1.649	0.90	0.28	6.93	-99.6	23.6				
9:21	21.09	1.669	0.92	0.24	6.98	-99.7	15.1				

Field parameters collected during purging using a YSI 6920 with flow thru cell.

Field parameters recorded after every liter of purge.

NM - Not Measured





Table 3: (Page 8 of 8) Groundwater Field Parameter Data. Celi Drive BCP Site, Syracuse, NY.

Well I.D.	Date	Time	Temp (°C)	Conductivity (mmhos/cm)	Salinity (%)	Dissolved Oxygen (mg/L)	pH (units)	ORP (mV)	Turbidity (NTU)	Amount Purged (liters)	Comments
MW-8	1/31/2014	NM	NM	NM	NM	NM	NM	NM	NM	-	Well could not be located to be sampled.
	9/1/2016	12:36	19.24	1.336	0.76	4.91	7.63	-48.9	1395.8	15.0	Purged 15 liters with peristaltic pump. Water turbid at first with very fine sediment. Cleared with purge. Sample water clear with no sheen and no odor.
		12:39	16.61	1.264	0.76	2.56	7.41	-52.6	569.0		
		12:42	16.90	1.254	0.75	2.14	7.38	-51.1	291.7		
		12:43	16.89	1.248	0.75	2.01	7.22	-50.5	221.4		
		12:45	16.95	1.255	0.75	1.82	7.03	-50.8	113.8		
		12:48	16.78	1.260	0.76	1.62	7.03	-51.9	91.6		
		12:54	16.64	1.262	0.76	1.02	7.00	-54.9	44.2		
		12:56	16.53	1.258	0.76	1.04	6.98	-56.8	91.2		
		12:57	16.58	1.257	0.76	1.50	6.99	-57.7	70.5		
		12:59	16.78	1.259	0.75	1.42	6.97	-58.6	57.5		
		13:01	16.69	1.261	0.76	1.23	6.95	-58.6	25.7		
		13:03	16.64	1.258	0.76	1.15	6.96	-58.8	36.5		
13:05	16.64	1.260	0.76	1.09	6.97	-58.9	28.8				

Field parameters collected during purging using a YSI 6920 with flow thru cell.

Field parameters recorded after every liter of purge.

NM - Not Measured



Table 4: (Page 1 of 14) Summary of Groundwater Laboratory Analytical Results. Celi Drive BCP Site, Syracuse, NY.

Analyte	GW Std (ug/L)	Sample Identification						D.L.	R.L.
		MW-1							
Date Sampled		Aug-05*	Mar-10*	Jan-14		Sep-16			
<b>Metals by EPA Method 6010C</b>									
Aluminum		-	-	-				U	200
Antimony	3	-	-	-				U	20
Arsenic	25	-	-	-				U	15
Barium	1,000	-	-	-			<b>1,300</b>		2
Beryllium	3 (G)	-	-	-				U	2
Cadmium	5	-	-	-				U	2
Calcium		-	-	-			190,000		500
Chromium, total	50	U	U	2.3	J	1		U	4
Cobalt		-	-	-				U	4
Copper	200	U	U	4.4	J^B	1.6		U	10
Iron	300	-	-	-			<b>6,300</b>		50
Lead	25	-	-	-				U	10
Magnesium	35,000 (G)	-	-	-			<b>50,800</b>		200
Manganese	300	-	-	-			54		3
Nickel	100	U	1.4	J	3.8	J	1.3	U	10
Potassium		-	-	-			5,200		500
Selenium	10	-	-	-				U	25
Silver	50	-	-	-				U	6
Sodium	20,000	-	-	-			<b>215,000</b>		1000
Thallium	0.5 (G)	-	-	-				U	20
Vanadium		-	-	-				U	5
Zinc	2,000 (G)	U	9.4	J	7.7	JB	1.5	U	10
<b>Hexavalent Chromium by EPA Method 7196A</b>									
Chromium, hexavalent	50	11		U		U	5	UJ	100
<b>Mercury by EPA Method 7470A</b>									
Mercury	0.7	-	-	-				U	0.2
<b>Cyanide by EPA Method 9012</b>									
Cyanide	200	U		U		U	5	U	10

All values reported as ug/L

GW Std - Class GA Groundwater Quality Standard or Guidance Value from New York State Department of Environmental Conservation (NYSDEC) Division of Water Technical and Operational Guidance Series (June 1998).

(G) - Guidance value

\* - Historic samples taken by ERM

U - Analyzed for but Not Detected

J - Indicates an estimated value

B - Compound was found in the blank and sample

^ - Instrument related QC exceeds the control limits

NS - Not sampled during sampling event

D.L. - Laboratory Detection Limit

R.L. - Laboratory Reporting Limit

**Bold and boxed results indicate an exceedance of Groundwater Standards**



Table 4: (Page 2 of 14) Summary of Groundwater Laboratory Analytical Results. Celi Drive BCP Site, Syracuse, NY.

Analyte	GW Std (ug/L)	Sample Identification						D.L.	R.L.	
		MW-2								
Date Sampled		Aug-05*	Mar-10*	Jan-14	Sep-16					
<b>Metals by EPA Method 6010C</b>										
Aluminum		-	-	-				5,000	200	
Antimony	3	-	-	-				U	20	
Arsenic	25	-	-	-				U	15	
Barium	1,000	-	-	-			430		2	
Beryllium	3 (G)	-	-	-				U	2	
Cadmium	5	-	-	-				U	2	
Calcium		-	-	-			291,000		500	
Chromium, total	50	U	2.4	J	3.7	J	1	10	4	
Cobalt		-	-	-				U	4	
Copper	200	3.6		U	4.1	JB	1.6	11	10	
Iron	300	-	-	-				<b>15,300</b>	50	
Lead	25	-	-	-				12	10	
Magnesium	35,000 (G)	-	-	-				<b>101,000</b>	200	
Manganese	300	-	-	-				<b>600</b>	3	
Nickel	100	5.9	8.4		7.8	J	1.3	18	10	
Potassium		-	-	-				6,800	500	
Selenium	10	-	-	-				U	25	
Silver	50	-	-	-				U	6	
Sodium	20,000	-	-	-				<b>200,000</b>	1000	
Thallium	0.5 (G)	-	-	-				U	20	
Vanadium		-	-	-				13	5	
Zinc	2,000 (G)	U	10.4	J	6.4	JB	1.5	16	10	
<b>Hexavalent Chromium by EPA Method 7196A</b>										
Chromium, hexavalent	50	9		U		U	5		U	10
<b>Mercury by EPA Method 7470A</b>										
Mercury	0.7	-	-	-					U	0.2
<b>Cyanide by EPA Method 9012</b>										
Cyanide	200	U	3.56	J		U	5		U	10

All values reported as ug/L

GW Std - Class GA Groundwater Quality Standard or Guidance Value from New York State Department of Environmental Conservation (NYSDEC) Division of Water Technical and Operational Guidance Series (June 1998).

(G) - Guidance value

\* - Historic samples taken by ERM

U - Analyzed for but Not Detected

J - Indicates an estimated value

B - Compound was found in the blank and sample

^ - Instrument related QC exceeds the control limits

NS - Not sampled during sampling event

D.L. - Laboratory Detection Limit

R.L. - Laboratory Reporting Limit

**Bold and boxed results indicate an exceedance of Groundwater Standards**



Table 4: (Page 3 of 14) Summary of Groundwater Laboratory Analytical Results. Celi Drive BCP Site, Syracuse, NY.

Analyte	GW Std (ug/L)	Sample Identification						D.L.	R.L.
		MW-3							
Date Sampled		Aug-05*	Mar-10*	Jan-14			Sep-16		
<b>Metals by EPA Method 6010C</b>									
Aluminum		-	-	-				U	200
Antimony	3	-	-	-				U	20
Arsenic	25	-	-	-				U	15
Barium	1,000	-	-	-			220		2
Beryllium	3 (G)	-	-	-				U	2
Cadmium	5	-	-	-				U	2
Calcium		-	-	-			219,000		500
Chromium, total	50	U	U	5.1		1		U	4
Cobalt		-	-	-				U	4
Copper	200	U	4.1	J	10	B	1.6	U	10
Iron	300	-	-	-			<b>7,400</b>		50
Lead	25	-	-	-				U	10
Magnesium	35,000 (G)	-	-	-			<b>54,400</b>		200
Manganese	300	-	-	-			<b>1,200</b>		3
Nickel	100	4.7	<b>102</b>	<b>120</b>		1.3	<b>160</b>		10
Potassium		-	-	-			3,400		500
Selenium	10	-	-	-				U	25
Silver	50	-	-	-				U	6
Sodium	20,000	-	-	-			<b>211,000</b>		1000
Thallium	0.5 (G)	-	-	-				U	20
Vanadium		-	-	-				U	5
Zinc	2,000 (G)	U	11.8	J	12	B	1.5	U	10
<b>Hexavalent Chromium by EPA Method 7196A</b>									
Chromium, hexavalent	50	14		U		U	5	U	10
<b>Mercury by EPA Method 7470A</b>									
Mercury	0.7	-	-	-				U	0.2
<b>Cyanide by EPA Method 9012</b>									
Cyanide	200	U	3.71	J		UJ	5	U	10

All values reported as ug/L

GW Std - Class GA Groundwater Quality Standard or Guidance Value from New York State Department of Environmental Conservation (NYSDEC) Division of Water Technical and Operational Guidance Series (June 1998).

(G) - Guidance value

\* - Historic samples taken by ERM

U - Analyzed for but Not Detected

J - Indicates an estimated value

B - Compound was found in the blank and sample

^ - Instrument related QC exceeds the control limits

NS - Not sampled during sampling event

D.L. - Laboratory Detection Limit

R.L. - Laboratory Reporting Limit

**Bold and boxed results indicate an exceedance of Groundwater Standards**



Table 4: (Page 4 of 14) Summary of Groundwater Laboratory Analytical Results. Celi Drive BCP Site, Syracuse, NY.

Analyte	GW Std (ug/L)	Sample Identification				
		MW-4				
Date Sampled		Mar-10*	Jan-14		Sep-16	
<b>Metals by EPA Method 6010C</b>				D.L.		R.L.
Aluminum		-	-		480	200
Antimony	3	-	-			U 20
Arsenic	25	-	-			U 15
Barium	1,000	-	-		<b>1,400</b>	2
Beryllium	3 (G)	-	-			U 2
Cadmium	5	-	-			U 2
Calcium		-	-		205,000	500
Chromium, total	50	10	29	1	5.4	4
Cobalt		-	-			U 4
Copper	200	22.6	93	B 1.6	34	10
Iron	300	-	-		<b>4,200</b>	50
Lead	25	-	-			U 10
Magnesium	35,000 (G)	-	-		32,500	200
Manganese	300	-	-		<b>500</b>	3
Nickel	100	<b>237</b>	<b>340</b>	1.3	<b>680</b>	10
Potassium		-	-		6,300	500
Selenium	10	-	-			U 25
Silver	50	-	-			U 6
Sodium	20,000	-	-		<b>258,000</b>	1000
Thallium	0.5 (G)	-	-			U 20
Vanadium		-	-			U 5
Zinc	2,000 (G)	22	23	B 1.5		U 10
<b>Hexavalent Chromium by EPA Method 7196A</b>						
Chromium, hexavalent	50	U	U	5		U 10
<b>Mercury by EPA Method 7470A</b>						
Mercury	0.7	-	-			U 0.2
<b>Cyanide by EPA Method 9012</b>						
Cyanide	200	U	U	5		U 10

All values reported as ug/L

GW Std - Class GA Groundwater Quality Standard or Guidance Value from New York State Department of Environmental Conservation (NYSDEC) Division of Water Technical and Operational Guidance Series (June 1998).

(G) - Guidance value

\* - Historic samples taken by ERM

U - Analyzed for but Not Detected

J - Indicates an estimated value

B - Compound was found in the blank and sample

^ - Instrument related QC exceeds the control limits

NS - Not sampled during sampling event

D.L. - Laboratory Detection Limit

R.L. - Laboratory Reporting Limit

**Bold and boxed results indicate an exceedance of Groundwater Standards**



Table 4: (Page 5 of 14) Summary of Groundwater Laboratory Analytical Results. Celi Drive BCP Site, Syracuse, NY.

Analyte	GW Std (ug/L)	Sample Identification					
		MW-5					
Date Sampled		Mar-10*		Jan-14		Sep-16	
<b>Metals by EPA Method 6010C</b>						<b>D.L.</b>	<b>R.L.</b>
Aluminum		-	-			710	200
Antimony	3	-	-				U 20
Arsenic	25	-	-			22	15
Barium	1,000	-	-			91	2
Beryllium	3 (G)	-	-				U 2
Cadmium	5	-	-				U 2
Calcium		-	-			112,000	500
Chromium, total	50		U 10		1		U 4
Cobalt		-	-				U 4
Copper	200		U 11	B	1.6		U 10
Iron	300	-	-			<b>3,600</b>	50
Lead	25	-	-				U 10
Magnesium	35,000 (G)	-	-			28,500	200
Manganese	300	-	-			69	3
Nickel	100	3.1	J	12		1.3	U 10
Potassium		-	-			4,000	500
Selenium	10	-	-				U 25
Silver	50	-	-				U 6
Sodium	20,000	-	-			<b>319,000</b>	1000
Thallium	0.5 (G)	-	-				U 20
Vanadium		-	-				U 5
Zinc	2,000 (G)	11.9	J	18	B	1.5	U 10
<b>Hexavalent Chromium by EPA Method 7196A</b>							
Chromium, hexavalent	50	10	J		U 5		U 10
<b>Mercury by EPA Method 7470A</b>							
Mercury	0.7	-	-				U 0.2
<b>Cyanide by EPA Method 9012</b>							
Cyanide	200		U		U 5		U 10

All values reported as ug/L

GW Std - Class GA Groundwater Quality Standard or Guidance Value from New York State Department of Environmental Conservation (NYSDEC) Division of Water Technical and Operational Guidance Series (June 1998).

(G) - Guidance value

\* - Historic samples taken by ERM

U - Analyzed for but Not Detected

J - Indicates an estimated value

B - Compound was found in the blank and sample

^ - Instrument related QC exceeds the control limits

NS - Not sampled during sampling event

D.L. - Laboratory Detection Limit

R.L. - Laboratory Reporting Limit

**Bold and boxed results indicate an exceedance of Groundwater Standards**



Table 4: (Page 6 of 14) Summary of Groundwater Laboratory Analytical Results. Celi Drive BCP Site, Syracuse, NY.

Analyte	GW Std (ug/L)	Sample Identification				
		MW-6				
Date Sampled		Mar-10*	Jan-14	Sep-16		
<b>Metals by EPA Method 6010C</b>					D.L.	R.L.
Aluminum		-	-			NS
Antimony	3	-	-			NS
Arsenic	25	-	-			NS
Barium	1,000	-	-			NS
Beryllium	3 (G)	-	-			NS
Cadmium	5	-	-			NS
Calcium		-	-			NS
Chromium, total	50	U	2.0	J	1	NS
Cobalt		-	-			NS
Copper	200	U	3.4	JB	1.6	NS
Iron	300	-	-			NS
Lead	25	-	-			NS
Magnesium	35,000 (G)	-	-			NS
Manganese	300	-	-			NS
Nickel	100	10	3.9	J	1.3	NS
Potassium		-	-			NS
Selenium	10	-	-			NS
Silver	50	-	-			NS
Sodium	20,000	-	-			NS
Thallium	0.5 (G)	-	-			NS
Vanadium		-	-			NS
Zinc	2,000 (G)	11.4	J	7.0	JB	1.5
<b>Hexavalent Chromium by EPA Method 7196A</b>						
Chromium, hexavalent	50	U		U	5	NS
<b>Mercury by EPA Method 7470A</b>						
Mercury	0.7	-	-			NS
<b>Cyanide by EPA Method 9012</b>						
Cyanide	200	U		U	5	NS

All values reported as ug/L

GW Std - Class GA Groundwater Quality Standard or Guidance Value from New York State Department of Environmental Conservation (NYSDEC) Division of Water Technical and Operational Guidance Series (June 1998).

(G) - Guidance value

\* - Historic samples taken by ERM

U - Analyzed for but Not Detected

J - Indicates an estimated value

B - Compound was found in the blank and sample

^ - Instrument related QC exceeds the control limits

NS - Not sampled during sampling event

D.L. - Laboratory Detection Limit

R.L. - Laboratory Reporting Limit

**Bold and boxed results indicate an exceedance of Groundwater Standards**



Table 4: (Page 7 of 14) Summary of Groundwater Laboratory Analytical Results. Celi Drive BCP Site, Syracuse, NY.

Analyte	GW Std (ug/L)	Sample Identification					R.L.	
		MW-7						
Date Sampled		Mar-10*	Jan-14		Sep-16			
<b>Metals by EPA Method 6010C</b>					D.L.			
Aluminum		-	-			U	200	
Antimony	3	-	-			U	20	
Arsenic	25	-	-			<b>63</b>	15	
Barium	1,000	-	-			490	2	
Beryllium	3 (G)	-	-			U	2	
Cadmium	5	-	-			U	2	
Calcium		-	-			143,000	500	
Chromium, total	50	U	3.1	J	1	U	4	
Cobalt		-	-			U	4	
Copper	200	U	5.7	JB	1.6	U	10	
Iron	300	-	-			<b>13,000</b>	50	
Lead	25	-	-			U	10	
Magnesium	35,000 (G)	-	-			28,400	200	
Manganese	300	-	-			<b>370</b>	3	
Nickel	100	1.8	J	4.5	J	1.3	U	10
Potassium		-	-			10,900	500	
Selenium	10	-	-			U	25	
Silver	50	-	-			U	6	
Sodium	20,000	-	-			<b>241,000</b>	1000	
Thallium	0.5 (G)	-	-			U	20	
Vanadium		-	-			U	5	
Zinc	2,000 (G)	13.8	J	11	B	1.5	10	
<b>Hexavalent Chromium by EPA Method 7196A</b>								
Chromium, hexavalent	50	U		UJ	5	U	10	
<b>Mercury by EPA Method 7470A</b>								
Mercury	0.7	-	-			U	0.2	
<b>Cyanide by EPA Method 9012</b>								
Cyanide	200	7.77		U	5	U	10	

All values reported as ug/L

GW Std - Class GA Groundwater Quality Standard or Guidance Value from New York State Department of Environmental Conservation (NYSDEC) Division of Water Technical and Operational Guidance Series (June 1998).

(G) - Guidance value

\* - Historic samples taken by ERM

U - Analyzed for but Not Detected

J - Indicates an estimated value

B - Compound was found in the blank and sample

^ - Instrument related QC exceeds the control limits

NS - Not sampled during sampling event

D.L. - Laboratory Detection Limit

R.L. - Laboratory Reporting Limit

**Bold and boxed results indicate an exceedance of Groundwater Standards**





Table 4: (Page 8 of 14) Summary of Groundwater Laboratory Analytical Results. Celi Drive BCP Site, Syracuse, NY.

Analyte	GW Std (ug/L)	Sample Identification				
		MW-8				
Date Sampled		Mar-10*	Jan-14	Sep-16		
<b>Metals by EPA Method 6010C</b>					D.L.	R.L.
Aluminum		-	-		1,000	200
Antimony	3	-	-			U 20
Arsenic	25	-	-			U 15
Barium	1,000	-	-		270	2
Beryllium	3 (G)	-	-			U 2
Cadmium	5	-	-			U 2
Calcium		-	-		215,000	500
Chromium, total	50		U NS			U 4
Cobalt		-	-			U 4
Copper	200		U NS			U 10
Iron	300	-	-		<b>7,600</b>	50
Lead	25	-	-			U 10
Magnesium	35,000 (G)	-	-		<b>51,200</b>	200
Manganese	300	-	-		210	3
Nickel	100	4.2	J NS			U 10
Potassium		-	-		2,600	500
Selenium	10	-	-			U 25
Silver	50	-	-			U 6
Sodium	20,000	-	-		<b>94,500</b>	1000
Thallium	0.5 (G)	-	-			U 20
Vanadium		-	-			U 5
Zinc	2,000 (G)	14.5	NS			U 10
<b>Hexavalent Chromium by EPA Method 7196A</b>						
Chromium, hexavalent	50		U NS			U 10
<b>Mercury by EPA Method 7470A</b>						
Mercury	0.7	-	-			U 0.2
<b>Cyanide by EPA Method 9012</b>						
Cyanide	200	4.1	J NS			U 10

All values reported as ug/L

GW Std - Class GA Groundwater Quality Standard or Guidance Value from New York State Department of Environmental Conservation (NYSDEC) Division of Water Technical and Operational Guidance Series (June 1998).

(G) - Guidance value

\* - Historic samples taken by ERM

U - Analyzed for but Not Detected

J - Indicates an estimated value

B - Compound was found in the blank and sample

^ - Instrument related QC exceeds the control limits

NS - Not sampled during sampling event

D.L. - Laboratory Detection Limit

R.L. - Laboratory Reporting Limit

**Bold and boxed results indicate an exceedance of Groundwater Standards**



Table 4: (Page 9 of 14) Summary of Groundwater Laboratory Analytical Results. Celi Drive BCP Site, Syracuse, NY.

Analyte	GW Std (ug/L)	Sample Identification							
		Duplicate							
		Aug-05* (MW-1)		Jan-14 (MW-3)			Sep-16 (MW-3)		
		D.L.	RPD	D.L.	RPD	R.L.	RPD		
<b>Metals by EPA Method 6010C</b>									
Aluminum		-	-	-	-	U	200	N/A	
Antimony	3	-	-	-	-	U	20	N/A	
Arsenic	25	-	-	-	-	U	15	N/A	
Barium	1,000	-	-	-	220	U	2	0.00%	
Beryllium	3 (G)	-	-	-	-	U	2	N/A	
Cadmium	5	-	-	-	-	U	2	N/A	
Calcium		-	-	-	219,000	U	500	0.00%	
Chromium, total	50	U	4.7	1	8.16%	U	4	N/A	
Cobalt		-	-	-	-	U	4	N/A	
Copper	200	U	9.6	JB	1.6	4.08%	U	10	N/A
Iron	300	-	-	-	-	<b>7,400</b>	50	0.00%	
Lead	25	-	-	-	-	U	10	N/A	
Magnesium	35,000 (G)	-	-	-	-	<b>54,300</b>	200	0.18%	
Manganese	300	-	-	-	-	<b>1,200</b>	3	0.00%	
Nickel	100	U	<b>120</b>	1.3	0.00%	<b>160</b>	10	0.00%	
Potassium		-	-	-	-	3,500	500	2.90%	
Selenium	10	-	-	-	-	U	25	N/A	
Silver	50	-	-	-	-	U	6	N/A	
Sodium	20,000	-	-	-	-	<b>213,000</b>	1000	0.94%	
Thallium	0.5 (G)	-	-	-	-	U	20	N/A	
Vanadium		-	-	-	-	U	5	N/A	
Zinc	2,000 (G)	U	9.8	JB	1.5	20.18%	U	10	N/A
<b>Hexavalent Chromium by EPA Method 7196A</b>									
Chromium, hexavalent	50	10		UJ	5	N/A	U	10	N/A
<b>Mercury by EPA Method 7470A</b>									
Mercury	0.7	-	-	-	-	U	0.2	N/A	
<b>Cyanide by EPA Method 9012</b>									
Cyanide	200	U		U	5	N/A	U	10	N/A

All values reported as ug/L

GW Std - Class GA Groundwater Quality Standard or Guidance Value from New York State Department of Environmental Conservation (NYSDEC) Division of Water Technical and Operational Guidance Series (June 1998).

(G) - Guidance value

\* - Historic samples taken by ERM

U - Analyzed for but Not Detected

J - Indicates an estimated value

B - Compound was found in the blank and sample

^ - Instrument related QC exceeds the control limits

NS - Not sampled during sampling event

N/A - Not Applicable, analyte not detected in either parent sample or duplicate sample

D.L. - Laboratory Detection Limit

R.L. - Laboratory Reporting Limit

**Bold and boxed results indicate an exceedance of Groundwater Standards**



Table 4: (Page 10 of 14) Summary of Groundwater Laboratory Analytical Results. Celi Drive BCP Site, Syracuse, NY.

Analyte	GW Std (ug/L)	Sample Identification									
		MW-1		MW-2		MW-3		MW-4		MW-5	
Date Sampled		Sep-16		Sep-16		Sep-16		Sep-16		Sep-16	
			R.L.		R.L.		R.L.		R.L.		R.L.
<b>Polychlorinated Biphenyls by EPA Method 8082A</b>											
PCB-1016 (Aroclor 1016)		U	0.5	U	0.49	U	0.49	U	0.49	U	0.49
PCB-1221 (Aroclor 1221)		U	0.5	U	0.49	U	0.49	U	0.49	U	0.49
PCB-1232 (Aroclor 1232)		U	0.5	U	0.49	U	0.49	U	0.49	U	0.49
PCB-1242 (Aroclor 1242)		U	0.5	U	0.49	U	0.49	U	0.49	U	0.49
PCB-1248 (Aroclor 1248)		U	0.5	U	0.49	U	0.49	4.6	0.49	U	0.49
PCB-1254 (Aroclor 1254)		U	0.5	U	0.49	U	0.49	U	0.49	U	0.49
PCB-1260 (Aroclor 1260)		U	0.5	U	0.49	U	0.49	U	0.49	U	0.49
<b>Total PCBs</b>	0.09	ND		ND		ND		<b>4.6</b>		ND	

Analyte	GW Std (ug/L)	Sample Identification							
		MW-6		MW-7		MW-8		Duplicate	
Date Sampled		Sep-16		Sep-16		Sep-16		Sep-16 (MW-3)	
			R.L.		R.L.		R.L.		RPD
<b>Polychlorinated Biphenyls by EPA Method 8082A</b>									
PCB-1016 (Aroclor 1016)		NS		U	0.51	U	0.49	U	0.5 N/A
PCB-1221 (Aroclor 1221)		NS		U	0.51	U	0.49	U	0.5 N/A
PCB-1232 (Aroclor 1232)		NS		U	0.51	U	0.49	U	0.5 N/A
PCB-1242 (Aroclor 1242)		NS		U	0.51	U	0.49	U	0.5 N/A
PCB-1248 (Aroclor 1248)		NS		U	0.51	U	0.49	U	0.5 N/A
PCB-1254 (Aroclor 1254)		NS		U	0.51	U	0.49	U	0.5 N/A
PCB-1260 (Aroclor 1260)		NS		U	0.51	U	0.49	U	0.5 N/A
<b>Total PCBs</b>	0.09	NS		ND		ND		ND	N/A

All values reported as ug/L

GW Std - Class GA Groundwater Quality Standard or Guidance Value from New York State Department of Environmental Conservation (NYSDEC) Division of Water Technical and Operational Guidance Series (June 1998).

(G) - Guidance value

U - Analyzed for but Not Detected

J - Indicates an estimated value

NS - Not sampled during sampling event

ND - Not Detected above laboratory detection limits

N/A - Not Applicable, analyte not detected in either parent sample or duplicate sample

R.L. - Laboratory Reporting Limit

**Bold and boxed results indicate an exceedance of Groundwater Standards**



Table 4: (Page 11 of 14) Summary of Groundwater Laboratory Analytical Results. Celi Drive BCP Site, Syracuse, NY.

Date Sampled	Analyte	GW Std (ug/L)	Sample Identification									
			MW-1 Sep-16		MW-2 Sep-16		MW-3 Sep-16		MW-4 Sep-16		MW-5 Sep-16	
			R.L.	R.L.	R.L.	R.L.	R.L.	R.L.	R.L.	R.L.	R.L.	
	<b>Volatile Organic Compounds by EPA Method 8260C</b>											
	1,1,1-trichloroethane	5	U 1	U 1	U 1	U 1	U 1	U 1	U 1	U 1	U 1	
	1,1,2,2-tetrachloroethane	5	U 1	U 1	U 1	U 1	U 1	U 1	U 1	U 1	U 1	
	1,1,2-trichloro-1,2,2-trifluoroethane	5	U 1	U 1	U 1	U 1	U 1	U 1	U 1	U 1	U 1	
	1,1,2-trichloroethane	1	U 1	U 1	U 1	U 1	U 1	U 1	U 1	U 1	U 1	
	1,1-dichloroethane	5	U 1	U 1	U 1	U 1	U 1	U 1	U 1	U 1	U 1	
	1,1-dichloroethane	5	U 1	U 1	U 1	U 1	U 1	U 1	U 1	U 1	U 1	
	1,2,4-trichlorobenzene	5	U 1	U 1	U 1	U 1	U 1	U 1	U 1	U 1	U 1	
	1,2,4-trimethylbenzene	5	U 1	U 1	U 1	U 1	U 1	U 1	U 1	U 1	U 1	
	1,2-dibromo-3-chloropropane	0.04	U 1	U 1	U 1	U 1	U 1	U 1	U 1	U 1	U 1	
	1,2-dibromoethane (ethylene dibromide)	6.00E-04	U 1	U 1	U 1	U 1	U 1	U 1	U 1	U 1	U 1	
	1,2-dichlorobenzene	3	U 1	U 1	U 1	U 1	U 1	U 1	U 1	U 1	U 1	
	1,2-dichloroethane	0.6	U 1	U 1	U 1	U 1	U 1	U 1	U 1	U 1	U 1	
	1,2-dichloropropane	1	U 1	U 1	U 1	U 1	U 1	U 1	U 1	U 1	U 1	
	1,3,5-trimethylbenzene (mesitylene)	5	U 1	U 1	U 1	U 1	U 1	U 1	U 1	U 1	U 1	
	1,3-dichlorobenzene	3	U 1	U 1	U 1	U 1	U 1	U 1	U 1	U 1	U 1	
	1,4-dichlorobenzene	3	U 1	U 1	U 1	U 1	U 1	U 1	U 1	U 1	U 1	
	2-hexanone	50 (G)	U 5	U 5	U 5	U 5	U 5	U 5	U 5	U 5	U 5	
	Acetone	50 (G)	U 10	U 10	U 10	U 10	U 10	U 10	U 10	U 10	U 10	
	Benzene	1	U 1	U 1	U 1	U 1	U 1	U 1	U 1	U 1	U 1	
	Bromodichloromethane	50 (G)	U 1	U 1	U 1	U 1	U 1	U 1	U 1	U 1	U 1	
	Bromoform	50 (G)	U 1	U 1	U 1	U 1	U 1	U 1	U 1	U 1	U 1	
	Bromomethane	5	U 1	U 1	U 1	U 1	U 1	U 1	U 1	U 1	U 1	
	Carbon disulfide	60 (G)	U 1	U 1	U 1	U 1	U 1	U 1	U 1	U 1	U 1	
	Carbon tetrachloride	5	U 1	U 1	U 1	U 1	U 1	U 1	U 1	U 1	U 1	
	Chlorobenzene	5	U 1	U 1	U 1	U 1	U 1	U 1	U 1	U 1	U 1	
	Chloroethane	5	U 1	U 1	U 1	U 1	U 1	U 1	U 1	U 1	U 1	
	Chloroform	7	U 1	U 1	U 1	U 1	U 1	U 1	U 1	U 1	U 1	
	Chloromethane	5	U 1	U 1	U 1	U 1	U 1	U 1	U 1	U 1	U 1	
	cis-1,2-dichloroethylene	5	U 1	U 1	U 1	U 1	U 1	U 1	U 1	U 1	U 1	
	cis-1,3-dichloropropene	0.4*	U 1	U 1	U 1	U 1	U 1	U 1	U 1	U 1	U 1	
	Cyclohexane	U 1	U 1	U 1	U 1	U 1	U 1	U 1	U 1	U 1	U 1	
	Cymene	5	U 1	U 1	U 1	U 1	U 1	U 1	U 1	U 1	U 1	
	Dibromochloromethane	50 (G)	U 1	U 1	U 1	U 1	U 1	U 1	U 1	U 1	U 1	
	Dichlorodifluoromethane	5	U 1	U 1	U 1	U 1	U 1	U 1	U 1	U 1	U 1	
	Ethylbenzene	5	U 1	U 1	U 1	U 1	U 1	U 1	U 1	U 1	U 1	
	Isopropylbenzene (cumene)	5	U 1	U 1	U 1	U 1	U 1	U 1	U 1	U 1	U 1	
	Methyl acetate	U 1	U 2.5	U 2.5	U 2.5	U 2.5	U 2.5	U 2.5	U 2.5	U 2.5	U 2.5	
	Methyl ethyl ketone (2-butanone)	50 (G)	U 10	U 10	U 10	U 10	U 10	U 10	U 10	U 10	U 10	
	Methyl isobutyl ketone (4-methyl-2-pentanone)	U 5	U 5	U 5	U 5	U 5	U 5	U 5	U 5	U 5	U 5	
	Methylcyclohexane	U 1	U 1	U 1	U 1	U 1	U 1	U 1	U 1	U 1	U 1	
	Methylene chloride	5	U 1	U 1	U 1	U 1	U 1	U 1	U 1	U 1	U 1	
	Naphthalene	10 (G)	U 1	U 1	U 1	U 1	U 1	U 1	U 1	U 1	U 1	
	n-butylbenzene	5	U 1	U 1	U 1	U 1	U 1	U 1	U 1	U 1	U 1	
	n-propylbenzene	5	U 1	U 1	U 1	U 1	U 1	U 1	U 1	U 1	U 1	
	sec-butylbenzene	5	U 1	U 1	U 1	U 1	U 1	U 1	U 1	U 1	U 1	
	Styrene	5	U 1	U 1	U 1	U 1	U 1	U 1	U 1	U 1	U 1	
	t-butylbenzene	5	U 1	U 1	U 1	U 1	U 1	U 1	U 1	U 1	U 1	
	Tert-butyl methyl ether	10 (G)	U 1	U 1	U 1	U 1	U 1	U 1	U 1	U 1	U 1	
	Tetrachloroethylene (PCE)	5	U 1	U 1	U 1	U 1	U 1	U 1	U 1	U 1	U 1	
	Toluene	5	U 1	U 1	U 1	U 1	U 1	U 1	U 1	U 1	U 1	
	trans-1,2-dichloroethene	5	U 1	U 1	U 1	U 1	U 1	U 1	U 1	U 1	U 1	
	trans-1,3-dichloropropene	0.4*	U 1	U 1	U 1	U 1	U 1	U 1	U 1	U 1	U 1	
	Trichloroethylene (TCE)	5	U 1	U 1	U 1	U 1	U 1	U 1	U 1	U 1	U 1	
	Trichlorofluoromethane	5	U 1	U 1	U 1	U 1	U 1	U 1	U 1	U 1	U 1	
	Vinyl chloride	2	U 1	U 1	U 1	U 1	U 1	U 1	U 1	U 1	U 1	
	Xylenes, total	5	U 2	U 2	U 2	U 2	U 2	U 2	U 2	U 2	U 2	
	<b>Total VOCs</b>		ND	ND	ND	ND	ND	ND	ND	ND	ND	

All values reported as ug/L

GW Std - Class GA Groundwater Quality Standard or Guidance Value from New York State Department of Environmental Conservation (NYSDEC) Division of Water Technical and Operational Guidance Series (June 1998).

(G) - Guidance value

\* - applies to the sum of cis and trans

U - Analyzed for but Not Detected

J - Indicates an estimated value

NS - Not sampled during sampling event

ND - Not Detected above laboratory detection limits

R.L. - Laboratory Reporting Limit

**Bold and boxed results indicate an exceedance of Groundwater Standards**



Table 4: (Page 12 of 14) Summary of Groundwater Laboratory Analytical Results. Celi Drive BCP Site, Syracuse, NY.

Analyte	GW Std (ug/L)	Sample Identification					
		MW-6 Sep-16	MW-7 Sep-16	MW-8 Sep-16	Duplicate Sep-16 (MW-3)		
<b>Volatile Organic Compounds by EPA Method 8260C</b>		R.L.	R.L.	R.L.	R.L.	R.L.	RPD
1,1,1-trichloroethane	5	NS	U 1	U 1	U 1	U 1	N/A
1,1,2,2-tetrachloroethane	5	NS	U 1	U 1	U 1	U 1	N/A
1,1,2-trichloro-1,2,2-trifluoroethane	5	NS	U 1	U 1	U 1	U 1	N/A
1,1,2-trichloroethane	1	NS	U 1	U 1	U 1	U 1	N/A
1,1-dichloroethane	5	NS	U 1	U 1	U 1	U 1	N/A
1,1-dichloroethene	5	NS	U 1	U 1	U 1	U 1	N/A
1,2,4-trichlorobenzene	5	NS	U 1	U 1	U 1	U 1	N/A
1,2,4-trimethylbenzene	5	NS	U 1	U 1	U 1	U 1	N/A
1,2-dibromo-3-chloropropane	0.04	NS	U 1	U 1	U 1	U 1	N/A
1,2-dibromoethane (ethylene dibromide)	6.00E-04	NS	U 1	U 1	U 1	U 1	N/A
1,2-dichlorobenzene	3	NS	U 1	U 1	U 1	U 1	N/A
1,2-dichloroethane	0.6	NS	U 1	U 1	U 1	U 1	N/A
1,2-dichloropropane	1	NS	U 1	U 1	U 1	U 1	N/A
1,3,5-trimethylbenzene (mesitylene)	5	NS	U 1	U 1	U 1	U 1	N/A
1,3-dichlorobenzene	3	NS	U 1	U 1	U 1	U 1	N/A
1,4-dichlorobenzene	3	NS	U 1	U 1	U 1	U 1	N/A
2-hexanone	50 (G)	NS	U 5	U 5	U 5	U 5	N/A
Acetone	50 (G)	NS	U 10	U 10	U 10	U 10	N/A
Benzene	1	NS	U 1	U 1	U 1	U 1	N/A
Bromodichloromethane	50 (G)	NS	U 1	U 1	U 1	U 1	N/A
Bromoform	50 (G)	NS	U 1	U 1	U 1	U 1	N/A
Bromomethane	5	NS	U 1	U 1	U 1	U 1	N/A
Carbon disulfide	60 (G)	NS	U 1	U 1	U 1	U 1	N/A
Carbon tetrachloride	5	NS	U 1	U 1	U 1	U 1	N/A
Chlorobenzene	5	NS	U 1	U 1	U 1	U 1	N/A
Chloroethane	5	NS	U 1	U 1	U 1	U 1	N/A
Chloroform	7	NS	U 1	U 1	U 1	U 1	N/A
Chloromethane	5	NS	U 1	U 1	U 1	U 1	N/A
cis-1,2-dichloroethylene	5	NS	U 1	U 1	U 1	U 1	N/A
cis-1,3-dichloropropene	0.4*	NS	U 1	U 1	U 1	U 1	N/A
Cyclohexane		NS	U 1	U 1	U 1	U 1	N/A
Cymene	5	NS	U 1	U 1	U 1	U 1	N/A
Dibromochloromethane	50 (G)	NS	U 1	U 1	U 1	U 1	N/A
Dichlorodifluoromethane	5	NS	U 1	U 1	U 1	U 1	N/A
Ethylbenzene	5	NS	U 1	U 1	U 1	U 1	N/A
Isopropylbenzene (cumene)	5	NS	U 1	U 1	U 1	U 1	N/A
Methyl acetate		NS	U 2.5	U 2.5	U 2.5	U 2.5	N/A
Methyl ethyl ketone (2-butanone)	50 (G)	NS	U 10	U 10	U 10	U 10	N/A
Methyl isobutyl ketone (4-methyl-2-pentanone)		NS	U 5	U 5	U 5	U 5	N/A
Methylcyclohexane		NS	U 1	U 1	U 1	U 1	N/A
Methylene chloride	5	NS	U 1	U 1	U 1	U 1	N/A
Naphthalene	10 (G)	NS	U 1	U 1	U 1	U 1	N/A
n-butylbenzene	5	NS	U 1	U 1	U 1	U 1	N/A
n-propylbenzene	5	NS	U 1	U 1	U 1	U 1	N/A
sec-butylbenzene	5	NS	U 1	U 1	U 1	U 1	N/A
Styrene	5	NS	U 1	U 1	U 1	U 1	N/A
t-butylbenzene	5	NS	U 1	U 1	U 1	U 1	N/A
Tert-butyl methyl ether	10 (G)	NS	1.2	U 1	U 1	U 1	N/A
Tetrachloroethylene(PCE)	5	NS	U 1	U 1	U 1	U 1	N/A
Toluene	5	NS	U 1	U 1	U 1	U 1	N/A
trans-1,2-dichloroethene	5	NS	U 1	U 1	U 1	U 1	N/A
trans-1,3-dichloropropene	0.4*	NS	U 1	U 1	U 1	U 1	N/A
Trichloroethylene (TCE)	5	NS	U 1	U 1	U 1	U 1	N/A
Trichlorofluoromethane	5	NS	U 1	U 1	U 1	U 1	N/A
Vinyl chloride	2	NS	U 1	U 1	U 1	U 1	N/A
Xylenes, total	5	NS	U 2	U 2	U 2	U 2	N/A
<b>Total VOCs</b>		NS	1.20	ND	ND	ND	N/A

All values reported as ug/L.

GW Std - Class GA Groundwater Quality Standard or Guidance Value from New York State Department of Environmental Conservation (NYSDEC) Division of Water Technical and Operational Guidance Series (June 1998).

(G) - Guidance value

\* - applies to the sum of cis and trans

U - Analyzed for but Not Detected

J - Indicates an estimated value

NS - Not sampled during sampling event

ND - Not Detected above laboratory detection limits

N/A - Not Applicable, analyte not detected in either parent sample or duplicate sample

R.L. - Laboratory Reporting Limit

**Bold and boxed results indicate an exceedance of Groundwater Standards**



Table 4: (Page 13 of 14) Summary of Groundwater Laboratory Analytical Results, Celi Drive BCP Site, Syracuse, NY.

Date Sampled	Analyte	GW Std (ug/L)	Sample Identification									
			MW-1 Sep-16		MW-2 Sep-16		MW-3 Sep-16		MW-4 Sep-16		MW-5 Sep-16	
				R.L.		R.L.		R.L.		R.L.		R.L.
	<b>Semi Volatile Organic Compounds by EPA Method 8270D</b>											
	2,4,5-trichlorophenol		U	5	U	5	U	4.8	U	4.9	U	4.8
	2,4,6-trichlorophenol		U	5	U	5	U	4.8	U	4.9	U	4.8
	2,4-dichlorophenol	5	U	5	U	5	U	4.8	U	4.9	U	4.8
	2,4-dimethylphenol	50 (G)	U	5	U	5	U	4.8	U	4.9	U	4.8
	2,4-dinitrophenol	10 (G)	UT	10	U	10	U	9.7	U	9.9	U	9.6
	2,4-dinitrotoluene	5	U	5	U	5	U	4.8	U	4.9	U	4.8
	2,6-dinitrotoluene	5	U	5	U	5	U	4.8	U	4.9	U	4.8
	2-chloronaphthalene	10 (G)	U	5	U	5	U	4.8	U	4.9	U	4.8
	2-chlorophenol		U	5	U	5	U	4.8	U	4.9	U	4.8
	2-methylnaphthalene		U	5	U	5	U	4.8	U	4.9	U	4.8
	2-methylphenol (o-cresol)		U	5	U	5	U	4.8	U	4.9	U	4.8
	2-nitroaniline	5	U	10	U	10	U	9.7	U	9.9	U	9.6
	2-nitrophenol		U	5	U	5	U	4.8	U	4.9	U	4.8
	3,3'-dichlorobenzidine	5	U	5	U	5	U	4.8	U	4.9	U	4.8
	3-nitroaniline	5	U	10	U	10	U	9.7	U	9.9	U	9.6
	4,6-dinitro-2-methylphenol		U	10	U	10	U	9.7	U	9.9	U	9.6
	4-bromophenyl phenyl ether		U	5	U	5	U	4.8	U	4.9	U	4.8
	4-chloro-3-methylphenol		U	5	U	5	U	4.8	U	4.9	U	4.8
	4-chloroaniline	5	U	5	U	5	U	4.8	U	4.9	U	4.8
	4-chlorophenyl phenyl ether		U	5	U	5	U	4.8	U	4.9	U	4.8
	4-methylphenol (p-cresol)		U	10	U	10	U	9.7	U	9.9	U	9.6
	4-nitroaniline	5	U	10	U	10	U	9.7	U	9.9	U	9.6
	4-nitrophenol		UT	10	U	10	U	9.7	U	9.9	U	9.6
	Acenaphthene	20 (G)	U	5	U	5	U	4.8	U	4.9	U	4.8
	Acenaphthylene		U	5	U	5	U	4.8	U	4.9	U	4.8
	Acetophenone		U	5	U	5	U	4.8	U	4.9	U	4.8
	Anthracene	50 (G)	U	5	U	5	U	4.8	U	4.9	U	4.8
	Atrazine	7.5	U	5	U	5	U	4.8	U	4.9	U	4.8
	Benzaldehyde		U	5	U	5	U	4.8	U	4.9	U	4.8
	Benzo(a)anthracene	0.002 (G)	U	5	U	5	U	4.8	U	4.9	U	4.8
	Benzo(a)pyrene	ND	U	5	U	5	U	4.8	U	4.9	U	4.8
	Benzo(b)fluoranthene	0.002 (G)	U	5	U	5	U	4.8	U	4.9	U	4.8
	Benzo(g,h,i)perylene		UJ	5	U	5	U	4.8	U	4.9	U	4.8
	Benzo(k)fluoranthene	0.002 (G)	U	5	U	5	U	4.8	U	4.9	U	4.8
	Benzyl butyl phthalate		U	5	U	5	U	4.8	U	4.9	U	4.8
	Biphenyl (diphenyl)		U	5	U	5	U	4.8	U	4.9	U	4.8
	bis(2-chloroethoxy) methane	5	U	5	U	5	U	4.8	U	4.9	U	4.8
	bis(2-chloroethyl) ether (2-chloroethyl ether)	1	U	5	U	5	U	4.8	U	4.9	U	4.8
	bis(2-chloroisopropyl) ether		U	5	U	5	U	4.8	U	4.9	U	4.8
	bis(2-ethylhexyl) phthalate	5	U	5	U	5	U	4.8	U	4.9	U	4.8
	Caprolactam		U	5	U	5	U	4.8	U	4.9	U	4.8
	Carbazole		U	5	U	5	U	4.8	U	4.9	U	4.8
	Chrysene	0.002 (G)	U	5	U	5	U	4.8	U	4.9	U	4.8
	Dibenz(a,h)anthracene		UJ	5	U	5	U	4.8	U	4.9	U	4.8
	Dibenzofuran		U	10	U	10	U	9.7	U	9.9	U	9.6
	Diethyl phthalate	50 (G)	U	5	U	5	U	4.8	U	4.9	U	4.8
	Dimethyl phthalate	50 (G)	U	5	U	5	U	4.8	U	4.9	U	4.8
	di-n-butyl phthalate		U	5	U	5	U	4.8	U	4.9	U	4.8
	di-n-octylphthalate	50 (G)	U	5	U	5	U	4.8	U	4.9	U	4.8
	Fluoranthene	50 (G)	U	5	U	5	U	4.8	U	4.9	U	4.8
	Fluorene	50 (G)	U	5	U	5	U	4.8	U	4.9	U	4.8
	Hexachlorobenzene	0.04	U	5	U	5	U	4.8	U	4.9	U	4.8
	Hexachlorobutadiene	0.5	U	5	U	5	U	4.8	U	4.9	U	4.8
	Hexachlorocyclopentadiene	5	U	5	U	5	U	4.8	U	4.9	U	4.8
	Hexachloroethane	5	U	5	U	5	U	4.8	U	4.9	U	4.8
	Indeno(1,2,3-c,d)pyrene	0.002 (G)	UJ	5	U	5	U	4.8	U	4.9	U	4.8
	Isophorone	50 (G)	U	5	U	5	U	4.8	U	4.9	U	4.8
	Naphthalene	10 (G)	U	5	U	5	U	4.8	U	4.9	U	4.8
	Nitrobenzene	0.4	U	5	U	5	U	4.8	U	4.9	U	4.8
	n-nitrosodi-n-propylamine		U	5	U	5	U	4.8	U	4.9	U	4.8
	n-nitrosodiphenylamine	50 (G)	U	5	U	5	U	4.8	U	4.9	U	4.8
	Pentachlorophenol	1	U	10	U	10	U	9.7	U	9.9	U	9.6
	Phenanthrene	50 (G)	U	5	U	5	U	4.8	U	4.9	U	4.8
	Phenol	1	U	5	U	5	U	4.8	U	4.9	U	4.8
	Pyrene	50 (G)	U	5	U	5	U	4.8	U	4.9	U	4.8
	<b>Total SVOCs</b>		ND		ND		ND		ND		ND	

All values reported as ug/L.

GW Std - Class GA Groundwater Quality Standard or Guidance Value from New York State Department of Environmental Conservation (NYSDEC) Division of Water Technical and Operational Guidance Series (June 1998).

(G) - Guidance value

U - Analyzed for but Not Detected

J - Indicates an estimated value

NS - Not sampled during sampling event

ND - Not Detected above laboratory detection limits

R.L. - Laboratory Reporting Limit

**Bold and boxed results indicate an exceedance of Groundwater Standards**



Table 4: (Page 14 of 14) Summary of Groundwater Laboratory Analytical Results. Celi Drive BCP Site, Syracuse, NY.

Date Sampled	Analyte	GW Std (ug/L)	Sample Identification					
			MW-6 Sep-16	MW-7 Sep-16	MW-8 Sep-16	Duplicate Sep-16 (MW-3)		
	<b>Semi Volatile Organic Compounds by EPA Method 8270D</b>		R.L.	R.L.	R.L.	R.L.	R.L.	RPD
	2,4,5-trichlorophenol		NS	U 5	U 4.9	U 4.9	U 4.9	N/A
	2,4,6-trichlorophenol		NS	U 5	U 4.9	U 4.9	U 4.9	N/A
	2,4-dichlorophenol	5	NS	U 5	U 4.9	U 4.9	U 4.9	N/A
	2,4-dimethylphenol	50 (G)	NS	U 5	U 4.9	U 4.9	U 4.9	N/A
	2,4-dinitrophenol	10 (G)	NS	U 10	U 9.8	U 9.9	U 9.9	N/A
	2,4-dinitrotoluene	5	NS	U 5	U 4.9	U 4.9	U 4.9	N/A
	2,6-dinitrotoluene	5	NS	U 5	U 4.9	U 4.9	U 4.9	N/A
	2-chloronaphthalene	10 (G)	NS	U 5	U 4.9	U 4.9	U 4.9	N/A
	2-chlorophenol		NS	U 5	U 4.9	U 4.9	U 4.9	N/A
	2-methylnaphthalene		NS	U 5	U 4.9	U 4.9	U 4.9	N/A
	2-methylphenol (o-cresol)		NS	U 5	U 4.9	U 4.9	U 4.9	N/A
	2-nitroaniline	5	NS	U 10	U 9.8	U 9.9	U 9.9	N/A
	2-nitrophenol		NS	U 5	U 4.9	U 4.9	U 4.9	N/A
	3,3-dichlorobenzidine	5	NS	U 5	U 4.9	U 4.9	U 4.9	N/A
	3-nitroaniline	5	NS	U 10	U 9.8	U 9.9	U 9.9	N/A
	4,6-dinitro-2-methylphenol		NS	U 10	U 9.8	U 9.9	U 9.9	N/A
	4-bromophenyl phenyl ether		NS	U 5	U 4.9	U 4.9	U 4.9	N/A
	4-chloro-3-methylphenol		NS	U 5	U 4.9	U 4.9	U 4.9	N/A
	4-chloroaniline	5	NS	U 5	U 4.9	U 4.9	U 4.9	N/A
	4-chlorophenyl phenyl ether		NS	U 5	U 4.9	U 4.9	U 4.9	N/A
	4-methylphenol (p-cresol)		NS	U 10	U 9.8	U 9.9	U 9.9	N/A
	4-nitroaniline	5	NS	U 10	U 9.8	U 9.9	U 9.9	N/A
	4-nitrophenol		NS	U 10	U 9.8	U 9.9	U 9.9	N/A
	acenaphthene	20 (G)	NS	U 5	U 4.9	U 4.9	U 4.9	N/A
	acenaphthylene		NS	U 5	U 4.9	U 4.9	U 4.9	N/A
	acetophenone		NS	U 5	U 4.9	U 4.9	U 4.9	N/A
	anthracene	50 (G)	NS	U 5	U 4.9	U 4.9	U 4.9	N/A
	atrazine	7.5	NS	U 5	U 4.9	U 4.9	U 4.9	N/A
	benzaldehyde		NS	U 5	U 4.9	U 4.9	U 4.9	N/A
	benzo(a)anthracene	0.002 (G)	NS	U 5	U 4.9	U 4.9	U 4.9	N/A
	benzo(a)pyrene	ND	NS	U 5	U 4.9	U 4.9	U 4.9	N/A
	benzo(b)fluoranthene	0.002 (G)	NS	U 5	U 4.9	U 4.9	U 4.9	N/A
	benzo(g,h,i)perylene		NS	U 5	U 4.9	U 4.9	U 4.9	N/A
	benzo(k)fluoranthene	0.002 (G)	NS	U 5	U 4.9	U 4.9	U 4.9	N/A
	benzyl butyl phthalate		NS	U 5	U 4.9	U 4.9	U 4.9	N/A
	biphenyl (diphenyl)		NS	U 5	U 4.9	U 4.9	U 4.9	N/A
	bis(2-chloroethoxy) methane	5	NS	U 5	U 4.9	U 4.9	U 4.9	N/A
	bis(2-chloroethyl) ether (2-chloroethyl ether)	1	NS	U 5	U 4.9	U 4.9	U 4.9	N/A
	bis(2-chloroisopropyl) ether		NS	U 5	U 4.9	U 4.9	U 4.9	N/A
	bis(2-ethylhexyl) phthalate	5	NS	U 5	U 4.9	U 4.9	U 4.9	N/A
	caprolactam		NS	U 5	U 4.9	U 4.9	U 4.9	N/A
	carbazole		NS	U 5	U 4.9	U 4.9	U 4.9	N/A
	chrysene	0.002 (G)	NS	U 5	U 4.9	U 4.9	U 4.9	N/A
	dibenz(a,h)anthracene		NS	U 5	U 4.9	U 4.9	U 4.9	N/A
	dibenzofuran		NS	U 10	U 9.8	U 9.9	U 9.9	N/A
	diethyl phthalate	50 (G)	NS	U 5	U 4.9	U 4.9	U 4.9	N/A
	dimethyl phthalate	50 (G)	NS	U 5	U 4.9	U 4.9	U 4.9	N/A
	di-n-butyl phthalate		NS	U 5	U 4.9	U 4.9	U 4.9	N/A
	di-n-octylphthalate	50 (G)	NS	U 5	U 4.9	U 4.9	U 4.9	N/A
	fluoranthene	50 (G)	NS	U 5	U 4.9	U 4.9	U 4.9	N/A
	fluorene	50 (G)	NS	U 5	U 4.9	U 4.9	U 4.9	N/A
	hexachlorobenzene	0.04	NS	U 5	U 4.9	U 4.9	U 4.9	N/A
	hexachlorobutadiene	0.5	NS	U 5	U 4.9	U 4.9	U 4.9	N/A
	hexachlorocyclopentadiene	5	NS	U 5	U 4.9	U 4.9	U 4.9	N/A
	hexachloroethane	5	NS	U 5	U 4.9	U 4.9	U 4.9	N/A
	indeno(1,2,3-c,d)pyrene	0.002 (G)	NS	U 5	U 4.9	U 4.9	U 4.9	N/A
	isophorone	50 (G)	NS	U 5	U 4.9	U 4.9	U 4.9	N/A
	naphthalene	10 (G)	NS	U 5	U 4.9	U 4.9	U 4.9	N/A
	nitrobenzene	0.4	NS	U 5	U 4.9	U 4.9	U 4.9	N/A
	n-nitrosodi-n-propylamine		NS	U 5	U 4.9	U 4.9	U 4.9	N/A
	n-nitrosodiphenylamine	50 (G)	NS	U 5	U 4.9	U 4.9	U 4.9	N/A
	pentachlorophenol	1	NS	U 10	U 9.8	U 9.9	U 9.9	N/A
	phenanthrene	50 (G)	NS	U 5	U 4.9	U 4.9	U 4.9	N/A
	phenol	1	NS	U 5	U 4.9	U 4.9	U 4.9	N/A
	pyrene	50 (G)	NS	U 5	U 4.9	U 4.9	U 4.9	N/A
	<b>Total SVOCs</b>		NS	ND	ND	ND	ND	N/A

All values reported as ug/L.

GW Std - Class GA Groundwater Quality Standard or Guidance Value from New York State Department of Environmental Conservation (NYSDEC) Division of Water Technical and Operational Guidance Series (June 1998).

(G) - Guidance value

U - Analyzed for but Not Detected

J - Indicates an estimated value

NS - Not sampled during sampling event

ND - Not Detected above laboratory detection limits

N/A - Not Applicable, analyte not detected in either parent sample or duplicate sample

R.L. - Laboratory Reporting Limit

**Bold and boxed results indicate an exceedance of Groundwater Standards**



Table 5 - (Page 1 of 1): Summary of Post-Excavation Soil Sample Laboratory Analytical Results - Bridge Street Swale. Celi Drive BCP Site (BCP Site #C734108). Syracuse, NY.

ANALYTE (mg/kg)	SOIL CLEANUP OBJECTIVES		SAMPLE IDENTIFICATION BRIDGE STREET SWALE		
	UNRESTRICTED USE	PROTECTION OF ECOLOGICAL RESOURCES	BSS-SED1-COMP		
Sample Date			8/23/2016		
<b>Metals by EPA Method 6010C</b>				D.L.	R.L.
Chromium, Total	30	41	<b>55</b>		
Copper, Total	50	50	30		
Nickel, Total	30	30	17		
<b>Cyanide by EPA Method 9010C</b>					
Cyanide, Total	27	NS	U	0.21	1.3
<b>Chromium by EPA Method 7196A</b>					
Chromium, Hexavalent	1	1	U	0.22	1.1

All values reported as mg/kg (parts per million)

Soil Cleanup Objectives from 6 NYCRR Part 375-6.8(b) (December 2006) and Supplemental Soil Cleanup Objectives (October 2010)

U - Analyzed for but not detected above the laboratory reporting limit

J - Estimated value

D.L. - Laboratory Detection Limit

R.L. - Laboratory Reporting Limit

NS - Not Specified

Bold, thick outlined, and shaded cell indicates analyte exceeds the Protection of Ecological Resources Soil Cleanup Objectives





Table 6 - (Page 1 of 7): Summary of Post-Excavation Soil Sample Laboratory Analytical Results. Celi Drive BCP Site (BCP Site #C734108). Syracuse, NY.

ANALYTE (mg/kg)	SOIL CLEANUP OBJECTIVES		SAMPLE IDENTIFICATION															
	UNRESTRICTED USE	PROTECTION OF ECOLOGICAL RESOURCES	MAIN SWALE															
			AOC4-SED1A			AOC4-SED1B			AOC4-SED1C			DUPLICATE 2						
Sample Date			8/23/2016			8/23/2016			8/23/2016			8/23/2016 (AOC4-SED1B)						
<b>Metals by EPA Method 6010C</b>			D.L.	R.L.		D.L.	R.L.		D.L.	R.L.	D.L.	R.L.	D.L.	R.L.				
Chromium, Total	30	41	11			<b>140</b>					<b>160</b>			31				
Copper, Total	50	50	39			<b>170</b>					<b>300</b>			<b>57</b>				
Nickel, Total	30	30	14			<b>57</b>					<b>140</b>			27				
<b>Cyanide by EPA Method 9010C</b>																		
Cyanide, Total	27	NS	0.26	J	0.2	1.2	0.92	J	0.27	1.6	0.78	J	0.57	3.4	0.67	J	0.64	3.9
<b>Chromium by EPA Method 7196A</b>																		
Chromium, Hexavalent	1	1	U	0.21	1	U	0.27	1.4	U	0.3	1.5	U	0.32	1.6				

All values reported as mg/kg (parts per million)

Soil Cleanup Objectives from 6 NYCRR Part 375-6.8(b) (December 2006) and Supplemental Soil Cleanup Objectives (October 2010)

U - Analyzed for but not detected above the laboratory reporting limit

J - Estimated value

D.L. - Laboratory Detection Limit

R.L. - Laboratory Reporting Limit

NS - Not Specified

Bold, thick outlined, and shaded cell indicates analyte exceeds the Protection of Ecological Resources Soil Cleanup Objectives



Table 6 - (Page 2 of 7): Summary of Post-Excavation Soil Sample Laboratory Analytical Results. Celi Drive BCP Site (BCP Site #C734108). Syracuse, NY.

ANALYTE (mg/kg)	SOIL CLEANUP OBJECTIVES		SAMPLE IDENTIFICATION											
	UNRESTRICTED USE	PROTECTION OF ECOLOGICAL RESOURCES	MAIN SWALE											
			AOC4-SED2A			AOC4-SED2B			AOC4-SED2C					
Sample Date			8/23/2016			8/23/2016			8/23/2016					
<b>Metals by EPA Method 6010C</b>				D.L.	R.L.		D.L.	R.L.		D.L.	R.L.			
Chromium, Total	30	41	<b>130</b>			<b>210</b>			<b>190</b>					
Copper, Total	50	50	<b>220</b>			<b>530</b>			<b>66</b>					
Nickel, Total	30	30	<b>130</b>			<b>140</b>			<b>53</b>					
<b>Cyanide by EPA Method 9010C</b>														
Cyanide, Total	27	NS	0.96	J	0.6	3.6	2.8	J	1	6.1	1.6	J	0.4	2.4
<b>Chromium by EPA Method 7196A</b>														
Chromium, Hexavalent	1	1	U	0.31	1.6	U	0.52	2.6	U	0.4	2			

All values reported as mg/kg (parts per million)

Soil Cleanup Objectives from 6 NYCRR Part 375-6.8(b) (December 2006) and Supplemental Soil Cleanup Objectives (October 2010)

U - Analyzed for but not detected above the laboratory reporting limit

J - Estimated value

D.L. - Laboratory Detection Limit

R.L. - Laboratory Reporting Limit

NS - Not Specified

Bold, thick outlined, and shaded cell indicates analyte exceeds the Protection of Ecological Resources Soil Cleanup Objectives



Table 6 - (Page 3 of 7): Summary of Post-Excavation Soil Sample Laboratory Analytical Results. Celi Drive BCP Site (BCP Site #C734108). Syracuse, NY.

ANALYTE (mg/kg)	SOIL CLEANUP OBJECTIVES		SAMPLE IDENTIFICATION											
	UNRESTRICTED USE	PROTECTION OF ECOLOGICAL RESOURCES	MAIN SWALE											
			AOC4-SED3A			AOC4-SED3B			AOC4-SED3C					
Sample Date			8/23/2016			8/23/2016			8/23/2016					
<b>Metals by EPA Method 6010C</b>				D.L.	R.L.		D.L.	R.L.		D.L.	R.L.			
Chromium, Total	30	41	<b>270</b>			<b>62</b>				40				
Copper, Total	50	50	<b>240</b>			<b>150</b>				40				
Nickel, Total	30	30	<b>59</b>			<b>54</b>				27				
<b>Cyanide by EPA Method 9010C</b>														
Cyanide, Total	27	NS	1.4	J	0.39	2.3	1.5	J	0.41	2.5	U	0.3	1.8	
<b>Chromium by EPA Method 7196A</b>														
Chromium, Hexavalent	1	1		U	0.38	1.9		U	0.42	2.1		U	0.31	1.5

All values reported as mg/kg (parts per million)

Soil Cleanup Objectives from 6 NYCRR Part 375-6.8(b) (December 2006) and Supplemental Soil Cleanup Objectives (October 2010)

U - Analyzed for but not detected above the laboratory reporting limit

J - Estimated value

D.L. - Laboratory Detection Limit

R.L. - Laboratory Reporting Limit

NS - Not Specified

Bold, thick outlined, and shaded cell indicates analyte exceeds the Protection of Ecological Resources Soil Cleanup Objectives



Table 6 - (Page 4 of 7): Summary of Post-Excavation Soil Sample Laboratory Analytical Results. Celi Drive BCP Site (BCP Site #C734108). Syracuse, NY.

ANALYTE (mg/kg)	SOIL CLEANUP OBJECTIVES		SAMPLE IDENTIFICATION															
	UNRESTRICTED USE	PROTECTION OF ECOLOGICAL RESOURCES	MAIN SWALE															
			AOC4-SED4A				AOC4-SED4B				AOC4-SED4C				DUPLICATE			
Sample Date			8/23/2016				8/23/2016				8/23/2016				8/23/2016 (AOC4-SED4C)			
<b>Metals by EPA Method 6010C</b>			D.L.	R.L.	D.L.	R.L.	D.L.	R.L.	D.L.	R.L.	D.L.	R.L.	D.L.	R.L.				
Chromium, Total	30	41	<b>75</b>		<b>120</b>		<b>160</b>		<b>82</b>									
Copper, Total	50	50	<b>230</b>		<b>81</b>		<b>440</b>		<b>200</b>									
Nickel, Total	30	30	<b>60</b>		<b>34</b>		<b>67</b>		<b>59</b>									
<b>Cyanide by EPA Method 9010C</b>																		
Cyanide, Total	27	NS	1.1	J 0.67	4	16	0.29	1.8	1.2	J 0.55	3.3	0.51	J 0.24	1.5				
<b>Chromium by EPA Method 7196A</b>																		
Chromium, Hexavalent	1	1	U	0.33	1.6	U	0.23	1.4	U	0.28	1.4	U	0.26	1.3				

All values reported as mg/kg (parts per million)

Soil Cleanup Objectives from 6 NYCRR Part 375-6.8(b) (December 2006) and Supplemental Soil Cleanup Objectives (October 2010)

U - Analyzed for but not detected above the laboratory reporting limit

J - Estimated value

D.L. - Laboratory Detection Limit

R.L. - Laboratory Reporting Limit

NS - Not Specified

Bold, thick outlined, and shaded cell indicates analyte exceeds the Protection of Ecological Resources Soil Cleanup Objectives



Table 6 - (Page 5 of 7): Summary of Post-Excavation Soil Sample Laboratory Analytical Results. Celi Drive BCP Site (BCP Site #C734108). Syracuse, NY.

ANALYTE (mg/kg)	SOIL CLEANUP OBJECTIVES		SAMPLE IDENTIFICATION										
	UNRESTRICTED USE	PROTECTION OF ECOLOGICAL RESOURCES	MAIN SWALE										
			AOC4-SED5A			AOC4-SED5B			AOC4-SED5C				
Sample Date			8/23/2016			8/23/2016			8/23/2016				
<b>Metals by EPA Method 6010C</b>				D.L.	R.L.		D.L.	R.L.		D.L.	R.L.		
Chromium, Total	30	41	27			170			33				
Copper, Total	50	50	70			410			150				
Nickel, Total	30	30	34			170			340				
<b>Cyanide by EPA Method 9010C</b>													
Cyanide, Total	27	NS	U	0.24	1.4	2.2	J	0.42	2.5	0.58	J	0.28	1.7
<b>Chromium by EPA Method 7196A</b>													
Chromium, Hexavalent	1	1	U	0.24	1.2	U	0.44	2.2	U	0.28	1.4		

All values reported as mg/kg (parts per million)

Soil Cleanup Objectives from 6 NYCRR Part 375-6.8(b) (December 2006) and Supplemental Soil Cleanup Objectives (October 2010)

U - Analyzed for but not detected above the laboratory reporting limit

J - Estimated value

D.L. - Laboratory Detection Limit

R.L. - Laboratory Reporting Limit

NS - Not Specified

Bold, thick outlined, and shaded cell indicates analyte exceeds the Protection of Ecological Resources Soil Cleanup Objectives



Table 6 - (Page 6 of 7): Summary of Post-Excavation Soil Sample Laboratory Analytical Results. Celi Drive BCP Site (BCP Site #C734108). Syracuse, NY.

ANALYTE (mg/kg)	SOIL CLEANUP OBJECTIVES		SAMPLE IDENTIFICATION											
	UNRESTRICTED USE	PROTECTION OF ECOLOGICAL RESOURCES	MAIN SWALE											
			AOC4-SED6A				AOC4-SED6B				AOC4-SED6C			
Sample Date			8/23/2016				8/23/2016				8/23/2016			
<b>Metals by EPA Method 6010C</b>				D.L.	R.L.		D.L.	R.L.		D.L.	R.L.		D.L.	R.L.
Chromium, Total	30	41	<b>51</b>			<b>210</b>			<b>220</b>					
Copper, Total	50	50	<b>120</b>			<b>730</b>			<b>500</b>					
Nickel, Total	30	30	<b>51</b>			<b>200</b>			<b>140</b>					
<b>Cyanide by EPA Method 9010C</b>														
Cyanide, Total	27	NS	0.33	J	0.29	1.8	1.7	J	0.45	2.7	0.7	J	0.48	2.9
<b>Chromium by EPA Method 7196A</b>														
Chromium, Hexavalent	1	1	U	0.31	1.5	U	0.46	2.3	U	0.25	1.2			

All values reported as mg/kg (parts per million)

Soil Cleanup Objectives from 6 NYCRR Part 375-6.8(b) (December 2006) and Supplemental Soil Cleanup Objectives (October 2010)

U - Analyzed for but not detected above the laboratory reporting limit

J - Estimated value

D.L. - Laboratory Detection Limit

R.L. - Laboratory Reporting Limit

NS - Not Specified

Bold, thick outlined, and shaded cell indicates analyte exceeds the Protection of Ecological Resources Soil Cleanup Objectives



Table 6 - (Page 7 of 7): Summary of Post-Excavation Soil Sample Laboratory Analytical Results. Celi Drive BCP Site (BCP Site #C734108). Syracuse, NY.

ANALYTE (mg/kg)	SOIL CLEANUP OBJECTIVES		SAMPLE IDENTIFICATION											
	UNRESTRICTED USE	PROTECTION OF ECOLOGICAL RESOURCES	MAIN SWALE											
			AOC4-SED7A			AOC4-SED7B			AOC4-SED7C					
Sample Date			8/23/2016			8/23/2016			8/23/2016					
<b>Metals by EPA Method 6010C</b>				D.L.	R.L.		D.L.	R.L.		D.L.	R.L.			
Chromium, Total	30	41	<b>290</b>			<b>86</b>				35				
Copper, Total	50	50	<b>980</b>			<b>89</b>				<b>70</b>				
Nickel, Total	30	30	<b>370</b>			<b>56</b>				<b>33</b>				
<b>Cyanide by EPA Method 9010C</b>														
Cyanide, Total	27	NS	0.74	J	0.69	4.2	1.4	J	0.24	1.5	1.2	J	0.34	2.1
<b>Chromium by EPA Method 7196A</b>														
Chromium, Hexavalent	1	1		U	0.36	1.8		U	0.25	1.3		U	0.34	1.7

All values reported as mg/kg (parts per million)

Soil Cleanup Objectives from 6 NYCRR Part 375-6.8(b) (December 2006) and Supplemental Soil Cleanup Objectives (October 2010)

U - Analyzed for but not detected above the laboratory reporting limit

J - Estimated value

D.L. - Laboratory Detection Limit

R.L. - Laboratory Reporting Limit

NS - Not Specified

Bold, thick outlined, and shaded cell indicates analyte exceeds the Protection of Ecological Resources Soil Cleanup Objectives



Depth of Boring : 14.0-feet bgs  
 Drilling Contractor : Parratt-Wolff  
 Driller : Mark Eaves  
 Drilling Method : Direct Push  
 Sample Equipment : DT-325  
 Field Geologist : Ian McNamara  
 Initial Depth to GW : 3.0'  
 Stable Depth to GW : 2.5'  
 Surveyed By : D.W. Hannig

## LOG OF BORING MW-8

(Page 1 of 1)


GSP Holdings, Inc.  
 Celi Drive BCP Site  
 BCP Site #E734108  
 Dewitt, New York

Date Started : August 26, 2016  
 Date Completed : August 26, 2016

Northing/Latitude : 43.05008  
 Easting/Longitude : -76.06868  
 Surface Elevation : 412.8'

Project No. 37-11082

DEPTH (feet bgs)	Water Level	SOIL DESCRIPTION	BLOW COUNT	RECOVERY (inches)	PID READING (ppm)	DEPTH (feet bgs)
	▼ After Completion ▽ During Drilling					
0		Asphalt millings, brick and concrete fragments, loose (fill)				0
1						1
2		Brown, CLAY and SILT with fine to medium grained SAND and fine GRAVEL, medium-stiff, moist to wet with depth	N/A	30	0.0	2
3						3
4						4
5		Gray, CLAY and SILT, some fine to medium grained SAND, rusty orange mottling, medium-stiff to stiff, wet				5
6		Decreasing clay with depth	N/A	42	0.1	6
7						7
8		Brown, SILT and fine to medium grained SAND, loose, wet				8
9						9
10		Brown, fine to coarse grained SAND, some fine GRAVEL and SILT, loose, wet	N/A	48	0.0	10
11						11
12		Reddish-brown, CLAY with SILT, medium-stiff, wet (dilatancy)				12
13			N/A	24	0.1	13
14		End of Boring at 14' bgs				14
15						15



NOTES:  
 BGS - Below Ground Surface  
 N/A - Not Applicable  
 ppm - Parts Per Million

## LOG OF BORING MW-8

(Page 1 of 1)



[www.ghd.com](http://www.ghd.com)



*APPENDIX C*

*2020 Wetland Delineation Report  
Prepared by GHD*



**GSP Holdings, Inc.**  
**Celi Drive BCP Site (BCP Site #C734108)**  
Town of DeWitt, Onondaga County

**Wetland Delineation Report**

June 2020

# Table of contents

1. Project Description .....	1
2. Site Description .....	1
3. Wetland Delineation Methods .....	1
4. Results.....	2
4.1 Review of Secondary Data.....	2
4.2 Field Investigation Data.....	2
5. Summary and Conclusions .....	3

## Figures

Figure 1 – USGS Topographic Location Map

Figure 2 – U.S. Fish & Wildlife Service National Wetland Inventory Mapping

Figure 3 – NYDEC Environmental Mapper

Figure 4 – NRCS Web Soil Survey Map

## Appendices

Appendix A – Wetland Investigation Site Map

Appendix B – Wetland Determination Data Forms

Appendix C - Color Photographs

Appendix D – Wetland Certifications

# 1. Project Description

GSP Holdings, Inc. (GSP) is investigating and remediating a historic accidental release of metal plating chemicals along swales located between Erie Boulevard, Bridge Street, and Interstate 690 in the Town of DeWitt and Village of East Syracuse, Onondaga County, New York under the New York State Department of Environmental Conservation's Brownfield Cleanup Program (BCP Site #C734108). The proposed remedial action will involve the excavation and removal of contaminated soil and sediments from the drainage swales and restoration of the areas to provide positive drainage and, when applicable, wetland conditions. The project area is shown on the attached USGS Topographic Location Map (Figure 1).

## 2. Site Description

The potential remediation areas and study area boundaries are situated south of the Interstate 690 eastbound off-ramp and west of Bridge Street. Also included is a section of swale that runs north under the Interstate 690 eastbound off-ramp and into a corridor south of Interstate 690. Current and future land uses of the immediate project area and areas adjacent to the project site are and will continue to be commercial retail, stormwater drainage, electrical transmission lines and associated substations, and watercourse. No changes in land use are proposed.

## 3. Wetland Delineation Methods

The wetland field investigation used the methods as described in the Corps of Engineers 1987 Wetlands Delineation Manual (Technical Report Y-87-1) and the Regional Supplement to the Corps of Engineers Wetland Delineation Manual: Northcentral and Northeast (Version 2.0, January 2012). The wetland field investigation was also consistent with the methods in the New York State Wetlands Delineation Manual (NYSDEC 1995). According to these methods, wetlands are typically identified by the presence of three parameters: the dominance of hydrophytic vegetation, the presence of hydric soils, and positive indicators of wetland hydrology. Typically, all three parameters must be present for an area to be considered a wetland. However, in areas where one or more of the wetland parameters were significantly disturbed (e.g., mowed lawn areas) the undisturbed parameters and best professional judgment were used to delineate the extent of wetlands.

Potential wetlands are first identified on the dominance of hydrophytic vegetation and both surface and subsurface hydrology. Then, a more detailed analysis of hydrology, soil and vegetation are performed to confirm the presence of wetland and/or upland boundaries. The general sequence used in determining the presence of hydrophytic vegetation is as follows:

- Indicator 1 – Rapid Field Test: Vegetation is considered hydrophytic if all dominant species are classified as facultative wetland (FACW) or obligate (OBL);
- Indicator 2 – Dominance Test (and basic hydrophytic vegetation indicator): More than 50% of the dominant plant species across all strata are rated OBL, FACW, or facultative (FAC);
- Indicator 3 – Prevalence Index: Conducted if necessary depending on the presence of hydric soil and wetland hydrology. This indicator takes non-dominant plant species into consideration;
- Indicator 4 – Morphological Adaptations: Observing the presence of morphological adaptations.

Hydrology is based on visual observation using primary and secondary indicators. One primary or two secondary indicators are required to confirm wetland hydrology. Soils are considered hydric if one or

more of the hydric soil indicators is present. Soil colors are identified in the field using the Munsell®<sup>1</sup> Soil Color Charts. The presence of surface water, depth to groundwater and saturation is recorded at each soil pit location.

## 4. Results

### 4.1. Review of Secondary Data

Secondary sources of data for the study area, including the USGS topographic map, aerial photography, NRCS soil survey, USFWS National Wetlands Inventory (NWI) map, and NYSDEC Environmental Mapper were reviewed prior to conducting the field investigation.

Aerial photography and the USGS topographic map, Syracuse East quadrant (Figure 1), of the area was observed and found to be extensively anthropogenically developed into commercial and industrial structures, parking lots, and paved highways. The drainage swale was visible as was areas which appeared to potentially contain wetland characteristics such as darker vegetative cover, depressions, and drainage pattern. USFWS NWI mapping (Figure 2) was referenced using the agency's Wetland Mapper online tool which revealed two pockets of Freshwater Emergent Wetlands present within the Interstate 690 eastbound off-ramp and westbound on-ramp. Riverine wetlands were mapped consistent with the South Branch of Ley Creek. NYDEC Environmental Mapper produced the most detailed results (Figure 3) which revealed a continuous wetland following the drainage swale and South Branch of Ley Creek.

Soils in the project area are identified using the NRCS Web Soil Survey, and are shown on the accompanying soil map<sup>2</sup> (Figure 4). Three (3) soil types are mapped within the study area. All three soil units are classified as hydric or having hydric inclusions. They include the Canandaigua mucky silt loam (Cd), Cut and fill land (CFL), and Urban land (Ub). Soils mapped in the project area are summarized in Table 1.

**Table 1 - Summary of Soil Type and Soil Characteristics Mapped in the Study Area**

Soil Map Unit	Soil Series Name	Slope (%)	Description/Texture	Drainage Class <sup>*</sup>	Hydric
Cd	Canandaigua mucky silt loam	0 - 3	on depressions; parent material of stratified silt loam to very fine sand to fine sand; depth to restrictive feature greater than 80"	PD	Y
CFL	Cut and fill land	0 - 8	depth to restrictive feature greater than 80"	SED	N**
Ub	Urban land	NR	previously disturbed and/or not rated; depth to restrictive feature greater than 80"	NR	N**

\* (NR) Not Rated, (SED) Somewhat excessively drained, (PD) Poorly drained

\*\* Not predominantly hydric but can contain hydric inclusions

### 4.1. Field Investigation Data

Following the review of the secondary sources of data, a wetland field investigation was conducted November 14-16, 2017 by Melissa Harrison PWS (GHD), and Gregory Kunka WPIT (GHD), Environmental Scientists. The boundaries were flagged in the field and the wetland boundary flags were surveyed using GPS.

<sup>1</sup> Munsell® Soil Color Charts, 1994 Revised Edition. GretagMacbeth, New Windsor, NY.

<sup>2</sup> Soil Map obtained from the USDA, Natural Resources Conservation Service Web Soil Survey 2.0, National Cooperative Soil Survey (<http://websoilsurvey.nrcs.usda.gov/app/>).


The location and extent of wetlands and watercourses (streams and ditches) identified and delineated within the Study Area are shown on the Wetland Investigation Site Map in Appendix A. As shown on the Wetland Investigation Site Map, GHD identified and delineated a total of 10.3 acres of wetlands within the Study Area. The wetlands within the study area are part of a wetland complex hydrologically connected by a series of ditches and culverts. As shown on the Wetland Investigation Site Map, the wetlands are bisected by various roads and ditches. However, all of the wetlands delineated within the Study Area are hydrologically connected to South Branch of Ley Creek via ditches or culverts. Watercourse present within the study area was measured to be 1.1 acres in size and 8,813 linear feet in length. Note that the wetlands delineated within the Study Area often extend beyond the Study Area Boundary as shown on the Wetland Investigation Site Map in Appendix A.

Wetlands delineated within the Study Area include 6.0 acres of palustrine emergent wetland (PEM), 2.2 acres of palustrine scrub-shrub wetland (PSS), and 2.1 acres of palustrine forested wetland (PFO). The dominant wetland vegetation in the wetlands included eastern cottonwood (*Populus deltoides*), green ash (*Fraxinus pennsylvanica*), black willow (*Salix nigra*), red maple (*Acer rubrum*), common buckthorn (*Rhamnus cathartica*), silky dogwood (*Cornus amomum*), common reed (*Phragmites australis*), sphagnum moss (*Sphagnum spp.*), and Canadian goldenrod (*Solidago canadensis*). Soils were loamy / clayey and were often extremely stony, often resulting in the formation of a restrictive layer within the upper part of the soil profile. The soils located in the wetlands exhibited surface matrix colors ranging from 10YR 3/1 to 10YR 4/2 which were underlain by a depleted layer with matrix colors mostly of 10YR 4/1 and 10YR 4/2 having at least 2% prominent redox concentrations. These colorations meet criteria for a Depleted Matrix (F3). Soils profiles at data points SP-01, SP-03, SP-05, SP-06, SP-08, SP-10, SP-12, SP-13, SP-14, and SP-15 have a restrictive layer of stones at varying depths, which is likely related to historical cut and fill activities. Hydrology indicators observed most often were saturation (A3) and high water table (A2) within 12" of the soil surface. Secondary indicators included geomorphic position (D2) and the passing of the FAC-Neutral test (D5).

Documentation of the wetland boundaries is provided on the Wetland Determination Data Forms in Appendix B. Photos of the wetlands and surrounding areas taken from surveyed data points and wetland flags shown on the Wetland Investigation Site Map are provided in Appendix C.

## 5. Summary and Conclusions

Based on GHD's wetland delineation, a total of 10.3 acres within the Study Area meet the Army Corps of Engineers' wetland criterion. The delineated wetland areas include 6.0 acres of palustrine emergent wetland (PEM), 2.2 acres of palustrine scrub-shrub wetland (PSS), and 2.1 acres of palustrine forested wetland (PFO) which drain to the South Branch of Ley Creek through a series of ditches. Watercourse present within the study area was measured to be 1.1 acres in size and 8,813 linear feet in length. Based on GHD's findings, the proposed remedial activities in the delineated areas would likely require NYSDEC and Army Corps of Engineers authorizations.



Paper Size 8.5 x 11  
 0 500 1,000 1,500 2,000  
 Feet  
 Map Projection: Transverse Mercator  
 Horizontal Datum: NAD 1983 2011  
 Grid: NAD 1983 2011 StatePlane New York Central FIPS 3102 FUS



**CELI DRIVE BCP SITE (BCP SITE #C734108)**  
**USGS TOPOGRAPHIC MAP**  
 GSP HOLDINGS, INC.  
 TOWN OF DEWITT, ONONDAGA COUNTY, NY  
 USGS QUAD: SYRACUSE EAST

Job Number 3711082  
 Revision A  
 Date Dec 07, 2017

**FIGURE 1**

C:\Users\gkunka\Desktop\temp\GSP Holdings\GHD-Permit Map.mxd  
 1240 North Mountain Road Hamisburg, PA 17112 T 717 541 0622 F 717 541 8004 W www.ghd.com  
 © 2018. While every care has been taken to prepare this map, GHD (and DATA CUSTODIAN) make no representations or warranties about its accuracy, reliability, completeness or suitability for any particular purpose and cannot accept liability and responsibility of any kind (whether in contract, tort or otherwise) for any expenses, losses, damages and/or costs (including indirect or consequential damage) which are or may be incurred by any party as a result of the map being inaccurate, incomplete or unsuitable in any way and for any reason.





U.S. Fish and Wildlife Service  
**National Wetlands Inventory**

APPROXIMATE  
PROJECT AREA



November 29, 2017

**Wetlands**

- |                                |                                   |          |
|--------------------------------|-----------------------------------|----------|
| Estuarine and Marine Deepwater | Freshwater Emergent Wetland       | Lake     |
| Estuarine and Marine Wetland   | Freshwater Forested/Shrub Wetland | Other    |
|                                | Freshwater Pond                   | Riverine |

This map is for general reference only. The US Fish and Wildlife Service is not responsible for the accuracy or currentness of the base data shown on this map. All wetlands related data should be used in accordance with the layer metadata found on the Wetlands Mapper web site.

**FIGURE 2**  
**NWI Map**


National Wetlands Inventory (NWI)  
 This page was produced by the NW Mapper

## GSP Holdings Celi Drive Site



January 15, 2018

1:9,028



NYS Department of Environmental Conservation  
Not a legal document

Sources: Esri, HERE, DeLorme, Intermap, Incent P Corp., GEBCO, USGS, FAO, NPS, NRCAN, GeoBasis, IGN, Kadaster NL, Ordnance Survey, Esri Japan, METI, Esri China (Hong Kong), Swisstopo, Mapbox, © OpenStreetMap contributors, and the GIS User Community

**FIGURE 3**  
**NYSDEC WETLAND MAPPER**

Hydric Rating by Map Unit—Onondaga County, New York



FIGURE 4  
NRCS WEB SOIL SURVEY

Hydric Rating by Map Unit—Onondaga County, New York




FIGURE 4  
NRCS WEB SOILS SURVEY


## Hydric Rating by Map Unit

Map unit symbol	Map unit name	Rating	Acres In AOI	Percent of AOI
CaD2	Camillus silt loam, 12 to 18 percent slopes eroded	0	0.8	0.3%
Cd	Canandaigua mucky silt loam	95	11.8	3.7%
CfB	Cazenovia silt loam, 2 to 8 percent slopes	0	3.6	1.1%
CFL	Cut and fill land	10	190.9	60.5%
Fo	Fonda mucky silty clay loam	90	0.0	0.0%
NgA	Niagara silt loam, 0 to 4 percent slopes	7	2.8	0.9%
OvA	Ovid silt loam, 0 to 3 percent slopes	7	0.4	0.1%
Rh	Rhinebeck silt loam	5	20.4	6.5%
Ub	Urban land	10	84.8	26.9%
<b>Totals for Area of Interest</b>			<b>315.6</b>	<b>100.0%</b>

FIGURE 4  
NRCS WEB SOILS SURVEY

# Appendices

# **Appendix A – Wetland Investigation Site Map**



Paper Size ARCH D  
 0 50 100 150 200  
 Feet  
 Map Projection: Transverse Mercator  
 NAD 1983 (2011)



LEGEND	
[Solid line]	STUDY AREA BOUNDARY
[Dashed line]	WETLAND FLAG
[Dotted line]	APPROXIMATE WATERCOURSE CENTERLINE
[Thin solid line]	CONTOUR
[Small square]	WETLAND DATA POINT
[Thick solid line]	WETLAND BOUNDARY
[Cross-hatched pattern]	PALUSTRINE SCRUB-SHRUB WETLAND (PSS)
[Stippled pattern]	PALUSTRINE FORESTED WETLAND (PFD)
[Diagonal line pattern]	PALUSTRINE EMERGENT WETLAND (PEM)



**CELI DRIVE BCP SITE (BCP SITE #C734108)**  
**WETLAND INVESTIGATION**  
**NOVEMBER 14-16, 2017**  
 GSP HOLDINGS, INC.  
 TOWN OF DEWITT, ONONDAGA COUNTY, NY

Job Number: 3711082  
 Revision: A  
 Date: Jan 16, 2018

This map was prepared by GHD for the use of the client. It is not to be used for any other purpose without the written consent of GHD. GHD and its employees are not responsible for any errors or omissions in this map. The client is responsible for the accuracy of the data provided to GHD.



## **Appendix B – Wetland Determination Data Forms**

**WETLAND DETERMINATION DATA FORM – Northcentral and Northeast Region**

Project/Site: Cell Drive BCP Site (BCP Site #C734108) City/County: Onondaga County Sampling Date: 11/14/2017  
 Applicant/Owner: GSP Holdings, Inc. State: NY Sampling Point: SP-01  
 Investigator(s): Melissa Harrison, Gregory Kunka Section, Township, Range: Town of Dewitt  
 Landform (hillside, terrace, etc.): floodplain, upland access road Local relief (concave, convex, none): none Slope %: 0-2  
 Subregion (LRR or MLRA): LRR L, MLRA 101 Lat: 43.0536642899 Long: -76.069690378 Datum: NAD 1983  
 Soil Map Unit Name: Cut and fill land (CFL) NWI classification: none

Are climatic / hydrologic conditions on the site typical for this time of year? Yes X No      (If no, explain in Remarks.)  
 Are Vegetation X, Soil X, or Hydrology X significantly disturbed? Are "Normal Circumstances" present? Yes      No X  
 Are Vegetation     , Soil     , or Hydrology      naturally problematic? (If needed, explain any answers in Remarks.)

**SUMMARY OF FINDINGS – Attach site map showing sampling point locations, transects, important features, etc.**

Hydrophytic Vegetation Present? Yes <u>    </u> No <u>X</u>	<b>Is the Sampled Area within a Wetland?</b> Yes <u>    </u> No <u>X</u> If yes, optional Wetland Site ID: <u>                    </u>
Hydric Soil Present? Yes <u>    </u> No <u>X</u>	
Wetland Hydrology Present? Yes <u>    </u> No <u>X</u>	

Remarks: (Explain alternative procedures here or in a separate report.)  
 Area is mowed and maintained as an access road. Soils comprised of what is likely historic fill.

**HYDROLOGY**

<b>Wetland Hydrology Indicators:</b>		<u>    </u> <b>Secondary Indicators (minimum of two required)</b>
<u>    </u> <b>Primary Indicators (minimum of one is required; check all that apply)</b>		<u>    </u> Surface Soil Cracks (B6)
<u>    </u> Surface Water (A1)	<u>    </u> Water-Stained Leaves (B9)	<u>    </u> Drainage Patterns (B10)
<u>    </u> High Water Table (A2)	<u>    </u> Aquatic Fauna (B13)	<u>    </u> Moss Trim Lines (B16)
<u>    </u> Saturation (A3)	<u>    </u> Marl Deposits (B15)	<u>    </u> Dry-Season Water Table (C2)
<u>    </u> Water Marks (B1)	<u>    </u> Hydrogen Sulfide Odor (C1)	<u>    </u> Crayfish Burrows (C8)
<u>    </u> Sediment Deposits (B2)	<u>    </u> Oxidized Rhizospheres on Living Roots (C3)	<u>    </u> Saturation Visible on Aerial Imagery (C9)
<u>    </u> Drift Deposits (B3)	<u>    </u> Presence of Reduced Iron (C4)	<u>    </u> Stunted or Stressed Plants (D1)
<u>    </u> Algal Mat or Crust (B4)	<u>    </u> Recent Iron Reduction in Tilled Soils (C6)	<u>    </u> Geomorphic Position (D2)
<u>    </u> Iron Deposits (B5)	<u>    </u> Thin Muck Surface (C7)	<u>    </u> Shallow Aquitard (D3)
<u>    </u> Inundation Visible on Aerial Imagery (B7)	<u>    </u> Other (Explain in Remarks)	<u>    </u> Microtopographic Relief (D4)
<u>    </u> Sparsely Vegetated Concave Surface (B8)		<u>    </u> FAC-Neutral Test (D5)

<b>Field Observations:</b>				<b>Wetland Hydrology Present?</b> Yes <u>    </u> No <u>X</u>
Surface Water Present?	Yes <u>    </u> No <u>X</u>	Depth (inches):	<u>    </u>	
Water Table Present?	Yes <u>    </u> No <u>X</u>	Depth (inches):	<u>    </u>	
Saturation Present? (includes capillary fringe)	Yes <u>    </u> No <u>X</u>	Depth (inches):	<u>    </u>	

Describe Recorded Data (stream gauge, monitoring well, aerial photos, previous inspections), if available:

Remarks:

**VEGETATION – Use scientific names of plants.**

Sampling Point: SP-01

	Absolute % Cover	Dominant Species?	Indicator Status																	
<b>Tree Stratum</b> (Plot size: <u>30</u> )																				
1.																				
2.																				
3.																				
4.																				
5.																				
6.																				
7.																				
		=Total Cover																		
<b>Sapling/Shrub Stratum</b> (Plot size: <u>15</u> )																				
1.																				
2.																				
3.																				
4.																				
5.																				
6.																				
7.																				
		=Total Cover																		
<b>Herb Stratum</b> (Plot size: <u>5</u> )																				
1.	<u>Poa pratensis</u>	45	Yes	FACU																
2.	<u>Cynodon dactylon</u>	40	Yes	FACU																
3.	<u>Galium concinnum</u>	20	No	FACU																
4.	<u>Plantago lanceolata</u>	15	No	FACU																
5.	<u>Trifolium pratense</u>	10	No	FACU																
6.																				
7.																				
8.																				
9.																				
10.																				
11.																				
12.																				
		130	=Total Cover																	
<b>Woody Vine Stratum</b> (Plot size: <u>15</u> )																				
1.																				
2.																				
3.																				
4.																				
			=Total Cover																	
Dominance Test worksheet: Number of Dominant Species That Are OBL, FACW, or FAC: <u>0</u> (A) Total Number of Dominant Species Across All Strata: <u>2</u> (B) Percent of Dominant Species That Are OBL, FACW, or FAC: <u>0.0%</u> (A/B)																				
Prevalence Index worksheet: <table style="width:100%; border-collapse: collapse;"> <thead> <tr> <th style="width:50%; text-align:center;">Total % Cover of:</th> <th style="width:50%; text-align:center;">Multiply by:</th> </tr> </thead> <tbody> <tr> <td>OBL species <u>0</u></td> <td>x 1 = <u>0</u></td> </tr> <tr> <td>FACW species <u>0</u></td> <td>x 2 = <u>0</u></td> </tr> <tr> <td>FAC species <u>0</u></td> <td>x 3 = <u>0</u></td> </tr> <tr> <td>FACU species <u>130</u></td> <td>x 4 = <u>520</u></td> </tr> <tr> <td>UPL species <u>0</u></td> <td>x 5 = <u>0</u></td> </tr> <tr> <td>Column Totals: <u>130</u> (A)</td> <td><u>520</u> (B)</td> </tr> <tr> <td colspan="2" style="text-align:center;">Prevalence Index = B/A = <u>4.00</u></td> </tr> </tbody> </table>					Total % Cover of:	Multiply by:	OBL species <u>0</u>	x 1 = <u>0</u>	FACW species <u>0</u>	x 2 = <u>0</u>	FAC species <u>0</u>	x 3 = <u>0</u>	FACU species <u>130</u>	x 4 = <u>520</u>	UPL species <u>0</u>	x 5 = <u>0</u>	Column Totals: <u>130</u> (A)	<u>520</u> (B)	Prevalence Index = B/A = <u>4.00</u>	
Total % Cover of:	Multiply by:																			
OBL species <u>0</u>	x 1 = <u>0</u>																			
FACW species <u>0</u>	x 2 = <u>0</u>																			
FAC species <u>0</u>	x 3 = <u>0</u>																			
FACU species <u>130</u>	x 4 = <u>520</u>																			
UPL species <u>0</u>	x 5 = <u>0</u>																			
Column Totals: <u>130</u> (A)	<u>520</u> (B)																			
Prevalence Index = B/A = <u>4.00</u>																				
Hydrophytic Vegetation Indicators: ___ 1 - Rapid Test for Hydrophytic Vegetation ___ 2 - Dominance Test is >50% ___ 3 - Prevalence Index is ≤3.0 <sup>1</sup> ___ 4 - Morphological Adaptations <sup>1</sup> (Provide supporting data in Remarks or on a separate sheet) ___ Problematic Hydrophytic Vegetation <sup>1</sup> (Explain)																				
<sup>1</sup> Indicators of hydric soil and wetland hydrology must be present, unless disturbed or problematic.																				
Definitions of Vegetation Strata: <b>Tree</b> – Woody plants 3 in. (7.6 cm) or more in diameter at breast height (DBH), regardless of height. <b>Sapling/shrub</b> – Woody plants less than 3 in. DBH and greater than or equal to 3.28 ft (1 m) tall. <b>Herb</b> – All herbaceous (non-woody) plants, regardless of size, and woody plants less than 3.28 ft tall. <b>Woody vines</b> – All woody vines greater than 3.28 ft in height.																				
Hydrophytic Vegetation Present?      Yes <u>    </u> No <u>X</u>																				
Remarks: (Include photo numbers here or on a separate sheet.) Area is mowed and maintained as an access road.																				



**WETLAND DETERMINATION DATA FORM – Northcentral and Northeast Region**

Project/Site: Celi Drive BCP Site (BCP Site #C734108) City/County: Onondaga County Sampling Date: 11/14/2017  
 Applicant/Owner: GSP Holdings, Inc. State: NY Sampling Point: SP-02  
 Investigator(s): Melissa Harrison, Gregory Kunka Section, Township, Range: Town of Dewitt  
 Landform (hillside, terrace, etc.): floodplain Local relief (concave, convex, none): concave Slope %: 0-2  
 Subregion (LRR or MLRA): LRR L, MLRA 101 Lat: 43.053692909 Long: -76.0697076559 Datum: NAD 1983  
 Soil Map Unit Name: Cut and fill land (CFL) NWI classification: none

Are climatic / hydrologic conditions on the site typical for this time of year? Yes X No      (If no, explain in Remarks.)  
 Are Vegetation     , Soil     , or Hydrology      significantly disturbed? Are "Normal Circumstances" present? Yes X No       
 Are Vegetation     , Soil     , or Hydrology      naturally problematic? (If needed, explain any answers in Remarks.)

**SUMMARY OF FINDINGS – Attach site map showing sampling point locations, transects, important features, etc.**

Hydrophytic Vegetation Present?      Yes <u>X</u> No <u>    </u> Hydric Soil Present?                      Yes <u>X</u> No <u>    </u> Wetland Hydrology Present?            Yes <u>X</u> No <u>    </u>	<b>Is the Sampled Area</b> <b>within a Wetland?</b> Yes <u>X</u> No <u>    </u> If yes, optional Wetland Site ID: _____
Remarks: (Explain alternative procedures here or in a separate report.) PEM	

**HYDROLOGY**

<b>Wetland Hydrology Indicators:</b> <u>Primary Indicators (minimum of one is required; check all that apply)</u>	<u>Secondary Indicators (minimum of two required)</u>
___ Surface Water (A1)                      ___ Water-Stained Leaves (B9) ___ High Water Table (A2)                ___ Aquatic Fauna (B13) ___ Saturation (A3)                          ___ Marl Deposits (B15) ___ Water Marks (B1)                        ___ Hydrogen Sulfide Odor (C1) ___ Sediment Deposits (B2)                ___ Oxidized Rhizospheres on Living Roots (C3) ___ Drift Deposits (B3)                      ___ Presence of Reduced Iron (C4) ___ Algal Mat or Crust (B4)                 ___ Recent Iron Reduction in Tilled Soils (C6) ___ Iron Deposits (B5)                        ___ Thin Muck Surface (C7) ___ Inundation Visible on Aerial Imagery (B7) ___ Other (Explain in Remarks) ___ Sparsely Vegetated Concave Surface (B8)	___ Surface Soil Cracks (B6) ___ Drainage Patterns (B10) ___ Moss Trim Lines (B16) ___ Dry-Season Water Table (C2) ___ Crayfish Burrows (C8) ___ Saturation Visible on Aerial Imagery (C9) ___ Stunted or Stressed Plants (D1) ___ <u>X</u> Geomorphic Position (D2) ___ Shallow Aquitard (D3) ___ Microtopographic Relief (D4) ___ <u>X</u> FAC-Neutral Test (D5)

<b>Field Observations:</b> Surface Water Present?    Yes <u>    </u> No <u>X</u> Depth (inches): _____ Water Table Present?      Yes <u>    </u> No <u>X</u> Depth (inches): _____ Saturation Present?        Yes <u>    </u> No <u>X</u> Depth (inches): _____ (includes capillary fringe)	<b>Wetland Hydrology Present?</b> Yes <u>X</u> No <u>    </u>
---	---

Describe Recorded Data (stream gauge, monitoring well, aerial photos, previous inspections), if available:

Remarks:

**VEGETATION – Use scientific names of plants.**

Sampling Point: SP-02

<u>Tree Stratum</u> (Plot size: <u>30</u> )	Absolute % Cover	Dominant Species?	Indicator Status
1. _____	_____	_____	_____
2. _____	_____	_____	_____
3. _____	_____	_____	_____
4. _____	_____	_____	_____
5. _____	_____	_____	_____
6. _____	_____	_____	_____
7. _____	_____	_____	_____
	_____ =Total Cover		
<u>Sapling/Shrub Stratum</u> (Plot size: <u>15</u> )			
1. <u>Rhamnus cathartica</u>	40	Yes	FAC
2. <u>Cornus amomum</u>	35	Yes	FACW
3. _____	_____	_____	_____
4. _____	_____	_____	_____
5. _____	_____	_____	_____
6. _____	_____	_____	_____
7. _____	_____	_____	_____
	75 =Total Cover		
<u>Herb Stratum</u> (Plot size: <u>5</u> )			
1. <u>Phragmites australis</u>	95	Yes	FACW
2. <u>Solidago gigantea</u>	5	No	FACW
3. _____	_____	_____	_____
4. _____	_____	_____	_____
5. _____	_____	_____	_____
6. _____	_____	_____	_____
7. _____	_____	_____	_____
8. _____	_____	_____	_____
9. _____	_____	_____	_____
10. _____	_____	_____	_____
11. _____	_____	_____	_____
12. _____	_____	_____	_____
	100 =Total Cover		
<u>Woody Vine Stratum</u> (Plot size: <u>15</u> )			
1. _____	_____	_____	_____
2. _____	_____	_____	_____
3. _____	_____	_____	_____
4. _____	_____	_____	_____
	_____ =Total Cover		

**Dominance Test worksheet:**

Number of Dominant Species That Are OBL, FACW, or FAC: 3 (A)

Total Number of Dominant Species Across All Strata: 3 (B)

Percent of Dominant Species That Are OBL, FACW, or FAC: 100.0% (A/B)

**Prevalence Index worksheet:**

Total % Cover of:	Multiply by:
OBL species _____	x 1 = _____
FACW species _____	x 2 = _____
FAC species _____	x 3 = _____
FACU species _____	x 4 = _____
UPL species _____	x 5 = _____
Column Totals: _____	(A) _____ (B)
Prevalence Index = B/A = _____	

**Hydrophytic Vegetation Indicators:**

\_\_\_ 1 - Rapid Test for Hydrophytic Vegetation

X 2 - Dominance Test is >50%

\_\_\_ 3 - Prevalence Index is ≤3.0<sup>1</sup>

\_\_\_ 4 - Morphological Adaptations<sup>1</sup> (Provide supporting data in Remarks or on a separate sheet)

\_\_\_ Problematic Hydrophytic Vegetation<sup>1</sup> (Explain)

<sup>1</sup>Indicators of hydric soil and wetland hydrology must be present, unless disturbed or problematic.

**Definitions of Vegetation Strata:**

**Tree** – Woody plants 3 in. (7.6 cm) or more in diameter at breast height (DBH), regardless of height.

**Sapling/shrub** – Woody plants less than 3 in. DBH and greater than or equal to 3.28 ft (1 m) tall.

**Herb** – All herbaceous (non-woody) plants, regardless of size, and woody plants less than 3.28 ft tall.

**Woody vines** – All woody vines greater than 3.28 ft in height.

**Hydrophytic Vegetation Present?** Yes X No \_\_\_\_\_

Remarks: (Include photo numbers here or on a separate sheet.)

**SOIL**

Sampling Point: SP-02

**Profile Description: (Describe to the depth needed to document the indicator or confirm the absence of indicators.)**

Depth (inches)	Matrix		Redox Features				Texture	Remarks
	Color (moist)	%	Color (moist)	%	Type <sup>1</sup>	Loc <sup>2</sup>		
0-6	10YR 3/2	100					Loamy/Clayey	
6-18	10YR 4/2	98	10YR 4/4	2	C	M	Loamy/Clayey	Distinct redox concentrations

<sup>1</sup>Type: C=Concentration, D=Depletion, RM=Reduced Matrix, MS=Masked Sand Grains. <sup>2</sup>Location: PL=Pore Lining, M=Matrix.

<b>Hydric Soil Indicators:</b>		<b>Indicators for Problematic Hydric Soils<sup>3</sup>:</b>	
<input type="checkbox"/> Histosol (A1)	<input type="checkbox"/> Polyvalue Below Surface (S8) (LRR R, MLRA 149B)	<input type="checkbox"/> 2 cm Muck (A10) (LRR K, L, MLRA 149B)	
<input type="checkbox"/> Histic Epipedon (A2)	<input type="checkbox"/> Thin Dark Surface (S9) (LRR R, MLRA 149B)	<input type="checkbox"/> Coast Prairie Redox (A16) (LRR K, L, R)	
<input type="checkbox"/> Black Histic (A3)	<input type="checkbox"/> High Chroma Sands (S11) (LRR K, L)	<input type="checkbox"/> 5 cm Mucky Peat or Peat (S3) (LRR K, L, R)	
<input type="checkbox"/> Hydrogen Sulfide (A4)	<input type="checkbox"/> Loamy Mucky Mineral (F1) (LRR K, L)	<input type="checkbox"/> Polyvalue Below Surface (S8) (LRR K, L)	
<input type="checkbox"/> Stratified Layers (A5)	<input type="checkbox"/> Loamy Gleyed Matrix (F2)	<input type="checkbox"/> Thin Dark Surface (S9) (LRR K, L)	
<input checked="" type="checkbox"/> Depleted Below Dark Surface (A11)	<input checked="" type="checkbox"/> Depleted Matrix (F3)	<input type="checkbox"/> Iron-Manganese Masses (F12) (LRR K, L, R)	
<input type="checkbox"/> Thick Dark Surface (A12)	<input type="checkbox"/> Redox Dark Surface (F6)	<input type="checkbox"/> Piedmont Floodplain Soils (F19) (MLRA 149B)	
<input type="checkbox"/> Sandy Mucky Mineral (S1)	<input type="checkbox"/> Depleted Dark Surface (F7)	<input type="checkbox"/> Mesic Spodic (TA6) (MLRA 144A, 145, 149B)	
<input type="checkbox"/> Sandy Gleyed Matrix (S4)	<input type="checkbox"/> Redox Depressions (F8)	<input type="checkbox"/> Red Parent Material (F21)	
<input type="checkbox"/> Sandy Redox (S5)	<input type="checkbox"/> Marl (F10) (LRR K, L)	<input type="checkbox"/> Very Shallow Dark Surface (F22)	
<input type="checkbox"/> Stripped Matrix (S6)		<input type="checkbox"/> Other (Explain in Remarks)	
<input type="checkbox"/> Dark Surface (S7)			

<sup>3</sup>Indicators of hydrophytic vegetation and wetland hydrology must be present, unless disturbed or problematic.

<b>Restrictive Layer (if observed):</b>	<b>Hydric Soil Present?</b> Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
Type: _____ Depth (inches): _____	

Remarks:  
 This data form is revised from Northcentral and Northeast Regional Supplement Version 2.0 to include the NRCS Field Indicators of Hydric Soils, Version 7.0, 2015 Errata. ([http://www.nrcs.usda.gov/Internet/FSE\\_DOCUMENTS/nrcs142p2\\_051293.docx](http://www.nrcs.usda.gov/Internet/FSE_DOCUMENTS/nrcs142p2_051293.docx))

**WETLAND DETERMINATION DATA FORM – Northcentral and Northeast Region**

Project/Site: Celi Drive BCP Site (BCP Site #C734108) City/County: Onondaga County Sampling Date: 11/14/2017  
 Applicant/Owner: GSP Holdings, Inc. State: NY Sampling Point: SP-03  
 Investigator(s): Melissa Harrison, Gregory Kunka Section, Township, Range: Town of Dewitt  
 Landform (hillside, terrace, etc.): floodplain Local relief (concave, convex, none): none Slope %: 0-2  
 Subregion (LRR or MLRA): LRR L, MLRA 101 Lat: 43.0539324766 Long: -76.0694244871 Datum: NAD 1983  
 Soil Map Unit Name: Cut and fill land (CFL) NWI classification: none

Are climatic / hydrologic conditions on the site typical for this time of year? Yes X No      (If no, explain in Remarks.)  
 Are Vegetation     , Soil     , or Hydrology      significantly disturbed? Are "Normal Circumstances" present? Yes X No       
 Are Vegetation     , Soil     , or Hydrology      naturally problematic? (If needed, explain any answers in Remarks.)

**SUMMARY OF FINDINGS – Attach site map showing sampling point locations, transects, important features, etc.**

Hydrophytic Vegetation Present? Yes <u>X</u> No <u>    </u> Hydric Soil Present? Yes <u>X</u> No <u>    </u> Wetland Hydrology Present? Yes <u>X</u> No <u>    </u>	<b>Is the Sampled Area within a Wetland?</b> Yes <u>X</u> No <u>    </u> If yes, optional Wetland Site ID: <u>    </u>
Remarks: (Explain alternative procedures here or in a separate report.) PFO	

**HYDROLOGY**

<b>Wetland Hydrology Indicators:</b> <u>Primary Indicators (minimum of one is required; check all that apply)</u> ___ Surface Water (A1)                      ___ Water-Stained Leaves (B9) ___ High Water Table (A2)                   ___ Aquatic Fauna (B13) <u>X</u> Saturation (A3)                              ___ Marl Deposits (B15) ___ Water Marks (B1)                         ___ Hydrogen Sulfide Odor (C1) ___ Sediment Deposits (B2)                 ___ Oxidized Rhizospheres on Living Roots (C3) ___ Drift Deposits (B3)                        ___ Presence of Reduced Iron (C4) ___ Algal Mat or Crust (B4)                   ___ Recent Iron Reduction in Tilled Soils (C6) ___ Iron Deposits (B5)                        ___ Thin Muck Surface (C7) ___ Inundation Visible on Aerial Imagery (B7) ___ Other (Explain in Remarks) ___ Sparsely Vegetated Concave Surface (B8)	<u>Secondary Indicators (minimum of two required)</u> ___ Surface Soil Cracks (B6) ___ Drainage Patterns (B10) ___ Moss Trim Lines (B16) ___ Dry-Season Water Table (C2) ___ Crayfish Burrows (C8) ___ Saturation Visible on Aerial Imagery (C9) ___ Stunted or Stressed Plants (D1) <u>X</u> Geomorphic Position (D2) ___ Shallow Aquitard (D3) ___ Microtopographic Relief (D4) <u>X</u> FAC-Neutral Test (D5)
--	---

<b>Field Observations:</b> Surface Water Present? Yes <u>    </u> No <u>X</u> Depth (inches): <u>    </u> Water Table Present? Yes <u>    </u> No <u>X</u> Depth (inches): <u>    </u> Saturation Present? Yes <u>X</u> No <u>    </u> Depth (inches): <u>8</u> (includes capillary fringe)	<b>Wetland Hydrology Present?</b> Yes <u>X</u> No <u>    </u>
---	---

Describe Recorded Data (stream gauge, monitoring well, aerial photos, previous inspections), if available:

Remarks:



**VEGETATION – Use scientific names of plants.**

Sampling Point: SP-03

	Absolute % Cover	Dominant Species?	Indicator Status
<b>Tree Stratum</b> (Plot size: <u>30</u> )			
1. <u>Rhamnus cathartica</u>	<u>60</u>	<u>Yes</u>	<u>FAC</u>
2. _____	_____	_____	_____
3. _____	_____	_____	_____
4. _____	_____	_____	_____
5. _____	_____	_____	_____
6. _____	_____	_____	_____
7. _____	_____	_____	_____
	<u>60</u> =Total Cover		
<b>Sapling/Shrub Stratum</b> (Plot size: <u>15</u> )			
1. <u>Rhamnus cathartica</u>	<u>40</u>	<u>Yes</u>	<u>FAC</u>
2. <u>Cornus amomum</u>	<u>35</u>	<u>Yes</u>	<u>FACW</u>
3. _____	_____	_____	_____
4. _____	_____	_____	_____
5. _____	_____	_____	_____
6. _____	_____	_____	_____
7. _____	_____	_____	_____
	<u>75</u> =Total Cover		
<b>Herb Stratum</b> (Plot size: <u>5</u> )			
1. <u>Unknown Sphagnum spp.</u>	<u>45</u>	<u>Yes</u>	<u>FAC</u>
2. <u>Rhamnus cathartica</u>	<u>30</u>	<u>Yes</u>	<u>FAC</u>
3. <u>Fragaria vesca</u>	<u>20</u>	<u>No</u>	<u>UPL</u>
4. <u>Cornus amomum</u>	<u>10</u>	<u>No</u>	<u>FACW</u>
5. _____	_____	_____	_____
6. _____	_____	_____	_____
7. _____	_____	_____	_____
8. _____	_____	_____	_____
9. _____	_____	_____	_____
10. _____	_____	_____	_____
11. _____	_____	_____	_____
12. _____	_____	_____	_____
	<u>105</u> =Total Cover		
<b>Woody Vine Stratum</b> (Plot size: <u>15</u> )			
1. _____	_____	_____	_____
2. _____	_____	_____	_____
3. _____	_____	_____	_____
4. _____	_____	_____	_____
	_____ =Total Cover		

**Dominance Test worksheet:**

Number of Dominant Species That Are OBL, FACW, or FAC: 5 (A)

Total Number of Dominant Species Across All Strata: 5 (B)

Percent of Dominant Species That Are OBL, FACW, or FAC: 100.0% (A/B)

**Prevalence Index worksheet:**

Total % Cover of:	Multiply by:
OBL species _____	x 1 = _____
FACW species _____	x 2 = _____
FAC species _____	x 3 = _____
FACU species _____	x 4 = _____
UPL species _____	x 5 = _____
Column Totals: _____	(A) _____ (B)
Prevalence Index = B/A = _____	

**Hydrophytic Vegetation Indicators:**

1 - Rapid Test for Hydrophytic Vegetation

2 - Dominance Test is >50%

3 - Prevalence Index is  $\leq 3.0$ <sup>1</sup>

4 - Morphological Adaptations<sup>1</sup> (Provide supporting data in Remarks or on a separate sheet)

Problematic Hydrophytic Vegetation<sup>1</sup> (Explain)

<sup>1</sup>Indicators of hydric soil and wetland hydrology must be present, unless disturbed or problematic.

**Definitions of Vegetation Strata:**

**Tree** – Woody plants 3 in. (7.6 cm) or more in diameter at breast height (DBH), regardless of height.

**Sapling/shrub** – Woody plants less than 3 in. DBH and greater than or equal to 3.28 ft (1 m) tall.

**Herb** – All herbaceous (non-woody) plants, regardless of size, and woody plants less than 3.28 ft tall.

**Woody vines** – All woody vines greater than 3.28 ft in height.

**Hydrophytic Vegetation Present?** Yes X No \_\_\_\_\_

Remarks: (Include photo numbers here or on a separate sheet.)  
 Unknown Sphagnum spp. was assigned FAC indicator status

**SOIL**

Sampling Point: SP-03

**Profile Description: (Describe to the depth needed to document the indicator or confirm the absence of indicators.)**

Depth (inches)	Matrix		Redox Features				Texture	Remarks
	Color (moist)	%	Color (moist)	%	Type <sup>1</sup>	Loc <sup>2</sup>		
0-5	10YR 3/1	100					Loamy/Clayey	
5-12	10YR 4/1	98	10YR 4/4	2	C	M	Loamy/Clayey	Distinct redox concentrations

<sup>1</sup>Type: C=Concentration, D=Depletion, RM=Reduced Matrix, MS=Masked Sand Grains. <sup>2</sup>Location: PL=Pore Lining, M=Matrix.

<b>Hydric Soil Indicators:</b>		<b>Indicators for Problematic Hydric Soils<sup>3</sup>:</b>
<input type="checkbox"/> Histosol (A1)	<input type="checkbox"/> Polyvalue Below Surface (S8) (LRR R, MLRA 149B)	<input type="checkbox"/> 2 cm Muck (A10) (LRR K, L, MLRA 149B)
<input type="checkbox"/> Histic Epipedon (A2)	<input type="checkbox"/> Thin Dark Surface (S9) (LRR R, MLRA 149B)	<input type="checkbox"/> Coast Prairie Redox (A16) (LRR K, L, R)
<input type="checkbox"/> Black Histic (A3)	<input type="checkbox"/> High Chroma Sands (S11) (LRR K, L)	<input type="checkbox"/> 5 cm Mucky Peat or Peat (S3) (LRR K, L, R)
<input type="checkbox"/> Hydrogen Sulfide (A4)	<input type="checkbox"/> Loamy Mucky Mineral (F1) (LRR K, L)	<input type="checkbox"/> Polyvalue Below Surface (S8) (LRR K, L)
<input type="checkbox"/> Stratified Layers (A5)	<input type="checkbox"/> Loamy Gleyed Matrix (F2)	<input type="checkbox"/> Thin Dark Surface (S9) (LRR K, L)
<input checked="" type="checkbox"/> Depleted Below Dark Surface (A11)	<input checked="" type="checkbox"/> Depleted Matrix (F3)	<input type="checkbox"/> Iron-Manganese Masses (F12) (LRR K, L, R)
<input type="checkbox"/> Thick Dark Surface (A12)	<input type="checkbox"/> Redox Dark Surface (F6)	<input type="checkbox"/> Piedmont Floodplain Soils (F19) (MLRA 149B)
<input type="checkbox"/> Sandy Mucky Mineral (S1)	<input type="checkbox"/> Depleted Dark Surface (F7)	<input type="checkbox"/> Mesic Spodic (TA6) (MLRA 144A, 145, 149B)
<input type="checkbox"/> Sandy Gleyed Matrix (S4)	<input type="checkbox"/> Redox Depressions (F8)	<input type="checkbox"/> Red Parent Material (F21)
<input type="checkbox"/> Sandy Redox (S5)	<input type="checkbox"/> Marl (F10) (LRR K, L)	<input type="checkbox"/> Very Shallow Dark Surface (F22)
<input type="checkbox"/> Stripped Matrix (S6)		<input type="checkbox"/> Other (Explain in Remarks)
<input type="checkbox"/> Dark Surface (S7)		

<sup>3</sup>Indicators of hydrophytic vegetation and wetland hydrology must be present, unless disturbed or problematic.

<b>Restrictive Layer (if observed):</b> Type: <u>stones, fill</u> Depth (inches): <u>12</u>	<b>Hydric Soil Present?</b> Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
---	---

Remarks:  
variegated fill layer starting at 5"

**WETLAND DETERMINATION DATA FORM – Northcentral and Northeast Region**

Project/Site: Celi Drive BCP Site (BCP Site #C734108) City/County: Onondaga County Sampling Date: 11/14/2017  
 Applicant/Owner: GSP Holdings, Inc. State: NY Sampling Point: SP-04  
 Investigator(s): Melissa Harrison, Gregory Kunka Section, Township, Range: Town of Dewitt  
 Landform (hillside, terrace, etc.): floodplain Local relief (concave, convex, none): none Slope %: 0-2  
 Subregion (LRR or MLRA): LRR L, MLRA 101 Lat: 43.0550523825 Long: -76.0694721944 Datum: NAD 1983  
 Soil Map Unit Name: Cut and fill land (CFL) NWI classification: none

Are climatic / hydrologic conditions on the site typical for this time of year? Yes X No      (If no, explain in Remarks.)  
 Are Vegetation X, Soil     , or Hydrology      significantly disturbed? Are "Normal Circumstances" present? Yes      No X  
 Are Vegetation     , Soil     , or Hydrology      naturally problematic? (If needed, explain any answers in Remarks.)

**SUMMARY OF FINDINGS – Attach site map showing sampling point locations, transects, important features, etc.**

Hydrophytic Vegetation Present? Yes <u>X</u> No <u>    </u> Hydric Soil Present? Yes <u>X</u> No <u>    </u> Wetland Hydrology Present? Yes <u>X</u> No <u>    </u>	<b>Is the Sampled Area within a Wetland?</b> Yes <u>X</u> No <u>    </u> If yes, optional Wetland Site ID: <u>    </u>
Remarks: (Explain alternative procedures here or in a separate report.) PEM Area where point was taken in a maintained ROW for power lines.	

**HYDROLOGY**

<b>Wetland Hydrology Indicators:</b> Primary Indicators (minimum of one is required: check all that apply)	<b>Secondary Indicators (minimum of two required)</b>
<input type="checkbox"/> Surface Water (A1) <input type="checkbox"/> Water-Stained Leaves (B9) <input checked="" type="checkbox"/> High Water Table (A2) <input type="checkbox"/> Aquatic Fauna (B13) <input checked="" type="checkbox"/> Saturation (A3) <input type="checkbox"/> Marl Deposits (B15) <input type="checkbox"/> Water Marks (B1) <input type="checkbox"/> Hydrogen Sulfide Odor (C1) <input type="checkbox"/> Sediment Deposits (B2) <input type="checkbox"/> Oxidized Rhizospheres on Living Roots (C3) <input type="checkbox"/> Drift Deposits (B3) <input type="checkbox"/> Presence of Reduced Iron (C4) <input type="checkbox"/> Algal Mat or Crust (B4) <input type="checkbox"/> Recent Iron Reduction in Tilled Soils (C6) <input type="checkbox"/> Iron Deposits (B5) <input type="checkbox"/> Thin Muck Surface (C7) <input type="checkbox"/> Inundation Visible on Aerial Imagery (B7) <input type="checkbox"/> Other (Explain in Remarks) <input type="checkbox"/> Sparsely Vegetated Concave Surface (B8)	<input type="checkbox"/> Surface Soil Cracks (B6) <input type="checkbox"/> Drainage Patterns (B10) <input type="checkbox"/> Moss Trim Lines (B16) <input type="checkbox"/> Dry-Season Water Table (C2) <input type="checkbox"/> Crayfish Burrows (C8) <input type="checkbox"/> Saturation Visible on Aerial Imagery (C9) <input type="checkbox"/> Stunted or Stressed Plants (D1) <input checked="" type="checkbox"/> Geomorphic Position (D2) <input type="checkbox"/> Shallow Aquitard (D3) <input type="checkbox"/> Microtopographic Relief (D4) <input checked="" type="checkbox"/> FAC-Neutral Test (D5)
<b>Field Observations:</b> Surface Water Present? Yes <u>    </u> No <u>X</u> Depth (inches): <u>    </u> Water Table Present? Yes <u>X</u> No <u>    </u> Depth (inches): <u>3</u> Saturation Present? Yes <u>X</u> No <u>    </u> Depth (inches): <u>0</u> (includes capillary fringe)	<b>Wetland Hydrology Present?</b> Yes <u>X</u> No <u>    </u>
Describe Recorded Data (stream gauge, monitoring well, aerial photos, previous inspections), if available:	
Remarks:	

**VEGETATION – Use scientific names of plants.**

Sampling Point: SP-04

	Absolute % Cover	Dominant Species?	Indicator Status	
<b>Tree Stratum</b> (Plot size: <u>30</u> )				<b>Dominance Test worksheet:</b> Number of Dominant Species That Are OBL, FACW, or FAC: <u>2</u> (A) Total Number of Dominant Species Across All Strata: <u>2</u> (B) Percent of Dominant Species That Are OBL, FACW, or FAC: <u>100.0%</u> (A/B)
1.				
2.				
3.				
4.				
5.				
6.				
7.				
=Total Cover				<b>Prevalence Index worksheet:</b> Total % Cover of: _____ Multiply by: _____ OBL species _____ x 1 = _____ FACW species _____ x 2 = _____ FAC species _____ x 3 = _____ FACU species _____ x 4 = _____ UPL species _____ x 5 = _____ Column Totals: _____ (A) _____ (B) Prevalence Index = B/A = _____
<b>Sapling/Shrub Stratum</b> (Plot size: <u>15</u> )				
1.	<u>5</u>	<u>Yes</u>	<u>FAC</u>	
2.				
3.				
4.				
5.				
6.				
7.				
=Total Cover				
<b>Herb Stratum</b> (Plot size: <u>5</u> )				<b>Hydrophytic Vegetation Indicators:</b> <u>1</u> - Rapid Test for Hydrophytic Vegetation <u>X</u> 2 - Dominance Test is >50% <u>3</u> - Prevalence Index is ≤3.0 <sup>1</sup> <u>4</u> - Morphological Adaptations <sup>1</sup> (Provide supporting data in Remarks or on a separate sheet) _____ Problematic Hydrophytic Vegetation <sup>1</sup> (Explain) <sup>1</sup> Indicators of hydric soil and wetland hydrology must be present, unless disturbed or problematic.
1.	<u>95</u>	<u>Yes</u>	<u>FACW</u>	
2.	<u>20</u>	<u>No</u>	<u>FAC</u>	
3.	<u>10</u>	<u>No</u>	<u>FACU</u>	
4.	<u>5</u>	<u>No</u>	<u>FAC</u>	
5.				
6.				
7.				
8.				
9.				
10.				
11.				
12.				
=Total Cover				
<b>Woody Vine Stratum</b> (Plot size: <u>15</u> )				<b>Definitions of Vegetation Strata:</b> <b>Tree</b> – Woody plants 3 in. (7.6 cm) or more in diameter at breast height (DBH), regardless of height. <b>Sapling/shrub</b> – Woody plants less than 3 in. DBH and greater than or equal to 3.28 ft (1 m) tall. <b>Herb</b> – All herbaceous (non-woody) plants, regardless of size, and woody plants less than 3.28 ft tall. <b>Woody vines</b> – All woody vines greater than 3.28 ft in height.
1.				
2.				
3.				
4.				
=Total Cover				
Remarks: (Include photo numbers here or on a separate sheet.) Unknown Sphagnum spp. was assigned FAC indicator status				<b>Hydrophytic Vegetation Present?</b> Yes <u>X</u> No _____

**SOIL**

Sampling Point SP-04

**Profile Description: (Describe to the depth needed to document the indicator or confirm the absence of indicators.)**

Depth (inches)	Matrix		Redox Features				Texture	Remarks
	Color (moist)	%	Color (moist)	%	Type <sup>1</sup>	Loc <sup>2</sup>		
0-4	10YR 3/1	100					Loamy/Clayey	
4-18	10YR 4/1	98	10YR 4/4	2	C	M	Loamy/Clayey	Distinct redox concentrations

<sup>1</sup>Type: C=Concentration, D=Depletion, RM=Reduced Matrix, MS=Masked Sand Grains. <sup>2</sup>Location: PL=Pore Lining, M=Matrix.

- |   |   |  |
|---|---|--|
| <p><b>Hydric Soil Indicators:</b></p> <p><input type="checkbox"/> Histosol (A1)</p> <p><input type="checkbox"/> Histic Epipedon (A2)</p> <p><input type="checkbox"/> Black Histic (A3)</p> <p><input type="checkbox"/> Hydrogen Sulfide (A4)</p> <p><input type="checkbox"/> Stratified Layers (A5)</p> <p><input checked="" type="checkbox"/> Depleted Below Dark Surface (A11)</p> <p><input type="checkbox"/> Thick Dark Surface (A12)</p> <p><input type="checkbox"/> Sandy Mucky Mineral (S1)</p> <p><input type="checkbox"/> Sandy Gleyed Matrix (S4)</p> <p><input type="checkbox"/> Sandy Redox (S5)</p> <p><input type="checkbox"/> Stripped Matrix (S6)</p> <p><input type="checkbox"/> Dark Surface (S7)</p> | <p><input type="checkbox"/> Polyvalue Below Surface (S8) (LRR R, MLRA 149B)</p> <p><input type="checkbox"/> Thin Dark Surface (S9) (LRR R, MLRA 149B)</p> <p><input type="checkbox"/> High Chroma Sands (S11) (LRR K, L)</p> <p><input type="checkbox"/> Loamy Mucky Mineral (F1) (LRR K, L)</p> <p><input type="checkbox"/> Loamy Gleyed Matrix (F2)</p> <p><input checked="" type="checkbox"/> Depleted Matrix (F3)</p> <p><input type="checkbox"/> Redox Dark Surface (F6)</p> <p><input type="checkbox"/> Depleted Dark Surface (F7)</p> <p><input type="checkbox"/> Redox Depressions (F8)</p> <p><input type="checkbox"/> Marl (F10) (LRR K, L)</p> | <p><b>Indicators for Problematic Hydric Soils<sup>3</sup>:</b></p> <p><input type="checkbox"/> 2 cm Muck (A10) (LRR K, L, MLRA 149B)</p> <p><input type="checkbox"/> Coast Prairie Redox (A16) (LRR K, L, R)</p> <p><input type="checkbox"/> 5 cm Mucky Peat or Peat (S3) (LRR K, L, R)</p> <p><input type="checkbox"/> Polyvalue Below Surface (S8) (LRR K, L)</p> <p><input type="checkbox"/> Thin Dark Surface (S9) (LRR K, L)</p> <p><input type="checkbox"/> Iron-Manganese Masses (F12) (LRR K, L, R)</p> <p><input type="checkbox"/> Piedmont Floodplain Soils (F19) (MLRA 149B)</p> <p><input type="checkbox"/> Mesic Spodic (TA6) (MLRA 144A, 145, 149B)</p> <p><input type="checkbox"/> Red Parent Material (F21)</p> <p><input type="checkbox"/> Very Shallow Dark Surface (F22)</p> <p><input type="checkbox"/> Other (Explain in Remarks)</p> |
|---|---|--|

<sup>3</sup>Indicators of hydrophytic vegetation and wetland hydrology must be present, unless disturbed or problematic.

<p><b>Restrictive Layer (if observed):</b></p> <p>Type: _____</p> <p>Depth (inches): _____</p>	<p>Hydric Soil Present?    Yes <input checked="" type="checkbox"/>    No <input type="checkbox"/></p>
--	---

Remarks:  
 stony soils

**WETLAND DETERMINATION DATA FORM – Northcentral and Northeast Region**

Project/Site: Celi Drive BCP Site (BCP Site #C734108) City/County: Onondaga County Sampling Date: 11/14/2017  
 Applicant/Owner: GSP Holdings, Inc. State: NY Sampling Point: SP-05  
 Investigator(s): Melissa Harrison, Gregory Kunka Section, Township, Range: Town of Dewitt  
 Landform (hillside, terrace, etc.): floodplain, upland access road Local relief (concave, convex, none): none Slope %: 0-2  
 Subregion (LRR or MLRA): LRR L, MLRA 101 Lat: 43.0549964809 Long: -76.0692682257 Datum: NAD 1983  
 Soil Map Unit Name: Cut and fill land (CFL) NWI classification: none

Are climatic / hydrologic conditions on the site typical for this time of year? Yes X No      (If no, explain in Remarks.)  
 Are Vegetation X, Soil X, or Hydrology X significantly disturbed? Are "Normal Circumstances" present? Yes      No X  
 Are Vegetation     , Soil     , or Hydrology      naturally problematic? (If needed, explain any answers in Remarks.)

**SUMMARY OF FINDINGS – Attach site map showing sampling point locations, transects, important features, etc.**

Hydrophytic Vegetation Present? Yes <u>    </u> No <u>X</u> Hydric Soil Present? Yes <u>    </u> No <u>X</u> Wetland Hydrology Present? Yes <u>    </u> No <u>X</u>	Is the Sampled Area within a Wetland? Yes <u>    </u> No <u>X</u> If yes, optional Wetland Site ID: <u>    </u>
Remarks: (Explain alternative procedures here or in a separate report.) Area is mowed and maintained as an access road. Soils comprised of what is likely historic fill.	

**HYDROLOGY**

<b>Wetland Hydrology Indicators:</b> Primary Indicators (minimum of one is required; check all that apply)	<b>Secondary Indicators (minimum of two required)</b>
<input type="checkbox"/> Surface Water (A1) <input type="checkbox"/> Water-Stained Leaves (B9) <input type="checkbox"/> High Water Table (A2) <input type="checkbox"/> Aquatic Fauna (B13) <input type="checkbox"/> Saturation (A3) <input type="checkbox"/> Marl Deposits (B15) <input type="checkbox"/> Water Marks (B1) <input type="checkbox"/> Hydrogen Sulfide Odor (C1) <input type="checkbox"/> Sediment Deposits (B2) <input type="checkbox"/> Oxidized Rhizospheres on Living Roots (C3) <input type="checkbox"/> Drift Deposits (B3) <input type="checkbox"/> Presence of Reduced Iron (C4) <input type="checkbox"/> Algal Mat or Crust (B4) <input type="checkbox"/> Recent Iron Reduction in Tilled Soils (C6) <input type="checkbox"/> Iron Deposits (B5) <input type="checkbox"/> Thin Muck Surface (C7) <input type="checkbox"/> Inundation Visible on Aerial Imagery (B7) <input type="checkbox"/> Other (Explain in Remarks) <input type="checkbox"/> Sparsely Vegetated Concave Surface (B8)	<input type="checkbox"/> Surface Soil Cracks (B6) <input type="checkbox"/> Drainage Patterns (B10) <input type="checkbox"/> Moss Trim Lines (B16) <input type="checkbox"/> Dry-Season Water Table (C2) <input type="checkbox"/> Crayfish Burrows (C8) <input type="checkbox"/> Saturation Visible on Aerial Imagery (C9) <input type="checkbox"/> Stunted or Stressed Plants (D1) <input checked="" type="checkbox"/> Geomorphic Position (D2) <input type="checkbox"/> Shallow Aquitard (D3) <input type="checkbox"/> Microtopographic Relief (D4) <input type="checkbox"/> FAC-Neutral Test (D5)
<b>Field Observations:</b> Surface Water Present? Yes <u>    </u> No <u>X</u> Depth (inches): <u>    </u> Water Table Present? Yes <u>    </u> No <u>X</u> Depth (inches): <u>    </u> Saturation Present? Yes <u>    </u> No <u>X</u> Depth (inches): <u>    </u> (includes capillary fringe)	Wetland Hydrology Present? Yes <u>    </u> No <u>X</u>
Describe Recorded Data (stream gauge, monitoring well, aerial photos, previous inspections), if available:	
Remarks:	

**VEGETATION – Use scientific names of plants.**

Sampling Point: SP-05

<u>Tree Stratum</u> (Plot size: <u>30</u> )		Absolute % Cover	Dominant Species?	Indicator Status
1.	_____	_____	_____	_____
2.	_____	_____	_____	_____
3.	_____	_____	_____	_____
4.	_____	_____	_____	_____
5.	_____	_____	_____	_____
6.	_____	_____	_____	_____
7.	_____	_____	_____	_____
		_____ =Total Cover		
<u>Sapling/Shrub Stratum</u> (Plot size: <u>15</u> )		Absolute % Cover	Dominant Species?	Indicator Status
1.	_____	_____	_____	_____
2.	_____	_____	_____	_____
3.	_____	_____	_____	_____
4.	_____	_____	_____	_____
5.	_____	_____	_____	_____
6.	_____	_____	_____	_____
7.	_____	_____	_____	_____
		_____ =Total Cover		
<u>Herb Stratum</u> (Plot size: <u>5</u> )		Absolute % Cover	Dominant Species?	Indicator Status
1.	<u>Poa pratensis</u>	<u>35</u>	<u>Yes</u>	<u>FACU</u>
2.	<u>Poa compressa</u>	<u>25</u>	<u>Yes</u>	<u>FACU</u>
3.	<u>Galium concinnum</u>	<u>10</u>	<u>No</u>	<u>FACU</u>
4.	<u>Plantago lanceolata</u>	<u>10</u>	<u>No</u>	<u>FACU</u>
5.	<u>Fragaria vesca</u>	<u>5</u>	<u>No</u>	<u>UPL</u>
6.	_____	_____	_____	_____
7.	_____	_____	_____	_____
8.	_____	_____	_____	_____
9.	_____	_____	_____	_____
10.	_____	_____	_____	_____
11.	_____	_____	_____	_____
12.	_____	_____	_____	_____
		<u>85</u> =Total Cover		
<u>Woody Vine Stratum</u> (Plot size: <u>15</u> )		Absolute % Cover	Dominant Species?	Indicator Status
1.	_____	_____	_____	_____
2.	_____	_____	_____	_____
3.	_____	_____	_____	_____
4.	_____	_____	_____	_____
		_____ =Total Cover		

**Dominance Test worksheet:**

Number of Dominant Species That Are OBL, FACW, or FAC: 0 (A)

Total Number of Dominant Species Across All Strata: 2 (B)

Percent of Dominant Species That Are OBL, FACW, or FAC: 0.0% (A/B)

---

**Prevalence Index worksheet:**

Total % Cover of:	Multiply by:
OBL species <u>0</u>	x 1 = <u>0</u>
FACW species <u>0</u>	x 2 = <u>0</u>
FAC species <u>0</u>	x 3 = <u>0</u>
FACU species <u>80</u>	x 4 = <u>320</u>
UPL species <u>5</u>	x 5 = <u>25</u>
Column Totals: <u>85</u> (A)	<u>345</u> (B)
Prevalence Index = B/A = <u>4.06</u>	

---

**Hydrophytic Vegetation Indicators:**

   1 - Rapid Test for Hydrophytic Vegetation

   2 - Dominance Test is >50%

   3 - Prevalence Index is ≤3.0<sup>1</sup>

   4 - Morphological Adaptations<sup>1</sup> (Provide supporting data in Remarks or on a separate sheet)

   Problematic Hydrophytic Vegetation<sup>1</sup> (Explain)

<sup>1</sup>Indicators of hydric soil and wetland hydrology must be present, unless disturbed or problematic.

---

**Definitions of Vegetation Strata:**

**Tree** – Woody plants 3 in. (7.6 cm) or more in diameter at breast height (DBH), regardless of height.

**Sapling/shrub** – Woody plants less than 3 in. DBH and greater than or equal to 3.28 ft (1 m) tall.

**Herb** – All herbaceous (non-woody) plants, regardless of size, and woody plants less than 3.28 ft tall.

**Woody vines** – All woody vines greater than 3.28 ft in height.

---

**Hydrophytic Vegetation Present?**      Yes         No X

Remarks: (Include photo numbers here or on a separate sheet.)

**SOIL**

Sampling Point: SP-05

**Profile Description: (Describe to the depth needed to document the indicator or confirm the absence of indicators.)**

Depth (inches)	Matrix		Redox Features				Texture	Remarks
	Color (moist)	%	Color (moist)	%	Type <sup>1</sup>	Loc <sup>2</sup>		
0-10	10YR 3/1	100					Loamy/Clayey	

<sup>1</sup>Type: C=Concentration, D=Depletion, RM=Reduced Matrix, MS=Masked Sand Grains.      <sup>2</sup>Location: PL=Pore Lining, M=Matrix.

<p><b>Hydric Soil Indicators:</b></p> <p><input type="checkbox"/> Histosol (A1)</p> <p><input type="checkbox"/> Histic Epipedon (A2)</p> <p><input type="checkbox"/> Black Histic (A3)</p> <p><input type="checkbox"/> Hydrogen Sulfide (A4)</p> <p><input type="checkbox"/> Stratified Layers (A5)</p> <p><input type="checkbox"/> Depleted Below Dark Surface (A11)</p> <p><input type="checkbox"/> Thick Dark Surface (A12)</p> <p><input type="checkbox"/> Sandy Mucky Mineral (S1)</p> <p><input type="checkbox"/> Sandy Gleyed Matrix (S4)</p> <p><input type="checkbox"/> Sandy Redox (S5)</p> <p><input type="checkbox"/> Stripped Matrix (S6)</p> <p><input type="checkbox"/> Dark Surface (S7)</p>	<p><input type="checkbox"/> Polyvalue Below Surface (S8) (LRR R, MLRA 149B)</p> <p><input type="checkbox"/> Thin Dark Surface (S9) (LRR R, MLRA 149B)</p> <p><input type="checkbox"/> High Chroma Sands (S11) (LRR K, L)</p> <p><input type="checkbox"/> Loamy Mucky Mineral (F1) (LRR K, L)</p> <p><input type="checkbox"/> Loamy Gleyed Matrix (F2)</p> <p><input type="checkbox"/> Depleted Matrix (F3)</p> <p><input type="checkbox"/> Redox Dark Surface (F6)</p> <p><input type="checkbox"/> Depleted Dark Surface (F7)</p> <p><input type="checkbox"/> Redox Depressions (F8)</p> <p><input type="checkbox"/> Marl (F10) (LRR K, L)</p>	<p><b>Indicators for Problematic Hydric Soils<sup>3</sup>:</b></p> <p><input type="checkbox"/> 2 cm Muck (A10) (LRR K, L, MLRA 149B)</p> <p><input type="checkbox"/> Coast Prairie Redox (A16) (LRR K, L, R)</p> <p><input type="checkbox"/> 5 cm Mucky Peat or Peat (S3) (LRR K, L, R)</p> <p><input type="checkbox"/> Polyvalue Below Surface (S8) (LRR K, L)</p> <p><input type="checkbox"/> Thin Dark Surface (S9) (LRR K, L)</p> <p><input type="checkbox"/> Iron-Manganese Masses (F12) (LRR K, L, R)</p> <p><input type="checkbox"/> Piedmont Floodplain Soils (F19) (MLRA 149B)</p> <p><input type="checkbox"/> Mesic Spodic (TA6) (MLRA 144A, 145, 149B)</p> <p><input type="checkbox"/> Red Parent Material (F21)</p> <p><input type="checkbox"/> Very Shallow Dark Surface (F22)</p> <p><input type="checkbox"/> Other (Explain in Remarks)</p>
--	--	--

<sup>3</sup>Indicators of hydrophytic vegetation and wetland hydrology must be present, unless disturbed or problematic.

<p><b>Restrictive Layer (if observed):</b></p> <p>Type: <u>stones, fill</u></p> <p>Depth (inches): <u>10</u></p>	<p>Hydric Soil Present?      Yes <input type="checkbox"/>      No <input checked="" type="checkbox"/></p>
--	---

Remarks:  
 stony soils



**WETLAND DETERMINATION DATA FORM – Northcentral and Northeast Region**

Project/Site: Cell Drive BCP Site (BCP Site #C734108) City/County: Onondaga County Sampling Date: 11/14/2017  
 Applicant/Owner: GSP Holdings, Inc. State: NY Sampling Point: SP-06  
 Investigator(s): Melissa Harrison, Gregory Kunka Section, Township, Range: Town of Dewitt  
 Landform (hillside, terrace, etc.): floodplain Local relief (concave, convex, none): none Slope %: 0-2  
 Subregion (LRR or MLRA): LRR L, MLRA 101 Lat: 43.0539707839 Long: -76.0690777228 Datum: NAD 1983  
 Soil Map Unit Name: Cut and fill land (CFL) NWI classification: none

Are climatic / hydrologic conditions on the site typical for this time of year? Yes X No      (If no, explain in Remarks.)  
 Are Vegetation X, Soil X, or Hydrology X significantly disturbed? Are "Normal Circumstances" present? Yes      No X  
 Are Vegetation     , Soil     , or Hydrology      naturally problematic? (If needed, explain any answers in Remarks.)

**SUMMARY OF FINDINGS – Attach site map showing sampling point locations, transects, important features, etc.**

Hydrophytic Vegetation Present? Yes <u>X</u> No <u>    </u> Hydric Soil Present? Yes <u>X</u> No <u>    </u> Wetland Hydrology Present? Yes <u>X</u> No <u>    </u>	Is the Sampled Area within a Wetland? Yes <u>X</u> No <u>    </u> If yes, optional Wetland Site ID: <u>    </u>
Remarks: (Explain alternative procedures here or in a separate report.) Area is impacted from parking lot runoff and may have recently been leveled according to an adjacent property owner.	

**HYDROLOGY**

<b>Wetland Hydrology Indicators:</b> Primary Indicators (minimum of one is required; check all that apply)	<b>Secondary Indicators (minimum of two required)</b>
<input type="checkbox"/> Surface Water (A1) <input type="checkbox"/> Water-Stained Leaves (B9) <input type="checkbox"/> High Water Table (A2) <input type="checkbox"/> Aquatic Fauna (B13) <input type="checkbox"/> Saturation (A3) <input type="checkbox"/> Marl Deposits (B15) <input type="checkbox"/> Water Marks (B1) <input type="checkbox"/> Hydrogen Sulfide Odor (C1) <input type="checkbox"/> Sediment Deposits (B2) <input type="checkbox"/> Oxidized Rhizospheres on Living Roots (C3) <input type="checkbox"/> Drift Deposits (B3) <input type="checkbox"/> Presence of Reduced Iron (C4) <input type="checkbox"/> Algal Mat or Crust (B4) <input type="checkbox"/> Recent Iron Reduction in Tilled Soils (C6) <input type="checkbox"/> Iron Deposits (B5) <input type="checkbox"/> Thin Muck Surface (C7) <input type="checkbox"/> Inundation Visible on Aerial Imagery (B7) <input type="checkbox"/> Other (Explain in Remarks) <input type="checkbox"/> Sparsely Vegetated Concave Surface (B8)	<input type="checkbox"/> Surface Soil Cracks (B6) <input type="checkbox"/> Drainage Patterns (B10) <input type="checkbox"/> Moss Trim Lines (B16) <input type="checkbox"/> Dry-Season Water Table (C2) <input type="checkbox"/> Crayfish Burrows (C8) <input type="checkbox"/> Saturation Visible on Aerial Imagery (C9) <input type="checkbox"/> Stunted or Stressed Plants (D1) <input checked="" type="checkbox"/> Geomorphic Position (D2) <input type="checkbox"/> Shallow Aquitard (D3) <input type="checkbox"/> Microtopographic Relief (D4) <input checked="" type="checkbox"/> FAC-Neutral Test (D5)

<b>Field Observations:</b> Surface Water Present? Yes <u>    </u> No <u>X</u> Depth (inches): <u>    </u> Water Table Present? Yes <u>    </u> No <u>X</u> Depth (inches): <u>    </u> Saturation Present? Yes <u>    </u> No <u>X</u> Depth (inches): <u>    </u> (includes capillary fringe)	Wetland Hydrology Present? Yes <u>X</u> No <u>    </u>
--	--

Describe Recorded Data (stream gauge, monitoring well, aerial photos, previous inspections), if available:

Remarks:

**VEGETATION – Use scientific names of plants.**

Sampling Point: SP-06

Tree Stratum (Plot size: <u>30</u> )	Absolute % Cover	Dominant Species?	Indicator Status
1. _____	_____	_____	_____
2. _____	_____	_____	_____
3. _____	_____	_____	_____
4. _____	_____	_____	_____
5. _____	_____	_____	_____
6. _____	_____	_____	_____
7. _____	_____	_____	_____
	_____ =Total Cover		

Sapling/Shrub Stratum (Plot size: <u>15</u> )	Absolute % Cover	Dominant Species?	Indicator Status
1. <u>Cornus alba</u>	<u>5</u>	<u>Yes</u>	<u>FACW</u>
2. _____	_____	_____	_____
3. _____	_____	_____	_____
4. _____	_____	_____	_____
5. _____	_____	_____	_____
6. _____	_____	_____	_____
7. _____	_____	_____	_____
	<u>5</u> =Total Cover		

Herb Stratum (Plot size: <u>5</u> )	Absolute % Cover	Dominant Species?	Indicator Status
1. <u>Oenothera biennis</u>	<u>80</u>	<u>Yes</u>	<u>FACU</u>
2. <u>Cornus alba</u>	<u>20</u>	<u>No</u>	<u>FACW</u>
3. <u>Phragmites australis</u>	<u>15</u>	<u>No</u>	<u>FACW</u>
4. <u>Lythrum salicaria</u>	<u>5</u>	<u>No</u>	<u>OBL</u>
5. _____	_____	_____	_____
6. _____	_____	_____	_____
7. _____	_____	_____	_____
8. _____	_____	_____	_____
9. _____	_____	_____	_____
10. _____	_____	_____	_____
11. _____	_____	_____	_____
12. _____	_____	_____	_____
	<u>120</u> =Total Cover		

Woody Vine Stratum (Plot size: <u>15</u> )	Absolute % Cover	Dominant Species?	Indicator Status
1. _____	_____	_____	_____
2. _____	_____	_____	_____
3. _____	_____	_____	_____
4. _____	_____	_____	_____
	_____ =Total Cover		

**Dominance Test worksheet:**

Number of Dominant Species That Are OBL, FACW, or FAC: 1 (A)

Total Number of Dominant Species Across All Strata: 2 (B)

Percent of Dominant Species That Are OBL, FACW, or FAC: 50.0% (A/B)

**Prevalence Index worksheet:**

Total % Cover of:	Multiply by:
OBL species <u>5</u>	x 1 = <u>5</u>
FACW species <u>40</u>	x 2 = <u>80</u>
FAC species <u>0</u>	x 3 = <u>0</u>
FACU species <u>80</u>	x 4 = <u>320</u>
UPL species <u>0</u>	x 5 = <u>0</u>
Column Totals: <u>125</u> (A)	<u>405</u> (B)
Prevalence Index = B/A = <u>3.24</u>	

- Hydrophytic Vegetation Indicators:**
- 1 - Rapid Test for Hydrophytic Vegetation
  - 2 - Dominance Test is >50%
  - 3 - Prevalence Index is ≤3.0<sup>1</sup>
  - 4 - Morphological Adaptations<sup>1</sup> (Provide supporting data in Remarks or on a separate sheet)
  - X Problematic Hydrophytic Vegetation<sup>1</sup> (Explain)
- <sup>1</sup>Indicators of hydric soil and wetland hydrology must be present, unless disturbed or problematic.

**Definitions of Vegetation Strata:**

**Tree** – Woody plants 3 in. (7.6 cm) or more in diameter at breast height (DBH), regardless of height.

**Sapling/shrub** – Woody plants less than 3 in. DBH and greater than or equal to 3.28 ft (1 m) tall.

**Herb** – All herbaceous (non-woody) plants, regardless of size, and woody plants less than 3.28 ft tall.

**Woody vines** – All woody vines greater than 3.28 ft in height.

**Hydrophytic Vegetation Present?**      Yes X      No   

Remarks: (Include photo numbers here or on a separate sheet.)

The wetland area documented by SP06 has been disturbed on multiple occasions. The property owner adjacent to the area informed GHD that the area has been cleared previously and when the drainage channel needed maintenance, the dredged material was placed in this area. Clearing and placement of dredged material likely interfered with hydrology, vegetative colonization, and soil interactions that would affect wetland indicators.

**SOIL**

Sampling Point: SP-06

**Profile Description: (Describe to the depth needed to document the indicator or confirm the absence of indicators.)**

Depth (inches)	Matrix		Redox Features				Texture	Remarks
	Color (moist)	%	Color (moist)	%	Type <sup>1</sup>	Loc <sup>2</sup>		
0-8	10YR 3/1	100					Loamy/Clayey	

<sup>1</sup>Type: C=Concentration, D=Depletion, RM=Reduced Matrix, MS=Masked Sand Grains. <sup>2</sup>Location: PL=Pore Lining, M=Matrix.

- |   |   |   |
|---|---|---|
| <p><b>Hydric Soil Indicators:</b></p> <ul style="list-style-type: none"> <li><input type="checkbox"/> Histosol (A1)</li> <li><input type="checkbox"/> Histic Epipedon (A2)</li> <li><input type="checkbox"/> Black Histic (A3)</li> <li><input type="checkbox"/> Hydrogen Sulfide (A4)</li> <li><input type="checkbox"/> Stratified Layers (A5)</li> <li><input type="checkbox"/> Depleted Below Dark Surface (A11)</li> <li><input type="checkbox"/> Thick Dark Surface (A12)</li> <li><input type="checkbox"/> Sandy Mucky Mineral (S1)</li> <li><input type="checkbox"/> Sandy Gleyed Matrix (S4)</li> <li><input type="checkbox"/> Sandy Redox (S5)</li> <li><input type="checkbox"/> Stripped Matrix (S6)</li> <li><input type="checkbox"/> Dark Surface (S7)</li> </ul> | <ul style="list-style-type: none"> <li><input type="checkbox"/> Polyvalue Below Surface (S8) (LRR R, <b>MLRA 149B</b>)</li> <li><input type="checkbox"/> Thin Dark Surface (S9) (LRR R, <b>MLRA 149B</b>)</li> <li><input type="checkbox"/> High Chroma Sands (S11) (LRR K, L)</li> <li><input type="checkbox"/> Loamy Mucky Mineral (F1) (LRR K, L)</li> <li><input type="checkbox"/> Loamy Gleyed Matrix (F2)</li> <li><input type="checkbox"/> Depleted Matrix (F3)</li> <li><input type="checkbox"/> Redox Dark Surface (F6)</li> <li><input type="checkbox"/> Depleted Dark Surface (F7)</li> <li><input type="checkbox"/> Redox Depressions (F8)</li> <li><input type="checkbox"/> Marl (F10) (LRR K, L)</li> </ul> | <p><b>Indicators for Problematic Hydric Soils<sup>3</sup>:</b></p> <ul style="list-style-type: none"> <li><input type="checkbox"/> 2 cm Muck (A10) (LRR K, L, <b>MLRA 149B</b>)</li> <li><input type="checkbox"/> Coast Prairie Redox (A16) (LRR K, L, R)</li> <li><input type="checkbox"/> 5 cm Mucky Peat or Peat (S3) (LRR K, L, R)</li> <li><input type="checkbox"/> Polyvalue Below Surface (S8) (LRR K, L)</li> <li><input type="checkbox"/> Thin Dark Surface (S9) (LRR K, L)</li> <li><input type="checkbox"/> Iron-Manganese Masses (F12) (LRR K, L, R)</li> <li><input type="checkbox"/> Piedmont Floodplain Soils (F19) (<b>MLRA 149B</b>)</li> <li><input type="checkbox"/> Mesic Spodic (TA6) (<b>MLRA 144A, 145, 149B</b>)</li> <li><input type="checkbox"/> Red Parent Material (F21)</li> <li><input type="checkbox"/> Very Shallow Dark Surface (F22)</li> <li><input checked="" type="checkbox"/> Other (Explain in Remarks)</li> </ul> |
|---|---|---|

<sup>3</sup>Indicators of hydrophytic vegetation and wetland hydrology must be present, unless disturbed or problematic.

<p><b>Restrictive Layer (if observed):</b></p> Type: <u>stones, fill</u> Depth (inches): <u>8</u>	<p style="text-align: right;"><b>Hydric Soil Present?</b>    Yes <u>X</u>    No <u>    </u></p>
--	---

Remarks:  
Very stony soils and asphalt pieces

The previous disturbance to this area as a result of placing dredge and fill material makes it difficult to determine the presence of hydric soil indicators. Similar to SP02-4, it is likely that the soil would exhibit indicators A11 and F3. The soil would meet the value and chroma requirements for A11 if the surface layer extended to a depleted matrix. However, due to refusal at 8", the presence of a depleted matrix below 8" could not be determined. Therefore, given the disturbance history of the area, it is assumed that a depleted matrix would be present below 8", satisfying hydric soil criterion.

**WETLAND DETERMINATION DATA FORM – Northcentral and Northeast Region**

Project/Site: Cell Drive BCP Site (BCP Site #C734108) City/County: Onondaga County Sampling Date: 11/15/2017  
 Applicant/Owner: GSP Holdings, Inc. State: NY Sampling Point: SP-07  
 Investigator(s): Melissa Harrison, Gregory Kunka Section, Township, Range: Town of Dewitt  
 Landform (hillside, terrace, etc.): foodplain Local relief (concave, convex, none): convex Slope %: 2-4  
 Subregion (LRR or MLRA): LRR L, MLRA 101 Lat: 43.0539707839 Long: -76.0690777228 Datum: NAD 1983  
 Soil Map Unit Name: Cut and fill land (CFL) NWI classification: none

Are climatic / hydrologic conditions on the site typical for this time of year? Yes X No      (If no, explain in Remarks.)  
 Are Vegetation     , Soil     , or Hydrology X significantly disturbed? Are "Normal Circumstances" present? Yes      No X  
 Are Vegetation     , Soil     , or Hydrology      naturally problematic? (If needed, explain any answers in Remarks.)

**SUMMARY OF FINDINGS – Attach site map showing sampling point locations, transects, important features, etc.**

Hydrophytic Vegetation Present? Yes <u>X</u> No <u>    </u> Hydric Soil Present? Yes <u>X</u> No <u>    </u> Wetland Hydrology Present? Yes <u>X</u> No <u>    </u>	<b>Is the Sampled Area within a Wetland?</b> Yes <u>X</u> No <u>    </u> If yes, optional Wetland Site ID: <u>    </u>
Remarks: (Explain alternative procedures here or in a separate report.)  PEM	

**HYDROLOGY**

<b>Wetland Hydrology Indicators:</b> Primary Indicators (minimum of one is required; check all that apply)	Secondary Indicators (minimum of two required)
<input type="checkbox"/> Surface Water (A1) <input type="checkbox"/> Water-Stained Leaves (B9) <input checked="" type="checkbox"/> High Water Table (A2) <input type="checkbox"/> Aquatic Fauna (B13) <input checked="" type="checkbox"/> Saturation (A3) <input type="checkbox"/> Marl Deposits (B15) <input type="checkbox"/> Water Marks (B1) <input type="checkbox"/> Hydrogen Sulfide Odor (C1) <input type="checkbox"/> Sediment Deposits (B2) <input type="checkbox"/> Oxidized Rhizospheres on Living Roots (C3) <input type="checkbox"/> Drift Deposits (B3) <input type="checkbox"/> Presence of Reduced Iron (C4) <input type="checkbox"/> Algal Mat or Crust (B4) <input type="checkbox"/> Recent Iron Reduction in Tilled Soils (C6) <input type="checkbox"/> Iron Deposits (B5) <input type="checkbox"/> Thin Muck Surface (C7) <input type="checkbox"/> Inundation Visible on Aerial Imagery (B7) <input type="checkbox"/> Other (Explain in Remarks) <input type="checkbox"/> Sparsely Vegetated Concave Surface (B8)	<input type="checkbox"/> Surface Soil Cracks (B6) <input type="checkbox"/> Drainage Patterns (B10) <input type="checkbox"/> Moss Trim Lines (B16) <input type="checkbox"/> Dry-Season Water Table (C2) <input type="checkbox"/> Crayfish Burrows (C8) <input type="checkbox"/> Saturation Visible on Aerial Imagery (C9) <input type="checkbox"/> Stunted or Stressed Plants (D1) <input checked="" type="checkbox"/> Geomorphic Position (D2) <input type="checkbox"/> Shallow Aquitard (D3) <input type="checkbox"/> Microtopographic Relief (D4) <input checked="" type="checkbox"/> FAC-Neutral Test (D5)
<b>Field Observations:</b> Surface Water Present? Yes <u>    </u> No <u>X</u> Depth (inches): <u>    </u> Water Table Present? Yes <u>X</u> No <u>    </u> Depth (inches): <u>6</u> Saturation Present? Yes <u>X</u> No <u>    </u> Depth (inches): <u>0</u> (includes capillary fringe)	<b>Wetland Hydrology Present?</b> Yes <u>X</u> No <u>    </u>
Describe Recorded Data (stream gauge, monitoring well, aerial photos, previous inspections), if available:	
Remarks:	

**VEGETATION – Use scientific names of plants.**

Sampling Point: SP-07

Tree Stratum (Plot size: <u>30</u> )		Absolute % Cover	Dominant Species?	Indicator Status
1.	<u>Rhamnus cathartica</u>	<u>10</u>	<u>Yes</u>	<u>FAC</u>
2.	_____	_____	_____	_____
3.	_____	_____	_____	_____
4.	_____	_____	_____	_____
5.	_____	_____	_____	_____
6.	_____	_____	_____	_____
7.	_____	_____	_____	_____
		<u>10</u>	=Total Cover	
Sapling/Shrub Stratum (Plot size: <u>15</u> )				
1.	_____	_____	_____	_____
2.	_____	_____	_____	_____
3.	_____	_____	_____	_____
4.	_____	_____	_____	_____
5.	_____	_____	_____	_____
6.	_____	_____	_____	_____
7.	_____	_____	_____	_____
		_____	=Total Cover	
Herb Stratum (Plot size: <u>5</u> )				
1.	<u>Phragmites australis</u>	<u>95</u>	<u>Yes</u>	<u>FACW</u>
2.	<u>Cirsium vulgare</u>	<u>10</u>	<u>No</u>	<u>FACU</u>
3.	_____	_____	_____	_____
4.	_____	_____	_____	_____
5.	_____	_____	_____	_____
6.	_____	_____	_____	_____
7.	_____	_____	_____	_____
8.	_____	_____	_____	_____
9.	_____	_____	_____	_____
10.	_____	_____	_____	_____
11.	_____	_____	_____	_____
12.	_____	_____	_____	_____
		<u>105</u>	=Total Cover	
Woody Vine Stratum (Plot size: <u>15</u> )				
1.	_____	_____	_____	_____
2.	_____	_____	_____	_____
3.	_____	_____	_____	_____
4.	_____	_____	_____	_____
		_____	=Total Cover	

**Dominance Test worksheet:**

Number of Dominant Species That Are OBL, FACW, or FAC: 2 (A)

Total Number of Dominant Species Across All Strata: 2 (B)

Percent of Dominant Species That Are OBL, FACW, or FAC: 100.0% (A/B)

**Prevalence Index worksheet:**

Total % Cover of:	Multiply by:
OBL species _____	x 1 = _____
FACW species _____	x 2 = _____
FAC species _____	x 3 = _____
FACU species _____	x 4 = _____
UPL species _____	x 5 = _____
Column Totals: _____	(A) _____ (B) _____
Prevalence Index = B/A = _____	

**Hydrophytic Vegetation Indicators:**

   1 - Rapid Test for Hydrophytic Vegetation

X 2 - Dominance Test is >50%

   3 - Prevalence Index is ≤3.0<sup>1</sup>

   4 - Morphological Adaptations<sup>1</sup> (Provide supporting data in Remarks or on a separate sheet)

   Problematic Hydrophytic Vegetation<sup>1</sup> (Explain)

<sup>1</sup>Indicators of hydric soil and wetland hydrology must be present, unless disturbed or problematic.

**Definitions of Vegetation Strata:**

**Tree** – Woody plants 3 in. (7.6 cm) or more in diameter at breast height (DBH), regardless of height.

**Sapling/shrub** – Woody plants less than 3 in. DBH and greater than or equal to 3.28 ft (1 m) tall.

**Herb** – All herbaceous (non-woody) plants, regardless of size, and woody plants less than 3.28 ft tall.

**Woody vines** – All woody vines greater than 3.28 ft in height.

**Hydrophytic Vegetation Present?** Yes X No   

Remarks: (Include photo numbers here or on a separate sheet.)

SOIL

Sampling Point: SP-07

Profile Description: (Describe to the depth needed to document the indicator or confirm the absence of indicators.)

Depth (inches)	Matrix		Redox Features				Texture	Remarks
	Color (moist)	%	Color (moist)	%	Type <sup>1</sup>	Loc <sup>2</sup>		
0-3	10YR 4/1	100					Loamy/Clayey	
3-18	10YR 4/2	96	10YR 4/4	4	C	M	Loamy/Clayey	Distinct redox concentrations

<sup>1</sup>Type: C=Concentration, D=Depletion, RM=Reduced Matrix, MS=Masked Sand Grains.

<sup>2</sup>Location: PL=Pore Lining, M=Matrix.

Hydric Soil Indicators:

- Histosol (A1)
- Histic Epipedon (A2)
- Black Histic (A3)
- Hydrogen Sulfide (A4)
- Stratified Layers (A5)
- Depleted Below Dark Surface (A11)
- Thick Dark Surface (A12)
- Sandy Mucky Mineral (S1)
- Sandy Gleyed Matrix (S4)
- Sandy Redox (S5)
- Stripped Matrix (S6)
- Dark Surface (S7)
- Polyvalue Below Surface (S8) (LRR R, MLRA 149B)
- Thin Dark Surface (S9) (LRR R, MLRA 149B)
- High Chroma Sands (S11) (LRR K, L)
- Loamy Mucky Mineral (F1) (LRR K, L)
- Loamy Gleyed Matrix (F2)
- Depleted Matrix (F3)
- Redox Dark Surface (F6)
- Depleted Dark Surface (F7)
- Redox Depressions (F8)
- Marl (F10) (LRR K, L)

Indicators for Problematic Hydric Soils<sup>3</sup>:

- 2 cm Muck (A10) (LRR K, L, MLRA 149B)
- Coast Prairie Redox (A16) (LRR K, L, R)
- 5 cm Mucky Peat or Peat (S3) (LRR K, L, R)
- Polyvalue Below Surface (S8) (LRR K, L)
- Thin Dark Surface (S9) (LRR K, L)
- Iron-Manganese Masses (F12) (LRR K, L, R)
- Piedmont Floodplain Soils (F19) (MLRA 149B)
- Mesic Spodic (TA6) (MLRA 144A, 145, 149B)
- Red Parent Material (F21)
- Very Shallow Dark Surface (F22)
- Other (Explain in Remarks)

<sup>3</sup>Indicators of hydrophytic vegetation and wetland hydrology must be present, unless disturbed or problematic.

**Restrictive Layer (if observed):**  
 Type: \_\_\_\_\_  
 Depth (inches): \_\_\_\_\_

Hydric Soil Present? Yes  No

Remarks:

**WETLAND DETERMINATION DATA FORM – Northcentral and Northeast Region**

Project/Site: Celi Drive BCP Site (BCP Site #C734108) City/County: Onondaga County Sampling Date: 11/15/2017  
 Applicant/Owner: GSP Holdings, Inc. State: NY Sampling Point: SP-08  
 Investigator(s): Melissa Harrison, Gregory Kunka Section, Township, Range: Town of Dewitt  
 Landform (hillside, terrace, etc.): floodplain Local relief (concave, convex, none): none Slope %: 4-8  
 Subregion (LRR or MLRA): LRR L, MLRA 101 Lat: 43.0558011016 Long: -76.0698365989 Datum: NAD 1983  
 Soil Map Unit Name: Cut and fill land (CFL) NWI classification: none

Are climatic / hydrologic conditions on the site typical for this time of year? Yes X No      (If no, explain in Remarks.)  
 Are Vegetation X, Soil X, or Hydrology      significantly disturbed? Are "Normal Circumstances" present? Yes      No X  
 Are Vegetation     , Soil     , or Hydrology      naturally problematic? (If needed, explain any answers in Remarks.)

**SUMMARY OF FINDINGS – Attach site map showing sampling point locations, transects, important features, etc.**

Hydrophytic Vegetation Present? Yes <u>    </u> No <u>X</u> Hydric Soil Present? Yes <u>    </u> No <u>X</u> Wetland Hydrology Present? Yes <u>    </u> No <u>X</u>	<b>Is the Sampled Area within a Wetland?</b> Yes <u>    </u> No <u>X</u> If yes, optional Wetland Site ID: <u>    </u>
Remarks: (Explain alternative procedures here or in a separate report.) Area impacted from previous roadway construction and continued maintenance	

**HYDROLOGY**

<b>Wetland Hydrology Indicators:</b> <u>Primary Indicators (minimum of one is required; check all that apply)</u> ___ Surface Water (A1)                      ___ Water-Stained Leaves (B9) ___ High Water Table (A2)                 ___ Aquatic Fauna (B13) ___ Saturation (A3)                           ___ Marl Deposits (B15) ___ Water Marks (B1)                        ___ Hydrogen Sulfide Odor (C1) ___ Sediment Deposits (B2)                ___ Oxidized Rhizospheres on Living Roots (C3) ___ Drift Deposits (B3)                      ___ Presence of Reduced Iron (C4) ___ Algal Mat or Crust (B4)                 ___ Recent Iron Reduction in Tilled Soils (C6) ___ Iron Deposits (B5)                        ___ Thin Muck Surface (C7) ___ Inundation Visible on Aerial Imagery (B7) ___ Other (Explain in Remarks) ___ Sparsely Vegetated Concave Surface (B8)	<u>Secondary Indicators (minimum of two required)</u> ___ Surface Soil Cracks (B6) ___ Drainage Patterns (B10) ___ Moss Trim Lines (B16) ___ Dry-Season Water Table (C2) ___ Crayfish Burrows (C8) ___ Saturation Visible on Aerial Imagery (C9) ___ Stunted or Stressed Plants (D1) ___ Geomorphic Position (D2) ___ Shallow Aquitard (D3) ___ Microtopographic Relief (D4) ___ FAC-Neutral Test (D5)
<b>Field Observations:</b> Surface Water Present? Yes <u>    </u> No <u>X</u> Depth (inches): <u>    </u> Water Table Present? Yes <u>    </u> No <u>X</u> Depth (inches): <u>    </u> Saturation Present? Yes <u>    </u> No <u>X</u> Depth (inches): <u>    </u> (includes capillary fringe)	<b>Wetland Hydrology Present?</b> Yes <u>    </u> No <u>X</u>
Describe Recorded Data (stream gauge, monitoring well, aerial photos, previous inspections), if available:	
Remarks:	

**VEGETATION – Use scientific names of plants.**

Sampling Point: SP-08

<u>Tree Stratum</u> (Plot size: <u>30</u> )		Absolute % Cover	Dominant Species?	Indicator Status
1.	<u>Rhamnus cathartica</u>	<u>10</u>	<u>Yes</u>	<u>FAC</u>
2.	_____			
3.	_____			
4.	_____			
5.	_____			
6.	_____			
7.	_____			
		<u>10</u>	=Total Cover	
<u>Sapling/Shrub Stratum</u> (Plot size: <u>15</u> )				
1.	_____			
2.	_____			
3.	_____			
4.	_____			
5.	_____			
6.	_____			
7.	_____			
			=Total Cover	
<u>Herb Stratum</u> (Plot size: <u>5</u> )				
1.	<u>Poa pratensis</u>	<u>20</u>	<u>Yes</u>	<u>FACU</u>
2.	<u>Lolium perenne</u>	<u>20</u>	<u>Yes</u>	<u>FACU</u>
3.	<u>Cynodon dactylon</u>	<u>15</u>	<u>Yes</u>	<u>FACU</u>
4.	<u>Phragmites australis</u>	<u>15</u>	<u>Yes</u>	<u>FACW</u>
5.	<u>Plantago lanceolata</u>	<u>15</u>	<u>Yes</u>	<u>FACU</u>
6.	<u>Lythrum salicaria</u>	<u>5</u>	<u>No</u>	<u>OBL</u>
7.	_____			
8.	_____			
9.	_____			
10.	_____			
11.	_____			
12.	_____			
		<u>90</u>	=Total Cover	
<u>Woody Vine Stratum</u> (Plot size: <u>15</u> )				
1.	_____			
2.	_____			
3.	_____			
4.	_____			
			=Total Cover	

**Dominance Test worksheet:**

Number of Dominant Species That Are OBL, FACW, or FAC: 2 (A)

Total Number of Dominant Species Across All Strata: 6 (B)

Percent of Dominant Species That Are OBL, FACW, or FAC: 33.3% (A/B)

**Prevalence Index worksheet:**

Total % Cover of:	Multiply by:
OBL species <u>5</u>	x 1 = <u>5</u>
FACW species <u>15</u>	x 2 = <u>30</u>
FAC species <u>10</u>	x 3 = <u>30</u>
FACU species <u>70</u>	x 4 = <u>280</u>
UPL species <u>0</u>	x 5 = <u>0</u>
Column Totals: <u>100</u> (A)	<u>345</u> (B)
Prevalence Index = B/A = <u>3.45</u>	

**Hydrophytic Vegetation Indicators:**

   1 - Rapid Test for Hydrophytic Vegetation

   2 - Dominance Test is >50%

   3 - Prevalence Index is ≤3.0<sup>1</sup>

   4 - Morphological Adaptations<sup>1</sup> (Provide supporting data in Remarks or on a separate sheet)

   Problematic Hydrophytic Vegetation<sup>1</sup> (Explain)

<sup>1</sup>Indicators of hydric soil and wetland hydrology must be present, unless disturbed or problematic.

**Definitions of Vegetation Strata:**

**Tree** – Woody plants 3 in. (7.6 cm) or more in diameter at breast height (DBH), regardless of height.

**Sapling/shrub** – Woody plants less than 3 in. DBH and greater than or equal to 3.28 ft (1 m) tall.

**Herb** – All herbaceous (non-woody) plants, regardless of size, and woody plants less than 3.28 ft tall.

**Woody vines** – All woody vines greater than 3.28 ft in height.

**Hydrophytic Vegetation Present?** Yes    No X

Remarks: (Include photo numbers here or on a separate sheet.)



**SOIL**

Sampling Point: SP-08

**Profile Description: (Describe to the depth needed to document the indicator or confirm the absence of indicators.)**

Depth (inches)	Matrix		Redox Features				Texture	Remarks
	Color (moist)	%	Color (moist)	%	Type <sup>1</sup>	Loc <sup>2</sup>		
0-2	10YR 4/2	100					Loamy/Clayey	
2-8	10YR 4/2	60					Loamy/Clayey	variegated fill later
	10YR 4/4	40						

<sup>1</sup>Type: C=Concentration, D=Depletion, RM=Reduced Matrix, MS=Masked Sand Grains.      <sup>2</sup>Location: PL=Pore Lining, M=Matrix.

**Hydric Soil Indicators:**

- Histosol (A1)
- Histic Epipedon (A2)
- Black Histic (A3)
- Hydrogen Sulfide (A4)
- Stratified Layers (A5)
- Depleted Below Dark Surface (A11)
- Thick Dark Surface (A12)
- Sandy Mucky Mineral (S1)
- Sandy Gleyed Matrix (S4)
- Sandy Redox (S5)
- Stripped Matrix (S6)
- Dark Surface (S7)
- Polyvalue Below Surface (S8) (LRR R, MLRA 149B)
- Thin Dark Surface (S9) (LRR R, MLRA 149B)
- High Chroma Sands (S11) (LRR K, L)
- Loamy Mucky Mineral (F1) (LRR K, L)
- Loamy Gleyed Matrix (F2)
- Depleted Matrix (F3)
- Redox Dark Surface (F6)
- Depleted Dark Surface (F7)
- Redox Depressions (F8)
- Mari (F10) (LRR K, L)

**Indicators for Problematic Hydric Soils<sup>3</sup>:**

- 2 cm Muck (A10) (LRR K, L, MLRA 149B)
- Coast Prairie Redox (A16) (LRR K, L, R)
- 5 cm Mucky Peat or Peat (S3) (LRR K, L, R)
- Polyvalue Below Surface (S8) (LRR K, L)
- Thin Dark Surface (S9) (LRR K, L)
- Iron-Manganese Masses (F12) (LRR K, L, R)
- Piedmont Floodplain Soils (F19) (MLRA 149B)
- Mesic Spodic (TA6) (MLRA 144A, 145, 149B)
- Red Parent Material (F21)
- Very Shallow Dark Surface (F22)
- Other (Explain in Remarks)

<sup>3</sup>Indicators of hydrophytic vegetation and wetland hydrology must be present, unless disturbed or problematic.

**Restrictive Layer (if observed):**

Type: fill stones  
 Depth (inches): 8

Hydric Soil Present?      Yes       No

Remarks:



**VEGETATION – Use scientific names of plants.**

Sampling Point: SP-09

	Absolute % Cover	Dominant Species?	Indicator Status	
<b>Tree Stratum</b> (Plot size: <u>30</u> )				<b>Dominance Test worksheet:</b> Number of Dominant Species That Are OBL, FACW, or FAC: <u>2</u> (A) Total Number of Dominant Species Across All Strata: <u>2</u> (B) Percent of Dominant Species That Are OBL, FACW, or FAC: <u>100.0%</u> (A/B)
1. <u>Rhamnus cathartica</u>	10	Yes	FAC	
2. _____				
3. _____				
4. _____				
5. _____				
6. _____				
7. _____				
<u>10</u> =Total Cover				<b>Prevalence Index worksheet:</b> Total % Cover of: _____ Multiply by: _____ OBL species _____ x 1 = _____ FACW species _____ x 2 = _____ FAC species _____ x 3 = _____ FACU species _____ x 4 = _____ UPL species _____ x 5 = _____ Column Totals: _____ (A) _____ (B) Prevalence Index = B/A = _____
<b>Sapling/Shrub Stratum</b> (Plot size: <u>15</u> )				
1. _____				
2. _____				
3. _____				
4. _____				
5. _____				
6. _____				
7. _____				
_____ =Total Cover				
<b>Herb Stratum</b> (Plot size: <u>5</u> )				<b>Hydrophytic Vegetation Indicators:</b> _____ 1 - Rapid Test for Hydrophytic Vegetation <input checked="" type="checkbox"/> 2 - Dominance Test is >50% _____ 3 - Prevalence Index is $\leq 3.0^1$ _____ 4 - Morphological Adaptations <sup>1</sup> (Provide supporting data in Remarks or on a separate sheet) _____ Problematic Hydrophytic Vegetation <sup>1</sup> (Explain) <sup>1</sup> Indicators of hydric soil and wetland hydrology must be present, unless disturbed or problematic.
1. <u>Phragmites australis</u>	85	Yes	FACW	
2. <u>Solidago canadensis</u>	20	No	FACU	
3. _____				
4. _____				
5. _____				
6. _____				
7. _____				
8. _____				
9. _____				
10. _____				
12. _____				
<u>105</u> =Total Cover				
<b>Woody Vine Stratum</b> (Plot size: <u>15</u> )				<b>Definitions of Vegetation Strata:</b> <b>Tree</b> – Woody plants 3 in. (7.6 cm) or more in diameter at breast height (DBH), regardless of height. <b>Sapling/shrub</b> – Woody plants less than 3 in. DBH and greater than or equal to 3.28 ft (1 m) tall. <b>Herb</b> – All herbaceous (non-woody) plants, regardless of size, and woody plants less than 3.28 ft tall. <b>Woody vines</b> – All woody vines greater than 3.28 ft in height.
1. _____				
2. _____				
3. _____				
4. _____				
_____ =Total Cover				
<b>Hydrophytic Vegetation Present?</b> Yes <input checked="" type="checkbox"/> No _____				
Remarks: (Include photo numbers here or on a separate sheet.)				

**SOIL**

Sampling Point SP-09

**Profile Description: (Describe to the depth needed to document the indicator or confirm the absence of indicators.)**

Depth (inches)	Matrix		Redox Features				Texture	Remarks
	Color (moist)	%	Color (moist)	%	Type <sup>1</sup>	Loc <sup>2</sup>		
0-6	10YR 3/1	100					Loamy/Clayey	
6-18	10YR 4/1	97	10YR 4/4	3	C	M	Loamy/Clayey	

<sup>1</sup>Type: C=Concentration, D=Depletion, RM=Reduced Matrix, MS=Masked Sand Grains. <sup>2</sup>Location: PL=Pore Lining, M=Matrix.

<b>Hydric Soil Indicators:</b>		<b>Indicators for Problematic Hydric Soils<sup>3</sup>:</b>
<input type="checkbox"/> Histosol (A1)	<input type="checkbox"/> Polyvalue Below Surface (S8) (LRR R, MLRA 149B)	<input type="checkbox"/> 2 cm Muck (A10) (LRR K, L, MLRA 149B)
<input type="checkbox"/> Histic Epipedon (A2)	<input type="checkbox"/> Thin Dark Surface (S9) (LRR R, MLRA 149B)	<input type="checkbox"/> Coast Prairie Redox (A16) (LRR K, L, R)
<input type="checkbox"/> Black Histic (A3)	<input type="checkbox"/> High Chroma Sands (S11) (LRR K, L)	<input type="checkbox"/> 5 cm Mucky Peat or Peat (S3) (LRR K, L, R)
<input type="checkbox"/> Hydrogen Sulfide (A4)	<input type="checkbox"/> Loamy Mucky Mineral (F1) (LRR K, L)	<input type="checkbox"/> Polyvalue Below Surface (S8) (LRR K, L)
<input type="checkbox"/> Stratified Layers (A5)	<input type="checkbox"/> Loamy Gleyed Matrix (F2)	<input type="checkbox"/> Thin Dark Surface (S9) (LRR K, L)
<input checked="" type="checkbox"/> Depleted Below Dark Surface (A11)	<input checked="" type="checkbox"/> Depleted Matrix (F3)	<input type="checkbox"/> Iron-Manganese Masses (F12) (LRR K, L, R)
<input type="checkbox"/> Thick Dark Surface (A12)	<input type="checkbox"/> Redox Dark Surface (F6)	<input type="checkbox"/> Piedmont Floodplain Soils (F19) (MLRA 149B)
<input type="checkbox"/> Sandy Mucky Mineral (S1)	<input type="checkbox"/> Depleted Dark Surface (F7)	<input type="checkbox"/> Mesic Spodic (TA6) (MLRA 144A, 145, 149B)
<input type="checkbox"/> Sandy Gleyed Matrix (S4)	<input type="checkbox"/> Redox Depressions (F8)	<input type="checkbox"/> Red Parent Material (F21)
<input type="checkbox"/> Sandy Redox (S5)	<input type="checkbox"/> Marl (F10) (LRR K, L)	<input type="checkbox"/> Very Shallow Dark Surface (F22)
<input type="checkbox"/> Stripped Matrix (S6)		<input type="checkbox"/> Other (Explain in Remarks)
<input type="checkbox"/> Dark Surface (S7)		

<sup>3</sup>Indicators of hydrophytic vegetation and wetland hydrology must be present, unless disturbed or problematic.

<b>Restrictive Layer (if observed):</b> Type: _____ Depth (inches): _____	<b>Hydric Soil Present?</b> Yes <input checked="" type="checkbox"/> No _____
---	--

Remarks:

**WETLAND DETERMINATION DATA FORM – Northcentral and Northeast Region**

Project/Site: Celi Drive BCP Site (BCP Site #C734108) City/County: Onondaga County Sampling Date: 11/15/2017  
 Applicant/Owner: GSP Holdings, Inc. State: NY Sampling Point: SP-10  
 Investigator(s): Melissa Harrison, Gregory Kunka Section, Township, Range: Town of Dewitt  
 Landform (hillside, terrace, etc.):  floodplain  Local relief (concave, convex, none):  none  Slope %:  4-8   
 Subregion (LRR or MLRA):  LRR L, MLRA 101  Lat:  43.0573928221  Long:  -76.0761419665  Datum:  NAD 1983   
 Soil Map Unit Name:  Cut and fill land (CFL)  NWI classification:  none

Are climatic / hydrologic conditions on the site typical for this time of year? Yes  X  No   (If no, explain in Remarks.)  
 Are Vegetation  X , Soil  X , or Hydrology   significantly disturbed? Are "Normal Circumstances" present? Yes   No  X   
 Are Vegetation  , Soil  , or Hydrology   naturally problematic? (If needed, explain any answers in Remarks.)

**SUMMARY OF FINDINGS – Attach site map showing sampling point locations, transects, important features, etc.**

Hydrophytic Vegetation Present? Yes <u> </u> No <u> X </u> Hydric Soil Present? Yes <u> </u> No <u> X </u> Wetland Hydrology Present? Yes <u> </u> No <u> X </u>	<b>Is the Sampled Area within a Wetland?</b> Yes <u> </u> No <u> X </u> If yes, optional Wetland Site ID: _____
Remarks: (Explain alternative procedures here or in a separate report.) Area impacted from previous roadway construction and continued maintenance	

**HYDROLOGY**

<b>Wetland Hydrology Indicators:</b> Primary Indicators (minimum of one is required; check all that apply) _____ ___ Surface Water (A1)                      ___ Water-Stained Leaves (B9) ___ High Water Table (A2)                ___ Aquatic Fauna (B13) ___ Saturation (A3)                          ___ Marl Deposits (B15) ___ Water Marks (B1)                        ___ Hydrogen Sulfide Odor (C1) ___ Sediment Deposits (B2)                ___ Oxidized Rhizospheres on Living Roots (C3) ___ Drift Deposits (B3)                      ___ Presence of Reduced Iron (C4) ___ Algal Mat or Crust (B4)                 ___ Recent Iron Reduction in Tilled Soils (C6) ___ Iron Deposits (B5)                        ___ Thin Muck Surface (C7) ___ Inundation Visible on Aerial Imagery (B7) ___ Other (Explain in Remarks) ___ Sparsely Vegetated Concave Surface (B8)	<b>Secondary Indicators (minimum of two required)</b> ___ Surface Soil Cracks (B6) ___ Drainage Patterns (B10) ___ Moss Trim Lines (B16) ___ Dry-Season Water Table (C2) ___ Crayfish Burrows (C8) ___ Saturation Visible on Aerial Imagery (C9) ___ Stunted or Stressed Plants (D1) ___ Geomorphic Position (D2) ___ Shallow Aquitard (D3) ___ Microtopographic Relief (D4) ___ FAC-Neutral Test (D5)
---	---

<b>Field Observations:</b> Surface Water Present? Yes <u> </u> No <u> X </u> Depth (inches): _____ Water Table Present? Yes <u> </u> No <u> X </u> Depth (inches): _____ Saturation Present? Yes <u> </u> No <u> X </u> Depth (inches): _____ (includes capillary fringe)	<b>Wetland Hydrology Present?</b> Yes <u> </u> No <u> X </u>
---	--

Describe Recorded Data (stream gauge, monitoring well, aerial photos, previous inspections), if available:

Remarks:

**VEGETATION – Use scientific names of plants.**

Sampling Point: SP-10

<u>Tree Stratum</u> (Plot size: <u>30</u> )		Absolute % Cover	Dominant Species?	Indicator Status
1.	<u>Rhamnus cathartica</u>	<u>10</u>	<u>Yes</u>	<u>FAC</u>
2.	_____	_____	_____	_____
3.	_____	_____	_____	_____
4.	_____	_____	_____	_____
5.	_____	_____	_____	_____
6.	_____	_____	_____	_____
7.	_____	_____	_____	_____
		<u>10</u>	<u>=Total Cover</u>	
<u>Sapling/Shrub Stratum</u> (Plot size: <u>15</u> )				
1.	_____	_____	_____	_____
2.	_____	_____	_____	_____
3.	_____	_____	_____	_____
4.	_____	_____	_____	_____
5.	_____	_____	_____	_____
6.	_____	_____	_____	_____
7.	_____	_____	_____	_____
		_____	<u>=Total Cover</u>	
<u>Herb Stratum</u> (Plot size: <u>5</u> )				
1.	<u>Poa pratensis</u>	<u>25</u>	<u>Yes</u>	<u>FACU</u>
2.	<u>Lolium perenne</u>	<u>20</u>	<u>Yes</u>	<u>FACU</u>
3.	<u>Cynodon dactylon</u>	<u>15</u>	<u>No</u>	<u>FACU</u>
4.	<u>Phragmites australis</u>	<u>15</u>	<u>No</u>	<u>FACW</u>
5.	<u>Plantago lanceolata</u>	<u>5</u>	<u>No</u>	<u>FACU</u>
6.	<u>Lythrum salicaria</u>	<u>5</u>	<u>No</u>	<u>OBL</u>
7.	_____	_____	_____	_____
8.	_____	_____	_____	_____
9.	_____	_____	_____	_____
10.	_____	_____	_____	_____
11.	_____	_____	_____	_____
12.	_____	_____	_____	_____
		<u>85</u>	<u>=Total Cover</u>	
<u>Woody Vine Stratum</u> (Plot size: <u>15</u> )				
1.	_____	_____	_____	_____
2.	_____	_____	_____	_____
3.	_____	_____	_____	_____
4.	_____	_____	_____	_____
		_____	<u>=Total Cover</u>	

**Dominance Test worksheet:**

Number of Dominant Species That Are OBL, FACW, or FAC: 1 (A)

Total Number of Dominant Species Across All Strata: 3 (B)

Percent of Dominant Species That Are OBL, FACW, or FAC: 33.3% (A/B)

**Prevalence Index worksheet:**

Total % Cover of:	Multiply by:
OBL species <u>5</u>	x 1 = <u>5</u>
FACW species <u>15</u>	x 2 = <u>30</u>
FAC species <u>10</u>	x 3 = <u>30</u>
FACU species <u>65</u>	x 4 = <u>260</u>
UPL species <u>0</u>	x 5 = <u>0</u>
Column Totals: <u>95</u> (A)	<u>325</u> (B)
Prevalence Index = B/A = <u>3.42</u>	

**Hydrophytic Vegetation Indicators:**

   1 - Rapid Test for Hydrophytic Vegetation

   2 - Dominance Test is >50%

   3 - Prevalence Index is  $\leq 3.0$ <sup>1</sup>

   4 - Morphological Adaptations<sup>1</sup> (Provide supporting data in Remarks or on a separate sheet)

   Problematic Hydrophytic Vegetation<sup>1</sup> (Explain)

<sup>1</sup>Indicators of hydric soil and wetland hydrology must be present, unless disturbed or problematic.

**Definitions of Vegetation Strata:**

**Tree** – Woody plants 3 in. (7.6 cm) or more in diameter at breast height (DBH), regardless of height.

**Sapling/shrub** – Woody plants less than 3 in. DBH and greater than or equal to 3.28 ft (1 m) tall.

**Herb** – All herbaceous (non-woody) plants, regardless of size, and woody plants less than 3.28 ft tall.

**Woody vines** – All woody vines greater than 3.28 ft in height.

**Hydrophytic Vegetation Present?** Yes    No X

Remarks: (Include photo numbers here or on a separate sheet.)

SOIL

Sampling Point: SP-10

Profile Description: (Describe to the depth needed to document the indicator or confirm the absence of indicators.)

Depth (inches)	Matrix		Redox Features				Texture	Remarks
	Color (moist)	%	Color (moist)	%	Type <sup>1</sup>	Loc <sup>2</sup>		
0-2	10YR 4/2	100					Loamy/Clayey	
2-8	10YR 4/2	60					Loamy/Clayey	variegated fill later
	10YR 4/4	40					Loamy/Clayey	

<sup>1</sup>Type: C=Concentration, D=Depletion, RM=Reduced Matrix, MS=Masked Sand Grains. <sup>2</sup>Location: PL=Pore Lining, M=Matrix.

**Hydric Soil Indicators:**

- Histosol (A1)
- Histic Epipedon (A2)
- Black Histic (A3)
- Hydrogen Sulfide (A4)
- Stratified Layers (A5)
- Depleted Below Dark Surface (A11)
- Thick Dark Surface (A12)
- Sandy Mucky Mineral (S1)
- Sandy Gleyed Matrix (S4)
- Sandy Redox (S5)
- Stripped Matrix (S6)
- Dark Surface (S7)
- Polyvalue Below Surface (S8) (LRR R, MLRA 149B)
- Thin Dark Surface (S9) (LRR R, MLRA 149B)
- High Chroma Sands (S11) (LRR K, L)
- Loamy Mucky Mineral (F1) (LRR K, L)
- Loamy Gleyed Matrix (F2)
- Depleted Matrix (F3)
- Redox Dark Surface (F6)
- Depleted Dark Surface (F7)
- Redox Depressions (F8)
- Marl (F10) (LRR K, L)

**Indicators for Problematic Hydric Soils<sup>3</sup>:**

- 2 cm Muck (A10) (LRR K, L, MLRA 149B)
- Coast Prairie Redox (A16) (LRR K, L, R)
- 5 cm Mucky Peat or Peat (S3) (LRR K, L, R)
- Polyvalue Below Surface (S8) (LRR K, L)
- Thin Dark Surface (S9) (LRR K, L)
- Iron-Manganese Masses (F12) (LRR K, L, R)
- Piedmont Floodplain Soils (F19) (MLRA 149B)
- Mesic Spodic (TA6) (MLRA 144A, 145, 149B)
- Red Parent Material (F21)
- Very Shallow Dark Surface (F22)
- Other (Explain in Remarks)

<sup>3</sup>Indicators of hydrophytic vegetation and wetland hydrology must be present, unless disturbed or problematic.

<b>Restrictive Layer (if observed):</b> Type: <u>fill stones</u> Depth (inches): <u>8</u>	<b>Hydric Soil Present?</b> Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>
---	---

Remarks:

**WETLAND DETERMINATION DATA FORM – Northcentral and Northeast Region**

Project/Site: Celi Drive BCP Site (BCP Site #C734108) City/County: Onondaga County Sampling Date: 11/15/2017  
 Applicant/Owner: GSP Holdings, Inc. State: NY Sampling Point: SP-12  
 Investigator(s): Melissa Harrison, Gregory Kunka Section, Township, Range: Town of Dewitt  
 Landform (hillside, terrace, etc.):  floodplain  Local relief (concave, convex, none): concave Slope %: 2-3  
 Subregion (LRR or MLRA): LRR L, MLRA 101 Lat: 43.0561550188 Long: -76.0731242402 Datum: NAD 1983  
 Soil Map Unit Name: Canandaigua mucky silt loam (Cd) NWI classification: none  
 Are climatic / hydrologic conditions on the site typical for this time of year? Yes X No   (If no, explain in Remarks.)  
 Are Vegetation  , Soil  , or Hydrology   significantly disturbed? Are "Normal Circumstances" present? Yes X No    
 Are Vegetation  , Soil  , or Hydrology   naturally problematic? (If needed, explain any answers in Remarks.)

**SUMMARY OF FINDINGS – Attach site map showing sampling point locations, transects, important features, etc.**

Hydrophytic Vegetation Present? Yes <u>X</u> No <u> </u> Hydric Soil Present? Yes <u>X</u> No <u> </u> Wetland Hydrology Present? Yes <u>X</u> No <u> </u>	Is the Sampled Area within a Wetland? Yes <u>X</u> No <u> </u> If yes, optional Wetland Site ID: <u> </u>
Remarks: (Explain alternative procedures here or in a separate report.)  PEM	

**HYDROLOGY**

<b>Wetland Hydrology Indicators:</b> <u>Primary Indicators (minimum of one is required; check all that apply)</u> ___ Surface Water (A1)      ___ Water-Stained Leaves (B9) ___ High Water Table (A2)      ___ Aquatic Fauna (B13) <u>X</u> Saturation (A3)      ___ Marl Deposits (B15) ___ Water Marks (B1)      ___ Hydrogen Sulfide Odor (C1) ___ Sediment Deposits (B2)      ___ Oxidized Rhizospheres on Living Roots (C3) ___ Drift Deposits (B3)      ___ Presence of Reduced Iron (C4) ___ Algal Mat or Crust (B4)      ___ Recent Iron Reduction in Tilled Soils (C6) ___ Iron Deposits (B5)      ___ Thin Muck Surface (C7) ___ Inundation Visible on Aerial Imagery (B7)      ___ Other (Explain in Remarks) ___ Sparsely Vegetated Concave Surface (B8)	<u>Secondary Indicators (minimum of two required)</u> ___ Surface Soil Cracks (B6) ___ Drainage Patterns (B10) ___ Moss Trim Lines (B16) ___ Dry-Season Water Table (C2) ___ Crayfish Burrows (C8) ___ Saturation Visible on Aerial Imagery (C9) ___ Stunted or Stressed Plants (D1) <u>X</u> Geomorphic Position (D2) ___ Shallow Aquitard (D3) ___ Microtopographic Relief (D4) <u>X</u> FAC-Neutral Test (D5)
---	---

<b>Field Observations:</b> Surface Water Present? Yes <u> </u> No <u>X</u> Depth (inches): <u> </u> Water Table Present? Yes <u> </u> No <u>X</u> Depth (inches): <u> </u> Saturation Present? Yes <u>X</u> No <u> </u> Depth (inches): <u>0</u> (includes capillary fringe)	Wetland Hydrology Present? Yes <u>X</u> No <u> </u>
--	---

Describe Recorded Data (stream gauge, monitoring well, aerial photos, previous inspections), if available:

Remarks:



**VEGETATION – Use scientific names of plants.**

Sampling Point: SP-12

<u>Tree Stratum</u> (Plot size: <u>30</u> )	Absolute % Cover	Dominant Species?	Indicator Status																	
1. _____	_____	_____	_____	<b>Dominance Test worksheet:</b>  Number of Dominant Species That Are OBL, FACW, or FAC: _____ (A)  Total Number of Dominant Species Across All Strata: _____ (B)  Percent of Dominant Species That Are OBL, FACW, or FAC: _____ (A/B)																
2. _____	_____	_____	_____																	
3. _____	_____	_____	_____																	
4. _____	_____	_____	_____																	
5. _____	_____	_____	_____																	
6. _____	_____	_____	_____																	
7. _____	_____	_____	_____																	
_____ =Total Cover				<b>Prevalence Index worksheet:</b>  <table style="width:100%; border:none;"> <tr> <td style="width:50%; text-align: center;">Total % Cover of:</td> <td style="width:50%; text-align: center;">Multiply by:</td> </tr> <tr> <td>OBL species _____</td> <td>x 1 = _____</td> </tr> <tr> <td>FACW species _____</td> <td>x 2 = _____</td> </tr> <tr> <td>FAC species _____</td> <td>x 3 = _____</td> </tr> <tr> <td>FACU species _____</td> <td>x 4 = _____</td> </tr> <tr> <td>UPL species _____</td> <td>x 5 = _____</td> </tr> <tr> <td>Column Totals: _____</td> <td>(A) _____ (B) _____</td> </tr> <tr> <td colspan="2" style="text-align: center;">Prevalence Index = B/A = _____</td> </tr> </table>	Total % Cover of:	Multiply by:	OBL species _____	x 1 = _____	FACW species _____	x 2 = _____	FAC species _____	x 3 = _____	FACU species _____	x 4 = _____	UPL species _____	x 5 = _____	Column Totals: _____	(A) _____ (B) _____	Prevalence Index = B/A = _____	
Total % Cover of:	Multiply by:																			
OBL species _____	x 1 = _____																			
FACW species _____	x 2 = _____																			
FAC species _____	x 3 = _____																			
FACU species _____	x 4 = _____																			
UPL species _____	x 5 = _____																			
Column Totals: _____	(A) _____ (B) _____																			
Prevalence Index = B/A = _____																				
_____ =Total Cover																				
_____ =Total Cover																				
_____ =Total Cover																				
_____ =Total Cover																				
_____ =Total Cover																				
_____ =Total Cover																				
_____ =Total Cover				<b>Hydrophytic Vegetation Indicators:</b> <input checked="" type="checkbox"/> 1 - Rapid Test for Hydrophytic Vegetation <input type="checkbox"/> 2 - Dominance Test is >50% <input type="checkbox"/> 3 - Prevalence Index is $\leq 3.0$ <sup>1</sup> <input type="checkbox"/> 4 - Morphological Adaptations <sup>1</sup> (Provide supporting data in Remarks or on a separate sheet)  <input type="checkbox"/> Problematic Hydrophytic Vegetation <sup>1</sup> (Explain)  <sup>1</sup> Indicators of hydric soil and wetland hydrology must be present, unless disturbed or problematic.																
_____ =Total Cover																				
_____ =Total Cover																				
_____ =Total Cover																				
_____ =Total Cover																				
_____ =Total Cover																				
_____ =Total Cover																				
_____ =Total Cover																				
_____ =Total Cover																				
_____ =Total Cover																				
_____ =Total Cover																				
_____ =Total Cover																				
_____ =Total Cover				<b>Definitions of Vegetation Strata:</b>  <b>Tree</b> – Woody plants 3 in. (7.6 cm) or more in diameter at breast height (DBH), regardless of height.  <b>Sapling/shrub</b> – Woody plants less than 3 in. DBH and greater than or equal to 3.28 ft (1 m) tall.  <b>Herb</b> – All herbaceous (non-woody) plants, regardless of size, and woody plants less than 3.28 ft tall.  <b>Woody vines</b> – All woody vines greater than 3.28 ft in height.																
_____ =Total Cover																				
_____ =Total Cover																				
_____ =Total Cover																				
_____ =Total Cover				<b>Hydrophytic Vegetation Present?</b> Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>																
Remarks: (Include photo numbers here or on a separate sheet.)																				

**SOIL**

Sampling Point: SP-12

**Profile Description: (Describe to the depth needed to document the indicator or confirm the absence of indicators.)**

Depth (inches)	Matrix		Redox Features				Texture	Remarks
	Color (moist)	%	Color (moist)	%	Type <sup>1</sup>	Loc <sup>2</sup>		
0-6	10YR 3/1	100					Loamy/Clayey	
6-14	10YR 4/1	98	10YR 4/4	2	C	M	Loamy/Clayey	

<sup>1</sup>Type: C=Concentration, D=Depletion, RM=Reduced Matrix, MS=Masked Sand Grains.      <sup>2</sup>Location: PL=Pore Lining, M=Matrix.

- |   |  |  |
|---|--|--|
| <b>Hydric Soil Indicators:</b>  |  | <b>Indicators for Problematic Hydric Soils<sup>3</sup>:</b>          |
| <input type="checkbox"/> Histosol (A1)                                | <input type="checkbox"/> Polyvalue Below Surface (S8) (LRR R, MLRA 149B) | <input type="checkbox"/> 2 cm Muck (A10) (LRR K, L, MLRA 149B)       |
| <input type="checkbox"/> Histic Epipedon (A2)                         | <input type="checkbox"/> Thin Dark Surface (S9) (LRR R, MLRA 149B)       | <input type="checkbox"/> Coast Prairie Redox (A16) (LRR K, L, R)     |
| <input type="checkbox"/> Black Histic (A3)                            | <input type="checkbox"/> High Chroma Sands (S11) (LRR K, L)              | <input type="checkbox"/> 5 cm Mucky Peat or Peat (S3) (LRR K, L, R)  |
| <input type="checkbox"/> Hydrogen Sulfide (A4)                        | <input type="checkbox"/> Loamy Mucky Mineral (F1) (LRR K, L)             | <input type="checkbox"/> Polyvalue Below Surface (S8) (LRR K, L)     |
| <input type="checkbox"/> Stratified Layers (A5)                       | <input type="checkbox"/> Loamy Gleyed Matrix (F2)                        | <input type="checkbox"/> Thin Dark Surface (S9) (LRR K, L)           |
| <input checked="" type="checkbox"/> Depleted Below Dark Surface (A11) | <input checked="" type="checkbox"/> Depleted Matrix (F3)                 | <input type="checkbox"/> Iron-Manganese Masses (F12) (LRR K, L, R)   |
| <input type="checkbox"/> Thick Dark Surface (A12)                     | <input type="checkbox"/> Redox Dark Surface (F6)                         | <input type="checkbox"/> Piedmont Floodplain Soils (F19) (MLRA 149B) |
| <input type="checkbox"/> Sandy Mucky Mineral (S1)                     | <input type="checkbox"/> Depleted Dark Surface (F7)                      | <input type="checkbox"/> Mesic Spodic (TA6) (MLRA 144A, 145, 149B)   |
| <input type="checkbox"/> Sandy Gleyed Matrix (S4)                     | <input type="checkbox"/> Redox Depressions (F8)                          | <input type="checkbox"/> Red Parent Material (F21)                   |
| <input type="checkbox"/> Sandy Redox (S5)                             | <input type="checkbox"/> Mart (F10) (LRR K, L)                           | <input type="checkbox"/> Very Shallow Dark Surface (F22)             |
| <input type="checkbox"/> Stripped Matrix (S6)                         |  | <input type="checkbox"/> Other (Explain in Remarks)                  |
| <input type="checkbox"/> Dark Surface (S7)                            |  |  |

<sup>3</sup>Indicators of hydrophytic vegetation and wetland hydrology must be present, unless disturbed or problematic.

<b>Restrictive Layer (if observed):</b> Type: <u>stones</u> Depth (inches): <u>14</u>	<b>Hydric Soil Present?</b> Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
---	---

Remarks:

**WETLAND DETERMINATION DATA FORM – Northcentral and Northeast Region**

Project/Site: Celi Drive BCP Site (BCP Site #C734108) City/County: Onondaga County Sampling Date: 11/15/2017  
 Applicant/Owner: GSP Holdings, Inc. State: NY Sampling Point: SP-13  
 Investigator(s): Melissa Harrison, Gregory Kunka Section, Township, Range: Town of Dewitt  
 Landform (hillside, terrace, etc.): foodplain Local relief (concave, convex, none): none Slope %: 4-8  
 Subregion (LRR or MLRA): LRR L, MLRA 101 Lat: 43.0561950496 Long: -76.0731571902 Datum: NAD 1983  
 Soil Map Unit Name: Canandaigua mucky silt loam (Cd) NWI classification: none

Are climatic / hydrologic conditions on the site typical for this time of year? Yes X No      (If no, explain in Remarks.)  
 Are Vegetation X, Soil X, or Hydrology      significantly disturbed? Are "Normal Circumstances" present? Yes      No X  
 Are Vegetation     , Soil     , or Hydrology      naturally problematic? (If needed, explain any answers in Remarks.)

**SUMMARY OF FINDINGS – Attach site map showing sampling point locations, transects, important features, etc.**

Hydrophytic Vegetation Present? Yes <u>    </u> No <u>X</u> Hydric Soil Present? Yes <u>    </u> No <u>X</u> Wetland Hydrology Present? Yes <u>    </u> No <u>X</u>	Is the Sampled Area within a Wetland? Yes <u>    </u> No <u>X</u> If yes, optional Wetland Site ID: <u>    </u>
Remarks: (Explain alternative procedures here or in a separate report.) Area impacted from previous construction of access road and continued maintenance including mowing.	

**HYDROLOGY**

<b>Wetland Hydrology Indicators:</b> Primary Indicators (minimum of one is required; check all that apply)	Secondary Indicators (minimum of two required)
<input type="checkbox"/> Surface Water (A1) <input type="checkbox"/> Water-Stained Leaves (B9) <input type="checkbox"/> High Water Table (A2) <input type="checkbox"/> Aquatic Fauna (B13) <input type="checkbox"/> Saturation (A3) <input type="checkbox"/> Marl Deposits (B15) <input type="checkbox"/> Water Marks (B1) <input type="checkbox"/> Hydrogen Sulfide Odor (C1) <input type="checkbox"/> Sediment Deposits (B2) <input type="checkbox"/> Oxidized Rhizospheres on Living Roots (C3) <input type="checkbox"/> Drift Deposits (B3) <input type="checkbox"/> Presence of Reduced Iron (C4) <input type="checkbox"/> Algal Mat or Crust (B4) <input type="checkbox"/> Recent Iron Reduction in Tilled Soils (C6) <input type="checkbox"/> Iron Deposits (B5) <input type="checkbox"/> Thin Muck Surface (C7) <input type="checkbox"/> Inundation Visible on Aerial Imagery (B7) <input type="checkbox"/> Other (Explain in Remarks) <input type="checkbox"/> Sparsely Vegetated Concave Surface (B8)	<input type="checkbox"/> Surface Soil Cracks (B6) <input type="checkbox"/> Drainage Patterns (B10) <input type="checkbox"/> Moss Trim Lines (B16) <input type="checkbox"/> Dry-Season Water Table (C2) <input type="checkbox"/> Crayfish Burrows (C8) <input type="checkbox"/> Saturation Visible on Aerial Imagery (C9) <input type="checkbox"/> Stunted or Stressed Plants (D1) <input type="checkbox"/> Geomorphic Position (D2) <input type="checkbox"/> Shallow Aquitard (D3) <input type="checkbox"/> Microtopographic Relief (D4) <input type="checkbox"/> FAC-Neutral Test (D5)

<b>Field Observations:</b> Surface Water Present? Yes <u>    </u> No <u>X</u> Depth (inches): <u>    </u> Water Table Present? Yes <u>    </u> No <u>X</u> Depth (inches): <u>    </u> Saturation Present? Yes <u>    </u> No <u>X</u> Depth (inches): <u>    </u> (includes capillary fringe)	Wetland Hydrology Present? Yes <u>    </u> No <u>X</u>
--	--

Describe Recorded Data (stream gauge, monitoring well, aerial photos, previous inspections), if available:

Remarks:

**VEGETATION – Use scientific names of plants.**

Sampling Point: SP-13

Tree Stratum (Plot size: <u>30</u> )	Absolute % Cover	Dominant Species?	Indicator Status
1. _____	_____	_____	_____
2. _____	_____	_____	_____
3. _____	_____	_____	_____
4. _____	_____	_____	_____
5. _____	_____	_____	_____
6. _____	_____	_____	_____
7. _____	_____	_____	_____

Sapling/Shrub Stratum (Plot size: <u>15</u> )	Absolute % Cover	Dominant Species?	Indicator Status
1. _____	_____	_____	_____
2. _____	_____	_____	_____
3. _____	_____	_____	_____
4. _____	_____	_____	_____
5. _____	_____	_____	_____
6. _____	_____	_____	_____
7. _____	_____	_____	_____

Herb Stratum (Plot size: <u>5</u> )	Absolute % Cover	Dominant Species?	Indicator Status
1. <u>Poa pratensis</u>	<u>15</u>	<u>Yes</u>	<u>FACU</u>
2. <u>Lolium perenne</u>	<u>15</u>	<u>Yes</u>	<u>FACU</u>
3. <u>Securigera varia</u>	<u>15</u>	<u>Yes</u>	<u>UPL</u>
4. <u>Cynodon dactylon</u>	<u>10</u>	<u>No</u>	<u>FACU</u>
5. <u>Plantago major</u>	<u>10</u>	<u>No</u>	<u>FACU</u>
6. _____	_____	_____	_____
7. _____	_____	_____	_____
8. _____	_____	_____	_____
9. _____	_____	_____	_____
10. _____	_____	_____	_____
11. _____	_____	_____	_____
12. _____	_____	_____	_____

Woody Vine Stratum (Plot size: <u>15</u> )	Absolute % Cover	Dominant Species?	Indicator Status
1. _____	_____	_____	_____
2. _____	_____	_____	_____
3. _____	_____	_____	_____
4. _____	_____	_____	_____

**Dominance Test worksheet:**

Number of Dominant Species That Are OBL, FACW, or FAC: 0 (A)

Total Number of Dominant Species Across All Strata: 3 (B)

Percent of Dominant Species That Are OBL, FACW, or FAC: 0.0% (A/B)

**Prevalence Index worksheet:**

Total % Cover of:	Multiply by:
OBL species <u>0</u>	x 1 = <u>0</u>
FACW species <u>0</u>	x 2 = <u>0</u>
FAC species <u>0</u>	x 3 = <u>0</u>
FACU species <u>50</u>	x 4 = <u>200</u>
UPL species <u>15</u>	x 5 = <u>75</u>
Column Totals: <u>65</u> (A)	<u>275</u> (B)

Prevalence Index = B/A = 4.23

- Hydrophytic Vegetation Indicators:**
- 1 - Rapid Test for Hydrophytic Vegetation
  - 2 - Dominance Test is >50%
  - 3 - Prevalence Index is ≤3.0<sup>1</sup>
  - 4 - Morphological Adaptations<sup>1</sup> (Provide supporting data in Remarks or on a separate sheet)
- Problematic Hydrophytic Vegetation<sup>1</sup> (Explain)
- <sup>1</sup>Indicators of hydric soil and wetland hydrology must be present, unless disturbed or problematic.

**Definitions of Vegetation Strata:**

**Tree** – Woody plants 3 in. (7.6 cm) or more in diameter at breast height (DBH), regardless of height.

**Sapling/shrub** – Woody plants less than 3 in. DBH and greater than or equal to 3.28 ft (1 m) tall.

**Herb** – All herbaceous (non-woody) plants, regardless of size, and woody plants less than 3.28 ft tall.

**Woody vines** – All woody vines greater than 3.28 ft in height.

**Hydrophytic Vegetation Present?** Yes    No X

Remarks: (Include photo numbers here or on a separate sheet.)

**SOIL**

Sampling Point: SP-13

**Profile Description: (Describe to the depth needed to document the indicator or confirm the absence of indicators.)**

Depth (inches)	Matrix		Redox Features				Texture	Remarks
	Color (moist)	%	Color (moist)	%	Type <sup>1</sup>	Loc <sup>2</sup>		
0-3	10YR 4/2	100					Loamy/Clayey	extremely stony

<sup>1</sup>Type: C=Concentration, D=Depletion, RM=Reduced Matrix, MS=Masked Sand Grains.      <sup>2</sup>Location: PL=Pore Lining, M=Matrix.

**Hydric Soil Indicators:**

- Histosol (A1)
- Histic Epipedon (A2)
- Black Histic (A3)
- Hydrogen Sulfide (A4)
- Stratified Layers (A5)
- Depleted Below Dark Surface (A11)
- Thick Dark Surface (A12)
- Sandy Mucky Mineral (S1)
- Sandy Gleyed Matrix (S4)
- Sandy Redox (S5)
- Stripped Matrix (S6)
- Dark Surface (S7)
- Polyvalue Below Surface (S8) (LRR R, MLRA 149B)
- Thin Dark Surface (S9) (LRR R, MLRA 149B)
- High Chroma Sands (S11) (LRR K, L)
- Loamy Mucky Mineral (F1) (LRR K, L)
- Loamy Gleyed Matrix (F2)
- Depleted Matrix (F3)
- Redox Dark Surface (F6)
- Depleted Dark Surface (F7)
- Redox Depressions (F8)
- Marl (F10) (LRR K, L)

**Indicators for Problematic Hydric Soils<sup>3</sup>:**

- 2 cm Muck (A10) (LRR K, L, MLRA 149B)
- Coast Prairie Redox (A16) (LRR K, L, R)
- 5 cm Mucky Peat or Peat (S3) (LRR K, L, R)
- Polyvalue Below Surface (S8) (LRR K, L)
- Thin Dark Surface (S9) (LRR K, L)
- Iron-Manganese Masses (F12) (LRR K, L, R)
- Piedmont Floodplain Soils (F19) (MLRA 149B)
- Mesic Spodic (TA6) (MLRA 144A, 145, 149B)
- Red Parent Material (F21)
- Very Shallow Dark Surface (F22)
- Other (Explain in Remarks)

<sup>3</sup>Indicators of hydrophytic vegetation and wetland hydrology must be present, unless disturbed or problematic.

**Restrictive Layer (if observed):**

Type: fill/stones  
 Depth (inches): 3

Hydric Soil Present?      Yes       No

Remarks:  
 Area was likely built up with fill in order to grade access road.

**WETLAND DETERMINATION DATA FORM – Northcentral and Northeast Region**

Project/Site: Celi Drive BCP Site (BCP Site #C734108) City/County: Onondaga County Sampling Date: 11/15/2017  
 Applicant/Owner: GSP Holdings, Inc. State: NY Sampling Point: SP-14  
 Investigator(s): Melissa Harrison, Gregory Kunka Section, Township, Range: Town of Dewitt  
 Landform (hillside, terrace, etc.):  floodplain  Local relief (concave, convex, none): concave Slope %: 2-4  
 Subregion (LRR or MLRA): LRR L, MLRA 101 Lat: 43.0569172062 Long: -76.074909428 Datum: NAD 1983  
 Soil Map Unit Name: Cut and fill land (CFL) NWI classification: none  
 Are climatic / hydrologic conditions on the site typical for this time of year? Yes X No   (If no, explain in Remarks.)  
 Are Vegetation  , Soil  , or Hydrology   significantly disturbed? Are "Normal Circumstances" present? Yes X No    
 Are Vegetation  , Soil  , or Hydrology   naturally problematic? (If needed, explain any answers in Remarks.)

**SUMMARY OF FINDINGS – Attach site map showing sampling point locations, transects, important features, etc.**

Hydrophytic Vegetation Present? Yes <u>X</u> No <u> </u> Hydric Soil Present? Yes <u>X</u> No <u> </u> Wetland Hydrology Present? Yes <u>X</u> No <u> </u>	Is the Sampled Area within a Wetland? Yes <u>X</u> No <u> </u> If yes, optional Wetland Site ID: <u> </u>
Remarks: (Explain alternative procedures here or in a separate report.)  <p style="margin-left: 20px;">PSS</p>	

**HYDROLOGY**

<b>Wetland Hydrology Indicators:</b> Primary Indicators (minimum of one is required; check all that apply) <table style="width:100%; border: none;"> <tr> <td style="width:33%;"><u> </u> Surface Water (A1)</td> <td style="width:33%;"><u> </u> Water-Stained Leaves (B9)</td> </tr> <tr> <td><u>X</u> High Water Table (A2)</td> <td><u> </u> Aquatic Fauna (B13)</td> </tr> <tr> <td><u>X</u> Saturation (A3)</td> <td><u> </u> Marl Deposits (B15)</td> </tr> <tr> <td><u> </u> Water Marks (B1)</td> <td><u> </u> Hydrogen Sulfide Odor (C1)</td> </tr> <tr> <td><u> </u> Sediment Deposits (B2)</td> <td><u> </u> Oxidized Rhizospheres on Living Roots (C3)</td> </tr> <tr> <td><u> </u> Drift Deposits (B3)</td> <td><u> </u> Presence of Reduced Iron (C4)</td> </tr> <tr> <td><u> </u> Algal Mat or Crust (B4)</td> <td><u> </u> Recent Iron Reduction in Tilled Soils (C6)</td> </tr> <tr> <td><u> </u> Iron Deposits (B5)</td> <td><u> </u> Thin Muck Surface (C7)</td> </tr> <tr> <td><u> </u> Inundation Visible on Aerial Imagery (B7)</td> <td><u> </u> Other (Explain in Remarks)</td> </tr> <tr> <td><u> </u> Sparsely Vegetated Concave Surface (B8)</td> <td></td> </tr> </table>	<u> </u> Surface Water (A1)	<u> </u> Water-Stained Leaves (B9)	<u>X</u> High Water Table (A2)	<u> </u> Aquatic Fauna (B13)	<u>X</u> Saturation (A3)	<u> </u> Marl Deposits (B15)	<u> </u> Water Marks (B1)	<u> </u> Hydrogen Sulfide Odor (C1)	<u> </u> Sediment Deposits (B2)	<u> </u> Oxidized Rhizospheres on Living Roots (C3)	<u> </u> Drift Deposits (B3)	<u> </u> Presence of Reduced Iron (C4)	<u> </u> Algal Mat or Crust (B4)	<u> </u> Recent Iron Reduction in Tilled Soils (C6)	<u> </u> Iron Deposits (B5)	<u> </u> Thin Muck Surface (C7)	<u> </u> Inundation Visible on Aerial Imagery (B7)	<u> </u> Other (Explain in Remarks)	<u> </u> Sparsely Vegetated Concave Surface (B8)		<b>Secondary Indicators (minimum of two required)</b> <table style="width:100%; border: none;"> <tr><td><u> </u> Surface Soil Cracks (B6)</td></tr> <tr><td><u> </u> Drainage Patterns (B10)</td></tr> <tr><td><u> </u> Moss Trim Lines (B16)</td></tr> <tr><td><u> </u> Dry-Season Water Table (C2)</td></tr> <tr><td><u> </u> Crayfish Burrows (C8)</td></tr> <tr><td><u> </u> Saturation Visible on Aerial Imagery (C9)</td></tr> <tr><td><u> </u> Stunted or Stressed Plants (D1)</td></tr> <tr><td><u>X</u> Geomorphic Position (D2)</td></tr> <tr><td><u> </u> Shallow Aquitard (D3)</td></tr> <tr><td><u> </u> Microtopographic Relief (D4)</td></tr> <tr><td><u>X</u> FAC-Neutral Test (D5)</td></tr> </table>	<u> </u> Surface Soil Cracks (B6)	<u> </u> Drainage Patterns (B10)	<u> </u> Moss Trim Lines (B16)	<u> </u> Dry-Season Water Table (C2)	<u> </u> Crayfish Burrows (C8)	<u> </u> Saturation Visible on Aerial Imagery (C9)	<u> </u> Stunted or Stressed Plants (D1)	<u>X</u> Geomorphic Position (D2)	<u> </u> Shallow Aquitard (D3)	<u> </u> Microtopographic Relief (D4)	<u>X</u> FAC-Neutral Test (D5)
<u> </u> Surface Water (A1)	<u> </u> Water-Stained Leaves (B9)																															
<u>X</u> High Water Table (A2)	<u> </u> Aquatic Fauna (B13)																															
<u>X</u> Saturation (A3)	<u> </u> Marl Deposits (B15)																															
<u> </u> Water Marks (B1)	<u> </u> Hydrogen Sulfide Odor (C1)																															
<u> </u> Sediment Deposits (B2)	<u> </u> Oxidized Rhizospheres on Living Roots (C3)																															
<u> </u> Drift Deposits (B3)	<u> </u> Presence of Reduced Iron (C4)																															
<u> </u> Algal Mat or Crust (B4)	<u> </u> Recent Iron Reduction in Tilled Soils (C6)																															
<u> </u> Iron Deposits (B5)	<u> </u> Thin Muck Surface (C7)																															
<u> </u> Inundation Visible on Aerial Imagery (B7)	<u> </u> Other (Explain in Remarks)																															
<u> </u> Sparsely Vegetated Concave Surface (B8)																																
<u> </u> Surface Soil Cracks (B6)																																
<u> </u> Drainage Patterns (B10)																																
<u> </u> Moss Trim Lines (B16)																																
<u> </u> Dry-Season Water Table (C2)																																
<u> </u> Crayfish Burrows (C8)																																
<u> </u> Saturation Visible on Aerial Imagery (C9)																																
<u> </u> Stunted or Stressed Plants (D1)																																
<u>X</u> Geomorphic Position (D2)																																
<u> </u> Shallow Aquitard (D3)																																
<u> </u> Microtopographic Relief (D4)																																
<u>X</u> FAC-Neutral Test (D5)																																
<b>Field Observations:</b> Surface Water Present? Yes <u> </u> No <u>X</u> Depth (inches): <u> </u> Water Table Present? Yes <u>X</u> No <u> </u> Depth (inches): <u>4</u> Saturation Present? Yes <u>X</u> No <u> </u> Depth (inches): <u>0</u> (includes capillary fringe)	Wetland Hydrology Present? Yes <u>X</u> No <u> </u>																															
Describe Recorded Data (stream gauge, monitoring well, aerial photos, previous inspections), if available:  																																
Remarks:																																

**VEGETATION – Use scientific names of plants.**

Sampling Point: SP-14

<u>Tree Stratum</u> (Plot size: <u>30</u> )	Absolute % Cover	Dominant Species?	Indicator Status		
1. _____	_____	_____	_____	<b>Dominance Test worksheet:</b>  Number of Dominant Species That Are OBL, FACW, or FAC: _____ (A)  Total Number of Dominant Species Across All Strata: _____ (B)  Percent of Dominant Species That Are OBL, FACW, or FAC: _____ (A/B)	
2. _____	_____	_____	_____		
3. _____	_____	_____	_____		
4. _____	_____	_____	_____		
5. _____	_____	_____	_____		
6. _____	_____	_____	_____		
7. _____	_____	_____	_____		
_____ =Total Cover				<b>Prevalence Index worksheet:</b>  Total % Cover of: _____ Multiply by: _____ OBL species _____ x 1 = _____ FACW species _____ x 2 = _____ FAC species _____ x 3 = _____ FACU species _____ x 4 = _____ UPL species _____ x 5 = _____ Column Totals: _____ (A) _____ (B) Prevalence Index = B/A = _____	
<u>Sapling/Shrub Stratum</u> (Plot size: <u>15</u> )	Absolute % Cover	Dominant Species?	Indicator Status		
1. _____	_____	_____	_____		
2. _____	_____	_____	_____		
3. _____	_____	_____	_____		
4. _____	_____	_____	_____		
5. _____	_____	_____	_____		
6. _____	_____	_____	_____		
7. _____	_____	_____	_____		
_____ =Total Cover				<b>Hydrophytic Vegetation Indicators:</b> <input checked="" type="checkbox"/> 1 - Rapid Test for Hydrophytic Vegetation <input type="checkbox"/> 2 - Dominance Test is >50% <input type="checkbox"/> 3 - Prevalence Index is ≤3.0 <sup>1</sup> <input type="checkbox"/> 4 - Morphological Adaptations <sup>1</sup> (Provide supporting data in Remarks or on a separate sheet) <input type="checkbox"/> Problematic Hydrophytic Vegetation <sup>1</sup> (Explain)  <sup>1</sup> Indicators of hydric soil and wetland hydrology must be present, unless disturbed or problematic.	
<u>Herb Stratum</u> (Plot size: <u>5</u> )	Absolute % Cover	Dominant Species?	Indicator Status		
1. <u>Phragmites australis</u>	90	Yes	FACW		
2. <u>Cornus amomum</u>	15	No	FACW		
3. _____	_____	_____	_____		
4. _____	_____	_____	_____		
5. _____	_____	_____	_____		
6. _____	_____	_____	_____		
7. _____	_____	_____	_____		
8. _____	_____	_____	_____		
9. _____	_____	_____	_____		
10. _____	_____	_____	_____		
11. _____	_____	_____	_____		
12. _____	_____	_____	_____		
105 =Total Cover				<b>Definitions of Vegetation Strata:</b>  <b>Tree</b> – Woody plants 3 in. (7.6 cm) or more in diameter at breast height (DBH), regardless of height.  <b>Sapling/shrub</b> – Woody plants less than 3 in. DBH and greater than or equal to 3.28 ft (1 m) tall.  <b>Herb</b> – All herbaceous (non-woody) plants, regardless of size, and woody plants less than 3.28 ft tall.  <b>Woody vines</b> – All woody vines greater than 3.28 ft in height.	
<u>Woody Vine Stratum</u> (Plot size: <u>15</u> )	Absolute % Cover	Dominant Species?	Indicator Status		
1. <u>Cornus amomum</u>	30	Yes	FACW		
2. _____	_____	_____	_____		
3. _____	_____	_____	_____		
4. _____	_____	_____	_____		
30 =Total Cover				<b>Hydrophytic Vegetation Present?</b> Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>	
Remarks: (Include photo numbers here or on a separate sheet.)					

**SOIL**

Sampling Point: SP-14

**Profile Description: (Describe to the depth needed to document the indicator or confirm the absence of indicators.)**

Depth (inches)	Matrix		Redox Features				Texture	Remarks
	Color (moist)	%	Color (moist)	%	Type <sup>1</sup>	Loc <sup>2</sup>		
0-16	10YR 4/1	98	10YR 4/4	2	C	M	Loamy/Clayey	

<sup>1</sup>Type: C=Concentration, D=Depletion, RM=Reduced Matrix, MS=Masked Sand Grains. <sup>2</sup>Location: PL=Pore Lining, M=Matrix.

<b>Hydric Soil Indicators:</b>			<b>Indicators for Problematic Hydric Soils<sup>3</sup>:</b>		
<input type="checkbox"/> Histosol (A1)	<input type="checkbox"/> Polyvalue Below Surface (S8) (LRR R, MLRA 149B)	<input type="checkbox"/> 2 cm Muck (A10) (LRR K, L, MLRA 149B)			
<input type="checkbox"/> Histic Epipedon (A2)	<input type="checkbox"/> Thin Dark Surface (S9) (LRR R, MLRA 149B)	<input type="checkbox"/> Coast Prairie Redox (A16) (LRR K, L, R)			
<input type="checkbox"/> Black Histic (A3)	<input type="checkbox"/> High Chroma Sands (S11) (LRR K, L)	<input type="checkbox"/> 5 cm Mucky Peat or Peat (S3) (LRR K, L, R)			
<input type="checkbox"/> Hydrogen Sulfide (A4)	<input type="checkbox"/> Loamy Mucky Mineral (F1) (LRR K, L)	<input type="checkbox"/> Polyvalue Below Surface (S8) (LRR K, L)			
<input type="checkbox"/> Stratified Layers (A5)	<input type="checkbox"/> Loamy Gleyed Matrix (F2)	<input type="checkbox"/> Thin Dark Surface (S9) (LRR K, L)			
<input type="checkbox"/> Depleted Below Dark Surface (A11)	<input checked="" type="checkbox"/> Depleted Matrix (F3)	<input type="checkbox"/> Iron-Manganese Masses (F12) (LRR K, L, R)			
<input type="checkbox"/> Thick Dark Surface (A12)	<input type="checkbox"/> Redox Dark Surface (F6)	<input type="checkbox"/> Piedmont Floodplain Soils (F19) (MLRA 149B)			
<input type="checkbox"/> Sandy Mucky Mineral (S1)	<input type="checkbox"/> Depleted Dark Surface (F7)	<input type="checkbox"/> Mesic Spodic (TA6) (MLRA 144A, 145, 149B)			
<input type="checkbox"/> Sandy Gleyed Matrix (S4)	<input type="checkbox"/> Redox Depressions (F8)	<input type="checkbox"/> Red Parent Material (F21)			
<input type="checkbox"/> Sandy Redox (S5)	<input type="checkbox"/> Marl (F10) (LRR K, L)	<input type="checkbox"/> Very Shallow Dark Surface (F22)			
<input type="checkbox"/> Stripped Matrix (S6)		<input type="checkbox"/> Other (Explain in Remarks)			
<input type="checkbox"/> Dark Surface (S7)					

<sup>3</sup>Indicators of hydrophytic vegetation and wetland hydrology must be present, unless disturbed or problematic.

<b>Restrictive Layer (if observed):</b>		<b>Hydric Soil Present?</b>	
Type: <u>fill/stones</u>		Yes <u>X</u>	No <u>    </u>
Depth (inches): <u>16</u>			

Remarks:



**WETLAND DETERMINATION DATA FORM – Northcentral and Northeast Region**

Project/Site: Celi Drive BCP Site (BCP Site #C734108) City/County: Onondaga County Sampling Date: 11/15/2017  
 Applicant/Owner: GSP Holdings, Inc. State: NY Sampling Point: SP-15  
 Investigator(s): Melissa Harrison, Gregory Kunka Section, Township, Range: Town of Dewitt  
 Landform (hillside, terrace, etc.): floodplain Local relief (concave, convex, none): none Slope %: 0-2  
 Subregion (LRR or MLRA): LRR L, MLRA 101 Lat: 43.0568707203 Long: -76.0749921338 Datum: NAD 1983  
 Soil Map Unit Name: Cut and fill land (CFL) NWI classification: none

Are climatic / hydrologic conditions on the site typical for this time of year? Yes X No \_\_\_\_\_ (If no, explain in Remarks.)  
 Are Vegetation X, Soil X, or Hydrology \_\_\_\_\_ significantly disturbed? Are "Normal Circumstances" present? Yes \_\_\_\_\_ No X  
 Are Vegetation \_\_\_\_\_, Soil \_\_\_\_\_, or Hydrology \_\_\_\_\_ naturally problematic? (If needed, explain any answers in Remarks.)

**SUMMARY OF FINDINGS – Attach site map showing sampling point locations, transects, important features, etc.**

Hydrophytic Vegetation Present?	Yes _____	No <u>X</u>	<b>Is the Sampled Area within a Wetland?</b> Yes _____ No <u>X</u> If yes, optional Wetland Site ID: _____
Hydric Soil Present?	Yes _____	No <u>X</u>	
Wetland Hydrology Present?	Yes _____	No <u>X</u>	
Remarks: (Explain alternative procedures here or in a separate report.) Area impacted from previous construction of electric utility pad and continued maintenance including mowing.			

**HYDROLOGY**

<p><b>Wetland Hydrology Indicators:</b></p> <p><u>Primary Indicators (minimum of one is required; check all that apply)</u></p> <table style="width:100%;"> <tr> <td><input type="checkbox"/> Surface Water (A1)</td> <td><input type="checkbox"/> Water-Stained Leaves (B9)</td> </tr> <tr> <td><input type="checkbox"/> High Water Table (A2)</td> <td><input type="checkbox"/> Aquatic Fauna (B13)</td> </tr> <tr> <td><input type="checkbox"/> Saturation (A3)</td> <td><input type="checkbox"/> Marl Deposits (B15)</td> </tr> <tr> <td><input type="checkbox"/> Water Marks (B1)</td> <td><input type="checkbox"/> Hydrogen Sulfide Odor (C1)</td> </tr> <tr> <td><input type="checkbox"/> Sediment Deposits (B2)</td> <td><input type="checkbox"/> Oxidized Rhizospheres on Living Roots (C3)</td> </tr> <tr> <td><input type="checkbox"/> Drift Deposits (B3)</td> <td><input type="checkbox"/> Presence of Reduced Iron (C4)</td> </tr> <tr> <td><input type="checkbox"/> Algal Mat or Crust (B4)</td> <td><input type="checkbox"/> Recent Iron Reduction in Tilled Soils (C6)</td> </tr> <tr> <td><input type="checkbox"/> Iron Deposits (B5)</td> <td><input type="checkbox"/> Thin Muck Surface (C7)</td> </tr> <tr> <td><input type="checkbox"/> Inundation Visible on Aerial Imagery (B7)</td> <td><input type="checkbox"/> Other (Explain in Remarks)</td> </tr> <tr> <td><input type="checkbox"/> Sparsely Vegetated Concave Surface (B8)</td> <td></td> </tr> </table>	<input type="checkbox"/> Surface Water (A1)	<input type="checkbox"/> Water-Stained Leaves (B9)	<input type="checkbox"/> High Water Table (A2)	<input type="checkbox"/> Aquatic Fauna (B13)	<input type="checkbox"/> Saturation (A3)	<input type="checkbox"/> Marl Deposits (B15)	<input type="checkbox"/> Water Marks (B1)	<input type="checkbox"/> Hydrogen Sulfide Odor (C1)	<input type="checkbox"/> Sediment Deposits (B2)	<input type="checkbox"/> Oxidized Rhizospheres on Living Roots (C3)	<input type="checkbox"/> Drift Deposits (B3)	<input type="checkbox"/> Presence of Reduced Iron (C4)	<input type="checkbox"/> Algal Mat or Crust (B4)	<input type="checkbox"/> Recent Iron Reduction in Tilled Soils (C6)	<input type="checkbox"/> Iron Deposits (B5)	<input type="checkbox"/> Thin Muck Surface (C7)	<input type="checkbox"/> Inundation Visible on Aerial Imagery (B7)	<input type="checkbox"/> Other (Explain in Remarks)	<input type="checkbox"/> Sparsely Vegetated Concave Surface (B8)		<p><u>Secondary Indicators (minimum of two required)</u></p> <table style="width:100%;"> <tr><td><input type="checkbox"/> Surface Soil Cracks (B6)</td></tr> <tr><td><input type="checkbox"/> Drainage Patterns (B10)</td></tr> <tr><td><input type="checkbox"/> Moss Trim Lines (B16)</td></tr> <tr><td><input type="checkbox"/> Dry-Season Water Table (C2)</td></tr> <tr><td><input type="checkbox"/> Crayfish Burrows (C8)</td></tr> <tr><td><input type="checkbox"/> Saturation Visible on Aerial Imagery (C9)</td></tr> <tr><td><input type="checkbox"/> Stunted or Stressed Plants (D1)</td></tr> <tr><td><input type="checkbox"/> Geomorphic Position (D2)</td></tr> <tr><td><input type="checkbox"/> Shallow Aquitard (D3)</td></tr> <tr><td><input type="checkbox"/> Microtopographic Relief (D4)</td></tr> <tr><td><input type="checkbox"/> FAC-Neutral Test (D5)</td></tr> </table>	<input type="checkbox"/> Surface Soil Cracks (B6)	<input type="checkbox"/> Drainage Patterns (B10)	<input type="checkbox"/> Moss Trim Lines (B16)	<input type="checkbox"/> Dry-Season Water Table (C2)	<input type="checkbox"/> Crayfish Burrows (C8)	<input type="checkbox"/> Saturation Visible on Aerial Imagery (C9)	<input type="checkbox"/> Stunted or Stressed Plants (D1)	<input type="checkbox"/> Geomorphic Position (D2)	<input type="checkbox"/> Shallow Aquitard (D3)	<input type="checkbox"/> Microtopographic Relief (D4)	<input type="checkbox"/> FAC-Neutral Test (D5)
<input type="checkbox"/> Surface Water (A1)	<input type="checkbox"/> Water-Stained Leaves (B9)																															
<input type="checkbox"/> High Water Table (A2)	<input type="checkbox"/> Aquatic Fauna (B13)																															
<input type="checkbox"/> Saturation (A3)	<input type="checkbox"/> Marl Deposits (B15)																															
<input type="checkbox"/> Water Marks (B1)	<input type="checkbox"/> Hydrogen Sulfide Odor (C1)																															
<input type="checkbox"/> Sediment Deposits (B2)	<input type="checkbox"/> Oxidized Rhizospheres on Living Roots (C3)																															
<input type="checkbox"/> Drift Deposits (B3)	<input type="checkbox"/> Presence of Reduced Iron (C4)																															
<input type="checkbox"/> Algal Mat or Crust (B4)	<input type="checkbox"/> Recent Iron Reduction in Tilled Soils (C6)																															
<input type="checkbox"/> Iron Deposits (B5)	<input type="checkbox"/> Thin Muck Surface (C7)																															
<input type="checkbox"/> Inundation Visible on Aerial Imagery (B7)	<input type="checkbox"/> Other (Explain in Remarks)																															
<input type="checkbox"/> Sparsely Vegetated Concave Surface (B8)																																
<input type="checkbox"/> Surface Soil Cracks (B6)																																
<input type="checkbox"/> Drainage Patterns (B10)																																
<input type="checkbox"/> Moss Trim Lines (B16)																																
<input type="checkbox"/> Dry-Season Water Table (C2)																																
<input type="checkbox"/> Crayfish Burrows (C8)																																
<input type="checkbox"/> Saturation Visible on Aerial Imagery (C9)																																
<input type="checkbox"/> Stunted or Stressed Plants (D1)																																
<input type="checkbox"/> Geomorphic Position (D2)																																
<input type="checkbox"/> Shallow Aquitard (D3)																																
<input type="checkbox"/> Microtopographic Relief (D4)																																
<input type="checkbox"/> FAC-Neutral Test (D5)																																
<p><b>Field Observations:</b></p> <table style="width:100%;"> <tr> <td>Surface Water Present?</td> <td>Yes _____</td> <td>No <u>X</u></td> <td>Depth (inches): _____</td> </tr> <tr> <td>Water Table Present?</td> <td>Yes _____</td> <td>No <u>X</u></td> <td>Depth (inches): _____</td> </tr> <tr> <td>Saturation Present?</td> <td>Yes _____</td> <td>No <u>X</u></td> <td>Depth (inches): _____</td> </tr> </table> <p>(includes capillary fringe)</p>	Surface Water Present?	Yes _____	No <u>X</u>	Depth (inches): _____	Water Table Present?	Yes _____	No <u>X</u>	Depth (inches): _____	Saturation Present?	Yes _____	No <u>X</u>	Depth (inches): _____	<p><b>Wetland Hydrology Present?</b> Yes _____ No <u>X</u></p>																			
Surface Water Present?	Yes _____	No <u>X</u>	Depth (inches): _____																													
Water Table Present?	Yes _____	No <u>X</u>	Depth (inches): _____																													
Saturation Present?	Yes _____	No <u>X</u>	Depth (inches): _____																													
Describe Recorded Data (stream gauge, monitoring well, aerial photos, previous inspections), if available:																																
Remarks:																																

**VEGETATION – Use scientific names of plants.**

Sampling Point: SP-15

	Absolute % Cover	Dominant Species?	Indicator Status																	
<b>Tree Stratum</b> (Plot size: <u>30</u> )				<b>Dominance Test worksheet:</b>  Number of Dominant Species That Are OBL, FACW, or FAC: <u>0</u> (A)  Total Number of Dominant Species Across All Strata: <u>2</u> (B)  Percent of Dominant Species That Are OBL, FACW, or FAC: <u>0.0%</u> (A/B)																
1.																				
2.																				
3.																				
4.																				
5.																				
6.																				
7.																				
=Total Cover				<b>Prevalence Index worksheet:</b>  <table style="width:100%; border:none;"> <tr> <td style="text-align:right;">Total % Cover of:</td> <td style="text-align:center;">Multiply by:</td> </tr> <tr> <td>OBL species <u>0</u></td> <td>x 1 = <u>0</u></td> </tr> <tr> <td>FACW species <u>0</u></td> <td>x 2 = <u>0</u></td> </tr> <tr> <td>FAC species <u>0</u></td> <td>x 3 = <u>0</u></td> </tr> <tr> <td>FACU species <u>85</u></td> <td>x 4 = <u>340</u></td> </tr> <tr> <td>UPL species <u>0</u></td> <td>x 5 = <u>0</u></td> </tr> <tr> <td>Column Totals: <u>85</u> (A)</td> <td><u>340</u> (B)</td> </tr> <tr> <td colspan="2" style="text-align:center;">Prevalence Index = B/A = <u>4.00</u></td> </tr> </table>	Total % Cover of:	Multiply by:	OBL species <u>0</u>	x 1 = <u>0</u>	FACW species <u>0</u>	x 2 = <u>0</u>	FAC species <u>0</u>	x 3 = <u>0</u>	FACU species <u>85</u>	x 4 = <u>340</u>	UPL species <u>0</u>	x 5 = <u>0</u>	Column Totals: <u>85</u> (A)	<u>340</u> (B)	Prevalence Index = B/A = <u>4.00</u>	
Total % Cover of:	Multiply by:																			
OBL species <u>0</u>	x 1 = <u>0</u>																			
FACW species <u>0</u>	x 2 = <u>0</u>																			
FAC species <u>0</u>	x 3 = <u>0</u>																			
FACU species <u>85</u>	x 4 = <u>340</u>																			
UPL species <u>0</u>	x 5 = <u>0</u>																			
Column Totals: <u>85</u> (A)	<u>340</u> (B)																			
Prevalence Index = B/A = <u>4.00</u>																				
<b>Sapling/Shrub Stratum</b> (Plot size: <u>15</u> )																				
1.																				
2.																				
3.																				
4.																				
5.																				
6.																				
7.																				
=Total Cover																				
<b>Herb Stratum</b> (Plot size: <u>5</u> )				<b>Hydrophytic Vegetation Indicators:</b> <u>1</u> - Rapid Test for Hydrophytic Vegetation <u>2</u> - Dominance Test is >50% <u>3</u> - Prevalence Index is ≤3.0 <sup>1</sup> <u>4</u> - Morphological Adaptations <sup>1</sup> (Provide supporting data in Remarks or on a separate sheet) Problematic Hydrophytic Vegetation <sup>1</sup> (Explain)  <sup>1</sup> Indicators of hydric soil and wetland hydrology must be present, unless disturbed or problematic.																
1.	<u>Poa pratensis</u>	35	Yes		FACU															
2.	<u>Poa compressa</u>	25	Yes		FACU															
3.	<u>Cynodon dactylon</u>	15	No		FACU															
4.	<u>Plantago major</u>	5	No		FACU															
5.	<u>Digitaria sanguinalis</u>	5	No		FACU															
6.																				
7.																				
8.																				
9.																				
10.																				
11.																				
12.																				
85 =Total Cover																				
<b>Woody Vine Stratum</b> (Plot size: <u>15</u> )				<b>Definitions of Vegetation Strata:</b>  <b>Tree</b> – Woody plants 3 in. (7.6 cm) or more in diameter at breast height (DBH), regardless of height.  <b>Sapling/shrub</b> – Woody plants less than 3 in. DBH and greater than or equal to 3.28 ft (1 m) tall.  <b>Herb</b> – All herbaceous (non-woody) plants, regardless of size, and woody plants less than 3.28 ft tall.  <b>Woody vines</b> – All woody vines greater than 3.28 ft in height.																
1.																				
2.																				
3.																				
4.																				
=Total Cover																				
<b>Hydrophytic Vegetation Present?</b> Yes <u>      </u> No <u>  X  </u>																				
Remarks: (Include photo numbers here or on a separate sheet.)    																				

**SOIL**

Sampling Point: SP-15

**Profile Description: (Describe to the depth needed to document the indicator or confirm the absence of indicators.)**

Depth (Inches)	Matrix		Redox Features				Texture	Remarks
	Color (moist)	%	Color (moist)	%	Type <sup>1</sup>	Loc <sup>2</sup>		
0-6	10YR 4/4	100					Loamey/Clayey	variegated fill

<sup>1</sup>Type: C=Concentration, D=Depletion, RM=Reduced Matrix, MS=Masked Sand Grains.      <sup>2</sup>Location: PL=Pore Lining, M=Matrix.

**Hydric Soil Indicators:**

- Histosol (A1)
- Histic Epipedon (A2)
- Black Histic (A3)
- Hydrogen Sulfide (A4)
- Stratified Layers (A5)
- Depleted Below Dark Surface (A11)
- Thick Dark Surface (A12)
- Sandy Mucky Mineral (S1)
- Sandy Gleyed Matrix (S4)
- Sandy Redox (S5)
- Stripped Matrix (S6)
- Dark Surface (S7)

- Polyvalue Below Surface (S8) (LRR R, MLRA 149B)
- Thin Dark Surface (S9) (LRR R, MLRA 149B)
- High Chroma Sands (S11) (LRR K, L)
- Loamy Mucky Mineral (F1) (LRR K, L)
- Loamy Gleyed Matrix (F2)
- Depleted Matrix (F3)
- Redox Dark Surface (F6)
- Depleted Dark Surface (F7)
- Redox Depressions (F8)
- Marl (F10) (LRR K, L)

**Indicators for Problematic Hydric Soils<sup>3</sup>:**

- 2 cm Muck (A10) (LRR K, L, MLRA 149B)
- Coast Prairie Redox (A16) (LRR K, L, R)
- 5 cm Mucky Peat or Peat (S3) (LRR K, L, R)
- Polyvalue Below Surface (S8) (LRR K, L)
- Thin Dark Surface (S9) (LRR K, L)
- Iron-Manganese Masses (F12) (LRR K, L, R)
- Piedmont Floodplain Soils (F19) (MLRA 149B)
- Mesic Spodic (TA6) (MLRA 144A, 145, 149B)
- Red Parent Material (F21)
- Very Shallow Dark Surface (F22)
- Other (Explain in Remarks)

<sup>3</sup>Indicators of hydrophytic vegetation and wetland hydrology must be present, unless disturbed or problematic.

**Restrictive Layer (if observed):**

Type: fill/stones  
 Depth (inches): 6

Hydric Soil Present?      Yes       No

**Remarks:**

Area impacted from previous construction of electric utility pad and continued maintenance including mowing.

## **Appendix C – Color Photographs**



**Photo: 1. Facing N at SP-01 towards PEM in Wetland Complex A (photo taken 11/14/2017).**



**Photo: 2. Facing E at SP-01 towards swale (photo taken 11/14/2017).**



**Photo: 3. Facing S at SP-01 towards swale (photo taken 11/14/2017).**



**Photo: 4. Facing W at SP-01 towards study area boundary, PEM in Wetland Complex A (on right), and access road (on left) (photo taken 11/14/2017).**



**Photo: 5. Facing N at SP-03 towards PFO in Wetland Complex A (photo taken 11/14/2017).**



**Photo: 6. Facing E at SP-03 towards PFO boundary and upland (photo taken 11/14/2017).**



**Photo: 7. Facing S at SP-03 towards upland (photo taken 11/14/2017).**



**Photo: 8. Facing W at SP-03 towards PFO in Wetland Complex A (photo taken 11/14/2017).**





**Photo: 9. Facing N at culvert, flag "GPS BENCH 1" towards swale and PEM in Wetland Complex A (on right) (photo taken 11/14/2017).**



**Photo: 10. Facing E at culvert, flag "GPS BENCH 1" towards uplands (photo taken 11/14/2017).**



**Photo: 11. Facing S at culvert, flag "GPS BENCH 1" towards uplands (photo taken 11/14/2017).**



**Photo: 12. Facing W at culvert, flag "GPS BENCH 1" towards uplands (photo taken 11/14/2017).**



**Photo: 13. Facing N at flag "SWALE 11 CULVERT OPEN" towards access road (on left) and PEM in Wetland Complex A (on right) (photo taken 11/14/2017).**



**Photo: 14. Facing E at flag "SWALE 11 CULVERT OPEN" towards access road (on left) and PEM in Wetland Complex A (on right) (photo taken 11/14/2017).**



**Photo: 15. Facing S at flag "SWALE 11 CULVERT OPEN" towards access road (on left) and PEM in Wetland Complex A (on right) (photo taken 11/14/2017).**



**Photo: 16. Facing W at flag "SWALE 11 CULVERT OPEN" towards access road and PEM in Wetland Complex A (photo taken 11/14/2017).**



**Photo: 17. Facing N from SP-04 towards PEM in Wetland Complex A (photo taken 11/14/2017).**



**Photo: 18. Facing E from SP-04 towards PEM in Wetland Complex A (in foreground) and access road (in background) (photo taken 11/14/2017).**



**Photo: 19. Facing S from SP-04 towards PEM in Wetland Complex A (photo taken 11/14/2017).**



**Photo: 20. Facing W from SP-04 towards PEM in Wetland Complex A (photo taken 11/14/2017).**



**Photo: 21. Facing N at flag “WL A 301 FENCE” towards PEM in Wetland Complex A (on left) and swale (on right) (photo taken 11/14/2017).**



**Photo: 22. Facing E at flag “WL A 301 FENCE” towards uplands (on left) and swale (on right) (photo taken 11/14/2017).**



**Photo: 23. Facing S at flag "WL A 301 FENCE" towards uplands (on left), swale, and access road (on right) (photo taken 11/14/2017).**



**Photo: 24. Facing W at flag "WL A 301 FENCE" towards PSS in Wetland Complex A (photo taken 11/14/2017).**





**Photo: 25. Facing N at flag “WL A 422 OPEN” towards PEM in Wetland Complex A and parking lot (on right) (photo taken 11/15/2017).**



**Photo: 26. Facing E at flag “WL A 422 OPEN” towards PEM in Wetland Complex A and parking lot (on right) (photo taken 11/15/2017).**



**Photo: 27. Facing S at flag “WL A 422 OPEN” towards PSS in Wetland Complex A and parking lot (on right) (photo taken 11/15/2017).**



**Photo: 28. Facing W at flag “WL A 422 OPEN” towards PSS in Wetland Complex A and parking lot (on right) (photo taken 11/15/2017).**



**Photo: 29. Facing N at flag “WL A 604 OPEN” towards PEM in Wetland Complex A (on left), swale (center), and Bridge Street (on right) (photo taken 11/15/2017).**



**Photo: 30. Facing E at flag “WL A 604 OPEN” towards PEM in Wetland Complex A (on left), swale (center), and Bridge Street (on right) (photo taken 11/15/2017).**



**Photo: 31. Facing S at flag “WL A 603 OPEN” towards PEM in Wetland Complex A (on right), swale (center), and Bridge Street (on left) (photo taken 11/15/2017).**



**Photo: 32. Facing W at flag “WL A 603 OPEN” towards PEM in Wetland Complex A swale (foreground) (photo taken 11/15/2017).**



**Photo:** 33. Facing N at SP-07 towards upland and Interstate 690 (photo taken 11/15/2017).



**Photo:** 34. Facing E at SP-07 towards PEM in Wetland Complex A and swale (on right) (photo taken 11/15/2017).



**Photo: 35. Facing S at SP-07 towards swale (photo taken 11/15/2017).**



**Photo: 36. Facing W at SP-07 towards PEM in Wetland Complex A, swale (on left) and uplands (on right) (photo taken 11/15/2017).**



**Photo: 37. Facing N at flag “WL A 710 OPEN” towards upland and Interstate 690 (photo taken 11/15/2017).**



**Photo: 38. Facing E at flag “WL A 710 OPEN” towards PEM in Wetland Complex A (on right) and PFO in Wetland Complex A (in background) (photo taken 11/15/2017).**



**Photo: 39. Facing S at flag “WL A 710 OPEN” towards PEM in Wetland Complex A (photo taken 11/15/2017).**




**Photo: 40. Facing W at flag “WL A 710 OPEN” towards PEM in Wetland Complex A (on left) and PFO in Wetland Complex A (in background) (photo taken 11/15/2017).**





**Photo: 41. Facing W at the intersection of the swale and culvert crossing of Interstate 690 (photo taken 11/15/2017).**



**Photo: 42. Facing W at the intersection of the swale and culvert crossing of Interstate 690 (photo taken 11/15/2017).**



**Photo: 43. Facing N at flag “WL A 922” towards PEM in Wetland Complex A (photo taken 11/15/2017).**



**Photo: 44. Facing E at flag “WL A 922” towards PEM in Wetland Complex A (photo taken 11/15/2017).**



**Photo: 45. Facing S at flag "WL A 922" towards PEM in Wetland Complex A (photo taken 11/15/2017).**



**Photo: 46. Facing W at flag "WL A 922" towards PEM in Wetland Complex A (photo taken 11/15/2017).**



**Photo: 47. Facing N at SP-13 towards access road and PSS in Wetland Complex A (photo taken 11/15/2017).**



**Photo: 48. Facing E at SP-13 towards access road (on left) and PEM in Wetland Complex A (on right) (photo taken 11/15/2017).**



**Photo: 49. Facing S at SP-13 towards PEM in Wetland Complex A (photo taken 11/15/2017).**



**Photo: 50. Facing W at SP-13 towards access road (on right) and PEM in Wetland Complex A (on left) (photo taken 11/15/2017).**



**Photo: 51. Facing N at flag “WL A 196” towards swale and PEM in Wetland Complex A (photo taken 11/15/2017).**



**Photo: 52. Facing E at flag “WL A 196” towards PEM in Wetland Complex A (on left) and uplands and electric substation (on right) (photo taken 11/15/2017).**



**Photo:** 53. Facing S at flag “WL A 196” towards uplands and access road (photo taken 11/15/2017).



**Photo:** 54. Facing W at flag “WL A 196” towards swale (in foreground) and PEM in Wetland Complex A (in background) (photo taken 11/15/2017).



**Photo: 55. Facing N at flag "WL A 1407" towards swale and PSS in Wetland Complex A (photo taken 11/15/2017).**



**Photo: 56. Facing E at flag "WL A 1407" towards access road (on right) and PSS in Wetland Complex A (on left) (photo taken 11/15/2017).**





**Photo:** 57. Facing S at flag "WL A 1407" towards access road (in foreground) and PEM in Wetland Complex A (in background) (photo taken 11/15/2017).



**Photo:** 58. Facing W at flag "WL A 1407" towards access road (on left) and PSS Wetland Complex A (on right) (photo taken 11/15/2017).



**Photo: 59. Facing N at SP-15 (upland) towards PEM in Wetland Complex A (photo taken 11/15/2017).**




**Photo: 60. Facing E at SP-15 (upland) towards PEM in Wetland Complex A (photo taken 11/15/2017).**



**Photo: 61. Facing S at SP-15 (upland) towards PEM in Wetland Complex A and electric substation (on right) (photo taken 11/15/2017).**



**Photo: 62. Facing W at SP-15 (upland) towards PEM in Wetland Complex A (on right) and electric substation (on left) (photo taken 11/15/2017).**



**Photo: 63. Facing N at flag “WL A 1711” towards swale and PFO in Wetland Complex A (on right) (photo taken 11/15/2017).**



**Photo: 64. Facing E at flag “WL A 1711” towards uplands (photo taken 11/15/2017).**



**Photo: 65. Facing S at flag “WL A 1711” towards uplands (on left) and swale (on right) (photo taken 11/15/2017).**



**Photo: 66. Facing W at flag “WL A 1711” towards swale (in foreground) study area boundary (in background) (photo taken 11/15/2017).**

## **Appendix D– Wetland Certifications**

# Certificate of Training

## Wetland Delineation & Regional Supplement Training

This certifies that

**Melissa M. Harrison**

has participated in 36 hours of classroom & field instruction.

Date: May 1, 2015

This course has been pre-approved by the SWSPCP as meeting standards for content and instruction and, upon successful completion, has been judged to be immediately eligible to receive credits and/or points toward SWSPCP Professional Certification or SWSPCP Professional Certification Renewal.



**Swamp School, LLC**

RALEIGH, NC 27603  
1-877-479-2673

[www.SwampSchool.org](http://www.SwampSchool.org)



*Marc Seelinger*  
SIGNATURE OF AUTHORIZATION





# Richard Chinn Environmental Training, Inc.

certifies that

**Gregory Kunka**

has successfully completed a

## 38 Hour Army Corps of Engineers Wetland Delineation Training Program

issued certificate No. 7893 and 3.8 CEUs, April 12 - 15, 2016 in State College, Pennsylvania

This course is pre-approved by the Society of Wetland Scientists Professional Certification Program to provide 2.5 Training Credits and/or Points.

  
Richard Chinn, PWS, CET

Richard Chinn Environmental Training, Inc.

804 Cottage Hill Way, Brandon, FL 33511-8098

813.655.7549 • FAX: 813.354.4659 • [info@richardchinn.com](mailto:info@richardchinn.com) • <http://www.richardchinn.com>

This training has been based in part on the U. S. Army Corps of Engineers Wetlands Delineation Manual Technical Report Y-87-1 (1987 manual), as provided for in the training materials developed in conjunction with section 307(c) of the Water Resources Development Act of 1990 for the Wetland Delineator Certification Program.





**GHD**

**1240 North Mountain Road**

**Harrisburg PA 17112**

**T: 1 717 541 0622 F: 1 717 541 8004 E: harrisburg@ghd.com**

**© GHD 2018**

**This document is and shall remain the property of GHD. The document may only be used for the purpose of assessing our offer of services and for inclusion in documentation for the engagement of GHD. Unauthorized use of this document in any form whatsoever is prohibited.**

*APPENDIX D*

*Health & Safety Plan*

# HEALTH AND SAFETY PLAN (HASP)

*The HASP considers the specific hazards inherent to this project and presents procedures for managing those hazards. Due to the potential hazards of this Site and the activities occurring thereon, it is not possible to discover, evaluate, and provide protection for all possible hazards, which may be encountered. Strict adherence to the health and safety guidelines set forth herein, will reduce, but may not eliminate, the potential for injury at this Site.*

<b>PROJECT NAME:</b>	Celi Drive BCP Site AOC-4	<b>CLIENT ORGANIZATION:</b>	General Super Plating Co., Inc./GSP Holdings, Inc.
<b>SITE ADDRESS:</b>	Celi Drive Dewitt, NY	<b>CLIENT ADDRESS:</b>	
<b>NYSDEC REGION:</b>	7	<b>CLIENT CONTACT:</b>	
<b>PROJECT NUMBER:</b>	NYSDEC Site No. C734108	<b>CLIENT PHONE:</b>	
<b>ORIGINAL HASP DATE:</b>	12-13-22	<b>CONTACT:</b>	
<b>REVISED DATE:</b>	-	<b>CONTACT PHONE:</b>	
<b>REVISION NUMBER:</b>	-		

## Table of Contents

1.	SITE DESCRIPTION AND FEATURES.....	2
2.	SITE HISTORY .....	2
3.	HASP-SPECIFIC TASKS .....	2
4.	SITE TYPE.....	3
5.	POTENTIAL HAZARDOUS MATERIAL SUMMARY .....	3
6.	SITE HAZARD ASSESSMENT .....	5
7.	LEVELS OF PROTECTION .....	7
8.	SITE WORKER & COMMUNITY AIR MONITORING PLAN (CAMP) .....	8
9.	DECONTAMINATION .....	8
10.	WORK TASK SUMMARY.....	9
11.	SITE EMERGENCY / CONTINGENCY PLAN .....	9
12.	MAP TO HOSPITAL:.....	11
13.	TRAINING AND PLAN ACKNOWLEDGEMENT .....	12
14.	SITE MAP .....	12

### 1. SITE DESCRIPTION AND FEATURES:

The Site is the former General Super Plating facility located on Celi Drive in the Town of Dewitt, Onondaga County, New York. Area of Concern 4 (AOC-4) is located on the west side of Bridge Street and encompasses approximately 2,800 linear feet of drainage ditches.

**Nature and Extent of Contamination:** The contaminants of concern at the Site are heavy metals (total and hexavalent chromium, copper, nickel and cyanide).

These contaminants have impacted surface water, soil and sediment in AOC-4.

### 2. SITE HISTORY:

The former General Super Plating operated a plating business on Celi Drive. A wastewater release occurred to the facility in 2005. Wastewater entered the storm water drainage system at and down stream of the facility.

#### **Site Conditions:**

AOC-4 encompasses a series of stormwater drainage ditches on the west side of Bridge Street in the Town of Dewitt. Topographically, the area is relatively flat. Water flows in the drainage ditches from the south to the north and then to the west. Much of the land around the drainage ditches is covered with vegetation characteristic of wetlands. Water flow in the drainage ditches is sluggish. Access to AOC-4 is via gravel drives from the east and the west.

### 3. HASP-SPECIFIC TASKS:

**Excavation of impacted soil, sediment and containment of surface water; and the collection of surface water and soil samples.**

4. SITE TYPE:			
STATUS		TYPE	
Active/Occupied Building		Monitoring wells	
Inactive		Landfill	
Secure (Building)		Former Industrial	
Unsecure	X	Petroleum	
Enclosed space		Undeveloped	X
Remediation	X	Military	
Other	Electrical Substation	Retail - Commercial	

**5. POTENTIAL HAZARDOUS MATERIAL SUMMARY:** [Potential Hazard –Shaded]

CHEMICALS	SOLIDS	SLUDGES	SOLVENTS	OILS	OTHER
Detergents	Heavy Metals	Heavy Metals		Gasoline	
				Diesel	
				Lubricants	

**WASTE TYPES:**

X	Liquid (surface water)	X	Solid (soils)		Sludge		Gas		Unknown		Other-None
---	---------------------------	---	------------------	--	--------	--	-----	--	---------	--	------------

**WASTE CHARACTERISTICS:**

	Corrosive	X	Toxic		Inert Gas		Flammable		Volatile		Reactive		Other
--	-----------	---	-------	--	-----------	--	-----------	--	----------	--	----------	--	-------

MATERIALS TO BE BROUGHT ON SITE FOR THE IDENTIFIED SPECIFIC TASKS: See attached MSDS									
Preservatives		Decontamination		Calibration		Remediation		Others	
	HCL	X	Liquinox™		100ppm isobutylene		Sodium permanganate		Bentonite/Cement Grout
	Other-specify		Alconox™		pH standards		Hydrogen peroxide		
			Other-specify		Conductivity standards		Biostimulant	X	Diesel Fuel (equipment)
					Other-Specify			X	Gasoline (equipment)
KNOWN CONTAMINANTS:									
CONTAMINANT		EXPOSURE ROUTES						PHYSICAL CHARACTERISTICS SYMPTOMS	
Chromium		Ingestion, skin and/or eye contact						Eye and skin irritant, dermatitis	
Copper		Ingestion, skin and/or eye contact						Eye and skin irritant, dermatitis	
Nickel		Ingestion, skin and/or eye contact						Eye and skin irritant, dermatitis	
Cyanide		Ingestion, skin and/or eye contact						Eye and skin irritant, dermatitis	



<b>6. SITE HAZARD ASSESSMENT:</b>					
<b>#</b>	<b>HAZARD</b>	<b>SITE-SPECIFIC CONDITIONS</b>	<b>MITIGATION METHODS</b>	<b>WARNINGS/SYMPTOMS</b>	<b>RESPONSE TO EXPOSURE</b>
A	Heat Stress	-Vigorous physical work associated with excavation and soil staging activities -Warm temperatures -Confining personal protective equipment (PPE) such as tyvek.	-Regulate pace of work -Take regular breaks -Use shade when possible -Regular intake of cool fluids -Dress for task & conditions -Buddy system monitoring	<u>Heat stress/heat stroke</u> -Heavy perspiration -Dizziness -Nausea -Headache -Vertigo -Weakness and thirst -Heat stroke may include hot dry skin and confusion	-Rest in a cool place -Drink cool fluids -Seek immediate medical attention for heat stroke symptoms
B	Cold Stress	-Freezing temperatures during excavation activities -Exposure and wet clothing and gloves from working below the water table and during/ decontamination activities.	-Dress accordingly for task and conditions -Regulate clothing layers to keep body temp comfortable, avoid perspiration -Take breaks in warm areas -Buddy system monitoring	<u>Hypothermia and frostbite</u> -Shivering, tingling, numbness -Apathy or sleepiness, blanching or whitening of skin -Unconsciousness, tissue becomes pale and hard, frozen extremities	-Get out of the cold during the first stages of hypothermia or frostbite -Seek immediate medical attention if frostbite or advanced hypothermia is suspected
C	Explosive Flammable	N/A			
D	Oxygen Deficient	N/A			
E	Noise	Heavy Equipment	-Keep a reasonable distance from noisy equipment -Hearing protection PPE -Buddy system monitoring	-Difficulty hearing normal conversation 2-3 feet away -Increased heart rate -Muscle fatigue	-Move away from noise -Use hearing protection PPE
F	Inorganic Chemicals	N/A			
G	Chemical Exposure	Heavy Metals	-Avoid physical contact / exposure when possible -Stay up-wind of work zone -Review work plans -Use proper PPE -Monitor for exposure -Remove potentially exposed PPE and wash hands whenever leaving the work zone -Buddy system monitoring	-Monitoring indicates unprotected exposure above exposure limit occurred -There is physical evidence of exposure (visual or odors) -Exposure symptoms occur (see Hazardous Material Summary above)	-Stop work and leave the work zone if possible exposure is suspected. -Reevaluate exposure mitigation methods (PPE level, Methodologies, etc.) -If exposure symptoms have occurred seek medical attention immediately

<b>SITE HAZARD ASSESSMENT CONT'D:</b>					
<b>#</b>	<b>HAZARD</b>	<b>SITE-SPECIFIC CONDITIONS</b>	<b>MITIGATION METHODS</b>	<b>WARNINGS/SYMPTOMS</b>	<b>RESPONSE TO EXPOSURE</b>
H	Motorized Traffic	Construction equipment and support vehicles	-Define and secure all work areas with safety cones, safety tape, construction fence, other barriers, or signs as appropriate -If possible, set up work zone to maintain visual on traffic flow	-Review safety procedures with all job site personnel	-Review safety procedures with all job site personnel
I	Heavy Equipment	<u>Track hoers/Skid steers/Dump Trucks:</u> -Entrapment in the machinery -Being struck by machinery	-Only operators of the equipment are allowed in the work zone unless the operator is aware of another person and is maintaining eye contact -Operators must be familiar with equipment procedures for safe operation/ emergency stop features and test daily -Equipment not attended by the operator should be shut down and locked out from operation -Proper PPE must be used	-If mitigation methods are not followed -Close calls	-Review safety procedures with all job site personnel -Seek first aid or immediate medical attention as appropriate
J	Slips & Falls	-Uneven ground surface	-Keep known walking areas free of obstructions / hazards -Identify potential hazards (cones, signage, paint, etc.) -Walk slowly, surveying the ground ahead -Wear appropriate PPE	-If mitigation methods are not followed -Close calls	-Review safety procedures with all job site personnel -Seek first aid or immediate medical attention as appropriate
K	Power and hand tools	-Electric shocks - high pressure water stream (steam cleaner) -Burns (steam cleaner) -Cuts from blades	-Only operators of the tools are allowed in the work zone unless the operator is aware of another person and is maintaining eye contact -Operators must be familiar with equipment procedures for safe operation and inspect tool, cords and GFI operation before use -Equipment not attended by the operator should be unplugged and locked out from operation -Proper PPE must be used, including safety glasses, hearing protection and appropriate gloves	-If mitigation methods are not followed -Close calls	-Review safety procedures with all job site personnel -Seek first aid or immediate medical attention as appropriate
L	Waste Handling	-Drum moving and lifting -Pinch-point -Spillage	-Use of appropriate equipment/hand carts for the moving and staging of drums -Follow proper lifting procedures -Proper PPE must be used for the handling and staging of waste		-Review safety procedures with all job site personnel -Seek first aid or immediate medical attention as appropriate

**7. LEVELS OF PROTECTION:** *Shade minimum PPE for each level of protection used*  
*See section 10 for a summary of levels of protection for each activity.*

<i>D-level</i>		<i>D modified-level (D-M)</i>		<i>C-level</i>		<i>B-level</i>	
<input type="checkbox"/>	<i>Steel Toe Boots</i>	<input type="checkbox"/>	<i>All D Items Selected</i>	<input type="checkbox"/>	<i>All D Modified Selected</i>	<input type="checkbox"/>	<i>Not Used</i>
<input type="checkbox"/>	<i>Work Gloves</i>	<input type="checkbox"/>	<i>Rubber Boots</i>	<input type="checkbox"/>	<i>Rubber Boots</i>	<input type="checkbox"/>	
<input type="checkbox"/>	<i>Hard Hat</i>	<input type="checkbox"/>	<i>Latex/Vinyl Disposable Gloves</i>	<input type="checkbox"/>	<i>Half-face APR</i>	<input type="checkbox"/>	
<input type="checkbox"/>	<i>Safety Glasses</i>	<input type="checkbox"/>	<i>Nitrile Gloves</i>	<input type="checkbox"/>	<i>Full-Face APR</i>	<input type="checkbox"/>	
<input type="checkbox"/>	<i>Hearing Protection</i>	<input type="checkbox"/>	<i>Tyvek Coverall</i>	<input type="checkbox"/>	<i>Tyvek Coverall</i>	<input type="checkbox"/>	
<input type="checkbox"/>		<input type="checkbox"/>	<i>Splash Suit</i>	<input type="checkbox"/>	<i>Splash Suit</i>	<input type="checkbox"/>	
<input type="checkbox"/>		<input type="checkbox"/>	<i>Safety Glasses</i>	<input type="checkbox"/>	<i>Face shield</i>	<input type="checkbox"/>	
<input type="checkbox"/>		<input type="checkbox"/>	<i>Face Shield</i>	<input type="checkbox"/>	<i>Other</i>	<input type="checkbox"/>	
<input type="checkbox"/>		<input type="checkbox"/>	<i>Hearing Protection</i>	<input type="checkbox"/>		<input type="checkbox"/>	
<input type="checkbox"/>		<input type="checkbox"/>	<i>Other</i>	<input type="checkbox"/>		<input type="checkbox"/>	

<b>8. SITE WORKER &amp; COMMUNITY AIR MONITORING PLAN (CAMP):</b>		
<b>Work Zone monitoring for fugitive dust will be performed.</b>		
<b>WORK ZONE:</b>	For the purpose of this HASP, the Work Zones (WZ) will be defined as the area within a 50-foot radius of ongoing excavation work. All Work Zones are mobile, should be established in consideration of prevailing wind direction and will be moved as the work crew advances to new locations within the Project Site.	
<b>SUPPORT ZONE:</b>	Support Zones will be all areas outside of current Work Zones.	
<b>INTRUSIVE:</b>	For the purpose of this HASP, intrusive activities will be those that have the ability to unearth identified impacted soils.	
<b>NON-INTRUSIVE:</b>	Any activity, which is not defined as intrusive.	
<b>PERIODIC MONITORING:</b>	All monitoring will be continuous.	
<b>CONTINUOUS MONITORING:</b>	Non-stop real time monitoring with equipment capable of calculating a running average over no less than 15-minute intervals and log monitoring data over no less than an 8-hour work day, which can be downloaded or printed.	
<b>MONITORING REQUIREMENTS:</b>	<b>VOC MONITORING</b>	<b>FUGITIVE DUST &amp; PARTICULATE MONITORING</b>
<b>INTRUSIVE</b>	VOCs are not a contaminant of concern at the site.	
	<b>CONDITION</b>	<b>RESPONSE</b>
	Reasonable fugitive dust suppression techniques must be employed during all site activities, which may generate fugitive dust. Dust suppression techniques may include covering soil piles, wetting of haul pathways, and the use of potable water spray during intrusive activities.  Particulate concentrations will be measured continuously at the upwind and downwind perimeters of the Work Zone at temporary particulate monitoring stations. Real time monitoring equipment will be utilized, capable of measuring particulate matter less than 10 micrometers in size (PM-10) and capable of integrating a 15-minute period for comparison to the particulate action level.  The action level is 150 micrograms-per-cubic-meter (ug/m <sup>3</sup> ) (15 minutes average).  If the downwind PM-10 level is 100 ug/m <sup>3</sup> greater than background (upwind perimeter) for the 15-minute period or if air-borne dust is observed leaving the work area, then dust suppression techniques must be employed. Work may continue with dust suppression techniques provided that downwind PM-10 particulate levels do not exceed 150 mg/m <sup>3</sup> above background.  Should the action level of 150 ug/m <sup>3</sup> continue to be exceeded, work must stop until dust suppression techniques prove adequate or weather conditions change.	
<b>NON-INTRUSIVE</b>		Not required.

<b>9. DECONTAMINATION:</b>		
TYPE	METHOD	CONTAINMENT & DISPOSAL
<b>HEAVY EQUIPMENT</b>	Power washing	Equipment washing will occurred in designated area(s), all waste will be containerized.
<b>SAMPLING EQUIPMENT</b>	Liquinox solution and tap water rinse	Equipment washing will occurred in designated area(s), all waste will be containerized.

<b>PERSONNEL</b>	-Remove PPE avoiding contact with skin -Wash hands first and then face with soap and warm water	Wash water for personnel will be containerized. All one-time use PPE will be discarded into disposable garbage bags for disposal in designated on-site containers
------------------	--	--

**10. WORK TASK SUMMARY:**

This Section summarizes information from Sections 6-9 for each site specific Task.

TASK	PPE LEVEL See section 7	MONITORING	HAZARDS See Section 6	DECONTAMINATION See Section 9
1. Sampling	D	See Section 8	A, B, E, G, H, I, J, K, L	Personnel, Equipment
2. Field Work Oversight	D	See Section 8	A, B, E, G, H, I, J, K, L	Personnel

**11. SITE EMERGENCY / CONTINGENCY PLAN:**

The following Site Emergency / Contingency Plan provide responses and contact information if an accident or injury should occur. All accidents or injuries must be reported within a 24-hour period to the Health and Safety Officer. This includes even minor cuts and abrasions. Failure to immediately report accidents and injuries sustained on the job may result in the loss of workers compensation and disability benefits. All employees reporting an accident or injury will be required to fill out an accident report form.

All on-site workers must become familiar with the provisions of this HASP and sign the attached Training and Acknowledgement section.

Should any worker observe hazards that are not addressed in this plan or that they are unprepared for, they should withdraw immediately and consult with the Health & Safety Officer before resuming work.

**SITE EMERGENCY / CONTINGENCY PLAN CONT'D:**

**FIRST AID:**

The safety of employees working around heavy/sampling equipment should be maintained at all times. In the event that an injury or accident occurs, a first aid kit must be kept on the site within a reasonable distance of personnel at all times.

Seek emergency medical attention as soon as possible when appropriate. Directions to the nearest emergency medical facility and emergency phone numbers are provided below.

**FIRE:**

Fire extinguishers are located on heavy equipment. GeoLogic personnel will be familiar with their location and operation. Emergency contact information for fire response is provided below.


**SITE SECURITY:**

The temporary fencing will be installed; however, for the purposes of this HASP, the site should be considered unsecured.

EMERGENCY CONTACT	DESCRIPTION	PHONE
Police		911
Fire Department		911
Ambulance		911
Hospital	Upstate Hospital Emergency Room	315-464-5611
Poison Control Center	Nationwide	800-222-1222

NYSDEC Spill Hotline	Spills must be reported within 2 hours of their discovery	800-457-7362
<p><b>MEDICAL EMERGENCY:</b></p> <p><b>Directions to hospital:</b></p> <p><b>Get on I-690 W in Syracuse</b></p> <p>3 min (1.6 mi)</p> <p><b>Follow I-690 W to N Townsend St. Take exit 13 from I-690 W</b></p> <p>3 min (2.9 mi)</p> <p><b>Continue on N Townsend St to your destination</b></p> <p>5 min (0.9 mi)</p> <p><b>Upstate Univ Hospital</b></p> <p>750 E Adams St, Syracuse, NY 13210</p> <p><b>EVACUATION:</b></p> <p>In the event of a situation requiring emergency evacuation of the site such as a contaminant release above the highest action levels or an underground gas line break, the following procedures should be followed:</p> <ol style="list-style-type: none"><li>1. Activate emergency stop feature on operating equipment</li><li>2. Notify all personnel of the need to leave the site immediately</li><li>3. Immediately walk up wind, if a contaminate release has occurred.</li><li>4. Contact emergency services / personnel</li></ol>		

**12. MAP TO HOSPITAL:**




**13. PLAN ACKNOWLEDGEMENT:**

Personnel authorized to work at this Site include:

TEAM MEMBER	RESPONSIBILITIES	SIGNATURE
Kenneth Teter, PE	Project Engineer	
Forrest Earl, PG	Project Geologist	
Joseph Menzel, PG	Geologist	
Christopher Gabriel	Environmental Scientist	

**14. SITE MAP:**

**General Work Area**





*APPENDIX E*

*Community Air Monitoring Plan*

## **Community Air Monitoring Program (CAMP) AOC-4, Celi Drive, BCP Site #C734108**

A Community Air Monitoring Plan (CAMP) requires real-time observation/monitoring for particulates (i.e., dust) at the downwind perimeter of each designated work area when certain activities are in progress at contaminated sites.

The CAMP is not intended for use in establishing action levels for worker respiratory protection. Rather, its intent is to provide a measure of protection for the downwind community (i.e., off-site receptors including residences and businesses and on-site workers not directly involved with the subject work activities) from potential airborne contaminant releases as a direct result of investigative and remedial work activities. Additionally, the CAMP helps to confirm that work activities did not spread contamination off-site through the air. The action levels specified herein require increased monitoring, corrective actions to abate emissions, and / or work shutdown.

Continuous monitoring will be required for all ground intrusive activities, including but not limited to, site clearing; soil and sediment excavation, handling, staging, and loading; placement of clean fill; and grading.

The prevailing wind generally blows from west to east. However, monitoring locations will be adjusted on a daily or more frequent basis based on actual wind directions to provide an upwind and at least one downwind monitoring station.

At this time, the primary chemicals of concern include the following:

Particulates (containing metals)

As the investigation progresses and soil and groundwater data is collected for these other classes of chemicals, this CAMP will be updated to reflect any new information.

Particulate concentrations will be monitored continuously at the upwind and downwind perimeters of the work area or exclusion zone at temporary particulate monitoring stations. The particulate monitoring will be performed using a DUSTTRAK™ Aerosol Monitor Model 8520 (or similar). The device will be capable of measuring particulate matter less than 10 micrometers in size (PM-10), integrating over a period of 15 minutes for comparison to the airborne particulate action level, and equipped with an audible alarm to indicate exceedance of the following action levels:

If the downwind PM-10 particulate level is 100 micrograms per cubic meter ( $\text{mcg}/\text{m}^3$ ) greater than background (upwind perimeter) for the 15-minute period or if airborne dust is observed leaving the work area, then dust suppression techniques will be employed. Work may continue with dust suppression techniques provided that downwind PM-10 particulate levels do not exceed 150  $\text{mcg}/\text{m}^3$  above the upwind level, and provided that no visible dust is migrating from the work area.

If, after implementation of dust suppression techniques, downwind PM-10 particulate levels are greater than 150 mcg/m<sup>3</sup> above the upwind level, work will be stopped and an evaluation of activities will be initiated. Work will resume provided that dust suppression measures and other controls are successful in reducing the downwind PM-10 particulate concentration to within 150 mcg/m<sup>3</sup> of the upwind level and in preventing visible dust migration.

In addition, fugitive dust migration will be visually assessed during all work activities.

All readings will be recorded and be available for NYSDEC and NYSDOH review.

CAMP data summary tables will be provided to the NYSDEC and NYSDOH on a weekly basis (at a minimum), and any exceedances of CAMP action levels and corrective measure taken will be reported to the Departments within 24 hours.

CAMP data will be provided as an attachment within the Remedial Construction Completion Report.

*APPENDIX F*

*Quality Assurance Project Plan*

# QUALITY ASSURANCE PROJECT PLAN

**AOC-4  
Celi Drive  
Town of Dewitt, New York  
NYSDEC Site No. C734108**

## INTRODUCTION

This Quality Assurance Project Plan (QAPP) addresses the Interim Remedial Measures (IRM) associated with Area of Concern 4 (AOC-4) of NYSDEC BCP Site # C734108.

This QAPP presents the quality assurance (QA) and quality control (QC) guidelines associated with the collection of data during the implementation of the IRM. This QAPP has been prepared in accordance with the USEPA requirements for QAPPs for Environmental Data Operations, the USEPA Region II CERCLA Quality Assurance Manual and NYSDEC DER-10 Technical Guidance for Site Investigation and Remediation. This document may be modified as necessary as the work progresses.

## PROJECT TEAM

The Project Team consists of the following members:

NYSDEC with NYSDOH – combined NYSDEC/NYSDOH are responsible for ensuring the work performed satisfies the regulatory requirements and that the data and documentation obtained during the remedial activities supports any conclusions they reach.

BCP Participant – the Participant is responsible for insuring this QAPP is adhered to, whether the work performed is completed by the Participant or by consultants and/or contractors hired by the Participant.

Consultant(s) and Contractor(s) – if utilized, consultants and contractors hired by the Participant are responsible for implementing the QAPP.

The Project Team Positions are:

### Project Manager

The Participant will assign a Project Manager who is responsible for ensuring the overall project goals are met. The Project manager will report directly to the Participant. Responsibilities of the Project Manger include, but are not limited to:

Developing a project schedule and communicating that schedule to the team members.

Ensuring policies and procedures are in place to ensure the project requirements are met.

Review all project documentation to ensure conformance with the QAPP.

Prepare and review all submittals to the various team members.

Work with the other team members to develop solutions to address any deficiencies or scheduling issues that occur.

Communicating on a regular basis with the team members to ensure all members are apprised as to the status of the project.

#### Field Team Leader

The Field Team Leader will report to the Project manager. The Field Team Leader will have responsibility for coordinating the day-to-day interactions between the various personnel on site and for ensuring the procedures implemented follow the requirements of the QAPP.

#### Quality Assurance Officer

The Quality Assurance Officer will review the various activities for conformance with the QAPP, regularly communicate to the Project Manager any issues or disputes that may arise, work with the Project Manager to resolve any disputes or issues, and interface with the analytical laboratory(s) to coordinate timely analysis and reporting of all analytical results.

#### Subcontractors

Subcontractor and subconsultants may be utilized for various tasks including, but not limited to: surveying, wetlands delineation, utility locating, excavating, trucking, and data validation.

Prior to the initiation of the work, a roster of the key team members will be distributed to all team members.

### **QUALITY ASSURANCE PROJECT PLAN (QAPP)**

#### **Project Description**

This QAPP includes identification of sampling locations and media; methods for collection, handling, and preservation; and the protocols to be used for sample analysis. Environmental media to be sampled is soil, sediment and surface water. The data will be utilized to form conclusions as to the presence, transport, and fate of site-specific contaminants.

#### **Field Sampling Procedures**

All sampling objectives, locations and procedures have been included as the Field Sampling Plan and described in this QAPP. Items include field measurement techniques, general field decontamination procedures, and sample acquisition and management.

### **Analytical Methodologies**

Sampling and analysis will be performed for total chromium, copper, nickel and cyanide by EPA Methods 6010, 7471 and 9014. Soil samples will also be analyzed for hexavalent chromium by EPA Method 3060A.

Analyses of these samples will be consistent with the NYSDEC ASP 2005, Category B requirements.

Trip blanks will accompany each shipment of aqueous samples. If several samples are collected for analysis on any one day, all samples will be packed in the same cooler with the trip blank. All trip blanks will be analyzed according to NYSDEC ASP (2005) protocol for metals.

Duplicate samples will be obtained from surface water and soil/sediment samples for each twenty field samples collected for both matrices. Duplicate samples will be referenced to a specific field sample location.

All data will be presented in modified Category B deliverables format.

### **Laboratory Certification and Coordination**

All chemical analyses for samples collected will be completed by a NYSDOH ELAP laboratory capable of performing project-specific analysis indicated in the attached QA/QC requirements. The project manager will be responsible for all project-related laboratory coordination.

### **Analytical Quality Control**

Analytical quality control will be consistent with the methodologies and quality assurance/quality control requirements in the NYSDEC ASP 2005. This analytical data will be subject to data usability reviews in general accordance with NYSDEC ASP Category B reportable and deliverable formats. Data Usability Summary Reports (DUSR) will be prepared in a manner consistent with NYSDEC's Guidance for Data Deliverables and Development of Data Usability Summary Reports, NYSDEC DER-10, May 2010. The main objective of a DUSR is to determine whether the data presented meets the project-specific needs for data quality and data use.

## **FIELD SAMPLING PLAN**

### **Sampling Objectives**

Field sampling at the Site has been designed to obtain representative samples of environmental media to further assess the impact that the Site may have upon human health and the environment. The field sampling plan includes sampling surface water and soil/sediment.

### **Sampling Procedures**

The following sections provide procedures for collecting soil/sediment and surface water samples.

### Preparation for Sampling

The sample collection technique is of prime importance to assure the integrity of the collected sample. The following techniques include provisions so that:

- A representative sample is obtained;
- Contamination of the sample is minimized;
- The sample is properly preserved; and
- An acceptable Chain-of-Custody record is maintained.

The QA/QC Sampling Component of the Plan includes:

- Incorporation of accepted sampling techniques referenced in the sampling plan;
- Procedures for documenting any field actions contrary to the QAPP;
- Documentation of all preliminary activities such as equipment check-out, calibrations, and container storage and preparation;
- Documentation of field measurement quality control data (quality control procedures for such measurements shall be equivalent to corresponding QC procedures);
- Documentation of field activities;
- Documentation of post-field activities including sample shipment and receipt, field team debriefing, and equipment check-in;
- Generation of quality control samples including duplicate samples and trip blanks; and
- The use of these samples in the context of data evaluation with details of the methods employed (including statistical methods) and of the criteria upon which the information generated will be judged.

The personnel responsible for collection of surface water and soil/sediment samples will be familiar with standard sampling procedures and follow the appropriate protocol. Daily field records will be maintained to document daily instrument calibration, locations sampled, field observations, and weather conditions. Each page will be dated and signed by the sampler.

Prior to sampling, all equipment must be procured and accommodations for sample container delivery, and sample shipment must be made. The following is a list of general equipment that would be on hand for sampling events. Special equipment for each sampling event is presented in the section describing that specific sampling event.

General Field Sampling Equipment:

- Project Data Information/Plans;
- Chain-of-Custody forms;
- Nitrile/Vinyl gloves;



- Bio-degradable phosphate free detergent;
- Coolers (with ice);
- Sample bottles;
- Tap water/Distilled water; and Liquinox

### Surface Water Sample Collection

Surface water samples will be collected using dedicated or disposable equipment as needed. All other related sampling equipment will be properly decontaminated in the field. Surface water samples may be obtained from standing water in the drainage ditches, water storage tanks and or containment sumps. The following equipment will be available for sampling of surface water in addition to the general sampling equipment list:

- Dedicated disposable bailers/low-flow pump with disposable tubing;
- Reusable water dippers.

The following steps describe the sample preparation and collection of surface water:

1. Obtain the sampling parameters for each location to be sampled.
2. Select the appropriate sample containers for the day's sampling.
3. Select the appropriate equipment needed to collect the sample(s).
4. Fill the appropriate sample bottles according to the sampling schedule for the location. Prior to filling the sample bottles, record the location, type, volume of container, and the preservatives used.
5. Collect the field duplicate samples. Take samples according to sampling schedule presented in the QAPP.
6. Record all pertinent information in the field logbook (include color, odor, sediment content of sample, etc.). Any situations at the Site that have the potential to interfere with the analytical results should also be recorded here.
7. Dispose of potentially contaminated materials in designated containers for Investigation-Derived Waste (IDW).

### Soil Sampling

1. Each soil sample will be a composite of three (3) individual locations.
2. Soil for the sample will be collected from six (6) inches deep into the soil using a shovel or a trowel.
3. The shovel will be washed with Liquinox and a tap water rinse water between each composite sample collection.
4. The equal amounts of soil by volume will be collected from the three (3) locations and placed into a baggie and mixed by homogenizing the baggie.

5. Each composited sample will then be placed into the appropriate sample jar(s).

### **General Decontamination**

The following procedures will be performed for the decontamination of exploration equipment, and sampling equipment after each sampling event:

Reusable Equipment – The following steps will be employed to decontaminate reusable equipment:

- Rinse equipment of soil or foreign material with potable water;
- Immerse and scrub equipment with bio-degradable phosphate-free detergent (Liquinox) and potable water;
- Immerse and scrub in a potable water rinse without detergent.

Sample Containers – Upon filling and capping sample bottles, the outside of the bottle will be wiped off with a clean paper towel. These towels will be disposed of in a dedicated container for contaminated solids.

Personnel Decontamination – The following procedures will be used to decontaminate sampling personnel:

- After each sampling event chemical-resistant gloves will be disposed of in a dedicated container for contaminated solids;
- At the end of each sampling day, Tyvek™ coveralls, if used, will be disposed of in a dedicated container for contaminated solids;
- Personnel will be required to follow procedures outlined in the Health and Safety Plan.

### **Sample Management Plan**

The Sample Management Plan provides procedures to document and track samples and results obtained during this work effort. A series of pre-printed forms with the appropriate information serves as a vehicle for documentation and tracking. In order to accomplish this task, the documentation materials will include sample labels, sample characterization and Chain-of-Custody sheets, daily field reports, and a sample log.

Sample Label – A sample label will be completed for each sample obtained and will be affixed to the sample container. The label is configured in a way to address various types of mediums. Information on the label includes, at a minimum, client name, location, sample description, sample number, date, time, grab sample, composite sample, notes, and sampler's name.

Sample Characterization & Chain-of-Custody Sheet – All pertinent field information will be entered into the field book and chain-of-custody (COC) sheets. The COC sheets will include client name, sample ID, sample description, location of sample, number of containers, container type, analysis required, and preservation. The COC section of the form will document the sample's pathway of sample shipment, which will include names of persons delivering/receiving, dates, and times. Copies of the completed forms will be retained by the consultant and the analytical laboratory. Chain-of-Custody sheets will be included in the laboratory data package submittal.

Sample Designation – Each sample will have a unique sample code that will include, where appropriate, the sample media, and the sample location.

Sample Handling – Each collected sample will be dispensed into the appropriate sample containers for the type of analysis to be performed. Appropriate sample preservatives will be added to the sample containers by the contracted analytical laboratory prior to the delivery into the field, except in cases where the sample preservative must be added after sample collection. All samples that require cool storage will be immediately placed in coolers with appropriate packaging materials so as to protect the breakage of sample containers during shipment. The sample coolers will be filled with cubed ice prior to leaving the sample collection location. Careful packaging techniques will be used to prevent sample containers from breakage during shipment. Materials such as cardboard, foam wrap, or Styrofoam may be used as packaging materials. All samples will be either hand-delivered to the contracted analytical laboratory or arrangement for pick-up by the laboratory will be made.

### **Imported Fill Material (Topsoil and Granular Fill)**

Samples of materials proposed for import and use as fill material will be analyzed for the parameters listed below.

TCL VOCs USEPA Method 8260B + TICS

TCL SVOCs USEPA Method 8270C +TICS

TAL Metals USEPA Method 6010, 7470/7471 (Hg), 9014 (CN)

PCB Aroclors USEPA Method 8082

Herbicides USEPA Method 8151

Pesticides USEPA Method 8081

1,4-Dioxane USEPA Methods 8270SIM (soil) and 522 (groundwater)

PFAS NYSDOH Method 537 (Modified) – Groundwater Only

The number of samples analyzed will be consistent with the requirements of DER-10.