

Syracuse Label Company, Inc.

110 Luther Avenue BCP Site (BCP Site #C734118)

Periodic Review Report - Jan. 2012 - Jun. 2013

July 2013

Executive Summary

The 110 Luther Avenue Brownfield Cleanup Program (BCP) Site (BCP Site #C734118) consists of approximately 1.40-acres of land located at 110 Luther Avenue, Town of Salina, Onondaga County, New York. The Site owner is Syracuse Label Company, Inc. (Syracuse Label). The Site groundwater was found to be contaminated with volatile organic compounds (VOCs), primarily tetrachloroethene (PCE) and its degradation byproducts, trichloroethene (TCE), dichloroethene (DCE) and vinyl chloride (VC). The Site was remediated to commercial use cleanup standards and received a Certificate of Completion (COC) from the New York State Department of Environmental Conservation (NYSDEC) on December 22, 2011.

The Site is currently in the monitoring stage, and groundwater samples are collected from Site monitoring wells on a quarterly basis. Based on the data, concentrations of target compounds in groundwater have shown a general decrease over time, with the exception of samples taken from groundwater monitoring well MW-13.

Based on a review of quarterly groundwater monitoring results, and discussions with the NYSDEC, Syracuse Label implemented corrective measures to address the elevated concentrations of degradation byproducts identified in Site groundwater monitoring wells and the increasing trend in concentrations of target compounds in groundwater monitoring well MW-13. Implementation of corrective measures was begun on February 25, 2013 and completed on June 18, 2013. The effectiveness of the corrective measures will be monitored quarterly as part of the ongoing groundwater monitoring program.

The institutional controls and engineering controls for the Site remain in place and effective for protecting human health and the environment. The sub-slab depressurization system (SSDS) engineering control is inspected monthly by Syracuse Label and the system has been operating as planned. The soil cover engineering controls remain in place. Groundwater monitoring has been completed in accordance with the Site Management Plan (SMP), which identified the need for quarterly groundwater monitoring.

There is no need to revise the SMP or propose a change to the frequency of PRR submittals at this time. Groundwater will continue to be monitored on a quarterly basis in accordance with the SMP. The requirements necessary to discontinue Site monitoring have not been met at this time.

Table of contents

1.	Introduction	3
1.1	Purpose	3
1.2	Certification Period	3
1.3	Scope and Limitations	3
2.	Site Overview	5
2.1	Background	5
3.	Institutional and Engineering Controls	7
3.1	Institutional Controls	7
3.2	Engineering Controls	7
4.	Operations and Monitoring	9
4.1	Corrective Measures	11
5.	Recommendations	12

Table index

Table 1 – Groundwater Elevation Data
Table 2 – Summary of Groundwater Analytical Results

Figure index

Figure 1 – Site Location Map
Figure 2 – Site Layout
Figure 3 – Groundwater Monitoring Results
Figure 4 – Sub-Slab Depressurization System Layout
Figure 5 – Soil Cover Engineering Controls
Figure 6 – Corrective Measures Injection Array

Appendices

Appendix A - Institutional and Engineering Controls Certification Form
Appendix B - Property Ownership Information for Adjoining Property
Appendix C - Sub-Slab Depressurization System Inspection Checklists
Appendix D - Approval Notifications for EQuIS Database Submittals

1. Introduction

1.1 Purpose

This Periodic Review Report (PRR) is being submitted on behalf of Syracuse Label Company, Inc. (Syracuse Label) for the 110 Luther Avenue Brownfield Cleanup Program (BCP) Site (BCP Site No. C734118) located at 110 Luther Avenue, Liverpool, New York (Figure 1). The purpose of this PRR, and attached documents, is to document that institutional and engineering controls, as described in the New York State Department of Environmental Conservation (NYSDEC)-approved Site Management Plan (SMP) and Environmental Easement, are in place in accordance with 6NYCRR Part 375-3. The following elements are included in this report:

- A complete description of all institutional and/or engineering controls employed at the Site;
- An evaluation of the plans developed for implementation of the engineering and institutional controls, regarding the continued effectiveness of any institutional and/or engineering controls required by the decision document for the Site;
- A certification prepared by a professional engineer or qualified environmental professional that the institutional controls and/or engineering controls employed at the Site during the period are:
 - Unchanged from the previous certification, unless approved by the Department, consistent with the SMP;
 - In place and effective;
 - Performing as designed, and that nothing has occurred that would (1) impair the ability of the controls to protect public health and environment, or (2) constitute a violation or failure to comply with any operation and maintenance plan for such controls;
- The institutional and engineering controls certification form as issued by the Department has been completed and included as Appendix A;
- Data tables and figures depicting results of quarterly groundwater monitoring activities conducted on-Site; and
- Information related to ongoing remedial action.

1.2 Certification Period

This Periodic Review Report (PRR) is the initial PRR and discusses maintenance and monitoring activities for the period between January 1, 2012 and June 30, 2013, which is the 18-month period following issuance of the Certificate of Completion. During this period, Syracuse Label performed regular inspections of the engineering controls on-Site, including the sub-slab depressurization system (SSDS) and soil covers.

1.3 Scope and Limitations

This report: has been prepared by GHD for Syracuse Label Company, Inc. and may only be used and relied on by Syracuse Label Company, Inc. for the purpose agreed between GHD and the Syracuse Label Company, Inc. as set out in section 1.1 of this report.

GHD otherwise disclaims responsibility to any person other than Syracuse Label Company, Inc. arising in connection with this report. GHD also excludes implied warranties and conditions, to the extent legally permissible.

The services undertaken by GHD in connection with preparing this report were limited to those specifically detailed in the report and are subject to the scope limitations set out in the report.

The opinions, conclusions and any recommendations in this report are based on conditions encountered and information reviewed at the date of preparation of the report. GHD has no responsibility or obligation to update this report to account for events or changes occurring subsequent to the date that the report was prepared.

The opinions, conclusions and any recommendations in this report are based on assumptions made by GHD described in this report. GHD disclaims liability arising from any of the assumptions being incorrect.

GHD has prepared this report on the basis of information provided by Syracuse Label Company, Inc. and others who provided information to GHD (including Government authorities), which GHD has not independently verified or checked beyond the agreed scope of work. GHD does not accept liability in connection with such unverified information, including errors and omissions in the report which were caused by errors or omissions in that information.

The opinions, conclusions and any recommendations in this report are based on information obtained from, and testing undertaken at or in connection with, specific sample points. Site conditions at other parts of the Site may be different from the Site conditions found at the specific sample points.

Investigations undertaken in respect of this report are constrained by the particular Site conditions, such as the location of buildings, services and vegetation. As a result, not all relevant Site features and conditions may have been identified in this report.

Site conditions (including the presence of hazardous substances and/or Site contamination) may change after the date of this Report. GHD does not accept responsibility arising from, or in connection with, any change to the Site conditions. GHD is also not responsible for updating this report if the Site conditions change.

2. Site Overview

2.1 Background

The Site is located in the Town of Salina, Onondaga County, New York and is identified as Block 12 and Lots 04.1, 05.0, 06.1, 08.0, and 09.0 on the Onondaga County Tax Map (Tax Map No. 85-12). The Site is approximately 1.40-acres of land bounded by Albion Avenue to the northwest, Knapp Street to the northeast, Luther Avenue and a parcel operated by Brannock Devices Company, Inc. to the southeast, and an unpaved parking area operated by Bush Electronics to the southwest (see Figure 2).

The Site is currently developed with a two story building used for office space, light manufacturing, and warehouse operations. The portion of the Site not occupied by the building consists of paved parking and delivery areas, with minor landscaping areas.

The Remedial Investigation (RI), which was conducted under Brownfield Cleanup Agreement (BCA Index #B7-0811-09-08) between December 2009 and November 2010, characterized the nature and extent of contamination at the Site. The results of the RI, as reported in the RI Report (S&W Redevelopment of North America, LLC (SWRNA), January 2011, Revised: June 2011) determined that groundwater contamination, consisting of chlorinated volatile organic solvents (tetrachloroethene, trichloroethene, and their degradation products), existed in a discrete area located in the eastern/central portion of the Site (Figure 3). This area of the Site corresponds to the location of a historic floor trench drain.

A Remedial Action Work Plan (RAWP) was prepared by SWRNA (June 2011, Revised: September 2011), which:

- identified the remedial goals and remedial action objectives;
- discussed the remedy selection;
- summarized remedial action pilot test findings;
- summarized the sub-slab communication testing findings; and
- outlined the remedial design for the proposed remedial approach.

The proposed remedial approach was to remediate the Site to a Track 4 Restricted Use by meeting the Commercial Use Soil Cleanup Objectives (SCOs). This remediation approach included implementation of a groundwater remedy and engineering/institutional controls. The groundwater remedy included in-situ chemical reduction (ISCR), which consisted of injection of 11,100 pounds of a granular carbon and zero valent iron powder mixed into a slurry and 12 liters of a bacterial consortium (*Dehalococcoides*). The groundwater remedy was completed in a discrete area of the Site between February 2011 (pilot test) and July 2011 (full scale). The engineering controls consisted of maintaining the soil cover system and installing a sub-slab depressurization system (SSDS) in the existing on-Site building. The institutional controls included a Site groundwater use restriction, a Site use restriction restricting the use to Commercial or Industrial uses, and the requirement that a SSDS will be installed in any future buildings constructed on-Site.

An Environmental Easement (EE) for the Site was filed with the Onondaga County Clerk's Office on October 21, 2011. A Site Management Plan, which outlines Site restrictions and requirements of future maintenance and monitoring, was completed in November 2011. A Certificate of Completion

(COC) allowing for commercial or industrial uses of the Site was received from the NYSDEC on December 22, 2011.

The reader of this PRR may refer to previous reports for more detail, as needed. These reports include:

- *Remedial Investigation*, Brownfield Cleanup Program, 110 Luther Avenue Site, 110 Luther Avenue, Liverpool, Onondaga County, New York, BCP Site #C734118, S&W Redevelopment of North America, LLC, January 2011, Revised: June 2011.
- *Remedial Action Work Plan*, Brownfield Cleanup Program, 110 Luther Avenue Brownfield Site, 110 Luther Avenue, Liverpool, Onondaga County, New York, S&W Redevelopment of North America, LLC, June 2011, Revised: September 2011.
- *Site Management Plan*, 110 Luther Avenue Site, Onondaga County, New York, NYSDEC Site Number: C734118, S&W Redevelopment of North America, LLC, August 2011, Revised: November 2011.
- *Final Engineering Report*, 110 Luther Avenue Site, Onondaga County, New York, NYSDEC Site Number: C734118, S&W Redevelopment of North America, LLC, September 2011, Revised: November 2011.

3. Institutional and Engineering Controls

Based on identified groundwater contamination, potential soil vapor contamination, and the Site's past and present use, institutional and engineering controls are utilized at the Site to limit exposure risks. These institutional and engineering controls are described below.

3.1 Institutional Controls

The institutional controls (ICs) for this Site are outlined in the NYSDEC-approved SMP (SWRNA, August 2011, Revised: November 2011), and include the following:

- An Environmental Easement filed with the Onondaga County Clerk's Office;
- A restriction on the use of groundwater without prior approval by NYSDEC;
- An Excavation Work Plan providing guidance for future excavations conducted on-Site;
- A use restriction limiting future Site use to commercial or industrial use without prior approval of the NYSDEC; and
- Monitoring for ownership changes of adjacent property (116 Luther Avenue - Tax Identification 085.-12-10.0).

3.1.1 Groundwater

Groundwater is not being used at the Site.

3.1.2 Excavations

No excavations have occurred on-Site during the certification period.

3.1.3 Site Use

The Site use has not changed since the NYSDEC has issued the Certificate of Completion (COC).

3.1.4 Ownership of Adjacent Property

Based on information from the Onondaga County Real Property Tax Services website (<http://www.ongov.net/rpts/propertyTaxInfo.html>), the adjacent property located to the south of Syracuse Label has been owned by Salvatore A. Leonardi, Junior since 1995. Based on field observations, the property has been, and continues to be, operated as Brannock Devices Company, Inc. (Appendix B).

3.2 Engineering Controls

The engineering controls (ECs) for this Site are outlined in the NYSDEC-approved SMP (SWRNA, August 2011, Revised: November 2011), and include the following:

3.2.1 Sub-Slab Depressurization System

A sub-slab depressurization system (SSDS) was installed in the existing Site building in July 2011 by Radon Home Services, Inc. a certified radon mitigation contractor. The SSDS is a high vacuum system utilizing fourteen (14) suction points positioned at locations throughout the building (Figure 4). The system is designed to operate continuously to create a negative pressure beneath the

building slab in order to preclude potential soil vapor intrusion issues. The extracted soil vapor is vented to the atmosphere.

System inspection forms, completed by Syracuse Label personnel monthly during the certification period, indicate that the system was operating continuously and that there was no need for repairs or maintenance (Appendix C).

Additional information can be found in the Institutional and Engineering Controls Certification Form (Appendix A).

3.2.2 Soil Cover Engineering Control

Direct contact with soil/fill at the Site is mitigated by a soil cover system in place over the entirety of the Site. This soil cover system is comprised of existing asphalt pavement, existing concrete building slabs, and existing grassed areas. The location of the soil cover system is depicted in Figure 5.

The soil cover system was in place for the duration of the certification period and no maintenance was required to amend the soil cover system.

Additional information can be found in the Institutional and Engineering Controls Certification Form (Appendix A).

4. Operations and Monitoring

The NYSDEC-approved SMP (SWRNA, August 2011, Revised: November 2011) requires quarterly monitoring and reporting to demonstrate groundwater remedy effectiveness (Figure 2 and Tables 1, and 2). The quarterly monitoring is intended to assess the performance of the remedy and overall reduction in contamination on-Site. The laboratory sample results were transmitted to the NYSDEC on:

- May 11, 2012 (1st Quarter 2012 sampling);
- July 24, 2012 (2nd Quarter 2012 sampling);
- October 5, 2012 (3rd Quarter 2012 sampling);
- January 18, 2013 (4th Quarter 2012 sampling); and
- July 2, 2013 (1st Quarter 2013 sampling).

The 2nd Quarter 2013 groundwater monitoring event was conducted on June 27 and 28, 2013. As a result, the data from this groundwater monitoring event was not received prior to completing this PRR and will be included in the next PRR (June 2014).

Based on the data, concentrations of target compounds in groundwater have shown a decrease over time, with several samples from monitoring wells at non-detect (ND) concentrations for PCE and TCE. The exception is samples taken from groundwater monitoring well MW-13, as shown in the summary tables below.

- MW-7:

Target Compounds	Baseline Concentration (February 2010)	Current Concentration (March 2013)
Tetrachloroethene (PCE)	27,000 micrograms per liter (ug/L)	ND (Laboratory detection limit (LDL) of 140 ug/L)
Trichloroethene (TCE)	4,300 ug/L	ND (LDL of 180 ug/L)
cis-1,2-dichloroethene (cis-DCE)	2,600 ug/L	18,000 ug/L
trans-1,2-dichloroethene (trans-DCE)	Non-Detect (ND)	ND (LDL of 360 ug/L)
Vinyl chloride (VC)	260 ug/L	7,900 ug/L

- MW-8:

Target Compounds	Baseline Concentration (February 2010)	Current Concentration (March 2013)
Tetrachloroethene (PCE)	3,900 ug/L	800 ug/L
Trichloroethene (TCE)	860 ug/L	380 ug/L
cis-1,2-dichloroethene (cis-DCE)	2,500 ug/L	9,400 ug/L
trans-1,2-dichloroethene (trans-DCE)	ND (LDL of 15 ug/L)	ND (LDL of 180 ug/L)
Vinyl chloride (VC)	250 ug/L	4,300 ug/L

- MW-11:

Target Compounds	Baseline Concentration (February 2011)	Current Concentration (March 2013)
Tetrachloroethene (PCE)	42,000 ug/L	ND (LDL of 290 ug/L)
Trichloroethene (TCE)	6,300 ug/L	ND (LDL of 370 ug/L)
cis-1,2-dichloroethene (cis-DCE)	3,800 ug/L	37,000 ug/L
trans-1,2-dichloroethene (trans-DCE)	ND (LDL of 380 ug/L)	ND (LDL of 720 ug/L)
Vinyl chloride (VC)	ND (LDL of 500 ug/L)	4,900 ug/L

- MW-12:

Target Compounds	Baseline Concentration (February 2010)	Current Concentration (March 2013)
Tetrachloroethene (PCE)	220 ug/L	ND (LDL of 1.8 ug/L)
Trichloroethene (TCE)	79 ug/L	ND (LDL of 2.3 ug/L)
cis-1,2-dichloroethene (cis-DCE)	670 ug/L	93 ug/L
trans-1,2-dichloroethene (trans-DCE)	ND (LDL of 3.8 ug/L)	ND (LDL of 4.5 ug/L)
Vinyl chloride (VC)	18 ug/L	4.9 ug/L

- MW-13:

Target Compounds	Baseline Concentration (February 2010)	Current Concentration (March 2013)
Tetrachloroethene (PCE)	410 ug/L	4,600 ug/L
Trichloroethene (TCE)	600 ug/L	2,500 ug/L
cis-1,2-dichloroethene (cis-DCE)	780 ug/L	9,600 ug/L
trans-1,2-dichloroethene (trans-DCE)	12 ug/L	ND (LDL of 90 ug/L)
Vinyl chloride (VC)	29 ug/L	500 ug/L

- MW-17:

Target Compounds	Baseline Concentration (February 2010)	Current Concentration (March 2013)
Tetrachloroethene (PCE)	14,000 ug/L	ND (LDL of 3.6 ug/L)
Trichloroethene (TCE)	2,000 ug/L	ND (LDL of 4.6 ug/L)
cis-1,2-dichloroethene (cis-DCE)	750 ug/L	570 ug/L
trans-1,2-dichloroethene (trans-DCE)	ND (LDL of 76 ug/L)	ND (LDL of 9.0 ug/L)
Vinyl chloride (VC)	ND (LDL of 99 ug/L)	410 ug/L

Concentrations of cis-DCE and VC showed a sharp increase in most wells sampled following implementation of the pre-COC groundwater remedy (Table 2). The increases observed for cis-DCE and VC were expected as a result of the groundwater remediation efforts, which are degrading PCE and TCE into cis-DCE and VC. The concentrations of cis-DCE and VC have shown a decreasing trend, which is expected to continue over time as degradation continues (Table 2).

Groundwater sampling results for each quarterly sampling event were uploaded into the NYSDEC EQuIS Database, approved by the EQuIS Team, and are ready for use (Appendix D).

4.1 Corrective Measures

Based on a review of quarterly groundwater monitoring results, and discussions with the NYSDEC, Syracuse Label implemented corrective measures to address the elevated concentrations of degradation byproducts (cis-DCE and VC) identified in Site groundwater monitoring wells as a result of the degradation of PCE and TCE in groundwater and the increasing trend in concentrations of target compounds (PCE and TCE) in groundwater monitoring well MW-13.


The corrective measures, which included additional carbon and zero valent iron slurry and bacterial consortium injection, were begun on February 25, 2013 and completed on June 18, 2013. The corrective measures injections were completed in areas within the building around MW-12, the trench drain area (around wells MW-7, MW-11, and MW-17), and the area between MW-1 and MW-10 outside of the building (Figure 6). Implementation of the corrective measures will be reported in a separate Corrective Measures Report, and as a result are not discussed further here.

5. Recommendations

Based on a review of the quarterly groundwater data, it is recommended that the ICs and ECs currently in place for the Site remain in place in order to ensure the continued effectiveness and protectiveness of the remedy. Groundwater monitoring should continue to be conducted on a quarterly basis. The effectiveness of the remedy should continue to be evaluated through quarterly groundwater monitoring results.



A Corrective Measures Report documenting the corrective measures implemented during the first and second quarters of 2013 will be prepared and submitted to the NYSDEC and New York State Department of Health (NYSDOH) for review and comment.

Figures



Contour Interval: 10 Feet


Map Taken From: USGS 7.5 Minute Series
 Topographic Quadrangle;
 Syracuse West (1975, photorevised 1978)
 (www.nysgis.state.ny.us/quads/usgsdrg.htm)






Syracuse Label Company, Inc
 Periodic Review Report - Jan. 2012 - Jun. 2013
 BCP Site # C734118
 Site Location Map

Job Number 86-14941.06
 Revision A
 Date June 2013

Figure 1



LEGEND:

-  GROUNDWATER MONITORING WELL LOCATION AND ID
-  SOIL VAPOR MONITORING WELL LOCATION AND ID
-  BCP SITE BOUNDARY (APPROXIMATE)



NOTES:


- GROUNDWATER MONITORING WELLS SAMPLED FOR IN-SITU CHEMICAL REDUCTION (ISCR) EFFECTIVENESS MONITORING INCLUDE MW-2, MW-7, MW-8, MW-11, MW-12, MW-13, AND MW-17.
- GROUNDWATER MONITORING WELLS SAMPLED FOR SITE MONITORING INCLUDE MW-1, MW-10, MW-18, AND MW-19.



Syracuse Label Company, Inc.
 Periodic Review Report - Jan. 2012 - Jun. 2013
 BCP Site #C734118
 Site Layout

NOTES:
 1. SITE FEATURES BASED ON SITE SURVEY BY INUZI & ROMANS, P.C. MARCH 2010 AND NOVEMBER 2010.









NOTES:
1. ONLY POST CERTIFICATE OF COMPLETION (COC) INJECTION POINTS ARE SHOWN ON THIS FIGURE. IB-1 THROUGH IB-30 AND INB-1 THROUGH INB-6 WERE COMPLETED DURING THE INITIAL REMEDIAL ACTION PRIOR TO THE ISSUANCE OF THE COC.
2. SITE FEATURES BASED ON SITE SURVEY BY IANUZI & ROMANS, P.C. MARCH 2010 AND NOVEMBER 2010.

Corrective Measures Injection Array

Figure 6

One Remington Park Drive, Cazenovia NY 13035 USA **T** 1 315 679 5800 **F** 1 315 679 5801 **E** cazmail@qhd.com **W** www.qhd.com

Plot Date: 9 July 2013 - 1:24 PM
Cad File No: G:\06\149\41\PRR - Jan 2012 to June 2013\Figures\86-14941_06-L6.cadd.dwg

Plot Date: 9 July 2013 - 1:24 PM

Tables



110 LUTHER AVENUE BCP SITE (BCP SITE #C734118)

PERIODIC REVIEW REPORT

TABLE 1: GROUNDWATER ELEVATION DATA

PAGE 1 OF 2

Monitoring Well I.D.	Date	Reference Point	Reference Elevation (feet)	DTW (feet)	DOW (feet)	Water Elevation (feet)	Volume (gal)
MW-1	9/22/2011	Top of PVC	97.75	2.10	11.11	95.65	0.36
	3/29/2012			2.32	11.11	95.43	0.35
	12/20/2012			2.41	11.11	95.34	0.35
	3/28/2013			2.45	11.11	95.30	0.35
MW-2	6/23/2011	Top of PVC	100.38	3.02	9.90	97.36	0.28
	8/29/2011			2.37	11.17	98.01	0.35
	9/22/2011			2.82	11.17	97.56	0.33
	3/29/2012			3.10	11.90	97.28	0.35
	6/28/2012			3.39	11.90	96.99	0.34
	9/13/2012			3.45	11.90	96.93	0.34
	12/19/2012			3.16	11.90	97.22	0.35
	3/28/2013			3.06	11.90	97.32	0.35
MW-3	12/19/2012	Top of PVC	100.21	2.15	NM	98.06	NM
	3/28/2013			2.22	NM	97.99	NM
MW-4	12/19/2012	Top of PVC	99.22	NM	NM	NM	NM
MW-5	12/19/2012	Top of PVC	99.65	2.28	NM	97.37	NM
	3/28/2013			2.32	NM	97.33	NM
MW-6	12/19/2012	Top of PVC	97.49	NM	NM	NM	NM
MW-7	6/23/2011	Top of PVC	97.28	2.73	15.80	94.55	2.09
	8/30/2011			2.31	15.71	94.97	2.14
	9/22/2011			3.35	15.71	93.93	1.98
	3/29/2012			3.04	15.79	94.24	2.04
	6/28/2012			2.95	15.79	94.33	2.05
	9/13/2012			4.89	15.79	92.39	1.74
	12/21/2012			2.92	15.79	94.36	2.06
	3/28/2013			3.35	16.29	93.93	2.07
MW-8	6/23/2011	Top of PVC	97.38	2.50	17.05	94.88	2.33
	8/30/2011			2.50	17.05	94.88	2.33
	9/22/2011			2.46	17.05	94.92	2.33
	3/30/2012			2.51	17.06	94.87	2.33
	6/28/2012			2.76	17.06	94.62	2.29
	9/13/2012			2.90	17.06	94.48	2.27
	12/21/2012			2.41	17.06	94.97	2.34
	3/28/2013			2.37	17.26	95.01	2.38
MW-9	12/19/2012	Top of PVC	97.14	NM	NM	NM	NM
MW-10	9/22/2011	Top of PVC	97.34	2.60	11.82	94.74	1.48
	3/29/2012			2.64	11.82	94.70	1.47
	12/21/2012			2.63	11.82	94.71	1.47
	3/28/2013			2.49	11.82	94.85	1.49

DTW - Depth to water
DOW - Depth of well
NM - Not measured



110 LUTHER AVENUE BCP SITE (BCP SITE #C734118)

PERIODIC REVIEW REPORT

TABLE 1: GROUNDWATER ELEVATION DATA

PAGE 2 OF 2

Monitoring Well I.D.	Date	Reference Point	Reference Elevation (feet)	DTW (feet)	DOW (feet)	Water Elevation (feet)	Volume (gal)
MW-11	6/23/2011	Top of PVC	97.89	2.51	14.30	95.38	0.47
	8/29/2011			2.48	14.34	95.41	0.47
	9/22/2011			4.22	14.34	93.67	0.40
	3/29/2012			2.43	14.35	95.46	0.48
	6/28/2012			2.81	14.35	95.08	0.46
	9/13/2012			3.28	14.35	94.61	0.44
	12/19/2012			2.67	14.35	95.22	0.47
	3/28/2013			2.23	14.35	95.66	0.48
MW-12	6/23/2011	Top of PVC	98.02	2.27	15.60	95.75	0.53
	8/29/2011			2.12	15.60	95.90	0.54
	9/22/2011			2.32	15.60	95.70	0.53
	3/29/2012			2.16	15.61	95.86	0.54
	6/28/2012			2.05	15.61	95.97	0.54
	9/13/2012			3.08	15.61	94.94	0.50
	12/19/2012			2.25	15.60	95.77	0.53
	3/28/2013			2.00	15.60	96.02	0.54
MW-13	6/23/2011	Top of PVC	97.98	2.70	12.30	95.28	0.38
	8/29/2011			2.62	12.36	95.36	0.39
	9/22/2011			4.41	12.36	93.57	0.32
	3/29/2012			2.59	12.41	95.39	0.39
	6/28/2012			2.93	12.41	95.05	0.38
	9/13/2012			3.36	12.41	94.62	0.36
	12/19/2012			2.85	12.41	95.13	0.38
	3/28/2013			2.42	12.41	95.56	0.40
MW-14	12/19/2012	Top of PVC	100.40	3.89	NM	96.51	NM
	3/28/2013			3.55	NM	96.85	NM
MW-15	12/19/2012	Top of PVC	98.13	1.62	11.91	96.51	0.41
	3/28/2013			1.38	11.91	96.75	0.42
MW-16	12/19/2012	Top of PVC	97.80	2.27	12.11	95.53	0.39
	3/28/2013			1.80	12.11	96.00	0.41
MW-17	6/23/2011	Top of PVC	97.89	2.05	13.00	95.84	1.75
	8/29/2011			1.95	12.60	95.94	1.70
	9/22/2011			3.72	12.60	94.17	1.42
	3/29/2012			1.95	12.52	95.94	1.69
	6/28/2012			2.33	12.52	95.56	1.63
	9/13/2012			2.86	12.52	95.03	1.55
	12/19/2012			2.15	12.52	95.74	1.66
	3/28/2013			1.73	12.52	96.16	1.73
MW-18	9/22/2011	Top of PVC	96.86	4.19	12.61	92.67	1.35
	3/29/2012			2.44	12.61	94.42	1.63
	12/20/2012			2.36	12.58	94.50	1.64
MW-19	9/22/2011	Top of PVC	97.14	4.26	13.11	92.88	1.42
	3/29/2012			2.52	13.11	94.62	1.69
	12/20/2012			2.35	13.10	94.79	1.72

DTW - Depth to water
DOW - Depth of well
NM - Not measured



110 LUTHER AVENUE BCP SITE (BCP SITE #C734118)

PERIODIC REVIEW REPORT

TABLE 2: SUMMARY OF GROUNDWATER ANALYTICAL RESULTS
PAGE 1 OF 21

Analyte	GW Std ^a (ug/L)	MW-1											
		Feb-10			Sep-11			Mar-12			Dec-12		
VOCs by EPA Method 8260B													
Tetrachloroethene	5	60	D.L.	72	D.L.	45	0.36	1	1	25	0.36	1	1
Trichloroethene	5	39	34	19	1.6	1	1	1	1	21	0.46	1	1
dis-1,2-dichloroethene	5	150	110	100	0.46	2	2	0.81	1	78	0.81	1	1
trans-1,2-dichloroethene	5	0.91	J	0.76	U	0.90	1	1	1	U	0.90	1	1
Vinyl chloride	2	33	12	29	0.90	1	1	0.90	1	25	0.90	1	1
EPA Method RSK-175													
Ethane		NS	U	4	3	0.49	1.5	1	U	0.49	7.5	1	1
Ethylene		NS	U	3	1.3	J	0.52	1.5	1	U	0.52	7	1
Methane		NS	290	1,700	22	100	100	270	2.2	40	10		
EPA Method 6010B (total)													
Calcium		229,000	928,000	334,000	B	100	500	1	110,000	100	500	1	1
Iron	300	5,140	186,000	41,100	19	50	1	8,300	19	50	1	1	1
Magnesium	35,000	64,200	296,000	94,900	43	200	1	25,400	43	200	1	1	1
Manganese	300	4,820	7,180	4,100	B	0.4	3	1	2,000	0.4	3	1	1
EPA Method 6010B (dissolved)													
Iron	300	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS
EPA Method 300													
Nitrate as N	10,000	NS	U	33	U	11	50	1	39	J	11	50	1
Sulfate	250,000	NS	48,700.0	25,200	1,700	10,000	5	22,300	700	4,000	2	1	1
Chloride	250,000	NS	1,270,000	972,000	5,600	10,000	20	521,000	5,600	10,000	20	1	1
EPA Method SM5310C													
Dissolved Organic Carbon - Quad		NS	U	230	U	430	1,000	1	5,700	430	1,000	1	1
Total Organic Carbon - Quad		NS	U	230	U	430	1,000	1	3,500	430	1,000	1	1
EPA Method 2320B													
Alkalinity		NS	353,000	B	327,000	790	5,000	1	380,000	790	5,000	1	1
EPA Method SM2340B													
Hardness as Calcium Carbonate		NS	3,540,000	1,220,000	100	500	1	379,000	100	500	1	1	1
EPA Method SM5210B													
Biochemical Oxygen Demand		NS	U	650	U	2,000	2,000	1	4,800	2,000	2,000	1	1

NOTES:

All values reported as µg/L (parts per billion)

Bold and heavy outlined cells indicate and exceedance of applicable groundwater standard or guidance value

U – Analyzed for but not detected above laboratory detection limits

J – Indicates an estimated value

H – Sample was prepped or analyzed beyond the specified holding time

B – Analyte detected in the associated laboratory blank

b – Result detected in the USB

NS – Not sampled

NA – Not analyzed for

D.L. – Laboratory detection limit

R.L. – Laboratory reporting limit

D.F. – Laboratory dilution factor

* - Reported as 1,2-Dichloroethene. Total is previous laboratory reports

Feb-11, Mar-11, and Apr-11 data represents pilot test baseline, 1st post-pilot test sampling event, and 2nd post-pilot test sampling event, respectively

Jun-11, Aug-11, and Sep-11 data represents full scale ISCR injection baseline, 1st post-ISCR sampling event, and 2nd post-ISCR sampling event, respectively

^a - GW Std – Class GA Groundwater Quality Standard or Guidance Value from New York State Department of Environmental Conservation (NYSDEC) Division of Water

Technical and Operational Guidance Series (June 1998).



110 LUTHER AVENUE BCP SITE (BCP SITE #C734118)
PERIODIC REVIEW REPORT
TABLE 2: SUMMARY OF GROUNDWATER ANALYTICAL RESULTS
PAGE 2 OF 21

Analyte	GW Std ^a (ug/L)	MW-2				
		Dec-07	Feb-10	Jun-11	Aug-11	Sep-11
VOCs by EPA Method 8260B						
Tetrachloroethene	5	D.L. 1	22	D.L. 0.81	R 0.81	D.L. 0.81
Trichloroethene	5	NS	1.2	U 0.81	R 0.62	R 0.62
cis-1,2-dichloroethene	5	NS	U 0.99	U 0.62	R 0.99	R 0.99
trans-1,2-dichloroethene	5	NS	U 0.76	U 0.99	R 0.76	R 0.76
Vinyl chloride	2	NS	U 0.99	U 0.99	R 0.99	R 0.99
EPA Method RSK-175						
Ethane		NS	NS	U 4	U 4	U 4
Ethylene		NS	NS	U 3	U 3	U 3
Methane		NS	NS	U 2	9.3	14
EPA Method 6010B (total)						
Calcium		NS	NS	279,000	999,000	310,000
Iron	300	NS	NS	18,500	138,000	27,100
Magnesium	35,000	NS	NS	80,700	309,000	87,300
Manganese	300	NS	NS	1,370	5,090	1,110
EPA Method 6010B (dissolved)						
Iron	300	NS	NS	NS	NS	NS
EPA Method 300						
Nitrate as N	10,000	NS	NS	U 33	120	54
Sulfate	250,000	NS	NS	76,600	43,100	57,300
Chloride	250,000	NS	NS	1,440,000	783,000	972,000
EPA Method SM5310C						
Dissolved Organic Carbon - Quad		NS	NS	U 230	U 230	U 230
Total Organic Carbon - Quad		NS	NS	U 230	U 230	U 230
EPA Method 2320B						
Alkalinity		NS	NS	401,000	334,000	365,000
EPA Method SM2340B						
Hardness as Calcium Carbonate		NS	NS	1,030,000	3,760,000	1,130,000
EPA Method SM5210B						
Biochemical Oxygen Demand		NS	NS	13,200	1,300	174,000

NOTES:

All values reported as µg/L (parts per billion)

Bold and heavy outlined cells indicate and exceedance of applicable groundwater standard or guidance value

U – Analyzed for but not detected above laboratory detection limits

J – Indicates an estimated value

H – Sample was prepped or analyzed beyond the specified holding time

B – Analyte detected in the associated laboratory blank

b – Result detected in the USB

NS – Not sampled

NA – Not analyzed for

D.L. – Laboratory detection limit

R.L. – Laboratory reporting limit

D.F. – Laboratory dilution factor

* – Reported as 1,2-Dichloroethene. Total is previous laboratory reports

Feb-11, Mar-11, and Apr-11 data represents pilot test baseline, 1st post-pilot test sampling event, and 2nd post-pilot test sampling event, respectively

Jun-11, Aug-11, and Sep-11 data represents full scale ISCR injection baseline, 1st post-ISCR sampling event, and 2nd post-ISCR sampling event, respectively

^a – GW Std – Class GA Groundwater Quality Standard or Guidance Value from New York State Department of Environmental Conservation (NYSDEC) Division of Water

Technical and Operational Guidance Series (June 1998).



110 LUTHER AVENUE BCP SITE (BCP SITE #C734118)
PERIODIC REVIEW REPORT
TABLE 2: SUMMARY OF GROUNDWATER ANALYTICAL RESULTS
PAGE 3 OF 21

Analyte	GW Std ^a (ug/L)	MW-2											
		Jun-12			Sep-12			Dec-12			Mar-13		
VOCs by EPA Method 8260B													
Tetrachloroethene	5	D.L. 0.36 1	R.L. 1	U 0.36 1	D.L. 0.36 1	R.L. 1	U 0.36 1	D.L. 0.36 1	R.L. 1	U 0.36 1	D.L. 0.36 1	R.L. 1	U 0.36 1
Trichloroethene	5	D.L. 0.46 1	R.L. 1	U 0.46 1	D.L. 0.46 1	R.L. 1	U 0.46 1	D.L. 0.46 1	R.L. 1	U 0.46 1	D.L. 0.46 1	R.L. 1	U 0.46 1
cis-1,2-dichloroethene	5	D.L. 0.81 1	R.L. 1	U 0.81 1	D.L. 0.81 1	R.L. 1	U 0.81 1	D.L. 0.81 1	R.L. 1	U 0.81 1	D.L. 0.81 1	R.L. 1	U 0.81 1
trans-1,2-dichloroethene	5	D.L. 0.90 1	R.L. 1	U 0.90 1	D.L. 0.90 1	R.L. 1	U 0.90 1	D.L. 0.90 1	R.L. 1	U 0.90 1	D.L. 0.90 1	R.L. 1	U 0.90 1
Vinyl chloride	2	D.L. 0.90 1	R.L. 1	U 0.90 1	D.L. 0.90 1	R.L. 1	U 0.90 1	D.L. 0.90 1	R.L. 1	U 0.90 1	D.L. 0.90 1	R.L. 1	U 0.90 1
EPA Method RSK-175													
Ethane		U 0.93 7.2		U 0.49 7.5	U 0.49 7.5	1.7 J	0.49 7.5	7.6		0.49 7.5			
Ethylene		U 1.2 6.7		U 0.52 7	U 0.52 7		U 0.52 7			U 0.52 7			
Methane		63 U 1.3 3.9	40	U 0.22 4	41		U 0.22 4	52		U 0.22 4			
EPA Method 6010B (total)													
Calcium	883,000	100 500	884,000	100 500	693,000	100 500	NA						
Iron	300	70,300	19 50	86,800	19 50	46,700	19 50	65,800		19 50			
Magnesium	35,000	136,000	43 200	134,000	43 200	86,100	43 200	NA					
Manganese	300	5,000	0.4 3	5,300	0.4 3	3,500	0.4 3	NA					
EPA Method 6010B (dissolved)													
Iron	300	NS	NS	NS	NS	NS	1,500	19 50					
EPA Method 300													
Nitrate as N	10,000	U 11 50	3,500 20,000	U 11 50	27 J	11 50	43 JH	20 50					
Sulfate	250,000	76,400	51,000	7,000 40,000	65,300	7,000 40,000	79,000	7,000 40,000					
Chloride	250,000	1,200,000	5,600 10,000	1,250,000	5,600 10,000	936,000	5,600 10,000	1,260,000					
EPA Method SM5310C													
Dissolved Organic Carbon - Quad		3,200	430 1,000	3,200	430 1,000	3,800	430 1,000	3,100		430 1,000			
Total Organic Carbon - Quad		3,400	430 1,000	3,300	430 1,000	2,400	430 1,000	4,500		430 1,000			
EPA Method 2320B													
Alkalinity		408,000	790 5,000	396,000	790 5,000	388,000	790 5,000	458,000		790 5,000			
EPA Method SM2340B													
Hardness as Calcium Carbonate		2,760,000	100 500	2,760,000	100 500	2,080,000	100 500	2,430,000		100 500			
EPA Method SM5210B													
Biochemical Oxygen Demand		3,200	2,000 2,000	UH 2,000 2,000	UH 2,000 2,000		U 2,000 2,000	NS					

NOTES:
All values reported as ug/L (parts per billion)
Bold and heavy outlined cells indicate and exceedance of applicable groundwater standard or guidance value
U – Analyzed for but not detected above laboratory detection limits
J – Indicates an estimated value
H – Sample was prepped or analyzed beyond the specified holding time
B – Analyte detected in the associated laboratory blank
b – Result detected in the USB
NS – Not sampled
NA – Not analyzed for
D.L. – Laboratory detection limit
R.L. – Laboratory reporting limit
D.F. – Laboratory dilution factor
* - Reported as 1,2-Dichloroethene. Total is previous laboratory reports
Feb-11, Mar-11, and Apr-11 data represents pilot test baseline, 1st post-pilot test sampling event, and 2nd post-pilot test sampling event, respectively
Jun-11, Aug-11, and Sep-11 data represents full scale ISCR injection baseline, 1st post-ISCR sampling event, and 2nd post-ISCR sampling event, respectively
^a - GW Std – Class GA Groundwater Quality Standard or Guidance Value from New York State Department of Environmental Conservation (NYSDEC) Division of Water Technical and Operational Guidance Series (June 1998).



110 LUTHER AVENUE BCP SITE (BCP SITE #C734118)
PERIODIC REVIEW REPORT
TABLE 2: SUMMARY OF GROUNDWATER ANALYTICAL RESULTS
PAGE 4 OF 21

Analyte	GW Std ^a (ug/L)	MW-7									
		Jan-08	Feb-10	Feb-11	Mar-11	Apr-11	Jun-11	Aug-11	Sep-11		
VOCs by EPA Method 8260B											
Tetrachloroethene	5	14,000	D.L.	D.L.	D.L.	D.L.	D.L.	D.L.	D.L.	D.L.	D.L.
Trichloroethene	5	1,700	27,000	17,000	6,900	370	1,600	240	240	240	J
cis-1,2-dichloroethene	5	2,600	4,300	2,600	3,600	150	3,300	520	380	380	J
trans-1,2-dichloroethene	5	2,600	2,600	2,600	14,000	17,000	19,000	24,000	7,400	7,400	J
Vinyl chloride	2	560	260	620	460	690	1,100	8,500	4,300	4,300	J
EPA Method RSK-175											
Ethane	NS	NS	NS	4.7	8	4	5	U	8	U	20
Ethylene	NS	NS	NS	9.9	19	11	48	290	330	330	J
Methane	NS	NS	NS	240	350	160	230	390	720	720	J
EPA Method 6010B (total)											
Calcium	NS	181,000	176,000	313,000	253,000	212,000	274,000	54,200	62,300	62,300	B
Iron	300	NS	2,800	3,270	48,300	19,700	7,370	67,200	95,000	95,000	J
Magnesium	35,000	NS	56,200	53,200	89,400	65,000	59,500	2,010	1,430	1,430	J
Manganese	300	NS	150	314	2,270	1,130	649				J
EPA Method 6010B (dissolved)											
Iron	300	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS
EPA Method 300											
Nitrate as N	10,000	NS	NS	106,000	88,900	55,100	43,600.0	17,500	30,200	30,200	J
Sulfate	250,000	NS	NS	325,000	280,000	277,000	268,000	214,000	340,000	340,000	J
Chloride	250,000	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS
EPA Method SM5310C											
Dissolved Organic Carbon - Quad	NS	NS	NS	U	230	NR	115,000	303,000	457,000	457,000	J
Total Organic Carbon - Quad	NS	NS	NS	U	230	207,000	123,000	305,000	520,000	520,000	J
EPA Method 2320B											
Alkalinity	NS	NS	NS	326,000	521,000	506,000	488,000	594,000	725,000	725,000	B
EPA Method SM2340B											
Hardness as Calcium Carbonate	NS	NS	NS	659,000	1,150,000	900,000	773,000	961,000	1,280,000	1,280,000	J
EPA Method SM5210B											
Biochemical Oxygen Demand	NS	NS	NS	U	650	>228,300	>241,200	763,000	786,000	786,000	J

NOTES:

All values reported as µg/L (parts per billion)

Bold and heavy outlined cells indicate and exceedance of applicable groundwater standard or guidance value

U – Analyzed for but not detected above laboratory detection limits

J – Indicates an estimated value

H – Sample was prepped or analyzed beyond the specified holding time

B – Analyte detected in the associated laboratory blank

b – Result detected in the USB

NS – Not sampled

NA – Not analyzed for

D.L. – Laboratory detection limit

R.L. – Laboratory reporting limit

D.F. – Laboratory dilution factor

* - Reported as 1,2-Dichloroethene. Total is previous laboratory reports

Feb-11, Mar-11, and Apr-11 data represents pilot test baseline, 1st post-pilot test sampling event, and 2nd post-pilot test sampling event, respectively

Jun-11, Aug-11, and Sep-11 data represents full scale ISCR injection baseline, 1st post-ISCR sampling event, and 2nd post-ISCR sampling event, respectively

^a - GW Std – Class GA Groundwater Quality Standard or Guidance Value from New York State Department of Environmental Conservation (NYSDEC) Division of Water Technical and Operational Guidance Series (June 1998).



110 LUTHER AVENUE BCP SITE (BCP SITE #C734118)
PERIODIC REVIEW REPORT
TABLE 2: SUMMARY OF GROUNDWATER ANALYTICAL RESULTS
PAGE 5 OF 21

Analyte	GW Std ^a (ug/L)	MW-7																
		Mar-12			Jun-12			Sep-12			Dec-12			Mar-13				
		D.L.	R.L.	D.F.	D.L.	R.L.	D.F.	D.L.	R.L.	D.F.	D.L.	R.L.	D.F.	D.L.	R.L.	D.F.		
VOCs by EPA Method 8260B																		
Tetrachloroethene	5	34	0.36	1	1	U	72	200	200	U	140	400	400	U	140	400	400	
Trichloroethene	5	170	J	92	200	200	140	J	92	200	U	180	400	400	U	180	400	
cis-1,2-dichloroethene	5	11,000	160	200	200	26,000	320	400	400	27,000	320	400	400	16,000	320	400	400	
trans-1,2-dichloroethene	5	36	0.9	1	1	U	180	200	200	U	360	400	400	U	360	400	400	
Vinyl chloride	2	4,300	180	200	200	8,400	180	200	200	8,900	360	400	400	7,900	360	400	400	
EPA Method RSK-175																		
Ethane		120	J	49	150	100	U	47	360	50	U	25	380	50	430	25	380	50
Ethylene		280	52	150	100	860	60	340	50	1,800	26	350	50	2,000	26	350	50	
Methane		750	22	150	100	600	66	190	50	3,300	11	200	50	5,300	11	200	50	
EPA Method 6010B (total)																		
Calcium		200,000	B	100	500	1	303,000	100	500	1	649,000	100	500	1	469,000	B	100	500
Iron	300	5,300	19	50	1	23,800	19	50	1	179,000	19	50	1	73,300	B	19	50	1
Magnesium	35,000	62,600	43	200	1	93,700	43	200	1	136,000	43	200	1	138,000	B	43	200	1
Manganese	300	220	B	0.4	3	1	430	0.4	3	1	1,800	0.4	3	1	1,000	B	0.4	3
EPA Method 6010B (dissolved)																		
Iron	300	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	17,500	19	50	1	
EPA Method 300																		
Nitrate as N	10,000	U	11	50	1	12,300	U	11	50	1	U	11	50	1	52	11	50	1
Sulfate	250,000	47,000	350	2,000	1	360	2,000	1	350	2,000	1	3,500	350	2,000	1	7,400	350	2,000
Chloride	250,000	260,000	1,400	2,500	5	315,000	1,400	2,500	5	363,000	1,400	2,500	5	424,000	1,400	2,500	5	
EPA Method SM5310C																		
Dissolved Organic Carbon - Quad		18,500	430	1,000	1	308,000	17,400	40,000	40	1,250,000	17,400	40,000	40	334,000	4,300	10,000	10	
Total Organic Carbon - Quad		19,400	430	1,000	1	287,000	17,400	40,000	40	1,210,000	17,400	40,000	40	351,000	4,300	10,000	10	
EPA Method 2320B																		
Alkalinity		400,000	790	5,000	1	717,000	B	790	5,000	1	1,510,000	790	5,000	1	1,020,000	790	5,000	1
EPA Method SM2340B																		
Hardness as Calcium Carbonate		757,000	100	500	1	1,140,000	100	500	1	2,180,000	100	500	1	1,740,000	100	500	1	1,440,000
EPA Method SM5210B																		
Biochemical Oxygen Demand		27,400	b	2,000	2,000	1	698,000	H	20,000	20,000	10	2,960,000	8,000	8,000	4	470,000	2,000	2,000
																		NS

NOTES:

All values reported as µg/L (parts per billion)

Bold and heavy outlined cells indicate and exceedance of applicable groundwater standard or guidance value

U – Analyzed for but not detected above laboratory detection limits

J – Indicates an estimated value

H – Sample was prepped or analyzed beyond the specified holding time

B – Analyte detected in the associated laboratory blank

b – Result detected in the USB

NS – Not sampled

NA – Not analyzed for

D.L. – Laboratory detection limit

R.L. – Laboratory reporting limit

D.F. – Laboratory dilution factor

* - Reported as 1,2-Dichloroethene. Total is previous laboratory reports

Feb-11, Mar-11, and Apr-11 data represents pilot test sampling event, and 2nd post-pilot test sampling event, respectively

Jun-11, Aug-11, and Sep-11 data represents full scale ISCR injection baseline, 1st post-ISCR sampling event, and 2nd post-ISCR sampling event, respectively

^a - GW Std – Class GA Groundwater Quality Standard or Guidance Value from New York State Department of Environmental Conservation (NYSDEC) Division of Water

Technical and Operational Guidance Series (June 1998).



110 LUTHER AVENUE BCP SITE (BCP SITE #C734118)
PERIODIC REVIEW REPORT
TABLE 2: SUMMARY OF GROUNDWATER ANALYTICAL RESULTS
PAGE 6 OF 21

Analyte	GW Std ^a (ug/L)	MW-8						
		Jan-08	Feb-10	Jun-11	Aug-11	Sep-11	Mar-12	
VOCs by EPA Method 8260B								
Tetrachloroethene	5	6,200	D.L.	D.L.	D.L.	D.L.	D.L.	D.F.
Trichloroethene	5	920	860	1,500	380	1,100	82	0.36
cis-1,2-dichloroethene	5	1,600	2,500	540	140	420	22	0.46
trans-1,2-dichloroethene	5	1,600	2,500	1,700	5,100	7,900	140	3.2
Vinyl chloride	2	290	250	200	4,000	83	1.1	0.90
EPA Method RSK-175								
Ethane		NS	NS	15	20	30	74	0.49
Ethylene		NS	NS	14	290	710	930	52
Methane		NS	NS	670	930	1,200	22	100
EPA Method 6010B (total)								
Calcium		NS	NS	202,000	263,000	284,000	284,000	500
Iron	300	NS	NS	5,660	33,000	43,900	19	50
Magnesium	35,000	NS	NS	62,500	76,400	82,000	43	200
Manganese	300	NS	NS	1,990	3,870	3,730	710	0.4
EPA Method 6010B (dissolved)								
Iron	300	NS	NS	NS	NS	NS	NS	3
EPA Method 300								
Nitrate as N	10,000	NS	NS	81,100	4,500	3,500	44,600	11
Sulfate	250,000	NS	NS	431,000	482,000	474,000	538,000	1,700
Chloride	250,000	NS	NS				2,800	5,000
EPA Method SM5310C								
Dissolved Organic Carbon - Quad		NS	NS	U	155,000	200,000	2,400	430
Total Organic Carbon - Quad		NS	NS	U	173,000	168,000	2,400	430
EPA Method 2320B								
Alkalinity		NS	NS	385,000	633,000	643,000	790	5,000
EPA Method SM2340B								
Hardness as Calcium Carbonate		NS	NS	761,000	971,000	1,050,000	1,120,000	100
EPA Method SM5210B								
Biochemical Oxygen Demand		NS	NS	2,600	483,000	216,000	2,000	2,000

NOTES:

All values reported as µg/L (parts per billion)

Bold and heavy outlined cells indicate and exceedance of applicable groundwater standard or guidance value

U – Analyzed for but not detected above laboratory detection limits

J – Indicates an estimated value

H – Sample was prepped or analyzed beyond the specified holding time

B – Analyte detected in the associated laboratory blank

b – Result detected in the USB

NS – Not sampled

NA – Not analyzed for

D.L. – Laboratory detection limit

R.L. – Laboratory reporting limit

D.F. – Laboratory dilution factor

* - Reported as 1,2-Dichloroethene. Total is previous laboratory reports

Feb-11, Mar-11, and Apr-11 data represents pilot test baseline, 1st post-pilot test sampling event, and 2nd post-pilot test sampling event, respectively

Jun-11, Aug-11, and Sep-11 data represents full scale ISCR injection baseline, 1st post-ISCR sampling event, and 2nd post-ISCR sampling event, respectively

^a - GW Std – Class GA Groundwater Quality Standard or Guidance Value from New York State Department of Environmental Conservation (NYSDEC) Division of Water Technical and Operational Guidance Series (June 1998).



110 LUTHER AVENUE BCP SITE (BCP SITE #C734118)

PERIODIC REVIEW REPORT

TABLE 2: SUMMARY OF GROUNDWATER ANALYTICAL RESULTS
PAGE 7 OF 21

Analyte	GW Std ^a (ug/L)	MW43											
		Jun-12				Sep-12				Dec-12			
		D.L.	R.L.	D.F.		D.L.	R.L.	D.F.		D.L.	R.L.	D.F.	
VOCs by EPA Method 8260B													
Tetrachloroethene	5	1,000	72	200	200	9,500	72	200	200	1,800	36	100	100
Trichloroethene	5	460	92	200	200	1,900	92	200	200	470	46	100	100
cis-1,2-dichloroethene	5	4,000	160	200	200	8,000	160	200	200	6,600	81	100	100
trans-1,2-dichloroethene	5	21	3.6	4	4	34	0.90	1	1	U	90	100	100
Vinyl chloride	2	1,300	180	200	200	2,100	180	200	200	2,700	90	100	100
EPA Method RSK-175													
Ethane		U	47	360	50	U	25	380	50	160	J	25	380
Ethylene		270	J	60	340	50	U	26	350	350	26	350	50
Methane		6,800	66	190	50	3,300	11	200	50	6,100	11	200	50
EPA Method 6010B (total)													
Calcium		209,000	100	500	1	231,000	100	500	1	177,000	B	100	500
Iron	300	10,800	19	50	1	15,500	19	50	1	8,100	B	19	50
Magnesium	35,000	72,100	43	200	1	78,800	43	200	1	57,600	B	0.43	200
Manganese	300	2,000	0.4	3	1	1,600	0.4	3	1	1,800	B	0.4	3
EPA Method 6010B (dissolved)													
Iron	300	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS
EPA Method 300													
Nitrate as N	10,000	U	11	50	1	36	J	11	50	39	J	11	50
Sulfate	250,000	49,600	700	4,000	2	71,000	3,500	20,000	10	60,100	3,500	20,000	10
Chloride	250,000	414,000	2,800	5,000	10	406,000	2,800	5,000	10	370,000	2,800	5,000	10
EPA Method SM5310C													
Dissolved Organic Carbon - Quad		3,700	430	1,000	1	4,500	430	1,000	1	4,000	430	1,000	1
Total Organic Carbon - Quad		2,800	430	1,000	1	U	430	1,000	1	3,100	430	1,000	1
EPA Method 2320B													
Alkalinity		466,000	B	790	5,000	420,000	790	5,000	1	392,000	790	5,000	1
EPA Method SM2340B													
Hardness as Calcium Carbonate		818,000	100	500	1	902,000	100	500	1	678,000	100	500	1
EPA Method SM5210B													
Biochemical Oxygen Demand		U	2,000	2,000	1	6,500	2,000	2,000	1	U	2,000	2,000	1

NOTES:

All values reported as µg/L (parts per billion)

Bold and heavy outlined cells indicate and exceedance of applicable groundwater standard or guidance value

U – Analyzed for but not detected above laboratory detection limits

J – Indicates an estimated value

H – Sample was prepped or analyzed beyond the specified holding time

B – Analyte detected in the associated laboratory blank

b – Result detected in the USB

NS – Not sampled

NA – Not analyzed for

D.L. – Laboratory detection limit

R.L. – Laboratory reporting limit

D.F. – Laboratory dilution factor

* - Reported as 1,2-Dichloroethene. Total is previous laboratory reports

Feb-11, Mar-11, and Apr-11 data represents pilot test baseline, 1st post-pilot test sampling event, and 2nd post-pilot test sampling event, respectively

Jun-11, Aug-11, and Sep-11 data represents full scale ISCR injection baseline, 1st post-ISCR sampling event, and 2nd post-ISCR sampling event, respectively

^a - GW Std – Class GA Groundwater Quality Standard or Guidance Value from New York State Department of Environmental Conservation (NYSDEC) Division of Water

Technical and Operational Guidance Series (June 1998).



110 LUTHER AVENUE BCP SITE (BCP SITE #C734118)

PERIODIC REVIEW REPORT

TABLE 2: SUMMARY OF GROUNDWATER ANALYTICAL RESULTS
PAGE 8 OF 21

Analyte	GW Std ^a (ug/L)	MW-10							
		Feb-10		Sep-11		Mar-12		Dec-12	
VOCs by EPA Method 8260B									
Tetrachloroethene	5	NS	D.L.	U	0.81	U	0.36	U	0.36
Trichloroethene	5	NS		U	0.62	U	0.46	U	0.46
cis-1,2-dichloroethene	5	NS					56		90
trans-1,2-dichloroethene	5	NS		U	0.76	U	0.90	U	0.90
Vinyl chloride	2	NS					13		13
EPA Method RSK-175									
Ethane		NS		U	4	U	0.49	U	0.49
Ethylene		NS		U	3	U	0.52	U	0.52
Methane		NS		9.4		20	0.22	19	0.22
EPA Method 6010B (total)									
Calcium		141,000		595,000		173,000	100	500	100
Iron	300	1,570		71,000		8,500	19	50	17,600
Magnesium	35,000	47,300		230,000		61,000	43	200	60,500
Manganese	300	140		3,550		350	0.4	3	370
EPA Method 6010B (dissolved)									
Iron	300	NS		NS		NS			NS
EPA Method 300									
Nitrate as N	10,000	NS		U	33	U	11	50	32
Sulfate	250,000	NS		24,800.0		26,400	350	2,000	20,400
Chloride	250,000	NS		221,000		180,000	1,400	2,500	187,000
EPA Method SM5310C									
Dissolved Organic Carbon - Quad		NS		U	230	U	430	1,000	2,800
Total Organic Carbon - Quad		NS		U	230	U	430	1,000	880
EPA Method 2320B									
Alkalinity		NS		359,000		327	790	5,000	304,000
EPA Method SM2340B									
Hardness as Calcium Carbonate		NS		2,430,000		684,000	100	500	694,000
EPA Method SM5210B									
Biochemical Oxygen Demand		NS		U	650	U	2,000	2,000	U

NOTES:

All values reported as µg/L (parts per billion)

Bold and heavy outlined cells indicate and exceedance of applicable groundwater standard or guidance value

U – Analyzed for but not detected above laboratory detection limits

J – Indicates an estimated value

H – Sample was prepped or analyzed beyond the specified holding time

B – Analyte detected in the associated laboratory blank

b – Result detected in the USB

NS – Not sampled

NA – Not analyzed for

D.L. – Laboratory detection limit

R.L. – Laboratory reporting limit

D.F. – Laboratory dilution factor

* - Reported as 1,2-Dichloroethene. Total is previous laboratory reports

Feb-11, Mar-11, and Apr-11 data represents pilot test baseline, 1st post-pilot test sampling event, and 2nd post-pilot test sampling event, respectively

Jun-11, Aug-11, and Sep-11 data represents full scale ISCR injection baseline, 1st post-ISCR sampling event, and 2nd post-ISCR sampling event, respectively

^a - GW Std – Class GA Groundwater Quality Standard or Guidance Value from New York State Department of Environmental Conservation (NYSDEC) Division of Water

Technical and Operational Guidance Series (June 1998).



110 LUTHER AVENUE BCP SITE (BCP SITE #C734118)
PERIODIC REVIEW REPORT
TABLE 2: SUMMARY OF GROUNDWATER ANALYTICAL RESULTS
PAGE 9 OF 21

Analyte	GW Std* (ug/L)	MW-11									
		Mar-08	Feb-10	Feb-11	Mar-11	Apr-11	Jun-11	Aug-11	Sep-11		
VOCs by EPA Method 8260B											
Tetrachloroethene	5	14,000	D.L.	D.L.	D.L.	D.L.	D.L.	D.L.	D.L.		
Trichloroethene	5	2,400	20,000	42,000	4,200	2,200	J	U	410		
cis-1,2-dichloroethene	5	NS	6,100	6,300	1,100	U	310	U	620		
trans-1,2-dichloroethene	5	NS	4,400	3,800	39,000	77,000	58,000	49,000	380		
Vinyl chloride	2	U 1,000	U 76	U 380	U 150	U	U	U	U 300		
		U 1,000	270	U 500	U 200	U	U	U	680		
EPA Method RSK-175											
Ethane	NS	NS	NS	U 4	U 4	U 4	36	100	100		
Ethylene	NS	NS	NS	5.2	U 3	U 3	53	58	66		
Methane	NS	NS	NS	46	4.8	8.7	270	170	130		
EPA Method 6010B (total)											
Calcium	NS	170,000		189,000	361,000	515,000	930,000	1,230,000	1,240,000		
Iron	300	34,900	37,300	37,300	298,000	459,000	470,000	1,070,000	1,100,000		
Magnesium	35,000	50,800	55,700	55,700	82,300	111,000	140,000	178,000	175,000		
Manganese	300	NS	233	359	2,270	2,510	3,830	7,300	7,900		
EPA Method 6010B (dissolved)											
Iron	300	NS	NS	NS	NS	NS	NS	NS	NS		
EPA Method 300											
Nitrate as N	10,000	NS	NS	U 33	U 33	U 33	U 33	U 170	U 33		
Sulfate	250,000	NS	NS	107,000	40,100	100,000	106,000	124,000	176,000		
Chloride	250,000	NS	NS	300,000	404,000	523,000	541,000	236,000	241,000		
EPA Method SM5310C											
Dissolved Organic Carbon - Quad	NS	NS	NS	U 230	1,290,000	NR	2,350,000	3,570,000	5,190,000		
Total Organic Carbon - Quad	NS	NS	NS	U 230	1,310,000	2,280,000	2,720,000	4,620,000	4,430,000		
EPA Method 2320B											
Alkalinity	NS	NS	NS	281,000	837,000	1,700,000	2,070,000	3,170,000	3,310,000		
EPA Method SM2340B											
Hardness as Calcium Carbonate	NS	NS	NS	701,000	1,240,000	1,740,000	14,500,000	3,800,000	3,820,000		
EPA Method SM5210B											
Biochemical Oxygen Demand	NS	NS	NS	U 650	>2,367,000	337,000	>2,412,000	>4,566,000	6,830,000		

NOTES:

All values reported as µg/L (parts per billion)

Bold and heavy outlined cells indicate and exceedance of applicable groundwater standard or guidance value

U – Analyzed for but not detected above laboratory detection limits

J – Indicates an estimated value

H – Sample was prepped or analyzed beyond the specified holding time

B – Analyte detected in the associated laboratory blank

b – Result detected in the USB

NS – Not sampled

NA – Not analyzed for

D.L. – Laboratory detection limit

R.L. – Laboratory reporting limit

D.F. – Laboratory dilution factor

* - Reported as 1,2-Dichloroethene. Total is previous laboratory reports

Feb-11, Mar-11, and Apr-11 data represents pilot test sampling event, and 2nd post-pilot test sampling event, respectively

Jun-11, Aug-11, and Sep-11 data represents full scale ISCR injection baseline, 1st post-ISCR sampling event, and 2nd post-ISCR sampling event, respectively

^ - GW Std – Class GA Groundwater Quality Standard or Guidance Value from New York State Department of Environmental Conservation (NYSDEC) Division of Water

Technical and Operational Guidance Series (June 1998).



110 LUTHER AVENUE BCP SITE (BCP SITE #C734118)
PERIODIC REVIEW REPORT
TABLE 2: SUMMARY OF GROUNDWATER ANALYTICAL RESULTS
PAGE 10 OF 21

Analyte	GW Std ^a (ug/L)	MW-11											
		Mar-12				Jun-12				Sep-12			
		D.L.	R.L.	D.F.		D.L.	R.L.	D.F.		D.L.	R.L.	D.F.	
VOCs by EPA Method 8260B													
Tetrachloroethene	5	58	3.6	10	10	U	14	40	40	U	290	800	800
Trichloroethene	5	40	4.6	10	10	U	18	40	40	U	370	800	800
cis-1,2-dichloroethene	5	53,000	650	800	800	47,000	1,600	2,000	2,000	59,000	650	800	800
trans-1,2-dichloroethene	5	16	9.0	10	10	U	36	40	40	U	720	800	800
Vinyl chloride	2	2,700	720	800	800	3,500	36	40	40	4,300	720	800	800
EPA Method RSK-175													
Ethane		9.1	0.49	1.5	1	1,800	47	360	50	1,100	25	380	50
Ethylene		9.4	0.52	1.5	1	2,100	60	340	50	1,500	26	350	50
Methane		1.4	0.22	1	1	4,900	66	190	50	3,700	11	200	50
EPA Method 8010B (total)													
Calcium		1,390,000	B	500	2,500	5	1,450,000	500	2,500	5	1,240,000	1,000	5,000
Iron	300	1,280,000	97	250	5	1,270,000	97	250	5	1,120,000	19	50	1
Magnesium	35,000	169,000	43	200	1	184,000	43	200	1	155,000	43	200	1
Manganese	300	6,600	B	0.4	3	6,600	0.4	3	1	3,800	0.4	3	1
EPA Method 8010B (dissolved)													
Iron	300	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS
EPA Method 300													
Nitrate as N	10,000	U	11	50	1	780	U	11	50	1	U	11	50
Sulfate	250,000	U*	350	2,000	1	720	U	11	50	1	U	11	50
Chloride	250,000	343,000	2,800	5,000	10	470,000	1,400	2,500	5	455,000	1,400	2,500	5
EPA Method SM5310C													
Dissolved Organic Carbon - Quad		4,940,000	174,000	400,000	400	4,630,000	43,400	100,000	100	4,310,000	43,400	100,000	100
Total Organic Carbon - Quad		4,600,000	174,000	400,000	400	4,950,000	43,400	100,000	100	4,450,000	43,400	100,000	100
EPA Method 2320B													
Alkalinity		3,620,000	790	5,000	1	3,800,000	B	790	5,000	1	3,070,000	790	5,000
EPA Method SM2340B													
Hardness as Calcium Carbonate		4,160,000	100	500	1	4,380,000	100	500	1	4,840,000	100	500	1
EPA Method SM5210B													
Biochemical Oxygen Demand		9,870,000	H	20,000	10	10,200,000	H	20,000	10	10,200,000	Hb	200,000	100,000

NOTES:

All values reported as µg/L (parts per billion)

Bold and heavy outlined cells indicate and exceedance of applicable groundwater standard or guidance value

U – Analyzed for but not detected above laboratory detection limits

J – Indicates an estimated value

H – Sample was prepped or analyzed beyond the specified holding time

B – Analyte detected in the associated laboratory blank

b – Result detected in the USB

NS – Not sampled

NA – Not analyzed for

D.L. – Laboratory detection limit

R.L. – Laboratory reporting limit

D.F. – Laboratory dilution factor

* - Reported as 1,2-Dichloroethene. Total is previous laboratory reports

Feb-11, Mar-11, and Apr-11 data represents pilot test baseline, 1st post-pilot test sampling event, and 2nd post-pilot test sampling event, respectively

Jun-11, Aug-11, and Sep-11 data represents full scale ISCR injection baseline, 1st post-ISCR sampling event, and 2nd post-ISCR sampling event, respectively

^a - GW Std – Class GA Groundwater Quality Standard or Guidance Value from New York State Department of Environmental Conservation (NYSDEC) Division of Water Technical and Operational Guidance Series (June 1998).



110 LUTHER AVENUE BCP SITE (BCP SITE #C734118)
PERIODIC REVIEW REPORT
TABLE 2: SUMMARY OF GROUNDWATER ANALYTICAL RESULTS
PAGE 11 OF 21

Analyte	GW Std ^a (ug/L)	MW-12					
		Mar-08	Feb-10	Jun-11	Aug-11	Sep-11	Mar-12
VOCs by EPA Method 8260B							
Tetrachloroethene	5	1,200	D.L.	D.L.	D.L.	D.L.	D.L.
Trichloroethene	5	280	220	23	J	20	J
cis-1,2-dichloroethene	5	NS	79	U	U	16	J
trans-1,2-dichloroethene	5	NS	670	1,000	U	480	U
Vinyl chloride	2	U	U	U	U	7.6	U
		U	18	45	J	100	95
EPA Method RSK-175							
Ethane	NS	NS	NS	22	U	4	4.5
Ethylene	NS	NS	NS	41	7.8	5.5	20
Methane	NS	NS	NS	61	110	74	280
EPA Method 6010B (total)							
Calcium	NS	NS	NS	105,000	388,000	497,000	541,000
Iron	300	NS	NS	38,400	85,400	76,800	98,500
Magnesium	35,000	NS	NS	40,500	146,000	184,000	183,000
Manganese	300	NS	NS	583	1,500	2,110	2,500
EPA Method 6010B (dissolved)							
Iron	300	NS	NS	NS	NS	NS	NS
EPA Method 300							
Nitrate as N	10,000	NS	NS	4,200	U	33	U
Sulfate	250,000	NS	NS	NS	66,600	71,900	1,700
Chloride	250,000	NS	NS	485,000	526,000	473,000	2,800
EPA Method SM5310C							
Dissolved Organic Carbon - Quad		NS	NS	690	J	U	430
Total Organic Carbon - Quad		NS	NS	2,000	U	U	430
EPA Method 2320B							
Alkalinity		NS	NS	142,000	469,000	482,000	790
EPA Method SM2340B							
Hardness as Calcium Carbonate		NS	NS	429,000	1,570,000	2,000,000	100
EPA Method SM5210B							
Biochemical Oxygen Demand		NS	NS	6,500	2,500	U	2,000

NOTES:

All values reported as µg/L (parts per billion)

Bold and heavy outlined cells indicate and exceedance of applicable groundwater standard or guidance value

U – Analyzed for but not detected above laboratory detection limits

J – Indicates an estimated value

H – Sample was prepped or analyzed beyond the specified holding time

B – Analyte detected in the associated laboratory blank

b – Result detected in the USB

NS – Not sampled

NA – Not analyzed for

D.L. – Laboratory detection limit

R.L. – Laboratory reporting limit

D.F. – Laboratory dilution factor

* - Reported as 1,2-Dichloroethene. Total is previous laboratory reports

Feb-11, Mar-11, and Sep-11 data represents pilot test baseline, 1st post-pilot test sampling event, and 2nd post-pilot test sampling event, respectively

Jun-11, Aug-11, and Sep-11 data represents full scale ISCR injection baseline, 1st post-ISCR sampling event, and 2nd post-ISCR sampling event, respectively

^a - GW Std – Class GA Groundwater Quality Standard or Guidance Value from New York State Department of Environmental Conservation (NYSDEC) Division of Water

Technical and Operational Guidance Series (June 1998).



110 LUTHER AVENUE BCP SITE (BCP SITE #C734118)
PERIODIC REVIEW REPORT
TABLE 2: SUMMARY OF GROUNDWATER ANALYTICAL RESULTS
PAGE 12 OF 21

Analyte	GW Std ^a (ug/L)	MW-12											
		Jun-12				Sep-12				Dec-12			
		D.L.	R.L.	D.F.		D.L.	R.L.	D.F.		D.L.	R.L.	D.F.	
VOCs by EPA Method 8260B													
Tetrachloroethene	5	7.4	1.8	5	22	13	1.8	5	13	1.8	5	5	5
Trichloroethene	5	6.8	2.3	5	17	15	2.3	5	15	2.3	5	5	5
cis-1,2-dichloroethene	5	250	4.1	5	310	250	4.1	5	250	4.1	5	5	5
trans-1,2-dichloroethene	5	U	4.5	5	U	4.5	5	5	U	4.5	5	5	5
Vinyl chloride	2	57	4.5	5	64	58	4.5	5	58	4.5	5	5	5
EPA Method RSK-175													
Ethane		U	47	360	50	U	49	75	10	U	49	75	10
Ethylene		U	60	340	50	U	52	70	10	U	52	70	10
Methane		340	66	190	50	130	22	40	10	140	22	40	10
EPA Method 6010B (total)													
Calcium		689,000	100	500	1	431,000	100	500	1	632,000	100	500	1
Iron	300	76,500	19	50	1	115,000	19	50	1	95,300	19	50	1
Magnesium	35,000	180,000	43	200	1	165,000	43	200	1	131,000	43	200	1
Manganese	300	3,500	0.4	3	1	2,000	0.4	3	1	3,300	0.4	3	1
EPA Method 6010B (dissolved)													
Iron	300	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS
EPA Method 300													
Nitrate as N	10,000	U	11	50	1	U	11	50	1	24	J	11	50
Sulfate	250,000	70,500	1,700	10,000	5	82,000	1,700	10,000	5	83,900	3,500	20,000	10
Chloride	250,000	444,000	1,400	2,500	5	636,000	2,800	5,000	10	529,000	2,800	5,000	10
EPA Method SM5310C													
Dissolved Organic Carbon - Quad		2,000	430	1,000	1	1,800	430	1,000	1	800	J	430	1,000
Total Organic Carbon - Quad		1,400	430	1,000	1	1,600	430	1,000	1	550	J	430	1,000
EPA Method 2320B													
Alkalinity		433,000	B	790	5,000	1	456,000	790	5,000	1	393,000	790	5,000
EPA Method SM2340B													
Hardness as Calcium Carbonate		2,490,000	100	500	1	1,760,000	100	500	1	2,120,000	100	500	1
EPA Method SM5210B													
Biochemical Oxygen Demand		U	2,000	2,000	1	U	2,000	2,000	1	U	2,000	2,000	1

NOTES:

All values reported as µg/L (parts per billion)

Bold and heavy outlined cells indicate and exceedance of applicable groundwater standard or guidance value

U – Analyzed for but not detected above laboratory detection limits

J – Indicates an estimated value

H – Sample was prepped or analyzed beyond the specified holding time

B – Analyte detected in the associated laboratory blank

b – Result detected in the USB

NS – Not sampled

NA – Not analyzed for

D.L. – Laboratory detection limit

R.L. – Laboratory reporting limit

D.F. – Laboratory dilution factor

* - Reported as 1,2-Dichloroethene. Total is previous laboratory reports

Feb-11, Mar-11, and Apr-11 data represents pilot test baseline, 1st post-pilot test sampling event, and 2nd post-pilot test sampling event, respectively

Jun-11, Aug-11, and Sep-11 data represents full scale ISCR injection baseline, 1st post-ISCR sampling event, and 2nd post-ISCR sampling event, respectively

^a - GW Std – Class GA Groundwater Quality Standard or Guidance Value from New York State Department of Environmental Conservation (NYSDEC) Division of Water Technical and Operational Guidance Series (June 1998).



110 LUTHER AVENUE BCP SITE (BCP SITE #C734118)
PERIODIC REVIEW REPORT
TABLE 2: SUMMARY OF GROUNDWATER ANALYTICAL RESULTS
PAGE 13 OF 21

		MW-13					
Analyte	GW Std* (ug/L)	Mar-08	Feb-10	Jun-11	Aug-11	Sep-11	Mar-12
VOCs by EPA Method 8260B							
Tetrachloroethene	5	900	D.L.	D.L.	D.L.	D.L.	D.L. R.L. D.F.
Trichloroethene	5	470	410	1,300	2,500	2,800	36 100 100
cis-1,2-dichloroethene	5	NS	600	1,300	1,800	2,000	46 100 100
trans-1,2-dichloroethene	5	NS	780	12,000	11,000	7,800	81 100 100
Vinyl chloride	2	U 100	12 J	U 150	U 150	U 76	0.90 1 1
		U 100	29	300 J	220 J	140 J	90 100 100
EPA Method RSK-175							
Ethane	NS	NS	NS	9.3	4	U 4	14 0.49 1.5 1
Ethylene	NS	NS	NS	24	10	6.6	39 0.52 1.5 1
Methane	NS	NS	NS	230	160	91	360 22 100 100
EPA Method 6010B (total)							
Calcium	NS	NS	NS	130,000	97,000	96,900	334,000 B 100 500 1
Iron	300	NS	NS	103,000	25,600	28,500	19 50 1
Magnesium	35,000	NS	NS	37,900	29,800	30,500	115,000 43 200 1
Manganese	300	NS	NS	757	201	236	0.4 3 1
EPA Method 6010B (dissolved)							
Iron	300	NS	NS	NS	NS	NS	NS
EPA Method 300							
Nitrate as N	10,000	NS	NS	190	U 33	U 33	U 11 50 1
Sulfate	250,000	NS	NS	10,400	8,700	9,400	360 2,000 1
Chloride	250,000	NS	NS	114,000	119,000	115,000	560 1,000 2
EPA Method SM5310C							
Dissolved Organic Carbon - Quad	NS	NS	NS	560 J	410 J	580 J	430 1,000 1
Total Organic Carbon - Quad	NS	NS	NS	1,500	U 230	U 230	430 1,000 1
EPA Method 2320B							
Alkalinity	NS	NS	NS	246,000	260,000 B	264,000	790 5,000 1
EPA Method SM2340B							
Hardness as Calcium Carbonate	NS	NS	NS	480,000	365,000	368,000	1,310,000 100 500 1
EPA Method SM5210B							
Biochemical Oxygen Demand	NS	NS	NS	10,200	660 J	1,100 J	2,900 H 2,000 2,000 1

NOTES:
All values reported as µg/L (parts per billion)
Bold and heavy outlined cells indicate and exceedance of applicable groundwater standard or guidance value
U – Analyzed for but not detected above laboratory detection limits
J – Indicates an estimated value
H – Sample was prepped or analyzed beyond the specified holding time
B – Analyte detected in the associated laboratory blank
b – Result detected in the USB
NS – Not sampled
NA – Not analyzed for
D.L. – Laboratory detection limit
R.L. – Laboratory reporting limit
D.F. – Laboratory dilution factor
* - Reported as 1,2-Dichloroethene. Total is previous laboratory reports
Feb-11, Mar-11, and Apr-11 data represents pilot test baseline, 1st post-pilot test sampling event, and 2nd post-pilot test sampling event, respectively
Jun-11, Aug-11, and Sep-11 data represents full scale ISCR injection baseline, 1st post-ISCR sampling event, and 2nd post-ISCR sampling event, respectively
^a - GW Std – Class GA Groundwater Quality Standard or Guidance Value from New York State Department of Environmental Conservation (NYSDEC) Division of Water Technical and Operational Guidance Series (June 1998).



110 LUTHER AVENUE BCP SITE (BCP SITE #C734118)

PERIODIC REVIEW REPORT

TABLE 2: SUMMARY OF GROUNDWATER ANALYTICAL RESULTS
PAGE 14 OF 21

Analyte		MW-13																									
		Jun-12				Sep-12				Dec-12				Mar-13													
GW Std ^a (ug/L)		D.L.	R.L.	D.F.	D.L.	R.L.	D.F.	D.L.	R.L.	D.F.	D.L.	R.L.	D.F.	D.L.	R.L.	D.F.											
VOCs by EPA Method 8260B																											
Tetrachloroethene	5	2,400	36	100	100	3,300	36	100	100	5,100	36	100	100	4,600	36	100	100										
Trichloroethene	5	1,400	46	100	100	1,900	46	100	100	2,600	46	100	100	2,500	46	100	100										
cis-1,2-dichloroethene	5	9,200	160	200	200	9,700	81	100	100	8,400	81	100	100	9,600	81	100	100										
trans-1,2-dichloroethene	5		U	90	100	100	U	90	100	100	U	90	100	100	U	90	100	100									
Vinyl chloride	2	290	90	100	100	440	90	100	100	480	90	100	100	500	90	100	100										
EPA Method RSK-175																											
Ethane		U	47	360	50		U	4.9	75	10		U	4.9	75	10	16	J	4.9	75	10							
Ethylene		U	60	340	50		U	5.2	70	10		U	5.2	70	10	27	J	5.2	70	10							
Methane		430	66	190	50	420		2.2	40	10	320		2.2	40	10	290		2.2	40	10							
EPA Method 6010B (total)																											
Calcium		111,000	100	500	1	878,000	100	500	1	116,000	100	500	1	NA		19	50	1	NA	50	1						
Iron	300	23,900	19	50	1	275,000	19	50	1	29,300	19	50	1	347,000		19	50	1	347,000	19	50	1					
Magnesium	35,000	36,800	43	200	1	224,000	43	200	1	39,600	43	200	1	NA		43	200	1	NA	43	200	1					
Manganese	300	250	0.4	3	1	6,700	0.4	3	1	390	0.4	3	1	NA		0.4	3	1	NA	0.4	3	1					
EPA Method 6010B (dissolved)																											
Iron	300	NS				NS				NS				7,800		19	50	1	7,800	19	50	1					
EPA Method 300																											
Nitrate as N	10,000	U	11	50	1		U	11	50	1		U	11	50	1	46	JH	20	50	1	46	JH	20	50	1		
Sulfate	250,000	10,200	350	2,000	1	8,900	700	4,000	2	7,400	700	4,000	2	9,200	700	4,000	2	700	4,000	2	700	4,000	2	700	4,000	2	
Chloride	250,000	113,000	560	1,000	2	117,000	560	1,000	2	109,000	560	1,000	2	126,000	560	1,000	2	560	1,000	2	560	1,000	2	560	1,000	2	
EPA Method SM5310C																											
Dissolved Organic Carbon - Quad		2,800	430	1,000	1	5,200	430	1,000	1	4,600	430	1,000	1	2,500		430	1,000	1	2,500	430	1,000	1	430	1,000	1		
Total Organic Carbon - Quad		820	J	430	1,000	1	2,500	430	1,000	1	1,300	430	1,000	1	4,200		430	1,000	1	4,200	430	1,000	1	430	1,000	1	
EPA Method 2320B																											
Alkalinity		258,000	B	790	5,000	1	265,000	790	5,000	1	240,000	790	5,000	1	249,000		790	5,000	1	249,000	790	5,000	1	790	5,000	1	
EPA Method SM2340B																											
Hardness as Calcium Carbonate		429,000	100	500	1	3,110,000	100	500	1	452,000	100	500	1	3,330,000		100	500	1	3,330,000	100	500	1	100	500	1		
EPA Method SM5210B																											
Biochemical Oxygen Demand		2,600	2,000	2,000	1		UH	2,000	2,000	1	2,200	b	2,000	2,000	1	NS		2,000	2,000	1	NS	2,000	2,000	1	2,000	2,000	1

NOTES:

All values reported as µg/L (parts per billion)

Bold and heavy outlined cells indicate and exceedance of applicable groundwater standard or guidance value

U – Analyzed for but not detected above laboratory detection limits

J – Indicates an estimated value

H – Sample was prepped or analyzed beyond the specified holding time

B – Analyte detected in the associated laboratory blank

b – Result detected in the USB

NS – Not sampled

NA – Not analyzed for

D.L. – Laboratory detection limit

R.L. – Laboratory reporting limit

D.F. – Laboratory dilution factor

* - Reported as 1,2-Dichloroethene. Total is previous laboratory reports

Feb-11, Mar-11, and Apr-11 data represents pilot test baseline, 1st post-pilot test sampling event, and 2nd post-pilot test sampling event, respectively

Jun-11, Aug-11, and Sep-11 data represents full scale ISCR injection baseline, 1st post-ISCR sampling event, and 2nd post-ISCR sampling event, respectively

^a - GW Std – Class GA Groundwater Quality Standard or Guidance Value from New York State Department of Environmental Conservation (NYSDEC) Division of Water

Technical and Operational Guidance Series (June 1998).



110 LUTHER AVENUE BCP SITE (BCP SITE #C734118)

PERIODIC REVIEW REPORT

TABLE 2: SUMMARY OF GROUNDWATER ANALYTICAL RESULTS

PAGE 15 OF 21

Analyte	GW Std ^a (ug/L)	MW-15				MW-16					
		Apr-08	Dec-12			Apr-08	Feb-10	Dec-12			
		D.L.	R.L.	D.F.		D.L.	R.L.	D.F.			
VOCs by EPA Method 8260B											
Tetrachloroethene	5	U	1	U	0.36	1	U	0.87	J	0.36	1
Trichloroethene	5	U	1	U	0.46	1	U		U	0.46	1
cis-1,2-dichloroethene	5	NS		U	0.81	1	50	43	0.81	1	1
trans-1,2-dichloroethene	5	U	1	U	0.90	1	U		U	0.90	1
Vinyl chloride	2	U	1	U	0.90	1	2.5	2.3	J	0.90	1
EPA Method RSK-175											
Ethane		NS		U	2.5	38	NS		U	0.49	7.5
Ethylene		NS		U	2.6	35	NS		U	0.52	7
Methane		NS			4.4	20	NS	38		0.22	4
EPA Method 6010B (total)											
Calcium		NS			879,000	100	NS			912,000	100
Iron	300	NS			42,600	19	NS			65,700	19
Magnesium	35,000	NS			126,000	43	NS			112,000	43
Manganese	300	NS			4,400	0.4	NS			5,500	0.4
EPA Method 6010B (dissolved)											
Iron	300	NS			NS		NS			NS	
EPA Method 300											
Nitrate as N	10,000	NS				11	NS			23	J
Sulfate	250,000	NS			72,900	1,700	NS			36,400	700
Chloride	250,000	NS			416,000	1,400	NS			236,000	1,400
EPA Method SM5310C											
Dissolved Organic Carbon - Quad		NS			4,200	430	NS			1,400	430
Total Organic Carbon - Quad		NS			1,600	430	NS			1,700	430
EPA Method 2320B											
Alkalinity		NS			460,000	790	NS			287,000	790
EPA Method SM2340B											
Hardness as Calcium Carbonate		NS			2,710,000	100	NS			2,740,000	100
EPA Method SM5210B											
Biochemical Oxygen Demand		NS			3,700	b	NS			3,800	b

NOTES:

All values reported as ug/L (parts per billion)

Bold and heavy outlined cells indicate and exceedance of applicable groundwater standard or guidance value

U – Analyzed for but not detected above laboratory detection limits

J – Indicates an estimated value

H – Sample was prepped or analyzed beyond the specified holding time

B – Analyte detected in the associated laboratory blank

b – Result detected in the USB

NS – Not sampled

NA – Not analyzed for

D.L. – Laboratory detection limit

R.L. – Laboratory reporting limit

D.F. – Laboratory dilution factor

* - Reported as 1,2-Dichloroethene. Total is previous laboratory reports

Feb-11, Mar-11, and Apr-11 data represents pilot test baseline, 1st post-pilot test sampling event, and 2nd post-pilot test sampling event, respectively

Jun-11, Aug-11, and Sep-11 data represents full scale ISCR injection baseline, 1st post-ISCR sampling event, and 2nd post-ISCR sampling event, respectively

^a - GW Std – Class GA Groundwater Quality Standard or Guidance Value from New York State Department of Environmental Conservation (NYSDEC) Division of Water

Technical and Operational Guidance Series (June 1998).



110 LUTHER AVENUE BCP SITE (BCP SITE #C734118)
PERIODIC REVIEW REPORT
TABLE 2: SUMMARY OF GROUNDWATER ANALYTICAL RESULTS
PAGE 16 OF 21

Analyte	GW Std ^a (ug/L)	MW-17						
		Feb-10	Feb-11	Mar-11	Apr-11	Jun-11	Aug-11	Sep-11
VOCs by EPA Method 8260B								
Tetrachloroethene	5	14,000	D.L.	6,300	D.L.	7,600	D.L.	D.L.
Trichloroethene	5	2,000	8,800	1,200	1,800	1,000	U	U
cis-1,2-dichloroethene	5	750	1,400	780	1,400	940	21,000	12,000
trans-1,2-dichloroethene	5	U	U	U	U	U	U	U
Vinyl chloride	2	U	U	U	U	U	360	1,800
EPA Method RSK-175								
Ethane		NS	U	U	U	U	U	U
Ethylene		NS	U	U	U	U	U	U
Methane		NS	11	27	9.5	32	2,100	2,100
EPA Method 6010B (total)								
Calcium		NS	295,000	126,000	341,000	89,600	465,000	387,000
Iron	300	NS	50,000	13,200	36,400	924	89,200	58,900
Magnesium	35,000	NS	102,000	35,500	110,000	21,100	81,500	85,400
Manganese	300	NS	2,080	737	2,210	521	6,710	4,530
EPA Method 6010B (dissolved)								
Iron	300	NS	NS	NS	NS	NS	NS	NS
EPA Method 300								
Nitrate as N	10,000	NS	U	U	U	U	U	U
Sulfate	250,000	NS	97,000	84,200	101,000	212,000	31,000	21,700
Chloride	250,000	NS	193,000	213,000	222,000	89,700.0	169,000	219,000
EPA Method SM5310C								
Dissolved Organic Carbon - Quad		NS	U	U	U	U	804,000	415,000
Total Organic Carbon - Quad		NS	U	U	U	U	813,000	457,000
EPA Method 2320B								
Alkalinity		NS	245,000	249,000	258,000	247,000	1,150,000	889,000
EPA Method SM2340B								
Hardness as Calcium Carbonate		NS	1,160,000	461,000	1,300,000	310,000	1,500,000	1,320,000
EPA Method SM5210B								
Biochemical Oxygen Demand		NS	U	U	U	U	>1,743,000	717,000

NOTES:

All values reported as µg/L (parts per billion)

Bold and heavy outlined cells indicate and exceedance of applicable groundwater standard or guidance value

U – Analyzed for but not detected above laboratory detection limits

J – Indicates an estimated value

H – Sample was prepped or analyzed beyond the specified holding time

B – Analyte detected in the associated laboratory blank

b – Result detected in the USB

NS – Not sampled

NA – Not analyzed for

D.L. – Laboratory detection limit

R.L. – Laboratory reporting limit

D.F. – Laboratory dilution factor

* - Reported as 1,2-Dichloroethene. Total is previous laboratory reports

Feb-11, Mar-11, and Apr-11 data represents pilot test baseline, 1st post-pilot test sampling event, and 2nd post-pilot test sampling event, respectively

Jun-11, Aug-11, and Sep-11 data represents full scale ISCR injection baseline, 1st post-ISCR sampling event, and 2nd post-ISCR sampling event, respectively

^a - GW Std – Class GA Groundwater Quality Standard or Guidance Value from New York State Department of Environmental Conservation (NYSDEC) Division of Water Technical and Operational Guidance Series (June 1998).



110 LUTHER AVENUE BCP SITE (BCP SITE #C734118)
PERIODIC REVIEW REPORT
TABLE 2: SUMMARY OF GROUNDWATER ANALYTICAL RESULTS
PAGE 17 OF 21

Analyte	GW Std ^a (µg/L)	MW-17											
		Mar-12			Jun-12			Sep-12			Dec-12		
		D.L.	R.L.	D.F.	D.L.	R.L.	D.F.	D.L.	R.L.	D.F.	D.L.	R.L.	D.F.
VOCs by EPA Method 8260B													
Tetrachloroethene	5	9.7	1.8	5	3.6	1	1	U	18	50	50	U	3.6
Trichloroethene	5	6.5	2.3	5	7.0	0.46	1	U	23	50	50	U	4.6
cis-1,2-dichloroethene	5	2,700	41	50	4,300	65	80	3,500	41	50	3,800	41	50
trans-1,2-dichloroethene	5	6.6	4.5	5	U	0.90	1	U	45	50	U	45	50
Vinyl chloride	2	990	45	50	1,800	72	80	1,200	45	50	2,100	45	50
EPA Method RSK-175													
Ethane		260	0.49	1.5	400	47	360	50	470	9.8	150	20	450
Ethylene		160	52	150	460	60	340	50	390	10	140	20	560
Methane		4,000	22	100	11,000	260	780	200	5,100	44	800	200	6,800
EPA Method 6010B (total)													
Calcium		256,000	B	100	500	1	242,000	100	500	1	254,000	100	500
Iron	300	22,500	19	50	24,800	19	50	41,200	19	50	23,400	19	50
Magnesium	35,000	63,600	43	200	65,400	43	200	87,800	43	200	68,400	43	200
Manganese	300	2,500	B	0.4	3	1	2,100	0.4	3	1	1,700	0.4	3
EPA Method 6010B (dissolved)													
Iron	300	NS	NS	NS	NS	NS	NS	NS	NS	NS	21,800	19	50
EPA Method 300													
Nitrate as N	10,000	U	11	50	1	28,800	U	11	50	1	36	J	11
Sulfate	250,000	28,000	1,700	10,000	5	10,200	1,700	10,000	5	2,100	350	2,000	1
Chloride	250,000	260,000	1,400	2,500	5	253,000	1,400	2,500	5	234,000	1,400	2,500	5
EPA Method SM5310C													
Dissolved Organic Carbon - Quad		6,800	430	1,000	1	20,300	430	1,000	1	2,600	430	1,000	1
Total Organic Carbon - Quad		34,100	430	1,000	1	15,100	430	1,000	1	26,200	430	1,000	1
EPA Method 2320B													
Alkalinity		760,000	790	5,000	1	792,000	B	790	5,000	1	770,000	790	5,000
EPA Method SM2340B													
Hardness as Calcium Carbonate		901,000	100	500	1	874,000	100	500	1	1,100,000	100	500	1
EPA Method SM5210B													
Biochemical Oxygen Demand		49,000	2,000	2,000	1	47,300	2,000	2,000	1	55,200	2,000	2,000	1

NOTES:

All values reported as µg/L (parts per billion)

Bold and heavy outlined cells indicate and exceedance of applicable groundwater standard or guidance value

U – Analyzed for but not detected above laboratory detection limits

J – Indicates an estimated value

H – Sample was prepped or analyzed beyond the specified holding time

B – Analyte detected in the associated laboratory blank

b – Result detected in the USB

NS – Not sampled

NA – Not analyzed for

D.L. – Laboratory detection limit

R.L. – Laboratory reporting limit

D.F. – Laboratory dilution factor

* - Reported as 1,2-Dichloroethene. Total is previous laboratory reports

Feb-11, Mar-11, and Apr-11 data represents pilot test baseline, 1st post-pilot test sampling event, and 2nd post-pilot test sampling event, respectively

Jun-11, Aug-11, and Sep-11 data represents full scale ISCR injection baseline, 1st post-ISCR sampling event, and 2nd post-ISCR sampling event, respectively

^a - GW Std – Class GA Groundwater Quality Standard or Guidance Value from New York State Department of Environmental Conservation (NYSDEC) Division of Water

Technical and Operational Guidance Series (June 1998).



110 LUTHER AVENUE BCP SITE (BCP SITE #C734118)

PERIODIC REVIEW REPORT

TABLE 2: SUMMARY OF GROUNDWATER ANALYTICAL RESULTS
PAGE 18 OF 21

Analyte	GW Std ^a (ug/L)	MW-18															
		Feb-10			Sep-11	Mar-12		Dec-12									
VOCs by EPA Method 8260B																	
Tetrachloroethene	5		U	0.81		U	0.81		U	0.36	1						
Trichloroethene	5		U	0.62		U	0.62		U	0.46	1						
cis-1,2-dichloroethene	5		U	0.59		U	0.81		5.5	0.81	1						
trans-1,2-dichloroethene	5		U	0.76		U	0.90		U	0.90	1						
Vinyl chloride	2		2.7	J		17		9.2		U	0.90	1					
EPA Method RSK-175																	
Ethane			NS		U	4		U	0.49	1.5		U	4.9	75			
Ethylene			NS		U	3		1.2	J	0.52	1.5		U	5.2	70		
Methane			NS		70			42		0.22	1		240		2.2	40	
EPA Method 6010B (total)																	
Calcium			NS		120,000			81,600	B	100	500		41,900		100	500	
Iron	300		NS		34,500			10,000		19	50		5,600		19	50	
Magnesium	35,000		NS		37,800			21,500		43	200		10,200		43	200	
Manganese	300		NS		1,270			670	B	0.4	3		400		0.4	3	
EPA Method 6010B (dissolved)																	
Iron	300		NS		NS			NS					NS				
EPA Method 300																	
Nitrate as N	10,000		NS														
Sulfate	250,000		NS			U	33	42,200		U	11	50	23		J	11	50
Chloride	250,000		NS		385,000			892,000			5,600	10,000	58,900		7,000	40,000	
EPA Method SM5310C																	
Dissolved Organic Carbon - Quad			NS		640		J	3,700			430	1,000	10,900		430	1,000	
Total Organic Carbon - Quad			NS		620		J	2,500			430	1,000	10,100		430	1,000	
EPA Method 2320B																	
Alkalinity			NS		370,000		B	247,000			790	5,000	400,000		790	5,000	
EPA Method SM2340B																	
Hardness as Calcium Carbonate			NS		455,000			292,000			100	500	146,000		100	500	
EPA Method SM5210B																	
Biochemical Oxygen Demand			NS		660		J			U	2,000	2,000			U	2,000	2,000



110 LUTHER AVENUE BCP SITE (BCP SITE #C734118)

PERIODIC REVIEW REPORT

TABLE 2: SUMMARY OF GROUNDWATER ANALYTICAL RESULTS
PAGE 19 OF 21

Analyte	GW Std ^a (ug/L)	MW-19							
		Feb-10		Sep-11		Mar-12		Dec-12	
VOCs by EPA Method 8260B									
Tetrachloroethene	5	D.L.	U 0.81	U 0.81	D.L.	U 0.36	1	U 0.36	1
Trichloroethene	5	U 0.62	U 0.62	U 0.46	1	U 0.46	1	U 0.46	1
cis-1,2-dichloroethene	5	U 0.99	U 0.99	U 0.81	1	U 0.81	1	U 0.81	1
trans-1,2-dichloroethene	5	U 0.76	U 0.76	U 0.90	1	U 0.90	1	U 0.90	1
Vinyl chloride	2	U 0.99	U 0.99	U 0.90	1	U 0.90	1	U 0.90	1
EPA Method RSK-175									
Ethane		NS	U 8	U 0.49	1.5	U 0.49	7.5	U 0.49	7.5
Ethylene		NS	U 6	U 0.52	1.5	U 0.52	7	U 0.52	7
Methane		NS	680	180	2.2	10	36	0.22	4
EPA Method 6010B (total)									
Calcium		NS	101,000	79,900	B	100	500	43,600	100
Iron	300	NS	3,440	26,500	19	50	3,400	19	50
Magnesium	35,000	NS	22,700	22,700	43	200	8,100	43	200
Manganese	300	NS	997	1,000	B	0.4	3	180	0.4
EPA Method 6010B (dissolved)									
Iron	300	NS	NS	NS	NS	NS	NS	NS	NS
EPA Method 300									
Nitrate as N	10,000	NS	43,100	U 33	U 11	50	88	11	50
Sulfate	250,000	NS	661,000	30,200	350	2,000	26,600	1,700	10,000
Chloride	250,000	NS	661,000	433,000	1,400	2,500	149,000	1,400	2,500
EPA Method SM5310C									
Dissolved Organic Carbon - Quad		NS	520	J	4,300	430	1,000	430	1,000
Total Organic Carbon - Quad		NS	230	J	3,100	430	1,000	430	1,000
EPA Method 2320B									
Alkalinity		NS	336,000	B	220,000	790	5,000	207,000	790
EPA Method SM2340B									
Hardness as Calcium Carbonate		NS	347,000	293,000	100	500	142,000	100	500
EPA Method SM5210B									
Biochemical Oxygen Demand		NS	3,700	U	2,000	2,000	U	2,000	2,000

NOTES:

All values reported as µg/L (parts per billion)

Bold and heavy outlined cells indicate and exceedance of applicable groundwater standard or guidance value

U – Analyzed for but not detected above laboratory detection limits

J – Indicates an estimated value

H – Sample was prepped or analyzed beyond the specified holding time

B – Analyte detected in the associated laboratory blank

b – Result detected in the USB

NS – Not sampled

NA – Not analyzed for

D.L. – Laboratory detection limit

R.L. – Laboratory reporting limit

D.F. – Laboratory dilution factor

* - Reported as 1,2-Dichloroethene. Total is previous laboratory reports

Feb-11, Mar-11, and Apr-11 data represents pilot test baseline, 1st post-pilot test sampling event, and 2nd post-pilot test sampling event, respectively

Jun-11, Aug-11, and Sep-11 data represents full scale ISCR injection baseline, 1st post-ISCR sampling event, and 2nd post-ISCR sampling event, respectively

^a - GW Std – Class GA Groundwater Quality Standard or Guidance Value from New York State Department of Environmental Conservation (NYSDEC) Division of Water

Technical and Operational Guidance Series (June 1998).



110 LUTHER AVENUE BCP SITE (BCP SITE #C734118)

PERIODIC REVIEW REPORT

TABLE 2: SUMMARY OF GROUNDWATER ANALYTICAL RESULTS

PAGE 20 OF 21

Analyte	GW Std ^a (ug/L)	DUPLICATE						
		Feb-10 (MW-8)	Feb-11 (MW-17)	Mar-11 (MW-17)	Apr-11 (MW-17)	Jun-11 (MW-8)	Aug-11 (MW-8)	Sep-11 (MW-8)
VOCs by EPA Method 8260B								
Tetrachloroethene	5	3,500	D.L.	D.L.	D.L.	D.L.	D.L.	D.L.
Trichloroethene	5	900	14,000	4,000	11,000	1,700	330	500
cis-1,2-dichloroethene	5	2,500	2,700	1,000	2,000	570	130	220
trans-1,2-dichloroethene	5	U	1,900	740	1,200	1,800	3,900	5,500
Vinyl chloride	2	270	U 30	U 150	U 30	U 78	U 19	87
			U 200	U 40	U 99	220	2,900	3,400
EPA Method RSK-175								
Ethane	NS	NS	U 4	U 4	U 4	U 20	21	25
Ethylene	NS	NS	U 3	U 3	U 3	U 15	320	640
Methane	NS	NS	23	24	8.7	390	1,000	1,100
EPA Method 6010B (total)								
Calcium	NS	305,000	128,000	324,000	200,000	265,000	282,000	
Iron	300	52,400	14,100	32,900	5,460	33,300	43,400	
Magnesium	35,000	106,000	36,200	100,000	82,100	77,000	82,400	
Manganese	300	2,160	762	2,100	1,960	3,870	3,740	
EPA Method 6010B (dissolved)								
Iron	300	NS	NS	NS	NS	NS	NS	NS
EPA Method 300								
Nitrate as N	10,000	NS	U 33	U 33	U 33	U 33	U 33	U 33
Sulfate	250,000	97,800	83,200	99,800	81,000.0	4,400	4000.0	
Chloride	250,000	196,000	209,000	222,000	433,000	469,000	468,000	
EPA Method SM5310C								
Dissolved Organic Carbon - Quad	NS	NS	U 230	U 230	U 230	U 230	164,000	198,000
Total Organic Carbon - Quad	NS	NS	U 230	U 230	U 230	U 230	172,000	177,000
EPA Method 2320B								
Alkalinity	NS	251,000	248,000	257,000	381,000	638,000	645,000	B
EPA Method SM2340B								
Hardness as Calcium Carbonate	NS	1,200,000	469,000	1,220,000	756,000	978,000	1,040,000	
EPA Method SM5210B								
Biochemical Oxygen Demand	NS	NS	U 650	U 650	U 650	4,000	363,000	>213,600

NOTES:

All values reported as ug/L (parts per billion)

Bold and heavy outlined cells indicate and exceedance of applicable groundwater standard or guidance value

U – Analyzed for but not detected above laboratory detection limits

J – Indicates an estimated value

H – Sample was prepped or analyzed beyond the specified holding time

B – Analyte detected in the associated laboratory blank

b – Result detected in the USB

NS – Not sampled

NA – Not analyzed for

D.L. – Laboratory detection limit

R.L. – Laboratory reporting limit

D.F. – Laboratory dilution factor

* - Reported as 1,2-Dichloroethene. Total is previous laboratory reports

Feb-11, Mar-11, and Apr-11 data represents pilot test baseline, 1st post-pilot test sampling event, and 2nd post-pilot test sampling event, respectively

Jun-11, Aug-11, and Sep-11 data represents full scale ISCR injection baseline, 1st post-ISCR sampling event, and 2nd post-ISCR sampling event, respectively

^a - GW Std – Class GA Groundwater Quality Standard or Guidance Value from New York State Department of Environmental Conservation (NYSDEC) Division of Water

Technical and Operational Guidance Series (June 1998).



110 LUTHER AVENUE BCP SITE (BCP SITE #C734118)

PERIODIC REVIEW REPORT

TABLE 2: SUMMARY OF GROUNDWATER ANALYTICAL RESULTS

PAGE 21 OF 21

Analyte	GW Std ^a (ug/L)	DUPLICATE											
		Mar-12 (MW-10)			Jun-12 (MW-5)			Sep-12 (MW-5)			Dec-12 (MW-19)		
		D.L.	R.L.		D.L.	R.L.		D.L.	R.L.		D.L.	R.L.	
VOCs by EPA Method 8260B													
Tetrachloroethene	5	U	0.36	1	3,000	72	80	6,800	72	200	U	0.36	1
Trichloroethene	5	U	0.46	1	1,300	37	80	1,500	92	200	U	0.46	1
cis-1,2-dichloroethene	5	54	0.81	1	6,500	65	80	7,000	160	200	U	0.81	1
trans-1,2-dichloroethene	5	U	0.90	1	U	72	80	34	0.90	1	U	0.90	1
Vinyl chloride	2	12	0.90	1	2,000	72	80	2,200	180	200	U	0.90	1
EPA Method RSK-175													
Ethane		U	0.49	1.5	U	47	360	U	25	380	U	0.49	7.5
Ethylene		1.2	J	0.52	1.5	U	60	340	46	J	U	0.52	7
Methane		21	0.22	1	3,500	66	190	4,200	11	200	62	0.22	4
EPA Method 6010B (total)													
Calcium		171,000	B	100	500	210,000	100	500	228,000	100	500	44,200	100
Iron	300	8,500	19	50	10,800	19	50	14,200	19	50	3,200	19	50
Magnesium	35,000	60,200	43	200	77,400	43	200	77,700	43	200	8,300	43	200
Manganese	300	330	B	0.4	3	1,900	0.4	3	1,600	0.4	3	180	0.4
EPA Method 6010B (dissolved)													
Iron	300	NS	NS	NS	NS	NS	NS	NS	NS	NS	NS	16,800	19
EPA Method 300													
Nitrate as N	10,000	U	11	50	U	11	50	35	J	11	50	23	J
Sulfate	250,000	26,400	350	2,000	25,100	350	2,000	74,200	1,700	10,000	1,700	10,000	1,700
Chloride	250,000	180,000	1,400	2,500	419,000	1,400	2,500	407,000	1,400	2,500	151,000	1,400	2,500
EPA Method SM5310C													
Dissolved Organic Carbon - Quad		2,900	430	1,000	2,900	430	1,000	5,800	430	1,000	3,900	430	1,000
Total Organic Carbon - Quad		1,000	430	1,000	2,700	430	1,000	710	J	430	3,700	430	1,000
EPA Method 2320B													
Alkalinity		333,000	790	5,000	466,000	B	790	5,000	419,000	790	5,000	207,000	790
EPA Method SM2340B													
Hardness as Calcium Carbonate		674,000	100	500	818,000	100	500	888,000	100	500	144,000	100	500
EPA Method SM5210B													
Biochemical Oxygen Demand		U	2,000	2,000	8,900	b	2,000	2,000	5,900	2,000	2,000	NS	NS

NOTES:

All values reported as µg/L (parts per billion)

Bold and heavy outlined cells indicate and exceedance of applicable groundwater standard or guidance value

U – Analyzed for but not detected above laboratory detection limits

J – Indicates an estimated value

H – Sample was prepped or analyzed beyond the specified holding time

B – Analyte detected in the associated laboratory blank

b – Result detected in the USB

NS – Not sampled

NA – Not analyzed for

D.L. – Laboratory detection limit

R.L. – Laboratory reporting limit

D.F. – Laboratory dilution factor

* - Reported as 1,2-Dichloroethene. Total is previous laboratory reports

Feb-11, Mar-11, and Apr-11 data represents pilot test baseline, 1st post-pilot test sampling event, and 2nd post-pilot test sampling event, respectively


Jun-11, Aug-11, and Sep-11 data represents full scale ISCR injection baseline, 1st post-ISCR sampling event, and 2nd post-ISCR sampling event, respectively

^a - GW Std – Class GA Groundwater Quality Standard or Guidance Value from New York State Department of Environmental Conservation (NYSDEC) Division of Water

Technical and Operational Guidance Series (June 1998).

Appendices

Appendix A - Institutional and Engineering Controls Certification Form



Enclosure 2
NEW YORK STATE DEPARTMENT OF ENVIRONMENTAL CONSERVATION
Site Management Periodic Review Report Notice
Institutional and Engineering Controls Certification Form



Site Details		Box 1
Site No.	C734118	
Site Name 110 Luther Ave. Site		
Site Address: 110 Luther Avenue		Zip Code: 13088
City/Town: Liverpool		
County: Onondaga		
Site Acreage: 1.4		
Reporting Period: November 16, 2011 to March 17, 2013 JANUARY 1, 2012 TO JUNE 30, 2013		
		YES NO
1. Is the information above correct?		<input checked="" type="checkbox"/> <input type="checkbox"/>
If NO, include handwritten above or on a separate sheet.		
2. Has some or all of the site property been sold, subdivided, merged, or undergone a tax map amendment during this Reporting Period?		<input type="checkbox"/> <input checked="" type="checkbox"/>
3. Has there been any change of use at the site during this Reporting Period (see 6NYCRR 375-1.11(d))?		<input type="checkbox"/> <input checked="" type="checkbox"/>
4. Have any federal, state, and/or local permits (e.g., building, discharge) been issued for or at the property during this Reporting Period?		<input type="checkbox"/> <input checked="" type="checkbox"/>
If you answered YES to questions 2 thru 4, include documentation or evidence that documentation has been previously submitted with this certification form.		
5. Is the site currently undergoing development?		<input type="checkbox"/> <input checked="" type="checkbox"/>

Box 2	
	YES NO
6. Is the current site use consistent with the use(s) listed below? Commercial and Industrial	<input checked="" type="checkbox"/> <input type="checkbox"/>
7. Are all ICs/ECs in place and functioning as designed?	<input checked="" type="checkbox"/> <input type="checkbox"/>
IF THE ANSWER TO EITHER QUESTION 6 OR 7 IS NO, sign and date below and DO NOT COMPLETE THE REST OF THIS FORM. Otherwise continue.	
A Corrective Measures Work Plan must be submitted along with this form to address these issues.	
Signature of Owner, Remedial Party or Designated Representative	Date
	7/8/13

Box 2A

8. Has any new information revealed that assumptions made in the Qualitative Exposure Assessment regarding offsite contamination are no longer valid?

YES NO

☐ ☒

If you answered YES to question 8, include documentation or evidence that documentation has been previously submitted with this certification form.

9. Are the assumptions in the Qualitative Exposure Assessment still valid?
(The Qualitative Exposure Assessment must be certified every five years)

☒ ☐

If you answered NO to question 9, the Periodic Review Report must include an updated Qualitative Exposure Assessment based on the new assumptions.

SITE NO. C734118**Box 3****Description of Institutional Controls**

<u>Parcel</u>	<u>Owner</u>	<u>Institutional Control</u>
085-12-04.1	Syracuse Label Co., Inc.	Ground Water Use Restriction IC/EC Plan Landuse Restriction Monitoring Plan O&M Plan Site Management Plan
085-12-05.0	Syracuse Label Co., Inc.	Ground Water Use Restriction IC/EC Plan Landuse Restriction Monitoring Plan O&M Plan Site Management Plan
085-12-06.1	Syracuse Label Co., Inc.	Ground Water Use Restriction IC/EC Plan Landuse Restriction Monitoring Plan O&M Plan Site Management Plan
085-12-08.0	Syracuse Label Co., Inc.	Ground Water Use Restriction IC/EC Plan Landuse Restriction Monitoring Plan O&M Plan Site Management Plan
085-12-09.0	Syracuse Label Co., Inc.	Ground Water Use Restriction IC/EC Plan Landuse Restriction Monitoring Plan O&M Plan Site Management Plan

Box 4

Description of Engineering Controls

<u>Parcel</u>	<u>Engineering Control</u>
085-12-04.1	Cover System Vapor Mitigation
085-12-05.0	Cover System Vapor Mitigation
085-12-06.1	Cover System Vapor Mitigation
085-12-08.0	Cover System Vapor Mitigation
085-12-09.0	Cover System Vapor Mitigation

Parcel

Engineering Control

Cover System
Vapor Mitigation

Engineering Control Details for Site No. C734118

Engineering Control Details for Site No. C734118

Parcel: 085-12-04.1

A sub-slab depressurization system (SSDS) was installed in the existing Site building in 2011. The SSDS is a high vacuum system utilizing fourteen (14) suction points positioned at location shown on Figure 9. Photographs of the system installation are included in Appendix B of this SMP. The fourteen (14) suction points are identified herein, and will be referenced in the future, as S-1, S-2, S-3, and S-4 (clockwise around warehouse starting in the southwest corner); S-5, S-6, and S-7 (south to north along office area wall); S-8 and S-9 (northeastern rooms of building), and S-10, S-11, S-12, S-13, and S-14 (southeastern rooms of building).

Each SSDS suction point consists of a 4 inch hole cored through the existing concrete slab. Each suction riser was constructed of 3 inch diameter schedule 40 polyvinyl chloride (PVC) piping. Each suction riser was connected to a single fan on the roof utilizing a trunk line network consisting of 4 inch diameter PVC piping. Each riser pipe is outfitted with a magnehelic pressure gauge, to allow for monitoring of system performance, and an interior baffle that can be adjusted to regulate airflow. All floor, wall, and roof penetrations were sealed with a VOC compliant urethane sealant. Design details are presented in the Operation and Maintenance Plan (Section 4 of this SMP).

Procedures for monitoring the system, including inspections in the event that an identified severe condition occurs, are included in the Monitoring Plan (Section 3 of this SMP). Procedures for operating and maintaining the SSDS are documented in the Operation and Maintenance Plan (Section 4 of this SMP).

A series of Institutional Controls is required by the RAWP to: (1) implement, maintain and monitor Engineering Control systems; (2) prevent future exposure to remaining contamination by controlling disturbances of the subsurface contamination; and, (3) limit the use and development of the Site to Commercial or Industrial uses only. Adherence to these Institutional Controls on the Site is required by the Environmental Easement and will be implemented under this Site Management Plan. These Institutional Controls are:

- Compliance with the Environmental Easement and this SMP by the Grantor and the Grantor's successors and assigns;
- All Engineering Controls must be operated and maintained as specified in this SMP;
- All Engineering Controls on the Controlled Property must be inspected at a frequency and in a manner defined in the SMP;
- Groundwater and other environmental or public health monitoring must be performed as defined in this SMP; and
- Data and information pertinent to Site Management of the Controlled Property must be reported at the frequency and in a manner defined in this SMP.

Institutional Controls identified in the Environmental Easement may not be discontinued without an amendment to or extinguishment of the Environmental Easement.

The Site has a series of Institutional Controls in the form of Site restrictions. Adherence to these Institutional Controls is required by the Environmental Easement. Site restrictions that apply to the Controlled Property are:

- The property may only be used for Commercial or Industrial use provided that the long-term Engineering and Institutional Controls included in this SMP are employed;
- The property may not be used for a higher level of use, such as unrestricted, residential, or restricted residential use without additional remediation and amendment of the Environmental Easement, as approved by the NYSDEC;
- All future activities on the property that will disturb remaining contaminated material must be conducted in accordance with this SMP and the Excavation Work Plan (Appendix C);
- The use of the groundwater underlying the property is prohibited without treatment rendering it safe for intended use;
- The potential for vapor intrusion must be evaluated for any buildings developed onsite, and any potential impacts that are identified must be monitored or mitigated;
- Vegetable gardens and farming on the property are prohibited;
- The Site owner or remedial party will submit to NYSDEC a written statement that certifies, under penalty of perjury, that: (1) controls employed at the Controlled Property are unchanged from the previous certification or that any changes to the controls were approved by the NYSDEC; and, (2) nothing has occurred that impairs the ability of the controls to protect public health and environment or that constitute a violation or failure to comply with the SMP. NYSDEC retains the right to access such Controlled Property at any time in order to evaluate the continued maintenance of any and all controls. This certification shall be submitted annually, or an alternate period of time that NYSDEC may allow and will be made by an expert that the NYSDEC finds acceptable; and
- The Site owner is required to monitor whether there is a change in ownership of the adjacent property currently owned by The Brannock Device Company, located at 116 Luther Avenue. If a change in ownership occurs the current owner will need to be notified of the environmental conditions of the 110

Engineering Control Details for Site No. C734118

Luther Avenue Site and afforded the option to evaluate the potential for soil vapor intrusion into the building. Notification must also be made to the NYSDEC if the adjacent property is sold or ownership is transferred.

2.3.1 Excavation Work Plan

The Site has been remediated for commercial use. Any future intrusive work that will encounter or disturb the remaining contamination, including any modifications or repairs to the existing cover system will be performed in compliance with the Excavation Work Plan (EWP) that is attached as Appendix C to this SMP. Any work conducted pursuant to the EWP must also be conducted in accordance with the procedures defined in a Health and Safety Plan (HASP) and Community Air Monitoring Plan (CAMP) prepared for the Site. A sample HASP and CAMP are attached as Appendix D to this SMP that is in current compliance with DER-10, and 29 CFR 1910, 29 CFR 1926, and all other applicable Federal, State and local regulations. Based on future changes to State and federal health and safety requirements, and specific methods employed by future contractors, the HASP and CAMP will be updated and re-submitted with the notification provided in Section C-1 of the EWP. Any intrusive construction work will be performed in compliance with the EWP, HASP and CAMP, and will be included in the periodic inspection and certification reports submitted under the Site Management Reporting Plan (See Section 5).

The Site owner and associated parties preparing the remedial documents submitted to the State, and parties performing this work, are completely responsible for the safe performance of all intrusive work, the structural integrity of excavations, proper disposal of excavation de-water, control of runoff from open excavations into remaining contamination, and for structures that may be affected by excavations (such as building foundations and bridge footings). The Site owner will ensure that Site development activities will not interfere with, or otherwise impair or compromise, the engineering controls described in this SMP.

2.3.2 Soil Vapor Intrusion Evaluation

Prior to the construction of any enclosed structures at the Site, an SVI evaluation will be performed to determine whether any mitigation measures are necessary to eliminate potential exposure to vapors in the proposed structure. Alternatively, an SVI mitigation system may be installed as an element of the building foundation without first conducting an investigation. This mitigation system will include a vapor barrier and passive sub-slab depressurization system that is capable of being converted to an active system.

Prior to conducting an SVI investigation or installing a mitigation system, a work plan will be developed and submitted to the NYSDEC and NYSDOH for approval. This work plan will be developed in accordance with the most recent NYSDOH "Guidance for Evaluating Vapor Intrusion in the State of New York". Measures to be employed to mitigate potential vapor intrusion will be evaluated, selected, designed, installed, and maintained based on the SVI evaluation, the NYSDOH guidance, and construction details of the proposed structure.

Preliminary (unvalidated) SVI sampling data will be forwarded to the NYSDEC and NYSDOH for initial review and interpretation. Upon validation, the final data will be transmitted to the agencies, along with a recommendation for follow-up action, such as mitigation. If any indoor air test results exceed NYSDOH guidelines, relevant NYSDOH fact sheets will be provided to all tenants and occupants of the property within 15 days of receipt of validated data.

SVI sampling results, evaluations, and follow-up actions will also be summarized in the next Periodic Review Report.

Engineering Control Details for Site No. C734118

Parcel: 085-12-05.0

A sub-slab depressurization system (SSDS) was installed in the existing Site building in 2011. The SSDS is a high vacuum system utilizing fourteen (14) suction points positioned at location shown on Figure 9. Photographs of the system installation are included in Appendix B of this SMP. The fourteen (14) suction points are identified herein, and will be referenced in the future, as S-1, S-2, S-3, and S-4 (clockwise around warehouse starting in the southwest corner); S-5, S-6, and S-7 (south to north along office area wall); S-8 and S-9 (northeastern rooms of building), and S-10, S-11, S-12, S-13, and S-14 (southeastern rooms of building).

Each SSDS suction point consists of a 4 inch hole cored through the existing concrete slab. Each suction riser was constructed of 3 inch diameter schedule 40 polyvinyl chloride (PVC) piping. Each suction riser was connected to a single fan on the roof utilizing a trunk line network consisting of 4 inch diameter PVC piping. Each riser pipe is outfitted with a magnehelic pressure gauge, to allow for monitoring of system performance, and an interior baffle that can be adjusted to regulate airflow. All floor, wall, and roof penetrations were sealed with a VOC compliant urethane sealant. Design details are presented in the Operation and Maintenance Plan (Section 4 of this SMP).

Procedures for monitoring the system, including inspections in the event that an identified severe condition occurs, are included in the Monitoring Plan (Section 3 of this SMP). Procedures for operating and maintaining the SSDS are documented in the Operation and Maintenance Plan (Section 4 of this SMP).

A series of Institutional Controls is required by the RAWP to: (1) implement, maintain and monitor Engineering Control systems; (2) prevent future exposure to remaining contamination by controlling disturbances of the subsurface contamination; and, (3) limit the use and development of the Site to Commercial or Industrial uses only. Adherence to these Institutional Controls on the Site is required by the Environmental Easement and will be implemented under this Site Management Plan. These Institutional Controls are:

- Compliance with the Environmental Easement and this SMP by the Grantor and the Grantor's successors and assigns;
- All Engineering Controls must be operated and maintained as specified in this SMP;
- All Engineering Controls on the Controlled Property must be inspected at a frequency and in a manner defined in the SMP;
- Groundwater and other environmental or public health monitoring must be performed as defined in this SMP; and
- Data and information pertinent to Site Management of the Controlled Property must be reported at the frequency and in a manner defined in this SMP.

Institutional Controls identified in the Environmental Easement may not be discontinued without an amendment to or extinguishment of the Environmental Easement.

The Site has a series of Institutional Controls in the form of Site restrictions. Adherence to these Institutional Controls is required by the Environmental Easement. Site restrictions that apply to the Controlled Property are:

- The property may only be used for Commercial or Industrial use provided that the long-term Engineering and Institutional Controls included in this SMP are employed;
- The property may not be used for a higher level of use, such as unrestricted, residential, or restricted residential use without additional remediation and amendment of the Environmental Easement, as approved by the NYSDEC;
- All future activities on the property that will disturb remaining contaminated material must be conducted in accordance with this SMP and the Excavation Work Plan (Appendix C);
- The use of the groundwater underlying the property is prohibited without treatment rendering it safe for intended use;
- The potential for vapor intrusion must be evaluated for any buildings developed onsite, and any potential impacts that are identified must be monitored or mitigated;
- Vegetable gardens and farming on the property are prohibited;
- The Site owner or remedial party will submit to NYSDEC a written statement that certifies, under penalty of perjury, that: (1) controls employed at the Controlled Property are unchanged from the previous certification or that any changes to the controls were approved by the NYSDEC; and, (2) nothing has occurred that impairs the ability of the controls to protect public health and environment or that constitute a violation or failure to comply with the SMP. NYSDEC retains the right to access such Controlled Property at any time in order to evaluate the continued maintenance of any and all controls. This certification shall be submitted annually, or an alternate period of time that NYSDEC may allow and will be made by an expert that the NYSDEC finds acceptable; and
- The Site owner is required to monitor whether there is a change in ownership of the adjacent property currently owned by The Brannock Device Company, located at 116 Luther Avenue. If a change in ownership occurs the current owner will need to be notified of the environmental conditions of the 110

Engineering Control Details for Site No. C734118

Luther Avenue Site and afforded the option to evaluate the potential for soil vapor intrusion into the building. Notification must also be made to the NYSDEC if the adjacent property is sold or ownership is transferred.

2.3.1 Excavation Work Plan

The Site has been remediated for commercial use. Any future intrusive work that will encounter or disturb the remaining contamination, including any modifications or repairs to the existing cover system will be performed in compliance with the Excavation Work Plan (EWP) that is attached as Appendix C to this SMP. Any work conducted pursuant to the EWP must also be conducted in accordance with the procedures defined in a Health and Safety Plan (HASP) and Community Air Monitoring Plan (CAMP) prepared for the Site. A sample HASP and CAMP are attached as Appendix D to this SMP that is in current compliance with DER-10, and 29 CFR 1910, 29 CFR 1926, and all other applicable Federal, State and local regulations. Based on future changes to State and federal health and safety requirements, and specific methods employed by future contractors, the HASP and CAMP will be updated and re-submitted with the notification provided in Section C-1 of the EWP. Any intrusive construction work will be performed in compliance with the EWP, HASP and CAMP, and will be included in the periodic inspection and certification reports submitted under the Site Management Reporting Plan (See Section 5).

The Site owner and associated parties preparing the remedial documents submitted to the State, and parties performing this work, are completely responsible for the safe performance of all intrusive work, the structural integrity of excavations, proper disposal of excavation de-water, control of runoff from open excavations into remaining contamination, and for structures that may be affected by excavations (such as building foundations and bridge footings). The Site owner will ensure that Site development activities will not interfere with, or otherwise impair or compromise, the engineering controls described in this SMP.

2.3.2 Soil Vapor Intrusion Evaluation

Prior to the construction of any enclosed structures at the Site, an SVI evaluation will be performed to determine whether any mitigation measures are necessary to eliminate potential exposure to vapors in the proposed structure. Alternatively, an SVI mitigation system may be installed as an element of the building foundation without first conducting an investigation. This mitigation system will include a vapor barrier and passive sub-slab depressurization system that is capable of being converted to an active system.

Prior to conducting an SVI investigation or installing a mitigation system, a work plan will be developed and submitted to the NYSDEC and NYSDOH for approval. This work plan will be developed in accordance with the most recent NYSDOH "Guidance for Evaluating Vapor Intrusion in the State of New York". Measures to be employed to mitigate potential vapor intrusion will be evaluated, selected, designed, installed, and maintained based on the SVI evaluation, the NYSDOH guidance, and construction details of the proposed structure.

Preliminary (unvalidated) SVI sampling data will be forwarded to the NYSDEC and NYSDOH for initial review and interpretation. Upon validation, the final data will be transmitted to the agencies, along with a recommendation for follow-up action, such as mitigation. If any indoor air test results exceed NYSDOH guidelines, relevant NYSDOH fact sheets will be provided to all tenants and occupants of the property within 15 days of receipt of validated data.

SVI sampling results, evaluations, and follow-up actions will also be summarized in the next Periodic Review Report.

Engineering Control Details for Site No. C734118

Parcel: 085-12-06.1

A sub-slab depressurization system (SSDS) was installed in the existing Site building in 2011. The SSDS is a high vacuum system utilizing fourteen (14) suction points positioned at location shown on Figure 9. Photographs of the system installation are included in Appendix B of this SMP. The fourteen (14) suction points are identified herein, and will be referenced in the future, as S-1, S-2, S-3, and S-4 (clockwise around warehouse starting in the southwest corner); S-5, S-6, and S-7 (south to north along office area wall); S-8 and S-9 (northeastern rooms of building), and S-10, S-11, S-12, S-13, and S-14 (southeastern rooms of building).

Each SSDS suction point consists of a 4 inch hole cored through the existing concrete slab. Each suction riser was constructed of 3 inch diameter schedule 40 polyvinyl chloride (PVC) piping. Each suction riser was connected to a single fan on the roof utilizing a trunk line network consisting of 4 inch diameter PVC piping. Each riser pipe is outfitted with a magnehelic pressure gauge, to allow for monitoring of system performance, and an interior baffle that can be adjusted to regulate airflow. All floor, wall, and roof penetrations were sealed with a VOC compliant urethane sealant. Design details are presented in the Operation and Maintenance Plan (Section 4 of this SMP).

Procedures for monitoring the system, including inspections in the event that an identified severe condition occurs, are included in the Monitoring Plan (Section 3 of this SMP). Procedures for operating and maintaining the SSDS are documented in the Operation and Maintenance Plan (Section 4 of this SMP).

A series of Institutional Controls is required by the RAWP to: (1) implement, maintain and monitor Engineering Control systems; (2) prevent future exposure to remaining contamination by controlling disturbances of the subsurface contamination; and, (3) limit the use and development of the Site to Commercial or Industrial uses only. Adherence to these Institutional Controls on the Site is required by the Environmental Easement and will be implemented under this Site Management Plan. These Institutional Controls are:

- Compliance with the Environmental Easement and this SMP by the Grantor and the Grantor's successors and assigns;
- All Engineering Controls must be operated and maintained as specified in this SMP;
- All Engineering Controls on the Controlled Property must be inspected at a frequency and in a manner defined in the SMP;
- Groundwater and other environmental or public health monitoring must be performed as defined in this SMP; and
- Data and information pertinent to Site Management of the Controlled Property must be reported at the frequency and in a manner defined in this SMP.

Institutional Controls identified in the Environmental Easement may not be discontinued without an amendment to or extinguishment of the Environmental Easement.

The Site has a series of Institutional Controls in the form of Site restrictions. Adherence to these Institutional Controls is required by the Environmental Easement. Site restrictions that apply to the Controlled Property are:

- The property may only be used for Commercial or Industrial use provided that the long-term Engineering and Institutional Controls included in this SMP are employed;
- The property may not be used for a higher level of use, such as unrestricted, residential, or restricted residential use without additional remediation and amendment of the Environmental Easement, as approved by the NYSDEC;
- All future activities on the property that will disturb remaining contaminated material must be conducted in accordance with this SMP and the Excavation Work Plan (Appendix C);
- The use of the groundwater underlying the property is prohibited without treatment rendering it safe for intended use;
- The potential for vapor intrusion must be evaluated for any buildings developed onsite, and any potential impacts that are identified must be monitored or mitigated;
- Vegetable gardens and farming on the property are prohibited;
- The Site owner or remedial party will submit to NYSDEC a written statement that certifies, under penalty of perjury, that: (1) controls employed at the Controlled Property are unchanged from the previous certification or that any changes to the controls were approved by the NYSDEC; and, (2) nothing has occurred that impairs the ability of the controls to protect public health and environment or that constitute a violation or failure to comply with the SMP. NYSDEC retains the right to access such Controlled Property at any time in order to evaluate the continued maintenance of any and all controls. This certification shall be submitted annually, or an alternate period of time that NYSDEC may allow and will be made by an expert that the NYSDEC finds acceptable; and
- The Site owner is required to monitor whether there is a change in ownership of the adjacent property currently owned by The Brannock Device Company, located at 116 Luther Avenue. If a change in ownership occurs the current owner will need to be notified of the environmental conditions of the 110

Engineering Control Details for Site No. C734118

Luther Avenue Site and afforded the option to evaluate the potential for soil vapor intrusion into the building. Notification must also be made to the NYSDEC if the adjacent property is sold or ownership is transferred.

2.3.1 Excavation Work Plan

The Site has been remediated for commercial use. Any future intrusive work that will encounter or disturb the remaining contamination, including any modifications or repairs to the existing cover system will be performed in compliance with the Excavation Work Plan (EWP) that is attached as Appendix C to this SMP. Any work conducted pursuant to the EWP must also be conducted in accordance with the procedures defined in a Health and Safety Plan (HASP) and Community Air Monitoring Plan (CAMP) prepared for the Site. A sample HASP and CAMP are attached as Appendix D to this SMP that is in current compliance with DER-10, and 29 CFR 1910, 29 CFR 1926, and all other applicable Federal, State and local regulations. Based on future changes to State and federal health and safety requirements, and specific methods employed by future contractors, the HASP and CAMP will be updated and re-submitted with the notification provided in Section C-1 of the EWP. Any intrusive construction work will be performed in compliance with the EWP, HASP and CAMP, and will be included in the periodic inspection and certification reports submitted under the Site Management Reporting Plan (See Section 5).

The Site owner and associated parties preparing the remedial documents submitted to the State, and parties performing this work, are completely responsible for the safe performance of all intrusive work, the structural integrity of excavations, proper disposal of excavation de-water, control of runoff from open excavations into remaining contamination, and for structures that may be affected by excavations (such as building foundations and bridge footings). The Site owner will ensure that Site development activities will not interfere with, or otherwise impair or compromise, the engineering controls described in this SMP.

2.3.2 Soil Vapor Intrusion Evaluation

Prior to the construction of any enclosed structures at the Site, an SVI evaluation will be performed to determine whether any mitigation measures are necessary to eliminate potential exposure to vapors in the proposed structure. Alternatively, an SVI mitigation system may be installed as an element of the building foundation without first conducting an investigation. This mitigation system will include a vapor barrier and passive sub-slab depressurization system that is capable of being converted to an active system.

Prior to conducting an SVI investigation or installing a mitigation system, a work plan will be developed and submitted to the NYSDEC and NYSDOH for approval. This work plan will be developed in accordance with the most recent NYSDOH "Guidance for Evaluating Vapor Intrusion in the State of New York". Measures to be employed to mitigate potential vapor intrusion will be evaluated, selected, designed, installed, and maintained based on the SVI evaluation, the NYSDOH guidance, and construction details of the proposed structure.

Preliminary (unvalidated) SVI sampling data will be forwarded to the NYSDEC and NYSDOH for initial review and interpretation. Upon validation, the final data will be transmitted to the agencies, along with a recommendation for follow-up action, such as mitigation. If any indoor air test results exceed NYSDOH guidelines, relevant NYSDOH fact sheets will be provided to all tenants and occupants of the property within 15 days of receipt of validated data.

SVI sampling results, evaluations, and follow-up actions will also be summarized in the next Periodic Review Report.

Engineering Control Details for Site No. C734118

Parcel: 085-12-08.0

A sub-slab depressurization system (SSDS) was installed in the existing Site building in 2011. The SSDS is a high vacuum system utilizing fourteen (14) suction points positioned at location shown on Figure 9. Photographs of the system installation are included in Appendix B of this SMP. The fourteen (14) suction points are identified herein, and will be referenced in the future, as S-1, S-2, S-3, and S-4 (clockwise around warehouse starting in the southwest corner); S-5, S-6, and S-7 (south to north along office area wall); S-8 and S-9 (northeastern rooms of building), and S-10, S-11, S-12, S-13, and S-14 (southeastern rooms of building).

Each SSDS suction point consists of a 4 inch hole cored through the existing concrete slab. Each suction riser was constructed of 3 inch diameter schedule 40 polyvinyl chloride (PVC) piping. Each suction riser was connected to a single fan on the roof utilizing a trunk line network consisting of 4 inch diameter PVC piping. Each riser pipe is outfitted with a magnehelic pressure gauge, to allow for monitoring of system performance, and an interior baffle that can be adjusted to regulate airflow. All floor, wall, and roof penetrations were sealed with a VOC compliant urethane sealant. Design details are presented in the Operation and Maintenance Plan (Section 4 of this SMP).

Procedures for monitoring the system, including inspections in the event that an identified severe condition occurs, are included in the Monitoring Plan (Section 3 of this SMP). Procedures for operating and maintaining the SSDS are documented in the Operation and Maintenance Plan (Section 4 of this SMP).

A series of Institutional Controls is required by the RAWP to: (1) implement, maintain and monitor Engineering Control systems; (2) prevent future exposure to remaining contamination by controlling disturbances of the subsurface contamination; and, (3) limit the use and development of the Site to Commercial or Industrial uses only. Adherence to these Institutional Controls on the Site is required by the Environmental Easement and will be implemented under this Site Management Plan. These Institutional Controls are:

- Compliance with the Environmental Easement and this SMP by the Grantor and the Grantor's successors and assigns;
- All Engineering Controls must be operated and maintained as specified in this SMP;
- All Engineering Controls on the Controlled Property must be inspected at a frequency and in a manner defined in the SMP;
- Groundwater and other environmental or public health monitoring must be performed as defined in this SMP; and
- Data and information pertinent to Site Management of the Controlled Property must be reported at the frequency and in a manner defined in this SMP.

Institutional Controls identified in the Environmental Easement may not be discontinued without an amendment to or extinguishment of the Environmental Easement.

The Site has a series of Institutional Controls in the form of Site restrictions. Adherence to these Institutional Controls is required by the Environmental Easement. Site restrictions that apply to the Controlled Property are:

- The property may only be used for Commercial or Industrial use provided that the long-term Engineering and Institutional Controls included in this SMP are employed;
- The property may not be used for a higher level of use, such as unrestricted, residential, or restricted residential use without additional remediation and amendment of the Environmental Easement, as approved by the NYSDEC;
- All future activities on the property that will disturb remaining contaminated material must be conducted in accordance with this SMP and the Excavation Work Plan (Appendix C);
- The use of the groundwater underlying the property is prohibited without treatment rendering it safe for intended use;
- The potential for vapor intrusion must be evaluated for any buildings developed onsite, and any potential impacts that are identified must be monitored or mitigated;
- Vegetable gardens and farming on the property are prohibited;
- The Site owner or remedial party will submit to NYSDEC a written statement that certifies, under penalty of perjury, that: (1) controls employed at the Controlled Property are unchanged from the previous certification or that any changes to the controls were approved by the NYSDEC; and, (2) nothing has occurred that impairs the ability of the controls to protect public health and environment or that constitute a violation or failure to comply with the SMP. NYSDEC retains the right to access such Controlled Property at any time in order to evaluate the continued maintenance of any and all controls. This certification shall be submitted annually, or an alternate period of time that NYSDEC may allow and will be made by an expert that the NYSDEC finds acceptable; and
- The Site owner is required to monitor whether there is a change in ownership of the adjacent property currently owned by The Brannock Device Company, located at 116 Luther Avenue. If a change in ownership occurs the current owner will need to be notified of the environmental conditions of the 110

Engineering Control Details for Site No. C734118

Luther Avenue Site and afforded the option to evaluate the potential for soil vapor intrusion into the building. Notification must also be made to the NYSDEC if the adjacent property is sold or ownership is transferred.

2.3.1 Excavation Work Plan

The Site has been remediated for commercial use. Any future intrusive work that will encounter or disturb the remaining contamination, including any modifications or repairs to the existing cover system will be performed in compliance with the Excavation Work Plan (EWP) that is attached as Appendix C to this SMP. Any work conducted pursuant to the EWP must also be conducted in accordance with the procedures defined in a Health and Safety Plan (HASP) and Community Air Monitoring Plan (CAMP) prepared for the Site. A sample HASP and CAMP are attached as Appendix D to this SMP that is in current compliance with DER-10, and 29 CFR 1910, 29 CFR 1926, and all other applicable Federal, State and local regulations. Based on future changes to State and federal health and safety requirements, and specific methods employed by future contractors, the HASP and CAMP will be updated and re-submitted with the notification provided in Section C-1 of the EWP. Any intrusive construction work will be performed in compliance with the EWP, HASP and CAMP, and will be included in the periodic inspection and certification reports submitted under the Site Management Reporting Plan (See Section 5).

The Site owner and associated parties preparing the remedial documents submitted to the State, and parties performing this work, are completely responsible for the safe performance of all intrusive work, the structural integrity of excavations, proper disposal of excavation de-water, control of runoff from open excavations into remaining contamination, and for structures that may be affected by excavations (such as building foundations and bridge footings). The Site owner will ensure that Site development activities will not interfere with, or otherwise impair or compromise, the engineering controls described in this SMP.

2.3.2 Soil Vapor Intrusion Evaluation

Prior to the construction of any enclosed structures at the Site, an SVI evaluation will be performed to determine whether any mitigation measures are necessary to eliminate potential exposure to vapors in the proposed structure. Alternatively, an SVI mitigation system may be installed as an element of the building foundation without first conducting an investigation. This mitigation system will include a vapor barrier and passive sub-slab depressurization system that is capable of being converted to an active system.

Prior to conducting an SVI investigation or installing a mitigation system, a work plan will be developed and submitted to the NYSDEC and NYSDOH for approval. This work plan will be developed in accordance with the most recent NYSDOH "Guidance for Evaluating Vapor Intrusion in the State of New York". Measures to be employed to mitigate potential vapor intrusion will be evaluated, selected, designed, installed, and maintained based on the SVI evaluation, the NYSDOH guidance, and construction details of the proposed structure.

Preliminary (unvalidated) SVI sampling data will be forwarded to the NYSDEC and NYSDOH for initial review and interpretation. Upon validation, the final data will be transmitted to the agencies, along with a recommendation for follow-up action, such as mitigation. If any indoor air test results exceed NYSDOH guidelines, relevant NYSDOH fact sheets will be provided to all tenants and occupants of the property within 15 days of receipt of validated data.

SVI sampling results, evaluations, and follow-up actions will also be summarized in the next Periodic Review Report.

Engineering Control Details for Site No. C734118

Parcel: 085-12-09.0

A sub-slab depressurization system (SSDS) was installed in the existing Site building in 2011. The SSDS is a high vacuum system utilizing fourteen (14) suction points positioned at location shown on Figure 9. Photographs of the system installation are included in Appendix B of this SMP. The fourteen (14) suction points are identified herein, and will be referenced in the future, as S-1, S-2, S-3, and S-4 (clockwise around warehouse starting in the southwest corner); S-5, S-6, and S-7 (south to north along office area wall); S-8 and S-9 (northeastern rooms of building), and S-10, S-11, S-12, S-13, and S-14 (southeastern rooms of building).

Each SSDS suction point consists of a 4 inch hole cored through the existing concrete slab. Each suction riser was constructed of 3 inch diameter schedule 40 polyvinyl chloride (PVC) piping. Each suction riser was connected to a single fan on the roof utilizing a trunk line network consisting of 4 inch diameter PVC piping. Each riser pipe is outfitted with a magnehelic pressure gauge, to allow for monitoring of system performance, and an interior baffle that can be adjusted to regulate airflow. All floor, wall, and roof penetrations were sealed with a VOC compliant urethane sealant. Design details are presented in the Operation and Maintenance Plan (Section 4 of this SMP).

Procedures for monitoring the system, including inspections in the event that an identified severe condition occurs, are included in the Monitoring Plan (Section 3 of this SMP). Procedures for operating and maintaining the SSDS are documented in the Operation and Maintenance Plan (Section 4 of this SMP).

A series of Institutional Controls is required by the RAWP to: (1) implement, maintain and monitor Engineering Control systems; (2) prevent future exposure to remaining contamination by controlling disturbances of the subsurface contamination; and, (3) limit the use and development of the Site to Commercial or Industrial uses only. Adherence to these Institutional Controls on the Site is required by the Environmental Easement and will be implemented under this Site Management Plan. These Institutional Controls are:

- Compliance with the Environmental Easement and this SMP by the Grantor and the Grantor's successors and assigns;
- All Engineering Controls must be operated and maintained as specified in this SMP;
- All Engineering Controls on the Controlled Property must be inspected at a frequency and in a manner defined in the SMP;
- Groundwater and other environmental or public health monitoring must be performed as defined in this SMP; and
- Data and information pertinent to Site Management of the Controlled Property must be reported at the frequency and in a manner defined in this SMP.

Institutional Controls identified in the Environmental Easement may not be discontinued without an amendment to or extinguishment of the Environmental Easement.

The Site has a series of Institutional Controls in the form of Site restrictions. Adherence to these Institutional Controls is required by the Environmental Easement. Site restrictions that apply to the Controlled Property are:

- The property may only be used for Commercial or Industrial use provided that the long-term Engineering and Institutional Controls included in this SMP are employed;
- The property may not be used for a higher level of use, such as unrestricted, residential, or restricted residential use without additional remediation and amendment of the Environmental Easement, as approved by the NYSDEC;
- All future activities on the property that will disturb remaining contaminated material must be conducted in accordance with this SMP and the Excavation Work Plan (Appendix C);
- The use of the groundwater underlying the property is prohibited without treatment rendering it safe for intended use;
- The potential for vapor intrusion must be evaluated for any buildings developed onsite, and any potential impacts that are identified must be monitored or mitigated;
- Vegetable gardens and farming on the property are prohibited;
- The Site owner or remedial party will submit to NYSDEC a written statement that certifies, under penalty of perjury, that: (1) controls employed at the Controlled Property are unchanged from the previous certification or that any changes to the controls were approved by the NYSDEC; and, (2) nothing has occurred that impairs the ability of the controls to protect public health and environment or that constitute a violation or failure to comply with the SMP. NYSDEC retains the right to access such Controlled Property at any time in order to evaluate the continued maintenance of any and all controls. This certification shall be submitted annually, or an alternate period of time that NYSDEC may allow and will be made by an expert that the NYSDEC finds acceptable; and
- The Site owner is required to monitor whether there is a change in ownership of the adjacent property currently owned by The Brannock Device Company, located at 116 Luther Avenue. If a change in ownership occurs the current owner will need to be notified of the environmental conditions of the 110

Engineering Control Details for Site No. C734118

Luther Avenue Site and afforded the option to evaluate the potential for soil vapor intrusion into the building. Notification must also be made to the NYSDEC if the adjacent property is sold or ownership is transferred.

2.3.1 Excavation Work Plan

The Site has been remediated for commercial use. Any future intrusive work that will encounter or disturb the remaining contamination, including any modifications or repairs to the existing cover system will be performed in compliance with the Excavation Work Plan (EWP) that is attached as Appendix C to this SMP. Any work conducted pursuant to the EWP must also be conducted in accordance with the procedures defined in a Health and Safety Plan (HASP) and Community Air Monitoring Plan (CAMP) prepared for the Site. A sample HASP and CAMP are attached as Appendix D to this SMP that is in current compliance with DER-10, and 29 CFR 1910, 29 CFR 1926, and all other applicable Federal, State and local regulations. Based on future changes to State and federal health and safety requirements, and specific methods employed by future contractors, the HASP and CAMP will be updated and re-submitted with the notification provided in Section C-1 of the EWP. Any intrusive construction work will be performed in compliance with the EWP, HASP and CAMP, and will be included in the periodic inspection and certification reports submitted under the Site Management Reporting Plan (See Section 5).

The Site owner and associated parties preparing the remedial documents submitted to the State, and parties performing this work, are completely responsible for the safe performance of all intrusive work, the structural integrity of excavations, proper disposal of excavation de-water, control of runoff from open excavations into remaining contamination, and for structures that may be affected by excavations (such as building foundations and bridge footings). The Site owner will ensure that Site development activities will not interfere with, or otherwise impair or compromise, the engineering controls described in this SMP.

2.3.2 Soil Vapor Intrusion Evaluation

Prior to the construction of any enclosed structures at the Site, an SVI evaluation will be performed to determine whether any mitigation measures are necessary to eliminate potential exposure to vapors in the proposed structure. Alternatively, an SVI mitigation system may be installed as an element of the building foundation without first conducting an investigation. This mitigation system will include a vapor barrier and passive sub-slab depressurization system that is capable of being converted to an active system.

Prior to conducting an SVI investigation or installing a mitigation system, a work plan will be developed and submitted to the NYSDEC and NYSDOH for approval. This work plan will be developed in accordance with the most recent NYSDOH "Guidance for Evaluating Vapor Intrusion in the State of New York". Measures to be employed to mitigate potential vapor intrusion will be evaluated, selected, designed, installed, and maintained based on the SVI evaluation, the NYSDOH guidance, and construction details of the proposed structure.

Preliminary (unvalidated) SVI sampling data will be forwarded to the NYSDEC and NYSDOH for initial review and interpretation. Upon validation, the final data will be transmitted to the agencies, along with a recommendation for follow-up action, such as mitigation. If any indoor air test results exceed NYSDOH guidelines, relevant NYSDOH fact sheets will be provided to all tenants and occupants of the property within 15 days of receipt of validated data.

SVI sampling results, evaluations, and follow-up actions will also be summarized in the next Periodic Review Report.

Periodic Review Report (PRR) Certification Statements

1. I certify by checking "YES" below that:

a) the Periodic Review report and all attachments were prepared under the direction of, and reviewed by, the party making the certification;

b) to the best of my knowledge and belief, the work and conclusions described in this certification are in accordance with the requirements of the site remedial program, and generally accepted engineering practices; and the information presented is accurate and complete.

YES NO

☒ ☐

2. If this site has an IC/EC Plan (or equivalent as required in the Decision Document), for each Institutional or Engineering control listed in Boxes 3 and/or 4, I certify by checking "YES" below that all of the following statements are true:

(a) the Institutional Control and/or Engineering Control(s) employed at this site is unchanged since the date that the Control was put in-place, or was last approved by the Department;

(b) nothing has occurred that would impair the ability of such Control, to protect public health and the environment;

(c) access to the site will continue to be provided to the Department, to evaluate the remedy, including access to evaluate the continued maintenance of this Control;

(d) nothing has occurred that would constitute a violation or failure to comply with the Site Management Plan for this Control; and

(e) if a financial assurance mechanism is required by the oversight document for the site, the mechanism remains valid and sufficient for its intended purpose established in the document. NA

YES NO

☒ ☐

**IF THE ANSWER TO QUESTION 2 IS NO, sign and date below and
DO NOT COMPLETE THE REST OF THIS FORM. Otherwise continue.**

A Corrective Measures Work Plan must be submitted along with this form to address these issues.

Wage S. McDaniel
Signature of Owner, Remedial Party or Designated Representative

7/8/13
Date

IC CERTIFICATIONS
SITE NO. C734118

Box 6

SITE OWNER OR DESIGNATED REPRESENTATIVE SIGNATURE

I certify that all information and statements in Boxes 1, 2, and 3 are true. I understand that a false statement made herein is punishable as a Class "A" misdemeanor, pursuant to Section 210.45 of the Penal Law.

Kathleen Alaimo at 110 Luther Ave Liverpool, NY 13088
print name print business address

am certifying as Owner (Owner or Remedial Party)

for the Site named in the Site Details Section of this form.

Kathleen Alaimo
Signature of Owner, Remedial Party, or Designated Representative
Rendering Certification

7/11/13
Date

IC/EC CERTIFICATIONS


Box 7

Professional Engineer Signature

I certify that all information in Boxes 4 and 5 are true. I understand that a false statement made herein is punishable as a Class "A" misdemeanor, pursuant to Section 210.45 of the Penal Law.

I WAYNE MCFARLAND at 1 REMINGTON PARK DRIVE, CATZENDUWA, NY
print name print business address

am certifying as a Professional Engineer for the SPRAWSE LABEL
(Owner or Remedial Party)



Wayne E. McFarland
Signature of Professional Engineer, for the Owner or Remedial Party, Rendering Certification

Stamp
(Required for PE)

7/8/13
Date

Appendix B - Property Ownership Information for Adjoining Property



Department of Finance
Office of Real Property
Services



Image Mate Online

Navigation GIS Map Tax Maps | ORPS Links Assessment Info

Help Log In

Commercial

Property Info

Owner/Sales

Inventory

Improvements

Report

Comparables

Tax Info

Tax data not available. Some or all of the systems serving the requested information may be down for maintenance at this time.

Municipality of Town of Salina

SWIS: 314889 Tax ID: 085.-12-10.0

Property #:

Ownership Information

Name	Address
Leonardi Salvatore A Jr	116 Luther Ave Liverpool NY 13088-6726

Sale Information

Sale Date	Price	Property Class	Sale Type	Prior Owner
7/12/1995	\$125,000	710 - Manufacture	Land & Building	Masterpol Nicholas J
	Value Usable	Arms Length	Deed Book	Deed Page
	Yes	Yes	4013	42

Sale Date	Price	Property Class	Sale Type	Prior Owner
1/4/1995	\$75,000	710 - Manufacture	Land & Building	Krull Duane
	Value Usable	Arms Length	Deed Book	Deed Page
	Yes	Yes	3977	76

Photographs

No Photo Available

Tax Bills

(Select tax bill from list, click button.)

2013 Town & County Tax
2012 Town & County Tax
2012-2013 School Tax
2011 Town & County Tax
2011-2012 School Tax

Show Tax Bill

Pictometry LiveLink

View this property's Pictometry imagery in LiveLink.

Documents

No documents found for this parcel

Maps

View Tax Map

Pin Property on GIS Map

View in Google Maps

View in Yahoo! Maps

View in Bing Maps

Map Disclaimer

Appendix C - Sub-Slab Depressurization System Inspection Checklists

Sub-Slab Depressurization System

Inspection Checklist

Syracuse Label, 110 Luther Avenue, Liverpool, NY

Date: 1-10-12
 Insepectors Name: Kevin Gagnon
 Company: SYRLSP
 Inspector Initials: KG

I. Pressure Readings

Suction Riser Identification	Pressure Reading (inWC)
S-1	<u>3.0</u>
S-2	<u>3.0</u>
S-3	<u>6.5</u>
S-4	<u>5.0</u>
S-5	<u>3.5</u>
S-6	<u>3.0</u>
S-7	<u>3.0</u>
S-8	<u>4.5</u>
S-9	<u>2.0</u>
S-10	<u>2.25</u>
S-11	<u>2.0</u>
S-12	<u>2.25</u>
S-13	<u>2.5</u>
S-14	<u>2.0</u>

II. Fan Inspection

- | | | | | |
|--|---|----------|---|----------|
| 1. Operational? | Y | <u>X</u> | N | ___ |
| 2. Fan/Controls Clear of obstructions? | Y | <u>X</u> | N | ___ |
| 3. Rapair needs? | Y | ___ | N | <u>X</u> |

A. Observations/comments:

Attach photographs as appropriate

Notes:

Locations of suction risers can be found on attached Figure.
 System details are included in Appendix B.

III. Piping/Penetrations

1. Is piping intact? (Y or N)
 2. Are floor/wall penetrations sealed? (Y or N)

If 'No' to either of the above, provide observations and describe corrective actions taken

B. Actions taken:

C. Recommended Maintenance/Repairs:

Do any of the pressure gages require repair or replacement?
 If so, indicate locations, and actions taken:

Y ___ N X

IV. Building Modifications: Have building modifications been made that could affect the operation of the SSD System? (Describe)

None at this time

Additional Comments:

Checked Condensation trap - No water at all.

Kevin Gagnon

Report all maintenance/repair needs immediately to building facility manager

Sub-Slab Depressurization System

Inspection Checklist

Syracuse Label, 110 Luther Avenue, Liverpool, NY

Date:

2/16/12

Inspector's Name:

Kevin Gagnon

Company:

SYRLSP

Inspector Initials:

KG

I. Pressure Readings

Suction Riser Identification	Pressure Reading (inWC)
S-1	3.0
S-2	3.0
S-3	5.7
S-4	5.0
S-5	3.5
S-6	3.0
S-7	2.0
S-8	4.5
S-9	2.0
S-10	2.1
S-11	2.0
S-12	2.0
S-13	2.4
S-14	2.0

II. Fan Inspection

- | | | | | |
|--|---|----------|---|----------|
| 1. Operational? | Y | <u>X</u> | N | ___ |
| 2. Fan/Controls Clear of obstructions? | Y | <u>X</u> | N | ___ |
| 3. Repair needs? | Y | ___ | N | <u>X</u> |

A. Observations/comments:

Attach photographs as appropriate

Notes:

Locations of suction risers can be found on attached Figure.

System details are included in Appendix B.

III. Piping/Penetrations

1. Is piping intact? (Y) or (N)
2. Are floor/wall penetrations sealed? (Y) or (N)

If 'No' to either of the above, provide observations and describe corrective actions taken

B. Actions taken:

C. Recommended Maintenance/Repairs:

Do any of the pressure gages require repair or replacement?
If so, indicate locations, and actions taken:

Y ___ N X

IV. Building Modifications: Have building modifications been made that could affect the operation of the SSD System? (Describe)

None at this time

Additional Comments:

Checked Condensation trap - NO water at all

KG

Report all maintenance/repair needs immediately to building facility manager

Sub-Slab Depressurization System

Inspection Checklist

Syracuse Label, 110 Luther Avenue, Liverpool, NY

Date:

3/26/12

Inspector's Name:

Kevin Gagnon

Company:

SYRCLSP

Inspector Initials:

KG

I. Pressure Readings

Suction Riser Identification	Pressure Reading (inWC)
S-1	3.0
S-2	3.0
S-3	5.4
S-4	5.0
S-5	3.5
S-6	3.0
S-7	2.1
S-8	4.5
S-9	2.0
S-10	2.3
S-11	2.1
S-12	2.1
S-13	2.4
S-14	2.1

II. Fan Inspection

1. Operational?	Y	X	N	
2. Fan/Controls Clear of obstructions?	Y	X	N	
3. Repair needs?	Y		N	X

A. Observations/comments:

Attach photographs as appropriate

Notes:

Locations of suction risers can be found on attached Figure.

System details are included in Appendix B.

III. Piping/Penetrations

1. Is piping intact? (Y or N)
2. Are floor/wall penetrations sealed? (Y or N)

If 'No' to either of the above, provide observations and describe corrective actions taken

B. Actions taken:

C. Recommended Maintenance/Repairs:

Do any of the pressure gages require repair or replacement?
If so, indicate locations, and actions taken:

Y ___ N X

IV. Building Modifications: Have building modifications been made that could affect the operation of the SSD System? (Describe)

None at this time. (KG)

Additional Comments:

Checked condensation trap - no water at all (KG)

Report all maintenance/repair needs immediately to building facility manager

Sub-Slab Depressurization System

Inspection Checklist

Syracuse Label, 110 Luther Avenue, Liverpool, NY

Date: 4/25/12
 Inspectors Name: Kevin Gagnon
 Company: SYRLSP
 Inspector Initials: KG

I. Pressure Readings

Suction Riser Identification	Pressure Reading (inWC)
S-1	<u>3.0</u>
S-2	<u>3.0</u>
S-3	<u>5.5</u>
S-4	<u>5.0</u>
S-5	<u>3.5</u>
S-6	<u>3.0</u>
S-7	<u>2.0</u>
S-8	<u>4.5</u>
S-9	<u>2.0</u>
S-10	<u>2.3</u>
S-11	<u>2.1</u>
S-12	<u>2.1</u>
S-13	<u>2.7</u>
S-14	<u>2.1</u>

II. Fan Inspection

- | | | | | |
|--|---|----------|---|----------|
| 1. Operational? | Y | <u>X</u> | N | ___ |
| 2. Fan/Controls Clear of obstructions? | Y | <u>X</u> | N | ___ |
| 3. Repair needs? | Y | ___ | N | <u>X</u> |

A. Observations/comments:

Attach photographs as appropriate

Notes:

Locations of suction risers can be found on attached Figure.

System details are included in Appendix B.

III. Piping/Penetrations

- Is piping intact? (Y or N)
- Are floor/wall penetrations sealed? (Y or N)

If 'No' to either of the above, provide observations and describe corrective actions taken

B. Actions taken:

C. Recommended Maintenance/Repairs:

Do any of the pressure gages require repair or replacement?
 If so, indicate locations, and actions taken:

Y ___ N X

IV. Building Modifications: Have building modifications been made that could affect the operation of the SSD System? (Describe)

None at this time (KG)

Additional Comments:

Checked Condensation trap NO water at all (KG)

Report all maintenance/repair needs immediately to building facility manager

Sub-Slab Depressurization System

Inspection Checklist

Syracuse Label, 110 Luther Avenue, Liverpool, NY

Date:

5/23/12

Inspector's Name:

Kevin Gagnon

Company:

SYRLSP

Inspector Initials:

KG

I. Pressure Readings

Suction Riser Identification	Pressure Reading (inWC)
S-1	3.0
S-2	3.0
S-3	5.5
S-4	5.0
S-5	3.5
S-6	3.0
S-7	2.0
S-8	4.5
S-9	2.0
S-10	2.4
S-11	2.2
S-12	2.3
S-13	2.4
S-14	2.2

II. Fan Inspection

- | | | | | |
|--|---|-------------------------------------|---|-------------------------------------|
| 1. Operational? | Y | <input checked="" type="checkbox"/> | N | <input type="checkbox"/> |
| 2. Fan/Controls Clear of obstructions? | Y | <input checked="" type="checkbox"/> | N | <input type="checkbox"/> |
| 3. Repair needs? | Y | <input type="checkbox"/> | N | <input checked="" type="checkbox"/> |

A. Observations/comments:

Attach photographs as appropriate

Notes:

Locations of suction risers can be found on attached Figure.

System details are included in Appendix B.

III. Piping/Penetrations

1. Is piping intact? (Y or N)
2. Are floor/wall penetrations sealed? (Y or N)

If 'No' to either of the above, provide observations and describe corrective actions taken

B. Actions taken:

C. Recommended Maintenance/Repairs:

Do any of the pressure gages require repair or replacement?

Y ☐ N ☒

If so, indicate locations, and actions taken:

IV. Building Modifications: Have building modifications been made that could affect the operation of the SSD System? (Describe)

NO - None at this time. (KG)

Additional Comments:

Checked condensation trap - NO water at all (KG)

Report all maintenance/repair needs immediately to building facility manager

Sub-Slab Depressurization System

Inspection Checklist

Syracuse Label, 110 Luther Avenue, Liverpool, NY

Date:

6/25/12

Inspectors Name:

Kevin Gagnon

Company:

SRLSP

Inspector Initials:

KG

I. Pressure Readings

Suction Riser Identification	Pressure Reading (inWC)
S-1	3.0
S-2	2.9
S-3	5.5
S-4	4.9
S-5	3.2
S-6	2.9
S-7	2.0
S-8	4.5
S-9	1.9
S-10	2.1
S-11	2.1
S-12	2.1
S-13	2.3
S-14	2.1

II. Fan Inspection

- | | | | | |
|--|---|-------------------------------------|---|-------------------------------------|
| 1. Operational? | Y | <input checked="" type="checkbox"/> | N | <input type="checkbox"/> |
| 2. Fan/Controls Clear of obstructions? | Y | <input checked="" type="checkbox"/> | N | <input type="checkbox"/> |
| 3. Repair needs? | Y | <input type="checkbox"/> | N | <input checked="" type="checkbox"/> |

A. Observations/comments:

Attach photographs as appropriate

Notes:

Locations of suction risers can be found on attached Figure.

System details are included in Appendix B.

III. Piping/Penetrations

1. Is piping intact? (Y or N) ☒ Y ☐ N
2. Are floor/wall penetrations sealed? (Y or N) ☒ Y ☐ N

If 'No' to either of the above, provide observations and describe corrective actions taken

B. Actions taken:

C. Recommended Maintenance/Repairs:

Do any of the pressure gages require repair or replacement?
If so, indicate locations, and actions taken:

Y ☐ N ☒

IV. Building Modifications: Have building modifications been made that could affect the operation of the SSD System? (Describe)

No - None at this time

Additional Comments:

Check Condensation trap - NO water

Report all maintenance/repair needs immediately to building facility manager

Sub-Slab Depressurization System

Inspection Checklist

Syracuse Label, 110 Luther Avenue, Liverpool, NY

Date:

7/30/12

Inspector's Name:

Kevin Gannon

Company:

SVRLSP

Inspector Initials:

KG

I. Pressure Readings

Suction Riser Identification	Pressure Reading (inWC)
S-1	3.0
S-2	3.0
S-3	5.5
S-4	4.9
S-5	3.2
S-6	2.9
S-7	2.1
S-8	4.5
S-9	1.9
S-10	2.1
S-11	2.0
S-12	2.1
S-13	2.3
S-14	2.1

II. Fan Inspection

- Operational? Y ☒ N ☐
- Fan/Controls Clear of obstructions? Y ☒ N ☐
- Repair needs? Y ☐ N ☒

A. Observations/comments:

Attach photographs as appropriate

Notes:

Locations of suction risers can be found on attached Figure.

System details are included in Appendix B.

III. Piping/Penetrations

- Is piping intact? (Y or N) ☒
- Are floor/wall penetrations sealed? (Y or N) ☒

If 'No' to either of the above, provide observations and describe corrective actions taken

B. Actions taken:

C. Recommended Maintenance/Repairs:

Do any of the pressure gages require repair or replacement?

Y ☐ N ☒

If so, indicate locations, and actions taken:

IV. Building Modifications: Have building modifications been made that could affect the operation of the SSD System? (Describe)

No - None at this time KG

Additional Comments:

Checked condensation trap - NO Water KG

Report all maintenance/repair needs immediately to building facility manager

Sub-Slab Depressurization System

Inspection Checklist

Syracuse Label, 110 Luther Avenue, Liverpool, NY

Date:

8.31.12

Inspector's Name:

Kevin Jagan

Company:

Syr. Label Co

Inspector Initials:

KJ

I. Pressure Readings

Suction Riser Identification	Pressure Reading (inWC)
S-1	4.0
S-2	2.8
S-3	5.4
S-4	4.7
S-5	3.1
S-6	2.9
S-7	2.0
S-8	4.3
S-9	1.9
S-10	2.1
S-11	2.0
S-12	2.0
S-13	2.2
S-14	2.0

II. Fan Inspection

- | | | | | |
|--|---|-----|---|-----|
| 1. Operational? | Y | X | N | ___ |
| 2. Fan/Controls Clear of obstructions? | Y | X | N | ___ |
| 3. Repair needs? | Y | ___ | N | X |

A. Observations/comments:

Attach photographs as appropriate

B. Actions taken:

C. Recommended Maintenance/Repairs:

Notes:

Locations of suction risers can be found on attached Figure.

System details are included in Appendix B.

III. Piping/Penetrations

1. Is piping intact? (Y or N)
2. Are floor/wall penetrations sealed? (Y or N)

If 'No' to either of the above, provide observations and describe corrective actions taken

Do any of the pressure gages require repair or replacement?
If so, indicate locations, and actions taken:

Y ___ N X

IV. Building Modifications: Have building modifications been made that could affect the operation of the SSD System? (Describe)

NO changes at this time. (KJ)

Additional Comments:

Checked Condensation trap

Report all maintenance/repair needs immediately to building facility manager

Sub-Slab Depressurization System

Inspection Checklist

Syracuse Label, 110 Luther Avenue, Liverpool, NY

Date:

9-25-12

Inspector's Name:

Kevin Gannon

Company:

SYRLSP

Inspector Initials:

(KG)

I. Pressure Readings

Suction Riser Identification	Pressure Reading (inWC)
S-1	2.9
S-2	2.8
S-3	5.4
S-4	4.8
S-5	3.2
S-6	2.9
S-7	2.1
S-8	4.5
S-9	2.1
S-10	2.2
S-11	2.0
S-12	2.1
S-13	2.3
S-14	2.1

II. Fan Inspection

- | | | | | |
|--|---|-------------------------------------|---|-------------------------------------|
| 1. Operational? | Y | <input checked="" type="checkbox"/> | N | <input type="checkbox"/> |
| 2. Fan/Controls Clear of obstructions? | Y | <input checked="" type="checkbox"/> | N | <input type="checkbox"/> |
| 3. Repair needs? | Y | <input type="checkbox"/> | N | <input checked="" type="checkbox"/> |

A. Observations/comments:

Attach photographs as appropriate

Notes:

Locations of suction risers can be found on attached Figure.

System details are included in Appendix B.

III. Piping/Penetrations

1. Is piping intact? (Y or N)
2. Are floor/wall penetrations sealed? (Y or N)

If 'No' to either of the above, provide observations and describe corrective actions taken

B. Actions taken:

C. Recommended Maintenance/Repairs:

Do any of the pressure gages require repair or replacement?
If so, indicate locations, and actions taken:

Y ☐ N ☒

IV. Building Modifications: Have building modifications been made that could affect the operation of the SSD System? (Describe)

None at this time (KG)

Additional Comments:

Check Condensation trap - NO water (KG)

Report all maintenance/repair needs immediately to building facility manager

Sub-Slab Depressurization System

Inspection Checklist

Syracuse Label, 110 Luther Avenue, Liverpool, NY

Date:

10-26-12

Inspector's Name:

Kevin Gagnon

Company:

SYRCLSP

Inspector Initials:

KG

I. Pressure Readings

Suction Riser Identification	Pressure Reading (inWC)
S-1	4.2
S-2	2.9
S-3	5.6
S-4	4.9
S-5	3.3
S-6	3.0
S-7	2.1
S-8	4.6
S-9	2.1
S-10	2.4
S-11	2.4
S-12	2.4
S-13	2.6
S-14	2.3

II. Fan Inspection

- | | | | | |
|--|---|-------------------------------------|---|-------------------------------------|
| 1. Operational? | Y | <input checked="" type="checkbox"/> | N | <input type="checkbox"/> |
| 2. Fan/Controls Clear of obstructions? | Y | <input checked="" type="checkbox"/> | N | <input type="checkbox"/> |
| 3. Repair needs? | Y | <input type="checkbox"/> | N | <input checked="" type="checkbox"/> |

A. Observations/comments:

Attach photographs as appropriate

Notes:

Locations of suction risers can be found on attached Figure.

System details are included in Appendix B.

III. Piping/Penetrations

- Is piping intact? (Y or N)
- Are floor/wall penetrations sealed? (Y or N)

If 'No' to either of the above, provide observations and describe corrective actions taken

B. Actions taken:

C. Recommended Maintenance/Repairs:

Do any of the pressure gages require repair or replacement?
If so, indicate locations, and actions taken:

Y ☐ N ☒

IV. Building Modifications: Have building modifications been made that could affect the operation of the SSD System? (Describe)

None at this time (KG)

Additional Comments:

Checked condensation trap - nothing (KG)

Report all maintenance/repair needs immediately to building facility manager

Sub-Slab Depressurization System

Inspection Checklist

Syracuse Label, 110 Luther Avenue, Liverpool, NY

Date:

11-28-12

Inspector's Name:

Kevin Gagnon

Company:

SYRLSP

Inspector Initials:

KG

I. Pressure Readings

Suction Riser Identification	Pressure Reading (inWC)
S-1	4.2
S-2	3.0
S-3	5.5
S-4	4.9
S-5	3.3
S-6	3.0
S-7	2.1
S-8	4.6
S-9	2.1
S-10	2.6
S-11	2.4
S-12	2.4
S-13	2.6
S-14	2.3

II. Fan Inspection

- | | | | | |
|--|---|-----|---|-----|
| 1. Operational? | Y | X | N | ___ |
| 2. Fan/Controls Clear of obstructions? | Y | X | N | ___ |
| 3. Repair needs? | Y | ___ | N | X |

A. Observations/comments:

Attach photographs as appropriate

Notes:

Locations of suction risers can be found on attached Figure.

System details are included in Appendix B.

III. Piping/Penetrations

1. Is piping intact? (Y or N)
2. Are floor/wall penetrations sealed? (Y or N)

If 'No' to either of the above, provide observations and describe corrective actions taken

B. Actions taken:

C. Recommended Maintenance/Repairs:

Do any of the pressure gages require repair or replacement?
If so, indicate locations, and actions taken:

Y ___ N X

IV. Building Modifications: Have building modifications been made that could affect the operation of the SSD System? (Describe)

None at this time (KG)

Additional Comments:

Checked Condensation trap - Nothing (KG)

Report all maintenance/repair needs immediately to building facility manager

Sub-Slab Depressurization System

Inspection Checklist

Syracuse Label, 110 Luther Avenue, Liverpool, NY

Date:

12-28-12

Inspector's Name:

Kevin Gagnon

Company:

Syr/Sp

Inspector Initials:

(KG)

I. Pressure Readings

Suction Riser Identification	Pressure Reading (inWC)
S-1	3.4
S-2	3.0
S-3	5.7
S-4	5.0
S-5	5.7 3.4
S-6	3.0
S-7	2.1
S-8	4.7
S-9	2.3
S-10	3.0
S-11	2.9
S-12	3.0
S-13	3.2
S-14	2.9

II. Fan Inspection

1. Operational?	Y	X	N	___
2. Fan/Controls Clear of obstructions?	Y	X	N	___
3. Repair needs?	Y	___	N	X

A. Observations/comments:

Attach photographs as appropriate

Notes:

Locations of suction risers can be found on attached Figure.

System details are included in Appendix B.

III. Piping/Penetrations

1. Is piping intact? (Y or N)
2. Are floor/wall penetrations sealed? (Y or N)

If 'No' to either of the above, provide observations and describe corrective actions taken

B. Actions taken:

C. Recommended Maintenance/Repairs:

Do any of the pressure gages require repair or replacement?
If so, indicate locations, and actions taken:

Y ___ N X

IV. Building Modifications: Have building modifications been made that could affect the operation of the SSD System? (Describe)

None @ this time (KG)

Additional Comments:

Checked Condensation trap. - Nothing (KG)

Sub-Slab Depressurization System

Inspection Checklist

Syracuse Label, 110 Luther Avenue, Liverpool, NY

Date:

1/31/13

Inspector Name:

Kevin Gagnon

Company:

SYRLSP

Inspector Initials:

KG

I. Pressure Readings

Suction Riser Identification	Pressure Reading (inWC)
S-1	3.2
S-2	3.1
S-3	5.9
S-4	5.0
S-5	3.5
S-6	3.1
S-7	2.2
S-8	5.1
S-9	2.9
S-10	4.0
S-11	4.6
S-12	4.0
S-13	4.0
S-14	3.5

II. Fan Inspection

- | | | | | |
|--|---|-------------------------------------|---|-------------------------------------|
| 1. Operational? | Y | <input checked="" type="checkbox"/> | N | <input type="checkbox"/> |
| 2. Fan/Controls Clear of obstructions? | Y | <input checked="" type="checkbox"/> | N | <input type="checkbox"/> |
| 3. Repair needs? | Y | <input type="checkbox"/> | N | <input checked="" type="checkbox"/> |

A. Observations/comments:

Attach photographs as appropriate

Notes:

Locations of suction risers can be found on attached Figure.

System details are included in Appendix B.

III. Piping/Penetrations

- Is piping intact? (Y or N)
- Are floor/wall penetrations sealed? (Y or N)

If 'No' to either of the above, provide observations and describe corrective actions taken

B. Actions taken:

C. Recommended Maintenance/Repairs:

Do any of the pressure gages require repair or replacement?
If so, indicate locations, and actions taken:

Y ☐ N ☒

IV. Building Modifications: Have building modifications been made that could affect the operation of the SSD System? (Describe)

None at this time (KG)

Additional Comments:

Checked condensation trap - no water (KG)

Sub-Slab Depressurization System
Inspection Checklist
Syracuse Label, 110 Luther Avenue, Liverpool, NY

Date: 2/28/13
Inspector Name: Kevin Gayard
Company: SYRLSP
Inspector Initials: KG

I. Pressure Readings

Suction Riser Identification	Pressure Reading (inWC)
S-1	<u>3.6</u>
S-2	<u>3.4</u>
S-3	<u>6.2</u>
S-4	<u>5.5</u>
S-5	<u>4.1</u>
S-6	<u>3.6</u>
S-7	<u>2.5</u>
S-8	<u>6.0</u>
S-9	<u>4.5</u>
S-10	<u>4.5</u>
S-11	<u>4.1</u>
S-12	<u>4.2</u>
S-13	<u>4.5</u>
S-14	<u>4.2</u>

Notes:
Locations of suction risers can be found on attached Figure.
System details are included in Appendix B.

III. Piping/Penetrations

1. Is piping intact? (Y or N)
2. Are floor/wall penetrations sealed? (Y or N)

If 'No' to either of the above, provide observations and describe corrective actions taken

II. Fan Inspection

1. Operational?

Y X N —

2. Fan/Controls Clear of obstructions?

Y X N —

3. Repair needs?

Y — N X

A. Observations/comments:

Attach photographs as appropriate

B. Actions taken:

C. Recommended Maintenance/Repairs:

Y — N X

Do any of the pressure gages require repair or replacement?
If so, indicate locations, and actions taken:

IV. Building Modifications: Have building modifications been made that could affect the operation of the SSD System? (Describe)

None at this time

Comments:

water (KG)

Sub-Slab Depressurization System

Inspection Checklist

Syracuse Label, 110 Luther Avenue, Liverpool, NY

Date:

3/28/13

Inspector Name:

Kevin Gagnon

Company:

SVRLSP

Inspector Initials:

KG

I. Pressure Readings

Suction Riser Identification	Pressure Reading (inWC)
S-1	3.2
S-2	3.0
S-3	5.6
S-4	5.0
S-5	3.4
S-6	3.1
S-7	2.1
S-8	4.5
S-9	2.1
S-10	2.9
S-11	2.9
S-12	2.6
S-13	2.9
S-14	2.9

II. Fan Inspection

1. Operational?	Y	X	N	
2. Fan/Controls Clear of obstructions?	Y	X	N	
3. Repair needs?	Y		N	X

A. Observations/comments:

Attach photographs as appropriate

Notes:

Locations of suction risers can be found on attached Figure.

System details are included in Appendix B.

III. Piping/Penetrations

1. Is piping intact? (Y or N)
2. Are floor/wall penetrations sealed? (Y or N)

If 'No' to either of the above, provide observations and describe corrective actions taken

B. Actions taken:

C. Recommended Maintenance/Repairs:

Do any of the pressure gages require repair or replacement?
If so, indicate locations, and actions taken:

Y ___ N X

IV. Building Modifications: Have building modifications been made that could affect the operation of the SSD System? (Describe)

None at this time (KG)

Additional Comments:

opened condensation trap no water (KG)

Sub-Slab Depressurization System

Inspection Checklist

Syracuse Label, 110 Luther Avenue, Liverpool, NY

Date:

4/30/13

Inspector Name:

KG

Company:

SYRLSP

Inspector Initials:

KG

I. Pressure Readings

Suction Riser Identification	Pressure Reading (inWC)
S-1	3.1
S-2	3.0
S-3	5.5
S-4	5.0
S-5	3.4
S-6	3.1
S-7	2.1
S-8	4.5
S-9	2.1
S-10	2.5
S-11	2.4
S-12	2.4
S-13	2.6
S-14	2.5

II. Fan Inspection

- | | | | | |
|--|---|-------------------------------------|---|-------------------------------------|
| 1. Operational? | Y | <input checked="" type="checkbox"/> | N | <input type="checkbox"/> |
| 2. Fan/Controls Clear of obstructions? | Y | <input checked="" type="checkbox"/> | N | <input type="checkbox"/> |
| 3. Repair needs? | Y | <input type="checkbox"/> | N | <input checked="" type="checkbox"/> |

A. Observations/comments:

Attach photographs as appropriate

Notes:

Locations of suction risers can be found on attached Figure.

System details are included in Appendix B.

III. Piping/Penetrations

- Is piping intact? (Y or N) ☒ Y
- Are floor/wall penetrations sealed? (Y or N) ☒ Y

If 'No' to either of the above, provide observations and describe corrective actions taken

B. Actions taken:

C. Recommended Maintenance/Repairs:

Do any of the pressure gages require repair or replacement?

Y ☐ N ☒

If so, indicate locations, and actions taken:

IV. Building Modifications: Have building modifications been made that could affect the operation of the SSD System? (Describe)

None at this time - (NW-17 drilling) (KG)

Additional Comments:

Checked Condensation trap - NO water.

KG

Sub-Slab Depressurization System

Inspection Checklist

Syracuse Label, 110 Luther Avenue, Liverpool, NY

Date: 5/30/13
 Inspectors Name: Kevin Gagnon
 Company: SAC LSP
 Inspector Initials: (KG)

I. Pressure Readings

Suction Riser Identification	Pressure Reading (inWC)
S-1	<u>3.2</u>
S-2	<u>3.1</u>
S-3	<u>6.5</u>
S-4	<u>5.0</u>
S-5	<u>3.4</u>
S-6	<u>3.1</u>
S-7	<u>2.0</u>
S-8	<u>2.3 5.0</u>
S-9	<u>2.3</u>
S-10	<u>4.5</u>
S-11	<u>4.0</u>
S-12	<u>4.2</u>
S-13	<u>4.5</u>
S-14	<u>4.5</u>

II. Fan Inspection

- | | | | | |
|--|---|----------|---|----------|
| 1. Operational? | Y | <u>X</u> | N | ___ |
| 2. Fan/Controls Clear of obstructions? | Y | <u>X</u> | N | ___ |
| 3. Repair needs? | Y | ___ | N | <u>X</u> |

A. Observations/comments:

Attach photographs as appropriate

Notes:

Locations of suction risers can be found on attached Figure.

System details are included in Appendix B.

III. Piping/Penetrations

1. Is piping intact? (Y or N)
2. Are floor/wall penetrations sealed? (Y or N)

If 'No' to either of the above, provide observations and describe corrective actions taken

B. Actions taken:

C. Recommended Maintenance/Repairs:

Do any of the pressure gages require repair or replacement?
 If so, indicate locations, and actions taken:

Y ___ N X

IV. Building Modifications: Have building modifications been made that could affect the operation of the SSD System? (Describe)

NONE @ this time (mw 17 drilling)

(KG)

Additional Comments:

Checked Condensation trap - NO water

(KG)

Report all maintenance/repair needs immediately to building facility manager

Sub-Slab Depressurization System

Inspection Checklist

Syracuse Label, 110 Luther Avenue, Liverpool, NY

Date:

6/18/13

Inspector's Name:

Kevin Gaynor

Company:

Syr. Label Co

Inspector Initials:

KG

I. Pressure Readings

Suction Riser Identification	Pressure Reading (inWC)
S-1	3.4
S-2	3.2
S-3	5.8
S-4	5.1
S-5	3.6
S-6	3.2
S-7	2.2
S-8	5.0
S-9	2.5
S-10	4.5
S-11	4.2
S-12	4.5
S-13	4.5
S-14	4.5

II. Fan Inspection

- Operational? Y ☒ N ☐
- Fan/Controls Clear of obstructions? Y ☒ N ☐
- Repair needs? Y ☐ N ☒

A. Observations/comments:

Attach photographs as appropriate

B. Actions taken:

C. Recommended Maintenance/Repairs:

Notes:

Locations of suction risers can be found on attached Figure.

System details are included in Appendix B.

III. Piping/Penetrations

- Is piping intact? (Y or N) ☒
- Are floor/wall penetrations sealed? (Y or N) ☒

If 'No' to either of the above, provide observations and describe corrective actions taken

Do any of the pressure gages require repair or replacement?
If so, indicate locations, and actions taken:

Y ☐ N ☒

IV. Building Modifications: Have building modifications been made that could affect the operation of the SSD System? (Describe)

Still drilling in MW-17

Additional Comments:

Checked condensation trap - no water (KG)

Report all maintenance/repair needs immediately to building facility manager

Appendix D - Approval Notifications for EQulS Database Submittals

Ian McNamara

From: NYENVDATA <NYENVDATA@gw.dec.state.ny.us>
Sent: Monday, November 05, 2012 2:00 PM
To: Ian McNamara
Cc: Christopher Mannes
Subject: Re: BCP Site #C734118 Groundwater Sampling EDD's

Data Provider,

Thank you for your EDD submittals. NYSDEC has successfully uploaded the EDDs "20121003 1350.C734118.NYSDEC.zip" and "20121003 1353.C734118.NYSDEC.zip" and the data is ready for use.

Thank you,
Aaron
NYSDEC EIMS Team

>>> Ian McNamara <Ian.McNamara@ghd.com> 10/5/2012 10:32 AM >>>

Hi,
Attached are 2 EDD's for the above referenced site. These EDD's are for 3rd Quarter 2012 Groundwater Sampling activities.
Thanks,

Ian McNamara
Environmental Scientist

GHD

T: 1 315 314 5661 | M: 1 315 368 8432 | E: ian.mcnamara@ghd.com
301 Plainfield Road Suite 180 Syracuse New York 13212 USA | www.ghd.com
[WATER](#) | [ENERGY & RESOURCES](#) | [ENVIRONMENT](#) | [PROPERTY & BUILDINGS](#) | [TRANSPORTATION](#)

Please consider the environment before printing this email

This email and all attachments are confidential. For further important information about emails sent to or from GHD or if you have received this email in error, please refer to <http://www.ghd.com/emaildisclaimer.html> .

This e-mail has been scanned for viruses by MessageLabs.

This e-mail has been scanned for viruses by MessageLabs.

From: NYENVDATA <NYENVDATA@gw.dec.state.ny.us>
Sent: Thursday, November 08, 2012 2:56 PM
To: Ian McNamara
Cc: Christopher Mannes; Eric Hausamann
Subject: Re: 2nd Quarter 2012 Groundwater Monitoring EDD for BCP#C734118

Ian,

Thank you for your EDD submittals. NYSDEC has successfully uploaded the EDDs "20120718 1457.C734118.NYSDEC.zip" and "20120718 1502.C734118.NYSDEC.zip". The data is ready for use.

Thank you,
Aaron
NYSDEC EIMS Team

>>> <Ian.McNamara@ghd.com> 7/18/2012 3:06 PM >>>

Hi,
Attached are 2 EDDs for the above referenced Site. They are split into a field results and a sample results EDD. Please let me know if these need any edits to be acceptable.

Thanks,

Ian McNamara
Environmental Scientist

GHD

T: 1 315 314 5661 | M: 1 315 368 8432 | E: ian.mcnamara@ghd.com
301 Plainfield Road Suite 180 Syracuse New York 13212 USA | www.ghd.com

[WATER](#) | [ENERGY & RESOURCES](#) | [ENVIRONMENT](#) | [PROPERTY & BUILDINGS](#) | [TRANSPORTATION](#)

Please consider the environment before printing this email

This email and all attachments are confidential. For further important information about emails sent to or from GHD or if you have received this email in error, please refer to <http://www.ghd.com/emaildisclaimer.html> .

This e-mail has been scanned for viruses by MessageLabs.

This e-mail has been scanned for viruses by MessageLabs.

Ian McNamara

From: NYENVDATA <NYENVDATA@gw.dec.state.ny.us>
Sent: Monday, January 28, 2013 12:12 PM
To: Ian McNamara
Cc: Christopher Mannes
Subject: RE: BCP Site #C734118 Groundwater Sampling EDD's

Ian,

Thank you for your EDD resubmission. NYSDEC has successfully uploaded the EDD "20130122 1412.C734118.NYSDEC.zip" and the data is ready for use.

Aaron
NYSDEC EIMS Team

>>> Ian McNamara <Ian.McNamara@ghd.com> 1/22/2013 2:22 PM >>>
Hi,

Attached is the revised EDD with the additional sample locations.

Your proposed solutions to the 2 issues outlined below are acceptable to me. Is there anything that I need to do to allow for these solutions, such as fixing them in my EDDs and resubmitting?

Thanks,

Ian McNamara
Environmental Scientist

Please note my new telephone (T) number and address.

GHD

T: 1 315 679 5732 | M: 1 315 368 8432 | V: 865732 | E: ian.mcnamara@ghd.com
One Remington Park Drive Cazenovia New York 13035 USA | www.ghd.com
[WATER](#) | [ENERGY & RESOURCES](#) | [ENVIRONMENT](#) | [PROPERTY & BUILDINGS](#) | [TRANSPORTATION](#)

Please consider the environment before printing this email

From: NYENVDATA [mailto:NYENVDATA@gw.dec.state.ny.us]
Sent: Tuesday, January 22, 2013 1:48 PM
To: Ian McNamara
Cc: Christopher Mannes
Subject: Re: BCP Site #C734118 Groundwater Sampling EDD's

Ian,

NYSDEC has encountered some errors while reviewing your data packages "20130110 1035.C734118.NYSDEC.zip" and "20130110 1036.C734118.NYSDEC.zip" with the EQUiS Data Processor application available here:

<http://www.earthsoft.com/products/edp/edp-format-for-nysdec/> to all data providers. These errors include:

- Missing Locations: The WaterLevel table refers to the following locations which have not been loaded into the database with previous EDDs: 'MW-14' 'MW-15' 'MW-16' 'MW-3' and 'MW-5'. Please provide a location table with the location data for these locations with your resubmission. To avoid error messages, you may choose to include all locations referenced by the WaterLevel table, but if you choose to include only the locations referenced above, we can provide the rest of the location data.

Please review these errors and resubmit your EDD for upload into the NYSDEC database. Please do not hesitate to contact us with any questions. Also, for future reference, here is the link for the updated EDD Manual:

http://www.dec.ny.gov/docs/remediation_hudson_pdf/eddmanual.pdf, and the link for the main EDD instruction page:
<http://www.dec.ny.gov/chemical/62440.html>.

In addition to reviewing the currently submitted EDDs, the EIMS team is also responsible for conducting reviews of the overall data, within the EQuIS database, for each facility. This is to ensure that the data previously loaded into the system is indeed correct and is able to properly generate reports.

In reviewing the facility C734118 we have noticed some QAQC items that may need some more attention before we load any future data. Below, please find a list of the issues we are finding as well as how we would like to resolve them.

1. Issue 1: The Sample Name field is inconsistently populated in our database.
 - Solution: Where the Sample Name field is unpopulated, we would populate it with the sys loc code.
2. Issue 2: The Column Number field is inconsistently populated in the database
 - Solution: Where the Column Number is unpopulated from previous EDD submissions, we would populate the field with the value 'NA'.

We would really appreciate discussing these changes with you, but if you agree with these proposed corrections and have no further concerns, please let us know and we will move forward on these changes. Thank you so much for your time and cooperation throughout this process.

Sincerely,
Aaron
NYSDEC EIMS Team

>>> Ian McNamara <Ian.McNamara@ghd.com> 1/10/2013 10:40 AM >>>

Hi,
Attached are 2 EDD's for the above referenced site. These EDD's are for 4th Quarter 2012 Groundwater Sampling activities.
Thanks,

Ian McNamara
Environmental Scientist

Please note my new telephone (T) number and address.

GHD

T: 1 315 679 5732 | M: 1 315 368 8432 | V: 865732 | E: ian.mcnamara@ghd.com
One Remington Park Drive Cazenovia New York 13035 USA | www.ghd.com
[WATER](#) | [ENERGY & RESOURCES](#) | [ENVIRONMENT](#) | [PROPERTY & BUILDINGS](#) | [TRANSPORTATION](#)

Please consider the environment before printing this email

This email and all attachments are confidential. For further important information about emails sent to or from GHD or if you have received this email in error, please refer to <http://www.ghd.com/emaildisclaimer.html> .

This e-mail has been scanned for viruses by MessageLabs.

This e-mail has been scanned for viruses by MessageLabs.

This email and all attachments are confidential. For further important information about emails sent to or from GHD or if you have received this email in error, please refer to <http://www.ghd.com/emaildisclaimer.html> .

This e-mail has been scanned for viruses by MessageLabs.

Ian McNamara

From: NYENVDATA <NYENVDATA@gw.dec.state.ny.us>
Sent: Thursday, March 21, 2013 1:53 PM
To: Ian McNamara
Cc: Christopher Mannes
Subject: Re: BCP #C734118 EDDs Resubmitted due to QAQC issues identified by EIMS Team

Ian, Chris,

We of the EIMS Team actually expected to be contacted by the PM before we all worked to resolve the issues present in the database.

The EDD review process has evolved over time, and NYSDEC decided in the fall that the database's information should, where possible, match the quality standards we hold for incoming EDDs. We proposed solutions for each of the issues associated with the 110 Luther Ave. Site – none of our proposed solutions, in the e-mail you both read, necessarily required a resubmission of EDDs. That said, we appreciate the lengths you went to in order to produce these resubmissions, especially as they appear to be in line with our present QC standards. The only issue your EDDs do not address is that of the Location Name field in the DT_LOCATION table. We have taken this thread, from us, to the PM, to you, and back to us, as confirmation that we should populate the loc name fields in the database with the values from the sys loc code fields.

As I noted above, the EDDs are in line with our present QC standards, and have therefore been successfully loaded. The data from the EDDs "20130305 1323.C734118.NYSDEC.zip" "20130305 1451.C734118.NYSDEC.zip" "20130305 1505.C734118.NYSDEC.zip" "20130305 1556.C734118.NYSDEC.zip" "20130305 1606.C734118.NYSDEC.zip" and "20130305 1646.C734118.NYSDEC.zip" have been successfully loaded and have replaced related data in the database. The data is ready for use.

Thank you,
Aaron
NYSDEC EIMS Team

>>> Ian McNamara <Ian.McNamara@ghd.com> 3/5/2013 4:59 PM >>>
Hi,

Attached are the EDD's that are being resubmitted with the additional information requested in an e-mail forwarded to me from Chris Mannes on Thursday February 21, 2013.

The e-mail had a subject line of *110 Luther Ave. Site, C734118* and consisted of QAQC issues identified by the EIMS team. These issues were updated on the attached EDD's. The attached EDD's are the only ones provided by GHD that had errors. Any other EDD's submitted for this site were submitted by another consultant.

I am assuming that this information was not required in the initial EDD's since they were uploaded and ready for use when I initially submitted them. Could you please provide me with an explanation as to why the additional information is required for historically submitted EDD's? Our client is going to question why we are billing additional time to something that was thought to already be completed.

Please let me know if you need anything else.

Thanks,
Ian McNamara
Environmental Scientist

Please note my new telephone (T) number and address.

GHD

T: 1 315 679 5732 | M: 1 315 368 8432 | V: 865732 | E: ian.mcnamara@ghd.com

One Remington Park Drive Cazenovia New York 13035 USA | www.ghd.com

[WATER](#) | [ENERGY & RESOURCES](#) | [ENVIRONMENT](#) | [PROPERTY & BUILDINGS](#) | [TRANSPORTATION](#)

Please consider the environment before printing this email

This email and all attachments are confidential. For further important information about emails sent to or from GHD or if you have received this email in error, please refer to <http://www.ghd.com/emaildisclaimer.html> .

This e-mail has been scanned for viruses by MessageLabs.

This e-mail has been scanned for viruses by MessageLabs.

From: NYENVDATA <NYENVDATA@gw.dec.state.ny.us>
Sent: Thursday, June 27, 2013 5:26 PM
To: Ian McNamara
Cc: Christopher Mannes
Subject: Re: EDD's for BCP Site #C734118

Ian,

First, thank you for dividing the EDDs by section. Because of this step, we were able to successfully load the EDD "20130624 1516.C734118.NYSDEC.zip" with the FieldActivities section. That data is in the database and ready for use.

However, there were some issues with the EDD "20130624 1514.C734118.NYSDEC.zip" which, while they do not arise as errors in EDP, will create problems during the reporting process. These items include:

- Sample Type Codes: The sample type codes for samples must reflect their nature. The sample types for the samples DUPLICATE_03/28/13, TRIP BLANK_03/28/13, and TRIP BLANK_03/29/13 must be revised. These are not normal samples, they are duplicate and trip blank samples, therefore their sample types should be revised to FD for 'Field Duplicate', and TB for Trip Blank. Moreover, The location code references for these samples are unnecessary – which is handy, because we are obliged to reject location data for location codes like 'DUPLICATE' or 'TRIP BLANK' in the first place.

Because of the above issues, we are unable to load the data into the database. Please review these errors, revise the EDD, check it in EDP, and resubmit your EDD for upload into the NYSDEC database. Please do not hesitate to contact us with any questions. Also, for future reference, here is the link for the updated EDD Manual:

http://www.dec.ny.gov/docs/remediation_hudson_pdf/eddmanual.pdf, and the link for the main EDD instruction page: <http://www.dec.ny.gov/chemical/62440.html>.

Thank you,
Aaron
NYSDEC EIMS Team

>>> Ian McNamara <Ian.McNamara@ghd.com> 6/24/2013 4:54 PM >>>

Hello,

The attached files are EDD's related to 1st Quarter 2013 sampling conducted at the 110 Luther Avenue BCP Site (BCP Site #C734118).

Please let me know if they need any edits.

Thanks,

Ian

Ian McNamara
Environmental Scientist

Please note my new telephone (T) number and address.

GHD

T: 1 315 679 5732 | M: 1 315 368 8432 | V: 865732 | E: ian.mcnamara@ghd.com
One Remington Park Drive Cazenovia New York 13035 USA | www.ghd.com
[WATER](#) | [ENERGY & RESOURCES](#) | [ENVIRONMENT](#) | [PROPERTY & BUILDINGS](#) | [TRANSPORTATION](#)

Please consider the environment before printing this email

This email and all attachments are confidential. For further important information about emails sent to or from GHD or if

you have received this email in error, please refer to <http://www.ghd.com/emaildisclaimer.html> .

This e-mail has been scanned for viruses by MessageLabs.

This e-mail has been scanned for viruses by MessageLabs.

Ian McNamara

From: NYENVDATA <NYENVDATA@gw.dec.state.ny.us>
Sent: Tuesday, July 09, 2013 1:13 PM
To: Ian McNamara
Cc: Christopher Mannes
Subject: RE: EDD's for BCP Site #C734118

CompleteRepository: 861494104
Description: Syracuse Label 2013 Groundwater Monitoring
JobNo: 14941
OperatingCentre: 86
RepoEmail: 8614941@ghd.com
RepoType: Job
SubJob: 04

Ian,

Thank you for your EDD submission. NYSDEC has successfully uploaded the EDD "20130701 1506.C734118.NYSDEC.zip" and the data is ready for use.

Aaron
NYSDEC EIMS Team

>>> Ian McNamara <Ian.McNamara@ghd.com> 7/1/2013 3:08 PM >>>

Hello,

Attached is the revised EDD for BCP Site #C734118. Please let me know if there are any other issues.

Thanks,

Ian

Ian McNamara
Environmental Scientist

Please note my new telephone (T) number and address.

GHD

T: 1 315 679 5732 | M: 1 315 368 8432 | V: 865732 | E: ian.mcnamara@ghd.com

One Remington Park Drive Cazenovia New York 13035 USA | www.ghd.com

[WATER](#) | [ENERGY & RESOURCES](#) | [ENVIRONMENT](#) | [PROPERTY & BUILDINGS](#) | [TRANSPORTATION](#)

Please consider the environment before printing this email

From: NYENVDATA [<mailto:NYENVDATA@gw.dec.state.ny.us>]

Sent: Thursday, June 27, 2013 5:26 PM

To: Ian McNamara

Cc: Christopher Mannes

Subject: Re: EDD's for BCP Site #C734118

Ian,

First, thank you for dividing the EDDs by section. Because of this step, we were able to successfully load the EDD "20130624 1516.C734118.NYSDEC.zip" with the FieldActivities section. That data is in the database and ready for use.

However, there were some issues with the EDD "20130624 1514.C734118.NYSDEC.zip" which, while they do not arise as errors in EDP, will create problems during the reporting process. These items include:

- Sample Type Codes: The sample type codes for samples must reflect their nature. The sample types for the samples DUPLICATE_03/28/13, TRIP BLANK_03/28/13, and TRIP BLANK_03/29/13 must be revised. These are not normal samples, they are duplicate and trip blank samples, therefore their sample types should be revised to FD for 'Field Duplicate', and TB for Trip Blank. Moreover, The location code references for these samples are unnecessary – which is handy, because we are obliged to reject location data for location codes like 'DUPLICATE' or 'TRIP BLANK' in the first place.

Because of the above issues, we are unable to load the data into the database. Please review these errors, revise the EDD, check it in EDP, and resubmit your EDD for upload into the NYSDEC database. Please do not hesitate to contact us with any questions. Also, for future reference, here is the link for the updated EDD Manual:

http://www.dec.ny.gov/docs/remediation_hudson_pdf/eddmanual.pdf, and the link for the main EDD instruction page: <http://www.dec.ny.gov/chemical/62440.html>.

Thank you,
Aaron
NYSDEC EIMS Team

>>> Ian McNamara <Ian.McNamara@ghd.com> 6/24/2013 4:54 PM >>>

Hello,

The attached files are EDD's related to 1st Quarter 2013 sampling conducted at the 110 Luther Avenue BCP Site (BCP Site #C734118).

Please let me know if they need any edits.

Thanks,
Ian

Ian McNamara
Environmental Scientist

Please note my new telephone (T) number and address.

GHD

T: 1 315 679 5732 | M: 1 315 368 8432 | V: 865732 | E: ian.mcnamara@ghd.com

One Remington Park Drive Cazenovia New York 13035 USA | www.ghd.com

[WATER](#) | [ENERGY & RESOURCES](#) | [ENVIRONMENT](#) | [PROPERTY & BUILDINGS](#) | [TRANSPORTATION](#)

Please consider the environment before printing this email

This email and all attachments are confidential. For further important information about emails sent to or from GHD or if you have received this email in error, please refer to <http://www.ghd.com/emaildisclaimer.html> .

This e-mail has been scanned for viruses by MessageLabs.

This e-mail has been scanned for viruses by MessageLabs.

This email and all attachments are confidential. For further important information about emails sent to or from GHD or if you have received this email in error, please refer to <http://www.ghd.com/emaildisclaimer.html> .

This e-mail has been scanned for viruses by MessageLabs.

This e-mail has been scanned for viruses by MessageLabs.

www.ghd.com

